# CONSTRUCTION COMPLETION REPORT
# SA-6 SOUTH CHROMIUM REMEDY

STUDY AREA 6 SOUTH
NJDEP SITES 073, 124, 125, 134, 140, AND 163

JERSEY CITY, NEW JERSEY

*Prepared for*

Honeywell

115 Tabor Road
Morris Plains, New Jersey 07950

*Prepared by:*

Amec Foster Wheeler Environment & Infrastructure, Inc.
200 American Metro Boulevard, Suite 113
Hamilton, New Jersey 08619
Project No. 3480160515

**OCTOBER 2017**

# TABLE OF CONTENTS

EXECUTIVE SUMMARY ..... VIII
1.0 INTRODUCTION ..... 1
1.1 Purpose and Scope ..... 1
1.2 Site Setting and Site History ..... 5
1.3 Project Background and Land Development ..... 7
1.4 Contaminants of Concern and Remedial Action Objectives ..... 10
1.5 Construction Overview ..... 13
1.6 Data Validation and Data Usability Evaluation ..... 18
1.7 Report Organization ..... 20
2.0 PREPARATORY CONSTRUCTION ACTIVITIES ..... 22
2.1 Mobilization and Site Preparation ..... 22
2.2 Health and Safety ..... 23
2.3 Background and Baseline Perimeter Air Monitoring ..... 24
2.4 Site Security ..... 25
2.5 Support Facilities and Temporary Site Utilities ..... 25
2.6 Traffic Control ..... 26
2.7 Demolition ..... 26
2.8 Utility Abandonment ..... 27
2.9 Groundwater Testing for pH ..... 27
2.10 Waste Classification ..... 28
3.0 MODIFICATIONS AND FIELD CHANGES TO SA-6 SOUTH 100% DESIGN REPORT ..... 29
4.0 DEFERRED AREAS ..... 30
5.0 UNANTICIPATED ITEMS ENCOUNTERED DURING REMEDIAL ACTIVITIES ..... 33
5.1 Concrete Building Slabs, Foundations, Arsenic-Impacted Asphalt, Debris ..... 33
5.2 Hydrocarbon-Impacted Soil at SA-6 South ..... 34
5.3 USTs Encountered at Site 134 at SA-6 South ..... 35
5.4 Stratum D Repair ..... 36
5.5 Additional Sampling Conducted ..... 37
5.5.1 Quarterly Groundwater Sampling ..... 37
5.5.2 Verification Sampling at Site 073 Bulkhead Deferred Area ..... 39

6.0 DEWATERING AND CONSTRUCTION WATER TREATMENT ..... 41
6.1 General ..... 41
6.2 Excavation Dewatering/Pumping ..... 41
6.2.1 Well Installation ..... 41
6.2.2 SA-6 South Dewatering/Pumping System ..... 43
6.3 Construction Water Treatment Plant ..... 44
6.4 Groundwater Level and Baseline Gradient Monitoring ..... 45
7.0 MONITORING WELL ABANDONMENT AND INSTALLATION ..... 48
8.0 EXCAVATION ..... 50
8.1 Temporary Excavation Support ..... 50
8.2 Excavated Soil Management ..... 51
8.3 Excavation Sequencing and Schedule ..... 53
8.4 Excavated Material (Stockpile) Testing ..... 55
8.5 Excavation Extent Surveying and Excavation Completion Confirmation ..... 56
8.6 Anomalous Material Sampling ..... 58
8.7 Anomalous Material at Site 125 Under 60 Kellogg Street Building Slab ..... 60
8.8 Offsite Transportation and Disposal ..... 61
9.0 EXCAVATION BACKFILLING, BACKFILL COMPACTION, AND BACKFILL COMPACTION TESTING ..... 64
9.1 Backfill Sources ..... 64
9.2 Backfill Testing ..... 65
9.3 Concrete Testing ..... 66
9.4 Backfilling and Compaction ..... 67
9.5 In-Place Backfill Density Testing ..... 68
10.0 CONTAINMENT SYSTEM CONSTRUCTION ..... 69
10.1 Hydraulic Barrier Installation ..... 69
10.2 Vibration Monitoring ..... 71
10.3 Consolidation of Soils in Open Space AOC ..... 72
10.4 Contingent Groundwater Extraction System Construction ..... 73
10.5 Surcharge Program ..... 74
10.6 Cap Construction ..... 76
11.0 PERIMETER AIR MONITORING ..... 82
12.0 IN-SITU TREATMENT ..... 84
13.0 GWTP RELOCATION AND CONSTRUCTION ..... 86
14.0 SITE RESTORATION ..... 88

15.0 CONSTRUCTION PERMITS ..... 89
16.0 SUSTAINABILITY EFFORTS DURING CONSTRUCTION ..... 91
17.0 POST-REMEDY OPERATION & MAINTENANCE ..... 92
18.0 INSTITUTIONAL CONTROLS ..... 94
18.1 Deed Notices ..... 94
18.2 Soil Remedial Action Permits ..... 94
18.3 Groundwater Remedial Action Permits ..... 95
18.4 Classification Exception Area ..... 95
18.5 Conservation Restrictions ..... 95
19.0 RECORD DRAWINGS ..... 97
20.0 REMEDIAL ACTION COSTS ..... 98
20.1 Financial Assurances ..... 98
21.0 REMEDIATION CLOSE OUT SUMMARY ..... 99
22.0 REFERENCES ..... 101
23.0 LIST OF ACRONYMS AND ABBREVIATIONS ..... 103

**ILLUSTRATIONS**

Illustration 1: SA-6, SA-7, and Surrounding Area ..... 8
Illustration 2: Bayside Redevelopment Area ..... 9
Illustration 3: SA-6 South Chromium Remedy and Redevelopment Plans ..... 10
Illustration 4: Surcharge Loading Plan ..... 75

**TABLES**

Table 1A: Baseline PAMP Data
Table 1B: PAMP Data
Table 2A: Stockpile Soil Results (<20 mg/kg Hexavalent Chromium)
Table 2B: Stockpile Soil Results (>1000 mg/kg Hexavalent Chromium)
Table 3A: CWTP Effluent Results – VOCs
Table 3B: CWTP Effluent Results – Metals
Table 3C: CWTP Effluent Results – General Chemistry
Table 4: Baseline Groundwater Elevation Monitoring
Table 5: Shallow Monitoring Well List
Table 6A: Expanded Excavation Site 134 Soil Sample Results
Table 6B: Post-Excavation Anomalous Soil Sample Results
Table 6C: Site 073 Deferred Area Soil Sample Results
Table 6D: Site 125 Post-Excavation Soil Results
Table 7A: Concrete Sample Results – VOCs

Table 7B: Concrete Sample Results – SVOCs
Table 7C: Concrete Sample Results – Metals
Table 7D: Concrete Sample Results – Pesticides and PCBs
Table 7E: Concrete Sample Results – EPH/Petroleum Hydrocarbons
Table 7F: Concrete Sample Results – General Chemistry
Table 7G: Concrete Sample Results – TCLP
Table 7H: Concrete Sample Results – SPLP
Table 8: Site 163 In-Situ Soil Samples
Table 9: Stockpile Tracking Table
Table 10 Chromium Remedy Elements Referenced to Previous Relevant Documents

**FIGURES**

Figure 1: Site Location Map
Figure 2: Site Layout Map
Figure 3: SA-6 Project Team Organization Chart
Figure 4: Perimeter Air Monitoring Station Locations
Figure 5: Truck Route Map
Figure 6: Groundwater Sample Results (pH)
Figure 7A: Waste Classification Sample Locations Chromium Sampling Interval 1
Figure 7B: Waste Classification Sample Locations Chromium Sampling Interval 2
Figure 7C: Waste Classification Sample Locations Chromium Sampling Interval 3
Figure 7D: Waste Classification Sample Locations Chromium Sampling Interval 4
Figure 7E: Waste Classification Sample Locations Chromium Sampling Interval 5
Figure 7F: Waste Classification Sample Locations Chromium Sampling Interval 6
Figure 7G: Waste Classification Sample Locations Chromium Sampling Interval 7
Figure 8A: Site 073 Deferred Area Soil Boring Locations
Figure 8B: Post-Excavation Sample Locations 60 Kellogg
Figure 9: Construction Water Treatment System Layout
Figure 10: Shallow Monitoring Well Locations

Figure 11: Additional Post-Excavation Sidewall Sample Locations
Figure 12: Site 134 Expanded Excavation
Figure 13: Site 073 Impacted Concrete Area of Excavation Expansion
Figure 14: Vibration Monitoring
Figure 15: Chromium Remedy Components
Figure 16: Cap System Detail
Figure 17: Utility Corridors
Figure 18: Site 163 Deep Excavation Locations
Figure 19: Deed Notice Restricted Areas

**APPENDICES**

Appendix A: Representative Photographs
Appendix B: Electronic Data Deliverable Submittal Confirmation
Appendix C: Record Drawings and Final Documentation (CD only)
Appendix D: Design Change Bulletin Log
Appendix E: Monitoring Well Installation/ Records/Form B's (CD only)
Appendix F: Monitoring Well Abandonment Reports (CD only)
Appendix G: Previous Groundwater Sampling Results
Appendix H: Boring Logs (CD only)
Appendix I: Dewatering Logs
Appendix J: Items Encountered During Remedial Actions
Appendix K: Disposal Manifests (CD only)
Appendix L: Backfill Documentation
Appendix M: Compaction Tests
Appendix N: Sheetpile Documentation
Appendix O: Vibration Monitoring (CD only)
Appendix P: Surcharge Report (CD only)
Appendix Q: Cap Geosynthetic Quality Assurance Report (CD only)
Appendix R: Draft Deed Notice Documents (CD only)
Appendix S: Additional Documents (CD only)
Part 1 of 25

- Groundwater Memo 11/07/2016
- 2013 Monthly Reports
- 2014 Monthly Reports Part 1

Part 2 of 25
- 2014 Monthly Reports Part 2

Part 3 of 25
- 2014 Monthly Reports Part 3

Part 4 of 25
- 2014 Monthly Reports Part 4

Part 5 of 25
- 2014 Monthly Reports Part 5

Part 6 of 25
- 2014 Monthly Reports Part 6

Part 7 of 25
- 2014 Monthly Reports Part 7

Part 8 of 25
- 2015 Monthly Reports Part 1

Part 9 of 25
- 2015 Monthly Reports Part 2

Part 10 of 25
- 2015 Monthly Reports Part 3

Part 11 of 25
- 2015 Monthly Reports Part 4

Part 12 of 25
- 2016 Monthly Reports Part 1

Part 13 of 25
- 2016 Monthly Reports Part 2

Part 14 of 25
- 2016 Monthly Reports Part 3

Part 15 of 25
- 2016 Monthly Reports Part 4

Part 16 of 25
- DCBs Applicable to SA-6 South Part 1 (DCB 001 and 003-007.5)

Part 17 of 25
- DCBs Applicable to SA-6 South Part 2 (DCB 008.1 and 009)

Part 18 of 25
- DCBs Applicable to SA-6 South Part 3 (DCB 010-032)

Part 19 of 25
- DCBs Applicable to SA-6 South Part 4 (DCB 034-060)

Part 20 of 25
- Initial Declaration #1

Part 21 of 25
- Declaration #2 Part 1
- Attachments A – F (Part 1)

Part 22 of 25
- Declaration #2 Part 2
- Attachments F (Part 2) – I

Part 23 of 25
- Declaration #5 Part 1
- Attachments A – P (Part 1)

Part 24 of 25
- Declaration #5 Part 2
- Attachments P (Part 2) – Q

Part 25 of 25
- Excavation Certification E-Mails

# EXECUTIVE SUMMARY

Honeywell is submitting this Construction Completion Report (CCR) pursuant to the First Amended Consent Decree Regarding the Remediation and Redevelopment of Study Area 6 South, ECF No. 434, entered by the United States District Court, District of New Jersey on August 2, 2012, in Civil No. 05-05955, later consolidated with Civ. No. 95-2097 ("SA-6 South Consent Decree") in order to document the Chromium Remedy implemented to address chromium-impacted soil site-wide and groundwater for the Open Space Area of Concern (AOC) at Study Area 6 South ("SA-6 South"), located in Jersey City, Hudson County, New Jersey. The remedial activities were initiated in March 2013 and were completed in November 2016. A Remedial Action Report (RAR) was prepared by Honeywell and submitted to New Jersey Department of Environmental Protection (NJDEP). NJDEP approved the RAR on March 30, 2017.

The Chromium Remedy was implemented successfully in accordance with the following:

- NJDEP-approved Remedial Action Work Plans;
- SA-6 South Consent Decree, the SA-6 South 100% Design Report and Design Change Bulletins;
- NJDEP's Technical Requirements for Site Remediation; and
- NJDEP's Administrative Requirements for the Remediation of Contaminated Sites.

SA-6 South encompasses approximately 25 acres along Kellogg Street between Route 440 and the Hackensack River. For this CCR, the contaminant of concern (COC) in soils at SA-6 South is hexavalent chromium and the COC for shallow groundwater is total chromium per the NJDEP-approved RAWPs. Deep overburden and bedrock groundwater zones are being addressed by the Study Area 7 (SA-7) regional groundwater remedy. SA-6 South consists of three AOCs, as shown on **Figure 19**, with respect to chromium:

- Kellogg Street Development AOC;

- Site 163 Development AOC[1]; and
- Open Space AOC.

The Remedial Action Objectives (RAOs) established in the NJDEP-approved RAWPs for the SA-6 South AOCs are as follows:

The RAOs for soils include:

- Prevent exposure to chromium-impacted soils[2] containing hexavalent chromium above the NJDEP soil criteria of 20 milligrams per kilogram (mg/kg) to a depth of 20 feet, consistent with NJDEP policy.
- Remove and consolidate chromium-impacted soils that may be disturbed by future Site redevelopment activities; and reuse soils beneath area to be capped, to the extent feasible.
- Coordinate remedial actions for chromium with remedial actions for non-chromium contaminants and Site redevelopment, to the extent feasible.

RAOs for groundwater include:

- Mitigate the potential for surface water infiltration and leaching of contaminants (total and hexavalent chromium) from fill soils (vadose zone) to groundwater.

---

[1] The Site 163 Development AOC is comprised of two areas, the Deed Notice Area and the Non-Deed Notice Area. The remediation differed in the two areas of the Site 163 Development AOC. In the Deed Notice Area, chromium-impacted soils were excavated only to 4 feet below ground surface (bgs), leaving chromium-impacted soils at concentrations exceeding 20 mg/kg deeper than 4 feet bgs in place. The Deed Notice Area will be subject to a deed notice and conservation restriction, like the Open Space AOC. Residential development is prohibited in the Deed Notice Area. In the Non-Deed Notice Area, chromium-impacted soils at concentrations exceeding 20 mg/kg were excavated to a depth of 20 feet bgs or to the meadow mat, as discussed in Section 8.

[2] Throughout this CCR reference to chromium-impacted soils shall mean soils containing hexavalent chromium above the NJDEP soil criteria of 20 mg/kg and reference to chromium-impacted groundwater shall mean groundwater with total chromium above the NJDEP groundwater standard of 70 µg/L.

- Mitigate offsite migration of chromium in groundwater above the NJDEP Groundwater Quality Standard (GWQS). ).[3]
- Reduce chromium concentrations in groundwater.
- Prevent exposure to groundwater chromium concentrations above the NJDEP GWQS.

Remediation was completed across SA-6 South in order to meet the RAOs, with the exception of two areas where remediation has been deferred ("Deferred Areas") as shown on **Figure 19**:

- Bulkhead area along the western perimeter of SA-6 South ("Site 073 Bulkhead Deferred Area"); and
- Route 440 right-of-way along part of the eastern perimeter of SA-6 South ("Route 440 ROW Deferred Area").

Therefore, other than remediation in the identified Deferred Areas, no further remedial actions are required for SA-6 South other than actions to support the long-term maintenance and operation requirements for shallow groundwater and the deed noticed areas where chromium-impacted soils remain, including the Open Space AOC and the Site 163 Development AOC Deed Notice Area. Remediation of the Deferred Areas will be coordinated with the Bayfront Redevelopment Project and the widening of Route 440.

Major activities associated with the Chromium Remedy included:

- Excavation and offsite disposal of approximately 22,400 cubic yards (CYs) of chromium-impacted soil from the Kellogg Street Development AOC and the Site 163 Development AOC Non-Deed Notice Area;

[3] The SA 6 South Consent Decree requires Honeywell to isolate shallow groundwater and to intercept and treat shallow groundwater flowing above the meadow mat in the Open Space AOC to the extent that such groundwater contains total chromium in concentrations in excess of 70 µg/l. The Study Area 6 South Consent Decree also requires Honeywell to maintain an outward gradient of shallow groundwater from Study Area 7.

- Excavation and offsite disposal of approximately 23,000 CYs of petroleum-impacted soil co-mingled with chromium-impacted soil from the Kellogg Street Development AOC;
- Excavation of approximately 59,000 CYs of chromium-impacted soil from the Kellogg Street Development AOC and the Site 163 Development AOC (referred to together as "Development AOCs") and consolidation of this material in the Open Space AOC;
- Reuse of approximately 46,000 CYs of confirmed non-chromium-impacted historic fill soils as backfill in excavations;
- Placement of approximately 217,000 CYs of clean fill material as supplemental backfill in excavations;
- Surcharging of the Open Space AOC to consolidate underlying compressible strata;
- Construction of approximately 2,586 feet of hydraulic barrier around the Open Space AOC;
- Construction of an approximately 8-acre Resource Conservation and Recovery Act (RCRA) cap in the Open Space AOC; and
- Construction of a 1,700-foot long contingent groundwater extraction system within the Open Space AOC.

Prior to and during the development of the 100% Design, Pre-Design Investigation (PDI) sampling and analytical activities were completed to delineate the lateral and vertical limits of hexavalent chromium concentrations to 20 mg/kg in soils at SA-6 South. The PDI samples were considered post-excavation equivalent samples that precluded the need for collection of traditional post-excavation confirmatory samples at the completion of excavation activities for most of the site. Additional post-excavation sampling was required to confirm excavation limits upon encountering isolated incidences of anomalous material under the office portion of the 60 Kellogg Street building south of the 20 mg/kg line delineated during the PDI, and along isolated locations of excavation sidewalls or bottoms at Sites 073, 125, 134, and 140 as documented in Section 8.6. Other than these instances, the PDI allowed the remedial action to be more definitively designed and implemented in the field and is a process that has been accepted by the NJDEP in the RAWP and has been implemented successfully by Honeywell at other sites. The results of the PDI are

contained in Appendix A, Pre-Design Investigation Summary Report (PDI Report), of the SA-6 South Chromium Remedy 100% Design Report.

In addition, pursuant to the SA-6 South 100% Design Report, an in-situ treatment program involving injections of a chemical reductant was conducted within the Site 163 Development AOC to treat chromium-impacted soils at isolated locations. The in-situ injections were ineffective in achieving hexavalent chromium detections of <20 mg/kg at all depths. As a result, full excavation of chromium-impacted soils was conducted in the Site 163 Development AOC Non-Deed Notice Area. In the Site 163 Development AOC Deed Notice Area, chromium-impacted soils were excavated to a depth of 4 feet bgs, and chromium-impacted soils at a depth below 4 feet bgs were left in place and capped with clean soil and gravel.

During excavation activities in the Kellogg Street Development AOC, numerous unforeseen subsurface features, conditions, or structures were encountered and managed in accordance with NJDEP requirements.

The RAOs for soils in the Kellogg Street Development AOC were met by implementation of excavation in accordance with the SA-6 South 100% Design Report. The RAOs for soils in the Site 163 Development AOC are being met by a combination of excavation and capping that has been completed and institutional controls (deed notice and conservation restriction) that will be established in 2017. The RAOs for soils in the Open Space AOC are being met by a combination of a RCRA cap that has been completed and institutional controls (deed notice and conservation restriction) that will be established (deed notice) and/or updated (conservation restriction) in 2017.

It is anticipated that RAOs for SA-6 South shallow groundwater in the Development AOCs will be met as a result of the removal of chromium-impacted soil from the Development AOC and containment and capping of chromium-impacted soils and groundwater in the Open Space AOC. Preliminary sampling following the completion of the excavation remedy shows groundwater results below the GWQS for total chromium. This will be confirmed by post-remediation shallow groundwater sampling, which will be implemented in the Development AOCs in accordance with a Long Term Monitoring Plan (LTMP) currently being prepared for SA-6 North and SA-6 South. Further, the LTMP establishes procedures and schedules for long-term monitoring of shallow groundwater quality and levels in the

Open Space AOC to determine the potential operation of the contingent groundwater extraction system. The LTMP also establishes the inspection, maintenance, and operation of critical features of the Chromium Remedy.

Honeywell will establish appropriate institutional controls at SA-6 South that supplement the remedial actions. These include: deed notices and a remedial action permit for soils for four distinct areas: the Open Space AOC, the Site 163 Development AOC Deed Notice Area, and the two Deferred Areas; a conservation restriction for the Site 163 Development AOC Deed Notice Area; and a remedial action permit for shallow groundwater in the Open Space AOC. A conservation restriction has already been established for the Open Space AOC and will be updated to reflect the final as-built boundaries of the Open Space Area. A classification exception area (CEA) has already been established with the NJDEP for the regional shallow groundwater, but Honeywell may revise the boundary of the shallow groundwater CEA slightly based upon post-remediation shallow groundwater results from the Development AOCs.

It is Honeywell's intention that this document will close out remediation of chromium-impacted soils at SA-6 South with the exception of the implementation of the institutional controls and remediation of the Deferred Areas. Honeywell will subsequently request review and approval of similar documents to close out remediation of chromium-impacted shallow groundwater in the Development AOCs once groundwater sampling confirms that the RAOs have been met and the remediation of chromium-impacted soils in the Deferred Areas.

# 1.0 INTRODUCTION

## 1.1 PURPOSE AND SCOPE

Honeywell International Inc. (Honeywell) is submitting this Construction Completion Report (CCR) prepared by Amec Foster Wheeler Environment and Infrastructure, Inc. (Amec Foster Wheeler) to document completion of remedial activities associated with the Chromium Remedy at Study Area 6 South (SA-6 South), located in Jersey City, Hudson County, New Jersey. A Site Location Map is included as **Figure 1**. This CCR was prepared for and is submitted solely to the Special Master, the Parties, and the Court pursuant to the First Amended Consent Decree Regarding the Remediation and Redevelopment of Study Area 6 South, ECF No. 434, entered by the United States District Court, District of New Jersey on August 2, 2012, in Civil No. 05-05955, later consolidated with Civ. No. 95-2097 ("SA-6 South Consent Decree"). [4]

A Remedial Action Report (RAR)was prepared by Honeywell and submitted to the New Jersey Department of Environmental Protection (NJDEP) in accordance with the remedial action reporting requirements specified in the Technical Requirements for Site Remediation (TRSR), (New Jersey Administrative Code [N.J.A.C.] 7:26E-5.7). Since NJDEP's Site Remediation Program Case Management Team retained direct oversight of the Chromium Remedy, Honeywell requested NJDEP review and approval of the RAR in accordance with paragraph 23, G of the Consent Judgment between Honeywell and the NJDEP dated September 7, 2011 ("Consent Judgment"). NJDEP approved the RAR on March 30, 2017.

The purpose of this CCR is to provide documentation of the successful execution of the Chromium Remedy at SA-6 South to address chromium-impacted soil and

[4] The "Parties" referenced in this CCR are the signatories to the SA-6 South Consent Decree: the City of Jersey City, Hackensack Riverkeeper, and Honeywell. In addition, the "Special Master" referenced in this CCR is the Honorable Senator Robert Torricelli, who was appointed pursuant to the SA-6 South Consent Decree, paragraph 85, to oversee and enforce the implementation and long-term monitoring of the Chromium Remedy within SA-6 South, and the Initial Development Period related to the Open Space AOC.

groundwater[5]. The Chromium Remedy was completed in three Area of Concerns (AOCs) as shown on Figure 19:

- Kellogg Street Development AOC,
- Site 163 Development AOC[6], and
- Open Space AOC.

The Chromium Remedy was implemented at SA-6 South in accordance with the following documents:

- An Administrative Consent Order ("ACO") between Honeywell, formerly Allied Signal, Inc., and the NJDEP (NJDEP, 1993), modified pursuant to the Consent Judgment;
- SA-6 South Consent Decree;
- July 1, 2013: Technical Requirements for Site Remediation N.J.A.C. 7:26E-1-5 adopted May 7, 2012, revised 2013;
- NJDEP, 2012. New Jersey Administrative Code, Chapter 26C Administrative Requirements for the Remediation of Contaminated Sites (ARRCS); last revised May 7, 2012, Trenton, New Jersey.
- December 23, 2008: *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan for Chromium* to address chromium contamination at SA-6 South, exclusive of Site 163 (SA-6

[5] Throughout this CCR, reference to chromium-impacted soils shall mean soils containing hexavalent chromium above the NJDEP soil criteria of 20 mg/kg, and reference to chromium-impacted groundwater shall mean groundwater total chromium above the NJDEP groundwater standard of 70 µg/l.

[6] The Site 163 Development AOC is comprised of two areas, the Deed Notice Area and the Non-Deed Notice Area. The remediation differed in the two areas of the Site 163 Development AOC. In the Deed Notice Area, chromium-impacted soils were excavated only to 4 feet below ground surface (bgs), leaving chromium-impacted soils at concentrations exceeding 20 mg/kg deeper than 4 feet bgs in place. The Deed Notice Area will be subject to a deed notice and conservation restriction, like the Open Space AOC. Residential development is prohibited in the Deed Notice Area. In the Non-Deed Notice Area, chromium-impacted soils at concentrations exceeding 20 mg/kg were excavated to a depth of 20 feet bgs or to the meadow mat, as discussed in Section 8.

South Chromium SRIR/RASR/RAWP). This document was approved by the NJDEP in a letter dated March 24, 2009.

- May 18, 2012: *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan,* to address chromium contamination at Site 163 only (Site 163 Chromium SRIR/RASR/RAWP). This document was approved by the NJDEP in a letter dated June 22, 2012.
- June 28, 2013: *Chromium Remedy 100% Design Report - Issued for Construction* for SA-6 South, ECF Nos. 1176 and1180, entered by the United States District Court, District of New Jersey on July 10, 2013, in Civ. No. 05-05955, later consolidated with Civ. No. 95-2097 ("SA-6 South 100% Design Report"). Portions of this document were reviewed and approved by the NJDEP in an email on May 15, 2013. The Design Report for SA-6 North was issued at the same time and contains some information in the Appendices that also applies to SA-6 South. Unless otherwise noted, the design report, drawings, and specifications are collectively referred to herein as the 100% Design Report.
- Design Change Bulletins (DCs) to SA-6 South 100% Design Report as indicated in Section 3 below.

As the Chromium Remedy progressed, Honeywell prepared a series of Declarations which were periodically submitted to the Parties to memorialize completion of specific remedial elements of the Chromium Remedy in accordance with the above documents. There are three individual Declarations related to SA-6 South (Declarations Nos. 1, 2 and 5), and five in total for SA-6 South and SA-6 North. In general accordance with Honeywell correspondence dated June 19, 2014 and February 4, 2016 submitted to all Parties, the elements of each Declaration were as follows:

- Declaration No. 1: Excavation and backfilling, hydraulic barrier wall construction, and soil management and disposition at SA-6 South;
- Declaration No. 2: Open space cap subgrade, geosynthetic components, contingent groundwater extraction system trench construction, and trimming of the hydraulic barrier wall sheet pile to final elevation at SA-6 South;
- Declaration No. 3: Excavation and backfilling, hydraulic barrier wall construction, and soil management and disposition at SA-6 North;

- Declaration No. 4: Open space cap subgrade, geosynthetic components and contingent groundwater extraction system trench construction at SA-6 North; and
- Declaration No. 5: All Remaining construction activities including: additional miscellaneous excavations at SA-6 South within 60 Kellogg and Site 163; installation of gas vent system, cover soil placement, final contingent groundwater extraction system infrastructure installation, discussion of deferred areas and pending institutional controls required, in-situ treatment, soil erosion and sediment control at SA-6 South and SA-6 North; monitoring well installation and abandonment, final grading and historic fill cap installation at SA-6 South; and meadow mat (Stratum D) repair at SA-6 North .

In addition, each Declaration is signed by Honeywell and a New Jersey-licensed professional engineer and all five Declarations have been entered with the United States District Court for the District of New Jersey in Civil No. 95-2097 (see ECF Nos. 1403-1, 1464-1, 1484, 1487, and 1515, for Declarations 1 through 5, respectively). While the Declarations are not required by the TRSR for RARs, the Special Master and Parties have agreed that the Declarations will be included in the CCR. As a result, the Declarations are attached to this CCR (**Appendix S**). The CCR will be filed with the Court in accordance with paragraph 5 of the Consent Order Entering Consolidated 100% Design for Study Area 6 North and Study Area 6 South, *Jersey City Municipal Utilities Auth. v. Honeywell*, D.N.J., Consol. Cases, Civ. No. 95-2097, July 9, 2013, ECF No. 1180.

Non-chromium areas of concern (AOCs) within SA-6 South were also remediated during the implementation of the Chromium Remedy. This CCR does not address non-chromium AOCs. A separate RAR addressing the SA-6 South non-chromium AOCs was prepared and submitted to NJDEP by Honeywell's Licensed Site Remediation Professional (LSRP) in December 2016. A separate RAR for chromium remediated at SA-6 North was submitted to NJDEP, the Special Master, and the Parties on March 16, 2017. NJDEP approved the SA-6 North RAR on June 1, 2017. A CCR for SA-6 North will be prepared and submitted solely to the Special Master and the Parties.

The SA-6 Chromium Remedy 100% Design was prepared by Honeywell as one integrated project for both SA-6 North and SA-6 South. The 100% Design Report was used to obtain bids from and select a remedial contractor to implement the Chromium Remedy at both sites concurrently with the same project team under one contract. Although two 100% Design Reports were prepared for SA-6 North and SA-6 South, remedial activities or elements that were common to each were combined to the extent possible. Project execution followed the integrated approach with certain elements of the SA-6 Chromium Remedy common to both sites, such as project support systems and infrastructure, construction water treatment, decontamination pads, site security and preparation, etc.

## 1.2 SITE SETTING AND SITE HISTORY

SA-6 North and SA-6 South are located on the west side of Jersey City. SA-6 North and SA-6 South are separated by Study Area 7 (SA-7). SA-6 North, SA-6 South, and SA-7 lie between Route 440 to the east and the Hackensack River to the west. A Site Layout Map is included as **Figure 2.** SA-6 South is bordered by SA-7 to the north and Droyers Cove, Kellogg Street and Droyers Point Society Hill developments to the south. Adjacent commercial properties, including New Jersey City University (NJCU) and a Home Depot, are located east of Route 440.

Collectively, SA-6 North, SA-7, and SA-6 South comprise approximately 100 acres (see **Illustration 1**). Bayfront Redevelopment LLC, a wholly owned subsidiary of Honeywell, owns both the SA-6 North and SA-6 South properties with the exception of: (a) Lot 4, a 0.4-acre lot that is owned by Mr. Paul Trenk, and (b) Block 6 on SA-6 North, representing a 6.25-acre lot occupied by the Jersey City Municipal Utilities Authority (JCMUA), and the City of Jersey City (Jersey City). All lots and blocks on SA-6 South are owned by Bayfront Redevelopment LLC and total just over 25 acres as indicated below.

SA-6 South is comprised of the following six sites:

| NJDEP Site No. | NJDEP Site Name | Program Interest Number for Chromium | Block 24601 Lot No. | Address | Acres |
|---|---|---|---|---|---|
| 073 | Degen Oil | G000000927 | 1 | 200 Kellogg St. | **3.19** |
| 124 | Roosevelt Bowling Lanes | G000008741 | 8 & 12 | 427 Route 440 | **3.65** |

| NJDEP Site No. | NJDEP Site Name | Program Interest Number for Chromium | Block 24601 Lot No. | Address | Acres |
|---|---|---|---|---|---|
| 125 | Delphic Consolidated | G000008742 | 7 | 60 Kellogg St. | **2.99** |
| 134 | Old Dominion | 033312 | 3, 4, & 5 | 100 Kellogg St. | **4.82** |
| 140 | ABF Trucking | 003846 | 6 | 80 Kellogg St. | **3.67** |
| 163 | Posnak & Turkish | 010374 | 11 | 75 Kellogg St. | **4.97 (of which 2.58 is submerged)** |
| Included in 124 | Cordova | NA | 9 & 10 | 28 & 38 Kellogg St. | **1.2** |
| Included in 134 | Boatyard | NA | 2 | 150 Kellogg St. | **0.89** |
| **Total Acres** | | | | | **25.38** |

Detailed site histories have been provided in previous regulatory submittals. Recent operations at SA-6 South and SA-6 North are summarized as follows:

- SA-6 North is also referred to as the "Jersey City Properties." Since approximately the mid-1950s, the SA-6 North was owned by Jersey City and occupied by "Jersey City Entities" including the Jersey City Department of Public Works (JCDPW), Jersey City Incinerator Authority (JCIA), and JCMUA. JCDPW and JCIA vacated the SA-6 North in 2014 during the implementation of the Chromium Remedy and some of the associated structures formerly occupied by the JCIA were demolished. JCMUA continues operations on Block 6 including primary waste water treatment (grit removal) and sanitary conveyance to the regional Passaic Valley Sewerage Commission (PVSC) wastewater treatment facility located in Kearny, New Jersey. JCMUA also performs vehicle maintenance and material storage and maintains administrative operations on Block 6. Bayfront took ownership of the SA-6 North properties June 5, 2008.
- SA-6 South is also referred to as the "Kellogg Street Properties." SA-6 South was the location of historic industrial and commercial operations. Recent operations included a bowling alley, freight trucking terminals, chemical production, concrete mixing and distribution, boat repair, and light retail and

office space. Honeywell purchased the SA-6 South properties between 2005 and 2010.

Historical maps and aerial photographs indicate that, prior to development, SA-6 South and the surrounding area consisted of marshland, which extended to the edge of the former Morris Canal (approximately the eastern edge of Route 440). Filling activities occurred from approximately the 1920s to the 1950s. The aerial photographs indicate that the area comprising SA-6 and SA-7 had been filled over the years to build up the grade to approximately current levels. No detailed information is available on the placement of chromite ore processing residue (COPR) for the properties comprising SA-6 South. However, it is believed that COPR deposited on SA-7 likely spilled over and was co-mingled with other types of fill, spreading the COPR material onto the adjacent portions of the SA-6 North and South properties. The deposition of COPR is believed to have resulted from operations at a former sodium dichromate plant that operated on the east side of Route 440.

Visual observations of soil borings and sample analytical results from soil borings conducted on SA-6 North and SA-6 South indicate the presence of other types of fill consistent with the NJDEP's definition of "historic" fill in the TRSR. The historic fill map of the Jersey City quadrangle (NJDEP, 2004) was obtained from the NJDEP's website and was reviewed. This map confirms that SA-6 North, SA-6 South, and SA-7 were identified as containing historic fill as mapped by the NJDEP. The resulting material on the SA-6 properties is thus a mixture of COPR and indigenous historic fills and soils.

## 1.3 PROJECT BACKGROUND AND LAND DEVELOPMENT

A redevelopment plan, known as the Bayfront Redevelopment Plan, encompasses the entire 100-acre parcel designated as SA-6 North, SA-7 and SA-6 South (see **Illustrations 1 and 2**) and was approved by the City of Jersey City on March 12, 2008. Remediation of chromium-impacted soils and groundwater was conducted consistent with the planned future use and redevelopment of SA-6 South as set forth in the Bayfront Redevelopment Plan. Remediation of chromium-impacted soils at SA-7 was completed in September 2009. Honeywell remediated SA-6 South from March 2013 to November 2016 so that the Redevelopment Project may now proceed.

Remediation of SA-6 North has also now been completed, and will be reported under a separate RAR and CCR.




**Illustration 1: SA-6, SA-7, and Surrounding Area**

The Bayfront Redevelopment Plan lays out the redevelopment of the nominal 100-acre site that is owned by Bayfront Redevelopment LLC (Bayfront, a subsidiary of Honeywell) and is being developed in partnership with the City of Jersey City into a residential, commercial and retail complex. The Bayfront Redevelopment Plan represents a major opportunity to revitalize the west side of Jersey City; it meets the objectives of Jersey City's master plan for the broader west side area designated as the Bayside Redevelopment Area (see **Illustration 2**).

The Chromium Remedy and Non-Chromium Remedies at both SA-6 North and SA-6 South integrate the requirements of the future Bayfront Redevelopment Plan.

To be consistent with future planned use and the Bayfront Redevelopment Plan, SA-6 South and SA-6 North are divided into Open Space and Development Areas. The designation of these areas is contained in the SA-6 North and SA-6 South Consent Decrees, and is designated as follows:




**Illustration 2: Bayside Redevelopment Area**

- SA-6 North Consent Decree: "Open Space Area" and "Residential Area" and "Additional Excavation Areas." The Residential Area and Additional Excavation Areas are development areas.
- SA-6 South Consent Decree: "Open Space AOC" and "Development AOC." The "Development AOC" consists of two parts: the Kellogg Street Development AOC and the Site 163 Development AOC. When both the Kellogg Street Development AOC and the Site 163 Development AOC are referred to together in this CCR, the term Development AOCs will be used for brevity.

The Bayfront Redevelopment Plan designates the SA-6 North and SA-6 South Development Areas for future residential and commercial/retail use redevelopment, and designates the Open Space Areas for future redevelopment as linear parks and recreational use areas currently known as "Central Park" on SA-6 North and the "Promenade" on SA-6 South. The final grades of the cap associated with the Chromium Remedy in the Open Space AOC are consistent with the Bayfront

Redevelopment Plan grades, with smoothing as needed to facilitate drainage pending development, and associated installation of roadways and stormwater management. Development in the Open Space Area and Site 163 Development AOC Deed Notice Area is also restricted via conservation restrictions that are or will be recorded. **Illustration 3** depicts the conceptual Chromium Remedy related to future redevelopment AOCs.





**Illustration 3: SA-6 South Chromium Remedy and Redevelopment Plans**

## 1.4 CONTAMINANTS OF CONCERN AND REMEDIAL ACTION OBJECTIVES

For the purpose of this CCR, the contaminant of concern (COC) in soils at SA-6 South is hexavalent chromium and the COC for shallow groundwater is total chromium per the NJDEP-approved RAWPs. The NJDEP-approved RAWPs identified specific remedial action objectives for soil and groundwater as follows:

Specific Remedial Action Objectives (RAOs) for soils include:

- Prevent exposure to chromium-impacted soils containing hexavalent chromium above the NJDEP soil criteria of 20 milligrams per kilogram (mg/kg) to a depth of 20 feet, consistent with NJDEP policy.
- Remove and consolidate chromium-impacted soils that may be disturbed by future Site redevelopment activities; and reuse soils beneath area to be capped, to the extent feasible.

- Coordinate remedial actions for chromium with remedial actions for non-chromium contaminants and Site redevelopment, to the extent feasible.

Specific RAOs for groundwater include:

- Mitigate the potential for surface water infiltration and leaching of contaminants (total and hexavalent chromium) from fill soils (vadose zone) to groundwater.
- Mitigate offsite migration of chromium in groundwater above the NJDEP Groundwater Quality Standard (GWQS).[7]
- Reduce chromium concentrations in groundwater.
- Prevent exposure to groundwater chromium concentrations above the NJDEP GWQS.

To achieve the RAOs for soils in the Kellogg Street Development AOC, Honeywell excavated chromium-impacted soils to a depth of 20 feet bgs and either disposed of such material offsite or consolidated the material in the Open Space AOC.

To achieve the RAOs for soils on the Open Space AOC, engineering controls (vertical hydraulic barrier and Resource Conservation and Recovery Act [RCRA] cap) were constructed around the Open Space AOC to fully contain existing and consolidated hexavalent chromium-impacted soil. Institutional controls (deed notice and conservation restriction) will also be established for the Open Space AOC so that this area remains as open space.

The NJDEP-approved Site 163 Chromium SRIR/RASR/RAWP indicated that to achieve the RAOs for soils the shallow chromium-impacted soils would be excavated and deeper chromium-impacted soils (i.e., 4 feet or more bgs) would be treated in-situ. However, because in-situ treatment was ineffective, a combination of excavation and capping was instituted. Additional details pertaining to the

[7] The SA 6 South Consent Decree requires Honeywell to isolate shallow groundwater and to intercept and treat shallow groundwater flowing above the meadow mat in the Open Space AOC to the extent that such groundwater contains total chromium in concentrations in excess of 70 µg/l. The Study Area 6 South Consent Decree also requires Honeywell to maintain an outward gradient of shallow groundwater from Study Area 7.

implementation of the in-situ chemical reduction in the Site 163 Development AOC are provided in Section 12. To achieve the soil RAOs for the Site 163 Development AOC Non-Deed Notice Area, chromium-impacted soils were excavated to a depth of 20 feet bgs and either disposed of offsite or consolidated in the Open Space AOC. To achieve the soil RAOs for Site 163 Development AOC Deed Notice Area, shallow chromium-impacted soils (i.e., less than 4 feet bgs) were excavated and either disposed of offsite or consolidated in the Open Space AOC, deeper chromium-impacted soils (i.e., 4 feet or more bgs) were capped, and institutional controls (deed notice and conservation restriction) will be established subsequently.

The RAOs for soils were met in all three AOCs with the exception of the two Deferred Areas discussed in Section 4 and shown on **Figure 19**, and the implementation of the institutional controls in the Open Space AOC and Site 163 Development AOC Deed Notice Area.

It is expected that groundwater RAOs in the Development AOCs will be met because excavation and removal of chromium-impacted soils in the Development AOCs significantly reduced total chromium concentrations in groundwater following completion of the Chromium Remedy. Post-soil remedy total chromium groundwater concentrations in the Development AOCs are now below the NJDEP GWQS for groundwater of 70 micrograms per liter (µg/L) for total chromium throughout most of the Development AOCs (see Section 5.5.1 for further discussion). In the Open Space AOC groundwater RAOs were met by construction of a vertical barrier and a cap which now fully contains groundwater in the Open Space AOC. Further, a contingent groundwater extraction system has been installed to assist in maintaining an inward hydraulic gradient relative to the Open Space AOC. Groundwater monitoring will be implemented in accordance with the Long Term Monitoring Plan (LTMP), currently under development for both SA-6 North and SA-6 South, to establish the post-Remedy disposition of groundwater in the Development AOCs. Groundwater level measurements will be implemented in accordance with the LTMP to monitor hydraulic conditions within the Open Space AOC.

Honeywell will establish appropriate institutional controls at SA-6 South including deed notices and a remedial action permit for soils for four distinct areas: the Open Space AOC, the Site 163 Development AOC Deed Notice Area, and the two Deferred Areas. A remedial action permit for groundwater in the Open Space AOC will be

requested from NJDEP. A Classification Exception Area (CEA) has already been established with NJDEP for the regional shallow groundwater. Honeywell may revise the boundary of the shallow groundwater CEA slightly based upon the post-remediation results of shallow groundwater sampling at SA-6 South. More details concerning the institutional controls are provided in Section 18.

Sections 4 and 18.1 more fully describe the deed noticed areas, but a summary of the four areas at SA-6 South are:

- Deed Notice Area 1: Open Space AOC
- Deed Notice Area 2: Route 440 Right of Way (ROW)
- Deed Notice Area 3: Portion of Site 163
- Deed Notice Area 4: Site 073 Bulkhead Area and the SA-7 Bulkhead Area.

## 1.5 CONSTRUCTION OVERVIEW

The Chromium Remedy for the Kellogg Street Development AOC and the Site 163 Development AOC Non-Deed Notice Area consisted of excavation of soils exceeding 20 mg/kg hexavalent chromium to the elevations established in the SA-6 South 100% Design Report, DC 2013-12-12, DC 2014-5-06, and DC 2015-9-28 based either upon pre-design investigation (PDI) sample data or encountering Stratum D. Depending on the hexavalent chromium concentration, the excavated soil from the Development AOCs was either disposed of offsite, consolidated under the cap in the SA-6 South Open Space AOC (20-1,000 mg/kg) or transferred to the SA-6 North Open Space AOC (20-240 mg/kg). To contain impacted groundwater within the Open Space AOC, hydraulic barriers keyed into the Stratum D were installed on the east, south and west sides of the open space AOC. The SA-7 Soil-Cement Bentonite (SCB) Wall forms the northern side of the hydraulic barrier. The southern hydraulic barrier also serves as temporary excavation support for the adjacent excavation in the Development AOC. A RCRA-equivalent cap was constructed over the Open Space AOC to isolate chromium-impacted soils. A clean soil and gravel cap was constructed in the Site 163 Development AOC Deed Notice Area to isolate chromium-impacted soils at a depth of 4 feet or more bgs.

More specifically, the Chromium Remedy included the following main work elements:

- Site preparation (utility mark out, temporary fencing, and erosion controls);
- Remedial Contractor mobilization and installation of site support facilities including construction trailers, decontamination stations, utility abandonment and bypassing, soil erosion controls, construction dewatering and stormwater control and treatment infrastructure;
- Abandonment/demolition/removal/relocation of existing structures, select monitoring wells, and utilities as necessary to remediate chromium-impacted areas;
- Construction water management;
- Installation of temporary sheetpile for excavation support;
- Excavation within the designated Kellogg Street Development AOC and Site 163 Development AOC Non-Deed Notice Area of chromium-impacted soils exceeding 20 mg/kg hexavalent chromium to a maximum depth of 20 feet or shallower if meadow mat (Stratum D) was reached;
- Consolidation of excavated material exhibiting hexavalent chromium concentrations between 20 and 1,000 mg/kg within the Open Space AOC;
- Offsite disposal and transportation of excavated material exhibiting hexavalent chromium concentrations exceeding 1,000 mg/kg;
- Installation of a hydraulic barrier along the perimeter of the designated Open Space AOC that was embedded approximately 2 feet (minimum) into the underlying Stratum D and was tied into the existing hydraulic barrier associated with the SA-7 remedy along the common SA-6 South and SA-7 boundaries;
- Installation within the Open Space AOC of a contingent groundwater extraction system which will be operated as needed to maintain an inward hydraulic gradient as specified in the SA-6 LTMP that is currently being developed;
- Soil surcharging in the Open Space AOC to consolidate underlying compressible strata;
- Grading of consolidated soil from other areas in the Open Space AOC and compaction of existing material/subgrade fill;

- Installation of the RCRA-equivalent geosynthetic cap system, including a methane venting layer to address naturally occurring methane;
- Installation of surface drainage and erosion control structures;
- Installation of a cap drainage system to collect stormwater infiltration and discharge to surface water;
- Installation of utility corridors for future site redevelopment;
- Installation of piezometers and/or monitoring wells within the Development AOC, the Open Space AOC, and SA-7, to allow for groundwater level monitoring for hydraulic control and groundwater sampling;
- Restoration of site and vegetation planting; and
- Recording of institutional controls and initiation of future monitoring.

**Table 10** provides a cross-reference table of major construction elements referenced to particular components of the SA-6 South 100% Design (100% Design Report, Specifications, and Drawings), DCs, and the Declarations documenting completion of specified portions of the Chromium Remedy.

The Chromium Remedy activities included the following major categories, and corresponding approximate quantities for SA-6 South (quantities that are combined for SA-6 North and SA-6 South are noted):

| Item | Units | Quantity |
|---|---|---|
| Construction Water Discharged (North and South) | Gallons | 41,257,040 |
| Abandoned Existing Monitoring Wells/Piezometers | Each (EA) | 47 |
| Dewatering Wells | | |
| Shallow | EA | 339 |
| Deep | EA | 6 |
| New Monitoring Wells | | |
| Piezometers | EA | 10 |
| Monitoring Wells | EA | 11 |
| Material Handling | | |
| Recycled Concrete | Cubic Yards (CY) | 18,000 |
| Excavated Soils | | |

| Item | Units | Quantity |
|---|---|---|
| <20 mg/kg | CY | 73,700 |
| 20-240 | CY | 50,800 |
| 240-1,000 | CY | 18,700 |
| >1,000 | CY | 25,000 |
| New Stormwater Pipe | Linear Feet (LF) | 463 |
| Consolidated Materials | | |
| 20-1,000 (South) | CY | 35,000 |
| 20-240 (North) | CY | 35,000 |
| Petroleum | CY | 24,000 |
| Asphalt | CY | 1,250 |
| Hydraulic Barrier | LF | 2,586 |
| Cap Materials | | |
| Subgrade Fill | CY | 59,000 |
| Geosynthetic Venting Layer (GVL) | Square Feet (SF) | 245,217 |
| Geosynthetic Composite Layer (GCL) | SF | 46,797 |
| Geotextile Layer | SF | 62,779 |
| Geosynthetic Drainage Layer (GDL) | SF | 352,500 |
| Liner | SF | 352,500 |
| GDL Soil | CY | 15,200 |
| Root Barrier | SF | 352,500 |
| Clean Cover Soils | CY | 43,000 |
| Backfill | | |
| <20 mg/kg | CY | 33,500 |
| Imported Fill: Dense Grade Aggregate (DGA)/Screenings | CY | 130,000 |
| Clean Stone leftover from SA-7 Sediment Remedy | CY | 1,000 |
| Celgene, Somerset, NJ Excavation | CY | 69,000 |
| Clean Stone leftover from NJCU | CY | 17,000 |
| Surcharge | | |
| Soil | CY | 240,000 |

| Item | Units | Quantity |
|---|---|---|
| Monitoring Points | EA | 22 Half Stations<br>7 Full Stations<br>8 Settlement Platforms |
| Disposal | | |
| Recycled Asphalt | Tons | 3,700 |
| >1,000 | Tons | 33,000 |
| Concrete | Tons | 815 |
| Petroleum | Tons | 36,000 |
| Debris | Tons | 315 |

The following entities were involved in the construction of the SA-6 South remediation (see also **Figure 3,** Project Team Organization Chart):

| Party | Responsibility |
|---|---|
| **Honeywell** | Overall compliance with court-ordered remediation |
| **Amec Foster Wheeler** | Engineer of Record (EOR), Design, Contract Documents, Construction Inspection, Health and Safety Oversight, and Overall Site Construction Management |
| **Entact** | Excavation of COPR, imported backfill purchase and placement, and Dewatering and Groundwater Extraction |
| **Entact Subcontractors:**<br>**B&B Drilling, Inc.**<br><br>**Maser Consulting P.A.**<br>**Chemtech**<br><br>**Eurofins**<br><br>**Vertical V-Northeast**<br>**ESI** | <br>Install and abandon monitoring wells and piezometers<br>Surveying<br>Analytical Laboratory for Imported Fill Samples (non-chromium)<br><br>Analytical Laboratory for Imported Fill Samples (chromium)<br><br>Compaction Testing<br>Installation of all geosynthetic materials for the RCRA-equivalent cap |
| **Emilcott Associates** | Air Monitoring |
| **Arecon** | Manifests, and Management of Excavated Soil Disposal |
| **Mueser Rutledge Consulting Engineers (MRCE)** | 3rd Party Structural and Geotechnical Engineering Peer Review |
| **Langan** | 3rd Party Liner QA |

| Party | Responsibility |
|---|---|
| **Accutest Laboratories Inc. (Accutest)** | Analytical Laboratory for samples collected by Amec Foster Wheeler |
| **Travelers Industrial Hygiene Laboratory** | Analytical Laboratory for Perimeter Air Monitoring Plan (PAMP) samples |
| **Analytical & Environmental Services, Inc. (AESI)** | 3rd Party Analytical QA/QC |
| **Validata, LLC** | 3rd Party Analytical Data Validation |
| **Cornerstone** | Groundwater Modeling |
| **Geocomp Engineering** | Prepared Vibration Monitoring Report |

Mobilization commenced on March 1, 2013 and was completed on June 28, 2013. The Chromium Remedy on SA-6 South was substantially complete by November 2016. Work on SA-6 North was also substantially completed by November 2016. Representative photographs of major components of the work are included in **Appendix A.**

## 1.6 DATA VALIDATION AND DATA USABILITY EVALUATION

Unless otherwise indicated for specific sample types, Accutest analyzed soil and groundwater samples collected during the Chromium Remedy implementation. Hexavalent chromium analysis was performed using United States Environmental Protection Agency (USEPA) Method 7199. Data validation was performed by a third-party data validation specialist with Validata, LLC (Validata) of Seattle, Washington. Additionally, Honeywell employs Dr. Rene Surgi of Analytical & Environmental Services, Inc. (AESI) of Glencoe, Illinois, to provide third-party analytical quality assurance/quality control (QA/QC).

Honeywell's protocol was to have Dr. R. Surgi review 100% of the soil sample hexavalent chromium analytical data and work with Accutest on any QA/QC matters prior to issuance of the final analytical data packages. Soil samples that do not meet the laboratory's strict internal QA/QC criteria are re-logged by the laboratory and re-analyzed. Once the data packages are issued by Accutest to Validata, the hexavalent (and total chromium, if performed) chromium data are validated. Employing such a protocol provides a high degree of confidence that the hexavalent chromium analytical data that has passed the internal laboratory QA/QC standards and was not rejected by the validator is accurate, precise,

representative and, thus, usable. Rejected data, although reported, is flagged with an "R" and is not used for the intended purpose of the associated sampling.

The Data Management Plan (DMP) contained in the SA-6 North 100% Design Report outlined, among other things, the specific data validation objectives and procedures involved in producing quality, usable analytical data during implementation of the Chromium Remedy. Honeywell revised the DMP in August 2014 to clarify data validation level and frequency based upon the purpose of the sampling and end use of the data. This revised DMP was submitted to NJDEP and all Parties on August 22, 2014. A summary of the data validation level and frequency for soil samples analyzed for total and hexavalent chromium collected during the SA-6 Chromium Remedy and based upon the revised DMP was as follows:

- Level IV data validation on 100% of samples analyzed that were used for compliance purposes (i.e. post-excavation soil samples and those collected for re-use applicability of excavated material and quarterly groundwater samples); and
- Level II data validation of approximately 25% on samples that were used for non-compliance purposes (i.e. samples for soils consolidated in the Open Space AOC and those collected from soils being disposed of offsite).

Additionally, and in accordance with the DMP, data validation was also conducted on the following samples that included analysis of parameters other than total and hexavalent chromium:

- Level IV data validation on 100% of the monthly effluent water samples for tested parameters;
- Level IV data validation on 10% of soil samples for other (non-chromium) tested parameters; and
- Level IV data validation of approximately 10% of the PAMP air samples analyzed for hexavalent chromium for other (non-chromium) tested parameters. Those samples for which data validation was conducted only on a 10% frequency are indicated as **Tables 1A and 1B**.

The NJDEP issued guidance for the Data of Known Quality Protocols (DKQPs) in April 2014, approximately 1 year after the start of the SA-6 Chromium Remedy. The NJDEP was consulted regarding whether the questionnaire that is part of the DKQP process needed to be filled out for samples collected during the implementation of the Chromium Remedy. NJDEP concluded that the DKQP questionnaires were not required for the Chromium Remedy since the laboratory follows rigorous QA/QC protocols specifically developed for the chromium program in Jersey City which results in the generation of data of known quality and because the third-party validation process covers the data assessment and usability evaluation promoted in the DKQP guidance. We note that the validation process essentially asks the same questions as those on the questionnaire. As indicated above, 100% of such samples for hexavalent chromium analysis were validated by Validata, whereas validation of all other analytical parameters was conducted on 10% of the samples. Rejected data is not used.

Given the high level of internal and external QA/QC that is conducted, the 100% data validation that Honeywell employs for hexavalent chromium, and validation of 10% of samples for analytical parameters other than hexavalent chromium, the analytical data meets NJDEP's standards of precision, accuracy, and usability.

Copies of the laboratory analytical reports and the data validation reports are available upon request. Electronic Data Deliverable (EDD) documentation is included in **Appendix B**.

## 1.7 REPORT ORGANIZATION

This document has been prepared to meet the provisions specified in Sections 1.6 and 5.7 of the TRSR and contains the following sections:

- *Introduction.* This section contains information on the purpose and scope of the document, pertinent site setting information, project background and relationship between the Bayside Redevelopment Area and Bayfront, COCs and RAOs, overview of the Chromium Remedy construction elements, and report organization.
- *Preparatory Construction Activities.* This section describes the activities implemented that were in support of the main elements of the Chromium Remedy.

- *Modifications and field changes to* SA-6 South *100% Design Report.* Changes to what was proposed in the SA-6 South 100% Design report are summarized in this section.
- *Deferred Areas and Unanticipated Items Encountered During Remedial Activities.* These sections summarize uncompleted, unexpected or unanticipated conditions encountered during implementation of the Chromium Remedy.
- *Dewatering and Construction Water Treatment* (Section 6) through *Site Restoration* (Section 14). Detailed descriptions of the main elements of the Chromium Remedy are provided in these sections. Tables and figures are used to graphically communicate the information.
- *Construction Permits.* This section presents a description of the permits obtained to implement the Chromium Remedy.
- *Sustainability Efforts During Construction.* Sustainable elements of the Chromium Remedy implementation are presented in this section.
- *Post-Remedy Operation & Maintenance.* This section describes the activities to inspect, monitor, and maintain elements of the Chromium Remedy that remain. In addition, groundwater monitoring and sampling is described.
- *Institutional Controls*. The implementation of deed notices, soil and groundwater remedial action permit(s), and a classification exception area are presented in this section.
- *Record Drawings*. Record drawings are discussed and provided.
- *Remedial Action Costs*. A summary of the costs to complete the project are provided.
- *Remediation Close Out Summary*. This section contains the conclusions and recommendations.
- *References.* References used in preparing this document are listed in this section.
- *List of Acronyms and Abbreviations.* This section contains a list of acronyms and abbreviations used in this document.

# 2.0 PREPARATORY CONSTRUCTION ACTIVITIES

On behalf of Honeywell, Amec Foster Wheeler managed and oversaw the bidding and contractor selection process for the SA-6 South Chromium Remedy. The selected contractor was Entact LLC (Entact) of Pittsburgh, Pennsylvania. Prior to mobilization, Entact prepared and submitted to Amec Foster Wheeler and Honeywell various work plans and submittals and acquired certain construction permits and approvals required by the SA-6 South 100% Design Report for implementation of the SA-6 South Chromium Remedy.

In addition, several other permits were obtained by Amec Foster Wheeler for execution of the SA-6 South Chromium Remedy during the design process. Other additional permits were obtained after the design process as detailed designs prepared by Entact were needed to obtain certain permits. Permits acquired for implementation of the SA-6 South Chromium Remedy are listed in Section 15.

## 2.1 MOBILIZATION AND SITE PREPARATION

Amec Foster Wheeler and Entact mobilized equipment and labor forces to SA-6 South between March 1, 2013 and June 28, 2013. Mobilization and site preparation included the following key activities:

- Re-establishment of Amec Foster Wheeler and Honeywell office space in the southern portion of the building located at 60 Kellogg Street;
- Mobilization and set-up of office trailers at SA-6 South for Entact operations. The trailers were outfitted with temporary electrical, internet, and telephone infrastructure;
- Establishment of a global positioning system (GPS) base station for use with construction layout and surveying;
- Mark-out of excavation, capping, staging and lay down areas;
- Geophysical surveys to locate unknown utilities, utility mark-outs, onsite utilities to be maintained, relocated or abandoned;
- Establishment of vehicular traffic pathways and staging areas;
- Installation of soil and erosion controls;

- Setup of the temporary construction water treatment plant (CWTP) at SA-6 North. The CWTP was utilized for SA-6 North and SA-6 South;
- Relocation of electrical feed for SA-7 regional groundwater extraction wells;
- Construction of decontamination facilities; and
- Installation of fencing, and establishment of initial exclusion zones, contaminant reduction zones and support zones. Such zones were maintained and modified as needed throughout the execution of remediation activities.

Other preparatory activities that occurred either just prior to or during initial stages of the construction activities are described in the sections that follow.

## 2.2 HEALTH AND SAFETY

Health and Safety on the SA-6 South Chromium Remedy was controlled by a Master Health and Safety Plan (HASP). The Master HASP was included as Appendix D of the SA-6 North Chromium Remedy 100% Design Report and was used for SA-6 South. Each site contractor was required to prepare and submit a HASP for their specific work requirements in conformance with the Master HASP. Direct responsibility for employee safety was retained by each contractor as outlined in the contractor's respective HASP.

The minimum personal protective equipment (PPE) for personnel within the fenced-in portion of SA-6 South included hardhats, high visibility vests, gloves, safety glasses, and steel toed boots. Minimum worker PPE within exclusion zones at SA-6 South consisted of hardhat, safety glasses, high visibility vests, Tyvek™ suits, gloves, and steel-toed boots. Upon leaving the exclusion zone, disposable PPE was placed into containers staged within the contamination reduction zone. Non-disposable PPE was decontaminated in the same area. Disposable PPE was combined with other chromium-impacted waste and transported and disposed of offsite. Decontamination fluids were processed through the onsite CWTP and subsequently discharged via JCMUA and PVSC discharge permits and agreements.

During the course of the project, 386,624 man-hours were worked on site. This number represents the combined total with SA-6 North as this was conducted as an integrated project. Of that total, approximately 60% of the total hours worked could

be allocated to SA-6 South. There were no Occupational Safety and Health Administration (OSHA) recordable incidents for the SA-6 South Chromium Remedy. Annual details are summarized in the table below:

| Year | Man-Hours* |
|---|---|
| 2013 | 60,928 |
| 2014 | 132,272 |
| 2015 | 104,384 |
| 2016 | 89,040 |
| **Project Total** | **386,624** |

*The man-hours include all hours on both SA-6 North and SA-6 South from mobilization through November 18, 2016.

A perimeter air monitoring program was carried out to document protection of human health outside of the remediation zone(s) to airborne COCs. The perimeter air monitoring program is discussed in detail in Section 11, but background and baseline monitoring activities are presented briefly below in Section 2.3 as they were part of the preparatory construction activities. In the course of the project, there were no exceedances of the perimeter air action levels.

## 2.3 BACKGROUND AND BASELINE PERIMETER AIR MONITORING

A perimeter air monitoring program (PAMP) was implemented and maintained whenever ground intrusive activities were occurring throughout the course of the SA-6 Chromium Remedy. The PAMPs were provided in the 100% Design Report. Separate PAMPs were prepared for SA-6 North and SA-6 South to account for the disparate durations of ground intrusive activities between SA-6 North and SA-6 South. The PAMP for SA-6 South was Appendix F of the SA-6 South Chromium Remedy 100% Design Report. More details of the overall perimeter air monitoring program are provided in Section 11.

During the mobilization phase and prior to ground intrusive activities, background perimeter air monitoring was performed to establish baseline air conditions that could be used for comparison to those measured during ground intrusive activities as shown on **Table 1A**. The background sampling was conducted for a minimum of 10

days during fair weather conditions (i.e., not during rain, snow, or high humidity) from July 15, 2013 to August 6, 2013.

Upon completion of the baseline sampling activities, the laboratory analytical data, real-time volatile organic compounds (VOC) [if applicable] and particulate matter dust monitoring data, and meteorological data was tabulated and presented to Honeywell. **Table 1A** summarizes the baseline perimeter air monitoring sample analytical data collected. **Figure 4** indicates the locations of the PAMP stations.

## 2.4 SITE SECURITY

Site security was established during the mobilization phase. Site security focused on perimeter security and access. The primary feature of Site Perimeter security was the perimeter fence line. SA-6 North was already surrounded by a perimeter fence due to the presence of the Jersey City Entities at that Site. The existing chain link fence along the exterior borders of SA-7 and SA-6 South previously installed during the remediation of SA-7 was repaired and replaced, as needed. Where new fence was required, 8-foot chain link fence was installed (equivalent to that installed on SA-7).

In addition to the perimeter fencing, control of access to SA-6 North, SA-6 South, and SA-7 was established primarily by use of strategically placed gates in the perimeter fencing. Site Access for SA-6 South was established with the entrance and exit through a security manned gate from Kellogg Street. No access to SA-7 was provided from offsite locations. All access to SA-7 was from either SA-6 North or SA-6 South.

Finally, a 24-hour security guard presence was also maintained throughout the project. Guards patrolled SA-6 North, SA-6 South, and SA-7 in vehicles.

## 2.5 SUPPORT FACILITIES AND TEMPORARY SITE UTILITIES

Support facilities for the Honeywell and Amec Foster Wheeler construction management and Entact teams were also established during mobilization. Honeywell and Amec Foster Wheeler shared office space in the southern portion of the existing building at Site 125 (60 Kellogg Street) from the beginning of mobilization in March 2013 until February 2016. Once Honeywell and Amec Foster

Wheeler moved out of the office space at Site 125, a set of permanent office trailers was established in the northeast corner of SA-6 North.

Water for construction and dust suppression activities for both SA-6 North and SA-6 South was obtained from a JCMUA fire hydrant located on SA-6 North.

Additionally, the CWTP was constructed between the former JCMUA Sludge Digesters and the JCDPW "H" building. The construction of the CWTP is described in more detail in Section 6.3. SA-7 was used for the staging of incoming clean materials including surcharge fill and geosynthetic materials. Equipment staging, parking, truck staging, and other storage was located in available areas.

## 2.6 TRAFFIC CONTROL

Onsite traffic associated with remedial activities was controlled by using designated routes established in the 100% Design and DC 2016-05-06. A paved, perimeter road was established on SA-7, which provided access to both SA-6 South and SA-6 North. Temporary ramps were built out of clean fill for transport between elevation changes on both SA-6 South and SA-6 North. These routes were marked using orange construction fence, traffic barricades, jersey barriers, signage and/or other types of traffic control devices.

Offsite truck traffic routes were consistent with routes previously approved for SA-7 and SA-5 remediation projects. The offsite truck routes used are indicated on **Figure 5**.

## 2.7 DEMOLITION

In accordance with a Site Preparation Plan prepared for SA-6 South, dated November 1, 2011, buildings were demolished on SA-6 South as part of the SA-6 Chromium Remedy as listed below.

| NJDEP Site No. | NJDEP Site Name | Feature(s) |
|---|---|---|
| 125 | Delphic Consolidated | 1 Building |
| 134 | Boatyard | 1 Building |
| 140 | ABF Trucking | 4 Buildings |
| 163 | Posnak & Turkish | 2 Buildings |

Prior to demolition, each impacted facility was evaluated for inventory, hazardous material survey/characterization, removal/abatement, decommissioning, and demolition. Viable products remaining at the facilities were shipped to other facilities that could either use, store, or manage the product. Decommissioning included the cleaning of equipment, piping, and storage vessels; the management, removal, and recycling of the tank bottom sludge, if any; abatement of environmentally sensitive building materials (such as asbestos containing building materials); and removal of Universal Wastes such as mercury devices, refrigerant, lamps, light ballasts, and batteries. Buildings and above-ground storage tanks were demolished and equipment, piping, and materials removed from SA-6 South. Demolition permits were received prior to ground intrusive work.

## 2.8 UTILITY ABANDONMENT

Utilities at SA-6 South included gas, electric, telephone/internet, water, storm and sanitary sewer which serviced SA-6 South. Utilities that crossed into the excavation areas were removed. Additionally, a section of storm sewer adjacent to Site 140 along Kellogg Street was replaced and a new catch basin was installed as shown on the Record Drawing, entitled "As Built Restoration Plan."

## 2.9 GROUNDWATER TESTING FOR pH

During the mobilization phase and early stages of the Chromium Remedy implementation and prior to ground intrusive activities, Amec Foster Wheeler collected groundwater pH readings from 13 different locations along the proposed hydraulic barrier wall alignments at SA-6 South. The groundwater pH measurements were necessary to determine the type of sealant material that was suitable for the hydraulic barrier (sheetpile) joints.

Groundwater pH values above 11.5 standard units required a cement-bentonite grouted seal. **Figure 6** shows the measured pH values at each SA-6 North and SA-6 South location and stationing along the hydraulic barrier wall alignments. Section 10 details the installation of the hydraulic barrier and sealing of its joints.

The pH monitoring was performed in accordance with the methodology documented in a technical memorandum, dated August 12, 2013 and submitted by Honeywell to All Parties. All pH monitoring was performed in the fill above the meadow mat

(Stratum D). Groundwater measurements were collected by Amec Foster Wheeler personnel certified with the NJDEP Office of Quality Assurance to perform field analysis of non-potable water for specific conductance, turbidity, dissolved oxygen, pH and temperature.

## 2.10 WASTE CLASSIFICATION

The *Proposed In Situ Waste Classification and Disposal Facility Approval Sampling Plan* (Amec, 2013) established a protocol for the sampling and analysis of the estimated 25,120 CYs of potentially chromium-impacted material that was planned to be disposed offsite from both SA-6 North and SA-6 South. Materials containing hexavalent chromium >240 mg/kg at SA-6 North or >1,000 mg/kg at SA-6 South were designated for offsite disposal as shown on **Figures 7A through 7G**.

In order to properly classify the material for offsite disposal, the NJDEP *Waste Classification Request Form and Instructions* dated June 22, 2009 were used as a reference for the specific sampling frequency and analysis for the waste classification protocol in addition to any receiving disposal facilities' acceptance criteria.

In addition to the hexavalent chromium impacted soil, SA-6 South contained non-chromium impacted soil with other COCs. In some locations, the soil exhibiting the non-chromium COCs was co-mingled with the potentially chromium impacted material, although typically not with the higher hexavalent chromium concentrations that required offsite disposal. Therefore, waste characterization samples were also collected from those AOCs at SA-6 South that contained the non-chromium COCs, using the same two-part compositing procedure for chromium-impacted areas designated for offsite disposal. The results were compared to RCRA hazardous limits. This sampling protocol was used by Honeywell to properly classify the material and obtain disposal facility approvals as needed.

# 3.0 MODIFICATIONS AND FIELD CHANGES TO SA-6 SOUTH 100% DESIGN REPORT

Throughout the course of the implementation of the SA-6 Chromium Remedy, it was occasionally necessary to make modifications to the SA-6 South 100% Design Report based upon unforeseen field conditions and/or provide further detail to conceptual design items. Design changes were documented in DCs. Design changes are classified as either major or minor, where major DCs were defined as those that could significantly impact cost and schedule and minor DCs as those having minimal to no impact to cost and schedule.

DCs were issued using sequential numbering starting with DC 000. A single combined DC log was maintained for SA-6 South and SA-6 North (see **Appendix D**). Some DCs applied to both sites. For purposes of the Special Master process a separate numbering system was maintained. The DC Log provides a cross reference to the Special Master numbering.

During the course of the project a number of requests for information (RFIs) were received from the contractor. These RFIs sought clarification on specific areas of the SA-6 South 100% Design Report. Responses to all requests were provided. In the cases where a RFI resulted in a design change an associated DC was prepared and issued.

# 4.0 DEFERRED AREAS

As discussed in the Executive Summary, and Sections 1.4 and 4.5.2, there are two areas within the SA-6 South Development AOC where excavation was technically impracticable during implementation of the SA-6 Chromium Remedy. Remediation of these areas will be deferred until a later time.[8] In the meantime, Honeywell will establish deed notices on both areas until remediation can be completed. These two areas are shown on **Figure 19** and are referred to as the Route 440 ROW and Site 073 Bulkhead Deferred Areas, corresponding to Deed Notice Area 2 and Deed Notice Area 4, respectively. Honeywell will document the remediation of each Deferred Area with a supplement to this CCR after the completion of the remedial work in each Deferred Area.

Deed Notice Area 2 is an approximately 1,300 SF strip of land on SA-6 South between the eastern boundary of the SA 6 South Open Space AOC (eastern hydraulic barrier) and the Route 440 ROW. Public Service Electric & Gas (PSE&G) owns and operates a 24-inch high pressure gas main within the ROW in this area. Honeywell inquired of PSE&G and New Jersey Department of Transportation (NJDOT) about the potential relocation of a portion of this gas main and determined that utility relocation should be deferred pending the comprehensive Route 440 Road Widening Project which is currently in the design phase. Consequently, a portion of the eastern SA-6 South hydraulic barrier was relocated approximately 10 feet westward in this area. The Route 440 Road Widening Project is expected to commence no later than 2019, three years from the completion of the Chromium Remedy. Honeywell will continue to monitor NJDOT and PSE&G progress on the Route 440 Road Widening Project and will address residual chromium contamination proximate to the gas line when relocated in the future for the Route 440 improvements.

As indicated in Section 4.1 of the SA-6 South 100% Design Report, the hydraulic barrier alignment was moved approximately 10 feet to the west to avoid impacts to the gas main. Consequently, this approximately 15-foot wide portion of SA-6 South

[8] In the event that the Route 440 road widening project and the bulkhead repair project are not completed by the end of 2021 (five years after completion of the SA-6 Chromium Remedy), the Parties will confer regarding appropriate action for the Deferred Areas.

was then outside of the hydraulic barrier/cap of the Open Space AOC. As indicated in Section 4.1 of the SA-6 South 100% Design Report, Honeywell indicated its intention to defer excavation of chromium-impacted soil within the Deed Notice Area 2 footprint until such time that the gas main is relocated during the Route 440 Road Widening Project. Excavation of residual chromium-impacted soil between the eastern hydraulic barrier and the SA-6 South property line in this area will be coordinated with the relocation of the gas main during the Route 440 Road Widening Project. In the meantime, Honeywell will institute a deed notice on this area. Once the remediation of this area is complete and achieves soil RAOs, Honeywell will terminate the deed notice. A draft of the deed notice is contained in **Appendix R**.

Deed Notice Area 4 is comprised of two tracts of land; Tract 1[9] is on SA-7 and Tract 2 is on a portion of Site 073 on SA-6 South. Tract 2 will be discussed further herein. Tract 2 is an approximately 11,600 SF area adjacent to the bulkhead partially between the western boundary of the SA 6 South Open Space AOC (western hydraulic barrier) and the bulkhead and partially south of the SA-6 South Open Space AOC. The SA-6 South 100% Design plan for the Site 073 deferred area was to excavate the top 4 feet of soils within the deferred area and defer additional excavation below a depth of 4 feet until implementation of the Bayfront Redevelopment Plan when the bulkhead will either be repaired or replaced. Because an approximately 5-foot thick concrete slab was unexpectedly encountered while excavating in this area and because removal of this concrete would jeopardize the integrity of the bulkhead, DC 2014-5-19 proposed deferral of *all* excavation in this area until implementation of the Bayfront Redevelopment Plan. The proposal to defer remediation was approved by all parties and the Special Master under the SA-6 South Consent Decree. Excavation of residual chromium-impacted soil along the bulkhead in Tract 2 will be coordinated with bulkhead improvement work to be implemented during the Bayfront Redevelopment Project. In the meantime, Honeywell will institute a deed notice on this area (both Tracts 1 and 2 together in

[9] Tract 1 on SA-7 is the "Technically Impracticable Area or TI Area" identified in the SA-7 RAR. NJDEP issued a conditional No Further Action letter for SA-7 soils, excluding the TI Area. Soils within Tract 1 met the Final Judgment cleanup objective of 240 mg/kg for hexavalent chromium for SA-7, but did not meet the 20 mg/kg objective in the NJDEP Chromium Policy. Soils exceeding the 20 mg/kg objective for hexavalent chromium are covered by at least 7 feet of clean soils. Tract 1 will not be remediated by Honeywell. Instead, the 7-foot thick clean soil cap will remain in place and Tract 1 will be subject to a Deed Notice.

Deed Notice Area 4). Once the remediation of the Tract 2 area is complete and achieves soil RAOs, Honeywell will terminate the deed notice for Tract 2. Tract 1 will continue to be subject to a deed notice. A draft of the deed notice is contained in **Appendix R**.

It is not anticipated that the Bayfront Redevelopment Project will impact Deed Notice Area 2 because this area is so narrow, is proximate to the Route 440 ROW, and the gas main is located within the area. Development of this area will be deferred until the gas main is relocated. The Bayfront Redevelopment Project bulkhead reconstruction will impact Deed Notice Area 4. However, once appropriate permits are obtained for the bulkhead reconstruction and the embankment in this area is secured, the remediation of chromium-impacted soil in Tract 2 of Deed Notice Area 4 will be implemented in connection with the Bayfront Redevelopment Project.

# 5.0 UNANTICIPATED ITEMS ENCOUNTERED DURING REMEDIAL ACTIVITIES

During excavation activities at SA-6 South, numerous unforeseen subsurface features, conditions, or structures were encountered requiring actions not included as part of the SA-6 South 100% Design including the following:

- A larger than expected quantity of miscellaneous concrete building slabs, and foundations;
- Arsenic-impacted asphalt;
- Debris co-mingled as part of the historic fill;
- Hydrocarbon-impacted soil;
- Three unregistered underground storage tanks (USTs); and
- Discontinuities related to penetrations, vertical cracks, and vertical shear zones of Stratum D.

Additional sampling was conducted that included:

- An initial post-remedial quarterly groundwater sampling event;
- Soil sampling in the Site 073 deferred area; and
- Soil sampling of anomalous material as described in Sections 8.6 and 8.7.

Descriptions of these items, with the exception of anomalous material sampling, are provided in the sections below.

## 5.1 CONCRETE BUILDING SLABS, FOUNDATIONS, ARSENIC-IMPACTED ASPHALT, DEBRIS

A larger than expected volume of concrete building slabs, foundations, and debris from previous structures were encountered. Concrete and arsenic-impacted asphalt was sampled, analyzed, evaluated, and handled in accordance with the NJDEP-approved Soil Management Plan (SMP) which was part of the 100% Design Report and the *Proposed Concrete and Asphalt Sampling Plan* (CASP), dated September 2013 which was submitted to the NJDEP on October 28, 2013. The SMP allowed

concrete meeting NJDEP reuse parameters to be reused onsite as backfill in excavations or placed in the Open Space AOC with consolidated chromium-impacted soil. Most of the concrete that met the reuse criteria was sized to 3-inch minus for reuse by Entact in accordance with the SA-6 South 100% Design Report. Details concerning the sampling, testing, and disposition of the concrete material are contained in Section 9.

As part of the SA-6 Chromium Remedy, Entact collected 16 samples (Asphalt-001 through Asphalt-016) of the existing asphalt pavement throughout the excavation footprint at SA-6 South in accordance with the September 2013 CASP. The sampling procedures followed are detailed in **Appendix J-1**. The locations of the asphalt samples are shown on the figure provided in **Appendix J-1**. The quantity of asphalt represented by the samples was approximately 1,250 CYs or 2,100 tons. The purpose of the sampling was to determine the disposition of the asphalt in accordance with the NJDEP-approved SMP. Upon approval by the NJDEP, all of the arsenic-impacted asphalt was consolidated in both SA-6 North and South Open Space Areas.

A larger volume than expected of debris was encountered comingled with soil in the eastern (Sites 124 and 125) and central (Site 134) portions of the SA-6 South excavation areas. The composition of the debris and soil separation procedures are described in **Appendix J-1**. The debris-free soil was then considered suitable for reuse or consolidation in both SA-6 North and South Open Space Areas. The debris was disposed of offsite, totaling 315 tons.

## 5.2 HYDROCARBON-IMPACTED SOIL AT SA-6 SOUTH

Hydrocarbon-impacted soil was first encountered during the excavation at Site 124 and continued into Site 125 in the eastern part of SA-6 South. Additionally, hydrocarbon-impacted soil was encountered at Site 073 and Site 134 in the western part of SA-6 South. These materials were identified by their odor and elevated photo-ionization detector (PID) readings in the work zone. Entact segregated and stockpiled the hydrocarbon-impacted soil based upon the hexavalent chromium concentration ranges depicted in the design. Amec Foster Wheeler and Honeywell evaluated options for addressing the hydrocarbon-impacted soil with NJDEP as described in **Appendix J-2**.

This evaluation determined that any VOCs and naphthalene that were below their respective NJDEP inhalation-based residential standards would not pose an unacceptable inhalation risk or cause nuisance odors if the hydrocarbon-impacted soils were consolidated and capped in the Open Space AOC as approved by the NJDEP and indicated in DC 2014-10-28. Hydrocarbon-impacted soils that did not meet the NJDEP inhalation-based residential standards were shipped offsite for disposal.

The following summarizes the disposition of the hydrocarbon-impacted soil encountered at SA-6 South, see Appendix J-2 for additional details:

- Approximately 48,150 CYs of hydrocarbon-impacted soil co-mingled with <1,000 mg/kg of chromium-impacted soils was encountered, stockpiled, and sampled/characterized at SA-6 South.
- Of this, 39,200 tons (approximately 25,750 CYs) of hydrocarbon-impacted material was shipped offsite for disposal for excessive debris or based upon an evaluation of inhalation risk described above.
- The remaining approximately 24,000 CYs of hydrocarbon-impacted soil were consolidated in the Open Space AOC (cap area) at SA-6 South upon approval by NJDEP as described below.

## 5.3 USTS ENCOUNTERED AT SITE 134 AT SA-6 SOUTH

During the course of chromium-impacted soil excavation activities at Site 134 located in the Kellogg Street Development AOC, three, unknown USTs were discovered in succession between June 30, 2014 and July 3, 2014. Upon discovery, Honeywell immediately notified their LSRP, Mr. Peter Jaran, P.E. of Equity Environmental Engineering, LLC (Equity), who is overseeing remediation of the non-chromium AOCs. Upon consultation and oversight by the LSRP, Honeywell authorized Entact to remove the USTs. Entact removed the USTs from the ground on July 1, 2014, July 7, 2014, and July 9, 2014 respectively. Since the tanks were previously unregistered, the LSRP registered the tanks with NJDEP.

Each of the USTs measured approximately 5-feet in diameter and 24 feet in length (approximately 3,500-gallon capacity). Given the length and depth of the USTs, six post-excavation soil samples were collected from 8 feet bgs and analyzed for appropriate parameters for USTs of unknown origin in accordance with the TRSR.

Since the use/former contents of the USTs were unknown, the tanks were treated as Category 2 tanks per NJDEP's "Protocol for Addressing Extractable Petroleum Hydrocarbons" (EPH Guidance) for investigation/remediation purposes.

Additional details concerning the three USTs encountered at Site 134 at SA-6 South are contained in the report *Underground Storage Tank Remedial Action Report* (UST RAR), dated January 2015 prepared by Equity and Amec Foster Wheeler on behalf of Honeywell. The LSRP submitted the UST RAR to NJDEP on November 13, 2015 and issued the Remedial Action Outcome on May 21, 2015.

## 5.4 STRATUM D REPAIR

During the development of the 100% Design, a geotechnical investigation was conducted to determine the elevation and thickness of the meadow mat (Stratum D) that underlies SA-6 South. A Geotechnical Investigation Report (Geotechnical Report) was included as Appendix C of the SA-6 South Chromium Remedy 100% Design Report and provided the details of the characteristics and incidence of Stratum D. In summary, Stratum D is a native marsh deposit consisting of organic silt/clay and peat with an average permeability of 4.8 x 10-7 cm/sec (as reported in the Geotechnical Report). Due to its low permeability, Stratum D plays an important role in preventing vertical migration of contaminants from the fill material overlying Stratum D to the native material aquifer below and establishing hydrogeologic flow characteristics of the shallow groundwater perched atop the Stratum D. No breaches or discontinuities of the Stratum D were documented in the SA-6 South Geotechnical Report.[10] However, several isolated discontinuities of Stratum D within SA-6 South were encountered during excavation.

The 100% Design for SA-6 South did not address Stratum D repair. However, upon encountering the isolated discontinuity in Stratum D in cells 76 to 77 at SA-6 South, Honeywell informed the Special Master and the Parties that the identified discontinuity was discovered and recommended a method of repair of this discontinuity in Stratum D in an email dated November 5, 2014 (see **Appendix S**).

[10] In contrast, the SA-6 North Geotechnical Report, Appendix B to the SA-6 North Chromium Remedy 100% Design Report, documented breaches of the Stratum D in the area known as the JCIA Pit. As a result, the SA-6 North 100% Design required repair of the Stratum D in accordance with Specification Section 02180.8 Special Instructions – Repair of Stratum D on SA-6 North.

The repair of Stratum D at each discontinuity location was necessary to maintain integrity of the Stratum D as a confining layer. Therefore, the Stratum D discontinuities encountered during the excavation were repaired using a GCL in accordance with applicable sections of Specification Section 02180.8 Special Instructions – Repair of Stratum D on SA-6 North, as agreed to by the Parties.

During the course of the remaining chromium-impacted soil excavation activities at SA-6 South, similar repairs to Stratum D were necessary in the following situations:

- On several occasions pilings that penetrated the Stratum D were removed inadvertently in the excavation process
- In several locations, vertical cracks were observed in the Stratum D; and
- In one location, there appeared to be a vertical shear zone resulting in an offset in the Stratum D.

In each Stratum D repair location, GCL was placed over, and extended at least 3 feet beyond the repair area to provide continuity to the Stratum D layer. The location of the repairs was surveyed and noted on the Entact drawing titled SA-6 South Cap Panel Layout 60 mil Textured LLDPE Geomembrane in **Appendix C**.

## 5.5 ADDITIONAL SAMPLING CONDUCTED

Two additional sampling events were implemented as the Chromium Remedy at SA-6 South was being completed. These additional sampling events included:

- Three post-remedial quarterly groundwater sampling events;
- Soil sampling along the bulkhead to further define the area of deferred excavation at Site 073; and
- Soil sampling of anomalous material as described in Sections 8.6 and 8.7.

Each of these additional sampling events are described in the Sections below.

### *5.5.1 Quarterly Groundwater Sampling*

Twelve new monitoring wells were installed within the Development AOC as described in the SA-6 South 100% Design, Appendix D and in CCR Section 7.0. The initial quarterly groundwater sampling of one existing monitoring well located on

Site 163 and the 12 new monitoring wells was conducted from April 6 through 8, 2016 to evaluate the condition of groundwater in the Development AOC following the excavation of the chromium-impacted soils from that area. The second quarterly groundwater sampling event was conducted July 5 through 7, 2016. The third quarterly sampling event was conducted October 4 through 6, 2016. Technical memoranda summarizing each event including the analytical results are included in **Appendix J-3**.

A summary of the analytical results from the three groundwater sampling events is as follows:

- The only instance of hexavalent chromium detected above the laboratory reporting limit of 5.5 µg/L was in the unfiltered and filtered samples of 140-MW-10 during the October 2016 event. Both concentrations were below 70 µg/L total chromium,
- Total chromium was detected above the laboratory reporting limit of 10 µg/L in unfiltered samples at 9 of the 12 locations and in filtered samples at only 2 of the 12 locations.
- Total chromium was detected above the GWQS of 70 µg/L in the unfiltered samples collected from:
    - 125-MW-03 (July only);
    - 134-MW-04 (April only);
    - 140-MW-09 (April, July, and October).
- Total chromium was detected above the GWQS of 70 µg/L in the filtered samples collected from 140-MW-09 only in July and October.

The October sample from 140-MW-09 was also filtered through a smaller filter size (0.1 micron) in addition to the standard filter size (0.45 micron). The objective of the extra filtering was to evaluate whether trivalent chromium detected in the monitoring wells during the previous sampling event is complexing on colloidal particles smaller than the standard 0.45 micron filters. Total chromium was below the GWQS of 70 µg/L in the sample filtered through the smaller filter, indicating that smaller particles are contributing to the higher total chromium results. Since all chromium-impacted soil has now been excavated from the Development AOC at

SA-6 South and monitoring well 140-MW-09 is located within an area of historic fill, differences between total chromium and hexavalent chromium may be associated, at least in part, with non-COPR sources of chromium such as historic fill or other historical industries in this part of SA-6 South.

The groundwater total and hexavalent chromium results represent a marked improvement in groundwater quality as compared to pre-remediation conditions, particularly in the eastern portion of SA-6 South at Site 124, where total chromium concentrations had been as high as 137,000 µg/L and hexavalent chromium concentrations had been as high as 6,400 µg/L. For comparative purposes, Figure 8 from the NJDEP-approved SA-6 South Chromium SRIR/RASR/RAWP and Figure 8 from the SA-6 South Pre-Design Investigation Summary Report as part of the SA-6 South 100% Design showing groundwater total and hexavalent chromium results in groundwater samples collectively from 1997 to 2010 are provided in **Appendix G**.

### *5.5.2 Verification Sampling at Site 073 Bulkhead Deferred Area*

The SA-6 South 100% Design plan for the Site 073 Bulkhead Deferred Area, shown on **Figure 19**, was to excavate the top 4 feet of soils within the deferred area and defer additional excavation below a depth of 4 feet until implementation of the Bayfront Redevelopment Plan when the bulkhead will either be repaired or replaced. Because an approximately 5-foot thick concrete slab was unexpectedly encountered while excavating in this area, DC 2014-5-19 proposed deferral of *all* excavation in this area until implementation of the Bayfront Redevelopment Plan. The proposal to defer remediation was approved by all parties and the Special Master under the SA6 South Consent Decree.

Additional soil borings were conducted in the Site 073 Bulkhead Deferred Area to further investigate the extent of subsurface concrete slabs in the area and characterize hexavalent chromium concentrations in soil in this area for use during the deferred excavation during bulkhead improvements. The additional soil borings in the Site 073 Bulkhead Deferred Area were conducted in two phases with additional details described in **Appendix J-4**. The first phase, consisting of two borings, 073-SB-101 and 073-SB-102, was conducted on May 5 and 6, 2014. The second phase, consisting of four borings, 073-SB-103 through 073-SB-106, was conducted on May 9 and 10, 2016. The locations of all six borings are shown on **Figure 8A** as well as other proximate PDI borings drilled in the deferred area and boring logs are contained in **Appendix H**. The analytical data for hexavalent

chromium are summarized in **Table 6C** and confirm conditions in the deferred area based upon RI and PDI sample results.

# 6.0 DEWATERING AND CONSTRUCTION WATER TREATMENT

## 6.1 GENERAL

Dewatering was conducted to remove groundwater and stormwater from within the excavation areas and to minimize the moisture content of excavated soils. Capture, collection, and treatment of stormwater/surface water that came in contact with impacted soils was also completed. Collected groundwater, stormwater, and surface water was pumped to the CWTP installed on SA-6 North.

For management of stormwater, diversion berms were installed upgradient of excavation areas and within large excavation areas as needed to divert the flow of surface water away from open excavation areas. Additional controls used to minimize the volume of water requiring treatment included extending sheetpile to elevation 10.7 feet based on the National Geodetic Vertical Datum 1929 (NGVD29), sealed jersey barriers, and minimizing the open excavation between the excavation face and the backfill.

Wastewater collected at designated decontamination pads was also collected and pumped to the CWTP for treatment.

## 6.2 EXCAVATION DEWATERING/PUMPING

Excavation dewatering in the Development AOC was accomplished with a combination of shallow well points, and localized sumps and pumps installed above Stratum D and deep wells installed below Stratum D.

### *6.2.1 Well Installation*

Shallow well points and deep wells for dewatering above and below Stratum D in the Development AOC were drilled and installed by B&B Drilling, Inc. (B&B Drilling), a licensed New Jersey well driller, in accordance with N.J.A.C. 7:9D. The shallow well points and deep dewatering wells are shown on the Excavation De-Watering Layout 03/15/16 figure provided by Entact contained in **Appendix C**. Deep dewatering wells within the main SA-6 South excavation area were given the designations DW-1 through DW-5. A sixth deep dewatering well (DW-8) was also installed within the deeper chromium-impacted soil excavation area at Site 163.

As shown in the Excavation De-Watering Layout figure in **Appendix C**, approximately 18 interior shallow well point systems (H-1 to H-18) were installed horizontally or vertically within the excavation footprints as excavation progressed across the phases. A row of perimeter well points were installed along the boundary of the SA-6 South excavation area with the exception of an area where temporary sheetpile was installed. The temporary sheetpile is shown on the Excavation De-Watering Layout figure in **Appendix C.**

Shallow well points were covered under the Temporary Dewatering Permit obtained from NJDEP. Deep dewatering wells constructed through Stratum D (confining layer) required permits for the deep wells. Well records for the deep wells are included in **Appendix E**.

The deep dewatering wells were drilled and installed by B&B drilling using a hollow-stem auger rig. Each deep well was drilled through the Stratum O/D layer to a total depth of up to 50 feet bgs, 32 to 33 feet below the top of the Stratum O/D layer. A 6-inch diameter screen and riser pipe were used in the construction of each deep dewatering well. Screen lengths were 25 feet long in each. A 10-inch diameter steel conductor casing was set 1 to 2 feet into the top of the Stratum O/D layer to isolate water above the Stratum O/D layer from that below.

Shallow well points were installed by B&B Drilling. Shallow well points consisted of a 2.5" slotted polyvinyl chloride (PVC) well casing with filter pack placed around the slotted screen and a 1.5" PVC interior drop tube. The well casing was advanced to 2 feet below the anticipated bottom of the excavation or to the top of the Stratum D layer using hollow-stem auger drilling methods. Each well point was equipped with a control valve and was connected to a header pipe (H-1 to H-18) via flexible hoses which connected to the electrically driven vacuum stations. The interior well points system was connected to the header pipes in a staggered row pattern to maximize the radius of influence. The perimeter well points were connected to a common header pipe in a single row.

Well component specifications were submitted by Entact to Amec Foster Wheeler for review and approval prior to installation. Shallow well points within the excavation areas were removed with the excavated soils. Deep dewatering wells were abandoned by B&B Drilling's licensed driller once an adequate amount of backfill

placement and compaction within an area was complete. Abandonment reports are included in **Appendix F.**

To determine the depth of the Stratum D at header locations, B&B Drilling drilled investigatory boreholes at a frequency of one sample per 50 lineal feet of the header pipe and collected core samples from each to determine the actual bgs depth of the Stratum D layer prior to installing interior and perimeter well points. Boreholes were offset approximately 10 feet from the well point location to protect the integrity of the well point. The boreholes were advanced with the drill rig to within 4 feet of the assumed Stratum D layer. The remaining 4 feet were advanced using a 2-foot-long split-spoon sampler to retrieve core samples. The core samples were evaluated by Amec Foster Wheeler to determine if the Stratum D layer was encountered. Soil boring logs are included in **Appendix H**. At the completion of sample collection, the depth of the observed Stratum D layer or termination point of the borehole was recorded and the borehole was grouted. The data collected during the split-spoon sampling event was evaluated to determine the depth at which the dewatering well points would be driven to effectively dewater excavation areas within breaching the Stratum D layer.

### *6.2.2 SA-6 South Dewatering/Pumping System*

The general process for managing water was to prevent water from contacting chromium-impacted fill materials. However, this was not possible for activities performed below the groundwater table and where surface water/stormwater and incidental precipitation fell on active excavation areas, backfill areas, exclusion zones and contaminant reduction zones. Construction water was removed from remediation and support areas and stormwater that contacted chromium-impacted soils was removed using localized sumps and pumps. Sumps were installed at the low point within an excavation area and consisted of submersible pumps placed inside perforated pipe wrapped in geotextile liner and embedded in stone. Sumps were not installed below and did not penetrate the Stratum D layer and were constructed and relocated as needed as excavations proceeded. Stormwater and surface water collected in sumps was pumped to 21,000-gallon settling tanks to remove sediment and then to the CWTP.

The SA-6 South excavation in the Development AOC was dewatered in four phases corresponding with excavation sequencing. Dewatering with shallow well points and deep wells began in an excavation area and/or phase to achieve drawdown in

advance of excavation activities. Thus, shallow well points and deep wells were installed prior to the start of excavation activities to allow adequate time for groundwater removal. Dewatering data for both SA-6 North and SA-6 South is included in **Appendix I**.

## 6.3 CONSTRUCTION WATER TREATMENT PLANT

The CWTP for SA-6 North and SA-6 South was constructed west of the JCMUA Digestion Tanks on SA-6 North. The CWTP was constructed within a secondary containment system for spill prevention. The secondary containment consisted of a 40-mil high-density polyethylene (HDPE) geomembrane overlain with a 6-inch layer of 1-1/2-inch crushed stone. Class A geotextile liner was placed above and below the geomembrane. The 40 mil geomembrane panels were welded in the field. The secondary containment area had a perimeter berm constructed out of geotextile-covered jersey barriers. The CWTP consisted of approximately 300,000 gallons of untreated (influent) storage made up of eight, 21,000-gallon frac tanks manifolded together by flexible hoses and six additional frac tanks during the peak of excavation activities.

The CWTP had a dual treatment train composed of 50-micron and 5-micron bag filters with a maximum throughput capacity of 500 gallons per minute (gpm). Treated effluent water was pumped into the unused JCMUA South Sludge Digestion tank. The digestion tank was fitted with a gate valve to regulate discharge. The tank normally operated in a flow through condition. During precipitation events, the valve was closed and the digester used to provide an excess of 1 million gallons of temporary effluent storage. The effluent was discharged by gravity to the JCMUA wet well. The CWTP base components are shown in **Figure 9**.

The PVSC-required MR-1 and MR-2 self-reporting documents for the CWTP were completed and sent to PVSC each month, reporting for the prior month. The effluent sample analytical results for the monthly samples are summarized on **Tables 3A, 3B, and 3C**. **Table 3B** also shows the chromium analytical results in each effluent sample. The total chromium load discharge limit permitted by PVSC is 11 pounds per day. The discharge limit was not exceeded during implementation of the Chromium Remedy. Chemical treatment to remove chromium from the construction water was not required.

Commissioning and startup test procedures specified in the SA-6 South 100% Design Report were performed prior to initial discharge from the effluent tank. Entact oversaw operations and maintenance of the system during normal work hours. In the event that pumping was required during non-work hours, the system was manually operated by Entact personnel in the same manner as it was during work hours.

Upon completion of the SA-6 South and North Chromium Remedies, the CWTP was decontaminated, disassembled, and demobilized and residual solids and spent media generated as a result of the operation of the CWTP were sent offsite for disposal. Disposal manifests for the CWTP are included in the SA-6 North RAR.

## 6.4 GROUNDWATER LEVEL AND BASELINE GRADIENT MONITORING

The SA-6 South 100% Design Report requires that the groundwater levels within the SA-6 South Open Space AOC are to be maintained at lower levels than both SA-7 to the north and the Development AOC to the south in the post-Remedy condition. If monitoring indicates that this inward gradient is not being maintained, dewatering is to be conducted within the Open Space AOC to maintain compliance with the gradient requirements. The LTMP details the specific post-Remedy monitoring requirements, frequencies, and action steps depending on water level measurements.

Shallow groundwater levels were monitored within the SA-6 South Open Space AOC along the border with SA-7 SCB using three piezometers installed during the SA-7 remedy along the southern side of the SA-7 SCB wall as shown on **Figure 10**:

- 115-E1A-SO;
- 115-W3-SO; and
- 115-W5-SO.

Along the southern side of the SA-7 SCB wall, the standpipes that monitor perimeter pools S1 through S4 were utilized to determine the head against the north side of the SA-7 SCB wall. Elevation 4.0 feet, based upon the NGVD29 datum, is the lowest head elevation within the SA-7 site-wide underdrain system. Honeywell has installed water-level monitoring points within SA-7, which will be used in the determination of whether there is an outward gradient from SA-7 towards SA-6 South.

The SA-6 South 100% Design Report detailed the installation of 5 pairs of new piezometers along the SA-6 South hydraulic barrier. These piezometers allow long-term monitoring of the hydraulic gradient of the shallow groundwater zone between the Open Space AOC and the SA-6 South Development AOC. The 10 piezometers are:

- 124-PZ-11;
- 124-PZ-12.
- 124-PZ-13
- 124-PZ-14
- 124-PZ-15
- 124-PZ-16
- 124-PZ-17
- 124-PZ-18
- 124-PZ-19; and
- 124-PZ-20.

The locations of the 10 piezometers are shown on **Figure 10**. At each piezometer pair location, one piezometer is located inside of the SA-6 South hydraulic barrier and the other on the outside of the hydraulic barrier. The piezometers were constructed of 4-inch diameter stainless steel casing with a 5-foot-long screen set just above Stratum D. Record Drawing construction diagrams for the piezometers are contained in **Appendix E.**

Following installation of the geomembrane portion of the cap and initial drawdown of the contingent groundwater system, Amec Foster Wheeler conducted initial interim groundwater level monitoring during the 12-month transition period on a bi-monthly basis. In accordance with the LTMP and Groundwater Level Monitoring Plan, Honeywell provided notice to the Parties that long-term groundwater monitoring activities at SA-6 South were being initiated in November 2016 in correspondence dated November 7, 2016 (see **Appendix J-3**). To supplement the manual groundwater measurements to monitor the hydraulic gradient within the SA-6 South Open Space AOC compared to outside of it, data loggers were utilized at 124-PZ-19, 124-PZ-20, 115-W3-SO, 124-PZ-18, 124-PZ-17, MH-2, 115-W5-SO, 124-PZ-13, 124-PZ-14 and 115-E1A-SO. The results of the manual readings taken during the first event per month of the initial interim groundwater level monitoring

are provided in **Table 4**. The results indicate that the piezometers are performing as expected and an inward gradient is maintained at most piezometer locations without active pumping of the contingent groundwater system. However, at the western end of the Open Space AOC along the Hackensack River, the gradient, measured in 124-PZ-19 (exterior) and 124-PZ-20 (interior), is generally outward and fluctuates depending on tidal influences. Since manual water level readings only provide an instantaneous measure of head and do not capture the full tidal cycle, they may not be an accurate means of determining head gradients across the barrier wall at this location. Tidal fluctuations in PZ-20 at SA-6 South are in the range of 1.5 to 2.0 feet in amplitude with little or no lag from the river tides. By comparison, tidal fluctuations in the companion piezometer (PZ-19) are approximately 0.1 feet in amplitude. Tidal influences are not present at any of the other piezometer pairs at SA-6 South. As indicated below, samples from all interior piezometers were collected. The analytical results summarized in the November 7, 2016 correspondence indicates that the filtered and unfiltered groundwater samples from 124-PZ-20 were non-detect for both hexavalent and total chromium.

In response to Plaintiffs' request to establish baseline groundwater quality conditions inside the Open Space Areas, filtered and unfiltered groundwater samples were collected from each piezometer on the interior of both SA-6 North and SA-6 South. The samples were analyzed for total and hexavalent chromium. A summary of this data for the interior piezometers is included in **Appendix S**. The location of the piezometers is shown on **Figure 10**.

# 7.0 MONITORING WELL ABANDONMENT AND INSTALLATION

Selected monitoring wells at SA-6 South were abandoned during implementation of the SA-6 South Chromium Remedy in accordance with the Updated Monitoring Well Abandonment Plan submitted to NJDEP on April 20, 2017, which amended Appendix A-2 of the SA-6 North Chromium Remedy 100% Design Report. Minor DC 2014-6-6- provided clarification as to the wells requiring abandonment.

As discussed in Section 6.4, five pairs of new shallow piezometers were installed on either side of the SA-6 South hydraulic barrier to monitor hydraulic gradients across the barrier. Additionally, 12 new shallow groundwater monitoring wells were installed throughout the SA-6 South Development AOC to allow monitoring of groundwater conditions with respect to chromium in accordance with the Development AOC Shallow Groundwater Monitoring Plan (SGWMP) which was Appendix D of the SA-6 South 100% Design Report. The well logs are included in **Appendix H**.

Existing monitoring wells which are to be maintained in the Open Space AOC were raised to meet proposed grade and re-surveyed with revised Form B certifications included in **Appendix E**. These monitoring wells are shown on **Figure 10** and are the following:

- 115-E1A-SO;
- 115-W3-SO; and
- 115-W5-SO.

**Figure 10** shows the location of three types of monitoring wells at SA-6 South:

- Monitoring wells that existed prior to the start of the SA-6 Chromium Remedy and were abandoned;
- Monitoring wells that existed prior to the start of the SA-6 Chromium Remedy and were retained because they are still needed for ongoing and future groundwater monitoring, including those exclusively needed for non-chromium AOCs; and

- New monitoring wells installed for groundwater monitoring in the Development AOC at SA-6 South in accordance with the SGWMP.

The 12 new monitoring wells installed in the SA-6 South Development AOC are:

- 073-MW-06;
- 073-MW-07;
- 073-MW-08;
- 124-MW-12;
- 124-MW-13;
- 125-MW-02;
- 125-MW-03;
- 134-MW-03;
- 134-MW-04;
- 134-MW-V09R (installed in a non-chromium AOC);
- 140-MW-09; and
- 140-MW-10.

**Table 5** also lists the ID and current status of monitoring wells at SA-6 South.

All well abandonment activities were performed in accordance with N.J.A.C. 7:9D by a New Jersey licensed driller from B&B. Well abandonment records are included in **Appendix F**. Permits for new wells were obtained from the NJDEP by B&B. New well permits, Form A & B wells records, and new well construction diagrams are included in **Appendix E**.

# 8.0 EXCAVATION

Excavation of chromium-impacted soil was performed consistent with the NJDEP-approved RAWP, SA-6 South 100% Design Report, and subsequent DCs applicable to excavation. The excavation at SA-6 South was implemented only in the Development AOCs. Excavation was performed at SA-6 South from October 22, 2013 to June 2, 2016.[11] More details concerning the excavation sequence and schedule are provided in Section 8.3. A progression chart was maintained throughout the project that tracked excavation and backfilling operations showing zones for work sequence and quality control and was reviewed with all Parties at routine progress meetings/conference calls and was provided in the Monthly Progress Reports **(Appendix S)**. As excavation progressed, Honeywell periodically submitted to all Parties documentation of completion of portions of the excavation operations in accordance with the SA-6 South Standard Operating Procedure - Confirmation of Excavation Limits, dated March 3, 2014 (and including Honeywell's April 24, 2014 letter and attachments) for acknowledgement by the Special Master prior to commencing backfilling. The excavation completion correspondence is included in **Appendix S**. Record Drawings for excavation and backfill work are included in **Appendix C**.

## 8.1 TEMPORARY EXCAVATION SUPPORT

Temporary excavation support consisting of sheetpile was installed as shown on SA-6 South Temporary Support of Excavation Plans (S-501 to S-504) as prepared by Honeywell's geotechnical consultant, MRCE, and in accordance with SA-6 South 100% Design Report Specification Section 02150 to stabilize certain portions of the excavation areas adjacent to roadways or other critical infrastructure. The temporary excavation support was removed when possible. Areas where the temporary excavation support remains are shown on the Entact drawing titled "As Built Restoration Plan" in **Appendix C**. The temporary excavation support systems consisted of 2807 Hoesch Larssen Z sheetpile installed at the following locations:

[11] Declaration #1 describes the excavation period as October 22, 2013 to December 22, 2014. The time period described in this CCR includes the excavation of areas of Site 163 originally intended for in-situ treatment (see Section 12), and excavation of anomalous materials at 60 Kellogg Street (see Section 8.7) which came after the issuance of Declaration #1.

| SA-6 South Excavation Area |
|---|
| Site 124 – Jughandle at Route 440 |
| Site 140 – Kellogg Street |
| The property boundaries between Site 163 and Site 073 and Site 134 |
| Site 163 Development AOC – Additional Deeper Excavation |

The Entact Quality Control Engineer monitored the temporary excavation supports for horizontal deflection during excavation. The SA-6 South 100% Design Report also mandated the need for vibration monitoring when sheeting was being driven at the Route 440 jughandle and in close proximity to underground utilities. Vibration monitoring is discussed further in Section 10.2.

## 8.2 EXCAVATED SOIL MANAGEMENT

Excavated soil was managed onsite in accordance with the NJDEP-approved SMP and the approved soil erosion and sediment control plan. Prior to the start of the Chromium Remedy, as part of the PDI, post-excavation equivalent samples were collected and boring locations were surveyed (see the PDI Results and Mapping Report in Appendix A of SA-6 South 100% Design Report). The post-excavation equivalent samples established the horizontal and vertical limits of the chromium-impacted soils and, thus, defined the extent of the excavations for most of the site. Additional post-excavation sampling was required to confirm excavation limits upon encountering isolated incidences of anomalous material under the office portion of the 60 Kellogg Street building south of the 20 mg/kg line delineated during the PDI, and along isolated locations of excavation sidewalls or bottoms at Sites 073, 125, 134, and 140 as documented in Section 8.6. Other than these instances, the PDI allowed for the excavation limits of soils exhibiting hexavalent chromium >20 mg/kg to be more definitively determined during the design phase and implemented in the field and is a process that has been accepted by the NJDEP in the RAWP and has been implemented successfully by Honeywell at other sites. Additionally, considering the PDI samples as post-excavation equivalent samples minimized the collection of traditional confirmatory samples following completion of excavation, and eliminated the associated logistical and scheduling impacts.

The PDI sample hexavalent chromium results also established the designation and final disposition of the excavated material. Entact adopted four designations for

tracking and management purposes based upon their hexavalent chromium concentrations as follows:

- **A Material**: <20 mg/kg hexavalent chromium;
- **B Material**: 20 to 240 mg/kg hexavalent chromium;
- **C Material**: 240 to 1,000 mg/kg hexavalent chromium; and
- **D Material**: >1,000 mg/kg hexavalent chromium.

As provided in the SMP and SA-6 South 100% Design Report:

- **A Material** was stockpiled and tested to confirm its designation and, if confirmed, reused as backfill. If sample results of the A Material stockpiles, or portions of stockpiles, indicated one of the other designations, then the material represented by such samples was managed accordingly. **Table 9** is the Stockpile Tracking Table.
- **B Material** was consolidated in either the SA-6 North or SA-6 South Open Space Areas.
- **C Material** was consolidated in the SA-6 South Open Space AOC only.
- **D Material** was stockpiled and tested to verify whether the sample exceeded 1,000 mg/kg for hexavalent chromium. If confirmed, the material was shipped offsite for disposal. If sample results of the D Material stockpiles, or portions of stockpiles, indicated one of the other designations, then the material represented by such samples was managed accordingly.

As part of the means and methods developed by Entact, the excavation in the Kellogg Street Development AOC was divided up into 156 15-foot wide cells for tracking, management, and reporting purposes (see Entact Figure 1.3 Excavation Cell Layout in **Appendix C**). Drawings C-112 – C-120, Chromium Excavation Interval drawings (included in this CCR as **Figures 7A-7G** and entitled "Waste Classification Sample Locations Chromium Sampling Interval [X]"), delineated the limits of each type of waste material. Based upon the PDI data, these drawings show four soil designations depending on the hexavalent chromium concentrations. These area designations allowed Entact to segregate and manage the excavated material as they were encountered within the cells as excavation progressed. The

PDI sample results established the elevations to which excavation was to be performed for an excavation cell or general area, with the understanding that if Stratum D (i.e., "meadow mat") was encountered or suspect material identified, the excavation could be halted at a shallower depth or expanded as necessary. For the reasons stated in Section 5.4 regarding the need to maintain the integrity of Stratum D, the excavations did not extend vertically below Stratum D.

Excavation was performed using hydraulic excavators directly loading into off-road articulated dump trucks (end dumps) to transport to designated on-site stockpiling areas. The end dumps did not leave SA-6 South, and were decontaminated if they were travelling out of an exclusion zone. The excavators were equipped with GPS equipment manufactured by Trimble®. Entact loaded X, Y, Z coordinates of the designed excavation limits into the GPS system and a transponder was attached to the bucket of the machine enabling the operator to precisely excavate in real-time to the design limits. Additionally, using the GPS and known coordinates differentiated the extents of the designation of various soils as shown on Design Drawings C-112 – C-120 based upon the concentration of hexavalent chromium. A summary of the total excavated volume of each waste material is provided in the quantity summary table in Section 1.6.

Stockpiles were placed on plastic sheeting liners at grade. Stockpiles of D Material were covered with plastic sheeting to minimize air-borne dust and stormwater runoff. As provided in the SA-6 South 100% Design Report, excavations and soil stockpiles were protected from flooding to the 100-year flood elevation (10.2 feet) based on the NGVD29 datum by one or more of the options provided in the NJDEP Coastal Area Facilities Act (CAFRA)/Flood Hazard Area (FHA) permit (see Section 15 for more details). Daily inspections of the liners and plastic sheeting were performed to minimize migration of chromium-impacted soils beyond the designated stockpile area.

## 8.3 EXCAVATION SEQUENCING AND SCHEDULE

Excavation in the Kellogg Street Development AOC began in excavation cell No. 1 at the east end of Site 124, adjacent to Route 440, and proceeded west to approximately cell No. 59 at the western side of Site 125. The westward progression of the excavation was halted there due to the presence of the original groundwater treatment plant (GWTP) built at 80 Kellogg Street in Site 140 during the SA-7 chromium remedy. The excavation activities were then shifted to cell No. 153 in Site

073 and proceeded to the east to Cell No. 81. Upon demolition of the GWTP at 80 Kellogg Street in March 2014 and the former ABF Trucking office and warehouse building at Site 140, the central portion of the excavation in cell Nos. 80 to 60 was completed.

The use of Cell designations was not part of the 100% Design, but rather a means and methods approach developed along with the contractor to track and report on incremental excavation progress in SA-6 South due to the large excavation footprint. While these Cell references were included in routine progress reporting, they are not relied upon for this as-built final documentation. All of the requirements of the 100% Design (including but not limited to surveying of excavation limits, surveying of post-excavation soil sampling locations, etc.) were developed for the excavation as a whole, and as such, the as-built information and final supporting documentation within this report is presented relative to attaining excavation requirements established in the 100% Design and not the incremental cells.

Excavation of the shallow chromium-impacted soils (nominally to 4 feet deep) in the Site 163 Development AOC began at the west end of Site 163 and proceeded to the east. Subsequent to completion of the shallow excavation in the Site 163 Development AOC, Honeywell excavated the deeper chromium-impacted soil in the Site 163 Development AOC Non-Deed Notice Area located within Site 163 to the north of the proposed curb line of the Riverside Park, Riverside Drive, and Kellogg Street (see DC 2014-5-6).

Additional excavation occurred within the Kellogg Street Development AOC in cell Nos 105 to 114 on Site 134, and under the 60 Kellogg Street Building slab, outside of the cell designations of the main excavation area, as discussed in Sections 8.6 and 8.7.

A summary of the excavation schedule is provided in the table below.

| Area Excavated | Start Date | End Date |
|---|---|---|
| Kellogg Street Development AOC (cells 1 through 156) and Site 163 Development AOC | October 22, 2013 | December 22, 2014 |

| Area Excavated | Start Date | End Date |
|---|---|---|
| (shallow excavation to 4 feet bgs) | | |
| Additional Excavation Area on Site 134 | November 12, 2014 | December 9, 2014 |
| Site 163 Development AOC Non-Deed Notice Area (deeper excavation) | December 28, 2015 | February 22, 2016 |
| Site 125 60 Kellogg St Building Area | June 2, 2016 | June 2, 2016 |

## 8.4 EXCAVATED MATERIAL (STOCKPILE) TESTING

In accordance with the SMP, stockpiles of A Material were managed onsite and sampled to confirm that the soil was <20 mg/kg for hexavalent chromium. A Material stockpiles ranged from 135 to 2,850 CYs. The volumes within individual stockpiles differed based upon site layout constraints and the contractor's preferences for advancing excavation and overall soil management. Once an individual stockpile was deemed completed, no further soil was added to the location and sampling commenced. Grab samples were collected from each stockpile for hexavalent chromium analysis at a maximum sampling frequency of 1 sample per 250 CYs in accordance with the SMP. If the hexavalent chromium concentration in any sample from a portion of a stockpile was equal to or greater than 20 mg/kg, that portion of the stockpile was isolated from the remainder of the stockpile and consolidated in the Open Space AOC. Stockpiled soil that was verified to contain <20 mg/kg hexavalent chromium, A Material, was approved for re-use as backfill in excavations. This approved-for-reuse A Material is still considered historic fill. At least 6 inches of imported clean backfill was placed over the reused A Material as needed to achieve the design grades. An institutional control (Restricted Area/Deed Notice) for the remaining historic fill soil will be filed in accordance with the NJDEP-approved RAWPs as part of an RAR for non-chromium impacts submitted by Honeywell's LSRP in December 2016.

Excavated soils designated as D Material (>1,000 mg/kg hexavalent chromium) from the PDI soil sampling were managed onsite and sampled to confirm hexavalent chromium levels. Grab samples were collected from each stockpile for hexavalent chromium analysis at a maximum sampling frequency of 1 sample per 250 CYs. If

the hexavalent chromium concentration in a sample from a portion of a stockpile was >1,000 mg/kg, then that portion of the stockpile was designated for offsite disposal as hazardous waste. Portions of stockpiles that were confirmed to be <1,000 mg/kg hexavalent chromium were consolidated under the SA-6 South Open Space AOC.

**Tables 2A and 2B** summarize the hexavalent stockpile sample analytical results.

## 8.5 EXCAVATION EXTENT SURVEYING AND EXCAVATION COMPLETION CONFIRMATION

As discussed in Section 8.2, post-excavation equivalent samples collected during the remedial investigation (RI) and PDI established the horizontal and vertical limits of the chromium-impacted soils and, thus, defined the extent of the excavations at SA-6 South. On January 30, 2012, Honeywell submitted a request and justification for a variance in post-excavation sidewall and bottom sample frequencies for SA-6 South to the default frequency mandated in the TRSR. NJDEP approved the alternative post-excavation sidewall and bottom sample frequencies in a letter, dated February 16, 2012. Excavation was expanded beyond the limits defined by the PDI samples in two locations due to visual identification of anomalous material requiring additional horizontal and vertical delineation samples to define the excavation limits for the expanded areas as discussed in Sections 8.6 and 8.7. The PDI sample data are included as **Appendix A** to the SA-6 South 100% Design and the location of the PDI samples are shown on **Figure 1.2**, Excavation Confirmation Points, in **Appendix C** to this CCR.

**Tables 6A and 6B** provide the hexavalent chromium concentrations for the post-excavation samples collected in the expanded excavation areas. EDDs for these samples were submitted to the NJDEP's electronic mail site on April 1, 2016. A copy of the confirmation email message from the NJDEP acknowledging submittal of the EDD is included in **Appendix B**.

Upon completion of excavation in each cell, the horizontal and vertical extent of the excavation limits were surveyed.

Honeywell periodically submitted excavation completion documentation to the Special Master and Plaintiffs prior to commencing backfilling. See **Appendix S**.

The submittals summarized the activities undertaken to complete the excavation and included the following Engineer's certification:

> "Amec inspectors certify to the best of our technical ability that impacted soils as defined in the 100% Design Report have been removed and that the requirements to allow backfilling had been met."

Honeywell also noted, where applicable/appropriate, that the excavation in the referenced cells terminated [by depth] in the Stratum D and provided an Excavation Bottom Map that included the surveyed post-excavation bottom elevations for the cell(s). In addition, Honeywell provided an updated figure depicting the 156 cells comprising the SA-6 South excavation that was used as an excavation progress chart, attached a figure of the excavation cells, and included an excavation bottom map. Honeywell further stated that the contractor was ready to backfill the respective cells. During the course of the excavation, the Special Master acknowledged receipt of Honeywell's submittals and the notification that the contractor was ready to backfill the respective cells.

Surveying of the final "as-built" horizontal and vertical extent of the excavations was conducted by Maser Consulting P.A. (Maser) of Marmora, New Jersey. R. Thomas Hugg, a New Jersey Professional Land Surveyor, certified record drawings surveyed by Maser. Record Drawings are discussed and presented in Section 19.

Maser also surveyed the position and elevation of each PDI post-excavation equivalent soil sample to verify that the excavation was carried to or beyond the confirmatory points and tabulated the survey information. The tables are provided in **Appendix C**. Three sets of tables are provided as follows:

- **Set 1**: Eastern portion of the Kellogg Street Development AOC excavation area starting at Route 440, west of the Route 440 ROW Deferred Area (Deed Notice Area 2), moving west, including cell Nos. 1 to 58;
- **Set 2**: Remainder of the Kellogg Street Development AOC excavation area up to the Site 073 Bulkhead Deferred Area (Deed Notice Area 4), including Area 41, Lens Area and cell Nos. 59 to 153; and
- **Set 3**: Shallow and deep excavation areas at the Site 163 Development AOC labeled Attachment B-3 in **Appendix C**.

There are three tables in Sets 1 and 2 as follows:

- Table 1.0 provides the coordinates of the PDI bottom samples and a comparison of the actual excavation elevation to the targeted (design) elevation at the established PDI bottom sample locations;
- Table 2.0 tabulates the design elevation and final excavation elevation at the center points of the excavation cells; and
- Table 3.0 provides the coordinates of the PDI sidewall samples and a comparison of the actual excavation elevation to the targeted (design) elevation at the established PDI sidewall sample locations.

Set 3 includes only equivalent Tables 1.0 and 3.0 for the Site 163 Development AOC excavation (Table 2.0 is not included because the excavation cells were not extended into Site 163).

## 8.6 ANOMALOUS MATERIAL SAMPLING

The SA-6 South 100% Design Report indicated that additional post-excavation sampling may be required if certain field conditions indicated the need to extend excavations beyond the identified limits, as determined by the onsite Construction Manager or designee or Honeywell's Remediation Manager. Conditions specified in the SA-6 South 100% Design Report that would trigger the need for additional post-excavation sampling included:

- Field observations indicating that an area previously characterized as clean shows evidence of contamination. In that event, sampling may be conducted to help identify the source and assess the impact;
- Observations that were not consistent with soil conditions characterized by the samples that were collected during the RI and PDI;
- Observations of chromium blooms on the surface of soils previously thought to be clean; and
- Other field conditions which suggest chromium impacts may extend outside of the previously defined limits.

Material meeting one or more of the trigger criteria is referred to as anomalous material in this CCR. Anomalous material was visually identified as potentially chromium-impacted soil at several locations in the excavation sidewall at the previously delineated horizontal extent of the >20 mg/kg hexavalent chromium impacted soils. At such locations, Amec Foster Wheeler collected a sample of the visually-impacted material. Additional details on the sampling are included in **Appendix J-5**.

Three locations in the Development AOC where anomalous material was visually identified and sampled included the southern excavation sidewall on Site 125 and two locations on the southern sidewall on Site 140 as shown on **Figure 11**. **Table 6B** shows that the hexavalent chromium results were <20 mg/kg; therefore, no additional excavation or sampling was required for these three locations. The cell references corresponding to the three anomalous material samples are:

- 140-SB-107: Cell 77
- 140-SB-108: Cell 70
- 125-SB-306: Cell 49

One additional location in the Development AOC where anomalous material was observed was in the sidewall and bottom of the western portion of the excavation at Site 134. The visually anomalous material was a thin lens observed just above the Stratum D. Three samples were collected and analyzed by Accutest for hexavalent chromium in the sidewalls of this area as excavation advanced to the west, and results reported >20 mg/kg for hexavalent chromium. Soil borings were conducted to delineate the extent of elevated hexavalent chromium concentrations as shown on **Figure 12**. Additional delineation details are included in **Appendix J-5**. Soil borings logs are included in **Appendix H**. The results of the samples are included on **Table 6A** and were utilized to determine the expanded excavation limits.

During excavation at Site 073, a potentially chromium-impacted 1-foot thick concrete slab was observed lying immediately below the ground surface at approximately 1 to 2 feet bgs at the location shown on **Figure 13**. The stained side of the concrete slab was in contact with underlying soils. The stained concrete was broken up and removed for subsequent offsite disposal with D Material. Two post-excavation sidewall samples were then collected from approximately 3 feet bgs from

the soils underlying the stained concrete and analyzed for hexavalent chromium. Results are shown on **Table 6B** and were <20 mg/kg for hexavalent chromium.

All sampling and analysis of samples was performed in accordance with the Data Management Plan combined for both the SA-6 South and SA-6 North Chromium Remedies included as Appendix H of the SA-6 North Chromium Remedy 100% Design Report. EDDs for final (<20 mg/kg for hexavalent chromium) post-excavation samples were submitted to the NJDEP as documented in **Appendix B**.

Section 8.7 provides a separate discussion on one other area where anomalous material was visually identified and sampled during the demolition of the remaining portion of the 60 Kellogg Street building on Site 125.

## 8.7 ANOMALOUS MATERIAL AT SITE 125 UNDER 60 KELLOGG STREET BUILDING SLAB

A limited quantity of anomalous material was observed in shallow soils within the 60 Kellogg Street building footprint during the demolition activities on April 29, 2016. Once the raised concrete building slab was removed, it was noted that timber piles were present below the slab. The demolition contractor was directed to cut off the tops of the timber piles, thus, they excavated some soil adjacent to the piles to expose the approximately top 2 feet of pile to allow for cutting them off with a chain saw. Between two such piles, a small amount of granular material with a yellowish color mingled with soils was observed at elevation +7.4 based on the NGVD29 datum, which was approximately 2 to 2.5 feet below grade (**Figure 8B**). A sample (125-SB-307) of this yellowish granular material/soil was collected for analysis of hexavalent chromium. The hexavalent chromium concentration of the sample was 10,100 mg/kg, confirming the material was COPR.

As discussed in Section 8.2 above, the anomalous material under the office portion of the 60 Kellogg Street building was located south of the 20 mg/kg line delineated during the PDI. The incidence of the COPR at the 60 Kellogg Street building is isolated from other observed locations of COPR in the northern and eastern parts of site. Thus, it appears that this isolated instance of COPR was associated with previous grading activities prior to construction of the building.

Upon receipt of the analytical results of the yellowish granular material/soil sample, Amec Foster Wheeler developed an excavation plan in compliance with the SA-6 South 100% Design Report for this material on behalf of Honeywell as detailed in **Appendix J-5**. Honeywell submitted the excavation plan to all Parties on May 17, 2016. Parties verbally approved the proposed excavation plan at the All Parties call on May 25, 2016.

Honeywell implemented the excavation on June 2, 2016 in accordance with the approved excavation plan. The final excavation limits and sample locations are shown on **Figure 8B** and on a Record Drawing C-111 Excavation Plan contained in **Appendix C**. The analytical results are summarized on **Table 6D** and show that hexavalent chromium concentrations at all post-excavation samples were <20 mg/kg. Approximately 54 CYs were excavated and placed in roll-off boxes for subsequent offsite disposal as hazardous waste (see Section 8.8).

Once the analytical results confirmed that the hexavalent chromium concentrations were <20 mg/kg in post-excavation samples, the excavation was backfilled with clean imported fill material. Additionally, the tops of the remaining timber piles were then exposed by removing surrounding soils to confirm there are no additional isolated locations of anomalous material adjacent to any other piles.

Once the preliminary analytical results of the post-excavation soil samples were obtained by Amec Foster Wheeler and reviewed with Honeywell, Honeywell submitted the results and a summary of the excavation plan to All Parties on May 17, 2016, which the Parties and Special Master approved on May 25, 2016. Subsequently, Honeywell submitted the standard certification email, including an as-built survey and tabulated coordinates of the finished excavation at the bottom and sidewall sample locations, on June 28, 2016, after the analytical results were validated.

## 8.8 OFFSITE TRANSPORTATION AND DISPOSAL

D Material (>1,000 mg/kg for hexavalent chromium) was loaded into tri-axle dump trucks and shipped offsite as hazardous waste to a rail transfer station, owned by Horwith Leasing Company LLC., in Northampton, PA. No confirmed D Material (>1,000 mg/kg for hexavalent chromium) was characterized as non-hazardous waste. Therefore, all confirmed D Material (>1,000 mg/kg for hexavalent chromium) designated for offsite disposal was transported to the contracted disposal facility,

Heritage Environmental Services, in Indianapolis, Indiana. Approximately 33,000 tons of hazardous soils were disposed of offsite. Hazardous waste manifests and certificates of disposal are included as **Appendix K**.

Trucks were lined with synthetic liners which closed over the loads near the truck scales before leaving the work zone. Dump truck bodies were equipped with road covers which were closed over the liners before leaving the project site.

Initially, trucks were decontaminated at the contamination reduction zone, and washed in a designated truck wash zone before leaving the site and entering the public roadways. Chromium-impacted waste was transported by truck to eastern Pennsylvania where it was trans-loaded into gondola railroad cars. Gondola cars were lined with synthetic liners to contain the chromium-impacted waste during rail transport. The chromium-impacted hazardous waste was transported to Heritage Environmental Services or Clean Earth (only the 54 CYs of excavated material from the 60 Kellogg Street building footprint placed in roll-offs) for treatment and disposal. **Appendix K** includes disposal manifests.

As seen on **Tables 7A through 7H,** one concrete sample (124-WC-C14-021114) exhibited elevated copper and two concrete samples (124-WC-C29-092314 and 124-WC-C30-092314) exhibited elevated dieldrin. Because of the copper and dieldrin results in this concrete material exceeded the NJDEP most stringent criteria to which it was compared, Honeywell shipped this material offsite for disposal as non-hazardous waste to the New Jersey Meadowlands Commission Landfill. The total amount of concrete shipped offsite was 815 tons.

The offsite disposal facilities for chromium-impacted material were:

| Disposal Facility | Material Type and Source | Waste Classification | Weight (Tons) |
|---|---|---|---|
| Heritage/Clean Earth | Confirmed Chromium-Impacted D Material Excavated from the Development AOC | Hazardous | 33,000 |
| Bayshore Recycling | Petroleum soil co-mingled with Chromium-Impacted A & B Material and Debris Excavated from the Development AOC | Non-hazardous | 8,900 |

| Disposal Facility | Material Type and Source | Waste Classification | Weight (Tons) |
|---|---|---|---|
| Middlesex County Landfill | Petroleum soil co-mingled with Chromium-Impacted A & B Material Excavated from the Development AOC | Non-hazardous | 27,000 |
| New Jersey Meadowlands Commission Landfill | Copper-dieldrin impacted concrete Excavated from the Development AOC (see Section 9.3) | Non-hazardous | 815 |
| Bayshore Recycling | Debris | Non-hazardous | 315 |

# 9.0 EXCAVATION BACKFILLING, BACKFILL COMPACTION, AND BACKFILL COMPACTION TESTING

Backfilling within the excavations in the Development AOC included the spreading/placing, compacting, and grading of backfill materials that met the Specification 02315 and were approved by the EOR.

## 9.1 BACKFILL SOURCES

Sources of imported backfill from offsite locations were tested and analyzed to confirm the material met the NJDEP's definition of clean fill in accordance with the TRSR and did not contain hexavalent chromium above 1 mg/kg. Tested and approved imported backfill sources for SA-6 South included:

- Approximately 1,000 CYs of surplus clean gravel that remained at SA-7 after the completion of the SA-7 sediment remedy;
- Approximately 17,000 CYs of surplus clean fill material from a capital improvement construction project on SA-5 NJCU located on the east side of Route 440;
- Approximately 69,000 CYs of common borrow material from a construction site in Summit, New Jersey; and
- Approximately 195,000 CYs of purchased fill materials from the following quarries licensed by NJDEP:

| Source | Quarry | Material Type | Approximate Volume Imported (CYs) |
|---|---|---|---|
| Weldon | Watchung | Screenings | **82,200** |
| Weldon | Watchung | Quarry Process | **9,300** |
| Weldon | Watchung | DGA | **300** |
| Weldon | Lake Hopatcong | Screenings | **5,300** |
| Tilcon | Mount Hope | DGA | **17,700** |
| Tilcon | Mount Hope | 1.5" Stone | **3,000** |
| Tilcon | Mount Hope | 3/8" Stone | **300** |
| Tilcon | Mount Hope | 6"-18" Riprap | **100** |
| Tilcon | Mount Hope | 2.5 Stone | **500** |
| Liberty Aggregates | Liberty | I-5 Structural Fill | **5,000** |
| Tilcon | Mount Hope | I-8 Structural Fill | **7,000** |

| Source | Quarry | Material Type | Approximate Volume Imported (CYs) |
|---|---|---|---|
| Tilcon | Mount Hope | 575 Stone | **9,900** |

Additionally, the following sources of onsite backfill material were tested and approved in accordance with the SMP to confirm they met the reuse criteria:

- Approximately 18,000 CYs of onsite recycled concrete tested and approved for reuse; and
- Approximately 46,000 CYs of excavated A Material tested and approved for reuse.

## 9.2 BACKFILL TESTING

Backfill quality control testing was performed as indicated in the SA-6 South 100% Design Report. One sample for chemical analytical testing was required for each 5,000 tons brought onsite to confirm the imported backfill material met the definition of clean fill in the TRSR. Analytical results for imported backfill used in the Development AOC were compared to the Residential Direct Contact Soil Remediation Standards. In addition, the SA-6 South 100% Design Report required imported fill to have a hexavalent chromium concentration of ≤1 mg/kg.

Entact collected samples of imported fill material for analysis, other than hexavalent chromium, by their subcontracted analytical laboratory, ChemTech Laboratories of Mountainside, New Jersey. Samples were submitted to Eurofins (a.k.a. Lancaster Laboratories) of Lancaster, Pennsylvania for analysis of hexavalent chromium by USEPA Method 7199.

In accordance with the SA-6 South 100% Design Report, imported fill samples were analyzed for (see **Appendix L**):

- Target Compound List (TCL) VOCs by SW8260
- TCL Semi-volatiles by SW8270
- EPH by NJEPH 10/08
- Target Analyte List (TAL) Metals by SW6010B/7471
- Pesticides by SW8081

- Herbicides by SW846 8151
- Polychlorinated Biphenyls by SW8082
- Cyanide SW846 9012
- Hexavalent Chromium by USEPA 7199
- Synthetic Precipitation Leaching Procedure (SPLP) Metals by SW6010B/7471 only for those contaminants that exceed Impact to Groundwater (IGW) standards.

Clean fill certifications, certifying that the soil material was virgin and free of hazardous material and contaminants were obtained from the suppliers of the imported source location and are included in **Appendix L**. Specification 02315.2.13 also required one sample of each source of imported fill to be tested for maximum dry density and optimum moisture content as determined by American Society of Testing Materials (ASTM) D 698 (Standard Proctor). The Proctor results were used by the technician conducting the compaction testing in the field to determine the degree of compaction based upon a percentage of the Proctor as specified (see Specification 02315.3.12 and **Table 10**) in the SA-6 South 100% Design Report.

## 9.3 CONCRETE TESTING

Onsite sources of recycled concrete included:

- Approximately 5,000 CYs of crushed concrete generated from demolition of the sedimentation basin at SA-6 North; and
- Approximately 13,000 CYs of concrete building foundations and slabs encountered in excavations at SA-6 South.

All concrete materials were evaluated for suitability for onsite reuse through sampling and analysis. The SMP allowed concrete meeting NJDEP reuse parameters to be reused onsite as backfill in excavations or placed in the Open Space AOC with consolidated chromium-impacted soil. Concrete material that was not suitable for onsite reuse was shipped offsite to an approved waste facility.

Concrete sampling and analysis was conducted in accordance with the September 2013 CASP. The procedures outlined in the CASP were in accordance with the

NJDEP guidance document titled *Guidance for Characterization of Concrete and Clean Material Certification for Recycling*, dated January 12, 2010 and the NJDEP guidance document titled *Alternative and Clean Fill Guidance for SRP Sites*, dated December 29, 2011 – Version 2.

Concrete samples were collected at a maximum sampling frequency of one sample for every 250 CYs of concrete. Representative samples were obtained from the concrete cross-section (including the exposed surfaces) and crushed to fit into laboratory-supplied sample containers. A total of 18 concrete samples were collected from the crushed concrete generated from demolition of the sedimentation basin. A total of 39 concrete samples were collected from the remaining sources of recycled concrete from SA-6 South. Thirty-seven additional concrete samples were collected for synthetic precipitation leaching procedure analysis for those instances when the IGW standards were exceeded. Concrete that met the reuse criteria was sized to 3-inch minus for reuse by Entact in accordance with the SA-6 South 100% Design Report.

Concrete samples were field screened with a PID and collected with a bias towards any instrument or visual contamination. Sample collection, preservation and handling was performed in accordance the NJDEP Field Sampling Procedures Manual, August 2005, updated 2011 (NJDEP, 2005) and the Quality Assurance Project Plan provided in Appendix H-1 of the SA-6 North Chromium Remedy 100% Design Report.

In accordance with the CASP, concrete samples were analyzed for the same parameters as those tested on imported fill materials. The concrete sample results are included in **Tables 7A through 7H**.

## 9.4 BACKFILLING AND COMPACTION

The SA-6 South 100% Design Specification 02201.2.03 allowed for the use of crushed recycled concrete as bridge lift where necessary to stabilize soft or wet subgrade materials at the bottom of excavations. A Material re-use soil or the offsite sources of clean backfill indicated above in Section 9.1 were placed over the bridge lift to bring the backfill to the appropriate design grades.

Bridge lifts were initially placed in nominal 12-inch lifts and compacted with a minimum of 3 passes of a static steel drum roller as specified in Specification

02201.3.03 and **Table 10**. Vibratory compaction equipment was not used in the bridging lift. Based on the observation of the stability of the lift, the EOR permitted increasing the lift to 18 inches using dozer placement. If the lift was stable, static rolling was initiated. In some locations, it was necessary to defer rolling until up to a 3-foot-thick bridging lift was placed due to excessive dewatering. In other locations geotextile fabric was added between bridge lift layers or on top of the bridge lift to add additional reinforcing and material separation. Subsequent lifts of non-bridge-lift backfill materials were placed at a maximum of 12 inches' thick loose lift and compacted using vibratory smooth-drum rollers to at least 95% of the maximum dry density in accordance with the Specifications 02315.3.11 and 02315.3.12 as detailed on **Table 10**.

Approved-for-reuse A Material (historic fill) was placed and compacted at the bottom of the excavations and buried to the maximum extent possible with at least 6 inches of imported clean backfill as needed to achieve the design grades. The variable nature of this material precluded testing for compaction using the Proctor density methods. The condition of the material was observed, unsuitable materials removed, and compaction conducted in accordance with the specified methodology using 2 to 3 passes of a vibratory roller.

## 9.5 IN-PLACE BACKFILL DENSITY TESTING

The in-place density of the compacted imported backfill materials were verified in the field using a nuclear surface moisture-density gauge in accordance with American Society of Testing Materials (ASTM) D 6938. Vertical V-Northeast, Inc. of Rahway, New Jersey, was subcontracted to Entact and performed compaction testing at SA-6 South. Testing was performed in accordance with the SA-6 South 100% Design Report at a testing frequency of one test per 2,500 SF per compacted lift. Figures showing the in-place density testing locations at every 2,500 SF in the SA-6 South main excavation cells and tables ("Field Density Test Summary Log") summarizing the in-field density test results for each lift at these testing locations are provided in **Appendix M.** The coordinates of the testing locations and elevations of each associated lift are also provided on the Field Density Test Summary Logs. Test locations where test results showed the in-place density of the backfill material of that lift was less than 95% of the maximum dry density are also shown highlighted on the Field Density Test Summary Logs. Such lifts were re-compacted and re-tested until the in-field density results met the criterion.

# 10.0 CONTAINMENT SYSTEM CONSTRUCTION

In accordance with the SA-6 South Consent Decree and the SA-6 South 100% Design Report, the Chromium Remedy for the Open Space AOC includes a containment system consisting of a hydraulic barrier, a RCRA-equivalent cap (Cap), and a contingent groundwater extraction system to provide hydraulic control of shallow groundwater. The objectives of the containment system are to physically separate chromium-impacted soils within the Open Space AOC from the adjacent Development AOC and SA-7; to prevent the migration of contaminated groundwater out of the Open Space AOC; and to limit infiltration of precipitation into the chromium-impacted soil within the Open Space AOC.

Major containment system construction activities included:

- Installation of Hydraulic Barrier;
- Vibration Monitoring
- Consolidation of Chromium-Impacted Soil Excavated from the Development AOC;
- Construction of the Contingent Groundwater Extraction System;
- Surcharging of soils in the Open Space Cap AOC; and
- Construction of the Cap in the Open Space AOC.

## 10.1 HYDRAULIC BARRIER INSTALLATION

The hydraulic barrier at SA-6 South consisting of steel sheetpile with sealed joints was installed around the eastern, southern, and western perimeters of the Open Space AOC in accordance with the SA-6 South 100% Design and DCs 2013-8-14, 2013-9-12, 2015-5-29, and 2015-08-20. The hydraulic barrier is connected to the existing SA-7 SCB on the northern boundary of SA-6 South and keyed into the meadow mat (Stratum D) or Stratum O. The western hydraulic barrier was installed approximately 38 feet inboard of the bulkhead. The chromium-impacted soil area between the hydraulic barrier and the bulkhead is the Site 073 Bulkhead Deferred Area (Deed Notice Area 4) and will be excavated during implementation of the Bayfront Redevelopment Plan following replacement of the existing bulkhead.

The barrier wall was installed using an ABI Mobileram with a high frequency vibratory driver. Prior to driving the sheets, pre-trenching was conducted to approximately 4 to 5 feet bgs along the hydraulic barrier alignment to remove debris that could inhibit sheetpile driving. Material removed during the pre-trenching was consolidated in the Open Space AOC. The trench was backfilled with crushed recycled concrete.

The sheet piling was 1907 Hoesch Larssen Z Series sheetpile. The length of sheets varied along the alignment subject to the final design top elevation, the depth to Stratum D, and temporary support stability requirements. Sheets were fabricated and supplied to the site at specific lengths based upon the design profiles. The majority of sheetpile was delivered to the site in welded pairs. Single sheets and fabricated special sheets were used at specific locations. Sheet welding and epoxy coating was conducted by Durabond at their Steelton, Pennsylvania facility. Specification 02180.6, as documented on **Table 10,** required application of an epoxy coating from the top of the sheet to a length equivalent of 2-feet into the Stratum D. Where longer sheets were used for structural purposes (i.e. to facilitate temporary excavation) the section of sheet below the 2 feet key did not require coating. The intent of the epoxy coating is to extend the life of the hydraulic barrier.

Independent QA was performed at the Durabond facility to verify conformance with the specified requirements.

To meet the permeability objectives of the hydraulic barrier, the field joints were sealed with a cement bentonite grout between Station 0+00 and Station 17+80 (east wall and eastern portion of south wall) and with hydrophilic sealant between Station 17+80 and Station 25+86 (west portion of southern wall and west wall). The type of sealant was based on the pH in the groundwater along the alignment. Record drawings of the sheetpile plan and profile are included in **Appendix N**.

Supplemental pH testing of groundwater was conducted along limited sections of the hydraulic barrier alignment that were accessible due to building at the time of the design as shown on **Figure 6**. In accordance with the SA-6 South 100% Design either a bentonite grout mix or hydrophilic seal was utilized on the sheetpile depending on the pH of the groundwater.

To achieve a continuous barrier around the Open Space AOC, the hydraulic barrier was connected to the southeast and southwest corners of the SA-7 SCB wall using a grouted connection. These connections were made by drilling a series of 6-inch diameter boreholes at the connection point using a track mounted drill rig fitted with a continuous flight hollow stem auger. The auger was advanced into the Stratum D and a Cement Bentonite grout was pumped from the bottom of the auger to fill the void. The closure section of the sheetpile barrier was then installed prior to the grout setting.

The toe of the wall was designed to key a minimum of 2 feet into the Stratum D or Stratum O. The Geotechnical Investigation Report from Appendix C of the SA-6 South 100% Design Report, was used to develop an elevation profile of the top of Stratum D along the barrier wall. As noted above, the sheets were fabricated and installed based on that design profile. Knowing the elevation of the top of Stratum D from the profile and the length of the sheet at any given location along the barrier wall alignment, the sheets were driven to the prescribed depth bgs (or elevation) so that the bottom of the sheets were keyed at least 2 feet into Stratum D. In many areas of the SA-6 Kellogg Street Development AOC excavation, the excavation was carried down to Stratum D. These areas provided corroboration of the accuracy of the design Stratum D profile and, therefore, confirmed that the sheet length/key and coating length were correct.

For the majority of SA-6 South, the cap to barrier wall profile is above the water table. In some utility corridors, the connection is submerged. Langan Engineering, Inc. (Langan) of Lawrenceville, New Jersey was retained by Amec Foster Wheeler to provide 3rd party QA on the construction of the cap components. In submerged areas, GCL was placed under the geomembrane in lieu of the gas vent layer and a sand bentonite plug was installed against the top of the sheetpile to provide for a low permeability connection. The installation of the connection detail for these areas is discussed in the Geosynthetics Quality Assurance Report prepared by Langan in **Appendix Q**.

## 10.2 VIBRATION MONITORING

The SA-6 South 100% Design Report mandated vibration monitoring when sheeting was being driven proximate to critical subsurface infrastructure or other features

that could be damaged due to vibration. Such areas at SA-6 South are shown on **Figure 14** and included:

- Adjacent to Route 440 on the east side of the SA6 South Open Space AOC; and;
- temporary excavation support installation along the jughandle that connects Route 440 and Kellogg Street at Site 124; and
- Kellogg Street at Development AOC Site 140.

Honeywell's geotechnical engineering consultant, MRCE, developed the vibration limits for these sensitive areas. The Vibration Monitoring Plan (VMP) was prepared by Geocomp Engineering, Inc. in August 2013. This plan stated the maximum vibration limits as well as trigger limits which specified a change in the work approach if met. Seismographs were placed over the utilities at the jughandle and along Kellogg Street to monitor the vibration levels during installation. Vibrations on the building adjacent to Site 124 (440 Diner) were monitored in the basement. The ABI Mobileram operator had the ability to adjust the vibration frequency and total applied energy during driving. If the trigger levels were approached, the operator adjusted the driving parameters to keep the seismograph reading below the vibration limits. Vibration monitoring results are provided in **Appendix O**. Work was preformed per the VMP.

## 10.3 CONSOLIDATION OF SOILS IN OPEN SPACE AOC

The Chromium Remedy allowed for the consolidation of soil excavated from the SA-6 South Development AOC with hexavalent chromium concentrations of 20 to 1,000 mg/kg (B & C Materials) to be consolidated in the SA-6 South Open Space AOC. Additionally, the Chromium Remedy allowed for the consolidation of soil excavated from the SA-6 South Development AOC with hexavalent chromium concentrations of 20 to 240 mg/kg (B Material only) to be consolidated in the SA-6 North Open Space AOC.

The total volume of excavated soils consolidated in the SA-6 South Open Space AOC was approximately 35,000 CYs. The total volume of soils excavated from the SA-6 South Development AOC consolidated in the SA-6 North Open Space AOC was approximately 35,000 CYs. As discussed in Section 5.2, NJDEP approved the

consolidation of petroleum-impacted soils co-mingled with excavated A, B, & C Materials from SA-6 South in the SA-6 South Open Space AOC. Thus, of the approximately 59,000 CYs of material consolidated in the SA-6 South Open Space AOC, approximately 24,000 CYs of that material was petroleum-impacted soils co-mingled with excavated A, B, & C Materials.

Soils placed within the SA-6 South Open Space AOC were compacted as required by Specification 01600 (see **Table 10)** to create a stable subgrade for the capping system. In accordance with paragraph 65(d) of the SA-6 South Consent Decree, debris, or deleterious materials that could interfere with compaction was not placed under the cap. Compaction was typically performed using a vibratory steel drum roller. The subgrade was proof rolled with the roller operating in static mode loaded to provide a 1 ton per square foot (2,000 pounds per square foot), or equivalent, loading to the subgrade. The roller traversed over the subgrade materials until no further significant rutting or deformation of the subgrade was evident. In smaller areas where the roller would not fit (such as adjacent to the hydraulic barrier wall or adjacent to wells or surcharge monitoring instrumentation), a plate compactor was utilized to provide compaction. Subgrade compaction was subject to engineer's approval. Soils that were too wet to compact were either dried or treated with Calciment® to reduce moisture content and increase strength to meet the specified criteria. The grading of the consolidated soils met the grading requirements in the SA-6 South 100% Design Report.

## 10.4 CONTINGENT GROUNDWATER EXTRACTION SYSTEM CONSTRUCTION

The SA-6 South 100% Design originally required a conceptual groundwater extraction design based on vertically-installed wells subject to further evaluation and possible change. Honeywell determined that a trench system would be more effective in the variable fill above the Stratum D. DC 2014-3-25 and an additional 8 minor DCs document the change to the trench design. The collection trench was installed prior to the surcharging program described in Section 10.5 of this report. The contingent groundwater extraction trench location is shown on **Figure 10** and the Record Drawing contained in **Appendix C**. The system will only operate as necessary to comply with the groundwater capture and gradient requirements noted in Paragraph 69 of the SA-6 South Consent Decree.

Specification 02140.3.01 required that the water table be controlled during construction of the cap to maintain an outward gradient towards SA-6 South from

the SA-7 perimeter pools (see **Table 10**). Pumping from the collection trench and other temporary trenches within the Open Space AOC was initiated prior to cap placement to control groundwater levels and terminated once the cap was completed in October 2015. Evaluation of preliminary groundwater level monitoring results in existing shallow wells in the Development AOC indicates that an inward gradient to the SA-6 South Open Space AOC has been created throughout most of the area.

The contingent groundwater system trench consists of 1,700 feet of 8-inch diameter perforated HDPE pipe that was placed running east/west through the center of the Open Space AOC. The HDPE pipe was placed on top of 6 inches (nominally) of clean crushed stone and was covered with additional stone to depths in accordance with the above-referenced DC. Geotextile fabric was placed across the top of the trench to prevent vertical migration of fines into the trench. As shown on the Record Drawing in **Appendix C**, the perforated piping is connected to an extraction manhole located near the western end of the Open Space AOC. Four access manholes are installed along the alignment to provide access for maintenance, if required. A double walled force main runs from the extraction manhole to the GWTP. Electrical and instrumentation conduits were also installed between the pump station and GWTP as shown on the drawing Contingent Groundwater Extraction System, South Cap in **Appendix C**.

The groundwater model predicts that the inward gradient can be maintained by passive means (i.e. without active pumping). In the event it is necessary to implement active pumping, a pump will be installed into the extraction manhole along with the requisite electrical and instrumentation wiring and controls.

## 10.5 SURCHARGE PROGRAM

The existing surface grade of the Open Space AOC generally varied between elevation 8 and elevation 10 based on the NGVD29 datum. The maximum "redevelopment grade" at the Open Space AOC is elevation 21 based on the NGVD29 datum. Engineering calculations indicated that up to approximately 20 inches of settlement could result due to the increased load resulting from the increase in grade. That settlement was estimated to be primarily through consolidation of the underlying compressible Stratum O and Stratum D Soils. A decision was made, based on this potential settlement, to surcharge the site to remove 100% of the Primary Consolidation attributable to the Development AOC grade loading, prior to placement of the cap.

The surcharge program was designed to be completed in a rolling fashion starting from 1S and moving east to 3S (see **Illustration 4**).





**Illustration 4: Surcharge Loading Plan**

The surcharge loads pile geometry was designed to achieve settlement as a result of primary consolidation in a period of approximately 6 months. Surcharge pile geometry was included in the SA-6 South 100% Design Report. The actual time required for the individual areas was determined by the results of the Surcharge Monitoring Plan. The Surcharge Monitoring Plan was provided in Appendix N of the SA-6 South 100% Design Report.

A Surcharge Monitoring report summarizing the results of the surcharge program for SA-6 South was generated on a monthly basis during active surcharging. The Surcharge Monitoring Report included in **Appendix P** indicates that 100% of primary consolidation was achieved at the monitoring locations.

Upon completion of the analysis and verification by Amec Foster Wheeler that surcharge objectives were met, data packages were sent to MRCE for 3rd party review. The dates of surcharging and 3rd party agreement of completion are:

| Surcharge Area | Initiation Date | Completion Date | MRCE Agreement |
|---|---|---|---|
| 1S | June 2014 | September 2014 | October 27, 2014 |
| 2S | July 2014 | January 2015 | February 5, 2015 |
| 3S | November 2014 | March 2015 | April 24, 2015 |

Following completion of the Surcharge Program, excess surcharge material was removed and the subgrade prepared for deployment of the cap geosynthetics.

## 10.6 CAP CONSTRUCTION

This Section provides a summary of the cap construction and third-party QA testing performed. A full detailed explanation, including step-by-step construction sequencing and procedures, photographs of cap elements, and a full description of QA testing procedures and results is contained in the Langan Cap Geosynthetic Quality Assurance (QA) Report for Study Area 6 South ("Langan Report"), (**Appendix Q).**

The Chromium Remedy included a RCRA-equivalent geosynthetic cap system, including a methane GVL to address the potential release of naturally occurring methane, 60 mil Linear Low Density Polyethylene geomembrane, GDL and cover soils to protect the geosynthetic components and support plant growth. Cap construction proceeded from west to east at SA-6 South, starting on July 20, 2015. The construction of the geosynthetic cap system was completed on November 4, 2015.

The following process was utilized for construction of the cap within the Open Space AOC:

- Verification survey by Maser of the cap subgrade.
- Certification by the installation contractor (ESI) and Langan that the subgrade surface was suitable for geosynthetic deployment;
- Install cap geosynthetics (gas venting layer, geomembrane liner, geocomposite drainage layer) in the Open Space AOC;
- QA/QC of placed geosynthetics;
- Install Warning Layer.
- Placement of protective cover soil;
- Placement of root barrier;
- Placement of imported clean soil of the type required to the design thicknesses and grades; and

- Seeding and or gravel placement to serve as final cover pending redevelopment.

**Figures 15 and 16** graphically portray the Chromium Remedy components including the cap details.

The final design of the Bayfront Redevelopment includes roadways that traverse the Open Space AOC in a North-South alignment. The geosynthetic cap system was designed to accommodate future utilities in the roadways traversing the SA-6 South Open Space AOC. The locations and design of the utility corridors were coordinated with the future Bayfront Redevelopment design and were in accordance with the SA-6 South Consent Decree. The location of utility corridors is shown on **Figure 17**. The liner grades provide a minimum of 3 feet between the Bayfront Redevelopment road surface and the liner. The 3 feet criterion was established by Amec Foster Wheeler based on a conservative approach utilizing Bayfront Redevelopment planned traffic flows and a typical Municipal pavement design that was consistent with the road designation/traffic loadings. In areas designated as future roadways either imported NJ I-5 or NJ I-8 was placed as "Structural Fill under Roadways" above the cap components per Specification 02315.2.05 and **Table 10**.

Upon surcharge completion, the cap subgrade was graded and compacted in accordance with the lines, grades and compaction requirements specified in the SA-6 South 100% Design Report and associated DCs (see **Table 10**). Subgrade preparation was performed between May 11, 2015 and October 9, 2015. To document compliance with the grading requirements, a Construction Control Grid was established consistent with Specification 01460.1.04 and **Table 10**. The Construction Control Grid is included as Figures 1.1 and 1.2 SA-6 South Construction Control Grid in **Appendix C**. Also included are summary tables (Table 1 SA-6 South Open Space Cap Area – Construction Control Grid As Built Summary) prepared by Maser comparing the design grades and actual grades at the Construction Control Grid nodes confirming that all nodes are within tolerance. A topographic survey of the SA-6 South subgrade was prepared by Maser (C-125, 126, and 127, **Appendix C**).

Installation of the cap geosynthetics followed Maser's certification that the subgrade surface conformed to the specified Construction Control Grid. Amec Foster Wheeler provided QA approval of Maser's documented subgrade elevations prior to issuing to

Langan for approval for geosynthetics deployment. In addition, as part of the subgrade approvals, Amec Foster Wheeler provided QA approval of the sand bentonite GCL to barrier wall connections (signed GCL to barrier wall logs are included in Appendix H of the Langan Report [**Appendix Q**]).

The cap geosynthetics were placed between July 20, 2015 and November 4, 2015. The cap geosynthetics included components that were designed to meet the technical requirements of Section 65(a) of the Consent Decree. The cap geosynthetics scope included the following key tasks:

- Subgrade inspection for acceptability prior to geosynthetics deployment,
- Gas Vent/Geotextile and GCL installation over the subgrade and under the geomembrane,
- Geomembrane Installation-60 mil LLDPE,
- Geocomposite drainage/warning layer installation, and
- Warning tape installation.

The top component of the GDL is comprised of a high visibility orange non-woven geotextile liner that met the visibility requirements, but not the printed warning requirements, of the SA-6 South Consent Decree. Therefore, yellow polyethylene direct burial tape, with black lettered warning language, was installed every 5 feet on center on top of the GDL and also on top of the root barrier that was installed 12 inches above the high visibility orange non-woven geotextile.

Honeywell contracted with Langan to provide Independent QA for the SA-6 cap geosynthetics installation. As the Independent QA Engineer, Langan performed the QA activities specified in the Langan Report, including monitoring, field oversight, and documentation. The Langan Report documents the results of the QA Geosynthetic activities conducted during the construction of the cap at SA-6 South by both Langan and Amec Foster Wheeler field personnel. Refer to the Construction Quality Assurance (CQA) Plan prepared by Langan in June 2015 (attached as Appendix B to the Langan Report) for a description of the scope of work conducted by Langan, as well as the roles and responsibilities of the owner, EOR, earthwork contractor, and liner contractor. DCBs and RFIs which were generated subsequent

to the 100% Design, and relevant to the QA scope of work were reviewed and approved by the EOR, and are further summarized in this CCR.

The Langan Report specifically included the following documentation of the cap construction activities:

- Relevant Record Drawings;
- Summary of the various phases of the work observed as part of the QA program;
- Daily QA Reports indicating the work activities completed each day and other pertinent information;
- Daily cap construction forms submitted by the Geosynthetic Installer which included:
    - Repair Reports, Trial Weld Logs, Panel Placement Forms, Seam Control Forms, Destructive & Non-Destructive Test Forms, and Subgrade Approval Forms;
    - Field testing results for fusion welds and extrusion welds;
    - Laboratory testing results for the destructive samples collected (i.e., fusion & extrusion welds); and
    - Photographs depicting daily work activities and the various phases of the capping activities.

The Langan Report certifies that placement of the SA-6 South cap geosynthetics was completed in compliance with the construction design documents (**Appendix Q**).

The Amec Foster Wheeler EOR provided a full-time site Geosynthetics Inspector to inspect materials deployment, installation and documentation for compliance with the SA-6 South 100% Design of the capping system. The Geosynthetics Inspector observed the placement of the GDL cover soil to verify that the soil was placed in accordance with the Earthwork and GDL Specifications (02315 and 02374, respectively) and that the GDL was not damaged or unnecessarily stressed. The Geosynthetics Inspector also observed the fabrication, installation and extrusion welding and vacuum testing of all boots.

QC for geosynthetics installation was provided by Entact and their specialty installer ESI. Entact also contracted with Geotechnics, Inc. to conduct the specified offsite laboratory testing required as part of the capping project, such as destructive seam testing. All ESI field QC and Geotechnics laboratory testing is incorporated into the Langan QA Report and are the subject of the Langan QA Certification. Langan offsite QA laboratory testing was completed by TRI Environmental, Inc. Record drawings of the cap geosynthetics (SA6 South Cap Panel Layout; SA6 South Cap GVL/GCL Layout – Class A Geotextile/Gas Vent Layer/Geosynthetic Clay Liner 01/28/16; SA6 South GDL Layout – Geocomposite Drainage Layer 01/27/16) are included as **Appendix C**.

After completion of the cap, cover soils that are referred to as Horizon B and C soils were placed consistent with the SA-6 South 100% Design Report. Multiple sources of Horizon B and Horizon C soils were identified by Entact and Amec Foster Wheeler. Multiple samples from these sources were tested for geotechnical and chemical analysis to find sources of the cap cover soil materials that met the SA-6 South 100% Design Specification 02315 and DC 2015-9-17, 2016-03-21, and 2016-4-20. The analytical data obtained during the Horizon B and Horizon C source identification process is summarized on the Backfill Sample Comparison to NJDEP Standards table in **Appendix L**.

A woven geotextile root barrier was installed within the landscape areas. At least 6 inches of Horizon C soil was placed immediately above the root barrier and compacted to 90% of the maximum dry density as measured by ASTM D-698 (Standard Proctor). Additional Horizon C, Horizon B where designated, and 6 inches of topsoil (Horizon A) were placed to complete the cover soil build up. Analytical sample results of Horizon A are also included in the Backfill Sample Comparison to NJDEP Standards table in **Appendix L**. The approximate volumes of cap cover soils imported and placed above the cap components were as follows:

| Material Layer | Vendor/Source | Approximate Volume Imported (CYs) |
|---|---|---|
| GDL Cover Soil | Celgene | 15,200 |
| Structural Fill under Roadways | Liberty | 5,000 |
| Structural Fill under Roadways | Tilcon Mount Hope | 7,000 |

| Material Layer | Vendor/Source | Approximate Volume Imported (CYs) |
|---|---|---|
| Horizon A - Topsoil | Nature's Choice | 9,500 |
| Horizon A - Topsoil | Excavating Materials & Equipment, Inc. (EME) | 150 |
| Horizon B | Cedar Hill | 11,600 |
| Horizon C | Nature's Choice | 11,600 |

In accordance with the SA-6 South Consent Decree, a minimum thickness of 1 foot of clean soil (in areas to be paved) and 2 feet of clean soils (in other unpaved areas) were placed above the geomembrane liner. More clean soils may have actually been placed depending on the final surface grade features. The SA-6 South Consent Decree required an average thickness of clean cover soil above the geomembrane of 3 feet. The actual average thickness is 4.4 feet.

Throughout the work, the amount of cover soil varied. As work advanced in some places the GDL was exposed for more than 30 days. Subsequently, GDL repairs were completed in April 2016 at the locations shown on the figure on Record Drawing SA6 South Cap Panel Layout, 60-mil Textured LLDPE Geomembrane 01/28/16 (**Appendix C**).

The cap was designed with consideration of grading, drainage, and groundwater management provisions of the adjacent SA-7 site.

The methane vents extend from the geocomposite drainage, gas collection layer below the geomembrane liner through the cover soils to the atmosphere. See the Gas Vent Detail figure in **Appendix C** for details of construction.

# 11.0 PERIMETER AIR MONITORING

As part of the Health and Safety monitoring conducted during remediation, air monitoring within the work zone area and around the perimeter of SA-6 South was implemented by Emilcott Associates, Inc., on behalf of Honeywell, to assess in an ongoing manner that COCs did not result in potential exposures to the surrounding public. Honeywell maintains a website at the following URL: www.jerseycitychromiumcleanup.com, which provided daily updates with perimeter air data and other information during implementation of the SA-6 Chromium Remedy. Any changes to the website or URL will be addressed as part of Long Term Monitoring activities pursuant to the LTMP. **Tables 1A and 1B** contain the baseline and project data.

The primary COC, potentially found in dust from activities occurring at the site, was hexavalent chromium. Action levels determined for the SA-6 South project included 339.0 micrograms per cubic meter (µg/m$^3$) for air-borne dust. Although the approved action level for SA-6 South is 339 µg/m$^3$, Honeywell voluntarily applied the action level of 221 µg/m$^3$ that was calculated for SA-6 North, since the remedies for SA-6 North and SA-6 South were implemented as an integrated remedy. The discrepancy in air monitoring levels between the two sites, was not attributable to chromium, but was rather based on the presence of lead as a contaminant in discrete areas of SA-6 North. Thus, the air monitoring level was based on the potential for encountering lead dust at that site. Preventative measures taken to control the generation of dust were conducted per the PAMP and HASPs. In order to assess the potential presence of hexavalent chromium in dust, the perimeter air monitoring stations were located throughout the multi-phase excavation activities using a grid system as shown on **Figure 4**. The points were determined by the PAMP and the Honeywell onsite representative based on the location of soil disturbance activities, prevailing wind direction, and field conditions.

Baseline PAMP data was discussed and presented in Section 2.3. In the course of the project, there were no recorded employee exposures above the OSHA Permissible Exposure Limit. The highest total particulate detection at SA-6 South was on March 8, 2016 at 200 µg/m$^3$ (below operative action level of 221 µg/m$^3$) where the corresponding hexavalent chromium sample was not detected. The highest

hexavalent chromium detection was on November 25, 2013 at 42 nanograms per cubic meter where the corresponding particulate detection was 77 µg/m$^3$.

# 12.0 IN-SITU TREATMENT

Pursuant to the SA-6 South 100% Design Report, in-situ injections of a chemical reductant were conducted within the Site 163 Development AOC to treat chromium-impacted soils at depths greater than 4 feet bgs in isolated locations. The in-situ injections were ineffective. As a result, the chromium-impacted soils that were not effectively treated within the Site 163 Development AOC Non-Deed Notice Area were excavated. In the Site 163 Development AOC Deed Notice Area chromium-impacted soils that were not effectively treated were left in place and capped with clean soil and gravel. The in-situ work is described below.

In-situ treatment was conducted per the Work Plan which was submitted to the NJDEP as part of the Discharge to Groundwater Permit-By-Rule (DGW-PBR) and provided additional details regarding the in-situ treatment program. This Work Plan was submitted to the NJDEP on September 28, 2012 and NJDEP issued the DGW-PBR on January 3, 2013.

In accordance with the SRIR/RASR/RAWP and subsequent work plans, the in-situ injections of calcium polysulfide (CAPS) spanned a zone from 2 feet above to 2 feet below the impacted zone. Further, injections were not implemented below the Stratum D underlying the hexavalent-impacted soil/fill materials.

Prior to the initiation of injections in each area, 57 temporary well points (TWPs) were installed. TWPs were installed from July 21, 2014 and from July 28, 2014 through July 31, 2014.

Geoprobe® direct push drill rigs were used to accomplish injection of CAPS solution. Injections were initiated on July 31, 2014 using one drill rig and one mixing station. On August 4, 2014, a second Geoprobe® direct push drill rig was mobilized to Site 163 to inject CAPS solution simultaneously utilizing two mixing stations. In several areas, surficial concrete slabs or unknown subsurface obstructions required minor field adjustments to the originally proposed TWP or injection point locations.

Following the in-situ treatment program, 6-month soil sampling was implemented as described in the Site 163 Cr RIR/RASR/RAWP to determine the effectiveness of the in-situ treatment. The results are included in **Table 8** and showed that the 20

mg/kg criterion had not been uniformly achieved in the area of treatment. It was determined that additional excavation would be required to remediate the chromium soils to <20 mg/kg as shown in **Figure 18**.

Major DC 2015-09-28 described that an additional 6,335 square feet of soil would be excavated from the Site 163 Development AOC Non-Deed Notice Area and the area backfilled with clean fill. DC 2015-09-28 also provided that unexcavated areas in the Site 163 Development AOC Deed Notice Area, south of the proposed curb line that will be part of the Riverside Park, Riverside Drive, and Kellogg Street, will be deed restricted and subject to a conservation restriction, consistent with paragraph 61(c)(ii)(3) of the Study Area 6 South Consent Decree.

# 13.0 GWTP RELOCATION AND CONSTRUCTION

Honeywell constructed a new GWTP on SA-6 North. The GWTP is designed to handle and treat groundwater recovered as part of the SA-7 deep overburden and bedrock groundwater remedy and will handle and treat shallow groundwater from the activation of the contingent groundwater extraction system installed within the Open Space AOC. The former GWTP previously located at Site 140 on SA-6 South in the former ABR Trucking warehouse and office building was demolished to implement the SA-6 South Chromium Remedy. The former GWTP was initially built to handle and treat construction water during the SA-7 chromium remedy, but following the completion of the remediation of SA-7, had been treating recovered regional deep and overburden groundwater since December 2008. Once the new GWTP was built and started accepting flows on February 14, 2014, the former GWTP at SA-6 South was decommissioned, dismantled and removed from the Site 140 building.

AMEC Foster Wheeler designed, permitted and managed the construction of the 65 gpm GWTP beginning in March 2013. The GWTP pre-treats hexavalent chromium contaminated groundwater for discharge to the PVSC. The GWTP replaced an existing plant at 80 Kellogg Street which needed to be demolished as required for soil remediation activities. The $4.5M GWTP design/build project also involved re-configuration of the existing three well groundwater extraction system, controls, and double wall conveyance system to allow for transition of flow from the old plant to the new plant and as required for GWTP commissioning activities.

The new GWTP incorporates chemical reduction, precipitation, flocculation, clarification and filter press processes which generates significantly less filter cake than the microfiltration system used in the original plant. The GWTP is housed in a 4,800-square foot pre-engineered metal building which also accommodates an office, equipment repair shop and state of the art chemical storage rooms and tanker offloading facilities.

Such facilities incorporate secondary containment, automatic leak and vapor detection systems, and an interface control system with remote monitoring capability, a closed-circuit television monitoring system as well as a card swipe access control and burglar alarm system. An innovative hydraulic pusher system

was also custom designed and installed to allow for more efficient filling of the 30 CY waste filter cake roll-off. Local permitting included development of site plan approval applications and testimony as required for both existing conditions and post redevelopment conditions. Interaction with the Jersey City building department and JCMUA at the preliminary design phase also led to a more streamlined building permitting process and local cooperation during the construction phase.

# 14.0 SITE RESTORATION

Site restoration activities were performed during the demobilization phase of the project. Site restoration activities included the following:

- Decontamination and demobilization of construction equipment and surplus materials;
- Decontamination, decommissioning and dismantling of the construction wastewater treatment system piping;
- Relocation/removal of the jersey barriers and relocation of the chain-link fence along the Route 440 sidewalk to the property line boundary;
- Removal of contractor temporary office trailers and power/phone service;
- Removal of traffic control features along Route 440;
- Removal of construction debris;
- Disposal of other non-regulated waste; and
- Stabilization of the Open Space AOC cover soils, including seeding and other erosion control measures.

# 15.0 CONSTRUCTION PERMITS

The following construction permits were obtained to complete the onsite work. Applications for renewals were submitted as needed. Permits that were no longer required were allowed to expire.

| Permit | Site | Status | Expiration Date |
|---|---|---|---|
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | 9/25/2017 |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | 8/31/2018 |
| Soil Erosion and Sedimentation Control Plan | SA-6 Chromium Remedy | Obtained 5/16/2013 | 11/16/2016 |
| Request for Authorization (RFA) | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | 5/31/2018 |
| NJDEP – Treatment Works Approval (TWA) | SA-6 Chromium Remedy | Obtained 7/8/2013 | 6/30/2016 (no extension necessary) |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | 6/30/2016 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 South (Site 163) Only | Obtained 1/3/2013 | Not Specified |

| Permit | Site | Status | Expiration Date |
|---|---|---|---|
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte. 440 ROW | SA-6 Chromium Remedy | Final Executed Permit Issued 12/2/14 Extension Obtained 12/24/2015 | 12/3/2016 |

# 16.0 SUSTAINABILITY EFFORTS DURING CONSTRUCTION

Under Honeywell's stewardship the construction process was integrated into the overall vision for the Jersey City west side redevelopment by incorporating a sustainable design approach which focused on conservation of natural resources through beneficial reuse, recycling, minimization of ongoing energy consumption and reduction in carbon footprint. Specifically, Honeywell's sustainable construction efforts integrated:

- Use of renewable B-20 Biodiesel in lieu of conventional fossil fuel based petro-diesel in construction equipment,
- Crushing and recycling of demolition generated clean concrete to be reused as clean fill material on site, and
- The removal and transportation of petroleum soils from the SA-6 South cap to reduce Greenhouse Gas emissions via hazardous waste reduction.

# 17.0 POST-REMEDY OPERATION & MAINTENANCE

Following completion of the remedial actions, including installation of the groundwater extraction system which is to be operated on a contingent basis, a post-remediation long term monitoring program will be implemented in accordance with the pending LTMP. The LTMP was developed and submitted to NJDEP and all Parties in October 2015 to address the monitoring requirements specified in the SA-6 South Consent Decree Paragraphs 74 and 78. As of the writing of this CCR, Honeywell and the Parties are in final negotiations regarding the terms of the LTMP. Honeywell will be implementing the uncontested LTMP activities until the LTMP is finalized. The LTMP satisfies the Consent Decree requirements for long term monitoring, maintenance, and protection of engineering and institutional controls by establishing procedures and schedules for the following activities required by the Consent Decree:

- Quarterly visual inspections to ensure only permitted land usage is occurring and verify no usage compromises the integrity of the Chromium Remedy;
- Quarterly visual inspection monitoring of the grade and slope to identify whether erosion has occurred or is occurring;
- Quarterly visual inspection monitoring to determine if noticeable differential settlement or subsidence has occurred that could impair the integrity of the Chromium Remedy;
- Baseline topographic survey at completion of the Chromium Remedy and additional surveys annually for the first 5 years, then every 5 years for an additional 10 years;
- Quarterly visual inspection monitoring to determine if disturbance of the Chromium Remedy in the Open Space AOC has occurred;
- Quarterly visual inspection monitoring to ensure that burrowing animals are not materially impairing the integrity of the Chromium Remedy;
- Quarterly visual inspection monitoring of the vegetative cover to ensure that vegetative cover in the Open Space AOC is in conformance with the landscaping provisions of the SA-6 South 100% Design, including the OSDS, and the Redevelopment Plan and will not materially impair the integrity of the Chromium Remedy;

- Maintenance of the vegetative cover to include mowing to ensure tree species cannot become established except in designated areas and removal of any vegetation not permitted by the OSDS that would impair the integrity of the Chromium Remedy;
- Quarterly groundwater elevation monitoring to ensure specified hydraulic gradients across the hydraulic barriers;
- Monthly monitoring of vented gases and the gas venting system for 1 year. Frequency will be reduced to quarterly after 1 year if data are stable; and
- Any additional monitoring required by the specific design details.

The draft LTMP was submitted to all Parties, including NJDEP, in October 2015. A revised draft LTMP was submitted to all Parties, including NJDEP, in September 2016. The LTMP, once finalized after review by the NJDEP, Plaintiffs and the Special Master, will be the governing document for the operation, maintenance, and inspection of the Chromium Remedy components, including the contingent operation of the groundwater extraction system.

The relationship between long-term monitoring and institutional controls that are required by the SA-6 South Chromium Remedy is discussed in Section 18.

# 18.0 INSTITUTIONAL CONTROLS

Institutional controls are integral to the Chromium Remedy at SA-6 South and were made a part of the RAOs. The institutional controls are applied in accordance with Subchapter 7 of NJDEP's ARRCS (N.J.A.C. 7:26C).

Institutional controls include deed notices and remedial action permits at specific areas where chromium-impacted soils remain and a groundwater remedial action permit and CEA for residual chromium-impacted groundwater. Additional institutional controls for the Open Space AOC and a portion of Site 163 pursuant to the SA-6 South consent decrees include transferring ownership to Jersey City and the granting of a conservation restriction.

## 18.1 DEED NOTICES

To meet Honeywell's and Bayfront's objectives for SA-6 South and coordinate with the objectives of the Development, four deed notices are required for the chromium impacts at SA-6 South. The areas to which each of the four deed notices apply are shown on **Figure 19**. Draft deed notices are contained in **Appendix R**. After the final text of the deed notices has been reviewed and approved by the NJDEP, they will be recorded at the office of the Hudson County Register.

The deed notices have been prepared in accordance with NJDEP's ARRCS. Each deed notice specifies conditions for alteration, improvement, and/or disturbance of the engineering controls, and provides monitoring, maintenance, notification and reporting requirements. These requirements include documentation that applicable worker health and safety laws and regulations are followed during the disturbance and restoration of those controls. The deed notices contain figures and cross-sections showing the engineering controls and details regarding notification and reporting requirements.

## 18.2 SOIL REMEDIAL ACTION PERMITS

Honeywell has prepared draft Remedial Action Permit Applications for Soil for the SA-6 South Open Space AOC, the deed noticed portion of Site 163, and the two Deferred Areas for NJDEP review. Once the deed notices are filed, the Remedial Action Permit applications will be finalized and submitted to the NJDEP. The permit applications contain requirements for monitoring, maintenance and

reporting to document the protectiveness of the remedial actions and engineering controls for each of the areas on which the deed notices have been established until such time the deed notice is no longer required. The permit also includes a schedule for submittal of Biennial Certification Reports to the NJDEP, and requirements pertaining to financial assurance (see Section 20) and permit transfer, modification and termination.

## 18.3 GROUNDWATER REMEDIAL ACTION PERMITS

Honeywell has prepared a draft Remedial Action Permit Application for Groundwater for the SA-6 South Open Space AOC. The draft Remedial Action Permit application was attached to the RAR approved by NJDEP on March 30, 2017, and now that the RAR has been approved by NJDEP, the Remedial Action Permit application will be finalized and submitted to the NJDEP. The permit applications contain requirements for monitoring, maintenance and reporting to document the protectiveness of the remedial actions and engineering controls for each of the areas on which the deed notices have been established until such time the deed notice is no longer required. The permit also includes a schedule for submittal of Biennial Certification Reports to the NJDEP, and requirements pertaining to financial assurance (see Section 20) and permit transfer, modification and termination.

## 18.4 CLASSIFICATION EXCEPTION AREA

A regional CEA for groundwater has been established by NJDEP on February 16, 2012 for the SA-5/6/7 sites as an institutional control to identify chromium-impacted groundwater above the NJDEP GWQS and prevent the use of groundwater within the designated CEA areas. The CEAs address the shallow fill, deep overburden, and bedrock zones. The shallow zone refers to groundwater within fill material (above the Stratum D and underlying native soils), generally to a depth of 20 feet bgs. The deep overburden zone refers to groundwater below the fill and Stratum D down to bedrock, generally from approximately 20 feet to 90 feet bgs. The bedrock zone refers to groundwater within the upper 20 to 40 feet of fractured bedrock. The shallow groundwater CEA may be modified in the future following one year of post-remedial action groundwater monitoring.

## 18.5 CONSERVATION RESTRICTIONS

Conservation Restrictions were prepared for both Open Space Areas at SA-6 North and SA-6 South at the time of property transfer from Jersey City Redevelopment

Agency to Bayfront Redevelopment LLC per Paragraph 60(b) of the SA-6 North Consent Decree and at the time of the granting of the option to buy per Paragraph 74(b) of the SA-6 South Consent Decree. These conservation restrictions were recorded on March 25, 2010. The existing conservation restriction placed on the SA-6 South Open Space AOC will be amended to include the as-built hydraulic barrier walls. A new conservation restriction will be established on the deed noticed portion of Site 163, where remaining chromium-impacted soils were identified in the area south of the northern curbline which is within the Development AOC, or Honeywell may combine this area with the conservation restriction for the SA-6 South Open Space AOC. Hackensack River Watershed Land Trust shall be the primary holder of the conservation restrictions.

# 19.0 RECORD DRAWINGS

In accordance with Section 60(j)(viii) of the SA-6 South Consent Decree and the TRSR, Record Drawings were prepared and are included in **Appendix C**. Maser completed surveys by a NJ licensed surveyor and Mr. Thomas Hugg sealed drawings prepared by Maser. Amec Foster Wheeler engineer of record for SA-6 South, Mr. Samuel (Geoff) Shallard, PE, sealed Record Drawings prepared by Amec Foster Wheeler.

The Record Drawings and the SA-6 South 100% Design Report set the standard for future repair or replacement of the Chromium Remedy under the Study Area 6 South Consent Decree.

# 20.0 REMEDIAL ACTION COSTS

Remediation costs are summarized in the table below:

| Activity | Cost ($1MM) |
|---|---|
| Construction Costs | $28 |
| Soil Disposal | $8 |
| Oversight/Construction Management | $1.6 |
| **Total** | **$37.6** |

## 20.1 FINANCIAL ASSURANCES

Long term monitoring for SA 6 North and South is part of the overall financial assurance letter of credit for chromium remediation at SA-5, SA-6 North, SA-6 South, and SA-7 that are subject to the oversight of the Special Master. This letter of credit is issued by the MUFG Union Bank, N.A. in the amount of $46,915,000 to cover all remediation and long term monitoring activities at these sites.

# 21.0 REMEDIATION CLOSE OUT SUMMARY

The Chromium Remedy at SA-6 South commenced on March 2013 and was substantially complete by November 2016. The Chromium Remedy was implemented in accordance with the TRSR, the ACO, the SA-6 South Consent Decree, the SA-6 South 100% Design Report and subsequent DCs, and other clarifying correspondence between Honeywell and NJDEP and/or Honeywell, the Special Master, and Plaintiffs. Therefore, other than remediation of the Deferred Areas, no further remedial actions are required for either the Development or Open Space AOCs at SA-6 South. Remediation of Deferred Areas will be coordinated with the Bayfront Redevelopment Project and the widening of Route 440.

The RAOs for SA-6 South soils, except in the Deferred Areas, will be met by the Chromium Remedy implemented in all AOCs and the establishment of institutional controls. It is anticipated that RAOs for SA-6 South shallow groundwater in the Development AOCs will be met as a result of the removal of chromium-impacted soil from the Development Area AOC and containment and capping of chromium-impacted soils and groundwater in the Open Space AOC, but will be confirmed by post-remediation shallow groundwater sampling. The hydraulic barrier is designed to restrict potential offsite migration of chromium-impacted groundwater. Post-remediation groundwater sampling will be implemented in the Development AOCs in accordance with the LTMP prepared for both SA-6 North and SA-6 South. The LTMP establishes procedures and schedules for long-term monitoring of groundwater quality and levels in the Open Space AOC to determine the potential operation of the contingent groundwater extraction system. The LTMP also establishes the inspection, maintenance, and operation of critical features of the Chromium Remedy.

Honeywell will establish appropriate institutional controls at SA-6 South that supplement the physical remedial actions including deed notices and remedial action permits for soils for four distinct areas, conservation restrictions for the Open Space AOC and the deed noticed portion of Site 163, and a groundwater remedial action permit in the Open Space AOC. A classification exception area has already been established with NJDEP for the regional shallow groundwater, but Honeywell may revise the boundary of the shallow groundwater CEA slightly based upon the post-

remediation shallow groundwater results at SA-6 South. Final soil and groundwater Remedial Action Permit applications will be submitted to NJDEP.

It is Honeywell's intention that this CCR will close out remediation of chromium-impacted soil for SA-6 South with the exception of the Deferred Areas. Honeywell will document additional soil remediation in the deferred areas by filing supplements to this CCR. NJDEP has reviewed and approved the RAR submitted separately from this CCR. Honeywell will close out remediation of chromium-impacted shallow groundwater in the Development AOCs once groundwater sampling confirms that the RAOs have been met. Honeywell will document the completed remediation of the shallow groundwater in the Development AOCs by filing a supplement to this CCR.

In accordance with paragraph 5 of the Consent Order Entering Consolidated 100% Design for Study Area 6 North and Study Area 6 South, *Jersey City Municipal Utilities Auth. v. Honeywell,* No. 2:05-cv-05955-DMC-JAD (D. N.J. July 9, 2013), ECF No. 448, Honeywell will submit a Consent Order which has appended to it (i) the 100% Design except the drawings and (ii) the Final CCR for entry into Federal Court. The supplements to this CCR for the deferred areas and shallow groundwater will be subject to the Special Master review and approval requirements of the SA-6 South Consent Decree, and will be filed with the Court as a supplement to the Consent Order filed in accordance with paragraph 5 of the Consent Order Entering Consolidated 100% Design for Study Area 6 North and Study Area 6 South.

# 22.0 REFERENCES

AMEC Environment and Infrastructure, Inc., 2015. Long Term Monitoring Plan, Study Area 6 North (Sites 087 and 088) and Study Area 6 South (Sites 073, 124, 125, 134, 140, and 163), Jersey City, New Jersey. June 2013.

AMEC Environment and Infrastructure, Inc., 2013. Chromium Remedy 100% Design Report – Issued for Construction, Study Area 6 North, Sites 087 and 088, Jersey City, New Jersey. June 2013.

AMEC Environment and Infrastructure, Inc., 2013. Chromium Remedy 100% Design Report – Issued for Construction, Study Area 6 South, Sites 073, 124, 125, 134, 140, and 163, Jersey City, New Jersey. June 2013.

Administrative Consent Order (ACO) between Honeywell, formerly Allied Signal, Inc., and the New Jersey Department of Environmental Protection, 1993.

Consent Decree Regarding Remediation and Redevelopment of Study Area 6 South, entered December 19, 2008.

Consent Judgment between Honeywell and the NJDEP dated September 7, 2011.

Equity Environmental Engineering, 2015a. Underground Storage Tank Remedial Action Report, Study Area 6 South, Site 134, Jersey City, New Jersey. January 2015.

Equity Environmental Engineering, 2015b. Underground Storage Tank Remedial Action Report, Study Area 6 South, Site 163, 75 Kellogg Street, Jersey City, New Jersey. February 2015.

HydroQual, Inc., 2005. HydroQual, Inc., 2005. Preliminary Deep Overburden Groundwater Report, Honeywell Study Area 7. March 31, 2005, HWEL.002.001.11.

HydroQual, Inc., 2006. Deep Overburden Groundwater Remedial Alternatives (DORAA) Report Honeywell Study Area 7. June 2006. HWEL.002.001.11.

HydroQual, Inc., 2007. Final Groundwater Investigation Report, Honeywell Study Area 7. February 2, 2007. HWEL 002.001.11

MACTEC Engineering and Consulting, Inc., 2008. Supplemental Remedial Investigation Report/ Remedial Action Selection Report/Remedial Action

Work Plan for Chromium, Study Area 6 South, Kellogg Street Properties, Jersey City, New Jersey. December 2008.

NJDEP, 2004; Historic Fill of the Jersey City Quadrangle (HFM-53)

NJDEP, 2005; Field Sampling Procedures Manual dated August 2005; last updated April 11, 2011. Available at http://www.nj.gov/dep/srp/guidance/fspm/

NJDEP, 2007; Chromium Policy Memorandum dated February 8, 2007

NJDEP, 2012. New Jersey Administrative Code, Chapter 26C Administrative Requirements for the Remediation of Contaminated Sites; last revised May 7, 2012, Trenton, New Jersey.

NJDEP, 2013. New Jersey Administrative Code, Chapter 26E Technical Requirements for Site Remediation May 7, 2012; last revised July 1, 2013, Trenton, New Jersey.

Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc., entered April 21, 2008.

TetraTech, Inc., July 2000. Draft Remedial Investigation Report Addendum, Study Area 6 NJDEP Site No. 073, 087, 088, 124, 125, 134, 140, and 163, Jersey City, New Jersey. July 2000.

# 23.0 LIST OF ACRONYMS AND ABBREVIATIONS

| | |
|---|---|
| ACO | Administrative Consent Order |
| AOC | Area of Concern |
| ARRCS | Administrative Requirements for Remediation of Contaminated Sites |
| ASTM | American Society of Testing Materials |
| bgs | Below ground surface |
| CAFRA | Coastal Area Facilities Act |
| CAPS | Calcium Polysulfide |
| CASP | Concrete and Asphalt Sampling Plan |
| CCR | Construction Completion Report |
| CEA | Classification Exception Area |
| COC | Contaminants of Concern |
| COPR | Chromite Ore Processing Residue |
| CWTP | Construction Water Treatment Plant |
| CY | Cubic Yards |
| DC | Design Change Bulletins |
| DGW-PBR | Discharge to Groundwater Permit by Rule |
| DMP | Data Management Plan |
| EA | Each |
| EDD | Electronic Data Deliverables |
| EOR | Engineer of Record |
| EPH | Extractable Petroleum Hydrocarbons |
| FHA | Flood Hazard Area |
| GCL | Geosynthetic Composite Layer |
| GDL | Geosynthetic Drainage Layer |
| gpm | gallons per minute |
| GPS | Global Positioning System |
| GWTP | Groundwater Treatment Plant |
| GWQS | Groundwater Quality Standards |
| GVL | Geosynthetic Venting Layer |
| HASP | Health and Safety Plan |
| HDPE | High-density polyethylene |
| IGW | Impact to Groundwater |

| | |
|---|---|
| JCDPW | Jersey City Department of Public Works |
| JCIA | Jersey City Incinerator Authority |
| JCMUA | Jersey City Municipal Utilities Authority |
| LF | Linear Feet |
| LLDPE | Linear Low-Density Polyethylene |
| LSRP | Licensed Site Remediation Professional |
| LTMP | Long Term Monitoring Plan |
| µg/L | micrograms per liter |
| µg/m$^3$ | micrograms per cubic meter |
| mg/kg | milligrams per kilogram |
| MRCE | Mueser Rutledge Consulting Engineers |
| NGVD29 | National Geodetic Vertical Datum 1929 |
| N.J.A.C. | New Jersey Administrative Code |
| NJCU | New Jersey City University |
| NJDEP | New Jersey Department of Environmental Protection |
| NJDOT | New Jersey Department of Transportation |
| OSHA | Occupational Safety and Health Administration |
| PAMP | Perimeter Air Monitoring Plan |
| PDI | Pre-Design Investigation |
| PID | Photo-ionization Detector |
| PPE | Personal Protective Equipment |
| PSE&G | Public Service Electric & Gas |
| PVC | Polyvinyl Chloride |
| PVSC | Passaic Valley Sewerage Commission |
| QA/QC | Quality Assurance/Quality Control |
| RAOs | Remedial Action Objectives |
| RAR | Remedial Action Report |
| RAP | Remedial Action Permit |
| RAWP | Remedial Action Work Plan |
| RCRA | Resource Conservation and Recovery Act |
| RFI | Request for Information |
| RI | Remedial Investigation |
| RIR | Remedial Investigation Report |
| ROW | Right of Way |
| SA | Study Area |
| SCB | Soil-Cement Bentonite |
| SF | Square Feet |
| SGWMP | Shallow Groundwater Monitoring Plan |
| SMP | Soil Management Plan |

| | |
|---|---|
| SPLP | Synthetic Precipitation Leaching Procedure |
| SRIR | Supplemental Remedial Investigation Report |
| TAL | Target Analyte List |
| TCL | Target Compound List |
| TI | Technically Impracticable |
| TRSR | Technical Regulations for Site Remediation |
| TWP | Temporary Well Point |
| USEPA | United States Environmental Protection Agency |
| UST | Underground Storage Tank |
| VMP | Vibration Monitoring Plan |
| VOC | Volatile Organic Compound |

# TABLES

**TABLE 1A**
**Baseline PAMP Data**
**Hexavalent Chromium Air Samples**
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample ID | Location (Station) | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Monday, July 15, 2013 | **S1CrD071513*** | S1 | 7:30 | 15:25 | 475 | 982.0 | < | 100.0 | < | 21.0 |
| 2 | Tuesday, July 16, 2013 | S1CrD071613 | S1 | 7:15 | 15:41 | 506 | 1046.0 | < | 96.0 | < | 19.0 |
| 3 | Wednesday, July 17, 2013 | S1CrD071713 | S1 | 7:10 | 15:32 | 502 | 1041.0 | | 150.0 | < | 19.0 |
| 4 | Monday, July 22, 2013 | S1CrD072213 | S1 | 7:22 | 15:40 | 498 | 1020.0 | < | 98.0 | < | 20.0 |
| 5 | Wednesday, July 24, 2013 | S1CrD072413 | S1 | 7:12 | 15:39 | 507 | 1050.0 | | 99.0 | < | 19.0 |
| 6 | Thursday, July 25, 2013 | S1CrD072513 | S1 | 5:51 | 14:09 | 498 | 1034.0 | < | 97.0 | < | 19.0 |
| 7 | Tuesday, July 30, 2013 | **S1CrD073013*** | S1 | 7:25 | 15:45 | 500 | 1033.9 | | 510.0 | | 20.0 |
| 8 | Wednesday, July 31, 2013 | **S1CrD073113*** | S1 | 6:50 | 15:41 | 531 | 1100.2 | < | 91.0 | < | 18.0 |
| 9 | Monday, August 05, 2013 | S1CrD080513 | S1 | 7:15 | 15:35 | 500 | 1052.5 | < | 95.0 | < | 19.0 |
| 10 | Tuesday, August 06, 2013 | S1CrD080613 | S1 | 6:50 | 15:10 | 500 | 1037.8 | < | 96.0 | < | 19.0 |

| **Notes:** | **Action Levels** | |
|---|---|---|
| Detectable Results Below Action Level | Hexavalent Chromium | 221 $ng/m^3$ |
| $ng/m^3$: nanograms per cubic meter | ***Validated by 3rd Party** | |
| $ug/m^3$: microgram per cubic meter | | |

**TABLE 1A**
**Baseline PAMP Data**
**Metals**
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for As (ng/m$^3$) | Analytical Results for Pb(ng/m$^3$) | Analytical Results for V (ng/m$^3$) | Analytical Results for Zn (ng/m$^3$) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Monday, July 15, 2013 | **S1Met071513*** | S1 | 7:30 | 15:25 | 475 | 998.0 | < 51 | < 52 | < 3000 | < 1000 |
| 2 | Tuesday, July 16, 2013 | S1Met071613 | S1 | 7:15 | 15:41 | 506 | 1063.0 | < 48 | 61 | < 2800 | < 940 |
| 3 | Wednesday, July 17, 2013 | S1Met071713 | S1 | 7:10 | 15:32 | 502 | 1020.0 | < 50 | < 51 | < 2900 | < 980 |
| 4 | Monday, July 22, 2013 | S1Met072213 | S1 | 7:22 | 15:40 | 498 | 1029.0 | < 49 | < 50 | < 2900 | < 970 |
| 5 | Wednesday, July 24, 2013 | S1Met072413 | S1 | 7:12 | 15:39 | 507 | 1045.0 | < 49 | 56 | < 2900 | < 960 |
| 6 | Thursday, July 25, 2013 | S1Met072513 | S1 | 5:51 | 14:09 | 498 | 1024.0 | < 50 | < 50 | < 2900 | < 980 |
| 7 | Tuesday, July 30, 2013 | **S1Met073013*** | S1 | 7:25 | 15:45 | 500 | 712.6 | < 71 | < 4200 | < 4200 | < 1400 |
| 8 | Wednesday, July 31, 2013 | S1Met073113 | S1 | 6:50 | 15:41 | 531 | 1077.1 | < 47 | < 2800 | < 2800 | < 930 |
| 9 | Monday, August 05, 2013 | S1Met080513 | S1 | 7:15 | 15:35 | 500 | 1049.2 | < 48 | < 250 | < 2900 | < 950 |
| 10 | Tuesday, August 06, 2013 | S1Met080613 | S1 | 6:50 | 15:10 | 500 | 1032.1 | < 49 | < 250 | < 2900 | < 970 |

| **Notes:** | **Action Levels** | |
|---|---|---|
| Detectable Results Below Action Level | Arsenic (As) | 200 ng/m³ |
| ***Validated by 3rd Party** | Lead (Pb) | 300 ng/m³ |
| ng/m³: nanograms per cubic meter | Vanadium (V) | 300 ng/m³ |
| | Zinc (Zn) | Not Applicable |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Tuesday, October 22, 2013 | S1CRD102213 | S1 | 7:17 | 15:00 | 463 | 977 | < | 100.0 | < | 10.0 |
| 2 | Wednesday, October 23, 2013 | S1CRD102313 | S1 | 7:05 | 15:25 | 500 | 1125 | < | 89.0 | < | 8.9 |
| 3 | Wednesday, October 23, 2013 | S3CRD102313 | S3 | 7:05 | 15:25 | 500 | 753 | < | 130.0 | < | 13.0 |
| 4 | Thursday, October 24, 2013 | S1CRD102413 | S1 | 8:00 | 16:00 | 480 | 982 | < | 100.0 | < | 20.0 |
| 5 | Friday, October 25, 2013 | S1CRD102513 | S1 | 7:30 | 16:00 | 510 | 977 | < | 100.0 | < | 20.0 |
| 6 | Monday, October 28, 2013 | S1CRD102813 | S1 | 7:19 | 16:00 | 521 | 988 | < | 100.0 | < | 10.0 |
| 7 | Tuesday, October 29, 2013 | S3CRD102913 | S3 | 7:07 | 16:00 | 533 | 1020 | < | 98.0 | < | 9.8 |
| 8 | Wednesday, October 30, 2013 | S1CRD103013 | S3 | 7:40 | 15:10 | 450 | 1071 | < | 93.0 | < | 9.3 |
| 9 | Thursday, October 31, 2013 | S1CRD103113 | S1 | 8:00 | 15:10 | 430 | 848 | < | 120.0 | < | 12.0 |
| 10 | Friday, November 01, 2013 | S1CRD110113 | S1 | 8:00 | 15:30 | 450 | 948 | < | 100.0 | | 26.0 |
| 11 | Monday, November 04, 2013 | S1CRD110413 | S1 | 7:13 | 16:05 | 532 | 1317.5 | < | 76.0 | < | 15.0 |
| 12 | Tuesday, November 05, 2013 | S1CRD110513 | S1 | 6:21 | 15:40 | 559 | 1173 | < | 85.0 | < | 17.0 |
| 13 | Wednesday, November 06, 2013 | S1CRD110613 | S1 | 7:06 | 15:48 | 522 | 1451 | < | 65.0 | < | 13.0 |
| 14 | Thursday, November 07, 2013 | S1CRD110713 | S1 | 6:41 | 15:09 | 508 | 1402 | < | 71.0 | < | 14.0 |
| 15 | Friday, November 08, 2013 | **S1CRD110813*** | S1 | 6:45 | 16:45 | 600 | 1,315 | < | 76.0 | | 35.0 |
| 16 | Monday, November 11, 2013 | S1CRD111113 | S2 | 6:50 | 15:10 | 500 | 1415 | < | 71.0 | | 9.8 |
| 17 | Tuesday, November 12, 2013 | S1CRD111213 | S3 | 6:48 | 15:10 | 502 | 1421 | < | 70.0 | < | 7.1 |
| 18 | Wednesday, November 13, 2013 | S1CRD111313 | S4 | 6:30 | 16:04 | 574 | 1670 | < | 60.0 | | 7.9 |
| 19 | Thursday, November 14, 2013 | S1CRD111413 | S1 | 6:45 | 15:16 | 511 | 1464 | < | 68.0 | < | 14.0 |
| 20 | Friday, November 15, 2013 | S1CRD111513 | S1 | 6:55 | 15:10 | 495 | 1406 | < | 71.0 | < | 14.0 |
| 21 | Monday, November 18, 2013 | S1CRD111813 | S1 | 6:30 | 16:00 | 570 | 1650 | < | 61.0 | | 13.0 |
| 22 | Tuesday, November 19, 2013 | S1CRD111913 | S1 | 6:30 | 15:56 | 566 | 1715 | < | 58.0 | | 16.0 |
| 23 | Wednesday, November 20, 2013 | S3CRD112013 | S3 | 6:50 | 16:28 | 578 | 1725 | < | 58.0 | < | 12.0 |
| 24 | Thursday, November 21, 2013 | **S3CRD112113*** | S3 | 6:16 | 15:40 | 564 | 1701 | < | 59.0 | < | 12.0 |
| 25 | Friday, November 22, 2013 | S1CRD112213 | S1 | 7:15 | 16:06 | 531 | 1580 | < | 63.0 | < | 13.0 |
| 26 | Monday, November 25, 2013 | S1CRD112513 | S1 | 6:55 | 15:10 | 495 | 1559 | | 77.0 | | 42.0 |
| 27 | Tuesday, November 26, 2013 | S1CRD112613 | S1 | 6:58 | 15:14 | 496 | 1520 | < | 66.0 | < | 13.0 |
| 28 | Wednesday, November 27, 2013 | S1CRD112713 | S1 | 7:08 | 14:20 | 432 | 1309 | < | 76.0 | < | 15.0 |
| 29 | Monday, December 02, 2013 | S3CRD120213 | S1 | 6:30 | 15:00 | 510 | 1402 | < | 71.0 | | 17.0 |
| 30 | Tuesday, December 03, 2013 | S1CRD120313 | S1 | 6:32 | 15:34 | 542 | 1657 | < | 60.0 | < | 12.0 |
| 31 | Wednesday, December 04, 2013 | S3CRD120413 | S1 | 6:43 | 15:10 | 507 | 1493 | | 88.0 | < | 14.0 |
| 32 | Thursday, December 05, 2013 | S1CRD120513 | S1 | 6:36 | 15:06 | 510 | 1535 | < | 65.0 | | 18.0 |
| 33 | Friday, December 06, 2013 | S2CRD120613 | S2 | 6:24 | 15:20 | 536 | 1637 | < | 61.0 | < | 6.2 |
| 34 | Monday, December 09, 2013 | S2CRD120913 | S2 | 6:48 | 15:40 | 532 | 1631 | < | 61.0 | | 14.0 |
| 35 | Tuesday, December 10, 2013 | S1CRD121013 | S1 | 6:50 | 15:01 | 491 | 1561 | < | 64.0 | | 20.0 |
| 36 | Wednesday, December 11, 2013 | **S1CRD121113*** | S1 | 6:38 | 16:28 | 590 | 1819 | < | 65.0 | | 22.0 |
| 37 | Thursday, December 12, 2013 | S2CRD121213 | S2 | 6:45 | 15:03 | 498 | 1492 | < | 67.0 | | 7.1 |
| 38 | Friday, December 13, 2013 | S1CRD121313 | S1 | 6:50 | 16:26 | 576 | 1699 | < | 59.0 | | 8.0 |
| 39 | Monday, December 16, 2013 | S1CRD121613 | S1 | 6:48 | 15:06 | 498 | 1820 | < | 55.0 | < | 5.5 |
| 40 | Tuesday, December 17, 2013 | S3CRD121713 | S3 | 6:50 | 15:10 | 500 | 1773 | < | 56.0 | < | 5.7 |
| 41 | Wednesday, December 18, 2013 | S1CRD121813 | S1 | 6:45 | 15:10 | 505 | 1717 | < | 58.0 | | 7.9 |
| 42 | Thursday, December 19, 2013 | S1CRD121913 | S1 | 6:40 | 14:12 | 452 | 1634 | < | 61.0 | < | 12.0 |
| 43 | Friday, December 20, 2013 | S2CRD122013 | S2 | 6:35 | 14:15 | 460 | 1642 | < | 61.0 | < | 12.0 |
| 44 | Monday, December 23, 2013 | S1CRD122313 | S1 | 6:50 | 15:11 | 501 | 1252 | < | 80.0 | < | 16.0 |
| 45 | Tuesday, December 24, 2013 | S2CRD122413 | S2 | 6:27 | 13:39 | 432 | 1328 | < | 81.0 | < | 16.0 |
| 46 | Monday, December 30, 2013 | S1CRD123013 | S1 | 6:50 | 15:15 | 505 | 1523 | < | 66.0 | < | 13.0 |
| 47 | Tuesday, December 31, 2013 | S1CRD123113 | S1 | 7:00 | 14:10 | 430 | 1301 | < | 77.0 | < | 16.0 |
| 48 | Thursday, January 02, 2014 | S3CRD010213 | S3 | 7:00 | 15:27 | 507 | 1516 | < | 66.0 | < | 13.0 |
| 49 | Monday, January 06, 2014 | S1CRD010614 | S1 | 6:25 | 15:05 | 520 | 1656 | < | 60.0 | < | 12.0 |
| 50 | Tuesday, January 07, 2014 | S1CRD010714 | S1 | 6:53 | 15:01 | 488 | 1545 | < | 65.0 | < | 13.0 |
| 51 | Wednesday, January 08, 2014 | S1CRD010814 | S1 | 6:53 | 15:40 | 527 | 1652 | < | 61.0 | < | 12.0 |
| 52 | Thursday, January 09, 2014 | S1CRD010914 | S1 | 6:50 | 15:02 | 492 | 1557 | | 67.0 | < | 13.0 |
| 53 | Friday, January 10, 2014 | S1CRD011014 | S1 | 7:00 | 15:00 | 480 | 1541 | < | 65.0 | < | 13.0 |
| 54 | Monday, January 13, 2014 | **S2CRD011314*** | S2 | 6:50 | 15:00 | 490 | 1558 | < | 64.0 | < | 13.0 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 55 | Tuesday, January 14, 2014 | **S1CRD011414*** | S1 | 6:32 | 15:00 | 508 | 1605 | < | 62.0 | < | 13.0 |
| 56 | Wednesday, January 15, 2014 | S2CRD011514 | S2 | 6:26 | 15:15 | 529 | 1680 | < | 60.0 | < | 12.0 |
| 57 | Thursday, January 16, 2014 | S2011614 | S2 | 6:55 | 15:04 | 489 | 1560 | < | 64.0 | < | 13.0 |
| 58 | Friday, January 17, 2014 | S1011714 | S1 | 6:50 | 15:20 | 510 | 1622 | < | 62.0 | < | 12.0 |
| 59 | Monday, January 20, 2014 | S1CRD012014 | S1 | 6:38 | 15:26 | 528 | 1679 | < | 60.0 | < | 12.0 |
| 60 | Tuesday, January 21, 2014 | S3CRD012114 | S3 | 6:53 | 14:00 | 427 | 1362 | < | 73.0 | < | 15.0 |
| 61 | Thursday, January 23, 2014 | S1CRD012314 | S1 | 6:57 | 15:17 | 500 | 1595 | < | 63.0 | < | 13.0 |
| 62 | Friday, January 24, 2014 | S1CRD012414 | S1 | 7:00 | 15:10 | 490 | 1556 | < | 64.0 | < | 13.0 |
| 63 | Monday, January 27, 2014 | S1CRD012714 | S1 | 6:45 | 15:00 | 495 | 1584 | < | 63.0 | < | 13.0 |
| 64 | Tuesday, January 28, 2014 | S2CRD012814 | S2 | 6:47 | 15:01 | 494 | 1581 | < | 63.0 | < | 13.0 |
| 65 | Wednesday, January 29, 2014 | S1CRD012914 | S1 | 6:50 | 15:00 | 490 | 1568 | < | 64.0 | < | 13.0 |
| 66 | Thursday, January 30, 2014 | S1013014 | S1 | 6:55 | 15:35 | 520 | 1661 | < | 60.0 | | 8.3 |
| 67 | Friday, January 31, 2014 | S1013114 | S1 | 6:45 | 15:29 | 524 | 1593 | | 66.0 | < | 6.4 |
| 68 | Monday, February 03, 2014 | S2020314 | S2 | 6:50 | 11:50 | 300 | 954 | < | 100.0 | < | 21.0 |
| 69 | Tuesday, February 04, 2014 | S2020414 | S2 | 6:45 | 15:00 | 495 | 1574 | < | 64.0 | | 29.0 |
| 70 | Thursday, February 06, 2014 | S2020614 | S2 | 6:45 | 15:11 | 506 | 1617 | < | 62.0 | < | 13.0 |
| 71 | Friday, February 07, 2014 | S1020714 | S1 | 6:55 | 15:06 | 491 | 1552 | < | 64.0 | < | 13.0 |
| 72 | Monday, February 10, 2014 | S2021014 | S2 | 6:37 | 15:00 | 503 | 1610 | < | 62.0 | < | 13.0 |
| 73 | Tuesday, February 11, 2014 | S2021114 | S2 | 6:40 | 15:06 | 506 | 1612 | < | 62.0 | < | 13.0 |
| 74 | Thursday, February 13, 2014 | S3021314 | S3 | 7:00 | 15:00 | 480 | 1606 | < | 62.0 | < | 13.0 |
| 75 | Friday, February 14, 2014 | S1021414 | S1 | 8:30 | 15:08 | 398 | 1329 | < | 75.0 | < | 7.7 |
| 76 | Tuesday, February 18, 2014 | S3021814 | S3 | 6:55 | 15:23 | 508 | 1575 | < | 63.0 | < | 6.4 |
| 77 | Wednesday, February 19, 2014 | S2021914 | S2 | 6:50 | 15:10 | 500 | 1600 | | 66.0 | < | 6.3 |
| 78 | Thursday, February 20, 2014 | S1022014 | S1 | 6:53 | 15:21 | 508 | 1577 | < | 63.0 | < | 6.4 |
| 79 | Friday, February 21, 2014 | S3022114 | S3 | 7:10 | 15:49 | 519 | 1614 | < | 62.0 | < | 6.3 |
| 80 | Monday, February 24, 2014 | **S2022414*** | S2 | 6:48 | 15:00 | 492 | 1604 | < | 62.0 | < | 6.3 |
| 81 | Tuesday, February 25, 2014 | **S1022514*** | S1 | 6:50 | 15:02 | 492 | 1624 | < | 62.0 | < | 6.3 |
| 82 | Wednesday, February 26, 2014 | **S1022614*** | S1 | 6:42 | 15:00 | 498 | 1653 | < | 60.0 | < | 6.1 |
| 83 | Thursday, February 27, 2014 | S1022714 | S1 | 7:13 | 15:04 | 471 | 1524 | < | 66.0 | < | 6.6 |
| 84 | Friday, February 28, 2014 | S2022814 | S2 | 6:53 | 15:00 | 487 | 1539 | < | 65.0 | < | 6.6 |
| 85 | Monday, March 03, 2014 | S2030314 | S2 | 6:50 | 15:00 | 490 | 1583 | < | 63.0 | < | 13.0 |
| 86 | Tuesday, March 04, 2014 | S2030414 | S2 | 6:57 | 15:15 | 498 | 1574 | | 88.0 | < | 13.0 |
| 87 | Wednesday, March 05, 2014 | S2030514 | S2 | 6:58 | 15:00 | 482 | 1542 | | 93.0 | < | 13.0 |
| 88 | Thursday, March 06, 2014 | S3030614 | S3 | 7:00 | 15:08 | 488 | 1542 | < | 65.0 | < | 6.6 |
| 89 | Friday, March 07, 2014 | S3030714 | S3 | 6:53 | 15:06 | 493 | 1587 | < | 63.0 | < | 6.4 |
| 90 | Monday, March 10, 2014 | S1031014 | S1 | 7:00 | 15:10 | 490 | 1568 | < | 64.0 | < | 6.4 |
| 91 | Tuesday, March 11, 2014 | S1031114 | S1 | 6:55 | 15:39 | 524 | 1672 | | 85.0 | < | 6.0 |
| 92 | Wednesday, March 12, 2014 | S3031214 | S3 | 6:59 | 15:19 | 500 | 1585 | | 98.0 | < | 6.4 |
| 93 | Thursday, March 13, 2014 | S2031314 | S2 | 6:56 | 15:10 | 494 | 1566 | < | 79.0 | < | 6.5 |
| 94 | Friday, March 14, 2014 | S3031414 | S3 | 6:58 | 15:00 | 482 | 1528 | | 65.0 | < | 6.6 |
| 95 | Monday, March 17, 2014 | S2031714 | S2 | 6:48 | 15:17 | 509 | 1619 | < | 62.0 | < | 6.3 |
| 96 | Tuesday, March 18, 2014 | S3031814 | S3 | 7:00 | 15:08 | 488 | 1542 | < | 65.0 | < | 6.6 |
| 97 | Wednesday, March 19, 2014 | S3031914 | S3 | 7:05 | 15:20 | 495 | 1574 | | 95.0 | < | 6.4 |
| 98 | Thursday, March 20, 2014 | S1032014 | S1 | 6:28 | 16:34 | 606 | 1939 | < | 52.0 | < | 5.2 |
| 99 | Friday, March 21, 2014 | S3032114 | S3 | 6:50 | 15:28 | 518 | 1658 | < | 60.0 | < | 6.1 |
| 100 | Monday, March 24, 2014 | **S2032414*** | S2 | 6:50 | 16:12 | 562 | 1796 | < | 56.0 | < | 5.6 |
| 101 | Tuesday, March 25, 2014 | **S2032514*** | S2 | 6:57 | 15:15 | 498 | 1,594 | < | 63.0 | < | 6.4 |
| 102 | Wednesday, March 26, 2014 | **S2032614*** | S2 | 6:48 | 15:06 | 498 | 1,601 | | 91.0 | < | 6.3 |
| 103 | Thursday, March 27, 2014 | S1032714 | S1 | 7:02 | 15:06 | 484 | 1,549 | < | 65.0 | < | 6.5 |
| 104 | Friday, March 28, 2014 | S1032814 | S1 | 6:45 | 15:33 | 528 | 1,700 | | 72.0 | < | 6.0 |
| 105 | Monday, March 31, 2014 | S2033114 | S2 | 6:56 | 15:06 | 490 | 1,480 | < | 63.0 | < | 6.4 |
| 106 | Tuesday, April 01, 2014 | 553UH | S2 | 6:42 | 15:00 | 498 | 1,594 | < | 63.0 | < | 6.4 |
| 107 | Wednesday, April 02, 2014 | 558UH | S1 | 6:53 | 15:05 | 492 | 1,574 | < | 64.0 | < | 6.4 |
| 108 | Thursday, April 03, 2014 | S2040314 | S2 | 6:46 | 15:20 | 514 | 1,660 | < | 60.0 | < | 6.1 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 109 | Friday, April 04, 2014 | S3040414 | S3 | 6:58 | 15:16 | 498 | 1,559 | < | 64.0 | < | 6.5 |
| 110 | Monday, April 07, 2014 | S2040714 | S2 | 6:55 | 16:50 | 595 | 1,934 | | 68.0 | | 14.0 |
| 111 | Tuesday, April 08, 2014 | S1MET040814 | S1 | 6:50 | 15:33 | 523 | 1,674 | | | | |
| 112 | Wednesday, April 09, 2014 | S2040914 | S2 | 6:56 | 15:10 | 494 | 1,586 | < | 63.0 | < | 6.4 |
| 113 | Thursday, April 10, 2014 | S4041014 | S4 | 6:50 | 15:56 | 546 | 1,731 | < | 58.0 | < | 5.8 |
| 114 | Friday, April 11, 2014 | S4041114 | S4 | 6:56 | 15:32 | 516 | 1,646 | | 77.0 | < | 6.1 |
| 115 | Monday, April 14, 2014 | S4041414 | S4 | 6:34 | 15:23 | 529 | 1,693 | < | 59.0 | < | 5.9 |
| 116 | Tuesday, April 15, 2014 | S4041514 | S4 | 6:34 | 16:33 | 599 | 1,926 | < | 52.0 | < | 10.0 |
| 117 | Wednesday, April 16, 2014 | S3041614 | S3 | 6:57 | 17:03 | 606 | 1,936 | < | 52.0 | < | 10.0 |
| 118 | Thursday, April 17, 2014 | S4041714 | S4 | 6:55 | 15:59 | 544 | 1,724 | < | 58.0 | < | 12.0 |
| 119 | Friday, April 18, 2014 | S4041814 | S4 | 6:45 | 15:07 | 502 | 1,591 | < | 63.0 | < | 13.0 |
| 120 | Monday, April 21, 2014 | S2042114 | S2 | 6:50 | 17:50 | 660 | 1,914 | < | 52.0 | < | 5.3 |
| 121 | Tuesday, April 22, 2014 | S2042214 | S2 | 6:46 | 17:30 | 644 | 2,054 | < | 49.0 | < | 4.9 |
| 122 | Wednesday, April 23, 2014 | S1042314 | S1 | 6:43 | 15:10 | 507 | 1,617 | < | 62.0 | < | 6.2 |
| 123 | Thursday, April 24, 2014 | S2042414 | S2 | 6:43 | 15:00 | 497 | 1,588 | | 81.0 | < | 6.3 |
| 124 | Friday, April 25, 2014 | S1042514 | S1 | 6:38 | 15:03 | 505 | 1,603 | < | 62.0 | < | 6.3 |
| 125 | Monday, April 28, 2014 | **S2042814*** | S2 | 6:29 | 15:27 | 538 | 1,732 | < | 58.0 | | 14.0 |
| 126 | Tuesday, April 29, 2014 | **S4042914*** | S4 | 6:35 | 16:55 | 620 | 1,981 | < | 50.0 | < | 5.1 |
| 127 | Wednesday, April 30, 2014 | **S2043014*** | S2 | 6:23 | 16:12 | 589 | 1,897 | < | 53.0 | < | 5.3 |
| 128 | Thursday, May 01, 2014 | S3050114 | S3 | 6:22 | 16:10 | 588 | 1,876 | < | 53.0 | < | 5.4 |
| 129 | Friday, May 02, 2014 | S4050214 | S4 | 6:35 | 15:29 | 534 | 1,698 | < | 59.0 | < | 5.9 |
| 130 | Monday, May 05, 2014 | S2050514 | S2 | 6:53 | 17:15 | 622 | 1,994 | < | 50.0 | < | 5.1 |
| 131 | Tuesday, May 06, 2014 | S2050614 | S2 | 6:39 | 17:20 | 641 | 2,048 | < | 49.0 | < | 4.9 |
| 132 | Wednesday, May 07, 2014 | S2050714 | S2 | 6:50 | 15:39 | 529 | 1,688 | < | 59.0 | < | 6.0 |
| 133 | Thursday, May 08, 2014 | S3050814 | S3 | 6:48 | 15:20 | 512 | 1,654 | < | 60.0 | < | 6.1 |
| 134 | Friday, May 09, 2014 | S4050914 | S4 | 7:00 | 15:08 | 488 | 1,559 | < | 64.0 | < | 6.5 |
| 135 | Monday, May 12, 2014 | S1051214 | S1 | 6:42 | 16:00 | 558 | 1,786 | | 82.0 | < | 5.7 |
| 136 | Tuesday, May 13, 2014 | S4051314 | S4 | 6:43 | 15:30 | 527 | 1,734 | | 61.0 | | 9.0 |
| 137 | Wednesday, May 14, 2014 | S4051414 | S4 | 6:40 | 18:00 | 680 | 2,237 | | 50.0 | < | 4.5 |
| 138 | Friday, May 16, 2014 | S2051614 | S2 | 6:40 | 15:12 | 512 | 1,644 | < | 61.0 | < | 6.2 |
| 139 | Monday, May 19, 2014 | **S2051914*** | S2 | 6:38 | 17:55 | 677 | 2,237 | < | 45.0 | < | 4.5 |
| 140 | Tuesday, May 20, 2014 | S2052014 | S2 | 6:33 | 15:26 | 533 | 1,706 | < | 59.0 | < | 6.0 |
| 141 | Wednesday, May 21, 2014 | S3052114 | S3 | 6:27 | 15:30 | 543 | 1,732 | < | 58.0 | < | 5.9 |
| 142 | Thursday, May 22, 2014 | S30522UG | S3 | 6:29 | 15:27 | 538 | 1,718 | < | 58.0 | | 9.2 |
| 143 | Friday, May 23, 2014 | S30523UG | S3 | 6:29 | 14:11 | 462 | 1,474 | < | 58.0 | < | 6.9 |
| 144 | Tuesday, May 27, 2014 | S1052714 | S1 | 6:18 | 15:20 | 542 | 1,734 | < | 58.0 | | 6.8 |
| 145 | Wednesday, May 28, 2014 | S3052814 | S3 | 6:45 | 16:13 | 568 | 1,820 | < | 55.0 | < | 5.6 |
| 146 | Thursday, May 29, 2014 | S2052914 | S2 | 6:25 | 17:50 | 685 | 2,189 | < | 46.0 | < | 4.6 |
| 147 | Friday, May 30, 2014 | S2053014 | S2 | 6:40 | 15:02 | 502 | 1,608 | < | 62.0 | < | 6.3 |
| 148 | Monday, June 02, 2014 | S1060214 | S1 | 6:38 | 15:30 | 532 | 1,686 | < | 59.0 | < | 6.0 |
| 149 | Tuesday, June 03, 2014 | S1060314 | S1 | 6:26 | 15:30 | 544 | 1,730 | | 12.0 | | 9.3 |
| 150 | Wednesday, June 04, 2014 | S3060414 | S3 | 6:30 | 17:17 | 647 | 2,067 | < | 48.0 | | 7.1 |
| 151 | Thursday, June 05, 2014 | S3060514 | S3 | 6:58 | 16:00 | 542 | 1,734 | < | 58.0 | < | 5.8 |
| 152 | Monday, June 09, 2014 | S4060914 | S4 | 6:38 | 15:29 | 531 | 1,699 | < | 59.0 | < | 6.0 |
| 153 | Tuesday, June 10, 2014 | S2061014 | S2 | 6:42 | 15:15 | 513 | 1,631 | < | 61.0 | < | 6.2 |
| 154 | Wednesday, June 11, 2014 | S3061114 | S3 | 7:00 | 17:17 | 617 | 1,962 | < | 63.0 | < | 6.4 |
| 155 | Thursday, June 12, 2014 | S3061214 | S3 | 7:10 | 15:36 | 506 | 1,596 | < | 63.0 | < | 6.4 |
| 156 | Friday, June 13, 2014 | S2061314 | S2 | 6:40 | 15:15 | 515 | 1,633 | < | 61.0 | < | 6.2 |
| 157 | Monday, June 16, 2014 | S2061614 | S2 | 6:28 | 15:08 | 520 | 1,643 | < | 61.0 | | 9.2 |
| 158 | Tuesday, June 17, 2014 | S2061714 | S2 | 6:56 | 15:17 | 501 | 1,598 | < | 63.0 | < | 6.4 |
| 159 | Wednesday, June 18, 2014 | S2061814 | S2 | 6:42 | 14:20 | 458 | 1,468 | | 100.0 | | 8.6 |
| 160 | Thursday, June 19, 2014 | S2061914 | S2 | 5:45 | 15:16 | 571 | 1,853 | | 62.0 | < | 5.5 |
| 161 | Friday, June 20, 2014 | S3062014 | S3 | 6:15 | 14:15 | 480 | 1,483 | | 78.0 | < | 6.9 |
| 162 | Monday, June 23, 2014 | S3062314 | S3 | 6:15 | 14:40 | 505 | 1,579 | < | 63.0 | < | 6.4 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 163 | Tuesday, June 24, 2014 | S3062414 | S3 | 6:30 | 14:20 | 470 | 1,459 | < | 69.0 | < | 7.0 |
| 164 | Wednesday, June 25, 2014 | S2062514 | S2 | 6:30 | 14:40 | 490 | 1,563 | < | 64.0 | < | 6.5 |
| 165 | Thursday, June 26, 2014 | **S2062614*** | S2 | 5:58 | 14:20 | 502 | 1,551 | < | 64.0 | < | 6.6 |
| 166 | Friday, June 27, 2014 | **S2062714*** | S2 | 6:15 | 14:23 | 488 | 1,518 | < | 66.0 | | 6.9 |
| 167 | Monday, June 30, 2014 | **S2063014*** | S2 | 5:58 | 14:35 | 517 | 1,647 | < | 61.0 | < | 6.2 |
| 168 | Tuesday, July 01, 2014 | S2070114 | S2 | 5:55 | 15:26 | 571 | 1,861 | < | 54.0 | < | 5.5 |
| 169 | Wednesday, July 02, 2014 | S2070214 | S2 | 5:51 | 15:23 | 572 | 1,830 | | 61.0 | < | 5.6 |
| 170 | Thursday, July 03, 2014 | S2070314 | S2 | 5:50 | 15:12 | 562 | 1,807 | < | 55.0 | | 11.0 |
| 171 | Monday, July 07, 2014 | S1070714 | S1 | 6:15 | 14:45 | 510 | 1,627 | < | 62.0 | < | 6.2 |
| 172 | Tuesday, July 08, 2014 | S2070814 | S2 | 6:07 | 15:30 | 563 | 1,793 | < | 56.0 | < | 5.7 |
| 173 | Wednesday, July 09, 2014 | S2070914 | S2 | 6:35 | 14:32 | 477 | 1,524 | < | 66.0 | | 15.0 |
| 174 | Thursday, July 10, 2014 | S3071014 | S3 | 6:35 | 15:20 | 525 | 1,683 | < | 59.0 | < | 6.0 |
| 175 | Friday, July 11, 2014 | S2071114 | S2 | 6:01 | 14:22 | 501 | 1,596 | < | 63.0 | | 8.0 |
| 176 | Monday, July 14, 2014 | S1071414 | S1 | 6:15 | 14:35 | 500 | 1,605 | < | 62.0 | | 7.1 |
| 177 | Tuesday, July 15, 2014 | S2071514 | S2 | 5:50 | 14:28 | 518 | 1,660 | < | 60.0 | | 8.3 |
| 178 | Wednesday, July 16, 2014 | S2071614 | S2 | 5:29 | 14:25 | 536 | 1,750 | < | 57.0 | | 7.3 |
| 179 | Thursday, July 17, 2014 | S2071714 | S2 | 5:53 | 15:19 | 566 | 1,873 | < | 53.0 | < | 5.4 |
| 180 | Friday, July 18, 2014 | S3071814 | S3 | 5:49 | 14:17 | 508 | 1,629 | < | 63.0 | < | 6.2 |
| 181 | Monday, July 21, 2014 | **S2072114*** | S2 | 5:52 | 14:08 | 496 | 1,622 | < | 62.0 | < | 6.2 |
| 182 | Tuesday, July 22, 2014 | **S1072214*** | S1 | 5:58 | 14:20 | 502 | 1,604 | | 97.0 | < | 6.3 |
| 183 | Wednesday, July 23, 2014 | **S1072314*** | S1 | 6:03 | 15:30 | 567 | 1,837 | | 17.0 | < | 5.5 |
| 184 | Thursday, July 24, 2014 | S2072414 | S2 | 5:53 | 15:30 | 577 | 1,820 | < | 55.0 | < | 5.6 |
| 185 | Friday, July 25, 2014 | S2072514 | S2 | 5:50 | 14:30 | 520 | 1,672 | < | 60.0 | < | 6.1 |
| 186 | Monday, July 28, 2014 | S1072814 | S1 | 5:46 | 14:45 | 539 | 1,719 | < | 58.0 | < | 5.9 |
| 187 | Tuesday, July 29, 2014 | S2072914 | S2 | 5:58 | 14:36 | 518 | 1,658 | < | 60.0 | < | 6.1 |
| 188 | Wednesday, July 30, 2014 | S2073014 | S2 | 5:50 | 14:30 | 520 | 1,670 | < | 55.0 | < | 5.6 |
| 189 | Thursday, July 31, 2014 | S1073114 | S1 | 5:46 | 15:08 | 562 | 1,807 | < | 55.0 | < | 5.6 |
| 190 | Friday, August 01, 2014 | S1080114 | S1 | 5:50 | 14:30 | 520 | 1,659 | | 100.0 | < | 6.1 |
| 191 | Monday, August 04, 2014 | S3080414 | S3 | 6:00 | 15:50 | 590 | 1,894 | | 71.0 | < | 5.4 |
| 192 | Tuesday, August 05, 2014 | S2080514 | S2 | 5:47 | 14:40 | 533 | 1,706 | < | 59.0 | < | 6.0 |
| 193 | Wednesday, August 06, 2014 | S2080614 | S2 | 5:50 | 16:15 | 625 | 1,978 | < | 51.0 | < | 5.1 |
| 194 | Thursday, August 07, 2014 | **S2080714*** | S2 | 5:49 | 16:05 | 616 | 1,999 | < | 50.0 | < | 5.1 |
| 195 | Friday, August 08, 2014 | **S2080814*** | S2 | 5:58 | 15:00 | 542 | 1,729 | < | 58.0 | < | 5.9 |
| 196 | Monday, August 11, 2014 | S3081114 | S3 | 5:58 | 14:30 | 512 | 1,641 | < | 61.0 | < | 6.2 |
| 197 | Tuesday, August 12, 2014 | S4081214 | S4 | 6:05 | 14:30 | 505 | 1,611 | < | 62.0 | < | 6.3 |
| 198 | Wednesday, August 13, 2014 | S1081314 | S1 | 5:53 | 14:30 | 517 | 1,665 | < | 60.0 | < | 6.1 |
| 199 | Thursday, August 14, 2014 | S2081414 | S2 | 5:57 | 14:30 | 513 | 1,611 | < | 61.0 | < | 6.2 |
| 200 | Friday, August 15, 2014 | S2081514 | S2 | 5:59 | 14:30 | 511 | 1,635 | < | 61.0 | < | 6.2 |
| 201 | Monday, August 18, 2014 | S2081814 | S2 | 5:58 | 14:30 | 512 | 1,646 | < | 61.0 | < | 6.2 |
| 202 | Tuesday, August 19, 2014 | S3081914 | S3 | 5:59 | 16:00 | 601 | 1,914 | < | 52.0 | < | 5.3 |
| 203 | Wednesday, August 20, 2014 | S4082014 | S4 | 5:57 | 14:30 | 513 | 1,636 | < | 61.0 | < | 6.2 |
| 204 | Thursday, August 21, 2014 | S4082114 | S4 | 5:45 | 15:00 | 555 | 1,795 | < | 56.0 | < | 5.7 |
| 205 | Friday, August 22, 2014 | S4082214 | S4 | 5:48 | 14:30 | 522 | 1,676 | < | 60.0 | < | 6.1 |
| 206 | Monday, August 25, 2014 | **S2082514*** | S2 | 6:04 | 15:30 | 566 | 1,800 | < | 56.0 | < | 5.7 |
| 207 | Tuesday, August 26, 2014 | S1082614 | S1 | 5:51 | 16:04 | 613 | 1,974 | < | 51.0 | < | 5.2 |
| 208 | Wednesday, August 27, 2014 | **S3082714*** | S3 | 6:03 | 14:30 | 507 | 1,640 | | 90.0 | < | 6.2 |
| 209 | Thursday, August 28, 2014 | S2082814 | S2 | 5:48 | 14:30 | 522 | 1,670 | < | 60.0 | < | 6.1 |
| 210 | Friday, August 29, 2014 | S2082914 | S2 | 5:56 | 13:20 | 444 | 1,434 | < | 70.0 | < | 7.1 |
| 211 | Tuesday, September 02, 2014 | S1090214 | S1 | 6:28 | 15:00 | 512 | 1,638 | < | 61.0 | < | 6.2 |
| 212 | Wednesday, September 03, 2014 | S2090314 | S2 | 6:28 | 15:00 | 512 | 1,628 | < | 61.0 | < | 6.3 |
| 213 | Thursday, September 04, 2014 | S2090414 | S2 | 6:26 | 15:00 | 514 | 1,635 | < | 61.0 | < | 6.2 |
| 214 | Friday, September 05, 2014 | S2090514 | S2 | 6:22 | 15:02 | 520 | 1,667 | < | 60.0 | < | 6.1 |
| 215 | Monday, September 08, 2014 | S3090814 | S3 | 6:40 | 15:00 | 500 | 1,642 | < | 61.0 | < | 6.2 |
| 216 | Tuesday, September 09, 2014 | S4090914 | S4 | 6:30 | 15:00 | 510 | 1,637 | < | 61.0 | < | 6.2 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 217 | Wednesday, September 10, 2014 | S2091014 | S2 | 6:23 | 15:00 | 517 | 1,649 | < | 61.0 | < | 6.2 |
| 218 | Friday, September 12, 2014 | S2091214 | S2 | 6:26 | 15:00 | 514 | 1,691 | | 71.0 | < | 6.0 |
| 219 | Monday, September 15, 2014 | **S2091514*** | S2 | 6:23 | 15:00 | 517 | 1,644 | < | 61.0 | < | 6.2 |
| 220 | Tuesday, September 16, 2014 | **S1091614*** | S1 | 6:33 | 15:30 | 537 | 1,721 | < | 58.0 | < | 5.9 |
| 221 | Wednesday, September 17, 2014 | **S3091714*** | S3 | 6:23 | 15:00 | 517 | 1,706 | < | 59.0 | < | 6.0 |
| 222 | Thursday, September 18, 2014 | S2091814 | S2 | 6:28 | 15:07 | 519 | 1,710 | < | 58.0 | < | 5.9 |
| 223 | Friday, September 19, 2014 | S3091914 | S3 | 6:35 | 15:00 | 505 | 1,661 | | 73.0 | < | 6.1 |
| 224 | Monday, September 22, 2014 | S2092214 | S2 | 6:29 | 17:00 | 631 | 2,003 | < | 50.0 | < | 5.1 |
| 225 | Tuesday, September 23, 2014 | S2092314 | S2 | 6:26 | 16:58 | 632 | 2,060 | < | 48.0 | < | 4.9 |
| 226 | Wednesday, September 24, 2014 | S2092414 | S2 | 6:25 | 17:15 | 650 | 2,204 | < | 45.0 | < | 4.6 |
| 227 | Thursday, September 25, 2014 | S3092514 | S3 | 6:36 | 15:00 | 504 | 1,714 | < | 58.0 | < | 12.0 |
| 228 | Friday, September 26, 2014 | S2092614 | S2 | 6:23 | 16:55 | 632 | 2,130 | < | 47.0 | < | 9.5 |
| 229 | Monday, September 29, 2014 | S3092914 | S3 | 6:34 | 17:18 | 644 | 2,128 | | 51.0 | < | 4.8 |
| 230 | Tuesday, September 30, 2014 | S3093014 | S3 | 6:40 | 17:14 | 634 | 2,124 | < | 47.0 | < | 4.8 |
| 231 | Wednesday, October 01, 2014 | S2100114 | S2 | 6:40 | 17:20 | 640 | 2,134 | < | 47.0 | < | 4.7 |
| 232 | Thursday, October 02, 2014 | S4100214 | S4 | 6:28 | 17:05 | 637 | 2,134 | < | 47.0 | < | 4.7 |
| 233 | Friday, October 03, 2014 | S2100314 | S2 | 6:40 | 17:15 | 635 | 2,118 | < | 47.0 | < | 4.8 |
| 234 | Tuesday, October 07, 2014 | S1100714 | S1 | 6:57 | 17:12 | 615 | 2,017 | < | 50.0 | < | 5.0 |
| 235 | Wednesday, October 08, 2014 | S1100814 | S1 | 6:43 | 17:15 | 632 | 2,120 | < | 47.0 | < | 4.8 |
| 236 | Thursday, October 09, 2014 | S2100914 | S2 | 6:35 | 17:15 | 640 | 2,173 | < | 46.0 | < | 4.6 |
| 237 | Friday, October 10, 2014 | S2101014 | S2 | 6:44 | 17:10 | 626 | 2,078 | < | 48.0 | < | 4.9 |
| 238 | Monday, October 13, 2014 | S3101314 | S3 | 6:53 | 15:28 | 515 | 1,718 | < | 58.0 | < | 5.9 |
| 239 | Tuesday, October 14, 2014 | S1101414 | S1 | 7:12 | 17:18 | 606 | 2,036 | < | 49.0 | < | 5.0 |
| 240 | Wednesday, October 15, 2014 | S4101514 | S4 | 6:20 | 17:17 | 657 | 2,175 | < | 46.0 | < | 4.6 |
| 241 | Thursday, October 16, 2014 | S2101614 | S2 | 6:15 | 17:03 | 648 | 2,151 | < | 46.0 | < | 4.7 |
| 242 | Friday, October 17, 2014 | S1101714 | S1 | 6:58 | 17:10 | 612 | 2,066 | < | 48.0 | < | 4.9 |
| 243 | Monday, October 20, 2014 | **S1102014*** | S1 | 6:35 | 17:12 | 637 | 2,108 | < | 47.0 | | 6.5 |
| 244 | Tuesday, October 21, 2014 | **S2102114*** | S2 | 6:37 | 17:19 | 642 | 2,147 | | 58.0 | < | 4.7 |
| 245 | Wednesday, October 22, 2014 | S3102214 | S3 | 6:36 | 17:13 | 637 | 2,121 | < | 47.0 | < | 4.8 |
| 246 | Thursday, October 23, 2014 | S3102314 | S3 | 6:33 | 17:10 | 637 | 2,153 | < | 46.0 | < | 4.7 |
| 247 | Friday, October 24, 2014 | S2102414 | S2 | 6:37 | 17:15 | 638 | 2,118 | < | 47.0 | < | 4.8 |
| 248 | Monday, October 27, 2014 | S1102714 | S1 | 6:33 | 17:18 | 645 | 2,148 | < | 47.0 | < | 4.7 |
| 249 | Tuesday, October 28, 2014 | S2102814 | S2 | 6:30 | 15:22 | 532 | 1,769 | < | 56.0 | < | 5.7 |
| 250 | Wednesday, October 29, 2014 | S2102914 | S2 | 6:32 | 15:26 | 534 | 1,768 | < | 57.0 | < | 5.7 |
| 251 | Thursday, October 30, 2014 | S4103014 | S4 | 6:36 | 15:27 | 531 | 1,755 | < | 57.0 | < | 5.7 |
| 252 | Friday, October 31, 2014 | S2103114 | S2 | 6:32 | 15:19 | 527 | 1,744 | < | 57.0 | < | 5.8 |
| 253 | Monday, November 03, 2014 | S2110314 | S2 | 6:32 | 15:28 | 536 | 1,788 | < | 56.0 | < | 5.6 |
| 254 | Tuesday, November 04, 2014 | S4110414 | S4 | 6:30 | 15:28 | 538 | 1,781 | < | 56.0 | < | 5.6 |
| 255 | Wednesday, November 05, 2014 | S1110514 | S1 | 6:43 | 15:16 | 513 | 1,688 | < | 59.0 | < | 5.9 |
| 256 | Thursday, November 06, 2014 | S4110614 | S4 | 6:26 | 15:14 | 528 | 1,758 | < | 57.0 | < | 5.7 |
| 257 | Friday, November 07, 2014 | S4110714 | S4 | 6:23 | 15:23 | 540 | 1,790 | < | 56.0 | < | 5.6 |
| 258 | Monday, November 10, 2014 | **S4111014*** | S4 | 6:33 | 15:34 | 541 | 1,793 | | 66.0 | < | 5.6 |
| 259 | Tuesday, November 11, 2014 | **S3111114*** | S3 | 6:39 | 15:06 | 507 | 1,678 | < | 60.0 | < | 6.0 |
| 260 | Wednesday, November 12, 2014 | **S2111214*** | S2 | 6:28 | 15:06 | 518 | 1,717 | < | 58.0 | < | 5.9 |
| 261 | Thursday, November 13, 2014 | S2111314 | S2 | 6:26 | 15:10 | 524 | 1,769 | < | 56.0 | < | 5.7 |
| 262 | Friday, November 14, 2014 | S4111414 | S4 | 6:23 | 15:19 | 536 | 1,820 | < | 22.0 | < | 5.5 |
| 263 | Monday, November 17, 2014 | S2111714 | S2 | 6:33 | 15:34 | 541 | 1,788 | < | 56.0 | < | 5.7 |
| 264 | Tuesday, November 18, 2014 | S1111814 | S1 | 6:48 | 15:20 | 512 | 1,702 | < | 59.0 | < | 5.9 |
| 265 | Wednesday, November 19, 2014 | S1111914 | S1 | 6:36 | 15:22 | 526 | 1,744 | | 92.0 | | 6.4 |
| 266 | Thursday, November 20, 2014 | S1112018 | S1 | 6:29 | 15:18 | 529 | 1,722 | < | 56.0 | < | 5.7 |
| 267 | Friday, November 21, 2014 | S1112118 | S1 | 6:42 | 15:26 | 524 | 1,758 | < | 57.0 | < | 5.7 |
| 268 | Monday, November 24, 2014 | S2112414 | S2 | 6:44 | 15:18 | 514 | 1,704 | < | 59.0 | < | 5.9 |
| 269 | Tuesday, November 25, 2014 | S1112514 | S1 | 6:29 | 15:31 | 542 | 1,794 | < | 56.0 | < | 5.6 |
| 270 | Wednesday, November 26, 2014 | S2112614 | S2 | 6:22 | 14:00 | 458 | 1,555 | < | 64.0 | < | 6.5 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 271 | Monday, December 01, 2014 | S1120114 | S1 | 6:26 | 15:22 | 536 | 1,830 | < | 55.0 | < | 5.5 |
| 272 | Tuesday, December 02, 2014 | S3120214 | S3 | 6:37 | 15:18 | 521 | 1,584 | < | 63.0 | < | 6.3 |
| 273 | Wednesday, December 03, 2014 | S4120314 | S4 | 6:39 | 15:21 | 522 | 1,728 | < | 58.0 | < | 5.8 |
| 274 | Thursday, December 04, 2014 | S2120414 | S2 | 6:50 | 15:21 | 511 | 1,656 | < | 60.0 | < | 6.0 |
| 275 | Friday, December 05, 2014 | S3100514 | S3 | 6:57 | 15:17 | 500 | 1,613 | < | 62.0 | < | 6.4 |
| 276 | Monday, December 08, 2014 | S3120814 | S3 | 6:55 | 17:00 | 605 | 2,012 | < | 50.0 | < | 5.0 |
| 277 | Tuesday, December 09, 2014 | S2120914 | S2 | 6:42 | 15:12 | 510 | 1,688 | < | 59.0 | < | 5.9 |
| 278 | Wednesday, December 10, 2014 | S2121014 | S2 | 6:24 | 15:21 | 537 | 1,697 | < | 59.0 | < | 5.9 |
| 279 | Thursday, December 11, 2014 | S1121114 | S1 | 6:29 | 15:30 | 541 | 1,769 | < | 56.0 | < | 5.7 |
| 280 | Friday, December 12, 2014 | S2121214 | S2 | 6:55 | 15:23 | 508 | 1,681 | < | 60.0 | < | 6.0 |
| 281 | Monday, December 15, 2014 | S2121514 | S2 | 6:45 | 15:25 | 520 | 1,711 | < | 58.0 | < | 5.9 |
| 282 | Tuesday, December 16, 2014 | S2121614 | S2 | 6:45 | 16:00 | 555 | 1,826 | < | 55.0 | < | 5.5 |
| 283 | Wednesday, December 17, 2014 | S2121714 | S2 | 6:33 | 15:28 | 535 | 1,771 | < | 56.0 | < | 5.7 |
| 284 | Thursday, December 18, 2014 | **S2121814*** | S2 | 6:48 | 15:22 | 514 | 1,629 | < | 61.0 | < | 6.2 |
| 285 | Friday, December 19, 2014 | **S2121914*** | S2 | 6:42 | 15:20 | 518 | 1,655 | < | 60.0 | < | 6.1 |
| 286 | Monday, December 22, 2014 | S3122214 | S3 | 6:40 | 15:23 | 523 | 1,828 | < | 55.0 | < | 5.5 |
| 287 | Tuesday, December 23, 2014 | S3122314 | S3 | 6:44 | 15:21 | 517 | 1,680 | < | 60.0 | < | 6.0 |
| 288 | Wednesday, December 24, 2014 | S3122414 | S3 | 6:36 | 12:47 | 371 | 1,217 | < | 82.0 | < | 8.2 |
| 289 | Monday, December 29, 2014 | S2122914 | S2 | 6:34 | 15:35 | 541 | 1,837 | < | 54.0 | < | 5.5 |
| 290 | Tuesday, December 30, 2014 | S3123014 | S3 | 6:58 | 15:26 | 508 | 1,699 | < | 59.0 | < | 5.9 |
| 291 | Wednesday, December 31, 2014 | S2123114 | S2 | 6:31 | 13:50 | 439 | 1,482 | < | 68.0 | < | 6.8 |
| 292 | Monday, January 05, 2015 | S2010515 | S2 | 6:29 | 15:18 | 529 | 1,801 | < | 56.0 | < | 5.6 |
| 293 | Tuesday, January 06, 2015 | S2010615 | S2 | 6:50 | 15:26 | 516 | 1,651 | < | 61.0 | < | 6.1 |
| 294 | Wednesday, January 07, 2015 | S2010715 | S2 | 6:50 | 15:30 | 520 | 1,664 | < | 60.0 | < | 6.0 |
| 295 | Thursday, January 08, 2015 | S2010815 | S2 | 6:50 | 15:20 | 510 | 1,683 | < | 59.0 | < | 6.0 |
| 296 | Friday, January 09, 2015 | S2010915 | S2 | 6:50 | 15:32 | 522 | 1,697 | < | 59.0 | < | 5.9 |
| 297 | Monday, January 12, 2015 | S2011215 | S2 | 6:45 | 15:27 | 522 | 1,762 | < | 57.0 | < | 5.7 |
| 298 | Tuesday, January 13, 2015 | **S2011315*** | S2 | 7:00 | 15:26 | 506 | 1,695 | < | 59.0 | < | 5.9 |
| 299 | Wednesday, January 14, 2015 | **S2011415*** | S2 | 7:00 | 15:28 | 508 | 1,727 | < | 58.0 | < | 5.8 |
| 300 | Thursday, January 15, 2015 | S2011515 | S2 | 6:45 | 15:27 | 522 | 1,749 | < | 57.0 | < | 5.7 |
| 301 | Friday, January 16, 2015 | S2011615 | S2 | 6:45 | 15:30 | 525 | 1,772 | | 57.0 | < | 5.7 |
| 302 | Monday, January 19, 2015 | S2011915 | S2 | 6:42 | 15:25 | 523 | 1,752 | < | 57.0 | < | 11.0 |
| 303 | Tuesday, January 20, 2015 | S2012015 | S2 | 6:45 | 15:40 | 535 | 1,819 | < | 55.0 | < | 11.0 |
| 304 | Wednesday, January 21, 2015 | S3012115 | S3 | 6:50 | 15:26 | 516 | 1,754 | < | 57.0 | < | 11.0 |
| 305 | Thursday, January 22, 2015 | S3012215 | S3 | 6:50 | 15:24 | 514 | 1,748 | < | 57.0 | < | 12.0 |
| 306 | Friday, January 23, 2015 | S2012315 | S2 | 7:00 | 15:20 | 500 | 1,700 | < | 59.0 | < | 12.0 |
| 307 | Monday, January 26, 2015 | S3012615 | S3 | 6:40 | 14:56 | 496 | 1,674 | < | 60.0 | < | 12.0 |
| 308 | Wednesday, January 28, 2015 | S2012815 | S2 | 7:30 | 15:23 | 473 | 1,585 | < | 63.0 | < | 6.3 |
| 309 | Thursday, January 29, 2015 | S2012915 | S2 | 7:05 | 15:22 | 497 | 1,677 | < | 60.0 | < | 6.0 |
| 310 | Friday, January 30, 2015 | S2013015 | S2 | 7:05 | 15:20 | 495 | 1,671 | < | 60.0 | < | 6.0 |
| 311 | Tuesday, February 03, 2015 | S2020315 | S2 | 7:00 | 15:03 | 483 | 1,630 | < | 61.0 | < | 6.2 |
| 312 | Wednesday, February 04, 2015 | S2020415 | S2 | 7:05 | 15:20 | 495 | 1,683 | < | 59.0 | < | 6.0 |
| 313 | Thursday, February 05, 2015 | S2020515 | S2 | 7:07 | 16:10 | 543 | 1,819 | < | 55.0 | < | 5.5 |
| 314 | Friday, February 06, 2015 | S2020615 | S2 | 7:05 | 15:10 | 485 | 1,613 | < | 62.0 | < | 6.2 |
| 315 | Monday, February 09, 2015 | S2020915 | S2 | 7:05 | 15:26 | 501 | 1,703 | < | 59.0 | < | 5.9 |
| 316 | Tuesday, February 10, 2015 | S2021015 | S2 | 7:05 | 15:40 | 515 | 1,738 | < | 58.0 | < | 5.8 |
| 317 | Wednesday, February 11, 2015 | S2021115 | S2 | 7:05 | 15:28 | 503 | 1,710 | < | 58.0 | < | 5.9 |
| 318 | Thursday, February 12, 2015 | S2021215 | S2 | 7:10 | 15:20 | 490 | 1,642 | < | 61.0 | < | 6.1 |
| 319 | Friday, February 13, 2015 | S2021315 | S2 | 7:15 | 15:15 | 480 | 1,608 | < | 62.0 | < | 6.2 |
| 320 | Tuesday, February 17, 2015 | S2021715 | S2 | 7:30 | 15:30 | 480 | 1,608 | < | 62.0 | < | 6.2 |
| 321 | Wednesday, February 18, 2015 | S2021815 | S2 | 7:00 | 15:30 | 510 | 1,721 | | 72.0 | < | 5.8 |
| 322 | Thursday, February 19, 2015 | S2021915 | S2 | 7:05 | 15:41 | 516 | 1,754 | < | 57.0 | < | 5.7 |
| 323 | Friday, February 20, 2015 | S2'022015 | S2 | 6:55 | 15:13 | 498 | 1,668 | < | 60.0 | < | 6.0 |
| 324 | Monday, February 23, 2015 | **S2022315*** | S2 | 6:55 | 15:35 | 520 | 1,742 | < | 57.0 | < | 5.8 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 325 | Tuesday, February 24, 2015 | **S2022415*** | S2 | 7:05 | 15:20 | 495 | 1,671 | < | 60.0 | < | 6.0 |
| 326 | Wednesday, February 25, 2015 | S2022515 | S2 | 7:10 | 15:15 | 485 | 1,649 | < | 61.0 | < | 6.1 |
| 327 | Thursday, February 26, 2015 | S2022615 | S2 | 7:05 | 15:22 | 497 | 1,690 | < | 59.0 | < | 5.9 |
| 328 | Friday, February 27, 2015 | S2022715 | S2 | 7:07 | 15:10 | 483 | 1,630 | < | 61.0 | < | 6.2 |
| 329 | Monday, March 02, 2015 | S2030215 | S2 | 7:05 | 15:32 | 507 | 1,698 | < | 59.0 | < | 5.9 |
| 330 | Tuesday, March 03, 2015 | S2030314 | S2 | 6:26 | 15:22 | 536 | 1,796 | < | 56.0 | < | 5.6 |
| 331 | Wednesday, March 04, 2015 | S3020415 | S3 | 6:32 | 15:25 | 533 | 1,727 | < | 58.0 | < | 5.8 |
| 332 | Thursday, March 05, 2015 | S1030515 | S1 | 6:33 | 14:20 | 467 | 1,520 | < | 66.0 | < | 6.6 |
| 333 | Friday, March 06, 2015 | S3030615 | S3 | 7:10 | 15:22 | 492 | 1,587 | < | 63.0 | < | 6.4 |
| 334 | Monday, March 09, 2015 | S2030915 | S2 | 6:27 | 15:20 | 533 | 1,722 | < | 58.0 | < | 5.9 |
| 335 | Tuesday, March 10, 2015 | S2031015 | S2 | 6:22 | 15:18 | 536 | 1,721 | < | 58.0 | < | 5.9 |
| 336 | Wednesday, March 11, 2015 | S2031115 | S2 | 6:45 | 15:20 | 515 | 1,859 | < | 54.0 | < | 5.4 |
| 337 | Thursday, March 12, 2015 | S1031215 | S1 | 6:25 | 15:21 | 536 | 1,956 | < | 51.0 | < | 5.2 |
| 338 | Friday, March 13, 2015 | S2021315 | S2 | 6:23 | 15:26 | 543 | 1,966 | < | 51.0 | < | 5.1 |
| 339 | Monday, March 16, 2015 | S1031615 | S1 | 6:22 | 15:31 | 549 | 1,825 | < | 55.0 | < | 5.5 |
| 340 | Tuesday, March 17, 2015 | S2031715 | S2 | 6:18 | 15:20 | 542 | 1,805 | < | 55.0 | < | 5.6 |
| 341 | Wednesday, March 18, 2015 | S1031815 | S1 | 6:23 | 15:25 | 542 | 1,808 | < | 55.0 | < | 5.6 |
| 342 | Thursday, March 19, 2015 | S2031915 | S2 | 6:22 | 15:22 | 540 | 1,812 | < | 55.0 | < | 5.6 |
| 343 | Friday, March 20, 2015 | S4032015 | S4 | 6:35 | 14:23 | 468 | 1,542 | | 72.0 | < | 6.5 |
| 344 | Monday, March 23, 2015 | S2032315 | S2 | 6:28 | 15:20 | 532 | 1,769 | < | 56.0 | < | 5.7 |
| 345 | Tuesday, March 24, 2015 | S3032415 | S3 | 6:23 | 15:22 | 539 | 1,795 | < | 56.0 | < | 5.6 |
| 346 | Wednesday, March 25, 2015 | S2032515 | S2 | 6:26 | 15:13 | 527 | 1,760 | | 96.0 | < | 5.7 |
| 347 | Thursday, March 26, 2015 | S2032615 | S2 | 6:26 | 15:12 | 526 | 1,744 | < | 57.0 | < | 5.8 |
| 348 | Friday, March 27, 2015 | S1032715 | S1 | 6:28 | 15:09 | 521 | 1,730 | < | 58.0 | < | 5.8 |
| 349 | Monday, March 30, 2015 | S2033015 | S2 | 6:32 | 15:16 | 524 | 1,742 | < | 57.0 | < | 5.8 |
| 350 | Tuesday, March 31, 2015 | S1033115 | S1 | 6:36 | 15:12 | 516 | 1,743 | < | 57.0 | < | 5.8 |
| 351 | Wednesday, April 01, 2015 | S1040115 | S1 | 6:25 | 15:09 | 524 | 1,732 | < | 58.0 | < | 5.8 |
| 352 | Thursday, April 02, 2015 | S2040215 | S2 | 6:28 | 15:10 | 522 | 1,743 | < | 57.0 | < | 5.8 |
| 353 | Friday, April 03, 2015 | S2040315 | S2 | 6:55 | 15:10 | 495 | 1,634 | < | 61.0 | < | 6.1 |
| 354 | Monday, April 06, 2015 | S1040615 | S1 | 6:18 | 15:28 | 550 | 1,832 | | 62.0 | < | 5.5 |
| 355 | Tuesday, April 07, 2015 | S2040715 | S2 | 6:20 | 15:22 | 542 | 1,791 | | 70.0 | < | 5.6 |
| 356 | Wednesday, April 08, 2015 | S3040815 | S3 | 6:21 | 15:08 | 527 | 1,750 | < | 57.0 | < | 5.7 |
| 357 | Thursday, April 09, 2015 | S3040915 | S3 | 6:20 | 15:12 | 532 | 1,758 | < | 57.0 | < | 5.7 |
| 358 | Friday, April 10, 2015 | S2041015 | S2 | 6:17 | 15:19 | 542 | 1,802 | < | 56.0 | < | 5.6 |
| 359 | Monday, April 13, 2015 | S2041315 | S2 | 7:00 | 15:27 | 507 | 1,610 | | 67.0 | < | 6.2 |
| 360 | Tuesday, April 14, 2015 | S1041415 | S1 | 7:15 | 15:15 | 480 | 1,560 | < | 64.0 | < | 6.4 |
| 361 | Wednesday, April 15, 2015 | S2041515 | S2 | 7:10 | 15:20 | 490 | 1,605 | < | 62.0 | < | 6.3 |
| 362 | Thursday, April 16, 2015 | **S3041615*** | S3 | 7:00 | 15:20 | 500 | 1,688 | < | 59.0 | < | 5.9 |
| 363 | Friday, April 17, 2015 | **S2041715*** | S2 | 7:00 | 15:25 | 505 | 1,704 | | 130.0 | < | 5.9 |
| 364 | Monday, April 20, 2015 | **S4042015*** | S4 | 7:00 | 15:31 | 511 | 1,622 | | 88.0 | < | 6.2 |
| 365 | Tuesday, April 21, 2015 | S1042115 | S1 | 7:00 | 15:31 | 511 | 1,725 | < | 58.0 | < | 5.8 |
| 366 | Wednesday, April 22, 2015 | S2042215 | S2 | 7:05 | 15:15 | 490 | 1,646 | < | 61.0 | < | 6.1 |
| 367 | Thursday, April 23, 2015 | S2042315 | S2 | 7:10 | 15:55 | 525 | 1,680 | < | 60.0 | < | 6.0 |
| 368 | Friday, April 24, 2015 | S1042415 | S1 | 7:30 | 15:15 | 465 | 1,696 | < | 59.0 | < | 5.9 |
| 369 | Monday, April 27, 2015 | S2042715 | S2 | 7:00 | 15:30 | 510 | 1,721 | < | 58.0 | < | 5.8 |
| 370 | Tuesday, April 28, 2015 | S2042815 | S2 | 7:00 | 15:15 | 495 | 1,678 | < | 60.0 | < | 6.0 |
| 371 | Wednesday, April 29, 2015 | S2042915 | S2 | 6:53 | 15:22 | 509 | 1,654 | < | 60.0 | < | 6.1 |
| 372 | Thursday, April 30, 2015 | S3043015 | S3 | 7:00 | 15:20 | 500 | 1,645 | | 64.0 | < | 6.1 |
| 373 | Friday, May 01, 2015 | S2050115 | S2 | 7:00 | 15:30 | 510 | 1,709 | < | 58.0 | < | 5.9 |
| 374 | Monday, May 04, 2015 | S2050415 | S2 | 7:00 | 15:30 | 510 | 1,670 | < | 60.0 | < | 6.0 |
| 375 | Tuesday, May 05, 2015 | S3050515 | S3 | 7:10 | 15:24 | 494 | 1,667 | < | 60.0 | < | 6.0 |
| 376 | Wednesday, May 06, 2015 | S2050615 | S2 | 7:05 | 15:28 | 503 | 1,635 | | 62.0 | < | 6.1 |
| 377 | Thursday, May 07, 2015 | S3050715 | S3 | 7:10 | 15:53 | 523 | 1,713 | < | 58.0 | < | 5.8 |
| 378 | Friday, May 08, 2015 | S2050815 | S2 | 7:00 | 15:15 | 495 | 1,636 | < | 61.0 | < | 6.1 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 379 | Monday, May 11, 2015 | S2051115 | S2 | 7:00 | 15:40 | 520 | 1,703 | < | 59.0 | < | 5.9 |
| 380 | Tuesday, May 12, 2015 | S1051215 | S1 | 7:00 | 15:24 | 504 | 1,701 | < | 59.0 | < | 5.9 |
| 381 | Wednesday, May 13, 2015 | S1051315 | S1 | 6:35 | 15:23 | 528 | 1,830 | < | 55.0 | < | 5.5 |
| 382 | Thursday, May 14, 2015 | S2051415 | S2 | 6:55 | 15:20 | 505 | 1,722 | < | 58.0 | < | 5.8 |
| 383 | Friday, May 15, 2015 | S2051515 | S2 | 6:50 | 15:15 | 505 | 1,659 | < | 60.0 | < | 6.0 |
| 384 | Monday, May 18, 2015 | **S3051815*** | S3 | 6:50 | 15:27 | 517 | 1,750 | < | 57.0 | < | 5.7 |
| 385 | Tuesday, May 19, 2015 | **S2051915*** | S2 | 6:45 | 15:13 | 508 | 1,709 | < | 58.0 | < | 5.9 |
| 386 | Wednesday, May 20, 2015 | **S1052015*** | S1 | 7:00 | 15:15 | 495 | 1,663 | | 100.0 | | 10.0 |
| 387 | Thursday, May 21, 2015 | **S2052115*** | S2 | 7:00 | 15:16 | 496 | 1,669 | < | 60.0 | < | 6.0 |
| 388 | Friday, May 22, 2015 | S1052215 | S1 | 7:00 | 14:20 | 440 | 1,492 | < | 67.0 | < | 6.7 |
| 389 | Tuesday, May 26, 2015 | S2052615 | S2 | 6:00 | 14:20 | 500 | 1,695 | < | 59.0 | < | 5.9 |
| 390 | Wednesday, May 27, 2015 | S2052715 | S2 | 5:32 | 14:18 | 526 | 1,867 | < | 54.0 | < | 5.4 |
| 391 | Thursday, May 28, 2015 | S2052815 | S2 | 6:10 | 14:51 | 521 | 1,808 | < | 55.0 | < | 5.5 |
| 392 | Friday, May 29, 2015 | S2052915 | S2 | 6:05 | 14:23 | 498 | 1,706 | < | 59.0 | | 6.1 |
| 393 | Monday, June 01, 2015 | S3060115 | S3 | 6:10 | 14:27 | 497 | 1,685 | < | 59.0 | < | 6.0 |
| 394 | Tuesday, June 02, 2015 | S3060215 | S3 | 6:05 | 14:28 | 503 | 1,750 | < | 57.0 | < | 5.7 |
| 395 | Wednesday, June 03, 2015 | S2060315 | S2 | 6:00 | 14:20 | 500 | 1,712 | < | 58.0 | < | 5.9 |
| 396 | Thursday, June 04, 2015 | S3060415 | S3 | 6:00 | 14:23 | 503 | 1,705 | < | 59.0 | < | 5.9 |
| 397 | Friday, June 05, 2015 | S2060515 | S2 | 6:00 | 14:20 | 500 | 1,685 | < | 59.0 | < | 6.0 |
| 398 | Monday, June 08, 2015 | **S2060815*** | S2 | 5:42 | 14:30 | 528 | 1,713 | < | 58.0 | < | 5.9 |
| 399 | Tuesday, June 09, 2015 | **S2060915*** | S2 | 6:00 | 15:25 | 565 | 1,873 | < | 53.0 | < | 5.4 |
| 400 | Wednesday, June 10, 2015 | **S3061015*** | S3 | 6:00 | 16:08 | 608 | 2,019 | < | 50.0 | < | 5.0 |
| 401 | Thursday, June 11, 2015 | S1061115 | S1 | 6:00 | 15:30 | 570 | 1,927 | < | 52.0 | | 8.1 |
| 402 | Friday, June 12, 2015 | S2061215 | S2 | 6:00 | 15:40 | 580 | 1,908 | | 67.0 | | 5.8 |
| 403 | Monday, June 15, 2015 | S2061515 | S2 | 5:50 | 14:25 | 515 | 1,692 | < | 59.0 | < | 5.9 |
| 404 | Tuesday, June 16, 2015 | S3061615 | S3 | 6:00 | 14:25 | 505 | 1,687 | < | 59.0 | < | 5.9 |
| 405 | Wednesday, June 17, 2015 | S2061715 | S2 | 6:00 | 15:45 | 585 | 1,942 | < | 51.0 | < | 5.1 |
| 406 | Thursday, June 18, 2015 | S3061815 | S3 | 6:00 | 14:15 | 495 | 1,681 | < | 59.0 | < | 5.9 |
| 407 | Friday, June 19, 2015 | S1061915 | S1 | 6:00 | 14:20 | 500 | 1,687 | < | 59.0 | < | 5.9 |
| 408 | Monday, June 22, 2015 | S1062215 | S1 | 5:50 | 14:25 | 515 | 1,746 | < | 57.0 | < | 5.7 |
| 409 | Tuesday, June 23, 2015 | S2062315 | S2 | 5:50 | 15:16 | 566 | 1,913 | < | 52.0 | < | 5.2 |
| 410 | Wednesday, June 24, 2015 | S2062415 | S2 | 5:50 | 14:26 | 516 | 1,742 | < | 57.0 | < | 5.7 |
| 411 | Thursday, June 25, 2015 | S2062515 | S2 | 5:50 | 15:38 | 588 | 1,987 | < | 50.0 | < | 5.0 |
| 412 | Friday, June 26, 2015 | S3062615 | S3 | 5:50 | 15:25 | 575 | 1,935 | < | 52.0 | < | 5.2 |
| 413 | Monday, June 29, 2015 | S1062915 | S1 | 5:50 | 15:15 | 565 | 1,924 | < | 52.0 | < | 5.2 |
| 414 | Tuesday, June 30, 2015 | S2063015 | S2 | 5:50 | 15:00 | 550 | 1,867 | < | 54.0 | < | 5.4 |
| 415 | Wednesday, July 01, 2015 | S1070115 | S1 | 5:50 | 14:50 | 540 | 1,812 | < | 55.0 | < | 5.5 |
| 416 | Thursday, July 02, 2015 | S2070215 | S2 | 6:00 | 14:20 | 500 | 1,695 | < | 59.0 | < | 5.9 |
| 417 | Monday, July 06, 2015 | S2070615 | S2 | 5:55 | 15:35 | 580 | 1,960 | < | 51.0 | < | 5.2 |
| 418 | Tuesday, July 07, 2015 | S3070715 | S3 | 6:00 | 15:00 | 540 | 1,806 | < | 55.0 | < | 5.6 |
| 419 | Wednesday, July 08, 2015 | S1070815 | S1 | 5:45 | 14:24 | 519 | 1,702 | < | 59.0 | < | 5.9 |
| 420 | Thursday, July 09, 2015 | S2070915 | S2 | 5:50 | 15:00 | 550 | 1,834 | < | 55.0 | < | 5.5 |
| 421 | Friday, July 10, 2015 | S2071015 | S2 | 5:50 | 14:25 | 515 | 1,725 | < | 58.0 | < | 5.9 |
| 422 | Monday, July 13, 2015 | S2071315 | S2 | 5:55 | 16:00 | 605 | 2,018 | < | 50.0 | | 6.2 |
| 423 | Tuesday, July 14, 2015 | S4071415 | S4 | 5:55 | 14:30 | 515 | 1,728 | < | 58.0 | < | 5.9 |
| 424 | Wednesday, July 15, 2015 | S2071515 | S2 | 5:50 | 14:35 | 525 | 1,754 | < | 57.0 | < | 5.8 |
| 425 | Thursday, July 16, 2015 | S3071615 | S3 | 5:50 | 16:05 | 615 | 2,060 | < | 49.0 | < | 4.9 |
| 426 | Friday, July 17, 2015 | S4071715 | S4 | 5:50 | 16:00 | 610 | 2,050 | < | 49.0 | < | 5.0 |
| 427 | Monday, July 20, 2015 | S1072015 | S1 | 5:50 | 17:50 | 720 | 2,560 | < | 39.0 | < | 4.0 |
| 428 | Tuesday, July 21, 2015 | S1072115 | S1 | 5:50 | 16:20 | 630 | 2,155 | < | 46.0 | < | 4.7 |
| 429 | Wednesday, July 22, 2015 | S1072215 | S1 | 5:48 | 16:02 | 614 | 2,207 | | 49.0 | | 4.7 |
| 430 | Thursday, July 23, 2015 | S2072315 | S2 | 5:55 | 16:35 | 640 | 2,234 | < | 45.0 | < | 4.6 |
| 431 | Friday, July 24, 2015 | S2072415 | S2 | 6:30 | 17:00 | 630 | 2,246 | | 76.0 | | 5.9 |
| 432 | Monday, July 27, 2015 | **S2072715*** | S2 | 5:58 | 15:10 | 552 | 1,899 | < | 53.0 | | 5.5 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 433 | Tuesday, July 28, 2015 | **S2072815*** | S2 | 5:47 | 16:22 | 635 | 2,216 | < | 45.0 | | 4.9 |
| 434 | Wednesday, July 29, 2015 | **S2072915*** | S2 | 5:50 | 16:05 | 615 | 2,134 | < | 47.0 | < | 4.8 |
| 435 | Thursday, July 30, 2015 | S3073015 | S3 | 6:00 | 15:12 | 552 | 1,899 | < | 53.0 | < | 5.4 |
| 436 | Friday, July 31, 2015 | S2073115 | S2 | 5:50 | 16:15 | 625 | 2,184 | < | 46.0 | < | 4.7 |
| 437 | Monday, August 03, 2015 | **S3080315*** | S3 | 6:05 | 16:15 | 610 | 2,123 | < | 47.0 | < | 4.8 |
| 438 | Tuesday, August 04, 2015 | **S2080415*** | S2 | 6:10 | 17:20 | 670 | 2,301 | < | 43.0 | < | 4.4 |
| 439 | Wednesday, August 05, 2015 | **S2080515*** | S2 | 6:00 | 17:05 | 665 | 2,294 | < | 44.0 | < | 4.5 |
| 440 | Thursday, August 06, 2015 | S1080615 | S1 | 6:00 | 16:30 | 630 | 2,167 | < | 46.0 | < | 4.7 |
| 441 | Friday, August 07, 2015 | S3080715 | S3 | 6:00 | 17:45 | 705 | 2,432 | | 130.0 | | 6.6 |
| 442 | Monday, August 10, 2015 | S2081015 | S2 | 5:51 | 16:00 | 609 | 2,144 | < | 47.0 | < | 4.8 |
| 443 | Wednesday, August 12, 2015 | S1081215 | S1 | 5:55 | 16:15 | 620 | 2,099 | < | 48.0 | < | 4.9 |
| 444 | Thursday, August 13, 2015 | S2081315 | S2 | 5:55 | 16:48 | 653 | 2,227 | < | 45.0 | < | 4.6 |
| 445 | Friday, August 14, 2015 | S2081415 | S2 | 5:55 | 14:40 | 525 | 1,780 | < | 56.0 | < | 5.7 |
| 446 | Monday, August 17, 2015 | S2081715 | S2 | 5:55 | 14:45 | 530 | 1,821 | < | 55.0 | < | 5.6 |
| 447 | Tuesday, August 18, 2015 | S2081815 | S2 | 5:50 | 14:30 | 520 | 1,758 | < | 57.0 | < | 5.8 |
| 448 | Wednesday, August 19, 2015 | S3081915 | S3 | 5:55 | 14:45 | 530 | 1,794 | < | 56.0 | < | 5.7 |
| 449 | Thursday, August 20, 2015 | S4082015 | S4 | 5:55 | 14:40 | 525 | 1,753 | < | 57.0 | < | 5.8 |
| 450 | Friday, August 21, 2015 | S1082115 | S1 | 6:00 | 14:15 | 495 | 1,646 | < | 61.0 | < | 6.2 |
| 451 | Monday, August 24, 2015 | S1082415 | S1 | 6:00 | 15:05 | 545 | 1,848 | < | 54.0 | < | 5.5 |
| 452 | Tuesday, August 25, 2015 | S4082515 | S4 | 6:00 | 14:30 | 510 | 1,721 | < | 58.0 | | 6.3 |
| 453 | Wednesday, August 26, 2015 | S1082615 | S1 | 6:00 | 14:30 | 510 | 1,731 | < | 58.0 | < | 5.9 |
| 454 | Thursday, August 27, 2015 | S1082715 | S1 | 6:00 | 14:40 | 520 | 1,760 | < | 57.0 | < | 5.8 |
| 455 | Friday, August 28, 2015 | S2082815 | S2 | 6:00 | 14:30 | 510 | 1,711 | < | 58.0 | < | 6.0 |
| 456 | Monday, August 31, 2015 | S2083115 | S2 | 6:00 | 15:05 | 545 | 1,850 | < | 54.0 | < | 5.5 |
| 457 | Tuesday, September 01, 2015 | S1090115 | S1 | 6:00 | 15:20 | 560 | 1,870 | | 67.0 | < | 5.5 |
| 458 | Wednesday, September 02, 2015 | S2090215 | S2 | 6:00 | 14:25 | 505 | 1,702 | < | 59.0 | < | 6.0 |
| 459 | Thursday, September 03, 2015 | S2090315 | S2 | 5:50 | 15:08 | 558 | 1,964 | | 63.0 | < | 5.2 |
| 460 | Friday, September 04, 2015 | S3090415 | S3 | 5:48 | 13:22 | 454 | 1,580 | | 65.0 | < | 6.5 |
| 461 | Tuesday, September 08, 2015 | S2090815 | S2 | 6:30 | 15:00 | 510 | 1,754 | < | 57.0 | < | 5.9 |
| 462 | Wednesday, September 09, 2015 | S4090915 | S4 | 6:30 | 15:30 | 540 | 1,866 | < | 54.0 | < | 5.5 |
| | Thursday, September 10, 2015 | S2091015 | S2 | SAMPLE DISCARDED DUE TO RAIN WATER COLLECTED INSIDE SAMPLING CASSETTE | | | | | | | |
| 463 | Friday, September 11, 2015 | S2091115 | S2 | 6:30 | 15:00 | 510 | 1,719 | < | 58.0 | < | 6.0 |
| 464 | Monday, September 14, 2015 | S1091415 | S1 | 6:30 | 16:30 | 600 | 2,061 | < | 49.0 | < | 5.0 |
| 465 | Tuesday, September 15, 2015 | S1091515 | S1 | 6:30 | 16:34 | 604 | 2,042 | < | 49.0 | < | 5.0 |
| 466 | Wednesday, September 16, 2015 | S2091615 | S2 | 6:30 | 16:00 | 570 | 1,924 | < | 52.0 | < | 5.3 |
| 467 | Thursday, September 17, 2015 | S2091715 | S2 | 6:30 | 17:30 | 660 | 2,234 | | 77.0 | < | 4.6 |
| 468 | Friday, September 18, 2015 | S2091815 | S2 | 6:30 | 17:00 | 630 | 2,139 | < | 47.0 | < | 4.8 |
| 469 | Monday, September 21, 2015 | S2092115 | S2 | 6:30 | 16:40 | 610 | 2,065 | | 61.0 | | 10.0 |
| 470 | Tuesday, September 22, 2015 | **S2092215*** | S2 | 6:28 | 18:40 | 732 | 2,500 | < | 40.0 | < | 4.1 |
| 471 | Wednesday, September 23, 2015 | **S2092315*** | S2 | 6:12 | 16:58 | 646 | 2,180 | < | 46.0 | < | 4.7 |
| 472 | Thursday, September 24, 2015 | **S3092415*** | S3 | 6:30 | 17:00 | 630 | 2,133 | < | 47.0 | < | 4.8 |
| 473 | Friday, September 25, 2015 | S3092515 | S3 | 6:30 | 16:00 | 570 | 1,870 | < | 53.0 | < | 5.5 |
| 474 | Monday, September 28, 2015 | S3092815 | S3 | 6:14 | 17:00 | 646 | 2,167 | | 70.0 | < | 4.7 |
| 475 | Tuesday, September 29, 2015 | S3092915 | S3 | 6:28 | 16:36 | 608 | 2,064 | < | 48.0 | < | 5.0 |
| 476 | Wednesday, September 30, 2015 | S2093015 | S2 | 6:27 | 15:30 | 543 | 1,800 | < | 56.0 | < | 5.7 |
| 477 | Thursday, October 01, 2015 | S4100115 | S4 | 6:23 | 15:10 | 527 | 1,723 | < | 58.0 | < | 6.0 |
| 478 | Friday, October 02, 2015 | S3100215 | S3 | 6:25 | 15:15 | 530 | 1,775 | < | 56.0 | < | 5.8 |
| 479 | Monday, October 05, 2015 | S2100515 | S2 | 6:25 | 18:12 | 707 | 1,443 | < | 69.0 | < | 7.1 |
| 480 | Tuesday, October 06, 2015 | S1100615 | S1 | 6:53 | 18:00 | 667 | 2,254 | < | 44.0 | < | 4.6 |
| 481 | Wednesday, October 07, 2015 | S2100715 | S2 | 6:55 | 17:57 | 662 | 2,234 | < | 45.0 | < | 4.6 |
| 482 | Thursday, October 08, 2015 | S2100815 | S2 | 6:55 | 17:55 | 660 | 2,228 | < | 45.0 | < | 4.6 |
| 483 | Friday, October 09, 2015 | S3100915 | S3 | 7:00 | 15:45 | 525 | 1,767 | < | 57.0 | < | 5.8 |
| 484 | Monday, October 12, 2015 | **S2101215*** | S2 | 6:52 | 15:00 | 488 | 1,571 | < | 64.0 | < | 6.5 |
| 485 | Tuesday, October 13, 2015 | **S1101315*** | S1 | 6:57 | 15:20 | 503 | 1,637 | < | 61.0 | < | 6.3 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 486 | Wednesday, October 14, 2015 | **S1101415*** | S1 | 6:56 | 15:23 | 507 | 1,706 | < | 59.0 | < | 6.0 |
| 487 | Thursday, October 15, 2015 | **S2101515*** | S2 | 6:55 | 15:23 | 508 | 1,605 | < | 62.0 | < | 6.4 |
| 488 | Friday, October 16, 2015 | S1101615 | S1 | 6:53 | 15:30 | 517 | 1,755 | < | 57.0 | < | 5.8 |
| 489 | Monday, October 19, 2015 | S1101915 | S1 | 6:53 | 15:23 | 510 | 1,744 | < | 57.0 | < | 5.8 |
| 490 | Tuesday, October 20, 2015 | S2102015 | S2 | 7:26 | 15:32 | 486 | 1,626 | < | 62.0 | < | 6.2 |
| 491 | Wednesday, October 21, 2015 | S1102115 | S1 | 6:55 | 15:26 | 511 | 1,653 | | 68.0 | < | 6.1 |
| 492 | Thursday, October 22, 2015 | S2102215 | S2 | 6:45 | 15:00 | 495 | 1,671 | < | 60.0 | < | 6.1 |
| 493 | Friday, October 23, 2015 | S2102315 | S2 | 6:56 | 15:22 | 506 | 1,682 | < | 59.0 | < | 6.0 |
| 494 | Monday, October 26, 2015 | S2102615 | S2 | 6:50 | 15:30 | 520 | 1,763 | < | 57.0 | < | 5.8 |
| 495 | Tuesday, October 27, 2015 | S2102715 | S2 | 7:20 | 15:10 | 470 | 1,582 | < | 63.0 | < | 6.4 |
| 496 | Wednesday, October 28, 2015 | S3102815 | S3 | 6:50 | 15:15 | 505 | 1,712 | | VOID | | VOID |
| 497 | Thursday, October 29, 2015 | S2102915 | S2 | 6:51 | 15:05 | 494 | 1,655 | < | 60.0 | < | 6.1 |
| 498 | Friday, October 30, 2015 | S2103015 | S2 | 6:50 | 15:12 | 502 | 1,707 | < | 59.0 | < | 5.9 |
| 499 | Monday, November 02, 2015 | S1110215 | S1 | 7:00 | 15:44 | 524 | 1,771 | < | 56.0 | < | 5.7 |
| 500 | Tuesday, November 03, 2015 | S3110315 | S3 | 7:10 | 15:15 | 485 | 1,639 | < | 61.0 | < | 6.2 |
| 501 | Wednesday, November 04, 2015 | S3110415 | S3 | 7:00 | 15:30 | 510 | 1,726 | < | 58.0 | < | 5.8 |
| 502 | Thursday, November 05, 2015 | S3110515 | S3 | 7:00 | 15:35 | 515 | 1,738 | < | 58.0 | < | 5.8 |
| 503 | Friday, November 06, 2015 | S2110615 | S2 | 6:55 | 15:20 | 505 | 1,707 | < | 59.0 | < | 5.9 |
| 504 | Monday, November 09, 2015 | S2110915 | S2 | 7:10 | 15:00 | 470 | 1,591 | < | 63.0 | < | 6.4 |
| 505 | Tuesday, November 10, 2015 | S3111015 | S3 | 7:05 | 15:21 | 496 | 1,672 | < | 60.0 | < | 6.0 |
| 506 | Wednesday, November 11, 2015 | S11115 | S1 | 7:05 | 15:03 | 478 | 1,611 | < | 62.0 | < | 6.3 |
| 507 | Thursday, November 12, 2015 | S2111215 | S2 | 7:05 | 15:05 | 480 | 1,620 | < | 62.0 | < | 6.2 |
| 508 | Friday, November 13, 2015 | S1111315 | S1 | 7:00 | 15:05 | 485 | 1,644 | < | 61.0 | < | 6.1 |
| 509 | Monday, November 16, 2015 | S1111615 | S1 | 6:55 | 15:30 | 515 | 1,741 | < | 57.0 | < | 5.8 |
| 510 | Tuesday, November 17, 2015 | S2111715 | S2 | 7:00 | 15:15 | 495 | 1,668 | < | 60.0 | < | 6.0 |
| 511 | Wednesday, November 18, 2015 | S3111815 | S3 | 6:55 | 15:15 | 500 | 1,685 | < | 59.0 | < | 6.0 |
| 512 | Thursday, November 19, 2015 | S4111915 | S4 | 7:00 | 15:10 | 490 | 1,654 | < | 60.0 | < | 6.1 |
| 513 | Friday, November 20, 2015 | S1112015 | S1 | 7:15 | 15:20 | 485 | 1,644 | < | 61.0 | < | 6.1 |
| 514 | Monday, November 23, 2015 | S1112315 | S1 | 6:55 | 15:35 | 520 | 1,763 | < | 57.0 | < | 5.7 |
| 515 | Tuesday, November 24, 2015 | S1112415 | S1 | 6:55 | 15:15 | 500 | 1,695 | < | 59.0 | < | 5.9 |
| 516 | Wednesday, November 25, 2015 | S1112515 | S1 | 6:55 | 14:00 | 425 | 1,439 | < | 69.0 | < | 7.0 |
| 517 | Monday, November 30, 2015 | **S1113015*** | S1 | 6:50 | 15:27 | 517 | 1,747 | < | 57.0 | < | 5.7 |
| 518 | Tuesday, December 01, 2015 | S4120115 | S4 | 6:55 | 15:20 | 505 | 1,712 | < | 58.0 | < | 5.9 |
| 519 | Wednesday, December 02, 2015 | S2120215 | S2 | 7:06 | 15:28 | 502 | 1,702 | < | 59.0 | < | 5.9 |
| 520 | Thursday, December 03, 2015 | S2120315 | S2 | 6:56 | 15:25 | 509 | 1,726 | < | 58.0 | < | 5.8 |
| 521 | Friday, December 04, 2015 | **S1120415*** | S1 | 6:50 | 15:20 | 510 | 1,731 | < | 58.0 | < | 5.8 |
| 522 | Monday, December 07, 2015 | S1120715 | S1 | 6:45 | 15:35 | 530 | 1,797 | | 57.0 | < | 5.6 |
| 523 | Tuesday, December 08, 2015 | S1120815 | S1 | 6:50 | 15:15 | 505 | 1,707 | < | 59.0 | < | 5.9 |
| 524 | Wednesday, December 09, 2015 | S1120915 | S1 | 6:55 | 15:20 | 505 | 1,709 | | 71.0 | < | 5.9 |
| 525 | Thursday, December 10, 2015 | S1121015 | S1 | 6:52 | 15:22 | 510 | 1,724 | < | 58.0 | < | 5.8 |
| 526 | Friday, December 11, 2015 | S2121115 | S2 | 6:46 | 15:25 | 519 | 1,762 | < | 57.0 | < | 5.7 |
| 527 | Monday, December 14, 2015 | S4121415 | S4 | 6:50 | 15:10 | 500 | 1,705 | | 68.0 | < | 5.9 |
| 528 | Tuesday, December 15, 2015 | S1121515 | S1 | 6:50 | 15:15 | 505 | 1,712 | < | 58.0 | < | 5.8 |
| 529 | Wednesday, December 16, 2015 | S1121615 | S1 | 6:50 | 15:07 | 497 | 1,685 | < | 59.0 | < | 5.9 |
| 530 | Thursday, December 17, 2015 | S1121715 | S1 | 6:50 | 15:35 | 525 | 1,788 | < | 56.0 | < | 5.6 |
| 531 | Friday, December 18, 2015 | S1121815 | S1 | 6:50 | 15:20 | 510 | 1,719 | < | 58.0 | < | 5.8 |
| 532 | Monday, December 21, 2015 | S2122115 | S2 | 6:45 | 15:35 | 530 | 1,791 | < | 56.0 | < | 5.6 |
| 533 | Tuesday, December 22, 2015 | S2122215 | S2 | 6:55 | 15:23 | 508 | 1,727 | < | 58.0 | < | 5.8 |
| 534 | Wednesday, December 23, 2015 | S1122315 | S1 | 6:50 | 14:05 | 435 | 1,479 | < | 68.0 | < | 6.8 |
| 535 | Monday, December 28, 2015 | S4122815 | S4 | 6:52 | 15:20 | 508 | 1,712 | < | 58.0 | < | 5.8 |
| 536 | Tuesday, December 29, 2015 | S3122915 | S3 | 6:55 | 15:32 | 517 | 1,745 | < | 57.0 | < | 5.7 |
| 537 | Wednesday, December 30, 2015 | S4123015 | S4 | 6:48 | 15:26 | 518 | 1,761 | < | 57.0 | < | 5.7 |
| 538 | Thursday, December 31, 2015 | S1123115 | S1 | 8:57 | 14:05 | 308 | 1,023 | < | 98.0 | < | 9.8 |
| 539 | Monday, January 04, 2016 | S1010416 | S1 | 6:50 | 15:35 | 525 | 1,782 | | 98.0 | < | 5.6 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 540 | Tuesday, January 05, 2016 | S1010516 | S1 | 7:00 | 15:20 | 500 | 1,690 | < | 59.0 | < | 5.9 |
| 541 | Wednesday, January 06, 2016 | S2010616 | S2 | 6:48 | 15:15 | 507 | 1,721 | < | 58.0 | < | 5.8 |
| 542 | Thursday, January 07, 2016 | S1010716 | S1 | 6:55 | 15:20 | 505 | 1,717 | | 79.0 | < | 5.8 |
| 543 | Friday, January 08, 2016 | S1010816 | S1 | 7:00 | 15:10 | 490 | 1,664 | | 82.0 | < | 6.0 |
| 544 | Monday, January 11, 2016 | S1011116 | S1 | 6:45 | 15:35 | 530 | 1,844 | < | 54.0 | < | 5.4 |
| 545 | Tuesday, January 12, 2016 | S2011216 | S2 | 7:00 | 15:33 | 513 | 1,793 | < | 56.0 | < | 5.6 |
| 546 | Wednesday, January 13, 2016 | S1011316 | S1 | 6:43 | 15:27 | 524 | 1,816 | < | 55.0 | < | 5.5 |
| 547 | Thursday, January 14, 2016 | S1011416 | S1 | 7:23 | 15:28 | 485 | 1,758 | < | 57.0 | < | 5.7 |
| 548 | Friday, January 15, 2016 | S2011516 | S2 | 6:24 | 15:29 | 545 | 1,913 | < | 52.0 | < | 5.2 |
| 549 | Monday, January 18, 2016 | S1011816 | S1 | 6:36 | 15:31 | 535 | 1,929 | < | 52.0 | < | 5.2 |
| 550 | Tuesday, January 19, 2016 | S1011916 | S1 | 6:36 | 15:21 | 525 | 1,851 | | 73.0 | < | 5.4 |
| 551 | Wednesday, January 20, 2016 | S1012016 | S1 | 6:39 | 15:12 | 513 | 1,842 | < | 54.0 | < | 5.4 |
| 552 | Thursday, January 21, 2016 | S2012116 | S2 | 6:29 | 15:20 | 531 | 1,901 | < | 53.0 | < | 5.3 |
| | Friday, January 22, 2016 | S2012216 | S2 | SAMPLE DISCARDED DUE TO PUMP FAILURE | | | | | | | |
| 553 | Tuesday, January 26, 2016 | S1012616 | S1 | 6:47 | 15:10 | 503 | 1,773 | < | 56.0 | < | 5.6 |
| 554 | Wednesday, January 27, 2016 | S1012716 | S1 | 6:39 | 15:15 | 516 | 1,796 | < | 56.0 | < | 5.6 |
| 555 | Thursday, January 28, 2016 | S2012816 | S2 | 7:25 | 15:22 | 477 | 1,708 | < | 59.0 | < | 5.9 |
| 556 | Friday, January 29, 2016 | S2012916 | S2 | 6:27 | 15:27 | 540 | 1,885 | < | 53.0 | < | 5.3 |
| 557 | Monday, February 01, 2016 | S1020116 | S1 | 7:14 | 15:25 | 491 | 1,726 | < | 58.0 | < | 5.8 |
| 558 | Tuesday, February 02, 2016 | S1020216 | S1 | 7:10 | 15:21 | 491 | 1,714 | < | 58.0 | < | 5.8 |
| 559 | Wednesday, February 03, 2016 | S2020316 | S2 | 7:17 | 15:24 | 487 | 1,690 | < | 59.0 | < | 5.9 |
| 560 | Thursday, February 04, 2016 | S1020416 | S1 | 7:34 | 15:45 | 491 | 1,679 | < | 60.0 | < | 6.0 |
| 561 | Friday, February 05, 2016 | S1020516 | S1 | 7:05 | 15:40 | 515 | 1,761 | < | 57.0 | < | 5.7 |
| 562 | Monday, February 08, 2016 | S1020816 | S1 | 6:48 | 15:42 | 534 | 1,824 | | 55.0 | < | 5.5 |
| 563 | Tuesday, February 09, 2016 | S4020916 | S4 | 7:15 | 15:24 | 489 | 1,682 | < | 59.0 | < | 6.0 |
| 564 | Wednesday, February 10, 2016 | S1021016 | S1 | 7:34 | 15:03 | 449 | 1,529 | < | 65.0 | < | 6.5 |
| 565 | Thursday, February 11, 2016 | S1021116 | S1 | 7:21 | 15:21 | 480 | 1,634 | < | 61.0 | < | 6.1 |
| 566 | Friday, February 12, 2016 | S1021216 | S1 | 7:25 | 15:13 | 468 | 1,582 | < | 63.0 | < | 6.3 |
| 567 | Tuesday, February 16, 2016 | S1021616 | S1 | 9:17 | 15:20 | 363 | 1,207 | < | 83.0 | < | 8.4 |
| 568 | Wednesday, February 17, 2016 | S1021716 | S1 | 7:16 | 15:24 | 488 | 1,647 | < | 61.0 | < | 6.1 |
| 569 | Thursday, February 18, 2016 | S1021816 | S1 | 7:20 | 15:30 | 490 | 1,661 | < | 60.0 | < | 6.1 |
| 570 | Friday, February 19, 2016 | S4021916 | S4 | 7:16 | 15:24 | 488 | 1,623 | < | 62.0 | < | 6.2 |
| 571 | Monday, February 22, 2016 | S1022216 | S1 | 7:23 | 16:22 | 539 | 1,838 | < | 54.0 | < | 5.5 |
| 572 | Tuesday, February 23, 2016 | S4022316 | S4 | 7:40 | 15:22 | 462 | 1,578 | < | 63.0 | < | 6.4 |
| 573 | Wednesday, February 24, 2016 | S1022416 | S1 | 7:27 | 15:24 | 477 | 1,622 | < | 62.0 | < | 6.2 |
| 574 | Thursday, February 25, 2016 | S1022516 | S1 | 6:56 | 15:17 | 501 | 1,706 | < | 59.0 | < | 6.4 |
| 575 | Monday, February 29, 2016 | S4022916 | S4 | 7:19 | 15:41 | 502 | 1,717 | < | 58.0 | < | 5.9 |
| 576 | Tuesday, March 01, 2016 | S1030116 | S1 | 6:52 | 15:05 | 493 | 1,698 | < | 59.0 | < | 5.9 |
| 577 | Wednesday, March 02, 2016 | S1030216 | S1 | 7:27 | 15:33 | 486 | 1,660 | < | 60.0 | < | 6.1 |
| 578 | Thursday, March 03, 2016 | S1030316 | S1 | 6:51 | 15:17 | 506 | 1,738 | < | 58.0 | < | 5.8 |
| 579 | Friday, March 04, 2016 | S4030416 | S4 | 8:24 | 15:25 | 421 | 1,450 | < | 69.0 | < | 7.0 |
| 580 | Monday, March 07, 2016 | S1030716 | S1 | 6:53 | 15:20 | 507 | 1,731 | < | 58.0 | < | 5.8 |
| 581 | Tuesday, March 08, 2016 | S1030816 | S1 | 8:06 | 15:24 | 438 | 1,505 | | 200.0 | < | 6.7 |
| 582 | Wednesday, March 09, 2016 | S1030916 | S1 | 7:20 | 15:13 | 473 | 1,648 | | 91.0 | < | 6.1 |
| 583 | Thursday, March 10, 2016 | S1031016 | S1 | 6:53 | 15:38 | 525 | 1,816 | | 70.0 | < | 5.6 |
| 584 | Friday, March 11, 2016 | S1031116 | S1 | 7:12 | 15:14 | 482 | 1,653 | < | 60.0 | < | 6.1 |
| 585 | Monday, March 14, 2016 | S4031416 | S4 | 6:57 | 15:45 | 528 | 1,816 | < | 55.0 | < | 5.6 |
| 586 | Tuesday, March 15, 2016 | S1031516 | S1 | 7:17 | 15:32 | 495 | 1,708 | < | 59.0 | < | 5.9 |
| 587 | Wednesday, March 16, 2016 | S4031616 | S4 | 6:56 | 15:30 | 514 | 1,771 | < | 56.0 | < | 5.7 |
| 588 | Thursday, March 17, 2016 | S1031716 | S1 | 6:58 | 15:25 | 507 | 1,757 | < | 57.0 | < | 5.8 |
| 589 | Friday, March 18, 2016 | S1031816 | S1 | 6:50 | 15:35 | 525 | 1,817 | < | 55.0 | < | 5.6 |
| 590 | Monday, March 21, 2016 | S3032116 | S3 | 7:11 | 15:36 | 505 | 1,735 | < | 58.0 | < | 5.8 |
| 591 | Tuesday, March 22, 2016 | S1032216 | S1 | 6:52 | 15:40 | 528 | 1,811 | < | 55.0 | < | 5.6 |
| 592 | Wednesday, March 23, 2016 | S1032316 | S1 | 7:12 | 15:24 | 492 | 1,683 | < | 59.0 | < | 6.0 |

# TABLE 1B
# PAMP Data
# Hexavalent Chromium Air Samples

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 593 | Thursday, March 24, 2016 | S1032416 | S1 | 6:43 | 15:34 | 531 | 1,827 | | 100.0 | < | 5.5 |
| 594 | Friday, March 25, 2016 | S1032516 | S1 | 6:48 | 15:39 | 531 | 1,829 | | 69.0 | < | 5.5 |
| 595 | Monday, March 28, 2016 | S1032816 | S1 | 6:28 | 15:47 | 559 | 1,926 | < | 52.0 | < | 5.3 |
| 596 | Tuesday, March 29, 2016 | S1032916 | S1 | 6:38 | 16:11 | 573 | 1,983 | < | 50.0 | < | 5.1 |
| 597 | Wednesday, March 30, 2016 | S1033016 | S1 | 6:52 | 15:47 | 535 | 1,840 | < | 54.0 | < | 5.5 |
| 598 | Thursday, March 31, 2016 | S2033116 | S2 | 6:45 | 15:39 | 534 | 1,850 | < | 54.0 | < | 5.5 |
| 599 | Friday, April 01, 2016 | S4040116 | S4 | 6:53 | 15:25 | 512 | 1,764 | < | 57.0 | < | 5.8 |
| 600 | Monday, April 04, 2016 | S1040416 | S1 | 6:28 | 15:43 | 555 | 1,906 | < | 52.0 | < | 5.3 |
| 601 | Tuesday, April 05, 2016 | S1040516 | S1 | 6:37 | 15:25 | 528 | 1,806 | < | 55.0 | < | 5.6 |
| 602 | Wednesday, April 06, 2016 | S1040616 | S1 | 6:35 | 15:30 | 535 | 1,843 | < | 54.0 | < | 5.5 |
| 603 | Thursday, April 07, 2016 | S4040716 | S4 | 6:50 | 15:37 | 527 | 1,794 | < | 56.0 | < | 5.7 |
| 604 | Friday, April 08, 2016 | S1040816 | S1 | 6:47 | 15:31 | 524 | 1,810 | < | 55.0 | < | 5.6 |
| 605 | Monday, April 11, 2016 | S4041116 | S4 | 6:48 | 15:19 | 511 | 1,760 | < | 57.0 | < | 5.8 |
| 606 | Tuesday, April 12, 2016 | S1041216 | S1 | 6:43 | 15:28 | 525 | 1,809 | < | 55.0 | < | 5.6 |
| 607 | Wednesday, April 13, 2016 | S1041316 | S1 | 6:33 | 15:15 | 522 | 1,793 | < | 56.0 | < | 5.7 |
| 608 | Thursday, April 14, 2016 | S1041416 | S1 | 6:39 | 15:12 | 513 | 1,770 | < | 56.0 | < | 5.8 |
| 609 | Friday, April 15, 2016 | S4041516 | S4 | 6:40 | 15:19 | 519 | 1,788 | < | 56.0 | < | 5.7 |
| 610 | Monday, April 18, 2016 | S4041816 | S4 | 6:30 | 15:21 | 531 | 1,827 | < | 55.0 | < | 5.6 |
| 611 | Tuesday, April 19, 2016 | S4041916 | S4 | 6:22 | 15:26 | 544 | 1,880 | < | 53.0 | < | 5.4 |
| 612 | Wednesday, April 20, 2016 | S1042016 | S1 | 6:25 | 15:17 | 532 | 1,838 | < | 54.0 | < | 5.5 |
| 613 | Thursday, April 21, 2016 | S1042116 | S1 | 7:15 | 15:40 | 505 | 1,735 | < | 58.0 | < | 5.9 |
| 614 | Friday, April 22, 2016 | S4042216 | S4 | 6:43 | 15:27 | 524 | 1,805 | < | 55.0 | < | 5.7 |
| 615 | Monday, April 25, 2016 | S4042516 | S4 | 6:45 | 15:42 | 537 | 1,861 | < | 54.0 | < | 5.5 |
| 616 | Tuesday, April 26, 2016 | S4042616 | S4 | 6:28 | 15:12 | 524 | 1,797 | | 61.0 | < | 5.7 |
| 617 | Wednesday, April 27, 2016 | S1042716 | S1 | 6:40 | 15:19 | 519 | 1,780 | < | 56.0 | < | 5.7 |
| 618 | Thursday, April 28, 2016 | S1042816 | S1 | 6:40 | 15:23 | 523 | 1,817 | < | 55.0 | < | 5.6 |
| 619 | Friday, April 29, 2016 | S4042916 | S4 | 6:45 | 15:32 | 527 | 1,816 | < | 55.0 | < | 5.6 |
| 620 | Monday, May 02, 2016 | S1050216 | S1 | 6:40 | 15:43 | 543 | 1,871 | < | 53.0 | < | 5.5 |
| 621 | Tuesday, May 03, 2016 | S4050316 | S4 | 7:27 | 15:23 | 476 | 1,649 | < | 61.0 | < | 6.2 |
| 622 | Wednesday, May 04, 2016 | S1050416 | S1 | 7:32 | 15:14 | 462 | 1,587 | < | 63.0 | < | 6.4 |
| 623 | Thursday, May 05, 2016 | S1050516 | S1 | 6:35 | 15:37 | 542 | 1,867 | < | 54.0 | < | 5.5 |
| 624 | Friday, May 06, 2016 | S4050616 | S4 | 6:32 | 15:25 | 533 | 1,834 | < | 55.0 | < | 5.6 |
| 625 | Monday, May 09, 2016 | S1050916 | S1 | 6:33 | 15:36 | 543 | 1,873 | < | 53.0 | < | 5.5 |
| 626 | Tuesday, May 10, 2016 | S1051016 | S1 | 6:38 | 15:25 | 527 | 1,800 | < | 56.0 | < | 5.7 |
| 627 | Wednesday, May 11, 2016 | S1051116 | S1 | 6:36 | 15:37 | 541 | 1,866 | < | 54.0 | < | 5.5 |
| 628 | Thursday, May 12, 2016 | S4051216 | S4 | 6:34 | 15:46 | 552 | 1,891 | | 66.0 | < | 5.4 |
| 629 | Friday, May 13, 2016 | S4051316 | S4 | 6:32 | 15:26 | 534 | 1,837 | < | 54.0 | < | 5.6 |
| 630 | Monday, May 16, 2016 | S1051616 | S1 | 6:33 | 15:35 | 542 | 1,864 | | 56.0 | < | 5.5 |
| 631 | Tuesday, May 17, 2016 | S1051716 | S1 | 6:35 | 15:19 | 524 | 1,789 | < | 56.0 | < | 5.7 |
| 632 | Wednesday, May 18, 2016 | S1051816 | S1 | 6:28 | 15:12 | 524 | 1,803 | < | 55.0 | < | 5.7 |
| 633 | Thursday, May 19, 2016 | S1051916 | S1 | 6:35 | 15:35 | 540 | 1,858 | < | 54.0 | < | 5.5 |
| 634 | Friday, May 20, 2016 | S1052016 | S1 | 6:33 | 15:24 | 531 | 1,832 | < | 55.0 | < | 5.6 |
| 635 | Monday, May 23, 2016 | S1052316 | S1 | 6:25 | 15:39 | 554 | 1,895 | < | 53.0 | < | 5.4 |
| 636 | Tuesday, May 24, 2016 | S1052416 | S1 | 6:43 | 15:17 | 514 | 1,773 | < | 56.0 | < | 5.8 |
| 637 | Wednesday, May 25, 2016 | S1052516 | S1 | 7:00 | 15:27 | 507 | 1,744 | | 60.0 | < | 5.9 |
| 638 | Thursday, May 26, 2016 | S1052616 | S1 | 6:45 | 15:22 | 517 | 1,773 | < | 56.0 | < | 5.8 |
| 639 | Friday, May 27, 2016 | S3052716 | S3 | 6:40 | 14:25 | 465 | 1,600 | < | 63.0 | < | 6.4 |
| 640 | Tuesday, May 31, 2016 | S1053116 | S1 | 5:28 | 14:23 | 535 | 1,838 | < | 54.0 | < | 5.6 |
| 641 | Wednesday, June 01, 2016 | S1060116 | S1 | 5:38 | 14:27 | 529 | 1,801 | < | 56.0 | < | 5.7 |
| 642 | Thursday, June 02, 2016 | S4060216 | S4 | 5:38 | 14:21 | 523 | 1,804 | < | 55.0 | < | 5.7 |
| 643 | Friday, June 03, 2016 | S1060316 | S1 | 5:39 | 14:20 | 521 | 1,790 | < | 56.0 | < | 5.7 |
| 644 | Monday, June 06, 2016 | S1060616 | S1 | 5:38 | 16:04 | 626 | 2,157 | < | 46.0 | < | 4.8 |
| 645 | Tuesday, June 07, 2016 | S1060716 | S1 | 5:27 | 16:14 | 647 | 2,226 | | 57.0 | < | 4.6 |
| 646 | Wednesday, June 08, 2016 | S1060816 | S1 | 7:22 | 13:02 | 340 | 1,156 | < | 87.0 | < | 8.9 |

# TABLE 1B
# PAMP Data
## Hexavalent Chromium Air Samples
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for Particulate ($ug/m^3$) | | Analytical Results for CrVI ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 647 | Thursday, June 09, 2016 | S1 060916 | S1 | 5:31 | 16:13 | 642 | 2,202 | | 65.0 | | 8.1 |
| 648 | Friday, June 10, 2016 | S1 061016 | S1 | 5:38 | 16:01 | 623 | 2,121 | | 98.0 | | 7.7 |
| 649 | Monday, June 13, 2016 | S1 061316 | S1 | 5:43 | 16:17 | 634 | 2,175 | | 51.0 | < | 4.7 |
| 650 | Tuesday, June 14, 2016 | S1 061416 | S1 | 5:38 | 16:08 | 630 | 2,170 | < | 46.0 | < | 4.7 |
| 651 | Wednesday, June 15, 2016 | S1 061516 | S1 | 6:17 | 15:53 | 576 | 1,979 | < | 51.0 | < | 5.2 |
| 652 | Thursday, June 16, 2016 | S1 061616 | S1 | 5:46 | 16:18 | 632 | 2,161 | < | 46.0 | < | 4.7 |
| 653 | Friday, June 17, 2016 | S3 061716 | S3 | 5:39 | 16:24 | 645 | 2,216 | < | 45.0 | < | 4.6 |
| 654 | Monday, June 20, 2016 | S1 062016 | S1 | 5:23 | 16:17 | 654 | 2,243 | | 77.0 | < | 4.6 |
| 655 | Tuesday, June 21, 2016 | S1 062116 | S1 | 5:37 | 16:02 | 625 | 2,134 | < | 47.0 | < | 4.8 |
| 656 | Wednesday, June 22, 2016 | S1 062216 | S1 | 5:47 | 16:15 | 628 | 2,151 | | 110.0 | < | 4.8 |
| 657 | Thursday, June 23, 2016 | S1 062316 | S1 | 5:45 | 16:15 | 630 | 2,205 | | 53.0 | < | 4.7 |
| 658 | Friday, June 24, 2016 | S2 062416 | S2 | 5:33 | 16:25 | 652 | 2,262 | < | 44.0 | < | 4.5 |
| 659 | Monday, June 27, 2016 | S1 062716 | S1 | 6:25 | 19:10 | 765 | 2,655 | < | 38.0 | < | 3.9 |
| 660 | Tuesday, June 28, 2016 | S1 062816 | S1 | 5:40 | 16:10 | 630 | 2,183 | < | 46.0 | < | 4.7 |
| 661 | Wednesday, June 29, 2016 | S1 062916 | S1 | 5:48 | 15:42 | 594 | 2,055 | < | 49.0 | < | 5.0 |
| 662 | Thursday, June 30, 2016 | S1 063016 | S1 | 5:42 | 16:20 | 638 | 2,211 | < | 45.0 | < | 4.7 |
| 663 | Friday, July 01, 2016 | S1 070116 | S1 | 5:50 | 14:10 | 500 | 1,750 | < | 57.0 | < | 5.9 |

| Notes: | Action Levels | |
|---|---|---|
| Detectable Results Below Action Level | Hexavalent Chromium | 221 ng/m³ |
| ng/m³: nanograms per cubic meter | ***Validated by 3rd Party** | |
| ug/m³: microgram per cubic meter | | |

**TABLE 1B**
**PAMP Data**
**Metals Air Samples**
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for As (ng/m$^3$) | | Analytical Results for Pb (ng/m$^3$) | | Analytical Results for V (ng/m$^3$) | | Analytical Results for Zn (ng/m$^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Thursday, October 24, 2013 | S1MET102413 | S1 | | | 0 | 1,003 | < | 50 | < | 50 | < | 53 | < | 250 |
| 2 | Wednesday, November 06, 2013 | S1MET110613 | S1 | 7:06 | 15:48 | 522 | 1,493 | < | 33 | < | 100 | < | 35 | < | 330 |
| 3 | Thursday, November 14, 2013 | S1MET111413 | S1 | 6:45 | 15:16 | 511 | 1,479 | < | 34 | < | 35 | < | 35 | < | 340 |
| 4 | Tuesday, November 26, 2013 | S1MET112613 | S1 | 6:58 | 15:14 | 496 | 1,520 | < | 33 | < | 33 | < | 34 | < | 330 |
| 5 | Wednesday, December 04, 2013 | S3MET120413 | S1 | 6:30 | 15:00 | 510 | 1,493 | < | 34 | | 36 | < | 35 | | 430 |
| 6 | Thursday, December 12, 2013 | S2MET121213 | S2 | 6:45 | 15:03 | 498 | 1,571 | < | 32 | < | 32 | < | 33 | < | 310 |
| 7 | Wednesday, December 18, 2013 | S1MET121813 | S1 | 6:45 | 15:10 | 505 | 1,518 | < | 33 | < | 33 | < | 34 | < | 330 |
| 8 | Tuesday, December 24, 2013 | S2MET | S2 | 6:27 | 13:30 | 423 | 1,330 | < | 38 | < | 38 | < | 39 | < | 370 |
| 9 | Tuesday, December 31, 2013 | S1MET123113 | S1 | 7:00 | 14:10 | 430 | 1,357 | < | 37 | | 92 | < | 38 | < | 360 |
| 10 | Thursday, January 09, 2014 | S1MCE010914 | S1 | 6:50 | 15:02 | 492 | 1,486 | < | 34 | < | 34 | < | 35 | < | 330 |
| 11 | Monday, January 13, 2014 | S2MET011314 | S2 | 6:50 | 15:00 | 490 | 1,490 | < | 34 | < | 34 | < | 35 | < | 330 |
| 12 | Tuesday, January 21, 2014 | S3MET012114 | S3 | 6:53 | 14:00 | 427 | 1,296 | < | 39 | < | 39 | < | 40 | < | 370 |
| 13 | Tuesday, January 28, 2014 | S2MET012814 | S2 | 6:47 | 15:01 | 494 | 1,541 | < | 33 | < | 33 | < | 34 | < | 310 |
| 14 | Monday, February 03, 2014 | S2MET020314 | S2 | 6:50 | 11:50 | 300 | 941 | < | 53 | < | 56 | < | 55 | < | 260 |
| 15 | Tuesday, February 11, 2014 | S2M021114 | S2 | 6:40 | 15:06 | 506 | 1,609 | < | 31 | < | 32 | < | 32 | < | 300 |
| 16 | Wednesday, February 19, 2014 | **S2MET021914*** | S2 | 6:50 | 15:10 | 500 | 1,565 | < | 32 | < | 33 | < | 33 | < | 310 |
| 17 | Monday, February 24, 2014 | S2MET022414 | S2 | 6:48 | 15:00 | 492 | 1,555 | < | 32 | < | 33 | < | 33 | < | 310 |
| 18 | Monday, March 03, 2014 | S2MET030314 | S2 | 6:50 | 15:00 | 490 | 1,597 | < | 31 | < | 32 | < | 32 | < | 300 |
| 19 | Tuesday, March 11, 2014 | S1031114 | S1 | 6:55 | 15:39 | 524 | 1,664 | | VOID | | VOID | | VOID | | VOID |
| 20 | Monday, March 17, 2014 | S2MET031714 | S2 | 6:48 | 15:17 | 509 | 1,619 | < | 31 | | 36 | < | 32 | < | 300 |
| 21 | Monday, March 24, 2014 | S2MET032414 | S2 | 6:50 | 16:12 | 562 | 1,793 | < | 28 | < | 29 | < | 29 | < | 270 |
| 22 | Tuesday, April 01, 2014 | 2983AA | S2 | 6:42 | 15:00 | 498 | 1,591 | < | 31 | < | 32 | < | 32 | < | 300 |
| 23 | Tuesday, April 08, 2014 | S1MET040814 | S1 | 6:50 | 15:33 | 523 | 1,695 | < | 29 | < | 32 | < | 31 | < | 290 |
| 24 | Thursday, April 17, 2014 | S4MET041714 | S4 | 6:55 | 15:59 | 544 | 1,741 | < | 29 | < | 29 | < | 29 | < | 280 |
| 25 | Tuesday, April 22, 2014 | S2MET042214 | S2 | 6:46 | 17:30 | 644 | 2,048 | < | 24 | < | 25 | < | 25 | < | 240 |
| 26 | Monday, April 28, 2014 | S2MET042814 | S2 | 6:29 | 15:30 | 541 | 1,742 | < | 29 | < | 30 | < | 29 | < | 280 |
| 27 | Tuesday, May 06, 2014 | **S2MET050614*** | S2 | 6:39 | 17:20 | 641 | 2,077 | < | 24 | < | 25 | < | 25 | < | 230 |
| 28 | Monday, May 12, 2014 | S1MET051214 | S1 | 6:42 | 16:00 | 558 | 1,797 | < | 28 | < | 29 | < | 28 | < | 270 |
| 29 | Tuesday, May 20, 2014 | S2MET052014 | S2 | 6:33 | 15:26 | 533 | 1,754 | < | 28 | < | 29 | < | 29 | < | 280 |
| 30 | Tuesday, May 27, 2014 | S1MET052714 | S1 | 6:18 | 15:20 | 542 | 1,737 | < | 29 | < | 30 | < | 29 | < | 280 |
| 31 | Monday, June 02, 2014 | S1MET060214 | S1 | 6:38 | 15:30 | 532 | 1,697 | < | 29 | < | 30 | < | 30 | < | 300 |
| 32 | Monday, June 09, 2014 | S4MET060914 | S4 | 6:38 | 15:29 | 531 | 1,691 | < | 29 | < | 31 | < | 30 | < | 290 |
| 33 | Monday, June 16, 2014 | **S2MET061614*** | S2 | 6:28 | 15:08 | 520 | 1,661 | < | 30 | < | 31 | < | 30 | < | 290 |
| 34 | Wednesday, June 25, 2014 | S2MET062514 | S2 | 6:30 | 14:40 | 490 | 1,566 | < | 32 | < | 33 | < | 32 | < | 310 |
| 35 | Wednesday, July 02, 2014 | S2MET070214 | S2 | 5:51 | 15:23 | 572 | 1,842 | < | 27 | < | 28 | < | 27 | < | 270 |
| 36 | Thursday, July 10, 2014 | S3MET071014 | S3 | 6:35 | 15:20 | 525 | 1,698 | < | 30 | < | 32 | < | 30 | < | 290 |
| 37 | Monday, July 14, 2014 | S2MET071114 | S2 | 6:15 | 14:35 | 500 | 1,603 | < | 31 | < | 32 | < | 31 | < | 310 |
| 38 | Tuesday, July 22, 2014 | S1MET072214 | S1 | 5:58 | 14:20 | 502 | 1,619 | < | 31 | < | 32 | < | 32 | < | 300 |
| 39 | Monday, July 28, 2014 | S1MET072814 | S1 | 5:46 | 14:45 | 539 | 1,738 | < | 29 | < | 30 | < | 29 | < | 280 |

**TABLE 1B**
**PAMP Data**
**Metals Air Samples**
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for As ($ng/m^3$) | | Analytical Results for Pb ($ng/m^3$) | | Analytical Results for V ($ng/m^3$) | | Analytical Results for Zn ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 40 | Wednesday, August 06, 2014 | S2MET080614 | S2 | 5:47 | 14:40 | 533 | 1,735 | < | 29 | < | 30 | < | 29 | < | 280 |
| 41 | Monday, August 11, 2014 | S3MET081114 | S3 | 5:58 | 14:30 | 512 | 1,644 | < | 30 | < | 32 | < | 31 | < | 300 |
| 42 | Monday, August 18, 2014 | S2MET081814 | S2 | 5:58 | 14:30 | 512 | 1,654 | < | 30 | < | 32 | < | 30 | < | 290 |
| 43 | Monday, August 25, 2014 | **S2MET082514*** | S2 | 6:03 | 15:30 | 567 | 1,809 | < | 28 | < | 29 | < | 28 | < | 270 |
| 44 | Tuesday, September 02, 2014 | S1MET090214 | S1 | 6:05 | 14:30 | 505 | 1,628 | < | 31 | < | 32 | < | 31 | < | 300 |
| 45 | Monday, September 08, 2014 | S3MET090814 | S3 | 6:40 | 15:00 | 500 | 1,605 | < | 31 | < | 33 | < | 31 | < | 310 |
| 46 | Monday, September 15, 2014 | S2MET091514 | S2 | 6:23 | 15:00 | 517 | 1,634 | < | 31 | < | 32 | < | 31 | < | 300 |
| 47 | Tuesday, September 23, 2014 | S2MET092314 | S2 | 6:26 | 16:58 | 632 | 2,092 | < | 24 | < | 25 | < | 24 | < | 240 |
| 48 | Thursday, October 02, 2014 | S4MET100214 | S4 | 6:28 | 17:05 | 637 | 2,105 | < | 24 | < | 25 | < | 24 | < | 230 |
| 49 | Wednesday, October 08, 2014 | S1MET100814 | S1 | 6:43 | 17:15 | 632 | 2,089 | < | 24 | < | 25 | < | 24 | < | 240 |
| 50 | Wednesday, October 15, 2014 | S4MET101514 | S4 | 6:20 | 17:17 | 657 | 2,198 | < | 22 | < | 24 | < | 23 | < | 230 |
| 51 | Friday, October 24, 2014 | **S2MET102414*** | S2 | 6:37 | 17:15 | 638 | 2,099 | < | 24 | < | 25 | < | 24 | < | 240 |
| 52 | Tuesday, October 28, 2014 | S2MET102814 | S2 | 6:32 | 15:26 | 534 | 1,765 | < | 28 | < | 30 | < | 29 | < | 280 |
| 53 | Wednesday, November 05, 2014 | S1MET110514 | S1 | 6:41 | 15:16 | 515 | 1,736 | < | 28 | < | 30 | < | 29 | < | 280 |
| 54 | Friday, November 14, 2014 | S4MET111414 | S4 | 6:22 | 15:19 | 537 | 1,845 | < | 27 | < | 28 | < | 27 | < | 270 |
| 55 | Wednesday, November 19, 2014 | S1MET111914 | S1 | 6:34 | 15:22 | 528 | 1,811 | < | 27 | < | 29 | < | 28 | < | 270 |
| 56 | Tuesday, November 25, 2014 | S1MET112514 | S1 | 6:29 | 15:31 | 542 | 1,816 | < | 27 | < | 29 | < | 28 | < | 270 |
| 57 | Thursday, December 04, 2014 | S2MET120414 | S2 | 6:57 | 15:17 | 500 | 1,628 | < | 32 | < | 31 | < | 31 | < | 300 |
| 58 | Tuesday, December 09, 2014 | S2MET120914 | S2 | 6:42 | 15:12 | 510 | 1,637 | < | 30 | < | 32 | < | 31 | < | 300 |
| 59 | Friday, December 19, 2014 | **S2MET121914*** | S2 | 6:42 | 15:20 | 518 | 1,707 | < | 29 | < | 30 | < | 29 | < | 290 |
| 60 | Monday, December 22, 2014 | S3MET122214 | S3 | 6:40 | 15:23 | 523 | 1,723 | < | 8.6 | < | 90 | < | 87 | < | 860 |
| 61 | Monday, December 29, 2014 | S2MET122914 | S2 | 6:34 | 15:35 | 541 | 1,769 | < | 28 | < | 29 | < | 28 | < | 280 |
| 62 | Monday, January 05, 2015 | S2MET010515 | S2 | 6:29 | 15:18 | 529 | 1,772 | < | 28 | < | 29 | < | 28 | < | 280 |
| 63 | Monday, January 12, 2015 | S2MET011215 | S2 | 6:45 | 15:27 | 522 | 1,762 | < | 28 | < | 29 | < | 28 | < | 280 |
| 64 | Monday, January 19, 2015 | S2MET011915 | S2 | 6:42 | 15:25 | 523 | 1,752 | < | 28 | < | 30 | < | 29 | < | 280 |
| 65 | Wednesday, January 28, 2015 | S2MET012815 | S2 | 7:30 | 15:23 | 473 | 1,596 | < | 31 | < | 32 | < | 32 | < | 310 |
| 66 | Wednesday, February 04, 2015 | S2MET020415 | S2 | 7:05 | 15:20 | 495 | 1,671 | < | 30 | < | 30 | < | 30 | < | 300 |
| 67 | Wednesday, February 11, 2015 | S2MET021115 | S2 | 7:05 | 15:28 | 503 | 1,685 | < | 29 | < | 30 | < | 30 | < | 290 |
| 68 | Thursday, February 19, 2015 | **S2MET021915*** | S2 | 7:05 | 15:41 | 516 | 1,741 | < | 28 | < | 29 | < | 29 | < | 280 |
| 69 | Thursday, February 26, 2015 | S2MET022615 | S2 | 7:05 | 15:22 | 497 | 1,739 | < | 28 | < | 29 | < | 29 | < | 280 |
| 70 | Wednesday, March 04, 2015 | S3MET030415 | S3 | 6:33 | 15:20 | 527 | 1,702 | < | 29 | < | 29 | < | 29 | < | 280 |
| 71 | Thursday, March 12, 2015 | S1MET031215 | S1 | 6:25 | 15:21 | 536 | 1,798 | < | 27 | < | 28 | < | 28 | < | 270 |
| 72 | Wednesday, March 18, 2015 | S1MET031815 | S1 | 6:23 | 15:25 | 542 | 1,965 | < | 25 | < | 26 | < | 26 | < | 250 |
| 73 | Thursday, March 26, 2015 | S2MET032615 | S2 | 6:26 | 15:12 | 526 | 1,709 | < | 29 | | 33 | < | 30 | < | 290 |
| 74 | Tuesday, March 31, 2015 | S1MET033115 | S1 | 6:25 | 15:09 | 524 | 1,871 | < | 26 | < | 27 | < | 27 | < | 260 |
| 75 | Thursday, April 09, 2015 | **S3MET040915*** | S3 | 6:20 | 15:12 | 532 | 1,833 | < | 27 | < | 28 | < | 28 | < | 270 |
| 76 | Wednesday, April 15, 2015 | S2MET041515 | S2 | 7:10 | 15:20 | 490 | 1,661 | < | 30 | < | 31 | < | 30 | < | 300 |
| 77 | Wednesday, April 22, 2015 | S2MET042215 | S2 | 7:05 | 15:15 | 490 | 1,659 | < | 30 | < | 31 | < | 30 | < | 300 |
| 78 | Thursday, April 30, 2015 | S3MET043015 | S3 | 7:00 | 15:20 | 500 | 1,650 | < | 30 | < | 31 | < | 31 | < | 300 |

**TABLE 1B**
**PAMP Data**
**Metals Air Samples**
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for As (ng/m$^3$) | Analytical Results for Pb (ng/m$^3$) | Analytical Results for V (ng/m$^3$) | Analytical Results for Zn (ng/m$^3$) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 79 | Thursday, May 07, 2015 | S3MET050715 | S3 | 7:10 | 15:53 | 523 | 1,752 | < 28 | < 29 | < 29 | < 280 |
| 80 | Thursday, May 14, 2015 | S2MET051415 | S2 | 6:55 | 15:20 | 505 | 1,682 | < 30 | < 30 | < 30 | < 290 |
| 81 | Wednesday, May 20, 2015 | S1MET052015 | S1 | 7:00 | 15:15 | 495 | 1,641 | < 30 | < 30 | < 31 | < 300 |
| 82 | Thursday, May 28, 2015 | S3MET052815 | S3 | 6:10 | 14:51 | 521 | 1,748 | < 28 | < 29 | < 29 | < 280 |
| 83 | Thursday, June 04, 2015 | S3MET060415 | S3 | 6:00 | 14:23 | 503 | 1,730 | < 29 | < 29 | < 29 | < 280 |
| 84 | Thursday, June 11, 2015 | **S2MET061115*** | S2 | 6:00 | 15:30 | 570 | 1,924 | < 26 | < 26 | < 26 | < 250 |
| 85 | Wednesday, June 17, 2015 | S2MET061715 | S2 | 6:00 | 15:45 | 585 | 1,960 | < 26 | < 26 | < 26 | < 260 |
| 86 | Thursday, June 25, 2015 | S2MET062515 | S2 | 5:50 | 15:38 | 588 | 1,976 | < 25 | < 25 | < 25 | < 250 |
| 87 | Thursday, July 02, 2015 | S2MET070215 | S2 | 6:00 | 14:20 | 500 | 1,712 | < 29 | < 29 | < 29 | < 290 |
| 88 | Wednesday, July 08, 2015 | S1MET070815 | S1 | 5:46 | 14:23 | 517 | 1,789 | < 28 | < 28 | < 28 | < 280 |
| 89 | Friday, July 17, 2015 | S4MET071715 | S4 | 5:50 | 16:00 | 610 | 2,062 | < 24 | < 24 | < 25 | < 240 |
| 90 | Thursday, July 23, 2015 | S2MET072315 | S2 | 5:55 | 16:35 | 640 | 2,234 | < 22 | < 22 | < 23 | < 220 |
| 91 | Wednesday, July 29, 2015 | S2MET072915 | S2 | 5:50 | 16:05 | 615 | 2,149 | < 23 | < 23 | < 24 | < 230 |
| 92 | Wednesday, August 05, 2015 | S2MET080515 | S2 | 6:00 | 17:05 | 665 | 2,284 | < 22 | < 22 | < 22 | < 220 |
| 93 | Wednesday, August 12, 2015 | S1MET081215 | S1 | 5:55 | 16:15 | 620 | 2,123 | < 24 | < 24 | < 24 | < 240 |
| 94 | Wednesday, August 19, 2015 | S3MET081915 | S3 | 5:55 | 14:45 | 530 | 1,778 | < 28 | < 28 | < 29 | < 280 |
| 95 | Wednesday, August 26, 2015 | **S1MET082615*** | S1 | 6:00 | 14:30 | 510 | 1,721 | < 29 | < 29 | < 30 | < 290 |
| 96 | Wednesday, September 02, 2015 | S2MET090215 | S2 | 6:00 | 14:25 | 505 | 1,707 | < 29 | < 29 | < 30 | < 290 |
| 97 | Friday, September 11, 2015 | S2MET091115 | S2 | 6:30 | 15:00 | 510 | 1,739 | < 29 | < 29 | < 29 | < 290 |
| 98 | Wednesday, September 16, 2015 | S2MET091615 | S2 | 6:30 | 16:00 | 570 | 1,929 | < 26 | < 26 | < 27 | < 260 |
| 99 | Thursday, September 24, 2015 | S3MET092415 | S3 | 6:30 | 17:00 | 630 | 2,123 | < 24 | < 24 | < 24 | < 240 |
| 100 | Monday, September 28, 2015 | S3MET092815 | S3 | 6:14 | 17:00 | 646 | 2,196 | < 23 | < 23 | < 23 | < 230 |
| 101 | Tuesday, October 06, 2015 | S1MET100615 | S1 | 6:53 | 17:00 | 607 | 2,091 | < 24 | < 24 | < 24 | < 240 |
| 102 | Friday, October 16, 2015 | S1MET101615 | S1 | 6:48 | 15:23 | 515 | 1,715 | < 29 | < 29 | < 30 | < 290 |
| 103 | Wednesday, October 21, 2015 | **S1MET102115*** | S1 | 6:55 | 15:26 | 511 | 1,740 | < 29 | < 29 | < 29 | < 290 |
| 104 | Wednesday, October 28, 2015 | S3MET102815 | S3 | 6:50 | 15:15 | 505 | 1,704 | < 29 | < 29 | < 30 | < 290 |
| 105 | Thursday, November 05, 2015 | S3MET110515 | S3 | 7:00 | 15:35 | 515 | 1,743 | < 29 | < 29 | < 29 | < 290 |
| 106 | Thursday, November 12, 2015 | S2MET111215 | S2 | 7:05 | 15:05 | 480 | 1,632 | < 31 | < 31 | < 31 | < 310 |
| 107 | Thursday, November 19, 2015 | S4MET111915 | S4 | 7:00 | 15:10 | 490 | 1,668 | < 30 | < 30 | < 31 | < 300 |
| 108 | Wednesday, November 25, 2015 | S1MET112515 | S1 | 6:55 | 14:00 | 425 | 1,441 | < 35 | < 35 | < 36 | < 350 |
| 109 | Friday, December 04, 2015 | **S1MET120415*** | S1 | 6:55 | 15:20 | 505 | 1,699 | < 30 | < 30 | < 30 | < 290 |
| 110 | Wednesday, December 09, 2015 | S1MET120915 | S1 | 6:55 | 15:20 | 505 | 1,707 | < 30 | < 29 | < 30 | < 290 |
| 111 | Thursday, December 17, 2015 | S1MET121715 | S1 | 6:50 | 15:35 | 525 | 1,775 | < 29 | < 28 | < 29 | < 280 |
| 112 | Wednesday, December 23, 2015 | S1MET122315 | S1 | 6:50 | 14:05 | 435 | 1,475 | < 34 | 36 | < 35 | < 340 |
| 113 | Thursday, January 07, 2016 | S1MET010716 | S1 | 6:55 | 15:20 | 505 | 1,709 | < 30 | < 29 | < 30 | < 290 |
| 114 | Thursday, January 14, 2016 | **S1MET011416*** | S1 | 7:23 | 15:28 | 485 | 1,649 | < 31 | < 30 | < 31 | < 300 |
| 115 | Friday, January 22, 2016 | S2MET012116 | S2 | 6:29 | 15:20 | 531 | 1,795 | < 28 | < 28 | < 29 | < 280 |
| 116 | Thursday, January 28, 2016 | S2MET012816 | S2 | 7:25 | 15:22 | 477 | 1,624 | < 31 | < 31 | < 32 | < 310 |
| 117 | Thursday, February 04, 2016 | S1MET020416 | S1 | 7:34 | 15:45 | 491 | 1,679 | < 30 | < 30 | < 31 | < 300 |

**TABLE 1B**
**PAMP Data**
**Metals Air Samples**
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Entry | Date | Sample # | Location | Start | Stop | Minutes | Volume | Analytical Results for As ($ng/m^3$) | | Analytical Results for Pb ($ng/m^3$) | | Analytical Results for V ($ng/m^3$) | | Analytical Results for Zn ($ng/m^3$) | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 118 | Thursday, February 11, 2016 | **S1MET021116*** | S1 | 7:21 | 15:21 | 480 | 1,658 | < | 30 | < | 30 | < | 31 | < | 300 |
| 119 | Thursday, February 18, 2016 | S1MET021816 | S1 | 7:22 | 15:30 | 488 | 1,662 | < | 30 | < | 30 | < | 31 | < | 300 |
| 120 | Friday, February 26, 2016 | S1MET022616 | S1 | 7:19 | 15:12 | 473 | 1,601 | < | 32 | < | 31 | < | 32 | < | 310 |
| 121 | Thursday, March 03, 2016 | S1MET030316 | S1 | 6:51 | 15:17 | 506 | 1,743 | < | 29< | < | 29 | < | 29 | < | 290 |
| 122 | Thursday, March 10, 2016 | **S1MET031016*** | S1 | 6:53 | 15:38 | 525 | 1,806 | < | 28 | < | 28 | < | 28 | < | 280 |
| 123 | Wednesday, March 16, 2016 | S4MET031616 | S4 | 6:56 | 15:30 | 514 | 1,781 | < | 28 | < | 28 | < | 29 | < | 280 |
| 124 | Thursday, March 24, 2016 | S1MET032416 | S1 | 6:43 | 15:34 | 531 | 1,827 | < | 27 | < | 27 | < | 28 | < | 270 |
| 125 | Thursday, March 31, 2016 | S1MET033116 | S1 | 6:45 | 15:39 | 534 | 1,840 | < | 27 | < | 27 | < | 28 | < | 270 |
| 126 | Thursday, April 07, 2016 | S4MET040716 | S4 | 6:50 | 15:37 | 527 | 1,818 | < | 28 | < | 28 | < | 28 | < | 280 |
| 127 | Thursday, April 14, 2016 | S1MET041416 | S1 | 6:39 | 15:12 | 513 | 1,772 | < | 28 | < | 28 | < | 29 | < | 280 |
| 128 | Thursday, April 21, 2016 | S1MET042116 | S1 | 7:15 | 15:40 | 505 | 1,745 | < | 29 | < | 29 | < | 29 | < | 290 |
| 129 | Thursday, April 28, 2016 | S1MET042816 | S1 | 6:40 | 15:23 | 523 | 1,802 | < | 28 | < | 28 | < | 28 | < | 280 |
| 130 | Thursday, May 05, 2016 | S1MET050516 | S1 | 6:35 | 15:37 | 542 | 1,864 | < | 27 | < | 27 | < | 27 | < | 270 |
| 131 | Thursday, May 12, 2016 | S4MET051216 | S4 | 6:34 | 15:46 | 552 | 1,888 | < | 26 | < | 26 | < | 27 | < | 260 |
| 132 | Thursday, May 19, 2016 | S1MET051916 | S1 | 6:35 | 15:35 | 540 | 1,855 | < | 27 | < | 27 | < | 27 | < | 270 |
| 133 | Thursday, May 26, 2016 | S1MET052616 | S1 | 6:51 | 15:28 | 517 | 1,781 | < | 28 | < | 28 | < | 28 | < | 280 |
| 134 | Thursday, June 02, 2016 | S4MET060216 | S4 | 5:38 | 14:21 | 523 | 1,802 | < | 28 | < | 28 | < | 28 | < | 280 |
| 135 | Thursday, June 09, 2016 | S1MET060916 | S1 | 5:31 | 16:13 | 642 | 2,202 | < | 23 | < | 23 | < | 23 | < | 230 |
| 136 | Friday, June 17, 2016 | S3MET061716 | S3 | 5:39 | 16:24 | 645 | 2,216 | < | 23 | < | 23 | < | 23 | < | 230 |
| 137 | Thursday, June 23, 2016 | S1MET062316 | S1 | 5:45 | 16:15 | 630 | 2,205 | < | 23 | < | 23 | < | 23 | < | 230 |

| **Notes:** | **Action Levels** | |
|---|---|---|
| Detectable Results Below Action Level | Arsenic (As) | 200 $ng/m^3$ |
| ***Validated by 3rd Party** | Lead (Pb) | 300 $ng/m^3$ |
| $ng/m^3$: nanograms per cubic meter | Vanadium (V) | 300 $ng/m^3$ |
| | Zinc (Zn) | Not Applicable |

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-7-20-a | | | | | | | | 124-12-20-a | | | | | | | | 124-12-20-b | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-7-20-a1 | | 124-7-20-a2 | | 124-7-20-a3 | | 124-7-20-a4 | | 124-12-20-a1 | | 124-12-20-a2 | | 124-12-20-a3 | | 124-12-20-a4 | | 124-12-20-b1 | | 124-12-20-b2 | | 124-12-20-b3 | | 124-12-20-b4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB51746-1/1R | | JB51746-2 | | JB51746-3/3R | | JB51746-4/4R | | JB54242-1/1R | | JB54242-2 | | JB54242-3 | | JB54242-4 | | JB54242-5 | | JB54242-6 | | JB54242-7/7R | | JB54242-8 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 10/31/2013 | | 10/31/2013 | | 10/31/2013 | | 10/31/2013 | | 11/26/2013 | | 11/26/2013 | | 11/26/2013 | | 11/26/2013 | | 11/26/2013 | | 11/26/2013 | | 11/26/2013 | | 11/26/2013 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 5.8 | J | 7.8 | J | 4.6 | J | 4.7 | J | **26.1** | | 2.9 | J | 12.5 | J | **23.2** | **J** | 4.3 | J | 2.5 | J | 5.1 | | 5.8 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-22-20-a | | | | | | | | 124-25-20-a | | | | | | | | 124-29-20-a | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | **124-22-20-a1** | | **124-22-20-a2** | | **124-22-20-a3** | | **124-22-20-a4** | | **124-25-20-a1** | | **124-25-20-a2** | | **124-25-20-a3** | | **124-25-20-a4** | | **124-29-20-a1** | | **124-29-20-a2** | | **124-29-20-a3** | | **124-29-20-a4** | |
| LAB SAMPLE ID | **NJ 2012** | **NJ 2013** | JB55610-1/1R | | JB55610-2/2R | | JB55610-3 | | JB55610-4 | | JB56360-1 | | JB56360-2 | | JB56360-3/3R | | JB56360-4/4R | | JB57677-1 | | JB57677-2 | | JB57677-3/3R | | JB57677-4 | |
| DATE SAMPLED | **MOST STRINGENT SRS** | **IGW SOIL** | 12/13/2013 | | 12/13/2013 | | 12/13/2013 | | 12/13/2013 | | 12/23/2013 | | 12/23/2013 | | 12/23/2013 | | 12/23/2013 | | 01/13/2014 | | 01/13/2014 | | 01/13/2014 | | 01/13/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 5.5 | | 11.9 | | 1.3 | J | 2.3 | J | 1.6 | | 1.7 | | 10.8 | J | 17.4 | J | 3.1 | | 0.84 | | 3.4 | J | 1.9 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-46-20-a | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-46-20-a1 | | 124-46-20-a2 | | 124-46-20-a3 | | 124-46-20-a4 | | 124-46-20-b1 | | 124-46-20-b2 | | 124-46-20-b3 | | 124-46-20-b4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB61677-1 | | JB61677-2 | | JB61677-3 | | JB61677-4 | | JB61677-5 | | JB61677-6 | | JB61677-7 | | JB61677-8 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 3.2 | | 2.2 | | 3.9 | | 2 | | 2.9 | | 3.8 | | 2.2 | | 2.6 | |

| | | | 124-57-20-a | | | | | |
|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-57-20-a1 | | 124-57-20-a2 | | 124-57-20-a3 | | 124-57-20-a4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB63864-1 | | JB63864-2 | | JB63864-3 | | JB63864-4/4R | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 17 | J | 3.8 | J | 4.2 | J | 0.79 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016
Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-57-20-b | | | | | | | | 124-57-20-c | | | | | | | | 124-152-20-a | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-57-20-b1 | | 124-57-20-b2 | | 124-57-20-b3 | | 124-57-20-b4 | | 124-57-20-c1 | | 124-57-20-c2 | | 124-57-20-c3 | | 124-57-20-c4 | | 124-152-20-a1 | | 124-152-20-a2 | | 124-152-20-a3 | | 124-152-20-a4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB63864-5 | | JB63864-6 | | JB63864-7 | | JB63864-8/8R | | JB63864-9 | | JB63864-10 | | JB63864-11 | | JB63864-12 | | JB65406-1 | | JB65406-2 | | JB65406-3 | | JB65406-4/4R | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/04/2014 | | 04/23/2014 | | 04/23/2014 | | 04/23/2014 | | 04/23/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 4.1 | J | 14.2 | J | 15.7 | J | 1 | J | 10.3 | J | 11.6 | J | 11.8 | J | **41.4** | **J** | 0.73 | | 0.76 | | 0.42 | U | 2.4 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-145-20-a | | | | | | | | 124-142-20-a | | | | | | | | 124-138-20-a | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-145-20-a1 | | 124-145-20-a2 | | 124-145-20-a3 | | 124-145-20-a4 | | 124-142-20-a1 | | 124-142-20-a2 | | 124-142-20-a3 | | 124-142-20-a4 | | 124-138-20-a1 | | 124-138-20-a2 | | 124-138-20-a3 | | 124-138-20-a4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB66698-1 | | JB66698-2/2R | | JB66698-3 | | JB66698-4/4R | | JB67191-1 | | JB67191-2 | | JB67191-3 | | JB67191-4 | | JB67301-1 | | JB67301-2 | | JB67301-3 | | JB67301-4 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 05/09/2014 | | 05/09/2014 | | 05/09/2014 | | 05/09/2014 | | 05/15/2014 | | 05/15/2014 | | 05/15/2014 | | 05/15/2014 | | 05/19/2014 | | 05/19/2014 | | 05/19/2014 | | 05/19/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | **22.8** | J | 0.48 | J | 5.4 | J | 3.2 | J | 2.1 | | 8.7 | | 5.9 | | 4.3 | | 4 | | 10.2 | | 5.7 | | 3.9 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-138-20-b | | | | 124-134-20-a | | | | 124-134-20-b | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-138-20-b1 | 124-138-20-b2 | 124-138-20-b3 | 124-138-20-b4 | 124-134-20-a1 | 124-134-20-a2 | 124-134-20-a3 | 124-134-20-a4 | 124-134-20-b1 | 124-134-20-b2 | 124-134-20-b3 | 124-134-20-b4 |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB67301-5 | JB67301-6 | JB67301-7 | JB67301-8 | JB67567-1 | JB67567-2 | JB67567-3 | JB67567-4 | JB67567-5 | JB67567-6 | JB67567-7 | JB67567-8 |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 05/19/2014 | 05/19/2014 | 05/19/2014 | 05/19/2014 | 05/21/2014 | 05/21/2014 | 05/21/2014 | 05/21/2014 | 05/21/2014 | 05/21/2014 | 05/21/2014 | 05/21/2014 |
| **Analytes <20 ppm (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 1.2 | 4.9 | 2.7 | 5.4 | 7.5 | 7.8 | 4.2 | **30.5** | 10.7 | 2.5 | 4.9 | 7.3 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-128-20-a | | | | 124-126-20-a | | | | 124-126-20-b | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-128-20-a1 | 124-128-20-a2 | 124-128-20-a3 | 124-128-20-a4 | 124-126-20-a1 | 124-126-20-a2 | 124-126-20-a3 | 124-126-20-a4 | 124-126-20-b1 | 124-126-20-b2 | 124-126-20-b3 | 124-126-20-b4 |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB68316-1/1R | JB68316-2/2R | JB68316-3/3R | JB68316-4/4R | JB69272-1 | JB69272-2 | JB69272-3 | JB69272-4 | JB69272-5 | JB69272-6 | JB69272-7 | JB69272-8 |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 06/03/2014 | 06/03/2014 | 06/03/2014 | 06/03/2014 | 06/13/2014 | 06/13/2014 | 06/13/2014 | 06/13/2014 | 06/13/2014 | 06/13/2014 | 06/13/2014 | 06/13/2014 |
| **Analytes <20 ppm (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | NC | **32.4** | **38.4** | 17 | **45.1** | **41.1** | 13.9 | 15 | 2.9 | 12.9 | 8.6 | **59.4** | 8 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-124-20-a | | | | 124-124-20-b | | | | 124-119-20-a | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | **124-124-20-a1** | **124-124-20-a2** | **124-124-20-a3** | **124-124-20-a4** | **124-124-20-b1** | **124-124-20-b2** | **124-124-20-b3** | **124-124-20-b4** | **124-119-20-a1** | **124-119-20-a2** | **124-119-20-a3** | **124-119-20-a4** |
| LAB SAMPLE ID | **NJ 2012** | **NJ 2013** | JB70229-1 | JB70229-2 | JB70229-3 | JB70229-4 | JB70229-5/5R | JB70229-6 | JB70229-7 | JB70229-8 | JB70485-1 | JB70485-2/2R | JB70485-3/3R | JB70485-4/4R |
| DATE SAMPLED | **MOST STRINGENT SRS** | **IGW SOIL** | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/27/2014 | 06/27/2014 | 06/27/2014 | 06/27/2014 |
| **Analytes <20 ppm (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 11.2 | 14.6 | 12.2 | 8 | 19.4 | 4.8 | 2.1 | 10.5 | 9.6 | 7.8 | 6 | **28.8** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-118-20-a | | | | 124-112-20-a | | | | 124-112-20-b | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | **124-118-20-a1** | **124-118-20-a2** | **124-118-20-a3** | **124-118-20-a4** | **124-112-20-a1** | **124-112-20-a2** | **124-112-20-a3** | **124-112-20-a4** | **124-112-20-b1** | **124-112-20-b2** | **124-112-20-b3** | **124-112-20-b4** |
| LAB SAMPLE ID | **NJ 2012** | **NJ 2013** | JB71213-1 | JB71213-2 | JB71213-3 | JB71213-4 | JB72878-1 | JB72878-2 | JB72878-3 | JB72878-4 | JB72878-5 | JB72878-6 | JB72878-7 | JB72878-8 |
| DATE SAMPLED | **MOST STRINGENT SRS** | **IGW SOIL** | 07/09/2014 | 07/09/2014 | 07/09/2014 | 07/09/2014 | 07/30/2014 | 07/30/2014 | 07/30/2014 | 07/30/2014 | 07/30/2014 | 07/30/2014 | 07/30/2014 | 07/30/2014 |
| **Analytes <20 ppm (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | NC | **20.3** | 19.7 | **37.1** | **61.1** | 16.1 | 6.7 | 8.7 | 11 | 2.4 | 2.6 | 14.7 | 1.6 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-112-20-c | | | | | | 124-101-20-a | | | | | | 124-101-20-b | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-112-20-c1 | | 124-112-20-c2 | | 124-112-20-c3 | | 124-112-20-c4 | | 124-101-20-a1 | | 124-101-20-a2 | | 124-101-20-a3 | | 124-101-20-a4 | | 124-101-20-b1 | | 124-101-20-b2 | | 124-101-20-b3 | | 124-101-20-b4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB72878-9 | | JB72878-10 | | JB72878-11 | | JB72878-12 | | JB74771-1 | | JB74771-2 | | JB74771-3 | | JB74771-4 | | JB74771-5 | | JB74771-6 | | JB74771-7 | | JB74771-8 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 07/30/2014 | | 07/30/2014 | | 07/30/2014 | | 07/30/2014 | | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | **24** | J | 3.4 | | 6 | | 2.6 | | **22.4** | | 13.3 | | **23.8** | | **24.6** | | **22.5** | | 17.2 | | 11.5 | | **21.8** | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-101-20-c | | | | 124-88-20-a | | | | 124-88-20-b | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-101-20-c1 | 124-101-20-c2 | 124-101-20-c3 | 124-101-20-c4 | 124-88-20-a1 | 124-88-20-a2 | 124-88-20-a3 | 124-88-20-a4 | 124-88-20-b1 | 124-88-20-b2 | 124-88-20-b3 | 124-88-20-b4 |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB74771-9 | JB74771-10 | JB74771-11 | JB74771-12 | JB75541-1/1R | JB75541-2/2R | JB75541-3/3R | JB75541-4/4R | JB75541-5/5R | JB75541-6/6R | JB75541-7/7R | JB75541-8/8R |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 08/22/2014 | 08/22/2014 | 08/22/2014 | 08/22/2014 | 09/03/2014 | 09/03/2014 | 09/03/2014 | 09/03/2014 | 09/03/2014 | 09/03/2014 | 09/03/2014 | 09/03/2014 |
| **Analytes <20 ppm (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 6.8 | **25** | 13.6 | 4.2 | 7.1 J | 10.9 J | 15.4 J | 3.3 J | 9.6 J | **26.6 J** | 6.9 J | 4.4 J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-88-20-c | | | | | | | | 124-82-20-a | | | | | | | | 124-82-20-b | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-88-20-c1 | | 124-88-20-c2 | | 124-88-20-c3 | | 124-88-20-c4 | | 124-82-20-a1 | | 124-82-20-a2 | | 124-82-20-a3 | | 124-82-20-a4 | | 124-82-20-b1 | | 124-82-20-b2 | | 124-82-20-b3 | | 124-82-20-b4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB75541-9/9R | | JB75541-10/10R | | JB75541-11 | | JB75541-12/12R | | JB76844-1/1R | | JB76844-2/2R | | JB76844-3/3R | | JB76844-4/4R | | JB76844-5/5R | | JB76844-6/6R | | JB76844-7/7R | | JB76844-8/8R | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 09/03/2014 | | 09/03/2014 | | 09/03/2014 | | 09/03/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 18.3 | J | 2.6 | J | 9.4 | J | 16.2 | J | **23.9** | **J** | 16.8 | J | **35.3** | **J** | 12.9 | J | **34.6** | **J** | **142** | **J** | **25.4** | **J** | 12.8 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-82-20-c | | | | | | | | 124-78-20-a | | | | | | | | 124-78-20-b | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-82-20-c1 | | 124-82-20-c2 | | 124-82-20-c3 | | 124-82-20-c4 | | 124-78-20-a1 | | 124-78-20-a2 | | 124-78-20-a3 | | 124-78-20-a4 | | 124-78-20-b1 | | 124-78-20-b2 | | 124-78-20-b3 | | 124-78-20-b4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB76844-9/9R | | JB76844-10/10R | | JB76844-11/11R | | JB76844-12/12R | | JB77954-1/1R | | JB77954-2/2R | | JB77954-3/3R | | JB77954-4/4R | | JB77954-5 | | JB77954-6 | | JB77954-7 | | JB77954-8 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/17/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | **33.7** | J | 16.5 | J | **26.8** | J | **39.2** | J | 9.2 | J | **23.3** | J | 15.3 | J | 11.9 | J | 15.7 | J | 9.3 | J | **25.8** | J | **21.2** | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-78-20-c | | | | | | | | 124-75-20-a | | | | | | | | 124-75-20-b | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-78-20-c1 | | 124-78-20-c2 | | 124-78-20-c3 | | 124-78-20-c4 | | 124-75-20-a1 | | 124-75-20-a2 | | 124-75-20-a3 | | 124-75-20-a4 | | 124-75-20-b1 | | 124-75-20-b2 | | 124-75-20-b3 | | 124-75-20-b4 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB77954-9 | | JB77954-10 | | JB77954-11/11R | | JB77954-12 | | JB79402-1/1R | | JB79402-2 | | JB79402-3 | | JB79402-4/4R | | JB79402-5/5R | | JB79402-6 | | JB79402-7 | | JB79402-8/8R | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 09/30/2014 | | 10/16/2014 | | 10/16/2014 | | 10/16/2014 | | 10/16/2014 | | 10/16/2014 | | 10/16/2014 | | 10/16/2014 | | 10/16/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 19.5 | J | **20.4** | **J** | **25.4** | **J** | **39** | **J** | 9.6 | J | 10 | J | 11 | J | **25.3** | **J** | 17.3 | J | 15.6 | J | **29.3** | **J** | **65.3** | **J** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-67-20-a | | | | 124-67-20-b | | | | 124-106-20-a | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-67-20-a1 | 124-67-20-a2 | 124-67-20-a3 | 124-67-20-a4 | 124-67-20-b1 | 124-67-20-b2 | 124-67-20-b3 | 124-67-20-b4 | 124-106-20-a1 | 124-106-20-a2 | 124-106-20-a3 | 124-106-20-a4 |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB80267-1 | JB80267-2/2R | JB80267-3/3R | JB80267-4 | JB80267-5 | JB80267-6/6R | JB80267-7 | JB80267-8/8R | JB82420-1 | JB82420-2 | JB82420-3 | JB82420-4 |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 10/28/2014 | 10/28/2014 | 10/28/2014 | 10/28/2014 | 10/28/2014 | 10/28/2014 | 10/28/2014 | 10/28/2014 | 11/21/2014 | 11/21/2014 | 11/21/2014 | 11/21/2014 |
| **Analytes <20 ppm (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 0.45 | **98.2** | 2.6 | 5.2 | **71.9** | **340** | **29.6** | **23.3** | 9.2 | 12.1 | 15.6 | **20** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-110-20-a | | | | | | | | 124-110-20-b | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-110-20-a1-120214 | | 124-110-20-a2-120214 | | 124-110-20-a3-120214 | | 124-110-20-a4-120214 | | 124-110-20-b1-120214 | | 124-110-20-b2-120214 | | 124-110-20-b3-120214 | | 124-110-20-b4-120214 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB83003-1 | | JB83003-2 | | JB83003-3 | | JB83003-4 | | JB83003-5 | | JB83003-6/6R | | JB83003-7 | | JB83003-8/8R | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | **25** | J | **43.9** | J | **29.1** | J | 14.8 | J | **23.1** | J | 12.9 | J | 3.4 | J | 1.8 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-110-20-c | | | | | | | | | | | | 124-114-20-a | | | | | | | | 124-114-20-b | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-110-20-c1-120214 | | 124-110-20-c2-120214 | | 124-110-20-c3-120214 | | 124-110-20-c4-120214 | | 124-114-20-a1 | | 124-114-20-a2 | | 124-114-20-a3 | | 124-114-20-a4 | | 124-114-20-b1 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JB83003-9 | | JB83003-10 | | JB83003-11/11R | | JB83003-12 | | JB84293-1 | | JB84293-2 | | JB84293-3 | | JB84293-4 | | JB84293-5 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/02/2014 | | 12/16/2014 | | 12/16/2014 | | 12/16/2014 | | 12/16/2014 | | 12/16/2014 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 12.9 | J | 15.6 | J | **29.1** | **J** | **179** | **J** | **29.8** | **J** | **34.5** | **J** | **49.3** | **J** | 19.9 | J | 10.6 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2A

## STOCKPILE SOIL RESULTS

## (Designated for <20 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-20-A | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 163-20-A1-011916 | | 163-20-A2-011916 | | 163-20-A3-011916 | | 163-20-A4-011916 | | 163-20-A5-022216 | | 163-20-A6-022216 | | 163-20-A7-022216 | | 163-20-A8-022216 | |
| LAB SAMPLE ID | NJ 2012 | NJ 2013 | JC12931-1 | | JC12931-2 | | JC12931-3 | | JC12931-4 | | JC114638-1 | | JC114638-2 | | JC114638-3 | | JC114638-4 | |
| DATE SAMPLED | MOST STRINGENT SRS | IGW SOIL | 01/19/2016 | | 01/19/2016 | | 01/19/2016 | | 01/19/2016 | | 02/22/2016 | | 02/22/2016 | | 02/22/2016 | | 02/22/2016 | |
| **Analytes <20 ppm (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | 20 | NC | 8.1 | J | 4 | J | 1.7 | J | 5 | J | 2.7 | | 3.6 | | 1 | | 5.1 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; la

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/16/2016

Reviewed by: JLD 05/24/2016

# TABLE 2B
## STOCKPILE SOIL RESULTS
## (Designated for >1,000 mg/Kg Hexavalent Chromium)
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | 124-41-1000-a | | | | 124-41-1000-b | | | | 124-49-1000-a | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | **124-41-1000-a1** | **124-41-1000-a2** | **124-41-1000-a3** | **124-41-1000-a4** | **124-41-1000-b1** | **124-41-1000-b2** | **124-41-1000-b3** | **124-41-1000-b4** | **124-49-1000-a1** | **124-49-1000-a2** | **124-49-1000-a3** | **124-49-1000-a4** |
| LAB SAMPLE ID | **NJ 2012** | JB60523-1 | JB60523-2 | JB60523-3 | JB60523-4 | JB60523-5 | JB60523-6 | JB60523-7 | JB60523-8 | JB62792-1/1R | JB62792-2 | JB62792-3 | JB62792-4 |
| DATE SAMPLED | **MOST STRINGENT SRS** | 02/25/2014 | 02/25/2014 | 02/25/2014 | 02/25/2014 | 02/25/2014 | 02/25/2014 | 02/25/2014 | 02/25/2014 | 03/24/2014 | 03/24/2014 | 03/24/2014 | 03/24/2014 |
| | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | **1750** | **3690** | **3410** | **453** | **490** | **1110** | **669** | **1920** | **3580** | **3850** | **2580** | **5570** |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].
**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**
Depths reported in feet below ground surface
CONC: Concentration reported in milligrams per kilogram (mg/kg)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 2B
## STOCKPILE SOIL RESULTS
## (Designated for >1,000 mg/Kg Hexavalent Chromium)
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | 124-49-1000-b | | | | 124-59-1000-a | | | | 124-125-1000-a | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | **124-49-1000-b1** | **124-49-1000-b2** | **124-49-1000-b3** | **124-49-1000-b4** | **124-59-1000-a1** | **124-59-1000-a2** | **124-59-1000-a3** | **124-59-1000-a4** | **124-125-1000-a1** | **124-125-1000-a2** | **124-125-1000-a3** | **124-125-1000-a4** |
| LAB SAMPLE ID | **NJ 2012** | JB62792-5 | JB62792-6 | JB62792-7 | JB62792-8 | JB64503-1/1R | JB64503-2 | JB64503-3 | JB64503-4 | JB70227-1 | JB70227-2 | JB70227-3 | JB70227-4 |
| DATE SAMPLED | **MOST STRINGENT SRS** | 03/24/2014 | 03/24/2014 | 03/24/2014 | 03/24/2014 | 04/11/2014 | 04/11/2014 | 04/11/2014 | 04/11/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 | 06/25/2014 |
| | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | **8840** | **2340** | 2 | **4250** | **11200** | **26900** | **11900** | **32700** | **42.1** | **652** | **346** | **400** |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26
**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**
Depths reported in feet below ground surface
CONC: Concentration reported in milligrams per kilogram (mg/kg)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 2B
## STOCKPILE SOIL RESULTS
## (Designated for >1,000 mg/Kg Hexavalent Chromium)
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | 124-119-1000-a | | | | | | | | 124-102-1000-a | | | | | | | | 124-102-1000-b | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 124-119-1000-a1 | | 124-119-1000-a2 | | 124-119-1000-a3 | | 124-119-1000-a4 | | 124-102-1000-a1 | | 124-102-1000-a2 | | 124-102-1000-a3 | | 124-102-1000-a4 | | 124-102-1000-b1 | | 124-102-1000-b2 | | 124-102-1000-b3 | | 124-102-1000-b4 | |
| LAB SAMPLE ID | NJ 2012 | JB72777-1 | | JB72777-2/2R | | JB72777-3 | | JB72777-4 | | JB74046-1/1R | | JB74046-2/2R | | JB74046-3/3R | | JB74046-4/4R | | JB74046-5/5R | | JB74046-6 | | JB74046-7/7R | | JB74046-8/8T | |
| DATE SAMPLED | MOST STRINGENT SRS | 07/29/2014 | | 07/29/2014 | | 07/29/2014 | | 07/29/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | |
| | | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| HEXAVALENT CHROMIUM | 20 | **174** | | **302** | | **149** | | **2180** | | **1680** | J | **487** | | **446** | | **299** | | **38.4** | | **139** | J | **64.8** | | **663** | J |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26
**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**
Depths reported in feet below ground surface
CONC: Concentration reported in milligrams per kilogram (mg/kg)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 2B
## STOCKPILE SOIL RESULTS
## (Designated for >1,000 mg/Kg Hexavalent Chromium)
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | 124-75-1000-a | | | | 124-75-1000-b | | | | 163-122-1000-a | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | **124-75-1000-a1** | **124-75-1000-a2** | **124-75-1000-a3** | **124-75-1000-a4** | **124-75-1000-b1** | **124-75-1000-b2** | **124-75-1000-b3** | **124-75-1000-b4** | **163-122-1000-a1** | **163-122-1000-a2** | **163-122-1000-a3** | **163-122-1000-a4** |
| LAB SAMPLE ID | **NJ 2012** | JB80452-1/1R | JB80452-2/2R | JB80452-3 | JB80452-4 | JB80452-5 | JB80452-6 | JB80452-7 | JB80452-8 | JB82103-1 | JB81582-1 | JB82103-2 | JB81582-2 |
| DATE SAMPLED | **MOST STRINGENT SRS** | 10/29/2014 | 10/29/2014 | 10/29/2014 | 10/29/2014 | 10/29/2014 | 10/29/2014 | 10/29/2014 | 10/29/2014 | 11/12/2014 | 11/12/2014 | 11/12/2014 | 11/12/2014 |
| | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | **1410** | **750** | **1360** | **2050** | **2060** | **454** | **591** | **2860** | 4.5 | 4 | **80.1** | **38.1** |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26
**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**
Depths reported in feet below ground surface
CONC: Concentration reported in milligrams per kilogram (mg/kg)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 2B

## STOCKPILE SOIL RESULTS

## (Designated for >1,000 mg/Kg Hexavalent Chromium)

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | 124-114-1000-a | | | |
|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | **124-114-1000-a1** | **124-114-1000-a2** | **124-114-1000-a3** | **124-114-1000-a4** |
| LAB SAMPLE ID | **NJ 2012** | JB84292-1 | JB84292-2 | JB84292-3/3R | JB84292-4 |
| DATE SAMPLED | **MOST STRINGENT SRS** | 12/16/2014 | 12/16/2014 | 12/16/2014 | 12/16/2014 |
| | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| HEXAVALENT CHROMIUM | 20 | **42.3** | **65** | **75.3** | 16.5 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 3A

## CWTP Effluent Results - VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-102813 | | 087-TW-01-111813 | | 087-TW-01-120313 | | 087-TW-01-010914 | | 087-TW-01-020414 | | 087-TW-01-030514 | | 087-TW-01-040314 | | 087-TW-01-050714 | | 087-TW-01-060414 | | 087-TW-01-080514 | | 087-TW-01-080514 | | 087-TW-01-090214 | | 087-TW-01-100914 | | 087-TW-01-110514 | | 087-TW-01-120214 | |
| SAMPLING DATE | | | 10/28/2013 | | 11/18/2013 | | 12/03/2013 | | 01/09/2014 | | 02/04/2014 | | 03/05/2014 | | 04/03/2014 | | 05/07/2014 | | 06/04/2014 | | 08/05/2014 | | 08/05/2014 | | 09/02/2014 | | 10/09/2014 | | 11/05/2014 | | 12/02/2014 | |
| LAB SAMPLE ID | | | JB51378-1 | | JB53452-1 | | JB54588-1 | | JB57249-1 | | JB59174-1 | | JB61118-1 | | JB63754-1 | | JB66403-1 | | JB68434-1 | | JB70814-1 | | JB73272-1 | | JB75472-1 | | JB78961-1 | | JB80999-1 | | JB83004-1 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | |
| PARAMETER | Report Units | Criteria | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1,1-TRICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1,2,2-TETRACHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1,2-TRICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1-DICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1-DICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,2-DICHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,2-DICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | UJ | 1 | U | 1 | U |
| 1,2-DICHLOROPROPANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,3-DICHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,4-DICHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 2-CHLOROETHYL VINYL ETHER | ug/l | NC | 5 | U | 5 | UJ | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | UJ | 5 | U | 5 | UJ | 5 | U | 5 | U |
| ACROLEIN | ug/l | NC | 50 | R | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U |
| ACRYLONITRILE | ug/l | NC | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| BENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 0.45 | J | 0.25 | J | 0.72 | J | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.27 | J | 1 | U | 1 | U |
| BROMODICHLOROMETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BROMOFORM | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BROMOMETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | UJ | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CARBON TETRACHLORIDE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.54 | J |
| CHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 5.4 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.47 | J |
| CHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CHLOROFORM | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1.4 | | 1 | U | 1 | U | 0.27 | J | 0.42 | J |
| CHLOROMETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.31 | J | 1 | U | 1 | U | 0.34 | J | 1 | U |
| CIS-1,2-DICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CIS-1,3-DICHLOROPROPENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| Dibromochloromethane | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| DICHLORODIFLUOROMETHANE | ug/l | NC | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | UJ | 2 | U | 2 | U | 2 | U | 2 | U |
| ETHYLBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 0.65 | J | 0.63 | J | 1.8 | | 1.9 | | 1.1 | | 0.32 | J | 1 | U | 0.35 | J | 0.32 | J | 0.38 | J | 0.84 | J | 1 | U |
| METHYLENE CHLORIDE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.33 | J | 1 | U | 1 | U | 1 | U |
| TETRACHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TOLUENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 0.36 | J | 0.35 | J | 0.45 | J | 1 | U | 1 | U | 1 | U | 1 | U | 0.33 | J | 0.25 | J | 0.33 | J | 0.23 | J | 1 | U |
| TRANS-1,2-DICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TRANS-1,3-DICHLOROPROPENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | UJ | 1 | U | 1 | U |
| TRICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TRICHLOROFLUOROMETHANE | ug/l | NC | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U |
| VINYL CHLORIDE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| XYLENES, TOTAL | ug/l | NC | 1 | U | 1 | U | 1 | U | 2.9 | | 2.8 | | 12.8 | | 21.4 | | 9.1 | | 2.1 | | 0.89 | J | 1.9 | | 2.2 | | 2.3 | | 5.8 | | 1 | U |
| Total VOCs | ug/l | 2130 | 0 | | 0 | | 0 | | 4.36 | | 4.03 | | 15.77 | | 23.3 | | 10.2 | | 7.82 | | 0.89 | | 4.29 | | 3.1 | | 3.28 | | 7.48 | | 1.43 | |

Notes:

SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019

NC: No criterion established

**Bold and underlined concentrations exceed the CWTP Effluent Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

CONC: Concentration reported in micrograms per liter (ug/l)

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 3A

## CWTP Effluent Results - VOCs

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-011315 | | 087-TW-01-020415 | | 087-TW-01-030415 | | 087-TW-01-040115 | | 087-TW-01-050515 | | 087-TW-01-060415 | | 087-TW-01-070115 | | 087-TW-01-080715 | | 087-TW-01-090115 | | 087-TW-01-100115 | | 087-TW-01-110215 | | 087-TW-01-121015 | | 087-TW-01-011216 | | 087-TW-01-020216 | |
| SAMPLING DATE | | | 01/13/2015 | | 02/04/2015 | | 03/04/2015 | | 04/01/2015 | | 05/05/2015 | | 06/04/2015 | | 07/01/2015 | | 08/07/2015 | | 09/01/2015 | | 10/01/2015 | | 11/02/2015 | | 12/10/2015 | | 01/12/2016 | | 02/02/2016 | |
| LAB SAMPLE ID | | | JB86263-1 | | JB87588-1 | | JB89260-1 | | JB91370-1 | | JB93967-1 | | JB96257-1 | | JB98303-1 | | JC1065-1 | | JC2782-1 | | JC5236-1 | | JC7548-1 | | JC10340-1 | | JC12447-1 | | JC13531-1 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | |
| PARAMETER | Report Units | Criteria | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1,1-TRICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1,2,2-TETRACHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1,2-TRICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1-DICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,1-DICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,2-DICHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,2-DICHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,2-DICHLOROPROPANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,3-DICHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 1,4-DICHLOROBENZENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| 2-CHLOROETHYL VINYL ETHER | ug/l | NC | 5 | U | 5 | U | 5 | U | 5 | UJ | 5 | U | 5 | U | 5 | U | 5 | U | 5 | UJ | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U |
| ACROLEIN | ug/l | NC | 50 | R | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| ACRYLONITRILE | ug/l | NC | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| BENZENE | ug/l | NC | 0.43 | J | 0.49 | J | 0.3 | J | 0.62 | J | 1 | U | 0.26 | J | 0.29 | J | 1 | U | 0.22 | J | 1 | U | 0.29 | J | 1 | U | 1 | U | 1 | U |
| BROMODICHLOROMETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 4.9 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BROMOFORM | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BROMOMETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CARBON TETRACHLORIDE | ug/l | NC | 1.1 | | 4.4 | | 12.3 | | 1.3 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.38 | J | 1 | U |
| CHLOROBENZENE | ug/l | NC | 0.66 | J | 1.6 | | 1.9 | | 0.38 | J | 0.21 | J | 0.22 | J | 0.58 | J | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.62 | J |
| CHLOROETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CHLOROFORM | ug/l | NC | 3.2 | | 13.7 | | 21.2 | | 1.6 | | 1 | U | 1 | U | 1 | U | 8.8 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CHLOROMETHANE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 0.19 | J | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CIS-1,2-DICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1.2 | | 1 | U |
| CIS-1,3-DICHLOROPROPENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| Dibromochloromethane | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1.7 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| DICHLORODIFLUOROMETHANE | ug/l | NC | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U |
| ETHYLBENZENE | ug/l | NC | 1.2 | | 1.3 | | 0.84 | J | 0.99 | J | 0.32 | J | 1 | U | 0.49 | J | 1 | U | 1 | U | 0.36 | J | 1 | U | 1 | U | 1 | U | 1 | U |
| METHYLENE CHLORIDE | ug/l | NC | 1 | U | 0.37 | J | 0.49 | J | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TETRACHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TOLUENE | ug/l | NC | 0.47 | J | 0.68 | J | 0.34 | J | 1 | U | 0.25 | J | 1 | U | 0.35 | J | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TRANS-1,2-DICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TRANS-1,3-DICHLOROPROPENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TRICHLOROETHENE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| TRICHLOROFLUOROMETHANE | ug/l | NC | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U |
| VINYL CHLORIDE | ug/l | NC | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| XYLENES, TOTAL | ug/l | NC | 9.6 | | 10.5 | | 5.9 | | 3 | | 2.9 | | 1.5 | | 4.1 | | 1 | U | 0.26 | J | 2.5 | | 1 | U | 1 | U | 1 | U | 1 | U |
| Total VOCs | ug/l | 2130 | 16.66 | | 33.04 | | 43.27 | | 7.89 | | 3.68 | | 1.98 | | 5.81 | | 15.4 | | 0.67 | | 2.86 | | 0.29 | | 0 | | 1.58 | | 0.62 | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in micrograms per liter (ug/l)
J: Estimated concentration
R or N: Rejected or negated by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3B

## CWTP Effluent Results - Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-102813 | | 087-TW-01-111813 | | 087-TW-01-120313 | | 087-TW-01-010914 | | 087-TW-01-020414-C | | 087-TW-01-030514 | | 087-TW-01-040314 | | 087-TW-01-050714 | | 087-TW-01-060414 | | 087-TW-01-080514 | | 087-TW-01-080514 | | 087-TW-01-090214-C | | 087-TW-01-100914-C | | 087-TW-01-110514-C | |
| SAMPLING DATE | | | 10/28/2013 | | 11/18/2013 | | 12/03/2013 | | 01/09/2014 | | 02/04/2014 | | 03/05/2014 | | 04/03/2014 | | 05/07/2014 | | 06/04/2014 | | 08/05/2014 | | 08/05/2014 | | 09/02/2014 | | 10/09/2014 | | 11/05/2014 | |
| LAB SAMPLE ID | | | JB51378-1 | | JB53452-1 | | JB54588-1 | | JB57249-2 | | JB59174-2 | | JB61118-2 | | JB63754-2 | | JB66403-2 | | JB68434-2 | | JB70814-2 | | JB73272-2 | | JB75472-2 | | JB78961-2 | | JB80999-2 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | |
| PARAMETER | Report Units | Criteria | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| CHROMIUM | mg/L | NC | 0.522 | | 0.298 | | 0.188 | | 0.822 | | 0.321 | | 0.338 | | 0.385 | | 0.407 | | 1.12 | | 5.01 | | 2.55 | | 1.43 | | 1.41 | | 1.29 | |
| COPPER | mg/L | 3.6 | 0.0108 | | 0.01 | U | 0.01 | UJ | 0.0104 | | 0.01 | U | 0.0154 | | 0.0247 | | 0.0352 | | 0.0357 | | 0.012 | | 0.0188 | | 0.0205 | | 0.01 | U | 0.0315 | |
| LEAD | mg/L | 1 | 0.003 | U | 0.0051 | | 0.0061 | | 0.0075 | | 0.0127 | | 0.0085 | | 0.0176 | | 0.0371 | | 0.0432 | | 0.014 | | 0.0198 | | 0.0217 | | 0.0055 | | 0.0244 | |
| MERCURY | mg/L | 0.08 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.00031 | | 0.00045 | | 0.0002 | U | 0.00044 | | 0.00037 | | 0.0002 | U | 0.0003 | |
| NICKEL | mg/L | 3.9 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.0126 | | 0.0151 | | 0.0231 | | 0.032 | | 0.0201 | | 0.0284 | | 0.0345 | | 0.0323 | | 0.0467 | |
| ZINC | mg/L | 4.2 | 0.154 | | 0.216 | | 0.269 | | 0.133 | | 0.222 | | 0.418 | | 0.446 | | 0.168 | J | 0.163 | | 0.109 | | 0.117 | | 0.247 | | 0.0569 | J | 0.151 | |

Notes:

SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019

NC: No criterion established

**Bold and underlined concentrations exceed the CWTP Effluent Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

CONC: Concentration reported in milligrams per liter (mg/L)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 3B
## CWTP Effluent Results - Metals
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-120214C | | 087-TW-01-011315C | | 087-TW-01-020415C | | 087-TW-01-030415C | | 087-TW-01-040115C | | 087-TW-01-050515C | | 087-TW-01-060415C | | 087-TW-01-070115C | | 087-TW-01-080715C | | 087-TW-01-090115C | | 087-TW-01-100115C | | 087-TW-01-110215C | | 087-TW-01-121015C | |
| SAMPLING DATE | | | 12/02/2014 | | 01/13/2015 | | 02/04/2015 | | 03/04/2015 | | 04/01/2015 | | 05/05/2015 | | 06/04/2015 | | 07/01/2015 | | 08/07/2015 | | 09/01/2015 | | 10/01/2015 | | 11/02/2015 | | 12/10/2015 | |
| LAB SAMPLE ID | | | JB83004-2 | | JB86263-2 | | JB87588-2 | | JB89260-2 | | JB91370-2 | | JB93967-2 | | JB96257-2 | | JB98303-2 | | JC1065-2 | | JC2782-2 | | JC5236-2 | | JC7548-2 | | JC10340-2 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent Criteria | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | |
| **PARAMETER** | **Report Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CHROMIUM | mg/L | NC | 0.77 | | 1.85 | | 2.09 | | 1.1 | | 0.274 | | 1.04 | | 5.46 | | 3.59 | | 0.392 | | 2.14 | | 1.25 | | 4.61 | | 1.36 | |
| COPPER | mg/L | 3.6 | 0.052 | | 0.01 | U | 0.01 | U | 0.0219 | | 0.0113 | | 0.01 | U | 0.0168 | | 0.01 | U | 0.0195 | | 0.0322 | | 0.0197 | | 0.0205 | | 0.0141 | |
| LEAD | mg/L | 1 | 0.0464 | | 0.0061 | | 0.0055 | | 0.015 | U | 0.0387 | | 0.0141 | | 0.0061 | | 0.0081 | | 0.0552 | | 0.0418 | | 0.0058 | | 0.0123 | | 0.0407 | |
| MERCURY | mg/L | 0.08 | 0.0013 | | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0004 | U | 0.0002 | U | 0.0002 | U | 0.00027 | |
| NICKEL | mg/L | 3.9 | 0.0638 | | 0.036 | | 0.0227 | | 0.05 | U | 0.0196 | | 0.0196 | | 0.0148 | | 0.016 | | 0.01 | U | 0.0235 | | 0.0253 | | 0.0224 | | 0.01 | U |
| ZINC | mg/L | 4.2 | 0.858 | | 0.149 | | 0.309 | | 0.241 | | 0.0799 | | 0.0525 | | 0.0873 | | 0.153 | | 0.0699 | | 0.0688 | | 0.0314 | | 0.094 | | 0.058 | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3B
## CWTP Effluent Results - Metals
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-011216C | | 087-TW-01-020216C | |
| SAMPLING DATE | | | 01/12/2016 | | 02/02/2016 | |
| LAB SAMPLE ID | | | JC12447-2 | | JC13531-2 | |
| Sample Purpose | | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent | No | | No | |
| PARAMETER | Report Units | Criteria | CONC | Q | CONC | Q |
| CHROMIUM | mg/L | NC | 0.218 | | 0.0997 | |
| COPPER | mg/L | 3.6 | 0.0134 | | 0.0325 | |
| LEAD | mg/L | 1 | 0.0163 | | 0.0555 | |
| MERCURY | mg/L | 0.08 | 0.0002 | U | 0.0002 | |
| NICKEL | mg/L | 3.9 | 0.01 | U | 0.0164 | |
| ZINC | mg/L | 4.2 | 0.0768 | | 0.165 | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3C
## CWTP Effluent Results - General Chemistry
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-EFF-01 | | 087-INF-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-102813 | | 087-TW-01-111813 | | 087-TW-01-120313 | | 087-TW-01-010914 | | 087-TW-01-010914 | | 087-TW-01-020414 | | 087-TW-01-020414-C | | 087-TW-01-030514 | | 087-TW-01-030514 | | 087-TW-01-040314 | | 087-TW-01-040314 | | 087-EFF-01-042514 | | 087-INF-01-042514 | | 087-TW-01-050714 | |
| SAMPLING DATE | | | 10/28/2013 | | 11/18/2013 | | 12/03/2013 | | 01/09/2014 | | 01/09/2014 | | 02/04/2014 | | 02/04/2014 | | 03/05/2014 | | 03/05/2014 | | 04/03/2014 | | 04/03/2014 | | 04/25/2014 | | 04/25/2014 | | 05/07/2014 | |
| LAB SAMPLE ID | | | JB51378-1/1A | | JB53452-1/1A | | JB54588-1/1A | | JB57249-1 | | JB57249-2 | | JB59174-1 | | JB59174-2 | | JB61118-1 | | JB61118-2 | | JB63754-1 | | JB63754-2 | | JB65610-1 | | JB65610-2 | | JB66403-1 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent Criteria | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | |
| PARAMETER | Report Units | | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| BIOCHEMICAL OXYGEN DEMAND, FIVE DAY | mg/L | NC | 13.8 | | 10.9 | | 14.5 | | - | | 88 | | - | | 32.2 | | - | | 301 | | - | | 193 | | - | | - | | - | |
| HEXANE EXT MATERIAL SILICA GEL TREATED | mg/L | 100 | 5.3 | U | 5 | U | 5.1 | U | 5.3 | U | - | | 5.1 | UJ | - | | 5.1 | UJ | - | | 5 | UJ | - | | 5.1 | U | 5.1 | U | 5.1 | U |
| pH | S.U. | 5-10.5 | 7.48 | | 7.44 | | 7.53 | | 7.85 | | - | | 7.29 | | - | | 7.79 | | - | | 7.7 | | - | | - | | - | | 8.51 | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3C
## CWTP Effluent Results - General Chemistry
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-050714 | | 087-TW-01-060414 | | 087-TW-01-060414 | | 087-TW-01-080514 | | 087-TW-01-080514 | | 087-TW-01-080514 | | 087-TW-01-080514 | | 087-TW-01-090214 | | 087-TW-01-090214-C | | 087-TW-01-100914 | | 087-TW-01-100914-C | | 087-TW-01-110514 | | 087-TW-01-110514-C | |
| SAMPLING DATE | | | 05/07/2014 | | 06/04/2014 | | 06/04/2014 | | 08/05/2014 | | 08/05/2014 | | 08/05/2014 | | 08/05/2014 | | 09/02/2014 | | 09/02/2014 | | 10/09/2014 | | 10/09/2014 | | 11/05/2014 | | 11/05/2014 | |
| LAB SAMPLE ID | | | JB66403-2 | | JB68434-1 | | JB68434-2 | | JB70814-1 | | JB70814-2 | | JB73272-1 | | JB73272-2 | | JB75472-1 | | JB75472-2 | | JB78961-1 | | JB78961-2 | | JB80999-1 | | JB80999-2 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent Criteria | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | | No | |
| PARAMETER | Report Units | | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| BIOCHEMICAL OXYGEN DEMAND, FIVE DAY | mg/L | NC | 10 | U | - | | 13.1 | | - | | 9.2 | | - | | 20 | U | - | | 9.5 | | - | | 16.9 | | - | | 7.9 | |
| HEXANE EXT MATERIAL SILICA GEL TREATED | mg/L | 100 | - | | 5.1 | UJ | - | | 5 | U | - | | 5.2 | U | - | | 5 | U | - | | 5.1 | U | - | | 5.4 | U | - | |
| pH | S.U. | 5-10.5 | - | | 7.93 | | - | | 6.8 | | - | | 8.7 | | - | | 8.86 | | - | | 10.61 | | - | | 8.01 | | - | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3C
## CWTP Effluent Results - General Chemistry
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-120214 | | 087-TW-01-120214C | | 087-TW-01-011315 | | 087-TW-01-011315C | | 087-TW-01-020415 | | 087-TW-01-020415C | | 087-TW-01-030415 | | 087-TW-01-030415C | | 087-TW-01-040115 | | 087-TW-01-040115C | | 087-TW-01-050515 | | 087-TW-01-050515C | |
| SAMPLING DATE | | | 12/02/2014 | | 12/02/2014 | | 01/13/2015 | | 01/13/2015 | | 02/04/2015 | | 02/04/2015 | | 03/04/2015 | | 03/04/2015 | | 04/01/2015 | | 04/01/2015 | | 05/05/2015 | | 05/05/2015 | |
| LAB SAMPLE ID | | | JB83004-1 | | JB83004-3 | | JB86263-1 | | JB86263-2 | | JB87588-1 | | JB87588-2 | | JB89260-1 | | JB89260-2 | | JB91370-1 | | JB91370-2 | | JB93967-1 | | JB93967-2 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent Criteria | No | | No | | No | | No | | No | | No | | No | | N | | N | | N | | N | | N | |
| **PARAMETER** | **Report Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| BIOCHEMICAL OXYGEN DEMAND, FIVE DAY | mg/L | NC | - | | 32.5 | | - | | 29.4 | | - | | 11.6 | | - | | 12.8 | | - | | 9.3 | | - | | 7.5 | | - | | 20 | U |
| HEXANE EXT MATERIAL SILICA GEL TREATED | mg/L | 100 | 5 | UJ | - | | 5.1 | UJ | - | | 5.3 | UJ | - | | 5 | U | - | | 5.1 | U | - | | 5.2 | U | - | | 5.1 | U | - | |
| pH | S.U. | 5-10.5 | 8.07 | | - | | 7.07 | | - | | 9.41 | | - | | 7.91 | | - | | 8.62 | | - | | 6.91 | | - | | 7.89 | | - | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3C
## CWTP Effluent Results - General Chemistry
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-070115 | | 087-TW-01-070115C | | 087-TW-01-080715 | | 087-TW-01-080715C | | 087-TW-01-090115 | | 087-TW-01-090115C | | 087-TW-01-100115 | | 087-TW-01-100115C | | 087-TW-01-110215 | | 087-TW-01-110215C | | 087-TW-01-121015 | | 087-TW-01-121015C | | 087-TW-01-011216 | | 087-TW-01-011216C | |
| SAMPLING DATE | | | 07/01/2015 | | 07/01/2015 | | 08/07/2015 | | 08/07/2015 | | 09/01/2015 | | 09/01/2015 | | 10/01/2015 | | 10/01/2015 | | 11/02/2015 | | 11/02/2015 | | 12/10/2015 | | 12/10/2015 | | 01/12/2016 | | 01/12/2016 | |
| LAB SAMPLE ID | | | JB98303-1 | | JB98303-2 | | JC1065-1 | | JC1065-2 | | JC2782-1 | | JC2782-2 | | JC5236-1 | | JC5236-2 | | JC7548-1 | | JC7548-2 | | JC10340-1 | | JC10340-2 | | JC12447-1 | | JC12447-2 | |
| Sample Purpose | | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent Criteria | No | | No | | No | | No | | No | | No | | No | | N | | N | | N | | N | | N | | N | | N | |
| PARAMETER | Report Units | | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| BIOCHEMICAL OXYGEN DEMAND, FIVE DAY | mg/L | NC | - | | 10.3 | | - | | 5 | U | - | | 14 | U | - | | 8.8 | | - | | 5 | U | - | | 4.3 | U | - | | 8.6 | |
| HEXANE EXT MATERIAL SILICA GEL TREATED | mg/L | 100 | 5 | U | - | | 5 | U | - | | 5.2 | U | - | | 5.2 | U | - | | 5.1 | U | - | | 5.1 | UJ | - | | 5.1 | U | - | |
| pH | S.U. | 5-10.5 | 8.59 | | - | | 8.23 | | - | | 8.74 | | - | | 6.95 | | - | | 7.69 | | - | | 8.39 | | - | | 7.52 | | - | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 3C

## CWTP Effluent Results - General Chemistry

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| SAMPLE LOCATION | | | 087-TW-01 | | 087-TW-01 | |
|---|---|---|---|---|---|---|
| FIELD SAMPLE ID | | | 087-TW-01-020216 | | 087-TW-01-020216C | |
| SAMPLING DATE | | | 02/02/2016 | | 02/02/2016 | |
| LAB SAMPLE ID | | | JC13531-1 | | JC13531-2 | |
| Sample Purpose | | | REG | | REG | |
| Filtered | | SA-6 CWTP Effluent Criteria | No | | No | |
| PARAMETER | Report Units | | CONC | Q | CONC | Q |
| BIOCHEMICAL OXYGEN DEMAND, FIVE DAY | mg/L | NC | - | | 7.8 | |
| HEXANE EXT MATERIAL SILICA GEL TREATED | mg/L | 100 | 5 | U | - | |
| pH | S.U. | 5-10.5 | 7.51 | | - | |

Notes:
SA-6 CWTP Effluent Criteria is the discharge limitation criteria from Sewer Use Permit #31630019
NC: No criterion established
**Bold and underlined concentrations exceed the CWTP Effluent Criteria**
*Italicized values not detected; reporting limit exceeds criteria*
CONC: Concentration reported in milligrams per liter (mg/L)
J: Estimated concentration
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 4

## Baseline Groundwater Elevation Monitoring

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | SA-6 South Cap Contingent Groundwater System Water Elevations | | | |
|---|---|---|---|---|
| | Pump Station | Access MH #1 | Access MH #2 | Access MH #3 |
| 10/1/2015 | 0.42 | 0.58 | 1.62 | 1.73 |
| 10/28/2015 | 0.82 | 0.68 | 1.62 | 1.72 |
| 12/1/2015 | 1.74 | 1.48 | 1.64 | 1.66 |
| 12/30/2015 | 1.97 | 1.84 | 0.87 | 1.88 |
| 2/1/2016 | 2.25 | 2.08 | 2.17 | 2.16 |
| 3/1/2016 | 2.52 | 2.48 | Temp. Unavailable | 2.46 |
| 4/1/2016 | 2.86 | 2.68 | 2.77 | 2.69 |
| 5/2/2016 | 2.8 | 2.79 | 2.73 | 2.86 |
| 6/1/2016 | 3 | 2.98 | 2.95 | 3.01 |
| 6/28/2016 | 3.05 | 3.16 | 3.19 | 3.19 |
| 7/27/2016 | 3.21 | 3.31 | 3.35 | 3.36 |
| 8/29/2016 | 3.4 | 3.45 | 3.45 | 3.46 |
| 9/29/2016 | 3.49 | 3.56 | 3.51 | 3.51 |
| 11/4/2016 | 3.52 | 3.55 | 3.56 | 3.54 |

| | SA-6 South Monitoring Wells | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | 115-W3-SO | 115-W5-SO | 115-E1A-SO | 073-MW-07 | 124-MW-11 | 124-MW-12 | 134-MW-03 | 140-MW-10 | 163-MW-1 |
| 10/1/2015 | 1.16 | 1.58 | 1.83 | NR | NR | NR | NR | NR | NR |
| 10/28/2015 | 1.26 | 1.48 | 1.93 | NR | NR | NR | NR | NR | NR |
| 12/1/2015 | 1.66 | 1.58 | 1.73 | NR | NR | NR | NR | NR | NR |
| 12/30/2015 | 1.83 | 1.85 | 1.83 | NR | NR | NR | NR | NR | NR |
| 2/1/2016 | 2.12 | 2.13 | 2.18 | NR | NR | NR | NR | NR | NR |
| 3/1/2016 | 2.26 | 2.48 | 2.53 | NR | NR | NR | NR | NR | NR |
| 4/1/2016 | 2.59 | 2.69 | 2.73 | NR | NR | NR | NR | NR | NR |
| 5/2/2016 | 2.6 | 2.83 | 2.86 | NR | NR | NR | NR | NR | NR |
| 6/1/2016 | 2.82 | 3.00 | 2.68 | 2.99 | 5.07 | 5.03 | 3.61 | 3.91 | 3.26 |
| 6/28/2016 | 3.07 | 3.18 | 3.21 | 3.85 | 4.67 | 6.24 | 4.18 | 3.7 | 3.32 |
| 7/27/2016 | 3.06 | 3.3 | 3.17 | 3.88 | 4.73 | 6.17 | 4.2 | 3.86 | 3.34 |
| 8/29/2016 | 3.35 | 3.48 | 3.52 | 2.96 | 4.21 | 4.4 | 3.48 | 3.7 | 3.88 |
| 9/29/2016 | 3.45 | 3.52 | 3.57 | 2.94 | 4.14 | 4.91 | 3.31 | 3.56 | 3.53 |
| 11/4/2016 | 3.57 | 3.57 | 3.6 | 3.78 | 4.59 | 4.65 | 3.91 | 4.25 | 3.84 |



Prepared by: JLD 09/30/2016

Reviewed by: NW 11/30/2016

# TABLE 4

## Baseline Groundwater Elevation Monitoring

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | SA-6 South Piezometers | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | 124-PZ-11 | 124-PZ-12 | 124-PZ-13 | 124-PZ-14 | 124-PZ-15 | 124-PZ-16 | 124-PZ-17 | 124-PZ-18 | 124-PZ-19 | 124-PZ-20 |
| 10/1/2015 | NR | NR | NR | NR | NR | NR | NR | NR | NR | NR |
| 10/28/2015 | 3.64 | 2.55 | 4.54 | 1.94 | 4.23 | 1.91 | 4.07 | 1.13 | 4.96 | 0.88 |
| 12/1/2015 | 3.09 | 2.15 | 4.36 | 1.77 | 3.86 | 1.59 | 3.61 | 1.63 | 2.79 | 1.71 |
| 12/30/2015 | 6.04 | 2.44 | 6.17 | 1.95 | 4.76 | 1.81 | 4.74 | 1.69 | 3.13 | 1.94 |
| 2/1/2016 | 6.34 | 2.77 | 7.04 | 2.58 | 5.79 | 2.13 | 5.87 | 2.13 | 2.76 | 2.18 |
| 3/1/2016 | 6.49 | 3.17 | 6.82 | 3.13 | 5.76 | 2.49 | 5.17 | 2.48 | 2.41 | 2.48 |
| 4/1/2016 | 4.81 | 3.22 | 5.98 | 2.93 | 5.16 | 2.78 | 4.27 | 2.74 | 2.59 | 2.83 |
| 5/2/2016 | 3.96 | 3.11 | 5.42 | 2.98 | 4.63 | 2.88 | 3.66 | 2.64 | 2.71 | 2.95 |
| 6/1/2016 | 5.65 | 3.22 | 5.68 | 3.13 | 3.67 | 3.00 | 3.73 | 2.97 | 2.71 | 3.03 |
| 6/28/2016 | 4.51 | 3.43 | 5.27 | 3.38 | 4.39 | 3.28 | 3.65 | 2.93 | 2.82 | 3.25 |
| 7/27/2016 | 5.63 | 3.49 | 5.17 | 3.43 | 4.36 | 3.35 | 3.91 | 3.01 | 2.81 | 3.41 |
| 8/29/2016 | 4.22 | 3.58 | 4.89 | 3.62 | 4.24 | 3.55 | 3.55 | 3.20 | 3.04 | 3.56 |
| 9/29/2016 | 3.64 | 3.48 | 4.3 | 3.52 | 3.9 | 3.54 | 3.36 | 3.12 | 4.26 | 3.57 |
| 11/4/2016 | 4.38 | 3.46 | 4.96 | 3.57 | 4.44 | 3.62 | 3.91 | 3.26 | 3.63 | 3.72 |



Prepared by: JLD 09/30/2016

Reviewed by: NW 11/30/2016

# TABLE 5

## SHALLOW MONITORING WELL LIST

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Study Area | Site | Well | Easting | Northing | Permit Number | Well Depth (feet below TOC) | Well Diam (in) | Well Construction |
|---|---|---|---|---|---|---|---|---|
| SA-6 South | 73 | 073-MW-03 | 601380.5 | 685414.4 | 26-8427 | 15 | 2.0 | PVC |
| SA-6 South | 73 | 073-MW-06 | 601396.0 | 685464.0 | E201601094 | 21.61 | 2.0 | PVC |
| SA-6 South | 73 | 073-MW-07 | 601451.0 | 685358.0 | E201601093 | 18.70 | 2.0 | PVC |
| SA-6 South | 73 | 073-MW-08 | 601621.0 | 685234.0 | E201601092 | 18.23 | 2.0 | PVC |
| SA-6 South | 124 | 124-MW-10 | 602764.9 | 684042.8 | E201005711 | 10.91 | 2.0 | PVC |
| SA-6 South | 124 | 124-MW-11 | 603010.7 | 683800.1 | E201005712 | 8.11 | 2.0 | PVC |
| SA-6 South | 124 | 124-MW-12 | 602732.0 | 684286.0 | E201601085 | 13.55 | 2.0 | PVC |
| SA-6 South | 124 | 124-MW-13 | 603014.0 | 684268.0 | E201601084 | 14.88 | 2.0 | PVC |
| SA-6 South | 125 | 125-MW-02 | 602448.0 | 684489.0 | E201601087 | 13.22 | 2.0 | PVC |
| SA-6 South | 125 | 125-MW-03 | 602577.0 | 684585.0 | E201601086 | 13.55 | 2.0 | PVC |
| SA-6 South | 134 | 134-MW-02 | 602033.0 | 684898.0 | E201009352 | 10 | 2.0 | PVC |
| SA-6 South | 134 | 134-MW-V09R | 601868.0 | 685185.4 | E201601098 | 20.07 | 2.0 | PVC |
| SA-6 South | 134 | 134-MW-03 | 601865.0 | 685020.0 | E201601091 | 16.70 | 2.0 | PVC |
| SA-6 South | 134 | 134-MW-04 | 602016.0 | 685002.0 | E201601090 | 17.15 | 2.0 | PVC |
| SA-6 South | 140 | 140-MW-04 | 602308.6 | 684543.7 | 2632541 | 11.95 | 4.0 | PVC |
| SA-6 South | 140 | 140-MW-1R | 602326.0 | 684576.0 | 2600084352 | 12.41 | 2.0 | PVC |
| SA-6 South | 140 | 140-MW-08R | 602412.0 | 684614.0 | E201601100 | 13.24 | 2.0 | PVC |
| SA-6 South | 140 | 140-MW-09 | 602106.0 | 684819.0 | E201601089 | 15.68 | 2.0 | PVC |
| SA-6 South | 140 | 140-MW-10 | 602287.0 | 684774.0 | E201601088 | 13.90 | 2.0 | PVC |
| SA-6 South | 163 | 163-MW-1 | 601890.4 | 684839.6 | -- | 12.41 | 2.0 | PVC |
| SA-6 South | 163 | 163-MW-2R | 601444.8 | 685203.1 | E201115327 | 17.20 | 2.0 | PVC |
| SA-6 South | 163 | 163-MW-03 | 601575.0 | 685166.0 | E201601099 | 21.17 | 2.0 | PVC |
| SA-6 South | 124 | 124-PZ-11 | 603289.6 | 684200.3 | E201506364 | 15.22 | 4.0 | SS |
| SA-6 South | 124 | 124-PZ-12 | 603277.3 | 684208 | E201506365 | 15.20 | 4.0 | SS |
| SA-6 South | 124 | 124-PZ-13 | 602894.3 | 684390.9 | E201506366 | 15.16 | 4.0 | SS |



Prepared by CR
Reviewed by NW 06/14/16

# TABLE 5

## SHALLOW MONITORING WELL LIST

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Study Area | Site | Well | Easting | Northing | Permit Number | Well Depth (feet below TOC) | Well Diam (in) | Well Construction |
|---|---|---|---|---|---|---|---|---|
| SA-6 South | 124 | 124-PZ-14 | 602907.3 | 684420.4 | E201506367 | 15.17 | 4.0 | SS |
| SA-6 South | 140 | 124-PZ-15 | 602497.6 | 684735.3 | E201506368 | 15.25 | 4.0 | SS |
| SA-6 South | 140 | 124-PZ-16 | 602508.9 | 684751.4 | E201506369 | 19.66 | 4.0 | SS |
| SA-6 South | 134 | 124-PZ-17 | 601977 | 685121.8 | E201506370 | 19.94 | 4.0 | SS |
| SA-6 South | 134 | 124-PZ-18 | 601988.8 | 685136.7 | E201506371 | 19.80 | 4.0 | SS |
| SA-6 South | 73 | 124-PZ-19 | 601501 | 685587 | E201506372 | 19.75 | 4.0 | SS |
| SA-6 South | 73 | 124-PZ-20 | 601504.2 | 685583.9 | E201506373 | 20.06 | 4.0 | SS |
| SA-7 | 115 | 115-E1A-SO | 603040.1 | 684482.3 | -- | 23.70 | 2.0 | PVC |
| SA-7 | 115 | 115-W3-SO | 601654.4 | 685551.2 | 2600078831 | 20.73 | 2.0 | PVC |
| SA-7 | 115 | 115-W5-SO | 602426.2 | 684964.5 | -- | 23.80 | 2.0 | PVC |

Notes:

1. New Jersey State Plane Coordinates relative to North American Datum (NAD) of 1983.
2. Diam (in) = Well diameter in inches
3. PVC = Polyvinyl Chloride
4. SS = Stainless Steel
5. SA-7 wells included are within the SA-6 South Open Space AOC.
6. Well depth is feet below top of casing (April 2016).
7. NM = not measured.



Prepared by CR
Reviewed by NW 06/14/16

# TABLE 6A

## Expanded Excavation Site 134 Soil Sample Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Location ID | | | | 134-SB-160 | | 134-SB-161 | | 134-SB-162 | | 134-SB-164 | | 134-SB-165 | | 134-SB-167 | | 134-SB-168 | | 134-SB-169 | | 134-SB-170 | | 134-SB-171 | | 134-SB-172 | | 134-SB-173 | | 134-SB-174 | | 134-SB-175 | | 134-SB-177 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Client Sample ID | | | | 134-SB-160-073014 | | 134-SB-161-081914 | | 134-SB-162-081914 | | 134-SB-164-082014 | | 134-SB-165-082114 | | 134-SB-167-090914 | | 134-SB-168-091014 | | 134-SB-169-090914 | | 134-SB-170-091014 | | 134-SB-171-091114 | | 134-SB-172-091114 | | 134-SB-173-091114 | | 134-SB-174-091114 | | 134-SB-175-091114 | | 134-SB-177-120214 | |
| Lab Sample ID | | | | JB72879-1 | | JB74373-1 | | JB74373-2 | | JB76165-2/2R | | JB76165-3/3R | | JB76165-5 | | JB76165-6 | | JB76165-7 | | JB76165-8/8T | | JB76292-1/1R | | JB76292-2/2R | | JB76292-3/3R | | JB76292-4 | | JB76292-5/5R | | JB83002-1/1R | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 07/30/2014 | | 08/19/2014 | | 08/19/2014 | | 08/20/2014 | | 08/21/2014 | | 09/09/2014 | | 09/10/2014 | | 09/09/2014 | | 09/10/2014 | | 09/11/2014 | | 09/11/2014 | | 09/11/2014 | | 09/11/2014 | | 09/11/2014 | | 12/02/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **848** | J | **230** | | **198** | | **57.0** | J | 6.2 | J | **328** | | **383** | | **80.0** | | 19.6 | J | 8.6 | | **1220** | | **276** | | **177** | J | 2.2 | | 2.6 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator



Prepared by: DP 05/24/2016

Reviewed by: NAW 04/21/2017

# TABLE 6B

## Post-Excavation Anomalous Soil Sample Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Location ID | | | | 073-SB-079 | | 073-SB-080 | | 073-SB-082 | | 125-SB-306 | | 140-SB-107 | | 140-SB-108 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Client Sample ID | | | | 073-SB-079-051514 | | 073-SB-080-051514 | | 073SB-082-0203 | | 125-SB-306-032614 | | 140-SB-107-091814 | | 140-SB-108-100814 | |
| Lab Sample ID | | NJ 2012 MOST | NJ 2013 IGW | JB67189-1/1R | | JB67189-2/2R | | JB69168-2U/V | | JB63130-1 | | JB76993-1 | | JB78672-1 | |
| Date Sampled | | STRINGENT SRS | SOIL | 05/15/2014 | | 05/15/2014 | | 06/12/2014 | | 03/26/2014 | | 09/18/2014 | | 10/08/2014 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | 4.7 | | **42.3** | | 7.9 | J | 2.2 | | 0.69 | UJ | 6.5 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 6C

## Site 073 Deferred Area Soil Sample Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Location ID | | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | 073-SB-101 | | 073-SB-101 | | 073-SB-101 | | 073-SB-101 | | 073-SB-101 | | 073-SB-103 | | 073-SB-103 | | 073-SB-103 | | 073-SB-103 | | 073-SB-103 | | 073-SB-103 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Client Sample ID | | | | 073-SB-101-0204 | | 073-SB-101-0507 | | 073-SB-101-0709 | | 073-SB-101-1113 | | 073-SB-101-1315 | | 073-SB-101-1517 | | 073-SB-103-0405 | | 073-SB-103-0607 | | 073-SB-103-0809 | | 073-SB-103-1011 | | 073-SB-103-1213 | | 073-SB-103-1415 | |
| Lab Sample ID | | | | JB66204-1/1R | | JB66204-2 | | JB66204-3 | | JB66204-4/4R | | JB66204-5/5R | | JB66204-6 | | JC19974-3 | | JC19974-4 | | JC19974-5 | | JC19974-6 | | JC19974-7 | | JC19974-8 | |
| Date Sampled | | | | 05/05/2014 | | 05/05/2014 | | 05/05/2014 | | 05/05/2014 | | 05/05/2014 | | 05/05/2014 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **705** | | 0.53 | U | 4.5 | | **21.1** | | 4.1 | | 0.54 | U | 10 | J | **71.6** | | **1490** | | **523** | | **35.0** | | **23.6** | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 6C

## Site 073 Deferred Area Soil Sample Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Location ID | | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | 073-SB-103 | | 073-SB-103 | | 073-SB-103 | | 073-SB-104 | | 073-SB-104 | | 073-SB-104 | | 073-SB-104 | | 073-SB-104 | | 073-SB-104 | | 073-SB-104 | | 073-SB-104 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Client Sample ID | | | | 073-SB-103-1617 | | 073-SB-103-1819 | | 073-SB-103-2021 | | 073-SB-104-0405 | | 073-SB-104-0607 | | 073-SB-104-0809 | | 073-SB-104-1011 | | 073-SB-104-1213 | | 073-SB-104-1415 | | 073-SB-104-1617 | | 073-SB-104-1819 | | 073-SB-104-2021 | |
| Lab Sample ID | | | | JC19974-9 | | JC19974-10 | | JC19974-11/11T | | JC19974-13 | | JC19974-14/14T | | JC19974-15 | | JC19974-16 | | JC19974-17 | | JC19974-18 | | JC19974-19 | | JC19974-20 | | JC19974-21 | |
| Date Sampled | | | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **136** | | **35.4** | | **76** | J | 2.1 | | **362** | J | **4710** | | **118** | | **144** | | **112** | | **25.7** | | **54.6** | | **87.3** | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 6C

## Site 073 Deferred Area Soil Sample Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Location ID | | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | 073-SB-104 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | | 073-SB-105 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Client Sample ID | | | | 073-SB-104-2223 | | 073-SB-105-0405 | | 073-SB-105-0607 | | 073-SB-105-0809 | | 073-SB-105-1011 | | 073-SB-105-1213 | | 073-SB-105-1415 | | 073-SB-105-1617 | | 073-SB-105-1819 | | 073-SB-105-2021 | | 073-SB-105-2223 | |
| Lab Sample ID | | | | JC19974-22/22T | | JC19974-24/24T | | JC19974-25 | | JC19974-26 | | JC19974-27 | | JC19974-28 | | JC19974-29 | | JC19974-30 | | JC19974-31 | | JC19974-32 | | JC19974-33/33T | |
| Date Sampled | | | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | | 05/09/2016 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **67.4** | **J** | 3 | J | **59.7** | **J** | 0.54 | UJ | **52.6** | **J** | **36.7** | **J** | **69.4** | **J** | 16.3 | J | **125** | **J** | **264** | **J** | **142** | **J** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 6C

## Site 073 Deferred Area Soil Sample Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Location ID | | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | | 073-SB-106 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Client Sample ID | | | | 073-SB-106-0405 | | 073-SB-106-0607 | | 073-SB-106-0809 | | 073-SB-106-1011 | | 073-SB-106-1213 | | 073-SB-106-1415 | | 073-SB-106-1617 | | 073-SB-106-1819 | | 073-SB-106-2021 | | 073-SB-106-2223 | |
| Lab Sample ID | | | | JC19974-35/35R | | JC19974-36/36R | | JC19974-37/37T | | JC19974-38 | | JC19974-39 | | JC19974-40 | | JC19974-41 | | JC19974-42 | | JC19974-43 | | JC19974-44 | |
| Date Sampled | | | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | | 05/10/2016 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | 0.44 | UJ | 14.9 | J | **36.7** | **J** | 15 | J | **76.1** | **J** | **50.3** | **J** | **57.7** | **J** | **59.3** | **J** | **23** | **J** | **88.7** | **J** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 6D

## Site 125- Post Ex Soil Results

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | 125-SB-307-042916 | | 125-SB-308-0304 | | 125-SB-309-0203 | | 125-SB-310-0304 | | 125-SB-311-0203 | | 125-SB-312-0304 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JC19868-1 | | JC21399-1 | | JC21399-2 | | JC21399-3 | | JC21399-4/4R | | JC21399-5 | |
| Date Sampled | | | 04/29/2016 | | 06/02/2016 | | 06/02/2016 | | 06/02/2016 | | 06/02/2016 | | 06/02/2016 | |
| Sample Purpose | | NJ 2012 MOST | REG | | REG | | REG | | REG | | REG | | REG | |
| Parameter Name | Units | STRINGENT SRS | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | **10100** | | 0.55 | U | 0.66 | | 0.52 | U | 2.3 | | 1.9 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 06/22/2016

Reviewed by: JLD 06/22/2016

# TABLE 7A
## Concrete Sample Results –VOCs
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C01-091113 | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | | 087-WC-C04-091113 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-1 | | JB47199-10 | | JB47199-11 | | JB47199-12 | | JB47199-13 | | JB47199-14 | | JB47199-15 | | JB47199-16 | | JB47199-17 | | JB47199-18 | | JB47199-2 | | JB47199-3 | | JB47199-4 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **VOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | 290 | 0.3 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,1,2,2-TETRACHLOROETHANE | 1 | 0.007 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,1,2-TRICHLOROETHANE | 2 | 0.02 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,1-DICHLOROETHANE | 8 | 0.2 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,1-DICHLOROETHENE | 11 | 0.008 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,2,3-TRICHLOROBENZENE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,2,4-TRICHLOROBENZENE | 73 | 0.7 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | 0.08 | 0.005 | *0.0098* | *U* | *0.01* | *U* | *0.01* | *U* | *0.0095* | *U* | *0.0094* | *U* | *0.01* | *U* | *0.01* | *U* | *0.01* | *U* | *0.01* | *U* | *0.011* | *U* | *0.011* | *U* | *0.0087* | *U* | *0.0096* | *U* |
| 1,2-DIBROMOETHANE | 0.008 | 0.005 | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| 1,2-DICHLOROBENZENE | 5300 | 17 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,2-DICHLOROETHANE | 0.9 | 0.005 | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| 1,2-DICHLOROPROPANE | 2 | 0.005 | 0.0049 | U | *0.0052* | *U* | *0.0052* | *U* | 0.0047 | U | 0.0047 | U | *0.0051* | *U* | *0.0051* | *U* | 0.005 | U | *0.0052* | *U* | *0.0054* | *U* | *0.0056* | *U* | 0.0043 | U | 0.0048 | U |
| 1,3-DICHLOROBENZENE | 5300 | 19 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 1,4-DICHLOROBENZENE | 5 | 2 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 2-BUTANONE | 3100 | 0.9 | 0.0098 | U | 0.01 | U | 0.01 | U | 0.0095 | U | 0.0094 | U | 0.0192 | | 0.01 | U | 0.0185 | | 0.0148 | | 0.0223 | | 0.0046 | J | 0.0087 | U | 0.0096 | U |
| 2-HEXANONE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| 4-METHYL-2-PENTANONE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| ACETONE | 70000 | 19 | 0.0154 | | 0.0133 | | 0.01 | U | 0.0302 | | 0.0684 | | 0.11 | | 0.105 | | 0.118 | | 0.109 | | 0.183 | | 0.0451 | | 0.0079 | J | 0.0096 | U |
| BENZENE | 2 | 0.005 | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| BROMOCHLOROMETHANE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| BROMODICHLOROMETHANE | 1 | 0.005 | 0.0049 | U | *0.0052* | *U* | *0.0052* | *U* | 0.0047 | U | 0.0047 | U | *0.0051* | *U* | *0.0051* | *U* | 0.005 | U | *0.0052* | *U* | *0.0054* | *U* | *0.0056* | *U* | 0.0043 | U | 0.0048 | U |
| BROMOFORM | 81 | 0.03 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| BROMOMETHANE | 25 | 0.04 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CARBON DISULFIDE | 7800 | 6 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CARBON TETRACHLORIDE | 0.6 | 0.005 | 0.0049 | U | *0.0052* | *U* | *0.0052* | *U* | 0.0047 | U | 0.0047 | U | *0.0051* | *U* | *0.0051* | *U* | 0.005 | U | *0.0052* | *U* | *0.0054* | *U* | *0.0056* | *U* | 0.0043 | U | 0.0048 | U |
| CHLOROBENZENE | 510 | 0.6 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CHLOROETHANE | 220 | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CHLOROFORM | 0.6 | 0.4 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CHLOROMETHANE | 4 | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CIS-1,2-DICHLOROETHENE | 230 | 0.3 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.00032 | J | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CIS-1,3-DICHLOROPROPENE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| CYCLOHEXANE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| DIBROMOCHLOROMETHANE | 3 | 0.005 | 0.0049 | U | *0.0052* | *U* | *0.0052* | *U* | 0.0047 | U | 0.0047 | U | *0.0051* | *U* | *0.0051* | *U* | 0.005 | U | *0.0052* | *U* | *0.0054* | *U* | *0.0056* | *U* | 0.0043 | U | 0.0048 | U |
| DICHLORODIFLUOROMETHANE | 490 | 39 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| ETHYLBENZENE | 7800 | 13 | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| ISOPROPYLBENZENE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| METHYL ACETATE | 78000 | 22 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| METHYL TERT-BUTYL ETHER | 110 | 0.2 | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| METHYLCYCLOHEXANE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| METHYLENE CHLORIDE | 34 | 0.01 | 0.0012 | J | **0.0122** | | 0.0053 | | 0.0035 | J | 0.0038 | J | 0.0021 | J | 0.0021 | J | 0.002 | J | 0.0033 | J | 0.0023 | J | 0.0017 | J | 0.0016 | J | 0.0026 | J |
| O-XYLENE | NC | NC | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| STYRENE | 90 | 3 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| TETRACHLOROETHENE | 2 | 0.005 | 0.0049 | U | *0.0052* | *U* | *0.0052* | *U* | 0.0047 | U | 0.0047 | U | *0.0051* | *U* | *0.0051* | *U* | 0.005 | U | *0.0052* | *U* | *0.0054* | *U* | *0.0056* | *U* | 0.0043 | U | 0.0048 | U |
| TOLUENE | 6300 | 7 | 0.00098 | U | 0.001 | U | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.00036 | J | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| TRANS-1,2-DICHLOROETHENE | 300 | 0.6 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| TRANS-1,3-DICHLOROPROPENE | NC | NC | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| TRICHLOROETHENE | 7 | 0.01 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| TRICHLOROFLUOROMETHANE | 23000 | 34 | 0.0049 | U | 0.0052 | U | 0.0052 | U | 0.0047 | U | 0.0047 | U | 0.0051 | U | 0.0051 | U | 0.005 | U | 0.0052 | U | 0.0054 | U | 0.0056 | U | 0.0043 | U | 0.0048 | U |
| VINYL CHLORIDE | 0.7 | 0.005 | 0.0049 | U | *0.0052* | *U* | *0.0052* | *U* | 0.0047 | U | 0.0047 | U | *0.0051* | *U* | *0.0051* | *U* | 0.005 | U | *0.0052* | *U* | *0.0054* | *U* | *0.0056* | *U* | 0.0043 | U | 0.0048 | U |
| XYLENES, TOTAL | 12000 | 19 | 0.00098 | U | 0.00072 | J | 0.001 | U | 0.00095 | U | 0.00094 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.001 | U | 0.00061 | J | 0.0011 | U | 0.00087 | U | 0.00096 | U |
| TOTAL TICS, ALKANES | -- | -- | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0.17 | J | 0.14 | J | 0 | | 0 | | 0 | | 0 | | 0 | |
| TOTAL TICS, VOLATILES | -- | -- | 0 | | 0 | | 0 | | 0 | | 0.011 | J | 0.027 | J | 0.024 | J | 0.0081 | J | 0.0086 | J | 0.0314 | J | 0 | | 0 | | 0 | |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].
NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]
NC: No criterion established
**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**
**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**
*Italicized values not detected; reporting limit exceeds criteria*
Depths reported in feet below ground surface
J: Estimated concentration
R or N: Rejected or negated by laboratory or data validator
U: Not detected above method detection limit
Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016
Reviewed by: JLD 05/24/2016

# TABLE 7A
## Concrete Sample Results –VOCs
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C01-091713 | | 124-WC-C02-091713 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-5 | | JB47199-6 | | JB47199-7 | | JB47199-8 | | JB47199-9 | | JB47734-1 | | JB47734-2 | | JB59616-1 | | JB59616-2 | | JB59616-3 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 09/17/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | |
| **VOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | 290 | 0.3 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,1,2,2-TETRACHLOROETHANE | 1 | 0.007 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,1,2-TRICHLOROETHANE | 2 | 0.02 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,1-DICHLOROETHANE | 8 | 0.2 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,1-DICHLOROETHENE | 11 | 0.008 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,2,3-TRICHLOROBENZENE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,2,4-TRICHLOROBENZENE | 73 | 0.7 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | 0.08 | 0.005 | *0.0096* | *U* | *0.0098* | *U* | *0.0095* | *U* | *0.01* | *U* | *0.0095* | *U* | *0.0092* | *U* | *0.011* | *U* | *0.01* | *UJ* | *0.0096* | *UJ* | *0.011* | *U* |
| 1,2-DIBROMOETHANE | 0.008 | 0.005 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| 1,2-DICHLOROBENZENE | 5300 | 17 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,2-DICHLOROETHANE | 0.9 | 0.005 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| 1,2-DICHLOROPROPANE | 2 | 0.005 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | *0.0056* | *U* | 0.005 | UJ | 0.0048 | UJ | *0.0053* | *U* |
| 1,3-DICHLOROBENZENE | 5300 | 19 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 1,4-DICHLOROBENZENE | 5 | 2 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 2-BUTANONE | 3100 | 0.9 | 0.0096 | U | 0.0098 | U | 0.0095 | U | 0.01 | U | 0.0095 | U | 0.0092 | U | 0.011 | U | 0.01 | R | 0.0096 | R | 0.011 | U |
| 2-HEXANONE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| 4-METHYL-2-PENTANONE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| ACETONE | 70000 | 19 | 0.0096 | U | 0.0098 | U | 0.0095 | U | 0.01 | U | 0.0095 | U | 0.0092 | U | 0.0158 | | 0.0143 | R | 0.0174 | R | 0.0207 | |
| BENZENE | 2 | 0.005 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| BROMOCHLOROMETHANE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| BROMODICHLOROMETHANE | 1 | 0.005 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | *0.0056* | *U* | 0.005 | UJ | 0.0048 | UJ | *0.0053* | *U* |
| BROMOFORM | 81 | 0.03 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| BROMOMETHANE | 25 | 0.04 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CARBON DISULFIDE | 7800 | 6 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.00085 | J | 0.0012 | J | 0.0053 | U |
| CARBON TETRACHLORIDE | 0.6 | 0.005 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | *0.0056* | *U* | 0.005 | UJ | 0.0048 | UJ | *0.0053* | *U* |
| CHLOROBENZENE | 510 | 0.6 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CHLOROETHANE | 220 | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CHLOROFORM | 0.6 | 0.4 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CHLOROMETHANE | 4 | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CIS-1,2-DICHLOROETHENE | 230 | 0.3 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CIS-1,3-DICHLOROPROPENE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| CYCLOHEXANE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| DIBROMOCHLOROMETHANE | 3 | 0.005 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | *0.0056* | *U* | 0.005 | UJ | 0.0048 | UJ | *0.0053* | *U* |
| DICHLORODIFLUOROMETHANE | 490 | 39 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| ETHYLBENZENE | 7800 | 13 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| ISOPROPYLBENZENE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| METHYL ACETATE | 78000 | 22 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| METHYL TERT-BUTYL ETHER | 110 | 0.2 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| METHYLCYCLOHEXANE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| METHYLENE CHLORIDE | 34 | 0.01 | 0.0086 | | 0.0056 | | 0.0058 | | 0.005 | U | **0.0126** | | 0.0024 | J | 0.003 | J | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| O-XYLENE | NC | NC | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| STYRENE | 90 | 3 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| TETRACHLOROETHENE | 2 | 0.005 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | *0.0056* | *U* | 0.005 | UJ | 0.0048 | UJ | *0.0053* | *U* |
| TOLUENE | 6300 | 7 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00096 | UJ | 0.0011 | U |
| TRANS-1,2-DICHLOROETHENE | 300 | 0.6 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| TRANS-1,3-DICHLOROPROPENE | NC | NC | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| TRICHLOROETHENE | 7 | 0.01 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| TRICHLOROFLUOROMETHANE | 23000 | 34 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.005 | UJ | 0.0048 | UJ | 0.0053 | U |
| VINYL CHLORIDE | 0.7 | 0.005 | 0.0048 | U | 0.0049 | U | 0.0047 | U | 0.005 | U | 0.0047 | U | 0.0046 | U | *0.0056* | *U* | 0.005 | UJ | 0.0048 | UJ | *0.0053* | *U* |
| XYLENES, TOTAL | 12000 | 19 | 0.00096 | U | 0.00098 | U | 0.00095 | U | 0.001 | U | 0.00095 | U | 0.00092 | U | 0.0011 | U | 0.001 | UJ | 0.00038 | J | 0.0011 | U |
| TOTAL TICS, ALKANES | -- | -- | 0 | | 0 | | 0 | | 0 | | 0.01 | J | 0 | | 0 | | 0 | J | 0.02 | J | 0 | |
| TOTAL TICS, VOLATILES | -- | -- | 0 | | 0 | | 0 | | 0 | | 0.0049 | J | 0 | | 0 | | 0 | J | 0.3219 | J | 0 | |

| | | | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C14-021114 | | 124-WC-C15-040414 | | 124-WC-C16-040414 | | | | | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB59616-4 | | JB63854-1 | | JB63854-2 | | | | | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 02/12/2014 | | 04/04/2014 | | 04/04/2014 | | | | | |
| **VOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | | | | |
| 1,1,1-TRICHLOROETHANE | 290 | 0.3 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,1,2,2-TETRACHLOROETHANE | 1 | 0.007 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,1,2-TRICHLOROETHANE | 2 | 0.02 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,1-DICHLOROETHANE | 8 | 0.2 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,1-DICHLOROETHENE | 11 | 0.008 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,2,3-TRICHLOROBENZENE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,2,4-TRICHLOROBENZENE | 73 | 0.7 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,2-DIBROMO-3-CHLOROPROPANE | 0.08 | 0.005 | *0.01* | *U* | *0.0094* | *UJ* | *0.0082* | *U* | | | | |
| 1,2-DIBROMOETHANE | 0.008 | 0.005 | 0.001 | U | 0.00094 | UJ | 0.00082 | U | | | | |
| 1,2-DICHLOROBENZENE | 5300 | 17 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,2-DICHLOROETHANE | 0.9 | 0.005 | 0.001 | U | 0.00094 | UJ | 0.00082 | U | | | | |
| 1,2-DICHLOROPROPANE | 2 | 0.005 | *0.0052* | *U* | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,3-DICHLOROBENZENE | 5300 | 19 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 1,4-DICHLOROBENZENE | 5 | 2 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 2-BUTANONE | 3100 | 0.9 | 0.01 | U | 0.0094 | R | 0.0082 | U | | | | |
| 2-HEXANONE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| 4-METHYL-2-PENTANONE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| ACETONE | 70000 | 19 | 0.0083 | J | 0.0413 | R | 0.014 | | | | | |
| BENZENE | 2 | 0.005 | 0.001 | U | 0.00094 | UJ | 0.00082 | U | | | | |
| BROMOCHLOROMETHANE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| BROMODICHLOROMETHANE | 1 | 0.005 | *0.0052* | *U* | 0.0047 | UJ | 0.0041 | U | | | | |
| BROMOFORM | 81 | 0.03 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| BROMOMETHANE | 25 | 0.04 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CARBON DISULFIDE | 7800 | 6 | 0.0052 | U | 0.0047 | UJ | 0.0029 | J | | | | |
| CARBON TETRACHLORIDE | 0.6 | 0.005 | *0.0052* | *U* | 0.0047 | UJ | 0.0041 | U | | | | |
| CHLOROBENZENE | 510 | 0.6 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CHLOROETHANE | 220 | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CHLOROFORM | 0.6 | 0.4 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CHLOROMETHANE | 4 | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CIS-1,2-DICHLOROETHENE | 230 | 0.3 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CIS-1,3-DICHLOROPROPENE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| CYCLOHEXANE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| DIBROMOCHLOROMETHANE | 3 | 0.005 | *0.0052* | *U* | 0.0047 | UJ | 0.0041 | U | | | | |
| DICHLORODIFLUOROMETHANE | 490 | 39 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| ETHYLBENZENE | 7800 | 13 | 0.001 | U | 0.0019 | J | 0.00082 | U | | | | |
| ISOPROPYLBENZENE | NC | NC | 0.0052 | U | 0.0021 | J | 0.0041 | U | | | | |
| METHYL ACETATE | 78000 | 22 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| METHYL TERT-BUTYL ETHER | 110 | 0.2 | 0.001 | U | 0.00094 | UJ | 0.00082 | U | | | | |
| METHYLCYCLOHEXANE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| METHYLENE CHLORIDE | 34 | 0.01 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| O-XYLENE | NC | NC | 0.001 | U | 0.0023 | J | 0.00082 | U | | | | |
| STYRENE | 90 | 3 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| TETRACHLOROETHENE | 2 | 0.005 | *0.0052* | *U* | 0.0047 | UJ | 0.0041 | U | | | | |
| TOLUENE | 6300 | 7 | 0.001 | U | 0.00032 | J | 0.00082 | U | | | | |
| TRANS-1,2-DICHLOROETHENE | 300 | 0.6 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| TRANS-1,3-DICHLOROPROPENE | NC | NC | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| TRICHLOROETHENE | 7 | 0.01 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| TRICHLOROFLUOROMETHANE | 23000 | 34 | 0.0052 | U | 0.0047 | UJ | 0.0041 | U | | | | |
| VINYL CHLORIDE | 0.7 | 0.005 | *0.0052* | *U* | 0.0047 | UJ | 0.0041 | U | | | | |
| XYLENES, TOTAL | 12000 | 19 | 0.001 | U | 0.0059 | J | 0.00082 | U | | | | |
| TOTAL TICS, ALKANES | -- | -- | 0 | | 0.022 | J | 5.23 | J | | | | |
| TOTAL TICS, VOLATILES | -- | -- | 0 | | 0.445 | J | 0.0194 | J | | | | |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standar
NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.
NC: No criterion established
**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**
**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**
*Italicized values not detected; reporting limit exceeds criteria*
Depths reported in feet below ground surface
J: Estimated concentration
R or N: Rejected or negated by laboratory or data validator
U: Not detected above method detection limit
Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016
Reviewed by: JLD 05/24/2016

# TABLE 7A
## Concrete Sample Results –VOCs
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C17-041114 | | 124-WC-C18-041114 | | 124-WC-C19-041114 | | 124-WC-C20-041114 | | 124-WC-C21-050914 | | 124-WC-C22-053014 | | 124-WC-C23-053014 | | 124-WC-C24-053014 | | 124-WC-C25-061614 | | 124-WC-C26-072914 | | 124-WC-C27-072914 | | 124-WC-C28-090514 | | 124-WC-C29-092314 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB64504-1 | | JB64504-2 | | JB64504-3 | | JB64504-4 | | JB66694-1 | | JB68105-1 | | JB68105-2 | | JB68105-3 | | JB69461-1 | | JB72778-1 | | JB72778-2 | | JB75850-1 | | JB77376-1 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 05/09/2014 | | 05/30/2014 | | 05/30/2014 | | 05/30/2014 | | 06/16/2014 | | 07/29/2014 | | 07/29/2014 | | 09/05/2014 | | 09/23/2014 | |
| **VOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | 290 | 0.3 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| 1,1,2,2-TETRACHLOROETHANE | 1 | 0.007 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| 1,1,2-TRICHLOROETHANE | 2 | 0.02 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| 1,1-DICHLOROETHANE | 8 | 0.2 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 1,1-DICHLOROETHENE | 11 | 0.008 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 1,2,3-TRICHLOROBENZENE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| 1,2,4-TRICHLOROBENZENE | 73 | 0.7 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | 0.08 | 0.005 | *0.0096* | *UJ* | *0.0085* | *U* | *0.0075* | *U* | *0.0085* | *U* | *0.0097* | *U* | *0.0098* | *UJ* | *0.0098* | *U* | *0.0097* | *U* | 0.005 | UJ | *0.0058* | *U* | *0.0055* | *U* | 0.0045 | U | 0.0048 | U |
| 1,2-DIBROMOETHANE | 0.008 | 0.005 | 0.00096 | UJ | 0.00085 | U | 0.00075 | U | 0.00085 | U | 0.00097 | U | 0.00098 | UJ | 0.00098 | U | 0.00097 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 1,2-DICHLOROBENZENE | 5300 | 17 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 1,2-DICHLOROETHANE | 0.9 | 0.005 | 0.00096 | UJ | 0.00085 | U | 0.00075 | U | 0.00085 | U | 0.00097 | U | 0.00098 | UJ | 0.00098 | U | 0.00097 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 1,2-DICHLOROPROPANE | 2 | 0.005 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| 1,3-DICHLOROBENZENE | 5300 | 19 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 1,4-DICHLOROBENZENE | 5 | 2 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| 2-BUTANONE | 3100 | 0.9 | 0.0096 | R | 0.0089 | | 0.0085 | | 0.0085 | U | 0.0097 | R | 0.0098 | R | 0.0098 | U | 0.0097 | U | 0.0099 | R | 0.012 | U | 0.011 | U | 0.0091 | U | 0.0096 | U |
| 2-HEXANONE | NC | NC | 0.0048 | UJ | 0.0043 | | 0.0037 | J | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| 4-METHYL-2-PENTANONE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0019 | J | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| ACETONE | 70000 | 19 | 0.0077 | J | 0.0517 | | 0.0698 | | 0.0273 | | 0.0076 | J | 0.008 | J | 0.0141 | | 0.0189 | | 0.0058 | J | 0.0065 | J | 0.005 | J | 0.0091 | U | 0.033 | |
| BENZENE | 2 | 0.005 | 0.00096 | UJ | 0.00085 | U | 0.00075 | U | 0.00085 | U | 0.00097 | U | 0.00022 | J | 0.00098 | U | 0.00097 | U | 0.0005 | UJ | 0.00058 | U | 0.00055 | U | 0.00045 | U | 0.00048 | U |
| BROMOCHLOROMETHANE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| BROMODICHLOROMETHANE | 1 | 0.005 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| BROMOFORM | 81 | 0.03 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | UJ | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| BROMOMETHANE | 25 | 0.04 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| CARBON DISULFIDE | 7800 | 6 | 0.0048 | UJ | 0.0022 | J | 0.0013 | J | 0.0012 | J | 0.0049 | U | 0.0049 | UJ | 0.00053 | J | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| CARBON TETRACHLORIDE | 0.6 | 0.005 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| CHLOROBENZENE | 510 | 0.6 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| CHLOROETHANE | 220 | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| CHLOROFORM | 0.6 | 0.4 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| CHLOROMETHANE | 4 | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| CIS-1,2-DICHLOROETHENE | 230 | 0.3 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| CIS-1,3-DICHLOROPROPENE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| CYCLOHEXANE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| DIBROMOCHLOROMETHANE | 3 | 0.005 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| DICHLORODIFLUOROMETHANE | 490 | 39 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | UJ | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| ETHYLBENZENE | 7800 | 13 | 0.001 | J | 0.0016 | | 0.00069 | J | 0.00077 | J | 0.00097 | U | 0.00098 | UJ | 0.00098 | U | 0.0013 | | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| ISOPROPYLBENZENE | NC | NC | 0.0048 | UJ | 0.0017 | J | 0.00056 | J | 0.0012 | J | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| METHYL ACETATE | 78000 | 22 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| METHYL TERT-BUTYL ETHER | 110 | 0.2 | 0.00096 | UJ | 0.00085 | U | 0.00075 | U | 0.00085 | U | 0.00097 | U | 0.00098 | UJ | 0.00098 | U | 0.00097 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| METHYLCYCLOHEXANE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| METHYLENE CHLORIDE | 34 | 0.01 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0018 | J | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0017 | J | 0.0016 | J |
| O-XYLENE | NC | NC | 0.001 | J | 0.0053 | | 0.00083 | | 0.00046 | J | 0.00097 | U | 0.00098 | UJ | 0.00098 | U | 0.0013 | | 0.00099 | UJ | 0.0012 | U | 0.00039 | J | 0.00091 | U | 0.00096 | U |
| STYRENE | 90 | 3 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| TETRACHLOROETHENE | 2 | 0.005 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| TOLUENE | 6300 | 7 | 0.00024 | J | 0.00063 | J | 0.00074 | J | 0.00037 | J | 0.00097 | U | 0.00023 | J | 0.00098 | U | 0.00097 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| TRANS-1,2-DICHLOROETHENE | 300 | 0.6 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| TRANS-1,3-DICHLOROPROPENE | NC | NC | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| TRICHLOROETHENE | 7 | 0.01 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.00099 | UJ | 0.0012 | U | 0.0011 | U | 0.00091 | U | 0.00096 | U |
| TRICHLOROFLUOROMETHANE | 23000 | 34 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | UJ | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.005 | UJ | 0.0058 | U | 0.0055 | U | 0.0045 | U | 0.0048 | U |
| VINYL CHLORIDE | 0.7 | 0.005 | 0.0048 | UJ | 0.0043 | U | 0.0038 | U | 0.0042 | U | 0.0049 | U | 0.0049 | UJ | 0.0049 | U | 0.0048 | U | 0.002 | UJ | 0.0023 | U | 0.0022 | U | 0.0018 | U | 0.0019 | U |
| XYLENES, TOTAL | 12000 | 19 | 0.0057 | J | 0.0287 | | 0.0034 | | 0.0023 | | 0.00097 | U | 0.00098 | UJ | 0.00098 | U | 0.0057 | | 0.00099 | UJ | 0.0012 | U | 0.00039 | J | 0.00091 | U | 0.00096 | U |
| TOTAL TICS, ALKANES | -- | -- | 0 | J | 0 | | 0.082 | J | 0 | | 0 | | 0 | J | 0 | | 0 | | 0 | J | 0 | | 0 | | 0 | | 0 | |
| TOTAL TICS, VOLATILES | -- | -- | 0.1213 | J | 0.0726 | J | 0.0949 | J | 0.0069 | J | 0 | | 0 | J | 0 | | 0.03 | J | 0 | J | 0 | | 0.6571 | J | 0 | | 0 | |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standar
NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.
NC: No criterion established
**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**
**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**
*Italicized values not detected; reporting limit exceeds criteria*
Depths reported in feet below ground surface
J: Estimated concentration
R or N: Rejected or negated by laboratory or data validator
U: Not detected above method detection limit
Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016
Reviewed by: JLD 05/24/2016

# TABLE 7A

## Concrete Sample Results –VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | 124-WC-C32-100214 | | 124-WC-C33-100214 | | 124-WC-C34-100214 | | 124-WC-C35-121914 | | 124-WC-C36-121914 | | 124-WC-C37-121914 | | 124-WC-C38-012916 | | 124-WC-C39-012916 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB77376-2 | | JB77376-3 | | JB78325-1 | | JB78325-2 | | JB78325-3 | | JB84701-1 | | JB84701-2 | | JB85005-1 | | JC13390-1 | | JC13390-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/23/2014 | | 09/23/2014 | | 10/02/2014 | | 10/02/2014 | | 10/02/2014 | | 12/19/2014 | | 12/19/2014 | | 12/24/2014 | | 01/29/2016 | | 01/29/2016 | |
| **VOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | 290 | 0.3 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| 1,1,2,2-TETRACHLOROETHANE | 1 | 0.007 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | NC | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| 1,1,2-TRICHLOROETHANE | 2 | 0.02 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| 1,1-DICHLOROETHANE | 8 | 0.2 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 1,1-DICHLOROETHENE | 11 | 0.008 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 1,2,3-TRICHLOROBENZENE | NC | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| 1,2,4-TRICHLOROBENZENE | 73 | 0.7 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | 0.08 | 0.005 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0022 | U | 0.0022 | U |
| 1,2-DIBROMOETHANE | 0.008 | 0.005 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 1,2-DICHLOROBENZENE | 5300 | 17 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 1,2-DICHLOROETHANE | 0.9 | 0.005 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 1,2-DICHLOROPROPANE | 2 | 0.005 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| 1,3-DICHLOROBENZENE | 5300 | 19 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 1,4-DICHLOROBENZENE | 5 | 2 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| 2-BUTANONE | 3100 | 0.9 | 0.0091 | U | 0.009 | U | 0.0096 | U | 0.0096 | U | 0.0097 | U | 0.0096 | U | 0.0089 | U | 0.0098 | U | 0.011 | U | 0.011 | U |
| 2-HEXANONE | NC | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| 4-METHYL-2-PENTANONE | NC | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| ACETONE | 70000 | 19 | 0.0362 | | 0.023 | | 0.0096 | U | 0.0079 | J | 0.0049 | J | 0.0096 | U | 0.0089 | U | 0.0155 | | 0.0062 | J | 0.0119 | |
| BENZENE | 2 | 0.005 | 0.00046 | U | 0.00045 | U | 0.00048 | U | 0.00048 | U | 0.00049 | U | 0.00048 | U | 0.00044 | U | 0.00049 | U | 0.00054 | U | 0.00055 | U |
| BROMOCHLOROMETHANE | NC | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| BROMODICHLOROMETHANE | 1 | 0.005 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| BROMOFORM | 81 | 0.03 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| BROMOMETHANE | 25 | 0.04 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| CARBON DISULFIDE | 7800 | 6 | 0.0018 | U | 0.0027 | | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.0019 | J | 0.0024 | | 0.00069 | J |
| CARBON TETRACHLORIDE | 0.6 | 0.005 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| CHLOROBENZENE | 510 | 0.6 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| CHLOROETHANE | 220 | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| CHLOROFORM | 0.6 | 0.4 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| CHLOROMETHANE | 4 | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| CIS-1,2-DICHLOROETHENE | 230 | 0.3 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| CIS-1,3-DICHLOROPROPENE | NC | NC | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| CYCLOHEXANE | NC | NC | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| DIBROMOCHLOROMETHANE | 3 | 0.005 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| DICHLORODIFLUOROMETHANE | 490 | 39 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| ETHYLBENZENE | 7800 | 13 | 0.00071 | J | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| ISOPROPYLBENZENE | NC | NC | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0022 | U | 0.0022 | U |
| METHYL ACETATE | 78000 | 22 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| METHYL TERT-BUTYL ETHER | 110 | 0.2 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| METHYLCYCLOHEXANE | NC | NC | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.0011 | J | 0.0022 | U | 0.0022 | U |
| METHYLENE CHLORIDE | 34 | 0.01 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0033 | J | 0.002 | J | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| O-XYLENE | NC | NC | 0.0005 | J | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.00035 | J | 0.0011 | U |
| STYRENE | 90 | 3 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| TETRACHLOROETHENE | 2 | 0.005 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0022 | U | 0.0022 | U |
| TOLUENE | 6300 | 7 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| TRANS-1,2-DICHLOROETHENE | 300 | 0.6 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| TRANS-1,3-DICHLOROPROPENE | NC | NC | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| TRICHLOROETHENE | 7 | 0.01 | 0.00091 | U | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0011 | U | 0.0011 | U |
| TRICHLOROFLUOROMETHANE | 23000 | 34 | 0.0046 | U | 0.0045 | U | 0.0048 | U | 0.0048 | U | 0.0049 | U | 0.0048 | U | 0.0044 | U | 0.0049 | U | 0.0054 | U | 0.0055 | U |
| VINYL CHLORIDE | 0.7 | 0.005 | 0.0018 | U | 0.0018 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0019 | U | 0.0018 | U | 0.002 | U | 0.0022 | U | 0.0022 | U |
| XYLENES, TOTAL | 12000 | 19 | 0.0025 | | 0.0009 | U | 0.00096 | U | 0.00096 | U | 0.00097 | U | 0.00096 | U | 0.00089 | U | 0.00098 | U | 0.0012 | | 0.0011 | U |
| TOTAL TICS, ALKANES | -- | -- | 0 | | 0 | | 0 | | 0.207 | J | 0 | | 0 | | 0 | | 1.037 | J | 0.083 | J | 0.1226 | J |
| TOTAL TICS, VOLATILES | -- | -- | 0 | | 0 | | 1.303 | J | 0.405 | J | 0 | | 0 | | 0 | | 0.22 | J | 0.375 | J | 0.0716 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standar

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016

Reviewed by: JLD 05/24/2016

# TABLE 7B

## Concrete Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C01-091113 | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C02-091113 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-1 | | JB47199-10 | | JB47199-11 | | JB47199-12 | | JB47199-13 | | JB47199-14 | | JB47199-15 | | JB47199-16 | | JB47199-17 | | JB47199-18 | | JB47199-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **SVOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1'-BIPHENYL | 3100 | 140 | 0.066 | U | 0.0142 | J | 0.0231 | J | 0.064 | U | 0.551 | | 0.0455 | J | 0.0224 | J | 0.0189 | J | 0.0335 | J | 0.0756 | | 0.073 | U |
| 1,2,4,5-TETRACHLOROBENZENE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 1,4-DIOXANE | NC | NC | 0.12 | U | 0.13 | U | 0.13 | U | 0.12 | U | 0.12 | U | 0.13 | U | 0.13 | U | 0.13 | U | 0.13 | U | 0.14 | U | 0.14 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | 23 | 5 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 2,3,4,6-TETRACHLOROPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2,4,5-TRICHLOROPHENOL | 6100 | 68 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2,4,6-TRICHLOROPHENOL | 19 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2,4-DICHLOROPHENOL | 180 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2,4-DIMETHYLPHENOL | 1200 | 1 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2,4-DINITROPHENOL | 120 | 0.3 | *0.66* | *U* | *0.67* | *U* | *0.68* | *U* | *0.64* | *U* | *0.68* | *U* | *0.75* | *U* | *0.72* | *U* | *0.71* | *U* | *0.75* | *U* | *0.7* | *U* | *0.73* | *U* |
| 2,4-DINITROTOLUENE | 0.7 | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 2,6-DINITROTOLUENE | 0.7 | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 2-CHLORONAPHTHALENE | NC | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 2-CHLOROPHENOL | 310 | 0.8 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2-METHYLNAPHTHALENE | 230 | 8 | 0.066 | U | 0.0387 | J | 0.0393 | J | 0.064 | U | 1.4 | | 0.185 | | 0.0755 | | 0.0515 | J | 0.12 | | 0.22 | | 0.073 | U |
| 2-METHYLPHENOL | 310 | NC | 0.066 | U | 0.067 | U | 0.068 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 2-NITROANILINE | 39 | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 2-NITROPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 3&4-METHYLPHENOL | NC | NC | 0.066 | U | 0.067 | U | 0.068 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 3,3'-DICHLOROBENZIDINE | 1 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 3-NITROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 4,6-DINITRO-2-METHYLPHENOL | 6 | 0.3 | *0.66* | *U* | *0.67* | *U* | *0.68* | *U* | *0.64* | *U* | *0.68* | *U* | *0.75* | *U* | *0.72* | *U* | *0.71* | *U* | *0.75* | *U* | *0.7* | *U* | *0.73* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | NC | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 4-CHLORO-3-METHYLPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 4-CHLOROANILINE | NC | NC | 0.025 | J | 0.0262 | J | 0.051 | J | 0.0274 | J | 0.042 | J | 0.0341 | J | 0.0259 | J | 0.0371 | J | 0.0275 | J | 0.0316 | J | 0.18 | U |
| 4-CHLOROPHENYL PHENYL ETHER | NC | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| 4-NITROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| 4-NITROPHENOL | NC | NC | 0.33 | U | 0.33 | U | 0.34 | U | 0.32 | U | 0.34 | U | 0.38 | U | 0.36 | U | 0.35 | U | 0.37 | U | 0.35 | U | 0.37 | U |
| ACENAPHTHENE | 3400 | 110 | 0.0691 | | 0.349 | | 0.541 | | 0.175 | | 7.98 | | 0.81 | | 0.343 | | 0.253 | | 0.591 | | 1.23 | | 0.404 | |
| ACENAPHTHYLENE | 300000 | NC | 0.033 | U | 0.0117 | J | 0.033 | U | 0.032 | U | 0.074 | | 0.0155 | J | 0.036 | U | 0.035 | U | 0.037 | U | 0.0216 | J | 0.037 | U |
| ACETOPHENONE | 2 | 3 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| ANTHRACENE | 17000 | 2400 | 0.14 | | 0.615 | | 0.876 | | 0.375 | | 14.7 | | 0.993 | | 0.508 | | 0.274 | | 0.792 | | 1.9 | | 0.665 | |
| ATRAZINE | 210 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| BENZALDEHYDE | 6100 | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| BENZO(A)ANTHRACENE | 0.6 | 0.8 | 0.336 | | **1.73** | | **0.939** | | **0.7** | | **21.2** | | **1.65** | | **0.896** | | 0.476 | | **1.22** | | **2.9** | | **1.28** | |
| BENZO(A)PYRENE | 0.2 | 0.2 | **0.305** | | **1.62** | | **0.832** | | **0.636** | | **16.5** | | **1.44** | | **0.806** | | **0.443** | | **1.1** | | **2.45** | | **1.17** | |
| BENZO(B)FLUORANTHENE | 0.6 | 2 | 0.369 | | **1.58** | | **1.02** | | **0.786** | | **14.8** | | **1.32** | | **0.949** | | 0.416 | | **1.22** | | **2.17** | | **1.31** | |
| BENZO(G,H,I)PERYLENE | 30000 | NC | 0.213 | | 0.914 | | 0.541 | | 0.414 | | 8.27 | | 0.773 | | 0.515 | | 0.248 | | 0.677 | | 1.19 | | 0.744 | |
| BENZO(K)FLUORANTHENE | 6 | 25 | 0.137 | | 1.13 | | 0.338 | | 0.26 | | **15** | | 1.07 | | 0.346 | | 0.319 | | 0.484 | | 1.78 | | 0.53 | |
| BIS(2-CHLOROETHOXY)METHANE | NC | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| BIS(2-CHLOROETHYL)ETHER | 0.4 | 0.2 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | 35 | 1200 | 0.0386 | J | 0.0748 | | 0.876 | | 0.0459 | J | 0.133 | | 0.0922 | | 0.0732 | | 0.0883 | | 0.0843 | | 0.0904 | | 0.0816 | |
| BUTYLBENZYL PHTHALATE | 1200 | 230 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| CAPROLACTAM | 31000 | 12 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| CARBAZOLE | 24 | NC | 0.0711 | | 0.292 | | 0.351 | | 0.196 | | 7.92 | | 0.503 | | 0.237 | | 0.159 | | 0.374 | | 0.847 | | 0.319 | |
| CHRYSENE | 62 | 80 | 0.343 | | 1.81 | | 0.942 | | 0.717 | | 19.9 | | 1.65 | | 0.886 | | 0.482 | | 1.19 | | 2.82 | | 1.23 | |
| DI-N-BUTYL PHTHALATE | 6100 | 760 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| DI-N-OCTYL PHTHALATE | 2400 | 3300 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| DIBENZO(A,H)ANTHRACENE | 0.2 | 0.8 | 0.0579 | | **0.329** | | 0.142 | | 0.111 | | **2.56** | | **0.289** | | 0.132 | | 0.0878 | | 0.182 | | **0.465** | | 0.194 | |
| DIBENZOFURAN | NC | NC | 0.0351 | J | 0.137 | | 0.342 | | 0.1 | | 4.84 | | 0.444 | | 0.181 | | 0.142 | | 0.282 | | 0.722 | | 0.204 | |
| DIETHYL PHTHALATE | 49000 | 88 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| DIMETHYL PHTHALATE | NC | NC | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| FLUORANTHENE | 2300 | 1300 | 0.739 | | 3.72 | | 2.56 | | 1.71 | | 59 | | 4.04 | | 2.13 | | 1.13 | | 2.91 | | 6.16 | | 3.01 | |
| FLUORENE | 2300 | 170 | 0.0487 | | 0.253 | | 0.467 | | 0.13 | | 7.48 | | 0.518 | | 0.2 | | 0.142 | | 0.397 | | 1.06 | | 0.289 | |
| HEXACHLOROBENZENE | 0.3 | 0.2 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| HEXACHLOROBUTADIENE | 6 | 0.9 | 0.033 | U | 0.033 | U | 0.033 | U | 0.032 | U | 0.034 | U | 0.038 | U | 0.036 | U | 0.035 | U | 0.037 | U | 0.035 | U | 0.037 | U |
| HEXACHLOROCYCLOPENTADIENE | 45 | 320 | 0.33 | U | 0.33 | U | 0.33 | U | 0.32 | U | 0.34 | U | 0.38 | U | 0.36 | U | 0.35 | U | 0.37 | U | 0.35 | U | 0.37 | U |
| HEXACHLOROETHANE | 35 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| INDENO(1,2,3-CD)PYRENE | 0.6 | 7 | 0.183 | | **0.824** | | 0.465 | | 0.363 | | **7.16** | | **0.712** | | 0.429 | | 0.225 | | 0.571 | | **1.14** | | **0.813** | |
| ISOPHORONE | 510 | 0.2 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| N-NITROSO-DI-N-PROPYLAMINE | 0.2 | 0.2 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| N-NITROSODIPHENYLAMINE | 99 | 0.4 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.18 | U |
| NAPHTHALENE | 6 | 25 | 0.033 | U | 0.0825 | | 0.0553 | | 0.0275 | J | 1.05 | | 0.328 | | 0.144 | | 0.0643 | | 0.288 | | 0.431 | | 0.0612 | |
| NITROBENZENE | 31 | 0.2 | 0.066 | U | 0.067 | U | 0.066 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| PHENANTHRENE | 300000 | NC | 0.538 | | 2.08 | | 3.53 | | 1.46 | | 51.7 | | 3.59 | | 1.86 | | 1.05 | | 2.85 | | 5.64 | | 2.39 | |
| PHENOL | 18000 | 8 | 0.066 | U | 0.067 | U | 0.068 | U | 0.064 | U | 0.068 | U | 0.075 | U | 0.072 | U | 0.071 | U | 0.075 | U | 0.07 | U | 0.073 | U |
| PYRENE | 1700 | 840 | 0.591 | | 3.04 | | 1.89 | | 1.33 | | 47.7 | | 3.27 | | 1.65 | | 0.972 | | 2.28 | | 4.99 | | 2.24 | |
| TOTAL TICS, ALKANES | -- | -- | 0.15 | J | 0 | | 1.69 | J | 0.35 | J | 0 | | 0 | | 0.17 | J | 0.14 | J | 0.18 | J | 0 | | 0.18 | J |
| TOTAL TICS, SEMI-VOLATILES | -- | -- | 4.66 | J | 9.66 | J | 17.15 | J | 5.71 | J | 93.2 | J | 9.27 | J | 7.34 | J | 8.63 | J | 10.04 | J | 12.15 | J | 10.62 | J |

| | | | 087-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C03-091113 | | 087-WC-C04-091113 | | 087-WC-C05-091113 | | | | | | | | | | | | | | | | | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-3 | | JB47199-4 | | JB47199-5 | | | | | | | | | | | | | | | | | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | | | | | | | | | | | | | | | | |
| **SVOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | | | | | | | | | | | | | | | | |
| 1,1'-BIPHENYL | 3100 | 140 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 1,2,4,5-TETRACHLOROBENZENE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 1,4-DIOXANE | NC | NC | 0.11 | U | 0.12 | U | 0.12 | U | | | | | | | | | | | | | | | | |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | 23 | 5 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 2,3,4,6-TETRACHLOROPHENOL | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2,4,5-TRICHLOROPHENOL | 6100 | 68 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2,4,6-TRICHLOROPHENOL | 19 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2,4-DICHLOROPHENOL | 180 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2,4-DIMETHYLPHENOL | 1200 | 1 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2,4-DINITROPHENOL | 120 | 0.3 | *0.7* | *U* | *0.67* | *U* | *0.68* | *U* | | | | | | | | | | | | | | | | |
| 2,4-DINITROTOLUENE | 0.7 | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 2,6-DINITROTOLUENE | 0.7 | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 2-CHLORONAPHTHALENE | NC | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 2-CHLOROPHENOL | 310 | 0.8 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2-METHYLNAPHTHALENE | 230 | 8 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 2-METHYLPHENOL | 310 | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 2-NITROANILINE | 39 | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 2-NITROPHENOL | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 3&4-METHYLPHENOL | NC | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 3,3'-DICHLOROBENZIDINE | 1 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 3-NITROANILINE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 4,6-DINITRO-2-METHYLPHENOL | 6 | 0.3 | *0.7* | *U* | *0.67* | *U* | *0.68* | *U* | | | | | | | | | | | | | | | | |
| 4-BROMOPHENYL PHENYL ETHER | NC | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 4-CHLORO-3-METHYLPHENOL | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 4-CHLOROANILINE | NC | NC | 0.0283 | J | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 4-CHLOROPHENYL PHENYL ETHER | NC | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| 4-NITROANILINE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| 4-NITROPHENOL | NC | NC | 0.35 | U | 0.33 | U | 0.34 | U | | | | | | | | | | | | | | | | |
| ACENAPHTHENE | 3400 | 110 | 0.0757 | | 0.0346 | | 0.0217 | J | | | | | | | | | | | | | | | | |
| ACENAPHTHYLENE | 300000 | NC | 0.035 | U | 0.033 | U | 0.034 | U | | | | | | | | | | | | | | | | |
| ACETOPHENONE | 2 | 3 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| ANTHRACENE | 17000 | 2400 | 0.161 | | 0.0655 | | 0.0264 | J | | | | | | | | | | | | | | | | |
| ATRAZINE | 210 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| BENZALDEHYDE | 6100 | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| BENZO(A)ANTHRACENE | 0.6 | 0.8 | 0.55 | | 0.247 | | 0.125 | | | | | | | | | | | | | | | | | |
| BENZO(A)PYRENE | 0.2 | 0.2 | **0.527** | | **0.27** | | 0.139 | | | | | | | | | | | | | | | | | |
| BENZO(B)FLUORANTHENE | 0.6 | 2 | **0.63** | | 0.355 | | 0.183 | | | | | | | | | | | | | | | | | |
| BENZO(G,H,I)PERYLENE | 30000 | NC | 0.366 | | 0.212 | | 0.114 | | | | | | | | | | | | | | | | | |
| BENZO(K)FLUORANTHENE | 6 | 25 | 0.245 | | 0.143 | | 0.0725 | | | | | | | | | | | | | | | | | |
| BIS(2-CHLOROETHOXY)METHANE | NC | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| BIS(2-CHLOROETHYL)ETHER | 0.4 | 0.2 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| BIS(2-ETHYLHEXYL)PHTHALATE | 35 | 1200 | 0.0424 | J | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| BUTYLBENZYL PHTHALATE | 1200 | 230 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| CAPROLACTAM | 31000 | 12 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| CARBAZOLE | 24 | NC | 0.0795 | | 0.0346 | J | 0.018 | J | | | | | | | | | | | | | | | | |
| CHRYSENE | 62 | 80 | 0.565 | | 0.267 | | 0.143 | | | | | | | | | | | | | | | | | |
| DI-N-BUTYL PHTHALATE | 6100 | 760 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| DI-N-OCTYL PHTHALATE | 2400 | 3300 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| DIBENZO(A,H)ANTHRACENE | 0.2 | 0.8 | 0.0914 | | 0.0558 | | 0.0278 | J | | | | | | | | | | | | | | | | |
| DIBENZOFURAN | NC | NC | 0.0244 | J | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| DIETHYL PHTHALATE | 49000 | 88 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| DIMETHYL PHTHALATE | NC | NC | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| FLUORANTHENE | 2300 | 1300 | 1.09 | | 0.479 | | 0.262 | | | | | | | | | | | | | | | | | |
| FLUORENE | 2300 | 170 | 0.0505 | | 0.0232 | J | 0.034 | U | | | | | | | | | | | | | | | | |
| HEXACHLOROBENZENE | 0.3 | 0.2 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| HEXACHLOROBUTADIENE | 6 | 0.9 | 0.035 | U | 0.033 | U | 0.034 | U | | | | | | | | | | | | | | | | |
| HEXACHLOROCYCLOPENTADIENE | 45 | 320 | 0.35 | U | 0.33 | U | 0.34 | U | | | | | | | | | | | | | | | | |
| HEXACHLOROETHANE | 35 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| INDENO(1,2,3-CD)PYRENE | 0.6 | 7 | 0.306 | | 0.181 | | 0.0959 | | | | | | | | | | | | | | | | | |
| ISOPHORONE | 510 | 0.2 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| N-NITROSO-DI-N-PROPYLAMINE | 0.2 | 0.2 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| N-NITROSODIPHENYLAMINE | 99 | 0.4 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | | | | | | | | | |
| NAPHTHALENE | 6 | 25 | 0.035 | U | 0.033 | U | 0.034 | U | | | | | | | | | | | | | | | | |
| NITROBENZENE | 31 | 0.2 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| PHENANTHRENE | 300000 | NC | 0.55 | | 0.241 | | 0.131 | | | | | | | | | | | | | | | | | |
| PHENOL | 18000 | 8 | 0.07 | U | 0.067 | U | 0.068 | U | | | | | | | | | | | | | | | | |
| PYRENE | 1700 | 840 | 0.922 | | 0.378 | | 0.211 | | | | | | | | | | | | | | | | | |
| TOTAL TICS, ALKANES | -- | -- | 0 | | 0 | | 0 | | | | | | | | | | | | | | | | | |
| TOTAL TICS, SEMI-VOLATILES | -- | -- | 3.77 | J | 0.22 | J | 0 | | | | | | | | | | | | | | | | | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

B: Analyte found in sample and associated blank

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7B

## Concrete Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C01-091713 | | 124-WC-C02-091713 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | | 124-WC-C14-021114 | | 124-WC-C15-040414 | |
| LAB SAMPLE ID | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | JB47199-6 | | JB47199-7 | | JB47199-8 | | JB47199-9 | | JB47734-1 | | JB47734-2 | | JB59616-1 | | JB59616-2 | | JB59616-3 | | JB59616-4 | | JB63854-1 | |
| DATE SAMPLED | | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 09/17/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 04/04/2014 | |
| **SVOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1'-BIPHENYL | 3100 | 140 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.023 | J | 0.068 | U | 0.064 | U | 0.176 | J |
| 1,2,4,5-TETRACHLOROBENZENE | NC | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 1,4-DIOXANE | NC | NC | 0.12 | U | 0.12 | U | 0.12 | U | 0.12 | U | 0.12 | U | 0.14 | U | 0.034 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.036 | UJ |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | 23 | 5 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 2,3,4,6-TETRACHLOROPHENOL | NC | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 2,4,5-TRICHLOROPHENOL | 6100 | 68 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 2,4,6-TRICHLOROPHENOL | 19 | 0.2 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 2,4-DICHLOROPHENOL | 180 | 0.2 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 2,4-DIMETHYLPHENOL | 1200 | 1 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 2,4-DINITROPHENOL | 120 | 0.3 | *0.64* | *U* | *0.63* | *U* | *0.62* | *U* | *0.69* | *U* | *0.67* | *U* | *0.75* | *U* | *0.68* | *U* | *0.66* | *U* | *0.68* | *U* | *0.64* | *U* | *0.73* | *UJ* |
| 2,4-DINITROTOLUENE | 0.7 | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.034 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.036 | UJ |
| 2,6-DINITROTOLUENE | 0.7 | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.034 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.036 | UJ |
| 2-CHLORONAPHTHALENE | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 2-CHLOROPHENOL | 310 | 0.8 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 2-METHYLNAPHTHALENE | 230 | 8 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.213 | | 0.068 | U | 0.064 | U | 0.911 | J |
| 2-METHYLPHENOL | 310 | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 2-NITROANILINE | 39 | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | UJ | 0.16 | UJ | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 2-NITROPHENOL | NC | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 3&4-METHYLPHENOL | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 3,3'-DICHLOROBENZIDINE | 1 | 0.2 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 3-NITROANILINE | NC | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 4,6-DINITRO-2-METHYLPHENOL | 6 | 0.3 | *0.64* | *U* | *0.63* | *U* | *0.62* | *U* | *0.69* | *U* | *0.67* | *U* | *0.75* | *U* | *0.68* | *U* | *0.66* | *U* | *0.68* | *U* | *0.64* | *U* | *0.73* | *UJ* |
| 4-BROMOPHENYL PHENYL ETHER | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 4-CHLORO-3-METHYLPHENOL | NC | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 4-CHLOROANILINE | NC | NC | 0.16 | U | 0.0159 | J | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 4-CHLOROPHENYL PHENYL ETHER | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| 4-NITROANILINE | NC | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| 4-NITROPHENOL | NC | NC | 0.32 | U | 0.32 | U | 0.31 | U | 0.34 | U | 0.33 | U | 0.38 | U | 0.34 | UJ | 0.33 | UJ | 0.34 | U | 0.32 | U | 0.36 | UJ |
| ACENAPHTHENE | 3400 | 110 | 0.0246 | J | 0.0222 | J | 0.0171 | J | 0.0326 | J | 0.033 | U | 0.038 | U | 0.034 | U | 0.0262 | J | 0.0157 | J | 0.0194 | J | 0.036 | UJ |
| ACENAPHTHYLENE | 300000 | NC | 0.032 | U | 0.032 | U | 0.031 | U | 0.034 | U | 0.033 | U | 0.038 | U | 0.034 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.036 | UJ |
| ACETOPHENONE | 2 | 3 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| ANTHRACENE | 17000 | 2400 | 0.0547 | | 0.0371 | | 0.0193 | J | 0.0494 | | 0.033 | U | 0.038 | U | 0.034 | U | 0.0364 | | 0.033 | J | 0.0346 | | 0.036 | UJ |
| ATRAZINE | 210 | 0.2 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| BENZALDEHYDE | 6100 | NC | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| BENZO(A)ANTHRACENE | 0.6 | 0.8 | 0.245 | | 0.139 | | 0.085 | | 0.206 | | 0.0276 | J | 0.038 | U | 0.034 | U | 0.0805 | | 0.0295 | J | 0.0495 | | 0.0146 | J |
| BENZO(A)PYRENE | 0.2 | 0.2 | **0.254** | | 0.15 | | 0.0952 | | **0.219** | | 0.033 | U | 0.038 | U | 0.034 | U | 0.0719 | | 0.021 | J | 0.0398 | | 0.036 | UJ |
| BENZO(B)FLUORANTHENE | 0.6 | 2 | 0.32 | | 0.187 | | 0.124 | | 0.274 | | 0.033 | U | 0.038 | U | 0.034 | U | 0.0722 | | 0.0297 | J | 0.0569 | | 0.036 | UJ |
| BENZO(G,H,I)PERYLENE | 30000 | NC | 0.181 | | 0.122 | | 0.0782 | | 0.166 | | 0.033 | U | 0.038 | U | 0.034 | U | 0.0506 | | 0.034 | U | 0.0292 | J | 0.036 | UJ |
| BENZO(K)FLUORANTHENE | 6 | 25 | 0.122 | | 0.0643 | | 0.0488 | | 0.107 | | 0.033 | U | 0.038 | U | 0.034 | U | 0.046 | | 0.034 | U | 0.0198 | J | 0.036 | UJ |
| BIS(2-CHLOROETHOXY)METHANE | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| BIS(2-CHLOROETHYL)ETHER | 0.4 | 0.2 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| BIS(2-ETHYLHEXYL)PHTHALATE | 35 | 1200 | 0.064 | U | 0.0389 | J | 0.0487 | J | 0.0356 | J | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 1.3 | | 0.064 | U | 0.073 | UJ |
| BUTYLBENZYL PHTHALATE | 1200 | 230 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| CAPROLACTAM | 31000 | 12 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | UJ | 0.066 | UJ | 0.068 | U | 0.064 | U | 0.073 | UJ |
| CARBAZOLE | 24 | NC | 0.0306 | J | 0.0232 | J | 0.0154 | J | 0.0292 | J | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.0174 | J | 0.073 | UJ |
| CHRYSENE | 62 | 80 | 0.273 | | 0.145 | | 0.0972 | | 0.222 | | 0.0286 | J | 0.038 | U | 0.034 | U | 0.0864 | | 0.0309 | J | 0.0544 | | 0.0158 | J |
| DI-N-BUTYL PHTHALATE | 6100 | 760 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| DI-N-OCTYL PHTHALATE | 2400 | 3300 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| DIBENZO(A,H)ANTHRACENE | 0.2 | 0.8 | 0.05 | | 0.0291 | J | 0.0177 | J | 0.0412 | | 0.033 | U | 0.038 | U | 0.034 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.036 | UJ |
| DIBENZOFURAN | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.0213 | J | 0.0318 | J | 0.198 | J |
| DIETHYL PHTHALATE | 49000 | 88 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| DIMETHYL PHTHALATE | NC | NC | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| FLUORANTHENE | 2300 | 1300 | 0.535 | | 0.268 | | 0.192 | | 0.426 | | 0.0427 | | 0.0201 | J | 0.0184 | J | 0.155 | | 0.0785 | | 0.129 | | 0.037 | J |
| FLUORENE | 2300 | 170 | 0.0152 | J | 0.0146 | J | 0.031 | U | 0.0195 | J | 0.033 | U | 0.038 | U | 0.034 | U | 0.0483 | | 0.0213 | J | 0.0187 | J | 0.036 | UJ |
| HEXACHLOROBENZENE | 0.3 | 0.2 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| HEXACHLOROBUTADIENE | 6 | 0.9 | 0.032 | U | 0.032 | U | 0.031 | U | 0.034 | U | 0.033 | U | 0.038 | U | 0.034 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.036 | UJ |
| HEXACHLOROCYCLOPENTADIENE | 45 | 320 | 0.32 | U | 0.32 | U | 0.31 | U | 0.34 | U | 0.33 | U | 0.38 | U | 0.34 | U | 0.33 | U | 0.34 | U | 0.32 | U | 0.36 | UJ |
| HEXACHLOROETHANE | 35 | 0.2 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| INDENO(1,2,3-CD)PYRENE | 0.6 | 7 | 0.157 | | 0.0996 | | 0.0671 | | 0.142 | | 0.033 | U | 0.038 | U | 0.034 | U | 0.0471 | | 0.034 | U | 0.0232 | J | 0.036 | UJ |
| ISOPHORONE | 510 | 0.2 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| N-NITROSO-DI-N-PROPYLAMINE | 0.2 | 0.2 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| N-NITROSODIPHENYLAMINE | 99 | 0.4 | 0.16 | U | 0.16 | U | 0.15 | U | 0.17 | U | 0.17 | U | 0.19 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.16 | U | 0.18 | UJ |
| NAPHTHALENE | 6 | 25 | 0.032 | U | 0.032 | U | 0.031 | U | 0.034 | U | 0.033 | U | 0.038 | U | 0.034 | U | 0.0363 | | 0.034 | U | 0.032 | U | 0.04 | J |
| NITROBENZENE | 31 | 0.2 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| PHENANTHRENE | 300000 | NC | 0.241 | | 0.149 | | 0.0991 | | 0.22 | | 0.0163 | J | 0.038 | U | 0.0198 | J | 0.237 | | 0.101 | | 0.159 | | 0.774 | J |
| PHENOL | 18000 | 8 | 0.064 | U | 0.063 | U | 0.062 | U | 0.069 | U | 0.067 | U | 0.075 | U | 0.068 | U | 0.066 | U | 0.068 | U | 0.064 | U | 0.073 | UJ |
| PYRENE | 1700 | 840 | 0.43 | | 0.211 | | 0.156 | | 0.34 | | 0.0362 | | 0.016 | J | 0.0174 | J | 0.164 | | 0.062 | | 0.126 | | 0.0725 | J |
| TOTAL TICS, ALKANES | -- | -- | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 11.31 | J | 9.14 | J | 0 | | 18.6 | J |
| TOTAL TICS, SEMI-VOLATILES | -- | -- | 1.13 | J | 3.1 | J | 0.8 | J | 0.4 | J | 19.47 | J | 1.84 | J | 0 | | 4.08 | J | 2.51 | J | 0 | | 4.57 | J |

| | | | 124-WC | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C15-040414 | | 124-WC-C16-040414 | | 124-WC-C17-041114 | | 124-WC-C18-041114 | | | | | | | |
| LAB SAMPLE ID | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | JB63854-2 | | JB64504-1 | | JB64504-2 | | | | | | | | | |
| DATE SAMPLED | | | 04/04/2014 | | 04/11/2014 | | 04/11/2014 | | | | | | | | | |
| **SVOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | | | | | | | | |
| 1,1'-BIPHENYL | 3100 | 140 | 0.0941 | | 0.066 | U | 0.066 | U | | | | | | | | |
| 1,2,4,5-TETRACHLOROBENZENE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 1,4-DIOXANE | NC | NC | 0.035 | U | 0.033 | U | 0.033 | U | | | | | | | | |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | 23 | 5 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 2,3,4,6-TETRACHLOROPHENOL | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 2,4,5-TRICHLOROPHENOL | 6100 | 68 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 2,4,6-TRICHLOROPHENOL | 19 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 2,4-DICHLOROPHENOL | 180 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 2,4-DIMETHYLPHENOL | 1200 | 1 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 2,4-DINITROPHENOL | 120 | 0.3 | *0.7* | *U* | *0.66* | *U* | *0.66* | *U* | | | | | | | | |
| 2,4-DINITROTOLUENE | 0.7 | NC | 0.035 | U | 0.033 | UJ | 0.033 | U | | | | | | | | |
| 2,6-DINITROTOLUENE | 0.7 | NC | 0.035 | U | 0.033 | U | 0.033 | U | | | | | | | | |
| 2-CHLORONAPHTHALENE | NC | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 2-CHLOROPHENOL | 310 | 0.8 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 2-METHYLNAPHTHALENE | 230 | 8 | 0.117 | | 0.0571 | J | 0.066 | U | | | | | | | | |
| 2-METHYLPHENOL | 310 | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 2-NITROANILINE | 39 | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 2-NITROPHENOL | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 3&4-METHYLPHENOL | NC | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 3,3'-DICHLOROBENZIDINE | 1 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 3-NITROANILINE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 4,6-DINITRO-2-METHYLPHENOL | 6 | 0.3 | *0.7* | *U* | *0.66* | *U* | *0.66* | *U* | | | | | | | | |
| 4-BROMOPHENYL PHENYL ETHER | NC | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 4-CHLORO-3-METHYLPHENOL | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 4-CHLOROANILINE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 4-CHLOROPHENYL PHENYL ETHER | NC | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| 4-NITROANILINE | NC | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| 4-NITROPHENOL | NC | NC | 0.35 | U | 0.33 | U | 0.33 | U | | | | | | | | |
| ACENAPHTHENE | 3400 | 110 | 0.373 | | 0.033 | U | 0.0186 | J | | | | | | | | |
| ACENAPHTHYLENE | 300000 | NC | 0.035 | U | 0.016 | J | 0.033 | U | | | | | | | | |
| ACETOPHENONE | 2 | 3 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| ANTHRACENE | 17000 | 2400 | 0.136 | | 0.033 | U | 0.0148 | J | | | | | | | | |
| ATRAZINE | 210 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| BENZALDEHYDE | 6100 | NC | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| BENZO(A)ANTHRACENE | 0.6 | 0.8 | 0.178 | | 0.033 | U | 0.033 | U | | | | | | | | |
| BENZO(A)PYRENE | 0.2 | 0.2 | 0.0377 | | 0.033 | U | 0.033 | U | | | | | | | | |
| BENZO(B)FLUORANTHENE | 0.6 | 2 | 0.0812 | | 0.033 | U | 0.033 | U | | | | | | | | |
| BENZO(G,H,I)PERYLENE | 30000 | NC | 0.0187 | J | 0.033 | U | 0.033 | U | | | | | | | | |
| BENZO(K)FLUORANTHENE | 6 | 25 | 0.0382 | | 0.033 | U | 0.033 | U | | | | | | | | |
| BIS(2-CHLOROETHOXY)METHANE | NC | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| BIS(2-CHLOROETHYL)ETHER | 0.4 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| BIS(2-ETHYLHEXYL)PHTHALATE | 35 | 1200 | 0.0409 | J | 0.0552 | J | 0.0432 | JB | | | | | | | | |
| BUTYLBENZYL PHTHALATE | 1200 | 230 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| CAPROLACTAM | 31000 | 12 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| CARBAZOLE | 24 | NC | 0.134 | | 0.066 | U | 0.066 | U | | | | | | | | |
| CHRYSENE | 62 | 80 | 0.174 | | 0.033 | U | 0.033 | U | | | | | | | | |
| DI-N-BUTYL PHTHALATE | 6100 | 760 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| DI-N-OCTYL PHTHALATE | 2400 | 3300 | 0.07 | U | 0.066 | UJ | 0.066 | U | | | | | | | | |
| DIBENZO(A,H)ANTHRACENE | 0.2 | 0.8 | 0.035 | U | 0.033 | U | 0.033 | U | | | | | | | | |
| DIBENZOFURAN | NC | NC | 0.732 | | 0.066 | U | 0.0163 | J | | | | | | | | |
| DIETHYL PHTHALATE | 49000 | 88 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| DIMETHYL PHTHALATE | NC | NC | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| FLUORANTHENE | 2300 | 1300 | 1.31 | | 0.0179 | J | 0.0365 | | | | | | | | | |
| FLUORENE | 2300 | 170 | 0.131 | | 0.033 | U | 0.0252 | J | | | | | | | | |
| HEXACHLOROBENZENE | 0.3 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| HEXACHLOROBUTADIENE | 6 | 0.9 | 0.035 | U | 0.033 | U | 0.033 | U | | | | | | | | |
| HEXACHLOROCYCLOPENTADIENE | 45 | 320 | 0.35 | U | 0.33 | U | 0.33 | U | | | | | | | | |
| HEXACHLOROETHANE | 35 | 0.2 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| INDENO(1,2,3-CD)PYRENE | 0.6 | 7 | 0.0173 | J | 0.033 | U | 0.033 | U | | | | | | | | |
| ISOPHORONE | 510 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| N-NITROSO-DI-N-PROPYLAMINE | 0.2 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| N-NITROSODIPHENYLAMINE | 99 | 0.4 | 0.18 | U | 0.17 | U | 0.17 | U | | | | | | | | |
| NAPHTHALENE | 6 | 25 | 0.035 | U | 0.0159 | J | 0.033 | U | | | | | | | | |
| NITROBENZENE | 31 | 0.2 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| PHENANTHRENE | 300000 | NC | 3.4 | | 0.0852 | | 0.0813 | | | | | | | | | |
| PHENOL | 18000 | 8 | 0.07 | U | 0.066 | U | 0.066 | U | | | | | | | | |
| PYRENE | 1700 | 840 | 0.872 | | 0.0269 | J | 0.0229 | J | | | | | | | | |
| TOTAL TICS, ALKANES | -- | -- | 5.23 | J | 4.16 | J | 1.9 | J | | | | | | | | |
| TOTAL TICS, SEMI-VOLATILES | -- | -- | 2.49 | J | 1.53 | J | 2 | J | | | | | | | | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standard

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C

NC: No criterion established

**STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

B: Analyte found in sample and associated blank

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7B

## Concrete Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C19-041114 | | 124-WC-C20-041114 | | 124-WC-C21-050914 | | 124-WC-C22-053014 | | 124-WC-C23-053014 | | 124-WC-C24-053014 | | 124-WC-C25-061614 | | 124-WC-C26-072914 | | 124-WC-C27-072914 | | 124-WC-C28-090514 | | 124-WC-C29-092314 | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | 124-WC-C32-100214 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB64504-3 | | JB64504-4 | | JB66694-1 | | JB68105-1 | | JB68105-2 | | JB68105-3 | | JB69461-1 | | J72778-1 | | J72778-2 | | J75850-1 | | J77376-1 | | J77376-2 | | J77376-3 | | JB78325-1 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 04/11/2014 | | 04/11/2014 | | 05/09/2014 | | 05/30/2014 | | 05/30/2014 | | 05/30/2014 | | 06/16/2014 | | 07/29/2014 | | 07/29/2014 | | 09/05/2014 | | 09/23/2014 | | 09/23/2014 | | 09/23/2014 | | 10/02/2014 | |
| **SVOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1'-BIPHENYL | 3100 | 140 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.0164 | J | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.532 | |
| 1,2,4,5-TETRACHLOROBENZENE | NC | NC | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 1,4-DIOXANE | NC | NC | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.031 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | 23 | 5 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 2,3,4,6-TETRACHLOROPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | UJ | 0.17 | U | 0.17 | U | 0.16 | R | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 2,4,5-TRICHLOROPHENOL | 6100 | 68 | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | R | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 2,4,6-TRICHLOROPHENOL | 19 | 0.2 | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | R | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 2,4-DICHLOROPHENOL | 180 | 0.2 | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | R | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 2,4-DIMETHYLPHENOL | 1200 | 1 | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | U | 0.102 | J | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 2,4-DINITROPHENOL | 120 | 0.3 | *0.67* | *U* | *0.66* | *U* | *0.62* | *U* | *0.67* | *UJ* | *0.69* | *U* | *0.68* | *U* | 0.64 | R | *0.64* | *U* | *0.6* | *U* | *0.66* | *U* | *0.66* | *U* | *0.68* | *U* | *0.65* | *U* | *0.62* | *U* |
| 2,4-DINITROTOLUENE | 0.7 | NC | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.031 | U |
| 2,6-DINITROTOLUENE | 0.7 | NC | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.031 | U |
| 2-CHLORONAPHTHALENE | NC | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 2-CHLOROPHENOL | 310 | 0.8 | 0.067 | U | 0.066 | U | 0.062 | R | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 2-METHYLNAPHTHALENE | 230 | 8 | 0.0779 | | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.0492 | J | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 1.49 | |
| 2-METHYLPHENOL | 310 | NC | 0.067 | U | 0.066 | U | 0.062 | R | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | R | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 2-NITROANILINE | 39 | NC | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | UJ | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 2-NITROPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 3&4-METHYLPHENOL | NC | NC | 0.067 | U | 0.066 | U | 0.062 | R | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | R | 0.064 | U | 0.041 | J | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 3,3'-DICHLOROBENZIDINE | 1 | 0.2 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 3-NITROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 4,6-DINITRO-2-METHYLPHENOL | 6 | 0.3 | *0.67* | *U* | *0.66* | *U* | 0.62 | R | *0.67* | *U* | *0.69* | *U* | *0.68* | *U* | *0.64* | *U* | *0.64* | *U* | *0.6* | *U* | *0.66* | *U* | *0.66* | *U* | *0.68* | *U* | *0.65* | *U* | *0.62* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | NC | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 4-CHLORO-3-METHYLPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.16 | R | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | R | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 4-CHLOROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 4-CHLOROPHENYL PHENYL ETHER | NC | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| 4-NITROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| 4-NITROPHENOL | NC | NC | 0.34 | U | 0.33 | U | 0.31 | R | 0.34 | UJ | 0.34 | U | 0.34 | U | 0.32 | R | 0.32 | U | 0.3 | U | 0.33 | U | 0.33 | U | 0.34 | U | 0.33 | U | 0.31 | U |
| ACENAPHTHENE | 3400 | 110 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.0515 | | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 1.15 | |
| ACENAPHTHYLENE | 300000 | NC | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.0442 | |
| ACETOPHENONE | 2 | 3 | 0.0176 | J | 0.0325 | J | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| ANTHRACENE | 17000 | 2400 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.0236 | J | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.39 | |
| ATRAZINE | 210 | 0.2 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| BENZALDEHYDE | 6100 | NC | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| BENZO(A)ANTHRACENE | 0.6 | 0.8 | 0.0136 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.0151 | J | 0.033 | U | 0.36 | |
| BENZO(A)PYRENE | 0.2 | 0.2 | 0.0155 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.0834 | |
| BENZO(B)FLUORANTHENE | 0.6 | 2 | 0.0165 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.175 | |
| BENZO(G,H,I)PERYLENE | 30000 | NC | 0.0157 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.0247 | J |
| BENZO(K)FLUORANTHENE | 6 | 25 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.0733 | |
| BIS(2-CHLOROETHOXY)METHANE | NC | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| BIS(2-CHLOROETHYL)ETHER | 0.4 | 0.2 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | 35 | 1200 | 0.101 | B | 0.0335 | JB | 0.062 | U | 0.067 | U | 0.069 | U | 0.0761 | | 0.064 | U | 0.064 | U | 0.06 | U | 0.0911 | | 0.0678 | | 0.579 | | 0.065 | U | 0.062 | U |
| BUTYLBENZYL PHTHALATE | 1200 | 230 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| CAPROLACTAM | 31000 | 12 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| CARBAZOLE | 24 | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.245 | |
| CHRYSENE | 62 | 80 | 0.0133 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.0315 | J | 0.033 | U | 0.376 | |
| DI-N-BUTYL PHTHALATE | 6100 | 760 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.06 | BJ | 0.0488 | J | 0.0646 | J | 0.065 | U | 0.0315 | J |
| DI-N-OCTYL PHTHALATE | 2400 | 3300 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| DIBENZO(A,H)ANTHRACENE | 0.2 | 0.8 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.031 | U |
| DIBENZOFURAN | NC | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.0734 | | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 1.97 | |
| DIETHYL PHTHALATE | 49000 | 88 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| DIMETHYL PHTHALATE | NC | NC | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| FLUORANTHENE | 2300 | 1300 | 0.02 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.0518 | | 0.033 | U | 0.0197 | J | 0.0656 | | 0.033 | U | 2.37 | |
| FLUORENE | 2300 | 170 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.0419 | | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.531 | |
| HEXACHLOROBENZENE | 0.3 | 0.2 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| HEXACHLOROBUTADIENE | 6 | 0.9 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.031 | U |
| HEXACHLOROCYCLOPENTADIENE | 45 | 320 | 0.34 | U | 0.33 | U | 0.31 | U | 0.34 | U | 0.34 | U | 0.34 | U | 0.32 | U | 0.32 | U | 0.3 | U | 0.33 | U | 0.33 | U | 0.34 | U | 0.33 | U | 0.31 | U |
| HEXACHLOROETHANE | 35 | 0.2 | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| INDENO(1,2,3-CD)PYRENE | 0.6 | 7 | 0.034 | U | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.0371 | |
| ISOPHORONE | 510 | 0.2 | 0.067 | U | 0.066 | U | **0.206** | | **3.23** | | **39.9** | | **20.9** | | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| N-NITROSO-DI-N-PROPYLAMINE | 0.2 | 0.2 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| N-NITROSODIPHENYLAMINE | 99 | 0.4 | 0.17 | U | 0.17 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U | 0.15 | U | 0.16 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.16 | U |
| NAPHTHALENE | 6 | 25 | 0.0233 | J | 0.0126 | J | 0.031 | U | 0.104 | | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.03 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.033 | U | 0.186 | |
| NITROBENZENE | 31 | 0.2 | 0.067 | U | 0.066 | U | 0.062 | U | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | U | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.062 | U |
| PHENANTHRENE | 300000 | NC | 0.0291 | J | 0.0165 | J | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.145 | | 0.033 | U | 0.0159 | J | 0.0395 | | 0.033 | U | 4.39 | |
| PHENOL | 18000 | 8 | 0.067 | U | 0.066 | U | 0.062 | R | 0.067 | U | 0.069 | U | 0.068 | U | 0.064 | R | 0.064 | U | 0.06 | U | 0.066 | U | 0.066 | U | 0.068 | U | 0.065 | U | 0.307 | |
| PYRENE | 1700 | 840 | 0.023 | J | 0.033 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.032 | U | 0.0302 | | 0.033 | U | 0.0214 | J | 0.0424 | | 0.033 | U | 1.46 | |
| TOTAL TICS, ALKANES | -- | -- | 6.88 | J | 1.48 | J | 0 | | 0 | | 0 | | 4.92 | J | 0 | | 0 | | 0 | | 0 | | 3.88 | J | 6.12 | J | 0 | | 2.21 | J |
| TOTAL TICS, SEMI-VOLATILES | -- | -- | 3.43 | J | 19.79 | J | 3.19 | J | 43.38 | J | 49.47 | J | 57.15 | J | 4.28 | J | 0 | | 0 | | 0.92 | J | 6.35 | J | 26.66 | J | 1.49 | J | 7.16 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standard

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C

NC: No criterion established

**STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

B: Analyte found in sample and associated blank

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7B

## Concrete Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C33-100214 | | 124-WC-C34-100214 | | 124-WC-C35-121914 | | 124-WC-C36-121914 | | 124-WC-C37-121914 | | 124-WC-C38-012916 | | 124-WC-C39-012916 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB78325-2 | | JB78325-3 | | JB84701-1 | | JB84701-2 | | JB85005-1 | | JC13390-1 | | JC13390-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 10/02/2014 | | 10/02/2014 | | 12/19/2014 | | 12/19/2014 | | 12/24/2014 | | 01/29/2016 | | 01/29/2016 | |
| **SVOCs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1'-BIPHENYL | 3100 | 140 | 0.194 | | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.0219 | J |
| 1,2,4,5-TETRACHLOROBENZENE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 1,4-DIOXANE | NC | NC | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.034 | U | 0.033 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | 23 | 5 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 2,3,4,6-TETRACHLOROPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 2,4,5-TRICHLOROPHENOL | 6100 | 68 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 2,4,6-TRICHLOROPHENOL | 19 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 2,4-DICHLOROPHENOL | 180 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 2,4-DIMETHYLPHENOL | 1200 | 1 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 2,4-DINITROPHENOL | 120 | 0.3 | *0.69* | *U* | *0.69* | *U* | *0.67* | *U* | *0.64* | *U* | *0.71* | *U* | 0.17 | U | 0.17 | U |
| 2,4-DINITROTOLUENE | 0.7 | NC | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.034 | U | 0.033 | U |
| 2,6-DINITROTOLUENE | 0.7 | NC | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.034 | U | 0.033 | U |
| 2-CHLORONAPHTHALENE | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 2-CHLOROPHENOL | 310 | 0.8 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 2-METHYLNAPHTHALENE | 230 | 8 | 1.04 | | 0.069 | U | 0.0695 | | 0.0813 | | 0.0669 | J | 0.0868 | | 0.0736 | |
| 2-METHYLPHENOL | 310 | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 2-NITROANILINE | 39 | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 2-NITROPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 3&4-METHYLPHENOL | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 3,3'-DICHLOROBENZIDINE | 1 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 3-NITROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 4,6-DINITRO-2-METHYLPHENOL | 6 | 0.3 | *0.69* | *U* | *0.69* | *U* | *0.67* | *U* | *0.64* | *U* | *0.71* | *U* | *0.17* | *U* | *0.17* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 4-CHLORO-3-METHYLPHENOL | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 4-CHLOROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 4-CHLOROPHENYL PHENYL ETHER | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| 4-NITROANILINE | NC | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| 4-NITROPHENOL | NC | NC | 0.34 | U | 0.34 | U | 0.34 | U | 0.32 | U | 0.36 | U | 0.34 | U | 0.33 | U |
| ACENAPHTHENE | 3400 | 110 | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.101 | | 0.033 | U |
| ACENAPHTHYLENE | 300000 | NC | 0.034 | U | 0.034 | U | 0.016 | J | 0.032 | U | 0.036 | U | 0.034 | U | 0.033 | U |
| ACETOPHENONE | 2 | 3 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | | | | |
| ANTHRACENE | 17000 | 2400 | 0.034 | U | 0.0138 | J | 0.034 | U | 0.032 | U | 0.036 | U | 0.0853 | | 0.0137 | J |
| ATRAZINE | 210 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| BENZALDEHYDE | 6100 | NC | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| BENZO(A)ANTHRACENE | 0.6 | 0.8 | 0.034 | U | 0.0188 | J | 0.0539 | | 0.0213 | J | 0.036 | U | 0.0389 | | 0.0179 | J |
| BENZO(A)PYRENE | 0.2 | 0.2 | 0.034 | U | 0.034 | U | 0.0564 | | 0.032 | U | 0.036 | U | 0.0358 | | 0.0154 | J |
| BENZO(B)FLUORANTHENE | 0.6 | 2 | 0.034 | U | 0.034 | U | 0.0957 | | 0.032 | U | 0.036 | U | 0.0471 | | 0.0226 | J |
| BENZO(G,H,I)PERYLENE | 30000 | NC | 0.034 | U | 0.034 | U | 0.0432 | | 0.032 | U | 0.036 | U | 0.0241 | J | 0.033 | U |
| BENZO(K)FLUORANTHENE | 6 | 25 | 0.034 | U | 0.034 | U | 0.0251 | J | 0.032 | U | 0.036 | U | 0.0165 | J | 0.033 | U |
| BIS(2-CHLOROETHOXY)METHANE | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| BIS(2-CHLOROETHYL)ETHER | 0.4 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | 35 | 1200 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.0889 | | 0.0759 | |
| BUTYLBENZYL PHTHALATE | 1200 | 230 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| CAPROLACTAM | 31000 | 12 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| CARBAZOLE | 24 | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| CHRYSENE | 62 | 80 | 0.0252 | J | 0.0211 | J | 0.0713 | | 0.0205 | J | 0.036 | U | 0.0509 | | 0.0234 | J |
| DI-N-BUTYL PHTHALATE | 6100 | 760 | 0.069 | U | 0.0521 | J | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| DI-N-OCTYL PHTHALATE | 2400 | 3300 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| DIBENZO(A,H)ANTHRACENE | 0.2 | 0.8 | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.034 | U | 0.033 | U |
| DIBENZOFURAN | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| DIETHYL PHTHALATE | 49000 | 88 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| DIMETHYL PHTHALATE | NC | NC | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| FLUORANTHENE | 2300 | 1300 | 0.0338 | J | 0.0517 | | 0.0711 | | 0.0258 | J | 0.036 | U | 0.109 | | 0.0486 | |
| FLUORENE | 2300 | 170 | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.205 | | 0.033 | U |
| HEXACHLOROBENZENE | 0.3 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| HEXACHLOROBUTADIENE | 6 | 0.9 | 0.034 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.034 | U | 0.033 | U |
| HEXACHLOROCYCLOPENTADIENE | 45 | 320 | 0.34 | U | 0.34 | U | 0.34 | U | 0.32 | U | 0.36 | U | 0.34 | U | 0.33 | U |
| HEXACHLOROETHANE | 35 | 0.2 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| INDENO(1,2,3-CD)PYRENE | 0.6 | 7 | 0.034 | U | 0.034 | U | 0.0464 | | 0.032 | U | 0.036 | U | 0.0231 | J | 0.033 | U |
| ISOPHORONE | 510 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.0621 | J |
| N-NITROSO-DI-N-PROPYLAMINE | 0.2 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| N-NITROSODIPHENYLAMINE | 99 | 0.4 | 0.17 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.17 | U | 0.17 | U |
| NAPHTHALENE | 6 | 25 | 0.126 | | 0.034 | U | 0.034 | U | 0.032 | U | 0.036 | U | 0.018 | J | 0.0183 | J |
| NITROBENZENE | 31 | 0.2 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| PHENANTHRENE | 300000 | NC | 0.5 | | 0.0503 | | 0.0197 | J | 0.0194 | J | 0.0652 | | 0.516 | | 0.116 | |
| PHENOL | 18000 | 8 | 0.069 | U | 0.069 | U | 0.067 | U | 0.064 | U | 0.071 | U | 0.069 | U | 0.067 | U |
| PYRENE | 1700 | 840 | 0.0629 | | 0.0437 | | 0.0867 | | 0.0294 | J | 0.036 | U | 0.146 | | 0.0407 | |
| TOTAL TICS, ALKANES | -- | -- | 87.5 | J | 0 | | 1.73 | J | 0.39 | J | 26.26 | J | 18.67 | J | 17.43 | J |
| TOTAL TICS, SEMI-VOLATILES | -- | -- | 16.4 | J | 0 | | 0 | | 0.33 | J | 7.15 | J | 11.13 | J | 2.34 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standard

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C

NC: No criterion established

**STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

B: Analyte found in sample and associated blank

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7C

## Concrete Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C01-091113 | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | | 087-WC-C04-091113 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-1 | | JB47199-10 | | JB47199-11 | | JB47199-12 | | JB47199-13 | | JB47199-14 | | JB47199-15 | | JB47199-16 | | JB47199-17 | | JB47199-18 | | JB47199-2 | | JB47199-3 | | JB47199-4 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **Metals (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ALUMINUM | 78000 | 6000 | **7510** | | **6190** | | **6510** | | **6760** | | **6570** | | **6330** | | **6830** | | 5720 | | **6320** | | **6230** | | **6690** | | **7070** | | 5560 | |
| ANTIMONY | 31 | 6 | 2.1 | U | 2.1 | U | 2.1 | U | 2.1 | U | 2.2 | U | 2.3 | U | 2.3 | U | 2.2 | U | 2.2 | U | 2.3 | U | 2.2 | U | 4.3 | | 2 | |
| ARSENIC | 19 | 19 | 3.7 | | 2.1 | U | 2.1 | U | 2.2 | | 2.2 | U | 2.3 | U | 2.3 | | 2.2 | U | 2.2 | U | 2.3 | U | 2.9 | | 3.8 | | 2.3 | |
| BARIUM | 16000 | 2100 | 54.5 | | 42.4 | | 47.8 | | 51 | | 44.9 | | 44.5 | | 47.3 | | 39.2 | | 46.3 | | 47.1 | | 49 | | 46.7 | | 35.4 | |
| BERYLLIUM | 16 | 0.7 | 0.3 | | 0.3 | | 0.31 | | 0.33 | | 0.34 | | 0.31 | | 0.31 | | 0.28 | | 0.3 | | 0.29 | | 0.3 | | 0.39 | | 0.24 | |
| CADMIUM | 78 | 2 | 0.52 | U | 0.52 | U | 0.52 | U | 0.53 | U | 0.55 | U | 0.57 | U | 0.58 | U | 0.55 | U | 0.56 | U | 0.58 | U | 0.56 | U | 0.53 | U | 0.5 | U |
| CALCIUM | NC | NC | 80400 | | 63800 | | 58800 | | 65300 | | 63000 | | 62500 | | 63700 | | 59800 | | 69200 | | 62500 | | 68000 | | 68400 | | 56900 | |
| CHROMIUM | NC | NC | 21.7 | J | 13.8 | | 14.2 | | 15.1 | | 12.8 | | 12.6 | | 13.4 | | 11.6 | | 12.8 | | 11.9 | | 17.2 | J | 16.5 | J | 11.6 | J |
| COBALT | 590 | 90 | 5.2 | U | 5.2 | U | 5.2 | U | 5.3 | U | 5.5 | U | 5.7 | U | 5.8 | U | 5.5 | U | 5.6 | U | 5.8 | U | 5.6 | U | 5.3 | U | 5 | U |
| COPPER | 3100 | 11000 | 19.9 | | 17 | | 16.4 | | 19.1 | | 17.4 | | 16.2 | | 21.9 | | 16.4 | | 20 | | 15.8 | | 23.4 | | 22.7 | | 16.9 | |
| IRON | NC | NC | 9420 | | 7940 | | 8320 | | 7700 | | 8490 | | 7760 | | 9270 | | 6640 | | 7170 | | 6970 | | 11900 | | 15100 | | 9220 | |
| LEAD | 400 | 90 | 46.7 | | 31.1 | | 22.6 | | 33.7 | | 58.2 | | 23.8 | | 28.8 | | 31.7 | | 28.1 | | 25.1 | | 30 | | 35.8 | | 18.7 | |
| MAGNESIUM | NC | NC | 4880 | | 4100 | | 4020 | | 4060 | | 4270 | | 4090 | | 4760 | | 5390 | | 7810 | | 4220 | | 4440 | | 4610 | | 3810 | |
| MANGANESE | 11000 | 65 | **171** | | **149** | | **160** | | **171** | | **160** | | **144** | | **163** | | **128** | | **150** | | **146** | | **174** | | **184** | | **144** | |
| MERCURY | 23 | 0.1 | 0.051 | | **0.13** | | 0.085 | | 0.075 | | 0.079 | | 0.068 | | 0.068 | | 0.095 | | 0.064 | | 0.078 | | **0.14** | | 0.074 | | 0.034 | U |
| NICKEL | 1600 | 48 | 8.9 | | 7.6 | | 8 | | 8.3 | | 8.1 | | 7.3 | | 8.3 | | 6.5 | | 9 | | 6.8 | | 9.7 | | 11.8 | | 7 | |
| POTASSIUM | NC | NC | 1000 | U | 1000 | U | 1300 | | 1100 | U | 1100 | U | 1100 | U | 1200 | U | 1100 | U | 1100 | U | 1200 | U | 1100 | U | 1100 | U | 990 | U |
| SELENIUM | 390 | 11 | 2.1 | U | 2.1 | U | 2.1 | U | 2.1 | U | 2.2 | U | 2.3 | U | 2.3 | U | 2.2 | U | 2.2 | U | 2.3 | U | 2.2 | U | 2.1 | U | 2 | U |
| SILVER | 390 | 1 | 0.52 | U | 0.52 | U | 0.52 | U | 0.53 | U | 0.55 | U | 0.57 | U | 0.58 | U | 0.55 | U | 0.56 | U | 0.58 | U | 0.56 | U | 0.53 | U | 0.5 | U |
| SODIUM | NC | NC | 1000 | U | 1000 | U | 1000 | U | 1100 | U | 1100 | U | 1100 | U | 1200 | U | 1100 | U | 1100 | U | 1200 | U | 1100 | U | 1100 | U | 990 | U |
| THALLIUM | 5 | 3 | 1 | U | 1 | U | 1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.2 | U | 1.1 | U | 1.1 | U | 1.2 | U | 1.1 | U | 1.1 | U | 0.99 | U |
| VANADIUM | 78 | NC | 13 | | 10.8 | | 10.7 | | 10.8 | | 11.2 | | 10.1 | | 13.6 | | 8.6 | | 9.4 | | 9.7 | | 10.8 | | 11.7 | | 8.5 | |
| ZINC | 23000 | 930 | 103 | | 83.2 | | 72 | | 75.7 | | 70.7 | | 67.3 | | 74.2 | | 64.9 | | 78.6 | | 76.8 | | 92.7 | | 128 | | 74.6 | |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7C

## Concrete Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C01-091713 | | 124-WC-C02-091713 | | 124-WC-C03-100713 | | 124-WC-C04-100713 | | 124-WC-C05-100713 | | 124-WC-C06-100713 | | 124-WC-C07-100713 | | 124-WC-C08-100713 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-5 | | JB47199-6 | | JB47199-7 | | JB47199-8 | | JB47199-9 | | JB47734-1 | | JB47734-2 | | JB49574-1 | | JB49574-2 | | JB49574-3 | | JB49574-4 | | JB49574-5 | | JB49574-6 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 09/17/2013 | | 10/07/2013 | | 10/07/2013 | | 10/07/2013 | | 10/07/2013 | | 10/07/2013 | | 10/07/2013 | |
| **Metals (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ALUMINUM | 78000 | 6000 | **6040** | | **7030** | | **6860** | | 5830 | | 5920 | | **8460** | | **13000** | | **9460** | | **9350** | | **11100** | | **12500** | | **10500** | | **10400** | |
| ANTIMONY | 31 | 6 | 4 | | 3 | | **13.9** | | **10.7** | | 2.2 | U | 2 | U | 2 | U | 3.4 | | 3 | | 4.6 | | 4.5 | | 3.3 | | 2.8 | |
| ARSENIC | 19 | 19 | 2.1 | | 5.7 | | 2.4 | | 2.2 | | 2.2 | U | 3.5 | | **21.1** | | 5.1 | | 4.1 | | 5.8 | | 5 | | 5.4 | | 4.7 | |
| BARIUM | 16000 | 2100 | 41.4 | | 44.4 | | 47 | | 45 | | 46.4 | | 47.9 | | 90.1 | | 50.1 | | 52.8 | | 60.6 | | 54.8 | | 57.8 | | 57 | |
| BERYLLIUM | 16 | 0.7 | 0.26 | | 0.36 | | 0.29 | | 0.25 | | 0.28 | | 0.2 | U | 0.62 | | 0.41 | | 0.4 | | 0.54 | | 0.21 | U | 0.39 | | 0.44 | |
| CADMIUM | 78 | 2 | 0.5 | U | 0.5 | U | 0.53 | U | 0.52 | U | 0.54 | U | 0.51 | U | 0.51 | | 0.52 | U | 0.53 | U | 0.53 | U | 0.54 | U | 0.52 | U | 0.55 | U |
| CALCIUM | NC | NC | 62900 | | 76300 | | 70000 | | 55800 | | 57700 | | 85500 | | 91600 | | 94200 | | 78800 | | 71900 | | 95600 | | 87800 | | 105000 | |
| CHROMIUM | NC | NC | 12.2 | J | 48.7 | J | 15.7 | J | 14.7 | J | 15.4 | | 28.8 | | 38.9 | | 32 | | 24 | | 61.4 | | 90.9 | | 49.5 | | 18.4 | |
| COBALT | 590 | 90 | 5 | U | 20.1 | | 5.3 | U | 5.2 | U | 5.4 | U | 11.7 | | 15.6 | | 13.8 | | 14.8 | | 13.6 | | 15.6 | | 14.1 | | 12.1 | |
| COPPER | 3100 | 11000 | 14.4 | | 72.5 | | 21.3 | | 20.5 | | 21.4 | | 48.1 | | 33.8 | | 37.1 | | 37.6 | | 73.8 | | 51.7 | | 37.4 | | 35.3 | |
| IRON | NC | NC | 7490 | | 31600 | | 10100 | | 8610 | | 8540 | | 10600 | | 16100 | | 16400 | | 16300 | | 24400 | | 17300 | | 22000 | | 16500 | |
| LEAD | 400 | 90 | 17.3 | | 10.9 | | 32.7 | | 28.4 | | 28.4 | | 15.4 | | 13.6 | | 4.4 | | 5.6 | | 46.3 | | 6.2 | | 8.5 | | 4.4 | U |
| MAGNESIUM | NC | NC | 4540 | | 7610 | | 4310 | | 3750 | | 3100 | | 7400 | | 6650 | | 4970 | | 4740 | | 5170 | | 5410 | | 5420 | | 5850 | |
| MANGANESE | 11000 | 65 | **142** | | **292** | | **169** | | **164** | | **147** | | **171** | | **184** | | **261** | | **241** | | **324** | | **287** | | **318** | | **274** | |
| MERCURY | 23 | 0.1 | 0.04 | | 0.034 | U | 0.062 | | 0.053 | | 0.053 | | 0.034 | U | 0.042 | U | 0.033 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.03 | U | 0.035 | U |
| NICKEL | 1600 | 48 | 6.6 | | 41.6 | | 9.4 | | 8.6 | | 8.7 | | 19.1 | | 23.9 | | 26.8 | | 19.2 | | 38.9 | | **55.3** | | 42.4 | | 13.7 | |
| POTASSIUM | NC | NC | 1000 | U | 1000 | U | 1100 | U | 1070 | | 1100 | U | 1000 | U | 1290 | | 1470 | | 1730 | | 1150 | | 1100 | U | 1720 | | 1600 | |
| SELENIUM | 390 | 11 | 2 | U | 2 | U | 2.1 | U | 2.1 | U | 2.2 | U | 2 | U | 2 | U | 2.1 | U | 2.1 | U | 2.1 | U | 2.1 | U | 2.1 | U | 2.2 | U |
| SILVER | 390 | 1 | 1 | | 0.5 | U | 0.53 | U | 0.52 | U | 0.54 | U | 0.93 | | 0.91 | | 1 | | 0.86 | | 0.93 | | **1.1** | | 0.94 | | **1.4** | |
| SODIUM | NC | NC | 1000 | U | 1000 | U | 1100 | U | 1000 | U | 1100 | U | 1000 | U | 1000 | U | 1420 | | 1380 | | 1100 | U | 1170 | | 1330 | | 1100 | |
| THALLIUM | 5 | 3 | 1 | U | 1 | U | 1.1 | U | 1 | U | 1.1 | U | 1 | U | 1 | U | 2.1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1 | U | 2.2 | U |
| VANADIUM | 78 | NC | 9.3 | | 10.5 | | 10.6 | | 10 | | 9.3 | | 26.7 | | 42.3 | | 30.5 | | 39.2 | | 36 | | 32.3 | | 43.7 | | 36.5 | |
| ZINC | 23000 | 930 | 71.7 | | 225 | | 140 | | 90.9 | | 101 | | 131 | | 51.5 | | 63.8 | | 52 | | 145 | | 41.7 | | 46.3 | | 43.2 | |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remedi

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7C

## Concrete Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C09-100813 | | 124-WC-C10-100813 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | | 124-WC-C14-021114 | | 124-WC-C15-040414 | | 124-WC-C16-040414 | | 124-WC-C17-041114 | | 124-WC-C18-041114 | | 124-WC-C19-041114 | | 124-WC-C20-041114 | | 124-WC-C21-050914 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB49574-7 | | JB49574-8 | | JB59616-1 | | JB59616-2 | | JB59616-3 | | JB59616-4 | | JB63854-1 | | JB63854-2 | | JB64504-1 | | JB64504-2 | | JB64504-3 | | JB64504-4 | | JB66694-1 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 10/08/2013 | | 10/08/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 04/04/2014 | | 04/04/2014 | | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 05/09/2014 | |
| **Metals (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ALUMINUM | 78000 | 6000 | 5150 | | **12100** | | **11100** | | **10900** | | **9520** | | **7080** | | 6000 | J | **7640** | | **8190** | | **6710** | | **8210** | | **11100** | | **7350** | **J** |
| ANTIMONY | 31 | 6 | 2.2 | U | 4 | | 2.2 | UJ | 2.2 | UJ | 2.2 | U | 2.3 | U | 2.2 | UJ | 2.3 | U | 2.1 | UJ | 2 | U | 2.1 | U | 2.1 | U | 2.1 | UJ |
| ARSENIC | 19 | 19 | 4.4 | | 4.4 | | 3.1 | | 3.1 | | 2.9 | | 4 | | 4.2 | J | 4.1 | | 3.8 | | 3.4 | | 3.4 | | 3.3 | | 3.2 | |
| BARIUM | 16000 | 2100 | 42.5 | | 52 | | 67.8 | | 51.1 | | 54.1 | | 58.9 | | 53.3 | | 43 | | 47.5 | | 50.2 | | 64.1 | | 138 | | 38.4 | J |
| BERYLLIUM | 16 | 0.7 | 0.33 | | 0.55 | | **0.96** | | 0.55 | | 0.53 | | 0.46 | | 0.22 | U | 0.23 | U | 0.29 | | 0.32 | | 0.32 | | 0.32 | | 0.3 | J |
| CADMIUM | 78 | 2 | 0.54 | U | 0.54 | U | 0.54 | U | 0.56 | U | 0.56 | U | 0.58 | U | 0.54 | U | 0.57 | U | 0.54 | U | 0.51 | U | 0.58 | | 0.53 | U | 0.52 | U |
| CALCIUM | NC | NC | 143000 | | 105000 | | 81400 | | 68500 | | 65500 | | 61000 | | 126000 | J | 75800 | | 89400 | J | 54600 | | 76100 | | 59100 | | 71200 | J |
| CHROMIUM | NC | NC | 23.5 | | 19.8 | | 21 | | 19.4 | | 30.6 | | 23.2 | | 25 | | 27.1 | | 22.8 | | 47.6 | | 35 | | 36 | | 14.2 | |
| COBALT | 590 | 90 | 9.1 | | 11.2 | | 10.3 | | 10.2 | | 7.9 | | 9.1 | | 5.5 | | 8.5 | | 8.2 | | 11.9 | | 9.1 | | 15.6 | | 8.3 | |
| COPPER | 3100 | 11000 | 10.9 | | 27.1 | | 54.5 | | 82.4 | | 21.3 | | **4870** | | 13 | | 37.1 | | 28.9 | | 31.2 | | 33 | | 44 | | 8.4 | |
| IRON | NC | NC | 8990 | | 14600 | | 17000 | J | 20400 | J | 11700 | | 10800 | | 8330 | | 15500 | | 13900 | | 12900 | | 12200 | | 18400 | | 6950 | J |
| LEAD | 400 | 90 | 9.9 | | 10.6 | | 15.7 | J | 22.3 | J | **98.2** | | 42.5 | | 6.5 | | 6.5 | | 15.2 | | 33.7 | | 60.9 | | 37 | | 3.2 | |
| MAGNESIUM | NC | NC | 11200 | | 6910 | | 8940 | J | 6190 | J | 4760 | | 3780 | | 19400 | J | 14800 | | 4360 | | 4020 | | 4860 | | 7270 | | 4060 | J |
| MANGANESE | 11000 | 65 | **373** | | **173** | | **279** | **J** | **251** | **J** | **224** | | **182** | | **248** | **J** | **194** | | **206** | | **196** | | **219** | | **250** | | **154** | **J** |
| MERCURY | 23 | 0.1 | 0.032 | U | 0.035 | U | 0.035 | U | 0.037 | | 0.033 | U | 0.034 | U | 0.035 | U | 0.051 | | 0.033 | U | **1.1** | | **8.9** | | **13** | | 0.032 | U |
| NICKEL | 1600 | 48 | 7 | | 12 | | 18.4 | | 11.2 | | 16.9 | | 11.3 | | 6.8 | | 11.9 | | 15.5 | | 19.7 | | 19.8 | | 28.3 | | 8 | |
| POTASSIUM | NC | NC | 1100 | U | 1100 | U | 1100 | U | 1100 | U | 1140 | | 1200 | U | 1100 | U | 1100 | U | 1120 | | 1610 | | 1340 | | 4880 | | 1000 | U |
| SELENIUM | 390 | 11 | 2.2 | U | 2.1 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.3 | U | 4.3 | U | 2.3 | U | 2.1 | U | 2 | U | 2.1 | U | 2.1 | U | 2.1 | U |
| SILVER | 390 | 1 | **1.5** | | **1.3** | | **1.1** | | **1.1** | | 0.97 | | 0.84 | | **1.5** | | **1.1** | | 0.54 | U | 0.51 | U | 0.53 | U | 0.53 | U | 1 | U |
| SODIUM | NC | NC | 1100 | U | 1270 | | 1100 | U | 1100 | U | 1110 | | 1200 | U | 1100 | U | 1100 | U | 1100 | U | 1000 | U | 1100 | U | 1100 | U | 1000 | UJ |
| THALLIUM | 5 | 3 | 2.2 | U | 2.1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.2 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1 | U | 1.1 | U | 1.1 | U | 2.1 | U |
| VANADIUM | 78 | NC | 8.7 | | 31.2 | | 38.1 | | 42.8 | | 19.2 | | 15.9 | | 10.7 | | 21.6 | | 23.6 | | 22.8 | | 16.9 | | 34.7 | | 9.7 | |
| ZINC | 23000 | 930 | 39.9 | | 245 | | 136 | J | 81.8 | J | 53 | | 38.3 | | 43.3 | J | 59.8 | | 66.5 | | 69.5 | | 96.7 | | 94.3 | | 17.8 | |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remedi

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7C

## Concrete Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C22-053014 | | 124-WC-C23-053014 | | 124-WC-C24-053014 | | 124-WC-C25-061614 | | 124-WC-C26-072914 | | 124-WC-C27-072914 | | 124-WC-C28-090514 | | 124-WC-C29-092314 | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | 124-WC-C32-100214 | | 124-WC-C33-100214 | | 124-WC-C34-100214 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB68105-1 | | JB68105-2 | | JB68105-3 | | JB69461-1 | | JB72778-1A | | JB72778-2A | | JB75850-1A | | JB77376-1A | | JB77376-2A | | JB77376-3A | | JB78325-1A | | JB78325-2A | | JB78325-3A | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 05/30/2014 | | 05/30/2014 | | 05/30/2014 | | 06/16/2014 | | 07/29/2014 | | 07/29/2014 | | 09/05/2014 | | 09/23/2014 | | 09/23/2014 | | 09/23/2014 | | 10/02/2014 | | 10/02/2014 | | 10/02/2014 | |
| **Metals (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ALUMINUM | 78000 | 6000 | **8690** | | **8090** | | **6810** | | 5150 | | **7690** | | **10400** | | 5840 | | **7340** | | 5490 | | **7820** | | 4410 | | **6350** | | **7110** | |
| ANTIMONY | 31 | 6 | 2.1 | UJ | 2.1 | U | 2.2 | U | 2 | UJ | 2 | U | 1.9 | U | 2.1 | U | 2.1 | U | 2 | U | 2.1 | U | 2.1 | U | 2.2 | U | 2.2 | U |
| ARSENIC | 19 | 19 | 8.5 | | 2.1 | U | 3.5 | | 2 | U | 3.3 | | 3.4 | | 7.2 | | 11.5 | | 5.9 | | 4.8 | | 3.6 | | 2.5 | | 2.2 | U |
| BARIUM | 16000 | 2100 | 55.4 | | 52.7 | | 241 | | 33.5 | | 48 | | 77.8 | | 104 | | 72.7 | | 66 | | 81 | | 43.3 | | 48.8 | | 40.1 | |
| BERYLLIUM | 16 | 0.7 | 0.4 | | 0.37 | | 0.48 | | 0.2 | U | **0.71** | | **1.1** | | 0.58 | | 0.33 | | 0.35 | | 0.46 | | 0.36 | | 0.33 | | 0.28 | |
| CADMIUM | 78 | 2 | 0.53 | U | 0.53 | U | 0.54 | U | 0.5 | U | 0.5 | U | 0.46 | U | 0.53 | U | 0.53 | U | 0.51 | U | 0.53 | U | 0.53 | U | 0.56 | U | 0.55 | U |
| CALCIUM | NC | NC | 84900 | J | 70800 | | 96600 | | 45900 | J | 84900 | | 82500 | | 77300 | | 84200 | | 111000 | | 78000 | | 87100 | | 73700 | | 56600 | |
| CHROMIUM | NC | NC | 29.6 | | 12.3 | | 19.8 | | 11.6 | | 31.3 | | 38.2 | | 56.1 | J | 25.9 | J | 15.8 | J | 41 | J | 574 | | 302 | | 313 | |
| COBALT | 590 | 90 | 18.7 | | 8.5 | | 8.4 | | 6.6 | | 5.5 | | 7.8 | | 10.9 | | 7.2 | | 11.7 | | 25.9 | | 12.5 | | 10.1 | | 10.8 | |
| COPPER | 3100 | 11000 | 18.9 | | 8.3 | | 15.6 | | 4.8 | | 18.5 | | 44.5 | | 35.4 | | 17.9 | | 23.6 | | 94.8 | | 7 | | 10.8 | | 31.1 | |
| IRON | NC | NC | 11000 | J | 9320 | | 10600 | | 6190 | J | 13300 | | 11700 | | 9290 | | 20500 | | 10300 | | 17800 | | 6970 | | 8160 | | 14500 | |
| LEAD | 400 | 90 | 19.8 | | 4.3 | | 4.1 | | 2.8 | | 4.2 | | 10.6 | | 17.6 | | 5.2 | | 4.8 | | 8.8 | | 3.5 | | 4.2 | | 2.2 | |
| MAGNESIUM | NC | NC | 4950 | J | 4390 | | 21500 | | 3940 | J | 4220 | | 4350 | | 17100 | | 5090 | | 30500 | | 18800 | | 18900 | | 3670 | | 3750 | |
| MANGANESE | 11000 | 65 | **158** | **J** | **156** | | **360** | | **108** | **J** | **207** | | **254** | | **183** | | **346** | | **195** | | **232** | | **127** | | **155** | | **267** | |
| MERCURY | 23 | 0.1 | 0.031 | U | 0.046 | | 0.077 | | 0.033 | U | 0.033 | U | 0.032 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.034 | U | 0.032 | U | 0.037 | | 0.042 | |
| NICKEL | 1600 | 48 | 16.9 | | 8.7 | | 9.9 | | 15.3 | | 17.7 | | 17.6 | | 22.3 | | 9.4 | | 7.9 | | **48.6** | | 6.6 | | 6.5 | | 7.1 | |
| POTASSIUM | NC | NC | 1530 | | 1100 | U | 1260 | | 1000 | U | 1000 | U | 1630 | | 1100 | U | 1560 | | 1670 | | 1100 | U | 1100 | U | 1100 | U | 1110 | |
| SELENIUM | 390 | 11 | 2.1 | U | 2.1 | U | 2.2 | U | 2 | U | 2 | U | 1.9 | U | 2.1 | U | 2.1 | U | 2 | U | 2.1 | U | 2.1 | U | 2.2 | U | 2.2 | U |
| SILVER | 390 | 1 | 0.53 | U | 0.53 | U | 0.54 | U | 0.5 | U | 0.5 | U | 0.46 | U | 0.53 | U | 0.53 | U | 0.51 | U | 0.53 | U | 0.53 | U | 0.56 | U | 0.55 | U |
| SODIUM | NC | NC | 1100 | U | 1100 | U | 1120 | | 1000 | U | 1000 | U | 930 | U | 1100 | U | 1100 | U | 1210 | | 1100 | U | 1100 | U | 1100 | U | 1100 | U |
| THALLIUM | 5 | 3 | 1.1 | U | 1.1 | U | 1.1 | U | 1 | U | 1 | U | 0.93 | U | 1.1 | U | 1.1 | U | 1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.1 | U |
| VANADIUM | 78 | NC | 26.4 | J | 10.7 | | 17 | | 7.2 | J | 30.7 | | 21.1 | | 16.9 | | 32.5 | | 18.8 | | 41 | | 12.1 | | 12 | | 45.9 | |
| ZINC | 23000 | 930 | 66 | J | 22.8 | | 37.4 | | 15.3 | J | 49.6 | | 134 | | 34.3 | | 41.5 | | 29.3 | | 33.8 | | 25.1 | | 206 | | 24.9 | |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remedi

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7C

## Concrete Sample Results – Metals

Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C35-121914 | | 124-WC-C36-121914 | | 124-WC-C37-121914 | | 124-WC-C38-012916 | | 124-WC-C39-012916 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB84701-1 | | JB84701-2 | | JB85005-1 | | JC13390-1 | | JC13390-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 12/19/2014 | | 12/19/2014 | | 12/24/2014 | | 01/29/2016 | | 01/29/2016 | |
| **Metals (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ALUMINUM | 78000 | 6000 | **6370** | | **13000** | | **8530** | | **7400** | | **6960** | |
| ANTIMONY | 31 | 6 | 2.1 | U | 2.1 | U | 4.2 | U | 2.1 | U | 2 | U |
| ARSENIC | 19 | 19 | 3 | | 2.7 | | 8.5 | | 2.9 | | 4.9 | |
| BARIUM | 16000 | 2100 | 52.3 | | 55 | | 60.7 | | 55.9 | | 50.6 | |
| BERYLLIUM | 16 | 0.7 | 0.25 | | 0.27 | | 0.54 | | 0.28 | | 0.28 | |
| CADMIUM | 78 | 2 | 0.53 | U | 0.53 | U | 0.53 | U | 0.52 | U | 0.51 | U |
| CALCIUM | NC | NC | 29900 | | 28100 | | 82400 | | 77100 | | 132000 | |
| CHROMIUM | NC | NC | 53.5 | | 46.1 | | 28.1 | | 32.7 | | 30.9 | |
| COBALT | 590 | 90 | 7.7 | | 12.3 | | 5.5 | | 8.4 | | 7.8 | |
| COPPER | 3100 | 11000 | 75.4 | | 47.1 | | 22.1 | | 27.1 | | 18.6 | |
| IRON | NC | NC | 9550 | | 19800 | | 10700 | | 11800 | | 10500 | |
| LEAD | 400 | 90 | 18.6 | | 8.9 | | 8.2 | | 5.7 | | 8.7 | |
| MAGNESIUM | NC | NC | 3830 | | 10200 | | 5320 | | 10500 | | 5450 | |
| MANGANESE | 11000 | 65 | **166** | | **309** | | **226** | | **177** | | **243** | |
| MERCURY | 23 | 0.1 | 0.039 | | 0.036 | | 0.035 | U | 0.038 | | 0.047 | |
| NICKEL | 1600 | 48 | 15.2 | | 30.5 | | 15.2 | | 16.8 | | 11.4 | |
| POTASSIUM | NC | NC | 1100 | U | 1100 | U | 1170 | | 1000 | U | 1190 | |
| SELENIUM | 390 | 11 | 2.1 | U | 2.1 | U | 2.1 | U | 2.1 | U | 2 | U |
| SILVER | 390 | 1 | 0.55 | | 0.61 | | 0.53 | U | 0.52 | U | 0.51 | U |
| SODIUM | NC | NC | 1100 | U | 1140 | | 1100 | U | 1000 | U | 1000 | U |
| THALLIUM | 5 | 3 | 1.1 | U | 1.1 | U | 1.1 | U | 1 | U | 10 | U |
| VANADIUM | 78 | NC | 19.9 | | 44 | | 28.9 | | 22.6 | | 25 | |
| ZINC | 23000 | 930 | 68.6 | | 67.5 | | 72.9 | | 25.4 | | 34.9 | |

Notes:
TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remedi
NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening
NC: No criterion established
**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**
**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**
*Italicized values not detected: reporting limit exceeds criteria*
Depths reported in feet below ground surface
J: Estimated concentration
U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7D
## Concrete Sample Results – Pesticides and PCBs
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C01-091113 | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | | 087-WC-C04-091113 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-1 | | JB47199-10 | | JB47199-11 | | JB47199-12 | | JB47199-13 | | JB47199-14 | | JB47199-15 | | JB47199-16 | | JB47199-17 | | JB47199-18 | | JB47199-2 | | JB47199-3 | | JB47199-4 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **Pesticides/PCBs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | 3 | 4 | 0.00067 | U | 0.0012 | | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00083 | | 0.00067 | U |
| 4,4'-DDE | 2 | 18 | 0.0066 | | 0.0098 | | 0.0094 | | 0.0107 | | 0.0093 | | 0.0067 | | 0.0099 | | 0.0097 | | 0.0096 | | 0.0092 | | 0.0109 | | 0.0069 | | 0.0009 | |
| 4,4'-DDT | 2 | 11 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.0025 | | 0.0013 | | 0.00072 | U | 0.0013 | | 0.0029 | | 0.0013 | | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ALDRIN | 0.04 | 0.2 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ALPHA-BHC | 0.1 | 0.002 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ALPHA-CHLORDANE | NC | NC | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| AROCLOR-1016 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1221 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1232 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1242 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1248 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1254 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1260 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.0779 | | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1262 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| AROCLOR-1268 | NC | NC | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.037 | U | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| **TOTAL PCBs** | 0.2 | 0.2 | 0.034 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.037 | U | 0.034 | U | 0.036 | U | 0.037 | U | 0.0779 | | 0.037 | U | 0.035 | U | 0.035 | U | 0.034 | U |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| BETA-BHC | 0.4 | 0.002 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| BETA-CHLORDANE | NC | NC | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| CHLORDANE | 0.2 | 0.05 | 0.00067 | | 0.0007 | | 0.00069 | | 0.00068 | | 0.00073 | | 0.00068 | | 0.00072 | | 0.00073 | | 0.00074 | | 0.00074 | | 0.00071 | | 0.00069 | | 0.00067 | |
| DELTA-BHC | NC | NC | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| DIELDRIN | 0.04 | 0.003 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ENDOSULFAN I | NC | NC | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ENDOSULFAN II | NC | NC | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ENDOSULFAN SULFATE | 470 | 2 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ENDRIN | 23 | 1 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| ENDRIN ALDEHYDE | NC | NC | 0.0013 | | 0.0032 | | 0.0016 | | 0.0027 | | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.0035 | | 0.0014 | | 0.00067 | U |
| ENDRIN KETONE | NC | NC | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| GAMMA-BHC (LINDANE) | 0.4 | 0.002 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| HEPTACHLOR | 0.1 | 0.5 | 0.00067 | U | 0.0007 | U | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| HEPTACHLOR EPOXIDE | 0.07 | 0.01 | 0.00067 | U | 0.00072 | | 0.00069 | U | 0.00068 | U | 0.00073 | U | 0.00068 | U | 0.00072 | U | 0.00073 | U | 0.00074 | U | 0.00074 | U | 0.00071 | U | 0.00069 | U | 0.00067 | U |
| METHOXYCHLOR | 390 | 160 | 0.0013 | U | 0.0014 | U | 0.0014 | U | 0.0014 | U | 0.0015 | U | 0.0014 | U | 0.0014 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0014 | U | 0.0014 | | 0.0013 | U |
| PENTACHLOROPHENOL | 3 | 0.3 | *0.33* | *U* | *0.33* | *U* | *0.34* | *U* | *0.32* | *U* | *0.34* | *U* | *0.38* | *U* | *0.36* | *U* | *0.35* | *U* | *0.37* | *U* | *0.35* | *U* | *0.37* | *U* | *0.35* | *U* | *0.33* | *U* |
| TOXAPHENE | 0.6 | 0.3 | 0.017 | U | 0.018 | U | 0.017 | U | 0.017 | U | 0.018 | U | 0.017 | U | 0.018 | U | 0.018 | U | 0.019 | U | 0.018 | U | 0.018 | U | 0.017 | U | 0.017 | U |

Notes:
NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].
NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]
NC: No criterion established
**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**
**SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**
*Italicized values not detected; reporting limit exceeds criteria*
Depths reported in feet below ground surface
J: Estimated concentration
R or N: Rejected or negated by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7D

## Concrete Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | 124-WC | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C01-091713 | | 124-WC-C02-091713 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | | 124-WC-C14-021114 | | 124-WC-C15-040414 | | 124-WC-C16-040414 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-5 | | JB47199-6 | | JB47199-7 | | JB47199-8 | | JB47199-9 | | JB47734-1 | | JB47734-2 | | JB59616-1 | | JB59616-2 | | JB59616-3 | | JB59616-4 | | JB63854-1 | | JB63854-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 09/17/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 04/04/2014 | | 04/04/2014 | |
| **Pesticides/PCBs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | 3 | 4 | 0.00064 | U | 0.00064 | U | 0.0017 | | 0.0013 | | 0.002 | | 0.0012 | | 0.0008 | U | 0.00067 | U | 0.0021 | J | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| 4,4'-DDE | 2 | 18 | 0.00064 | U | 0.00064 | U | 0.0029 | | 0.00065 | U | 0.0017 | | 0.0021 | | 0.0008 | U | 0.00067 | U | 0.002 | | 0.00072 | U | 0.0014 | | 0.00074 | U | 0.00072 | U |
| 4,4'-DDT | 2 | 11 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.0064 | | 0.0008 | U | 0.00067 | U | 0.0015 | | 0.00072 | U | 0.0015 | | 0.00074 | U | 0.00088 | |
| ALDRIN | 0.04 | 0.2 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| ALPHA-BHC | 0.1 | 0.002 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| ALPHA-CHLORDANE | NC | NC | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.0058 | J | 0.00072 | U |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| AROCLOR-1016 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1221 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1232 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1242 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1248 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1254 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1260 | NC | NC | 0.032 | U | 0.032 | U | 0.0364 | | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1262 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1268 | NC | NC | 0.032 | U | 0.032 | U | 0.032 | U | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| **TOTAL PCBs** | 0.2 | 0.2 | 0.032 | U | 0.032 | U | 0.0364 | | 0.033 | U | 0.034 | U | 0.032 | U | 0.04 | U | 0.033 | U | 0.036 | U | 0.036 | U | 0.034 | U | 0.037 | U | 0.036 | U |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| BETA-BHC | 0.4 | 0.002 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | UJ | 0.00071 | UJ | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| BETA-CHLORDANE | NC | NC | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| CHLORDANE | 0.2 | 0.05 | 0.00064 | | 0.00064 | | 0.00065 | | 0.00065 | | 0.00068 | | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.0058 | | 0.00072 | U |
| DELTA-BHC | NC | NC | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| DIELDRIN | 0.04 | 0.003 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00079 | | 0.00074 | U | 0.00072 | U |
| ENDOSULFAN I | NC | NC | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| ENDOSULFAN II | NC | NC | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| ENDOSULFAN SULFATE | 470 | 2 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| ENDRIN | 23 | 1 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.0037 | J | 0.00072 | U |
| ENDRIN ALDEHYDE | NC | NC | 0.00064 | U | 0.00064 | U | 0.0019 | | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| ENDRIN KETONE | NC | NC | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| GAMMA-BHC (LINDANE) | 0.4 | 0.002 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| HEPTACHLOR | 0.1 | 0.5 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| HEPTACHLOR EPOXIDE | 0.07 | 0.01 | 0.00064 | U | 0.00064 | U | 0.00065 | U | 0.00065 | U | 0.00068 | U | 0.00063 | U | 0.0008 | U | 0.00067 | U | 0.00071 | U | 0.00072 | U | 0.00068 | U | 0.00074 | U | 0.00072 | U |
| METHOXYCHLOR | 390 | 160 | 0.0013 | U | 0.0013 | U | 0.0013 | U | 0.0013 | U | 0.0014 | U | 0.0013 | U | 0.0016 | U | 0.0013 | UJ | 0.0014 | UJ | 0.0014 | U | 0.0014 | U | 0.0015 | U | 0.0014 | U |
| PENTACHLOROPHENOL | 3 | 0.3 | *0.34* | *U* | *0.32* | *U* | *0.32* | *U* | *0.31* | *U* | *0.34* | *U* | *0.33* | *U* | *0.38* | *U* | *0.34* | *U* | *0.33* | *U* | **0.42** | | *0.32* | *U* | *0.36* | *UJ* | *0.35* | *U* |
| TOXAPHENE | 0.6 | 0.3 | 0.016 | U | 0.016 | U | 0.016 | U | 0.016 | U | 0.017 | U | 0.016 | U | 0.02 | U | 0.017 | U | 0.018 | U | 0.018 | U | 0.017 | U | 0.018 | U | 0.018 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediati

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Lev

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7D

## Concrete Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C17-041114 | | 124-WC-C18-041114 | | 124-WC-C19-041114 | | 124-WC-C20-041114 | | 124-WC-C21-050914 | | 124-WC-C22-053014 | | 124-WC-C23-053014 | | 124-WC-C24-053014 | | 124-WC-C25-061614 | | 124-WC-C26-072914 | | 124-WC-C27-072914 | | 124-WC-C28-090514 | | 124-WC-C29-092314 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB64504-1 | | JB64504-2 | | JB64504-3 | | JB64504-4 | | JB66694-1 | | JB68105-1 | | JB68105-2 | | JB68105-3 | | JB69461-1 | | JB72778-1 | | JB72778-2 | | JB75850-1 | | JB77376-1 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 05/09/2014 | | 05/30/2014 | | 05/30/2014 | | 05/30/2014 | | 06/16/2014 | | 07/29/2014 | | 07/29/2014 | | 09/05/2014 | | 09/23/2014 | |
| **Pesticides/PCBs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | 3 | 4 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| 4,4'-DDE | 2 | 18 | 0.00067 | U | 0.00068 | U | 0.0018 | | 0.002 | | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.0387 | |
| 4,4'-DDT | 2 | 11 | 0.00067 | U | 0.00068 | U | 0.0028 | | 0.0055 | | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00096 | | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.002 | |
| ALDRIN | 0.04 | 0.2 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| ALPHA-BHC | 0.1 | 0.002 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| ALPHA-CHLORDANE | NC | NC | 0.00067 | U | 0.00068 | U | 0.00089 | | 0.00071 | | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.0033 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| AROCLOR-1016 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1221 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1232 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1242 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1248 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1254 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.163 | | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.0576 | |
| AROCLOR-1260 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1262 | NC | NC | 0.034 | U | 0.034 | U | 0.0561 | | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| AROCLOR-1268 | NC | NC | 0.034 | U | 0.034 | U | 0.033 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.031 | U |
| **TOTAL PCBs** | 0.2 | 0.2 | 0.034 | U | 0.034 | U | 0.0561 | | 0.033 | U | 0.034 | U | 0.163 | | 0.034 | U | 0.031 | U | 0.033 | U | 0.034 | U | 0.031 | U | 0.035 | U | 0.0576 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| BETA-BHC | 0.4 | 0.002 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| BETA-CHLORDANE | NC | NC | 0.00067 | U | 0.00068 | U | 0.00072 | | 0.00074 | | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.0286 | |
| CHLORDANE | 0.2 | 0.05 | 0.00067 | U | 0.00068 | U | 0.0016 | | 0.0014 | | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.0319 | |
| DELTA-BHC | NC | NC | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| DIELDRIN | 0.04 | 0.003 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | **0.0612** | |
| ENDOSULFAN I | NC | NC | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| ENDOSULFAN II | NC | NC | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| ENDOSULFAN SULFATE | 470 | 2 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| ENDRIN | 23 | 1 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.0027 | |
| ENDRIN ALDEHYDE | NC | NC | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| ENDRIN KETONE | NC | NC | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| GAMMA-BHC (LINDANE) | 0.4 | 0.002 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| HEPTACHLOR | 0.1 | 0.5 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.00062 | U |
| HEPTACHLOR EPOXIDE | 0.07 | 0.01 | 0.00067 | U | 0.00068 | U | 0.00066 | U | 0.00067 | U | 0.00068 | U | 0.00063 | U | 0.00067 | U | 0.00063 | U | 0.00066 | U | 0.00068 | U | 0.00063 | U | 0.00069 | U | 0.0037 | |
| METHOXYCHLOR | 390 | 160 | 0.0013 | U | 0.0014 | U | 0.0013 | U | 0.0013 | U | 0.0014 | U | 0.0013 | U | 0.0013 | U | 0.0017 | | 0.0013 | U | 0.0014 | U | 0.0013 | U | 0.0014 | U | 0.0012 | U |
| PENTACHLOROPHENOL | 3 | 0.3 | *0.33* | *U* | *0.33* | *U* | *0.34* | *U* | *0.33* | *U* | 0.31 | R | *0.34* | *U* | *0.34* | *U* | *0.34* | *U* | *0.32* | *U* | *0.32* | *U* | 0.3 | U | *0.33* | *U* | *0.33* | *U* |
| TOXAPHENE | 0.6 | 0.3 | 0.017 | U | 0.017 | U | 0.016 | U | 0.017 | U | 0.017 | U | 0.016 | U | 0.017 | U | 0.016 | U | 0.016 | U | 0.017 | U | 0.016 | U | 0.017 | U | 0.015 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediati

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Lev

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7D

## Concrete Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | 124-WC-C32-100214 | | 124-WC-C33-100214 | | 124-WC-C34-100214 | | 124-WC-C35-121914 | | 124-WC-C36-121914 | | 124-WC-C37-121914 | | 124-WC-C38-012916 | | 124-WC-C39-012916 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB77376-2 | | JB77376-3 | | JB78325-1 | | JB78325-2 | | JB78325-3 | | JB84701-1 | | JB84701-2 | | JB85005-1 | | JC13390-1 | | JC13390-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/23/2014 | | 09/23/2014 | | 10/02/2014 | | 10/02/2014 | | 10/02/2014 | | 12/19/2014 | | 12/19/2014 | | 12/24/2014 | | 01/29/2016 | | 01/29/2016 | |
| **Pesticides/PCBs (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | 3 | 4 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| 4,4'-DDE | 2 | 18 | 0.0305 | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.0013 | | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| 4,4'-DDT | 2 | 11 | 0.0044 | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.0017 | | 0.00067 | U | 0.00072 | U | 0.00069 | UJ | 0.0007 | U |
| ALDRIN | 0.04 | 0.2 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ALPHA-BHC | 0.1 | 0.002 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ALPHA-CHLORDANE | NC | NC | 0.0265 | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| | | | | | | | | | | | | | | | | | | | | | | |
| AROCLOR-1016 | NC | NC | 0.033 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1221 | NC | NC | 0.033 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1232 | NC | NC | 0.033 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1242 | NC | NC | 0.033 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1248 | NC | NC | 0.115 | | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1254 | NC | NC | 0.0772 | | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1260 | NC | NC | 0.033 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1262 | NC | NC | 0.0379 | | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| AROCLOR-1268 | NC | NC | 0.033 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| **TOTAL PCBs** | 0.2 | 0.2 | **0.2301** | | 0.034 | U | 0.034 | U | 0.035 | U | 0.032 | U | 0.032 | U | 0.034 | U | 0.036 | U | 0.035 | U | 0.035 | U |
| | | | | | | | | | | | | | | | | | | | | | | |
| BETA-BHC | 0.4 | 0.002 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| BETA-CHLORDANE | NC | NC | 0.0583 | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| CHLORDANE | 0.2 | 0.05 | **0.0848** | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | | 0.00069 | U | 0.0007 | U |
| DELTA-BHC | NC | NC | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| DIELDRIN | 0.04 | 0.003 | **0.0083** | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ENDOSULFAN I | NC | NC | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ENDOSULFAN II | NC | NC | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ENDOSULFAN SULFATE | 470 | 2 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ENDRIN | 23 | 1 | 0.0013 | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ENDRIN ALDEHYDE | NC | NC | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| ENDRIN KETONE | NC | NC | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| GAMMA-BHC (LINDANE) | 0.4 | 0.002 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| HEPTACHLOR | 0.1 | 0.5 | 0.00066 | U | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| HEPTACHLOR EPOXIDE | 0.07 | 0.01 | 0.0053 | | 0.00068 | U | 0.00068 | U | 0.0007 | U | 0.00063 | U | 0.00064 | U | 0.00067 | U | 0.00072 | U | 0.00069 | U | 0.0007 | U |
| METHOXYCHLOR | 390 | 160 | 0.0169 | | 0.0014 | U | 0.0014 | U | 0.0014 | U | 0.0013 | U | 0.0013 | U | 0.0013 | U | 0.0014 | U | 0.0014 | U | 0.0014 | U |
| PENTACHLOROPHENOL | 3 | 0.3 | *0.34* | *U* | *0.33* | *U* | *0.31* | *U* | *0.34* | *U* | *0.34* | *U* | *0.34* | *U* | *0.32* | *U* | *0.36* | *U* | *0.17* | *U* | *0.17* | *U* |
| TOXAPHENE | 0.6 | 0.3 | 0.016 | U | 0.017 | U | 0.017 | U | 0.018 | U | 0.016 | U | 0.016 | U | 0.017 | U | 0.018 | U | 0.017 | U | 0.017 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediati

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Lev

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7E

## Concrete Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | 087-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | 087-WC-C01-091113 | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | |
| LAB SAMPLE ID | JB47199-1 | | JB47199-10 | | JB47199-11 | | JB47199-12 | | JB47199-13 | | JB47199-14 | | JB47199-15 | | JB47199-16 | | JB47199-17 | | JB47199-18 | | JB47199-2 | | JB47199-3 | |
| DATE SAMPLED | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **EPH (mg/kg)** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | 5.2 | U | 5.4 | U | 5.6 | U | 5.5 | U | 5.8 | U | 5.4 | U | 5.7 | U | 5.3 | U | 5.9 | U | 5.9 | U | 5.9 | U | 5.4 | U |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.2 | U | 5.4 | U | 5.6 | U | 5.5 | U | 5.8 | U | 5.4 | U | 5.7 | U | 5.3 | U | 5.9 | U | 5.9 | U | 5.9 | U | 5.4 | U |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | 5.2 | U | 5.4 | U | 5.6 | U | 5.5 | U | 5.8 | U | 5.4 | U | 5.7 | U | 5.3 | U | 5.9 | U | 5.9 | U | 5.9 | U | 5.4 | U |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.2 | U | 5.4 | U | 5.6 | U | 5.5 | U | 5.8 | U | 5.4 | U | 5.7 | U | 5.3 | U | 5.9 | U | 5.9 | U | 5.9 | U | 5.4 | U |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | 5.2 | U | 11.9 | | 13.9 | | 19.7 | | 11.7 | | 11.9 | | 39.2 | | 13.8 | | 12.5 | | 18.4 | | 16.7 | | 5.4 | U |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | 24 | | 29.2 | | 36.5 | | 32.6 | | 37.5 | | 29.5 | | 81.1 | | 36.7 | | 35.7 | | 32.5 | | 40.8 | | 20.8 | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | 64.8 | | 53.7 | | 99.2 | | 70.1 | | 75.8 | | 60.8 | | 75.1 | | 74.9 | | 82.9 | | 80 | | 80 | | 55.6 | |
| EPH (C9-C28) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| EXTRACTABLE PETROLEUM HYDROCARBONS (>C28-C40) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| PETROLEUM HYDROCARBONS | 88.7 | | 94.8 | | 150 | | 122 | | 125 | | 102 | | 195 | | 125 | | 131 | | 131 | | 138 | | 76.4 | |
| Residual Range Organics C28-C40 | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| Residual Range Organics, Aliphatic | 64.8 | | 53.7 | | 99.2 | | 70.1 | | 75.8 | | 60.8 | | 75.1 | | 74.9 | | 82.9 | | 80 | | 80 | | 55.6 | |
| Residual Range Organics, Aromatic | 24 | | 41.1 | | 50.4 | | 52.2 | | 49.2 | | 41.4 | | 120 | | 50.5 | | 48.2 | | 51 | | 57.6 | | 20.8 | |
| Total EPH (C9-C40) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | 5.2 | U | 5.4 | U | 5.6 | U | 5.5 | U | 5.8 | U | 5.4 | U | 5.7 | U | 5.3 | U | 5.9 | U | 5.9 | U | 5.9 | U | 5.4 | U |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amended 8/9/2010 cap value for total organic contaminants in the Soil Cleanup Criteria Table; last amended 5/12/1999

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7E

## Concrete Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | 087-WC | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | 087-WC-C04-091113 | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C01-091713 | | 124-WC-C02-091713 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | |
| LAB SAMPLE ID | JB47199-4 | | JB47199-5 | | JB47199-6 | | JB47199-7 | | JB47199-8 | | JB47199-9 | | JB47734-1 | | JB47734-2 | | JB59616-1 | | JB59616-2 | | JB59616-3 | |
| DATE SAMPLED | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 09/17/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | |
| **EPH (mg/kg)** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | 5.5 | U | 5.3 | U | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.5 | U | 5.3 | U | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | 5.5 | U | 5.3 | U | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.5 | U | 5.3 | U | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | 5.5 | U | 5.3 | U | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | 19.9 | | 22.8 | | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.5 | U | 5.3 | U | 5.4 | U | 196 | | 55.8 | | 80.5 | | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| EPH (C9-C28) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | 35.5 | | 169 | | 154 | |
| EXTRACTABLE PETROLEUM HYDROCARBONS (>C28-C40) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| PETROLEUM HYDROCARBONS | 19.9 | | 22.8 | | 5.4 | U | 196 | | 55.8 | | 80.5 | | 5.5 | U | 6.3 | U | NT | | | | NT | |
| Residual Range Organics C28-C40 | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | 6.8 | U | 7 | U | 114 | |
| Residual Range Organics, Aliphatic | 5.5 | U | 5.3 | U | 5.4 | U | 196 | | 55.8 | | 80.5 | | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| Residual Range Organics, Aromatic | 19.9 | | 22.8 | | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |
| Total EPH (C9-C40) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | 35.5 | | 169 | | 268 | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | 5.5 | U | 5.3 | U | 5.4 | U | 5.5 | U | 5.3 | U | 5.3 | U | 5.5 | U | 6.3 | U | NT | | NT | | NT | |

| | 124-WC | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | 124-WC-C14-021114 | | 124-WC-C15-040414 | | 124-WC-C16-040414 | | | |
| LAB SAMPLE ID | JB59616-4 | | JB63854-1 | | JB63854-2 | | | |
| DATE SAMPLED | 02/12/2014 | | 04/04/2014 | | 04/04/2014 | | | |
| **EPH (mg/kg)** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | | |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | NT | | NT | | NT | | | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | NT | | NT | | NT | | | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | NT | | NT | | NT | | | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | NT | | NT | | NT | | | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | NT | | NT | | NT | | | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | NT | | NT | | NT | | | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | NT | | NT | | NT | | | |
| EPH (C9-C28) | 33.6 | | 746 | | 216 | | | |
| EXTRACTABLE PETROLEUM HYDROCARBONS (>C28-C40) | NT | | 7.4 | U | 65.6 | | | |
| PETROLEUM HYDROCARBONS | NT | | NT | | NT | | | |
| Residual Range Organics C28-C40 | 16.5 | | NT | | NT | | | |
| Residual Range Organics, Aliphatic | NT | | NT | | NT | | | |
| Residual Range Organics, Aromatic | NT | | NT | | NT | | | |
| Total EPH (C9-C40) | 50.1 | | 746 | | 282 | | | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | NT | | NT | | NT | | | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; cap value for total organic contaminants in the Soil Cleanup Criteria Table; last amended 5/12/1999

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7E

## Concrete Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | 124-WC-C17-041114 | 124-WC-C18-041114 | 124-WC-C19-041114 | 124-WC-C20-041114 | 124-WC-C21-050914 | 124-WC-C22-053014 | 124-WC-C23-053014 | 124-WC-C24-053014 | 124-WC-C25-061614 | 124-WC-C26-072914 |
| LAB SAMPLE ID | JB64504-1 | JB64504-2 | JB64504-3 | JB64504-4 | JB66694-1 | JB68105-1 | JB68105-2 | JB68105-3 | JB69461-1 | JB72778-1 |
| DATE SAMPLED | 04/11/2014 | 04/11/2014 | 04/11/2014 | 04/11/2014 | 05/09/2014 | 05/30/2014 | 05/30/2014 | 05/30/2014 | 06/16/2014 | 07/29/2014 |
| **EPH (mg/kg)** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| EPH (C9-C28) | 235 J | 114 | 382 | 54.9 | 6.3 U | 61.7 | 15.8 | 96.4 | 69.5 | NT |
| EXTRACTABLE PETROLEUM HYDROCARBONS (>C28-C40) | 47.6 | 53.5 | 40.6 | 93 | 6.3 U | 10.5 | 6.6 U | 54.7 | 6.2 U | NT |
| PETROLEUM HYDROCARBONS | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| Residual Range Organics C28-C40 | NT | NT | NT | NT | NT | NT | NT | NT | NT | NT |
| Residual Range Organics, Aliphatic | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| Residual Range Organics, Aromatic | NT | NT | NT | NT | NT | NT | NT | NT | NT | 5.4 U |
| Total EPH (C9-C40) | 283 | 168 | 423 | 148 | 6.3 U | 72.2 | 15.8 | 151 | 69.5 | NT |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | NT | NT | NT | NT | NT | NT | NT | NT | NT NT | 5.4 U |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; cap value for total organic contaminants in the Soil Cleanup Criteria Table; last amended 5/12/1999

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7E

## Concrete Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | 124-WC | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | 124-WC-C27-072914 | | 124-WC-C28-090514 | | 124-WC-C29-092314 | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | 124-WC-C32-100214 | | 124-WC-C33-100214 | | 124-WC-C34-100214 | |
| LAB SAMPLE ID | JB72778-2 | | JB75850-1 | | JB77376-1 | | JB77376-2 | | JB77376-3 | | JB78325-1 | | JB78325-2 | | JB78325-3 | |
| DATE SAMPLED | 07/29/2014 | | 09/05/2014 | | 09/23/2014 | | 09/23/2014 | | 09/23/2014 | | 10/02/2014 | | 10/02/2014 | | 10/02/2014 | |
| **EPH (mg/kg)** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | 13 | | 5.5 | U | 5.3 | U | 5.4 | U | 5.6 | U | 5.1 | U | 5.7 | U | 5.6 | U |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.2 | U | 5.5 | U | 5.3 | U | 5.4 | U | 5.6 | U | 5.1 | U | 334 | | 5.6 | U |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | 5.2 | U | 5.5 | U | 5.3 | U | 5.4 | U | 5.6 | U | 5.1 | U | 66.7 | | 5.6 | U |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.2 | U | 5.5 | U | 5.3 | U | 88 | | 5.6 | U | 5.1 | U | 264 | | 5.6 | U |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | 5.2 | U | 5.5 | U | 5.3 | U | 37.5 | | 5.6 | U | 30.9 | J | 159 | J | 5.6 | UJ |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | 5.2 | U | 5.5 | U | 5.3 | U | 186 | | 5.6 | U | 5.1 | U | 41 | | 5.6 | U |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.2 | U | 5.5 | U | 14.3 | | 1650 | | 114 | | 33.9 | J | 121 | J | 5.6 | UJ |
| EPH (C9-C28) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| EXTRACTABLE PETROLEUM HYDROCARBONS (>C28-C40) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| PETROLEUM HYDROCARBONS | 13 | | 5.5 | U | 14.3 | | 1960 | | 114 | | 64.8 | | 1010 | | 5.6 | U |
| Residual Range Organics C28-C40 | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| Residual Range Organics, Aliphatic | 5.2 | U | 5.5 | U | 14.3 | | 1740 | | 114 | | 33.9 | | 745 | | 5.6 | U |
| Residual Range Organics, Aromatic | 13 | | 5.5 | U | 5.3 | U | 223 | | 5.6 | U | 30.9 | | 267 | | 5.6 | U |
| Total EPH (C9-C40) | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | 5.2 | U | 5.5 | U | 5.3 | U | 5.4 | U | 5.6 | U | 5.1 | U | 25.4 | | 5.6 | U |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; cap value for total organic contaminants in the Soil Cleanup Criteria Table; last amended 5/12/1999

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7E

## Concrete Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | 124-WC-C35-121914 | | 124-WC-C36-121914 | | 124-WC-C37-121914 | | 124-WC-C38-012916 | | 124-WC-C39-012916 | |
| LAB SAMPLE ID | JB84701-1 | | JB84701-2 | | JB85005-1 | | JC13390-1 | | JC13390-2 | |
| DATE SAMPLED | 12/19/2014 | | 12/19/2014 | | 12/24/2014 | | 01/29/2016 | | 01/29/2016 | |
| **EPH (mg/kg)** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | 5.3 | U | 5.4 | U | 5.8 | U | NT | | NT | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.3 | U | 5.4 | U | 154 | | NT | | NT | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | 5.3 | U | 5.4 | U | 5.8 | U | NT | | NT | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | 5.3 | U | 5.4 | U | 146 | | NT | | NT | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | 5.3 | U | 5.4 | U | 50.5 | | NT | | NT | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | 5.3 | U | 5.4 | U | 5.8 | U | NT | | NT | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | 32 | | 27.4 | | 30.5 | | NT | | NT | |
| EPH (C9-C28) | NT | | NT | | NT | | 297 | J | 216 | |
| EXTRACTABLE PETROLEUM HYDROCARBONS (>C28-C40) | NT | | NT | | NT | | 6.8 | U | 34.9 | |
| PETROLEUM HYDROCARBONS | 32 | | 27.4 | | 381 | | NT | | NT | |
| Residual Range Organics C28-C40 | NT | | NT | | NT | | NT | | NT | |
| Residual Range Organics, Aliphatic | 32 | | 27.4 | | 331 | | NT | | NT | |
| Residual Range Organics, Aromatic | 5.3 | U | 5.4 | U | 50.5 | | NT | | NT | |
| Total EPH (C9-C40) | NT | | NT | | NT | | NT | | NT | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | 5.3 | U | 5.4 | U | 5.8 | U | NT | | NT | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; cap value for total organic contaminants in the Soil Cleanup Criteria Table; last amended 5/12/1999

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7F

## Concrete Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C01-091113 | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-1 | | JB47199-10 | | JB47199-11 | | JB47199-12 | | JB47199-13 | | JB47199-14 | | JB47199-15 | | JB47199-16 | | JB47199-17 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **General Chemistry (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CYANIDE | 1600 | 20 | 0.66 | | 0.35 | | 0.63 | | 0.65 | | 0.31 | | 0.4 | | 0.48 | | 0.45 | | 0.33 | |
| HEXAVALENT CHROMIUM | 20 | NC | 0.65 | | 0.46 | | 0.61 | | 0.57 | | 0.5 | | 0.6 | | 0.63 | | 0.52 | | 0.51 | |

| | | | 087-WC | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C18-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | | 087-WC-C04-091113 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-18 | | JB47199-2 | | JB47199-3 | | JB47199-4 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **General Chemistry (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CYANIDE | 1600 | 20 | 0.39 | | 0.41 | | 0.72 | | 0.24 | U |
| HEXAVALENT CHROMIUM | 20 | NC | 0.54 | | 0.55 | | 0.55 | | 0.43 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7F

## Concrete Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 087-WC | | | | | | | | | | 124-WC | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | | 124-WC-C14-021114 | | 124-WC-C15-040414 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB47199-5 | | JB47199-6 | | JB47199-7 | | JB47199-8 | | JB47199-9 | | JB59616-1 | | JB59616-2 | | JB59616-3 | | JB59616-4 | | JB63854-1 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 04/04/2014 | |
| **General Chemistry (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CYANIDE | 1600 | 20 | 0.25 | U | 0.25 | U | 0.37 | | 0.25 | U | 0.4 | | NT | | NT | | NT | | NT | | NT | |
| HEXAVALENT CHROMIUM | 20 | NC | 0.6 | | 0.47 | | 0.62 | | 0.78 | | 0.78 | | 1.7 | | 0.7 | | 4.1 | | 2.6 | | 2.3 | |

| | | | 124-WC | | | | | |
|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C16-040414 | | 124-WC-C17-041114 | | 124-WC-C18-041114 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB63854-2 | | JB64504-1 | | JB64504-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 04/04/2014 | | 04/11/2014 | | 04/11/2014 | |
| **General Chemistry (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CYANIDE | 1600 | 20 | NT | | NT | | NT | |
| HEXAVALENT CHROMIUM | 20 | NC | 2.9 | | 2.6 | | 9 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C.

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7F

## Concrete Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C19-041114 | | 124-WC-C20-041114 | | 124-WC-C21-050914 | | 124-WC-C22-053014 | | 124-WC-C23-053014 | | 124-WC-C24-053014 | | 124-WC-C25-061614 | | 124-WC-C26-072914 | | 124-WC-C27-072914 | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB64504-3 | | JB64504-4 | | JB66694-1/1R | | JB68105-1 | | JB68105-2 | | JB68105-3 | | JB69461-1 | | JB72778-1 | | JB72778-2 | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 04/11/2014 | | 04/11/2014 | | 05/09/2014 | | 05/30/2014 | | 05/30/2014 | | 05/30/2014 | | 06/16/2014 | | 07/29/2014 | | 07/29/2014 | |
| **General Chemistry (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CYANIDE | 1600 | 20 | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | | NT | |
| HEXAVALENT CHROMIUM | 20 | NC | 2.2 | | 2.7 | | 3.4 | | 6 | | 0.51 | | 4.2 | | 0.62 | | 1.1 | | 1.7 | |

| | | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C28-090514 | | 124-WC-C29-092314 | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | | | | | | | | | | |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB75850-1 | | JB77376-1 | | JB77376-2/2R | | JB77376-3 | | | | | | | | | | | |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 09/05/2014 | | 09/23/2014 | | 09/23/2014 | | 09/23/2014 | | | | | | | | | | | |
| **General Chemistry (mg/kg)** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | | | | | | | | | | |
| CYANIDE | 1600 | 20 | NT | | NT | | NT | | NT | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | 20 | NC | 2.6 | | 10.2 | J | 1.6 | J | 10 | J | | | | | | | | | | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C.

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7F

## Concrete Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 124-WC | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | | 124-WC-C32-100214 | 124-WC-C33-100214 | 124-WC-C34-100214 | 124-WC-C35-121914 | 124-WC-C36-121914 | 124-WC-C37-121914 | 124-WC-C38-012916 | 124-WC-C39-012916 |
| LAB SAMPLE ID | NJ 2012 MOST | NJ 2013 | JB78325-1 | JB78325-2 | JB78325-3 | JB84701-1 | JB84701-2 | JB85005-1 | JC13390-1 | JC13390-2 |
| DATE SAMPLED | STRINGENT SRS | IGW SOIL | 10/02/2014 | 10/02/2014 | 10/02/2014 | 12/19/2014 | 12/19/2014 | 12/24/2014 | 01/29/2016 | 01/29/2016 |
| **General Chemistry (mg/kg)** | | | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** | **CONC Q** |
| CYANIDE | 1600 | 20 | NT | NT | NT | NT | NT | NT | NT | NT |
| HEXAVALENT CHROMIUM | 20 | NC | **604** J | **272** J | **329** | 13.1 J | 3.2 J | 2.6 | 2.2 | 2.6 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C.

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

NT: Not Tested

U: Not detected above method detection limit



Prepared by: DP 02/15/2016

Reviewed by: JD 05/24/2016

# TABLE 7G

## Concrete Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | 087-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C01-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | | 087-WC-C04-091113 | |
| LAB SAMPLE ID | RCRA Toxicity Characteristics | JB47199-10A/10B | | JB47199-11A/11B | | JB47199-12A/12B | | JB47199-13A/13B | | JB47199-14A/14B | | JB47199-15A/15B | | JB47199-16A/16B | | JB47199-17A/17B | | JB47199-18A/18B | | JB47199-1A/1B | | JB47199-2A/2B | | JB47199-3A/3B | | JB47199-4A/4B | |
| DATE SAMPLED | (40 CFR261.24) | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **SA-6 TAL Metals (mg/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | 100 | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BERYLLIUM | NC | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CADMIUM | 1 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHROMIUM | 5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |
| LEAD | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| SELENIUM | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | 5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per liter (mg/L)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7G

## Concrete Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | 087-WC | | | | | | | | | | 124-WC | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C01-091713 | | 124-WC-C02-091713 | | 124-WC-C11-021114 | | 124-WC-C12-021114 | | 124-WC-C13-021114 | | 124-WC-C14-021114 | | 124-WC-C15-040414 | | 124-WC-C16-040414 | |
| LAB SAMPLE ID | RCRA Toxicity Characteristics | JB47199-5A/5B | | JB47199-6A/6B | | JB47199-7A/7B | | JB47199-8A/8B | | JB47199-9A/9B | | JB47734-1A | | JB47734-2A | | JB59616-1A | | JB59616-2A | | JB59616-3A | | JB59616-4A | | JB63854-1A | | JB63854-2A | |
| DATE SAMPLED | (40 CFR261.24) | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 09/17/2013 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 02/12/2014 | | 04/04/2014 | | 04/04/2014 | |
| **SA-6 TAL Metals (mg/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | 100 | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BERYLLIUM | NC | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | - | | - | | - | | - | | - | | - | |
| CADMIUM | 1 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.0095 | | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHROMIUM | 5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.011 | | 0.01 | U | 0.069 | | 0.065 | | 0.021 | J | 0.069 | J |
| LEAD | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| SELENIUM | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | 5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.05 | U | 0.05 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per liter (mg/L)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7G

## Concrete Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | 124-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 124-WC-C17-041114 | | 124-WC-C18-041114 | | 124-WC-C19-041114 | | 124-WC-C20-041114 | | 124-WC-C21-050914 | | 124-WC-C22-053014 | | 124-WC-C23-053014 | | 124-WC-C24-053014 | | 124-WC-C25-061614 | | 124-WC-C26-072914 | | 124-WC-C27-072914 | | 124-WC-C28-090514 | | 124-WC-C29-092314 | |
| LAB SAMPLE ID | RCRA Toxicity Characteristics | JB64504-1A | | JB64504-2A | | JB64504-3A | | JB64504-4A | | JB66694-1A | | JB68105-1A | | JB68105-2A | | JB68105-3A | | JB69461-1A | | JB72778-1 | | JB72778-2 | | JB75850-1 | | JB77376-1 | |
| DATE SAMPLED | (40 CFR261.24) | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 04/11/2014 | | 05/09/2014 | | 05/30/2014 | | 05/30/2014 | | 05/30/2014 | | 06/16/2014 | | 07/29/2014 | | 07/29/2014 | | 09/05/2014 | | 09/23/2014 | |
| **SA-6 TAL Metals (mg/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | 100 | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | UJ | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BERYLLIUM | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CADMIUM | 1 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | UJ | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| CHROMIUM | 5 | 0.035 | | 0.15 | | 0.015 | | 0.01 | | 0.04 | | 0.075 | J | 0.01 | J | 0.053 | J | 0.012 | | 0.05 | U | 0.05 | U | 0.05 | U | 0.06 | J |
| LEAD | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | 0.2 | 0.0002 | U | 0.0002 | U | 0.0006 | | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| SELENIUM | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | 5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.02 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per liter (mg/L)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7G

## Concrete Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 124-WC-C30-092314 | | 124-WC-C31-092314 | | 124-WC-C32-100214 | | 124-WC-C33-100214 | | 124-WC-C34-100214 | | 124-WC-C35-121914 | | 124-WC-C36-121914 | | 124-WC-C37-121914 | | 124-WC-C38-012916 | | 124-WC-C39-012916 | |
| LAB SAMPLE ID | RCRA Toxicity Characteristics | JB77376-2 | | JB77376-3 | | JB78325-1 | | JB78325-2 | | JB78325-3 | | JB84701-1A | | JB84701-2A | | JB85005-1A | | JC13390-1A | | JC13390-2A | |
| DATE SAMPLED | (40 CFR261.24) | 09/23/2014 | | 09/23/2014 | | 10/02/2014 | | 10/02/2014 | | 10/02/2014 | | 12/19/2014 | | 12/19/2014 | | 12/24/2014 | | 01/29/2016 | | 01/29/2016 | |
| **SA-6 TAL Metals (mg/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | 100 | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| BERYLLIUM | NC | - | | - | | - | | - | | - | | - | | - | | - | | | | | |
| CADMIUM | 1 | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| CHROMIUM | 5 | 0.05 | U | 0.11 | J | **8.4** | | **5.1** | | 3.5 | | 0.15 | | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| LEAD | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| SELENIUM | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | 5 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per liter (mg/L)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7H

## Concrete Sample Results – SPLP

Study Area 6 South

Hudson County, New Jersey

| | | 087-WC | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 087-WC-C10-091113 | | 087-WC-C11-091113 | | 087-WC-C12-091113 | | 087-WC-C13-091113 | | 087-WC-C14-091113 | | 087-WC-C15-091113 | | 087-WC-C16-091113 | | 087-WC-C17-091113 | | 087-WC-C18-091113 | | 087-WC-C01-091113 | | 087-WC-C02-091113 | | 087-WC-C03-091113 | |
| LAB SAMPLE ID | NJ_Default Leachate | JB47199-10A/10B | | JB47199-11A/11B | | JB47199-12A/12B | | JB47199-13A/13B | | JB47199-14A/14B | | JB47199-15A/15B | | JB47199-16A/16B | | JB47199-17A/17B | | JB47199-18A/18B | | JB47199-1A/1B | | JB47199-2A/2B | | JB47199-3A/3B | |
| DATE SAMPLED | Criteria for Class II GW | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | |
| **SA-6 TAL Metals (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 3 | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* |
| BARIUM | 120000 | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U |
| BERYLLIUM | 20 | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U |
| CADMIUM | 80 | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U |
| CHROMIUM | NC | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| LEAD | 100 | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* |
| MERCURY | 40 | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U |
| NICKEL | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| SELENIUM | 800 | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U |
| SILVER | 800 | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| **SA-6 PCB/Pesticide/Herbicide (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | 0.04 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | 6 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 GC/MS Semi-Volatiles (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ISOPHORONE | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ Default Leachate Criteria for Class II Groundwater

NC: No criterion established

**Bold and underlined concentrations exceed the criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in micrograms per liter (ug/L)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7H
## Concrete Sample Results – SPLP
Study Area 6 South
Hudson County, New Jersey

| | | 087-WC | | | | | | | | | | | | 124-WC | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 087-WC-C04-091113 | | 087-WC-C05-091113 | | 087-WC-C06-091113 | | 087-WC-C07-091113 | | 087-WC-C08-091113 | | 087-WC-C09-091113 | | 124-WC-C02-091713 | | 124-WC-C11A-022514 | | 124-WC-C11B-022514 | | 124-WC-C11C-022514 | | 124-WC-C13A-022514 | | 124-WC-C13B-022514 | |
| LAB SAMPLE ID | NJ_Default Leachate | JB47199-4A/4B | | JB47199-5A/5B | | JB47199-6A/6B | | JB47199-7A/7B | | JB47199-8A/8B | | JB47199-9A/9B | | JB47734-2R | | JB60536-1 | | JB60536-2 | | JB60536-3 | | JB60536-4 | | JB60536-5 | |
| DATE SAMPLED | Criteria for Class II GW | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/11/2013 | | 09/17/2013 | | 02/25/2014 | | 02/25/2014 | | 02/25/2014 | | 02/25/2014 | | 02/25/2014 | |
| **SA-6 TAL Metals (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 3 | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | 3 | U | - | | - | | - | | - | | - | |
| BARIUM | 120000 | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | - | | - | | - | | - | | - | | - | |
| BERYLLIUM | 20 | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | - | | - | |
| CADMIUM | 80 | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | - | | - | | - | | - | | - | | - | |
| CHROMIUM | NC | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | - | | - | | - | | - | | - | | - | |
| LEAD | 100 | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | *500* | *U* | - | | - | | - | | - | | 50 | U | 50 | U |
| MERCURY | 40 | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | - | | - | | - | | - | | - | | - | |
| NICKEL | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| SELENIUM | 800 | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | 500 | U | - | | - | | - | | - | | - | | - | |
| SILVER | 800 | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | - | | - | | - | | - | | - | | - | |
| **SA-6 PCB/Pesticide/Herbicide (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | 0.04 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | 6 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.3 | U | 0.3 | U |
| **SA-6 GC/MS Semi-Volatiles (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ISOPHORONE | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:
TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)
NJ Default Leachate Criteria for Class II Groundwater
NC: No criterion established
**Bold and underlined concentrations exceed the criteria**
*Italicized values not detected; reporting limit exceeds criteria*
Depths reported in feet below ground surface
CONC: Concentration reported in micrograms per liter (ug/L)
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7H

## Concrete Sample Results – SPLP

Study Area 6 South

Hudson County, New Jersey

| | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 124-WC-C13C-022514 | | 124-WC-C18a-042214 | | 124-WC-C18b-042214 | | 124-WC-C18c-042214 | | 124-WC-C19a-042214 | | 124-WC-C19b-042214 | | 124-WC-C19c-042214 | | 124-WC-C20a-042214 | | 124-WC-C20b-042214 | | 124-WC-C20c-042214 | | 124-WC-C21a-060214 | | 124-WC-C21b-060214 | |
| LAB SAMPLE ID | NJ_Default Leachate | JB60536-6 | | JB65319-1 | | JB65319-2 | | JB65319-3 | | JB65319-4 | | JB65319-5 | | JB65319-6 | | JB65319-7 | | JB65319-8 | | JB65319-9 | | JB68222-1 | | JB68222-2 | |
| DATE SAMPLED | Criteria for Class II GW | 02/25/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 06/02/2014 | | 06/02/2014 | |
| **SA-6 TAL Metals (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BARIUM | 120000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BERYLLIUM | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CADMIUM | 80 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHROMIUM | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| LEAD | 100 | 50 | U | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| MERCURY | 40 | - | | 0.26 | | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.44 | | - | | - | |
| NICKEL | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| SELENIUM | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| SILVER | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 PCB/Pesticide/Herbicide (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | 0.04 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | 6 | 0.3 | U | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 GC/MS Semi-Volatiles (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ISOPHORONE | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 2 | U | 2 | U |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ Default Leachate Criteria for Class II Groundwater

NC: No criterion established

**Bold and underlined concentrations exceed the criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in micrograms per liter (ug/L)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7H

## Concrete Sample Results – SPLP

Study Area 6 South

Hudson County, New Jersey

| | | 124-WC | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | | 124-WC-C21c-060214 | | 124-WC-C22a-061014 | | 124-WC-C22b-061014 | | 124-WC-C22c-061014 | | 124-WC-C23a-061014 | | 124-WC-C23b-061014 | | 124-WC-C23c-061014 | | 124-WC-C24a-061014 | | 124-WC-C24b-061014 | | 124-WC-C24c-061014 | | 124-WC-C27a-080514 | | 124-WC-C27b-080514 | |
| LAB SAMPLE ID | NJ_Default Leachate | JB68222-3 | | JB68879-1 | | JB68879-2 | | JB68879-3 | | JB68879-4 | | JB68879-5 | | JB68879-6 | | JB68879-7 | | JB68879-8 | | JB68879-9 | | JB73271-1 | | JB73271-2 | |
| DATE SAMPLED | Criteria for Class II GW | 06/02/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 06/10/2014 | | 08/05/2014 | | 08/05/2014 | |
| **SA-6 TAL Metals (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BARIUM | 120000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BERYLLIUM | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 5 | U | 5 | U |
| CADMIUM | 80 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHROMIUM | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| LEAD | 100 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| MERCURY | 40 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| NICKEL | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| SELENIUM | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| SILVER | 800 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 PCB/Pesticide/Herbicide (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | 0.04 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | 6 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 GC/MS Semi-Volatiles (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ISOPHORONE | 800 | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | 2 | U | - | | - | |

Notes:

TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)

NJ Default Leachate Criteria for Class II Groundwater

NC: No criterion established

**Bold and underlined concentrations exceed the criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in micrograms per liter (ug/L)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 7H

## Concrete Sample Results – SPLP

Study Area 6 South

Hudson County, New Jersey

| | | 124-WC | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CLIENT SAMPLE ID | NJ_Default Leachate Criteria for Class II GW | 124-WC-C27c-080514 | | 124-WC-C30a-092914 | | 124-WC-C30b-092914 | | 124-WC-C30c-092914 | | 124-WC-C31a-092914 | | 124-WC-C31b-092914 | | 124-WC-C31c-092914 | |
| LAB SAMPLE ID | | JB73271-3 | | JB77877-1 | | JB77877-2 | | JB77877-3 | | JB77877-4 | | JB77877-5 | | JB77877-6 | |
| DATE SAMPLED | | 08/05/2014 | | 09/29/2014 | | 09/29/2014 | | 09/29/2014 | | 09/29/2014 | | 09/29/2014 | | 09/29/2014 | |
| **SA-6 TAL Metals (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | 3 | - | | - | | - | | - | | - | | - | | - | |
| BARIUM | 120000 | - | | - | | - | | - | | - | | - | | - | |
| BERYLLIUM | 20 | 5 | U | - | | - | | - | | - | | - | | - | |
| CADMIUM | 80 | - | | - | | - | | - | | - | | - | | - | |
| CHROMIUM | NC | - | | - | | - | | - | | - | | - | | - | |
| LEAD | 100 | - | | - | | - | | - | | - | | - | | - | |
| MERCURY | 40 | - | | - | | - | | - | | - | | - | | - | |
| NICKEL | 2000 | - | | - | | - | | - | | 10 | U | 10 | U | 10 | U |
| SELENIUM | 800 | - | | - | | - | | - | | - | | - | | - | |
| SILVER | 800 | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 PCB/Pesticide/Herbicide (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | 0.5 | - | | 0.5 | U | 0.5 | U | 0.5 | U | - | | - | | - | |
| DIELDRIN | 0.04 | - | | 0.01 | U | 0.01 | U | 0.01 | U | - | | - | | - | |
| PENTACHLOROPHENOL | 6 | - | | - | | - | | - | | - | | - | | - | |
| **SA-6 GC/MS Semi-Volatiles (ug/L)** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ISOPHORONE | 800 | - | | - | | - | | - | | - | | - | | - | |

Notes:
TAL: Target Analyte List; hexavalent chromium results included for comparison (see Table 1 for full results)
NJ Default Leachate Criteria for Class II Groundwater
NC: No criterion established
**Bold and underlined concentrations exceed the criteria**
*Italicized values not detected; reporting limit exceeds criteria*
Depths reported in feet below ground surface
CONC: Concentration reported in micrograms per liter (ug/L)
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit



Prepared by: DP 02/15/2016
Reviewed by: JD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-200 | | 163-SB-201 | | 163-SB-202 | | 163-SB-203 | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-200 | 163-SB-200 | 163-SB-201 | 163-SB-201 | 163-SB-202 | 163-SB-202 | 163-SB-203 | 163-SB-203 | 163-SB-203 | 163-SB-203 |
| Client Sample ID | | | 163-SB-200-1213 | 163-SB-200-1314 | 163-SB-201-1415 | 163-SB-201-1516 | 163-SB-202-1415 | 163-SB-202-1516 | 163-SB-203-1011 | 163-SB-203-1112 | 163-SB-203-1213 | 163-SB-203-1314 |
| Lab Sample ID | | | JB92370-1R | JB92370-2R | JB92370-3R | JB92370-4R | JB92370-5 | JB92370-6R | JB92370-7R | JB92370-8R | JB92370-9R | JB92370-10R |
| Date Sampled | | NJ 2012 MOST | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 | 04/14/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 9.9 | 10.6 | **21.1** | 16.4 | 14.3 | **22.1** | 6.2 | 9.2 | 14.8 | 11.3 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-204 | | | | 163-SB-205 | | | | 163-SB-206 | | 163-SB-207 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-204 | 163-SB-204 | 163-SB-204 | 163-SB-204 | 163-SB-205 | 163-SB-205 | 163-SB-205 | 163-SB-205 | 163-SB-206 | 163-SB-206 | 163-SB-207 | 163-SB-207 |
| Client Sample ID | | | 163-SB-204-1112 | 163-SB-204-1213 | 163-SB-204-1314 | 163-SB-204-1415 | 163-SB-205-1112 | 163-SB-205-1213 | 163-SB-205-1314 | 163-SB-205-1415 | 163-SB-206-1112 | 163-SB-206-1213 | 163-SB-207-1213 | 163-SB-207-1314 |
| Lab Sample ID | | | JB92370-12 | JB92776-29 | JB92370-14R | JB92776-30 | JB92370-16R | JB92776-31 | JB92370-18R | JB92776-32R | JB92370-20R | JB92776-33 | JB92512-1R | JB92512-2R |
| Date Sampled | | NJ 2012 MOST | 04/14/2015 | 04/17/2015 | 04/14/2015 | 04/17/2015 | 04/14/2015 | 04/17/2015 | 04/14/2015 | 04/17/2015 | 04/14/2015 | 04/17/2015 | 04/15/2015 | 04/15/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 2.0 | 13.8 | 9.7 | 15.7 | 2.6 | 7.9 | 16.6 | **64.6** | 14.1 | 16.7 | 14.6 | 13.7 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016
Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-208 | | 163-SB-209 | | 163-SB-210 | | 163-SB-211 | | 163-SB-212 | | 163-SB-213 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-208 | 163-SB-208 | 163-SB-209 | 163-SB-209 | 163-SB-210 | 163-SB-210 | 163-SB-211 | 163-SB-211 | 163-SB-212 | 163-SB-212 | 163-SB-213 | 163-SB-213 |
| Client Sample ID | | | 163-SB-208-1213 | 163-SB-208-1314 | 163-SB-209-1112 | 163-SB-209-1213 | 163-SB-210-1112 | 163-SB-210-1213 | 163-SB-211-1112 | 163-SB-211-1213 | 163-SB-212-1112 | 163-SB-212-1213 | 163-SB-213-1112 | 163-SB-213-1213 |
| Lab Sample ID | | | JB92512-3R | JB92512-4 | JB92776-34 | JB92512-5 | JB92776-35R | JB92512-7R | JB92776-36R | JB92512-9 | JB92776-37R | JB92512-11R | JB92776-38 | JB92512-13R |
| Date Sampled | | NJ 2012 MOST | 04/15/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 2.6 U | 1.3 J | 2.5 U | 0.70 | 14.5 | **23.1** | 13.6 | 0.96 | **44.5** | 11.2 | **24.0** | 10.8 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-214 | | 163-SB-215 | | 163-SB-216 | | 163-SB-217 | | 163-SB-218 | | 163-SB-219 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-214 | 163-SB-214 | 163-SB-215 | 163-SB-215 | 163-SB-216 | 163-SB-216 | 163-SB-217 | 163-SB-217 | 163-SB-218 | 163-SB-218 | 163-SB-219 | 163-SB-219 |
| Client Sample ID | | | 163-SB-214-1213 | 163-SB-214-1314 | 163-SB-215-1314 | 163-SB-215-1415 | 163-SB-216-1314 | 163-SB-216-1415 | 163-SB-217-0809 | 163-SB-217-0910 | 163-SB-218-0809 | 163-SB-218-0910 | 163-SB-219-0304 | 163-SB-219-0405 |
| Lab Sample ID | | | JB92512-15R | JB92512-16 | JB92776-39R | JB92512-17 | JB92776-40 | JB92512-19 | JB92776-1 | JB92776-2 | JB92776-3 | JB92776-4R | JB92776-5R | JB92776-6R |
| Date Sampled | | NJ 2012 MOST | 04/15/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 | 04/17/2015 | 04/15/2015 | 04/17/2015 | 04/17/2015 | 04/17/2015 | 04/17/2015 | 04/17/2015 | 04/16/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 3.7 | 3.8 | 1.8 | 2.4 | 0.83 | 0.68 | 6.2 J | **22.5 J** | 11.9 J | 7.2 | 0.97 | 2.0 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-220 | | 163-SB-221 | | 163-SB-222 | | 163-SB-223 | | 163-SB-224 | | 163-SB-225 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-220 | 163-SB-220 | 163-SB-221 | 163-SB-221 | 163-SB-222 | 163-SB-222 | 163-SB-223 | 163-SB-223 | 163-SB-224 | 163-SB-224 | 163-SB-225 | 163-SB-225 |
| Client Sample ID | | | 163-SB-220-0304 | 163-SB-220-0405 | 163-SB-221-0405 | 163-SB-221-0506 | 163-SB-222-0304 | 163-SB-222-0405 | 163-SB-223-0304 | 163-SB-223-0405 | 163-SB-224-0607 | 163-SB-224-0708 | 163-SB-225-0607 | 163-SB-225-0708 |
| Lab Sample ID | | | JB92776-7R | JB92776-8R | JB92776-9 | JB92776-10 | JB92776-11 | JB92776-12 | JB92776-13R | JB92776-14 | JB92776-15 | JB92776-16 | JB92776-17 | JB92776-18 |
| Date Sampled | | NJ 2012 MOST | 04/17/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/17/2015 | 04/16/2015 | 04/17/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 3.5 | 1.4 | 9.7 | 3.7 | 2.4 | 0.80 | 1.6 | 2.0 | 17.0 | 17.7 | 0.51 U | 0.53 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-226 | | 163-SB-227 | | 163-SB-228 | | 163-SB-229 | | 163-SB-230 | | 163-SB-231 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-226 | 163-SB-226 | 163-SB-227 | 163-SB-227 | 163-SB-228 | 163-SB-228 | 163-SB-229 | 163-SB-229 | 163-SB-230 | 163-SB-230 | 163-SB-231 | 163-SB-231 |
| Client Sample ID | | | 163-SB-226-1617 | 163-SB-226-1718 | 163-SB-227-0708 | 163-SB-227-0809 | 163-SB-228-0607 | 163-SB-228-0708 | 163-SB-229-0809 | 163-SB-229-0910 | 163-SB-230-1012 | 163-SB-230-1113 | 163-SB-231-1213 | 163-SB-231-1314 |
| Lab Sample ID | | | JB92776-19 | JB92776-20R | JB92776-21R | JB92776-22 | JB92776-23R | JB92776-24 | JB92776-25R | JB92776-26 | JB92776-27R | JB92776-28 | JB92822-1 | JB92822-2R |
| Date Sampled | | NJ 2012 MOST | 04/16/2015 | 04/16/2015 | 04/17/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/16/2015 | 04/20/2015 | 04/20/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 1.4 | 5.7 | 16.9 | 8.3 | 8.4 | 8.4 | **57.2** | **79.3** | **27.7** | **40.7** | **27.6** J | **23.8** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-232 | | 163-SB-233 | | 163-SB-234 | | 163-SB-235 | | 163-SB-236 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-232 | 163-SB-232 | 163-SB-233 | 163-SB-233 | 163-SB-234 | 163-SB-234 | 163-SB-235 | 163-SB-235 | 163-SB-236 | 163-SB-236 |
| Client Sample ID | | | 163-SB-232-1213 | 163-SB-232-1314 | 163-SB-233-1112 | 163-SB-233-1213 | 163-SB-234-1112 | 163-SB-234-1213 | 163-SB-235-1112 | 163-SB-235-1213 | 163-SB-236-1112 | 163-SB-236-1213 |
| Lab Sample ID | | | JB92822-3 | JB92822-4 | JB92822-5R | JB92822-6 | JB92822-7 | JB92822-8 | JB92822-9 | JB92822-10R | JB92822-11R | JB92822-12 |
| Date Sampled | | NJ 2012 MOST | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | **39.2** J | **36.1** J | **68.0** | 4.3 | **102** | **22.2** | **53.3** | **31.0** | **50.6** | 11.5 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-237 | | | | 163-SB-238 | | | | 163-SB-239 | | 163-SB-240 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-237 | 163-SB-237 | 163-SB-237 | 163-SB-237 | 163-SB-238 | 163-SB-238 | 163-SB-238 | 163-SB-238 | 163-SB-239 | 163-SB-239 | 163-SB-240 | 163-SB-240 |
| Client Sample ID | | | 163-SB-237-1112 | 163-SB-237-1213 | 163-SB-237-1314 | 163-SB-237-1415 | 163-SB-238-1112 | 163-SB-238-1213 | 163-SB-238-1314 | 163-SB-238-1415 | 163-SB-239-1112 | 163-SB-239-1213 | 163-SB-240-1415 | 163-SB-240-1516 |
| Lab Sample ID | | | JB92822-13 | JB92822-14R | JB92822-15 | JB92822-16 | JB92881-1R | JB92881-2R | JB92881-3R | JB92881-4R | JB92881-5R | JB92881-6R | JB92881-7R | JB92881-8R |
| Date Sampled | | NJ 2012 MOST | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/20/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | **34.3** | **38.7** | **31.3** | **80.6** | 11.2 | 5.0 | 18.4 | **31.6** | 17.9 | **36.8** | **27.2** | 13.1 |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-241 | | 163-SB-242 | | 163-SB-243 | | 163-SB-244 | | 163-SB-245 | | 163-SB-246 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-241 | 163-SB-241 | 163-SB-242 | 163-SB-242 | 163-SB-243 | 163-SB-243 | 163-SB-244 | 163-SB-244 | 163-SB-245 | 163-SB-245 | 163-SB-246 | 163-SB-246 |
| Client Sample ID | | | 163-SB-241-1213 | 163-SB-241-1314 | 163-SB-242-1415 | 163-SB-242-1516 | 163-SB-243-0809 | 163-SB-243-0910 | 163-SB-244-0809 | 163-SB-244-0910 | 163-SB-245-1314 | 163-SB-245-1415 | 163-SB-246-0809 | 163-SB-246-0910 |
| Lab Sample ID | | | JB92881-9R | JB92881-10R | JB92881-11R | JB92881-12R | JB92881-13R | JB92881-14R | JB92881-15R | JB92881-16 | JB92881-17R | JB92881-18 | JB92881-19R | JB92881-20R |
| Date Sampled | | NJ 2012 MOST | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 | 04/21/2015 |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q |
| HEXAVALENT CHROMIUM | mg/kg | 20 | **22.2** | **30.6** | **27.3** | **92.5** | 4.2 | 9.9 | **34.9** | **22.3** | 1.9 U | 2.4 | **44.5** | **39.7** |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 8

## Site 163 In-Situ Soil Samples

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | | 163-SB-247 | | 163-SB-248 | | 163-SB-249 | | 163-SB-250 | | 163-SB-251 | | 163-SB-252 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | | | 163-SB-247 | 163-SB-247 | 163-SB-248 | 163-SB-248 | 163-SB-249 | 163-SB-249 | 163-SB-250 | 163-SB-250 | 163-SB-251 | 163-SB-251 | 163-SB-252 | |
| Client Sample ID | | | 163-SB-247-0809 | 163-SB-247-0910 | 163-SB-248-0304 | 163-SB-248-0405 | 163-SB-249-0304 | 163-SB-249-0405 | 163-SB-250-0607 | 163-SB-250-0708 | 163-SB-251-0304 | 163-SB-251-0405 | 163-SB-252-0201 | |
| Lab Sample ID | | | JB92948-1 | JB92948-2 | JB92948-3 | JB92948-4 | JB92948-5 | JB92948-6 | JB92948-7 | JB92948-8R | JB92948-9 | JB92948-10 | JC6658-1R | |
| Date Sampled | | NJ 2012 MOST | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 04/22/2015 | 10/20/2015 | |
| Parameter Name | Units | STRINGENT SRS | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | CONC Q | |
| HEXAVALENT CHROMIUM | mg/kg | 20 | 7.7 | 4.2 | 1.9 | 0.75 | 9.9 | 15.0 | 0.51 U | 0.64 | 17.1 | 9.0 | 12.4 J | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediatic

**Bold and shaded concentrations exceed the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 1-7 | <20 | 7-20-a (A1) | 500 | 124-7-20-a1 | 10/31/2013 | 5.8 | Yes | | |
| | | | | 124-7-20-a2 | 10/31/2013 | 7.8 | Yes | | |
| | | | | 124-7-20-a3 | 10/31/2013 | 4.6 | Yes | | |
| | | | | 124-7-20-a4 | 10/31/2013 | 4.7 | Yes | | |
| 7-12 | <20 | 12-20-a, b (A2) & (A3) | 1000 | 124-12-20-a1 | 11/26/2013 | 26.1 | | Yes | |
| | | | | 124-12-20-a2 | 11/26/2013 | 2.9 | Yes | | |
| | | | | 124-12-20-a3 | 11/26/2013 | 7.8 | Yes | | |
| | | | | 124-12-20-a4 | 11/26/2013 | 23.2 | | Yes | |
| | | | | 124-12-20-b1 | 11/26/2013 | 4.3 | Yes | | |
| | | | | 124-12-20-b2 | 11/26/2013 | 2.5 | Yes | | |
| | | | | 124-12-20-b3 | 11/26/2013 | 5.1 | Yes | | |
| | | | | 124-12-20-b4 | 11/26/2013 | 5.8 | Yes | | |
| 12-22 | <20 | 22-20-a (A4) & (A5) | 600 | 124-22-20-a1 | 12/13/2013 | 5.5 | Yes | | |
| | | | | 124-22-20-a2 | 12/13/2013 | 11.9 | Yes | | |
| | | | | 124-22-20-a3 | 12/13/2013 | 1.3 | Yes | | |
| | | | | 124-22-20-a4 | 12/13/2013 | 2.3 | Yes | | |
| 12-25 | <20 | 25-20-a (A6) | 1000 | 124-25-20-a1 | 12/23/2013 | 1.6 | Yes | | |
| | | | | 124-25-20-a2 | 12/23/2013 | 1.7 | Yes | | |
| | | | | 124-25-20-a3 | 12/23/2013 | 10.8 | Yes | | |
| | | | | 124-25-20-a4 | 12/23/2013 | 17.4 | Yes | | |
| 20-29 | <20 | 29-20-a (A8) | 500 | 124-29-20-a1 | 1/13/2014 | 0.31 | Yes | | |
| | | | | 124-29-20-a2 | 1/13/2014 | 0.84 | Yes | | |
| | | | | 124-29-20-a3 | 1/13/2014 | 3.4 | Yes | | |
| | | | | 124-29-20-a4 | 1/13/2014 | 1.9 | Yes | | |
| 30-41 | >1000 | 41-1000-a | 750 | 124-41-1000-a1 | 2/25/2014 | 1,750 | | | Yes |
| | | | | 124-41-1000-a2 | 2/25/2014 | 3,690 | | | Yes |
| | | | | 124-41-1000-a3 | 2/25/2014 | 3,410 | | | Yes |
| | | | | 124-41-1000-a4 | 2/25/2014 | 453 | | Yes | |
| 30-41 | >1000 | 41-1000-b | 750 | 124-41-1000-b1 | 2/25/2014 | 490 | | Yes | |
| | | | | 124-41-1000-b2 | 2/25/2014 | 1,110 | | | Yes |
| | | | | 124-41-1000-b3 | 2/25/2014 | 669 | | Yes | |
| | | | | 124-41-1000-b4 | 2/25/2014 | 1,920 | | | Yes |
| 37-46 | <20 | 46-20-a & b (A10) | 1500 | 124-46-20-a1 | 3/12/2014 | 3.2 | Yes | | |
| | | | | 124-46-20-a2 | 3/12/2014 | 2.2 | Yes | | |
| | | | | 124-46-20-a3 | 3/12/2014 | 3.9 | Yes | | |
| | | | | 124-46-20-a4 | 3/12/2014 | 2 | Yes | | |
| | | | | 124-46-20-b1 | 3/12/2014 | 2.9 | Yes | | |
| | | | | 124-46-20-b2 | 3/12/2014 | 3.8 | Yes | | |
| | | | | 124-46-20-b3 | 3/12/2014 | 2.2 | Yes | | |
| | | | | 124-46-20-b4 | 3/12/2014 | 2.6 | Yes | | |
| 41-49 | >1000 | 124-49-1000-a | 1000 | 124-49-1000-a1 | 3/24/2014 | 3490 | | | Yes |
| | | | | 124-49-1000-a2 | 3/24/2014 | 3850 | | | Yes |
| | | | | 124-49-1000-a3 | 3/24/2014 | 2580 | | | Yes |
| | | | | 124-49-1000-a4 | 3/24/2014 | 5570 | | | Yes |

Prepared by JD 05/01/2016

Reviewed by NW 05/15/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 41-49 | >1000 | 124-49-1000-b | 1000 | 124-49-1000-b1 | 3/24/2014 | 8840 | | | Yes |
| | | | | 124-49-1000-b2 | 3/24/2014 | 2340 | | | Yes |
| | | | | 124-49-1000-b3 | 3/24/2014 | 2 | | Yes | |
| | | | | 124-49-1000-b4 | 3/24/2014 | 4250 | | | Yes |
| 47-57 | <20 | 124-57-20-a, b, & c (A11) | 2580 | 124-57-20-a1 | 4/4/2014 | 17.0 | Yes | | |
| | | | | 124-57-20-a2 | 4/4/2014 | 3.8 | Yes | | |
| | | | | 124-57-20-a3 | 4/4/2014 | 4.2 | Yes | | |
| | | | | 124-57-20-a4 | 4/4/2014 | <.52 | Yes | | |
| | | | | 124-57-20-b1 | 4/4/2014 | 4.1 | Yes | | |
| | | | | 124-57-20-b2 | 4/4/2014 | 14.2 | Yes | | |
| | | | | 124-57-20-b3 | 4/4/2014 | 15.7 | Yes | | |
| | | | | 124-57-20-b4 | 4/4/2014 | <.49 | Yes | | |
| | | | | 124-57-20-c1 | 4/4/2014 | 10.3 | Yes | | |
| | | | | 124-57-20-c2 | 4/4/2014 | 11.6 | Yes | | |
| | | | | 124-57-20-c3 | 4/4/2014 | 8.9 | Yes | | |
| | | | | 124-57-20-c4 | 4/4/2014 | 41.4 | | Yes | |
| 49-59 | >1000 | 124-59-1000-a | 800 | 124-59-1000-a1 | 4/11/2014 | 11,000 | | | Yes |
| | | | | 124-59-1000-a2 | 4/11/2014 | 26,900 | | | Yes |
| | | | | 124-59-1000-a3 | 4/11/2014 | 11,900 | | | Yes |
| | | | | 124-59-1000-a4 | 4/11/2014 | 32,700 | | | Yes |
| 57,58 144-152 | <20 | 124-152-20-a (A12) | 800 | 124-152-20-a1 | 4/23/2014 | 0.73 | Yes | | |
| | | | | 124-152-20-a2 | 4/23/2014 | 0.76 | Yes | | |
| | | | | 124-152-20-a3 | 4/23/2014 | 0.42 | Yes | | |
| | | | | 124-152-20-a4 | 4/23/2014 | 1.2 | Yes | | |
| 135,141,143-145 | <20 | 124-145-20-a (A13) | 675 | 124-145-20-a1 | 5/9/2014 | 22.8 | | Yes | |
| | | | | 124-145-20-a2 | 5/9/2014 | 0.4 | Yes | | |
| | | | | 124-145-20-a3 | 5/9/2014 | 5.4 | Yes | | |
| | | | | 124-145-20-a4 | 5/9/2014 | 3.0 | Yes | | |
| 139-142B, 131-132A | <20 | 124-142-20-a (A14) | 1000 | 124-142-20-a1 | 5/15/2014 | 2.1 | Yes | | |
| | | | | 124-142-20-a2 | 5/15/2014 | 8.7 | Yes | | |
| | | | | 124-142-20-a3 | 5/15/2014 | 5.9 | Yes | | |
| | | | | 124-142-20-a4 | 5/15/2014 | 4.3 | Yes | | |

Prepared by JD 05/01/2016
Reviewed by NW 05/15/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 135-138B, 131A | <20 | 124-138-20-a, b (A15) | 1500 | 124-138-20-a1 | 5/19/2014 | 4.0 | Yes | | |
| | | | | 124-138-20-a2 | 5/19/2014 | 10.2 | Yes | | |
| | | | | 124-138-20-a3 | 5/19/2014 | 5.7 | Yes | | |
| | | | | 124-138-20-a4 | 5/19/2014 | 3.9 | Yes | | |
| | | | | 124-138-20-b1 | 5/19/2014 | 1.2 | Yes | | |
| | | | | 124-138-20-b2 | 5/19/2014 | 4.9 | Yes | | |
| | | | | 124-138-20-b3 | 5/19/2014 | 2.7 | Yes | | |
| | | | | 124-138-20-b4 | 5/19/2014 | 5.4 | Yes | | |
| 129-134 | <20 | 124-134-20-a, b (A16) | 1250 | 124-134-20-a1 | 5/21/2014 | 7.5 | Yes | | |
| | | | | 124-134-20-a2 | 5/21/2014 | 7.8 | Yes | | |
| | | | | 124-134-20-a3 | 5/21/2014 | 4.2 | Yes | | |
| | | | | 124-134-20-a4 | 5/21/2014 | 30.5 | | Yes | |
| | | | | 124-134-20-b1 | 5/21/2014 | 10.7 | Yes | | |
| | | | | 124-134-20-b2 | 5/21/2014 | 2.5 | Yes | | |
| | | | | 124-134-20-b3 | 5/21/2014 | 4.9 | Yes | | |
| | | | | 124-134-20-b4 | 5/21/2014 | 7.3 | Yes | | |
| 126-128 | <20 | 124-128-20-a (A17) | 1000 | 124-128-20-a1 | 6/3/2014 | 32.4 | | Yes | |
| | | | | 124-128-20-a2 | 6/3/2014 | 38.4 | | Yes | |
| | | | | 124-128-20-a3 | 6/3/2014 | 17.0 | Yes | | |
| | | | | 124-128-20-a4 | 6/3/2014 | 45.1 | | Yes | |
| 124-126 | <20 | 124-126-20-a, b (A18) | 1450 | 124-126-20-a1 | 6/13/2014 | 41.1 | | Yes | |
| | | | | 124-126-20-a2 | 6/13/2014 | 13.9 | Yes | | |
| | | | | 124-126-20-a3 | 6/13/2014 | 15.0 | Yes | | |
| | | | | 124-126-20-a4 | 6/13/2014 | 2.9 | Yes | | |
| | | | | 124-126-20-b1 | 6/13/2014 | 12.9 | Yes | | |
| | | | | 124-126-20-b2 | 6/13/2014 | 8.6 | Yes | | |
| | | | | 124-126-20-b3 | 6/13/2014 | 59.4 | | Yes | |
| | | | | 124-126-20-b4 | 6/13/2014 | 8.0 | Yes | | |
| 119-124 | <20 | 124-124-20-a, b (A19) | 2000 | 124-124-20-a1 | 6/25/2014 | 11.2 | Yes | | |
| | | | | 124-124-20-a2 | 6/25/2014 | 14.6 | Yes | | |
| | | | | 124-124-20-a3 | 6/25/2014 | 12.2 | Yes | | |
| | | | | 124-124-20-a4 | 6/25/2014 | 8.0 | Yes | | |
| | | | | 124-124-20-b1 | 6/25/2014 | 19.4 | Yes | | |
| | | | | 124-124-20-b2 | 6/25/2014 | 4.8 | Yes | | |
| | | | | 124-124-20-b3 | 6/25/2014 | 2.1 | Yes | | |
| | | | | 124-124-20-b4 | 6/25/2014 | 10.5 | Yes | | |
| 119-125 | >1000 | 124-125-1000-a | 550 | 124-125-1000-a1 | 6/25/2014 | 42.1 | | Yes | |
| | | | | 124-125-1000-a2 | 6/25/2014 | 652.0 | | Yes | |
| | | | | 124-125-1000-a3 | 6/25/2014 | 346.0 | | Yes | |
| | | | | 124-125-1000-a4 | 6/25/2014 | 400.0 | | Yes | |

Prepared by JD 05/01/2016
Reviewed by NW 05/15/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 115-119 | <20 | 124-119-20-a (A20) | 1000 | 124-119-20-a1 | 6/27/2014 | 9.6 | Yes | | |
| | | | | 124-119-20-a2 | 6/27/2014 | 7.8 | Yes | | |
| | | | | 124-119-20-a3 | 6/27/2014 | 6.0 | Yes | | |
| | | | | 124-119-20-a4 | 6/27/2014 | 28.8 | | Yes | |
| 110-118 | <20 | 124-118-20-a (A21) | 1000 | 124-118-20-a1 | 7/9/2014 | 20.3 | | Yes | |
| | | | | 124-118-20-a2 | 7/9/2014 | 19.7 | Yes | | |
| | | | | 124-118-20-a3 | 7/9/2014 | 37.1 | | Yes | |
| | | | | 124-118-20-a4 | 7/9/2014 | 61.1 | | Yes | |
| 102-119 | >1000 | 124-119-1000-a | 800 | 124-119-1000-a1 | 7/29/2014 | 174.0 | | Yes | |
| | | | | 124-119-1000-a2 | 7/29/2014 | 302.0 | | Yes | |
| | | | | 124-119-1000-a3 | 7/29/2014 | 149.0 | | Yes | |
| | | | | 124-119-1000-a4 | 7/29/2014 | 2,180.0 | | | Yes |
| 101-112 | <20 | 124-112-20-a,b,c (A22) | 2800 | 124-112-20-a1 | 7/30/2014 | 16.1 | Yes | | |
| | | | | 124-112-20-a2 | 7/30/2014 | 6.7 | Yes | | |
| | | | | 124-112-20-a3 | 7/30/2014 | 8.7 | Yes | | |
| | | | | 124-112-20-a4 | 7/30/2014 | 11.0 | Yes | | |
| | | | | 124-112-20-b1 | 7/30/2014 | 2.4 | Yes | | |
| | | | | 124-112-20-b2 | 7/30/2014 | 2.6 | Yes | | |
| | | | | 124-112-20-b3 | 7/30/2014 | 14.7 | Yes | | |
| | | | | 124-112-20-b4 | 7/30/2014 | 1.6 | Yes | | |
| | | | | 124-112-20-c1 | 7/30/2014 | 24.0 | | Yes | |
| | | | | 124-112-20-c2 | 7/30/2014 | 3.4 | Yes | | |
| | | | | 124-112-20-c3 | 7/30/2014 | 6.0 | Yes | | |
| | | | | 124-112-20-c4 | 7/30/2014 | 2.6 | Yes | | |
| 92-102 | >1000 | 124-102-1000-a,b | 2100 | 124-102-1000-a1 | 8/14/2014 | 1,680 | | | Yes |
| | | | | 124-102-1000-a2 | 8/14/2014 | 487 | | Yes | |
| | | | | 124-102-1000-a3 | 8/14/2014 | 446 | | Yes | |
| | | | | 124-102-1000-a4 | 8/14/2014 | 299 | | Yes | |
| | | | | 124-102-1000-b1 | 8/14/2014 | 38.4 | | Yes | |
| | | | | 124-102-1000-b2 | 8/14/2014 | 139 | | Yes | |
| | | | | 124-102-1000-b3 | 8/14/2014 | 64.8 | | Yes | |
| | | | | 124-102-1000-b4 | 8/14/2014 | 663 | | Yes | |

Prepared by JD 05/01/2016
Reviewed by NW 05/15/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 88-101 | <20 | 124-101-20-a, b, c (A23) | 2850 | 124-101-20-a1 | 8/22/2014 | 22.4 | | Yes | |
| | | | | 124-101-20-a2 | 8/22/2014 | 13.3 | Yes | | |
| | | | | 124-101-20-a3 | 8/22/2014 | 23.8 | | Yes | |
| | | | | 124-101-20-a4 | 8/22/2014 | 24.6 | | Yes | |
| | | | | 124-101-20-b1 | 8/22/2014 | 22.5 | | Yes | |
| | | | | 124-101-20-b2 | 8/22/2014 | 17.2 | Yes | | |
| | | | | 124-101-20-b3 | 8/22/2014 | 11.5 | Yes | | |
| | | | | 124-101-20-b4 | 8/22/2014 | 21.8 | | Yes | |
| | | | | 124-101-20-c1 | 8/22/2014 | 6.8 | Yes | | |
| | | | | 124-101-20-c2 | 8/22/2014 | 25.0 | | Yes | |
| | | | | 124-101-20-c3 | 8/22/2014 | 13.6 | Yes | | |
| | | | | 124-101-20-c4 | 8/22/2014 | 4.2 | Yes | | |
| 83-88 | <20 | 124-88-20-a,b,c (A24) | 2800 | 124-88-20-a1 | 9/3/2014 | 7.1 | Yes | | |
| | | | | 124-88-20-a2 | 9/3/2014 | 10.9 | Yes | | |
| | | | | 124-88-20-a3 | 9/3/2014 | 15.4 | Yes | | |
| | | | | 124-88-20-a4 | 9/3/2014 | 3.3 | Yes | | |
| | | | | 124-88-20-b1 | 9/3/2014 | 9.6 | Yes | | |
| | | | | 124-88-20-b2 | 9/3/2014 | 26.6 | | Yes | |
| | | | | 124-88-20-b3 | 9/3/2014 | 6.9 | Yes | | |
| | | | | 124-88-20-b4 | 9/3/2014 | 4.4 | Yes | | |
| | | | | 124-88-20-c1 | 9/3/2014 | 18.3 | Yes | | |
| | | | | 124-88-20-c2 | 9/3/2014 | 2.6 | Yes | | |
| | | | | 124-88-20-c3 | 9/3/2014 | 9.4 | Yes | | |
| | | | | 124-88-20-c4 | 9/3/2014 | 16.2 | Yes | | |
| 79-82 | <20 | 124-82-20-a,b,c (A25) | 2800 | 124-82-20-a1 | 9/17/2014 | 23.9 | | Yes | |
| | | | | 124-82-20-a2 | 9/17/2014 | 16.8 | Yes | | |
| | | | | 124-82-20-a3 | 9/17/2014 | 35.3 | | Yes | |
| | | | | 124-82-20-a4 | 9/17/2014 | 12.9 | Yes | | |
| | | | | 124-82-20-b1 | 9/17/2014 | 34.6 | | Yes | |
| | | | | 124-82-20-b2 | 9/17/2014 | 142 | | Yes | |
| | | | | 124-82-20-b3 | 9/17/2014 | 25.4 | | Yes | |
| | | | | 124-82-20-b4 | 9/17/2014 | 12.8 | Yes | | |
| | | | | 124-82-20-c1 | 9/17/2014 | 33.7 | | Yes | |
| | | | | 124-82-20-c2 | 9/17/2014 | 16.5 | Yes | | |
| | | | | 124-82-20-c3 | 9/17/2014 | 26.8 | | Yes | |
| | | | | 124-82-20-c4 | 9/17/2014 | 39.2 | | Yes | |

Prepared by JD 05/01/2016
Reviewed by NW 05/15/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 75-78 | <20 | 124-78-20-a,b,c (A26) | 2300 | 124-78-20-a1 | 9/30/2014 | 9.2 | Yes | | |
| | | | | 124-78-20-a2 | 9/30/2014 | 23.3 | | Yes | |
| | | | | 124-78-20-a3 | 9/30/2014 | 15.3 | Yes | | |
| | | | | 124-78-20-a4 | 9/30/2014 | 11.9 | Yes | | |
| | | | | 124-78-20-b1 | 9/30/2014 | 15.7 | Yes | | |
| | | | | 124-78-20-b2 | 9/30/2014 | 9.3 | Yes | | |
| | | | | 124-78-20-b3 | 9/30/2014 | 25.8 | | Yes | |
| | | | | 124-78-20-b4 | 9/30/2014 | 21.2 | | Yes | |
| | | | | 124-78-20-c1 | 9/30/2014 | 19.5 | Yes | | |
| | | | | 124-78-20-c2 | 9/30/2014 | 20.4 | | Yes | |
| | | | | 124-78-20-c3 | 9/30/2014 | 25.4 | | Yes | |
| | | | | 124-78-20-c4 | 9/30/2014 | 39 | | Yes | |
| 67-75 | <20 | 124-75-20-a,b (A27) | 1200 | 124-75-20-a1 | 10/16/2014 | 9.6 | Yes | | |
| | | | | 124-75-20-a2 | 10/16/2014 | 7.6 | Yes | | |
| | | | | 124-75-20-a3 | 10/16/2014 | 11 | Yes | | |
| | | | | 124-75-20-a4 | 10/16/2014 | 25.3 | | Yes | |
| | | | | 124-75-20-b1 | 10/16/2014 | 17.3 | Yes | | |
| | | | | 124-75-20-b2 | 10/16/2014 | 15.6 | Yes | | |
| | | | | 124-75-20-b3 | 10/16/2014 | 29.3 | | Yes | |
| | | | | 124-75-20-b4 | 10/16/2014 | 65.3 | | Yes | |
| 58-67 | <20 | 124-67-20-a,b (A28) | 1665 | 124-67-20-a1 | 10/28/2014 | 0.45 | Yes | | |
| | | | | 124-67-20-a2 | 10/28/2014 | 98.2 | | Yes | |
| | | | | 124-67-20-a3 | 10/28/2014 | 2.6 | Yes | | |
| | | | | 124-67-20-a4 | 10/28/2014 | 5.2 | Yes | | |
| | | | | 124-67-20-b1 | 10/28/2014 | 71.9 | | Yes | |
| | | | | 124-67-20-b2 | 10/28/2014 | 340 | | Yes | |
| | | | | 124-67-20-b3 | 10/28/2014 | 29.6 | | Yes | |
| | | | | 124-67-20-b4 | 10/28/2014 | 23.3 | | Yes | |
| 75-58 | >1000 | 124-75-1000-a,b | 1600 | 124-75-1000-a1 | 10/29/2014 | 1,410 | | | Yes |
| | | | | 124-75-1000-a2 | 10/29/2014 | 750 | | Yes | |
| | | | | 124-75-1000-a3 | 10/29/2014 | 1,360 | | | Yes |
| | | | | 124-75-1000-a4 | 10/29/2014 | 2,050 | | | Yes |
| | | | | 124-75-1000-b1 | 10/29/2014 | 2,060 | | | Yes |
| | | | | 124-75-1000-b2 | 10/29/2014 | 454 | | Yes | |
| | | | | 124-75-1000-b3 | 10/29/2014 | 591 | | Yes | |
| | | | | 124-75-1000-b4 | 10/29/2014 | 2,860 | | | Yes |
| Site 163 | >1000 | 163-122-1000-a | 850 | 163-122-1000-a1 | 11/18/2014 | 4.5 | | Yes | |
| | | | | 163-122-1000-a2 | 11/12/2014 | 4 | | Yes | |
| | | | | 163-122-1000-a3 | 11/18/2014 | 80.1 | | Yes | |
| | | | | 163-122-1000-a4 | 11/12/2014 | 38.1 | | Yes | |

Prepared by JD 05/01/2016
Reviewed by NW 05/15/2016

# TABLE 9

**Stockpile Tracking Table**

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Hexavalent Chromium Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 103-106 | <20 | 124-106-20-a (A29) | 950 | 124-106-20-a1 | 11/21/2014 | 9.2 | Yes | | |
| | | | | 124-106-20-a2 | 11/21/2014 | 12.1 | Yes | | |
| | | | | 124-106-20-a3 | 11/21/2014 | 15.6 | Yes | | |
| | | | | 124-106-20-a4 | 11/21/2014 | 20 | | Yes | |
| 106-110 | <20 | 124-110-20-a,b,c (A30) | 2400 | 124-110-20-a1 | 12/2/2014 | 25 | | Yes | |
| | | | | 124-110-20-a2 | 12/2/2014 | 44 | | Yes | |
| | | | | 124-110-20-a3 | 12/2/2014 | 29.1 | | Yes | |
| | | | | 124-110-20-a4 | 12/2/2014 | 14.8 | Yes | | |
| | | | | 124-110-20-b1 | 12/2/2014 | 23.1 | | Yes | |
| | | | | 124-110-20-b2 | 12/2/2014 | 12.9 | Yes | | |
| | | | | 124-110-20-b3 | 12/2/2014 | 3 | Yes | | |
| | | | | 124-110-20-b4 | 12/2/2014 | 1.8 | Yes | | |
| | | | | 124-110-20-c1 | 12/2/2014 | 12.9 | Yes | | |
| | | | | 124-110-20-c2 | 12/2/2014 | 15.6 | Yes | | |
| | | | | 124-110-20-c3 | 12/2/2014 | 29.1 | | Yes | |
| | | | | 124-110-20-c4 | 12/2/2014 | 179 | | Yes | |
| 110-114 | <20 | 124-114-20-a (A31) | 1000 | 124-114-20-a1 | 12/16/2014 | 29.8 | | Yes | |
| | | | | 124-114-20-a2 | 12/16/2014 | 34.5 | | Yes | |
| | | | | 124-114-20-a3 | 12/16/2014 | 49.3 | | Yes | |
| | | | | 124-114-20-a4 | 12/16/2014 | 19.9 | Yes | | |
| Site 41 | <20 | 124-114-20-b | 135 | 124-114-20-b1 | 12/16/2014 | 10.6 | Yes | | |
| 110-114 | >1,000 | 124-114-1000-a (East D 6) | 625 | 124-114-1000-a1 | 12/16/2014 | 42.3 | | Yes | |
| | | | | 124-114-1000-a2 | 12/16/2014 | 65 | | Yes | |
| | | | | 124-114-1000-a3 | 12/16/2014 | 75.3 | | Yes | |
| | | | | 124-114-1000-a4 | 12/16/2014 | 16.5 | | Yes | |
| Site 163 | <20 | 163-20-a | 840 | 163-20-a1 | 1/19/2016 | 8.1 | Yes | | |
| | | | | 163-20-a2 | 1/19/2016 | 4.0 | Yes | | |
| | | | | 163-20-a3 | 1/19/2016 | 1.7 | Yes | | |
| | | | | 163-20-a4 | 1/19/2016 | 5.0 | Yes | | |
| Site 163 | <20 | 163-20-a5:a8 | 840 | 163-20-a5 | 2/22/2016 | 2.7 | Yes | | |
| | | | | 163-20-a6 | 2/22/2016 | 3.6 | Yes | | |
| | | | | 163-20-a7 | 2/22/2016 | 1.0 | Yes | | |
| | | | | 163-20-a8 | 2/22/2016 | 5.1 | Yes | | |

mg/kg = milligrams per kilogram

*Material placement locations are approximate and based on concentrations in mg/kg.

Prepared by JD 05/01/2016

Reviewed by NW 05/15/2016

**TABLE 10**
**Study Area 6 South Chromium Construction Completion Report (CCR)**
**Chromium Remedy Elements Referenced to Previous Relevant Documents**

| SA-6 S Chromium Remedy Element | Declaration No. | 100% Design Report Location/ Section/Work Plan | 100% Design Drawing | 100% Design Specification | Design Change (DC) | Section in SA-6 S Cr CCR |
|---|---|---|---|---|---|---|
| Mobilization and Site Prep | NA | 100% DR, 3.2 | G-005, C-106 | 01100 | NA | 2.1 |
| Health & Safety | NA | 100% DR, 3.3, HASP | NA | 01620 | NA | 2.2 |
| Perimeter Air Monitoring | NA | 100% DR, 3.4, PAMP | NA | 01560 | NA | 2.3, 11 |
| Site Security | NA | 100% DR, 3.5 | NA | 01100 | NA | 2.4 |
| Support Facilities | NA | 100% DR, 3.6 | C-106 | 01100 | NA | 2.5 |
| Temporary Site Utilities | NA | 100% DR, 3.7 | C-106 | 01100 | NA | 2.5 |
| Traffic Control | 5 | 100% DR, 3.8 | C-106 | Summary of Work, 7.1.1.1 02332, Part 3 | DC 2016-05-06 | 2.6 |
| Utility Abandonment | NA | 100% DR, 4.1 | NA | 02216 | NA | 2.8 |
| Erosion Controls | 5 | 100% DR, 18.9 | G-005, C-125 to C-127 | 02370 | DC September-16 | 2.1 |
| Demolition of Existing Structures | NA | 100% DR, 4.0 | C-105 | 02220 | DC 2014-5-19 | 2.7, 4.0 |
| Groundwater Testing for pH | NA | 100% DR, 9.1.2 | NA | 02180.5 | DC 2013-8-14 (Grouted Angles) | 2.9 |
| Waste Classification | NA | 100% DR, 3.10 | NA | NA | NA | 2.10, 8.8 |
| CWTP Construction | NA | 100% DR, 5.3 and 5.4, Appendix I (North DR) | NA | NA | NA | 6.3 |
| Monitoring Well Abandonment | 5 | 100% DR, Appendix A-2 (North DR) | NA | NA | DC 2014-7-28 | 7.0 |
| Monitoring Well/Piezometer Installation | 2 / 5 | 100% DR, Appendix A-2 (North DR) | C-201 to C-203 | 06961, 02670 | DC 2014-7-28 DC 2015-06-05 | 7.0 |
| Dewatering/Pumping | NA | 100% DR, 5.0 | NA | 02140 | NA | 6.0 |
| GW Level Monitoring | NA | 100% DR, Figure 7, Appendix J (North DR) | NA | 16961 | NA | 6.4 |
| Temporary Excavation Support | NA | 100% DR, 10.0 | C-112 to C-120 | 02150 | NA | 8.1 |
| Excavation Extent Survey/Confirmation | 1 | 100% DR, 10.0 | NA | 04160 | DC 2015-12-21 | 8.3, 8.5 |
| Excavation | 1 | 100% DR, 10.0 | G-003, G-004, C-104, C-111 to C-120 | 02135 | DC 2013-12-12 DC 2014-5-6 DC 2014-5-19 DC 2015-01-22 DC 2015-09-28 DC 2015-12-21 | 8.0-8.7; 1.4,1.5, 5.2, 5.3, 12 |

**TABLE 10**
**Study Area 6 South Chromium Construction Completion Report (CCR)**
**Chromium Remedy Elements Referenced to Previous Relevant Documents**

| SA-6 S Chromium Remedy Element | Declaration No. | 100% Design Report Location/ Section/Work Plan | 100% Design Drawing | 100% Design Specification | Design Change (DC) | Section in SA-6 S Cr CCR |
|---|---|---|---|---|---|---|
| Excavation Material (Stockpile) Test/Soil Reuse | 1 | 100% DR, 3.10, Appendix G (North DR) | NA | NA | DC 2014-10-28<br>DC 2015-01-22 | 8.2, 8.4 |
| Offsite Transportation & Disposal | 1 | 100% DR, 11.1 to 11.5 | C-111 to C-120 | 01600, 02332 | NA | 8.8 |
| Backfill Source Testing | 1 | 100% DR, 12.0 | NA | 02315 | DC 2013-9-24 | 9.2 |
| Concrete Testing | 1 | 100% DR, 4.0, Appendix G (North DR) | NA | 02201 | DC 2014-10-31 | 9.3, J-1 |
| Backfilling and Compaction | 1 | 100% DR, 12.0 | NA | 02315 | DC 2014-12-01 | 9.4 |
| In-Place Compaction Testing | 1 | 100% DR, 12.0 and 12.2 | NA | 02315 | NA | 9.5 |
| Hydraulic Barrier Installation | 1 / 2 | 100% DR, 9.0 | S-201 to S-203 | 02170, 02180 | DC 2013-8-14 (Grouted Angles)<br>DC 2013-9-12<br>DC 2015-05-29<br>DC 2015-08-20 | 10.1 |
| Vibration Monitoring | NA | 100% DR, 9.1.5 | NA | 02150, 020180 | NA | 10.2 |
| Sheet Pile Fab & Delivery | NA | 100% DR, 9.1.2 | NA | 02180.3 | NA | 10.1 |
| Epoxy Coating | NA | 100% DR, 9.1.5 | NA | 02180.6 | NA | 10.1 |
| Joint Grouting | NA | 100% DR, 9.1.2 and 9.1.5 | S-203 | 02180.5 | DC 2013-8-14 (Grouted Angles) | 10.1 |
| Deflection Monitoring & Dewatering | NA | NA | NA | NA | NA | 10.2 |
| Consolidation of Soils in Open Space Area | 1 / 2 | 100% DR, 10.1, Appendix G (North DR) | NA | 01600 | DC 2014-10-28<br>DC 2014-10-31<br>DC 2015-06-18 | 10.3 |
| Surcharge & Surcharge Monitoring | 2 | 100% DR, Appendix N (North DR) | C-107 to C-110 | Refer to Appendix N (North DR) | DC 2013-7-29<br>DC 2013-8-14 (Surcharge)<br>DC 2015-03-04 | 10.5 |
| Cap Construction | 2 | 100% DR, 13.0 | C-121 to C-124, C-301, C-309, C-501 to C-504 | 02372, 02373, 02374, 02375 | DC 2015-05-29<br>DC 2015-06-15<br>DC 2015-10-06<br>DC 2015-07-22<br>DC 2015-07-28<br>DC 2015-07-30 | 10.6 |

**TABLE 10**
**Study Area 6 South Chromium Construction Completion Report (CCR)**
**Chromium Remedy Elements Referenced to Previous Relevant Documents**


| SA-6 S Chromium Remedy Element | Declaration No. | 100% Design Report Location/ Section/Work Plan | 100% Design Drawing | 100% Design Specification | Design Change (DC) | Section in SA-6 S Cr CCR |
|---|---|---|---|---|---|---|
| Cap Construction (continued) | 2 | 100% DR, 13.0 | C-121 to C-124, C-301, C-309, C-501 to C-504 | 02372, 02373, 02374, 02375 | DC 2015-08-07<br>DC 2015-08-18<br>DC 2015-08-19<br>DC 2015-08-21<br>DC 2015-10-02<br>DC 2016-05-06 | 10.6 |
| Gas Venting System | 5 | 100% DR, 13.2, Appendix M (North DR) | C-121 | 02380 | DC 2015-07-16 | 10.6 |
| Utility Corridors | NA | 100% DR, 13.3 | C-122 to C-124 | NA | DC 2015-06-18<br>DC 2015-08-20 | 10.6 |
| Final Cap Cover Soils | 5 | 100% DR, Appendix L OSDS (North DR) | NA | 02315, 02900 | DC 2015-9-17<br>DC 2016-05-03<br>DC 2016-03-21<br>DC 2016-04-20 | 10.6 |
| Final Cap Grading | 5 | 100% DR, 13.4 | C-125 to C-127 | NA | DC 2015-11-12<br>DC 2016-04-15<br>DC September-16 | 10.6, App C |
| Contingent GW Extraction System Installation | 2 / 5 | 100% DR, 9.1.7 | C-201 to C-203, C-304 to C-306 | NA | DC 2014-3-25<br>DC 2014-6-10<br>DC 2015-2-12<br>DC 2015-9-03<br>DC 2016-5-24<br>DC 2015-2-24<br>DC 2015-05-19<br>DC 2016-05-31<br>DC 2016-12-20 | 10.4 |
| Deferred Areas | 5 | 100% DR, 10.0 | C-104 | NA | DC 2014-5-19<br>DC 2014-12-23 | 2.8, 18.1, 21.0 |
| In-Situ Treatment | 5 | Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012 | C-104, C-111 to C-120 | NA | DC 2015-06-18 (South) | 12.0 |
| Site Restoration | 5 | 100% DR, 16.0, Appendix L OSDS (North DR) | C-128 | 02900 | DC 2015-11-12<br>DC 2016-04-15 | 14.0 |

**FIGURES**

**FIGURES**

UNLESS OTHERWISE AGREED TO IN WRITING BY AMEC FOSTER WHEELER, ITS USE BY, RELIANCE BY OR MODIFICATION OF THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND WITHOUT LIABILITY TO AMEC FOSTER WHEELER. ANY LOSS, DAMAGE OR INJURY SUFFERED BY THIRD PARTIES AS A RESULT OF UNAUTHORIZED USE OR RELIANCE ON THIS DOCUMENT OR ADOPTION OF OR BASING DECISIONS UPON THIS DOCUMENT, OR ANY PORTION OF IT, IS THE RESPONSIBILITY OF SUCH THIRD PARTIES. AMEC FOSTER WHEELER ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THIS DOCUMENT. THIS DOCUMENT IS NOT INTENDED FOR USE ON ANY PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT HAS BEEN PREPARED. IF YOUR PROJECT IS DIFFERENT IN ANY WAY, CONTACT AMEC FOSTER WHEELER TO DETERMINE HOW OUR WORK SHOULD BE MODIFIED. ANY OTHER USE OF THIS DOCUMENT IS AT YOUR SOLE RISK AND WITHOUT LIABILITY TO AMEC FOSTER WHEELER.

CONFIDENTIAL AND PROPRIETARY INFORMATION. THIS DRAWING AND THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF AMEC FOSTER WHEELER AND IS LOANED SUBJECT TO RETURN UPON REQUEST. IN ACCEPTANCE OF THIS DRAWING, THE RECIPIENT AGREES THAT NO COPIES WILL BE MADE AND THAT THE INFORMATION CONTAINED HEREIN WILL NOT BE DISCLOSED TO OTHERS WITHOUT THE WRITTEN CONSENT OF AMEC FOSTER WHEELER.




SOURCE: USGS QUADRANGLE MAP, 7.5 MIN SERIES
JERSEY CITY, NJ-NY 1967, PHOTO REVISED 1981

0 1000 2000 4000
SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150488<br>*DRAWING:* 3480150488-5710-SLM0-F100 | |
| *PREPARED/DATE:* STR 03/10/16 | *CHECKED/DATE:* DEN 03/10/16 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 1**
SITE LOCATION MAP
STUDY AREA SA-6 SOUTH
SITES 073, 124, 125, 134, 140 & 163
JERSEY CITY, NEW JERSEY


P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-SLM0-F100.dwg Wed, 07 Dec 2016 - 2:21pm scott.rudkin

WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

LEGEND

- SITE 073 PROPERTY BOUNDARY
- SITE 124 PROPERTY BOUNDARY
- SITE 125 PROPERTY BOUNDARY
- SITE 134 PROPERTY BOUNDARY
- SITE 140 PROPERTY BOUNDARY
- SITE 163 PROPERTY BOUNDARY
- CORDOVA PROPERTY BOUNDARY
- BOATYARD PROPERTY BOUNDARY
- SITE BOUNDARY
- SURFACE WATER

STUDY AREA 7




0 100 200 400

SCALE IN FEET

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-SL00-F200

*PREPARED/DATE:* STR 03/10/16

*CHECKED/DATE:* DEN 03/10/16

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 2**
SITE LAYOUT
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

USE OR STORAGE AGREED TO IN WRITING CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT. (2) THIS DOCUMENT CONTAINS INFORMATION, DATA AND IDEAS THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (3) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS BEEN RELEASED, AND OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY OTHER PARTY IS AT THE PARTY'S SOLE RISK AND RESPONSIBILITY.

# SA-6 South Project Team Organizational Chart

**Honeywell Remediation Management**
**William Hague** – Director, Remediation Engineering & Construction
**John Morris** – Remediation Director

**Honeywell Procurement**
**Raj Ghaisas** – Sr. Commodity Manager Services & Suppliers

**Honeywell Communications**
**Victoria Streitfeld** – Director Communications HSE&S

**Honeywell Construction Management**
**John Mojka** – Engineering & Construction Manager

**Honeywell Project Manager**
**Maria Kaouris** – Remediation Manager

**Amec Foster Wheeler Project Management**
**Principal Engineer** - Joseph Clifford
**Project Manager** – Dennis Nagg

## Field Support

**Analytical Lab**
**Accutest**

**3rd Party Liner QA**
**Langan**

**Air Monitoring**
**Endicott**
**Travelers (PAM Analytical)**

**Amec Foster Wheeler Construction Management**
**Construction Manager** - Stuart Bills

**Analytical QA**
**AESI (QA)**
**Validata (Data Validation)**

**Waste Coordination**
**Anacon**
Dino Ciccone

**Amec Foster Wheeler Field Staff**
**Asst CM/SSO** – George Pfeiffer
**CQA** – Dave Ambrose
**Project Controls** – Eric Christodoulatos
**Clerical** – Diana Rocha
**CQA Tech** – Brian Shea, Michael Serra, Jenna Desiderio
**Field Engineer** – Anzanu Eslaminejad

**Excavation Subcontractor**
**Entact**
**Superintendent** – Keith Goisse
**Project Manager** – Kurt Gimbel
**H&S** – Ross DeAmbrogio

**Subcontracts**
B&B Drilling
Vertical on V- Northeast
Maser Consulting

**Clean Fill Analytical**
ChemTech
Eurofins

**Technical Support**
**Amec Foster Wheeler**
**EOR** – Geoff Shallard
**Design Manager** – Anthony Donovan
**Permitting** – Bill Mikula
**Water Treatment** – Ralph Oulton

**Mueser Rutledge**
Sheetpile

**Cornerstone**
GW Modeling

**Geocomp Engineering**
Vibration Monitoring

| REV. | DATE | STATUS | PREP BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

Amec Foster Wheeler PROJECT No. 3480150488
DRAWING: 3480150488-5710-ORGD-F300

PREPARED/DATE: STR 03/11/16
CHECKED/DATE: DEN 03/11/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE, Inc.
200 AMERICAN METRO BLVD, SUITE 118
HAMILTON, NEW JERSEY 08610

**FIGURE 3**
**SA-6 PROJECT TEAM ORGANIZATION CHART**
**STUDY AREA 6 SOUTH**
**JERSEY CITY, NEW JERSEY**

P:\GROUP\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\570004\DURRENT DRAWINGS\3480150488-5710-ORGD-F002.dwg Thu, 20 Apr 2017 - 1:31pm mestevens Layout: Layout1

CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-PAM0-F400.dwg Wed, 07 Dec 2016 - 2:22pm scott.rudkin Layout: Layout1

N

LEGEND

- S-1 STATIONARY PERIMETER AIR MONITORING LOCATION
- STUDY AREA 6 SOUTH SITE BOUNDARY
- STUDY AREA 6 SOUTH INDIVIDUAL SITE BOUNDARY

SITE 073
DEGEN OIL

BOATYARD
PROPERTY

SITE 134
OLD DOMINION

SITE 140
ABF TRUCKING

SITE 125
DELPHIC
CONSOLIDATED

SITE 124
ROOSEVELT
BOWLING LANES

CORDOVA
PROPERTY

SITE 163
POSNAK & TURKISH

S-1
S-2
S-3
S-4

0 50 100 200
SCALE IN FEET

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-PAM0-F400

*PREPARED/DATE:* STR 03/11/16


*CHECKED/DATE:* DEN 03/11/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 4**
PERIMETER AIR MONITORING
STATION LOCATIONS
STUDY AREA 6 SOUTH
SITES 073,124,125,134,140 & 163
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND PROPRIETARY TO AMEC FOSTER WHEELER AND (2) THIS DOCUMENT IS PROVIDED AS-IS, WITH NO REPRESENTATIONS OR WARRANTIES OF ANY KIND. THE CLIENT AGREES THAT IT SHALL NOT DISCLOSE THIS DOCUMENT TO ANY THIRD PARTY, IN WHOLE OR IN PART, WITHOUT THE PRIOR WRITTEN CONSENT OF AMEC FOSTER WHEELER, WHICH IT HAS NOT GIVEN. THIS DOCUMENT IS NOT TO BE USED BY ANY THIRD PARTY FOR ANY PURPOSE WHATSOEVER, AND ANY RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

# Honeywell Study Area 6
# Transportation Local Routes




Primary Truck Route

Emergency/Backup Truck Route

0 50 100 200
SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150488<br>DRAWING: 3480150488-5710-0TR0-F500 | | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 |
| PREPARED/DATE:<br>STR 03/23/16 | CHECKED/DATE:<br>DEN 03/23/16 | **FIGURE 5**<br>TRUCK ROUTE MAP<br>STUDY AREA 6 SOUTH<br>SITES 073, 124,125, 134, 140 & 163<br>JERSEY CITY, NEW JERSEY |

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-0TR0-F500.dwg Wed, 07 Dec 2016 - 2:23pm scott.rudkin

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




**Legend**

- Station Point
- Station Label
  - 0+00 - Station Location
  - 088-TWP-01 - Sample Name
  - 7.0 - pH Sample Result
- Proposed Hydraulic Barrier Wall (at the time of pH monitoring)
- Study Area Boundary

0 75 150 300
SCALE IN FEET

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-GWSR-F500

*PREPARED/DATE:* STR 03/11/16

*CHECKED/DATE:* DEN 03/11/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 6**
GROUNDWATER SAMPLE RESULTS (pH)
STUDY AREA SA-6 NORTH AND SOUTH
JERSEY CITY, NEW JERSEY

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-GWSR-F500.dwg Wed, 07 Dec 2016 - 2:23pm scott.rudisin Layout: Layout1

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

124-SB-604

125-SB-605

125-SB-603

MATCH LINE SEE BELOW

LIMIT OF EXCAVATION (TYP)
(SEE NOTE EXC6 ON SHEET G-004)

SOIL RETENTION SYSTEM (TYP)
(SEE NOTE EXC2 ON SHEET G-004)

NEW JERSEY STATE HIGHWAY ROUTE 440

HACKENSACK RIVER

EXCAVATION INTERVAL 1
EXISTING GRADE TO ELEVATION 8.1

CHROMIUM IMPACTED MATERIAL TO BE ADDRESSED DURING FUTURE BULKHEAD IMPROVEMENTS (SEE NOTE EXC5 ON SHEET G-004)

134-SB-603

163-SB-601

LOT 163 EXCAVATION FROM EXISTING GRADE TO 2'(BGS)

EXISTING BULKHEAD (TYP)

MATCH LINE SEE ABOVE

LEGEND

HEXAVALENT CHROMIUM DESIGNATIONS BASED ON PDI (100% DESIGN) DATA

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- NO EXCAVATION REQUIRED
- DEFERRED AREA
- SOIL BORING COMPOSITE SAMPLE

0 50 100 200
SCALE IN FEET

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

**FIGURE 7A**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 1**

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

125-SB-607

140-SB-603

125-SB-605

125-SB-603

124-SB-608

124-SB-604

124-SB-602

124-SB-601

MATCH LINE SEE BELOW

LIMIT OF EXCAVATION (TYP) (SEE NOTE EXC6 ON SHEET G-004)

SOIL RETENTION SYSTEM (TYP) (SEE NOTE EXC2 ON SHEET G-004)

NEW JERSEY STATE HIGHWAY ROUTE 440

EXCAVATION INTERVAL 2
ELEVATION 8.1 TO ELEVATION 5.7

CHROMIUM IMPACTED MATERIAL TO BE ADDRESSED DURING FUTURE BULKHEAD IMPROVEMENTS (SEE NOTE EXC5 ON SHEET G-004)

HACKENSACK RIVER

134-SB-603

163-SB-601

MATCH LINE SEE ABOVE

LEGEND

HEXAVALENT CHROMIUM DESIGNATIONS BASED ON PDI (100% DESIGN) DATA

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- NO EXCAVATION REQUIRED
- DEFERRED AREA
- SOIL BORING COMPOSITE SAMPLE

0 50 100 200
SCALE IN FEET

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 588 - 2629
NJ Certificate of Authorization Number 24GA28019600

**FIGURE 7B**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 2**

P:\CAD\VU2\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480160489\3710\3710\GIS\PROJT DRAWINGS\3480160489_3710_CHRO_7B00.dwg Tue, 18 Apr 2017 - 10:46am johnmw.wingfield

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

CHROMIUM IMPACTED MATERIAL (SEE NOTE EXC9 ON SHEET G-004)

MATCH LINE SEE BELOW

125-SB-602

124-SB-611

124-SB-608

124-SB-604

124-SB-610

124-SB-609

124-SB-605

124-SB-602

124-SB-603

124-SB-601

LIMIT OF EXCAVATION (TYP) (SEE NOTE EXC6 ON SHEET G-004)

SOIL RETENTION SYSTEM (TYP) (SEE NOTE EXC2 ON SHEET G-004)

NEW JERSEY STATE HIGHWAY ROUTE 440

HACKENSACK RIVER

EXCAVATION INTERVAL 3
ELEVATION 5.7 TO ELEVATION 4.2

CHROMIUM IMPACTED MATERIAL TO BE ADDRESSED DURING FUTURE BULKHEAD IMPROVEMENTS (SEE NOTE EXC5 ON SHEET G-004)

(SEE NOTE EXC10 ON SHEET G-004)

134-SB-603

MATCH LINE SEE ABOVE

EXISTING BULKHEAD (TYP)

LEGEND

HEXAVALENT CHROMIUM DESIGNATIONS BASED ON PDI (100% DESIGN) DATA

HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM

HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM

HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM

HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM

NO EXCAVATION REQUIRED

DEFERRED AREA

SOIL BORING COMPOSITE SAMPLE

0 50 100 200

SCALE IN FEET

Honeywell

101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler

Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018600

**FIGURE 7C**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 3**

P:\CAD\VOLUME2\JERSEY CITY\SA 6 SOUTH\344601\SAM\5710\5710A1\CURRENT DRAWINGS\344601SA6-5710-CHRO-7800.dwg Wed, 07 Dec 2016 - 2:28pm awelt.rubio





Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 569 - 2829
NJ Certificate of Authorization Number 24GA28010800

**FIGURE 7D**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 4**

P:\CAD\HONEYWELL\JOBS\... Wed, 07 Dec 2016 - 3:03pm scott.rudin




LEGEND

- HEXAVALENT CHROMIUM DESIGNATIONS BASED ON PDI (100% DESIGN) DATA
- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20–240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- NO EXCAVATION REQUIRED
- DEFERRED AREA
- SOIL BORING COMPOSITE SAMPLE

MATCH LINE SEE ABOVE

0 50 100 200
SCALE IN FEET

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010600

**FIGURE 7E**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 5**

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

CHROMIUM IMPACTED MATERIAL (SEE NOTE EXC9 ON SHEET G-004)

NEW JERSEY STATE HIGHWAY ROUTE 440

MATCH LINE SEE BELOW

X2

125-SB-602

125-SB-604

125-SB-601

124-SB-611

124-SB-610

124-SB-609

124-SB-608

124-SB-604

124-SB-605

124-SB-603

124-SB-601

LIMIT OF EXCAVATION (TYP)
(SEE NOTE EXC6 ON SHEET G-004)

SOIL RETENTION SYSTEM (TYP)
(SEE NOTE EXC2 ON SHEET G-004)

HACKENSACK RIVER

EXCAVATION INTERVAL 6
ELEVATION 0.40 TO ELEVATION -1.2

CHROMIUM IMPACTED MATERIAL TO BE ADDRESSED DURING FUTURE BULKHEAD IMPROVEMENTS (SEE NOTE EXC5 ON SHEET G-004)

EXISTING BULKHEAD (TYP)

MATCH LINE SEE ABOVE

LEGEND

HEXAVALENT CHROMIUM DESIGNATIONS BASED ON PDI (100% DESIGN) DATA

HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM

HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM

HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM

HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM

NO EXCAVATION REQUIRED

DEFERRED AREA

SOIL BORING COMPOSITE SAMPLE

0 50 100 200

SCALE IN FEET

P:\CAD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\346015048R\5710\5710A\CURRENT DRAWINGS\346015048R-5710-5710A-CHR6-FBF0.dwg Wed, 07 Dec 2016 - 8:33pm scott.nadkn

**Honeywell**
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

**FIGURE 7F**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 6**

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

CHROMIUM IMPACTED MATERIAL (SEE NOTE EXC9 ON SHEET G-004)

NEW JERSEY STATE HIGHWAY ROUTE 440

MATCH LINE SEE BELOW

125-SB-602
125-SB-604
125-SB-601
124-SB-611
124-SB-610
124-SB-609
124-SB-608
124-SB-602

LIMIT OF EXCAVATION (TYP)
(SEE NOTE EXC6 ON SHEET G-004)

SOIL RETENTION SYSTEM (TYP)
(SEE NOTE EXC2 ON SHEET G-004)

HACKENSACK RIVER

CHROMIUM IMPACTED MATERIAL TO BE ADDRESSED DURING FUTURE BULKHEAD IMPROVEMENTS (SEE NOTE EXC5 ON SHEET G-004)

EXCAVATION INTERVAL 7
ELEVATION -1.2 TO ELEVATION -2.5

EXISTING BULKHEAD (TYP)

MATCH LINE SEE ABOVE

LEGEND

HEXAVALENT CHROMIUM DESIGNATIONS BASED ON PDI (100% DESIGN) DATA

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- NO EXCAVATION REQUIRED
- DEFERRED AREA
- SOIL BORING COMPOSITE SAMPLE

0 50 100 200
SCALE IN FEET

P:\CAD\HONEYWELL_JERSEY CITY\SA 6 SOUTH\346013504869\3710\3710004\CURRENT DRAWINGS\346013504869-3710-CHR0-FIG06.dwg Tue, 18 Apr 2017 - 10:39am chorris.wingfield

**Honeywell**
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2529
NJ Certificate of Authorization Number 24GA28010900

**FIGURE 7G**
**WASTE CLASSIFICATION SAMPLE LOCATIONS**
**CHROMIUM SAMPLING**
**INTERVAL 7**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND AMEC FOSTER WHEELER RETAINS ALL RIGHTS TO CONTROL ITS USE AND DISCLOSURE; AND (2) NEITHER THIS DOCUMENT NOR ANY PART OF IT MAY BE DISCLOSED TO ANY THIRD PARTY OR USED BY ANY OTHER PERSON OR FOR ANY OTHER PROJECT WITHOUT AMEC FOSTER WHEELER'S PRIOR WRITTEN CONSENT. AMEC FOSTER WHEELER ACCEPTS NO RESPONSIBILITY FOR ANY DAMAGE WHICH IT HAS BEEN DELIVERED AND FOR ANY DECISIONS MADE OR ACTIONS TAKEN BASED ON THIS DOCUMENT BY ANY THIRD PARTY. IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-AB00-F8A0.dwg Wed, 07 Dec 2016 - 2:35pm scott.rudkin




LEGEND


- ⊠ JUNE 2016 SOIL BORINGS AT 20° ANGLE INTO BULKHEAD
- ○ SOIL BORING LOCATION
- PROPERTY LINE
- BULKHEAD
- HYDRAULIC BARRIER SA-6 SOUTH
- HYDRAULIC BARRIER SA-7

0 15 40 80

SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150488<br>DRAWING: 3480150488-5710-AB00-F8A0 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE, Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **FIGURE 8A**<br>SITE 073 DEFERRED AREA<br>SOIL BORING LOCATIONS<br>STUDY AREA 6 SOUTH<br>JERSEY CITY , NEW JERSEY |
| PREPARED/DATE: STR 09/28/16<br>CHECKED/DATE: DEN 09/28/16 | | |

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




LEGEND:

- SUPPLEMENTAL SAMPLE LOCATION
- EXCAVATION AREA

0 5 10 20

SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150488<br>*DRAWING:* 3480150488-5710-AB00-F8B0 | |
| *PREPARED/DATE:* STR 09/28/16 | *CHECKED/DATE:* DEN 09/28/16 |


amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 8B**
POST-EXCAVATION SAMPLING LOCATIONS 60 KELLOGG
STUDY AREA 6 SOUTH - SITE 125
JERSEY CITY, NEW JERSEY

P:\CAD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710A\CURRENT DRAWINGS\3480150488-5710-AB00-F8B0.dwg Wed, 07 Dec 2016 - 2:45pm scott.radkin Layout: SITE 124

CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




P:\JCMUA\WETWELL\JERSEY CITY\SA 6 SOUTH\3480150488\3710\5710\100A\CURRENT DRAWINGS\3480150488-5710-CWTS-F100.dwg Wed, 07 Dec 2016 - 2:39pm scott.rucklin Layout: LAYOUT

SOURCE REFERENCE:

DRAWING TITLE: "WASTEWATER MANAGEMENT PROCESS FLOW DIAGRAM" PREPARED BY ENTACT, 699 SOUTH FRIENDSWOOD DRIVE, FRIENDSWOOD, TEXAS 77546. SHEET 1 OF 1, DATED 03/15/13, REVISION A.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-CWTS-F100

*PREPARED/DATE:* STR 03/11/16

*CHECKED/DATE:* DEN 03/11/16

SEAL:
BRENT C. DODELL


NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE3801700

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 9**
CONSTRUCTION WATER TREATMENT SYSTEM LAYOUT
STUDY AREA 6 NORTH & STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE COURSE AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN CREATED AND ANY USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT SUCH PARTY'S SOLE RISK AND DISCRETION.




SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488–5710–MWLO–F900

*PREPARED/DATE:* STR 07/08/16
*CHECKED/DATE:* DEN 07/08/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 10**
SHALLOW MONITORING WELL LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\CAD\HOMEWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\S7100\CURRENT DRAWINGS\3480150488–5710–MWLO–F900.dwg Thu, 20 Apr 2017 - 3:31pm scottcurdin Layout: cr

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS COPYRIGHT AMEC FOSTER WHEELER AND MAY NOT BE REPRODUCED, AMENDED OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE EXPRESS WRITTEN CONSENT OF AMEC FOSTER WHEELER; AND (II) AMEC FOSTER WHEELER ACCEPTS NO LIABILITY OF ANY KIND FOR ANY USE OF THIS DOCUMENT OTHER THAN FOR THE PURPOSE FOR WHICH IT WAS ORIGINALLY PREPARED, AND ACCEPTS NO LIABILITY WHATSOEVER FOR ANY USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IN A THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-PESW-F100.dwg Wed, 07 Dec 2016 - 9:38am




LEGEND

- ADDITIONAL POST-EXCAVATION SIDEWALL SAMPLE
- AS-BUILT CHROMIUM EXCAVATION LIMIT
- HYDRAULIC BARRIER (SA-6 SOUTH)
- DEFERRED EXCAVATION AREAS
- EXPANDED EXCAVATION AREA

0 40 80 160
SCALE IN FEET

| REV. | DATE | STATUS | DRFT BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-PESW-F100

*PREPARED/DATE:* STR 04/20/16

*CHECKED/DATE:* DEN 05/06/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 11**
ADDITIONAL POST-EXCAVATION
SIDEWALL SAMPLE LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT OF THE PROJECT AND FOR THE PURPOSES FOR WHICH IT WAS PREPARED.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\S710\S71004\WORKING\3480150488-5710-LAMO-F600 w ex call overlay.dwg Mon, 05 Jun 2017 - 10:33am scott.rudkin Layout: Layout1

120 119 118 117 116 115 114 113 112 111 110 109 108 107 106 105 104 103 102 101 100

HYDRAULIC BARRIER WALL (TYP)

LIMIT OF EXCAVATION (100 PERCENT DESIGN)

LIMIT OF EXPANDED EXCAVATION (TYP)

134-SB-019
134-SB-021
134-SB-061
134-SB-092
134-SB-074
134-SB-075
134-SB-097
134-SB-113
134-SB-160
134-SB-161
134-SB-162
134-SB-165
134-SB-166
134-SB-167
134-SB-168
134-SB-169
134-SB-170
134-SB-171
134-SB-172
134-SB-173
134-SB-174
134-SB-175
134-SB-177
134-SB-164

BOTTOM OF EXCAVATION = STRATUM D
(ELEV VARIES -4.9 TO -7.7 FT)

LEGEND

- EXCAVATION PREVIOUSLY COMPLETED TO STRATUM D
- EXPANDED EXCAVATION AREA
- 100% DESIGN EXCAVATION AREA
- EXPANDED EXCAVATION AREA
- ORIGINAL PDI SIDEWALL SAMPLE LOCATION
- ORIGINAL PDI BOTTOM SAMPLE LOCATION
- SUPPLEMENTAL SAMPLE LOCATION
- HORIZONTAL DELINEATION SAMPLE LOCATION
- 101 EXCAVATION CELL NUMBER

0 10 20 40
SCALE IN FEET


| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

Amec Foster Wheeler PROJECT No. 3480150488
DRAWING: 34801504888-5710-LAMO-F600 W EX CALL OVERLAY

PREPARED/DATE: STR 04/20/16
CHECKED/DATE: DEN 05/06/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE, Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 12**
SITE 134 EXPANDED EXCAVATION
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY




UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (i) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (ii) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710D4\CURRENT DRAWINGS\3480150488-5710-CAEE-F120.dwg Mon, 05 Jun 2017 - 10:27am scott.rudkin


| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150488<br>DRAWING: 3480150488-5710-CAEE-F120 | |
| PREPARED/DATE: STR 03/29/16 | CHECKED/DATE: DEN 05/06/16 |


amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE, Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619


**FIGURE 13**
SITE 073 IMPACTED CONCRETE
AREA OF EXCAVATION EXPANSION
STUDY AREA 6 SOUTH - SITE 073
JERSEY CITY, NEW JERSEY

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND DISCRETION.




DETAIL A
EXCAVATION AREA PARTIAL PLAN AT KELLOGG STREET
SCALE: 1"=30'-0"
30' 20' 10' 0 30' 60'




DETAIL B
EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE
SCALE: 1"=30'-0"
30' 20' 10' 0 30' 60'

LEGEND

- EXISTING SHALLOW MONITORING WELL LOCATION
- OPEN SPACE AOC
- DEVELOPMENT AOC
- PROPERTY LINE
- PROPOSED LIMIT OF CHROMIUM REMEDIAL ACTION
- HYDRAULIC BARRIER (SA-6 SOUTH)
- HYDRAULIC BARRIER WALL (SA-7)
- VIBRATION MONITORING LOCATION

0 100 200 400
SCALE IN FEET

NOTE:
PROPOSED CONTINGENT GROUNDWATER EXTRACTION PUMPING WELL AND MONITORING WELL LOCATIONS SUBJECT TO CHANGE BASED ON SITE DEVELOPMENT PLAN.

SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |


*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-VM00-F130

*PREPARED/DATE:* STR 03/31/16
*CHECKED/DATE:* DEN 03/31/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 14**
VIBRATION MONITORING
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\CAD\VM\NEWELL JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710VA\CURRENT DRAWINGS\3480150488-5710-VM00-F130.dwg Thu, 20 Apr 2017 - 10:03am charles.winyfield Layout: SITE




CHROMIUM REMEDY COMPONENTS

NTS

| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150488<br>DRAWING: 3480150488-5710-CRC0-F140 | |
| PREPARED/DATE: STR 03/10/16 | CHECKED/DATE: DEN 03/10/16 |

amec foster wheeler


ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 15**
CHROMIUM REMEDY COMPONENTS
STUDY AREA SA-6 SOUTH
JERSEY CITY, NEW JERSEY

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-CRC0-F140.dwg Wed, 07 Dec 2016 - 2:46pm scott.rudkin

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND NOT DISCLOSED OR DISCUSSED IN ANY WAY TO ANY PERSON OR ENTITY OTHER THAN THE CLIENT AND THOSE EMPLOYED BY THE CLIENT WHO HAVE A NEED TO KNOW THE CONTENTS FOR THE PURPOSE OF THE PROJECT, AND (2) THE CLIENT AND THOSE EMPLOYED BY THE CLIENT WHO HAVE A NEED TO KNOW THE CONTENTS FOR THE PURPOSE OF THE PROJECT SHALL NOT USE THE DOCUMENT FOR ANY PURPOSE OTHER THAN THE PROJECT WITHOUT THE EXPRESS WRITTEN PERMISSION OF AMEC FOSTER WHEELER. IN ADDITION, THE CLIENT AGREES TO INDEMNIFY AMEC FOSTER WHEELER AGAINST ANY CLAIMS, LIABILITIES, LOSSES, OR DAMAGES ARISING OUT OF OR CONNECTED WITH THE UNAUTHORIZED USE OF THIS DOCUMENT BY THE CLIENT OR ANY THIRD PARTY TO WHOM THE CLIENT OR ANYONE ACTING ON BEHALF OF THE CLIENT HAS DISCLOSED THIS DOCUMENT OR ANY PART THEREOF. IF THIS DOCUMENT IS RECEIVED BY ANY PERSON OTHER THAN THE CLIENT, THAT PERSON IS ADVISED THAT UNAUTHORIZED USE OF THIS DOCUMENT IN ANY FORM BY ANY PERSON OR ENTITY IS PROHIBITED.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-CAPD-F15D.dwg Wed, 07 Dec 2016 - 2:47pm scott.rudkin




## CAP SYSTEM DETAIL

NTS


| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150488<br>DRAWING: 3480150488-5710-CAPD-F15D | |
| PREPARED/DATE: STR 03/10/16 | CHECKED/DATE: DEN 03/10/16 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 16**
CAP SYSTEM DETAIL
STUDY AREA SA-6 SOUTH
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




LEGEND

- UTILITY CORRIDOR
- OPEN SPACE AOC
- DEVELOPMENT AOC
- PROPERTY LINE
- HYDRAULIC BARRIER (SA-6 SOUTH)
- HYDRAULIC BARRIER WALL (SA-7)

0 400 100 200
SCALE IN FEET

| REV. | DATE | STATUS | DRFT BY | CHKD BY |
|---|---|---|---|---|

Amec Foster Wheeler PROJECT No. 3480150488
DRAWING: 3480150488-5710-UC00-F160

PREPARED/DATE: STR 04/20/16
CHECKED/DATE: DEN 04/21/16


amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE, Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 17**
UTILITY CORRIDORS
STUDY AREAS 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\CAD\VONCMELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\V5710DA\CURRENT DRAWINGS\3480150488-5710-UC00-F160.dwg Mon, 05 Jun 2017 - 10:38am scott.rufkin

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND PROPRIETARY TO AMEC FOSTER WHEELER AND (II) AMEC FOSTER WHEELER ASSUMES NO DUTY TO, AND DISCLAIMS ANY LIABILITY TO, ANY THIRD PARTY WHICH IT HAS NOT DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CAD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\57100A\CURRENT DRAWINGS\3480150488-5710-DPEX-F170.dwg Wed, 19 Apr 2017 - 2:55pm charles.wingfield Layout: Layout1




LEGEND:

- LIMIT OF HEXAVALENT CHROMIUM EXCAVATION
- ORIGINAL PDI BOTTOM SAMPLE LOCATION
- ORIGINAL PDI SIDEWALL SAMPLE LOCATION

0 10 20 40
HORIZONTAL SCALE

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|

Amec Foster Wheeler PROJECT No. 3480150488
DRAWING: 3480150488-5710-DPEX-F170

PREPARED/DATE: STR 03/29/16
CHECKED/DATE: DEN 03/29/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE, Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 18**
SITE 163 DEEP EXCAVATION LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT, CONTAINS INFORMATION, DATA AND DESIGNS THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS ORIGINALLY PREPARED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\57100A\CURRENT DRAWINGS\3480150488-5710-DNRA-F180.dwg Tue, 25 Apr 2017 - 8:07am scott.rudkin Layout: Layout1




LEGEND

- PROPERTY LINE SA-7
- PROPERTY LINE SA-6 NORTH
- PROPERTY LINE SA6 SOUTH
- DEED NOTICE AREA 1
- DEED NOTICE AREA 2 (DEFERRED AREA)
- DEED NOTICE AREA 3
- DEED NOTICE AREA 4 (TRACT 2 IS DEFERRED AREA)
- 1 BAYFRONT BLOCKS
- SA-7 SOIL BENTONITE CEMENT HYDRAULIC BARRIERS
- JCMUA BLOCK 6 BOUNDARY
- SA-6 NORTH & SOUTH STEEL SHEETPILE HYDRAULIC BARRIERS
- SITE 163 DEVELOPMENT AREA

0 150 300 600
SCALE IN FEET

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150438
*DRAWING:* 3480150488-5710-DNRA-F180

*PREPARED/DATE:* STR 4/20/16

*CHECKED/DATE:* DEN 04/24/17

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 19**
DEED NOTICE RESTRICTED AREAS
HONEYWELL - SA 6 & SA-7
JERSEY CITY, NEW JERSEY

# APPENDIX A

# REPRESENTATIVE PHOTOGRAPHS

# SA-6 South Chromium Remedy



001 60 Kellogg air monitoring station S1



002 60 Kellogg Warehouse Demo



003 60 Kellogg slab




004 Beginning to auger PZ18

# SA-6 South Chromium Remedy



005 Kellogg jughandle sawcutting




006 60 Kellogg warehouse demo E2



007 Surcharge Instrument Station Protection



008 Kellogg St parking lot paving

# SA-6 South Chromium Remedy



009 60 Kellogg warehouse demo S2



010 Kellogg jughandle temp fencing S2




011 Kellogg St air monitoring station S2




012 Kellogg St island removal and paving

# SA-6 South Chromium Remedy



013 Kellogg St parking lot 80 Kellogg utility termination



014 Lift around surcharge instruments




015 SA-6S air monitoring station



016 SA-6S Site 124 pre-trenching

# SA-6 South Chromium Remedy



017 SA-6S staging area



018 SA-7 roadway paving prep



019 Demarcation fabric around instrumentation stations



020 Settlement platform

# SA-6 South Chromium Remedy




021 Beginning to break up concrete at Site 163




022 Installing the gas vent pipe down the slope at station-20+00



023 ABI machine removing temp



024 Compacting the final lift of historic fill in the expanded excavation at Site 134



025 Placing historic fill in the expanded excavation at Site 134



026 Placing historic fill in the expanded excavation at Site 134




027 Removing Petroleum impacted soil from 1S




028 Uncovering SCB wall

# SA-6 South Chromium Remedy



029 Expanded Excavation at Site 134




030 Loading Petroleum soil into trucks for transport to MCL



031 Exposure of petroleum soil in 1S



032 Spreading material in the expanded excavation at Site 134

# SA-6 South Chromium Remedy




033 Expanded excavation at Site 134 after compaction




034 Spreading material in the expanded excavation at Site 134



035 S1 Pile-Placing demarcation fabric for petroleum impacted material



036 SA-6N construction water treatment bag filters and tanks



037 SA-6N construction water treatment system piping



038 SA-6S drilling dewatering wells



039 GGWES trench gravel




040 SA-6S dewatering piping



041 SA-6S dewatering system



042 SA-6S dewatering system



043 Welding dewatering dual walled pipe



044 Dewatering on the clean side of the exclusion zone

# SA-6 South Chromium Remedy



045 Placing pipe in trench



046 SA-6S excavation bridge lift




047 Ramp to 2S area




048 Creating ramp onto SA-6S cap for coversoil

# SA-6 South Chromium Remedy




049 Geofoam placed on edge of liner



050 SA-6S excavation cells 1-6



051 SA-6S greater than 1000 ppm soil loading



052 Entact clean scraping cell 115

# SA-6 South Chromium Remedy



053 SA-6S less than 20 ppm soil stockpiling




054 Excavation load out of greater than 1000 ppm soil



055 Excavation progress looking west



056 Entact clean scraping cells 110B to 106B



057 Live load out of greater than 1000 ppm soil




058 Fine grading the east slope of the D Street corridor




059 Unloading material in 2S surcharge area




060 Excavation- Start of Cell 44

# SA-6 South Chromium Remedy



061 Excavation at Site 163



062 Excavation face




063 Excavation



064 SA-6S Excavation - Beginning cell 51

# SA-6 South Chromium Remedy




065 Excavation




066 Excavation




067 Excavation




068 Loading soils for transit to the SA-6S cap



069 View of excavation progress



070 Excavating cell 126



071 Excavation 4



072 Removing surcharge material in 2S

# SA-6 South Chromium Remedy




073 Excavation at site 163




074 Excavating the asphalt in the SA-6S cap



075 Entact backfilling and compacting screenings in cells 139 to 132



076 SA-6S Backfill - Covering Stratum O behind the 60 Kellogg Street office



077 Backfilling and compacting historical fill in cells 80-73



078 Entact backfilling approved historic fill in cells 127B to 116B




079 Placing material on 2S



080 Compacting DGA and screenings in cells 75 - 72



081 Compaction testing in cell 151




082 Entact compacting DGA on top of fabric in cells 126 through 119



083 Placing crushed concrete



084 Spreading backfill



085 Compacting soil on 3S




086 Rolling material in 2S surcharge area



087 Entact pushing a lift of screenings from cells 131 to 138



088 Backfilling the DR-11 HDPE storm drain adjacent to Kellogg Street



089 Backfilling cell 153 to 149



090 Compacting DGA in cell 139




091 Compaction-testing cell 141



092 Compacting DGA in cells 88 and 87



093 Performing a nuclear density compaction test in cell 123



094 Compacting a lift of screenings in cells 85 - 78



095 Compacting the first lift of screenings in cells 129 through 120



096 Assembled vibrating wire piezometer



097 Grading 3S surcharge area



098 Contingent groundwater trench



099 Grouting angles on HB wall



100 Contingent groundwater trench

# SA-6 South Chromium Remedy



101 Contingent groundwater trench



102 Compacting material



103 SA-6S driving HB wall



104 SA-6S driving HB wall

# SA-6 South Chromium Remedy



105 Moving HB sheets



106 SA-6S grouting angles




107 SA-6S HB driving




108 Installing manhole in south contingent system

# SA-6 South Chromium Remedy



109 SA-6S HB wall driving



110 SA-6S HB wall



111 Hydrualic Barrier Installation




112 SA-6S Kellogg jughandle temp sheets




113 Contingent groundwater trench



114 Contingent groundwater system gravel, fabric, soil




115 Relief trench along hydraulic barrier lookiing west



116 SA-6S grouting angles

# SA-6 South Chromium Remedy



117 Contingent groundwater trench



118 Contingent GW system



119 Setting HB sheets to grade



120 SA-6S grouting angles

# SA-6 South Chromium Remedy




121 SA-6S temp sheet driving



122 Vibration Monitoring Equipment



123 1S Pre-surcharge




124 Covering holes in SCB wall with bentonite

# SA-6 South Chromium Remedy



125 Surcharge Placement



126 SA-6S HB installation




127 SA-6S HB installation



128 Off-loading material on surcharge S1

# SA-6 South Chromium Remedy



129 Welded angle repair-full section




130 Pushing out cover soil at station 18+00




131 Laying out Do Not Dig tape in the B Street corridor



132 Installing sheets to grade




133 Pushing cover soil over the edge of the eastern slope of the B Street corridor



134 Sheetpile installation



135 Installed sheetpiles with swellseal




136 Entact reached the current end of the GDL with the cover soil



137 Surveying gravel in contingent groundwater trench



138 Placing soil on top of gravel in contingent groundwater trench



139 2S surcharge pile



140 Placing material over fabric on 2S surcharge pile



141 Pipe contected to manhole in trench



142 Manhole, stone, and geo-tech fabric in trench



143 S1 surcharge pile



144 End dump unloading material over demarcation fabric in S1 surcharge area




145 Demarcation fabric with material being placed over it on S1 surcharge area



146 S1 surcharge pile dozer placing material in 1 foot lifts




147 Placement of demarcation fabric on S1 surcharge



148 Special closure section for SA-6 South HB wall

# SA-6 South Chromium Remedy



149 2S surcharge pile



150 Special closure section for SA-6 HB wall in place




151 Pushing cover soil through the C Street corridor




152 Cover soil progress along the SCB wall

# SA-6 South Chromium Remedy





153 Caution tape placed over root barrier




154 Geofoam installation in corridor




155 Graded cover soil




156 Placement of Horizon C soil

# SA-6 South Chromium Remedy




157 Graded cover soil in utility corridor




158 Root barrier with caution tape



159 Site 163 in-situ treatment containment area



160 Site 163 in-situ treatment markout

# SA-6 South Chromium Remedy



161 Site 163 in-situ active treatment



162 Site 163 in-situ active treatment




163 Fine grading the cap subgrade near sta. 18+00



164 Removing surcharge soil from the SA-6 south cap area



165 Fine grading and compacting the cap subgrade at sta. 15+50



166 Placing historic fill outboard of the HB Wall



167 Beginning to sculpt the cap subgrade in the southwest corner of 3S



168 Placing historic fill from 1N outboard of the HB wall in cells 115-105



169 East corner of cap



170 Fine grading and compacting the cap subgrade at Sta. 24+00




171 Fine grading on 1S



172 Fine grading the cap subgrade at Sta. 23+50

# SA-6 South Chromium Remedy



173 South side of cap




174 Hand grading SA-6 cap area




175 Graded surcharge material stockpiled on SA-7




176 Inspecting cover of SA-6 S cap area

# SA-6 South Chromium Remedy




177 Liner installation in south cap




178 Beginning to spread cover soil at station 23+00



179 Grading Eastern cap material



180 Spreading coversoil over south cap

# SA-6 South Chromium Remedy



181 Grading Eastern cap material



182 Spreading coversoil over south cap



183 Enddump placing coversoil onto south cap




184 Grading cap material

# SA-6 South Chromium Remedy



185 Grading Eastern cap material



186 Loading cap material



187 South cap demarcation layer



188 Plastic covered cap area




189 Screening surcharge soil directly into dump trucks for transport to the west side of the cap



190 South cap demarcation layer




191 Grading cap material



192 Spreading coversoil over south cap



193 ESI laying down GDL and demarcation layer on the south cap and P-122



194 Eastern edge of the south cap




195 Placing geomembrane layer on the eastern boundary of the south cap




196 Excavating the asphalt out of the SA-6S cap area at station 2+00

# SA-6 South Chromium Remedy




197 Installing liner on south cap near the eastern boundary




198 Placing geomembrane layer on the eastern boundary of the south cap




199 Placing soil onto the south side of the SA-6S cap near station 11+00




200 Placing geomembrane layer on the eastern boundary of the south cap

# SA-6 South Chromium Remedy



201 Geotextile fabric to cover stratum O from cells 24-29



202 Spreading coversoil on south cap




203 Screening Celgene soil into a truck to be transfered to the SA-6S cap



204 Spreading coversoil on south cap

# SA-6 South Chromium Remedy



205 Coversoil and warning tape progress along the south slope of the cap near station 9+00




206 Grading cap material




207 Regrading cap material




208 Regrading cap material

# SA-6 South Chromium Remedy




209 Creating ramp onto SA-6 S cap for coversoil




210 Grading cap material




211 Connecting GDL panels 1 and 2




212 Cementing SCB top on the north end of the east side of the south cap

# SA-6 South Chromium Remedy




213 Rolling out the first panel of GDL




214 3S cap area



215 3S cap area




216 Southern cap area




217 Moving material in southern cap




218 Placing material in southern cap




219 Installation of cap




220 Cap installation

# SA-6 South Chromium Remedy




221 SCB Mortor




222 Graded subgrade for the cap




223 SCB Grout




224 Cap Installation




225 Geofoam installed in utility corridor




226 GDL Installation




227 GDL Installation




228 GDL boot install around a piezometer




229 GDL boot install around a piezometer




230 Liner boot install around well




231 Extrusion welding liner around the contingent manhole




232 Extrusion welding around contingent manhole




233 Extrusion welding the skirt around manhole




234 GCL installation over SCB wall




235 GCL Deployment




236 Geofoam in utility corridor

# SA-6 South Chromium Remedy




237 GDL




238 Liner




239 Graded Subgrade




240 GDL & Liner

# SA-6 South Chromium Remedy




241 GCL placement




242 Liner




243 Liner install over GCL




244 Liner




245 Extrusion welding a repair patch at station 23+60




246 Welding liner panels P28 and P29




247 Unrolling a liner panel at station 11+00




248 Prepping truck with a liner

# SA-6 South Chromium Remedy



249 SA-6S truck decon



250 Pressure washing the epoxy coated sheets in cells 98 and 97




251 Poured grout mix over the SCB wall in the D Street corridor



252 Lining trucks

# SA-6 South Chromium Remedy




253 Laying out fabric and Celgene soil on 1S



254 SA-6S truck scale



255 SA-6S truck lining




256 Installing silt fence along the southern slope of N1 Pile



257 Road berm to prevent runoff




258 Repairing slope against SCB wall




259 Vacuum testing RP-1




260 Finishing the concrete on top of the SCB wall on the west side of D Street

# SA-6 South Chromium Remedy




261 Cemented SCB wall at avenue B along SA-6 S



262 Restoration Grade in SA-6 South Development Area



263 Restoration Grade in SA-6 South Development Area



264 60 Kellogg Excavation

# SA-6 South Chromium Remedy




265 60 Kellogg Excavation




266 60 Kellogg Excavation




267 Sampling event in 60 Kellogg Excavation



268 Grading topsoil to SA-6S Restoration Area on 10-28-16

# SA-6 South Chromium Remedy



269 Hydroseeding SA-6S Cap on 10-28-16



270 Grading topsoil along north edge of SA-6S cap on 10-26-16




271 Site 073 Deferred Area Sampling

# APPENDIX B

# ELECTRONIC DATA DELIVERABLE SUBMITTAL CONFIRMATION

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, April 06, 2016 4:50 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 003846, HCC140, HB180068 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC140_19970822_20120116.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 04/06/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 003846 it was sent on:

Your submission has been issued an SRP Catalog ID: HB180068 Thank You

The following identifiers were in the DTST file:
Directory: NJ030816
DESC: Honeywell SA-6
SRPID: HCC140
Submit Date: 3/8/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, September 30, 2016 12:01 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 003846, HCC140, HB198265 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC140_20160407_20160707.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 09/30/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 003846,HCC140,RPC930001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB198265 Thank You

The following identifiers were in the DTST file:
Directory: 14092316
DESC: Honeywell SA-6
SRPID: HCC140
Submit Date: 9/23/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Thursday, May 26, 2016 3:11 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 003846, HCC140, HB188456 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; 003846_20140918_20141008.KML; DTST.TXT; EDSA_Error_Log.html; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 05/26/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 003846, HCC140, RPC930001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB188456 Thank You

The following identifiers were in the DTST file:
Directory: NJ052416
DESC: Honeywell SA-6
SRPID: 003846
Submit Date: 5/24/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, April 01, 2016 5:33 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 010374, E20100027, HB179824 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; E20100027_20101102_20120322.KML; EDSA_Error_Log.html; HZRESULT.TXT; HZSAMPLE.TXT

**Follow Up Flag:** Flag for follow up
**Flag Status:** Flagged

The EDD submission shown below was processed 04/01/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 010374 it was sent on:

Your submission has been issued an SRP Catalog ID: HB179824 Thank You

The following identifiers were in the DTST file:
Directory: NJ030816
DESC: Honeywell SA-6
SRPID: E20100027
Submit Date: 3/8/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, September 30, 2016 12:01 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 010374, E20100027, HB198274 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; 010374_20160719_20160906.KML; DTST.TXT; EDSA_Error_Log.html; HZRESULT.TXT; HZSAMPLE.TXT

**Follow Up Flag:** Follow up
**Flag Status:** Completed

The EDD submission shown below was processed 09/30/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 010374, LSR100001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB198274 Thank You

The following identifiers were in the DTST file:
Directory: 16392816
DESC: Honeywell SA-6
SRPID: 010374
Submit Date: 9/28/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, April 06, 2016 4:50 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 033312, HCC134, HB180127 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC134_19970530_20141202.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 04/06/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 033312 it was sent on:

Your submission has been issued an SRP Catalog ID: HB180127 Thank You

The following identifiers were in the DTST file:
Directory: NJ030816
DESC: Honeywell SA-6
SRPID: HCC134
Submit Date: 3/8/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, September 30, 2016 12:01 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 033312, HCC134, HB198298 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC134_20160407_20160706.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 09/30/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 033312, HCC134, RPC050001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB198298 Thank You

The following identifiers were in the DTST file:
Directory: 13492316
DESC: Honeywell SA-6
SRPID: HCC134
Submit Date: 9/23/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Thursday, May 26, 2016 3:11 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** 033312, HCC134, HB188507 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; 033312_20140820_20141202.KML; DTST.TXT; EDSA_Error_Log.html; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 05/26/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: 033312, HCC134, RPC050001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB188507 Thank You

The following identifiers were in the DTST file:
Directory: NJ052416
DESC: Honeywell SA-6
SRPID: 033312
Submit Date: 5/24/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, September 30, 2016 12:01 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000000927, E20080042, HB198316 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; E20080042_20160406_20160706.KML; EDSA_Error_Log.html; HZRESULT.TXT; HZSAMPLE.TXT

**Follow Up Flag:** Follow up
**Flag Status:** Completed

The EDD submission shown below was processed 09/30/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000000927, E20080042, RPC030001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB198316 Thank You

The following identifiers were in the DTST file:
Directory: 07392316
DESC: Honeywell SA-6
SRPID: E20080042
Submit Date: 9/23/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, April 06, 2016 4:50 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000000927, HCC73, HB180134 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC73_20080709_20140612.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 04/06/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G0000000927 it was sent on:

Your submission has been issued an SRP Catalog ID: HB180134 Thank You

The following identifiers were in the DTST file:
Directory: NJ030816
DESC: Honeywell SA-6
SRPID: HCC73
Submit Date: 3/8/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, June 01, 2016 9:33 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000000927, E20080042, HB188695 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; G000000927_20140505_20140612.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 06/01/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000000927, E20080042, RPC03001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB188695 Thank You

The following identifiers were in the DTST file:
Directory: NJ052416
DESC: Honeywell SA-6
SRPID: G000000927
Submit Date: 5/26/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, July 01, 2016 8:13 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000000927, E20080042, HB189901 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; G000000927_20160509_20160510.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 07/01/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000000927, E20080042, RPC03001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB189901 Thank You

The following identifiers were in the DTST file:
Directory: NJ062716
DESC: Honeywell SA-6
SRPID: G000000927
Submit Date: 6/27/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, April 06, 2016 4:50 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008741, HCC124, HB180147 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC124_19970508_20120322.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 04/06/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G0000008741 it was sent on:

Your submission has been issued an SRP Catalog ID: HB180147 Thank You

The following identifiers were in the DTST file:
Directory: NJ030816
DESC: Honeywell SA-6
SRPID: HCC124
Submit Date: 3/8/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, September 30, 2016 12:01 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008741, HCC124, HB198317 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC124_20160408_20160707.KML; HZRESULT.TXT; HZSAMPLE.TXT

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

The EDD submission shown below was processed 09/30/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000008741, HCC124, RPC920001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB198317 Thank You

The following identifiers were in the DTST file:
Directory: 12492316
DESC: Honeywell SA-6
SRPID: HCC124
Submit Date: 9/23/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, December 07, 2016 5:51 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008741, HCC124, HB200334 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC124_20160901_20160906.KML; HZRESULT.TXT; HZSAMPLE.TXT

**Follow Up Flag:** Follow up
**Flag Status:** Completed

The EDD submission shown below was processed 12/07/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000008741, HCC124, PRC920001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB200334 Thank You

The following identifiers were in the DTST file:
Directory: 12412616
DESC: Honeywell SA-6
SRPID: HCC124
Submit Date: 12/6/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Wednesday, April 06, 2016 4:50 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008742, HCC125, HB180148 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC125_20080416_20120118.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 04/06/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G0000008742 it was sent on:

Your submission has been issued an SRP Catalog ID: HB180148 Thank You

The following identifiers were in the DTST file:
Directory: NJ030816
DESC: Honeywell SA-6
SRPID: HCC125
Submit Date: 3/8/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, September 30, 2016 12:01 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008742, HCC125, HB198318 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; HCC125_20160408_20160707.KML; HZRESULT.TXT; HZSAMPLE.TXT

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

The EDD submission shown below was processed 09/30/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000008742, HCC125, RPC930001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB198318 Thank You

The following identifiers were in the DTST file:
Directory: 12592316
DESC: Honeywell SA-6
SRPID: HCC125
Submit Date: 9/23/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Thursday, May 26, 2016 3:11 PM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008742, HCC125, HB188518 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; G000008742_20140326_20140326.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 05/26/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000008742, HCC125, RPC930001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB188518 Thank You

The following identifiers were in the DTST file:
Directory: NJ052416
DESC: Honeywell SA-6
SRPID: G000008742
Submit Date: 5/24/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

## Dunleavy, Timothy J

**From:** srpedd@dep.nj.gov
**Sent:** Friday, July 01, 2016 8:13 AM
**To:** Warner, Natalie A
**Cc:** hazsite@dep.nj.gov
**Subject:** G000008742, HCC125, HB189902 Passed
**Attachments:** erdtst-7-1-8.txt; erresult-7-1-8.txt; ersample-7-1-8.txt; rstp-7-1-8.txt; DTST.TXT; EDSA_Error_Log.html; G000008742_20160602_20160602.KML; HZRESULT.TXT; HZSAMPLE.TXT

The EDD submission shown below was processed 07/01/2016. This submission has passed and is cataloged in our system.
The email containing your EDD had the subject line of: G000008742, HCC125, RPC930001 it was sent on:

Your submission has been issued an SRP Catalog ID: HB189902 Thank You


The following identifiers were in the DTST file:
Directory: NJ062816
DESC: Honeywell SA-6
SRPID: G000008742
Submit Date: 6/28/2016

If you are using the email to process your EDD with your key document, include a copy of this email with your key document package.
This is an automated message.

# APPENDIX C

## RECORD DRAWINGS AND FINAL DOCUMENTATION
## (CD ONLY)

# PLAN VIEW




# PROFILE VIEW




## LEGEND

- 8" PERFORATED HDPE PIPE INVER (ELEV. TYPICAL)
- 4FT DIA. MANHOLE RISER PROFILE
- SCB WALL
- HYDRAULIC BARRIER WALL
- CAP SUBGRADE CONTOUR (DESIGN)
- CAP FINAL GRADE CONTOUR (DESIGN)
- 4FT DIA. MANHOLE
- 1.5" CLEAN STONE TRENCH (WIDTH VARIES 3' TO 12')

| REV | DATE | BY | CHK'D | APPR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 1/13/16 | CDC | AE | AE | RECORD DRAWING |
| 1 | 2/10/16 | CDC | AE | AE | ADDED ANNOTATION EDITS |
| 2 | 2/19/16 | CDC | AE | AE | REVISED ANNOTATION EDITS AND ADJUSTED MANHOLE REFERNCES |

J.H. 06/21/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP
CONTINGENT GROUNDWATER COLLECTION TRENCH
RECORD DRAWING 02/19/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

PZ16
N=684751.18
E=602508.94

PZ15
N=684735.78
E=602497.53

PZ14
N=684420.82
E=602907.51

PZ13
N=684391.71
E=602893.97

PZ12
N=684207.73
E=603276.91

PZ11
N=684200.51
E=603290.09

FINAL REMEDY GRADE CONTOURS AS BUILT SURFACE 2016-0922

INSTRUMENTATION CONDUIT DELETED

| SA-6 South Piezometers | | | |
|---|---|---|---|
| Well ID | TOC Elevation[1] | Top of Screen Elevation | Bottom of Well Elevation |
| PZ-11 | 15.89 | 5.67 | 0.67 |
| PZ-12 | 15.97 | 5.77 | 0.77 |
| PZ-13 | 16.02 | 5.86 | 0.86 |
| PZ-14 | 16.03 | 5.86 | 0.86 |
| PZ-15 | 14.16 | 3.91 | -1.09 |
| PZ-16 | 19.00 | 4.34 | -0.66 |
| PZ-17 | 18.07 | 3.13 | -1.87 |
| PZ-18 | 18.20 | 3.40 | -1.60 |
| PZ-19 | 17.91 | 3.16 | -1.84 |
| PZ-20 | 18.38 | 3.32 | -1.68 |

**Notes:**
1) TOC Elevations will change after final adjustment of piezometer
2) All screens are 5 ft long.

PZ20
N=685584.00
E=601504.14

PZ19
N=685587.17
E=601500.99

PZ18
N=685136.43
E=601988.86

PZ17
N=685121.22
E=601977.60

RECORD DRAWINGS - 12/20/16

Prepared/Date: RJR 12/20/16
Checked/Date: SGS 12/20/16

RECORD DRAWING - 12/20/16

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

Piezometer As Built Location
Project 3480-13-0377
Figure 2

Z:\Projects\HONEYWELL\JERSEY CITY\Dgn Design-SA6-CSX\CAD\SA6-North-South-RW_Extraction_Trench\SP314-C-001_Cont_RWE_Trench.dwg Tue, 05 Sep 2017 - 2:48pm tony.donovan

HACKENSACK RIVER

SA6 SOUTH CAP

SA6 NORTH CAP

RECORD DRAWING - 12/19/16

Refer to SA-6 South Design Drawing C-204 (DCB 007.4.1) for existing conduit and force main piping not installed under this contract.

Existing Cleanout N: 685998.35 E: 601903.64 El: 8.31'

Existing Cleanout N: 686003.68 E: 601906.17 El: 8.26'

Electrical Handhole N: 685651.58 E: 601550.68 El: 8.07'

Electrical Conduit N: 685652.46 E: 601553.03 El: 5.56'

Leak Detection N: 685687.13 E: 601564.17 El: 7.17'

Electrical Conduit N: 685686.91 E: 601587.96 El: 5.35'

3"x6" Pipe Top Elevation N: 685682.79 E: 601584.79 El: 1.86'

Wye Cleanout N: 685684.9 E: 601571.73 El: 7.05'

2"x4" Pipe Top Elevation N: 685651.98 E: 601553.89 El: 1.39'

Electrical Conduit N: 685648.24 E: 601550.95 El: 6.18'

(2) 2" Sch 40 Conduit

2"x4" Pipe Top Elevation N: 685648.24 E: 601553.73 El: 5.66'

Electrical Conduit N: 685598.02 E: 601613.38 El: 6.75'

2"x4" Pipe Top Elevation N: 685600.48 E: 601613.46 El: 8.63'

(2) 2" Sch 40 Conduit

Electrical Conduit N: 685568.99 E: 601677.64 El: 6.97'

2"x4" Pipe Top Elevation N: 685556.62 E: 601675.48 El: 6.97'

Electric Handhole N: 685503.28 E: 601742.93 El: 8.95'

Electrical Conduit N: 685500.28 E: 601743.38 El: 8.62'

Electrical Conduit N: 685481.75 E: 601730.52 El: 14.76'

Electrical Conduit N: 685504.28 E: 601742.83 El: 7.41'

2"x4" Pipe Top Elevation N: 685490.18 E: 601732.46 El: 14.71'

Elbow Cleanout N: 685505.72 E: 601750.51 El: 10.07'

2"x4" Pipe Top Elevation N: 685504.22 E: 601747.85 El: 7.22'

Electrical Conduit N: 685481.98 E: 601737.99 El: 15.7'

2"x4" Pipe Top Elevation N: 685443.98 E: 601741.93 El: 15.56'

(2) 2" Sch 40 Conduit

Electrical Conduit N: 685398.59 E: 601747.89 El: 16.03'

2"x4" Pipe Top Elevation N: 685412.93 E: 601747.24 El: 15.85'

Extraction Pump Station N: 685404.24 E: 601751.91 El: 18.9'

Electric Handhole N: 685392.83 E: 601751.17 El: 19.0'

(1) 2" Sch 40 Conduit

Electrical Conduit N: 685730.25 E: 601730.25 El: 5.85'

Electrical Conduit N: 685736.58 E: 601639.67 El: 5.5'

Electrical Conduit N: 685785.02 E: 601688.56 El: 5.27'

Electric Handhole N: 685822.76 E: 601730.68 El: 5.97'

(1) 2" Sch 40 Conduit

Electrical Conduit N: 685872.04 E: 601781.18 El: 5.3'

Electrical Conduit N: 685930.19 E: 601842.34 El: 5.53'

Electrical Conduit N: 686002.3 E: 601914.11 El: 8.4'

Electric Handhole N: 686005.13 E: 601916.99 El: 8.21'

Electric Handhole N: 686061.6 E: 602027.4 El: 16.68'

2"x4" Pipe Top Elevation El: 13.67'

2"x4" Pipe Top Elevation N: 686082.76 E: 602076.12 El: 13.16'

(3) 2" Sch 40 Conduit

2"x4" Pipe Top Elevation El: 14.18'

Air Release N: 686118.07 E: 602132.79 El: 18.43'

Electric Handhole N: 686048.48 E: 602028.15 El: 18.74'

3"x6" tie-in to 2"x4" Pipe N: 686049.98 E: 602030.54 El: 13.65'

(2) 2" Sch 40 Conduit

Electrical Conduit N: 686071.04 E: 602063.12 El: 13.92'

Electrical Conduit N: 686104.12 E: 602103.38 El: 14.53'

(3) 2" Sch 40 Conduit

2"x4" Pipe Top Elevation El: 14.57'

Electric Handhole N: 686087.6 E: 602084.41 El: 17.83'

(1) 2" Sch 40 Conduit

2"x4" Pipe Top Elevation N: 686104.56 E: 602178.43 El: 15.02'

Elbow Cleanout N: 686089.35 E: 602214.99 El: 17.95'

Electrical Conduit N: 686105.54 E: 602174.58 El: 15.51'

(3) 2" Sch 40 Conduit

2"x4" Pipe Top Elevation N: 686161.11 E: 602254.31 El: 13.79'

(4) 2" Sch 40 Conduit (2) 3" Sch 40 Conduit

Groundwater Treatment Plant

Electric Handhole N: 686062.11 E: 602275.94 El: 15.34'

Electrical Conduit N: 685785.02 E: 601688.56 El: 5.27'

Electric Handhole N: 686115.89 E: 602294.68 El: 16.83'

## LEGEND

- FO[illegible]AIN STATIONS
- ELE[illegible]C HANDHOLE
- SC[illegible]ALL
- HB WALL (Inner Edge)
- ELECTRICAL CONDUIT
- FORCEMAIN
- TEXT ELECTRICAL DESCRIPTION
- TEXT FORCEMAIN DESCRIPTION

0 80 160 Feet

SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | CONTINGENT GROUNDWATER EXTRACTION SYSTEM – SOUTH CAP |
| 1 | 12/19/16 | EJP | AE | AE | ADDED NOTES INDICATING QUANTITY OF CONDUITS |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
CONTINGENT GROUNDWATER EXTRACTION SYSTEM
SOUTH CAP
12/19/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

Honeywell SA-6 South
Chromium Remedy
Jersey City, New Jersey

Created By: T. Donovan 12/21/16
Checked By: S. Shallard 12/21/16

**TABLE 1. SA-6 SOUTH OPEN SPACE CAP AREA - CONSTRUCTION CONTROL GRID AS BUILT SUMMARY**

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | 685518.44 | 601481.51 | GRID | 15.72 | 15.73 | 1.11 | 0.55 | 20.00 | | 0.66 | 4.28 |
| 3 | 685543.44 | 601481.51 | GRID | 15.32 | 15.35 | 1.13 | 0.68 | 20.09 | | 0.57 | 4.74 |
| 4 | 685493.4362 | 601506.5129 | GRID | 14.21 | 14.19 | 1.29 | | 19.44 | | 0.55 | 5.25 |
| 6 | 685543.44 | 601506.51 | GRID | 16.56 | 16.64 | 1.12 | 0.45 | 20.14 | | 0.61 | 3.50 |
| 7 | 685568.44 | 601506.51 | GRID | 16.96 | 16.94 | 1.19 | 0.49 | 20.13 | | 0.55 | 3.19 |
| 8 | 685468.44 | 601531.51 | GRID | 13.09 | 13.12 | 1.11 | 0.74 | 18.81 | | 0.54 | 5.69 |
| 9 | 685493.44 | 601531.51 | GRID | 13.72 | 13.75 | 1.19 | 0.52 | 19.99 | | 0.54 | 6.24 |
| 10 | 685543.4362 | 601531.5129 | GRID | 14.75 | 14.84 | 1.17 | | 20.09 | | 0.53 | 5.25 |
| 11 | 685568.44 | 601531.51 | GRID | 15.00 | 15.08 | 1.18 | 0.64 | 20.29 | | 0.59 | 5.21 |
| 12 | 685593.44 | 601531.51 | GRID | 18.07 | 17.96 | 1.28 | 0.58 | 20.29 | | 0.46 | 2.32 |
| 14 | 685468.44 | 601556.51 | GRID | 13.86 | 13.86 | 1.21 | 0.56 | 18.98 | | 0.59 | 5.12 |
| 15 | 685493.44 | 601556.51 | GRID | 15.86 | 15.83 | 1.23 | 0.52 | 20.07 | | 0.50 | 4.24 |
| 16 | 685518.44 | 601556.51 | GRID | 16.67 | 16.76 | 1.14 | 0.48 | 20.07 | | 0.53 | 3.32 |
| 17 | 685543.4362 | 601556.5129 | GRID | 17.01 | 16.97 | 1.29 | | 20.19 | | 0.61 | 3.22 |
| 18 | 685568.4362 | 601556.5129 | GRID | 14.11 | 14.15 | 1.11 | | 20.23 | | 0.57 | 6.08 |
| 19 | 685593.44 | 601556.51 | GRID | 17.41 | 17.49 | 1.17 | 0.48 | 20.16 | | 0.55 | 2.67 |
| 20 | 685443.44 | 601581.51 | GRID | 13.26 | 13.31 | 1.11 | 0.65 | 18.25 | | 0.49 | 4.94 |
| 21 | 685468.44 | 601581.51 | GRID | 14.37 | 14.35 | 1.28 | 0.68 | 18.91 | | 0.49 | 4.56 |
| 22 | 685493.44 | 601581.51 | GRID | 15.75 | 15.69 | 1.30 | 0.49 | 20.04 | | 0.56 | 4.35 |
| 23 | 685518.44 | 601581.51 | GRID | 16.64 | 16.64 | 1.21 | 0.48 | 20.09 | | 0.51 | 3.45 |
| 24 | 685543.44 | 601581.51 | GRID | 17.49 | 17.50 | 1.10 | 0.50 | 20.15 | | 0.56 | 2.64 |
| 25 | 685568.4362 | 601581.5129 | GRID | 17.03 | 17.13 | 1.15 | | 20.10 | | 0.57 | 2.97 |
| 26 | 685418.44 | 601606.51 | GRID | 11.91 | 11.97 | 1.19 | 0.53 | 17.40 | | 0.60 | 5.43 |
| 27 | 685443.44 | 601606.51 | GRID | 13.82 | 13.80 | 1.30 | 0.65 | 18.39 | | 0.62 | 4.59 |
| 29 | 685493.44 | 601606.51 | GRID | 15.28 | 15.29 | 1.24 | 0.74 | 19.99 | | 0.60 | 4.70 |
| 30 | 685518.44 | 601606.51 | GRID | 16.15 | 16.21 | 1.17 | 0.67 | 20.09 | | 0.59 | 3.89 |
| 31 | 685543.44 | 601606.51 | GRID | 16.75 | 16.75 | 1.21 | 0.53 | 20.13 | | 0.58 | 3.37 |
| 32 | 685393.44 | 601631.51 | GRID | 11.44 | 11.47 | 1.19 | 0.72 | 17.23 | | 0.62 | 5.76 |
| 33 | 685418.44 | 601631.51 | GRID | 13.25 | 13.31 | 1.14 | 0.62 | 17.90 | | 0.55 | 4.58 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 34 | 685443.44 | 601631.51 | GRID | 13.79 | 13.80 | 1.19 | 0.51 | 18.27 | | 0.57 | 4.47 |
| 35 | 685468.44 | 601631.51 | GRID | 15.71 | 15.71 | 1.25 | 0.48 | 18.78 | | 0.66 | 3.06 |
| 36 | 685493.44 | 601631.51 | GRID | 14.79 | 14.80 | 1.26 | 0.54 | 19.52 | | 0.59 | 4.72 |
| 37 | 685518.44 | 601631.51 | GRID | 15.60 | 15.58 | 1.26 | 0.73 | 20.08 | | 0.61 | 4.50 |
| 38 | 685543.44 | 601631.51 | GRID | 16.01 | 15.98 | 1.26 | 0.58 | 20.10 | | 0.56 | 4.12 |
| 39 | 685393.44 | 601656.51 | GRID | 12.63 | 12.66 | 1.19 | 0.57 | 17.68 | | 0.58 | 5.02 |
| 40 | 685443.44 | 601656.51 | GRID | 13.74 | 13.70 | 1.21 | 0.59 | 18.34 | | 0.65 | 4.64 |
| 41 | 685468.44 | 601656.51 | GRID | 15.64 | 15.68 | 1.18 | 0.54 | 18.67 | | 0.57 | 3.00 |
| 42 | 685493.44 | 601656.51 | GRID | 16.11 | 16.13 | 1.22 | 0.48 | 19.10 | | 0.46 | 2.98 |
| 43 | 685518.44 | 601656.51 | GRID | 16.65 | 16.55 | 1.24 | 0.64 | 20.05 | | 0.51 | 3.50 |
| 44 | 685368.44 | 601681.51 | GRID | 11.59 | 11.63 | 1.22 | 0.66 | 17.43 | | 0.50 | 5.80 |
| 45 | 685393.44 | 601681.51 | GRID | 15.72 | 15.72 | 1.24 | 0.47 | 18.05 | | 0.62 | 2.34 |
| 46 | 685443.44 | 601681.51 | GRID | 13.67 | 13.64 | 1.25 | 0.47 | 18.22 | | 0.63 | 4.58 |
| 47 | 685468.44 | 601681.51 | GRID | 15.52 | 15.52 | 1.25 | 0.47 | 18.58 | | 0.57 | 3.06 |
| 48 | 685493.44 | 601681.51 | GRID | 15.97 | 15.95 | 1.26 | 0.47 | 18.97 | | 0.58 | 3.02 |
| 49 | 685343.44 | 601706.51 | GRID | 10.97 | 10.90 | 1.36 | 0.52 | 17.39 | | 0.54 | 6.49 |
| 50 | 685393.44 | 601706.51 | GRID | 15.97 | 15.96 | 1.21 | 0.58 | 18.27 | | 0.52 | 2.31 |
| 51 | 685443.44 | 601706.51 | GRID | 13.55 | 13.52 | 1.27 | 0.67 | 18.14 | | 0.51 | 4.62 |
| 52 | 685468.44 | 601706.51 | GRID | 15.38 | 15.37 | 1.21 | 0.48 | 18.07 | | 0.50 | 2.69 |
| 53 | 685493.44 | 601706.51 | GRID | 14.27 | 14.32 | 1.20 | 0.55 | 18.36 | | 0.50 | 4.04 |
| 54 | 685318.44 | 601731.51 | GRID | 10.69 | 10.63 | 1.18 | 0.52 | 17.92 | | 0.54 | 7.29 |
| 55 | 685368.44 | 601731.51 | GRID | 16.17 | 16.14 | 1.22 | 0.60 | 18.51 | | 0.55 | 2.37 |
| 56 | 685393.44 | 601731.51 | GRID | 16.28 | 16.24 | 1.25 | 0.50 | 18.61 | | 0.62 | 2.37 |
| 57 | 685443.44 | 601731.51 | GRID | 13.53 | 13.48 | 1.32 | 0.50 | 18.08 | | 0.54 | 4.60 |
| 58 | 685343.44 | 601756.51 | GRID | 16.57 | 16.54 | 1.14 | 0.52 | 18.99 | | 0.65 | 2.45 |
| 59 | 685368.44 | 601756.51 | GRID | 16.33 | 16.35 | 1.15 | 0.60 | 18.71 | | 0.61 | 2.36 |
| 61 | 685443.44 | 601756.51 | GRID | 13.55 | 13.55 | 1.12 | 0.84 | 18.09 | | 0.61 | 4.53 |
| 62 | 685293.4362 | 601781.5129 | GRID | 10.50 | 10.42 | 1.25 | | 19.14 | | 0.60 | 8.73 |
| 63 | 685318.44 | 601781.51 | GRID | 17.40 | 17.40 | 1.15 | 0.50 | 19.62 | | 0.57 | 2.22 |
| 64 | 685343.44 | 601781.51 | GRID | 16.94 | 16.91 | 1.13 | 0.53 | 19.47 | | 0.65 | 2.55 |
| 65 | 685368.44 | 601781.51 | GRID | 16.55 | 16.53 | 1.20 | 0.58 | 18.97 | | 0.66 | 2.44 |
| 66 | 685393.44 | 601781.51 | GRID | 16.31 | 16.26 | 1.21 | 0.62 | 18.61 | | 0.51 | 2.34 |
| 67 | 685418.44 | 601781.51 | GRID | 16.14 | 16.13 | 1.17 | 0.52 | 18.36 | | 0.53 | 2.22 |
| 69 | 685268.4362 | 601806.5129 | GRID | 11.03 | 10.95 | 1.32 | | 19.36 | | 0.56 | 8.41 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 70 | 685318.44 | 601806.51 | GRID | 18.11 | 18.05 | 1.20 | 0.50 | 20.30 | | 0.56 | 2.25 |
| 71 | 685343.44 | 601806.51 | GRID | 17.66 | 17.63 | 1.17 | 0.45 | 19.87 | | 0.56 | 2.24 |
| 72 | 685368.44 | 601806.51 | GRID | 17.12 | 17.11 | 1.13 | 0.56 | 19.39 | | 0.59 | 2.28 |
| 73 | 685393.44 | 601806.51 | GRID | 16.68 | 16.61 | 1.20 | 0.52 | 18.96 | | 0.63 | 2.35 |
| 74 | 685418.44 | 601806.51 | GRID | 16.28 | 16.27 | 1.19 | 0.48 | 18.56 | | 0.56 | 2.29 |
| 75 | 685243.4362 | 601831.5129 | GRID | 12.66 | 12.64 | 1.28 | | 19.11 | | 0.46 | 6.47 |
| 77 | 685318.4362 | 601831.5129 | GRID | 15.70 | 15.68 | 1.28 | | 20.55 | | 0.55 | 4.87 |
| 78 | 685343.44 | 601831.51 | GRID | 18.29 | 18.27 | 1.19 | 0.47 | 20.61 | | 0.68 | 2.34 |
| 79 | 685368.44 | 601831.51 | GRID | 17.73 | 17.67 | 1.22 | 0.45 | 20.02 | | 0.59 | 2.35 |
| 80 | 685393.44 | 601831.51 | GRID | 17.22 | 17.25 | 1.05 | 0.51 | 19.27 | | 0.46 | 2.02 |
| 81 | 685243.44 | 601856.51 | GRID | 15.58 | 15.64 | 1.18 | 0.50 | 20.33 | | 0.52 | 4.69 |
| 82 | 685268.44 | 601856.51 | GRID | 16.08 | 16.08 | 1.25 | 0.48 | 20.55 | | 0.54 | 4.47 |
| 83 | 685293.4362 | 601856.5129 | GRID | 15.74 | 15.83 | 1.18 | | 20.72 | | 0.65 | 4.89 |
| 85 | 685368.44 | 601856.51 | GRID | 18.00 | 17.99 | 1.20 | 0.45 | 20.24 | | 0.60 | 2.26 |
| 86 | 685218.44 | 601881.51 | GRID | 15.64 | 15.58 | 1.16 | 0.60 | 20.38 | | 0.58 | 4.81 |
| 87 | 685243.44 | 601881.51 | GRID | 16.37 | 16.38 | 1.15 | 0.55 | 20.84 | | 0.66 | 4.47 |
| 88 | 685268.44 | 601881.51 | GRID | 18.72 | 18.68 | 1.16 | 0.54 | 20.97 | | 0.58 | 2.29 |
| 89 | 685293.44 | 601881.51 | GRID | 18.57 | 18.49 | 1.19 | 0.60 | 20.86 | | 0.58 | 2.37 |
| 90 | 685343.4362 | 601881.5129 | GRID | 15.15 | 15.20 | 1.20 | | 20.12 | | 0.48 | 4.91 |
| 91 | 685368.4362 | 601881.5129 | GRID | 11.78 | 11.78 | 1.23 | | 17.65 | | 0.52 | 5.86 |
| 92 | 685193.44 | 601906.51 | GRID | 15.54 | 15.50 | 1.14 | 0.75 | 20.38 | | 0.69 | 4.89 |
| 93 | 685218.44 | 601906.51 | GRID | 16.30 | 16.26 | 1.19 | 0.53 | 20.87 | | 0.69 | 4.61 |
| 94 | 685243.44 | 601906.51 | GRID | 18.74 | 18.67 | 1.21 | 0.56 | 21.09 | | 0.66 | 2.43 |
| 95 | 685268.44 | 601906.51 | GRID | 18.62 | 18.56 | 1.17 | 0.58 | 20.84 | | 0.53 | 2.28 |
| 96 | 685293.44 | 601906.51 | GRID | 18.47 | 18.40 | 1.16 | 0.59 | 20.71 | | 0.56 | 2.31 |
| 97 | 685318.44 | 601906.51 | GRID | 18.31 | 18.32 | 1.14 | 0.49 | 20.56 | | 0.60 | 2.23 |
| 99 | 685193.44 | 601931.51 | GRID | 15.75 | 15.79 | 1.10 | 0.81 | 20.60 | | 0.78 | 4.81 |
| 101 | 685243.44 | 601931.51 | GRID | 18.58 | 18.54 | 1.17 | 0.53 | 20.81 | | 0.57 | 2.27 |
| 102 | 685268.44 | 601931.51 | GRID | 18.48 | 18.43 | 1.15 | 0.58 | 20.72 | | 0.56 | 2.29 |
| 103 | 685293.44 | 601931.51 | GRID | 18.37 | 18.36 | 1.19 | 0.51 | 20.57 | | 0.51 | 2.21 |
| 104 | 685168.44 | 601956.51 | GRID | 14.56 | 14.64 | 1.11 | 0.65 | 19.76 | | 0.63 | 5.12 |
| 105 | 685193.44 | 601956.51 | GRID | 18.03 | 18.13 | 1.04 | 0.52 | 20.27 | | 0.58 | 2.14 |
| 107 | 685243.44 | 601956.51 | GRID | 18.28 | 18.37 | 1.05 | 0.55 | 20.57 | | 0.61 | 2.20 |
| 108 | 685268.44 | 601956.51 | GRID | 18.29 | 18.38 | 1.03 | 0.58 | 20.62 | | 0.63 | 2.24 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 109 | 685293.44 | 601956.51 | GRID | 18.22 | 18.30 | 1.02 | 0.57 | 20.56 | | 0.66 | 2.26 |
| 110 | 685143.44 | 601981.51 | GRID | 13.64 | 13.74 | 1.03 | 0.59 | 18.81 | | 0.77 | 5.08 |
| 111 | 685168.44 | 601981.51 | GRID | 17.22 | 17.31 | 1.04 | 0.56 | 19.46 | | 0.55 | 2.15 |
| 112 | 685193.44 | 601981.51 | GRID | 17.44 | 17.54 | 1.01 | 0.60 | 19.70 | | 0.56 | 2.16 |
| 113 | 685218.44 | 601981.51 | GRID | 17.67 | 17.75 | 1.04 | 0.55 | 19.88 | | 0.55 | 2.13 |
| 114 | 685243.44 | 601981.51 | GRID | 17.85 | 17.94 | 1.00 | 0.62 | 20.15 | | 0.59 | 2.21 |
| 115 | 685268.44 | 601981.51 | GRID | 17.92 | 18.01 | 1.02 | 0.52 | 20.30 | | 0.75 | 2.29 |
| 116 | 685118.44 | 602006.51 | GRID | 13.00 | 13.10 | 1.00 | 0.58 | 17.83 | | 0.59 | 4.74 |
| 117 | 685168.44 | 602006.51 | GRID | 16.62 | 16.71 | 1.05 | 0.55 | 19.20 | | 0.72 | 2.49 |
| 118 | 685193.44 | 602006.51 | GRID | 16.85 | 16.94 | 1.06 | 0.52 | 19.20 | | 0.67 | 2.26 |
| 119 | 685218.44 | 602006.51 | GRID | 17.08 | 17.16 | 1.05 | 0.55 | 19.37 | | 0.60 | 2.20 |
| 121 | 685268.44 | 602006.51 | GRID | 17.52 | 17.59 | 1.05 | 0.58 | 19.69 | | 0.47 | 2.10 |
| 122 | 685118.44 | 602031.51 | GRID | 13.00 | 13.10 | 1.12 | 0.45 | 17.95 | | 0.59 | 4.85 |
| 123 | 685143.44 | 602031.51 | GRID | 16.11 | 16.20 | 1.03 | 0.55 | 19.08 | | 0.61 | 2.87 |
| 124 | 685168.44 | 602031.51 | GRID | 16.20 | 16.30 | 1.15 | 0.55 | 18.90 | | 0.52 | 2.60 |
| 125 | 685193.44 | 602031.51 | GRID | 16.32 | 16.39 | 1.18 | 0.50 | 18.93 | | 0.68 | 2.54 |
| 126 | 685218.44 | 602031.51 | GRID | 16.50 | 16.59 | 1.07 | 0.53 | 18.92 | | 0.72 | 2.32 |
| 127 | 685118.44 | 602056.51 | GRID | 14.00 | 13.92 | 1.26 | 0.59 | 18.61 | | 0.55 | 4.69 |
| 128 | 685143.44 | 602056.51 | GRID | 16.15 | 16.22 | 1.06 | 0.55 | 19.10 | | 0.64 | 2.87 |
| 129 | 685168.44 | 602056.51 | GRID | 16.07 | 16.16 | 1.02 | 0.56 | 19.07 | | 0.53 | 2.91 |
| 130 | 685193.44 | 602056.51 | GRID | 16.21 | 16.29 | 1.13 | 0.45 | 18.77 | | 0.54 | 2.48 |
| 131 | 685218.44 | 602056.51 | GRID | 16.34 | 16.43 | 1.08 | 0.57 | 18.64 | | 0.55 | 2.21 |
| 132 | 685068.4362 | 602081.5129 | GRID | 4.37 | 4.46 | 1.01 | | 18.34 | 0.75 | | 13.88 |
| 134 | 685143.44 | 602081.51 | GRID | 16.50 | 16.58 | 1.08 | 0.50 | 19.05 | | 0.56 | 2.46 |
| 135 | 685168.44 | 602081.51 | GRID | 16.30 | 16.39 | 1.00 | 0.58 | 19.11 | | 0.59 | 2.72 |
| 136 | 685193.44 | 602081.51 | GRID | 16.11 | 16.19 | 1.00 | 0.59 | 18.95 | | 0.61 | 2.77 |
| 137 | 685218.44 | 602081.51 | GRID | 16.14 | 16.23 | 1.10 | 0.46 | 18.61 | | 0.56 | 2.38 |
| 138 | 685043.4362 | 602106.5129 | GRID | 4.55 | 4.49 | 1.27 | | 18.20 | | 0.55 | 13.71 |
| 140 | 685093.4362 | 602106.5129 | GRID | 4.78 | 4.86 | 1.01 | | 19.05 | 0.56 | | 14.19 |
| 141 | 685118.4362 | 602106.5129 | GRID | 5.02 | 5.08 | 1.02 | | 19.08 | | 0.64 | 14.00 |
| 142 | 685168.44 | 602106.51 | GRID | 16.64 | 16.73 | 1.02 | 0.61 | 19.09 | | 0.59 | 2.36 |
| 143 | 685193.44 | 602106.51 | GRID | 16.31 | 16.40 | 1.01 | 0.57 | 19.12 | | 0.67 | 2.72 |
| 144 | 685068.44 | 602131.51 | GRID | 14.98 | 15.01 | 1.16 | 0.66 | 19.13 | | 0.53 | 4.12 |
| 145 | 685118.4362 | 602131.5129 | GRID | 5.19 | 5.13 | 1.15 | | 19.05 | 0.55 | | 13.92 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 146 | 685143.4362 | 602131.5129 | GRID | 5.42 | 5.50 | 1.01 | | 19.07 | 0.54 | | 13.57 |
| 147 | 685043.44 | 602156.51 | GRID | 15.05 | 15.06 | 1.23 | 0.64 | 19.70 | | 0.54 | 4.64 |
| 148 | 685093.44 | 602156.51 | GRID | 17.85 | 17.78 | 1.18 | 0.58 | 20.09 | | 0.56 | 2.31 |
| 149 | 685143.4362 | 602156.5129 | GRID | 5.59 | 5.61 | 1.10 | | 19.11 | 0.54 | | 13.50 |
| 150 | 685168.4362 | 602156.5129 | GRID | 5.82 | 5.88 | 1.03 | | 18.70 | 0.50 | | 12.82 |
| 151 | 684993.44 | 602181.51 | GRID | 5.65 | 5.58 | 1.19 | 0.77 | 19.43 | | 0.59 | 13.85 |
| 152 | 685018.44 | 602181.51 | GRID | 15.74 | 15.82 | 1.18 | 0.56 | 20.06 | | 0.58 | 4.24 |
| 153 | 685043.44 | 602181.51 | GRID | 15.20 | 15.28 | 1.15 | 0.83 | 20.01 | | 0.51 | 4.73 |
| 154 | 685068.44 | 602181.51 | GRID | 17.51 | 17.56 | 1.06 | 0.55 | 20.16 | | 0.80 | 2.59 |
| 155 | 685093.44 | 602181.51 | GRID | 17.55 | 17.57 | 1.06 | 0.58 | 19.93 | | 0.72 | 2.36 |
| 156 | 685118.44 | 602181.51 | GRID | 17.55 | 17.55 | 1.11 | 0.59 | 19.76 | | 0.51 | 2.21 |
| 157 | 685143.44 | 602181.51 | GRID | 14.65 | 14.72 | 1.13 | 0.52 | 19.19 | | 0.49 | 4.47 |
| 159 | 684968.44 | 602206.51 | GRID | 6.08 | 6.09 | 1.08 | 0.60 | 20.30 | | 0.57 | 14.21 |
| 160 | 685018.44 | 602206.51 | GRID | 18.26 | 18.28 | 1.10 | 0.58 | 20.45 | | 0.50 | 2.17 |
| 161 | 685068.44 | 602206.51 | GRID | 17.61 | 17.61 | 1.08 | 0.63 | 20.11 | | 0.72 | 2.50 |
| 162 | 684993.44 | 602231.51 | GRID | 18.81 | 18.84 | 1.12 | 0.57 | 21.06 | | 0.53 | 2.22 |
| 163 | 685018.44 | 602231.51 | GRID | 16.00 | 15.94 | 1.18 | 0.90 | 20.74 | | 0.72 | 4.80 |
| 164 | 685068.44 | 602231.51 | GRID | 17.85 | 17.78 | 1.22 | 0.54 | 20.12 | | 0.58 | 2.34 |
| 165 | 685093.44 | 602231.51 | GRID | 15.01 | 15.11 | 1.06 | 0.94 | 19.88 | | 0.69 | 4.77 |
| 166 | 684968.44 | 602256.51 | GRID | 19.36 | 19.37 | 1.10 | 0.55 | 21.58 | | 0.56 | 2.21 |
| 167 | 684993.44 | 602256.51 | GRID | 19.06 | 19.05 | 1.13 | 0.55 | 21.28 | | 0.55 | 2.23 |
| 168 | 685018.44 | 602256.51 | GRID | 16.25 | 16.26 | 1.08 | 0.69 | 20.98 | | 0.76 | 4.72 |
| 169 | 685043.44 | 602256.51 | GRID | 18.43 | 18.44 | 1.11 | 0.60 | 20.65 | | 0.50 | 2.21 |
| 170 | 685068.44 | 602256.51 | GRID | 18.10 | 18.08 | 1.14 | 0.56 | 20.30 | | 0.52 | 2.22 |
| 171 | 684918.44 | 602281.51 | GRID | 7.15 | 7.15 | 1.13 | 0.90 | 21.67 | | 0.49 | 14.52 |
| 172 | 684968.44 | 602281.51 | GRID | 19.61 | 19.63 | 1.07 | 0.59 | 21.81 | | 0.52 | 2.17 |
| 173 | 684993.44 | 602281.51 | GRID | 16.82 | 16.83 | 1.10 | 0.94 | 21.50 | | 0.70 | 4.68 |
| 174 | 685018.44 | 602281.51 | GRID | 19.00 | 19.00 | 1.09 | 0.59 | 21.27 | | 0.58 | 2.27 |
| 175 | 685043.44 | 602281.51 | GRID | 18.69 | 18.68 | 1.13 | 0.60 | 20.91 | | 0.50 | 2.23 |
| 176 | 685068.44 | 602281.51 | GRID | 18.36 | 18.36 | 1.08 | 0.61 | 20.60 | | 0.55 | 2.24 |
| 178 | 684943.44 | 602306.51 | GRID | 20.15 | 20.17 | 1.10 | 0.53 | 22.37 | | 0.57 | 2.20 |
| 179 | 684968.44 | 602306.51 | GRID | 19.86 | 19.89 | 1.17 | 0.48 | 22.09 | | 0.55 | 2.20 |
| 180 | 684993.44 | 602306.51 | GRID | 17.07 | 17.10 | 1.10 | 0.90 | 21.85 | | 0.75 | 4.75 |
| 181 | 685018.44 | 602306.51 | GRID | 19.26 | 19.27 | 1.09 | 0.55 | 21.57 | | 0.66 | 2.30 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 182 | 685043.44 | 602306.51 | GRID | 16.45 | 16.37 | 1.23 | 0.83 | 21.20 | | 0.69 | 4.84 |
| 183 | 684918.44 | 602331.51 | GRID | 17.91 | 17.93 | 1.19 | 0.49 | 22.38 | | 0.53 | 4.45 |
| 184 | 684943.44 | 602331.51 | GRID | 17.80 | 17.81 | 1.15 | 0.52 | 22.29 | | 0.53 | 4.48 |
| 185 | 684968.44 | 602331.51 | GRID | 17.57 | 17.49 | 1.23 | 0.54 | 22.04 | | 0.49 | 4.55 |
| 186 | 684993.44 | 602331.51 | GRID | 19.82 | 19.76 | 1.22 | 0.53 | 22.09 | | 0.58 | 2.33 |
| 187 | 685018.44 | 602331.51 | GRID | 17.03 | 16.94 | 1.18 | 0.99 | 21.41 | | 0.52 | 4.47 |
| 188 | 684893.44 | 602356.51 | GRID | 17.90 | 17.86 | 1.21 | 0.48 | 22.14 | | 0.49 | 4.28 |
| 189 | 684918.44 | 602356.51 | GRID | 17.87 | 17.86 | 1.14 | 0.57 | 22.28 | | 0.55 | 4.42 |
| 190 | 684943.44 | 602356.51 | GRID | 17.85 | 17.84 | 1.18 | 0.49 | 22.25 | | 0.51 | 4.41 |
| 191 | 684968.44 | 602356.51 | GRID | 17.68 | 17.67 | 1.16 | 0.52 | 22.06 | | 0.47 | 4.39 |
| 192 | 684993.44 | 602356.51 | GRID | 17.48 | 17.47 | 1.17 | 0.53 | 22.05 | | 0.55 | 4.58 |
| 193 | 684843.44 | 602381.51 | GRID | 8.70 | 8.73 | 1.20 | 0.46 | 21.34 | | 0.56 | 12.61 |
| 194 | 684868.44 | 602381.51 | GRID | 17.37 | 17.31 | 1.20 | 0.52 | 21.87 | | 0.53 | 4.56 |
| 195 | 684893.44 | 602381.51 | GRID | 17.65 | 17.65 | 1.19 | 0.47 | 22.09 | | 0.53 | 4.44 |
| 196 | 684918.44 | 602381.51 | GRID | 17.82 | 17.83 | 1.10 | 0.60 | 22.19 | | 0.58 | 4.37 |
| 197 | 684943.44 | 602381.51 | GRID | 17.81 | 17.81 | 1.17 | 0.52 | 22.24 | | 0.56 | 4.44 |
| 198 | 684968.44 | 602381.51 | GRID | 17.78 | 17.79 | 1.20 | 0.51 | 22.12 | | 0.49 | 4.34 |
| 199 | 684993.44 | 602381.51 | GRID | 17.62 | 17.62 | 1.16 | 0.49 | 22.02 | | 0.53 | 4.40 |
| 200 | 684868.44 | 602406.51 | GRID | 16.97 | 16.99 | 1.16 | 0.46 | 21.53 | | 0.52 | 4.54 |
| 201 | 684893.44 | 602406.51 | GRID | 17.32 | 17.32 | 1.13 | 0.54 | 21.87 | | 0.54 | 4.55 |
| 202 | 684918.44 | 602406.51 | GRID | 17.63 | 17.62 | 1.21 | 0.50 | 22.11 | | 0.59 | 4.49 |
| 203 | 684943.44 | 602406.51 | GRID | 17.73 | 17.70 | 1.17 | 0.58 | 22.11 | | 0.51 | 4.42 |
| 204 | 684968.44 | 602406.51 | GRID | 17.76 | 17.73 | 1.17 | 0.55 | 22.07 | | 0.53 | 4.34 |
| 205 | 684818.44 | 602431.51 | GRID | 15.03 | 15.11 | 1.12 | 0.52 | 20.06 | | 0.51 | 4.95 |
| 206 | 684843.44 | 602431.51 | GRID | 16.11 | 16.09 | 1.23 | 0.48 | 20.63 | | 0.51 | 4.54 |
| 207 | 684868.44 | 602431.51 | GRID | 16.57 | 16.59 | 1.15 | 0.54 | 21.17 | | 0.52 | 4.58 |
| 208 | 684893.44 | 602431.51 | GRID | 17.00 | 16.94 | 1.22 | 0.54 | 21.54 | | 0.53 | 4.59 |
| 209 | 684918.44 | 602431.51 | GRID | 17.37 | 17.34 | 1.20 | 0.53 | 21.70 | | 0.53 | 4.36 |
| 210 | 684943.44 | 602431.51 | GRID | 17.60 | 17.63 | 1.17 | 0.48 | 22.03 | | 0.51 | 4.40 |
| 211 | 684793.44 | 602456.51 | GRID | 14.01 | 13.97 | 1.24 | 0.62 | 19.12 | | 0.52 | 5.15 |
| 212 | 684818.44 | 602456.51 | GRID | 15.20 | 15.17 | 1.24 | 0.45 | 19.70 | | 0.54 | 4.53 |
| 213 | 684843.44 | 602456.51 | GRID | 15.74 | 15.74 | 1.19 | 0.50 | 20.31 | | 0.56 | 4.57 |
| 214 | 684868.44 | 602456.51 | GRID | 16.27 | 16.27 | 1.15 | 0.57 | 20.85 | | 0.56 | 4.58 |
| 215 | 684893.44 | 602456.51 | GRID | 16.69 | 16.68 | 1.17 | 0.50 | 21.13 | | 0.57 | 4.45 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 216 | 684918.44 | 602456.51 | GRID | 17.11 | 17.07 | 1.19 | 0.56 | 21.26 | | 0.53 | 4.19 |
| 217 | 684768.44 | 602481.51 | GRID | 13.24 | 13.23 | 1.15 | 0.64 | 18.03 | | 0.57 | 4.80 |
| 218 | 684793.44 | 602481.51 | GRID | 14.27 | 14.21 | 1.27 | 0.53 | 18.74 | | 0.57 | 4.53 |
| 219 | 684818.44 | 602481.51 | GRID | 14.86 | 14.85 | 1.18 | 0.51 | 19.41 | | 0.56 | 4.56 |
| 220 | 684843.44 | 602481.51 | GRID | 15.42 | 15.44 | 1.18 | 0.49 | 19.97 | | 0.50 | 4.53 |
| 221 | 684868.44 | 602481.51 | GRID | 15.93 | 15.91 | 1.20 | 0.49 | 20.48 | | 0.51 | 4.57 |
| 222 | 684893.44 | 602481.51 | GRID | 16.43 | 16.40 | 1.16 | 0.58 | 21.03 | | 0.55 | 4.63 |
| 223 | 684918.44 | 602481.51 | GRID | 16.87 | 16.84 | 1.17 | 0.58 | 21.07 | | 0.55 | 4.23 |
| 224 | 684768.44 | 602506.51 | GRID | 13.31 | 13.28 | 1.25 | 0.58 | 18.06 | | 0.59 | 4.77 |
| 225 | 684793.44 | 602506.51 | GRID | 13.98 | 14.03 | 1.04 | 0.65 | 18.50 | | 0.55 | 4.47 |
| 226 | 684818.44 | 602506.51 | GRID | 14.55 | 14.49 | 1.19 | 0.69 | 19.12 | | 0.55 | 4.63 |
| 227 | 684843.44 | 602506.51 | GRID | 15.10 | 15.05 | 1.22 | 0.58 | 19.68 | | 0.55 | 4.63 |
| 228 | 684868.44 | 602506.51 | GRID | 15.62 | 15.62 | 1.16 | 0.60 | 20.33 | | 0.59 | 4.71 |
| 229 | 684893.44 | 602506.51 | GRID | 16.12 | 16.18 | 1.12 | 0.56 | 20.66 | | 0.46 | 4.48 |
| 230 | 684743.44 | 602531.51 | GRID | 12.58 | 12.60 | 1.14 | 0.76 | 17.67 | | 0.52 | 5.07 |
| 231 | 684768.44 | 602531.51 | GRID | 15.82 | 15.81 | 1.21 | 0.47 | 18.01 | | 0.52 | 2.20 |
| 232 | 684793.44 | 602531.51 | GRID | 16.25 | 16.22 | 1.22 | 0.47 | 18.48 | | 0.56 | 2.26 |
| 233 | 684818.44 | 602531.51 | GRID | 16.76 | 16.69 | 1.26 | 0.47 | 18.91 | | 0.49 | 2.22 |
| 234 | 684843.44 | 602531.51 | GRID | 17.30 | 17.35 | 1.12 | 0.54 | 19.59 | | 0.58 | 2.24 |
| 235 | 684868.44 | 602531.51 | GRID | 17.86 | 17.87 | 1.17 | 0.50 | 20.12 | | 0.59 | 2.26 |
| 236 | 684718.44 | 602556.51 | GRID | 7.45 | 7.45 | 1.21 | 0.84 | 17.22 | | 0.55 | 9.77 |
| 237 | 684743.44 | 602556.51 | GRID | 15.59 | 15.67 | 1.18 | 0.46 | 17.80 | | 0.50 | 2.14 |
| 239 | 684843.44 | 602556.51 | GRID | 17.05 | 17.13 | 1.05 | 0.57 | 19.29 | | 0.55 | 2.16 |
| 240 | 684868.44 | 602556.51 | GRID | 17.59 | 17.65 | 1.03 | 0.56 | 19.81 | | 0.58 | 2.17 |
| 241 | 684693.4362 | 602581.5129 | GRID | 5.82 | 5.81 | 1.28 | | 17.31 | | 0.57 | 11.50 |
| 242 | 684718.44 | 602581.51 | GRID | 13.18 | 13.26 | 1.14 | 0.51 | 17.84 | | 0.47 | 4.58 |
| 243 | 684743.44 | 602581.51 | GRID | 15.71 | 15.69 | 1.19 | 0.49 | 17.99 | | 0.59 | 2.30 |
| 244 | 684768.44 | 602581.51 | GRID | 13.86 | 13.79 | 1.26 | 0.55 | 18.43 | | 0.51 | 4.64 |
| 245 | 684793.44 | 602581.51 | GRID | 14.14 | 14.11 | 1.13 | 0.68 | 18.80 | | 0.54 | 4.69 |
| 246 | 684818.44 | 602581.51 | GRID | 14.12 | 14.10 | 1.19 | 0.55 | 19.01 | | 0.53 | 4.90 |
| 247 | 684843.44 | 602581.51 | GRID | 14.33 | 14.41 | 1.11 | 0.77 | 19.01 | | 0.56 | 4.59 |
| 248 | 684693.4362 | 602606.5129 | GRID | 5.20 | 5.29 | 1.15 | | 18.71 | | 0.56 | 13.41 |
| 249 | 684743.44 | 602606.51 | GRID | 16.46 | 16.49 | 1.12 | 0.54 | 19.12 | | 0.59 | 2.64 |
| 250 | 684768.44 | 602606.51 | GRID | 15.98 | 16.03 | 1.19 | 0.53 | 19.10 | | 0.54 | 3.07 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 251 | 684793.44 | 602606.51 | GRID | 14.46 | 14.37 | 1.24 | 0.54 | 19.06 | | 0.54 | 4.69 |
| 252 | 684818.44 | 602606.51 | GRID | 14.27 | 14.32 | 1.10 | 0.60 | 19.08 | | 0.53 | 4.76 |
| 253 | 684693.4362 | 602631.5129 | GRID | 5.45 | 5.52 | 1.07 | | 19.05 | | 0.56 | 13.53 |
| 254 | 684718.4362 | 602631.5129 | GRID | 5.80 | 5.85 | 1.10 | | 19.11 | | 0.52 | 13.26 |
| 255 | 684768.44 | 602631.51 | GRID | 17.04 | 17.07 | 1.17 | 0.45 | 19.31 | | 0.55 | 2.23 |
| 256 | 684793.44 | 602631.51 | GRID | 16.34 | 16.43 | 1.03 | 0.56 | 19.09 | | 0.50 | 2.66 |
| 257 | 684818.44 | 602631.51 | GRID | 16.19 | 16.18 | 1.12 | 0.59 | 19.04 | | 0.52 | 2.86 |
| 259 | 684718.4362 | 602656.5129 | GRID | 6.06 | 5.98 | 1.28 | | 19.35 | | 0.52 | 13.37 |
| 260 | 684743.4362 | 602656.5129 | GRID | 6.41 | 6.45 | 1.08 | | 19.24 | | 0.62 | 12.79 |
| 261 | 684793.44 | 602656.51 | GRID | 14.54 | 14.62 | 1.12 | 0.61 | 19.07 | | 0.55 | 4.46 |
| 263 | 684743.4362 | 602681.5129 | GRID | 6.67 | 6.69 | 1.22 | | 19.49 | | 0.64 | 12.81 |
| 264 | 684768.4362 | 602681.5129 | GRID | 7.01 | 7.01 | 1.13 | | 18.98 | | 0.59 | 11.97 |
| 265 | 684793.4362 | 602681.5129 | GRID | 7.37 | 7.34 | 1.21 | | 17.88 | | 0.65 | 10.54 |
| 545 | 685526.43 | 601442.32 | BNDY | 12.92 | 13.01 | 1.02 | 0.57 | 15.13 | | 0.54 | 2.12 |
| 546 | 685543.45 | 601459.45 | BNDY | 13.45 | 13.37 | 1.27 | 0.46 | 15.63 | | 0.52 | 2.25 |
| 547 | 685561.91 | 601478.03 | BNDY | 14.24 | 14.20 | 1.12 | 0.59 | 16.42 | | 0.51 | 2.22 |
| 548 | 685583.37 | 601539.44 | BRK | 15.12 | 15.18 | 1.13 | 0.81 | 20.20 | | 0.48 | 5.02 |
| 549 | 685595.8952 | 601578.0005 | BRK | 14.21 | 14.27 | 1.19 | | 18.24 | | 0.50 | 3.96 |
| 550 | 685562.63 | 601543.70 | BRK | 17.48 | 17.45 | 1.17 | 0.49 | 20.14 | | 0.54 | 2.69 |
| 551 | 685559.4866 | 601547.9749 | BRK | 13.94 | 14.02 | 1.16 | | 20.17 | | 0.59 | 6.15 |
| 552 | 685555.5634 | 601552.5373 | BRK | 13.93 | 13.97 | 1.17 | | 20.10 | | 0.47 | 6.13 |
| 553 | 685552.5036 | 601556.6952 | BRK | 17.37 | 17.31 | 1.21 | | 20.17 | | 0.56 | 2.86 |
| 554 | 685602.63 | 601551.44 | BRK | 17.71 | 17.63 | 1.26 | 0.49 | 20.17 | | 0.52 | 2.54 |
| 555 | 685524.8988 | 601529.9774 | BRK | 13.12 | 13.20 | 1.18 | | 20.09 | | 0.55 | 6.89 |
| 556 | 685521.8453 | 601534.1334 | BRK | 16.56 | 16.41 | 1.25 | | 20.11 | | 0.58 | 3.70 |
| 557 | 685518.43 | 601506.14 | BRK | 15.53 | 15.44 | 1.25 | 0.47 | 20.01 | | 0.53 | 4.57 |
| 558 | 685516.84 | 601455.37 | BNDY | 13.73 | 13.68 | 1.13 | 0.56 | 18.14 | | 0.45 | 4.47 |
| 559 | 685566.10 | 601602.95 | BRK | 17.39 | 17.30 | 1.29 | 0.63 | 20.11 | | 0.89 | 2.81 |
| 560 | 685557.11 | 601621.51 | BRK | 16.15 | 16.11 | 1.29 | 0.53 | 19.95 | | 0.50 | 3.83 |
| 561 | 685572.96 | 601633.24 | BNDY | 9.96 | 10.05 | 1.17 | 0.46 | 13.83 | | 0.57 | 3.79 |
| 562 | 685589.38 | 601610.88 | BNDY | 10.19 | 10.10 | 1.25 | 0.48 | 13.66 | | 0.54 | 3.56 |
| 563 | 685606.3327 | 601587.7847 | BNDY | 9.93 | 10.03 | 1.06 | | 13.51 | | 0.55 | 3.48 |
| 564 | 685633.80 | 601550.37 | BNDY | 9.78 | 9.77 | 1.23 | 0.48 | 13.00 | | 0.75 | 3.23 |
| 565 | 685622.62 | 601565.61 | BNDY | 9.96 | 10.03 | 1.14 | 0.48 | 13.19 | | 0.56 | 3.16 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 566 | 685614.41 | 601530.85 | BNDY | 15.70 | 15.79 | 1.01 | 0.58 | 17.88 | | 0.50 | 2.09 |
| 567 | 685591.47 | 601507.77 | BNDY | 15.02 | 15.06 | 1.08 | 0.54 | 17.21 | | 0.53 | 2.15 |
| 568 | 685577.88 | 601494.10 | BNDY | 14.55 | 14.65 | 1.13 | 0.45 | 16.73 | | 0.50 | 2.09 |
| 569 | 685488.0585 | 601495.4211 | BNDY | 14.30 | 14.31 | 1.09 | | 18.26 | | 0.52 | 3.95 |
| 570 | 685501.08 | 601477.69 | BNDY | 14.94 | 14.96 | 1.05 | 0.55 | 18.25 | | 0.51 | 3.29 |
| 571 | 685474.3133 | 601513.2966 | BNDY | 13.64 | 13.58 | 1.31 | | 18.30 | | 0.52 | 4.71 |
| 572 | 685459.92 | 601533.74 | BNDY | 12.84 | 12.83 | 1.08 | 0.65 | 18.25 | | 0.64 | 5.42 |
| 573 | 685442.87 | 601556.12 | BNDY | 12.43 | 12.43 | 1.11 | 0.87 | 18.08 | | 0.53 | 5.66 |
| 574 | 685428.08 | 601576.27 | BNDY | 12.19 | 12.21 | 1.06 | 0.59 | 17.34 | | 0.65 | 5.14 |
| 575 | 685413.27 | 601596.44 | BNDY | 11.95 | 12.02 | 1.10 | 0.53 | 17.08 | | 0.57 | 5.06 |
| 576 | 685398.47 | 601616.59 | BNDY | 11.42 | 11.44 | 1.17 | 0.55 | 17.02 | | 0.55 | 5.58 |
| 577 | 685383.68 | 601636.74 | BNDY | 11.34 | 11.31 | 1.18 | 0.59 | 16.96 | | 0.64 | 5.65 |
| 578 | 685368.88 | 601656.89 | BNDY | 11.27 | 11.24 | 1.18 | 0.58 | 15.82 | | 0.53 | 4.58 |
| 579 | 685558.28 | 601653.23 | BNDY | 9.90 | 9.93 | 1.22 | 0.51 | 13.58 | | 0.54 | 3.65 |
| 581 | 685543.38 | 601673.52 | BNDY | 9.88 | 9.87 | 1.24 | 0.48 | 13.37 | | 0.49 | 3.50 |
| 582 | 685528.60 | 601693.65 | BNDY | 9.84 | 9.81 | 1.10 | 0.61 | 13.23 | | 0.50 | 3.41 |
| 583 | 685469.10 | 601609.94 | BRK | 15.99 | 15.91 | 1.21 | 0.66 | 18.82 | | 0.57 | 2.91 |
| 584 | 685468.06 | 601601.70 | BRK | 14.55 | 14.56 | 1.21 | 0.80 | 18.89 | | 0.60 | 4.33 |
| 585 | 685534.63 | 601655.70 | BRK | 15.46 | 15.38 | 1.32 | 0.46 | 19.31 | | 0.51 | 3.93 |
| 586 | 685515.15 | 601685.29 | BRK | 14.82 | 14.60 | 1.37 | 0.56 | 18.44 | | 0.55 | 3.84 |
| 587 | 685503.84 | 601702.15 | BRK | 14.49 | 14.45 | 1.13 | 0.62 | 17.92 | | 0.47 | 3.48 |
| 588 | 685484.63 | 601722.61 | BRK | 15.55 | 15.47 | 1.25 | 0.54 | 17.98 | | 0.53 | 2.52 |
| 589 | 685482.47 | 601731.53 | BRK | 11.10 | 11.14 | 1.21 | 0.78 | 17.58 | | 0.57 | 6.44 |
| 590 | 685467.89 | 601733.01 | BRK | 13.13 | 13.22 | 1.16 | 0.84 | 17.99 | | 0.51 | 4.77 |
| 591 | 685467.14 | 601729.90 | BRK | 15.25 | 15.18 | 1.19 | 0.63 | 18.01 | | 0.48 | 2.83 |
| 592 | 685465.84 | 601749.83 | BRK | 15.15 | 15.09 | 1.19 | 0.58 | 17.93 | | 1.01 | 2.84 |
| 593 | 685444.26 | 601779.76 | BRK | 13.57 | 13.66 | 1.14 | 0.78 | 17.81 | | 0.59 | 4.15 |
| 594 | 685429.29 | 601800.21 | BRK | 15.09 | 15.00 | 1.31 | 0.49 | 17.52 | | 0.66 | 2.53 |
| 595 | 685453.48 | 601767.05 | BRK | 15.07 | 14.98 | 1.26 | 0.56 | 17.98 | | 0.57 | 3.00 |
| 596 | 685514.37 | 601713.04 | BNDY | 9.77 | 9.72 | 1.19 | 0.52 | 12.96 | | 0.54 | 3.25 |
| 597 | 685499.50 | 601733.28 | BNDY | 9.70 | 9.78 | 1.22 | 0.52 | 12.69 | | 0.52 | 2.91 |
| 598 | 685485.10 | 601752.90 | BNDY | 9.64 | 9.66 | 1.33 | 0.50 | 12.54 | | 0.54 | 2.89 |
| 599 | 685469.40 | 601774.28 | BNDY | 9.60 | 9.70 | 1.11 | 0.45 | 12.32 | | 0.67 | 2.62 |
| 600 | 685454.74 | 601794.25 | BNDY | 9.64 | 9.70 | 1.20 | 0.60 | 12.05 | | 0.55 | 2.35 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 601 | 685439.85 | 601814.53 | BNDY | 9.68 | 9.64 | 1.28 | 0.42 | 12.00 | | 0.58 | 2.36 |
| 602 | 685425.01 | 601834.73 | BNDY | 9.73 | 9.66 | 1.29 | 0.40 | 11.86 | | 0.52 | 2.20 |
| 603 | 685418.25 | 601641.07 | BRK | 13.45 | 13.41 | 1.26 | 0.62 | 18.04 | | 0.60 | 4.63 |
| 604 | 685415.60 | 601650.93 | BRK | 15.85 | 15.62 | 1.37 | 0.55 | 18.05 | | 0.51 | 2.43 |
| 605 | 685417.81 | 601680.87 | BRK | 15.90 | 15.77 | 1.24 | 0.56 | 18.14 | | 0.57 | 2.37 |
| 606 | 685421.62 | 601680.64 | BRK | 13.35 | 13.42 | 1.20 | 0.79 | 18.06 | | 0.57 | 4.64 |
| 607 | 685417.84 | 601705.42 | BRK | 16.07 | 15.91 | 1.40 | 0.48 | 18.33 | | 0.54 | 2.42 |
| 608 | 685421.83 | 601705.56 | BRK | 13.40 | 13.43 | 1.20 | 0.80 | 18.14 | | 0.51 | 4.71 |
| 609 | 685420.68 | 601733.21 | BRK | 13.46 | 13.54 | 1.08 | 0.86 | 18.20 | | 0.59 | 4.66 |
| 610 | 685416.60 | 601732.96 | BRK | 16.18 | 16.19 | 1.13 | 0.55 | 18.33 | | 0.45 | 2.14 |
| 611 | 685420.69 | 601759.40 | BRK | 13.52 | 13.60 | 1.13 | 0.70 | 18.20 | | 0.56 | 4.60 |
| 612 | 685417.42 | 601761.34 | BRK | 16.06 | 16.08 | 1.13 | 0.57 | 18.32 | | 0.54 | 2.24 |
| 613 | 685367.91 | 601704.46 | BRK | 13.34 | 13.35 | 1.18 | 0.73 | 18.01 | | 0.54 | 4.66 |
| 614 | 685370.79 | 601706.98 | BRK | 15.89 | 15.67 | 1.46 | 0.48 | 18.25 | | 0.64 | 2.58 |
| 615 | 685343.44 | 601731.17 | BRK | 13.71 | 13.67 | 1.28 | 0.58 | 18.23 | | 0.52 | 4.55 |
| 616 | 685345.91 | 601734.17 | BRK | 16.30 | 16.33 | 1.07 | 0.50 | 18.48 | | 0.57 | 2.15 |
| 617 | 685303.14 | 601806.86 | BRK | 18.27 | 18.27 | 1.14 | 0.47 | 20.42 | | 0.55 | 2.15 |
| 618 | 685298.7657 | 601809.6667 | BRK | 15.77 | 15.84 | 1.26 | | 20.32 | | 0.63 | 4.48 |
| 619 | 685294.5364 | 601809.7779 | BRK | 15.35 | 15.41 | 1.17 | | 20.16 | | 0.57 | 4.75 |
| 620 | 685288.9198 | 601805.6788 | BRK | 10.72 | 10.67 | 1.28 | | 19.94 | | 0.56 | 9.26 |
| 621 | 685298.8544 | 601821.3782 | BRK | 15.76 | 15.72 | 1.27 | | 20.29 | | 0.57 | 4.57 |
| 622 | 685295.9426 | 601825.3091 | BRK | 12.49 | 12.56 | 1.16 | | 20.29 | | 0.51 | 7.72 |
| 623 | 685294.6542 | 601831.8216 | BRK | 12.53 | 12.55 | 1.14 | | 20.38 | | 0.51 | 7.83 |
| 624 | 685291.7461 | 601835.7476 | BRK | 15.79 | 15.46 | 1.52 | | 20.41 | | 0.54 | 4.95 |
| 625 | 685324.5764 | 601840.1333 | BRK | 15.86 | 15.66 | 1.46 | | 20.55 | | 0.51 | 4.89 |
| 626 | 685321.5217 | 601844.257 | BRK | 12.44 | 12.40 | 1.25 | | 20.60 | | 0.54 | 8.19 |
| 627 | 685322.6741 | 601852.5775 | BRK | 12.42 | 12.40 | 1.28 | | 20.57 | | 0.62 | 8.16 |
| 628 | 685319.6365 | 601856.6782 | BRK | 15.82 | 15.69 | 1.32 | | 20.47 | | 0.51 | 4.78 |
| 629 | 685341.3972 | 601852.7202 | BRK | 15.72 | 15.42 | 1.39 | | 20.31 | | 0.53 | 4.89 |
| 630 | 685338.4032 | 601856.762 | BRK | 12.37 | 12.42 | 1.17 | | 20.32 | | 0.53 | 7.90 |
| 631 | 685345.647 | 601844.394 | BRK | 15.88 | 15.94 | 1.28 | | 20.33 | | 0.54 | 4.39 |
| 632 | 685347.89 | 601841.36 | BRK | 18.39 | 18.30 | 1.25 | 0.49 | 20.52 | | 0.47 | 2.22 |
| 633 | 685372.8508 | 601864.5453 | BRK | 15.31 | 15.40 | 1.18 | | 19.83 | | 0.57 | 4.43 |
| 634 | 685364.474 | 601869.9863 | BRK | 15.23 | 15.14 | 1.17 | | 20.03 | | 0.59 | 4.88 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 635 | 685361.5623 | 601873.917 | BRK | 11.96 | 12.06 | 1.26 | | 20.08 | | 0.62 | 8.03 |
| 636 | 685354.9207 | 601876.4641 | BRK | 12.04 | 12.13 | 1.10 | | 20.05 | | 0.52 | 7.92 |
| 637 | 685350.4407 | 601879.237 | BRK | 15.34 | 15.19 | 1.38 | | 20.08 | | 0.55 | 4.89 |
| 638 | 685354.08 | 601677.04 | BNDY | 11.30 | 11.10 | 1.30 | 0.63 | 17.09 | | 0.64 | 5.99 |
| 639 | 685353.62 | 601747.98 | BRK | 16.38 | 16.33 | 1.30 | 0.50 | 18.71 | | 0.57 | 2.38 |
| 640 | 685357.16 | 601746.52 | BRK | 13.83 | 13.77 | 1.31 | 0.74 | 18.66 | | 0.70 | 4.90 |
| 641 | 685361.58 | 601753.32 | BRK | 13.86 | 13.90 | 1.17 | 0.89 | 18.69 | | 0.76 | 4.79 |
| 642 | 685364.98 | 601751.93 | BRK | 16.31 | 16.20 | 1.29 | 0.53 | 18.71 | | 0.69 | 2.51 |
| 643 | 685324.49 | 601717.35 | BNDY | 11.30 | 10.63 | 1.80 | 0.47 | 17.27 | | 0.60 | 6.64 |
| 644 | 685339.29 | 601697.19 | BNDY | 11.30 | 10.61 | 1.91 | 0.46 | 17.08 | | 0.61 | 6.47 |
| 645 | 685381.55 | 601830.67 | BRK | 17.46 | 17.42 | 1.20 | 0.47 | 19.67 | | 0.58 | 2.25 |
| 646 | 685385.39 | 601829.73 | BRK | 14.82 | 14.77 | 1.30 | 0.68 | 19.40 | | 0.76 | 4.64 |
| 647 | 685383.26 | 601850.36 | BRK | 17.59 | 17.51 | 1.20 | 0.49 | 19.67 | | 0.48 | 2.16 |
| 648 | 685408.65 | 601820.74 | BRK | 16.62 | 16.54 | 1.18 | 0.62 | 18.93 | | 0.59 | 2.39 |
| 649 | 685309.86 | 601737.62 | BNDY | 10.63 | 10.59 | 1.22 | 0.52 | 18.08 | | 0.60 | 7.49 |
| 650 | 685295.20 | 601757.86 | BNDY | 10.54 | 10.64 | 1.05 | 0.48 | 18.48 | | 0.61 | 7.85 |
| 651 | 685280.5071 | 601778.0937 | BNDY | 10.44 | 10.29 | 1.31 | | 18.88 | | 0.59 | 8.59 |
| 652 | 685265.6993 | 601798.2407 | BNDY | 10.74 | 10.78 | 1.29 | | 19.03 | | 0.55 | 8.25 |
| 653 | 685250.8952 | 601818.3828 | BNDY | 11.94 | 11.95 | 1.30 | | 19.05 | | 0.51 | 7.11 |
| 654 | 685236.0879 | 601838.5324 | BNDY | 15.09 | 15.11 | 1.09 | | 19.55 | | 0.76 | 4.45 |
| 655 | 685221.28 | 601858.68 | BNDY | 15.58 | 15.61 | 1.12 | 0.49 | 20.00 | | 0.62 | 4.39 |
| 656 | 685206.48 | 601878.81 | BNDY | 15.50 | 15.41 | 1.22 | 0.50 | 19.99 | | 0.57 | 4.59 |
| 657 | 685191.67 | 601898.96 | BNDY | 15.50 | 15.46 | 1.13 | 0.54 | 20.04 | | 0.65 | 4.58 |
| 658 | 685176.87 | 601919.10 | BNDY | 15.42 | 15.45 | 1.18 | 0.47 | 19.84 | | 0.46 | 4.39 |
| 659 | 685410.29 | 601854.79 | BNDY | 9.65 | 9.55 | 1.35 | 0.42 | 11.85 | | 0.53 | 2.30 |
| 660 | 685395.44 | 601875.02 | BNDY | 9.64 | 9.58 | 1.12 | 0.55 | 11.73 | | 0.48 | 2.16 |
| 661 | 685380.6628 | 601895.1371 | BNDY | 9.65 | 9.67 | 1.10 | | 11.74 | | 0.52 | 2.07 |
| 662 | 685365.9126 | 601915.2263 | BNDY | 9.73 | 9.69 | 1.12 | | 11.83 | | 0.68 | 2.14 |
| 663 | 685351.03 | 601935.49 | BNDY | 9.87 | 9.86 | 1.26 | 0.47 | 12.08 | | 0.49 | 2.22 |
| 664 | 685336.28 | 601955.58 | BNDY | 9.93 | 9.88 | 1.29 | 0.47 | 12.19 | | 0.54 | 2.30 |
| 665 | 685321.52 | 601975.69 | BNDY | 9.98 | 9.91 | 1.26 | 0.46 | 12.26 | | 0.63 | 2.35 |
| 666 | 685306.70 | 601995.87 | BNDY | 9.98 | 9.92 | 1.28 | 0.47 | 12.31 | | 0.65 | 2.40 |
| 667 | 685292.04 | 602015.84 | BNDY | 9.96 | 9.96 | 1.22 | 0.49 | 12.21 | | 0.54 | 2.25 |
| 668 | 685277.22 | 602036.03 | BNDY | 9.95 | 10.01 | 1.08 | 0.57 | 12.29 | | 0.63 | 2.28 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 669 | 685262.73 | 602055.75 | BNDY | 9.91 | 9.95 | 1.17 | 0.48 | 12.51 | | 0.55 | 2.56 |
| 670 | 685247.66 | 602076.28 | BNDY | 10.02 | 10.09 | 1.19 | 0.47 | 12.62 | | 0.63 | 2.53 |
| 671 | 685232.64 | 602096.74 | BNDY | 10.21 | 10.12 | 1.33 | 0.51 | 12.86 | | 0.58 | 2.74 |
| 672 | 685359.0086 | 601899.4038 | BRK | 14.46 | 14.43 | 1.20 | | 16.65 | | 0.51 | 2.22 |
| 673 | 685328.78 | 601922.42 | BRK | 18.12 | 18.18 | 1.07 | 0.53 | 20.32 | | 0.54 | 2.14 |
| 674 | 685299.89 | 601934.58 | BRK | 18.32 | 18.37 | 1.12 | 0.50 | 20.55 | | 0.56 | 2.18 |
| 675 | 685300.62 | 601938.23 | BRK | 15.84 | 15.80 | 1.23 | 0.91 | 20.55 | | 0.79 | 4.75 |
| 676 | 685305.79 | 601944.00 | BRK | 15.75 | 15.75 | 1.22 | 0.90 | 20.52 | | 0.79 | 4.77 |
| 677 | 685308.02 | 601946.97 | BRK | 18.23 | 18.08 | 1.25 | 0.63 | 20.49 | | 0.52 | 2.40 |
| 678 | 685292.65 | 601972.35 | BRK | 18.06 | 18.06 | 1.10 | 0.58 | 20.23 | | 0.49 | 2.17 |
| 679 | 685305.3308 | 601869.9088 | BRK | 15.99 | 16.07 | 1.18 | | 20.59 | | 0.51 | 4.52 |
| 680 | 685303.05 | 601872.98 | BRK | 18.54 | 18.11 | 1.67 | 0.46 | 20.73 | | 0.49 | 2.62 |
| 681 | 685268.9883 | 601832.9886 | BRK | 12.10 | 12.16 | 1.10 | | 20.11 | | 0.49 | 7.95 |
| 682 | 685272.6449 | 601835.6573 | BRK | 15.11 | 14.74 | 1.54 | | 20.26 | | 0.53 | 5.52 |
| 683 | 685218.81 | 601931.92 | BRK | 18.60 | 18.17 | 1.55 | 0.48 | 20.90 | | 0.70 | 2.73 |
| 684 | 685217.81 | 601935.62 | BRK | 16.04 | 16.10 | 1.19 | 0.98 | 20.79 | | 0.71 | 4.69 |
| 685 | 685217.77 | 601956.54 | BRK | 18.21 | 18.12 | 1.16 | 0.63 | 20.43 | | 0.53 | 2.31 |
| 686 | 685214.25 | 601958.05 | BRK | 15.65 | 15.75 | 1.15 | 0.95 | 20.47 | | 0.82 | 4.73 |
| 687 | 685162.06 | 601939.25 | BNDY | 14.94 | 14.89 | 1.18 | 0.63 | 19.38 | | 0.54 | 4.48 |
| 688 | 685246.08 | 602006.05 | BRK | 17.34 | 17.40 | 1.13 | 0.51 | 19.62 | | 0.57 | 2.21 |
| 689 | 685249.42 | 602007.82 | BRK | 14.83 | 14.91 | 1.18 | 0.87 | 19.55 | | 0.79 | 4.64 |
| 690 | 685250.13 | 602009.68 | BRK | 14.79 | 14.82 | 1.19 | 0.93 | 19.48 | | 0.74 | 4.66 |
| 691 | 685253.44 | 602011.40 | BRK | 17.28 | 17.25 | 1.18 | 0.51 | 19.51 | | 0.56 | 2.25 |
| 692 | 685256.80 | 602026.88 | BRK | 16.95 | 17.03 | 1.07 | 0.54 | 19.19 | | 0.55 | 2.16 |
| 693 | 685147.26 | 601959.39 | BNDY | 14.32 | 14.41 | 1.03 | 0.54 | 18.38 | | 0.66 | 3.97 |
| 694 | 685132.45 | 601979.53 | BNDY | 13.68 | 13.77 | 1.02 | 0.59 | 18.27 | | 0.81 | 4.50 |
| 695 | 685117.65 | 601999.68 | BNDY | 13.18 | 13.25 | 1.05 | 0.59 | 17.65 | | 0.56 | 4.40 |
| 696 | 685102.93 | 602019.90 | BNDY | 10.35 | 10.37 | 1.24 | 0.77 | 17.17 | | 0.64 | 6.79 |
| 697 | 685088.04 | 602039.97 | BNDY | 6.10 | 6.14 | 1.10 | 0.90 | 17.13 | | 0.61 | 10.99 |
| 698 | 685073.2297 | 602060.1093 | BNDY | 4.74 | 4.79 | 1.16 | | 17.18 | | 0.67 | 12.39 |
| 699 | 685058.4247 | 602080.2525 | BNDY | 4.27 | 4.36 | 1.16 | | 17.74 | 1.10 | | 13.38 |
| 700 | 685043.6189 | 602100.3969 | BNDY | 4.49 | 4.45 | 1.17 | | 18.06 | | 0.53 | 13.61 |
| 701 | 685028.81 | 602120.54 | BNDY | 4.79 | 4.88 | 1.12 | 0.72 | 18.10 | | 0.55 | 13.22 |
| 702 | 685014.01 | 602140.69 | BNDY | 5.10 | 5.19 | 1.06 | 0.60 | 19.00 | | 0.56 | 13.80 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 703 | 684999.20 | 602160.83 | BNDY | 5.40 | 5.38 | 1.11 | 0.66 | 19.06 | | 0.51 | 13.68 |
| 704 | 684984.40 | 602180.97 | BNDY | 5.71 | 5.66 | 1.13 | 0.65 | 19.13 | | 0.52 | 13.47 |
| 705 | 685217.90 | 602116.82 | BNDY | 10.37 | 10.28 | 1.24 | 0.54 | 13.02 | | 0.58 | 2.74 |
| 706 | 685203.10 | 602136.97 | BNDY | 10.48 | 10.57 | 1.15 | 0.59 | 13.16 | | 0.60 | 2.60 |
| 707 | 685188.3051 | 602157.12 | BNDY | 6.02 | 6.10 | 2.95 | | 15.50 | 2.87 | | 9.40 |
| 708 | 685173.5091 | 602177.2715 | BNDY | 6.02 | 5.97 | 3.02 | | 15.58 | 2.86 | | 9.61 |
| 709 | 685143.92 | 602217.57 | BNDY | 11.24 | 11.16 | 1.16 | 0.57 | 13.60 | | 0.53 | 2.44 |
| 710 | 685158.71 | 602197.42 | BNDY | 11.06 | 11.02 | 1.19 | 0.55 | 13.49 | | 0.69 | 2.47 |
| 711 | 685129.12 | 602237.73 | BNDY | 11.43 | 11.43 | 1.13 | 0.55 | 13.87 | | 0.49 | 2.44 |
| 712 | 685114.32 | 602257.88 | BNDY | 11.62 | 11.62 | 1.08 | 0.65 | 14.13 | | 0.69 | 2.51 |
| 713 | 685099.53 | 602278.03 | BNDY | 11.79 | 11.71 | 1.25 | 0.53 | 14.35 | | 0.61 | 2.64 |
| 714 | 685084.73 | 602298.18 | BNDY | 11.98 | 11.98 | 1.15 | 0.48 | 14.60 | | 0.52 | 2.62 |
| 715 | 685069.94 | 602318.33 | BNDY | 11.95 | 11.96 | 1.18 | 0.46 | 14.94 | | 0.51 | 2.98 |
| 716 | 685055.15 | 602338.47 | BNDY | 11.91 | 11.90 | 1.12 | 0.56 | 15.16 | | 0.55 | 3.26 |
| 717 | 685040.35 | 602358.63 | BNDY | 11.85 | 11.88 | 1.11 | 0.56 | 15.42 | | 0.52 | 3.54 |
| 718 | 685025.55 | 602378.78 | BNDY | 11.82 | 11.88 | 1.05 | 0.59 | 15.64 | | 0.54 | 3.76 |
| 719 | 685010.76 | 602398.93 | BNDY | 11.80 | 11.88 | 1.07 | 0.52 | 15.58 | | 0.52 | 3.71 |
| 720 | 684995.96 | 602419.08 | BNDY | 11.79 | 11.72 | 1.23 | 0.53 | 15.49 | | 0.51 | 3.77 |
| 721 | 684981.17 | 602439.24 | BNDY | 11.72 | 11.71 | 1.13 | 0.53 | 15.47 | | 0.53 | 3.76 |
| 722 | 684966.37 | 602459.39 | BNDY | 11.57 | 11.61 | 1.15 | 0.50 | 15.40 | | 0.51 | 3.80 |
| 723 | 684951.57 | 602479.54 | BNDY | 11.50 | 11.53 | 1.06 | 0.56 | 15.22 | | 0.47 | 3.70 |
| 724 | 684936.78 | 602499.69 | BNDY | 11.52 | 11.60 | 1.01 | 0.59 | 14.95 | | 0.50 | 3.35 |
| 725 | 684921.98 | 602519.84 | BNDY | 11.56 | 11.53 | 1.14 | 0.56 | 14.69 | | 0.53 | 3.16 |
| 726 | 684907.19 | 602539.99 | BNDY | 11.59 | 11.57 | 1.27 | 0.54 | 14.43 | | 0.49 | 2.86 |
| 727 | 684892.39 | 602560.14 | BNDY | 11.60 | 11.67 | 1.08 | 0.54 | 14.18 | | 0.47 | 2.51 |
| 728 | 684877.59 | 602580.30 | BNDY | 11.56 | 11.60 | 1.17 | 0.48 | 14.20 | | 0.53 | 2.60 |
| 729 | 684862.80 | 602600.45 | BNDY | 11.68 | 11.71 | 1.23 | 0.51 | 14.36 | | 0.49 | 2.65 |
| 730 | 684848.00 | 602620.60 | BNDY | 11.71 | 11.79 | 1.16 | 0.45 | 14.81 | | 0.52 | 3.02 |
| 731 | 684969.59 | 602201.11 | BNDY | 6.02 | 6.01 | 1.11 | 0.55 | 20.03 | | 0.57 | 14.03 |
| 732 | 684954.79 | 602221.26 | BNDY | 6.32 | 6.37 | 1.09 | 0.59 | 20.16 | | 0.51 | 13.79 |
| 733 | 684939.98 | 602241.40 | BNDY | 6.63 | 6.62 | 1.11 | 0.92 | 20.27 | | 0.52 | 13.66 |
| 734 | 684925.18 | 602261.55 | BNDY | 6.93 | 6.84 | 1.29 | 0.86 | 20.94 | | 0.47 | 14.09 |
| 735 | 684910.37 | 602281.69 | BNDY | 7.13 | 7.19 | 1.13 | 0.84 | 20.92 | | 0.46 | 13.73 |
| 736 | 684895.57 | 602301.83 | BNDY | 7.40 | 7.44 | 1.20 | 0.82 | 20.94 | | 0.56 | 13.50 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 737 | 684880.76 | 602321.98 | BNDY | 7.76 | 7.85 | 1.08 | 0.89 | 20.93 | | 0.51 | 13.09 |
| 738 | 684865.95 | 602342.12 | BNDY | 8.16 | 8.16 | 1.16 | 0.55 | 20.95 | | 0.55 | 12.79 |
| 739 | 684851.15 | 602362.27 | BNDY | 8.46 | 8.54 | 1.05 | 0.62 | 20.93 | | 0.54 | 12.39 |
| 740 | 684827.24 | 602394.80 | BNDY | 8.95 | 8.94 | 1.26 | 0.82 | 20.67 | | 0.55 | 11.73 |
| 741 | 684821.28 | 602402.91 | BNDY | 15.66 | 15.65 | 1.13 | 0.58 | 20.43 | | 0.55 | 4.78 |
| 742 | 684806.74 | 602422.70 | BNDY | 15.05 | 15.04 | 1.14 | 0.53 | 19.80 | | 0.54 | 4.76 |
| 743 | 684792.02 | 602442.92 | BNDY | 14.42 | 14.43 | 1.17 | 0.55 | 19.16 | | 0.55 | 4.74 |
| 744 | 684833.20 | 602640.76 | BNDY | 11.75 | 11.84 | 1.18 | 0.50 | 14.82 | | 0.50 | 2.98 |
| 745 | 684818.41 | 602660.91 | BNDY | 11.73 | 11.80 | 1.18 | 0.52 | 14.89 | | 0.52 | 3.09 |
| 746 | 684803.6081 | 602681.0604 | BNDY | 9.08 | 9.10 | 1.17 | | 15.19 | | 0.61 | 6.09 |
| 747 | 684790.6 | 602698.7769 | BNDY | 7.50 | 7.59 | 0.99 | | 14.25 | | 0.54 | 6.66 |
| 761 | 684777.12 | 602462.99 | BNDY | 13.79 | 13.79 | 1.14 | 0.55 | 18.36 | | 0.58 | 4.58 |
| 762 | 684762.31 | 602483.14 | BNDY | 13.20 | 13.12 | 1.16 | 0.56 | 17.73 | | 0.51 | 4.61 |
| 763 | 684747.51 | 602503.28 | BNDY | 12.75 | 12.70 | 1.20 | 0.52 | 17.42 | | 0.52 | 4.72 |
| 764 | 684732.70 | 602523.42 | BNDY | 12.49 | 12.41 | 1.28 | 0.67 | 17.11 | | 0.53 | 4.70 |
| 765 | 684717.90 | 602543.56 | BNDY | 7.90 | 7.91 | 1.20 | 0.82 | 16.49 | | 0.53 | 8.58 |
| 766 | 684703.09 | 602563.72 | BNDY | 6.74 | 6.81 | 1.10 | 0.78 | 17.01 | | 0.53 | 10.20 |
| 767 | 684687.1063 | 602585.4579 | BNDY | 5.47 | 5.54 | 1.11 | | 17.10 | | 0.54 | 11.56 |
| 768 | 684672.8746 | 602604.8211 | BNDY | 4.91 | 4.96 | 1.19 | | 17.31 | | 0.65 | 12.35 |
| 769 | 684656.5065 | 602623.7179 | BNDY | 4.99 | 5.01 | 1.17 | | 18.32 | | 0.68 | 13.31 |
| 822 | 685209.17 | 602098.14 | BRK | 16.12 | 16.21 | 1.02 | 0.54 | 18.37 | | 0.60 | 2.16 |
| 823 | 685187.68 | 602127.24 | BRK | 16.40 | 16.47 | 1.16 | 0.47 | 19.02 | | 0.73 | 2.55 |
| 824 | 685169.69 | 602121.14 | BRK | 16.91 | 16.98 | 1.08 | 0.50 | 19.19 | | 0.63 | 2.21 |
| 825 | 685159.5985 | 602134.7709 | BRK | 5.60 | 5.69 | 1.05 | | 19.16 | | 0.59 | 13.47 |
| 826 | 685142.99 | 602100.91 | BRK | 16.77 | 16.71 | 1.18 | 0.56 | 19.07 | | 0.56 | 2.36 |
| 827 | 685132.6767 | 602114.8475 | BRK | 5.21 | 5.29 | 1.19 | | 19.05 | | 0.53 | 13.77 |
| 828 | 685117.94 | 602082.20 | BRK | 16.50 | 16.46 | 1.14 | 0.56 | 19.07 | | 0.59 | 2.61 |
| 829 | 685108.0441 | 602096.6184 | BRK | 4.85 | 4.94 | 1.06 | | 19.03 | | 0.51 | 14.09 |
| 830 | 685097.56 | 602070.88 | BRK | 13.71 | 13.78 | 1.03 | 0.69 | 18.44 | | 0.66 | 4.66 |
| 831 | 685091.6225 | 602084.4656 | BRK | 4.62 | 4.71 | 1.06 | | 18.83 | | 0.55 | 14.12 |
| 832 | 685079.0777 | 602074.2284 | BRK | 4.44 | 4.53 | 1.06 | | 18.20 | | 0.69 | 13.67 |
| 833 | 685087.2307 | 602063.2368 | BRK | 5.15 | 5.21 | 1.14 | | 17.68 | | 0.59 | 12.47 |
| 834 | 685228.90 | 602033.89 | BRK | 16.52 | 16.51 | 1.25 | 0.48 | 18.98 | | 0.74 | 2.47 |
| 835 | 685232.50 | 602033.47 | BRK | 14.10 | 14.17 | 1.18 | 1.01 | 18.97 | | 0.70 | 4.80 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 836 | 685239.46 | 602034.31 | BRK | 14.12 | 14.21 | 1.16 | 1.14 | 18.93 | | 0.77 | 4.72 |
| 837 | 685243.00 | 602035.55 | BRK | 16.62 | 16.54 | 1.16 | 0.59 | 18.94 | | 0.65 | 2.40 |
| 838 | 685241.70 | 602050.98 | BRK | 16.30 | 16.34 | 1.19 | 0.49 | 18.61 | | 0.59 | 2.26 |
| 839 | 685057.3284 | 602100.4637 | BRK | 4.41 | 4.45 | 1.21 | | 18.40 | | 0.46 | 13.95 |
| 840 | 685060.41 | 602121.19 | BRK | 14.47 | 14.50 | 1.20 | 0.51 | 19.02 | | 0.53 | 4.53 |
| 841 | 685068.9275 | 602108.102 | BRK | 4.57 | 4.65 | 1.09 | | 18.88 | | 0.54 | 14.23 |
| 842 | 685048.4367 | 602112.4097 | BRK | 4.57 | 4.61 | 1.19 | | 18.48 | | 0.53 | 13.88 |
| 843 | 685096.9218 | 602128.8191 | BRK | 4.97 | 5.04 | 1.16 | | 19.06 | | 0.58 | 14.03 |
| 844 | 685091.28 | 602143.63 | BRK | 15.20 | 15.25 | 1.18 | 0.50 | 19.15 | | 0.51 | 3.90 |
| 845 | 685121.5544 | 602147.0482 | BRK | 5.33 | 5.37 | 1.16 | | 19.33 | | 0.60 | 13.96 |
| 846 | 685109.62 | 602161.54 | BRK | 17.81 | 17.77 | 1.15 | 0.52 | 19.91 | | 0.46 | 2.14 |
| 847 | 685117.56 | 602193.69 | BRK | 17.43 | 17.36 | 1.17 | 0.57 | 19.64 | | 0.53 | 2.27 |
| 848 | 685118.92 | 602197.25 | BRK | 14.89 | 14.96 | 1.09 | 1.00 | 19.53 | | 0.69 | 4.58 |
| 849 | 685119.73 | 602203.55 | BRK | 14.81 | 14.87 | 1.06 | 0.73 | 19.58 | | 0.72 | 4.71 |
| 850 | 685121.10 | 602206.98 | BRK | 17.27 | 17.30 | 1.06 | 0.63 | 19.45 | | 0.47 | 2.16 |
| 851 | 685114.98 | 602226.59 | BRK | 17.17 | 17.11 | 1.14 | 0.60 | 19.49 | | 0.64 | 2.38 |
| 852 | 685105.19 | 602198.82 | BRK | 17.35 | 17.38 | 1.08 | 0.57 | 19.73 | | 0.69 | 2.35 |
| 853 | 685103.22 | 602203.76 | BRK | 14.79 | 14.84 | 1.21 | 0.71 | 19.78 | | 0.71 | 4.94 |
| 854 | 685088.02 | 602208.76 | BRK | 17.36 | 17.29 | 1.26 | 0.52 | 19.91 | | 0.72 | 2.62 |
| 855 | 685089.52 | 602212.18 | BRK | 14.88 | 14.95 | 1.17 | 0.68 | 19.88 | | 0.68 | 4.92 |
| 856 | 685085.84 | 602227.09 | BRK | 15.07 | 15.15 | 1.09 | 0.93 | 19.98 | | 0.75 | 4.83 |
| 857 | 685083.49 | 602230.12 | BRK | 17.63 | 17.55 | 1.17 | 0.62 | 20.00 | | 0.66 | 2.45 |
| 858 | 685094.99 | 602252.22 | BRK | 17.70 | 17.67 | 1.13 | 0.59 | 19.87 | | 0.48 | 2.20 |
| 859 | 685081.79 | 602269.14 | BRK | 18.05 | 18.07 | 1.13 | 0.52 | 20.27 | | 0.56 | 2.21 |
| 860 | 685047.09 | 602237.51 | BRK | 15.69 | 15.73 | 1.22 | 0.82 | 20.41 | | 0.70 | 4.68 |
| 861 | 685043.77 | 602234.95 | BRK | 18.21 | 18.13 | 1.22 | 0.55 | 20.43 | | 0.54 | 2.30 |
| 862 | 685039.91 | 602232.72 | BRK | 15.73 | 15.69 | 1.31 | 0.80 | 20.46 | | 0.73 | 4.77 |
| 863 | 685042.37 | 602238.43 | BRK | 15.71 | 15.79 | 1.16 | 0.88 | 20.48 | | 0.66 | 4.69 |
| 864 | 685066.11 | 602161.84 | BRK | 17.75 | 17.67 | 1.18 | 0.55 | 19.94 | | 0.54 | 2.27 |
| 865 | 685062.13 | 602161.07 | BRK | 15.28 | 15.35 | 1.13 | 0.72 | 19.97 | | 0.63 | 4.62 |
| 866 | 685052.96 | 602208.15 | BRK | 17.82 | 17.75 | 1.23 | 0.56 | 20.21 | | 0.67 | 2.47 |
| 867 | 685049.31 | 602206.51 | BRK | 15.37 | 15.37 | 1.24 | 0.75 | 20.21 | | 0.73 | 4.84 |
| 868 | 685045.11 | 602202.48 | BRK | 15.62 | 15.59 | 1.28 | 0.76 | 20.22 | | 0.72 | 4.63 |
| 869 | 685042.10 | 602200.70 | BRK | 17.89 | 17.81 | 1.17 | 0.61 | 20.22 | | 0.63 | 2.40 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 870 | 685022.96 | 602172.09 | BRK | 15.38 | 15.35 | 1.17 | 0.96 | 19.96 | | 0.59 | 4.62 |
| 871 | 685044.91 | 602142.21 | BRK | 14.83 | 14.76 | 1.27 | 0.48 | 19.40 | | 0.54 | 4.63 |
| 872 | 684994.42 | 602217.26 | BRK | 18.66 | 18.67 | 1.09 | 0.58 | 20.88 | | 0.53 | 2.20 |
| 873 | 684975.68 | 602242.79 | BRK | 19.14 | 19.08 | 1.17 | 0.58 | 21.41 | | 0.59 | 2.33 |
| 874 | 685005.71 | 602243.75 | BRK | 18.78 | 18.75 | 1.14 | 0.55 | 21.02 | | 0.59 | 2.27 |
| 875 | 685009.09 | 602245.47 | BRK | 16.25 | 16.35 | 1.06 | 0.57 | 20.97 | | 0.66 | 4.63 |
| 876 | 685025.00 | 602263.80 | BRK | 16.24 | 16.33 | 1.15 | 0.55 | 20.95 | | 0.66 | 4.62 |
| 877 | 685027.83 | 602266.24 | BRK | 18.73 | 18.65 | 1.18 | 0.59 | 20.94 | | 0.52 | 2.29 |
| 878 | 685053.73 | 602299.58 | BRK | 18.74 | 18.68 | 1.16 | 0.57 | 20.90 | | 0.49 | 2.22 |
| 879 | 685053.33 | 602303.33 | BRK | 16.27 | 16.33 | 1.18 | 0.93 | 20.86 | | 0.54 | 4.52 |
| 880 | 685060.48 | 602307.84 | BRK | 16.22 | 16.14 | 1.22 | 0.53 | 19.44 | | 0.52 | 3.30 |
| 881 | 685039.62 | 602323.93 | BRK | 18.58 | 18.51 | 1.17 | 0.55 | 21.05 | | 0.51 | 2.54 |
| 882 | 685021.34 | 602349.28 | BRK | 18.40 | 18.31 | 1.20 | 0.58 | 21.16 | | 0.49 | 2.84 |
| 883 | 685006.56 | 602373.52 | BRK | 17.51 | 17.47 | 1.15 | 0.61 | 21.78 | | 0.46 | 4.31 |
| 884 | 684985.52 | 602400.52 | BRK | 17.74 | 17.67 | 1.21 | 0.53 | 22.01 | | 0.57 | 4.34 |
| 885 | 684968.75 | 602423.06 | BRK | 17.72 | 17.72 | 1.22 | 0.47 | 22.01 | | 0.53 | 4.29 |
| 886 | 684958.59 | 602266.06 | BRK | 19.57 | 19.50 | 1.20 | 0.56 | 21.80 | | 0.54 | 2.30 |
| 887 | 684944.51 | 602285.23 | BRK | 19.93 | 19.97 | 1.15 | 0.45 | 22.12 | | 0.55 | 2.15 |
| 888 | 684924.17 | 602312.77 | BRK | 20.38 | 20.34 | 1.14 | 0.58 | 22.59 | | 0.53 | 2.25 |
| 889 | 684896.37 | 602343.10 | BRK | 18.02 | 17.95 | 1.19 | 0.59 | 22.22 | | 0.51 | 4.28 |
| 890 | 684880.77 | 602362.80 | BRK | 17.79 | 17.78 | 1.22 | 0.55 | 22.11 | | 0.52 | 4.32 |
| 891 | 684869.32 | 602354.21 | BRK | 8.25 | 8.30 | 1.13 | 0.89 | 22.08 | | 0.58 | 13.78 |
| 892 | 684884.22 | 602334.10 | BRK | 7.94 | 7.99 | 1.06 | 0.98 | 22.09 | | 0.52 | 14.10 |
| 893 | 684908.58 | 602301.22 | BRK | 7.44 | 7.48 | 1.17 | 0.86 | 22.10 | | 0.58 | 14.63 |
| 894 | 684928.96 | 602273.71 | BRK | 7.02 | 6.99 | 1.14 | 0.98 | 21.67 | | 0.63 | 14.67 |
| 895 | 684943.18 | 602254.50 | BRK | 6.73 | 6.71 | 1.22 | 0.82 | 21.32 | | 0.57 | 14.60 |
| 896 | 684960.30 | 602231.40 | BRK | 6.38 | 6.42 | 1.18 | 0.57 | 20.89 | | 0.52 | 14.46 |
| 897 | 684979.15 | 602205.95 | BRK | 5.99 | 6.03 | 1.21 | 0.65 | 20.37 | | 0.55 | 14.34 |
| 898 | 685010.86 | 602163.13 | BRK | 5.34 | 5.42 | 1.14 | 0.51 | 19.49 | | 0.57 | 14.07 |
| 899 | 685032.93 | 602133.34 | BRK | 4.89 | 4.95 | 1.17 | 0.68 | 19.05 | | 0.63 | 14.11 |
| 900 | 684953.81 | 602443.85 | BRK | 17.56 | 17.51 | 1.17 | 0.55 | 21.86 | | 0.48 | 4.35 |
| 901 | 684933.84 | 602472.48 | BRK | 17.17 | 17.21 | 1.09 | 0.52 | 21.01 | | 0.50 | 3.80 |
| 902 | 684913.09 | 602504.45 | BRK | 16.54 | 16.57 | 1.17 | 0.48 | 20.21 | | 0.49 | 3.64 |
| 909 | 684858.28 | 602571.33 | BRK | 14.73 | 14.82 | 1.13 | 0.85 | 19.30 | | 0.55 | 4.48 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 910 | 684887.04 | 602531.88 | BRK | 18.22 | 18.19 | 1.14 | 0.56 | 20.48 | | 0.59 | 2.29 |
| 911 | 684720.03 | 602604.99 | BRK | 14.67 | 14.64 | 1.11 | 0.57 | 19.08 | | 0.55 | 4.44 |
| 912 | 684710.9277 | 602615.2523 | BRK | 5.53 | 5.61 | 1.16 | | 19.11 | | 0.60 | 13.50 |
| 913 | 684795.24 | 602555.71 | BRK | 13.67 | 13.76 | 1.17 | 0.70 | 18.40 | | 0.57 | 4.65 |
| 914 | 684795.33 | 602552.00 | BRK | 16.14 | 16.20 | 1.10 | 0.54 | 18.41 | | 0.46 | 2.21 |
| 915 | 684770.38 | 602552.44 | BRK | 15.78 | 15.71 | 1.25 | 0.51 | 18.02 | | 0.56 | 2.31 |
| 916 | 684771.04 | 602556.03 | BRK | 13.34 | 13.44 | 1.16 | 0.88 | 18.06 | | 0.54 | 4.62 |
| 917 | 684841.91 | 602602.61 | BRK | 16.61 | 16.54 | 1.19 | 0.55 | 19.02 | | 0.55 | 2.47 |
| 919 | 684835.00 | 602400.55 | BRK | 8.95 | 8.99 | 1.22 | 0.88 | 20.89 | | 0.55 | 11.90 |
| 920 | 684843.87 | 602407.12 | BRK | 16.31 | 16.30 | 1.27 | 0.54 | 20.99 | | 0.56 | 4.68 |
| 921 | 684754.50 | 602627.17 | BRK | 17.19 | 17.10 | 1.18 | 0.57 | 19.37 | | 0.52 | 2.27 |
| 922 | 684744.7356 | 602640.3266 | BRK | 6.26 | 6.33 | 1.19 | | 19.37 | | 0.64 | 13.04 |
| 923 | 684774.69 | 602642.80 | BRK | 17.28 | 17.19 | 1.28 | 0.49 | 19.50 | | 0.54 | 2.31 |
| 924 | 684765.2453 | 602655.538 | BRK | 6.71 | 6.79 | 1.08 | | 19.28 | | 0.64 | 12.49 |
| 925 | 684807.26 | 602664.88 | BRK | 13.82 | 13.73 | 1.17 | 0.59 | 17.20 | | 0.58 | 3.47 |
| 927 | 684774.9564 | 602705.0711 | BRK | 7.36 | 7.44 | 1.09 | | 18.03 | | 0.51 | 10.59 |
| 929 | 684725.0996 | 602668.0939 | BRK | 6.28 | 6.34 | 1.15 | | 19.63 | | 0.66 | 13.30 |
| 933 | 684699.1256 | 602648.8297 | BRK | 5.72 | 5.76 | 1.22 | | 19.31 | | 0.57 | 13.56 |
| 934 | 684677.3237 | 602632.6599 | BRK | 5.25 | 5.34 | 1.04 | | 18.86 | | 0.54 | 13.52 |
| 936 | 684665.7626 | 602624.1345 | BRK | 5.02 | 4.97 | 1.21 | | 18.48 | | 0.61 | 13.50 |
| 979 | 685388.74 | 601749.07 | BRK | 13.50 | 13.43 | 1.33 | 0.88 | 18.64 | | 0.68 | 5.21 |
| 980 | 685384.77 | 601750.03 | BRK | 16.23 | 16.26 | 1.10 | 0.62 | 18.63 | | 0.66 | 2.38 |
| 2000 | 684774.23 | 602717.67 | BNDY | 12.40 | 12.49 | 1.04 | 0.83 | 15.78 | | 0.66 | 3.29 |
| 2001 | 684757.86 | 602736.57 | BNDY | 12.87 | 12.80 | 1.20 | 0.52 | 16.10 | | 0.68 | 3.30 |
| 2002 | 684741.50 | 602755.47 | BNDY | 13.17 | 13.10 | 1.18 | 0.53 | 16.38 | | 0.62 | 3.28 |
| 2003 | 684725.13 | 602774.36 | BNDY | 13.48 | 13.39 | 1.19 | 0.53 | 16.61 | | 0.57 | 3.21 |
| 2004 | 684708.76 | 602793.26 | BNDY | 13.77 | 13.70 | 1.16 | 0.60 | 16.89 | | 0.54 | 3.19 |
| 2005 | 684692.39 | 602812.16 | BNDY | 13.98 | 13.89 | 1.30 | 0.49 | 17.19 | | 0.67 | 3.29 |
| 2006 | 684676.02 | 602831.05 | BNDY | 13.61 | 13.67 | 1.18 | 0.79 | 17.06 | | 0.49 | 3.39 |
| 2007 | 684659.66 | 602849.95 | BNDY | 13.71 | 13.73 | 1.17 | 0.61 | 17.34 | | 0.64 | 3.60 |
| 2008 | 684643.29 | 602868.85 | BNDY | 13.80 | 13.79 | 1.15 | 0.81 | 17.47 | | 0.65 | 3.67 |
| 2009 | 684626.92 | 602887.74 | BNDY | 13.90 | 13.94 | 1.08 | 0.71 | 17.56 | | 0.58 | 3.62 |
| 2010 | 684610.55 | 602906.64 | BNDY | 13.99 | 14.08 | 1.02 | 0.60 | 17.68 | | 0.55 | 3.60 |
| 2011 | 684589.1204 | 602931.3825 | BNDY | 6.65 | 6.66 | 1.24 | | 17.76 | | 0.56 | 11.10 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2012 | 684575.9627 | 602946.5728 | BNDY | 13.30 | 13.28 | 1.28 | | 17.39 | | 0.53 | 4.11 |
| 2013 | 684545.08 | 602982.23 | BNDY | 13.75 | 13.76 | 1.26 | 0.65 | 16.62 | | 0.50 | 2.86 |
| 2014 | 684561.447 | 602963.331 | BNDY | 14.75 | 14.79 | 1.14 | | 17.09 | | 0.63 | 2.31 |
| 2015 | 684528.71 | 603001.12 | BNDY | 12.84 | 12.83 | 1.19 | 0.64 | 16.17 | | 0.51 | 3.34 |
| 2016 | 684512.34 | 603020.02 | BNDY | 11.93 | 12.01 | 1.13 | 0.72 | 15.83 | | 0.54 | 3.82 |
| 2017 | 684495.97 | 603038.92 | BNDY | 11.01 | 11.06 | 1.06 | 0.77 | 15.35 | | 0.67 | 4.29 |
| 2018 | 684479.61 | 603057.81 | BNDY | 10.10 | 10.06 | 1.15 | 0.82 | 14.80 | | 0.62 | 4.74 |
| 2019 | 684463.24 | 603076.71 | BNDY | 9.19 | 9.14 | 1.31 | 0.50 | 14.33 | | 1.61 | 5.19 |
| 2020 | 684446.87 | 603095.61 | BNDY | 8.28 | 8.34 | 1.16 | 0.66 | 13.64 | | 1.10 | 5.30 |
| 2021 | 684430.50 | 603114.50 | BNDY | 7.48 | 7.52 | 1.16 | 0.84 | 12.50 | | 0.88 | 4.98 |
| 2022 | 684414.13 | 603133.40 | BNDY | 6.81 | 6.88 | 1.19 | 0.74 | 12.07 | | 0.62 | 5.20 |
| 2023 | 684397.77 | 603152.30 | BNDY | 6.28 | 6.36 | 1.16 | 0.88 | 12.13 | | 0.67 | 5.76 |
| 2024 | 684381.40 | 603171.20 | BNDY | 6.50 | 6.46 | 1.26 | 0.84 | 12.10 | | 0.96 | 5.65 |
| 2025 | 684365.0301 | 603190.0917 | BNDY | 6.55 | 6.51 | 1.27 | | 11.97 | | 0.46 | 5.46 |
| 2026 | 684348.6621 | 603208.9884 | BNDY | 6.83 | 6.80 | 1.26 | | 11.99 | | 0.61 | 5.18 |
| 2027 | 684332.29 | 603227.89 | BNDY | 6.81 | 6.78 | 1.16 | 0.68 | 11.94 | | 1.42 | 5.16 |
| 2028 | 684315.93 | 603246.78 | BNDY | 7.74 | 7.83 | 1.11 | 0.59 | 11.86 | | 1.48 | 4.04 |
| 2029 | 684299.56 | 603265.68 | BNDY | 7.92 | 7.91 | 1.17 | 0.67 | 11.63 | | 1.43 | 3.73 |
| 2030 | 684283.19 | 603284.58 | BNDY | 8.06 | 8.14 | 1.02 | 0.63 | 11.32 | | 1.30 | 3.19 |
| 2031 | 684258.4125 | 603313.1804 | BNDY | 8.20 | 8.12 | 1.24 | | 11.68 | | 1.77 | 3.56 |
| 2032 | 684238.1787 | 603303.292 | BNDY | 7.08 | 7.09 | 1.16 | | 10.44 | | 0.75 | 3.35 |
| 2033 | 684215.7175 | 603292.3151 | BNDY | 6.83 | 6.86 | 1.21 | | 10.58 | | 0.55 | 3.72 |
| 2034 | 684193.2563 | 603281.3381 | BNDY | 6.47 | 6.48 | 1.17 | | 10.48 | | 0.63 | 4.00 |
| 2035 | 684170.795 | 603270.3612 | BNDY | 6.39 | 6.38 | 1.17 | | 10.11 | | 0.59 | 3.73 |
| 2036 | 684148.3338 | 603259.3842 | BNDY | 6.33 | 6.35 | 1.08 | | 9.61 | | 0.55 | 3.26 |
| 2037 | 684124.1262 | 603238.3439 | BNDY | 6.10 | 6.16 | 1.05 | | 8.89 | | 0.48 | 2.73 |
| 2038 | 684149.11 | 603209.50 | BNDY | 6.10 | 6.14 | 1.11 | 0.70 | 9.04 | | 0.52 | 2.90 |
| 2039 | 684165.48 | 603190.60 | BNDY | 6.10 | 6.16 | 1.12 | 0.59 | 9.08 | | 0.55 | 2.92 |
| 2040 | 684182.05 | 603171.63 | BNDY | 6.11 | 6.14 | 1.12 | 0.58 | 9.08 | | 0.54 | 2.95 |
| 2041 | 684198.59 | 603153.14 | BNDY | 6.13 | 6.06 | 1.18 | 0.65 | 9.09 | | 0.52 | 3.04 |
| 2042 | 684214.58 | 603133.91 | BNDY | 6.10 | 6.15 | 1.16 | 0.57 | 9.10 | | 0.49 | 2.95 |
| 2043 | 684230.9841 | 603114.9778 | BNDY | 4.58 | 4.59 | 1.07 | | 9.74 | | 0.60 | 5.15 |
| 2044 | 684247.3179 | 603096.1207 | BNDY | 6.24 | 6.21 | 1.14 | | 9.60 | | 0.58 | 3.39 |
| 2045 | 684263.6863 | 603077.2236 | BNDY | 5.91 | 5.92 | 1.08 | | 9.72 | | 0.67 | 3.80 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2046 | 684280.05 | 603058.33 | BNDY | 4.16 | 4.18 | 1.17 | 0.61 | 9.87 | | 0.67 | 5.69 |
| 2047 | 684296.42 | 603039.43 | BNDY | 4.26 | 4.26 | 1.09 | 0.66 | 9.98 | | 0.58 | 5.73 |
| 2048 | 684312.79 | 603020.53 | BNDY | 4.62 | 4.62 | 1.19 | 0.55 | 10.27 | | 0.59 | 5.65 |
| 2049 | 684329.16 | 603001.64 | BNDY | 5.15 | 5.11 | 1.26 | 0.53 | 10.53 | | 0.62 | 5.41 |
| 2050 | 684345.53 | 602982.74 | BNDY | 5.85 | 5.82 | 1.29 | 0.45 | 10.79 | | 0.54 | 4.97 |
| 2051 | 684361.89 | 602963.84 | BNDY | 6.71 | 6.75 | 1.04 | 0.65 | 11.24 | | 0.74 | 4.49 |
| 2052 | 684378.26 | 602944.95 | BNDY | 7.74 | 7.79 | 1.21 | 0.69 | 12.20 | | 0.63 | 4.41 |
| 2053 | 684394.63 | 602926.05 | BNDY | 8.91 | 8.97 | 1.16 | 0.50 | 13.28 | | 0.56 | 4.31 |
| 2054 | 684411.00 | 602907.15 | BNDY | 10.10 | 10.02 | 1.24 | 0.53 | 14.50 | | 0.67 | 4.48 |
| 2055 | 684427.9409 | 602887.5938 | BNDY | 8.45 | 8.54 | 0.99 | | 15.56 | | 0.66 | 7.02 |
| 2056 | 684443.7347 | 602869.3601 | BNDY | 10.37 | 10.38 | 1.10 | | 16.56 | | 0.56 | 6.18 |
| 2057 | 684459.7017 | 602850.9264 | BNDY | 5.87 | 5.95 | 1.18 | | 17.65 | | 0.53 | 11.70 |
| 2058 | 684476.47 | 602831.57 | BNDY | 9.77 | 9.75 | 1.17 | 0.68 | 18.94 | | 0.51 | 9.19 |
| 2059 | 684492.84 | 602812.67 | BNDY | 9.33 | 9.41 | 1.12 | 0.52 | 20.12 | | 0.55 | 10.71 |
| 2060 | 684509.31 | 602793.66 | BNDY | 8.89 | 8.98 | 1.11 | 0.50 | 20.99 | | 0.53 | 12.00 |
| 2061 | 684525.58 | 602774.88 | BNDY | 8.46 | 8.43 | 1.27 | 0.51 | 20.87 | | 0.49 | 12.44 |
| 2062 | 684541.94 | 602755.98 | BNDY | 8.03 | 8.12 | 1.07 | 0.71 | 20.87 | | 0.59 | 12.75 |
| 2063 | 684558.31 | 602737.08 | BNDY | 7.60 | 7.61 | 1.21 | 0.56 | 20.23 | | 0.63 | 12.62 |
| 2064 | 684574.68 | 602718.19 | BNDY | 7.16 | 7.15 | 1.12 | 0.56 | 20.08 | | 0.53 | 12.93 |
| 2065 | 684591.05 | 602699.29 | BNDY | 6.73 | 6.70 | 1.10 | 0.66 | 20.05 | | 0.56 | 13.35 |
| 2066 | 684607.42 | 602680.39 | BNDY | 6.29 | 6.33 | 1.19 | 0.82 | 19.71 | | 0.57 | 13.37 |
| 2067 | 684623.78 | 602661.50 | BNDY | 5.86 | 5.85 | 1.21 | 0.55 | 19.23 | | 0.61 | 13.38 |
| 2068 | 684640.15 | 602642.60 | BNDY | 5.43 | 5.37 | 1.14 | 0.87 | 18.68 | | 0.53 | 13.31 |
| 2069 | 684743.44 | 602706.51 | GRID | 17.78 | 17.79 | 1.16 | 0.48 | 20.00 | | 0.57 | 2.21 |
| 2070 | 684743.44 | 602731.51 | GRID | 15.37 | 15.39 | 1.16 | 0.71 | 19.42 | | 0.60 | 4.03 |
| 2071 | 684718.44 | 602756.51 | GRID | 15.80 | 15.79 | 1.14 | 1.03 | 20.68 | | 0.61 | 4.88 |
| 2072 | 684718.44 | 602706.51 | GRID | 18.02 | 18.02 | 1.18 | 0.50 | 20.38 | | 0.52 | 2.36 |
| 2073 | 684693.44 | 602706.51 | GRID | 15.37 | 15.35 | 1.18 | 1.24 | 20.69 | | 0.56 | 5.34 |
| 2074 | 684693.44 | 602731.51 | GRID | 18.43 | 18.47 | 1.13 | 0.53 | 21.03 | | 0.50 | 2.56 |
| 2075 | 684693.44 | 602756.51 | GRID | 18.84 | 18.84 | 1.10 | 0.60 | 21.19 | | 0.58 | 2.36 |
| 2076 | 684693.44 | 602781.51 | GRID | 19.25 | 19.26 | 1.08 | 0.59 | 21.45 | | 0.52 | 2.19 |
| 2077 | 684668.44 | 602806.51 | GRID | 17.44 | 17.40 | 1.22 | 0.51 | 21.63 | | 0.62 | 4.23 |
| 2078 | 684668.44 | 602781.51 | GRID | 17.08 | 17.10 | 1.14 | 0.56 | 21.38 | | 0.54 | 4.28 |
| 2079 | 684668.44 | 602756.51 | GRID | 16.38 | 16.40 | 1.16 | 0.57 | 21.08 | | 0.53 | 4.69 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2080 | 684668.44 | 602731.51 | GRID | 15.99 | 15.95 | 1.21 | 0.70 | 21.03 | | 0.55 | 5.08 |
| 2081 | 684668.44 | 602706.51 | GRID | 18.32 | 18.33 | 1.11 | 0.52 | 20.75 | | 0.54 | 2.43 |
| 2082 | 684668.44 | 602681.51 | GRID | 17.91 | 17.82 | 1.27 | 0.50 | 20.31 | | 0.49 | 2.48 |
| 2083 | 684668.44 | 602656.51 | GRID | 14.93 | 14.87 | 1.28 | 0.80 | 19.61 | | 0.56 | 4.73 |
| 2084 | 684643.44 | 602706.51 | GRID | 18.61 | 18.56 | 1.22 | 0.53 | 20.88 | | 0.57 | 2.32 |
| 2085 | 684643.44 | 602731.51 | GRID | 16.27 | 16.19 | 1.29 | 0.50 | 21.08 | | 0.59 | 4.88 |
| 2086 | 684643.44 | 602756.51 | GRID | 16.85 | 16.78 | 1.22 | 0.52 | 21.19 | | 0.56 | 4.40 |
| 2087 | 684643.44 | 602781.51 | GRID | 17.25 | 17.23 | 1.23 | 0.49 | 21.59 | | 0.57 | 4.36 |
| 2088 | 684643.44 | 602806.51 | GRID | 17.61 | 17.60 | 1.18 | 0.76 | 21.92 | | 0.55 | 4.32 |
| 2089 | 684643.44 | 602831.51 | GRID | 17.71 | 17.69 | 1.21 | 0.83 | 22.32 | | 0.55 | 4.63 |
| 2090 | 684618.44 | 602731.51 | GRID | 16.56 | 16.60 | 1.19 | 0.45 | 21.10 | | 0.58 | 4.50 |
| 2091 | 684618.44 | 602756.51 | GRID | 17.06 | 17.07 | 1.18 | 0.52 | 21.45 | | 0.55 | 4.38 |
| 2092 | 684618.44 | 602781.51 | GRID | 17.42 | 17.43 | 1.14 | 0.57 | 21.79 | | 0.55 | 4.37 |
| 2093 | 684618.44 | 602806.51 | GRID | 17.59 | 17.56 | 1.21 | 0.58 | 22.16 | | 0.54 | 4.59 |
| 2094 | 684618.44 | 602831.51 | GRID | 17.69 | 17.63 | 1.21 | 0.55 | 22.41 | | 0.55 | 4.79 |
| 2095 | 684618.44 | 602856.51 | GRID | 20.32 | 20.30 | 1.17 | 0.57 | 22.66 | | 0.64 | 2.37 |
| 2096 | 684593.44 | 602881.51 | GRID | 19.56 | 19.51 | 1.16 | 0.58 | 22.18 | | 0.75 | 2.67 |
| 2097 | 684593.44 | 602856.51 | GRID | 19.93 | 19.88 | 1.22 | 0.49 | 22.40 | | 0.73 | 2.52 |
| 2098 | 684593.44 | 602806.51 | GRID | 17.57 | 17.50 | 1.24 | 0.53 | 22.20 | | 0.57 | 4.70 |
| 2099 | 684593.44 | 602781.51 | GRID | 17.47 | 17.47 | 1.17 | 0.57 | 21.94 | | 0.58 | 4.47 |
| 2100 | 684593.44 | 602756.51 | GRID | 17.23 | 17.22 | 1.22 | 0.48 | 21.62 | | 0.62 | 4.40 |
| 2101 | 684593.44 | 602706.51 | GRID | 6.81 | 6.79 | 1.23 | 0.60 | 20.38 | | 0.58 | 13.59 |
| 2102 | 684568.44 | 602731.51 | GRID | 7.41 | 7.46 | 1.13 | 0.55 | 20.44 | | 0.68 | 12.97 |
| 2103 | 684568.44 | 602781.51 | GRID | 17.44 | 17.39 | 1.22 | 0.57 | 21.82 | | 0.53 | 4.43 |
| 2104 | 684568.44 | 602831.51 | GRID | 19.87 | 19.85 | 1.12 | 0.65 | 22.32 | | 0.70 | 2.47 |
| 2105 | 684568.44 | 602856.51 | GRID | 19.43 | 19.38 | 1.21 | 0.56 | 21.98 | | 0.77 | 2.59 |
| 2106 | 684568.44 | 602881.51 | GRID | 18.79 | 18.77 | 1.16 | 0.57 | 21.39 | | 0.75 | 2.62 |
| 2108 | 684543.4362 | 602956.5129 | GRID | 14.35 | 14.32 | 1.26 | | 19.11 | | 0.55 | 4.79 |
| 2109 | 684543.4362 | 602931.5129 | GRID | 13.88 | 13.96 | 1.03 | | 19.21 | | 0.65 | 5.25 |
| 2110 | 684543.4362 | 602906.5129 | GRID | 6.37 | 6.46 | 1.14 | | 19.75 | | 0.58 | 13.29 |
| 2111 | 684543.44 | 602856.51 | GRID | 18.74 | 18.76 | 1.12 | 0.57 | 21.17 | | 0.72 | 2.41 |
| 2112 | 684543.44 | 602831.51 | GRID | 19.47 | 19.49 | 1.14 | 0.55 | 21.74 | | 0.58 | 2.26 |
| 2113 | 684543.44 | 602806.51 | GRID | 19.60 | 19.64 | 1.10 | 0.65 | 22.07 | | 0.59 | 2.43 |
| 2114 | 684518.44 | 602831.51 | GRID | 18.61 | 18.57 | 1.28 | 0.45 | 20.90 | | 0.60 | 2.33 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2115 | 684518.44 | 602856.51 | GRID | 18.10 | 18.16 | 1.20 | 0.46 | 20.30 | | 0.49 | 2.15 |
| 2116 | 684518.4362 | 602906.5129 | GRID | 12.95 | 12.99 | 1.11 | | 19.06 | | 0.59 | 6.08 |
| 2117 | 684518.4362 | 602931.5129 | GRID | 13.70 | 13.78 | 1.16 | | 19.13 | | 0.54 | 5.35 |
| 2118 | 684518.44 | 602956.51 | GRID | 16.84 | 16.83 | 1.11 | 0.58 | 19.00 | | 0.49 | 2.18 |
| 2119 | 684518.44 | 602981.51 | GRID | 15.93 | 15.93 | 1.10 | 0.60 | 18.18 | | 0.54 | 2.24 |
| 2121 | 684493.44 | 603006.51 | GRID | 14.49 | 14.44 | 1.20 | 0.53 | 16.76 | | 0.59 | 2.32 |
| 2122 | 684493.44 | 602981.51 | GRID | 14.91 | 14.90 | 1.14 | 0.57 | 17.23 | | 0.62 | 2.33 |
| 2123 | 684493.44 | 602956.51 | GRID | 15.48 | 15.48 | 1.19 | 0.54 | 17.94 | | 0.55 | 2.47 |
| 2124 | 684493.44 | 602931.51 | GRID | 16.57 | 16.66 | 1.01 | 0.62 | 18.79 | | 0.50 | 2.13 |
| 2125 | 684493.4362 | 602906.5129 | GRID | 13.39 | 13.44 | 1.16 | | 18.71 | | 0.60 | 5.27 |
| 2126 | 684493.44 | 602831.51 | GRID | 9.60 | 9.61 | 1.19 | 0.48 | 19.85 | | 0.50 | 10.24 |
| 2127 | 684468.44 | 603031.51 | GRID | 13.11 | 13.10 | 1.17 | 0.53 | 15.41 | | 0.62 | 2.31 |
| 2128 | 684468.44 | 603006.51 | GRID | 13.49 | 13.50 | 1.10 | 0.58 | 15.81 | | 0.63 | 2.31 |
| 2129 | 684468.44 | 602981.51 | GRID | 13.91 | 13.92 | 1.21 | 0.50 | 16.27 | | 0.64 | 2.35 |
| 2130 | 684468.44 | 602956.51 | GRID | 14.41 | 14.46 | 1.09 | 0.58 | 16.76 | | 0.60 | 2.30 |
| 2131 | 684468.44 | 602931.51 | GRID | 15.04 | 15.05 | 1.12 | 0.55 | 17.57 | | 0.54 | 2.52 |
| 2132 | 684468.4362 | 602856.5129 | GRID | 5.94 | 5.95 | 1.12 | | 18.08 | | 0.61 | 12.13 |
| 2133 | 684443.4362 | 602881.5129 | GRID | 7.90 | 7.89 | 1.11 | | 16.78 | | 0.71 | 8.89 |
| 2134 | 684443.4362 | 602906.5129 | GRID | 12.14 | 12.14 | 1.14 | | 16.66 | | 0.62 | 4.52 |
| 2135 | 684443.44 | 602931.51 | GRID | 13.75 | 13.83 | 1.07 | 0.61 | 16.15 | | 0.65 | 2.33 |
| 2136 | 684443.44 | 602956.51 | GRID | 13.27 | 13.32 | 1.16 | 0.47 | 15.60 | | 0.65 | 2.28 |
| 2137 | 684443.44 | 602981.51 | GRID | 12.85 | 12.85 | 1.09 | 0.62 | 15.17 | | 0.61 | 2.32 |
| 2138 | 684443.44 | 603006.51 | GRID | 12.44 | 12.46 | 1.11 | 0.54 | 14.78 | | 0.67 | 2.32 |
| 2139 | 684443.44 | 603031.51 | GRID | 12.01 | 11.99 | 1.15 | 0.58 | 14.38 | | 0.67 | 2.39 |
| 2140 | 684443.44 | 603056.51 | GRID | 11.69 | 11.64 | 1.14 | 0.55 | 13.96 | | 0.63 | 2.32 |
| 2141 | 684443.44 | 603081.51 | GRID | 11.40 | 11.37 | 1.15 | 0.60 | 13.63 | | 0.51 | 2.26 |
| 2142 | 684418.44 | 603106.51 | GRID | 10.24 | 10.18 | 1.26 | 0.49 | 12.46 | | 0.54 | 2.28 |
| 2143 | 684418.44 | 603081.51 | GRID | 10.44 | 10.46 | 1.10 | 0.59 | 12.79 | | 0.64 | 2.33 |
| 2144 | 684418.44 | 603056.51 | GRID | 10.65 | 10.58 | 1.17 | 0.59 | 13.22 | | 0.79 | 2.64 |
| 2145 | 684418.44 | 603031.51 | GRID | 10.92 | 10.83 | 1.21 | 0.77 | 13.42 | | 0.61 | 2.59 |
| 2146 | 684418.44 | 603006.51 | GRID | 11.27 | 11.35 | 1.04 | 0.73 | 13.83 | | 0.71 | 2.48 |
| 2147 | 684418.44 | 602981.51 | GRID | 11.70 | 11.69 | 1.19 | 0.50 | 14.07 | | 0.69 | 2.38 |
| 2148 | 684418.44 | 602956.51 | GRID | 12.12 | 12.10 | 1.21 | 0.52 | 14.50 | | 0.67 | 2.40 |
| 2149 | 684418.44 | 602906.51 | GRID | 9.84 | 9.79 | 1.34 | 0.64 | 15.00 | | 0.55 | 5.21 |


| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2150 | 684393.44 | 602931.51 | GRID | 8.63 | 8.62 | 1.19 | 0.75 | 13.32 | | 0.64 | 4.70 |
| 2151 | 684393.44 | 602956.51 | GRID | 10.95 | 10.94 | 1.19 | 0.66 | 13.29 | | 0.49 | 2.34 |
| 2152 | 684393.44 | 602981.51 | GRID | 10.53 | 10.56 | 1.21 | 0.65 | 13.01 | | 0.60 | 2.45 |
| 2153 | 684393.44 | 603006.51 | GRID | 10.15 | 10.09 | 1.19 | 0.55 | 12.68 | | 0.79 | 2.59 |
| 2154 | 684393.44 | 603031.51 | GRID | 9.91 | 9.90 | 1.17 | 0.58 | 12.31 | | 0.66 | 2.41 |
| 2155 | 684393.44 | 603056.51 | GRID | 9.70 | 9.65 | 1.20 | 0.56 | 12.02 | | 0.61 | 2.37 |
| 2156 | 684393.44 | 603106.51 | GRID | 9.38 | 9.33 | 1.25 | 0.53 | 11.70 | | 0.52 | 2.37 |
| 2157 | 684393.44 | 603131.51 | GRID | 9.32 | 9.24 | 1.18 | 0.64 | 11.91 | | 0.61 | 2.67 |
| 2159 | 684368.4362 | 603181.5129 | GRID | 6.44 | 6.36 | 1.29 | | 11.99 | | 0.55 | 5.63 |
| 2160 | 684368.44 | 603156.51 | GRID | 8.56 | 8.52 | 1.29 | 0.53 | 11.62 | | 0.62 | 3.10 |
| 2161 | 684368.44 | 603131.51 | GRID | 8.65 | 8.58 | 1.18 | 0.62 | 11.41 | | 0.52 | 2.83 |
| 2162 | 684368.44 | 603106.51 | GRID | 8.75 | 8.68 | 1.19 | 0.64 | 11.31 | | 0.59 | 2.63 |
| 2163 | 684368.44 | 603056.51 | GRID | 8.85 | 8.80 | 1.14 | 0.61 | 11.37 | | 0.52 | 2.57 |
| 2164 | 684368.44 | 603031.51 | GRID | 8.98 | 8.95 | 1.14 | 0.56 | 11.52 | | 0.58 | 2.56 |
| 2165 | 684368.44 | 603006.51 | GRID | 9.17 | 9.13 | 1.25 | 0.52 | 11.54 | | 0.55 | 2.41 |
| 2166 | 684368.44 | 602981.51 | GRID | 9.38 | 9.32 | 1.32 | 0.48 | 11.79 | | 0.67 | 2.47 |
| 2167 | 684343.44 | 603006.51 | GRID | 8.26 | 8.19 | 1.28 | 0.48 | 10.85 | | 0.60 | 2.66 |
| 2168 | 684343.44 | 603031.51 | GRID | 8.15 | 8.11 | 1.17 | 0.58 | 10.78 | | 0.56 | 2.66 |
| 2169 | 684343.44 | 603056.51 | GRID | 8.17 | 8.16 | 1.13 | 0.58 | 10.76 | | 0.54 | 2.60 |
| 2170 | 684343.44 | 603106.51 | GRID | 8.37 | 8.37 | 1.09 | 0.66 | 10.91 | | 0.55 | 2.53 |
| 2171 | 684343.44 | 603131.51 | GRID | 8.36 | 8.39 | 1.08 | 0.62 | 10.97 | | 0.54 | 2.59 |
| 2172 | 684343.4362 | 603181.5129 | GRID | 6.47 | 6.46 | 1.14 | | 11.46 | | 1.02 | 5.01 |
| 2173 | 684343.4362 | 603206.5129 | GRID | 6.78 | 6.70 | 1.26 | | 11.85 | | 0.56 | 5.15 |
| 2174 | 684318.44 | 603231.51 | GRID | 8.81 | 8.74 | 1.22 | 0.54 | 11.68 | | 1.18 | 2.94 |
| 2175 | 684318.44 | 603206.51 | GRID | 6.84 | 6.89 | 1.08 | 0.66 | 11.28 | | 0.81 | 4.39 |
| 2176 | 684318.4362 | 603181.5129 | GRID | 6.51 | 6.46 | 1.20 | | 10.99 | | 0.59 | 4.53 |
| 2177 | 684318.4362 | 603156.5129 | GRID | 6.25 | 6.17 | 1.22 | | 10.85 | | 0.59 | 4.68 |
| 2178 | 684318.44 | 603031.51 | GRID | 4.71 | 4.79 | 1.14 | 0.66 | 10.30 | | 0.46 | 5.52 |
| 2179 | 684293.44 | 603056.51 | GRID | 4.35 | 4.27 | 1.18 | 0.76 | 10.05 | | 0.57 | 5.78 |
| 2180 | 684293.44 | 603081.51 | GRID | 7.37 | 7.32 | 1.30 | 0.71 | 10.21 | | 0.60 | 2.89 |
| 2181 | 684293.4362 | 603131.5129 | GRID | 5.94 | 5.89 | 1.23 | | 10.45 | | 0.60 | 4.56 |
| 2182 | 684293.4362 | 603156.5129 | GRID | 6.32 | 6.33 | 1.11 | | 10.59 | | 0.52 | 4.26 |
| 2183 | 684293.44 | 603181.51 | GRID | 6.52 | 6.60 | 1.18 | 0.55 | 10.75 | | 0.55 | 4.15 |
| 2184 | 684293.44 | 603206.51 | GRID | 7.97 | 7.98 | 1.14 | 0.58 | 10.92 | | 0.57 | 2.94 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2185 | 684293.44 | 603231.51 | GRID | 8.29 | 8.21 | 1.26 | 0.61 | 11.13 | | 0.58 | 2.92 |
| 2186 | 684293.44 | 603256.51 | GRID | 8.50 | 8.46 | 1.43 | 0.45 | 11.56 | | 1.03 | 3.09 |
| 2187 | 684268.44 | 603281.51 | GRID | 7.07 | 7.05 | 1.28 | 0.53 | 11.07 | | 0.56 | 4.02 |
| 2188 | 684268.44 | 603256.51 | GRID | 8.18 | 8.12 | 1.25 | 0.52 | 11.04 | | 0.62 | 2.92 |
| 2189 | 684268.44 | 603231.51 | GRID | 7.79 | 7.80 | 1.10 | 0.59 | 10.86 | | 0.54 | 3.06 |
| 2190 | 684268.44 | 603206.51 | GRID | 7.41 | 7.49 | 1.12 | 0.56 | 10.77 | | 0.58 | 3.29 |
| 2191 | 684268.44 | 603181.51 | GRID | 7.46 | 7.49 | 1.18 | 0.49 | 10.64 | | 0.56 | 3.16 |
| 2192 | 684268.44 | 603156.51 | GRID | 6.21 | 6.19 | 1.12 | 0.66 | 10.48 | | 0.55 | 4.30 |
| 2193 | 684268.4362 | 603131.5129 | GRID | 5.85 | 5.85 | 1.18 | | 10.29 | | 0.59 | 4.44 |
| 2194 | 684268.4362 | 603106.5129 | GRID | 3.07 | 3.12 | 1.06 | | 10.16 | | 0.62 | 7.04 |
| 2195 | 684268.4362 | 603081.5129 | GRID | 5.85 | 5.88 | 1.13 | | 9.88 | | 0.41 | 4.01 |
| 2196 | 684243.44 | 603131.51 | GRID | 2.98 | 3.02 | 1.10 | 0.67 | 10.13 | | 0.53 | 7.11 |
| 2197 | 684243.44 | 603181.51 | GRID | 7.56 | 7.52 | 1.27 | 0.50 | 10.45 | | 0.55 | 2.92 |
| 2198 | 684243.44 | 603206.51 | GRID | 7.25 | 7.29 | 1.08 | 0.66 | 10.59 | | 0.52 | 3.29 |
| 2199 | 684243.44 | 603231.51 | GRID | 7.47 | 7.47 | 1.20 | 0.54 | 10.70 | | 0.58 | 3.23 |
| 2200 | 684243.44 | 603256.51 | GRID | 7.83 | 7.79 | 1.22 | 0.54 | 10.69 | | 0.53 | 2.90 |
| 2201 | 684243.4362 | 603281.5129 | GRID | 7.25 | 7.20 | 1.20 | | 10.52 | | 0.58 | 3.32 |
| 2202 | 684218.4362 | 603281.5129 | GRID | 6.93 | 6.95 | 1.14 | | 10.53 | | 0.50 | 3.58 |
| 2203 | 684218.44 | 603256.51 | GRID | 7.09 | 7.10 | 1.19 | 0.57 | 10.44 | | 0.58 | 3.34 |
| 2204 | 684218.44 | 603231.51 | GRID | 7.43 | 7.43 | 1.19 | 0.52 | 10.42 | | 0.52 | 2.99 |
| 2205 | 684218.44 | 603206.51 | GRID | 7.25 | 7.21 | 1.19 | 0.56 | 10.38 | | 0.53 | 3.18 |
| 2206 | 684218.44 | 603156.51 | GRID | 7.69 | 7.70 | 1.14 | 0.54 | 10.15 | | 0.59 | 2.45 |
| 2208 | 684193.4362 | 603181.5129 | GRID | 7.48 | 7.44 | 1.27 | 0.45 | 10.16 | | 0.60 | 2.72 |
| 2209 | 684193.4362 | 603206.5129 | GRID | 7.25 | 7.28 | 1.09 | 0.59 | 10.17 | | 0.56 | 2.89 |
| 2210 | 684193.4362 | 603231.5129 | GRID | 7.34 | 7.30 | 1.19 | 0.56 | 10.19 | | 0.52 | 2.89 |
| 2211 | 684193.4362 | 603256.5129 | GRID | 6.74 | 6.76 | 1.14 | | 10.24 | | 0.60 | 3.48 |
| 2212 | 684168.4362 | 603256.5129 | GRID | 6.51 | 6.46 | 1.22 | | 10.03 | | 0.59 | 3.57 |
| 2213 | 684168.4362 | 603231.5129 | GRID | 6.45 | 6.50 | 1.15 | 0.61 | 10.04 | | 0.59 | 3.54 |
| 2214 | 684168.4362 | 603206.5129 | GRID | 7.60 | 7.60 | 1.10 | 0.67 | 10.06 | | 0.60 | 2.46 |
| 2215 | 684143.4362 | 603231.5129 | GRID | 6.43 | 6.49 | 1.19 | | 9.76 | | 0.65 | 3.27 |
| 2216 | 684768.70 | 602713.78 | BRK | 14.50 | 14.53 | 1.15 | 0.48 | 17.86 | | 0.58 | 3.34 |
| 2217 | 684755.49 | 602705.02 | BRK | 14.78 | 14.86 | 1.07 | 0.56 | 19.36 | | 0.60 | 4.50 |
| 2218 | 684750.5364 | 602706.2925 | BRK | 17.38 | 17.30 | 1.18 | 0.54 | 19.62 | | 0.52 | 2.32 |
| 2219 | 684719.5112 | 602728.0937 | BRK | 18.07 | 17.99 | 1.30 | 0.45 | 20.61 | | 0.56 | 2.62 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2220 | 684721.25 | 602731.77 | BRK | 15.36 | 15.36 | 1.23 | 0.79 | 20.54 | | 0.55 | 5.18 |
| 2222 | 684686.52 | 602801.63 | BRK | 17.16 | 17.18 | 1.08 | 0.70 | 20.72 | | 0.60 | 3.54 |
| 2223 | 684714.8245 | 602681.948 | BRK | 17.78 | 17.74 | 1.25 | 0.48 | 20.02 | | 0.55 | 2.28 |
| 2224 | 684695.23 | 602678.31 | BRK | 15.18 | 15.25 | 1.15 | 0.79 | 20.15 | | 0.63 | 4.90 |
| 2225 | 684691.1633 | 602677.7592 | BRK | 17.91 | 17.89 | 1.21 | 0.48 | 20.16 | | 0.58 | 2.27 |
| 2226 | 684679.2563 | 602656.4152 | BRK | 17.47 | 17.43 | 1.18 | 0.53 | 19.79 | | 0.65 | 2.37 |
| 2227 | 684678.94 | 602651.43 | BRK | 14.87 | 14.85 | 1.28 | 0.60 | 19.57 | | 0.56 | 4.72 |
| 2228 | 684668.1313 | 602643.1239 | BRK | 14.48 | 14.54 | 1.04 | | 19.15 | | 0.57 | 4.61 |
| 2229 | 684657.2632 | 602634.2584 | BRK | 5.13 | 5.21 | 1.15 | | 18.69 | | 0.53 | 13.48 |
| 2230 | 684652.03 | 602663.18 | BRK | 15.06 | 15.12 | 1.05 | 0.59 | 19.65 | | 0.53 | 4.53 |
| 2231 | 684641.00 | 602654.19 | BRK | 5.58 | 5.57 | 1.24 | 0.68 | 19.21 | | 0.54 | 13.64 |
| 2232 | 684642.3753 | 602682.8752 | BRK | 18.24 | 18.17 | 1.23 | 0.52 | 20.37 | | 0.45 | 2.20 |
| 2233 | 684640.23 | 602679.29 | BRK | 15.45 | 15.55 | 1.11 | 0.72 | 20.20 | | 0.63 | 4.65 |
| 2234 | 684618.68 | 602681.55 | BRK | 6.20 | 6.28 | 1.15 | 0.79 | 20.09 | | 0.70 | 13.81 |
| 2235 | 684632.7117 | 602692.9947 | BRK | 18.26 | 18.21 | 1.27 | 0.46 | 20.60 | | 0.66 | 2.39 |
| 2236 | 684620.0994 | 602708.5791 | BRK | 18.67 | 18.58 | 1.22 | 0.51 | 20.95 | | 0.63 | 2.37 |
| 2239 | 684603.43 | 602700.25 | BRK | 6.62 | 6.69 | 1.10 | 0.65 | 20.52 | | 0.63 | 13.83 |
| 2240 | 684580.79 | 602728.00 | BRK | 7.24 | 7.30 | 1.12 | 0.76 | 20.82 | | 0.76 | 13.52 |
| 2241 | 684592.09 | 602737.22 | BRK | 16.96 | 16.96 | 1.12 | 0.64 | 21.25 | | 0.53 | 4.30 |
| 2245 | 684652.97 | 602837.52 | BRK | 17.97 | 17.92 | 1.14 | 0.63 | 21.66 | | 0.60 | 3.73 |
| 2248 | 684632.9903 | 602849.2342 | BRK | 20.53 | 20.48 | 1.21 | 0.55 | 22.74 | | 0.51 | 2.27 |
| 2249 | 684573.19 | 602760.13 | BRK | 17.37 | 17.33 | 1.24 | 0.50 | 21.53 | | 0.54 | 4.21 |
| 2250 | 684562.02 | 602751.01 | BRK | 7.76 | 7.85 | 1.13 | 0.58 | 21.32 | | 0.62 | 13.46 |
| 2251 | 684549.64 | 602787.35 | BRK | 17.30 | 17.31 | 1.11 | 0.56 | 21.81 | | 0.53 | 4.50 |
| 2252 | 684539.27 | 602778.90 | BRK | 8.39 | 8.43 | 1.20 | 0.65 | 21.45 | | 0.51 | 13.02 |
| 2253 | 684568.32 | 602806.28 | BRK | 17.40 | 17.45 | 1.20 | 0.67 | 22.12 | | 0.56 | 4.67 |
| 2254 | 684565.5811 | 602809.0345 | BRK | 19.99 | 19.95 | 1.16 | 0.56 | 22.34 | | 0.68 | 2.40 |
| 2255 | 684590.8103 | 602830.4334 | BRK | 20.31 | 20.27 | 1.13 | 0.58 | 22.50 | | 0.52 | 2.23 |
| 2256 | 684593.43 | 602827.27 | BRK | 17.57 | 17.64 | 1.18 | 0.48 | 22.33 | | 0.55 | 4.69 |
| 2257 | 684611.5712 | 602875.6442 | BRK | 20.29 | 20.21 | 1.18 | 0.58 | 22.52 | | 0.54 | 2.31 |
| 2259 | 684588.8716 | 602908.3113 | BRK | 19.04 | 19.11 | 1.12 | 0.49 | 21.37 | | 0.65 | 2.26 |
| 2261 | 684576.8825 | 602901.086 | BRK | 18.28 | 18.32 | 1.19 | 0.46 | 21.15 | | 0.68 | 2.84 |
| 2262 | 684562.2754 | 602912.3889 | BRK | 6.48 | 6.55 | 1.12 | | 20.16 | | 0.60 | 13.61 |
| 2263 | 684546.9908 | 602879.913 | BRK | 18.10 | 18.01 | 1.23 | 0.58 | 20.48 | | 0.52 | 2.46 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2264 | 684536.885 | 602894.4246 | BRK | 6.32 | 6.38 | 1.19 | | 19.87 | | 0.58 | 13.49 |
| 2265 | 684518.8905 | 602881.693 | BRK | 6.20 | 6.26 | 1.20 | | 19.67 | | 0.59 | 13.41 |
| 2266 | 684529.1345 | 602867.2143 | BRK | 18.03 | 17.99 | 1.12 | 0.61 | 20.34 | | 0.56 | 2.35 |
| 2267 | 684498.05 | 602850.83 | BRK | 14.79 | 14.79 | 1.20 | 0.65 | 19.61 | | 0.55 | 4.81 |
| 2268 | 684490.4473 | 602861.5687 | BRK | 6.02 | 6.09 | 1.20 | | 19.03 | | 0.62 | 12.94 |
| 2269 | 684529.6237 | 602815.0512 | BRK | 19.24 | 19.20 | 1.12 | 0.59 | 21.47 | | 0.55 | 2.26 |
| 2270 | 684517.71 | 602805.33 | BRK | 8.99 | 9.02 | 1.13 | 0.68 | 21.32 | | 0.55 | 12.30 |
| 2271 | 684492.1914 | 603028.6259 | BRK | 14.08 | 14.16 | 1.03 | 0.59 | 16.31 | | 0.52 | 2.14 |
| 2272 | 684495.31 | 603031.35 | BRK | 11.32 | 11.38 | 1.05 | 0.93 | 16.05 | | 0.61 | 4.68 |
| 2273 | 684467.4432 | 603056.9831 | BRK | 12.70 | 12.63 | 1.22 | 0.56 | 14.91 | | 0.51 | 2.28 |
| 2274 | 684470.54 | 603059.69 | BRK | 9.95 | 9.95 | 1.10 | 0.62 | 14.78 | | 0.50 | 4.83 |
| 2275 | 684469.1556 | 602880.7528 | BRK | 13.16 | 13.25 | 1.10 | | 18.07 | | 0.59 | 4.83 |
| 2276 | 684420.7841 | 602931.9468 | BRK | 12.65 | 12.68 | 1.12 | 0.56 | 15.04 | | 0.67 | 2.36 |
| 2277 | 684418.27 | 602928.58 | BRK | 9.85 | 9.93 | 1.18 | 0.79 | 14.81 | | 0.62 | 4.88 |
| 2278 | 684497.2553 | 602878.6355 | BRK | 6.10 | 6.09 | 1.23 | | 18.81 | | 0.55 | 12.72 |
| 2279 | 684491.4795 | 602886.7988 | BRK | 12.77 | 12.69 | 1.19 | | 18.60 | | 0.56 | 5.92 |
| 2280 | 684466.7342 | 602909.2074 | BRK | 16.17 | 16.17 | 1.12 | 0.53 | 18.34 | | 0.51 | 2.16 |
| 2281 | 684469.256 | 602906.0452 | BRK | 13.48 | 13.50 | 1.17 | | 18.23 | | 0.53 | 4.73 |
| 2282 | 684569.9023 | 602930.035 | BRK | 6.56 | 6.58 | 1.18 | | 19.90 | | 0.54 | 13.32 |
| 2283 | 684564.1649 | 602938.2256 | BRK | 13.23 | 13.27 | 1.17 | | 19.44 | | 0.54 | 6.18 |
| 2284 | 684462.8239 | 602873.5669 | BRK | 6.77 | 6.86 | 1.15 | | 17.80 | | 0.62 | 10.94 |
| 2285 | 684396.208 | 603081.167 | BRK | 9.60 | 9.51 | 1.21 | 0.58 | 11.89 | | 0.58 | 2.38 |
| 2286 | 684394.9524 | 603084.8241 | BRK | 7.02 | 6.94 | 1.29 | 0.80 | 11.83 | | 0.57 | 4.89 |
| 2287 | 684370.173 | 603081.0797 | BRK | 6.46 | 6.46 | 1.22 | 0.84 | 11.35 | | 0.60 | 4.88 |
| 2288 | 684369.7302 | 603084.5148 | BRK | 8.77 | 8.80 | 1.17 | 0.57 | 11.25 | | 0.54 | 2.45 |
| 2289 | 684346.8159 | 603155.6092 | BRK | 8.42 | 8.34 | 1.28 | 0.58 | 11.18 | | 0.62 | 2.85 |
| 2290 | 684344.2815 | 603158.0189 | BRK | 6.97 | 6.96 | 1.23 | | 11.16 | | 0.71 | 4.20 |
| 2291 | 684343.8322 | 603080.6842 | BRK | 5.89 | 5.86 | 1.21 | 0.87 | 10.84 | | 0.55 | 4.98 |
| 2292 | 684344.0192 | 603084.2703 | BRK | 8.28 | 8.25 | 1.22 | 0.54 | 10.86 | | 0.58 | 2.62 |
| 2293 | 684318.4322 | 603058.4683 | BRK | 7.59 | 7.53 | 1.25 | 0.52 | 10.36 | | 0.61 | 2.83 |
| 2294 | 684314.6302 | 603057.9817 | BRK | 5.03 | 5.12 | 1.16 | 0.82 | 10.34 | | 0.61 | 5.23 |
| 2296 | 684244.6142 | 603103.2697 | BRK | 6.25 | 6.16 | 1.25 | | 9.75 | | 0.58 | 3.59 |
| 2297 | 684317.0076 | 603131.3066 | BRK | 6.55 | 6.47 | 1.30 | | 10.67 | | 0.58 | 4.21 |
| 2298 | 684318.8822 | 603129.9683 | BRK | 8.06 | 8.09 | 1.10 | 0.56 | 10.73 | | 0.57 | 2.64 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2299 | 684244.4868 | 603157.7645 | BRK | 7.52 | 7.53 | 1.10 | 0.61 | 10.36 | | 0.59 | 2.83 |
| 2300 | 684238.7773 | 603154.4036 | BRK | 3.11 | 3.14 | 1.22 | 0.59 | 10.26 | | 0.58 | 7.12 |
| 2301 | 684221.7368 | 603183.6523 | BRK | 7.75 | 7.68 | 1.20 | 0.55 | 10.33 | | 0.57 | 2.66 |
| 2302 | 684225.099 | 603177.8813 | BRK | 3.30 | 3.26 | 1.21 | 0.80 | 10.31 | | 0.59 | 7.05 |
| 2303 | 684293.4362 | 603106.5129 | GRID | 7.12 | 7.15 | 1.15 | 0.75 | 10.33 | | 0.55 | 3.18 |
| 2304 | 684318.4362 | 603081.5129 | GRID | 5.36 | 5.28 | 1.35 | 0.78 | 10.53 | | 0.63 | 5.25 |
| 2305 | 684268.0011 | 603302.1104 | BNDY | 8.15 | 8.20 | 1.14 | | 11.54 | | 1.61 | 3.34 |
| 2306 | 684383.2214 | 603153.3604 | BRK | 8.95 | 8.87 | 1.19 | 0.61 | 11.85 | | 0.54 | 2.98 |
| 2307 | 684386.53 | 603155.86 | BRK | 6.58 | 6.53 | 1.30 | 0.82 | 11.96 | | 0.56 | 5.43 |
| 2308 | 684541.16 | 602978.86 | BRK | 13.86 | 13.78 | 1.33 | 0.77 | 18.44 | | 0.49 | 4.66 |
| 2309 | 684537.9282 | 602976.1552 | BRK | 16.66 | 16.72 | 1.03 | 0.54 | 19.01 | | 0.56 | 2.29 |
| 2310 | 684519.64 | 603003.49 | BRK | 12.67 | 12.64 | 1.25 | 0.82 | 17.60 | | 0.56 | 4.95 |
| 2311 | 684516.5171 | 603000.7679 | BRK | 15.43 | 15.47 | 1.05 | 0.58 | 17.70 | | 0.59 | 2.22 |
| 2312 | 684688.247 | 602662.9919 | BRK | 17.62 | 17.65 | 1.20 | 0.46 | 19.87 | | 0.55 | 2.21 |
| 2313 | 684666.34 | 602822.94 | BRK | 17.70 | 17.62 | 1.21 | 0.58 | 21.27 | | 0.48 | 3.65 |




Prepared/Date: RJR 07/02/15
Checked/Date: TDD 07/02/15


**Honeywell**
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013900

SA-6 SOUTH CONSTRUCTION CONTROL GRID
FIGURE 1 OF 2
Project 3480-13-0377
Figure 1.1

Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design - SA6 - 2301\DAD\SA6SCtrlGrid.dwg Thu, 02 Jul 2015 - 10:55am roger.frazier




Prepared/Date: RJR 07/02/15
Checked/Date: TDD 07/02/15

**Honeywell**
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013400


SA-6 SOUTH CONSTRUCTION CONTROL GRID
FIGURE 2 OF 2
Project 3480-13-0377
Figure 1.2

Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design-SA6-C3D\CAD\SA6S.dwt Thu, 02 Jul 2015 - 10:59am ingler.rojuler

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING.




MATCH LINE SHEET C-126




LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM OCT. 2015 THROUGH MAY 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

| NO. | DATE | REVISION | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|---|

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP GDL COVER
SOIL GRADING PLAN

FILE NUMBER 12001511A


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ 08619
(609) 689 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 11/17/16 |
| PROJ | 3480-10-0027 |
| DWG | C-125 |
| SHEET | 1 OF 3 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SOUTH CAP GDL COVER SOIL SURVEY-11-17-16.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 4:32 PM




## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM OCT. 2015 THROUGH MAY 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS35737

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | | DR | | | | |

THIS DRAWING IS THE PROPERTY OF AMEC; INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP GDL COVER
SOIL GRADING PLAN

FILE NUMBER 12001511A


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 08223


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 11/17/16 |
| PROJ | 3480-10-0027 |
| DWG | C-126 |
| SHEET | 2 OF 3 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SOUTH CAP GDL COVER SOIL SURVEY-11-17-16.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 4:08 PM




LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

0 20 40 80

SCALE IN FEET

## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.
2. AS-BUILT SOUTH CAP GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM OCT. 2015 THROUGH MAY 2016
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER 12001511A

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS38737

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR | CHK | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP GDL COVER
SOIL GRADING PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ 08619
(609) 689 - 2829


VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 11/17/16 |
| PROJ | 3480-10-0027 |
| DWG | C-127 |
| SHEET | 3 OF 3 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SOUTH CAP GDL COVER SOIL SURVEY-11-17-16.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 4:09 PM




## LEGEND

RP-1 (Repair Number)

LINER SEAM/EDGE

SCB WALL

HB WALL (Inner Edge)

RP: Repair

DSX: Destructive Extrusion Weld Test

DS: Destructive Fusion Weld Test

P: Panel

\- Bead

0 80 160 Feet

NOTE: Refer to ESI Repair Report for repair details

J.H. 01/28/2016


ENTACT 302 Unity Plaza Latrobe, PA 15650


DRAWING NAME

SA6 SOUTH CAP PANEL LAYOUT
60 mil Textured LLDPE Geomembrane
01/28/16

PROJECT NAME & LOCATION

HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




## LEGEND

- GEOCOMPOSITE GAS VENT LAYER (GVL)
- GEOSYNTHETIC CLAY LINER (GCL)
- Class A/16 oz Geotextile
- SCB WALL
- HB WALL (Inner Edge)
- GAS VENT PIPE
- GAS VENT (NOT TO SCALE)

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 1 | 02/14/17 | EJP | AE | AE | ADDED GAS VENT DETAIL |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP GVL/GCL LAYOUT
Class A Geotextile/Gas Vent Layer/Geosynthetic Clay Liner
02/14/17

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

HACKENSACK RIVER

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

ROUTE 440

## LEGEND

GEOCOMPOSITE DRAINAGE LAYER (GDL)

SCB WALL

HB WALL (Inner Edge)

0 80 160 Feet

J.H. 01/27/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

SA6 SOUTH CAP GDL LAYOUT
GEOCOMPOSITE DRAINAGE LAYER 01/27/16

PROJECT NAME & LOCATION

HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

N

GRAND BLVD.

RIVERSIDE DRIVE

A STREET

B STREET

C STREET

D STREET

FRONTAGE STREET

RIVER

D

B

C

A

18

19

20

21

22

23

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

RECORD DRAWING - 12/15/16

LEGEND


Structural Fill Under Roadways

SCE[illegible]LL

HB WALL (Inner Edge)

0 80 160 Feet

SCALE




STRUCTURAL FILL CROSS SECTION
NTS

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/7/16 | EJP | AE | AE | STRUCTURAL FILL UNDER ROADWAYS – SOUTH CAP |
| 1 | 12/15/16 | EJP | AE | AE | ADDED FUTURE DEVELOPMENT LAYOUT & STRUCTURAL FILL X-SECTION |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
STRUCTURAL FILL UNDER ROADWAYS
SOUTH CAP
12/15/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

0 20 40 80

SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GEOMEMBRANE GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT GEOMEMBRANE GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM 7/2/15 THROUGH 10/7/15. GEOMEMBRANE GRADING SURFACES AND CONTOURS WERE GENERATED BY ENTACT, CHECKED BY AMEC AND CONFIRMED BY MASER CONSULTING P.A.*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 7/12/16 | REVISED ASBUILT TOPO PER ENTACTS COMMENTS | BSB | RTH |
| DSGN | | DR CHK | | APVD |

R. THOMAS HUGG

NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
GEOMEMBRANE GRADING
PLAN

FILE NUMBER
12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 889 - 2629

VERIFY SCALE


BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/11/16 |
| PROJ | 3480-10-0027 |
| DWG | C-122 |
| SHEET | 1 OF 3 |

FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-ASBT-SUBGRD-SOUTH-CAP-10-07-15.dwg PLOT DATE: Wed, 19 Oct 2016 PLOT TIME: 3:35 PM

FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-ASBT-SUBGRD-SOUTH-CAP-10-07-15.dwg PLOT DATE: Wed, 19 Oct 2016 PLOT TIME: 3:35 PM

MATCH LINE SHEET C-124




LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

SCALE IN FEET: 0 20 40 80

MATCH LINE SHEET C-122

NJ STATE PLANE COORDINATE SYSTEM (NAD83) W E

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER 12001511A

SHEET 2 OF 3 | DWG C-123 | PROJ 3480-10-0027 | DATE 2/11/16

BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"

VERIFY SCALE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

GEOMEMBRANE GRADING PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962


STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 7/12/16 | REVISED ASBUILT TOPO PER ENTACT'S COMMENTS | BSB | RTH |

DSGN | DR | CHK | APVD

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-ASBT-SUBGRD-SOUTH-CAP-10-07-15.dwg PLOT DATE: Wed, 19 Oct 2016 PLOT TIME: 3:34 PM

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER 12001511A

SHEET 3 OF 3
DWG C-124
PROJ 3480-10-0027
DATE 2/11/16
BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"
VERIFY SCALE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

GEOMEMBRANE GRADING PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 7/12/16 | REVISED ASBUILT TOPO PER ENTACT'S COMMENTS | BSB | RTH |

| DSGN | DR | CHK | APVD |
|---|---|---|---|
| | | | |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

# 1.0 Field Density Test Summary Log

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-03-1 | 10/20/2015 | 685534.39 | 601506.6 | 17.45 | 114.3 | 3.3 | 117 | 8.6 | 97.7 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-04-1 | 10/20/2015 | 685573.6 | 601571 | 18.25 | 118 | 4.1 | 117 | 8.6 | 100.9 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-05-1 | 10/20/2015 | 685530.6 | 601543.8 | 17.84 | 116.6 | 6.4 | 117 | 8.6 | 99.7 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-06-1 | 10/20/2015 | 685488.8 | 601532.7 | 14.72 | 118.6 | 7.1 | 117 | 8.6 | 101.4 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-07-1 | 10/20/2015 | 685512.5 | 601575.8 | 17.71 | 115 | 5.9 | 117 | 8.6 | 98.3 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-08-1 | 10/20/2015 | 685536.3 | 601610.7 | 17.61 | 117.3 | 5.4 | 117 | 8.6 | 100.3 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-09-1 | 10/20/2015 | 685492.5 | 601601.9 | 16.43 | 122.4 | 3.7 | 117 | 8.6 | 104.6 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-10-1 | 10/20/2015 | 685448.8 | 601585.8 | 14.79 | 114.5 | 5.6 | 117 | 8.6 | 97.9 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-11-1 | 10/20/2015 | 685477.6 | 601634.6 | 17.08 | 122.2 | 5.8 | 117 | 8.6 | 104.4 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-12-1 | 10/20/2015 | 685503.5 | 601668.8 | 17.32 | 115.3 | 5.9 | 117 | 8.6 | 98.5 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-13-1 | 10/20/2015 | 685462.1 | 601659.8 | 16.59 | 115.5 | 4.5 | 117 | 8.6 | 98.7 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-14-1 | 10/20/2015 | 685423.8 | 601646.8 | 14.54 | 117.9 | 3.2 | 117 | 8.6 | 100.8 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-15-1 | 10/20/2015 | 685444.3 | 601687.7 | 14.73 | 114.8 | 5 | 117 | 8.6 | 98.1 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-16-1 | 10/20/2015 | 685460.2 | 601724.9 | 16.34 | 115.8 | 4 | 117 | 8.6 | 99.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-17-1 | 10/20/2015 | 685433.8 | 601722.1 | 14.62 | 113.7 | 7.3 | 117 | 8.6 | 97.2 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-18-1 | 10/20/2015 | 685394.4 | 601715.0 | 17.21 | 118.9 | 3.4 | 117 | 8.6 | 101.6 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-129-1 | 11/4/2015 | 684281.4 | 603180.2 | 8.75 | 120.2 | 8.0 | 117 | 8.6 | 102.7 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-130-1 | 11/4/2015 | 684216.2 | 603153.2 | 8.83 | 113.6 | 6.7 | 117 | 8.6 | 97.1 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-131-1 | 11/4/2015 | 684261.4 | 603206.7 | 8.42 | 114.1 | 10.9 | 117 | 8.6 | 97.5 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-132-1 | 11/4/2015 | 684292.4 | 603250.5 | 9.53 | 118.3 | 6.2 | 117 | 8.6 | 101.1 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-133-1 | 11/4/2015 | 684236.5 | 603231.2 | 8.64 | 111.6 | 8.1 | 117 | 8.6 | 95.4 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-134-1 | 11/4/2015 | 684175.3 | 603214.9 | 8.57 | 122.5 | 7.7 | 117 | 8.6 | 104.7 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-135-1 | 11/4/2015 | 684215.0 | 603254.8 | 8.32 | 118.4 | 6.6 | 117 | 8.6 | 101.2 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-136-1 | 11/4/2015 | 684251.9 | 603305.8 | 8.40 | 115.1 | 8.8 | 117 | 8.6 | 98.4 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-137-1 | 11/4/2015 | 684189.5 | 603274.7 | 7.64 | 116.9 | 9.3 | 117 | 8.6 | 99.9 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-138-1 | 11/4/2015 | 684143.3 | 603253.5 | 7.36 | 117.9 | 10.5 | 117 | 8.6 | 100.8 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-125-1 | 11/6/2015 | 684314.5 | 603125.9 | 7.68 | 111.2 | 8.2 | 117 | 8.6 | 95.0 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-126-1 | 11/6/2015 | 684270.3 | 603123.5 | 7.05 | 120.0 | 9.7 | 117 | 8.6 | 102.6 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-127-1 | 11/6/2015 | 684305.4 | 603158.0 | 7.55 | 115.7 | 7.6 | 117 | 8.6 | 98.9 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-128-1 | 11/6/2015 | 684334.4 | 603202.5 | 7.75 | 117.7 | 7.4 | 117 | 8.6 | 100.6 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | SF-17-1 | 11/6/2015 | 684184.8 | 603260.8 | 8.67 | 126.8 | 5.4 | 133 | 8.6 | 95.3 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | SF-18-1 | 11/6/2015 | 684230.8 | 603283.7 | 9.16 | 127.2 | 5.9 | 133 | 8.6 | 95.6 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | CS-117-1 | 11/10/2015 | 684405.2 | 603020.3 | 11.64 | 111.0 | 5.2 | 117 | 8.6 | 94.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-118-1 | 11/10/2015 | 684350.5 | 603002.3 | 9.66 | 115.2 | 7.3 | 117 | 8.6 | 98.5 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-119-1 | 11/10/2015 | 684384.6 | 603051.2 | 10.55 | 116.0 | 6.3 | 117 | 8.6 | 99.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-120-1 | 11/10/2015 | 684422.3 | 603088.8 | 11.72 | 115.7 | 6.6 | 117 | 8.6 | 98.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-122-1 | 11/10/2015 | 684307.2 | 603059.7 | 8.50 | 116.8 | 7.5 | 117 | 8.6 | 99.8 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-110-1 | 11/11/2015 | 684445.1 | 602994.4 | 13.50 | 115.5 | 9.7 | 117 | 8.6 | 98.7 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-111-1 | 11/11/2015 | 684477.2 | 602955.6 | 15.83 | 125.3 | 9.0 | 117 | 8.6 | 107.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-112-1 | 11/11/2015 | 684507.0 | 602999.4 | 16.21 | 122.7 | 9.0 | 117 | 8.6 | 104.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-113-1 | 11/11/2015 | 684455.2 | 602974.1 | 14.56 | 118.0 | 9.0 | 117 | 8.6 | 100.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-114-1 | 11/11/2015 | 684396.7 | 602954.9 | 12.21 | 120.6 | 10.0 | 117 | 8.6 | 103.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-115-1 | 11/11/2015 | 684426.7 | 603002.4 | 12.86 | 118.5 | 8.4 | 117 | 8.6 | 101.3 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-116-1 | 11/11/2015 | 684459.1 | 603046.2 | 13.60 | 122.3 | 8.1 | 117 | 8.6 | 104.5 | 90 | 4 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-121-1 | 11/11/2015 | 684364.2 | 603084.9 | 9.73 | 121.3 | 9.3 | 117 | 8.6 | 103.7 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-123-1 | 11/11/2015 | 684344.5 | 603105.3 | 9.51 | 119.7 | 10.3 | 117 | 8.6 | 102.3 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-124-1 | 11/11/2015 | 684370.5 | 603148.7 | 9.80 | 116.4 | 11.3 | 117 | 8.6 | 99.5 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | SF-15-1 | 11/11/2015 | 684280.3 | 603136.7 | 7.80 | 131.4 | 7.0 | 133 | 8.6 | 98.8 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-15-2 | 11/11/2015 | 684279.3 | 603138.5 | 9.15 | 129.9 | 6.8 | 133 | 8.6 | 97.7 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 3 | SF-15-3 | 11/11/2015 | 684271.2 | 603129.6 | 9.64 | 132.5 | 3.3 | 133 | 8.6 | 99.6 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 1 | SF-16-1 | 11/11/2015 | 684316.8 | 603171.2 | 8.29 | 133.6 | 6.8 | 133 | 8.6 | 100.5 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-16-2 | 11/11/2015 | 684319.3 | 603178.5 | 9.48 | 133.6 | 5.4 | 133 | 8.6 | 100.5 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 3 | SF-16-3 | 11/11/2015 | 684314.6 | 603172.8 | 10.70 | 135.6 | 5.0 | 133 | 8.6 | 102.0 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-17-2 | 11/11/2015 | 684184.9 | 603258.9 | 9.56 | 126.4 | 6.7 | 133 | 8.6 | 95.0 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 2 | SF-18-2 | 11/11/2015 | 684234.3 | 603282.9 | 9.71 | 133.9 | 6.3 | 133 | 8.6 | 100.7 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | HC-10-1 | 11/13/2015 | 685444.5 | 601588.5 | 15.22 | 114.6 | 9.5 | 126 | 9.5 | 91.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-11-1 | 11/13/2015 | 685477.6 | 601635.1 | 17.64 | 122.2 | 9.7 | 126 | 9.5 | 97.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-128-1 | 11/13/2015 | 684307.4 | 603209.5 | 9.94 | 114.5 | 10.8 | 126 | 9.5 | 90.9 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-129-1 | 11/13/2015 | 684280.0 | 603181.7 | 9.33 | 110.0 | 10.2 | 126 | 9.5 | 87.3 | 90 | 2 | Horizon C | SF-129-1R (Page 2) | V5N |
| 1 | HC-13-1 | 11/13/2015 | 685461.4 | 601657.1 | 17.20 | 122.5 | 9.3 | 126 | 9.5 | 97.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-131-1 | 11/13/2015 | 684261.3 | 603208.3 | 8.99 | 119.8 | 10.7 | 126 | 9.5 | 95.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-130-1 | 11/13/2015 | 684238.9 | 603170.2 | 9.33 | 121.4 | 10.6 | 126 | 9.5 | 96.3 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-132-1 | 11/13/2015 | 684294.6 | 603252.5 | 10.11 | 114.6 | 13.1 | 126 | 9.5 | 91.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-133-1 | 11/13/2015 | 684236.1 | 603230.2 | 9.14 | 124.7 | 11.3 | 126 | 9.5 | 99.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-134-1 | 11/13/2015 | 684173.7 | 603204.1 | 9.17 | 120.2 | 11 | 126 | 9.5 | 95.4 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-135-1 | 11/13/2015 | 684223.3 | 603252.6 | 8.92 | 120 | 11.5 | 126 | 9.5 | 95.2 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-136-1 | 11/13/2015 | 684264.7 | 603275 | 9.06 | 128.5 | 10.45 | 126 | 9.5 | 102.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-137-1 | 11/13/2015 | 684206.1 | 603237.7 | 9.16 | 118.4 | 10.5 | 126 | 9.5 | 94.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-138-1 | 11/13/2015 | 684160.6 | 603231.8 | 7.70 | 110.2 | 12.4 | 126 | 9.5 | 87.5 | 90 | 2 | Horizon C | SF-138-1R (Page 2) | V5N |
| 1 | HC-14-1 | 11/13/2015 | 685422.6 | 601647.6 | 15.13 | 117.4 | 9.9 | 126 | 9.5 | 93.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-15-1 | 11/13/2015 | 684443.2 | 601689.6 | 15.42 | 117.3 | 9.9 | 126 | 9.5 | 93.1 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | CS-106-1 | 11/17/2015 | 684477.6 | 602852.8 | 7.70 | 117.5 | 8.0 | 117 | 8.6 | 100.4 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-107-1 | 11/17/2015 | 684525.2 | 602897.0 | 7.36 | 108.0 | 4.3 | 117 | 8.6 | 92.3 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-108-1 | 11/17/2015 | 684553.4 | 602948.7 | 15.71 | 123.4 | 7.5 | 117 | 8.6 | 105.5 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-109-1 | 11/17/2015 | 684499.0 | 602921.5 | 14.74 | 119.4 | 5.9 | 117 | 8.6 | 102.1 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | HC-118-1 | 11/17/2015 | 684353.8 | 603000.7 | 10.34 | 113.6 | 11.1 | 126 | 9.5 | 90.2 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-119-1 | 11/17/2015 | 684385.6 | 603051.8 | 11.10 | 120.1 | 12.4 | 126 | 9.5 | 95.3 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-120-1 | 11/17/2015 | 684417.3 | 603086.2 | 12.07 | 128.7 | 10.9 | 126 | 9.5 | 102.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-121-1 | 11/17/2015 | 684363.8 | 603008.5 | 10.29 | 116.5 | 8.3 | 126 | 9.5 | 92.5 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-122-1 | 11/17/2015 | 684319.6 | 603062.6 | 9.47 | 115.4 | 10.1 | 126 | 9.5 | 91.6 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-123-1 | 11/17/2015 | 684343.7 | 603110.5 | 10.08 | 122.0 | 12.0 | 126 | 9.5 | 96.8 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-124-1 | 11/17/2015 | 684373.8 | 603148.2 | 10.36 | 116.8 | 9.5 | 126 | 9.5 | 92.7 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-125-1 | 11/17/2015 | 684322.9 | 603123.8 | 9.85 | 113.4 | 11.3 | 126 | 9.5 | 90.0 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-126-1 | 11/17/2015 | 684294.5 | 603104.5 | 9.33 | 113.7 | 9.7 | 126 | 9.5 | 90.2 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-127-1 | 11/17/2015 | 684344.3 | 603150.7 | 10.16 | 118.9 | 11.6 | 126 | 9.5 | 94.4 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-129-1R | 11/17/2015 | 684276.4 | 603183.7 | 9.24 | 113.4 | 9.2 | 126 | 9.5 | 90.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-138-1R | 11/17/2015 | 684162.8 | 603230.4 | 7.91 | 114.8 | 10.3 | 126 | 9.5 | 91.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-108-1 | 11/19/2015 | 684536.2 | 902967.2 | 18.62 | 113.4 | 10.0 | 126 | 9.5 | 90.0 | 90 | 5 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | HC-109-1 | 11/19/2015 | 684492.9 | 602930.4 | 18.27 | 127.2 | 10.0 | 126 | 9.5 | 101.0 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-110-1 | 11/19/2015 | 684449.3 | 602900.5 | 14.40 | 115.7 | 10.0 | 126 | 9.5 | 91.8 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-111-1 | 11/19/2015 | 684475.6 | 602955.2 | 16.38 | 118.6 | 11.3 | 126 | 9.5 | 94.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-112-1 | 11/19/2015 | 684507.3 | 602998.5 | 16.87 | 119.2 | 9.9 | 126 | 9.5 | 94.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-113-1 | 11/19/2015 | 684452.2 | 602978.3 | 14.98 | 121.1 | 12.1 | 126 | 9.5 | 96.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-114-1 | 11/19/2015 | 684397.7 | 602956.1 | 12.85 | 121.5 | 10.7 | 126 | 9.5 | 96.4 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-115-1 | 11/19/2015 | 684428.1 | 603001.7 | 13.53 | 125.5 | 9.9 | 126 | 9.5 | 99.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-116-1 | 11/19/2015 | 684461.4 | 603048.2 | 14.24 | 115.4 | 9.9 | 126 | 9.5 | 91.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-117-1 | 11/19/2015 | 684402.1 | 603019.3 | 12.08 | 121.6 | 10.5 | 126 | 9.5 | 96.5 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | SF-12-1 | 11/19/2015 | 684485.9 | 602888.7 | 15.10 | 129.8 | 3.5 | 133 | 8.6 | 97.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-13-1 | 11/19/2015 | 684515.4 | 602913.9 | 15.90 | 129.9 | 4.3 | 133 | 8.6 | 97.7 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-14-1 | 11/19/2015 | 684548.8 | 602937.5 | 16.40 | 125.4 | 3.5 | 133 | 8.6 | 94.3 | 95 | 5 | Structural Fill -Liberty | SF-14-1R (Page 3) | V5N |
| 1 | SF-14-1R | 11/19/2015 | 684548.8 | 602937.5 | 16.40 | 127.3 | 3.5 | 133 | 8.6 | 95.7 | 95 | 5 | Structural Fill -Liberty | Re-roll/re-test; D Street-shallow | V5N |
| 1 | SF-19-1 | 11/19/2015 | 684505.8 | 602882.5 | 8.54 | 129.3 | 3.3 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-19-2 | 11/19/2015 | 684507.6 | 602881.4 | 9.70 | 126.4 | 4.4 | 133 | 8.6 | 95.0 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 3 | SF-19-3 | 11/19/2015 | 684507.5 | 602880.7 | 10.66 | 131.5 | 3.7 | 133 | 8.6 | 98.9 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 4 | SF-19-4 | 11/19/2015 | 684508.0 | 602880.1 | 11.49 | 131.0 | 4.7 | 133 | 8.6 | 98.5 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | SF-20-1 | 11/19/2015 | 684546.3 | 602907.6 | 8.77 | 129.3 | 4.3 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-20-2 | 11/19/2015 | 684545.4 | 602907.4 | 9.83 | 129.9 | 3.2 | 133 | 8.6 | 97.7 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 3 | SF-20-3 | 11/19/2015 | 684547.9 | 602908.6 | 10.90 | 130.1 | 3.5 | 133 | 8.6 | 97.8 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 4 | SF-20-4 | 11/19/2015 | 684548.3 | 602910.0 | 11.78 | 129.3 | 3.5 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | CS-100-1 | 11/24/2015 | 684631.4 | 602847.9 | 21.61 | 115.7 | 8.1 | 117 | 8.6 | 98.9 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-101-1 | 11/24/2015 | 684579.4 | 602829.3 | 21.00 | 122.2 | 5.3 | 117 | 8.6 | 104.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-103-1 | 11/24/2015 | 684559.4 | 602849.9 | 20.50 | 117.0 | 4.5 | 117 | 8.6 | 100.0 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-104-1 | 11/24/2015 | 684591.9 | 602894.4 | 20.26 | 118.5 | 6.3 | 117 | 8.6 | 101.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-105-1 | 11/24/2015 | 684549.1 | 602875.2 | 19.46 | 116.3 | 8.1 | 117 | 8.6 | 99.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-93-1 | 11/24/2015 | 684673.4 | 602728.7 | 17.07 | 115.0 | 9.4 | 117 | 8.6 | 98.3 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-95-1 | 11/24/2015 | 684652.5 | 602744.8 | 17.71 | 126.5 | 5.5 | 117 | 8.6 | 108.1 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-96-1 | 11/24/2015 | 684681.1 | 602793.4 | 18.36 | 119.7 | 6.8 | 117 | 8.6 | 102.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-97-1 | 11/24/2015 | 684634.5 | 602782.1 | 18.43 | 115.4 | 6.5 | 117 | 8.6 | 98.6 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-98-1 | 11/24/2015 | 684578.8 | 602757.8 | 18.44 | 117.4 | 6.3 | 117 | 8.6 | 100.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-99-1 | 11/24/2015 | 684610.9 | 602806.5 | 18.70 | 118.6 | 6.8 | 117 | 8.6 | 101.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 5 | SF-19-5 | 11/24/2015 | 684507.1 | 602879.1 | 13.03 | 133.2 | 5.6 | 133 | 8.6 | 100.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 6 | SF-19-6 | 11/24/2015 | 684506.8 | 602882.9 | 14.10 | 131.8 | 3.7 | 133 | 8.6 | 99.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 7 | SF-19-7 | 11/24/2015 | 684510.4 | 602881.3 | 15.06 | 130.9 | 4.2 | 133 | 8.6 | 98.4 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 5 | SF-20-5 | 11/24/2015 | 684546.9 | 602907.7 | 12.52 | 126.8 | 6.7 | 133 | 8.6 | 95.3 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 6 | SF-20-6 | 11/24/2015 | 684545.9 | 602910.3 | 13.50 | 133.1 | 4.7 | 133 | 8.6 | 100.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 7 | SF-20-7 | 11/24/2015 | 684540.5 | 602910.5 | 14.48 | 129.1 | 4.7 | 133 | 8.6 | 97.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | CS-102-1 | 12/8/2015 | 684522.1 | 602789.6 | 9.92 | 119.0 | 9.9 | 117 | 8.6 | 101.7 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-86-1 | 12/8/2015 | 684691.4 | 602613.8 | 6.27 | 120.7 | 8.5 | 117 | 8.6 | 103.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-87-1 | 12/8/2015 | 684741.0 | 602650.3 | 9.32 | 120.8 | 8.7 | 117 | 8.6 | 103.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-88-1 | 12/8/2015 | 684774.1 | 602700.3 | 8.44 | 122.0 | 9.4 | 117 | 8.6 | 104.3 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-89-1 | 12/8/2015 | 684713.8 | 602685.9 | 19.10 | 113.6 | 5.5 | 117 | 8.6 | 97.1 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-90-1 | 12/8/2015 | 684663.9 | 602654.3 | 15.96 | 115.2 | 6.4 | 117 | 8.6 | 98.5 | 90 | 7 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-91-1 | 12/8/2015 | 684668.9 | 602109.2 | 19.40 | 113.2 | 8.2 | 117 | 8.6 | 96.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-92-1 | 12/8/2015 | 684729.2 | 602749.3 | 16.89 | 117.9 | 7.2 | 117 | 8.6 | 100.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-94-1 | 12/8/2015 | 684610.2 | 602684.0 | 7.41 | 116.3 | 9.6 | 117 | 8.6 | 99.4 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | HC-100-1 | 12/8/2015 | 684624.6 | 602844.3 | 22.22 | 116.6 | 10.6 | 126 | 9.5 | 92.5 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-101-1 | 12/8/2015 | 684579.3 | 602829.2 | 21.65 | 128.5 | 9.0 | 126 | 9.5 | 102.0 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-102-1 | 12/8/2015 | 684517.4 | 602793.0 | 10.54 | 115.0 | 11.3 | 126 | 9.5 | 91.3 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-103-1 | 12/8/2015 | 684558.5 | 602852.7 | 20.94 | 121.1 | 10.2 | 126 | 9.5 | 96.1 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-104-1 | 12/8/2015 | 684589.0 | 602899.7 | 20.69 | 119.1 | 11.1 | 126 | 9.5 | 94.5 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-105-1 | 12/8/2015 | 684547.5 | 602874.7 | 20.00 | 114.1 | 12.6 | 126 | 9.5 | 90.6 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-106-1 | 12/8/2015 | 684488.5 | 602824.5 | 11.23 | 117.5 | 10.4 | 126 | 9.5 | 93.3 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-97-1 | 12/8/2015 | 684634.5 | 602785.1 | 19.13 | 113.4 | 10.4 | 126 | 9.5 | 90.0 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-98-1 | 12/8/2015 | 684580.8 | 602761.3 | 19.04 | 114.9 | 10.3 | 126 | 9.5 | 91.2 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-99-1 | 12/8/2015 | 684613.8 | 602809.7 | 19.33 | 115.5 | 9.6 | 126 | 9.5 | 91.7 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | SF-10-1 | 12/8/2015 | 684712.0 | 602632.9 | 8.47 | 146.3 | 3.0 | 133 | 8.6 | 110.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 1 | SF-11-1 | 12/8/2015 | 684764.1 | 602680.4 | 9.70 | 138.2 | 4.8 | 133 | 8.6 | 103.9 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 2 | SF-12-2 | 12/8/2015 | 684486.5 | 602887.8 | 16.20 | 132.2 | 7.3 | 133 | 8.6 | 99.4 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-12-3 | 12/8/2015 | 684483.4 | 602896.1 | 17.66 | 129.1 | 8.2 | 133 | 8.6 | 97.1 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 2 | SF-13-2 | 12/8/2015 | 684519.0 | 602908.4 | 17.00 | 127.7 | 6.0 | 133 | 8.6 | 96.0 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-13-3 | 12/8/2015 | 684517.8 | 602915.5 | 18.34 | 130.7 | 6.3 | 133 | 8.6 | 98.3 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 2 | SF-14-2 | 12/8/2015 | 684545.3 | 602935.8 | 17.44 | 127.2 | 6.6 | 133 | 8.6 | 95.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-14-3 | 12/8/2015 | 684538.7 | 602936.2 | 18.35 | 127.2 | 7.0 | 133 | 8.6 | 95.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 8 | SF-19-8 | 12/8/2015 | 684511.3 | 602878.7 | 16.16 | 133.8 | 6.3 | 133 | 8.6 | 100.6 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 9 | SF-19-9 | 12/8/2015 | 684512.4 | 602884.5 | 17.40 | 120.8 | 7.0 | 133 | 8.6 | 90.8 | 95 | 5 | Structural Fill -Liberty | SF-19-9R (Page 4) | V5N |
| 9 | SF-19-9R | 12/8/2015 | 684512.0 | 602884.0 | 17.40 | 130.2 | 7.4 | 133 | 8.6 | 97.9 | 95 | 5 | Structural Fill -Liberty | Re-test lift after rolling | V5N |
| 8 | SF-20-8 | 12/8/2015 | 684559.3 | 602906.9 | 15.66 | 127.8 | 7.6 | 133 | 8.6 | 96.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 9 | SF-20-9 | 12/8/2015 | 684559.5 | 602915.7 | 17.27 | 126.7 | 7.4 | 133 | 8.6 | 95.3 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-10-2 | 12/10/2015 | 684716.8 | 602639.7 | 9.79 | 132.4 | 6.0 | 133 | 8.6 | 99.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-10-3 | 12/10/2015 | 684718.1 | 602641.1 | 10.74 | 129.7 | 3.0 | 133 | 8.6 | 97.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 2 | SF-11-2 | 12/10/2015 | 684763.0 | 602675.2 | 10.41 | 130.5 | 6.0 | 133 | 8.6 | 98.1 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-11-3 | 12/10/2015 | 684762.5 | 602675.9 | 11.33 | 125.7 | 3.0 | 133 | 8.6 | 94.5 | 95 | 7 | Structural Fill -Liberty | SF-11-3R (Page 4) | V5N |
| 4 | SF-10-4 | 12/14/2015 | 684719.5 | 602644.8 | 11.71 | 126.4 | 1.9 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 5 | SF-10-5 | 12/14/2015 | 684713.2 | 602644.6 | 12.77 | 126.4 | 2.5 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 6 | SF-10-6 | 12/14/2015 | 684716.5 | 602649.2 | 13.99 | 126.5 | 3.4 | 133 | 8.6 | 95.1 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-11-3R | 12/14/2015 | 684762.0 | 602675.0 | 11.33 | 126.4 | 1.5 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | Re-test lift after rolling | V5N |
| 4 | SF-11-4 | 12/14/2015 | 684761.3 | 602678.2 | 12.57 | 127.9 | 2.1 | 133 | 8.6 | 96.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 5 | SF-11-5 | 12/14/2015 | 684770.8 | 602673.9 | 13.60 | 126.6 | 3.2 | 133 | 8.6 | 95.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 6 | SF-11-6 | 12/14/2015 | 684762.3 | 602666.3 | 14.54 | 126.6 | 3.9 | 133 | 8.6 | 95.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 7 | SF-10-7 | 12/15/2015 | 684716.8 | 602641.2 | 15.03 | 131.0 | 5.3 | 133 | 8.6 | 98.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 8 | SF-10-8 | 12/15/2015 | 684716.0 | 602649.9 | 16.07 | 126.7 | 3.3 | 133 | 8.6 | 95.3 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 9 | SF-10-9 | 12/15/2015 | 684719.3 | 602639.9 | 16.86 | 128.9 | 5.7 | 133 | 8.6 | 96.9 | 95 | 7 | Structural Fill -Liberty | C Street Corridor-final el | V5N |
| 7 | SF-11-7 | 12/15/2015 | 684765.3 | 602680.3 | 15.76 | 126.3 | 3.4 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 8 | SF-11-8 | 12/15/2015 | 684762.4 | 602675.2 | 16.71 | 128.1 | 5.7 | 133 | 8.6 | 96.3 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 9 | SF-11-9 | 12/15/2015 | 684752.5 | 602686.1 | 16.86 | 130.0 | 7.4 | 133 | 8.6 | 97.7 | 95 | 7 | Structural Fill -Liberty | C Street Corridor-final el | V5N |
| 5 | SF-10-5R | 3/6/2016 | 684712.8 | 602643.3 | 13.55 | 108.2 | 2.5 | 112.2 | 9.7 | 96.4 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | SF-10-4R | 3/16/2016 | 684708.7 | 602643.3 | 12.47 | 111.6 | 2.8 | 112.2 | 9.7 | 99.5 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 4 | SF-11-4R | 3/16/2016 | 684760.2 | 602681.4 | 12.15 | 112.0 | 2.5 | 112.2 | 9.7 | 99.8 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 5 | SF-11-5R | 3/16/2016 | 684748.8 | 602679.9 | 13.15 | 108.0 | 2.4 | 112.2 | 9.7 | 96.3 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 6 | SF-10-6R | 3/17/2016 | 684707.5 | 602634.2 | 15.23 | 109.5 | 2.3 | 112.2 | 9.7 | 97.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 7 | SF-10-7R | 3/17/2016 | 684716.6 | 602642.7 | 16.50 | 114.0 | 3.2 | 112.2 | 9.7 | 101.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 6 | SF-11-6R | 3/17/2016 | 684750.5 | 602661.5 | 15.23 | 107.3 | 2.2 | 112.2 | 9.7 | 95.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 7 | SF-11-7R | 3/17/2016 | 684750.3 | 602672.5 | 16.40 | 115.4 | 2.5 | 112.2 | 9.7 | 102.9 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 1 | CS-12-1R | 4/14/2016 | 685504.9 | 601673 | 17.30 | 121.5 | 8.7 | 117 | 8.6 | 103.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-16-1R | 4/14/2016 | 685457.6 | 601721.7 | 16.30 | 117.9 | 7.8 | 117 | 8.6 | 100.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-17-1R | 4/14/2016 | 685434.6 | 601718.5 | 14.70 | 122.5 | 8.0 | 117 | 8.6 | 104.7 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-18-1R | 4/14/2016 | 685395.1 | 601714.8 | 17.20 | 120.3 | 5.3 | 117 | 8.6 | 102.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-19-1 | 4/14/2016 | 685414.3 | 601758.3 | 17.20 | 120.6 | 5.6 | 117 | 8.6 | 103.1 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-20-1 | 4/14/2016 | 685421.8 | 601782.3 | 17.30 | 122.8 | 7.0 | 117 | 8.6 | 105.0 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-21-1 | 4/14/2016 | 685388.8 | 601769.3 | 17.40 | 120.0 | 6.8 | 117 | 8.6 | 102.6 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-22-1 | 4/14/2016 | 685341.2 | 601751.2 | 17.60 | 119.0 | 8.0 | 117 | 8.6 | 101.7 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-23-1 | 4/14/2016 | 685366.5 | 601794.2 | 18.10 | 121.4 | 4.7 | 117 | 8.6 | 103.8 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-24-1 | 4/14/2016 | 685390.4 | 601829.7 | 18.20 | 114.8 | 6.0 | 117 | 8.6 | 98.1 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-25-1 | 4/14/2016 | 685348.8 | 601819.2 | 19.00 | 121.5 | 7.7 | 117 | 8.6 | 103.8 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-26-1 | 4/14/2016 | 685305.2 | 601804.9 | 19.30 | 117.9 | 5.4 | 117 | 8.6 | 100.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-27-1 | 4/14/2016 | 685325.1 | 601846.4 | 16.90 | 120.3 | 7.0 | 117 | 8.6 | 102.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-28-1 | 4/15/2016 | 685354.8 | 601891.6 | 16.00 | 125.7 | 6.8 | 117 | 8.6 | 107.4 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-29-1 | 4/15/2016 | 685310.4 | 601883.3 | 19.60 | 120.1 | 7.3 | 117 | 8.6 | 102.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-30-1 | 4/15/2016 | 685259.5 | 601859.9 | 17.30 | 120.9 | 6.7 | 117 | 8.6 | 103.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-31-1 | 4/15/2016 | 685289.6 | 601902.5 | 19.60 | 125.3 | 7.4 | 117 | 8.6 | 107.1 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | HC-08-1 | 4/15/2016 | 685535.1 | 601617.9 | 17.00 | 115.8 | 9.8 | 126 | 9.8 | 91.9 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-09-1 | 4/15/2016 | 685492.6 | 601603.4 | 17.10 | 116.4 | 9.7 | 126 | 9.5 | 92.4 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-12-1 | 4/15/2016 | 685500.6 | 601671.6 | 17.90 | 115.1 | 9.4 | 126 | 9.5 | 91.3 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-16-1 | 4/15/2016 | 685457.5 | 601729.1 | 16.80 | 120.2 | 9.4 | 126 | 9.5 | 95.4 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-04-01 | 4/18/2016 | 685309.3 | 601839.5 | 14.50 | 107.5 | 1.7 | 112.2 | 9.7 | 95.8 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-04-02 | 4/18/2016 | 685311.3 | 601840.4 | 16.00 | 110.5 | 1.6 | 112.2 | 9.7 | 98.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 3 | SF-04-03 | 4/18/2016 | 685289.9 | 601837.7 | 17.60 | 108.1 | 1.8 | 112.2 | 9.7 | 96.3 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | SF-05-01 | 4/18/2016 | 685325.3 | 601867.3 | 18.00 | 114.9 | 2.0 | 112.2 | 9.7 | 102.4 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | SF-06-01 | 4/18/2016 | 685357.4 | 601889.1 | 17.50 | 111.6 | 2.0 | 112.2 | 9.7 | 99.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 4 | SF-04-04 | 4/20/2016 | 685294.4 | 601842.4 | 19.10 | 106.6 | 2.0 | 112.2 | 9.7 | 95.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-05-02 | 4/20/2016 | 685320.8 | 601866.4 | 19.70 | 107.7 | 2.0 | 112.2 | 9.7 | 96.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-06-02 | 4/20/2016 | 685348.9 | 601890.6 | 19.50 | 106.6 | 2.0 | 112.2 | 9.7 | 95.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | HC-17-01 | 4/20/2016 | 685432.8 | 601721.6 | 15.20 | 122.4 | 9.5 | 126 | 9.5 | 97.1 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-18-01 | 4/20/2016 | 685393.5 | 601712.7 | 17.70 | 117.2 | 10.2 | 126 | 9.5 | 93.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-19-01 | 4/20/2016 | 685419.8 | 601751.3 | 15.30 | 117.4 | 9.5 | 126 | 9.5 | 93.2 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-20-01 | 4/20/2016 | 685423.4 | 601782.8 | 17.80 | 125.8 | 8.8 | 126 | 9.5 | 99.8 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-21-01 | 4/20/2016 | 685383.0 | 601770.6 | 18.20 | 127.3 | 8.9 | 126 | 9.5 | 101.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-22-01 | 4/20/2016 | 685340.2 | 601758.3 | 18.30 | 118.4 | 8.6 | 126 | 9.5 | 94.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-23-01 | 4/20/2016 | 685366.4 | 601793.6 | 18.50 | 122.2 | 8.8 | 126 | 9.5 | 97.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-24-01 | 4/20/2016 | 685392.1 | 601831.1 | 18.90 | 119.7 | 8.4 | 126 | 9.5 | 95.0 | 90 | 8 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | HC-25-01 | 4/20/2016 | 685351.7 | 601822.1 | 19.40 | 129.8 | 9.2 | 126 | 9.5 | 103.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-26-01 | 4/20/2016 | 685303.8 | 601806.5 | 19.90 | 113.4 | 8.1 | 126 | 9.5 | 90.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-27-01 | 4/20/2016 | 685361.7 | 601845.0 | 19.70 | 121.0 | 9.0 | 126 | 9.5 | 96.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | CS-01-01 | 4/20/2016 | 685552.1 | 601486.2 | 16.40 | 111.2 | 9.0 | 117 | 8.6 | 95.1 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-02-01 | 4/20/2016 | 685571.4 | 601519.1 | 18.50 | 120.5 | 9.1 | 117 | 8.6 | 103.0 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-47-01 | 4/22/2016 | 685133.2 | 602127.9 | 6.50 | 117.0 | 8.6 | 117 | 8.6 | 100.0 | 90 | 13 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | CS-48-01 | 4/22/2016 | 685161.9 | 602170.3 | 7.10 | 115.8 | 8.4 | 117 | 8.6 | 99.0 | 90 | 14 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | CS-49-01 | 4/22/2016 | 685114.8 | 602135.6 | 6.40 | 111.2 | 8.4 | 117 | 8.6 | 95.0 | 90 | 14 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | HC-05-01 | 4/22/2016 | 685511.7 | 601549.5 | 18.30 | 113.4 | 8.2 | 126 | 9.5 | 90.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-06-01 | 4/22/2016 | 685479.0 | 601533.4 | 15.00 | 119.7 | 8.0 | 126 | 9.5 | 95.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-07-01 | 4/22/2016 | 685514.3 | 601578.6 | 18.30 | 113.4 | 8.2 | 126 | 9.5 | 90.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-01-01 | 4/22/2016 | 685510.3 | 601523.6 | 16.60 | 107.7 | 8.0 | 112.2 | 9.7 | 96.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-02-01 | 4/22/2016 | 685547.6 | 601542.6 | 18.30 | 102.0 | 8.1 | 112.2 | 9.7 | 90.9 | 95 | 10 | Structural Fill - Tilcon | SF-02-01R (Page 6) | V5N |
| 1 | SF-03-01 | 4/22/2016 | 685585.2 | 601572.6 | 18.20 | 106.6 | 8.2 | 112.2 | 9.7 | 95.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-02-01R | 4/22/2016 | 685547.6 | 601542.6 | 18.30 | 106.6 | 8.1 | 112.2 | 9.7 | 95.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; reroll and retes | V5N |
| 1 | HC-04-01 | 4/26/2016 | 685586.2 | 601559.0 | 19.40 | 117.5 | 9.1 | 126 | 9.5 | 93.3 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-02-01 | 4/26/2016 | 685575.9 | 601519.7 | 19.30 | 114.2 | 10.6 | 126 | 9.5 | 90.6 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-03-01 | 4/26/2016 | 685531.2 | 601505.9 | 17.90 | 124.3 | 8.1 | 126 | 9.5 | 98.7 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-01-01 | 4/26/2016 | 685554.0 | 601483.2 | 16.80 | 114.7 | 9.6 | 126 | 9.5 | 91.0 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 2 | SF-01-02 | 4/26/2016 | 685512.5 | 601525.3 | 17.50 | 118.2 | 7.0 | 112.2 | 9.7 | 105.3 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 2 | SF-02-02 | 4/26/2016 | 685553.1 | 601555.1 | 18.90 | 114.9 | 4.7 | 112.2 | 9.7 | 102.4 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 2 | SF-03-02 | 4/26/2016 | 685577.3 | 601575.2 | 19.30 | 120.3 | 4.9 | 112.2 | 9.7 | 107.2 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | CS-32-01 | 4/26/2016 | 685305.2 | 601932.9 | 19.50 | 117.6 | 7.2 | 117 | 8.6 | 100.5 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-33-01 | 4/26/2016 | 685271.2 | 601934.8 | 19.60 | 117.0 | 10.6 | 117 | 8.6 | 100.0 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-34-01 | 4/26/2016 | 685225.8 | 601921.4 | 19.80 | 117.7 | 9.8 | 117 | 8.6 | 100.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-35-01 | 4/26/2016 | 685251.7 | 601967.3 | 19.30 | 117.6 | 10.5 | 117 | 8.6 | 100.5 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-36-01 | 4/26/2016 | 685269.0 | 601997.3 | 18.80 | 114.6 | 9.7 | 117 | 8.6 | 97.9 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | SF-07-01 | 4/26/2016 | 685096.6 | 606106.8 | 7.10 | 130.5 | 6.2 | 112.2 | 9.7 | 116.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | SF-08-01 | 4/26/2016 | 685131.5 | 602130.1 | 7.40 | 129.9 | 5.8 | 112.2 | 9.7 | 115.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | SF-09-01 | 4/26/2016 | 685163.1 | 602153.3 | 7.60 | 127.8 | 5.7 | 112.2 | 9.7 | 113.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-07-02 | 4/26/2016 | 685098.7 | 602108.8 | 7.90 | 124.6 | 4.8 | 112.2 | 9.7 | 111.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-08-02 | 4/26/2016 | 685134.0 | 602134.2 | 8.20 | 116.8 | 3.7 | 112.2 | 9.7 | 104.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-09-02 | 4/26/2016 | 685173.6 | 602160.2 | 8.60 | 128.1 | 5.5 | 112.2 | 9.7 | 114.2 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-07-03 | 4/27/2016 | 685096.6 | 602106.8 | 9.40 | 113.2 | 2.8 | 112.2 | 9.7 | 100.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-08-03 | 4/27/2016 | 685131.5 | 602133.6 | 9.60 | 112.5 | 3.2 | 112.2 | 9.7 | 100.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-09-03 | 4/27/2016 | 685168.9 | 602159.4 | 10.00 | 116.2 | 2.9 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-07-04 | 4/28/2016 | 685089.9 | 602105.5 | 10.40 | 107.2 | 4.7 | 112.2 | 9.7 | 95.5 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-08-04 | 4/28/2016 | 685130.3 | 602135.1 | 10.50 | 108.4 | 2.6 | 112.2 | 9.7 | 96.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-09-04 | 4/28/2016 | 685158.3 | 602159.3 | 10.80 | 110.9 | 3.7 | 112.2 | 9.7 | 98.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-07-05 | 4/28/2016 | 658087.4 | 602109.5 | 11.30 | 106.9 | 4.6 | 112.2 | 9.7 | 95.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-08-05 | 4/28/2016 | 685126.7 | 602137.8 | 11.60 | 115.8 | 3.2 | 112.2 | 9.7 | 103.2 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-09-05 | 4/28/2016 | 685164.5 | 602163.5 | 11.50 | 112.6 | 3.3 | 112.2 | 9.7 | 100.4 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | CS-37-01 | 4/28/2016 | 685234.1 | 601983.7 | 18.80 | 121.7 | 8.8 | 117 | 8.6 | 104.0 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-38-01 | 4/28/2016 | 685185.5 | 601970.6 | 18.70 | 116.6 | 6.7 | 117 | 8.6 | 99.7 | 90 | 12 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-39-01 | 4/28/2016 | 685213.8 | 602102.2 | 18.20 | 122.0 | 8.3 | 117 | 8.6 | 104.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-40-01 | 4/28/2016 | 685227.8 | 602065.5 | 17.70 | 119.1 | 8.7 | 117 | 8.6 | 101.8 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-41-01 | 4/28/2016 | 685193.2 | 602041.5 | 17.40 | 120.0 | 10.9 | 117 | 8.6 | 102.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-42-01 | 4/28/2016 | 685152.5 | 602025.7 | 17.30 | 119.6 | 8.9 | 117 | 8.6 | 102.2 | 90 | 13 | GDL Cover Soil | | V5N |
| 6 | SF-07-06 | 4/29/2016 | 658082.9 | 602108.5 | 12.26 | 114.3 | 2.7 | 112.2 | 9.7 | 101.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 6 | SF-08-06 | 4/29/2016 | 685136.5 | 602126.5 | 12.47 | 110.8 | 2.4 | 112.2 | 9.7 | 98.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 6 | SF-09-06 | 4/29/2016 | 685146.5 | 602166.6 | 12.35 | 113.3 | 2.4 | 112.2 | 9.7 | 101.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | HC-28-01 | 4/29/2016 | 685334.6 | 601903.6 | 19.80 | 119.8 | 9.5 | 126 | 9.5 | 95.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-29-01 | 4/29/2016 | 685294.7 | 601866.8 | 20.20 | 128.7 | 8.4 | 126 | 9.5 | 102.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-30-01 | 4/29/2016 | 685258.9 | 601854.0 | 17.80 | 114.7 | 10.7 | 126 | 9.5 | 91.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-31-01 | 4/29/2016 | 685286.1 | 601905.7 | 20.20 | 124.7 | 9.2 | 126 | 9.5 | 99.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-32-01 | 4/29/2016 | 685294.9 | 601951.8 | 19.90 | 124.5 | 8.7 | 126 | 9.5 | 98.8 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-33-01 | 4/29/2016 | 685267.6 | 601932.2 | 20.10 | 114.7 | 10.2 | 126 | 9.5 | 91.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-35-01 | 4/29/2016 | 685251.4 | 601960.8 | 19.80 | 113.7 | 10.5 | 126 | 9.5 | 90.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 7 | SF-07-07 | 5/2/2016 | 685098.9 | 602107.7 | 13.20 | 113.7 | 2.2 | 112.2 | 9.7 | 101.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 7 | SF-08-07 | 5/2/2016 | 685131.4 | 602134.6 | 13.40 | 113.2 | 3.4 | 112.2 | 9.7 | 100.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 7 | SF-09-07 | 5/2/2016 | 685141.4 | 602154.3 | 13.20 | 113.0 | 2.1 | 112.2 | 9.7 | 100.7 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-07-08 | 5/2/2016 | 685090.8 | 602099.0 | 14.20 | 119.6 | 4.0 | 112.2 | 9.7 | 106.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-08-08 | 5/2/2016 | 685126.1 | 602130.8 | 14.50 | 116.2 | 2.6 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-09-08 | 5/2/2016 | 685060.5 | 602159.1 | 14.00 | 117.3 | 3.4 | 112.2 | 9.7 | 104.5 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | CS-43-01 | 5/2/2016 | 685178.7 | 602060.3 | 17.20 | 119.7 | 10.1 | 117 | 8.6 | 102.3 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-44-01 | 5/2/2016 | 685227.7 | 602065.5 | 17.70 | 115.8 | 7.3 | 117 | 8.6 | 99.0 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-45-01 | 5/2/2016 | 685152.4 | 602803.2 | 17.60 | 114.5 | 7.1 | 117 | 8.6 | 97.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-46-01 | 5/2/2016 | 685108.7 | 602067.4 | 15.00 | 109.9 | 7.8 | 117 | 8.6 | 93.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | HC-34-01 | 5/2/2016 | 685227.3 | 601914.0 | 20.50 | 117.5 | 10.3 | 126 | 9.5 | 93.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-36-01 | 5/2/2016 | 685269.4 | 601989.1 | 19.50 | 119.1 | 11.1 | 126 | 9.5 | 94.5 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-37-01 | 5/2/2016 | 685232.0 | 601988.5 | 19.30 | 115.0 | 9.8 | 126 | 9.5 | 91.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-38-01 | 5/2/2016 | 685181.9 | 601969.6 | 19.30 | 113.7 | 11.7 | 126 | 9.5 | 90.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-39-01 | 5/2/2016 | 685213.9 | 602004.5 | 18.70 | 116.0 | 8.9 | 126 | 9.5 | 92.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-40-01 | 5/2/2016 | 685226.0 | 602151.1 | 18.10 | 125.0 | 10.0 | 126 | 9.5 | 99.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-41-01 | 5/2/2016 | 685199.7 | 602037.5 | 18.00 | 120.1 | 10.4 | 126 | 9.5 | 95.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 9 | SF-07-09 | 5/5/2016 | 685008.1 | 602099.3 | 14.90 | 120.0 | 3.5 | 112.2 | 9.7 | 107.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 9 | SF-08-09 | 5/5/2016 | 685134.3 | 602127.7 | 15.00 | 123.4 | 3.2 | 112.2 | 9.7 | 110.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 9 | SF-09-09 | 5/5/2016 | 685169.3 | 602144.8 | 14.90 | 115.7 | 4.2 | 112.2 | 9.7 | 103.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-07-10 | 5/5/2016 | 685087.7 | 602155.6 | 16.50 | 120.4 | 4.4 | 112.2 | 9.7 | 107.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-08-10 | 5/5/2016 | 685117.3 | 602137.9 | 16.60 | 111.9 | 3.8 | 112.2 | 9.7 | 99.7 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-09-10 | 5/5/2016 | 685155.3 | 602167.4 | 16.30 | 107.8 | 3.1 | 112.2 | 9.7 | 96.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | HC-42-01 | 5/5/2016 | 685157.1 | 602028.8 | 17.80 | 117.3 | 11.6 | 126 | 9.5 | 93.1 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-43-01 | 5/5/2016 | 685169.9 | 602065.8 | 17.80 | 117.2 | 12.1 | 126 | 9.5 | 93.0 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-44-01 | 5/5/2016 | 685193.6 | 602102.8 | 18.00 | 124.0 | 11.7 | 126 | 9.5 | 98.4 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-45-01 | 5/5/2016 | 685166.2 | 602112.5 | 18.40 | 123.3 | 10.3 | 126 | 9.5 | 97.9 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-46-01 | 5/5/2016 | 685107.4 | 602064.3 | 15.40 | 125.5 | 11.6 | 126 | 9.5 | 99.6 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-47-01 | 5/5/2016 | 685140.2 | 602092.3 | 18.30 | 121.2 | 9.2 | 126 | 9.5 | 96.2 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | CS-50-01 | 5/11/2016 | 685060.3 | 602129.0 | 16.00 | 114.9 | 9.2 | 117 | 8.6 | 98.2 | 90 | 14 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-51-01 | 5/11/2016 | 685095.6 | 602173.6 | 18.80 | 115.3 | 9.2 | 117 | 8.6 | 98.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-52-01 | 5/11/2016 | 685118.1 | 602212.6 | 18.30 | 116.9 | 9.2 | 117 | 8.6 | 99.9 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-53-01 | 5/11/2016 | 685077.2 | 602198.8 | 18.80 | 115.3 | 9.8 | 117 | 8.6 | 98.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-54-01 | 5/11/2016 | 685018.9 | 602196.7 | 19.40 | 113.0 | 8.8 | 117 | 8.6 | 96.6 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-55-01 | 5/11/2016 | 685037.7 | 602225.0 | 16.90 | 112.7 | 13.2 | 117 | 8.6 | 96.3 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-57-01 | 5/11/2016 | 685029.4 | 602258.5 | 17.50 | 116.7 | 11.6 | 117 | 8.6 | 99.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-58-01 | 5/11/2016 | 684989.3 | 602236.4 | 20.10 | 117.6 | 9.4 | 117 | 8.6 | 100.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-59-01 | 5/11/2016 | 685005.7 | 602278.3 | 17.80 | 119.0 | 11.8 | 117 | 8.6 | 101.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-61-01 | 5/11/2016 | 684990.1 | 602311.3 | 18.30 | 112.5 | 14.7 | 117 | 8.6 | 96.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-62-01 | 5/11/2016 | 684954.1 | 602272.2 | 20.80 | 116.1 | 9.5 | 117 | 8.6 | 99.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-63-01 | 5/11/2016 | 684978.4 | 602338.7 | 18.70 | 110.8 | 6.8 | 117 | 8.6 | 94.7 | 90 | 15 | GDL Cover Soil | | V5N |
| 11 | SF-07-11 | 5/11/2016 | 685085.8 | 602102.0 | 17.60 | 108.4 | 2.1 | 112.2 | 9.7 | 96.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 11 | SF-08-11 | 5/11/2016 | 685120.0 | 602122.7 | 17.80 | 107.5 | 2.5 | 112.2 | 9.7 | 95.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 11 | SF-09-11 | 5/11/2016 | 685157.2 | 602150.4 | 17.70 | 109.8 | 2.6 | 112.2 | 9.7 | 97.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 3 | SF-01-03 | 5/11/2016 | 685512.3 | 601525.2 | 19.30 | 113.1 | 2.0 | 112.2 | 9.7 | 100.8 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 3 | SF-02-03 | 5/11/2016 | 685546.3 | 601552.4 | 19.40 | 116.2 | 2.4 | 112.2 | 9.7 | 103.6 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 3 | SF-03-03 | 5/11/2016 | 685585.6 | 601575.9 | 19.30 | 116.9 | 2.0 | 112.2 | 9.7 | 104.2 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 1 | HC-48-01 | 5/16/2016 | 685126.3 | 602180.8 | 19.30 | 114.6 | 14.9 | 126 | 9.5 | 91.0 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-49-01 | 5/16/2016 | 685093.4 | 602149.0 | 17.00 | 145.7 | 9.9 | 126 | 9.5 | 115.6 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-50-01 | 5/16/2016 | 685061.4 | 602128.9 | 16.50 | 119.8 | 13.2 | 126 | 9.5 | 95.1 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-51-01 | 5/16/2016 | 685096.6 | 602178.9 | 19.30 | 120.1 | 11.0 | 126 | 9.5 | 95.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-52-01 | 5/16/2016 | 685119.9 | 602212.3 | 18.80 | 114.5 | 11.6 | 126 | 9.5 | 90.9 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-53-01 | 5/16/2016 | 685054.2 | 602219.1 | 19.60 | 118.1 | 10.7 | 126 | 9.5 | 93.7 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-54-01 | 5/16/2016 | 685019.8 | 602191.5 | 19.80 | 114.2 | 12.4 | 126 | 9.5 | 90.6 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-55-01 | 5/16/2016 | 685054.2 | 602219.1 | 19.60 | 120.1 | 12.8 | 126 | 9.5 | 95.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-56-01 | 5/16/2016 | 685075.9 | 602263.9 | 19.80 | 116.8 | 12.7 | 126 | 9.5 | 92.7 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-57-01 | 5/16/2016 | 685032.7 | 602252.7 | 17.90 | 118.6 | 9.8 | 126 | 9.5 | 94.1 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-58-01 | 5/16/2016 | 684988.4 | 602235.8 | 20.60 | 114.7 | 11.1 | 126 | 9.5 | 91.0 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-59-01 | 5/16/2016 | 685010.1 | 602267.9 | 18.10 | 122.6 | 8.7 | 126 | 9.5 | 97.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | CS-56-01 | 5/16/2016 | 685025.1 | 602299.5 | 20.30 | 118.5 | 11.5 | 117 | 8.6 | 101.3 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-60-01 | 5/16/2016 | 685025.9 | 602329.2 | 18.00 | 113.1 | 11.9 | 117 | 8.6 | 96.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 5 | SF-04-05 | 5/16/2016 | 685352.5 | 601871.7 | 19.40 | 114.6 | 1.5 | 112.2 | 9.7 | 102.1 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 3 | SF-05-03 | 5/16/2016 | 685321.5 | 601855.6 | 19.70 | 117.7 | 1.8 | 112.2 | 9.7 | 104.9 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 3 | SF-06-03 | 5/16/2016 | 685289.7 | 601832.8 | 19.70 | 108.3 | 1.4 | 112.2 | 9.7 | 96.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 1 | CS-64-01 | 5/18/2016 | 684999.1 | 602372.6 | 18.70 | 115.6 | 7.7 | 117 | 8.6 | 98.8 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-65-01 | 5/18/2016 | 684995.4 | 602360.5 | 18.90 | 116.5 | 11.3 | 117 | 8.6 | 99.6 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-66-01 | 5/18/2016 | 684907.9 | 602343.4 | 19.00 | 120.8 | 9.0 | 117 | 8.6 | 103.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-67-01 | 5/18/2016 | 684935.3 | 602386.4 | 18.90 | 115.3 | 11.1 | 117 | 8.6 | 98.5 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-68-01 | 5/18/2016 | 684960.5 | 602427.3 | 18.80 | 112.6 | 9.6 | 117 | 8.6 | 96.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-69-01 | 5/18/2016 | 684918.4 | 602414.4 | 18.70 | 114.0 | 11.0 | 117 | 8.6 | 97.4 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-71-01 | 5/18/2016 | 684888.7 | 602434.3 | 18.00 | 116.7 | 12.4 | 117 | 8.6 | 99.7 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-72-01 | 5/18/2016 | 684917.8 | 602480.4 | 18.00 | 117.5 | 8.8 | 117 | 8.6 | 100.4 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | HC-49-01R | 5/18/2016 | 685093.4 | 602149.0 | 17.00 | 117.5 | 9.9 | 126 | 9.5 | 93.3 | 90 | 14 | Horizon C | Back Scatter; re-run test | V5N |
| 1 | CS-70-01 | 5/20/2016 | 684860.3 | 602329.6 | 18.20 | 111.8 | 7.6 | 117 | 8.6 | 95.6 | 90 | 16 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-73-01 | 5/20/2016 | 684869.9 | 602462.4 | 17.40 | 115.6 | 11.7 | 117 | 8.6 | 98.8 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-74-01 | 5/20/2016 | 684821.2 | 602444.5 | 16.60 | 116.4 | 12.6 | 117 | 8.6 | 99.5 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-75-01 | 5/20/2016 | 684852.3 | 602488.7 | 16.60 | 114.2 | 10.0 | 117 | 8.6 | 97.6 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | HC-60-01 | 5/20/2016 | 685036.3 | 602315.7 | 18.50 | 117.4 | 9.5 | 126 | 9.5 | 93.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-61-01 | 5/20/2016 | 685958.1 | 602318.7 | 19.30 | 123.7 | 11.9 | 126 | 9.5 | 98.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-62-01 | 5/20/2016 | 684943.1 | 602291.6 | 21.70 | 116.8 | 10.2 | 126 | 9.5 | 92.7 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-63-01 | 5/20/2016 | 684974.6 | 602334.4 | 19.20 | 116.1 | 13.3 | 126 | 9.5 | 92.1 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-64-01 | 5/20/2016 | 685000.9 | 602370.5 | 19.20 | 116.7 | 9.4 | 126 | 9.5 | 92.6 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-65-01 | 5/20/2016 | 684954.1 | 602361.6 | 19.50 | 120.6 | 13.2 | 126 | 9.5 | 95.7 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-66-01 | 5/20/2016 | 684906.2 | 602342.6 | 19.50 | 114.5 | 11.8 | 126 | 9.5 | 90.9 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-68-01 | 5/20/2016 | 684955.8 | 602413.4 | 19.40 | 120.4 | 12.5 | 126 | 9.5 | 95.6 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-69-01 | 5/20/2016 | 684906.3 | 602419.1 | 19.00 | 123.7 | 10.1 | 126 | 9.5 | 98.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-70-01 | 5/20/2016 | 684858.7 | 302396.2 | 18.70 | 124.3 | 11.1 | 126 | 9.5 | 98.7 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-71-01 | 5/20/2016 | 684882.1 | 602433.1 | 18.50 | 114.6 | 13.6 | 126 | 9.5 | 91.0 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-72-01 | 5/20/2016 | 684913.9 | 602473.4 | 18.60 | 124.6 | 11.3 | 126 | 9.5 | 98.9 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-73-01 | 5/20/2016 | 684870.2 | 602464.3 | 18.00 | 122.3 | 12.4 | 126 | 9.5 | 97.1 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-74-01 | 5/20/2016 | 684819.9 | 602423.5 | 16.90 | 124.6 | 11.3 | 126 | 9.5 | 98.9 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | CS-76-01 | 5/27/2016 | 684877.8 | 602531.3 | 19.20 | 107.5 | 6.6 | 117 | 8.6 | 91.9 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-77-01 | 5/27/2016 | 684831.7 | 602514.5 | 15.90 | 111.5 | 9.1 | 117 | 8.6 | 95.3 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-78-01 | 5/27/2016 | 684774.7 | 602493.1 | 14.40 | 111.0 | 8.8 | 117 | 8.6 | 94.9 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-79-01 | 5/27/2016 | 684809.3 | 602541.2 | 17.60 | 111.8 | 6.4 | 117 | 8.6 | 95.6 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-80-01 | 5/27/2016 | 684830.6 | 602582.9 | 15.20 | 113.6 | 9.0 | 117 | 8.6 | 97.1 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-81-01 | 5/27/2016 | 684786.1 | 602567.2 | 14.90 | 113.7 | 8.1 | 117 | 8.6 | 97.2 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-82-01 | 5/27/2016 | 684747.7 | 602551.4 | 14.30 | 108.8 | 8.0 | 117 | 8.6 | 93.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-83-01 | 5/27/2016 | 684775.8 | 602598.9 | 15.40 | 108.9 | 8.7 | 117 | 8.6 | 93.1 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-84-01 | 5/27/2016 | 684806.4 | 602648.6 | 15.30 | 107.6 | 10.1 | 117 | 8.6 | 92.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-85-01 | 5/27/2016 | 684758.7 | 602624.2 | 18.20 | 111.2 | 7.6 | 117 | 8.6 | 95.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | HC-67-01 | 5/27/2016 | 684934.5 | 602386.8 | 19.50 | 122.9 | 10.4 | 126 | 9.5 | 97.5 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-75-01 | 5/27/2016 | 684852.9 | 602485.9 | 17.20 | 114.0 | 7.0 | 126 | 9.5 | 90.5 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-76-01 | 6/2/2016 | 684876.3 | 602531.1 | 19.70 | 119.3 | 9.3 | 126 | 9.5 | 94.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-77-01 | 6/2/2016 | 684830.6 | 602514.8 | 16.40 | 122.3 | 8.4 | 126 | 9.5 | 97.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-78-01 | 6/2/2016 | 684776.0 | 602494.2 | 15.10 | 114.4 | 8.4 | 126 | 9.5 | 90.8 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-79-01 | 6/2/2016 | 684810.5 | 602540.7 | 18.10 | 122.2 | 7.3 | 126 | 9.5 | 97.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-80-01 | 6/2/2016 | 684834.1 | 602583.5 | 15.80 | 121.5 | 8.2 | 126 | 9.5 | 96.4 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-81-01 | 6/2/2016 | 684789.9 | 602568.2 | 15.50 | 122.3 | 12.2 | 126 | 9.5 | 97.1 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-82-01 | 6/2/2016 | 684752.2 | 602543.1 | 17.30 | 126.2 | 10.2 | 126 | 9.5 | 100.2 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-83-01 | 6/2/2016 | 684781.1 | 602601.8 | 16.00 | 118.6 | 10.2 | 126 | 9.5 | 94.1 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-84-01 | 6/2/2016 | 684801.5 | 602638.4 | 17.70 | 124.5 | 9.3 | 126 | 9.5 | 98.8 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-85-01 | 6/2/2016 | 684757.6 | 602625.7 | 18.70 | 121.4 | 8.7 | 126 | 9.5 | 96.3 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-86-01 | 6/2/2016 | 684704.4 | 602572.9 | 8.10 | 126.9 | 11.6 | 126 | 9.5 | 100.7 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-87-01 | 6/2/2016 | 684739.4 | 602607.5 | 18.30 | 124.2 | 9.8 | 126 | 9.5 | 98.6 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-88-01 | 6/2/2016 | 684755.1 | 602716.9 | 16.70 | 113.2 | 13.2 | 126 | 9.5 | 90.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-89-01 | 6/2/2016 | 684729.9 | 602698.7 | 19.60 | 115.7 | 11.8 | 126 | 9.5 | 91.8 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-90-01 | 6/2/2016 | 684676.0 | 602662.2 | 19.50 | 127.3 | 11.2 | 126 | 9.5 | 101.0 | 90 | 7 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | TEST | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | HC-91-01 | 6/2/2016 | 684684.9 | 602718.4 | 17.30 | 120.5 | 12.8 | 126 | 9.5 | 95.6 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-92-01 | 6/2/2016 | 684700.5 | 602765.4 | 20.60 | 113.6 | 9.3 | 126 | 9.5 | 90.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-93-01 | 6/2/2016 | 684673.2 | 602735.5 | 17.70 | 116.1 | 13.6 | 126 | 9.5 | 92.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-94-01 | 6/2/2016 | 684616.3 | 602716.8 | 18.00 | 125.0 | 9.4 | 126 | 9.5 | 99.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-95-01 | 6/2/2016 | 684650.6 | 602768.2 | 18.70 | 120.9 | 12.6 | 126 | 9.5 | 96.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-96-01 | 6/2/2016 | 684681.4 | 602798.3 | 18.90 | 113.5 | 12.7 | 126 | 9.5 | 90.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 8 | SF-10-8R | 6/2/2016 | 684712.5 | 602638.8 | 17.50 | 111.0 | 1.5 | 112.2 | 8.6 | 99.1 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 8 | SF-11-8R | 6/2/2016 | 684758.7 | 602671.8 | 17.40 | 110.5 | 1.8 | 112.2 | 8.6 | 98.7 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 9 | SF-10-9R | 6/2/2016 | 684715.2 | 602640.1 | 18.40 | 113.7 | 1.4 | 112.2 | 8.6 | 101.5 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 9 | SF-11-9R | 6/2/2016 | 684759.7 | 602673.9 | 18.40 | 115.7 | 1.4 | 112.2 | 8.6 | 103.3 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 10 | SF-19-10 | 6/15/2016 | 684509.5 | 602871.3 | 18.50 | 108.3 | 2.9 | 112.2 | 8.6 | 96.7 | 95 | 5 | Structural Fill - Tilcon | D Street Corridor-final el | V5N |
| 10 | SF-20-10 | 6/15/2016 | 684550.8 | 602901.1 | 19.00 | 108.7 | 2.6 | 112.2 | 8.6 | 97.0 | 95 | 5 | Structural Fill - Tilcon | D Street Corridor-final el | V5N |


Notes: Maximum Dry Density for Celgene GDL Cover Soil (CS) based on Vertical 5 Northeast Inc Sample ID 12691 approved in Entact Submittal 112B
Maximum Dry Density for 6 inch lift of Horizon C based on Vertical 5 Northeast Inc Sample ID 12934
Maximum Dry Density for Liberty Structural Fill (SF) based on Vertical 5 Northeast Inc Sample ID 12924 approved in Entact Submittal 117A
Maximum Dry Density for Tilcon Structural Fill (SF) based on Vertical 5 Northeast Inc Sample ID 13163 approved in Entact Submittal 128
Sample ID CS-1-2 Where:
CS=Cover Soil; HC=Horizon C; SF=Structural Fill
1 = Test Location as noted on Compaction Location Figures
2 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again

HC-107 became a Structural Fill test location after the D Street Corridor was widened

## 2.0 Test Location Drawings

- **GDL Cover Soil**
- **Horizon C**
- **Structural Fill**

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION CS-XX


GDL COVER SOIL ELEVATION CONTOURS


ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

| | |
|---|---|
| DRAWING NAME | GDL COVER SOIL COMPACTION LOCATIONS |
| PROJECT NAME & LOCATION | HONEYWELL SA-6 REMEDIATION<br>JERSEY CITY, NJ |

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | C. CYMBOR | APPROVED BY | | | |
| DATE | 10/15/15 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

2) HC-107 became a structural fill test location after the D street corridor was widened.

LEGEND:

COMPACTION TEST LOCATION HC-XX

GDL COVER SOIL ELEVATION CONTOURS



ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102



DRAWING NAME: HORIZON C PLANTING SOIL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | | |
| DATE | 06/17/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION SF-XX

PLANTING SOIL BOUNDARIES

STRUCTURAL FILL

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

DRAWING NAME: STRUCTURAL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | | |
| DATE | 05/19/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

**ATTACHMENT D-2**


**Figure Backfill Compaction Locations BF-01 to B-45**

**Figure Backfill Compaction Locations BF-46 to BF-94**

**Figure Backfill Compaction Locations BF-95 to BF-136**

**Figure Backfill Compaction Locations RF-01 to RF-21**

**Figure Backfill Compaction Locations RF 22 to RF-39**




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JN 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-01 TO BF-45

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-46 TO BF-94

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| | | | | | | JH | 9/15/15 |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on reduced testing frequency specified in 02315 3.13 A. 3.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-01 TO RF-21

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 02315 3.13 A. 3.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39, SITE 163, AND LOAM

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT D-3**

**Field Density Test Summary Log Table (Pages 1 to 7)**

**Field Density Test Summary Log Table (Pages 1 to 4)**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01* | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02* | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Brid | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-62 | | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-62-1 | 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |
| 0 | BF-64 | | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-64-1 | 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 3 | BF-64-2 | 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-65 | | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-65-1 | 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 0 | BF-66 | | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-66-1 | 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 2 | BF-66-2 | 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 0 | BF-67 | | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-67-1 | 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-67-2 | 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-68 | | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-68-1 | 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-68-2 | 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 0 | BF-69 | | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-69-1 | 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-69-2 | 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-70 | | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-70-1 | 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-70-2 | 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| 0 | BF-71 | | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 5 | BF-71-1 | 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-72 | | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 3 | BF-72-1 | 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| 0 | BF-73 | | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 6 | BF-73-1 | 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 6 | BF-75-2 | 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 6 | BF-76-2 | 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 6 | BF-77-2 | 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 7 | BF-78-2 | 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 7 | BF-80-2 | 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 4 | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 7 | BF-81-2 | 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 6 | BF-82-2 | 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 6 | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 7 | BF-83-3 | 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 6 | BF-84-3 | 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 6 | BF-85-3 | 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-86-2 | 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.
Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again
= Area subject to re-compaction

* *Initial field testing indicated compaction of greater then 95% (see attached Sor Testing Lab (STL) memo). Laboratory results for initially provided Weldon WC QP sample indicated a maximum dry density of 136.7 pcf. Using this density the compaction results are greater than the 95%. Laboratory tests on later deliveries indicated density results of 142.6 pcf. This range is typical of what can be expected for this type of source. The Engineer of Record (EOR) directed that the results be reported using the higher more conservative value and that the STL field test report verifying the higher passing results be attached to the final documentation. It is further noted that the Design Documents do not designate this area for compaction as Structural Fill per Specification Section 02315 Section 3.12, Structural Fill 95%; Non Structural Fill 90% Standard Proctor. The 95% value noted in this Table was implemented to provide for uniform compaction in areas slated for future development. It is the EOR's opinion that these two samples meet the 100% Design and project requirements.*

# SOR TESTING LABORATORIES, INC.

*Geotechnical Engineering - Materials Testing - Forensic Studies*
98 Sand Park Rd., Cedar Grove, NJ 07009
(973) 239-6001 Fax (973) 239-8380

Kamil Sor, Ph.D.
Orhun Sor, P.E.
Yilmaz Arhan, Ph.D.
Kenneth Rowbotham, P.E.
Atilla Sencar, P.E.



This report is the confidential property of the Client, and information
Contained may not be published or reproduced without our written permission.


| | | | |
|---|---|---|---|
| Client: | Entact Environmental Services | | |
| Project: | Honeywell SA-6, Jersey City NJ | | |
| Subject: | In-Place Density Tests | | |
| Job No.: | 13-208 | Report No.: 13-1994 | Date: 12/3/13 |

At the request of the client, on November 22, 2013 a field technician from Sor Testing Laboratories, Inc. reported to the project site for the purpose of performing in-place density tests over previously compacted lifts of materials at locations indicated by the client's representative.

Using a nuclear density gauge, our technician performed two density tests at locations 01BF-2 and 02BF-2 per the client's instructions. The proctor value of 136.7 pcf at our optimum moisture content of 8.1% was also provided by the client.

Test results were 97.5% and 95.7% compaction.

Technician: J.C. Jean-Toussaint

Very truly yours,

SOR TESTING LABORATORIES, INC.

Atilla Sencar, P.E.
Senior Engineer

AS/jh
Attachment

cc: (1) Client, Attn: Craig Cymbor (Email: ccymbor@entact.com)
(1) Client, Attn: Caroline Panico (Email: cpanico@entact.com)
(1) Client, Attn: Andrew Rizzuto (Email: arizzuto@entact.com)

# SOR TESTING LABORATORIES, INC.

*Geotechnical Engineering · Materials Testing · Forensic Studies*

98 Sand Park Rd., Cedar Grove, N.J. 07009
(973) 239-6001 • Fax (973) 239-8380

Kamil Sor, Ph.D.
Orhun Sor, P.E.
Peter G. Mickus, P.E.


## NUCLEAR DENSITY TEST DATA

Client: Entact Date: 11-22-2013
Project: HoneyWell SA-6 Job No.: 13-208 Report No. 13-1994
Daily Standard Count: _____ Density: 1975 Moisture 627

| TEST NUMBER | 1 | X | 2 | X | | | |
|---|---|---|---|---|---|---|---|
| Station | | | | | | | |
| Offset | | | | | | | |
| Elevation | 01BF-2 | | 02BF-2 | | | | |
| Mode & Depth (inches) | NORMAL/+10" | | NORMAL +10" | | | | |
| Density Count | N/A | | N/A | | | | |
| Wet Density (P.C.F.) | 137.8 | | 134.6 | | | | |
| Moisture Count | N/A | | N/A | | | | |
| Dry Density (P.C.F.) | 133.3 | | 130.8 | | | | |
| Moisture (P.C.F.) | 4.5 | | 3.6 | | | | |
| Moisture (%) | 3.4 | | 2.8 | | | | |
| Proctor Density (P.C.F.) | 136.7 | | 136.7 | | | | |
| Optimum Moisture (%) | | | | | | | |
| % Compaction | 97.5 | | 95.7 | | | | |
| Moisture Correction | | | | | | | |

REMARKS:

Jean C. Jean Mouaint
INSPECTOR

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 1 | RF-14-2 | 11/5/2014 | 684662.9 | 602542.6 | 0.0 | 134.0 | 0.6 | 135.8 | 6.4 | 99 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-16-2 | 11/5/2014 | 684767.6 | 602428.4 | 1.2 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 67 | Weldon WC Screenings | | V5N |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-17-2 | 11/5/2014 | 684723.7 | 602387.9 | 1.5 | 124.0 | 3.8 | 128.9 | 12.1 | 96 | 95 | 70 | Weldon WC Screenings | | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| 6 | RF-18-2 | 11/5/2014 | 684636.8 | 602258.1 | 5.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 73 | Weldon WC Screenings | Placed on Type A material | V5N |
| | RF-19 | | 684790.8 | 602339.5 | -2.5 | | | | | | | 75 | Stratum D | Bottom of excavation elevation | |
| 3 | RF-19-1 | 11/5/2014 | 684776.9 | 602328.5 | 1.8 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 75 | Weldon WC Screenings | | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| 4 | RF-21-2 | 11/5/2014 | 684823.4 | 602288.0 | 1.8 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 79 | Tilcon MH DGA | | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| 5 | RF-23-04 | 11/5/2014 | 684877.6 | 602222.8 | 2.5 | 134.0 | 0.7 | 135.8 | 6.4 | 99 | 95 | 85 | Tilcon MH DGA | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| NA | RF-27-LOAM | 12/15/2014 | 685045.9 | 601945.1 | -4.4 | 129.0 | 3.0 | 135.8 | 6.4 | 95 | 95 | 106 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| NA | RF-28-LOAM | 12/15/2014 | 685085.0 | 601862.1 | -4.7 | 135.8 | 4.0 | 135.8 | 6.4 | 100 | 95 | 112 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 0 | Site 163-2 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-2-1 | 11/5/2014 | 685070.9 | 601614.2 | 6.1 | 122.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| 2 | Site 163-2-2 | 11/14/2014 | 685070.5 | 601616.0 | 7.5 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| | | | | | | | | | | | | | | | |

***Notes:*** Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID RF-01-01 where:

RF = Reduced Frequency
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again
= Area subject to re-compaction

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

NOTE:
CONTOURS SHOWN HEREON REPRESENT THE CURRENT TOP OF BACKFILL AS SURVEYED BY ENTACT ON 12/29/2014.

AS BUILT BOTTOM OF EXCAVATION LIMIT

MAJOR CONTOUR

MINOR CONTOUR

0 40 80 160
SCALE IN FEET

ENTACT 302 UnRy Plaza Latrobe, PA 15650

DRAWING NAME:
FIGURE 2.1
BACKFILL TOPOGRAPHIC PROGRESS MAP

PROJECT NAME & LOCATION:
HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

JH 9/15/15

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

CONFIRMATORY BOTTOM SAMPLE ELEVATION

CONFIRMATORY SIDEWALL SAMPLE ELEVATION

0.0 POINT ELEVATION

POINT POINT DESCRIPTION

EXCAVATION TO STRATUM D

DESIGN EXCAVATION AREA

DESIGN EXCAVATION LIMIT

0 40 80 160

SCALE IN FEET

J.H. 02/01/16

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

FIGURE 1.2
EXCAVATION CONFIRMATION POINTS

PROJECT NAME & LOCATION

HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

DESIGN EXCAVATION LIMIT

AS BUILT BOTTOM OF EXCAVATION LIMIT

DEFERRED EXCAVATION AREAS (DC 2014-05-19)

0 40 80 160

SCALE IN FEET


ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

FIGURE 1.1
LIMIT OF EXCAVATION MAP

PROJECT NAME & LOCATION

HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ




ENTACT 302 Unity Plaza Latrobe, PA 15650


DRAWING NAME

FIGURE 1.3
EXCAVATION CELL LAYOUT

PROJECT NAME & LOCATION

HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

J.H. 02/01/16




LEGEND

- EXCAVATION LIMITS
- DE-WATERING WELLPOINT LOCATION
- SPLIT SPOON SOIL BORING
- TEMPORARY SHEETPILE ALIGNMENT
- DEEP WELL LOCATION

| REV | DATE | BY | CHK'D | APPR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| | | | | | |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: HONEYWELL SA-6 EXCAVATION DE-WATERING LAYOUT 03/15/16

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**ATTACHMENT B-1**

**SA-6 SOUTH EXCAVATION CONFIRMATORY POINTS (EAST)**

**Table 1.0 – 1.8 PDI Locations**

**Table 2.0 – 2.7 Center Points**

**Table 3.0 – 3.2 Sidewall**

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684138.4 | 603182.8 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1.0 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2.0 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684221.8 | 603013.0 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

* Elevations based on NGVD 1929 Datum. Coordinates are in the New Jersey state plane coordinate system, NAD 1983.

## SA-6 South Excavation: Confirmatory Points (Table 1.1)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684272.8 | 602944.8 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684273.8 | 602864.2 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684285.9 | 602856.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684305.4 | 602833.3 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684392.6 | 602878.7 | -2.8 | 124-SB-123 | 30 | 1/23/2014 | -2.4 | Stratum D Reached |
| 684311.9 | 602821.5 | 3.5 | 124-SB-021R | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684381.0 | 602861.0 | -2.3 | 124-SB-110 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684362.9 | 602837.4 | 3.2 | 124-SB-124 | 31 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684340.0 | 602818.0 | 3.2 | 124-SB-109 | 31 | 1/23/2014 | -1.6 | Stratum D Reached |
| 684318.6 | 602806.8 | 3.5 | 124-SB-021R | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684416.9 | 602861.1 | -2.8 | 124-SB-029 | 32 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684335.2 | 602800.6 | 3.5 | 124-SB-021R | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684411.9 | 602839.0 | -2.2 | 124-SB-092 | 33 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684348.7 | 602791.2 | 3.5 | 124-SB-021R | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684372.0 | 602797.0 | 2.6 | 124-PT-14 | 34 | 2/4/2014 | -1.9 | Stratum D Reached |
| 684355.8 | 602781.0 | 3.5 | 124-SB-021R | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684458.4 | 602838.3 | -2.3 | 124-SB-027 | 35 | 2/4/2014 | -2.7 | Stratum D Reached |
| 684367.5 | 602768.5 | 3.5 | 124-SB-021R | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684440.8 | 602806.0 | -2.8 | 124-SB-091 | 36 | 2/11/2014 | -2.7 | Stratum D Reached |
| 684371.2 | 602753.4 | 3.5 | 124-SB-021R | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684394.0 | 602777.3 | 4.7 | 124-SB-117A | 36 | 2/11/2014 | -1.6 | Stratum D Reached |
| 684473.9 | 602819.4 | -2.8 | 124-SB-026 | 37 | 2/11/2014 | -2.9 | Stratum D Reached |
| 684430.7 | 602784.0 | -1.3 | 124-SB-023 | 37 | 2/11/2014 | -3.6 | Stratum D Reached |
| 684412.9 | 602766.1 | 2.0 | 124-SB-121A | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684400.0 | 602762.0 | -0.1 | 124-PT-04 | 37 | 2/11/2014 | -2.2 | Stratum D Reached |
| 684380.7 | 602742.6 | 3.5 | 124-SB-021R | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684463.2 | 602783.7 | -2.3 | 124-SB-136 | 38 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684397.4 | 602736.2 | 3.5 | 124-SB-021R | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684448.4 | 602763.0 | 4.7 | 124-SB-022 | 39 | 2/20/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684505.3 | 602786.0 | -2.8 | 124-SB-024 | 40 | 2/27/2014 | -3.4 | Stratum D Reached |
| 684482.9 | 602770.8 | -3.3 | 124-SB-025 | 40 | 2/27/2014 | -3.0 | Stratum D Reached |
| 684430.0 | 602730.0 | 1.7 | 124-PT-03 | 40 | 2/27/2014 | 0.0 | Target Elevation Reached |
| 684468.5 | 602745.2 | 1.8 | 124-SB-066 | 40 | 2/27/2014 | -2.2 | Stratum D Reached |
| 684491.3 | 602754.6 | -2.3 | 124-SB-136R | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | 125-SB-029R | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684524.5 | 602765.0 | -3.5 | 125-SB-017 | 42 | 3/5/2014 | -3.1 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | 125-SB-029R | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684513.0 | 602736.0 | -4.3 | 125-PT-22 | 43 | 3/5/2014 | -3.5 | Stratum D Reached |
| 684496.0 | 602718.9 | -1.7 | 125-SB-086 | 43 | 3/5/2014 | -2.6 | Stratum D Reached |
| 684473.0 | 602698.0 | 0.3 | 125-PT-21 | 43 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684446.6 | 602677.9 | 0.5 | 125-SB-028 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684543.1 | 602743.1 | -3.9 | 125-SB-018 | 44 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684431.0 | 602654.0 | 0.7 | 125-PT-20 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684467.4 | 602652.6 | 1.0 | 125-SB-027 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684495.1 | 602674.9 | 0.4 | 125-SB-025 | 45 | 3/11/2014 | 0.3 | Target Elevation Reached |
| 684512.8 | 602689.3 | 0.3 | 125-SB-024 | 45 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684561.9 | 602720.2 | -3.3 | 125-SB-019 | 46 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684543.0 | 602699.0 | -4.7 | 125-PT-17 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684539.5 | 602702.1 | -3.7 | 125-SB-022 | 46 | 3/17/2014 | -3.3 | Stratum D Reached |
| 684503.0 | 602661.0 | 1.0 | 125-PT-16 | 46 | 3/17/2014 | -2.9 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | 125-SB-029R | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.3 | 124-SB-136R | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684481.2 | 602625.7 | 1.7 | 125-SB-089 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684488.7 | 602626.5 | 1.3 | 125-SB-026 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684581.0 | 602697.1 | -3.4 | 125-SB-020 | 48 | 3/20/2014 | -2.9 | Stratum D Reached |
| 684558.6 | 602678.9 | -4.0 | 125-SB-021 | 48 | 3/20/2014 | -3.4 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | 125-SB-029R | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |
| 684545.6 | 602650.2 | -3.3 | 125-SB-038 | 49 | 3/20/2014 | -3.3 | Stratum D Reached |
| 684597.3 | 602676.1 | -3.5 | 125-SB-037 | 49 | 3/25/2014 | -2.6 | Stratum D Reached |
| 684574.9 | 602657.9 | -3.4 | 125-SB-039 | 49 | 3/25/2014 | -3.3 | Stratum D Reached |
| 684535.1 | 602625.9 | 0.6 | 125-SB-032 | 49 | 3/25/2014 | -3.3 | Stratum D Reached |
| 684516.6 | 602611.2 | 1.1 | 125-SB-031 | 49 | 3/25/2014 | 0.1 | Target Elevation Reached |
| 684511.6 | 602592.1 | -1.0 | 125-SB-090 | 50 | 3/25/2014 | -1.3 | Target Elevation Reached |
| 684526.0 | 602608.3 | 0.4 | 125-SB-029R | 50 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684574.8 | 602647.4 | -2.3 | 124-SB-136R | 50 | 3/25/2014 | -3.6 | Stratum D Reached |
| 684514.6 | 602580.4 | -1.0 | 125-SB-090R | 51 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684535.3 | 602597.8 | 0.4 | 125-SB-029R | 51 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684584.1 | 602636.9 | -2.3 | 124-SB-136R | 51 | 3/28/2014 | -3.0 | Stratum D Reached |
| 684619.0 | 602648.6 | -1.5 | 125-SB-035 | 52 | 3/28/2014 | -2.5 | Stratum D Reached |
| 684596.6 | 602630.5 | -3.6 | 125-SB-034 | 52 | 3/28/2014 | -3.0 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684574.5 | 602612.8 | 0.7 | 125-SB-033 | 52 | 3/28/2014 | -3.4 | Stratum D Reached |
| 684556.8 | 602598.4 | 0.8 | 125-SB-030 | 52 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684538.3 | 602583.7 | 0.4 | 125-SB-029 | 52 | 3/28/2014 | 0.4 | Target Elevation Reached |
| 684523.8 | 602562.3 | -0.9 | 125-SB-078 | 52 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684579.0 | 602588.0 | 0.9 | 125-SB-009 | 53 | 4/1/2014 | -2.2 | Stratum D Reached |
| 684557.0 | 602576.5 | 0.4 | 125-SB-029R | 53 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684533.6 | 602556.0 | -1.0 | 125-SB-090R | 53 | 4/1/2014 | -1.4 | Target Elevation Reached |
| 684620.4 | 602605.9 | 0.4 | 125-SB-065 | 54 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684641.2 | 602623.7 | -2.1 | 125-SB-070 | 54 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684597.0 | 602588.0 | -2.7 | 125-SB-009A | 54 | 4/1/2014 | -2.2 | Stratum D Reached |
| 684573.7 | 602577.0 | 0.7 | 125-SB-044 | 54 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684557.6 | 602564.1 | 1.2 | 125-SB-050 | 54 | 4/1/2014 | 0.2 | Target Elevation Reached |
| 684632.0 | 602597.9 | -1.4 | 140-SB-083R | 55 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684576.2 | 602552.1 | 0.4 | 125-SB-029R | 55 | 4/4/2014 | 0.3 | Target Elevation Reached |
| 684664.6 | 602597.6 | -3.3 | 125-SB-071 | 56 | 4/4/2014 | -2.5 | Stratum D Reached |
| 684642.2 | 602579.5 | 0.2 | 125-SB-053 | 56 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684601.1 | 602556.0 | 3.1 | 125-SB-045 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684583.0 | 602540.8 | 0.6 | 125-SB-066 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684576.6 | 602529.9 | 2.1 | 125-SB-069 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684574.5 | 602511.9 | 2.1 | 125-SB-069R | 57 | 4/9/2014 | 1.6 | Target Elevation Reached |
| 684606.0 | 602536.9 | 0.4 | 125-SB-029R | 57 | 4/9/2014 | 0.1 | Target Elevation Reached |
| 684636.4 | 602554.1 | -2.4 | 125-SB-052 | 57 | 4/9/2014 | -1.2 | Stratum D Reached |
| 684591.8 | 602507.6 | 2.1 | 125-SB-069R | 58 | 4/9/2014 | 1.5 | Target Elevation Reached |
| 684679.9 | 602578.9 | -2.3 | 125-SB-062 | 58 | 4/9/2014 | -2.6 | Stratum D Reached |
| 684620.0 | 602524.0 | 0.6 | 125-SB-007 | 58 | 4/9/2014 | 0.2 | Target Elevation Reached |
| 684600.1 | 602523.2 | 0.6 | 125-SB-049 | 58 | 4/9/2014 | -0.1 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |
| 684373.5 | 602871.7 | -2.5 | C-30 | 30 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684311.9 | 602821.5 | 2.1 | C-30-1 | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684384.9 | 602861.2 | -2.5 | C-31 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684318.6 | 602806.8 | 2.1 | C-31-1 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684383.8 | 602841.5 | -2.5 | C-32 | 32 | 1/30/2014 | -1.8 | Stratum D Reached |
| 684335.2 | 602800.6 | 2.1 | C-32-1 | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684393.5 | 602830.6 | -2.5 | C-33 | 33 | 1/30/2014 | -1.9 | Stratum D Reached |
| 684348.7 | 602791.2 | 2.1 | C-33-1 | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684412.7 | 602824.5 | -2.5 | C-34 | 34 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684355.8 | 602781.0 | 2.1 | C-34-1 | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684422.4 | 602815.2 | -2.5 | C-35 | 35 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684367.5 | 602768.5 | 2.1 | C-35-1 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684432.1 | 602801.8 | -2.5 | C-36 | 36 | 2/11/2014 | -2.4 | Stratum D Reached |
| 684371.2 | 602753.4 | 2.1 | C-36-1 | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684440.7 | 602791.6 | -2.5 | C-37 | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684380.7 | 602742.6 | 2.1 | C-37-1 | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684460.4 | 602787.7 | -2.5 | C-38 | 38 | 2/20/2014 | -2.8 | Stratum D Reached |
| 684397.4 | 602736.2 | 2.1 | C-38-1 | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684471.9 | 602777.2 | -2.5 | C-39 | 39 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684416.4 | 602732.1 | 2.1 | C-39-1 | 39 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684481.8 | 602765.6 | -2.5 | C-40 | 40 | 2/27/2014 | -3.1 | Stratum D Reached |
| 684427.0 | 602721.5 | 0.4 | C-40-1 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684491.3 | 602754.6 | -2.5 | C-41 | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | C-41-1 | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684496.7 | 602740.4 | -2.5 | C-42 | 42 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | C-42-1 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684507.5 | 602729.5 | -2.5 | C-43 | 43 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684447.1 | 602679.0 | 0.4 | C-43-1 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684524.2 | 602722.2 | -2.5 | C-44 | 44 | 3/11/2014 | -3.5 | Stratum D Reached |
| 684454.3 | 602665.7 | 0.4 | C-44-1 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684536.0 | 602714.2 | -2.5 | C-45 | 45 | 3/11/2014 | -3.2 | Stratum D Reached |
| 684464.6 | 602655.3 | 0.4 | C-45-1 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684535.1 | 602693.1 | -2.5 | C-46 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | C-46-1 | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.5 | C-47 | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684483.8 | 602632.5 | 0.4 | C-47-1 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684551.5 | 602667.8 | -2.5 | C-48 | 48 | 3/20/2014 | -3.0 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | C-48-1 | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |
| 684564.6 | 602658.9 | -2.5 | C-49 | 49 | 3/25/2014 | -3.0 | Stratum D Reached |
| 684501.1 | 602607.9 | 0.4 | C-49-1 | 49 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684574.8 | 602647.4 | -2.5 | C-50 | 50 | 3/25/2014 | -3.6 | Stratum D Reached |
| 684526.0 | 602608.3 | 0.4 | C-50-1 | 50 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684507.7 | 602591.7 | -1.2 | C-50-2 | 50 | 3/25/2014 | -1.3 | Target Elevation Reached |
| 684584.1 | 602636.9 | -2.5 | C-51 | 51 | 3/28/2014 | -3.0 | Stratum D Reached |
| 684535.3 | 602597.8 | 0.4 | C-51-1 | 51 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684514.6 | 602580.4 | -1.2 | C-51-2 | 51 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684596.7 | 602626.3 | -2.5 | C-52 | 52 | 3/28/2014 | -2.9 | Stratum D Reached |
| 684547.0 | 602587.9 | 0.4 | C-52-1 | 52 | 3/28/2014 | 0.2 | Target Elevation Reached |
| 684524.8 | 602569.7 | -1.2 | C-52-2 | 52 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684602.1 | 602612.0 | -2.5 | C-53 | 53 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684557.0 | 602576.5 | 0.4 | C-53-1 | 53 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684533.6 | 602556.0 | -1.2 | C-53-2 | 53 | 4/1/2014 | -1.4 | Target Elevation Reached |
| 684610.8 | 602599.7 | -2.5 | C-54 | 54 | 4/4/2014 | -2.0 | Stratum D Reached |
| 684560.2 | 602558.1 | 0.4 | C-54-1 | 54 | 4/4/2014 | 0.3 | Target Elevation Reached |
| 684632.0 | 602597.9 | -2.5 | C-55 | 55 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684576.2 | 602552.1 | 0.4 | C-55-1 | 55 | 4/4/2014 | 0.3 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684641.4 | 602586.6 | -2.5 | C-56 | 56 | 4/4/2014 | -2.5 | Stratum D Reached |
| 684586.1 | 602541.3 | 0.4 | C-56-1 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684656.7 | 602578.2 | -2.5 | C-57 | 57 | 4/9/2014 | -2.4 | Stratum D Reached |
| 684606.0 | 602536.9 | 0.4 | C-57-1 | 57 | 4/9/2014 | 0.1 | Target Elevation Reached |
| 684574.5 | 602511.9 | 2.1 | C-57-2 | 57 | 4/9/2014 | 1.6 | Target Elevation Reached |
| 684662.3 | 602565.2 | -2.5 | C-58 | 58 | 4/9/2014 | -2.7 | Stratum D Reached |
| 684616.2 | 602527.5 | 0.4 | C-58-1 | 58 | 4/9/2014 | 0.3 | Target Elevation Reached |
| 684591.8 | 602507.6 | 2.1 | C-58-2 | 58 | 4/9/2014 | 1.5 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

## SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0)

| Sidewall Target Coordinates | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 0.6 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.6 | 603009.0 | -1.8 | 124-SB-075 | 14 | 11/21/2013 | -0.1 | Stratum D Reached |
| 684170.5 | 603030.7 | -1.8 | 124-SB-076 | 13 | 11/21/2013 | -0.1 | Stratum D Reached |
| 684173.5 | 602976.5 | -2.2 | 124-SB-074 | 16 | 12/5/2013 | -0.6 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684301.0 | 602795.0 | 2.6 | 124-SB-108 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684328.2 | 602790.2 | 3.3 | 124-SB-063 | 32 | 1/30/2014 | 1.8 | Target Elevation Reached |
| 684338.1 | 602786.6 | 4.7 | 124-SB-056 | 33 | 1/30/2014 | 1.7 | Target Elevation Reached |
| 684348.0 | 602746.0 | 3.4 | 124-PT-02 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684386.0 | 602707.0 | 3.3 | 124-PT-01 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684411.1 | 602714.2 | 3.9 | 124-SB-065 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684408.4 | 602664.2 | 2.2 | 125-SB-088 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684419.7 | 602644.6 | 1.8 | 125-SB-067 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684457.0 | 602620.0 | 1.1 | 125-PT-15 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684479.5 | 602597.5 | 3.7 | 125-SB-081 | 49 | 3/20/2014 | 0.1 | Target Elevation Reached |
| 684495.3 | 602579.6 | 0.8 | 125-SB-091 | 50 | 3/25/2014 | -1.4 | Target Elevation Reached |
| 684499.2 | 602575.0 | 2.3 | 125-SB-080 | 51 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684513.9 | 602557.6 | 0.6 | 125-SB-092 | 52 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684519.3 | 602551.3 | 2.5 | 125-SB-079 | 53 | 4/1/2014 | -1.5 | Target Elevation Reached |
| 684552.7 | 602504.6 | 3.5 | 125-SB-087 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 9/22/15

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**ATTACHMENT B-2**

**SA-6 SOUTH EXCAVATION CONFIRMATORY POINTS (WEST)**

**Table 1.0 – 1.8 PDI Locations**

**Table 2.0 – 2.7 Center Points**

**Table 3.0 – 3.2 Sidewall**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

* Elevations based on NGVD 1929 Datum. Coordinates are in the New Jersey state plane coordinate system, NAD 1983.

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -5.5 | 134-SB-019 | 114A | 12/8/2014 | -5.7 | Stratum D Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.0 | 601878.0 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Stratum D Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.4 | 601974.0 | -3.3 | 134-SB-061 | 106A | 11/20/2014 | -5.7 | Stratum D Reached |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.7 | 601978.2 | -7.5 | 134-SB-113 | 103 | 11/20/2014 | -7.6 | Stratum D Reached |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |
| 684908.2 | 602155.7 | -8.0 | 134-SB-049 | 89 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684943.6 | 602214.1 | -6.9 | 140-SB-035 | 88 | 8/25/2014 | -6.7 | Stratum D Reached |
| 684905.5 | 602180.6 | -7.8 | 140-SB-063 | 88 | 8/25/2014 | -6.1 | Stratum D Reached |
| 684875.3 | 602175.3 | -7.8 | 140-SB-062 | 87 | 8/25/2014 | -5.8 | Stratum D Reached |
| 684875.5 | 602187.9 | -7.3 | 140-SB-103 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684915.0 | 602239.0 | -6.1 | 140-SB-007 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |
| 684896.1 | 602229.3 | -6.6 | 140-SB-038 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684862.9 | 602228.0 | -6.1 | 134-SB-032R | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684901.7 | 602269.3 | -5.3 | 140-SB-040 | 83 | 9/4/2014 | -5.7 | Stratum D Reached |
| 684826.5 | 602208.8 | -6.5 | 140-SB-051 | 83 | 9/4/2014 | -4.7 | Stratum D Reached |
| 684854.3 | 602237.3 | -6.7 | 140-SB-041 | 83 | 9/4/2014 | -4.9 | Stratum D Reached |
| 684771.0 | 602188.4 | -4.8 | 140-SB-044 | 82 | 9/10/2014 | -5.2 | Stratum D Reached |
| 684800.2 | 602210.9 | -6.5 | 140-SB-042 | 82 | 9/10/2014 | -4.7 | Stratum D Reached |
| 684865.2 | 602271.1 | -6.2 | 140-SB-064 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684830.9 | 602252.5 | -6.3 | 140-SB-066 | 81 | 9/17/2014 | -3.1 | Stratum D Reached |
| 684716.6 | 602169.4 | -0.2 | 140-SB-043 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684755.4 | 602222.4 | -5.7 | 140-SB-047 | 80 | 9/23/2014 | -4.6 | Stratum D Reached |
| 684823.4 | 602275.4 | -5.0 | 140-SB-048 | 80 | 9/17/2014 | -2.8 | Stratum D Reached |
| 684687.1 | 602171.5 | 0.3 | 140-SB-049 | 79 | 9/23/2014 | -3.9 | Stratum D Reached |
| 684721.0 | 602200.6 | -4.2 | 140-SB-046 | 79 | 9/23/2014 | -5.1 | Stratum D Reached |
| 684680.8 | 602178.0 | -3.3 | 140-SB-075 | 79 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684695.5 | 602194.5 | -4.8 | 140-SB-018 | 79 | 9/23/2014 | -4.4 | Stratum D Reached |
| 684767.0 | 602244.0 | -4.4 | 140-SB-010 | 79 | 9/23/2014 | -4.0 | Stratum D Reached |
| 684818.0 | 602299.0 | -5.4 | 140-SB-009 | 78 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684855.0 | 602329.0 | -5.8 | 140-SB-065 | 78 | 9/23/2014 | -2.7 | Stratum D Reached |
| 684656.0 | 602192.0 | -2.7 | 140-SB-026 | 77 | 9/29/2014 | -2.3 | Stratum D Reached |
| 684740.4 | 602255.2 | -5.4 | 140-SB-082 | 77 | 9/29/2014 | -3.5 | Stratum D Reached |
| 684815.0 | 602348.7 | -3.4 | 140-SB-094 | 76 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684787.4 | 602330.2 | -0.4 | 140-SB-086 | 75 | 10/2/2014 | -4.0 | Stratum D Reached |
| 684744.9 | 602306.7 | -1.4 | 140-SB-083 | 75 | 10/2/2014 | -4.5 | Stratum D Reached |
| 684713.1 | 602276.0 | -0.4 | 140-SB-081 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684668.4 | 602240.2 | 0.1 | 140-SB-079 | 75 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684643.7 | 602221.3 | -4.2 | 140-SB-050 | 75 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684628.7 | 602233.7 | -2.9 | 140-SB-074 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684703.0 | 602285.6 | 2.6 | 140-SB-080 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684733.7 | 602322.4 | 0.6 | 140-SB-084 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.9 | 602371.9 | 0.1 | 140-SB-088 | 74 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684653.9 | 602259.3 | -1.4 | 140-SB-078 | 73 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684755.3 | 602343.3 | 0.6 | 140-SB-085 | 73 | 10/7/2014 | -1.6 | Stratum D Reached |
| 684660.7 | 602300.1 | 0.9 | 140-SB-089 | 72 | 10/9/2014 | -2.8 | Stratum D Reached |
| 684693.1 | 602326.3 | -3.0 | 140-SB-090 | 72 | 10/7/2014 | -3.3 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684745.4 | 602367.1 | 1.0 | 140-SB-091 | 72 | 10/7/2014 | -0.1 | Target Elevation Reached |
| 684640.0 | 602295.0 | 1.9 | 140-SB-011 | 71 | 10/9/2014 | -4.0 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | 125-SB-029R | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684629.9 | 602309.5 | 5.8 | 140-SB-033 | 70 | 10/9/2014 | 2.4 | Target Elevation Reached |
| 684725.2 | 602383.8 | 0.4 | 125-SB-029R | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684642.9 | 602315.4 | 0.9 | 140-SB-089R | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684764.0 | 602429.2 | -7.0 | 140-SB-N07 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | 125-SB-029R | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684632.0 | 602327.7 | 5.8 | 140-SB-033R | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684669.3 | 602386.6 | -0.6 | 140-SB-070 | 68 | 10/21/2014 | -2.3 | Stratum D Reached |
| 684679.0 | 602393.0 | 0.0 | 140-SB-013 | 68 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684760.1 | 602448.4 | -1.4 | 140-SB-083R | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | 125-SB-029R | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684629.6 | 602343.1 | 5.8 | 140-SB-033R | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684749.9 | 602465.0 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684700.0 | 602423.0 | 0.8 | 140-SB-012 | 67 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684715.4 | 602440.1 | -1.0 | 140-SB-029 | 67 | 10/21/2014 | -1.4 | Stratum D Reached |
| 684662.8 | 602394.7 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -1.4 | 140-SB-083R | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | 125-SB-073R | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684666.6 | 602417.0 | -2.7 | 140-SB-068 | 66 | 10/21/2014 | -3.0 | Stratum D Reached |
| 684735.5 | 602488.2 | -1.4 | 140-SB-083R | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | 125-SB-029R | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | 125-SB-073R | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | 125-SB-029R | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -1.4 | 140-SB-083R | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684666.2 | 602452.6 | 2.5 | 140-SB-030 | 64 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684735.4 | 602510.4 | -3.6 | 140-SB-067 | 64 | 10/24/2014 | -2.3 | Stratum D Reached |
| 684713.8 | 602503.3 | 4.3 | 140-SB-028 | 63 | 10/27/2014 | -2.4 | Stratum D Reached |
| 684727.7 | 602515.9 | -2.0 | 140-SB-104 | 63 | 10/27/2014 | -2.2 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | 125-SB-029R | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | 125-SB-073R | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | 125-SB-029R | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684653.2 | 602490.5 | 0.2 | 125-SB-057 | 61 | 10/24/2014 | -2.6 | Stratum D Reached |
| 684675.4 | 602508.2 | -1.2 | 125-SB-073 | 61 | 10/27/2014 | -2.5 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.8) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684697.8 | 602526.3 | -2.2 | 125-SB-055 | 61 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684707.1 | 602549.9 | -3.4 | 125-SB-072 | 61 | 10/28/2014 | -2.8 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | 125-SB-029R | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | 125-SB-073R | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | 125-SB-029R | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | 125-SB-069R | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684678.4 | 602552.4 | -2.4 | 125-SB-061 | 59 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684615.0 | 602501.1 | 0.5 | 125-SB-048 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684633.9 | 602516.6 | 0.6 | 125-SB-046 | 59 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684656.3 | 602534.7 | -1.4 | 125-SB-074 | 59 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684604.5 | 602498.0 | 2.1 | 125-SB-069R | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684916.0 | 601955.0 | -0.4 | 134-SB-026 | Area 41 | 12/10/2014 | -2.0 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | Increased excavation depth - UST location |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | Increased excavation depth - UST location |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | Increased excavation depth - UST location |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |
| 684922.3 | 602179.9 | -4.3 | C-89 | 89 | 8/20/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684912.0 | 602189.2 | -4.3 | C-88 | 88 | 8/25/2014 | -6.3 | Stratum D Reached |
| 684895.8 | 602194.1 | -4.3 | C-87 | 87 | 8/25/2014 | -6.0 | Stratum D Reached |
| 684880.8 | 602203.6 | -4.3 | C-86 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684872.8 | 602212.7 | -4.3 | C-85 | 85 | 8/29/2014 | -5.2 | Stratum D Reached |
| 684862.9 | 602228.0 | -4.3 | C-84 | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684820.9 | 602207.7 | -2.5 | C-83 | 83 | 9/4/2014 | -4.5 | Stratum D Reached |
| 684812.4 | 602218.7 | -2.5 | C-82 | 82 | 9/10/2014 | -4.1 | Stratum D Reached |
| 684788.9 | 602227.5 | -2.5 | C-81 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684778.7 | 602237.4 | -2.5 | C-80 | 80 | 9/17/2014 | -4.6 | Stratum D Reached |
| 684759.2 | 602240.0 | -2.5 | C-79 | 79 | 9/23/2014 | -4.1 | Stratum D Reached |
| 684758.4 | 602256.3 | -2.5 | C-78 | 78 | 9/23/2014 | -3.4 | Stratum D Reached |
| 684753.6 | 602273.9 | -2.5 | C-77 | 77 | 9/29/2014 | -3.8 | Stratum D Reached |
| 684731.1 | 602272.7 | -2.5 | C-76 | 76 | 9/29/2014 | -3.0 | Stratum D Reached |
| 684735.0 | 602292.1 | -2.5 | C-75 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684732.6 | 602313.2 | -2.5 | C-74 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.5 | 602381.3 | -2.5 | C-73 | 73 | 10/7/2014 | -2.7 | Stratum D Reached |
| 684752.7 | 602351.0 | 0.4 | C-73-1 | 73 | 10/7/2014 | 0.1 | Target Elevation Reached |
| 684662.4 | 602274.6 | -2.5 | C-73-2 | 73 | 10/7/2014 | -2.1 | Stratum D Reached |
| 684788.0 | 602395.1 | -2.5 | C-72 | 72 | 10/7/2014 | -2.5 | Stratum D Reached |
| 684743.1 | 602361.9 | 0.4 | C-72-1 | 72 | 10/7/2014 | -0.2 | Target Elevation Reached |
| 684664.8 | 602296.2 | -2.5 | C-72-2 | 72 | 10/7/2014 | -3.0 | Stratum D Reached |
| 684783.1 | 602411.4 | -2.5 | C-71 | 71 | 10/9/2014 | -2.7 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | C-71-1 | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684652.0 | 602308.3 | -2.5 | C-71-2 | 71 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684772.6 | 602425.4 | -2.5 | C-70 | 70 | 10/9/2014 | -2.5 | Stratum D Reached |
| 684725.2 | 602383.8 | 0.4 | C-70-1 | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684674.6 | 602346.3 | -2.5 | C-70-2 | 70 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684642.9 | 602315.4 | 0.4 | C-70-3 | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684626.5 | 602306.7 | 5.7 | C-70-4 | 70 | 10/9/2014 | 4.8 | Target Elevation Reached |
| 684762.8 | 602431.3 | -2.5 | C-69 | 69 | 10/14/2014 | -2.7 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | C-69-1 | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684670.5 | 602360.9 | -2.5 | C-69-2 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684632.0 | 602327.7 | 5.7 | C-69-3 | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684760.1 | 602448.4 | -2.5 | C-68 | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | C-68-1 | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684671.6 | 602375.8 | -2.5 | C-68-2 | 68 | 10/14/2014 | -2.2 | Stratum D Reached |
| 684629.6 | 602343.1 | 5.7 | C-68-3 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684749.9 | 602465.0 | -2.5 | C-67 | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684698.4 | 602419.3 | 0.4 | C-67-1 | 67 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684662.8 | 602394.7 | -2.5 | C-67-2 | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -2.5 | C-66 | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | C-66-1 | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | C-66-2 | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | C-66-3 | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684664.0 | 602411.1 | -2.5 | C-66-4 | 66 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684735.5 | 602488.2 | -2.5 | C-65 | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | C-65-1 | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | C-65-2 | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | C-65-3 | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -2.5 | C-65-4 | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684713.4 | 602487.7 | -1.2 | C-64 | 64 | 10/24/2014 | -1.8 | Stratum D Reached |
| 684653.2 | 602444.8 | 0.4 | C-64-1 | 64 | 10/21/2014 | -4.0 | Increased excavation depth - UST location |
| 684701.6 | 602502.1 | -1.2 | C-63 | 63 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | C-63-1 | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | C-62 | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | C-62-1 | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684689.4 | 602527.1 | -1.2 | C-61 | 61 | 10/28/2014 | -2.7 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | C-61-1 | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | C-60 | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | C-60-1 | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | C-60-2 | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684665.2 | 602547.7 | -1.2 | C-59 | 59 | 10/27/2014 | -2.8 | Stratum D Reached |
| 684620.0 | 602510.0 | 0.4 | C-59-1 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684604.5 | 602498.0 | 2.1 | C-59-2 | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 685023.9 | 601966.6 | -2.5 | C-104L | 104 | 11/20/2014 | -6.9 | Stratum D Reached |
| 685033.9 | 601960.1 | -2.5 | C-105L | 105 | 11/20/2014 | -6.6 | Stratum D Reached |
| 685039.4 | 601938.6 | -2.5 | C-106L | 106 | 11/20/2014 | -6.3 | Stratum D Reached |
| 685043.6 | 601927.9 | Stratum D | C-107L | Lens Area | 11/25/2014 | -6.2 | Stratum D Reached |
| 685042.9 | 601906.9 | Stratum D | C-108L | Lens Area | 11/25/2014 | -6.8 | Stratum D Reached |
| 685057.6 | 601895.2 | Stratum D | C-109L | Lens Area | 12/8/2014 | -6.6 | Stratum D Reached |
| 685055.4 | 601873.1 | Stratum D | C-110L | Lens Area | 12/8/2014 | -7.5 | Stratum D Reached |
| 685071.5 | 601867.1 | Stratum D | C-111L | Lens Area | 12/8/2014 | -7.6 | Stratum D Reached |
| 685086.2 | 601861.8 | Stratum D | C-112L | Lens Area | 12/8/2014 | -7.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685092.3 | 601848.6 | Stratum D | C-113L | Lens Area | 12/8/2014 | -7.0 | Stratum D Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685471.0 | 601475.6 | 4.3 | 073-SB-079 | 148 | 7/31/2014 | 4.3 | Expanded Excavation 4 |
| 685451.0 | 601460.9 | 7.1 | 073-SB-082 | 148 | 7/31/2014 | 2.2 | Expanded Excavation 4 |
| 685441.0 | 601496.0 | 4.0 | 073-SB-044 | 146A | 4/24/2014 | 5.4 | Expanded Excavation 3 |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685296.0 | 601562.0 | -0.6 | 073-SB-052 | 136 | 5/19/2014 | 2.1 | Expanded Excavation 3 |
| 685423.8 | 601494.3 | 1.6 | 073-SB-073 | 145A | 4/24/2014 | 5.4 | Expanded Excavation 3 |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685201.0 | 601844.0 | 0.9 | 134-SB-101 | 118A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685178.1 | 601893.6 | -3.0 | 134-SB-053 | 114 | 6/25/2014 | -0.1 | Expanded Excavation 3 |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Expanded Excavation 3 |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685095.0 | 601890.0 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Expanded Excavation 3 |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |


| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685081.0 | 601928.1 | -5.5 | 134-SB-021 | 109A | 11/25/2014 | -5.8 | Expanded Excavation 3 |
| 685081.0 | 601936.0 | 3.0 | 134-SB-092 | 108 | 7/10/2014 | -1.6 | Expanded Excavation 3 |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Expanded Excavation 3 |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 684999.6 | 601940.6 | -4.5 | 134-SB-097 | 104 | 11/20/2014 | -7.2 | Stratum D Reached |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |
| 684887.0 | 602147.0 | -2.1 | 134-SB-100 | 89 | 8/20/2014 | -5.8 | Stratum D Reached |
| 684869.0 | 602167.0 | -6.4 | 140-SB-061 | 87 | 8/25/2014 | -5.9 | Expanded Excavation 3 |
| 684821.2 | 602190.7 | -4.8 | 140-SB-060 | 84 | 9/4/2014 | -5.2 | Stratum D Reached |
| 684779.8 | 602174.6 | -0.8 | 140-SB-059 | 83 | 9/10/2014 | -5.6 | Stratum D Reached |
| 684727.5 | 602143.2 | 0.7 | 140-SB-076 | 83 | 9/10/2014 | -4.5 | Stratum D Reached |
| 684701.3 | 602132.8 | -0.8 | 140-SB-003 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684686.4 | 602158.8 | -0.8 | 140-SB-105 | 80 | 9/17/2014 | -4.8 | Stratum D Reached |
| 684651.0 | 602180.0 | -2.1 | 140-SB-027 | 77 | 9/29/2014 | -2.8 | Stratum D Reached |
| 684630.0 | 602210.0 | -1.9 | 140-SB-077 | 75 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684622.2 | 602287.4 | -2.0 | 140-SB-034 | 71 | 10/9/2014 | -3.0 | Stratum D Reached |
| 684597.0 | 602258.0 | -3.2 | 140-SB-025 | 71 | 10/9/2014 | -3.2 | Stratum D Reached |
| 684626.0 | 602343.0 | 6.8 | 140-SB-014 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684613.7 | 602330.2 | 6.1 | 140-SB-072 | 68 | 10/14/2014 | 4.5 | Target Elevation Reached |
| 684649.1 | 602367.2 | -1.0 | 140-SB-071 | 68 | 10/14/2014 | -2.8 | Stratum D Reached |
| 684648.1 | 602370.8 | -0.8 | 140-SB-032 | 67 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684649.1 | 602409.4 | -2.3 | 140-SB-069 | 65 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684629.1 | 602423.3 | 1.5 | 140-SB-031 | 64 | 10/21/2014 | -3.5 | Stratum D Reached |
| 684633.2 | 602474.4 | 0.4 | 125-SB-058 | 61 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684616.1 | 602485.8 | 3.0 | 125-SB-068 | 60 | 10/21/2014 | 1.8 | Target Elevation Reached |
| 684588.4 | 602494.2 | -3.5 | 125-SB-119 | 59 | 10/21/2014 | 1.5 | Expanded Excavation 3 |
| 685087.0 | 601829.1 | -6.0 | 134-SB-171 | Lens Area | 12/8/2014 | -6.1 | Expanded Excavation 4 |
| 685053.5 | 601827.8 | -6.5 | 134-SB-170 | Lens Area | 12/8/2014 | -6.8 | Expanded Excavation 4 |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685029.7 | 601840.0 | -5.5 | 134-SB-175 | Lens Area | 12/8/2014 | -6.7 | Expanded Excavation 4 |
| 685003.5 | 601868.2 | -5.8 | 134-SB-177 | Lens Area | 12/8/2014 | -5.9 | Expanded Excavation 4 |
| 684917.7 | 601947.9 | -1.2 | 134-SB-087 | Area 41 | 12/10/2014 | -2.1 | Target Elevation Reached |
| 684936.3 | 601954.8 | -1.2 | 134-SB-088 | Area 41 | 12/10/2014 | -2.4 | Target Elevation Reached |
| 684918.0 | 601975.0 | -1.2 | 134-SB-089 | Area 41 | 12/10/2014 | -1.7 | Target Elevation Reached |
| 684904.3 | 601963.0 | -1.2 | 134-SB-090 | Area 41 | 12/10/2014 | -1.6 | Target Elevation Reached |

3 Horizontal and/or vertical expansion of excavation due to visual inspection and analytical sampling resulted in removal of the PDI Sidewall Sample. The objectives of the 100% design and the target excavation limits were achieved.

4 Additional sidewall sample collected and analyzed to establish expanded excavation limit.

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**



1/27/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**ATTACHMENT B-3**

**SA-6 SOUTH EXCAVATION SITE 163 & 60 KELLOGG EXCAVATION**

**Table 1.0 PDI Locations**

**Table 3.0 Sidewall**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation (Site 163): Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685185.6 | 601432.8 | 5.8 | 163-SB-107 | N/A | 10/30/2014 | 5.0 | Area 43 - Target Elevation Reached |
| 685169.6 | 601446.1 | 6.0 | 163-SB-020 | N/A | 10/30/2014 | 4.8 | Area 43 - Target Elevation Reached |
| 685102.9 | 601588.4 | 5.2 | 163-SB-015 | N/A | 10/30/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685125.0 | 601586.5 | 6.3 | 163-SB-043 | N/A | 10/30/2014 | 5.7 | Area 163 - Target Elevation Reached |
| 685037.6 | 601660.2 | 4.5 | 163-SB-010 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685029.9 | 601632.6 | 5.2 | 163-SB-013 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685028.1 | 601625.3 | 6.8 | 163-SB-064 | N/A | 11/5/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 685064.3 | 601635.5 | 4.9 | 163-SB-112 | N/A | 11/5/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685069.7 | 601654.2 | 5.0 | 163-SB-011 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685054.7 | 601600.3 | 3.6 | 163-SB-063 | N/A | 10/31/2014 | 3.5 | Area 163 - Target Elevation Reached |
| 685062.5 | 601603.2 | 4.6 | 163-SB-014 | N/A | 10/31/2014 | 3.4 | Area 163 - Target Elevation Reached |
| 685100.1 | 601617.6 | 5.3 | 163-SB-012 | N/A | 10/31/2014 | 3.7 | Area 163 - Target Elevation Reached |
| 684984.0 | 601680.9 | 5.5 | 163-SB-101 | N/A | 11/7/2014 | 5.0 | Area 163 - Target Elevation Reached |
| 684997.7 | 601696.5 | 5.5 | 163-SB-093 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685012.8 | 601711.3 | 5.6 | 163-SB-092 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685001.4 | 601739.4 | 6.6 | 163-SB-086 | N/A | 11/7/2014 | 4.8 | Area 163 - Target Elevation Reached |
| 684854.7 | 601827.8 | 5.7 | 163-SB-008 | N/A | 11/12/2014 | 5.1 | Area 163 - Target Elevation Reached |
| 684889.4 | 601833.1 | 6.2 | 163-SB-072 | N/A | 11/12/2014 | 4.7 | Area 163 - Target Elevation Reached |
| 684901.6 | 601758.2 | 7.6 | 163-SB-065 | N/A | 11/12/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 684913.3 | 601758.5 | 5.7 | 163-SB-009 | N/A | 11/12/2014 | 5.1 | Area 163 - Target Elevation Reached |
| 684943.7 | 601757.2 | 5.9 | 163-SB-073 | N/A | 11/12/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684970.6 | 601767.7 | 3.3 | 163-SB-007 | N/A | 11/12/2014 | 3.1 | Area 163 - Target Elevation Reached |
| 684970.3 | 601782.2 | 3.3 | 163-SB-060 | N/A | 11/12/2014 | 2.6 | Area 163 - Target Elevation Reached |
| 684784.2 | 602004.7 | 4.9 | 163-SB-114 | N/A | 12/12/2014 | 4.0 | Area 42 - Target Elevation Reached |
| 684779.6 | 601989.9 | 4.8 | 163-SB-003 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |
| 684756.5 | 602015.6 | 5.8 | 163-SB-108 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Elevations based on NGVD 1929 Datum. Coordinates are in the New Jersey state plane coordinate system, NAD 1983.

## SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0)

| Sidewall Target Coordinates | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685197.1 | 601418.1 | 5.2 | 163-SB-097 | N/A | 10/30/2014 | 5.0 | Area 43 - Target Elevation Reached |
| 685181.4 | 601455.3 | 6.0 | 163-SB-035 | N/A | 10/30/2014 | 5.1 | Area 43 - Target Elevation Reached |
| 685158.1 | 601437.3 | 7.0 | 163-SB-061 | N/A | 10/30/2014 | 8.9 | Area 43 - Deferred to preserve Bulk Head 2 |
| 685160.1 | 601457.8 | 7.5 | 163-SB-036 | N/A | 10/30/2014 | 4.6 | Area 43 - Target Elevation Reached |
| 685026.9 | 601624.6 | 7.8 | 163-SB-076 | N/A | 11/5/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 685045.9 | 601596.1 | 7.9 | 163-SB-077 | N/A | 10/31/2014 | 3.2 | Area 163 - Target Elevation Reached |
| 685072.2 | 601547.5 | 7.1 | 163-SB-062 | N/A | 10/30/2014 | 3.6 | Area 163 - Target Elevation Reached |
| 684993.2 | 601662.1 | 6.4 | 163-SB-100 | N/A | 11/7/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 684961.1 | 601691.9 | 7.3 | 163-SB-113 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684871.6 | 601791.8 | 5.6 | 163-SB-066 | N/A | 11/12/2014 | 7.2 | Area 163 - Deferred to preserve Bulk Head 2 |
| 684893.3 | 601758.8 | 5.6 | 163-SB-085 | N/A | 11/12/2014 | 4.8 | Area 163 - Target Elevation Reached |
| 684929.4 | 601730.4 | 5.2 | 163-SB-084 | N/A | 11/12/2014 | 5.0 | Area 163 - Target Elevation Reached |
| 684891.6 | 601853.5 | 6.9 | 163-SB-051 | N/A | 11/12/2014 | 4.5 | Area 163 - Target Elevation Reached |
| 684852.1 | 601829.3 | 5.6 | 163-SB-052 | N/A | 11/12/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684843.0 | 601829.0 | 5.6 | 163-SB-067 | N/A | 11/12/2014 | 6.8 | Area 163 - Deferred to preserve Bulk Head 2 |
| 684797.0 | 601966.1 | 5.7 | 163-SB-069 | N/A | 12/12/2014 | 4.1 | Area 42 - Target Elevation Reached |
| 684807.5 | 602016.1 | 5.9 | 134-SB-146 | N/A | 12/12/2014 | 4.1 | Area 42 - Target Elevation Reached |
| 684750.1 | 602027.2 | 6.4 | 163-SB-091 | N/A | 12/12/2014 | 4.5 | Area 42 - Target Elevation Reached |
| 684747.0 | 601998.4 | 6.0 | 163-SB-058 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |
| 684751.6 | 601971.2 | 5.6 | 163-SB-071 | N/A | 12/12/2014 | 4.2 | Area 42 - Target Elevation Reached |
| 685138.0 | 601563.6 | 6.2 | 163-SB-078 | N/A | 12/22/2014 | 4.7 | Area 163-1 - Target Elevation reached |
| 685083.7 | 601558.5 | 6.0 | 163-SB-017 | N/A | 12/22/2014 | 4.3 | Area 163-1 - Target Elevation reached |
| 685165.5 | 601546.0 | 6.5 | 163-SB-080 | N/A | 12/22/2014 | 5.6 | Area 163-1 - Target Elevation reached |

2 Work adjacent the bulkhead had been deferred and will be completed in accordance with the Consent Order Consolidating the 100% Design for Study Area 6 North and Study Area 6 South filed into the court on July 9, 2013.

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades.**

R. Thomas Hugg 1/26/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South: Site 163 Chrome Excavation (2016): Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 685069.7 | 601654.2 | -3.0 | 163-SB-011 | 1/15/2016 | -3.2 | Target Elevation Reached |
| 685102.9 | 601588.4 | -6.7 | 163-SB-015 | 1/19/2016 | -6.8 | Target Elevation Reached |
| 685184.5 | 601554.4 | -6.7 | 163-SB-104 | 2/12/2016 | -7.1 | Target Elevation Reached |
| 685186.5 | 601509.2 | -8.0 | 163-SB-016 | 2/19/2016 | -8.3 | Target Elevation Reached 2 |
| 685247.3 | 601467.8 | -6.6 | 163-SB-105 | 2/19/2016 | -7.1 | Target Elevation Reached* |

* The PDI Target Depth was -6.6 ft. The excavation Design Bottom was set conservatively at -6.8 ft. The excavation bottom was surveyed at -7.1 ft.

## SA-6 South: Site 163 Chrome Excavation (2016): Sidewall Confirmatory Points (Table 2.0)

| Sidewall Target Coordinates | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 685138.0 | 601563.6 | -5.3 | 163-SB-078 | 1/19/2016 | -6.9 | Target Elevation Reached |
| 685165.5 | 601546.0 | -3.5 | 163-SB-080 | 2/12/2016 | -7.1 | Target Elevation Reached |
| 685201.0 | 601525.8 | -5.0 | 163-SB-019 | 2/19/2016 | -7.1 | Target Elevation Reached |
| 685207.2 | 601503.5 | -3.0 | 163-SB-037 | 2/19/2016 | -7.1 | Target Elevation Reached |
| 685247.6 | 601452.5 | -5.2 | 163-SB-021 | 2/19/2016 | -7.2 | Target Elevation Reached |

1 This is the actual elevation of the PDI sample included with the approved Figure 1 - Site 163 Additional Chromium Excavation Areas dated 9/22/15.

2 Elevation -8.3 ft. was coincidental with the top of Stratum D.

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Sidewall Confirmatory Sidewall Points Table 2 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades.**



4/14/16

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South: 60 Kellogg Excavation (2016): Post Excavation Points (Table 1.0)

| Bottom Target Coordinates | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 684474.8 | 602542.4 | 6.3 | 125-SB-312 | 6/10/2016 | 6.2 | Target Elevation Reached |

## SA-6 South: 60 Kellogg Excavation (2016): Sidewall Post Excavation Points (Table 2.0)


| Sidewall Target Coordinates | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 684465.7 | 602542.9 | 6.0 | 125-SB-308 | 6/10/2016 | 6.0 | Target Elevation Reached |
| 684460.7 | 602551.9 | 6.8 | 125-SB-309 | 6/10/2016 | 6.7 | Target Elevation Reached |
| 684476.4 | 602554.5 | 6.0 | 125-SB-310 | 6/10/2016 | 6.0 | Target Elevation Reached |
| 684477.8 | 602543.5 | 6.4 | 125-SB-311 | 6/10/2016 | 6.4 | Target Elevation Reached |

1 This is the actual elevation of the samples that were collected post excavation (6/2/16).

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Post Excavation Points depicted in Table 1, Post Excavation Sidewall Points Table 2 are correct, and representative of the as-built post-excavation grades.**

R. Thomas Hugg 6/17/16

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**




## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW POST-EXCAVATION ELEVATIONS WITHIN THE SA6 SOUTH, SITE 163 & SITE 60 KELLOGG EXCAVATION AREAS AT THE PROJECT SITE.
2. POST-EXCAVATION LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM 10/23/13 THROUGH 12/22/14, 1/4/16 THROUGH 3/4/16 & 6/10/16. POST EXCAVATION SURFACES AND CONTOURS WERE GENERATED BY ENTACT AND CONFIRMED BY MASER CONSULTING P.A. WITH MINOR ADJUSTMENTS.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 3 | 7/30/16 | UPDATED DESIGN BOE LIMITS | BSB | RTH |
| 2 | 7/12/16 | ADDED SITE 163 DATA & 60 KELLOGG TOPO | BSB | RTH |
| 1 | 3/13/15 | REVISED PER CLIENT COMMENTS 3/4/15 | BSB | RTH |

DSGN BSB | DR | CHK JR | APVD RTH

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
EXCAVATION PLAN

FILE NUMBER
XXXXX


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 08223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 890 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 3/3/15 |
| PROJ | 3480-10-0027 |
| DWG | C-111 |
| SHEET | 1 OF 1 |


FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-SA6S-FINAL.dwg PLOT DATE: Mon, 01 Aug 2016 PLOT TIME: 3:09 PM




NOTES:

1. PLAN LOCATION AND TOP ELEVATION OF HYDRAULIC BARRIER BASED ON SURVEY COMPLETED UNDER SUPERVISON OF MASER AND REPRSENTS THE FINAL ELEVATION AFTER THE WALL WAS CUT TO MATCH DESIGN LINER GRADES.
2. BOTTOM OF HYDRAULIC BARRIER AND EXTENT OF EPOXY COATING BASED ON ENTACT TOP SURVEY AND SHEET PILE FABRICATION DRAWINGS. ALL SHEETS DELIVERED TO THE SITE WERE INSPECTED BY AMEC PERSONNEL TO VERIFY LENGTHS AND EPOXY COATING.
3. STRATUM D SHOWN FOR REFERENCE ONLY AND IS BASED ON GEOTECHNICAL BORINGS COMPLETED DURING THE PRELIMINARY DESIGN INVESTIGATION.

NOTE: GROUTED ANGLES INSTALLED FROM STATION 0+00 TO 18+49




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 2/10/16 | TDD | RJR | TDD | TDD |

DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT

REVISION BY APVD

TDD SGS

NJ PROFESSIONAL ENGINEER LICENSE NUMBER SGS

Honeywell
101 COLUMBIA RD. BOX 2106, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 587-2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-201 |
| SHEET | OF |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:06 PM




NOTES:

1. REFER TO NOTES 1 THRU 3 ON SHEET S-201




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT | | | | | |
|---|---|---|---|---|---|---|---|
| | | REVISION | | | | BY | APVD |
| 1 | 2/10/16 | | | | | TDD | SGS |
| DSGN | | DR | CHK | APVD | | | |
| | TDD | | RJR | TDD | | | |

NJ PROFESSIONAL ENGINEER
SGS LICENSE NUMBER

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-202 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:05 PM




MATCH LINE SHEET S-202


NOTES:

1. REFER TO NOTES 1 THRU 3 ON SHEET S-201




SEE NOTE HB19 ON SHEET GN-003

SHEET SEALING DETAIL
NTS
F
SN-201 | CN-301




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | REVISION | BY | APV'D |
|---|---|---|---|---|
| 1 | 2/10/16 | DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT | TDD | SGS |

DSGN TDD DR RJR CHK TDD APV'D SGS

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER
SGS

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS


CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 956 - 2929

VERIFY SCALE
BAR IS ONE INCH ON
ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-203 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO ATTACHED TABLE FOR SURVEY DOCUMENTATION OF 6 INCH HISTORIC FILL CAP INSTALLATION. TABLE PROVIDES SURVEYED SUBGRADE PRIOR TO DEPLOYMENT OF HISTORIC FILL DEMARCATION LAYER AND FINAL TOP OF STONE ELEVATIONS.
2. REFER TO FIGURE 1 FOR INSTALLED HISTORIC FILL CAP LIMITS.

0 50 100 200
SCALE IN FEET

Prepared/Date: TDD 11/15/16
Checked/Date: DEN 11/15/16
Revised/Date: TDD 12/21/16

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | NON-CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec foster wheeler<br>Environment & Infrastructure, Inc.<br>200 American Metro Blvd, Suite 113<br>Hamilton, NJ, 08619, (609) 689 - 2929<br>NJ Certificate of Authorization No.for 24GA28012600 | HISTORIC FILL CAP<br>SURVEY CONTROL GRID<br>PROJECT 3480-16-0515<br>FIGURE 2 |

C:\Drawings\SA-6 South Excavation Limits April 2013 Excavation Shapes\SA-6 South Non Cr Excavation.dwg Wed, 21 Dec 2016 - 8:48pm tony.dacevero

Honeywell SA-6 South
Devlopment Area Historic Fill Cap
Jersey City, New Jersey

Prepared By: T. Donovan 10/21/16
Checked By: N. Warner 11/17/16
Revised By: T.Donovan 12/21/16

**TABLE 1 - STONE COVER THICKNESS SUMMARY**

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 1 | 684850.53 | 601890.86 | 8.48 | 8.98 | 9.03 | 0.55 |
| 2 | 684878.09 | 601886.77 | 7.98 | 8.48 | 8.51 | 0.54 |
| 3 | 684938.83 | 601910.40 | 7.94 | 8.44 | 8.49 | 0.55 |
| 4 | 684788.76 | 601960.51 | 8.44 | 8.94 | 8.98 | 0.54 |
| 5 | 684838.82 | 601960.40 | 8.42 | 8.92 | 8.95 | 0.53 |
| 6 | 684888.87 | 601960.14 | 8.34 | 8.84 | 8.88 | 0.54 |
| 7 | 684941.99 | 601977.09 | 8.47 | 8.97 | 8.99 | 0.52 |
| 8 | 684978.23 | 601947.46 | 7.96 | 8.46 | 8.59 | 0.63 |
| 9 | 684788.61 | 602010.46 | 8.05 | 8.55 | 8.56 | 0.52 |
| 10 | 684838.88 | 602010.42 | 8.02 | 8.52 | 8.54 | 0.52 |
| 11 | 684888.76 | 602010.35 | 8.28 | 8.78 | 8.84 | 0.56 |
| 12 | 684938.87 | 602010.44 | 8.42 | 8.92 | 8.98 | 0.56 |
| 13 | 684988.66 | 602010.40 | 8.79 | 9.29 | 9.36 | 0.58 |
| 14 | 685038.80 | 602010.45 | 9.11 | 9.61 | 9.64 | 0.54 |
| 15 | 684784.65 | 602084.60 | 8.12 | 8.62 | 8.69 | 0.57 |
| 16 | 684838.95 | 602060.58 | 8.45 | 8.95 | 8.96 | 0.52 |
| 17 | 684888.63 | 602060.53 | 8.50 | 9.00 | 9.04 | 0.54 |
| 18 | 684938.91 | 602060.54 | 8.34 | 8.84 | 8.89 | 0.55 |
| 19 | 684988.96 | 602060.41 | 8.46 | 8.96 | 9.06 | 0.60 |
| 20 | 685036.50 | 602069.93 | 9.48 | 9.98 | 10.06 | 0.58 |
| 21 | 684738.84 | 602104.02 | 8.01 | 8.51 | 8.72 | 0.71 |
| 22 | 684788.71 | 602110.46 | 8.27 | 8.77 | 8.81 | 0.54 |
| 23 | 684838.96 | 602110.44 | 7.56 | 8.06 | 8.31 | 0.75 |
| 24 | 684888.70 | 602110.46 | 7.95 | 8.45 | 8.47 | 0.52 |
| 25 | 684938.82 | 602110.49 | 8.21 | 8.71 | 8.82 | 0.61 |
| 26 | 684991.33 | 602121.34 | 8.49 | 8.99 | 9.09 | 0.61 |
| 27 | 684702.90 | 602119.08 | 6.79 | 7.29 | 7.34 | 0.55 |
| 28 | 684738.91 | 602160.55 | 6.64 | 7.14 | 7.16 | 0.52 |
| 29 | 684788.83 | 602160.58 | 7.88 | 8.38 | 8.43 | 0.55 |
| 30 | 684838.77 | 602160.57 | 7.48 | 7.98 | 8.03 | 0.55 |
| 31 | 684888.90 | 602160.51 | 7.75 | 8.25 | 8.29 | 0.54 |
| 32 | 684949.21 | 602173.60 | 8.49 | 8.99 | 9.11 | 0.62 |
| 33 | 684638.88 | 602197.41 | 6.52 | 7.02 | 7.05 | 0.53 |
| 34 | 684688.86 | 602210.42 | 6.54 | 7.04 | 7.10 | 0.57 |
| 35 | 684738.91 | 602210.37 | 6.75 | 7.25 | 7.30 | 0.56 |
| 36 | 684788.78 | 602210.40 | 7.03 | 7.53 | 7.62 | 0.59 |
| 37 | 684838.87 | 602210.43 | 7.28 | 7.78 | 7.85 | 0.57 |
| 38 | 684895.42 | 602235.22 | 7.46 | 7.96 | 8.18 | 0.72 |
| 39 | 684586.72 | 602271.55 | 6.93 | 7.43 | 7.48 | 0.55 |
| 40 | 684638.81 | 602260.41 | 6.47 | 6.97 | 7.00 | 0.53 |
| 41 | 684688.77 | 602260.49 | 6.73 | 7.23 | 7.27 | 0.53 |
| 42 | 684738.85 | 602260.36 | 6.96 | 7.46 | 7.49 | 0.52 |
| 43 | 684788.88 | 602260.50 | 7.25 | 7.75 | 7.79 | 0.54 |
| 44 | 684838.81 | 602260.36 | 7.42 | 7.92 | 7.98 | 0.57 |
| 45 | 684638.83 | 602310.40 | 7.11 | 7.61 | 7.63 | 0.52 |
| 46 | 684689.00 | 602310.59 | 6.95 | 7.45 | 7.48 | 0.53 |
| 47 | 684738.74 | 602310.39 | 7.14 | 7.64 | 7.72 | 0.58 |
| 48 | 684788.83 | 602310.46 | 7.37 | 7.87 | 7.88 | 0.51 |
| 49 | 684848.05 | 602300.52 | 7.44 | 7.94 | 8.22 | 0.78 |
| 50 | 684619.91 | 602360.46 | 7.98 | 8.48 | 8.51 | 0.54 |
| 51 | 684688.83 | 602360.58 | 7.63 | 8.13 | 8.15 | 0.52 |
| 52 | 684739.13 | 602360.50 | 7.50 | 8.00 | 8.06 | 0.56 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 53 | 684816.55 | 602343.81 | 7.51 | 8.01 | 8.44 | 0.93 |
| 54 | 684638.63 | 602410.42 | 8.46 | 8.96 | 8.99 | 0.53 |
| 55 | 684688.76 | 602410.52 | 8.28 | 8.78 | 8.83 | 0.55 |
| 56 | 684781.49 | 602402.20 | 8.51 | 9.01 | 9.03 | 0.53 |
| 57 | 684688.66 | 602460.47 | 8.63 | 9.13 | 9.21 | 0.58 |
| 58 | 684737.30 | 602478.82 | 9.54 | 10.04 | 10.29 | 0.75 |
| 59 | 684588.71 | 602510.27 | 8.28 | 8.78 | 8.81 | 0.53 |
| 60 | 684638.69 | 602510.50 | 8.25 | 8.75 | 8.78 | 0.53 |
| 61 | 684688.88 | 602510.53 | 8.64 | 9.14 | 9.16 | 0.52 |
| 62 | 684530.78 | 602520.13 | 9.17 | 9.67 | 9.70 | 0.53 |
| 63 | 684584.76 | 602578.22 | 7.41 | 7.91 | 7.98 | 0.57 |
| 64 | 684675.41 | 602559.84 | 8.52 | 9.02 | 9.39 | 0.87 |
| 65 | 684488.74 | 602610.39 | 8.41 | 8.91 | 8.94 | 0.53 |
| 66 | 684538.76 | 602610.26 | 7.83 | 8.33 | 8.36 | 0.53 |
| 67 | 684633.33 | 602608.11 | 8.53 | 9.03 | 9.32 | 0.79 |
| 69 | 684488.79 | 602660.54 | 8.16 | 8.66 | 8.74 | 0.57 |
| 70 | 684575.62 | 602667.46 | 8.52 | 9.02 | 9.31 | 0.79 |
| 71 | 684370.71 | 602715.69 | 9.25 | 9.75 | 9.76 | 0.51 |
| 72 | 684438.80 | 602710.54 | 8.64 | 9.14 | 9.20 | 0.56 |
| 73 | 684496.01 | 602718.89 | 8.52 | 9.02 | 9.04 | 0.52 |
| 74 | 684388.65 | 602760.45 | 9.06 | 9.56 | 9.61 | 0.55 |
| 75 | 684438.79 | 602760.46 | 8.68 | 9.18 | 9.23 | 0.55 |
| 76 | 684514.09 | 602738.44 | 9.50 | 10.00 | 10.15 | 0.65 |
| 77 | 684338.82 | 602810.43 | 9.53 | 10.03 | 10.05 | 0.53 |
| 78 | 684388.72 | 602810.44 | 8.98 | 9.48 | 9.53 | 0.54 |
| 79 | 684431.95 | 602851.50 | 9.53 | 10.03 | 10.08 | 0.56 |
| 80 | 684236.11 | 602854.74 | 9.99 | 10.49 | 10.69 | 0.71 |
| 81 | 684288.76 | 602860.37 | 9.66 | 10.16 | 10.20 | 0.55 |
| 82 | 684338.78 | 602860.35 | 9.47 | 9.97 | 10.00 | 0.53 |
| 83 | 684388.99 | 602860.30 | 9.41 | 9.91 | 9.94 | 0.53 |
| 84 | 684172.97 | 602894.67 | 10.97 | 11.47 | 11.49 | 0.52 |
| 85 | 684238.76 | 602910.44 | 10.12 | 10.62 | 10.67 | 0.55 |
| 86 | 684288.63 | 602910.46 | 9.80 | 10.30 | 10.37 | 0.57 |
| 87 | 684326.56 | 602906.44 | 9.50 | 10.00 | 10.04 | 0.54 |
| 88 | 684188.78 | 602960.47 | 10.27 | 10.77 | 10.80 | 0.53 |
| 89 | 684238.84 | 602960.43 | 9.81 | 10.31 | 10.34 | 0.53 |
| 90 | 684288.81 | 602960.31 | 9.25 | 9.75 | 9.80 | 0.54 |
| 91 | 684338.79 | 602960.55 | 9.95 | 10.45 | 10.46 | 0.52 |
| 92 | 684188.77 | 603010.41 | 9.41 | 9.91 | 9.96 | 0.55 |
| 93 | 684238.70 | 603010.36 | 9.06 | 9.56 | 9.58 | 0.51 |
| 94 | 684288.66 | 603010.40 | 9.20 | 9.70 | 9.74 | 0.54 |
| 95 | 684188.60 | 603060.40 | 8.75 | 9.25 | 9.28 | 0.53 |
| 96 | 684238.88 | 603060.50 | 8.62 | 9.12 | 9.15 | 0.52 |
| 97 | 684188.84 | 603110.46 | 8.35 | 8.85 | 8.88 | 0.53 |
| 98 | 684138.84 | 603160.56 | 8.35 | 8.85 | 8.87 | 0.52 |
| 99 | 684183.32 | 603156.53 | 8.43 | 8.93 | 8.96 | 0.53 |
| 100 | 684138.93 | 603210.41 | 8.41 | 8.91 | 8.92 | 0.51 |
| 101 | 684154.79 | 603090.07 | 8.48 | 8.98 | 9.00 | 0.53 |
| 102 | 684114.14 | 603210.60 | 8.43 | 8.93 | 8.97 | 0.54 |
| 103 | 684158.66 | 603187.23 | 8.41 | 8.91 | 8.96 | 0.55 |
| 104 | 684649.94 | 602460.53 | 8.45 | 8.95 | 8.98 | 0.53 |
| 105 | 684842.24 | 601884.19 | 8.99 | 9.49 | 9.54 | 0.55 |
| 106 | 684743.69 | 602009.93 | 8.47 | 8.97 | 8.99 | 0.53 |
| 107 | 684465.34 | 602799.24 | 9.48 | 9.98 | 10.01 | 0.53 |
| 108 | 684162.46 | 602987.20 | 10.56 | 11.06 | 11.11 | 0.55 |
| 109 | 684299.28 | 602791.88 | 9.91 | 10.41 | 10.46 | 0.56 |
| 111 | 684469.46 | 602592.76 | 9.75 | 10.25 | 10.29 | 0.54 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 112 | 684426.35 | 602551.07 | 8.95 | 9.45 | 9.67 | 0.71 |
| 113 | 684465.37 | 602513.85 | 9.54 | 10.04 | 10.19 | 0.66 |
| 114 | 684506.30 | 602540.54 | 9.09 | 9.59 | 9.62 | 0.53 |
| 115 | 684300.35 | 602633.76 | 9.37 | 9.87 | 9.96 | 0.59 |
| 116 | 684241.58 | 602696.86 | 9.64 | 10.14 | 10.20 | 0.55 |
| 117 | 684322.55 | 602660.05 | 9.71 | 10.21 | 10.22 | 0.51 |
| 118 | 684280.62 | 602729.42 | 9.98 | 10.48 | 10.68 | 0.70 |
| 119 | 684226.49 | 602751.17 | 11.31 | 11.81 | 11.91 | 0.60 |
| 120 | 684192.72 | 602724.85 | 10.86 | 11.36 | 11.41 | 0.55 |
| 121 | 684129.32 | 602792.92 | 10.28 | 10.78 | 10.85 | 0.57 |
| 122 | 684189.03 | 602766.50 | 11.19 | 11.69 | 11.70 | 0.52 |
| 123 | 684206.60 | 602825.41 | 10.84 | 11.34 | 11.37 | 0.53 |
| 124 | 684271.32 | 602794.41 | 11.65 | 12.15 | 12.16 | 0.52 |
| 125 | 684352.11 | 602692.92 | 9.51 | 10.01 | 10.15 | 0.65 |
| 126 | 684141.54 | 602849.80 | 10.73 | 11.23 | 11.25 | 0.52 |
| 127 | 684105.24 | 602861.12 | 10.75 | 11.25 | 11.26 | 0.51 |
| 128 | 684061.00 | 602864.26 | 10.95 | 11.45 | 11.45 | 0.50 |
| 129 | 684084.37 | 602909.12 | 11.19 | 11.69 | 11.73 | 0.54 |
| 130 | 684124.50 | 602949.30 | 11.31 | 11.81 | 11.83 | 0.52 |
| 131 | 684163.34 | 602941.90 | 10.84 | 11.34 | 11.36 | 0.52 |
| 132 | 684316.22 | 602732.34 | 10.46 | 10.96 | 11.00 | 0.54 |
| 133 | 684338.20 | 602754.97 | 9.70 | 10.20 | 10.27 | 0.57 |
| 134 | 685355.89 | 601230.69 | 9.11 | 9.61 | 9.61 | 0.50 |
| 135 | 685324.33 | 601302.06 | 9.00 | 9.50 | 9.69 | 0.68 |
| 136 | 685275.64 | 601348.34 | 9.19 | 9.69 | 9.72 | 0.53 |
| 137 | 685322.51 | 601333.80 | 8.76 | 9.26 | 9.29 | 0.53 |
| 138 | 685391.57 | 601355.09 | 9.53 | 10.03 | 10.12 | 0.59 |
| 139 | 685438.87 | 601360.40 | 9.62 | 10.12 | 10.13 | 0.51 |
| 140 | 685233.03 | 601403.24 | 9.48 | 9.98 | 10.27 | 0.79 |
| 141 | 685288.85 | 601410.45 | 9.33 | 9.83 | 9.88 | 0.55 |
| 142 | 685352.13 | 601375.02 | 8.13 | 8.63 | 8.75 | 0.62 |
| 143 | 685381.70 | 601415.65 | 8.02 | 8.52 | 8.59 | 0.57 |
| 144 | 685438.76 | 601401.67 | 9.16 | 9.66 | 10.08 | 0.92 |
| 145 | 685488.71 | 601410.53 | 9.19 | 9.69 | 9.76 | 0.56 |
| 146 | 685185.04 | 601463.89 | 8.49 | 8.99 | 9.22 | 0.73 |
| 147 | 685238.86 | 601460.43 | 7.80 | 8.30 | 8.34 | 0.54 |
| 148 | 685288.63 | 601460.34 | 7.93 | 8.43 | 8.49 | 0.56 |
| 149 | 685338.77 | 601460.53 | 7.95 | 8.45 | 8.52 | 0.57 |
| 150 | 685388.72 | 601460.53 | 8.14 | 8.64 | 8.82 | 0.67 |
| 151 | 685438.85 | 601460.42 | 8.51 | 9.01 | 9.10 | 0.59 |
| 152 | 685138.89 | 601510.39 | 8.45 | 8.95 | 9.07 | 0.61 |
| 153 | 685171.47 | 601516.47 | 7.95 | 8.45 | 8.52 | 0.57 |
| 154 | 685238.84 | 601510.42 | 7.91 | 8.41 | 8.50 | 0.60 |
| 155 | 685288.87 | 601510.50 | 7.99 | 8.49 | 8.58 | 0.59 |
| 156 | 685338.72 | 601510.43 | 8.06 | 8.56 | 8.60 | 0.54 |
| 157 | 685388.81 | 601510.45 | 8.25 | 8.75 | 8.77 | 0.52 |
| 158 | 685091.55 | 601573.95 | 9.01 | 9.51 | 9.54 | 0.53 |
| 159 | 685139.17 | 601560.87 | 8.01 | 8.51 | 8.52 | 0.51 |
| 160 | 685188.95 | 601560.43 | 7.98 | 8.48 | 8.49 | 0.52 |
| 161 | 685238.79 | 601560.52 | 7.95 | 8.45 | 8.57 | 0.63 |
| 162 | 685288.79 | 601560.44 | 8.02 | 8.52 | 8.59 | 0.57 |
| 163 | 685338.83 | 601560.54 | 8.14 | 8.64 | 8.69 | 0.56 |
| 164 | 685388.81 | 601560.55 | 8.26 | 8.76 | 8.80 | 0.53 |
| 165 | 685108.25 | 601601.30 | 8.02 | 8.52 | 8.57 | 0.55 |
| 166 | 685141.73 | 601615.66 | 8.10 | 8.60 | 8.56 | 0.47 |
| 167 | 685188.81 | 601610.44 | 8.01 | 8.51 | 8.60 | 0.59 |
| 168 | 685238.77 | 601610.51 | 8.02 | 8.52 | 8.56 | 0.54 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 169 | 685288.72 | 601610.43 | 8.09 | 8.59 | 8.63 | 0.54 |
| 170 | 685338.74 | 601610.37 | 8.22 | 8.72 | 8.75 | 0.53 |
| 171 | 685042.54 | 601644.70 | 8.49 | 8.99 | 9.01 | 0.53 |
| 172 | 685088.79 | 601660.54 | 7.97 | 8.47 | 8.51 | 0.54 |
| 173 | 685138.80 | 601660.45 | 7.97 | 8.47 | 8.48 | 0.51 |
| 174 | 685188.79 | 601660.67 | 8.58 | 9.08 | 9.14 | 0.55 |
| 175 | 685238.85 | 601660.43 | 8.57 | 9.07 | 9.20 | 0.62 |
| 176 | 685288.82 | 601660.43 | 8.30 | 8.80 | 8.81 | 0.51 |
| 177 | 685378.00 | 601603.14 | 9.01 | 9.51 | 9.56 | 0.55 |
| 178 | 684985.35 | 601708.30 | 8.48 | 8.98 | 9.03 | 0.55 |
| 179 | 685038.72 | 601710.44 | 7.95 | 8.45 | 8.47 | 0.52 |
| 180 | 685088.70 | 601710.51 | 7.95 | 8.45 | 8.48 | 0.53 |
| 181 | 685138.70 | 601710.42 | 8.00 | 8.50 | 8.53 | 0.53 |
| 182 | 685188.77 | 601710.45 | 8.10 | 8.60 | 8.65 | 0.54 |
| 183 | 685245.18 | 601696.62 | 9.11 | 9.61 | 9.67 | 0.56 |
| 184 | 684938.65 | 601760.43 | 8.48 | 8.98 | 9.01 | 0.53 |
| 185 | 684988.83 | 601760.39 | 7.79 | 8.29 | 8.35 | 0.57 |
| 186 | 685038.79 | 601760.40 | 7.88 | 8.38 | 8.38 | 0.50 |
| 187 | 685088.76 | 601760.49 | 7.94 | 8.44 | 8.47 | 0.52 |
| 188 | 685138.85 | 601760.56 | 7.99 | 8.49 | 8.52 | 0.53 |
| 189 | 685188.77 | 601760.47 | 8.08 | 8.58 | 8.62 | 0.54 |
| 190 | 685243.48 | 601776.76 | 8.52 | 9.02 | 9.53 | 1.01 |
| 191 | 684938.83 | 601810.34 | 7.95 | 8.45 | 8.50 | 0.55 |
| 192 | 684988.71 | 601810.51 | 7.92 | 8.42 | 8.44 | 0.52 |
| 193 | 685038.93 | 601810.65 | 7.93 | 8.43 | 8.45 | 0.52 |
| 194 | 685088.74 | 601810.48 | 8.01 | 8.51 | 8.55 | 0.55 |
| 195 | 685138.84 | 601810.44 | 8.15 | 8.65 | 8.70 | 0.55 |
| 196 | 685188.76 | 601810.45 | 8.23 | 8.73 | 8.76 | 0.53 |
| 197 | 684900.77 | 601820.97 | 8.49 | 8.99 | 9.03 | 0.55 |
| 198 | 684938.61 | 601860.44 | 7.95 | 8.45 | 8.49 | 0.54 |
| 199 | 684988.79 | 601860.38 | 7.92 | 8.42 | 8.50 | 0.57 |
| 200 | 685038.71 | 601860.53 | 7.95 | 8.45 | 8.56 | 0.61 |
| 201 | 685088.78 | 601860.46 | 8.08 | 8.58 | 8.59 | 0.51 |
| 202 | 685138.76 | 601860.39 | 8.27 | 8.77 | 8.82 | 0.56 |
| 203 | 684989.00 | 601910.71 | 7.95 | 8.45 | 8.48 | 0.53 |
| 204 | 685038.68 | 601910.43 | 8.04 | 8.54 | 8.56 | 0.51 |
| 205 | 685089.10 | 601910.60 | 8.17 | 8.67 | 8.70 | 0.53 |
| 206 | 685153.99 | 601894.76 | 8.50 | 9.00 | 9.18 | 0.69 |
| 207 | 685038.79 | 601960.46 | 8.16 | 8.66 | 8.72 | 0.56 |
| 208 | 685088.76 | 601960.51 | 8.20 | 8.70 | 8.75 | 0.55 |
| 209 | 685088.34 | 601998.68 | 8.53 | 9.03 | 9.08 | 0.55 |
| 210 | 685238.84 | 601433.13 | 7.83 | 8.33 | 8.95 | 1.12 |
| 211 | 685464.45 | 601375.39 | 9.22 | 9.72 | 9.76 | 0.53 |
| 212 | 684965.05 | 601707.90 | 7.69 | 8.19 | 8.22 | 0.53 |
| 213 | 685514.96 | 601424.03 | 12.02 | 12.52 | 12.57 | 0.55 |
| 214 | 685394.14 | 601276.89 | 9.54 | 10.04 | 10.07 | 0.54 |
| 215 | 685280.99 | 601380.01 | 9.16 | 9.66 | 9.68 | 0.53 |
| 216 | 685494.34 | 601395.26 | 9.62 | 10.12 | 10.14 | 0.52 |
| 217 | 685418.92 | 601304.80 | 10.54 | 11.04 | 11.06 | 0.52 |
| 218 | 685304.76 | 601272.35 | 8.73 | 9.23 | 9.26 | 0.52 |
| 219 | 685238.01 | 601363.97 | 8.56 | 9.06 | 9.30 | 0.75 |
| 220 | 685189.66 | 601417.66 | 7.95 | 8.45 | 8.73 | 0.78 |
| 221 | 685148.00 | 601467.87 | 9.25 | 9.75 | 9.81 | 0.56 |
| 222 | 685098.56 | 601526.04 | 7.53 | 8.03 | 8.09 | 0.56 |
| 223 | 685056.74 | 601591.18 | 7.60 | 8.10 | 8.31 | 0.71 |
| 224 | 684992.62 | 601668.34 | 7.03 | 7.53 | 7.79 | 0.76 |
| 225 | 684881.94 | 601800.15 | 6.54 | 7.04 | 7.33 | 0.79 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 226 | 684845.03 | 601850.20 | 8.45 | 8.95 | 9.13 | 0.69 |
| 227 | 684794.36 | 601918.98 | 7.45 | 7.95 | 8.06 | 0.61 |
| 228 | 684724.35 | 602006.36 | 7.22 | 7.72 | 7.74 | 0.52 |

GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW TOP OF STONE ELEVATIONS WITHIN THE SA6 SOUTH EXCAVATION AREAS AT THE PROJECT SITE.
2. STONE LAYER LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. AND ENTACT ON MULTIPLE FIELD VISITS FROM 10/5/16, 10/6/16, AND 10/20/16.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 158 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12-1511A

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | M.H.S. | DR | B.S.B. | APVD | BSB | R.T.H. |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER 24GS36737


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS


CIVIL
SA6 SOUTH STONE LAYER



amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/19/16 |
| PROJ | 3480-10-0027 |
| DWG | C-113 |
| SHEET | 1 OF 1 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\V-SURV-SA6S-SOUTH-STONE.dwg PLOT DATE: Tue, 20 Dec 2016 PLOT TIME: 10:44 AM




NOTE: NO HISTORIC FILL SHALL BE PLACED ON SA–7

TYPICAL VEGETATED SLOPE
NTS

NOTE:

1. REFER TO FIGURE 2 FOR CONSTRUCTION CONTROL GRID AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE ON THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL AS SHOWN ON THE TYPICAL VEGETATED SLOPE DETAIL. THE VEGETATED SLOPE ALONG SA–7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. EXISTING PAVEMENT WAS FIELD INSPECTED BY LSRP AND SUBJECT TO MINOR CRACK FILLING TO SATISFY HISTORIC FILL CAP REQUIREMENTS.
4. STEEL SHEETPILE WALL WAS INSTALLED AS EXCAVATION SUPPORT ALONG THIS AREA AND THEN CUT BELOW CURRENT GRADE AND LEFT IN PLACE. THE TOP OF SHEETPILE IS GENERALLY 0.5 TO 2.0 FT BELOW CURRENT GRADES.

STONE COVER
VEGETATED COVER
PAVEMENT COVER
CONCRETE COVER
STONE COVER IN PLANTER AREAS
RIPARIAN ZONE
DGA COVER
STONE TOE DRAIN
STEEL SHEETPILE WALL
STORM DRAIN PIPE
STORM DRAIN CATCH BASIN


0 80 160 FEET
SCALE


| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: AS BUILT RESTORATION PLAN SA–6 SOUTH – SHEET 001 12/12/16

PROJECT NAME & LOCATION: HONEYWELL SA–6 REMEDIATION JERSEY CITY, NJ




LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT TOPSOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP TOPSOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS ON JUNE 23, 2016 & FROM OCT. 3 THROUGH NOV. 3, 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR CHK | APVD | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP TOPSOIL
GRADING PLAN

FILE NUMBER
12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 158 STAGECOACH ROAD - MARMORA, NJ 08223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/20/16 |
| PROJ | 3480-10-0027 |
| DWG | C-128 |
| SHEET | 1 OF 3 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SA6S GDL SOUTH TOPSOIL.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 5:54 PM

MATCH LINE SHEET C-130

MATCH LINE SHEET C-128

INSIDE SOUTHWEST EDGE OF SCB WALL LIMITS

BARRIER WALL LIMIT (TYP.)

AS-BUILT TOPSOIL LIMITS (TYP.)

LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

0 20 40 80

SCALE IN FEET

## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT TOPSOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.
2. AS-BUILT SOUTH CAP TOPSOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS ON JUNE 23, 2016 & FROM OCT. 3 THROUGH NOV. 3, 2016
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12001511A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP TOPSOIL GRADING PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829


VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/20/16 |
| PROJ | 3480-10-0027 |
| DWG | C-129 |
| SHEET | 2 OF 3 |


Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962


STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR CHK | APVD | |


R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.



FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SA6S GDL SOUTH TOPSOIL.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 5:54 PM




MATCH LINE SHEET C-129

LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT TOPSOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.
2. AS-BUILT SOUTH CAP TOPSOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS ON JUNE 23, 2016 & FROM OCT. 3 THROUGH NOV. 3, 2016
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR | CHK | APVD |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP TOPSOIL
GRADING PLAN

FILE NUMBER
12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2229

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/20/16 |
| PROJ | 3480-10-0027 |
| DWG | C-130 |
| SHEET | 3 OF 3 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SA6S GDL SOUTH TOPSOIL.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 5:54 PM

**ATTACHMENT B**
**SURCHARGE COMPLETION EVALUATION TABLES**

## TABLE 1S-1
## SURCHARGE COMPLETION EVALUATION
## SUMMARY OF EFFECTIVE STRESS

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-01** | 2616 | 3236 | **124%** | Data as of November 2014. Pore pressure elevated 5 ft in Stratum D and 3 ft in Stratum RC. |
| **S_FS-02** | 2627 | 3201 | **122%** | Data as of November 2014. Pore pressure elevated 4.5 ft in Stratum D. |
| **S_HS-01** | 3064 | 3292 | **107%** | Data as of November 2014. |
| **S_HS-02** | 2571 | 2962 | **115%** | Data as of November 2014. Pore pressure elevated 3 ft in Stratum D. |
| **S_HS-03** | 2400 | 2541 | **106%** | Data as of November 2014. Pore pressure elevated 11 ft in Stratum D and 5.5 ft in Stratum RC. |
| **S_HS-04** | 2548 | 3053 | **120%** | Data as of November 2014. Pore pressure elevated 5 ft in Stratum D. |
| **S_HS-05** | 2583 | 2919 | **113%** | Data as of November 2014. |
| **S_HS-06** | 2881 | 3205 | **111%** | Data as of November 2014. Pore pressure elevated 1.5 ft in Stratum D and 7 ft in Stratum RC. |
| **S_HS-07** | 2494 | 3130 | **126%** | Data as of November 2014. |
| **S_HS-08** | 2595 | 2880 | **111%** | Data as of November 2014. Pore pressure elevated 5 ft in Stratum D. |

**TABLE 2S-1**
**SURCHARGE COMPLETION EVALUATION**
**AMEC CORRECTED RESULTS JANUARY 2015**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| S_FS-03 | 2343 | 2984 | 127% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_FS-04 | 2359 | 2909 | 123% | VWP data through 1/18/15; SP data through 1/30/15. |
| S_FS-05 | 1839 | 1833 | 100% | VWP data through 1/29/15; SP data through 1/30/15. |
| S_HS-09 | 2232 | 3194 | 143% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-10 | 2479 | 2777 | 112% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-11 | 2342 | 2656 | 113% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-12 | 2482 | 2877 | 116% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-13 | 2100 | 2412 | 115% | VWP data as of 1/29/15; SP data through 1/30/15. |
| S_HS-14 | 2138 | 2839 | 133% | VWP data as of 1/12/15; SP data through 1/30/15. |
| S_HS-15 | 2637 | 3234 | 123% | VWP data as of 1/12/15; SP data through 1/30/15. |

**TABLE 3S-1**
**SURCHARGE COMPLETION EVALUATION**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-06** | 2099 | 2664 | **127%** | Data through March 2015 |
| **S_FS-07** | 2376 | 2691 | **113%** | Data through March 2015 |
| **S_HS-16** | 2522 | 2619 | **104%** | Data through March 2015 |
| **S_HS-17** | 1751 | 2046 | **117%** | Data through March 2015 |
| **S_HS-18** | 970 | 1458 | **150%** | Data through March 2015 |
| **S_HS-19** | 845 | 1206 | **143%** | Data through March 2015 |
| **S_HS-20** | 2484 | 2499 | **101%** | Data through March 2015 |
| **S_HS-21** | 1504 | 1978 | **132%** | Data through March 2015 |
| **S_HS-22** | 966 | 1198 | **124%** | Data through March 2015 |

**ATTACHMENT C**
**MRCE SURCHARGE COMPLETION LETTERS**

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacollo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

April 24, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 1S Surcharge Review
SA-6 South
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) October 27, 2014 review of Area 1S indicated settlement monitoring location S_FS-02 did not meet the defined surcharge program goal as of September 23, 2014. AMEC provided MRCE with updated settlement and piezometer monitoring data for Area 1S location S_FS-02 on April 14, 2015. The MRCE review of April 14, 2015 AMEC settlement and piezometer monitoring data for Area 1S location S_FS-02 is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated November 18, 2014 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressure. Post-surcharge total stress was calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken on November 25, 2014. Calculated post-surcharge effective stress for S_FS-02 is presented in Table 1. MRCE compared the calculated post-surcharge effective stress with the "Final Post-Development Conditions" effective stress estimate provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 1S monitoring locations have met the surcharge program goal as of November 25, 2014.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

Table 1. MRCE SA-6 South Surcharge Monitoring Review for Area 1S (April 2015)

| Source: | | AMEC | | | | MRCE | | | | | | | | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Settlement Monitoring Point | Layer | Center of the Layer EL. (ft) | Pre-Surcharge Conditions Total Stress (psf) | Final Development Condition Effective Stress (psf) | Surcharge Conditions Effective Stress | Settlement Monitoring Data | | VWP Monitoring Data | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion (November 2014) |
| | | | | | | Date of Recording | Fill Thickness (ft) | Date of Recording | Elevation Head (ft) | | | | | |
| S_FS-01 | Center D | -8.6 | 1852.5 | 2616.3 | 2451.0 | 9/22/2014 | 17.15 | 9/23/2014 | 11.83 | 3996.3 | 1274.8 | 2721.4 | 104% | 124% |
| S_FS-02 | Center D | -11.16 | 2083.8 | 2627.1 | 2428.0 | 11/25/2014 | 21.17 | 11/18/2014 | 11.6 | 4730.1 | 1420.2 | 3309.8 | 126% | 122% |
| S_HS-01 | Center D | -11.2 | 2260.0 | 3064.0 | 3196.0 | 9/22/2014 | 15.31 | 9/23/2014 | 3.09 | 4173.8 | 891.7 | 3282.1 | 107% | 107% |
| S_HS-02 | Center D | -9.6 | 2103.8 | 2570.7 | 2774.0 | 9/22/2014 | 15.22 | 9/23/2014 | 7.11 | 4006.3 | 1042.7 | 2963.6 | 115% | 115% |
| S_HS-03 | Center D | -9.4 | 1942.5 | 2400.1 | 2440.0 | 9/22/2014 | 15.9 | 9/23/2014 | 12.19 | 3930.0 | 1347.2 | 2582.8 | 108% | 106% |
| S_HS-04 | Center D | -8.3 | 1841.3 | 2548.2 | 2595.0 | 9/22/2014 | 15.54 | 9/23/2014 | 9.4 | 3783.8 | 1104.5 | 2679.3 | 105% | 120% |
| S_HS-05 | Center D | -8.5 | 2031.3 | 2583.0 | 2703.0 | 9/22/2014 | 13.89 | 9/23/2014 | 6.25 | 3767.6 | 920.4 | 2847.2 | 110% | 113% |
| S_HS-06 | Center D | -10.4 | 2126.3 | 2880.7 | 3214.0 | 9/22/2014 | 16.24 | 9/23/2014 | 2.75 | 4156.3 | 820.6 | 3335.7 | 116% | 111% |
| S_HS-07 | Center D | -9.5 | 1867.5 | 2493.7 | 2894.0 | 9/22/2014 | 17.84 | 9/23/2014 | 6.65 | 4097.5 | 1007.8 | 3089.7 | 124% | 126% |
| S_HS-08 | Center D | -7.7 | 1787.5 | 2595.0 | 2707.0 | 9/22/2014 | 16.29 | 9/23/2014 | 7.74 | 3823.8 | 963.5 | 2860.3 | 110% | 111% |

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Michael J. Chow
Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

February 06, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 2S Surcharge Review
SA-6 North
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of February 06, 2015 AMEC settlement and piezometer monitoring data for Area 2S is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated between January 12-29, 2015 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken at corresponding dates, between January 14-30, 2015. Calculated post-surcharge effective stresses are presented in Table 1. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 2S monitoring locations have met the surcharge program goal as of 01/30/2015.

Very truly yours,
**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

Table 1. MRCE SA-6 Surcharge Monitoring Review for Area 2S

| Settlement Monitoring Point | Layer | Existing EL (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| S_FS-03 | Center O | -3.3 | 1332.5 | 2208.4 | 1/14/2015 | 1/12/2015 | 19.7 | 9.9 | 3798.8 | 823.7 | 2975.1 | 135% | - |
| | Top D | -5.8 | 1525.0 | 2291.7 | | | 19.7 | 13.0 | 3991.3 | 1172.5 | 2818.8 | 123% | - |
| | Center D | -7.0 | 1716.3 | 2342.5 | | | 19.7 | 13.4 | 4182.6 | 1273.6 | 2909.0 | 124% | 145% |
| | Bottom D | -8.3 | 1907.5 | 2393.4 | | | 19.7 | 6.5 | 4373.8 | 926.0 | 3447.7 | 144% | - |
| S_FS-04 | Center O | -1.5 | 1204.5 | 2223.3 | 1/23/2015 | 1/18/2015 | 19.8 | 7.6 | 3683.3 | 566.0 | 3117.3 | 140% | - |
| | Top D | -4.5 | 1353.0 | 2287.6 | | | 19.8 | 12.4 | 3831.8 | 1050.2 | 2781.6 | 122% | - |
| | Center D | -6.2 | 1620.8 | 2358.7 | | | 19.8 | 13.0 | 4099.6 | 1196.8 | 2902.7 | 123% | 134% |
| | Bottom D | -7.7 | 1888.5 | 2429.9 | | | 19.8 | 10.6 | 4367.3 | 1143.8 | 3223.5 | 133% | - |
| | RC | -46.5 | 6613.5 | 4771.3 | | | 19.8 | 3.9 | 9092.3 | 3147.5 | 5944.8 | 125% | - |
| S_FS-05 | Center O | -0.6 | 1185.0 | 1696.9 | 1/30/2015 | 1/29/2015 | 14.5 | 5.9 | 2992.5 | 406.8 | 2585.7 | 152% | - |
| | Top D | -3.6 | 1350.0 | 1768.3 | | | 14.5 | 8.1 | 3157.5 | 730.1 | 2427.4 | 137% | - |
| | Center D | -5.1 | 1617.8 | 1839.5 | | | 14.5 | 20.3 | 3425.3 | 1583.1 | 1842.2 | 100% | 115% |
| | Bottom D | -6.6 | 1885.5 | 1910.7 | | | 14.5 | 9.8 | 3693.0 | 1022.7 | 2670.3 | 140% | - |
| S_HS-09 | Center O | -4.0 | 1272.5 | 2097.7 | 1/14/2015 | 1/12/2015 | 18.2 | 9.1 | 3547.5 | 818.7 | 2728.8 | 130% | - |
| | Center D | -8.0 | 1656.3 | 2231.9 | | | 18.2 | 6.4 | 3931.3 | 896.7 | 3034.6 | 136% | 156% |
| S_HS-10 | Center O | -2.1 | 1831.3 | 2384.9 | 1/14/2015 | 1/12/2015 | 12.6 | 6.6 | 3406.3 | 545.4 | 2860.9 | 120% | - |
| | Center D | -4.4 | 2088.8 | 2478.6 | | | 12.6 | 10.2 | 3663.8 | 912.3 | 2751.5 | 111% | 131% |
| S_HS-11 | Center O | -5.2 | 1660.0 | 2218.6 | 1/14/2015 | 1/12/2015 | 12.8 | 9.0 | 3253.8 | 887.3 | 2366.4 | 107% | - |
| | Center D | -7.5 | 1986.3 | 2342.0 | | | 12.8 | 7.4 | 3580.1 | 927.9 | 2652.2 | 113% | 132% |
| | RC | -50.2 | 7257.5 | 4930.1 | | | 12.8 | 3.8 | 8851.3 | 3372.7 | 5478.5 | 111% | - |
| S_HS-12 | Center O | -3.9 | 1485.0 | 2350.9 | 1/14/2015 | 1/12/2015 | 15.9 | 10.1 | 3477.5 | 871.7 | 2605.8 | 111% | - |
| | Center D | -7.9 | 1875.3 | 2482.1 | | | 15.9 | 9.4 | 3867.8 | 1076.4 | 2791.4 | 112% | 130% |
| | RC | -52.4 | 7238.0 | 5077.5 | | | 15.9 | 1.8 | 9230.5 | 3382.1 | 5848.4 | 115% | - |
| S_HS-13 | Center O | -2.0 | 1261.5 | 1962.8 | 1/30/2015 | 1/292015 | 16.0 | 17.0 | 3255.3 | 1183.7 | 2071.5 | 106% | - |
| | Center D | -5.2 | 1664.0 | 2100.1 | | | 16.0 | 14.9 | 3657.8 | 1253.6 | 2404.1 | 114% | 129% |
| S_HS-14 | Center O | -2.0 | 1365.0 | 2023.3 | 1/14/2015 | 1/12/2015 | 17.6 | 10.6 | 3563.8 | 783.7 | 2780.0 | 137% | - |
| | Center D | -6.3 | 1691.5 | 2137.6 | | | 17.6 | 10.4 | 3890.3 | 1039.6 | 2850.7 | 133% | 148% |
| S_HS-15 | Center O | -2.8 | 1858.8 | 2539.5 | 1/14/2015 | 1/12/2015 | 16.6 | 11.5 | 3928.8 | 889.8 | 3039.0 | 120% | - |
| | Center D | -6.8 | 2111.9 | 2636.6 | | | 4181.9 | 964.7 | 3217.2 | 122% | 3217.2 | 122% | 140% |

"Note that the Amec calculations referenced by MRCE were subsequently updated. Please refer to Table 2S-1 for the final values used. The correction does not impact the conclusion."

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

April 24, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 3S Surcharge Review
SA-6 South
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of March 30, 2015 AMEC settlement and piezometer monitoring data for Area 3S is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated between March 24-13, 2015 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken on March 19, 2015. Calculated post-surcharge effective stresses are presented in Table 1. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 3S monitoring locations have met the surcharge program goal as of 03/30/2015.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

MP:F:\111\11173\2014 Surcharge Removal Review\SA-6_Area 3S\MRCE Review-Area 3S-April15.docx

Table 1. MRCE SA-6 South Surcharge Monitoring Review for Area 3S (April 2015)

| Settlement Monitoring Point | Layer | Existing EL (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| S_FS-06 | Top D | -2.7 | 1365.0 | 2031.3 | 3/19/2015 | 3/24/2015 | 14.3 | 6.6 | 3148.8 | 574.1 | 2574.7 | 127% | - |
| | Center D | -3.9 | 1620.0 | 2099.1 | | | 14.3 | 7.2 | 3403.8 | 693.3 | 2710.5 | 129% | 127% |
| | Bottom D | -5.2 | 1875.0 | 2166.9 | | | 14.3 | 9.6 | 3658.8 | 919.8 | 2739.0 | 126% | - |
| S_FS-07 | Center O | -0.8 | 1234.0 | 2256.5 | 3/19/2015 | 3/24/2015 | 16.9 | 4.8 | 3346.5 | 348.9 | 2997.6 | 133% | - |
| | Top D | -3.0 | 1388.0 | 2323.2 | | | 16.9 | 5.2 | 3500.5 | 510.7 | 2989.8 | 129% | - |
| | Center D | -4.3 | 1587.8 | 2376.3 | | | 16.9 | 11.8 | 3700.3 | 999.5 | 2700.8 | 114% | 113% |
| | Bottom D | -5.5 | 1787.5 | 2429.4 | | | 16.9 | 6.9 | 3900.0 | 775.1 | 3124.9 | 129% | - |
| | RC | -34.3 | 5220.0 | 4145.9 | | | 16.9 | 3.4 | 7332.5 | 2352.4 | 4980.1 | 120% | - |
| S_HS-16 | Center O | -0.6 | 1222.5 | 2420.6 | 3/19/2015 | 3/24/2015 | 18.0 | 5.3 | 3472.5 | 368.2 | 3104.3 | 128% | - |
| | Center D | -4.1 | 1551.5 | 2521.8 | | | 18.0 | 14.7 | 3801.5 | 1173.1 | 2628.4 | 104% | 104% |
| S_HS-17 | Center D | -3.8 | 1460.0 | 1750.9 | 3/19/2015 | 3/24/2015 | 10.3 | 7.4 | 2743.8 | 697.6 | 2046.1 | 117% | 117% |
| S_HS-18 | Center D | -2.5 | 1406.0 | 969.9 | 3/19/2015 | 3/24/2015 | 3.5 | 3.6 | 1841.0 | 382.5 | 1458.5 | 150% | 150% |
| S_HS-19 | Center D | -0.6 | 1207.5 | 844.5 | 3/19/2015 | 3/24/2015 | 3.0 | 4.9 | 1578.8 | 345.1 | 1233.7 | 146% | 143% |
| S_HS-20 | Center O | -1.2 | 1209.5 | 2392.7 | 3/19/2015 | 3/24/2015 | 15.1 | 5.3 | 3093.3 | 403.7 | 2689.5 | 112% | - |
| | Center D | -4.4 | 1494.3 | 2484.0 | | 3/13/2015 | 15.1 | 9.7 | 3378.0 | 878.6 | 2499.4 | 101% | 101% |
| S_HS-21 | Center D | -4.3 | 1581.5 | 1503.7 | 3/19/2015 | 3/24/2015 | 6.1 | 1.6 | 2339.0 | 367.5 | 1971.5 | 131% | 132% |
| S_HS-22 | Center D | -2.6 | 1436.8 | 966.3 | 3/19/2015 | 3/24/2015 | 1.7 | 4.6 | 1651.8 | 450.5 | 1201.2 | 124% | 124% |

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

September 29, 2015

AMEC Environmental & Infrastructure
511 Congress Street
Portland, ME 04101

Attn: Mr. Samuel G. Shallard
Re: DC 03-04-15
Area 3S Surcharge Pile Geometry on East End
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

This letter is in response to DC-03-04-15 "3S Surcharge Pile Geometry on East End," which requests change of the surcharge program at Area 3S to eliminate surcharge pre-load of a small area at the east end of the fill along the west side of Route 440.The April 24, 2015 MRCE letter summarized the settlement and piezometer monitoring data and confirmed that all monitoring locations in Area 3S satisfied the surcharge program goals. However, MRCE was not aware of the request of DC-03-04-15 at that review.

AMEC suggested that truncating the eastern tip of the wedge shaped surcharge fill will not significantly affect the goals of the Remedy/Surcharge program since the change in grade is from 0 – 5 ft. MRCE agrees with AMEC that since the increase in final grade is small, surcharging will have no significant affect. MRCE also reviewed available geotechnical data for the area in question, and finds that the compressible strata is pre-loaded such that no settlement will occur.

**Examining Pre-Consolidation Stress**

MRCE reviewed the soil profile closest to the "Deferred Area" and laboratory testing for compressible Stratum D. Boring location plan and summary of consolidation tests for Stratum D are attached (see Drawing B-1, Figure S-1, Plate 13 & Plate 18). The pre-consolidation stress (P'c) of the compressible layer Stratum D was tested for design of the Study Area 7 remediation. This test data was used to compute the pre-consolidation stress using two methods. The first method calculated the average P'c from the laboratory consolidation tests, resulting in P'c = 1930 psf. The second method calculated the effective overburden pressure at midpoint of Stratum D and multiplied it by the average OCR (overconsolidation ratio) defined by consolidation testing. With the average OCR = 2.23 and the average effective overburden stress = 1064 psf, the resulting average P'c = 2372 psf.

(see Appendix A). Settlement would only occur at the compressible layer if the effective stress due to filling exceeds 1930 to 2372 psf.

**Estimated Stress at Final Conditions**

Based on DC-03-04-15, the final grade will increase by 0 to 0.5 ft. The additional soil placed on top of the 12 ft wide area ranges from a height of 0 to 3 ft. Assuming an average height of the added soil as 1.5 ft and the maximum increase of grade, the final effective stress at the midpoint of Stratum D = 1314 psf, which is less than the lower bound of P'c = 1930 psf. (see Appendix A)

Since the effective vertical stress due to the final grade including planned added soil is less than the P'c of Stratum D, no settlement is expected. This technical review supports the AMEC evaluation that surcharging is not needed in the area addressed by DC-03-04-15.

Very truly yours,
**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, NJ PE # 24GE04652200


**Attachments**

| | |
|---|---|
| Drawing B-1 | Boring Location Plan |
| Figure S-1 | Soil Profile |
| Plate 18 | Consolidation Test Boring SB-210D |
| Plate 13 | Consolidation Test Boring SB-211D |

**Appendices**

| | |
|---|---|
| Appendix A | Calculations of Stresses |

# ATTACHMENTS




GRAPHIC SCALE

100' 50' 0 100' 200'

## LEGEND:

- – Geotechnical borings performed by CT&E under the inspection of MRCE in 1997.
- – Environmental borings performed by CT&E under the inspection of Brown and Root.
- – Nested monitoring wells performed by CT&E under the inspection of Parsons.
- – SB-100 Series: Shallow COPR characterization borings performed by B&B under the inspection of MRCE in 2003.
- – GEO Series: Geotechnical water borings performed by CMI under the inspection of MRCE in 2003.
- – SB-200 Series: Perimeter geotechnical borings performed by B&B under the inspection of MRCE in 2003.
- – SB-300 Series: Phase 2 Perimeter geotechnical borings performed by B&B under the inspection of MRCE in 2004.
- – MW Series: Shallow monitoring wells performed by CMI under the inspection of MRCE in 2003.
- – CPT Probes performed by Furgo Geosciences under the inspection of Parsons and MRCE in 2003.
- – SB-400 Series: Phase 2 geotechnical borings performed by B&B under the inspection of MRCE in 2004.
- – Test pits performed under the inspection of MRCE in 1997.
- – Test pits performed by Conti under the inspection of MRCE in 2004.

## NOTES:

1. See drawing K-1 for section location.
2. See drawing T-2 for general strata descriptions, notes and legend.

THIS DRAWING, THE PROPERTY OF HONEYWELL, IS FURNISHED SUBJECT TO RETURN ON DEMAND AND THE CONDITION THAT THE INFORMATION AND TECHNOLOGY EMBODIED HEREIN SHALL NOT BE DISCLOSED OR USED AND THE DRAWING SHALL NOT BE REPRODUCED OR COPIED IN WHOLE OR IN PART EXCEPT AS PREVIOUSLY AUTHORIZED IN WRITING. ANY PERSON WHO MAY RECEIVE OR OBSERVE THIS DESIGN WILL BE HELD STRICTLY LIABLE FOR ANY VIOLATION WHETHER WILLFUL OR NEGLIGENT.

| REV. | DATE | BY | DESCRIPTION |
|---|---|---|---|
| 1 | 7/9/04 | | PHASE 2 SUBSURFACE INVESTIGATION UPDATE |

STUDY AREA 7

JERSEY CITY NEW JERSEY

**Honeywell**

101 COLUMBIA ROAD, MORRISTOWN, NEW JERSEY 07962

PROJECT NO. 35037

MUESER RUTLEDGE CONSULTING ENGINEERS

14 PENN PLAZA – 225 W. 34TH STREET, NEW YORK, NY 10122

| SCALE | MADE BY | DATE | FILE NO. |
|---|---|---|---|
| GRAPHIC | B.B. | 2/18/04 | 10210 |
| | CHK'D BY K.R. | DATE 7/8/04 | DRAWING NO. |

BORING LOCATION PLAN

B-1

MUESER RUTLEDGE CONSULTING ENGINEERS

SHEET ____ OF ____

FILE 11173


MADE BY APS DATE 9/28/15

PROJECT CHROMIUM REMEDY SA-6


CHECKED BY ____ DATE ____

SUBJECT SOIL PROFILE

FIGURE S-1




(D) Compressible Layer








PLATE NO. 18

| CURVE NO. | INCREMENT FROM (TSF) | INCREMENT TO (TSF) |
|---|---|---|
| ① | 0.18 | 0.37 |
| ② | 0.73 | 1.46 |
| ③ | 11.69 | 23.39 |

SPECIMEN DESCRIPTION: SOFT BLACK ORGANIC SILTY CLAY, TRACE FINE SAND, FINE SAND POCKETS (OL)

STRATUM D

**PROPERTIES OF PLASTICITY LIMIT SPECIMEN**

UNIFIED SOILS CLASSIFICATION - OL
LIQUID LIMIT, $w_L$ = 36
PLASTICITY LIMIT, $w_p$ = 22
PLASTICITY INDEX, $I_p$ = 14
NATURAL WATER CONT., $\%_w$ = 42.9
LIQUIDITY INDEX, $(w-w_p)/I_p$ = 1.5
SPECIFIC GRAVITY, $G_s$ = 2.61

**PROPERTIES OF CONSOLIDATION SPECIMEN**

ELEVATION OF SPECIMEN = -3.2
DEPTH OF SPECIMEN (FT) = 16.0
DIAMETER OF SPECIMEN (IN) = 2.5
INITIAL THICKNESS OF SPECIMEN (IN) = 1.0045
INITIAL WATER CONTENT, % = 38.9
FINAL WATER CONTENT, % = 27.1
INITIAL DEGREE OF SATURATION, % = 91.8
FINAL DEGREE OF SATURATION, % = 92.8

— — — — INITIAL VOID RATIO, $e_o$ = 1.107
- - - - - - - FINAL VOID RATIO, $e_f$ = 0.761
ESTIMATED PRECONSOLIDATION STRESS (TSF), $P_c$ = 0.53
EXISTING OVERBURDEN STRESS (TSF), $P_o$ = 0.347
COMPRESSION INDEX, $C_c$ = 0.292
SWELLING INDEX, $C_s$ =0.06 REBOUND FROM e = 0.486

**STUDY AREA 7**

JERSEY CITY NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
225 WEST 34TH STREET, NEW YORK, N.Y. 10122


MADE BY. BEE/MM DATE: 01-22-04
CHKD BY. WJP DATE: 02-02-04

FILE NO. 10028

CONSOLIDATION TEST
BORING 120-SB-210D SAMPLE 1U

PLATE NO. 18

MRCE Form CONSOL-1








PLATE NO. 13

| CURVE NO. | INCREMENT FROM (TSF) | INCREMENT TO (TSF) |
|---|---|---|
| ① | 0.36 | 0.73 |
| ② | 1.46 | 2.91 |
| ③ | 2.91 | 5.82 |

SPECIMEN DESCRIPTION: STIFF BROWN PEAT (Pt)

STRATUM D

**PROPERTIES OF PLASTICITY LIMIT SPECIMEN**

UNIFIED SOILS CLASSIFICATION - Pt
LIQIUD LIMIT, $w_L$ = 541
PLASTICITY LIMIT, $w_P$ = 379
PLASTICITY INDEX, $I_P$ = 161
NATURAL WATER CONT., $\%_w$ = 229 6
LIQUIDITY INDEX, $(w-w_P)/I_P$ = -0.93
SPECIFIC GRAVITY, $G_s$ = 1.78

**PROPERTIES OF CONSOLIDATION SPECIMEN**

ELEVATION OF SPECIMEN = -5.0
DEPTH OF SPECIMEN (FT) = 19.5
DIAMETER OF SPECIMEN (IN) = 150
INITIAL THICKNESS OF SPECIMEN (IN) = 0.9946
INITIAL WATER CONTENT, % = 289.0
FINAL WATER CONTENT, % = 212.4
INITIAL DEGREE OF SATURATION, % = 91.8
FINAL DEGREE OF SATURATION, % = 94.7

INITIAL VOID RATIO, $e_o$ = 5.597
FINAL VOID RATIO, $e_f$ = 3.989
ESTIMATED PRECONSOLIDATION STRESS (TSF), $P_c$ = 1.4
EXISTING OVERBURDEN STRESS (TSF), $P_o$ = 0.52
COMPRESSION INDEX, $C_c$ = 3.62
SWELLING INDEX, $C_s$ = 0 58, REBOUND FROM e = 2.242

**STUDY AREA 7**

JERSEY CITY NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
225 WEST 34TH STREET, NEW YORK, N.Y. 10122

MADE BY: BEE DATE: 01-06-04
CHKD BY: WJP DATE: 01-27-04

FILE NO. 10028

**CONSOLIDATION TEST**
BORING 115-SB-211D SAMPLE 1U

PLATE NO. 13

MRCE Form CONSOL-1

# APPENDIX A

**MUESER RUTLEDGE CONSULTING ENGINEERS**

FILE 11173

MADE BY APS DATE 9/28/15

PROJECT CHROMIUM REMEDY SA-6

CHECKED BY ____ DATE ____

SUBJECT CALCULATION OF STRESSES

## APPENDIX A

① Using average Pc from consolidation tests:

Pc (SB-210D) = 0.53 tsf = 1060 psf

Pc (SB-211D) = 1.4 tsf = 2800 psf

Pc (average) = 1930 psf

② Using OCR from consolidation tests:

At ELEV. -2.5 ⇒ $\sigma'_v$ = 120pcf x 13.5 ft − 62.4pcf x 10 ft

= 1064 psf

OCR(SB-210D) = 1.77

OCR(SB-211D) = 2.69

OCR(average) = 2.23

1064 psf x 2.23 = 2372 psf

AVERAGE ① & ② = 2151 psf

③ Stress at Final Condition




Final Effective overburden stress:

$\sigma'_{vf}$ = 1064 + (1.5+0.5) x 125pcf


= 1314 psf < 1930 psf

Added soil avg height = 1.5'

Max. increase in grade = 0.5'

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\CURRENT DRAWINGS\3480150488-5710-GVD0-0000.dwg Fri, 12 May 2017 - 1:15pm charles.wingfield




# GAS VENT DETAIL

NTS

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480160544<br>DRAWING: 3480150488-5710-GVD0-0000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE, Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | SA-6 GAS VENT DETAIL<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 04/20/17 \| CHECKED/DATE: NW 04/20/17 | | |

# APPENDIX D

# DESIGN CHANGE BULLETIN LOG

| SA-6 North/South Field Change Log | | | | | |
|---|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** | **AOC Designation[1]** |
| **1** | **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentation Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. | SA-6 North & SA-6 South | A, C |
| **2** | **DC 2013-8-14 (HB Wall)** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. | North | A |
| **3** | **DC 2013-8-14 (Grouted Angles)** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only as clarification or response to RFI. | South | C |
| **4** | **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only as clarification or response to RFI. | South | C |
| **5** | **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only as clarification or response to RFI. | SA-6 North & SA-6 South | A, B, C, D, E |
| **6** | **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. | South | D, E |
| **7** | **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. | SA-6 North & SA-6 South | A, C |
| **7.1** | **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized based field observations and constructability review. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | South | C |
| **7.2** | **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. | North | A |
| **7.22** | **DC 2016-6-6** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 004. (Design Change ID changed from DC 2016-6-10 to DC 2016-6-6 to reflect actual date on Design Change form). | North | A |
| **7.3** | **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | South | C |
| **7.4** | **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | South | C |
| **7.4.1** | **DC 2016-5-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to address the elimination of a drop structure, the elimination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | South | C |
| **7.4.2** | **DC 2016-12-20** | This DCB documents a number of minor field changes that have been conveyed by the EOR to Entact during the course of the work and also includes revisions to the (E series) electrical drawings for both SA-6N and SA-6S. | Included as an attachment to Declaration 005. | SA-6 North & SA-6 South | A, C |
| **7.5** | **DC 2015-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA-6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | SA-6 North & SA-6 South | A, C |
| **8.1** | **DC 2013-8-14 (Surcharge)** | Modify surcharge pile toe of slope to reduce load on the bulkhead. | Submitted to all Parties on July 10, 2014. | South | C, D |
| **9** | **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS Site Vision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. | South | E |
| **10** | **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. | South | D, E |
| **11** | **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. | SA-6 North & SA-6 South | A, B, C, D, E |
| **12** | **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. | South | C, D |
| **13** | **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. | North | A |
| **14** | **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. | North | A |

| SA-6 North/South Field Change Log | | | | | |
|---|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** | **AOC Designation[1]** |
| **15** | **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only as clarification or response to RFI. | SA-6 North & SA-6 South | A, B, C, D, E |
| **16** | **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only as clarification or response to RFI. | South | E |
| **17** | **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Parties as Attachment to Declaration 004. | SA-6 North & SA-6 South | A, B, C, D, E |
| **18** | **DC 2014-12-23** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. | South | E |
| **19** | **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. | North | A, B |
| **20** | **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. | North | A |
| **21** | **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. | South | C |
| **22** | **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only as clarification or response to RFI. | North | B |
| **23** | **DC 2015-04-30** | A concrete protuberance was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only as clarification or response to RFI. | North | A |
| **26.1** | **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | SA-6 North & SA-6 South | A, C |
| **27** | **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. | South | C |
| **28** | **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. | South | C |
| **29** | **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. | South | C, D |
| **30** | **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Included as an attachment to Declaration 005. | South | C, D, E |
| **30.1** | **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | Included as an attachment to Declaration 005. | South | C, D, E |

| SA-6 North/South Field Change Log | | | | | |
|---|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** | **AOC Designation[1]** |
| **30.2** | **September 2016-South** | The design change documents revisions to the final grading and SESCP drawings on the SA-6 South Chromium Remedy. Minor grading changes were performed in the field to improve surface drainage. In addition, the extent of demarcation fabric, crushed stone and DGA placed over the Development Area was increased to meet historic fill regulations. SESCP changes included installation of crushed stone toe drain along SA-7, installation of erosion mat, installation of supplemental diversion berms, and installation of stone check dams. | Included as an attachment to Declaration 005. | South | C, D, E |
| **32** | **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. | South | E |
| **33** | **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. | North | B |
| **34** | **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. | South | C |
| **35** | **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. | South | C |
| **35.2** | **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. | South | C |
| **35.3** | **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only as clarification or response to RFI. | South | C |
| **36** | **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. | South | C |
| **37** | **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only as clarification or response to RFI. | South | C |
| **37.2** | **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only as clarification or response to RFI. | South | C |
| **38** | **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only as clarification or response to RFI. | North | A |
| **39** | **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only as clarification or response to RFI. | South | C |
| **41** | **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. | SA-6 North & SA-6 South | A, C |
| **42** | **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longer required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. | SA-6 North & SA-6 South | A, C |
| **43** | **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. | South | C |
| **45** | **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Parties as Attachment to Declaration 004. | North | A |

| SA-6 North/South Field Change Log | | | | | |
|---|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** | **AOC Designation[1]** |
| **46** | **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. | SA-6 North & SA-6 South | A, C |
| **47** | **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Parties as Attachment to Declaration 003. | North | B |
| **47.1** | **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Parties as Attachment to Declaration 003. | North | B |
| **48** | **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. | South | E |
| **48.1** | **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only as clarification or response to RFI. | South | E |
| **50** | **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. | SA-6 North & SA-6 South | A, C |
| **51** | **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only as clarification or response to RFI. | North | B |
| **52** | **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance with ASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. | North | A |
| **53** | **DC 2015-11-30** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Parties as Attachment to Declaration 003. | North | B |
| **54** | **DC 2016-02-02** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Parties as Attachment to Declaration 004. (Design Change ID changed from DC 2016-02-03 to DC 2016-02-02 to reflect actual date on Design Change form). | North | A |
| **54.1** | **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Parties as Attachment to Declaration 004. | North | A |
| **54.2** | **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Parties as Attachment to Declaration 004. | North | A |
| **54.3** | **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | Submitted to Parties as Attachment to Declaration 004. | North | A |

| SA-6 North/South Field Change Log | | | | | |
|---|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** | **AOC Designation[1]** |
| **54.4** | **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. | North | A |
| **54.5** | **DC 2016-7-14** | Design change documenting minor field changes needed to achieve positive drainage in the cap area. | Included as an attachment to November 2016 monthly progress report and included in the finalized Declaration 004. | North | A |
| **54.6** | **September 2016-North** | The design change documents revisions to the interim/final grading and SESCP drawings on the SA-6 North Chromium Remedy. Minor grading changes were performed in the field to improve surface drainage pending redevelopment. SESCP changes included installation of crushed stone toe drain along SA-7, installation of erosion mat, installation of supplemental diversion berms, and installation of stone check dams. | Included as an attachment to Declaration 005. | North | A |
| **55** | **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only as clarification or response to RFI. | SA-6 North & SA-6 South | A, C |
| **56** | **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. The Parties did not agree to implement this DCB as drafted. However, Plaintiffs and Honeywell subsequently held discussions and DCB 2016-4-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. | SA-6 North & SA-6 South | A, C |
| **57** | **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. | SA-6 North & SA-6 South | A, C |
| **58** | **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. | South | C |
| **59** | **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. | SA-6 North & SA-6 South | A, C |
| **60** | **DC 2016-05-31** | This DCB documents the vault sketch Drawing C-310 (Rev 5, 5/31/16) | Submitted to Contractor only as clarification or response to RFI. | South | C |
| **61** | **DC 2016-11-09** | The limits and the type of restoration north of the SA-6N cap has been modified to be integrated with the SA-6N Non Chrome Remedy. | Included as an attachment to Declaration 005. | North | B |
| **62** | **DC 2016-7-12** | DC 2016-7-12 clarifies the limit of GCL deployment and the location of the sand bentonite plug in the SA-6 North cap. | Included as an attachment to July 2016 Monthly Progress Report. | North | A |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

1) Area of Concern (AOC) Designations:
   A = SA-6 North Open Space Area
   B = SA-6 North Development Area
   C = SA-6 South Open Space AOC
   D = SA-6 South Kellogg Street Development AOC
   E = SA-6 South Site 163 Development AOC

**APPENDIX E**

**MONITORING WELL INSTALLATION PERMITS/RECORDS/FORM B'S**
**(CD ONLY)**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601094**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601396 Northing (Y): 685464
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 073-MW-06

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601094**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601094**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601396 Northing (Y): 685464
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 17, 2016

**DATE WELL COMPLETED:** February 17, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-06

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 20 Finished Well Depth (ft.): 20 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 20 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 19 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 20 | 6 | 2 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 6 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 14: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 14 - 16: BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 16 - 20: BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601093**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601451 Northing (Y): 685358
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 073-MW-07

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Jerry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601093**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601093**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601451 Northing (Y): 685358
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 23, 2016

**DATE WELL COMPLETED:** February 23, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-07

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 18 Finished Well Depth (ft.): 18 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 18 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 18 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 18 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - .5: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines CONCRETE |
| .5 - 15: BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 15 - 18: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601092**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601621 Northing (Y): 685234
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 073-MW-08

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601092**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601092**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601621 Northing (Y): 685234
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 12, 2016

**DATE WELL COMPLETED:** February 12, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-08

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17.5 Finished Well Depth (ft.): 17 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.5 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 17 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 6 | 2 | 0 | 55 | 3 |
| Gravel Pack | 4 | 17 | 6 | 2 | MORIE#1 | | |
| Gravel Pack | 17 | 17.5 | 6 | 0 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5.2 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GOS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 14: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 14 - 17.5: BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601085**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602732 Northing (Y): 684286
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 124-MW-12

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 1, 2016
**Expiration Date:** January 31, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601085**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601085**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602732 Northing (Y): 684286
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 19, 2016

**DATE WELL COMPLETED:** February 19, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-12

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 14.5 Finished Well Depth (ft.): 14.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 14.5 | 6 | | |
| Casing | 0 | 4.5 | 2 | PVC | SH40 |
| Screen | 4.5 | 14.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3.5 | 6 | 2 | 0 | 50 | 2.75 |
| Gravel Pack | 3.5 | 14.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 5: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 8: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |
| 8 - 14.5: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601084**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603014 Northing (Y): 684268
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 124-MW-13

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 1, 2016
**Expiration Date:** January 31, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601084**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601084**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603014 Northing (Y): 684268
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 10, 2016

**DATE WELL COMPLETED:** February 10, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-13

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 13 Finished Well Depth (ft.): 13 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 13 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 13 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 13 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 3.1 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 12: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 12 - 13: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601087**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602448 Northing (Y): 684489
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 125-MW-02

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 1, 2016
**Expiration Date:** January 31, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601087**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601087**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602448 Northing (Y): 684489
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 19, 2016

**DATE WELL COMPLETED:** February 19, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 125-MW-02

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 13.5 Finished Well Depth (ft.): 13.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 13.5 | 6 | | |
| Casing | 0 | 3.5 | 2 | PVC | SH40 |
| Screen | 3.5 | 13.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 13.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 1: BLACK GM - Silty gravels, gravel-sand-silt mixtures ASPHALT |
| 1 - 4: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 4 - 13.5: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601086**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602577 Northing (Y): 684585
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 125-MW-03

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 1, 2016
**Expiration Date:** January 31, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601086**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601086**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602577 Northing (Y): 684585
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 11, 2016

**DATE WELL COMPLETED:** February 11, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 125-MW-03

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 11.5 Finished Well Depth (ft.): 11.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 11.5 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 11.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 11.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 2.1 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 11: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 11 - 11.5: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601091**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 4 Block: 24601

Easting (X): 601865 Northing (Y): 685020
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 134-MW-03

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Terry D. Pilawski

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601091**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601091**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 4 Block: 24601

Easting (X): 601865 Northing (Y): 685020
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 16, 2016

**DATE WELL COMPLETED:** February 16, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-03

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17 Finished Well Depth (ft.): 17 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 17 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 17 | 6 | 2 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5.2 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMENSIBLW
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 14: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 14 - 17: BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601090**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602016 Northing (Y): 685002
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 134-MW-04

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Terry D. Pilawski

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601090**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601089**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Development

Address: 80 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602106 Northing (Y): 684819
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 140-MW-09

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601089**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601089**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Development

Address: 80 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602106 Northing (Y): 684819
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 12, 2016

**DATE WELL COMPLETED:** February 12, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-09

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 14.5 Finished Well Depth (ft.): 14 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 14.5 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 14 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 6 | 2 | 0 | 55 | 3 |
| Gravel Pack | 4 | 14 | 6 | 2 | MORIE#1 | | |
| Gravel Pack | 14 | 14.5 | 6 | 0 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4.7 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 1: BLACK GW - Well-graded gravels and gravel-sand mixtures, little or no fines ASPHALT |
| 1 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 10: BRN SM - Silty sands, sand-silt mixtures |
| 10 - 14.5: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601088**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Development

Address: 80 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602287 Northing (Y): 684774
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 140-MW-10

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601088**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601088**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Development

Address: 80 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602287 Northing (Y): 684774
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 11, 2016

**DATE WELL COMPLETED:** February 11, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-10

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 12 Finished Well Depth (ft.): 12 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 12 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 12 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 12 | 6 | 2 | MORIE31 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 11: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 11 - 12: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines CRUSHED CONCRETE |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601098**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601868 Northing (Y): 685185
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 22, 2016

**DATE WELL COMPLETED:** February 22, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-V09R

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17.5 Finished Well Depth (ft.): 17.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.5 | 6 | | |
| Casing | 0 | 3.5 | 2 | PVC | SH40 |
| Screen | 3.5 | 17.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 17.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4.5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 17.5: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601098**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601868 Northing (Y): 685185
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 134-MW-V09R

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Terry D. Pilawski

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601098**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601099**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 75 Kellogg St

County: Hudson Municipality: Jersey City Lot: 11 Block: 24601

Easting (X): 601575 Northing (Y): 685166
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 163-MW-03

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 1, 2016
**Expiration Date:** January 31, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601099**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601100**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: 80 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602412 Northing (Y): 684614
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** 140-MW-11

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** MONITORING

Other Use(s):

Diameter (in.): 2

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Air Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** February 2, 2016
**Expiration Date:** February 1, 2017

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601100**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 200 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000000927 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 200 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 1

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601094
2. Site Well Number (As shown on application or plans): 073-MW-06
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-52.52 Longitude: West 074-06-20.63
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685465 East 601414
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 11.50
   Elevation Top of Outer casing: 11.72 Elevation of ground: 9.01
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 200 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000000927 Case Tracking Number(s): N.A

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 200 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 1

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601093
2. Site Well Number (As shown on application or plans): 073-MW-07
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-51.46 Longitude: West 074-06-20.16
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685359 East 601451
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.38
   Elevation Top of Outer casing: 11.24 Elevation of ground: 9.71 (High side) / 7.30 (Low side)
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 200 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000000927 Case Tracking Number(s): N.A

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 200 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 1

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601092
2. Site Well Number (As shown on application or plans): 073-MW-08
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-50.23 Longitude: West 074-06-17.95
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685235 East 601621
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.57
   Elevation Top of Outer casing: 11.01 Elevation of ground: 7.47
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 427 Rte. 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008741 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 427 Rte. 440, Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 8

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601085
2. Site Well Number (As shown on application or plans): 124-MW-12
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-40.77 Longitude: West 074-06-03.53
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684282 East 602736
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 11.97
   Elevation Top of Outer casing: 13.37 Elevation of ground: 9.89
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 427 Rte. 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008741 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 427 Rte. 440, Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 8

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601084
2. Site Well Number (As shown on application or plans): 124-MW-13
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-40.61 Longitude: West 074-05-59.91
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684267 East 603014
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 13.02
   Elevation Top of Outer casing: 13.22 Elevation of ground: 9.52
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 60 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008742 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 60 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 7

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601087
2. Site Well Number (As shown on application or plans): 125-MW-02
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-42.82 Longitude: West 074-06-07.22
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684488 East 602451
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 8.07
   Elevation Top of Outer casing: 8.44 Elevation of ground: 8.45
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Glen J. Lloyd Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 60 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008742 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 60 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 7

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601086
2. Site Well Number (As shown on application or plans): 125-MW-03
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-43.77 Longitude: West 074-06-05.58
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684585 East 602577
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 11.27
   Elevation Top of Outer casing: 11.54 Elevation of ground: 7.60
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Glen J. Lloyd Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 100 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 033312 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 100 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 4

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601091
2. Site Well Number (As shown on application or plans): 134-MW-03
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-48.41 Longitude: West 074-06-14.64
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685051 East 601877
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.40
   Elevation Top of Outer casing: 11.01 Elevation of ground: 7.44
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Glen J. Lloyd Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

Date Stamp
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 100 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 033312 Case Tracking Number(s): N.A.

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 100 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 5

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601090
2. Site Well Number (As shown on application or plans): 134-MW-04
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-48.07 Longitude: West 074-06-12.76
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685018 East 602022
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 9.85
   Elevation Top of Outer casing: 10.63 Elevation of ground: 8.74 (High side) / 6.86 (Low side)
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Glen J. Lloyd Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

# Monitoring Well Certification Form B - Location Certification

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 80 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 003846 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 80 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 6

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601089
2. Site Well Number (As shown on application or plans): 140-MW-09
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-46.10 Longitude: West 074-06-11.68
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684819 East 602106
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.72
   Elevation Top of Outer casing: 10.95 Elevation of ground: 8.65
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

Date Stamp
(For Department use only)

## SECTION A. SITE NAME AND LOCATION

Site Name: Development AOC Shallow Ground Water Wells 02-Site

List all AKAs: Honeywell SA6-South

Street Address: 80 Kellogg St.

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 003846 Case Tracking Number(s): N.A.

## SECTION B. WELL OWNER AND LOCATION

1. Name of Well Owner Honeywell
2. Well Location (Street Address) 80 Kellogg St., Jersey City, Hudson County, NJ
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 6

## SECTION C. WELL LOCATION SPECIFICS

1. Well Permit Number (This number must be permanently affixed to the well casing): E201601088
2. Site Well Number (As shown on application or plans): 140-MW-10
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-45.77 Longitude: West 074-06-09.24
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684786 East 602294
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.49
   Elevation Top of Outer casing: 10.77 Elevation of ground: 8.46 (High side) / 6.64 (Low side)
   *Check one*: ☐ NAVD 88 ☒ NVGD29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

## SECTION D. LAND SURVEYOR'S CERTIFICATION

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date 4/13/16

Surveyor's Name: Glen J. Lloyd License Number: GS037598

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 2AGA27986500

Mailing Address 331 Newman Springs Road Suite 203

City/Town: Red Bank State New Jersey Zip Code: 07701

Phone Number 732-383-1950 Ext.: 3466 Fax: 732-383-1984

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506364**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603290 Northing (Y): 684201
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-11

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506364**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506364**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603290 Northing (Y): 684201
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 13, 2015

**DATE WELL COMPLETED:** July 13, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-11

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 9.5 Finished Well Depth (ft.): 9.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 9.5 | 8 | | |
| Casing | 0 | 4.5 | 4 | Stainless Steel | SH40 |
| Screen | 4.5 | 9.5 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 2.5 | 8 | 4 | 1.2 | 55 | 3 |
| Gravel Pack | 2.5 | 3.5 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 3.5 | 9.5 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 2 ft. below land surface
Water Level Measure Tool: Tape
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Moble B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 1: BLK OT - Other ASPHALT |
| 1 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 9.5: BRN SM - Silty sands, sand-silt mixtures |

| **ADDITIONAL INFORMATION:** |
|---|

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506365**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603277 Northing (Y): 684208
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-12

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506365**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506365**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603277 Northing (Y): 684208
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 9, 2015

**DATE WELL COMPLETED:** July 9, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-12

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 9.46 Finished Well Depth (ft.): 9.46 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 9.46 | 8 | | |
| Casing | 0 | 4.46 | 4 | Stainless Steel | SH40 |
| Screen | 4.46 | 9.46 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 1.46 | 8 | 4 | 1 | 31 | 1.5 |
| Gravel Pack | 1.46 | 3.46 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 3.46 | 9.46 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 7.5 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 9.46: GRAY-BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506366**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602902 Northing (Y): 684414
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-13

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506366**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506366**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602894 Northing (Y): 684392
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 10, 2015

**DATE WELL COMPLETED:** July 10, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-13

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 9.58 Finished Well Depth (ft.): 9.58 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 9.58 | 8 | | |
| Casing | 0 | 4.58 | 4 | Stainless Steel | SH40 |
| Screen | 4.58 | 9.58 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 2.58 | 8 | 4 | 1.2 | 30 | 1.75 |
| Gravel Pack | 2.58 | 3.58 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 3.58 | 9.58 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 2 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 9.58: GRAY-BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506367**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602908 Northing (Y): 684421
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-14

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506367**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506367**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602908 Northing (Y): 684421
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 10, 2015

**DATE WELL COMPLETED:** July 10, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-14

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 14.1 Finished Well Depth (ft.): 14.1 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 14.1 | 8 | | |
| Casing | 0 | 9.1 | 4 | Stainless Steel | SH40 |
| Screen | 9.1 | 14.1 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 6.1 | 8 | 4 | 6 | 130 | 7.33 |
| Gravel Pack | 6.1 | 8.1 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 8.1 | 14.1 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 11.2 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 5: BRN SM - Silty sands, sand-silt mixtures FILL |
| 5 - 14.1: RD-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506368**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602498 Northing (Y): 684736
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-15

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506368**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506368**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602498 Northing (Y): 684736
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 7, 2015

**DATE WELL COMPLETED:** July 7, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-15

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 10.1 Finished Well Depth (ft.): 10.1 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 10.1 | 8 | | |
| Casing | 0 | 5.1 | 4 | Stainless Steel | SH40 |
| Screen | 5.1 | 10.1 | 4 | Stanless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3.1 | 8 | 4 | 1 | 65 | 3.75 |
| Gravel Pack | 3.1 | 5.1 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 5.1 | 10.1 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 7 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 10.1: BRN GM - Silty gravels, gravel-sand-silt mixtures Fill

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506369**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602509 Northing (Y): 684751
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-16

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506369**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506369**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602509 Northing (Y): 684751
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 8, 2015

**DATE WELL COMPLETED:** July 8, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-16

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 18.66 Finished Well Depth (ft.): 18.66 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 18.66 | 8 | | |
| Casing | 0 | 13.66 | 4 | Stainless Steel | SH40 |
| Screen | 13.66 | 18.66 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10.66 | 8 | 4 | 10 | 230 | 13 |
| Gravel Pack | 10.66 | 12.66 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 12.66 | 18.66 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 14.7 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 8: BRN SM - Silty sands, sand-silt mixtures |
| 8 - 15: BRN GM - Silty gravels, gravel-sand-silt mixtures |
| 15 - 18.66: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506370**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 601978 Northing (Y): 685121
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-17

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506370**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506370**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 601978 Northing (Y): 685121
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** June 30, 2015

**DATE WELL COMPLETED:** July 1, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-17

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 12 Finished Well Depth (ft.): 12 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 12 | 8 | | |
| Casing | 0 | 7 | 4 | Stainless Steel | SH40 |
| Screen | 7 | 12 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 8 | 4 | 0.75 | 85 | 4.75 |
| Gravel Pack | 4 | 6 | 8 | 4 | MORIE #00 | | |
| Gravel Pack | 6 | 12 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506371**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 601989 Northing (Y): 685136
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-18

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506371**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506371**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 601989 Northing (Y): 685136
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 6, 2015

**DATE WELL COMPLETED:** July 7, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-18

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 16.2 Finished Well Depth (ft.): 16.2 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 16.2 | 8 | | |
| Casing | 0 | 11.2 | 4 | Stainless Steel | SH40 |
| Screen | 11.2 | 16.2 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 9.2 | 8 | 4 | 1.1 | 200 | 11 |
| Gravel Pack | 9.2 | 11.2 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 11.2 | 16.2 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 8 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 16.2: BRN GM - Silty gravels, gravel-sand-silt mixtures fill

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506372**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 200 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601501 Northing (Y): 685587
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-19

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506372**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506372**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 200 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601501 Northing (Y): 685587
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 1, 2015

**DATE WELL COMPLETED:** July 1, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-19

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 10.4 Finished Well Depth (ft.): 10.4 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 10.4 | 8 | | |
| Casing | 0 | 5.4 | 4 | Stainless Steel | SH40 |
| Screen | 5.4 | 10.4 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3.4 | 8 | 4 | 1 | 70 | 4 |
| Gravel Pack | 3.4 | 5.4 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 5.4 | 10.4 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 7 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 10.4: BRN GM - Silty gravels, gravel-sand-silt mixtures Fill

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506373**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: BAYFRONT REDEVELOPMENT

Address: 200 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601504 Northing (Y): 685584
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** PZ-20

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 4

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** June 10, 2015
**Expiration Date:** June 9, 2016

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506373**

# WELL PERMIT

%%:activity_class_well%%

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506373**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 200 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601504 Northing (Y): 685584
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 2, 2015

**DATE WELL COMPLETED:** July 2, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-20

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17.3 Finished Well Depth (ft.): 17.3 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.3 | 8 | | |
| Casing | 0 | 12.3 | 4 | Stainless Steel | SH40 |
| Screen | 12.3 | 17.3 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10.3 | 8 | 4 | 1 | 220 | 12.5 |
| Gravel Pack | 10.3 | 12.3 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 12.3 | 17.3 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 12 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures Fill |
| 12 - 17.3: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201514336**

# WELL PERMIT

New Well

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Bayfront Redevelopment

Address: Kellogg St

County: Hudson Municipality: Jersey City Lot: 11 Block: 24601

Easting (X): 601529 Northing (Y): 685182
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** DW-8

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** DEWATERING

Other Use(s):

Diameter (in.): 6

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 50

Case ID Number:

Pump Capacity (gpm): 20

Deviation Requested: N

Drilling Method: Mud Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Terry D. Pilawski

**Approval Date:** December 1, 2015
**Expiration Date:** November 30, 2016

Approved by the authority of:
Bob Martin
Commissioner

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201514336**

# WELL PERMIT

New Well

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201312361**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Former Roosvelt Bowling Lanes

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603064 Northing (Y): 684266
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** DW-01

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** DEWATERING

Other Use(s):

Diameter (in.): 6

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 50

Case ID Number:

Pump Capacity (gpm): 10

Deviation Requested: N

Drilling Method: Mud Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** August 28, 2013
**Expiration Date:** August 28, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201312361**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313208**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348
**Permit Issued to:** B & B DRILLING INC
**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC
Organization: BAYFRONT REDEVELOPMENT, LLC
Address: 101 COLUMBIA ROAD
City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Former Delphic Consolidated
Address: 60 Kellogg St Well dischaged to on-site treatment
County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602394 Northing (Y): 684743
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** DW-02

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** DEWATERING
Other Use(s):
Diameter (in.): 6
Regulatory Program Requiring Wells/Borings:
Depth (ft.): 50
Case ID Number:
Pump Capacity (gpm): 10
Deviation Requested: N
Drilling Method: Mud Rotary
Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** September 11, 2013
**Expiration Date:** September 11, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313208**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313209**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Former Old Dominion

Address: 100 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602394 Northing (Y): 684743
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** DW-03

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** DEWATERING

Other Use(s):

Diameter (in.): 6

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 50

Case ID Number:

Pump Capacity (gpm): 10

Deviation Requested: N

Drilling Method: Mud Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** September 11, 2013
**Expiration Date:** September 11, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313209**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313210**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Former ABF Trucking

Address: 80 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602047 Northing (Y): 685060
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** DW-04

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** DEWATERING

Other Use(s):

Diameter (in.): 6

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 50

Case ID Number:

Pump Capacity (gpm): 10

Deviation Requested: N

Drilling Method: Mud Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** September 11, 2013
**Expiration Date:** September 11, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313210**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313226**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Former Boatyard

Address: 150 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 2 Block: 24601

Easting (X): 601735 Northing (Y): 685278
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** DW-O5

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** DEWATERING

Other Use(s):

Diameter (in.): 6

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 50

Case ID Number:

Pump Capacity (gpm): 10

Deviation Requested: N

Drilling Method: Mud Rotary

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** September 11, 2013
**Expiration Date:** September 11, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313226**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201514336**

# WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: Kellogg St

County: Hudson Municipality: Jersey City Lot: 11 Block: 24601

Easting (X): 601529 Northing (Y): 685182
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** December 18, 2015

**DATE WELL COMPLETED:** December 23, 2015

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-8

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 48 Finished Well Depth (ft.): 48 Well Surface: 3 ft. Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.5 | 14 | | |
| Borehole | 17.5 | 48 | 10 | | |
| Casing | 0 | 23 | 6 | PVC | SC40 |
| Casing | 0 | 17.5 | 10 | Steel | SC40 |
| Screen | 23 | 48 | 6 | PVC | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 22 | 10 | 6 | 0 | 630 | 35 |
| Grout | 0 | 17.5 | 14 | 10 | 0 | 750 | 42 |
| Gravel Pack | 22 | 48 | 10 | 6 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**RECORD OF TEST**
Test Date: December 18, 2015
Pump Equipment: Submersible
Well Yield: 10 gpm
Static Water Level: 8 ft. below land surface
Pumping Water Level: 18 ft. below land surface

**ATTACHMENTS**

**PUMPING EQUIPMENT**
Installed: Not Installed
Installer's Name: ,
Pump Type:
Depth to Pump: _ ft. below land surface
Pump Capacity: _ gpm
Total Design Head: _ ft.
Pump Horsepower: _ hp
If pump tested Discharge Rate: 10 gpm
Duration of Test: 1 hours

| **GEOLOGIC LOG** |
|---|
| 0 - 2: GRAY GM - Silty gravels, gravel-sand-silt mixtures |
| 2 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 10: BRN SM - Silty sands, sand-silt mixtures |
| 10 - 16: BRN/RED ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 16 - 19: BRN/BLK PT - Peat, muck, and other highly organic soils |
| 19 - 24: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 24 - 35: GRAY SM - Silty sands, sand-silt mixtures |
| 35 - 48: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201312361**

# WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Former Roosvelt Bowling Lanes

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603064 Northing (Y): 684266
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** September 9, 2013

**DATE WELL COMPLETED:** September 12, 2013

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-01

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 44.5 Finished Well Depth (ft.): 44.5 Well Surface: 3 ft. Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 44.5 | 10 | | |
| Borehole | 0 | 13 | 14 | | |
| Casing | 0 | 19.5 | 6 | PVC | SH40 |
| Casing | 0 | 13 | 10 | Steel | SH40 |
| Screen | 19.5 | 44.5 | 6 | PVC | 0.020" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 16.5 | 10 | 6 | 0 | 470 | 27 |
| Grout | 0 | 13 | 14 | 10 | 0 | 600 | 34 |
| Gravel Pack | 16.5 | 44.5 | 10 | 6 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**RECORD OF TEST**
Test Date: September 12, 2014
Pump Equipment: AIR LIFT
Well Yield: 10 gpm
Static Water Level: 4.7 ft. below land surface
Pumping Water Level: 30 ft. below land surface

**ATTACHMENTS**

**PUMPING EQUIPMENT**
Installed: Installed by Others
Installer's Name: ,
Pump Type:
Depth to Pump: _ ft. below land surface
Pump Capacity: _ gpm
Total Design Head: _ ft.
Pump Horsepower: _ hp
If pump tested Discharge Rate: _ gpm
Duration of Test: _ hours

| **GEOLOGIC LOG** |
|---|
| 0 - 2: GRAY OT - Other CONCRETE |
| 2 - 6: BRN GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |
| 6 - 10: BLK SM - Silty sands, sand-silt mixtures |
| 10 - 12: BLK ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 12 - 15.5: BRN PT - Peat, muck, and other highly organic soils |
| 15.5 - 17: RED-BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 17 - 44.5: RED SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313208**

# WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Former Delphic Consolidated

Address: 60 Kellogg St Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602394 Northing (Y): 684743
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** September 18, 2013

**DATE WELL COMPLETED:** September 23, 2013

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-02

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 46 Finished Well Depth (ft.): 46 Well Surface: 3 ft. Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 46 | 10 | | |
| Borehole | 0 | 14 | 14 | | |
| Casing | 0 | 21 | 6 | PVC | SH40 |
| Casing | 0 | 14 | 10 | Steel | SH40 |
| Screen | 21 | 46 | 6 | PVC | 0.020" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 18 | 10 | 6 | 0 | 515 | 29 |
| Grout | 0 | 14 | 14 | 10 | 0 | 600 | 34 |
| Gravel Pack | 18 | 46 | 10 | 6 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**RECORD OF TEST**
Test Date: September 23, 2014
Pump Equipment: AIR LIFT
Well Yield: 10 gpm
Static Water Level: 4.9 ft. below land surface
Pumping Water Level: 30 ft. below land surface

**ATTACHMENTS**

**PUMPING EQUIPMENT**
Installed: Installed by Others
Installer's Name: ,
Pump Type:
Depth to Pump: _ ft. below land surface
Pump Capacity: _ gpm
Total Design Head: _ ft.
Pump Horsepower: _ hp
If pump tested Discharge Rate: _ gpm
Duration of Test: _ hours

| **GEOLOGIC LOG** |
|---|
| 0 - 2: BLK OT - Other ASPHALT/CONCRETE |
| 2 - 6: BRN GP - Poorly graded gravels and gravel-sand mixtures, little or no fines FILL |
| 6 - 12: GRAY SM - Silty sands, sand-silt mixtures |
| 12 - 12.6: GRAY ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 12.6 - 17: BRN PT - Peat, muck, and other highly organic soils |
| 17 - 21: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 21 - 46: RED SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313209**

# WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Former Old Dominion

Address: 100 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602394 Northing (Y): 684743
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** June 4, 2014

**DATE WELL COMPLETED:** June 6, 2014

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-03

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 46 Finished Well Depth (ft.): 46 Well Surface: 3 ft. Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 46 | 10 | | |
| Borehole | 0 | 15.5 | 14 | | |
| Casing | 0 | 21 | 6 | PVC | SH40 |
| Casing | 0 | 15.5 | 10 | Steel | SH40 |
| Screen | 21 | 46 | 6 | PVC | 0.020" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 18 | 10 | 6 | 0 | 520 | 30 |
| Grout | 0 | 15.5 | 14 | 10 | 0 | 660 | 37 |
| Gravel Pack | 18 | 46 | 10 | 6 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**RECORD OF TEST**
Test Date: June 6, 2014
Pump Equipment: AIR LIFT
Well Yield: 10 gpm
Static Water Level: 8 ft. below land surface
Pumping Water Level: 40 ft. below land surface

**ATTACHMENTS**

**PUMPING EQUIPMENT**
Installed: Not Installed
Installer's Name: ,
Pump Type:
Depth to Pump: _ ft. below land surface
Pump Capacity: _ gpm
Total Design Head: _ ft.
Pump Horsepower: _ hp
If pump tested Discharge Rate: _ gpm
Duration of Test: _ hours

| **GEOLOGIC LOG** |
|---|
| 0 - 1: BLK GP - Poorly graded gravels and gravel-sand mixtures, little or no fines ASPHALT |
| 1 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 10: GRAY ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 10 - 13: GRAY SM - Silty sands, sand-silt mixtures |
| 13 - 16: BRN-BLK PT - Peat, muck, and other highly organic soils |
| 16 - 20: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 20 - 46: RED SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313210**

# WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Former ABF Trucking

Address: 80 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602047 Northing (Y): 685060
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** May 12, 2014

**DATE WELL COMPLETED:** May 15, 2014

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-04

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 48 Finished Well Depth (ft.): 48 Well Surface: 3 ft. Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 48 | 10 | | |
| Borehole | 0 | 17 | 14 | | |
| Casing | 0 | 23 | 6 | PVC | SH40 |
| Casing | 0 | 17 | 10 | Steel | SH40 |
| Screen | 23 | 48 | 6 | PVC | 0.020" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 22 | 10 | 6 | 0 | 630 | 35 |
| Grout | 0 | 17 | 14 | 10 | 0 | 600 | 34 |
| Gravel Pack | 22 | 48 | 10 | 6 | #1 MORIE | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**RECORD OF TEST**
Test Date: May 15, 2014
Pump Equipment: AIR LIFT
Well Yield: 13 gpm
Static Water Level: 8 ft. below land surface
Pumping Water Level: 20 ft. below land surface

**ATTACHMENTS**

**PUMPING EQUIPMENT**
Installed: Installed by Others
Installer's Name: ,
Pump Type:
Depth to Pump: _ ft. below land surface
Pump Capacity: _ gpm
Total Design Head: _ ft.
Pump Horsepower: _ hp
If pump tested Discharge Rate: _ gpm
Duration of Test: _ hours

| **GEOLOGIC LOG** |
|---|
| 0 - 1: BLK GW - Well-graded gravels and gravel-sand mixtures, little or no fines ASPHALT |
| 1 - 5: BRN GP - Poorly graded gravels and gravel-sand mixtures, little or no fines FILL |
| 5 - 10: BRN SM - Silty sands, sand-silt mixtures |
| 10 - 14: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 14 - 16: BLK ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 16 - 20: BRN PT - Peat, muck, and other highly organic soils |
| 20 - 24: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 24 - 40: RED-BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 40 - 48: RED-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313210**

# WELL RECORD

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313226**

# WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Former Boatyard

Address: 150 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 2 Block: 24601

Easting (X): 601735 Northing (Y): 685278
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 28, 2014

**DATE WELL COMPLETED:** March 5, 2014

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-O5

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 50 Finished Well Depth (ft.): 50 Well Surface: 2.5 ft. Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 50 | 10 | | |
| Borehole | 0 | 19.5 | 14 | | |
| Casing | 0 | 25 | 6 | PVC | SC40 |
| Casing | 0 | 19.5 | 10 | Steel | SH40 |
| Screen | 25 | 50 | 6 | PVC | 0.020" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 24 | 10 | 6 | 0 | 685 | 39 |
| Grout | 0 | 19.5 | 14 | 10 | 0 | 835 | 47 |
| Gravel Pack | 24 | 50 | 10 | 6 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**RECORD OF TEST**
Test Date: March 5, 2014
Pump Equipment: AIR LIFT
Well Yield: 20 gpm
Static Water Level: 6.7 ft. below land surface
Pumping Water Level: 25 ft. below land surface

**ATTACHMENTS**

**PUMPING EQUIPMENT**
Installed: Installed by Others
Installer's Name: ,
Pump Type:
Depth to Pump: _ ft. below land surface
Pump Capacity: _ gpm
Total Design Head: _ ft.
Pump Horsepower: _ hp
If pump tested Discharge Rate: _ gpm
Duration of Test: _ hours

| **GEOLOGIC LOG** |
|---|
| 0 - 1: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines CONCRETE |
| 1 - 7: BRN GP - Poorly graded gravels and gravel-sand mixtures, little or no fines FILL |
| 7 - 12: BRN SM - Silty sands, sand-silt mixtures |
| 12 - 16: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 16 - 18: BLK ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 18 - 21: BRN PT - Peat, muck, and other highly organic soils |
| 21 - 30: RED-BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 30 - 42: BRN SM - Silty sands, sand-silt mixtures |
| 42 - 50: GRAY ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313226**

# WELL RECORD

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601084** |
| Owner's Well Number (as shown on the application or plans: | **124-MW-13** |
| Well Completion Date: | **February 10, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **13 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **9 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **3.1 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **0.5 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN E. BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601084**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603014 Northing (Y): 684268
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 10, 2016

**DATE WELL COMPLETED:** February 10, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-13

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 13 Finished Well Depth (ft.): 13 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 13 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 13 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 13 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 3.1 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 12: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 12 - 13: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601085** |
| Owner's Well Number (as shown on the application or plans: | **124-MW-12** |
| Well Completion Date: | **February 19, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **14.5 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4.5 ft** |
| Screen Length: | **10 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **5 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**GORDON BLEWETT** 

Name (type or print) Signature

Certification or License No. **0021852**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601085**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602732 Northing (Y): 684286
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 19, 2016

**DATE WELL COMPLETED:** February 19, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-12

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 14.5 Finished Well Depth (ft.): 14.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 14.5 | 6 | | |
| Casing | 0 | 4.5 | 2 | PVC | SH40 |
| Screen | 4.5 | 14.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3.5 | 6 | 2 | 0 | 50 | 2.75 |
| Gravel Pack | 3.5 | 14.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 5: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 8: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |
| 8 - 14.5: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601086** |
| Owner's Well Number (as shown on the application or plans: | **125-MW-03** |
| Well Completion Date: | **February 11, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **11.5 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **7.5 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **2.1 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **0.5 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN E. BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601086**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602577 Northing (Y): 684585
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 11, 2016

**DATE WELL COMPLETED:** February 11, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 125-MW-03

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 11.5 Finished Well Depth (ft.): 11.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 11.5 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 11.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 11.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 2.1 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 11: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 11 - 11.5: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines FILL |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION


Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601087** |
| Owner's Well Number (as shown on the application or plans: | **125-MW-02** |
| Well Completion Date: | **February 19, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **13.5 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **3.5 ft** |
| Screen Length: | **10 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **4 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**GORDON BLEWETT** 

Name (type or print) Signature

Certification or License No. **0021852**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601087**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602448 Northing (Y): 684489
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 19, 2016

**DATE WELL COMPLETED:** February 19, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 125-MW-02

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 13.5 Finished Well Depth (ft.): 13.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 13.5 | 6 | | |
| Casing | 0 | 3.5 | 2 | PVC | SH40 |
| Screen | 3.5 | 13.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 13.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 1: BLACK GM - Silty gravels, gravel-sand-silt mixtures ASPHALT |
| 1 - 4: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 4 - 13.5: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601088** |
| Owner's Well Number (as shown on the application or plans: | **140-MW-10** |
| Well Completion Date: | **February 11, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **12 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **8 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **4 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **0.5 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN E. BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601088**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Development

Address: 80 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602287 Northing (Y): 684774
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 11, 2016

**DATE WELL COMPLETED:** February 11, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-10

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 12 Finished Well Depth (ft.): 12 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 12 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 12 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 12 | 6 | 2 | MORIE31 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 11: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL

11 - 12: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines CRUSHED CONCRETE

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601089** |
| Owner's Well Number (as shown on the application or plans: | **140-MW-09** |
| Well Completion Date: | **February 12, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **14 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **10 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **4.7 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **0.5 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN E. BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601089**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Development

Address: 80 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602106 Northing (Y): 684819
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 12, 2016

**DATE WELL COMPLETED:** February 12, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-09

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 14.5 Finished Well Depth (ft.): 14 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 14.5 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 14 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 6 | 2 | 0 | 55 | 3 |
| Gravel Pack | 4 | 14 | 6 | 2 | MORIE#1 | | |
| Gravel Pack | 14 | 14.5 | 6 | 0 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4.7 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 1: BLACK GW - Well-graded gravels and gravel-sand mixtures, little or no fines ASPHALT |
| 1 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 10: BRN SM - Silty sands, sand-silt mixtures |
| 10 - 14.5: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION


Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601090** |
| Owner's Well Number (as shown on the application or plans: | **134-MW-04** |
| Well Completion Date: | **February 22, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **16 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **12 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **5 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**GORDON. BLEWETT** 

Name (type or print) Signature

Certification or License No. **JD0021852**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601090**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevelopment is correct owner

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602016 Northing (Y): 685002
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 22, 2016

**DATE WELL COMPLETED:** February 22, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-04

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 16 Finished Well Depth (ft.): 16 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 16 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 16 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 16 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 16: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601091** |
| Owner's Well Number (as shown on the application or plans: | **134-MW-03** |
| Well Completion Date: | **February 16, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **17 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **13 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **5.2 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **0.5 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN E. BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601091**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 4 Block: 24601

Easting (X): 601865 Northing (Y): 685020
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 16, 2016

**DATE WELL COMPLETED:** February 16, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-03

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17 Finished Well Depth (ft.): 17 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 17 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 17 | 6 | 2 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5.2 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMENSIBLW
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 14: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 14 - 17: BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601092** |
| Owner's Well Number (as shown on the application or plans: | **073-MW-08** |
| Well Completion Date: | **February 12, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **17 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **13 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **5.2 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **0.5 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN E. BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601092**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601621 Northing (Y): 685234
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 12, 2016

**DATE WELL COMPLETED:** February 12, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-08

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17.5 Finished Well Depth (ft.): 17 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.5 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 17 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 6 | 2 | 0 | 55 | 3 |
| Gravel Pack | 4 | 17 | 6 | 2 | MORIE#1 | | |
| Gravel Pack | 17 | 17.5 | 6 | 0 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5.2 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: .5 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GOS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 14: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 14 - 17.5: BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION


Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601093** |
| Owner's Well Number (as shown on the application or plans: | **073-MW-07** |
| Well Completion Date: | **February 23, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **18 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **14 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **5 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**GORDON BLEWETT** 

Name (type or print) Signature

Certification or License No. **0021852**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601093**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601451 Northing (Y): 685358
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 23, 2016

**DATE WELL COMPLETED:** February 23, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-07

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 18 Finished Well Depth (ft.): 18 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 18 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 18 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 18 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - .5: GRAY GW - Well-graded gravels and gravel-sand mixtures, little or no fines CONCRETE |
| .5 - 15: BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 15 - 18: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601094** |
| Owner's Well Number (as shown on the application or plans: | **073-MW-06** |
| Well Completion Date: | **February 17, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **19 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4 ft** |
| Screen Length: | **15 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **6 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** 

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601094**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601396 Northing (Y): 685464
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 17, 2016

**DATE WELL COMPLETED:** February 17, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-06

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 20 Finished Well Depth (ft.): 20 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 20 | 6 | | |
| Casing | 0 | 4 | 2 | PVC | SH40 |
| Screen | 4 | 19 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 45 | 2.5 |
| Gravel Pack | 3 | 20 | 6 | 2 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 6 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 14: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 14 - 16: BRN SP - Poorly graded sands and gravelly sands, little or no fines |
| 16 - 20: BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION


Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Development Area**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201601098** |
| Owner's Well Number (as shown on the application or plans: | **134-MW-V09R** |
| Well Completion Date: | **February 22, 2016** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **17.5 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **3.5 ft** |
| Screen Length: | **14 ft** |
| Screen or Slot Size: | **0.010 inch** |
| Screen or Slot Material (in.): | **PVC** |
| Casing Material: (pvc, steel or other-specify): | **PVC** |
| Casing Diameter (inches): | **2 INCH** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **4.5 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**GORDON BLEWETT** 

Name (type or print) Signature

Certification or License No. **0021852**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201601098**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Bayfront Redevelopment

Address: 100 Kellogg St Bayfront Redevlopment is correct owner

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601868 Northing (Y): 685185
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** February 22, 2016

**DATE WELL COMPLETED:** February 22, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-V09R

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17.5 Finished Well Depth (ft.): 17.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.5 | 6 | | |
| Casing | 0 | 3.5 | 2 | PVC | SH40 |
| Screen | 3.5 | 17.5 | 2 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 2 | 0 | 47 | 2.5 |
| Gravel Pack | 3 | 17.5 | 6 | 2 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 4.5 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH BRAT
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 17.5: GRAY GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Gordon Blewett, JOURNEYMAN LICENSE # 0021852 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION


Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506364** |
| Owner's Well Number (as shown on the application or plans: | **PZ-11** |
| Well Completion Date: | **July 13, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **9.5 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4.5 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **2 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** 

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506364**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603290 Northing (Y): 684201
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 13, 2015

**DATE WELL COMPLETED:** July 13, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-11

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 9.5 Finished Well Depth (ft.): 9.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 9.5 | 8 | | |
| Casing | 0 | 4.5 | 4 | Stainless Steel | SH40 |
| Screen | 4.5 | 9.5 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 2.5 | 8 | 4 | 1.2 | 55 | 3 |
| Gravel Pack | 2.5 | 3.5 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 3.5 | 9.5 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 2 ft. below land surface
Water Level Measure Tool: Tape
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Moble B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 1: BLK OT - Other ASPHALT |
| 1 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 9.5: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506365** |
| Owner's Well Number (as shown on the application or plans: | **PZ-12** |
| Well Completion Date: | **July 9, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **9.46 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4.46 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **7.5 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506365**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603277 Northing (Y): 684208
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 9, 2015

**DATE WELL COMPLETED:** July 9, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-12

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 9.46 Finished Well Depth (ft.): 9.46 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 9.46 | 8 | | |
| Casing | 0 | 4.46 | 4 | Stainless Steel | SH40 |
| Screen | 4.46 | 9.46 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 1.46 | 8 | 4 | 1 | 31 | 1.5 |
| Gravel Pack | 1.46 | 3.46 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 3.46 | 9.46 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 7.5 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 9.46: GRAY-BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506366** |
| Owner's Well Number (as shown on the application or plans: | **PZ-13** |
| Well Completion Date: | **July 10, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **9.58 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **4.58 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **2 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature

**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506366**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602894 Northing (Y): 684392
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 10, 2015

**DATE WELL COMPLETED:** July 10, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-13

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 9.58 Finished Well Depth (ft.): 9.58 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 9.58 | 8 | | |
| Casing | 0 | 4.58 | 4 | Stainless Steel | SH40 |
| Screen | 4.58 | 9.58 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 2.58 | 8 | 4 | 1.2 | 30 | 1.75 |
| Gravel Pack | 2.58 | 3.58 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 3.58 | 9.58 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 2 ft. below land surface
Water Level Measure Tool: TAPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 9.58: GRAY-BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506367** |
| Owner's Well Number (as shown on the application or plans: | **PZ-14** |
| Well Completion Date: | **July 10, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **14.1 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **9.1 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **11.2 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506367**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 427 RT. 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602908 Northing (Y): 684421
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 10, 2015

**DATE WELL COMPLETED:** July 10, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-14

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 14.1 Finished Well Depth (ft.): 14.1 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 14.1 | 8 | | |
| Casing | 0 | 9.1 | 4 | Stainless Steel | SH40 |
| Screen | 9.1 | 14.1 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 6.1 | 8 | 4 | 6 | 130 | 7.33 |
| Gravel Pack | 6.1 | 8.1 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 8.1 | 14.1 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 11.2 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 5: BRN SM - Silty sands, sand-silt mixtures FILL |
| 5 - 14.1: RD-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506368** |
| Owner's Well Number (as shown on the application or plans: | **PZ-15** |
| Well Completion Date: | **July 7, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **10.1 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **5.1 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **7 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature

**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506368**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602498 Northing (Y): 684736
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 7, 2015

**DATE WELL COMPLETED:** July 7, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-15

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 10.1 Finished Well Depth (ft.): 10.1 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 10.1 | 8 | | |
| Casing | 0 | 5.1 | 4 | Stainless Steel | SH40 |
| Screen | 5.1 | 10.1 | 4 | Stanless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3.1 | 8 | 4 | 1 | 65 | 3.75 |
| Gravel Pack | 3.1 | 5.1 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 5.1 | 10.1 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 7 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 10.1: BRN GM - Silty gravels, gravel-sand-silt mixtures Fill |

| ADDITIONAL INFORMATION: |
|---|

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506369** |
| Owner's Well Number (as shown on the application or plans: | **PZ-16** |
| Well Completion Date: | **July 8, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **18.66 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **13.66 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **14.7 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506369**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602509 Northing (Y): 684751
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 8, 2015

**DATE WELL COMPLETED:** July 8, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-16

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 18.66 Finished Well Depth (ft.): 18.66 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 18.66 | 8 | | |
| Casing | 0 | 13.66 | 4 | Stainless Steel | SH40 |
| Screen | 13.66 | 18.66 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10.66 | 8 | 4 | 10 | 230 | 13 |
| Gravel Pack | 10.66 | 12.66 | 8 | 4 | MORIE#00 | | |
| Gravel Pack | 12.66 | 18.66 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 14.7 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBILE B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 8: BRN SM - Silty sands, sand-silt mixtures |
| 8 - 15: BRN GM - Silty gravels, gravel-sand-silt mixtures |
| 15 - 18.66: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506370** |
| Owner's Well Number (as shown on the application or plans: | **PZ-17** |
| Well Completion Date: | **July 1, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **12 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **7 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **5 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506370**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 601978 Northing (Y): 685121
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** June 30, 2015

**DATE WELL COMPLETED:** July 1, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-17

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 12 Finished Well Depth (ft.): 12 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 12 | 8 | | |
| Casing | 0 | 7 | 4 | Stainless Steel | SH40 |
| Screen | 7 | 12 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 8 | 4 | 0.75 | 85 | 4.75 |
| Gravel Pack | 4 | 6 | 8 | 4 | MORIE #00 | | |
| Gravel Pack | 6 | 12 | 8 | 4 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: SUBMERSIBLE
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506371** |
| Owner's Well Number (as shown on the application or plans: | **PZ-18** |
| Well Completion Date: | **July 7, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **16.2 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **11.2 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **8 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** Warren E Blewett

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD**

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506371**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 601989 Northing (Y): 685136
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 6, 2015

**DATE WELL COMPLETED:** July 7, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-18

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 16.2 Finished Well Depth (ft.): 16.2 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 16.2 | 8 | | |
| Casing | 0 | 11.2 | 4 | Stainless Steel | SH40 |
| Screen | 11.2 | 16.2 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 9.2 | 8 | 4 | 1.1 | 200 | 11 |
| Gravel Pack | 9.2 | 11.2 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 11.2 | 16.2 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 8 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 16.2: BRN GM - Silty gravels, gravel-sand-silt mixtures fill

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506372** |
| Owner's Well Number (as shown on the application or plans: | **PZ-19** |
| Well Completion Date: | **July 1, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **10.4 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **5.4 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **7 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** 

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506372**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 200 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601501 Northing (Y): 685587
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 1, 2015

**DATE WELL COMPLETED:** July 1, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-19

## WELL CONSTRUCTION

Total Depth Drilled (ft.): 10.4 Finished Well Depth (ft.): 10.4 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 10.4 | 8 | | |
| Casing | 0 | 5.4 | 4 | Stainless Steel | SH40 |
| Screen | 5.4 | 10.4 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3.4 | 8 | 4 | 1 | 70 | 4 |
| Gravel Pack | 3.4 | 5.4 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 5.4 | 10.4 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

## ADDITIONAL INFORMATION

Protective Casing: No
Static Water Level: 7 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

## ATTACHMENTS:

**GEOLOGIC LOG**

0 - 10.4: BRN GM - Silty gravels, gravel-sand-silt mixtures Fill

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION

Name of Permittee: **B&B Drilling, Inc.**
Name of Facility: **Honeywell – Cap Monitoring**
Location: **Jersey City, Hudson County, New Jersey**
NJDES Permit No.: Or ECRA Case No.:

CERTIFICATION:

| | |
|---|---|
| Well Permit Number (as assigned by NJDEP's Bureau of Water Allocation): | **E201506373** |
| Owner's Well Number (as shown on the application or plans: | **PZ-20** |
| Well Completion Date: | **July 2, 2015** |
| Distance from Top of Casing (cap off) to ground surface (to the nearest ½ foot): | **2 ft** |
| Total Depth of Well to the nearest ½ foot: (finished well depth) | **17.3 ft** |
| Depth to Top of Screen to top of Casing ( to the nearest ½ foot): | **12.3 ft** |
| Screen Length: | **5 ft** |
| Screen or Slot Size: | **0.030 inch** |
| Screen or Slot Material (in.): | **Stainless Steel** |
| Casing Material: (pvc, steel or other-specify): | **Stainless Steel** |
| Casing Diameter (inches): | **4 inch** |
| Static Water Level from Top of Casing at the time of installation (to the nearest ½ foot): | **12 ft** |
| Yield (gallons per minute): | **NM** |
| Development Technique (specify): | **Pump and surge** |
| Length of Time Well is Developed/Pumped or Bailed: | **1 hr** |
| Lithologic Log: | **Attached** |

Authentication:


I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

**WARREN BLEWETT** 

Name (type or print) Signature

Certification or License No. **JD0014578**

Certification by Executive Officer or Duly Authorized Representative

Name (type or print) Signature
**H. ROBERT SEYBOLD** 

Title **President** Date **04/01/2016**

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201506373**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** BAYFRONT REDEVELOPMENT

Address: 200 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601504 Northing (Y): 685584
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** July 2, 2015

**DATE WELL COMPLETED:** July 2, 2015

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** PZ-20

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 17.3 Finished Well Depth (ft.): 17.3 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 17.3 | 8 | | |
| Casing | 0 | 12.3 | 4 | Stainless Steel | SH40 |
| Screen | 12.3 | 17.3 | 4 | Stainless Steel | 0.030" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10.3 | 8 | 4 | 1 | 220 | 12.5 |
| Gravel Pack | 10.3 | 12.3 | 8 | 4 | Morie #00 | | |
| Gravel Pack | 12.3 | 17.3 | 8 | 4 | Morie #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: No
Static Water Level: 12 ft. below land surface
Water Level Measure Tool: m-scope
Well Development Period: 1 hrs.
Method of Development: Submersible
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| GEOLOGIC LOG |
|---|
| 0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures Fill |
| 12 - 17.3: BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-11 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/13/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 9.69 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Riser Pipe | 0 | 9.69 |
| Top of Seal | 2.5 | 7.19 |
| Top of Filter Pack | 3.5 | 6.19 |
| Top of Screen | 4.5 | 5.19 |
| Base of Screen / Drilled Depth | 9.5 | 0.19 |



**Description**

| | |
|---|---|
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Stainless Steel |
| Riser Pipe ID: | 4 inch |
| Borehole Diameter: | 8 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Stainless Steel |
| Screen ID: | 4 inch |
| Screen Slot Size: | .030" |
| Screen Length: | 5 ft |
| Filter/Sand Pack Type: | #1 Sand |

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-12 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/9/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 10.63 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Riser Pipe | 0 | 10.63 |
| Top of Seal | 1.46 | 9.17 |
| Top of Filter Pack | 3.46 | 7.17 |
| Top of Screen | 4.46 | 6.17 |
| Base of Screen / Drilled Depth | 9.46 | 1.17 |



| Description | |
|---|---|
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Stainless Steel |
| Riser Pipe ID: | 4 inch |
| Borehole Diameter: | 8 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Stainless Steel |
| Screen ID: | 4 inch |
| Screen Slot Size: | .030" |
| Screen Length: | 5 ft |
| Filter/Sand Pack Type: | #1 Sand |

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-13 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/10/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 10.62 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) | Description |
|---|---|---|---|
| Riser Pipe | 0 | 10.62 | |
| Top of Seal | 2.58 | 8.04 | |
| Top of Filter Pack | 3.58 | 7.04 | |
| Top of Screen | 4.58 | 6.04 | |
| Base of Screen / Drilled Depth | 9.58 | 1.04 | |



Surface Seal Type: Concrete

Backfill/Grout Type: Bentonite Grout

Riser Pipe Type: Stainless Steel

Riser Pipe ID: 4 inch

Borehole Diameter: 8 inch

Type of Seal: #00 Sand

Screen Type: Stainless Steel

Screen ID: 4 inch

Screen Slot Size: .030"

Screen Length: 5 ft

Filter/Sand Pack Type: #1 Sand

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-14 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/10/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 15.15 |


| Item | Depth, below Measuring Point (ft) | Elevation (ft) | Description |
|---|---|---|---|
| Riser Pipe | 0 | 15.15 | |
| | | | Surface Seal Type: Concrete |
| | | | Backfill/Grout Type: Bentonite Grout |
| | | | Riser Pipe Type: Stainless Steel |
| | | | Riser Pipe ID: 4 inch |
| | | | Borehole Diameter: 8 inch |
| Top of Seal | 6.1 | 9.05 | |
| | | | Type of Seal: #00 Sand |
| Top of Filter Pack | 8.1 | 7.05 | |
| Top of Screen | 9.1 | 6.05 | |
| | | | Screen Type: Stainless Steel |
| | | | Screen ID: 4 inch |
| | | | Screen Slot Size: .030" |
| | | | Screen Length: 5 ft |
| | | | Filter/Sand Pack Type: #1 Sand |
| Base of Screen / Drilled Depth | 14.1 | 1.05 | |



**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-15 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/7/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 13.34 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Riser Pipe | 0 | 13.34 |
| Top of Seal | 3.1 | 10.24 |
| Top of Filter Pack / Top of Screen | 5.1 | 8.24 |
| Base of Screen / Drilled Depth | 10.1 | 3.24 |



| Description | |
|---|---|
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Stainless Steel |
| Riser Pipe ID: | 4 inch |
| Borehole Diameter: | 8 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Stainless Steel |
| Screen ID: | 4 inch |
| Screen Slot Size: | .030" |
| Screen Length: | 5 ft |
| Filter/Sand Pack Type: | #1 Sand |

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-16 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/8/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 17.7 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) | Description |
|---|---|---|---|
| Riser Pipe | 0 | 17.7 | |
| Top of Seal | 10.66 | 7.04 | |
| Top of Filter Pack | 12.66 | 5.04 | |
| Top of Screen | 13.66 | 4.04 | |
| Base of Screen / Drilled Depth | 18.66 | -0.96 | |



| | |
|---|---|
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Stainless Steel |
| Riser Pipe ID: | 4 inch |
| Borehole Diameter: | 8 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Stainless Steel |
| Screen ID: | 4 inch |
| Screen Slot Size: | .030" |
| Screen Length: | 5 ft |
| Filter/Sand Pack Type: | #1 Sand |

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-17 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/1/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 15.15 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) | Description |
|---|---|---|---|
| Riser Pipe | 0 | 15.15 | |
| Top of Seal | 4 | 11.15 | |
| Top of Filter Pack | 6 | 9.15 | |
| Top of Screen | 7 | 8.15 | |
| Base of Screen / Drilled Depth | 12 | 3.15 | |



Surface Seal Type: Concrete

Backfill/Grout Type: Bentonite Grout

Riser Pipe Type: Stainless Steel

Riser Pipe ID: 4 inch

Borehole Diameter: 8 inch

Type of Seal: #00 Sand

Screen Type: Stainless Steel

Screen ID: 4 inch

Screen Slot Size: .030"


Screen Length: 5 ft

Filter/Sand Pack Type: #1 Sand

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-18 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 7/7/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | **Elevation (ft):** 18.13 |


| Item | Depth, below Measuring Point (ft) | Elevation (ft) | Description |
|---|---|---|---|
| Riser Pipe | 0 | 18.13 | |
| | | | Surface Seal Type: Concrete |
| | | | Backfill/Grout Type: Bentonite Grout |
| | | | Riser Pipe Type: Stainless Steel |
| | | | Riser Pipe ID: 4 inch |
| | | | Borehole Diameter: 8 inch |
| Top of Seal | 9.2 | 8.93 | |
| | | | Type of Seal: #00 Sand |
| Top of Filter Pack / Top of Screen | 11.2 | 6.93 | |
| | | | Screen Type: Stainless Steel |
| | | | Screen ID: 4 inch |
| | | | Screen Slot Size: .030" |
| | | | Screen Length: 5 ft |
| | | | Filter/Sand Pack Type: #1 Sand |
| Base of Screen / Drilled Depth | 16.2 | 1.93 | |



**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-19 |
|---|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** | 3480130377 | |
| **Client:** | Honeywell | **Date:** | 7/1/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | | **Measuring Point** |
| **Development Method:** | Submersible | | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | | **Elevation (ft):** 15.38 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Riser Pipe | 0 | 15.38 |
| Top of Seal | 3.4 | 11.98 |
| Top of Filter Pack / Top of Screen | 5.4 | 9.98 |
| Base of Screen / Drilled Depth | 10.4 | 4.98 |




**Description**

| | |
|---|---|
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Stainless Steel |
| Riser Pipe ID: | 4 inch |
| Borehole Diameter: | 8 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Stainless Steel |
| Screen ID: | 4 inch |
| Screen Slot Size: | .030" |
| Screen Length: | 5 ft |
| Filter/Sand Pack Type: | #1 Sand |

**Notes:**

| Amec Foster Wheeler Environment & Infrastructure | | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-PZ-20 |
|---|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** | 3480130377 | |
| **Client:** | Honeywell | **Date:** | 7/2/2015 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | | **Measuring Point** |
| **Development Method:** | Submersible | | | **Type:** Top Of Riser |
| **Bucking Posts:** | | | | **Elevation (ft):** 18.18 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Riser Pipe | 0 | 18.18 |
| Top of Seal | 10.3 | 7.88 |
| Top of Filter Pack / Top of Screen | 12.3 | 5.88 |
| Base of Screen / Drilled Depth | 17.3 | 0.88 |



**Description**

| | |
|---|---|
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Stainless Steel |
| Riser Pipe ID: | 4 inch |
| Borehole Diameter: | 8 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Stainless Steel |
| Screen ID: | 4 inch |
| Screen Slot Size: | .030" |
| Screen Length: | 5 ft |
| Filter/Sand Pack Type: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 073-MW-06 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/17/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 11.72 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 11.72 | 0 |
| Riser Pipe | 11.5 | 0.22 |
| Grade | 9.01 | 2.71 |
| Top of Seal | 2.5 | 9.22 |
| Top of Filter Pack | 3 | 8.72 |
| Top of Screen | 4 | 7.72 |
| Base of Screen | 19 | -7.28 |
| Drilled Depth | 19.7 | -7.98 |



**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 15 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

# AMEC Environment & Infrastructure

**STICKUP OVERBURDEN WELL/PIEZOMETER 073-MW-07**

| | | | |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/23/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | Air Rotary | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 11.24 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 11.24 | 0 |
| Riser Pipe | 10.38 | 0.86 |
| Grade | 9.71/7.30 | 1.53/3.94 |
| | High side/Low side | |
| Top of Seal | 1 | 10.24 |
| Top of Filter Pack | 1.5 | 9.74 |
| Top of Screen | 2 | 9.24 |
| Base of Screen | 16 | -4.76 |
| Drilled Depth | 16.6 | -5.36 |



**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 14 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 073-MW-08 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/16/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 11.01 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 11.01 | 0 |
| Riser Pipe | 10.57 | 0.44 |
| Grade | 7.47 | 3.54 |
| Top of Seal | 1 | 10.01 |
| Top of Filter Pack | 1.5 | 9.51 |
| Top of Screen | 2 | 9.01 |
| Base of Screen | 15 | -3.99 |
| Drilled Depth | 15.5 | -4.49 |




**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 13 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-MW-12 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/19/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 13.37 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 13.37 | 0 |
| Riser Pipe | 11.97 | 1.4 |
| Grade | 9.89 | 3.48 |
| Top of Seal | 1.5 | 11.87 |
| Top of Filter Pack | 2 | 11.37 |
| Top of Screen | 3 | 10.37 |
| Base of Screen | 11.5 | 1.87 |
| Drilled Depth | 12 | 1.37 |



**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 8.5 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 124-MW-13 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/10/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 13.22 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 13.22 | 0 |
| Riser Pipe | 13.02 | 0.2 |
| Grade | 9.52 | 3.7 |
| Top of Seal | 1 | 12.22 |
| Top of Filter Pack | 1.5 | 11.72 |
| Top of Screen | 2 | 11.22 |
| Base of Screen | 11 | 2.22 |
| Drilled Depth | 11 | 2.22 |




| Description | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 9 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| Amec Foster Wheeler | | | FLUSHMOUNT OVERBURDEN WELL/PIEZOMETER 125-MW-02 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/19/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | | | **Type:** Ground |
| **Bucking Posts:** | No | | **Elevation (ft):** 8.45 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) | Description | |
|---|---|---|---|---|
| Grade | 8.44 | 0.01 | Flushmount Diameter: | 8 inch |
| Riser Pipe | 8.07 | 0.38 | Surface Seal Type: | Concrete |
| | | | Backfill/Grout Type: | Bentonite Grout |
| | | | Riser Pipe Type: | Schedule 40 PVC |
| | | | Riser Pipe ID: | 2 inch |
| | | | Borehole Diameter: | 6 inch |
| Top of Seal | 2 | 6.45 | | |
| | | | Type of Seal: | #00 Sand |
| Top of Filter Pack | 2.5 | 5.95 | | |
| Top of Screen | 3.5 | 4.95 | | |
| | | | Screen Type: | Schedule 40 PVC |
| | | | Screen ID: | 2 inch |
| | | | Screen Slot Size: | .010" |
| | | | Screen Length: | 10 ft. |
| | | | Filter/Sand Pack Type: | #1 Sand |
| Base of Screen | 13.5 | -5.05 | | |
| Drilled Depth | 14 | -5.55 | Fallback/Backfill: | # 1 Sand |



**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 125-MW-03 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/11/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 11.54 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 11.54 | 0 |
| Riser Pipe | 11.27 | 0.27 |
| Grade | 7.6 | 3.94 |
| Top of Seal | 1 | 10.54 |
| Top of Filter Pack | 1.5 | 10.04 |
| Top of Screen | 2 | 9.54 |
| Base of Screen | 9.5 | 2.04 |
| Drilled Depth | 10 | 1.54 |




**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 7.5 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 134-MW-03 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/16/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 11.01 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 11.01 | 0 |
| Riser Pipe | 10.4 | 0.61 |
| Grade | 7.44 | 3.57 |
| Top of Seal | 1 | 10.01 |
| Top of Filter Pack | 1.5 | 9.51 |
| Top of Screen | 2 | 9.01 |
| Base of Screen | 14.5 | -3.49 |
| Drilled Depth | 15 | -3.99 |



| Description | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 12.5 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

# AMEC Environment & Infrastructure

**STICKUP OVERBURDEN WELL/PIEZOMETER 134-MW-04**

| | | | |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/22/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 10.63 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 10.63 | 0 |
| Riser Pipe | 9.85 | 0.78 |
| Grade | 8.74/6.86 | 1.89/3.77 |
| | High side/Low side | |
| Top of Seal | 1 | 9.63 |
| Top of Filter Pack | 1.5 | 9.13 |
| Top of Screen | 2 | 8.63 |
| Base of Screen | 14 | -3.37 |
| Drilled Depth | 14.5 | -3.87 |




**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 12 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | | STICKUP OVERBURDEN WELL/PIEZOMETER 134-MW-V09R |
|---|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** | 3480130377 | |
| **Client:** | Honeywell | **Date:** | 2/22/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | | **Measuring Point** |
| **Development Method:** | Submersible | | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | | **Elevation (ft):** 12.08 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 0 | 12.08 |
| Riser Pipe | 0.97 | 11.11 |
| Grade | 1.82/3.57 | 10.26/8.51 |
| | High side/Low side | |
| Top of Seal | 4.57 | 7.51 |
| Top of Filter Pack | 5.07 | 7.01 |
| Top of Screen | 5.57 | 6.51 |
| Base of Screen | 19.57 | -7.49 |
| Drilled Depth | 20.07 | -7.99 |



| Description | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 14 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 140-MW-09 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/12/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 10.95 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 10.95 | 0 |
| Riser Pipe | 10.72 | 0.23 |
| Grade | 8.65 | 2.3 |
| Top of Seal | 2.5 | 8.45 |
| Top of Filter Pack | 3 | 7.95 |
| Top of Screen | 3.5 | 7.45 |
| Base of Screen | 13.5 | -2.55 |
| Drilled Depth | 14 | -3.05 |



**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 10 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

| AMEC Environment & Infrastructure | | | STICKUP OVERBURDEN WELL/PIEZOMETER 140-MW-10 |
|---|---|---|---|
| **Project:** | Honeywell Jersey City SA-6 South | **Number:** 3480130377 | |
| **Client:** | Honeywell | **Date:** 2/11/2016 | **Subcontractor:** B&B Drilling |
| **Drilling Method:** | HSA | | **Measuring Point** |
| **Development Method:** | Submersible | | **Type:** Top Of Riser |
| **Bucking Posts:** | No | | **Elevation (ft):** 10.77 |

| Item | Depth, below Measuring Point (ft) | Elevation (ft) |
|---|---|---|
| Stickup | 10.77 | 0 |
| Riser Pipe | 10.49 | 0.28 |
| Grade | 8.46/6.64 | 2.31/4.13 |
| | High side/ Low side | |
| Top of Seal | 1 | 9.77 |
| Top of Filter Pack | 1.5 | 9.27 |
| Top of Screen | 2 | 8.77 |
| Base of Screen | 10 | 0.77 |
| Drilled Depth | 10 | 0.77 |



**Description**

| | |
|---|---|
| Stickup Type: | Steel |
| Stickup Diameter: | 6 inch |
| Surface Seal Type: | Concrete |
| Backfill/Grout Type: | Bentonite Grout |
| Riser Pipe Type: | Schedule 40 PVC |
| Riser Pipe ID: | 2 inch |
| Borehole Diameter: | 6 inch |
| Type of Seal: | #00 Sand |
| Screen Type: | Schedule 40 PVC |
| Screen ID: | 2 inch |
| Screen Slot Size: | .010" |
| Screen Length: | 8 ft. |
| Filter/Sand Pack Type: | #1 Sand |
| Fallback/Backfill: | #1 Sand |

**Notes:**

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Roosevelt Bowling Lanes (Site 124)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008741 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 427 Rt. 440
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 8

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506364
2. Site Well Number (As shown on application or plans): 124-PZ-11
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-39.93 Longitude: West 074-05-56.34
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684200 East 603290
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 9.69'
   Elevation Top of Outer casing: 10.00' Elevation of ground: 9.81'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Roosevelt Bowling Lanes (Site 124)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008741 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 427 Rt. 440
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 8

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506365
2. Site Well Number (As shown on application or plans): 124-PZ-12
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-40.01 Longitude: West 074-05-56.50
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684208 East 603278
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.63'
   Elevation Top of Outer casing: 10.87' Elevation of ground: 10.31'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Roosevelt Bowling Lanes (Site 124)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008741 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 427 Rt. 440
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 8

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506366
2. Site Well Number (As shown on application or plans): 124-PZ-13
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-41.84 Longitude: West 074-06-01.47
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684391 East 602894
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 10.62'
   Elevation Top of Outer casing: 10.87' Elevation of ground: 10.65'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Roosevelt Bowling Lanes (Site 124)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G000008741 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 427 Rt. 440
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 8

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506367
2. Site Well Number (As shown on application or plans): 124-PZ-14
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-42.13 Longitude: West 074-06-01.29
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684420 East 602908
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 15.15'
   Elevation Top of Outer casing: 15.40' Elevation of ground: 15.15'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: ABF Trucking (Site 140)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 003846 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 80 Kellogg St.
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 6

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506368
2. Site Well Number (As shown on application or plans): 124-PZ-15
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-45.26 Longitude: West 074-06-06.60
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684735 East 602498
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 13.34'
   Elevation Top of Outer casing: 13.60' Elevation of ground: 12.54'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: ABF Trucking (Site 140)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 003846 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 80 Kellogg St.
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 6

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506369
2. Site Well Number (As shown on application or plans): 124-PZ-16
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-45.42 Longitude: West 074-06-06.45
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 684751 East 602509
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 17.70'
   Elevation Top of Outer casing: 17.99' Elevation of ground: 17.63'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Old Dominion (Site 134)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 033312 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 100 Kellogg St.
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 5

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506370
2. Site Well Number (As shown on application or plans): 124-PZ-17
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-49.10 Longitude: West 074-06-13.33
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685122 East 601977
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 15.15'
   Elevation Top of Outer casing: 15.42' Elevation of ground: 14.36'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Old Dominion (Site 134)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): 033312 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 100 Kellogg St.
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 5

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506371
2. Site Well Number (As shown on application or plans): 124-PZ-18
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-49.25 Longitude: West 074-06-13.18
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685137 East 601989
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 18.13'
   Elevation Top of Outer casing: 18.61' Elevation of ground: 18.29'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Degen Oil (Site 073)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G00000927 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 200 Kellogg St.
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 1

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506372
2. Site Well Number (As shown on application or plans): 124-PZ-19
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-53.74 Longitude: West 074-06-19.53
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685589 East 601498
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 15.38'
   Elevation Top of Outer casing: 15.62' Elevation of ground: 14.43'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

**New Jersey Department of Environmental Protection**
Site Remediation Program

**Monitoring Well Certification Form B - Location Certification**

**Date Stamp**
**(For Department use only)**

**SECTION A. SITE NAME AND LOCATION**

Site Name: Study Area SA-6 South Chromium Remedy

List all AKAs: Degen Oil (Site 073)

Street Address: 427 Route 440

Municipality: Jersey City (Township, Borough or City)

County: Hudson Zip Code: 07305

Program Interest (PI) Number(s): G00000927 Case Tracking Number(s):

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Bayfront Redevelopment, LLC
2. Well Location (Street Address) 200 Kellogg St.
3. Well Location (Municipal Block and Lot) Block# 24601 Lot # 1

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201506373
2. Site Well Number (As shown on application or plans): 124-PZ-20
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:
   Latitude: North 40-42-53.69 Longitude: West 074-06-19.45
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:
   North 685584 East 601504
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 18.18'
   Elevation Top of Outer casing: 18.52' Elevation of ground: 17.88'
   *Check one*: ☐ NAVD 88 ☒ NGVD 29 ☐ On Site Datum ☐ Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).
   NGS Bench Mark KV0272. Elevation = 36.37' (NGVD29). (Subtract 1.14' to convert elevation to NAVD88 datum)
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Date

Surveyor's Name: Jeffrey D. Bunce License Number: GS41045

Firm Name: Maser Consulting P.A. Certificate of Authorization #: 24GA27986500

Mailing Address 400 Valley Road Road Suite 304

City/Town: Mt. Arlington State New Jersey Zip Code: 07856

Phone Number 973-398-3110 Ext.: 4544 Fax: 973-398-3199

# APPENDIX F

# MONITORING WELL ABANDONMENT RECORDS
# (CD ONLY)

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** 425/445 ROUTE 440 PROP. C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Bayfront Redevelopment

Address: 200 Kellogg St.

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601743 Northing (Y): 685380
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** May 30, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-04

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 10 | 4 | PVC | |
| Screen | 10 | 15 | 4 | PVC | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 15 | 4 | 0 | 0 | 107 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1405108

Alternative Decomm. Method? No

Authorization Date: May 23, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201005710**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** HONEYWELL INTERNATIONAL

Company/Organization: HONEYWELL INTERNATIONAL

Address: 101 COLUMBIA ROAD Morristown Town, New Jersey 07962

**WELL LOCATION:** Honeywell International

Address: 200 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 11W Block: 1290.A

Easting (X): 601569 Northing (Y): 685440
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 11, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-05

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 15

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 2 | 2 | PVC | sch 40 |
| Screen | 2 | 15 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 15 | 2 | 0 | 0 | 27 | 1.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600047177**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** DEGEN OIL & CHEMICAL CO.

Company/Organization: Degen Oil

Address: 288 Kellogg St. Jersey City, New Jersey 07305

**WELL LOCATION:** Honewell Redevelopment Project

Address: 288 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 11.2 Block: 1290.A

Easting (X): 601475 Northing (Y): 685543
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-BB11

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 2 | PVC | sch 40 |
| Screen | 3 | 13 | 2 | PVC | .020 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 2 | 0 | 0 | 23 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600047178**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** DEGEN OIL & CHEMICAL CO.

Company/Organization: Degen Oil & Chemical Co.

Address: 288 Kellogg St. Jersey City, New Jersey 07305

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 288 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 11.2 Block: 1290.A

Easting (X): 601665 Northing (Y): 685388
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 11, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 073-MW-Y10

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 2 | PVC | sch 40 |
| Screen | 3 | 13 | 2 | PVC | .020 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 2 | 0 | 0 | 23 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004258**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 073-PZ-001

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20 & 11W Block: 1290.A

Easting (X): 601646 Northing (Y): 685488
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 2, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 073-PZ-001

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 12.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 7.5 | 2 | PVC | sch 40 |
| Screen | 7.5 | 12.5 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 12.5 | 2 | 0 | 0 | 22 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004251**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 073-PZ-002

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20,11W Block: 1290.A

Easting (X): 601641 Northing (Y): 685490
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 2, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 073-PZ-002

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 26

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 16.5 | 2 | PVC | sch 40 |
| Screen | 21 | 26 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 26 | 2 | 0 | 0 | 46 | 2.6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Brian Buttari

Obstruction Type:

Authorization Number: A1402035

Alternative Decomm. Method? No

Authorization Date: February 25, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600078865**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** SURGEES SINGH

Company/Organization: Surgees Singh

Address: 1061 Main Avenues Belleville, New Jersey 07109

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 127 BELLEVILLE AVE R & M AUTO

County: Hudson Municipality: Jersey City Lot: 13 Block: 127

Easting (X): 603027 Northing (Y): 684519
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 2, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 115-E1-DO

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 25

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 15 | 2 | PVC | SCH40 |
| Screen | 15 | 25 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 25 | 2 | 0 | 0 | 44.5 | 2.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: PO Box 4900 Dept 356 Scottsdale, Arizona 85261

**WELL LOCATION:** Honeywell

Address: 445 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603027 Northing (Y): 684519
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 30, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 115-E1-SO

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 10 | 2 | PVC | |
| Screen | 10 | 20 | 2 | PVC | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 20 | 2 | 0 | 0 | 36 | 2 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1603087

Alternative Decomm. Method? No

Authorization Date: March 29, 2016

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600078836**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Former ABF Trucking

Address: STATE ROUTE 440 SA-7

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602149 Northing (Y): 685188
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** May 26, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 115-W4-DO

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 21.4 | 4 | PVC | |
| Casing | 0 | 20 | 8 | Steel | |
| Screen | 21.4 | 41.4 | 4 | PVC | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 41.4 | 4 | 0 | 0 | 300 | 17 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1405118

Alternative Decomm. Method? No

Authorization Date: May 23, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075504**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 ROUTE 440 FORMER ROOSEVELT BOWLING LANES

County: Hudson Municipality: Jersey City Lot: 11.U Block: 1290.A

Easting (X): 603141 Northing (Y): 684150
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-02

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 10

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 10 | 2 | PVC | SC40 |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10 | 2 | 0 | 0 | 18 | 1 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310026

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600066477**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell SA-6 South

Address: STATE HIGHWAY RT. 440

County: Hudson Municipality: Jersey City Lot: 11.U Block: 1290.A

Easting (X): 603066 Northing (Y): 684446
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW06

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 70

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 69.7 | 2 | PVC | SH40 |
| Casing | 0 | 17 | 6 | Steel | SH40 |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 69.7 | 2 | 0 | 0 | 125 | 7 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310043

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600051462**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 ROUTE 440

County: Hudson Municipality: Jersey City Lot: 11.U Block: 1290.A

Easting (X): 603261 Northing (Y): 684189
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-07

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 12

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 11.4 | 2 | PVC | SH40 |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 11.4 | 2 | 0 | 0 | 20 | 1 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310027

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600087305**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 60 KELLOGG STREET STUDY AREA SA-6

County: Hudson Municipality: Jersey City Lot: 12B,11Q,11R Block: 1290.1

Easting (X): 602762 Northing (Y): 684418
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124MW09

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 11

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 11 | 4 | PVC | SH40 |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 11 | 4 | 0 | 0 | 20 | 1 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310028

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600074879**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE HWY RT 440 FORMER PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 11U Block: 1290A

Easting (X): 603131 Northing (Y): 684311
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-102D

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 30

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 20 | 2 | PVC | SH40 |
| Casing | 0 | 12 | 6 | Steel | SH40 |
| Screen | 20 | 30 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 30 | 2 | 0 | 0 | 55 | 3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310031

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600074597**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE RT 440 FORMER PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 11U Block: 1290A

Easting (X): 603140 Northing (Y): 684304
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-102T

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 75

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 65 | 2 | PVC | SH40 |
| Casing | 0 | 12 | 6 | Steel | SH40 |
| Screen | 65 | 75 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 75 | 2 | 0 | 0 | 130 | 7.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310036

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075657**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE HWY. RT. 440 FORMER PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 11U Block: 1290.A

Easting (X): 603052 Northing (Y): 684444
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124 MW 103D

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 30

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 20 | 2 | PVC | SH40 |
| Casing | 0 | 14.35 | 6 | Steel | SH40 |
| Screen | 20 | 30 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 30 | 2 | 0 | 0 | 55 | 3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310032

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075660**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE HWY. RT. 440 PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 11U Block: 1290.A

Easting (X): 603059 Northing (Y): 684437
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-103L

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 57

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 45 | 2 | PVC | SH40 |
| Casing | 0 | 14 | 6 | Steel | SH40 |
| Screen | 45 | 55 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 55 | 2 | 0 | 0 | 94 | 5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310037

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075658**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE HWY. RT. 440 FORMER PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 11U Block: 1290.A

Easting (X): 603183 Northing (Y): 684119
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124 MW104D

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 26

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 16 | 2 | PVC | SH40 |
| Casing | 0 | 11.5 | 6 | Steel | SH40 |
| Screen | 16 | 26 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 26 | 2 | 0 | 0 | 45 | 2.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310033

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075661**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** HONEYWELL INTERNATIONAL

Company/Organization: HONEYWELL INTERNATIONAL

Address: 101 COLUMBIA ROAD Morristown Town, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE HWY. RT. 440 FORMER PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603173 Northing (Y): 684122
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 6, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-104T

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 68

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 58 | 2 | PVC | SH40 |
| Casing | 0 | 11 | 6 | Steel | SH40 |
| Screen | 58 | 68 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 68 | 2 | 0 | 0 | 125 | 7 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310039

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075659**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 STATE HWY. RT. 440 FORMER PLAYDROME ROOSEVELT LANES

County: Hudson Municipality: Jersey City Lot: 11U Block: 1290.A

Easting (X): 602987 Northing (Y): 684286
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-105D

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 24

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 14 | 2 | PVC | SH40 |
| Casing | 0 | 13 | 6 | Steel | SH40 |
| Screen | 14 | 24 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 24 | 2 | 0 | 0 | 40 | 2.25 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310034

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** SA-6 SOUTH

Address: 427 ST. HWY 440

County: Hudson Municipality: Jersey City Lot: 24601 Block: 7

Easting (X): 602821 Northing (Y): 684581
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** November 18, 2013

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 124-MW-107T

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 70 | 2 | PVC | SH40 |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 70 | 2 | 0 | 0 | 125 | 7 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1310042

Alternative Decomm. Method? No

Authorization Date: October 11, 2013

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075505**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** MI HOLDINGS

Company/Organization: MI Holdings

Address: Rt. 440 & Carbon Place C/O Honeywell Jersey City, New Jersey 07303

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 60 KELLOGG ST DELPHIC CONSOLIDATION

County: Hudson Municipality: Jersey City Lot: 11.Q Block: 1290.A

Easting (X): 602680 Northing (Y): 684704
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 125-MW-01

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 12

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 2 | 2 | PVC | sch 40 |
| Screen | 2 | 12 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 12 | 2 | 0 | 0 | 21 | 1.2 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004262**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 125-PZ-001

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20 & 11W Block: 1290.A

Easting (X): 602617 Northing (Y): 684759
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 125PZ-001

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 12.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 7.5 | 2 | PVC | sch 40 |
| Screen | 7.5 | 12.5 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 12.5 | 2 | 0 | 0 | 22 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004255**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** SA-6 SOUTH SITE

Address: 200 KELLOGG STREET 125-PZ-002

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602605 Northing (Y): 684762
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 125PZ-002

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 25.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 20.5 | 2 | PVC | SH40 |
| Casing | 0 | 16 | 6 | PVC | SH40 |
| Screen | 20.5 | 25.5 | 2 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 25.5 | 2 | 0 | 0 | 45 | 2.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Brian Buttari

Obstruction Type:

Authorization Number: A1402042

Alternative Decomm. Method? No

Authorization Date: February 25, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004263**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 124-PZ-003

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20 & 11W Block: 1290.A

Easting (X): 602723 Northing (Y): 684482
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 125-PZ-003

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 8

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 2 | PVC | sch 40 |
| Screen | 3 | 8 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 8 | 2 | 0 | 0 | 14.5 | 0.8 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004256**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 124-PZ-004

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20, 11W Block: 1290.A

Easting (X): 602729 Northing (Y): 684487
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 125-PZ-004

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 24.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 19.5 | 2 | PVC | sch 40 |
| Screen | 19.5 | 24.5 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 24.5 | 2 | 0 | 0 | 44 | 2.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Brian Buttari

Obstruction Type:

Authorization Number: A1402043

Alternative Decomm. Method? No

Authorization Date: February 25, 2014

Method Used

ATTACHMENTS:

Sealing Driller: Mark Christman
JOURNEYMAN
LICENSE # 0021241

Company: B & B DRILLING INC
BOX 8 RT 206
Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075501**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: PO Box 4900 Dept 356 Scottsdale, Arizona 85261

**WELL LOCATION:** Honeywell

Address: 100 KELLOGG ST OLD DOMINION

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602039 Northing (Y): 685209
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 4, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-01

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 15

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 1 | 2 | PVC | |
| Screen | 1 | 15 | 2 | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 15 | 2 | 0 | 0 | 27 | 1.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600047317**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** TYL REALTY ASSOCIATES

Company/Organization: TYL Realty Associates

Address: Hackensack Ave., Bldg. #4-D Kearny Town, New Jersey 07032

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 100 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 11L,11Y Block: 1290.A

Easting (X): 602199 Northing (Y): 684965
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 26, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 134-MW-Q08

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 2 | PVC | sch 40 |
| Screen | 3 | 13 | 2 | PVC | .020 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 2 | 0 | 0 | 23 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004259**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 134-PZ-001

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20 & 11W Block: 1290.A

Easting (X): 601817 Northing (Y): 685164
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 28, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 134-PZ-001

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 15.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 10.5 | 2 | PVC | sch 40 |
| Screen | 10.5 | 15.5 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 15.5 | 2 | 0 | 0 | 28.2 | 1.6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004260**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 134-PZ-003

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20 & 11W Block: 1290.A

Easting (X): 602133 Northing (Y): 685110
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 1, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 134-PZ-003

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 12.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 7.5 | 2 | PVC | sch 40 |
| Screen | 7.5 | 12.5 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 12.5 | 2 | 0 | 0 | 22 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004253**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 134-PZ-004

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20,11W Block: 1290.A

Easting (X): 602126 Northing (Y): 685111
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 1, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 134-PZ-004

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 26

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 16 | 2 | PVC | sch 40 |
| Screen | 21 | 26 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 26 | 2 | 0 | 0 | 46 | 2.6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Brian Buttari

Obstruction Type:

Authorization Number: A1402044

Alternative Decomm. Method? No

Authorization Date: February 25, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600075506**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: PO Box 4900 Dept 356 Scottsdale, Arizona 85261

**WELL LOCATION:** Honeywell

Address: 80 KELLOGG ST ABF TRUCKING

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602282 Northing (Y): 685043
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** April 4, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-01

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 15

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 2 | 2 | PVC | |
| Screen | 2 | 15 | 2 | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 15 | 2 | 0 | 0 | 27 | 1.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Bayfront Redevelopment

Address: Kellogg St. Bayfront Redevelopment

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602540 Northing (Y): 684834
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** May 30, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-NW-06

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3.4 | 4 | PVC | Sh40 |
| Screen | 3.4 | 5.4 | 4 | PVC | Unknown |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 5.4 | 4 | 0 | 0 | 35 | 2 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1405120

Alternative Decomm. Method? No

Authorization Date: May 23, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Bayfront Redevelopment

Address: Kellog St.

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602442 Northing (Y): 684702
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** May 30, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-07

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 4.4 | 4 | PVC | Sc40 |
| Screen | 4.4 | 6.4 | 4 | PVC | Unknown |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 6.4 | 4 | 0 | 0 | 45 | 2.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1405121

Alternative Decomm. Method? No

Authorization Date: May 23, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201009351**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG STREET 80 PROP.%T.REUTERS

Company/Organization: 80 Kellogg Street

Address: PO Box 4900 Dept 356 Scottsdale, Arizona 85261

**WELL LOCATION:** 80 KELLOGG

Address: 80 KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602401 Northing (Y): 684616
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 10, 2016

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-08

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 10

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 2 | 2 | PVC | |
| Screen | 2 | 10 | 2 | PVC | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10 | 2 | 0 | 0 | 18 | 1 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Douglas Myerchin
MASTER
Sealing Driller: LICENSE # 0001612

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Bayfront Redevelopment

Address: Kellogg St.

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602173 Northing (Y): 684746
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** May 30, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 140-MW-106

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.):

Was a New Well Drilled? Y

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 5.3 | 2 | PVC | Sc40 |
| Screen | 5.3 | 7.3 | 2 | PVC | Unknown |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 7.3 | 2 | 0 | 0 | 13 | 0.75 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1405122

Alternative Decomm. Method? No

Authorization Date: May 23, 2014

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004261**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 140-PZ-001

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20 & 11W Block: 1290.A

Easting (X): 602237 Northing (Y): 684845
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 28, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 140-PZ-001

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 11

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 6 | 2 | PVC | sch 40 |
| Screen | 6 | 11 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 11 | 2 | 0 | 0 | 20 | 1.1 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**P201004254**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** KELLOGG ST. PROPERTY, LLC

Company/Organization: Kellogg St. Property, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 200 KELLOGG STREET 140-PZ-002

County: Hudson Municipality: Jersey City Lot: 9L,17,18,19,20,11W Block: 1290.A

Easting (X): 602240 Northing (Y): 684851
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 28, 2014

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** 140-PZ-002

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 24.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 19.5 | 2 | PVC | sch 40 |
| Screen | 19.5 | 24.5 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 24.5 | 2 | 0 | 0 | 44 | 2.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201115326**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: Bayfront Redevelopment, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 75 Kellogg Street

County: Hudson Municipality: Jersey City Lot: 9.0H Block: 1290.0A

Easting (X): 602293 Northing (Y): 685390
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 25, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 163-MW-CC8R

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 15

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 5 | 2 | PVC | sch 40 |
| Screen | 5 | 15 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 15 | 2 | 0 | 0 | 27 | 1.5 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**2600047308**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** POSNAK & TURKISH, INC.

Company/Organization: Posnak & Turkish, Inc.

Address: P.O. Box 1775 Bayonne, New Jersey 07002

**WELL LOCATION:** Honeywell Redevelopment Project

Address: FOOT OF KELLOGG ST.

County: Hudson Municipality: Jersey City Lot: 9H Block: 1290.A

Easting (X): 601979 Northing (Y): 684776
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 26, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 163-MW-R05

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 2 | PVC | sch 40 |
| Screen | 3 | 13 | 2 | PVC | .020 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 2 | 0 | 0 | 23 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201115328**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: Bayfront Redevelopment, LLC

Address: 101 Columbia Rd. Morristown, New Jersey 07962

**WELL LOCATION:** Honeywell Redevelopment Project

Address: 75 Kellogg Street

County: Hudson Municipality: Jersey City Lot: 9.0H Block: 1290.0A

Easting (X): 601552 Northing (Y): 685509
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** February 26, 2014

**WELL USE:** MONITORING

**Other Use(s):**

**Local ID:** 163-MW-Y6R

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 2 | PVC | sch 40 |
| Screen | 3 | 13 | 2 | PVC | .010 |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 2 | 0 | 0 | 23 | 1.3 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Mark Christman
JOURNEYMAN
Sealing Driller: LICENSE # 0021241

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201312361**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Former Roosvelt Bowling Lanes

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 603064 Northing (Y): 684266
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 4, 2015

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-01

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 44.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 19.5 | 6 | PVC | SH40 |
| Casing | 0 | 13 | 10 | Steel | SH40 |
| Screen | 19.5 | 44.5 | 6 | pvc | 0.020" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 44.5 | 6 | 0 | 0 | 712 | 40 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1502071

Alternative Decomm. Method? No

Authorization Date: February 27, 2015

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313208**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Former Delphic Consolidated

Address: 60 Kellogg St Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602394 Northing (Y): 684743
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 4, 2015

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-02

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 46

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 14 | 10 | Steel | SH40 |
| Casing | 0 | 21 | 6 | PVC | SH40 |
| Screen | 21 | 46 | 6 | PVC | 0.020" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 46 | 6 | 0 | 0 | 734 | 40 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1502072

Alternative Decomm. Method? No

Authorization Date: February 27, 2015

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313209**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Former Old Dominion

Address: 100 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602304 Northing (Y): 684743
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 6, 2015

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-03

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 46

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 21 | 6 | PVC | SH40 |
| Casing | 0 | 15.5 | 10 | PVC | Sh40 |
| Screen | 21 | 46 | 6 | PVC | 0.020" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 46 | 6 | 0 | 0 | 735 | 40 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1502073

Alternative Decomm. Method? No

Authorization Date: February 27, 2015

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313210**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Former ABF Trucking

Address: 80 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602047 Northing (Y): 685060
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 6, 2015

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-04

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 48

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 23 | 6 | PVC | SH40 |
| Casing | 0 | 17 | 10 | Steel | Sh40 |
| Screen | 23 | 48 | 6 | PVC | 0.020" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 48 | 6 | 0 | 0 | 770 | 45 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1502074

Alternative Decomm. Method? No

Authorization Date: February 27, 2015

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201313226**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Former Boatyard

Address: 150 Kellogg St. Well dischaged to on-site treatment

County: Hudson Municipality: Jersey City Lot: 2 Block: 24601

Easting (X): 601735 Northing (Y): 685278
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 6, 2015

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-O5

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 50

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 25 | 6 | PVC | sh40 |
| Casing | 0 | 19.5 | 10 | Steel | Sh40 |
| Screen | 25 | 50 | 6 | PVC | 0.020" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 50 | 6 | 0 | 0 | 800 | 45 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1502075

Alternative Decomm. Method? No

Authorization Date: February 27, 2015

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201514336**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: PO Box 4900 Dept 356 Scottsdale, Arizona 85261

**WELL LOCATION:** Bayfront Redevelopment

Address: Kellogg St

County: Hudson Municipality: Jersey City Lot: 11 Block: 24601

Easting (X): 601529 Northing (Y): 685182
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 22, 2016

**WELL USE:** DEWATERING

**Other Use(s):**

**Local ID:** DW-8

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 48

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 23 | 6 | PVC | sch 40 |
| Screen | 23 | 48 | 6 | PVC | 0.030" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 48 | 6 | 0 | 0 | 770 | 43 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official: Lynn Stout

Obstruction Type:

Authorization Number: A1603066

Alternative Decomm. Method? No

Authorization Date: March 21, 2016

Method Used


ATTACHMENTS:

Gordon Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0021852

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

# APPENDIX G

# PREVIOUS GROUNDWATER SAMPLING RESULTS




## LEGEND

- MONITORING WELL LOCATION
- EXISTING BUILDING
- DEMOLISHED BUILDING LOCATION
- PROPERTY LINE
- EXISTING FENCE
- EXISTING ELEVATION CONTOUR
- PROPOSED LIMIT OF CHROMIUM REMEDIAL ACTION
- PROPOSED HYDRAULIC BARRIER (SA-6 SOUTH)

NJDEP GROUNDWATER QUALITY STANDARDS ug/L

| GWQS 2010 (ug/L) | |
|---|---|
| CHROMIUM | 70 |

NOTES:

1. ALL RESULTS EXPRESSED IN ug/L.
2. **5880** BOLD INDICATES COMPOUND GREATER THAN NJDEP GWQS.
3. J = ESTIMATED CONCENTRATION
4. U = NOT DETECTED
5. B = COMPOUND FOUND IN ASSOCIATED BLANK
6. NT = NOT TESTED

0 50 100 200
SCALE IN FEET

| 073-MW-BB11 | | | | |
|---|---|---|---|---|
| Sample Date | 6/24/2010 (unfiltered) | 6/24/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | 64.4 | 11.1 | 66.6 | 10.3 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 073-MW-5 | | | | |
|---|---|---|---|---|
| Sample Date | 6/24/2010 (unfiltered) | 6/24/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | 48 | **70.8** | 33.1 | 28.7 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 13 | 12 |

| 073-MW-Y10 | | | | |
|---|---|---|---|---|
| Sample Date | 6/24/2010 (unfiltered) | 6/24/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | 11.8 | 10 U | 10 U | 10 U |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 073-MW-4 | | |
|---|---|---|
| Sample Date | 12/14/2010 (unfiltered) | 12/14/2010 (filtered) |
| CHROMIUM | **362** | NT |
| HEXAVALENT CHROMIUM | NT | NT |

| 134-MW-V09 | | | | |
|---|---|---|---|---|
| Sample Date | 6/24/2010 (unfiltered) | 6/24/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | **751** | 23.4 JB | **255** | 23.2 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 134-MW-01 | | | | |
|---|---|---|---|---|
| Sample Date | 6/24/2010 (unfiltered) | 6/24/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | **3150** | **4210** | **3640** | **3470** |
| HEXAVALENT CHROMIUM | 3500 | 4500 | 4200 | 3500 |

| 134-MW-Q08 | | | | |
|---|---|---|---|---|
| Sample Date | 6/25/2010 (unfiltered) | 6/25/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | 19 | 10 U | 10 U | 49.4 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 140-MW-01 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | 47.5 JB | 10 U | 50.5 | 13.5 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 140-MW-06 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | **905** | 11.2 B | **2440** | 25 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 17 |

| 140-MW-07 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | **1070** | 10 U | **83.6** | 10 U |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 125-MW-01 | | | | |
|---|---|---|---|---|
| Sample Date | 6/25/2010 (unfiltered) | 6/25/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | **1190** | **1090** | **308** | **160** |
| HEXAVALENT CHROMIUM | 710 | 950 | 120 | 78 |

| 125-MW-01DP | | | | |
|---|---|---|---|---|
| Sample Date | 6/25/2010 (unfiltered) | 6/25/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | **1180** | **1210** | **388** | **140** |
| HEXAVALENT CHROMIUM | 790 | 930 | 130 | 24 |

| 124-MW-07 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | **8510** | **9170** | **9360** | **9950** |
| HEXAVALENT CHROMIUM | 8200 | 8300 | 9000 | 9200 |

| 124-MW-02 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | **5880** | **7370** | **120000** | **137000** |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 50 U | 50 U |

| 073-MW-3 | | |
|---|---|---|
| Sample Date | 12/14/2010 (unfiltered) | 12/14/2010 (filtered) |
| CHROMIUM | **607** | NT |
| HEXAVALENT CHROMIUM | NT | NT |

| 073-MW-3DP | | |
|---|---|---|
| Sample Date | 12/14/2010 (unfiltered) | 12/14/2010 (filtered) |
| CHROMIUM | **592** | NT |
| HEXAVALENT CHROMIUM | NT | NT |

| 163-MW-CC8R | | | | |
|---|---|---|---|---|
| Sample Date | 10/21/2011 (unfiltered) | 10/21/2011 (filtered) | 11/28/2011 (unfiltered) | 11/28/2011 (filtered) |
| CHROMIUM | **104** | 27.8 | 43.4 | 55.5 |
| HEXAVALENT CHROMIUM | 5 U | 5 U | 5.5 U | 5.5 U |

| 163-MW-CC8R - DUP | | | | |
|---|---|---|---|---|
| Sample Date | 10/21/2011 (unfiltered) | 10/21/2011 (filtered) | 11/28/2011 (unfiltered) | 11/28/2011 (filtered) |
| CHROMIUM | **94.2** | 27.9 | **79.9** | 64.8 |
| HEXAVALENT CHROMIUM | 5 U | 5 U | 5.5 U | 5.5 U |

| 163-MW-2R | | | | |
|---|---|---|---|---|
| Sample Date | 10/21/2011 (unfiltered) | 10/21/2011 (filtered) | 11/28/2011 (unfiltered) | 11/28/2011 (filtered) |
| CHROMIUM | 10 | 10 U | 13.4 | 10 U |
| HEXAVALENT CHROMIUM | 5.5 U | 5.5 U | 5.5 U | 5.5 U |

| 163-MW-2 | | | | |
|---|---|---|---|---|
| Sample Date | 6/25/2010 (unfiltered) | 6/25/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | 10 U | 10 U | 20.7 | 10 U |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 163-MW-Y6R | | | | |
|---|---|---|---|---|
| Sample Date | 10/21/2011 (unfiltered) | 10/21/2011 (filtered) | 11/28/2011 (unfiltered) | 11/28/2011 (filtered) |
| CHROMIUM | **83.1** | 22.8 | **105** | 43.6 |
| HEXAVALENT CHROMIUM | 5.5 U | 5.5 U | 5.5 U | 5.5 U |

| 163-MW-1 | | | | | | |
|---|---|---|---|---|---|---|
| Sample Date | 6/25/2010 (unfiltered) | 6/25/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) | 4/16/2012 (unfiltered) | 4/16/2012 (filtered) |
| CHROMIUM | **127** | 49.4 | **95.3** | **147** | **76.8** | 25 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 | 10 U | 5.5 U | 5.5 U |

| 140-MW-04 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | 10 U | 10 U | 11.8 | 10 U |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 140-MW-106 | | | | |
|---|---|---|---|---|
| Sample Date | 6/23/2010 (unfiltered) | 6/23/2010 (filtered) | 8/3/2010 (unfiltered) | 8/3/2010 (filtered) |
| CHROMIUM | 26.2 JB | 10 U | 29.9 | 10 U |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 134-MW-02 | | | | |
|---|---|---|---|---|
| Sample Date | 9/8/2010 (unfiltered) | 9/8/2010 (filtered) | 10/6/2010 (unfiltered) | 10/6/2010 (filtered) |
| CHROMIUM | 10 U | 10 U | 10.9 | 10 U |
| HEXAVALENT CHROMIUM | NT | NT | NT | NT |

| 163-MW-R05 | | | | |
|---|---|---|---|---|
| Sample Date | 6/24/2010 (unfiltered) | 6/24/2010 (filtered) | 8/2/2010 (unfiltered) | 8/2/2010 (filtered) |
| CHROMIUM | 48.6 JB | 23.7 JB | **244** | 30.3 |
| HEXAVALENT CHROMIUM | 10 U | 10 U | 10 U | 10 U |

| 124-MW-11 | | | | |
|---|---|---|---|---|
| Sample Date | 10/19/2010 (unfiltered) | 10/19/2010 (filtered) | 4/26/2011 (unfiltered) | 4/26/2011 (filtered) |
| CHROMIUM | 30.2 | 4 U | 4.1 | 4 U |
| HEXAVALENT CHROMIUM | 5.5 UJ | 5.5 UJ | 5.5 UJ | 5.5 UJ |

| 124-MW-10 | | | | | | |
|---|---|---|---|---|---|---|
| Sample Date | 10/19/2010 (unfiltered) | 10/19/2010 (filtered) | 4/26/2011 (unfiltered) | 4/26/2011 (filtered) | 4/26/2011 (filtered) DP | 4/26/2011 (filtered) DP |
| CHROMIUM | 15.8 | 11.3 | 5.3 | 5.4 | 5 | 5 |
| HEXAVALENT CHROMIUM | 5.5 UJ | 5.5 UJ | 5.5 UJ | 5.5 UJ | 5.5 UJ | 5.5 UJ |

| 140-MW-08 | | | | |
|---|---|---|---|---|
| Sample Date | 9/8/2010 (unfiltered) | 9/8/2010 (filtered) | 10/6/2010 (unfiltered) | 10/6/2010 (filtered) |
| CHROMIUM | 10 U | 10 U | 10 U | 10 U |
| HEXAVALENT CHROMIUM | NT | NT | NT | NT |

| 140-MW-08DP | | | | |
|---|---|---|---|---|
| Sample Date | 9/8/2010 (unfiltered) | 9/8/2010 (filtered) | 10/6/2010 (unfiltered) | 10/6/2010 (filtered) |
| CHROMIUM | 10 U | 10 U | 10 U | 10 U |
| HEXAVALENT CHROMIUM | NT | NT | NT | NT |

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| 3 | 05/15/12 | REVISE HYDRAULIC BARRIER WALL, REPLACE 163-MW-1 CHEM BOX | STR | MM |
| 2A | 03/07/12 | TITLE BLOCK EDITS | DL | MM |
| 2 | 01/11/12 | ABANDON 163-MW-2 & CC8, ADD 163-MW-CC8R, 2R & Y6R & CHEMBOXES | STR | MM |
| 1A | 09/21/11 | ADDED CHEM BOXES FOR 073-MW-3/073-MW-4/140-MW-08/134-MW-02 | DL | MM |
| 1 | 04/27/11 | UPDATED BUILDING STATUS | DL | MM |

*AMEC PROJECT No.* 3480120317
*DRAWING:* SA6-S SITE AREA RESULTS

*PREPARED/DATE:* DL 04/01/11

*CHECKED/DATE:* MM 04/19/11

amec
ENVIRONMENT & INFRASTRUCTURE
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 8**
GROUNDWATER MONITORING WELL LOCATIONS AND SAMPLE RESULTS
PRE-DESIGN INVESTIGATION SUMMARY REPORT
100% REMEDIAL DESIGN
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\CADD\VONEWELL\JERSEY CITY\SA 6 SOUTH\CHROME 100% REMEDIAL DESIGN\CURRENT DRAWINGS\SA6-S SITE AREA RESULTS.dwg Tue, 15 May 2012 - 4:59pm rcostudillo Layout: SITE

| Field Sample ID | 073-MW-BB11 | 073-MW-BB11 | 073-MW-BB11 | 073-MW-BB11DP | 073-MW-BB11 | 073-MW-BB11 |
|---|---|---|---|---|---|---|
| Sample Date | 8/27/1997 | 9/30/1998 | 7/6/2005 | 7/6/2005 | 8/9/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 2,990 | 2,340 | 6,160 | 7,160 | 447 | 387 |
| Hexavalent Chromium | 2,080 | 1,840 | 100 U | 100 U | 10 U | 20 UJ |
| Chromium (F) | 2,990 | 1,780 | 9.8 | 11.8 | 7.2 | 5.9 |
| Hexavalent Chromium (F) | 1,900 | 1,620 | 10 U | 10 U | 10 U | 10 UJ |

| Field Sample ID | 073-MW-Y10 | 073-MW-Y10 | 073-MW-Y10 | 073-MW-Y10 | 073-MW-Y10DUP | 073-MW-Y10 |
|---|---|---|---|---|---|---|
| Sample Date | 10/21/1997 | 6/30/1998 | 7/6/2005 | 8/9/2005 | 8/9/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 77.4 | 13.3 | 13 | 21.8 | 17.6 | 11.2 |
| Hexavalent Chromium | 14.2 | 10 U | 10 U | 10 U | 10 U | 10 UJ |
| Chromium (F) | 15.3 | 13.4 | 5.2 | 7.1 | 6.9 | 5.6 |
| Hexavalent Chromium (F) | 10.7 | 10 U | 17.1 | 10 U | 10 U | 10 UJ |

| Field Sample ID | 134-MW-V9 | 134-MW-V9 | 134-MW-V9 | 134-MW-V9 | 134-MW-V09 | 134-MW-V09 |
|---|---|---|---|---|---|---|
| Sample Date | 10/14/1997 | 7/8/1998 | 4/15/2003 | 7/7/2005 | 8/12/2005 | 5/23/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 475 | 168 | 223 | 1240 | 744 | 97 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 10 U | 100 | 10 UJ |
| Chromium (F) | 7.3 | 37.1 | 46.4 | 10.7 | 14 | 4.9 |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U | 10 U | 10 U | 10 UJ |

| Field Sample ID | 134-MW-01 | 134-MW-01 | 134-MW-01 |
|---|---|---|---|
| Sample Date | 7/7/2005 | 8/12/2005 | 5/23/2006 |
| Units | ug/L | ug/L | ug/L |
| Chromium | 10,000 | 9,390 | 11,000 |
| Hexavalent Chromium | 12,000 | 9,990 | 10,500 |
| Chromium (F) | 10,400 | 9,010 | 10,200 |
| Hexavalent Chromium (F) | 11,900 | 9,540 | 9,470 |

| Field Sample ID | 134-MW-Q8 | 134-MW-Q8 | 134-MW-Q8 | 134-MW-Q8 | 134-MW-Q08 | 134-MW-Q08 |
|---|---|---|---|---|---|---|
| Sample Date | 10/14/1997 | 7/8/1998 | 4/15/2003 | 7/7/2005 | 8/12/2005 | 5/23/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 11.7 | 2.9 U | 12.5 | 9 | 20.7 | 6.7 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 10 U | 10 U | 10 UJ |
| Chromium (F) | 4.8 | 2.9 U | 1.2 | 3.7 | 4 | 3.9 |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U | 10 U | 10 U | 10 UJ |


| Field Sample ID | 140-MW-01 | 140-MW-01 | 140-MW-01 |
|---|---|---|---|
| Sample Date | 7/7/2005 | 8/11/2005 | 5/23/2006 |
| Units | ug/L | ug/L | ug/L |
| Chromium | 78.8 | 168 | 11.3 |
| Hexavalent Chromium | 14 | 10 U | 10 UJ |
| Chromium (F) | 14.8 | 2.6 U | 3 |
| Hexavalent Chromium (F) | 17.1 | 10 U | 10 UJ |

| Field Sample ID | 140-MW-7 | 140-MW-7 | 140-MW-7 | 140-MW-7 | 140-MW-7 |
|---|---|---|---|---|---|
| Sample Date | 11/30/1997 | 7/10/1998 | 7/07/2005 | 8/11/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 36.1 | 24.9 | 154 | 53.4 | 16.9 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 10 U | 10 U |
| Chromium (F) | 9.7 | 5.5 | 6.9 | 2.8 U | 3 U |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U | 10 U | 10 U |

| Field Sample ID | 140-MW-06 | 140-MW-06 | 140-MW-06 | 140-MW-06 | 140-MW-06 |
|---|---|---|---|---|---|
| Sample Date | 11/3/1997 | 7/15/1998 | 7/7/2005 | 8/11/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 6,720 | 6,830 | 2,870 | 3,820 | 1,400 |
| Hexavalent Chromium | 7,400 | 6,320 | 3,330 | 3,740 | 797 |
| Chromium (F) | 7,320 | 7,090 | 2,810 | 3,300 | 2,930 |
| Hexavalent Chromium (F) | 7,460 | 6,940 | 3,180 | 4,670 | 1,480 |

| Field Sample ID | 125-MW-01 | 125-MW-01 | 125-MW-01 |
|---|---|---|---|
| Sample Date | 7/6/2005 | 8/11/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L |
| Chromium | 3,510 | 2,810 | 607 |
| Hexavalent Chromium | 3,300 | 2,710 | 10 U |
| Chromium (F) | 2,830 | 2,210 | 171 |
| Hexavalent Chromium (F) | 3,130 | 2,560 | 10 U |

| Field Sample ID | 124-MW-01 | 124-MW-01 | 124-MW-01 | 124-MW-01_DUP |
|---|---|---|---|---|
| Sample Date | 7/6/2005 | 8/10/2005 | 5/22/2006 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L | ug/L |
| Chromium | 20,900 | 24,700 | 25,100 | 23,800 |
| Hexavalent Chromium | 22,500 | 27,100 | 23,700 | 24,200 |
| Chromium (F) | 21,000 | 25,600 | 21,200 | 21,200 |
| Hexavalent Chromium (F) | 22,000 | 26,500 | 21,800 | 21,200 |




| Field Sample ID | 163-MW-Y6H | 163-MW-Y6L | 163-MW-Y6H | 163-MW-Y6L | 163-MW-Y6 |
|---|---|---|---|---|---|
| Location | 10/20/1997 | 10/21/1997 | 6/30/1998 | 6/30/1998 | 8/10/2005 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 88.5 | 14.7 | 3.2 | 2.9 U | 9.3 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 10 U | 10 U |
| Chromium (F) | 8.6 | 5.8 | 3.4 | 2.9 U | 3 U |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U | 10 U | 10 U |

| Field Sample ID | 163-MW-CC8H | 163-MW-CC8L | 163-MW-CC8H | 163-MW-CC8L | 163-MW-CC8 | 163-MW-CC8 | 163-MW-CC08 | 163-MW-CC08 |
|---|---|---|---|---|---|---|---|---|
| Location | 10/20/1997 | 10/21/1997 | 6/29/1998 | 7/1/1998 | 4/15/2003 | 7/8/2005 | 8/10/2005 | 5/23/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 22.2 | 11.9 | 10.8 | 16.5 | 27 | 53 | 9.4 | 91.3 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 19.8 | 10 U | 10 U | 10 U | 10 UJ |
| Chromium (F) | 9 U | 4.5 U | 5.8 B | 12.5 | 33 | 5.7 | 6.1 | 14.4 |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U | 17.3 | 10 U | 10 U | 10 U | 10 UJ |

STUDY AREA 6 SOUTH
(BLOCK

| Field Sample ID | 140-MW-106 | 140-MW-106 | 140-MW-106 |
|---|---|---|---|
| Sample Date | 7/7/2005 | 8/11/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L |
| Chromium | 17.6 | 10.9 | 15.7 |
| Hexavalent Chromium | 10 U | 10 U | 10 U |
| Chromium (F) | 4.8 | 3.8 | 3.3 |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U |

| Field Sample ID | 163-MW-R5 | 163-MW-R5 | 163-MW-R5 | 163-MW-R5 | 163-MW-R05 | 163-MW-R05 | 163-MW-R05 |
|---|---|---|---|---|---|---|---|
| Location | 10/20/1997 | 6/29/1998 | 4/15/2003 | 4/15/2003 | 7/8/2005 | 8/10/2005 | 5/23/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 236 | 78.4 | 12.2 | 28.7 | 68.2 | 284 | 39.6 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 12.2 | 10 U | 10 U | 10 U |
| Chromium (F) | 188 | 70.1 | | 12.2 | 6 | 228 | 11 |
| Hexavalent Chromium (F) | 10 U | 10 U | | 10 U | 10 U | 10 U | 10 U |

| Field Sample ID | 125-MW-L3 | 125-MW-L3 | 125-MW-L3 |
|---|---|---|---|
| Sample Date | 9/3/1997 | 7/10/1998 | 4/16/2003 |
| Units | ug/L | ug/L | ug/L |
| Chromium | 8.2 | 2.4 | 16.1 |
| Hexavalent Chromium | 10 U | 10 U | 10 U |
| Chromium (F) | 5.5 U | 2.5 | 1.8 |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U |

| Field Sample ID | 140-MW-04 | 140-MW-04 | 140-MW-04 | 140-MW-04 | 140-MW-04 |
|---|---|---|---|---|---|
| Sample Date | 11/04/1997 | 7/10/1998 | 7/7/2005 | 8/11/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L | ug/L | ug/L |
| Chromium | 10.4 | 8.2 | 9.6 | 11.5 | 14 |
| Hexavalent Chromium | 10 U | 10 U | 10 U | 10 U | 10 U |
| Chromium (F) | 8.8 | 5.1 | 4.7 | 4.8 | 6.3 |
| Hexavalent Chromium (F) | 10 U | 10 U | 10 U | 10 U | 10 U |

| Field Sample ID | 124-MW-02 | 124-MW-02 | 124-MW-02 |
|---|---|---|---|
| Sample Date | 7/6/2005 | 8/10/2005 | 5/22/2006 |
| Units | ug/L | ug/L | ug/L |
| Chromium | 6,820 | 3,040 | 4,080 |
| Hexavalent Chromium | 6,460 | 2,430 | 1,250 |
| Chromium (F) | 6,060 | 2,060 | 5,180 |
| Hexavalent Chromium (F) | 6,360 | 2,140 | 1,270 |

## LEGEND

- SHALLOW DEPTH MONITORING WELL
- SHALLOW GROUNDWATER DATA INDICATE DISSOLVED TOTAL CHROMIUM ABOVE NJDEP GWQS (MOST RECENT SAMPLING)
- SHALLOW GROUNDWATER DATA INDICATE TOTAL CHROMIUM (DISSOLVED/FILTERED) AND HEXAVALENT CHROMIUM BELOW NJDEP GWQS (MOST RECENT SAMPLING)
- APPROXIMATE LIMITS OF AREA WHERE DETECTED HEXAVALENT CHROMIUM CONCENTRATION VALUES > 1000 mg/kg
- APPROXIMATE LIMITS OF AREA WHERE DETECTED HEXAVALENT CHROMIUM CONCENTRATION VALUES > 20 mg/kg
- PROPOSED CAP AREA
- SITE 073 PROPERTY BOUNDARY
- SITE 124 PROPERTY BOUNDARY
- SITE 125 PROPERTY BOUNDARY
- SITE 134 PROPERTY BOUNDARY
- SITE 140 PROPERTY BOUNDARY
- SITE 163 PROPERTY BOUNDARY
- CORDOVA PROPERTY BOUNDARY
- BOATYARD PROPERTY BOUNDARY
- SITE BOUNDARY

NOTES:

1. BORING LOCATIONS AND MONITORING WELL LOCATIONS SURVEYED BY KELLER AND KIRKPATRICK , JULY 2005. HORIZONTAL DATUM NAD 1983.
2. **BOLD** VALUES INDICATE THAT DETECTED CONCENTRATION EXCEEDS THE NJDEP GWQS OF 70 ug/L FOR TOTAL CHROMIUM.

0 50 100 200
SCALE IN FEET

| REV. | DATE | STATUS | BY |
|---|---|---|---|

MACTEC PROJECT No. 3480050143
DRAWING: SA-6 SOUTH – FIGURE 3 THROUGH FIGURE 9

PREPARED/DATE: DS 12/22/08

CHECKED/DATE: DN 12/22/08

MACTEC
MACTEC Engineering and Consulting
200 American Metro Boulevard, Suite 113
Hamilton, NJ 08619

**FIGURE 8**
**SHALLOW GROUNDWATER SAMPLE RESULTS**
**TOTAL AND HEXAVALENT CHROMIUM**
**STUDY AREA 6 SOUTH**
**SITES 073, 124, 125, 134, & 140,**
**JERSEY CITY, NEW JERSEY**

P:\Active Projects\Honeywell_Jersey City\CADD sa-6\6 SOUTH\SUBMITTAL 12-22-08 - 6 SOUTH AREAS 073, 124, 134, 140\SA-6 SOUTH - FIGURE 3 THROUGH FIGURE 9.dwg Mon, 22 Dec 2008 - 2:33pm ogiambattista Layout: FIG 08

**APPENDIX H**

**BORING LOGS**
**(CD ONLY)**

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 073-MW-06
**DATE BEGAN:** 2-17-16
**DATE FINISHED:** 2-17-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 20' bgs
**GW DEPTH:** 3.8' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 3 | 2.0 | | 14.0 - 14.5' SM: Reddish brown fine SAND and SILT | NM | Augered to 14' bgs<br>Starting elevation 9.3'<br>GW elevation 5.5' |
| | | | 2 | | | 14.5 - 15.4' SW: Gray and reddish brown fine to coarse SAND, some silt | | |
| | 15.0 | | 4 | | | | | Meadow mat expected at -6 to -7 elevation (15.0-16.0' bgs) |
| | | | 4 | | | 15.4 - 16.0' ML: Reddish brown SILT, trace fine sand; medium dense, wet | | |
| | 16.0 | SS2 | 2 | 2.0 | | 16.0 - 18.0' ML: Reddish brown CLAYEY SILT, some fine to coarse sand; medium dense, wet | | |
| | | | 2 | | | | | |
| | 17.0 | | 3 | | | | | |
| | | | 3 | | | | | |
| | 18.0 | SS3 | 1 | 2.0 | | 18.0 - 19.5' ML: Reddish brown CLAYEY SILT | | |
| | | | 2 | | | | | |
| | 19.0 | | 2 | | | | | |
| | | | 3 | | | 19.5 - 19.7' ML: Black SILT | | |
| | | | | | | 19.7 - 19.8' OL: Gray SILT with organics | | |
| | 20.0 | | | | | 19.8 - 20.0' PT: Dark brown PEAT. End of boring at 20.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 073-MW-07
**DATE BEGAN:** 2-23-16
**DATE FINISHED:** 2-23-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Air Rotary
**DRILL EQUIP:**
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17' bgs
**GW DEPTH:** 2.5' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | 5 | 2.0 | | 15.0 - 16.0' SW: Reddish brown fine SAND; loose, wet | NM | Augered to 15' bgs<br>Starting elevation 7.5'<br>GW elevation 5.0'<br>Sheen on auger spoils |
| | | | 1 | | | | | |
| | 16.0 | | 2 | | | 16.0 - 16.6' OL: Black SILT, organic fibers at 16.5' | | |
| | | | 4 | | | | | |
| | 17.0 | | | | | 16.6 - 17.0' PT: Dark brown PEAT. End of boring at 17.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 073-MW-08
**DATE BEGAN:** 2-12-16
**DATE FINISHED:** 2-16-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 2.4' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | SS1 | 1 | 2.0 | | 12.0 - 13.4' ML: Reddish brown CLAYEY SILT; loose, wet | NM | Augered to 12' bgs<br>Starting elevation 7.4'<br>GW elevation 5.0' |
| | | | 2 | | | | | |
| | 13.0 | | 4 | | | | | |
| | | | 9 | | | 13.4 - 14.0' SW: Reddish brown fine SAND; medium dense, wet | | |
| | 14.0 | SS2 | 1 | 2.0 | | 14.0 - 14.3' SM: Reddish brown fine SAND and SILT | | |
| | | | 2 | | | 14.3 - 15.5' ML: Black SILT | | |
| | 15.0 | | 1 | | | | | |
| | | | 3 | | | 15.5 - 16.0' PT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073- Deagan Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-001
**DATE BEGAN:** 7/9/2008
**DATE FINISHED:** 7/14/08
**INSPECTOR:** B. Senna/ E. Jackson
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 4 | | 0.0 - 0.5' ASPHALT: Asphalt | NA | First attempt 7/9/2008 with truck mounted rig, refusal @ 2' bgs; re-mobilized on7/14/08 with 6610DT track mounted geoprobe rig |
| | | | | | | 0.5 - 1.0' FILL: Brown silty sand, some asphalt (fine-coarse), dry | | |
| | -1.0 | | | | | 1.0 - 3.0' FILL: Concrete | | PID/4-gas meter malfunctioning due to rain; Collect sample from 0.5-1' bgs @ 8:13 |
| | -2.0 | | | | | | | Collect sample from 3-3.5' bgs @ 8:15 |
| | -3.0 | | | | | 3.0 - 3.8' FILL: Light brown sand (fine-medium), moist | | |
| | | | | | | 3.8 - 4.0' FILL: Dark brown silty clay, moist | | |
| | -4.0 | 2 | NA | 4 | | 4.0 - 4.3' FILL: Concrete | NA | Collect sample from 4.5-5' bgs @ 8:19 |
| | | | | | | 4.3 - 4.8' FILL: Light brown sand (fine-medium), medium dense, wet | | |
| | -5.0 | | | | | 4.8 - 6.0' FILL: light red/brown silty sand (fine), dense, wet | | |
| | -6.0 | | | | | 6.0 - 8.0' FILL: Light red/brown sand (fine-coarse) some layers of silt; 1" of light yellow brown silty gravel @ 6'; wet | | Collect sample from 6-6.5' bgs @ 8:22 |
| | -7.0 | | | | | | | |
| | -8.0 | 3 | | 4 | | 8.0 - 8.8' FILL: Light brown sand (fine), loose, saturated | NA | Collect sample from 9-9.5' bgs @ 8:27 |
| | | | | | | 8.8 - 9.3' FILL: Light brown clayey silt, firm, saturated | | |
| | -9.0 | | | | | 9.3 - 10.0' FILL: Light brown sand (fine), some organic material, loose, saturated | | |
| | -10.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073- Deagan Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-001
**DATE BEGAN:** 7/9/2008
**DATE FINISHED:** 7/14/08
**INSPECTOR:** B. Senna/ E. Jackson
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | | | | | | | |
| | | | | | | 10.0 - 11.0' FILL: Light brown sand (fine), some organic material, loose, saturated | | Collect sample from 11.5-12' bgs @ 8:30 |
| | -11.0 | | | | | 11.0 - 12.0' FILL: Light brown silty clay, firm, saturated, fine sand @ tip | | |
| | -12.0 | 4 | | 1.5 | | 12.0 - 13.5' FILL: Light brown sandy clay (fine-medium), firm, saturated | NA | Collect sample from 13-13.5' bgs @ 8:40 |
| | -13.0 | | | | | 13.5 - 16.0' No recovery | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | | | |
| | -16.0 | 5 | | 0 | | 16.0 - 18.0' No recovery | NA | |
| | -17.0 | | | | | | | |
| | -18.0 | 6 | | 1 | | 18.0 - 19.0' PT: Light brown/dark brown peat, clayey silt lens from 18.25'-18.75'; end of boring at 19' | | |
| | -19.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-001A
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:**
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 12.0' Begin logging soil boring at 12 ft bgs; see boring log 073-SB-001 for details | | |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | | | |
| | -4.0 | | | | | | | |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | | | |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-001A
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:**
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-1 | NA | 0.0 | | 12.0 - 16.0' No recovery | NA | Driller advanced to 12.0' bgs prior to sampling |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | | | |
| | -16.0 | S-2 | NA | 2.5 | | 16.0 - 17.0' FILL: Light/red brown sand (fine-medium), wet | 0.0 | 073-SB-001A_1618 collected from 16.0-16.5' bgs @ 10:00; DUP @ 10:02 |
| | -17.0 | | | | | 17.0 - 17.3' OL: Black silt, some shells and organic material, moist | | |
| | | | | | | 17.3 - 17.8' PT: Dark brown peat, moist | | |
| | -18.0 | | | | | 17.8 - 18.5' SP: Light brown sand (fine), some organic material, trace silt, moist | | 073-SB-001A_1820 collected from 18.0 - 18.5' bgs @ 10:05 |
| | -19.0 | | | | | 18.5 - 20.0' No recovery; end of boring at 20.0' bgs | | |
| | -20.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-002
**DATE BEGAN:** 7/9/2008
**DATE FINISHED:** 7/14/08
**INSPECTOR:** E Jackson / B Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 4 | | 0.0 - 0.8' ASPHALT: Asphalt | NA | First attempt 7/9/2008 with truck mounted rig, refusal @ 2.5' bgs; re-mobilized on7/14/08 with 6610DT track mounted geoprobe rig |
| | -1.0 | | | | | 0.8 - 2.0' FILL: Dark brown/red brown silt and clay, firm, with few small white and yellow brown mottles, green staining @ 1' bgs, suspect COPR, moist. | | PID/4-gas meter malfunctioning due to rain |
| | -2.0 | | | | | 2.0 - 4.0' FILL: White/yellow green concrete and silt, very tight, green staining throughout, suspect COPR; dry | | Collect sample from 1-1.5' bgs @ 9:38 |
| | -3.0 | | | | | | | Collect sample from 3.5-4' bgs @ 9:40 |
| | -4.0 | 2 | NA | 4 | | 4.0 - 4.8' FILL: Light brown gravelly sand some silt, loose, saturated | NA | |
| | -5.0 | | | | | 4.8 - 5.5' FILL: Light yellow/brown silt, 1/2" dark brown stripe @ 4.8 and 4.9, yellow green stripe @ top, suspect COPR, few bright red mottles, firm, wet | | Collect sample from 4.5-5' bgs @ 9:50 |
| | -6.0 | | | | | 5.5 - 6.5' FILL: Light/red brown gravelly silt, some sand, firm, wet | | |
| | -7.0 | | | | | 6.5 - 7.8' FILL: Light brown sand (fine-medium), dark brown @ 7'; wet | | Collect sample from 6.5-7' bgs @ 9:52 |
| | -8.0 | 3 | | 1.5 | | 7.8 - 8.0' FILL: Red brown clayey silt, wet | NA | No recovery 1st attempt pushed through with basket and got 1.5' of recovery |
| | -9.0 | | | | | 8.0 - 8.5' FILL: Dark brown sand (fine-medium), loose, saturated | | Collect sample from 9-9.5' bgs @ 10:00 |
| | -10.0 | | | | | 8.5 - 9.5' FILL: Light brown silty clay, soft, some gravel (fine-coarse), saturated | | |
| | -11.0 | | | | | 9.5 - 10.0' No recovery | | |
| | -12.0 | | | | | 10.0 - 12.0' No recovery | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-002
**DATE BEGAN:** 7/9/2008
**DATE FINISHED:** 7/14/08
**INSPECTOR:** E Jackson / B Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | 4 | | 3 | | 12.0 - 15.0' CL: Light brown silty clay, some sand (fine-coarse) throughout, firm, saturated | NA | Collect sample from 12-12.5' bgs @10:05; DUP @ 10:06 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | Collect sample from 14.5-15' bgs @ 10:08 |
| | -15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | -16.0 | 5 | | 1 | | 16.0 - 17.0' CL: Light brown silty clay, some sand (fine-coarse) throughout, trace gravel, firm, saturated | NA | Collect sample from 16-16.5' bgs @ 10:20 |
| | -17.0 | | | | | 17.0 - 18.0' No recovery | | |
| | -18.0 | 6 | | 1 | | 18.0 - 18.8' CL: Light brown silty clay, some sand (fine-coarse) from 18.0'-18.5'; wet | | Collect sample from 18-18.5' bgs @ 10:30 |
| | -19.0 | | | | | 18.8 - 19.0' PT: Peat; moist; end of boring at 19' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-003
**DATE BEGAN:** 7/9/2008
**DATE FINISHED:** 7/14/08
**INSPECTOR:** E Jackson / B Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 4 | | 0.0 - 0.5' ASPHALT: Asphalt & gravel | N/A | Attempted three borings on 7/9/2008 with truck-mounted rig, refusal @ 2' bgs; re-mobilized on7/14/08 with 6610DT track mounted geoprobe rig |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Black silt and gravel (fine-medium), very firm, dry | | |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Concrete | | PID/ 4-gas meter malfunctioning due to rain |
| | -3.0 | | | | | 2.0 - 4.0' FILL: Light yellow brown silt, some gravel (fine-medium), rounded, very firm, dark brown @ bottom, moist | | Collect sample from 1-1.5' bgs @ 10:58<br>Collect sample from 2.5-3' bgs @ 11:00 |
| | -4.0 | 2 | NA | 3.5 | | 4.0 - 5.5' FILL: Dark brown silty sand, some gravel and clay, yellow brown coloring from 4-4.5' bgs, angular brick and gravel @ 5' bgs, firm, wet | N/A | |
| | -5.0 | | | | | | | Collect sample from 4-4.5' bgs @ 11:05 |
| | -6.0 | | | | | 5.5 - 7.5' FILL: Light/red brown sand (fine-medium), wet. | | Collect sample from 7-7.5' bgs @ 11:08 |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | 7.5 - 8.0' No recovery | | |
| | | 3 | NA | 4 | | 8.0 - 8.5' FILL: Light brown sand (fine-medium), dense, wet | N/A | Collect sample from 8.5-9' bgs @ 11:10 |
| | -9.0 | | | | | 8.5 - 9.0' FILL: Light brown sandy clay with yellow brown mottles and angular gravel (fine-medium), saturated | | |
| | -10.0 | | | | | 9.0 - 10.0' FILL: Light brown sand (fine-medium), saturated. | | Collect sample from 11.5-12' bgs @ 11:12 |
| | -11.0 | | | | | 10.0 - 12.0' FILL: Light brown sand (fine-medium), some coarse red brown silty sand @ 11.0'-11.5'; saturated. | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-003
**DATE BEGAN:** 7/9/2008
**DATE FINISHED:** 7/14/08
**INSPECTOR:** E Jackson / B Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | 4 | NA | 4 | | 12.0 - 16.0' FILL: Light brown sand (f-c), some rounded fine gravel, saturated | N/A | Collect sample from 12.5-13' bgs @ 11:15 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | Collect sample from 15.5-16' bgs @ 11:18 |
| | -15.0 | | | | | | | |
| | -16.0 | 5 | NA | 3 | | 16.0 - 19.0' CL: Light brown silty clay, some sand @ 18' bgs, dark brown clay in tip, wet; end of boring at 19' | N/A | Collect sample from 16-16.5' bgs @ 11:25 |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | | Collect sample from 18.5-19' bgs @ 11:27 |
| | -19.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-004
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 17.0 ft bgs
**GW DEPTH:** 8.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE: concrete | 0 | Driller cored through concrete |
| | -1.0 | | | | | 0.3 - 1.3' FILL: Dark brown silty sand (fine), some gravel (fine-coarse), moist, sheen from 1 - 1.25' | 10.4 | |
| | -2.0 | | | | | 1.3 - 2.8' FILL: Red brown silt, moist | 8.1 | 073-SB-004_0002 collected from 1.0-1.5' bgs @ 14:05 |
| | -3.0 | | | | | 2.8 - 3.0' FILL: Light brown sand (fine-medium), moist | 0 | 073-SB-004_0204 collected from 2.5-3.0' bgs @ 14:10 |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown/red sand (fine-medium); very moist; lenses of silt from 5.0 - 7.0 | 1.3 | |
| | -5.0 | | | | | | 2.4 | 073-SB-004_0406 collected from 4.5-5.0' bgs @ 14:15 |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | | 0 | 073-SB-004_0608 collected from 6.5-7.0' bgs @ 14:20 |
| ▽ | -8.0 | S-3 | NA | 3.0 | | 8.0 - 9.0' FILL: Red brown silt; wet | 0 | |
| | -9.0 | | | | | 9.0 - 11.0' FILL: Light brown sand (fine-medium); wet | | 073-SB-004_0810 collected from 8.5-9.0' bgs @ 14:25 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 073-SB-004_1012 collected from 12.5-13.0' bgs @ 14:30 |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-004
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 17.0 ft bgs
**GW DEPTH:** 8.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 13.0' FILL: Red brown/light brown silt; wet | 0 | |
| | -13.0 | | | | | 13.0 - 14.5' FILL: Red brown silt; wet; black silt on top | | 073-SB-004_1214 collected from 12.5-13.0' bgs @ 14:35 |
| | -14.0 | | | | | | | 073-SB-004_1416 collected from 14.0-14.5' bgs @ 14:40 |
| | -15.0 | | | | | | | |
| | -16.0 | S-5 | NA | 1.0 | | 16.0 - 17.0' PT: Dark brown peat; moist | 0 | |
| | -17.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-005
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE: concrete | 0 | Driller cored through concrete |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Dark brown silty sand (fine); trace wood and gravel (fine-medium), dry | | |
| | -2.0 | | | | | 1.5 - 3.0' FILL: Red brown silt; some gravel (fine), dry | | 073-SB-005_0002 collected from 1.0-1.5' bgs @ 10:20 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | 073-SB-005_0204 collected from 2.5-3.0' bgs @ 10:25 |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 5.5' FILL: Light brown sand (fine-medium), dry | 0 | |
| | -5.0 | | | | | 5.5 - 6.0' FILL: Yellow green clayey silt; potentially COPR, dry | | |
| | -6.0 | | | | | 6.0 - 7.0' FILL: Dark brown silty sand (fine); wet; trace clayey silt | | 073-SB-005_0406 collected from 5.5-6.0' bgs @ 10:30 |
| | -7.0 | | | | | 7.0 - 8.0' FILL: Light gray/ light brown sand (fine); some silt; wet | | 073-SB-005_0608 collected from 7.0-7.5 bgs @ 10:35 |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown silt; saturated | 0 | 073-SB-005_0810 collected from 8.0-8.5' bgs @ 10:40 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | 073-SB-005_1012 collected from 10.5-11.0' bgs @ 10:45 |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-005
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-4 | NA | 2.5 | | 12.0 - 14.0' FILL: SAA; Light brown silt; saturated | 0 | 073-SB-005_1214 collected from 12.0-12.5' bgs @ 10:50 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 14.5' OL: Black silt; trace organic material, wet | | |
| | -15.0 | | | | | 14.5 - 16.0' No recovery | | 073-SB-005_1416 collected from 14.0-14.5' bgs @ 10:55 |
| | -16.0 | S-5 | NA | 2.75 | | 16.0 - 16.5' OL: Black silt; trace organic material, wet | 0 | |
| | -17.0 | | | | | 16.5 - 18.0' PT: Dark brown peat; moist | | 073-SB-005_1618 collected from 16.5-17.0' bgs @ 11:00 |
| | -18.0 | | | | | 18.0 - 18.8' SP: Light brown/olive sand (fine); some organic material | | 073-SB-005_1820 collected from 18.0-18.5' bgs @ 11:05 |
| | -19.0 | | | | | 18.8 - 20.0' No recovery; end of boring at 20.0' | | |
| | -20.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-006
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' CONCRETE: Concrete and gravel | 0 | Driller cored through concrete |
| | | | | | | 0.5 - 0.8' FILL: Dark brown/black silty sand, dry | 15.8 | 073-SB-006_0002 collected from 1.0-1.5' bgs @ 12:50 |
| | -1.0 | | | | | 0.8 - 2.5' FILL: Light brown/gray sand (fine-medium); oil odor 1.5-2.0', dry | 25.1 | |
| | -2.0 | | | | | | 20.3 | |
| | | | | | | 2.5 - 4.0' No recovery | 81.8 | 073-SB-006_0204 collected from 2.0-2.5' bgs @ 12:55 |
| | -3.0 | | | | | | | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown/gray sand (fine-medium); strong oil odor; trace sheen 4.5-5.0'; moist @ 5.0' | 105 | |
| | | | | | | | 187 | |
| | -5.0 | | | | | | 151 | 073-SB-006_0406 collected from 4.5-5.0' bgs @ 13:00 |
| | | | | | | | 35.1 | |
| | -6.0 | | | | | | 25.8 | |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | 9.6 | 073-SB-006_0608 collected from 6.5-7.0' bgs @ 13:05 |
| ▽ | -8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown/red brown sand (fine-medium); lenses of red brown silt 8.0-9.0'; wet | 1.5 | |
| | | | | | | | 1.9 | 073-SB-006_0810 collected from 8.0-8.5' bgs @ 13:10 |
| | -9.0 | | | | | | 1.3 | |
| | -10.0 | | | | | | 1.4 | |
| | | | | | | 10.5 - 12.0' No recovery | | 073-SB-006_1012 collected from 10.0-10.5' bgs @ 13:15 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-006
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-4 | NA | 3.0 | | 12.0 - 14.5' FILL: Red brown silt; some sand (fine); wet | 1.8 | |
| | -13.0 | | | | | | 0 | 073-SB-006_1214 collected from 12.5-13.0' bgs @ 13:20 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | 14.5 - 15.0' OL: Black silt; wet | 0 | 073-SB-006_1416 collected from 14.5-15.0' bgs @ 13:25 |
| | -16.0 | S-5 | NA | 3.0 | | 15.0 - 16.0' No recovery<br>16.0 - 16.3' OL: SAA; Black silt; wet | 0 | |
| | -17.0 | | | | | 16.3 - 17.3' PT: Dark brown peat; moist | 0 | 073-SB-006_1618 collected from 16.0-16.5' bgs @ 13:30 |
| | -18.0 | | | | | 17.3 - 19.0' SW: Light brown sand (fine-medium); some organic material | 0 | |
| | -19.0 | | | | | 19.0 - 20.0' No recovery; end of boring at 20' | 0 | 073-SB-006_1820 collected from 18.5-19.0' bgs @ 13:35 |
| | -20.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-007
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** E Jackson / B Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3 | | 0.0 - 0.5' ASPHALT: Asphalt | | Strong odor |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Dark brown sand and gravel; sticky | 900 | Collect sample from 0.5-1' bgs @ 13:18 |
| | -2.0 | | | | | 1.5 - 2.8' FILL: Dark brown clayey silt, wet | | Collect sample from 2.5-3.0' bgs @ 13:20 |
| | -3.0 | | | | | 2.8 - 3.0' FILL: Dark brown sand (fine-medium), wet | 2300 | |
| | -4.0 | 2 | NA | 4 | | 3.0 - 4.0' No recovery | | Collect sample from 4.5-5' bgs @ 13:25 |
| | -5.0 | | | | | 4.0 - 8.0' FILL: Light brown sand (fine-coarse), clay throughout, gravel (fine), saturated | 10 | |
| | -6.0 | | | | | | | Collect sample from 7-7.5' bgs @ 13:28 |
| | -7.0 | | | | | | 2300 | |
| | -8.0 | 3 | NA | 4 | | 8.0 - 10.0' FILL: Light brown sand (fine-coarse), trace shells; saturated | 0 | Collect sample from 8.5-9' bgs @ 13:55 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 12.0' FILL: Light brown sand (fine-coarse), trace shells, fine sand and silt @ 10.0'-10.5'; saturated | | Collect sample from 10-10.5 bgs @ 13:38 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-007
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** E Jackson / B Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | 4 | NA | 4 | | 12.0 - 15.8' FILL: Light brown sand (fine-medium), some coarse sand from 14.0'-15.75', saturated | 0 | Collect sample form 13-13.5' bgs @ 13:56<br>Collect sample from 14-14.5' bgs @ 14:01 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.8 - 16.0' CL: Brown silt and clay, organic odor; end of boring at 16' | | |
| | -16.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-008
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 17.0 ft bgs
**GW DEPTH:** 8.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel; dry | 0 | |
| | | | | | | 0.5 - 1.3' FILL: Red brown silt; some gravel; dry | 0 | 073-SB-008_0002 collected from 0.5-1.0' bgs @ 08:05 |
| | -1.0 | | | | | 1.3 - 3.5' FILL: Dark brown silty sand (fine); some gravel (fine), wood; 3.0-3.5 moist; odor | 9.8 | |
| | -2.0 | | | | | | 15.3 | |
| | -3.0 | | | | | 3.5 - 4.0' No recovery | | 073-SB-008_0204 collected from 3.0-3.5' bgs @ 08:10 |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 6.0' FILL: Dark brown/red brown silt; some sand (fine); trace sheen; oil odor ; moist | 12.1 | |
| | -5.0 | | | | | | 15.8 | 073-SB-008_0406 collected from 4.5-5.0' bgs @ 08:15 |
| | -6.0 | | | | | 6.0 - 7.5' FILL: Light brown sand (fine-medium); oil odor; moist | 43.8 | |
| | -7.0 | | | | | | 15.5 | |
| | | | | | | 7.5 - 8.0' No recovery | | 073-SB-008_0608 collected from 7.0-7.5' bgs @ 08:20 |
| ▽ | -8.0 | S-3 | NA | 2.5 | | 8.0 - 9.0' FILL: light brown sand (fine-medium); oil odor; wet | 9.8 | 073-SB-008_0810 collected from 8.0-8.5' bgs @ 08:25 |
| | -9.0 | | | | | 9.0 - 10.5' FILL: Brown silt; wet | 5.3 | |
| | -10.0 | | | | | | 0.9 | |
| | | | | | | 10.5 - 12.0' No recovery | | 073-SB-008_1012 collected from 10.0-10.5' bgs @ 08:30 |
| | -11.0 | | | | | | 0 | |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-008
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 17.0 ft bgs
**GW DEPTH:** 8.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-4 | NA | 2.5 | | 12.0 - 13.5' FILL: Brown silt wet; | 0 | |
| | -13.0 | | | | | | 0 | 073-SB-008_1214 collected from 12.0-12.5' bgs @ 08:35 |
| | -14.0 | | | | | 13.5 - 14.5' FILL: Red brown silt; trace sand (fine); wet | 0 | |
| | -15.0 | | | | | 14.5 - 16.0' OL: Black silt; wet | 0 | 073-SB-008_1416 collected from 14.0-14.5' bgs @ 08:40 |
| | -16.0 | S-5 | NA | 1.0 | | 16.0 - 16.3' OL: Dark brown/black silt; heavy organic material; wet | 0 | |
| | -17.0 | | | | | 16.3 - 17.0' PT: Dark brown peat; moist; end of boring at 17.0' | 0 | 073-SB-008_1618 collected from 16.0-16.5' bgs @ 08:45 |
| | -18.0 | | | | | | 0 | |
| | -19.0 | | | | | | 0 | |
| | -20.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-009
**DATE BEGAN:** 7/9/08
**DATE FINISHED:** 7/9/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Mustafah
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3 | | 0.0 - 0.5' ASPHALT: Asphalt | 150 | Collect sample from 0.5-1' bgs @ 8:30 |
| | -1.0 | | | | | 0.5 - 1.0' FILL: Light brown sand (medium-coarse), wood, and gravel, dry | | |
| | -2.0 | | | | | 1.0 - 2.0' FILL: Light brown sand (fine-coarse), some silt and fine rounded gravel, trace clay; dry | 80 | Collect sample from 2.5-3' bgs @ 8:33 |
| | -3.0 | | | | | 2.0 - 3.0' FILL: Light brown sand (fine-coarse); moist | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.5 | | 4.0 - 4.5' FILL: Light brown sand (fine-coarse); moist | 0 | Collect sample from 4.5-5' bgs @ 8:39 |
| | -5.0 | | | | | 4.5 - 5.5' FILL: Light brown sand (fine-coarse), fine rounded gravel, clay lenses, wet | | |
| | -6.0 | | | | | 5.5 - 7.5' FILL: Light brown sand (fine-coarse), tight, clay lenses @ 6.5' and 7'; wet | 0 | Collect sample from 6.5-7' bgs @ 8:42 |
| | -7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | -8.0 | 3 | NA | 3 | | 8.0 - 10.0' FILL: Light brown sand (medium-coarse), trace fine rounded gravel, shell at 8.5' , some clay lenses; wet | 0 | Collect sample from 8-8.5' bgs @ 9:06 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 11.0' FILL: Light brown sand (medium-coarse), trace fine rounded gravel, some clay lenses; wet | | Collect sample from 10.5-11' bgs @ 9:08 |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-009
**DATE BEGAN:** 7/9/08
**DATE FINISHED:** 7/9/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Mustafah
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | 4 | NA | 4 | | 12.0 - 13.0' FILL: Light brown sand (medium-coarse), trace fine rounded gravel, some clay lenses; wet | 0 | Collect sample from 12-12.5' bgs @ 9:26 |
| | -13.0 | | | | | 13.0 - 17.5' OH: Dark brown/black organic silt & clay, soft, wet | | |
| | -14.0 | | | | | | | Collect sample from 14-14.5' bgs @ 9:28 |
| | -15.0 | | | | | | | |
| | -16.0 | 5 | NA | 2 | | | 0 | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | 17.5 - 18.0' PT: Peat; end of boring at 18' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 North

**SITE INFO:** Site 073/ Degan Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-010
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** E. Jackson/ T. Giouzelis
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Moustafa
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE | 0 | |
| | -1.0 | | | | | 0.5 - 1.5' FILL: red brown sandy silt (fine-medium) with trace fine gravel; firm; dry | | Collect sample from 0.5'-1.0' bgs @ 11:10 |
| | -2.0 | | | | | 1.5 - 3.0' FILL: dark brown clayey silt some fine gravel and sand, moist | 0 | Collect sample from 2.5'-3.0' bgs @ 11:13 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 4.0 | | 4.0 - 6.0' FILL: light brown sand (f-c), trace rounded fine gravel; medium dense; saturated | 0 | Collect sample from 4.0'-4.5' bgs @ 11:16 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 6.0 - 8.0' FILL: light brown sand (fine-medium), trace layers of silt; saturated | 0 | |
| | -7.0 | | | | | | | Collect sample from 7.0'-7.5' bgs @ 11:19 |
| | -8.0 | 3 | NA | 4.0 | | 8.0 - 10.0' FILL: light brown silt, some clay, trace sand, ; loose; saturated | 0 | Collect sample from 8.5'-9.5' bgs @ 11:21 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 11.0' FILL : light brown silt, some clay, trace sand, ; loose; saturated | 0 | Collect sample from 10.0'-10.5' bgs @ 11:23 |
| | -11.0 | | | | | 11.0 - 12.0' FILL: brown sand (fine-medium); dense; saturated | | |
| | -12.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 North

**SITE INFO:** Site 073/ Degan Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-010
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** E. Jackson/ T. Giouzelis
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Moustafa
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | 4 | NA | 4.0 | | 12.0 - 16.0' FILL: light brown/red brown sand (fine-medium), 2" clay lens at 14'; medium density; saturated | 0 | Collect sample from 12.5' - 13.0' bgs @ 1139 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | | Collect sample from 15.5'- 16.0' bgs @ 11:42 |
| | -16.0 | 5 | NA | 4.0 | | 16.0 - 20.0' PT: dark brown/black peat, clay in tip; end of boring at 20' | 0 | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | 0 | |
| | -19.0 | | | | | | | |
| | -20.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-011
**DATE BEGAN:** 7/9/08
**DATE FINISHED:** 7/9/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Mustafah
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | Collect sample from 1-1.5' bgs @ 10:20 |
| | -1.0 | | | | | 0.5 - 1.0' FILL: Red brown silt clay gravel mix, some concrete; moist | | |
| | | | | | | 1.0 - 1.8' FILL: Dark brown gravelly sand, angular, some coal fragments; moist | | |
| | -2.0 | | | | | 1.8 - 3.5' FILL: Red brown layers of silty clay and fine sand, some coarse sand @ bottom; firm; moist | 0 | Collect sample from 3-3.5' bgs @ 10:23 |
| | -3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 4 | | 4.0 - 5.0' FILL: Red/dark brown gravelly sands, trace glass, coal frags, some silt and clay, moist | 0 | Collect sample from 4.5-5' bgs @ 10:28 |
| | -5.0 | | | | | 5.0 - 8.0' FILL: Light/red brown sand (f-c), few layers of fine sand and clay, wet | | |
| | -6.0 | | | | | | 0 | Collect sample from 7.5-8' bgs @ 10:30 |
| | -7.0 | | | | | | | |
| | -8.0 | 3 | NA | 4 | | 8.0 - 11.0' FILL: Light brown sand (f-c), trace clay lenses, firm, saturated | 0 | Collect sample from 8.5-9' bgs @ 10:40 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | 11.0 - 11.5' FILL: Light brown silty clay, soft, saturated | | Collect sample from 10.5-11' bgs @ 10:43 |
| | | | | | | 11.5 - 12.0' FILL: Light brown sand (fine-medium), saturated | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-011
**DATE BEGAN:** 7/9/08
**DATE FINISHED:** 7/9/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Mustafah
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | 4 | NA | 3 | | 12.0 - 14.0' FILL: Light brown sand (fine-medium), firm, trace clay, saturated | 0 | Collect sample from 12.5-13' bgs @ 11:08 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 14.5' CL: Light brown clay, trace silt, wet | 0 | |
| | -15.0 | | | | | 14.5 - 15.0' OL: Dark brown/black silty clay, varved, organic odor; moist | | |
| | | | | | | 15.0 - 18.0' No recovery; end of boring at 18' | | |
| | -16.0 | 5 | NA | 0 | | | | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-011A
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 12.0' See 073-SB-011 for description; begin logging soil boring at 12' bgs | | |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | | | |
| | -4.0 | | | | | | | |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | | | |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-011A
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | | | |
| | | S-1 | NA | 2.5 | | 12.0 - 13.5' FILL: Light brown/black clayey silt | 0 | |
| | -13.0 | | | | | | 0 | |
| | | | | | | 13.5 - 14.5' OL: Black silt | | |
| | -14.0 | | | | | | 0 | 073-SB-008_1416 collected from 14.0-14.5' bgs @ 13:25 |
| | | | | | | 14.5 - 16.0' No recovery | | |
| | -15.0 | | | | | | 0 | |
| | -16.0 | S-2 | NA | 2.0 | | 16.0 - 16.5' PT: Dark brown peat; moist | 0 | 073-SB-008_1618 collected from 16.5-17.0' bgs @ 13:30 |
| | | | | | | 16.5 - 19.0' OL: Olive clayey silt; heavy organic material; moist | | |
| | -17.0 | | | | | | 0 | |
| | -18.0 | | | | | | 0 | 073-SB-008_1820 collected from 18.5-19.0' bgs @ 13:35 |
| | -19.0 | | | | | 19.0 - 19.5' PT: Dark brown peat; moist | 0 | |
| | | | | | | 19.5 - 20.0' No recovery; end of boring at 20.0' | | |
| | -20.0 | | | | | | | |

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-012
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 6.0 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt, gravel | 0 | |
| | -1.0 | | | | | 1.0 - 1.5' FILL: Wood, dry | 0 | |
| | -2.0 | | | | | 1.5 - 3.5' FILL: Dark brown/ black silty sand (fine) with wood, dry | 0 | 073-SB-012_0002 collected from 1.0-1.5' bgs @ 15:05 |
| | -3.0 | | | | | | 0 | |
| | | | | | | 3.5 - 4.0' No recovery | | 073-SB-012_0204 collected from 3.0-3.5' bgs @ 15:10 |
| | -4.0 | S-2 | NA | 2.0 | | 4.0 - 4.5' FILL: Light brown/light red brown silty sand (fine); some white/yellow nodules; potential COPR, dry | 0 | 073-SB-012_0406 collected from 4.0-4.5' bgs @ 15:15 |
| | -5.0 | | | | | 4.5 - 6.0' FILL: Yellow/green/white silt; some sand (fine); potentially COPR; wet @ 5' bgs; end of boring at 6.0' | 0 | |
| | -6.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-013

**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 6.0 ft bgs
**GW DEPTH:** 5.0 ft bgs

**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | -1.0 | | | | | 0.5 - 2.5' FILL: Dark brown silty sand (fine); some gravel (fine-coarse), wood, and metal, dry | 0 | 073-SB-013_0002 collected from 0.5-1.0' bgs @ 15:20 |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | 2.5 - 4.0' No recovery | 0 | 073-SB-013_0204 collected from 2.0-2.5' bgs @ 15:25 |
| | -4.0 | S-2 | NA | 2.0 | | 4.0 - 5.5' FILL: Red/brown silty sand; glue-like substance at 4.0'; heavy odor; sticky; wet from 5' bgs | 67.9<br>51.8 | |
| | -5.0 | | | | | | 40.0 | 073-SB-013_0406 collected from 4.5-5.0' bgs @ 15:30 |
| | -6.0 | | | | | 5.5 - 6.0' FILL: Yellow/green silt; potentially COPR, wet; end of boring at 6.0' | 48.3 | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-014
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.3' CONCRETE | 0 | Driller cored through concrete |
| | -1.0 | | | | | 0.3 - 2.5' FILL: Red brown/brown silt; moist; stiff | 0 | 073-SB-014_0002 collected from 0.5-1.0' bgs @ 09:20 |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | 2.5 - 4.0' No recovery | 0 | 073-SB-014_0204 collected from 2.0-2.5' bgs @ 09:25 |
| | -4.0 | S-2 | NA | 2.0 | | 4.0 - 5.0' FILL: Brown silt; wet | 0 | |
| | -5.0 | | | | | 5.0 - 6.0' FILL: Light brown fine-medium sand; lenses of black silt from 5.5-5.75', wet; end of boring at 6' | 0 | 073-SB-014_0406 collected from 4.5-5.0' bgs @ 09:30 |
| | -6.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-015
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 6.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt, gravel; dry | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Black silty sand (fine); some gravel (fine-coarse); dry | 0 | |
| | -2.0 | | | | | 1.5 - 3.5' FILL: Dark brown sand (fine); some wood; moist | 0 | 073-SB-015_0002 collected from 1.0-1.5' bgs @ 09:35 |
| | -3.0 | | | | | | 0 | |
| | -4.0 | | | | | 3.5 - 4.0' FILL: No recovery | | 073-SB-015_0204 collected from 3.0-3.5' bgs @ 09:40 |
| | | S-2 | NA | 2.0 | | 4.0 - 5.0' FILL: Red brown silt; trace sand (fine); wet | 0 | |
| | -5.0 | | | | | 5.0 - 6.0' FILL: Yellow/white/green silt; tight; potential COPR; wet; end of boring at 6.0' | 0 | 073-SB-015_0406 collected from 4.5-5.0' bgs @ 09:40 |
| | -6.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-016
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete; dry | 0 | |
| | -1.0 | | | | | 0.8 - 1.8' FILL: Brown clayey silt; dry | 0 | |
| | -2.0 | | | | | 1.8 - 3.0' FILL: Light brown silty sand (fine-medium); lenses of reddish brown silt; some gravel (f-c); moist | 0 | 073-SB-016_0002 collected from 1.5-2.0' bgs @ 11:20 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | 0 | 073-SB-016_0204 collected from 2.5-3.0' bgs @ 11:25 |
| ▽ | -4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: light brown silty sand (fine-medium); lenses reddish brown silt; some gravel (f-c); wet | 0 | 073-SB-016_0406 collected from 4.0-4.5' bgs @ 11:30 |
| | -5.0 | | | | | | 0 | |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | | 0 | 073-SB-016_0608 collected from 6.5-7.0' bgs @ 11:33 |
| | -8.0 | S-3 | NA | 2.5 | | | 0 | 073-SB-016_0608 collected from 7.0-7.5' bgs @ 11:35 |
| | -9.0 | | | | | 8.0 - 10.5' FILL: light brown silty sand (fine-medium); some lenses reddish brown silt; some gravel (f-c); wet | 0 | 073-SB-016_0810 collected from 8.0-8.5' bgs @ 11:40 |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | 10.5 - 12.0' FILL: No recovery | 0 | 073-SB-016_1012 collected from 10.0-10.5' bgs @ 11:45 |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 073
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-016
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-4 | NA | 3.0 | | 12.0 - 13.5' FILL: light brown silty sand (fine-medium); some lenses reddish brown silt; some gravel (f-c); wet | 0 | |
| | -13.0 | | | | | | 0 | 073-SB-016_1214 collected from 12.5-13.0' bgs @ 11:50 |
| | | | | | | 13.5 - 14.5' OL: Black silt; wet | | |
| | -14.0 | | | | | 14.5 - 14.8' OL: Dark brown silt; some organic material; wet | 0 | |
| | -15.0 | | | | | 14.8 - 15.0' PT: Dark borwn peat; moist | 0 | 073-SB-016_1416 collected from 14.5-15.0' bgs @ 11:55 |
| | -16.0 | | | | | 15.0 - 16.0' No recovery; end of boring @ 16.0' | | |

# Honeywell SA-6 south

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-017
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, fine to medium gravel, fine to course sand | 0 | |
| | 1.0 | | | | | 0.5 - 2.5' FILL: Brown fine to coarse sand, fine to medium gravel, trace silt and brick; moderate dense, dry | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Brown silty clay, some fine sand; firm, moist | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Fine to medium sand, some clay, trace silt; moist, dense | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Brown fine to coarse sand, trace fine gravel, mottling of clay; wet, loose | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 073-SB-017-0608 @ 6.5-7.0' @ 8:55 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Brown fine to medium sand, some mottling of clay, trace shells; more clay with depth; wet, moderately firm | 0 | Sample collected 073-SB-017-0810 @ 8.5-9.0' @ 9:00 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 073-SB-017-1012 @ 10.5-11.0' @ 9:05 |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.0' FILL: Same as above | 0 | |
| | 13.0 | | | | | 13.0 - 13.5' OL: Clayey silt, some fine sand, trace organics; loose, wet | | Sample collected 073-SB-017-1214 @ 13.0-13.5' @ 9:10 |
| | 14.0 | | | | | 13.5 - 14.0' No recovery, end of boring @ 14' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 south

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-018
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.8' ASPHALT: Asphalt, fine to medium gravel, fine to coarse sand | 0 | |
| | 1.0 | | | | | 0.8 - 3.8' FILL: Reddish fine to medium brown sand, some silt, trace coal, fine to medium grave and bricks; dry, moderate dense | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | 3.8 - 4.0' No recovery | | |
| | | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Brown fine to medium sand, trace silt and shells; wet, loose | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-018-0608 from 7.0-7.5' bgs @9:20 |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 8.5' FILL: Brown fine to medium sand, some clay; wet, loose | 0 | |
| | 9.0 | | | | | 8.5 - 10.5' FILL: Black clayey silt, some fine sand; very loose, wet | | Sample collected 073-SB-018-0810 from 8.5-9.0' bgs @9:25 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' FILL: Brown fine to medium sand; wet, loose | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 13.8' OL: Black clayey silt, some fine sand, trace organics | 0 | Sample collected 073-SB-018-1012 from 11.0-11.5' bgs @9:30 |
| | 13.0 | | | | | 13.8 - 14.0' OL: Brown clayey silt, some fine sand, trace organics; end of boring @ 14' bgs | | Sample collected 073-SB-018-1214 from 13.0-13.5' bgs @9:35 |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 south

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-019
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, fine to medium gravel, fine to course sand, trace silt; loose, dry | 0 | |
| | 1.0 | | | | | 0.5 - 2.3' FILL: Reddish Brown silty clay, fine to medium sand; very dense, dry | | |
| | 2.0 | | | | | 2.3 - 3.0' FILL: Reddish brown fine to medium sand, some clay, fine to medium gravel | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 3.5' FILL: Reddish brown silty clay, fine to medium sand, trace fine to medium gravel; dense, moist | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 6.0' FILL: Same as above; wet | | |
| | 7.0 | | | | | 6.0 - 7.0' FILL: Brown silt, some fine to course sand, some fine to course gravel; wet,dense | | Sample collected 073-SB-019-0608 from 6.5-7.0' bgs @09:40 |
| | 8.0 | S-3 | NA | 3.5 | | 7.0 - 8.0' No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 11.5' FILL: Brown fine to course sand, trace fine to medium gravel, trace mottling of clay at depths | | Sample collected 073-SB-019-0810 from 8.5-9.0' bgs @09:45 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Sample collected 073-SB-019-1012 from 10.5-11.0' bgs @09:50 |
| | 12.0 | S-4 | NA | 2.5 | | 11.5 - 12.0' No recovery | 0 | Sample collected 073-SB-019-1214 from 12.0-12.5' bgs @09:55 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 14.5' OL: Clayey silt, fine to medium sand, trace organics; wet, loose | | Sample collected 073-SB-019-1416 from 14.0-14.5' bgs @10:00 |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring @ 16' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 south

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-020
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 3.8' FILL: Brown fine to medium sand, fine to medium gravel, lenses of coal @ 1.25-1.5' bgs, trace silt, lenses of clay @ 1.0 and 3.5' bgs;, wet, loose | 0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.8 - 4.0' FILL: No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 11.5' FILL: Brown fine to medium sand, trace fine to medium gravel, trace shells, lenses of clay @ 6.5' and 8.0' bgs; wet, loose | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-020-0608 from 7.0-7.5' bgs @10:10 |
| | 8.0 | S-3 | NA | 4.0 | | | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-020-0810 from 9.0-9.5' bgs @10:15 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.5 - 11.8' FILL: Clayey silt, some fine sand; wet, loose | | Sample collected 073-SB-020-1012 from 11.0-11.5' bgs @10:20 |
| | 12.0 | S-4 | NA | 3.0 | | 11.8 - 12.0' FILL: Brown fine to coarse sand; dense, wet | 0 | |
| | 13.0 | | | | | 12.0 - 14.0' FILL: Same as above, lenses of clay, more clay with depth; wet, loose | | Sample collected 073-SB-020-1214 from 12.5-13.0' bgs @10:25 |
| | 14.0 | | | | | 14.0 - 15.0' OL: Brown clayey silt, some fine sand; wet, loose | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery; end of boring at 16' bgs | | Sample collected 073-SB-020-1416 from 14.5-15.0' bgs @10:30 |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-021
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' CONCRETE | 13 | |
| | 1.0 | | | | | 0.5 - 2.5' FILL: Brown fine to medium sand, trace silt, moist, dense | 4.8 | Organic Odors from 0-4' bgs |
| | 2.0 | | | | | | 5.7 | |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 7.5' FILL: Same as above, more silt with depth; loose, wet | 34.9 | Sheen noticed at 6.5' bgs |
| | 5.0 | | | | | | 14.4 | |
| | 6.0 | | | | | | 14.5<br>6.5 | Sample collected 073-SB-021-0608 from 6.5-7.0' bgs @10:35 |
| | 7.0 | | | | | | 5.7 | |
| | 8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No recovery<br>8.0 - 12.0' FILL: Same as above | 4.0<br>0 | Sample collected 073-SB-021-0810 from 8.5-9.0' bgs @10:40 |
| | 9.0 | | | | | | 0 | |
| | 10.0 | | | | | | 0 | Sample collected 073-SB-021-1012 from 10.5-11.0' bgs @10:45 |
| | 11.0 | | | | | | 0 | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.4' FILL: Same as above; wet, very loose | 0 | Sample collected 073-SB-021-1214 from 12.5-13.0' bgs @10:50 |
| | 13.0 | | | | | | 0 | |
| | 14.0 | | | | | 14.4 - 14.5' OL: Brown clayey silt, some fine sand, trace organics | 0 | Sample collected 073-SB-021-1416 from 14.0-14.5' bgs @10:55 |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring @ 16.0' bgs | 0 | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-022
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' CONCRETE | 0.8 | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Dark brown fine to coarse sand, trace clinker, brick and silt; loose, moist | 0.5 | |
| | 2.0 | | | | | 0.5 - 3.0' FILL: Brown fine to coarse sand, some silt; loose, moist | 1.3<br>6.3<br>42.1 | |
| | 3.0 | | | | | | 56.6 | |
| | 4.0 | | | | | 3.0 - 4.0' No recovery | | |
| | | S-2 | NA | 4 | | 4.0 - 8.0' FILL: Same as above, trace clay; loose, wet | 13.4<br>21.5<br>13.6<br>5.5<br>3.9 | Sample collected 073-SB-022-0608 from 7.5-8.0' bgs @11:00, DUP @11:02 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | 1.7<br>1.6<br>0.9 | |
| | 8.0 | S-3 | NA | 3 | | 8.0 - 11.0' FILL: Same as above, trace shells; wet, very loose | 0.4 | |
| | 9.0 | | | | | | 0 | Sample collected 073-SB-022-0810 from 8.5-9.0' bgs @11:10 |
| | 10.0 | | | | | | 0 | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 073-SB-022-1012 from 10.5-11.0' bgs @11:15 |
| | 12.0 | S-4 | NA | 3 | | 12.0 - 13.5' FILL: Same as above | | |
| | 13.0 | | | | | | | Sample collected 073-SB-022-1214 from 12.5-13.0' bgs @11:20 |
| | 14.0 | | | | | 13.5 - 14.5' OL: Brown clayey silt, some fine sand, trace organics; wet, very loose | | |
| | 15.0 | | | | | 14.5 - 15.0' OL: Black silty clay, some fine sand, trace organics; wet, loose | | |
| | 16.0 | | | | | 15.0 - 16.0' No recovery, end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-023
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 0 | |
| | 1.0 | | | | | 0.3 - 1.5' FILL: Dark brown fine to coarse sand, fine to medium gravel, trace silt and brick; loose, moist | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brown fine to medium sand; loose, moist | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Reddish brown silty clay; very firm, moist | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 3.0' FILL: Brown fine to coarse sand | 0 | |
| | 5.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 7.0' FILL: Brown fine to coarse sand with lenses of silt and clay, trace shells; loose, wet | | Sample collected 073-SB-023-0608 from 6.5-7.0' bgs @11:30 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Same as above, very loose; wet | 0 | Sample collected 073-SB-023-0810 from 8.5-9.0' bgs @11:35 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 073-SB-023-1012 from 10.5-11.0' bgs @11:40 |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 12.8' FILL: Clayey silt, some fine sand; wet, very loose | 0 | |
| | 13.0 | | | | | 12.8 - 14.0' FILL: Fine to medium sand, trace silt; loose, wet | | Sample collected 073-SB-023-1214 from 13.0-13.5' bgs @11:45 |
| | 14.0 | | | | | 14.0 - 15.0' OL: Black silty clay, some fine sand, trace organics; firm, wet | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-023A
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' CONCRETE: Concrete | 0 | |
| | 1.0 | | | | | 0.3 - 1.5' FILL: Dark Brown fine to course sand, fine to medium gravel, trace silt and brick, loose, moist | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brown fine to medium sand, loose, moist | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Reddish brown silty clay, very firm, moist | | |
| | 4.0 | S-2 | NA | 3 | | 3.0 - 3.0' FILL: Brown fine to course sand | 0 | |
| | 5.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 7.0' FILL: Brown fine to course sand with lenses of silt and clay, trace shells, loose, wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 4 | | 8.0 - 12.0' FILL: SAA, very loose, very wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 12.8' FILL: Clayey silt with some fine sand, very wet, very loose | 0 | |
| | 13.0 | | | | | 12.8 - 14.0' FILL: Fine to medium sand with trace silt, loose, wet | | Sample collected 073-SB-023A-1416 from 14.0-14.5' bgs @9:45 |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Black clayey silt, organics | | |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-024
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 0 | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Dark Brown fine sand, some silt; moist, dense | | |
| | 2.0 | | | | | 0.5 - 3.0' FILL: Brown fine to coarse sand, lenses of clay, more clay with depth; loose, moist | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Brown fine to coarse sand, trace silt, lense of clay from 7.5-7.75' bgs; wet, loose | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 073-SB-024-0608 from 6.5-7.0' bgs @12:40, DUP @12:43 |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 8.5' FILL: Brown fine sand with trace silt; wet, loose | 0 | |
| | 9.0 | | | | | 8.5 - 9.3' FILL: Clayey silt, some fine sand; wet, very loose | | Sample collected 073-SB-024-0810 from 9.5-10.0' bgs @12:45 |
| | 10.0 | | | | | 9.3 - 11.0' FILL: Brown fine to coarse sand with lenses of clay at depth; wet, loose | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 073-SB-024-1012 from 10.5-11.0' bgs @12:50 |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 12.8' FILL: Brown fine to coarse sand with lenses of clay at depth, trace shells; wet, loose | 0 | |
| | 13.0 | | | | | 12.8 - 13.0' OL: Brown clayey silt, some fine sand; wet, loose | | Sample collected 073-SB-024-1214 from 13.0-13.5' bgs @12:55 |
| | 14.0 | | | | | 13.0 - 14.0' OL: Black silty clay, some fine sand; firm, wet; end of boring @ 14.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-025
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' ASPHALT: Gravel | 0 | |
| | | | | | | 0.5 - 3.0' FILL: Brown fine to medium sand, some fine to medium gravel, trace brick, tar, coal, and silt | | Sample collected 073-SB-025-0002 from 1.5-2.0' bgs @14:50 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | | | | | | | | Sample collected 073-SB-025-0204 from 2.5-3.0' bgs @14:55 |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Dark Brown fine to coarse sand, some silt, trace brick; wet, moderate dense | | |
| | | | | | | 3.5 - 4.0' FILL: Concrete | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 5.0' FILL: Light Brown fine sand, some fine gravel (Possible COPR) | 0 | |
| ▽ | | | | | | | | Sample collected 073-SB-025-0406 from 4.5-5.0' bgs @15:00 |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Silt, some fine sand, trace fine to medium gravel;, moist, dense | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Reddish brown fine to coarse sand with lenses of clay; moist, dense | | |
| | 7.0 | | | | | | | Sample collected 073-SB-025-0608 from 7.0-7.5' bgs @15:05 |
| | | | | | | 7.5 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-026
**DATE BEGAN:** 4/19/10
**DATE FINISHED:** 4/19/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' ASPHALT: Gravel | 0 | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Reddish brown fine to medium sand, some silt, trace brick; moist, very dense | | |
| | 2.0 | | | | | 1.8 - 2.0' FILL: Fine to coarse gravel | | |
| | | | | | | 2.0 - 2.8' FILL: Dark brown fine to course sand, fine to medium gravel, trace silt; moist, very dense | | |
| | 3.0 | | | | | 2.8 - 3.0' FILL: Greenish brown fine to medium sand (COPR) | | |
| | | | | | | 3.0 - 3.5' FILL: Mixture of yellowish green fine sand (COPR) and gravel | | |
| | 4.0 | | NA | 3.5 | | 3.5 - 4.0' FILL: Brown granular COPR | 0 | |
| | | | | | | 4.0 - 4.8' FILL: Fine to coarse sand, fine to medium gravel, trace silt | | |
| | 5.0 | | | | | 4.8 - 5.0' FILL: Yellowish green COPR mixed with fine to medium gravel, red fine to medium sand, dry | | |
| | | | | | | 5.0 - 5.5' FILL: Fine to medium sand, some silt; dense, moist | | |
| | 6.0 | | | | | 5.5 - 7.5' FILL: Fine to coarse sand, trace clay and silt; dense, moist | | |
| | 7.0 | | | | | | | Sample collected 073-SB-026-0608 from 7.0-7.5' bgs @14:30 |
| | 8.0 | | | | | 7.5 - 8.0' No recovery; end of boring @ 8.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-027
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 11 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -1.0 | | | | | | | |
| | | S-1 | | 4.0 | | -1.0 - 1.0' CONCRETE | 0 | |
| | 0.0 | | NA | | | | | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Brown fine to medium sand, fine to medium gravel. trace silt and tar; moist, loose | | Sample collected 073-SB-027-0002 from1.5-2.0' bgs @08:10 |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Concrete | | |
| | 3.0 | S-2 | | 3.0 | | 3.0 - 3.5' FILL: Grey and white resin; wet, loose | 0 | Sample collected 073-SB-027-0204 from3.0-3.5' bgs @08:15 |
| | 4.0 | | | | | 3.5 - 4.5' FILL: Dark Brown clayey silt, trace fine sand; firm, moist | | |
| ▽ | 5.0 | | | | | 4.5 - 6.5' FILL: Brown fine to coarse sand with lenses of clay; wet, loost | | Sample collected 073-SB-027-0406 from5.5-6.0' bgs @08:20 |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 7.0' No recovery | | |
| | 7.0 | S-3 | | 2.0 | | 7.0 - 9.0' FILL: Brown fine to coarse sand, some silt, trace clay and shells; wet, loose | 0 | Sample collected 073-SB-027-0608 from 7.0-7.5 bgs @08:25 |
| | 8.0 | | | | | | | |
| | 9.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-028
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 9 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -1.0 | S-1 | NA | 4.0 | | -1.0 - 0.0' CONCRETE | 0 | |
| | 0.0 | | | | | -0.2 - 0.0' FILL: Light brown fine to coarse sand, trace fine to medium gravel and brick | | |
| | | | | | | 0.0 - 0.5' FILL: Brown fine to medium sand, some silt and fine to medium gravel | | |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Black fine to coarse sand, fine to medium gravel, some tar | | Staining from -0.5 to -0.75 |
| | | | | | | 0.8 - 1.8' FILL: Concrete | | |
| | 2.0 | | | | | 1.8 - 3.5' FILL: Brown fine to coarse sand, trace silt; loose, wet | | |
| | 3.0 | S-2 | NA | 3.5 | | | 0 | |
| | 4.0 | | | | | 3.5 - 4.5' FILL: Brown silt clay; firm, wet | | Sample collected 073-SB-028-0406 from 4.5-5.0' bgs @08:35 |
| | 5.0 | | | | | 4.5 - 6.5' FILL: Brown fine to coarse sand with lenses of clay; wet, loost | | |
| | 6.0 | | | | | | | Sample collected 073-SB-028-0608 from 6.0-6.5' bgs @08:40 |
| | | | | | | 6.5 - 7.0' No recovery | | |
| | 7.0 | S-3 | NA | 1.5 | | 7.0 - 8.5' FILL: Brown fine to coarse sand with lenses of clay, trace shells; wet, loose | 0 | |
| | 8.0 | | | | | | | Sample collected 073-SB-028-0810 from 8.0-8.5 bgs @08:45 |
| | | | | | | 8.5 - 9.0' No recovery; end of boring @ 9.0' bgs | | |
| | 9.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-029
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -1.0 | S-1 | NA | 4.0 | | -1.0 - 3.5' CONCRETE | 0 | |
| | 0.0 | | | | | | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | S-2 | NA | 3.5 | | | 0 | |
| | 4.0 | | | | | 3.5 - 4.0' FILL: Greenish brown granular sand (COPR); dense, moist | | |
| | | | | | | 4.0 - 4.3' FILL: Dark brown fine to coarse sand, trace silt, fine to medium gravel | | |
| | 5.0 | | | | | 4.3 - 5.5' FILL: Brown clayey silt; firm, moist | | Sample collected 073-SB-029-0406 from5.0-5.5' bgs @09:25 |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Brown fine to coarse sand, fine to medium gravel and lenses of clay and sil; dense, wet | | |
| | | | | | | 6.5 - 7.0' No recovery | | Sample collected 073-SB-029-0608 from 6.0-6.5' bgs @09:30 |
| | 7.0 | S-3 | NA | 1.5 | | 7.0 - 8.5' FILL: Brown fine to coarse sand, fine to medium gravel and silt; loose, wet | 0 | |
| | 8.0 | | | | | | | |
| | 9.0 | | | | | 8.5 - 10.0' FILL: No recovery; end of boring @10.0' bgs | | Sample collected 073-SB-029-0810 from 8.0-8.5 bgs @09:35 |
| | 10.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-030
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Brown fine to medium sand with wood, trace coal and brick; moist | | Sample collected 073-SB-030-0002 from 0.5-1.0' bgs @10:25 |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Brown clayey silt; firm, moist | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Brown fine to coarse sand, trace fine to medium gravel; wet, loose | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | Sample collected 073-SB-030-0204 from 2.5-3.0' bgs @10:30 |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.8' FILL: Brown fine to coarse sand, trace fine to medium gravel, mottling of clay; wet, loose | 0 | |
| | 5.0 | | | | | | | Sample collected 073-SB-030-0406 from 4.5-5.0 bgs @10:40 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-030-0608 from 7.5-8.0 bgs @10:45 |
| | 8.0 | S-3 | NA | 2.5 | | 7.8 - 8.0' FILL: Brown fine sand, some silt; loose, wet | 0 | |
| | | | | | | 8.0 - 10.5' FILL: Brown fine sand, some silt, trace shells; loose, wet | | Sample collected 073-SB-030-0810 from 8.0-8.5 bgs @10:50 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | Sample collected 073-SB-030-1012 from 10.0-10.5 bgs @10:55 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywel Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-031
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Fine to coarse grave, some dark brown fine to coarse sand | | |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Brown fine to medium sand, trace silt; moist, dense | | Sample collected 073-SB-031-0002 from 0.5-1.0' bgs @10:55 |
| | 2.0 | | | | | 0.8 - 1.8' FILL: Red fine to medium sand, some silt and fine to medium gravel; moist, dense | | |
| | 3.0 | | | | | 1.8 - 3.0' FILL: Silt with fine sand; moderate dense, moist | | Sample collected 073-SB-031-0204 from 2.5-3.0' bgs @11:00 |
| | 4.0 | S-2 | NA | 4.0 | | 3.0 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 8.0' FILL: Brown fine to coarse sand, more fine sand with depth, trace shells; wet, loose | | Sample collected 073-SB-031-0406 from 4.5-5.0 bgs @11:05 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-031-0608 from 7.0-7.5 bgs @11:10 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 11.5' FILL: Brown fine to medium sand, trace silt and shells; wet, loose | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-031-0810 from 9.0-9.5 bgs @11:15 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Sample collected 073-SB-031-1012 from 11.0-11.5 bgs @11:20 |
| | 12.0 | | | | | 11.5 - 12.0' FILL: Silt with fine sand; wet, loose; end of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywel Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-031R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Fine to coarse grave, some dark brown fine to coarse sand | | |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Brown fine to medium sand, trace silt; moist, dense | | |
| | | | | | | 0.8 - 1.8' FILL: Red fine to medium sand, some silt and fine to medium gravel; moist, dense | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Silt with fine sand; moderate dense, moist | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Brown fine to medium sand, silt, trace shells; wet; end of boring at 8.0' bgs. | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-031R-0608 from 7.0-7.5 bgs at 8:10 |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-032
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.4' CONCRETE | 0 | |
| | 1.0 | | | | | 0.4 - 1.8' FILL: Brown fine to medium sand, some silt, trace fine to medium gravel and glass; moist, dense | | Sample collected 073-SB-032-0002 from 1.0-1.5' bgs @11:25 |
| | 2.0 | | | | | 1.8 - 2.3' FILL: Dark brown fine to medium sand, some clinker, trace wood; moist, dense | | |
| | 3.0 | | | | | 2.3 - 3.3' FILL: Silt, some fine sand, trace wood; moist, dense | | Sample collected 073-SB-032-0204 from 2.5-3.0' bgs @11:30 |
| | 4.0 | S-2 | NA | 3.5 | | 3.3 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.4' FILL: Silty clay, some fine to medium sand; wet, loose | | Sample collected 073-SB-032-0406 from 4.5-5.0 bgs @11:35 |
| | 6.0 | | | | | 4.4 - 7.5' FILL: Brown fine to coarse sand, some mottling of clay; wet, loose | | |
| | 7.0 | | | | | 7.5 - 8.0' No recovery | | Sample collected 073-SB-032-0608 from 6.5-7.0' bgs @11:40 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 11.0' FILL: Brown fine to medium sand, trace shells; wet, loose | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-032-0810 from 8.5-9.0' bgs @11:45 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Brown clayey silt, some fine sand; wet, very loose | | Sample collected 073-SB-032-1012 from 11.0-11.5' bgs @11:50 |
| | 12.0 | | | | | 11.5 - 12.0' FILL: Brown fine to medium sand, trace silt; wet loose; end of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-033
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Dark brown fine to medium sand, some fine to medium gravel, trace silt, coal, and clinker; moderate dense, moist | | Sample collected 073-SB-033-0002 from 1.0-1.5' bgs @11:55 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Reddish brown fine to medium sand, fine to coarse gravel, trace brick; moist, moderate dense | | |
| | 2.0 | | | | | 2.0 - 2.1' FILL: Grey lense of fine to medium sand | | |
| | 3.0 | | | | | 2.1 - 2.5' FILL: Dark brown fine to medium sand, some coal, trace fine to medium gravel | | Sample collected 073-SB-033-0204 from 2.5-3.0' bgs @12:00 |
| | 4.0 | S-2 | NA | 4.0 | | 2.5 - 3.5' FILL: Silt with fine sand; dense, moist | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | Sample collected 073-SB-033-0406 from 4.5-5.0' bgs @12:05 |
| | | | | | | 4.0 - 4.5' FILL: Silt with fine sand; firm, moist | | |
| | 6.0 | | | | | 4.5 - 8.0' FILL: Brown fine to coarse sand with lenses of clay; wet, loose | | |
| | 7.0 | | | | | | | Sample collected 073-SB-033-0608 from 7.0-7.5' bgs @12:10 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Brown fine to coarse sand with lenses of clay; wet, very loose; end of boring @ 12.0' bgs | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-033-0810 from 8.5-9.0' bgs @12:15 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Sample collected 073-SB-033-1012 from 10.5-11.0' bgs @12:20 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-034
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Brown fine to medium sand, trace silt, brick, and fine to medium gravel | | Sample collected 073-SB-034-0002 from 1.0-1.5' bgs @12:25 |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Silt, some fine sand; moist, moderate dense | | |
| | 2.0 | | | | | 1.3 - 2.3' FILL: Reddish brown fine to medium sand; moist, moderate dense | | |
| | 3.0 | | | | | 2.3 - 3.0' FILL: Brown silt, some fine sand; moist, dense | | Sample collected 073-SB-034-0204 from 2.5-3.0' bgs @12:30 |
| | 4.0 | S-2 | NA | 4.0 | | 3.0 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 4.3' FILL: Brown silt, some fine sand; wet, loose | | |
| | 5.0 | | | | | 4.3 - 4.8' FILL: Clayey silt; firm, wet | | Sample collected 073-SB-034-0406 from 4.5-5.0 bgs @12:35 |
| | 6.0 | | | | | 4.8 - 9.0' FILL: Brown fine to coarse sand with lenses of fine sand; wet, loose | | |
| | 7.0 | | | | | | | Sample collected 073-SB-034-0608 from 7.0-7.5' bgs @12:40 |
| | 8.0 | S-3 | NA | 3.5 | | | 0 | |
| | 9.0 | | | | | 9.0 - 11.0' FILL: Brown clayey silt; wet, very loose | | Sample collected 073-SB-034-0810 from 8.5-9.0 bgs @12:45 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Brown fine sand,some silt; loose, wet | | Sample collected 073-SB-034-1012 from 10.5-11.0 bgs @12:50 |
| | 12.0 | | | | | 11.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-035
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 0.8' FILL: Brown fine sand, some silt, trace gravel, moist, moderate dense | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Dark brown fine to coarse sand with fine to medium gravel, trace brick, coal, and clinker (staining) | | |
| | 2.0 | | | | | 1.3 - 1.9' FILL: Clayey silt, trace fine sand; firm, moist | | |
| | 3.0 | | | | | 1.9 - 3.0' FILL: Brown silt, some fine sand; moist, dense | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.0 - 3.3' FILL: Brown fine to coarse sand; moist, loose | 0 | |
| | | | | | | 3.3 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 7.5' FILL: Brown fine to coarse sand with lense of clay; wet, loose | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 11.0' FILL: Brown fine to medium sand with lenses of clay; wet, loose | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Brown silt, some fine sand; wet, very loose | | |
| | | | | | | 11.5 - 11.9' FILL: Brown fine to medium sand, trace silt; wet, loose | | |
| | 12.0 | S-4 | NA | 2.5 | | | 0 | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-035
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | | | | | 11.9 - 12.0' FILL: Clayey silt; wet, very loose<br>12.0 - 13.0' FILL: Brown fine to coarse sand with lenses of clay; wet, loose | | |
| | 14.0 | | | | | 13.0 - 13.8' OL: Brown clayey silt, fine sand; loose, wet<br>13.8 - 14.5' OL: Black silty clay, some fine sand; firm, moist | | |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-036
**DATE BEGAN:** 4/20/10
**DATE FINISHED:** 4/20/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' CONCRETE | 0 | |
| | 1.0 | | | | | 0.3 - 1.3' FILL: Dark brown fine to coarse sand, some clinker, trace brick | | Sample collected 073-SB-036-0002 from 0.5-1.0' bgs @13:35 |
| | 2.0 | | | | | 1.3 - 2.5' FILL: Brown clayey silt; firm, moist | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Brown fine to coarse sand; moist, loose | | Sample collected 073-SB-036-0204 from 3.0-3.5' bgs @13:40 |
| | 4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 11.5' FILL: Brown fine to coarse sand, lenses of clay; wet, loose | | Sample collected 073-SB-036-0406 from 5.0-5.5' bgs @13:45 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-036-0608 from 7.0-7.5' bgs @13:50 |
| | 8.0 | S-3 | NA | 4.0 | | | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-036-0810 from 8.5-9.0' bgs @13:55 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Sample collected 073-SB-036-1012 from 11.5-12.0' bgs @14:00 |
| | 12.0 | S-4 | NA | 3.0 | | 11.5 - 13.5' FILL: Brown clayey silt; wet, very loose | 0 | |
| | 13.0 | | | | | 13.5 - 14.0' FILL: Brown fine sand, some silt | | Sample collected 073-SB-036-1214 from 13.5-14.0' bgs @14:05 |
| | 14.0 | | | | | 14.0 - 14.5' OL: Brown clayey silt, some fine sand; loose, wet | | |
| | 15.0 | | | | | 14.5 - 14.9' OL: Black silty clay, some fine sand; firm, moist | | Sample collected 073-SB-036-1416from 14.0-14.5.0' bgs @14:10 |
| | | | | | | 14.9 - 15.0' PT: Peat | | |
| | 16.0 | | | | | 15.0 - 16.0' No recovery; end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South


**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-037
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 64.9 | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Dark brown fine to course sand with some fine to coarse gravel; moist, loose | 955 | Sample collected 073-SB-037-0002 from 1.0-1.5' bgs @07:40 |
| | 2.0 | | | | | 0.5 - 1.8' FILL: Brown fine to coarse sand, some fine to medium gravel, trace silt (staining); wet. loose | 217<br>231<br>211 | |
| | 3.0 | | | | | 1.8 - 2.0' FILL: Brown silty clay, some fine sand; firm, wet | 158 | Sample collected 073-SB-037-0204 from 2.5-3.0' bgs @07:45 |
| | 4.0 | S-2 | NA | 3.0 | | 2.0 - 3.0' Fill: Brown fine to medium silty sand; moist, loose | 72.0<br>76.7 | |
| | 5.0 | | | | | 3.0 - 4.0' No recovery | 85.3<br>41.5 | Sample collected 073-SB-037--0406 from 4.5-5.0' bgs @07:50 |
| | 6.0 | | | | | 4.0 - 7.0' FILL: Brown fine to medium silty sand, lenses of clay; wet, loose | 11.6<br>10.2 | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | 19.0 | Sample collected 073-SB-037-0608 from 6.5-7.0' bgs @07:55 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Brown fine to medium silty sand, lenses of clay; wet, loose | 0.9<br>4.3<br>4.3 | Sample collected 073-SB-037-0810 from 8.5-9.0' bgs @08:00 |
| | 9.0 | | | | | | 5.1<br>3.0<br>2.4 | |
| | 10.0 | | | | | | 2.0<br>2.1 | Sample collected 073-SB-037-1012 from 10.5-11.0' bgs @08:05 |
| | 11.0 | | | | | | 2.8 | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 13.8' FILL: Brown fine to medium silty sand, lenses of clay; wet, very loose | 2.5<br>0.6 | |
| | 13.0 | | | | | | 0 | Sample collected 073-SB-037-1214 from 13.0-13.5' bgs @08:10 |
| | 14.0 | | | | | 13.8 - 15.8' OL: Brown clayey silt, some fine sand, loose, wet | 0<br>0 | |
| | 15.0 | | | | | 15.8 - 16.0' OL: Black silty clay, some fine sand, firm; moist; end of boring @ 16.0' bgs | 0 | Sample collected 073-SB-037-1416 from 14.5-15.0' bgs @08:15 |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-038
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**




| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' CONCRETE | 150 | |
| | 1.0 | | | | | 0.3 - 1.3' FILL: Brown fine to coarse sand with fine to coarse gravel, trace coal and wood; wet, loose | 273 | Sample collected 073-SB-038-0002 from 0.5-1.0' bgs @08:20; Petroleum odor |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Brown silty clay, some fine sand; firm wet | 290<br>186 | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Brown clayey silt, some fine sand; loose, wet | 229<br>39.9 | Sample collected 073-SB-038-0204 from 2.5-3.0' bgs @08:25 |
| | 4.0 | S-2 | NA | 3.5 | | 3.0 - 3.3' FILL: Brown fine to coarse sand with lenses of clay; loose, wet | 14.9<br>15.8 | |
| | 5.0 | | | | | 3.3 - 4.0' No recovery | 13.6<br>11.7 | Sample collected 073-SB-038--0406 from 4.5-5.0' bgs @08:30 |
| | 6.0 | | | | | 4.0 - 7.5' FILL: Brown fine to coarse sand with lenses of clay, trace fine to medium gravel; loose, wet | 4.0<br>3.5 | |
| | 7.0 | | | | | 7.5 - 8.0' No recovery | 1.8 | Sample collected 073-SB-038-0608 from 7.0-7.5' bgs @08:35 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Brown silty fine sand; wet, very loose | 2.9<br>1.3 | |
| | 9.0 | | | | | 9.0 - 13.0' FILL: Brown fine to course sand with lenses of clay, trace fine gravel; loose, wet | 1.4<br>1.0<br>0.9<br>0<br>0 | Sample collected 073-SB-038-0810 from 9.0-9.5' bgs @08:40 |
| | 10.0 | | | | | | 0<br>0 | Sample collected 073-SB-038-1012 from 10.5-11.0' bgs @08:45 |
| | 11.0 | | | | | | 0<br>0 | |
| | 12.0 | S-4 | NA | 3.25 | | | 0<br>0 | |
| | 13.0 | | | | | 13.0 - 14.3' OL: Brown clayey silt, some fine sand; wet, very loose | 0<br>0 | Sample collected 073-SB-038-1214 from 12.5-13.0' bgs @08:50 |
| | 14.0 | | | | | 14.3 - 15.3' OL: Black silty clay, some fine sand; firm, moist | 0<br>0 | |
| | 15.0 | | | | | 15.3 - 16.0' No recovery; end of boring @ 16.0' bgs | 0 | Sample collected 073-SB-038-1416 from 14.5-15.0' bgs @ 8:55 |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-039
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.1' CONCRETE | | |
| | | | | | | 0.1 - 1.8' FILL: Brown fine to coarse sand, fine to medium gravel, trace brick and silt | 6.8<br>0.9<br>1.3 | Sample collected 073-SB-039-0002 from 0.5-1.0' bgs @ 09:00 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.8 - 3.8' FILL: Brown silty fine sand, trace organics and clay; firm moist | 43.1<br>10.5 | |
| | 3.0 | | | | | | 6 | Sample collected 073-SB-039-0204 from 3.0-3.5' bgs @ 09:05 |
| | | | | | | 3.8 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.75 | | 4.0 - 8.0' FILL: Brown fine to coarse sand with lenses of clay, trace fine gravel; loose, wet | 50.3<br>2.0 | |
| | 5.0 | | | | | | 0.8 | Sample collected 073-SB-039--0406 from 5.5-6.0' bgs @ 09:10 |
| | 6.0 | | | | | | 0 | |
| | 7.0 | | | | | | | Sample collected 073-SB-039-0608 from 7.0-7.5' bgs @ 09:15 |
| | 8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No recovery | 0 | |
| | | | | | | 8.0 - 9.0' FILL: Brown silty fine sand; wet, very loose | | |
| | 9.0 | | | | | 8.0 - 11.5' FILL: Brown fine to medium sand, some silt, trace clay; wet, very loose | | Sample collected 073-SB-039-0810 from 8.5-9.0' bgs @ 09:20 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Sample collected 073-SB-039-1012 from 11.5-12.0' bgs @ 09:25 |
| | | | | | | 9.0 - 12.5' FILL: Brown fine to coarse sand | | |

PREPARED BY: MS
CHECKED BY: MD

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-039
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | S-4 | NA | 3.5 | | with lenses of clay, trace fine gravel; loose, wet | 0 | |
| | 13.0 | | | | | 11.5 - 12.0' FILL: Brown clayey silt, some fine sand; wet, very loose | | |
| | | | | | | 12.5 - 14.0' OL: Brown clayey silt, some fine sand; wet, loose | | Sample collected 073-SB-038-1214 from 13.0-13.5' bgs @ 09:30 |
| | 14.0 | | | | | 14.0 - 15.4' OL: Black silty clay, some fine sand; firm, moist | | |
| | 15.0 | | | | | 15.4 - 15.5' PT: PEAT | | Sample collected 073-SB-038-1416 from 15.0-15.5' bgs @ 9:35 |
| | | | | | | 15.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: MD

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-040
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | | |
| | | | | | | 0.3 - 0.5' FILL: Fine to medium gravel, some brown fine to medium sand; firm moist | 734 | |
| | 1.0 | | | | | | 1994 | Sample collected 073-SB-040-0002 from 1.0-1.5' bgs @ 09:40 |
| | | | | | | 0.5 - 1.5' FILL: Red fine sand, some silt, trace fine to medium gravel; firm,dry | 2613 | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brown fine to coarse sand, some fine to medium gravel, trace silt; firm, moist (black staining) | 498 | |
| | | | | | | | 85.2 | |
| | 3.0 | | | | | 2.0 - 2.5' FILL: Brown fine silty sand, trace clay; firm, moist | 87.5 | Sample collected 073-SB-040-0204 from 2.5-3.0' bgs @ 09:45 |
| | 4.0 | S-2 | NA | 3.0 | | 2.5 - 3.0' FILL: Brown fine sand, trace silt; moist, moderate dense | 37.6 | |
| | | | | | | 3.0 - 4.0' No recovery | 21.0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Brown silty clay, some fine sand; moderate dense, wet | 10.0 | Sample collected 073-SB-040--0406 from 4.0-4.5' bgs @ 09:50 |
| | | | | | | | 6.0 | |
| | 6.0 | | | | | 4.5 - 7.0' FILL: Brown fine to coarse sand with lenses of clay, trace fine gravel and shell; loose, wet | 3.0 | |
| | | | | | | | 4.0 | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | 0 | Sample collected 073-SB-040-0608 from 6.5-7.0' bgs @ 09:55; DUP @ 9:57 |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.0' FILL: Brown silty fine to medium sand; wet, very loose | 0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Brown fine sandy silt; wet, very loose | | Sample collected 073-SB-040-0810 from 8.5-9.0' bgs @10:00 |
| | | | | | | 9.5 - 11.5' FILL: Brown fine to coarse sand, trace mottling of clay; loose, wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | 0 | Sample collected 073-SB-040-1012 from 11.0-11.5' bgs @ 10:05 |
| | | | | | | 11.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-041
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | 3325 | |
| | | | | | | 0.3 - 1.0' FILL: Brown fine sand, trace silt; moist, loose | 4511 | |
| | 1.0 | | | | | | 1243 | Sample collected 073-SB-041-0002 from 1.0-1.5' bgs @ 10:10; Organic Odors |
| | | | | | | 1.0 - 1.3' FILL: Brown fine to coarse sand, fine to medium gravel | 445 | |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Red fine silty sand, trace brick; firm, moist | 360 | |
| | | | | | | | 1213 | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Brown fine silty sand; medium dense, moist | 586 | Sample collected 073-SB-041-0204 from 2.5-3.0' bgs @ 10:15 |
| | | | | | | 3.0 - 4.0' No recovery | | |
| ▽ | 4.0 | S-2 | NA | 3.25 | | 4.0 - 4.5' FILL: Brown clayey silty, some fine sand; loose, wet | 1512 | |
| | | | | | | | 195 | |
| | 5.0 | | | | | 4.5 - 7.3' FILL: Brown fine to medium sand with lenses of clay, trace fine gravel; loose, wet | 33.9 | Sample collected 073-SB-041-0406 from4.0-4.5' bgs @ 10:20 |
| | | | | | | | 85.3 | |
| | 6.0 | | | | | | 37.6 | |
| | | | | | | | 47.2 | |
| | 7.0 | | | | | | 45.3 | Sample collected 073-SB-041-0608 from 6.5-7.0' bgs @ 10:25; DUP @ 10:27 |
| | | | | | | 7.3 - 8.0' FILL: No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Brown fine to coarse sand, trace mottling of clay and shells; loose, wet | | |
| | 9.0 | | | | | | | Sample collected 073-SB-041-0810 from 8.5-9.0' bgs @10:30 |
| | 10.0 | | | | | | | |
| | | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 11.0 | | | | | | | Sample collected 073-SB-041-1012 from 10.5-11.0' bgs @ 10:35 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-042
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE | | |
| | | | | | | 0.3 - 1.0' FILL: Dark brown fine to coarse sand with fine to coarse gravel, trace coal | 96.2 | Sample collected 073-SB-042-0002 from 1.0-1.5' bgs @ 10:40 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Brown silty clay, some fine sand; firm, moist | 9.1 | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Brown fine to medium sand, moist, loose | 6.7 | |
| | | | | | | | 11.6 | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | 29.3 | Sample collected 073-SB-042-0204 from 2.5-3.0' bgs @ 10:45 |
| ▽ | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Brown fine to medium sand with lenses of clay and silt, trace fine to medium gravel; wet, loose | 6.9 | |
| | | | | | | | 9.3 | |
| | 5.0 | | | | | | 4.5 | Sample collected 073-SB-042-0406 from 4.5-5.0' bgs @ 10:50 |
| | | | | | | | 1.2 | |
| | 6.0 | | | | | | 0.9 | |
| | | | | | | | 0.3 | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | 0 | Sample collected 073-SB-042-0608 from 7.0-7.5' bgs @ 10:55 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Brown fine to medium sand with lenses of clay; wet, very loose | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-042-0810 from 8.5-9.0' bgs @ 11:00 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring @ 12.0 ft bgs | | Sample collected 073-SB-042-1012 from 10.5-11.0' bgs @ 11:05 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-043
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' CONCRETE | | |
| | | | | | | 0.3 - 1.5' FILL: Dark brown fine to coarse sand with fine to coarse gravel, some wood, moist; moderate dense | 178 | |
| | 1.0 | | | | | | 157 | Sample collected 073-SB-043-0002 from 1.5-2.0' bgs @ 11:10 |
| | | | | | | 1.5 - 3.0' FILL: Brown silty clay, trace fine sand; firm moist | 185 | |
| | 2.0 | | | | | | 823 | |
| | | | | | | | 145 | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown fine to medium sand; moist, loose | 10.0 | Sample collected 073-SB-043-0204 from 3.0-3.5' bgs @ 11:15 |
| | | | | | | 3.5 - 4.0' No recovery | 8.3 | |
| ▽ | 4.0 | S-2 | NA | 3.5 | | 4.0 - 7.5' FILL: Brown fine to medium sand with lenses of clay and silt, trace fine to medium gravel; wet, loose | 0 | |
| | 5.0 | | | | | | 0 | Sample collected 073-SB-043-0406 from 5.0-5.5' bgs @ 11:20; DUP @ 11:22 |
| | 6.0 | | | | | | 0 | |
| | 7.0 | | | | | | 0 | Sample collected 073-SB-043-0608 from 6.5-7.05' bgs @ 11:25 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 11.0' FILL: Brown fine to medium sand with lenses of clay, wet, loose | 0.5 | |
| | | | | | | | 0.3 | |
| | 9.0 | | | | | | 0 | Sample collected 073-SB-043-0810 from 8.5-9.0' bgs @ 11:30 |
| | 10.0 | | | | | | 0 | |
| | 11.0 | | | | | 11.0 - 11.3' FILL: Brown silt; wet, very loose | 0 | Sample collected 073-SB-043-1012 from 10.5-11.0' bgs @ 11:35 |
| | | | | | | 11.3 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-044
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE | | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown fine to coarse sand, fine to medium gravel; moist, loose | 166 | Sample collected 073-SB-044-0002 from 1.0-1.5' bgs @ 11:40 |
| | | | | | | 1.0 - 2.3' FILL: Brown silty clay, trace fine sand; moist, firm | 268 | |
| | 2.0 | | | | | | 67.6 | |
| | | | | | | 2.3 - 3.0' FILL: Brown fine to medium sand with lenses of clay and silt, trace organics; moist, loose | 50.1 | |
| | 3.0 | | | | | | 140 | Sample collected 073-SB-044-0204 from 2.5-3.0' bgs @ 11:45 |
| ▽ | 4.0 | S-2 | NA | 3.5 | | 3.0 - 4.0' No recovery | | |
| | | | | | | 4.0 - 7.5' FILL: Brown fine to medium sand with mottling of clay and silt, less clay with depth, trace shells; wet, loose; (5.0-5.5' Black sand) (6.5-7.5' banding of brown and greyish brown fine to medium sand) | 104 | |
| | 5.0 | | | | | | 29.1 | |
| | | | | | | | 7.2 | Sample collected 073-SB-044-0406 from 5.0-5.5' bgs @ 11:50 |
| | 6.0 | | | | | | 4.3 | |
| | | | | | | | 4.1 | |
| | 7.0 | | | | | | 1.9 | |
| | | | | | | | 0.9 | Sample collected 073-SB-044-0608 from 6.5-7.0' bgs @ 11:55 |
| | | | | | | 7.5 - 8.0' No recovery | 0 | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 11.5' FILL: Brown fine to medium sand; wet, loose | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-044-0810 from 9.0-9.5' bgs @ 12:00 |
| | 10.0 | | | | | | 0 | |
| | 11.0 | | | | | | | Sample collected 073-SB-044-1012 from 11.0-11.5' bgs @ 12:05 |
| | 12.0 | | | | | 11.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-045

**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT

**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs

**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE | | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, fine to medium gravel, trace brick; moist, loose | 10.6 | Sample collected 073-SB-045-0002 from 0.5-1.0' bgs @ 12:10; Organic Odor |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Concrete | 1.3 | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Dark brown fine to course sand, some silt and fine to medium gravel; wet, loose | 3.6 | |
| | | | | | | | 212 | |
| | 3.0 | | | | | 2.0 - 2.2' FILL: Brown silty clay | 286 | Sample collected 073-SB-045-0204 from 2.0-2.50' bgs @ 12:15 |
| | | | | | | 2.2 - 2.8' FILL: Brown fine to coarse silty sand, fine to medium gravel; moist, firm | | |
| ▽ | 4.0 | S-2 | NA | 4.0 | | 2.8 - 3.0' FILL: Brown fine to medium sand with lenses of clay and silty; wet, loose | 64.7 | |
| | | | | | | | 156 | |
| | 5.0 | | | | | 3.0 - 4.0' No recovery | 34.7 | Sample collected 073-SB-045--0406 from 4.5-5.0' bgs @ 12:20 |
| | | | | | | 4.0 - 10.0' FILL: Brown fine to medium sand with lenses of clay and silt, trace brick, wet, loose | 13.2 | |
| | 6.0 | | | | | | 5.0 | |
| | | | | | | | 3.2 | |
| | 7.0 | | | | | | 1.9 | Sample collected 073-SB-045-0608 from 6.5-7.0' bgs @ 12:25 |
| | | | | | | | 1.4 | |
| | 8.0 | S-3 | NA | 2.5 | | | 1.9 | |
| | | | | | | | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-045-0810 from 8.5-9.0' bgs @ 12:30 |
| | 10.0 | | | | | 10.0 - 10.5' FILL: Fine to coarse brown sand | 0 | |
| | | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 11.0 | | | | | | | Sample collected 073-SB-045-1012 from 10.0-10.5' bgs @ 12:35 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-046
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' CONCRETE | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Dark brown fine to coarse silty sand, fine to medium gravel, trace brick and coal; moist, moderate dense | 3.5 | Sample collected 073-SB-046-0002 from 1.5-2.0' bgs @ 12:40 |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Brown silty clay, trace fine sand and organics | | |
| | 3.0 | | | | | 2.0 - 3.5' FILL: Brown fine to medium sand with lenses of clay; moist, loose | 0 | Sample collected 073-SB-046-0204 from 3.0-3.5' bgs @ 12:45 |
| | 4.0 | S-2 | NA | 3.5 | | 3.5 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 7.5' FILL: Brown fine to medium sand with lenses of clay; wet, loose | 0 | Sample collected 073-SB-046-0406 from 4.5-5.0' bgs @ 12:50: DUP @ 12:52 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-046-0608 from 6.5-7.0' bgs @ 12:55 |
| | 8.0 | S-3 | NA | 2.5 | | 7.5 - 8.0' No recovery | | |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Brown fine to medium sand with lenses of clay; wet, loose | 0 | Sample collected 073-SB-046-0810 from 8.5-9.0' bgs @ 13:00 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | Sample collected 073-SB-045-1012 from 10.0-10.5' bgs @ 13:05 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-047
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.2' ASPHALT | 0 | |
| | 1.0 | | | | | 0.2 - 1.5' FILL: Dark brown silty fine to coarse sand, fine to medium gravel, trace brick, coal, clinker; moist, loose | 12.0 | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Brown fine to medium sand, trace shells | 20.2<br>4.5<br>2.4 | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | 1.9 | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.5' FILL: Brown fine to medium sand with lenses of clay and silt, trace shells; loose, wet | 0.6<br>0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | 0 | |
| | 7.0 | | | | | | | Sample collected 073-SB-047-0608 from 6.5-7.0' bgs @ 13:15 |
| | 8.0 | S-3 | NA | 2.5 | | 7.0 - 8.0' No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 9.8' FILL: Brown fine to medium sand with lenses of clay and silt, trace shells; loose, wet | | Sample collected 073-SB-047-0810 from 8.5-9.0' bgs @ 13:20 |
| | 10.0 | | | | | 9.8 - 10.5' FILL: Brown fine to medium silty sand; wet, loose | 0 | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | Sample collected 073-SB-047-1012 from 10.0-10.5' bgs @ 13:25 |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' FILL: Brown fine to medium silty sand, more silt with depth; wet, loose | 0 | |
| | 13.0 | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0' bgs. | | Sample collected 073-SB-047-1214 from 12.5-13.0' bgs @ 13:30 |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-047R
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.2' ASPHALT | 0 | |
| | 1.0 | | | | | 0.2 - 1.5' FILL: Dark brown silty fine to coarse sand, fine to medium gravel, trace brick, coal, clinker; moist, loose | 12.0 | |
| | 2.0 | | | | | | 20.2 | |
| | 3.0 | | | | | 1.5 - 3.0' FILL: Brown fine to medium sand, trace shells | 4.5 | |
| | | | | | | | 2.4 | |
| | | | | | | 3.0 - 4.0' No recovery | 1.9 | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.5' FILL: Brown fine to medium sand with lenses of clay and silt, trace shells; loose, wet | 0.6 | |
| | 5.0 | | | | | | 0 | |
| | 6.0 | | | | | | 0 | |
| | 7.0 | | | | | | | |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 9.8' FILL: Brown fine to medium sand with lenses of clay and silt, trace shells; loose, wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.8 - 10.5' FILL: Brown fine to medium silty sand; wet, loose | 0 | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' FILL: Brown fine to medium silty sand, more silt with depth; wet, loose | 0 | |
| | 13.0 | | | | | | | |
| | | | | | | 13.5 - 14.0' No recovery | | |
| | 14.0 | S-5 | NA | 2.0 | | 14.0 - 16.0' FILL: Red brown silt, fine sand; wet; end of boring at 16.0' bgs. | 0 | Sample collected 073-SB-047R-1416 from 14.5-15.0' bgs @ 13:05 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 south

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480080011
**BORING ID:** 073-SB-048
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.4' CONCRETE | 3.1 | |
| | 1.0 | | | | | 0.4 - 1.3' FILL: Dark brown fine to medium silty sand, fine to medium gravel, trace coal and organics; moist, loose | 0 | |
| | 2.0 | | | | | 1.3 - 3.0' FILL: Brown fine to medium sand, fine to medium gravel, some mottling of clay; moist, moderate dense | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.75 | | 4.0 - 6.8' FILL: Brown fine to medium sand with lenses of clay and silt, trace shells and coarse sand; loose, wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.8 - 8.0' No recovery | | Sample collected 073-SB-048-0608 from 6.0-6.5' bgs @ 13:40 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.0' FILL: Brown fine to medium sand with lenses of clay and silt, trace shells and coarse sand; loose, wet | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-048-0810 from 8.5-9.0' bgs @ 13:45 |
| | 10.0 | | | | | 10.0 - 11.0' OL: Brown silt, trace fine sand; wet, very loose | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 073-SB-048-01012 from 10.5-11.0' bgs @ 13:50 |
| | 12.0 | S-4 | NA | 1.75 | | 12.0 - 13.8' OL: Brown silt, trace fine sand; wet, very loose | 0 | |
| | 13.0 | | | | | 13.8 - 14.0' No recovery; end of boring @ 14.0' bgs | | Sample collected 073-SB-048-1214 from 12.5-13.0' bgs @ 13:55 |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-049
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' APHALT | 0 | |
| | 1.0 | | | | | 0.1 - 0.5' CONCRETE | | |
| | 2.0 | | | | | 0.5 - 0.8' FILL: Brown silty sand, trace coal; dry, dense | | |
| | 3.0 | | | | | 0.8 - 3.5' FILL: Red sandy silt, trace fine to medium gravel, coal and clay; more clay with depth, trace lenses of fine sand; moist, firm | | |
| | 4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Brown fine to medium sand with mottling of clay and silt, trace coarse sand and shells; wet, loose | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-049-0608 from 6.0-6.5' bgs @ 11:25: DUP @ 11:27 |
| | 8.0 | | | | | 7.0 - 8.0' No recovery | | |
| | | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Brown fine to medium sand with mottling of clay and silt, trace coarse sand and shells; wet, loose | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-049-0810 from 9.0-9.5' bgs @ 11:30 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | Sample collected 073-SB-049-1012 from 10.0-10.5' bgs @ 11:35 |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 12.5' SM: Black silty sand; wet, very loose | 0 | |
| | 13.0 | | | | | 12.5 - 13.5' OL: Black silt , trace fine sand; wet, very loose | | Sample collected 073-SB-049-1214 from 12.0-12.5' bgs @ 11:40 (HOLD) |
| | 14.0 | | | | | 13.5 - 14.0' No recovery; end of boring @ 14.0' bgs | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-050
**DATE BEGAN:** 4/21/10
**DATE FINISHED:** 4/21/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.1' ASPHALT | 0 | |
| | | | | | | 0.1 - 0.3' FILL: Dark brown fine to medium silty sand, fine to medium gravel; dry, loose | | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Concrete | | |
| | 2.0 | | | | | 0.5 - 2.5' FILL: Brown clayey silt, trace fine to medium gravel; moist, firm | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Brown fine to coarse sand, mottling of grey silt; wet, loose | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.0 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 7.5' FILL: Brown fine to coarse sand, mottling of grey silt, lenses of brown clay; wet, loose | | Sample collected 073-SB-050-0608 from 6.5-7.0' bgs @ 11:05: DUP @ 11:07 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 8.8' FILL: Brown fine to medium sand, mottling of brown clay; wet, loose | 0 | |
| | 9.0 | | | | | 8.8 - 10.8' FILL: Black silt, trace fine sand; wet, very loose | | Sample collected 073-SB-050-0810 from 9.0-9.5' bgs @ 11:10 |
| | 10.0 | | | | | | | |
| | | | | | | 10.8 - 11.3' FILL: Brown fine to medium sand; wet, loose | | |
| | 11.0 | | | | | | | Sample collected 073-SB-050-1012 from 10.5-11.0' bgs @ 11:15 |
| | | | | | | 11.3 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' SM: Light brown fine to medium sand, mottling of clay and silt; wet, loose | 0 | Sample collected 073-SB-050-1214 from 12.5-13.0' bgs @ 11:20 (HOLD) |
| | 13.0 | | | | | 13.5 - 14.0' No recovery; End of boring @ 14.0' bgs | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-051
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Black/dark brown silty sand, gravel, coal, wood, glass | | |
| | 2.0 | | | | | 1.0 - 3.0' FILL: Red brown fine to medium sand, lenses of silt throughout | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Red brown fine to medium sand, lenses of silt throughout; wet; shells from 6.0-8.0' | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-051-0608 from 7.0-7.5' bgs @10:05 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine sand, silt | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.0 | | 12.0 - 13.0' FILL: Light brown fine sand, silt | 0 | Sample collected 073-SB-051-1214 from 12.0-12.5' bgs @10:10 |
| | 13.0 | | | | | 13.0 - 14.0' No recovery; end of boring at 14.0' | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-052
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Black silty sand, coal, gravel | | |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Light brown clayey silt | | |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Red brown silt | | |
| | 3.0 | | | | | 2.0 - 3.5' FILL: Light brown fine to medium sand, fine to medium gravel | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Light brown fine to medium sand, fine to medium gravel; shells from 6.0-8.0'; wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-052-0608 from 6.5-7.0' bgs @10:40<br>DUP @10:42 |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 10.0' FILL: Light brown fine sand, silt; saturated | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.0' : No recovery | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 13.0' FILL: Light brown/red brown silt, trace fine sand | 0 | |
| | 13.0 | | | | | 13.0 - 14.0' FILL: Light brown clayey silt; end of boring at 14.0' | | Sample collected 073-SB-052-1214 from 13.5-14.0' bgs @10:45 |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-053
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.8 - 2.5' FILL: Black silty sand, wood, gravel, concrete | | Sample collected 073-SB-053-0002 from 1.5-2.0' bgs @12:15 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | | | | | | 2.5 - 3.5' FILL: Yellow silt, gravel; dense; potential COPR | | Sample collected 073-SB-053-0204 from 3.0-3.5' bgs @12:20 |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' FILL: Concrete; end of boring at 4.0' | | |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-053R
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.8 - 2.5' FILL: Black silty sand, wood, gravel, concrete | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Yellow silt, gravel; dense; potential COPR | | |
| | 4.0 | S-2 | NA | 2.0 | | 3.5 - 4.0' FILL: Concrete; end of boring at 4.0' | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Dark brown silt, lenses of fine to medium sand, trace gravel | | |
| | 6.0 | | | | | 5.0 - 6.0' FILL: Red brown/light brown fine to medium sand, trace silt; end of boring at 6.0' bgs. | | Sample collected 073-SB-053R-0406 from 5.5-6.0' bgs @11:30 |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-054
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 5.0 ft. bgs.
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 3.0' CONCRETE | 0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.3' FILL: Light yellow silt; dense; potential COPR | | Sample collected 073-SB-054-0204 from 3.0-3.5' bgs @12:35 |
| | | | | | | 3.3 - 3.5' FILL: Concrete | | |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 5.0' FILL: Crushed concrete, coarse sand | 0 | |
| ▽ | 5.0 | | | | | 5.0 - 6.5' FILL: Light brown silt; dense, wet | | Sample collected 073-SB-054-0406 from 5.0-5.5' bgs @12:40 |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 7.5' FILL: Light brown fine to coarse sand, trace gravel; wet | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery; end of boring at 8.0' | | |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-055
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 3.5 ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, gravel | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Concrete | | |
| | | | | | | 1.5 - 2.0' FILL: Dark brown to black silty sand, wood, gravel, and coal | | Sample collected 073-SB-055-0002 from 1.5-2.0' bgs @ 9:05 |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Concrete | 0 | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Light brown fine to medium sand, gravel; refusal at 3.5' bgs; end of boring at 3.5' bgs. | | Sample collected 073-SB-055-0204 from 3.0-3.5' bgs @ 9:10 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-056
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' CONCRETE: Concrete | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Dark brown silty sand, gravel, glass, coal | | Sample collected 073-SB-056-0002 from 1.0-1.5' bgs @ 9:30 |
| | 2.0 | | | | | 1.5 - 2.3' FILL: Concrete | | |
| | 3.0 | | | | | 2.3 - 3.5' FILL: Gray fine to coarse sand, gravel | | Sample collected 073-SB-056-0204 from 3.0-3.5' bgs @ 9:35 |
| | 4.0 | S-2 | NA | 4.0 | | 3.5 - 4.5' FILL: Concrete | 0 | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Gray fine to coarse sand, gravel | | Sample collected 073-SB-056-0406 from 4.5-5.0' bgs @ 9:40 (Hold) |
| | | | | | | 5.0 - 6.0' FILL: Red brown silt, trace fine to medium sand, gravel | | |
| | 6.0 | | | | | 6.0 - 8.0' FILL: Light brown fine to medium sand, trace fine to medium gravel; wet; end of boring at 8.0' bgs. | | Sample collected 073-SB-056-0608 from 6.5-7.0' bgs @ 9:45 (Hold) |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-057
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' CONCRETE | 0 | |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Dark brown silty sand, gravel, wet | | Sample collected 073-SB-057-0002 from 1.0-1.5' bgs @ 10:00 |
| | 2.0 | | | | | 1.8 - 2.3' FILL: Gray fine to coarse sand | | |
| | | | | | | 2.3 - 3.0' FILL: Concrete | | Sample collected 073-SB-057-0204 from 2.0-2.5' bgs @ 10:05 |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brick | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.3' FILL: Brick | 0 | |
| | | | | | | 4.3 - 6.0' FILL: Brown silt, fine to medium sand, trace organics, trace brick, trace fine to medium gravel | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Brown fine to coarse sand, red brown silt lenses throughout, wet | | Sample collected 073-SB-057-0608 from 6.5-7.0' bgs @ 10:10 |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 10.0' FILL: Brown fine to coarse sand, saturated; end of boring at 10.0 ft. bgs. | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-057-0810 from 9.0-9.5' bgs @ 10:15 (Hold) |
| | 10.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-058
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 1.0' CONCRETE | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Dark brown silty sand, gravel; wet | | Sample collected 073-SB-058-0002 from 1.0-1.5' bgs @ 10:55 (HOLD) |
| | | | | | | 1.5 - 2.0' FILL: Concrete | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Gray fine to coarse sand, silt, gravel | | Sample collected 073-SB-058-0204 from 2.5-3.0' bgs @ 11:00 (HOLD) |
| | 3.0 | | | | | 3.0 - 3.3' FILL: Concrete | | |
| | | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 5.3' FILL: Gray fine to medium sand, silt | 0 | |
| | 5.0 | | | | | 5.3 - 6.5' FILL: Light brown fine to medium sand, lenses of red brown silt, wet at 6.0' | | Sample collected 073-SB-058-0406 from 5.0-5.5' bgs @ 11:05 (HOLD) |
| | 6.0 | | | | | 6.5 - 7.5' FILL: Brown fine to coarse sand; wet | | Sample collected 073-SB-058-0608 from 7.0-7.5' bgs @ 11:10 (HOLD) |
| | 7.0 | | | | | 7.5 - 8.0' No recovery; end of boring at 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-059
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' CONCRETE | 0 | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Dark brown silty sand, gravel | | Sample collected 073-SB-059-0002 from 1.0-1.5' bgs @ 11:20 |
| | | | | | | 1.3 - 2.0' FILL: Concrete | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Light brown to gray fine to coarse sand, gravel | | Sample collected 073-SB-059-0204 from 2.5-3.0' bgs @ 11:25 |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Concrete | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 5.0' FILL: Gray silt | 0 | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Brown silt, fine to medium sand | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Brown fine to coarse sand , trace shells, trace gravel; wet | | |
| | 7.0 | | | | | | | Sample collected 073-SB-059-0608 from 7.0-7.5' bgs @ 11:30 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 9.5' FILL: Brown fine to coarse sand; saturated | 0 | |
| | 9.0 | | | | | | | Sample collected 073-SB-059-0810 from 8.5-9.0' bgs @ 11:35 |
| | | | | | | 9.5 - 10.0' No recovery; end of boring at 10 ft. bgs. | | |
| | 10.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-060
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE: Concrete | 0 | |
| | | | | | | 0.5 - 3.0' FILL: Brown fine to medium sand, trace coal, fuel oil odor | 53.8 | |
| | 1.0 | | | | | | 75.1 | |
| | | | | | | | 129 | |
| | 2.0 | | | | | | 95.8 | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Dark brown fine to coarse sand, slight sheen, fuel oil odor, moist | 183 | |
| | | | | | | 3.5 - 4.0' FILL: No recovery | 191 | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 6.0' FILL: Brown fine to coarse sand, silt, trace shells, gravel, fuel oil odor, sheen; wet; end of boring at 6.0 ft. bgs. | 91.3 | |
| | | | | | | | 89.8 | |
| | 5.0 | | | | | | 124 | |
| | | | | | | | 85.3 | Sample collected 073-SB-060-0406 from 5.5-6.0' bgs @ 12:30 |
| | 6.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-061
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE | 51.3 | |
| | | | | | | 0.5 - 3.5' FILL: Dark brown fine to coarse sand, fuel oil odor, trace fine gravel, moist | 75.1 | |
| | 1.0 | | | | | | 85.9 | |
| | | | | | | | 105 | |
| | 2.0 | | | | | | 73.8 | |
| | | | | | | | | |
| | 3.0 | | | | | | 94.8 | |
| | | | | | | 3.5 - 4.0' No recovery | 123 | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 6.0' FILL: Dark brown fine to coarse sand, fuel oil odor, trace fine gravel, wet; end of boring at 6.0 ft. bgs. | 129 | |
| | | | | | | | 115 | |
| | 5.0 | | | | | | 101 | Sample collected 073-SB-061-0406 from 5.0-5.5' bgs @ 12:45 |
| | | | | | | | 65.3 | |
| | | | | | | | 58.7 | |
| | 6.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-062
**DATE BEGAN:** 8/5/10
**DATE FINISHED:** 8/5/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.8' CONCRETE | 0 | |
| | 1.0 | S-1 | NA | 3.0 | | 0.8 - 1.8' FILL: Black silty sand | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Brown fine to coarse sand | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.3' FILL: Brown fine to coarse sand | 0 | |
| | 5.0 | | | | | 4.3 - 7.0' FILL: Red brown to light brown fine to coarse sand; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Red brown to light brown fine to coarse sand, lenses of red brown silt; wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: No recovery | | Sample collected 073-SB-062-1012 from 10.5-11.0' bgs @ 13:10 |
| | 12.0 | S-4 | NA | 1.0 | | 12.0 - 13.0' FILL: Red brown to light brown fine to coarse sand, lenses of red brown silt; wet | 0 | |
| | 13.0 | | | | | 13.0 - 14.0' No recovery; end of boring at 14.0 ft. bgs. | | Sample collected 073-SB-062-1214 from 12.5-13.0' bgs @ 13:15 |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-063
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.0' CONCRETE: Concrete | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Dark brown silty sand | | Sample collected 073-SB-063-0002 from 1.0-1.5' bgs @ 11:40 |
| | | | | | | 1.5 - 2.0' CONCRETE: Concrete; end of boring at 2.0' bgs. | | |
| | 2.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-064
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' CONCRETE: Concrete | 0 | |
| | | | | | | 0.5 - 2.0' FILL: Red brown silty sand | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 3.0' CONCRETE: Concrete | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Red brown/light brown silt; end of boring at 4.0' bgs. | | Sample collected 073-SB-064-0204 from 3.5-4.0' bgs @ 12:30 |
| | 4.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-065
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 3 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | PID not working |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 073-SB-065-1012 from 10.5-11.0' bgs @ 13:35 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-065R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 3 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | PID not working |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' FILL: Light brown silt, clayey silt; end of boring at 14.0' | NA | Sample collected 073-SB-065R-1214 from 12.5-13.0' bgs @ 8:40 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-066
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE: Concrete | NA | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, gravel | | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Light brown fine to medium sand, lenses of silt; wet at 2.5' bgs | | PID not working |
| | 2.0 | | | | | | | |
| | | | | | | | | Sample collected 073-SB-066-0204 from 2.5-3.0' bgs @ 14:30 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | Sample collected 073-SB-066-0406 from 4.5-5.0' bgs @ 14:35 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 10.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor; end of boring at 10.0' bgs. | NA | |
| | 9.0 | | | | | | | Sample collected 073-SB-066-0810 from 8.5-9.0' bgs @ 14:40 |
| | 10.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-066R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | PID not working |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor; end of boring at 8.0' bgs. | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 073-SB-066R-1012 from 7.0-7.5' bgs @ 9:05 |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-067
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 7 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 2.0' FILL: Light brown fine to medium sand, fine to medium gravel | 0 | |
| | 1.0 | | | | | | | Sample collected 073-SB-067- 0002 from 1.0-1.5' bgs @7:55 |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Light brown clayey silt, fine to medium sand | | Sample collected 073-SB-067-0204 from 2.5-3.0' bgs @8:00 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 5.3' FILL: Light brown clayey silt, fine to medium sand | 0 | |
| | 5.0 | | | | | 5.3 - 5.8' FILL: White COPR | | Sample collected 073-SB-067-0406 from 5.5-6.0' bgs @8:05 |
| | 6.0 | | | | | 5.8 - 9.0' FILL: Light brown/light gray fine to coarse sand, shells; wet at 7.0' bgs. | | |
| ▽ | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.0 | | | 0 | Sample collected 073-SB-067-0608 from 7.5-8.0' bgs @8:10 |
| | 9.0 | | | | | | | Sample collected 073-SB-067-0810 from 8.5-9.0' bgs @8:15 |
| | 10.0 | | | | | 9.0 - 11.0' FILL: Light brown fine to medium sand, lenses of fine to coarse gravel throughout; wet | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 073-SB-067-1012 from 10.5-11.0' bgs @8:20 |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-067
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 7 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 14.0' FILL: Light brown fine to medium sand, trace shells; wet | 0 | Sample collected 073-SB-067-1214 from 12.5-13.0' bgs @8:25 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 16.5' FILL: Light brown/red brown clayey silt; soft; wet | | |
| | 15.0 | | | | | | | |
| | 16.0 | S-5 | NA | 4.0 | | | 0 | Sample collected 073-SB-067-1416 from 15.5-16.0' bgs @8:30 |
| | 17.0 | | | | | 16.5 - 18.5' OL: Light brown clayey silt; wet | | Sample collected 073-SB-067-1618 from 16.5-17.0' bgs @8:35 |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 18.5 - 19.8' SM: Brown fine to medium sand; organic odor; wet | | Sample collected 073-SB-067-1820 from 19.0-19.5' bgs @8:40 |
| | 20.0 | | | | | 19.8 - 20.0' SM: Brown fine to medium sand, organics; organic odor; wet; end of boring at 20.0' bgs. | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-068
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 22 ft bgs
**GW DEPTH:** 7 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.5' FILL: Black silty sand, gravel | 0 | Sample collected 073-SB-068- 0002 from 0.5-1.0' bgs @9:15 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Brown fine to medium sand, gravel | | Sample collected 073-SB-068-0204 from 2.5-3.0' bgs @9:20 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.5' FILL: Light brown fine to medium sand, silt | 0 | Sample collected 073-SB-068-0406 from 4.5-5.0' bgs @9:25 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Gray fine to medium sand; wet at 7.0' bgs. | | Sample collected 073-SB-068-0608 from 6.5-7.0' bgs @9:30 |
| ▽ | 7.0 | | | | | 7.0 - 8.0' FILL: No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 9.5' FILL: Gray fine to medium sand; wet | 0 | Sample collected 073-SB-068-0810 from 8.0-8.5' bgs @9:35 |
| | 9.0 | | | | | 9.5 - 9.6' FILL: Dark brown fine to medium sand ; wet | | |
| | 10.0 | | | | | 9.6 - 12.0' FILL: Light brown fine sand, silt; wet | | |
| | 11.0 | | | | | | | Sample collected 073-SB- |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-068
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 22 ft bgs
**GW DEPTH:** 7 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | | | | | | | 068-1012 from 11.0-11.5' bgs @9:40 |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 14.0' FILL: Light gray fine to medium sand; wet | 0 | |
| | 13.0 | | | | | | | Sample collected 073-SB-068-1214 from 12.5-13.0' bgs @9:45 |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Light brown fine to medium sand; wet | | |
| | | | | | | 14.5 - 15.0' FILL: Light brown/red brown silt; wet | | Sample collected 073-SB-068-1416 from 14.5-15.0' bgs @9:50 |
| | 15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | 16.0 | S-5 | NA | 3.5 | | 16.0 - 17.0' FILL: Light brown/red brown silt; wet | 0 | |
| | 17.0 | | | | | 17.0 - 19.0' OL: Light brown clayey silt; very moist | | Sample collected 073-SB-068-1618 from 16.5-17.0' bgs @9:55; DUP at 9:57 |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 19.0 - 19.5' SM: Brown fine to medium sand, organics; wet | | Sample collected 073-SB-068-1820 from 19.0-19.5' bgs @10:00 |
| | | | | | | 19.5 - 20.0' No recovery | | |
| | 20.0 | S-6 | NA | 2.0 | | 20.0 - 22.0' SM: Brown fine to medium sand, trace organics; wet; end of boring at 22.0' bgs. | 0 | |
| | 21.0 | | | | | | | Sample collected 073-SB-068-2022 from 21.5-22.0' bgs @10:05 |
| | 22.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-069
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 24 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | | | | | | 0.5 - 1.5' FILL: Dark brown/black silty sand, gravel | | Sample collected 073-SB-069-0002 from 1.0-1.5' bgs @10:15 |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 2.0' FILL: Crushed concrete, gravel | | |
| | 2.0 | | | | | 2.0 - 2.8' FILL: Light brown fine to medium sand | | Sample collected 073-SB-069-0204 from 2.0-2.5' bgs @10:20 |
| | 3.0 | | | | | 2.8 - 3.0' FILL: Wood | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 6.0' FILL: Black silty sand, yellow/orange from 4.5 - 5.0', gravel; potential COPR; wet | 0 | Sample collected 073-SB-069-0406 from 4.5-5.0' bgs @10:25 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Light gray/light brown fine to medium sand, wet | | |
| | 7.0 | | | | | | | Sample collected 073-SB-069-0608 from 7.0-7.5' bgs @10:30 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light gray/light brown fine to medium sand, shells, wet | 0 | Sample collected 073-SB-069-0810 from 8.5-9.0' bgs @10:35 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: No recovery | | Sample collected 073-SB-069-1012 from 10.5-11.0' bgs @10:40 |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 15.0' FILL: Light gray/light brown fine | 0 | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-069
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 24 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | | | | | to coarse sand, fine gravel, shells, wet | | Sample collected 073-SB-069-1214 from 12.5-13.0' bgs @10:45 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery | | Sample collected 073-SB-069-1416 from 14.5-15.0' bgs @10:50 |
| | 16.0 | S-5 | NA | 3.25 | | 16.0 - 16.5' FILL: Light brown/red brown silt; wet | 0 | |
| | 17.0 | | | | | 16.5 - 18.8' OL: Red brown clayey silt; very moist | | Sample collected 073-SB-069-1618 from 16.5-17.0' bgs @10:55; DUP at 10:57 |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 18.8 - 19.3' SM: Brown fine to medium sand, organics; wet | | Sample collected 073-SB-069-1820 from 19.0-19.5' bgs @11:00 |
| | | | | | | 19.3 - 20.0' No recovery | | |
| | 20.0 | S-6 | NA | 3.0 | | 20.0 - 23.0' SM: Light brown fine to medium sand, silt | 0 | |
| | 21.0 | | | | | | | Sample collected 073-SB-069-2022 from 21.5-22.0' bgs @11:05 |
| | 22.0 | | | | | | | |
| | 23.0 | | | | | 23.0 - 24.0' No recovery;end of boring at 24.0' bgs. | | |
| | 24.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-070
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, gravel | | Sample collected 073-SB-070-0002 from 0.5-1.0' bgs @11:15 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Crushed concrete, gravel | | |
| | 2.0 | | | | | 2.0 - 2.8' FILL: Dark brown silty sand, gravel, rubber, coal | | |
| | 3.0 | | | | | 2.8 - 3.5' FILL: Orange brown fine to medium sand | | Sample collected 073-SB-070-0204 from 3.0-3.5' bgs @11:20 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 6.0' FILL: Orange brown/light brown silt; wet at 5.0' bgs. | 0 | Sample collected 073-SB-070-0406 from 4.5-5.0' bgs @11:25 |
| ▽ | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Light brown/light gray fine to medium sand; wet | | |
| | 7.0 | | | | | | | Sample collected 073-SB-070-0608 from 7.0-7.5' bgs @11:30 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown/red brown fine to medium sand, lenses of silt, trace shells; wet | 0 | Sample collected 073-SB-070-0810 from 8.5-9.0' bgs @11:35 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 073-SB-070-1012 from 10.5-11.0' bgs @11:40 |
| | 11.0 | | | | | | | |
| | | | | | | 11.0 - 12.0' No recovery | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-070
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 15.0' FILL: Red brown silt, fine sand; wet | 0 | Sample collected 073-SB-070-1214 from 12.5-13.0' bgs @11:45 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 073-SB-070-1416 from 14.5-15.0' bgs @11:50 |
| | 15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | 16.0 | S-5 | NA | 3.5 | | 16.0 - 17.3' FILL: Red brown silt, fine sand; wet | 0 | Sample collected 073-SB-070-1618 from 16.5-17.0' bgs @11:55 |
| | 17.0 | | | | | 17.3 - 19.0' OL: Brown clayey silt; soft; wet | | |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 19.0 - 19.5' SM: Brown fine to medium sand, organics; wet | | Sample collected 073-SB-070-1820 from 19.0-19.5' bgs @12:00 |
| | 20.0 | | | | | 19.5 - 20.0' No recovery; end of boring at 20.0' bgs. | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-071
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 3 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | Sample collected 073-SB-071-1012 from 10.5-11.0' bgs @ 13:10 |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-072
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 3 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | Sample collected 073-SB-072-1012 from 10.5-11.0' bgs @ 13:20 |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-073
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE: Concrete | NA | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, gravel | | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Light brown fine to medium sand, lenses of silt; wet at 2.5' bgs | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 6.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor; end of boring at 6.0' bgs. | NA | |
| | 5.0 | | | | | | | Sample collected 073-SB-073-0406 from 5.0-5.5' bgs @ 13:30 |
| | 6.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480050143
**BORING ID:** 073-SB-074
**DATE BEGAN:** 11/29/10
**DATE FINISHED:** 11/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' CONCRETE: Concrete | NA | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, gravel | | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Light brown fine to medium sand, lenses of silt; wet at 2.5' bgs | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 6.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor; end of boring at 6.0' bgs. | NA | |
| | 5.0 | | | | | | | Sample collected 073-SB-074-0406 from 5.0-5.5' bgs @ 13:40 |
| | 6.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480100027
**BORING ID:** 073-SB-075
**DATE BEGAN:** 2/15/11
**DATE FINISHED:** 2/15/11
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 15 ft bgs
**GW DEPTH:** 3 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 12.5' FILL: Light brown fine to medium sand; wet | NA | |
| | 13.0 | | | | | 12.5 - 15.0' FILL: Light brown/red brown silt; wet; end of boring at 15.0' bgs. | | Sample collected 073-SB-075-1214 from 12.5-13.0' bgs @ 14:15 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 073 Degen Oil
**PROJECT NO:** 3480100027
**BORING ID:** 073-SB-076
**DATE BEGAN:** 2/15/11
**DATE FINISHED:** 2/15/11
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 3 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' CONCRETE: Concrete | NA | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown fine to coarse sand, lenses of silt; strong petroleum odor; wet at 3.0' bgs | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.0' FILL: Light brown fine to medium sand, silt, sheen; wet; petroleum odor | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.5' FILL: Light brown/red brown fine to medium sand, trace silt; wet | | Sample collected 073-SB-076-1012 from 10.5-11.0' bgs @ 14:35 |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.0 | | | NA | |
| | 13.0 | | | | | 12.5 - 14.0' FILL: Red brown/light brown silt; wet; end of boring at 14.0' bgs. | | Sample collected 073-SB-076-1214 from 13.0-13.5' bgs @ 14:40 |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**LOCATION:** Site 073 Degen Oil
**PROJECT NO:** 3480100027
**BORING ID:** 073-SB-077
**DATE BEGAN:** 3/21/2011
**DATE FINISHED:** 3/21/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8ft bgs
**GW DEPTH:** NA
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | Raining | Continuous push, no sleeve taken |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 3.5 | | 4.0 - 7.5' FILL: Greyish brown fine to medium sand, some mottling of reddish brown clayey silt, trace fine gravel; wet | | Sheen from 4.0-5.0' bgs<br>Sample collected 073-SB-077-0406 from 5.0-5.5' bgs @ 13:30<br>Organic Odor |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.5 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell SA-6 South

**LOCATION:** Site 073 Degen Oil
**PROJECT NO:** 3480100027
**BORING ID:** 073-SB-078
**DATE BEGAN:** 1/16/2012
**DATE FINISHED:** 1/16/2012
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake/Brian
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' CONCRETE | NA | |
| | | | | | | 0.8 - 1.5' FILL: Light brown fine sand, some silt, fine to medium gravel; moist, dense | | Sample collected 073-SB-078-0002 from 1.0 - 1.5' bgs @ 10:25 |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 3.0' CONCRETE | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.8' FILL: Brown fine to medium sand, some fine gravel, silt; very dense, moist | | Sample collected 073-SB-078-0204 from 3.5 - 4.0' bgs @ 10:27 |
| | | | | | | 3.8 - 4.0' FILL: Light grey silt; dense, moist; end of boring @ 4.0' bgs | | |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-101
**DATE BEGAN:** 5/5/14
**DATE FINISHED:** 5/5/14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** -
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 19' bgs
**GW DEPTH:** 13' bgs
**DRILLER:** Ed Blewett
**NORTH:** N/A
**EAST:** N/A

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 2.0' CONCRETE: Augered through 2' of CONCRETE | | |
| | 1.0 | | | | | | | |
| | 2.0 | | 26 | 0.75 | | 2.0 - 2.8' FILL: Greenish brown fine to coarse SAND, trace fine gravel, concrete, COPR; dense, moist | N/A | Refusal at 2' 9" bgs |
| | | | 3/50 | | | | | Sample collected 073-SB-101-0204 @ 1025, from 2-2.5' bgs |
| | 3.0 | | REFUSAL | | | 2.8 - 5.0' CONCRETE: CONCRETE | | |
| | 4.0 | | | | | | | |
| | 5.0 | | 12 | 1 | | 5.0 - 6.0' FILL: Reddist brown SILT, trace fine sand and fine gravel; dense, moist | N/A | Sample collected 073-SB-101-0507 @ 1125, from 5-5.5' bgs |
| | | | 14 | | | | | |
| | 6.0 | | 20 | | | 6.0 - 7.0' No Recovery | | |
| | | | 14 | | | | | |
| | 7.0 | | 12 | 0.5 | | 7.0 - 7.5' FILL: Reddist brown SILT, trace fine sand and fine gravel; dense, moist | N/A | Sample collected 073-SB-101-0709 @ 1135, from 7-7.5' bgs |
| | | | 17 | | | 7.5 - 9.0' No Recovery | | |
| | 8.0 | | 22 | | | | | |
| | | | 12 | | | | | |
| | 9.0 | | 10 | 0 | | 9.0 - 11.0' No Recovery | N/A | |
| | | | 15 | | | | | |
| | 10.0 | | 11 | | | | | |

PREPARED BY: KK
CHECKED BY: MS

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-101
**DATE BEGAN:** 5/5/14
**DATE FINISHED:** 5/5/14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** -
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 19' bgs
**GW DEPTH:** 13' bgs
**DRILLER:** Ed Blewett
**NORTH:** N/A
**EAST:** N/A

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | | 10 | | | | | |
| | 11.0 | | 4 | 0.5 | | 11.0 - 11.5' FILL: Reddish brown SILT, some fine to medium sand, trace gravel; medium dense, moist | N/A | Sample collected 073-SB-101-1113 @ 1300, from 11-11.5' bgs |
| | | | 3 | | | 11.5 - 13.0' No Recovery | | |
| | 12.0 | | 3 | | | | | |
| | | | 2 | | | | | |
| | 13.0 | | 2 | 0.5 | | 13.0 - 13.5' FILL: Reddish brown SILT, some fine to medium sand, trace gravel; medium dense, wet | N/A | Sample collected 073-SB-101-1315 @ 1320, from 13-13.5' bgs |
| | | | 2 | | | 13.5 - 15.0' No Recovery | | |
| | 14.0 | | 1 | | | | | |
| | | | 1 | | | | | |
| | 15.0 | | 1 | 2.0 | | 15.0 - 17.0' FILL: Reddish brown SILT, some fine to medium sand, trace gravel; medium dense, wet, more silt in bottom | N/A | |
| | | | 1 | | | | | |
| | 16.0 | | 1 | | | | | Sample collected 073-SB-101-1517 @ 1335, from 16-16.5' bgs |
| | | | 1 | | | | | |
| | 17.0 | | 3 | 2.0 | | 17.0 - 18.5' ML: Reddish brown CLAYEY SILT; soft, wet | N/A | |
| | | | 2 | | | | | |
| | 18.0 | | 2 | | | | | Sample collected 073-SB-101-1719 @ 1350, from 18-18.5' bgs; HOLD |
| | | | 2 | | | 18.5 - 19.0' SW: Grey fine to coarse SAND; loose, wet; End of boring at 19' | | |
| | 19.0 | | | | | | | |

PREPARED BY: KK
CHECKED BY: MS

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-102
**DATE BEGAN:** 5/6/14
**DATE FINISHED:** 5/6/14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** -
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 9' bgs
**GW DEPTH:** 7' bgs
**DRILLER:** Ed Blewett
**NORTH:** N/A
**EAST:** N/A

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 3.0' CONCRETE: Auger through 3' of CONCRETE | N/A | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | 7 | 0.75 | | 3.0 - 3.8' FILL: Brown/ reddish brown fine to coarse SAND, trace silt and fine to medium gravel; medium dense, moist | | Sample collected 073-SB-102-0305 @ 0900, from 3-3.5' bgs |
| | | | 15 | | | | | |
| | 4.0 | | 24 | | | 3.8 - 5.0' No Recovery | | |
| | | | 39 | | | | | |
| | 5.0 | | 1/14, 2/19 | 1 | | 5.0 - 6.0' FILL: Brown fine to coarse SAND, trace shells; medium dense, moist | N/A | First spoon broke; moved location 3' north, drove second spoon to depth |
| | | | 28, 26 | | | | | Sample collected 073-SB-102-0507 @ 1055, from 5.5-6' bgs |
| | 6.0 | | 20, 26 | | | 6.0 - 7.0' No Recovery | | |
| | | | 30, 23 | | | | | |
| | 7.0 | | 8 | 0.5 | | 7.0 - 7.5' FILL: Grey fine to coarse SAND; loose, wet; End of boring at 9' | N/A | |
| | | | 11 | | | 7.5 - 9.0' No Recovery | | |
| | 8.0 | | 12 | | | | | |
| | | | 10 | | | | | |
| | 9.0 | | | | | | | |

PREPARED BY: KK
CHECKED BY: MS

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-103
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 6.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' SW: Gray fine to coarse SAND, fine gravel; loose, wet | NM | Starting elevation 9.75'<br>20 degrees past vertical boring angle<br>Sample collected from 0.5-1.0' @ 8:30 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 2.0' SW: Brown fine to medium SAND, trace fine gravel; medium dense, moist | | Sample collected from 1.5-2.0' @ 8:32 |
| | 3.0 | | | | | 2.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | | 2.5 | | 4.0 - 6.5' SW: Light gray/light brown fine to coarse SAND, fine to coarse gravel; medium dense, moist (wet at 6.0' bgs) | | Sample collected from 4.0-4.5' @ 8:40 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected from 6.0-6.5' @ 8:42 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | | | | | 8.0 - 8.3' ML: Very light brown SILT, some | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-103
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 6.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | | 4.0 | | fine gravel | | Sample collected from 8.0-8.5' @ 8:50 |
| | | | | | | 8.3 - 10.4' SW: Light brown fine to coarse SAND; dense, wet | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | | | | | | 10.4 - 12.0' SW: Light brown/reddish brown fine to coarse SAND, some silt, trace fine gravel; dense, wet | | Sample collected from 10.5-11.0' @ 8:55 |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | | 4.0 | | 12.0 - 14.0' SW: Gray/reddish brown fine to medium SAND, some silt; medium dense, wet | | Sample collected from 12.0-12.5' @ 9:10 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 16.4' SW: Gray fine to coarse SAND; medium dense, wet | | Sample collected from 14.0-14.5' @ 9:15 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-103
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 6.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | | 3.0 | | | | Sample collected from 16.0-16.5' @ 9:30 |
| | | | | | | 16.4 - 18.7' ML: Brown SILT | | |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | Sample collected from 18.0-18.5' @ 9:35 |
| | | | | | | 18.7 - 19.0' ML: Reddish brown clayey SILT | | |
| | 19.0 | | | | | 19.0 - 20.0' No recovery | | |
| | 20.0 | S-6 | | 2.0 | | 20.0 - 21.3' ML: Reddish brown SILT | | Sample collected from 20.0-20.5' @ 10:00 |
| | 21.0 | | | | | 21.3 - 21.5' OL: Dark gray/black SILT with organics | | |
| | | | | | | 21.5 - 22.0' SW: Olive green/gray fine to medium SAND; loose, wet | | |
| | 22.0 | | | | | 22.0 - 24.0' No recovery. End of boring at 24.0' bgs. | | |
| | 23.0 | | | | | | | |
| | 24.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-104
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 8.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' FILL: Reddish brown FILL (celgene) | NM | Starting elevation 10.5' |
| | | | | | | 0.5 - 2.0' SW: Brown fine to coarse SAND, fine gravel; medium dense, moist | | 20 degrees past vertical boring angle |
| | 1.0 | | | | | | | Sample collected from 1.0-1.5' @ 10:30 |
| | 2.0 | | | | | 2.0 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | | 4.0 | | 4.0 - 4.8' GRAVEL: Crushed coarse gravel | | |
| | | | | | | 4.8 - 5.3' SW: Brown fine to coarse SAND, fine to coarse gravel | | Sample collected from 4.5-5.0' @ 10:40 |
| | 5.0 | | | | | 5.3 - 6.0' CONCRETE: Crushed concrete | | |
| | 6.0 | | | | | 6.0 - 8.0' SW: Brown fine to coarse SAND, fine to coarse gravel, trace glass, slag; medium dense, moist | | Sample collected from 6.0-6.5' @ 10:42 |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-104
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 8.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | | 3.0 | | 8.0 - 9.0' ML: Very light brown SILT; loose, wet | | Sample collected from 8.0-8.5' @ 11:00 |
| | 9.0 | | | | | 9.0 - 11.0' SW: Gray fine to coarse SAND; loose, wet | | |
| | 10.0 | | | | | | | Sample collected from 10.0-10.5' @ 11:05 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | | 4.0 | | 12.0 - 13.3' SW: Dark brown fine to coarse SAND, fine gravel; loose, wet | | Sample collected from 12.0-12.5' @ 11:20 |
| | 13.0 | | | | | 13.3 - 14.8' SW: Gray fine to coarse SAND; medium dense, wet | | |
| | 14.0 | | | | | | | Sample collected from 14.0-14.5' @ 11:25 |
| | 15.0 | | | | | 14.8 - 16.8' SW: Reddish brown/ gray fine to medium SAND; medium dense, wet | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-104
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 8.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | | 3.0 | | | | Sample collected from 16.0-16.5' @ 11:50 |
| | 17.0 | | | | | 16.8 - 19.0' SW: Reddish brown fine SAND, some silt; medium dense, wet | | |
| | 18.0 | | | | | | | Sample collected from 18.0-18.5' @ 11:55 |
| | 19.0 | | | | | 19.0 - 20.0' No recovery | | |
| | 20.0 | S-6 | | 3.5 | | 20.0 - 21.8' ML: Reddish brown SILT | | Sample collected from 20.0-20.5' @ 12:45 |
| | 21.0 | | | | | | | |
| | 22.0 | | | | | 21.8 - 22.0' ML: Reddish brown/gray SILT<br>22.0 - 22.4' OL: Dark gray SILT with organics, trace sand | | Sample collected from 22.0-22.5' @ 12:50 |
| | 23.0 | | | | | 22.4 - 23.5' SW: Gray fine to medium SAND, trace organics | | |
| | 24.0 | | | | | 23.5 - 24.0' No recovery. End of boring at 24.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-105
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 12.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.0' FILL: Reddish brown fine SAND (celgene) | NM | Starting elevation 10.6' |
| | 1.0 | | | | | 1.0 - 1.5' SW: Dark brown fine to coarse SAND, fine to coarse gravel; medium dense, moist | | 20 degrees past vertical boring angle<br>Sample collected from 1.0-1.5' @ 13:20 |
| | 2.0 | | | | | 1.5 - 2.0' CONCRETE: Crushed concrete | | |
| | 3.0 | | | | | 2.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | | 4.0 | | 4.0 - 4.8' SW: Brown fine to coarse SAND, fine to coarse gravel, trace crushed concrete; medium dense, moist | | Sample collected from 4.0-4.5' @ 13:30 |
| | 5.0 | | | | | 4.8 - 5.0' SW: Black fine to coarse SAND, fine to coarse gravel | | |
| | 6.0 | | | | | 5.0 - 8.0' SW: Light/dark brown fine to medium SAND, fine to coarse gravel, trace glass, plastic; medium dense, moist | | Sample collected from 6.0-6.5' @ 13:35 |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-105
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 12.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | | 3.25 | | 8.0 - 9.3' SW: Brown/black fine to coarse SAND, fine gravel, trace silt; medium dense, moist | | Sample collected from 8.0-8.5' @ 13:45 |
| | 9.0 | | | | | 9.3 - 11.3' SW: Brown fine to coarse SAND, trace fine gravel; medium dense, wet | | Hydrocarbon-like odor and sheen present (9.25-11.25') |
| | 10.0 | | | | | | | Sample collected from 10.0-10.5' @ 13:50 |
| | 11.0 | | | | | 11.3 - 12.0' No recovery | | |
| | 12.0 | S-4 | | 3.0 | | 12.0 - 14.0' SW: Gray/brown fine to medium SAND; medium dense, wet | | Sample collected from 12.0-12.5' @ 14:05 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 14.3' ML: Reddish brown SILT | | Sample collected from 14.0-14.5' @ 14:10 |
| | | | | | | 14.3 - 15.0' SW: Reddish brown/gray fine SAND, trace silt; medium dense, wet | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-105
**DATE BEGAN:** 5-9-16
**DATE FINISHED:** 5-9-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 12.0' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | | 2.5 | | 16.0 - 16.8' SW: Gray fine to coarse SAND, trace silt; loose, wet | | Sample collected from 16.0-16.5' @ 14:30 |
| | 17.0 | | | | | 16.8 - 18.3' SM: Reddish brown/light gray intermingled SILT, trace fine sand; medium dense, moist | | |
| | 18.0 | | | | | 18.3 - 18.5' SP: Reddish brown fine SAND, trace silt; medium dense, wet | | Sample collected from 18.0-18.5' @ 14:35 |
| | | | | | | 18.5 - 20.0' No recovery | | |
| | 19.0 | | | | | | | |
| | 20.0 | S-6 | | 3.5 | | 20.0 - 22.5' ML: Reddish brown SILT; medium dense, wet | | Sample collected from 20.0-20.5' @ 14:50 |
| | 21.0 | | | | | | | |
| | 22.0 | | | | | | | Sample collected from 22.0-22.5' @ 14:55 |
| | | | | | | 22.5 - 22.8' ML: Dark gray SILT | | |
| | 23.0 | | | | | 22.8 - 23.5' SW: Olive green/gray fine to medium SAND; loose, wet | | |
| | | | | | | 23.5 - 24.0' No recovery. End of boring at 24.0' bgs. | | |
| | 24.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-106
**DATE BEGAN:** 5-10-16
**DATE FINISHED:** 5-10-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 7.25' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.0 | | 0.0 - 1.0' CONCRETE: Crushed CONCRETE, some fine to coarse sand; dense, dry | NM | Starting elevation 10.5'<br>20 degrees past vertical boring angle<br>Sample collected from 0.5-1.0' @ 8:05 |
| | 1.0 | | | | | 1.0 - 4.0' No recovery | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | | 4.0 | | 4.0 - 4.8' SW: Dark brown fine to coarse SAND, fine to coarse gravel, trace glass; medium dense, mosit | | Sample collected from 4.0-4.5' @ 8:10 |
| | 5.0 | | | | | 4.8 - 6.0' CONCRETE: Crushed concrete and coarse gravel; dry | | |
| | 6.0 | | | | | 6.0 - 7.3' SW: Brown fine SAND, trace fine gravel and silt; medium dense, moist | | Sample collected from 6.0-6.5' @ 8:15 |
| | 7.0 | | | | | 7.3 - 8.0' SM: Reddish brown fine SAND and SILT; medium dense, wet | | |
| | 8.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-106
**DATE BEGAN:** 5-10-16
**DATE FINISHED:** 5-10-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 7.25' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | | 2.75 | | 8.0 - 10.8' SW: Gray/reddish brown fine to coarse SAND, trace silt; medium dense, wet | | Sample collected from 8.0-8.5' @ 8:20 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected from 10.0-10.5' @ 8:25 |
| | 11.0 | | | | | 10.8 - 12.0' No recovery | | |
| | 12.0 | S-4 | | 3.25 | | 12.0 - 15.5' SM: Reddish brown/gray fine to coarse SAND and SILT; medium dense, wet | | Sample collected from 12.0-12.5' @ 8:40 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected from 14.0-14.5' @ 8:45 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | 15.5 - 16.0' No recovery | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Site 073
**PROJECT NO:** 3480130377
**BORING ID:** 073-SB-106
**DATE BEGAN:** 5-10-16
**DATE FINISHED:** 5-10-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 24' bgs
**GW DEPTH:** 7.25' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | | 4.0 | | 16.0 - 20.0' SW: Reddish brown fine SAND, some silt (from 19.5-20.0' bgs); medium dense, wet | | Sample collected from 16.0-16.5' @ 9:00 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | Sample collected from 18.0-18.5' @ 9:05 |
| | 19.0 | | | | | | | |
| | 20.0 | S-6 | | 4.0 | | 20.0 - 22.0' ML: Reddish brown SILT, trace fine sand; medium dense, wet | | Sample collected from 20.0-20.5' @ 9:30 |
| | 21.0 | | | | | | | |
| | 22.0 | | | | | 22.0 - 22.4' ML: Reddish brown and gray SILT | | Sample collected from 22.0-22.5' @ 9:35 |
| | | | | | | 22.4 - 22.6' OL: Gray SILT with organics | | |
| | 23.0 | | | | | 22.6 - 24.0' SW: Gray fine to medium SAND with organics; loose, wet. End of boring at 24.0' bgs. | | |
| | 24.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-MW-010
**DATE BEGAN:** 6/9/10
**DATE FINISHED:** 6/9/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5.25 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' TOPSOIL: Light brown topsoil | 0 | |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Brown silty sand, gravel, coal | | |
| | 2.0 | | | | | 1.3 - 2.8' FILL: Dark brown to brown silt, trace fine sand, gravel, coal, glass | | |
| | 3.0 | | | | | 2.8 - 2.9' FILL: Crushed concrete, gravel | | |
| | | | | | | 2.9 - 3.0' FILL: Dark brown silty sand, gravel | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 4.3' FILL: Brown to light orange silt, fine to coarse sand, moist | | |
| | 5.0 | | | | | 4.3 - 5.3' FILL: Light brown to gray fine to medium sand, wet | | Set well 124-MW-010 to 11' bgs. |
| | 6.0 | | | | | 5.3 - 5.5' FILL: Light brown to gray silt, lenses of fine to medium sand, wet | | Screen Interval 3' - 11' bgs. |
| | 7.0 | | | | | 5.5 - 6.5' FILL: Brown peat, heavy organics, moist | | |
| | | | | | | 6.5 - 7.0' FILL: Dark brown silty sand, fine to coarse gravel, clinker, wet | | |
| | 8.0 | S-3 | NA | 3.5 | | 7.0 - 8.0' No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 10.0' FILL: Dark brown silty sand, fine to coarse gravel, clinker, wet | | |
| | 10.0 | | | | | 10.0 - 10.5' OL: Light brown clayey silt, wet | | |
| | | | | | | 10.5 - 11.3' OL: Black clayey silt, wet | | |
| | 11.0 | | | | | 11.3 - 11.5' PT: Brown peat, moist | | |
| | 12.0 | | | | | 11.5 - 12.0' No recovery; end of boring at 12.0 ft. bgs. | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-MW-011
**DATE BEGAN:** 6/9/10
**DATE FINISHED:** 6/9/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.8' TOPSOIL: Light brown topsoil | 0 | |
| | 1.0 | | | | | 0.8 - 2.5' FILL: Dark brown to black silty sand, coal, gravel, trace glass | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Light brown silty sand, coal, gravel, trace glass | | |
| | | | | | | 3.5 - 3.8' FILL: Light brown fine to coarse sand, very moist | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.8 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 4.5' FILL: Light brown fine to coarse sand, very moist | | |
| | 5.0 | | | | | 4.5 - 6.0' FILL: Light brown to red brown silt, fine sand, wet | | Set well 124-MW-011 to 8' bgs. |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Brown fine to medium sand, silt, wet | | Screen Interval 2' - 8' bgs. |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Brown silt with organics, wet | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 8.5' OL: Light brown clayey silt with heavy organics, wet | 0 | |
| | 9.0 | | | | | 8.5 - 10.0' PT: Brown peat, moist; end of boring at 10 ft. bgs. | | |
| | 10.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 124-MW-12
**DATE BEGAN:** 2-19-16
**DATE FINISHED:** 2-19-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 12 | 2.0 | | 10.0 - 11.7' SW: Gray fine to coarse SAND; medium dense, wet | NM | Augered to 10' bgs<br><br>Starting elevation 10.0'<br><br>GW elevation 6.0' |
| | | | 20 | | | | | |
| | 11.0 | | 13 | | | | | Meadow mat expected at elevation -1 to -2 (11.0-12.0' bgs) |
| | | | 9 | | | | | |
| | | | | | | 11.7 - 11.8' OL: Dark gray SILT with organics | | |
| | 12.0 | | | | | 11.8 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 124-MW-13
**DATE BEGAN:** 2-10-16
**DATE FINISHED:** 2-10-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 13' bgs
**GW DEPTH:** 3' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | SS1 | 30 | 0.8 | | 9.0 - 9.3' Dark gray screenings | NM | Augered to 9' bgs<br>Starting elevation 9.5'<br>GW elevation 6.5' |
| | | | 61 | | | 9.3 - 9.8' Crushed concrete | | |
| | 10.0 | | 50 | | | 9.8 - 11.0' No recovery | | |
| | | | 19 | | | | | |
| | 11.0 | SS2 | 1 | 2.0 | | 11.0 - 13.0' PT: Dark brown PEAT. End of boring at 13.0' bgs. | | |
| | | | 3 | | | | | |
| | 12.0 | | 3 | | | | | |
| | | | 7 | | | | | |
| | 13.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-01
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684386.21
**EAST:** 602706.88

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 2.0' FILL: Brown fine to medium sand, fine to medium concrete fragments, some silt and fine to medium gravel, loose | 0 | |
| | -1.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-PT-01_0002 collected from 1.5 - 2.0 ft bgs at 8:42 |
| | -2.0 | | | | | 2.0 - 3.5' FILL: Reddish brown silt and fine to medium sand, some fine to coarse concrete fragments and gravel, firm, moist at 3.3 ft below ground surface (bgs) | 0 | |
| | | | | | | | 0 | |
| | -3.0 | | | | | | 0 | Sample 124-PT-01_0204 collected from 3.0 - 3.5 ft bgs at 8:44 |
| | | | | | | 3.5 - 4.0' No Recovery | 0 | |
| | -4.0 | S-2 | NA | 2.5 | | 4.0 - 6.5' FILL: Brown fine to medium sand, some silt, wood from 4.5 - 4.75 ft bgs, trace gravel, wet | 0 | |
| | | | | | | | 0 | Sample 124-PT01_0406 collected from 4.5 - 5.0 ft bgs at 8:50 |
| | -5.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -6.0 | | | | | | 0 | Sample 124-PT01_0608 collected from 6.0 - 6.5 ft bgs at 8:55 |
| | | | | | | 6.5 - 8.0' No Recovery | 0 | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 10.0' FILL: Brown fine to medium sand, some silt, trace gravel, trace clay from 9.5 ft bgs, wet | 0 | |
| | | | | | | | 0 | |
| | -9.0 | | | | | | 0 | Sample 124-PT-01_0810 collected from 9.0 - 9.5 ft bgs at 9:03 |
| | | | | | | | 0 | |
| | -10.0 | | | | | 10.0 - 10.5' ML: Brown (7.5 YR 4.2) CLAYEY SILT, trace fine sand, soft, wet | 0 | Sample 124-PT-01_1012 collected from 10.0 - 10.5 ft bgs at 9:09 |
| | | | | | | 10.5 - 11.0' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some silt and clay, wet | 0 | |
| | -11.0 | | | | | | 0 | |
| | -12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-02
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684348.26
**EAST:** 602745.96

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 4.3' FILL: Brown to reddish brown fine to medium sand, some silt, trace fine to medium gravel, fine to medium concrete fragments from 0.0 - 2.0 ft below ground surface (bgs), trace coal and brick, trace clay from 3.5 ft bgs, moist at 3.75 ft bgs, wet at 4.0 ft bgs | 0 | |
| | -1.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-PT-02_0002 collected from 1.0 - 1.5 ft bgs at 9:48 |
| | -2.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | | | | | | | 0 | |
| | -3.0 | | | | | | 0 | Sample 124-PT-02_0204 collected from 3.5 - 4.0 ft bgs at 9:52 |
| | | | | | | | 0 | |
| | -4.0 | S-2 | NA | 3.0 | | 4.3 - 5.0' FILL: Light gray and dark brown fine to coarse sand and fine gravel (possible COPR), some wood, wet | 0 | |
| | | | | | | | 0 | Sample 124-PT-03_0406 collected from 4.5 - 5.0 ft bgs at 9:55 |
| | -5.0 | | | | | 5.0 - 7.0' FILL: Brown fine to medium sand, some silt, trace clay, wet | 0 | |
| | | | | | | | 0 | |
| | -6.0 | | | | | | 0 | Sample 124-PT-02_0608 collected from 6.5 - 7.0 ft bgs at 9:57 |
| | | | | | | | 0 | |
| | -7.0 | | | | | 7.0 - 8.0' No Recovery | 0 | |
| | | | | | | | | |
| | -8.0 | S-3 | NA | 3.25 | | 8.0 - 10.0' FILL: Brown fine to medium sand, some silt, trace clay, more clay from 8.0 - 8.25 ft bgs, wet | 0 | |
| | | | | | | | 0 | |
| | -9.0 | | | | | | 0 | Sample 124-PT-02_0810 collected from 9.0 - 9.5 ft bgs at 10:00 |
| | | | | | | | 0 | |
| | -10.0 | | | | | 10.0 - 10.8' ML: Brown (7.5 YR 3/2) CLAYEY SILT, trace fine sand, soft, wet | 0 | Sample 124-PT-02_1012 collected from 10.0 - 10.5 ft bgs at 10:03 |
| | | | | | | | 0 | |
| | -11.0 | | | | | 10.8 - 11.3' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some silt and clay, wet | 0 | |
| | | | | | | | | |
| | -12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-03
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684430.00
**EAST:** 602729.93

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.8' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.8 - 2.0' Void | | Cored through concrete |
| | 2.0 | S-1 | NA | 1.0 | | 2.0 - 3.0' FILL: Black fine to coarse sand, some fine to medium gravel and concrete fragments, trace coal, wet | 0 | |
| | | | | | | | 0 | Sample 124-PT-03_0204 collected from 2.5 - 3.0 ft bgs at 10:32 |
| | 3.0 | | | | | 3.0 - 4.0' No Recovery | 0 | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 4.5' FILL: Brown fine to coarse gravel, some fine to coarse sand, wet | 0 | |
| | | | | | | 4.5 - 5.0' FILL: Brown and light gray fine to medium sand, some silt (possible COPR), trace wood (green), wet | 0 | Sample 124-PT-03_0406 collected from 4.5 - 5.0 ft bgs at 10:35 |
| | 5.0 | | | | | | 0 | |
| | | | | | | 5.0 - 6.0' FILL: Brown fine to medium sand, trace silt, wet | 0 | |
| | 6.0 | | | | | 6.0 - 8.0' No Recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.6' FILL: Brown fine sand and silt, some clay, wet | 0 | |
| | | | | | | | 0 | Sample 124-PT-03_0810 collected from 8.5 - 9.0 ft bgs at 11:06 |
| | 9.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 10.0 | | | | | 10.6 - 11.0' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some clay and silt, decaying organic odors, wet | 0 | Sample 124-PT-03_1012 collected from 10.0 - 10.5 ft bgs at 11:12 |
| | | | | | | | 0 | |
| | 11.0 | | | | | | 0.1 | |
| | 12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-04
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684399.73
**EAST:** 602762.43

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.6' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.6 - 2.0' Void | | Cored through concrete |
| | 2.0 | S-1 | NA | 2.0 | | 2.0 - 3.8' FILL: Dark brown to black fine to medium sand, fine to medium gravel, trace silt, clinker material, coal, brick and concrete fragments, wet | 0 | |
| | 3.0 | | | | | | 0 | Sample 124-PT-04_0204 collected from 2.5 - 3.0 ft bgs at 12:05 |
| | | | | | | | 0 | |
| | 4.0 | S-2 | NA | 2.5 | | 3.8 - 4.0' FILL: Brown fine to medium sand and silt, trace fine gravel and concrete fragments, wet | 0 | |
| | | | | | | 4.0 - 5.3' FILL: Same as above, slight petroleum odors from 4.5 - 5.25 ft below ground surface (bgs), wet | 0.5 | |
| | 5.0 | | | | | | 0.7 | Sample 124-PT-04_0406 collected from 5.0 - 5.5 ft bgs at 12:10 |
| | | | | | | 5.3 - 5.5' FILL: Brown and gray fine to medium sand and gravel (possible COPR), wet | 0 | |
| | 6.0 | | | | | | 0 | Sample 124-PT-04_0608 collected from 6.0 - 6.5 ft bgs at 12:17 |
| | | | | | | 5.5 - 6.5' FILL: Brown fine to medium sand, trace silt, wet | 0 | |
| | 7.0 | | | | | 6.5 - 8.0' No Recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 10.8' FILL: Brown fine to medium sand, some silt, few clay lenses, wet | 0 | |
| | | | | | | | 0 | |
| | 9.0 | | | | | | 0 | Sample 124-PT-04_0810 collected from 9.0 - 9.5 ft bgs at 12:23 |
| | | | | | | | 0 | |
| | 10.0 | | | | | | 0 | |
| | | | | | | 10.8 - 11.2' ML: Brown (7.5 YR 3/2) CLAYEY SILT, trace fine sand, wet | 0 | Sample 124-PT-04_1012 collected from 10.5-11.0 ft bgs at 12:28 |
| | 11.0 | | | | | | 0 | |
| | | | | | | 11.2 - 11.5' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some clay and silt, wet | 0 | |
| | 12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-05
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684440.09
**EAST:** 602802.61

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.6' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.6 - 2.0' Void | | Cored through concrete |
| | 2.0 | S-1 | NA | 2.0 | | 2.0 - 3.3' FILL: Black to dark brown fine to coarse sand, some fine to medium gravel, trace silt, coal, clinker material, brick and concrete fragments, wet | 0 | |
| | 3.0 | | | | | | 0 | Sample 124-PT-05_0204 collected from 2.5 - 3.0 ft bgs at 13:27 |
| | | | | | | 3.3 - 3.8' FILL: Brown fine to medium sand, track silt and brick fragments, wet | 0 | |
| | 4.0 | S-2 | NA | 2.5 | | 3.8 - 4.0' No Recovery | 0 | |
| | | | | | | 4.0 - 4.3' FILL: Reddish brown fine to medium sand, some silt and brick fragments, wet | 0 | |
| | 5.0 | | | | | | 0 | Sample 124-PT-05_0406 collected from 5.5 - 6.0 ft bgs at 13:31 |
| | | | | | | 4.3 - 5.5' FILL: Brown fine to medium sand, some silt, trace gravel, coal, wood and brick fragments, wet | 0 | |
| | 6.0 | | | | | | 0 | Sample 124-PT-05_0608 collected from 6.0 - 6.5 ft bgs at 13:38 |
| | | | | | | 5.5 - 5.7' FILL: Gray and greenish gray fine to medium sand, silt and wood (possible COPR), wet | 0 | |
| | 7.0 | | | | | 5.7 - 6.5' FILL: Brown fine to medium sand, some silt, trace fine gravel, wet | | |
| | 8.0 | S-3 | NA | 3.5 | | 6.5 - 8.0' No Recovery | 0 | |
| | | | | | | | 0 | |
| | 9.0 | | | | | 8.0 - 9.3' FILL: Brown fine to medium sand, some silt and clay, trace fine gravel, wet, | 0 | |
| | | | | | | 9.3 - 9.5' SM: Black (2.5 Y 2.5/1) SILTY SAND, wet | 0 | Sample 124-PT-05_0810 collected from 9.5 - 10.0 ft bgs at 13:42 |
| | 10.0 | | | | | | 0 | |
| | | | | | | 9.5 - 10.0' ML: Dark olive gray (5 Y 3/2) SANDY SILT, some black mottling, wet | 0 | |
| | 11.0 | | | | | 10.0 - 11.0' PT: Black (2.5 Y 2.5/) PEAT, some clay, wet | 0 | |
| | | | | | | | 0 | |
| | 12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-06
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684470.22
**EAST:** 602770.11

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.4' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | | | | | | 0.4 - 2.0' Void | | Cored through concrete |
| | 1.0 | | | | | | | |
| | 2.0 | S-1 | NA | 2.0 | | 2.0 - 3.8' FILL: Dark brown to black fine to medium sand, some fine to medium gravel, trace coal, brick fragments, clinker material and silt, wet | 0 | |
| | 3.0 | | | | | | 0 | Sample 124-PT-06_0204 collected from 2.5 - 3.0 ft bgs at 13:55 |
| | | | | | | | 0 | |
| | | | | | | 3.8 - 4.0' FILL: Brown fine to medium sand, trace silt, wet | 0 | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 6.0' FILL: Same as above, more silt, trace clay, trace green nodules from 4.5 - 5.0 ft below ground surface (bgs) (possible COPR), wet | 0 | |
| | | | | | | | 0 | Sample 124-PT-06_0406 collected from 4.5 - 5.0 ft bgs at 14:03 |
| | 5.0 | | | | | | 0 | |
| | | | | | | 6.0 - 6.5' FILL: Reddish brown to dark brown fine to medium sand, some silt and wood, some redoxomorphic mottling, wet | 0 | |
| | 6.0 | | | | | | 0 | Sample 124-PT-06_0608 collected from 6.0 - 6.5 ft bgs at 14:10 |
| | | | | | | 6.5 - 8.0' No Recovery | 0 | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 10.0' FILL: Brown fine to medium sand, some silt, trace clay, some gravel from 9.8 - 10.0 ft bgs, wet | 0 | |
| | | | | | | | 0 | |
| | 9.0 | | | | | | 0 | Sample 124-PT-06_0810 collected from 9.0 - 9.5 ft bgs at 14:13 |
| | | | | | | | 0 | |
| | 10.0 | | | | | | 0 | |
| | | | | | | 10.0 - 11.0' FILL: Pale yellow silt, clay and fine sand (possible COPR), wet | 0 | Sample 124-PT-06_1012 collected from 10.5 - 11.0 ft bgs at 14:17 |
| | 11.0 | | | | | 11.0 - 11.5' PT: Black (2.5 Y 2.5/1) PEAT, some clay and silt, wet | 0 | |
| | | | | | | | 0 | |
| | 12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-07
**DATE BEGAN:** 3-12-08
**DATE FINISHED:** 3-12-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684533.50
**EAST:** 602838.48

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 1.2' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 1.2 - 2.0' Void | | Cored through concrete |
| | 2.0 | S-1 | NA | 0.75 | | 2.0 - 2.8' FILL: Black to brown fine to medium sand, some silt and fine gravel, wet | 0<br>0 | Sample 124-PT-07_0204 collected from 2.0 - 2.5 ft bgs at 14:35 |
| | 3.0 | | | | | 2.8 - 4.0' No Recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 6.5' FILL: Reddish brown fine to medium sand, some silt and clay, pale yellow from 6.3 - 6.5 ft below ground surface (bgs) (possible COPR), wet | 0<br>0<br>0<br>0<br>0<br>0 | Sample 124-PT-07_0406 collected from 4.5 - 5.0 ft bgs at 14:42<br>Sample 124-PT-07_0608 collected from 6.0 - 6.5 ft bgs at 14:46 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' No Recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.0' FILL: Pale yellow fine to medium sand, some silt and clay (possible COPR), wet | 0<br>0 | Sample 124-PT-07_0810 collected from 8.5 - 9.0 ft bgs at 14:51 |
| | 9.0 | | | | | 9.0 - 10.8' FILL: Brown to dark brown fine to medium sand, some silt and fine gravel, wet | 0<br>0<br>0<br>0 | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.8 - 11.5' FILL: Pale yellow fine to medium sand and silt (possible COPR), wet | 0<br>0 | Sample 124-PT-07_1012 collected from 11.0 - 11.5 ft bgs at 14:55 |
| | 12.0 | S-4 | NA | 2.0 | | 11.5 - 12.0' No Recovery<br>12.0 - 14.0' PT: Black (2.5 Y 2.5/1) PEAT, some clay and silt, wet | 0<br>0.2<br>0.3<br>0.1<br>0.4 | End of boring at 14.0 ft bgs |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-08
**DATE BEGAN:** 3-13-08
**DATE FINISHED:** 3-13-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684569.99
**EAST:** 602872.99

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.4' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.4 - 2.0' Void | | Hammered through concrete |
| | 2.0 | S-1 | NA | 2.0 | | 2.0 - 4.0' FILL: Black fine to medium sand, some fine gravel, trace silt, fine to medium brick fragments, clinker material and coal, wet | 0<br>0<br>0<br>0 | Sample 124-PT-08_0204 collected from 3.0 - 3.5 ft bgs at 13:47 |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 6.0' FILL: Reddish brown silty sand, some fine to coarse gravel, clay, brick fragments, clinker material and coal, wet | 0<br>0<br>0<br>0 | Sample 124-PT-08_0406 collected from 5.0 - 5.5 ft bgs at 13:51 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 8.0' No Recovery | 0 | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Dark brown fine to medium sand, trace clinker material and fine gravel, wet | 0<br>0 | |
| | 9.0 | | | | | 9.0 - 10.0' FILL: Dark brown silt and clay, trace sand and fine gravel, wet | 0<br>0 | Sample 124-PT-08_0810 collected from 9.0 - 9.5 ft bgs at 14:03 |
| | 10.0 | | | | | 10.0 - 12.0' FILL: Pale yellow silt, clay and fine sand (possible COPR), wet | 0<br>0<br>0<br>0 | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some clay and silt, wet | 0<br>0<br>0<br>0 | Sample 124-PT-08_1012 collected from 11.5 - 12.0 ft bgs at 14:07 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | End of boring at 14.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-09
**DATE BEGAN:** 3-13-08
**DATE FINISHED:** 3-13-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:** 684497.96
**EAST:** 602803.78

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.4' CONCRETE | | Boring elevation = 10.13' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.4 - 2.0' Void | | Hammered through concrete |
| | 2.0 | S-1 | NA | 1.75 | | 2.0 - 3.4' FILL: Black to dark brown fine to medium sand and gravel, some clinker material, trace silt and brick fragments, wet | 0<br>0 | Sample 124-PT-09_0204 collected from 2.5 - 3.0 ft bgs at 14:51 |
| | 3.0 | | | | | 3.4 - 3.8' FILL: Brown fine to medium sand, trace fine gravel and brick fragments, wet | 0<br>0 | |
| | 4.0 | S-2 | NA | 2.0 | | 3.8 - 4.0' No Recovery | 0 | |
| | 5.0 | | | | | 4.0 - 6.0' FILL: Brown fine to medium sand, some silt, trace clay, fine gravel and brick fragments, wet | 0<br>0<br>0 | Sample 124-PT-09_0406 collected from 5.0 - 5.5 ft bgs at 14:55 |
| | 6.0 | | | | | 6.0 - 8.0' No Recovery | 0 | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.5' FILL: Brown fine to medium sand, some silt, trace clay, fine gravel and brick fragments, wet | 0<br>0<br>0 | Sample 124-PT-09_0810 collected from 9.0 - 9.5 ft bgs at 15:13 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.5' FILL: Dark brown silt and fine sand, some clay, trace gravel, wet | 0<br>0 | |
| | 11.0 | | | | | 10.5 - 11.0' FILL: Pale yellow silt and fine sand, some clay, trace gravel (possible COPR), wet | 0<br>0 | Sample 124-PT-09_1012 collected from 10.5 - 11.0 ft bgs at 15:18 |
| | 12.0 | S-4 | NA | 2.0 | | 11.0 - 12.0' No Recovery | | |
| | 13.0 | | | | | 12.0 - 14.0' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some clay and silt, wet | 0.2<br>0.5<br>0.3<br>0.1 | |
| | 14.0 | | | | | | | End of boring at 14.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-10
**DATE BEGAN:** 3-14-08
**DATE FINISHED:** 3-14-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 1 ft bgs
**DRILLER:** Ed Blewett
**NORTH:** 684519.76
**EAST:** 602924.81

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.7' CONCRETE | | Boring elevation = 11.4' approximately 1.5' higher than surrounding grade |
| | 1.0 | S-1 | NA | 2.5 | | 0.7 - 1.0' Void | 0 | Hammered through concrete |
| | 2.0 | | | | | 1.0 - 3.0' FILL: Dark brown to black fine to medium sand and gravel, some silt, brick fragments and clinker material, wet | 0 | Sample 124-PT-10_0002 collected from 1.5 - 2.0 ft bgs at 7:51 |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Reddish brown fine to medium sand, some silt, fine gravel, brick fragments, trace coal, wet | 0 | Sample 124-PT-10_0204 collected from 3.0 - 3.5 ft bgs at 7:58 |
| | 4.0 | S-2 | NA | 2.0 | | 3.5 - 4.0' No Recovery | 0 | |
| | 5.0 | | | | | 4.0 - 6.0' FILL: Same as above, trace fine to medium gravel, brick fragments and coal, wet | 0 | Sample 124-PT-10_0406 collected from 5.0 - 5.5 ft bgs at 8:03 |
| | 6.0 | | | | | 6.0 - 8.0' No Recovery | 0 | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 10.0' FILL: Reddish brown silty sand, some clay, wet | 0 | |
| | 9.0 | | | | | | 0 | Sample 124-PT-10_0810 collected from 9.0 - 9.5 ft bgs at 8:11 |
| | 10.0 | | | | | 10.0 - 10.5' FILL: Reddish brown to brown to black, and yellowish brown fine to medium sand and silt (possible COPR), wet | 0 | |
| | 11.0 | | | | | 10.5 - 12.0' FILL: Pale yellow silt and clay, trace sand (possible COPR), wet | 0 | |
| | 12.0 | S-4 | NA | 4.0 | | | 0 | Sample 124-PT-10_1012 collected from 11.5 - 12.0 ft bgs at 8:14 |
| | 13.0 | | | | | 12.0 - 14.0' FILL: Same as above, Pale yellow silt and clay, trace sand (possible COPR), wet | 0 | |
| | 14.0 | | | | | | 0 | Sample 124-PT-10_1214 collected from 13.5 - 14.0 ft bgs at 8:20 |
| | 15.0 | | | | | 14.0 - 16.0' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some clay, wet | 0 | |
| | 16.0 | | | | | | 0 | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-11
**DATE BEGAN:** 3-14-08
**DATE FINISHED:** 3-14-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 1 ft bgs
**DRILLER:** Ed Blewett
**NORTH:** 684483.65
**EAST:** 602890.33

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' CONCRETE | | Boring elevation = 11.4' approximately 1.5' higher than surrounding grade |
| | 1.0 | S-1 | NA | 2.0 | | 0.5 - 1.0' Void | 0 | Hammered through concrete |
| | 2.0 | | | | | 1.0 - 3.0' FILL: Reddish brown and black fine to medium sand, some fine to medium gravel and brick fragments, some silt, trace clinker material and coal, wet | 0 | Sample 124-PT-11_0002 collected from 1.5 - 2.0 ft bgs at 8:46 |
| | 3.0 | | | | | 3.0 - 4.0' No Recovery | 0 | Sample 124-PT-11_0204 collected from 2.5 - 3.0 ft bgs at 8:51 |
| | 4.0 | S-2 | NA | 2.7 | | 4.0 - 6.5' FILL: Reddish brown silty sand, some clay and fine to medium brick fragments, trace coal, wet | 0 | |
| | 5.0 | | | | | | 0 | Sample 124-PT-11_0406 collected from 5.0 - 5.5 ft bgs at 8:57 |
| | 6.0 | | | | | 6.5 - 6.7' FILL: Fine to coarse gravel, wet | 0 | Sample 124-PT-11_0608 collected from 6.0 - 6.5 ft bgs at 9:02 |
| | 7.0 | | | | | 6.7 - 8.0' No Recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 9.3' FILL: Pale yellow with brown to black mottling fine to medium sand, some silt and clay (possible COPR), wet | 0 | Sample 124-PT-11_0810 collected from 8.5 - 9.0 ft bgs at 9:05 |
| | 9.0 | | | | | | 0 | |
| | 10.0 | | | | | 9.3 - 12.0' FILL: Brown silty sand, trace fine gravel and brick fragments, trace clay from 11.5 - 12.0 ft below ground surface (bgs), wet | 0 | |
| | 11.0 | | | | | | 0 | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' PT: Very dark grayish brown (2.5 Y 3/2) PEAT, some clay, wet | 0 | Sample 124-PT-11_1012 collected from 11.5 - 12.0 ft bgs at 9:11 |
| | 13.0 | | | | | | 1.1 | |
| | 14.0 | | | | | | 0.7 | |
| | | | | | | | 0.4 | |
| | | | | | | | 0.5 | End of boring at 14.0' bgs |

PREPARED BY: FP
CHECKED BY: QA/QC

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-12
**DATE BEGAN:** 3-14-08
**DATE FINISHED:** 3-14-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Ed Blewett
**NORTH:** 684447.67
**EAST:** 602855.86

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.7' CONCRETE | | Boring elevation = 11.4' approximately 1.5' higher than surrounding grade Hammered through concrete |
| | 1.0 | | | | | 0.7 - 2.0' Void | | |
| | 2.0 | S-1 | NA | 1.25 | | 2.0 - 3.3' FILL: Dark brown to black fine to medium sand, some fine to medium gravel, silt, brick fragments and clinker material, wet | 0 | |
| | 3.0 | | | | | | 0 | Sample 124-PT-12_0204 collected from 2.5 - 3.0 ft bgs at 9:35 |
| | | | | | | | 0 | |
| | 4.0 | | | | | 3.3 - 4.0' No Recovery | | |
| | | S-2 | NA | 2.5 | | 4.0 - 6.5' FILL: Reddish brown silty sand, some fine to medium gravel and brick fragments, wet | 0 | |
| | 5.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-PT-12_0406 collected from 5.0 - 5.5 ft bgs at 9:40 |
| | 6.0 | | | | | | 0 | Sample 124-PT-12_0608 collected from 6.0 - 6.5 ft bgs at 9:44 |
| | | | | | | | 0 | |
| | 7.0 | | | | | 6.5 - 8.0' No Recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Greenish yellow to brown silt and clay, some sand (possible COPR), wet | 0 | |
| | | | | | | | 0 | Sample 124-PT-12_0810 collected from 8.5 - 9.0 ft bgs at 9:49 |
| | 9.0 | | | | | 9.0 - 12.0' FILL: Brown silty sand, trace fine gravel, some clay from 11.25 - 12.0 ft below ground surface (bgs), wet | 0 | |
| | | | | | | | 0 | |
| | 10.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 11.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-PT-12_1012 collected from 11.5 - 12.0 ft bgs at 9:53 |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 14.0' FILL: Light brown to greenish yellow silt and clay, trace sand (possible COPR), wet | 0.5 | |
| | | | | | | | 0.2 | |
| | 13.0 | | | | | | 0 | |
| | | | | | | | 0 | Sampel 124-PT-12_1214 collected from 13.5 - 14.0 ft bgs at 10:03 |
| | 14.0 | | | | | 14.0 - 16.0' PT: Very dary grayish brown (2.5 Y 3/2) PEAT, some clay, wet | 0 | |
| | | | | | | | 0 | |
| | 15.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 16.0 | | | | | | | End of boring at 16.0' bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-13
**DATE BEGAN:** 3-14-08
**DATE FINISHED:** 3-14-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Ed Blewett
**NORTH:** 684410.01
**EAST:** 602835.64

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' CONCRETE | | Boring elevation = 11.5' approximately 1.5' higher than surrounding grade |
| | 1.0 | | | | | 0.5 - 2.0' Void | | Hammered through concrete |
| | 2.0 | S-1 | NA | 2.0 | | 2.0 - 2.3' FILL: Pieces of concrete, wet | 0 | |
| | 3.0 | | | | | 2.3 - 4.0' FILL: Black to dark browwn fine to medium sand, some fine gravel, clinker material, coal, trace silt, wet | 0<br>0<br>0 | Sample 124-PT-13_0204 collected from 2.5 - 3.0 ft bgs at 10:50 |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 6.0' FILL: Brown to reddish brown silty sand, some fine to medium gravel, brick fragments, clinker material, trace coal, wet | 0<br>0<br>0<br>0 | Sample 124-PT-13_0406 collected from 5.0 - 5.5 ft bgs at 10:55 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Brick fragments, wet | 0 | |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Reddish brown silty sand, some fine to medium gravel and brick fragments, trace clay, greenish yellow from 7.9 - 8.0 ft below ground surface (possible COPR), wet | 0<br>0<br>0 | Sample 124-PT-13_0608 collected from 7.0 - 7.5 ft bgs at 10:59 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 8.2' FILL: Greenish yellow silt and clay (possible COPR), wet | 0<br>0 | Sample 124-PT-13_0810 collected from 8.0 - 8.5 ft bgs at 11:07 |
| | 9.0 | | | | | 8.2 - 10.0' FILL: Brown fine to medium sand, some silt and clay from 9.4 ft bgs, trace fine gravel, wet | 0<br>0<br>0 | |
| | 10.0 | | | | | 10.0 - 12.0' PT: Very dary grayish brown (2.5 Y 3/2) PEAT, some clay, wet | 0.2<br>0.3<br>0.3<br>0.2 | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050165
**BORING ID:** 124-PT-14
**DATE BEGAN:** 3-14-08
**DATE FINISHED:** 3-14-08
**INSPECTOR:** J. Bacchus/F. Petrino
**DRILLING CO:** B&B Drilling Co.
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4' Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Ed Blewett
**NORTH:** 684371.83
**EAST:** 602797.43

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' CONCRETE | | Boring elevation = 11.5' approximately 1.5' higher than surrounding grade Hammered through concrete |
| | 1.0 | | | | | 0.5 - 2.0' Void | | |
| | 2.0 | S-1 | NA | 1.5 | | 2.0 - 3.5' FILL: Reddish brown to black fine to medium sand, some fine to medium gravel, concrete pieces, trace brick fragments and clinker material, wet | 0 | |
| | 3.0 | | | | | | 0 | Sample 124-PT-14_0204 collected from 2.5 - 3.0 ft bgs at 11:19 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' No Recovery | 0 | |
| | 5.0 | | | | | 4.0 - 6.0' FILL: Brown to reddish brown fine to medium sand, some fine to medium gravel, brick fragments, concrete pieces, trace silt and coal, wet | 0 | Sample 124-PT-14_0406 collected from 5.0 - 5.5 ft bgs at 11:24 |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Brown fine to medium sand, some silt, grayish brown clay and wood from 6.5 - 6.7 ft below ground surface (bgs) (possible COPR), wet | 0 | |
| | 7.0 | | | | | | 0 | Sample 124-PT-14_0608 collected from 6.5 - 7.0 ft bgs at 11:28 |
| | 8.0 | S-3 | NA | 4.0 | | 7.0 - 8.0' No Recovery | 0 | |
| | 9.0 | | | | | 8.0 - 12.0' FILL: Brown fine to coarse sand, trace silt, trace clay from 8.75 - 9.5 ft bgs, wet | 0 | Sample 124-PT-14_0810 collected from 9.0 - 9.5 ft bgs at 11:37 |
| | 10.0 | | | | | | 0 | |
| | 11.0 | | | | | | 0 | |
| | 12.0 | S-4 | NA | 4.0 | | | 0 | Sample 124-PT-14_1012 collected from 11.5 - 12.0 ft bgs at 11:41 |
| | 13.0 | | | | | 12.0 - 13.0' FILL: Brown fine to medium sand, some clay and silt, wet | 0 | Sample 124-PT-14_1214 collected from 12.5 - 13.0 ft bgs at 11:49 |
| | 14.0 | | | | | 13.0 - 16.0' PT: Very dary grayish brown (2.5 Y 3/2) PEAT, some clay, wet | 0 | |
| | 15.0 | | | | | | 0 | |
| | 16.0 | | | | | | 0 | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-PT-25

**DATE BEGAN:** 4/17/08
**DATE FINISHED:** 4/17/08
**INSPECTOR:** M. Daly / F. Petrino

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 14.5 ft bgs
**GW DEPTH:** 4.0 ft bgs

**DRILLER:** Ed Shaming
**NORTH:** 684402.53
**EAST:** 602691.15

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 1.0' FILL: Dark brown to gray fine to coarse sand, fine to coarse gravel, some silt, trace pieces of concrete | 1.8 | |
| | | | | | | | 0 | |
| | -1.0 | | | | | 1.0 - 2.3' FILL: Reddish brown fine to coarse sand fine to coarse sand, some silt, some fine gravel, moist | 0 | Sample 124-PT-25_0002 collected at 10:52 from 1.0 - 1.5 ft bgs |
| | | | | | | | 0 | |
| | -2.0 | | | | | | 0 | |
| | | | | | | 2.3 - 2.5' FILL: Pieces of concrete | | |
| | | | | | | 2.5 - 3.3' FILL: Brown fine to coarse sand, some silt, some fine gravel, moist, some mottling | 2.1 | Sample 124-PT-25_0204 collected at 10:55 from 2.5 - 3.0 ft bgs |
| | -3.0 | | | | | | 0.2 | |
| | | | | | | 3.3 - 4.0' No Recovery | | |
| | -4.0 | S-2 | NA | 2.75 | | 4.0 - 4.5' FILL: Brown fine to coarse sand, some silt, some fine gravel, wet | 0 | Mothball-like odors |
| | | | | | | 4.5 - 4.8' FILL: Possible bentonite or grout, wet | 0 | Sample 124-PT-25_0406 collected at 11:00 from 4.0 - 4.5 ft bgs |
| | -5.0 | | | | | 4.8 - 5.5' SW: Dark Brown (7.5YR 3/2) fine to coarse sand, some silt, horizontal bedding planes, trace shell fragments, wet | 0 | |
| | | | | | | | 0 | |
| | | | | | | 5.5 - 6.0' CL: Dark brown (7.5YR 3/2) clay, very plastic, wet | | |
| | -6.0 | | | | | | 0 | Sample 124-PT-25_0608 collected at 11:02 from 6.0 - 6.5 ft bgs |
| | | | | | | 6.0 - 6.8' ML: Dark brown (7.5YR 3/2) silty fine sand, wet | | |
| | | | | | | | 0 | |
| | -7.0 | | | | | 6.8 - 8.0' No Recovery | | |
| | -8.0 | | | | | | | |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-PT-25
**DATE BEGAN:** 4/17/08
**DATE FINISHED:** 4/17/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 14.5 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684402.53
**EAST:** 602691.15

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -8.0 | S-3 | NA | 1.0 | | 8.0 - 9.0' SW: Dark brown (7.5YR 3/2) fine to medium sand, some silt, one large piece of gravel, wet | 0<br>0 | Sample 124-PT-25_0810 collected at 11:24 from 8.5 - 9.0 ft bgs |
| | -9.0 | | | | | 9.0 - 12.0' No Recovery | 1.2 | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | NA | 2.5 | | 12.0 - 13.0' ML: Dark brown (7.5YR 3/2) fine to medium sand and silt, organic material, wet | 0<br>0 | Sample 124-PT-25_1214 collected at 11:29 from 12.5 - 13.0 ft bgs |
| | -13.0 | | | | | 13.0 - 14.5' PT: Greenish black (GLEY1 2.5/10Y) silt and clay, organic material, wet | 0 | |
| | -14.0 | | | | | | 0<br>0 | |
| | -15.0 | | | | | | 0 | End of boring at 14.5 ft bgs |
| | -16.0 | | | | | | | |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 124-SB-011 | **SITE ID:** 124

**DATE BEGAN:** 09/07/06 | **DATE FINISHED:** 09/07/06 | **INSPECTOR:** TG/JB

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 14 ft bgs | **GW DEPTH:** 6.5 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT | | 0 | |
| | -1.0 | | | | | FILL: Dark brown f-m sand, some silt and f-m gravel, trace brick, coal and glass | | | 124-SB-011_014 collected from 1-1.5 ft bgs @ 11:15 |
| | -2.0 | | | | | FILL: Concrete | | | |
| | -3.0 | | | | | FILL: Gray/brown f-c sand, f-m gravel, trace silt, some brick, concrete, ceramic shards, slight greenish brown mottling from 3.5 ft bgs (suspected COPR) | | | 124-SB-011_015 collected from 3.5-4 ft bgs @ 11:19 |
| | -4.0 | S-2 | N/A | 4 | | | | 0 | |
| -5.0 | -5.0 | | | | | FILL: Grayish brown with slight green tint, f-c sand, f-m gravel and brick | | | 124-SB-011_016 collected from 4.5-5 ft bgs @ 11:23 |
| | -6.0 | | | | | FILL: Gray f-c sand, f-m gravel, f-m concrete, trace silt, moist | | | 124-SB-011_017 collected from 6-6.5 ft bgs @ 11:30 |
| | -7.0 | | | | | FILL: Gray/white/brown f-c sand and clay with some green suspected COPR | | | |
| | -8.0 | S-3 | N/A | 3.5 | | FILL: Dark brown f-c sand, some silt, trace clay, wet | | 0 | 124-SB-011_018 collected from 7.5-8 ft bgs @ 11:35 |
| | -9.0 | | | | | FILL: Brown f-c sand, wet | | | 124-SB-011_019 collected from 8.5-9 ft bgs @ 11:42 |
| -10.0 | -10.0 | | | | | FILL: Brown clayey sand with layer of f-m sand from 11.5-11.75 ft bgs, wet | | | |
| | -11.0 | | | | | | | | |
| | -12.0 | S-4 | N/A | 2 | | FILL: Brown f-m sand and clay, more clay from 12.5 ft bgs | | 0 | 124-SB-011_020 collected from 11.5-12 ft bgs @ 11:43 |
| | -13.0 | | | | | PT: Peat | | | 124-SB-011_021 collected from 12.5-13 ft bgs @ 11:45 |
| | -14.0 | | | | | End boring @ 14 ft bgs | | | |
| -15.0 | -15.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-011A
**DATE BEGAN:** 7/8/2008
**DATE FINISHED:** 7/8/2008
**INSPECTOR:** E. Jackson
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | Collect sample from 1.0-1.5' bgs @ 13:20 |
| | -1.0 | | | | | 0.5 - 1.0' FILL: Dark brown silt and coarse sand | | |
| | -2.0 | | | | | 1.0 - 2.0' FILL: Yellow brown/light brown silt and clay, some fine gravel, bright green mottling, predominantly in gravel from 1-1.25' bgs (COPR); moist | | Collect sample from 2.5-3.0 @ 13:24 |
| | -3.0 | | | | | 2.0 - 2.3' FILL: Concrete | | |
| | -4.0 | 2 | NA | 3.0 | | 2.3 - 3.5' FILL: Light grey/brown medium to coarse sand, trace silt, some fine-medium angular gravel, very firm, moist | 0 | Collect sample from 4.5-5.0' bgs @ 13:28 |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -6.0 | | | | | 4.0 - 4.5' FILL: Light brown silty sand, some coarse angular gravel, loose, saturated | | Collect sample from 6.0-6.5' bgs @ 13:30 |
| | -7.0 | | | | | 4.5 - 5.3' FILL: Brown silty sand, trace angular gravel; wet | | |
| | -8.0 | 3 | NA | 0 | | 5.3 - 6.5' FILL: Light/yellow brown silty clay, some sand, COPR @ 6-6.5' bgs, saturated | 0 | |
| | -9.0 | | | | | 6.5 - 7.0' FILL: Brown silt and fine sand, firm, wet | | |
| | -10.0 | | | | | 7.0 - 12.0' No Recovery | | |
| | -11.0 | | | | | | | |
| | -12.0 | 4 | NA | 2.0 | | 12.0 - 14.0' PT: Peat; End of boring at 14' bgs | 0 | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 124-SB-012 | **SITE ID:** 124

**DATE BEGAN:** 09/07/06 | **DATE FINISHED:** 09/07/06 | **INSPECTOR:** TG/JB

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 16 ft bgs | **GW DEPTH:** 6.5 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT | | 0 | |
| | -1.0 | | | | | FILL: Dark brown f-c sand, some f-m gravel and silt, brick concrete, coal, black plastic @ 4.75 ft bgs | | | 124-SB-012_008 collected from 1-1.5 ft bgs @ 10:13 |
| | -2.0 | | | | | | | | |
| | -3.0 | | | | | | | | 124-SB-012_009 collected from 2.5-3 ft bgs @ 10:18 |
| | -4.0 | S-2 | N/A | 2.5 | | | | 0 | 124-SB-012_010 collected from 4.5-5 ft bgs @ 10:20 |
| -5.0 | -5.0 | | | | | FILL: Brown f-m sand, wet at 6.5 ft bgs | | | |
| | -6.0 | | | | | | | | 124-SB-012_011 collected from 6-6.5 ft bgs @ 10:25 |
| | -7.0 | | | | | | | | |
| | -8.0 | S-3 | N/A | 4 | | FILL: Brown f-m sand, wet | | 0 | |
| | -9.0 | | | | | | | | 124-SB-012_012 collected from 9-9.5 ft bgs @ 10:30 |
| -10.0 | -10.0 | | | | | FILL: Brown clayey sand | | | |
| | -11.0 | | | | | FILL: Brown clayey sand and gravel | | | |
| | -12.0 | S-4 | N/A | 3 | | FILL: Very light brown clayey sand | | 0 | 124-SB-012_013 collected from 11.5-12 ft bgs @ 10:32 |
| | -13.0 | | | | | FILL: Brown/dark grayish brown f-m sand | | | |
| | -14.0 | | | | | PT: Peat | | | |
| -15.0 | -15.0 | | | | | | | | |
| | -16.0 | | | | | End boring @ 16 ft bgs | | | |
| | -17.0 | | | | | | | | |

MACTEC

**SITE INFO:**

**DATE BEGAN:** 10/26/10

**DRILLING CO:** B and B

**SAMPLING TOOL:**

**DRILLER:** Gordon Blewitt

**PROJECT NO:** 3480050143

**DATE FINISHED:** 10/26/10

**DRILLING METHOD:** Direct Push

**COMPLETION DEPTH:** 15ft bgs

**NORTH:**

**BORING ID:** **124-SB-012R**

**INSPECTOR:** B. Senna

**DRILL EQUIP:** Geoprobe 6610 DT

**GW DEPTH:** 6.5 ft bgs

**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 4 | | 0.0 - 1.0' ASPHALT | 0 | |
| | 1.0 | | | | | 1.0 - 5.0' FILL: Dark brown f-c sand, some f-m gravel and silt, brick concrete, coal, black plastic @ 4.75 ft bgs | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | N/A | 2.5 | | | 0 | |
| | 5.0 | | | | | 5.0 - 6.5' FILL: Brown f-m sand, wet at 6.5 ft bgs | | |
| | 6.0 | | | | | | | |
| ▽ | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | N/A | 4 | | 8.0 - 9.5' FILL: Brown f-m sand, wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.5' FILL: Brown clayey sand | | |
| | 11.0 | | | | | 10.5 - 11.0' FILL: Brown clayey sand and gravel | | |
| | 12.0 | S-4 | N/A | 3 | | 11.0 - 11.5' FILL: Very light brown clayey sand | 0 | 124-SB-012_1214 collected from 12.0-12.5 ft bgs @ 11:30 |
| | 13.0 | | | | | 11.5 - 12.3' FILL: Brown/dark grayish brown f-m sand | | |
| | 14.0 | | | | | 12.3 - 15.0' PT: Peat; end of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY:

CHECKED BY:

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 124-SB-013 **SITE ID:** 124

**DATE BEGAN:** 09/07/06 **DATE FINISHED:** 09/07/06 **INSPECTOR:** TG/JB

**DRILLING CO:** TPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 14 ft bgs **GW DEPTH:** 6.5 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 2.5 | | FILL: Dark brown f-c sand, gravel, asphalt, concrete and roots | | 0 | |
| | -1.0 | | | | | | | | 124-SB-013_038 collected from 1-1.5 ft bgs @ 14:52 |
| | -2.0 | | | | | FILL: Concrete, light brown f-c sand and gravel | | | 124-SB-013_039 collected from 2-2.5 ft bgs @ 14:55 |
| | -3.0 | | | | | FILL: Dark brown f-c sand, gravel, some silt, brick and fibrous material | | | |
| | -4.0 | S-2 | N/A | 2.5 | | FILL: Dark brown f-c sand, gravel, some silt, brick, fibrous material, wood at 4.5 ft bgs | | 0 | 124-SB-013_040 collected from 4-4.5 ft bgs @ 15:00 |
| -5.0 | -5.0 | | | | | FILL: Dark grayish brown f-m sand, trace silt, wet @ 6.5 ft bgs | | | |
| | -6.0 | | | | | | | | 124-SB-013_041 collected from 6-6.5 ft bgs @ 15:03 |
| | -7.0 | | | | | | | | |
| | -8.0 | S-3 | N/A | 4 | | FILL: Dark grayish brown f-m sand, trace silt, wet | | 0 | |
| | -9.0 | | | | | FILL: Dark grayish brown sandy clay, wet | | | 124-SB-013_042 collected from 9-9.5 ft bgs @ 15:08 |
| -10.0 | -10.0 | | | | | | | | |
| | -11.0 | | | | | | | | |
| | -12.0 | S-4 | N/A | 2 | | | | 0 | 124-SB-013_043 collected from 11.5-12 ft bgs @ 15:10 |
| | -13.0 | | | | | PT: Peat | | | 124-SB-013_044 collected from 12.5-13 ft bgs @ 15:12 |
| | -14.0 | | | | | End boring @ 14 ft bgs | | | |
| -15.0 | -15.0 | | | | | | | | |

MACTEC

**SITE INFO:**

**DATE BEGAN:** 10/26/10

**DRILLING CO:** B and B

**SAMPLING TOOL:**

**DRILLER:** Gordon Blewitt

**PROJECT NO:** 3480050143

**DATE FINISHED:** 10/26/10

**DRILLING METHOD:** Direct Push

**COMPLETION DEPTH:** 15 ft bgs

**NORTH:**

**BORING ID:** **124-SB-013R**

**INSPECTOR:** B. Senna

**DRILL EQUIP:** Geoprobe 6610 DT

**GW DEPTH:** 6.5 ft bgs

**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 2.5 | | 0.0 - 1.0' FILL: Dark brown f-c sand, gravel, asphalt, concrete and roots | 0 | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Concrete, light brown f-c sand and gravel | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark brown f-c sand, gravel, some silt, brick and fibrous material | | |
| | 3.0 | | | | | 2.5 - 4.0' | | |
| | 4.0 | S-2 | N/A | 2.5 | | 4.0 - 4.5' FILL: Dark brown f-c sand, gravel, some silt, brick, fibrous material, wood at 4.5 ft bgs | 0 | |
| | 5.0 | | | | | 4.5 - 6.5' FILL: Dark grayish brown f-m sand, trace silt, wet @ 6.5 ft bgs | | |
| ▽ | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' | | |
| | 8.0 | S-3 | N/A | 4.0 | | 8.0 - 9.0' FILL: Dark grayish brown f-m sand, trace silt, wet | 0 | |
| | 9.0 | | | | | 9.0 - 13.0' FILL: Dark grayish brown sandy clay, wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | N/A | 3.0 | | | 0 | |
| | 13.0 | | | | | 13.0 - 14.0' PT: Peat | | |
| | 14.0 | | | | | 14.0 - 15.0' SM: Light brown fine to medium sand, organics; end boring @ 14' bgs. | | 124-SB-013_1416 collected from 14.0-14.5 ft bgs @ 11:10 |
| | 15.0 | | | | | | | |

PREPARED BY:

CHECKED BY:

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 124-SB-014 **SITE ID:** 124

**DATE BEGAN:** 09/07/06 **DATE FINISHED:** 09/07/06 **INSPECTOR:** TG/JB

**DRILLING CO:** TPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 6 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT | | 0 | |
| | -1.0 | | | | | FILL: Brick and brown silty sand | | | 124-SB-014_001 collected from 1-1.5 ft bgs @ 9:10 |
| | -2.0 | | | | | FILL: Black/dark brown f-c sand, gravel, silt, brick, asphalt, clinker, metal fragment @ 3.75 ft bgs, waxy material @ 3.8 ft bgs and wood from 4 ft bgs | | | |
| | -3.0 | | | | | | | | 124-SB-014_002 collected from 3-3.5 ft bgs @ 9:15 |
| | -4.0 | S-2 | N/A | 2.5 | | | | 0 | |
| -5.0 | -5.0 | | | | | | | | Odors from 5.5-6 ft bgs; no sheen or PID readings |
| | -6.0 | | | | | FILL: Brown f-m sand, trace silt, wet | | | 124-SB-014_003 collected from 5.5-6 ft bgs @ 9:20 |
| | -7.0 | | | | | | | | 124-SB-014_006 collected from 6-6.5 ft bgs @ 9:40 |
| | -8.0 | S-3 | N/A | 4 | | FILL: Brown f-m sand, trace silt, wet | | 0 | |
| | -9.0 | | | | | FILL: Brown silty sand, trace clay | | | |
| -10.0 | -10.0 | | | | | | | | 124-SB-014_004 collected from 9.5-10 ft bgs @ 9:35 |
| | -11.0 | | | | | FILL: Brown clayey sand | | | |
| | -12.0 | S-4 | N/A | 4 | | FILL: Reddish gray f-c sand | | 0 | 124-SB-014_005 collected from 11.5-12 ft bgs @ 9:37 |
| | -13.0 | | | | | FILL: Grayish brown f-m sand | | | |
| | -14.0 | | | | | FILL: Grayish brown sandy clay, soft | | | 124-SB-014_007 collected from 13-13.5 ft bgs @ 9:45 |
| -15.0 | -15.0 | | | | | PT: Peat | | | |
| | -16.0 | | | | | End boring @ 16 ft bgs | | | |
| | -17.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 124-SB-015 **SITE ID:** 124

**DATE BEGAN:** 09/07/06 **DATE FINISHED:** 09/07/06 **INSPECTOR:** TG/JB

**DRILLING CO:** TPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 8 ft bgs **GW DEPTH:** 7.5 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 3.5 | | FILL: Reddish brown silty sand, roots, brick and gravel | | 0 | 124-SB-015_045 collected from 1-1.5 ft bgs @ 15:25 |
| | -1.0 | | | | | | | | |
| | -2.0 | | | | | FILL: Concrete | | | |
| | -3.0 | | | | | FILL: Very dark brown f-c sand, gravel, silt, wood, brick and concrete | | | 124-SB-015_046 collected from 3-3.5 ft bgs @ 15:28 |
| | -4.0 | S-2 | N/A | 4 | | FILL: Dark brown silty sand, gravel and concrete | | 0 | 124-SB-015_047 collected from 4.5-5 ft bgs @ 15:30 |
| -5.0 | -5.0 | | | | | FILL: Brown f-m sand, trace silt, some clay from 7-7.5 ft bgs | | | |
| | -6.0 | | | | | | | | |
| | -7.0 | | | | | | | | 124-SB-015_048 collected from 7-7.5 ft bgs @ 15:33 |
| | -8.0 | | | | | PT: Peat, wet | | | |
| | -9.0 | | | | | End boring @ 8 ft bgs | | | |
| -10.0 | -10.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 124-SB-016 | **SITE ID:** 124

**DATE BEGAN:** 09/07/06 | **DATE FINISHED:** 09/07/06 | **INSPECTOR:** TG/JB

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 12 ft bgs | **GW DEPTH:** 7 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT | | 0 | |
| | -1.0 | | | | | FILL: Reddish brown silty sand and gravel, trace clay | | | 124-SB-016_049 collected from 1-1.5 ft bgs @ 15:51 |
| | -2.0 | | | | | FILL: Dark brown f-c sand, gravel, brick, concrete and metal fragments | | | |
| | -3.0 | | | | | | | | 124-SB-016_050 collected from 3-3.5 ft bgs @ 15:55 |
| | -4.0 | | | | | FILL: Concrete | | | |
| | | S-2 | N/A | 4 | | FILL: Brown f-c sand, trace silt and gravel, wet at 7 ft bgs | | 0 | |
| -5.0 | -5.0 | | | | | | | | 124-SB-016_051 collected from 4.5-5 ft bgs @ 16:00 |
| | -6.0 | | | | | | | | |
| | -7.0 | | | | | | | | 124-SB-016_052 collected from 6.5-7 ft bgs @ 16:03 |
| | -8.0 | | | | | FILL: Brown silt, trace clay, fine sand and organic material, wet | | | |
| | | S-3 | N/A | 4 | | FILL: Brown f-c sand | | 0 | |
| | -9.0 | | | | | | | | |
| -10.0 | -10.0 | | | | | | | | 124-SB-016_053 collected from 9.5-10 ft bgs @ 16:08 |
| | -11.0 | | | | | FILL: Brown silty sand, trace clay | | | |
| | -12.0 | | | | | FILL: Dark brown sandy clay | | | 124-SB-016_054 collected from 11.5-12 ft bgs @ 16:10 |
| | -13.0 | | | | | PT: Peat | | | |
| | | | | | | End boring @ 12 ft bgs | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 124-SB-017 | **SITE ID:** 124

**DATE BEGAN:** 09/07/06 | **DATE FINISHED:** 09/07/06 | **INSPECTOR:** TG/JB

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 12 ft bgs | **GW DEPTH:** 4 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 3 | | FILL: Dark brown silty sand, gravel, concrete, bricks and roots | | 0 | |
| | -1.0 | | | | | FILL: Reddish brown silty sand, brick and coal | | | 124-SB-017_030 collected from 1-1.5 ft bgs @ 12:45 |
| | -2.0 | | | | | FILL: Gray/brown/white f-c sand, f-m gravel and concrete | | | |
| | -3.0 | | | | | | | | 124-SB-017_031 collected from 2.5-3 ft bgs @ 12:51 |
| | -4.0 | S-2 | N/A | 4 | | FILL: Dark brown f-c sand, trace silt, wet | | 0 | 124-SB-017_032 collected from 4-4.5 ft bgs @ 12:56 |
| -5.0 | -5.0 | | | | | | | | Petroleum odors from 6-7 ft bgs |
| | -6.0 | | | | | FILL: Very dark brown silty clay, trace fine sand, wet | | 1.2 | |
| | -7.0 | | | | | FILL: Light grayish brown clay, silt, and sand, trace fine gravel, wet | | 3.8<br>0 | 124-SB-017_033, 124-SB-017MS_034, and 124-SB-017MSD_035 collected from 6.5-7 ft bgs @ 13:00 |
| | -8.0 | S-3 | N/A | 4 | | FILL: Dark brown f-m sand, wet | | 0 | |
| | -9.0 | | | | | | | | |
| -10.0 | -10.0 | | | | | | | | 124-SB-017_036 collected from 9.5-10 ft bgs @ 13:15 |
| | -11.0 | | | | | FILL: Dark brown sandy clay | | | |
| | -12.0 | | | | | PT: Peat | | | 124-SB-017_037 collected from 11.25-11.75 ft bgs @ 13:18 |
| | -13.0 | | | | | End boring @ 12 ft bgs | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 124-SB-018 **SITE ID:** 124

**DATE BEGAN:** 6/20/2005 **DATE FINISHED:** 6/20/2005 **INSPECTOR:** CH

**DRILLING CO:** EPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Ron Higgins **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | FILL: Topsoil; gravel, coal, ash, coarse | | 0 | 124-SB-018_005 collected from 1.5-2.0 ft bgs @ 0912<br>124-SB-018_006 collected from 1.5-2.0 ft bgs @ 0912<br>124-SB-018DUP_007 collected from 1.5-2.0 ft bgs @ 0913 |
| | -1.0 | | | | | | | | |
| | -2.0 | | | | | FILL: Green tint (suspected COPR), ash | | | |
| | -3.0 | | | | | | | | |
| | -4.0 | S-2 | | 4 | | FILL: Drak grey - green tint, ash; brick, concrete, gravel, fill | | 0 | 124-SB-018_008 collected from 3.5-4.0 ft bgs @ 0915 |
| -5.0 | -5.0 | | | | | FILL: Greenish - gray tint, ash | | | |
| | -6.0 | | | | | | | | |
| | -7.0 | | | | | | | | |
| | -8.0 | S-3 | | 4 | | | | 0 | 124-SB-018_009 collected from 7.5-8.0 ft bgs @ 0922 |
| | -9.0 | | | | | | | | |
| -10.0 | -10.0 | | | | | PT: Peat; some sandy clay | | | |
| | -11.0 | | | | | | | | |
| | -12.0 | | | | | End boring @ 12' | | 0 | 124-SB-018_010 collected from 11.5-12.0 ft bgs @ 0926 |
| | -13.0 | | | | | | | | |
| | -14.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 124-SB-019 **SITE ID:** 124

**DATE BEGAN:** 09/07/06 **DATE FINISHED:** 09/07/06 **INSPECTOR:** TG/JB

**DRILLING CO:** TPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 5400

**DRILLER:** Heath Kueller **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 14 ft bgs **GW DEPTH:** 7 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT | | 0 | |
| | -1.0 | | | | | FILL: Reddish brown f-c sand, gravel, silt, brick and wood | | | 124-SB-019_022 collected from 1-1.5 ft bgs @ 11:56 |
| | -2.0 | | | | | FILL: Gray/white f-c sand, gravel, silt, concrete and ash | | | |
| | -3.0 | | | | | FILL: Dark brown/black silty sand, gravel, wood and coal | | | 124-SB-019_023 collected from 3.5-4 ft bgs @ 12:01 |
| | -4.0 | S-2 | N/A | 3.5 | | | | 0 | Slight odors from 4-5.5 ft bgs |
| | | | | | | | | | 124-SB-019_024 collected from 4-4.5 ft bgs @ 12:10 |
| -5.0 | -5.0 | | | | | | | | 124-SB-019DP_025 collected from 4-4.5 ft bgs @ 12:10 |
| | -6.0 | | | | | FILL: Gray/white f-c sand, gravel, and concrete; bentonite from 6.25-6.5 ft | | | |
| | -7.0 | | | | | FILL: Brown f-m sand, wet at 7 ft bgs | | | 124-SB-019_026 collected from 7-7.5 ft bgs @ 12:20 |
| | -8.0 | S-3 | N/A | 4 | | FILL: Brown f-m sand, trace silt, wet | | 0 | |
| | -9.0 | | | | | | | | 124-SB-019_027 collected from 9.5-10 ft bgs @ 12:26 |
| -10.0 | -10.0 | | | | | | | | |
| | -11.0 | | | | | | | | 124-SB-019_028 collected from 11.5-12 ft bgs @ 12:28 |
| | -12.0 | S-4 | N/A | 2 | | | | 0 | |
| | -13.0 | | | | | PT: Peat | | | 124-SB-019_029 collected from 12.5-13 ft bgs @ 12:30 |
| | -14.0 | | | | | End boring @ 14 ft bgs | | | |
| -15.0 | -15.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-020
**DATE BEGAN:** 06/24/09
**DATE FINISHED:** 06/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 13.5 ft bgs
**GW DEPTH:** Not determined
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 2.0 | R-1 | N/A | 1.25 | | 1.5 - 1.8' FILL: Yellowish brown f-c sand, some fine gravel; wet | N/A | Field Map # 272 |
| | | | | | | 1.8 - 2.5' FILL: Brown/black f-c sand and fine clinker; wet | | Boring located in slab cutout; drilling started 1.5 ft below slab grade |
| | 3.0 | | | | | 2.5 - 2.8' FILL: Coarse gravel and brown f-m sand; wet | | No PID due to heavy rain |
| | 4.0 | | | | | 2.8 - 5.5' No recovery | | |
| | 5.0 | | | | | 5.5 - 6.0' FILL: Brown/white/yellow clayey COPR, some white nodules and dark brown fine sand; wet | | |
| | 6.0 | R-2 | N/A | 4.0 | | 6.0 - 7.3' FILL: Brown f-c sand, trace silt; wet | N/A | |
| | 7.0 | | | | | 7.3 - 8.0' FILL: Brown silty fine sand; wet | | |
| | 8.0 | | | | | 8.0 - 9.3' FILL: Brown sandy clay; wet | | |
| | 9.0 | | | | | | | |
| | 10.0 | R-3 | N/A | 4.0 | | 9.3 - 11.3' FILL: Brown f-c sand, trace silt, few clay lenses from 9.5'; wet | N/A | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | 11.3 - 12.5' FILL: Brown silty clay, trace sand; trace organic material from 12'; wet | | 124-SB-020-1012 collected from 11.5-12.0' bgs @ 13:45 |
| | 13.0 | | | | | 12.5 - 13.5' OL: Very dark grayish brown (10YR 3/2) silty clay, some organic material; end of boring at 13.5' | | |

PREPARED BY: JB
CHECKED BY: BS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-021
**DATE BEGAN:** 06/24/09
**DATE FINISHED:** 06/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 13.5 ft bgs
**GW DEPTH:** Not determined
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 2.0 | R-1 | N/A | 2.8 | | 1.5 - 1.8' FILL: Yellowish brown f-c sand, some fine gravel; wet | N/A | Field Map # 270 |
| | | | | | | 1.8 - 3.3' FILL: Dark brown f-c sand, some fine clinker and gravel; wet | | Boring located in slab cutout; drilling started 1.5 ft below slab grade |
| | 3.0 | | | | | | | No PID due to heavy rain |
| | | | | | | 3.3 - 4.0' FILL: Gravel, f-m; wet | | |
| | 4.0 | | | | | 4.0 - 4.3' FILL: Brown clayey sand, trace fine gravel; wet | | |
| | | | | | | 4.3 - 5.5' No recovery | | |
| | 5.0 | | | | | | | |
| | | R-2 | N/A | 3.0 | | 5.5 - 6.0' FILL: Brown clayey sand, trace fine gravel; white clayey COPR from 5.75-5.9'; wet | N/A | 124-SB-021-0406 collected from 5.5-6.0' bgs @ 14:15 |
| | 6.0 | | | | | | | |
| | | | | | | 6.0 - 8.5' FILL: Brown f-m sand, trace silt and clay; wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |
| | | | | | | 8.5 - 9.5' No recovery | | |
| | 9.0 | | | | | | | |
| | | R-3 | N/A | 4.0 | | 9.5 - 11.3' FILL: Brown f-m sand, trace silt and clay; wet | N/A | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | | | | | | 11.3 - 13.0' FILL: Brown silty clay, some fine sand lenses; wet | | 124-SB-021-1012 collected from 11.5-12.0' bgs @ 14:20 |
| | 12.0 | | | | | | | |
| | 13.0 | | | | | 13.0 - 13.4' OL: Very dark grayish brown (10YR 3/2) silty clay | | |
| | | | | | | 13.4 - 13.5' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 13.5' | | |

PREPARED BY: JB
CHECKED BY: BS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-022
**DATE BEGAN:** 06/24/09
**DATE FINISHED:** 06/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 13.5 ft bgs
**GW DEPTH:** Not determined
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 2.0 | R-1 | N/A | 3.5 | | 1.5 - 1.8' FILL: Yellowish brown f-c sand, some fine gravel; wet | N/A | Field Map # 269 |
| | 3.0 | | | | | 1.8 - 4.0' FILL: Dark brown f-c sand, some fine clinker and gravel, trace brick; wet | | Boring located in slab cutout; drilling started 1.5 ft below slab grade<br><br>No PID due to heavy rain |
| | 4.0 | | | | | 4.0 - 5.0' FILL: Reddish brown silty sand, some fine gravel; wet | | |
| | 5.0 | | | | | 5.0 - 5.5' No recovery | | |
| | 6.0 | R-2 | N/A | 2.0 | | 5.5 - 6.0' FILL: Reddish brown silty sand, some fine gravel; some white COPR from 5.8-6.0'; wet | N/A | 124-SB-022-0406 collected from 5.5-6.0' bgs @ 14:50 |
| | 7.0 | | | | | 6.0 - 7.5' FILL: Brown f-m sand, trace silt and clay; wet | | |
| | 8.0 | | | | | 7.5 - 9.5' No recovery | | |
| | 9.0 | | | | | | | |
| | 10.0 | R-3 | N/A | 4.0 | | 9.5 - 12.5' FILL: Brown silty sand, trace clay; wet | N/A | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | 124-SB-022-1012 collected from 11.5-12.0' bgs @ 14:55 |
| | 13.0 | | | | | 12.5 - 13.5' FILL: Brown silty clay, trace fine sand, trace organic material from 13.4'; wet; end of boring at 13.5' | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-023
**DATE BEGAN:** 06/24/09
**DATE FINISHED:** 06/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 13.5 ft bgs
**GW DEPTH:** Not determined
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 2.0 | R-1 | N/A | 3.25 | | 1.5 - 1.8' FILL: Yellowish brown f-c sand, some fine gravel; wet | N/A | Field Map # 271 |
| | 3.0 | | | | | 1.8 - 3.5' FILL: Dark brown/black f-c sand and fine clinker, trace gravel, brick, glass, and coal; wet | | Boring located in slab cutout; drilling started 1.5 ft below slab grade |
| | 4.0 | | | | | 3.5 - 4.8' FILL: Reddish brown silty sand, trace f-m gravel, brick, and coal; wet | | No PID due to heavy rain |
| | 5.0 | | | | | 4.8 - 5.5' No recovery | | |
| | 6.0 | R-2 | N/A | 2.5 | | 5.5 - 6.0' FILL: Reddish brown silty sand, trace f-m gravel, brick, and coal; trace white clayey COPR from 5.9-6.0'; wet | N/A | |
| | | | | | | 6.0 - 6.8' FILL: Brown f-c sand, trace silt; wet | | |
| | 7.0 | | | | | 6.8 - 8.0' FILL: Brown silty sand, trace clay; wet | | |
| | 8.0 | | | | | 8.0 - 9.5' No recovery | | |
| | 9.0 | R-3 | N/A | 4.0 | | 9.5 - 13.0' FILL: Brown silty sand, some clay from 11.25-12.0'; wet | N/A | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | 124-SB-023-1012 collected from 11.5-12.0' bgs @ 15:20 |
| | 13.0 | | | | | 13.0 - 13.5' FILL: Brown silty clay, trace fine sand; wet; end of boring at 13.5' | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-024

**DATE BEGAN:** 07/07/09 **DATE FINISHED:** 07/07/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 2 ft bgs

**DRILLER:** Gordon Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.8' CONCRETE | | Boring elevation = 10.12' approximately 0.5' higher than surrounding grade Field Map # 225 |
| | 1.0 | | | | | 0.8 - 2.0' VOID | | |
| | 2.0 | R-1 | N/A | 2.0 | | 2.0 - 4.0' FILL: Dark brown/brown silty sand, some f-m gravel, trace clinker and coal; wet | N/A | Driller cored through concrete slab<br>No PID due to rain |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 2.0 | | 4.0 - 5.0' FILL: Reddish brown clayey sand, some f-m gravel, trace wood and coal; wet | N/A | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Reddish brown sandy clay, some f-m gravel; trace brick, coal, glass; petroleum odors and sheen from 5.8'; wet | | |
| | 6.0 | | | | | 6.0 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.5' FILL: Yellow/green sandy clay (COPR), some organic material; wet | N/A | |
| | 9.0 | | | | | 8.5 - 11.0' FILL: Brown f-m sand, wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.9' FILL: Brown clayey silt, trace fine sand; wet | | |
| | 12.0 | R-4 | N/A | 3.2 | | 11.9 - 12.0' FILL: Gravel, f-m | N/A | |
| | 13.0 | | | | | 12.0 - 12.5' FILL: Green/white/brown/black clayey silt, some f-m sand and organic material, trace f-m gravel; wet | | 124-SB-024-1214 collected from 13.0-13.5' bgs @ 13:05; DUP @ 13:08 |
| | 14.0 | | | | | 12.5 - 15.2' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat | | |
| | 15.0 | | | | | | | EOB at 16 ft bgs |
| | 16.0 | | | | | 15.2 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: JB

CHECKED BY: BS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-025

**DATE BEGAN:** 07/07/09 **DATE FINISHED:** 07/07/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 1.5 ft bgs

**DRILLER:** Gordon Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.8' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.8 - 1.5' VOID | | |
| | 2.0 | R-1 | N/A | 2.0 | | 1.5 - 3.5' FILL: Dark brown f-m sand, some fine gravel and clinker, trace brick and coal; wet | N/A | Field Map # 226<br>Driller cored through concrete slab<br>No PID due to rain |
| | 3.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 2.3 | | 4.0 - 5.0' FILL: Dark brown f-m sand, some fine gravel and clinker, trace brick and coal; wet | N/A | |
| | 5.0 | | | | | 5.0 - 6.3' FILL: Reddish brown silty sand, trace fine gravel and brick; coarse gravel and yellow clayey COPR from 6.1'; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.3 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 10.0' FILL: Brown f-m sand; green clayey COPR, organic material, and medium gravel from 8.0-8.2'; wet | N/A | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.3' FILL: Brown sandy silt; v. stiff and dry from 11.0' | | |
| | 11.0 | | | | | 11.3 - 11.5' FILL: Grayish green clayey sand (COPR); wet | | |
| | 12.0 | R-4 | N/A | 3.5 | | 11.5 - 12.0' No recovery | N/A | |
| | 13.0 | | | | | 12.0 - 12.8' FILL: Yellow clayey COPR, trace fine sand; wet | | |
| | 14.0 | | | | | 12.8 - 13.0' OL: Very dark grayish brown (10YR 3/2) clayey silt, some organic material | | 124-SB-025-1214 collected from 13.5-14.0' bgs @ 14:00 |
| | 15.0 | | | | | 13.0 - 15.5' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat | | |
| | 16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | EOB at 16 ft bgs |

PREPARED BY: JB

CHECKED BY: BS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-026

**DATE BEGAN:** 07/08/09 **DATE FINISHED:** 07/08/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 4 ft bgs

**DRILLER:** Gordon Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.5 - 2.0' VOID | | |
| | 2.0 | R-1 | N/A | 2.0 | | 2.0 - 3.5' FILL: Dark brown f-m sand, some f-m gravel, trace clinker and brick; wet | 0.0 | Field Map # 227<br>Driller cored through concrete slab |
| | 3.0 | | | | | 3.5 - 4.0' FILL: Reddish brown/brown sandy silt, some fine gravel and coarse brick, trace coal; dry | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 6.4' FILL: Reddish brown/brown sandy silt, trace fine brick, f-m gravel, and coal; very firm, wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.4 - 6.5' FILL: Pale yellow/gray sandy clay (COPR); wet | | |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.2' FILL: Dark brown/green sandy silt (COPR), some organic material; wet | 0.0 | |
| | 9.0 | | | | | 8.2 - 9.5' FILL: Brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | 9.5 - 11.0' FILL: Dark brown silty fine sand grading to sandy silt, trace clay; soft, wet | | |
| | 11.0 | | | | | 11.0 - 12.2' FILL: Yellow clayey COPR, trace fine sand; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.2 - 12.5' FILL: Black clayey silt, some organic material and yellow clayey COPR | 0.0<br>0.0 | |
| | 13.0 | | | | | 12.5 - 16.0' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat; end of boring at 16' | 3.1 | 124-SB-026-1214 collected from 13.0-13.5' bgs @ 8:40 |
| | 14.0 | | | | | | 17.1<br>12.0 | |
| | 15.0 | | | | | | 8.9<br>10.5 | |
| | 16.0 | | | | | | 8.0<br>9.4 | EOB at 16 ft bgs |

PREPARED BY: JB

CHECKED BY: BS

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-027

**DATE BEGAN:** 07/08/09 **DATE FINISHED:** 07/08/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 4 ft bgs

**DRILLER:** Gordon Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' CONCRETE | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.5 - 2.0' VOID | | Field Map # 228 |
| | 2.0 | R-1 | N/A | 2.0 | | 2.0 - 3.5' FILL: Dark brown f-m sand, some f-m gravel, trace clinker and brick; wet | 0.0 | Driller cored through concrete slab |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.5 - 5.5' FILL: Reddish brown/brown sandy silt, some fine gravel, trace brick and coal; wet from 4.0' | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 8.0' FILL: Pale yellow/yellow/light brown clayey COPR; wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.3' FILL: Dark brownsandy silt; thin lens of green-stained organic material (COPR) at 8.2'; wet | 0.0 | |
| | 9.0 | | | | | 8.3 - 9.2' FILL: Brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | 9.2 - 10.5' FILL: Dark brown sandy silt, trace clay; very soft, wet | | |
| | 11.0 | | | | | 10.5 - 11.8' FILL: Yellow clayey COPR; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.8 - 12.0' FILL: Brown f-c sand; trace silt, fine gravel and organic material; wet | 0.0 | |
| | 13.0 | | | | | 12.0 - 12.5' OL: Very dark grayish brown (10YR 3/2) clayey silt, some organic material, trace f-m sand | 0.2<br>5.3 | 124-SB-027-1214 collected from 12.5-13.0' bgs @ 9:30 |
| | 14.0 | | | | | 12.5 - 16.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 16' | 7.4<br>6.9<br>12.7<br>14.0 | 124-SB-027-1416 collected from 14.0-14.5' bgs @ 9:40; HOLD |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | 11.5<br>4.4 | EOB at 16 ft bgs |

PREPARED BY: JB

CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-028

**DATE BEGAN:** 07/08/09 **DATE FINISHED:** 07/08/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 14 ft bgs **GW DEPTH:** 4 ft bgs

**DRILLER:** Gordon Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -2.0 | | | | | -2.0 - -1.5' CONCRETE | | Boring located on elevated portion of building slab, approx. 2 ft above slab grade. Driller cored through concrete slab |
| | -1.0 | | | | | -1.5 - 0.0' VOID | | |
| | 0.0 | R-1 | N/A | 2.0 | | 0.0 - 0.3' FILL: Brown silty sand, wet | 0.0 | Field Map # 229 |
| | 1.0 | | | | | 0.3 - 2.0' FILL: Very dark grayish brown fine sand, trace silt; firm, moist | | |
| | 2.0 | R-2 | N/A | 2.5 | | 2.0 - 4.5' FILL: Reddish brown sandy silt, some f-m gravel, trace concrete and brick; very stiff, wet from 4.0' | 0.0 | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | 4.5 - 6.0' No recovery | | |
| | 6.0 | R-3 | N/A | 3.5 | | 6.0 - 7.2' FILL: Yellow/green clayey COPR, wet | 0.0 | |
| | 7.0 | | | | | 7.2 - 8.0' FILL: Brown silty fine sand; dense | | |
| | 8.0 | | | | | 8.0 - 8.5' FILL: Brown f-m sand, wet | | |
| | 9.0 | | | | | 8.5 - 9.0' FILL: Brown silty fine sand, wet | | |
| | 10.0 | R-4 | N/A | 4.0 | | 9.0 - 9.5' FILL: Brown sandy silt, trace clay | 0.0 | |
| | 11.0 | | | | | 9.5 - 10.0' No recovery | | |
| | 12.0 | | | | | 10.0 - 11.8' FILL: Yellow clayey COPR, trace f-c sand and fine gravel; wet | | |
| | 13.0 | | | | | 11.8 - 12.5' OL: Very dark grayish brown (10YR 3/2) to dark olive brown (2.5Y 2/2) clayey silt, some organic material; soft, moist | 0.0<br>1.3<br>8.7 | 124-SB-028-1214 collected from 12.0-12.5' bgs @ 11:05 |
| | 14.0 | | | | | 12.5 - 14.0' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat; end of boring at 14' | 9.1<br>1.6 | |

PREPARED BY: JB

CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-029
**DATE BEGAN:** 07/08/09
**DATE FINISHED:** 07/08/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -2.0 | | | | | -2.0 - -1.5' CONCRETE | | Boring located on elevated portion of building slab, approx. 2 ft above slab grade. Driller cored through concrete slab |
| | -1.0 | | | | | -1.5 - 0.0' VOID | | |
| | 0.0 | R-1 | N/A | 2.0 | | 0.0 - 0.5' FILL: Brown clayey silt, trace fine sand and gravel; soft, wet | 0.0 | Field Map # 230 |
| | 1.0 | | | | | 0.5 - 2.2' FILL: Black/dark brown fine sand, some f-m gravel; trace silt, clinker, glass; moist, very firm | | |
| | 2.0 | R-2 | N/A | 3.5 | | 2.2 - 2.3' FILL: Concrete | 0.0 | |
| | 3.0 | | | | | 2.3 - 5.5' FILL: Reddish brown/brown sandy silt, some f-m gravel, trace clinker, coal, glass, and wood; wet from 3.5' | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.0' No recovery | | |
| | | R-3 | N/A | 4.0 | | 6.0 - 6.5' FILL: Reddish brown/brown sandy silt, some f-m gravel, trace clinker, coal, glass, and wood; wet | 0.0 | |
| | 7.0 | | | | | 6.5 - 7.5' FILL: Yellow clayey COPR, wet | | |
| | 8.0 | | | | | 7.5 - 9.0' FILL: Brown f-m sand, wet | | |
| | 9.0 | | | | | 9.0 - 10.0' FILL: Brown silty sand, wet | | |
| | 10.0 | R-4 | N/A | 4.0 | | 10.0 - 12.0' FILL: Yellow clayey COPR, wet | 0.0 | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | 12.0 - 12.5' OL: Black (2.5Y 2.5/1) clayey silt, some organic material | 0.0 | 124-SB-029-1214 collected from 12.0-12.5' bgs @ 13:35 |
| | 13.0 | | | | | 12.5 - 14.0' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat; end of boring at 14' | 4.0<br>7.8<br>12.7<br>1.0 | |
| | 14.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-030
**DATE BEGAN:** 08/03/09
**DATE FINISHED:** 08/03/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 236 |
| | 1.0 | | | | | 0.3 - 0.6' FILL: Dark brown f-c sand, some fine clinker and gravel | | Refusal at 2.5 ft bgs; moved 2 ft west |
| | 2.0 | | | | | 0.6 - 4.0' FILL: Reddish brown f-c sand and f-m gravel; trace silt, clinker and brick; yellow COPR from 1.5-2.6'; concrete from 2.2-3.0'; white COPR from 3.8' | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.5' FILL: Grayish brown f-m gravel, some f-c sand; trace ceramics, silt and brick; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.2' FILL: Light brown/white/yellow clayey COPR; v. soft, wet | | |
| | 7.0 | | | | | 6.2 - 8.0' FILL: Brown fine sand, trace silt; dense, wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.0' FILL: Grayish brown clayey sand and pale yellow COPR, trace f-m gravel; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.0' FILL: Yellow clayey COPR, trace grayish brown f-m sand and gravel; v. soft, wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 15.8' PT: Very dark brown (7.5YR 2.5/2) peat; moist | 0.0 | |
| | 13.0 | | | | | | | 124-SB-030-1214 collected from 13.0-13.5' bgs @ 8:55 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.8 - 16.0' SP: Dark gray (2.5Y 4/1) f-m sand; end of boring at 16' | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-031
**DATE BEGAN:** 08/03/09
**DATE FINISHED:** 08/03/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 15 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 240 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Dark brown f-c sand and fine clinker | | 124-SB-031-0002 collected from 1.0-1.5' bgs @ 9:10 |
| | 2.0 | | | | | 1.0 - 1.5' FILL: Reddish brown sandy silt, some f-m gravel | | |
| | 3.0 | | | | | 1.5 - 2.0' FILL: Dark brown/brown silty sand; trace f-m gravel, wood, brick and clinker | | |
| | 4.0 | R-2 | N/A | 4.0 | | 2.0 - 11.8' FILL: Yellowish brown/gray/pale yellow silty sand (COPR); compact, wet | 0.0 | 124-SB-031-0204 collected from 3.5-4.0' bgs @ 9:15 |
| | 5.0 | | | | | | | 124-SB-031-0406 collected from 4.5-5.0' bgs @ 9:20 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | 124-SB-031-0608 collected from 7.5-8.0' bgs @ 9:25 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-031-0810 collected from 9.5-10.0' bgs @ 9:30 |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 3.0 | | 11.8 - 12.0' FILL: Black clayey silt and wood | | 124-SB-031-1012 collected from 11.3-11.8' bgs @ 9:35 |
| | 13.0 | | | | | 12.0 - 15.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 15' | 0.0 | 124-SB-031-1214 collected from 12.5-13.0' bgs @ 9:45 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-032

**DATE BEGAN:** 08/03/09 **DATE FINISHED:** 08/03/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 15 ft bgs **GW DEPTH:** 2.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 244 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Dark brown f-c sand, some fine clinker and gravel, trace brick from 1.2-1.3' | | |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Brown/grayish brown silty sand with gray COPR mottling; wet from 2.5' | | |
| | 3.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 11.8' FILL: Grayish brown/pale yellow silty sand (COPR); wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | 11.8 - 12.0' FILL: Black clayey silt and wood | | |
| | | R-4 | N/A | 2.0 | | 12.0 - 14.0' PT: Very dark brown (7.5YR 2.5/2) peat | 0.0 | 124-SB-032-1214 collected from 12.5-13.0' bgs @ 10:40 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 15.0' No recovery; end of boring at 15' | | |
| | 15.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-033

**DATE BEGAN:** 08/03/09 **DATE FINISHED:** 08/03/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 1.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 250 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Dark brown f-c sand, some fine gravel, trace clinker | | |
| | 2.0 | | | | | 1.0 - 1.7' FILL: Black f-c sand and fine clinker, wet | | |
| | 3.0 | | | | | 1.7 - 3.5' FILL: White/gray/yellow silty sand (COPR), wet | | |
| | 4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | R-2 | N/A | 4.0 | | 4.0 - 10.0' FILL: Grayish brown/yellow silty sand (COPR); wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 10.5' FILL: Pale yellow clayey silt (COPR); soft, wet | | |
| | 11.0 | | | | | 10.5 - 10.7' FILL: Black clayey silt, some wood and fine gravel; wet | | 124-SB-033-1012 collected from 10.7-11.2' bgs @ 11.35 |
| | 12.0 | | | | | 10.7 - 11.0' OH: Black/dark olive brown (2.5Y 2.5/1 to 3/3) clayey silt, some organic material; soft, wet | | |
| | | | | | | 11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-034

**DATE BEGAN:** 08/03/09 **DATE FINISHED:** 08/03/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 243 |
| | | | | | | 0.2 - 0.6' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.6 - 3.0' FILL: Yellowish brown/brown/dark brown silt sand, some fine gravel, trace brick, clinker and coal, trace grey/white mottling (COPR) from 1.0-1.2', grey/green/reddish brown mottling (COPR) from 2.6'; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 11.0' FILL: Grayish brown/pale yellow silty sand (COPR); wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Pale yellow clayey silt (COPR); soft, wet | | 124-SB-034-1012 collected from 11.5-12.0' bgs @ 12:55 |
| | | | | | | 11.5 - 11.7' OL: Black (2.5Y 2.5/1) silt, trace fine sand and organic material; wet | | |
| | 12.0 | | | | | 11.7 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-034R
**DATE BEGAN:** 12/21/2010
**DATE FINISHED:** 12/21/2010
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | |
| | | | | | | 0.2 - 0.6' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.6 - 3.0' FILL: Yellowish brown/brown/dark brown silt sand, some fine gravel, trace brick, clinker and coal, trace grey/white mottling (COPR) from 1.0-1.2', grey/green/reddish brown mottling (COPR) from 2.6'; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 11.0' FILL: Grayish brown/pale yellow silty sand (COPR); wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 5.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Pale yellow clayey silt (COPR); soft, wet | | 124-SB-034R-1214 collected from 12.0-12.5' bgs |
| | | | | | | 11.5 - 11.7' OL: Black (2.5Y 2.5/1) silt, trace fine sand and organic material; wet | | |
| | 12.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: TG

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** **124-SB-034R**

**DATE BEGAN:** 12/21/2010 **DATE FINISHED:** 12/21/2010 **INSPECTOR:** Brian Senna

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | | | | 11.7 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; | | |
| | 13.0 | | | | | 12.0 - 13.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 13' | | |

PREPARED BY: BS

CHECKED BY: TG

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-035

**DATE BEGAN:** 08/03/09 **DATE FINISHED:** 08/03/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.4' ASPHALT | 0.0 | Field Map # 247 |
| | 1.0 | | | | | 0.4 - 0.6' FILL: Brown f-m sand, some fine gravel and clinker | | 124-SB-035-0002 collected from 1.0-1.5' bgs @ 13:15 |
| | 2.0 | | | | | 0.6 - 2.0' FILL: Brown silty sand, some f-c concrete; trace fine gravel, coal, and brick; wood from 1.6-1.8' | | 124-SB-035-0204 collected from 2.0-2.5' bgs @ 13:20 |
| | 3.0 | | | | | 2.0 - 2.5' FILL: Reddish brown f-m sand, some dark reddish brown mottling and nodules (COPR); wet | | |
| | | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.5' FILL: Brown f-c sand, some silt and f-m gravel; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 10.0' FILL: Grayish brown/pale yellow silty sand (COPR); light purple COPR from 5.5-5.6'; wet | | 124-SB-035-0406 collected from 5.5-6.0' bgs @ 13:25 |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | 124-SB-035-0608 collected from 7.5-8.0' bgs @ 13:30 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-035-0810 collected from 9.5-10.0' bgs @ 13:40 |
| | | | | | | 10.0 - 10.8' FILL: Pale yellow clayey silt (COPR); soft, wet | | |
| | 11.0 | | | | | 10.8 - 11.0' OH: Black (2.5Y 2.5/1) clayey silt, trace organic material; wet | | 124-SB-035-1012 collected from 11.5-12.0' bgs @ 13:45 |
| | 12.0 | | | | | 11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |

PREPARED BY: JB

CHECKED BY: FP

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-036

**DATE BEGAN:** 08/03/09 **DATE FINISHED:** 08/03/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 251 |
| | 1.0 | | | | | 0.5 - 0.7' FILL: Reddish brown f-m sand | | |
| | 2.0 | | | | | 0.7 - 4.0' FILL: Grayish brown silty sand and white/yellow/purple COPR, trace fine gravel, concrete from 1.6-1.8'; yellow crystalline COPR from 1.8-1.9'; wet from 2.0' | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 9.5' FILL: Grayish brown/pale yellow silty sand (COPR); wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.9' FILL: Pale yellow/light brown clayey silt (COPR); wet | | |
| | 11.0 | | | | | 10.9 - 11.0' FILL: Black silt and wood; wet | | |
| | 12.0 | | | | | 11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | 124-SB-036-1012 collected from 11.5-12.0' bgs @ 14:30 |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-037

**DATE BEGAN:** 08/04/09 **DATE FINISHED:** 08/04/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.1' ASPHALT | 0.0 | Field Map # 255 |
| | 1.0 | | | | | 0.1 - 1.0' FILL: Reddish brown silty sand, some f-m gravel | | 124-SB-037-0002 collected from 0.5-1.0' bgs @ 8:10 |
| | | | | | | 1.0 - 1.7' FILL: Gravel, f-m | | |
| | 2.0 | | | | | 1.7 - 3.0' FILL: Brown silty sand, trace fine gravel; white COPR mottling from 1.8-1.9'; yellow COPR and wet from 2.0' | | 124-SB-037-0204 collected from 2.5-3.0' bgs @ 8:15 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 8.0' FILL: Grayish brown/pale yellow silty sand (COPR), trace fine gravel; wet | 0.0 | 124-SB-037-0406 collected from 4.0-4.5' bgs @ 8:20 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 124-SB-037-0608 collected from 7.5-8.0' bgs @ 8:25 |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.8' FILL: Pale yellow clayey silt (COPR); wet | 0.0 | |
| | 9.0 | | | | | | | 124-SB-037-0810 collected from 9.0-9.5' bgs @ 8:30 |
| | 10.0 | | | | | 9.8 - 10.5' OH: Black (2.5Y 2.5/1) silt, trace clay; pale green seam of possible COPR at 10.3'; v. soft | | |
| | 11.0 | | | | | 10.5 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | 124-SB-037-1012 collected from 11.0-11.5' bgs @ 8:35 |
| | 12.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-038

**DATE BEGAN:** 08/04/09 **DATE FINISHED:** 08/04/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 1.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 254 |
| | | | | | | 0.2 - 0.5' FILL: Brown silty sand, some organic material | | |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Gravel, f-m | | 124-SB-038-0002 collected from 1.5-2.0' bgs @ 8:45 |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Dark brown f-c sand and fine clinker; trace brick, fine gravel and ceramics; wet from 1.5' | | 124-SB-038-0204 collected from 2.5-3.0' bgs @ 8:50 |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Grayish brown silty sand, trace f-m gravel; white COPR mottling; few nodules of dark reddish brown COPR; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 4.0' No recovery | 0.0 | 124-SB-038-0406 collected from 4.0-4.5' bgs @ 8:55 |
| | | | | | | 4.0 - 8.0' FILL: Grayish brown/pale yellow silty sand (COPR), trace fine gravel; wet | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.8' FILL: Grayish brown/pale yellow clayey silt (COPR); wet | 0.0 | 124-SB-038-0608 collected from 7.5-8.0' bgs @ 9:00 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.8 - 10.3' OH: Black/dark olive brown (2.5Y 2.5/1 to 3/3) clayey silt, wet | | 124-SB-038-0810 collected from 9.8-10.3' bgs @ 9:05 |
| | 11.0 | | | | | 10.3 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | 124-SB-038-1012 collected from 10.0-10.5' bgs @ 9:10 |
| | 12.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-039

**DATE BEGAN:** 08/04/09 **DATE FINISHED:** 08/04/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 232 |
| | 1.0 | | | | | 0.3 - 4.0' FILL: Reddish brown sandy silt; trace fine gravel, brick, coal, and concrete | | 124-SB-039-0002 collected from 0.5-1.0' bgs @ 9:55 |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | | 0.0 | 124-SB-039-0204 collected from 3.5-3.0' bgs @ 10:00 |
| | 5.0 | | | | | 4.0 - 7.9' FILL: Reddish brown silt; trace clay, fine sand, and f-m brick; greenish gray mottling; yellow/white clayey COPR from 7.7-7.9'; v. stiff, wet from 5.0' | | 124-SB-039-0406 collected from 5.0-5.5' bgs @ 10:10 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 7.9 - 9.2' FILL: Brown fine sand; v. dense, wet | 0.0 | 124-SB-039-0608 collected from 7.5-8.0' bgs @ 10:15 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.2 - 12.0' FILL: Yellow/grayish brown silty sand, trace clay and fine gravel (COPR); wet | | 124-SB-039-0810 collected from 9.5-10.0' bgs @ 10:25 |
| | 11.0 | | | | | | | 124-SB-039-1012 collected from 11.5-12.0' bgs @ 10:30 |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 12.2' FILL: Brown f-m sand, wet | 0.0 | |
| | 13.0 | | | | | 12.2 - 16.0' PT: Very dark brown (7.5YR 3/3) peat; end of boring at 16' | | 124-SB-039-1214 collected from 12.5-13.0' bgs @ 10:40 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-040

**DATE BEGAN:** 08/04/09 **DATE FINISHED:** 08/04/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 4 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 237 |
| | 1.0 | | | | | 0.3 - 3.0' FILL: Reddish brown sandy silt; trace fine gravel, brick, coal, and concrete; stiff | | 124-SB-040-0002 collected from 1.5-2.0' bgs @ 10:50 |
| | 2.0 | | | | | | | 124-SB-040-0204 collected from 2.5-3.0' bgs @ 10:55 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 4.5' FILL: Brown/dark brown clayey sand and f-m gravel; loose, wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 12.0' FILL: Grayish brown/pale yellow silty sand (COPR), trace fine gravel; wet | | 124-SB-040-0406 collected from 5.5-6.0' bgs @ 11:00 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 124-SB-040-0608 collected from 7.5-8.0' bgs @ 11:05 |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | |
| | 9.0 | | | | | | | 124-SB-040-0810 collected from 9.5-10.0' bgs @ 11:10 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 12.0 - 12.1' FILL: Dark brown/black sandy silt, wet | | 124-SB-040-1012 collected from 11.5-12.0' bgs @ 11:15 |
| | 12.0 | R-4 | N/A | 4.0 | | 12.1 - 16.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 16' | 0.0 | |
| | 13.0 | | | | | | | 124-SB-040-1214 collected from 12.5-13.0' bgs @ 11:25 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-041
**DATE BEGAN:** 08/04/09
**DATE FINISHED:** 08/04/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 279 |
| | | | | | | 0.2 - 1.2' FILL: Reddish brown fine sand, trace silt and fine gravel | 0.0 | |
| | 1.0 | | | | | | 0.0 | |
| | | | | | | 1.2 - 2.0' FILL: Dark brown/brown f-m gravel, some f-m sand and brick, trace ceramics; slight petroleum odors and wet from 1.5' | 2.1 | |
| | 2.0 | | | | | | 1.3 | |
| | | | | | | 2.0 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | | | | | | 4.0 - 4.3' FILL: Brown f-m gravel and brick, some f-c sand; petroleum odors, wet | 15.9 | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.3 - 6.5' FILL: Brown silty sand; white/gray/green COPR from 5.0-5.5'; wet | 9.5 | |
| | | | | | | | 4.3 | 124-SB-041-0406 collected from 5.0-5.5' bgs @ 13:00 |
| | 5.0 | | | | | | 1.0 | |
| | | | | | | | 0.0 | 124-SB-041-0608 collected from 6.0-6.5' bgs @ 13:05 |
| | 6.0 | | | | | | 0.0 | |
| | | | | | | 6.5 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 9.7' FILL: Brown clayey silt; soft, wet | 0.0 | No recovery from 8-10' bgs on initial attempt. Moved 2 ft E and re-sampled the 8-10' bgs interval. |
| | 9.0 | | | | | | | |
| | | | | | | 9.7 - 10.0' FILL: Brown silty sand, wet; end of boring at 10' | | 124-SB-041-0810 collected from 9.5-10.0' bgs @ 13:25 |
| | 10.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-042
**DATE BEGAN:** 08/04/09
**DATE FINISHED:** 08/04/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 283 |
| | | | | | | 0.2 - 1.8' FILL: Reddish brown silty sand, trace brick; dense | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.8 - 3.2' FILL: Brown f-m sand, some f-m clinker, trace coal and gray mottling (possible COPR) | | |
| | 3.0 | | | | | 3.2 - 4.0' FILL: Concrete | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 4.8' FILL: Grayish brown silty sand, some yellow COPR; wet from 4.5' | 0.0 | |
| | | | | | | 4.8 - 5.2' FILL: Dark gray f-c sand, some f-m ceramics; wet | | |
| | 5.0 | | | | | 5.2 - 6.0' FILL: Yellow clayey COPR, wet | | |
| | 6.0 | | | | | 6.0 - 6.2' FILL: Dark greenish gray COPR, wet | | |
| | | | | | | 6.2 - 7.5' FILL: Dark reddish brown fine sand, trace silt; dense, wet | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 8.2' FILL: Black silt, wet | 0.0 | |
| | | | | | | 8.2 - 8.5' FILL: Yellow silt (COPR), wet | | |
| | 9.0 | | | | | 8.5 - 9.0' FILL: Brown silty sand, wet | | |
| | | | | | | 9.0 - 10.0' FILL: Brown clayey silt, thin lenses of organic material; end of boring at 10' | | 124-SB-042-0810 collected from 9.5-10.0' bgs @ 14:00 |
| | 10.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-043

**DATE BEGAN:** 08/04/09 **DATE FINISHED:** 08/04/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 1.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 298 |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Dark brown silty sand and clinker | | |
| | 2.0 | | | | | 0.8 - 1.5' FILL: Brown silty sand; trace coal, brick and fine gravel | | |
| | 3.0 | | | | | 1.5 - 3.0' FILL: Dark brown sandy silt; trace clay and brick; some wood from 2.8'; wet | | |
| | 4.0 | R-2 | N/A | 3.5 | | 3.0 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Dark brown sandy silt, some wood, trace clay and brick; wet | | |
| | 6.0 | | | | | 5.0 - 5.5' FILL: Gravel, f-c; wet | | |
| | 7.0 | | | | | 5.5 - 6.0' FILL: Brown clayey silt, trace greenish gray COPR; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 6.0 - 7.4' FILL: Brown silty sand, trace clay; dense, wet | 0.0 | |
| | 9.0 | | | | | 7.4 - 9.0' FILL: Yellow/white silty sand (COPR), wet | | |
| | 10.0 | | | | | 8.0 - 9.0' FILL: Yellow/white silty sand (COPR), wet | | |
| | 11.0 | | | | | 9.0 - 9.8' FILL: Brown silty sand, wet | | 124-SB-043-1012 collected from 10.5-11.0' bgs @ 14:45 |
| | 12.0 | | | | | 9.8 - 10.3' FILL: Brown/dark brown clayey silt, trace fine gravel | | |
| | | | | | | 10.3 - 11.0' OL: Black clayey siilt, some organic material | | |
| | | | | | | 11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-044

**DATE BEGAN:** 08/05/09 **DATE FINISHED:** 08/05/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 292 |
| | | | | | | 0.3 - 0.5' FILL: Concrete | | |
| | 1.0 | | | | | 0.5 - 2.5' FILL: Brown f-m sand, some concrete; trace silt, brick, gravel and coal; wood from 2.3'; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | | | | | | 2.5 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.0' FILL: Dark brown silty sand, some f-m gravel from 4.0-4.5'; loose, wet | 0.0 | |
| | 5.0 | | | | | 5.0 - 8.0' FILL: Dark brown clayey silt; v. soft, wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.2' FILL: Grayish brown silty sand, some yellow COPR, trace fine gravel and organic material; wet | 0.0 | 124-SB-044-0608 collected from 7.5-8.0' bgs @ 8:05; DUP @ 8:07 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-044-0810 collected from 9.5-10.0' bgs @ 8:15 |
| | | | | | | 10.2 - 11.0' FILL: Yellow clayey COPR; soft | | |
| | 11.0 | | | | | 11.0 - 11.4' OH: Dk olive brown/black (2.5Y 3/3 - 2.5/1) clayey silt, trace organic material | | |
| | 12.0 | | | | | 11.4 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | 124-SB-044-1012 collected from 11.5-12.0' bgs @ 8:20 |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** **124-SB-044R**

**DATE BEGAN:** 10/26/10 **DATE FINISHED:** 10/26/10 **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 14ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.3' ASPHALT | 0.0 | |
| | | | | | | 0.3 - 0.5' FILL: Concrete | | |
| | 1.0 | | | | | 0.5 - 2.5' FILL: Brown f-m sand, some concrete; trace silt, brick, gravel and coal; wood from 2.3'; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.0' FILL: Dark brown silty sand, some f-m gravel from 4.0-4.5'; loose, wet | 0.0 | |
| | 5.0 | | | | | 5.0 - 8.0' FILL: Dark brown clayey silt; v. soft, wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.2' FILL: Grayish brown silty sand, some yellow COPR, trace fine gravel and organic material; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.2 - 11.0' FILL: Yellow clayey COPR; soft | | |
| | 11.0 | | | | | 11.0 - 11.4' OH: Dk olive brown/black (2.5Y 3/3 - 2.5/1) clayey silt, trace organic material | | |
| | 12.0 | R-4 | N/A | 2.0 | | 11.4 - 14.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 14.0' bgs. | 0.0 | 124-SB-044-1214 collected from 12.5-13.0' bgs @ 10:20 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: FP

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-045

**DATE BEGAN:** 08/05/09 **DATE FINISHED:** 08/05/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 1.0' ASPHALT | 0.0 | Field Map # 294 |
| | 1.0 | | | | | 1.0 - 1.6' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.6 - 2.0' FILL: Reddish brown fine sand, trace white COPR | | |
| | 3.0 | | | | | 2.0 - 4.7' FILL: Dark gray f-m clinker, some f-c sand; trace white COPR, brick and gravel; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | | 0.0 | |
| | 5.0 | | | | | 4.7 - 8.5' FILL: Light brown/yellow/grayish brown silty sand (COPR); wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | 124-SB-045-0608 collected from 7.5-8.0' bgs @ 8:35 |
| | 9.0 | | | | | 8.5 - 10.5' FILL: Pale yellow clayey silt (COPR); wet | | |
| | 10.0 | | | | | | | 124-SB-045-0810 collected from 9.5-10.0' bgs @ 8:45 |
| | 11.0 | | | | | 10.5 - 11.0' OL: Dk olive brown/black (2.5Y 3/3 to 2.5/1) clayey silt, some organic material | | |
| | 12.0 | | | | | 11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | 124-SB-045-1012 collected from 11.0-11.5' bgs @ 8:50 |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-046

**DATE BEGAN:** 08/05/09 **DATE FINISHED:** 08/05/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 1.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 304 |
| | 1.0 | | | | | 0.3 - 0.8' FILL: Reddish brown sandy silt; trace fine gravel, brick and coal | | |
| | | R-2 | N/A | 1.5 | | 0.8 - 1.8' FILL: Concrete | 0.0 | Driller stopped first run at 1.5' bgs to prevent bit from damage by concrete |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Black f-m sand, some f-m gravel; trace brick, clinker and coal; wet from 2.0' | | |
| | 3.0 | | | | | 2.5 - 5.0' FILL: Brown f-m gravel and brick, some f-c sand; wet | | |
| | 4.0 | R-3 | N/A | 3.0 | | | 0.0 | |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Brown silty fine sand, yellow COPR from 6.7'; wet | | |
| | 6.0 | | | | | | | 124-SB-046-0608 collected from 6.5-7.0' bgs @ 9:40 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-4 | N/A | 4.0 | | 8.0 - 10.5' FILL: Brown silty fine sand, thin seam of yellow COPR at 8.2'; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-046-0810 collected from 9.5-10.0' bgs @ 9:50 |
| | | | | | | 10.5 - 11.0' OH: Dark olive brown/black (2.5Y 3/3 to 2.5/1) clayey silt | | 124-SB-046-1012 collected from 10.5-11.0' bgs @ 9:55 |
| | 11.0 | | | | | 11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-047

**DATE BEGAN:** 08/05/09 **DATE FINISHED:** 08/05/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 1.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 302 |
| | 1.0 | | | | | 0.2 - 1.0' FILL: Dark brown/yellowish brown f-m sand | | |
| | 2.0 | | | | | 1.0 - 3.0' FILL: Dark brown silty sand; trace f-m gravel, brick and wood; wet from 1.5' | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 2.0 | | 4.0 - 5.8' FILL: Dark brown silty sand, trace fine gravel; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.8 - 6.0' FILL: Wood | | |
| | 7.0 | | | | | 6.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown silty sand; very loose, wet | 0.0 | 8-10' bgs interval too saturated to sample; poured out of sleeve |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | 124-SB-047-1012 collected from 10.0-10.5' bgs @ 10:40; DUP @ 10:42 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-048

**DATE BEGAN:** 08/05/09 **DATE FINISHED:** 08/05/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 1.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 1.8 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 289 |
| | 1.0 | | | | | 0.2 - 0.5' FILL: Reddish brown silty sand, trace brick | | Location # 290 was abandoned after multiple refusals on concrete from 0.5-1.5' bgs. |
| | 2.0 | | | | | 0.5 - 1.8' FILL: Brown/dark brown silty sand; trace fine gravel, brick and glass; concrete from 1.0-1.3'; some wood from 1.4'; wet from 1.5' | | |
| | 3.0 | | | | | 1.8 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 0.5 | | 4.0 - 4.5' FILL: Black rubber fragments and f-m gravel; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 8.0' No recovery | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.0' FILL: Very dark grayish brown clayey sand; soft, wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-048-0810 collected from 9.5-10.0' bgs @ 12:15; DUP @ 12:17 |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Brown/reddish brown/dark brown f-c sand, some clayey silt lenses | | 124-SB-048-1012 collected from 11.5-12.0' bgs @ 12:20 |
| | 12.0 | | | | | 11.5 - 11.7' OH: Black (2.5Y 2.5/1) clayey silt | | |
| | | | | | | 11.7 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South


**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-049

**DATE BEGAN:** 08/05/09 **DATE FINISHED:** 08/05/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 3.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**




PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-050
**DATE BEGAN:** 08/06/09
**DATE FINISHED:** 08/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 262 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Reddish brown sandy silt, trace fine gravel and coal | | Boring located too close to shed; moved 1 ft SE<br>Refusal at 5.5 ft bgs due to concrete; moved 2 ft SE |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Concrete | | |
| | 3.0 | | | | | 2.0 - 6.0' FILL: Grayish brown f-m sand and gray silt (COPR), some fine gravel, trace clinker; very dense, wet from 2.5' | | |
| | 4.0 | R-2 | N/A | 4.0 | | | 0.0 | 124-SB-050-0406 collected from 3.5-4.0' bgs @ 8:25; HOLD |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: White silty sand (COPR), some brown f-m sand, trace f-c gravel and dark green COPR; wet | | 124-SB-050-0608 collected from 6.0-6.5' bgs @ 8:30 |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Brown f-m sand, trace silt; wet | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 10.0' FILL: Brown silty sand, trace clay; end of boring at 10' | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-050-0810 collected from 9.5-10.0' bgs @ 8:35 |

PREPARED BY: JB
CHECKED BY: FP

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-051
**DATE BEGAN:** 08/06/09
**DATE FINISHED:** 08/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 281 |
| | | | | | | 0.5 - 0.7' FILL: Reddish brown sandy silt, some fine gravel | | |
| | 1.0 | | | | | 0.7 - 1.5' FILL: Concrete | | |
| | | | | | | 1.5 - 4.0' FILL: Grayish brown f-m sand, some gray silt (COPR), trace fine gravel and clinker; wet | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 6.0' FILL: Grayish brown f-c sand, some f-c gravel, trace brick and gray/green COPR; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: White/light brown clayey sand (COPR), trace fine gravel; wet | | 124-SB-051-0608 collected from 6.0-6.5' bgs @ 9:20 |
| | | | | | | 6.5 - 7.5' FILL: Brown f-m sand, trace silt; wet | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 10.0' FILL: Brown silty sand, trace clay, trace f-m sand from 9.9'; wet; end of boring at 10' | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 124-SB-051-0810 collected from 9.5-10.0' bgs @ 9:25 |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-052
**DATE BEGAN:** 08/06/09
**DATE FINISHED:** 08/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 264 |
| | 1.0 | | | | | 0.3 - 1.8' FILL: Brown f-m sand, some f-m gravel, trace brick; wet from 1.5' | | |
| | 2.0 | | | | | 1.8 - 2.2' FILL: Concrete; wet | | |
| | 3.0 | | | | | 2.2 - 3.5' FILL: Brown/reddish brown/dark brown f-m sand, some white/green/gray COPR, trace fine gravel; wet | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.5' FILL: Brown/reddish brown/dark brown f-m sand, some white/green/gray COPR and concrete, trace fine gravel; wet | 0.0 | 124-SB-052-0406 collected from 4.0-4.5' bgs @ 10:00 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.8' FILL: Dark brown f-c sand, some f-m gravel; wet | | |
| | 7.0 | | | | | 6.8 - 7.3' FILL: White/yellow sandy clay (COPR), trace wood and fine gravel; wet | | 124-SB-052-0608 collected from 6.8-7.3' bgs @ 10:05 |
| | | | | | | 7.3 - 8.2' FILL: Brown f-m sand, trace silt; wet | | |
| | 8.0 | R-3 | N/A | 2.0 | | | 0.0 | |
| | 9.0 | | | | | 8.2 - 10.0' FILL: Brown silty sand, trace clay; wet; end of boring at 10' | | |
| | 10.0 | | | | | | | 124-SB-052-0810 collected from 9.5-10.0' bgs @ 10:10 |

PREPARED BY: JB
CHECKED BY: FP

# MACTEC — Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-053
**DATE BEGAN:** 08/06/09
**DATE FINISHED:** 08/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 77300DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 296 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Concrete | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Gray clinker, some reddish brown/brown silty sand, trace brick; wet from 1.5' | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Yellowish brown silty sand (COPR), trace fine gravel; trace white/green COPR from 2.0-2.2'; wet | | |
| | 4.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 5.0 | R-2 | N/A | 4.0 | | 4.0 - 6.5' FILL: Brown f-c sand, some f-m gravel, trace silt; trace white/yellow/green mottling; gray clinker from 5.5-6.0'; wet | 0.0 | 124-SB-053-0608 collected from 6.0-6.5' bgs @ 10:45 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Brown f-m sand, trace silt; wet | | |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 8.5' FILL: Brown sandy clay and yellow/dark green COPR; soft, wet | 0.0 | 124-SB-053-0810 collected from 8.0-8.5' bgs @ 10:50 |
| | 9.0 | | | | | 8.5 - 10.0' FILL: Brown clayey silt, trace fine sand; soft, wet | | |
| | 10.0 | | | | | 10.0 - 10.5' OH: Dark olive brown (2.5Y 3/3) clayey silt, trace organic material; stiff | | 124-SB-053-1012 collected from 10.0-10.5' bgs @ 10:55 |
| | 11.0 | | | | | 10.5 - 11.5' PT: Dark olive brown/very dark brown (2.5Y 3/3 to 7.5YR 2.5/2) peat; wet | | |
| | 12.0 | | | | | 11.5 - 12.0' No recovery; end of boring at 12' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-054

**DATE BEGAN:** 08/06/09 **DATE FINISHED:** 08/06/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 2.0 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 286 |
| | 1.0 | | | | | 0.2 - 0.7' FILL: Brown f-m sand, some f-m gravel | | |
| | 2.0 | | | | | 0.7 - 3.0' FILL: Dark brown/reddish brown silty sand, some brick, trace concrete, gravel and coal, trace green mottling from 2.3-2.6'; wet from 2.0' | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 6.0' FILL: Dark brown/reddish brown silty sand, some brick, trace concrete, gravel and coal, trace gray silt and fine gravel (possible COPR) from 4.8'; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.6' FILL: Grayish brown f-c sand, some gray silt and clinker (possible COPR); white/green clayey COPR from 7.3'; wet | | |
| | 7.0 | | | | | 7.6 - 8.0' FILL: Brown f-m sand, trace gravel; wet | | 124-SB-054-0608 collected from 7.0-7.5' bgs @ 11:30 |
| | 8.0 | R-3 | N/A | 2.8 | | 8.0 - 9.8' FILL: Brown silty sand; yellow clayey sand (COPR) from 9.0-9.5'; wet | 0.0 | |
| | 9.0 | | | | | 9.8 - 10.0' FILL: Brown clayey silt, trace sand; moist | | 124-SB-054-0810 collected from 9.0-9.5' bgs @ 11:35 |
| | 10.0 | | | | | 10.0 - 10.5' OL: Dark olive brown (2.5Y 3/3) clayey silt, trace organic material; moist | | 124-SB-054-1012 collected from 10.0-10.5' bgs @ 11:40 |
| | 11.0 | | | | | 10.5 - 10.8' PT: Dark olive brown (2.5Y 3/3) peat; wet | | |
| | 12.0 | | | | | 10.8 - 12.0' No recovery; end of boring at 12' | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-055

**DATE BEGAN:** 08/06/09 **DATE FINISHED:** 08/06/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 14 ft bgs **GW DEPTH:** 2.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 300 |
| | | | | | | 0.2 - 0.5' FILL: Brown f-m sand, some f-m gravel | 0.0 | |
| | 1.0 | | | | | | 6.5 | |
| | | | | | | 0.5 - 3.0' FILL: Dark brown silty sand, some fine gravel, trace brick, clinker, coal, wood and concrete; very stiff, wet from 2.5' | 54.6 | |
| | 2.0 | | | | | | 2.7 | |
| | | | | | | | 1.8 | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | 0.1 | |
| | 4.0 | R-2 | N/A | 3.2 | | 4.0 - 5.2' FILL: Dark brown/black silty sand, some fine gravel, trace brick, clinker, coal, wood and concrete; very stiff, wet | 0.0 | |
| | 5.0 | | | | | 5.2 - 6.0' FILL: Concrete | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Grayish brown f-c sand, some f-m gravel and white clayey COPR; wet | | |
| | 7.0 | | | | | 6.5 - 7.2' FILL: Brown f-m sand, trace silt; wet | | |
| | | | | | | 7.2 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.5 | | 8.0 - 9.0' FILL: Brown silty sand; wet | 0.0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Pale yellow/white clayey silt (COPR), some f-m sand; wet | | |
| | | | | | | 9.5 - 10.3' FILL: Brown f-m sand; wet | | |
| | 10.0 | | | | | 10.3 - 10.5' FILL: Brown clayey silt, trace fine sand; wet | | 124-SB-055-1012 collected from 10.0-10.5' bgs @ 12:55 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 2.0 | | 12.0 - 14.0' PT: Dark olive brown/very dark brown (2.5Y 3/3 to 7.5YR 2.5/2) peat; wet; end of boring at 14' | 0.0 | 124-SB-055-1214 collected from 12.0-12.5' bgs @ 13:00 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** 124-SB-056

**DATE BEGAN:** 08/06/09 **DATE FINISHED:** 08/06/09 **INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 77300DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 8 ft bgs **GW DEPTH:** 2.5 ft bgs

**DRILLER:** Ed Blewett **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 1.0' FILL: Brown f-m sand, some f-m gravel and clinker | 0.0 | Field Map # 261 |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Reddish brown sandy silt, trace fine gravel and brick, trace green mottling at 2.4' | | |
| | 2.0 | | | | | | | 124-SB-056-0204 collected from 2.0-2.5' bgs @ 14:15 |
| | | | | | | 2.5 - 3.0' FILL: Brown silty sand, some f-m gravel and wood; wet | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 5.5' FILL: Dark brown/brown silty sand, some fine gravel; trace clinker, concrete and brick; white COPR and wood from 5.2-5.3'; wet | 0.0 | |
| | 5.0 | | | | | | | 124-SB-056-0406 collected from 5.0-5.5' bgs @ 14:20 |
| | | | | | | 5.5 - 6.8' FILL: Brown f-m sand, few silt lenses; wet | | |
| | 6.0 | | | | | | | 124-SB-056-0608 collected from 6.5-7.0' bgs @ 14:25 |
| | | | | | | 6.8 - 7.0' FILL: Brown sandy silt; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring at 8' | | |
| | 8.0 | | | | | | | |

PREPARED BY: JB

CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** **124-SB-058**

**DATE BEGAN:** 11/11/09 **DATE FINISHED:** 11/11/09 **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 3.75 ft bgs.

**DRILLER:** Mike Kinnney **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0.0 | |
| | 1.0 | | | | | 0.3 - 0.8' FILL: Brown fine silty sand with trace coal and trace gravel | | 124-SB-058-0002 collected from 1.0-1.5' bgs @ 13:55 |
| | 2.0 | | | | | 0.8 - 3.8' FILL: Light green to green silt with white nodules; moist at 3.0 ft bgs.; potential COPR | | |
| | 3.0 | | | | | 3.8 - 4.0' FILL: Wet light green silt with white nodules and fine to medium gravel; potential COPR | | 124-SB-058-0204 collected from 3.5-4.0' bgs @ 14:00 |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.3' FILL: Wet light green silt with white nodules and fine to medium gravel; potential COPR | 0.0 | 124-SB-058-0406 collected from 4.5-5.0' bgs @ 14:05 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.3 - 7.0' FILL: White to light brown silt with white nodules and fine gravel; potential COPR | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Light brown fine to medium sand with trace silt | | 124-SB-058-0608 collected from 7.5-8.0' bgs @ 14:10 |
| | 8.0 | R-3 | N/A | 3.0 | | 8.0 - 9.0' FILL: Light brown fine to medium sand with trace silt | 0.0 | 124-SB-058-0810 collected from 8.5-9.0' bgs @ 14:15 |
| | 9.0 | | | | | 9.0 - 10.5' OL: Black clayey silt with organics | | |
| | 10.0 | | | | | | | 124-SB-058-1012 collected from 10.0-10.5' bgs @ 14:20 |
| | 11.0 | | | | | 10.5 - 11.0' PT: Brown peat; moist | | |
| | 12.0 | | | | | 11.0 - 12.0' No Recovery; end of boring at 12.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MV

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** **124-SB-059**

**DATE BEGAN:** 11/11/09 **DATE FINISHED:** 11/11/09 **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 3.0 ft bgs.

**DRILLER:** Mike Kinnney **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0.0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Moist light brown fine silty sand with gravel | | 124-SB-059-0002 collected from 1.0-1.5' bgs @ 14:25 |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown fine gravelly sand with wood; wet at tip | | 124-SB-059-0204 collected from 2.0-2.5' bgs @ 14:30 |
| | 3.0 | | | | | 2.5 - 4.0' No Recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 5.5' FILL: Saturated white clayey silt ; potential COPR | 0.0 | 124-SB-059-0406 collected from 4.5-5.0' bgs @ 14:35 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Wet white to light purple to light green silt with white nodules; stiff; potential COPR | | 124-SB-059-0608 collected from 6.5-7.0' bgs @ 14:40 |
| | 7.0 | | | | | 7.0 - 8.0' No Recovery | | 124-SB-059DP-0608 collected from 6.5-7.0' bgs @ 14:43 |
| | 8.0 | R-3 | N/A | 3.0 | | 8.0 - 9.5' FILL: Wet light green to yellow clayey silt; Potential COPR | 0.0 | 124-SB-059-0810 collected from 9.0-9.5' bgs @ 14:45 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.3' OL: Black clayey silt with heavy organics | | 124-SB-059-1012 collected from 10.0-10.5' bgs @ 14:50 |
| | 11.0 | | | | | 10.3 - 11.0' PT: Brown peat; moist | | |
| | 12.0 | | | | | 11.0 - 12.0' No Recovery; end of boring at 12.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124, Roosevelt Lanes, Jersey City, NJ **PROJECT NO:** 3480050143 **BORING ID:** **124-SB-060**

**DATE BEGAN:** 11/11/09 **DATE FINISHED:** 11/11/09 **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore **COMPLETION DEPTH:** 12 ft bgs **GW DEPTH:** 3.0 ft bgs.

**DRILLER:** Mike Kinnney **NORTH:** **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0.0 | |
| | | | | | | 0.5 - 0.8' FILL: Stiff red brown clayey silt | | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Dark brown fine silty sand with gravel | | 124-SB-060-0002 collected from 1.0-1.5' bgs @ 14:55 |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Light brown to orange fine to medium sand; Wet at 3.0' bgs. | | |
| ▽ | 3.0 | | | | | | | 124-SB-060-0204 collected from 2.5-3.0' bgs @ 15:00 |
| | | | | | | 3.5 - 4.0' No Recovery | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 5.3' FILL: Light brown to orange fine to medium sand | 0.0 | 124-SB-060-0406 collected from 4.0-4.5' bgs @ 15:05 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.3 - 7.5' FILL: Wet stiff light green to yellow silt with white nodules; potential COPR | | |
| | 7.0 | | | | | | | 124-SB-060-0608 collected from 7.0-7.5' bgs @ 15:10 |
| | | | | | | 7.5 - 8.0' No Recovery | | |
| | 8.0 | R-3 | N/A | 3.0 | | 8.0 - 8.8' FILL: Wet white to light purple clayey silt | 0.0 | 124-SB-060-0810 collected from 8.0-8.5' bgs @ 15:15 |
| | 9.0 | | | | | 8.8 - 10.3' OL: Saturated black clayey silt with organics | | |
| | 10.0 | | | | | 10.3 - 11.0' PT: Moist brown peat | | 124-SB-060-1012 collected from 10.0-10.5' bgs @ 15:20 |
| | 11.0 | | | | | 11.0 - 12.0' No Recovery; end of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: BS

CHECKED BY: MV

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-063
**DATE BEGAN:** 5/7/10
**DATE FINISHED:** 5/7/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT | 0 | |
| | | | | | | 0.5 - 2.5' FILL: Brown silty fine sand, brick, gravel, fine to coarse sand | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | | | | | | 2.5 - 3.0' FILL: Black silty coarse sand, wood, coarse gravel, gray material form 2.75-3.0' bgs; moist | | |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.5' FILL: Dark brown silty sand, gravel, trace shells; wet | 0 | |
| | 5.0 | | | | | | | |
| | | | | | | 5.5 - 6.5' FILL: Light brown fine to medium sand; wet | | |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 7.0' FILL: Light brown fine to medium sand, red brown silt; wet | | Sample collected 124-SB-063-0608 from 6.5-7.0' bgs @9:30 |
| | 7.0 | | | | | 7.0 - 8.0' : No recovery; end of boring at 8' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-064
**DATE BEGAN:** 5/7/10
**DATE FINISHED:** 5/7/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' FILL: Brown silty sand, fine to coarse gravel; moist | 0 | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Red brown silt, fine to medium sand, gravel | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Light brown silty sand, fine to medium gravel, brick | | Sample collected 124-SB-064-0204 from 2.5-3.0' bgs @9:45 |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 6.5' FILL: Light brown fine to medium sand, lenses of red brown silt throughout; wood and roots from 4.0-5.0' bgs; wet | 0 | Sample collected 124-SB-064-0406 from 4.5-5.0' bgs @9:50, DUP @ 9:52 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 124-SB-064-0608 from 6.0-6.5' bgs @9:55 |
| | 7.0 | | | | | 6.5 - 8.0' : No recovery; end of boring at 8.0' bgs | | EOB at 8 ft bgs |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-065
**DATE BEGAN:** 5/7/10
**DATE FINISHED:** 5/7/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE | 0 | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | | | | | | 0.5 - 1.0' : Void | | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Dark brown silty sand, gravel | | |
| | 2.0 | | | | | | | Sample collected 124-SB-065-0204 from 2.5-3.0' bgs @10:15 |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Light brown silt, trace fine sand and fine to medium gravel | | |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Light brown silt, fine sand, fine to medium gravel, creosote odor, slight sheen; moist | 0 | Sample collected 124-SB-065-0406 from 4.5-5.0' bgs @10:20 |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, roots, trace silt lenses from 6.5-7.0' bgs; wet | | |
| | 6.0 | | | | | | | Sample collected 124-SB-065-0608 from 6.5-7.0' bgs @10:25 |
| | 7.0 | | | | | 7.0 - 8.0' : No recovery; end of boring at 8' bgs | | EOB at 8 ft bgs |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**LOCATION:** Site 124 | **PROJECT NO:** 3480050143 | **BORING ID:** 124-SB-066

**DATE BEGAN:** 5/7/10 | **DATE FINISHED:** 5/7/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 10 ft bgs | **GW DEPTH:** 5.0 ft bgs

**DRILLER:** G. Blewitt | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.5' CONCRETE | 0 | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | | | | | | 0.5 - 1.3' : Void | | |
| | 1.0 | | | | | 1.3 - 3.3' FILL: Dark brown/ black silty sand, coal, gravel, glass | | Sample collected 124-SB-066-0002 from 1.5-2.0' bgs @10:40 |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | Sample collected 124-SB-066-0204 from 2.5-3.0' bgs @10:45 |
| | | | | | | 3.3 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Light brown/ red brown silty sand, fine to medium gravel, potential COPR from 4.0-4.5' bgs, creosote odor | 0 | Sample collected 124-SB-066-0406 from 4.0-4.5' bgs @10:50 |
| ▽ | 5.0 | | | | | 5.0 - 6.0' FILL: Light brown silty sand, sheen, creosote odor; wet | | Sample for VOCs-Hold sample at 5.0-5.5' bgs @10:55 |
| | 6.0 | | | | | 6.0 - 6.3' FILL: Yellow/light green silt, potential COPR | | Sample collected 124-SB-066-0608 from 6.0-6.5' bgs @10:55 |
| | | | | | | 6.3 - 7.0' FILL: Light brown fine to medium sand | | |
| | 7.0 | | | | | 7.0 - 8.0' : No recovery | | |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 8.3' FILL: Light brown fine to medium sand, trace black clayey silt | 0 | |
| | | | | | | 8.3 - 10.0' FILL: Light brown silt, fine sand; end of boring at 10' | | Sample collected 124-SB-066-0810 from 8.5-9.0' bgs @11:00 |
| | 9.0 | | | | | | | EOB at 10 ft bgs |
| | 10.0 | | | | | | | |

PREPARED BY: MS

CHECKED BY: TG

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-067
**DATE BEGAN:** 5/7/10
**DATE FINISHED:** 5/7/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.5' ASPHALT | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown silty sand, trace wood and brick | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: COPR, purple and brown fine to medium sand; hard, dry | | Sample collected 124-SB-067-0002 from 1.5-2.0' bgs @11:25 |
| | 3.0 | | | | | 2.0 - 4.0' FILL: COPR, greenish-gray sandy silt; dense, moist | | Sample collected 124-SB-067-0204 from 3.0-3.5' bgs @11:30 |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 8.0' FILL: COPR, greenish-gray sandy silt; medium dense, wet | 0 | Sample collected 124-SB-067-0406 from 4.5-5.0' bgs @11:35 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 124-SB-067-0608 from 6.5-7.0' bgs @11:40, DUP @11:42 |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4 | | 8.0 - 11.0' FILL: COPR, greenish-gray sandy silt, grayish brown silt from10.0-11.0' bgs; soft, wet | 0 | Sample collected 124-SB-067-0810 from 8.5-9.0' bgs @11:45 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.3' OL: Black silty clay, trace fine sand; firm, moist | | Sample collected 124-SB-067-1012 from 10.5-11.0' bgs @11:50 |
| | 12.0 | S-4 | NA | 2 | | 11.3 - 12.5' PT: Peat | 0 | |
| | 13.0 | | | | | 12.5 - 14.0' SM: Brown sandy silt, organics; firm, wet; end of boring at 14' bgs | | Sample collected 124-SB-067-1214 from 12.5-13.0' bgs @11:55 |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-067R
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.5' ASPHALT | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown silty sand, trace wood and brick | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: COPR, purple and brown fine to medium sand; hard, dry | | |
| | 3.0 | | | | | 2.0 - 4.0' FILL: COPR, greenish-gray sandy silt; dense, moist | | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 8.0' FILL: COPR, greenish-gray sandy silt; medium dense, wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4 | | 8.0 - 11.0' FILL: COPR, greenish-gray sandy silt, grayish brown silt from10.0-11.0' bgs; soft, wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.3' OL: Black silty clay, trace fine sand; firm, moist | | |
| | 12.0 | S-4 | NA | 2 | | 11.3 - 12.5' PT: Peat | 0 | |
| | 13.0 | | | | | 12.5 - 14.0' SM: Brown sandy silt, organics; firm, wet; end of boring at 14' bgs | | Sample collected 124-SB-067R-1214 from 12.5-13.0' bgs @8:00 |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# MACTEC Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-068
**DATE BEGAN:** 5/7/10
**DATE FINISHED:** 5/7/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.5' ASPHALT | 0 | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Reddish brown silty sand, green staining, fine to medium gravel, trace wood and brick; dense, moist | 21.9 | Organic odor from 1.0-2.0' |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Wood with creosote | 1.2 | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: COPR, light brown silt, greenish brown nodules, possible porcelain; very soft, wet | | |
| | 4.0 | S-2 | NA | 4 | | 3.0 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Gray fine to coarse gravel, dark brown fine to coarse sand; loose, wet | | |
| | 6.0 | | | | | 4.5 - 5.3' FILL: Brown fine to medium sand, trace brick; dense, wet | | |
| | 7.0 | | | | | 5.3 - 8.0' FILL: COPR, greenish gray silty sand; dense, wet | | |
| | 8.0 | S-3 | NA | 4 | | 8.0 - 11.5' FILL: COPR, greenish gray silty sand; very dense, wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.5 - 11.8' FILL: Brown fine to medium sand, trace silt; dense, moist | | |
| | 12.0 | S-4 | NA | 4 | | 11.8 - 12.0' CL: Black silt, trace clay; firm, moist | 0 | Sample collected 124-SB-068-1214 from 12.5-13.0' bgs @13:30 |
| | 13.0 | | | | | 12.0 - 15.0' PT: Peat | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' SM: Gray silty sand; end of boring at 16' bgs | | Sample collected 124-SB-068-1416 from 15.0-15.5' bgs @13:35 |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-069
**DATE BEGAN:** 5/18/10
**DATE FINISHED:** 5/18/10
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 3.75 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.75 | | 0.0 - 0.5' ASPHALT: Asphalt and Gravel | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Reddish brown silty sand, trace fine to medium gravel; dry; loose | | |
| | 2.0 | | | | | 1.5 - 1.8' FILL: Concrete and Tile | | No PID readings - Raining |
| | 3.0 | | | | | 1.8 - 2.6' FILL: Brown/gray fine to coarse sand with some brick and tile, trace silt; wet; loose | | |
| | 4.0 | S-2 | NA | 1.75 | | 2.6 - 2.8' FILL: Crushed concrete | 0 | |
| | 5.0 | | | | | 2.8 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 4.2' FILL: Crushed concrete | | |
| | 7.0 | | | | | 4.2 - 4.8' FILL: Brown sandy silt, trace coarse gravel; firm; wet | | |
| | 8.0 | S-3 | NA | 3.0 | | 4.8 - 5.8' FILL: Brown silt with trace fine sand and organics;firm; wet | 0 | |
| | 9.0 | | | | | 5.8 - 8.0' : No recovery | | |
| | 10.0 | | | | | 8.0 - 9.0' FILL: Brown silt with trace fine sand and organics; firm; wet | | |
| | 11.0 | | | | | 9.0 - 10.0' CL: Brown silt with trace fine sand; very loose; very wet | | Sample collected 124-SB-069-1012 from 10.5-11.0 bgs @ 8:05 |
| | 12.0 | S-4 | NA | 1.75 | | 10.0 - 11.0' OL: Black silty clay with trace organics; firm; moist | 0 | |
| | 13.0 | | | | | 11.0 - 12.0' : No recovery | | |
| | 14.0 | | | | | 12.0 - 12.3' OL: Black silty clay with trace organics; firm; moist | | |
| | | | | | | 12.3 - 13.8' PT: Brown peat; moist | | Sample collected 124-SB-069-1214 from 12.5-13.0 bgs @ 8:10 |
| | | | | | | 13.8 - 14.0' No recovery; end of boring @ 14.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-070
**DATE BEGAN:** 5/18/10
**DATE FINISHED:** 5/18/10
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT: Asphalt and Gravel | NA | |
| | | | | | | 0.3 - 1.0' FILL: Reddish brown silty sand, trace brick; dense | | Sample collected 124-SB-070-0002 from 0.5-1.0 bgs @ 8:15 |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Concrete | | |
| | | | | | | 1.5 - 3.5' FILL: Gray/brown fine to medium silty sand; very dense | | Sample collected 124-SB-070-0204 from 2.5-3.0 bgs @ 8:20 |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' FILL: Concrete | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 6.0' FILL: Brown fine to course silty sand; very wet; very loose | NA | |
| | 5.0 | | | | | | | Sample collected 124-SB-070-0406 from 5.0-5.5 bgs @ 8:25 |
| | 6.0 | | | | | 6.0 - 6.3' FILL: Gray silt; moist; dense | | |
| | | | | | | 6.3 - 6.5' FILL: Gray and orange silt; soft; wet | | |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Reddish borwn fine to medium silty sand, lenses of dense red silt; wet; loose; end of boring @ 8.0' bgs | | Sample collected 124-SB-070-0608 from 6.0-6.5bgs @ 8:30 |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell Site 124

**SITE INFO:** Honeywell SA-6 South
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-071
**DATE BEGAN:** 5/18/10
**DATE FINISHED:** 5/18/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 11 ft bgs
**GW DEPTH:** 3.75 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | | |
| | | | NA | 2.5 | | 0.0 - 0.3' ASPHALT: Asphalt and Gravel | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Dark brown fine silty sand, some fine to medium gravel, trace brick | | Sample collected 124-SB-071-0002 from 0.5-1.0 bgs @ 8:40 |
| | 1.0 | S-1 | | | | 1.0 - 1.3' FILL: Concrete | | |
| | | | | | | 1.3 - 1.4' FILL: Wood | | |
| | | | | | | 1.4 - 1.8' FILL: Concrete | | |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Dark brown silt with fine to coarse gravel, wet, loose, trace organics | | |
| | | | | | | 2.5 - 4.0' No recovery | | Sample collected 124-SB-071-0204 from 2.0-2.5' bgs @ 8:45 |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 6.0' FILL: Dark brown silt with fine to coarse gravel, very wet, very loose, trace organics | 0 | |
| | 5.0 | | | | | | | Sample collected 124-SB-071-0406 from 5.0-5.5 bgs @ 8:50 |
| | 6.0 | | | | | 6.0 - 6.8' FILL: Brown fine to medium sand, trace silt, wet | | |
| | 7.0 | | | | | 6.8 - 7.5' FILL: Red brown silt, trace fine sand, firm, wet | | |
| | | | | | | 7.5 - 8.8' FILL: Yellow green COPR, silt, wet, firm | | Sample collected 124-SB-071-0608 from 7.5-8.0'bgs @ 8:55 |
| | 8.0 | S-3 | NA | 2.75 | | | 0 | |
| | | | | | | 8.8 - 9.0' FILL: Brown fine to medium sand | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell Site 124

**SITE INFO:** Honeywell SA-6 South
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-071

**DATE BEGAN:** 5/18/10
**DATE FINISHED:** 5/18/10
**INSPECTOR:** M. Daly

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT

**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 11 ft bgs
**GW DEPTH:** 3.75 ft bgs

**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.0 - 10.0' FILL: Saturated brown silt, trace fine sand, very loose | | Sample collected 124-SB-071-0810 from 9.0-9.5'bgs @ 9:00 |
| | 10.0 | | | | | 10.0 - 10.7' OL: Black silty clay, trace organics, firm, wet | | Sample collected 124-SB-071-1012 from 10.0-10.5'bgs @ 9:05 |
| | | | | | | 10.7 - 10.8' PT: Moist brown peat | | |
| | 11.0 | | | | | 10.8 - 11.0' No recovery; end of boring at 11.0 ft. bgs. | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-072
**DATE BEGAN:** 5/18/10
**DATE FINISHED:** 5/18/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' FILL: Asphalt and gravel | NA | |
| | | | | | | 0.1 - 0.3' FILL: Concrete | | |
| | 1.0 | | | | | 0.3 - 3.3' FILL: Dark brown/red brown silt, trace fine sand, fine to medium gravel, trace glass, some brick; very dense; moist | | No PID - Heavy rain |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.3 - 3.5' FILL: Gray fine to medium silty sand; loose | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 5.3' FILL: Dark brown sandy silt, fine to medium gravel, trace brick, trace clay | NA | |
| | 5.0 | | | | | 5.3 - 5.5' FILL: Wood | | |
| | | | | | | 5.5 - 5.8' FILL: Light brown fine to medium silty sand; loose; wet | | |
| | 6.0 | | | | | 5.8 - 5.8' FILL: Gray silt, some fine to medium gravel; very soft; potential COPR; wet | | |
| | 7.0 | | | | | 5.8 - 6.5' FILL: Red brown fine to medium sand, mottling of silty clay, trace silt; loose; wet | | |
| | 8.0 | S-3 | NA | 3.0 | | 6.5 - 8.0' No recovery | NA | |
| | | | | | | 8.0 - 8.5' FILL: Red brown fine to medium sand, mottling of silty clay, trace silt; loose; wet | | |
| | 9.0 | | | | | 8.5 - 9.3' FILL: Black silt, trace fine sand; loose; wet | | |
| | 10.0 | | | | | 9.3 - 9.8' FILL: Black silt, trace fine sand; very loose; very wet | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-072
**DATE BEGAN:** 5/18/10
**DATE FINISHED:** 5/18/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | S-4 | NA | 3.0 | | 9.8 - 10.5' FILL: Brown fine to medium silty sand; loose; wet<br>10.5 - 11.0' FILL: Brown silt; firm; wet<br>11.0 - 12.0' No recovery<br>12.0 - 12.5' OL: Brown silty clay, organics; firm; wet<br>12.5 - 15.0' PT: Brown peat; moist<br>15.0 - 16.0' No recovery; end of boring at 16.0' bgs. | NA | Sample collected 124-SB-072-1416 from 14.5-15.0' @ 9:30 |
| | 12.0 | | | | | | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-073
**DATE BEGAN:** 5/18/2010
**DATE FINISHED:** 5/18/2010
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' FILL: Asphalt and gravel | NA | |
| | | | | | | 0.3 - 0.4' FILL: Light brown silty fine to medium sand, fine to medium gravel; dense | | |
| | 1.0 | | | | | 0.4 - 1.0' FILL: Reddish brown sand and silt, some fine to medium gravel, trace brick; dense | | Heavy rain - No PID |
| | | | | | | 1.0 - 1.3' FILL: Concrete | | |
| | 2.0 | | | | | 1.3 - 2.5' FILL: Reddish brown silt, some sand, fine to medium gravel, trace brick; moist; dense | | |
| | 3.0 | | | | | 2.5 - 2.8' FILL: Concrete | | |
| | | | | | | 2.8 - 3.3' FILL: Dark brown silty sand, gray coarse sand | | |
| ▽ | 4.0 | S-2 | NA | 3.5 | | 3.3 - 4.0' No recovery | NA | |
| | | | | | | 4.0 - 4.8' FILL: Brown silty clay; wet; firm | | Organic odor at 4.75 - 5.25 |
| | 5.0 | | | | | 4.8 - 5.5' FILL: Dark brown silty fine to coarse sand, trace nodules of hard gray silt; wet; dense | | |
| | 6.0 | | | | | 5.5 - 5.9' FILL: Wood | | |
| | | | | | | 5.9 - 6.3' FILL: Gray sillt, possible COPR; wet; very soft | | Sample collected 124-SB-073-0608 from 6.0-6.5' @ 10:00 DUP at 10:02 |
| | 7.0 | | | | | 6.3 - 7.0' FILL: Reddish brown silt, trace organics; wet; loose | | |
| | | | | | | 7.0 - 7.5' FILL: Brown fine to medium sand, some wood; wet; loose | | Organic odor at 8.5 - 9.0' |
| | 8.0 | S-3 | NA | 2.0 | | 7.5 - 8.0' No recovery | NA | |
| | | | | | | 8.0 - 10.0' FILL: Brown silt, some fine sand; wet; firm; end of boring at 10.0' bgs. | | Sample collected 124-SB-073-0810 from 8.5-9.0' @ 10:05 (HOLD) |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-074
**DATE BEGAN:** 5/21/10
**DATE FINISHED:** 5/21/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT | 0 | |
| | | | | | | 0.5 - 2.0' FILL: Dark brown silty sand, gravel, coal, glass, trace glass; moist | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 2.8' FILL: Light brown silty sand, gravel, coal, glass, trace glass; moist | | |
| | | | | | | 2.8 - 3.0' FILL: Crushed brick | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.5' FILL: Red brown/light brown silty sand, gravel, trace fine brick | 0 | |
| | | | | | | 4.5 - 5.0' FILL: Black silt, wood; wet | | |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, trace silt; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 10.5' FILL: Light brown/brown silt; soft, wet | 0 | |
| | 9.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-074
**DATE BEGAN:** 5/21/10
**DATE FINISHED:** 5/21/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' FILL: Light brown/brown clayey silt; wet | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 12.5' FILL: Red brown fine to medium sand; wet | 0 | |
| | | | | | | 12.5 - 13.0' FILL: Red brown fine to medium sand, silt lenses; wet | | |
| | 13.0 | | | | | 13.0 - 13.5' FILL: Light brown/ red brown silt, fine to medium sand, organics; wet | | Sample collected 124-SB-074-1214 from 13.0-13.5' @11:25 |
| | 14.0 | | | | | 13.5 - 14.0' PT: Dark brown peat; moist; end of boring at 14.0' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-075
**DATE BEGAN:** 5/21/10
**DATE FINISHED:** 5/21/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.25 | | 0.0 - 0.5' TOPSOIL: Topsoil, grass, roots | 0 | |
| | 1.0 | | | | | 0.5 - 0.6' FILL: Concrete | | |
| | | | | | | 0.6 - 1.5' FILL: Light yellow/gray silt | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Red brown fine to medium sand | | |
| | 3.0 | | | | | 2.0 - 2.3' FILL: Crushed concrete | | |
| | | | | | | 2.3 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 1.5 | | 4.0 - 4.5' FILL: Light brown silty sand, wood | 0 | |
| | 5.0 | | | | | 4.5 - 5.5' FILL: Light brown fine to medium sand, shells | | |
| | | | | | | 5.5 - 8.0' No recovery | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.0' FILL: Light brown silt, shells | 0 | |
| | 9.0 | | | | | 9.0 - 11.3' FILL: Brown silt; soft | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.3 - 11.5' FILL: Black silt | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 13.0' FILL: Light brown fine to medium sand, dark brown silt, organics; wet | 0 | Sample collected 124-SB-075-1214 from 12.5-13.0' @12:00 |
| | 13.0 | | | | | 13.0 - 14.0' PT: Brown peat; moist; end of boring at 14.0' | | DUP @12:03 |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-076
**DATE BEGAN:** 5/21/10
**DATE FINISHED:** 5/21/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' TOPSOIL: Topsoil, grass, roots | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown silty sand, gravel, brick | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Crushed concrete | | |
| | 3.0 | | | | | 2.0 - 2.5' FILL: Light yellow crushed sandstone | | |
| | | | | | | 2.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.25 | | 4.0 - 6.0' FILL: Light brown fine to medium sand, trace silt | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Black clayey silt | | |
| | 7.0 | | | | | 7.0 - 7.3' FILL: Light yellow/light brown fine to medium sand, silt | | |
| | | | | | | 7.3 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.0' FILL: Light yellow/light brown fine to medium sand, silt | 0 | |
| | 9.0 | | | | | 9.0 - 10.5' FILL: Black clayey silt | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' PT: Brown peat; moist | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.0 | | 12.0 - 13.0' PT: Brown peat; moist | 0 | Sample collected 124-SB-076-1214 from 12.0-12.5' @12:50 |
| | 13.0 | | | | | 13.0 - 14.0' No recovery; end of boring at 14.0' | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124 | **PROJECT NO:** 3480050143 | **BORING ID:** 124-SB-077

**DATE BEGAN:** 5/21/10 | **DATE FINISHED:** 5/21/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 12 ft bgs | **GW DEPTH:** 4.5 ft bgs

**DRILLER:** G. Blewitt | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Black silty sand, coal, brick | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Crushed sandstone, brick, concrete | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Black silty sand, coal, gravel | | |
| | | | | | | 2.0 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.5' FILL: Gravel, brick, black silty sand; loose | 0 | |
| | | | | | | 4.5 - 5.5' FILL: Black silty sand, wood, newspaper, gravel; wet | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Light brown silt, fine sand; wet | | Sample collected 124-SB-077-0608 from 6.5-7.0' @13:00 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.5' FILL: Light brown silt, fine sand; wet | 0 | Sample collected 124-SB-077-0810 from 8.5-9.0' @13:05 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | | | | | | 10.5 - 11.0' PT: Peat; moist | | Sample collected 124-SB-077-1012 from 10.5-11.0' @13:10 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-077R
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Black silty sand, coal, brick | | |
| | 2.0 | | | | | 1.0 - 1.5' FILL: Crushed sandstone, brick, concrete | | |
| | 3.0 | | | | | 1.5 - 2.0' FILL: Black silty sand, coal, gravel | | |
| | 4.0 | S-2 | NA | 3.0 | | 2.0 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Gravel, brick, black silty sand; loose | 0 | |
| | 6.0 | | | | | 4.5 - 5.5' FILL: Black silty sand, wood, newspaper, gravel; wet | | |
| | 7.0 | | | | | 5.5 - 7.0' FILL: Light brown silt, fine sand; wet | | |
| | 8.0 | S-3 | NA | 3.0 | | 7.0 - 8.0' No recovery | | |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Light brown silt, fine sand; wet | 0 | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.0' PT: Peat; moist | | |
| | 12.0 | S-4 | NA | 1.5 | | 11.0 - 12.0' No recovery | | |
| | 13.0 | | | | | 12.0 - 13.5' PT: Peat; moist | 0 | Sample collected 124-SB-077-1214 from 12.5-13.0' @10:40 |
| | 14.0 | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0' bgs. | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-078
**DATE BEGAN:** 5/21/10
**DATE FINISHED:** 5/21/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.8 - 1.0' FILL: Brown silty sand, gravel | | |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Plastic, gravel | | |
| | | | | | | 1.3 - 1.5' FILL: Crushed sandstone | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown silty sand, gravel, coal, wood, brick | | |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | | | | | | 4.0 - 4.3' FILL: Dark brown silty sand, gravel, coal, wood, brick | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.3 - 4.8' FILL: Brown fine sand, silt, trace fine gravel | 0 | |
| | 5.0 | | | | | 4.8 - 7.5' FILL: Dark brown silt; soft, wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 9.5' FILL: Dark brown silt; soft, wet | 0 | |
| | 9.0 | | | | | | | |
| | | | | | | 9.5 - 10.5' FILL: Gray clayey silt, organics | | |
| | 10.0 | | | | | 10.5 - 11.3' PT: Brown peat; moist | | Sample collected 124-SB-078-1012 from 10.5-11.0' @13:25 |
| | 11.0 | | | | | 11.3 - 12.0' No recovery; end of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-079
**DATE BEGAN:** 5/21/10
**DATE FINISHED:** 5/21/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Brown silty fine sand, gravel, brick | | |
| | 2.0 | | | | | 2.0 - 2.3' FILL: Brown silty fine sand, gravel, brick, wood | | |
| | | | | | | 2.3 - 3.0' FILL: Wood | | |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 6.0' FILL: Dark brown silty sand, fine to medium gravel, fine glass, trace wood; wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 6.3' FILL: Red brown silt | | |
| | | | | | | 6.3 - 7.0' FILL: Red brown silt, fine sand | | Sample collected 124-SB-079-0608 from 6.5-7.0' @13:35 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 8.3' FILL: Red brown/light brown silt; dense, wet | 0 | |
| | | | | | | 8.3 - 9.0' FILL: Dark brown silt, fine sand (light green tint); soft, wet; potential COPR | | Sample collected 124-SB-079-0810 from 8.5-9.0' @13:40 |
| | 9.0 | | | | | 9.0 - 10.3' FILL: Black silt, trace organics | | |
| | 10.0 | | | | | | | |
| | | | | | | 10.3 - 11.0' PT: Brown peat; moist | | Sample collected 124-SB-079-1012 from 10.5-11.0' @13:45 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-080
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 9.5 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | | | | | | 0.3 - 0.8' FILL: Brown silty fine sand, some gravel (40%) | | |
| | 1.0 | | | | | 0.8 - 2.8' FILL: Brown sandy silt, trace brick coal, and trace sandstone and fine to medium gravel, moist, loose | | Sample collected 124-SB-080-0002 from 1.0-1.5' @ 8:45 |
| | 2.0 | | | | | | | |
| | | | | | | | | Sample collected 124-SB-080-0204 from 2.5-3.0' @ 8:50 |
| | 3.0 | | | | | 2.8 - 3.3' FILL: Dark brown clayey silt, some organics (15%), very moist, firm | | |
| | | | | | | 3.3 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Dark brown clayey silt, some organics (15%), very moist, firm | 0 | |
| | | | | | | 4.5 - 7.0' FILL: Dark brown fine to medium sand, some clinker (30%), coal, and fine to medium gravel, wet, loose | | Sample collected 124-SB-080-0406 from 4.5-5.0' @ 8:55 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.5' OH: Dark brown silty clay, trace organics | | Sample collected 124-SB-080-0608 from 7.0-7.5' @ 9:00 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 1 | | 8.0 - 8.8' OL: Dark brown silty clay, trace organics | 0 | Sample collected 124-SB-080-0810 from 8.5-9.0' @ 9:05 |
| | | | | | | 8.8 - 9.0' PT: Brown moist peat | | |
| | 9.0 | | | | | 9.0 - 9.5' No recovery; end of boring at 9.5' bgs | | EOB at 9.5 ft bgs |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-081
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.3 - 1.0' FILL: Brown fine to medium silty sand, trace wood, brick, coal and fine to medium gravel, dry, loose | | Sample collected 124-SB-081-0002 from 0.5-1.0' @8:15 |
| | 2.0 | | | | | 1.0 - 1.5' FILL: Light orange sandstone | | |
| | 3.0 | | | | | 1.5 - 3.0' FILL: Brown fine sandy silt, trace brick, coal and glass, dry, loose | | Sample collected 124-SB-081-0204 from 2.5-3.0' @8:20 |
| | 4.0 | S-2 | NA | 2.5 | | 3.0 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.3' FILL: Brown fine sandy silt, trace brick, coal and glass, dry, loose | | Sample collected 124-SB-081-0406 from 4.0-4.5' @8:25 |
| | 6.0 | | | | | 4.3 - 5.3' FILL: Brown silty sand, some wood and clay, wet, loose | | |
| | 7.0 | | | | | 5.3 - 6.3' FILL: Greyish brown fine sand, lenses of silty clay (20%), wet, loose | | Sample collected 124-SB-081-0608 from 6.0-6.5' @ 8:30 |
| | 8.0 | S-3 | NA | 3 | | 6.3 - 6.5' FILL: Red sandy silt, wet, loose | 0 | |
| | 9.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 8.5' FILL: Red sandy silt, wet, loose | | Sample collected 124-SB-081-0810 from 8.5-9.0' @8:35 |
| | 11.0 | | | | | 8.5 - 8.8' FILL: Red silty clay, trace organics, wet, firm | | |
| | 12.0 | | | | | 8.8 - 10.0' OL: Brown clay, organics (50%), wet, firm | | |
| | | | | | | 10.0 - 11.0' PT: Brown moist peat | | Sample collected 124-SB-081-1012 from 10.5-11.0' @8:40 |
| | | | | | | 11.0 - 12.0' No recovery; End of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-082
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.1' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.1 - 1.5' FILL: Brown silty sand, some fine to medium gravel, trace brick coal and glass, dry, loose | | Sample collected 124-SB-082-0002 from 0.5-1.0' @ 10:30 |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown silty sand, some wood, trace clinker and brick, moist, firm | | Sample collected 124-SB-082-0204 from 2.0-2.5' @ 10:35 |
| | 3.0 | | | | | 2.5 - 4.0' FILL: No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 4.5' FILL: Reddish brown fine sand, trace gravel, wet, firm | 0 | |
| | 5.0 | | | | | 4.5 - 5.3' FILL: Dark brown sandy silt, trace wood, wet | | Sample collected 124-SB-082-0406 from 4.5-5.0' @ 10:40 |
| | 6.0 | | | | | 5.3 - 6.5' FILL: Greyish brown fine to medium sand, wet | | Sample collected 124-SB-082-0608 from 6.0-6.5' @ 10:45; DUP @ 10:47 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3 | | 8.0 - 8.8' FILL: Reddish brown silt, trace fine sand, wet, firm | 0 | |
| | 9.0 | | | | | 8.8 - 9.5' OL: Greyish brown silty clay, some organics, wet, firm | | Sample collected 124-SB-082-0810 from 8.5-9.0' @ 10:50 |
| | 10.0 | | | | | 9.5 - 11.0' PT: Brown moist peat | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; End of boring @ 12.0' bgs | | Sample collected 124-SB-082-1012 from 10.0-10.5' @ 10:55 |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-083
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.1' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.1 - 2.5' FILL: Brown sandy silt, mottling of brown and orange silt, trace brick, fine to medium gravel, wood and glass, moist, loose | | Sample collected 124-SB-083-0002 from 0.5-1.0' @ 11:00 |
| | 2.0 | | | | | | | Sample collected 124-SB-083-0204 from 2.0-2.5' @ 11:05 |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 4.2' FILL: Concrete | 0 | Sample collected 124-SB-083-0406 from 4.0-4.5' @ 11:10 |
| | 5.0 | | | | | 4.2 - 4.8' FILL: Dark brown silt, trace fine sand and fine to medium gravel, wet, loose | | |
| | 6.0 | | | | | 4.8 - 6.0' FILL: Dark brown silt, some clinker, trace fine to medium gravel, very wet, very loose | | Sample collected 124-SB-083-0608 from 6.0-6.5' @ 11:15 |
| | 7.0 | | | | | 6.0 - 6.5' FILL: Brown fine to coarse sand, some silt, wet, loose | | |
| | 8.0 | S-3 | NA | 3 | | 6.5 - 8.0' No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 8.5' FILL: Brown fine to coarse sand, some silt, wet, loose | | Sample collected 124-SB-083-0810 from 8.5-9.0' @ 11:20 DUP @ 11:22 |
| | 10.0 | | | | | 8.5 - 9.5' FILL: Reddish brown silty sand, trace organics, wet, firm | | |
| | 11.0 | | | | | 9.5 - 11.0' OL: Greyish brown silty clay, some organics, wet, firm | | Sample collected 124-SB-083-1012 from 10.0-10.5' @ 11:25 |
| | 12.0 | | | | | 9.7 - 11.0' PT: Brown moist peat | | |
| | | | | | | 11.0 - 12.0' No recovery; End of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** **124-SB-084**
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | HOLD ALL SAMPLES |
| | | | | | | 0.3 - 0.5' FILL: Brown sandy silt, some fine to medium gravel, trace brick and coal, dry, loose | | Sample collected 124-SB-084-0002 from 1.0-1.5' @ 11:30 |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Concrete | 7.9 | |
| | | | | | | 0.8 - 1.5' FILL: Dark brown silt, trace brick and fine gravel | | Slight petroleum odor |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brown silt, some organics | | |
| | | | | | | 2.0 - 2.5' FILL: Brick | | Sample collected 124-SB-084-0204 from 3.0-3.5' @ 11:35 |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Brown silty sand | 5.1 | |
| | | S-2 | NA | 3 | | 3.0 - 3.8' FILL: Dark brown silt, trace coal | 0 | Slight petroleum odor |
| | 4.0 | | | | | 3.8 - 4.0' No recovery | | Sample collected 124-SB-084-0406 from 4.5-5.0' @ 11:40 |
| | | | | | | 4.0 - 4.5' FILL: Dark brown sandy silt, trace brick | | |
| | 5.0 | | | | | 4.5 - 4.7' FILL: Concrete | | |
| | | | | | | 4.7 - 4.8' FILL: Dark brown silt, some wood and coarse gravel, very wet, very loose | | Sample collected 124-SB-084-0608 from 6.0-6.5' @ 11:45 |
| | 6.0 | | | | | 4.8 - 7.0' FILL: Reddish brown fine to coarse sand, lenses of clayey silt (25%), wet, firm | | |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 7.0 | | | | | 8.0 - 9.5' FILL: Reddish brown fine to coarse sand, lenses of clayey silt (25%), wet, firm | | |
| | | S-3 | NA | 3 | | 9.5 - 10.0' OL: Greyish brown silty clay, some organics, wet, firm | 0 | Sample collected 124-SB-084-0810 from 9.0-9.5' @ 11:50 |
| | 8.0 | | | | | 10.0 - 11.0' PT: Brown moist peat | | |
| | | | | | | 11.0 - 12.0' No recovery; End of Boring @ 12.0' bgs | | Sample collected 124-SB-084-1012 from 10.5-11.0' @ 11:55 |
| | 9.0 | | | | | | | |
| | | | | | | | | |
| | 10.0 | | | | | | | |
| | | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-085
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' ASPHALT: Asphalt and gravel | 0 | HOLD ALL SAMPLES |
| | | | | | | 0.1 - 0.5' FILL: Fine to medium gravel, some brown silt, dry, loose | | |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Degraded brick | | Sample collected 124-SB-085-0002 from 1.0-1.5' @ 10:00 |
| | | | | | | 0.8 - 1.5' FILL: Light brown fine silty sand, dry, loose | | |
| | 2.0 | | | | | | 0 | |
| | | | | | | 1.5 - 3.5' FILL: Dark brown silty clay, trace organics, coal, brick, and fine sand, moist, firm | | |
| | 3.0 | | | | | | | Sample collected 124-SB-085-0204 from 2.5-3.0' @ 10:05 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.25 | | 4.0 - 5.5' FILL: Dark brown silty clay, trace organics, coal, brick, and some fine sand, wet, firm | 0 | |
| | | | | | | | | Sample collected 124-SB-085-0406 from 4.5-5.0' @ 10:10 |
| | 5.0 | | | | | | | |
| | | | | | | 5.5 - 6.0' FILL: Dark brown clayey silt, trace organics, very wet, loose | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Brown fine to medium sand, lenses of silty clay, trace organics and fine to medium gravel, wet, loose | 0 | Sample collected 124-SB-085-0608 from 6.5-7.0' @ 10:15 |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' FILL: No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 9.0' FILL: Reddish brown sandy silt, wet, firm | 0 | |
| | | | | | | | | Sample collected 124-SB-085-0810 from 8.5-9.0' @ 10:20 |
| | 9.0 | | | | | 9.0 - 9.8' OL: Brown silty clay, some organics | | |
| | 10.0 | | | | | 9.8 - 10.5' PT: Brown moist peat | 0 | |
| | | | | | | 10.5 - 12.0' No recovery; end of Boring @ 12.0' bgs | | Sample collected 124-SB-085-0810 from 10.0-10.5' @ 10:25 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-086
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10.0 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' ASPHALT: Asphalt and gravel | 0 | HOLD ALL SAMPLES |
| | | | | | | 0.1 - 1.0' FILL: Reddish brown silt, some fine sand and fine to medium gravel | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Brown sandy silt, trace brick, moist, firm | | Sample collected 124-SB-086-0002 from 0.5-1.0' @ 9:35 |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Dark brown clayey silt, trace clinker, brick, organics, and fine gravel, moist, firm | 0 | |
| | 3.0 | | | | | | | Sample collected 124-SB-086-0204 from 3.0-3.5' @ 9:40 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3 | | 4.0 - 4.5' FILL: Dark brown silty clay, trace organics | 0 | |
| | | | | | | 4.5 - 5.5' FILL: Reddish brown silt, trace fine sand, wet, firm | | Sample collected 124-SB-086-0406 from 4.5-5.0' @ 9:45 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Brown fine to medium and trace silt, wet, loose | 0 | |
| | 7.0 | | | | | | | Sample collected 124-SB-086-0608 from 6.5-7.0' @ 9:50 |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2 | | 8.0 - 9.0' FILL: Reddish brown silty clay | 0 | |
| | 9.0 | | | | | 9.0 - 9.5' OL: Dark brown silty clay, some organics | | Sample collected 124-SB-086-0810 from 9.5-10.0' @ 9:55 |
| | 10.0 | | | | | 9.5 - 10.0' PT: Brown moist peat; end of boring @ 10.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-087
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 9.5 ft bgs
**GW DEPTH:** 3.75ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | HOLD ALL SAMPLES |
| | | | | | | 0.3 - 1.0' FILL: Brown sandy silt, trace brick, fine to medium gravel and coal, dry, loose | | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Medium brown silt, trace fine sand, brick and fine gravel, moist, loose | | Sample collected 124-SB-087-0002 from 1.0-1.5' @ 9:10 |
| | 2.0 | | | | | | 0 | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Greyish brown silty clay, trace organics, wet, firm | | Sample collected 124-SB-087-0204 from 3.0-3.5' @ 9:15 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.3' FILL: Greyish brown silty clay, trace organics, wet, firm | 0 | |
| | | | | | | 4.3 - 6.5' FILL: Clinker (80%), some brown fine to coarse sand, trace coal, wet, loose | | Sample collected 124-SB-087-0406 from 5.0-5.5' @ 9:20 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | 0 | |
| | | | | | | 6.5 - 6.8' FILL: Dark brown silt, trace dark brown fine sand and clay, wet, loose | | Sample collected 124-SB-087-0608 from 6.5-7.0' @ 9:25 |
| | 7.0 | | | | | 6.8 - 7.0' OH: Dark brown clay, some organics and trace silt | | |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 9.0' OL: Dark brown silty clay, some organics (30%), firm, wet | 0 | |
| | 9.0 | | | | | 9.0 - 9.5' PT: Brown moist peat; end of boring @ 9.5' bgs | | Sample collected 124-SB-087-0810 from 9.0-9.5' @ 9:30 |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-088
**DATE BEGAN:** 6/14/2010
**DATE FINISHED:** 6/14/2010
**INSPECTOR:** B. Senna/ M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** -10.0 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 4 | | 0.0 - 0.3' FILL: Asphalt and gravel | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Reddish brown sandy silt, some fine to medium gravel, trace brick | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Degraded brick | | |
| | | S-1 | | | | 1.5 - 2.5' FILL: Light brown fine sand, moist, firm | 0 | Sample collected 124-SB-088-0002 from 1.5-2.0' @ 12:00 |
| | 2.0 | | | | | | | |
| | | | | | | 2.5 - 4.0' FILL: Dark brown silty sand, some clinker, trace coal and brick, moist, firm | | |
| | 3.0 | S-2 | | | | | | Sample collected 124-SB-088-0204 from 3.0-3.5' @ 12:05 |
| | 4.0 | | NA | 4 | | 4.0 - 4.5' FILL: Brown silt, firm, dry | 0 | |
| | | | | | | 4.5 - 4.8' FILL: Brick | | |
| | 5.0 | S-3 | | | | 4.8 - 7.5' FILL: Dark brown silty fine to medium sand, some clinker, trace shells, brick and coal, very wet, firm | | Sample collected 124-SB-088-0406 from 5.0-5.5' @ 12:10 |
| | 6.0 | | | | | | 0 | |
| | | S-4 | | | | | | Sample collected 124-SB-088-0608 from 6.0-6.5' @ 12:15 |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' FILL: Reddish brown silt, trace fine sand, wet, firm | | |
| | 8.0 | | NA | 2 | | 8.0 - 9.0' OL: Dark brown silty clay,some organics (30%), firm, wet | 0 | |
| | 9.0 | S-5 | | | | 8.0 - 9.0' OL: Greyish brown silty clay | | Sample collected 124-SB-088-0810 from 9.0-9.5' @ 12:20 |
| | | | | | | 9.0 - 10.0' PT: Brown moist peat; End of boring @ 10.0' bgs | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124 | **PROJECT NO:** 3480050143 | **BORING ID:** 124-SB-089

**DATE BEGAN:** 6/14/2010 | **DATE FINISHED:** 6/14/2010 | **INSPECTOR:** B. Senna/ M. Daly

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 12.0 ft bgs | **GW DEPTH:** 4.5 ft bgs

**DRILLER:** G. Blewitt | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | HOLD ALL SAMPLES |
| | 1.0 | | | | | 0.3 - 0.8' FILL: Brown sandy silt, some brick and coal | | Sample collected 124-SB-089-0002 from 1.0-1.5' @ 12:25 |
| | 2.0 | | | | | 0.8 - 2.5' FILL: Reddish brown silt, some brick, trace fine to medium gravel | 0 | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Concrete with gravel | | Sample collected 124-SB-089-0204 from 2.5-3.0' @ 12:30 |
| | | | | | | 3.0 - 3.5' FILL: Wood and fine to medium gravel | 4.9 | Creosote odor |
| | 4.0 | S-2 | NA | 3 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Concrete | | Sample collected 124-SB-089-0406 from 4.5-5.0' @ 12:35 |
| | | | | | | 4.5 - 5.3' FILL: Dark brown sandy silt, trace organics and clay | | |
| | 6.0 | | | | | 5.3 - 7.0' FILL: Greyish brown fine to medium sand, lenses of clayey silt, wet, loose | 0 | Sample collected 124-SB-089-0608 from 6.0-6.5' @ 12:40 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3 | | 8.0 - 9.0' FILL: Greyish brown fine to medium sand, lenses of clayey silt, wet, loose | 0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Brown silty clay, some organics, moist, firm | | |
| | 10.0 | | | | | 9.0 - 9.8' FILL: Grey fine sand, trace organics, wet, loose | | Sample collected 124-SB-089-0810 from 9.5-10.0' @ 12:45 |
| | 11.0 | | | | | 9.8 - 10.9' OL: Greyish brown silty clay, trace organics, | | Sample collected 124-SB-089-0810 from 10.5-11.00' @ 12:50 |
| | | | | | | 10.9 - 11.0' PT: Brown moist peat | | |
| | 12.0 | | | | | 11.0 - 12.0' No recovery; end of boring @ 12.0' bgs | | |

PREPARED BY: MD

CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-090
**DATE BEGAN:** 8/18/10
**DATE FINISHED:** 8/18/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.3' FILL: Brown silty sand, very moist | | |
| | 1.0 | | | | | 1.3 - 2.3' FILL: Concrete | | |
| | 2.0 | | | | | 2.3 - 2.5' FILL: Dark brown silt, fine sand, shells, gravel, brick, moist | | |
| | | | | | | 2.5 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Dark brown silt, gravel, organics, very moist | 0 | |
| | | | | | | 4.5 - 5.0' FILL: Brick, coarse gravel | | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Dark brown silt, sand, medium to coarse gravel, wet | | |
| | | | | | | 5.5 - 7.5' FILL: Light brown fine to medium sand, wet | | Sample collected 124-SB-090-0608 from 6.5-7.0' @ 9:35 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery; end of boring at 8.0 ft. bgs. | | |
| | 8.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-091
**DATE BEGAN:** 5/25/10
**DATE FINISHED:** 5/25/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE: Concrete | 0 | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.5 - 1.5' Void | | |
| | 2.0 | | | | | 1.5 - 2.8' FILL: Dark brown fine to medium silty sand, trace coal; moderate dense; very wet | | |
| | 3.0 | | | | | 2.8 - 4.0' FILL: Brown fine to medium sand, some silt; loose | | |
| | 4.0 | S-2 | NA | 3 | | 4.0 - 6.9' FILL: Red brown silt, trace fine sand, trace brick, trace fine to medium gravel, trace clay; dense; moist | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.9 - 7.0' FILL: Green silty sand; COPR; wet | | |
| | 8.0 | S-3 | NA | 3.5 | | 7.0 - 8.0' FILL: No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 8.3' FILL: Green silty sand; COPR; wet | | |
| | 10.0 | | | | | 8.3 - 8.5' FILL: Red brown silty clay; wet | | |
| | 11.0 | | | | | 8.5 - 9.0' FILL: Brown silty sand; loose; wet | | |
| | 12.0 | S-4 | NA | 2.0 | | 9.0 - 11.0' FILL: Brown silt, some fine sand; very loose; very wet | 0 | |
| | 13.0 | | | | | 11.0 - 11.5' FILL: Green/yellow silt; COPR; firm; wet | | Sample collected 124-SB-091-1214 from 12.5-13.0' @ 13:10 |
| | 14.0 | | | | | 11.5 - 12.0' No recovery | | EOB at 14 ft bgs |
| | | | | | | 12.0 - 12.3' FILL: Brown silt; wet | | |
| | | | | | | 12.3 - 12.5' OL: Black silty clay | | |
| | | | | | | 12.5 - 14.0' PT: Brown peat; moist; end of boring @ 14.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-091R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 15.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE: Concrete | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' Void | | |
| | 2.0 | | | | | 1.5 - 2.8' FILL: Dark brown fine to medium silty sand, trace coal; moderate dense; very wet | | |
| | 3.0 | | | | | 2.8 - 4.0' FILL: Brown fine to medium sand, some silt; loose | | |
| | 4.0 | S-2 | NA | 3 | | 4.0 - 6.9' FILL: Red brown silt, trace fine sand, trace brick, trace fine to medium gravel, trace clay; dense; moist | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.9 - 7.0' FILL: Green silty sand; COPR; wet | | |
| | 8.0 | S-3 | NA | 3.5 | | 7.0 - 8.0' FILL: No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 8.3' FILL: Green silty sand; COPR; wet | | |
| | 10.0 | | | | | 8.3 - 8.5' FILL: Red brown silty clay; wet | | |
| | 11.0 | | | | | 8.5 - 9.0' FILL: Brown silty sand; loose; wet | | |
| | 12.0 | S-4 | NA | 3.0 | | 9.0 - 11.0' FILL: Brown silt, some fine sand; very loose; very wet | 0 | |
| | 13.0 | | | | | 11.0 - 11.5' FILL: Green/yellow silt; COPR; firm; wet | | |
| | 14.0 | | | | | 11.5 - 12.0' No recovery | | |
| | | | | | | 12.0 - 12.3' FILL: Brown silt; wet | | |
| | | | | | | 12.3 - 12.5' OL: Black silty clay | | Sample collected 124-SB-091R-1214 from 13.0-13.5' @ 7:15 |
| | | | | | | 12.5 - 14.0' PT: Brown peat; moist; end of boring @ 15.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-092
**DATE BEGAN:** 5/25/10
**DATE FINISHED:** 5/25/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE: Concrete | 0 | Boring elevation = 11.5' approximately 1.5' higher than surrounding grade |
| | 1.0 | | | | | 0.5 - 1.5' Void | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brown silty fine to medium sand, some brick, trace clay; dense; wet | | |
| | 3.0 | | | | | 2.0 - 3.5' FILL: Black fine to medium silty sand, trace clinker; dense; wet | | |
| | 4.0 | S-2 | NA | 2.5 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 6.5' FILL: Red brown clayey silt, trace fine sand, trace fine to medium gravel, trace brick; very dense moist | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.5' FILL: Yellow/green silt; COPR; Hard brown COPR from 9.4' - 9.5' bgs; wet | 0 | |
| | 9.0 | | | | | 9.5 - 9.8' FILL: Brown silt; dense; moist | | |
| | 10.0 | | | | | 9.8 - 10.5' FILL: Brown fine to medium sand; black staining at 10.0 - 10.5' bgs. | | Organic odor from 10.0 - 10.5' bgs. |
| | 11.0 | | | | | 10.5 - 11.4' FILL: Brown clayey silt | | |
| | 12.0 | S-4 | NA | 2.0 | | 11.4 - 11.5' FILL: Green/yellow silt; COPR | 0 | |
| | | | | | | 11.5 - 12.0' No recovery | | Sample collected 124-SB-092-1214 from 13.5-14.0' @ 13:40 |
| | 13.0 | | | | | 12.0 - 13.3' FILL: Green/yellow silt; COPR; very soft; very wet | | |
| | 14.0 | | | | | 13.3 - 13.5' OL: Black silty clay; loose; wet | | EOB at 14 ft bgs |
| | | | | | | 13.5 - 14.0' PT: Brown peat; moist; end of boring @ 14.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-092R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14.0 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE: Concrete | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' Void | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brown silty fine to medium sand, some brick, trace clay; dense; wet | | |
| | 3.0 | | | | | 2.0 - 3.5' FILL: Black fine to medium silty sand, trace clinker; dense; wet | | |
| | 4.0 | S-2 | NA | 2.5 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 6.5' FILL: Red brown clayey silt, trace fine sand, trace fine to medium gravel, trace brick; very dense moist | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.5' FILL: Yellow/green silt; COPR; Hard brown COPR from 9.4' - 9.5' bgs; wet | 0 | |
| | 9.0 | | | | | 9.5 - 9.8' FILL: Brown silt; dense; moist | | |
| | 10.0 | | | | | 9.8 - 10.5' FILL: Brown fine to medium sand; black staining at 10.0 - 10.5' bgs. | | Organic odor from 10.0 - 10.5' bgs. |
| | 11.0 | | | | | 10.5 - 11.4' FILL: Brown clayey silt | | |
| | 12.0 | S-4 | NA | 2.0 | | 11.4 - 11.5' FILL: Green/yellow silt; COPR | 0 | |
| | 13.0 | | | | | 11.5 - 12.0' No recovery | | |
| | 14.0 | | | | | 12.0 - 13.3' FILL: Green/yellow silt; COPR; very soft; very wet | | Sample collected 124-SB-092R-1314 from 13.5-14.0' @ 7:30 |
| | | | | | | 13.3 - 13.5' OL: Black silty clay; loose; wet | | |
| | | | | | | 13.5 - 14.0' PT: Brown peat; moist; end of boring @ 14.0' bgs | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-108
**DATE BEGAN:** 7/7/2008
**DATE FINISHED:** 7/7/08
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | Collect sample from 1.0-1.5' bgs @ 11:25 |
| | -1.0 | | | | | 0.5 - 3.0' FILL: Dark brown / Black silty sand (fine) with gravel (fine-coarse), some brick (fine-medium), wood, and crushed concrete (from 1.5-2.0' bgs); moist; light sheen from (2.0-3.0 ' bgs) | 0 | |
| | -2.0 | | | | | | 0 | |
| | | | | | | | 29.7 | Collect sample from 2.5-3.0' bgs @ 11:30 |
| | -3.0 | | | | | | 32.8 | |
| | | | | | | | 23.8 | |
| | -4.0 | | | | | 3.0 - 4.0' No recovery | | |
| | | 2 | NA | 2.5 | | 4.0 - 6.0' FILL: Dark brown silty sand (fine), some wood, shells, gravel (fine), slight sheen, wet @ 4.5' bgs | 12.4 | Collect sample from 4.5-5.0' bgs @ 11:35 |
| | -5.0 | | | | | | 9.8 | |
| | | | | | | | 14.8 | |
| | -6.0 | | | | | 6.0 - 6.5' FILL: Brown silt (fine) some gravel (fine-medium), lenses of sand (fine-medium), wet | 9.1 | |
| | | | | | | | 6.3 | Collect sample from 6.0-6.5' bgs @ 11:40 |
| | -7.0 | | | | | 6.5 - 8.0' No recovery | 0 | |
| | -8.0 | 3 | NA | 2.75 | | 8.0 - 10.5' FILL: Light brown sand (fine-medium) with lenses of red brown silt; wet | 0 | Collect sample from 8.5-9.0' bgs @ 11:45; DUP @ 11:50 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.5 - 10.8' FILL: Red brown silt; wet | | Collect sample from 10.0-10.5' bgs @ 11:55 |
| | -11.0 | | | | | 10.8 - 12.0' | | |
| | -12.0 | 4 | NA | 2.0 | | 12.0 - 14.0' PEAT: Dark brown peat; wet; end of boring at 14' | 0 | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-109
**DATE BEGAN:** 7/7/2008
**DATE FINISHED:** 7/7/08
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 1.5 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | Collect sample from 0.5-1.0' bgs @ 10:55 |
| | -1.0 | | | | | 0.3 - 0.8' FILL: Dark brown silty sand; dry | | |
| | -2.0 | | | | | 0.8 - 1.5' FILL: Gravel (coarse); dry | | |
| | -3.0 | | | | | 1.5 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.0 | | 4.0 - 5.0' FILL: Light brown silty sand (fine) with shells (fine) and gravel (fine); wet | 2.6<br>1.8 | Collect sample from 5.5-6.0' bgs @ 11:00 |
| | -5.0 | | | | | 5.0 - 6.0' FILL: Dark brown/black silty sand (fine) with yellow/white nodules; (COPR) from 5-6' bgs; wet | 2.9<br>0 | |
| | -6.0 | | | | | 6.0 - 7.0' FILL: Red/light brown sand (fine-medium) with lenses of red brown silt (fine), wet | | Collect sample from 6.5-7.0' bgs @ 11:05 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | 3 | NA | 3.5 | | 8.0 - 9.0' FILL: Light brown silt (fine) with sand (fine), wet | 0 | Collect sample from 8.5-9.0' bgs @ 11:10 |
| | -9.0 | | | | | 9.0 - 10.5' FILL: Light brown sand (fine-medium), wet | | |
| | -10.0 | | | | | | | Collect sample from 10.5-11' bgs @ 11:15 |
| | -11.0 | | | | | 10.5 - 11.5' FILL: Red brown clayey silt with trace shells (fine) and organics (fine), wet | | |
| | -12.0 | 4 | NA | 1.75 | | 11.5 - 12.0' No recovery | | |
| | -13.0 | | | | | 12.0 - 13.8' PT: Dark brown peat; moist | 0 | |
| | -14.0 | | | | | 13.8 - 14.0' No recovery; end of boring at 14' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-109A
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 20.0 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | |
| | -1.0 | | | | | 0.5 - 3.5' FILL: Brown silty sand (fine); trace gravel (coarse); dry to moist | 0 | |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | | 0 | 124-SB-109A_0002 collected from 2.5-3.0' bgs @ 08:25 |
| | -4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 5.0' FILL: Brown silty sand (fine); trace gravel (fine-medium); moist to wet | 0 | |
| | -6.0 | | | | | 5.0 - 6.5' FILL: Dark brown/black sand; trace gravel (fine-medium); medium stiff; wet | 0 | 124-SB-109A_0204 collected from 5.5-6.0' bgs @ 08:30 |
| | -7.0 | | | | | 6.5 - 8.0' FILL: Brown sand (fine-medium); wet | 0 | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.5' FILL: Brown silty clay; wet | 0 | |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | 9.5 - 11.0' FILL: Brown silty sand (medium); wet | 0 | |
| | -11.0 | | | | | 11.0 - 13.0' FILL: Brown silty clay; wet | 0 | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | |
| | -13.0 | | | | | 13.0 - 16.0' PT: Peat; meadow mat; organic material; moist | 0 | 124-SB-109A_0406 collected from 12.5-13.0' bgs @ 08:35 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | 0 | |
| | -16.0 | | | | | 16.0 - 17.0' PT: Peat; meadow mat; wet | 0 | 124-SB-109A_0608 collected from 15.5-16.0' bgs @ 08:40 |
| | -17.0 | | | | | 17.0 - 19.5' SM: Gray silty sand; wet | | 124-SB-109A_0810 collected from 17.0-17.5' bgs @ 08:45 |
| | -18.0 | | | | | | | |
| | -19.0 | | | | | 19.5 - 20.0' No recovery; end of boring at 20.0' | | 124-SB-109A_1820 collected from 19.0-19.5' |
| | -20.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-110
**DATE BEGAN:** 7/7/2008
**DATE FINISHED:** 7/7/08
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** G Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 3.5' FILL: Light brown silty sand (fine) with gravel (fine-coarse), glass (fine-medium), brick (fine-medium); potential COPR from 3.0-3.5'; dry | 0 | 124-SB-110-0002 from 1.0-1.5' bgs @ 10:15 |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | 124-SB-110-0204 from 3.0-3.5' bgs @ 10:20 |
| | -3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Light brown silty sand (fine) with gravel (fine-coarse), glass (fine-medium), brick (fine-medium); moist | 0 | 124-SB-110-0406 from 4.0-4.5' bgs @ 10:25 |
| | -5.0 | | | | | 4.5 - 5.0' FILL: Crushed concrete | | |
| | -6.0 | | | | | 5.0 - 7.0' FILL: Red brown silt (fine) with gravel (fine), wood (fine), coal (fine), and green/olive nodules, (COPR); moist | | 124-SB-110-0608 from 7.0-7.5' bgs @ 10:30 |
| | -7.0 | | | | | 7.0 - 7.5' FILL: Light brown clayey silt with white and green nodules, (COPR), and organic material; moist | | |
| | -8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No recovery | 0 | 124-SB-110-0810 from 8..0-8.5' bgs @ 10:35 |
| | -9.0 | | | | | 8.0 - 9.0' FILL: Light brown sand (fine) with trace shells (fine) and gravel (fine) | | |
| | -10.0 | | | | | 9.0 - 11.0' FILL: Dark brown saturated silt (fine) with trace sand (fine) | | 124-SB-110-1012 from 11-11.5' bgs @ 10:40 |
| | -11.0 | | | | | 11.0 - 12.0' FILL: Green/yellow silt, (COPR) | | |
| | -12.0 | S-4 | NA | 2.0 | | 12.0 - 12.3' FILL: Black silt (fine), (COPR), and some organic material | 0 | 124-SB-110-1214 from 12-12.5' bgs @ 10:45 |
| | -13.0 | | | | | 12.3 - 14.0' PT: Dark brown peat; end of boring at 14' | | |
| | -14.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-111
**DATE BEGAN:** 7/8/2008
**DATE FINISHED:** 7/8/2008
**INSPECTOR:** E. Jackson
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | Advance adjacent boring 124-SB-011A to obtain sufficient recovery for samples, see log for details |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silt and coarse sand; moist | | |
| | -1.0 | | | | | 1.0 - 2.0' FILL: Yellow brown/light brown silt and clay, some fine gravel; moist | | |
| | -2.0 | | | | | 2.0 - 2.3' FILL: Concrete | | |
| | -3.0 | | | | | 2.3 - 3.5' FILL: Light grey/brown medium to coarse sand, trace silt, some fine-medium angular gravel, very firm, moist | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 1 | | 4.0 - 5.0' FILL: Brown fine to coarse gravel and sand, trace silt and clay, wet | 0 | |
| | -5.0 | | | | | 5.0 - 8.0' No Recovery | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | 3 | NA | 0 | | 8.0 - 12.0' No Recovery, End of boring at 12' | 0 | |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-011A
**DATE BEGAN:** 7/8/2008
**DATE FINISHED:** 7/8/2008
**INSPECTOR:** E. Jackson
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | Collect sample from 1.0-1.5' bgs @ 13:20 |
| | -1.0 | | | | | 0.5 - 1.0' FILL: Dark brown silt and coarse sand | | |
| | -2.0 | | | | | 1.0 - 2.0' FILL: Yellow brown/light brown silt and clay, some fine gravel, bright green mottling, predominantly in gravel from 1-1.25' bgs (COPR); moist | | Collect sample from 2.5-3.0 @ 13:24 |
| | -3.0 | | | | | 2.0 - 2.3' FILL: Concrete | | |
| | -4.0 | 2 | NA | 3.0 | | 2.3 - 3.5' FILL: Light grey/brown medium to coarse sand, trace silt, some fine-medium angular gravel, very firm, moist | 0 | Collect sample from 4.5-5.0' bgs @ 13:28 |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -6.0 | | | | | 4.0 - 4.5' FILL: Light brown silty sand, some coarse angular gravel, loose, saturated | | Collect sample from 6.0-6.5' bgs @ 13:30 |
| | -7.0 | | | | | 4.5 - 5.3' FILL: Brown silty sand, trace angular gravel; wet | | |
| | -8.0 | 3 | NA | 0 | | 5.3 - 6.5' FILL: Light/yellow brown silty clay, some sand, COPR @ 6-6.5' bgs, saturated | 0 | |
| | -9.0 | | | | | 6.5 - 7.0' FILL: Brown silt and fine sand, firm, wet | | |
| | -10.0 | | | | | 7.0 - 12.0' No Recovery | | |
| | -11.0 | | | | | | | |
| | -12.0 | 4 | NA | 2.0 | | 12.0 - 14.0' PT: Peat; End of boring at 14' bgs | 0 | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-116
**DATE BEGAN:** 7/29/08
**DATE FINISHED:** 7/29/08
**INSPECTOR:** Brian Senna/Will Lang
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' TOPSOIL: Light brown topsoil | 0 | |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Dark brown silty sand (fine); some gravel (fine-coarse) and glass; moist | 0 | |
| | -2.0 | | | | | 1.5 - 3.0' FILL: Brown sand (fine-medium); moist | 0 | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | 0 | |
| | -4.0 | S-2 | NA | 2.5 | | 4.0 - 5.0' FILL: brown sand (fine-medium); moist | 0 | |
| | -5.0 | | | | | 5.0 - 5.5' FILL: Red brown/ light brown sand (fine-medium); wet at 5.5' | 0 | |
| | -6.0 | | | | | 5.5 - 7.5' FILL: Light gray sand (fine-medium); wet | 0 | |
| | -7.0 | | | | | 7.5 - 8.0' No recovery | 0 | |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 10.0' FILL: Light brown sand (fine); wet | 0 | |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | 10.0 - 10.8' FILL: Dark brown clayey silt (fine); some organic material, wet | 0 | |
| | -11.0 | | | | | 10.8 - 11.0' PT: Dark brown peat; moist | 0 | |
| | -12.0 | S-4 | NA | 3.5 | | 11.0 - 12.0' No recovery | 0 | |
| | -13.0 | | | | | 12.0 - 14.8' PT: Dark brown peat; moist | 0 | |
| | -14.0 | | | | | | 0 | 124-SB-116_1416 collected from 14.5-15.0' bgs @ 14:45 |
| | -15.0 | | | | | 14.8 - 15.5' SP: Light brown/red brown sand (fine); some organic material; trace silt; moist | 0 | 124-SB-116DP_1416 collected from 14.5-15.0' bgs @ 14:50 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16.0' | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell SA-6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-117A
**DATE BEGAN:** 3/25/2011
**DATE FINISHED:** 3/25/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | NA | 3.75 | | 0.0 - 0.5' FILL: Dark grey fine to medium silty sand, some clinker; dense, wet | 0 | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | 0.5 - 3.8' FILL: Reddish brown silt, some fine to medium gravel and brick, trace coal; dense, moist | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | Sample collected 124-SB-117A-0304 from 3.0-3.5' @ 10:15 |
| | 4.0 | R-2 | NA | 3.5 | | 3.8 - 4.0' No recovery | | |
| | | | | | | 4.0 - 4.5' GW: Gravel | 0 | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Greenish grey silt; soft, wet (COPR) | | Sample collected 124-SB-117A-0405 from 4.5-5.0' @ 10:20 |
| | 6.0 | | | | | 5.0 - 6.5' FILL: Greyish brown fine to medium sand; loose, wet | | Sample collected 124-SB-117A-0506 from 5.5-6.0' @ 10:25 |
| | 7.0 | | | | | 6.5 - 7.5' FILL: Reddish brown silt; stiff, wet | | Sample collected 124-SB-117A-0608 from 7.0-7.5' @ 10:30 |
| | 8.0 | R-3 | NA | 2.0 | | 7.5 - 8.0' No recovery | | |
| | | | | | | 8.0 - 9.0' FILL: Greyish brown fine silty sand | 0 | |
| | 9.0 | | | | | 9.0 - 9.5' OL: Dark grey organic silt | | |
| | 10.0 | | | | | 9.5 - 10.0' PT: Peat; end of boring @ 10.0' | | EOB at 10 ft bgs |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell SA-6 South

**LOCATION:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-121A
**DATE BEGAN:** 3/25/2011
**DATE FINISHED:** 3/25/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | NA | 3.75 | | 0.0 - 0.3' FILL: Orange red fine to coarse sand | 0 | Strong creosote odor |
| | | | | | | 0.3 - 3.3' FILL: Dark grey fine to coarse silty sand, some fine to medium gravel, trace coal and brick; dense, moist | | Boring elevation = 10.1' approximately 0.5' higher than surrounding grade |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.3 - 3.8' FILL: Reddish brown silt, gravel at bottom; stiff, moist | | |
| | 4.0 | R-2 | NA | 3.5 | | 3.8 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 4.5' FILL: Dark grey fine sandy silt | | |
| | | | | | | 4.5 - 5.0' FILL: Reddish brown silt; stiff, moist | | Sample collected 124-SB-121A-0405 from 4.5-5.0' @ 10:35 |
| | 5.0 | | | | | 5.0 - 5.3' FILL: Greyish green silt (COPR); soft, moist | | |
| | | | | | | 5.3 - 7.3' FILL: Brown fine to medium sand, trace fine gravel; loose, wet | | Sample collected 124-SB-121A-0506 from 5.0-5.5' @ 10:40 |
| | 6.0 | | | | | | | Rotten egg odor @ 7.0' |
| | 7.0 | | | | | 7.3 - 7.5' FILL: Dark grey silt, soft; wet | | Sample collected 124-SB-121A-0608 from 7.0-7.5' @ 10:45 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | NA | 2.0 | | 8.0 - 8.5' FILL: Brown sandy silt; loose, wet | 0 | |
| | | | | | | 8.5 - 9.5' OH: Brown clayey silt; soft, wet | | |
| | 9.0 | | | | | | | |
| | | | | | | 9.5 - 10.0' PT: Peat; end of boring @ 10.0' | | EOB at 10 ft bgs |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-122
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.5 - 3.0' FILL: Dark brown silty sand, gravel, shells, glass | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown COPR | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Light green COPR | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 11.0' FILL: Light green COPR | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.3' OL: Black clayey silt | | Sample collected 124-SB-122-1012 from 11.0-11.5' @ 8:35 |
| | | | | | | 11.3 - 11.5' PT: Brown peat; moist | | |
| | 12.0 | S-4 | NA | 1.0 | | 11.5 - 12.0' No recovery | 0 | Sample collected 124-SB-122-1214 from 12.0-12.5' @ 8:40 |
| | 13.0 | | | | | 12.0 - 13.0' PT: Brown peat; moist | | |
| | 14.0 | | | | | 13.0 - 14.0' No recovery; end of boring at 14.0 ft. bgs. | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-123
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 6.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.5 - 3.0' FILL: Red brown silt, gravel, wood | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Red brown/light brown silt, fine sand, layers of gravel throughout; wet at 6.5' bgs. | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 10.0' FILL: Light brown silt; wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.0' FILL: Green COPR; wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' PT: Brown peat; moist | 0 | Sample collected 124-SB-123-1214 from 12.5-13.0' @ 9:10 |
| | 13.0 | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0 ft. bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-124
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 6.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.8' FILL: Brown silty sand, fine to coarse gravel | 0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown silt, gravel; moist | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Light brown silt, gravel; moist | 0 | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Brown clayey silt; soft | | |
| | 6.0 | | | | | 6.0 - 6.3' FILL: White COPR; soft | | |
| | | | | | | 6.3 - 7.0' FILL: Red brown/light brown fine to medium sand; wet at 6.5' bgs. | | Sample collected 124-SB-124-0608 from 6.5-7.0' @ 9:25 |
| | 7.0 | | | | | 7.0 - 8.0' FILL: No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown/red brown clayey silt, lenses of fine to medium sand, shells; soft | 0 | Sample collected 124-SB-124-0810 from 8.5-9.0' @ 9:30 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 124-SB-124-1012 from 10.5-11.0' @ 9:35 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 12.5' OL: Dark brown clayey silt, trace shells, heavy organics | 0 | Sample collected 124-SB-124-1214 from 12.0-12.5' @ 9:40 |
| | 13.0 | | | | | 12.5 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-125
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.5 - 2.5' FILL: Dark brown silt, gravel, trace wood | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Light brown fine to coarse sand, concrete, gravel | | |
| | 4.0 | S-2 | NA | 2.5 | | 3.0 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Black silty sand, wood; wet | | |
| | 6.0 | | | | | 5.0 - 6.5' FILL: Light brown silt, fine sand; saturated | | |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.5' FILL: Light brown silt, fine sand; saturated | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 11.0' OL: Brown clayey silt, organics; soft | | |
| | 11.0 | | | | | 11.0 - 11.5' PT: Brown peat; moist | | Sample collected 124-SB-125-1012 from 11.0-11.5' @ 11:55 |
| | 12.0 | S-4 | NA | 2.0 | | 11.5 - 12.0' No recovery | 0 | |
| | 13.0 | | | | | 12.0 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | | Sample collected 124-SB-125-1214 from 12.0-12.5' @ 12:00 |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-126
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Dark brown silty sand, brick | | |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Concrete | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Dark brown silty sand, gravel, coal, glass | | |
| | 4.0 | S-2 | NA | 2.5 | | 3.0 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.5' FILL: Dark brown silty sand, gravel, coal, glass | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Light brown silt, fine sand; wet | | Sample collected 124-SB-126-0608 from 6.0-6.5' @ 12:15; DUP at 12:17 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.5' FILL: Light brown silt, fine to medium sand; wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 11.0' OL: Dark brown clayey silt, heavy organics | | Sample collected 124-SB-126-1012 from 10.5-11.0' @ 12:20 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | 0 | Sample collected 124-SB-126-1214 from 12.0-12.5' @ 12:25 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Site 124
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-127
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | | Begin sampling at 8.0' bgs. |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-1 | NA | 3.5 | | 8.0 - 9.5' FILL: Light brown clayey silt; soft; wet | 0 | Sample collected 124-SB-127-0810 from 8.0-8.5' @ 15:05 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 11.0' FILL: Red brown/light brown clayey silt | | |
| | 11.0 | | | | | 11.0 - 11.5' OL: Light brown/olive clayey silt, organics | | Sample collected 124-SB-127-1012 from 11.0-11.5' @ 15:10 |
| | 12.0 | S-2 | NA | 2.0 | | 11.5 - 12.0' No recovery<br>12.0 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | 0 | Sample collected 124-SB-127-1214 from 12.5-13.0' @ 15:15 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 124
**PROJECT NO:** 3480
**BORING ID:** 124-SB-128
**DATE BEGAN:** 3/21/11
**DATE FINISHED:** 3/21/11
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** 7730 DT
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | NA | | 0.0 - 14.0' See Boring Log 124-SB-34 for Details | | Sample collected 124-SB-128-1213 from 12.5-13.0 bgs at 14:35 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: KK
CHECKED BY: TG

# Honeywell SA-6 South

**LOCATION:** Site 124 - Cordova Property
**PROJECT NO:** 3480050143
**BORING ID:** 124-SB-129
**DATE BEGAN:** 3/25/2011
**DATE FINISHED:** 3/25/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and concrete | 0 | Initial refusal @ 2.0'. Moved 1.0' south, north, and east but encountered refusal in all attempts. Moved boring location 10' north and advanced to completion depth. |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Reddish brown sandy silt, some brick and fine to medium gravel; very dense, dry | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Dark brown silt, trace fine gravel; dense, dry | | |
| | 3.0 | | | | | 2.0 - 2.3' FILL: Concrete | | |
| | 4.0 | | | | | 2.3 - 3.0' FILL: Fine to coarse brown sand, some brick, sandstone, green silt in tip (possible COPR) | | |
| | 4.0 | R-1 | NA | 2.0 | | 3.0 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Fine to medium gravel, some fine to medium brown sand and brick; wet | | |
| | 6.0 | | | | | 5.0 - 6.0' FILL: Dark grey sandy silty, some clay; dense, wet | | |
| | 7.0 | | | | | 6.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | NA | 3.0 | | 8.0 - 9.0' FILL: Brown fine to medium sand; loose, wet | 0 | |
| | 9.0 | | | | | 9.0 - 9.8' FILL: Brown silt; soft, wet | | |
| | 10.0 | | | | | 9.8 - 10.0' FILL: Greenish grey silt; soft, wet (COPR) | | Sample collected 124-SB-129-1012 from 10.5-11.0' @ 12:00 |
| | 11.0 | | | | | 10.0 - 10.5' FILL: Brown fine to coarse sand; loose, wet | | |
| | 12.0 | | | | | 10.5 - 11.0' OH: Brown silt; soft, wet | | |
| | | | | | | 11.0 - 12.0' No recovery; end of boring @ 12.0' | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 124-SB-130
**DATE BEGAN:** 11/3/2011
**DATE FINISHED:** 11/3/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | | | | | | | |
| | | | 2 | 2.0 | | 8.0 - 9.0' FILL: COPR | N/A | Location HSA-1 on sampling table. Augered to 8 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 9.0 | | 1 | | | 9.0 - 9.5' OH: Black silt, some clay, trace organics | | |
| | | | 1 | | | 9.5 - 11.5' PT: Dark brown peat | | |
| | 10.0 | | 3 | 2.0 | | | N/A | Collected 124-SB-130-1011 from 10.0-10.5 ft bgs @ 10:15 |
| | | | 4 | | | | | |
| | 11.0 | | 4 | | | | | |
| | | | 8 | | | 11.5 - 12.0' SP: Dark brown fine to medium sand; wet, loose; end of boring @ 12.0' bgs | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 124-SB-131
**DATE BEGAN:** 11/3/2011
**DATE FINISHED:** 11/3/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | | 3 | 2.0 | | 8.0 - 9.8' FILL: Greenish grey COPR | N/A | Location HSA-2 on sampling table. Augered to 8 ft bgs before sampling. |
| | | | 2 | | | | | |
| | 9.0 | | 4 | | | | | |
| | | | 3 | | | | | |
| | 10.0 | | 1 | 2.0 | | 9.8 - 10.5' OH: Black silt, some clay and organic material; plastic, wet | N/A | |
| | | | 1 | | | 10.5 - 14.0' PT: Dark brown peat; end of boring @ 14.0' bgs | | |
| | 11.0 | | 1 | | | | | Collected 124-SB-131-1112 from 11.0-11.5 ft bgs @ 11:05 |
| | | | 3 | | | | | |
| | 12.0 | | NR | 2.0 | | | N/A | Collected 124-SB-131-1213 from 12.0-12.5 ft bgs @ 11:10 |
| | | | NR | | | | | |
| | 13.0 | | NR | | | | | |
| | | | NR | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 124-SB-132
**DATE BEGAN:** 11/3/2011
**DATE FINISHED:** 11/3/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 1 | 2.0 | | 10.0 - 10.8' FILL: COPR | N/A | Location HSA-3 on sampling table. Augered to 8 ft bgs and augered 2 additional ft through COPR before sampling. |
| | | | 1 | | | | | |
| | | | | | | 10.8 - 11.0' OH: Black silt, some clay | | |
| | 11.0 | | 2 | | | 11.0 - 12.0' PT: Very dark brown peat | | |
| | | | 5 | | | | | |
| | 12.0 | | 1 | 2.0 | | 12.0 - 14.0' PT: Dark brown peat | N/A | Collected 124-SB-132-1213 from 12.0-12.5 ft bgs @ 12:20 |
| | | | 3 | | | | | |
| | 13.0 | | 6 | | | | | |
| | | | 7 | | | | | |
| | 14.0 | | 2 | 0.0 | | 14.0 - 16.0' No recovery; wood in tip; end of boring @ 16.0' bgs | N/A | |
| | | | 7 | | | | | |
| | 15.0 | | 54 | | | | | |
| | | | 28 | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 124-SB-133
**DATE BEGAN:** 11/3/2011
**DATE FINISHED:** 11/3/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 1 | 2.0 | | 10.0 - 10.8' FILL: COPR | N/A | Location HSA-6 on sampling table. Augered to 8 ft bgs and augered 2 additional ft through COPR before sampling. |
| | | | 1 | | | | | |
| | | | | | | 10.8 - 11.0' OH: Black silt, some clay | | |
| | 11.0 | | 2 | | | 11.0 - 12.0' PT: Dark brown peat | | |
| | | | 4 | | | | | |
| | 12.0 | | 2 | 2.0 | | 12.0 - 15.5' PT: Very dark brown peat | N/A | Collected 124-SB-133-1213 from 12.0-12.5 ft bgs @ 14:10 |
| | | | 2 | | | | | |
| | 13.0 | | 3 | | | | | |
| | | | 4 | | | | | |
| | 14.0 | | 2 | 2.0 | | | N/A | |
| | | | 6 | | | | | |
| | 15.0 | | 17 | | | | | |
| | | | 11 | | | 15.5 - 17.0' SP: Grey fine to medium sand; loose, wet | | Collected 124-SB-133-1416 from 15.5 - 16.0 ft bgs @ 14:15 |
| | 16.0 | | 9 | 2.0 | | | N/A | |
| | | | 12 | | | | | |
| | 17.0 | | 19 | | | 17.0 - 18.0' SW: Reddish brown fine to coarse sand; loose, wet; end of boring @ 18.0' bgs | | Collected 124-SB-133-1618 from 17.0 - 17.5 ft bgs @ 14:20 |
| | | | 17 | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 124-SB-134
**DATE BEGAN:** 11/3/2011
**DATE FINISHED:** 11/3/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 5 | 2.0 | | 10.0 - 11.5' FILL: COPR | N/A | Location HSA-5 on sampling table. Augered to 8 ft bgs and augered 2 additional ft through COPR before sampling. |
| | | | 13 | | | | | |
| | 11.0 | | 16 | | | | | |
| | | | 16 | | | 11.5 - 11.8' OH: Black silt, some clay | | |
| | | | | | | 11.8 - 12.0' PT: Brown peat | | |
| | 12.0 | | 3 | 2.0 | | 12.0 - 14.0' PT: Very dark brown peat; end of boring @ 14.0' bgs | N/A | Collected 124-SB-134-1213 from 12.0-12.5 ft bgs @ 15:30 |
| | | | 5 | | | | | |
| | 13.0 | | 6 | | | | | |
| | | | 8 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 124-SB-135
**DATE BEGAN:** 11/11/2011
**DATE FINISHED:** 11/11/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 4 | 1.5 | | 10.0 - 12.5' FILL: Grayish brown fine to medium sand, trace silt, some lenses of clayey silt from 11.0'; loose, wet | N/A | Location HSA-4 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 2 | | | | | |
| | 11.0 | | 4 | | | | | |
| | | | 7 | | | | | |
| | 12.0 | | 3 | 2.0 | | | N/A | |
| | | | 3 | | | 12.5 - 14.0' PT: Very dark gray (5Y 3/1) peat from 12.5-12.7'; dark brown (10YR 3/3) peat from 12.7'; medium stiff, crumbly, moist; end of boring at 14' | | Collected 124-SB-135-1213 from 12.5-13.0 ft bgs @ 8:45 |
| | 13.0 | | 5 | | | | | Collected 124-SB-135-1314 from 13.0-13.5 ft bgs @ 8:50 |
| | | | 8 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 124-SB-136
**DATE BEGAN:** 1/17/2012
**DATE FINISHED:** 1/17/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57, freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | S-1 | 4 | 0.7 | | 10.0 - 10.7' FILL: Grayish brown fine to medium sand, trace silt; loose, wet | N/A | Location HSA-8 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 4 | | | 10.7 - 12.0' No recovery | | |
| | -11.0 | | 4 | | | | | Note: Concrete was 4" thick and therewas a 14" void to the top of soil. Grade is top of concrete |
| | | | 3 | | | | | |
| | -12.0 | S-2 | 3 | 2.0 | | 12.0 - 12.3' FILL: Grayish brown fine to medium sand, trace silt; very loose, wet | N/A | Collected 124-SB-136-1213 from 12.5-13.0 ft bgs @ 10:40 |
| | | | 1 | | | 12.3 - 12.6' OH: Black (2.5Y 2.5/1) silt and clay, trace fine sand and organic material; yellow clay (COPR) mixed in from 12.3-12.4' bgs; soft, wet | | |
| | -13.0 | | 2 | | | | | Collected 124-SB-136-1314 from 13.0-13.5 ft bgs @ 10:45 (HOLD) |
| | | | 4 | | | 12.6 - 14.0' PT: Dark olive brown (2.5Y/ 3/3) peat, some clay; soft wet; end of boring @ 14.0' bgs | | |
| | -14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 124-SB-137
**DATE BEGAN:** 1/17/2012
**DATE FINISHED:** 1/17/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57, freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-1 | 1<br>2<br>1<br>2 | 2.0 | | 12.0 - 13.4' FILL: Yellow clay (COPR); soft, wet<br>13.4 - 13.8' OH: Black (2.5YR 2.5/1) silt, some clay, trace organic material; soft, wet<br>13.8 - 14.0' PT: Dark olive brown (2.5 YR 3/3) peat; end of boring @ 14.0' bgs | N/A | Location HSA-7 on sampling table. Augered to 12 ft bgs before sampling.<br><br>Note: Concrete was 5" thick and there was a 12" void to the top of soil, grade is top of concrete (~2' higher than HSA-8)<br><br>No sample taken |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 124-SB-138
**DATE BEGAN:** 1/17/2012
**DATE FINISHED:** 1/17/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57, freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | S-1 | 1<br>1<br>2<br>3 | 2.0 | | 10.0 - 10.5' FILL: Dark brown silt with gray and green COPR, trace fine sand and gravel; soft, wet<br>10.5 - 11.0' OH: Dark olive brown/black (2.5YR 2.5/1 to 3/3) silt, some clay, trace organic material, some COPR mixed in from 10.5-10.6'; soft, plastic<br>11.0 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; soft, moist; end of boring at 12.0' | N/A | Adjacent to 124-SB-131 (HSA-2). Augered to 10 ft bgs before sampling.<br>124-SB-138-1012 collected from 11.0-11.5' bgs @ 14:00 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-601
**DATE BEGAN:** 07/22/2013
**DATE FINISHED:** 07/22/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Ed/Justin
**NORTH:** 684132.4781
**EAST:** 603197.9486

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2 | | 0.0 - 1.0' FILL: Dark brown/black coarse SAND, fine to medium gravel, asphalt; loose; dry | 0 | Sample 124-SB-601-U1 from 1.1-3.5 ft bgs @ 1325 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Black fine to coarse SAND, fine to medium gravel, coal; medium dense; wet | 0 | |
| | 2.0 | | | | | 2.0 - 4.0' No Recovery | 0 | |
| | 3.0 | | | | | | 0 | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 4.5' FILL: Black fine to coarse SAND, fine to medium gravel, coal; medium dense; wet | 0 | Sample 124-SB-601-U2 from 3.5-5.0 ft bgs @ 1335; EnCore taken from 124-SB-601-U2 @ 1335 |
| | 5.0 | | | | | 4.5 - 8.0' FILL: Gray fine SAND and fine gravel, trace silt, COPR; medium dense; moist | 0 | Sample 124-SB-601-GG2 from 5.0-7.1 ft bgs @ 1340 |
| | 6.0 | | | | | | 0 | Sample 124-SB-601-MM1 from 7.1-8.8 ft bgs @ 1345; EnCore taken from 124-SB-601-MM1 @ 1345 |
| | 7.0 | | | | | | 0 | |
| | 8.0 | S-3 | NA | 4 | | 8.0 - 10.0' FILL: Gray fine SAND and fine gravel, trace silt, COPR; medium dense; moist | 0 | Sample 124-SB-601-MM2 from 8.8-10.4 ft bgs @ 1350 |
| | 9.0 | | | | | | 0 | |
| | 10.0 | | | | | 10.0 - 12.0' FILL: Light brown fine SAND, silt; medium dense; moist | 0 | |
| | 11.0 | | | | | | 0 | |
| | 12.0 | | | | | | | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-602
**DATE BEGAN:** 07/22/2013
**DATE FINISHED:** 07/22/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** NR
**DRILLER:** Ed/Justin
**NORTH:** 684169.6050
**EAST:** 603159.6973

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 2.0' FILL: Dark brown / black coarse to fine SAND, medium to fine gravel, some coal, trace glass; loose; dry | 0 | |
| | | | | | | | 0 | |
| | 1.0 | | | | | | 0 | Sample 124-SB-602-T1 from 1.1-3.5 ft bgs @ 1405 |
| | | | | | | | 0 | |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Gray medium to fine SAND, fine gravel, COPR; medium dense; moist | 0 | |
| | | | | | | | 0 | |
| | 3.0 | | | | | | 0 | |
| | | | | | | 3.5 - 4.0' FILL: Gray medium to fine SAND, trace silt; medium dense; moist | 0 | Sample 124-SB-602-T2 from 3.5-5.0 ft bgs @ 1410; EnCore taken from 124-SB-602-T2 @ 1410 |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Gray medium to fine SAND, silt, trace fine gravel; medium dense; moist | 0 | |
| | | | | | | | 0 | |
| | 5.0 | | | | | | 0 | Sample 124-SB-602-GG1 from 5.0-7.0 ft bgs @ 1415; EnCore taken from 124-SB-602-GG1 @ 1415 |
| | | | | | | | 0 | |
| | 6.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 7.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 8.0 | | | | | | | End of boring at 8 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-603
**DATE BEGAN:** 07/23/2013
**DATE FINISHED:** 07/23/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684221.4994
**EAST:** 603614.6301

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 2.5 | | 4.0 - 6.5' FILL: Dark brown fine SAND, trace silt, fine gravel; medium dense; wet | 0 | |
| | 5.0 | | | | | | 0 | Sample 124-SB-603-Z1 from 4.6-6.1 ft bgs @ 0815; EnCore taken from 124-SB-603-Z1 @ 0815 |
| | 6.0 | | | | | | 0 | Sample 124-SB-603-Z2 from 6.1-8.2 ft bgs @ 0820 |
| | 7.0 | | | | | 6.5 - 8.0' No Recovery | 0 | |
| | 8.0 | S-2 | NA | 3.0 | | 8.0 - 11.0' FILL: Dark brown fine SAND, trace silt, fine gravel; medium dense; wet | 0 | Sample 124-SB-603-OO1 from 8.2-9.9 ft bgs @ 0825; EnCore taken from 124-SB-603-OO1 @ 0825 |
| | 9.0 | | | | | | 0 | |
| | 10.0 | | | | | | 0 | Sample 124-SB-603-OO2 from 9.9-11.5 ft bgs @ 0830 |
| | 11.0 | | | | | 11.0 - 12.0' No Recovery | 0 | |
| | 12.0 | | | | | | 0 | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-604
**DATE BEGAN:** 07/22/2013
**DATE FINISHED:** 07/22/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Ed/Justin
**NORTH:** 684240.2014
**EAST:** 603093.3238

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' FILL: Black coarse to fine SAND, medium to fine gravel, brick; loose; dry | 0 | Sample 124-SB-604-O1 from 0.0-1.5 ft bgs @ 1430 |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Wood | 0 | |
| | | | | | | 1.3 - 1.5' FILL: Orange/red coarse to fine SAND; medium dense; dry | 0 | Sample 124-SB-604-O2 from 1.5-3.9 ft bgs @ 1435; EnCore taken from 124-SB-604-O2 @ 1435 |
| | 2.0 | | | | | 1.5 - 4.0' FILL: Grayish-green coarse to fine SAND, fine gravel; medium dense; moist | 0 | |
| | 3.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 6.0' FILL: Dark brown coarse to fine SAND, trace fine gravel; medium dense; moist | 0 | Sample 124-SB-604-Y1 from 3.9-5.4 ft bgs @ 1445 |
| | 5.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-SB-604-Y2 from 5.4-7.5 ft bgs @ 1450; EnCore taken from 124-SB-604-Y2 @ 1450 |
| | 6.0 | | | | | 6.0 - 8.0' FILL: Grayish-green fine SAND and SILT, trace fine gravel; medium dense; moist | 0 | |
| | 7.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-SB-604-NN1 from 7.5-9.2 ft bgs @ 1455; EnCore taken from 124-SB-604-NN1 @ 1455 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 10.5' FILL: Gray medium to fine SAND and SILT, trace fine gravel; medium dense; moist | 0 | |
| | 9.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 124-SB-604-NN2 from 9.2-10.8 ft bgs @ 1500 |
| | 10.0 | | | | | | 0 | |
| | | | | | | 10.5 - 11.5' FILL: Light brown SILT; medium dense; moist | 0 | |
| | 11.0 | | | | | | 0 | |
| | | | | | | 11.5 - 12.0' PEAT | 0 | |
| | 12.0 | | | | | | | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-605
**DATE BEGAN:** 07/23/2013
**DATE FINISHED:** 07/23/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684276.9738
**EAST:** 602997.1604

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 3.0 | | 4.0 - 5.5' FILL: Dark brown fine SAND, silt; loose; wet | 0 | Sample 124-SB-605-AA1 from 4.0-5.5 ft bgs @ 0900 |
| | 5.0 | | | | | | 0 | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Dark brown medium to fine SAND, fine gravel; medium dense; moist | 0 | Sample 124-SB-605-AA2 from 5.5-7.6 ft bgs @ 0905; EnCore taken from 124-SB-605-AA2 @ 0905 |
| | 7.0 | | | | | 7.0 - 8.0' No Recovery | 0 | |
| | 8.0 | S-2 | NA | 4.0 | | 8.0 - 10.0' FILL: Dark brown medium to fine SAND, fine gravel; loose; wet | 0 | Sample 124-SB-605-PP1 from 7.6-9.3 ft bgs @ 0910 |
| | 9.0 | | | | | | 0 | |
| | 10.0 | | | | | 10.0 - 11.5' FILL: Gray fine SAND, fine gravel, silt; dense; moist | 0 | Sample 124-SB-605-PP2 from 9.3-10.9 ft bgs @ 0915; EnCore taken from 124-SB-605-PP2 @ 0915 |
| | 11.0 | | | | | 11.5 - 11.8' FILL: Light brown SILT; dense, moist | 0 | |
| | 12.0 | | | | | 11.8 - 12.0' PEAT | 0 | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** **124-SB-607**
**DATE BEGAN:** 07/23/2013
**DATE FINISHED:** 07/23/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684348.9175
**EAST:** 602853.9690

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 3.0 | | 4.0 - 5.5' FILL: Dark brown coarse to fine SAND, medium to fine gravel; loose; wet | 0<br>0<br>0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Dark brown medium to fine SAND, trace fine gravel; loose; wet | 2.3<br>6.5<br>5.1 | Sample 124-SB-607-EE1 from 5.6-7.7 ft bgs @ 1000; EnCore taken from 124-SB-607-EE1 @ 1000 |
| | 7.0 | | | | | 7.0 - 8.0' No Recovery | 2.1 | |
| | 8.0 | S-2 | NA | 4.0 | | 8.0 - 9.0' FILL: Gray coarse to fine SAND, medium to fine gravel; loose; wet | 3.7 | |
| | 9.0 | | | | | 9.0 - 10.5' FILL: Reddish-brown medium to fine SAND; loose; wet | 0<br>0<br>0 | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' FILL: Reddish-brown clayey silt; medium dense; moist | 0<br>0 | Sample 124-SB-607-EE2 from 11.0-12.3 ft bgs @ 1005 |
| | 12.0 | | | | | 11.5 - 12.0' FILL: Reddish-brown coarse to fine SAND; loose; moist | 0 | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-608
**DATE BEGAN:** 07/23/2013
**DATE FINISHED:** 07/23/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684365.2500
**EAST:** 602952.3800

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.5' FILL: Dark brown/black coarse to fine SAND, medium to fine gravel; loose; moist | 0<br>0<br>0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Reddish-brown fine SAND, some medium to fine gravel, trace coal; medium dense; moist | 0<br>0<br>0 | Sample 124-SB-608-V1 from 1.5-3.9 ft bgs @ 0930; EnCore taken from 124-SB-608-V1 @0930 |
| | 3.0 | | | | | 3.0 - 4.0' No Recovery | 0<br>0 | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 5.5' FILL: Reddish-brown fine SAND, some medium to fine gravel, trace coal; medium dense; moist | 0<br>0<br>0 | Sample 124-SB-608-V2 from 3.9-5.4 ft bgs @ 0935 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Reddish-brown coarse to fine SAND, fine gravel; loose; moist | 0<br>0 | Sample 124-SB-608-FF1 from 5.4-7.5 ft bgs @ 0940; EnCore taken from 124-SB-608-FF1 @ 0940 |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Grayish-green fine SAND, silt, trace fine gravel; medium dense; moist | 0<br>0<br>0 | Sample 124-SB-608-FF2 from 7.5-9.2 ft bgs @ 0945 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 10.0' FILL: Reddish-brown coarse to fine SAND, medium to fine gravel; loose; wet | 0<br>0<br>0<br>0 | Sample 124-SB-608-TT1 from 9.2-10.8 ft bgs @ 0950 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Reddish-brown coarse to fine SAND, fine gravel; loose; wet | 0<br>0 | Sample 124-SB-608-TT2 from 10.8-11.7 ft bgs @ 0955; EnCore taken from 124-SB-608-TT2 @ 0955 |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Brown fine SAND, silt, possible COPR; medium dense; moist | 0<br>0 | |
| | 12.0 | | | | | | | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-609
**DATE BEGAN:** 07/26/2013
**DATE FINISHED:** 07/26/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684386.5620
**EAST:** 602871.9181

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 4.0 | | 4.0 - 5.0' FILL: Brown coarse to fine SAND, medium to fine gravel; loose; wet | 0<br>0 | Sample 124-SB-609-BB1 from 4.2-5.7 ft bgs @ 0940 |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Reddish-brown fine SAND and SILT; dense; moist | 0<br>0<br>0<br>0 | Sample 124-SB-609-BB2 from 5.7-7.8 ft bgs @ 0945; EnCore taken from 124-SB-609-BB2 @ 0945 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.3' FILL: Light brown SILT, trace wood; medium dense; moist | 0 | |
| | 8.0 | S-2 | NA | 4.0 | | 7.3 - 9.5' FILL: Dark brown coarse to fine SAND; medium dense, moist | 0<br>0<br>0<br>0 | Sample 124-SB-609-QQ1 from 7.8-9.5 ft bgs @ 0950 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 11.0' FILL: Dark brown SILT; medium dense; wet | 0<br>0<br>0 | Sample 124-SB-609-QQ2 from 9.5-11.1 ft bgs @ 0955; EnCore taken from 124-SB-609-QQ2 @ 0955 |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Pale yellow SILT; medium dense; moist | 0<br>0 | Sample 124-SB-609-UU1 from 11.1-12.4 ft bgs @ 1000 |
| | 12.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-610
**DATE BEGAN:** 07/26/2013
**DATE FINISHED:** 07/26/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684426.9410
**EAST:** 602853.0657

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 2.0 | | 4.0 - 5.0' FILL: Dark brown / black coarse to fine SAND, medium to fine gravel; loose; wet | 0 | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Reddish-brown fine SAND, some fine gravel, trace silt; medium dense; wet | 0<br>0<br>0 | Sample 124-SB-610-CC1 from 5.5-7.0 ft bgs @ 0905 |
| | 6.0 | | | | | 6.0 - 8.0' No Recovery | 0 | |
| | 7.0 | | | | | | | Sample 124-SB-610-CC2 from 7.0-9.1 ft bgs @ 0910; EnCore taken from 124-SB-610-CC2 @ 0910 |
| | 8.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-610
**DATE BEGAN:** 07/26/2013
**DATE FINISHED:** 07/26/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684426.9410
**EAST:** 602853.0657

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-2 | NA | 3.75 | | 8.0 - 8.8' FILL: Light brown fine SAND, silt, fine gravel; loose; wet | 0 | |
| | | | | | | | 0.3 | |
| | 9.0 | | | | | 8.8 - 9.8' FILL: Reddish-brown coarse to fine SAND; loose; wet | 0.7 | Sample 124-SB-610-RR1 from 9.1-10.8 ft bgs @ 0915 |
| | 10.0 | | | | | 9.8 - 11.8' FILL: Dark brown fine SAND, silt; medium dense; wet | 1.0 | |
| | | | | | | | 1.1 | |
| | 11.0 | | | | | | 0.7 | Sample 124-SB-610-RR2 from 10.8-12.4 ft bgs @ 0920; EnCore taken from 124-SB-610-RR2 @ 0920 |
| | | | | | | 11.8 - 12.0' No Recovery | 1.3 | |
| | 12.0 | S-3 | NA | 4.0 | | 12.0 - 13.0' FILL: Dark brown medium to fine SAND, fine gravel; loose; wet | | Sample 124-SB-610-UU2 from 12.4-13.7 ft bgs @ 0925; EnCore taken from 124-SB-610-UU2 @ 0925 |
| | 13.0 | | | | | 13.0 - 15.8' FILL: Dark brown medium to fine SAND, medium to fine gravel; loose; wet | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | | | | | | 15.8 - 16.0' PEAT | | End of boring at 16 ft bgs |
| | 16.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-611
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684464.8214
**EAST:** 602834.6079

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | PID not working |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 2.5 | | 4.0 - 4.3' FILL: Black SILT, fine sand; loose; dry | | |
| | | | | | | 4.3 - 6.5' FILL: Reddish-brown SILT, some medium gravel, trace coal; medium dense; moist | | |
| | 5.0 | | | | | | | Sample 124-SB-611-DD1 from 5.2-6.7 ft bgs @ 1400 |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 8.0' No Recovery | | Sample 124-SB-611-DD2 from 6.7-8.8 ft bgs @ 1405; EnCore taken from 124-SB-611-DD2 at 1405 |
| | 7.0 | | | | | | | |
| | 8.0 | S-2 | NA | 4.0 | | 8.0 - 8.5' FILL: Reddish-brown SILT, some | | |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 124
**PROJECT NO:** 3480130354
**BORING ID:** 124-SB-611
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684464.8214
**EAST:** 602834.6079

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-2 | NA | 4.0 | | medium gravel, trace coal; medium dense; moist | | |
| | 9.0 | | | | | 8.5 - 11.0' FILL: Dark brown medium to fine SAND, trace fine gravel; loose; wet | | Sample 124-SB-611-SS1 from 8.8-10.5 ft bgs @ 1410 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Dark brown SILT; medium dense; wet | | Sample 124-SB-611-SS2 from 10.5-12.1 ft bgs @ 1415; EnCore take from 124-SB-611-SS2 at 1415 |
| | | | | | | 11.5 - 12.0' FILL: Yellow/brown SILT, possible COPR; medium dense; moist | | |
| | 12.0 | S-3 | NA | | | 12.0 - 13.8' FILL: Dark brown/yellow SILT, possible COPR; medium dense; wet | | Sample 124-SB-611-VV1 from 12.1-13.4 ft bgs @ 1420 |
| | 13.0 | | | | | | | |
| | | | | | | 13.8 - 14.0' PEAT | | End of boring at 14 ft bgs |
| | 14.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 125-MW-02
**DATE BEGAN:** 2-19-16
**DATE FINISHED:** 2-19-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 6 | 2.0 | | 10.0 - 13.4' SW: Gray fine to coarse SAND; medium dense, wet | NM | Augered to 10' bgs<br>Starting elevation 8.5'<br>GW elevation 4.5' |
| | | | 9 | | | | | |
| | 11.0 | | 6 | | | | | |
| | | | 10 | | | | | |
| | 12.0 | SS2 | 13 | 2.0 | | | | |
| | | | 10 | | | | | |
| | 13.0 | | 9 | | | | | |
| | | | 12 | | | 13.4 - 13.5' OL: Dark gray SILT with organic fibers<br>13.5 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 125-MW-03
**DATE BEGAN:** 2-11-16
**DATE FINISHED:** 2-11-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 10' bgs
**GW DEPTH:** 2' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 24 | 1.5 | | 8.0 - 9.4' SW: Gray fine to coarse SAND, fine gravel; medium dense, wet | NM | Augered to 8' bgs<br><br>Starting elevation 7.5' |
| | | | 41 | | | | | |
| | 9.0 | | 25 | | | 9.4 - 9.5' OL: Dark gray SILT with organics | | |
| | | | 6 | | | 9.5 - 10.0' No recovery. End of boring at 10.0' bgs. | | Meadow mat expected at -2 elevation (9.5' bgs) |
| | 10.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-15
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684456.94
**EAST:** 602620.14

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' ASPHALT | 2.0 | |
| | | | | | | 0.3 - 1.5' CONCRETE | 0 | |
| | -1.0 | | | | | | 0 | |
| | | | | | | 1.5 - 2.8' FILL: Reddish brown silty sand, some fine to medium gravel, moist | 0 | Sample 125-PT-15_0002 collected at 9:03 from 1.5 - 2.0 ft bgs |
| | -2.0 | | | | | | 0 | |
| | | | | | | 2.8 - 3.3' FILL: Black fine to medium sand, some silt, some fine to medium gravel | 0 | |
| | -3.0 | | | | | | 0.3 | Sample 125-PT-15_0204 collected at 9:07 from 2.75 - 3.25 ft bgs |
| | | | | | | 3.3 - 4.0' No Recovery | | |
| ▽ | -4.0 | S-2 | NA | 0.75 | | 4.0 - 4.8' FILL: Black fine to medium sand, some silt, some fine to medium gravel, wet | 0 | Sample 125-PT-15_0406 collected at 9:09 from 4.0 - 4.5 ft bgs |
| | | | | | | | 0 | |
| | -5.0 | | | | | 4.8 - 8.0' No Recovery | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 3.5 | | 8.0 - 11.0' FILL: Brown to reddish brown fine to coarse sand, some fine gravel, trace silt, wet | 0 | Sample 125-PT-15_0810 collected at 9:14 from 8.0 - 8.5 ft bgs |
| | | | | | | | 0 | |
| | -9.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -10.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -11.0 | | | | | 11.0 - 11.5' FILL: Brown silty fine sand, definite Peat in tip, approx. 3", silt and clay, organic material, wet | 0 | Sample 125-PT-15_1012 collected at 9:16 from 11.0 - 11.5 ft bgs |
| | -12.0 | | | | | | 0 | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-16
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684503.33
**EAST:** 602660.80

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.5' CONCRETE | 0 | |
| | -1.0 | | | | | | 1.2 | |
| | | | | | | 1.5 - 3.3' FILL: Dark brown to black fine to coarse sand, some fine to medium gravel, some silt, brick from 1.75 - 2.0 ft bgs, wood at bottom | 0 | Sample 125-PT-16_0002 collected at 9:24 from 1.5 - 2.0 ft bgs |
| | -2.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -3.0 | | | | | | 0 | Sample 125-PT-16_0204 collected at 9:26 from 2.75 - 3.25 ft bgs |
| | | | | | | 3.3 - 4.0' No Recovery | | |
| | -4.0 | S-2 | NA | 2.0 | | 4.0 - 6.0' FILL: Dark brown to black fine to coarse sand, some fine to medium gravel, some silt, 2" lens of grayish sand and silt at 4.5 ft bgs with wood chips, wet | 0 | |
| | | | | | | | 0 | Sample 125-PT-16_0406 collected at 9:28 from 4.5 - 5.0 ft bgs |
| | -5.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -6.0 | | | | | 6.0 - 8.0' No Recovery | 0 | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 3.5 | | 8.0 - 9.8' FILL: Dark brown to black fine to coarse sand, some fine to medium gravel, som silt loose, soft, wet | 0 | |
| | | | | | | | 0 | Sample 125-PT-16_0810 collected at 9:33 from 8.5 - 9.0 ft bgs |
| | -9.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -10.0 | | | | | 9.8 - 11.5' FILL: Reddish brown fine to coarse sand, some silt, gets siltier with depth, trace organic material at bottom, wet | 0 | |
| | | | | | | | 0 | |
| | -11.0 | | | | | | 0 | Sample 125-PT-16_1012 collected at 9:35 from 11.0 - 11.5 ft bgs |
| | | | | | | 11.5 - 12.0' No Recovery | 0 | |
| | -12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' PT: Greenish black (GLEY 1 2.5/10Y) silt and clay, some sand, organic material, wet | | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | End of boring at 14.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-17
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684543.453
**EAST:** 602699.13

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.5' CONCRETE | 0 | |
| | -1.0 | | | | | | 0 | |
| | | | | | | 1.5 - 3.0' FILL: Dark brown to black fine to coarse sand, some fine to coarse gravel, trace silt, trace pieces of brick | 0 | Sample 125-PT-17_0002 collected at 10:01 from 1.5 - 2.0 ft bgs |
| | -2.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 125-PT-17_0204 collected at 10:03 from 2.5 - 3.0 ft bgs |
| | -3.0 | | | | | 3.0 - 4.0' FILL: Pieces of brick | 0 | |
| | -4.0 | S-2 | NA | 1.75 | | 4.0 - 5.8' FILL: Dark brown fine to coarse gravel, some fine to coarse sand, trace silt, trace organic material, wet, pieces of brick from 5.25 - 5.75 ft bgs | 0 | Sample 125-PT-17_0406 collected at 10:07 from 4.0 - 4.5 ft bgs |
| | | | | | | | 0 | |
| | -5.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -6.0 | | | | | 5.8 - 8.0' No Recovery | | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 3.75 | | 8.0 - 9.0' FILL: Dark brown fine to coarse gravel, some fine to coarse sand, trace silt, trace organic material, wet | 0 | |
| | | | | | | | 0 | |
| | -9.0 | | | | | 9.0 - 10.3' FILL: Brown to reddish brown fine to coarse sand, some silt, trace fine gravel, wet | 0 | Sample 125-PT-17_0810 collected at 10:20 from 9.0 - 9.5 ft bgs |
| | | | | | | | 0 | |
| | -10.0 | | | | | 10.3 - 11.8' FILL: Brown to reddish brown sandy silt, COPR material in tip, pasty, green, wet | 0 | |
| | -11.0 | | | | | | 0 | Sample 125-PT-17_1012 collected at 10:22 from 11.25 - 11.75 ft bgs |
| | | | | | | 11.8 - 12.0' No Recovery | 0 | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | |
| | | | | | | 12.0 - 13.5' FILL: Brown to reddish brown sandy silt, no COPR, more sand, firm, wet | 0 | |
| | -13.0 | | | | | | 0 | |
| | | | | | | 13.5 - 14.0' COPR: Greenish, pasty, silt and clay, wet | 0 | Sample 125-PT-17_1214 collected at 10:26 from 13.5 - 14.0 ft bgs |
| | -14.0 | | | | | | 0 | |
| | | | | | | 14.0 - 16.0' PT: Greenish black (GLEY 1 2.5/10Y) silt and clay, some sand, organic material, decaying organic odors, wet | 0 | |
| | -15.0 | | | | | | 0 | |
| | | | | | | | 29 | |
| | -16.0 | | | | | | 57 | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-17R
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | 1.0 | | | | | 0.3 - 1.5' CONCRETE | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Dark brown to black fine to coarse sand, some fine to coarse gravel, trace silt, trace pieces of brick | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Pieces of brick | | |
| | 4.0 | S-2 | NA | 1.75 | | 4.0 - 5.8' FILL: Dark brown fine to coarse gravel, some fine to coarse sand, trace silt, trace organic material, wet, pieces of brick from 5.25 - 5.75 ft bgs | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.8 - 8.0' No Recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.75 | | 8.0 - 9.0' FILL: Dark brown fine to coarse gravel, some fine to coarse sand, trace silt, trace organic material, wet | 0 | |
| | 9.0 | | | | | 9.0 - 10.3' FILL: Brown to reddish brown fine to coarse sand, some silt, trace fine gravel, wet | | |
| | 10.0 | | | | | 10.3 - 11.8' FILL: Brown to reddish brown sandy silt, COPR material in tip, pasty, green, wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 11.8 - 12.0' No Recovery | 0 | |
| | 13.0 | | | | | 12.0 - 13.5' FILL: Brown to reddish brown sandy silt, no COPR, more sand, firm, wet | | |
| | 14.0 | | | | | 13.5 - 14.0' COPR: Greenish, pasty, silt and clay, wet | | Sample 125-PT-17R-1416 from 14.0 - 14.5 ft bgs at 14:15 |
| | 15.0 | | | | | 14.0 - 16.0' PT: Brown peat; moist; end of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-18
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684592.97
**EAST:** 602747.03

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.5' FILL: Black fine to coarse sand, some fine to medium gravel, trace silt | 0 | Sample 125-PT-18_0002 collected at 10:47 from 1.0 - 1.5 ft bgs |
| | -1.0 | | | | | | 0 | |
| | | | | | | 1.5 - 2.0' FILL: Pieces of concrete | 0 | Sample 125-PT-18_0204 collected at 10:49 from 2.0 - 2.5 ft bgs |
| | -2.0 | | | | | | 0 | |
| | | | | | | 2.0 - 2.5' COPR: Tan to greenish silt and clay, some fine to coarse sand, dry | 0 | |
| | -3.0 | | | | | | 0 | |
| | | | | | | 2.5 - 3.0' FILL: Dark brown fine to coarse sand, some fine to medium gravel, some silt | | |
| | -4.0 | S-2 | NA | 3.5 | | 3.0 - 4.0' FILL: Pieces of brick | 0 | Sample 125-PT-18_0406 collected at 10:55 from 4.0 - 4.5 ft bgs |
| | | | | | | | 0 | |
| | -5.0 | | | | | 4.0 - 6.0' FILL: Dark brown to black fine to coarse sand and fine to coarse gravel, pieces of brick, trace silt, organic material, wet | 0 | |
| | | | | | | | 0 | |
| | -6.0 | | | | | | 0 | |
| | | | | | | 6.0 - 7.5' COPR: Tan to pale green, pasty, silt and clay, wet | 0 | Sample 125-PT-18_0608 collected at 10:57 from 6.5 - 7.0 ft bgs |
| | -7.0 | | | | | | 0 | |
| | | | | | | 7.5 - 8.0' No Recovery | 0 | |
| | -8.0 | S-3 | NA | NR | | 8.0 - 12.0' No Recovery: Small amount of possible COPR in tip | 0 | Not enough COPR to sample |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' PT: Greenish black (GLEY 1 2.5/10Y) silt and sand, organic material, decaying organic odors, wet | 0 | |
| | | | | | | | 0 | |
| | -13.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | | |
| | -16.0 | | | | | | | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-19
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684641.18
**EAST:** 602793.35

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.8' FILL: Black fine to coarse sand and fine to coarse gravel, pieces of concrete | 0 | |
| | -1.0 | | | | | | 0 | Sample 125-PT-19_0002 collected at 11:34 from 1.0 - 1.5 ft bgs |
| | | | | | | | 0 | |
| | -2.0 | | | | | 1.8 - 2.3' FILL: Pieces of brick | 0 | |
| | | | | | | 2.3 - 2.6' FILL: Reddish brown fine to coarse sand, some silt, moist, organic material | 0 | Sample 125-PT-19_0204 collected at 11:36 from 2.5 - 3.0 ft bgs |
| | -3.0 | | | | | 2.6 - 3.2' FILL: Dark brown to black fine to coarse sand and silt, moist, organic material | 0 | |
| | | | | | | 3.2 - 3.8' FILL: Pieces of brick | 0 | |
| | | | | | | 3.8 - 4.0' No Recovery | | |
| | -4.0 | S-2 | NA | 2.75 | | 4.0 - 6.0' FILL: Dark brown to black fine to coarse sand, some fine to coarse gravel, trace silt, pices of brick, organic material and wood chips, wet | 0 | Sample 125-PT-19_0406 collected at 11:38 from 4.0 - 4.5 ft bgs |
| | | | | | | | 0 | |
| | -5.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -6.0 | | | | | 6.0 - 6.5' COPR: Tan to pale yellow, pasty, silt and clay, wet | 0 | Sample 125-PT-19_0608 collected at 11:41 from 6.0 - 6.5 ft bgs |
| | | | | | | 6.5 - 6.8' FILL: Dark brown silty fine sand, wet | 0 | |
| | -7.0 | | | | | 6.8 - 8.0' No Recovery | | |
| | -8.0 | | | | | | | |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-19
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684641.18
**EAST:** 602793.35

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.8' FILL: Dark brown silt and fine to coarse sand, wet | 0 | |
| | | | | | | | 0 | Sample 125-PT-19_0810 collected at 11:48 from 8.5 - 9.0 ft bgs |
| | -9.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -10.0 | | | | | 9.8 - 10.3' FILL: Dark brown to reddish brown silty sand, very soft, wet | 0 | |
| | | | | | | 10.3 - 12.0' COPR: Tan to pale green, pasty, silt and clay, wet | 0 | Sample 125-PT-19_1012 collected at 11:50 from 10.5 - 11.0 ft bgs |
| | -11.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -12.0 | S-4 | NA | 3.5 | | 12.0 - 15.5' PT: Greenish black (GLEY1 2.5/10Y) silt and clay, organic material, wet | 0 | |
| | | | | | | | 0 | |
| | -13.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -14.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -15.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -16.0 | | | | | | | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-20
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 15 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684431.48
**EAST:** 602654.21

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 2.0' FILL: Black fine to coarse sand and fine to coarse gravel, some pieces of concrete | 0 | |
| | -1.0 | | | | | | 0 | Sample 125-PT-20_0002 collected at 13:14 from 1.0 - 1.5 ft bgs |
| | | | | | | | 0 | |
| | -2.0 | | | | | 2.0 - 3.5' FILL: Reddish brown fine to coarse sand, some silt, some fine to medium gravel, very tightly packed, hard | 0 | |
| | | | | | | | 0 | |
| | -3.0 | | | | | | 0 | Sample 125-PT-20_0204 collected at 13:16 from 3.0 - 3.5 ft bgs |
| | | | | | | 3.5 - 4.0' No Recovery | 47 | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 5.0' FILL: Brown to gray fine to medium sand, some fine to medium gravel, trace silt | 0 | |
| | | | | | | | 0 | |
| | -5.0 | | | | | 5.0 - 6.0' FILL: Reddish brown fine to medium sand, some fine to medium gravel, some silt, some organic material, wet at 5.5 ft bgs | 0 | |
| ▽ | | | | | | | 0 | Sample 125-PT-20_0406 collected at 13:22 from 5.5 - 6.0 ft bgs |
| | -6.0 | | | | | | 2.5 | |
| | | | | | | 6.0 - 7.5' FILL: Reddish brown fine to coarse sand, some fine gravel, trace silt, some organic material, wet | 0 | |
| | -7.0 | | | | | | 0 | Sample 125-PT-20_0608 collected at 13:24 from 7.0 - 7.5 ft bgs |
| | | | | | | 7.5 - 8.0' No Recovery | 0 | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 10.5' FILL: Reddish brown fine to coarse sand, some fine gravel, trace silt, some organic material, wet | 0 | |
| | | | | | | | 0 | |
| | -9.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 125-PT-20_0810 collected at 13:28 from 9.5 - 10.0 ft bgs |
| | -10.0 | | | | | | 0 | |
| | | | | | | 10.5 - 11.3' FILL: Dark brown silty fine sand, very soft, wet | 0 | |
| | -11.0 | | | | | | 0 | |
| | | | | | | 11.3 - 12.0' FILL: Reddish brown fine to coarse sand, some fine gravel, some silt, wet | 0 | Sample 125-PT-20_1012 collected at 13:29 from 11.5 - 12.0 ft bgs |
| | -12.0 | S-4 | NA | 3.0 | | | 0 | |
| | | | | | | 12.0 - 13.0' FILL: Same as above, reddish brown fine to coarse sand, some fine gravel, some silt, wet | 0 | Sample 125-PT-20_1214 collected at 13:41 from 12.5 - 13.0 ft bgs |
| | -13.0 | | | | | | 0 | |
| | | | | | | 13.0 - 15.0' PT: Greenish black (GLEY1 2.5/10Y) silt and clay, organic material, wet | 0 | |
| | -14.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -15.0 | | | | | | | End of boring at 15.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-21
**DATE BEGAN:** 4/16/08
**DATE FINISHED:** 4/16/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684473.11
**EAST:** 602697.71

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.3' CONCRETE | 0 | |
| | -1.0 | | | | | 1.3 - 2.0' FILL: Black fine to coarse sand, some fine to coarse gravel, trace silt | 0 | Sample 125-PT-21_0002 collected at 13:49 from 1.5 - 2.0 ft bgs |
| | -2.0 | | | | | 2.0 - 4.0' FILL: Reddish brown to red fine to medium sand, some fine gravel, some silt, moist, some mottling | 0 | |
| | -3.0 | | | | | | 0 | Sample 125-PT-21_0204 collected at 13:51 from 3.0 - 3.5 ft bgs |
| | -4.0 | S-2 | NA | 2.5 | | 4.0 - 6.5' FILL: Same as above, 1" lens of white, pasty COPR at 6.0 ft bgs, wet, trace organic material | 0 | |
| | -5.0 | | | | | | 0 | Sample 125-PT-21_0406 collected at 14:09 from 4.5 - 5.0 ft bgs |
| | -6.0 | | | | | | 0 | Sample 125-PT-21_0608 collected at 14:11 from 6.0 - 6.5 ft bgs |
| | -7.0 | | | | | 6.5 - 8.0' No Recovery | 0 | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Reddish brown fine to coarse sand, some silt, trace fine gravel, wet | 0 | |
| | -9.0 | | | | | | 0 | Sample 125-PT-21_0810 collected at 14:14 from 9.0 - 9.5 ft bgs |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | | 0 | |
| | -12.0 | S-4 | NA | 3.5 | | 12.0 - 15.5' PT: Greenish black (GLEY 1 2.5/10Y), silt and clay, organic material, wet | 0 | Sample 125-PT-21_1012 collected at 14:16 from 11.5 - 12.0 ft bgs |
| | -13.0 | | | | | | 0 | |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | 0 | |
| | -16.0 | | | | | | 0 | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-22
**DATE BEGAN:** 4/17/08
**DATE FINISHED:** 4/17/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5.25 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684513.18
**EAST:** 602735.72

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.5' CONCRETE | 0 | |
| | -1.0 | | | | | 1.5 - 2.0' FILL: Dark brown to brown fine to cooarse sand, some fine to medium gravel, trace silt | 0 | Sample 125-PT-22_0002 collected at 7:55 from 1.5 - 2.0 ft bgs |
| | -2.0 | | | | | 2.0 - 4.0' FILL: Reddish brown fine to medium sand and silt, some fine to medium gravel, moist at approx. 3.0 ft bgs | 0 | |
| | -3.0 | | | | | | 0 | Sample 125-PT-22_0204 collected at 7:57 from 3.5 - 4.0 ft bgs |
| | -4.0 | S-2 | NA | 2.75 | | 4.0 - 4.5' FILL: Same as above | 0 | |
| | -5.0 | | | | | 4.5 - 5.3' FILL: Brown to gray to reddish brown fine to medium sand and silt, some fine to medium gravel | 0 | Sample 125-PT-22_0406 collected at 7:59 from 5.0 - 5.5 ft bgs |
| | -6.0 | | | | | 5.3 - 6.8' FILL: Reddish brown fine to medium sand and silt, some fine gravel, trace clay, wet | 0 | Sample 125-PT-22_0608 collected at 8:01 from 6.0 - 6.5 ft bgs |
| | -7.0 | | | | | 6.8 - 8.0' No Recovery | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Reddish brown fine to medium sand and silt, some fine gravel, tight, drier, trace organic material, some mottling | 0 | Sample 125-PT-22_0810 collected at 8:04 from 8.5 - 9.0 ft bgs |
| | -9.0 | | | | | 9.0 - 10.5' FILL: Brown fine to coarse sand, trace silt, trace fine gravel, wet | 0 | |
| | -10.0 | | | | | 10.5 - 11.8' FILL: Dark brown silty fine sand, very soft, wet | 0 | |
| | -11.0 | | | | | 11.8 - 12.0' COPR: Gray to tan, pasty, silty and clay, wet | 0 | Sample 125-PT-22_1012 collected at 8:06 from 11.5 - 12.0 ft bgs |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 13.8' FILL: Reddish brown to brown fine to medium sand and silt, some clay, some fine gravel, wet | 0 | |
| | -13.0 | | | | | 13.8 - 14.0' COPR: Tan to green, pasty, silt and clay, wet | 0.8 | Sample 125-PT-22_1214 collected at 8:14 from 13.5 - 14.0 ft bgs |
| | -14.0 | | | | | 14.0 - 16.0' PT: Greenish black (GLEY 1 2.5/10Y) silt and clay, organic material, some wood, wet | 0 | |
| | -15.0 | | | | | | 0 | |
| | -16.0 | | | | | | 0 | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-23
**DATE BEGAN:** 4/17/08
**DATE FINISHED:** 4/17/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5.3 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684562.63
**EAST:** 602783.44

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.5' CONCRETE | 0 | |
| | -1.0 | | | | | | 0 | |
| | | | | | | 1.5 - 4.0' FILL: Brown to reddish brown fine to medium sand, some silt, some fine to medium gravel, moist from 3.0 ft bgs, some mottling | 0 | Sample 125-PT-23_0002 collected at 8:26 from 1.5 - 2.0 ft bgs |
| | -2.0 | | | | | | 0 | |
| | | | | | | | 0 | Sample 125-PT-23_0204 collected at 8:28 from 3.5 - 4.0 ft bgs |
| | -3.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Brown fine to coarse sand, some silt, some fine to medium gravel, trace pieces of brick | 0 | Hit wood obstruction (possibly a piling) at 5.0 ft bgs, had creosote odors, will step out 5 ft to the west |
| | | | | | | | 0 | |
| ▽ | -5.0 | | | | | 5.0 - 5.3' CONCRETE: Pieces of concrete | 0 | Sample 125-PT-23_0406 collected at 8:43 from 4.5 - 5.0 ft bgs |
| | | | | | | 5.3 - 6.3' FILL: Brown silty fine sand, trace fine gravel, trace organic material, wet | 0 | |
| | -6.0 | | | | | | 0 | |
| | | | | | | 6.3 - 7.0' COPR: Tan to pale yellow to bright green, pasty, silt and clay, wet | 0 | Sample 125-PT-23_0608 collected at 8:45 from 6.5 - 7.0 ft bgs |
| | -7.0 | | | | | | 0 | |
| | | | | | | 7.0 - 8.0' No Recovery | | |
| | -8.0 | S-3 | NA | 3.5 | | | 0 | |
| | | | | | | 8.0 - 9.0' FILL: Brown fine to medium sand, some silt, some fine gravel, gray lens from 8.5 - 8.7 ft bgs, wet | 0 | |
| | -9.0 | | | | | | 0 | Sample 125-PT-23_0810 collected at 8:53 from 9.0 - 9.5 ft bgs |
| | | | | | | 9.0 - 9.8' FILL: Brown fine to coarse sand, some fine gravel, trace silt, wet | 0 | |
| | -10.0 | | | | | | 0 | |
| | | | | | | 9.8 - 10.8' FILL: Dark brown fine to medium sand and silt, wet | 0 | |
| | -11.0 | | | | | | 0 | Sample 125-PT-23_1012 collected at 8:55 from 11.0 - 11.5 ft bgs |
| | | | | | | 10.8 - 11.5' COPR: Pale yellow to tan to white, pasty, silt and clay, wet | 0 | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | |
| | | | | | | 11.5 - 12.0' No Recovery | 0 | |
| | -13.0 | | | | | | 0 | |
| | | | | | | 12.0 - 16.0' PT: Greenish black (GLEY 1 2.5/10Y) silty and clay, organic material, wet | 0 | |
| | -14.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -15.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | -16.0 | | | | | | | End of boring at 16.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-PT-24
**DATE BEGAN:** 4/17/08
**DATE FINISHED:** 4/17/08
**INSPECTOR:** M. Daly / F. Petrino
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Geoprobe
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Shaming
**NORTH:** 684611.02
**EAST:** 602829.94

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.3' CONCRETE | 0 | |
| | -1.0 | | | | | | 0 | Sample 125-PT-24_0002 collected at 10:03 from 1.5 - 2.0 ft bgs |
| | | | | | | 1.3 - 2.0' FILL: Gray to black fine to coarse sand, some fine to coarse gravel, trace silt | 0 | |
| | -2.0 | | | | | 2.0 - 2.6' COPR: Pale yellow to pale green sand and silt, very dry | 0 | Sample 125-PT-24_0204 collected at 10:05 from 2.0 - 2.5 ft bgs |
| | | | | | | | 0 | |
| | -3.0 | | | | | 2.6 - 4.0' FILL: Reddish brown to brown fine to coarse sand, some fine to medium gravel, some silt, wood chips at bottom, moist at 3.0 ft bgs | 0 | |
| | | | | | | | 0 | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 5.3' FILL: Brown to black fine to coarse gravel and wood chips, some fine to coarse sand, trace silt, wet | 0 | |
| | | | | | | | 0 | Sample 125-PT-24_0406 collected at 10:08 from 4.5 - 5.0 ft bgs |
| | -5.0 | | | | | | 0 | |
| | | | | | | 5.3 - 7.0' COPR: Tan to pale yellow, pasty, silt and clay, wet | 0 | |
| | -6.0 | | | | | | 0 | Sample 125-PT-24_0608 collected at 10:10 from 6.5 - 7.0 ft bgs, Duplicate sample also collected at 10:12 |
| | | | | | | | 0 | |
| | -7.0 | | | | | 7.0 - 8.0' No Recovery | 0 | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.8' FILL: Brown fine to coarse sand, some silt, wet | 0 | |
| | | | | | | | 0.7 | |
| | -9.0 | | | | | | 0 | Sample 125-PT-24_0810 collected at 10:16 from 9.0 - 9.5 ft bgs |
| | | | | | | | 0 | |
| | -10.0 | | | | | 9.8 - 11.5' COPR: Pale yellow to pale green to tan, pasty, silt and clay, wet | 0 | |
| | | | | | | | 0 | Sample 125-PT-24_1012 collected at 10:18 from 10.5 - 11.0 ft bgs |
| | -11.0 | | | | | | 0 | |
| | | | | | | 11.5 - 12.0' PT: Greenish black (GLEY 1 2.5/10Y) silt and clay, organic material, wet | 0 | |
| | -12.0 | | | | | | | End of boring at 12.0 ft bgs |

PREPARED BY: FP
CHECKED BY: AGS

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 125-SB-002 **SITE ID:** 125

**DATE BEGAN:** 6/20/2005 **DATE FINISHED:** 6/20/2005 **INSPECTOR:** CH

**DRILLING CO:** EPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Ron Higgins **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 7.5 ft bgs **GW DEPTH:** NA

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 3 | | ASPHALT: Asphalt, DGA | | 0 | |
| | -1.0 | | | | | FILL: Topsoil, concrete, gravel, asphalt, coal, ash, trace suspected COPR | | | 125-SB-002_005 collected from 2.0-2.5 ft bgs @ 1426<br>125-SB-002_006 collected from 2.0-2.5 ft bgs @ 1430 |
| | -2.0 | | | | | | | | |
| | -3.0 | | | | | | | | |
| | -4.0 | S-2 | | 1 | | FILL: Brick | | 0 | |
| -5.0 | -5.0 | | | | | | | | |
| | -6.0 | | | | | | | | |
| | -7.0 | | | | | | | | |
| | -8.0 | | | | | End boring @ 7.5' | | | Refusal @ 7.5 ft bgs |
| | -9.0 | | | | | | | | |
| -10.0 | -10.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 125-SB-003 **SITE ID:** 125

**DATE BEGAN:** 6/20/2005 **DATE FINISHED:** 6/20/2005 **INSPECTOR:** CH

**DRILLING CO:** EPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Ron Higgins **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 16 ft bgs **GW DEPTH:** 2 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT: Asphalt, DGA | | 0 | |
| | -1.0 | | | | | FILL: Topsoil | | | |
| | -2.0 | | | | | FILL: Brick | | | 125-SB-003_007 collected from 1.5-2.0 ft bgs @ 1653 |
| | -3.0 | | | | | FILL: Black, silt; some wood | | | |
| | -4.0 | | | | | FILL: Brick | | | |
| | | S-2 | | 4 | | FILL: Dark brown, sand, coarse; some gravel, medium | | 0 | 125-SB-003_008 collected from 4.5-5.0 ft bgs @ 1659 |
| -5.0 | -5.0 | | | | | | | | |
| | -6.0 | | | | | | | | |
| | -7.0 | | | | | FILL: Brick | | | |
| | -8.0 | S-3 | | 4 | | FILL: Sand, coarse; some clay | | 0 | |
| | -9.0 | | | | | FILL: Dark brown, sand, fine | | | 125-SB-003_009 collected from 9.5-10.0 ft bgs @ 1703 |
| -10.0 | -10.0 | | | | | | | | |
| | -11.0 | | | | | FILL: Silty sand, fine | | | |
| | -12.0 | | | 4 | | | | 0 | |
| | -13.0 | | | | | FILL: White sand; brown - black, some silt/clay; green (suspected COPR) | | | 125-SB-003_010 collected from 13.5-14.0 ft bgs @ 1706 |
| | -14.0 | | | | | OH: Brown - black, silty clay; organics | | | 125-SB-003_011 collected from 14.0-14.5 ft bgs @ 1707 |
| -15.0 | -15.0 | | | | | PT: Peat | | | |
| | -16.0 | | | | | End boring @ 16' | | 0 | |
| | -17.0 | | | | | | | | |

MACTEC

**SITE INFO:**

**DATE BEGAN:** 10/26/10

**DRILLING CO:** B and B

**SAMPLING TOOL:**

**DRILLER:** Gordon Blewitt

**PROJECT NO:** 3480050143

**DATE FINISHED:** 10/26/10

**DRILLING METHOD:** Direct Push

**COMPLETION DEPTH:** 16 ft bgs

**NORTH:**

**BORING ID:** **125-SB-003R**

**INSPECTOR:** B. Senna

**DRILL EQUIP:** Geoprobe 6610 DT

**GW DEPTH:** 2 ft bgs

**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 4 | | 0.0 - 1.0' ASPHALT: Asphalt, DGA | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Topsoil | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Brick | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Black, silt; some wood | | |
| | 4.0 | S-2 | N/A | 4 | | 3.5 - 4.0' FILL: Brick | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Dark brown, sand, coarse; some gravel, medium | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Brick | | |
| | 8.0 | S-3 | N/A | 4 | | 8.0 - 9.0' FILL: Sand, coarse; some clay | 0 | |
| | 9.0 | | | | | 9.0 - 10.5' FILL: Dark brown, sand, fine | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 13.5' FILL: Silty sand, fine | | |
| | 12.0 | S-4 | N/A | 4 | | | 0 | |
| | 13.0 | | | | | 13.5 - 14.0' FILL: White sand; brown - black, some silt/clay; green (suspected COPR) | | |
| | 14.0 | | | | | 14.0 - 14.5' OH: Brown - black, silty clay; organics | | 125-SB-003R-1416 collected from 14.0-14.5 ft bgs @ 14:00 |
| | 15.0 | | | | | 14.5 - 16.0' PT: Brown peat; moist; end of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY:

CHECKED BY:

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-004
**DATE BEGAN:** 7/8/2008
**DATE FINISHED:** 7/8/2008
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | Collect sample from 1-1.5' bgs @ 10:24 |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Red brown silt, some sand, trace (fine) angular gravel, firm, few olive green mottles, dry | | |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Dark brown sand (medium-coarse) and angular gravel (fine-medium), white and black fine gravel at 2.0'; dry | | Collect sample from 2.5-3' bgs @ 10:26 |
| | | | | | | 2.0 - 2.5' FILL: Wood fragments, dry | | |
| | -3.0 | | | | | 2.5 - 2.8' FILL: Olive green angular plastic pieces, (fine-medium) gravel sized; dry | | |
| | | | | | | 2.8 - 3.3' FILL: Yellow brown (fine-coarse) sand and gravel; dry | | Slight odor from 3.3-4.3' bgs |
| ▽ | -4.0 | 2 | NA | 4.0 | | 3.3 - 3.5' FILL: Dark brown silt and gravel, some organic material, trace coal, slight odor, wet | 0 | Collect sample from 4.5-5' bgs @ 10:35 |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | | | | | 4.0 - 4.3' FILL: Dark brown silt and gravel, some organics, trace coal, slight odor, saturated | | |
| | -6.0 | | | | | 4.3 - 6.0' FILL: Dark brown sand (fine-coarse), trace silt and clay, saturated | | Collect sample from 7.5-8' bgs @ 10:38 |
| | -7.0 | | | | | 6.0 - 6.5' FILL: Light brown sand (fine-coarse) some rounded gravel (fine), saturated | | |
| | | | | | | 6.5 - 8.0' FILL: Light brown clayey silt, some rounded gravel (fine), firm, saturated | | |
| | -8.0 | 3 | NA | 0.5 | | 8.0 - 8.5' FILL: Light brown sand (fine-coarse) and rounded gravel (fine), large piece of gravel at 8.5'; saturated | 0 | Collect sample from 8-8.5' bgs @ 10:40 |
| | -9.0 | | | | | 8.5 - 10.0' No recovery | | |
| | -10.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-004
**DATE BEGAN:** 7/8/2008
**DATE FINISHED:** 7/8/2008
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | | | | | 10.0 - 12.0' No recovery | | |
| | -11.0 | | | | | | | |
| | -12.0 | 4 | NA | 2.0 | | 12.0 - 14.0' PT: Peat, trace sand at 12'; end of boring at 14' | 0 | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-005
**DATE BEGAN:** 7/8/2008
**DATE FINISHED:** 7/8/2008
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 2 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | Refusal @ 3' bgs due to concrete on first attempt |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Dark brown/black silt, fine-coarse angular gravel throughout, dry | | Collect sample from 1-1.5' bgs @ 9:49 |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Light brown sand (fine-coarse), loose, concrete pieces @ top and bottom, dry | | |
| | -3.0 | | | | | 2.0 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.5 | | 4.0 - 4.5' FILL: Light brown fine-coarse rounded gravel and sand, saturated | 0 | Collect sample from 4.5-5' bgs @ 9:54 |
| | -5.0 | | | | | 4.5 - 5.5' FILL: Dark brown silt and organic material, saturated | | |
| | -6.0 | | | | | 5.5 - 7.5' FILL: Light brown sand (fine-coarse), some clay from 6-6.5' bgs, saturated | | Collect sample from 6.5-7' bgs @ 9:56 |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | 7.5 - 8.0' No recovery | | |
| | -9.0 | 3 | NA | 4 | | 8.0 - 12.0' FILL: Light/reddish brown sand (fine-coarse), saturated, clay lenses at 11' and 11.5', trace silt from 11-12' bgs; peat in tip; end of boring at 12' | 0 | Collect sample form 8.5-9' bgs @ 10:01 |
| | -10.0 | | | | | | | Collect sample from 10.5-11' bgs @ 10:04 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-005A
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** Brian Senna/Will Lang
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 4.0 ft bgs
**GW DEPTH:** NE
**DRILLER:** Dave Myerchia
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | | | | | | 0.5 - 2.8' FILL: Dark brown silty sand (fine); some gravel, glass, shells; dry | 0 | |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | 0 | |
| | | | | | | 2.8 - 3.0' FILL: Crushed concrete; dry | | |
| | -3.0 | | | | | 3.0 - 3.5' FILL: Black/dark brown silty sand (fine); some gravel, glass, brick; dry | 0 | |
| | | | | | | 3.5 - 4.0' No recovery; end of boring @ 4.0' | | 125-SB-005A_0204 collected from 3.0-3.5' bgs @ 14:45 |
| | -4.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-006
**DATE BEGAN:** 6/26/08
**DATE FINISHED:** 6/26/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** E. Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | Collect sample from 0.5-1' bgs @ 11:24 |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Brown silt and sand (fine), firm, dry | | |
| | -2.0 | | | | | 1.5 - 3.0' FILL: Dark brown sand with red mottling, trace clay, trace organic material from 2.5'-3.0', firm, dry | | Collect sample from 2.5-3' bgs @ 11:26 |
| | -3.0 | | | | | 3.0 - 3.5' FILL: Dark brown silt, some sand (fine) and clay, firm, dry | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 2.5 | | 4.0 - 4.8' FILL: dark/red brown silt, some sand and clay, loose, moist | 0 | Collect sample from 4-4.5' bgs @ 11:35 |
| | -5.0 | | | | | 4.8 - 5.3' FILL: dark brown silt, firm, wet | | |
| | -6.0 | | | | | 5.3 - 6.5' FILL: dark brown sand (medium-coarse), some gravel, broken glass and concrete, yellow from 5.25-5.5' bgs, wet | | Collect sample from 6-6.5' bgs @ 11:38 |
| | -7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | -8.0 | 3 | NA | 2.0 | | 8.0 - 9.5' FILL: Light brown sand (fine-medium), trace clay, saturated | 0 | Collect sample from 9-9.5' bgs @ 11:45 |
| | -9.0 | | | | | 9.5 - 10.0' FILL: Silt and fine sand, trace clay, saturated | | |
| | -10.0 | | | | | 10.0 - 10.1' PT: Peat | | |
| | -11.0 | | | | | 10.1 - 12.0' No recovery; end of boring at 12' | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125 | **PROJECT NO:** 3480050143 | **BORING ID:** 125-SB-007

**DATE BEGAN:** 6/28/08 | **DATE FINISHED:** 7/7/08 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610 DT

**SAMPLING TOOL:** Macrocore | **COMPLETION DEPTH:** 13 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** G Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | Refusal at 2.0' and 4.2 ft bgs on three previous attempts, remobilized on 7/7/08 |
| | -1.0 | | | | | 1.0 - 1.8' FILL: Red brown silty sand with gravel (fine-medium), moist | | Collect sample form 1-1.5' bgs @ 8:55 |
| | -2.0 | | | | | 1.8 - 3.5' FILL: Dark brown silty sand (fine) with shells, brick, glass, gravel (fine-coarse), moist from 2.5' bgs | | Collect sample form 3-3.5' bgs @ 9:00 |
| | -3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.5 | | 4.0 - 5.0' FILL: Dark brown/black silty sand with gravel (fine-medium), glass, brick, and wood, potential COPR from 4.5-5' bgs, wet | 0 | Collect smaple from 4.5-5' bgs @ 9:05 |
| | -5.0 | | | | | 5.0 - 6.8' FILL: Light brown sand (fine) with trace silt, wet | | |
| | -6.0 | | | | | | | Collect sample from 6.5-7' bgs @ 9:10 |
| | -7.0 | | | | | 6.8 - 7.5' FILL: Light brown/brown sand (fine-medium), wet | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | -8.0 | 3 | | 3.5 | | 8.0 - 9.8' FILL: Light brown/brown sand (fine-medium), wet | 0 | Collect sample from 8.5-9' bgs @ 9:15 |
| | -9.0 | | | | | 9.8 - 10.0' FILL: Red brown sand (fine) with trace silt, wet | | |
| | -10.0 | | | | | 10.0 - 11.5' FILL: Light brown sand (fine-medium), stringy organic material from 11.3-11.5'; wet | | Collect sample from 10.5-11' bgs @ 9:20 |
| | -11.0 | | | | | | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | -12.0 | 4 | | 1.0 | | 12.0 - 13.0' PT: Dark brown peat, very moist, end of boring at 13.0' | 0 | |
| | -13.0 | | | | | | | |

PREPARED BY: EMJ

CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-008
**DATE BEGAN:** 7/8/08
**DATE FINISHED:** 7/8/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | Collect sample form 1-1.5' bgs @ 11:20 |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Red brown silt and trace gravel, firm, dry | | |
| | -2.0 | | | | | 1.5 - 2.5' FILL: Dark brown sand (fine), some gravel, wood frags, and brick, dry | | Collect sample from 3-3.5' bgs @ 11:22 |
| | -3.0 | | | | | 2.5 - 3.5' FILL: Dark brown and olive sand (fine-coarse) and silt, trace coal, wet at 3.0' | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.0 | | 4.0 - 4.5' FILL: Dark brown sand and gravel (fine-coarse), saturated | 0 | Collect sample from 4.5-5' bgs @ 11:24 |
| | -5.0 | | | | | 4.5 - 6.5' FILL: Light brown sand (fine), silt, and trace clay, saturated | | |
| | -6.0 | | | | | | | Collect sample from 6-6.5' bgs @ 11:26 |
| | -7.0 | | | | | 6.5 - 7.0' FILL: Light brown clay and sand, subangular gravel (fine-coarse), wet | | |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | 3 | NA | 4.0 | | 8.0 - 12.0' FILL: Light brown sand (fine-coarse), trace subangular gravel (fine), clay lens from 11-11.25', finer sand from 11.25-12', peat in tip, end of boring at 12' | 0 | Collect sample form 9-9.5' bgs @ 11:28 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | Collect sample from 11.5-12' bgs @ 11:30 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-008A
**DATE BEGAN:** 8/6/08
**DATE FINISHED:** 8/6/08
**INSPECTOR:** Brian Senna/Will Lang
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 4.0 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | | |
| | | S-1 | NA | 2.75 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | -1.0 | | | | | 0.5 - 1.3' FILL: Red brown silt (fine); some gravel (fine-medium), moist | 0 | |
| | -2.0 | | | | | 1.3 - 2.5' FILL: Dark brown silty sand (fine); some crushed glass, gravel (fine), moist | 0 | |
| | -3.0 | | | | | 2.5 - 2.8' FILL: Dark brown silty sand (fine); some crushed glass, gravel (fine), wood, moist | 0 | |
| | -4.0 | S-2 | NA | 3.0 | | 2.8 - 4.0' No recovery | 0 | 125-SB-008A_0406 collected from 4.0-4.5' bgs @ 13:30 |
| | -5.0 | | | | | 4.0 - 4.3' FILL: Dark brown silty sand (fine); some white clayey substance; moist | 0 | |
| | -6.0 | | | | | 4.3 - 7.0' SM: Light brown sand (fine-medium); some silt lenses; wet | 0 | |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | 0 | |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 9.0' SM: Light brown sand (fine-medium); wet | 0 | |
| | -9.0 | | | | | 9.0 - 9.5' SM: Red brown silt (fine); trace sand (fine); wet | 0 | |
| | -10.0 | | | | | 9.5 - 11.0' SM: Light brown sand (fine-medium); wet; some organic material at 10.0-10.5' | 0 | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | 0 | |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 16.0' PT: Dark brown peat; moist | 0 | 125-SB-008A_1214 collected from 12.5-13.0' bgs @ 13:45 |
| | -13.0 | | | | | | 0 | |
| | -14.0 | | | | | | 0 | 125-SB-008A_1416 collected from 14.5-15.0' bgs @ 13:50 |
| | -15.0 | | | | | | 0 | |
| | -16.0 | S-5 | NA | 2.0 | | 16.0 - 18.0' SW: Gray sand (fine-medium); end of boring at 18.0' | 0 | 125-SB-008A_1618 collected from 16.0-16.5' bgs @ 14:00 |
| | -17.0 | | | | | | 0 | |
| | -18.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-009
**DATE BEGAN:** 6/26/08
**DATE FINISHED:** 6/26/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 2.0 | | 0.0 - 1.0' ASPHALT: Asphalt and concrete | 0 | Drillers cored through asphalt and concrete |
| | -1.0 | | | | | 1.0 - 2.0' FILL: Light brown silt and sand (fine-medium), firm, moist | | Collect sample form 1-1.5' bgs @ 8:24; DUP @ 8:25 |
| | -2.0 | | | | | 2.0 - 3.0' FILL: Dark brown silt, trace clay, brick from 2.5-2.75' bgs, firm, moist | | Collect sample from 2-2.5' bgs @ 8:28 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.0 | | 4.0 - 4.8' FILL: Light brown silt, trace sand, loose, saturated | 0 | Collect sample from 4-4.5' bgs @ 8:35 |
| | -5.0 | | | | | 4.8 - 5.0' FILL: Brick, wet | | |
| | | | | | | 5.0 - 5.5' FILL: Black gravel (fine-coarse), silt, and organic material, wet | | |
| | -6.0 | | | | | 5.5 - 7.0' FILL: Light brown sand (fine), clay lense from 5.5-6' & 7.5-7.75', wet | | Collect sample from 6.5-7' bgs @ 8:38 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | 3 | NA | 4.0 | | 8.0 - 10.0' FILL: Light brown sand (fine-medium), saturated | 0 | Collect sample from 8.5-9' bgs @ 8:45 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 10.5' PT: Peat | | Collect sample from 10-10.5' bgs @ 8:47 |
| | -11.0 | | | | | 10.5 - 11.5' OH: Dark brown organic clay, fine sand from 10.75-11', saturated | | |
| | -12.0 | | | | | 11.5 - 12.0' PT: Peat; end of boring at 12' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-009A
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** Brian Senna/Will Lang
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** NE
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 6.0' Advance boring to 6' bgs to obtain additional samples | | Log of missing depths from 125-SB-009 |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | | | |
| | -4.0 | | | | | | | |
| | -5.0 | | | | | | | |
| | -6.0 | S-1 | NA | 1.0 | | 6.0 - 7.0' ML: Light brown silt; some lenses of black silt; wet | 0 | |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | 0 | 125-SB-009A_0608 collected from 6.5-7.0' bgs @ 14:05 |
| | -8.0 | S-2 | NA | 0.0 | | 8.0 - 12.0' No recovery | 0 | |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | | 0 | |
| | -12.0 | S-3 | NA | 3.5 | | 12.0 - 12.5' ML: Dark brown silt; heavy organic material; moist | 0 | |
| | -13.0 | | | | | 12.5 - 15.5' PT: Dark brown peat; moist | 0 | 125-SB-009A_1214 collected from 12.0-12.5' bgs @ 14:20 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | 0 | 125-SB-009A_1416 collected from 14.5-15.0' bgs @ 14:25 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-010
**DATE BEGAN:** 7/8/08
**DATE FINISHED:** 7/8/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** E Schaming
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 2.0' FILL: Light brown/grey silt with angular gravel (medium-coarse) and sand, concrete @ bottom, dry | | Collect sample from 1-1.5' bgs @ 14:18 |
| | -2.0 | | | | | 2.0 - 3.5' FILL: Dark brown silt and trace sand, some angular gravel (medium-coarse), 1" lens of white sand @ 3' bgs, trace coal, brick, dry | | Collect sample from 2.5-3' bgs @ 14:20 |
| | -3.0 | | | | | | | |
| | -4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | 2 | NA | 3.0 | | 4.0 - 4.5' FILL: Dark brown silt, some clay, trace gravel, dry | 0 | Collect sample from 4.5-5' bgs @ 14:24 |
| | -5.0 | | | | | 4.5 - 5.5' FILL: Light brown sand (fine-coarse), trace rounded gravel, wet | | |
| | -6.0 | | | | | 5.5 - 7.0' FILL: Light brown sand (fine-medium), some clay towards bottom, wet | | Collect sample from 6.5-7' bgs @ 14:26 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | 3 | NA | 2.0 | | 8.0 - 8.5' FILL: Dark brown (fine-coarse) sand and gravel, wet | 0 | |
| | -9.0 | | | | | 8.5 - 10.0' FILL: Dark brown silty clay, some rounded gravel (fine) from 9.5-10' , trace coarse sand, firm, saturated | | Collect sample form 9.5-10' bgs @ 14:32 |
| | -10.0 | | | | | 10.0 - 12.0' No recovery | | |
| | -11.0 | | | | | | | |
| | -12.0 | 4 | NA | 2.0 | | 12.0 - 13.0' FILL: Light brown clay and some rounded gravel from 12-12.5' bgs, trace silt, saturated | 0 | Collect sample from 12-12.5' bgs @ 14:35 |
| | -13.0 | | | | | 13.0 - 14.0' PT: Peat; end of boring at 14' | | |
| | -14.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-010A
**DATE BEGAN:** 7/31/08
**DATE FINISHED:** 7/31/08
**INSPECTOR:** Brian Senna/Will Lang
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4.0' Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Dave Myerchia
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 8.0' Advance borings to 8 ft bgs to obtain additional samples | | |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | | | |
| | -4.0 | | NA | 1 | | | | |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | | 0 | |
| | -8.0 | S-1 | NA | 0 | | 8.0 - 10.0' CL: Red brown clayey silt with fine-medium sand lenses | 0 | |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | 10.0 - 10.5' CL: Red brown silt with fine-medium sand and some fine-medium gravel | 0 | Sample 10.0-10.5' @ 7:55 |
| | -11.0 | | | | | 10.5 - 12.0' No recovery; end of boring @ 12' | 0 | |
| | -12.0 | | | | | | | |

PREPARED BY: CH
CHECKED BY: MWV

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-011
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 1.0' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 1.0 - 3.0' FILL: reddish brown silt, coarse gravel from 1.25-1.3'; very stiff; dry | 0 | 125-SB-011-0002 from 1.5-2.0' @ 855 |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | 3.0 - 3.5' FILL: light brown silty sand, trace fine gravel; moist | 0 | 125-SB-011-0204 from 3.0-3.5' @ 900 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.0 | | 4.0 - 6.0' FILL: light brown silty sand, some fine-medium gravel, yellow/green precipitate (COPR) from 5.5'; wet; end of boring at 6' | 0 | |
| | -5.0 | | | | | | 0 | 125-SB-011-0406 from 5.5-6.0' @ 905 |
| | -6.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-012
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 1.0' ASPHALT: asphalt and gravel | | |
| | -1.0 | | | | | 1.0 - 2.0' FILL: reddish brown silt | 0 | 125-SB-012-0002 from 1.0-1.5' @ 920 |
| | -2.0 | | | | | 2.0 - 3.5' FILL: dark brown silty sand with some fine to medium gravel; moist from 3.0' | 0 | |
| | -3.0 | | | | | | 0 | 125-SB-012-0204 from 3.0-3.5' @ 925 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.0 | | 4.0 - 5.0' FILL: dark brown silty sand with some fine to medium gravel | 0 | |
| | -5.0 | | | | | 5.0 - 5.5' FILL: light grey silty sand with fine to coarse gravel | 0 | 125-SB-012-0406 from 5.0-5.5' @ 930 |
| | -6.0 | | | | | 5.5 - 6.0' FILL: light brown silty sand with fine to medium gravel and yellow/green precipitate (COPR); end of boring at 6' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-013
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6.0 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: light brown silty sand with fine to coarse gravel, dry | | 125-SB-013-0002 from 0.5-1.0' bgs @ 1045 |
| | -1.0 | | | | | 1.0 - 1.5' FILL: concrete | 0 | |
| | | | | | | 1.5 - 2.5' FILL: reddish brown silty sand with green/grey lenses (COPR); very stiff; dry | | |
| | -2.0 | | | | | | 0 | 125-SB-013-0204 from 2.0-2.5' bgs @ 1050 |
| | | | | | | 2.5 - 3.0' FILL: dark brown silt, trace sand; moist | | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.0 | | 4.0 - 6.0' FILL: dark brown silt with trace sand; wet from 4.5'; end of boring at 6' | 0 | |
| | -5.0 | | | | | | 0 | 125-SB-013-0406 from 5.0-5.5' bgs @ 1055 |
| | -6.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-014
**DATE BEGAN:** 7/29/08
**DATE FINISHED:** 7/29/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 0.8' FILL: crushed concrete; dry | 0 | |
| | -2.0 | | | | | 0.8 - 3.0' FILL: dark brown silty sand with fine brick, fine coal, fine glass, shells; dry | 0 | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.5 | | 4.0 - 4.8' FILL: dark brown silty sand with fine brick, fine coal, fine glass, shells; moist | 0 | |
| | -5.0 | | | | | 4.8 - 6.0' FILL: reddish brown silty sand; wet from 5.0' | 0 | |
| | -6.0 | | | | | 6.0 - 6.5' FILL: light brown fine to medium sand; wet | 0 | |
| | -7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | -8.0 | S-3 | N/A | 1.5 | | 8.0 - 8.8' FILL: light brown fine to medium sand; wet | 0 | |
| | -9.0 | | | | | 8.8 - 9.5' FILL: reddish brown clayey silt, trace organic material; wet | 0 | |
| | -10.0 | | | | | 9.5 - 12.0' No recovery | | |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | N/A | 3.5 | | 12.0 - 15.5' PT: dark brown peat; moist | 0 | |
| | -13.0 | | | | | | 0 | |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | 0 | 125-SB-014-1416 from 14.5-15.0' bgs @ 1415 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-015
**DATE BEGAN:** 7/29/08
**DATE FINISHED:** 7/29/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 3.0' FILL: dark brown/black silty sand with fine shells, fine glass, fine coal; moist from 2.75' | 0 | |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 3.5 | | 4.0 - 4.5' FILL: dark brown/black silty sand with fine shells, fine glass, fine coal; moist | 0 | |
| | -5.0 | | | | | 4.5 - 6.0' FILL: light brown fine to medium sand; wet | 0 | |
| | -6.0 | | | | | 6.0 - 7.5' FILL: light brown/reddish brown fine to medium sand with lenses of clayey silt from 6.25-6.5'; wet | 0 | |
| | -7.0 | | | | | | 0 | |
| | -8.0 | S-3 | N/A | 3.5 | | 7.5 - 8.0' No recovery | | |
| | -9.0 | | | | | 8.0 - 8.3' FILL: light brown/reddish brown fine to medium sand; wet | 0 | |
| | -10.0 | | | | | 8.3 - 8.8' FILL: light brown/light grey silty sand with organic material; wet | 0 | |
| | -11.0 | | | | | 8.8 - 11.5' FILL: light grey fine sand; wet | 0 | |
| | -12.0 | S-4 | N/A | 2.0 | | 11.5 - 12.0' No recovery | 0 | |
| | -13.0 | | | | | 12.0 - 13.0' FILL: light grey fine sand; wet | 0 | 125-SB-015-1214 from 12.5-13.0' bgs @ 1320 |
| | -14.0 | | | | | 13.0 - 13.8' PT: dark brown peat; moist | 0 | |
| | | | | | | 13.8 - 14.0' SM: light brown silty sand and | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-015
**DATE BEGAN:** 7/29/08
**DATE FINISHED:** 7/29/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -14.0 | | | | | organic material; end of boring at 14' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-015A
**DATE BEGAN:** 8/8/08
**DATE FINISHED:** 8/8/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.5' FILL: dark brown/black silty sand with coal, glass, gravel; moist | | |
| | -1.0 | | | | | | 0 | |
| | | | | | | 1.5 - 3.5' FILL: brown silty sand, with fine to medium gravel; moist | | |
| | -2.0 | | | | | | 0 | |
| | | | | | | | | 125-SB-015A-0204 from 2.5-3.0' bgs @ 1320 |
| | -3.0 | | | | | | 0 | |
| | | | | | | 3.5 - 4.0' No recovery; end of boring at 4' | | |
| | -4.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-016
**DATE BEGAN:** 7/29/08
**DATE FINISHED:** 7/29/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | | |
| | | 1.5 | N/A | 1.5 | | 0.0 - 0.5' TOPSOIL | 0 | |
| | -1.0 | | | | | 0.5 - 1.5' FILL: light brown fine sand with fine coal and fine glass, dry | 0 | |
| | -2.0 | 2.0 | N/A | 2.0 | | 1.5 - 2.0' No recovery | 0 | |
| | | | | | | 2.0 - 2.3' FILL: fine to coarse gravel; moist | 0 | |
| | -3.0 | | | | | 2.3 - 6.5' FILL: light brown fine to medium sand; silt lenses from 2.3-4'; wet from 5' | | |
| | -4.0 | 3.5 | N/A | 3.5 | | | 0 | |
| | -5.0 | | | | | | 0 | |
| | -6.0 | | | | | | 0 | |
| | | | | | | 6.5 - 7.0' FILL: reddish brown clayey silt, wet | | |
| | -7.0 | | | | | 7.0 - 7.5' FILL: light brown/grey fine to medium sand; wet | 0 | |
| | -8.0 | 3.0 | N/A | 3.0 | | 7.5 - 8.0' No recovery | 0 | |
| | -9.0 | | | | | 8.0 - 9.5' FILL: light brown fine to coarse sand; wet | 0 | |
| | -10.0 | | | | | 9.5 - 11.0' FILL: light grey/light brown fine to medium sand; wet | 0 | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | 3.5 | N/A | 3.5 | | 12.0 - 12.5' FILL: light grey/light brown fine to medium sand; wet | 0 | |
| | -13.0 | | | | | 12.5 - 15.3' PT: dark brown peat; moist | 0 | |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | 15.3 - 15.5' SP: brown fine sand, some organic material, moist | 0 | 125-SB-016-1416 from 14.5-15.0' bgs @ 1205 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-017
**DATE BEGAN:** 06/23/09
**DATE FINISHED:** 06/23/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.25 | | 0.0 - 0.7' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 224 |
| | 1.0 | | | | | 0.7 - 1.0' FILL: Brown/light brown f-c sand, some f-m gravel; trace silt, brick, and clinker | | |
| | 2.0 | | | | | 1.0 - 3.3' FILL: Reddish brown silty fine sand, trace fine gravel and clinker | 0.0 | |
| | 3.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 7.3' FILL: Reddish brown silt, some fine sand; trace clay, fine gravel and clinker; wood and medium gravel from 5.5-5.7'; wood from 6.6-6.7'; greenish yellow clayey COPR with reddish brown COPR nodules from 7.0-7.3' | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | 0.0 | |
| | 7.0 | | | | | 7.3 - 7.5' FILL: Brown f-m sand, trace fine gravel and wood, trace green COPR mottling; moist | | |
| | 8.0 | R-3 | N/A | 4.0 | | 7.5 - 8.0' No recovery | 0.0 | |
| | 9.0 | | | | | 8.0 - 9.5' FILL: Brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | 9.5 - 10.0' FILL: Yellowish brown clayey COPR, some f-m sand; soft, wet | 0.0 | |
| | 11.0 | | | | | 10.0 - 11.5' FILL: Brown f-c sand, trace silt and wood | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.5 - 12.3' FILL: Dark grayish brown silty clay, trace fine sand and gravel; trace white COPR mottling; soft, wet | 0.5 | |
| | 13.0 | | | | | 12.3 - 15.8' PT: Very dark grayish brown (10YR 3/2) peat; stiff | 8.2<br>14.5<br>15.1<br>12.6<br>9.9 | 125-SB-017-1214 collected from 12.5-13.0' bgs @ 9:05 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.8 - 16.0' SP: Dark grayish brown (10YR 4/2) fine sand; wet; end of boring at 16' | 11.3<br>14.0 | Driller sealed hole with bentonite chips due to peat penetration |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-018
**DATE BEGAN:** 06/23/09
**DATE FINISHED:** 06/23/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 8.75 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.25 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 223 |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Brown f-m sand, some f-m gravel, trace silt and concrete | | |
| | 2.0 | | | | | 1.8 - 2.0' FILL: Concrete | | |
| | 3.0 | | | | | 2.0 - 3.3' FILL: Brown to reddish brown silty sand, some f-m gravel; trace clinker, brick, and coal; dense | | |
| | 4.0 | R-2 | N/A | 3.0 | | 3.3 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 8.8' FILL: Reddish brown silt, some clay, trace fine sand, gravel, and brick; moist from 5.5'; stiff | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 3.5 | | 8.8 - 9.4' FILL: Green/reddish brown/white soft clayey COPR; some white/reddish brown nodules, some wood; wet | 0.0 | |
| | 9.0 | | | | | 9.4 - 11.2' FILL: Dark brown f-m sand, trace f-m gravel, clinker, and silt; wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.2 - 11.5' FILL: Very dark grayish brown silty sand; wet; organic odors | | |
| | 12.0 | R-4 | N/A | 3.25 | | 11.5 - 12.0' No recovery | 0.0 | |
| | 13.0 | | | | | 12.0 - 12.5' FILL: Very dark grayish brown silty sand, some white/yellow COPR; dense | 10.2 | 125-SB-018-1214 collected from 13.0-13.5' bgs @ 9:55; DUP @ 10:00 |
| | 14.0 | | | | | 12.5 - 12.7' OL: Black (2.5Y 2.5/1) silty clay; trace organic material | 14.7<br>21.0 | |
| | 15.0 | | | | | 12.7 - 15.3' PT: Dark olive brown (2.5Y 3/3) to dark grayish brown (10YR 3/2) peat | 22.7<br>13.5 | |
| | 16.0 | | | | | 15.3 - 16.0' No recovery; end of boring at 16' | 17.8<br>20.9 | |

PREPARED BY: EJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-019
**DATE BEGAN:** 06/23/09
**DATE FINISHED:** 06/23/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 1.5' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 221 |
| | 1.0 | | | | | 1.5 - 3.0' FILL: Reddish brown f-m sand and silt, some f-m brick and gravel, trace concrete and coal, trace greeen/grey/yellow COPR mottling; moist from 2.5' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 6.0' FILL: Brown/reddish brown f-c sand and gravel, some brick, wood from 5.5-5.75'; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 9.3' FILL: Brownish yellow/pale greenish yellow clayey COPR, some f-c gravel and brick from 8.0'; soft, wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 3.5 | | | 0.0 | |
| | 9.0 | | | | | 9.3 - 9.5' FILL: Brown f-m sand, trace wood and green COPR mottling; wet | | |
| | 10.0 | | | | | 9.5 - 10.5' FILL: Dark brown f-m sand, trace silt; wet | | |
| | 11.0 | | | | | 10.5 - 11.5' FILL: Dark brown silty sand, trace clay; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.5 - 12.0' No recovery | 0.6 | |
| | 13.0 | | | | | 12.0 - 12.2' OL: Black (2.5Y 2.5/1) silty clay, trace organic material | 17.2<br>15.9 | 125-SB-019-1214 collected from 12.5-13.0' bgs @ 10:55 |
| | 14.0 | | | | | 12.2 - 16.0' PT: Dark olive brown (2.5YR 3/3) to very dark grayish brown (10YR 3/2) peat; end of boring at 16' | 35.2<br>24.9 | |
| | 15.0 | | | | | | 28.3<br>19.5 | |
| | 16.0 | | | | | | 20.4<br>18.8 | |

PREPARED BY: EJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-020
**DATE BEGAN:** 6/23/09
**DATE FINISHED:** 6/23/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | | Field Map #219 |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Dark brown f-c sand and f-m gravel | | |
| | 2.0 | | | | | 1.8 - 2.3' FILL: Reddish brown silty sand, some f-m gravel and brick | | |
| | 3.0 | | | | | 2.3 - 4.0' FILL: Reddish brown to dark grown silt, some fine sand, trace clay, f-m gravel, coal and brick, trace greenish yellow COPR mottling, trace wood from 3.8'; stiff | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.5' FILL: Dark brown silty sand, some f-m gravel and brick; wet | | |
| | 5.0 | | | | | 4.5 - 6.5' FILL: Reddish brown to brown f-m brick, some f-c sand and f-m gravel, trace yellow clayey COPR from 6.4'; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.5' FILL: Reddish brown to brown f-m brick, some f-c sand and f-m gravel; wet | | |
| | 9.0 | | | | | 8.5 - 10.5' FILL: Brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' FILL: Dark brown silty sand, trace clay; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 12.4' FILL: Black sandy clay, trace fine gravel, trace yellow COPR from 12.0-12.2'; wet | | |
| | 13.0 | | | | | 12.4 - 16.0' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat; end of boring at 16.0' | | 125-SB-020-1214 collected from 13.0-13.5' bgs @ 11:45 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: FP
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-021
**DATE BEGAN:** 6/23/09
**DATE FINISHED:** 6/23/09
**INSPECTOR:** J Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.5' ASPHALT: Asphalt and gravel | 0.0 | |
| | 1.0 | | | | | 1.5 - 2.8' FILL: Reddish brown silty sand, come f-m gravel, trace brick, clinker, glass, coal and wood, trace yellow COPR mottling from 2.0-2.2' | | |
| | 2.0 | | | | | 2.8 - 3.8' FILL: Dark brown silty sand, trace f-m gravel and wood; moist | | |
| | 3.0 | | | | | 3.8 - 4.0' FILL: Brick | | |
| ▽ | 4.0 | R-2 | N/A | 1.5 | | 4.0 - 5.0' FILL: Brick, wood and gravel; wet | 0.0 | |
| | 5.0 | | | | | 5.0 - 5.3' FILL: Light brown f-c sand, some f-m gravel; wet | | |
| | 6.0 | | | | | 5.3 - 5.5' FILL: Yellow/white clayey COPR, trace fine sand; wet | | |
| | 7.0 | | | | | 5.5 - 8.0' FILL: No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.0' FILL: Dark brown f-c sand, some fine brick and gravel, yellow clayey COPR from 8.75-8.9'; wet | 0.0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Brown silty sand and f-m gravel, olive green COPR and fibrous wood from 9.1-9.2'; wet | | |
| | 10.0 | | | | | 9.5 - 11.5' FILL: Brown f-c sand, trace silt; wet | | |
| | 11.0 | | | | | 11.5 - 12.0' FILL: Brown fine sand, trace silt; wet | | |
| | 12.0 | R-4 | N/A | 2.0 | | | 0.0 | |

PREPARED BY: MC
CHECKED BY: TG

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-021
**DATE BEGAN:** 6/23/09
**DATE FINISHED:** 6/23/09
**INSPECTOR:** J Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | R-4 | N/A | 2.0 | | 12.0 - 12.5' FILL: Brown fine sand, trace silt, some lenses of f-c sand; wet<br>12.5 - 13.0' FILL: Brown silt and clay, trace fine sand, trace light brown to white clayey COPR; wet<br>13.0 - 13.3' OL: Black sitly clay, trace organic material; wet<br>13.3 - 14.0' PT: Dark olive brown (2.5Y 3/3) peat<br>14.0 - 16.0' No recovery; end of boring at 16.0' | 0.0 | 125-SB-021-1214 collected from 13.5-14.0' bgs @13:15 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: TG

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-022
**DATE BEGAN:** 6/23/09
**DATE FINISHED:** 6/23/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #222 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Grey f-m gravel | | |
| | 3.0 | | | | | 2.0 - 2.5' FILL: Brick, some brown silty sand | | |
| | 4.0 | R-2 | N/A | 2.5 | | 2.5 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 5.5' FILL: Brown f-c sand, brick and gravel, some wood from 5.0'; wet | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Yellow/white/light brown clayey COPR, trace f-m gravel and wood from 5.5-6.0'; wet | | |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.6' FILL: Brown f-m sand and yellow clayey COPR, trace f-m gravel and brick; wet | 0.0 | |
| | 9.0 | | | | | 9.6 - 11.0' FILL: Brown f-m sand, trace silt and fine gravel; wet | | |
| | 10.0 | | | | | 11.0 - 12.0' FILL: Brown to dark brown silty fine sand, trace clay; wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 3.5 | | 12.0 - 12.3' FILL: White/light brown clayey COPR; wet | 0.0 | |
| | 13.0 | | | | | 12.3 - 12.5' OL: Black (2.5Y 2.5/1) silty clay, trace organic material; wet | 0.1<br>4.3<br>8.7 | 125-SB-022-1214 collected from 13.0-13.5' bgs @ 14:00 |
| | 14.0 | | | | | 12.5 - 15.5' PT: Dark olive brown (2.5Y 3/3) to very dark brown (7.5YR 2.5/2) peat | 12.5<br>7.9 | |
| | 15.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16.0' | 18.1<br>9.0 | |
| | 16.0 | | | | | | | |

PREPARED BY: FP
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-023
**DATE BEGAN:** 6/24/09
**DATE FINISHED:** 6/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0.0 | Field Map #214 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Brown silty sand, some f-m gravel and concrete, trace brick, clinker and glass | | |
| | 2.0 | | | | | 2.0 - 4.0' FILL: Reddish brown silt, trace clay and fine sand; very stiff | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 5.0' FILL: Concrete | 0.0 | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Light brown to white clayey COPR, trace dark brown sand; wet | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Brown silty sand (f-m from 5.5-5.8'), some clay from 5.8-6.0'; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.3' FILL: Brown sandy clay; wet | 0.0 | 125-SB-023-0608 collected from 7.5-8.0' bgs @ 8:05; HOLD |
| | 9.0 | | | | | 8.3 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 12.0' | 3.1<br>4.7<br>11.9 | 125-SB-023-0810 collected from 8.5-9.0' bgs @ 8:10 |
| | 10.0 | | | | | | 5.5<br>7.8 | 125-SB-023-1012 collected from 10.0-10.5' bgs @ 8:15; HOLD |
| | 11.0 | | | | | | 4.5 | |
| | 12.0 | | | | | | 9.0 | |

PREPARED BY: FP
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-024
**DATE BEGAN:** 6/24/09
**DATE FINISHED:** 6/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #214 |
| | 1.0 | | | | | 0.5 - 1.8' FILL: Brown f-m sand and f-m gravel | | |
| | 2.0 | | | | | 1.8 - 3.3' FILL: Reddish brown silty sand, some f-m gravel, trace brick, clinker, and coal | | |
| | 3.0 | | | | | 3.3 - 4.0' FILL: Reddish brown clayey silt, trace fine sand and gravel; stiff | | |
| | 4.0 | R-2 | N/A | 2.75 | | 4.0 - 5.3' FILL: Reddish brown clayey silt, trace fine sand and gravel, white/green COPR from 5.1'; stiff; wet from 5.0' | 0.0 | |
| ▽ | 5.0 | | | | | 5.3 - 6.0' FILL: Brown f-m sand | | 125-SB-024-0406 collected from 5.0-5.5' bgs @ 8:45 |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Brown silty fine sand; wet | | 125-SB-024-0608 collected from 6.0-6.5' bgs @ 8:50 |
| | 7.0 | | | | | 6.5 - 6.8' FILL: Brown sandy clay; wet<br>6.8 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown sandy clay; wet | 0.0 | |
| | 9.0 | | | | | | | 125-SB-024-0810 collected from 9.0-9.5' bgs @ 8:55 |
| | 10.0 | | | | | 10.0 - 12.0' FILL: Brown f-m sand, trace silt; wet | | |
| | 11.0 | | | | | | | 125-SB-024-1012 collected from 11.0-11.5' bgs @ 9.00; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: EJ
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-025
**DATE BEGAN:** 6/24/09
**DATE FINISHED:** 6/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #212 |
| | 1.0 | | | | | 0.5 - 1.8' FILL: Brown f-m sand and f-m gravel | | |
| | 2.0 | | | | | 1.8 - 3.2' FILL: Reddish brown silty sand, some fine gravel, trace clinker, brick, and coal | | |
| | 3.0 | | | | | 3.2 - 3.5' FILL: Concrete | | |
| | 4.0 | R-2 | N/A | 3.5 | | 3.5 - 4.0' FILL: Brown, f-c clayey sand, some f-m gravel, trace clinker, glass, and coal | 0.0 | |
| | 5.0 | | | | | 4.0 - 6.0' FILL: Brown/reddish brown silt and clay, some f-c sand and fine gravel, trace brick, wet from 5.0' | | |
| | 6.0 | | | | | 6.0 - 6.3' FILL: Brown/white/green clayey COPR; wet | | |
| | 7.0 | | | | | 6.3 - 7.5' FILL: Brown silty sand, some f-c sand from 6.5-6.75', trace silt, trace organic material from 6.25-6.4'; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 7.5 - 8.0' No recovery | 0.0 | 125-SB-025-0608 collected from 7.0-7.5' bgs @ 9:35 |
| | | | | | | 8.0 - 8.3' FILL: Brown f-m sand, trace silt; wet | | |
| | 9.0 | | | | | 8.3 - 10.0' FILL: Brown silty clay, trace fine sand; wet | | 125-SB-025-0810 collected from 9.0-9.5' bgs @ 9:40 |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Brown f-m sand; wet | | 125-SB-025-1012 collected from 10.5-11.0' bgs @ 9:45; HOLD |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Brown, silty sand, some organic material from 11-11.25', trace clay; wet; end of boring @ 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-026
**DATE BEGAN:** 6/24/09
**DATE FINISHED:** 6/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #210 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown silty sand and f-m gravel | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Reddish brown/brown/black silty sand, trace fine gravel, brick, clinker, wood | | |
| | 3.0 | | | | | 2.0 - 2.5' FILL: Concrete | | |
| | | | | | | 2.5 - 3.0' FILL: Brick | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 5.3' FILL: Brown silty clay, some f-m gravel and brick; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.3 - 7.0' FILL: Brown f-c sand, trace silt, white/green clayey COPR from 5.25-5.3', some clay from 6.5-6.7'; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.0' FILL: Brown sandy clay; wet; soft | 0.0 | 125-SB-026-0608 collected from 6.5-7.0' bgs @ 10:20; HOLD |
| | 9.0 | | | | | 9.0 - 12.0' FILL: Brown f-m sand, trace silt, some clay from 11.8'; wet; end of boring at 12.0' | | 125-SB-026-0810 collected from 8.5-9.0' bgs @ 10:25 |
| | 10.0 | | | | | | | 125-SB-026-1012 collected from 10.5-11.0' bgs @ 10:30; HOLD |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-027
**DATE BEGAN:** 6/24/09
**DATE FINISHED:** 6/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5.25 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0.0 | Field Map #213 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Reddish brown silty fine sand, some fine brick and gravel | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Concrete | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Reddish brown silt, some fine sand, trace wood and fine gravel | | |
| | 4.0 | R-2 | N/A | 1.0 | | 4.0 - 4.5' FILL: Reddish brown silt, some fine sand, trace wood and fine gravel | 0.0 | Due to poor recovery, the volume confirmation sampling was switched to 125-SB-028 |
| | | | | | | 4.5 - 4.8' FILL: Wood | | |
| | 5.0 | | | | | 4.8 - 5.0' FILL: F-m gravel and brown clayey sand; wet @ 5.0' | | |
| | 6.0 | | | | | 5.0 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.3' FILL: Brown sandy clay; wet | 0.0 | 125-SB-027-0810 collected from 8.5-9.0' bgs @ 11:05; DUP @ 11:08 |
| | 9.0 | | | | | 9.3 - 11.7' FILL: Brown f-m sand, trace silt, some clay from 11-11.25'; wet | | |
| | 10.0 | | | | | | | 125-SB-027-1012 collected from 11.0-11.5' bgs @ 11:10 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | 11.7 - 12.0' FILL: Brown silty clay, trace fine sand; wet; end of boring @ 12.0' | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-028
**DATE BEGAN:** 6/24/09
**DATE FINISHED:** 6/24/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0.0 | Field Map #215 |
| | 1.0 | | | | | 1.0 - 4.0' FILL: Reddish brown silty sand, some f-m gravel, trace brick, clincker and coal | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 6.0' FILL: Reddish brown silty sand, some f-m gravel, trace brick, clincker and coal | 0.0 | 125-SB-028-0406 collected from 4.5-5.0' bgs @ 11:40 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 6.3' FILL: White/green/borwn clayey COPR; wet | | 125-SB-028-0608 collected from 6.0-6.5' bgs @ 11:45 |
| | 7.0 | | | | | 6.3 - 8.0' FILL: Brown f-c sand, trace silt and clay, trace white/brown COPR from 6.3-6.5'; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown silty clay, trace fine sand; wet | 0.0 | 125-SB-028-0810 collected from 9.0-9.5' bgs @ 11:05; DUP @ 11:50 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Brown f-m sand, trace silt; wet | | 125-SB-028-1012 collected from 11.0-11.5' bgs @ 11:55; HOLD |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Brown silty fine sand, some clay from 11.8'; wet; end of boring @ 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-029
**DATE BEGAN:** 6/25/09
**DATE FINISHED:** 6/25/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #207; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.5' VOID | | Driller cored through concrete |
| | -2.0 | R-1 | N/A | 2.5 | | -2.5 - -1.0' FILL: Brown f-m sand, trace coal and brick; moist | 0.0 | |
| | -1.0 | | | | | -1.0 - 1.5' FILL: Reddish brown silty sand, trace fine gravel and coal; concrete from 0.7-1.0' ags | | |
| | 0.0 | R-2 | N/A | 4.0 | | | 0.0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Brown f-m sand | | |
| | 3.0 | | | | | 3.0 - 5.0' FILL: Brick, gravel, and wood; some dark brown f-c sand and wet from 4.0' bgs | | |
| | 4.0 | R-3 | N/A | 3.25 | | | 0.0 | |
| | 5.0 | | | | | 5.0 - 5.3' FILL: Green/white clayey COPR, some f-m sand; wet | | 125-SB-029-0406 collected from 5.0-5.5' bgs @ 10:45 |
| | 6.0 | | | | | 5.3 - 7.3' FILL: Brown f-c sand, trace silt, f-m gravel from 6.0-6.5' bgs; wet | | 125-SB-029-0608 collected from 6.5-7.0' bgs @ 10:50; HOLD |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | 7.3 - 8.0' No recovery | | |
| | 9.0 | R-4 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown silty clay, trace fine sand; wet | 0.0 | 125-SB-029-0810 collected from 9.5-10.0' bgs @ 10:55 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.0 - 12.0' FILL: Brown f-m sand, trace silt; wet; end of boring @ 12.0' bgs | | 125-SB-029-1012 collected from 11.0-11.5' bgs @ 11:00; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, Jersey City, New Jersey
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-030
**DATE BEGAN:** 6/25/09
**DATE FINISHED:** 6/25/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4 ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #206; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.5' VOID | | |
| | | R-1 | N/A | 2.5 | | -2.5 - -1.0' FILL: Brown f-m sand, trace coal and brick; moist | 0.0 | Driller cored through concrete; moved 2 ft. SW due to thick concrete |
| | -2.0 | | | | | | | |
| | -1.0 | | | | | -1.0 - 0.0' FILL: Reddish brown silty sand, trace fine gravel and coal | | |
| | 0.0 | R-2 | N/A | 3.5 | | 0.0 - 1.0' FILL: Reddish brown fine sand | 0.0 | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Brown/reddish brown/dark brown f-m sand and gravel; trace silt, coal, and brick; clinker from 2.0-2.2' bgs | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brick, wood and gravel | | |
| ▽ | 4.0 | R-3 | N/A | 3.0 | | 3.5 - 4.0' No recovery | 0.0 | |
| | | | | | | 4.0 - 5.5' FILL: Brick, wood, and gravel, some dark brown sand, some white clayey COPR from 5.3-5.4' bgs; wet | | 125-SB-030-0406 collected from 5.0-5.5' bgs @ 11:55 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.0' FILL: Dark brown silty sand, trace brick and coal; wet | | |
| | 7.0 | | | | | 6.0 - 7.0' FILL: Brown f-m sand, trace silt; wet | | 125-SB-030-0608 collected from 6.5-7.0' bgs @ 12:00; HOLD |
| | 8.0 | R-4 | N/A | 4.0 | | 7.0 - 8.0' FILL: No recovery | 0.0 | |
| | | | | | | 8.0 - 8.8' FILL: Brown f-m sand, trace silt; wet | | |
| | 9.0 | | | | | 8.8 - 10.3' FILL: Brown silty clay, trace fine sand; wet | | 125-SB-030-0810 collected from 9.0-9.5' bgs @ 12:05 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.3 - 12.0' FILL: Brown f-m sand, trace silt; wet; end of boring @ 12.0' bgs | | 125-SB-030-1012 collected from 11.5-12.0' bgs @ 12:10; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-031
**DATE BEGAN:** 6/25/09
**DATE FINISHED:** 6/25/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #209; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.5' VOID | | |
| | -2.0 | R-1 | N/A | 2.5 | | -2.5 - -1.0' FILL: Brown f-m sand, trace coal and brick; moist | 0.0 | |
| | -1.0 | | | | | -1.0 - 0.0' FILL: Reddish brown silty sand, trace fine gravel and coal | | |
| | 0.0 | R-2 | N/A | 3.5 | | 0.0 - 2.5' FILL: Reddish brown silt and fine sand, some f-m gravel and brick, trace to some clay, lens of white COPR @ 2.5' bgs | 0.0 | MD collected sample for DPC test |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Brick | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-3 | N/A | 2.5 | | 4.0 - 5.3' FILL: Dark brown f-m sand and gravel, some wood and brick; wet | 0.0 | MD collected sample for DPC test |
| | 5.0 | | | | | 5.3 - 6.5' FILL: Dark brown/brown f-m sand, some silt from 6.0' bgs; wet | | |
| | 6.0 | | | | | | | 125-SB-031-0608 collected from 6.0-6.5' bgs @ 13:25; HOLD |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-4 | N/A | 4.0 | | 8.0 - 9.8' FILL: Brown, silty clay, trace fine sand; wet | 0.0 | |
| | 9.0 | | | | | | | 125-SB-031-0810 collected from 9.0 9.5' bgs @ 13:30 |
| | 10.0 | | | | | 9.8 - 12.0' FILL: Brown f-m sand, trace to some silt; wet; end of boring @ 12.0' bgs | | |
| | 11.0 | | | | | | | 125-SB-031-1012 collected from 11.0-11.5' bgs @ 13:35; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-032
**DATE BEGAN:** 6/25/09
**DATE FINISHED:** 6/25/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #208; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.5' VOID | | |
| | -2.0 | R-1 | N/A | 2.5 | | -2.5 - -1.8' FILL: Brown f-m sand and gravel | 0.0 | 125-SB-032-0402AG collected from 2.5-2.0' ags @ 14:05 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| | -1.0 | | | | | -1.8 - 0.0' FILL: Reddish brown fine sand, trace silt | | |
| | 0.0 | R-2 | N/A | 3.5 | | 0.0 - 3.0' FILL: Reddish brown fine sand, trace silt, trace clay and f-m gravel; moist from 2.5' bgs | 0.0 | 125-SB-032-0200AG collected from 0.5-0.0' ags @ 14:10 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown f-c sand, trace silt and gravel | | |
| | 4.0 | R-3 | N/A | 2.5 | | 3.5 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Brick, gravel, and wood; wet | | |
| | 6.0 | | | | | 5.0 - 6.5' FILL: Brown f-m sand, trace silt; white/green COPR from 5.0-5.4' bgs; wet | | 125-SB-032-0406 collected from 5.0-5.5 bgs @ 14:30; Hex Chromium<br>125-SB-032-0608 collected from 6.0-6.5' bgs @ 14:35; Hex Chromium |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-4 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown silty clay, trace fine sand; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.0' FILL: Brown silty sand, wet; end of boring @ 12.0' bgs | | 125-SB-032-0810 collected from 9.5-10.0' bgs @ 14:40;Hex Chromium |
| | 11.0 | | | | | | | 125-SB-032-1012 collected from 11.5-12.0' bgs @ 14:45; Hex Chromium; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, Jersey City, New Jersey
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-033
**DATE BEGAN:** 6/26/09
**DATE FINISHED:** 6/26/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #181; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 2.0 | | -2.0 - -1.0' FILL: Brown f-m sand | 0.0 | |
| | -1.0 | | | | | -1.0 - 3.5' FILL: Reddish brown silty sand, some f-m gravel; trace concrete, brick, clinker, and coal | | |
| | 0.0 | R-2 | N/A | 3.5 | | | 0.0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-3 | N/A | 4.0 | | 4.0 - 6.0' FILL: Reddish brown silty sand; trace f-m gravel, concrete, brick, clinker, and coal | 0.0 | |
| ▼ | 6.0 | | | | | 6.0 - 6.5' FILL: Brick and wood; wet | | |
| | 7.0 | | | | | 6.5 - 7.8' FILL: Brown silty sand; wet | | 125-SB-033-0608 collected from 7.0-7.5' bgs @ 9:45; HOLD |
| | 8.0 | R-4 | N/A | 4.0 | | 7.8 - 9.5' FILL: Brown silty clay, trace sand; wet | 0.0 | |
| | 9.0 | | | | | | | 125-SB-033-0810 collected from 9.0-9.5' bgs @ 9:50 |
| | 10.0 | | | | | 9.5 - 12.0' FILL: Brown f-m sand, trace silt; wet; end of boring @ 12.0' bgs | | |
| | 11.0 | | | | | | | 125-SB-033-1012 collected from 11.5-12.0' bgs @ 9:55; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, Jersey City, New Jersey
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-034
**DATE BEGAN:** 6/26/09
**DATE FINISHED:** 6/26/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #180; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 2.0 | | -2.0 - -1.0' FILL: Brown f-m sand | 0.0 | |
| | -1.0 | | | | | -1.0 - -0.3' FILL: Reddish brown fine sand, trace fine gravel and silt | | |
| | 0.0 | R-2 | N/A | 2.5 | | -0.3 - 0.0' FILL: Concrete | 0.0 | |
| | 1.0 | | | | | 0.0 - 2.0' FILL: Reddish brown silty sand, some fine gravel, trace coal and brick | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark brown f-m sand and clinker, some concrete | | |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | R-3 | N/A | 2.2 | | 4.0 - 6.2' FILL: Brown silty sand, some f-m gravel; trace clay, concrete, brick, clinker, and coal; trace white clayey COPR @ 6.2' bgs; wet from 5.0' bgs | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.2 - 8.0' No recovery | | |
| | 8.0 | R-4 | N/A | 4.0 | | 8.0 - 8.8' FILL: Yellow/white clayey COPR, some gravel, trace glass | 0.0 | 125-SB-034-0810 collected from 8.0-8.5' bgs @ 10:15 |
| | 9.0 | | | | | 8.8 - 9.0' FILL: Brown f-c sand, some wood and fine gravel | | |
| | 10.0 | | | | | 9.0 - 13.0' FILL: Brown silty sand, some clay from 11.75' bgs; seam of white clayey COPR and black clay from 12.9' bgs | | |
| | 11.0 | | | | | | | |
| | 12.0 | R-5 | N/A | 2.0 | | | 0.0 | |
| | 13.0 | | | | | | 0.0 | |
| | 14.0 | | | | | 13.0 - 14.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 14.0' bgs | 8.0<br>21.3<br>4.4 | 125-SB-034-1012 collected from 13.5-14.0' bgs @ 10:30 |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-035
**DATE BEGAN:** 6/26/09
**DATE FINISHED:** 6/26/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14.5 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #179; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 2.0 | | -2.0 - -0.3' FILL: Brown f-m sand | 0.0 | |
| | -1.0 | | | | | -0.3 - 0.0' FILL: Reddish brown silty sand; trace fine gravel, brick, coal, and clinker | | 125-SB-035-0200AG collected from 1.0-0.5' ags @ 10:55 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| | 0.0 | R-2 | N/A | 4.0 | | 0.0 - 4.0' FILL: Reddish brown/brown/dark brown silty sand; trace fine gravel and reddish brown COPR nodules from 1.8-2.2' bgs; moist from 2.0' bgs | 0.0 | 125-SB-035-0002 collected from 1.5-2.0 bgs @ 11:00; Hex Chromium |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | 125-SB-035-0204 collected from 3.5-4.0 bgs @ 11:05; Hex Chromium |
| | 3.0 | | | | | | | |
| | 4.0 | R-3 | N/A | 2.5 | | 4.0 - 5.5' FILL: Brick and wood, some dark brown f-m sand; wet | 0.0 | 125-SB-035-0406 collected from 4.0-4.5 bgs @ 11:10; Hex Chromium; low sample volume |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Yellow/light brown clayey COPR, trace fine sand; wet | | 125-SB-035-0608 collected from 6.0-6.5' bgs @ 11:15; Hex Chromium |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-4 | N/A | 4.0 | | 8.0 - 9.0' FILL: Yellow/light brown clayey COPR, trace fine sand; wet | 0.0 | 125-SB-035-0810 collected from 8.5-9.0' bgs @ 11:20; Hex Chromium |
| | 9.0 | | | | | 9.0 - 11.0' FILL: Brown f-m sand, trace silt, some green-stained wood from 9.1-9.2' bgs; wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Dark brown clayey silt, trace fine sand; wet | | 125-SB-035-1012 collected from 11.5-12.0' bgs @ 11:25; Hex Chromium |
| | 12.0 | R-5 | N/A | 2.5 | | 12.0 - 12.5' FILL: White clayey COPR and black clayey silt, wet | 0.0<br>0.0 | |
| | 13.0 | | | | | 12.5 - 14.5' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 14.5' bgs | 11.6<br>12.3<br>8.9<br>7.4 | 125-SB-035-1214 collected from 13.5-14.0' bgs @ 11:30; Hex Chromium; HOLD |
| | 14.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, Jersey City, New Jersey
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-036
**DATE BEGAN:** 6/26/09
**DATE FINISHED:** 6/26/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 5 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.1' CONCRETE | | Field Map #216; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.1 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 1.0 | | -2.0 - -1.0' FILL: Brown fine sand, trace clinker and coal | 0.0 | |
| | -1.0 | | | | | -1.0 - 0.0' No recovery | | |
| | 0.0 | R-2 | N/A | 3.0 | | 0.0 - 0.8' FILL: Brown fine sand, trace clinker and coal | 0.0 | |
| | 1.0 | | | | | 0.8 - 2.3' FILL: Reddish brown sandy silt, some fine gravel, clinker, brick, coal, and concrete; moist from 1.5' bgs | | |
| | 2.0 | | | | | 2.3 - 3.0' FILL: Dark brown sandy silt, trace clay; very stiff | | |
| | 3.0 | | | | | 3.0 - 5.0' No recovery; refusal at 5.0' bgs | | |
| | 4.0 | R-3 | N/A | 0.0 | | | 0.0 | |
| | 5.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-037
**DATE BEGAN:** 6/26/09
**DATE FINISHED:** 6/26/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.1' CONCRETE | | |
| | -3.0 | | | | | -3.1 - -2.0' VOID | | |
| | -2.0 | N/A | N/A | N/A | | -2.0 - 4.0' FILL: See 125-SB-036 log for details | N/A | |
| | -1.0 | | | | | | | |
| | 0.0 | N/A | N/A | N/A | | | N/A | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-1 | N/A | 1.5 | | 4.0 - 5.5' FILL: Brown/dark brown silty sand, some f-m gravel and brick, trace clay and clinker; wet from 5.0' | 0.0 | Boring located in warehouse 4 ft above parking lot grade. Second attempt at Field Map #179; moved 2 ft NW of 125-SB-036. Driller cored through concrete and advanced to 4 ft bgs before sampling. |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-2 | N/A | 4.0 | | 8.0 - 9.0' FILL: Yellow/white clayey COPR, trace sand and glass; trace green-stained wood @ 8.9'; wet | 0.0 | |
| | 9.0 | | | | | 9.0 - 11.0' FILL: Brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Dark brown clayey silt, trace fine sand; wet | | |
| | 12.0 | R-3 | N/A | 2.0 | | 12.0 - 12.8' FILL: White clayey COPR, trace sand; wet | 0.0 | |
| | 13.0 | | | | | 12.8 - 14.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 14.0' bgs | 0.0<br>5.3<br>12.8<br>9.7 | 125-SB-037-1214 collected from 13.5-14.0' bgs @ 13:20 |
| | 14.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-038
**DATE BEGAN:** 6/29/09
**DATE FINISHED:** 6/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 1 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #218; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 2.0 | | -2.0 - -1.0' FILL: Brown/dark brown fine sand | 0.0 | |
| | -1.0 | | | | | -1.0 - 1.0' FILL: Reddish brown silt and fine sand; trace fine gravel, concrete, brick, and clinker | | |
| | 0.0 | R-2 | N/A | 2.0 | | | 0.0 | |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Dark brown sandy silt; wet | | |
| | 2.0 | | | | | 1.8 - 2.0' FILL: Brick and f-m gravel, some wood and f-m sand; wet | | |
| | 3.0 | | | | | 2.0 - 4.0' No recovery | | |
| | 4.0 | R-3 | N/A | 0.5 | | 4.0 - 4.5' FILL: Brick and f-m gravel, some wood and f-m sand; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 12.0' No recovery | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-4 | N/A | 0.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | R-5 | N/A | 2.0 | | 12.0 - 13.0' FILL: Brown silty clay, trace fine sand; very soft, wet | 0.0 | |
| | 13.0 | | | | | | 0.0 | |
| | 14.0 | | | | | 13.0 - 13.6' OL: Very dark grayish brown (10YR 3/2) clayey silt, some organic material; moist, firm | 0.0<br>8.4<br>19.8 | 125-SB-038-1214 collected from 13.5-14.0' bgs @ 8:25 |
| | | | | | | 13.6 - 14.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 14.5' bgs | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-039
**DATE BEGAN:** 6/29/09
**DATE FINISHED:** 6/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #217; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 2.0 | | -2.0 - -1.0' FILL: Brown f-m sand | 0.0 | |
| | -1.0 | | | | | -1.0 - 2.0' FILL: Reddish brown silt, some f-m sand; trace fine gravel, concrete, and brick; moist from 1.5' | | |
| | 0.0 | R-2 | N/A | 2.5 | | | 0.0 | |
| | 1.0 | | | | | 2.0 - 2.5' FILL: Dark brown fine sand, trace fine gravel and clinker; wet | | |
| | 2.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-3 | N/A | 3.5 | | 4.0 - 7.3' FILL: Reddish brown/brown/dark brown silt, some f-m sand and gravel; trace clinker, wood, and brick; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 7.3 - 7.5' FILL: Yellow clayey COPR, trace f-m sand; wet | | |
| | 7.0 | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-4 | N/A | 2.5 | | 8.0 - 8.5' FILL: Yellow/white clayey COPR, trace f-m sand; wet | 0.0 | |
| | 9.0 | | | | | 8.5 - 10.3' FILL: Brown f-m sand, trace silt | | |
| | 10.0 | | | | | 10.3 - 10.5' FILL: Dark brown silt, some fine sand; wet | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | 0.0 | |
| | 12.0 | R-5 | N/A | 4.0 | | 12.0 - 12.5' FILL: Dark brown silt, some fine sand; wet | 0.0 | |
| | 13.0 | | | | | 12.5 - 12.7' FILL: Black fine sand, some clinker, trace silt and white/green COPR; wet | 0.3 | 125-SB-039-1214 collected from 13.5-14.0' bgs @ 9:15 |
| | 14.0 | | | | | 12.7 - 13.0' OL: Very dark grayish brown (10YR 3/2) clayey silt, some organic material | 5.5 | |
| | 15.0 | | | | | 13.0 - 16.0' PT: Dark olive brown (2.5Y 3/3) to very dark brown (10YR 2/2) peat | 12.6<br>8.2<br>13.0<br>17.5 | |
| | 16.0 | | | | | | 0.4 | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-040
**DATE BEGAN:** 6/29/09
**DATE FINISHED:** 6/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 1 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #194; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 0.3 | | -2.0 - -1.7' FILL: Reddish brown silt, some f-m sand and fine gravel | 0.0 | |
| | -1.0 | | | | | -1.7 - 0.0' No recovery | | |
| | 0.0 | R-2 | N/A | 1.5 | | 0.0 - 1.3' FILL: Reddish brown silt, some f-m sand and fine gravel | 0.0 | |
| | 1.0 | | | | | 1.3 - 1.5' FILL: Dark brown fine sand, trace fine gravel and clinker; wet | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | R-3 | N/A | 3.0 | | 4.0 - 6.0' FILL: Dark brown fine sand, trace fine gravel and clinker; wet | 0.0 | 125-SB-040-0406 collected from 4.0-4.5' bgs @ 11:45 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Brown f-m sand, trace silt; wet | | 125-SB-040-0608 collected from 6.5-7.0' bgs @ 11:50 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-041
**DATE BEGAN:** 06/29/09
**DATE FINISHED:** 06/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #193; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 1.5 | | -2.0 - -1.5' FILL: Brown f-m sand, trace fine gravel | 0.0 | |
| | -1.0 | | | | | -1.5 - -0.5' FILL: Reddish brown silt, some fine sand and gravel, trace brick | | |
| | | | | | | -0.5 - 0.0' No recovery | | |
| | 0.0 | R-2 | N/A | 2.5 | | 0.0 - 0.3' FILL: Reddish brown silt, some fine sand and gravel, trace brick | 0.0 | |
| | 1.0 | | | | | 0.3 - 1.8' FILL: Yellowish brown fine sand, trace fine gravel, silt & coal | | |
| ▽ | 2.0 | | | | | 1.8 - 2.3' FILL: Brown/ reddish brown silt, some fine sand, trace fine gravel & coal & brick; wet from 2.0' | | |
| | | | | | | 2.3 - 2.8' FILL: Wood; wet | | Obstruction at 3.0' bgs; drilled through wood |
| | 3.0 | | | | | 2.8 - 3.0' No recovery | | |
| | | | | | | 3.0 - 3.5' FILL: Wood; wet | | |
| | 4.0 | R-3 | N/A | 2.5 | | 3.5 - 4.0' No recovery | 0.0 | 125-SB-041-0406 from 4.0-4.5' bgs @ 12:50 |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Yellowish brown fine sand; wet | | |
| | | | | | | 4.5 - 6.0' FILL: Dark brown f-m gravel & wood, some f-m sand; wet | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Brown f-m sand; wet | | 125-SB-041-0608 from 6.0-6.5' bgs @ 12:55 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery; end of boring at 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-041R
**DATE BEGAN:** 12/1/10
**DATE FINISHED:** 12/1/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.3' FILL: Reddish brown silt, some fine sand and gravel, trace brick | 0.0 | |
| | 1.0 | | | | | 0.3 - 1.8' FILL: Yellowish brown fine sand, trace fine gravel, silt & coal | | |
| | 2.0 | | | | | 1.8 - 2.3' FILL: Brown/ reddish brown silt, some fine sand, trace fine gravel & coal & brick; wet from 2.0' | | |
| | 2.3 | | | | | 2.3 - 2.8' FILL: Wood; wet | | |
| | 2.8 | | | | | 2.8 - 3.0' No recovery | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Wood; wet | | |
| | 3.5 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.5' FILL: Yellowish brown fine sand; wet | 0.0 | |
| | 4.5 | | | | | 4.5 - 6.0' FILL: Dark brown f-m gravel & wood, some f-m sand; wet | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Brown f-m sand; wet | | |
| | 6.5 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 1.5 | | 8.0 - 9.5' FILL: Light brown fine to medium sand; wet | 0.0 | 125-SB-041R-0810 from 9.0-9.5' bgs @ 12:30 |
| | 9.5 | | | | | 9.5 - 10.0' No recovery; end of boring at 10.0' bgs. | | |
| | 10.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-042
**DATE BEGAN:** 06/29/09
**DATE FINISHED:** 06/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.2' CONCRETE | | Field Map #192; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | | | | | -3.2 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 2.0 | | -2.0 - -1.5' FILL: Brown f-m sand | 0.0 | |
| | -1.0 | | | | | -1.5 - 2.0' FILL: Reddish brown silt, some fine sand and gravel; trace brick, clinker and coal; wet from 1.5' | | |
| | 0.0 | R-2 | N/A | 2.5 | | | 0.0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Wood with creosote odors; wet | | |
| | 3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | 4.0 | R-3 | N/A | 3.0 | | 4.0 - 4.5' FILL: Black silt, some fine sand & wood, some f-c gravel; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: White clayey silt (potential COPR); wet | | 125-SB-042-0406 from 4.5-5.0' bgs @ 13:05 |
| | 6.0 | | | | | 5.0 - 7.0' FILL: Light brown silt, some f-m sand & gravel; wet | | 125-SB--042-0608 from 6.5-7.0' bgs @ 13:10 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery, end of boring @ 8.0' | | |
| | 8.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-043
**DATE BEGAN:** 06/29/09
**DATE FINISHED:** 06/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 1.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.3' CONCRETE | | |
| | -3.0 | | | | | -3.3 - -2.0' VOID | | |
| | -2.0 | R-1 | N/A | 1.0 | | -2.0 - -1.0' FILL: Brown/ reddish brown silt, trace fine sand & gravel, trace concrete & brick | 0.0 | |
| | -1.0 | | | | | -1.0 - 0.0' No recovery | | |
| | 0.0 | R-2 | N/A | 2.0 | | 0.0 - 1.0' FILL: Brown/ reddish brown silt, trace fine sand & gravel, trace concrete & brick | 0.0 | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Wood with creosote odos and sheen; wet | 0.9<br>2.0 | |
| | 2.0 | | | | | 2.0 - 4.0' FILL: No recovery | 0.4 | |
| | 3.0 | | | | | | | |
| | 4.0 | R-3 | N/A | 3.0 | | 4.0 - 4.7' FILL: Dark brown silt, some fine sand & wood with tarry creosote, lens of while clayey COPR from 4.5-4.6'; wet | 0.0<br>0.1 | 125-SB-043-0406 from 4.5-5.0' bgs @ 14:00; HOLD |
| | 5.0 | | | | | 4.7 - 6.5' FILL: Brown f-m sand; wet | | |
| | 6.0 | | | | | | 0.0 | |
| | 7.0 | | | | | 6.5 - 7.0' FILL: Brown silt, some fine sand | | 125-SB--043-0608 from 6.5-7.0' bgs @ 14:05; HOLD |
| | 8.0 | | | | | 7.0 - 8.0' No recovery, end of boring @ 8.0' | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-044
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field # 204<br>Driller cored through asphalt |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown f-c sand, some f-m gravel, trace silt | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Reddish brown/gray/brown silt & fine sand, trace f-m gravel, brick, wood, ceramics, coal & clinker | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown f-m sand, some fine gravel, trace coal, asphalt, wood & clinker; moist | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.5' FILL: Brown f-c sand and f-m brick, some wood; wet with sheen | 0.0 | |
| | 5.0 | | | | | 4.5 - 6.8' FILL: Brown f-m sand, trace silt; wet | | |
| | 6.0 | | | | | 6.8 - 7.0' FILL: Brown clayey silt; trace fine sand; wet; soft | | 125-SB--044-0608 from 6.0-6.5' bgs @ 8:25; HOLD |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.0' FILL: Dark brown clayey silt; trace fine sand; wet; soft | 0.0 | 125-SB-044-0810 from 8.5-9.0' bgs @ 8:30 |
| | 9.0 | | | | | 9.0 - 12.0' FILL: Brown f-m sand, trace silt, 0.5" clay lens @ 9.2'; wet; end of boring @ 12.0' bgs | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | 125-SB-044-1012 from 11.5-12.0' bgs @ 8:55; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-045
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field # 202 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown f-m sand & gravel | | |
| | 2.0 | | | | | 1.5 - 4.0' FILL: Brown /dark brown f-m sand, some f-m gravel, trace brick, coal, glass, clinker, and silt | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.5' FILL: Wood with creosote & sheen, some f-m brick and sand; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.5' FILL: Brown f-m sand, trace wood from 4.5-4.7'; wet | | 125-SB--045-0406 from 5.0-5.5' bgs @ 8:55 |
| | 6.0 | | | | | 5.5 - 6.8' FILL: Brown clayey silt, trace fine sand; wet | | 125-SB--045-0608 from 6.0-6.5' bgs @ 9:00 |
| | 7.0 | | | | | 6.8 - 7.0' FILL: Brown f-m sand, trace clay; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 7.0 - 8.0' No recovery | 0.0 | |
| | 9.0 | | | | | 8.0 - 11.0' FILL: Brown f-m sand, trace silt; wet | | 125-SB-045-0810 from 8.5-9.0' bgs @ 9:05 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.4' FILL: Brown clayey silt, trace fine sand; wet | | 125-SB-045-1012 from 10.5-11.0' bgs @ 9:10; HOLD |
| | 12.0 | | | | | 11.4 - 11.6' FILL: Brown f-m sand; wet | | |
| | | | | | | 11.6 - 12.0' FILL: Dark brown fine sand, some silt and clay, trace organic material; wet; end of boring @ 12.0' bgs | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-046
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field # 199 |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | Drillers cored through asphalt |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Reddish brown fine sand, trace concrete, fine gravel & brick | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Concrete | | |
| | | | | | | 3.5 - 4.0' FILL: Dark brown f-m sand, some silt, trace clinker, coal, fine gravel, metal fragments, & wood | | |
| ▽ | 4.0 | R-2 | N/A | 3.0 | | | 0.0 | |
| | | | | | | 4.0 - 4.5' FILL: Brown f-m sand, some f-m brick & gravel, trace wood and ceramics; wet | | |
| | 5.0 | | | | | 4.5 - 6.0' FILL: Brown f-m sand, some silt and fine gravel; wet | | |
| | 6.0 | | | | | 6.0 - 6.5' Brown silt, some fine sand; wet | | |
| | | | | | | 6.5 - 7.0' FILL: Brown f-m sand; wet | | 125-SB--046-0608 from 6.5-7.0' bgs @ 9:40; HOLD |
| | 7.0 | | | | | 7.0 - 8.0' FILL: No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.8' FILL: Brown f-c sand; wet | 0.0 | |
| | | | | | | | | 125-SB-046-0810 from 8.5-9.0' bgs @ 9:45; DUP @ 9:48 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.8 - 10.3' FILL: Brown silty clay, trace fine sand; wet | | |
| | | | | | | 10.3 - 12.0' FILL: Brown f-m sand; wet; end of boring @ 12.0' bgs | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | 125-SB-046-1012 from 11.5-12.0' bgs @ 9:50; HOLD |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-047
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 4.5 ft bgs
**GW DEPTH:** NE ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field # 200 |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | Drillers cored through asphalt |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Reddish brown fine sand & silt; trace f-m gravel, trace coal | | |
| | 2.0 | | | | | | | |
| | | | | | | 2.5 - 4.0' FILL: Brown/dark brown f-m sand & clinker, trace f-m brick & gravel, trace greenish yellow granular COPR from 3.4-3.5' | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | 4.0 - 4.5' No recovery; refusal @ 4.5' bgs | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-048
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' See Log for 125-SB-047 for 0-4.0'; Driller advanced to 4.0' | | Step out 2 ft east for Location # 200 (125-SB-047) |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-1 | N/A | 3.5 | | 4.0 - 5.0' FILL: Dark brown f-m gravel & clinker, some f-m sand, trace brick, ceremics, coal, and wood, white clay and fine sand (COPR) from 4.8-4.9'; wet; trace sheen | 0.0 | |
| | 5.0 | | | | | 5.0 - 7.5' FILL: Brown f-m sand, some silt from 5.5-6.0' and 6.5-7.0'; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 125-SB--048-0608 from 7.0-7.5' bgs @ 10:20; HOLD |
| | 8.0 | R-2 | N/A | 4.0 | | 7.5 - 8.0' FILL: No recovery<br>8.0 - 12.0' FILL: Brown f-c sand, some silt from 10.5-11.0'; wet; end of boring @ 12.0' bgs | 0.0 | 125-SB-048-0810 from 8.5-9.0' bgs @ 10:25 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | 125-SB-048-1012 from 11.5-12.0' bgs @ 10:30; HOLD |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-049
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | | |
| | | | | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 201 |
| | | R-1 | N/A | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | Drillers cored through asphalt |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Reddish brown silt, some f-m gravel, trace fine sand | | |
| | 2.0 | | | | | 1.5 - 4.0' FILL: Dark brown/brown f-m sand, some f-m clinker , trace silt, brick, concrete, glass, & gravel | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 5.0' FILL: Dark brown/brown f-m sand, some f-m clinker , trace silt, brick, concrete, glass, & gravel, green/white clayey fine sand (COPR) from 4.6-4.8'; wet | 0.0 | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Brown f-m sand; wet | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Brown silt; trace clay & fine sand; wet | | |
| | 7.0 | | | | | 6.5 - 7.0' FILL: Brown f-m sand; wet | | 125-SB--049-0608 from 6.0-6.5' bgs @ 10:45; HOLD |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.0' FILL: Brown f-c sand; wet | 0.0 | |
| | 9.0 | | | | | | | 125-SB-049-0810 from 8.5-9.0' bgs @ 10:50 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 11.6' FILL: Brown clayey silt; trace fine sand; wet | | 125-SB-049-1012 from 11.0-11.5' bgs @ 10:55; HOLD |
| | 12.0 | | | | | 11.6 - 12.0' FILL: Grayish brown fine sand, some lenses of silt; wet; end of boring @ 12.0'bgs | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-050
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 205 |
| | 1.0 | R-1 | N/A | 4.0 | | 0.5 - 1.5' FILL: Brown f-m sand & gravel | | Drillers cored through asphalt |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Reddish brown fine sand & silt, trace clinker, coal, glass, brick, & fine gravel | 0.0 | |
| | 3.0 | | | | | 2.5 - 4.0' FILL: Dark brown/black f-m sand, some brick, trace clinker & gravel, wood & yellow/white clayey COPR from 3.8' | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.8' FILL: Dark brown f-m gravel and wood, some f-c sand and brick, trace white claysy COPR from 4.6'; wet | 0.0 | |
| | 5.0 | | | | | 4.8 - 5.0' FILL: Green/yellow gray clayey COPR, some f-m sand, trace wood; wet | | |
| | 6.0 | | | | | 5.0 - 6.0' FILL: Brown f-m sand, trace silt; wet | 0.0 | 125-SB--050-0608 from 6.0-6.5' bgs @ 11:35; HOLD |
| | 7.0 | | | | | 6.0 - 6.5' FILL: Brown silt, some fine sand, trace clay; wet | | |
| | | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.8' FILL: Brown silt, some fine sand, trace clay; wet | 0.0 | 125-SB-050-0810 from 8.0-8.5' bgs @ 11:40 |
| | 9.0 | | | | | 8.8 - 11.8' FILL: Brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | | 0.0 | |
| | 11.0 | | | | | | | 125-SB-050-1012 from 11.0-11.5' bgs @ 11:45; HOLD |
| | 12.0 | | | | | 11.8 - 12.0' FILL: Brown clayey silt; trace fine sand; wet; end of boring @ 12.0' bgs | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-051
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 186 |
| | 1.0 | R-1 | N/A | | | 0.5 - 1.2' FILL: Brown f-m sand and gravel | | Drillers cored through asphalt |
| | | | | | | 1.2 - 1.5' FILL: Reddish brown silt and fine sand, trace gravel | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Dark brown f-m sand, some f-m clinker, trace gravel, brick, coal, & glass | | |
| | 3.0 | | | | | 2.0 - 2.8' FILL: Yellowish brown clayey sand (COPR) | | |
| | | | | | | 2.8 - 4.0' FILL: Dark brown fine sand, some silt | | |
| | 4.0 | R-2 | N/A | 4 | | 4.0 - 5.5' FILL: Dark brown fine sand, some silt, trace yellowish brown sandy COPR from 4.0-4.3', trace brick and fine gravel from 4.5-4.7'; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.8' FILL: Dark brown f-m sand, some f-m gravel and clinker, trace wood and ceramics; wet | | |
| | | | | | | 6.8 - 7.0' Wood and yellowish brown clayey COPR; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Brown f-m sand, trace silt; wet | | |
| | 8.0 | R-3 | N/A | 0 | | 8.0 - 12.0' FILL: No recovery; end of boring @ 12' bgs | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-052
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' ASPHALT | | 2 ft. East of Field Map # 186<br>No PID due to rain |
| | 1.0 | | | | | 0.5 - 8.0' FILL: See 125-SB-051 for 0-8'; driller advanced to 8.0'bgs. | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-1 | N/A | 4.0 | | 8.0 - 10.5' FILL: Brown/dark brown f-m sand, trace silt; wet | N/A | 125-SB-052-0810 from 8.5-9.0' bgs @ 12:55; HOLD |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' FILL: Brown clayey silt, some lenses of f-c sand | | |
| | 12.0 | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs | | 125-SB-052-1112 from 11.5-12.0' bgs @ 13:00; HOLD |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-053
**DATE BEGAN:** 07/02/09
**DATE FINISHED:** 07/02/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' ASPHALT | N/A | Field Map # 176<br>No PID due to rain<br>Drillers cored through asphalt |
| | | R-1 | N/A | 3.5 | | 0.5 - 1.5' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 3.5' FILL: Reddish brown/dark brown fine sand & silt, some fine clinker from 2-2.5', trace f-m gravel, brick, coal, & glass | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' FILL: Dark brown silt & fine sand; firm; moist | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 5.0' FILL: Dark brown silt & fine sand; firm; wet | N/A | |
| | 5.0 | | | | | | | |
| | | | | | | 5.0 - 7.0' FILL: Dark brown f-m sand, some fine gravel & clinker, trace brick, coal & silt; wet | | |
| | 6.0 | | | | | | | |
| | | | | | | | | 125-SB--053-0608 from 6.5-7.0' bgs @ 13:15; HOLD |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.5' FILL: Brown/ dark brown silty fine sand, some clay lenses; wet | N/A | |
| | 9.0 | | | | | | | 125-SB-053-0810 from 9.0-9.5' bgs @ 13:20 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs | | 125-SB-053-1012 from 11.0-11.5' bgs @ 13:25; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-054
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 13.5 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 173 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 2.0 | | | | | 1.0 - 4.0' FILL: Reddish Brown silt & fine sand, trace gravel, coal, & clinker | | 125-SB--054-0002 from 1.5-2.0' bgs @ 8:30; |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 4.5' FILL: Reddish Brown silt & fine sand, trace gravel, coal, & clinker | 0.0 | 125-SB-054-0204 from 3.5-4.0' bgs @ 8:35 |
| | 5.0 | | | | | 4.5 - 8.0' FILL: Very dark grayish brown silt, some fine sand; white/green clayey COPR from 7.8'; wet; firm | | 125-SB-054-0406 from 4.5-5.0' bgs @ 8;40 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 125-SB--054-0608 from 7.5-8.0' bgs @ 8:45; |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 10.0' FILL: Brown silty fine sand; wet | 0.0 | 125-SB-054-0810 from 8.0-8.5' bgs @ 8:50 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 10.8' FILL: Dark brown sandy silt, trace clay; wet; soft | | |
| | 11.0 | | | | | 10.8 - 11.3' FILL: Dark brown f-m sand; wet | | 125-SB-054-1012 from 11.0-11.5' bgs @ 8:55 |
| | 12.0 | R-4 | | 1.5 | | 11.3 - 11.5' OL: Very dark grayish brown (10YR 3/2) clayey silt & organic material | 0.0 | 125-SB-054-1214 from 12.0-12.5' bgs @ 9:00; HOLD |
| | 13.0 | | | | | 11.5 - 12.0' No recovery | | |
| | | | | | | 12.0 - 13.5' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 13.5' | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-055
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #182<br>2ft offset ESE |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | 1.0 - 4.0' FILL: Reddish brown silt & fine sand, trace gravel, coal, & clinker | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.5' FILL: Reddish brown silt & fine sand, trace gravel, coal, & clinker | 0.0 | |
| | | | | | | 4.5 - 5.0' FILL: Brown f-m sand, fine gravel; wet | | |
| | 5.0 | | | | | 5.0 - 6.5' FILL: Very dark brown grayish brown silt & fine sand; wet; firm | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 7.0' FILL: Dark brown f-m sand, some f-m gravel, trace brick, clinker, wood, & plastic; wet | | |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.0' FILL: Dark brown f-m sand, some f-m gravel, trace brick, clinker, wood, & plastic with yellow clayey COPR; wet | 0.0<br>0.0<br>0.0 | |
| | 9.0 | | | | | 9.0 - 10.0' FILL: Brown silty fine sand; wet | 0.0 | |
| | 10.0 | | | | | 10.0 - 10.8' FILL: Dark brown silt, some fine sand, trace clay; wet | 0.0<br>0.0 | |
| | 11.0 | | | | | 10.8 - 11.0' FILL: Brown silt & fine sand, trace yellow/green COPR; wet | 3.1 | |
| | | | | | | 11.0 - 11.2' OL: Very dark grayish brown silt, some organic matter, trace fine sand & clay; wet | 12.0<br>7.8 | 125-SB-055-1012 from 11.5-12.0' bgs @ 9:10 |
| | 12.0 | | | | | 11.2 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs. | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-056
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0 | Field Map # 183 |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 1.0 - 3.3' FILL: Reddish brown/brown fine sand, some silt and fine gravel; trace brick, clinker, coal, wood and glass; firm. | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.3 - 3.5' FILL: Very dark grayish brown silt and fine sand | | 125-SB-056-0204 collected from 3.0-3.5' bgs @ 9:40 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3 | | 4.0 - 5.0' FILL: Reddish brown fine sand, some f-m gravel; trace silt, brick and clinker | 0 | |
| | 5.0 | | | | | 5.0 - 6.5' FILL: Dark brown f-c sand, some f-m gravel; trace silt, brick, wood, glass, plastic and clinker; wet | | 125-SB-056-0406 collected from 5.0-5.5' bgs @ 9:45 |
| | 6.0 | | | | | 6.5 - 6.6' FILL: White/gray clayey COPR, trace fine sand; wet | | |
| | 7.0 | | | | | 6.6 - 7.0' FILL: Brown clayey silt, trace fine sand; wet | | 125-SB-056-0608 collected from 6.5-7.0' bgs @ 9:50 |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4 | | 8.0 - 8.5' OL: Black (2.5Y 2.5/1) clayey silt, some organic material; wet | 0 | |
| | | | | | | 8.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' | 0.5 | 125-SB-056-0810 collected from 8.5-9.0' bgs @ 9:55 |
| | 9.0 | | | | | | 4.9 | |
| | | | | | | | 11.2 | |
| | 10.0 | | | | | | 8.5 | |
| | | | | | | | 9.1 | |
| | 11.0 | | | | | | 14.7 | |
| | | | | | | | 5.3 | |
| | 12.0 | | | | | | 6.4 | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-057
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 197 Encountered refusal @ 2' bgs due to concrete; Refusal @ 2nd and 3rd attemps in 2' radius E and SE. Moved 5' South and tried again. Refusal @ 2' bgs. Refusal @ 5'East offset. Moved 5' NE and advanced to 4'bgs |
| | 0.5 | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | 1.0 - 2.3' FILL: Reddish brown silty fine sand, trace fine gravel, brick, coal, & glass | | |
| | 2.0 | | | | | | | |
| | 2.3 | | | | | 2.3 - 3.5' FILL: Dark brown/light brown f-m sand, some concrete, trace fine gravel, wood, & clinker | | |
| | 3.0 | | | | | | | |
| | 3.5 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.8' FILL: Dark brown/ black f-c sand, some f-m gravel & brick, white clayey COPR from 4.2-4.6', green mottling from 4.6-4.8'; wet | 0.0 | |
| | 4.8 | | | | | 4.8 - 6.5' FILL: Reddish brown/brown silty fine sand, trace clay from 6.0'; wet | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 6.5 | | | | | 6.5 - 7.0' FILL: Brown f-m sand; wet | | 125-SB-057-0608 from 6.5-7.0' bgs @ 10:30 HOLD |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.5 | | 8.0 - 10.0' FILL: Brown f-m sand, some silt from 8.5-8.8'; wet | 0.0 | |
| | 8.5 | | | | | | 0.0 | |
| | 9.0 | | | | | | 0.0 | 125-SB-057-0810 from 9.0-9.5' bgs @ 10:35 |
| | 9.5 | | | | | | 0.0 | |
| | 10.0 | | | | | 10.0 - 10.5' PT: Dark olive brown (2.5Y 3/3) peat | 0.4 | 125-SB-057-1012 from 10.0-10.5' bgs @ 10:40; HOLD |
| | 10.5 | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | 3.0 | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-058
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 198 |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | 1.0 - 2.7' FILL: Redish brown/dark brown silty fine sand, some fine gravel, trace brick, clinker, & coal, concrete from 2.4-2.5' | | |
| | 2.0 | | | | | 2.7 - 3.0' FILL: Gray & pale yellow crushed brick | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.5' FILL: Dark brown f-m grqavel & brick, trace f-m sand & wood; wet | 0.0 | |
| | | | | | | 4.5 - 5.7' FILL: Brown silty fine sand, trace clay from 5.0'; wet | | 125-SB-058-0406 from 4.5-5.0' bgs @ 10:55 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.7 - 7.0' FILL: Brown f-m sand | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | 125-SB-058-0608 from 6.5-7.0' bgs @ 11:00 |
| | 8.0 | R-3 | N/A | 3.8 | | 8.0 - 10.8' FILL: Brown f-m sand | 0.0 | |
| | | | | | | | 0.0 | |
| | 9.0 | | | | | | 0.0 | 125-SB-058-0810 from 9.0-9.5' bgs @11:05 |
| | | | | | | | 0.0 | |
| | 10.0 | | | | | 10.8 - 11.0' OL: Very dark grayish brown(10YR 3/2) clayey silt, trace organic material | 0.0 | |
| | | | | | | | 0.0 | |
| | 11.0 | | | | | 11.0 - 11.8' PT: Dark olive brown (2.5Y 3/3) peat | 0.0 | 125-SB-058-1012 from 11.0-11.5' bgs @ 11:10; HOLD |
| | | | | | | | 1.8 | |
| | 12.0 | | | | | 11.8 - 12.0' No recovery; end of boring @ 12.0' bgs | 5.1 | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-059

**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs

**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 185 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Reddish brown silt and fine sand, trace fine gravel | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Brown f-m sand, some f-m gravel, trace clinker, brick, glass, coal | | |
| | 4.0 | R-2 | N/A | 1.0 | | 3.0 - 4.0' FILL: Very dark grayish brown silt and fine sand, trace f-m gravel, clinker, & wood | 0.0 | |
| | 5.0 | | | | | 4.0 - 4.8' FILL: Very dark grayish brown silt and fine sand, trace f-m gravel, clinker, & wood; wet; firm | | |
| | 6.0 | | | | | 4.8 - 5.0' FILL: Dark brown f-c sand, fine gravel, trace silt and clinker; wet | | |
| | 7.0 | | | | | 5.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 1.2 | | 8.0 - 9.0' FILL: Brown f-m sand, traace fine gravel; wet | 0.0<br>0.0 | 125-SB-059-0810 from 8.5-9.0' bgs @ 11:45; HOLD |
| | 9.0 | | | | | 9.0 - 9.2' OL: Very dark grayish brown (10YR 3/2) silt, some peat fragments, trace clay & fine sand; wet' | 0.0 | |
| | 10.0 | | | | | 9.2 - 12.0' No recovery | 0.0<br>1.0<br>6.5<br>3.1 | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 2.0 | | 12.0 - 14.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs | 12.2<br>7.4 | 125-SB-059-1214 from 12.5-13.0' bgs @ 11:50 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-060
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6.5 ft. bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 184 |
| | | | | | | 0.5 - 1.5' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 3.0' FILL: Raddish brown silty fine sand, trace fine gravel, brick, & wood | | |
| | 2.0 | | | | | | | |
| | | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Very dark grayish brown silt, some fine sand; firm | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.5' FILL: Reddish brown/dark brown silty fine sand, trace fine gravel, brick | 0.0 | |
| | | | | | | 4.5 - 5.0' FILL: F-m gravel; wet | | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Dark brown silty fine sand some fine gravel & clinker; wet | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Brick and concrete; wet; refusal at 6.5' bgs due to concrete, end of boring @ 6.5' bgs | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-061
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | 5 ft NE of #184 |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | 1.0 - 2.8' FILL: Reddish brown/brown silty fine sand, some brick, trace fine gravel; firm | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.8 - 5.0' FILL: Very dark grayish brown silt, some fine sand; firm; wet at 4.0' | | |
| | 4.0 | R-2 | N/A | 3.0 | | | 0.0 | |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Dark brown f-c sand, some f-m gravel and brick, trace wood @ 6.5', concrete from 6.5-6.8'; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 8.7' FILL: Dark greenish gray silty sand, trace f-m gravel & clay, trace white clayey COPR from 8.1-8.2'; wet | 0.0 | 125-SB-061-0810 from 8.0-8.5' bgs @ 13:20; HOLD |
| | | | | | | 8.7 - 11.0' FILL: Brown f-m sand, trace silt, more silt from 10.0', trace clay from 10.5'; wet | 0.0 | |
| | 9.0 | | | | | | 0.0 | |
| | | | | | | | 0.0 | |
| | 10.0 | | | | | | 0.0 | |
| | | | | | | 11.0 - 11.5' OL: Very dark grayish brown (10YR 3/2) clayey silt, some organic material; wet | 0.0 | |
| | 11.0 | | | | | | 0.0 | |
| | | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs | 2.1 | 125-SB-061-1012 from 11.5-12.0' bgs @ 13:25 |
| | 12.0 | | | | | | 9.7 | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-062
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #174 |
| | | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Reddish brown/brown fine sand, some silt & fine gravel, trace brick, coal, & clinker, some yellow-brown mottling from 2.5-2.8' (possible COPR) | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 8.0' FILL: Very dark grayish brown silt, some fine sand; firm; moist, wet at 4.0' | | |
| | 4.0 | R-2 | N/A | 4.0 | | | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.7' FILL: Brown f-m sand, trace silt | 0.0 | |
| | 9.0 | | | | | | 0.0 | |
| | | | | | | | 0.0 | |
| | | | | | | | 0.0 | |
| | 10.0 | | | | | 9.7 - 10.5' FILL: Dark brown clayey silt, trace fine sand; soft; wet | 0.0 | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-062
**DATE BEGAN:** 07/06/09
**DATE FINISHED:** 07/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | | | | | 10.5 - 11.3' FILL: Brown silty sand, some fine gravel, whilte/light brown clayey COPR throughout; wet | 0.0 | |
| | | | | | | | 0.0 | |
| | | | | | | 11.3 - 11.5' OL: Very dark grayish brown (10YR 3/2) clayey silt, trace organic material; wet | 2.0 | 125-SB-062-1012 from 11.5-12.0' bgs @ 14:00 |
| | 12.0 | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-063
**DATE BEGAN:** 07/07/09
**DATE FINISHED:** 07/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #175 |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Brown f-m sand, some f-m gravel | | Initial refusal at 2.5' bgs. Moved 2' west. |
| | 2.0 | | | | | | | 125-SB-063-0002 from 1.5-2.0' bgs @ 7:55 |
| | 3.0 | | | | | 2.0 - 3.5' FILL: Reddish brown silt, some fine sand, trace fine gravel, coal, & brick | | |
| | 4.0 | R-2 | N/A | 3.5 | | 3.5 - 7.0' FILL: Very dark grayish brown silt, some fine sand; wet at 4.0' | 0.0 | 125-SB-063-0204 from 3.5-4.0' bgs @ 8:00 |
| | 5.0 | | | | | | | 125-SB-063-0406 from 5.0-5.5' bgs @ 8:05 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Yellow/white clayey COPR, trace f-m sand; wet | | 125-SB-063-0608 from 7.0-7.5' bgs @ 8:10 |
| | 8.0 | R-3 | N/A | 4.0 | | 7.5 - 8.0' No recovery | 0.0 | |
| | 9.0 | | | | | 8.0 - 9.0' FILL: Brown f-m sand; wet | | 125-SB-063-0810 from 8.5-9.0 bgs @ 8:15 |
| | 10.0 | | | | | 9.0 - 11.0' FILL: Dark brown sandy silt, trace to some clay; wet | | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Light brown clayey COPR, trace f-m sand, fine gravel; wet | | 125-SB-063-1012 from 11.0-11.5' bgs @ 8:20 |
| | 12.0 | R-4 | N/A | 2.0 | | 11.5 - 12.0' OL: Very dark grayish brown (10YR 3/2) clayey silt, organic material; wet | 0.0 | |
| | 13.0 | | | | | 12.0 - 14.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 14.0' bgs | 5.1<br>2.4<br>6.8 | 125-SB-063-1214 from 12.5-13.0 bgs @ 8:25; HOLD |
| | 14.0 | | | | | | 12.0 | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-064
**DATE BEGAN:** 07/07/09
**DATE FINISHED:** 07/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #177 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown f-m sand & gravel | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Brown/reddish brown silty sand, some fine gravel, trace brick, coal, & clinker | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Very dark grayish brown silt, some fine sand; firm | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 8.0' FILL: Very dark grayish brown silt, some fine sand, brick & wood from 6.7-6.9'; firm; wet | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | 0.0 | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 9.8' FILL: Brown f-m sand; wet | 0.0 | 125-SB-064-0608 from 7.5-8.0' bgs @ 8:45; HOLD |
| | 9.0 | | | | | | 0.0<br>0.0<br>0.0 | 125-SB-064-0810 from 8.5-9.0' bgs @ 8:50 |
| | 10.0 | | | | | 9.8 - 11.0' FILL: Dark brown sandy silt, trace clay; wet | 0.0<br>0.0 | |
| | 11.0 | | | | | 11.0 - 11.5' FILL: Black/dark brown silty sand, some f-m gravel, trace clay; wet | 0.0 | |
| | 12.0 | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring @ 12.0' bgs | 3.5<br>0.1 | 125-SB-064-1012 from 11.5-12.0' bgs @ 8:55; HOLD |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-065
**DATE BEGAN:** 07/07/09
**DATE FINISHED:** 07/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #178 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand & gravel | | |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Brown/reddish brown silty sand, some fine gravel, trace brick, clinker, & coal | | |
| | 3.0 | | | | | 2.5 - 4.0' FILL: Dark brown silty sand, some f-m gravel & brick, trace wood, coal, & clinker; moist | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.7' FILL: Dark brown silty sand, some f-m gravel & brick, trace wood, coal, & clinker, f-m sand from 4.5'; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.7 - 8.0' FILL: Brown/dark brown/black f-m sand, some f-m gravel, trace clinker, glass, brick, green silty sand (COPR) from 7.0-7.2' and 7.8-8.0', yellow clayey COPR from 7.5-7.8'; wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.0' FILL: Brown silty sand; firm; wet | 0.0<br>0.0<br>0.0<br>0.0<br>0.0<br>0.0 | 125-SB-065-0810 from 9.0-9.5' bgs @ 9:35; DUP @ 9:37 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 12.0' bgs | 2.2<br>8.0<br>1.0 | 125-SB-065-1012 from 11.5-12.0' bgs @ 9:40; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-066
**DATE BEGAN:** 07/07/09
**DATE FINISHED:** 07/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.8 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #203 |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Brown f-m sand and gravel | | No recovery on first run (0-4') due to gravel in shoe. Moved 2' NE. |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Dark brown silty sand, some f-m gravel, trace brick and clinker | | |
| | 3.0 | | | | | 3.0 - 3.8' FILL: Wood and brick | | |
| | | | | | | 3.8 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.8' FILL: Wood, some dark brown f-c sand & fine gravel, white green clayey sand (COPR) from 4.7-4.8'; wet | 0.0 | |
| | 5.0 | | | | | 4.8 - 6.0' FILL: Brown f-m sand; wet | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Brown silty sand; wet | | 125-SB-066-0608 from 6.0-6.5' bgs @ 10:10; HOLD |
| | | | | | | 6.5 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown f-m sand; wet | 0.0 | |
| | 9.0 | | | | | | 0.0 | 125-SB-066-0810 from 8.5-9.0' bgs @ 10:15 |
| | | | | | | | 0.0 | |
| | 10.0 | | | | | | 0.0 | |
| | | | | | | 10.0 - 11.5' FILL: Brown silty sand' wet | 0.0 | |
| | 11.0 | | | | | | 0.0 | |
| | | | | | | | 0.0 | |
| | 12.0 | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 12.0' bgs | 1.0<br>4.3 | 125-SB-066-1012 from 11.5-12.0' bgs @ 10:20; HOLD |

PREPARED BY: MC
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-067
**DATE BEGAN:** 08/06/09
**DATE FINISHED:** 08/06/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #196 |
| | | | | | | 0.5 - 0.7' FILL: Brown f-m sand and gravel | 0.0 | |
| | 1.0 | | | | | 0.7 - 1.5' FILL: Concrete | 0.0 | |
| | | | | | | 1.5 - 3.3' FILL: Reddish brown/brown silty sand, some concrete and f-m gravel; strong creosote-like odors | 5.4 | |
| | 2.0 | | | | | | 22.8 | |
| | | | | | | | 25.8 | |
| | 3.0 | | | | | | 13.3 | |
| | | | | | | 3.3 - 4.0' FILL: Gray f-m sand and clinker | 0.0 | |
| | 4.0 | R-2 | | 4.0 | | 4.0 - 5.5' FILL: Brown f-m sand, some f-m gravel, trace concrete; gray clinker and wet from 5.0' | 0.0 | |
| | | | | | | | 0.0 | |
| | 5.0 | | | | | | 0.0 | 125-SB-067-0406 from 5.0-5.5' bgs @ 15:40 |
| | | | | | | 5.5 - 5.7' FILL: Dark brown silty sand and wood; wet | 0.0 | |
| | 6.0 | | | | | 5.7 - 8.0' FILL: Brown f-m sand, some silt from 6.5-6.7' and 7.5-8.0'; end of boring at 8.0' | 0.0 | |
| | | | | | | | 0.0 | |
| | 7.0 | | | | | | 0.0 | |
| | | | | | | | 0.0 | 125-SB-067-0608 from 7.5-8.0' bgs @ 15:45 |
| | 8.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-068
**DATE BEGAN:** 08/07/09
**DATE FINISHED:** 08/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map #188 |
| | | | | | | 0.3 - 0.7' FILL: Brown f-m sand, some f-m gravel | | Macrocore bent by concrete layer; driller repaired and resumed drilling |
| | 1.0 | | | | | 0.7 - 2.5' FILL: Reddish brown sandy silt; trace fine gravel, brick and coal; trace green mottling (reduction zones) | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Dark brown f-c sand, some fine clinker and gravel, wood from 3.3'; wet | | |
| | | | | | | 3.5 - 4.0' FILL: Concrete | | |
| | 4.0 | R-2 | | 4.0 | | 4.0 - 5.3' FILL: Grayish brown f-c sand and f-m gravel, trace clinker and wood; wet | 0.0 | |
| | 5.0 | | | | | 5.3 - 6.8' FILL: Brown silty sand, trace wood; wet | | 125-SB-068-0406 from 5.5-6.0' bgs @ 8:25 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.8 - 7.2' FILL: Dark brown silt, trace fine sand and clay; wet | | |
| | 8.0 | | | | | 7.2 - 8.0' FILL: Brown f-m sand, trace silt from 7.8'; end of boring at 8.0' | | 125-SB-068-0608 from 7.5-8.0' bgs @ 8:30 |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 125, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-069
**DATE BEGAN:** 08/07/09
**DATE FINISHED:** 08/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map #190 |
| | | | | | | 0.3 - 0.5' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Brown/dark brown f-m sand, some fine gravel; trace clinker, wood, coal and brick | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Wood, wet at 2.5' | | |
| | | | | | | 2.5 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | | 3.5 | | 4.0 - 4.5' FILL: Dark brown fine clinker, some f-c sand, trace brick and gravel; wet | 0.0 | |
| | | | | | | 4.5 - 6.5' FILL: Brown silty sand, trace clay and coarse sand from 4.5-5.0'; wet | | |
| | 5.0 | | | | | | | |
| | | | | | | | | 125-SB-069-0406 from 5.5-6.0' bgs @ 8:50 |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 7.2' FILL: Dark brown clayey silt, trace fine sand; soft, wet | | |
| | 7.0 | | | | | 7.2 - 7.5' FILL: Brown f-m sand, trace silt; wet | | 125-SB-068-0608 from 7.0-7.5' bgs @ 8:55 |
| | | | | | | 7.5 - 8.0' No recovery; end of boring at 8.0' | | |
| | 8.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-070
**DATE BEGAN:** 5/4/10
**DATE FINISHED:** 5/4/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.3' ASPHALT | 0 | |
| | 1.0 | | | | | 0.3 - 1.0' FILL: Fine to coarse gravel, brown silty sand; loose, dry | | |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Red silt, some fine sand, fine to medium gravel, trace coal, lens of wood from 1.25-1.4'; dense, dry | | |
| | 3.0 | | | | | 2.5 - 3.8' FILL: Gray silt, some fine sand; dense, moist | | |
| | 4.0 | S-2 | NA | 4 | | 3.8 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.8' FILL: Gray silt, some fine sand, trace organics; dense, moist | | |
| | 6.0 | | | | | 4.8 - 5.3' FILL: Black sillty clay; firm, wet | | |
| | 7.0 | | | | | 5.3 - 8.0' FILL: Gray silt, trace fine sand and red brick; dense, wet | | |
| | 8.0 | S-3 | NA | 4 | | 8.0 - 8.0' FILL: Green and white COPR, orange silt; loose, wet | 0 | |
| | 9.0 | | | | | 8.0 - 8.8' FILL: Brown fine to medium sand, mottling of silt and clay, trace silt; loose, wet | | |
| | 10.0 | | | | | 8.8 - 9.1' FILL: (Sheen) Brown silt, some fine sand; very loose, wet | | |
| | 11.0 | | | | | 9.1 - 11.3' FILL: Black gray silt; very loose, wet | | Sample collected 125-SB-070-1012 from 11.5-12.0' bgs @12:20 |
| | 12.0 | S-4 | NA | 4 | | 11.3 - 11.9' FILL: Gray silt, possible light green/light yellow COPR; dense, moist | 0 | |
| | 13.0 | | | | | 11.9 - 16.0' PT: Peat; end of boring at 16' | | Sample collected 125-SB-070-1214 from 12.5-13.0' bgs @12:25 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | Sample collected 125-SB-070-1416 from 14.5-15.0' bgs @12:30 |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-071
**DATE BEGAN:** 5/4/10
**DATE FINISHED:** 5/4/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.4 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' ASPHALT | 0 | |
| | 1.0 | | | | | 0.3 - 1.3' FILL: Fine to medium gravel, brown silty fine to medium sand | | |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Red silt, some fine sand, trace coal; dense | | |
| | 3.0 | | | | | 2.0 - 2.2' FILL: Dark brown to light brown silt, some fine sand, trace wood and fine to medium gravel; loose, moist | | |
| | 4.0 | S-2 | NA | 4 | | 2.2 - 3.0' FILL: Concrete | 0 | |
| | 5.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 6.0 | | | | | 4.0 - 7.6' FILL: Gray silt, some fine sand, trace brick; dense, moist | | |
| | 7.0 | | | | | 7.6 - 8.0' FILL: Yellowish brown/ orange silty sand (COPR); soft | | |
| | 8.0 | S-3 | NA | .5 | | 8.0 - 8.5' FILL: Brown silty sand; wet | 0 | |
| | 9.0 | | | | | 8.5 - 12.0' : No recovery | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4 | | 12.0 - 16.0' PT: Peat; end of boring at 16' | 0 | |
| | 13.0 | | | | | | | Sample collected 125-SB-071-1214 from 12.5-13.0' bgs @12:50, DUP @12:52 |
| | 14.0 | | | | | | | Sample collected 125-SB-071-1416 from 14.0-14.5' bgs @12:55 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-072
**DATE BEGAN:** 5/4/10
**DATE FINISHED:** 5/4/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.3' ASPHALT | 0 | |
| | 1.0 | | | | | 0.3 - 1.0' FILL: Fine to medium gravel, dark brown silty fine to medium sand, trace wood and coal; dense, dry | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Red silt, some fine sand, trace coal and fine to medium gravel; dense, dry | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Black silty fine to medium, mottling of greenish gray silt (possible COPR); dense, moist | | |
| | 4.0 | S-2 | NA | 4 | | 3.0 - 3.9' FILL: Red silt, trace fine gravel; dense, dry | 0 | |
| ▽ | 5.0 | | | | | 3.9 - 4.0' FILL: Black silt, trace coal; medium dense, moist | | |
| | 6.0 | | | | | 4.0 - 4.5' FILL: Red silt, trace brick; dense, dry | | |
| | 7.0 | | | | | 4.5 - 7.9' FILL: Black silt, some fine sand; dense, wet | | |
| | 8.0 | S-3 | NA | 3.25 | | 7.9 - 8.0' FILL: COPR; green, orange, and white silt; soft, wet | 0 | |
| | 9.0 | | | | | 8.0 - 9.5' FILL: Brown silty sand, trace clay mottling; loose, wet | | |
| | 10.0 | | | | | 9.5 - 10.3' CL: Black silt, trace fine sand; very loose, wet | | |
| | 11.0 | | | | | 10.3 - 11.3' SM: Dark brown silty sand; loose, wet | | |
| | 12.0 | S-4 | NA | 3.5 | | 11.3 - 12.0' No recovery | 0 | Sample collected 125-SB-072-1214 from 12.5-13.0' bgs @13:35 |
| | 13.0 | | | | | 12.0 - 15.5' PT: Peat | | |
| | 14.0 | | | | | | | Sample collected 125-SB-072-1416 from 14.0-14.5' bgs @13:30 |
| | 15.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-073
**DATE BEGAN:** 5/4/10
**DATE FINISHED:** 5/4/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 0.8' FILL: Fine to medium gravel, dark brown silty sand; loose, dry | | |
| | 1.0 | | | | | 0.8 - 1.0' FILL: Fine to coarse gravel, trace brown silty sand; loose, wet | | |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Red silt, trace fine sand, wood, fine gravel, and coal; dense, dry | | |
| | 3.0 | | | | | 2.5 - 3.3' FILL: Dark brown silty fine to medium sand, trace coal, plaster, brick, and metal; dense, dry | | |
| | 4.0 | S-2 | NA | 2 | | 3.3 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Black silt, fine sand | | Creosote odor at 5.0' |
| | 6.0 | | | | | 4.5 - 5.0' FILL: Black fine to coarse sand, clinker, glass, wood, trace white silt and fine to medium gravel; wet | | |
| | 7.0 | | | | | 5.0 - 5.3' FILL: Wood | | |
| | | | | | | 5.3 - 5.8' FILL: COPR, whitish/green silt; soft | | |
| | 8.0 | S-3 | NA | 3.25 | | 5.8 - 6.0' FILL: Brown silt; loose, wet | 0 | |
| | 9.0 | | | | | 6.0 - 8.0' No recovery | | |
| | | | | | | 8.0 - 8.2' FILL: Brown silt; loose, wet | | |
| | 10.0 | | | | | 8.2 - 8.5' OL: Black silt, fine sand; wet | | |
| | 11.0 | | | | | 8.5 - 11.3' PT: Peat | | Sample collected 125-SB-073-1012 from 10.5-11.0' bgs @13:50 |
| | | | | | | 11.3 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 2 | | 12.0 - 14.0' PT: Peat; end of boring at 14' bgs. | 0 | Sample collected 125-SB-073-1214 from 12.5-13.0' bgs @13:55 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-074
**DATE BEGAN:** 5/4/10
**DATE FINISHED:** 5/4/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.8' FILL: Fine to medium gravel, brown silty fine to medium sand; dense, dry | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.8 - 2.8' FILL: Red silt, trace fine to medium gravel; dense, dry | | |
| | | | | | | 2.8 - 2.9' FILL: Brown silty fine to medium sand, trace clinker, coal, organics, and brick; dense, dry | | |
| | 3.0 | | | | | 2.9 - 3.8' FILL: Dark brown silty fine to medium sand, fine to medium gravel, trace coal, glass and mottling of yellowish/green/orange silt (possible COPR) | | |
| | | | | | | 3.8 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 4.3' FILL: Red silt | 0 | |
| | | | | | | 4.3 - 4.5' FILL: Brown fine to medium sand, fine to medium gravel | | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Black silt; dense, wet | | |
| | | | | | | 5.0 - 6.3' FILL: Drak brown silty sand, clinker, fine to medium gravel, trace glass, coal, and brick; loose, wet | | |
| | 6.0 | | | | | 6.3 - 6.5' FILL: Brown silt, some fine sand; loose, wet | | |
| | | | | | | 6.5 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-074
**DATE BEGAN:** 5/4/10
**DATE FINISHED:** 5/4/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 10.0' FILL: Brown silty sand, trace clay; firm, wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 10.3' OL: Black silt, trace fine sand | | Sample collected 125-SB-074-1012 from 10.5-11.0' bgs @14:20 |
| | | | | | | 10.3 - 10.5' SW: Brown fine to medium sand, lens of clay and silt | | |
| | 11.0 | | | | | 10.5 - 11.3' OL: Black silt, fine sand | | |
| | | | | | | 11.3 - 12.0' No recovery; end of boring at 12' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-075
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Fine to medium gravel, brown fine to medium sand, tar, some silt; dense, dry | | |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Red silt, fine sand | | |
| | | | | | | 1.3 - 1.8' FILL: Dark brown silt fine to medium sand, trace fine to medium gravel and coal; dense, dry | | |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Red silt, fine sand, trace fine to medium gravel; dense, dry | | |
| | | | | | | 2.5 - 2.7' FILL: Wood | | |
| | 3.0 | | | | | 2.7 - 4.0' FILL: Dark gray/ black silt; dense, moist | | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 4.8' FILL: Dark gray/ black silt; dense, wet | 0 | |
| | | | | | | 4.8 - 5.0' FILL: Dark brown fine to coarse sand, clinker, some brick | | |
| | 5.0 | | | | | 5.0 - 5.1' FILL: White lens of COPR, fine to medium gravel | | |
| | | | | | | 5.1 - 5.3' FILL: Dark brown fine to medium sand, clinker | | |
| | 6.0 | | | | | 5.3 - 5.5' FILL: Yellowish brown lens of COPR, medium sand; dense, wet | | |
| | | | | | | 5.5 - 7.3' FILL: Dark brown fine to medium sand, some clinker, fine to medium gravel, trace brick, wood; dense, wet | | |
| | 7.0 | | | | | 7.3 - 8.0' FILL: Green, gray, and white COPR, some wood, silt; soft | | |
| | 8.0 | S-3 | NA | 3 | | 8.0 - 10.5' OL: Brown sandy silt; loose, wet | 0 | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-075
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 10.6' SM: Brown fine to medium sand, trace silt | | Sample collected 125-SB-075-1012 from 10.5-11.0' bgs @ 8:00 |
| | | | | | | 10.6 - 11.0' PT: Peat | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.25 | | 12.0 - 15.3' PT: Peat | 0 | Sample collected 125-SB-075-1214 from 12.5-13.0' bgs @ 8:05 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 125-SB-075-1416 from 14.5-15.0' bgs @ 8:10 |
| | 15.0 | | | | | | | |
| | | | | | | 15.3 - 16.0' No recovery; end of boring at 16' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-076
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.3' CONCRETE | | |
| | 1.0 | | | | | 1.3 - 1.4' FILL: Brownish yellow/ white fine to medium sand, concrete; dry | | |
| | | | | | | 1.4 - 2.0' FILL: Reddish brown sandy silt, trace brick; dense, dry | | |
| | 2.0 | | | | | 2.0 - 2.2' FILL: Brownish yellow fine to medium sand, fine to medium gravel, possible COPR | | |
| | | | | | | 2.2 - 3.5' FILL: Dark brown fine to coarse sand, trace coal, clinker, brick; dense, moist | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' FILL: Dark gray silt, trace glass and coal; dense, moist | | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 4.5' FILL: Brown and gray silt, fine to medium gravel; soft | 0 | |
| | | | | | | 4.5 - 5.0' FILL: Gray silt; dense, wet | | |
| | 5.0 | | | | | 5.0 - 5.2' FILL: Brownish yellow lens of COPR, fine silty sand, trace fine to medium gravel | | |
| | | | | | | 5.2 - 7.0' FILL: Fine to medium sandy silt, trace clinker, coal, and brick; wood from 5.5-5.7, COPR from 6.7-6.8 | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: COPR, yellow to green silt, trace wood; soft, wet | | |
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 8.5' FILL: Brown silty sand, trace wood; | 0 | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-076
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | | | | | soft, wet | | |
| | 9.0 | | | | | 8.5 - 9.5' FILL: Brown sand, silt, trace organics; loose, wet | | |
| | | | | | | 9.5 - 10.3' FILL: Brown silt; loose, wet | | |
| | 10.0 | | | | | 10.3 - 11.3' PT: Peat | | Sample collected125-SB-076-1012 from 10.5-11.0' bgs @08:35, DUP @08:37 |
| | 11.0 | | | | | 11.3 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3 | | 12.0 - 15.0' PT: Peat | 0 | |
| | 13.0 | | | | | | | Sample collected 125-SB-076-1214 from 12.5-13.0' bgs @08:40 |
| | 14.0 | | | | | | | Sample collected 125-SB-076-1416 from 14.0-14.5' bgs @08:45 |
| | 15.0 | | | | | 15.0 - 16.0' No recovery; end of boring at 16' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-077
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 0.8' FILL: Fine to medium gravel, brown silty sand, some tar | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Red silt, some fine sand, trace fine to medium gravel | | |
| | | | | | | 1.3 - 2.3' FILL: Dark brown fine to medium sand, some silt, clinker, brick, coal and glass | | |
| | 2.0 | | | | | 2.3 - 2.8' FILL: Concrete | | |
| | | | | | | 2.8 - 3.0' FILL: Dark brown fine to medium sand, some silt, clinker, brick, and coal, trace fine to medium gravel; loose, moist | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.8' FILL: Dark brown fine to medium sand, some silt, clinker, brick, and coal, trace fine to medium gravel, orange and light yellow lens of COPR from 4.2-4.3; dense, wet | 0 | |
| | 5.0 | | | | | 4.8 - 4.9' FILL: Dark brown fine to medium sand; loose, wet | | Sample collected 125-SB-077-0406 from 5.0-5.5' bgs @09:00 |
| | | | | | | 4.9 - 5.5' FILL: Brown fine to medium sand, some silt, mottling of silt and clay; wet | | |
| | 6.0 | | | | | 5.5 - 6.8' FILL: Brown silt, trace fine sand; loose, wet | | |
| | 7.0 | | | | | 6.8 - 7.5' FILL: Brown fine to medium silt; loose, wet | | Sample collected 125-SB-077-0608 from 7.0-7.5' bgs @09:05 |
| | 8.0 | | | | | 7.5 - 8.0' No recovery; end of boring at 8' bgs. | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-078
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 2 | | -4.0 - -3.0' CONCRETE | 0 | |
| | -3.0 | | | | | -3.0 - -2.0' Void | | |
| | -2.0 | | | | | -2.0 - -1.5' FILL: Brown silty sand, fine to medium gravel; loose, dry | | |
| | -1.0 | | | | | -1.5 - 0.0' FILL: Brown clayey silt, fine to medium gravel; dense, moist | | Sample collected 125-SB-078-0200 from 1.0-.5' ags @07:45 |
| | 0.0 | S-2 | NA | 2 | | 0.0 - 1.5' FILL: Brown clayey silty sand, trace brick and coal; medium dense, moist | 0 | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Brown clayey silt, some sand, trace brick and fine to medium gravel; loose, wet | | Sample collected 125-SB-078-0002 from 1.0-1.5' bgs @07:50 |
| | 2.0 | | | | | 2.0 - 8.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-3 | NA | 0 | | | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-4 | NA | 3 | | 8.0 - 10.5' FILL: Brown fine to medium sand, lenses of clay and silt; loose, wet | 0 | Sample collected 125-SB-078-0810 from 8.5-9.0' bgs @07:55 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 11.0' FILL: Brown clayey silt; loose, wet | | Sample collected 125-SB-078-1012 from 10.5-11.0' bgs @08:00 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-5 | NA | 2 | | 12.0 - 13.0' FILL: Brown clayey silt, fine sand; firm, wet | 0 | Sample collected 125-SB-078-1214 from 12.5-13.0' bgs @08:05 |
| | 13.0 | | | | | 13.0 - 14.0' PT: Peat; end of boring at 14' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** **125-SB-078**
**DATE BEGAN:** 5/5/10
**DATE FINISHED:** 5/5/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125 | **PROJECT NO:** 3480050143 | **BORING ID:** 125-SB-079

**DATE BEGAN:** 5/6/10 | **DATE FINISHED:** 5/6/10 | **INSPECTOR:** M.Daly

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 14 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** G. Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 1.5 | | -4.0 - -3.3' CONCRETE | 0 | |
| | -3.0 | | | | | -3.3 - -2.0' Void | | |
| | -2.0 | | | | | -2.0 - -0.5' FILL: Brown silt, some fine sand, trace brick | | |
| | -1.0 | | | | | -0.5 - 0.0' No recovery | | Sample collected 125-SB-079-0200 from 1.0-0.5' ags @08:15 |
| | 0.0 | S-2 | NA | 3.5 | | 0.0 - 2.8' FILL: Brown clayey silt, some fine sand, trace fine to medium gravel, glass, coal, and brick; dense, moist | 0 | Sample collected 125-SB-079-0002 from 0.5-1.0' bgs @08:20 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.8 - 3.3' FILL: Dark brown fine to medium sand, clinker, coal, whit silt (possible COPR) | | Sample collected 125-SB-079-0204 from 3.0-3.5' bgs @08:25 (COPR sample) |
| ▽ | 4.0 | S-3 | NA | 3 | | 3.3 - 3.5' FILL: COPR, grayish white pastey silt | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | Sample collected 125-SB-079-0406 from 4.0-4.5' bgs @08:30 |
| | 6.0 | | | | | 4.0 - 4.8' FILL: Dark brown fine to medium sand, some wood; loose, wet | | |
| | 7.0 | | | | | 4.8 - 5.0' FILL: Brown clayey silt; firm, wet | | |
| | 8.0 | S-4 | NA | 3.25 | | 5.0 - 6.0' No recovery | 0 | Sample collected 125-SB-079-0608 from 6.5-7.0' bgs @08:35 |
| | 9.0 | | | | | 6.0 - 6.5' FILL: Dark brown sandy silt, clinker; very loose, wet | | |
| | | | | | | 6.5 - 7.3' FILL: Brown silt, fine sand; loose, wet | | |
| | | | | | | 7.3 - 7.5' No recovery | | |
| | | | | | | 7.5 - 9.5' FILL: Brown fine to medium sand, clay, trace silt; firm, wet | | Sample collected 125-SB-079-0810 from 9.0-9.5' bgs |

PREPARED BY: MS

CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-079
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | S-5 | NA | 2 | | 9.5 - 10.3' FILL: Brown silt; firm, wet | 0 | @08:40 |
| | 11.0 | | | | | 10.3 - 11.3' CL: Gray fine to medium sand, silt, and clay; medium firm, wet | | Sample collected 125-SB-079-1012 from 10.5-11.0' bgs @08:45 |
| | 12.0 | | | | | 11.3 - 12.0' No recovery | | |
| | 13.0 | | | | | 12.0 - 12.5' CL: Gray fine to medium sand, silt, and clay; medium firm, wet | | Sample collected 125-SB-079-1214 from 12.5-13.0' bgs @08:50 |
| | 14.0 | | | | | 12.5 - 14.0' PT: Peat; end of boring at 14' bgs. | | |

PREPARED BY: MS
CHECKED BY: QA/QC

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125 | **PROJECT NO:** 3480050143 | **BORING ID:** 125-SB-080

**DATE BEGAN:** 5/6/10 | **DATE FINISHED:** 5/6/10 | **INSPECTOR:** M.Daly

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 14 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** G. Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 2 | | -4.0 - -3.0' CONCRETE | 0 | |
| | -3.0 | | | | | -3.0 - -2.0' Void | | |
| | -2.0 | | | | | -2.0 - 0.0' FILL: Red silt, some fine sand, fine to medium gravel, wood; loose | | Sample collected 125-SB-080-0200 from 1.5-1.0' ags @09:10 |
| | -1.0 | | | | | | | |
| | 0.0 | S-2 | NA | 4 | | 0.0 - 2.5' FILL: Reddish brown silt, trace shells, lens of brick and coal from 1.9-2.0'; loose, moist | 0 | Sample collected 125-SB-080-0002 from 0.5-1.0' bgs @09:15, DUP @09:17 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.5 - 2.8' FILL: Concrete | | |
| | 3.0 | | | | | 2.8 - 4.3' FILL: Dark brown fine to medium sand, clinker, trace coal, fine to medium gravel, rubber, and porcelin; loose, moist | | Sample collected 125-SB-080-0204 from 3.0-3.5' bgs @09:20 |
| ▽ | 4.0 | S-3 | NA | 4 | | | 0 | |
| | 5.0 | | | | | 4.3 - 4.5' FILL: Grayish/white COPR, wood; soft, wet | | Sample collected 125-SB-080-0406 from 4.0-4.5' bgs @09:25 |
| | 6.0 | | | | | 4.5 - 6.0' FILL: Reddish brown silt, some fine sand, trace clay; firm, wet | | |
| | 7.0 | | | | | 6.0 - 7.5' FILL: Brown fine to medium sand, some silt; loose, wet | | Sample collected 125-SB-080-0608 from 7.0-7.5' bgs @09:30 |
| | 8.0 | S-4 | NA | 3 | | 7.5 - 8.0' FILL: Brown silt; loose, wet | 0 | |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Brown silt, lens of clay; firm, wet | | Sample collected 125-SB-080-0810 from 8.5-9.0' bgs @09:35 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.0' FILL: Brown silty sand; firm, wet | | Sample collected 125-SB-080-1012 from 10.5-11.0' bgs @09:40 |
| | 12.0 | S-5 | NA | 2 | | 11.0 - 12.0' No recovery | | |
| | 13.0 | | | | | 12.0 - 12.5' CL: Brown sandy clay, some silt; firm, wet | 0 | Sample collected 125-SB-080-1214 from 12.0-12.5' bgs @09:45 |
| | 14.0 | | | | | 12.5 - 14.0' PT: Peat; end of boring at 14' bgs. | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-081
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 2 | | -4.0 - -3.3' CONCRETE | 0 | |
| | -3.0 | | | | | -3.3 - -2.0' Void | | |
| | -2.0 | | | | | -2.0 - 0.0' FILL: Brown silt, some brick, trace fine sand and clay; firm, dry | | Sample collected 125-SB-081-0200 from 0.5-0.0' ags @10:50 |
| | -1.0 | | | | | | | |
| | 0.0 | S-2 | NA | 3.5 | | 0.0 - 2.0' FILL: Light reddish brown silt, fine to medium gravel, trace coal and brick; firm, moist | 0 | Sample collected 125-SB-081-0002 from 1.0-1.5' bgs @10:55 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Concrete | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown fine to coarse sand, some clinker and wood, trace fine to coarse gravel | | Sample collected 125-SB-081-0204 from 3.0-3.5' bgs @11:00 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| ▽ | 4.0 | S-3 | NA | 2.5 | | 4.0 - 5.0' Brown fine to coarse sand, some clinker and wood, trace fine to coarse gravel, band of greenish/ white sand at 4.1-4.2' (possible COPR); loose, wet | 0 | Sample collected 125-SB-081-0406 from 4.0-4.5' bgs @11:05 |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Brown fine to medium sand; loose, wet | | |
| | | | | | | 5.5 - 6.0' No recovery | | |
| | 6.0 | | | | | | | Sample collected 125-SB- |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-081
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 7.0 | | | | | 6.0 - 6.5' FILL: Grayish brown fine to medium sand; loose, wet | | 081-0608 from 6.0-6.5' bgs @11:10, DUP @11:12 |
| | 8.0 | S-4 | NA | 3 | | 6.5 - 7.0' FILL: Brown silt, some fine sand, trace organics; loose, wet | 0 | |
| | 9.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 8.3' FILL: Brown silt, some fine sand, trace organics; loose, wet | | |
| | 11.0 | | | | | 8.3 - 10.8' FILL: Grayish brown fine to medium sand, lenses of silt; loose, wet | | Sample collected 125-SB-081-0810 from 8.5-9.0' bgs @11:15 |
| | 12.0 | S-5 | NA | 1.5 | | 10.8 - 11.0' CL: Brown silt, some fine sand, trace organics; firm, wet | 0 | Sample collected 125-SB-081-1012 from 10.5-11.0' bgs @11:20 |
| | 13.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 14.0 | | | | | 12.0 - 12.5' CL: Brown silt, some fine sand, trace organics; firm, wet | | |
| | | | | | | 12.5 - 13.5' PT: Peat | | Sample collected 125-SB-081-1214 from 13.0-13.5' bgs @11:25 |
| | | | | | | 13.5 - 14.0' No recovery; end of boring at 14' bgs. | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-082
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 1.5 | | -4.0 - -3.3' CONCRETE | 0 | |
| | -3.0 | | | | | -3.3 - -2.0' Void | | |
| | -2.0 | | | | | -2.0 - -0.5' FILL: Reddish brown silt, some fine sand, trace fine to medium gravel, brick, and clay; firm, dry | | Sample collected 125-SB-082-0200 from 1.0-0.5' ags @10:15 |
| | -1.0 | | | | | -0.5 - 0.0' No recovery | | |
| | 0.0 | S-2 | NA | 3 | | 0.0 - 2.0' FILL: Reddish brown silt, some fine sand, trace fine to medium gravel, brick, and clay; firm, dry | 0 | Sample collected 125-SB-082-0002 from 0.5-1.0' bgs @10:20 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Brown fine to medium sand, trace fine to medium gravel, coal, brick, clinker, porcelain, concrete, and wood | | Sample collected 125-SB-082-0204 from 2.5-3.0' bgs @10:25 |
| | 3.0 | | | | | 3.0 - 3.0' FILL: COPR, grayish/ white silt; soft, moist | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-3 | NA | 1.75 | | 4.0 - 4.3' FILL: Brown silt; hard, dry | 0 | Sample collected 125-SB-082-0406 from 4.0-4.5' bgs @10:30 |
| | | | | | | 4.3 - 4.8' FILL: Brown fine to medium sand; loose, wet | | |
| | 5.0 | | | | | 4.8 - 6.0' No recovery; end of boring at 6' bgs. | | |
| | 6.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-083
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 2.5 | | -4.0 - -3.3' CONCRETE | 0 | |
| | -3.0 | | | | | -3.3 - -2.5' Void | | |
| | -2.0 | | | | | -2.5 - 1.8' FILL: Red silt, some fine sand, trace coal, brick, glass, and fine to medium gravel; medium dense, dry | | |
| | -1.0 | | | | | | | Sample collected 125-SB-083-0200 from 1.0-0.5' ags @12:40 |
| | 0.0 | S-2 | NA | 3.5 | | | 0 | |
| | 1.0 | | | | | 1.8 - 2.0' FILL: Brown silty sand, fine to medium gravel, trace coal, brick, and wood; loose, moist | | Sample collected 125-SB-083-0002 from 1.5-2.0' bgs @12:45 |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Dark brown fine to medium sand, some clinker and wood, trace coal, newspaper, glass, and rubber; loose, moist | | Sample collected 125-SB-083-0204 from 2.5-3.0' bgs @12:50 |
| | 3.0 | | | | | | | |
| | 4.0 | S-3 | NA | 2.5 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: White silty fiber mixed with paper (possible COPR) | | Sample collected 125-SB-083-0406 from 4.0-4.5' bgs @12:55 |
| | 6.0 | | | | | 4.5 - 5.5' FILL: Brown fine to medium sand, trace silt; loose, wet | | |
| | 7.0 | | | | | 5.5 - 6.0' No recovery | | |
| | | | | | | 6.0 - 6.8' FILL: Brown sandy silt, trace organics; loose, wet | | |
| | | | | | | 6.8 - 7.0' FILL: Brown fine to medium sand | | Sample collected 125-SB-083-0608 from 6.5-7.0' bgs @13:00 |
| | | | | | | 7.0 - 8.0' No recovery | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-083
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-4 | NA | 2.5 | | 8.0 - 10.3' FILL: Brown fine to medium sand, lenses of silt; loose, wet | 0 | Sample collected 125-SB-083-0810 from 9.0-9.5' bgs @13:05 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.3 - 10.5' FILL: Brown silt; firm, wet | | |
| | | | | | | 10.5 - 12.0' No recovery | | Sample collected 125-SB-083-1012 from 10.0-10.5' bgs @13:10 |
| | 11.0 | | | | | | | |
| | 12.0 | S-5 | NA | 1 | | 12.0 - 12.8' OL: Gray sandy silt, trace clay and organics; firm, wet | 0 | Sample collected 125-SB-083-1214 from 12.0-12.5' bgs @13:15 |
| | 13.0 | | | | | 12.8 - 13.0' PT: Peat | | |
| | | | | | | 13.0 - 14.0' No recovery; end of boring at 14' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-084
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 2.75 | | -4.0 - -3.8' CONCRETE | 0 | |
| | | | | | | -3.8 - -2.8' Void | | |
| | -3.0 | | | | | -2.8 - 0.0' FILL: Red silt, trace sand, coal, fine to medium gravel | | Sample collected 125-SB-084-0200 from 1.5-1.0' ags @13:40 |
| | -2.0 | | | | | | | |
| | -1.0 | | | | | | | |
| | 0.0 | S-2 | NA | 4 | | 0.0 - 1.5' FILL: Reddish brown sandy silt, trace coal, brick, and fine to medium gravel; medium dense, moist | 0 | Sample collected 125-SB-084-0002 from 1.0-1.5' bgs @13:45 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Brick | | |
| | | | | | | 2.0 - 2.5' FILL: Brown silt, some fine sand, trace clay, coal, and fine to medium gravel; loose, dry | | Sample collected 125-SB-084-0204 from 2.5-3.0' bgs @13:50 |
| | 3.0 | | | | | 2.5 - 4.0' FILL: Dark brown fine to medium sand, some clinker, brick, coal, and fine to medium gravel; loose, moist | | |
| ▽ | 4.0 | S-3 | NA | 4 | | 4.0 - 4.3' FILL: Brick | 0 | |
| | | | | | | 4.3 - 6.0' FILL: Dark brown fine to medium sand, trace wood | | Sample collected 125-SB-084-0406 from 4.5-5.0' bgs @13:55 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 8.0' FILL: Brown silt, fine sand, trace clay; loose, wet | | |
| | 7.0 | | | | | | | Sample collected 125-SB-084-0608 from 7.0-7.5' bgs @14:00 |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-084
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-4 | NA | 2 | | 8.0 - 8.5' FILL: Brown clayey silt, some fine to medium sand; firm, wet | 0 | |
| | 9.0 | | | | | 8.5 - 10.0' FILL: Brown fine to medium sand, lenses of clay and silt; medium dense, wet | | Sample collected 125-SB-084-0810 from 9.0-9.5' bgs @14:05 |
| | 10.0 | | | | | 10.0 - 12.0' No recovery | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-5 | NA | 2 | | 12.0 - 12.3' ML: Gray silty sand, trace organics; loose, wet | 0 | Sample collected 125-SB-084-1214 from 12.0-12.5' bgs @14:10 |
| | | | | | | 12.3 - 12.5' CL: Gray silty clay, trace organics; firm, wet | | |
| | 13.0 | | | | | 12.5 - 14.0' PT: Peat; end of boring at 14' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-085
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 1 | | -4.0 - -2.5' CONCRETE | 0 | |
| | -3.0 | | | | | -2.5 - -1.5' Void | | |
| | -2.0 | | | | | -1.5 - -0.5' FILL: Red silt, trace fine sand, clay, coal, and fine to medium gravel; firm, dry | | |
| | -1.0 | | | | | -0.5 - 0.0' No recovery | | |
| | 0.0 | S-2 | NA | 2.25 | | 0.0 - 0.9' Red silt, trace fine sand, clay, coal, and fine to medium gravel, lens of concrete from 0.3-0.5'; firm, dry | 0 | Sample collected 125-SB-085-0002 from 0.5-1.0' bgs @14:50 |
| | 1.0 | | | | | 0.9 - 1.0' FILL: Dark brown fine to medium sand, some clinker and coal; loose, dry | | |
| | 2.0 | | | | | 1.0 - 2.0' No recovery | | |
| | 3.0 | | | | | 2.0 - 2.5' Dark brown fine to medium sand, some clinker and coal; loose, dry | | Sample collected 125-SB-085-0204 from 2.5-3.0' bgs @14:55 |
| ▽ | 4.0 | S-3 | NA | 4 | | 2.5 - 3.0' FILL: Grayish white silt, glass, wood, bones, rock, lens of purple staining at 2.6-2.8' | 0 | |
| | 5.0 | | | | | 3.0 - 3.3' FILL: Reddish brown sand, trace clay and sandstone; loose, moist | | |
| | 6.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 7.0 | | | | | 4.0 - 6.0' FILL: Brown fine to medium clayey sand, some silt | | Sample collected 125-SB-085-0406 from 5.5-6.0' bgs @15:00 |
| | | | | | | 6.0 - 11.0' FILL: Fine to medium sand, some silt, lens of clay and silt; loose, wet | | Sample collected 125-SB-085-0608 from 7.0-7.5' bgs @15:05 |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-085
**DATE BEGAN:** 5/6/10
**DATE FINISHED:** 5/6/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-4 | NA | 3.25 | | | 0 | Sample collected 125-SB-085-0810 from 8.5-9.0' bgs @15:10 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' ML: Brown silt, some fine sand, trace organics; firm, wet | | Sample collected 125-SB-085-1012 from 11.0-11.5' bgs @15:15 |
| | 12.0 | S-5 | NA | 2 | | 12.0 - 12.5' OL: Gray sandy silt, trace organics; firm, wet | 0 | Sample collected 125-SB-085-1214 from 12.0-12.5' bgs @15:20 |
| | 13.0 | | | | | 12.5 - 14.0' PT: Peat; end of boring at 14' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-086
**DATE BEGAN:** 5/7/10
**DATE FINISHED:** 5/7/10
**INSPECTOR:** M.Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.5' ASPHALT: Gravel | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Dark brown silty sand, coal, glass, brick, gravel | | |
| | 2.0 | | | | | 1.5 - 4.5' FILL: Red brown silt, fine sand, brick, gravel | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3 | | | 0 | |
| | 5.0 | | | | | 4.5 - 6.0' FILL: Light brown silt, trace fine sand and fine to medium gravel | | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Light brown silt, wood, potential COPR; wet at 5.5' | | |
| | 7.0 | | | | | 6.5 - 7.0' FILL: Brown fine to medium sand, trace organics; wet | | |
| | 8.0 | S-3 | NA | 4 | | 7.0 - 8.0' No recovery<br>8.0 - 8.5' Brown fine to medium sand, trace organics; wet | 0 | |
| | 9.0 | | | | | 8.5 - 10.0' OL: Brown silt, heavy organics | | |
| | 10.0 | | | | | 10.0 - 12.0' PT: Brown moist peat; end of boring at 12' bgs. | | |
| | 11.0 | | | | | | | Sample collected 125-SB-086-1012 from 11.0-11.5' bgs @ 8:55 |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-087
**DATE BEGAN:** 8/18/10
**DATE FINISHED:** 8/18/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and Gravel | 0 | |
| | | | | | | 0.5 - 3.0' FILL: Dark brown silty sand, brick, wood, gravel, glass, coal | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 4.3' FILL: Dark brown silty sand, brick, wood, gravel, glass, coal | 0 | |
| | | | | | | 4.3 - 6.0' FILL: Light brown silt with fine to medium sand, wet at 4.5' bgs.; end of boring at 6.0 ft. bgs. | | |
| | 5.0 | | | | | | | Sample collected 125-SB-087-0406 from 5.0-5.5' bgs @ 10:05 |
| | 6.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-088
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and Gravel | 0 | |
| | | | | | | 0.5 - 3.5' FILL: Brown silty sand, gravel, glass, trace brick | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 4.5' FILL: Brown silty sand, gravel, glass, trace brick; wet | 0 | |
| | | | | | | 4.5 - 6.5' FILL: Light brown fine to coarse sand, lenses of red brown/light brown silt; wet | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 125-SB-088-0608 from 6.0-6.5' bgs @ 13:20 |
| | | | | | | 6.5 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 10.0' FILL: Light brown fine to coarse sand, lenses of red brown/light brown silt; saturated; end of boring at 10.0' bgs. | 0 | Sample collected 125-SB-088-0810 from 8.0-8.5' bgs @ 13:25 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 125
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-089
**DATE BEGAN:** 10/26/10
**DATE FINISHED:** 10/26/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and Gravel | 0 | |
| | | | | | | 0.5 - 3.0' FILL: Dark brown silty sand, gravel, brick, clinker | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 5.5' FILL: Dark brown silt; wet at 4.5' bgs. | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Light brown silt with fine to coarse sand | | |
| | | | | | | 6.5 - 8.0' No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 10.0' FILL: Light brown fine to coarse sand, lenses of silt; saturated; end of boring at 10.0' bgs. | 0 | Sample collected 125-SB-089-0810 from 8.0-8.5' bgs @ 13:45 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site 125

**LOCATION:** Honeywell SA-6 South
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-090
**DATE BEGAN:** 3/23/2011
**DATE FINISHED:** 3/23/2011
**INSPECTOR:** M.Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** -13.5
**GW DEPTH:** 7 ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 0 | | -4.0 - -3.5' CONCRETE | 0 | |
| | -3.0 | | | | | -3.5 - -2.5' Void | | |
| | -2.0 | | | | | -2.5 - -0.5' FILL: Reddish brown silty fine to medium sand, trace tile | | |
| | -1.0 | | | | | | | |
| | 0.0 | S-2 | NA | 3 | | -0.5 - 1.5' no recovery | 0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Reddish brown silty fine to medium sand, trace brick; dry | | |
| | 3.0 | | | | | 3.5 - 4.0' FILL: reddish brown silt, some fine sand, dense; moist | | |
| | 4.0 | S-3 | NA | 3 | | 4.0 - 4.5' FILL: Degraded Red Brick | 0 | |
| | 5.0 | | | | | 4.5 - 5.5' No Recovery | | |
| | 6.0 | | | | | 5.0 - 5.5' FILL: Brown fine to medium sand; loose, wet | | |
| | 7.0 | | | | | 5.5 - 6.0' FILL: Brown fine to medium sand; loose, wet | | |
| | 8.0 | S-4 | NA | 3.5 | | 6.0 - 7.0' FILL: Dark grey silty fine to medium sand, some fine to medium gravel gravel and organics | 0 | |
| | 9.0 | | | | | 7.0 - 8.5' FILL: Dark grey fine to medium sand; dense, wet | | |
| | 10.0 | | | | | 8.5 - 9.0' Fill: Brown sandy silt; moderate dense, wet | | |
| | 11.0 | | | | | 9.0 - 9.5' FILL: No Recovery | | Sample collected 125-SB-090-1012 from 11.0-11.5' bgs @11:53 |
| | 12.0 | S-5 | NA | 3.5 | | 9.5 - 10.5' FILL: Dark grey fine to medium sand, trace fine to medium gravel | 0 | |
| | 13.0 | | | | | 10.5 - 11.0' FILL: Brown silty clay; loose, wet | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell Site 125

**LOCATION:** Honeywell SA-6 South
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-090
**DATE BEGAN:** 3/23/2011
**DATE FINISHED:** 3/23/2011
**INSPECTOR:** M.Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** -13.5
**GW DEPTH:** 7 ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | | | | | 11.0 - 13.0' FILL: Greyish brown fine to medium sand, trace silt and mottling of reddish brown silty clay; moderate dense, wet | | |
| | | | | | | 13.0 - 13.5' FILL: No recovery; end of boring @ 13.5' bgs | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell Site 125

**LOCATION:** Honeywell SA-6 South
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-091
**DATE BEGAN:** 3/23/2011
**DATE FINISHED:** 3/23/2011
**INSPECTOR:** M.Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** -10
**GW DEPTH:** 4 ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | S-1 | NA | 2 | | -4.0 - -3.0' CONCRETE | 0 | |
| | -3.0 | | | | | -3.0 - -2.0' Void | | |
| | -2.0 | | | | | -2.0 - 0.0' FILL: Red silt, some fine sand, fine to medium gravel, wood, loose | | |
| | -1.0 | | | | | | | |
| | 0.0 | S-2 | NA | 3.5 | | 0.0 - 2.0' FILL: Light reddish brown silt, fine to medium gravel, trace coal and brick; firm, moist | 0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Concrete | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown fine to coarse sand, some clinker and wood, trace fine to coarse gravel | | |
| | 4.0 | S-3 | NA | 2.5 | | 3.5 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' Brown fine to coarse sand, some clinker and wood, trace fine to coarse gravel, band of greenish/ white sand at 4.1-4.2' (possible COPR); loose, wet | | |
| | 6.0 | | | | | 5.0 - 5.5' FILL: Brown fine to medium sand; loose, wet | | |
| | 7.0 | | | | | 5.5 - 6.0' No recovery | | |
| | 8.0 | S-4 | NA | 3 | | 6.0 - 6.5' FILL: Grayish brown fine to medium sand; loose, wet | 0 | |
| | 9.0 | | | | | 6.5 - 7.0' FILL: Brown silt, some fine sand, trace organics; loose, wet | | Sample collected 125-SB-091-0810 from 8.5-9.0' bgs @15:20 |
| | 10.0 | | | | | 7.0 - 8.0' No recovery | | |
| | | | | | | 8.0 - 8.3' FILL: Brown silt, some fine sand, | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell Site 125

**LOCATION:** Honeywell SA-6 South
**PROJECT NO:** 3480050143
**BORING ID:** 125-SB-091
**DATE BEGAN:** 3/23/2011
**DATE FINISHED:** 3/23/2011
**INSPECTOR:** M.Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** -10
**GW DEPTH:** 4 ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | S-5 | NA | | | trace organics; loose, wet<br>8.3 - 10.8' FILL: Grayish brown fine to medium sand, lenses of silt; loose, wet<br>10.8 - 11.0' CL: Brown silt, some fine sand, trace organics; firm, wet<br>11.0 - 12.0' No recovery<br>12.0 - 12.5' CL: Brown silt, some fine sand, trace organics; firm, wet<br>12.5 - 13.5' PT: Peat<br>13.5 - 14.0' No recovery; end of boring at 14' | 0 | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 125
**PROJECT NO:** 3480
**BORING ID:** 125-SB-092
**DATE BEGAN:** 3/24/11
**DATE FINISHED:** 3/24/11
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | | | |
| | -1.0 | | NA | NA | | 0.0 - 10.0' See Boring Log 125-SB-079 for Details | | |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | | | |
| | -4.0 | | | | | | | |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | | | |
| | -9.0 | | | | | | | Sample collected 125-SB-092-0810 from 8.5-9.0 bgs at 16:25 |
| | -10.0 | | | | | | | |

PREPARED BY: KK
CHECKED BY: TG

# Honeywell Study Area - 6 South

**LOCATION:** Site 125, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 125-SB-116
**DATE BEGAN:** 11/4/2011
**DATE FINISHED:** 11/4/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 2 | 2.0 | | 10.0 - 11.8' FILL: Reddish brown fine to medium sand, fine gravel, silt, some clay; wet | N/A | Location HSA-9 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 3 | | | | | |
| | 11.0 | | 6 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | | 2 | 2.0 | | 11.8 - 12.0' FILL: Coal | | |
| | | | | | | 12.0 - 12.5' FILL: Reddish brown fine to medium sand, trace silt | N/A | |
| | | | 2 | | | 12.5 - 14.0' PT: Dark brown peat; end of boring @ 14.0' bgs | | Collected 125-SB-116-1213 from 12.5 - 13.0 ft bgs @ 09:55 |
| | 13.0 | | 3 | | | | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 125, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 125-SB-117
**DATE BEGAN:** 11/4/2011
**DATE FINISHED:** 11/4/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 2 | 2.0 | | 10.0 - 11.8' FILL: Greyish brown fine to medium sand, trace silt; loose, moist | N/A | Location HSA-10 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 11.0 | | 3 | | | | | |
| | | | 2 | | | | | |
| | | | | | | 11.8 - 12.0' FILL: COPR | | |
| | 12.0 | | 1 | 2.0 | | 12.0 - 16.0' PT: Very dark brown peat; end of boring @ 16.0' bgs | N/A | |
| | | | 2 | | | | | Collected 125-SB-117-1213 from 12.5 - 13.0 ft bgs @ 11:15 |
| | 13.0 | | 2 | | | | | |
| | | | 4 | | | | | Collected 125-SB-117-1314 from 13.5 - 14.0 ft bgs @ 11:20 |
| | 14.0 | | NR | 2.0 | | | | |
| | | | NR | | | | | |
| | 15.0 | | NR | | | | | |
| | | | NR | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 125
**PROJECT NO:** 3480100027
**BORING ID:** 125-SB-118
**DATE BEGAN:** 1/16/2012
**DATE FINISHED:** 1/16/2012
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4 ft Macrocore
**COMPLETION DEPTH:** 8ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Jake/Brian
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' CONCRETE | | |
| | | | | | | 0.5 - 1.3' FILL: Dark grey silt, some fine to medium gravel, trace ash, tiles | | |
| | 1.0 | | | | | 1.3 - 2.0' CONCRETE: degraded | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark grey fine sand, some silt, brown ash, grey ash; moist @ 2.0', loose | | |
| | | | | | | 2.5 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | | 2.5 | | 4.0 - 4.5' FILL: Brown fine to medium sand; moist | | |
| | | | | | | 4.5 - 5.8' FILL: Brown silt, trace fine sand, roots; wet, stiff | | Sample collected 125-SB-118-0406 from 4.5 - 5.0' bgs @14:02 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.8 - 6.5' FILL: Dark grey silt, coal, ash, fine to medium gravel, trace light grey silt; wet, very loose | | Sample collected 125-SB-118-0608 from 6.0 - 6.5' bgs @14:05 |
| | | | | | | 6.5 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 124, Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 125-SB-119
**DATE BEGAN:** 1/17/12
**DATE FINISHED:** 1/18/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57; freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | S-1 | 1<br>2<br>2<br>3 | 2.0 |  | 12.0 - 12.3' OH: Black (2/5 YR 2.5/1) silt, some clay, trace organic material, yellow COPR from 12-12.02'; soft, plastic, wet<br><br>12.3 - 14.0' PT: Dark olive brown (2.5 YR 3/3) peat; medium stiff, moist; end of boring at 14' | N/A | Adjacent to HSA-10. Refusal at 5 ft bgs on 11/17/12. On 1/18/12, moved 4 ft north and augered to 12 ft bgs before sampling.<br><br>125-SB-119-1213 collected from 12.5 - 13.0' bgs @ 08:20 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: MM

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 125-SB-120
**DATE BEGAN:** 1/18/2012
**DATE FINISHED:** 1/18/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57, freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | S-1 | WOH | 2.0 | | 10.0 - 11.4' FILL: Very dark grayish brown silt, some fine sand, green and gray COPR from 10.8' bgs; medium stiff, wet | N/A | Location HSA-11 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 2 | | | | | |
| | -11.0 | | 3 | | | | | No sample taken |
| | | | 3 | | | 11.4 - 11.7' OH: Black silt, some clay and organic material; medium stiff, wet | | |
| | -12.0 | | | | | 11.7 - 12.0' PT: Dark olive brown (2.5YR 3/3) peat; medium stiff, moist; end of boring @ 12.0' bgs | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-601
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684497.0624
**EAST:** 602720.6280

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.8' ASPHALT | 1.5 | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Grey coarse to fine SAND, medium to fine gravel; loose; dry | 1.4 | |
| | | | | | | | 0.8 | |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Dark brown coarse to fine SAND, medium to fine gravel, brick, coal, wood; loose; moist | 0.8 | |
| | | | | | | 2.5 - 4.0' No Recovery | 0.7 | |
| | 3.0 | | | | | | 0.5 | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 6.0' FILL: Reddish-brown SILT, some coarse to fine sand, medium to fine gravel; medium dense; moist | 0 | |
| | 5.0 | | | | | | 0.6 | |
| | | | | | | | 2.5 | |
| | 6.0 | | | | | 6.0 - 6.5' FILL: Reddish-brown SILT; medium dense; moist | 9.5 | |
| | | | | | | 6.5 - 7.0' FILL: Brown SILT, some fine gravel; medium dense; moist | 4.6 | |
| | 7.0 | | | | | 7.0 - 7.3' FILL: Grey coarse to fine SAND, silt, wood; loose; wet | 2.2 | Sample 125-SB-601-LL1 from 7.0-8.7 ft bgs @ 1330 |
| | | | | | | 7.3 - 7.5' FILL: Brown coarse to fine SAND; loose; moist | 1.4 | |
| | 8.0 | S-3 | NA | 4.0 | | | | |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-601
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684497.0624
**EAST:** 602720.6280

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No Recovery | | |
| | | | | | | 8.0 - 8.3' FILL: Reddish-brown SILT; medium dense; moist | 0.6 | Sample 125-SB-601-LL2 from 8.7-10.3 ft bgs @ 1335; EnCore taken from 125-SB-601-LL2 at 1335 |
| | 9.0 | | | | | 8.3 - 10.0' FILL: Dark brown coarse to fine SAND, fine gravel | 0.5 | |
| | | | | | | | 0.2 | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Dark brown SILT, trace fine gravel; medium dense; moist | 1.0 | Sample 125-SB-601-VV2 from 10.3-11.6 ft bgs @ 1340; EnCore taken from 125-SB-601-VV2 at 1340 |
| | | | | | | | 0.9 | |
| | 11.0 | | | | | 11.0 - 11.8' FILL: Black coarse to fine SAND; loose; wet | 1.0 | |
| | | | | | | | 0.4 | |
| | 12.0 | | | | | 11.8 - 12.0' PEAT | | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-602
**DATE BEGAN:** 07/26/2013
**DATE FINISHED:** 07/24/2013
**INSPECTOR:** V. Whelan
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684540.2275
**EAST:** 602750.0541

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 8.0' Push to 8 ft bgs. | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-1 | NA | 4.0 | | 8.0 - 8.5' Reddish-brown SILT, trace fine sand, trace clay; soft, low plasticity; moist | 0.3 | |
| | | | | | | 8.5 - 9.0' Mottled reddish-brown SILT, dark gray coarse to fine sand, trace fine gravel; loose; moist | 0.4 | Sample 125-SB-602-WW1 from 8.5-10.1 ft bgs @ 0815 |
| | 9.0 | | | | | | 0.4 | |
| | | | | | | 9.0 - 12.0' Dark gray coarse to fine SAND, little silt, color darkening with depth; loose; wet from 9.0-10 ft bgs, moist from 10-12 ft bgs | 0.1 | |
| | 10.0 | | | | | | 0.8 | Sample 125-SB-602-WW2 from 10.1-11.4 ft bgs @ 0820; EnCore taken from 125-SB-602-WW2 @ 0820 |
| | | | | | | | 1.1 | |
| | 11.0 | | | | | | 1.5 | |
| | | | | | | | 1.4 | End of boring at 12 ft bgs |
| | 12.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** **125-SB-603**
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684600.4861
**EAST:** 602566.6490

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT | 0.6 | Sample 125-SB-603-Q1 from 0.0-1.1 ft bgs @ 1300 |
| | 1.0 | | | | | 0.8 - 2.5' FILL: Dark brown/reddish-brown SILT, fine gravel; medium dense; moist | 0.3<br>0.7<br>0.5 | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Black medium to fine SAND, silt, some fine gravel, trace wood; medium dense; moist | 0.4<br>0.6 | Sample 125-SB-603-Q2 from 1.1-3.5 ft bgs @ 1305; EnCore taken from 125-SB-603-Q2 @ 1305 |
| | 4.0 | | | | | 3.5 - 4.0' No Recovery | | End of boring at 4.0 ft bgs |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-604
**DATE BEGAN:** 07/26/2013
**DATE FINISHED:** 07/26/2013
**INSPECTOR:** H. Cerbone
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684602.8905
**EAST:** 602675.5053

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | | | |
| | | | | | | -4.0 - 0.0' Direct push through concrete pad to 0 ft. | | PID not working. |
| | -3.0 | | | | | | | |
| | -2.0 | | | | | | | |
| | -1.0 | | | | | | | |
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 3.3' FILL: Dark reddish-brown medium to fine SAND, little silt, trace coarse sand, brick; dry | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | 1st attempt - hit debris at 2.5 ft bgs |
| | 4.0 | S-2 | NA | 4.0 | | 3.3 - 4.0' FILL: Black fine SAND, trace coarse to medium sand and dark reddish-brown medium to fine sand, little silt; moist | | |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-604
**DATE BEGAN:** 07/26/2013
**DATE FINISHED:** 07/26/2013
**INSPECTOR:** H. Cerbone
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684602.8905
**EAST:** 602675.5053

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Brown/black/reddish-brown coarse to fine SAND, little silt, wood pieces, brick, large gravel; moist | | |
| | 5.0 | | | | | | | Sample 125-SB-604-KK1 from 5.5-7.6 ft bgs @ 1130 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample 125-SB-604-KK2 from 7.6-9.3 ft bgs @ 1135; EnCore taken from 125-SB-604-KK2 @ 1135 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 8.5' FILL: Dark brown SILT and fine SAND, trace coarse to medium sand; wet | | |
| | 9.0 | | | | | 8.5 - 10.0' FILL: White/green clayey SILT, possible COPR; moist | | Sample 125-SB-604-XX1 from 9.3-10.9 ft bgs @ 1140; EnCore taken from 125-SB-604-XX1 @ 1140 |
| | 10.0 | | | | | 10.0 - 11.7' FILL: Dark brown/black coarse to fine SAND; wet | | |
| | 11.0 | | | | | | | Sample 125-SB-604-XX2 from 10.9-12.2 ft bgs @ 1145 |
| | 12.0 | | | | | 11.7 - 12.0' FILL: Dark brown/black fine SAND; wet | | End of boring at 12 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-605
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684627.3310
**EAST:** 602581.3458

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' ASPHALT | | Sample 125-SB-605-P1 from 0.0-1.2 ft bgs @ 1140 |
| | | | | | | 0.5 - 1.0' FILL: Dark brown coarse to fine SAND, medium to fine gravel; loose; dry | 0.5 | |
| | 1.0 | | | | | 1.0 - 1.3' ASPHALT | 0.8 | |
| | | | | | | 1.3 - 3.0' FILL: Reddish-brown to dark brown SILT, some fine sand, some medium to fine gravel, some wood; medium dense; moist | 0.8 | Sample 125-SB-605-P2 from 1.2-3.6 ft bgs @ 1145; EnCore taken from 125-SB-605-P2 @ 1145 |
| | 2.0 | | | | | | 1.2 | |
| | | | | | | | 0.9 | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Black SILT, some medium to fine gravel; dense; moist | 0.9 | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.8' FILL: Reddish-brown to dark brown SILT, some fine sand; loose; moist | 0.7 | |
| | 5.0 | | | | | 4.8 - 6.0' FILL: Black SILT, coarse to fine sand, medium to fine gravel, coal, wood, ash; dense; moist | 0.9 | Sample 125-SB-605-II1 from 5.1-7.2 ft bgs @ 1150; EnCore taken from 125-SB-605-II1 @ 1150 |
| | | | | | | | 1.8 | |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Black SILT, some coarse to fine sand, medium to fine gravel, wood, light grey lense at 6.5 ft bgs; loose; wet | 0.9 | |
| | | | | | | | 0.8 | |
| | 7.0 | | | | | 7.0 - 8.0' No Recovery | | Sample 125-SB-605-II2 from 7.2-8.9 ft bgs @ 1155 |
| | 8.0 | S-3 | NA | 1.0 | | 8.0 - 9.0' FILL: Black coarse to fine SAND, medium to fine gravel, wood, metal, plastic, loose, wet | 1.0 | |
| | 9.0 | | | | | 9.0 - 10.0' No Recovery | 1.0 | |
| | 10.0 | | | | | | | End of boring at 10 ft bgs. |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-606
**DATE BEGAN:** 07/23/2013
**DATE FINISHED:** 07/23/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684642.4436
**EAST:** 602630.2665

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 4.0 | | 4.0 - 4.8' FILL: Black / Reddish-brown SILT, trace fine gravel; medium dense; wet | 0 | |
| | 5.0 | | | | | 4.8 - 8.0' FILL: Black SILT, white medium to fine gravel from 7.0-7.25 ft bgs; medium dense; moist | 0<br>0<br>0<br>0<br>0<br>0 | Sample 125-SB-606-JJ1 from 5.4-7.5 ft bgs @ 1345 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-2 | NA | 4.0 | | 8.0 - 10.0' FILL: Black SILT; medium dense; moist | 0<br>0.1 | Sample 125-SB-606-JJ2 from 7.5-9.2 ft bgs @ 1350; EnCore taken from 125-SB-606-JJ2 @ 1350 |
| | 9.0 | | | | | | 0 | |
| | 10.0 | | | | | 10.0 - 10.5' FILL: Reddish-brown SILT; medium dense; wet | 0<br>0 | |
| | 11.0 | | | | | 10.5 - 12.0' FILL: Black SILT, fine gravel; medium dense; wet | 0<br>0<br>0 | |
| | 12.0 | | | | | | | End of boring at 12 ft bgs. |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 125
**PROJECT NO:** 3480130354
**BORING ID:** 125-SB-607
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 684680.7717
**EAST:** 602584.0706

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' FILL: Black coarse to fine SAND, medium to fine gravel, asphalt; loose; dry | 0 | Sample 125-SB-607-W1 from 1.2-3.6 ft bgs @ 1110 |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Reddish-brown SILT, some fine gravel; medium dense; dry | 0 | |
| | | | | | | 1.5 - 3.0' FILL: Dark brown coarse to fine SAND, fine gravel; medium dense; dry | 0<br>0.5<br>0.6 | Sample 125-SB-607-W2 from 3.6-5.1 ft bgs @ 1115; EnCore taken from 125-SB-607-W2 @ 1115 |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Black SILT, fine sand; medium dense; moist | 0 | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 4.8' FILL: Reddish-brown/black SILT, some fine gravel; dense; moist | 1.0 | |
| | 5.0 | | | | | 4.8 - 8.0' FILL: Black SILT, fine sand, possible COPR in shoe; medium dense; moist | 1.2<br>1.1<br>1.8<br>0.9<br>1.4<br>1.3 | Sample 125-SB-607-HH1 from 5.1-7.2 ft bgs @ 1120; EnCore taken from 125-SB-607-HH1 @ 1120<br>Sample 125-SB-607-HH2 from 7.2-8.9 ft bgs @ 1125 |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 10.0' FILL: Black SILT, medium dense; moist | | |
| | 10.0 | | | | | | | End of boring at 10 ft bgs. |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 134-MW-03
**DATE BEGAN:** 2-16-16
**DATE FINISHED:** 2-16-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 2' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 27 | 2.0 | | 10.0 - 12.6' SW: Dark brown fine to medium SAND, fine to coarse gravel, trace SILT; dense, wet | NM | Augered to 10' bgs<br>Starting elevation 7.5'<br>GW elevation 5.5' |
| | | | 60 | | | | | |
| | 11.0 | | 67 | | | | | |
| | | | 43 | | | | | Meadow mat expected at elevation -4 (11.5' bgs) |
| | 12.0 | SS2 | 23 | 2.0 | | | | |
| | | | 75 | | | 12.6 - 15.0' SW: Gray fine to coarse SAND, fine to coarse gravel, crushed concrete; dense, wet | | |
| | 13.0 | | 51 | | | | | |
| | | | 95 | | | | | |
| | 14.0 | SS3 | 43 | 1.5 | | | | |
| | | | 94 | | | | | |
| | 15.0 | | 6 | | | 15.0 - 15.5' PT: Dark brown PEAT | | |
| | | | 3 | | | 15.5 - 16.0' No recovery. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 134-MW-04
**DATE BEGAN:** 2-22-16
**DATE FINISHED:** 2-22-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 2' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | SS1 | 22 | 0.5 | | 12.0 - 12.5' SW: Gray fine to coarse SAND, fine to coarse gravel; loose, wet | NM | Augered to 12' bgs<br>Starting elevation 7.0'<br>GW elevation 5.0' |
| | | | 26 | | | 12.5 - 14.0' No recovery | | |
| | 13.0 | | 4 | | | | | |
| | | | 5 | | | | | |
| | 14.0 | SS2 | 4 | 2.0 | | 14.0 - 14.2' OL: Dark gray SILT with organic fibers | | |
| | | | | | | 14.2 - 16.0' PT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | | | 5 | | | | | |
| | 15.0 | | 6 | | | | | |
| | | | 7 | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 134-MW-V09R
**DATE BEGAN:** 2-22-16
**DATE FINISHED:** 2-22-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 18' bgs
**GW DEPTH:** 2.5' bgs
**DRILLER:** Gordon Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 8 | 2.0 | | 14.0 - 15.0' SW: Reddish brown fine SAND, some silt; medium dense, wet | NM | Augered to 14' bgs<br>Starting elevation 8.0'<br>GW elevation 5.5' |
| | | | 11 | | | | | |
| | 15.0 | | 8 | | | 15.0 - 15.7' ML: Reddish brown CLAYEY SILT; wet | | |
| | | | 9 | | | | | |
| | | | | | | 15.7 - 16.4' ML: Black SILT; wet | | |
| | 16.0 | SS2 | 3 | 2.0 | | | | |
| | | | | | | 16.4 - 16.5' ML: Dark gray SILT with fibers | | |
| | | | 5 | | | 16.5 - 18.0' PT: Dark brown PEAT. End of boring at 18.0' bgs. | | |
| | 17.0 | | 9 | | | | | |
| | | | 15 | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 134-SB-001 | **SITE ID:** 134

**DATE BEGAN:** 6/17/2005 | **DATE FINISHED:** 6/17/2005 | **INSPECTOR:** CH

**DRILLING CO:** EPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Bob | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 16.1 ft bgs | **GW DEPTH:** 2 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT: Asphalt | | 0 | |
| | -1.0 | | | | | FILL: Topsoil; Gravel, brick, fill material; some sand; strong hues of green & orange between 1.0-2.0 ft. bgs | | | 134-SB-001_004 collected from 1.5-2.0 ft bgs @1353 |
| | -2.0 | | | | | FILL: Sand, medium - coarse; some gravel; ash, coal, fill material; trace green & orange hues | | | |
| | -3.0 | | | | | | | | |
| | -4.0 | S-2 | | 4 | | FILL: Dark Brown, sand, fine - medium | | 0 | |
| -5.0 | -5.0 | | | | | FILL: Dark Brown, silty | | | |
| | -6.0 | | | | | | | | |
| | -7.0 | | | | | FILL: Ash, green (suspected COPR) | | | |
| | -8.0 | S-3 | | 4 | | FILL: Dark Brown, sand, coarse | | 0 | |
| | -9.0 | | | | | | | | |
| -10.0 | -10.0 | | | | | | | | |
| | -11.0 | | | | | FILL: Reddish brown, silt | | | |
| | -12.0 | S-4 | | 4 | | FILL: Brown, clay | | 0 | |
| | -13.0 | | | | | OH: Dark brown, clay; trace black coloring; organic odor | | | |
| | -14.0 | | | | | | | | |
| -15.0 | -15.0 | | | | | | | | |
| | -16.0 | | | | | PT: Peat | | | 134-SB-001_003 collected from 15.5-16.0 ft bgs @1401 |
| | -17.0 | | | | | End boring @ 16.1' | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 134-SB-002 **SITE ID:** 134

**DATE BEGAN:** 6/17/2005 **DATE FINISHED:** 6/17/2005 **INSPECTOR:** CH

**DRILLING CO:** EPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Bob **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 20 ft bgs **GW DEPTH:** 2 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT: Asphalt | | 0 | |
| | -1.0 | | | | | FILL: Black - dark gray, sand, coarse | | | 134-SB-002_005 collected from 1.5-2.0 ft bgs @1316 |
| | -2.0 | | | | | FILL: Black, sand, coarse | | | 134-SB-002_010 collected from 1.5-2.0 ft bgs @1317 |
| | -3.0 | | | | | FILL: Sandy silt, gravel fragments, medium - fine | | | |
| | -4.0 | S-2 | | 4 | | FILL: Black, clay silt | | 0 | 134-SB-002_006 collected from 3.5-4.0 ft bgs @1322 |
| -5.0 | -5.0 | | | | | FILL: Light-medium green, ash, fill | | | |
| | -6.0 | | | | | FILL: Green tint, gray, ash | | | |
| | -7.0 | | | | | | | | 134-SB-002_007 collected from 6.5-7.0 ft bgs @1328 |
| | -8.0 | S-3 | | 4 | | | | 0 | |
| | -9.0 | | | | | FILL: Brown-green tints, 10R 3/2 | | | |
| -10.0 | -10.0 | | | | | | | | 134-SB-002_008 collected from 10.5-11.0 ft bgs @1333 |
| | -11.0 | | | | | FILL: Brown, silt, 10R 4/3 | | | |
| | -12.0 | S-4 | | 0 | | | | 0 | |
| | -13.0 | | | | | | | | |
| | -14.0 | | | | | | | | |
| -15.0 | -15.0 | | | | | | | | |
| | -16.0 | S-5 | | 2 | | | | 0 | |
| | -17.0 | | | | | | | | |
| | -18.0 | | | | | OH: Black , clay; organic matter, saturated | | | |
| | -19.0 | | | | | | | | |
| -20.0 | -20.0 | | | | | End boring @ 20' | | | 134-SB-002_009 collected from 19.5-20.0 ft bgs @1338 |
| | -21.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-012
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 3.5' FILL: reddish brown silty sand, some fine to medium gravel; dry | 0 | 134-SB-012-0002 from 1.0-1.5' bgs @ 1250 |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | | 0 | 134-SB-012-0204 from 3.0-3.5' bgs @ 1255 |
| | -4.0 | S-2 | N/A | 4.0 | | 3.5 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 8.0' FILL: light brown/reddish brown silty sand; wet | 0 | 134-SB-012-0406 from 4.0-4.5' bgs @ 1300 |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | | 0 | 134-SB-012-0608 from 7.0-7.5' bgs @ 1305 |
| | -8.0 | S-3 | N/A | 4.0 | | 8.0 - 14.5' FILL: light brown/reddish brown sandy silt; wet | 0 | |
| | -9.0 | | | | | | 0 | 134-SB-012-0810 from 8.5-9.0' bgs @ 1310 |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | | 0 | 134-SB-012-1012 from 10.5-11.0' bgs @ 1315 |
| | -12.0 | S-4 | N/A | 4.0 | | | 0 | |
| | -13.0 | | | | | | 0 | 134-SB-012 -1214 from 12.5-13.0' bgs @ 1320 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | 14.5 - 15.5' OL: black silt with trace organic material | 0 | 134-SB-012-1416 from 15.0-15.5' bgs @ 1325 |
| | -16.0 | | | | | 15.5 - 16.0' PT: peat; end of boring at 16' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-013
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Goeprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 17 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' FILL: reddish brown silt, some fine to medium sand, dry | 0 | 134-SB-013-0002 from 1.0-1.5' bgs @ 1030 |
| | -2.0 | | | | | 1.0 - 1.5' FILL: dark brown/black silty sand with shells and wood, dry | 0 | 134-SB-013-0204 from 2.5-3.0' bgs @ 1035 |
| | -3.0 | | | | | 1.5 - 3.0' FILL: reddish brown silty sand; compact, moist | | |
| | -4.0 | S-2 | N/A | 3.75 | | 3.0 - 4.0' No recovery | 0 | 134-SB-013-0406 from 4.5-5.0' bgs @ 1040 |
| | -5.0 | | | | | 4.0 - 7.5' FILL: light brown fine to medium sand with silt lenses; wet from 5' | 0 | |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | 7.5 - 7.8' FILL: fine to medium gravel; wet | 0 | 134-SB-013-0608 from 7.0-7.5' bgs @ 1045 |
| | -8.0 | S-3 | N/A | 3.0 | | 7.8 - 8.0' No recovery | 0 | 134-SB-013-0810 from 8.0-8.5' bgs @ 1050 |
| | -9.0 | | | | | 8.0 - 11.0' FILL: light brown fine to medium sand with silt lenses from 8.0-9.0'; wet | 0 | |
| | -10.0 | | | | | | 0 | 134-SB-013-1012 from 10.0-10.5' bgs @ 1055 |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | S-4 | N/A | 3.75 | | 12.0 - 13.0' FILL: light brown fine to medium sand; wet | 0 | |
| | -13.0 | | | | | 13.0 - 14.8' FILL: brown silty sand; wet | 0 | 134-SB-013-1214 from 13.0-13.5' bgs @ 1100 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | 14.8 - 15.8' FILL: brown silty clay, wet | 0 | 134-SB-013-1416 from 15.0-15.5' bgs @ 1105 |
| | -16.0 | S-5 | N/A | 1.0 | | 15.8 - 16.0' No recovery | 0 | |
| | -17.0 | | | | | 16.0 - 16.3' OL: black organic silt, wet | 0 | |
| | | | | | | 16.3 - 17.0' PT: dark brown peat; moist; end of boring at 17' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-014
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** E. Jackson / T. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | 1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' FILL: Light brown sand (coarse) and gravel (fine-medium), dry | | 134-SB-014_0002 collected from 0.5-1.0' bgs @ 9:45 |
| | -2.0 | | | | | 1.0 - 3.0' FILL: Dark brown silt, trace clay; sand (coarse), gravel and wood from 1.75-2'; firm, moist from 1.75' | | 134-SB-014_0204 collected from 2.5-3.0' bgs @ 9:48 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | 2 | NA | 3.5 | | 4.0 - 4.3' FILL: Dark brown silt, trace sand (coarse), clay, gravel and wood; loose, saturated | 0 | 134-SB-014_0406 collected from 4.5-5.0' bgs @ 9:50 |
| | -5.0 | | | | | 4.3 - 5.0' FILL: Light brown sand (medium-coarse) and gravel (fine), trace silt, saturated | | |
| | -6.0 | | | | | 5.0 - 5.8' FILL: Light brown silt, firm, wet | | 134-SB-014_0608 collected from 7.0-7.5' bgs @ 9:52 |
| | -7.0 | | | | | 5.8 - 6.3' FILL: Dark brown clayey silt, wet | | |
| | -8.0 | 3 | NA | 4.0 | | 6.3 - 7.5' FILL: Brown sand (fine-coarse), wet | 0 | 134-SB-014_0810 collected from 8.0-8.5' bgs @ 9:54 |
| | -9.0 | | | | | 7.5 - 8.0' No recovery | | |
| | -10.0 | | | | | 8.0 - 10.5' FILL: Light brown sand (fine-medium), few clay lenses, saturated | | 134-SB-014_1012 collected from 10.5-11.0' bgs @ 9:56 |
| | -11.0 | | | | | 10.5 - 12.0' FILL: Dark brown clay, saturated | | |
| | -12.0 | 4 | NA | 2.0 | | 12.0 - 13.3' FILL: Light brown sand (fine-medium), saturated | 0 | |
| | -13.0 | | | | | 13.3 - 15.0' FILL: Light brown silty clay with trace sand, saturated | | 134-SB-014_1214 collected from 13.5-14.0' bgs @ 9:58 |
| | -14.0 | 5 | NA | 3.5 | | | 0 | |
| | -15.0 | | | | | 15.0 - 16.0' OL: Black/dark brown clay and silt | | 134-SB-014_1416 collected from 14.5-15.0' bgs @ 10:00, DUP @ 10:02 |
| | -16.0 | | | | | 16.0 - 17.5' PT: Dark brown peat | | |
| | -17.0 | | | | | 17.5 - 18.0' No recovery; end of boring @ 18' | | |
| | -18.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-015
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | | |
| | -1.0 | | | | | 0.5 - 3.0' FILL: reddish brown silt, some fine to medium gravel; olive silt lenses from 2.0'; dry | 0 | 134-SB-015-0002 from 1.0-1.5' bgs @ 1205 |
| | -2.0 | | | | | | 0 | 134-SB-015-0204 from 2.0-2.5' bgs @ 1210 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 3.5 | | 4.0 - 4.5' FILL: reddish brown silt with fine to medium gravel; moist | 0 | |
| | -5.0 | | | | | 4.5 - 7.5' FILL: light brown fine to medium sand; wet from 5' | 0 | 134-SB-015-0406 from 4.5-5.0' bgs @ 1215 |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | | 0 | 134-SB-015-0608 from 7.0-7.5' bgs @ 1220 |
| | -8.0 | | | | | 7.5 - 8.0' No recovery | | |
| | | S-3 | N/A | 3.0 | | 8.0 - 9.5' FILL: light brown fine to medium sand; wet | 0 | 134-SB-015-0810 from 8.0-8.5' bgs @ 1225 |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | 9.5 - 11.0' FILL: light brown silt with fine sand from 10.5'; wet | 0 | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | 134-SB-015-1012 from 10.5-11.0' bgs @ 1230 |
| | -12.0 | S-4 | N/A | 4.0 | | 12.0 - 14.0' FILL: light brown silt with fine sand; wet | 0 | 134-SB-015-1214 from 12.0-12.5' bgs @ 1235 |
| | -13.0 | | | | | | 0 | |
| | -14.0 | | | | | 14.0 - 15.5' OL: black silt with organic material from 15', wet | 0 | |
| | -15.0 | | | | | 15.5 - 16.0' PT: dark brown peat; moist; end of boring at 16' | 0 | 134-SB-015-1416 from 15.0-15.5' bgs @ 1240 |
| | -16.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-016
**DATE BEGAN:** 8/1/08
**DATE FINISHED:** 8/1/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' FILL: DGA | 0 | 134-SB-016-0002 from 1.0-1.5' bgs @ 1350 |
| | -2.0 | | | | | 1.0 - 1.5' FILL: reddish brown silty sand, trace coarse gravel | 0 | |
| | -3.0 | | | | | 1.5 - 2.0' FILL: black silty sand, trace coal and coarse gravel; dry | 0 | 134-SB-016-0204 from 3.0-3.5' bgs @ 1355 |
| | -4.0 | S-2 | N/A | 3.5 | | 2.0 - 3.5' FILL: reddish brown silty sand, trace coarse gravel; dry | 0 | |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | 0 | 134-SB-016-0406 from 4.5-5.0' bgs @ 1400 |
| | -6.0 | | | | | 4.0 - 4.5' FILL: reddish brown silty sand, trace coarse gravel; moist | 0 | |
| | -7.0 | | | | | 4.5 - 6.5' FILL: brown silt, coarse sand, coarse gravel, lenses of red-brown silt; wet | 0 | 134-SB-016-0608 from 7.0-7.5' bgs @ 1405 |
| | -8.0 | S-3 | N/A | 4.0 | | 6.5 - 7.5' FILL: grey coarse sand, reddish brown silt lenses; wet | 0 | |
| | -9.0 | | | | | 7.5 - 8.0' No recovery | 0 | 134-SB-016-0810 from 8.5-9.0' bgs @ 1410 |
| | -10.0 | | | | | 8.0 - 9.0' FILL: grey coarse sand, reddish brown silt lenses; wet | 0 | |
| | -11.0 | | | | | 9.0 - 14.0' FILL: brown silty clay; wet | 0 | 134-SB-016-1012 from 10.5-11.0' bgs @ 1415 |
| | -12.0 | S-4 | N/A | 3.1 | | | 0 | |
| | -13.0 | | | | | | 0 | 134-SB-016-1214 from 12.5-13.0' bgs @ 1420 |
| | -14.0 | | | | | 14.0 - 15.0' OL: black silty organic material; wet | 0 | 134-SB-016-1416 from 14.0-14.5' bgs @ 1425; DUP @ 1427 |
| | -15.0 | | | | | 15.0 - 15.1' PT: peat; moist | 0 | |
| | -16.0 | | | | | 15.1 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-016R
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: gravel | NA | |
| | 1.0 | | | | | 0.3 - 1.5' FILL: Red silt; moist, firm | | |
| | 2.0 | | | | | 1.5 - 2.3' FILL: Dark grey fine sand, some silt, ash, and coal; moist, loose | | |
| | 3.0 | | | | | 2.3 - 2.5' FILL: Reddish brown clay, some silt; moist, very firm | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.5 - 3.5' FILL: Light brown fine sand, some silt, some lenses of light brown silty clay; moist, loose | NA | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 6.5' SP: Light brown fine sand, some silt, some lenses of light brown silty clay; moist, loose | | |
| | 7.0 | | | | | 6.5 - 8.0' SP: Greenish brown fine sand, some silt, some lenses of light brown silty clay; moist, loose | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 10.5' SP: Greyish brown fine to medium sand, trace shells; wet, loose | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' ML: Brown silt; wet, soft | | |
| | 12.0 | S-4 | NA | 4.0 | | 11.5 - 12.0' SW: Greyish brown fine sand, some silt, trace shells; moist, loose | NA | |
| | 13.0 | | | | | 12.0 - 16.0' SW: Greyish brown fine to medium sand, some silt, trace shells; wet, loose; end of boring @ 16.0' bgs | | |
| | 14.0 | | | | | | | Sample collected 134-SB-016R-1416 from14.5 - 15.0' bgs @ 934 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-017
**DATE BEGAN:** 6/18/08
**DATE FINISHED:** 6/18/08
**INSPECTOR:** E. Jackson/T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | 134-SB-017_0002 collected from 1.0-1.5' bgs @ 10:05 |
| | | | | | | 0.5 - 1.0' FILL: Concrete | | |
| | -1.0 | | | | | 1.0 - 2.5' FILL: Light brown sand (fine-coarse), some gravel, dry | | |
| | -2.0 | | | | | | 45 | 134-SB-017_0204 collected from 2.5-3.0' bgs @ 10:07 |
| | | | | | | 2.5 - 3.0' FILL: Black sand (medium-coarse), some gravel and ash, dry | | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 5.5' FILL: Light tan silty sand (fine-medium), trace gravel, dry | 35 | 134-SB-017_0406 collected from 5.0-5.5' bgs @ 10:10 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 5.5 - 7.0' FILL: Tan sand (fine-coarse), trace gravel, moist | 40 | 134-SB-017_0608 collected from 6.5-7.0' bgs @ 10:12 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Light grey sand (fine-coarse), saturated | 25 | 134-SB-017_0810 collected from 8.5-9.0' bgs @ 10:15, DUP @ 10:15 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | 22 | 134-SB-017_1012 collected from 11.0-11.5' bgs @ 10:20 |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | NA | 4.0 | | | 1.5 | 134-SB-017_1214 collected |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-017
**DATE BEGAN:** 6/18/08
**DATE FINISHED:** 6/18/08
**INSPECTOR:** E. Jackson/T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | | | |
| | | | | | | 12.0 - 14.0' FILL: Brown silty sand (fine-medium), saturated | | from 12.5-13.0' bgs @ 10:22 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 15.5' FILL: Brown silty sand (fine), saturated | 0.5 | 134-SB-017_1416 collected from 15.0-15.5' bgs @ 10:30 |
| | -15.0 | | | | | 15.5 - 16.0' FILL: Brown silty sand (fine-coarse), wet | | |
| | -16.0 | S-5 | NA | 4.0 | | 16.0 - 17.5' FILL: Brown sand (fine), some silt and clay, wet | | 134-SB-017_1618 collected from 16.0-16.5' bgs @ 10:33 |
| | -17.0 | | | | | | | |
| | | | | | | 17.5 - 18.0' FILL: Tan silty clay, wet | | |
| | -18.0 | | | | | 18.0 - 19.5' PT: Brown peat, wet | | 134-SB-017_1820 collected from 18.5-19.0' bgs @ 10:35 |
| | -19.0 | | | | | | | Driller grouted boring |
| | | | | | | 19.5 - 20.0' SW: Dark brown sand (medium-coarse), wet; end of boring at 20' | | |
| | -20.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-018
**DATE BEGAN:** 6/18/08
**DATE FINISHED:** 6/18/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 2.8' FILL: Reddish brown silty sand (fine-coarse) and trace angular gravel, dry | | 134_SB-018_0002 collected from 1.0-1.5' bgs @ 11:50 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.8 - 3.3' FILL: Red/dark brown silty clay, firm, low plasticity, dry | | |
| | | | | | | 3.3 - 3.5' FILL: Brown sand (medium-coarse), moist | | 134_SB-018_0204 collected from 3.5-4.0' bgs @ 11:53 |
| ▽ | -4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 6.0' FILL: Brown sand (fine-medium, trace coarse), wet | | 134_SB-018_0406 collected from 5.0-5.5' bgs @ 11:55 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | 6.0 - 7.3' FILL: Brown sand (medium-coarse), clay lens from 6.0-6.25', wet | | |
| | -8.0 | S-3 | NA | 4.0 | | 7.3 - 8.0' FILL: Brown silty sand, wet | | 134_SB-018_0608 collected from 7.5-8.0' bgs @ 11:58 |
| | -9.0 | | | | | 8.0 - 12.0' FILL: Brown sand (medium-coarse), brick at 9', clay from 11-11.25', wet | 0 | 134_SB-018_0810 collected from 9.0-9.5' bgs @ 12:04 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 134_SB-018_1012 collected from 11.5-12.0' bgs @ 12:08 |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-018
**DATE BEGAN:** 6/18/08
**DATE FINISHED:** 6/18/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | | | |
| | -13.0 | | | | | 12.0 - 14.5' FILL: Brown sand (fine-medium), saturated | | 134_SB-018_1214 collected from 12.0-12.5' bgs @ 12:19, DUP @ 12:21 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 14.5 - 16.0' CH: Brown clay, plastic, saturated | | 134_SB-018_1416 collected from 15.0-15.5' bgs @ 12:23 |
| | -16.0 | S-5 | NA | 4.0 | | 16.0 - 16.5' OH: Dark brown/black clay with organic odor, saturated, plastic | 0 | |
| | -17.0 | | | | | 16.5 - 19.5' PT: Peat | | 134_SB-018_1618 collected from 16.0-16.5' bgs @ 12:36 |
| | -18.0 | | | | | | | 134_SB-018_1820 collected from 18.5-19.0' bgs @ 12:41 |
| | -19.0 | | | | | | | |
| | -20.0 | | | | | 19.5 - 20.0' CL: Dark brown silty clay, trace sand; end of boring at 20' | | Driller grouted boring |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-019
**DATE BEGAN:** 6/18/08
**DATE FINISHED:** 6/18/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Red brown silty sand (fine-medium) | | |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Light yellow sand (medium-coarse), trace silt and angular gravel, dry | | 134-SB-019_0002 collected from 1.5-2.0' bgs @ 9:08 |
| | -3.0 | | | | | 2.0 - 2.8' FILL: Dark brown sand (coarse) and gravel (fine), trace silt, dry | | 134-SB-019_0204 collected from 2.5-3.0' bgs @ 9:02 |
| | | | | | | 2.8 - 3.0' FILL: Brown/dark brown clayey silt | | |
| | -4.0 | S-2 | NA | 4.0 | | 3.0 - 4.0' No recovery | 0 | 134-SB-019_0406 collected from 4.0-4.5' bgs @ 9:11 |
| | -5.0 | | | | | 4.0 - 4.8' FILL: Dark brown sand (medium-coarse), gravel (fine); moist | | |
| | -6.0 | | | | | 4.8 - 7.0' FILL: Brown/dark brown silty clay; moist from 4.75', wet from 5.5' | | 134-SB-019_0608 collected from 6.0-6.5' bgs @ 9:13 |
| | -7.0 | | | | | 7.0 - 8.8' FILL: Brown sand (fine-coarse), wet | | |
| | -8.0 | S-3 | NA | 4.0 | | | 0 | |
| | -9.0 | | | | | 8.8 - 11.5' FILL: Brown sandy (fine-medium) silt, trace clay, clay layer from 8.75-9'; wet | | 134-SB-019_0810 collected from 9.0-9.5' bgs @ 9:15 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 134-SB-019_1012 collected from 11.5-12.0' bgs @ 9:18 |
| | -12.0 | S-4 | NA | 4.0 | | 11.5 - 12.0' FILL: Brown sand (fine) and silt, wet | 0 | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-019
**DATE BEGAN:** 6/18/08
**DATE FINISHED:** 6/18/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | | | |
| | | | | | | 12.0 - 13.0' FILL: Brown sand (fine) and silt, wet | | 134-SB-019_1214 collected from 12.0-12.5' bgs @ 9:20 |
| | -13.0 | | | | | 13.0 - 15.0' FILL: Brown silty clay, wet | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.0 - 16.0' FILL: Brown sand (fine) and silt, wet | | 134-SB-019_1416 collected from 15.0-15.5' bgs @ 9:25 |
| | -16.0 | S-5 | NA | 4.0 | | 16.0 - 18.0' CH: Brown clay, firm, high plasticity | 0 | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | 18.0 - 19.9' PT: Peat and clay; end of boring at 20' | | |
| | -19.0 | | | | | | | Driller grouted boring |
| | | | | | | 19.9 - 20.0' SM: Brown sand (fine-medium) in tip; | | |
| | -20.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-021
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 2.0' ASPHALT: Asphalt and concrete | | Driller cored through asphalt and concrete pad |
| | -1.0 | | | | | | | |
| | -2.0 | S-1 | NA | 1.5 | | 2.0 - 3.5' FILL: Dark brown silty sand (fine) and gravel (fine-medium) | 0 | 134-SB-021_0204 collected from 2.5-3.0' bgs @ 12:10 |
| | -3.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 5.0' FILL: Dark brown silty sand (fine) and gravel (fine-medium), very moist | 0 | 134-SB-021_0406 collected from 4.5-5.0' bgs @ 12:15 |
| | -5.0 | | | | | 5.0 - 5.5' FILL: Light brown silt, wet | | |
| | -6.0 | | | | | 5.5 - 7.5' FILL: Light brown sand (fine-medium), trace silt, wet | | |
| | -7.0 | | | | | 7.5 - 8.0' No recovery | | 134-SB-021_0608 collected from 7.0-7.5' bgs @ 12:20 |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 9.0' FILL: Light brown silt, some sand (fine) | 0 | 134-SB-021_0810 collected from 8.0-8.5' bgs @ 12:25 |
| | -9.0 | | | | | 9.0 - 11.0' FILL: Light brown sand (fine), trace silt | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | 134-SB-021_1012 collected from 10.5-11.0' bgs @ 12:30 |
| | -12.0 | S-4 | NA | 3.5 | | 12.0 - 12.8' FILL: Light brown clayey silt, saturated | 0 | |
| | -13.0 | | | | | 12.8 - 13.8' ML: Light brown/olive silt, some fine organic material from 13.5' | | 134-SB-021_1214 collected from 13.0-13.5' bgs @ 12:35 |
| | -14.0 | | | | | 13.8 - 15.5' OL: Black silt, some fine organic material | | 134-SB-021_1416 collected from 15.0-15.5' bgs @ 12:40 |
| | -15.0 | | | | | 15.5 - 16.0' No recovery | | |
| | -16.0 | S-5 | NA | 1.0 | | 16.0 - 16.8' ML: Olive/light brown silt, trace fine organic material | 0 | 134-SB-021_1618 collected from 16.0-16.5' bgs @ 12:45 |
| | -17.0 | | | | | 16.8 - 17.0' PT: Dark brown peat; end of boring at 17' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-022
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' FILL: Red brown silt and clay; tight, dry. | | 134-SB-022_0002 collected from 0.5-1.0' bgs @ 7:59 |
| | -2.0 | | | | | 1.0 - 2.5' FILL: Dark brown silty sand, trace wood and clay; dry. | | 134-SB-022_0204 collected from 2.0-2.5' bgs @ 8:02 |
| | -3.0 | | | | | 2.5 - 3.0' FILL: Light brown sand (coarse), clay lens at 2.6'; dry | | |
| | -4.0 | S-2 | NA | 3.5 | | 3.0 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 7.5' FILL: Brown sand (fine-coarse), trace clay from 4.0-6.0'; saturated from 5' | | 134-SB-022_0406 collected from 4.5-5.0' bgs @ 8:05 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | 134-SB-022_0608 collected from 7.0-7.5' bgs @ 8:07 |
| | -8.0 | S-3 | NA | 3.5 | | 7.5 - 8.0' No recovery | 0 | 134-SB-022_0810 collected from 8.0-8.5' bgs @ 8:10 |
| | -9.0 | | | | | 8.0 - 9.0' OH: Dark brown/black silty clay; high plasticity, wet; | | |
| | -10.0 | | | | | 9.0 - 10.0' PT: Peat | | |
| | -11.0 | | | | | 10.0 - 11.0' OL: Dark brown/black silty clay, wet | | |
| | -12.0 | | | | | 11.0 - 11.5' OL: Dark brown/black silt, trace clay, wet | | Driller grouted boring |
| | | | | | | 11.5 - 12.0' No recovery; end of boring at 12' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-022A
**DATE BEGAN:** 8/8/08
**DATE FINISHED:** 8/8/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: reddish brown silt; stiff; dry | | |
| | -1.0 | | | | | 1.0 - 1.5' FILL: dark brown sandy silt with fine to medium gravel, fine glass; dry | 0 | |
| | -2.0 | | | | | 1.5 - 3.0' FILL: light brown fine to medium sand, lenses of reddish brown silt from 2.5'; dry | 0 | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 3.0 | | 4.0 - 7.0' FILL: light brown fine to medium sand, fine gravel from 5.0'; wet from 4.5' | 0 | 134-SB-22A-0406 fro SVOCs and metals from 4.0-4.5' bgs @ 1400 |
| | -5.0 | | | | | | 0 | |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | S-3 | N/A | 2.5 | | 8.0 - 8.3' ML: black clayey silt, wet | 0 | |
| | | | | | | 8.3 - 9.0' PT: dark brown peat; moist | | |
| | -9.0 | | | | | 9.0 - 10.0' ML: black clayey silt; moist | 0 | |
| | -10.0 | | | | | 10.0 - 10.5' ML: light brown clayey silt; moist | 0 | 134-SB-22A-1012 from 10.0-10.5' bgs @ 1410 |
| | | | | | | 10.5 - 12.0' No recovery; end of boring at 12' | | |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-023
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Dark brown silt; firm, moist | | 134-SB-023_0002 collected from 1.0-1.5' bgs @ 8:55 |
| | -2.0 | | | | | 1.5 - 3.0' FILL: Dark brown sand (medium-coarse), some coal, gravel, brick and slate; moist | | 134-SB-023_0204 collected from 2.5-3.0' bgs @ 8:58 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Dark brown sand (medium-coarse), some coal, gravel, brick and slate; wet | 0<br>20 | 134-SB-023_0406 collected from 4.0-4.5' bgs @ 9:01 |
| | -5.0 | | | | | 4.5 - 5.5' FILL: Brown silty clay; wet | 24<br>25 | |
| | -6.0 | | | | | 5.5 - 7.5' FILL: Brown sand (fine-coarse), wet | | 134-SB-023_0608 collected from 6.5-7.0' bgs @ 9:04 |
| | -7.0 | | | | | 7.5 - 8.0' No recovery | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Brown sand (fine-medium), trace clay from 8.0-8.25' and 9.75-10.0'; saturated | 0 | 134-SB-023_0810 collected from 8.5-9.0' bgs @ 9:08 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 134-SB-023_1012 collected from 11.0-11.5' bgs @ 9:11 |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 12.5' FILL: Dark brown silt and sand (fine), saturated | 0 | 134-SB-023_1214 collected from 12.0-12.5' bgs @ 9:23 |
| | -13.0 | | | | | 12.5 - 15.0' FILL: Brown clay, saturated | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.0 - 15.5' FILL: Yellow brown clay, moist | | |
| | -16.0 | S-5 | NA | 2.0 | | 15.5 - 16.0' FILL: Silty clay, organic odor; moist | 0 | 134-SB-023_1416 collected from 15.5-16.0' bgs @ 9:25 |
| | -17.0 | | | | | 16.0 - 18.0' PT: Peat; end of boring at 18' | | |
| | -18.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-024
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17.5 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 4.0 | S-1 | NA | 2.5 | | -4.5 - -4.0' CONCRETE | | Boring located in elevated trucking bay, approximately 4.5' above ground surface. Depth intervals in sample IDs are from top of boring, rather than depth above or below ground surface (see sampling notes below). Driller cored through concrete before drilling. |
| | | | | | | -4.0 - -1.5' FILL: Brown silty sand (fine) and gravel (fine-coarse) | 0 | 134-SB-024_0002 collected from 3.5-3.0' ags @ 9:00 |
| | 3.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | | | | | | -1.5 - -0.5' No recovery | | 134-SB-024_0204 collected from 2.5-2.0' ags @ 9:05 |
| | 1.0 | | | | | -0.5 - 0.0' FILL: Light brown silty sand (fine) and gravel (fine-medium) | | |
| | 0.0 | S-2 | NA | 3.0 | | 0.0 - 1.5' FILL: Black silty sand (fine) with yellow green precipitates (COPR), moist from 5' | 0 | 134-SB-024_0406 collected from 0.5-1.0' bgs @ 9:10 |
| | -1.0 | | | | | | | |
| | | | | | | 1.5 - 2.5' FILL: Wood; creosote odor | | |
| | -2.0 | | | | | | | |
| | | | | | | 2.5 - 3.5' No recovery | | |
| | -3.0 | S-3 | NA | 3.0 | | | | |
| | | | | | | 3.5 - 4.5' FILL: Light brown silt with sand (fine-medium), wet from 4.25' | 0 | |
| ▽ | -4.0 | | | | | | | 134-SB-024_0810 collected from 4.0-4.5' bgs @ 9:15 |
| | | | | | | 4.5 - 5.0' FILL: Dark brown clayey silt, saturated | | |
| | -5.0 | | | | | 5.0 - 6.5' FILL: Light brown sand (fine-medium) with trace silt, wet | | |
| | -6.0 | | | | | | | |
| | | | | | | 6.5 - 7.5' No recovery | | |
| | -7.0 | S-4 | NA | 3.5 | | | 0 | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-024
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17.5 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -8.0 | | | | | 7.5 - 9.5' FILL: Light brown sand (fine-medium) with trace silt, wet | | |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 9.5 - 10.5' FILL: Light brown clayey silt, wet | | 134-SB-024_1012 collected from 6.0-6.5' bgs @ 9:20 |
| | -11.0 | | | | | 10.5 - 11.0' FILL: Light brown silt, saturated | | |
| | | | | | | 11.0 - 11.5' No recovery | | |
| | | S-5 | NA | 3.5 | | 11.5 - 12.5' FILL: Light brown clayey silt; saturated | 0 | |
| | -12.0 | | | | | 12.5 - 12.8' FILL: Light brown/grey silt with trace sand (fine); wet | | 134-SB-024_1214 collected from 7.5-8.0' bgs @ 9:25; DUP @ 9:27 |
| | -13.0 | | | | | 12.8 - 14.5' OL: Dark brown/black silt with fine organic material; wet | | |
| | -14.0 | | | | | | | 134-SB-024_1416 collected from 10.5-11.0' bgs @ 9:30 |
| | | | | | | 14.5 - 15.0' OL: Light brown silt with trace fine organic material; wet | | |
| | -15.0 | | | | | 15.0 - 15.5' No recovery | | |
| | | S-6 | NA | 2.0 | | 15.5 - 16.3' OL: Light brown/olive silt with organic material; wet | 0 | |
| | -16.0 | | | | | | | 134-SB-024_1618 collected from 12.5-13.0' bgs @ 9:35 |
| | | | | | | 16.3 - 17.0' PT: Dark brown peat; wet | | |
| | -17.0 | | | | | 17.0 - 17.5' SP: Light brown sand (fine) with trace silt; end of boring at 17.5' bgs | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-025
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 1.8' FILL: Red brown silty sand (fine), crushed concrete and brick, dry | | 134-SB-025_0002 collected from 1.0-1.5' bgs @ 13:00 |
| | -2.0 | | | | | 1.8 - 2.3' FILL: Light brown sand (fine-medium), dry | | |
| | | | | | | 2.3 - 3.0' FILL: Red brown silt and gravel (coarse), dry | | |
| | -3.0 | | | | | 3.0 - 3.5' FILL: Light brown sand (fine-medium), dry | | 134-SB-025_0204 collected from 3.0-3.5' bgs @ 13:05 |
| | -4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 8.0' FILL: Light brown sand (fine-medium) with lenses of red brown silt; wet at 5' | | 134-SB-025_0406 collected from 4.5-5.0' bgs @ 13:10 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | 134-SB-025_0608 collected from 7.0-7.5' bgs @ 13:15 |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown sand (fine-medium), trace gravel from 9.5-11.0'; saturated | 0 | |
| | -9.0 | | | | | | | 134-SB-025_0810 collected from 8.5-9.0' bgs @ 13:20 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 134-SB-025_1012 collected from 10.5-11.0' bgs @ 13:25 |
| | | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | 134-SB-025_1214 collected |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-025
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | 12.0 - 14.0' FILL: Light/red brown silt, wet | | from 12.0-12.5' bgs @ 13:30 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 15.9' FILL: Light brown silt with trace clay lenses; soft, saturated | | |
| | -15.0 | | | | | | | 134-SB-025_1416 collected from 15.0-15.5' bgs @ 13:35 |
| | -16.0 | S-5 | NA | 3.5 | | 15.9 - 16.8' PT: Dark brown peat | 0 | |
| | -17.0 | | | | | 16.8 - 17.5' SP: Light brown sand (fine), trace silt, some organic material; wet | | 134-SB-025_1618 collected from 16.5-17.0' bgs @ 13:40 |
| | -18.0 | | | | | 17.5 - 19.5' SP: Olive sand (fine-medium), trace fine organic material and silt, saturated | | 134-SB-025_1820 collected from 18.5-19.0' bgs @ 13:45 |
| | -19.0 | | | | | | | |
| | -20.0 | | | | | 19.5 - 20.0' No recovery; end of boring at 20' | | Driller grouted boring |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-026
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.5 - 2.8' FILL: Dark brown silty sand (fine) and gravel (fine), dry | | 134-SB-026_0002 collected from 1.0-1.5' bgs @ 14:05 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.8 - 3.5' FILL: Light brown sand (fine-medium) some crushed concrete and brick, dry | | 134-SB-026_0204 collected from 3.0-3.5' bgs @ 14:10 |
| | -4.0 | S-2 | NA | 3.5 | | 3.5 - 4.0' No recovery | 0 | 134-SB-026_0406 collected from 4.0-4.5' bgs @ 14:15 |
| | -5.0 | | | | | 4.0 - 4.8' FILL: Dark brown silty sand (fine) and gravel (fine-medium), trace organics, moist | | |
| | -6.0 | | | | | 4.8 - 6.0' FILL: Light brown silty sand (fine), wet | | 134-SB-026_0608 collected from 6.0-6.5' bgs @ 14:20; DUP @ 14:25 |
| | -7.0 | | | | | 6.0 - 7.5' FILL: Light brown sand (fine-medium), trace silt lenses; wet | | |
| | -8.0 | S-3 | NA | 3.0 | | 7.5 - 8.0' No recovery | 0 | 134-SB-026_0810 collected from 8.0-8.5' bgs @ 14:30 |
| | -9.0 | | | | | 8.0 - 11.0' FILL: Light brown sand (fine), saturated | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | 134-SB-026_1012 collected from 10.5-11.0' bgs @ 14:35; DUP @14:40 |
| | -12.0 | S-4 | NA | 3.5 | | 12.0 - 13.0' FILL: Light brown sand (fine), saturated | 0 | 134-SB-026_1214 collected from 12.5-13.0' bgs @ 14:45 |
| | -13.0 | | | | | 13.0 - 14.3' FILL: Light brown silt with clay lenses, saturated | | |
| | -14.0 | | | | | 14.3 - 15.3' OL: Black clayey silt, wet | | 134-SB-026_1416 collected from 14.5-15.0' bgs @ 14:50 |
| | -15.0 | | | | | 15.3 - 15.5' PT: Dark brown peat, wet | | |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-027
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 2.5' FILL: Dark brown silt, firm with trace coal, brick, concrete, gravel (angular, fine), red brown from 1.75-2.0', dry | | 134-SB-027_0002 collected from 1.0-1.5' bgs @ 13:00 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.5 - 3.0' FILL: Brown clayey sand (fine), some gravel, yellow green staining at 3.25', dry | | 134-SB-027_0204 collected from 2.5-3.0' bgs @ 13:03 |
| | -4.0 | S-2 | NA | 4.0 | | 3.0 - 3.5' FILL: Dark brown gravelly sand, moist | 0 | |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | | 134-SB-027_0406 collected from 5.0-5.5' bgs @ 13:08 |
| | -6.0 | | | | | 4.0 - 4.5' FILL: Dark brown gravelly sand, saturated | | |
| | -7.0 | | | | | 4.5 - 4.8' FILL: Brown clay, wet | | 134-SB-027_0810 collected from 7.0-7.5' bgs @ 13:10 |
| | -8.0 | S-3 | NA | 4.0 | | 4.8 - 9.5' FILL: Brown/light brown sand (fine-medium), trace sand (coarse) from 4.75-8.0'; wet | 0 | |
| | -9.0 | | | | | | | 134-SB-027_0810 collected from 8.5-9.0' bgs @ 13:16 |
| | -10.0 | | | | | 9.5 - 10.5' FILL: Brown silty clay, trace sand, saturated | | |
| | -11.0 | | | | | 10.5 - 11.0' FILL: Brown/dark brown sand (fine-medium) | | 134-SB-027_1012 collected from 10.5-11.0' bgs @ 13:20 |
| | -12.0 | S-4 | NA | 4.0 | | 11.0 - 12.0' FILL: Dark brown clay, silt in tip; soft, wet | 0 | |
| | -13.0 | | | | | 12.0 - 13.5' FILL: Brown/light brown sand (fine), saturated | | 134-SB-027_1214 collected from 13.0-13.5' bgs @ 13:26 |
| | -14.0 | | | | | 13.5 - 14.5' FILL: Brown silty clay, trace sand; wet | | |
| | -15.0 | | | | | 14.5 - 16.0' OL: Dark brown/black silty clay, trace organic material | | 134-SB-027_1416 collected from 15.0-15.5' bgs @ 13:30 |
| | -16.0 | S-5 | NA | 1.0 | | 16.0 - 17.0' PT: Peat; end of boring at 17' | 0 | |
| | -17.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-028
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | 134-SB-028_0002 collected from 1.0-1.5' bgs @ 7:50 |
| | -1.0 | | | | | 0.5 - 3.3' FILL: Dark brown silty sand, some gravel (fine-coarse); moist from 2.5' | | |
| | -2.0 | | | | | | | 134-SB-028_0204 collected from 2.5-3.0' bgs @ 7:55 |
| | -3.0 | | | | | 3.3 - 3.5' FILL: Red brown silty sand (fine) with gravel (fine-medium), moist | | |
| | | | | | | 3.5 - 4.0' FILL: No recovery | | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Red brown silty sand (fine) with gravel (fine-medium), moist | 0 | 134-SB-028_0406 collected from 4.5-5.0' bgs @ 8:00 |
| ▽ | -5.0 | | | | | 4.5 - 5.0' FILL: Dark grey silty sand (fine) with gravel (fine-medium), moist | | |
| | | | | | | 5.0 - 5.8' FILL: Light brown silt, very firm, wet | | |
| | -6.0 | | | | | 5.8 - 7.0' FILL: Dark brown silty sand (fine), wet | | 134-SB-028_0608 collected from 7.0-7.5' bgs @ 8:05 |
| | -7.0 | | | | | 7.0 - 7.5' FILL: Light brown sand (fine-medium) with lenses of silt, wet | | |
| | | | | | | 7.5 - 8.0' FILL: No recovery | | |
| | -8.0 | S-3 | NA | 3.5 | | 8.0 - 11.5' FILL: Light brown sand (fine-medium) with few silt lenses, saturated | 0 | 134-SB-028_0810 collected from 8.5-9.0' bgs @ 8:10 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | 134-SB-028_1012 collected from 10.5-11.0' bgs @ 8:15 |
| | -11.0 | | | | | | | |
| | | | | | | 11.5 - 12.0' FILL: No recovery | | |
| | -12.0 | S-4 | NA | 3.5 | | | 0 | 134-SB-028_1214 collected |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-028
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | 12.0 - 12.5' FILL: Light brown silt, saturated | | from 12.5-13.0' bgs @ 8:20 |
| | -13.0 | | | | | 12.5 - 13.0' FILL: Olive/ yellow silt (COPR), wet | | |
| | | | | | | 13.0 - 13.8' OL: Light brown silt with organic material, wet | | |
| | -14.0 | | | | | 13.8 - 15.0' OL: Black silt with trace clay and organic material, wet | | 134-SB-028_1416 collected from 14.5-15.0' bgs @ 8:25 |
| | -15.0 | | | | | 15.0 - 15.5' OL: Light brown silt with trace organic material, wet | | |
| | | | | | | 15.5 - 16.0' No recovery | | |
| | -16.0 | S-5 | NA | 1.75 | | 16.0 - 17.3' OL: Light brown clayey silt with organic material, wet | 0 | 134-SB-028_1618 collected from 16.0-16.5' bgs @ 8:30; DUP @ 8:35 |
| | -17.0 | | | | | 17.3 - 17.8' PT: Dark brown peat | | |
| | -18.0 | | | | | 17.8 - 18.0' No recovery; end of boring at 18' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-029
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | 134-SB-029_0002 collected form 1.0-1.5' bgs @ 8:50 |
| | -1.0 | | | | | 1.0 - 2.0' FILL: Red/light brown silty sand (fine), dry | | |
| | -2.0 | | | | | 2.0 - 2.3' FILL: Red brown silt with some gravel (fine-medium), moist | | 134-SB-029_0204 collected from 2.5-3.0' bgs @ 8:55 |
| | -3.0 | | | | | 2.3 - 3.0' FILL: Olive sand (fine-medium), moist | | |
| | -4.0 | S-2 | NA | 4.0 | | 3.0 - 4.0' No recovery | 0 | 134-SB-029_0406 collected from 4.0-4.5' bgs @ 9:00 |
| | -5.0 | | | | | 4.0 - 8.0' FILL: Light brown sand (fine-medium), some silt lenses; wet from 5.5', saturated from 7.0' | | |
| | -6.0 | | | | | | | 134-SB-029_0608 collected from 7.0-7.5' bgs @ 9:05 |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 3.5 | | 8.0 - 9.8' FILL: Light brown/black clayey silt, wet | 0 | 134-SB-029_0810 collected from 9.0-9.5' bgs @ 9:10 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 9.8 - 11.5' FILL: Light brown sand (fine-medium) with lenses of red brown silt, wet | | 134-SB-029_1012 collected rom 11.0-11.5' bgs @ 9:15 |
| | -11.0 | | | | | 11.5 - 12.0' No recovery | | |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 12.5' FILL: Light brown silt, trace sand (fine); wet | 0 | 134-SB-029_1214 collected from 12.5-13.0' bgs @ 9:20 |
| | -13.0 | | | | | 12.5 - 15.0' OL: Black clayey silt, some organic material, more organic material from 14-15'; wet | | |
| | -14.0 | | | | | | | 134-SB-029_1416 collected from 15.0-15.5' bgs @ 9:25 |
| | -15.0 | | | | | 15.0 - 15.5' ML: Light brown clayey silt with some organic material, wet | | |
| | -16.0 | | | | | 15.5 - 16.0' PT: Dark brown peat; end of boring at 16' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-030
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Dark brown sand (coarse), silt, and gravel with red/yellow brown mottling, dry | | Collect 134-SB-030_0002 from 1.0-1.5' bgs @ 14:10 |
| | -2.0 | | | | | 1.5 - 1.8' FILL: Gravel, sand (coarse) and concrete, dry | | Hydrocarbon odor from 1.8-2.5' bgs |
| | -3.0 | | | | | 1.8 - 2.5' FILL: Black sand (coarse) and gravel (fine-medium), some ash and coal; moist | | Collect 134-SB-030_0204 from 2.0-2.5' bgs @ 14:13 |
| | -4.0 | S-2 | NA | 4.0 | | 2.5 - 3.0' FILL: Red brown silty sand, trace gravel; moist | 0 | Collect 134-SB-030_0406 from 4.0-4.5' bgs @ 14:15 |
| | | | | | | 3.0 - 3.5' FILL: Brown silt, trace wood; moist | | |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | | | | | 4.0 - 5.3' FILL: Silty clay, trace gravel; wet | | |
| | -6.0 | | | | | 5.3 - 8.0' FILL: Sand (fine-medium), trace clay; wet | | |
| | -7.0 | | | | | | | Collect 134-SB-030_0608 from 7.0-7.5' bgs @ 14:17; DUP @ 14:19 |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 10.5' FILL: Brown sand (fine-medium), trace clay, more clay from 8.75-9.0'; saturated | 0 | |
| | -9.0 | | | | | | | Collect 134-SB-030_0810 from 8.5-9.0' bgs @ 14:25 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 10.5 - 12.0' CL: Brown silty clay; saturated, organic odor. | | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | Collect 134-SB-030_1012 from 11.5-12.0' bgs @ 14:27 |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-030
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | 12.0 - 14.0' CL: Light brown/brown silty clay, wet | | Collect 134-SB-030_1214 from 12.5-13.0' bgs @ 14:40 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 15.0' CL: Dark brown/black silty clay, wet | | |
| | -15.0 | | | | | 15.0 - 15.9' CL: Brown clay, trace organic material, wet | | Collect 134-SB-030_1416 from 15.5-16.0' bgs @ 14:45 |
| | -16.0 | | | | | 15.9 - 16.0' PT: Peat in tip; end of boring at 16' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-031
**DATE BEGAN:** 6/20/08
**DATE FINISHED:** 6/20/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' FILL: Brown/light grey sand (fine-coarse), some brick and cinder; dry | 0 | Collect sample from 1.0-1.5 ft bgs @ 9:45 |
| | -1.0 | | | | | 0.5 - 5.0' FILL: Dark/light grey silty sand (fine); dry from 0.5-4'; moist from 4' | | |
| | -2.0 | | | | | | | Collect sample from 2.5-3.0 ft bgs @ 9:50 |
| | -3.0 | | | | | | | |
| | -4.0 | S-2 | NA | 4.0 | | | 0 | Collect sample from 5.0-5.5 ft bgs @ 9:55 |
| | -5.0 | | | | | 5.0 - 6.0' FILL: Olive brown silty sand, trace clay (suspect COPR); moist | | |
| | -6.0 | | | | | 6.0 - 7.0' FILL: Light grey sandy silt, trace clay; wet | | Collect sample from 7.0-7.5 ft bgs @ 10:00 |
| | -7.0 | | | | | 7.0 - 7.5' FILL: Dark grey silt, trace clay; wet | | |
| | -8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' FILL: Light brown sand (fine-coarse), wet | 0 | Collect sample from 8.5-9.0 ft bgs @ 10:05 |
| | -9.0 | | | | | 8.0 - 11.0' FILL: Light brown sand (fine-medium), wet | | |
| | -10.0 | | | | | | | Collect sample from 11.0-11.5 ft bgs @ 10:10 |
| | -11.0 | | | | | 11.0 - 12.0' FILL: Light brown silt, wet | | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | Collect sample from 13.0- |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-031
**DATE BEGAN:** 6/20/08
**DATE FINISHED:** 6/20/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | 12.0 - 12.8' FILL: Light brown clayey silt, wet | | 13.5 ft bgs @ 10:15 |
| | -13.0 | | | | | 12.8 - 13.8' FILL: Olive/light grey silt (COPR), moist | | |
| | -14.0 | | | | | 13.8 - 14.5' FILL: Brown silty sand (fine-medium), some organic material, moist | | Collect sample from 14.5-15.0 ft bgs @ 10:20 |
| | -15.0 | | | | | 14.5 - 15.5' FILL: Light brown silty sand, possible COPR from 14.5-15'; wet | | |
| | | | | | | 15.5 - 16.0' OL: Black organic silt, wet | | |
| | -16.0 | S-5 | NA | 4.0 | | 16.0 - 17.5' PT: Peat | 0 | Collect sample from 17.5-18.0 ft bgs @ 10:25 |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | 17.5 - 19.0' SP: Light grey sand (fine-medium), trace organic material from 17.5-18.5'; saturated | | Collect sample from 19.0-19.5 ft bgs @ 10:30 |
| | -19.0 | | | | | 19.0 - 20.0' SP: Olive sand (fine); wet, end of boring at 20' | | |
| | -20.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-032
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17.5 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 4.0 | S-1 | NA | 3.5 | | -4.5 - -4.0' CONCRETE: Core through concrete | 0 | Boring located in elevated trucking bay, approximately 4.5' above ground surface. Depth intervals in sample IDs are from top of boring, rather than depth above or below ground surface (see sampling notes below). Driller cored through concrete before drilling. |
| | 3.0 | | | | | -4.0 - -1.0' FILL: Dark brown silty sand (fine) with gravel (fine-medium), dry | | 134-SB-032_0002 collected from 4.0-3.5' ags @ 7:50 |
| | 2.0 | | | | | | | 134-SB-032_0204 collected from 2.5-2.0' ags @ 7:55 |
| | 1.0 | | | | | -1.0 - -0.5' No recovery | | |
| | | S-2 | NA | 3.5 | | -0.5 - 1.0' FILL: Light brown silty sand (fine), moist | 0 | |
| | 0.0 | | | | | | | |
| | -1.0 | | | | | 1.0 - 3.0' FILL: Dark brown silty sand (fine), yellow/green COPR at 5.75'; very hard, moist | | 134-SB-032_0406 collected from 1.0-1.5' bgs @ 8:00 |
| | -2.0 | | | | | | | 134-SB-0320608 collected from 2.5-3.0' bgs @ 8:05 |
| | -3.0 | | | | | 3.0 - 3.5' No recovery | | |
| | | S-3 | NA | 3.0 | | 3.5 - 4.0' FILL: Dark brown silty sand (fine) some glass and wood, moist | 0 | |
| ▽ | -4.0 | | | | | | | 134-SB-032_0810 collected from 4.0-4.5' bgs @ 8:10 |
| | -5.0 | | | | | 4.0 - 5.0' FILL: Light brown silt, trace sand (fine); wet | | |
| | | | | | | 5.0 - 5.3' FILL: Light brown clayey silt, wet | | |
| | -6.0 | | | | | 5.3 - 6.5' FILL: Light brown sand (fine-medium), trace clayey silt; wet | | 134-SB-032_1012 collected from 6.0-6.5' bgs @ 8:15 |
| | -7.0 | | | | | 6.5 - 7.5' No recovery | | |
| | | S-4 | NA | 3.5 | | | 0 | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-032
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17.5 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -8.0 | | | | | 7.5 - 11.0' FILL: Light brown sand (fine-medium) with trace clayey silt, saturated | | 134-SB-032_1214 collected from 8.0-8.5' bgs @ 8:20 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | 134-SB-032_1416 collected from 10.5-11.0' bgs @ 8:25 |
| | -11.0 | | | | | 11.0 - 11.5' No recovery | | |
| | | S-5 | NA | 3.5 | | 11.5 - 12.0' FILL: Light brown clayey silt, saturated | 0 | |
| | -12.0 | | | | | 12.0 - 12.8' FILL: Olive/light grey silt, saturated | | 134-SB-032_1618 collected from 12.0-12.5' bgs @ 8:30 |
| | -13.0 | | | | | 12.8 - 13.5' FILL: Light/dark brown silt with fine organics, saturated | | |
| | -14.0 | | | | | 13.5 - 15.0' OL: Black/light brown silt, trace fine organic material, organic odor, saturated | | 134-SB-032_1820 collected from 14.5-15.0' bgs @ 8:35 |
| | -15.0 | | | | | 15.0 - 15.5' No recovery | | |
| | | S-6 | NA | 2.0 | | 15.5 - 17.0' ML: Light brown silt with fine organics, wet | 0 | |
| | -16.0 | | | | | | | 134-SB-032_2022 collected from 16.0-16.5' bgs @ 8:40 |
| | -17.0 | | | | | 17.0 - 17.5' PT: Dark brown peat; end of boring at 17.5' bgs | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-033
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16.5 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 4.0 | S-1 | NA | 3.5 | | -4.5 - -4.0' CONCRETE | 0 | Boring located in elevated trucking bay, approximately 4.5' above ground surface. Depth intervals in sample IDs are from top of boring, rather than depth above or below ground surface (see sampling notes below). Driller cored through concrete before drilling. |
| | | | | | | -4.0 - -3.8' FILL: Gravel | | |
| | 3.0 | | | | | -3.8 - -1.0' FILL: Light brown silty sand (fine), brick, gravel (fine-medium), dry | | |
| | 2.0 | | | | | | | |
| | 1.0 | | | | | -1.0 - -0.5' No recovery | | 134-SB-033_0002 collected from 3.0-2.5' ags @ 10:25 |
| | | S-2 | NA | 3.5 | | -0.5 - -0.3' FILL: Light brown silty sand (fine), brick, gravel (fine-medium), dry | 0 | 134-SB-033_0204 collected from 1.5-1.0' ags @ 10:30 |
| | 0.0 | | | | | -0.3 - 1.8' FILL: Red brown/dark brown silty sand (fine), trace gravel (fine), dry | | 134-SB-033_0406 collected from 0.5-1.0' bgs @ 10:35 |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | 1.8 - 3.0' FILL: Dark grey silty sand (fine) with crushed concrete, gravel; moist | | 134-SB-033_0608 collected from 2.5-3.0' bgs @ 10:40 |
| | -3.0 | | | | | 3.0 - 3.5' No recovery | | |
| | | S-3 | NA | 3.0 | | 3.5 - 5.5' FILL: Light brown silt; wet from 4.5' bgs | 0 | 134-SB-033_0810 collected from 4.0-4.5' bgs @ 10:45 |
| | -4.0 | | | | | | | |
| | -5.0 | | | | | | | |
| | | | | | | 5.5 - 6.0' FILL: Black/light brown clayey silt, wet | | |
| | -6.0 | | | | | 6.0 - 6.5' FILL: Light brown sand (fine-medium), wet | | 134-SB-033_1012 collected from 6.0-6.5' bgs @ 10:50 |
| | -7.0 | | | | | 6.5 - 7.5' No recovery | | |
| | | S-4 | NA | 3.5 | | | 0 | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-033
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** B. Senna / M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16.5 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -8.0 | | | | | 7.5 - 11.0' FILL: Light brown sand (fine-medium), some silt from 10.5' bgs; saturated | | 134-SB-033_1214 collected from 8.0-8.5' bgs @ 10:55 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | 134-SB-033_1416 collected from 10.5-11.0' bgs @ 11:00 |
| | -11.0 | | | | | 11.0 - 11.5' No recovery | | |
| | | S-5 | NA | 4.0 | | 11.5 - 14.3' FILL: Light brown clayey silt; saturated | 0 | |
| | -12.0 | | | | | | | 134-SB-033_1618 collected from 12.0-12.5' bgs @ 11:05 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | | | | | | 14.3 - 15.5' OL: Black silt, trace clay and organic material; organic odor; wet | | 134-SB-033_1820 collected from 14.5-15.0' bgs @ 11:10 |
| | -15.0 | | | | | | | |
| | | S-6 | NA | 1.0 | | 15.5 - 16.4' ML: Light brown clayey silt with fine organic material; moist | 0 | 134-SB-033_2022 collected from 15.5-16.0' bgs @ 11:15 |
| | -16.0 | | | | | 16.4 - 16.5' PT: Dark brown peat; end of boring at 16.5' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-034
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt & gravel | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Red brown silt and sand (fine), trace coal and gravel; tight; dry | | |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Light yellow/white sand, angular gravel (medium-coarse) and concrete, dry | | 134-SB-034_0002 collected from 1.5-2.0' bgs @ 11:10 |
| | -3.0 | | | | | 2.0 - 3.5' FILL: Red brown silt, trace sand (fine), wood from 2.5-2.75', few dark green mottles; tight; moist from 2.75' | | 134-SB-034_0204 collected from 3.0-3.5' bgs @ 11:13 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 4.8' FILL: Red brown silt, trace sand (fine) and gravel (fine), dark green mottling; tight, moist | 0 | 134-SB-034_0406 collected from 4.0-4.5' bgs @ 11:20 |
| | -5.0 | | | | | 4.8 - 6.0' FILL: Silty sand, trace clay; wet | | |
| | -6.0 | | | | | 6.0 - 7.8' FILL: Brown/dark brown clay, trace silt; wet | | |
| | -7.0 | | | | | 7.8 - 8.0' FILL: Brown silty sand, trace clay; wet | | 134-SB-034_0608 collected from 7.5-8.0' bgs @ 11:28 |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Brown sand (fine-medium), trace clay from 11.0-11.5'; saturated | 0 | |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | 134-SB-034_0810 collected from 9.5-10.0' bgs @ 11:34 |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | 134-SB-034_1012 collected from 11.5-12.0' bgs @ 11:40 |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-034
**DATE BEGAN:** 6/19/08
**DATE FINISHED:** 6/19/08
**INSPECTOR:** E. Jackson / T.Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | | | |
| | -13.0 | | | | | 12.0 - 15.0' FILL: Light brown clay, trace silt; plastic; wet | | 134-SB-034_1214 collected from 13.5-14.0' bgs @ 11:50 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.0 - 16.8' CL: Dark brown/black silty clay; wet | | 134-SB-034_1416 collected from 15.5-16.0' bgs @ 11:53 |
| | -16.0 | S-5 | NA | 4.0 | | | 0 | |
| | -17.0 | | | | | 16.8 - 18.5' PT: Peat | | 134-SB-034_1618 collected from 16.0-16.5' bgs @ 12:17 |
| | -18.0 | | | | | | | |
| | -19.0 | | | | | 18.5 - 20.0' OL: Brown/light brown silty clay with organic material, trace sand; end of boring at 20' | | 134-SB-034_1820 collected from 19.0-19.5' bgs @ 12:19 |
| | -20.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-035
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | 134-SB-035_0002 collected from 0.5-1.0' bgs @ 9:19 |
| | | | | | | 0.5 - 1.5' FILL: Dark brown silt, sand (coarse) and gravel (fine-medium, angular); moist | | |
| | -1.0 | | | | | | | |
| | | | | | | 1.5 - 2.5' FILL: Dark brown silty sand (fine-medium); moist | | |
| | -2.0 | | | | | | | 134-SB-035_0204 collected from 2.0-2.5' bgs @ 9:23 |
| | | | | | | 2.5 - 4.0' No recovery | | |
| | -3.0 | | | | | | | |
| | -4.0 | S-2 | NA | 0.75 | | 4.0 - 4.8' FILL: Dark brown silty sand (fine-medium), red mottling; wet | 0 | 134-SB-035_0406 collected from 4.0-4.5' bgs @ 9:26 |
| | | | | | | 4.8 - 8.0' No recovery; end of boring at 8' bgs | | |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-036
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | 134-SB-036_0002 collected from 0.5-1.0' bgs @ 8:49 |
| | | | | | | 0.5 - 1.3' FILL: Dark grey/brown silty sand (fine), trace gravel (fine-medium), dry | | |
| | -1.0 | | | | | 1.3 - 1.5' FILL: Gravel (coarse), dry | | |
| | | | | | | 1.5 - 2.5' FILL: Dark/red brown silt; firm, moist | | |
| | -2.0 | | | | | | | 134-SB-036_0204 collected from 2.5-3.0' bgs @ 8:53 |
| | | | | | | 2.5 - 3.0' FILL: Grey silt, trace sand with bright green mottles (COPR), moist | | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 4.8' FILL: Olive/bright green silt, trace clay (COPR); firm, moist | 0 | 134-SB-036_0406 collected from 4.0-4.5' bgs @ 8:56 |
| | -5.0 | | | | | 4.8 - 6.0' FILL: Brown/olive green silty sand, trace clay; moist | | |
| | -6.0 | | | | | 6.0 - 8.0' FILL: Red brown silty clay, saturated; end of boring at 8' | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-037
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** B. Senna/M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | 134-SB-037_0002 collected from 1.0-1.5' bgs @ 11:50 |
| | -1.0 | | | | | 1.0 - 3.0' FILL: Dark brown silty sand (fine) with some coal, brick and gravel (fine-medium), moist | | |
| | -2.0 | | | | | | | 134-SB-037_0204 collected from 2.5-3.0' bgs @ 11:55 |
| | -3.0 | | | | | 3.0 - 3.3' FILL: Crushed concrete | | |
| | | | | | | 3.3 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 6.5' FILL: Dark brown silt, saturated | 0 | 134-SB-037_0406 collected from 5.5-6.0' bgs @ 12:00 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | 6.5 - 8.0' FILL: Yellow-green/white silt (COPR); very firm from 7', wet; end of boring at 8' | | |
| | -8.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-038
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** B. Senna/M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | 134-SB-038_0002 collected from 1.5-2.0' bgs @ 11:25 |
| | -1.0 | | | | | 0.5 - 2.0' FILL: Dark brown silty sand (fine) with gravel (fine-coarse) | | |
| | -2.0 | | | | | 2.0 - 2.5' FILL: Gravelly sand (fine), very moist | | 134-SB-038_0204 collected from 2.5-3.0' bgs @ 11:30 |
| | | | | | | 2.5 - 3.0' FILL: Light orange/yellow orange silty sand (COPR) | | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 6.0' FILL: Dark brown silt, yellow green from 5.0-6.0' (COPR); wet from 4.5' | 0 | 134-SB-038_0406 collected from 5.5-6.0' bgs @ 11:35 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 6.0 - 8.0' FILL: Yellow-green silt (COPR), wet; end of boring at 8' | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-039
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** E Jackson / T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | 134-SB-039_0002 collected from 1.5-2.0' bgs @ 8:24 |
| | | | | | | 0.5 - 1.0' FILL: Dark brown sand (coarse) and gravel (fine-coarse), trace silt, some brick, dry | | |
| | -1.0 | | | | | 1.0 - 3.5' FILL: Dark brown silt with bright green/yellow mottling from 2.75-3' (COPR); firm, moist | | |
| | -2.0 | | | | | | | 134-SB-039_0002 collected from 3.0-3.5' bgs @ 8:26 |
| | -3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 6.0' FILL: Dark brown silt with bright green/yellow mottling (COPR), saturated | 0 | 134-SB-039_0002 collected from 5.0-5.5' bgs @ 8:30 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 6.0 - 7.0' FILL: Dark brown clay and silt, trace sand; saturated | | |
| | -7.0 | | | | | 7.0 - 8.0' No recovery; end of boring at 8' | | |
| | -8.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-040
**DATE BEGAN:** 6/20/08
**DATE FINISHED:** 6/20/08
**INSPECTOR:** B. Senna/M. Vetter
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | 134-SB-040_0002 collected from 1.5-2.0' bgs @ 11:10 |
| | -1.0 | | | | | 1.0 - 2.0' FILL: Red brown silty sand with potential COPR from 1.75-2.0', dry | | |
| | -2.0 | | | | | 2.0 - 3.5' FILL: Light brown silty sand (fine) with crushed concrete, some gravel (fine-coarse), yellow green/white COPR; firm, dry | | 134-SB-040_0002 collected from 3.0-3.5' bgs @ 11:15 |
| | -3.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Dark brown silty sand (fine) with gravel (fine), moist | 0 | 134-SB-040_0204 collected form 5.0-5.5' bgs @ 11:20 |
| | -5.0 | | | | | 4.5 - 7.0' FILL: Light brown silt, saturated | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | 7.0 - 7.5' FILL: Yellow green silt (COPR) | | |
| | -8.0 | | | | | 7.5 - 8.0' No recovery; end of boring at 8' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-041
**DATE BEGAN:** 10/1/08
**DATE FINISHED:** 10/1/08
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: asphalt | 0 | |
| | -1.0 | | | | | 0.3 - 0.5' FILL: black/dark brown silty sand with fine to coarse gravel, dry | | |
| | -2.0 | | | | | 0.5 - 3.0' FILL: brown silty sand with brick concrete and gravel, dry | | |
| | -3.0 | | | | | 3.0 - 3.5' FILL: light brown silty sand with fine to medium gravel, moist | | |
| | -4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 4.8' FILL: brown/red brown silt with fine to medium gravel, very moist | | |
| | -6.0 | | | | | 4.8 - 6.5' FILL: brown silt, fine to coarse gravel throughout, some wood from 6.0-6.5, wet at 5.5 | | |
| | -7.0 | | | | | 6.5 - 7.0' FILL: black/dark brown silty sand, wet | | |
| | -8.0 | S-3 | NA | 3.0 | | 7.0 - 8.0' No recovery | 0 | |
| | -9.0 | | | | | 8.0 - 9.0' FILL: light brown silty sand, saturated | | |
| | -10.0 | | | | | 9.0 - 11.0' FILL: light brown fine to medium sand, saturated | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | S-4 | NA | 3.5 | | 12.0 - 13.0' FILL: light brown fine to medium sand, saturated | 0 | |
| | -13.0 | | | | | 13.0 - 14.3' FILL: red brown/light brwon clayey silt, saturated | | |
| | -14.0 | | | | | 14.3 - 15.5' FILL: black silt, tight, very moist | | |
| | -15.0 | | | | | 15.5 - 16.0' No recovery | | |
| | -16.0 | S-5 | NA | 2.0 | | 16.0 - 18.0' PEAT: dark brown peat, very moist | 0 | 134-SB-041_1618 collected @ 13:50 |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, Old Dominion, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-042
**DATE BEGAN:** 07/08/09
**DATE FINISHED:** 07/08/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18.5 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 113 |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 2.0 - 2.8' FILL: Black silt, some sand | | |
| | 3.0 | | | | | 2.8 - 3.5' FILL: Brown silty sand, some f-m gravel, trace brick, coal and clinker | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.5 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 5.2' FILL: Brown silty sand, some f-m gravel, trace clay, brick, coal and clinker; moist | | |
| | 6.0 | | | | | 5.2 - 5.6' FILL: Brown clayey silt, trace fine sand; wet | | |
| | 7.0 | | | | | 5.6 - 6.9' FILL: Brown silty clay; soft, wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 6.9 - 10.5' FILL: Brown f-m sand, trace fine gravel from 6.9-8.0', few clay lenses from 8.0'; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 11.0' FILL: Brown silty sand, wet | | |
| | 11.0 | | | | | 11.0 - 14.5' FILL: Brown/dark brown silty clay, trace fine sand; soft, wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.5 - 15.0' FILL: Brown clayey sand and f-m gravel; wet | | |
| | 15.0 | | | | | 15.0 - 15.5' FILL: Yellow clayey COPR; soft | | |
| | 16.0 | R-5 | N/A | 2.5 | | 15.5 - 16.5' OL: Very dark grayish brown (2.5Y 3/2) clayey silt, trace organic material | 0.0<br>1.7 | 134-SB-042-1618 collected from 16.5-17.0' bgs @ 15:15 |
| | 17.0 | | | | | 16.5 - 18.5' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 18.5' | 0.2<br>4.3<br>0.1 | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-043
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 19.3 ft. bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 114 |
| | 1.0 | | | | | 0.2 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.0 - 1.6' FILL: Reddish brown/brown silty sand, some f-m gravel, trace fine sand, trace brick, clinker | 0.0 | |
| | 3.0 | | | | | 1.6 - 3.0' FILL: Very dark grayish brown fine sand, trace silt; dense | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 3.8' FILL: Dark brown f-c sand and fine gravel, trace clinker, coal, and brick; wet | 0.0 | |
| | 5.0 | | | | | 3.8 - 4.0' FILL: Reddish brown f-m sand, trace fine gravel; wet | | |
| | 6.0 | | | | | 4.0 - 4.7' FILL: Dark brown f-c sand and fine gravel, trace coal and clinker; wet | 0.0 | |
| | 7.0 | | | | | 4.7 - 5.5' FILL: Reddish brown f-m sand, trace fine gravel and silt; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 5.5 - 6.2' FILL: Brown clayey silt, trace fine sand, soft; wet | 0.0 | |
| | 9.0 | | | | | 6.2 - 8.0' FILL: Brown, f-m sand, trace fine gravel and silt; wet | | |
| | 10.0 | | | | | 8.0 - 12.0' FILL: Brown f-m sand, trace silt and clay from 9.0-9.5', few silt lenses from 10.0'; wet | 0.0 | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 1.0 | | 12.0 - 13.0' FILL: Brown clayey silt, very soft | 0.0 | |
| | 13.0 | | | | | 13.0 - 16.0' No recovery | | |
| | 14.0 | | | | | | 0.0 | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-043
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 19.3 ft. bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | R-5 | N/A | 3.3 | | 16.0 - 17.0' OL: Dark gray (2.5 Y4/1) clayey silt, some organic material; soft, wet | 0.0 | 134-SB-043-1618 collected from 16.0-16.5' bgs @ 9:05 |
| | 17.0 | | | | | 17.0 - 18.3' PT: Very dark brown (7.5 YR 2.5/2) peat | | |
| | 18.0 | | | | | 18.3 - 18.6' OL: Very dark brown OL (7.5 YR 2.5/2), trace organic material; wet | 0.0 | |
| | 19.0 | | | | | 18.6 - 19.3' SM: Gray (2.5 Y 5/1) silty sand; wet; end of boring at 19.3' | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-044
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18.0 ft. bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 114 |
| | | | | | | 0.3 - 0.5' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.5 - 1.7' FILL: Dark brown/brown f-m sand, trace fine gravel, clinker, brick, coal, trace yellow green mottling at 1.5' | | |
| | 2.0 | | | | | 1.7 - 2.0' FILL: Yellow/white sandy silt, concrete from 1.9-2.0' | 0.0 | |
| | 3.0 | | | | | 2.0 - 2.5' FILL: Very dark brown silty sand | | |
| | | | | | | 2.5 - 3.5' FILL: Dark brown/black f-c sand and fine clinker, trace fine gravel and coal and brick; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.5 - 3.7' FILL: Reddish brown f-m sand; wet | 0.0 | |
| | 5.0 | | | | | 3.7 - 4.0' FILL: Brown/dark brown silt, trace fine sand and glass; wet | | |
| | 6.0 | | | | | 4.0 - 6.0' FILL: Dark brown/brown clayey silt; wet | 0.0 | |
| | 7.0 | | | | | 6.0 - 8.0' FILL: Dark brown f-m sand, few silt lenses from 7.5'; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 12.0' FILL: Brown/dark brown f-m sand,some silt and clay from 8.5-8.8', 9.2-9.5', 11.0-12.0'; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | 0.0 | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 3.0 | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-044
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18.0 ft. bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | R-4 | N/A | 3.0 | | 12.0 - 13.8' FILL: Brown/dark brown clayey silt, very soft; wet | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 13.8 - 15.0' OH: Very dark grayish brown (2.5Y 3/2) to black (2.5Y 2.5/1), trace organic material; wet | 0.0 | 134-SB-043-1416 collected from 14.5-15.0' bgs @ 10:20; HOLD |
| | 15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | 16.0 | R-5 | N/A | 2.0 | | 16.0 - 16.8' OL: Dark grayish brown (2.5Y 4/2) clayey silt, some organic material; wet | 0.0 | 134-SB-043-1618 collected from 16.0-16.5' bgs @ 10:40 |
| | 17.0 | | | | | 16.8 - 17.3' PT: Very dark brown (7.5YR 2.5/2) peat | | |
| | 18.0 | | | | | 17.3 - 18.0' SM: Gray (2.5Y 5/1) silty sand | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-045
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18.0 ft. bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 118 |
| | | | | | | 0.3 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Reddish brown f-m sand, trace yellow brown mottling, trace silt and fine gravel and brick | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Very dark grayish brown fine sand, trace silt, some brick from 1.7-1.9', yellow COPR from 2.0-2.2' | 0.0 | Sampled from 2.0-2.2' and performed DPT field test; result positive, i.e. pink color after 5 seconds |
| | 3.0 | | | | | 2.5 - 3.1' FILL: Reddish brown silty sand, some f-m gravel, trace coarse concrete and wood, trace coal and clinker | | |
| | 4.0 | R-2 | N/A | 3.0 | | 3.1 - 3.5' FILL: Reddish brown f-m sand, trace medium gravel | 0.0 | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Reddish brown f-m sand, trace medium gravel, trace wood; wet | | |
| | 6.0 | | | | | 4.5 - 5.7' FILL: Brown/dark brown silty sand, some clay from 5.5'; wet | 0.0 | |
| | 7.0 | | | | | 5.7 - 7.0' FILL: Brown f-m sand, few dark borwn silt lenses, trace coarse sand from 5.7-6.0'; wet | | |
| | | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 12.0' FILL: Brown f-m sand, some clay from 8.5-8.9' and 11.6-11.8'; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | 0.0 | |
| | 11.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-045
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18.0 ft. bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | R-4 | N/A | 3.0 | | 12.0 - 13.0' FILL: Light brown silty clay, trace fine gravel; wet | 0.0 | |
| | 13.0 | | | | | 13.0 - 15.0' OL: Very dark grayish brown (2.5 Y 3/2) clayey silt, few brown (10 YR 5/3) lenses; wet | | |
| | 14.0 | | | | | | 0.0 | |
| | 15.0 | | | | | 15.0 - 15.5' OH: Black (2.5 Y 2.5/1) silty clay; wet | | |
| | 16.0 | R-5 | N/A | 2.0 | | 15.5 - 16.5' OL: Dark grayish brown (2.5 Y 4/2) clayey silt, trace organic material; wet | 0.0 | 134-SB-045-1416 collected from 15.5-16.0' bgs @ 11:50 HOLD<br>134-SB-045-1618 collected from 16.0-16.5 bgs @ 12:10 |
| | 17.0 | | | | | 16.5 - 17.0' PT: Very dark brown (7.5 YR 2.5/2) peat | | |
| | 18.0 | | | | | 17.0 - 18.0' SM: Dark gray (2.5 Y 4/1) silty sand; wet; end of boring at 18.0' | | |

PREPARED BY: MC
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-046
**DATE BEGAN:** 07/09/09
**DATE FINISHED:** 07/09/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16.0 ft. bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 118 |
| | 1.0 | | | | | 0.2 - 0.5' FILL: Brown f-m gravel, some f-m sand | | |
| | 2.0 | R-2 | | 2.0 | | 0.5 - 1.8' FILL: Reddish brown/brown silty sand, some fine gravel and brick, trace coal, concrete, and clinker | 0.0 | Refusal at 2.5' bgs, moved 2ft NE |
| | 3.0 | | | | | 1.8 - 2.0' FILL: Dark grayish brown silty sand, trace wood; moist, compact | | |
| | 4.0 | R-3 | N/A | 3.5 | | 2.0 - 3.0' FILL: Dark grayish brown silty sand, trace wood; moist, compact | 0.0 | |
| | 5.0 | | | | | 3.0 - 3.5' FILL: Black f-m clinker, some f-m sand, trace fine gravel | | |
| | 6.0 | | | | | 3.5 - 4.0' FILL: Reddish brown f-m sand; wet | 0.0 | |
| | 7.0 | | | | | 4.0 - 4.1' FILL: Reddish brown f-m sand; wet | | |
| | 8.0 | R-4 | N/A | 4.0 | | 4.1 - 6.2' FILL: Brown clayey silt, trace organic material and fine sand; wet | 0.0 | |
| | 9.0 | | | | | 6.2 - 7.5' FILL: Brown f-m sand, few silt lenses; wet | | |
| | 10.0 | | | | | 7.5 - 8.0' FILL: No recovery | 0.0 | |
| | 11.0 | | | | | 8.0 - 10.5' FILL: Brown f-m sand, few silt lenses; wet | | |
| | 12.0 | | N/A | | | 10.5 - 12.0' FILL: Brown fine sand, trace silt, trace clay from 11.8'; wet | 0.0 | DPC test on gray clay showed pink (positive result) |
| | 13.0 | | | | | 12.0 - 13.0' FILL: Light brown silty clay, soft, some gray COPR; wet | | |
| | 14.0 | | | | | 13.0 - 16.0' OH: Very dark grayish brown/black clayey silt with lenses of very dark brown (7.5YR 2.5/2) peat from 15.5-16.0'; end of boring at 16.0' | 0.0 | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | 134-SB-046-1416 collected from 15.5-16.0' bgs @ |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-047
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 117 |
| | 1.0 | | | | | 0.3 - 1.0' FILL: Brown f-m sand, some f-m gravel | | |
| | 2.0 | | | | | 1.0 - 4.5' FILL: Very dark grayish brown silt, trace fine sand; some f-c sand and f-m gravel from 4.2-4.3'; dense, wet from 4.0' | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.8' FILL: Dark brown/ brown silty sand, trace clay; trace white silt and sand (COPR); wet | | |
| | 6.0 | | | | | 5.8 - 7.5' FILL: Very dark grayish brown silty clay; soft, wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 3.5 | | 7.5 - 9.7' FILL: Brown f-m sand, wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.7 - 11.5' FILL: Brown clayey silt, trace fine sand; wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.5 - 12.0' No recovery | 0.0 | |
| | 13.0 | | | | | 12.0 - 13.0' FILL: Brown f-m sand, few lenses of stiff varved silt; some light gray clayey COPR from 12.5'; soft, wet | | |
| | 14.0 | | | | | 13.0 - 15.5' OH: Very dark grayish brown(7.5YR 3/2) to black (7.5YR 2/1) clayey silt, trace organic material | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | 15.5 - 16.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 16.0' | | 134-SB-047-1416 collected from 15.0-15.5' bgs @ 8:40 |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-048
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.4' ASPHALT | 0.0 | Field Map # 94 |
| | 1.0 | | | | | 0.4 - 1.0' FILL: Reddish brown silt, some f-m, trace fine gravel; trace yellowish brown mottling (COPR) | | |
| | 2.0 | | | | | 1.0 - 1.2' FILL: Brick | | |
| | 3.0 | | | | | 1.2 - 4.0' FILL: Very dark grayish brown silt, trace fine sand, coal, and glass; dense | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.5' FILL: Dark brown f-m gravel and wood, trace f-m sand; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.3' FILL: Reddish brown silty sand, trace fine gravel; white silty sand (COPR) from 4.5-4.7'; wet | | |
| | 6.0 | | | | | 5.3 - 6.0' FILL: Very dark grayish brown silty clay; soft, wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | 6.0 - 6.5' FILL: Brown f-m sand, wet | 0.0 | |
| | 9.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 9.5' FILL: Brown f-m sand, wet | | |
| | 11.0 | | | | | 9.5 - 10.0' FILL: Dark brown clayey silt, some lenses of fine sand, trace wood; soft, wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 10.0 - 13.0' FILL: Brown clayey silt; some gray clayey COPR and nodules of stiff varved clay from 12.0'; very soft, wet | 0.0 | |
| | 13.0 | | | | | 13.0 - 15.5' OH: Very dark grayish brown(7.5YR 3/2) to black (7.5YR 2/1) clayey silt, trace organic material; soft to firm | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | R-5 | N/A | 2.0 | | 15.5 - 16.7' OL: Dark gray (2.5Y 4/1) clayey silt, some coarse organic material; firm | 0.0 | 134-SB-048-1618 collected from 16.0-16.5' bgs @ 9:25 |
| | 17.0 | | | | | 16.7 - 18.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 18.0' | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-049
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 121 |
| | | | | | | 0.2 - 0.7' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.7 - 1.5' FILL: Dark brown/brown f-m sand, trace fine gravel; trace light brown/white/ yellowish brown mottling (possible COPR) | | 134-SB-049-0002 collected from 1.0-1.5' bgs @ 9:50 |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Very dark grayish brown silt, trace fine sand; very stiff | | 134-SB-049-0204 collected from 2.5-3.0' bgs @ 9:55 |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Dark brown f-c sand, some f-m clinker, trace fine gravel; wet | | |
| | 4.0 | R-2 | N/A | 3.5 | | 3.0 - 3.5' FILL: Reddish brown silty sand, trace f-m brick; wet | 0.0 | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Reddish brown silty sand, trace f-m brick; wet | | 134-SB-049-0406 collected from 5.0-5.5' bgs @ 10:00 |
| | 6.0 | | | | | 4.5 - 6.5' FILL: Brown clayey silt, some organic material from 4.5-5.0'; wet | | |
| | 7.0 | | | | | 6.5 - 7.5' FILL: Brown f-m sand, wet | | 134-SB-049-0608 collected from 7.0-7.5' bgs @ 10:05 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 9.0' FILL: Brown f-m sand, wet | 0.0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Brown clayey silt, some nodules of stiff varved clay and silt; trace f-m sand; wet | | 134-SB-049-0810 collected from 8.5-9.0' bgs @ 10:10 |
| | | | | | | 9.5 - 11.5' FILL: Dark brown silty clay; soft | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | 134-SB-049-1012 collected from 11.0-11.5' bgs @ 10:15 |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 4.0 | | | | 134-SB-049-1214 collected |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-049
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 13.5' FILL: Dark brown silty clay; soft | 0.0 | 134-SB-049-1214 collected from 12.0-12.5' bgs @ 10:20 |
| | 13.0 | | | | | 13.5 - 15.5' OH: Very dark grayish brown(7.5YR 3/2) to black (7.5YR 2/1) clayey silt, trace to some organic material | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | 134-SB-049-1416 collected from 15.0-15.5' bgs @ 10:25; DUP @ 10:27 |
| | 16.0 | | | | | 15.5 - 16.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 16.0' | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-049R
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 17 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.2' ASPHALT | 0.0 | |
| | | | | | | 0.2 - 0.7' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.7 - 1.5' FILL: Dark brown/brown f-m sand, trace fine gravel; trace light brown/white/ yellowish brown mottling (possible COPR) | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Very dark grayish brown silt, trace fine sand; very stiff | | |
| | | | | | | 2.0 - 3.0' FILL: Dark brown f-c sand, some f-m clinker, trace fine gravel; wet | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Reddish brown silty sand, trace f-m brick; wet | | |
| | 4.0 | R-2 | N/A | 3.5 | | 3.5 - 4.0' No recovery | 0.0 | |
| | | | | | | 4.0 - 4.5' FILL: Reddish brown silty sand, trace f-m brick; wet | | |
| | 5.0 | | | | | 4.5 - 6.5' FILL: Brown clayey silt, some organic material from 4.5-5.0'; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 7.5' FILL: Brown f-m sand, wet | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 9.0' FILL: Brown f-m sand, wet | 0.0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Brown clayey silt, some nodules of stiff varved clay and silt; trace f-m sand; wet | | |
| | | | | | | 9.5 - 11.5' FILL: Dark brown silty clay; soft | | |
| | 10.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-049R
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 17 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.5 - 12.0' No recovery<br>12.0 - 13.5' FILL: Dark brown silty clay; soft | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 13.5 - 15.5' OH: Very dark grayish brown(7.5YR 3/2) to black (7.5YR 2/1) clayey silt, trace to some organic material | | |
| | 15.0 | | | | | | | |
| | 16.0 | R-5 | N/A | 1.0 | | 15.5 - 17.0' PT: Brown peat; end of boring at 17.0' bgs. | 0.0 | 134-SB-049R-1618 collected from 16.5-17.0' bgs @ 9:10 |
| | 17.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-050
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 110 |
| | 1.0 | | | | | 0.3 - 1.5' FILL: Brown f-m sand, some f-m gravel, trace brick; some clinker from 1.0-1.5' | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Very dark grayish brown silty sand | | 134-SB-050-0002 collected from 1.5-2.0' bgs @ 11:00 |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Dark brown f-c sand, some fine clinker and gravel; wet | | 134-SB-050-0204 collected from 3.0-3.5' bgs @ 11:05 |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 3.5' FILL: Reddish brown silty sand, trace organic material; wet | 0.0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | 134-SB-050-0406 collected from 4.5-5.0' bgs @ 11:10 |
| | 6.0 | | | | | 4.0 - 4.5' FILL: Brown f-m sand, some f-m gravel and brick; wet | | |
| | 7.0 | | | | | 4.5 - 5.0' FILL: Brown silty sand; dense, wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 5.0 - 5.5' FILL: Brown silt, trace fine sand and clay; firm, wet | | 134-SB-050-0608 collected from 7.5-8.0' bgs @ 11:15 |
| | 9.0 | | | | | 5.5 - 8.0' FILL: Brown f-m sand, wet | 0.0 | |
| | 10.0 | | | | | 8.0 - 10.0' FILL: Brown silty sand, trace clay; wet | | 134-SB-050-0810 collected from 9.0-9.5' bgs @ 11:20 |
| | 11.0 | | | | | 10.0 - 11.9' FILL: Brown clayey silt; soft, wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.9 - 12.0' FILL: Brown fine sand, wet | | 134-SB-050-1012 collected from 11.0-11.5' bgs @ 11:25 |
| | 13.0 | | | | | 12.0 - 12.5' FILL: Brown clayey sand; wet | 0.0 | |
| | 14.0 | | | | | 12.5 - 15.0' OL: Very dark grayish brown(7.5YR 3/2) to black (7.5YR 2/1) clayey silt, trace organic material; soft, wet | | 134-SB-050-1214 collected from 12.5-13.0' bgs @ 11:30 |
| | 15.0 | | | | | 15.0 - 16.0' OH: Dark gray (2.5Y 4/1) clayey silt, some organic material; stiff, moist; end of boring at 16.0' | | 134-SB-050-1416 collected from 15.5-16.0' bgs @ 11:35 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-051
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 80 |
| | | | | | | 0.2 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Dark brown/yellowish brown fine sand, trace f-m gravel, silt, clinker, and coal | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Dark brown f-c sand, some fine clinker; trace fine gravel, wood and coal; wet | | 134-SB-051-0204 collected from 2.0-2.5' bgs @ 12:35 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 4.2' FILL: Dark brown f-c sand, some fine clinker; trace fine gravel; wet | 0.0 | |
| | | | | | | 4.2 - 5.5' FILL: Brown silt, trace clay and fine sand; firm, wet | | 134-SB-051-0406 collected from 4.5-5.0' bgs @ 12:40 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.5' FILL: Brown f-m sand, silt from 6.8-7.0'; wet | | 134-SB-051-0608 collected from 6.5-7.0' bgs @ 12:45 |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.5' FILL: Brown f-m sand, clayey silt from 10.0-10.2'; wet | 0.0 | |
| | 9.0 | | | | | | | 134-SB-051-0810 collected from 9.0-9.5' bgs @ 12:50 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' FILL: Brown silty clay; soft, wet; end of boring at 12.0' | | 134-SB-051-1012 collected from 11.5-12.0' bgs @ 12:55; HOLD |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-052
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 83 |
| | | | | | | 0.2 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 1.0 - 2.7' FILL: Reddish brown/brown silty sand, some f-m gravel; trace brick, coal, and concrete; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | | | | | | 2.7 - 3.0' FILL: Dark brown/reddish brown f-c sand, trace clinker; wet | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.5' FILL: Dark brown/reddish brown f-c sand, trace clinker; wet | 0.0 | |
| | | | | | | 4.5 - 5.0' FILL: Reddish brown silty sand, trace f-m brick; dense, wet | | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Brown silt, trace fine sand and clay; firm, wet | | |
| | 6.0 | | | | | 5.5 - 6.2' FILL: Reddish brown fine sand; dense, wet | | |
| | 7.0 | | | | | 6.2 - 6.7' FILL: Dark brown silty clay; soft, wet | | |
| | | | | | | 6.7 - 7.0' FILL: Brown f-c sand, wet | | |
| | 8.0 | R-3 | N/A | 2.5 | | 7.0 - 8.0' No recovery | 0.0 | 134-SB-052-0810 collected from 8.0-8.5' bgs @ 13:15; HOLD |
| | 9.0 | | | | | 8.0 - 9.5' FILL: Brown f-m sand, trace fine gravel; wet | | |
| | | | | | | 9.5 - 10.2' FILL: Brown silty sand, wet | | |
| | 10.0 | | | | | 10.2 - 10.5' FILL: Dark brown clayey silt, trace organic material | | 134-SB-052-1012 collected from 10.0-10.5' bgs @ 13:20 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-053
**DATE BEGAN:** 07/15/09
**DATE FINISHED:** 07/15/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 81 |
| | | | | | | 0.2 - 0.5' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.5 - 3.0' FILL: Brown/reddish brown/black f-m sand; trace f-m gravel, brick, and coal | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Wood | | Driller cleared wood from hole before second sampling run |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 4.2' FILL: Dark brown/reddish brown f-m sand, some fine gravel, trace brick and wood | 0.0 | |
| | 5.0 | | | | | 4.2 - 6.2' FILL: Brown silty sand; compact, wet from 4.5' | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.2 - 8.0' FILL: Brown/dark brown silty clay; soft; stiff varved silty and clay from 7.4-7.5'; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.5' FILL: Brown f-m sand, wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 134-SB-053-0810 collected from 9.5-10.0' bgs @ 13:50; HOLD |
| | 11.0 | | | | | 11.5 - 12.0' FILL: Dark brown clayey silt, some lenses of fine sand; soft, wet; end of boring at 12.0' | | 134-SB-053-1012 collected from 11.5-12.05' bgs @ 13:55 |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-054
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 108 |
| | 1.0 | | | | | 0.2 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.0 - 1.7' FILL: Reddish brown f-m sand; trace fine gravel, brick, and cinders; nodules of gray/white COPR at 1.6' | | 134-SB-054-0002 collected from 1.5-2.0' bgs @ 8:25 |
| | 3.0 | | | | | 1.7 - 2.5' FILL: Very dark grayish brown silt, some fine sand; firm | | 134-SB-054-0204 collected from 3.0-3.5' bgs @ 8:30 |
| | 4.0 | R-2 | N/A | 3.2 | | 2.5 - 3.0' FILL: Black f-m sand and clinker, wet | 0.0<br>19.7 | Petroleum odors from 4.5-5.0' |
| | 5.0 | | | | | 3.0 - 3.7' FILL: Reddish brown f-m sand, some fine gravel; wet | 0.4 | 134-SB-054-0406 collected from 4.5-5.0' bgs @ 8:35 |
| | 6.0 | | | | | 3.7 - 3.8' FILL: Dark brown f-c sand and clinker, wet | 0.0 | |
| | 7.0 | | | | | 3.8 - 4.1' FILL: Brown silt, trace fine sand and organic material | 0.0 | 134-SB-054-0608 collected from 6.5-7.0' bgs @ 8:40 |
| | 8.0 | R-3 | N/A | 2.8 | | 4.1 - 7.2' FILL: Brown/dark brown f-m sand, trace fine gravel and silt nodules; trace organic material from 4.1-5.0'; wet | 0.0 | |
| | 9.0 | | | | | 7.2 - 8.0' No recovery | | 134-SB-054-0810 collected from 9.0-9.5' bgs @ 8:45 |
| | 10.0 | | | | | 8.0 - 10.8' FILL: Brown f-m sand, some lenses of dark brown clayey silt; wet | | 134-SB-054-1012 collected from 10.0-10.5' bgs @ 8:50 |
| | 11.0 | | | | | 10.8 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 12.5' FILL: Brown silty clay; very soft, wet | 0.0 | |
| | 13.0 | | | | | 12.5 - 14.0' FILL: Brown/dark brown silt, trace fine sand and clay; some gray silty COPR from 12.5-12.8'; stiff | | 134-SB-054-1214 collected from 12.5-13.0' bgs @ 8:55 |
| | 14.0 | | | | | 14.0 - 15.5' OH: Black (7.5YR 2/1) clayey silt, soft | | |
| | 15.0 | | | | | 15.5 - 16.0' OL: Dark gray (2.5Y 4/1) clayey silt, stiff; end of boring at 16.0' | | 134-SB-054-1416 collected from 15.5-16.0' bgs @ 9:00 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-055
**DATE BEGAN:** 07/28/09
**DATE FINISHED:** 07/28/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 106 |
| | 1.0 | | | | | 0.3 - 0.8' FILL: Concrete | | 134-SB-055-0002 collected from 1.5-2.0' bgs @ 8:35 |
| | 2.0 | | | | | 0.8 - 2.8' FILL: Brown/reddish brown silty sand, some fine gravel, trace brick and coal | | 134-SB-055-0204 collected from 2.0-2.5' bgs @ 8:40 |
| | 3.0 | | | | | 2.8 - 3.0' FILL: Wood | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 4.0' No recovery | 0.0 | 134-SB-055-0406 collected from 4.0-4.5' bgs @ 8:45 |
| | 5.0 | | | | | 4.0 - 4.7' FILL: Brown clayey sand, trace fine gravel and clinker; moist | | |
| | 6.0 | | | | | 4.7 - 6.2' FILL: Brown clayey silt, soft to firm; wet from 5.0' | | |
| | 7.0 | | | | | 6.2 - 11.0' FILL: Brown f-m sand, trace fine gravel and silt; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | 134-SB-055-0608 collected from 7.5-8.0' bgs @ 8:50 |
| | 9.0 | | | | | | | 134-SB-055-0810 collected from 8.5-9.0' bgs @ 8:55; DUP @ 8:57 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Dark brown/black silty clay, soft; some nodules of stiff, varved silt; wet | | 134-SB-055-1012 collected from 11.5-12.0' bgs @ 9:00 |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 14.0' FILL: Brown silty clay; very soft, wet | 0.0 | 134-SB-055-1214 collected from 12.5-13.0' bgs @ 9:05 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 15.0' FILL: Yellow/light brown clayey COPR, wet | | 134-SB-055-1416 collected from 14.0-14.5' bgs @ 9:10 |
| | 15.0 | | | | | 15.0 - 16.1' OH: Very dark grayish brown (10YR 3/2) clayey silt | | |
| | 16.0 | R-5 | N/A | 2.0 | | 16.1 - 18.0' PT: Very dark brown (7.5YR 2/2) peat; end of boring at 18.0' | 0.0 | 134-SB-055-1618 collected from 16.0-16.5' bgs @ 9:15 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-056
**DATE BEGAN:** 07/28/09
**DATE FINISHED:** 07/28/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 79 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand, some f-m gravel | | |
| | 2.0 | | | | | 1.0 - 3.7' FILL: Very dark grayish brown fine sand, trace silt; wood from 1.9-2.0' | | |
| | 3.0 | | | | | | | 134-SB-056-0204 collected from 3.0-3.5' bgs @ 9:55 |
| | 4.0 | R-2 | N/A | 3.5 | | 3.7 - 4.5' FILL: Reddish brown silty sand, trace f-m gravel and clay; wet from 4.0' | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Brick | | |
| | 6.0 | | | | | 5.0 - 6.2' FILL: Brown clayey silt, soft; some nodules of stiff, varved silt; wet | | 134-SB-056-0406 collected from 5.0-5.5' bgs @ 10:00 |
| | 7.0 | | | | | 6.2 - 7.5' FILL: Brown f-c sand, few silt nodules; wet | | 134-SB-056-0608 collected from 7.0-7.5' bgs @ 10:05 |
| | 8.0 | R-3 | N/A | 3.0 | | 7.5 - 8.0' No recovery | 0.0 | |
| | 9.0 | | | | | 8.0 - 9.5' FILL: Brown f-c sand, few silt nodules; wet | | 134-SB-056-0810 collected from 9.0-9.5' bgs @ 10:10 |
| | 10.0 | | | | | 9.5 - 11.0' FILL: Brown silty clay, soft | | 134-SB-056-1012 collected from 10.5-11.0' bgs @ 10:15 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-057
**DATE BEGAN:** 07/28/09
**DATE FINISHED:** 07/28/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 77 |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Concrete | | |
| | 2.0 | | | | | 1.3 - 3.0' FILL: Brown silty sand, some fine gravel; trace coal, brick, clinker and clay; moist | | 134-SB-057-0204 collected from 2.5-3.0' bgs @ 10:40 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 4.5' FILL: Brown f-m gravel and f-c sand; loose, wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 6.5' FILL: Brown fine sand, trace silt; dense, wet | | 134-SB-057-0406 collected from 5.0-5.5' bgs @ 10:45 |
| | 6.0 | | | | | 6.5 - 6.8' FILL: Dark brown clayey silt, trace fine sand; wet | | |
| | 7.0 | | | | | 6.8 - 10.5' FILL: Brown f-m sand, few silt nodules; wet | | 134-SB-057-0608 collected from 7.5-8.0' bgs @ 10:50 |
| | 8.0 | R-3 | N/A | 3.0 | | | 0.0 | |
| | 9.0 | | | | | | | 134-SB-057-0810 collected from 9.0-9.5' bgs @ 10:55 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.0' FILL: Dark brown silty clay, trace fine sand; wet | | 134-SB-057-1012 collected from 10.5-11.0' bgs @ 11:00 |
| | 12.0 | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-058
**DATE BEGAN:** 07/28/09
**DATE FINISHED:** 07/28/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map # 75 |
| | 1.0 | | | | | 0.3 - 1.0' FILL: Brown f-m sand, some f-m gravel and concrete | | |
| | 2.0 | | | | | 1.0 - 3.0' FILL: Reddish brown silty sand, some concrete, trace coal and brick | | 134-SB-058-0204 collected from 2.5-3.0' bgs @ 11:35 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.5' FILL: Reddish brown silty sand, some concrete, trace coal and brick; dense, wet | 0.0 | 134-SB-058-0406 collected from 4.0-4.5' bgs @ 11:40 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 7.0' FILL: Brown fine sand, trace silt; very dense, wet | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Dark brown/black clayey silt; firm, wet | | 134-SB-058-0608 collected from 7.5-8.0' bgs @ 11:45 |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 12.0' FILL: Brown f-m sand, some silt lenses from 11.7'; end of boring at 12.0' | 0.0 | |
| | 9.0 | | | | | | | 134-SB-058-0810 collected from 8.5-9.0' bgs @ 11:50; DUP @ 11:52 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | 134-SB-058-1112 collected from 11.5-12.0' bgs @ 11:55 |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-059
**DATE BEGAN:** 07/28/09
**DATE FINISHED:** 07/28/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0.0 | Field Map # 51 |
| | 1.0 | | | | | 0.8 - 1.2' FILL: Concrete | | |
| | 2.0 | | | | | 1.2 - 3.5' FILL: Reddish brown f-m sand, some f-m gravel and silt; trace coal, brick and clinker | | |
| | 3.0 | | | | | | | 134-SB-058-0204 collected from 3.0-3.5' bgs @ 13:10 |
| | 4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | R-2 | N/A | 4.0 | | 4.0 - 4.3' FILL: Reddish brown f-m sand, some f-m gravel and silt; trace coal, brick and clinker | 0.0 | 134-SB-058-0406 collected from 4.5-5.0' bgs @ 13:15 |
| | 5.0 | | | | | 4.3 - 7.0' FILL: Brown silty sand, some clay from 4.3-4.5'; wet from 4.5' | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.9' FILL: Very dark grayish brown clayey silt; few thin lenses of light brown silt; wet | | 134-SB-058-0608 collected from 7.5-8.0' bgs @ 13:20 |
| | 8.0 | R-3 | N/A | 3.5 | | 7.9 - 10.0' FILL: Brown f-m sand; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.5' FILL: Brown silty clay; very soft, wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | 11.5 - 12.0' No recovery; end of boring at 12.0' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-060
**DATE BEGAN:** 07/28/09
**DATE FINISHED:** 07/28/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.7 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 49 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown f-m sand, some concrete and fine gravel, trace clinker | | |
| | 2.0 | | | | | 1.5 - 3.7' FILL: Reddish brown clayey sand, some fine gravel, trace brick | | |
| | 3.0 | | | | | | | 134-SB-060-0204 collected from 3.0-3.5' bgs @ 13:35 |
| | | | | | | 3.7 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 4.3' FILL: Reddish brown/brown f-c sand, some fine gravel and clinker | 0.0 | |
| | 5.0 | | | | | 4.3 - 5.8' FILL: Brown fine sand, trace silt; dense, wet from 4.5' | | 134-SB-060-0406 collected from 4.5-5.0' bgs @ 13:40 |
| | 6.0 | | | | | 5.8 - 9.0' FILL: Brown f-m sand, trace silt from 7.7'; compact, wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 1.0 | | | 0.0 | 134-SB-060-0608 collected from 7.5-8.0' bgs @ 13:45 |
| | 9.0 | | | | | 9.0 - 10.0' No recovery; end of boring at 10.0' | | |
| | 10.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-061
**DATE BEGAN:** 07/29/09
**DATE FINISHED:** 07/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | | | |
| | -3.0 | R-1 | N/A | 2.0 | | -4.0 - -3.7' CONCRETE<br>-3.7 - -3.5' VOID<br>-3.5 - -1.5' FILL: Brown silty sand, trace coal and brick<br>-1.5 - 0.0' No recovery | 0.0 | Field Map #104; boring located in warehouse 4 ft above parking lot grade |
| | -2.0 | | | | | | | |
| | -1.0 | | | | | | | |
| | 0.0 | R-2 | N/A | 3.5 | | 0.0 - 3.3' FILL: Brown silty sand, trace coal and brick; some wood from 3.0-3.2'; wet from 1.5' | 0.0 | 134-SB-061-0002 collected from 0.0-0.5' bgs @ 9:15 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 3.3 - 3.5' FILL: Dark brown f-m gravel and clinker, some f-c sand; wet | | 134-SB-061-0204 collected from 2.5-3.0' bgs @ 9:20 |
| | 3.0 | | | | | | | |
| | 4.0 | R-3 | N/A | 4.0 | | 3.5 - 4.0' No recovery<br>4.0 - 4.7' FILL: Dark brown f-c gravel and clinker, some f-c sand; wet<br>4.7 - 6.5' FILL: Brown silty clay; firm, wet | 0.0 | |
| | 5.0 | | | | | | | 134-SB-061-0406 collected from 5.0-5.5' bgs @ 9:25 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 10.0' FILL: Brown f-m sand, some silt nodules; wet | | 134-SB-061-0608 collected from 7.5-8.0' bgs @ 9:30 |
| | 8.0 | R-4 | N/A | 3.0 | | | 0.0 | 134-SB-061-0810 collected from 8.0-8.5' bgs @ 9:40 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Brown silty clay; firm to soft, wet | | 134-SB-061-1012 collected from 10.5-11.0' bgs @ 9:45 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | R-5 | N/A | 4.0 | | 12.0 - 14.5' FILL: Brown silty clay, some f-m sand from 13.1-13.3'; wet | 0.0 | |
| | 13.0 | | | | | | | 134-SB-061-1214 collected from 13.5-14.0' bgs @ 9:55 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 14.5 - 16.0' OL: Black/dark olive brown (2.5YR 2.5/1 to 3/3) clayey silt, soft; end of boring at 16.0' | | 134-SB-061-1416 collected from 15.5-16.0' bgs @ 10:00 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-062
**DATE BEGAN:** 07/29/09
**DATE FINISHED:** 07/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 1.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.5' CONCRETE | | Field Map #86; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | R-1 | N/A | 3.2 | | -3.5 - -3.2' VOID | 0.0 | Refusal at 4 ft bgs due to wood; moved 2 ft NE of #86 |
| | -2.0 | | | | | -3.2 - 4.0' FILL: Brown/yellowish brown silty sand; trace fine gravel, brick and coal; wet from 1.0' | | 134-SB-062-0402AG collected from 3.0-2.5' ags @ 10:40 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| | -1.0 | | | | | | | |
| | 0.0 | R-2 | N/A | 4.0 | | | 0.0 | |
| | 1.0 | | | | | | | 134-SB-062-0200AG collected from 1.0-0.5' ags @ 10:45 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | 134-SB-062-0002 collected from 1.5-2.0' bgs @ 10:55 |
| | 4.0 | R-3 | N/A | 3.5 | | 4.0 - 5.2' FILL: Brown silty sand, some f-m gravel and wood; loose, wet | 0.0 | 134-SB-062-0204 collected from 3.5-4.0' bgs @ 11:00 |
| | 5.0 | | | | | 5.2 - 6.5' FILL: Brown silty clay; firm, wet | | 134-SB-062-0406 collected from 5.5-6.0' bgs @ 11:05 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 7.5' FILL: Brown f-m sand, wet | | 134-SB-062-0608 collected from 7.0-7.5' bgs @ 11:10 |
| | 8.0 | R-4 | N/A | 2.5 | | 7.5 - 8.0' No recovery | 0.0 | 134-SB-062-0810 collected from 8.0-8.5' bgs @ 11:20 |
| | 9.0 | | | | | 8.0 - 9.8' FILL: Brown f-m sand, wet | | |
| | 10.0 | | | | | 9.8 - 10.5' FILL: Brown silty clay; very soft, moist | | 134-SB-062-1012 collected from 10.0-10.5' bgs @ 11:25 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | R-5 | N/A | 4.0 | | 12.0 - 14.5' FILL: Brown silty clay; very soft, moist | 0.0 | 134-SB-062-1214 collected from 12.0-12.5' bgs @ 11:35; DUP @ 11:37 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 14.5 - 16.0' OL: Black/dark olive brown (2.5YR 2.5/1 to 3/3) clayey silt, trace organic material; end of boring at 16.0' | | 134-SB-062-1416 collected from 15.5-16.0' bgs @ 11:40 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-063
**DATE BEGAN:** 07/29/09
**DATE FINISHED:** 07/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 1.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.3' CONCRETE | | Field Map #92; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | R-1 | N/A | 2.0 | | -3.3 - -3.0' VOID | 0.0 | |
| | -2.0 | | | | | -3.0 - -1.0' FILL: Brown silty sand; trace fine gravel, concrete and coal | | 134-SB-063-0402AG collected from 3.0-2.5' ags @ 13:05 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| | -1.0 | | | | | -1.0 - 0.0' No recovery | | |
| | 0.0 | R-2 | N/A | 4.0 | | 0.0 - 2.0' FILL: Brown silty sand; trace fine gravel, concrete and coal; trace yellow COPR from 1.8'; wet from 1.0' | 0.0 | 134-SB-063-0200AG collected from 1.5-1.0' ags @ 13:10 for VOCs, SVOCs, TAL Metals, and Hex. Chromium |
| ▽ | 1.0 | | | | | | | |
| | 2.0 | | | | | | | 134-SB-063-0002 collected from 1.5-2.0' bgs @ 13:15 |
| | 3.0 | | | | | 2.0 - 4.5' FILL: Very dark grayish brown silt, some to trace fine sand; some yellow COPR from 2.0-2.3'; some white COPR from 3.9'; trace yellow COPR from 4.0'; stiff, wet | | 134-SB-063-0204 collected from 2.0-2.5' bgs @ 13:20 |
| | 4.0 | R-3 | N/A | 2.8 | | | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Brown silty sand and f-m gravel; wet | | 134-SB-063-0406 collected from 4.0-4.5' bgs @ 13:30 |
| | 6.0 | | | | | 5.0 - 5.4' FILL: Brown silt; stiff, moist | | |
| | 7.0 | | | | | 5.4 - 6.0' FILL: Very dark grayish brown silty clay; soft, wet | | 134-SB-063-0608 collected from 6.0-6.5' bgs @ 13:35 |
| | 8.0 | R-4 | N/A | 3.0 | | 6.0 - 6.8' FILL: Brown f-m sand, wet | 0.0 | |
| | 9.0 | | | | | 6.8 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 9.2' FILL: Brown f-m sand, trace shells; wet | | 134-SB-063-0810 collected from 9.5-10.0' bgs @ 13:45 |
| | 11.0 | | | | | 9.2 - 10.5' FILL: Brown silty clay; very soft | | 134-SB-063-1012 collected from 10.5-11.0' bgs @ 13:50 |
| | 12.0 | R-5 | N/A | 4.0 | | 10.5 - 11.0' FILL: Brown silty sand; wet | 0.0 | 134-SB-063-1214 collected from 12.0-12.5' bgs @ 14:00 |
| | 13.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 14.0 | | | | | 12.0 - 14.0' FILL: Brown/yellow clayey silt and COPR; moist | | |
| | 15.0 | | | | | 14.0 - 16.0' OL: Black/dark olive brown (2.5YR 2.5/1 to 3/3) clayey silt, trace organic material from 15.5'; end of boring at 16.0' | | 134-SB-063-1416 collected from 15.5-16.0' bgs @ 14:10 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-064
**DATE BEGAN:** 07/29/09
**DATE FINISHED:** 07/29/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | | | |
| | -3.0 | R-1 | N/A | 3.2 | | -4.0 - -3.5' CONCRETE<br>-3.5 - -3.2' VOID<br>-3.2 - 0.0' FILL: Brown silty sand; trace f-m gravel, brick and coal | 0.0 | Field Map #88; boring located in warehouse 4 ft above parking lot grade |
| | -2.0 | | | | | | | |
| | -1.0 | | | | | | | |
| | 0.0 | R-2 | N/A | 3.0 | | 0.0 - 2.0' FILL: Reddish brown/brown silty sand, some brick, trace fine gravel; dense | 0.0 | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark brown silt; very stiff, wet | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Reddish brown sandy silt, some wood; wet | | |
| | 4.0 | R-3 | N/A | 3.0 | | 3.0 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Wood, some silt and f-m gravel; wet | | |
| | 6.0 | | | | | 4.5 - 5.3' FILL: Brown silty clay, wet | | |
| | 7.0 | | | | | 5.3 - 7.0' FILL: Dark brown/brown f-m sand, trace silt; wet | | |
| | 8.0 | R-4 | N/A | 2.3 | | 7.0 - 8.0' No recovery | 0.0 | |
| | 9.0 | | | | | 8.0 - 9.5' FILL: Dark brown/brown f-m sand, trace silt; wet | | |
| | 10.0 | | | | | 9.5 - 10.3' FILL: Brown silty clay; very soft, moist | | |
| | 11.0 | | | | | 10.3 - 12.0' No recovery | | |
| | 12.0 | R-5 | N/A | 2.5 | | 12.0 - 13.5' FILL: Brown silty clay; stiff and varved from 12.5' | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 13.5 - 14.5' OL: Black (2.5YR 2.5/1) clayey silt; stiff, moist | | 134-SB-064-1416 collected from 14.0-14.5' bgs @ 15:05 |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring at 16.0' | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-065
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 0.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -4.0 | | | | | -4.0 - -3.3' CONCRETE | | Field Map #112; boring located in warehouse 4 ft above parking lot grade |
| | -3.0 | R-1 | N/A | 3.1 | | -3.3 - -3.1' VOID | 0.0 | |
| | -2.0 | | | | | -3.1 - 0.5' FILL: Brown silty sand, some f-m gravel; trace clinker, coal and brick; wet at grade | | |
| | -1.0 | | | | | | | |
| | 0.0 | R-2 | N/A | 0.5 | | | 0.0 | 134-SB-065-0002 collected from 0.0-0.5' bgs @ 7:55 |
| | 1.0 | | | | | 0.5 - 4.0' No recovery | | |
| | 2.0 | | | | | | | Poor recovery in R-2 due to coarse gravel in macrocore tip |
| | 3.0 | | | | | | | |
| | 4.0 | R-3 | N/A | 3.5 | | 4.0 - 4.5' FILL: Dark gray silt, trace fine gravel, sand, and yellow COPR; wet | 0.0 | 134-SB-065-0406 collected from 4.0-4.5' bgs @ 8:05 |
| | 5.0 | | | | | 4.5 - 5.7' FILL: Brown clayey silt, trace f-m gravel; stiff, wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 5.7 - 7.5' FILL: Brown f-m sand, wet | | |
| | 8.0 | R-4 | N/A | 2.8 | | 7.5 - 8.0' No recovery | 0.0 | 134-SB-065-0608 collected from 7.0-7.5' bgs @ 8:10<br>134-SB-065-0810 collected from 8.0-8.5' bgs @ 8:25 |
| | 9.0 | | | | | 8.0 - 9.4' FILL: Brown f-m sand, wet | | |
| | 10.0 | | | | | 9.4 - 10.8' FILL: Brown clayey silt, some lenses of fine sand; wet | | 134-SB-065-1012 collected from 10.0-10.5' bgs @ 8:30 |
| | 11.0 | | | | | 10.8 - 12.0' No recovery | | |
| | 12.0 | R-5 | N/A | 2.0 | | 12.0 - 12.5' FILL: Brown clayey silt, some lenses of fine sand; wet | 0.0 | |
| | 13.0 | | | | | 12.5 - 13.5' FILL: Brown clayey silt; white/green COPR from 12.8-13.3; stiff | | 134-SB-065-1214 collected from 12.8-13.3' bgs @ 8:40 |
| | 14.0 | R-6 | N/A | 2.0 | | | 0.0 | |
| | 15.0 | | | | | 13.5 - 14.0' OH: Very dark grayish brown (10YR 3/2) clayey silt, trace organic material; stiff, moist | | 134-SB-065-1416 collected from 15.5-16.0' bgs @ 8:50 |
| | 16.0 | | | | | 14.0 - 16.0' OL: Black/dark olive brown (2.5YR 2.5/1 to 3/3) clayey silt, some organic material; stiff, moist; end of boring at 16.0' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-066
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 95 |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Brown silty sand, some f-m gravel; trace brick, clinker and coal; moist | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Brown f-m sand, trace silt; wet from 2.5' | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 10.0' FILL: Brown f-c sand, trace silt; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.2 | | | 0.0 | 134-SB-066-0608 collected from 7.5-8.0' bgs @ 10:25; DUP @ 10:27 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 10.2' FILL: Brown fine sand, trace silt; compact, wet | | 134-SB-066-0810 collected from 9.5-10.0' bgs @ 10:35; HOLD |
| | 11.0 | | | | | 10.2 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-067
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 96 |
| | 1.0 | | | | | 0.5 - 3.0' FILL: Brown silty sand, some fine gravel, trace brick, concrete, clinker and coal; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 10.0' FILL: Brown f-c sand, trace silt; stiff silt from 1.5-1.7'; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.0 | | | 0.0 | 134-SB-067-0608 collected from 7.5-8.0' bgs @ 10:50 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 134-SB-067-0810 collected from 9.5-10.0' bgs @ 11:00; HOLD |
| | 11.0 | | | | | 10.0 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-068
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 1.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 103 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Dark brown f-c sand, some f-m clinker and gravel, trace brick and silt; wet from 1.0' | | |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Brown f-c sand, trace silt, some reddish brown silt and clay from 2.6-3.0'; wet | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | R-2 | N/A | 4.0 | | 4.0 - 10.5' FILL: Brown f-c sand, trace fine gravel from 4.0-4.3'; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.5 | | | 0.0 | 134-SB-068-0608 collected from 7.5-8.0' bgs @ 11:15; HOLD |
| | 9.0 | | | | | | | 134-SB-068-0810 collected from 9.5-10.0' bgs @ 11:25 |
| | 10.0 | | | | | | | 134-SB-068-1012 collected from 10.0-10.5' bgs @ 11:30; HOLD |
| | 11.0 | | | | | 10.5 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-069
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 102 |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Concrete | | |
| | | | | | | 0.8 - 1.8' FILL: Reddish brown silt, some f-m sand and gravel, trace brick and coal | | |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Brown f-m sand, trace silt; wet from 2.0' | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 8.4' FILL: Brown f-c sand, few silt lenses; wet | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.7 | | | 0.0 | 134-SB-069-0608 collected from 7.5-8.0' bgs @ 11:55; HOLD |
| | 9.0 | | | | | 8.4 - 10.7' FILL: Black/brown silty clay; very soft, wet | | 134-SB-069-0810 collected from 9.5-10.0' bgs @ 12:05 |
| | 10.0 | | | | | | | 134-SB-069-1012 collected from 10.0-10.5' bgs @ 12:10; HOLD |
| | 11.0 | | | | | 10.7 - 12.0' No recovery; end of boring at 12.0' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-070
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map # 100 |
| | 1.0 | | | | | 0.5 - 0.9' FILL: Concrete | | |
| | 2.0 | | | | | 0.9 - 1.2' FILL: Black/brown f-m sand and fine clinker | | |
| | 3.0 | | | | | 1.2 - 2.3' FILL: Reddish brown sandy silt, trace fine gravel; white COPR from 2.1-2.3' | | |
| | 4.0 | R-2 | N/A | 4.0 | | 2.3 - 3.5' FILL: Brown f-c sand, stiff silt from 2.5-2.6' and 3.3-3.4'; wet from 2.5' | 0.0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | 0.1 | |
| | 6.0 | | | | | 4.0 - 11.0' FILL: Brown f-c sand, some silt lenses; petroleum odors and sheen from 5.0-6.0'; wet | 0.5 | |
| | 7.0 | | | | | | 3.8 | |
| | 8.0 | R-3 | N/A | 3.0 | | | 1.1 | |
| | 9.0 | | | | | | 0.4 | |
| | 10.0 | | | | | | 0.0 | |
| | 11.0 | | | | | | 0.0 | 134-SB-070-0608 collected from 6.5-7.0' bgs @ 13:10 |
| | 12.0 | | | | | | 0.0 | 134-SB-070-0810 collected from 9.5-10.0' bgs @ 13:15; HOLD |
| | | | | | | 11.0 - 12.0' No recovery; end of boring at 12.0' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 134, 60 Kellog St., Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-071
**DATE BEGAN:** 08/11/09
**DATE FINISHED:** 08/11/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.2' ASPHALT | 0.0 | Field Map # 98 |
| | 1.0 | | | | | 0.2 - 1.5' FILL: Brown f-c sand and f-m gravel | | |
| | 2.0 | | | | | 1.5 - 6.0' FILL: Reddish brown silt, thinly laminated, some lenses of f-c sand, trace fine gravel from 3.8'; very stiff, wet from 3.0' | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | | 0.0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 10.0' FILL: Brown f-c sand, few silt nodules, trace shells; wet; end of boring at 10.0' | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.0 | | | 0.0 | 134-SB-071-0608 collected from 7.5-8.0' bgs @ 8:30; HOLD |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 134-SB-071-0810 collected from 9.5-10.0' bgs @ 8:40; DUP @ 8:42 |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-072
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' ASPHALT: Asphalt and tar | 0 | |
| | 1.0 | | | | | 0.3 - 1.0' FILL: Bronw fine to medium silty sand with some fine to medium gravel, trace wood and coal | | |
| | 2.0 | | | | | 1.0 - 3.3' FILL: Red fine to medium silty sand with motteling of grey silt and some clay, trace fine to medium gravel and coal, moist, dense | | |
| | 3.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.0' FILL: Reddish brown silty sand with trace clay, wet, loose | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Black clayey silt, loose, wet | | |
| | 8.0 | S-3 | NA | 2.5 | | 7.5 - 8.0' FILL: Brown fine to medium sand, wet, loose | 0 | |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Brown fine to medium silty sand with motteling of silt, trace clay and fine gravel, wet, loose | | Sample collected 134-SB-072-0810 from 8.5-9.0 bgs @ 12:15 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | Sample collected 134-SB-072-1012 from 10.0-10.5' bgs @ 12:20 (HOLD) |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 12.3' FILL: Brown fine to medium silty sand with motteling of silt, trace clay and fine gravel, wet, loose | 0 | |
| | 13.0 | | | | | 12.3 - 12.5' OL: Brown clayey silt with some fine sand ,wet, loose | | Sample collected 134-SB-072-1214 from 13.5-13.5' bgs @ 12:25 |
| | 14.0 | | | | | 12.5 - 14.0' SM: Brown fine silty sand with trace organics, wet, loose; end of boring @ 14.0' bgs | | |

PREPARED BY: MD
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-073
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 7 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' ASPHALT: Asphalt and tar | | |
| | | | | | | 0.1 - 1.0' FILL: Brown fine to medium silty sand with fine to medium gravel, trace coal, dry, moderate dense | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Red fine to medium silty sand with fine to medium gravel, dry, very dense | | PID sensor not working properly |
| | | | | | | 1.5 - 2.0' FILL: Brown fine to medium sand with some clinker and coal. trace fine gravel, wet, dense | | |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Red silt, some fine sand, mottling of grey silt, moist, very dense | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 5.0' FILL: Brown fine silty sand with some clay, trace organics, wet, firm | | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Brown silty caly with trace organics, wet, moderately firm | | Sample collected 134-SB-073-0406 from 5.0-5.5 bgs @ 7:55 |
| | | | | | | 5.5 - 6.5' FILL: Brown fine to medium sand with motteling of clay, wet, loose | | |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 7.0' No recovery; end of boring @ 7.0' bgs | | |
| | 7.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: FP

# MACTEC Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-074
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 7 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.2' ASPHALT: Asphalt | | |
| | | | | | | 0.2 - 0.8' FILL: Brown fine to medium sand with fine to medium gravel, trace silt and brick, dry, loose | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Light brown fine to medium sand with motteling of clay and some fine to medium gravel | | PID sensor not working properly |
| | | | | | | 1.3 - 1.4' FILL: Red fine silty sand | | |
| | 2.0 | | | | | 1.4 - 1.5' CONCRETE: Concrete | | |
| | | | | | | 1.5 - 1.6' FILL: Brown fine silty sand | | |
| | | | | | | 1.6 - 1.8' CONCRETE: Concrete | | |
| | 3.0 | | | | | 1.8 - 2.5' FILL: Dark brown fine to coarse sand, some clinker and coal, trace fine gravel and silt, wet, loose | | |
| | | | | | | 2.5 - 3.0' FILL: Red fine silty sand with mottling of grey silt and some fine to medium gravel, moist, very dense | | |
| | 4.0 | S-2 | NA | 2.5 | | 3.0 - 4.0' No recovery | | |
| | | | | | | 4.0 - 4.8' FILL: Reddish brown sandy silt, moist, firm | | |
| | 5.0 | | | | | 4.8 - 5.5' FILL: Brown silty clay, wet, loose | | Sample collected 134-SB-074-0406 from 5.5-6.0 bgs @ 8:15 |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Brown fine to medium sand, mottling of clay and trace fine gravel, wet, loose | | |
| | 7.0 | | | | | 6.5 - 7.0' No recovery; end of boring @ 7.0' bgs | | |

PREPARED BY: MD
CHECKED BY: FP

# MACTEC Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-075
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 7 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: Asphalt | | |
| | | | | | | 0.3 - 0.8' FILL: Brown fine to coarse sand with some fine to medium gravel, mottling of black silt, trace brick, coal, and clay | | |
| | 1.0 | | | | | 0.8 - 1.0' CONCRETE: Concrete | | PID sensor not working properly |
| | | | | | | 1.0 - 1.5' FILL: Brown fine to medium sand with mottling of red, black, and brown sand, trace fine gravel, moist, loose | | |
| | 2.0 | | | | | 1.5 - 2.3' FILL: Wood | | |
| | | | | | | 2.3 - 2.8' FILL: Reddish brown fine silty sand, some mottling of clay and trace fine gravel, moist, dense | | |
| | 3.0 | | | | | 2.8 - 3.5' FILL: Dark brown fine to coarse sand, some clinker, coal, and brick, trace organics, moist, loose | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| ▽ | 4.0 | S-2 | NA | 3 | | 4.0 - 5.0' FILL: Brown fine sandy silt, loose, wet | | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Brown silty clay, wet, loose | | Sample collected 134-SB-075-0406 from 5.5-6.0 bgs @ 8:30 |
| | | | | | | 5.5 - 7.0' FILL: Brown fine to medium sand with lenses of clay and trace fine gravel, wet, loose; End of boring @ 7.0' bgs | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-076
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6.5 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: Asphalt | | First run to 3.5' bgs |
| | | | | | | 0.3 - 0.5' CONCRETE: Concrete | | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown fine to medium silty sand, trace brick and fine to medium gravel, dry | | PID sensor not working properly |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Grey silt, trace fine gravel and coal, moist, very dense | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Reddish brown fine silty sand, trace organics and clay, wet, loose | | |
| | | | | | | 3.5 - 3.8' FILL: Concrete | | |
| | 4.0 | S-2 | NA | 3 | | 3.8 - 4.0' FILL: Dark brown fine to coarse sand, some clinker and coal, wet, loose | | Sample collected 134-SB-076-0406 from 4.0-4.5 bgs @ 8:45 |
| | | | | | | 4.0 - 4.3' FILL: Brown sandy silt, wet, firm | | |
| | 5.0 | | | | | 4.3 - 5.5' FILL: Brown silty clay, wet, moderately dense | | |
| | 6.0 | | | | | 5.5 - 6.5' FILL: Brown fine to medium sand with lenses of clay, trace fine gravel, wet, loose; End of boring @ 6.5' bgs | | |

PREPARED BY: MD
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-077

**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT

**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 7.0ft bgs
**GW DEPTH:** 3.5 ft bgs

**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: Asphalt | | |
| | | | | | | 0.3 - 0.5' FILL: Brown fine to medium sand, trace silt and fine gravel, dry | | |
| | | | | | | 0.5 - 0.8' FILL: Concrete | | |
| | 1.0 | | | | | 0.8 - 2.3' FILL: Greyish brown sandy silt, moist, dense | | PID sensor not working properly |
| | 2.0 | | | | | 2.3 - 3.0' FILL: Concrete | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown fine to medium sand, some wood and coal, trace fine to medium gravel, wet, dense | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3 | | 4.0 - 4.3' FILL: Brown fine to medium gravel, some brown fine to medium sand, wet, loose | | Sample collected 134-SB-077-0406 from 4.5-5.0 bgs @ 8:55 |
| | | | | | | 4.3 - 5.0' FILL: Brown clayey silt, trace coal, wet, loose | | |
| | 5.0 | | | | | 5.0 - 5.8' FILL: Brown silty clay, wet, loose | | |
| | 6.0 | | | | | 5.8 - 7.0' FILL: Brown fine to medium sand, some silt, trace coarse sand, wet, loose; end of boring @ 7.0' bgs | | |
| | 7.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: FP

# MACTEC Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-078
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -2.0 | S-1 | NA | 3 | | -2.0 - -1.3' FILL: Fine to medium gravel with dark brown fine to medium sand, loose, dry | 0 | |
| | -1.0 | | | | | -1.3 - -0.8' FILL: Brown fine to course sand, some fine to coarse gravel and brick, loose, dry | | |
| | 0.0 | | | | | -0.8 - 0.0' FILL: Brown fine to medium silty sand with trace brick and gravel, very dense | | |
| | 1.0 | | | | | 0.0 - 0.5' CONCRETE: Concrete | | |
| | 2.0 | S-2 | NA | 3 | | 0.5 - 1.0' FILL: Brown fine to medium sand, some brick and fine to medium gravel, trace coal, moist, dense | 0 | |
| | 3.0 | | | | | 1.0 - 2.0' No recovery | | |
| | 4.0 | | | | | 2.0 - 4.0' FILL: Brown fine to medium silty sand, some fine to medium gravel, trace concrete and brick, moist, moderate dense | | |
| | 5.0 | | | | | 4.0 - 4.2' FILL: Black sandy silt, wet, loose | | |
| | | | | | | 4.2 - 4.8' FILL: Brown silty clay with bands of black silt, wet, loose | | |
| | 6.0 | S-3 | NA | 4 | | 4.8 - 5.0' FILL: Brown fine to medium sand, trace fine gravel, wet, loose | 0 | |
| | 7.0 | | | | | 5.0 - 6.0' No recovery | | Sample collected 134-SB-078-0810 from 6.5-7.0' bgs @ 9:50 |
| | 8.0 | | | | | 6.0 - 8.5' FILL: Brown fine to medium sand, trace fine gravel, wet, loose | | Organic Odors in 6.0-10.0' sleeve |
| | 9.0 | | | | | 8.5 - 9.0' FILL: Brown silty fine sand, wet, loose | | |
| | | | | | | 9.0 - 9.5' FILL: Brown silty clay, wet, loose | | |
| | 10.0 | S-4 | NA | 3 | | 9.5 - 12.5' FILL: Brown fine to medium sand with lenses of firm clay, trace fine gravel, wet, loose | 0 | |
| | 11.0 | | | | | | | Sample collected 134-SB-078-1214 from 12.5-13.0' bgs @ 9:55 |
| | 12.0 | | | | | | | |

PREPARED BY:
CHECKED BY: QA/QC

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-078
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | S-5 | NA | 2 | | 12.5 - 13.0' FILL: Greenish-grey sand; wet, loost (COPR)<br>13.0 - 14.0' No recovery | 0 | Sample collected 134-SB-078-1416 from 14.0-14.5' bgs @ 10:00 |
| | 14.0 | | | | | 14.0 - 15.9' OL: Black clayey silt, trace organics | | |
| | 15.0 | | | | | 15.9 - 16.0' PT: Peat; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY:
CHECKED BY: QA/QC

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-079
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 1.5 ft bgs
**GW DEPTH:** NA
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 0 | | 0.0 - 0.0' No Recovery; Refusal @ 1.5' bgs | | Hit concrete at 2' bgs, moved 1' in every direction and hit concrete at 2' bgs in all locations<br><br>Moved 2' to the south, hit concrete at 2' bgs<br><br>Moved 2' to the east, hit concrete at 2' bgs<br><br>Moved 7' to the south, hit concrete at 2' bgs<br><br>Moved 10' to the south, hit concrete at 2' bgs<br><br>Moved 10' to the southwest, hit concrete at 2' bgs |
| | 1.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-080
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' CONCRETE: Concrete | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Red silty fine sand, some medium gravel; dry | | |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Black sandy silt, moist, dense | | |
| | | | | | | 0.8 - 1.3' FILL: Black fine to medium sand, some silt, trace fine to medium gravel; moist | | |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Red fine sandy silt, trace mottling of grey silty, moist, dense | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Reddish brown silty fine sand, some fine gravel, wet, moderate dense | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.25 | | 4.0 - 4.5' FILL: Brown silty sand, wet, loose | 0 | |
| | | | | | | 4.5 - 5.3' FILL: Brown sandy silt, some clay, more clay with depth, wet, loose | | |
| | 5.0 | | | | | 5.3 - 7.3' FILL: Brown fine to medium sand with lenses of clay, trace fine gravel, wet, loose | | Sample collected 134-SB-080-0608 from 6.5-7.0 bgs @ 11:15 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.3 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.5' FILL: Brown fine to medium sand with lenses of clay, trace fine gravel, wet, loose | 0 | |
| | 9.0 | | | | | 9.5 - 9.8' FILL: Black silt, trace fine gravel, wet, moderate firm | | Sample collected 134-SB-080-0810 from 9.5-10.0' bgs @ 11:20 |
| | 10.0 | | | | | 9.8 - 10.3' FILL: Grey silt, moist, dense; (possible COPR) | | |

PREPARED BY: MD
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-080
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | | | | | 10.3 - 11.0' FILL: Brown silt, wet, loose | | |
| | | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 15.3' FILL: Brown fine to medium sand, mottling of silt and clay, wet, loose | 0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | Sample collected 134-SB-080-1214 from 15.5-16.0' bgs @ 11:30 |
| | | | | | | 15.3 - 15.9' FILL: Brown clayey silt with greenish-brown motteling; (possible COPR) | | |
| | 16.0 | S-5 | NA | 2.0 | | 15.9 - 16.0' OL: Black clayey silt, some fine sand, wet, loose | 0 | |
| | | | | | | 16.0 - 16.5' PEAT: PEAT | | |
| | 17.0 | | | | | 16.5 - 17.5' OL: Black silt, trace fine sand, moist, firm | | Sample collected 134-SB-080-1416 from 16.5-17.0' bgs @ 11:35 |
| | 18.0 | | | | | 17.5 - 18.0' SW: Dark brown fine to medium sand, trace organics; transitions to light brown sand, trace silt; end of boring @ 18.0; bgs | | |

PREPARED BY: MD
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-081
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | 1.0 | | | | | 0.3 - 1.0' CONCRETE | | |
| | 2.0 | | | | | 1.0 - 1.8' FILL: Silty fine to medium sand, fine to medium gravel, trace coal and brick; dense, dry | | |
| | 3.0 | | | | | 1.8 - 2.5' FILL: Red sandy silt, trace brick and fine to medium gravel; very dense, dry | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.5 - 4.0' FILL: Fine to medium sand, fine to medium gravel, trace brick and coal | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Brown fine sandy silt, trace clay; loose, wet | | |
| | 6.0 | | | | | 5.0 - 5.5' FILL: Brown silty clay, trace fine sand; medium firm, wet | | |
| | 7.0 | | | | | 5.5 - 8.0' FILL: Brown fine to coarse sand, trace mottling of clay; wet | | Sample collected 134-SB-081-0608 from 7.0-7.5' bgs @13:00, DUP at 13:02 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Brown fine to medium sand, trace silt and mottling of clay | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 13.8' FILL: Brown silt, trace fine sand; very loose, wet | 0 | |
| | 13.0 | | | | | 13.8 - 14.3' FILL: Grayish green fine silt (possible COPR), with dark green nodules; firm, moist | | Sample collected 134-SB-081-1214 from 13.5-14.0' bgs @13:10 |
| | 14.0 | | | | | 14.3 - 15.8' OL: Black silty clay, trace fine sand and organics; loose, wet | | Sample collected 134-SB-081-1416 from 15.0-15.5' bgs @13:15 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | 15.8 - 16.0' PT: Peat; end of boring at 16' bgs | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-082
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' ASPHALT | 0 | |
| | 1.0 | | | | | 0.3 - 1.5' FILL: Brown fine to coarse sand, some fine to medium gravel, trace coal, brick, tar, and ash; medium dense, dry | | |
| | 2.0 | | | | | 1.5 - 2.8' FILL: Red silt, trace fine sand, fine to medium gravel,coal, brick, shells; black at 2.0'; firm, moist | | |
| | 3.0 | | | | | 2.8 - 3.0' FILL: Concrete | | |
| | 4.0 | S-2 | NA | 3.25 | | 3.0 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.5' FILL: Brown silt, some fine sand, trace coal; medium firm, wet | | |
| | 6.0 | | | | | 5.5 - 6.0' FILL: Black silt; loose, wet | | |
| | 7.0 | | | | | 6.0 - 7.3' FILL: Brown fine to coarse sand, lenses of clay and silt; loose, wet | | Sample collected 134-SB-082-0608 from 6.5-7.0' bgs @13:30, DUP at 13:32 |
| | 8.0 | S-3 | NA | 3.0 | | 7.3 - 8.0' : No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 10.0' FILL: Brown fine to coarse sand, lenses of clay and silt; more fine sand and trace silt with depth; loose, wet | | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Brown sandy silt; loose, wet | | |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.75 | | 12.0 - 13.5' FILL: Silt, some fine sand; very loose, wet | 0 | |
| | 13.0 | | | | | | | Sample collected 134-SB-082-1416 from 14.5-15.0' bgs @13:40, DUP at 13:42 |
| | 14.0 | | | | | 13.5 - 15.0' FILL: Greenish yellow COPR; soft,wet (harder with depth) | | |
| | 15.0 | | | | | 15.0 - 15.8' OL: Black clayey silt, fine sand, trace organics; firm, moist | | Sample collected 134-SB-082-1416 from 15.5-16.0' bgs @13:45 |
| | 16.0 | | | | | 15.8 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-083
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Sub-base; dark brown fine to medium gravel, fine to coarse sand, trace silt, coal, and brick; dry | | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Red sandy silt, trace coal and fine gravel; very dense, dry | | |
| | 2.0 | | | | | 1.0 - 1.5' FILL: Dark brown silty fine sand; very dense, moist | | |
| | 3.0 | | | | | 1.5 - 2.0' FILL: Red silty fine to medium sand, trace fine gravel; moist | | |
| | 4.0 | S-2 | NA | 3 | | 2.0 - 3.0' FILL: Black silt, some fine sand; very dense, moist | 0 | |
| | 5.0 | | | | | 3.0 - 3.4' FILL: Dark brown fine to coarse sand, some clinker, coal, brick, and ash; loose, moist | | |
| | 6.0 | | | | | 3.4 - 3.5' FILL: Reddish brown silt, trace fine sand and clay; dense, dry | | |
| | 7.0 | | | | | 3.5 - 4.0' : No recovery | | |
| | 8.0 | S-3 | NA | 3 | | 4.0 - 5.0' FILL: Reddish brown silt, trace fine sand and clay; dense, wet | 0 | |
| | 9.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, lenses of clay and silt; black from 6.5-7.0'; loose, wet | | |
| | 10.0 | | | | | 7.0 - 8.0' : No recovery | | |
| | 11.0 | | | | | 8.0 - 9.0' FILL: Light brown fine to medium sand, lenses of clay and silt; loose, wet | | |
| | 12.0 | S-4 | NA | 4 | | 9.0 - 9.3' FILL: Brown sandy silt; loose, wet | 0 | |
| | 13.0 | | | | | 9.3 - 11.0' FILL: Brown silty sand; loose, wet | | Sample collected 134-SB-083-1214 from 12.5-13.0' bgs @14:10 |
| | | | | | | 11.0 - 12.0' No recovery | | |
| | | | | | | 12.0 - 12.8' FILL: Brown silt; very loose, wet | | |
| | | | | | | 12.8 - 13.3' FILL: Grayish silt, (possible | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-083
**DATE BEGAN:** 4/22/10
**DATE FINISHED:** 4/22/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | | | | COPR) white nodules; medium firm, wet | | |
| | | | | | | 13.3 - 15.8' OL: Black silty clay, trace organics; firm, wet | | Sample collected 134-SB-083-1416 from 15.0-15.5' bgs @14:15, DUP @14:17 |
| | 15.0 | | | | | 15.8 - 16.0' PT: Peat; end of boring at 16.0' | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-084
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.2' ASPHALT | 0 | |
| | | | | | | 0.2 - 0.5' FILL: Sub-base; Brown fine to medium sand, fine to medium gravel, some silt, trace tar; loose, dry | | |
| | 1.0 | | | | | 0.5 - 1.8' FILL: Red sandy silt, yellow and orange mottling (possible COPR), fine to medium gravel, trace coal and brick; dense, dry | | |
| | 2.0 | | | | | 1.8 - 2.0' FILL: COPR material, yellowish green fine silt; dense | | |
| | 3.0 | S-2 | NA | 3.5 | | 2.0 - 2.8' FILL: Dark brown silt, trace fine to medium gravel; dense, dry | 0 | |
| | 4.0 | | | | | 2.8 - 3.3' FILL: Dark brown fine to coarse sand, some clinker, fine gravel, and coal; loose, moist | | |
| | 5.0 | | | | | 3.3 - 3.8' FILL: Red silty fine sand, trace clay; medium dense, moist | | |
| | 6.0 | | | | | 3.8 - 4.0' : No recovery | | |
| | 7.0 | S-3 | NA | 2 | | 4.0 - 4.5' FILL: Dark brown sand and silt; firm, wet | 0 | |
| | 8.0 | | | | | 4.5 - 5.0' FILL: Brown clayey silt; loose, wet | | |
| | 9.0 | | | | | 5.0 - 7.5' FILL: Brown fine to medium sand, trace silt, mottling of clay, and fine to medium gravel; wet | | |
| | 10.0 | | | | | 7.5 - 8.0' : No recovery | | |
| | 11.0 | | | | | 8.0 - 8.5' FILL: Brown fine to medium sand, trace silt, mottling of clay, and fine to medium gravel; wet | | |
| | 12.0 | S-4 | NA | 4 | | 8.5 - 8.8' FILL: Brown silt; firm | 0 | |
| | 13.0 | | | | | 8.8 - 9.8' FILL: Brown fine to medium sand, some silt; loose, wet | | |
| | | | | | | 9.8 - 10.0' FILL: Brown clayey silt; firm, wet | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-084
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | | | | 10.0 - 12.0' No recovery<br>12.0 - 15.8' OL: Black clayey silt; medium firm, wet | | Sample collected 134-SB-084-1416 from 14.5-15.0' bgs @07:50 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | 15.8 - 16.0' PT: Peat; end of boring at 16' | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-085
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 0.8' FILL: Sub-base: Fine to medium sand, some silt and fine to medium gravel, trace coal; loose, dry | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Red sandy silt, trace fine to medium gravel; dense, moist | | |
| | 2.0 | | | | | 1.3 - 1.4' FILL: COPR, gray silt, yellow-orange mottling | | |
| | 3.0 | | | | | 1.4 - 2.0' FILL: Black silt; dense, moist | | |
| | 4.0 | S-2 | NA | 2.75 | | 2.0 - 2.5' FILL: Fine to coarse sand, gray and brown mottling, some clinker, brick and fine to medium gravel | 0 | |
| | 5.0 | | | | | 2.5 - 3.0' FILL: Red silty sand, fine to medium gravel; loose, moist | | |
| | 6.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 7.0 | | | | | 4.0 - 4.5' FILL: Reddish brown sandy silt, some organics; dense, wet | | |
| | | | | | | 4.5 - 5.3' FILL: Brown clayey silt, trace fine sand; loose, wet | | |
| | 8.0 | S-3 | NA | 3 | | 5.3 - 6.8' FILL: Fine to medium sand, trace mottling of silt; loose, wet | 0 | |
| | 9.0 | | | | | 6.8 - 8.0' : No recovery | | |
| | 10.0 | | | | | 8.0 - 8.8' FILL: Fine to medium sand, trace mottling of silt; loose, wet | | |
| | 11.0 | | | | | 8.8 - 9.3' FILL: Brown silt, some fine sand; very loose, wet | | |
| | | | | | | 9.3 - 11.0' FILL: Brown fine to medium sand, trace silt; loose, wet | | |
| | 12.0 | S-4 | NA | 4 | | 11.0 - 12.0' No recovery | 0 | |
| | 13.0 | | | | | 12.0 - 12.5' FILL: Gray silt (possible COPR); very loose, wet | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-085
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | | | | 12.5 - 15.8' OL: Black clayey silt, trace organics; firm, wet | | Sample collected 134-SB-085-1416 from 15.0-15.5' bgs @08:20, DUP @08:22 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | 15.8 - 16.0' PT: Peat; end of boring at 16' | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Site 134 Old Dominion

**SITE INFO:** Honeywell SA-6 South
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-086
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Sub-base | | |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Red sandy silt, mottling of black silt; dense, dry | | |
| | 2.0 | | | | | 1.3 - 1.4' FILL: COPR, yellowish green fine sand; dense, dry | | |
| | | | | | | 1.4 - 1.5' FILL: Red sandy silt; dense, dry | | |
| | 3.0 | | | | | 1.5 - 3.8' FILL: Black silt, trace fine sand: dense, dry | | |
| | | | | | | 3.8 - 4.0' FILL: Wood | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.2' FILL: Brownish white fine sand (possible COPR); loose, wet | 0 | |
| | | | | | | 4.2 - 5.3' FILL: Brown sandy silt; firm, wet | | |
| | 5.0 | | | | | 5.3 - 6.0' FILL: Brown silt, trace fine sand; very loose, wet | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Brown fine to medium sand; loose, wet | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' : No recovery | | |
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 9.5' FILL: Brown fine to medium sand; loose, wet | 0 | |
| | 9.0 | | | | | | | |
| | | | | | | 9.5 - 10.3' FILL: Brown silt, lenses of fine sand; loose, wet | | |
| | 10.0 | | | | | 10.3 - 10.5' FILL: Silty fine sand; loose, wet | | |
| | | | | | | 10.5 - 11.3' FILL: Brown silt, mottling of fine sand; very loose, wet | | |
| | 11.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Site 134 Old Dominion

**SITE INFO:** Honeywell SA-6 South
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-086
**DATE BEGAN:** 4/23/10
**DATE FINISHED:** 4/23/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | S-4 | NA | 4 | | 11.3 - 12.0' No recovery | 0 | |
| | | | | | | 12.0 - 12.5' FILL: Gray silt (possible COPR) | | |
| | 13.0 | | | | | 12.5 - 15.9' OL: Black clayey silt, trace organics; firm, wet | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | Sample collected 134-SB-086-1416 from 15.0-15.5' bgs @08:45 |
| | | | | | | 15.9 - 16.0' PT: Peat; end of boring 16' | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-087
**DATE BEGAN:** 4/30/10
**DATE FINISHED:** 4/30/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Fine to coarse sand, some clinker, fine to medium gravel, trace brick, silt, and wood; dry | | |
| | 1.0 | | | | | 1.0 - 1.2' FILL: Brown lens of silt, trace fine sand; firm | | |
| | | | | | | 1.2 - 3.0' FILL: Fine to coarse sand with lenses of clay and silt | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 8.0' FILL: Fine to coarse sand, with lenses of clay and silt; end of boring at 8' | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | Sample collected 134-SB-087-0608 from 7.5-8.0' bgs @11:55 |

PREPARED BY: MS
CHECKED BY: FP

# MACTEC Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-088
**DATE BEGAN:** 4/30/10
**DATE FINISHED:** 4/30/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 0.8' FILL: Silty fine to medium sand and fine to medium gravel, trace coal; loose, dry | | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Brown silty sand with fine to medium gravel, trace coal, and brick (black from 1.25-1.5'); dense, moist | | |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Brown fine to medium sand with lenses of clay and silt; loose, wet at bottom | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 4 | | 4.0 - 7.8' FILL: Brown fine to medium sand, lens of brown silt from 6.25-6.5'; dense, wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | | | | | | | | Sample collected 134-SB-088-0608 from 6.5-7.0' bgs @12:45 |
| | 7.0 | | | | | | | |
| | | | | | | 7.8 - 8.0' FILL: Brown silty sand; very loose, wet | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 9.5' FILL: Brown silty sand, trace shells; very loose, wet | 0 | |
| | | | | | | | | Sample collected 134-SB-088-0810 from 8.5-9.0' bgs @12:50 |
| | 9.0 | | | | | | | |
| | | | | | | 9.5 - 10.0' : No recovery; end of boring at 10' | | |
| | 10.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Site 134 Old Dominion

**SITE INFO:** Honeywell SA-6 South
**PROJECT NO:** 3480080011
**BORING ID:** 134-SB-089
**DATE BEGAN:** 4/30/10
**DATE FINISHED:** 4/30/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.75 | | 0.0 - 0.3' ASPHALT | 0 | |
| | | | | | | 0.3 - 1.8' FILL: Brown silty sand with fine to medium gravel, trace coal; loose, dry | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.8 - 2.8' FILL: Brown silty sand, some clay, trace brick; loose, wet | | |
| | 3.0 | | | | | 2.8 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.75 | | 4.0 - 7.0' FILL: Brown fine to medium sand, trace fine to medium gravel, lens of clay from 6.0-6.25; loose, wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 134-SB-089-0608 from 7.0-7.5' bgs @11:45 |
| | 7.0 | | | | | 7.0 - 7.8' FILL: Brown silty fine to medium sand; loose, wet | | |
| | 8.0 | | | | | 7.8 - 8.0' : No recovery; end of boring at 8' | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell Study Area-6 South

**SITE INFO:** Site 134 Old Dominion
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-090
**DATE BEGAN:** 4/30/10
**DATE FINISHED:** 4/30/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.3' : Topsoil, grass | 0 | |
| | | | | | | 0.3 - 1.0' FILL: Concrete | | |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Black fine to coarse sand, some clinker, trace coal | | |
| | 2.0 | | | | | 1.3 - 1.5' FILL: Gray fine silt (possible COPR) | | |
| | | | | | | 1.5 - 1.6' FILL: Concrete | | |
| | 3.0 | | | | | 1.6 - 1.8' FILL: Fine to coarse sand, some clinker; loose, moist | | |
| | | | | | | 1.8 - 1.9' FILL: Black clayey silt, some fine sand; loose, moist | | |
| | 4.0 | S-2 | NA | 3.5 | | 1.9 - 2.0' FILL: Brown silt | 0 | |
| | | | | | | 2.0 - 2.2' FILL: Brown fine to medium sand | | |
| | 5.0 | | | | | 2.2 - 2.5' FILL: Brown lens of silt; dense | | |
| | | | | | | 2.5 - 4.0' FILL: Brown fine to medium sand and lenses of silt, trace organics; loose, wet at 3.5' | | |
| | 6.0 | | | | | 4.0 - 7.5' FILL: Brown fine to medium sand, lens of silt, trace clay; loose, wet | | |
| | 7.0 | | | | | | | Sample collected 134-SB-090-0608 from 7.0-7.5' bgs @12:25 |
| | | | | | | 7.5 - 10.0' : No recovery; end of boring at 10' | | |
| | 8.0 | S-3 | NA | 0 | | | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-091
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' FILL: Brown silty sand; moist | 0 | +4-0 Slab for teal building (No recovery) |
| | | | | | | 0.5 - 2.0' FILL: Concrete | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.5' FILL: Red brown silt; moist | 0 | |
| | | | | | | 4.5 - 7.0' FILL: Light brown fine to medium sand, lenses of red brown silt | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.0' FILL: Light brown fine to medium sand, lenses of red brown silt | 0 | |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Light gray silt; potential COPR | | Sample collected 134-SB-091-0810 from 9.0-9.5' @14:05 |
| | | | | | | 9.5 - 10.5' FILL: Red brown silt; dense | | |
| | 10.0 | | | | | | | |
| | | | | | | 10.5 - 11.0' FILL: Black/light brown clayey silt | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-091
**DATE BEGAN:** 5/24/10
**DATE FINISHED:** 5/24/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | S-4 | NA | 3.0 | | 11.0 - 12.0' No recovery | 0 | Sample collected 134-SB-091-1214 from 12.5-13.0' @14:10 |
| | 12.0 | | | | | 12.0 - 13.0' FILL: Black/light brown clayey silt, light green mottling | | |
| | 13.0 | | | | | 13.0 - 14.0' FILL: Black clayey silt, organics | | |
| | 14.0 | | | | | 14.0 - 14.8' FILL: Black clayey silt | | Sample collected 134-SB-091-1416 from 14.0-14.5' @14:15 HOLD |
| | | | | | | 14.8 - 15.0' PT: Peat | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery; end of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-092
**DATE BEGAN:** 5/25/10
**DATE FINISHED:** 5/25/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.8' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Black silt, trace fine to medium gravel; dense; moist | | |
| | 2.0 | | | | | 1.8 - 2.0' FILL: Concrete | | |
| | | | | | | 2.0 - 2.3' FILL: Black silt | | |
| | 3.0 | | | | | 2.3 - 3.5' FILL: Red silty sand; moderate dense; wet | | |
| | | | | | | 3.5 - 3.8' FILL: Dark brown fine to medium silty sand, trace clinker, trace coal; firm; moist | | |
| | 4.0 | | | | | 3.8 - 4.0' No recovery | | |
| | | S-2 | NA | 2.0 | | 4.0 - 5.0' FILL: Brown silty clay, trace fine sand; firm; wet | 0 | |
| | 5.0 | | | | | 5.0 - 5.5' FILL: Black fine to medium sand; loose; wet | | Sample collected 134-SB-092-0406 from 5.0-5.5' @8:10 |
| | | | | | | 5.5 - 6.0' FILL: Gray/brown fine to medium sand; loose; wet; end of boring at 6.0' bgs. | | |
| | 6.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-093
**DATE BEGAN:** 5/25/10
**DATE FINISHED:** 5/25/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.8' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.8 - 2.8' FILL: Reddish brown silty fine to medium sand, trace fine to medium gravel, trace clay, trace coal; dense; moist | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.8 - 3.3' FILL: Dark brown/black silty fine to medium sand, some clinker, coal, fine to medium gravel,; dense; moist | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.3 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Brown fine to medium clayey sand, some silt, trace fine gravel; moderate dense; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.3' FILL: Reddish brown fine to medium sand; wet | 0 | |
| | 9.0 | | | | | 9.3 - 11.0' FILL: Brown/black silty clay, trace organics; firm; wet | | Sample collected 134-SB-093-0810 from 9.0-9.5' @7:45 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.5 | | 12.0 - 13.0' FILL: Reddish brown silt, trace fine sand | 0 | |
| | 13.0 | | | | | 13.0 - 13.5' FILL: Greenish gray silt; COPR | | Sample collected 134-SB-093-1214 from 13.0-13.5' @7:50; DUP at 7:52 |
| | 14.0 | | | | | 13.5 - 15.3' OL: Black silty clay; firm; wet | | |
| | 15.0 | | | | | 15.3 - 15.5' PT: Brown peat; moist | | Sample collected 134-SB-093-1416 from 15.0-15.5' @7:55 |
| | 16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16.0' bgs. | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-094
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Dark brown/gray silty sand, gravel, coal | | |
| | 2.0 | | | | | 1.5 - 2.8' FILL: Red brown silt, brick | | |
| | 3.0 | | | | | 2.8 - 3.0' FILL: Red brown silt, fine to coarse gravel | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 5.0' FILL: Light brown silt, trace fine sand | 0 | Sample collected 134-SB-094-0406 from 4.5-5.0' @7:55 |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Light brown fine to medium sand; wet; end of boring at 6.0' bgs. | | |
| | 6.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-095
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** NE
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.3' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 1.3 - 2.3' FILL: Concrete | | |
| | 2.0 | | | | | 2.3 - 3.0' FILL: Dark brown silty fine sand, some coal, clinker, trace medium gravel; medium dense; moist | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Brown clayey silt; dense; moist | | Sample collected 134-SB-095-0204 from 3.0-3.5' @8:10 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.75 | | 4.0 - 4.5' FILL: Dark brown fine to medium silty sand, trace brick, some fine gravel; loose; moist | 0 | |
| | | | | | | 4.5 - 4.6' FILL: Concrete | | |
| | 5.0 | | | | | 4.6 - 7.8' FILL: Brown fine to medium sand, lenses of silty clay, trace organics, trace fine gravel; medium dense; moist | | Sample collected 134-SB-095-0406 from 5.0-5.5' @8:15 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 134-SB-095-0608 from 7.0-7.5' @8:20 |
| | 8.0 | | | | | 7.8 - 8.0' No recovery; end of boring at 8.0' bgs. | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-096
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Concrete, brick | | |
| | | | | | | 1.3 - 3.0' FILL: Dark brown silt, some brick, trace fine brown sand; loose; moist | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | Sample collected 134-SB-096-0204 from 3.0-3.5' @8:30 |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Brown silty clay; dense; moist | 0 | |
| | | | | | | 4.5 - 7.5' FILL: Brown fine to medium sand, trace lenses of silty clay, trace fine gravel, trace organics; loose; wet | | Sample collected 134-SB-096-0406 from 4.5-5.0' @8:35 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 134-SB-096-0608 from 6.5-7.0' @8:40 |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery; end of boring at 8.0' bgs. | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-097
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.8' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Reddish brown fine to medium sand, some fine to medium gravel, some glass, trace silt and clay; loose; gravel in tip | | Sample collected 134-SB-097-0002 from 1.5-2.0' @8:45 |
| | 2.0 | | | | | 2.0 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.5' FILL: Red brown silt, trace fine sand | 0 | |
| | 5.0 | | | | | 4.5 - 6.0' FILL: Light brown/brown fine sand, red brown silt lenses, fine gravel; wet | | Sample collected 134-SB-097-0406 from 4.5-5.0' @8:50 |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Light brown/brown fine sand; wet | | Sample collected 134-SB-097-0608 from 6.5-7.0' @8:55 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.5' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 134-SB-097-0810 from 8.5-9.0' @9:00 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 11.0' FILL: Light brown fine to coarse sand, trace fine gravel; wet | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' FILL: Brown/light brown fine to coarse sand, lenses of red brown silt; wet | 0 | Sample collected 134-SB-097-1214 from 12.5-13.0' @9:05 |
| | 13.0 | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-098
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.3' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 0.3 - 2.5' FILL: Brown fine to medium silty sand, some fine to medium gravel and brick; loose | | Sample collected 134-SB-098-0002 from 1.0-1.5' @9:10 |
| | 2.0 | | | | | 2.5 - 2.8' FILL: Brick | | |
| | 3.0 | | | | | 2.8 - 3.8' FILL: Brown fine to medium sand, lenses of red brown and light brown silt, trace coal | | Sample collected 134-SB-098-0204 from 3.0-3.5' @9:15 |
| | 4.0 | S-2 | NA | 4.0 | | 3.8 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.3' FILL: Brown fine to medium sand, lenses of red brown and light brown silt, trace coal | | Sample collected 134-SB-098-0406 from 4.5-5.0' @9:20 |
| | 6.0 | | | | | 4.3 - 8.0' FILL: Brown fine to medium sand, trace lenses of brown silty clay, red brown silty clay; loose; wet | | |
| | 7.0 | | | | | | | Sample collected 134-SB-098-0608 from 7.0-7.5' @9:25 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Gray/brown fine to medium sand, trace lenses of brown silty clay, red brown silty clay; loose; wet | 0 | Sample collected 134-SB-098-0810 from 8.0-8.5' @9:30 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 134-SB-098-1012 from 10.0-10.5' @9:35 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' FILL: Gray/brown fine to medium sand, trace lenses of brown silty clay, red brown silty clay; loose; wet | 0 | Sample collected 134-SB-098-1214 from 12.5-13.0' @9:40 |
| | 13.0 | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-099
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, coal, glass | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Dark brown silt, light yellow fine to coarse sand, trace clinker | | Sample collected 134-SB-099-0002 from 1.0-1.5' @10:20 |
| | 2.0 | | | | | 1.5 - 2.3' FILL: Dark brown silt with fine to coarse sand, light yellow fine to coarse sand, trace clinker | | |
| | 3.0 | | | | | 2.3 - 3.0' FILL: Red brown fine to medium sand, brick | | Sample collected 134-SB-099-0204 from 3.0-3.5' @10:25 |
| | | | | | | 3.0 - 3.5' FILL: Red brown/light brown silt | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.5 - 4.0' No recovery | 0 | |
| | | | | | | 4.0 - 4.5' FILL: Red brown/light brown silt, black clayey silt; moist | | Sample collected 134-SB-099-0406 from 4.5-5.0' @10:30 |
| | 5.0 | | | | | 4.5 - 7.5' FILL: Light brown/brown fine to coarse sand, lenses of red brown silt throughout; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | Sample collected 134-SB-099-0608 from 7.0-7.5' @10:35; DUP at 10:37 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 9.3' FILL: Light brown/brown fine to coarse sand, lenses of red brown silt throughout; wet | 0 | |
| | 9.0 | | | | | | | Sample collected 134-SB-099-0810 from 8.5-9.0' @10:40 |
| | | | | | | 9.3 - 11.0' FILL: Light brown clayey silt; soft; saturated | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-099
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | S-4 | NA | 3.5 | | 11.0 - 11.5' FILL: Light brown/red brown silt, trace fine sand; wet | 0 | Sample collected 134-SB-099-1012 from 11.0-11.5' @10:45 |
| | 12.0 | | | | | 11.5 - 12.0' No recovery | | |
| | | | | | | 12.0 - 13.5' FILL: Brown/light gray clayey silt; very moist | | |
| | 13.0 | | | | | | | Sample collected 134-SB-099-1214 from 13.0-13.5' @10:50 |
| | | | | | | 13.5 - 14.0' FILL: Brown/light gray clayey silt, organics; very moist | | |
| | 14.0 | | | | | 14.0 - 14.8' OL: Black clayey silt; very moist | | |
| | | | | | | 14.8 - 15.3' OL: Gray clayey silt, organics; very moist | | Sample collected 134-SB-099-1416 from 14.5-15.0' @10:55 |
| | 15.0 | | | | | 15.3 - 15.5' PT: Brown peat; moist | | |
| | 16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16.0' bgs. | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-100
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown silty sand, gravel, glass | | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Black silt, fine to medium sand, trace coal | | Sample collected 134-SB-100-0002 from 1.5-2.0 @11:00 |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark brown silty sand, clinker, gravel; wet | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Red brown fine to coarse sand, silt, brick | | Sample collected 134-SB-100-0204 from 3.0-3.5' @11:05 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Light brown clayey silt, trace organics; moist | 0 | Sample collected 134-SB-100-0406 from 4.5-5.0' @11:10 |
| ▽ | 5.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to coarse sand; wet | | |
| | 6.0 | | | | | | | Sample collected 134-SB-100-0608 from 6.5-7.0' @11:15; DUP at 11:17 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 8.5' FILL: Light brown fine to coarse sand; silt | 0 | Sample collected 134-SB-100-0810 from 8.0-8.5' @11:20 |
| | | | | | | 8.5 - 10.5' FILL: Light brown fine to coarse sand | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 134-SB-100-1012 from 10.0-10.5' @11:25 |
| | | | | | | 10.5 - 12.0' FILL: No recovery | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-100
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | S-4 | NA | 3.5 | | 12.0 - 13.5' FILL: Light brown silt; loose; saturated | 0 | Sample collected 134-SB-100-1214 from 13.0-13.5' @11:30 |
| | 12.0 | | | | | | | |
| | 13.0 | | | | | 13.5 - 14.0' FILL: Light brown clayey silt; very moist | | |
| | 14.0 | | | | | 14.0 - 15.0' OL: Black clayey silt; moist | | |
| | 15.0 | | | | | 15.0 - 15.5' PT: Dark brown peat; moist | | Sample collected 134-SB-100-1416 from 15.0-15.5' @11:35 |
| | 16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16.0' bgs. | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-101
**DATE BEGAN:** 8/6/10
**DATE FINISHED:** 8/6/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt, gravel | 0 | |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Red brown silt; gravel, brick, trace coal | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Red brown silt; gravel, brick, concrete, trace coal | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine san, trace silt; wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Black clayey silt; wet | | Sample collected 134-SB-101-0002 from 7.0-7.5 @8:00 |
| | 8.0 | | | | | 7.5 - 8.0' No recovery; end of boring at 8.0' bgs. | | |

PREPARED BY: MD
CHECKED BY: BS

# Honeywell SA-6 South

**SITE INFO:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-111
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt, gravel | 0 | |
| | | | | | | 0.5 - 3.0' FILL: Brown silt, gravel, trace coal | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Red brown clayey silt, lenses of fine to medium sand; wet | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, gravel from 4.0 - 6.0'; wet | 0 | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring at 8.0' bgs. | | Sample collected 134-SB-111-0608 from 6.5-7.0' @8:45 |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: FP

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-112
**DATE BEGAN:** 3/25/2011
**DATE FINISHED:** 3/25/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 3.25 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.5' ASPHALT | 0 | |
| | | | | | | 0.5 - 1.5' FILL: Brown fine to medium silty sand, some fine to medium gravel, trace organic material; dense, moist | | |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 3.3' FILL: Reddish brown fine to medium silty sand, trace coal, brick and organic material; dense, wet @ 3.25' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Reddish brown clayey silt, trace organic material and fine sand; wet | 0 | |
| | 5.0 | | | | | 5.0 - 6.5' FILL: Grey silt; soft, wet | | |
| | 6.0 | | | | | | | |
| | | | | | | 6.5 - 7.0' FILL: Greyish brown fine to medium sand; loose, wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 9.0' FILL: Greyish brown fine to medium sand; loose, wet | 0 | Sample collected 134-SB-112-0810 from 8.5-9.0' @ 9:12; DUP @ 9:15 |
| | 9.0 | | | | | 9.0 - 9.5' FILL: Greyish brown fine silty sand; loose, wet | | |
| | 10.0 | | | | | 9.5 - 10.0' No recovery; end of boring @ 10.0' | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134
**PROJECT NO:** 3480050143
**BORING ID:** 134-SB-113
**DATE BEGAN:** 3/25/2011
**DATE FINISHED:** 3/25/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** G. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.5' ASPHALT | 0 | |
| | 1.0 | | | | | 0.5 - 0.8' CONCRETE | | |
| | 2.0 | | | | | 0.8 - 2.8' FILL: Reddish grey to grey silt, some fine sand, trace fine to medium gravel and organic material; dense, moist | | |
| | 3.0 | | | | | 2.8 - 3.0' FILL: Dark grey fine to medium sand, some clinker and coal | | |
| | 4.0 | S-2 | NA | 4.0 | | 3.0 - 3.3' FILL: Reddish brown silty clay, trace fine gravel; dense, wet | 0 | |
| | 5.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 5.5' FILL: Reddish brown silt, trace clay; dense, wet | | |
| | 7.0 | | | | | 5.5 - 9.5' FILL: Greyish brown fine to medium sand, lenses of reddish brown silty clay, trace fine gravel; loose, wet | | |
| | 8.0 | S-3 | NA | 2.5 | | | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.5' FILL: Reddish brown silt; soft, wet | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 12.5' FILL: Reddish brown silt; soft, wet | 0 | |
| | 13.0 | | | | | 12.5 - 13.5' FILL: Greenish grey silt (COPR) | | |
| | 14.0 | | | | | 13.5 - 15.8' OL: Dark grey silt | | |
| | 15.0 | | | | | | | Sample collected 134-SB-113-1416 from 15.5-16.0' @ 9:55 |
| | 16.0 | | | | | 15.8 - 16.0' PT: Peat; end of boring @ 16.0' | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-114
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 1.0' FILL: Dark brown fine to medium silty sand, some coal, fine to medium gravel, trace red silty sand, clinker, rubber; moist, dense | 0 | Sample collected 134-SB-114-0002 from 0.5 - 1.0' bgs @ 8:52 |
| | -1.0 | | | | | 1.0 - 1.3' CONCRETE: Degraded | | |
| | -2.0 | | | | | 1.3 - 1.5' FILL: Dark brown silty clay; moist, firm | | Sample collected 134-SB-114-0204 from 2.5 - 3.0' bgs @ 8:55 |
| | -3.0 | | | | | 1.5 - 2.0' FILL: Reddish brown fine to medium silty sand; moist, loose | | |
| | -4.0 | | | 4.0 | | 2.0 - 3.0' FILL: Reddish brown silty clay, lenses of fine to medium sand, moist, firm | | Sample collected 134-SB-114-0406 from 4.5 - 5.0' bgs @ 9:00 |
| | -5.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -6.0 | | | | | 4.0 - 6.0' FILL: Reddish brown silty clay, lenses of fine to medium sand, wet, firm | | Sample collected 134-SB-114-0608 from 7.5 - 8.0' bgs @ 9:03 Petroleum odor and sheen |
| | -7.0 | | | | | 6.0 - 7.5' FILL: Brown fine to medium sand; wet, loose | | Sample collected 134-SB-114-0810 from 8.5 - 9.0' bgs @ 9:06 |
| | -8.0 | | | 2.5 | | 7.5 - 8.0' OL: Black silt, wet, very soft (sheen) | | |
| | -9.0 | | | | | 8.0 - 10.5' OL: Black silty, trace organics at bottom; wet, loose | | Sample collected 134-SB-114-1012 from 10.0 - 10.5' bgs @ 9:08 |
| | -10.0 | | | | | 10.5 - 12.0' No recovery | | |
| | -11.0 | | | | | | | |
| | -12.0 | | | 3.0 | | 12.0 - 13.5' ML: Reddish brown fine silty sand; wet, loose | | Sample collected 134-SB-114-1214 from 12.5 - 13.0' bgs @ 9:20 |
| | -13.0 | | | | | 13.5 - 15.0' OH: Brown silty clay; wet, moderately firm | | Sample collected 134-SB-114-1416 from 14.0 - 14.5' bgs @ 9:22 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | -16.0 | | | 3.0 | | | | Sample collected 134-SB- |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-114
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -16.0 | | | 3.0 | | 16.0 - 17.0' OH: Black clay; wet, firm | | Sample collected 134-SB-114-1618 from 16.0 - 16.5' bgs @ 9:30 |
| | -17.0 | | | | | 17.0 - 19.0' PT: Brown peat, trace brown clay; moist, firm | | |
| | -18.0 | | | | | | | |
| | -19.0 | | | | | 19.0 - 20.0' No recovery, end of boring @ 20.0' bgs | | |
| | -20.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-115
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.25 | | 0.0 - 0.3' ASPHALT | 0 | |
| | -1.0 | | | | | 0.3 - 2.0' FILL: Dark brown fine to medium sand, some fine to medium gravel, coal, ash, black glass fragments, trace brick; moist, moderate dense | | Sample collected 134-SB-115-0002 from 1.5 - 2.0' bgs @ 9:54 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.0 - 3.3' FILL: Reddish-brown silt, some fine to medium sand, firm, moist | | Sample collected 134-SB-115-0204 from 2.5 - 3.0' bgs @ 9:56 |
| | -4.0 | | | | | 3.3 - 4.0' No recover | | |
| | | | | 3.5 | | 4.0 - 4.8' FILL: Black fine to medium silty sand, ash, coal, black glass fragments; wet, loose | | Sample collected 134-SB-115-0406 from 4.5 - 5.0' bgs @ 10:00 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 4.8 - 7.5' FILL: Brown silt, some fine sand, trace fine to medium gravel; wet, firm | | |
| | -7.0 | | | | | | | Sample collected 134-SB-115-0608 from 7.0 - 7.5' bgs @ 10:02 |
| | -8.0 | | | | | 7.5 - 8.0' No recovery | | |
| | | | | 4.0 | | 8.0 - 12.0' FILL: Brown fine to medium sand, trace fine to medium gravel, silt, shells, lenses of still reddish clay; wet, moist | | Sample collected 134-SB-115-0810 from 9.0 - 9.5' bgs @ 10:04 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-115-1012 from 11.5 - 12.0' bgs @ 10:06 |
| | -12.0 | | | 4.0 | | 12.0 - 16.0' FILL: Brown fine to medium sand, trace fine to medium gravel, silt, shells, lenses of still reddish clay; wet, moist | | Sample collected 134-SB-115-1214 from 13.0 - 13.5' bgs @ 10:08 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | | | Sample collected 134-SB-115-1416 from 15.5 - 16.0' |
| | -16.0 | | | 3.5 | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-115
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -16.0 | | | 3.5 | | 16.0 - 17.3' CL: Brown silty clay; wet, moderate firm | | bgs @ 10:10 Sample collected 134-SB-115-1618 from 16.0 - 16.5' bgs @ 10:15 |
| | -17.0 | | | | | 17.3 - 17.5' OL: Black clay; moist, firm | | |
| | -18.0 | | | | | 17.5 - 19.5' PT: Brown peat, dark brown clay; firm moist | | |
| | -19.0 | | | | | 19.5 - 20.0' No recovery, end of boring @ 20.0' bgs | | |
| | -20.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-116
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 19ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | Creosote odor |
| | | | | | | 0.3 - 0.8' FILL: Red silt; moist, firm | | Sample collected 134-SB-116-0002 from 1.5 - 2.0' bgs @ 10:32 |
| | | | | | | 0.8 - 1.3' FILL: Wood | | |
| | -1.0 | | | | | 1.3 - 2.3' FILL: Dark brown fine to medium sand, ash, black glass fragments, trace coal, moist | | Sample collected 134-SB-116-0204 from 3.0 - 3.5' bgs @ 10:34 |
| | -2.0 | | | | | | | |
| | -3.0 | | | 3.75 | | 2.3 - 3.5' FILL: Reddish brown silt, lenses of fine to medium brown sand, trace organics; moist, firm | | Sample collected 134-SB-116-0406 from 4.0 - 4.5' bgs @ 10:36 |
| | -4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 4.8' FILL: Brown fine to coarse sand, some silt; wet, very loose | | Sample collected 134-SB-116-0608 from 6.5 - 7.0' bgs @ 10:38 |
| | -6.0 | | | | | | | |
| | -7.0 | | | 4.0 | | 4.8 - 7.8' FILL: Greyish brown fine to medium sand, trace lenses of clayey silt; wet, moderate dense | | Sample collected 134-SB-116-0810 from 8.5 - 9.0' bgs @ 10:40 |
| | -8.0 | | | | | 7.8 - 8.0' No recovery | | |
| | -9.0 | | | | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, trace lenses of clayey silt; wet, moderate dense | | Sample collected 134-SB-116-1012 from 11.0 - 11.5' bgs @ 10:42 |
| | -10.0 | | | | | | | |
| | -11.0 | | | 4.0 | | 12.0 - 15.0' FILL: Greyish brown fine to medium sand, trace shells; wet, loose | | Sample collected 134-SB-116-1214 from 12.5 - 13.0' bgs @ 10:50 |
| | -12.0 | | | | | | | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 15.0 - 15.5' ML: Reddish brown silt; wet, firm | | Sample collected 134-SB-116-1416 from 15.0 - 15.5' bgs @ 10:52 |
| | -15.0 | | | | | 15.5 - 16.0' OH: Black silty clay; wet, firm | | |
| | -16.0 | | | 2.0 | | 16.0 - 17.0' OH: Black silty clay; wet, firm | | Sample collected 134-SB-116-1618 from 16.0 - 16.5' bgs @ 11:00 |
| | -17.0 | | | | | 17.0 - 18.0' PT: Brown peat, brown clay; moist, firm | | |
| | -18.0 | | | | | 18.0 - 19.0' No recovery; end of boring @ 19.0' bgs | | |
| | -19.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-117
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 19ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 1.0' FILL: Red silt, firm, moist | 0 | Sample collected 134-SB-117-0002 from 0.5 - 1.0' bgs @ 11:22 |
| | -1.0 | | | | | 1.0 - 1.5' FILL: Dark brown, fine to medium silty sand, fine to medium gravel, coal, wet, loose | | |
| | -2.0 | | | | | 1.5 - 3.0' FILL: Reddish brown silt with lenses of fine to medium grayish brown sand, trace fine to medium gravel, firm, moist | | Sample collected 134-SB-117-0204 from 2.5 - 3.0' bgs @ 11:24 |
| | -3.0 | | | | | | | |
| | -4.0 | | | 4.0 | | 3.0 - 4.0' No recovery | | Sample collected 134-SB-117-0406 from 4.5 - 5.0' bgs @ 11:26 |
| | -5.0 | | | | | 4.0 - 8.0' FILL: Grayish brown fine to coarse sand turning fine to medium with lenses of reddish brown clayey silt, trace shells, wet, moderately dense | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | Sample collected 134-SB-117-0608 from 7.0 - 7.5' bgs @ 11:28 |
| | -8.0 | | | 4.0 | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, trace lenses of clayey silt; wet, moderate dense | | Sample collected 134-SB-117-0810 from 8.5 - 9.0' bgs @ 11:31 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-117-1012 from 11.0 - 11.5' bgs @ 11:33 |
| | -12.0 | | | 2.0 | | 12.0 - 14.0' FILL: Greyish brown fine to medium sand, trace shells; wet, loose | | Sample collected 134-SB-117-1214 from 12.5 - 13.0' bgs @ 11:37 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 16.0' No recovery | | |
| | -15.0 | | | | | | | |
| | -16.0 | | | 3.0 | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-117
**DATE BEGAN:** 6/20/2011
**DATE FINISHED:** 6/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 19ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -16.0 | | | 3.0 | | 16.0 - 17.0' OH: Black silty clay; wet, firm | | Sample collected 134-SB-117-1618 from 16.5 - 17.0' bgs @ 11:50 |
| | -17.0 | | | | | 17.0 - 18.5' PT: Brown peat, brown clay; fine to medium dark gray sand, moist, firm | | |
| | -18.0 | | | | | 18.5 - 19.0' No recovery; end of boring @ 19.0' bgs | | |
| | -19.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-118
**DATE BEGAN:** 6/22/2011
**DATE FINISHED:** 6/22/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 4.0 | | 0.0 - 0.3' ASPHALT | 0 | Sample collected 134-SB-118-0002 from 0.5 - 1.0' bgs @ 7:38 |
| | -1.0 | | | | | 0.3 - 0.5' FILL: Dark grey fine to medium sand, fine to medium gravel; moist, loose | | |
| | -2.0 | | | | | 0.5 - 4.0' FILL: Reddish brown silt, some fine sand, fine to medium gravel; moist, dense | | Sample collected 134-SB-118-0204 from 3.5 - 4.0' bgs @ 7:40 |
| | -3.0 | | | | | | | |
| | -4.0 | | | 4.0 | | 4.0 - 8.0' FILL: Reddish brown fine to medium silty sand, lenses of silty clay, trace fine to medium gravel and shells; wet, dense | | Sample collected 134-SB-118-0406 from 4.5 - 5.0' bgs @ 7:42; Dup @ 7:43 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | | | 4.0 | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, lenses of clay, trace shells; wet, loose | | Sample collected 134-SB-118-0608 from 7.5 - 8.0' bgs @ 7:45 |
| | -9.0 | | | | | | | Sample collected 134-SB-118-0810 from 9.0 - 9.5' bgs @ 7:47 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-118-1012 from 11.0 - 11.5' bgs @ 7:49 |
| | -12.0 | | | 4.0 | | 12.0 - 16.0' FILL: Greyish brown fine to medium sand, trace shells; wet, loose | | Sample collected 134-SB-118-1214 from 12.5 - 13.0' bgs @ 8:04 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | | | Sample collected 134-SB-118-1416 from 15.5 - 16.0' bgs @ 8:06 |
| | -16.0 | | | 2.0 | | 16.0 - 16.5' OL: Dark brown silty clay; wet, loose | | |
| | -17.0 | | | | | 16.5 - 17.0' PT: Brown peat, dark brown clay; moist, firm | | Sample collected 134-SB-118-1618 from 16.0 - 16.5' bgs @ 8:17 |
| | -18.0 | | | | | 17.0 - 18.0' SW: Brown fine to medium sand, some organics; moist, loose; end of boring @ 18.0' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-119
**DATE BEGAN:** 6/22/2011
**DATE FINISHED:** 6/22/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | Sample collected 134-SB-119-0002 from 1.0 - 1.5' bgs @ 8:29 |
| | -1.0 | | | | | 0.3 - 1.5' FILL: Red fine to medium silty sand, trace coal and fine gravel; moist, dense | | Sample collected 134-SB-119-0204 from 3.5 - 4.0' bgs @ 8:31 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 1.5 - 3.5' FILL: Reddish brown fine to medium sand, trace silt, layer of red silty clay @ bottom; moist, dense | | |
| | -4.0 | | | 4.0 | | 3.5 - 4.0' No recovery | | Sample collected 134-SB-119-0406 from 4.0 - 4.5' bgs @ 8:39 |
| | -5.0 | | | | | 4.0 - 6.0' FILL: Reddish brown fine to coarse sand, lenses of red silty stiff clay; wet, loose | | |
| | -6.0 | | | | | | | Sample collected 134-SB-119-0608 from 6.0 - 6.5' bgs @ 8:41 |
| | -7.0 | | | | | 6.0 - 8.0' FILL: Greyish brown fine to medium sand, nodules of dark brown silty clay; wet, loose | | |
| | -8.0 | | | 3.0 | | | | |
| | -9.0 | | | | | 8.0 - 11.0' FILL: Greyish brown fine to medium sand; wet, very loose | | Sample collected 134-SB-119-0810 from 8.5 - 9.0' bgs @ 8:43 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 134-SB-119-1012 from 10.5 - 11.0' bgs @ 8:45; Dup @ 8:47 |
| | -12.0 | | | 4.0 | | 12.0 - 15.5' OH: Black clay; wet, soft | | |
| | -13.0 | | | | | | | Sample collected 134-SB-119-1214 from 12.5 - 13.0' bgs @ 8:57 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.5 - 16.0' PT: Peat, dark brown clay; moist, soft; end of boring @ 16.0' bgs | | Sample collected 134-SB-119-1416 from 15.0 - 15.5' bgs @ 8:59 |
| | -16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-120
**DATE BEGAN:** 6/22/2011
**DATE FINISHED:** 6/22/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 0.5' ASPHALT | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' CONCRETE | | |
| | -2.0 | | | | | 1.0 - 1.5' FILL: Red sandy silt; moist, firm | | Sample collected 134-SB-120-0002 from 1.5 - 2.0' bgs @ 9:19 |
| | -3.0 | | | | | 1.5 - 2.0' FILL: Dark grey fine to medium sand, black glass-like fragments, coal and ash; moist, dense | | Sample collected 134-SB-120-0204 from 2.5 - 3.0' bgs @ 9:21 |
| | -4.0 | | | 4.0 | | 2.0 - 3.0' FILL: Reddish brown fine to medium sand; moist, dense | | Sample collected 134-SB-120-0406 from 4.5 - 5.0' bgs @ 9:23 |
| | -5.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -6.0 | | | | | 4.0 - 8.0' FILL: Greyish brown fine to medium sand, trace shells and lenses of reddish brown silty stif clay; wet, loose | | Sample collected 134-SB-120-0608 from 7.0 - 7.5' bgs @ 9:25 |
| | -7.0 | | | | | | | Sample collected 134-SB-120-0810 from 8.5 - 9.0' bgs @ 9:35 |
| | -8.0 | | | 4.0 | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, trace shells and red silt @ bottom; moist, loose | | Sample collected 134-SB-120-1012 from 11.5 - 12.0' bgs @ 9:37 |
| | -9.0 | | | | | | | Sample collected 134-SB-120-1214 from 12.5 - 13.0' bgs @ 9:46 |
| | -10.0 | | | | | | | Sample collected 134-SB-120-1416 from 15.0 - 15.5' bgs @ 9:48 |
| | -11.0 | | | | | | | |
| | -12.0 | | | 3.75 | | 12.0 - 15.8' FILL: Greyish brown fine to medium sand, trace shells and red silt; moist, loose | | |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | | | |
| | -16.0 | | | 2 | | 15.8 - 16.0' No recovery | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/22/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/22/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 18 ft bgs
**NORTH:**

**BORING ID:** 134-SB-120
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 4' bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -16.0 | | | 2 | | 16.0 - 17.0' FILL: Greyish brown fine to medium sand, trace shells and red silt; moist, loose | | Sample collected 134-SB-120-1618 from 16.0 - 16.5' bgs @ 10:02 |
| | -17.0 | | | | | 17.0 - 17.8' PT: Brown peat, brown clay; moist, firm | | |
| | -18.0 | | | | | 17.8 - 18.0' SM: Dark brown fine to medium silty sand, some organics; moist; moderate dense; end of boring @ 18.0' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-121
**DATE BEGAN:** 6/22/2011
**DATE FINISHED:** 6/22/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.75 | | 0.0 - 0.5' ASPHALT: Gravel | 0 | |
| | -1.0 | | | | | 0.5 - 1.5' FILL: Red fine to medium sand, fine to medium gravel, trace silt; dry dense | | Sample collected 134-SB-121-0002 from 1.5 - 2.0' bgs @ 14:59 |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Dark grey fine to medium dark grey slity sand, coal, ash, black glass pummice-like material | | Sample collected 134-SB-121-0204 from 3.0 - 3.5' bgs @ 15:01 |
| | -3.0 | | | | | | | |
| | -4.0 | | | 4.0 | | 2.0 - 2.1' FILL: Brown silty clay; moist, firm | | Sample collected 134-SB-121-0406 from 4.5 - 5.0' bgs @ 15:03 |
| | -5.0 | | | | | 2.1 - 3.8' FILL: Greyish brown fine to medium sand, lenses of red silty stiff clay; moist, firm | | |
| | -6.0 | | | | | 3.8 - 4.0' No recovery | | |
| | -7.0 | | | | | 4.0 - 8.0' FILL: Greyish brown fine to medium sand, lenses of red silty stiff clay, trace shells; moist, firm | | Sample collected 134-SB-121-0608 from 7.0 - 7.5' bgs @ 15:05 |
| | -8.0 | | | 4.0 | | | | Sample collected 134-SB-121-0810 from 8.5 - 9.0' bgs @ 15:11 |
| | -9.0 | | | | | 8.0 - 12.0' FILL: Grey brown fine to coarse sand, lenses of red silty stiff clay, trace silt; wet, soft | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-121-1012 from 11.0 - 11.5' bgs @ 15:13 |
| | -12.0 | | | 3.75 | | | | Sample collected 134-SB-121-1214 from 12.5 - 13.0' bgs @ 15:21 |
| | -13.0 | | | | | 12.0 - 15.0' FILL: Grey brown fine to coarse sand, lenses of red silty stiff clay, trace silt; wet, soft | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.0 - 15.8' FILL: Reddish brown silt, trace clay; wet, moderate firm | | Sample collected 134-SB-121-1416 from 15.0 - 15.5' bgs @ 15:23 |
| | -16.0 | | | 2.0 | | 15.8 - 16.0' No recovery | | Sample collected 134-SB-121-1618 from 16.0 - 16.5 bgs @ 15:30 |
| | -17.0 | | | | | 16.0 - 16.8' OL: Black clay; moist, firm | | |
| | -18.0 | | | | | 16.8 - 18.0' PT: Brown peat, dark brown clay; moist, firm, End of boring @ 18' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-122
**DATE BEGAN:** 6/22/2011
**DATE FINISHED:** 6/22/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | |
| | -1.0 | | | | | 0.3 - 0.5' FILL: Dark brown fine to medium silty sand; dry, dense | | Sample collected 134-SB-122-0002 from 1.0 - 1.5' bgs @ 15:40 |
| | -2.0 | | | | | 0.5 - 1.0' FILL: Red fine to medium silty sand, trace fine gravel; moist, dense | | |
| | -3.0 | | | | | 1.0 - 2.3' FILL: Dark brown fine to medium silty sand, trace coal, fine to medium gravel, ash; moist, dense | | Sample collected 134-SB-122-0204 from 3.0 - 3.5' bgs @ 15:42 |
| | -4.0 | | | 4.0 | | | | |
| | -5.0 | | | | | 2.3 - 3.5' FILL: Reddish brown fine to medium sand, lenses of red silty firm clay; moist, dense | | Sample collected 134-SB-122-0406 from 4.5 - 5.0' bgs @ 15:44 |
| | -6.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -7.0 | | | | | 4.0 - 8.0' FILL: Reddish brown fine to medium sand, lenses of red silty firm clay; moist, dense | | Sample collected 134-SB-122-0608 from 7.0 - 7.5' bgs @ 15:46 |
| | -8.0 | | | 4.0 | | | | |
| | -9.0 | | | | | 8.0 - 12.0' FILL: Reddish brown fine to medium sand, lenses of red silty firm clay; wet, very loose | | Sample collected 134-SB-122-0810 from 9.0 - 9.5' bgs @ 15:50 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | | | 4.0 | | 12.0 - 15.8' FILL: Reddish brown fine to medium sand, lenses of red silty firm clay; wet, very loose | | Sample collected 134-SB-122-1012 from 11.5 - 12.0' bgs @ 15:52 |
| | -13.0 | | | | | | | Sample collected 134-SB-122-1214 from 13.0 - 13.5' bgs @ 16:04 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.8 - 16.0' FILL: Reddish brown silty; wet, moderate firm | | Sample collected 134-SB-122-1416 from 15.5 - 16.0' bgs @ 16:06 |
| | -16.0 | | | 2.0 | | 16.0 - 17.0' CL: Brown clay | | |
| | -17.0 | | | | | 17.0 - 18.0' PT: Brown peat, dark brown clay; moist, firm; end of boring @ 18.0' bgs | | Sample collected 134-SB-122-1618 from 16.5 - 17.0' bgs @ 16:17 |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-123
**DATE BEGAN:** 6/23/2011
**DATE FINISHED:** 6/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.25 | | 0.0 - 0.5' ASPHALT: Gravel, coal, ash, glass pumice-like material; moist, loose | 0 | |
| | -1.0 | | | | | 0.5 - 1.3' FILL: Red fine to medium slity sand, trace fine gravel; moist, dense | | Sample collected 134-SB-123-0002 from 0.5 - 1.0' bgs @ 7:40 |
| | -2.0 | | | | | 1.3 - 2.8' FILL: Brown fine to medium silty sand, fine gravel; wet, moderate dense | | Sample collected 134-SB-123-0204 from 2.5 - 3.0' bgs @ 7:42 |
| | -3.0 | | | | | 2.8 - 3.3' FILL: Reddish brown silty clay; wet, firm | | |
| | -4.0 | | | 4.0 | | 3.3 - 4.0' No recovery | | Sample collected 134-SB-123-0406 from 4.5 - 5.0' bgs @ 7:44 |
| | -5.0 | | | | | 4.0 - 8.0' FILL: Greyish brown fine to medium sand, lenses of red silty stiff clay; trace fine to medium gravel; wet, moderate dense | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | Sample collected 134-SB-123-0608 from 7.0 - 7.5' bgs @ 7:46 |
| | -8.0 | | | 2.5 | | 8.0 - 10.5' FILL: Greyish brown fine to medium sand, lenses of red silty stiff clay; trace fine to medium gravel and shells; wet, moderate dense | | Sample collected 134-SB-123-0810 from 8.5 - 9.0' bgs @ 7:53 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | Sample collected 134-SB-123-1012 from 10.0 - 10.5' bgs @ 7:55 |
| | -11.0 | | | | | 10.5 - 12.0' No recovery | | Organic odor from 10.0 - 10.5' bgs |
| | -12.0 | | | 2.0 | | 12.0 - 13.8' FILL: Brown sandy silt; wet, very loose | | |
| | -13.0 | | | | | | | Sample collected 134-SB-123-1214 from 13.5 - 14.0' bgs @ 8:04 |
| | -14.0 | | | | | 13.8 - 14.0' OH: Black clay; wet, firm | | |
| | -15.0 | | | | | 14.0 - 16.0' No recovery | | |
| | -16.0 | | | 2.0 | | 16.0 - 17.3' OH: Black clay; moist, firm | | Sample collected 134-SB-123-1618 from 16.5 - 17.0 bgs @ 8:14 |
| | -17.0 | | | | | 17.3 - 18.0' PT: Brown peat, dark brown clay; moist, firm; end of boring @ 18.0' bgs | | |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/23/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/23/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 17.5 ft bgs
**NORTH:**

**BORING ID:** 134-SB-124
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 5' bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Gravel | 0 | |
| | -1.0 | | | | | 0.5 - 2.5' FILL: Red fine to medium silty sand; moist, dense | | Sample collected 134-SB-124-0002 from 1.0 - 1.5' bgs @ 10:52 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.5 - 3.0' FILL: Red silt; moist, very firm | | |
| | -4.0 | | | 4.0 | | 3.0 - 3.5' FILL: Dark brown silty clay, trace organics; moist, firm | | Sample collected 134-SB-124-0204 from 3.0 - 3.5' bgs @ 10:54 |
| | -5.0 | | | | | 3.3 - 4.0' No recovery | | |
| | -6.0 | | | | | 4.0 - 6.0' FILL: Reddish brown silt to brown silt with depth; moist, firm | | Sample collected 134-SB-124-0406 from 5.5 - 6.0' bgs @ 10:58 |
| | -7.0 | | | | | 6.0 - 8.0' FILL: Greyish brown fine to medium sand, trace silty and lenses of red silty clay; wet, loose | | Sample collected 134-SB-124-0608 from 7.0 - 7.5' bgs @ 11:00 |
| | -8.0 | | | 4.0 | | | | |
| | -9.0 | | | | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, trace silty and lenses of red silty clay; wet, loose | | Sample collected 134-SB-124-0810 from 8.0 - 8.5' bgs @ 11:04 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-124-1012 from 10.5 - 11.0' bgs @ 11:04 |
| | -12.0 | | | 4.0 | | 12.0 - 14.0' FILL: Brown silt, grey clay from 12.5 - 12.7' bgs; wet, firm | | |
| | -13.0 | | | | | | | Sample collected 134-SB-124-1214 from 12.5 - 13.0' bgs @ 11:14 |
| | -14.0 | | | | | 14.0 - 15.3' CL: Brown silt, moist, firm | | |
| | -15.0 | | | | | | | Sample collected 134-SB-124-1416 from 14.5 - 15.0' bgs @ 11:16 |
| | -16.0 | | | | | 15.3 - 16.0' OH: Black clay; moist, firm | | |
| | -17.0 | | | 1.5 | | 16.0 - 17.5' PT: Peat, brown clay; moist, firm; end of boring @ 17.5' bgs | | Sample collected 134-SB-124-1618 from 16.0 - 16.5 bgs @ 11:27; HOLD |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-125
**DATE BEGAN:** 6/23/2011
**DATE FINISHED:** 6/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 4.0 | | 0.0 - 0.5' ASPHALT | 0 | |
| | -1.0 | | | | | 0.5 - 0.8' FILL: Yellow green medium to coarse sand, trace gravel; dry | | Sample collected 134-SB-125-0002 from 0.5 - 1.0' bgs @ 9:19 |
| | -2.0 | | | | | 0.8 - 2.0' FILL: Reddish brown fine to medium sand; moist | | |
| | -3.0 | | | | | 2.0 - 2.5' FILL: Reddish brown clayey silt; moist | | Sample collected 134-SB-125-0204 from 3.0 - 3.5' bgs @ 9:21 |
| | -4.0 | | | 4.0 | | 2.5 - 3.0' FILL: Coal, ash, medium to coarse; moist | | |
| | -5.0 | | | | | 3.0 - 4.0' FILL: Reddish brown silty clay, trace fine to medium sand and gravel | | Sample collected 134-SB-125-0406 from 4.5 - 5.0' bgs @ 9:26 |
| | -6.0 | | | | | 4.0 - 4.5' FILL: Reddish brown silty fine sand; moist, dense | | |
| | -7.0 | | | | | 4.5 - 4.6' FILL: Yellow fine to medium sand (COPR); dry dense | | |
| | -8.0 | | | 3.0 | | 4.6 - 8.0' FILL: Brown medium sand; wet, loose | | Sample collected 134-SB-125-0608 from 7.5 - 8.0' bgs @ 9:28 |
| | -9.0 | | | | | 8.0 - 11.0' FILL: Brown fine to medium sand, trace gravel and shells; wet, loose | | Sample collected 134-SB-125-0810 from 9.0 - 9.5' bgs @ 9:30 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 134-SB-125-1012 from 10.5 - 11.0' bgs @ 9:32 |
| | -12.0 | | | 3.0 | | 12.0 - 13.0' FILL: Brown fine to medium sand, trace gravel and shells; wet, loose | | |
| | -13.0 | | | | | 13.0 - 14.0' FILL: Reddish yellow fine to medium sand, trace gravel; wet, loose | | Sample collected 134-SB-125-1214 from 13.5 - 14.0' bgs @ 9:38 |
| | -14.0 | | | | | 14.0 - 15.0' FILL: Brown clay, brown fine to medium sand; loose, moist | | Sample collected 134-SB-125-1416 from 14.5 - 15.0' bgs @ 9:40 |
| | -15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | -16.0 | | | 2.0 | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/23/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/23/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 18 ft bgs
**NORTH:**

**BORING ID:** 134-SB-125
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 4.5' bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -16.0 | | | 2.0 | | 16.0 - 17.0' OL: Dark brown silty clay; moist, medium firm | | Sample collected 134-SB-125-1618 from 16.5 - 17.0 bgs @ 9:49 |
| | -17.0 | | | | | 17.0 - 18.0' PT: Peat, dark clay; moist, firm; end of boring @ 18.0' bgs | | |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/23/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/23/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 18 ft bgs
**NORTH:**

**BORING ID:** 134-SB-126
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 4.0 bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.3' ASPHALT | 0 | |
| | -1.0 | | | | | 0.0 - 0.8' CONCRETE | | Sample collected 134-SB-126-0002 from 1.0 - 1.5' bgs @ 9:58 |
| | -2.0 | | | | | 0.8 - 1.3' FILL: Red fine to medium silty sand, trace fine to medium gravel, degraded brick @ bottom; moist, dense | | |
| | -3.0 | | | | | 1.3 - 3.5' FILL: Reddish brown silt, trace fine to medium sand; moist, dense | | Sample collected 134-SB-126-0204 from 3.0 - 3.5' bgs @ 10:00 |
| | -4.0 | | | 3.25 | | 3.5 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 6.0' FILL: Reddish brown silt, trace fine to medium sand; wet, dense | | Sample collected 134-SB-126-0406 from 4.5 - 5.0' bgs @ 10:02 |
| | -6.0 | | | | | 6.0 - 7.3' FILL: Reddish brown fine to coarse silty sand, fine to medium gravel; wet moderate dense | | |
| | -7.0 | | | | | 7.3 - 8.0' No recovery | | Sample collected 134-SB-126-0608 from 6.5-7.0' bgs @ 10:04 |
| | -8.0 | | | 3.0 | | 8.0 - 8.5' FILL: Brown fine to medium silty sand; wet, loose | | |
| | -9.0 | | | | | 8.5 - 9.5' FILL: Orange-red fine to meium sand; trace silt and fine to medium gravel; wet, loose | | Sample collected 134-SB-126-0810 from 8.5 - 9.0' bgs @ 10:12 |
| | -10.0 | | | | | 9.5 - 11.0' FILL: Brown clay; wet, soft | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 134-SB-126-1012 from 10.0 - 10.5' bgs @ 10:14 |
| | -12.0 | | | 2.75 | | 12.0 - 13.5' CL: Brown clay; wet, medium firm | | |
| | -13.0 | | | | | 13.5 - 14.8' OH: Black clay; moist, firm | | Sample collected 134-SB-126-1214 from 12.0 - 12.5' bgs @ 10:27 |
| | -14.0 | | | | | 14.8 - 16.0' No recovery | | Sample collected 134-SB-126-1416 from 14.0 - 14.5' bgs @ 10:29 |
| | -15.0 | | | | | | | |
| | -16.0 | | | 1.0 | | 16.0 - 16.3' OH: Black clay, moist, firm | | Sample collected 134-SB- |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-126
**DATE BEGAN:** 6/23/2011
**DATE FINISHED:** 6/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -16.0 | | | 1.0 | | 16.3 - 18.0' PT: Peat, dark clay; moist, firm; end of boring @ 18.0' bgs | | Sample collected 134-SB-126-1618 from 16.0 - 16.5 bgs @ 10:30; Hold |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-127
**DATE BEGAN:** 6/24/2011
**DATE FINISHED:** 6/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 8.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Gravel | 0 | |
| | -1.0 | | | | | 0.5 - 2.8' FILL: Red sandy silt, less sand with depth, fine to medium gravel, trace coal; dry, dense | | Sample collected 134-SB-127-0002 from 1.5 - 2.0' bgs @ 11:26 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.8 - 3.5' FILL: Dark greyish brown/brown silt, some fine sand, wood, fine to medium gravel; moist, stiff | | Sample collected 134-SB-127-0204 from 3.0 - 3.5' bgs @ 11:28 |
| | -4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | | | 4.0 | | 4.0 - 4.5' FILL: Red silt, trace fine sand; dry loose | | |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 4.5 - 4.8' FILL: Dark grey fine to medium silty sand, gravel and coal; dry, loose | | Sample collected 134-SB-127-0406 from 5.0 - 5.5' bgs @ 11:30 |
| | -7.0 | | | | | 4.8 - 5.0' FILL: Brown silty clay; moist, soft | | Sample collected 134-SB-127-0608 from 7.5 - 8.0' bgs @ 11:32 |
| | -8.0 | | | | | 5.0 - 8.0' FILL: Greyish brown fine to medium sand; moist, loose | | |
| | | | | 3.5 | | 8.0 - 11.5' FILL: Greyish brown fine to medium silty sand, trace shells; wet, loose | | Sample collected 134-SB-127-0810 from 8.5 - 9.0' bgs @ 11:34 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-127-1012 from 10.5 - 11.0' bgs @ 11:36 |
| | -12.0 | | | | | 11.5 - 12.0' No recovery | | |
| | | | | 3.75 | | 12.0 - 14.5' MH: Brown sandy silt; wet, very soft | | Sample collected 134-SB-127-1214 from 12.5 - 13.0' bgs @ 11:45 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 14.5 - 15.5' MH: Brown silt; wet, stiff | | Sample collected 134-SB-127-1416 from 15.0 - 15.5' bgs @ 11:47 |
| | | | | | | 15.5 - 15.8' OL: Dark grey clay; wet; stiff | | |
| | -16.0 | | | 1.5 | | 15.8 - 16.0' No recovery | | Sample collected 134-SB-127-1618 from 16.0 - 16.5 |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-127
**DATE BEGAN:** 6/24/2011
**DATE FINISHED:** 6/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 8.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -17.0 | | | | | 16.0 - 16.3' OL: Dark grey clay; wet; stiff | | bgs @ 11:54; Hold |
| | -18.0 | | | | | 16.3 - 17.5' PT: Brown peat, dark brown clay; moist, stiff | | |
| | | | | | | 17.5 - 18.0' No recovery; End boring @ 18' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-128
**DATE BEGAN:** 6/23/2011
**DATE FINISHED:** 6/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 17 ft bgs
**GW DEPTH:** 4.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 0.4' CONCRETE | 0 | |
| | -1.0 | | | | | 0.4 - 0.8' FILL: Red fine to medium silty sand; moist, dense | | Sample collected 134-SB-128-0002 from 1.0 - 1.5' bgs @ 12:28 |
| | -2.0 | | | | | 0.8 - 1.8' FILL: Red silty clay; moist, firm | | |
| | -3.0 | | | | | 1.8 - 2.0' FILL: Degraded brick | | Sample collected 134-SB-128-0204 from 2.5 - 3.0' bgs @ 12:30 |
| | -4.0 | | | 4.0 | | 2.0 - 2.5' FILL: Red silty clay; moist, firm | | |
| | -5.0 | | | | | 2.5 - 3.0' FILL: Reddish brown silt, trace clay and organics; moist, firm | | Sample collected 134-SB-128-0406 from 5.0 - 5.5' bgs @ 12:32 |
| | -6.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -7.0 | | | | | 4.0 - 4.3' FILL: Reddish brown silt, trace clay and organics; wet, soft | | Sample collected 134-SB-128-0608 from 7.5 - 8.0' bgs @ 12:34 |
| | -8.0 | | | 3.0 | | 4.3 - 4.5' CONCRETE | | |
| | -9.0 | | | | | 4.5 - 8.0' FILL: Greyish brown fine to medium sand; layers of red silty firm clay; wet, loose | | Sample collected 134-SB-128-0810 from 8.0 - 8.5' bgs @ 12:39 |
| | -10.0 | | | | | 8.0 - 10.5' FILL: Greyish brown fine to medium sand; layers of red silty firm clay; wet, loose | | |
| | -11.0 | | | | | 10.5 - 11.0' CL: Brown silty clay; wet, firm | | Sample collected 134-SB-128-1012 from 10.5 - 11.0' bgs @ 12:41 |
| | -12.0 | | | 3.5 | | 11.0 - 12.0' No recovery | | Sample collected 134-SB-128-1214 from 12.0 - 12.5' bgs @ 12:49 |
| | -13.0 | | | | | 12.0 - 12.5' ML: Brown fine to medium silty sand; wet, loose | | |
| | -14.0 | | | | | 12.5 - 15.5' CL: Brown silt, some fine sand; wet, firm | | |
| | -15.0 | | | | | | | Sample collected 134-SB-128-1416 from 14.5 - 15.0' bgs @ 12:51 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery | | |
| | -17.0 | | | 1.0 | | 16.0 - 16.5' OH: Black clay; wet, stiff | | Sample collected 134-SB-128-1618 from 16.0 - 16.5 bgs @ 13:01 |
| | | | | | | 16.5 - 17.0' PT: Peat, black clay; moist firm; end of boring @ 17.0' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-129
**DATE BEGAN:** 6/23/2011
**DATE FINISHED:** 6/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 17.5 ft bgs
**GW DEPTH:** 4.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 2.5 | | 0.0 - 0.4' CONCRETE | 0 | |
| | -1.0 | | | | | 0.4 - 1.0' FILL: Red fine to medium silty sand, trace fine gravel; wet, loose | | Sample collected 134-SB-129-0002 from 0.5 - 1.0' bgs @ 13:11 |
| | -2.0 | | | | | 1.0 - 2.5' FILL: Red silt, fine gravel; moist, dense | | Sample collected 134-SB-129-0204 from 2.0 - 2.5' bgs @ 13:13 |
| | -3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | -4.0 | | | 4.0 | | 4.0 - 4.5' FILL: Red silty sand, wet, loose (grey spots throughout) | | Sample collected 134-SB-129-0406 from 4.0 - 4.5' bgs @ 13:16 |
| | -5.0 | | | | | 4.5 - 5.0' FILL: Red silt; wet, firm | | |
| | -6.0 | | | | | 5.0 - 8.0' FILL: Greyish brown fine to medium sand; wet, loose | | Sample collected 134-SB-129-0608 from 7.5 - 8.0' bgs @ 13:18 |
| | -7.0 | | | | | | | Sample collected 134-SB-129-0810 from 8.5 - 9.0' bgs @ 13:24 |
| | -8.0 | | | 3.0 | | 8.0 - 11.0' FILL: Greyish brown fine to medium sand, 9.5 - 9-.75' bgs layer of grey silt; wet, soft | | Sample collected 134-SB-129-1012 from 10.5 - 11.0' bgs @ 13:26 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | | | 3.0 | | 12.0 - 14.0' FILL: Brown fine to medium sand; loose, wet | | Sample collected 134-SB-129-1214 from 12.5 - 13.0' bgs @ 13:37 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 14.8' CL: Brown silty clay, trace fine to medium sand; wet, soft | | Sample collected 134-SB-129-1416 from 14.0 - 14.5' bgs @ 13:39 |
| | -15.0 | | | | | 14.8 - 15.0' OH: Black clay; moist, firm | | |
| | -16.0 | | | 1.5 | | 15.0 - 16.0' No recovery | | Sample collected 134-SB-129-1618 from 16.0 - 16.5 bgs @ 13:46 |
| | -17.0 | | | | | 16.0 - 16.5' OH: Black clay; moist, firm | | |
| | | | | | | 16.5 - 17.5' PT: Peat, dark brown clay; moist, firm; end of boring @ 17.5' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/23/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/23/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 18.5 ft bgs
**NORTH:**

**BORING ID:** 134-SB-130
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 4.0 bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 2.5 | | 0.0 - 0.5' CONCRETE | 0 | |
| | -1.0 | | | | | 0.5 - 2.0' FILL: Reddish brown silty sand, trace clay; dry, firm | | Sample collected 134-SB-130-0002 from 0.5 - 1.0' bgs @ 14:01 |
| | -2.0 | | | | | 2.0 - 2.5' OL: Brownish grey silty clay; moist, firm | | Sample collected 134-SB-130-0204 from 2.0 - 2.5' bgs @ 14:03 |
| | -3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | -4.0 | | | 4.0 | | 4.0 - 4.3' SP: Reddish brown fine to medium sand; dry, loose | | |
| | -5.0 | | | | | 4.3 - 4.5' Concrete: fragments | | Sample collected 134-SB-130-0406 from 5.0 - 5.5' bgs @ 14:09 |
| | -6.0 | | | | | 4.5 - 7.0' SM: Reddish brown fine to medium silty sand, trace clay; wet, loose | | |
| | -7.0 | | | | | 7.0 - 8.0' SP: Brown fine to medium sand; loose, wet | | Sample collected 134-SB-130-0608 from 7.5 - 8.0' bgs @ 11:11; DUP @ 14:12 |
| | -8.0 | | | 3.5 | | 8.0 - 9.5' SP: Brown fine to medium sand; wet, loose | | Sample collected 134-SB-130-0810 from 8.5 - 9.0' bgs @ 14:16 |
| | -9.0 | | | | | 9.5 - 11.5' OH: Black organic clay; wet, loose | | |
| | -10.0 | | | | | 11.5 - 12.0' No recovery | | Sample collected 134-SB-130-1012 from 10.5 - 11.0' bgs @ 14:18; DUP @ 14:19 |
| | -11.0 | | | | | 12.0 - 15.0' SM: Brown fine to medium silty sand; wet, loose | | Sample collected 134-SB-130-1214 from 12.0 - 12.5' bgs @ 14:23 |
| | -12.0 | | | 3.0 | | 15.0 - 16.0' No recovery | | Sample collected 134-SB-130-1416 from 14.5 - 15.0' bgs @ 14:25 |
| | -13.0 | | | | | 16.0 - 17.3' OL: Brown fine to medium silty clay; wet, loose | | Sample collected 134-SB-130-1618 from 16.0 - 16.5 bgs @ 14:31 |
| | -14.0 | | | | | 17.3 - 18.5' PT: Peat, dark brown clay; moist, firm; end of boring @ 18.5' bgs | | |
| | -15.0 | | | | | | | |
| | -16.0 | | | 2.5 | | | | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/24/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/24/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 18.5 ft bgs
**NORTH:**

**BORING ID:** 134-SB-131
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 4.0 bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 2.5 | | 0.0 - 0.4' CONCRETE | 0 | Sample collected 134-SB-131-0002 from 1.0 - 1.5' bgs @ 7:40 |
| | -1.0 | | | | | 0.4 - 1.0' FILL: Red fine to medium silty sand, trace fine gravel; dry, loose | | Sample collected 134-SB-131-0204 from 2.0 - 2.5' bgs @ 7:42 |
| | -2.0 | | | | | 1.0 - 2.5' FILL: Reddish brown silty clay, fine sand, trace fine to medium gravel; moist, very stiff | | |
| | -3.0 | | | | | | | |
| | -4.0 | | | 4.0 | | 2.5 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 6.5' FILL: Reddish brown silty clay, trace fine to medium gravel; wet, firm | | Sample collected 134-SB-131-0406 from 5.0 - 5.5' bgs @ 7:45 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | 6.5 - 8.0' FILL: Brownish grey fine to medium sand; wet, moderate dense | | Sample collected 134-SB-131-0608 from 7.0 - 7.5' bgs @ 7:47; DUP @ 7:48 |
| | -8.0 | | | 4.0 | | 8.0 - 12.0' FILL: Brownish grey fine to medium sand; moist, dense | | Sample collected 134-SB-131-0810 from 9.0 - 9.5' bgs @ 7:49 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | Sample collected 134-SB-131-1012 from 11.5 - 12.0' bgs @ 7:51 |
| | -11.0 | | | | | | | |
| | -12.0 | | | 4.0 | | 12.0 - 13.5' FILL: Brown fine to medium silty sand; wet, loose | | Sample collected 134-SB-131-1214 from 12.5 - 13.0' bgs @ 8:02 |
| | -13.0 | | | | | 13.5 - 14.5' MH: Brown silt, lenses of brown fine to medium silty sand; wet, loose | | Sample collected 134-SB-131-1416 from 14.0 - 14.5' bgs @ 8:04 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 14.5 - 16.0' No recovery | | |
| | -16.0 | | | 2.5 | | 16.0 - 16.3' MH: Brown silt, lenses of brown fine to medium silty sand; wet, loose | | |
| | -17.0 | | | | | 16.3 - 17.0' OH: Black clay; moist, firm | | Sample collected 134-SB-131-1618 from 16.5 - 17.0 bgs @ 8:16 |
| | -18.0 | | | | | 17.0 - 18.5' PT: Peat, dark brown clay; moist, firm; end of boring @ 18.5' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-132
**DATE BEGAN:** 6/24/2011
**DATE FINISHED:** 6/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18.5 ft bgs
**GW DEPTH:** 5.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 0.5' CONCRETE | 0 | |
| | -1.0 | | | | | 0.5 - 3.0' FILL: Reddish brown fine sandy silt, trace coal, lense of dark grey fine to medium sand, coal, and ash from 1.5 - 1.65' bgs; moist, firm | | Sample collected 134-SB-132-0002 from 1.5 - 2.0' bgs @ 8:27 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | Sample collected 134-SB-132-0204 from 2.5 - 3.0' bgs @ 8:29 |
| | -4.0 | | | 3.25 | | 4.0 - 5.0' FILL: Reddish brown silt, trace fine sand, dry, very firm | | |
| | -5.0 | | | | | 5.0 - 6.0' FILL: Reddish brown silty clay, moist, moderate firm | | Sample collected 134-SB-132-0406 from 5.0 - 5.5' bgs @ 8:32 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | 6.0 - 6.8' FILL: Reddish brown fine to coarse silty sand, some clay and fine gravel; wet, dense | | Sample collected 134-SB-132-0608 from 6.0 - 6.5' bgs @ 8:34 |
| | -8.0 | | | 4.0 | | 6.8 - 7.0' FILL: Reddish brown silty clay; wet, firm | | Sample collected 134-SB-132-0810 from 8.5 - 9.0' bgs @ 8:39 |
| | -9.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -10.0 | | | | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, lenses of red silty clay @ top, wet; moderate dense | | Sample collected 134-SB-132-1012 from 11.0 - 11.5' bgs @ 8:41 |
| | -11.0 | | | | | | | |
| | -12.0 | | | 3.5 | | 12.0 - 15.5' FILL: Brown fine silty sand; trace shells, black clay in tip, wet, loose | | Sample collected 134-SB-132-1214 from 12.5 - 13.0' bgs @ 9:04 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.5 - 16.0' No recovery | | Sample collected 134-SB-132-1416 from 15.0 - 15.5' bgs @ 9:06 |
| | -16.0 | | | 2.5 | | 16.0 - 16.8' MH: Brown silt; wet, soft | | |
| | -17.0 | | | | | 16.8 - 17.5' OH: Black clay; moist, firm | | Sample collected 134-SB-132-1618 from 16.5 - 17.0 bgs @ 9:15 |
| | -18.0 | | | | | 17.5 - 18.5' PT: Peat, brown clay, moist, firm; end of boring @ 18.5' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-133
**DATE BEGAN:** 6/24/2011
**DATE FINISHED:** 6/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18.0 ft bgs
**GW DEPTH:** 8.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.75 | | 0.0 - 0.4' CONCRETE | 0 | |
| | -1.0 | | | | | 0.4 - 2.8' FILL: Red fine to medium silty sand, trace coal and ash; moist, loose | | Sample collected 134-SB-133-0002 from 1.5 - 2.0' bgs @ 929 |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | 2.8 - 3.8' FILL: Dark grey fine to medium silty sand, coal, trace ash, trash, fine gravel; moist, moderate dense | | Sample collected 134-SB-133-0204 from 3.0 - 3.5' bgs @ 9:31; DUP @ 9:32 |
| | -4.0 | | | 3.5 | | 3.8 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 5.0' FILL: Brown clayey silt; wet, firm | | Sample collected 134-SB-133-0406 from 4.5 - 5.0' bgs @ 9:33 |
| | -6.0 | | | | | 5.0 - 7.5' FILL: Brownish grey fine to medium sand, lenses of red silty firm clay; wet, loose | | |
| | -7.0 | | | | | 7.5 - 8.0' No recovery | | Sample collected 134-SB-133-0608 from 7.0 - 7.5' bgs @ 9:35 |
| ▽ | -8.0 | | | 4.0 | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, brown silt in top; wet, loose | | Sample collected 134-SB-133-0810 from 8.5 - 9.0' bgs @ 9:37 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | Sample collected 134-SB-133-1012 from 11.0 - 11.5' bgs @ 9:39 |
| | -12.0 | | | 3.25 | | 12.0 - 14.0' ML: Brown sandy silt; wet, loose | | Sample collected 134-SB-133-1214 from 12.5 - 13.0' bgs @ 9:53 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 15.3' MH: Brown silty; wet, soft | | Sample collected 134-SB-133-1416 from 14.5 - 15.0' bgs @ 9:55 |
| | -15.0 | | | | | 15.3 - 16.0' No recovery | | |
| | -16.0 | | | 2.0 | | 16.0 - 17.0' OH: Black clay; moist, firm | | Sample collected 134-SB-133-1618 from 16.5 - 17.0 bgs @ 10:11 |
| | -17.0 | | | | | 17.0 - 18.0' PT: Peat, brown clay, moist, firm; end of boring @ 18.0' bgs | | |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-134
**DATE BEGAN:** 6/24/2011
**DATE FINISHED:** 6/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18.5 ft bgs
**GW DEPTH:** 8.0 bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.4' CONCRETE | 0 | |
| | -1.0 | | | | | 0.4 - 0.5' FILL: Brown silt; moist, firm | | Sample collected 134-SB-134-0002 from 1.0 - 1.5' bgs @ 10:23 |
| | -2.0 | | | | | 0.5 - 0.8' FILL: Red silty sand, trace coal; moist, loose | | |
| | -3.0 | | | | | 0.8 - 3.0' FILL: Brown sandy silt, trace coal, fine to medium gravel and lenses of grey silt | | Sample colleced 134-SB-134-0204 from 2.5 - 3.0' bgs @ 10:25 |
| | -4.0 | | | 3.0 | | 3.0 - 3.5' FILL: Brown silt; moist, firm | | Sample collected 134-SB-134-0406 from 4.0 - 4.5' bgs @ 10:27 |
| | -5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | -6.0 | | | | | 4.0 - 5.0' FILL: Brown silt; moderate firm | | |
| | -7.0 | | | | | 5.0 - 7.0' FILL: Greyish brown fine to medium sand, trace lenses of reddish brown silty firm clay, fine to medium gravel; moist, loose | | Sample collected 134-SB-134-0608 from 6.5 - 7.0' bgs @ 10:29 |
| | -8.0 | | | 3.5 | | 7.0 - 8.0' No recovery | | Sample collected 134-SB-134-0810 from 8.5 - 9.0' bgs @ 10:32 |
| | -9.0 | | | | | 8.0 - 11.5' FILL: Greyish brown fine to medium sand, trace shells; wet, loose | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.5 - 12.0' No recovery | | Sample collected 134-SB-134-1012 from 11.0 - 11.5' bgs @ 10:34 |
| | -12.0 | | | 3.0 | | 12.0 - 14.5' FILL: Greyish brown fine to medium sand, trace shells; wet, loose | | Sample collected 134-SB-134-1214 from 12.5 - 13.0' bgs @ 10:42 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.5 - 15.0' MH: Brown silt; wet, loose | | Sample collected 134-SB-134-1416 from 14.5 - 15.0' bgs @ 10:44 |
| | -15.0 | | | | | 15.0 - 16.0' No recovery | | |
| | -16.0 | | | 2.5 | | 16.0 - 17.5' OH: Black clay; moist, firm | | Sample collected 134-SB-134-1618 from 16.5 - 17.0 bgs @ 10:56 |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | 17.5 - 18.5' PT: Peat, dark brown clay; moist, firm; end of boring @ 18.5' bgs | | Sample collected 134-SB-134-1820 from 18.0 - 18.5 bgs @ 10:58; HOLD |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-135
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.75 | | 0.0 - 0.8' FILL: Dark brown fine to medium silty sand, fine to medium gravel, coal, and ash; dry, loose | 0 | |
| | -1.0 | | | | | 0.8 - 1.0' FILL: Reddish brown silt; moist, very soft | | Sample collected 134-SB-135-0002 from 1.0 - 1.5' bgs @ 11:37 |
| | -2.0 | | | | | 1.0 - 2.8' FILL: Red fine to medium silty sand; moist, loose | | |
| | -3.0 | | | | | 2.8 - 3.8' FILL: Brown clayey silt; trace organics; moist, stiff | | Sample colleced 134-SB-135-0204 from 3.0 - 3.5' bgs @ 11:39 |
| | -4.0 | | | 4.0 | | 3.8 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 4.3' FILL: Reddish brown silty clay; moist, stiff | | Sample collected 134-SB-135-0406 from 4.5 - 5.0' bgs @ 11:51 |
| | | | | | | 4.3 - 4.5' FILL: Brown medium to coarse sand, trace gravel; wet, loose | | |
| | | | | | | 4.5 - 5.5' FILL: Brown silty fine sand; trace gravel | | |
| | -6.0 | | | | | 5.5 - 6.0' FILL: Brown silty clay; moist, loose | | |
| | -7.0 | | | | | 6.0 - 8.0' FILL: Brown fine to medium sand; moist | | |
| | -8.0 | | | 3.0 | | 8.0 - 8.5' FILL: Brown silty sand; wet, loose | | Sample collected 134-SB-135-0608 from 7.5 - 8.0' bgs @ 11:53 |
| | -9.0 | | | | | 8.5 - 10.0' FILL: Brown silty sand; wet, loose | | Sample collected 134-SB-135-0810 from 8.5 - 9.0' bgs @ 12:02 |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-135
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | | | 3.5 | | 10.0 - 11.0' CL: Brown fine to medium sand, wet, loose | | Sample collected 134-SB-135-1012 from 10.0 - 10.5' bgs @ 12:04 |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | | | | | 12.0 - 13.5' CL: Brown fine to medium sand , wet, loose | | |
| | -13.0 | | | | | | | Sample collected 134-SB-135-1214 from 13.0 - 13.5' bgs @ 12:13 |
| | -14.0 | | | | | 13.5 - 15.5' OH: Black clay; moist, stiff; peat in tip | | |
| | -15.0 | | | | | | | Sample collected 134-SB-135-1416 from 14.5 - 15.0' bgs @ 12:15 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**DATE BEGAN:** 6/27/2011
**DRILLING CO:** B&B Drilling
**BIT TYPE/SIZE:**
**CORE TYPE/SIZE:**
**SAMPLING TOOL:** 4-ft Macrocore
**DRILLER:** E. Blewitt

**PROJECT NO:** 3480100027
**DATE FINISHED:** 6/27/2011
**DRILLING METHOD:** Direct Push
**CASING:**
**ROCK DEPTH:**
**COMPLETION DEPTH:** 18.0 ft bgs
**NORTH:**

**BORING ID:** 134-SB-136
**INSPECTOR:** M. Daly
**DRILL EQUIP:** Geoprobe 6610DT
**HAMMER:**
**PERMIT NO:**
**GW DEPTH:** 8.0' bgs
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 0.5' ASPHALT | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' SM: Reddish brown fine to medium sand; moist, loose | | Sample collected 134-SB-136-0002 from 0.5 - 1.0' bgs @ 8:08 |
| | -2.0 | | | | | 1.0 - 2.0' CL: Brown silty clay, trace gravel; moist, dense | | |
| | -3.0 | | | | | 2.0 - 2.5' ML: Reddish brown fine silty sand, trace gravel; dry, loose | | Sample colleced 134-SB-136-0204 from 2.5 - 3.0' bgs @ 8:10 |
| | | | | | | 2.5 - 3.0' CL: Brown silty clay, trace gravel; moist, dense | | |
| | -4.0 | | | 4.0 | | 3.0 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 6.0' SM: Brown silty fine sand; wet, loose | | Sample collected 134-SB-136-0406 from 4.5 - 5.0' bgs @ 8:19 |
| | -6.0 | | | | | 6.0 - 6.5' SM: Brown fine to medium sand; moist, loose | | |
| | -7.0 | | | | | 6.5 - 6.8' OL: Organic clay, trace peat and silt; moist, loose | | Sample collected 134-SB-136-0608 from 7.0 - 7.5' bgs @ 8:21 |
| ▽ | -8.0 | | | 3.0 | | 6.8 - 8.0' SM: Brown fine to medium sand, moist, loose | | |
| | -9.0 | | | | | 8.0 - 10.0' CL: Brown silty clay; wet, loose | | Sample collected 134-SB-136-0810 from 8.5 - 9.0' bgs @ 8:27 |
| | -10.0 | | | | | 10.0 - 11.0' SM: Brown fine to medium sand, trace silt and clay; wet, loose | | Sample collected 134-SB-136-1012 from 10.5 - 11.0' bgs @ 8:29 |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -12.0 | | | 4.0 | | 12.0 - 14.0' CH: Brown silty clay; wet, loose | | Sample collected 134-SB-136-1214 from 12.5 - 13.0' bgs @ 8:37 |
| | -13.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-136
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18.0 ft bgs
**GW DEPTH:** 8.0' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -14.0 | | | 2.0 | | 14.0 - 15.5' CL: Brown clay; wet, loose | | Sample collected 134-SB-136-1416 from 15.5 - 16.0' bgs @ 8:39<br>Sample collected 134-SB-136-16186 from 16.0 - 16.5' bgs @ 8:47 |
| | -15.0 | | | | | 15.5 - 16.0' OH: Black clay; moist, firm | | |
| | -16.0 | | | | | 16.0 - 18.0' PT: Peat, dark brown organic clay; moist, stiff; end of boring @ 18.0' bgs | | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-137
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 4.0 | | 0.0 - 0.5' ASPHALT | | Sample collected 134-SB-137-0002 from 0.5 - 1.0' bgs @ 9:04 |
| | -1.0 | | | | | 0.5 - 0.8' SILTY SAND: Dark gray fine to medium silty sand, moist, loose | | |
| | -2.0 | | | | | 0.8 - 4.0' SILTY SAND: Reddish brown fine to medium silty sand, trace coal and fine to medium gravel, moist, loose, black stain @ 3.75 ft bgs | | Sample colleced 134-SB-137-0204 from 3.5 - 4.0' bgs @ 9:06 |
| | -3.0 | | | | | | | |
| | -4.0 | | | 4.0 | | 4.0 - 5.5' SILTY SAND: Dark gray. reddish brown fine silty sand, very soft, wet, fine to medium gravel @4.2-4.4 ft bgs | | Sample collected 134-SB-137-0406 from 5.5 - 6.0' bgs @ 9:07 |
| | -5.0 | | | | | | | |
| | -6.0 | | | | | 5.5 - 6.0' SILT: Black silt, soft, wet | | |
| | -7.0 | | | | | 6.0 - 8.0' SAND: Grayish borwn fine to medium sand, wet, loose | | Sample collected 134-SB-137-0608 from 7.5 - 8.0' bgs @ 9:09 |
| | -8.0 | | | 3.0 | | 8.0 - 10.5' SAND: Grayish borwn fine to medium sand, wet, loose | | Sample collected 134-SB-137-0810 from 8.5 - 9.0' bgs @ 9:13 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 10.5 - 11.0' SILT: Brownish silt soft, loose | | Sample collected 134-SB-137-1012 from 10.5 - 11.0' bgs @ 9:15 |
| | -12.0 | | | | | 11.0 - 12.0' No recovery | | |
| | -13.0 | | | 3.5 | | 12.0 - 13.3' SILT: Brownish silt soft, loose | | |
| | -14.0 | | | | | 13.3 - 15.0' CLAY: Black clay, medium stiff, moist | | Sample collected 134-SB-137-1214 from 13.5 - 14.0' bgs @ 9:24 |
| | -15.0 | | | | | 15.0 - 15.5' PEAT: Peat, brown clay, moist, stiff | | Sample collected 134-SB-137-1416 from 14.5 - 15.0' bgs @ 9:26: HOLD |
| | -16.0 | | | | | 15.5 - 16.0' No recovery, End of boring @ 16.0 ft bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-138
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.0 | | 0.0 - 0.5' ASPHALT: gravel | 0 | |
| | -1.0 | | | | | 0.5 - 0.8' GRAVEL: Fine to medium | | Sample collected 134-SB-138-0002 from 0.5 - 1.0' bgs @ 9:36 |
| | -2.0 | | | | | 0.8 - 1.0' FILL: Reddish brown fine silty sand; moist, dense | | |
| | -3.0 | | | | | 1.0 - 3.0' CL: Brown silt, trace organics; stiff | | Sample colleced 134-SB-138-0204 from 2.5 - 3.0' bgs @ 9:38 |
| | -4.0 | | | 3.5 | | 3.0 - 4.0' No recovery | | |
| | -5.0 | | | | | 4.0 - 5.0' CL: Brown silt, layer of dark grey fine to medium sand from 4.25 - 4.35' bgs; wet | | Sample collected 134-SB-138-0406 from 4.5 - 5.0' bgs @ 9:40 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | 5.0 - 7.5' FILL: Greysih brown fine to medium sand, lenses of reddish brown silty stiff clay; wet, loose | | Sample collected 134-SB-138-0608 from 7.0 - 8.0' bgs @ 9:42: DUP @ 9:43 |
| | -8.0 | | | 3.0 | | 7.5 - 8.0' No recovery | | Sample collected 134-SB-138-0810 from 8.0 - 8.5' bgs @ 9:45 |
| | -9.0 | | | | | 8.0 - 11.0' FILL: Brown silty fine to medium sand; wet, medium stiff | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 134-SB-138-1012 from 10.5 - 11.0' bgs @ 9:47 |
| | -12.0 | | | 3.5 | | 12.0 - 14.0' CL: Brown silt, trace fine sand; wet, soft | | |
| | -13.0 | | | | | | | Sample collected 134-SB-138-1214 from 12.5 - 13.0' bgs @ 9:57 |
| | -14.0 | | | | | 14.0 - 15.0' OH: Black clay, moist, medium stiff | | |
| | -15.0 | | | | | 15.0 - 15.5' PT: Peat, brown clay, moist, very stiff | | Sample collected 134-SB-136-1416 from 14.5 - 15.0' bgs @ 9:59 |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring @ 16' bgs | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-139
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.5 | | 0.0 - 0.5' FILL: Brown fine to medium silty sand, fine to medium gravel; dry, loose | 0 | |
| | -1.0 | | | | | 0.5 - 1.0' CONCRETE: degraded | | Sample collected 134-SB-139-0002 from 1.0 - 1.5' bgs @ 10:06 |
| | -2.0 | | | | | 1.0 - 1.8' FILL: Red clayey silt, some brick and coal; moist, stiff | | |
| | -3.0 | | | | | 1.8 - 3.5' CL: Brown silt; moist, medium stiff | | Sample colleced 134-SB-139-0204 from 3.0 - 3.5' bgs @ 10:08; DUP @ 10:09 |
| | -4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | | | 3.5 | | 4.0 - 4.3' CL: Brown silt, moist, medium stiff | | |
| | -5.0 | | | | | 4.3 - 4.5' FILL: Dark brown fine to medium sand, trace coal; moist, dense | | Sample collected 134-SB-139-0406 from 5.0 - 5.5' bgs @ 10:10 |
| | -6.0 | | | | | 4.5 - 5.0' CL: Brown silt; wet, medium stiff | | |
| | -7.0 | | | | | 5.0 - 5.3' FILL: Black silt; wet, very soft | | Sample collected 134-SB-139-0608 from 6.5 - 7.0' bgs @ 10:12 |
| | -8.0 | | | | | 5.3 - 7.5' FILL: Dark grey to greyish brown fine to medium sand, trace silt; wet, loose | | |
| | | | | 3.5 | | 7.5 - 8.0' No recovery | | Sample collected 134-SB-139-0810 from 8.5 - 9.0' bgs @ 10:19 |
| | -9.0 | | | | | 8.0 - 10.5' FILL: Greyish brown fine to medium sand, trace silt; wet, loose | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 10.5 - 11.5' FILL : Brown medium to fine silty sand; wet, loose | | Sample collected 134-SB-139-1012 from 11.0 - 11.5' bgs @ 10:21 |
| | -12.0 | | | | | 11.5 - 12.0' No recovery | | |
| | | | | 4.0 | | 12.0 - 14.0' CL: Brown sandy silt; wet, soft | | Sample collected 134-SB-139-1214 from 12.5 - 13.0' bgs @ 10:29 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 14.5' CL: Brown silt; wet, soft | | |
| | -15.0 | | | | | 14.5 - 16.0' OL: Black clay; moist, medium stiff; peat in tip; end of boring @ 16.0' bgs | | Sample collected 134-SB-139-1416 from 14.5 - 15.0' bgs @ 10:31 |
| | -16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-140
**DATE BEGAN:** 6/27/2011
**DATE FINISHED:** 6/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**BIT TYPE/SIZE:**
**CASING:**
**HAMMER:**
**CORE TYPE/SIZE:**
**ROCK DEPTH:**
**PERMIT NO:**
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | 3.25 | | 0.0 - 1.0' FILL: Dark brown fine to medium silty sand, fine to medium gravel, trace ash and coal | 0 | Sample collected 134-SB-140-0002 from 1.5 - 2.0' bgs @ 10:39 |
| | -1.0 | | | | | 1.0 - 1.5' FILL: Reddish brown silt; moist, stiff | | |
| | -2.0 | | | | | 1.5 - 1.8' FILL: Reddish brown fine to medium silty sand; moist, dense | | Sample colleced 134-SB-140-0204 from 2.5 - 3.0' bgs @ 10:41 |
| | -3.0 | | | | | 1.8 - 2.0' FILL: Brown silt; moist, very stiff | | |
| | -4.0 | | | 4.0 | | 2.0 - 3.3' FILL: Brown sandy silt; moist, medium stiff | | |
| | -5.0 | | | | | 3.3 - 4.0' No recovery | | Sample collected 134-SB-140-0406 from 4.5 - 5.0' bgs @ 10:42 |
| | -6.0 | | | | | 4.0 - 4.3' FILL: Brown sandy silt; moist, medium stiff | | |
| | -7.0 | | | | | 4.3 - 4.5' GRAVEL: Brown silt, trace organics, wet, very soft | | Sample collected 134-SB-140-0608 from 7.0 - 7.5' bgs @ 10:44 |
| | -8.0 | | | 4.0 | | 4.5 - 5.0' FILL: Black silt | | Sample collected 134-SB-140-0810 from 8.0 - 8.5' bgs @ 10:55 |
| | -9.0 | | | | | 5.0 - 8.0' FILL: Greyish brown fine to medium sand, trace silt; wet, loose | | |
| | -10.0 | | | | | 8.0 - 9.0' FILL: Greyish brown fine to medium sand, trace silt; wet, loose | | |
| | -11.0 | | | | | 9.0 - 12.0' CL: Brown silt; wet, very soft | | Sample collected 134-SB-140-1012 from 11.0 - 11.5' bgs @ 10:57 |
| | -12.0 | | | 3.0 | | 12.0 - 13.0' CL: Brown silt; wet, soft | | |
| | -13.0 | | | | | 13.0 - 14.8' OH: Black clay, stiff, moist; peat in tip | | Sample collected 134-SB-140-1214 from 12.5 - 13.0' bgs @ 11:09 |
| | -14.0 | | | | | 14.8 - 15.0' PT: Peat, brown organic clay; moist, stiff; end of boring @ 16.0' bgs | | |
| | -15.0 | | | | | | | Sample collected 134-SB-139-1416 from 14.5 - 15.0' bgs @ 11:11; HOLD |
| | -16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134 Boatyard
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-141
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18.0 ft bgs
**GW DEPTH:** 4.0' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT: gravel | NA | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Light brown fine sand, some silt and fine to medium gravel; moist, loose | | Sample collected 134-SB-141-0002 from 1.0 - 1.5' bgs @ 8:27 |
| | 2.0 | | | | | 0.5 - 3.0' FILL: Reddish brown silt, lenses of brown fine to medium sand, moist, very dense | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 4.0 | | 3.0 - 4.0' SP: Greyish brown fine to medium sand, lenses of reddish brown silt; moist, dense | NA | |
| | 5.0 | | | | | 4.0 - 6.0' SP: Greyish brown fine to medium sand, lenses of reddish brown silt, fine to medium gravel from 5.75' to 5.85' bgs; wet, loose | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.0 - 6.5' CL: Reddish brown clay, some silt; wet, very firm | | |
| | 8.0 | S-3 | NA | 3.5 | | 6.5 - 8.0' SP: Greyish brown fine to medium sand; wet, loose | NA | |
| | 9.0 | | | | | 8.0 - 11.5' SP: Greyish brown fine to medium sand, trace nodlues of reddish brown silty clay, trace shells; wet, very loose | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 15.0' SP: Greyish brown fine to medium sand, trace nodlues of reddish brown silty clay, trace shells; wet, very loose | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' SM: Greyish brown fine sand, some brown silt (30%); moist, loose | | Sample colleced 134-SB-141-1416 from 15.5 - 16.0' bgs @ 8:50 |
| | 16.0 | | | 1.5 | | 16.0 - 16.8' ML: Brown silt, trace shells; wet, loose | | Sample collected 134-SB-141-1618 from 17.0 - 17.5' bgs @ 9:02: HOLD |
| | 17.0 | | | | | 16.8 - 17.3' OH: Black clay | | |
| | 18.0 | | | | | 17.3 - 17.5' PT: Dark brown clay, peat; ,moist, firm; end of boring @ 18.0' bgs | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Honeywell Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-142
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0' bgs
**DRILLER:** E. Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: gravel | NA | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Orange brown sand, some silt, fine to medium gravel; dry, loose | | Refusal @ 6" bgs,Petroleum odor, hit refusal again, cored through without success; moved to the south |
| | 2.0 | | | | | 0.5 - 0.8' GRAVEL | | |
| | 3.0 | | | | | 0.8 - 2.0' FILL: Dark grey fine to medium sand, some silt and fine to medium gravel; dry, loose | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.0 - 2.5' FILL: Reddish brown silt, some fine sand; moist, dense | NA | |
| | 5.0 | | | | | 2.5 - 3.0' FILL: Reddish brown silt; dry, very firm | | Petroleum odor, sheen from 4.5' bgs to 7.5' bgs, staining |
| | 6.0 | | | | | 3.0 - 3.5' FILL: Dark grey/orange brown fine to medium sand, some silt, lenses of silty clay; moist, loose | | |
| | 7.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 4.0 - 8.0' SP: Greysih brown fine sand, some silt, lenses of reddish brown silty clay; wet, loose | NA | Sample collected 134-SB-142-0810 from 8.5 - 9.0' bgs @ 10:26 |
| | 9.0 | | | | | 8.0 - 11.0' SP: Brown fine sand, trace shells; wet, soft | | |
| | 10.0 | | | | | 11.0 - 12.0' OL: Black silt; wet, soft | | |
| | 11.0 | | | | | 12.0 - 13.0' SM: Brown sand, some silt; wet, loose | | |
| | 12.0 | S-4 | NA | 3.5 | | 13.0 - 15.0' ML: Brown silt; soft, loose | | Sample collected 134-SB-142-1416 from 14.5 - 15.0' bgs @ 10:35 |
| | 13.0 | | | | | 15.0 - 15.5' OH: Black clay; wet, firm | | |
| | 14.0 | | | | | 15.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-143
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.2' ASPHALT: gravel | NA | Sample collected 134-SB-143-0002 from 1.0 - 1.5' bgs @ 12:05 |
| | | | | | | 0.2 - 0.5' CONCRETE | | |
| | | | | | | 0.5 - 1.0' FILL: Red silt, some fine gravel; moist, firm | | |
| | 1.0 | | | | | 1.0 - 1.1' CONCRETE: green staining | | |
| | | | | | | 1.1 - 2.0' FILL: Redi silt, some fine sand (15%), trace fine to medium gravel; moist, very firm; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-144
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.2' ASPHALT | NA | Sample collected 134-SB-144-0002 from 1.5 - 2.0' bgs @ 12:16 |
| | | | | | | 0.2 - 0.8' FILL: Brown silt, some fine sand (30%), fine to medium gravel; moist | | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Red silt, trace lenses of brown fine to medium sand, trace fine to medium gravel; moist; end of boring @ .20' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-145
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.3' ASPHALT | NA | Sample collected 134-SB-145-0002 from 1.5 - 2.0' bgs @ 12:27 |
| | | | | | | 0.3 - 0.8' FILL: Red silt, trace wood and fine to medium gravel; dry, loose | | |
| | | | | | | 0.8 - 1.0' FILL: Red silt, some clay; moist, firm | | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Reddish brown fine sand, some silt (40%); moist, loose; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-146
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' ASPHALT | NA | Sample collected 134-SB-146-0002 from 1.5 - 2.0' bgs @ 12:38 |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Red and black silt, some fine sand (25%), trace fine to medium gravel; dry, loose; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-147
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' ASPHALT | NA | Sample collected 134-SB-147-0002 from 1.5 - 2.0' bgs @ 11:08 |
| | 1.0 | | | | | 0.3 - 1.5' CONCRETE | | |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Reddish brown silt, trace fine sand; moist | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' FILL: Reddish brown silt; moist | NA | |
| | 5.0 | | | | | 4.0 - 8.0' SP: Greyish brown fine to medium sand, lenses of red silt, trace shells; wet, loose | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' SP: Greysih brown fine to medium sand, some silt (25%), trace medium gravel and shells; wet, loose | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.5 | | 12.0 - 15.5' SM: Brown silt, some fine sand (15%); wet, loose | NA | Sample collected 134-SB-147-1416 from 14.5 - 15.0' bgs @ 11:53 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 134-SB-148
**DATE BEGAN:** 11/8/2011
**DATE FINISHED:** 11/8/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | 3 | 1.8 | | 12.0 - 13.0' FILL: White/light gray clayey silt (possible COPR); soft, plastic, wet | 0 | Location HSA-19 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 13.0 | | 3 | | | 13.0 - 13.6' OH: Very dark grayish brown (2.5Y 3/2) clayey silt, trace organic material; few fine sand from 13.25-13.3'; possible COPR from 13.5-13.6'; medium stiff, plastic, wet | | |
| | | | 4 | | | 13.6 - 13.8' ML: Brown (10YR 4/3) silt; medium stiff, non-plastic, moist | | |
| | | | | | | 13.8 - 14.0' No recovery | | |
| | 14.0 | | WOH | 2.0 | | 14.0 - 15.2' OH: Black (2.5Y 2.5/1) clayey silt, trace organic material; soft, plastic, wet | 0 | |
| | | | 1 | | | | | |
| | 15.0 | | 3 | | | | | |
| | | | 4 | | | 15.2 - 16.0' PT: Dark brown (10YR 3/3) peat; soft, crumbly, moist; end of boring at 16' | | No sample collected for chromium analysis |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 134-SB-149
**DATE BEGAN:** 11/8/2011
**DATE FINISHED:** 11/8/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | WOH | 2.0 | | 12.0 - 13.0' FILL: Brown silty clay, little fine gravel from 12.0-12.1'; very soft, plastic, wet | 0 | Location HSA-21 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 13.0 | | 1 | | | 13.0 - 13.8' FILL: Brown/white/green silt, trace fine sand and clay (possible COPR); partially cemented from 13.0-13.2' and 13.4-13.6'; very soft, medium plastic, wet | | |
| | | | 3 | | | | | |
| | 14.0 | | 1 | 1.0 | | 13.8 - 14.0' OH: Very dark grayish brown/very dark gray (2.5Y 3/2 to 3/1) clayey silt, trace organic material; very soft, plastic, wet | 0 | |
| | | | 1 | | | 14.0 - 14.6' OH: Black (2.5Y 2.5/1) clayey silt, trace fine sand; soft, plastic, wet | | |
| | | | | | | 14.6 - 15.0' OH: Very dark grayish brown (2.5Y 3/2) silty clay, few organic material, trace fine sand; soft, plastic, wet | | |
| | 15.0 | | 2 | | | 15.0 - 16.0' No recovery | | |
| | | | 3 | | | | | |
| | 16.0 | | 2 | 2.0 | | 16.0 - 17.7' PT: Dark brown (10YR 3/3) peat; medium stiff, crumbly, moist | 0 | Collected 134-SB-149-1617 from 16.0-16.5 ft bgs @ 14:20 |
| | | | 2 | | | | | |
| | 17.0 | | 3 | | | | | |
| | | | 4 | | | 17.7 - 18.0' SM: Dark brown (10YR 3/3) fine sand and silt, some peat; loose, wet; end of boring at 18' | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 134-SB-150
**DATE BEGAN:** 11/11/2011
**DATE FINISHED:** 11/11/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | 1 | 2.0 | | 12.0 - 13.5' MH: Brown (10YR 3/2) silty clay, trace fine sand; very soft, plastic, wet | N/A | Location HSA-18 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 13.0 | | 1 | | | | | |
| | | | 2 | | | 13.5 - 14.5' OL: Very dark grayish brown/black (2.5Y 3/2 to 2.5/1) silt, little clay and organic material; very soft, medium plastic, wet; medium stiff from 14' | | |
| | 14.0 | | 2 | 1.8 | | | N/A | Collected 134-SB-150-1415 from 14.0-14.5 ft bgs @ 11:25 |
| | | | 2 | | | 14.5 - 16.0' PT: Dark brown (10YR 3/3) peat; medium stiff, crumbly, moist; end of boring at 16' | | |
| | 15.0 | | 4 | | | | | Collected 134-SB-150-1516 from 15.0-15.5 ft bgs @ 11:30 |
| | | | 4 | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 134-SB-151
**DATE BEGAN:** 11/11/2011
**DATE FINISHED:** 11/11/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | 2 | 2.0 | | 12.0 - 13.0' FILL: Light gray/brown clayey silt, trace fine sand (possible COPR); medium stiff, plastic, wet | N/A | Location HSA-20 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 3 | | | | | |
| | 13.0 | | 4 | | | 13.0 - 14.3' OH: Very dark grayish brown/very dark gray (2.5Y 3/2 to 3/1) clayey silt, trace fine sand and organic material; medium stiff, plastic, wet | | |
| | | | 2 | | | | | |
| | 14.0 | | 3 | 2.0 | | | N/A | |
| | | | 3 | | | 14.3 - 17.2' OH: Dark olive gray (5Y 3/2) silty clay, little organic material; medium stiff, plastic, wet; stiff from 16' | | Collected 134-SB-151-1415 from 14.5-15.0 ft bgs @ 13:45 |
| | 15.0 | | 5 | | | | | |
| | | | 5 | | | | | |
| | 16.0 | | 2 | 2.0 | | | N/A | |
| | | | 4 | | | | | |
| | 17.0 | | 5 | | | | | |
| | | | 5 | | | 17.2 - 17.8' PT: Dark brown (10YR 3/3) peat; stiff, moist | | |
| | 18.0 | | | | | 17.8 - 18.0' SC: Very dark gray (2.5YR 3/1) fine sand, some clay and silt; loose, wet; end of boring at 18' | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-152
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** Not encouuntered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.5 | | 0.0 - 1.3' CONCRETE | NA | Sample collected 134-SB-152-0002 from 1.0 - 1.5' bgs @ 13:05; DUP 13:07 |
| | 1.0 | | | | | 1.3 - 1.5' FILL: Reddish brown silt; dry, dense | | |
| | | | | | | 1.5 - 2.0' No recovery; end of boring at 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-153
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.5 | | 0.0 - 0.8' CONCRETE: Degraded | NA | Sample collected 134-SB-153-0002 from 1.0 - 1.5' bgs @ 13:20 |
| | | | | | | 0.8 - 1.5' FILL: Reddish brown silt, some fine to medium gravel, trace grey fine sand; moist, dense | | |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 2.0' No recovery; end of boring at 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-154
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.2' ASPHALT | NA | |
| | | | | | | 0.2 - 0.5' FILL: Dark brown fine to coarse sand and fine gravel; loose, dry | | |
| | | | | | | 0.5 - 1.0' CONCRETE | | |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Reddish brown/very dark grayish brown fine to coarse sand, some silt, little fine gravel, trace clinker, brick, coal, and concrete; medium dense, moist | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 4.0' FILL: Reddish brown silt, some lenses of fine to medium sand and fine gravel; stiff, dry; moist from 3.8'; end of boring at 4.0' | | Sample collected 134-SB-154-0204 from 3.5-4.0' bgs @ 12:10 |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-155
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.2' ASPHALT | NA | |
| | | | | | | 0.2 - 1.0' CONCRETE | | |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Very dark grayish brown/reddish brown fine to coarse sand, some silt and fine gravel; trace clinker, coal, brick, and concrete; medium dense, dry | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 4.0' FILL: Reddish brown silt, few lenses of fine to medium sand, trace fine gravel; stiff, moist from 3.8'; end of boring at 4.0' | | Sample collected 134-SB-155-0204 from 3.5-4.0' bgs @ 12:30 |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-156
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.2' ASPHALT | NA | Sample collected 134-SB-156-0002 from 1.5-2.0' bgs @ 11:55 |
| | | | | | | 0.2 - 1.0' CONCRETE | | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Brown fine to coarse sand, some fine to coarse gravel; trace silt, brick, coal; medium dense, dry | | |
| | 2.0 | | | | | 2.0 - 4.0' FILL: Reddish brown silt, some lenses of fine to medium sand, trace fine gravel; stiff, dry; moist from 3.8'; end of boring at 4.0' | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell SA-6 South

**LOCATION:** Site 134
**PROJECT NO:** 3480100027
**BORING ID:** 134-SB-157
**DATE BEGAN:** 1/16/2012
**DATE FINISHED:** 1/16/2012
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 540DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake/Brian
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT | NA | Refusal @ 2.0', moved to boatyard side of fence |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Brown fine sand, some silt, fine to medium gravel | | |
| | 2.0 | | | | | 0.5 - 1.3' CONCRETE | | |
| | 3.0 | | | | | 1.3 - 1.5' BRICK | | |
| | 4.0 | S-2 | NA | 3.0 | | 1.5 - 1.8' FILL: Grey silt, some fine sand, ash, coal; dry, loose | NA | |
| | 5.0 | | | | | 1.8 - 3.5' FILL: Reddish brown silt, lenses of reddish brown fine to medium sand, trace fine gravel; stiff, moist | | |
| | 6.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 7.0 | | | | | 4.0 - 5.5' FILL: Reddish brown fine to medium sand, lenses of reddish brown silt, trece fine gravele; loose, moist | | |
| | 8.0 | S-3 | NA | 4.0 | | 5.5 - 7.0' FILL: Greyish brown fine to medium sand, trace nodules of reddish brown clay; loose, moist | NA | Sample collected 134-SB-157-0810 from 8.0 - 8.5' bgs @ 14:45 |
| | 9.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 12.5' FILL: Greyish brown fine to medium sand, trace nodules of reddish brown clay; loose, moist | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 3.5 | | | NA | |
| | 13.0 | | | | | 12.5 - 13.5' OL: Brown silt; stiff, moist | | |
| | 14.0 | | | | | 13.5 - 14.5' SM: Brown silt, some fine sand; stiff, moist | | Sample collected 134-SB-157-1416 from 15.0 - 15.5' bgs @ 15:00 |
| | 15.0 | | | | | 14.5 - 15.3' MH: Brown fine sand, some silt; loose, wet | | |
| | 16.0 | | | | | 15.3 - 15.5' CL: Brown clay, trace fine brown sand, silt; stiff, moist | | |
| | | | | | | 15.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 134, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 134-SB-158
**DATE BEGAN:** 1/18/2012
**DATE FINISHED:** 1/18/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57; freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -14.0 | S-1 | 3<br>4 | 1.5 | | 14.0 - 14.3' FILL: Light brown silty COPR; stiff, dry<br>14.3 - 14.6' OH: Black (2/5 YR 2.5/1) silt, some clay, few COPR from 14.3-14.4'; medium stiff, plastic, wet | N/A | Adjacent to HSA-19. Augered to 14 ft bgs before sampling.<br>134-SB-158-1415 collected from 14.5 - 15.0' bgs @ 14:25 |
| | -15.0 | | 4<br>6 | | | 14.6 - 15.5' PT: Very dark brown (7.5 YR 2.5/3) peat; medium stiff, moist<br>15.5 - 16.0' No recovery; end of boring at 16' | | 134-SB-158-1516 collected from 15.0 - 15.5' bgs @ 14:30 (HOLD) |
| | -16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: MM

# Honeywell Study Area - 6 South

**LOCATION:** Site 134, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 134-SB-159
**DATE BEGAN:** 1/18/2012
**DATE FINISHED:** 1/18/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57; freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 15 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -13.0 | S-1 | 5 | | | 13.0 - 13.5' FILL: Grayish brown fine to medium sand and clayey COPR, trace black silt; loose, wet | N/A | Adjacent to HSA-20. Augered to 13 ft bgs before sampling. |
| | | | 3 | | | 13.5 - 14.0' OH: Black (2/5 YR 2.5/1) silt, some clay, trace organic material; soft, plastic, wet | | 134-SB-159-1314 collected from 13.5 - 14.0' bgs @ 14:55 |
| | -14.0 | | 2 | | | 14.0 - 15.0' OH: Dark olive gray (5Y 3/2) clay, little silt and organic material; medium stiff, plastic, wet; end of boring at 15' | | |
| | | | 2 | | | | | 134-SB-159-1415 collected from 14.5 - 15.0' bgs @ 15:00 |
| | -15.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: MM

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-163
**DATE BEGAN:** 8-20-14
**DATE FINISHED:** 8-20-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 9'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 5.0 | SS1 | 9 | 0.5 | | 5.0 - 5.5' SM: Reddish brown/black fine SAND and SILT | NM | Augered to 5' bgs |
| | | | 14 | | | 5.5 - 7.0' No recovery | | |
| | 6.0 | | 12 | | | | | |
| | | | 5 | | | | | |
| | 7.0 | SS2 | 2 | 1.25 | | 7.0 - 7.3' SM: Reddish brown fine SAND and SILT | | Sample taken at 8:40 |
| | | | 2 | | | 7.3 - 7.8' OL: Gray SILT with organics | | |
| | 8.0 | | 1 | | | 7.8 - 8.3' PT: Dark brown PEAT | | |
| | | | 2 | | | 8.3 - 9.0' No recovery. End of boring at 9.0' bgs. | | |
| | 9.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-164
**DATE BEGAN:** 8-20-14
**DATE FINISHED:** 8-20-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 16.5'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 3 | 1.0 | | 11.0 - 12.0' SM: Reddish brown/gray fine to coarse SAND, trace silt | NM | Augered to 11' bgs |
| | | | 8 | | | | | |
| | 12.0 | | 16 | | | 12.0 - 13.0' No recovery | | |
| | | | 21 | | | | | |
| | 13.0 | SS2 | 9 | 2.0 | | 13.0 - 15.8' SM: Reddish brown/gray fine to coarse SAND, trace silt | | |
| | | | 15 | | | | | |
| | 14.0 | | 22 | | | | | |
| | | | 26 | | | | | |
| | 15.0 | SS3 | 4 | 1.5 | | | | Sample from 15.25-15.75 at 13:40 |
| | | | 12 | | | | | |
| | | | | | | 15.8 - 15.9' OL: Black SILT with organics | | |
| | 16.0 | | 16 | | | 15.9 - 16.5' PT: Dark brown PEAT | | |
| | | | 15 | | | 16.5 - 17.0' No recovery. End of boring at 17.0' bgs. | | |
| | 17.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-165
**DATE BEGAN:** 8-21-14
**DATE FINISHED:** 8-21-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 3 | 1.0 | | 11.0 - 12.0' SM: Brown/gray coarse SAND, trace silt | NM | Augered to 11' bgs |
| | | | 2 | | | | | |
| | 12.0 | | 2 | | | 12.0 - 13.0' No recovery | | |
| | | | 4 | | | | | |
| | 13.0 | SS2 | 1 | 1.75 | | 13.0 - 13.3' SM: Brown/gray coarse SAND, trace silt | | |
| | | | 1 | | | 13.3 - 14.3' ML: Reddish brown CLAYEY SILT | | |
| | 14.0 | | 2 | | | | | |
| | | | 3 | | | 14.3 - 14.8' OL: Gray SILT with organics | | Sample collected from 14.25 at 7:15<br>DPC test negative |
| | 15.0 | | | | | 14.8 - 15.0' No recovery. End of boring at 15.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-166
**DATE BEGAN:** 8-21-14
**DATE FINISHED:** 8-21-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 6 | 1.0 | | 11.0 - 12.0' SM: Brownish gray fine to coarse SAND, silt in tip | NM | Augered to 11' bgs |
| | | | 6 | | | | | |
| | 12.0 | | 3 | | | 12.0 - 13.0' No recovery | | |
| | | | 3 | | | | | |
| | 13.0 | SS2 | 2 | 2.0 | | 13.0 - 13.5' SM: Brownish gray fine to coarse SAND, silt in tip | | Sample collected at 13:30<br>DPC test negative |
| | | | 3 | | | 13.5 - 14.0' ML: Reddish brown/black interlayered SILT | | |
| | 14.0 | | 2 | | | 14.0 - 15.0' OL: Black/dark gray SILT with organic fibers. End of boring at 15.0' bgs. | | |
| | | | 3 | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-174
**DATE BEGAN:** 9-11-14
**DATE FINISHED:** 9-11-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 14.5'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | SS1 | 8 | 1.0 | | 10.5 - 11.5' SM: Reddish brown fine SAND and SILT | NM | Augered to 10.5' bgs |
| | 11.0 | | 5 | | | | | |
| | | | 4 | | | 11.5 - 12.5' No recovery | | |
| | 12.0 | | 5 | | | | | |
| | | SS2 | 2 | 1.75 | | 12.5 - 13.3' SM: Dark brown fine SAND and SILT | | |
| | 13.0 | | 2 | | | | | |
| | | | | | | 13.3 - 13.4' ML: Brown SILT; very hard | | Sample collected from 13.25-13.75 at 10:40 |
| | | | 3 | | | 13.4 - 13.5' ML: Brown/greenish gray layered SILT | | |
| | | | | | | 13.5 - 13.7' ML: Brown/black layered SILT | | |
| | | | | | | 13.7 - 14.3' OL: Black SILT with organics | | |
| | 14.0 | | 3 | | | | | |
| | | | | | | 14.3 - 14.5' No recovery. End of boring at 14.5' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 134
**PROJECT NO:** 3480130354
**BORING ID:** 134-SB-602
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 685197.6285
**EAST:** 601865.6293

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 4.0' Push to 4.0 ft bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-1 | NA | 3.5 | | 4.0 - 4.5' FILL: Reddish-brown to dark brown SILT, some medium to fine sand, medium to fine gravel; loose; moist | 0.1 | Sample 134-SB-602-NI1 from 4.0-6.0 ft bgs @ 1045 (2 jars); EnCore taken from 134-SB-602-NI1 @ 1045 |
| | 5.0 | | | | | 4.5 - 5.5' FILL: Brown SILT, lense of black silt, some fine sand; medium dense; moist | 1.1<br>0.5 | |
| | 6.0 | | | | | 5.5 - 6.0' FILL: Dark brown clayey SILT, some fine sand; medium dense; moist | 1.2 | |
| | | | | | | 6.0 - 7.0' FILL: Dark brown/black CLAY; soft; moist | 0.6<br>0.6 | |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Brown coarse to fine SAND, some silt; loose; moist | 0.7 | |
| | 8.0 | | | | | 7.5 - 8.0' No Recovery | 0.3 | End of boring at 8 ft bgs. |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-603-R
**DATE BEGAN:** 5/13/14
**DATE FINISHED:** 5/13/14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct push
**DRILL EQUIP:** Geoprobe 220
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:**
**DRILLER:** Gordon Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | N/A | 3.0 | | 0.0 - 3.0' FILL: Brown fine SAND, some fine gravel; loose, moist | 0.0 | Sample 134-SB-603-R1 (0.0'-4.0') @ 11:30 |
| | 1.0 | | | | | | 0.0 | |
| | 2.0 | | | | | | 0.0 | |
| | 3.0 | | | | | | 0.0 | |
| | 4.0 | | | | | | 0.0 | |
| | | | | | | 3.0 - 4.0' No Recovery | | |
| | | | N/A | 3.5 | | 4.0 - 4.5' FILL: Brown fine SAND, some fine gravel; loose, moist | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.5' FILL: Brown to olive green SILT, fine sand, some fine gravel; medium dense, moist | 0.0 | |
| | 6.0 | | | | | 5.5 - 7.5' FILL: Black SILT, fine sand; medium dense, moist | 0.0 | |
| | 7.0 | | | | | | 0.0 | |
| | | | | | | 7.0 - 8.0' No Recovery | 0.0 | |
| | 8.0 | | N/A | 4.0 | | 8.0 - 10.0' FILL: Reddish brown SILT | 0.0 | |
| | 9.0 | | | | | | 0.0 | |
| | 10.0 | | | | | | 0.0 | |
| | | | | | | 10.0 - 11.0' ML: Black CLAYEY SILT; loose, wet | 0.0 | Sample 134-SB-603-R2 (10.4'-12.1') @ 11:45; Encores taken |
| | 11.0 | | | | | | 0.4 | |
| | | | | | | 11.0 - 12.0' SP: Brown fine SAND; medium dense, wet; End of boring at 12' | 0.0 | |
| | 12.0 | | | | | | 0.0 | |

PREPARED BY: GB
CHECKED BY: MS

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 140-MW-08R
**DATE BEGAN:** 6-6-16
**DATE FINISHED:** 6-6-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 3.5' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 2 | 2.0 | | 10.0 - 10.5' SW: Gray fine to coarse SAND; loose, wet | NM | Starting elevation 7.5'<br><br>Augered to 10.0' bgs |
| | | | 2 | | | 10.5 - 12.0' PEAT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 11.0 | | 3 | | | | | |
| | | | 4 | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 140-MW-09
**DATE BEGAN:** 2-12-16
**DATE FINISHED:** 2-12-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 3 | 2.0 | | 10.0 - 13.8' SW: Gray fine to coarse SAND, trace reddish brown silt; loose, wet | NM | Augered to 10' bgs<br>Starting elevation 8.75'<br>GW elevation 4.75' |
| | | | 3 | | | | | |
| | 11.0 | | 4 | | | | | |
| | | | 16 | | | | | Meadow mat expected at -3 elevation (11.75' bgs) |
| | 12.0 | SS2 | 5 | 2.0 | | | | |
| | | | 6 | | | | | |
| | 13.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | | | | | | 13.8 - 13.9' ML: Black SILT | | |
| | 14.0 | | | | | 13.9 - 14.0' OL: Dark gray SILT with organics. End of boring at 14.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 140-MW-10
**DATE BEGAN:** 2-11-16
**DATE FINISHED:** 2-11-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 10' bgs
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | | | | | | | |
| | | SS1 | 75 | 1.75 | | 8.0 - 9.8' SW: Screenings, fine to coarse SAND, crushed concrete; dense, wet | NM | Augered to 8' bgs<br><br>Starting elevation 7.0' |
| | | | 35 | | | | | |
| | 9.0 | | 42 | | | | | Meadow mat expected at -2 elevation (9.0' bgs) |
| | | | 7 | | | 9.8 - 9.8' OL: Dark gray SILT with organics (tip of shoe) | | |
| | | | | | | 9.8 - 10.0' No recovery. End of boring at 10.0' bgs. | | |
| | 10.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 140-SB-001 | **SITE ID:** 140

**DATE BEGAN:** 6/20/2005 | **DATE FINISHED:** 6/20/2005 | **INSPECTOR:** CH

**DRILLING CO:** EPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Ron Higgins | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 20.0 ft bgs | **GW DEPTH:** 5 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT: Asphalt, DGA | | | |
| | -1.0 | | | | | | | 4.3 | |
| | -2.0 | | | | | FILL: Dark brown, sand, medium - coarse; wood; topsoil | | 1.9 | 140-SB-001_010 collected from 1-1.5 ft bgs @ 1603 |
| | -3.0 | | | | | FILL: Dark brown, sand, med-coarse; gravel, concrete, ash | | 0 | |
| | -4.0 | S-2 | | 4 | | FILL: Dark brown, clayey sand, med-coarse | | 0 | |
| -5.0 | -5.0 | | | | | FILL: Dark brown, sand, fine | | | |
| | -6.0 | | | | | FILL: Dark brown - black, clay; organic odor | | | |
| | -7.0 | | | | | FILL: White, sand, med-fine; trace clay silt | | | |
| | -8.0 | S-3 | | 4 | | FILL: Reddish brown, silt, hardened mud | | 0 | |
| | -9.0 | | | | | FILL: Dark brown, clayey sand, fine; organic odor; wood | | | |
| -10.0 | -10.0 | | | | | FILL: Light brown med-fine sand | | | |
| | -11.0 | | | | | FILL: Dark brown, clay; wood; hardened mud fragments | | | |
| | -12.0 | S-4 | | 3.5 | | FILL: Dark brown, sandy clay | | 0 | |
| | -13.0 | | | | | | | | |
| | -14.0 | | | | | | | | |
| -15.0 | -15.0 | | | | | | | | |
| | -16.0 | S-5 | | 4 | | FILL: Sand, coarse; gravel, brick; some silt | | 0 | |
| | -17.0 | | | | | | | | |
| | -18.0 | | | | | PT: Peat | | | 140-SB-001_009 collected from 18.0-18.5t bgs @ 1556 |
| | -19.0 | | | | | ML: Dark Brown, sandy silt, fine | | | |
| -20.0 | -20.0 | | | | | End boring @ 20' | | | |
| | -21.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 **BORING NO:** 140-SB-002 **SITE ID:** 140

**DATE BEGAN:** 6/20/2005 **DATE FINISHED:** 6/20/2005 **INSPECTOR:** CH

**DRILLING CO:** EPI **DRILLING METHOD:** Direct Push **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Ron Higgins **NORTH:** **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore **COMPLETION DEPTH:** 20.0 ft bgs **GW DEPTH:** NA

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 3 | | ASPHALT: Asphalt | | | |
| | -1.0 | | | | | FILL: Light brown, sand, coarse; some coarse gravel | | 0 | 140-SB-002_003 collected from 1.5-2.0 ft bgs @ 1412 |
| | -2.0 | | | | | | | | |
| | -3.0 | | | | | | | | |
| | -4.0 | S-2 | | 3 | | FILL: Light brown, sand, coarse; some coarse gravel | | | |
| -5.0 | -5.0 | | | | | FILL: Asphalt, DGA | | 0 | |
| | -6.0 | | | | | FILL: Green, gray, & orange, silt; brick, gravel | | | 140-SB-002_004 collected from 6.0-6.5t bgs @ 1416 |
| | -7.0 | | | | | | | | |
| | -8.0 | S-3 | | 4 | | FILL: Green, gray, & orange, silt; brick, gravel | | 0 | |
| | -9.0 | | | | | FILL: Dark brown, sand, fine; some clay spots | | | |
| -10.0 | -10.0 | | | | | | | | 140-SB-002_006 collected from 10.0-10.5 bgs @ 1424 |
| | -11.0 | | | | | FILL: Brown, clay; trace organic material/odor | | 1.9 | |
| | -12.0 | S-4 | | 4 | | FILL: Sand, fine; green traces (suspected COPR) | | 0 | 140-SB-002_005 collected from 11.5-12.0 bgs @ 1420 |
| | -13.0 | | | | | | | | |
| | -14.0 | | | | | | | | |
| -15.0 | -15.0 | | | | | | | 0 | 140-SB-002_007 collected from 15.0-15.5 bgs @ 1430 |
| | -16.0 | S-5 | | 4 | | SC: Reddish brown, sandy clay, fine-medium; 10R-3/2 | | | |
| | -17.0 | | | | | | | | |
| | -18.0 | | | | | | | | |
| | -19.0 | | | | | | | | |
| -20.0 | -20.0 | | | | | | | | 140-SB-002_008 collected from 19.5-20.0 bgs @ 1436 |
| | -21.0 | | | | | End boring @ 20' | | 0 | |

# Honeywell Study Area - 6 South

**PROJECT NO:** 3480050143 | **BORING NO:** 140-SB-003 | **SITE ID:** 140

**DATE BEGAN:** 6/20/2005 | **DATE FINISHED:** 6/20/2005 | **INSPECTOR:** CH

**DRILLING CO:** EPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Hurricane 5500

**DRILLER:** Ron Higgins | **NORTH:** | **EAST:**

**SAMPLING TOOL:** 2-inch diameter macrocore | **COMPLETION DEPTH:** 16.0 ft bgs | **GW DEPTH:** 2 ft bgs

| ELEV (FT.) | DEPTH (FT.) | SAMPLE NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | USCS | VOLATILE ORGANIC VAPORS (PPM) PID | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| 0.0 | 0.0 | S-1 | N/A | 4 | | ASPHALT: Asphalt, DGA | | 0 | |
| | -1.0 | | | | | FILL: Topsoil; some gravel, medium - coarse | | 1.9 | |
| | -2.0 | | | | | FILL: Brown, sand, medium - coarse; trace topsoil | | 2.2<br>0 | 140-SB-003_011 collected from 1.5-2.0 ft bgs @ 1115 |
| | -3.0 | | | | | FILL: Dark brown - black, sand, medium - coarse | | | 140-SB-003_012 collected from 1.5-2.0 bgs @ 1116 |
| | -4.0 | S-2 | | 4 | | | | | 140-SB-003_013 collected from 3.5-4.0 bgs @ 1119 |
| -5.0 | -5.0 | | | | | FILL: Red - brown, clay; some sand, coarse | | | |
| | -6.0 | | | | | FILL: Red - brown, sand, coarse | | | |
| | -7.0 | | | | | FILL: Red - brown, clay; some sand, coarse | | | |
| | -8.0 | S-3 | | 4 | | FILL: Reddish brown, sand; some clay | | 0 | 140-SB-003_014, MS_015 and MD_016 collected from 7.5-8.0 bgs @ 1123 |
| -10.0 | -9.0 | | | | | | | | |
| | -10.0 | | | | | | | | |
| | -11.0 | | | | | | | | |
| | -12.0 | S-4 | | 4 | | | | 0 | 140-SB-003_017 collected from 11.5-12.0 bgs @ 1129 |
| | -13.0 | | | | | | | | |
| | -14.0 | | | | | FILL: Reddish brown, clayey sand, coarse | | | |
| -15.0 | -15.0 | | | | | FILL: Brown - black, clay; trace organics | | | 140-SB-003_018 collected from 15.0-15.5 bgs @ 1135 |
| | -16.0 | | | | | PT: Peat | | 19.8<br>24.7 | 140-SB-003_019 collected from 15.0-15.5 bgs @ 1136 |
| | -17.0 | | | | | End boring @ 16' | | | |
| | -18.0 | | | | | | | | |

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-003A
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 0.9' ASPHALT | 0 | |
| | -1.0 | | | | | 0.9 - 1.2' CONCRETE | 0 | |
| | -2.0 | | | | | 1.2 - 3.5' FILL: brown silty sand, some fine to medium gravel and clayey silt lenses; moist | 0 | |
| | -3.0 | | | | | | 0 | |
| | -4.0 | S-2 | N/A | 4.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 12.0' FILL: brown silty sand, trace shells and fine to medium gravel; wet from 4.0' | 0 | |
| | -6.0 | | | | | | 0 | |
| | -7.0 | | | | | | 0 | |
| | -8.0 | S-3 | N/A | 4.0 | | | 0 | |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | | 0 | |
| | -12.0 | S-4 | N/A | 4.0 | | 12.0 - 13.0' FILL: light brown clayey silt; moist | 0 | |
| | -13.0 | | | | | 13.0 - 14.0' FILL: light brown/black silt; moist | 0 | |
| | -14.0 | | | | | 14.0 - 16.0' PT: dark brown peat; moist; end of boring at 16' | 0 | |
| | -15.0 | | | | | | 0 | 140-SB-003A-1416 from 15.0-15.5' bgs @ 1440 |
| | -16.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-004
**DATE BEGAN:** 7/10/08
**DATE FINISHED:** 7/10/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel, dry | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Dark brown angular gravel (fine-coarse), some silt; moist | | |
| | -2.0 | | | | | 1.5 - 3.5' FILL: Red brown sandy silt, some angular gravel, 2" lens of light gray/white clay at 3.3'; stiff, moist | | 140-SB-004_0002 collected from 1.5-2' bgs @ 8:42 |
| | -3.0 | | | | | | | 140-SB-004_0204 collected form 3-3.5' bgs @ 8:45 |
| | -4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 4.5' FILL: Light brown sand and gravel (fine-coarse); loose, wet | | 140-SB-004_0406 collected from 4.5-5' bgs @ 8:48 |
| | -6.0 | | | | | 4.5 - 5.0' FILL: Light brown sandy clay, some gravel (fine-medium); wet | | |
| | -7.0 | | | | | 5.0 - 7.5' FILL: Clayey sand, lenses of fine-medium sand; firm, wet | | 140-SB-004_0608 collected from 7-7.5' bgs @ 8:51 |
| | -8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' FILL: Light brown sand (fine-medium), wet | 0 | |
| | -9.0 | | | | | 8.0 - 11.5' FILL: Light brown sand (fine-coarse); firm, wet | | 140-SB-004_0810 collected from 9-9.5' bgs @ 9:20 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 140-SB-004_1012 collected from 11-11.5' bgs @ 9:23 |
| | -12.0 | S-4 | NA | 4.0 | | 11.5 - 12.0' FILL: Light brown silty clay, trace shells; soft, wet | 0 | |
| | -13.0 | | | | | 12.0 - 12.5' FILL: Light brown sand (fine-medium) and silt; loose, wet | | 140-SB-004_1214 collected form 13-13.5' bgs @ 9:40 |
| | -14.0 | | | | | 12.5 - 15.5' FILL: Light brown silty clay; soft, wet | | |
| | -15.0 | | | | | 15.5 - 16.0' OL: Dark brown/black silt and clay, organic odor, peat in tip; soft, wet; end of boring at 16' | | 140-SB-004_1416 collected from 15-15.5' bgs @ 9:43 |
| | -16.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-005
**DATE BEGAN:** 7/10/08
**DATE FINISHED:** 7/10/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | 140-SB-005_0002 collected from 1-1.5' bgs @ 10:15 |
| | -1.0 | | | | | 0.8 - 1.5' FILL: Brown silt and trace sand; firm, moist | | |
| | -2.0 | | | | | 1.5 - 2.0' FILL: Dark brown gravel (fine-medium), trace sand; moist | | 140-SB-005_0204 collected from 2-2.5' bgs @ 10:18 |
| | -3.0 | | | | | 2.0 - 2.5' FILL: Red brown silt, 1" olive green COPR lens at 2.15', 1" concrete at 2.25' | | |
| | -4.0 | S-2 | NA | 4.0 | | 2.5 - 4.0' No recovery | 0 | 140-SB-005_0406 collected from 4-4.5' bgs @ 10:25 |
| | -5.0 | | | | | 4.0 - 5.0' FILL: Brown gravelly sand, some clay and silt; wet | | |
| | -6.0 | | | | | 5.0 - 7.5' FILL: Light red/brown sand (fine-medium), trace clay lenses; wet | | 140-SB-005_0608 collected form 6.5-7' bgs @ 10:28 |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' FILL: Light brown sand (fine-medium), some clay; wet | 0 | 140-SB-005_0810 collected from 9-9.5' bgs @ 10:45 |
| | -9.0 | | | | | 8.0 - 12.0' FILL: Light brown sand (fine-medium), trace clay lenses; compact, wet | | |
| | -10.0 | | | | | | | 140-SB-005_1012 collected form 11.5-12' bgs @ 10:48 |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 13.0' FILL: Light brown silty clay, trace sand; very soft, wet | 0 | 140-SB-005_1214 collected from 12.5-13' bgs @ 11:15 |
| | -13.0 | | | | | 13.0 - 15.5' OL: Dark brown organic silty clay, wet | | |
| | -14.0 | | | | | | | 140-SB-005_1416 collected from 14-14.5' bgs @ 11:18 |
| | -15.0 | | | | | 15.5 - 16.0' OL: Light brown organic silt and clay, some peat; end of boring at 16' | | |
| | -16.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-006
**DATE BEGAN:** 7/10/08
**DATE FINISHED:** 7/10/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 17' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 0.0 | | 0.0 - 4.0' No recovery | 0 | Liner stuck in macrocore |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | Switched from truck-mounted 5410 rig to 6610 DT track rig and resumed drilling |
| | -3.0 | | | | | | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 4.5' FILL: Red brown gravelly sand and clay, wet | 0 | 140-SB-006_0406 collected from 4.5-5' bgs @ 13:13 |
| | -5.0 | | | | | 4.5 - 5.0' FILL: Red brown sandy silt; firm, moist | | |
| | -6.0 | | | | | 5.0 - 7.0' FILL: Brown silty clay, trace gravel; wet | | |
| | -7.0 | | | | | 7.0 - 8.0' FILL: Light brown sand (fine-medium); compact, wet | | 140-SB-006_0608 collected from 7-7.5' bgs @ 13:16 |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 10.0' FILL: Light brown sand (fine-coarse), compact, wet | 0 | 140-SB-006_0810 collected from 8-8.5' bgs @ 13:26 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 12.0' FILL: Light brown sand (fine-medium), trace clay; wet | | |
| | -11.0 | | | | | | | 140-SB-006_1012 collected from 11-11.5' bgs @ 13:28 |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 12.5' FILL: Light brown sand (fine); dense, wet | 0 | |
| | -13.0 | | | | | 12.5 - 15.5' FILL: Light brown silty clay; very soft, wet | | 140-SB-006_1214 collected from 12.5-13' bgs @ 13:37; DUP @ 13:40 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | 15.5 - 16.0' OH: Dark brown/black silty clay, organic material; soft | | 140-SB-006_1416 collected from 15-15.5' bgs @ 13:43 |
| | -16.0 | S-5 | NA | 1.0 | | 16.0 - 17.0' PT: Peat, sand in tip; end of boring at 17' | 0 | Driller grouted borehole |
| | -17.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-007
**DATE BEGAN:** 7/10/08
**DATE FINISHED:** 7/10/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18' bgs
**GW DEPTH:** 5.75' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Light brown silt, some angular gravel; dry | | |
| | -1.0 | | | | | 1.0 - 1.5' FILL: Asphalt and gravel, dry | | 140-SB-007_0002 collected from 1.5-2' bgs @ 14:35 |
| | -2.0 | | | | | 1.5 - 3.5' FILL: Dark brown/black silt; stiff, moist | | |
| | -3.0 | | | | | | | 140-SB-007_0204 collected from 3-3.5' bgs @ 14:38 |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 4.3' FILL: Dark brown/black silt; stiff, moist | 0 | 140-SB-007_0406 collected from 4-4.5' bgs @ 14:45; DUP @ 14:46 |
| | -5.0 | | | | | 4.3 - 4.5' FILL: Black sand (medium-coarse) and gravel, dry | | |
| | | | | | | 4.5 - 4.8' FILL: Dark brown/black silty clay, moist | | |
| | -6.0 | | | | | 4.8 - 5.8' FILL: Concrete | | 140-SB-007_0608 collected from 6.5-7' bgs @ 14:48 |
| | -7.0 | | | | | 5.8 - 6.5' FILL: Red brown sand (medium-coarse), tracel clay; wet | | |
| | | | | | | 6.5 - 7.8' FILL: Red brown/brown silty clay; firm, wet | | |
| | -8.0 | S-3 | NA | 4.0 | | 7.8 - 8.0' FILL: Dark brown sand (fine-medium); compact, wet | 0 | 140-SB-007_0810 collected from 8-8.5' bgs @ 14:55 |
| | -9.0 | | | | | 8.0 - 9.0' FILL: Light brown sand (fine-medium), trace rounded gravel (fine); dense, wet | | |
| | -10.0 | | | | | 9.0 - 11.0' FILL: Light brown sand (fine-medium), trace rounded gravel (fine); dense, wet | | |
| | -11.0 | | | | | 11.0 - 12.0' FILL: Light brown sand (fine), 1" silty clay lenses @ 11.2', 11.5', and 11.75', wet | | |
| | -12.0 | S-4 | NA | 4.0 | | | 0 | 140-SB-007_1012 collected from 11.5-12' bgs @ 14:58 |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-007
**DATE BEGAN:** 7/10/08
**DATE FINISHED:** 7/10/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18' bgs
**GW DEPTH:** 5.75' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -12.0 | | | | | | | |
| | -13.0 | | | | | 12.0 - 14.0' FILL: Light brown clayey silt; very soft, wet | | 140-SB-007_1214 collected form 13.5-14' bgs @ 15:09 |
| | -14.0 | | | | | 14.0 - 15.0' FILL: Light/yellow brown silty clay, wet | | |
| | -15.0 | | | | | 15.0 - 16.0' FILL: Dark/light brown silty clay, some angular gravel (fine-medium), less clay at tip, wet | | 140-SB-007_1416 collected from 15.5-16' bgs @ 15:12 |
| | -16.0 | S-5 | NA | 2.0 | | 16.0 - 17.5' CL: Light/dark brown/black clay, some silt; soft, wet, organic odor | 0 | |
| | -17.0 | | | | | | | |
| | -18.0 | | | | | 17.5 - 18.0' PT: Peat; end of boring at 18' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-007R
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft. bgs
**GW DEPTH:** 5.75' bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Light brown silt, some angular gravel; dry | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Asphalt and gravel, dry | | |
| | 2.0 | | | | | 1.5 - 3.5' FILL: Dark brown/black silt; stiff, moist | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 4.3' FILL: Dark brown/black silt; stiff, moist | 0 | |
| | | | | | | 4.3 - 4.5' FILL: Black sand (medium-coarse) and gravel, dry | | |
| | 5.0 | | | | | 4.5 - 4.8' FILL: Dark brown/black silty clay, moist | | |
| | 6.0 | | | | | 4.8 - 5.8' FILL: Concrete | | |
| | 7.0 | | | | | 5.8 - 6.5' FILL: Red brown sand (medium-coarse), tracel clay; wet | | |
| | 8.0 | S-3 | NA | 4.0 | | 6.5 - 7.8' FILL: Red brown/brown silty clay; firm, wet | 0 | |
| | | | | | | 7.8 - 8.0' FILL: Dark brown sand (fine-medium); compact, wet | | |
| | 9.0 | | | | | 8.0 - 9.0' FILL: Light brown sand (fine-medium), trace rounded gravel (fine); dense, wet | | |
| | 10.0 | | | | | 9.0 - 11.0' FILL: Light brown sand (fine-medium), trace rounded gravel (fine); dense, wet | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Light brown sand (fine), 1" silty clay lenses @ 11.2', 11.5', and 11.75', wet | | |
| | 12.0 | S-4 | NA | 4.0 | | | 0 | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** **140-SB-007R**
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 18 ft. bgs
**GW DEPTH:** 5.75' bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | | | | | 12.0 - 14.0' FILL: Light brown clayey silt; very soft, wet | | |
| | 14.0 | | | | | 14.0 - 15.0' FILL: Light/yellow brown silty clay, wet | | |
| | 15.0 | | | | | 15.0 - 16.0' FILL: Dark/light brown silty clay, some angular gravel (fine-medium), less clay at tip, wet | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 17.5' CL: Black clayey silt | 0 | 140-SB-007R-1618 collected from 16.0-16.5' bgs @ 9:50 |
| | 17.0 | | | | | 17.5 - 18.0' PT: Brown peat; moist; end of boring at 18' bgs. | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: BS

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-008
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** B. Senna/T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 5.5' bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 1.0 - 2.0' FILL: Dark brown silty sand (fine), some gravel (fine-medium); moist | | 140-SB-008_0002 collected from 1.5-2' bgs @ 7:35 |
| | -2.0 | | | | | 2.0 - 3.5' FILL: Red brown silt, some sand (fine-medium); moist | | |
| | -3.0 | | | | | | | 140-SB-008_0204 collected from 3-3.5' bgs @ 7:40 |
| | -4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 4.8' FILL: Dark brown silty sand (fine), some gravel (fine), trace metal fragments | | 140-SB-008_0406 collected from 4.5-5' bgs @ 7:45 |
| | -6.0 | | | | | 4.8 - 7.0' FILL: Light brown sand (fine-medium), some red brown silt lenses; moist, wet from 5.5' | | |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | 140-SB-008_0608 collected form 6.5-7' bgs @ 7:50 |
| | -8.0 | S-3 | NA | 3.0 | | 8.0 - 9.5' FILL: Light brown sand (fine), trace silt; wet | 0 | |
| | -9.0 | | | | | | | 140-SB-008_0810 collected from 8.5-9' bgs @ 7:55 |
| | -10.0 | | | | | 9.5 - 10.5' FILL: Red/light brown silt, some sand (fine); wet | | |
| | -11.0 | | | | | 10.5 - 10.8' FILL: Light brown clayey silt | | 140-SB-008_1012 collected from 10.5-11' bgs @ 8:00 |
| | -12.0 | S-4 | NA | 3.0 | | 10.8 - 11.0' FILL: Light brown silt | 0 | |
| | -13.0 | | | | | 11.0 - 12.0' No recovery | | 140-SB-008_1214 collected from 12-12.5' bgs @ 8:05 |
| | -14.0 | | | | | 12.0 - 13.0' FILL: Light brown clayey silt; firm, moist | | |
| | -15.0 | | | | | 13.0 - 15.0' FILL: Brown clayey silt, trace organic material from 14.9' | | |
| | -16.0 | | | | | 15.0 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-009
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** B. Senna/T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 5.25' bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.5' ASPHALT | 0 | Driller cored through asphalt and concrete |
| | -1.0 | | | | | 0.5 - 1.5' CONCRETE | | |
| | -2.0 | S-1 | NA | 1.5 | | 1.5 - 3.0' FILL: Red brown silty sand (fine), some gravel (fine-coarse), trace coal and glass from 2.5-3' bgs; firm, dry | | 140-SB-009_0002 collected from 1.5-2' bgs @ 8:30<br>140-SB-009_0204 collected from 2.5-3' bgs @ 8:35 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 5.3' FILL: Light brown silt, trace sand (fine); firm, moist | 0 | 140-SB-009_0406 collected from 4.5-5' bgs @ 8:40 |
| | -5.0 | | | | | 5.3 - 8.0' FILL: Light brown sand (fine-medium) with red brown lenses of silt, wet | | 140-SB-009_0608 collected from 7-7.5' bgs @ 8:45 |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Brown sand (fine-medium) and silt; very soft, wet | 0 | 140-SB-009_0810 collected from 8.5-9' bgs @ 8:57 |
| | -9.0 | | | | | 9.0 - 12.0' FILL: Light brown sand (fine-medium), silt at tip; compact, wet | | 140-SB-009_1012 collected from 11-11.5' bgs @ 9:00 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 13.0' FILL: Sand (fine-coarse); very loose, wet | 0 | 140-SB-009_1214 collected from 13-13.5' bgs @ 9:08 |
| | -13.0 | | | | | 13.0 - 15.0' FILL: Sand (fine-coarse); compact, wet | | 140-SB-009_1416 collected from 14.5-15' bgs @ 9:10 |
| | -14.0 | | | | | | | |
| | -15.0 | | | | | | | |
| | -16.0 | | | | | 15.0 - 16.0' CL: Light/dark brown silty clay, organic odor; end of boring at 16' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-010
**DATE BEGAN:** 7/11/08
**DATE FINISHED:** 7/11/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 4.25' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 2.0' FILL: Red brown silt, some angular gravel (fine-medium), bright green mottling (COPR) from 1-1.5' bgs; stiff, dry | | 140-SB-010_0002 collected from 1-1.5' bgs @ 9:35 |
| | -2.0 | | | | | 2.0 - 3.0' FILL: Brown/red brown silt, trace clay; firm, moist | | 140-SB-010_0204 collected from 2.5-3' bgs @ 9:40 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 4.0 | | 4.0 - 4.3' FILL: Brown/red brown silt, trace clay; firm, moist | 0 | 140-SB-010_0406 collected from 4-4.5' bgs @ 9:43; DUP @ 9:44 |
| | -5.0 | | | | | 4.3 - 5.0' FILL: Red/dark brown sandy silt, trace clay; soft, wet | | |
| | -6.0 | | | | | 5.0 - 8.0' FILL: Red/light brown clayey silt, some sand; stiff, wet | | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Red/light brown clayey silt, some sand; loose, wet | 0 | 140-SB-010_0608 collected from 7.5-8' bgs @ 9:45 |
| | -9.0 | | | | | 9.0 - 11.0' FILL: Light/red brown sand (fine-medium); compact, wet | | 140-SB-010_0810 collected from 9-9.5' bgs @ 9:51 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 12.0' FILL: Red/light brown silty sand; compact, wet | | 140-SB-010_1012 collected from 11-11.5' bgs @ 9:53 |
| | -12.0 | S-4 | NA | 4.0 | | 12.0 - 14.0' OL: Light brown organic clayey silt; firm, moist | 0 | 140-SB-010_1214 collected from 12.5-13' bgs @ 10:03 |
| | -13.0 | | | | | | | |
| | -14.0 | | | | | 14.0 - 15.0' OH: Dark brown organic clay; firm, moist | | |
| | -15.0 | | | | | 15.0 - 16.0' PT: Peat; end of boring at 16' | | |
| | -16.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-010R
**DATE BEGAN:** 10/25/10
**DATE FINISHED:** 10/25/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 4.25' bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Red brown silt, some angular gravel (fine-medium), bright green mottling (COPR) from 1-1.5' bgs; stiff, dry | | |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Brown/red brown silt, trace clay; firm, moist | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 4.3' FILL: Brown/red brown silt, trace clay; firm, moist | 0 | |
| | 5.0 | | | | | 4.3 - 5.0' FILL: Red/dark brown sandy silt, trace clay; soft, wet | | |
| | 6.0 | | | | | 5.0 - 8.0' FILL: Red/light brown clayey silt, some sand; stiff, wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Red/light brown clayey silt, some sand; loose, wet | 0 | |
| | 9.0 | | | | | 9.0 - 11.0' FILL: Light/red brown sand (fine-medium); compact, wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' FILL: Red/light brown silty sand; compact, wet | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 14.0' OL: Light brown organic clayey silt; firm, moist | 0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 15.0' OH: Dark brown clayey silt | | 140-SB-010R-1416 collected from 14.5 - 15.0' bgs @ 10:45; DUP at 10:47 |
| | 15.0 | | | | | 15.0 - 16.0' PT: Peat; end of boring at 16' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-011
**DATE BEGAN:** 7/7/08
**DATE FINISHED:** 7/7/08
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 3' bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | |
| | -1.0 | | | | | 1.0 - 2.8' FILL: Black silty sand (fine), some brick, concrete, glass, and coal | | 140-SB-011_0002 collected from 1-1.5' bgs @ 13:10 |
| | -2.0 | | | | | 2.8 - 3.0' FILL: Gravelly sand, some concrete and glass; wet | | 140-SB-011_0204 collected from 2.5-3' bgs @ 13:15 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 4.3' FILL: Gravelly sand, some concrete and glass; wet | 0 | |
| | -5.0 | | | | | 4.3 - 5.8' FILL: Light brown silt, some sand (fine-coarse); wet | | 140-SB-011_0406 collected from 4.5-5' bgs @ 13:20 |
| | -6.0 | | | | | 5.8 - 7.0' FILL: Light brown sand (fine-medium), wet | | 140-SB-011_0608 collected from 6.5-7' bgs @ 13:25 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | S-3 | NA | 3.5 | | 8.0 - 10.0' FILL: Light brown sand (fine-coarse), wet | 0 | 140-SB-011_0810 collected from 8.5-9' bgs @ 13:30: DUP @ 13:35 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 11.0' FILL: Red brown/light brown silt, trace sand (fine) and organic material | | 140-SB-011_1012 collected from 10-10.5' bgs @ 13:40 |
| | -11.0 | | | | | 11.0 - 11.5' PT: Dark brown peat | | |
| | -12.0 | | | | | 11.5 - 12.0' No recovery; end of boring at 12' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-012
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Moustafa Abouelmagd
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' ASPHALT: Asphalt, gravel and concrete | 0 | |
| | -1.0 | | | | | 1.0 - 1.8' FILL: Light grey sand (fine-coarse), silt, and gravel (fine-coarse); dry | | 140-SB-012_0002 collected from 1-1.5' bgs @ 7:27 |
| | -2.0 | | | | | 1.8 - 2.5' FILL: Dark brown/black silt and sand (fine); compact, moist | | 140-SB-012_0204 collected from 2-2.5' bgs @ 7:29 |
| | -3.0 | | | | | 2.5 - 3.0' FILL: Wood, brick and silt; moist | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Dark brown sand (coarse), some brick, wood, and silt; wet | 0 | |
| | -5.0 | | | | | 4.5 - 5.0' FILL: Light brown silt, trace clay; wet | | 140-SB-012_0406 collected from 4.5-5' bgs @ 7:33 |
| | -6.0 | | | | | 5.0 - 6.5' FILL: Light brown/brown clay and silt, wet | | |
| | -7.0 | | | | | 6.5 - 7.5' FILL: Light brown sand (fine-medium), some clay lenses; wet | | 140-SB-012_0608 collected from 7-7.5' bgs @ 7:35 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 9.0' FILL: Light brown sand (fine-medium), some clay lenses; wet | 0 | |
| | -9.0 | | | | | 9.0 - 10.0' FILL: Light brown silty clay, soft, moist | | 140-SB-012_0810 collected from 9-9.5' bgs @ 7:45 |
| | -10.0 | | | | | 10.0 - 11.5' FILL: Dark brown silty clay, some sand (fine) from 10.5-11', moist | | 140-SB-012_1012 collected from 10-10.5' bgs @ 7:48 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | 11.5 - 12.0' PT: Dark brown peat; end of boring at 12' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-013
**DATE BEGAN:** 6/25/08
**DATE FINISHED:** 6/25/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 2.0' FILL: Dark/light brown silt, sand (fine-coarse), and gravel (fine-coarse), concrete from 0.75-1'; dry | 0 | 140-SB-013_0002 collected from 0.5-1' bgs @ 7:27 |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | 2.0 - 2.5' FILL: Dark brown silt, trace fine sand; firm, moist | | |
| | -3.0 | | | | | 2.5 - 3.0' FILL: Dark brown sand (fine-coarse) and gravel, some brick and glass; moist | | 140-SB-013_0204 collected from 2.5-3' bgs @ 7:29 |
| | -4.0 | S-2 | NA | 4.0 | | 3.0 - 4.0' | 0 | |
| | -5.0 | | | | | 4.0 - 5.5' FILL: Light brown sand (fine-coarse) with olive mottling, trace clay and organic material; wet | | 140-SB-013_0406 collected from 4.5-5' bgs @ 7:33 |
| | -6.0 | | | | | 5.5 - 6.0' FILL: Light brown sand (fine-coarse), wet | | |
| | -7.0 | | | | | 6.0 - 8.0' FILL: Light brown sand (fine-medium), trace clay, more clay from 7-7.5'; saturated | | 140-SB-013_0608 collected from 7.5-8' bgs @ 7:35 |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 11.0' FILL: Light brown sand (fine-medium), saturated | 0 | 140-SB-013_0810 collected from 8.5-9' bgs @ 7:45 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | 11.0 - 11.8' FILL: Light/red brown silty clay and trace sand (fine), wet | | 140-SB-013_1012 collected from 11-11.5' bgs @ 7:48 |
| | -12.0 | | | | | 11.8 - 12.0' PT: Dark brown peat; end of boring at 12' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-014
**DATE BEGAN:** 6/25/08
**DATE FINISHED:** 6/25/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 2.0' FILL: Yellow/dark brown silt, sand (fine-coarse), and gravel (fine-coarse); dry | | 140-SB-014_0002 collected from 0.5-1' bgs @ 8:21 |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | 2.0 - 3.0' FILL: Yellow brown sand (medium-coarse), dry | 115 | 140-SB-014_0204 collected from 2.5-3' bgs @ 8:23 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | NA | 3.0 | | 4.0 - 4.3' FILL: Yellow brown sand (medium-coarse), dry | 0 | |
| | -5.0 | | | | | 4.3 - 5.5' FILL: Light/greyish brown silty clay, wet | | 140-SB-014_0406 collected from 4.5-5' bgs @ 8:34 |
| | -6.0 | | | | | 5.5 - 7.0' FILL: Light brown sand (fine-coarse), trace clay; wet | | 140-SB-014_0608 collected from 6-6.5' bgs @ 8:36 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 10.0' FILL: Light brown sand (fine-medium), wet | 0 | 140-SB-014_0810 collected from 8.5-9' bgs @ 8:42 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | 10.0 - 12.0' FILL: Light red brown sand (fine), peat in tip, wet; end of boring at 12' | | 140-SB-014_1012 collected from 10.5-11' bgs @ 8:45 |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-015
**DATE BEGAN:** 6/24/08
**DATE FINISHED:** 6/24/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 12' bgs
**GW DEPTH:** 4.5' bgs
**DRILLER:** E Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' ASPHALT | 0 | Driller cored through asphalt and concrete |
| | -1.0 | | | | | 0.5 - 2.0' CONCRETE | | |
| | -2.0 | | | | | 2.0 - 3.0' FILL: Red brown silt; stiff, dry | | |
| | -3.0 | | | | | 3.0 - 4.0' FILL: Dark brown/black silt; stiff, moist | | 140-SB-015_0204 collected from 3.5-4' bgs @ 12:31 |
| | -4.0 | S-2 | NA | 3.5 | | 4.0 - 4.5' FILL: Red/dark brown silt and gravel (coarse), trace sand, moist | 0 | |
| | -5.0 | | | | | 4.5 - 6.5' FILL: Dark brown/black silt and sand (fine); firm, wet | | 140-SB-015_0406 collected from 5-5.5' bgs @ 12:40 |
| | -6.0 | | | | | 6.5 - 7.0' FILL: Grey/light green silt (COPR), some organic material; dark brown with olive mottling at 6.6', wet | | 140-SB-015_0608 collected from 6.5-7' bgs @ 12:42 |
| | -7.0 | | | | | 7.0 - 7.5' FILL: Dark brown clay, silt and wood, wet | | |
| | -8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No recovery | 0 | |
| | | | | | | 8.0 - 9.0' FILL: Dark brown silty clay, saturated | | |
| | -9.0 | | | | | 9.0 - 10.0' FILL: Dark brown/black sandy clay, wet | | 140-SB-015_0810 collected from 9-9.5' bgs @ 12:45 |
| | -10.0 | | | | | 10.0 - 12.0' PT: Dark brown peat; end of boring at 12' | | Hydrogen sulfide detected with multi-gas meter |
| | -11.0 | | | | | | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-016
**DATE BEGAN:** 6/25/08
**DATE FINISHED:** 6/25/08
**INSPECTOR:** E Jackson/ T Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** E Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.3' FILL: Silt and sand (coarse), dry | 0 | |
| | -1.0 | | | | | 0.3 - 1.0' FILL: Light/red brown sand (fine-coarse), some gravel (fine-medium); dry | | 140-SB-016_0002 collected from 1-1.5' bgs @ 9:27 |
| | -2.0 | | | | | 1.0 - 1.5' FILL: Dark brown sand (fine-coarse), silt and gravel, trace concrete; moist | | |
| | -3.0 | | | | | 1.5 - 2.0' FILL: Red brown sand (fine) and silt, moist | | |
| | -4.0 | S-2 | NA | 4.0 | | 2.0 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 5.0' FILL: Light brown silty sand (coarse), trace clay; wet | | 140-SB-016_0406 collected from 4.5-5' bgs @ 9:35 |
| | -6.0 | | | | | 5.0 - 8.0' FILL: Light/red brown sand (fine-medium), trace clay, clay lenses from 6.5-7'; wet | | |
| | -7.0 | | | | | | | |
| | -8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Light brown sand (fine-medium), trace organic material from 8-9'; wet | 0 | 140-SB-016_0608 collected from 7.5-8' bgs @ 9:38 |
| | -9.0 | | | | | | | 140-SB-016_0810 and DUP collected from 8.5-9' bgs @ 9:45 |
| | -10.0 | | | | | | | |
| | -11.0 | | | | | | | 140-SB-016_1012 collected from 11-11.5' bgs @ 9:47 |
| | -12.0 | S-4 | NA | 2.0 | | 12.0 - 15.0' FILL: Light brown sand (fine-medium), wet | 0 | |
| | -13.0 | | | | | | | |
| | -14.0 | S-5 | NA | 2.0 | | | 0 | 140-SB-016_1214 collected from 13.5-14' bgs @ 9:52 |
| | -15.0 | | | | | | | 140-SB-016_1416 collected from 14-14.5' bgs @ 10:11 |
| | -16.0 | | | | | 15.0 - 16.0' PT: Peat and silt; end of boring at 16' | | |

PREPARED BY: EMJ
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-016A
**DATE BEGAN:** 09/30/2008
**DATE FINISHED:** 09/30/2008
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610 DT
**SAMPLING TOOL:** Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 4.25' bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' FILL: Silt and sand (coarse), dry<br>0.3 - 1.0' FILL: Light/red brown sand (fine-coarse), some gravel (fine-medium); dry<br>1.0 - 1.5' FILL: Dark brown sand (fine-coarse), silt and gravel, trace concrete; moist<br>1.5 - 4.0' FILL: Red brwon sand (fine) and silt; moist | 0 | 140-SB-016A-0002 collected from 1.0 - 1.5' bgs |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: TG

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-017
**DATE BEGAN:** 7/29/08
**DATE FINISHED:** 7/29/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Gordon Blewitt
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.8' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 2.0' FILL: light brown silty sand with fine gravel | 0 | 140-SB-017-0002 from 1.0-1.5' bgs @ 1005 |
| | -2.0 | | | | | 2.0 - 3.0' FILL: light brown silty sand with fine to coarse gravel; moist | 0 | 140-SB-017-0204 from 2.0-2.5' bgs @ 1010 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 3.5 | | 4.0 - 5.5' FILL: light brown silty sand with fine to coarse gravel; moist | 0 | 140-SB-017-0406 from 4.0-4.5' bgs @ 1015 |
| | -5.0 | | | | | 5.5 - 7.5' FILL: dark brown/reddish brown fine sand, trace silt; wet | 0 | |
| | -6.0 | | | | | 7.5 - 8.0' No recovery | 0 | |
| | -7.0 | | | | | 8.0 - 11.5' FILL: dark brown fine to medium sand, trace shells and fine gravel; wet | 0 | 140-SB-017-0608 from 7.0-7.5' bgs @ 1020 |
| | -8.0 | S-3 | N/A | 4.0 | | | 0 | 140-SB-017-0810 from 8.5-9.0' bgs @ 1025 |
| | -9.0 | | | | | | 0 | |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | | 0 | 140-SB-017-1012 from 11.0-11.5' bgs @ 1030 |
| | -12.0 | S-4 | N/A | 3.5 | | 11.5 - 14.5' PT: dark brown peat; moist | 0 | |
| | -13.0 | | | | | | 0 | 140-SB-017-1214 from 12.5-13.0' bgs @ 1035 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | 14.5 - 15.5' SM: dark brown fine sand, some organic material, trace silt; moist | 0 | 140-SB-017-1416 from 15.0-15.5' bgs @ 1040 |
| | -16.0 | S-5 | N/A | 3.0 | | 15.5 - 16.0' No recovery | 0 | |
| | -17.0 | | | | | 16.0 - 16.8' SP: light brown/light grey fine sand; moist | 0 | 140-SB-017-1618 from 16.5-17.0' bgs @ 1045 |
| | -18.0 | | | | | 16.8 - 18.3' SM: light grey silty sand; moist | 0 | |
| | -19.0 | | | | | 18.3 - 19.0' SP: light brown fine sand, trace silt; moist | | 140-SB-017-1820 from 18.5-19.0' bgs @ 1050 |
| | -20.0 | | | | | 19.0 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-018
**DATE BEGAN:** 8/7/08
**DATE FINISHED:** 8/7/08
**INSPECTOR:** B. Senna/W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Dave Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.75 | | 0.0 - 0.5' ASPHALT | 0 | |
| | -1.0 | | | | | 0.5 - 2.0' FILL: brown silty sand, trace fine to coarse gravel | 0 | 140-SB-018-0002 from 1.0-1.5' bgs @ 1510 |
| | -2.0 | | | | | 2.0 - 3.0' FILL: white silt (COPR) | 0 | 140-SB-018-0204 from 2.0-2.5' bgs @ 1515 |
| | -3.0 | | | | | 3.0 - 3.8' FILL: brown silty sand, trace fine to coarse gravel, moist | 0 | |
| | -4.0 | S-2 | N/A | 3.0 | | 3.8 - 4.0' No recovery | 0 | |
| | -5.0 | | | | | 4.0 - 5.5' FILL: dark brown silty sand, trace fine to coarse gravel; wet | 0 | 140-SB-018-0406 from 4.5-5.0' bgs @ 1520 |
| | -6.0 | | | | | 5.5 - 7.0' FILL: light brown silty sand, trace fine to medium gravel and coarse coal; wet | 0 | 140-SB-018-0406 for SVOCs and metals from 5.0-5.5' bgs @ 1523 |
| | -7.0 | | | | | 7.0 - 8.0' No recovery | | 140-SB-018-0608 from 6.5-7.0' bgs @ 1525 |
| | -8.0 | S-3 | N/A | 3.5 | | 8.0 - 11.0' FILL: light brown silty sand, trace fine to coarse gravel and shell fragments; wet | 0 | |
| | -9.0 | | | | | | 0 | 140-SB-018-0810 from 8.5-9.0' bgs @ 1530 |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | 11.0 - 11.5' PT: peat; moist | 0 | 140-SB-018-1012 from 10.5-11.0' bgs @ 1535 |
| | -12.0 | S-4 | N/A | 3.5 | | 11.5 - 12.0' No recovery | 0 | |
| | -13.0 | | | | | 12.0 - 15.5' PT: dark brown peat; moist | 0 | 140-SB-018-1214 from 12.5-13.0' bgs @ 1540 |
| | -14.0 | | | | | | 0 | 140-SB-018-1416 from 14.0-14.5' bgs @ 1545 |
| | -15.0 | | | | | | 0 | |
| | -16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-019
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT: asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.8' FILL: light brown silty sand with fine to coarse gravel, dry | 0 | 140-SB-019-0002 from 1.0-1.5' bgs @ 1220 |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | 1.8 - 2.0' FILL: medium to coarse gravel, dry | | |
| | | | | | | 2.0 - 3.5' FILL: dark brown silt with some fine sand; stiff; dry | 0 | 140-SB-019-0204 from 3.0-3.5' bgs @ 1225 |
| | -3.0 | | | | | | 0 | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 1.5 | | 4.0 - 5.5' FILL: dark brown silty sand with trace fine gravel; wet at tip | 0 | |
| | -5.0 | | | | | | 0 | 140-SB-019-0406 from 5.0-5.5' bgs @ 1230 |
| | | | | | | 5.5 - 6.0' No recovery; end of boring at 6.0' | | |
| | -6.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-020
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.8' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 3.0' FILL: light brown fine sand with fine to coarse gravel, trace coal, dry | 0 | 140-SB-020-0002 from 1.0-1.5' bgs @ 1240 |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | | | 140-SB-020-0204 from 2.5-3.0' bgs @ 1245 |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.0 | | 4.0 - 5.0' FILL: dark brown fine to medium sand; dense, moist | 0 | |
| | -5.0 | | | | | 5.0 - 6.0' FILL: dark brown silt; stiff, wet from 5.5'; end of boring at 6.0' | 0 | 140-SB-020-0406 from 5.0-5.5' bgs @ 1250 |
| | -6.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480059143
**BORING ID:** 140-SB-021
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.8' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 3.0' FILL: light brown fine sand, some fine to coarse gravel and fine to medium wood | 0 | 140-SB-021-0002 from 1.5-2.0' bgs @ 1310 |
| | -2.0 | | | | | | 0 | 140-SB-021-0204 from 2.0-2.5' bgs @ 1315 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.0 | | 4.0 - 4.8' FILL: crushed brick | 0 | |
| | -5.0 | | | | | 4.8 - 6.0' FILL: reddish brown/brown silt, some lenses of black silt; end of boring at 6' | 0 | 140-SB-021-0406 from 5.0-5.5' bgs @ 1320; DUP @ 1325 |
| | -6.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-023
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 1.0' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 1.0 - 1.3' FILL: crushed brick | 0 | |
| | | | | | | 1.3 - 3.0' FILL: dark brown silty sand with glass, brick, and fine to coarse gravel; moist | | 140-SB-023-0002 from 1.5-2.0' bgs @ 0945 |
| | -2.0 | | | | | | 0 | 140-SB-023-0204 from 2.5-3.0' bgs @ 0950; DUP @ 0953 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 1.5 | | 4.0 - 5.5' FILL: dark brown sandy silt, trace fine gravel; wet | 0 | |
| | -5.0 | | | | | | 0 | 140-SB-023-0406 from 5.0-5.5' bgs @ 0955 |
| | -6.0 | | | | | 5.5 - 6.0' No recovery; end of boring at 6' | | |

PREPARED BY: MWV
CHECKED BY: JB

# MACTEC

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-024
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4.75 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 0.8' ASPHALT: asphalt and gravel | 0 | |
| | -1.0 | | | | | 0.8 - 1.5' FILL: light brown fine sand with fine to coarse gravel | 0 | 140-SB-024-0002 from 1.0-1.5' bgs @ 1015 |
| | -2.0 | | | | | 1.5 - 3.0' FILL: reddish brown silt; very stiff; moist | 0 | 140-SB-024-0204 from 2.5-3.0' bgs @ 1020 |
| | -3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 2.0 | | 4.0 - 4.8' FILL: reddish brown silt; very stiff; moist | 0 | |
| | -5.0 | | | | | 4.8 - 6.0' FILL: light brown silty sand; wet; end of boring at 6' | 0 | 140-SB-024-0406 from 5.0-5.5' bgs @ 1025 |
| | -6.0 | | | | | | | |

PREPARED BY: MWV
CHECKED BY: JB

# MACTEC Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-025
**DATE BEGAN:** 7/30/08
**DATE FINISHED:** 7/30/08
**INSPECTOR:** B. Senna/ W. Lang
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 2.5 | | 0.0 - 0.5' FILL: mulch | 0 | |
| | -1.0 | | | | | 0.5 - 2.5' FILL: reddish brown silt with fine sand, some wood at 1.0-1.25'; moist | 0 | |
| | -2.0 | | | | | | 0 | |
| | -3.0 | | | | | 2.5 - 4.0' No recovery | | |
| | -4.0 | S-2 | N/A | 3.5 | | 4.0 - 4.5' FILL: dark brown silty sand, some wood and shells | 0 | |
| | -5.0 | | | | | 4.5 - 5.0' FILL: reddish brown/light brown silt; wet | 0 | |
| | -6.0 | | | | | 5.0 - 7.5' FILL: light brown/reddish brown fine to medium sand; wet | 0 | |
| | -7.0 | | | | | | 0 | |
| | -8.0 | S-3 | N/A | 3.5 | | 7.5 - 8.0' No recovery | | |
| | -9.0 | | | | | 8.0 - 11.5' FILL: light brown fine to medium sand, trace fine gravel; wet | 0 | |
| | -10.0 | | | | | | 0 | |
| | -11.0 | | | | | | 0 | 140-SB-025-1012 from 10.5-11.0' bgs @ 0800 |
| | -12.0 | S-4 | N/A | 3.0 | | 11.5 - 12.0' No recovery | 0 | |
| | -13.0 | | | | | 12.0 - 15.0' PT: dark brown peat | 0 | 140-SB-024-1214 from 12.5-13.0' bgs @ 0815 |
| | -14.0 | | | | | | 0 | |
| | -15.0 | | | | | | 0 | 140-SB-024-1416 from 14.5-15.0' bgs @ 0820 |
| | -16.0 | | | | | 15.0 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: MWV
CHECKED BY: JB

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-026
**DATE BEGAN:** 9/22/08
**DATE FINISHED:** 9/22/08
**INSPECTOR:** F. Petrino
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | N/A | | 0.0 - 5.0' FILL: Dark brown to black fine to coarse sand, some fine to coarse gravel and silt, pieces of stone, brick and concrete, wet @ 4.0' bgs. | | Hand augered to 5.0' bgs |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | | | |
| | -3.0 | | | | | | | |
| | -4.0 | | | | | | | |
| | -5.0 | S-2 | N/A | 3.0 | | 5.0 - 6.3' FILL: Dark brown to black fine to coarse sand, some fine to coarse gravel and silt, pieces of stone, brick and concrete, wet. | | |
| | -6.0 | | | | | 6.3 - 6.8' FILL: Reddish brown silt and fine sand, trace clay, wet, firm | | |
| | -7.0 | | | | | 6.8 - 8.0' FILL: Dark reddish brown to dark brown fine to coarse sand, some fine to medium gravel, trace silt, wet, loose | | |
| | -8.0 | S-3 | N/A | 4.0 | | 8.0 - 10.5' FILL: Reddish brown fine to coarse sand and silt, some fine to medium gravel, loose, wet | | 140-SB-026-0810 from 8.0-8.5' bgs @ 14:55 |
| | -9.0 | | | | | | | |
| | -10.0 | | | | | | | 140-SB-026-1012 from 10.0-10.5' bgs @ 14:58 |
| | -11.0 | | | | | 10.5 - 12.0' PEAT: Peat, mostly organic fibers, some silt and clay, anaerobic odors | | |
| | -12.0 | | | | | | | |

PREPARED BY: EMJ
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-027
**DATE BEGAN:** 10/27/08
**DATE FINISHED:** 10/27/08
**INSPECTOR:** B. Senna
**DRILLING CO:** B & B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT: Asaphalt & gravel | 0 | |
| | | | | | | 0.5 - 2.0' FILL: Brown silty sand (fine) some glass, gravel, and coal; moist | | |
| | -1.0 | | | | | | | |
| | -2.0 | | | | | 2.0 - 3.5' FILL: light brown sand (fine-medium) some gravel (fine), wet @ 2.5' | | |
| | -3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' | | |
| | -4.0 | S-2 | N/A | 3.5 | | 4.0 - 5.0' FILL: Light brown sand (fine-coarse) with gravel (fine) and lenses of light brown silt throughout, saturated | 0 | |
| | -5.0 | | | | | 5.0 - 7.5' FILL: Light brown/light gray sand (fine-coarse), saturated | | |
| | -6.0 | | | | | | | |
| | -7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | -8.0 | S-3 | N/A | 1.5 | | 8.0 - 9.0' FILL: Light grey sand (fine-coarse), saturated | 0 | 140-SB-027-0810 from 8.5-9.0' bgs @ 11:45 |
| | -9.0 | | | | | 9.0 - 9.1' FILL: Light brown silt with some organics, saturated | | |
| | | | | | | 9.1 - 9.5' PEAT: Dark brown peat, moist | | |
| | -10.0 | | | | | 9.5 - 10.0' No recovery; End of boring @ 10' | | |

PREPARED BY: EMJ
CHECKED BY: EMJ

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-028
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.8 | | 0.0 - 0.8' ASPHALT | 0.0 | Field Map #169 |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Reddish brown silty fine sand; trace f-m gravel, brick, and coal; dense | 0.0 | 140-SB-028-0002 collected from 1.5-2.0' bgs @ 9:45 |
| | 3.0 | | | | | 2.5 - 2.7' FILL: Yellow f-m sand (COPR) and concrete | | 140-SB-028-0204 collected from 2.5-3.0' bgs @ 9:50 |
| | 4.0 | R-2 | N/A | 4.0 | | 2.7 - 3.8' FILL: Dark brown/black silt, some fine sand; stiff | | |
| | 5.0 | | | | | 3.8 - 4.0' No recovery | 0.0 | |
| | 6.0 | | | | | 4.0 - 6.5' FILL: Dark brown/black silt, some fine sand; stiff, wet | 0.0 | 140-SB-028-0406 collected from 4.5-5.0' bgs @ 9:55<br>140-SB-028-0608 collected from 6.0-6.5' bgs @ 10:00 |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Wood | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 10.5' FILL: Reddish brown/brown/dark brown sandy silt, trace clay; soft, wet | 0.0 | 140-SB-028-0810 collected from 8.5-9.0' bgs @ 10:05 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | 0.0 | |
| | 11.0 | | | | | 10.5 - 11.5' OH: Very dark grayish brown (7.5YR 3/2) clayey silt, some organic material; soft, wet | | 140-SB-028-1012 collected from 11.0-11.5' bgs @ 10:10 |
| | 12.0 | | | | | 11.5 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 12.0' bgs | | |

PREPARED BY: JB
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-029
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.8 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #165<br>Boring near hydrant, may account for higher water table |
| | 1.0 | | | | | 0.5 - 1.2' FILL: Brown f-m sand | | |
| | 2.0 | | | | | 1.2 - 2.8' FILL: Dark brown silty sand, some f-m gravel, trace brick and concrete; wet from 1.5' | | 140-SB-029-0002 collected from 1.5-2.0' bgs @ 10:30<br>140-SB-029-0204 collected from 2.0-2.5' bgs @ 10:35 |
| | 3.0 | | | | | 2.8 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 4.2' FILL: Dark brown silty sand, some f-m gravel, trace brick and concrete; wet | 0.0 | |
| | 5.0 | | | | | 4.2 - 5.0' FILL: Wood, some black/ dark green sandy clay from 4.8-5.0'; wet | | 140-SB-029-0406 collected from 4.5-5.0' bgs @ 10:40 |
| | 6.0 | | | | | 5.0 - 6.2' FILL: Brown sandy silt, trace clay; wet; stiff | | |
| | 7.0 | | | | | 6.2 - 7.5' FILL: Brown/dark brown f-m sand; wet | | 140-SB-029-0608 collected from 7.0-7.5' bgs @ 10:45 |
| | 8.0 | | | | | 7.5 - 8.0' No recovery | | |
| | 9.0 | R-3 | N/A | 4.0 | | 8.0 - 10.0' FILL: Brown/dark brown f-m sand; wet | 0.0 | |
| | 10.0 | | | | | 10.0 - 12.0' PT: Dark olive brown (2.5Y 3/3) peat; end of boring at 12.0' bgs | | 140-SB-029-0810 collected from 9.5-10.0' bgs @ 10:50<br>140-SB-029-1012 collected from 10.5-11.0' bgs @ 10:55 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-030
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 1.5' ASPHALT | 0.0 | Field Map #171 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Gray to light brown f-c sand, some fine gravel | 0.0 | 140-SB-030-0002 collected from 1.5-2.0' bgs @ 11:35 |
| | 3.0 | | | | | 3.0 - 4.0' FILL: No recovery | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 5.3' Gray f-m gravel, some f-c brown sand; wet | 0.0 | |
| | 5.0 | | | | | 5.3 - 5.6' FILL: Brown f-m sand | | |
| | 6.0 | | | | | 5.6 - 6.5' FILL: Reddish brown sandy silt; stiff; wet | 0.0 | 140-SB-030-0608 collected from 6.0-6.5' bgs @ 11:50 |
| | 7.0 | | | | | 6.5 - 8.0' FILL: No recovery | | |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 10.0' FILL: Brown sand, layer of reddish brown silt from 8.8-9.0'; wet; stiff; compact | 0.0 | 140-SB-030-0810 collected from 8.0-8.5' bgs @ 11:55 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Brown silty sand; wet; compact | 0.0 | |
| | 11.0 | | | | | 11.0 - 11.5' PT: Dark olive brown (2.5YR 3/3) peat | | 140-SB-030-1012 collected from 10.5-11.0' bgs @ 12:00 |
| | 12.0 | | | | | 11.5 - 12.0' End of boring @ 12' bgs | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-031
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 1.5' ASPHALT | 0.0 | Field Map #163 |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Brown f-m sand & gravel | | 140-SB-031-0002 collected from 1.5-2.0' bgs @ 12:45 |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Dark brown silty sand, some f-m gravel, trace clinker & brick, wood from 3.0-3.2' | 0.0 | |
| | 3.0 | | | | | | | 140-SB-031-0204 collected from 3.0-3.5' bgs @ 12:50 |
| | 4.0 | R-2 | N/A | 2.5 | | 3.5 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 4.3' FILL: f-m gravel; wet | 0.0 | 140-SB-031-0406 collected from 4.5-5.0' bgs @ 12:55 |
| | 6.0 | | | | | 4.3 - 7.0' FILL: Brown f-m sand, reddish brown varved silt from 5.5-5.7'; wet | 0.0 | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | 140-SB-031-0608 collected from 6.5-7.0' bgs @ 13:00 |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 11.0' FILL: Brown f-m sand with reddish brown silt from 8.2-8.4'; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | 0.0 | 140-SB-031-0810 collected from 9.5-10.0' bgs @ 13:08 |
| | 11.0 | | | | | 11.0 - 11.5' PT: Dark olive brown (2.5YR 3/3) peat | | |
| | 12.0 | | | | | 11.5 - 12.0' End of boring @ 12' bgs | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-032
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #161 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown/dark brown/yellow brown f-m sand, some f-m gravel | | 140-SB-032-0002 collected from 1.0-1.5' bgs @ 13:20 |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Concrete | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Dark Brown f-m sand, trace gravel, coal, & clinker, concrete from 2.4-2.8' | | 140-SB-032-0204 collected from 2.0-2.5' bgs @ 13:25 |
| | | | | | | 3.0 - 3.5' FILL: Black/gray f-c sand and gravel, some concrete; spots of stam and odors; wet | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 4.5' FILL: Black/gray f-c sand and gravel, some concrete, white sandy COPR from 4.3'; spots of stam and odors; wet | 0.0 | 140-SB-032-0406 collected from 4.0-4.5' bgs @ 13:30 |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Reddish brown silty sand; wet; dense | | |
| | 6.0 | | | | | 5.0 - 7.5' FILL: Brown f-m sand, few nodules of reddish brown silt; wet | | |
| | 7.0 | | | | | | | 140-SB-032-0608 collected from 7.0-7.5' bgs @ 13:35 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 10.0' FILL: Brown f-m sand, few nodules of reddish brown silt; wet; end of boring @ 10' bgs | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 140-SB-032-0810 collected from 9.5-10.0' bgs @ 13:40 |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-033
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 1.0' ASPHALT | 0.0 | Field Map #160 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Brown f-m sand & gravel | | 140-SB-033-0002 collected from 1.5-2.0' bgs @ 13:55 |
| | 2.0 | | | | | 2.0 - 2.3' FILL: Concrete | | |
| | 3.0 | | | | | 2.3 - 3.0' FILL: Dark Brown f-c sand, come f-m gravel & clinker, trace glass; wet from 2.5' bgs | | 140-SB-033-0204 collected from 2.5-3.0' bgs @ 14:00 |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 2.5 | | 4.0 - 4.5' Dark Brown f-c sand, come f-m gravel & clinker, trace glass; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 6.3' FILL: Brown f-m sand | | 140-SB-033-0406 collected from 5.0-5.5' bgs @ 14:05 |
| | 6.0 | | | | | 6.3 - 6.5' FILL: Dark brown silty sand and fibrous organic material | | 140-SB-033-0608 collected from 6.0-6.5' bgs @ 14:10 |
| | | | | | | 6.5 - 8.0' FILL: No recovery | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 10.0' Brown f-m sand, trace shells; wet; end of boring @ 10' bgs | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 140-SB-033-0810 collected from 9.5-10.0' bgs @ 14:15 |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-034
**DATE BEGAN:** 07/16/09
**DATE FINISHED:** 07/16/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT | 0.0 | Field Map #159 |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Brown f-m sand & gravel | | |
| | | | | | | 1.5 - 1.6' FILL: Reddish brown fine sand | | 140-SB-034-0002 collected from 1.5-2.0' bgs @ 14:50 |
| | 2.0 | | | | | 1.6 - 2.0' FILL: Dark brown f-m sand, some fine gravel & clinker | 0.0 | 140-SB-034-0204 collected from 2.0-2.5' bgs @ 14:55 |
| | | | | | | 2.0 - 2.8' FILL: White/gray silty COPR, trace organic materials & glass; course & stiff | | |
| | 3.0 | | | | | 2.8 - 3.8' FILL: Reddish brown silty sand; wet from 3.5' | | |
| | | | | | | 3.8 - 4.0' FILL: Brown f-m sand; wet | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 6.0' FILL: Brown f-m sand; wet | 0.0 | 140-SB-034-0406 collected from 4.0-4.5' bgs @ 15:00 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 6.8' FILL: Reddish brown silty sand, trace clay; wet | 0.0 | |
| | | | | | | 6.8 - 7.0' FILL: Dark brown silt, some organic material; wet | | |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Brown f-m sand; wet | | 140-SB-034-0608 collected from 7.0-7.5' bgs @ 15:05 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.0 | | 8.0 - 10.0' FILL: Brown f-m sand, trace shells; wet; end of boring @ 10.0' bgs | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 140-SB-034-0810 collected from 9.5-10.0' bgs @ 15:10 |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-035
**DATE BEGAN:** 07/17/09
**DATE FINISHED:** 07/17/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT: Gravel, f-m sand | 0.0 | Field Map #125 |
| | 1.0 | | | | | 1.0 - 4.0' FILL: Very dark grayish brown silty sand; wet from 2.5'; compact | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | R-2 | N/A | 4.0 | | 4.0 - 5.0' FILL: Very dark grayish brown silty sand, fine gravel from 4.5-4.6', wood from 4.9'; wet; compact | 0.0 | |
| | 5.0 | | | | | 5.0 - 5.3' FILL: Dark brown f-m sand, trace silt, white silt and sand (COPR) from 5.2'; wet | | |
| | 6.0 | | | | | 5.3 - 7.5' FILL: Reddish brown silty sand; wet; dense | | |
| | 7.0 | | | | | 7.5 - 7.7' FILL: Dark brown silty clay; wet; soft | | |
| | 8.0 | R-3 | N/A | 3.0 | | 7.7 - 8.0' FILL: Brown f-m sand; wet | 0.0 | |
| | 9.0 | | | | | 8.0 - 11.0' FILL: Brown f-m sand, some silt lenses from 10.0'; wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | R-5 | N/A | 4.0 | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-035
**DATE BEGAN:** 07/17/09
**DATE FINISHED:** 07/17/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | R-5 | N/A | 4.0 | | 12.0 - 13.0' FILL: Brown silt clay; wet; very soft | 0.0 | |
| | 13.0 | | | | | 13.0 - 14.0' FILL: Brown silt, white silt (COPR) from 13.5'; wet; stiff and blocky | | 140-SB-035-1214 collected from 13.5-14.0' bgs @ 8:50 |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Dark brown silt, trace sand, dark gray/light brown (COPR?) f-m sand from 14.4'; wet; soft | | 140-SB-035-1416 collected from 14.0-14.5' bgs @ 8:55 |
| | 15.0 | | | | | 14.5 - 15.7' FILL: Brown silt; wet; very stiff | | |
| | | | | | | 15.7 - 16.0' FILL: Dark brown clayey silt; trace fine sand; wet | | |
| | 16.0 | R-5 | N/A | 2.0 | | 16.0 - 16.5' OH: Black (2.5Y 2.5/1) clayey silt; wet; soft | 0.0 | 140-SB-035-1618 collected from 16.0-16.5' bgs @ 9:00 |
| | 17.0 | | | | | 16.5 - 17.7' PT: Very dark brown (7.5YR 2.5/2) peat | | |
| | 18.0 | | | | | 17.7 - 18.0' SP: Dark gray (7.5YR 4/1) fine sand; wet; end of boring @ 18' bgs | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-036
**DATE BEGAN:** 07/17/09
**DATE FINISHED:** 07/17/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.0 | | 0.0 - 1.0' ASPHALT: Gravel, f-m sand | 0.0 | Field Map #127 |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Very darkgrayish brown silty trace fine sand; stiff | | |
| | 2.0 | R-2 | | 1.5 | | 1.8 - 2.0' FILL: Concrete | | |
| | 3.0 | | | | | 2.0 - 2.3' FILL: Very dark grayish brown silt, trace fine sand; stiff | | |
| | 4.0 | R-3 | N/A | 3.0 | | 2.3 - 2.5' FILL: Wood | 0.0 | |
| | 5.0 | | | | | 2.5 - 3.0' FILL: Black f-c sand and fine clinker, trace fine gravel; wet | | |
| | 6.0 | | | | | 3.0 - 3.5' FILL: Reddish brown f-m sand, trace fine gravel; wet | | |
| | 7.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 8.0 | R-4 | N/A | 2.5 | | 4.0 - 4.5' FILL: Reddish brown f-m sand, trace fine gravel; wet | 0.0 | |
| | 9.0 | | | | | 4.5 - 5.8' FILL: Brown, silty clay; wet; firm | | |
| | 10.0 | | | | | 5.8 - 7.0' FILL: Brown f-m sand; wet | | |
| | 11.0 | | | | | 7.0 - 8.0' FILL: No recovery | | |
| | 12.0 | R-5 | N/A | 4.0 | | 8.0 - 10.5' FILL: Brown f-m sand; wet | 0.0 | |
| | 13.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 14.0 | | | | | 12.0 - 12.3' FILL: Brown f-m sand; wet | | |
| | 15.0 | | | | | 12.3 - 15.0' FILL: Brown/ dark brown silty clay, trace fine sand; wet; soft | | |
| | 16.0 | | | | | 15.0 - 15.7' OH: Black (2.5Y 2.5/1) clayey silt; wet | | 140-SB-036-1416 collected from 15.0-15.5' bgs @ 10:20 |
| | | | | | | 15.7 - 16.0' PT: Very dark brown (7.5YR 2.5/2) peat; wet; end of boring @ 16' bgs | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-037
**DATE BEGAN:** 07/17/09
**DATE FINISHED:** 07/17/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.5' ASPHALT: Fine gravel and sand | 0.0 | Field Map #122 |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Dark brown fine sand, trace fine gravel | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Very dark grayish brown silt & fine sand | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Black f-c sand, fine clinker; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 4.0' FILL: Reddish brown silty sand, trace fine gravel; wet; dense | 0.0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Dark brown f-c sand, some f-m gravel & clinker; wet | | |
| | 6.0 | | | | | 5.0 - 5.7' FILL: Reddish brown silty sand; wet | | |
| | 7.0 | | | | | 5.7 - 6.5' FILL: Brown silty clay; wet; soft | | |
| | 8.0 | R-3 | N/A | 2.0 | | 6.5 - 8.0' FILL: Brown f-m sand, some silt lenses; wet | 0.0 | |
| | 9.0 | | | | | 8.0 - 10.0' FILL: Brown f-m sand, some silt lenses; wet | | |
| | 10.0 | | | | | 10.0 - 12.0' No recovery | | |
| | 11.0 | | | | | 12.0 - 12.2' FILL: Brown f-m sand, some silt lenses; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.2 - 14.7' FILL: Brown silty clay; wet; very soft | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | 140-SB-037-1214 collected from 13.5-14.0' bgs @ 11:00; HOLD |
| | 15.0 | | | | | 14.7 - 16.0' OH: Dark gray (2.5Y 4/1) to black (2.5Y 2.5/1) clayey silt; wet; end of boring @ 16.0' bgs | | 140-SB-037-1416 collected from 15.5-16.0' bgs @ 11:05 |
| | 16.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-038
**DATE BEGAN:** 07/17/09
**DATE FINISHED:** 07/17/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 3.7 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 1.0' ASPHALT | 0.0 | Field Map #129 |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Brown f-m sand & gravel | | |
| | 2.0 | | | | | 1.8 - 3.7' FILL: Very dark grayish brown silt & fine sand | | |
| | 3.0 | | | | | 3.7 - 4.0' FILL: Black f-c sand, f-m clinker, trace fine gravel & brick; wet | | |
| | 4.0 | R-2 | N/A | 3.0 | | 4.0 - 4.5' FILL: Black f-c sand, f-m clinker, trace fine gravel & brick; wet | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.0' FILL: Dark brown silty sand; wet | | |
| | 6.0 | | | | | 5.0 - 7.0' FILL: Dark brown f-m sand, silt from 5.8-6.2'; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.5 | | 8.0 - 10.0' FILL: Brown/ dark brown f-m sand; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 10.5' FILL: Dark brown silty clay, trace fine sand; wet | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 15.5' FILL: Brown/ dark brown silty clay; wet; mostly soft, but wil zones of very stiff, verved silt | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.5 - 16.0' OH: Black (2.5Y 2.5/1) clayey silt; trace organic material | | 140-SB-038-1416 collected from 15.5-16.0' bgs @ 11:55; HOLD |
| | 16.0 | R-5 | N/A | 2.0 | | 16.0 - 18.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring @ 18' bgs | 0.0 | 140-SB-038-1618 collected from 16.0-16.5' bgs @ 12:00 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: MC
CHECKED BY: BS

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-039
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.7 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #143 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Brown/dark brown f-c sand, some f-m gravel, trace silt | | |
| | 2.0 | | | | | 1.5 - 2.7' FILL: Very dark grayish brown sandy silt; stiff | | |
| | 3.0 | | | | | 2.7 - 4.0' No recovery | | |
| | 4.0 | R-2 | N/A | 3.5 | | 4.0 - 4.5' FILL: Brown f-m sand, some fine clinker and gravel | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.7' FILL: Reddish brown silty sand; dense, wet | | |
| | 6.0 | | | | | 5.7 - 7.5' FILL: Reddish brown f-c sand, some silt lenses; loose, wet | | |
| | 7.0 | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.7 | | 8.0 - 10.5' FILL: Reddish brown f-c sand, some silt lenses; loose, wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 10.7' FILL: Reddish brown fine sand; loose, wet | | |
| | 11.0 | | | | | 10.7 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 14.0' FILL: Brown clayey silt; soft, wet | 0.0 | |
| | 13.0 | | | | | 14.0 - 14.1' FILL: Dark brown/black f-m sand; wet | | 140-SB-039-1214 collected from 13.5-14.0' bgs @ 14:35; HOLD |
| | 14.0 | | | | | 14.1 - 14.8' FILL: Reddish brown/brown clayey silt; very stiff; wet | | |
| | 15.0 | | | | | 14.8 - 16.0' FILL: Brown silty clay; soft, wet; end of boring at 16.0' | | 140-SB-039-1416 collected from 15.5-16.0' bgs @ 14:40 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-040
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #131 |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Dark brown f-c sand, some gravel; yellowish brown COPR from 1.2' | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Gravel, some fine brown sand | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Very dark grayish brown silt, trace fine sand; very stiff | | |
| | 4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | R-2 | N/A | 4.0 | | 4.0 - 4.5' FILL: Very dark grayish brown silt, trace fine sand; very stiff | 0.0 | |
| | 5.0 | | | | | 4.5 - 5.3' FILL: Black fine clinker, some f-m sand and gravel, trace coal; wet | | |
| | 6.0 | | | | | 5.3 - 6.0' FILL: Brown silty sand; trace gravel, brick, wood and yellow/brown COPR | | |
| | 7.0 | | | | | 6.0 - 7.5' FILL: Brown/dark brown silty clay; some sand from 6.0-6.5'; trace white silty COPR from 6.0-6.2'; soft, wet | | |
| | 8.0 | R-3 | N/A | 2.5 | | 7.5 - 8.0' FILL: Dark brown f-m sand, some silt lenses; wet | 0.0 | |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Brown f-m sand, few stiff silt lenses; wet | | |
| | 10.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 16.0' FILL: Brown/dark brown clayey silt, some green/yellow mottling from 15.6'; very soft from 12.0-13.5; stiff and blocky with some soft layers from 13.5' | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-040
**DATE BEGAN:** 07/30/09
**DATE FINISHED:** 07/30/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | R-5 | N/A | 3.0 | | 16.0 - 16.5' OH: Black/dark olive brown (2.5Y 2.5/1 to 3/3) clayey silt; soft, wet | 0.0 | 140-SB-040-1618 collected from 16.0-16.5' bgs @ 15:40 |
| | 17.0 | | | | | 16.5 - 18.0' PT: Very dark brown (7.5YR 2.5/2) peat; firm, moist | | |
| | 18.0 | | | | | 18.0 - 19.0' SP: Dark gray (2.5Y 4/1) f-m sand; loose, wet | | |
| | 19.0 | | | | | 19.0 - 20.0' No recovery; end of boring @ 20' | | |
| | 20.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-041
**DATE BEGAN:** 07/31/09
**DATE FINISHED:** 07/31/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | N/A | Field Map #133 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown silty sand, some f-m gravel, trace coal and brick | | No PID due to rain |
| | 2.0 | | | | | 1.0 - 1.6' FILL: Dark gray sandy silt; stiff | | |
| | 3.0 | | | | | 1.6 - 3.0' FILL: Dark brown/reddish brown f-c sand, some fine clinker and gravel, trace silt and brick; wet from 2.0' | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 4.0' No recovery | N/A | |
| | 5.0 | | | | | 4.0 - 6.5' FILL: Dark brown/reddish brown f-c sand, some fine clinker and gravel, trace silt and brick; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 10.5' FILL: Brown f-m sand; dark brown from 10.3'; wet | | |
| | 8.0 | R-3 | N/A | 4.0 | | | N/A | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.6' FILL: Brown fine sand, trace silt; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | 11.6 - 12.0' FILL: Brown silty clay, trace fine sand; very soft, wet | N/A | 140-SB-041-1214 collected from 12.0-12.5' bgs @ 8:30 |
| | 13.0 | | | | | 12.0 - 15.5' FILL: Brown/dark brown clayey silt, few sand lenses; thin lens of white COPR @ 15.5'; soft, wet | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.5 - 16.0' PT: Very dark brown (10YR 2/2) peat; end of boring at 16' | | 140-SB-041-1416 collected from 15.5-16.0' bgs @ 8:35 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-042
**DATE BEGAN:** 07/31/09
**DATE FINISHED:** 07/31/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | N/A | Field Map #145<br>No PID due to rain |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-c sand, trace fine gravel | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Dark brown silty sand, trace brick and fine gravel | | |
| | 3.0 | | | | | 2.0 - 2.7' FILL: Dark brown f-c sand and fine clinker, some fine gravel; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 2.7 - 3.6' FILL: Reddish brown silty sand; compact, wet | N/A | 140-SB-042-0406 collected from 4.0-4.5' bgs @ 9:10 |
| | 5.0 | | | | | 3.6 - 8.0' FILL: Brown f-c sand; few silt nodules from 4.0'; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 140-SB-042-0608 collected from 7.5-8.0' bgs @ 9:15; DUP @ 9:17 |
| | 8.0 | R-3 | N/A | 3.5 | | 8.0 - 10.5' FILL: Brown f-m sand; wet | N/A | 140-SB-042-0810 collected from 8.0-8.5' bgs @ 9:20 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' FILL: Brown silty clay; wet | | 140-SB-042-1012 collected from 11.0-11.5' bgs @ 9:25 |
| | 12.0 | R-4 | N/A | 4.0 | | 11.5 - 12.0' No recovery<br>12.0 - 12.5' FILL: Brown silty clay; wet | N/A | 140-SB-042-1214 collected from 13.5-14.0' bgs @ 9:40 |
| | 13.0 | | | | | 12.5 - 13.0' FILL: Brown silt, trace clay; very stiff, dry | | |
| | 14.0 | | | | | 13.0 - 15.0' FILL: Brown/dark brown silty clay; very soft, wet | | |
| | 15.0 | | | | | 15.0 - 15.5' OL: Dark olive brown/black (2.5Y 3/3 to 2.5/1) clayey silt, trace organic material; stiff | | 140-SB-042-1416 collected from 15.0-15.5' bgs @ 9:45 |
| | 16.0 | | | | | 15.5 - 16.0' PT: Very dark brown (10YR 2/2) peat; end of boring at 16' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-043
**DATE BEGAN:** 07/31/09
**DATE FINISHED:** 07/31/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 15 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.7 | | 0.0 - 0.5' ASPHALT | N/A | Field Map #138<br>No PID due to rain |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Brown f-c sand, some fine clinker and gravel, trace coal and brick | | |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Brown silty sand, concrete from 2.2-2.3'; wet | | |
| | 3.0 | | | | | 3.5 - 3.7' FILL: Brown f-m sand, trace silt; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.7 - 4.0' No recovery | N/A | 140-SB-043-0406 collected from 4.0-4.5' bgs @ 10:15 |
| | 5.0 | | | | | 4.0 - 10.5' FILL: Brown f-m sand, few silt lenses, trace fine gravel; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 140-SB-043-0608 collected from 7.5-8.0' bgs @ 10:20 |
| | 8.0 | R-3 | N/A | 2.5 | | | N/A | 140-SB-043-0810 collected from 8.0-8.5' bgs @ 10:25 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 140-SB-043-1012 collected from 10.0-10.5' bgs @ 10:30 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 3.0 | | 12.0 - 12.3' FILL: Brown f-m sand, few stiff silt lenses; wet | N/A | |
| | 13.0 | | | | | 12.3 - 13.0' FILL: Brown/dark brown silty clay, trace f-m sand; wet | | |
| | 14.0 | | | | | 13.0 - 14.0' OL: Dark olive brown/black (2.5Y 3/3 to 2.5/1) clayey silt, trace fine sand | | 140-SB-043-1214 collected from 13.5-14.0' bgs @ 10:45 |
| | 15.0 | | | | | 14.0 - 15.0' PT: Very dark brown (10YR 2/2) peat; end of boring at 15' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-044
**DATE BEGAN:** 07/31/09
**DATE FINISHED:** 07/31/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.0 | | 0.0 - 0.5' ASPHALT | N/A | Field Map #136 |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Dark brown silty sand, some f-m gravel, trace clinker and brick | | No PID due to rain |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark brown f-c sand, some f-m gravel and clinker; wet | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Reddish brown clayey sand; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 4.0' No recovery | N/A | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Dark brown fine gravel, trace f-c sand and silt; wet | | |
| | 6.0 | | | | | 4.5 - 6.0' FILL: Brown f-m sand, trace fine gravel; wet | | 140-SB-044-0406 collected from 5.5-6.0' bgs @ 11:20 |
| | 7.0 | | | | | 6.0 - 6.5' FILL: Reddish brown clayey silt; stiff | | |
| | 8.0 | R-3 | N/A | 3.0 | | 6.5 - 10.7' FILL: Brown f-c sand, few silt nodules; wet | N/A | 140-SB-044-0608 collected from 7.5-8.0' bgs @ 11:25 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 140-SB-044-0810 collected from 9.5-10.0' bgs @ 11:30 |
| | 11.0 | | | | | 10.7 - 11.0' FILL: Brown sandy clay; very soft, wet | | 140-SB-044-1012 collected from 10.5-11.0' bgs @ 11:35 |
| | 12.0 | R-4 | N/A | 2.0 | | 11.0 - 12.0' No recovery | N/A | |
| | 13.0 | | | | | 12.0 - 12.3' FILL: Brown sandy clay; very soft, wet | | |
| | 14.0 | | | | | 12.3 - 13.0' FILL: Brown silty clay; very soft, wet | | 140-SB-044-1214 collected from 13.5-14.0' bgs @ 11:40 |
| | | | | | | 13.0 - 14.0' FILL: Brown/dark brown clayey silt, very stiff; end of boring at 14' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South


**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-045
**DATE BEGAN:** 08/07/09
**DATE FINISHED:** 08/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.7 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #153 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Yellowish brown f-c sand, some f-m gravel; wet from 2.0' | | |
| | 3.0 | | | | | 2.5 - 2.7' FILL: Dark brown f-m sand, some fine clinker and coal; wet | | |
| | 4.0 | | | | | 2.7 - 2.9' FILL: Gravel, f-c; wet | | |
| | | R-2 | N/A | 3.5 | | 2.9 - 3.7' FILL: Reddish brown silt, trace coal and fine sand, some gray clinker; wet | 0.0 | |
| | 5.0 | | | | | 3.7 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 5.2' FILL: Yellowish brown silt, trace coal and fine sand; wet | | 140-SB-045-0406 collected from 5.5-6.0' bgs @ 10:05 |
| | 7.0 | | | | | 5.2 - 6.5' FILL: Brown silty sand; wet | | 140-SB-045-0608 collected from 7.0-7.5' bgs @ 10:10 |
| | 8.0 | | | | | 6.5 - 7.0' FILL: Brown/dark brown silty clay | | |
| | | R-3 | N/A | 2.0 | | 7.0 - 7.5' FILL: Dark brown f-m sand; wet | 0.0 | |
| | 9.0 | | | | | 7.5 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 10.0' FILL: Brown f-m sand, trace silt; wet | | 140-SB-045-0810 collected from 9.5-10.0' bgs @ 10:15 |
| | 11.0 | | | | | 10.0 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 16.0' FILL: Brown/dark brown clayey silt, few sand lenses; end of boring at 16' | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | 140-SB-045-1214 collected from 13.5-14.0' bgs @ 10:25 |
| | 15.0 | | | | | | | 140-SB-045-1416 collected from 15.5-16.0' bgs @ 10:30 |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-046
**DATE BEGAN:** 08/07/09
**DATE FINISHED:** 08/07/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**




PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-047
**DATE BEGAN:** 08/10/09
**DATE FINISHED:** 08/10/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.2 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #151 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m gravel | | |
| | 2.0 | | | | | 1.0 - 2.2' FILL: Dark brown silty sand, some f-m gravel and concrete, trace clinker; wet from 2.0' bgs | | |
| | 3.0 | | | | | 2.2 - 3.2' FILL: Reddish brown silt, few sand lenses, trace clay; stiff, moist | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.2 - 4.0' No recovery | 0.0 | |
| | 5.0 | | | | | 4.0 - 10.8' FILL: Brown f-m sand, few silt lenses, trace f-m gravel; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.8 - 12.5' FILL: Brown silty sand, trace clay; wet | | |
| | 12.0 | R-4 | N/A | 4.0 | | | 0.0 | Possible COPR in 12-14' interval; no delineation sample collected |
| | 13.0 | | | | | 12.5 - 14.5' FILL: Brown/dark brown clayey silt; thin, white lens of possible COPR at 14.3'; wet | | |
| | 14.0 | | | | | 14.5 - 15.0' OH: Dark olive brown/black (2.5Y 3/3 to 2.5/1) clayey silt; wet | | 140-SB-047-1416 collected from 14.5-15.0' bgs @ 8:55 |
| | 15.0 | | | | | 15.0 - 16.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 16' | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-048
**DATE BEGAN:** 08/10/09
**DATE FINISHED:** 08/10/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #149 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Brown f-m sand and gravel | | |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Reddish brown/brown f-m sand; trace silt, f-m gravel, brick and coal; wet from 2.0' | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Dark brown fine clinker and f-c sand; loose, wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 3.0 - 3.5' FILL: Reddish brown fine sand, trace silt; dense, wet | 0.0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | 140-SB-048-0406 collected from 4.5-5.0' bgs @ 9:15 |
| | 6.0 | | | | | 4.0 - 8.0' FILL: Brown f-m sand, trace silt and fine gravel; wet | | |
| | 7.0 | | | | | | | 140-SB-048-0608 collected from 7.5-8.0' bgs @ 9:20; DUP @ 9:22 |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.3' FILL: Brown/dark brown f-m sand; compact, wet | 0.0 | |
| | 9.0 | | | | | | | 140-SB-048-0810 collected from 8.0-8.5' bgs @ 9:25 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.3 - 12.0' FILL: Brown silt, trace fine sand; very soft, wet | | 140-SB-048-1012 collected from 10.5-11.0' bgs @ 9:30 |
| | 12.0 | R-4 | N/A | 4.0 | | 12.0 - 14.0' FILL: Brown clayey silt; lens of f-m sand from 12.6-12.7'; soft, wet | 0.0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 15.0' OH: Dark olive brown (2.5Y 3/3) clayey silt; soft, wet | | 140-SB-048-1214 collected from 13.5-14.0' bgs @ 9:35 |
| | 15.0 | | | | | 15.0 - 15.6' OH: Black (2.5Y 2.5/1) clayey silt, trace organic material; soft, wet | | 140-SB-048-1416 collected from 15.0-15.5' bgs @ 9:40 |
| | 16.0 | | | | | 15.6 - 16.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 16' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-049
**DATE BEGAN:** 08/10/09
**DATE FINISHED:** 08/10/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 3.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map #139; location #141 abandoned due to overhead lines |
| | | | | | | 0.3 - 0.5' FILL: Brown f-m sand and gravel | | |
| | 1.0 | | | | | 0.5 - 2.8' FILL: Dark brown f-m sand, some f-c clinker, trace silt, f-m gravel, brick and coal; wet from 2.0' | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.8 - 3.3' FILL: Brown silt, trace clay and fine sand; stiff, wet | | |
| | | | | | | 3.3 - 3.5' FILL: Brown f-m sand, wet | | |
| | 4.0 | R-2 | N/A | 3.5 | | 3.5 - 4.0' No recovery | 0.0 | |
| | | | | | | 4.0 - 7.5' FILL: Brown f-c sand, trace fine gravel, some silt from 5.0-5.5'; wet | | 140-SB-049-0406 collected from 4.5-5.0' bgs @ 10:40 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | 140-SB-049-0608 collected from 7.0-7.5' bgs @ 10:45 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 4.0 | | 8.0 - 11.5' FILL: Brown f-c sand, trace fine gravel; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | 140-SB-049-0810 collected from 9.5-10.0' bgs @ 10:55 |
| | 11.0 | | | | | | | 140-SB-049-1012 collected from 11.5-12.0' bgs @ 11:00 |
| | | | | | | 11.5 - 12.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 12' | | |
| | 12.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-050
**DATE BEGAN:** 08/10/09
**DATE FINISHED:** 08/10/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 2.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 2.5 | | 0.0 - 0.3' ASPHALT | 0.0 | Field Map #158 |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Brown f-m sand and gravel | | |
| | | | | | | 0.5 - 1.5' FILL: Dark brown f-c sand, some fine clinker and gravel | | |
| | 2.0 | | | | | 1.5 - 2.2' FILL: Brown silty sand; wet from 2.0' bgs | | |
| | 3.0 | | | | | 2.2 - 2.5' FILL: Wood, some dark brown f-c sand and clinker; wet | | |
| | 4.0 | R-2 | N/A | 4.0 | | 2.5 - 4.0' No recovery | 0.0 | |
| | | | | | | 4.0 - 4.5' FILL: Dark brown f-c sand, some fine clinker and gravel; wet | | 140-SB-050-0406 collected from 4.5-5.0' bgs @ 12:05 |
| | 5.0 | | | | | 4.5 - 8.0' FILL: Brown/dark brown f-m sand, some silt lenses, trace wood; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | R-3 | N/A | 4.0 | | | 0.0 | 140-SB-050-0608 collected from 7.5-8.0' bgs @ 12:10 |
| | 9.0 | | | | | 8.0 - 12.0' FILL: Brown f-c sand, trace shells; wet | | |
| | 10.0 | | | | | | | 140-SB-050-0810 collected from 9.5-10.0' bgs @ 12:15 |
| | 11.0 | | | | | | | |
| | 12.0 | R-4 | N/A | 2.0 | | 12.0 - 14.0' PT: Very dark brown (7.5YR 2.5/2) peat; end of boring at 14' | 0.0 | 140-SB-050-1012 collected from 11.5-12.0' bgs @ 12:20 |
| | 13.0 | | | | | | | 140-SB-050-1214 collected from 12.0-12.5' bgs @ 12:30 |
| | 14.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Study Area - 6 South

**SITE INFO:** Site 140, ABF Trucking, Jersey City, NJ
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-051
**DATE BEGAN:** 08/11/09
**DATE FINISHED:** 08/11/09
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 1.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | R-1 | N/A | 4.0 | | 0.0 - 0.5' ASPHALT | 0.0 | Field Map #124 |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Very dark brown silty sand, trace fine gravel | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Very dark brown f-c sand and fine clinker; wet | | |
| | 3.0 | | | | | 2.0 - 5.0' FILL: Reddish brown silt, thinly laminated and stiff; few lenses of f-c sand, trace fine gravel and brick; wet | | |
| | 4.0 | R-2 | N/A | 3.0 | | | 0.0 | |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Brown f-m sand, trace silt; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | R-3 | N/A | 2.5 | | 8.0 - 10.5' FILL: Brown f-m sand, some silt nodules; wet | 0.0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | R-4 | N/A | 3.5 | | 12.0 - 13.2' FILL: Brown sandy silt, trace clay; moist | 0.0 | |
| | 13.0 | | | | | 13.2 - 14.0' FILL: Very dark grayish brown clayey silt; moist | | 140-SB-051-1214 collected from 13.5-14.0' bgs @ 10:45; DUP @ 10:47 |
| | 14.0 | | | | | 14.0 - 15.0' OH: Dark olive brown (2.5Y 3/3) clayey silt, some organic material; moist | | |
| | 15.0 | | | | | 15.0 - 15.5' PT: Very dark brown (7.5YR 2.5/2) peat; wet | | 140-SB-051-1416 collected from 14.5-15.0' bgs @ 10:50; DUP @ 10:52 |
| | 16.0 | | | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |

PREPARED BY: JB
CHECKED BY: FP

# Honeywell Site SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-059
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 1.0' ASPHALT | 0 | |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Brown silty fine to medium sand, some fine to medium gravel, trace brick and metal; moist, dense | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Fine to medium gravel, trace coarse sand; wet, loose | | |
| | 3.0 | | | | | 3.0 - 3.3' FILL: Red clayey silt, some fine brown sand, trace brick; moist, firm | | |
| ▽ | 4.0 | S-2 | NA | 4 | | 3.3 - 3.8' FILL: Brown fine to coarse sand, some fine to medium gravel and clinker, trace coal; wet, dense | 0 | |
| | 5.0 | | | | | 3.8 - 4.0' FILL: Brown silty sand, trace organics; moist, firm | | |
| | 6.0 | | | | | 4.0 - 6.0' FILL: Brown silty fine to medium sand, mottling of clay, trace coarse sand; wet, loose | | |
| | 7.0 | | | | | 6.0 - 8.0' FILL: Brown fine to coarse sand, motteling of silt; wet, loose | | |
| | 8.0 | S-3 | NA | 2 | | 8.0 - 10.0' FILL: Fine to medium brown sand, motteling of brown clay; wet, loose; end of boring @ 10.0' bgs | 0 | |
| | 9.0 | | | | | | | Sample collected 140-SB-059-0810 from 9.0-9.5 bgs @ 08:50 |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-060
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT | 0 | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Brown silty fine to medium sand, fine to coarse gravel, trace red silt; moist, dense | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dark greyish brown fine to coarse sand, some white and orange clinker; wet, loose | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.5 | | 2.5 - 3.5' FILL: Brown fine to medium sand, trace fine gravel, wood, and coarse sand; moist, loose | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 7.5' FILL: Brown fine to medium sand, lenses of reddish brown clay and silt, trace coarse sand; wet, loose | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No Recovery | 0 | |
| | 9.0 | | | | | 8.0 - 8.8' FILL: Brown fine to medium sand, lenses of reddish brown clay and silt, trace coarse sand; wet, loose | | |
| | 10.0 | | | | | 9.8 - 11.8' FILL: Brown silt, mottling of clayey silt; wet, loose | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 11.8 - 12.5' FILL: Brown clayey silt; wet, loose | 0 | |
| | 13.0 | | | | | 12.5 - 14.5' OL: Greyish brown silty clay, trace fine to medium sand; we, moderately firm | | Sample collected 140-SB-060-1214 from 13.0-13.5' bgs @ 0925 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 14.5 - 15.5' OL: Grey silty clay, trace organics; wet, moderately firm | | Sample collected 140-SB-060-1416 from 15.0-15.5' bgs @ 0930 |
| | 16.0 | | | | | 15.5 - 16.0' PT: PEAT; end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-061
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT | 0 | |
| | 1.0 | | | | | 0.8 - 1.8' FILL: Dark brown silty sand, trace metal; moist, dense | | |
| | 2.0 | | | | | 1.8 - 2.3' FILL: Dark brown fine to coarse sand with clinker and fine to medium gravel, trace coal | | |
| | 3.0 | | | | | 2.3 - 3.0' FILL: Red silty fine sand, trace coal; moist, dense | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.0 - 4.0' No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Reddish brown fine to coarse sand with fine to medium gravel; wet, very loose | | |
| | 6.0 | | | | | 4.5 - 5.5' FILL: Reddish brown silty clay; wet, firm | | |
| | 7.0 | | | | | 5.5 - 7.5' FILL: Brown fine to medium sand, some silt, trace fine to medium gravel and wood; wet, loose | | |
| | 8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 10.0' FILL: Brown fine to medium sand, some silt; wet, loose | | |
| | 10.0 | | | | | 10.0 - 11.8' FILL: Brown silt; wet, very loose | | |
| | 11.0 | | | | | 11.8 - 12.0' FILL: Brown and black mottling of silt, some clay | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 14.5' OL: Brown clayey silt, some fine sand with depth | 0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 14.5 - 15.8' OL: Black silty clay, trace organics; wet, firm | | Sample collected 140-SB-061-1416 from 15.0-15.5' bgs @ 1005; DUP @ 1007 |
| | 16.0 | | | | | 15.8 - 16.0' PT: Peat; end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-062
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Dark brown to black fine to medium sand | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown silt | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Dark brown silty fine sand with clinker, trace glass and fine to medium gravel | | |
| | 4.0 | S-2 | NA | 2.75 | | 3.0 - 3.5' FILL: Reddish brown silty sand, some fine to medium brick | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 4.5' FILL: Reddish brown silty sand, some fine to medium brick; wet | | |
| | 7.0 | | | | | 4.5 - 4.8' FILL: Light brown clayey silt; wet | | |
| | 8.0 | S-3 | NA | 4.0 | | 4.8 - 6.8' FILL: Light brown fine to medium sand with lenses of clayey silt; wet | 0 | |
| | 9.0 | | | | | 6.8 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 12.5' FILL: Light brown fine to medium sand with lenses of clayey silt; wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | | 4.0 | | | 0 | |
| | 13.0 | | | | | 12.5 - 13.8' OL: Light brown clayey silt; very soft | | |
| | 14.0 | | | | | 13.8 - 14.8' OL: Light brown clayey silt with fine to medium sand; very soft | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-062
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | S-5 | NA | 1.5 | | 14.8 - 15.8' OL: Light brown clayey silt<br>15.8 - 16.0' OL: Black clayey silt<br>16.0 - 17.5' PT: Dark brown peat; moist<br>17.5 - 18.0' No recovery; end of boring @ 18.0' bgs | 0 | Sample collected 140-SB-062-1618 from 16.5-17.0' bgs @ 1040 |
| | 16.0 | | | | | | | |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-063
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 3.75 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Dark brown to black silt with coal | | |
| | 2.0 | | | | | 1.5 - 1.8' FILL: Concrete | | |
| | 3.0 | | | | | 1.8 - 3.0' FILL: Black silty sand with clinker and gravel | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 3.5' FILL: Reddish brown fine to medium sand with silt and fine gravel; wet | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 4.5' FILL: Reddish brown fine to medium sand with silt and fine gravel; wet | | |
| | 7.0 | | | | | 4.5 - 6.5' FILL: Light brown clayey silt with organics from 4.5-5.0' bgs; wet | | |
| | 8.0 | S-3 | NA | 4.0 | | 6.5 - 7.0' FILL: Light brown fine to medium sand; wet | 0 | |
| | 9.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 10.0 | | | | | 8.0 - 10.5' FILL: SAA | | |
| | 11.0 | | | | | 10.5 - 11.3' FILL: Ligh brown clayey silt with lenses of fine to medium sand and silt; soft | | |
| | 12.0 | S-4 | | 3.75 | | 11.3 - 12.0' FILL: Light brown fine to medium sand | 0 | |
| | 13.0 | | | | | 12.0 - 15.3' FILL: Light brown clayey silt with lenses of fine to medium sand and silt | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.3 - 15.8' OL: Black clayey silt | | |
| | 16.0 | S-5 | NA | 2.0 | | 15.8 - 16.0' No recovery | 0 | Sample collected 140-SB-063-1618 from 16.5-17.0' bgs @ 1145 |
| | 17.0 | | | | | 16.0 - 18.0' PT: Dark brown peat; moist; end of boring @ 18.0' bgs | | |
| | 18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-064
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Brown silty sand, fine to coarse gravel and crushed concrete | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Dark brown silty fine sand, fine gravel and fine brick; dense | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| ▽ | 4.0 | S-2 | NA | 3.0 | | 4.0 - 5.0' FILL: Dark brown silty fine sand, fine gravel and fine brick; dense, wet | 0 | |
| | 5.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, lenses of reddish brown silt; wet | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Light brown fine to medium sand, lenses of reddish brown silt; wet | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 3.5 | | 12.0 - 14.0' FILL: Reddish brown to light brown clayey silt, lenses of reddish brown silty sand; clayey silt is soft, silty sand is dense | 0 | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 15.0' FILL: Dark brown clayey silt with organics; faint organic odor | | |
| | 15.0 | | | | | 15.0 - 15.5' OL: Light brown clayey silt | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-064

**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna

**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.0 ft bgs

**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | NA | 3.0 | | 15.5 - 16.0' No recovery | 0 | Sample collected 140-SB-064-1618 from 16.5-17.0' bgs @ 1300 |
| | 17.0 | | | | | 16.0 - 17.0' OL: Olive clayey silt with trace organics | | |
| | 18.0 | | | | | 17.0 - 18.3' PT: Brown peat; moist | | Sample collected 140-SB-064-1820 from 18.0-18.5' bgs @ 1305 |
| | 19.0 | | | | | 18.3 - 19.0' SW: Olive to light brown fine to medium sand with organics | | |
| | 20.0 | | | | | 19.0 - 20.0' No recovery; end of boring @ 20.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-065
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.0 - 0.8' FILL: Concrete | | |
| | 1.0 | | | | | 0.8 - 3.0' FILL: Light brown fine to medium sand and fine to medium gravel, trace coal and orange sand; dry, dense | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.8' FILL: Concrete | | |
| | 4.0 | S-2 | NA | 4.0 | | 3.8 - 4.0' FILL: Red fine silty sand, trace brick, yellowish green mottling of fine sand (COPR); dense, dry | 0 | |
| | | | | | | 4.0 - 4.0' FILL: Greenish yellow fine sand (COPR); dry, dense | | |
| | 5.0 | | | | | 4.0 - 6.5' FILL: Brown silty sand, mottling of brick and black silt, trace organics, coal, and fine to medium gravel | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.5 - 8.0' FILL: Brown fine to medium sand, some silt, trace mottling of clay; moist, loose | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 11.9' FILL: Brown fine to medium sand, some silt, trace mottling of clay; moist, loose | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 3.0 | | 11.9 - 12.0' OL: Brown silt; wet, soft | 0 | |
| | | | | | | 12.0 - 14.0' OL: Brown clayey silt | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 15.0' OL: Brown and black silt, some fine sand | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-065
**DATE BEGAN:** 5/03/10
**DATE FINISHED:** 5/03/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | NA | 3.5 | | 16.0 - 17.0' OL: Black silty clay, trace organics; wet, soft | 0 | |
| | 17.0 | | | | | 17.0 - 18.5' PT: Brown peat; moist | | Sample collected 140-SB-065-1618 from 16.5-17.0' bgs @ 1405 |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 18.5 - 19.5' SM: Brown silty sand | | Sample collected 140-SB-065-1820 from 19.0-19.5' bgs @ 1410 |
| | 20.0 | | | | | 19.5 - 20.0' No recovery; end of boring @ 20.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-066
**DATE BEGAN:** 5/04/10
**DATE FINISHED:** 5/04/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.2' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.2 - 0.8' FILL: Light brown to dark brown silty fine to medium sand and fine to medium gravel, trace brick; dry, loose | | |
| | 2.0 | | | | | 0.8 - 0.8' FILL: Concrete | | |
| | 3.0 | | | | | 0.8 - 2.3' FILL: Brown silty fine sand, trace brick, coal, and fine to medium gravel; moist | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.3 - 2.5' FILL: Dark brown fine to coarse sand, some clinker, trace silt | 0 | |
| | 5.0 | | | | | 2.5 - 3.0' FILL: Light brown silt, trace fine sand, organics, and clay; moist, firm | | |
| | 6.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 7.0 | | | | | 4.0 - 8.0' FILL: Brown fine to medium sand, lenses of silt and clay; saturated, loose | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Brown fine to medium sand, lenses of silty and clay, some silt; saturated, loose | 0 | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | | 4.0 | | 12.0 - 12.8' MH: Brown clayey silt, some fine sand; wet, firm | 0 | |
| | 13.0 | | | | | 12.8 - 15.0' OL: Brown silty clay, some fine sand; wet, soft | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 15.9' OL: Grey silty clay, trace fine sand and organics; wet, firm | | Sample collected 140-SB-066-1416 from 15.0-15.5' bgs @ 0800 |
| | 16.0 | | | | | 15.9 - 16.0' PT: Peat; end of boring @ 16.0' bgs | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-067
**DATE BEGAN:** 5/04/10
**DATE FINISHED:** 5/04/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' ASPHALT: Asphalt and gravel | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Concrete | | Sample collected 140-SB-067-0002 from 1.5-2.0' bgs @ 835 |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Red silt, some fine sand, trace fine to medium gravel and black silt; dry, dense | 1.1<br>1.1 | |
| | 3.0 | | | | | 2.0 - 2.9' FILL: Greenish brown fine sand, some silt (COPR), trace wood | 2.3<br>0 | Sample collected 140-SB-067-0204 from 2.5-3.0' bgs @ 840 |
| | 4.0 | S-2 | NA | 4.0 | | 2.9 - 6.0' FILL: Black silt, some fine sand and trace organics; dry, dense | 0 | |
| | 5.0 | | | | | | | Sample collected 140-SB-067-0406 from 4.5-5.0' bgs @ 845 |
| | 6.0 | | | | | 6.0 - 7.0' FILL: White, grey, greenish grey, and light brown silty sand (COPR), some wood; wet, loose | | Sample collected 140-SB-067-0608 from 6.5-7.0' bgs @ 850 |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Brown clayey silt; wet, soft | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.3' FILL: Brown fine to medium sand, some lenses of red silt, trace organics; wet, loose | 0 | Sample collected 140-SB-067-0810 from 8.5-9.0' bgs @ 855 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.3 - 10.5' FILL: Roots, some black silt; wet, loose | | Sample collected 140-SB-067-1012 from 10.0-10.5' bgs @ 900 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 16.5' PT: Peat | 0 | Sample collected 140-SB-067-1214 from 12.5-13.0' bgs @ 905 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-067
**DATE BEGAN:** 5/04/10
**DATE FINISHED:** 5/04/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | S-5 | NA | 3.0 | | | 0 | Sample collected 140-SB-067-1416 from 15.5-16.0' bgs @ 910 |
| | 16.0 | | | | | 16.5 - 18.0' SM: Brown silty sand, trace organics; wet, loose | | Sample collected 140-SB-067-1618 from 17.0-17.5' bgs @ 915 |
| | 17.0 | | | | | 18.0 - 18.8' SM: Greenish grey silty sand, trace clay; wet, loose | | Sample collected 140-SB-067-1820 from 18.5-19.0' bgs @ 920; DUP @ 922 |
| | 18.0 | | | | | 18.8 - 19.0' CL: Greenish grey clayey fine sand, some silt, trace organics; wet, loose | | |
| | 19.0 | | | | | 19.0 - 20.0' No recovery; end of boring @ 20.0' bgs | | |
| | 20.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-068
**DATE BEGAN:** 5/04/10
**DATE FINISHED:** 5/04/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.3 - 0.5' FILL: Brown silty sand and fine gravel | | Sample collected 140-SB-068-0002 from 0.5-1.0' bgs @ 935 |
| | 2.0 | | | | | 0.5 - 2.0' FILL: Concrete | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Brown silty sand, some brick, wood and fine to medium gravel, trace coal, glass and plastic | | Sample collected 140-SB-068-0204 from 2.5-3.0' bgs @ 940 |
| | 4.0 | S-2 | NA | 4.0 | | 3.0 - 3.3' FILL: Dark brown sandy silt, some clinker, coal and wood; wet, loose | 0 | Sample collected 140-SB-068-0406 from 4.0-4.5' bgs @ 945 |
| | 5.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 4.3' FILL: Reddish brown sandy silt, mottling of green, orange, and white silt (COPR), trace organics | | |
| | 7.0 | | | | | 4.3 - 5.5' FILL: Reddish brown silty sand, trace organics; wet, loose | | Sample collected 140-SB-068-0608 from 7.0-7.5' bgs @ 950 |
| | 8.0 | S-3 | NA | 4.0 | | 5.5 - 5.8' FILL: Reddish brown clayey silt; wet, very soft | 0 | |
| | 9.0 | | | | | 5.8 - 9.0' FILL: Brown fine to medium sand, lenses of clayey silt; saturated, loose | | Sample collected 140-SB-068-0810 from 8.5-9.0' bgs @ 955 |
| | 10.0 | | | | | 9.0 - 9.5' FILL: Brown clayey silt, some fine sand; wet, loose | | |
| | 11.0 | | | | | 9.5 - 11.8' SC: Brown fine to medium sand, mottling of organic black clay | | Sample collected 140-SB-068-1012 from 11.0-11.5' bgs @ 1000 |
| | 12.0 | S-4 | NA | 3.5 | | 11.8 - 12.0' PT: Brown peat; moist | 0 | |
| | 13.0 | | | | | 12.0 - 15.5' PT: Peat | | Sample collected 140-SB-068-1214 from 12.5-13.0' bgs @ 1005 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | Sample collected 140-SB-067-1416 from 14.5-15.0' bgs @ 1010 |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-069
**DATE BEGAN:** 5/04/10
**DATE FINISHED:** 5/04/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.3 - 1.5' FILL: Dark brown fine to medium gravel, fine to medium silty sand, trace coal and tar | | Sample collected 140-SB-069-0002 from 0.5-1.0' bgs @ 1020 |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown silty sand, wood and fine to medium gravel, trace brick and coal | | Sample collected 140-SB-069-0204 from 1.5-2.0' bgs @ 1025 |
| | 3.0 | | | | | 2.5 - 3.3' FILL: Whitish-grey silty sand (COPR); soft | | Sample collected 140-SB-069-0406 from 3.0-3.5' bgs @ 1030 |
| | 4.0 | S-2 | NA | 4.0 | | 3.3 - 3.5' FILL: Red silty sand, trace wood; dry, dense | 0 | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Reddish brown fine to medium sand mixed with white, green, grey sand (Possible COPR precipitants) | | Sample collected 140-SB-069-0406 from 5.0-5.5' bgs @ 1030 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Brown fine to medium, trace fine to medium gravel; wet, loose | | Sample collected 140-SB-069-0608 from 7.5-8.0' bgs @ 1035 |
| | 8.0 | S-3 | NA | 3.25 | | 8.0 - 9.0' FILL: Reddish brown silt; wet, soft | 0 | Sample collected 140-SB-069-0810 from 8.5-9.0' bgs @ 1040 |
| | 9.0 | | | | | 9.0 - 11.2' SM: Grey silty fine to medium sand, lenses of clay @ 10.9-11.0, more organics with depth; wet, dense | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.2 - 11.3' PT: Peat | | Sample collected 140-SB-069-1012 from 10.5-11.0' bgs @ 1045 |
| | | | | | | 11.3 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-070
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' ASPHALT: Asphalt, tar and gravel | 0 | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Dark brown sand, fine to medium gravel, some tar and coal, trace silt; dense | | Sample collected 140-SB-070-0002 from 1.5-2.0' bgs @ 935 |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Brown fine to medium sand, trace silt and fine to medium gravel; dry ,dense | | Sample collected 140-SB-070-0204 from 3.0-3.5' bgs @ 940 |
| | 3.0 | | | | | 2.5 - 2.8' FILL: Fine to coarse gravel, some fine to medium brown sand | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.8 - 3.5' FILL: Dark brown silty sand, fine to medium gravel, some wood, clinker, coal and glass; moderate dense | 0 | Sample collected 140-SB-070-0406 from 4.0-4.5' bgs @ 945 |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 4.8' FILL: Grey and white silt (COPR); soft, wet | | Sample collected 140-SB-070-0608 from 7.0-7.5' bgs @ 950 |
| | 7.0 | | | | | 4.8 - 7.5' FILL: Brown fine to medium sand, some silt, more fine sand with depth; firm, moist | | |
| | 8.0 | S-3 | NA | 3.25 | | 7.5 - 9.0' FILL: Brown fine to meidum sand, trace fine to medium gravel and mottling of silt | 0 | Sample collected 140-SB-070-0810 from 9.0-9.5' bgs @ 955 |
| | 9.0 | | | | | 9.0 - 9.5' ML: Brown silt, some fine sand; wet, firm | | Sample collected 140-SB-070-1012 from 10.0-10.5' bgs @ 1000 |
| | 10.0 | | | | | 9.5 - 10.0' OL: Black silt, trace fine sand; wet, soft | | |
| | 11.0 | S-4 | NA | 2.5 | | 10.0 - 11.3' PT: Brown peat; moist | 0 | Sample collected 140-SB-070-1214 from 12.0-12.5' bgs @ 1005 |
| | 12.0 | | | | | 11.3 - 12.0' No recovery | | |
| | 13.0 | | | | | 12.0 - 14.5' PT: Brown peat; moist | | Sample collected 140-SB-070-1416 from 14.0-14.5' bgs @ 1010 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-071
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12ft bgs
**GW DEPTH:** 3.75 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.3' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.3 - 0.5' FILL: Brown fine to medium sand, trace fine to medium gravel; dry, loose | | Sample collected 140-SB-068-0002 from 0.5-1.0' bgs @ 935 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Dark brown fine to medium silty sand, some coal, trace brick and fine to medium gravel; dry, moderate dense | | |
| | 2.0 | | | | | 1.0 - 2.0' FILL: Dark brown fine to coarse gravel, dark brown silty fine to medium sand and tar | | |
| | 3.0 | | | | | 2.0 - 3.8' FILL: Dark brown silty fine to coarse sand, some fine to medium gravel and clinker, trace brick, coal, and wood, lense of crushed concrete from 3.0-3.25; dense, moist | | |
| | 4.0 | S-2 | NA | 3.75 | | | 0 | |
| | 5.0 | | | | | 3.8 - 4.0' No recovery | | |
| | | | | | | 4.0 - 4.5' FILL: Grey and white silt (COPR); soft, wet | | |
| | 6.0 | | | | | 4.5 - 5.0' FILL: Brown silt, trace fine sand; wet, dense | | |
| | 7.0 | | | | | 5.0 - 7.8' FILL: Brown fine to medium sand, lenses of clayey silt, trace coarse sand; saturated, loose | | |
| | 8.0 | S-3 | NA | 2.5 | | 7.8 - 8.0' No recovery | 0 | |
| | | | | | | 8.0 - 9.5' FILL: Brown fine to medium sand, lenses of clayey silt, trace coarse sand; saturated, loose | | |
| | 9.0 | | | | | 9.5 - 10.0' SM: Brown sand, some silt; wet, dense | | |
| | 10.0 | | | | | 10.0 - 10.5' OL: Black silt, trace organics; wet, firm | | Sample collected 140-SB-071-1012 from 10.0-10.5' bgs @ 10:20 |
| | 11.0 | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** ite 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** **140-SB-072**
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Dark brown silty sand, fine to medium gravel, trace coal and brick; dry, loose; end of boring @ 2.0' bgs | | Sample collected 140-SB-072-0002 from 1.5-2.0' bgs @ 10:40 |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-073
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | | | | | | 0.5 - 1.8' FILL: Dark brown silt, some fine sand, trace coal, brick, and wood; dry, dense | | |
| | 1.0 | | | | | | | Sample collected 140-SB-073-0002 from 1.5-2.0' bgs @ 12:25 |
| | | | | | | 1.8 - 2.0' FILL: Dark brown silty sand; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-074
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.75 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.2' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.2 - 0.5' FILL: Brown fine to medium sand, trace silt; dry, dense | | Sample collected 140-SB-074-0002 from 1.0-1.5' bgs @ 1120 |
| | 2.0 | | | | | 0.5 - 0.8' FILL: Brown silty fine to medium sand, fine to medium gravel | | |
| | 3.0 | | | | | 0.8 - 0.9' FILL: Brown silt, some fine sand | | Sample collected 140-SB-074-0204 from 3.0-3.5' bgs @ 1125 |
| | 4.0 | S-2 | NA | 4.0 | | 0.9 - 3.0' FILL: Dark brown sandy silt, trace coal, glass, fine to medium gravel, and wood; moist, dense | 0 | |
| | 5.0 | | | | | 3.0 - 4.5' FILL: Brown silty sand; wet, moderate dense | | Sample collected 140-SB-074-0406 from 4.0-4.5' bgs @ 1130 |
| | 6.0 | | | | | 4.5 - 10.0' FILL: Brown fine to medium sand, lenses of clayey silt, trace shells; wet, loose | | |
| | 7.0 | | | | | | | Sample collected 140-SB-074-0608 from 7.0-7.5' bgs @ 1135 |
| | 8.0 | S-3 | NA | 3.0 | | | 0 | |
| | 9.0 | | | | | | | Sample collected 140-SB-074-0810 from 8.5-9.0' bgs @ 1140; DUP @ 1142 |
| | 10.0 | | | | | 10.0 - 11.0' PT: Peat | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | Sample collected 140-SB-074-1012 from 10.5-11.0' bgs @ 1145 |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' PT: Peat | 0 | |
| | 13.0 | | | | | | | Sample collected 140-SB-074-1214 from 12.5-13.0' bgs @ 1150 |
| | 14.0 | | | | | | | Sample collected 140-SB-074-1416 from 14.0-14.5' bgs @ 1155 |
| | 15.0 | | | | | 14.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-075
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Dark brown silty sand, fine to medium gravel, trace brick and coal; moderate dense, dry | | |
| | 2.0 | | | | | 1.3 - 1.8' FILL: Light brown fine to medium sand, some silt, trace coal; moist, dense | | |
| | 3.0 | | | | | 1.8 - 3.3' FILL: Dark brown fine to coarse sand, some silt and clinker, trace clay; wet, dense | | |
| | 4.0 | S-2 | NA | 3.75 | | 3.3 - 3.8' FILL: Brown silt, some fine sand, trace glass; dense wet | 0 | |
| | 5.0 | | | | | 3.8 - 4.0' FILL: Brown fine to coarse sand, some glass, trace silt; wet, loose | | |
| | 6.0 | | | | | 4.0 - 7.8' FILL: Brown fine to coase sand, lenses of silt, trace shells; wet, loose | | |
| | 7.0 | | | | | 7.8 - 8.0' No recovery | | Sample collected 140-SB-075-0608 from 7.0-7.5' bgs @ 12:50 |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 10.0' FILL: Brown fine to coarse sand, lenses of silt, trace shells; wet, loose | 0 | Sample collected 140-SB-075-0810 from 8.5-9.0' bgs @ 12:55 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.5' PT: Peat | | Sample collected 140-SB-075-1012 from 10.5-11.0' bgs @ 13:00 |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.0 | | 11.5 - 12.0' No recovery | | |
| | 13.0 | | | | | 12.0 - 14.0' PT: Peat; end of boring @ 14.0' bgs | 0 | Sample collected 140-SB-075-1214 from 12.5-13.0' bgs @ 13:05 |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-076
**DATE BEGAN:** 5/05/10
**DATE FINISHED:** 5/05/10
**INSPECTOR:** M. Daly/ B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt | 0 | |
| | | | | | | 0.5 - 1.0' FILL: Brown silty fine to medium sand, some fine to medium gravel, trace coal and brick | | |
| | 1.0 | | | | | 1.0 - 1.2' FILL: Reddish brown silt, some fine sand, trace wood and brick; dry, dense | | |
| | | | | | | 1.2 - 2.0' FILL: Brown fine to medium sand, trace fine to medium gravel and glass | | |
| | 2.0 | | | | | 2.0 - 2.5' CONCRETE: Concrete | | |
| | | | | | | 2.5 - 3.5' FILL: Brown fine to medium sand, fine to medium gravel, some silt, trace clay; moist, loose | | |
| | 3.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Brown fine to medium sand, mottling of silt and clay; wet, loose | 0 | Sample collected 140-SB-076-0608 from 6.5-7.0' bgs @ 13:30 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-077
**DATE BEGAN:** 8/18/10
**DATE FINISHED:** 8/18/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' ASPHALT: Asphalt and gravel | 0 | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Black to brown silt, fine sand, coal, gravel, trace brick | | |
| | 2.0 | | | | | 1.0 - 2.5' FILL: Light brown silt, gravel, sandstone | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Brown to gray fine to medium sand; wet at 3.0 ft. bgs. | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.5 - 4.0' No recovery<br>4.0 - 6.0' FILL: Brown to gray fine to medium sand; wet at 3.0 ft. bgs. | 0 | Sample collected 140-SB-077-0406 from 4.5-5.0' bgs @ 8:50 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Wet light brown silt, lenses of fine to coarse sand throughout | | |
| | 7.0 | | | | | | | Sample collected 140-SB-077-0608 from 7.0 - 7.5' bgs @ 8:55 |
| | 8.0 | S-3 | NA | 3.5 | | 7.5 - 8.0' No recovery<br>8.0 - 9.5' FILL: Wet gray fine to coarse sand , shells | 0 | |
| | 9.0 | | | | | | | Sample collected 140-SB-077-0810 from 8.5-9.0' bgs @ 9:00 |
| | 10.0 | | | | | 9.5 - 11.5' PT: Moist brown peat | | |
| | 11.0 | | | | | | | Sample collected 140-SB-077-1012 from 10.5-11.0' bgs @ 9:05 |
| | 12.0 | | | | | 11.5 - 12.0' No recovery; end of boring at 12.0 ft. bgs. | | |

PREPARED BY: BS
CHECKED BY: QA QC

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-078
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.7' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.7 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.0' FILL: Red brown silt, gravel | 0 | Sample collected 140-SB-078-0200 from 2.0-0.0' bgs @ 8:15 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 3.0' FILL: Light brown silt, fine sand | 0 | Sample collected 140-SB-078-0002 from 0.0 - 2.0' bgs @ 8:20 |
| | 1.0 | | | | | | | |
| | 2.0 | S-4 | NA | 1.5 | | | 0 | Sample collected 140-SB-078-0204 from 2.0-3.5' bgs @ 8:25 |
| ▽ | 3.0 | | | | | 3.0 - 3.5' FILL: Brown silt, fine sand, fine to coarse gravel; wet | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-5 | NA | 1.0 | | 4.0 - 5.0' FILL: Light brown fine sand, silt, trace wood, gravel; wet | 0 | Sample collected 140-SB-078-0406 from 4.0-5.0' bgs @ 8:30 |
| | 5.0 | | | | | 5.0 - 6.0' No recovery | | |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 6.5' FILL: Light brown fine sand, silt, trace wood, gravel; wet | 0 | Sample collected 140-SB-078-0608 from 6.0-8.0' bgs @ 8:35 |
| | | | | | | 6.5 - 7.0' FILL: Wood | | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Light gray/brown silt, light gray fine to medium sand; wood; wet | | |
| | 8.0 | S-7 | NA | 1.0 | | 8.0 - 9.0' FILL: Light brown silt; saturated | 0 | Sample collected 140-SB-078-0810 from 8.0-9.0' bgs @ 8:40 |
| | 9.0 | | | | | 9.0 - 10.0' No recovery | | |
| | 10.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-078
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | S-8 | NA | 1.0 | | 10.0 - 11.0' FILL: Light gray fine to medium sand, shells; wet | 0 | Sample collected 140-SB-078-1012 from 10.0-11.0' bgs @ 8:45 |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-9 | NA | 1.75 | | 12.0 - 12.3' FILL: Light gray fine to medium sand, shells; wet | 0 | Sample collected 140-SB-078-1214 from 12.0-13.0' bgs @ 8:50 |
| | 13.0 | | | | | 12.3 - 13.8' PT: Brown peat; moist | | |
| | 14.0 | | | | | 13.8 - 14.0' No recovery; end of boring at 14.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-079
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 12 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.7' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.7 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.0' FILL: Light brown/dark brown silt, gravel, concrete | 0 | Sample collected 140-SB-079-0200 from 2.0-0.0' bgs @ 9:15 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 1.0' FILL: Dark brown/black silty sand | 0 | Sample collected 140-SB-079-0002 from 0.0 - 2.0' bgs @ 9:20 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Brown silt, gravel, concrete, green tint on concrete; potential COPR | | |
| | 2.0 | S-4 | NA | 1.5 | | 2.0 - 3.5' FILL: Light brown/red brown silt. fine sand, trace wood, gravel, wet at 3.0' bgs. | 0 | Sample collected 140-SB-079-0204 from 2.0-3.5' bgs @ 9:25 |
| ▽ | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-5 | NA | 2.0 | | 4.0 - 4.3' FILL: White clayey silt; moist; Potential COPR | 0 | Sample collected 140-SB-079-0406 from 4.0-5.0' bgs @ 9:30 |
| | 5.0 | | | | | 4.3 - 4.5' FILL: Dark brown silty sand; wet | | |
| | 6.0 | S-6 | NA | 2.0 | | 4.5 - 6.0' FILL: Brown fine to medium sand; wet | 0 | Sample collected 140-SB-079-0608 from 6.0-8.0' bgs @ 9:35 |
| | 7.0 | | | | | 6.0 - 8.0' FILL: Brown fine to medium sand, lenses of clayey silt from 7.0 - 7.5' bgs.; wet | | |
| | 8.0 | S-7 | NA | 2.0 | | 8.0 - 11.0' FILL: Brown silt, heavy organics; moist | 0 | Sample collected 140-SB-079-0810 from 8.0-10.0' bgs @ 9:40 |
| | 9.0 | | | | | | | |
| | 10.0 | S-8 | NA | 2.0 | | | 0 | Sample collected 140-SB-079-1012 from 10.0-11.0' bgs @ 9:45 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | 11.0 - 12.0' PT: Brown peat; moist; end of boring at 12.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-080
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.4' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.4 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.0' FILL: Brown silt, gravel | 0 | Sample collected 140-SB-080-0200 from 2.0-0.0' bgs @ 10:15 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 2.0' FILL: Brown silt, fine sand, gravel, sandstone from 1.5 - 2.0' bgs. | 0 | Sample collected 140-SB-080-0002 from 0.0 - 2.0' bgs @ 10:20 |
| | 1.0 | | | | | | | |
| | 2.0 | S-4 | NA | 1.0 | | 2.0 - 3.0' FILL: Light brown silt, fine sand, fine light yellow nodules; potential COPR | 0 | Sample collected 140-SB-080-0204 from 2.0-3.0' bgs @ 10:25 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| ▽ | 4.0 | S-5 | NA | 2.0 | | 4.0 - 5.0' FILL: Dark brown silt, fine to coarse gravel; wet | 0 | Sample collected 140-SB-080-0406 from 5.0-6.0' bgs @ 10:30 |
| | 5.0 | | | | | 5.0 - 6.0' FILL: White clayey silt; COPR | | |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 8.0' FILL: Dark brown silt, fine to medium sand, trace wood from 6.0' - 7.0' bgs.; wet | 0 | Sample collected 140-SB-080-0608 from 6.0-8.0' bgs @ 10:35; DUP at 10:37 |
| | 7.0 | | | | | | | |
| | 8.0 | S-7 | NA | 2.0 | | 8.0 - 9.3' FILL: Light brown silt; wet | 0 | Sample collected 140-SB-080-0810 from 8.0-10.0' bgs @ 10:40 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-080
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.3 - 10.0' FILL: Dark brown/light brown fine to medium sand, lenses of silt; wet | | |
| | 10.0 | S-8 | NA | 2.0 | | 10.0 - 12.8' FILL: Light brown/light gray fine to medium sand | 0 | Sample collected 140-SB-080-1012 from 10.0-12.0' bgs @ 10:45 |
| | 11.0 | | | | | | | |
| | 12.0 | S-9 | NA | 1.5 | | | 0 | |
| | | | | | | 12.8 - 13.0' FILL: Red brown silt; wet | | |
| | 13.0 | | | | | 13.0 - 13.5' PT: Brown peat; moist | | Sample collected 140-SB-080-1214 from 13.0-13.5' bgs @ 10:50 |
| | | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-081
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.4' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.4 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.5' FILL: Light brown silty sand, gravel | 0 | Sample collected 140-SB-081-0200 from 2.0-0.0' bgs @ 12:15 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | | 0 | Sample collected 140-SB-081-0002 from 0.0 - 2.0' bgs @ 12:20 |
| | 1.0 | | | | | 0.5 - 3.0' FILL: Red brown silt, fine to coarse gravel | | |
| | 2.0 | S-4 | NA | 2.0 | | | 0 | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Black silty sand, brick, clinker, gravel, glass | | Sample collected 140-SB-081-0204 from 3.0-4.0' bgs @ 12:25 |
| ▽ | 4.0 | S-5 | NA | 2.0 | | 4.0 - 4.5' FILL: Black silty sand, brick, clinker, gravel, glass; wet | 0 | |
| | 5.0 | | | | | 4.5 - 6.0' FILL: White/light green COPR; wet | | Sample collected 140-SB-081-0406 from 5.0-6.0' bgs @ 12:30 |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 7.0' FILL: Light brown silt; wet | 0 | Sample collected 140-SB-081-0608 from 6.0-8.0' bgs @ 12:35 |
| | 7.0 | | | | | 7.0 - 9.0' FILL: Light brown silt, lenses of fine to medium sand; wet | | |
| | 8.0 | S-7 | NA | 2.0 | | | 0 | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-081
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.0 - 12.5' FILL: Light gray fine to medium sand; wet | | Sample collected 140-SB-081-0810 from 9.0-10.0' bgs @ 12:40 |
| | 10.0 | S-8 | NA | 2.0 | | | 0 | Sample collected 140-SB-081-1012 from 10.0-12.0' bgs @ 12:45 |
| | 11.0 | | | | | | | |
| | 12.0 | S-9 | NA | 2.0 | | | 0 | Sample collected 140-SB-081-1214 from 12.0-13.0' bgs @ 12:50 |
| | 13.0 | | | | | 12.5 - 13.5' OL: Light brown silt, heavy organics; wet | | |
| | | | | | | 13.5 - 14.0' FILL: Brown peat; moist; end of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-082
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.4' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.4 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.5' FILL: Red brown silt, gravel | 0 | Sample collected 140-SB-082-0200 from 2.0-0.0' bgs @ 13:40 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 1.5 | | | 0 | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Dark brown silty sand, coal, gravel, clinker | | Sample collected 140-SB-082-0002 from 1.0 - 1.5' bgs @ 13:45 |
| | | | | | | 1.5 - 2.0' No recovery | | |
| | 2.0 | S-4 | NA | 1.0 | | 2.0 - 3.0' FILL: Brown silty sand, wood, gravel, coal, shells | 0 | Sample collected 140-SB-082-0204 from 2.0-3.0' bgs @ 13:50 |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| ▽ | 4.0 | S-5 | NA | 2.0 | | 4.0 - 5.0' FILL: Brown silty sand, wood, gravel, coal, shells; wet | 0 | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Red brown silt, fine to medium sand lenses; wet | | Sample collected 140-SB-082-0406 from 5.0-6.0' bgs @ 13:55 |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 8.0' FILL: Light brown silt, lenses of light gray fine to medium sand, trace shells | 0 | Sample collected 140-SB-082-0608 from 6.0-8.0' bgs @ 14:00; DUP at 14:02 |
| | 7.0 | | | | | | | |
| | 8.0 | S-7 | NA | 1.0 | | 8.0 - 9.0' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-082-0810 from 8.0-9.0' bgs @ 14:05 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-082
**DATE BEGAN:** 10/27/10
**DATE FINISHED:** 10/27/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.0 - 10.0' No recovery | | |
| | 10.0 | S-8 | NA | 2.0 | | 10.0 - 11.5' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-082-1012 from 10.0-11.0' bgs @ 14:10 |
| | 11.0 | | | | | | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-9 | NA | 2.0 | | 12.0 - 13.0' FILL: Red brown silt | 0 | |
| | 13.0 | | | | | 13.0 - 14.0' OL: Gray clayey silt; very moist | | Sample collected 140-SB-082-1214 from 13.0-14.0' bgs @ 14:15 |
| | 14.0 | S-10 | NA | 2.0 | | 14.0 - 15.0' OL: Black clayey silt; very moist | 0 | Sample collected 140-SB-082-1416 from 14.0-15.0' bgs @ 14:20 |
| | 15.0 | | | | | 15.0 - 16.0' PT: Brown peat; moist; end of boring at 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-083
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.0' FILL: Red brown silt, fine sand, fine gravel | 0 | Sample collected 140-SB-083-0200 from 2.0-0.0' bgs @ 7:30 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 3.0' FILL: Brown silty sand, gravel, trace copper, trace coal | 0 | Sample collected 140-SB-083-0002 from 0.0 - 2.0' bgs @ 7:35 |
| | 1.0 | | | | | | | |
| | 2.0 | S-4 | NA | 2.0 | | | 0 | |
| ▽ | 3.0 | | | | | 3.0 - 5.3' FILL: Dark brown silt; wet | | Sample collected 140-SB-083-0204 from 3.0-4.0' bgs @ 7:40 |
| | 4.0 | S-5 | NA | 2.0 | | | 0 | |
| | 5.0 | | | | | 5.3 - 5.5' FILL: White silt; wet; Potental COPR | | Sample collected 140-SB-083-0406 from 5.0-6.0' bgs @ 7:45 |
| | | | | | | 5.5 - 6.0' FILL: Light brown silt; wet | | |
| | 6.0 | S-6 | NA | 1.5 | | 6.0 - 7.5' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 140-SB-083-0608 from 6.0-7.0' bgs @ 7:50 |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-7 | NA | 1.5 | | 8.0 - 8.5' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 140-SB-083-0810 from 8.0-9.5' bgs @ 7:55; DUP at 7:57 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-083
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 8.5 - 9.0' FILL: Light brown silt; wet | | |
| | | | | | | 9.0 - 9.5' FILL: Light brown fine to medium sand; wet | | |
| | 10.0 | S-8 | NA | 2.0 | | 9.5 - 10.0' No recovery | 0 | Sample collected 140-SB-083-1012 from 10.0-11.0' bgs @ 8:00 |
| | 11.0 | | | | | 10.0 - 12.0' FILL: Light brown/light gray fine to medium sand; wet | | |
| | 12.0 | S-9 | NA | 2.0 | | 12.0 - 12.5' FILL: Light brown/light gray fine to medium sand, shells; wet | 0 | |
| | | | | | | 12.5 - 13.9' FILL: Red brown silt; wet | | |
| | 13.0 | | | | | 13.9 - 14.0' PT: Brown peat; moist; end of boring at 16.0' bgs. | | Sample collected 140-SB-083-1214 from 13.0-14.0' bgs @ 8:05 |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-084
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 1.0 | | -2.0 - -1.0' FILL: Red brown silt, gravel, trace coal | 0 | Sample collected 140-SB-084-0210 from 2.0-1.0' bgs @ 8:40 |
| | -1.0 | | | | | -1.0 - 0.0' No recovery | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 0.5' FILL: Red brown silt, gravel, trace coal | 0 | Sample collected 140-SB-084-0002 from 0.0 - 1.5' bgs @ 8:45 |
| | | | | | | 0.5 - 0.8' FILL: Asphalt | | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Light brown silt, gravel | | |
| | | | | | | 1.5 - 2.0' FILL: Wood | | |
| | 2.0 | S-4 | NA | 2.0 | | 2.0 - 3.0' FILL: Brown silty sand, glass, gravel, coal | 0 | |
| ▽ | 3.0 | | | | | 3.0 - 4.0' FILL: Dark brown silt; wet | | Sample collected 140-SB-084-0204 from 3.0-4.0' bgs @ 8:50 |
| | 4.0 | S-5 | NA | 2.0 | | 4.0 - 5.5' FILL: Dark brown silt, gravel; wet | 0 | |
| | 5.0 | | | | | | | Sample collected 140-SB-084-0406 from 5.0-6.0' bgs @ 8:55 |
| | | | | | | 5.5 - 6.0' FILL: White COPR; we | | |
| | 6.0 | S-6 | NA | 1.5 | | 6.0 - 7.0' FILL: Dark brown silt; wet | 0 | Sample collected 140-SB-084-0608 from 6.0-7.5' bgs @ 9:00 |
| | 7.0 | | | | | 7.0 - 7.5' FILL: Light brown/red brown silt, fine sand; wet | | |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-7 | NA | 1.5 | | 8.0 - 8.5' FILL: Brown/light gray fine to medium sand; wet | 0 | Sample collected 140-SB-084-0810 from 8.0-9.0' bgs @ 9:05 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-084
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 8.5 - 9.5' FILL: Light brown fine sand; wet | | |
| | | | | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | S-8 | NA | 1.5 | | 10.0 - 11.5' FILL: Light brown/light gray fine to medium sand, trace coarse sand; wet | 0 | Sample collected 140-SB-084-1012 from 10.0-11.5' bgs @ 9:10 |
| | 11.0 | | | | | | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-9 | NA | 1.75 | | 12.0 - 12.8' FILL: Light brown/light gray fine to medium sand, trace coarse sand; wet | 0 | |
| | 13.0 | | | | | 12.8 - 13.5' OL: Brown clayey silt, organics | | Sample collected 140-SB-084-1214 from 12.5-13.5' bgs @ 9:15 |
| | | | | | | 13.5 - 13.8' PT: Brown peat; moist | | |
| | 14.0 | | | | | 13.8 - 14.0' No recovery; end of boring at 14.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-085
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 12 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.0' FILL: Red brown silt, gravel, trace coal | 0 | Sample collected 140-SB-085-0210 from 2.0-0.0' bgs @ 10:10 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 3.0' FILL: Light brown silt, fine sand, gravel, brick, coal | 0 | |
| | 1.0 | | | | | | | Sample collected 140-SB-085-0002 from 1.0 - 2.0' bgs @ 10:15 |
| | 2.0 | S-4 | NA | 1.75 | | | 0 | |
| ▽ | 3.0 | | | | | | | Sample collected 140-SB-085-0204 from 2.5-3.5' bgs @ 10:20 |
| | | | | | | 3.0 - 3.8' FILL: Dark brown silt, gravel; wet | | |
| | 4.0 | | | | | 3.8 - 4.0' No recovery | | |
| | | S-5 | NA | 2.0 | | 4.0 - 6.0' FILL: Dark brown silt, gravel from 4.0' - 4.5' bgs.; wet | 0 | |
| | 5.0 | | | | | | | Sample collected 140-SB-085-0406 from 5.0-6.0' bgs @ 10:25 |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 7.3' FILL: Light brown silt, fine sand, trace organics | 0 | Sample collected 140-SB-085-0608 from 6.0-8.0' bgs @ 10:30 |
| | 7.0 | | | | | | | |
| | | | | | | 7.3 - 8.0' FILL: Red brown silt; wet | | |
| | 8.0 | S-7 | NA | 1.5 | | 8.0 - 9.0' FILL: Red brown silt, lenses of fine to medium sand; wet | 0 | Sample collected 140-SB-085-0810 from 8.0-9.5' bgs @ 10:35 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-085
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 12 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | S-8 | NA | 2.0 | | 9.0 - 9.5' FILL: Light gray fine to medium sand; wet<br>9.5 - 10.0' No recovery<br>10.0 - 11.9' FILL: Light gray/light brown fine to medium sand, lenses of red brown silt; wet<br>11.9 - 12.0' PT: Brown peat; moist; end of boring at 12.0' bgs. | 0 | Sample collected 140-SB-085-1012 from 11.0-12.0' bgs @ 10:40 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-086
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.25 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 1.5' FILL: Light brown/red brown silt, gravel, brick | 0 | Sample collected 140-SB-086-0210 from 2.0-0.0' bgs @ 11:50 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | | 0 | |
| | 1.0 | | | | | | | Sample collected 140-SB-086-0002 from 1.0 - 2.0' bgs @ 11:55 |
| | 2.0 | S-4 | NA | 2.0 | | 1.5 - 3.0' FILL: Light brown/red brown silt, gravel, brick, wood. coal | 0 | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Dark brown silty sand, wood, gravel, plastic, coal; wet at 3.25' bgs. | | Sample collected 140-SB-086-0204 from 3.0-4.0' bgs @ 12:00 |
| | 4.0 | S-5 | NA | 1.0 | | 4.0 - 5.0' FILL: Brown silty sand, gravel, coal; saturated | 0 | Sample collected 140-SB-086-0406 from 4.0-5.5' bgs @ 12:05 |
| | 5.0 | | | | | 5.0 - 6.0' No recovery | | |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 6.5' FILL: Red brown silt; wet | 0 | |
| | 7.0 | | | | | 6.5 - 9.3' FILL: Light brown silt; wet | | Sample collected 140-SB-086-0608 from 7.0-8.0' bgs @ 12:15; DUP at 12:12 |
| | 8.0 | S-7 | NA | 2.0 | | | 0 | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-086
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.25 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.3 - 10.0' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | | Sample collected 140-SB-086-0810 from 9.0-10.0' bgs @ 12:15 |
| | 10.0 | S-8 | NA | 2.0 | | 10.0 - 11.9' FILL: Light brown/light gray fine to medium sand; wet | 0 | |
| | 11.0 | | | | | 11.9 - 12.0' OL: Brown clayey silt, heavy organics; very moist | | Sample collected 140-SB-086-1012 from 11.0-12.0' bgs @ 12:20 |
| | 12.0 | S-9 | NA | 2.0 | | 12.0 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | 0 | Sample collected 140-SB-086-1214 from 12.0-13.0' bgs @ 12:25 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-087
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.5' FILL: Red brown silt, gravel | 0 | Sample collected 140-SB-087-0200 from 2.0-0.0' bgs @ 12:55; VOCs, SVOCs |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | | 0 | |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Dark brown silty sand, brick, sandstone, wood | | Sample collected 140-SB-087-0002 from 1.0 - 2.0' bgs @ 13:00 |
| | 2.0 | S-4 | NA | 1.5 | | 2.0 - 3.5' FILL: Red brown silt, gravel, coal, trace glass | 0 | Sample collected 140-SB-087-0204 from 2.0-3.0' bgs @ 13:05 |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| ▽ | 4.0 | S-5 | NA | 2.0 | | 4.0 - 5.5' FILL: Red brown silt, gravel, coal, trace glass; wet | 0 | |
| | 5.0 | | | | | | | Sample collected 140-SB-087-0406 from 5.0-6.0' bgs @ 13:10 |
| | | | | | | 5.5 - 6.0' FILL: Olive/brown silt; wet | | |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 8.0' FILL: Light brown silt, fine to medium sand; saturated | 0 | |
| | 7.0 | | | | | | | Sample collected 140-SB-087-0608 from 7.0-8.0' bgs @ 13:15 |
| | 8.0 | S-7 | NA | 1.0 | | 8.0 - 9.0' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-087-0810 from 8.0-9.0' bgs @ 13:20 |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-087
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.0 - 10.0' No recovery | | |
| | 10.0 | S-8 | NA | 1.5 | | 10.0 - 11.3' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-087-1012 from 10.0-11.0' bgs @ 13:25; DUP at 13:27 |
| | 11.0 | | | | | 11.3 - 11.5' FILL: Brown clayey silt; wet | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-9 | NA | 2.0 | | 12.0 - 12.5' FILL: Green COPR | 0 | Sample collected 140-SB-087-1213 from 12.0-12.5' bgs @ 13:30 |
| | 13.0 | | | | | 12.5 - 13.8' FILL: Light brown silt; wet | | |
| | 14.0 | | | | | 13.8 - 14.0' FILL: Brown clayey silt; end of boring at 14.0' bgs. | | Sample collected 140-SB-087-1314 from 13.5-14.0' |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-087R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.5' FILL: Red brown silt, gravel | 0 | |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | | 0 | |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Dark brown silty sand, brick, sandstone, wood | | |
| | 2.0 | S-4 | NA | 1.5 | | 2.0 - 3.5' FILL: Red brown silt, gravel, coal, trace glass | 0 | |
| | 3.0 | | | | | | | |
| ▽ | 4.0 | | | | | 3.5 - 4.0' No recovery | | |
| | | S-5 | NA | 2.0 | | 4.0 - 5.5' FILL: Red brown silt, gravel, coal, trace glass; wet | 0 | |
| | 5.0 | | | | | | | |
| | | | | | | 5.5 - 6.0' FILL: Olive/brown silt; wet | | |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 8.0' FILL: Light brown silt, fine to medium sand; saturated | 0 | |
| | 7.0 | | | | | | | |
| | 8.0 | S-7 | NA | 1.0 | | 8.0 - 9.0' FILL: Light gray fine to medium sand; wet | 0 | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-087R
**DATE BEGAN:** 12/8/10
**DATE FINISHED:** 12/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | 9.0 - 10.0' No recovery | | |
| | 10.0 | S-8 | NA | 1.5 | | 10.0 - 11.3' FILL: Light gray fine to medium sand; wet | 0 | |
| | 11.0 | | | | | 11.3 - 11.5' FILL: Brown clayey silt; wet | | |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-9 | NA | 2.0 | | 12.0 - 12.5' FILL: Green COPR | 0 | |
| | 13.0 | | | | | 12.5 - 13.8' FILL: Light brown silt; wet | | |
| | | | | | | 13.8 - 14.0' FILL: Brown clayey silt; wet | | |
| | 14.0 | S-10 | NA | 1.5 | | 14.0 - 14.8' FILL: Light brown clayey silt; wet; soft | 0 | |
| | 15.0 | | | | | 14.8 - 15.0' FILL: Light brown silt; wet | | Sample collected 140-SB-087R-1416 from 15.0-15.5' bgs @ 11:00 |
| | 16.0 | | | | | 15.0 - 15.5' OL: Black/brown clayey silt, trace organics; very moist; end of boring at 16.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-088
**DATE BEGAN:** 10/29/10
**DATE FINISHED:** 10/29/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -3.0 | S-1 | NA | 0.0 | | -3.5 - -2.5' CONCRETE: Concrete | | Inside 80 Kellogg building - 3.5' above grade |
| | | | | | | -2.5 - -2.0' Void | | |
| | -2.0 | S-2 | NA | 2.0 | | -2.0 - 0.0' FILL: Red brown silt, gravel | 0 | Sample collected 140-SB-088-0200 from 2.0-0.0' bgs @ 12:35 |
| | -1.0 | | | | | | | |
| | 0.0 | S-3 | NA | 2.0 | | 0.0 - 2.0' FILL: Red brown silt, gravel, brick, coal | 0 | Sample collected 140-SB-088-0002 from 0.0 - 1.0' bgs @ 12:40 |
| | 1.0 | | | | | | | |
| | 2.0 | S-4 | NA | 2.0 | | 2.0 - 4.0' FILL: Red brown silt, gravel, brick, coal, concrete | 0 | Sample collected 140-SB-088-0204 from 2.0-3.0' bgs @ 12:45 |
| | 3.0 | | | | | | | |
| ▽ | 4.0 | S-5 | NA | 1.5 | | 4.0 - 5.5' FILL: Gray fine sand, silt, gravel; wet | 0 | Sample collected 140-SB-088-0406 from 4.0-5.0' bgs @ 12:50 |
| | 5.0 | | | | | 5.5 - 6.0' No recovery | | |
| | 6.0 | S-6 | NA | 2.0 | | 6.0 - 7.0' FILL: Light brown/gray clayey silt; soft; wet | 0 | Sample collected 140-SB-088-0608 from 6.0-7.0' bgs @ 12:55 |
| | 7.0 | | | | | 7.0 - 9.0' FILL: Light brown silt, fine sand; wet | | |
| | 8.0 | S-7 | NA | 2.0 | | | 0 | |
| | 9.0 | | | | | 9.0 - 13.0' FILL: Dark gray fine to medium sand; wet | | Sample collected 140-SB-088-0810 from 8.5-9.5' bgs @ 13:00 |
| | 10.0 | S-8 | NA | 2.0 | | | 0 | Sample collected 140-SB-088-1012 from 10.0-11.0' bgs @ 13:05 |
| | 11.0 | | | | | | | |
| | 12.0 | S-9 | NA | 2.0 | | | 0 | Sample collected 140-SB-088-1213 from 12.0-13.0' bgs @ 13:10 |
| | 13.0 | | | | | 13.0 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | | Sample collected 140-SB-088-1314 from 13.0-14.0' bgs @ 13:15 |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-089
**DATE BEGAN:** 11/1/10
**DATE FINISHED:** 11/1/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.0 | | 0.0 - 1.0' FILL: Dark brown silty sand, gravel, asphalt | 0 | Sample collected 140-SB-089-0002 from 0.0 - 1.0' bgs @ 13:20 |
| | 1.0 | | | | | 1.0 - 2.0' No recovery | | |
| | 2.0 | S-2 | NA | 1.5 | | 2.0 - 3.5' FILL: Dark brown/black silty sand, gravel, coal, brick, sandstone; wet at 3.0' bgs. | 0 | Sample collected 140-SB-089-0204 from 2.0-3.0' bgs @ 13:25 |
| ▽ | 3.0 | | | | | | | |
| | 3.5 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-3 | NA | 2.0 | | 4.0 - 7.5' FILL: Light brown fine to medium sand, lenses of silt; wet | 0 | Sample collected 140-SB-089-0406 from 4.0-6.0' bgs @ 13:30; DUP at 13:32 |
| | 5.0 | | | | | | | |
| | 6.0 | S-4 | NA | 1.5 | | | 0 | Sample collected 140-SB-089-0608 from 6.0-7.0' bgs @ 13:35 |
| | 7.0 | | | | | | | |
| | 7.5 | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-5 | NA | 1.5 | | 8.0 - 9.4' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-089-0810 from 8.0-9.0' bgs @ 13:40 |
| | 9.0 | | | | | 9.4 - 9.5' FILL: Gray clayey silt | | |
| | 9.5 | | | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | S-6 | NA | 2.0 | | 10.0 - 10.5' FILL: Gray fine to medium sand; wet | 0 | |
| | 10.5 | | | | | 10.5 - 11.0' FILL: Red brown silt; wet | | Sample collected 140-SB-089-1012 from 11.0-12.0' bgs @ 13:45 |
| | 11.0 | | | | | 11.0 - 12.5' OL: Black clayey silt | | |
| | 12.0 | S-7 | NA | 2.0 | | | 0 | Sample collected 140-SB-089-1214 from 12.0-13.0' bgs @ 13:50 |
| | 12.5 | | | | | 12.5 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-090
**DATE BEGAN:** 11/1/10
**DATE FINISHED:** 11/1/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' FILL: Asphalt, gravel | 0 | Sample collected 140-SB-090-0002 from 1.0 - 2.0' bgs @ 13:55 |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Concrete | | |
| | 2.0 | S-2 | NA | 1.5 | | 1.0 - 2.0' FILL: Dark brown silty sand, gravel | 0 | Sample collected 140-SB-090-0204 from 2.0-3.5' bgs @ 14:00 |
| ▽ | 3.0 | | | | | 2.0 - 3.5' FILL: Dark brown silty sand, gravel, coal, glass; wet at 3.0' bgs. | | |
| | 4.0 | S-3 | NA | 1.5 | | 3.5 - 4.0' No recovery | 0 | Sample collected 140-SB-090-0406 from 4.0-5.0' bgs @ 14:05 |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Dark brown silty sand, gravel, coal, glass; wet | | |
| | 6.0 | S-4 | NA | 1.5 | | 4.5 - 5.0' FILL: White COPR; wet | 0 | Sample collected 140-SB-090-0608 from 6.5-7.5' bgs @ 14:10 |
| | 7.0 | | | | | 5.0 - 5.5' FILL: Light brown silt; wet | | |
| | 8.0 | S-5 | NA | 1.0 | | 5.5 - 6.0' No recovery | 0 | Sample collected 140-SB-090-0810 from 8.0-9.0' bgs @ 14:15 |
| | 9.0 | | | | | 6.0 - 7.0' FILL: Light brown silt, fine to medium sand; wet | | |
| | 10.0 | S-6 | NA | 1.75 | | 7.0 - 7.5' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-090-1012 from 10.0-11.0' bgs @ 14:20 |
| | 11.0 | | | | | 7.5 - 8.0' No recovery | | |
| | 12.0 | S-7 | NA | 2.0 | | 8.0 - 9.0' FILL: Light gray fine to medium sand; saturated | 0 | Sample collected 140-SB-090-1214 from 12.0-13.0' bgs @ 14:25 |
| | 13.0 | | | | | 9.0 - 10.0' No recovery | | |
| | 14.0 | | | | | 10.0 - 11.5' FILL: Light gray fine to medium sand; saturated | | |
| | | | | | | 11.5 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs. | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**SITE INFO:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-091
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Bosch Electric Drill
**SAMPLING TOOL:** 2-ft Macrocore
**COMPLETION DEPTH:** 14 ft. bgs.
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.0' FILL: Asphalt, gravel | 0 | Sample collected 140-SB-091-0002 from 1.0 - 2.0' bgs @ 8:45 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Dark brown silty sand | | |
| | 2.0 | S-2 | NA | 1.0 | | 2.0 - 5.0' FILL: Dark brown silt; wet at 2.5' bgs. | 0 | Sample collected 140-SB-091-0204 from 2.0-3.0' bgs @ 8:50 |
| | 3.0 | | | | | | | |
| | 4.0 | S-3 | NA | 1.0 | | | 0 | Sample collected 140-SB-091-0406 from 4.0-5.0' bgs @ 8:55 |
| | 5.0 | | | | | 5.0 - 6.0' No recovery | | |
| | 6.0 | S-4 | NA | 1.5 | | 6.0 - 7.5' FILL: Red brown silt, lenses of fine to medium sand; wet | 0 | Sample collected 140-SB-091-0608 from 6.0-7.0' bgs @ 9:00 |
| | 7.0 | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-5 | NA | 1.5 | | 8.0 - 9.5' FILL: Light gray fine to medium sand; wet | 0 | Sample collected 140-SB-091-0810 from 8.0-9.0' bgs @ 9:05 |
| | 9.0 | | | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | S-6 | NA | 1.5 | | 10.0 - 11.5' PT: Brown peat; moist | 0 | Sample collected 140-SB-091-1012 from 10.0-11.0' bgs @ 9:10 |
| | 11.0 | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-7 | NA | 1.5 | | 12.0 - 13.5' PT: Brown peat; moist | 0 | Sample collected 140-SB-091-1214 from 12.0-13.0' bgs @ 9:15 |
| | 13.0 | | | | | 13.5 - 14.0' No recovery; end of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** 140-SB-094
**DATE BEGAN:** 3/23/2011
**DATE FINISHED:** 3/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 5ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' CONCRETE | 0 | Treatment Plant Building |
| | 1.0 | | | | | 0.3 - 0.5' VOID | | |
| | 2.0 | S-2 | NA | | | 0.5 - 4.0' FILL: Reddish brown silty fine to medium sand, some silt, trace brick and fine gravel; moderate dense, dry | 0 | |
| | 3.0 | | | | | | | |
| | 4.0 | S-3 | NA | 2.5 | | 4.0 - 5.0' FILL: Reddish brown silty fine to medium sand, some silt, trace brick and fine tomedium gravel; moderate dense, dry | 0 | |
| | 5.0 | | | | | 5.0 - 5.2' CONCRETE: Degraded | | |
| | 6.0 | S-4 | NA | | | 5.2 - 5.5' FILL: Gravel with medium to course dark brown sand; loose, wet | 0 | |
| | 7.0 | | | | | 5.5 - 6.4' FILL: Brown silty clay; dense, wet | | |
| | 8.0 | | NA | 3.5 | | 6.4 - 6.5' FILL: Greenish grey silt (possible COOPR) | 0 | |
| | 9.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 10.0 | | NA | | | 8.0 - 8.5' FILL: Fine to medium gravel with some dark brown silty sand; loose, wet | 0 | |
| | 11.0 | | | | | 8.5 - 9.0' FILL: Brown fine sand, trace silt; moderate dense, wet | | |
| | 12.0 | | NA | 0.5 | | 9.0 - 10.0' FILL: Brown clayey silt, some fine sand | 0 | No recovery, moved boring location over 2" to retrieve sample |
| | 13.0 | | | | | 10.0 - 11.3' OH: Dark brown silty clay, dense, wet, organic odor | | |
| | 14.0 | | | | | 11.3 - 11.5' SW: Brown fine to medium sand; loose, wet | | |
| | 15.0 | | | | | 11.5 - 12.0' No Recovery | | |
| | 16.0 | | | | | 12.0 - 12.5' OH: Black organic clay | | Sample collected 140-SB-094-1416 from 15.5-16.0' bgs @ 10:08 |
| | | | | | | 12.5 - 16.0' No recovery; end of boring @ 16.0' bgs | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480050143
**BORING ID:** **140-SB-094**
**DATE BEGAN:** 3/23/2011
**DATE FINISHED:** 3/23/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Dingo TX-420
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft. bgs.
**GW DEPTH:** 5ft bgs
**DRILLER:** John/Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | | | | | | | |

PREPARED BY: BS
CHECKED BY: MS

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-095
**DATE BEGAN:** 3/24/2011
**DATE FINISHED:** 3/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft. bgs.
**GW DEPTH:** 2.8 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.3' CONCRETE | 0 | |
| | | | | | | 0.3 - 1.0' ASPHALT | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Brown silty sand, trace fine gravel and brick | | |
| | | | | | | 1.5 - 3.0' FILL: Dark grey silty clay, some fine to medium gravel and brick | | |
| | 2.0 | S-2 | NA | | | | 0 | |
| | 3.0 | | | | | 3.0 - 3.3' FILL: Green silt (COPR) | | |
| | | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | | NA | 2.75 | | 4.0 - 4.5' FILL: Grey silty, some fine to medium sand; loose, wet | 0 | |
| | | | | | | 4.5 - 6.0' FILL: Dark grey clayey silt to brown in color @ 5.5' bgs; dense, wet | | Sample collected 140-SB-095-0406 from 4.5-5.0' bgs @ 13:30 |
| | 5.0 | | | | | | | |
| | 6.0 | | NA | | | 6.0 - 6.8' FILL: Brown fine to medium sand; loose, wet | 0 | |
| | 7.0 | | | | | 6.8 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-095R
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft. bgs.
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' ASPHALT | 0 | |
| | 1.0 | | | | | 1.0 - 3.8' FILL: Black silt, moist,stiff | | Barometer reading: 29.99 |
| | 2.0 | S-2 | NA | | | | 0 | |
| | 3.0 | | | | | | | Mercury reading: 0.011 Hg mg/m3 |
| | | | | | | 3.8 - 4.0' CONCRETE: degraded | | |
| | 4.0 | | | 1.0 | | 4.0 - 4.5' FILL: Gravel, black silt; wet, loose | 0 | |
| | | | | | | 4.5 - 5.0' FILL: Wood, black silt; wet, loose | | |
| | 5.0 | | | | | 5.0 - 6.0' No recovery; end of boring @ 6.0' bgs | | |
| | 6.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-096
**DATE BEGAN:** 3/24/2011
**DATE FINISHED:** 3/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft. bgs.
**GW DEPTH:** 2.7 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.5' ASPHALT | 0 | |
| | 1.0 | | | | | 1.5 - 1.8' Fill: Fine to coarse gravel, some dark grey fine silty sand; dense | | |
| | 2.0 | S-2 | NA | | | 1.8 - 3.3' FILL: Dark grey silt; dense, wet @ bottom | 0 | |
| | 3.0 | | | | | 3.3 - 3.5' FILL: Fine to medium gravel, trace fine sand; loose, wet | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | | NA | 4 | | 4.0 - 4.3' FILL: Greenish grey silty; loose, wet (COPR) | 0 | |
| | 5.0 | | | | | 4.3 - 7.0' FILL: Brown silt, some fine sand and lenses of clay, trace organics; dense wet | | Sample collected 140-SB-096-0406 from 4.5-5.0' bgs @ 13:55 |
| | 6.0 | | NA | | | | 0 | |
| | 7.0 | | | | | 7.0 - 8.0' FILL: Greyish brown fine to medium sand; loose, wet; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-096R
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 3 ft. bgs.
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.2' ASPHALT | 0 | Barometer reading: 29.97<br>Mercury reading: 0.004 Hg mg/ m3 |
| | 1.0 | | | | | 1.2 - 2.0' CONCRETE: gravel | | |
| | 2.0 | | NA | | | 2.0 - 3.0' FILL: Black silt; moist, firm; end of boring @ 3.0' bgs | 0 | |
| | 3.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-097
**DATE BEGAN:** 3/24/2011
**DATE FINISHED:** 3/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft. bgs.
**GW DEPTH:** 2.7 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' CONCRETE | 0 | |
| | | | | | | 0.5 - 1.0' ASPHALT | | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Dark grey silt, trace fine sand | | |
| | 2.0 | S-2 | NA | | | 2.0 - 4.0' No recovery | 0 | |
| | 3.0 | | | | | | | |
| | 4.0 | | NA | 3.0 | | 4.0 - 4.5' FILL: Fine to medium gravel, trace fine to medium grey sand | 0 | |
| | | | | | | 4.5 - 6.0' FILL: Brown silt, trace organics; moderate dense, wet | | Sample collected 140-SB-097-0406 from 5.0-5.5' bgs @ 14:20 |
| | 5.0 | | | | | | | |
| | 6.0 | | NA | | | 6.0 - 7.0' FILL: Greyish brown fine to medium sand; loose, wet | 0 | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-097R
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 3 ft. bgs.
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.8' ASPHALT | 0 | Barometer reading: 29.97 |
| | 1.0 | | | | | 0.8 - 1.6' CONCRETE | | |
| | | | | | | 1.6 - 2.0' FILL: Reddish brown silt, trace coal; dry, firm | | |
| | 2.0 | | NA | | | 2.0 - 3.0' FILL: Black silt; moist, firm; end of boring @ 3.0' bgs | 0 | Mercury reading: 0.022 Hg mg/m3 |
| | 3.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** **140-SB-098**
**DATE BEGAN:** 3/24/2011
**DATE FINISHED:** 3/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft. bgs.
**GW DEPTH:** 2.7 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 2.0' ASPHALT | 0 | |
| | 1.0 | | | | | | | |
| | 2.0 | S-2 | NA | | | 2.0 - 4.0' FILL: Dark grey silt; dense, wet @ bottom | 0 | |
| | 3.0 | | | | | | | |
| | 4.0 | | NA | 3.0 | | 4.0 - 4.5' FILL: Fine to medium gravel, trace fine grey sand; loose, wet | 0 | |
| | 5.0 | | | | | 4.5 - 5.5' FILL: Brown silt; moderate dense, wet | | Sample collected 140-SB-098-0406 from 4.5-5.0' bgs @ 14:30 |
| | 6.0 | | NA | | | 5.5 - 7.0' FILL: Greyish brown fine to medium sand, trace silt; loose wet | 0 | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-098R
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 3 ft. bgs.
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.5' ASPHALT | 0 | Barometer reading: 29.96 |
| | 1.0 | | | | | 1.5 - 1.6' GRAVEL: fine to medium | | |
| | | | | | | 1.6 - 2.0' FILL: Reddish brown silt, trace coal; dry, firm | | |
| | 2.0 | | NA | | | 2.0 - 3.0' FILL: Black silt; moist, firm; end of boring @ 3.0' bgs | 0 | Mercury reading: 0.013 Hg mg/m3 |
| | 3.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-099
**DATE BEGAN:** 3/24/2011
**DATE FINISHED:** 3/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft. bgs.
**GW DEPTH:** 2.7 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.5' ASPHALT | 0 | |
| | 1.0 | | | | | 1.5 - 3.0' FILL: Dark grey silt; dense, dry | | |
| | 2.0 | S-2 | NA | | | | 0 | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Fine to medium gravel, trace fine sand; loose wet; wood from -3.0 to -3.2' bgs | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | | NA | 3.0 | | 4.0 - 4.3' FILL: Fine to medium gravel, trace fine sand | 0 | |
| | | | | | | 4.3 - 4.3' FILL: Greyish brown silt (possible COPR) | | Sample collected 140-SB-099-0406 from 4.5-5.0' bgs @ 9:40 |
| | 5.0 | | | | | 4.3 - 6.0' FILL: Brown silt; loose, wet | | |
| | 6.0 | | NA | | | 6.0 - 7.0' FILL: Greyish brown fine to medium sand; loose, wet | 0 | Sample collected 140-SB-099-0608 from 6.5-7.0' bgs @ 9:42 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480090030
**BORING ID:** 140-SB-099R
**DATE BEGAN:** 9/27/2011
**DATE FINISHED:** 9/27/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 3 ft. bgs.
**GW DEPTH:** 2.5 ft bgs
**DRILLER:** G. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.5' ASPHALT: gravel | 0 | Barometer reading: 29.96 |
| | 1.0 | | | | | 1.5 - 1.8' CONCRETE: gravel | | |
| | 2.0 | | NA | | | 1.8 - 3.0' FILL: Black silt; moist, firm; greenish yellow grandular sand (COPR) in tip; end of boring @ 3.0' bgs | 0 | Mercury reading: 0.025 Hg mg/m3 |
| | 3.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell Study Area - 6 South

**LOCATION:** Site 140, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 140-SB-100
**DATE BEGAN:** 11/4/2011
**DATE FINISHED:** 11/4/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 5 | 2.0 | | 10.0 - 12.0' FILL: Brown fine to medium sand, some silt; wet | N/A | Location HSA-14 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 7 | | | | | |
| | 11.0 | | 8 | | | | | Collected 140-SB-100-1012 from 10.5 - 11.0 ft bgs @ 13:25 |
| | | | 5 | | | | | |
| | 12.0 | | 2 | 2.0 | | 12.0 - 15.0' OH: Brown silt, some clay | N/A | |
| | | | 3 | | | | | |
| | 13.0 | | 1 | | | | | |
| | | | 1 | | | | | Collected 140-SB-100-1314 from 13.5 - 14.0 ft bgs @ 13:30 |
| | 14.0 | | 1 | 2.0 | | | | |
| | | | 1 | | | | | |
| | 15.0 | | 1 | | | 15.0 - 17.0' OH: Black silt, some clay | | |
| | | | 2 | | | | | Collected 140-SB-100-1516 from 15.5 - 16.0 ft bgs @ 13:35 |
| | 16.0 | | 1 | 2.0 | | | | |
| | | | 1 | | | | | |
| | 17.0 | | NR | | | 17.0 - 18.0' PT: Dark brown peat; end of boring @ 18.0' bgs | | |
| | | | NR | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Site 140, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 140-SB-101
**DATE BEGAN:** 11/4/2011
**DATE FINISHED:** 11/4/2011
**INSPECTOR:** A. Giouzelis
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | 1 | 2.0 | | 12.0 - 13.5' OH: Brown silt, some clay; wet | N/A | Location HSA-16 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 13.0 | | 3 | | | | | Collected 140-SB-101-1213 from 12.5 - 13.0 ft bgs @ 14:45 |
| | | | 2 | | | 13.5 - 15.0' OH: Dark grey silt, some clay | | |
| | 14.0 | | 1 | 2.0 | | | N/A | |
| | | | 1 | | | | | |
| | 15.0 | | 3 | | | 15.0 - 16.0' OH: Olive silt, some clay; end of boring @ 16.0' bgs | | |
| | | | 5 | | | | | Collected 140-SB-101-1516 from 15.5 - 16.0 ft bgs @ 14:50 |
| | 16.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 140-SB-102
**DATE BEGAN:** 11/8/2011
**DATE FINISHED:** 11/8/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 2 | 1.5 | | 10.0 - 11.0' FILL: Very dark grayish brown fine to coarse sand, trace silt; loose, wet | 0 | Location HSA-15 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 11.0 | | 4 | | | 11.0 - 11.5' MH: Very dark grayish brown (10Y 3/2) clayey silt, few nodules of organic material and fine to medium sand (appears disturbed); medium stiff, medium plastic, wet | | |
| | | | 2 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | | 2 | 1.5 | | 12.0 - 13.0' OH: Olive/dark olive gray (5Y 4/3 to 3/2) silty clay, few organic material, trace fine sand; soft, plastic, wet | 0 | |
| | | | 1 | | | | | |
| | 13.0 | | 1 | | | 13.0 - 13.5' OL: Dark olive gray (5Y 3/2) silt, few clay and organic material; soft, medium plastic, wet | | Collected 140-SB-102-1314 from 13.0-13.5 ft bgs @ 09:05 |
| | | | 3 | | | 13.5 - 14.0' No recovery | | |
| | 14.0 | | 2 | 1.5 | | 14.0 - 14.2' OL: Dark olive gray (5Y 3/2) silt, few clay and organic material; medium stiff, medium plastic, wet | 0 | |
| | | | | | | 14.2 - 14.4' OH: Black (5Y 2.5/1) clayey silt; medium stiff, plastic, wet | | |
| | | | 2 | | | 14.4 - 15.5' PT: Dark brown (10YR 3/3) peat; medium stiff, crumbly, moist | | |
| | 15.0 | | 4 | | | | | No COPR observed on augers or in cuttings |
| | | | 7 | | | 15.5 - 16.0' No recovery; end of boring at 16' | | |
| | 16.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 140-SB-103
**DATE BEGAN:** 11/8/2011
**DATE FINISHED:** 11/8/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | 1 | 2.0 | | 12.0 - 12.9' MH: Very dark grayish brown (2.5Y 3/2) clayey silt, trace fine sand, possible COPR lenses at 12.55-12.6' and 12.75-12.8'; very soft, plastic, wet | 0 | Location HSA-17 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 1 | | | | | |
| | 13.0 | | 1 | | | 12.9 - 13.4' MH: Brown (10YR 4/3) clayey silt, trace fine sand; very soft, plastic, wet | | |
| | | | 1 | | | 13.4 - 14.0' OH: Very dark gray (2.5Y 3/1) clayey silt, trace organic material; peat lens from 13.9-14.0'; very soft, plastic, wet | | |
| | 14.0 | | 1 | 2.0 | | 14.0 - 15.4' OH: Very dark grayish brown (2.5Y 3/2) clayey silt, peat lens from 14.8-15.0'; medium stiff, plastic, wet | 0 | |
| | | | 2 | | | | | |
| | 15.0 | | 2 | | | | | |
| | | | 5 | | | 15.4 - 15.6' OH: Black (2.5Y 2.5/1) clayey silt; medium stiff, plastic, wet | | |
| | | | | | | 15.6 - 15.8' OH: Dark gray (2.5Y 3/1) clayey silt, trace organic material; medium stiff, plastic, wet | | |
| | 16.0 | | 2 | 1.2 | | 15.8 - 16.8' PT: Dark brown (10YR 3/3) peat; stiff, crumbly, moist | 0 | Collected 140-SB-103-1617 from 16.0-16.5 ft bgs @ 10:45 |
| | | | 4 | | | | | |
| | 17.0 | | 10 | | | 16.8 - 17.2' SP: Brown (7.5YR 4/2) fine sand, trace silt; medium dense, wet | | |
| | | | 23 | | | 17.2 - 18.0' No recovery; end of boring at 18' | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 140-SB-104
**DATE BEGAN:** 11/11/2011
**DATE FINISHED:** 11/11/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | S-1 | 1 | 2.0 |  | 10.0 - 10.1' MH: Brown (10YR 4/3) silt, some clay, trace fine sand; wet, very soft, plastic | N/A | Location HSA-12 on sampling table. Augered to 10 ft bgs before sampling. |
| | | | 1 | | | 10.1 - 11.0' OH: Very dark grayish brown/black (2/5 YR 3/2 to 2.5/1) silt, some clay and organic material, trace fine sand; wet, very soft, plastic | | Sample collected 140-SB-104-1011 from 10.5 - 11.0' bgs @ 10:10 |
| | -11.0 | | 1 | | | | | |
| | | | 2 | | | 11.0 - 14.0' PT: Dark brown (10 YR 3/3) peat; moist, soft, crumbly; end of boring @ 14.0' bgs | | Sample collected 140-SB-104-1112 from 11.0 - 11.5' bgs @ 10:15 |
| | -12.0 | S-2 | 1 | 2.0 | | | N/A | |
| | | | 2 | | | | | Sample collected 140-SB-104-1213 from 12.0 - 12.5' bgs @ 10:30 |
| | -13.0 | | 2 | | | | | |
| | | | 4 | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: TG

# Honeywell SA-6 South

**LOCATION:** Site 140 ABF Trucking
**PROJECT NO:** 3480100027
**BORING ID:** 140-SB-105
**DATE BEGAN:** 1/16/2012
**DATE FINISHED:** 1/16/2012
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push/ Soft Dig
**DRILL EQUIP:** Geoprobe 5400DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft. bgs.
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake/Brian
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | NA (soft dig) | | 0.0 - 0.4' ASPHALT | NA | |
| | | | | | | 0.4 - 4.0' FILL: Dark grey silt, some fine sand, ash, grey pumice like material (clinker); wet @ 4.0' bgs | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Greyish brown fine to medium sand, lenses of brown silt, trace fine gravel; wet, loose | NA | Collected 140-SB-105-0608 from 7.5 - 8.0' bgs @ 13:10 |
| | 8.0 | S-3 | | 2.0 | | 8.0 - 10.0' FILL: Greyish brown fine to medium sand, trace nodules of reddish brown clay; end of boring 10.0' bgs | NA | Collected 140-SB-105-0810 from 9.5 - 10.0' bgs @ 13:15 |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: MM

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 140-SB-106
**DATE BEGAN:** 1/18/2012
**DATE FINISHED:** 1/18/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57 freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -8.0 | S-1 | 2 | 2.0 | | 8.0 - 14.0' FILL: Gray fine to medium sand, trace shells and silt; loose, wet; end of boring @ 14.0' bgs | N/A | Location HSA-13 on sampling table. Augered to 8 ft bgs before sampling. |
| | | | 2 | | | | | |
| | -9.0 | | 4 | | | | | |
| | | | 5 | | | | | |
| | -10.0 | S-2 | 4 | 2.0 | | | N/A | |
| | | | 5 | | | | | |
| | -11.0 | | 7 | | | | | |
| | | | 8 | | | | | Sample collected 140-SB-106-1112 from 11.5 - 12.0' bgs @ 11:00 |
| | -12.0 | S-3 | 5 | 2.0 | | | N/A | |
| | | | 7 | | | | | Suspect heaving sand for 12 - 14' spoon |
| | -13.0 | | 7 | | | | | |
| | | | 8 | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 140-SB-107
**DATE BEGAN:** 1/18/2012
**DATE FINISHED:** 1/18/2012
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Mobile B-57, freefall winch
**BIT TYPE/SIZE:** 4.25-in. diam. auger
**CASING:** N/A
**HAMMER:** 140 lbs/30 inches
**CORE TYPE/SIZE:** N/A
**ROCK DEPTH:** Not encountered
**PERMIT NO:** N/A
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | -10.0 | S-1 | 4 | 2.0 | | 10.0 - 12.8' FILL: Gray fine to medium sand, trace silt and shells; loose, wet | N/A | Drilled ~5 ft east of 140-SB-106 to verify peat contact |
| | | | 6 | | | | | |
| | -11.0 | | 3 | | | | | |
| | | | 3 | | | | | |
| | -12.0 | S-2 | 4 | 1.5 | | | N/A | |
| | | | 3 | | | | | |
| | -13.0 | | 2 | | | 12.8 - 13.5' PT: Very dark brown (7.5 YR 2.5/3) peat; medium stiff, moist; end of boring @ 14.0' bgs | | |
| | | | 2 | | | | | |
| | -14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell

**LOCATION:** Site 140
**PROJECT NO:** 3480130377
**BORING ID:** 140-SB-603-X
**DATE BEGAN:** 5/13/14
**DATE FINISHED:** 5/13/14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct push
**DRILL EQUIP:** Geoprobe 220
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 8' bgs
**GW DEPTH:**
**DRILLER:** Gordon Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | N/A | 3.0 | | 0.0 - 0.5' GRAVEL: GRAVEL | 0.0 | |
| | | | | | | 0.5 - 1.0' FILL: Brown fine to coarse SAND, fine to medium gravel; loose, moist | 0.0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Reddish brown fine SAND, fine to medium gravel | 0.0 | Sample 140-SB-603-X1 (1.1'-3.5') @ 9:40 |
| | | | | | | 1.5 - 3.0' FILL: Grayish black fine SAND, fine to medium gravel, trace silt, COPR | 0.0 | |
| | 2.0 | | | | | | 0.0 | |
| | | | | | | | 0.0 | |
| | 3.0 | | | | | 3.0 - 4.0' No Recovery | | |
| | 4.0 | | N/A | 3.0 | | 4.0 - 4.3' FILL: Grayish black fine SAND, fine to medium gravel, trace silt, COPR | 0.0 | |
| | | | | | | 4.3 - 6.5' FILL: Black fine SAND, some silt; medium dense, moist | 0.0 | |
| | 5.0 | | | | | | 0.0 | Sample 140-SB-603-X2 (5.0'-7.1') @ 9:55; Encores taken |
| | | | | | | | 0.0 | |
| | 6.0 | | | | | | 0.0 | |
| | | | | | | 6.5 - 7.0' FILL: Black fine to coarse SAND, fine to medium gravel, metal, newspaper, plastic; loose, wet | 0.0 | |
| | 7.0 | | | | | 7.0 - 8.0' No Recovery; End of boring at 8' | | |
| | 8.0 | | | | | | | |

PREPARED BY: GB
CHECKED BY: MS

# Honeywell Jersey City

**LOCATION:** SA-6 South Meter Building (East)
**PROJECT NO:** 3480130377
**BORING ID:** 140-SB-606
**DATE BEGAN:** 3-28-16
**DATE FINISHED:** 3-28-16
**INSPECTOR:** Ari Eslaminejad
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 8' bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:** 684622.7
**EAST:** 602395.5

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' ASPHALT: Asphalt/Gravel | NM | Ground surface elevation +8.50 |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Dark brown SANDY SILT, some fine to coarse gravel; moist | | |
| | 2.0 | | | | | 2.0 - 3.0' SM: Yellowish red/light brown SANDY SILT; moist | | |
| | 3.0 | | | | | 3.0 - 5.0' SW: Brown fine SAND, few clay; medium dense | | |
| | 4.0 | S-2 | | 3.0 | | | | |
| | 5.0 | | | | | 5.0 - 7.0' SW: Brown fine to medium SAND; medium dense, wet | | |
| | 6.0 | | | | | | | Sample collected from 2.7-3.1' bgs at 8:55 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery. End of boring at 8.0' bgs. | | |
| | 8.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South Meter Building (West)
**PROJECT NO:** 3480130377
**BORING ID:** 140-SB-607
**DATE BEGAN:** 3-28-16
**DATE FINISHED:** 3-28-16
**INSPECTOR:** Ari Eslaminejad
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 8' bgs
**GW DEPTH:** NE
**DRILLER:** Gordon Blewett
**NORTH:** 684622.7
**EAST:** 602395.5

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' ASPHALT: Asphalt/Gravel; loose | NM | Ground surface elevation +8.45 |
| | 1.0 | | | | | 1.0 - 2.5' FILL: Brown SILT, some fine to coarse gravel; moist | | |
| | 2.0 | | | | | | | |
| | 2.5 | | | | | 2.5 - 3.0' SW: Light brown fine SAND; moist | | |
| | 3.0 | | | | | 3.0 - 3.5' SM: Brown SANDY SILT; moist | | |
| | 3.5 | S-2 | | 3.0 | | 3.5 - 5.0' SW: Dark brown fine to medium SAND; medium dense, moist | | |
| | 4.0 | | | | | | | |
| | 5.0 | | | | | 5.0 - 7.0' SW: Light brown fine to medium SAND; dense, moist | | Sample collected from 6.1-6.7' bgs at 8:55 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery. End of boring at 8.0' bgs. | | |
| | 8.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** 163-MW-03
**DATE BEGAN:** 6-1-16
**DATE FINISHED:** 6-1-16
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 18' bgs
**GW DEPTH:** 4' bgs
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 11 | 1.0 | | 14.0 - 15.0' SW: Reddish brown fine to coarse SAND, few fine to coarse gravel; loose, wet | NM | Starting elevation 7.5' Augered to 14.0' bgs |
| | | | 18 | | | | | |
| | 15.0 | | 17 | | | 15.0 - 16.0' No recovery | | |
| | | | 16 | | | | | |
| | 16.0 | SS2 | 8 | 2.0 | | 16.0 - 17.5' SM: Reddish brown/gray fine to medium SAND and SILT; medium dense, wet | | |
| | | | 17 | | | | | |
| | 17.0 | | 16 | | | | | |
| | | | 12 | | | 17.5 - 17.8' ML: Dark gray SILT | | |
| | | | | | | 17.8 - 17.9' OL: Dark gray SILT with organics | | |
| | 18.0 | | | | | 17.9 - 18.0' PEAT: Dark brown PEAT. End of boring at 18.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-001
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' CONCRETE | 0 | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Black silty sand, clinker, trace coal | | |
| | 2.0 | | | | | 1.5 - 2.0' FILL: Red brown silt, gravel | | Sample collected 163-SB-001-0002 from 1.5-2.0' bgs @9:45 |
| | 3.0 | | | | | 2.0 - 3.5' FILL: Red brown silt, lenses of fine to coarse sand; wet at tip | | Sample collected 163-SB-001-0204 from 3.0-3.5' bgs @9:50 |
| | 4.0 | S-2 | NA | 3.5 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Gray/red brown silt, gravel; wet | | Sample collected 163-SB-001-0406 from 4.5-5.0' bgs @9:55 |
| | 6.0 | | | | | 5.0 - 7.5' FILL: Light brown/light gray fine to medium sand; wet | | |
| | 7.0 | | | | | | | Sample collected 163-SB-001-0608 from 6.5-7.0' bgs @10:00: DUP at 10:02 |
| | 8.0 | S-3 | NA | 3.0 | | 7.5 - 8.0' : No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 9.3' FILL: Light brown fine to medium sand; wet | | Sample collected 163-SB-001-0810 from 8.0-8.5' bgs @10:05 |
| | 10.0 | | | | | 9.3 - 10.0' FILL: Red brown silt; wet | | |
| | 11.0 | | | | | 10.0 - 11.0' CL: Light brown clayey silt, organics; very moist | | Sample collected 163-SB-001-1012 from 10.0-10.5' bgs @10:10 |
| | 12.0 | S-4 | NA | 2.0 | | 11.0 - 12.0' No recovery | 0 | |
| | 13.0 | | | | | 12.0 - 12.5' CL: Light brown clayey silt, trace shells; wet | | |
| | 14.0 | | | | | 12.5 - 13.5' CL: Black clayey silt, organics; very moist | | Sample collected 163-SB-001-1214 from 13.0-13.5' bgs @10:15 |
| | | | | | | 13.5 - 14.0' PT: Brown peat; moist; end of boring at 14.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South


**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-002
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' TOPSOIL: Light brown topsoil | 0 | |
| | 1.0 | | | | | 0.5 - 1.0' FILL: Crushed concrete | | Sample collected 163-SB-002-0002 from 1.0-1.5' bgs @9:00 |
| | 2.0 | | | | | 1.0 - 1.5' FILL: Black silty sand, coal, gravel | | |
| | 3.0 | | | | | 1.5 - 3.5' FILL: Light brown silt, lenses of fine to medium sand | | Sample collected 163-SB-002-0204 from 2.5-3.0' bgs @9:05 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Light gray/light red brown fine to medium sand, lenses of red brown silt, clayey silt throughout; wet | | Sample collected 163-SB-002-0406 from 4.5-5.0' bgs @9:10 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' : No recovery | | Sample collected 163-SB-002-0608 from 6.5-7.0' bgs @9:15 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.0' FILL: Light gray/light red brown fine to medium sand, lenses of red brown silt, clayey silt throughout; wet | 0 | |
| | 9.0 | | | | | 9.0 - 10.5' FILL: Red brown clayey silt; soft, wet | | Sample collected 163-SB-002-0810 from 9.0-9.5' bgs @9:20 |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.0' FILL: Light gray fine to medium sand; wet | | Sample collected 163-SB-002-1012 from 10.5-11.0' bgs @9:25 |
| | 12.0 | S-4 | NA | 2.5 | | 11.0 - 12.0' No recovery | 0 | Sample collected 163-SB-002-1214 from 12.0-12.5' bgs @9:30 |
| | 13.0 | | | | | 12.0 - 14.5' FILL: Light brown fine to medium sand, light brown/red brown silt; wet | | |
| | 14.0 | | | | | | | Sample collected 163-SB-002-1416 from 14.0-14.5' bgs @9:35 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.5 | | 16.0 - 17.5' FILL: Light brown clayey silt, trace organics and shells; very moist | 0 | |
| | 17.0 | | | | | | | Sample collected 163-SB-002-1618 from 17.0-17.5' bgs @9:40 |
| | 18.0 | | | | | 17.5 - 18.5' PT: Brown peat; moist | | |
| | 19.0 | | | | | 18.5 - 20.0' No recovery; end of boring at 20.0' bgs | | |
| | 20.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-003**
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**




| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' FILL: Black silty sand, coal, clinker | 0 | |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Red brown silt; dense | | |
| | 2.0 | | | | | 1.3 - 2.0' FILL: Crushed concrete, silt, yellow green potential COPR | | Sample collected 163-SB-003-0002 from 1.5-2.0' bgs @10:20 |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Black silty sand, coal, clinker | | |
| | 4.0 | S-2 | NA | 4.0 | | 3.0 - 3.5' FILL: Light brown fine to medium sand; wet at tip | 0 | Sample collected 163-SB-003-0204 from 3.0-3.5' bgs @10:25 |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | 5.0 | | | | | 4.0 - 6.0' FILL: Light brown fine to medium sand; wet | | Sample collected 163-SB-003-0406 from 4.5-5.0' bgs @10:30 |
| | 6.0 | | | | | 6.0 - 8.0' FILL: Light brown fine to medium sand, lenses of red brown silt, shells | | Sample collected 163-SB-003-0608 from 6.5-7.0' bgs @10:35 |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 10.5' FILL: Light brown clayey silt | 0 | Sample collected 163-SB-003-0810 from 8.5-9.0' bgs @10:40 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 11.5' OL: Olive/black clayey silt | | Sample collected 163-SB-003-1012 from 11.0-11.5' bgs @10:45 |
| | | | | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 12.5' OL: Olive/black clayey silt | 0 | |
| | 13.0 | | | | | 12.5 - 14.0' OL: Light brown clayey silt, organics | | Sample collected 163-SB-003-1214 from 13.0-13.5' bgs @10:50 |
| | 14.0 | | | | | 14.0 - 15.0' PT: Brown peat; moist | | Sample collected 163-SB-003-1416 from 14.5-15.0' bgs @10:55 |
| | 15.0 | | | | | 15.0 - 16.0' : No recovery; end of boring at 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-004
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' FILL: Concrete | 0 | |
| | 1.0 | | | | | 0.8 - 1.0' FILL: Black silty sand, gravel | | |
| | 2.0 | | | | | 1.0 - 1.5' FILL: Fine to coarse gravel | | Sample collected 163-SB-004-0002 from 1.5-2.0' bgs @12:00 |
| | 3.0 | | | | | 1.5 - 2.0' FILL: Black silty sand, coal, brick | | |
| | 4.0 | S-2 | NA | 3.5 | | 2.0 - 3.5' FILL: Light brown fine to medium sand | | Sample collected 163-SB-004-0204 from 3.0-3.5' bgs @12:05 |
| | 5.0 | | | | | 3.5 - 4.0' : No recovery | 0 | Sample collected 163-SB-004-0406 from 4.0-4.5' bgs @12:10 |
| | 6.0 | | | | | 4.0 - 5.5' FILL: Light brown fine to medium sand, gray clayey silt; wet | | |
| | 7.0 | | | | | 5.5 - 6.5' FILL: Red brown/light brown silt, lenses of fine to medium sand; wet | | |
| | 8.0 | S-3 | NA | 2.5 | | 6.5 - 7.5' FILL: Light brown fine to medium sand; wet | | Sample collected 163-SB-004-0608 from 7.0-7.5' bgs @12:15 |
| | 9.0 | | | | | 7.5 - 8.0' No recovery | 0 | |
| | 10.0 | | | | | 8.0 - 10.5' FILL: Light brown/red brown fine sand, silt; wet | | Sample collected 163-SB-004-0810 from 8.5-9.0' bgs @12:20; DUP at 12:22 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | Sample collected 163-SB-004-1012 from 10.0-10.5' bgs @12:25 |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 13.0' FILL: Light brown/red brown fine sand, silt; wet | 0 | |
| | 13.0 | | | | | 13.0 - 14.3' OL: Black clayey silt, trace shells; wet | | Sample collected 163-SB-004-1214 from 13.0-13.5' bgs @12:30 |
| | 14.0 | | | | | 14.3 - 15.0' PT: Brown peat; moist | | Sample collected 163-SB-004-1416 from 14.0-14.5' bgs @12:35 |
| | 15.0 | | | | | 15.0 - 16.0' : No recovery; end of boring at 16.0' bgs | | |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-005
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' FILL: Concrete | 0 | |
| | | | | | | 0.5 - 2.5' FILL: Dark brown silty sand, fine to coarse gravel, coal | | Sample collected 163-SB-005-0002 from 1.0-1.5' bgs @12:40 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Light brown fine to medium sand; wet at tip | | Sample collected 163-SB-005-0204 from 3.0-3.5' bgs @12:45 |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 6.0' FILL: Light brown fine to medium sand; saturated | 0 | Sample collected 163-SB-005-0406 from 4.5-5.0' bgs @12:50 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Light brown fine to medium sand, red/brown silt; shells from 6.5-7.5'; wet | | |
| | 7.0 | | | | | | | Sample collected 163-SB-005-0608 from 7.0-7.5' bgs @12:55 |
| | | | | | | 7.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown/light gray fine to medium sand; saturated | 0 | Sample collected 163-SB-005-0810 from 8.0-8.5' bgs @13:00 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-005-1012 from 10.0-10.5' bgs @13:05 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 13.3' FILL: Light brown/light gray fine to medium sand; saturated | 0 | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-005**
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | | | | | 13.3 - 14.0' FILL: Light brown clayey silt; soft; very moist | | Sample collected 163-SB-005-1214 from 13.0-13.5' bgs @13:10 |
| | 14.0 | | | | | 14.0 - 14.5' OL: Black clayey silt; very moist | | Sample collected 163-SB-005-1416 from 14.0-14.5' bgs @13:15 |
| | 15.0 | | | | | 14.5 - 15.0' PT: Brown peat; moist | | |
| | 16.0 | | | | | 15.0 - 16.0' : No recovery; end of boring at 16.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-006**
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 3.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 2.5' FILL: Dark brown silty sand, gravel, coal, wood | 0 | |
| | 1.0 | | | | | | | Sample collected 163-SB-006-0002 from 1.0-1.5' bgs @13:20 |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Red brown silt, lenses of fine to medium sand; dense | | Sample collected 163-SB-006-0204 from 3.0-3.5' bgs @13:25 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt; wet | | Sample collected 163-SB-006-0406 from 4.0-4.5' bgs @13:30 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-006-0608 from 6.5-7.0' bgs @13:35 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 9.8' FILL: Light brown fine to medium sand, silt; wet | 0 | |
| | 9.0 | | | | | | | Sample collected 163-SB-006-0810 from 8.5-9.0' bgs @13:40 |
| | 10.0 | | | | | 9.8 - 11.0' FILL: Light brown silt; wet | | |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | Sample collected 163-SB-006-1012 from 10.5-11.0' bgs @13:45 |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 13.0' FILL: Light brown clayey silt; soft; wet | 0 | |
| | 13.0 | | | | | 13.0 - 14.0' FILL: Light brown silt; wet | | Sample collected 163-SB-006-1214 from 13.0-13.5' bgs @13:50 |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Black clayey silt; wet | | |
| | 15.0 | | | | | 14.5 - 15.0' PT: Brown peat; moist | | Sample collected 163-SB-006-1416 from 14.5-15.0' bgs @13:55 |
| | 16.0 | | | | | 15.0 - 16.0' : No recovery; end of boring at 16.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-007
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE | 0 | |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Dark brown/black silty sand, brick, coal, gravel | | Sample collected 163-SB-007-0002 from 1.0-1.5' bgs @14:00 |
| | 2.0 | | | | | 2.0 - 2.3' FILL: Crushed concrete | | |
| | 3.0 | | | | | 2.3 - 3.3' FILL: Black silty sand, coal, glass, trace clinker | | Sample collected 163-SB-007-0204 from 2.5-3.0' bgs @14:05 |
| | 4.0 | S-2 | NA | 3.5 | | 3.3 - 3.5' FILL: Light brown fine to medium sand | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' : No recovery | | Sample collected 163-SB-007-0406 from 5.0-5.5' bgs @14:10 |
| | 6.0 | | | | | 4.0 - 6.3' FILL: Light brown fine to medium sand; wet | | |
| | 7.0 | | | | | 6.3 - 7.5' FILL: Light gray fine to medium sand, clayey silt from 7.0-7.5'; wet | | Sample collected 163-SB-007-0608 from 7.0-7.5' bgs @14:15 |
| | 8.0 | S-3 | NA | 2.5 | | 7.5 - 8.0' No recovery | 0 | |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Light brown fine to medium sand, silt; wet | | Sample collected 163-SB-007-0810 from 8.5-9.0' bgs @14:20 |
| | 10.0 | | | | | | | Sample collected 163-SB-007-1012 from 10.0-10.5' bgs @14:25 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.5 | | 12.0 - 14.0' FILL: Light brown clayey silt; soft; wet | 0 | |
| | 13.0 | | | | | | | Sample collected 163-SB-007-1214 from 12.5-13.0' bgs @14:30 |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Olive clayey silt; very moist | | |
| | 15.0 | | | | | 14.5 - 15.3' OL: Black clayey silt; very moist | | Sample collected 163-SB-007-1416 from 14.5-15.0' bgs @14:35 |
| | | | | | | 15.3 - 15.5' PT: Brown peat; moist | | |
| | 16.0 | | | | | 15.5 - 16.0' : No recovery; end of boring at 16.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-008

**DATE BEGAN:** 11/3/10 | **DATE FINISHED:** 11/3/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 20 ft bgs | **GW DEPTH:** 4.0 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.3' TOPSOIL: Light brown topsoil | 0 | |
| | 1.0 | | | | | 0.3 - 2.0' FILL: Dark brown silty sand, wood, gravel | | Sample collected 163-SB-008-0002 from 1.0-1.5' bgs @8:20 |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Light brown fine to medium sand | | Sample collected 163-SB-008-0204 from 2.5-3.0' bgs @8:25 |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt lenses from 6.0-7.0'; wet | 0 | Sample collected 163-SB-008-0406 from 4.0-4.5' bgs @8:30 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-008-0608 from 6.5-7.0' bgs @8:35<br>DUP @8:37 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 163-SB-008-0810 from 8.0-8.5' bgs @8:40 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-008-1012 from 10.0-10.5' bgs @8:45 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 12.5' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 163-SB-008-1214 from 12.0-12.5' bgs @8:50 |
| | 13.0 | | | | | 12.5 - 14.5' FILL: Light brown silt; soft, wet | | |
| | 14.0 | | | | | | | Sample collected 163-SB-008-1416 from 14.0-14.5' bgs @8:55 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-008
**DATE BEGAN:** 11/3/10
**DATE FINISHED:** 11/3/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 18.5' FILL: Light brown silt; very soft, saturated | 0 | Sample collected 163-SB-008-1618 from 16.0-16.5' bgs @9:00 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 18.5 - 19.0' PT: Brown peat; moist | | Sample collected 163-SB-008-1820 from 18.5-19.0' bgs @9:05 |
| | 20.0 | | | | | 19.0 - 20.0' : No recovery; end of boring at 20.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-009

**DATE BEGAN:** 11/3/10 | **DATE FINISHED:** 11/3/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 20 ft bgs | **GW DEPTH:** 4.0 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 2.0' FILL: Dark brown silty sand, coal, gravel, shells | 0 | Sample collected 163-SB-009-0002 from 1.0-1.5' bgs @9:10 |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Light brown fine to medium sand | | Sample collected 163-SB-009-0204 from 3.0-3.5' bgs @9:15 |
| | 3.0 | | | | | 3.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, silt, lenses throughout; wet | 0 | Sample collected 163-SB-009-0406 from 4.5-5.0' bgs @9:20 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 163-SB-009-0608 from 6.5-7.0' bgs @9:25 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 9.5' FILL: Light brown silt; wet | 0 | Sample collected 163-SB-009-0810 from 8.0-8.5' bgs @9:30 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.5' FILL: Red brown/light brown silt | | Sample collected 163-SB-009-1012 from 10.0-10.5' bgs @9:35 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 12.8' FILL: Light brown silt, trace fine to medium sand; wet | 0 | |
| | 13.0 | | | | | 12.8 - 13.5' FILL: Light brown fine to medium sand; wet | | Sample collected 163-SB-009-1214 from 12.5-13.0' bgs @9:40 |
| | 14.0 | | | | | 13.5 - 14.5' FILL: Light brown silt; soft, wet | | |
| | 15.0 | | | | | 14.5 - 15.0' FILL: Light brown silt; wet | | Sample collected 163-SB-009-1416 from 14.5-15.0' bgs @9:45 |
| | | | | | | 15.0 - 16.0' : No recovery | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-009**
**DATE BEGAN:** 11/3/10
**DATE FINISHED:** 11/3/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 16.5' FILL: Light brown silt; wet | 0 | Sample collected 163-SB-009-1618 from 16.5-17.0' bgs @9:50<br><br>Sample collected 163-SB-009-1820 from 18.0-18.5' bgs @9:55 |
| | 17.0 | | | | | 16.5 - 18.0' FILL: Light brown clayey silt; soft | | |
| | 18.0 | | | | | 18.0 - 18.3' FILL: Light brown clayey silt, trace organics | | |
| | 19.0 | | | | | 18.3 - 19.0' PT: Brown peat; moist | | |
| | 20.0 | | | | | 19.0 - 20.0' : No recovery; end of boring at 20.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-010
**DATE BEGAN:** 11/3/10
**DATE FINISHED:** 11/3/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 19 ft bgs
**GW DEPTH:** 4.25 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' CONCRETE | 0 | |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Fine to coarse gravel | | Sample collected 163-SB-010-0002 from 1.5-2.0' bgs @10:00 |
| | 2.0 | | | | | 0.8 - 1.5' FILL: Conrete, gravel | | |
| | 3.0 | | | | | 1.5 - 2.0' FILL: Orange/red brown silt | | Sample collected 163-SB-010-0204 from 3.0-3.5' bgs @10:05 |
| | 4.0 | S-2 | NA | 3.5 | | 2.0 - 3.5' FILL: Black silty sand, coal, clinker, glass | 0 | |
| | 5.0 | | | | | 3.5 - 4.0' : No recovery | | Sample collected 163-SB-010-0406 from 4.5-5.0' bgs @10:10 |
| | 6.0 | | | | | 4.0 - 4.3' FILL: Black silty sand, coal, clinker, glass | | |
| | 7.0 | | | | | 4.3 - 5.8' FILL: Light brown fine to medium sand, silt lenses; wet | | Sample collected 163-SB-010-0608 from 7.0-7.5' bgs @10:15 |
| | 8.0 | S-3 | NA | 2.5 | | 5.8 - 7.5' FILL: Brown fine to medium sand, silt; wet | 0 | |
| | 9.0 | | | | | 7.5 - 8.0' No recovery | | Sample collected 163-SB-010-0810 from 8.5-9.0' bgs @10:20 |
| | 10.0 | | | | | 8.0 - 10.5' FILL: Light brown silt, lenses of fine to coarse sand, shells; wet | | Sample collected 163-SB-010-1012 from 10.0-10.5' bgs @10:25 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 14.5' FILL: Light brown silt, fine sand | 0 | |
| | 13.0 | | | | | | | Sample collected 163-SB-010-1214 from 12.5-13.0' bgs @10:30 |
| | 14.0 | | | | | 14.5 - 15.0' OL: Black clayey silt | | |
| | 15.0 | | | | | 15.0 - 16.0' : No recovery | | Sample collected 163-SB-010-1416 from 14.5-15.0' bgs @10:35 |
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 17.0' OL: Black clayey silt | 0 | |
| | 17.0 | | | | | 17.0 - 19.0' PT: Brown peat; moist; end of boring at 19.0' bgs | | |
| | 18.0 | | | | | | | Sample collected 163-SB-010-1618 from 17.5-18.0' bgs @10:40 |
| | 19.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-011

**DATE BEGAN:** 11/3/10 | **DATE FINISHED:** 11/3/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 18 ft bgs | **GW DEPTH:** 3.5 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.8' CONCRETE | 0 | Sample collected 163-SB-011-0002 from 1.0-1.5' bgs @10:45 |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Dark brown silty sand, gravel, crushed concrete | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Orange/red brown silt, yellow nodules, potential COPR; moist | | Sample collected 163-SB-011-0204 from 2.0-2.5' bgs @10:50 |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Crushed concrete | | |
| | 4.0 | S-2 | NA | 2.5 | | 3.0 - 3.5' FILL: Black silty sand, coal, gravel, clinker; wet at tip | 0 | Sample collected 163-SB-011-0406 from 4.0-4.5' bgs @10:55 |
| | 5.0 | | | | | 3.5 - 4.0' : No recovery | | |
| | 6.0 | | | | | 4.0 - 6.5' FILL: Light brown silt, fine to medium sand, shells | | Sample collected 163-SB-011-0608 from 6.0-6.5' bgs @11:00 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown silt, fine to medium sand, shells | 0 | Sample collected 163-SB-011-0810 from 8.0-8.5' bgs @11:05; DUP at 11:07 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-011-1012 from 10.0-10.5' bgs @11:10 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' FILL: Light brown fine to medium, trace silt | 0 | Sample collected 163-SB-011-1214 from 12.0-12.5' bgs @11:15 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 163-SB-011-1416 from 14.0-14.5' bgs @11:20 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 17.0' OL: Black clayey silt | 0 | Sample collected 163-SB-011-1618 from 16.0-16.5' bgs @11:25 |
| | 17.0 | | | | | 17.0 - 18.0' PT: Brown peat; moist; end of boring at 18.0' bgs | | |
| | 18.0 | | | | | | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-012
**DATE BEGAN:** 11/3/10
**DATE FINISHED:** 11/3/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 3.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.5' CONCRETE | 0 | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Brown silty sand, crushed concrete | | Sample collected 163-SB-012-0002 from 1.5-2.0' bgs @11:30 |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Crushed concrete | | |
| ▽ | 3.0 | | | | | 3.0 - 3.5' FILL: Light brown silt; dense, wet | | Sample collected 163-SB-012-0204 from 3.0-3.5' bgs @11:35 |
| | 4.0 | S-2 | NA | 2.5 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Light brown silt; dense, wet | | Sample collected 163-SB-012-0406 from 4.0-4.5' bgs @11:40 |
| | 6.0 | | | | | 4.5 - 6.5' FILL: Gray fine to medium sand; wet | | Sample collected 163-SB-012-0608 from 6.0-6.5' bgs @11:45 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Gray fine to medium sand, lenses of silt, shells; wet | 0 | Sample collected 163-SB-012-0810 from 8.0-8.5' bgs @11:50 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-012-1012 from 10.0-10.5' bgs @11:55 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.0' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 163-SB-012-1214 from 12.0-12.5' bgs @12:00 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Red brown silt; wet | | Sample collected 163-SB-012-1416 from 14.0-14.5' bgs @12:05 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 16.5' OL: Black clayey silt; very moist | 0 | Sample collected 163-SB-012-1618 from 16.0-16.5' bgs @12:10 |
| | 17.0 | | | | | 16.5 - 18.0' PT: Brown peat; moist; end of boring at 18.0' bgs | | |
| | 18.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-013**
**DATE BEGAN:** 11/3/10
**DATE FINISHED:** 11/3/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' FILL: Gravel, crushed concrete | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Orange silt, very dark brown nodules | | Sample collected 163-SB-013-0002 from 1.0-1.5' bgs @13:25 |
| | 2.0 | | | | | 1.5 - 1.8' FILL: Gravel, concrete | | |
| | 3.0 | | | | | 1.8 - 3.0' FILL: Black silty sand, coal, gravel, clinker | | Sample collected 163-SB-013-0204 from 2.5-3.0' bgs @13:30 |
| ▽ | 4.0 | S-2 | NA | 3.0 | | 3.0 - 4.0' : No recovery | 0 | Sample collected 163-SB-013-0406 from 4.0-4.5' bgs @13:35 |
| | 5.0 | | | | | 4.0 - 4.8' FILL: Light brown clayey silt, shells, gravel; dense, wet | | |
| | 6.0 | | | | | 4.8 - 7.0' FILL: Light brown clayey silt, lenses of red brown silt, fine to medium sand; wet | | Sample collected 163-SB-013-0608 from 6.5-7.0' bgs @13:40 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.0' FILL: Wood | 0 | Cannot sample from 8.0-10.0' |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.0' FILL: Light brown clayey silt; soft; wet | | Sample collected 163-SB-013-1012 from 10.5-11.0' bgs @13:45 |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.5 | | 12.0 - 14.5' FILL: Light brown clayey silt; soft; wet | 0 | Sample collected 163-SB-013-1214 from 12.5-13.0' bgs @13:50 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 14.5 - 15.0' FILL: Light brown silt; wet | | Sample collected 163-SB-013-1416 from 15.0-15.5' bgs @13:55 |
| | 16.0 | S-5 | NA | 2.0 | | 15.0 - 15.5' OL: Black clayey silt, trace organics; very moist | 0 | |
| | 17.0 | | | | | 15.5 - 16.0' : No recovery | | Sample collected 163-SB-013-1618 from 16.0-16.5' bgs @14:00 |
| | 18.0 | | | | | 16.0 - 18.0' PT: Brown peat; moist; end of boring at 18.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-014
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.5' FILL: Gravel, crushed concrete | 0 | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Orange silt, very dark brown nodules | | Sample collected 163-SB-014-0002 from 1.5-2.0' bgs @12:40 |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Black silty sand, coal, fine gravel, clinker | | |
| | 3.0 | | | | | 3.5 - 4.0' : No recovery | | Sample collected 163-SB-014-0204 from 3.0-3.5' bgs @12:45 |
| ▽ | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.5' FILL: Black silty sand, coal, fine gravel, clinker; wet | 0 | |
| | 5.0 | | | | | 4.5 - 7.0' FILL: Light brown fine to medium sand, lenses of silt, clayey silt; wet | | Sample collected 163-SB-014-0406 from 4.5-5.0' bgs @12:50 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-014-0608 from 6.5-7.0' bgs @12:55 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, lenses of silt, clayey silt, shells; wet | 0 | |
| | 9.0 | | | | | | | Sample collected 163-SB-014-0810 from 8.5-9.0' bgs @13:00 |
| | 10.0 | | | | | | | Sample collected 163-SB-014-1012 from 10.0-10.5' bgs @13:05 |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 12.5' FILL: Light brown fine to medium sand, lenses of silt, clayey silt, shells; wet | 0 | |
| | 13.0 | | | | | 12.5 - 13.0' FILL: Light brown/red brown silt; wet | | Sample collected 163-SB-014-1214 from 12.5-13.0' bgs @13:10 |
| | 14.0 | | | | | 13.0 - 15.0' FILL: Light brown fine to medium sand, lenses of silt; wet | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-014
**DATE BEGAN:** 11/2/10
**DATE FINISHED:** 11/2/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | | | | | | |
| | 15.0 | S-5 | NA | 2.0 | | 15.0 - 16.0' : No recovery | 0 | Sample collected 163-SB-014-1416 from 14.5-15.0' bgs @13:15 |
| | 16.0 | | | | | 16.0 - 16.5' OL: Light brown clayey silt; soft, wet | | |
| | 17.0 | | | | | 16.5 - 17.3' OL: Black clayey silt, trace organics; very moist | | Sample collected 163-SB-014-1618 from 16.5-17.0' bgs @13:20 |
| | 18.0 | | | | | 17.3 - 18.0' PT: Brown peat; moist; end of boring at 18.0' bgs | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-015

**DATE BEGAN:** 11/3/10 | **DATE FINISHED:** 11/3/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 18 ft bgs | **GW DEPTH:** 4.0 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' FILL: Gravel, concrete | 0 | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Orange/red silt, dark brown nodules; dense | | Sample collected 163-SB-015-0002 from 1.0-1.5' bgs @14:05 |
| | 2.0 | | | | | 1.5 - 3.3' FILL: Black silty sand, coal, gravel, clinker; dense | | Sample collected 163-SB-015-0204 from 2.5-3.0' bgs @14:10 |
| | 3.0 | | | | | 3.3 - 3.5' FILL: Light brown fine to medium sand | | |
| ▽ | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | Sample collected 163-SB-015-0406 from 4.5-5.0' bgs @14:15 |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Light brown fine to medium sand, lenses of silt throughout, shells from 5.0-7.0'; wet | | Sample collected 163-SB-015-0608 from 6.5-7.0' bgs @14:20 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand, lenses of silt throughout; wet | 0 | Sample collected 163-SB-015-0810 from 8.0-8.5' bgs @14:25; DUP at 14:27 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-015-1012 from 10.0-10.5' bgs @14:30 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 15.0' FILL: Red brown/light brown silt, lenses of fine to medium sand throughout; wet | 0 | Sample collected 163-SB-015-1214 from 12.0-12.5' bgs @14:35 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 163-SB-015-1416 from 14.5-15.0' bgs @14:40 |
| | 15.0 | | | | | 15.0 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 16.5' FILL: Red brown silt; wet | 0 | |
| | 17.0 | | | | | 16.5 - 17.0' OL: Black clayey silt; very moist | | Sample collected 163-SB-015-1618 from 16.5-17.0' bgs @14:45 |
| | 18.0 | | | | | 17.0 - 18.0' PT: Brown peat; moist; end of boring at 18.0' bgs | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-016

**DATE BEGAN:** 11/3/10 | **DATE FINISHED:** 11/3/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 18 ft bgs | **GW DEPTH:** 4.0 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 2.0' FILL: Gray silty sand, fine to coarse gravel, crushed concrete | 0 | |
| | 1.0 | | | | | | | Sample collected 163-SB-016-0002 from 1.0-1.5' bgs @14:50 |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Black silt, coal, gravel, clinker; dense | | |
| | 3.0 | | | | | 2.5 - 4.0' : No recovery | | Sample collected 163-SB-016-0204 from 2.0-2.5' bgs @14:55 |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, lenses of silt throughout, shells from 5.0-7.0'; wet | 0 | |
| | 5.0 | | | | | | | Sample collected 163-SB-016-0406 from 4.5-5.0' bgs @15:00 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-016-0608 from 6.5-7.0' bgs @15:05 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand, lenses of silt throughout; saturated | 0 | |
| | 9.0 | | | | | | | Sample collected 163-SB-016-0810 from 8.5-9.0' bgs @15:10 |
| | 10.0 | | | | | | | Sample collected 163-SB-016-1012 from 10.0-10.5' bgs @15:15 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 12.5' FILL: Light brown fine to medium sand; wet | 0 | Sample collected 163-SB-016-1214 from 12.0-12.5' bgs @15:20 |
| | 13.0 | | | | | 12.5 - 14.5' FILL: Light brown/red brown fine sand, some silt; wet | | |
| | 14.0 | | | | | | | Sample collected 163-SB-016-1416 from 14.0-14.5' bgs @15:25 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 16.5' FILL: Red brown silt; wet | 0 | |
| | 17.0 | | | | | 16.5 - 18.0' OL: Olive/black clayey silt, organics; very moist; end of boring at 18.0' | | Sample collected 163-SB-016-1618 from 17.0-17.5' bgs @15:30 |
| | 18.0 | | | | | | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-017
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' CONCRETE | 0 | |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Black silty sand, coal, clinker | | Sample collected 163-SB-017-0002 from 1.0-1.5' bgs @14:35 |
| | 2.0 | | | | | 1.8 - 3.0' FILL: Light brown silt; dense | | |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | Sample collected 163-SB-017-0204 from 2.5-3.0' bgs @14:45 |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, lenses of silt throughout; wet at 4.5' | 0 | Sample collected 163-SB-017-0406 from 4.5-5.0' bgs @14:45 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-017-0608 from 6.5-7.0' bgs @14:50 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 10.5' FILL: Light brown silt, fine sand; wet | 0 | Sample collected 163-SB-017-0810 from 8.0-8.5' bgs @14:55 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 11.0' FILL: Light brown silt, fine sand; wet | | Sample collected 163-SB-017-1012 from 10.5-11.0' bgs @15:00 |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 13.0' FILL: Light brown silt, fine sand; wet | 0 | Sample collected 163-SB-017-1214 from 12.0-12.5' bgs @15:10 |
| | 13.0 | | | | | 13.0 - 13.5' FILL: Light brown clayey silt; soft; wet | | |
| | 14.0 | | | | | 13.5 - 14.5' FILL: Light brown silt; wet | | Sample collected 163-SB-017-1416 from 14.0-14.5' bgs @15:10 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 16.5' FILL: Light brown silt; wet | 0 | |
| | 17.0 | | | | | 16.5 - 18.0' PT: Brown peat; moist; end of boring at 18.0' | | Sample collected 163-SB-017-1618 from 16.5-17.0' bgs @15:15 |
| | 18.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-018

**DATE BEGAN:** 11/8/10 | **DATE FINISHED:** 11/8/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 20 ft bgs | **GW DEPTH:** 5.0 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.0' FILL: Brown sand, fine to coarse gravel | 0 | Sample collected 163-SB-018-0002 from 0.5-1.0' bgs @13:45 |
| | 1.0 | | | | | 1.0 - 3.0' FILL: Brown sand, fine to coarse gravel, crushed concrete | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Dark brown/black silty sand, coal, gravel | | Sample collected 163-SB-018-0204 from 3.0-3.5' bgs @13:50 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Light brown fine to medium sand; petroleum odor | | Sample collected 163-SB-018-0406 from 4.0-4.5' bgs @13:55 |
| | 6.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, lenses of clayey silt; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-018-0608 from 6.5-7.0' bgs @14:00 |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, lenses of clayey silt, shells; wet | 0 | Sample collected 163-SB-018-0810 from 8.0-8.5' bgs @14:05; DUP @ 14:07 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | Sample collected 163-SB-018-1012 from 10.5-11.0' bgs @14:10 |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' FILL: Light brown fine to medium sand, trace silt | 0 | Sample collected 163-SB-018-1214 from 12.0-12.5' bgs @14:15 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 163-SB-018-1416 from 14.0-14.5' bgs @14:20 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 17.5' FILL: Light brown fine to medium sand, trace silt | 0 | Sample collected 163-SB-018-1618 from 16.0-16.5' bgs @14:25 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | 17.5 - 19.0' OL: Olive/light brown clayey silt, organics; very moist | | Sample collected 163-SB-018-1820 from 18.0-18.5' bgs @14:30; DUP @ 14:32 |
| | 19.0 | | | | | | | |
| | 20.0 | | | | | 19.0 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-019
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' FILL: Brown sand, gravel | 0 | Sample collected 163-SB-019-0002 from 0.5-1.0' bgs @12:55 |
| | 1.0 | | | | | 0.5 - 0.8' FILL: Black silty sand, coal, gravel | | |
| | 2.0 | | | | | 0.8 - 1.8' FILL: Crushed concrete | | |
| | 3.0 | | | | | 1.8 - 3.5' FILL: Light brown silt; dense | | Sample collected 163-SB-019-0204 from 3.0-3.5' bgs @13:00 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Light brown silt, lenses of fine to medium sand; dense; wet at 5.0' | | Sample collected 163-SB-019-0406 from 4.0-4.5' bgs @13:05 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-019-0608 from 6.5-7.0' bgs @13:10 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand, lenses of silt, shells; wet | 0 | Sample collected 163-SB-019-0810 from 8.0-8.5' bgs @13:15 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-019-1012 from 10.0-10.5' bgs @13:20 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' FILL: Light brown fine to medium sand, lenses of silt, shells; wet | 0 | Sample collected 163-SB-019-1214 from 12.0-12.5' bgs @13:25 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 163-SB-019-1416 from 14.0-14.5' bgs @13:30 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.75 | | 16.0 - 16.5' FILL: Light brown fine to medium sand, lenses of silt, shells; wet | 0 | Sample collected 163-SB-019-1618 from 16.0-16.5' bgs @13:35 |
| | 17.0 | | | | | 16.5 - 18.5' OL: Light brown clayey silt, organics; very moist | | |
| | 18.0 | | | | | 18.5 - 18.8' PT: Brown peat; moist | | Sample collected 163-SB-019-1820 from 18.0-18.5' bgs @13:40 |
| | 19.0 | | | | | 18.8 - 20.0' No recovery; end of boring at 20' | | |
| | 20.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: BS

# MACTEC Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-020
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 2.0' FILL: Crushed concrete, gray coarse sand, fine to coarse gravel | 0 | |
| | 1.0 | | | | | 2.0 - 2.5' FILL: Light orange fine to medium sand | | Sample collected 163-SB-020-0002 from 1.0-1.5' bgs @12:05 |
| | 2.0 | | | | | 2.5 - 3.5' FILL: Black silty sand, gravel, coal, clinker | | Sample collected 163-SB-020-0204 from 3.0-3.5' bgs @12:10 |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | Sample collected 163-SB-020-0406 from 4.0-4.5' bgs @12:15 |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Red brown silt | | |
| | 6.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | | Sample collected 163-SB-020-0608 from 6.5-7.0' bgs @12:20 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | 0 | Sample collected 163-SB-020-0810 from 8.0-8.5' bgs @12:25 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' : No recovery | | Sample collected 163-SB-020-1012 from 10.5-11.0' bgs @12:30 |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.0' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | 0 | Sample collected 163-SB-020-1214 from 12.0-12.5' bgs @12:35 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 14.5' FILL: Red brown silt; wet | | Sample collected 163-SB-020-1416 from 14.0-14.5' bgs @12:40 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 3.5 | | 16.0 - 19.0' FILL: Light brown clayey silt; soft; wet | 0 | Sample collected 163-SB-020-1618 from 16.0-16.5' bgs @12:45 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 19.0 - 19.5' OL: Black clayey silt; very moist | | Sample collected 163-SB-020-1820 from 19.0-19.5' bgs @12:50 |
| | 20.0 | | | | | 19.5 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-021
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 2.0' FILL: Light gray fine to medium sand, gravel, crushed concrete | 0 | Sample collected 163-SB-021-0002 from 1.0-1.5' bgs @11:15 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Black silty sand, coal, clinker, gravel | | |
| | 3.0 | | | | | 3.5 - 4.0' : No recovery | | Sample collected 163-SB-021-0204 from 3.0-3.5' bgs @11:20 |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Light brown fine to medium sand, lenses of silt; wet at 5.0' | 0 | Sample collected 163-SB-021-0406 from 4.0-4.5' bgs @11:25 |
| ▽ | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 163-SB-021-0608 from 6.5-7.0' bgs @11:30 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand, lenses of silt, shells; saturated | 0 | Sample collected 163-SB-021-0810 from 8.0-8.5' bgs @11:35 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-021-1012 from 10.0-10.5' bgs @11:40 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' FILL: Light brown fine to medium sand, lenses of silt, shells; saturated | 0 | Sample collected 163-SB-021-1214 from 12.0-12.5' bgs @11:45 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 163-SB-021-1416 from 14.0-14.5' bgs @11:50 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 2.5 | | 16.0 - 17.8' FILL: Light brown fine to medium sand, lenses of silt; wet | 0 | Sample collected 163-SB-021-1618 from 16.0-16.5' bgs @11:55 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | 17.8 - 18.0' OL: Black clayey silt; very moist | | |
| | 19.0 | | | | | 18.0 - 18.5' PT: Brown peat; moist | | Sample collected 163-SB-021-1820 from 18.0-18.5' bgs @12:00 |
| | 20.0 | | | | | 18.5 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-022
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 3.0' FILL: Light gray sand, gravel, crushed concrete | 0 | Sample collected 163-SB-022-0002 from 1.0-1.5' bgs @10:25 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Light brown fine to mediumn sand | | Sample collected 163-SB-022-0204 from 3.0-3.5' bgs @10:30 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | Sample collected 163-SB-022-0406 from 4.0-4.5' bgs @10:35 |
| | 5.0 | | | | | 4.0 - 4.5' FILL: Light brown fine to medium sand | | |
| | 6.0 | | | | | 4.5 - 5.0' FILL: Light brown clayey silt; sheen, petroleum odor; wet | | Sample collected 163-SB-022-0608 from 6.5-7.0' bgs @10:40; DUP @ 10:42 |
| | 7.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | | |
| | 8.0 | S-3 | NA | 2.5 | | 7.0 - 8.0' No recovery | 0 | Sample collected 163-SB-022-0810 from 8.0-8.5' bgs @10:45 |
| | 9.0 | | | | | 8.0 - 10.5' FILL: Light brown fine to medium sand, lenses of red brown silt, shells; wet | | |
| | 10.0 | | | | | 10.5 - 12.0' : No recovery | | Sample collected 163-SB-022-1012 from 10.0-10.5' bgs @10:50 |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' FILL: Light brown/light gray fine to medium sand, trace shells; wet | 0 | Sample collected 163-SB-022-1214 from 12.0-12.5' bgs @10:55 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.5 - 16.0' : No recovery | | Sample collected 163-SB-022-1416 from 14.0-14.5' bgs @11:00 |
| | 15.0 | | | | | | | |
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 18.0' FILL: Light brown clayey silt; soft, wet | 0 | Sample collected 163-SB-022-1618 from 16.0-16.5' bgs @11:05 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | 18.0 - 18.5' OL: Black clayey silt, trace organics; very moist | | Sample collected 163-SB-022-1820 from 18.0-18.5' bgs @11:10 |
| | 19.0 | | | | | 18.5 - 19.0' PT: Brown peat; moist | | |
| | 20.0 | | | | | 19.0 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-023
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 2.5' FILL: Light brown/gray fine to medium sand, gravel, crushed concrete | 0 | |
| | 1.0 | | | | | | | Sample collected 163-SB-023-0002 from 1.0-1.5' bgs @9:35 |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Black silty sand, coal, clinker, gravel | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Light brown fine to medium sand | | Sample collected 163-SB-023-0204 from 3.0-3.5' bgs @9:40 |
| ▽ | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 7.0' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | | Sample collected 163-SB-023-0406 from 4.0-4.5' bgs @9:45 |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-023-0608 from 6.5-7.0' bgs @9:50 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | 0 | Sample collected 163-SB-023-0810 from 8.0-8.5' bgs @9:55 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-023-1012 from 10.0-10.5' bgs @10:00 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 14.5' FILL: Light brown fine to medium sand, trace shells; wet | 0 | Sample collected 163-SB-023-1214 from 12.0-12.5' bgs @10:05 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | Sample collected 163-SB-023-1416 from 14.0-14.5' bgs @10:10 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 18.0' FILL: Light brown clayey silt; soft; wet | 0 | Sample collected 163-SB-023-1618 from 16.0-16.5' bgs @10:15 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | 18.0 - 18.5' OL: Black clayey silt, trace organics; very moist | | Sample collected 163-SB-023-1820 from 18.0-18.5' bgs @10:20 |
| | 19.0 | | | | | 18.5 - 19.0' PT: Brown peat; moist | | |
| | 20.0 | | | | | 19.0 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** 163-SB-024
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.5' FILL: Light brown sand, gravel, crushed concrete | 0 | Sample collected 163-SB-024-0002 from 0.5-1.0' bgs @8:45 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.0' FILL: Black silty sand, gravel | | Sample collected 163-SB-024-0204 from 2.5-3.0' bgs @8:50 |
| | 3.0 | | | | | 3.0 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 4.5' FILL: Black silty sand, gravel | 0 | Sample collected 163-SB-024-0406 from 4.0-4.5' bgs @8:55 |
| ▽ | 5.0 | | | | | 4.5 - 6.5' FILL: Light brown silt, lenses of fine to medium sand; dense, wet at 5.0' | | |
| | 6.0 | | | | | | | Sample collected 163-SB-024-0608 from 6.5-7.0' bgs @9:00 |
| | 7.0 | | | | | 6.5 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.5 | | 8.0 - 11.5' FILL: Light brown fine to medium sand, lenses of red brown silt; wet | 0 | Sample collected 163-SB-024-0810 from 8.5-9.0' bgs @9:05 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-024-1012 from 10.5-11.0' bgs @9:10 |
| | 11.0 | | | | | 11.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 12.8' FILL: Light gray fine to coarse sand; wet | 0 | Sample collected 163-SB-024-1214 from 12.0-12.5' bgs @9:15 |
| | 13.0 | | | | | 12.8 - 13.5' FILL: Red brown silt; wet | | |
| | 14.0 | | | | | 13.5 - 15.0' FILL: Light brown/light gray fine to medium sand; wet | | Sample collected 163-SB-024-1416 from 14.5-15.0' bgs @9:20 |
| | 15.0 | | | | | 15.0 - 16.0' : No recovery | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-024**
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 18.0' FILL: Light brown clayey silt; soft, wet | 0 | Sample collected 163-SB-024-1618 from 16.5-17.0' bgs @9:25 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | 18.0 - 18.5' FILL: Light brown/red brown silt; wet | | |
| | 19.0 | | | | | 18.5 - 19.0' OL: Black clayey silt, organics; very moist | | Sample collected 163-SB-024-1820 from 18.5-19.0' bgs @9:30 |
| | 20.0 | | | | | 19.0 - 20.0' No recovery; end of boring at 20' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163 | **PROJECT NO:** 3480050143 | **BORING ID:** 163-SB-025

**DATE BEGAN:** 11/8/10 | **DATE FINISHED:** 11/8/10 | **INSPECTOR:** B. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 6610DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 20 ft bgs | **GW DEPTH:** 5.0 ft bgs

**DRILLER:** Gordon Blewett | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 3.0' FILL: Crushed concrete, gravel | 0 | |
| | 1.0 | | | | | | | Sample collected 163-SB-025-0002 from 1.0-1.5' bgs @7:55 |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 3.5' FILL: Black silty sand, coal, gravel, clinker, trace brick | | Sample collected 163-SB-025-0204 from 3.0-3.5' bgs @8:00 |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | 0 | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Black silty sand, coal, gravel, clinker, trace brick | | Sample collected 163-SB-025-0406 from 4.0-4.5' bgs @8:05 |
| | 6.0 | | | | | 5.0 - 7.0' FILL: Light brown fine to medium sand, silt lenses; wet | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Sample collected 163-SB-025-0608 from 6.5-7.0' bgs @8:10 |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' FILL: Light brown fine to medium sand, silt lenses; wet | 0 | Sample collected 163-SB-025-0810 from 8.0-8.5' bgs @8:15 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-025-1012 from 10.0-10.5' bgs @8:20 |
| | 11.0 | | | | | 10.5 - 12.0' : No recovery | | |
| | 12.0 | S-4 | NA | 2.5 | | 12.0 - 12.8' FILL: Light brown fine to medium sand, silt lenses; wet | 0 | Sample collected 163-SB-025-1214 from 12.0-12.5' bgs @8:25 |
| | 13.0 | | | | | 12.8 - 14.5' FILL: Light brown silt; wet | | |
| | 14.0 | | | | | | | Sample collected 163-SB-025-1416 from 14.0-14.5' bgs @8:30 |
| | 15.0 | | | | | 14.5 - 16.0' : No recovery | | |

PREPARED BY: MS

CHECKED BY: BS

# Honeywell Site SA-6 South

**SITE INFO:** Site 163
**PROJECT NO:** 3480050143
**BORING ID:** **163-SB-025**
**DATE BEGAN:** 11/8/10
**DATE FINISHED:** 11/8/10
**INSPECTOR:** B. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Gordon Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | S-5 | NA | 4.0 | | 16.0 - 16.3' FILL: Light brown silt; wet | 0 | Sample collected 163-SB-025-1618 from 16.0-16.5' bgs @8:35 |
| | 17.0 | | | | | 16.3 - 19.5' OL: Light brown clayey silt; soft; wet | | |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | 19.5 - 19.9' OL: Light brown clayey silt, trace organics; very moist | | Sample collected 163-SB-025-1820 from 18.5-19.0' bgs @8:40 |
| | 20.0 | | | | | 19.9 - 20.0' PT: Peat in tip; end of boring at 20.0' | | |

PREPARED BY: MS
CHECKED BY: BS

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-026
**DATE BEGAN:** 09/15/2011
**DATE FINISHED:** 09/15/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | | | 0.0 - 2.5' CONCRETE | | Driller used concrete bit to advance to 2.5 ft bgs before sampling |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Black/yellowish brown/ lt. brown f-m sand, some clinker from 2.5-2.7', trace fine gravel + silt; loose | | |
| | 3.0 | S-1 | | 1.5 | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 4.6' SM: Reddish-brown/brown alternating lenses of clayey silt and f-c sand; dense, moise | NA | |
| | 5.0 | | | | | 4.6 - 6.0' SW: Brown f-c sand, trace nodules of reddish brown silt; med, dense, moist | | |
| | 6.0 | | | | | 6.0 - 16.0' SW: Grayish brown f-c sand, trace silt; loose, wet | | No sheen or odors observed |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | | | | NA | 163-SB-026 1214 from 12.0-12.5' @ 0915 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-027
**DATE BEGAN:** 09/14/2011
**DATE FINISHED:** 09/15/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | NA | | 0.0 - 2.0' CONCRETE | NA | |
| | 1.0 | | | | | | | 09/14/11 Driller used concrete bit to advance to 2ft bgs |
| | 2.0 | S-1 | | 2.0 | | 2.0 - 2.8' FILL: Black f-c sand + clinker, few trace coal; fine gravel, dense, dry | | |
| | 3.0 | | | | | 2.8 - 4.0' FILL: Lt brown f-c sand, trace silt, loose, dry | | 09/15/11 Began sampling from 2.0 ft bgs |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' SW: Brown/ grayish brown f-c sand few lenses of clayey silt, trace seashells; med dense, wet from 6.0' | NA | No sheen but chemical odor (poss. petroleum) from 6.0'. JB grabbed sample as requested by TG. Not for lab submittal; odor evaluation |
| ▽ | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' SW: SAA, little sheen throughout but odor is less obvious | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 16.0' SW: SAA; no sheen or odor | NA | |
| | 13.0 | | | | | | | 163-SB-027-1214 from 12.0-12.5' @ 0800 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-028
**DATE BEGAN:** 09/14/2011
**DATE FINISHED:** 09/14/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | NA | | 0.0 - 2.5' CONCRETE | NA | |
| | 1.0 | | | | | | | 09/14/11 Driller used concrete bit to advance to 2.5ft bgs before sampling |
| | 2.0 | | | | | | | |
| | | S-1 | NA | 1.5 | | 2.5 - 2.8' FILL: Brick | | |
| | 3.0 | | | | | 2.8 - 4.5' FILL: Brown/black fine sand and silt, little clinker + coal; trace brick, sense, dry | | |
| | 4.0 | S-2 | NA | 4.0 | | | NA | |
| | 5.0 | | | | | 4.5 - 6.0' SC: Brown f-c sand, some lenses of silty clay; med-dense, moist | | |
| | 6.0 | | | | | 6.0 - 12.0' SW: Brown/grayish brown f-c sand + trace silt; med dense, wet | | Petroleum odors but no sheen from 6.0' |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | | NA | SAA |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 14.0' SP: Brown fine sand, trace silt; loose, wet | NA | 163-SB-028-1214 from 12.0-12.5' @1430 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 16.0' SW: Grayish brown f-c sand, trace silt; loose, wet | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-029
**DATE BEGAN:** 09/15/2011
**DATE FINISHED:** 09/15/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | | | 0.0 - 2.5' CONCRETE | NA | Driller used concrete bit to advance to 2.5ft bgs before sampling |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.5 - 3.0' FILL: Black f-c sand and clinker, little coal, trace fine gravel; dense, dry | | |
| | 3.0 | S-1 | | 1.5 | | 3.0 - 3.5' ML: Reddish brown, thinly bedded silt with very thin lenses of fine sand; stiff, dry | | Liner jammed + some sample lost from S-1 |
| | 4.0 | S-2 | NA | 2.5 | | silt | NA | |
| | 5.0 | | | | | 4.0 - 5.0' SM: Alternating lenses of reddish brown silt and brown f-m sand, trace seashells; dense, moise | | |
| ▽ | 6.0 | | | | | 5.0 - 6.5' ML: Reddish brown/gray silt, few lenses of fine sand, trace clay; stiff, wet from 6.0' | | |
| | 7.0 | | | | | 6.5 - 8.0' No Recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' SW: Brown/grayish brown f-c sand, few lenses of silt; med, dense, wet | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No Recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 16.0' SW: Brown/grayish brown fine to coarse sand, few lenses of silt; med, dense, wet | NA | 163-SB-029 1214 from 12.0-12.5' @ 1100 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-030
**DATE BEGAN:** 09/14/2011
**DATE FINISHED:** 09/14/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | NA | | 0.0 - 2.5' CONCRETE | NA | |
| | 1.0 | S-1 | | | | | | Driller used concrete bit to advance to 2.5ft bgs before sampling |
| | 2.0 | | | 1.5 | | 2.5 - 3.2' FILL: Black/brown/red f-c sand, some clinker + fine gravel; dense, dry | | |
| | 3.0 | | | | | 3.2 - 6.0' FILL: Lt brown f-m sand; moise, loose | | |
| | 4.0 | S-2 | NA | 4.0 | | | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 16.0' SW: Brown/ grayish brown f-c sand, trace lenses of silt; wet, loose | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | 163-SB-030-1416 from 14.0-14.5' @ 11:45; DP @ 11:50 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-031
**DATE BEGAN:** 09/14/2011
**DATE FINISHED:** 09/14/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | NA | | 0.0 - 0.5' FILL: Lt brown f-c sand and fine gravel, some brick, loose, dry | NA | |
| | 1.0 | | | | | 0.5 - 2.0' CONCRETE | | Driller used concrete bit to advance to 2ft bgs before sampling |
| | 2.0 | S-1 | | 2.0 | | 2.0 - 4.0' FILL: Lt brown f-c sand + fine gravel, dense, dry | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.0' SC: Brown f-c sand, some lenses of silty clay; med dense, wet from 6.0' | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 12.0' SW: Grayish brown f-c sand, trace lenses of silty clay; med dense, wet | | |
| | 8.0 | S-3 | NA | 4.0 | | | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 14.0' SM: Brown fine sand, some silt, med-dense, wet | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 16.0' SW: Grayish brown f-c sand, trace silt and fine gravel; loose, wet | | 163-SB-031-1416 from 14.0-14.5' @ 1325 |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-032
**DATE BEGAN:** 09/06/2011
**DATE FINISHED:** 09/06/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 8.0 ft bgs
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | NA | | 0.0 - 1.0' CONCRETE | NA | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Reddish brown/dark brown fine to coarse sand, some fine to coarse gravel, trace silt; yellow COPR (granular) from 1.3-1.6'; moist | | |
| | 2.0 | | | 3.5 | | 2.0 - 2.5' FILL: Black fine to coarse sand, some fine gravel, trace clinker and coal | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Brown fine to coarse sand, trace silt; moist | | |
| | 4.0 | S-2 | NA | 3.5 | | 3.5 - 4.0' No Recovery | NA | |
| | 5.0 | | | | | 4.0 - 7.5' SM: Reddish brown fine to coarse sand, some lenses of silty clay, trace sea shell fragments; moist | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 7.5 - 8.0' No Recovery | NA | |
| | 9.0 | | | | | 8.0 - 12.0' SW: Reddish gray fine to coarse sand, few lenses of silty clay; wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 15.0' SW: Grayish brown fine to coarse sand, few lenses of silty clay; wet | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' No Recovery; End of boring at 16' | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-033
**DATE BEGAN:** 09/6/2011
**DATE FINISHED:** 09/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 8.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 3.5' FILL: Yellowish brown to grayish brown f-c sand, few fine gravel; trace concrete from 0-2'; trace silt, moist | NA | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No Recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 8.0' FILL: Yellowish brown/ grayish brown f-c sand, few f-c gravel, trace silt, moist | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 10.0' FILL: Same as above, Wet | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 12.0' SW: Reddish gray f-c sand, few lenses of silty clay, trace fine gravel, wet | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 16.0' SW: Reddish gray/gray f-c sand, trace fine gravel, trace lenses of reddish grey silty clay, wet | NA | 163-SB-033-1416 from 14.0-14.5' @ 1040 DP @ 1045 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Honeywell SA-6 South
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-034
**DATE BEGAN:** 09-12-11
**DATE FINISHED:** 09-12-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 2.0 | | 0.0 - 2.0' FILL: Light gray fine to coarse sand and fine gravel, few silt; dry, loose | N/A | |
| | 1.0 | | | | | | | 163-SB-034-0002 from 1.0-1.5' at 1320 |
| | 2.0 | | | | | | | EOB at 2.0' |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-035
**DATE BEGAN:** 09-12-11
**DATE FINISHED:** 09-12-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 1.5 | | 0.0 - 1.5' FILL: Grayish brown fine to coarse sand, some fine gravel, trace silt and concrete; dry, loose | N/A | 163-SB-035-0002 from 1.0-1.5' at 1335 |
| | 1.0 | | | | | 1.5 - 2.0' No Recovery | | EOB at 2.0' |
| | 2.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-036
**DATE BEGAN:** 09-12-11
**DATE FINISHED:** 09-12-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 1.5 | | 0.0 - 1.2' FILL: Brown fine to coarse sand, some fine to coarse gravel; dry | N/A | |
| | 1.0 | | | | | 1.2 - 1.5' FILL: Black fine to coarse sand, some clinker and coal, trace brick and fine gravel; dry | | |
| | | | | | | 1.5 - 2.0' No Recovery | | 163-SB-036-0002 from 1.0-1.5' at 1250 |
| | 2.0 | | | | | | | EOB at 2.0' |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-037
**DATE BEGAN:** 09-12-11
**DATE FINISHED:** 09-12-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 14.0 ft bgs
**GW DEPTH:** 6.0 ft
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 4.0 | | 0.0 - 0.7' FILL: Brown fine to coarse sand and fine gravel; dry | N/A | |
| | 1.0 | | | | | 0.7 - 1.8' FILL: Concrete | | |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Dark brown fine to medium sand, some silt and fine gravel; dry | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Black fine to coarse sand, some clinker and coal, trace fine gravel; moist from 3.0' | | |
| | 4.0 | S-2 | | 4.0 | | 3.5 - 4.0' SP: Grayish brown fine to medium sand | | |
| | 5.0 | | | | | 4.0 - 8.0' SP: Grayish brown fine to medium sand, few silt, from 7.0'; wet from 6.0' | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | | 3.0 | | 8.0 - 11.0' SW: Grayish brown fine to coarse sand, few lenses of reddish brown clayey silt; wet | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No Recovery | | |
| | 12.0 | S-4 | | 1.2 | | 12.0 - 13.2' SW: Grayish brown fine to coarse sand, few lenses of reddish brown clayey silt; wet, loose | | 163-SB-037-1214 from 12.0-12.5 at 1105 |
| | 13.0 | | | | | 13.2 - 14.0' No Recovery | | |
| | 14.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-038
**DATE BEGAN:** 09/14/2011
**DATE FINISHED:** 09/14/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | NA | NA | NA | | 0.0 - 0.5' FILL: Lt brown f-c sand, little fine gravel; loose, dry | NA | |
| | 1.0 | | | | | 0.5 - 3.0' CONCRETE | | Driller used concrete bit to advance to 3.0ft bgs before sampling |
| | 2.0 | | | | | | | |
| | 3.0 | S-1 | | 1.0 | | 3.0 - 4.0' FILL: Black f-c sand and clinker, some coal, trace fine gravel; dry, dense | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 6.0' SW: Grayish brown f-c sand few lenses of brown silt, trace fine gravel; loose, wet from 5.0' | NA | |
| ▽ | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 8.0' SC: Brown alternating layers of f-c sand trace fine gravel and seashells and silty clay, trace fine sand; med dense, wet | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 16.0' SW: Brown f-c sand, few lenses of silty clay, few seashells, trace fine gravel; loose, wet | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | | NA | 163-SB-038-1416 from 14.0-14.5' @1030 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-039
**DATE BEGAN:** 09-12-11
**DATE FINISHED:** 09-12-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 6.5 ft
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 4.0 | | 0.0 - 2.2' FILL: Brown/ dark brown fine to coarse sand, some fine gravel, few silt; trace concrete, asphalt, clinker; dry | N/A | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.2 - 3.5' FILL: Concrete | | |
| | 3.0 | | | | | 3.5 - 4.0' FILL: Black fine to coarse sand, some clinker and coal, trace fine gravel; dry | | |
| | 4.0 | S-2 | | 4.0 | | 4.0 - 5.0' FILL: Black fine to coarse sand, some clinker and coal, trace fine gravel; dry | | |
| | 5.0 | | | | | 5.0 - 7.0' SP: Grayish brown fine to medium sand, trace fine gravel and lenses of reddish brown silt; wet from 6.5' | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 7.8' ML: Reddish brown/ gray clayey silt, some lenses of fine to medium sand; wet, stiff | | |
| | 8.0 | S-3 | | 4.0 | | 7.8 - 8.0' SW: Reddish brown fine to coarse sand, trace silt, fine gravel and sea shell fragments; wet, loose | | |
| | 9.0 | | | | | 8.0 - 10.0' SM: Alternating lenses of reddish brown fine to coarse sand, some fine gravel, and clayey silt; wet, dense | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.0 - 12.0' No Recovery | | |
| | 12.0 | S-4 | | 3.0 | | 12.0 - 15.0' SW: Reddish gray fine to coarse sabd, trace fine gravel, few lenses of reddish brown clayey silt; wet | | 163-SB-039-1416 from 14.0-14.5' at 0915 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' No Recovery | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-040
**DATE BEGAN:** 09-9-11
**DATE FINISHED:** 09-9-11
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 16.0 ft bgs
**GW DEPTH:** 4 ft
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 4.0 | | 0.0 - 1.0' FILL: Light brown fine to medium silty sand, fine to medium gravel; moist, dense | N/A | |
| | 1.0 | | | | | 1.0 - 1.5' ASPHALT | | |
| | 2.0 | | | | | 1.5 - 3.5' CONCRETE | | |
| | 3.0 | | | | | 3.5 - 4.0' SILTY SAND: Dark gray fine to medium silty sand, ash, coal, clinker | | |
| | 4.0 | S-2 | | 4.0 | | 4.0 - 10.5' SAND AND SILT: Grayish brown fine to medium sand, lenses of reddish brown silty f-m clay; wet, loose | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | | 3.0 | | | | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.5 - 11.0' SAND AND SILT: Black silt; wet, soft | | |
| | 11.0 | | | | | 11.0 - 12.0' No Recovery | | |
| | 12.0 | S-4 | | 3.0 | | 12.0 - 16.0' SILT: Black silt; wet, soft | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | 163-SB-040 from 15.5-16.0 at 1425. Duplicate at 1430. |
| | 15.0 | | | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-041
**DATE BEGAN:** 9/9/2011
**DATE FINISHED:** 9/9/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 0.5' FILL: Reddish orange fine to medium sand | NA | |
| | | | | | | 0.5 - 0.8' FILL: Brown fine sand, some silt, nodules of red stiff silt; moist, stiff | | |
| | 1.0 | | | | | 0.8 - 1.3' FILL: Banded dark grey/reddish brown silt, trace fien sand, coal, and fine to medium gravel; moist, dense | | |
| | 2.0 | | | | | 1.3 - 2.3' FILL: Dark grey fine to medium sand, some silt, coal, ash, and lenses of reddish brown firm silt; moist, loose | | |
| | | | | | | 2.3 - 3.5' FILL: Reddish brown silt, lenses of dark grey fine to medium sand; moist, dense | | |
| | 3.0 | | | | | 3.5 - 4.0' SW: Greyish brown fine to medium sand; moist, loose | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 6.5' SP: Greysih brown fine to medium sand, lenses of reddish brown firm silt; wet, loose | NA | Petroleum odor @ 4.0' bgs |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | Sample collected 163-SB-041-0608 from 6.0 - 6.5' bgs @ 13:15 |
| | | | | | | 6.5 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-042
**DATE BEGAN:** 9/9/2011
**DATE FINISHED:** 9/9/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 1.8' CONCRETE | NA | |
| | 1.0 | | | | | 1.8 - 2.0' FILL: Brown fine sand, some silt; moist, loose | | Sample collected 163-SB-042-0002 from1.5 - 2.0' bgs @ 12:08 |
| | 2.0 | | | | | 2.0 - 2.8' CONCRETE: green staining | | |
| | 3.0 | | | | | 2.8 - 3.3' FILL: Dark brown/yellowish brown fine sand, some silt; trace fine gravel; wet, loose | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.3 - 4.0' No recovery | NA | |
| | 5.0 | | | | | 4.0 - 5.0' FILL: Dark brown/yellowish brown fine sand, some silt; trace fine gravel; wet, loose | | |
| | 6.0 | | | | | 5.0 - 7.0' SP: Dark greyish brown fine to medium sand, nodules of red silt, trace course sand; wet, loose | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' SP: Dark greyish brown fine to medium sand, nodules of red silt; moist, loose | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 1.0 | | 12.0 - 13.0' SP: Dark greyish brown fine to medium sand, nodules of red silt, trace fine gravel; moist, loose | | Sample collected 163-SB-042-1214 from 12.5 - 13.0' bgs @ 12:30 |
| | 13.0 | | | | | 13.0 - 14.0' No recovery; end of boring @ 14.0' bgs | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-043

**DATE BEGAN:** 9/9/2011 | **DATE FINISHED:** 9/9/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5410DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 14.0 ft bgs | **GW DEPTH:** 6.0 ft bgs

**DRILLER:** Jake | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' FILL: Brown fine sand, some silt and fine to medium gravel; dry, loose | NA | |
| | 1.0 | | | | | 0.3 - 0.4' ASPHALT | | |
| | 2.0 | | | | | 0.4 - 0.8' CONCRETE | | Sample collected 163-SB-043-0002 from 1.5 - 2.0' bgs @ 11:15 |
| | 3.0 | | | | | 0.8 - 2.0' FILL: Brown fine sand, some silt, asphalt, reddish brown nodules of silt, trace gravel and glass; moist, dense | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.0 - 3.5' FILL: Brown fine to medium sand, some silt and coal, trace nodules of red silt; moist, dense | NA | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 8.0' SP: Dark brown fine sand, some silt, trace fine to medium gravel and nodules of red silty clay, wet @ 6.0' bgs, dense | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' SP: Dark brown fine sand, some silt, trace fine to medium gravel, nodules of red silty clay, and shells; wet | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 0.5 | | 12.0 - 12.5' SP: Greyish brown fine sand, nodules of red silty clay; wet, loose | | Sample collected 163-SB-043-1214 from 12.0 - 12.5' bgs @ 11:40 |
| | 13.0 | | | | | 12.5 - 14.0' No recovery; end of boring @ 14.0' bgs | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-044
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.2' TOPSOIL: Organics | NA | |
| | | | | | | 0.2 - 0.5' FILL: Light brown fine to medium silty sand, fine to medium gravel; dry, dense | | |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Dark grey fine to medium silty sand, coal, ash, brown pumice-like material (clinker); moist, dense | | |
| | 2.0 | | | | | 2.0 - 3.3' ML: Reddish brown silt, trace clay; moist, firm | | Sample collected 163-SB-044-0204 from 2.0 - 2.5' bgs @ 12:20 |
| | 3.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.0' SP: Reddish brown silt, lenses of greysih brown fine to meidum sand from 5.5' - 6.0' bgs; wet, firm | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' SP: Greyish brown fine to course sand, some red silty clay throughout; firm, wet | | |
| | 8.0 | S-3 | NA | 2.5 | | 8.0 - 9.5' SW: Greysih brown fine to medium sand; wet, loose | NA | Sample collected 163-SB-044-1012 from 10.0 - 10.5' bgs @ 12:30 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 9.5 - 10.5' SM: Greyish brown fine silty sand; wet, loose | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery; end of boring @ 12.0' bgs | | |
| | 12.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-045

**DATE BEGAN:** 9/8/2011 | **DATE FINISHED:** 9/8/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5410DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 4 ft bgs | **GW DEPTH:** NA

**DRILLER:** Jake | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4 | | 0.0 - 2.0' CONCRETE | NA | No Sample collected 163-SB-045-0002 due to concrete |
| | 1.0 | | | | | | | Sample collected 163-SB-045-0204 from 2.5 - 3.0' bgs@ 15:15 |
| | 2.0 | | | | | 2.0 - 2.8' FILL: Red silt, trace clay and fine sand; moist, very stiff | | |
| | | | | | | 2.8 - 3.0' FILL: Green fine to medium and; dry, stiff | | |
| | 3.0 | | | | | 3.0 - 3.5' CONCRETE: green staining | | |
| | | | | | | 3.5 - 4.0' FILL: Dark grey silt, trace fine sand; moist, stiff; end of boring @ 4.0' bgs | | |
| | 4.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-046
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2 | | 0.0 - 1.3' CONCRETE: degraded from 0.75 - 1.25' bgs | NA | Sample collected 163-SB-046-0002 from 1.5 - 2.0' bgs @ 14:58 |
| | 1.0 | | | | | 1.3 - 1.5' FILL: Red silt; moist, dense | | |
| | | | | | | 1.5 - 2.0' FILL: Reddish brown fine to medium silty sand, trace green silt; moist, loose; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-047
**DATE BEGAN:** 09/7/2011
**DATE FINISHED:** 09/7/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' FILL: Grayish brown f-c sand + gravel, trace clinker + silt; wet | NA | |
| | | | | | | 0.5 - 1.0' FILL: Concrete | | |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Black f-c sand, some clinker, trace coal + fine gravel; moist | | 163-SB-047-0002 from 1.5-2.0' @ 0925 |
| | | | | | | 1.8 - 2.0' FILL: Yellow/white f-c sand, some fine gravel and crushed concrete (COPR); dry | | Refusal @ 2.0' |
| | 2.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-048
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.0 | | 0.0 - 0.5' Asphalt | NA | Sample collected 163-SB-048-0002 from 0.5-1.0' bgs @ 9:40 |
| | | | | | | 0.5 - 0.8' FILL: Reddish brown silt, fine to medium gravel; moist, very dense | | |
| | | | | | | 0.8 - 1.0' CONCRETE: green staining | | |
| | 1.0 | | | | | 1.0 - 2.0' No recovery; end of boring @ 2.0' bgs due to refusal | | Sample of concrete also collected; refusal @ 2', unable to power drill through |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-049
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10.0 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' TOPSOIL: organics | NA | |
| | | | | | | 0.1 - 0.5' FILL: Light brown fine silty sand, fine to medium gravel, organics; moist, dense | | |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Brown fine silty sand; moist, loose | | |
| | 2.0 | | | | | 1.3 - 2.3' FILL: Dark grey fine to medium silty sand, coal, ash, brown pumice-like material (clinker), trace organics; moist, dense | | |
| | 3.0 | | | | | 2.3 - 2.5' FILL: Reddish brown fine silty sand; loose, moist | | |
| | | | | | | 2.5 - 3.5' SW: Greyish brown fien to medium sand; wet, loose | | |
| | 4.0 | S-2 | NA | 4.0 | | 3.5 - 4.0' No recovery | NA | |
| | | | | | | 4.0 - 8.0' SP: Greyish brown fine to medium sand, lenses of red silty stiff clay from 4.75 - 5.25' and 7.0-7.75' bgs, trace shells; wet, loose | | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 1.0 | | 8.0 - 9.0' Greyish brown fine to medium sand, lenses of red silty stiff clay; wet, loose | | Sample collected 163-SB-049-0810 from 8.5 - 9.0' bgs @ 14:20 |
| | 9.0 | | | | | 9.0 - 10.0' No recovery; end of boring @ 10.0' bgs | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-050
**DATE BEGAN:** 9/7/2011
**DATE FINISHED:** 9/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' CONCRETE | NA | |
| | | | | | | 0.3 - 0.5' FILL: Reddish brown fine to medium silty sand, fine to medium gravel; moist, very dense | | Sample collected 163-SB-050-0002 from 1.0 - 1.5' bgs @ 15:55 |
| | 1.0 | | | | | 0.5 - 1.3' FILL: Dark grey fine to medium silty sand, fine to medium gravel, trace red silt; moist, very dense | | |
| | 2.0 | | | | | 1.3 - 1.8' FILL: Dark grey fine to medium silty sand, coal, and ash | | |
| | 3.0 | | | | | 1.8 - 2.3' FILL: Reddish brown silt; dry, dense | | |
| | | | | | | 2.3 - 2.5' FILL: Reddish brown fine sandy silt, trace clay; moist, dense | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.5 - 3.0' FILL: Dark grey fine silty sand, trace fine gravel | NA | |
| | | | | | | 3.0 - 3.5' SP: Greyish brown fine to medium sand, lenses of silty clay, trace fine gravel | | |
| | 5.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 6.0 | | | | | 4.0 - 5.0' SP: Greyish brown fine to medium sand; wet, loose | | |
| | | | | | | 5.0 - 5.5' CH: Red silty clay; wet, very firm | | |
| | 7.0 | | | | | 5.5 - 8.0' SP: Greyish brown fine to course sand, lenses of red firm silt; wet, loose | | |
| | 8.0 | S-3 | NA | 1.0 | | 8.0 - 9.0' SP: Greyish brown fine to course sand, lenses of red firm silt; wet, loose | NA | Sample collected 163-SB-050-0810 from 8.0 - 8.5' bgs @ 16:10 |
| | 9.0 | | | | | 9.0 - 10.0' No recovery; end of boring 10.0' bgs | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-051

**DATE BEGAN:** 9/7/2011 | **DATE FINISHED:** 9/7/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5410DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 10.5 ft bgs | **GW DEPTH:** 8.0 ft bgs

**DRILLER:** Jake | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' FILL: Dark brown fine to medium silty sand, fine to medium gravel, trace light brown sand and red fine to medium silty sand; moist, loose | NA | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Fine to medium gravel, dark brown fine to medium sand; moist, loose | | Sample collected 163-SB-051-0002 from 0.5 - 1.0' bgs @ 11:25 |
| | 2.0 | | | | | 1.5 - 4.0' SP: Brownish grey fine to medium sand, trace silt, nodules of red silty clay, trace gravel; moist, loose | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' SP: Brownish grey fine to medium sand, trace silt, nodules of red silty clay, trace gravel and course sand moist, loose | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| ▽ | 8.0 | S-3 | NA | 2.5 | | 8.0 - 10.5' SP: Brownish grey fine to medium sand, trace silt, nodules of red silty clay, trace gravel and course sand moist, loose; end of boring @ 10.5' bgs | NA | Hydrocarbon odor |
| | 9.0 | | | | | | | Sample collected 163-SB-051-0810 from 8.5 - 9.0' bgs @ 11:50; DUP @ 11:52 |
| | 10.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-052
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' TOPSOIL: Organics, marble, plastic; moist, loose | NA | |
| | | | | | | 0.5 - 1.5' FILL: Reddish brown fine to medium sand; moist, loose | | |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 3.5' VOID | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.5' SW: Greysih brown fine to medium sand; wet, loose | NA | Black staininng and organic odor @ 7.5' bgs |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.5 - 8.0' SP: Greyish brown fine silty sand, lense of reddish brown silty clay from 7.8' - 8.0' bgs; wet. loose; end of boring @ 8.0' bgs | | Sample collected 163-SB-052-0608 from 7.5 - 8.0' bgs @ 11:40 |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-053
**DATE BEGAN:** 09/6/2011
**DATE FINISHED:** 09/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' CONCRETE | NA | |
| | | | | | | 0.3 - 1.5' FILL: Reddish brown f-c sand and gravel, little silt; moist | | |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 2.0' FILL: Concrete and yellow f-c sand and gravel (COPR), dry | | 163-SB-053-0002 from 1.5-2.0' @ 1300 |
| | 2.0 | | | | | 2.0 - 3.0' FILL: Black f-c sand, some clinker and coal; dry | | 163-SB-053-0204 from 2.5-3.0' @ 1305 |
| | 3.0 | | | | | 3.0 - 4.0' SW: Reddish gray f-c sand, few lenses of silty clay, trace fine gravel; moist | | |
| | 4.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-054
**DATE BEGAN:** 09/6/2011
**DATE FINISHED:** 09/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NE
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.5' FILL: Reddish brown f-c sand + gravel; trace concrete + silt | NA | 163-SB-054-0002 from 1.5-2.0' @ 1315 |
| | 1.0 | | | | | 1.5 - 3.0' FILL: Black/grayish brown f-c sand; some clinker, brick + coal; few fine gravel | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.0 - 4.0' SW: Reddish gray f-c sand, trace lenses of silty clay | | |
| | 4.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-055
**DATE BEGAN:** 09/6/2011
**DATE FINISHED:** 09/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 3.5' FILL: Gray/black f-c sand; brick from 0.8-1.2', some clinker + coal from 2.0-3.0' | NA | 163-SB-055-0002 from 1.5-2.0' @ 1400 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.5 - 4.0' SW: Grayish brown f-c sand, few silt, trace clay | | |
| | 4.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-056
**DATE BEGAN:** 09/6/2011
**DATE FINISHED:** 09/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 2.0' FILL: Brown f-c sand+gravel; trace silt | NA | 163-SB-056-0002 from 1.5-2.0' @ 1335 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Dk brown f-c sand, some f-c gravel + silt, trace clinker + coal | | |
| | | | | | | 2.5 - 3.5' SW: Reddish gray f-c sand; little silt, trace clay from 3.2' | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' SW: Grayish brown f-c sand | | |
| | 4.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South


**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-057

**DATE BEGAN:** 9/7/2011 | **DATE FINISHED:** 9/7/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5410DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 18 ft bgs | **GW DEPTH:** 4.0 ft bgs

**DRILLER:** Jake | **NORTH:** | **EAST:**




| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' GRAVEL: concrete | NA | |
| | | | | | | 0.3 - 0.5' FILL: Dark grey silt, some fine sand, fine to medium gravel; moist, very firm | | Refusal @ 6" bgs due to wook, moved east 1' |
| | | | | | | 0.5 - 0.7' FILL: Dark grey fine to medium silty sand; ask, trace wook and black pumice like fragments (clinker) | | |
| | 4.0 | S-2 | NA | 4.0 | | 0.7 - 1.0' FILL: Black silty; moist, very firm | NA | |
| | | | | | | 1.0 - 1.2' FILL: Dark grey fine to medium silty sand, black pumice-like fragments (clinker) | | |
| | | | | | | 1.2 - 3.3' FILL: Reddish brown fine silty sand, lenses of red clayey firm silt, trace fine gravel and coal | | |
| | 8.0 | S-3 | NA | 2.0 | | 3.3 - 3.5' FILL: Greysih brown fine to medium sand, lenses of red silty clay; moist, firm | NA | |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | | | | | | 4.0 - 8.0' SP: Greyish brown fine to medium sand, trace lenses of grey silt, trace coarse sand and nodules of red silty clay | | |
| | 12.0 | S-4 | NA | 1.5 | | 8.0 - 9.9' SW: Greysih brown fine to medium sand, trace nodules of reddish brown silty clay; wet, loose | NA | |
| | | | | | | 9.9 - 10.0' SM: Grey silt, trace fine sand; wet | | |
| | | | | | | 10.0 - 12.0' No recovery | | |
| | | | | | | 12.0 - 13.5' ML: Brown fine sandy silt; moist, firm | | |
| | 16.0 | S-5 | NA | 1.0 | | 13.5 - 16.0' No recovery | NA | Sample collected 163-SB-057-1618 from 16.0 - 16.5' bgs @ 15:20 |
| | | | | | | 16.0 - 16.5' OH: Black silty Clay; firm | | |
| | | | | | | 16.5 - 17.0' PT: Brown moist stiff peat, grey clay; moist, soft | | |
| | 18.0 | | | | | 17.0 - 18.0' No recovery | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-058
**DATE BEGAN:** 09/7/2011
**DATE FINISHED:** 09/14/2011
**INSPECTOR:** M. Daly/ J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | | | | 0.0 - 0.3' CONCRETE | NA | |
| | | | | | | 0.3 - 0.5' SILTY SAND: Reddish brown fine to med silty sand, F-M gravel, moist, very dense | | |
| | 1.0 | | | | | 0.5 - 1.3' SILTY SAND: Dark gray fine to medium silty sand; f-m gravel, trace red silt, very dense, moist | | 163-SB-058-0002 from 1.0-1.5' @ 1555 |
| | | | | | | 1.3 - 1.8' SILTY SAND: Dark gray, F-M silty sand; coal, ash | | |
| | 2.0 | | | 3.5 | | 1.8 - 2.0' SILT: Reddish brown silt, fine sand; trace clay, moist | | |
| | | S-1 | | | | 2.0 - 2.5' SILTY SAND: Reddish brown fine sandy silt, trace clay, moist | | |
| | 3.0 | | | | | 2.5 - 3.5' SILTY SAND: Grayish brown f-m sand, lenses of red silty clay, trace fine gravel | | |
| | | | | | | 3.5 - 4.0' No Recovery | | |
| | 4.0 | | | | | 4.0 - 5.0' SAND: Grayish brown F-M sand, wet | NA | |
| | 5.0 | | | | | 5.0 - 5.5' CLAY AND SILT: Red silty clay, wet, fine to med | | |
| | | S-2 | | | | 5.5 - 8.0' SILTY SAND: Grayish brown F-C sand, lenses of red F-M silt, wet, loose | | |
| | 6.0 | | | 4.0 | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-058
**DATE BEGAN:** 09/7/2011
**DATE FINISHED:** 09/14/2011
**INSPECTOR:** M. Daly/ J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 4.5 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | S-3 | NA | 4 | | 8.0 - 10.0' SW: Grayish brown f-c sand, trace sill, loose, wet | NA | 163-SB-058-0810 from 8.0-8.5' @ 1600 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | 10.0 - 11.5' CH: Brown silty clay, trace fine sand; highly plastic, soft, wet; lenses of f-m sand from 10.6-10.8' | | |
| | 11.0 | | | | | | | |
| | | | | | | 11.5 - 12.0' SP: Brown/grayish brown f-m sand, few silt, med, dense, wet | | |
| | 12.0 | S-4 | NA | 4 | | 12.0 - 14.0' CH: Brown silty clay, lense of f-m sand from 13-13.2'; highly plastic, soft, wet | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 14.0 - 14.5' OH: Black clayey silt, trace fine sand, soft, wet | | 163-SB-058-1416 from 14.5-15.0' @ 0915 |
| | | | | | | 14.5 - 15.0' OH: Olive silty clay, few organic material; med, stiff, wet | | |
| | 15.0 | | | | | 15.0 - 16.0' PT: Dk brown peat; med dense, moist | | |
| | 16.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-059
**DATE BEGAN:** 9/7/2011
**DATE FINISHED:** 9/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' GRAVEL: concrete | NA | |
| | 1.0 | | | | | 0.3 - 2.0' FILL: Dark brown fine to medium silty sand, some clay and fine to medium gravel, trace light brown medium sand; moist, dense | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.0 - 2.1' FILL: Red silty clay; firm, moist | | |
| | 4.0 | S-2 | NA | 4.0 | | 2.1 - 3.3' SP: Reddish brown fine to medium sand, trace course sand, nodules of red silty clay; moist, firm | NA | |
| | 5.0 | | | | | 3.3 - 3.5' SW: Greyish brown fine to medium sand | | |
| | 6.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 7.0 | | | | | 4.0 - 7.0' SW: Greyish brown fine to medium sand, some layer of red silty firm clay, trace course sand and fine gravel; wet, moderate firm | | |
| | 8.0 | S-3 | NA | 4.0 | | | NA | |
| | 9.0 | | | | | 7.0 - 8.0' SP: Reddish grey fine sand, lenses of red silty frim clay; moist, moderate firm | | |
| | 10.0 | | | | | 8.0 - 10.0' SW: Greyish brown fine to medium sand, trace coarse sand; wet, loose | | |
| | 11.0 | | | | | 10.0 - 12.0' SM: Greyish brown fine sandy silt, nodules of brown silt; moist, firm | | |
| | 12.0 | S-4 | NA | 1.5 | | 12.0 - 13.5' ML: Greyish brown fine sandy silt, lenses of grey soft silt; wet, loose | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | 13.5 - 16.0' No recovery | | |
| | 15.0 | | | | | | | |
| | 16.0 | S-5 | NA | 2.0 | | 16.0 - 16.3' ML: Greyish brown fine sandy silt, lenses of grey soft silt; wet, loose | NA | Sample collected 163-SB-059-1618 from 16.5 - 17.0' bgs @ 13:20 |
| | 17.0 | | | | | 16.3 - 18.0' OH: Dark brown silt; moist, moderate firm; peat in tip; end of boring @ 18.0' bgs | | |
| | 18.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 Posnak & Turkish
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-060
**DATE BEGAN:** 09/7/2011
**DATE FINISHED:** 09/7/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 2.0' FILL: Brown/reddish brown f-c sand, some fine gravel, little silt, trace concrete moist | NA | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 3.3' FILL: Black/brown f-c sand, some clinker, little fine gravel; coal + silt; moist | | |
| | 3.0 | | | | | 3.3 - 4.0' SW: Reddish brown f-c sand, few lenses of silty clay; moist | | |
| | 4.0 | S-2 | | 2.0 | | 4.0 - 6.0' SW: Same as above; trace fine gravel; wet | | 163-SB-060-0406 from 5.5-6.0' @ 0855 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** 163-SB-061
**DATE BEGAN:** 09-12-11
**DATE FINISHED:** 09-12-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 3.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 3.0 | | 0.0 - 1.5' CONCRETE | N/A | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Brown fine to medium sand, some silt, trace concrete | | 163-SB-061-0002 from 1.5-2.0' at 1315 |
| | 2.0 | | | | | 2.0 - 2.7' FILL: Black fine to coarse sand, some clinker and coal; moist | | |
| | 3.0 | | | | | 2.7 - 3.0' ML: Brown silt, some fine to medium sand, trace clay; moist stiff | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-062
**DATE BEGAN:** 9/9/2011
**DATE FINISHED:** 9/9/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2 | | 0.0 - 0.5' FILL: Reddish orange fine to course sand, loose | NA | Sample collected 163-SB-062-0002 from 1.5 - 2.0' bgs @ 12:57 |
| | | | | | | 0.5 - 0.7' FILL: Brown fine sand, some silt and fine gravel; moist, dense | | |
| | | | | | | 0.7 - 0.8' FILL: Light brown silt, some fine gravel; moist, dense | | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Dark grey fine to medium sand, some silt, coal, ask brown pumice-like material (clinker); moist, dense; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-063
**DATE BEGAN:** 9/9/2011
**DATE FINISHED:** 9/9/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 7.0 ft bgs
**GW DEPTH:** 5.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.25 | | 0.0 - 0.4' CONCRETE | NA | |
| | | | | | | 0.4 - 1.0' FILL: Brown fine sand, some silt, organics, fine to medium gravel; moist, dense | | |
| | 1.0 | | | | | 1.0 - 1.3' FILL: Dark grey silt; moist, very firm | | |
| | | | | | | 1.3 - 1.4' FILL: Greenish yellow sand stone, dense, dry | | |
| | | | | | | 1.4 - 1.5' FILL: Brownish red silt; moist, dense | | |
| | 2.0 | | | | | 1.5 - 3.3' FILL: Dark grey fine sand, some silt, coal, ash, black pumice-like material (clinker) | | Refusal @ 2.0' bgs due to wook, moved NE 2' |
| | 3.0 | | | | | 3.3 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 2.5 | | 4.0 - 5.5' SM: Reddish brown silt, some fine to medium sand; wet @ 5.0' bgs, dense | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 5.5 - 6.5' SP: Greyish brown fine to medium sand, lenses of reddish brown firm silty clay, trace shells; wet, dense; wood in tip | | Sample collected 163-SB-063-0608 from 6.0 - 6.5' bgs @ 10:43 |
| | | | | | | 6.5 - 7.0' No recovery; end of boring @ 7.0' bgs | | Refusal @ 7.0' due to wood |
| | 7.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-064
**DATE BEGAN:** 9/9/2011
**DATE FINISHED:** 9/9/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.3' GRAVEL: some light brown sand | NA | Refusal @ 6" bgs, moved north 3' |
| | | | | | | 0.3 - 0.8' FILL: Brownish red silt, fine to medium gravel; moist, stiff | | |
| | | | | | | 0.8 - 1.3' FILL: Gravel, some light grey silt | | |
| | 1.0 | | | | | 1.3 - 1.4' FILL: Green gravel, trace green sand (COPR) | | |
| | | | | | | 1.4 - 2.5' FILL: Dark grey silt, some sand, coal ash, and fine to medium gravel; moist, dense | | Sample collected 163-SB-064-0002 from 1.0 - 1.5' bgs @ 9:58 |
| | 2.0 | | | | | | | |
| | | | | | | 2.5 - 3.5' FILL: Reddish brown silt, trace coal; moist, very stiff | | |
| | 3.0 | | | | | | | Sample collected 163-SB-064-0204 from 3.0 - 3.5' bgs @ 10:00 |
| | | | | | | 3.5 - 4.0' No recovery; end of boring @ 4.0' bgs | | |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-065
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NA
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.1' TOPSOIL: Organics | NA | Sample collected 163-SB-065-0002 from 0.0-0.5' bgs @ 13:05 |
| | | | | | | 0.1 - 0.3' FILL: Light brown silt; moist, dense | | |
| | | | | | | 0.3 - 1.0' FILL: Dark brown fine to medium silty sand, organics; moist, stiff | | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Dark grey fine to medium sand, coal, black pumice-like material (clinker), ash; moist, dense | | |
| | | | | | | 1.5 - 3.5' SP: Reddish brown fine to medium sand, some silt and lenses of reddish brown silty clay | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery; end of boring @ 4.0' bgs | | |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-066

**DATE BEGAN:** 9/8/2011 | **DATE FINISHED:** 9/8/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5410DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 10.0 ft bgs | **GW DEPTH:** 4.0 ft bgs

**DRILLER:** Jake | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 0.5' FILL: Brown fine silty sand, fine to medium gravel, organics | NA | |
| | | | | | | 0.5 - 1.5' FILL: Dark grey fine to medium silty sand, coal, ash, black pumice-like material (clinker); moist, loose | | Hit refusal due to building material, moved west 1'; hit refusal again, moved further west |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 3.8' FILL: Reddish brown clayey silt, lenses of reddish brown fine to medium sand; moist, stiff | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.8 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.0' SP: Greyish brown fine to course sand, lenses of red silty stiff clay; wet, loose | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' SW: Greyish brown fine sand, trace lenses of grey silt; wet, loose | | |
| | 8.0 | S-3 | NA | 1.0 | | 8.0 - 9.0' SW: Greyish brown fine sand, trace lenses of grey silt and shells; wet, loose | NA | Sample collected 163-SB-066-0810 from 8.5 - 9.0' bgs @ 13:42 |
| | 9.0 | | | | | 9.0 - 10.0' No recovery; end of boring @ 10.0' bgs | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-067
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/8/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8.0 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** Jake
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.5 | | 0.0 - 0.5' TOPSOIL: Organics, marble, plastic; moist, loose | NA | |
| | | | | | | 0.5 - 1.5' FILL: Reddish brown fine to medium sand; moist, loose | | |
| | 1.0 | | | | | 1.5 - 3.5' VOID | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.5 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.5' SW: Greysih brown fine to medium sand; wet, loose | NA | Trace petrolium odor @ 7.0' bgs |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.5 - 8.0' SP: Greyish brown fine silty sand, lense of reddish brown silty clay from 7.8' - 8.0' bgs; wet. loose; end of boring @ 8.0' bgs | | Sample collected 163-SB-067-0608 from 7.0 - 7.5' bgs @ 11:58 |
| | 8.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-068
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/14/2011
**INSPECTOR:** M. Daly/ J. Bacchus
**DRILLING CO:** TPI/ B+B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** J. Timmins/ E. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.2' TOPSOIL: Organics | NA | |
| | | | | | | 0.2 - 0.5' CONCRETE | | |
| | 1.0 | | | | | 0.5 - 1.6' FILL: Dark grey fine silty sand, lenses of red silty clay, trace fine gravel and wood; moist, loose | | |
| | | | | | | 1.6 - 1.8' FILL: Red clayey silt; moist, firm | | |
| | 2.0 | | | | | 1.8 - 2.0' FILL: Greyish brown fine to medium silty sand; wet, loose | | |
| | | | | | | 2.0 - 4.0' No recovery | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 6.8' SP: Reddish brown fine to course sand, nodules of red clayey silt, trace fine gravel; wet, loose | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.8 - 8.0' SP: Greyish brown fine to medium sand, nodules of red silty clay; wet, loose; end of boring @ 8.0' bgs | | Sample collected 163-SB-0680-0608 from 7.0 - 7.5' bgs @ 9:00 |
| | 8.0 | S-3 | | | | 8.0 - 12.0' SP: Greyish brown fine to medium sand, few silt lenses from 11'; medium dense, wet | | |
| | 9.0 | | | | | | | |

PREPARED BY: MD/NOK
CHECKED BY: DN

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-068
**DATE BEGAN:** 9/8/2011
**DATE FINISHED:** 9/14/2011
**INSPECTOR:** M. Daly/ J. Bacchus
**DRILLING CO:** TPI/ B+B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** 4.0 ft bgs
**DRILLER:** J. Timmins/ E. Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | | | | 12.0 - 15.0' SC: Alternating beds of very dark grayish brown fine sand, trace silt, and silty clay, trace fine sand; med dense, wet | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' No Recovery | | 163-SB-068-1618 from 17.0-17.5' at 0825 |
| | 16.0 | S-5 | | | | 16.0 - 17.8' OH: Very dark gray silty clay, trace fine sand; highly plastic, wet, soft EOB at 18 ft bgs | | |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: MD/NOK
CHECKED BY: DN

# Honeywell SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 34800100027
**BORING ID:** **163-SB-069**
**DATE BEGAN:** 09-07-11
**DATE FINISHED:** 09-07-11
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4ft Macrocore
**COMPLETION DEPTH:** 2.0 ft bgs
**GW DEPTH:** NA
**DRILLER:** J. Timmins
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | N/A | 2.0 | | 0.0 - 0.8' FILL: Grayish brown fine-coarse sand, some fine to coarse gravel, trace silt; wet | N/A | 10 ft west of 163-SB-047 |
| | | | | | | 0.8 - 1.5' FILL: Concrete, trace brick; dry | | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Dark brown fine to coarse sand, some silt, trace fine gravel | | 163-SB-069-0002 from 1.5-2.0' at 0935 |
| | 2.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-070
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.4' CONCRETE | NA | Sample collected 163-SB-070-0002 from 1.5 - 2.0' bgs @ 13:20; DUP @ 13:22 |
| | | | | | | 0.4 - 2.0' FILL: Reddish brown silt, trace clay; moist, firm; end of boring @ 2.0' bgs | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-071
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' FILL: Brown fine sand, some silt (30%), fine to medium gravel; moist, loose | NA | Sample collected 163-SB-071-0002 from 1.5 - 2.0' bgs @ 13:40 |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Black fine sand, some silt, coal, clinker; moist, loose; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-072
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | -0.6 - 0.2' CONCRETE | NA | |
| | | | | | | 0.2 - 1.5' FILL: Dark brown silt, some fine sand (35%), coal, firm ash, trace brick and clay; moist, loose | | Sample collected 163-SB-072-0002 from 1.0 - 1.5' bgs @ 15:00 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Reddish brown fine sand; moist, loose | | |
| | 3.0 | | | | | 2.5 - 3.0' FILL: Brownish grey fine to medium sand, trace silt; moist, dense | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' SP: Brown fine to medium sand; wet, loose | NA | Sample collected 163-SB-072-0608 from 6.5 - 7.0' bgs @ 15:01; DUP @ 15:03 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 1.5 | | 8.0 - 9.5' SP: Brown fine to medium sand; wet, loose | NA | Sample collected 163-SB-072-0810 from 9.0 - 9.5' bgs @ 15:12 |
| | 9.0 | | | | | | | |
| | | | | | | 9.5 - 10.0' No recovery; end of boring @ 10.0' bgs | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-073
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 10 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.75 | | 0.0 - 0.2' CONCRETE | NA | |
| | | | | | | 0.2 - 1.0' FILL: Reddish brown fine sand, some silt (30%), dry, loose | | |
| | 1.0 | | | | | 1.0 - 2.3' FILL: Dark brown fine sand, some silt, coal, and ash; moist, dense | | Sample collected 163-SB-073-0002 from 1.5- 2.0' bgs @ 14:05 |
| | 2.0 | | | | | | | 163-SB-073-0204 from 2.0-2.5' bgs @1407 |
| | | | | | | 2.3 - 2.8' FILL: Reddish brown fine to medium sand, trace clay; loose, moist | | |
| | 3.0 | | | | | 2.8 - 4.0' No recovery | | |
| ▽ | 4.0 | S-2 | NA | 4.0 | | 4.0 - 7.0' SP: Reddish brown fine to medium sand, trace lenses of reddish brown clay, some silt; wet, loose | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' SP: Greyish brown fine to medium sand; wet, loose | | |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 10.0' SP: Greyish brown fine to medium sand; wet, loose; end of boring @ 10.0' bgs | NA | |
| | 9.0 | | | | | | | Sample collected 163-SB-073-0810 from 9.5 - 10.0' bgs @ 14:26 |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-074
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' FILL: Light brown silt, some fine sand (40%), trace brick and fine gravel; dry, very dense | NA | Sample collected 163-SB-074-0204 from 3.5- 4.0' bgs @ 15:30 |
| | | | | | | 0.5 - 1.0' CONCRETE | | |
| | 1.0 | | | | | 1.0 - 2.8' FILL: Reddish silt, trace coal; moist, very stiff | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 2.8 - 3.8' CONCRETE: fine to medium gravel, green staining | | |
| | | | | | | 3.8 - 4.0' FILL: Dark brown silt; moist, very stiff; end of boring @ 4.0' bgs | | |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-075
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' CONCRETE: Green staining 1.3-1.5' bgs | NA | Sample collected 163-SB-075-0002 from 1.5- 2.0' bgs @ 15:46 |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Reddish silt, trace clay; wet, very stiff; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-076
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 3 ft bgs
**GW DEPTH:** NA
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.5' CONCRETE | NA | |
| | 1.0 | | | | | 1.5 - 2.5' FILL: Grey silt, some fine to medium gravel; very loose, then stiff, wet, then moist | | Sample collected 163-SB-076-0002 from 1.5- 2.0' bgs @ 16:07 |
| | 2.0 | | | | | 2.5 - 2.8' CONCRETE | | |
| | | | | | | 2.8 - 3.0' FILL: Brown fine to medium sand, some silt and fine to medium gravel; moist, dense; end of boring @ 2.0' bgs | | |
| | 3.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-077

**DATE BEGAN:** 10/19/2011 | **DATE FINISHED:** 10/19/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Geoprobe 5410DT

**SAMPLING TOOL:** 4-ft Macrocore | **COMPLETION DEPTH:** 14 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** George | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' FILL: Light brown fine sand, some silt (30%). fine to medium gravel | NA | |
| | 1.0 | | | | | 0.3 - 0.7' CONCRETE: degraded | | Sample collected 163-SB-078-0002 from 1.5 - 2.0' bgs @ 17:05 |
| | 2.0 | | | | | 0.7 - 2.0' FILL: Medium grey fine to medium sand, some silt and fine to medium gravel, trace brick; dry, loose | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Dark grey silt, lenses of grey fine to medium sand, some fine to meidum gravel, trace brick; moist, dense | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 4.0' FILL: Dark grey fine sand, some silt ash, coal, brown pumice-like material (clinker); moist, dense | NA | |
| | 5.0 | | | | | 4.0 - 7.0' SP: Greyish brown fine to medium sand, trace lenses of silt and clay; wet, loose | | Strong petroleum odor, sheen |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' SP: Greyish brown fine to medium sand, trace lenses of silt and clay, trace shells; wet, loose | NA | |
| | 9.0 | | | | | | | Strong petroleum odor, sheen |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' SP: Greyish brown fine to medium sand, some silt, trace lenses of silt and clay, trace shells; wet, loose; end of boring @ 14.0' bgs | | Sample collected 163-SB-078-214 from 13.5 - 14.0' bgs @ 17:20; DUP @ 17:22 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-078
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 14 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.3' FILL: Light brown fine sand, some silt (30%). fine to medium gravel | NA | |
| | 1.0 | | | | | 0.3 - 0.7' CONCRETE: degraded concrete | | Sample collected 163-SB-078-0002 from 1.5 - 2.0' bgs @ 17:05 |
| | 2.0 | | | | | 0.7 - 2.0' FILL: Medium grey fine to medium sand, some silt and fine to medium gravel, trace brick; dry, loose | | |
| | 3.0 | | | | | 2.0 - 3.0' FILL: Dark grey silt, lenses of grey fine to medium sand, some fine to meidum gravel, trace brick; moist, dense | | Petroleum odor 2-4' |
| | 4.0 | S-2 | NA | 3.0 | | 3.0 - 4.0' FILL: Dark grey fine sand, some silt ash, coal, clinker; moist, dense | NA | |
| | 5.0 | | | | | 4.0 - 7.0' SP: Greyish brown fine to medium sand, trace lenses of silt and clay; wet, loose | | Strong petroleum odor, sheen |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' SP: Greyish brown fine to medium sand, trace lenses of silt and clay, trace shells; wet, loose | NA | |
| | 9.0 | | | | | | | Strong petroleum odor, sheen |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 2.0 | | 12.0 - 14.0' SP: Greyish brown fine to medium sand, some silt, trace lenses of silt and clay, trace shells; wet, loose; end of boring @ 14.0' bgs | | Sample collected 163-SB-078-1214 from 13.5 - 14.0' bgs @ 17:20; DUP @ 17:22 |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-079
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' FILL: Light brown fine to medium sand, some fine to medium gravel; wet, loose | NA | |
| | 1.0 | | | | | 0.8 - 2.0' FILL: Dark grey silt, some coal and dark grey pumice-like material; moist, very dense | | |
| | 2.0 | | | | | 2.0 - 4.0' FILL: Reddish brown silt, some clay, trace shells; moist, very stiff | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 6.0' SW: Reddish silt, trace clay, lenses of greyish brown fine to medium sand; wet, stiff | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | 6.0 - 7.0' SP: Greysih brown fine to medium sand, lenses of reddish silt and clay, trace shells; wet, loose | | Sample collected 163-SB-079-0608 from 6.5 - 7.0' bgs @ 16:47 |
| | 7.0 | | | | | 7.0 - 8.0' No recovery; end of boring @ 8.0' bgs | | |
| | 8.0 | | | | | | | |

PREPARED BY: NOK
CHECKED BY: MM

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-080
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' FILL: Light brown fine to medium sand, some fine to medium gravel, trace wood; moist, loose | NA | |
| | 1.0 | | | | | 1.0 - 1.3' ASPHALT | | |
| | | | | | | 1.3 - 2.0' FILL: Greyish brown fine sand, some fine to medium gravel; wet, very loose | | |
| | 2.0 | | | | | 2.0 - 2.3' FILL: Fine to medium gravel, some greyish brown silt | | Sample collected 163-SB-080-0002 from 1.5 - 2.0' bgs @ 17:34; Petroleum odor |
| | | | | | | 2.3 - 3.0' FILL: Reddish silt, some clay | | |
| | 3.0 | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 6.8' SM: Dark grey silt, some fine sand (35%), fine to medium gravel; wet, very loose | NA | Sample collected 163-SB-080-0204 from 2.0 - 2.5' bgs @ 17:35<br>Sheen, petroleum odor<br>Sample collected 163-SB-080-0406 from 5.0 - 5.5' bgs @ 17:40 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 6.8 - 8.0' SP: Greyish brown fine to medium sand, lenses of silt and clay; wet, loose | | Sample collected 163-SB-080-0608 from 7.5 - 8.0' bgs @ 17:42 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' SP: Greyish brown fine to medium sand, lenses of silt and clay, trace shells; wet, loose | | Sample collected 163-SB-080-0810 from 8.5 - 9.0' bgs @ 17:45 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-080
**DATE BEGAN:** 10/19/2011
**DATE FINISHED:** 10/19/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 20 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** George
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Sample collected 163-SB-080-1012 from 11.5 - 12.0' bgs @ 17:47 |
| | 12.0 | S-4 | NA | 0.5 | | 12.0 - 12.5' SP: Greyish brown fine to medium sand; wet, loose | | |
| | | | | | | 12.5 - 16.0' No recovery | | |
| | 13.0 | | | | | | | Sample collected 163-SB-080-1214 from 12.0 - 12.5' bgs @ 17:49; Petroleum odor |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | |
| | 16.0 | S-5 | NA | 3.0 | | 16.0 - 16.5' CL: Brown silty clay; wet, loose | | Sample collected 163-SB-080-1618 from 16.0 - 16.5' bgs @ 18:01 |
| | 17.0 | | | | | 16.5 - 18.0' CL: Black clay; moist, stiff | | |
| | 18.0 | | | | | 18.0 - 19.0' PT: Brown clay, some brown peat (20%); moist, stiff | | Sample collected 163-SB-080-1820 from 18.5 - 19.0' bgs @ 18:03 |
| | 19.0 | | | | | 19.0 - 20.0' No recovery; end of boring @ 20.0' bgs | | |
| | 20.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-081
**DATE BEGAN:** 11/20/2011
**DATE FINISHED:** 11/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 24 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.0' CONCRETE | NA | |
| | 1.0 | | | | | 1.0 - 2.0' VOID | | HOLD ALL SAMPLES |
| | 2.0 | | | | | 2.0 - 3.0' CONCRETE | | |
| | 3.0 | | | | | 3.0 - 3.8' FILL: Greyish brown fine sand, some silt and fine to medium gravel | | Collected 163-SB-081-0204 from 3.0 - 3.5' bgs @ 11:40 |
| | 4.0 | S-2 | NA | 3.0 | | 3.8 - 4.0' FILL: Reddish brown fine to medium sand, some silt and clay; wet, stiff | NA | |
| | 5.0 | | | | | 4.0 - 6.8' FILL: Reddish brown fine to medium sand, lenses of silt and clay, trace fine gravel; wet, stiff | | Collected 163-SB-081-0406 from 5.0 - 5.5' bgs @ 11:45 |
| | 6.0 | | | | | 6.8 - 7.0' FILL: Greyish brown fine sand, some silt, trace fine to medium gravel; wet, dense | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | Collected 163-SB-081-0608 from 6.5 - 7.0' bgs @ 11:50 |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Greyish brown fine to medium sand, lenses of silt and clay, trace shells; wet, dense | NA | Collected 163-SB-081-0810 from 8.5 - 9.0' bgs @ 11:55 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | Collected 163-SB-081-1012 from 11.5 - 12.0' bgs @ 12:00 |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 15.0' FILL: Greyish brown fine to coarse sand, trace nodules of silt; wet, loose; sheen | NA | |
| | 13.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-081
**DATE BEGAN:** 11/20/2011
**DATE FINISHED:** 11/20/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 6610DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 24 ft bgs
**GW DEPTH:** 8 ft bgs
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | | | | | | | Collected 163-SB-081-1214 from 13.0 - 13.5' bgs @ 12:05 |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' FILL: Reddish brown silt, some fine sand, trace nodules of clay; wet, stiff | | Collected 163-SB-081-1416 from 15.5 - 16.0' bgs @ 12:15 |
| | 16.0 | S-5 | NA | 4.0 | | 16.0 - 19.9' FILL: Greyish brown fine to medium sand, some silt; wet, loose | NA | Collected 163-SB-081-1618 from 16.5 - 17.0' bgs @ 12:10 |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | | | Collected 163-SB-081-1820 from 19.0 - 19.5' bgs @ 12:20 |
| | | | | | | 19.9 - 20.0' FILL: Reddish brown fine sand, some silt | | |
| | 20.0 | S-6 | NA | 4.0 | | 20.0 - 23.0' SP: Brown fine sand, some organic material; moist, loose | NA | Collected 163-SB-081-2022 from 20.5 - 21.0' bgs @ 12:25 |
| | 21.0 | | | | | | | |
| | 22.0 | | | | | | | Collected 163-SB-081-2224 from 23.0 - 23.5' bgs @ 12:30 |
| | 23.0 | | | | | 23.0 - 23.5' SM: Brown fine sand, some silt and organic material, trace clay; moist, loose | | |
| | 24.0 | | | | | 23.5 - 24.0' PT: Peat, brown clay; moist, stiff; end of boring @ 24.0' bgs | | |

PREPARED BY: MD
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-082
**DATE BEGAN:** 10/24/2011
**DATE FINISHED:** 10/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** 6 ft bgs
**DRILLER:** John
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.75 | | 0.0 - 3.8' FILL: (SP): Reddish orange fine to medium sand, some fine to medium gravel, trace silt; moist, dense | NA | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.8 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: (SP): Reddish orange fine to medium sand, some fine to medium gravel and silt; layer of loose gravel from 6.75' to 7.0' bgs; wet @ 6.0' | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 8.0 - 8.5' SP: Reddish orange fine to medium sand, some fine to medium gravel and silt; wet | | |
| | 8.0 | S-3 | NA | 2.5 | | | | |
| | 9.0 | | | | | 8.5 - 10.5' SP: Greyish brown fine to medium sand, trace silt; wet, loose | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 10.5 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 15.0' SP: Greyish brown fine to medium sand, trace silt and shells; wet, loose | | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery, end of boring @ 16.0' bgs | | Sample collected 163-SB-082-1416 from 15.0 - 15.5' bgs @ 12:15 |
| | 16.0 | | | | | | | |
| | 17.0 | | | | | | | |
| | 18.0 | | | | | | | |
| | 19.0 | | | | | | | |
| | 20.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-083
**DATE BEGAN:** 10/24/2011
**DATE FINISHED:** 10/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** John
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' FILL: Dark grey fine sand, some silt and fine to medium gravel; moist, dense | NA | Sample collected 163-SB-083-0002 from 0.5 - 1.0' bgs @ 12:30 |
| | | | | | | 0.5 - 1.5' FILL: Light brown silt, some fine to medium gravel; moist, dense | | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Dark grey fine sand, some silt; moist, dense; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-084

**DATE BEGAN:** 10/24/2011 | **DATE FINISHED:** 10/24/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Hand Drill

**SAMPLING TOOL:** 2-ft Macrocore | **COMPLETION DEPTH:** 9 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** John | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.0 | | 0.0 - 0.2' TOPSOIL | NA | |
| | | | | | | 0.2 - 0.5' FILL: Marble | | |
| | 1.0 | | | | | 0.5 - 1.0' TOPSOIL: Dark brown fine to medium sand, some silt, organics; moist, loose | | |
| | | | | | | 1.0 - 2.0' No recovery | | |
| | 2.0 | S-2 | | 2.0 | | 2.0 - 4.0' FILL: Reddish brown fine to medium sand, lenses of silt and clay, trace organics; moist, loose | | |
| | 3.0 | | | | | | | |
| | 4.0 | S-3 | NA | 1.5 | | 4.0 - 4.5' No Recovery | NA | |
| | | | | | | 4.5 - 5.0' CL: Reddish brown clay, trace silt; wet, stiff | | |
| | 5.0 | | | | | 5.0 - 5.5' SP: Greyish brown fine to medium sand; wet, loose | | |
| | | | | | | 5.5 - 6.0' CL: Reddish brown clay, trace silt; moist, stiff | | |
| | 6.0 | S-4 | | 2.0 | | 6.0 - 7.5' SP: Greyish brown fine to medium sand; wet, loose | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' CL: Reddish brown clay, some silt; stiff, moist | | |
| | 8.0 | S-5 | NA | 1.0 | | 8.0 - 9.0' CL: Grey clay, some grey silt; wet, stiff; Refusal @ 9.0' bgs; end of boring @ 9.0' bgs | | Sample collected 163-SB-084-0810 from 8.0 - 8.5' bgs @ 10:40 |
| | 9.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-085

**DATE BEGAN:** 10/24/2011 | **DATE FINISHED:** 10/24/2011 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Direct Push | **DRILL EQUIP:** Hand Drill

**SAMPLING TOOL:** 2-ft Macrocore | **COMPLETION DEPTH:** 10 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** John | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | | NA | NA | | 0.0 - 4.0' NA | NA | Void in ground from 0-4' |
| | 1.0 | | | | | | | |
| | 2.0 | | | NA | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | 4.0 - 4.1' CONCRETE | | |
| | | S-1 | NA | 2.0 | | 4.1 - 6.0' SP: Reddish brown fine to medium sand, lenses of greyish brown silt and clay; wet, loose | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | S-2 | | 2.0 | | 6.0 - 8.0' SP: Greyish brown fine to medium sand, lenses of greyish brown silt and clay; wet, loose | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 2.0 | | 8.0 - 10.0' SP: Greyish brown fine to medium sand, lenses of greyish brown silt and clay, trace shells; wet, loose; end of boring @ 10.0' bgs | | Sample collected 163-SB-085-0810 from 8.5 - 9.0' bgs @ 10:00 |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-086
**DATE BEGAN:** 10/24/2011
**DATE FINISHED:** 10/24/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NA
**DRILLER:** John
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' CONCRETE: degraded concrete | NA | Sample collected 163-SB-086-0002 from 1.5 - 2.0' bgs @ 11:26 |
| | 1.0 | | | | | | | |
| | | | | | | 1.5 - 2.0' FILL: Dark grey silt, some fine to medium gravel; concrete in tip; dry, loose; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** Route 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 163-SB-087
**DATE BEGAN:** 12/6/2011
**DATE FINISHED:** 12/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | | 5<br>8 | 2.0 | | 10.0 - 12.0' FILL: Brown fine to coarse sand, some silt, trace shells and lenses of reddish brown clayey silt; medium dense, wet | N/A | Location HSA-25 on sampling table. Augered to 10 ft bgs before sampling. |
| | 11.0 | | 11<br>13 | | | | | |
| | 12.0 | | 3<br>5 | 1.5 | | 12.0 - 13.5' FILL: Brown fine to medium sand, trace shells; medium dense, wet | N/A | |
| | 13.0 | | 6<br>8 | | | | | Collected 163-SB-087-1314 from 13.0-13.5 ft bgs @ 9:25 |
| | | | | | | 13.5 - 14.0' No recovery | | |
| | 14.0 | | 2<br>3 | 2.0 | | 14.0 - 15.5' FILL: Brown fine to medium sand, trace shells; medium dense, wet | N/A | |
| | 15.0 | | 4<br>3 | | | 15.5 - 15.8' CH: Very dark greyish brown (10YR 3/2) silty clay; medium stiff, plastic, wet | | |
| | 16.0 | | 1<br>1 | 2.0 | | 15.8 - 16.7' OH: Black (2.5Y 2.5/1) clayey silt, trace organic material; miedium stiff, plastic, wet | N/A | |
| | 17.0 | | 4<br>4 | | | 16.7 - 18.0' PT: Dark brown (10YR 3/3) peat; medium stiff, crumbly, moist; end of boring @ 18' | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 163-SB-088
**DATE BEGAN:** 12/6/2011
**DATE FINISHED:** 12/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 22 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | | 2 | 2.0 | | 12.0 - 17.0' FILL: Brown fine to medium sand, some lenses of clayey silt, trace shells; medium dense, loose from 16.0', wet | N/A | Location HSA-23 on sampling table. Augered to 12 ft bgs before sampling. |
| | | | 2 | | | | | |
| | 13.0 | | 3 | | | | | |
| | | | 6 | | | | | |
| | 14.0 | | 6 | 2.0 | | | N/A | |
| | | | 10 | | | | | |
| | 15.0 | | 10 | | | | | |
| | | | 10 | | | | | Collected 163-SB-088-1516 from 15.5-16.0 ft bgs @ 11:30 |
| | 16.0 | | 4 | 1.7 | | | N/A | |
| | | | 4 | | | | | |
| | 17.0 | | 4 | | | 17.0 - 17.7' OH: Black/very dark grayish brown (2.5Y 2.5/1 to 3/2) clayey silt, trace organic material and fine sand; medium stiff, plastic, wet | | |
| | | | 3 | | | | | |
| | 18.0 | | 3 | 1.8 | | 17.7 - 18.0' No recovery | N/A | |
| | | | 3 | | | 18.0 - 19.8' OH: Dark olive gray (5Y 3/2) silty clay, little organic material; medium stiff, plastic, wet | | |
| | 19.0 | | 5 | | | | | |
| | | | 6 | | | 19.8 - 20.0' No recovery | | |
| | 20.0 | | 1 | 2.0 | | 20.0 - 21.5' OH: Dark olive gray (5Y 3/2) silty clay, little organic material; medium stiff, plastic, wet | N/A | |
| | | | 2 | | | | | |
| | 21.0 | | 3 | | | | | |
| | | | 5 | | | 21.5 - 22.0' SM: Very dark gray (5Y 3/1) fine sand, some silt; loose, wet; end of boring at 22' | | |
| | 22.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 163-SB-089
**DATE BEGAN:** 12/6/2011
**DATE FINISHED:** 12/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | 3 | 2.0 | | 14.0 - 15.4' FILL: Brown fine to medium sand, some silt; loose, wet | N/A | Location HSA-22 on sampling table. Augered to 14 ft bgs before sampling. |
| | | | 3 | | | | | |
| | 15.0 | | 2 | | | | | |
| | | | 2 | | | 15.4 - 16.0' CH: Very dark grayish brown (10YR 3/2) silty clay, some pieces of fibrous organic material (appears disturbed), one 2" root fragment at 15.8'; medium stiff, plastic, wet | | |
| | 16.0 | | 1 | 2.0 | | 16.0 - 16.8' OH: Dark olive gray (5Y 3/2) silty clay, some organic material; soft, plastic, wet | N/A | |
| | | | 1 | | | | | |
| | 17.0 | | 1 | | | 16.8 - 18.0' PT: Dark brown (10YR 3/3) peat; soft, moist; end of boring at 18' | | |
| | | | 1 | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Study Area - 6 South

**LOCATION:** Rt 440, Jersey City, NJ
**PROJECT NO:** 3480100022
**BORING ID:** 163-SB-090
**DATE BEGAN:** 12/6/2011
**DATE FINISHED:** 12/6/2011
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** Hollow-Stem Auger
**DRILL EQUIP:** Gus Pech BRAT-22R
**SAMPLING TOOL:** 3-in. diam., 2-ft split spoon
**COMPLETION DEPTH:** 18 ft bgs
**GW DEPTH:** Not measured
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | | | | | | | |
| | | | 4 | 2.0 | | 14.0 - 17.1' FILL: Brown fine to medium sand, some nodules of clayey silt, trace shells; medium dense, wet | N/A | Location HSA-24 on sampling table. Augered to 14 ft bgs before sampling. |
| | | | 7 | | | | | |
| | 15.0 | | 6 | | | | | |
| | | | 4 | | | | | Collected 163-SB-090-1516 from 15.5-16.0 ft bgs @ 15:15 |
| | 16.0 | | 1 | 2.0 | | | N/A | |
| | | | 1 | | | | | |
| | 17.0 | | 1 | | | 17.1 - 17.5' OH: Black (2.5Y 2.5/1) clayey silt, trace organic material; soft, plastic, wet | | |
| | | | 1 | | | 17.5 - 18.0' PT: Dark brown (10YR 3/3) peat; soft, moist; end of boring at 18' | | |
| | 18.0 | | | | | | | |

PREPARED BY: JB
CHECKED BY: KK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-091
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.5' CONCRETE | NA | |
| | | | | | | 0.5 - 2.0' FILL: Dark grey silt, coal, ash, clinker (brown pumice-like material); moist, dense; end of boring at 2.0'bgs | | Sample collected 163-SB-091-0002 from 1.0 - 1.5' bgs @12:10 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-092
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.2' FILL: Fine to medium gravel, brown silt, some fine sand; moist, dense | NA | |
| | | | | | | 0.2 - 0.4' FILL: Dark brown silt, fine to medium gravel; wet, dense | | |
| | | | | | | 0.4 - 0.8' FILL: Brown silt, some fine sand, fine to medium gravel | | |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Dark brown silt, some fine sand, fine to medium gravel, and coal; moist, dense | | |
| | | | | | | 1.5 - 1.8' FILL: Red silt; dry, dense | | |
| | | | | | | 1.8 - 2.0' FILL: Dark grey silt, ash, and coal; moist, dense | | |
| | 2.0 | | | | | 2.0 - 2.3' FILL: Red silt; dry, dense | | |
| | | | | | | 2.3 - 3.0' FILL: Dark grey silt, ash and coal; moist, dense | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Red silt,some clay, lenses of reddish brown fine to medium sand; moist, dense; end of boring at 4.0' bgs | | Sample collected 163-SB-092-0204 from 3.0 - 3.5' bgs @ 11:47 |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-093
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.4' CONCRETE | NA | |
| | | | | | | 0.4 - 0.6' FILL: Brown silt, some fine sand, fine to medium gravel; moist, dense | | |
| | | | | | | 0.6 - 1.0' CONCRETE: fine to medium gravel | | |
| | 1.0 | | | | | 1.0 - 2.0' FILL: Red silt, wet, soft | | Sample collected 163-SB-093-0002 from 1.5 - 2.0' bgs @ 11:08 |
| | 2.0 | | | | | 2.0 - 3.5' FILL: Dark grey silt, trace coal, fine to medium gravel, and grey fine sand; moist, dense | | |
| | 3.0 | | | | | | | Sample collected 163-SB-093-0204 from 3.0 - 3.5' bgs @ 11:10; HOLD |
| | | | | | | 3.5 - 4.0' No recovery; end of boring at 4.0' bgs | | |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-094
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.8' FILL: Fine to medium gravel, grey fine to medium sand; moist, loose | NA | |
| | | | | | | 0.8 - 1.3' CONCRETE: green staining | | |
| | 1.0 | | | | | | | Sample collected 163-SB-094-0002 from 1.0 - 1.5' bgs @ 11:55 |
| | | | | | | 1.3 - 2.8' FILL: Reddish brown silt; moist, dense | | |
| | 2.0 | | | | | | | |
| | | | | | | 2.8 - 4.0' FILL: Dark grey silt, ash, coal, and clinker (brown pumice-like material); moist, very dense; end of boring at 4.0' bgs | | |
| | 3.0 | | | | | | | Sample collected 163-SB-094-0204 from 3.0 - 3.5' bgs @ 11:57; HOLD |
| | 4.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** **163-SB-095**
**DATE BEGAN:** 12/7/2011
**DATE FINISHED:** 12/7/2011
**INSPECTOR:** M. Daly
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NE
**DRILLER:** Ed Blewett
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.5' FILL: Brown fine to medium sand, some medium gravle; moist, loose | NA | Sample collected 163-SB-095-0002 from 1.5 - 2.0' bgs @ 10:48: HOLD |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Reddish orange fine to medium sand, some medium gravel; moist, loose; end of boring @ 2.0' bgs | | |
| | 2.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-096
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 5.5 ft bgs
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' FILL: Gravel, fine to coarse | NA | |
| | | | | | | 0.5 - 2.0' FILL: Light gray fine to coarse sand, some fine gravel, few concrete, brick, and silt; loose, moist | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Concrete | | |
| | | | | | | 2.5 - 3.1' FILL: Reddish brown silt, some fine sand, little fine gravel; stiff, dry | | |
| | 3.0 | | | | | 3.1 - 3.5' FILL: Concrete, trace yellow discoloration from 3.1-3.2' | | |
| | | | | | | 3.5 - 4.0' FILL: Very dark grayish brown fine to medium sand, some silt, little clinker, trace brick; medium dense, moist | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 5.5' FILL: Very dark grayish brown fine to medium sand, some silt, little clinker, trace brick and shells; medium dense, moist | NA | |
| | 5.0 | | | | | | | Sample collected 163-SB-096-0406 from 5.0-5.5' bgs @ 9:15 |
| | | | | | | 5.5 - 6.0' FILL: Shredded wood; wet; end of boring at 6.0' | | |
| | 6.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-097
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.2' FILL: Light gray fine to coarse sand, trace fine gravel and shells; loose, wet<br>0.2 - 1.5' FILL: Concrete<br>1.5 - 3.5' FILL: Reddish brown silt, trace fine sand; stiff, dry<br>3.5 - 4.0' No recovery; end of boring at 4.0' | NA | Sample collected 163-SB-097-0002 from 1.5-2.0' bgs @ 10:20 |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | | | |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-098
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.5' CONCRETE | NA | |
| | 1.0 | | | | | 1.5 - 2.0' FILL: Reddish brown fine to medium sand, some silt and some yellow granular COPR, little fine gravel; medium dense, moist | | Sample collected 163-SB-098-0204 from 3.5-4.0' bgs @ 10:50 |
| | 2.0 | | | | | 2.0 - 3.4' FILL: Very dark grayish brown fine to coarse sand; few clinker, fine gravel, silt, trace brick and concrete; dense, moist | | |
| | 3.0 | | | | | 3.4 - 4.0' FILL: Grayish brown fine to medium sand, few lenses of brown silt; medium dense; end of boring at 4.0' | | |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-099
**DATE BEGAN:** 1/13/12
**DATE FINISHED:** 1/13/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** TPI
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 5410
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** Not encountered
**DRILLER:** George Demetriou
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.2' CONCRETE | NA | |
| | 1.0 | | | | | 1.2 - 2.0' FILL: Reddish brown fine to medium sand, some silt, trace fine gravel and brick; medium dense, dry | | Sample collected 163-SB-099-0002 from 1.5-2.0' bgs @ 11:10 |
| | 2.0 | | | | | 2.0 - 3.3' FILL: Very dark grayish brown fine to coarse sand, little clinker and fine gravel, trace silt and brick; medium dense, moist | | |
| | 3.0 | | | | | 3.3 - 4.0' FILL: Grayish brown fine to medium sand, few lenses of brown silt; medium dense, moist; end of boring at 4.0' | | Sample collected 163-SB-099-0204 from 3.5-4.0' bgs @ 11:15 |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-100
**DATE BEGAN:** 1/16/2012
**DATE FINISHED:** 1/16/2012
**INSPECTOR:** M. Daly
**DRILLING CO:** TPI
**DRILLING METHOD:** Hand Sampling/drill
**DRILL EQUIP:** Hand Drill
**SAMPLING TOOL:** 2-ft Macrocore, 1 inch diameter
**COMPLETION DEPTH:** 6 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Jake/Brian
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.5 | | 0.0 - 1.3' FILL: Dark grey fine sand, some silt, some fine gravel, trace ash, brown pumice like material (clinker); moist, loose | NA | Sample collected 163-SB-100-0002 from 0.5 - 1.0' bgs @ 8:38; DUP @ 8:49 |
| | 1.0 | | | | | 1.3 - 1.5' FILL: Dark grey fine sand, some silt, wood, ash, and clay; moist, dense | | |
| | | | | | | 1.5 - 2.0' No recovery | | |
| | 2.0 | S-2 | | 2.0 | | 2.0 - 4.0' FILL: Brown silt, some clay, brown fine sand, trace shells; moist, dense | | Sample collected 163-SB-100-0204 from 2.5 - 3.0' bgs @ 8:40 |
| | 3.0 | | | | | | | |
| ▽ | 4.0 | S-3 | | 1.5 | | 4.0 - 5.5' FILL: Brown silt, some clay, brown fine sand, trace shells; wet, dense | | Sample collected 163-SB-100-0406 from 4.5 - 5.0' bgs @ 8:42; HOLD |
| | 5.0 | | | | | | | |
| | | | | | | 5.5 - 6.0' No recovery; end of boring @ 6.0' bgs | | |
| | 6.0 | | | | | | | |

PREPARED BY: MD
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163 | **PROJECT NO:** 3480100027 | **BORING ID:** 163-SB-101

**DATE BEGAN:** 1/16/2012 | **DATE FINISHED:** 1/16/2012 | **INSPECTOR:** M. Daly

**DRILLING CO:** TPI | **DRILLING METHOD:** Hand Sampling/drill | **DRILL EQUIP:** Hand Drill

**SAMPLING TOOL:** 2-ft Macrocore; 1 inch diameter | **COMPLETION DEPTH:** 6 ft bgs | **GW DEPTH:** 4 ft bgs

**DRILLER:** Jake/Brian | **NORTH:** | **EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 1.3' FILL: Dark grey silt, some fine sand, trace ash coal; moist | NA | Sample collected 163-SB-101-0002 from 1.0 - 1.5' bgs @ 8:55 |
| | 1.0 | | | | | 1.3 - 2.0' FILL: Reddish brown silt, some fine sand, trace wood; moist | | |
| | 2.0 | S-2 | | 1.5 | | 2.0 - 3.5' FILL: Reddish brown silt, some lenses of fine sand, trace fine gravel; moist, dense | | |
| | 3.0 | | | | | | | |
| | | | | | | 3.5 - 4.0' No recovery | | Sample collected 163-SB-101-0204 from 3.0 - 3.5' bgs @ 8:57 |
| | 4.0 | S-3 | | 2.0 | | 4.0 - 5.5' FILL: Reddish brown silt, some lenses of fine sand, trace fine gravel and shells; wet, dense | | Sample collected 163-SB-101-0406 from 4.0 - 4.5' bgs @ 9:00; HOLD |
| | 5.0 | | | | | | | |
| | | | | | | 5.5 - 6.0' FILL: Brown fine to medium sand; wet, loose; end of boring @ 6.0' bgs | | |
| | 6.0 | | | | | | | |

PREPARED BY: MD

CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-102
**DATE BEGAN:** 1/19/12
**DATE FINISHED:** 1/19/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 1.6' FILL: Brown fine to coarse sand, some concrete and fine gravel; medium dense, dry | NA | |
| | 1.0 | | | | | 1.6 - 2.1' FILL: Black fine to medium sand, some clinker, trace coal and silt; medium dense, dry | | |
| | 2.0 | | | | | 2.1 - 3.0' FILL: Reddish brown silt, some lenses of fine to medium sand, trace clay; stiff, dry | | |
| | 3.0 | | | | | 3.0 - 4.0' FILL: Brown fine to medium sand, trace silt; loose, moist | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 8.0' FILL: Grayish brown fine to medium sand; trace fine gravel, silt and clay; medium dense, wet | NA | Sample collected 163-SB-102-0406 from 5.5-6.0' bgs @ 10:25 |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | 8.0 - 12.0' FILL: Grayish brown fine to coarse sand, trace lenses of clayey silt; medium dense, wet; end of boring at 12.0' | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-102-0810 from 9.5-10.0' bgs @ 10:35 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163, Kellog St, Jersey City, NJ
**PROJECT NO:** 3480100027
**BORING ID:** 163-SB-103
**DATE BEGAN:** 1/19/12
**DATE FINISHED:** 1/19/12
**INSPECTOR:** J. Bacchus
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 12 ft bgs
**GW DEPTH:** 4 ft bgs
**DRILLER:** Doug Myerchin
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 0.6' CONCRETE | NA | |
| | | | | | | 0.6 - 0.9' FILL: Brown fine to medium sand, some silt; loose, dry | | |
| | 1.0 | | | | | 0.9 - 1.4' FILL: Black fine to medium sand, some clinker, trace coal; medium dense, dry | | |
| | 2.0 | | | | | 1.4 - 1.6' FILL: Reddish brown silt, trace fine sand and clay; stiff, dry | | |
| | 3.0 | | | | | 1.6 - 3.0' FILL: Brown fine to medium sand, trace silt; loose, moist from 2.5' | | |
| | | | | | | 3.0 - 4.0' No recovery | | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 12.0' FILL: Brown/grayish brown fine to medium sand, few lenses of silty clay, trace fine gravel and shells; medium dense, wet; end of boring at 12.0' | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | | | |
| | 8.0 | S-3 | NA | 4.0 | | | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | Sample collected 163-SB-103-0810 from 9.5-10.0' bgs @ 11:15 |
| | 11.0 | | | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: JB

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027.4100.43002
**BORING ID:** 163-SB-104
**DATE BEGAN:** 2/2/12
**DATE FINISHED:** 2/2/12
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** NE
**DRILLER:** Doug
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 1.0' FILL: Crushed concrete | NA | |
| | 1.0 | | | | | 1.0 - 1.5' FILL: Crushed red brick | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown fine to coarse sand, fine gravel, glass, wood; loose, moist | | |
| | 3.0 | | | | | 2.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 2.0 | | 4.0 - 4.5' FILL: Dark brown fine to coarse sand, fine gravel, glass, wood; loose, moist | NA | |
| | 5.0 | | | | | 4.5 - 4.8' FILL: Light brown clayey silt; firm, moist | | |
| | 6.0 | | | | | 4.8 - 5.5' FILL: Dark brown fine to coarse sand, fine to medium gravel; loose, moist | | |
| | 7.0 | | | | | 5.5 - 6.0' FILL: Reddish brown silty clay, some fine to medium sand; firm, moist | | |
| | 8.0 | S-3 | NA | 3.5 | | 6.0 - 8.0' No recovery | NA | |
| | 9.0 | | | | | 8.0 - 11.5' FILL: Gray/reddish brown fine to coarse sand, trace silt, trace fine gravel; loose, wet | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | | | |
| | 12.0 | S-4 | NA | 4.0 | | 11.5 - 12.0' No recovery | NA | |
| | 13.0 | | | | | 12.0 - 14.0' FILL: Gray/reddish brown fine to coarse sand, trace silt, trace fine gravel; loose, wet | | |
| | 14.0 | | | | | 14.0 - 14.8' FILL: Dark gray silt; medium dense, moist | | |
| | 15.0 | | | | | 14.8 - 16.0' FILL: Reddish brown/light brown fine sand; medium dense, wet; End of boring at 16.0' | | Sample collected 163-SB-104-1416 from 15.0 - 15.5' bgs @ 9:15 |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027.4100.43002
**BORING ID:** 163-SB-105
**DATE BEGAN:** 2/2/12
**DATE FINISHED:** 2/2/12
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:** NE
**DRILLER:** Doug
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' FILL: Light brown fine to coarse sand, fine to medium gravel; loose, moist | NA | |
| | 1.0 | | | | | 0.5 - 2.0' FILL: Very dark brown fine to coarse, trace fine gravel; dense, moist | | |
| | 2.0 | | | | | 2.0 - 2.5' FILL: Very dark brown fine to coarse, trace fine gravel; dense, moist | | |
| | 3.0 | | | | | 2.5 - 3.5' FILL: Light brown fine to medium sand; loose, moist | | |
| | 4.0 | S-2 | NA | 3.0 | | 3.5 - 4.0' : No recovery | NA | |
| | 5.0 | | | | | 4.0 - 6.0' FILL: Light brown fine to coarse sand; loose, moist | | |
| | 6.0 | | | | | 6.0 - 7.0' FILL: Dark brown fine to coarse sand; loose, moist | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Gray/reddish brown fine to coarse sand, trace fine gravel; loose, wet; reddish brown silt from (9.5-10.0') | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 4.0 | | 12.0 - 16.0' FILL: Dark gray fine to coarse sand; loose, wet; End of boring at 16.0' | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | | | Sample collected 163-SB-105-1416 from 15.5 - 16.0' bgs @ 10:00 |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027.4100.43002
**BORING ID:** 163-SB-106
**DATE BEGAN:** 2/2/12
**DATE FINISHED:** 2/2/12
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 16 ft bgs
**GW DEPTH:**
**DRILLER:** Doug
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.5 | | 0.0 - 0.5' FILL: Concrete slab | NA | |
| | 1.0 | | | | | 0.5 - 1.5' FILL: Crushed concrete and gravel | | |
| | 2.0 | | | | | 1.5 - 2.5' FILL: Dark brown fine to coarse sand, fine to medium gravel; loose, dry | | |
| | 3.0 | | | | | 2.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.0 | | 4.0 - 7.0' FILL: Brown/reddish brown fine to medium sand, trace silt; loose, moist | NA | |
| | 5.0 | | | | | | | |
| | 6.0 | | | | | | | |
| | 7.0 | | | | | 7.0 - 8.0' No recovery | | |
| | 8.0 | S-3 | NA | 3.0 | | 8.0 - 11.0' FILL: Dark brown fine to coarse sand, trace reddish brown silt; loose, wet | NA | |
| | 9.0 | | | | | | | |
| | 10.0 | | | | | | | |
| | 11.0 | | | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | S-4 | NA | 3.0 | | 12.0 - 15.0' FILL: Dark brown fine to coarse sand, trace reddish brown silt; loose, wet | NA | |
| | 13.0 | | | | | | | |
| | 14.0 | | | | | | | |
| | 15.0 | | | | | 15.0 - 16.0' No recovery; End of boring at 16.0' | | Sample collected 163-SB-106-1416 from 14.5 - 15.0' bgs @ 11:25 |
| | 16.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027.4100.43002
**BORING ID:** 163-SB-107
**DATE BEGAN:** 2/2/12
**DATE FINISHED:** 2/2/12
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NE
**DRILLER:** Doug
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' FILL: Dark brown gravel; loose, dry | NA | |
| | | | | | | 0.5 - 3.3' FILL: Light brown fine to coarse sand, fine to medium gravel; dense, moist | | |
| | 1.0 | | | | | | | |
| | 2.0 | | | | | | | |
| | 3.0 | | | | | 3.3 - 3.5' FILL: Reddish brown silt; firm, moist | | Sample collected 163-SB-107-0204 from 3.0 - 3.5' bgs @ 11:45 |
| | | | | | | 3.5 - 4.0' : No recovery; End of boring at 4.0' | | |
| | 4.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027.4100.43002
**BORING ID:** 163-SB-108
**DATE BEGAN:** 2/2/12
**DATE FINISHED:** 2/2/12
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 66010DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** NE
**DRILLER:** Doug
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 0.5' FILL: Crushed concrete | NA | |
| | | | | | | 0.5 - 1.0' FILL: Dark brown fine to coarse sand; loose, dry | | |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Orange/red silt with dark red and black staining; firm, moist | | |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Black fine to coarse sand, fine gravel; dense, moist | | |
| | | | | | | 2.5 - 3.5' FILL: Dark brown fine to medium sand; dense, moist | | |
| | 3.0 | | | | | | | Sample collected 163-SB-108-0204 from 3.0 - 3.5' bgs @ 12:45 |
| | | | | | | 3.5 - 4.0' : No recovery | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 5.0' FILL: Dark brown fine to medium sand, trace orange red silt; dense, wet | NA | |
| | 5.0 | | | | | 5.0 - 6.0' FILL: Reddish brown fine to coarse sand, silt; medium dense, wet | | Sample collected 163-SB-108-0406 from 5.0 - 5.5' bgs @ 13:00 (HOLD) |
| | 6.0 | | | | | 6.0 - 7.5' FILL: Dark brown fine to coarse sand, trace silt; medium dense, wet | | |
| | 7.0 | | | | | | | |
| | | | | | | 7.5 - 8.0' No recovery; End of boring at 8.0' | | |
| | 8.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: NOK

# Honeywell Site SA-6 South

**LOCATION:** Site 163
**PROJECT NO:** 3480100027.4100.43002
**BORING ID:** 163-SB-109
**DATE BEGAN:** 2/2/12
**DATE FINISHED:** 2/2/12
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B
**DRILLING METHOD:**
**DRILL EQUIP:** Hand Auger
**SAMPLING TOOL:** Hand Auger
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NE
**DRILLER:** Doug
**NORTH:**
**EAST:**

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 1.0 | | 0.0 - 0.5' FILL: Gravel | NA | Sample collected 163-SB-109-0002 from 0.5 - 1.0' bgs @ 12:10 |
| | | | | | | 0.5 - 1.0' FILL: Dark brown/black fine to coarse sand, fine gravel; loose, moist | | |
| | 1.0 | | | | | 1.0 - 2.0' No recovery; End of boring at 2.0' | | |
| | 2.0 | | | | | | | |

PREPARED BY: MS
CHECKED BY: NOK

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 163
**PROJECT NO:** 3480130354
**BORING ID:** **163-SB-601**
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 4 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 685066.2085
**EAST:** 601664.0214

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 4.0 | | 0.0 - 0.5' FILL: Grey coarse to fine SAND, medium to fine gravel; loose; moist | | Sample 163-SB-601-S1 from 0.0-0.9 ft bgs @ 0955 |
| | | | | | | 0.5 - 0.8' ASPHALT | 0.1 | |
| | | | | | | 0.8 - 1.0' FILL: Brown coarse to fine SAND, medium to fine gravel; loose; moist | | |
| | 1.0 | | | | | 1.0 - 1.3' ASPHALT | 6.3 | Sample 163-SB-601-S2 from 0.9-3.3 ft bgs @ 1000; EnCore taken from 163-SB-601-S2 @ 1000 |
| | | | | | | 1.3 - 2.0' FILL: Brown coarse to fine SAND, medium to fine gravel; loose; moist, dry from 1.0-1.5 ft bgs | 8.4 | |
| | 2.0 | | | | | 2.0 - 2.8' FILL: Reddish-brown SILT; medium dense; moist | 13.7 | |
| | | | | | | | 4.4 | |
| | 3.0 | | | | | 2.8 - 3.5' FILL: White coarse to fine SAND, medium to fine gravel, possible COPR; loose; dry | 2.1 | |
| | | | | | | 3.5 - 4.0' FILL: Dark brown SILT, some fine sand, medium to fine gravel, coal; dense; moist | | End of boring at 4 ft bgs |
| | 4.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 163
**PROJECT NO:** 3480130354
**BORING ID:** **163-SB-602**
**DATE BEGAN:** 07/24/2013
**DATE FINISHED:** 07/24/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 685143.8569
**EAST:** 601555.6529

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.5 | | 0.0 - 1.5' FILL: Brown to gray coarse to fine SAND, medium to fine gravel; loose; moist | 1.5 | Sample 163-SB-602-ND1 from 0.0-2.0 ft bgs @ 1400 |
| | 1.0 | | | | | | 1.4 | |
| | | | | | | 1.5 - 2.5' FILL: Black coarse to fine SAND, medium to fine gravel, trace coal; loose; dry | 30.3 | |
| | 2.0 | | | | | | 259 | |
| | | | | | | 2.5 - 3.5' FILL: Black coarse to fine SAND, fine gravel, coal, ash; loose; dry | 65.8 | Sample 163-SB-602-ND2 from 2.0-4.0 ft bgs @ 1405; EnCore taken from 163-SB-602-ND2 @ 1405 |
| | 3.0 | | | | | | 28.7 | |
| | | | | | | 3.5 - 4.0' FILL: Reddish-brown SILT; dense; moist | | |
| | 4.0 | S-2 | NA | 3.5 | | 4.0 - 4.8' FILL: Reddish-brown SILT, fine sand, trace fine gravel; loose; moist | 107 | |
| | | | | | | | 284 | |
| | 5.0 | | | | | 4.8 - 5.5' FILL: Dark brown coarse to fine SAND; loose; moist | 84.4 | |
| | | | | | | 5.5 - 6.3' FILL: Reddish-brown clayey SILT; medium dense; moist | 59.2 | |
| | 6.0 | | | | | | 36 | Sample 163-SB-602-NJ2 from 6.0-8.0 ft bgs @ 1410; EnCore taken from 163-SB-602-NJ2 @ 1410 |
| | | | | | | 6.3 - 7.5' FILL: Dark brown coarse to fine SAND, trace silt; loose; moist | 25 | |
| | 7.0 | | | | | | 8.0 | |
| | | | | | | 7.5 - 8.0' FILL: Dark brown coarse to fine SAND, silt, trace shells; loose; moist | | End of boring at 8 ft bgs |
| | 8.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 163
**PROJECT NO:** 3480130354
**BORING ID:** 163-SB-603
**DATE BEGAN:** 07/24/2013
**DATE FINISHED:** 07/24/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 8 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 685179.0113
**EAST:** 601551.8883

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 3.0 | | 0.0 - 1.0' CONCRETE | 1.1 | Sample 163-SB-603-NC1 from 0.0-2.0 ft bgs @ 1420 |
| | 1.0 | | | | | 1.0 - 1.8' FILL: Light brown coarse to fine SAND, medium to fine gravel; loose; moist | 1.3 | |
| | | | | | | | 0.4 | |
| | 2.0 | | | | | 1.8 - 2.5' FILL: Black coarse to fine SAND, medium to fine gravel, coal; loose; moist | 0.1 | |
| | | | | | | 2.5 - 3.0' FILL: Reddish-brown clayey SILT; medium dense; moist | 0.4 | Sample 163-SB-603-NC2 from 2.5-4.5 ft bgs @ 1425; EnCore taken from 163-SB-603-NC2 @ 1425 |
| | 3.0 | | | | | 3.0 - 4.0' No Recovery | 0.2 | |
| | 4.0 | S-2 | NA | 4.0 | | 4.0 - 4.3' FILL: Reddish-brown clayey SILT; medium dense; moist | 0 | |
| | | | | | | 4.3 - 5.0' FILL: Dark brown SAND, silt; loose; moist | 0.2 | |
| | 5.0 | | | | | 5.0 - 8.0' FILL: Reddish-brown SILT, some coarse to fine sand; medium dense; wet | 0.1 | |
| | | | | | | | 0 | |
| | 6.0 | | | | | | 0 | Sample 163-SB-603-NJ1 from 6.0-8.0 ft bgs @ 1430 |
| | | | | | | | 0 | |
| | 7.0 | | | | | | 0 | |
| | | | | | | | 0 | |
| | 8.0 | | | | | | | End of boring at 8 ft bgs |

PREPARED BY: VMW
CHECKED BY: CMP

# Honeywell Study Area - 6 South

**LOCATION:** SA-6S Site 163
**PROJECT NO:** 3480130354
**BORING ID:** **163-SB-604**
**DATE BEGAN:** 07/25/2013
**DATE FINISHED:** 07/25/2013
**INSPECTOR:** M. Senna
**DRILLING CO:** HRS Drilling
**DRILLING METHOD:** Direct Push
**DRILL EQUIP:** Geoprobe 7730DT
**SAMPLING TOOL:** 4-ft Macrocore
**COMPLETION DEPTH:** 2 ft bgs
**GW DEPTH:** NR
**DRILLER:** Justin
**NORTH:** 685238.6133
**EAST:** 601477.9898

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 0.0 | S-1 | NA | 2.0 | | 0.0 - 0.8' FILL: Brown coarse to fine SAND, medium to fine gravel; loose; moist | 0.2 | Sample 163-SB-604-NA1 from 0.0-1.0 ft bgs @ 1010 (2 jars) |
| | 1.0 | | | | | 0.8 - 1.5' FILL: Dark grey SILT, some fine sand; medium dense; moist | 1.6 | |
| | | | | | | 1.5 - 2.0' FILL: Grey coarse to fine SAND, medium to fine gravel; loose; dry | 0.4 | |
| | 2.0 | | | | | | | |

PREPARED BY: VMW
CHECKED BY: CP

# Honeywell Jersey City

**LOCATION:** Site 163
**PROJECT NO:** 3480130377
**BORING ID:** B-1
**DATE BEGAN:** 12-11-15
**DATE FINISHED:** 12-11-15
**INSPECTOR:** M. Senna, A. Eslaminejad
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 20'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** 685241.3
**EAST:** 601466.2

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 12 | 0 | | 10.0 - 12.0' No recovery | NM | Augered to 10' bgs |
| | | | 8 | | | | | |
| | 11.0 | | 5 | | | | | |
| | | | 7 | | | | | |
| | 12.0 | SS2 | 14 | 2.0 | | 12.0 - 14.0' SW: Dark gray fine to coarse SAND; loose, wet | | |
| | | | 19 | | | | | |
| | 13.0 | | 13 | | | | | |
| | | | 14 | | | | | |
| | 14.0 | SS3 | 7 | 2.0 | | 14.0 - 16.0' SM: Dark gray coarse SAND, trace reddish brown silt; loose, wet | | |
| | | | 9 | | | | | |
| | 15.0 | | 12 | | | | | |
| | | | 12 | | | | | |
| | 16.0 | SS4 | 29 | 2.0 | | 16.0 - 18.0' SW: Dark gray fine to coarse SAND; medium dense, wet | | |
| | | | 25 | | | | | |
| | 17.0 | | 32 | | | | | |
| | | | 30 | | | | | |
| | 18.0 | SS5 | 3 | 2.0 | | 18.0 - 18.5' SW: Gray fine to medium SAND | | |
| | | | 7 | | | 18.5 - 20.0' PT: PEAT, gray silt clay with organic fibers. End of boring at 20.0' bgs. | | |
| | 19.0 | | 8 | | | | | |
| | | | 9 | | | | | |
| | 20.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** Site 163
**PROJECT NO:** 3480130377
**BORING ID:** B-2
**DATE BEGAN:** 12-11-15
**DATE FINISHED:** 12-11-15
**INSPECTOR:** A. Eslaminejad
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** 685218.5
**EAST:** 601498.2

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 16.0 | SS1 | 1 | 2.0 | | 16.0 - 16.5' ML: Gray SILT; soft, wet | NM | Augered to 16' bgs |
| | | | 1 | | | 16.5 - 17.5' ML: Black SILT | | |
| | 17.0 | | 1 | | | | | |
| | | | 2 | | | 17.5 - 18.0' PT: PEAT, gray silty clay with fibers. End of boring at 18.0' bgs. | | |
| | 18.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** Site 163
**PROJECT NO:** 3480130377
**BORING ID:** B-3
**DATE BEGAN:** 12-14-15
**DATE FINISHED:** 12-14-15
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 20'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** 685186.7
**EAST:** 601518.6

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 2 | 2.0 | | 14.0 - 15.6' SW: Dark gray fine to coarse SAND; loose, wet | NM | Augered to 14' bgs |
| | | | 2 | | | | | |
| | 15.0 | | 5 | | | | | |
| | | | 4 | | | 15.6 - 16.3' ML: Reddish brown SILT; medium dense, wet | | |
| | 16.0 | SS2 | 5 | 1.75 | | 16.3 - 16.5' OL: Black SILT with organic fibers | | |
| | | | 3 | | | 16.5 - 17.8' OL: Dark gray SILT with organic fibers; medium dense, wet | | |
| | 17.0 | | 4 | | | | | |
| | | | 3 | | | | | |
| | | | | | | 17.8 - 18.0' No recovery. | | |
| | 18.0 | SS3 | 4 | 2.0 | | 18.0 - 20.0' OL: Dark gray SILT with organic fibers; medium dense, wet. End of boring at 20.0' bgs. | | |
| | | | 3 | | | | | |
| | 19.0 | | 4 | | | | | MS spoke with Ari E, said we could stop here; stratum D achieved |
| | | | 5 | | | | | |
| | 20.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** Site 163
**PROJECT NO:** 3480130377
**BORING ID:** B-4
**DATE BEGAN:** 12-14-15
**DATE FINISHED:** 12-14-15
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** 685160.7
**EAST:** 601564

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 3 | 2.0 | | 14.0 - 16.0' SM: Gray fine to coarse SAND and reddish brown SILT, trace shells; loose, wet | NM | Augered to 14' bgs |
| | | | 8 | | | | | |
| | 15.0 | | 9 | | | | | |
| | | | 13 | | | | | |
| | 16.0 | SS2 | 10 | 2.0 | | 16.0 - 17.2' SM: Gray fine to coarse SAND and reddish brown SILT, trace shells; loose, wet | | |
| | | | 14 | | | | | |
| | 17.0 | | 13 | | | | | |
| | | | | | | 17.2 - 17.4' ML: Black SILT | | |
| | | | 13 | | | 17.4 - 18.0' PT: Dark brown PEAT. End of boring at 18.0' bgs. | | |
| | 18.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** Site 163
**PROJECT NO:** 3480130377
**BORING ID:** B-5
**DATE BEGAN:** 12-14-15
**DATE FINISHED:** 12-14-15
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** 685118.2
**EAST:** 601587.2

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 1 | 2.0 | | 14.0 - 15.3' ML: Reddish brown clayey SILT | NM | Augered to 14' bgs |
| | | | 1 | | | | | |
| | 15.0 | | 1 | | | | | |
| | | | | | | 15.3 - 16.0' ML: Black SILT; medium dense, wet | | |
| | | | 2 | | | | | |
| | 16.0 | SS2 | 2 | 2.0 | | 16.0 - 16.1' ML: Black SILT | | |
| | | | | | | 16.1 - 18.0' PT: Dark brown PEAT. End of boring at 18.0' bgs | | |
| | | | 2 | | | | | |
| | 17.0 | | 3 | | | | | |
| | | | 5 | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** Site 163
**PROJECT NO:** 3480130377
**BORING ID:** B-6
**DATE BEGAN:** 12-15-15
**DATE FINISHED:** 12-15-15
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** 685118.2
**EAST:** 601587.2

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 6 | 2.0 | | 14.0 - 14.7' ML: Reddish brown SILT | NM | Augered to 14' bgs |
| | | | 4 | | | | | |
| | | | | | | 14.7 - 15.8' OL: Black SILT, organic fibers from 15.6-15.8 | | |
| | 15.0 | | 4 | | | | | |
| | | | 3 | | | | | |
| | | | | | | 15.8 - 16.0' PT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** DW-1
**DATE BEGAN:** 9-9-13
**DATE FINISHED:** 9-10-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 1 | 2.0 | | 10.0 - 10.5' FILL: Dark brown fine to medium SAND | NM | Augered to 10' bgs |
| | | | 1 | | | 10.5 - 12.0' OL: Black SILT with organics | | |
| | 11.0 | | 2 | | | | | |
| | | | 2 | | | | | |
| | 12.0 | SS2 | 3 | 2.0 | | 12.0 - 15.5' PEAT: Dark brown PEAT | | |
| | | | 3 | | | | | |
| | 13.0 | | 4 | | | | | 10 inch casing for well set at 13.0 ft bgs. |
| | | | 5 | | | | | |
| | 14.0 | SS3 | 3 | 2.0 | | | | |
| | | | 3 | | | | | |
| | 15.0 | | 2 | | | | | |
| | | | 5 | | | 15.5 - 16.0' ML: Dark brown SILT. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** DW-2
**DATE BEGAN:** 9-18-13
**DATE FINISHED:** 9-20-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 7 | 1.5 | | 10.0 - 11.0' SW: Dark brown fine to medium SAND; loose, wet | NM | Augered to 10' bgs |
| | | | 3 | | | | | |
| | 11.0 | | 1 | | | 11.0 - 11.5' ML: Dark brown SILT; medium dense, moist | | |
| | | | 6 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | SS2 | 1 | 2.0 | | 12.0 - 12.3' ML: Dark brown SILT; medium dense, moist | | |
| | | | 1 | | | 12.3 - 12.6' OL: Black SILT/organics | | |
| | 13.0 | | 2 | | | 12.6 - 17.0' PT: Dark brown PEAT | | |
| | | | 3 | | | | | Stopped drilling for day until casing set |
| | 14.0 | SS3 | 1 | 2.0 | | | | 9/20/13- Resumed drilling |
| | | | 2 | | | | | |
| | 15.0 | | 2 | | | | | |
| | | | 5 | | | | | |
| | 16.0 | SS4 | 2 | 2.0 | | | | |
| | | | 3 | | | | | |
| | 17.0 | | 10 | | | 17.0 - 18.0' SW: Dark gray fine to medium SAND; medium dense, wet. End of boring at 18.0' bgs. | | |
| | | | 17 | | | | | |
| | 18.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-10B
**DATE BEGAN:** 8-9-13
**DATE FINISHED:** 8-9-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 2<br>1<br>7<br>11 | 2.0 | | 8.0 - 10.0' FILL: Brown fine to medium SAND, trace silt | NM | Augered to 8' bgs. |
| | 10.0 | SS2 | 8<br>8<br>11<br>14 | 1.75 | | 10.0 - 11.8' SW: Fine to medium SAND | | |
| | | | | | | 11.8 - 12.0' No recovery | | |
| | 12.0 | SS3 | | 2.0 | | 12.0 - 12.5' SW: Fine to medium SAND | | |
| | | | | | | 12.5 - 12.8' OL: Organic SILT | | |
| | 13.0 | | | | | 12.8 - 14.0' PT: PEAT. End of boring at 14.0' bgs | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-13B
**DATE BEGAN:** 8-9-13
**DATE FINISHED:** 8-9-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 2 | 2.0 | | 8.0 - 11.5' SW: Brown fine to medium SAND | NM | Augered to 8' bgs. |
| | | | 1 | | | | | |
| | 9.0 | | 8 | | | | | |
| | | | 10 | | | | | |
| | 10.0 | SS2 | 2 | 1.5 | | | | |
| | | | 2 | | | | | |
| | 11.0 | | 4 | | | | | |
| | | | 6 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | SS3 | 2 | 2.0 | | 12.0 - 12.2' SW: Brown fine to medium SAND | | |
| | | | | | | 12.2 - 13.0' OL: Organic SILTY CLAY | | |
| | | | 3 | | | | | |
| | 13.0 | | 5 | | | 13.0 - 14.0' PT: PEAT. End of boring at 14.0' bgs | | |
| | | | 8 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-16B
**DATE BEGAN:** 8-9-13
**DATE FINISHED:** 8-9-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 1 | 2.0 | | 8.0 - 9.0' ML: Brown sandy SILT | NM | Augered to 8' bgs. |
| | | | 1 | | | | | |
| | 9.0 | | 2 | | | 9.0 - 11.8' SW: Brown fine to medium SAND | | |
| | | | 5 | | | | | |
| | 10.0 | SS2 | 3 | 2.0 | | | | |
| | | | 3 | | | | | |
| | 11.0 | | 4 | | | | | |
| | | | 5 | | | 11.8 - 12.0' OL: Dark brown organic SILT, dry | | |
| | 12.0 | SS3 | 2 | 1.0 | | 12.0 - 12.2' OL: Dark organic SILT | | |
| | | | | | | 12.2 - 14.0' PT: PEAT. End of boring at 14.0' bgs | | |
| | | | 2 | | | | | |
| | 13.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-19B
**DATE BEGAN:** 8-12-13
**DATE FINISHED:** 8-12-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 16 | 1.5 | | 8.0 - 9.5' FILL: Dark brown SAND and SILT | NM | Augered to 8' bgs |
| | | | 13 | | | | | Slight sheen in spoon |
| | 9.0 | | 13 | | | | | |
| | | | 12 | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | SS2 | 27 | 0.5 | | 10.0 - 10.5' FILL: Dark brown SAND and SILT | | |
| | | | 19 | | | 10.5 - 12.0' No recovery | | |
| | 11.0 | | 20 | | | | | |
| | | | 12 | | | | | |
| | 12.0 | SS3 | 13 | 0.5 | | 12.0 - 12.5' FILL: Dark brown SAND and SILT | | |
| | | | 18 | | | 12.5 - 14.0' No recovery | | |
| | 13.0 | | 16 | | | | | |
| | | | 16 | | | | | |
| | 14.0 | SS4 | 7 | 2.0 | | 14.0 - 16.0' PT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | | | 3 | | | | | |
| | 15.0 | | 6 | | | | | |
| | | | 8 | | | | | Sheen on augers when pulled from ground |
| | 16.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-23B
**DATE BEGAN:** 8-12-13
**DATE FINISHED:** 8-12-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 3 | 2.0 | | 8.0 - 12.6' FILL: Dark brown SAND/SILT/GRAVEL | NM | Augered to 8' bgs. |
| | | | 6 | | | | | |
| | 9.0 | | 7 | | | | | |
| | | | 9 | | | | | |
| | 10.0 | SS2 | 5 | 2.0 | | | | |
| | | | 4 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 2 | 2.0 | | | | |
| | | | 2 | | | | | |
| | 13.0 | | 3 | | | 12.6 - 12.9' OL: Black SILT/CLAY, organics<br>12.9 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-26B
**DATE BEGAN:** 8-12-13
**DATE FINISHED:** 8-12-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 1<br>2 | 2.0 | | 10.0 - 11.0' FILL: Brown SAND/SILT | NM | Augered to 10' bgs |
| | 11.0 | | 2 | | | 11.0 - 11.5' OL: Black SILT, organic | | |
| | | | 3 | | | 11.5 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

```
:Last Modified - 1/29/2016

SETUP:  -8      -14     0       0       0
<COL_WIDTH>             237     242     242     242     242     </COL_WIDTH>

GROUP:  E-TEXT

EDIT-TEXT:      SITE INFO.
SA-6 South

EDIT-TEXT:      DATE BEGAN
8-13-13

EDIT-TEXT:      DRILLING CO
B&B Drilling

EDIT-TEXT:      DRILLER
Ed Blewett

EDIT-TEXT:      PROJECT NO.
3480130377

EDIT-TEXT:      DATE FINISHED
8-13-13

EDIT-TEXT:      DRILLING METHOD
HSA 140 lbs/30 inches

EDIT-TEXT:      NORTH
Northing

EDIT-TEXT:      COMPLETION DEPTH
14'

EDIT-TEXT:      INSPECTOR
M. Senna

EDIT-TEXT:      DRILL EQUIP
Gus Pech

EDIT-TEXT:      EAST
Easting

EDIT-TEXT:      GW DEPTH
Not Recorded

EDIT-TEXT:      BORING NO.
EPS-30B

EDIT-TEXT:      SAMPLER
2ft Split Spoon

GROUP-END:
<COL_WIDTH>     160     1028    </COL_WIDTH>

TEXT-COLUMN:    RUN NO.
-8      SS1^
-10     SS2^
-12     SS3^
END-DATA:
<COL_WIDTH>     80      1125    </COL_WIDTH>

TEXT-COLUMN:    SPT BLOWS PER .5'
-8      10^
-8.5    12^
-9      9^
-9.5    7^
-10     8^
-10.5   6^
-11     7^
-11.5   10^
-12     5^
```

```
-12.5   2^
-13     4^
-13.5   6^
END-DATA:
<COL_WIDTH>     80      1125    </COL_WIDTH>

TEXT-COLUMN:    REC, FT
-8      0.0^
-10     1.0^
-12     2.0^
END-DATA:
<COL_WIDTH>     80      1125    </COL_WIDTH>

TEXT-COLUMN:    REMARKS
-8      Augered to 8' bgs^
END-DATA:
<COL_WIDTH>     80      1125    </COL_WIDTH>

SYMBOL-COLUMN:  WATER
END-DATA:
<COL_WIDTH>     104     104     104     104     </COL_WIDTH>

GROUP:  Site Name

EDIT-TEXT:      Site Name
Honeywell Jersey City

GROUP-END:
<COL_WIDTH>     160     1028    </COL_WIDTH>

GROUP:  QA/QC Initials

EDIT-TEXT:      Preparer
CR

EDIT-TEXT:      QA/QC
KK/SH

GROUP-END:
<COL_WIDTH>     160     1028    </COL_WIDTH>

TEXT-COLUMN:    vol-org-pid
-8      NM^
END-DATA:
<COL_WIDTH>     80      1125    </COL_WIDTH>

LITH:   LITHOLOGY
-8      -10
No recovery^1/1/0
-10     -11     FILL
Brown SAND/SILT^1/1/0
-11     -12
No recovery^4/1/0
-12     -12.6   FILL
Brown SAND/SILT^1/1/0
-12.6   -14     PT
Dark brown PEAT. End of boring at 14.0' bgs.^0/1/0
END-DATA:
<COL_WIDTH>     80      80      80      80      869     </COL_WIDTH>

END-LOG:
```

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-33B
**DATE BEGAN:** 8-13-13
**DATE FINISHED:** 8-13-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 3 | 2.0 | | 10.0 - 12.6' FILL: Brown SAND/SILT | NM | Augered to 10' bgs |
| | | | 5 | | | | | |
| | 11.0 | | 5 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | SS2 | 2 | 2.0 | | | | |
| | | | 5 | | | 12.6 - 12.8' OL: Black SILT, organics | | |
| | 13.0 | | 5 | | | 12.8 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 4 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-36B
**DATE BEGAN:** 8-12-13
**DATE FINISHED:** 8-12-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 3 | 2.0 | | 8.0 - 11.5' FILL: Brown SAND and SILT | NM | Refusal at 3.0'- moved 3' east<br>Refusal at 3.5'- moved 3' north<br>Augered to 8' bgs |
| | | | 5 | | | | | |
| | 9.0 | | 6 | | | | | |
| | | | 9 | | | | | |
| | 10.0 | SS2 | 4 | 1.5 | | | | |
| | | | 5 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | 4 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | SS3 | 2 | 2.0 | | 12.0 - 12.8' FILL: Brown SAND and SILT | | |
| | | | 4 | | | | | |
| | | | | | | 12.8 - 12.9' OL: Black SILT, organics | | |
| | 13.0 | | 4 | | | 12.9 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-43B
**DATE BEGAN:** 9-25-13
**DATE FINISHED:** 9-25-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 15.5'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | SS1 | 3 | 1.0 | | 9.5 - 10.5' SW: Dark brown fine to medium SAND; loose, wet | 0.0 | Augered to 9.5' bgs |
| | 10.0 | | 3 | | | | | |
| | | | 12 | | | 10.5 - 11.5' No recovery | | |
| | 11.0 | | 16 | | | | | |
| | | SS2 | 12 | 1.5 | | 11.5 - 13.0' SW: Dark brown fine to medium SAND; loose, wet | | |
| | 12.0 | | 12 | | | | | |
| | | | 10 | | | | | |
| | 13.0 | | 10 | | | 13.0 - 13.5' No recovery | | |
| | | SS3 | 2 | 2.0 | | 13.5 - 15.5' PEAT: Dark brown PEAT. End of boring at 15.5' bgs. | | |
| | 14.0 | | 3 | | | | | |
| | | | 6 | | | | | |
| | 15.0 | | 10 | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-47B
**DATE BEGAN:** 9-25-13
**DATE FINISHED:** 9-25-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 3 | 1.0 | | 10.0 - 11.0' SW: Dark brown fine to medium SAND, loose, wet | NM | Augered to 10' bgs |
| | | | 3 | | | | | |
| | 11.0 | | 2 | | | 11.0 - 12.0' No recovery | | |
| | | | 3 | | | | | |
| | 12.0 | SS2 | 3 | 2.0 | | 12.0 - 12.7' SW: Dark brown fine to medium SAND, loose, wet | | |
| | | | 2 | | | | | |
| | | | | | | 12.7 - 12.9' OL: Black SILT with organics | | |
| | 13.0 | | 3 | | | 12.9 - 14.0' PEAT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-49B
**DATE BEGAN:** 9-25-13
**DATE FINISHED:** 9-25-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 5 | 2.0 | | 10.0 - 12.0' SW: Dark brown/gray fine to coarse SAND; loose, wet | NM | Augered to 10' bgs |
| | | | 7 | | | | | |
| | 11.0 | | 6 | | | | | |
| | | | 7 | | | | | |
| | 12.0 | SS2 | 6 | 2.0 | | 12.0 - 13.5' SW: Dark brown/gray fine to coarse SAND; loose, wet | | |
| | | | 4 | | | | | |
| | 13.0 | | 4 | | | | | |
| | | | 6 | | | 13.5 - 14.0' PEAT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-4B
**DATE BEGAN:** 8-9-13
**DATE FINISHED:** 8-9-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 4 | 2.0 | | 8.0 - 10.0' FILL: Brown fine SAND, trace silt | NM | Odors at 1-3'<br>Rubber debris at 2-4'<br>Augered to 8' bgs. |
| | | | 2 | | | | | |
| | 9.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | 10.0 - 11.8' CL: Dark brown silty CLAY | | |
| | | | 1 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 1 | 2.0 | | 11.8 - 12.3' OL: Organic SILT | | |
| | | | 2 | | | 12.3 - 14.0' PT: PEAT. End of boring at 14.0' bgs. | | |
| | 13.0 | | 3 | | | | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-53B
**DATE BEGAN:** 9-26-13
**DATE FINISHED:** 9-26-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 3 | 1.5 | | 10.0 - 11.5' FILL: Brown/gray fine to coarse SAND, loose, wet | NM | Augered to 10' bgs |
| | | | 2 | | | | | |
| | 11.0 | | 1 | | | | | |
| | | | 5 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | SS2 | 2 | 2.0 | | 12.0 - 12.1' OL: Black SILT with organics | | |
| | | | 1 | | | 12.1 - 14.0' PEAT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | 13.0 | | 3 | | | | | |
| | | | 3 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** EPS-7B
**DATE BEGAN:** 8-9-13
**DATE FINISHED:** 8-9-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 7<br>5 | 2.0 | | 8.0 - 9.0' SW: Brown fine to medium SAND | NM | Augered to 8' bgs. |
| | 9.0 | | 2<br>9 | | | 9.0 - 10.0' ML: Brown SILT with some clay | | |
| | 10.0 | SS2 | 13<br>16 | 0.0 | | 10.0 - 12.0' No Recovery | | |
| | 11.0 | | 12 | | | | | |
| | 12.0 | SS3 | 16<br>2 | 2.0 | | 12.0 - 12.5' OL: Organic SILT | | |
| | 13.0 | | 2<br>4 | | | 12.5 - 14.0' PT: PEAT. End of boring at 14.0' bgs. | | |
| | 14.0 | | 5 | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H1-1B
**DATE BEGAN:** 8-5-13
**DATE FINISHED:** 8-5-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 6.0 | SS1 | 12 | 2.0 | | 6.0 - 8.0' FILL: Greenish gray chromium FILL, COPR | NM | Augered to 6' bgs |
| | | | 24 | | | | | |
| | 7.0 | | 40 | | | | | |
| | | | 82 | | | | | |
| | 8.0 | SS2 | 10 | 2.0 | | 8.0 - 10.8' FILL: Greenish gray FILL material, COPR | | |
| | | | 8 | | | | | |
| | 9.0 | | 5 | | | | | |
| | | | 3 | | | | | |
| | 10.0 | SS3 | 1 | 2.0 | | | | |
| | | | 1 | | | | | |
| | 11.0 | | 2 | | | 10.8 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | | | 3 | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H12-16B
**DATE BEGAN:** 9-27-13
**DATE FINISHED:** 9-27-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA -140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 15.0 ft bgs
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | SS1 | 1 | 2.0 | | 13.0 - 14.2' ML: Dark gray SILT; medium dense, wet | NM | Augered to 13' bgs |
| | | | 1 | | | | | |
| | 14.0 | | 1 | | | 14.2 - 14.5' ML: Black SILT; dense, wet | | |
| | | | 4 | | | 14.5 - 15.0' PT: Dark brown PEAT. End of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H12-21B
**DATE BEGAN:** 9-26-13
**DATE FINISHED:** 9-26-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 4<br>6 | 1.0 | | 10.0 - 11.0' SW: Gray/black fine to medium SAND; loose, wet | NM | Augered to 10' bgs |
| | 11.0 | | 6<br>6 | | | 11.0 - 12.0' No recovery | | |
| | 12.0 | SS2 | 1<br>1 | 2.0 | | 12.0 - 14.0' ML: Light brown SILT; medium dense, wet | | |
| | 13.0 | | 1<br>1 | | | | | Lens of black from 13.0-13.25' bgs |
| | 14.0 | SS3 | WOR<br>WOR | 2.0 | | 14.0 - 15.0' ML: Light brown SILT; medium dense, wet | | |
| | 15.0 | | WOH<br>2 | | | 15.0 - 17.0' ML: Black SILT; dense, wet | | |
| | 16.0 | SS4 | 1<br>3 | 2.0 | | | | |
| | 17.0 | | 4<br>8 | | | 17.0 - 18.0' PT: Dark brown PEAT. End of boring at 18.0' bgs. | | |
| | 18.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H12-3B
**DATE BEGAN:** 9-30-13
**DATE FINISHED:** 9-30-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | SS1 | WOH | 2.0 | | 12.0 - 13.0' ML: Light brown SILT; medium dense, moist | NM | Augered to 12' bgs |
| | | | 1 | | | | | |
| | 13.0 | | 1 | | | 13.0 - 14.5' ML: Dark brown SILT; medium dense, moist | | |
| | | | 1 | | | | | |
| | 14.0 | | 1 | 2.0 | | | | |
| | | | 1 | | | 14.5 - 15.5' OL: Dark gray SILT with organics; medium dense, moist | | |
| | 15.0 | | 1 | | | | | |
| | | | 3 | | | 15.5 - 16.0' PEAT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H12-8B
**DATE BEGAN:** 9-27-13
**DATE FINISHED:** 9-27-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | SS1 | | 2.0 | | 13.0 - 14.0' ML: Dark gray SILT; medium dense, wet | NM | Augered to 13' bgs |
| | 14.0 | | | | | 14.0 - 14.5' ML: Black SILT; medium dense, wet | | |
| | | | | | | 14.5 - 15.0' PEAT: Dark brown PEAT. End of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H13-20B
**DATE BEGAN:** 9-26-13
**DATE FINISHED:** 9-26-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | SS1 | WOR | 2.0 | | 12.0 - 13.0' ML: Light brown SILT; medium dense, wet | NM | Augered to 12' bgs |
| | | | 1 | | | | | |
| | 13.0 | | 2 | | | 13.0 - 14.5' ML: Gray SILT; medium dense, wet | | |
| | | | 1 | | | | | |
| | 14.0 | SS2 | 1 | 2.0 | | | | |
| | | | 1 | | | 14.5 - 15.0' ML: Dark gray SILT; medium dense, wet | | |
| | 15.0 | | 2 | | | 15.0 - 15.5' ML: Black SILT; medium dense, wet | | |
| | | | 2 | | | 15.5 - 16.0' PT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H13-3B
**DATE BEGAN:** 9-27-13
**DATE FINISHED:** 9-27-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | SS1 | 2 | 2.0 | | 13.0 - 14.0' ML: Light brown SILT; medium dense, wet | NM | Augered to 13' bgs |
| | | | 2 | | | | | |
| | 14.0 | | 2 | | | 14.0 - 16.0' ML: Black SILT; medium dense, wet | | |
| | | | 3 | | | | | |
| | 15.0 | SS2 | 1 | 2.0 | | | | |
| | | | 1 | | | | | |
| | 16.0 | | 6 | | | 16.0 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | | | 6 | | | | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H13-5B
**DATE BEGAN:** 9-30-13
**DATE FINISHED:** 9-30-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | | 2.0 | | 14.0 - 14.5' ML: Black SILT | NM | Augered to 14' bgs |
| | | | | | | 14.5 - 15.5' OL: Dark gray SILT with organics | | |
| | 15.0 | | | | | | | |
| | | | | | | 15.5 - 16.0' PEAT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | 16.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H13-8B
**DATE BEGAN:** 9-30-13
**DATE FINISHED:** 9-30-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 2 | 2.0 | | 14.0 - 14.5' ML: Gray SILT; medium dense, wet | NM | Augered to 14' bgs |
| | | | 1 | | | 14.5 - 17.5' OL: Dark gray SILT with organics; medium dense, moist | | |
| | 15.0 | | 1 | | | | | |
| | | | 2 | | | | | |
| | 16.0 | SS2 | 2 | 2.0 | | | | |
| | | | 2 | | | | | |
| | 17.0 | | 4 | | | | | |
| | | | 5 | | | 17.5 - 17.7' PEAT: Dark brown PEAT | | |
| | 18.0 | | | | | 17.7 - 18.0' SW: Dark gray fine to medium SAND, medium dense, moist. End of boring 18.0' bgs. | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H14-21B
**DATE BEGAN:** 10-1-13
**DATE FINISHED:** 10-1-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | SS1 | 1 | 2.0 | | 13.0 - 14.0' SM: Dark brown fine SAND, some silt | NM | Augered to 13' bgs |
| | | | 3 | | | | | |
| | 14.0 | | 8 | | | 14.0 - 14.3' ML: Light brown SILT | | |
| | | | | | | 14.3 - 14.5' COPR | | COPR |
| | | | 6 | | | 14.5 - 15.5' ML: Black SILT | | |
| | 15.0 | SS2 | 2 | 2.0 | | | | |
| | | | 2 | | | 15.5 - 16.5' OL: Dark gray SILT with organics | | |
| | 16.0 | | 3 | | | | | |
| | | | 4 | | | 16.5 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H1-4B
**DATE BEGAN:** 8-5-13
**DATE FINISHED:** 8-5-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 8 | 2.0 | | 8.0 - 10.2' FILL: Greenish gray FILL, COPR | NM | Augered to 8' bgs |
| | | | 12 | | | | | |
| | 9.0 | | 8 | | | | | |
| | | | 8 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | | | | 10.2 - 10.4' OL: Black, organic CLAY/SILT | | |
| | | | 1 | | | 10.4 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 11.0 | | 1 | | | | | |
| | | | 2 | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H1-9B
**DATE BEGAN:** 8-5-13
**DATE FINISHED:** 8-5-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 7 | 2.0 | | 8.0 - 10.5' FILL: Greenish gray FILL, COPR | NM | Augered to 8' bgs |
| | | | 6 | | | | | |
| | 9.0 | | 7 | | | | | |
| | | | 6 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | 1 | | | 10.5 - 10.7' ML: Black SILT/CLAY | | |
| | | | | | | 10.7 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H2-11B
**DATE BEGAN:** 8-6-13
**DATE FINISHED:** 8-6-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 19 | 2.0 | | 8.0 - 11.0' FILL: FILL, COPR | NM | Augered to 8' bgs |
| | | | 28 | | | | | |
| | 9.0 | | 24 | | | | | |
| | | | 21 | | | | | |
| | 10.0 | SS2 | 10 | 2.0 | | | | |
| | | | 4 | | | | | |
| | 11.0 | | 5 | | | 11.0 - 11.5' OL: Black SILT/CLAY, organics | | |
| | | | 6 | | | 11.5 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H2-3B
**DATE BEGAN:** 8-5-13
**DATE FINISHED:** 8-5-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 16 | 2.0 | | 8.0 - 10.8' FILL: FILL, COPR | NM | Augered to 8' bgs |
| | | | 11 | | | | | |
| | 9.0 | | 9 | | | | | |
| | | | 9 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | 2 | | | | | |
| | 11.0 | | 2 | | | 10.8 - 11.5' OL: Black organic SILT/CLAY | | |
| | | | 3 | | | 11.5 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H2-6B
**DATE BEGAN:** 8-6-13
**DATE FINISHED:** 8-6-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 6 | 1.5 | | 8.0 - 9.5' FILL: FILL, COPR | NM | Augered to 8' bgs |
| | | | 19 | | | | | |
| | 9.0 | | 20 | | | | | |
| | | | 9 | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | SS2 | 1 | 1.7 | | 10.0 - 10.5' FILL: FILL, COPR | | |
| | | | 2 | | | 10.5 - 10.8' OL: Black SILT, organic | | |
| | 11.0 | | 2 | | | 10.8 - 11.7' PT: Dark brown PEAT | | |
| | | | 3 | | | | | |
| | 12.0 | | | | | 11.7 - 12.0' No recovery. End of boring at 12.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H3-12B
**DATE BEGAN:** 8-6-13
**DATE FINISHED:** 8-6-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 6 | 2.0 | | 8.0 - 11.0' FILL: FILL, COPR | NM | Augered to 8' bgs |
| | | | 13 | | | | | |
| | 9.0 | | 11 | | | | | |
| | | | 9 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | 2 | | | | | |
| | 11.0 | | 1 | | | 11.0 - 11.6' OL: Black SILT/CLAY, organics | | |
| | | | 2 | | | 11.6 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H3-3B
**DATE BEGAN:** 8-6-13
**DATE FINISHED:** 8-6-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 3 | 2.0 | | 8.0 - 11.2' FILL: FILL, COPR | NM | Augered to 8' bgs |
| | | | 4 | | | | | |
| | 9.0 | | 4 | | | | | |
| | | | 2 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | 1 | | | | | |
| | 11.0 | | 1 | | | | | |
| | | | 3 | | | 11.2 - 12.0' OL: Black SILT/CLAY, organics | | |
| | 12.0 | SS3 | 2 | 2.0 | | 12.0 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 2 | | | | | |
| | 13.0 | | 4 | | | | | |
| | | | 4 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H3-7B
**DATE BEGAN:** 8-6-13
**DATE FINISHED:** 8-6-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 21 | 0.0 | | 8.0 - 10.0' No recovery | NM | Petroleum odor while augering from 0-3'. Sample collected at 9:30. |
| | | | 7 | | | | | Augered to 8' bgs. |
| | 9.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 10.0 | SS2 | 10 | 1.5 | | 10.0 - 11.3' SW: Reddish brown fine SAND | | |
| | | | 6 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | | | | 11.3 - 11.5' SM: Dark brown SILT/SAND | | |
| | | | 2 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | SS3 | 2 | 2.0 | | 12.0 - 12.5' SM: Dark brown SILT/SAND | | |
| | | | 2 | | | 12.5 - 12.8' OL: Black SILT, organic | | |
| | 13.0 | | 4 | | | 12.8 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H4-10B
**DATE BEGAN:** 8-7-13
**DATE FINISHED:** 8-7-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 3 | 2.0 | | 8.0 - 12.5' FILL: FILL, COPR | NM | Augered to 8' bgs. |
| | | | 3 | | | | | |
| | 9.0 | | 3 | | | | | |
| | | | 8 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | 2 | | | | | |
| | 11.0 | | 3 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 1 | 2.0 | | | | |
| | | | 2 | | | 12.5 - 12.7' OL: Black SILT/CLAY, organics | | |
| | 13.0 | | 4 | | | 12.7 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H4-3B
**DATE BEGAN:** 8-7-13
**DATE FINISHED:** 8-7-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 6 | 1.0 | | 8.0 - 9.0' FILL | NM | Augered to 8' bgs.<br>Sheen in auger spoils |
| | | | 3 | | | | | |
| | 9.0 | | 13 | | | 9.0 - 10.0' No recovery | | |
| | | | 8 | | | | | |
| | 10.0 | SS2 | 3 | 2.0 | | 10.0 - 11.5' FILL | | |
| | | | 3 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | 11.5 - 12.0' OL: Black SILT/CLAY, organics | | |
| | 12.0 | SS3 | 5 | 2.0 | | 12.0 - 13.0' FILL: Fine to coarse SAND | | |
| | | | 5 | | | | | |
| | 13.0 | | 5 | | | 13.0 - 13.2' OL: Black SILT/CLAY, organics | | |
| | | | 5 | | | 13.2 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H5-2B
**DATE BEGAN:** 8-8-13
**DATE FINISHED:** 8-8-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 2 | 1.0 | | 8.0 - 9.0' FILL: Light brown fine to medium SAND | NM | Augered to 8' bgs. |
| | | | 4 | | | | | |
| | 9.0 | | 3 | | | 9.0 - 10.0' No recovery | | |
| | | | 4 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | 10.0 - 10.5' SW: SAND/SILT/CLAY | | |
| | | | 1 | | | 10.5 - 11.4' OL: Organic SILT | | |
| | 11.0 | | 2 | | | | | |
| | | | 2 | | | 11.4 - 12.0' PT: PEAT. End of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H5-5B
**DATE BEGAN:** 8-8-13
**DATE FINISHED:** 8-8-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 5 | 2.0 | | 8.0 - 10.0' FILL: Brown fine to medium SAND | NM | Augered to 8' bgs. |
| | | | 4 | | | | | |
| | 9.0 | | 4 | | | | | |
| | | | 4 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | 10.0 - 10.5' OL: Black organic SILT | | |
| | | | 1 | | | 10.5 - 12.0' PT: PEAT. End of boring at 12.0' bgs. | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H6-10B
**DATE BEGAN:** 8-7-13
**DATE FINISHED:** 8-7-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 3 | 1.5 | | 8.0 - 9.5' FILL | NM | Augered to 8' bgs |
| | | | 7 | | | | | |
| | 9.0 | | 4 | | | | | |
| | | | 2 | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | SS2 | WR | 0.5 | | 10.0 - 10.5' FILL: FILL, COPR | | |
| | | | 1 | | | 10.5 - 12.0' No recovery | | |
| | 11.0 | | 8 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 1 | 2.0 | | 12.0 - 12.8' FILL: FILL, COPR | | |
| | | | 2 | | | | | |
| | 13.0 | | 3 | | | 12.8 - 13.0' OL: Black SILT/CLAY, organics | | |
| | | | | | | 13.0 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 3 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H6-3B
**DATE BEGAN:** 8-7-13
**DATE FINISHED:** 8-7-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 2 | 2.0 | | 8.0 - 11.8' FILL: Brown SAND and SILT | NM | Augered to 8' bgs. |
| | | | 1 | | | | | |
| | 9.0 | | 5 | | | | | |
| | | | 5 | | | | | |
| | 10.0 | SS2 | 2 | 2.0 | | | | |
| | | | 7 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 2 | 2.0 | | 11.8 - 13.0' OL: Black SILT/CLAY, organics | | |
| | | | 3 | | | | | |
| | 13.0 | | 7 | | | 13.0 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 6 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H6-5B
**DATE BEGAN:** 8-8-13
**DATE FINISHED:** 8-8-13
**INSPECTOR:** K. Kacperowski
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 1<br>3 | 2.0 | | 8.0 - 10.0' FILL: Brown SILTY CLAY, some sand | NM | Augered to 8' bgs. |
| | 9.0 | | 1<br>6 | | | | | |
| | 10.0 | SS2 | 3<br>3 | 2.0 | | 10.0 - 11.5' SW: Brown fine to medium SAND | | |
| | 11.0 | | 3<br>5 | | | 11.5 - 12.0' OL: SANDY SILT (organic silt in tip) | | |
| | 12.0 | SS3 | 1<br>1 | 1.0 | | 12.0 - 12.3' OL: Black organic SILT<br>12.3 - 13.0' PT: PEAT | | |
| | 13.0 | | 3<br>4 | | | 13.0 - 14.0' No recovery. End of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H7-11B
**DATE BEGAN:** 9-24-13
**DATE FINISHED:** 9-24-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 4 | 2.0 | | 10.0 - 13.5' SW: Black/gray fine to medium SAND | NM | Augered to 10' bgs |
| | | | 4 | | | | | |
| | 11.0 | | 3 | | | | | |
| | | | 2 | | | | | |
| | 12.0 | SS2 | 5 | 2.0 | | | | |
| | | | 3 | | | | | |
| | 13.0 | | 3 | | | | | |
| | | | 2 | | | 13.5 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H7-3B
**DATE BEGAN:** 9-24-13
**DATE FINISHED:** 9-24-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 3 | 1.5 | | 10.0 - 11.5' SM: Dark brown fine to medium SAND, trace silt; loose, wet | NM | Augered to 10' bgs |
| | | | 5 | | | | | |
| | 11.0 | | 7 | | | | | |
| | | | 9 | | | 11.5 - 12.0' No recovery | | |
| | 12.0 | SS2 | 2 | 2.0 | | 12.0 - 13.5' SM: Dark brown fine to medium SAND, trace silt; loose, wet | | |
| | | | 2 | | | | | |
| | 13.0 | | 2 | | | | | |
| | | | 3 | | | 13.5 - 14.5' OL: Black SILT with organics present; medium dense, moist | | |
| | 14.0 | SS3 | 5 | 2.0 | | | | |
| | | | 4 | | | 14.5 - 16.0' PEAT: Dark brown PEAT. End of boring at 16.0' bgs. | | |
| | 15.0 | | 6 | | | | | |
| | | | 8 | | | | | |
| | 16.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H7-6B
**DATE BEGAN:** 9-24-13
**DATE FINISHED:** 9-24-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 2 | 1.0 | | 10.0 - 11.0' SW: Brown fine to coarse SAND, some fine gravel; loose, wet | NM | Augered to 10' bgs |
| | | | 4 | | | | | |
| | 11.0 | | 6 | | | 11.0 - 12.0' No recovery | | |
| | | | 4 | | | | | |
| | 12.0 | SS2 | 1 | 2.0 | | 12.0 - 13.3' SW: Brown fine to coarse SAND, some fine gravel; loose, wet | | |
| | | | 1 | | | | | |
| | 13.0 | | 2 | | | | | |
| | | | 2 | | | 13.3 - 13.6' OL: Black Silt with organics | | |
| | 14.0 | | | | | 13.6 - 14.0' PEAT: Dark brown PEAT. End of boring at 14.0' bgs. | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H8-11B
**DATE BEGAN:** 8-29-13
**DATE FINISHED:** 8-29-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 1<br>2 | 2.0 | | 10.0 - 11.2' SW: Grayish brown fine to medium SAND | NM | Augered to 10' bgs |
| | 11.0 | | 2 | | | 11.2 - 11.4' OL: Black organic SILT | | |
| | | | 3 | | | 11.4 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |
| | 12.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H8-3B
**DATE BEGAN:** 8-29-13
**DATE FINISHED:** 8-29-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 12'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 6 | 2.0 | | 8.0 - 11.7' SW: Grayish brown fine to medium SAND; wet | NM | Augered to 8' bgs |
| | | | 2 | | | | | |
| | 9.0 | | 3 | | | | | |
| | | | 4 | | | | | |
| | 10.0 | SS2 | 1 | 2.0 | | | | |
| | | | 1 | | | | | |
| | 11.0 | | 2 | | | | | |
| | | | 3 | | | 11.7 - 11.8' OL: Black SILT, organics | | |
| | 12.0 | | | | | 11.8 - 12.0' PT: Dark brown PEAT. End of boring at 12.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H8-6B
**DATE BEGAN:** 8-28-13
**DATE FINISHED:** 8-28-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 7 | 2.0 | | 8.0 - 11.0' FILL: Grayish/brown fine to coarse SAND; loose, wet | NM | Augered to 8' bgs |
| | | | 7 | | | | | |
| | 9.0 | | 7 | | | | | |
| | | | 8 | | | | | |
| | 10.0 | SS2 | 9 | 1.0 | | | | |
| | | | 8 | | | | | |
| | 11.0 | | 5 | | | 11.0 - 12.0' No recovery | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 2 | 2.0 | | 12.0 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 1 | | | | | |
| | 13.0 | | 3 | | | | | |
| | | | 2 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H9-3B
**DATE BEGAN:** 8-29-13
**DATE FINISHED:** 8-29-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 12 | 1.0 | | 10.0 - 11.0' SW: Grayish brown fine to medium SAND | NM | Augered to 10' bgs |
| | | | 11 | | | | | |
| | 11.0 | | 8 | | | 11.0 - 12.0' No recovery | | |
| | | | 10 | | | | | |
| | 12.0 | SS2 | 2 | 2.0 | | 12.0 - 12.5' SW: Grayish brown fine to medium SAND | | |
| | | | 2 | | | 12.5 - 12.8' OL: Black SILT/organics | | |
| | 13.0 | | 7 | | | 12.8 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | | | 8 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** H9-7B
**DATE BEGAN:** 8-29-13
**DATE FINISHED:** 8-29-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Gus Pech
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 8.0 | SS1 | 4 | 1.5 | | 8.0 - 9.5' SW: Grayish brown fine to medium SAND; wet | NM | Augered to 8' bgs |
| | | | 9 | | | | | |
| | 9.0 | | 9 | | | | | |
| | | | 17 | | | 9.5 - 10.0' No recovery | | |
| | 10.0 | SS2 | 5 | 1.0 | | 10.0 - 11.0' SW: Grayish brown fine to medium SAND; wet | | |
| | | | 6 | | | | | |
| | 11.0 | | 4 | | | 11.0 - 12.0' No recovery | | |
| | | | 3 | | | | | |
| | 12.0 | SS3 | 2 | 2.0 | | 12.0 - 12.1' SW: Grayish brown fine to medium SAND; wet | | |
| | | | | | | 12.1 - 12.4' OL: Black organic SILT | | |
| | | | 3 | | | 12.4 - 14.0' PT: Dark brown PEAT. End of boring at 14.0' bgs. | | |
| | 13.0 | | 3 | | | | | |
| | | | 5 | | | | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/SH

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-12B
**DATE BEGAN:** 10-1-13
**DATE FINISHED:** 10-1-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | SS1 | 2 | 2.0 | | 13.0 - 14.0' SW: Dark brown fine SAND; loose, wet | NM | Augered to 13' bgs |
| | | | 1 | | | | | |
| | 14.0 | | 1 | | | 14.0 - 15.0' ML: Black SILT; medium dense, moist | | |
| | | | 2 | | | | | |
| | 15.0 | SS2 | 3 | 2.0 | | 15.0 - 16.0' SW: Dark brown fine to medium SAND; loose, wet | | |
| | | | 2 | | | | | |
| | 16.0 | | 3 | | | 16.0 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | | | 4 | | | | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-15B
**DATE BEGAN:** 10-1-13
**DATE FINISHED:** 10-1-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 18'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 2 | 2.0 | | 14.0 - 14.5' SW: Dark gray fine to medium SAND; loose, wet | NM | Augered to 14' bgs |
| | | | 2 | | | 14.5 - 16.5' OL: Gray SILT with organics; medium dense, moist | | |
| | 15.0 | | 3 | | | | | |
| | | | 5 | | | | | |
| | 16.0 | SS2 | 3 | 2.0 | | | | |
| | | | 3 | | | 16.5 - 17.2' PEAT: Dark brown PEAT | | |
| | 17.0 | | 5 | | | | | |
| | | | 5 | | | 17.2 - 18.0' SM: Dark gray fine to medium SAND, some silt; loose, wet. End of boring at 18.0' bgs. | | |
| | 18.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-19B
**DATE BEGAN:** 10-3-13
**DATE FINISHED:** 10-3-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | 1 | 2.0 | | 15.0 - 16.7' OL: Gray SILT with organics | NM | Augered to 15' bgs |
| | | | 2 | | | | | |
| | 16.0 | | 4 | | | | | |
| | | | 3 | | | | | |
| | | | | | | 16.7 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-22B
**DATE BEGAN:** 10-3-13
**DATE FINISHED:** 10-3-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | 1 | 2.0 | | 15.0 - 15.7' ML: Black SILT | NM | Augered to 15' bgs |
| | | | 2 | | | 15.7 - 16.2' OL: Gray SILT with organics | | |
| | 16.0 | | 3 | | | 16.2 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | | | 6 | | | | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-25B
**DATE BEGAN:** 10-3-13
**DATE FINISHED:** 10-3-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | | 2.0 | | 15.0 - 15.6' ML: Black SILT | NM | Augered to 15' bgs |
| | | | | | | 15.6 - 15.9' OL: Gray SILT with organics | | |
| | 16.0 | | | | | 15.9 - 17.0' PT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-29B
**DATE BEGAN:** 10-4-13
**DATE FINISHED:** 10-4-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | 6 | 2.0 | | 15.0 - 15.5' ML: Brown and gray SILT | NM | Augered to 15' bgs |
| | | | 6 | | | 15.5 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | 16.0 | | 8 | | | | | |
| | | | 10 | | | | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-32B
**DATE BEGAN:** 10-4-13
**DATE FINISHED:** 10-4-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | 1 | 2.0 | | 15.0 - 15.2' ML: Dark gray SILT | NM | Augered to 15' bgs |
| | | | 2 | | | 15.2 - 16.2' PEAT: Dark brown PEAT | | |
| | 16.0 | | 3 | | | | | |
| | | | 5 | | | 16.2 - 17.0' SW: Dark brown fine SAND with organics. End of boring at 17.0' bgs. | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-35B
**DATE BEGAN:** 10-4-13
**DATE FINISHED:** 10-4-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 16'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 14.0 | SS1 | 6 | 2.0 | | 14.0 - 14.5' ML: Dark brown SILT | NM | Augered to 14' bgs |
| | | | 5 | | | 14.5 - 15.8' ML: Black SILT | | |
| | 15.0 | | 4 | | | | | |
| | | | 3 | | | | | |
| | 16.0 | | | | | 15.8 - 16.0' PEAT: Dark brown PEAT. End of boring at 16.0' bgs. | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** SA-6 South
**PROJECT NO:** 3480130377
**BORING ID:** WPS-39B
**DATE BEGAN:** 10-4-13
**DATE FINISHED:** 10-4-13
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** B-61
**SAMPLING TOOL:** 2ft Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 15.0 | SS1 | 1 | 2.0 | | 15.0 - 15.5' ML: Gray SILT | NM | Augered to 15' bgs |
| | | | 1 | | | 15.5 - 16.3' ML: Black SILT | | |
| | 16.0 | | 2 | | | | | |
| | | | 3 | | | 16.3 - 17.0' PEAT: Dark brown PEAT. End of boring at 17.0' bgs. | | |
| | 17.0 | | | | | | | |

PREPARED BY: JA
CHECKED BY: NW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-167
**DATE BEGAN:** 9-9-14
**DATE FINISHED:** 9-9-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 1 | 1.0 | | 11.0 - 11.5' SM: Dark brown/reddish brown fine SAND, some silt; medium dense, wet | NM | Augered to 11' bgs<br>Elevation 7.75' |
| | | | 2 | | | 11.5 - 12.0' ML: Dark brown/reddish brown CLAYEY SILT | | |
| | 12.0 | | 1 | | | 12.0 - 13.0' No recovery | | |
| | | | 4 | | | | | |
| | 13.0 | SS2 | 6 | 1.25 | | 13.0 - 13.3' ML: Dark brown SILT | | Sample taken from 13.0-13.5 at 11:40 |
| | | | | | | 13.3 - 13.4' Light brown/bluish green. Possible COPR | | DPC test positive |
| | | | 5 | | | 13.4 - 13.5' ML: Dark brown/black SILT | | |
| | | | | | | 13.5 - 14.3' OL: Black SILT with organics. Peat in tip | | |
| | 14.0 | | 4 | | | | | |
| | | | | | | 14.3 - 15.0' No recovery. End of boring at 15.0' bgs. | | |
| | | | 6 | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134 | **PROJECT NO:** 3480130377 | **BORING ID:** 134-SB-168

**DATE BEGAN:** 9-9-14 | **DATE FINISHED:** 9-10-14 | **INSPECTOR:** M. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** HSA 140 lbs/30 inches | **DRILL EQUIP:** Bret 22

**SAMPLING TOOL:** 2' Split Spoon | **COMPLETION DEPTH:** 14' | **GW DEPTH:** Not Recorded

**DRILLER:** Ed Blewett | **NORTH:** - | **EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 8 | 1.0 | | 10.0 - 11.0' SM: Brown fine to medium SAND and SILT | NM | Augered to 10' bgs<br>Elevation 7.43' |
| | | | 6 | | | | | |
| | 11.0 | | 4 | | | 11.0 - 12.0' No recovery | | |
| | | | 5 | | | | | |
| | 12.0 | SS2 | 3 | 1.75 | | 12.0 - 12.8' SM: Brown fine to medium SAND and SILT | | |
| | | | 8 | | | | | |
| | | | | | | 12.8 - 13.0' ML: Dark brown/very light brown (greenish tint) interlayered SILT. Possible COPR | | Sample from 12.75-13.25 at 7:30 |
| | 13.0 | | 4 | | | 13.0 - 13.8' OL: Black SILT with organics | | DPC = very light pink |
| | | | 4 | | | | | |
| | | | | | | 13.8 - 14.0' No recovery. End of boring at 14.0' bgs. | | |
| | 14.0 | | | | | | | |

PREPARED BY: CR

CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-169
**DATE BEGAN:** 9-9-14
**DATE FINISHED:** 9-9-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 9 | 0.5 | | 11.0 - 11.5' SM: Dark brown fine SAND, trace silt | NM | Augered to 11' bgs<br>Elevation 8.5' |
| | | | 10 | | | 11.5 - 13.0' No recovery | | |
| | 12.0 | | 7 | | | | | |
| | | | 6 | | | | | |
| | 13.0 | SS2 | 7 | 2.0 | | 13.0 - 13.8' SM: Dark brown fine to medium SAND, trace silt | | |
| | | | 5 | | | | | |
| | | | | | | 13.8 - 14.0' ML: Brown SILT; very hard | | |
| | 14.0 | | 3 | | | 14.0 - 14.3' ML: Black/brown SILT with possible COPR | | Sample from 14.0-14.5 at 13:30 |
| | | | | | | 14.3 - 14.5' OL: Gray SILT with organics | | DPC test negative |
| | | | 4 | | | 14.5 - 15.0' OL: Black SILT with organics. End of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-170
**DATE BEGAN:** 9-10-14
**DATE FINISHED:** 9-10-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 5 | 1.25 | | 11.0 - 12.3' SM: Dark brown fine SAND, trace silt | NM | Augered to 11' bgs<br>Elevation 7.26' |
| | | | 3 | | | | | |
| | 12.0 | | 3 | | | | | |
| | | | | | | 12.3 - 13.0' No recovery | | |
| | | | 4 | | | | | |
| | 13.0 | SS2 | 3 | 2.0 | | 13.0 - 13.9' SM: Dark brown fine SAND, trace silt | | |
| | | | 1 | | | | | |
| | 14.0 | | 2 | | | 13.9 - 14.3' ML: Dark brown/black layered SILT | | Sample collected from 14.0-14.5 at 10:20<br><br>DPC negative |
| | | | 2 | | | 14.3 - 15.0' OL: Dark gray/black SILT with organics. End of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-171
**DATE BEGAN:** 9-10-14
**DATE FINISHED:** 9-10-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 8 | 1.75 | | 11.0 - 12.8' SW: Brownish gray coarse SAND | NM | Augered to 11' bgs<br>Elevation 8.03' |
| | | | 13 | | | | | |
| | 12.0 | | 12 | | | | | |
| | | | 15 | | | | | |
| | | | | | | 12.8 - 13.0' No recovery | | |
| | 13.0 | SS2 | 15 | 2.0 | | 13.0 - 14.5' SW: Brownish gray coarse SAND | | |
| | | | 14 | | | | | |
| | 14.0 | | 16 | | | | | |
| | | | 32 | | | 14.5 - 15.0' SM: Grayish brown coarse SAND and SILT | | |
| | 15.0 | SS3 | 10 | 1.0 | | 15.0 - 16.0' SW: Grayish brown coarse SAND | | |
| | | | 23 | | | | | |
| | 16.0 | | 23 | | | 16.0 - 17.0' No recovery. End of boring at 17.0' bgs. | | B&B will move 3' NE and drill another boring to depth. |
| | | | 22 | | | | | |
| | 17.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-171b
**DATE BEGAN:** 9-10-14
**DATE FINISHED:** 9-10-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 13'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | | | | | | | |
| | | SS1 | 5 | 2.0 | | 11.0 - 13.0' SW: Grayish brown fine to coarse SAND. End of boring at 13.0' bgs. | NM | Augered to 11' bgs<br><br>Elevation 7.94' |
| | | | 5 | | | | | |
| | 12.0 | | 9 | | | | | |
| | | | 10 | | | | | |
| | 13.0 | | | | | | | B&B cannot get hole to stay open due to running sand. Pulled rods, moved to 507. |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-171c
**DATE BEGAN:** 9-11-14
**DATE FINISHED:** 9-11-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 17'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 5 | 1.5 | | 11.0 - 12.5' SW: Grayish brown coarse SAND | NM | Augered to 11' bgs<br>Elevation 8.0'<br>B&B will drill with light mud in auger to keep sand from leaving. |
| | | | 7 | | | | | |
| | 12.0 | | 11 | | | | | |
| | | | 15 | | | 12.5 - 13.0' No recovery | | |
| | 13.0 | SS2 | 27 | 2.0 | | 13.0 - 17.0' SW: Grayish brown coarse SAND. End of boring at 17.0' bgs. | | |
| | | | 23 | | | | | |
| | 14.0 | | 22 | | | | | Sample collected from 14.0-14.5 at 8:30 |
| | | | 20 | | | | | |
| | 15.0 | SS3 | 12 | 2.0 | | | | |
| | | | 15 | | | | | |
| | 16.0 | | 15 | | | | | |
| | | | 17 | | | | | |
| | 17.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134 | **PROJECT NO:** 3480130377 | **BORING ID:** 134-SB-172

**DATE BEGAN:** 9-10-14 | **DATE FINISHED:** 9-11-14 | **INSPECTOR:** M. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** HSA 140 lbs/30 inches | **DRILL EQUIP:** Bret 22

**SAMPLING TOOL:** 2' Split Spoon | **COMPLETION DEPTH:** 15' | **GW DEPTH:** Not Recorded

**DRILLER:** Ed Blewett | **NORTH:** - | **EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | WOR | 2.0 | | 11.0 - 12.0' SW: Grayish brown fine to coarse SAND | NM | Augered to 11' bgs<br>Elevation 7.66' |
| | | | 1 | | | | | |
| | 12.0 | | 3 | | | 12.0 - 13.0' ML: Dark brown/reddish brown CLAYEY SILT, some coarse sand | | |
| | | | 3 | | | | | |
| | 13.0 | SS2 | 8 | 1.75 | | 13.0 - 13.8' SM: Brown SILT and fine SAND | | |
| | | | 3 | | | | | |
| | 14.0 | | 2 | | | 13.8 - 14.2' ML: Brown SILT and green COPR | | Sample collected from 13.75-14.25 at 7:30<br><br>DPC positive |
| | | | | | | 14.2 - 14.4' ML: Brown/black layered SILT | | |
| | | | 3 | | | 14.4 - 14.8' OL: Black SILT with organics | | |
| | 15.0 | | | | | 14.8 - 15.0' No recovery. End of boring at 15.0' bgs. | | |

PREPARED BY: CR

CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-173
**DATE BEGAN:** 9-11-14
**DATE FINISHED:** 9-11-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | WOR | 2.0 | | 11.0 - 13.5' ML: Dark brown CLAYEY SILT | NM | Augered to 11' bgs<br>Elevation 7.9' |
| | | | 1 | | | | | |
| | 12.0 | | 1 | | | | | |
| | | | 1 | | | | | |
| | 13.0 | SS2 | 3 | 2.0 | | | | |
| | | | 2 | | | 13.5 - 13.8' ML: Brown and grayish green layered SILT (possible COPR) | | Sample collected from 13.5-14.0 at 9:40 |
| | | | | | | 13.8 - 14.0' ML: Light/dark brown interlayered SILT | | DPC positive |
| | 14.0 | | 1 | | | 14.0 - 15.0' OL: Black SILT with organics, peat in tip. End of boring at 15.0' bgs. | | |
| | | | 3 | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-175
**DATE BEGAN:** 9-11-14
**DATE FINISHED:** 9-11-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 14.5'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | SS1 | 1 | 1.5 | | 10.5 - 11.5' SM: Dark brown fine SAND and SILT | NM | Augered to 10.5' bgs<br>Elevation 7.2' |
| | 11.0 | | 4 | | | | | |
| | | | 9 | | | 11.5 - 12.0' SM: Reddish brown fine SAND and SILT | | |
| | 12.0 | | 8 | | | 12.0 - 12.5' No recovery | | |
| | | SS2 | 9 | 1.0 | | 12.5 - 13.3' SM: Reddish brown/black fine SAND, trace silt | | Sample from 12.75-13.25 at 11:30<br>DPC negative |
| | 13.0 | | 5 | | | | | |
| | | | | | | 13.3 - 13.5' OL: Black SILT with organics | | |
| | | | 4 | | | 13.5 - 14.5' No recovery. End of boring at 14.5' bgs. | | |
| | 14.0 | | 4 | | | | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** 134-SB-176
**DATE BEGAN:** 9-11-14
**DATE FINISHED:** 9-11-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** -
**EAST:** -

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 10.0 | SS1 | 2 | 2.0 | | 10.0 - 12.0' ML: Dark brown CLAYEY SILT | NM | Augered to 10' bgs<br>Elevation 7.0' |
| | | | 1 | | | | | |
| | 11.0 | | 1 | | | | | |
| | | | 1 | | | | | |
| | 12.0 | SS2 | 2 | 2.0 | | 12.0 - 12.5' ML: Light brown/dark brown layered SILT | | Sample from (12.0-12.5) at 13:40<br><br>DPC negative |
| | | | 1 | | | 12.5 - 13.8' OL: Black SILT with organics | | |
| | 13.0 | | 1 | | | | | |
| | | | 3 | | | | | |
| | 14.0 | | | | | 13.8 - 14.0' PT: PEAT. End of boring at 14.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: KK/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** A002
**DATE BEGAN:** 8-20-14
**DATE FINISHED:** 8-20-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 10.5'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | SS1 | 2 | 1.25 | | 6.5 - 7.8' ML: Reddish brown CLAYEY SILT | NM | Augered to 6.5' bgs |
| | 7.0 | | 2 | | | | | |
| | | | 1 | | | | | |
| | | | | | | 7.8 - 8.5' No recovery | | |
| | 8.0 | | 1 | | | | | |
| | | SS2 | 1 | 2.0 | | 8.5 - 9.3' ML: Reddish brown CLAYEY SILT | | |
| | 9.0 | | 1 | | | | | |
| | | | | | | 9.3 - 10.5' OL: Black SILT with organics. End of boring at 10.5' bgs. | | |
| | | | 1 | | | | | |
| | 10.0 | | 1 | | | | | |

PREPARED BY: CR
CHECKED BY: NW/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** A004
**DATE BEGAN:** 8-20-14
**DATE FINISHED:** 8-20-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15.5'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | SS1 | 4 | 1.5 | | 11.5 - 12.8' SW: Reddish brown fine SAND | NM | Augered to 11.5' bgs |
| | 12.0 | | 2 | | | | | |
| | | | 4 | | | | | |
| | | | | | | 12.8 - 13.0' SC: Reddish brown CLAYEY SAND | | |
| | 13.0 | | 2 | | | 13.0 - 13.5' No recovery | | |
| | | SS2 | 3 | 1.25 | | 13.5 - 13.9' SW: Reddish brown fine SAND | | |
| | 14.0 | | 5 | | | 13.9 - 14.8' PT: Dark brown PEAT | | |
| | | | 5 | | | | | |
| | | | | | | 14.8 - 15.5' No recovery. End of boring at 15.5' bgs. | | |
| | 15.0 | | 6 | | | | | Will move 2' N to try and get better recovery |

PREPARED BY: CR
CHECKED BY: NW/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** A004R
**DATE BEGAN:** 8-20-14
**DATE FINISHED:** 8-20-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 13.0 | SS1 | 1 | 1.5 | | 13.0 - 13.5' SM: Reddish brown fine SAND, trace silt | NM | Augered to 13' bgs<br><br>Sample from 13.0-13.5 at 11:40 |
| | | | 2 | | | 13.5 - 14.0' OL: Black SILT with organics | | |
| | 14.0 | | 1 | | | 14.0 - 14.5' PT: Dark brown PEAT | | |
| | | | 4 | | | 14.5 - 15.0' No recovery. End of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** A006
**DATE BEGAN:** 8-20-14
**DATE FINISHED:** 8-20-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 14'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 12.0 | SS1 | 3<br>2 | 2.0 | | 12.0 - 12.8' SW: Dark brown fine SAND | NM | Augered to 12' bgs |
| | 13.0 | | 1 | | | 12.8 - 13.3' ML: Dark brown CLAYEY SILT | | |
| | | | 4 | | | 13.3 - 13.8' ML: Dark brown stratified SILT with COPR; dry | | Sample collected from 13.25-13.75 at 14:30<br>DPC test positive |
| | 14.0 | | | | | 13.8 - 14.0' ML: Dark brown CLAYEY SILT. End of boring at 14.0' bgs. | | |

PREPARED BY: CR
CHECKED BY: NW/VW

# Honeywell Jersey City

**LOCATION:** Site 134 | **PROJECT NO:** 3480130377 | **BORING ID:** A007

**DATE BEGAN:** 8-21-14 | **DATE FINISHED:** 8-21-14 | **INSPECTOR:** M. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** HSA 140 lbs/30 inches | **DRILL EQUIP:** Bret 22

**SAMPLING TOOL:** 2' Split Spoon | **COMPLETION DEPTH:** 15' | **GW DEPTH:** Not Recorded

**DRILLER:** Ed Blewett | **NORTH:** Northing | **EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 5 | 1.0 | | 11.0 - 12.0' SM: Brownish gray fine to coarse SAND, clayey silt in tip | NM | Augered to 11' bgs |
| | | | 6 | | | | | |
| | 12.0 | | 4 | | | 12.0 - 13.0' No recovery | | |
| | | | 5 | | | | | |
| | 13.0 | SS2 | 4 | 2.0 | | 13.0 - 13.5' SM: Brownish gray fine to coarse SAND, clayey silt in tip | | |
| | | | 2 | | | 13.5 - 13.8' ML: Brown/black SILT, trace fine sand | | Sample collected from 13.5-14.0 at 9:40 |
| | 14.0 | | 2 | | | 13.8 - 15.0' OL: Black SILT with organics, peat in tip. End of boring at 15.0' bgs. | | DPC test negative |
| | | | 3 | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR

CHECKED BY: NW/VW

# Honeywell Jersey City

**LOCATION:** Site 134 | **PROJECT NO:** 3480130377 | **BORING ID:** A009

**DATE BEGAN:** 8-21-14 | **DATE FINISHED:** 8-21-14 | **INSPECTOR:** M. Senna

**DRILLING CO:** B&B Drilling | **DRILLING METHOD:** HSA 140 lbs/30 inches | **DRILL EQUIP:** Bret 22

**SAMPLING TOOL:** 2' Split Spoon | **COMPLETION DEPTH:** 15' | **GW DEPTH:** Not Recorded

**DRILLER:** Ed Blewett | **NORTH:** Northing | **EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 5 | 1.7 | | 11.0 - 11.6' SM: Brownish gray fine to coarse SAND, trace silt | NM | Augered to 11' bgs |
| | | | 3 | | | 11.6 - 12.7' ML: Reddish brown clayey SILT | | |
| | 12.0 | | 1 | | | | | |
| | | | 3 | | | | | |
| | | | | | | 12.7 - 13.0' No recovery | | |
| | 13.0 | SS2 | WOR | 1.5 | | 13.0 - 13.3' ML: Reddish brown clayey SILT | | |
| | | | | | | 13.3 - 13.8' ML: Light brown SILT | | |
| | | | 5 | | | | | Sample collected from 13.5-14.0 at 8:15 |
| | | | | | | | | DPC test positive |
| | | | | | | 13.8 - 14.0' Very light brown/yellow COPR | | |
| | 14.0 | | 5 | | | 14.0 - 14.5' OL: Gray SILT with organics | | |
| | | | 3 | | | | | |
| | | | | | | 14.5 - 15.0' No recovery. End of boring at 15.0' bgs. | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR

CHECKED BY: NW/VW

# Honeywell Jersey City

**LOCATION:** Site 134
**PROJECT NO:** 3480130377
**BORING ID:** A012
**DATE BEGAN:** 8-21-14
**DATE FINISHED:** 8-21-14
**INSPECTOR:** M. Senna
**DRILLING CO:** B&B Drilling
**DRILLING METHOD:** HSA 140 lbs/30 inches
**DRILL EQUIP:** Bret 22
**SAMPLING TOOL:** 2' Split Spoon
**COMPLETION DEPTH:** 15'
**GW DEPTH:** Not Recorded
**DRILLER:** Ed Blewett
**NORTH:** Northing
**EAST:** Easting

| ELEV (FT.) | DEPTH (FT.) | RUN NO. | SPT BLOWS PER 0.5' | REC (FT.) | PROFILE | DESCRIPTION | VOLATILE ORGANIC VAPORS (PPM) | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | 11.0 | SS1 | 6 | 2.0 | | 11.0 - 12.0' SW: Brownish gray fine SAND | NM | Augered to 11' bgs |
| | | | 4 | | | | | |
| | 12.0 | | 2 | | | 12.0 - 13.8' ML: Reddish brown CLAYEY SILT | | |
| | | | 1 | | | | | |
| | 13.0 | SS2 | 2 | 2.0 | | | | |
| | | | 3 | | | | | Sample collected from 13.5-14.0 at 14:15 |
| | | | | | | 13.8 - 14.0' Greenish brown/pale green COPR | | DPC test positive |
| | 14.0 | | 2 | | | 14.0 - 15.0' OL: Dark gray/black SILT with organics. End of boring at 15.0' bgs. | | |
| | | | 2 | | | | | |
| | 15.0 | | | | | | | |

PREPARED BY: CR
CHECKED BY: NW/VW

# APPENDIX I

# DEWATERING LOGS

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 10/17/13 | | | 1.5 | 0.45 | 19.49 | 19,040 | 19,040 | Test Operation: Potable Water |
| 10/18/13 | | | 1.0 | 19.49 | 27.50 | 8,010 | 27,050 | |
| 10/22/13 | | | 4.0 | 27.50 | 85.74 | 58,240 | 85,290 | |
| 10/23/13 | | | 2.0 | 85.74 | 116.87 | 31,130 | 116,420 | |
| 10/24/13 | | | 1.3 | 116.87 | 135.20 | 18,330 | 134,750 | |
| 10/28/13 | | | 4.5 | 135.20 | 200.88 | 65,680 | 200,430 | |
| 10/29/13 | | | 4.0 | 200.88 | 258.53 | 57,650 | 258,080 | |
| 11/01/13 | | | 4.3 | 258.53 | 300.34 | 41,810 | 299,890 | |
| 11/04/13 | | | 4.8 | 300.34 | 368.43 | 68,090 | 367,980 | |
| 11/05/13 | | | 4.3 | 368.43 | 408.77 | 40,340 | 408,320 | |
| 11/06/13 | | | 1.5 | 408.77 | 425.89 | 17,120 | 425,440 | |
| 11/07/13 | | | 1.0 | 425.89 | 453.88 | 27,990 | 453,430 | |
| 11/08/13 | | | 1.0 | 453.88 | 478.10 | 24,220 | 477,650 | |
| 11/12/13 | | | 4.5 | 478.10 | 526.82 | 48,720 | 526,370 | |
| 11/14/13 | | | 1.3 | 526.82 | 556.26 | 29,440 | 555,810 | |
| 11/18/13 | | | 5.0 | 556.26 | 619.36 | 63,100 | 618,910 | |
| 11/21/13 | | | 4.0 | 619.36 | 652.91 | 33,550 | 652,460 | |
| 11/26/13 | | | 6.0 | 652.91 | 719.80 | 66,890 | 719,350 | |
| 11/27/13 | | | 6.0 | 719.80 | 784.49 | 64,690 | 784,040 | |
| 11/29/13 | | | 5.0 | 784.49 | 840.47 | 55,980 | 840,020 | |
| 12/02/13 | | | 6.5 | 840.47 | 923.11 | 82,640 | 922,660 | |
| 12/03/13 | | | 7.0 | 923.11 | 1,011.32 | 88,210 | 1,010,870 | |
| 12/05/13 | | | 8.0 | 1,011.32 | 1,103.37 | 92,050 | 1,102,920 | |
| 12/06/13 | | | 4.0 | 1,103.37 | 1,143.07 | 39,700 | 1,142,620 | |
| 12/09/13 | | | 6.5 | 1,143.07 | 1,224.23 | 81,160 | 1,223,780 | |
| 12/10/13 | | | 6.0 | 1,224.23 | 1,286.03 | 61,800 | 1,285,580 | |
| 12/13/13 | | | 8.0 | 1,286.03 | 1,374.91 | 88,880 | 1,374,460 | |
| 12/16/13 | | | 8.0 | 1,374.91 | 1,485.04 | 110,130 | 1,484,590 | |
| 12/17/13 | | | 6.0 | 1,485.04 | 1,551.22 | 66,180 | 1,550,770 | |
| 12/18/13 | | | 7.0 | 1,551.22 | 1,628.26 | 77,040 | 1,627,810 | |
| 12/19/13 | | | 4.5 | 1,628.26 | 1,678.47 | 50,210 | 1,678,020 | |
| 12/20/13 | | | 5.0 | 1,678.47 | 1,732.93 | 54,460 | 1,732,480 | |
| 12/23/13 | | | 8.0 | 1,732.93 | 1,894.96 | 162,030 | 1,894,510 | |
| 12/24/13 | | | 7.0 | 1,894.96 | 1,989.84 | 94,880 | 1,989,390 | |
| 12/27/13 | | | 5.0 | 1,989.84 | 2,054.25 | 64,410 | 2,053,800 | |
| 12/30/13 | | | 8.0 | 2,054.25 | 2,147.46 | 93,210 | 2,147,010 | |
| 12/31/13 | | | 8.0 | 2,147.46 | 2,244.54 | 97,080 | 2,244,090 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 01/02/14 | | | 8.0 | 2,244.54 | 2,368.54 | 124,000 | 2,368,090 | |
| 01/06/14 | | | 8.0 | 2,368.54 | 2,485.40 | 116,860 | 2,484,950 | |
| 01/09/14 | | | 8.0 | 2,485.40 | 2,567.15 | 81,750 | 2,566,700 | |
| 01/10/14 | | | 8.0 | 2,567.15 | 2,635.97 | 68,820 | 2,635,520 | |
| 01/13/14 | | | 6.0 | 2,635.97 | 2,719.26 | 83,290 | 2,718,810 | |
| 01/14/14 | | | 8.0 | 2,719.26 | 2,864.73 | 145,470 | 2,864,280 | |
| 01/15/14 | | | 8.0 | 2,864.73 | 2,981.21 | 116,480 | 2,980,760 | |
| 01/16/14 | | | 8.0 | 2,981.21 | 3,111.28 | 130,070 | 3,110,830 | |
| 01/17/14 | | | 8.0 | 3,111.28 | 3,190.67 | 79,390 | 3,190,220 | |
| 01/20/14 | | | 8.0 | 3,190.67 | 3,297.59 | 106,920 | 3,297,140 | |
| 01/21/14 | | | 4.0 | 3,297.59 | 3,338.21 | 40,620 | 3,337,760 | |
| 01/27/14 | | | 8.0 | 3,338.21 | 3,438.26 | 100,050 | 3,437,810 | |
| 01/31/14 | | | 8.0 | 3,438.26 | 3,516.69 | 78,430 | 3,516,240 | |
| 02/04/14 | | | 8.0 | 3,516.69 | 3,628.15 | 111,460 | 3,627,700 | |
| 02/07/14 | | | 8.0 | 3,628.15 | 3,733.31 | 105,160 | 3,732,860 | |
| 02/11/14 | | | 8.0 | 3,733.31 | 3,854.45 | 121,140 | 3,854,000 | |
| 02/12/14 | | | 2.0 | 3,854.45 | 3,884.29 | 29,840 | 3,883,840 | |
| 02/14/14 | | | 6.0 | 3,884.29 | 3,933.69 | 49,400 | 3,933,240 | |
| 02/15/14 | | | 8.0 | 3,933.69 | 4,032.69 | 99,000 | 4,032,240 | |
| 02/18/14 | | | 8.0 | 4,032.69 | 4,123.91 | 91,220 | 4,123,460 | |
| 02/20/14 | | | 8.0 | 4,123.91 | 4,251.33 | 127,420 | 4,250,880 | |
| 02/21/14 | | | 8.0 | 4,251.33 | 4,412.37 | 161,040 | 4,411,920 | |
| 02/22/14 | | | 8.0 | 4,412.37 | 4,536.78 | 124,410 | 4,536,330 | |
| 02/24/14 | | | 8.0 | 4,536.78 | 4,660.60 | 123,820 | 4,660,150 | |
| 02/25/14 | | | 8.0 | 4,660.60 | 4,850.50 | 189,900 | 4,850,050 | |
| 02/26/14 | | | 8.0 | 4,850.50 | 4,970.69 | 120,190 | 4,970,240 | |
| 03/04/14 | | | 8.0 | 4,970.69 | 5,064.73 | 94,040 | 5,064,280 | |
| 03/05/14 | | | 8.0 | 5,064.73 | 5,170.07 | 105,340 | 5,169,620 | |
| 03/10/14 | | | 8.0 | 5,170.07 | 5,299.77 | 129,700 | 5,299,320 | |
| 03/11/14 | | | 8.0 | 5,299.77 | 5,368.86 | 69,090 | 5,368,410 | |
| 03/12/14 | | | 8.0 | 5,368.86 | 5,433.63 | 64,770 | 5,433,180 | |
| 03/17/14 | | | 8.0 | 5,433.63 | 5,590.00 | 156,370 | 5,589,550 | |
| 03/18/14 | | | 8.0 | 5,590.00 | 5,690.00 | 100,000 | 5,689,550 | |
| 03/19/14 | | | 8.0 | 5,690.00 | 5,849.46 | 159,460 | 5,849,010 | |
| 03/20/14 | | | 8.0 | 5,849.46 | 5,912.45 | 62,990 | 5,912,000 | |
| 03/21/14 | | | 8.0 | 5,912.45 | 6,024.94 | 112,490 | 6,024,490 | |
| 03/24/14 | | | 8.0 | 6,024.94 | 6,125.64 | 100,700 | 6,125,190 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 03/25/14 | | | 8.0 | 6,125.64 | 6,175.64 | 50,000 | 6,175,190 | |
| 03/26/14 | | | 8.0 | 6,175.64 | 6,248.89 | 73,250 | 6,248,440 | |
| 03/27/14 | | | 8.0 | 6,248.89 | 6,310.44 | 61,550 | 6,309,990 | |
| 03/28/14 | | | 8.0 | 6,310.44 | 6,380.45 | 70,010 | 6,380,000 | |
| 03/31/14 | | | 8.0 | 6,380.45 | 6,575.85 | 195,400 | 6,575,400 | |
| 04/01/14 | | | 8.0 | 6,575.85 | 6,717.81 | 141,960 | 6,717,360 | |
| 04/02/14 | | | 8.0 | 6,717.81 | 6,951.38 | 233,570 | 6,950,930 | |
| 04/03/14 | | | 8.0 | 6,951.38 | 7,050.47 | 99,090 | 7,050,020 | |
| 04/04/14 | | | 8.0 | 7,050.47 | 7,173.74 | 123,270 | 7,173,290 | |
| 04/05/14 | | | 8.0 | 7,173.74 | 7,250.14 | 76,400 | 7,249,690 | |
| 04/08/14 | | | 8.0 | 7,250.14 | 7,452.80 | 202,660 | 7,452,350 | |
| 04/09/14 | | | 8.0 | 7,452.80 | 7,538.06 | 85,260 | 7,537,610 | |
| 04/10/14 | | | 8.0 | 7,538.06 | 7,687.85 | 149,790 | 7,687,400 | |
| 04/11/14 | | | 8.0 | 7,687.85 | 7,810.35 | 122,500 | 7,809,900 | |
| 04/14/14 | | | 6.0 | 7,810.35 | 7,883.23 | 72,880 | 7,882,780 | |
| 04/15/14 | | | 6.0 | 7,883.23 | 7,948.35 | 65,120 | 7,947,900 | |
| 04/16/14 | | | 8.0 | 7,948.35 | 8,036.99 | 88,640 | 8,036,540 | |
| 04/17/14 | | | 8.0 | 8,036.99 | 8,120.52 | 83,530 | 8,120,070 | |
| 04/18/14 | | | 8.0 | 8,120.52 | 8,241.81 | 121,290 | 8,241,360 | |
| 04/19/14 | | | 8.0 | 8,241.81 | 8,416.26 | 174,450 | 8,415,810 | |
| 04/21/14 | | | 8.0 | 8,416.26 | 8,503.96 | 87,700 | 8,503,510 | |
| 04/22/14 | | | 8.0 | 8,503.96 | 8,649.60 | 145,640 | 8,649,150 | |
| 04/23/14 | | | 8.0 | 8,649.60 | 8,775.22 | 125,620 | 8,774,770 | |
| 04/24/14 | | | 8.0 | 8,775.22 | 8,877.66 | 102,440 | 8,877,210 | |
| 04/25/14 | | | 8.0 | 8,877.66 | 8,949.22 | 71,560 | 8,948,770 | |
| 04/26/14 | 7:00 | 15:30 | 8.0 | 8,949.22 | 9,030.24 | 81,020 | 9,029,790 | |
| 04/27/14 | 7:00 | 15:30 | 0.0 | 9,030.24 | 9,030.24 | 0 | 9,029,790 | |
| 04/28/14 | 7:00 | 15:30 | 8.0 | 9,030.24 | 9,133.26 | 103,020 | 9,132,810 | |
| 04/29/14 | 7:00 | 17:00 | 9.0 | 9,133.26 | 9,371.72 | 238,460 | 9,371,270 | |
| 04/30/14 | 7:00 | 15:30 | 0.0 | 9,371.72 | 9,371.72 | 0 | 9,371,270 | |
| 05/01/14 | 7:00 | 19:00 | 12.0 | 9,371.72 | 9,550.80 | 179,080 | 9,550,350 | |
| 05/02/14 | 7:00 | 18:30 | 23.5 | 9,665.35 | 9,775.14 | 224,340 | 9,774,690 | Includes system operation through 05/01/12 |
| 05/03/14 | 7:00 | 15:30 | 21.0 | 9,921.23 | 10,020.57 | 245,430 | 10,020,120 | Includes system operation through 05/02/13 |
| 05/05/14 | 7:00 | 16:55 | 37.0 | 10,377.22 | 10,584.99 | 564,420 | 10,584,540 | Includes system operation through 05/04/14 |
| 05/06/14 | 7:00 | 15:30 | 9.5 | 10,584.99 | 10,825.62 | 240,630 | 10,825,170 | |
| 05/07/14 | 7:00 | 15:30 | 7.5 | 10,825.62 | 11,006.06 | 180,440 | 11,005,610 | |
| 05/08/14 | 7:50 | 12:30 | 4.5 | 11,006.06 | 11,112.94 | 106,880 | 11,112,490 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 05/09/14 | 7:40 | 14:15 | 6.0 | 1,112.94 | 11,253.32 | 140,380 | 11,252,870 | |
| 05/12/14 | 6:55 | 14:03 | 7.0 | 11,253.32 | 11,439.87 | 186,550 | 11,439,420 | |
| 05/13/14 | 7:10 | 15:00 | 7.0 | 11,439.87 | 11,600.00 | 160,130 | 11,599,550 | |
| 05/14/14 | 8:00 | 15:05 | 6.5 | 11,600.00 | 11,712.86 | 112,860 | 11,712,410 | |
| 05/15/14 | 9:30 | 15:30 | 5.5 | 11,712.86 | 11,810.42 | 97,560 | 11,809,970 | |
| 05/16/14 | 8:25 | 15:00 | 6.0 | 11,810.42 | 11,885.46 | 75,040 | 11,885,010 | |
| 05/18/14 | 9:45 | 13:00 | 2.8 | 11,885.46 | 11,960.68 | 75,220 | 11,960,230 | |
| 05/19/14 | 8:30 | 16:00 | 7.0 | 11,960.68 | 12,098.90 | 138,220 | 12,098,450 | |
| 05/20/14 | 9:15 | 16:30 | 7.0 | 12,098.90 | 12,188.74 | 89,840 | 12,188,290 | |
| 05/21/14 | 10:00 | 15:30 | 5.0 | 12,188.74 | 12,262.55 | 73,810 | 12,262,100 | |
| 05/22/14 | 8:10 | 16:05 | 7.5 | 12,262.55 | 12,329.43 | 66,880 | 12,328,980 | |
| 05/23/14 | 7:10 | 14:42 | 7.5 | 12,329.43 | 12,405.66 | 76,230 | 12,405,210 | |
| 05/24/14 | 7:30 | 13:00 | 5.0 | 12,405.66 | 12,482.60 | 76,940 | 12,482,150 | |
| 05/25/14 | 14:45 | 17:30 | 2.0 | 12,482.60 | 12,527.46 | 44,860 | 12,527,010 | |
| 05/27/14 | 7:30 | 14:10 | 5.5 | 12,527.46 | 12,662.13 | 134,670 | 12,661,680 | |
| 05/28/14 | 13:00 | 15:00 | 2.0 | 12,662.13 | 12,696.70 | 34,570 | 12,696,250 | |
| 05/29/14 | 8:25 | 15:15 | 7.0 | 12,696.70 | 12,809.54 | 112,840 | 12,809,090 | |
| 05/30/14 | 8:00 | 15:12 | 7.0 | 12,809.54 | 12,906.92 | 97,380 | 12,906,470 | |
| 06/02/14 | 8:30 | 15:00 | 6:30 | 12,906.92 | 13,081.94 | 175,020 | 13,081,490 | |
| 06/04/14 | 8:00 | 15:00 | 7:00 | 13,081.94 | 13,233.54 | 151,600 | 13,233,090 | |
| 06/05/14 | 8:30 | 17:00 | 8:30 | 13,233.54 | 13,391.28 | 157,740 | 13,390,830 | |
| 06/06/14 | 7:30 | 15:30 | 8:00 | 13,391.28 | 13,444.66 | 53,380 | 13,444,210 | |
| 06/08/14 | 12:00 | 17:00 | 5:00 | 13,444.66 | 13,498.28 | 53,620 | 13,497,830 | |
| 06/09/14 | 8:30 | 14:45 | 6:15 | 13,498.28 | 13,667.07 | 168,790 | 13,666,620 | |
| 06/10/14 | 8:30 | 14:10 | 5:40 | 13,667.07 | 13,839.23 | 172,160 | 13,838,780 | |
| 06/11/14 | 8:10 | 13:00 | 4:50 | 13,839.23 | 13,952.75 | 113,520 | 13,952,300 | |
| 06/12/14 | 11:45 | 18:35 | 6:50 | 13,952.75 | 14,138.23 | 185,480 | 14,137,780 | |
| 06/13/14 | 7:30 | 20:45 | 13:15 | 14,138.23 | 14,296.51 | 158,280 | 14,296,060 | |
| 06/14/14 | 8:00 | 15:50 | 7:50 | 14,296.51 | 14,447.78 | 151,270 | 14,447,330 | |
| 06/16/14 | 7:30 | 15:50 | 8:20 | 14,447.78 | 14,602.88 | 155,100 | 14,602,430 | |
| 06/17/14 | 7:05 | 15:00 | 7:55 | 14,602.88 | 14,717.27 | 114,390 | 14,716,820 | |
| 06/18/14 | 7:00 | 15:00 | 8:00 | 14,717.27 | 14,832.09 | 114,820 | 14,831,640 | |
| 06/19/14 | 7:10 | 14:30 | 7:20 | 14,832.09 | 14,937.60 | 105,510 | 14,937,150 | |
| 06/20/14 | 6:20 | 14:40 | 8:20 | 14,937.60 | 15,083.23 | 145,630 | 15,082,780 | |
| 06/21/14 | 10:15 | 13:15 | 3:00 | 15,083.23 | 15,127.76 | 44,530 | 15,127,310 | |
| 06/23/14 | 6:40 | 14:30 | 7:50 | 15,127.76 | 15,294.76 | 167,000 | 15,294,310 | |
| 06/24/14 | 6:15 | 14:45 | 8:30 | 15,294.76 | 15,348.15 | 53,390 | 15,347,700 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 06/25/14 | 6:45 | 15:00 | 8:15 | 15,348.15 | 15,452.33 | 104,180 | 15,451,880 | |
| 06/26/14 | 6:55 | 14:45 | 7:50 | 15,452.33 | 15,551.63 | 99,300 | 15,551,180 | |
| 06/27/14 | 7:45 | 15:30 | 7:45 | 15,551.63 | 15,616.53 | 64,900 | 15,616,080 | |
| 06/30/14 | 6:25 | 14:25 | 8:00 | 15,616.53 | 15,754.00 | 137,470 | 15,753,550 | |
| 07/02/14 | 6:15 | 14:45 | 8:30 | 15,754.00 | 15,879.17 | 125,170 | 15,878,720 | |
| 07/03/14 | 9:30 | 14:45 | 5:15 | 15,879.17 | 15,995.15 | 115,980 | 15,994,700 | |
| 07/04/14 | 7:30 | 14:45 | 7:15 | 15,995.15 | 16,174.96 | 179,810 | 16,174,510 | |
| 07/05/14 | 7:25 | 14:25 | 7:00 | 16,174.96 | 16,354.58 | 179,620 | 16,354,130 | |
| 07/06/14 | 7:35 | 13:30 | 5:55 | 16,354.58 | 16,443.35 | 88,770 | 16,442,900 | |
| 07/07/14 | 6:45 | 15:50 | 9:05 | 16,443.35 | 16,582.28 | 138,930 | 16,581,830 | |
| 07/08/14 | 6:45 | 14:50 | 8:05 | 16,582.28 | 16,719.12 | 136,840 | 16,718,670 | |
| 07/09/14 | 7:00 | 14:30 | 7:30 | 16,719.12 | 16,813.21 | 94,090 | 16,812,760 | |
| 07/10/14 | 7:15 | 14:30 | 7:15 | 16,813.21 | 16,861.07 | 47,860 | 16,860,620 | |
| 07/11/14 | 8:00 | 14:00 | 6:00 | 16,861.07 | 16,927.80 | 66,730 | 16,927,350 | |
| 07/14/14 | 6:50 | 14:25 | 7:35 | 17,039.50 | 17,039.50 | 111,700 | 17,039,050 | |
| 07/15/14 | 6:35 | 14:45 | 8:10 | 17,151.47 | 17,151.47 | 111,970 | 17,151,020 | |
| 07/16/14 | 6:00 | 13:30 | 7:30 | 17,151.47 | 17,277.51 | 126,040 | 17,277,060 | |
| 07/17/14 | 9:45 | 15:00 | 5:15 | 17,277.51 | 17,369.50 | 91,990 | 17,369,050 | |
| 07/18/14 | 6:15 | 14:00 | 7:45 | 17,369.50 | 17,470.26 | 100,760 | 17,469,810 | |
| 07/21/14 | 6:15 | 14:45 | 8:30 | 17,470.26 | 17,603.88 | 133,620 | 17,603,430 | |
| 07/22/14 | 6:00 | 14:00 | 8:00 | 17,603.88 | 17,697.76 | 93,880 | 17,697,310 | |
| 07/23/14 | 6:15 | 13:45 | 7:30 | 17,697.76 | 17,756.61 | 58,850 | 17,756,160 | |
| 07/24/14 | 6:45 | 14:15 | 7:30 | 17,756.61 | 17,794.18 | 37,570 | 17,793,730 | |
| 07/25/14 | 7:00 | 14:00 | 7:00 | 17,794.18 | 17,849.88 | 55,700 | 17,849,430 | |
| 07/28/14 | 6:15 | 14:15 | 8:00 | 17,849.88 | 17,964.12 | 114,240 | 17,963,670 | |
| 07/29/14 | 6:15 | 14:15 | 8:00 | 17,964.12 | 18,017.49 | 53,370 | 18,017,040 | |
| 07/30/14 | 6:30 | 14:20 | 7:50 | 18,017.49 | 18,060.14 | 42,650 | 18,059,690 | |
| 08/04/14 | 6:45 | 9:00 | 2:15 | 18,060.14 | 18,144.28 | 84,140 | 18,143,830 | |
| 08/05/14 | 7:00 | 15:00 | 8:00 | 18,144.28 | 18,237.50 | 93,220 | 18,237,050 | |
| 08/06/14 | 6:30 | 14:15 | 7:45 | 18,237.50 | 18,289.93 | 52,430 | 18,289,480 | |
| 08/07/14 | 8:30 | 14:00 | 5:30 | 18,289.93 | 18,324.27 | 34,340 | 18,323,820 | |
| 08/08/14 | 7:00 | 14:20 | 7:20 | 18,324.27 | 18,357.38 | 33,110 | 18,356,930 | |
| 08/11/14 | 6:30 | 15:30 | 9:00 | 18,357.38 | 18,450.45 | 93,070 | 18,450,000 | |
| 08/12/14 | 7:00 | 14:00 | 7:00 | 18,450.45 | 18,524.19 | 73,740 | 18,523,740 | |
| 08/13/14 | 8:30 | 14:45 | 6:15 | 18,524.19 | 18,579.42 | 55,230 | 18,578,970 | |
| 08/14/14 | 8:00 | 15:00 | 7:00 | 18,579.42 | 18,610.35 | 30,930 | 18,609,900 | |
| 08/15/14 | 8:30 | 14:30 | 6:00 | 18,610.35 | 18,630.29 | 19,940 | 18,629,840 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 08/17/14 | 8:30 | 14:30 | 6:00 | 18,630.29 | 18,701.73 | 71,440 | 18,701,280 | |
| 08/19/14 | 6:15 | 14:15 | 8:00 | 18,701.73 | 18,805.82 | 104,090 | 18,805,370 | |
| 08/20/14 | 9:30 | 15:30 | 6:00 | 18,805.82 | 18,884.84 | 79,020 | 18,884,390 | |
| 08/21/14 | 6:15 | 14:15 | 8:00 | 18,884.84 | 18,986.62 | 101,780 | 18,986,170 | |
| 08/22/14 | 6:15 | 14:00 | 7:45 | 18,986.62 | 19,094.08 | 107,460 | 19,093,630 | |
| 08/25/14 | 6:30 | 14:30 | 8:00 | 19,094.08 | 19,193.73 | 99,650 | 19,193,280 | |
| 08/26/14 | 7:00 | 15:45 | 8:45 | 19,193.73 | 19,298.14 | 104,410 | 19,297,690 | |
| 08/27/14 | 7:30 | 15:00 | 7:30 | 19,298.14 | 19,368.93 | 70,790 | 19,368,480 | |
| 08/28/14 | 7:00 | 15:45 | 8:45 | 19,368.93 | 19,461.76 | 92,830 | 19,461,310 | |
| 08/29/14 | 6:30 | 12:15 | 5:45 | 19,461.76 | 19,495.63 | 33,870 | 19,495,180 | |
| 08/31/14 | 8:00 | 13:00 | 5:00 | 19,495.63 | 19,566.27 | 70,640 | 19,565,820 | |
| 09/02/14 | 7:00 | 15:00 | 8:00 | 19,566.27 | 19,626.24 | 59,970 | 19,625,790 | |
| 09/03/14 | 8:30 | 14:30 | 6:00 | 19,626.24 | 19,683.38 | 57,140 | 19,682,930 | |
| 09/04/14 | 7:30 | 14:00 | 6:30 | 19,683.38 | 19,752.78 | 69,400 | 19,752,330 | |
| 09/05/14 | 11:30 | 15:00 | 3:30 | 19,752.78 | 19,779.42 | 26,640 | 19,778,970 | |
| 09/06/14 | 9:00 | 14:00 | 5:00 | 19,779.42 | 19,824.20 | 44,780 | 19,823,750 | |
| 09/07/14 | 9:00 | 14:00 | 5:00 | 19,824.20 | 19,853.23 | 29,030 | 19,852,780 | |
| 09/08/14 | 7:30 | 14:45 | 7:15 | 19,853.23 | 19,922.16 | 68,930 | 19,921,710 | |
| 09/11/14 | 6:30 | 15:15 | 8:45 | 19,922.16 | 20,004.70 | 82,540 | 20,004,250 | |
| 09/12/14 | 13:00 | 14:30 | 1:30 | 20,004.70 | 20,053.63 | 48,930 | 20,053,180 | |
| 09/14/14 | 10:00 | 13:30 | 3:30 | 20,053.63 | 20,068.27 | 14,640 | 20,067,820 | |
| 09/15/14 | 7:30 | 14:30 | 7:00 | 20,068.77 | 20,133.27 | 65,000 | 20,132,820 | |
| 09/16/14 | 7:30 | 15:00 | 7:30 | 20,133.27 | 20,179.69 | 46,420 | 20,179,240 | |
| 09/17/14 | 7:00 | 14:00 | 7:00 | 20,179.69 | 20,231.28 | 51,590 | 20,230,830 | |
| 09/18/14 | 7:00 | 14:30 | 7:30 | 20,231.28 | 20,263.94 | 32,660 | 20,263,490 | |
| 09/19/14 | 6:30 | 15:00 | 8:30 | 20,263.94 | 20,347.22 | 83,280 | 20,346,770 | |
| 09/21/14 | 7:00 | 11:00 | 4:00 | 20,347.22 | 20,396.72 | 49,500 | 20,396,270 | |
| 09/22/14 | 7:00 | 15:20 | 8:20 | 20,396.72 | 20,491.07 | 94,350 | 20,490,620 | |
| 09/23/14 | 7:00 | 15:30 | 8:30 | 20,491.07 | 20,558.92 | 67,850 | 20,558,470 | |
| 09/24/14 | 7:00 | 15:15 | 8:15 | 20,558.92 | 20,654.42 | 95,500 | 20,653,970 | |
| 09/25/14 | 9:30 | 14:30 | 5:00 | 20,654.42 | 20,703.09 | 48,670 | 20,702,640 | |
| 09/26/14 | 7:00 | 14:30 | 7:30 | 20,703.09 | 20,732.78 | 29,690 | 20,732,330 | |
| 09/29/14 | 7:00 | 15:00 | 8:00 | 20,732.78 | 20,810.38 | 77,600 | 20,809,930 | |
| 09/30/14 | 7:00 | 14:30 | 7:30 | 20,810.38 | 20,855.01 | 44,630 | 20,854,560 | |
| 10/02/14 | 6:45 | 15:15 | 8:30 | 20,855.01 | 20,938.29 | 83,280 | 20,937,840 | |
| 10/03/14 | 8:00 | 14:00 | 6:00 | 20,938.29 | 20,977.59 | 39,300 | 20,977,140 | |
| 10/05/14 | 8:00 | 12:30 | 4:30 | 20,977.59 | 21,023.46 | 45,870 | 21,023,010 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 10/06/14 | 7:30 | 15:15 | 7:45 | 21,023.46 | 21,102.23 | 78,770 | 21,101,780 | |
| 10/09/14 | 7:00 | 15:00 | 8:00 | 21,102.23 | 21,182.13 | 79,900 | 21,181,680 | |
| 10/10/14 | 7:00 | 14:30 | 7:30 | 21,182.13 | 21,208.69 | 26,560 | 21,208,240 | |
| 10/12/14 | 7:00 | 11:30 | 4:30 | 21,208.69 | 21,228.53 | 19,840 | 21,228,080 | |
| 10/13/14 | 8:00 | 14:30 | 6:30 | 21,228.53 | 21,289.72 | 61,190 | 21,289,270 | |
| 10/14/14 | 7:30 | 9:30 | 2:00 | 21,289.72 | 21,292.46 | 2,740 | 21,292,010 | |
| 10/15/14 | 7:30 | 15:30 | 8:00 | 21,292.46 | 21,349.49 | 57,030 | 21,349,040 | |
| 10/16/14 | 7:30 | 15:30 | 8:00 | 21,349.49 | 21,411.09 | 61,600 | 21,410,640 | |
| 10/17/14 | 7:30 | 14:30 | 7:00 | 21,411.09 | 21,463.04 | 51,950 | 21,462,590 | |
| 10/19/14 | 8:00 | 13:00 | 5:00 | 21,463.04 | 21,523.23 | 60,190 | 21,522,780 | |
| 10/21/14 | 7:30 | 14:30 | 7:00 | 21,523.23 | 21,574.85 | 51,620 | 21,574,400 | |
| 10/22/14 | 7:30 | 15:30 | 8:00 | 21,574.85 | 21,611.86 | 37,010 | 21,611,410 | |
| 10/23/14 | 7:00 | 16:30 | 9:30 | 21,611.86 | 21,728.57 | 116,710 | 21,728,120 | |
| 10/24/14 | 8:00 | 15:00 | 7:00 | 21,728.57 | 21,795.15 | 66,580 | 21,794,700 | |
| 10/25/14 | 8:30 | 12:30 | 4:00 | 21,795.15 | 21,836.74 | 41,590 | 21,836,290 | |
| 10/27/14 | 7:30 | 15:30 | 8:00 | 21,836.74 | 21,934.46 | 97,720 | 21,934,010 | |
| 10/29/14 | 10:00 | 14:15 | 4:15 | 21,934.46 | 21,979.83 | 45,370 | 21,979,380 | |
| 10/30/14 | 9:00 | 11:00 | 2:00 | 21,979.83 | 21,987.45 | 7,620 | 21,987,000 | |
| 11/05/14 | 8:00 | 15:00 | 7:00 | 21,987.45 | 22,068.71 | 81,260 | 22,068,260 | |
| 11/07/14 | 10:00 | 15:00 | 5:00 | 22,068.71 | 22,093.24 | 24,530 | 22,092,790 | |
| 11/10/14 | 8:00 | 14:30 | 6:30 | 22,093.24 | 22,125.00 | 31,760 | 22,124,550 | CGWES pumped and isolated from 930 to 1530 |
| 11/11/14 | 11:00 | 16:00 | 5:00 | 22,125.00 | 22,151.18 | 26,180 | 22,150,730 | |
| 11/12/14 | 7:15 | 15:15 | 8:00 | 22,151.18 | 22,205.08 | 53,900 | 22,204,630 | |
| 11/13/14 | 7:30 | 15:30 | 8:00 | 22,205.08 | 22,232.39 | 27,310 | 22,231,940 | |
| 11/14/14 | 7:00 | 12:00 | 5:00 | 22,232.39 | 22,270.23 | 37,840 | 22,269,780 | |
| 11/15/14 | 11:00 | 14:45 | 3:45 | 22,270.23 | 22,327.83 | 57,600 | 22,327,380 | |
| 11/16/14 | 10:00 | 14:00 | 4:00 | 22,327.83 | 22,387.57 | 59,740 | 22,387,120 | |
| 11/17/14 | 9:00 | 16:00 | 7:00 | 22,387.57 | 22,488.01 | 100,440 | 22,487,560 | |
| 11/18/14 | 8:00 | 15:30 | 7:30 | 22,488.01 | 22,568.74 | 80,730 | 22,568,290 | |
| 11/19/14 | 8:00 | 15:30 | 7:30 | 22,568.74 | 22,653.22 | 84,480 | 22,652,770 | |
| 11/20/14 | 7:30 | 12:30 | 5:00 | 22,653.22 | 22,692.55 | 39,330 | 22,692,100 | |
| 11/21/14 | 8:00 | 16:00 | 8:00 | 22,692.55 | 22,747.08 | 54,530 | 22,746,630 | |
| 11/22/14 | 8:00 | 12:00 | 4:00 | 22,747.08 | 22,783.08 | 36,000 | 22,782,630 | |
| 11/24/14 | 7:00 | 15:30 | 8:30 | 22,783.08 | 22,833.40 | 50,320 | 22,832,950 | |
| 11/26/14 | 7:30 | 15:00 | 7:30 | 22,833.40 | 22,889.40 | 56,000 | 22,888,950 | |
| 11/28/14 | 11:00 | 16:00 | 5:00 | 22,889.40 | 22,984.22 | 94,820 | 22,983,770 | |
| 11/30/14 | 14:00 | 16:20 | 2:20 | 22,984.22 | 23,021.47 | 37,250 | 23,021,020 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 12/01/14 | 8:30 | 14:30 | 6:00 | 23,021.47 | 23,125.75 | 104,280 | 23,125,300 | |
| 12/02/14 | 7:00 | 15:00 | 8:00 | 23,125.75 | 23,223.33 | 97,580 | 23,222,880 | |
| 12/03/14 | 7:30 | 15:00 | 7:30 | 23,223.33 | 23,306.88 | 83,550 | 23,306,430 | |
| 12/04/14 | 7:30 | 15:15 | 7:45 | 23,306.88 | 23,418.88 | 112,000 | 23,418,430 | |
| 12/05/14 | 7:30 | 15:00 | 7:30 | 23,418.88 | 23,505.57 | 86,690 | 23,505,120 | |
| 12/06/14 | 12:30 | 16:30 | 4:00 | 23,505.57 | 23,547.36 | 41,790 | 23,546,910 | |
| 12/08/14 | 6:30 | 16:45 | 10:15 | 23,547.36 | 23,734.14 | 186,780 | 23,733,690 | |
| 12/09/14 | 7:00 | 17:00 | 10:00 | 23,734.14 | 23,938.58 | 204,440 | 23,938,130 | |
| 12/10/14 | 6:30 | 15:30 | 9:00 | 23,938.58 | 24,127.10 | 188,520 | 24,126,650 | |
| 12/11/14 | 7:00 | 15:00 | 8:00 | 24,127.10 | 24,278.59 | 151,490 | 24,278,140 | |
| 12/12/14 | 7:00 | 14:30 | 7:30 | 24,278.59 | 24,400.95 | 122,360 | 24,400,500 | |
| 12/13/14 | 7:00 | 14:00 | 7:00 | 24,400.95 | 24,465.38 | 64,430 | 24,464,930 | |
| 12/15/14 | 7:00 | 15:30 | 8:30 | 24,465.38 | 24,642.32 | 176,940 | 24,641,870 | |
| 12/16/14 | 7:00 | 16:00 | 9:00 | 24,642.32 | 24,790.34 | 148,020 | 24,789,890 | |
| 12/17/14 | 7:00 | 15:00 | 8:00 | 24,790.34 | 24,891.32 | 100,980 | 24,890,870 | |
| 12/18/14 | 7:00 | 14:30 | 7:30 | 24,891.32 | 24,942.66 | 51,340 | 24,942,210 | |
| 12/19/14 | 7:00 | 14:30 | 7:30 | 24,942.66 | 24,984.39 | 41,730 | 24,983,940 | |
| 12/22/14 | 7:00 | 15:00 | 8:00 | 24,984.39 | 25,135.32 | 150,930 | 25,134,870 | |
| 12/23/14 | 8:00 | 15:45 | 7:45 | 25,135.32 | 25,225.78 | 90,460 | 25,225,330 | |
| 12/24/14 | 7:00 | 14:00 | 7:00 | 25,225.78 | 25,261.74 | 35,960 | 25,261,290 | |
| 12/29/14 | 7:00 | 16:15 | 9:15 | 25,261.74 | 25,355.68 | 93,940 | 25,355,230 | |
| 12/30/14 | 7:00 | 16:00 | 9:00 | 25,355.68 | 25,472.64 | 116,960 | 25,472,190 | |
| 12/31/14 | 7:00 | 14:00 | 7:00 | 25,472.64 | 25,613.83 | 141,190 | 25,613,380 | |
| 01/02/15 | 7:00 | 14:30 | 7:30 | 25,613.83 | 25,704.93 | 91,100 | 25,704,480 | |
| 01/05/15 | 7:00 | 16:45 | 9:45 | 25,704.93 | 25,803.51 | 98,580 | 25,803,060 | |
| 01/06/15 | 7:00 | 15:15 | 8:15 | 25,803.51 | 25,934.54 | 131,030 | 25,934,090 | |
| 01/07/15 | 7:00 | 15:00 | 8:00 | 25,934.54 | 26,010.92 | 76,380 | 26,010,470 | |
| 01/11/15 | 9:00 | 14:00 | 5:00 | 26,010.92 | 26,076.69 | 65,770 | 26,076,240 | |
| 01/12/15 | 13:30 | 16:00 | 2:30 | 26,076.69 | 26,123.43 | 46,740 | 26,122,980 | |
| 01/13/15 | 13:30 | 16:00 | 2:30 | 26,123.43 | 26,242.94 | 119,510 | 26,242,490 | |
| 01/14/15 | 10:15 | 16:00 | 5:45 | 26,242.94 | 26,294.50 | 51,560 | 26,294,050 | |
| 01/15/15 | 7:30 | 15:00 | 7:30 | 26,294.50 | 26,374.46 | 79,960 | 26,374,010 | |
| 01/16/15 | 7:30 | 14:00 | 6:30 | 26,374.46 | 26,431.98 | 57,520 | 26,431,530 | |
| 01/19/15 | 7:00 | 16:00 | 9:00 | 26,431.98 | 26,544.34 | 112,360 | 26,543,890 | |
| 01/20/15 | 7:00 | 16:30 | 9:30 | 26,544.34 | 26,671.53 | 127,190 | 26,671,080 | |
| 01/21/15 | 7:00 | 16:00 | 9:00 | 26,671.53 | 26,795.65 | 124,120 | 26,795,200 | |
| 01/22/15 | 7:00 | 15:30 | 8:30 | 26,795.65 | 26,937.52 | 141,870 | 26,937,070 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 01/23/15 | 7:00 | 15:00 | 8:00 | 26,937.52 | 27,077.78 | 140,260 | 27,077,330 | |
| 01/28/15 | 7:00 | 14:30 | 7:30 | 27,077.78 | 27,127.82 | 50,040 | 27,127,370 | |
| 01/29/15 | 7:00 | 15:00 | 8:00 | 27,127.82 | 27,180.82 | 53,000 | 27,180,370 | |
| 01/30/15 | 7:00 | 14:00 | 7:00 | 27,180.82 | 27,268.67 | 87,850 | 27,268,220 | |
| 02/04/15 | 7:00 | 12:30 | 5:30 | 27,268.67 | 27,317.51 | 48,840 | 27,317,060 | |
| 02/05/15 | 7:30 | 15:00 | 7:30 | 27,317.51 | 27,437.11 | 119,600 | 27,436,660 | |
| 02/09/15 | 9:30 | 14:30 | 5:00 | 27,437.11 | 27,484.85 | 47,740 | 27,484,400 | |
| 02/10/15 | 9:30 | 16:15 | 6:45 | 27,484.85 | 27,587.00 | 102,150 | 27,586,550 | |
| 02/11/15 | 8:00 | 14:30 | 6:30 | 27,587.00 | 27,626.34 | 39,340 | 27,625,890 | |
| 02/12/15 | 8:00 | 14:30 | 6:30 | 27,626.34 | 27,687.34 | 61,000 | 27,686,890 | |
| 02/20/15 | 10:30 | 12:15 | 1:45 | 27,687.34 | 27,702.61 | 15,270 | 27,702,160 | |
| 02/23/15 | 7:30 | 15:30 | 8:00 | 27,702.61 | 27,758.65 | 56,040 | 27,758,200 | |
| 02/25/15 | 7:30 | 15:00 | 7:30 | 27,758.65 | 27,788.98 | 30,330 | 27,788,530 | |
| 02/26/15 | 7:30 | 14:00 | 6:30 | 27,788.98 | 27,806.88 | 17,900 | 27,806,430 | |
| 03/02/15 | 10:30 | 14:30 | 4:00 | 27,806.88 | 27,853.74 | 46,860 | 27,853,290 | |
| 03/04/15 | 7:30 | 14:00 | 6:30 | 27,853.74 | 27,955.09 | 101,350 | 27,954,640 | |
| 03/05/15 | 8:00 | 14:00 | 6:00 | 27,955.09 | 28,075.85 | 120,760 | 28,075,400 | |
| 03/06/15 | 7:30 | 14:30 | 7:00 | 28,075.85 | 28,200.09 | 124,240 | 28,199,640 | |
| 03/09/15 | 7:30 | 15:00 | 7:30 | 28,200.09 | 28,324.06 | 123,970 | 28,323,610 | |
| 03/10/15 | 7:30 | 15:00 | 7:30 | 28,324.06 | 28,458.25 | 134,190 | 28,457,800 | |
| 03/11/15 | 8:00 | 14:30 | 6:30 | 28,458.25 | 28,520.01 | 61,760 | 28,519,560 | |
| 03/12/15 | 9:00 | 15:00 | 6:00 | 28,520.01 | 28,571.66 | 51,650 | 28,571,210 | |
| 03/13/15 | 8:00 | 15:00 | 7:00 | 28,571.66 | 28,691.97 | 120,310 | 28,691,520 | |
| 03/14/15 | 8:00 | 16:30 | 8:30 | 28,691.97 | 28,827.02 | 135,050 | 28,826,570 | |
| 03/15/15 | 10:00 | 17:00 | 7:00 | 28,827.02 | 28,912.43 | 85,410 | 28,911,980 | |
| 03/16/15 | 7:30 | 15:15 | 7:45 | 28,912.43 | 29,086.98 | 174,550 | 29,086,530 | |
| 03/17/15 | 8:00 | 14:30 | 6:30 | 29,086.98 | 29,181.23 | 94,250 | 29,180,780 | |
| 03/18/15 | 7:30 | 15:00 | 7:30 | 29,181.23 | 29,228.98 | 47,750 | 29,228,530 | |
| 03/19/15 | 7:30 | 15:15 | 7:45 | 29,228.98 | 29,340.87 | 111,890 | 29,340,420 | |
| 03/20/15 | 8:00 | 14:00 | 6:00 | 29,340.87 | 29,436.92 | 96,050 | 29,436,470 | |
| 03/23/15 | 8:30 | 15:00 | 6:30 | 29,436.92 | 29,533.78 | 96,860 | 29,533,330 | |
| 03/24/15 | 7:30 | 15:00 | 7:30 | 29,533.78 | 29,615.04 | 81,260 | 29,614,590 | |
| 03/25/15 | 7:30 | 15:15 | 7:45 | 29,615.04 | 29,748.59 | 133,550 | 29,748,140 | |
| 03/26/15 | 7:30 | 15:30 | 8:00 | 29,748.59 | 29,862.15 | 113,560 | 29,861,700 | |
| 03/27/15 | 7:30 | 15:30 | 8:00 | 29,862.15 | 29,986.08 | 123,930 | 29,985,630 | |
| 03/28/15 | 9:00 | 15:00 | 6:00 | 29,986.08 | 30,091.41 | 105,330 | 30,090,960 | |
| 03/30/15 | 7:30 | 15:30 | 8:00 | 30,091.41 | 30,203.08 | 111,670 | 30,202,630 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 03/31/15 | 7:30 | 14:30 | 7:00 | 30,203.08 | 30,378.43 | 175,350 | 30,377,980 | |
| 04/01/15 | 7:30 | 15:00 | 7:30 | 30,378.43 | 30,506.05 | 127,620 | 30,505,600 | |
| 04/02/15 | 7:15 | 15:15 | 8:00 | 30,506.05 | 30,637.07 | 131,020 | 30,636,620 | |
| 04/04/15 | 7:30 | 15:30 | 8:00 | 30,637.07 | 30,677.37 | 40,300 | 30,676,920 | |
| 04/06/15 | 7:00 | 15:00 | 8:00 | 30,677.37 | 30,776.12 | 98,750 | 30,775,670 | |
| 04/07/15 | 7:15 | 15:00 | 7:45 | 30,776.12 | 30,842.73 | 66,610 | 30,842,280 | |
| 04/08/15 | 7:15 | 15:00 | 7:45 | 30,842.73 | 30,910.48 | 67,750 | 30,910,030 | |
| 04/09/15 | 8:30 | 15:00 | 6:30 | 30,910.48 | 30,974.48 | 64,000 | 30,974,030 | |
| 04/10/15 | 7:30 | 15:00 | 7:30 | 30,974.48 | 31,065.01 | 90,530 | 31,064,560 | |
| 04/13/15 | 11:45 | 16:15 | 4:30 | 31,065.01 | 31,142.89 | 77,880 | 31,142,440 | |
| 04/14/15 | 7:30 | 15:00 | 7:30 | 31,142.89 | 31,231.27 | 88,380 | 31,230,820 | |
| 04/15/15 | 7:30 | 14:00 | 6:30 | 31,231.27 | 31,277.99 | 46,720 | 31,277,540 | |
| 04/17/15 | 7:15 | 12:00 | 4:45 | 31,277.99 | 31,315.22 | 37,230 | 31,314,770 | |
| 04/20/15 | 7:30 | 15:15 | 7:45 | 31,315.22 | 31,405.02 | 89,800 | 31,404,570 | |
| 04/21/15 | 7:00 | 14:00 | 7:00 | 31,405.02 | 31,446.44 | 41,420 | 31,445,990 | |
| 04/22/15 | 7:30 | 13:00 | 5:30 | 31,446.44 | 31,498.34 | 51,900 | 31,497,890 | |
| 04/23/15 | 7:00 | 13:30 | 6:30 | 31,498.34 | 31,544.28 | 45,940 | 31,543,830 | |
| 04/24/15 | 7:30 | 14:00 | 6:30 | 31,544.28 | 31,600.00 | 55,720 | 31,599,550 | |
| 04/27/15 | 7:30 | 14:30 | 7:00 | 31,600.00 | 31,637.05 | 37,050 | 31,636,600 | |
| 04/29/15 | 9:30 | 15:00 | 5:30 | 31,637.05 | 31,706.56 | 69,510 | 31,706,110 | |
| 04/30/15 | 8:00 | 15:00 | 7:00 | 31,706.56 | 31,755.10 | 48,540 | 31,754,650 | |
| 05/01/15 | 10:00 | 14:30 | 4:30 | 31,755.10 | 31,779.92 | 24,820 | 31,779,470 | |
| 05/05/15 | 7:00 | 14:00 | 7:00 | 31,779.92 | 31,862.76 | 82,840 | 31,862,310 | |
| 05/08/15 | 7:30 | 14:30 | 7:00 | 31,862.76 | 31,923.11 | 60,350 | 31,922,660 | |
| 05/11/15 | 10:00 | 15:00 | 5:00 | 31,923.11 | 31,978.26 | 55,150 | 31,977,810 | |
| 05/14/15 | 10:00 | 15:00 | 5:00 | 31,978.26 | 32,016.71 | 38,450 | 32,016,260 | |
| 05/18/15 | 7:30 | 14:30 | 7:00 | 32,016.71 | 32,102.90 | 86,190 | 32,102,450 | |
| 05/19/15 | 7:30 | 14:00 | 6:30 | 32,102.90 | 32,136.78 | 33,880 | 32,136,330 | |
| 05/20/15 | 7:30 | 15:00 | 7:30 | 32,136.78 | 32,157.02 | 20,240 | 32,156,570 | |
| 05/21/15 | 7:00 | 13:30 | 6:30 | 32,157.02 | 32,194.76 | 37,740 | 32,194,310 | |
| 05/22/15 | 8:00 | 12:00 | 4:00 | 32,194.76 | 32,208.64 | 13,880 | 32,208,190 | |
| 05/24/15 | 10:00 | 14:00 | 4:00 | 32,208.64 | 32,256.26 | 47,620 | 32,255,810 | |
| 05/27/15 | 6:30 | 13:30 | 7:00 | 32,256.26 | 32,322.85 | 66,590 | 32,322,400 | |
| 05/29/15 | 10:00 | 14:15 | 4:15 | 32,322.85 | 32,377.97 | 55,120 | 32,377,520 | |
| 06/01/15 | 9:00 | 15:45 | 6:45 | 32,377.97 | 32,528.67 | 150,700 | 32,528,220 | |
| 06/02/15 | 7:00 | 14:00 | 7:00 | 32,528.67 | 32,620.67 | 92,000 | 32,620,220 | |
| 06/04/15 | 6:30 | 14:00 | 7:30 | 32,620.67 | 32,756.41 | 135,740 | 32,755,960 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 06/05/15 | 6:30 | 13:30 | 7:00 | 32,756.41 | 32,833.26 | 76,850 | 32,832,810 | |
| 06/08/15 | 7:00 | 14:00 | 7:00 | 32,833.26 | 32,958.71 | 125,450 | 32,958,260 | |
| 06/10/15 | 10:00 | 16:00 | 6:00 | 32,958.71 | 33,019.45 | 60,740 | 33,019,000 | |
| 06/11/15 | 7:00 | 16:00 | 9:00 | 33,019.45 | 33,086.57 | 67,120 | 33,086,120 | |
| 06/12/15 | 6:30 | 12:00 | 5:30 | 33,086.57 | 33,146.46 | 59,890 | 33,146,010 | |
| 06/15/15 | 6:30 | 12:15 | 5:45 | 33,146.46 | 33,183.12 | 36,660 | 33,182,670 | |
| 06/16/15 | 7:00 | 14:15 | 7:15 | 33,183.12 | 33,226.73 | 43,610 | 33,226,280 | |
| 06/17/15 | 6:30 | 16:00 | 9:30 | 33,226.73 | 33,276.97 | 50,240 | 33,276,520 | |
| 06/18/15 | 6:30 | 14:30 | 8:00 | 33,276.97 | 33,338.90 | 61,930 | 33,338,450 | |
| 06/19/15 | 6:30 | 14:00 | 7:30 | 33,338.90 | 33,439.40 | 100,500 | 33,438,950 | |
| 06/21/15 | 9:30 | 13:30 | 4:00 | 33,439.40 | 33,485.10 | 45,700 | 33,484,650 | |
| 06/22/15 | 6:30 | 14:00 | 7:30 | 33,485.10 | 33,567.88 | 82,780 | 33,567,430 | |
| 06/23/15 | 11:30 | 14:00 | 2:30 | 33,567.88 | 33,609.80 | 41,920 | 33,609,350 | |
| 06/24/15 | 9:00 | 13:30 | 4:30 | 33,609.80 | 33,646.89 | 37,090 | 33,646,440 | |
| 06/26/15 | 8:00 | 14:00 | 6:00 | 33,646.89 | 33,720.85 | 73,960 | 33,720,400 | |
| 06/29/15 | 7:00 | 14:30 | 7:30 | 33,720.85 | 33,738.82 | 17,970 | 33,738,370 | |
| 06/30/15 | 7:00 | 13:00 | 6:00 | 33,738.82 | 33,791.38 | 52,560 | 33,790,930 | |
| 07/01/15 | 6:30 | 14:00 | 7:30 | 33,791.38 | 33,923.97 | 132,590 | 33,923,520 | |
| 07/02/15 | 6:30 | 13:00 | 6:30 | 33,923.97 | 34,000.38 | 76,410 | 33,999,930 | |
| 07/06/15 | 7:00 | 13:30 | 6:30 | 34,000.38 | 34,066.66 | 66,280 | 34,066,210 | |
| 07/07/15 | 8:00 | 14:00 | 6:00 | 34,066.66 | 34,125.32 | 58,660 | 34,124,870 | |
| 07/08/15 | 6:30 | 13:30 | 7:00 | 34,125.32 | 34,199.65 | 74,330 | 34,199,200 | |
| 07/09/15 | 6:30 | 13:30 | 7:00 | 34,199.65 | 34,252.75 | 53,100 | 34,252,300 | |
| 07/10/15 | 6:30 | 12:00 | 5:30 | 34,252.75 | 34,298.94 | 46,190 | 34,245,390 | |
| 07/13/15 | 7:00 | 11:45 | 4:45 | 34,298.94 | 34,325.94 | 27,000 | 34,226,200 | |
| 07/14/15 | 6:30 | 12:30 | 6:00 | 34,325.94 | 34,396.15 | 70,210 | 34,269,410 | |
| 07/15/15 | 7:00 | 14:00 | 7:00 | 34,396.15 | 34,474.85 | 78,700 | 34,331,000 | |
| 07/16/15 | 6:30 | 13:00 | 6:30 | 34,474.85 | 34,526.84 | 51,990 | 34,382,990 | |
| 07/17/15 | 12:00 | 14:00 | 2:00 | 34,526.84 | 34,556.84 | 30,000 | 34,412,990 | |
| 07/21/15 | 6:30 | 14:30 | 8:00 | 34,556.84 | 34,653.22 | 96,380 | 34,509,370 | |
| 07/23/15 | 6:30 | 13:30 | 7:00 | 34,653.22 | 34,690.24 | 37,020 | 34,546,390 | |
| 07/24/15 | 10:30 | 13:30 | 3:00 | 34,690.24 | 34,702.10 | 11,860 | 34,558,250 | |
| 07/27/15 | 6:30 | 14:00 | 7:30 | 34,702.10 | 34,790.64 | 88,540 | 34,646,790 | |
| 07/31/15 | 6:30 | 14:30 | 8:00 | 34,790.64 | 34,908.04 | 117,400 | 34,764,190 | |
| 08/03/15 | 9:00 | 13:30 | 4:30 | 34,908.04 | 34,940.20 | 32,160 | 34,796,350 | |
| 08/04/15 | 10:30 | 21:30 | 11:00 | 34,940.20 | 35,081.91 | 141,710 | 34,938,060 | |
| 08/07/15 | 6:30 | 12:30 | 6:00 | 35,081.91 | 35,221.03 | 139,120 | 35,077,180 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 08/10/15 | 6:15 | 12:00 | 5:45 | 35,221.03 | 35,298.93 | 77,900 | 35,155,080 | |
| 08/11/15 | 6:35 | 14:30 | 7:55 | 35,298.93 | 35,398.03 | 99,100 | 35,254,180 | |
| 08/12/15 | 6:30 | 13:30 | 7:00 | 35,398.03 | 35,457.13 | 59,100 | 35,313,280 | |
| 08/13/15 | 7:00 | 13:30 | 6:30 | 35,457.13 | 35,497.93 | 40,800 | 35,354,080 | |
| 08/14/15 | 7:00 | 13:00 | 6:00 | 34,497.93 | 35,552.43 | 54,500 | 35,408,580 | |
| 08/17/15 | 6:30 | 12:30 | 6:00 | 35,552.43 | 35,618.63 | 66,200 | 35,474,780 | |
| 08/19/15 | 8:00 | 15:00 | 7:00 | 35,618.63 | 35,662.04 | 43,410 | 35,518,190 | |
| 08/20/15 | 7:00 | 14:00 | 7:00 | 35,662.04 | 35,706.84 | 44,800 | 35,562,990 | |
| 08/21/15 | 7:00 | 13:30 | 6:30 | 35,706.84 | 35,724.91 | 18,070 | 35,581,060 | |
| 08/25/15 | 8:00 | 14:00 | 6:00 | 35,724.91 | 35,790.40 | 65,490 | 35,646,550 | |
| 08/28/15 | 7:00 | 13:00 | 6:00 | 35,790.40 | 35,841.14 | 50,740 | 35,697,290 | |
| 09/01/15 | 7:00 | 13:00 | 6:00 | 35,841.14 | 35,929.31 | 88,170 | 35,785,460 | |
| 09/04/15 | 7:00 | 13:00 | 6:00 | 35,929.31 | 35,970.92 | 41,610 | 35,827,070 | |
| 09/09/15 | 7:00 | 15:00 | 8:00 | 35,970.92 | 36,046.73 | 75,810 | 35,902,880 | |
| 09/11/15 | 7:00 | 14:00 | 7:00 | 36,046.73 | 36,113.32 | 66,590 | 35,969,470 | |
| 09/18/15 | 7:00 | 15:00 | 8:00 | 36,113.32 | 36,198.63 | 85,310 | 36,054,780 | |
| 09/28/15 | 8:00 | 11:00 | 3:00 | 36,198.63 | 36,238.88 | 40,250 | 36,095,030 | |
| 09/30/15 | 7:30 | 15:00 | 7:30 | 36,238.88 | 36,367.55 | 128,670 | 36,223,700 | |
| 10/01/15 | 7:00 | 13:30 | 6:30 | 36,367.55 | 36,413.58 | 46,030 | 36,269,730 | |
| 10/02/15 | 7:00 | 15:00 | 8:00 | 36,413.58 | 36,458.01 | 44,430 | 36,314,160 | |
| 10/03/15 | 8:00 | 13:00 | 5:00 | 36,458.01 | 36,558.18 | 100,170 | 36,414,330 | |
| 10/04/15 | 9:30 | 13:00 | 3:30 | 36,558.18 | 36,598.54 | 40,360 | 36,454,690 | |
| 10/05/15 | 7:30 | 12:00 | 4:30 | 36,598.54 | 36,653.18 | 54,640 | 36,509,330 | |
| 10/06/15 | 7:30 | 11:30 | 4:00 | 36,653.18 | 36,704.47 | 51,290 | 36,560,620 | |
| 10/09/15 | 7:30 | 14:00 | 6:30 | 36,704.47 | 36,777.92 | 73,450 | 36,634,070 | |
| 10/15/15 | 8:00 | 15:00 | 7:00 | 36,777.92 | 36,888.81 | 110,890 | 36,744,960 | |
| 10/21/15 | 8:00 | 15:00 | 7:00 | 36,888.81 | 36,951.56 | 62,750 | 36,807,710 | |
| 10/23/15 | 11:00 | 14:30 | 3:30 | 36,951.56 | 36,973.34 | 21,780 | 36,829,490 | |
| 10/29/15 | 9:00 | 15:00 | 6:00 | 36,973.34 | 37,092.42 | 119,080 | 36,948,570 | |
| 11/02/15 | 8:00 | 13:00 | 5:00 | 37,092.42 | 37,158.61 | 66,190 | 37,014,760 | |
| 11/04/15 | 8:30 | 14:30 | 6:00 | 37,158.61 | 37,207.47 | 48,860 | 37,063,620 | |
| 11/06/15 | 12:00 | 15:00 | 3:00 | 37,207.47 | 37,237.70 | 30,230 | 37,093,850 | |
| 11/18/15 | 8:00 | 15:00 | 7:00 | 37,237.70 | 37,375.84 | 138,140 | 37,231,990 | |
| 11/22/15 | 9:00 | 13:00 | 4:00 | 37,375.84 | 37,440.68 | 64,840 | 37,296,830 | |
| 11/23/15 | 9:30 | 14:30 | 5:00 | 37,440.68 | 37,505.15 | 64,470 | 37,361,300 | |
| 11/25/15 | 7:15 | 13:45 | 6:30 | 37,505.15 | 37,566.11 | 60,960 | 37,422,260 | |
| 11/30/15 | 7:30 | 14:30 | 7:00 | 37,566.11 | 37,667.64 | 101,530 | 37,523,790 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 12/01/15 | 8:00 | 15:15 | 7:15 | 37,667.64 | 37,743.44 | 75,800 | 37,599,590 | |
| 12/02/15 | 7:00 | 15:00 | 8:00 | 37,743.44 | 37,805.70 | 62,260 | 37,661,850 | |
| 12/03/15 | 9:00 | 15:15 | 6:15 | 37,805.70 | 37,863.53 | 57,830 | 37,719,680 | |
| 12/04/15 | 7:00 | 12:30 | 5:30 | 37,863.53 | 37,912.70 | 49,170 | 37,768,850 | |
| 12/06/15 | 12:00 | 14:00 | 2:00 | 37,912.70 | 37,958.66 | 45,960 | 37,814,810 | |
| 12/07/15 | 10:30 | 15:15 | 4:45 | 37,958.66 | 37,984.16 | 25,500 | 37,840,310 | |
| 12/08/15 | 11:00 | 14:30 | 3:30 | 37,984.16 | 38,016.05 | 31,890 | 37,872,200 | |
| 12/09/15 | 10:30 | 15:00 | 4:30 | 38,016.05 | 38,051.66 | 35,610 | 37,907,810 | |
| 12/10/15 | 8:00 | 15:15 | 7:15 | 38,051.66 | 38,176.63 | 124,970 | 38,032,780 | |
| 12/13/15 | 9:00 | 12:15 | 3:15 | 38,176.63 | 38,243.45 | 66,820 | 38,099,600 | |
| 12/14/15 | 13:45 | 15:30 | 1:45 | 38,243.45 | 38,278.63 | 35,180 | 38,134,780 | |
| 12/15/15 | 7:00 | 12:30 | 5:30 | 38,278.63 | 38,398.71 | 120,080 | 38,254,860 | |
| 12/16/15 | 11:30 | 15:30 | 4:00 | 38,398.71 | 38,456.74 | 58,030 | 38,312,890 | |
| 12/17/15 | 7:00 | 11:00 | 4:00 | 38,456.74 | 38,495.28 | 38,540 | 38,351,430 | |
| 12/18/15 | 8:00 | 15:15 | 7:15 | 38,495.28 | 38,587.27 | 91,990 | 38,443,420 | |
| 12/20/15 | 8:45 | 12:00 | 3:15 | 38,587.27 | 38,637.00 | 49,730 | 38,493,150 | |
| 12/21/15 | 7:30 | 13:00 | 5:30 | 38,637.00 | 38,700.54 | 63,540 | 38,556,690 | |
| 12/23/15 | 7:30 | 13:45 | 6:15 | 38,700.54 | 38,805.80 | 105,260 | 38,661,950 | |
| 12/24/15 | 8:00 | 15:00 | 7:00 | 38,805.80 | 38,835.49 | 29,690 | 38,691,640 | |
| 12/26/15 | 8:00 | 14:00 | 6:00 | 38,835.49 | 38,889.27 | 53,780 | 38,745,420 | |
| 12/28/15 | 7:00 | 15:30 | 8:30 | 38,889.27 | 39,029.27 | 140,000 | 38,885,420 | |
| 12/30/15 | 7:15 | 14:30 | 7:15 | 39,029.27 | 39,125.05 | 95,780 | 38,981,200 | |
| 12/31/15 | 7:00 | 13:45 | 6:45 | 39,125.05 | 39,167.86 | 42,810 | 39,024,010 | |
| 01/04/16 | 7:30 | 16:15 | 8:45 | 39,167.86 | 39,269.10 | 101,240 | 39,125,250 | |
| 01/07/16 | 8:00 | 16:15 | 8:15 | 39,269.10 | 39,354.16 | 85,060 | 39,210,310 | |
| 01/11/16 | 7:30 | 14:00 | 6:30 | 39,354.16 | 39,425.93 | 71,770 | 39,282,080 | |
| 01/12/16 | 8:00 | 13:00 | 5:00 | 39,425.93 | 39,510.66 | 84,730 | 39,366,810 | |
| 01/14/16 | 9:30 | 14:00 | 4:30 | 39,510.66 | 39,562.31 | 51,650 | 39,418,460 | |
| 02/01/16 | 7:30 | 13:15 | 5:45 | 39,562.31 | 39,632.04 | 69,730 | 39,488,190 | |
| 02/02/16 | 7:00 | 11:30 | 4:30 | 39,632.04 | 39,691.51 | 59,470 | 39,547,660 | |
| 02/03/16 | 7:30 | 15:30 | 8:00 | 39,691.51 | 39,789.38 | 97,870 | 39,645,530 | |
| 02/04/16 | 8:00 | 15:30 | 7:30 | 39,789.38 | 39,869.34 | 79,960 | 39,725,490 | |
| 02/05/16 | 8:00 | 15:30 | 7:30 | 39,869.34 | 39,962.83 | 93,490 | 39,818,980 | |
| 02/06/16 | 8:00 | 14:00 | 6:00 | 39,962.83 | 40,010.68 | 47,850 | 39,866,830 | |
| 02/08/16 | 7:15 | 15:15 | 8:00 | 40,010.68 | 40,119.75 | 109,070 | 39,975,900 | |
| 02/09/16 | 8:30 | 15:30 | 7:00 | 40,119.75 | 40,195.00 | 75,250 | 40,051,150 | |
| 02/10/16 | 9:30 | 15:30 | 6:00 | 40,195.00 | 40,313.68 | 118,680 | 40,169,830 | |

Construction Water Discharge Data
Study Area 6
Honeywell International Inc.
Jersey City, New Jersey

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT OR PUMP START TIME | SHIFT OR PUMP END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal[2]) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal[1]) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 02/11/16 | 10:30 | 15:30 | 5:00 | 40,313.68 | 40,407.45 | 93,770 | 40,263,600 | |
| 02/16/16 | 10:00 | 16:00 | 6:00 | 40,407.45 | 40,472.48 | 65,030 | 40,328,630 | |
| 02/17/16 | 7:00 | 15:30 | 8:30 | 40,472.48 | 40,635.48 | 163,000 | 40,491,630 | |
| 02/18/16 | 9:30 | 14:30 | 5:00 | 40,635.48 | 40,695.00 | 59,520 | 40,551,150 | |
| 02/22/16 | 7:30 | 13:00 | 5:30 | 40,695.00 | 40,767.90 | 72,900 | 40,624,050 | |
| 02/23/16 | 7:30 | 15:00 | 7:30 | 40,767.90 | 40,847.01 | 79,110 | 40,703,160 | |
| 02/24/16 | 8:30 | 15:00 | 6:30 | 40,847.01 | 40,947.06 | 100,050 | 40,803,210 | |
| 02/25/16 | 9:00 | 16:00 | 7:00 | 40,947.06 | 41,052.04 | 104,980 | 40,908,190 | |
| 02/26/16 | 7:30 | 15:00 | 7:30 | 41,052.04 | 41,114.52 | 62,480 | 40,970,670 | |
| 02/27/16 | 9:00 | 12:30 | 3:30 | 41,114.52 | 41,172.24 | 57,720 | 41,028,390 | |
| 02/28/16 | 8:00 | 13:00 | 5:00 | 41,172.24 | 41,227.51 | 55,270 | 41,083,660 | |
| 02/29/16 | 6:30 | 15:15 | 8:45 | 41,227.51 | 41,400.89 | 173,380 | 41,257,040 | |

* This Table Includes North Acitivity

[1] Gal = gallon

[2] KGal = 1,000 gallons

# APPENDIX J

# ITEMS ENCOUNTERED DURING REMEDIAL ACTIVITIES

# APPENDIX J-1
# ARSENIC-IMPACTED ASPHALT DEBRIS IN SOIL

During excavation activities at SA-6 South numerous subsurface features, conditions, or structures were encountered. Additional details regarding activities related to those conditions are included below.

**Concrete Reuse**

On December 20, 2013, Honeywell submitted a Certificate of Authority to Operate-Beneficial Use Determination (CAO-BUD) application to govern the onsite reuse of such concrete as initially directed by NJDEP. However, during subsequent conversations with NJDEP, Honeywell and NJDEP jointly concluded that a CAO-BUD was not necessary since concrete encountered during excavations was handled under the following guidelines:

- The management of the reused concrete is governed by the NJDEP-approved SMP.
- The concrete was sampled and tested in accordance with the September 2013 CASP. Only concrete material that met the most stringent standards set forth in NJDEP's *Alternative and Clean Fill Guidance for SRP Sites* was considered for onsite re-use. In accordance with the NJDEP-approved SMP, if the material did not meet the reuse criteria, then it was transported offsite for disposal at an approved waste facility.
- Honeywell proposed reusing the concrete that met those standards as bridging lift for backfill in the onsite excavations. The concrete was then subsequently buried under additional fill material and is not exposed at the ground surface.

Therefore, on July 29, 2014 via electronic mail, Honeywell requested approval from NJDEP to rescind the December 20, 2013 CAO-BUD application. On September 30, 2014 NJDEP issued a letter approving Honeywell's request to rescind the CAO-BUD.

**Arsenic-impacted Asphalt**

As part of the SA-6 Chromium Remedy, Entact collected 16 samples (Asphalt-001 through Asphalt-016) of the existing asphalt pavement throughout the excavation footprint at SA-6 South in accordance with the September 2013 CASP as shown on the attached figure. The following summarizes the disposition of the arsenic-impacted asphalt encountered at SA-6 South:

- Minimum arsenic concentration for the six samples: 23.6 mg/kg;
- Maximum arsenic concentration for the six samples: 64.4 mg/kg; and


- Quantity of asphalt represented by the six samples: approximately 1,250 CYs or 2,100 tons.

On August 19, 2014, Honeywell submitted a letter via electronic mail to NJDEP requesting approval to consolidate the arsenic-impacted material within either the SA-6 North Open Space Area and/or SA-6 South Open Space AOC along with consolidated chromium-impacted soils. As required by the *Alternative and Clean Fill Guidance for SRP Sites* guidance document, Honeywell performed a "Like-on-Like" and "75th percentile analyses" on the historic fill soil sample results for the Open Space Areas at each Site. As explained in the August 19, 2014 letter, since conditions of the "75th percentile analyses" were not met, Honeywell sought a variance in accordance with Section 5.2 of the *Alternative and Clean Fill Guidance for SRP Sites* guidance document. Honeywell provided clarifying information on September 12, 2014 in response to verbal questions posed by NJDEP. Subsequently, in a September 15, 2014 letter to all Parties, Arnold and Porter clarified the proposal request to NJDEP in response to a September 9, 2014 letter from Plaintiffs. In response to Honeywell's written response and information subsequently provided, NJDEP sent an electronic mail to Honeywell approving of the proposed plan on October 15, 2014.

**Debris**

A larger volume than expected of debris was encountered comingled with soil in the eastern (Sites 124 and 125) and central (Site 134) portions of the SA-6 South excavation areas. The debris consisted of creosote-impacted piles from below buildings, concrete pieces, tires, sections of pipes, miscellaneous unrecognizable pieces of metal, general household items, etc. The debris co-mingled with soils that were being evaluated for reuse (i.e. soils previously classified as <20 mg/kg for hexavalent chromium) or those designated for consolidation in the Open Space AOC (i.e. soils previously classified as between 20 and 1,000 mg/kg for hexavalent chromium), posed a concern for jeopardizing the desired geotechnical properties of the re-compacted soil. Therefore, Entact mechanically separated the debris from soils designated for reuse or consolidation using the buckets of excavation equipment. The debris-free soil was then considered suitable for reuse or consolidation. The debris was disposed of offsite, totaling 315 tons. Entact did not separate debris comingled with soil already designated for offsite disposal. The soil co-mingled with the debris was loaded into trucks for offsite disposal.

# SA-6 SOUTH




NOTES:

Grab samples were collected randomly by breaking asphalt down to the soil interface.

LEGEND:

Asphalt Sample Point

| REV | DATE | BY | CHK'D | APR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| | | | | | |

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

DRAWING NAME: Asphalt Sample Locations

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | REV | 1 |
| DATE | 10/15/13 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

**APPENDIX J-2**
**HYDROCARBON-IMPACTED SOIL**

**Hydrocarbon-Impacted Soil**

Initially based upon findings during the PDI borings, it was believed that a very limited quantity of hydrocarbon-impacted soil would be encountered primarily in the eastern part of the Site and that this limited quantity of hydrocarbon-impacted soil would be disposed of offsite. However, as the quantity of the hydrocarbon-impacted soil grew, it became apparent that alternatives to offsite disposal were necessary. Amec Foster Wheeler evaluated whether the hydrocarbon-impacted soils could be consolidated in the Open Space AOC along with other chromium-impacted soils that were <1,000 mg/kg for hexavalent chromium. Since the cap constructed over the Open Space AOC incorporates passive venting, Amec Foster Wheeler evaluated the inhalation risk associated with volatile organics and semi-volatile organic COCs in the hydrocarbon-impacted soil. This evaluation determined that any VOCs and naphthalene that were below their respective NJDEP inhalation-based residential standards would not pose an unacceptable inhalation risk or cause nuisance odors if the hydrocarbon-impacted soils were consolidated and capped in the Open Space AOC as approved by the NJDEP and indicated in DCB 012. Hydrocarbon-impacted soils that did not meet the NJDEP inhalation-based residential standards were shipped offsite for disposal.

The characterization sampling of the stockpiled hydrocarbon-impacted soils indicated that certain samples of this material exhibited selected metals and/or polynuclear aromatic hydrocarbons (PAHs) above the NJDEP Impact to Groundwater (IGW) standards. For such samples, representative portions of the stockpiles were subsequently re-sampled for Synthetic Precipitation Leaching Procedure (SPLP) analysis for the COCs above the IGW standards to evaluate the potential for the material to impact groundwater. In all such cases, the SPLP results were below the default leachate criteria for Class II groundwater. Two samples also exhibited select metals above NJDEP Residential Direct Contact Soil Remediation Standards (RDCSRS) and IGW standards. While these samples were tested for SPLP metals, not all of the SPLP default leachate criteria were met.

On August 25, 2014 via electronic mail, Honeywell requested approval from NJDEP to consolidate the remaining 24,000 CYs hydrocarbon-impacted material within the SA-6 South Open Space AOC along with other chromium-impacted soils that are <1,000 mg/kg for hexavalent chromium as long as the hydrocarbon-impacted soils meet the NJDEP inhalation-based residential standards. Honeywell's electronic mail included an August 20, 2014 memo prepared by Amec Foster Wheeler which, using the *Alternative and Clean Fill Guidance for SRP Sites* as a guide, outlined why this approach is consistent with the TRSR. Based upon a follow-up telephone conversation between Honeywell, NJDEP, and Amec Foster Wheeler on September 26, 2014, NJDEP sent an electronic mail to Honeywell

approving the proposed plan on October 2, 2014. Based upon the memo, supplemental information provided, and the September 26, 2014 conversation, NJDEP agreed that this approach is consistent with the TRSR for the following reasons:

- The Open Space AOC is completely contained with a hydraulic barrier and a cap.
- The contaminants and concentrations detected in the hydrocarbon-impacted soils are generally similar to those detected in the historic fill soils and are lower than the maximum values in the historic fill. Thus, the Like-on-Like requirement specified in the *Alternative and Clean Fill Guidance for SRP Sites* is satisfied.
- Extractable Petroleum Hydrocarbon (EPH) data were < 1,700 mg/kg; therefore, EPH was not a concern.
- Generally, the highest levels of PAHs in the hydrocarbon-impacted soils were associated with samples also with elevated naphthalene levels and those soils were disposed offsite.
- Generally, the contaminant concentrations in the hydrocarbon-impacted soils were lower than the maximum concentrations of COCs in the historic fill in the Open Space AOC.
- Only three samples of hydrocarbon-impacted soils exhibited selected metals above the RDCSRS.
- While some metals were detected above the IGW standards in the hydrocarbon-impacted soils, subsequent SPLP analysis for such metals were below the NJDEP Default Leachate Criteria with the exception of two samples for arsenic and one sample for antimony.
- Consolidating the hydrocarbon-impacted soils in the Open Space AOC expanded the remediated area in the Development AOC.
- Given the overall similarity of the hydrocarbon-impacted soils with the historic fill soils in the Open Space AOC, a 75$^{th}$ percentile analysis of the historic fill in the Open Space AOC as specified in the *Alternative and Clean Fill Guidance for SRP Sites* is not warranted.
- As requested by NJDEP, Honeywell agreed to direct Entact to consolidate the few portions of the hydrocarbon-impacted soils that contained PAHs and metals above the standards in the Open Space AOC in the vicinity of existing historic fill with similar COCs/concentrations.

# TABLE A

## Petroleum Soil Sample Results – VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-06-012814 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-08-012814 | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-11-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB57182-1 | | JB57182-2 | | JB58165-1 | | JB58764-1 | | JB58764-2 | | JB58764-3 | | JB58764-4 | | JB58764-5 | | JB58764-6 | | JB60759-1 | | JB60759-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 01/08/2014 | | 01/08/2014 | | 01/20/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 02/27/2014 | | 02/27/2014 | |
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | mg/kg | 290 | 0.3 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| 1,1,2,2-TETRACHLOROETHANE | mg/kg | 1 | 0.007 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 1,1,2-TRICHLOROETHANE | mg/kg | 2 | 0.02 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| 1,1-DICHLOROETHANE | mg/kg | 8 | 0.2 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| 1,1-DICHLOROETHENE | mg/kg | 11 | 0.008 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| 1,2,3-TRICHLOROBENZENE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 1,2,4-TRICHLOROBENZENE | mg/kg | 73 | 0.7 | 0.43 | U | 0.39 | U | 0.35 | U | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | mg/kg | 0.08 | 0.005 | *0.86* | *U* | *0.78* | *U* | *0.7* | *U* | *1.7* | *U* | *0.013* | *U* | *0.011* | *U* | *0.011* | *U* | *0.011* | *U* | *0.012* | *U* | *0.011* | *U* | *0.63* | *U* |
| 1,2-DIBROMOETHANE | mg/kg | 0.008 | 0.005 | *0.086* | *U* | *0.078* | *U* | *0.07* | *U* | *0.17* | *U* | 0.0013 | U | 0.0011 | U | 0.0011 | U | 0.0011 | U | 0.0012 | U | 0.0011 | U | *0.063* | *U* |
| 1,2-DICHLOROBENZENE | mg/kg | 5300 | 17 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 1,2-DICHLOROETHANE | mg/kg | 0.9 | 0.005 | *0.086* | *U* | *0.078* | *U* | *0.07* | *U* | *0.17* | *U* | 0.0013 | U | 0.0011 | U | 0.0011 | U | 0.0011 | U | 0.0012 | U | 0.0011 | U | *0.063* | *U* |
| 1,2-DICHLOROPROPANE | mg/kg | 2 | 0.005 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | *0.0065* | *U* | *0.0057* | *U* | *0.0053* | *U* | *0.0053* | *U* | *0.006* | *U* | *0.0054* | *U* | *0.32* | *U* |
| 1,3-DICHLOROBENZENE | mg/kg | 5300 | 19 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 1,4-DICHLOROBENZENE | mg/kg | 5 | 2 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 2-BUTANONE | mg/kg | 3100 | 0.9 | 0.86 | U | 0.78 | U | 0.7 | U | *1.7* | *U* | 0.013 | U | 0.011 | U | 0.011 | U | 0.011 | U | 0.012 | U | 0.011 | U | 0.63 | U |
| 2-HEXANONE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| 4-METHYL-2-PENTANONE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| ACETONE | mg/kg | 70000 | 19 | 0.86 | U | 0.78 | U | 0.7 | U | 1.7 | U | 0.013 | U | 0.0126 | | 0.027 | | 0.0231 | | 0.0227 | | 0.0078 | J | 0.63 | U |
| BENZENE | mg/kg | 2 | 0.005 | *0.086* | *U* | *0.078* | *U* | *0.07* | *U* | *0.17* | *U* | 0.0013 | U | 0.0011 | U | 0.0011 | U | 0.0011 | U | 0.0012 | U | 0.0011 | U | *0.063* | *U* |
| BROMOCHLOROMETHANE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| BROMODICHLOROMETHANE | mg/kg | 1 | 0.005 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | *0.0065* | *U* | *0.0057* | *U* | *0.0053* | *U* | *0.0053* | *U* | *0.006* | *U* | *0.0054* | *U* | *0.32* | *U* |
| BROMOFORM | mg/kg | 81 | 0.03 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.00053 | J | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| BROMOMETHANE | mg/kg | 25 | 0.04 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| CARBON DISULFIDE | mg/kg | 7800 | 6 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0035 | J | 0.0016 | J | 0.00069 | J | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| CARBON TETRACHLORIDE | mg/kg | 0.6 | 0.005 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | *0.0065* | *U* | *0.0057* | *U* | *0.0053* | *U* | *0.0053* | *U* | *0.006* | *U* | *0.0054* | *U* | *0.32* | *U* |
| CHLOROBENZENE | mg/kg | 510 | 0.6 | 0.43 | U | 0.39 | U | 0.35 | U | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| CHLOROETHANE | mg/kg | 220 | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| CHLOROFORM | mg/kg | 0.6 | 0.4 | *0.43* | *U* | 0.39 | U | 0.35 | U | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| CHLOROMETHANE | mg/kg | 4 | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| CIS-1,2-DICHLOROETHENE | mg/kg | 230 | 0.3 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| CIS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| CYCLOHEXANE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| Dibromochloromethane | mg/kg | 3 | 0.005 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | *0.0065* | *U* | *0.0057* | *U* | *0.0053* | *U* | *0.0053* | *U* | *0.006* | *U* | *0.0054* | *U* | *0.32* | *U* |
| DICHLORODIFLUOROMETHANE | mg/kg | 490 | 39 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| ETHYLBENZENE | mg/kg | 7800 | 13 | 0.0177 | J | 0.078 | U | 0.0289 | J | 0.0877 | J | 0.0013 | U | 0.00048 | J | 0.00097 | J | 0.00033 | J | 0.0012 | U | 0.0011 | U | 0.063 | U |
| ISOPROPYLBENZENE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.0398 | J | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.00061 | J | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| METHYL ACETATE | mg/kg | 78000 | 22 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| METHYL TERT-BUTYL ETHER | mg/kg | 110 | 0.2 | 0.086 | U | 0.078 | U | 0.07 | U | 0.17 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U | 0.0011 | U | 0.0012 | U | 0.0011 | U | 0.063 | U |
| METHYLCYCLOHEXANE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.134 | J | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| METHYLENE CHLORIDE | mg/kg | 34 | 0.01 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| O-XYLENE | mg/kg | NC | NC | 0.086 | U | 0.078 | U | 0.0186 | J | 0.0443 | J | 0.0013 | U | 0.00046 | J | 0.00160 | | 0.00058 | J | 0.00075 | J | 0.0011 | U | 0.063 | U |
| STYRENE | mg/kg | 90 | 3 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| TETRACHLOROETHENE | mg/kg | 2 | 0.005 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | *0.0065* | *U* | *0.0057* | *U* | *0.0053* | *U* | *0.0053* | *U* | *0.006* | *U* | *0.0054* | *U* | *0.32* | *U* |
| TOLUENE | mg/kg | 6300 | 7 | 0.086 | U | 0.078 | U | 0.07 | U | 0.17 | U | 0.0013 | U | 0.0011 | U | 0.00037 | J | 0.0011 | U | 0.0012 | U | 0.0011 | U | 0.063 | U |
| TRANS-1,2-DICHLOROETHENE | mg/kg | 300 | 0.6 | 0.43 | U | 0.39 | U | 0.35 | U | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| TRANS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| TRICHLOROETHENE | mg/kg | 7 | 0.01 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | *0.32* | *U* |
| TRICHLOROFLUOROMETHANE | mg/kg | 23000 | 34 | 0.43 | U | 0.39 | U | 0.35 | U | 0.87 | U | 0.0065 | U | 0.0057 | U | 0.0053 | U | 0.0053 | U | 0.006 | U | 0.0054 | U | 0.32 | U |
| VINYL CHLORIDE | mg/kg | 0.7 | 0.005 | *0.43* | *U* | *0.39* | *U* | *0.35* | *U* | *0.87* | *U* | *0.0065* | *U* | *0.0057* | *U* | *0.0053* | *U* | *0.0053* | *U* | *0.006* | *U* | *0.0054* | *U* | *0.32* | *U* |
| XYLENES, M & P | mg/kg | NC | NC | 0.0454 | J | 0.078 | U | 0.0461 | J | 0.144 | J | 0.0013 | U | 0.00083 | J | 0.00210 | | 0.00063 | J | 0.00089 | J | 0.0011 | U | 0.063 | U |
| XYLENES, TOTAL | mg/kg | 12000 | 19 | 0.0454 | J | 0.078 | U | 0.0648 | J | 0.188 | | 0.0013 | U | 0.0013 | | 0.0037 | | 0.0012 | | 0.0016 | | 0.0011 | U | 0.063 | U |
| TOTAL TICS, ALKANES | mg/kg | | | 0 | | 0 | | 0 | | 0 | | 0.365 | J | 0.0187 | J | 0 | | 0.009 | J | 0 | | 0 | | 0 | |
| TOTAL TICS, VOLATILES | mg/kg | | | 20.41 | J | 15.73 | J | 47.8 | J | 79.5 | J | 0.342 | J | 3.8348 | J | 5.6923 | J | 0.4486 | J | 0.7893 | J | 0.0485 | J | 12.04 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE A

## Petroleum Soil Sample Results – VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-13-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-15-022714 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-19-031214 | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-22-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB60759-3 | | JB60759-4 | | JB60759-5 | | JB60759-6 | | JB60759-7 | | JB61696-1 | | JB61696-2 | | JB61696-3 | | JB61696-4 | | JB62045-1 | | JB62045-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/14/2014 | | 03/14/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1,1-TRICHLOROETHANE | mg/kg | 290 | 0.3 | *2.9* | *U* | 0.3 | U | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| 1,1,2,2-TETRACHLOROETHANE | mg/kg | 1 | 0.007 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 1,1,2-TRICHLOROETHANE | mg/kg | 2 | 0.02 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| 1,1-DICHLOROETHANE | mg/kg | 8 | 0.2 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| 1,1-DICHLOROETHENE | mg/kg | 11 | 0.008 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| 1,2,3-TRICHLOROBENZENE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 1,2,4-TRICHLOROBENZENE | mg/kg | 73 | 0.7 | *2.9* | *U* | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | mg/kg | 0.08 | 0.005 | *5.9* | *U* | *0.61* | *U* | *0.014* | *U* | *1* | *U* | *0.01* | *U* | *0.62* | *U* | *0.63* | *U* | *0.61* | *U* | *0.63* | *U* | *0.0097* | *U* | *0.011* | *U* |
| 1,2-DIBROMOETHANE | mg/kg | 0.008 | 0.005 | *0.59* | *U* | *0.061* | *U* | 0.0014 | U | *0.1* | *U* | 0.001 | U | *0.062* | *U* | *0.063* | *U* | *0.061* | *U* | *0.063* | *U* | 0.00097 | U | 0.0011 | U |
| 1,2-DICHLOROBENZENE | mg/kg | 5300 | 17 | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 1,2-DICHLOROETHANE | mg/kg | 0.9 | 0.005 | *0.59* | *U* | *0.061* | *U* | 0.0014 | U | *0.1* | *U* | 0.001 | U | *0.062* | *U* | *0.063* | *U* | *0.061* | *U* | *0.063* | *U* | 0.00097 | U | 0.0011 | U |
| 1,2-DICHLOROPROPANE | mg/kg | 2 | 0.005 | *2.9* | *U* | *0.3* | *U* | *0.007* | *U* | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | *0.0056* | *U* |
| 1,3-DICHLOROBENZENE | mg/kg | 5300 | 19 | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 1,4-DICHLOROBENZENE | mg/kg | 5 | 2 | *2.9* | *U* | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 2-BUTANONE | mg/kg | 3100 | 0.9 | *5.9* | *U* | 0.61 | U | 0.014 | U | *1* | *U* | 0.01 | U | 0.62 | U | 0.63 | U | 0.61 | U | 0.63 | U | 0.0097 | U | 0.011 | U |
| 2-HEXANONE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| 4-METHYL-2-PENTANONE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| ACETONE | mg/kg | 70000 | 19 | 5.9 | U | 0.61 | U | 0.0115 | J | 1 | U | 0.0088 | J | 0.62 | U | 0.63 | U | 0.61 | U | 0.63 | U | 0.185 | | 0.123 | |
| BENZENE | mg/kg | 2 | 0.005 | *0.59* | *U* | *0.061* | *U* | 0.0014 | U | *0.1* | *U* | 0.001 | U | *0.062* | *U* | *0.063* | *U* | *0.061* | *U* | *0.063* | *U* | 0.00097 | U | 0.0033 | |
| BROMOCHLOROMETHANE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| BROMODICHLOROMETHANE | mg/kg | 1 | 0.005 | *2.9* | *U* | *0.3* | *U* | *0.007* | *U* | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | *0.0056* | *U* |
| BROMOFORM | mg/kg | 81 | 0.03 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| BROMOMETHANE | mg/kg | 25 | 0.04 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| CARBON DISULFIDE | mg/kg | 7800 | 6 | 2.9 | U | 0.3 | U | 0.00087 | J | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.00069 | J | 0.0013 | J |
| CARBON TETRACHLORIDE | mg/kg | 0.6 | 0.005 | *2.9* | *U* | *0.3* | *U* | *0.007* | *U* | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | *0.0056* | *U* |
| CHLOROBENZENE | mg/kg | 510 | 0.6 | *2.9* | *U* | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| CHLOROETHANE | mg/kg | 220 | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| CHLOROFORM | mg/kg | 0.6 | 0.4 | *2.9* | *U* | 0.3 | U | 0.007 | U | *0.5* | *U* | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| CHLOROMETHANE | mg/kg | 4 | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| CIS-1,2-DICHLOROETHENE | mg/kg | 230 | 0.3 | *2.9* | *U* | 0.3 | U | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| CIS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| CYCLOHEXANE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| Dibromochloromethane | mg/kg | 3 | 0.005 | *2.9* | *U* | *0.3* | *U* | *0.007* | *U* | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | *0.0056* | *U* |
| DICHLORODIFLUOROMETHANE | mg/kg | 490 | 39 | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| ETHYLBENZENE | mg/kg | 7800 | 13 | 0.167 | J | 0.082 | | 0.00039 | J | 0.1 | U | 0.00031 | J | 0.062 | U | 0.063 | U | 0.061 | U | 0.063 | U | 0.0008 | J | 0.106 | |
| ISOPROPYLBENZENE | mg/kg | NC | NC | 2.9 | U | 0.0238 | J | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.00027 | J | 0.0176 | |
| METHYL ACETATE | mg/kg | 78000 | 22 | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| METHYL TERT-BUTYL ETHER | mg/kg | 110 | 0.2 | *0.59* | *U* | 0.061 | U | 0.0014 | U | 0.1 | U | 0.001 | U | 0.062 | U | 0.063 | U | 0.061 | U | 0.063 | U | 0.00097 | U | 0.0011 | U |
| METHYLCYCLOHEXANE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.00048 | J |
| METHYLENE CHLORIDE | mg/kg | 34 | 0.01 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.0056 | U |
| O-XYLENE | mg/kg | NC | NC | 0.203 | J | 0.09660 | | 0.00045 | J | 0.1 | U | 0.00032 | J | 0.062 | U | 0.063 | U | 0.061 | U | 0.063 | U | 0.00110 | | 0.1060 | |
| STYRENE | mg/kg | 90 | 3 | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| TETRACHLOROETHENE | mg/kg | 2 | 0.005 | *2.9* | *U* | *0.3* | *U* | *0.007* | *U* | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | *0.0056* | *U* |
| TOLUENE | mg/kg | 6300 | 7 | 0.59 | U | 0.034 | J | 0.0014 | U | 0.1 | U | 0.001 | U | 0.062 | U | 0.063 | U | 0.061 | U | 0.063 | U | 0.00035 | J | 0.0436 | |
| TRANS-1,2-DICHLOROETHENE | mg/kg | 300 | 0.6 | *2.9* | *U* | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| TRANS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| TRICHLOROETHENE | mg/kg | 7 | 0.01 | *2.9* | *U* | *0.3* | *U* | 0.007 | U | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | 0.00039 | J |
| TRICHLOROFLUOROMETHANE | mg/kg | 23000 | 34 | 2.9 | U | 0.3 | U | 0.007 | U | 0.5 | U | 0.005 | U | 0.31 | U | 0.32 | U | 0.31 | U | 0.32 | U | 0.0048 | U | 0.0056 | U |
| VINYL CHLORIDE | mg/kg | 0.7 | 0.005 | *2.9* | *U* | *0.3* | *U* | *0.007* | *U* | *0.5* | *U* | 0.005 | U | *0.31* | *U* | *0.32* | *U* | *0.31* | *U* | *0.32* | *U* | 0.0048 | U | *0.0056* | *U* |
| XYLENES, M & P | mg/kg | NC | NC | 0.524 | J | 0.2560 | | 0.0014 | U | 0.1 | U | 0.001 | U | 0.062 | U | 0.063 | U | 0.061 | U | 0.063 | U | 0.00210 | | 0.2610 | |
| XYLENES, TOTAL | mg/kg | 12000 | 19 | 0.727 | | 0.352 | | 0.00095 | J | 0.0229 | J | 0.00062 | J | 0.062 | U | 0.063 | U | 0.061 | U | 0.063 | U | 0.0032 | | 0.367 | |
| TOTAL TICS, ALKANES | mg/kg | | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0.287 | J | 0 | |
| TOTAL TICS, VOLATILES | mg/kg | | | 321.5 | J | 113.93 | J | 0.111 | J | 27.08 | J | 0.058 | J | 6.67 | J | 18.11 | J | 23.74 | J | 3.48 | J | 0.9 | J | 3.947 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE A

## Petroleum Soil Sample Results – VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID<br>Lab Sample ID<br>Date Sampled | | NJ 2012 MOST | NJ 2013 | 124-A_B-Pet-23-031414<br>JB62045-3<br>03/14/2014 | | 124-A_B-Pet-24-031414<br>JB62045-4<br>03/14/2014 | | 124-A_B-Pet-25-042214<br>JB65312-1A<br>04/22/2014 | | 124-A_B-Pet-26-042214<br>JB65312-2A<br>04/22/2014 | | 124-A_B-Pet-27-052214<br>JB67718-1A<br>05/22/2014 | | 124-A_B-Pet-28-052214<br>JB67718-2A<br>05/22/2014 | | 124-A_B-Pet-29-052214<br>JB67718-3A<br>05/22/2014 | | 124-A_B-Pet-30-052214<br>JB67718-4A<br>05/22/2014 | | 124-A_B-Pet-31-052214<br>JB67718-5A<br>05/22/2014 | | 124-A_B-Pet-32-052214<br>JB67718-6A<br>05/22/2014 | | 124-A_B-Pet-33-052214<br>JB67718-7A<br>05/22/2014 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | mg/kg | 290 | 0.3 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | 0.27 | U |
| 1,1,2,2-TETRACHLOROETHANE | mg/kg | 1 | 0.007 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 1,1,2-TRICHLOROETHANE | mg/kg | 2 | 0.02 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| 1,1-DICHLOROETHANE | mg/kg | 8 | 0.2 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| 1,1-DICHLOROETHENE | mg/kg | 11 | 0.008 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| 1,2,3-TRICHLOROBENZENE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 1,2,4-TRICHLOROBENZENE | mg/kg | 73 | 0.7 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | mg/kg | 0.08 | 0.005 | *0.01* | *U* | *0.01* | *U* | *0.011* | *U* | *0.011* | *U* | *0.58* | *U* | *0.58* | *U* | *0.0099* | *U* | *0.011* | *U* | *0.66* | *U* | *0.01* | *U* | *0.55* | *U* |
| 1,2-DIBROMOETHANE | mg/kg | 0.008 | 0.005 | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | *0.058* | *U* | *0.058* | *U* | 0.00099 | U | 0.0011 | U | *0.066* | *U* | 0.001 | U | *0.055* | *U* |
| 1,2-DICHLOROBENZENE | mg/kg | 5300 | 17 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 1,2-DICHLOROETHANE | mg/kg | 0.9 | 0.005 | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | *0.058* | *U* | *0.058* | *U* | 0.00099 | U | 0.0011 | U | *0.066* | *U* | 0.001 | U | *0.055* | *U* |
| 1,2-DICHLOROPROPANE | mg/kg | 2 | 0.005 | *0.0051* | *U* | 0.005 | U | *0.0054* | *U* | *0.0053* | *U* | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | *0.0053* | *U* | *0.33* | *U* | *0.0052* | *U* | *0.27* | *U* |
| 1,3-DICHLOROBENZENE | mg/kg | 5300 | 19 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 1,4-DICHLOROBENZENE | mg/kg | 5 | 2 | 0.0051 | U | 0.005 | U | 0.0032 | J | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 2-BUTANONE | mg/kg | 3100 | 0.9 | 0.01 | U | 0.01 | U | 0.011 | U | 0.011 | U | 0.58 | U | 0.58 | U | 0.0099 | U | 0.011 | U | 0.66 | U | 0.01 | U | 0.55 | U |
| 2-HEXANONE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| 4-METHYL-2-PENTANONE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| ACETONE | mg/kg | 70000 | 19 | 0.0758 | | 0.189 | | 0.011 | U | 0.011 | U | 0.58 | U | 0.58 | U | 0.0099 | U | 0.011 | U | 0.66 | U | 0.01 | U | 0.55 | U |
| BENZENE | mg/kg | 2 | 0.005 | 0.0019 | | 0.001 | U | 0.0011 | U | 0.0011 | U | *0.058* | *U* | *0.058* | *U* | 0.00099 | U | 0.0011 | U | *0.066* | *U* | 0.001 | U | *0.055* | *U* |
| BROMOCHLOROMETHANE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| BROMODICHLOROMETHANE | mg/kg | 1 | 0.005 | *0.0051* | *U* | 0.005 | U | *0.0054* | *U* | *0.0053* | *U* | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | *0.0053* | *U* | *0.33* | *U* | *0.0052* | *U* | *0.27* | *U* |
| BROMOFORM | mg/kg | 81 | 0.03 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| BROMOMETHANE | mg/kg | 25 | 0.04 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| CARBON DISULFIDE | mg/kg | 7800 | 6 | 0.0014 | J | 0.0021 | J | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.00032 | J | 0.00059 | J | 0.33 | U | 0.0052 | U | 0.27 | U |
| CARBON TETRACHLORIDE | mg/kg | 0.6 | 0.005 | *0.0051* | *U* | 0.005 | U | *0.0054* | *U* | *0.0053* | *U* | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | *0.0053* | *U* | *0.33* | *U* | *0.0052* | *U* | *0.27* | *U* |
| CHLOROBENZENE | mg/kg | 510 | 0.6 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| CHLOROETHANE | mg/kg | 220 | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| CHLOROFORM | mg/kg | 0.6 | 0.4 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| CHLOROMETHANE | mg/kg | 4 | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| CIS-1,2-DICHLOROETHENE | mg/kg | 230 | 0.3 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0022 | J | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | 0.27 | U |
| CIS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| CYCLOHEXANE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| Dibromochloromethane | mg/kg | 3 | 0.005 | *0.0051* | *U* | 0.005 | U | *0.0054* | *U* | *0.0053* | *U* | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | *0.0053* | *U* | *0.33* | *U* | *0.0052* | *U* | *0.27* | *U* |
| DICHLORODIFLUOROMETHANE | mg/kg | 490 | 39 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| ETHYLBENZENE | mg/kg | 7800 | 13 | 0.114 | | 0.0022 | | 0.0011 | U | 0.0011 | U | 0.127 | | 0.106 | | 0.00099 | U | 0.0011 | U | 0.078 | | 0.001 | U | 0.0887 | |
| ISOPROPYLBENZENE | mg/kg | NC | NC | 0.0223 | | 0.00066 | J | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.0157 | J | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| METHYL ACETATE | mg/kg | 78000 | 22 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| METHYL TERT-BUTYL ETHER | mg/kg | 110 | 0.2 | 0.001 | U | 0.001 | U | 0.0011 | U | 0.0011 | U | 0.058 | U | 0.058 | U | 0.00099 | U | 0.0011 | U | 0.066 | U | 0.001 | U | 0.055 | U |
| METHYLCYCLOHEXANE | mg/kg | NC | NC | 0.00048 | J | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.0787 | J | 0.0167 | J | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| METHYLENE CHLORIDE | mg/kg | 34 | 0.01 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| O-XYLENE | mg/kg | NC | NC | 0.1250 | | 0.00260 | | 0.0011 | U | 0.0011 | U | 0.0269 | J | 0.0225 | J | 0.00099 | U | 0.0011 | U | 0.0339 | J | 0.001 | U | 0.0121 | J |
| STYRENE | mg/kg | 90 | 3 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| TETRACHLOROETHENE | mg/kg | 2 | 0.005 | *0.0051* | *U* | 0.005 | U | *0.0054* | *U* | *0.0053* | *U* | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | *0.0053* | *U* | *0.33* | *U* | *0.0052* | *U* | *0.27* | *U* |
| TOLUENE | mg/kg | 6300 | 7 | 0.0276 | | 0.00066 | J | 0.0011 | U | 0.0011 | U | 0.0123 | J | 0.058 | U | 0.00099 | U | 0.0011 | U | 0.066 | U | 0.001 | U | 0.055 | U |
| TRANS-1,2-DICHLOROETHENE | mg/kg | 300 | 0.6 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| TRANS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| TRICHLOROETHENE | mg/kg | 7 | 0.01 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.00084 | J | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | 0.0053 | U | *0.33* | *U* | 0.0052 | U | *0.27* | *U* |
| TRICHLOROFLUOROMETHANE | mg/kg | 23000 | 34 | 0.0051 | U | 0.005 | U | 0.0054 | U | 0.0053 | U | 0.29 | U | 0.29 | U | 0.0049 | U | 0.0053 | U | 0.33 | U | 0.0052 | U | 0.27 | U |
| VINYL CHLORIDE | mg/kg | 0.7 | 0.005 | *0.0051* | *U* | 0.005 | U | *0.0054* | *U* | *0.0053* | *U* | *0.29* | *U* | *0.29* | *U* | 0.0049 | U | *0.0053* | *U* | *0.33* | *U* | *0.0052* | *U* | *0.27* | *U* |
| XYLENES, M & P | mg/kg | NC | NC | 0.2870 | | 0.00550 | | 0.0011 | U | 0.0011 | U | 0.2560 | | 0.3380 | | 0.00099 | U | 0.0011 | U | 0.1940 | | 0.001 | U | 0.1130 | |
| XYLENES, TOTAL | mg/kg | 12000 | 19 | 0.412 | | 0.0081 | | 0.0011 | U | 0.0011 | U | 0.283 | | 0.36 | | 0.00099 | U | 0.0011 | U | 0.228 | | 0.001 | U | 0.125 | |
| TOTAL TICS, ALKANES | mg/kg | | | 0 | | 0.012 | J | 0.206 | J | 0 | | 4.9 | J | 6.3 | J | 0.211 | J | 0.113 | J | 0 | | 0 | | 0 | |
| TOTAL TICS, VOLATILES | mg/kg | | | 2.919 | J | 1.981 | J | 0.753 | J | 0.331 | J | 66.3 | J | 24.1 | J | 0.442 | J | 0.582 | J | 6.92 | J | 0 | | 48.5 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE A

## Petroleum Soil Sample Results – VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID<br>Lab Sample ID<br>Date Sampled | | NJ 2012 MOST | NJ 2013 | 124-A_B-Pet-34-060414<br>JB68443-1A<br>06/04/2014 | | 124-A_B-Pet-35-060414<br>JB68443-2A<br>06/04/2014 | | 124-A_B-Pet-36-060414<br>JB68443-3A<br>06/04/2014 | | 124-A_B-Pet-37-060414<br>JB68443-4A<br>06/04/2014 | | 124-A_B-Pet-38-062714<br>JB70484-1A<br>06/27/2014 | | 124-A_B-Pet-39-062714<br>JB70484-2A<br>06/27/2014 | | 124-A_B-Pet-40-062714<br>JB70484-3A<br>06/27/2014 | | 124-A_B-Pet-41-062714<br>JB70484-4A<br>06/27/2014 | | 124-A_B-Pet-42-062714<br>JB70484-5A<br>06/27/2014 | | 124-A_B-Pet-43-081414<br>JB74045-1<br>08/14/2014 | | 124-A_B-Pet-44-081414<br>JB74045-2<br>08/14/2014 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | mg/kg | 290 | 0.3 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| 1,1,2,2-TETRACHLOROETHANE | mg/kg | 1 | 0.007 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| 1,1,2-TRICHLOROETHANE | mg/kg | 2 | 0.02 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| 1,1-DICHLOROETHANE | mg/kg | 8 | 0.2 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 1,1-DICHLOROETHENE | mg/kg | 11 | 0.008 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 1,2,3-TRICHLOROBENZENE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| 1,2,4-TRICHLOROBENZENE | mg/kg | 73 | 0.7 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | mg/kg | 0.08 | 0.005 | *0.0092* | *U* | *0.01* | *U* | *0.0093* | *U* | *0.0092* | *U* | *0.0056* | *U* | 0.0045 | U | *0.0052* | *U* | *0.0091* | *U* | *0.0067* | *U* | *0.0054* | *U* | *0.0053* | *U* |
| 1,2-DIBROMOETHANE | mg/kg | 0.008 | 0.005 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 1,2-DICHLOROBENZENE | mg/kg | 5300 | 17 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 1,2-DICHLOROETHANE | mg/kg | 0.9 | 0.005 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 1,2-DICHLOROPROPANE | mg/kg | 2 | 0.005 | 0.0046 | U | *0.0052* | *U* | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| 1,3-DICHLOROBENZENE | mg/kg | 5300 | 19 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 1,4-DICHLOROBENZENE | mg/kg | 5 | 2 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| 2-BUTANONE | mg/kg | 3100 | 0.9 | 0.0092 | U | 0.01 | U | 0.0093 | U | 0.0092 | U | 0.011 | U | 0.0091 | U | 0.01 | U | 0.018 | U | 0.013 | U | 0.011 | U | 0.011 | U |
| 2-HEXANONE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| 4-METHYL-2-PENTANONE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| ACETONE | mg/kg | 70000 | 19 | 0.0092 | U | 0.01 | U | 0.0093 | U | 0.0092 | U | 0.0299 | | 0.0234 | | 0.0206 | | 0.018 | U | 0.0203 | | 0.011 | U | 0.0057 | J |
| BENZENE | mg/kg | 2 | 0.005 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.00056 | U | 0.00045 | U | 0.00052 | U | 0.00091 | U | 0.00067 | U | 0.00054 | U | 0.00053 | U |
| BROMOCHLOROMETHANE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| BROMODICHLOROMETHANE | mg/kg | 1 | 0.005 | 0.0046 | U | *0.0052* | *U* | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| BROMOFORM | mg/kg | 81 | 0.03 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| BROMOMETHANE | mg/kg | 25 | 0.04 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| CARBON DISULFIDE | mg/kg | 7800 | 6 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0011 | J | 0.0033 | | 0.00092 | J | 0.001 | J | 0.0022 | U | 0.0021 | U |
| CARBON TETRACHLORIDE | mg/kg | 0.6 | 0.005 | 0.0046 | U | *0.0052* | *U* | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.001 | J | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| CHLOROBENZENE | mg/kg | 510 | 0.6 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0033 | | 0.0174 | | 0.0034 | | 0.0022 | J | 0.00089 | J | 0.0022 | U | 0.0021 | U |
| CHLOROETHANE | mg/kg | 220 | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| CHLOROFORM | mg/kg | 0.6 | 0.4 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.00036 | J | 0.0029 | | 0.0042 | | 0.00074 | J | 0.00072 | J | 0.0022 | U | 0.0021 | U |
| CHLOROMETHANE | mg/kg | 4 | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| CIS-1,2-DICHLOROETHENE | mg/kg | 230 | 0.3 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| CIS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| CYCLOHEXANE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| Dibromochloromethane | mg/kg | 3 | 0.005 | 0.0046 | U | *0.0052* | *U* | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| DICHLORODIFLUOROMETHANE | mg/kg | 490 | 39 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| ETHYLBENZENE | mg/kg | 7800 | 13 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| ISOPROPYLBENZENE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.00027 | J | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| METHYL ACETATE | mg/kg | 78000 | 22 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| METHYL TERT-BUTYL ETHER | mg/kg | 110 | 0.2 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| METHYLCYCLOHEXANE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.00067 | J |
| METHYLENE CHLORIDE | mg/kg | 34 | 0.01 | 0.0046 | U | 0.0019 | J | 0.0047 | U | 0.0046 | U | 0.0023 | J | 0.0016 | J | 0.0019 | J | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| O-XYLENE | mg/kg | NC | NC | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| STYRENE | mg/kg | 90 | 3 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| TETRACHLOROETHENE | mg/kg | 2 | 0.005 | 0.0046 | U | *0.0052* | *U* | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| TOLUENE | mg/kg | 6300 | 7 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| TRANS-1,2-DICHLOROETHENE | mg/kg | 300 | 0.6 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| TRANS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| TRICHLOROETHENE | mg/kg | 7 | 0.01 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| TRICHLOROFLUOROMETHANE | mg/kg | 23000 | 34 | 0.0046 | U | 0.0052 | U | 0.0047 | U | 0.0046 | U | 0.0056 | U | 0.0045 | U | 0.0052 | U | 0.0091 | U | 0.0067 | U | 0.0054 | U | 0.0053 | U |
| VINYL CHLORIDE | mg/kg | 0.7 | 0.005 | 0.0046 | U | *0.0052* | *U* | 0.0047 | U | 0.0046 | U | 0.0022 | U | 0.0018 | U | 0.0021 | U | 0.0036 | U | 0.0027 | U | 0.0022 | U | 0.0021 | U |
| XYLENES, M & P | mg/kg | NC | NC | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| XYLENES, TOTAL | mg/kg | 12000 | 19 | 0.00092 | U | 0.001 | U | 0.00093 | U | 0.00092 | U | 0.0011 | U | 0.00091 | U | 0.001 | U | 0.0018 | U | 0.0013 | U | 0.0011 | U | 0.0011 | U |
| TOTAL TICS, ALKANES | mg/kg | | | 0.0077 | J | 0.246 | J | 0.074 | J | 0.55 | J | 0 | | 0.011 | J | 0 | | 0 | | 0 | | 0 | | 0 | |
| TOTAL TICS, VOLATILES | mg/kg | | | 0.1384 | J | 0.686 | J | 0.287 | J | 1.819 | J | 0.0266 | J | 0.1977 | J | 0.75 | J | 0 | | 0.0069 | J | 0.0063 | J | 0.0335 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE A

## Petroleum Soil Sample Results – VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID<br>Lab Sample ID<br>Date Sampled | | NJ 2012 MOST | NJ 2013 | 124-A_B-Pet-45-081414<br>JB74045-3<br>08/14/2014 | | 124-A_B-Pet-46-081914<br>JB74372-1<br>08/19/2014 | | 124-A_B-Pet-47-090514<br>JB75848-1<br>09/05/2014 | | 124-A_B-Pet-48-090514<br>JB75848-2<br>09/05/2014 | | 124-A_B-Pet-49-090514<br>JB75848-3<br>09/05/2014 | | 124-A_B-Pet-50-102414<br>JB80064-1<br>10/24/2014 | | 124-A_B-Pet-51-102414<br>JB80064-2<br>10/24/2014 | | 124-A_B-Pet-52-102414<br>JB80064-3<br>10/24/2014 | | 124-A_B-Pet-53-102414<br>JB80064-4<br>10/24/2014 | | 124-C-Pet-01-102414<br>JB80065-1<br>10/24/2014 | | 134-SB-604-0627<br>JB70486-1A<br>06/27/2014 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | mg/kg | 290 | 0.3 | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| 1,1,2,2-TETRACHLOROETHANE | mg/kg | 1 | 0.007 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | mg/kg | NC | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.002 | J | 0.0071 | U | 0.0049 | U |
| 1,1,2-TRICHLOROETHANE | mg/kg | 2 | 0.02 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| 1,1-DICHLOROETHANE | mg/kg | 8 | 0.2 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 1,1-DICHLOROETHENE | mg/kg | 11 | 0.008 | 0.0011 | U | *0.054* | *U* | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 1,2,3-TRICHLOROBENZENE | mg/kg | NC | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| 1,2,4-TRICHLOROBENZENE | mg/kg | 73 | 0.7 | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | mg/kg | 0.08 | 0.005 | *0.0053* | *U* | *0.27* | *U* | *0.0054* | *U* | 0.0049 | U | *0.0053* | *U* | *0.0059* | *U* | 0.0046 | U | 0.0042 | U | *0.0068* | *U* | *0.0071* | *U* | 0.0049 | U |
| 1,2-DIBROMOETHANE | mg/kg | 0.008 | 0.005 | 0.0011 | U | *0.054* | *U* | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 1,2-DICHLOROBENZENE | mg/kg | 5300 | 17 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 1,2-DICHLOROETHANE | mg/kg | 0.9 | 0.005 | 0.0011 | U | *0.054* | *U* | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 1,2-DICHLOROPROPANE | mg/kg | 2 | 0.005 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| 1,3-DICHLOROBENZENE | mg/kg | 5300 | 19 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 1,4-DICHLOROBENZENE | mg/kg | 5 | 2 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| 2-BUTANONE | mg/kg | 3100 | 0.9 | 0.011 | U | 0.54 | U | 0.011 | U | 0.0097 | U | 0.011 | U | 0.012 | U | 0.0092 | U | 0.0084 | U | 0.014 | U | 0.014 | U | 0.0097 | U |
| 2-HEXANONE | mg/kg | NC | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| 4-METHYL-2-PENTANONE | mg/kg | NC | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| ACETONE | mg/kg | 70000 | 19 | 0.0068 | J | 0.54 | U | 0.011 | U | 0.0097 | U | 0.011 | U | 0.012 | U | 0.0065 | J | 0.0339 | | 0.014 | U | 0.014 | U | 0.014 | |
| BENZENE | mg/kg | 2 | 0.005 | 0.00053 | U | *0.027* | *U* | 0.00054 | U | 0.00049 | U | 0.00053 | U | 0.00059 | U | 0.0002 | J | 0.00042 | U | 0.00069 | | 0.00092 | | 0.00049 | U |
| BROMOCHLOROMETHANE | mg/kg | NC | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| BROMODICHLOROMETHANE | mg/kg | 1 | 0.005 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| BROMOFORM | mg/kg | 81 | 0.03 | 0.0053 | U | *0.27* | *U* | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| BROMOMETHANE | mg/kg | 25 | 0.04 | 0.0053 | U | *0.27* | *U* | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| CARBON DISULFIDE | mg/kg | 7800 | 6 | 0.00054 | J | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.00041 | J | 0.00066 | J | 0.0018 | | 0.00046 | J | 0.0028 | U | 0.00062 | J |
| CARBON TETRACHLORIDE | mg/kg | 0.6 | 0.005 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| CHLOROBENZENE | mg/kg | 510 | 0.6 | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0779 | |
| CHLOROETHANE | mg/kg | 220 | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| CHLOROFORM | mg/kg | 0.6 | 0.4 | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.00052 | J | 0.0027 | U | 0.0028 | U | 0.00048 | J |
| CHLOROMETHANE | mg/kg | 4 | NC | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| CIS-1,2-DICHLOROETHENE | mg/kg | 230 | 0.3 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.00048 | J | 0.00097 | U |
| CIS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| CYCLOHEXANE | mg/kg | NC | NC | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.00083 | J | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| Dibromochloromethane | mg/kg | 3 | 0.005 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| DICHLORODIFLUOROMETHANE | mg/kg | 490 | 39 | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| ETHYLBENZENE | mg/kg | 7800 | 13 | 0.0011 | U | 0.0173 | J | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00083 | J | 0.00033 | J | 0.0014 | U | 0.0014 | U | 0.0036 | |
| ISOPROPYLBENZENE | mg/kg | NC | NC | 0.0053 | U | 0.0169 | J | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.00031 | J | 0.0042 | U | 0.00095 | J | 0.0071 | U | 0.00023 | J |
| METHYL ACETATE | mg/kg | 78000 | 22 | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| METHYL TERT-BUTYL ETHER | mg/kg | 110 | 0.2 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| METHYLCYCLOHEXANE | mg/kg | NC | NC | 0.0021 | U | 0.168 | | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.002 | | 0.00019 | J | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| METHYLENE CHLORIDE | mg/kg | 34 | 0.01 | 0.0053 | U | *0.27* | *U* | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0022 | J | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| O-XYLENE | mg/kg | NC | NC | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00200 | | 0.00077 | J | 0.0014 | U | 0.0005 | J | 0.00810 | |
| STYRENE | mg/kg | 90 | 3 | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| TETRACHLOROETHENE | mg/kg | 2 | 0.005 | 0.0011 | U | *0.054* | *U* | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| TOLUENE | mg/kg | 6300 | 7 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00054 | J | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| TRANS-1,2-DICHLOROETHENE | mg/kg | 300 | 0.6 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0014 | U | 0.00097 | U |
| TRANS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0021 | U | 0.11 | U | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| TRICHLOROETHENE | mg/kg | 7 | 0.01 | 0.0011 | U | *0.054* | *U* | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00092 | U | 0.00084 | U | 0.0014 | U | 0.0023 | | 0.00097 | U |
| TRICHLOROFLUOROMETHANE | mg/kg | 23000 | 34 | 0.0053 | U | 0.27 | U | 0.0054 | U | 0.0049 | U | 0.0053 | U | 0.0059 | U | 0.0046 | U | 0.0042 | U | 0.0068 | U | 0.0071 | U | 0.0049 | U |
| VINYL CHLORIDE | mg/kg | 0.7 | 0.005 | 0.0021 | U | *0.11* | *U* | 0.0022 | U | 0.0019 | U | 0.0021 | U | 0.0024 | U | 0.0018 | U | 0.0017 | U | 0.0027 | U | 0.0028 | U | 0.0019 | U |
| XYLENES, M & P | mg/kg | NC | NC | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.00160 | | 0.00082 | J | 0.0014 | U | 0.0014 | U | 0.00380 | |
| XYLENES, TOTAL | mg/kg | 12000 | 19 | 0.0011 | U | 0.054 | U | 0.0011 | U | 0.00097 | U | 0.0011 | U | 0.0012 | U | 0.0036 | | 0.0016 | | 0.0014 | U | 0.0005 | J | 0.0119 | |
| TOTAL TICS, ALKANES | mg/kg | | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0.0456 | J | 0 | | 0 | | 0 | | 0 | |
| TOTAL TICS, VOLATILES | mg/kg | | | 0 | | 159 | J | 0.03 | J | 0.0676 | J | 0.0499 | J | 0.0342 | J | 0.1223 | J | 0.2666 | J | 0.0303 | J | 0.009 | J | 0.0626 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# TABLE B

## Petroleum Soil Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-06-012814 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-08-012814 | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-11-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB57182-1 | | JB57182-2 | | JB58165-1 | | JB58764-1 | | JB58764-2 | | JB58764-3 | | JB58764-4 | | JB58764-5 | | JB58764-6 | | JB60759-1 | | JB60759-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 01/08/2014 | | 01/08/2014 | | 01/20/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 02/27/2014 | | 02/27/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1'-BIPHENYL | mg/kg | 3100 | 140 | 0.032 | J | 0.103 | | 0.176 | | 0.721 | | 0.646 | | 0.723 | | 0.0664 | J | 0.346 | | 0.246 | | 0.805 | | 0.855 | |
| 1,2,4,5-TETRACHLOROBENZENE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 1,4-DIOXANE | mg/kg | NC | NC | - | | - | | - | | 0.038 | U | 0.036 | U | 0.036 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.035 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | mg/kg | 23 | 5 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 2,3,4,6-TETRACHLOROPHENOL | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 2,4,5-TRICHLOROPHENOL | mg/kg | 6100 | 68 | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 2,4,6-TRICHLOROPHENOL | mg/kg | 19 | 0.2 | 0.18 | U | 0.19 | U | *0.21* | *U* | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 2,4-DICHLOROPHENOL | mg/kg | 180 | 0.2 | 0.18 | U | 0.19 | U | *0.21* | *U* | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 2,4-DIMETHYLPHENOL | mg/kg | 1200 | 1 | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 2,4-DINITROPHENOL | mg/kg | 120 | 0.3 | *0.73* | *U* | *0.76* | *U* | *0.83* | *U* | *0.75* | *U* | *0.72* | *U* | *0.72* | *U* | *0.75* | *U* | *0.71* | *U* | *0.77* | *U* | *0.71* | *UJ* | *0.69* | *UJ* |
| 2,4-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.036 | U | 0.038 | U | 0.042 | U | 0.038 | U | 0.036 | U | 0.036 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.035 | U |
| 2,6-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.036 | U | 0.038 | U | 0.042 | U | 0.038 | U | 0.036 | U | 0.036 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.035 | U |
| 2-CHLORONAPHTHALENE | mg/kg | NC | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 2-CHLOROPHENOL | mg/kg | 310 | 0.8 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 2-METHYLNAPHTHALENE | mg/kg | 230 | 8 | 0.27 | | 1.01 | | 2.25 | | 1.99 | | 1.56 | | 2.24 | | 0.568 | | 1.03 | | 0.813 | | 1.87 | | 2.58 | |
| 2-METHYLPHENOL | mg/kg | 310 | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 2-NITROANILINE | mg/kg | 39 | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 2-NITROPHENOL | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 3&4-METHYLPHENOL | mg/kg | NC | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 3,3'-DICHLOROBENZIDINE | mg/kg | 1 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 3-NITROANILINE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 4,6-DINITRO-2-METHYLPHENOL | mg/kg | 6 | 0.3 | *0.73* | *U* | *0.76* | *U* | *0.83* | *U* | *0.75* | *U* | *0.72* | *U* | *0.72* | *U* | *0.75* | *U* | *0.71* | *U* | *0.77* | *U* | *0.71* | *U* | *0.69* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 4-CHLORO-3-METHYLPHENOL | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 4-CHLOROANILINE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 4-CHLOROPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| 4-NITROANILINE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| 4-NITROPHENOL | mg/kg | NC | NC | 0.36 | U | 0.38 | U | 0.42 | U | 0.38 | U | 0.36 | U | 0.36 | U | 0.37 | U | 0.35 | U | 0.38 | U | 0.36 | U | 0.35 | U |
| ACENAPHTHENE | mg/kg | 3400 | 110 | 0.0987 | | 0.231 | | 0.486 | | 2.65 | | 2.47 | | 2.07 | | 0.484 | | 1.38 | | 0.996 | | 3.53 | | 2.44 | |
| ACENAPHTHYLENE | mg/kg | 300000 | NC | 0.036 | U | 0.151 | | 0.042 | U | 0.202 | | 0.2 | | 0.249 | | 0.0278 | J | 0.119 | | 0.0928 | | 0.19 | | 0.138 | |
| ACETOPHENONE | mg/kg | 2 | 3 | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| ANTHRACENE | mg/kg | 17000 | 2400 | 0.132 | | 0.287 | | 0.624 | | 3.56 | | 3.49 | | 2.62 | | 0.803 | | 13.1 | | 8.92 | | 31 | | 17.6 | |
| ATRAZINE | mg/kg | 210 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| BENZALDEHYDE | mg/kg | 6100 | NC | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| BENZO(A)ANTHRACENE | mg/kg | 0.6 | 0.8 | 0.22 | | 0.339 | | **0.841** | | **1.18** | | **1.1** | | **1.09** | | 0.154 | | **1.06** | | **0.691** | | **2.19** | | **1.34** | |
| BENZO(A)PYRENE | mg/kg | 0.2 | 0.2 | **0.213** | | **0.322** | | **0.843** | | **0.646** | | **0.424** | | **0.616** | | 0.096 | | **0.552** | | **0.434** | | **0.729** | | **0.394** | |
| BENZO(B)FLUORANTHENE | mg/kg | 0.6 | 2 | 0.259 | | 0.396 | | **1** | | **0.89** | | **0.726** | | **0.888** | | 0.134 | | **0.927** | | **0.601** | | **1.75** | | **0.806** | |
| BENZO(G,H,I)PERYLENE | mg/kg | 30000 | NC | 0.145 | | 0.245 | | 0.51 | | 0.322 | | 0.19 | | 0.352 | | 0.0489 | | 0.278 | | 0.207 | | 0.361 | | 0.18 | |
| BENZO(K)FLUORANTHENE | mg/kg | 6 | 25 | 0.0948 | | 0.137 | | 0.434 | | 0.298 | | 0.238 | | 0.299 | | 0.0464 | | 0.296 | | 0.244 | | 0.575 | | 0.213 | |
| BIS(2-CHLOROETHOXY)METHANE | mg/kg | NC | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| BIS(2-CHLOROETHYL)ETHER | mg/kg | 0.4 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | mg/kg | 35 | 1200 | 0.185 | | 4.52 | | 0.672 | | 0.0889 | | 0.0642 | J | 0.0912 | | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.0535 | J |
| BUTYLBENZYL PHTHALATE | mg/kg | 1200 | 230 | 0.073 | U | 0.576 | | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| CAPROLACTAM | mg/kg | 31000 | 12 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| CARBAZOLE | mg/kg | 24 | NC | 0.0634 | J | 0.0576 | J | 0.131 | | 1.42 | | 1.37 | | 0.985 | | 0.45 | | 5.54 | | 2.91 | | 12.7 | | 7.1 | |
| CHRYSENE | mg/kg | 62 | 80 | 0.247 | | 0.326 | | 0.952 | | 1.31 | | 1.22 | | 1.22 | | 0.194 | | 1.35 | | 0.871 | | 2.51 | | 1.28 | |
| DI-N-BUTYL PHTHALATE | mg/kg | 6100 | 760 | 0.073 | U | 0.112 | | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| DI-N-OCTYL PHTHALATE | mg/kg | 2400 | 3300 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| DIBENZO(A,H)ANTHRACENE | mg/kg | 0.2 | 0.8 | 0.0406 | | 0.0637 | | 0.133 | | 0.101 | | 0.068 | | 0.108 | | 0.0151 | J | 0.0829 | | 0.0645 | | 0.139 | | 0.0685 | |
| DIBENZOFURAN | mg/kg | NC | NC | 0.151 | | 0.182 | | 0.511 | | 2.76 | | 2.84 | | 2.54 | | 0.341 | | 1.59 | | 1.12 | | 4.65 | | 3.12 | |
| DIETHYL PHTHALATE | mg/kg | 49000 | 88 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| DIMETHYL PHTHALATE | mg/kg | NC | NC | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| FLUORANTHENE | mg/kg | 2300 | 1300 | 0.515 | | 0.745 | | 2.04 | | 6.53 | | 4.76 | | 5.2 | | 0.657 | | 5.22 | | 2.37 | | 12.9 | | 6.98 | |
| FLUORENE | mg/kg | 2300 | 170 | 0.325 | | 0.529 | | 0.727 | | 3.17 | | 2.93 | | 1.91 | | 0.438 | | 2.42 | | 1.62 | | 5.46 | | 3.44 | |
| HEXACHLOROBENZENE | mg/kg | 0.3 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| HEXACHLOROBUTADIENE | mg/kg | 6 | 0.9 | 0.036 | U | 0.038 | U | 0.042 | U | 0.038 | U | 0.036 | U | 0.036 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.035 | U |
| HEXACHLOROCYCLOPENTADIENE | mg/kg | 45 | 320 | 0.36 | U | 0.38 | U | 0.42 | U | 0.38 | U | 0.36 | U | 0.36 | U | 0.37 | U | 0.35 | U | 0.38 | U | 0.36 | U | 0.35 | U |
| HEXACHLOROETHANE | mg/kg | 35 | 0.2 | 0.18 | U | 0.19 | U | *0.21* | *U* | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| INDENO(1,2,3-CD)PYRENE | mg/kg | 0.6 | 7 | 0.147 | | 0.215 | | 0.526 | | 0.34 | | 0.207 | | 0.359 | | 0.051 | | 0.293 | | 0.221 | | 0.372 | | 0.172 | |
| ISOPHORONE | mg/kg | 510 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| N-NITROSO-DI-N-PROPYLAMINE | mg/kg | 0.2 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| N-NITROSODIPHENYLAMINE | mg/kg | 99 | 0.4 | 0.18 | U | 0.19 | U | 0.21 | U | 0.19 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U |
| NAPHTHALENE | mg/kg | 6 | 25 | 0.0682 | | 0.109 | | 0.859 | | **6.53** | | 3.09 | | 4.41 | | 2.59 | | 1.34 | | 1.21 | | **7.62** | | 4.34 | |
| NITROBENZENE | mg/kg | 31 | 0.2 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| PHENANTHRENE | mg/kg | 300000 | NC | 0.655 | | 1.49 | | 2.48 | | 11.9 | | 8.91 | | 9.66 | | 0.852 | | 7.47 | | 3.21 | | 20.1 | | 14.5 | |
| PHENOL | mg/kg | 18000 | 8 | 0.073 | U | 0.076 | U | 0.083 | U | 0.075 | U | 0.072 | U | 0.072 | U | 0.075 | U | 0.071 | U | 0.077 | U | 0.071 | U | 0.069 | U |
| PYRENE | mg/kg | 1700 | 840 | 0.463 | | 0.971 | | 1.67 | | 3.02 | | 3.16 | | 2.83 | | 0.455 | | 2.59 | | 1.67 | | 8.04 | | 4.09 | |
| TOTAL TICS, ALKANES | mg/kg | | | 10.49 | J | 41.84 | J | 71.3 | J | 6.05 | J | 6.46 | J | 9.21 | J | 0.41 | J | 6.84 | J | 3.98 | J | 0 | | 0 | |
| TOTAL TICS, SEMI-VOLATILES | mg/kg | | | 14.73 | J | 8.45 | J | 132.3 | J | 12.01 | J | 11.62 | J | 17.07 | J | 5.11 | J | 19.02 | J | 10.59 | J | 15.98 | J | 10.75 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

B: Analyte found in sample and associated blank

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE B

## Petroleum Soil Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-13-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-15-022714 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-19-031214 | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-22-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB60759-3 | | JB60759-4 | | JB60759-5 | | JB60759-6 | | JB60759-7 | | JB61696-1 | | JB61696-2 | | JB61696-3 | | JB61696-4 | | JB62045-1 | | JB62045-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/14/2014 | | 03/14/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1'-BIPHENYL | mg/kg | 3100 | 140 | 20.2 | | 2.37 | | 0.848 | | 0.874 | | 0.252 | | 1.71 | | 2.09 | | 0.899 | | 0.194 | | 0.403 | | 3.49 | |
| 1,2,4,5-TETRACHLOROBENZENE | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 1,4-DIOXANE | mg/kg | NC | NC | 0.038 | U | 0.038 | U | 0.042 | U | 0.046 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.039 | U | 0.034 | U | 0.034 | U | 0.034 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | mg/kg | 23 | 5 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 2,3,4,6-TETRACHLOROPHENOL | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 2,4,5-TRICHLOROPHENOL | mg/kg | 6100 | 68 | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 2,4,6-TRICHLOROPHENOL | mg/kg | 19 | 0.2 | 0.19 | U | 0.19 | U | *0.21* | *U* | *0.23* | *U* | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 2,4-DICHLOROPHENOL | mg/kg | 180 | 0.2 | 0.19 | U | 0.19 | U | *0.21* | *U* | *0.23* | *U* | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 2,4-DIMETHYLPHENOL | mg/kg | 1200 | 1 | 0.807 | J | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 2,4-DINITROPHENOL | mg/kg | 120 | 0.3 | *0.76* | *UJ* | *0.77* | *UJ* | *0.83* | *UJ* | *0.91* | *UJ* | *0.75* | *UJ* | *0.7* | *U* | *0.75* | *U* | *0.77* | *U* | *0.68* | *U* | *0.67* | *U* | *0.68* | *U* |
| 2,4-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.038 | U | 0.038 | U | 0.042 | U | 0.046 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.039 | U | 0.034 | U | 0.034 | U | 0.034 | U |
| 2,6-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.038 | U | 0.038 | U | 0.042 | U | 0.046 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.039 | U | 0.034 | U | 0.034 | U | 0.034 | U |
| 2-CHLORONAPHTHALENE | mg/kg | NC | NC | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 2-CHLOROPHENOL | mg/kg | 310 | 0.8 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 2-METHYLNAPHTHALENE | mg/kg | 230 | 8 | **89.2** | | **9.04** | | 1.75 | | 1.39 | | 0.751 | | 2.21 | | 3.22 | | 1.13 | | 1.02 | | 0.493 | | **13.6** | |
| 2-METHYLPHENOL | mg/kg | 310 | NC | 0.108 | J | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 2-NITROANILINE | mg/kg | 39 | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 2-NITROPHENOL | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 3&4-METHYLPHENOL | mg/kg | NC | NC | 0.4 | J | 0.06 | J | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 3,3'-DICHLOROBENZIDINE | mg/kg | 1 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 3-NITROANILINE | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 4,6-DINITRO-2-METHYLPHENOL | mg/kg | 6 | 0.3 | *0.76* | *U* | *0.77* | *U* | *0.83* | *U* | *0.91* | *U* | *0.75* | *U* | *0.7* | *U* | *0.75* | *U* | *0.77* | *U* | *0.68* | *U* | *0.67* | *U* | *0.68* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 4-CHLORO-3-METHYLPHENOL | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 4-CHLOROANILINE | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 4-CHLOROPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| 4-NITROANILINE | mg/kg | NC | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| 4-NITROPHENOL | mg/kg | NC | NC | 0.38 | U | 0.38 | U | 0.42 | U | 0.46 | U | 0.37 | U | 0.35 | U | 0.38 | U | 0.39 | U | 0.34 | U | 0.34 | U | 0.34 | U |
| ACENAPHTHENE | mg/kg | 3400 | 110 | 64.4 | | 6.49 | | 3.23 | | 3.51 | | 1.19 | | 5.56 | | 8.08 | | 3.31 | | 1.33 | | 2.17 | | 15.3 | |
| ACENAPHTHYLENE | mg/kg | 300000 | NC | 1.93 | J | 0.289 | | 0.248 | | 0.175 | | 0.0867 | | 0.288 | | 0.406 | | 0.174 | | 0.131 | | 0.169 | | 0.493 | |
| ACETOPHENONE | mg/kg | 2 | 3 | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| ANTHRACENE | mg/kg | 17000 | 2400 | 331 | | 32.9 | | 26.9 | | 35.3 | | 11 | | 36.7 | | 39.9 | | 23.5 | | 1.23 | | 3.03 | | 22.6 | |
| ATRAZINE | mg/kg | 210 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| BENZALDEHYDE | mg/kg | 6100 | NC | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| BENZO(A)ANTHRACENE | mg/kg | 0.6 | 0.8 | **18.4** | | **2.96** | | **2.02** | | **1.79** | | **0.869** | | **3.18** | | **4.44** | | **1.8** | | **1.13** | | **1.52** | | **3.46** | |
| BENZO(A)PYRENE | mg/kg | 0.2 | 0.2 | **3.23** | | **0.8** | | **0.909** | | **0.825** | | **0.505** | | **0.962** | | **1.29** | | **0.534** | | **1.09** | | **0.973** | | **1.36** | |
| BENZO(B)FLUORANTHENE | mg/kg | 0.6 | 2 | **7.59** | | **1.52** | | **1.85** | | **1.5** | | **0.807** | | **1.68** | | **2.16** | | **0.943** | | **1.21** | | **1.17** | | **2.3** | |
| BENZO(G,H,I)PERYLENE | mg/kg | 30000 | NC | 1.08 | J | 0.311 | | 0.387 | | 0.368 | | 0.253 | | 0.354 | | 0.497 | | 0.198 | | 0.54 | | 0.416 | | 0.448 | |
| BENZO(K)FLUORANTHENE | mg/kg | 6 | 25 | 1.45 | J | 0.427 | | 0.511 | | 0.396 | | 0.222 | | 0.571 | | 0.726 | | 0.377 | | 0.419 | | 0.379 | | 0.609 | |
| BIS(2-CHLOROETHOXY)METHANE | mg/kg | NC | NC | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| BIS(2-CHLOROETHYL)ETHER | mg/kg | 0.4 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | mg/kg | 35 | 1200 | 0.076 | U | 0.0534 | J | 0.083 | U | 0.0585 | J | 0.075 | U | 0.07 | U | 0.149 | | 0.077 | U | 0.068 | U | 0.0426 | J | 0.068 | U |
| BUTYLBENZYL PHTHALATE | mg/kg | 1200 | 230 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| CAPROLACTAM | mg/kg | 31000 | 12 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| CARBAZOLE | mg/kg | 24 | NC | **199** | | 15.9 | | 11.9 | | 16.3 | | 4.41 | | 17 | | - | | 9.55 | | 0.803 | | 1.22 | | 8.77 | |
| CHRYSENE | mg/kg | 62 | 80 | 15.9 | | 2.73 | | 2.28 | | 1.99 | | 0.985 | | 2.99 | | 3.48 | | 1.67 | | 1.13 | | 1.41 | | 3.16 | |
| DI-N-BUTYL PHTHALATE | mg/kg | 6100 | 760 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| DI-N-OCTYL PHTHALATE | mg/kg | 2400 | 3300 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| DIBENZO(A,H)ANTHRACENE | mg/kg | 0.2 | 0.8 | **0.582** | **J** | 0.129 | | 0.15 | | 0.134 | | 0.0924 | | 0.14 | | 0.187 | | 0.0814 | | 0.166 | | 0.12 | | 0.167 | |
| DIBENZOFURAN | mg/kg | NC | NC | 71.2 | | 7.73 | | 3.86 | | 3.93 | | 1.28 | | 6.31 | | - | | 3.87 | | 1.11 | | 1.65 | | 14.7 | |
| DIETHYL PHTHALATE | mg/kg | 49000 | 88 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| DIMETHYL PHTHALATE | mg/kg | NC | NC | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| FLUORANTHENE | mg/kg | 2300 | 1300 | 111 | | 13.5 | | 9.7 | | 9.91 | | 3.25 | | 13.1 | | 18.3 | | 8.27 | | 1.94 | | 3.83 | | 19.4 | |
| FLUORENE | mg/kg | 2300 | 170 | 89.7 | | 8.65 | | 5.15 | | 4.41 | | 1.72 | | 8.7 | | 11.5 | | 5.18 | | 1.36 | | 2.5 | | 17.3 | |
| HEXACHLOROBENZENE | mg/kg | 0.3 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| HEXACHLOROBUTADIENE | mg/kg | 6 | 0.9 | 0.038 | U | 0.038 | U | 0.042 | U | 0.046 | U | 0.037 | U | 0.035 | U | 0.038 | U | 0.039 | U | 0.034 | U | 0.034 | U | 0.034 | U |
| HEXACHLOROCYCLOPENTADIENE | mg/kg | 45 | 320 | 0.38 | U | 0.38 | U | 0.42 | U | 0.46 | U | 0.37 | U | 0.35 | U | 0.38 | U | 0.39 | U | 0.34 | U | 0.34 | U | 0.34 | U |
| HEXACHLOROETHANE | mg/kg | 35 | 0.2 | 0.19 | U | 0.19 | U | *0.21* | *U* | *0.23* | *U* | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| INDENO(1,2,3-CD)PYRENE | mg/kg | 0.6 | 7 | **1.27** | **J** | 0.315 | | 0.392 | | 0.353 | | 0.229 | | 0.439 | | 0.591 | | 0.243 | | **0.616** | | 0.371 | | 0.424 | |
| ISOPHORONE | mg/kg | 510 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| N-NITROSO-DI-N-PROPYLAMINE | mg/kg | 0.2 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| N-NITROSODIPHENYLAMINE | mg/kg | 99 | 0.4 | 0.19 | U | 0.19 | U | 0.21 | U | 0.23 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U |
| NAPHTHALENE | mg/kg | 6 | 25 | **234** | | **30.1** | | 1.9 | | 1.77 | | 1.05 | | 3.08 | | 5.56 | | 1.62 | | 3.61 | | 2.12 | | **60.8** | |
| NITROBENZENE | mg/kg | 31 | 0.2 | 0.076 | U | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| PHENANTHRENE | mg/kg | 300000 | NC | 270 | | 30.8 | | 17.1 | | 19.9 | | 5.3 | | 26.1 | | 34.8 | | 15.8 | | 2.3 | | 6.81 | | 50.4 | |
| PHENOL | mg/kg | 18000 | 8 | 0.0982 | J | 0.077 | U | 0.083 | U | 0.091 | U | 0.075 | U | 0.07 | U | 0.075 | U | 0.077 | U | 0.068 | U | 0.067 | U | 0.068 | U |
| PYRENE | mg/kg | 1700 | 840 | 59.4 | | 7.47 | | 6.92 | | 7.3 | | 2.56 | | 8.65 | | 12.5 | | 5.49 | | 1.5 | | 3.02 | | 12.2 | |
| TOTAL TICS, ALKANES | mg/kg | | | 0 | | 0 | | 0 | | 0 | | 0.48 | J | 0 | | 3.22 | J | 0 | | 0 | | 0.46 | J | 0.6 | J |
| TOTAL TICS, SEMI-VOLATILES | mg/kg | | | 26.15 | J | 20.95 | J | 14.49 | J | 17.51 | J | 8.67 | J | 12.42 | J | 35 | J | 24.03 | J | 6.48 | J | 12.64 | J | 33.27 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

B: Analyte found in sample and associated blank

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE B

## Petroleum Soil Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-23-031414 | | 124-A_B-Pet-24-031414 | | 124-A_B-Pet-25-042214 | | 124-A_B-Pet-26-042214 | | 124-A_B-Pet-27-052214 | | 124-A_B-Pet-28-052214 | | 124-A_B-Pet-29-052214 | | 124-A_B-Pet-30-052214 | | 124-A_B-Pet-31-052214 | | 124-A_B-Pet-32-052214 | | 124-A_B-Pet-33-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB62045-3 | | JB62045-4 | | JB65312-1A | | JB65312-2A | | JB67718-1A | | JB67718-2A | | JB67718-3A | | JB67718-4A | | JB67718-5A | | JB67718-6A | | JB67718-7A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 03/14/2014 | | 03/14/2014 | | 04/22/2014 | | 04/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1'-BIPHENYL | mg/kg | 3100 | 140 | 4.46 | | 0.272 | | 0.046 | J | 0.0661 | J | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 1,2,4,5-TETRACHLOROBENZENE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 1,4-DIOXANE | mg/kg | NC | NC | 0.037 | U | 0.037 | U | 0.036 | U | 0.037 | U | - | | - | | - | | - | | - | | - | | - | |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | mg/kg | 23 | 5 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 2,3,4,6-TETRACHLOROPHENOL | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 2,4,5-TRICHLOROPHENOL | mg/kg | 6100 | 68 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 2,4,6-TRICHLOROPHENOL | mg/kg | 19 | 0.2 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 2,4-DICHLOROPHENOL | mg/kg | 180 | 0.2 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 2,4-DIMETHYLPHENOL | mg/kg | 1200 | 1 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 2,4-DINITROPHENOL | mg/kg | 120 | 0.3 | *0.74* | *U* | *0.75* | *U* | *0.73* | *U* | *0.75* | *U* | *0.71* | *U* | *0.7* | *U* | *0.7* | *U* | *0.65* | *U* | *0.7* | *U* | *0.71* | *U* | *0.67* | *U* |
| 2,4-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.037 | U | 0.037 | U | 0.036 | U | 0.037 | U | 0.036 | U | 0.035 | U | 0.035 | U | 0.033 | U | 0.035 | U | 0.035 | U | 0.033 | U |
| 2,6-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.037 | U | 0.037 | U | 0.036 | U | 0.037 | U | 0.036 | U | 0.035 | U | 0.035 | U | 0.033 | U | 0.035 | U | 0.035 | U | 0.033 | U |
| 2-CHLORONAPHTHALENE | mg/kg | NC | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 2-CHLOROPHENOL | mg/kg | 310 | 0.8 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 2-METHYLNAPHTHALENE | mg/kg | 230 | 8 | **21** | | 1.08 | | 0.073 | U | 0.217 | | 0.473 | | 0.0338 | J | 0.07 | U | 0.0341 | J | 0.07 | U | 0.0232 | J | 0.067 | U |
| 2-METHYLPHENOL | mg/kg | 310 | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 2-NITROANILINE | mg/kg | 39 | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 2-NITROPHENOL | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 3&4-METHYLPHENOL | mg/kg | NC | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 3,3'-DICHLOROBENZIDINE | mg/kg | 1 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 3-NITROANILINE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 4,6-DINITRO-2-METHYLPHENOL | mg/kg | 6 | 0.3 | *0.74* | *U* | *0.75* | *U* | *0.73* | *U* | *0.75* | *U* | *0.71* | *U* | *0.7* | *U* | *0.7* | *U* | *0.65* | *U* | *0.7* | *U* | *0.71* | *U* | *0.67* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 4-CHLORO-3-METHYLPHENOL | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 4-CHLOROANILINE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 4-CHLOROPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| 4-NITROANILINE | mg/kg | NC | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| 4-NITROPHENOL | mg/kg | NC | NC | 0.37 | U | 0.37 | U | 0.36 | U | 0.37 | U | 0.36 | U | 0.35 | U | 0.35 | U | 0.33 | U | 0.35 | U | 0.35 | U | 0.33 | U |
| ACENAPHTHENE | mg/kg | 3400 | 110 | 19.3 | | 1.24 | | 0.181 | | 1.01 | | 0.245 | | 0.035 | U | 0.035 | U | 0.033 | U | 0.035 | U | 0.035 | U | 0.204 | |
| ACENAPHTHYLENE | mg/kg | 300000 | NC | 0.534 | | 0.0984 | | 0.166 | | 0.171 | | 0.036 | U | 0.0319 | J | 0.0373 | | 0.0172 | J | 0.035 | U | 0.0226 | J | 0.033 | U |
| ACETOPHENONE | mg/kg | 2 | 3 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| ANTHRACENE | mg/kg | 17000 | 2400 | 24.4 | | 1.86 | | 0.441 | | 0.585 | | 0.036 | U | 0.0154 | J | 0.0248 | J | 0.0479 | | 0.035 | U | 0.0187 | J | 0.033 | U |
| ATRAZINE | mg/kg | 210 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| BENZALDEHYDE | mg/kg | 6100 | NC | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| BENZO(A)ANTHRACENE | mg/kg | 0.6 | 0.8 | **3.89** | | **0.682** | | 0.379 | | **0.953** | | 0.152 | | 0.0922 | | 0.104 | | 0.0887 | | 0.0481 | | 0.0838 | | 0.0732 | |
| BENZO(A)PYRENE | mg/kg | 0.2 | 0.2 | **1.04** | | **0.473** | | **0.301** | | **0.616** | | 0.163 | | 0.116 | | 0.134 | | 0.103 | | 0.0488 | | 0.0931 | | 0.0657 | |
| BENZO(B)FLUORANTHENE | mg/kg | 0.6 | 2 | **1.84** | | 0.539 | | 0.329 | | **0.797** | | 0.182 | | 0.117 | | 0.125 | | 0.0982 | | 0.0504 | | 0.0851 | | 0.0561 | |
| BENZO(G,H,I)PERYLENE | mg/kg | 30000 | NC | 0.276 | | 0.209 | | 0.2 | | 0.348 | | 0.116 | | 0.0748 | | 0.0839 | | 0.0698 | | 0.0418 | | 0.0693 | | 0.0424 | |
| BENZO(K)FLUORANTHENE | mg/kg | 6 | 25 | 0.662 | | 0.17 | | 0.103 | | 0.3 | | 0.075 | | 0.0442 | | 0.0528 | | 0.0436 | | 0.0228 | J | 0.0417 | | 0.0264 | J |
| BIS(2-CHLOROETHOXY)METHANE | mg/kg | NC | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| BIS(2-CHLOROETHYL)ETHER | mg/kg | 0.4 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | mg/kg | 35 | 1200 | 0.074 | U | 0.121 | | 0.328 | | 0.0658 | J | 0.0941 | B | 0.0614 | JB | 0.0544 | JB | 0.065 | U | 0.0586 | JB | 0.0481 | JB | 0.0652 | JB |
| BUTYLBENZYL PHTHALATE | mg/kg | 1200 | 230 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| CAPROLACTAM | mg/kg | 31000 | 12 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| CARBAZOLE | mg/kg | 24 | NC | 9.33 | | 0.723 | | 0.127 | | 0.196 | | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| CHRYSENE | mg/kg | 62 | 80 | 3.62 | | 0.68 | | 0.427 | | 0.912 | | 0.167 | | 0.104 | | 0.122 | | 0.0942 | | 0.0602 | | 0.0894 | | 0.0755 | |
| DI-N-BUTYL PHTHALATE | mg/kg | 6100 | 760 | 0.074 | U | 0.075 | U | 0.0501 | J | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| DI-N-OCTYL PHTHALATE | mg/kg | 2400 | 3300 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.175 | | 0.209 | | 0.166 | | 0.149 | | 1.34 | | 0.258 | | 0.067 | U |
| DIBENZO(A,H)ANTHRACENE | mg/kg | 0.2 | 0.8 | 0.112 | | 0.0636 | | 0.0538 | | 0.0959 | | 0.0381 | | 0.035 | U | 0.0206 | J | 0.0156 | J | 0.035 | U | 0.0213 | J | 0.033 | U |
| DIBENZOFURAN | mg/kg | NC | NC | 18 | | 1.06 | | 0.0776 | | 0.406 | | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| DIETHYL PHTHALATE | mg/kg | 49000 | 88 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| DIMETHYL PHTHALATE | mg/kg | NC | NC | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| FLUORANTHENE | mg/kg | 2300 | 1300 | 23.5 | | 2.29 | | 0.635 | | 3.28 | | 0.19 | | 0.109 | | 0.11 | | 0.102 | | 0.072 | | 0.0877 | | 0.1 | |
| FLUORENE | mg/kg | 2300 | 170 | 21.4 | | 1.44 | | 0.149 | | 0.552 | | 0.359 | | 0.035 | U | 0.035 | U | 0.0189 | J | 0.035 | U | 0.035 | U | 0.298 | |
| HEXACHLOROBENZENE | mg/kg | 0.3 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| HEXACHLOROBUTADIENE | mg/kg | 6 | 0.9 | 0.037 | U | 0.037 | U | 0.036 | U | 0.037 | U | 0.036 | U | 0.035 | U | 0.035 | U | 0.033 | U | 0.035 | U | 0.035 | U | 0.033 | U |
| HEXACHLOROCYCLOPENTADIENE | mg/kg | 45 | 320 | 0.37 | U | 0.37 | U | 0.36 | U | 0.37 | U | 0.36 | U | 0.35 | U | 0.35 | U | 0.33 | U | 0.35 | U | 0.35 | U | 0.33 | U |
| HEXACHLOROETHANE | mg/kg | 35 | 0.2 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| INDENO(1,2,3-CD)PYRENE | mg/kg | 0.6 | 7 | 0.286 | | 0.183 | | 0.203 | | 0.388 | | 0.112 | | 0.076 | | 0.0964 | | 0.063 | | 0.0406 | | 0.0691 | | 0.0339 | |
| ISOPHORONE | mg/kg | 510 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| N-NITROSO-DI-N-PROPYLAMINE | mg/kg | 0.2 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| N-NITROSODIPHENYLAMINE | mg/kg | 99 | 0.4 | 0.18 | U | 0.19 | U | 0.18 | U | 0.19 | U | 0.18 | U | 0.17 | U | 0.17 | U | 0.16 | U | 0.18 | U | 0.18 | U | 0.17 | U |
| NAPHTHALENE | mg/kg | 6 | 25 | **104** | | 5.21 | | 0.08 | | 0.155 | | 0.036 | U | 0.0204 | J | 0.0153 | J | 0.0223 | J | 0.035 | U | 0.0187 | J | 0.033 | U |
| NITROBENZENE | mg/kg | 31 | 0.2 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| PHENANTHRENE | mg/kg | 300000 | NC | 51.9 | | 4.46 | | 0.288 | | 1.66 | | 0.303 | | 0.0374 | | 0.0297 | J | 0.0563 | | 0.0467 | | 0.0302 | J | 0.149 | |
| PHENOL | mg/kg | 18000 | 8 | 0.074 | U | 0.075 | U | 0.073 | U | 0.075 | U | 0.071 | U | 0.07 | U | 0.07 | U | 0.065 | U | 0.07 | U | 0.071 | U | 0.067 | U |
| PYRENE | mg/kg | 1700 | 840 | 14.4 | | 1.89 | | 0.742 | | 2.83 | | 0.344 | | 0.133 | | 0.164 | | 0.163 | | 0.156 | | 0.121 | | 0.272 | |
| TOTAL TICS, ALKANES | mg/kg | | | 0.48 | J | 0.28 | J | 8.13 | J | 7.87 | J | 41.2 | J | 5.72 | J | 4.73 | J | 6.66 | J | 17.49 | J | 3.29 | J | 26.6 | J |
| TOTAL TICS, SEMI-VOLATILES | mg/kg | | | 33.44 | J | 7.79 | J | 18.02 | J | 53.72 | J | 42.2 | J | 4.78 | J | 4.88 | J | 7.84 | J | 16.36 | J | 3.03 | J | 30.87 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

B: Analyte found in sample and associated blank

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE B

## Petroleum Soil Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-34-060414 | | 124-A_B-Pet-35-060414 | | 124-A_B-Pet-36-060414 | | 124-A_B-Pet-37-060414 | | 124-A_B-Pet-38-062714 | | 124-A_B-Pet-39-062714 | | 124-A_B-Pet-40-062714 | | 124-A_B-Pet-41-062714 | | 124-A_B-Pet-42-062714 | | 124-A_B-Pet-43-081414 | | 124-A_B-Pet-44-081414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB68443-1A | | JB68443-2A | | JB68443-3A | | JB68443-4A | | JB70484-1A | | JB70484-2A | | JB70484-3A | | JB70484-4A | | JB70484-5A | | J74045-1 | | J74045-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 08/14/2014 | | 08/14/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1'-BIPHENYL | mg/kg | 3100 | 140 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.0176 | J | 0.074 | U |
| 1,2,4,5-TETRACHLOROBENZENE | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.19 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 1,4-DIOXANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.035 | U | 0.037 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | mg/kg | 23 | 5 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 2,3,4,6-TETRACHLOROPHENOL | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 2,4,5-TRICHLOROPHENOL | mg/kg | 6100 | 68 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 2,4,6-TRICHLOROPHENOL | mg/kg | 19 | 0.2 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | *0.25* | *U* | *0.24* | *U* | 0.18 | U | 0.18 | U |
| 2,4-DICHLOROPHENOL | mg/kg | 180 | 0.2 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | *0.25* | *U* | *0.24* | *U* | 0.18 | U | 0.18 | U |
| 2,4-DIMETHYLPHENOL | mg/kg | 1200 | 1 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 2,4-DINITROPHENOL | mg/kg | 120 | 0.3 | *0.75* | *U* | *0.67* | *U* | *0.68* | *U* | *0.69* | *U* | *0.7* | *U* | *0.71* | *U* | *0.76* | *U* | *1* | *U* | *0.98* | *U* | *0.71* | *U* | *0.74* | *U* |
| 2,4-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.038 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.036 | U | 0.038 | U | 0.05 | U | 0.049 | U | 0.035 | U | 0.037 | U |
| 2,6-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.038 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.036 | U | 0.038 | U | 0.05 | U | 0.049 | U | 0.035 | U | 0.037 | U |
| 2-CHLORONAPHTHALENE | mg/kg | NC | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 2-CHLOROPHENOL | mg/kg | 310 | 0.8 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 2-METHYLNAPHTHALENE | mg/kg | 230 | 8 | 0.0742 | J | 0.221 | | 0.0339 | J | 0.0583 | J | 0.07 | U | 0.071 | U | 0.0252 | J | 0.0407 | J | 0.0286 | J | 0.0651 | J | 0.0222 | J |
| 2-METHYLPHENOL | mg/kg | 310 | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 2-NITROANILINE | mg/kg | 39 | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 2-NITROPHENOL | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 3&4-METHYLPHENOL | mg/kg | NC | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 3,3'-DICHLOROBENZIDINE | mg/kg | 1 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 3-NITROANILINE | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 4,6-DINITRO-2-METHYLPHENOL | mg/kg | 6 | 0.3 | *0.75* | *U* | *0.67* | *U* | *0.68* | *U* | *0.69* | *U* | *0.7* | *U* | *0.71* | *U* | *0.76* | *U* | *1* | *U* | *0.98* | *U* | *0.71* | *U* | *0.74* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 4-CHLORO-3-METHYLPHENOL | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 4-CHLOROANILINE | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 4-CHLOROPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| 4-NITROANILINE | mg/kg | NC | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| 4-NITROPHENOL | mg/kg | NC | NC | 0.38 | U | 0.34 | U | 0.34 | U | 0.34 | U | 0.35 | U | 0.36 | U | 0.38 | U | 0.5 | U | 0.49 | U | 0.35 | U | 0.37 | U |
| ACENAPHTHENE | mg/kg | 3400 | 110 | 0.039 | | 0.0857 | | 0.0139 | J | 0.0397 | | 0.035 | U | 0.036 | U | 0.0329 | J | 0.05 | U | 0.0702 | | 0.0302 | J | 0.0173 | J |
| ACENAPHTHYLENE | mg/kg | 300000 | NC | 0.0443 | | 0.101 | | 0.0307 | J | 0.0492 | | 0.0145 | J | 0.036 | U | 0.0918 | | 0.05 | U | 0.0813 | | 0.0406 | | 0.027 | J |
| ACETOPHENONE | mg/kg | 2 | 3 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| ANTHRACENE | mg/kg | 17000 | 2400 | 0.0681 | | 0.034 | U | 0.0333 | J | 0.0809 | | 0.0166 | J | 0.0181 | J | 0.137 | | 0.05 | U | 0.161 | | 0.152 | | 0.0534 | |
| ATRAZINE | mg/kg | 210 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| BENZALDEHYDE | mg/kg | 6100 | NC | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| BENZO(A)ANTHRACENE | mg/kg | 0.6 | 0.8 | 0.182 | | 0.479 | | 0.113 | | 0.178 | | 0.0367 | | 0.0442 | | 0.384 | | 0.0396 | J | 0.377 | | 0.215 | | 0.199 | |
| BENZO(A)PYRENE | mg/kg | 0.2 | 0.2 | **0.201** | | **0.58** | | 0.155 | | **0.233** | | 0.0304 | J | 0.0428 | | **0.405** | | 0.039 | J | **0.346** | | **0.206** | | **0.203** | |
| BENZO(B)FLUORANTHENE | mg/kg | 0.6 | 2 | 0.236 | | **0.699** | | 0.183 | | 0.284 | | 0.0278 | J | 0.0577 | | 0.402 | | 0.0365 | J | 0.292 | | 0.244 | | 0.232 | |
| BENZO(G,H,I)PERYLENE | mg/kg | 30000 | NC | 0.134 | | 0.387 | | 0.0929 | | 0.151 | | 0.014 | J | 0.0263 | J | 0.196 | | 0.0302 | J | 0.173 | | 0.14 | | 0.128 | |
| BENZO(K)FLUORANTHENE | mg/kg | 6 | 25 | 0.0816 | | 0.252 | | 0.0565 | | 0.0896 | | 0.035 | U | 0.0216 | J | 0.146 | | 0.05 | U | 0.0996 | | 0.0973 | | 0.0855 | |
| BIS(2-CHLOROETHOXY)METHANE | mg/kg | NC | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| BIS(2-CHLOROETHYL)ETHER | mg/kg | 0.4 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | mg/kg | 35 | 1200 | 0.114 | | 0.13 | | 0.0628 | J | 0.0741 | | 0.07 | U | 0.0556 | J | 0.076 | U | 0.1 | U | 0.0873 | J | 0.0359 | J | 0.074 | U |
| BUTYLBENZYL PHTHALATE | mg/kg | 1200 | 230 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| CAPROLACTAM | mg/kg | 31000 | 12 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| CARBAZOLE | mg/kg | 24 | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.0299 | J | 0.074 | U |
| CHRYSENE | mg/kg | 62 | 80 | 0.211 | | 0.594 | | 0.153 | | 0.242 | | 0.0403 | | 0.0571 | | 0.395 | | 0.0375 | J | 0.394 | | 0.266 | | 0.235 | |
| DI-N-BUTYL PHTHALATE | mg/kg | 6100 | 760 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.0675 | BJ | 0.085 | B |
| DI-N-OCTYL PHTHALATE | mg/kg | 2400 | 3300 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| DIBENZO(A,H)ANTHRACENE | mg/kg | 0.2 | 0.8 | 0.0351 | J | 0.113 | | 0.0294 | J | 0.0446 | | 0.035 | U | 0.036 | U | 0.062 | | 0.05 | U | 0.0534 | | 0.0477 | | 0.0357 | J |
| DIBENZOFURAN | mg/kg | NC | NC | 0.0338 | J | 0.0423 | J | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.0176 | J | 0.1 | U | 0.098 | U | 0.0423 | J | 0.016 | J |
| DIETHYL PHTHALATE | mg/kg | 49000 | 88 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| DIMETHYL PHTHALATE | mg/kg | NC | NC | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| FLUORANTHENE | mg/kg | 2300 | 1300 | 0.267 | | 0.502 | | 0.139 | | 0.228 | | 0.053 | | 0.075 | | 0.533 | | 0.0506 | | 0.517 | | 0.314 | | 0.263 | |
| FLUORENE | mg/kg | 2300 | 170 | 0.0584 | | 0.034 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.036 | U | 0.0313 | J | 0.05 | U | 0.0595 | | 0.0471 | | 0.037 | U |
| HEXACHLOROBENZENE | mg/kg | 0.3 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| HEXACHLOROBUTADIENE | mg/kg | 6 | 0.9 | 0.038 | U | 0.034 | U | 0.034 | U | 0.034 | U | 0.035 | U | 0.036 | U | 0.038 | U | 0.05 | U | 0.049 | U | 0.035 | U | 0.037 | U |
| HEXACHLOROCYCLOPENTADIENE | mg/kg | 45 | 320 | 0.38 | U | 0.34 | U | 0.34 | U | 0.34 | U | 0.35 | U | 0.36 | U | 0.38 | U | 0.5 | U | 0.49 | U | 0.35 | U | 0.37 | U |
| HEXACHLOROETHANE | mg/kg | 35 | 0.2 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | *0.25* | *U* | *0.24* | *U* | 0.18 | U | 0.18 | U |
| INDENO(1,2,3-CD)PYRENE | mg/kg | 0.6 | 7 | 0.109 | | 0.334 | | 0.0791 | | 0.123 | | 0.0159 | J | 0.0284 | J | 0.219 | | 0.0252 | J | 0.165 | | 0.139 | | 0.133 | |
| ISOPHORONE | mg/kg | 510 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| N-NITROSO-DI-N-PROPYLAMINE | mg/kg | 0.2 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| N-NITROSODIPHENYLAMINE | mg/kg | 99 | 0.4 | 0.19 | U | 0.17 | U | 0.17 | U | 0.17 | U | 0.18 | U | 0.18 | U | 0.19 | U | 0.25 | U | 0.24 | U | 0.18 | U | 0.18 | U |
| NAPHTHALENE | mg/kg | 6 | 25 | 0.0435 | | 0.144 | | 0.0262 | J | 0.0556 | | 0.0183 | J | 0.0164 | J | 0.0469 | | 0.0242 | J | 0.0466 | J | 0.0706 | | 0.0293 | J |
| NITROBENZENE | mg/kg | 31 | 0.2 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| PHENANTHRENE | mg/kg | 300000 | NC | 0.168 | | 0.219 | | 0.047 | | 0.114 | | 0.0196 | J | 0.0245 | J | 0.133 | | 0.05 | U | 0.22 | | 0.171 | | 0.111 | |
| PHENOL | mg/kg | 18000 | 8 | 0.075 | U | 0.067 | U | 0.068 | U | 0.069 | U | 0.07 | U | 0.071 | U | 0.076 | U | 0.1 | U | 0.098 | U | 0.071 | U | 0.074 | U |
| PYRENE | mg/kg | 1700 | 840 | 0.313 | | 0.664 | | 0.183 | | 0.353 | | 0.0547 | | 0.0742 | | 0.462 | | 0.0516 | | 0.686 | | 0.353 | | 0.264 | |
| TOTAL TICS, ALKANES | mg/kg | | | 4.82 | J | 10.98 | J | 4.17 | J | 7.52 | J | 0 | | 0 | | 0.15 | J | 0 | | 0.56 | J | 1.61 | J | 0 | |
| TOTAL TICS, SEMI-VOLATILES | mg/kg | | | 9.94 | J | 17.35 | J | 5.78 | J | 8.46 | J | 0 | | 8.25 | J | 1.64 | J | 0 | | 6.56 | J | 1.36 | J | 0.35 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

B: Analyte found in sample and associated blank

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE B

## Petroleum Soil Sample Results – SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-45-081414 | | 124-A_B-Pet-46-081914 | | 124-A_B-Pet-47-090514 | | 124-A_B-Pet-48-090514 | | 124-A_B-Pet-49-090514 | | 124-A_B-Pet-50-102414 | | 124-A_B-Pet-51-102414 | | 124-A_B-Pet-52-102414 | | 124-A_B-Pet-53-102414 | | 124-C-Pet-01-102414 | | 134-SB-604-0627 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB74045-3 | | JB74372-1 | | JB75848-1 | | JB75848-2 | | JB75848-3 | | JB80064-1 | | JB80064-2 | | JB80064-3 | | JB80064-4 | | JB80065-1 | | JB70486-1A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 08/14/2014 | | 08/19/2014 | | 09/05/2014 | | 09/05/2014 | | 09/05/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 06/27/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| 1,1'-BIPHENYL | mg/kg | 3100 | 140 | 0.072 | U | 0.0618 | J | 0.07 | U | 0.073 | U | 0.071 | U | 0.0275 | J | 0.077 | U | 0.067 | U | 0.077 | U | 0.224 | | 0.0306 | J |
| 1,2,4,5-TETRACHLOROBENZENE | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 1,4-DIOXANE | mg/kg | NC | NC | 0.036 | U | 0.036 | U | 0.035 | U | 0.036 | U | 0.036 | U | 0.042 | U | 0.038 | U | 0.033 | U | 0.038 | U | 0.043 | U | - | |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | mg/kg | 23 | 5 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 2,3,4,6-TETRACHLOROPHENOL | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 2,4,5-TRICHLOROPHENOL | mg/kg | 6100 | 68 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 2,4,6-TRICHLOROPHENOL | mg/kg | 19 | 0.2 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | *0.21* | *U* | 0.19 | U | 0.17 | U | 0.19 | U | *0.21* | *U* | 0.19 | U |
| 2,4-DICHLOROPHENOL | mg/kg | 180 | 0.2 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | *0.21* | *U* | 0.19 | U | 0.17 | U | 0.19 | U | *0.21* | *U* | 0.19 | U |
| 2,4-DIMETHYLPHENOL | mg/kg | 1200 | 1 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 2,4-DINITROPHENOL | mg/kg | 120 | 0.3 | *0.72* | *U* | *0.72* | *U* | *0.7* | *U* | *0.73* | *U* | *0.71* | *U* | *0.84* | *U* | *0.77* | *U* | *0.67* | *U* | *0.77* | *U* | *0.86* | *U* | *0.76* | *U* |
| 2,4-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.036 | U | 0.036 | U | 0.035 | U | 0.036 | U | 0.036 | U | 0.042 | U | 0.038 | U | 0.033 | U | 0.038 | U | 0.043 | U | 0.038 | U |
| 2,6-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.036 | U | 0.036 | U | 0.035 | U | 0.036 | U | 0.036 | U | 0.042 | U | 0.038 | U | 0.033 | U | 0.038 | U | 0.043 | U | 0.038 | U |
| 2-CHLORONAPHTHALENE | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 2-CHLOROPHENOL | mg/kg | 310 | 0.8 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 2-METHYLNAPHTHALENE | mg/kg | 230 | 8 | 0.0213 | J | 0.459 | | 0.07 | U | 0.073 | U | 0.071 | U | 0.115 | | 0.0565 | J | 0.067 | U | 0.033 | J | 0.0565 | J | 0.127 | |
| 2-METHYLPHENOL | mg/kg | 310 | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 2-NITROANILINE | mg/kg | 39 | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 2-NITROPHENOL | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 3&4-METHYLPHENOL | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.1790 | | 0.076 | U |
| 3,3'-DICHLOROBENZIDINE | mg/kg | 1 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 3-NITROANILINE | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 4,6-DINITRO-2-METHYLPHENOL | mg/kg | 6 | 0.3 | *0.72* | *U* | *0.72* | *U* | *0.7* | *U* | *0.73* | *U* | *0.71* | *U* | *0.84* | *U* | *0.77* | *U* | *0.67* | *U* | *0.77* | *U* | *0.86* | *U* | *0.76* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 4-CHLORO-3-METHYLPHENOL | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 4-CHLOROANILINE | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 4-CHLOROPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| 4-NITROANILINE | mg/kg | NC | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| 4-NITROPHENOL | mg/kg | NC | NC | 0.36 | U | 0.36 | U | 0.35 | U | 0.36 | U | 0.36 | U | 0.42 | U | 0.38 | U | 0.33 | U | 0.38 | U | 0.43 | U | 0.38 | U |
| ACENAPHTHENE | mg/kg | 3400 | 110 | 0.0172 | J | 0.036 | U | 0.035 | U | 0.036 | U | 0.036 | U | 0.0539 | | 0.14 | | 0.033 | U | 0.0261 | J | 0.0588 | | 0.527 | |
| ACENAPHTHYLENE | mg/kg | 300000 | NC | 0.0223 | J | 0.036 | U | 0.0441 | | 0.0146 | J | 0.036 | U | 0.071 | | 0.0237 | J | 0.033 | U | 0.0352 | J | 0.102 | | 0.221 | |
| ACETOPHENONE | mg/kg | 2 | 3 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| ANTHRACENE | mg/kg | 17000 | 2400 | 0.0419 | | 0.228 | | 0.0685 | | 0.0263 | J | 0.0215 | J | 0.118 | | 0.317 | | 0.0163 | J | 0.0709 | | 0.195 | | 0.763 | |
| ATRAZINE | mg/kg | 210 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| BENZALDEHYDE | mg/kg | 6100 | NC | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| BENZO(A)ANTHRACENE | mg/kg | 0.6 | 0.8 | 0.162 | | **0.826** | | 0.225 | | 0.0491 | | 0.0697 | | 0.316 | | **0.677** | | 0.0411 | | 0.212 | | **0.609** | | **1.13** | |
| BENZO(A)PYRENE | mg/kg | 0.2 | 0.2 | 0.173 | | **0.824** | | **0.223** | | 0.036 | | 0.0637 | | **0.348** | | **0.647** | | 0.0428 | | **0.216** | | **0.621** | | **1.01** | |
| BENZO(B)FLUORANTHENE | mg/kg | 0.6 | 2 | 0.206 | | **0.903** | | 0.254 | | 0.0438 | | 0.0842 | | 0.367 | | **0.697** | | 0.0444 | | 0.23 | | **0.668** | | **1.13** | |
| BENZO(G,H,I)PERYLENE | mg/kg | 30000 | NC | 0.11 | | 0.457 | | 0.111 | | 0.0254 | J | 0.04 | | 0.24 | | 0.407 | | 0.0335 | | 0.139 | | 0.405 | | 0.542 | |
| BENZO(K)FLUORANTHENE | mg/kg | 6 | 25 | 0.0766 | | 0.351 | | 0.0888 | | 0.0208 | J | 0.0269 | J | 0.141 | | 0.275 | | 0.0165 | J | 0.0823 | | 0.286 | | 0.416 | |
| BIS(2-CHLOROETHOXY)METHANE | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| BIS(2-CHLOROETHYL)ETHER | mg/kg | 0.4 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | mg/kg | 35 | 1200 | 0.072 | U | 0.072 | U | 0.0455 | J | 0.073 | U | 0.071 | U | 0.103 | | 0.0715 | J | 0.0868 | | 0.0652 | J | 0.166 | | 0.269 | |
| BUTYLBENZYL PHTHALATE | mg/kg | 1200 | 230 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| CAPROLACTAM | mg/kg | 31000 | 12 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| CARBAZOLE | mg/kg | 24 | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.132 | | 0.067 | U | 0.077 | U | 0.0375 | J | 0.131 | |
| CHRYSENE | mg/kg | 62 | 80 | 0.193 | | 0.884 | | 0.249 | | 0.0516 | | 0.0691 | | 0.407 | | 0.75 | | 0.0459 | | 0.258 | | 0.748 | | 1.18 | |
| DI-N-BUTYL PHTHALATE | mg/kg | 6100 | 760 | 0.0515 | BJ | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.114 | B | 0.186 | B | 0.0921 | B | 0.117 | B | 0.105 | B | 0.076 | U |
| DI-N-OCTYL PHTHALATE | mg/kg | 2400 | 3300 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| DIBENZO(A,H)ANTHRACENE | mg/kg | 0.2 | 0.8 | 0.0305 | J | 0.137 | | 0.0277 | J | 0.036 | U | 0.036 | U | 0.0692 | | 0.109 | | 0.033 | U | 0.037 | J | 0.123 | | 0.166 | |
| DIBENZOFURAN | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.0445 | J | 0.0578 | J | 0.067 | U | 0.0177 | J | 0.0467 | J | 0.266 | |
| DIETHYL PHTHALATE | mg/kg | 49000 | 88 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| DIMETHYL PHTHALATE | mg/kg | NC | NC | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.0675 | J | 0.077 | | 0.0762 | J | 0.086 | U | 0.076 | U |
| FLUORANTHENE | mg/kg | 2300 | 1300 | 0.238 | | 0.988 | | 0.248 | | 0.102 | | 0.115 | | 0.469 | | 1.43 | | 0.0614 | | 0.343 | | 0.903 | | 2.68 | |
| FLUORENE | mg/kg | 2300 | 170 | 0.019 | J | 0.036 | U | 0.0161 | J | 0.036 | U | 0.036 | U | 0.042 | U | 0.129 | | 0.033 | U | 0.0282 | J | 0.0584 | | 0.371 | |
| HEXACHLOROBENZENE | mg/kg | 0.3 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| HEXACHLOROBUTADIENE | mg/kg | 6 | 0.9 | 0.036 | U | 0.036 | U | 0.035 | U | 0.036 | U | 0.036 | U | 0.042 | U | 0.038 | U | 0.033 | U | 0.038 | U | 0.043 | U | 0.038 | U |
| HEXACHLOROCYCLOPENTADIENE | mg/kg | 45 | 320 | 0.36 | U | 0.36 | U | 0.35 | U | 0.36 | U | 0.36 | U | 0.42 | U | 0.38 | U | 0.33 | U | 0.38 | U | 0.43 | U | 0.38 | U |
| HEXACHLOROETHANE | mg/kg | 35 | 0.2 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | *0.21* | *U* | 0.19 | U | 0.17 | U | 0.19 | U | *0.21* | *U* | 0.19 | U |
| INDENO(1,2,3-CD)PYRENE | mg/kg | 0.6 | 7 | 0.115 | | 0.527 | | 0.0871 | | 0.0193 | J | 0.0316 | J | 0.199 | | 0.327 | | 0.0248 | J | 0.12 | | 0.346 | | 0.589 | |
| ISOPHORONE | mg/kg | 510 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| N-NITROSO-DI-N-PROPYLAMINE | mg/kg | 0.2 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| N-NITROSODIPHENYLAMINE | mg/kg | 99 | 0.4 | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.18 | U | 0.21 | U | 0.19 | U | 0.17 | U | 0.19 | U | 0.21 | U | 0.19 | U |
| NAPHTHALENE | mg/kg | 6 | 25 | 0.018 | J | 0.036 | U | 0.0402 | | 0.036 | U | 0.036 | U | 0.269 | | 0.0421 | | 0.033 | U | 0.0352 | J | 0.0947 | | 0.319 | |
| NITROBENZENE | mg/kg | 31 | 0.2 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.086 | U | 0.076 | U |
| PHENANTHRENE | mg/kg | 300000 | NC | 0.0997 | | 0.344 | | 0.0804 | | 0.0818 | | 0.0719 | | 0.172 | | 0.94 | | 0.0257 | J | 0.159 | | 0.318 | | 0.897 | |
| PHENOL | mg/kg | 18000 | 8 | 0.072 | U | 0.072 | U | 0.07 | U | 0.073 | U | 0.071 | U | 0.084 | U | 0.077 | U | 0.067 | U | 0.077 | U | 0.217 | | 0.076 | U |
| PYRENE | mg/kg | 1700 | 840 | 0.242 | | 0.853 | | 0.307 | | 0.108 | | 0.14 | | 0.473 | | 1.23 | | 0.0826 | | 0.33 | | 0.735 | | 2.15 | |
| TOTAL TICS, ALKANES | mg/kg | | | 0.15 | J | 6.95 | J | 0 | | 0 | | 0 | | 12.13 | J | 2.61 | J | 1.6 | J | 3.21 | J | 6.79 | J | 0 | |
| TOTAL TICS, SEMI-VOLATILES | mg/kg | | | 0.33 | J | 26.68 | J | 0.84 | J | 0.21 | J | 0 | | 6.28 | J | 4.25 | J | 1.24 | J | 23.42 | J | 6.08 | J | 9.94 | J |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

B: Analyte found in sample and associated blank

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

R or N: Rejected or negated by laboratory or data validator

U: Not detected above method detection limit

Results with a value of "0" indicates no TICs were detected



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE C

## Petroleum Soil Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-06-012814 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-08-012814 | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-11-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB57182-1 | | JB57182-2 | | JB58165-1 | | JB58764-1 | | JB58764-2 | | JB58764-3 | | JB58764-4 | | JB58764-5 | | JB58764-6 | | JB60759-1 | | JB60759-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 01/08/2014 | | 01/08/2014 | | 01/20/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 02/27/2014 | | 02/27/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| ALUMINUM | mg/kg | 78000 | 6000 | **7680** | | 5820 | | **9210** | | **6130** | | **8460** | | **9040** | | **7860** | | **9460** | | **6450** | | **8540** | | 4760 | |
| ANTIMONY | mg/kg | 31 | 6 | 2.3 | UJ | 2.4 | UJ | 2.6 | UJ | 2.2 | U | 2.2 | U | 2.4 | U | 2.6 | U | 2.4 | U | 2.5 | U | *12* | *U* | *7* | *U* |
| ARSENIC | mg/kg | 19 | 19 | 8.4 | | 6.7 | | 7.6 | | 5.8 | | 5.4 | | 5.7 | | 5.2 | | 5.9 | | 4.5 | | 6.8 | | 7 | U |
| BARIUM | mg/kg | 16000 | 2100 | 105 | | 260 | | 192 | | 65.5 | | 72.3 | | 83.1 | | 60.3 | | 189 | | 66.9 | | 51.1 | | 37.7 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | 0.70 | | 0.62 | | 0.53 | | 0.32 | | 0.46 | | 0.40 | | 0.42 | | 0.45 | | 0.31 | | *1.2* | *U* | 0.7 | U |
| CADMIUM | mg/kg | 78 | 2 | 0.68 | | 0.60 | | 0.76 | | 0.67 | | 0.55 | U | 0.6 | U | 0.64 | U | 0.6 | U | 0.62 | U | 0.6 | U | 0.58 | U |
| CALCIUM | mg/kg | NC | NC | 10500 | | 15900 | | 14700 | | 4850 | | 5790 | | 11400 | | 7110 | | 12100 | | 4320 | | 2450 | | 3400 | |
| CHROMIUM | mg/kg | NC | NC | 378 | | 897 | | 991 | | 390 | | 336 | | 929 | | 151 | | 449 | | 825 | | 1870 | | 333 | |
| COBALT | mg/kg | 590 | 90 | 6.1 | | 5.9 | U | 9.3 | | 5.5 | | 7.8 | | 9.9 | | 6.4 | U | 6 | U | 6.2 | U | 8.9 | | 5.8 | U |
| COPPER | mg/kg | 3100 | 11000 | 153 | | 66.6 | | 101 | | 27.5 | | 31.0 | | 34.3 | | 19.3 | | 36.3 | | 19.9 | | 21.0 | | 14.0 | |
| IRON | mg/kg | NC | NC | 14500 | | 13300 | | 18600 | J | 12300 | | 16300 | | 17300 | | 16800 | | 21000 | | 12800 | | 15100 | | 12100 | |
| LEAD | mg/kg | 400 | 90 | **222** | J | **256** | J | **265** | | 50.0 | | 56.5 | | 55.5 | | 40.3 | | 82.4 | | 50.0 | | 24.7 | | 30.8 | |
| MAGNESIUM | mg/kg | NC | NC | 3490 | | 3560 | | 4890 | | 3280 | | 4910 | | 5180 | | 4180 | | 2560 | | 2730 | | 3750 | | 2500 | |
| MANGANESE | mg/kg | 11000 | 65 | **208** | | **186** | | **312** | J | **223** | | **334** | | **326** | | **346** | | **940** | | **395** | | **361** | | **196** | |
| MERCURY | mg/kg | 23 | 0.1 | **1.1** | | **0.46** | | **0.38** | | **0.23** | | **0.17** | | **0.25** | | **0.22** | | **0.23** | | **0.11** | | **0.29** | | **0.15** | |
| NICKEL | mg/kg | 1600 | 48 | 18.8 | | 25.1 | | 35.8 | | 15.8 | | 22.8 | | 32.4 | | 14.3 | | 15.7 | | 17.1 | | 28.4 | | 9.9 | |
| POTASSIUM | mg/kg | NC | NC | 1200 | U | 1200 | U | 1300 | U | 1100 | U | 1320 | | 1290 | | 1490 | | 1200 | U | 1200 | U | 1270 | | 1200 | U |
| SELENIUM | mg/kg | 390 | 11 | 2.3 | U | 2.4 | U | 5.2 | U | 2.2 | U | 2.2 | U | 2.4 | U | 2.6 | U | 2.4 | U | 2.5 | U | *12* | *U* | 2.3 | U |
| SILVER | mg/kg | 390 | 1 | 0.95 | | **1.6** | | **1.5** | | 0.55 | U | **1.1** | | 0.6 | U | **1.2** | | **1.7** | | **1.1** | | **24.2** | | **9.2** | |
| SODIUM | mg/kg | NC | NC | 1200 | U | 1200 | U | 1300 | U | 1100 | U | 1100 | U | 1200 | U | 1300 | U | 1200 | U | 1200 | U | 1200 | U | 1200 | U |
| THALLIUM | mg/kg | 5 | 3 | 1.2 | U | 1.2 | U | 2.6 | U | 1.1 | U | 1.1 | U | 1.2 | U | 1.3 | U | 1.2 | U | 1.2 | U | *6* | *U* | *3.5* | *U* |
| VANADIUM | mg/kg | 78 | NC | 32.7 | | 33.1 | | 61.9 | | 25.2 | | 36.7 | | 60.0 | | 25.1 | | 30.3 | | 24.5 | | **87.5** | | 20.9 | |
| ZINC | mg/kg | 23000 | 930 | **1690** | | **3160** | | **9800** | | **3540** | | **3270** | | **3240** | | **1160** | | **2820** | | **3550** | | **24100** | | **9090** | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE C

## Petroleum Soil Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-13-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-15-022714 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-19-031214 | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-22-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB60759-3 | | JB60759-4 | | JB60759-5 | | JB60759-6 | | JB60759-7 | | JB61696-1 | | JB61696-2 | | JB61696-3 | | JB61696-4 | | JB62045-1 | | JB62045-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/14/2014 | | 03/14/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| ALUMINUM | mg/kg | 78000 | 6000 | **9030** | | **8010** | | **7260** | | **6780** | | **6860** | | **7880** | | **8100** | | **10500** | | 3530 | | **8960** | | **9110** | |
| ANTIMONY | mg/kg | 31 | 6 | 2.2 | U | 2.3 | U | 2.8 | U | 2.6 | U | 2.4 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.1 | U | 2.2 | U |
| ARSENIC | mg/kg | 19 | 19 | 5.0 | | 7.0 | | 5.7 | | 5.0 | | 7.0 | | 4.9 | | 5.6 | | 5.1 | | 2.2 | U | 3.9 | | 4.8 | |
| BARIUM | mg/kg | 16000 | 2100 | 50.3 | | 75.3 | | 71.1 | | 77.4 | | 78.3 | | 76.9 | | 97.9 | | 84.5 | | 51.2 | | 90.9 | | 142 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | 0.41 | | 0.48 | | 0.46 | | 0.42 | | 0.45 | | 0.55 | | 0.53 | | **0.81** | | 0.24 | | 0.47 | | 0.53 | |
| CADMIUM | mg/kg | 78 | 2 | 0.56 | U | 0.59 | U | 0.7 | U | 0.66 | U | 0.61 | U | 0.55 | U | **2.1** | | 0.56 | U | 0.54 | U | 0.53 | U | 0.56 | U |
| CALCIUM | mg/kg | NC | NC | 3860 | | 6210 | | 6110 | | 7290 | | 5290 | | 33100 | | 18000 | | 5570 | | 2020 | | 3640 | | 4110 | |
| CHROMIUM | mg/kg | NC | NC | 98.0 | | 374 | | 877 | | 521 | | 806 | | 919 | | 1390 | | 572 | | 431 | | 562 | | 433 | |
| COBALT | mg/kg | 590 | 90 | 7.3 | | 6.5 | | 7 | U | 6.6 | U | 6.1 | U | 5.5 | U | 7.7 | | 10.2 | | 5.4 | U | 6.0 | | 9.7 | |
| COPPER | mg/kg | 3100 | 11000 | 29.0 | | 26.9 | | 29.0 | | 27.3 | | 43.2 | | 29.7 | | 62.0 | | 28.1 | | 8.5 | | 40.1 | | 48.9 | |
| IRON | mg/kg | NC | NC | 16300 | | 19200 | | 13400 | | 13400 | | 13800 | | 13900 | | 15200 | | 19300 | | 6980 | | 14900 | | 16800 | |
| LEAD | mg/kg | 400 | 90 | 31.7 | | 38.7 | | 36.7 | | 46.1 | | 54.3 | | 38.2 | | **116** | | 35.9 | | 12.4 | | 53.7 | | 45.5 | |
| MAGNESIUM | mg/kg | NC | NC | 3900 | | 3630 | | 3010 | | 2840 | | 3320 | | 3740 | | 5400 | | 4690 | | 1500 | | 3190 | | 3730 | |
| MANGANESE | mg/kg | 11000 | 65 | **310** | | **292** | | **233** | | **247** | | **240** | | **308** | | **291** | | **347** | | **78.7** | | **247** | | **317** | |
| MERCURY | mg/kg | 23 | 0.1 | **0.55** | | **0.25** | | **0.17** | | **0.43** | | **0.20** | | **0.24** | | **0.28** | | **0.27** | | 0.070 | | **0.29** | | **0.28** | |
| NICKEL | mg/kg | 1600 | 48 | 19.4 | | 17.3 | | 17.6 | | 17.4 | | 16.3 | | 17.8 | | 34.1 | | 26.1 | | 9.8 | | 28.3 | | **222** | |
| POTASSIUM | mg/kg | NC | NC | 1270 | | 1760 | | 1400 | U | 1300 | U | 1320 | | 1650 | | 1200 | | 2930 | | 1100 | U | 1320 | | 1510 | |
| SELENIUM | mg/kg | 390 | 11 | 2.2 | U | 2.3 | U | 2.8 | U | 2.6 | U | 2.4 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.1 | U | 2.2 | U |
| SILVER | mg/kg | 390 | 1 | **1.6** | | **2.0** | | **8.4** | | **5.9** | | **5.8** | | 0.55 | U | 0.56 | U | 0.79 | | 0.54 | U | 0.53 | U | 1.0 | |
| SODIUM | mg/kg | NC | NC | 1100 | U | 1200 | U | 1400 | U | 1300 | U | 1200 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U |
| THALLIUM | mg/kg | 5 | 3 | 1.1 | U | 1.2 | U | 1.4 | U | 1.3 | U | 1.2 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.1 | U |
| VANADIUM | mg/kg | 78 | NC | 28.8 | | 32.5 | | 30.7 | | 26.9 | | 26.9 | | 27.3 | | 41.4 | | 43.0 | | 10.9 | | 22.3 | | 24.9 | |
| ZINC | mg/kg | 23000 | 930 | 915 | | **1990** | | **7690** | | **5480** | | **5300** | | **3550** | | **2700** | | **3380** | | 894 | | **2610** | | 777 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE C

## Petroleum Soil Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-23-031414 | | 124-A_B-Pet-24-031414 | | 124-A_B-Pet-25-042214 | | 124-A_B-Pet-26-042214 | | 124-A_B-Pet-27-052214 | | 124-A_B-Pet-28-052214 | | 124-A_B-Pet-29-052214 | | 124-A_B-Pet-30-052214 | | 124-A_B-Pet-31-052214 | | 124-A_B-Pet-32-052214 | | 124-A_B-Pet-33-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB62045-3 | | JB62045-4 | | JB65312-1A | | JB65312-2A | | JB67718-1A | | JB67718-2A | | JB67718-3A | | JB67718-4A | | JB67718-5A | | JB67718-6A | | JB67718-7A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 03/14/2014 | | 03/14/2014 | | 04/22/2014 | | 04/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| ALUMINUM | mg/kg | 78000 | 6000 | **9900** | | **10900** | | **6480** | | **9410** | | 3590 | | 3460 | | 3710 | | 4180 | | 4110 | | 4310 | | 4520 | |
| ANTIMONY | mg/kg | 31 | 6 | 2.4 | U | 2.4 | U | **53.9** | | 2.5 | U | 2.3 | UJ | 2.4 | UJ | 2.2 | UJ | 2.2 | UJ | 2.2 | UJ | 2.2 | UJ | 2.2 | UJ |
| ARSENIC | mg/kg | 19 | 19 | 5.8 | | 4.8 | | 8.0 | | **19.6** | | 2.6 | | 2.4 | U | 2.8 | | 2.7 | | 2.2 | U | 2.3 | | 2.2 | U |
| BARIUM | mg/kg | 16000 | 2100 | 123 | | 108 | | **2170** | | 449 | | 34.2 | | 32.5 | | 37.3 | | 39.0 | | 30.6 | | 34.7 | | 31.9 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | 0.66 | | 0.63 | | 0.38 | | **0.84** | | 0.24 | | 0.24 | U | 0.22 | | 0.22 | | 0.22 | U | 0.24 | | 0.25 | |
| CADMIUM | mg/kg | 78 | 2 | 0.59 | U | 0.59 | U | **4.9** | | 0.87 | | 0.57 | U | 0.59 | U | 0.55 | U | 0.56 | U | 0.56 | U | 0.54 | U | 0.54 | U |
| CALCIUM | mg/kg | NC | NC | 5540 | | 4410 | | 11600 | | 11000 | | 4900 | | 2580 | | 2570 | | 2440 | | 2040 | | 2870 | | 1880 | |
| CHROMIUM | mg/kg | NC | NC | 738 | | 913 | | 2720 | J | 260 | J | 306 | | 231 | | 358 | | 232 | | 116 | | 255 | | 100 | |
| COBALT | mg/kg | 590 | 90 | 8.6 | | 7.6 | | 13.4 | | 10.9 | | 5.7 | U | 5.9 | U | 5.5 | U | 5.6 | U | 5.6 | U | 5.4 | U | 5.4 | U |
| COPPER | mg/kg | 3100 | 11000 | 43.3 | | 34.9 | | 86.4 | | 156 | | 9.5 | | 8.9 | | 11.7 | | 10.9 | | 12.9 | | 122 | | 8.8 | |
| IRON | mg/kg | NC | NC | 18000 | | 18000 | | 20700 | | 36100 | | 7170 | | 7100 | | 7680 | | 7870 | | 7740 | | 8140 | | 8300 | |
| LEAD | mg/kg | 400 | 90 | 54.9 | | 53.1 | | **332** | | **406** | | 14.9 | | 10.3 | | 19.0 | | 14.3 | | 9.1 | | 11.7 | | 8.2 | |
| MAGNESIUM | mg/kg | NC | NC | 3760 | | 4370 | | 2790 | | 2580 | | 1820 | | 1680 | | 1740 | | 1810 | | 1920 | | 2020 | | 1980 | |
| MANGANESE | mg/kg | 11000 | 65 | **350** | | **261** | | **865** | | **266** | | **109** | | **97.1** | | **112** | | **115** | | **93.3** | | **117** | | **110** | |
| MERCURY | mg/kg | 23 | 0.1 | **0.31** | | **0.26** | | **6.4** | | **0.78** | | 0.086 | | **0.14** | | **0.14** | | **0.12** | | **0.18** | | 0.098 | | 0.097 | |
| NICKEL | mg/kg | 1600 | 48 | **159** | | 34.4 | | **669** | | **101** | | 8.5 | | 7.1 | | 8.5 | | 28.9 | | 8.6 | | 8.6 | | 8.7 | |
| POTASSIUM | mg/kg | NC | NC | 1740 | | 2160 | | 1100 | U | 1300 | U | 1100 | U | 1200 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U |
| SELENIUM | mg/kg | 390 | 11 | 2.4 | U | 2.4 | U | 11 | U | 2.5 | U | 2.3 | U | 2.4 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.2 | U | 2.2 | U |
| SILVER | mg/kg | 390 | 1 | 0.74 | | 0.75 | | **16.7** | | **2.7** | | 0.57 | U | 0.59 | U | 0.55 | U | 0.70 | | 0.56 | U | 0.69 | | 0.57 | |
| SODIUM | mg/kg | NC | NC | 1200 | U | 1200 | U | 1100 | U | 1300 | U | 1100 | U | 1200 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U | 1100 | U |
| THALLIUM | mg/kg | 5 | 3 | 1.2 | U | 1.2 | U | *5.7* | *U* | 1.3 | U | 1.1 | U | 1.2 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.1 | U | 1.1 | U |
| VANADIUM | mg/kg | 78 | NC | 32.0 | | 33.3 | | 35.6 | | 43.0 | | 9.9 | | 9.7 | | 10 | | 10.2 | | 10.7 | | 10 | | 10.4 | |
| ZINC | mg/kg | 23000 | 930 | **3610** | | **4860** | | **19000** | | 666 | | 33.0 | | 30.8 | | 42.5 | | 34.0 | | 28.9 | | 32.9 | | 26.9 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE C

## Petroleum Soil Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-34-060414 | | 124-A_B-Pet-35-060414 | | 124-A_B-Pet-35a-061914 | | 124-A_B-Pet-35b-061914 | | 124-A_B-Pet-35c-061914 | | 124-A_B-Pet-36-060414 | | 124-A_B-Pet-37-060414 | | 124-A_B-Pet-38-062714 | | 124-A_B-Pet-39-062714 | | 124-A_B-Pet-40-062714 | | 124-A_B-Pet-41-062714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB68443-1A | | JB68443-2A | | JB69908-1/1R | | JB69908-2/2R | | JB69908-3/3R | | JB68443-3A | | JB68443-4A | | JB70484-1A | | JB70484-2A | | JB70484-3A | | JB70484-4A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 06/04/2014 | | 06/04/2014 | | 06/19/2014 | | 06/19/2014 | | 06/19/2014 | | 06/04/2014 | | 06/04/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| ALUMINUM | mg/kg | 78000 | 6000 | 5890 | | **6810** | | | | | | | | 4920 | | 4510 | | 2800 | | 3250 | | 3630 | | 5410 | |
| ANTIMONY | mg/kg | 31 | 6 | 2.3 | U | 2.3 | U | | | | | | | 2.2 | U | 2.2 | U | 2.2 | UJ | 2.1 | UJ | 2.1 | UJ | 3.3 | UJ |
| ARSENIC | mg/kg | 19 | 19 | 2.3 | | 3.5 | | | | | | | | 2.2 | U | 2.3 | | 2.9 | | 3.4 | | 2.5 | | 3.3 | U |
| BARIUM | mg/kg | 16000 | 2100 | 56.7 | | 63.1 | | | | | | | | 38.8 | | 37.4 | | 22 | U | 41.6 | | 46.8 | | 39.8 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | 0.32 | | 0.38 | | | | | | | | 0.26 | | 0.26 | | 0.22 | U | 0.21 | U | 0.21 | U | 0.33 | U |
| CADMIUM | mg/kg | 78 | 2 | 0.57 | U | 0.57 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.55 | U | 0.56 | U | 0.56 | U | 0.52 | U | 0.52 | U | 0.82 | U |
| CALCIUM | mg/kg | NC | NC | 5940 | | 4440 | | | | | | | | 2710 | | 4110 | | 2330 | J | 2340 | J | 2630 | J | 2630 | J |
| CHROMIUM | mg/kg | NC | NC | 364 | | 529 | | | | | | | | 188 | | 249 | | 356 | J | 268 | J | 318 | J | 356 | J |
| COBALT | mg/kg | 590 | 90 | 5.7 | U | 5.7 | U | | | | | | | 5.5 | U | 5.6 | U | 5.6 | U | 5.2 | U | 5.2 | U | 8.2 | U |
| COPPER | mg/kg | 3100 | 11000 | 16.3 | | 31.1 | | | | | | | | 11.8 | | 12.3 | | 4.9 | | 11.7 | | 7.6 | | 8.8 | |
| IRON | mg/kg | NC | NC | 11300 | | 12500 | | | | | | | | 9910 | | 7780 | | 5280 | | 8300 | | 7620 | | 10700 | |
| LEAD | mg/kg | 400 | 90 | 22.1 | | 37.1 | | | | | | | | 14.2 | | 15.9 | | 4.8 | | 23.8 | | 9.3 | | 8.5 | |
| MAGNESIUM | mg/kg | NC | NC | 2860 | | 2890 | | 0.1 | U | 0.1 | U | 0.1 | U | 2080 | | 1970 | | 1330 | | 1380 | | 1740 | | 2530 | |
| MANGANESE | mg/kg | 11000 | 65 | **164** | | **192** | | 0.1 | U | 0.1 | U | 0.1 | U | **180** | | **119** | | **76.6** | J | **110** | J | **106** | J | **127** | J |
| MERCURY | mg/kg | 23 | 0.1 | **0.13** | | **0.39** | | | | | | | | **0.14** | | **0.12** | | 0.061 | | **2.9** | | 0.039 | | 0.062 | |
| NICKEL | mg/kg | 1600 | 48 | 33.6 | | 16.6 | | | | | | | | 11.6 | | 11.0 | | 5.5 | | 11.9 | | 7.4 | | 10.9 | |
| POTASSIUM | mg/kg | NC | NC | 1180 | | 1420 | | | | | | | | 1100 | U | 1100 | U | 1100 | U | 1000 | U | 1000 | U | 1600 | U |
| SELENIUM | mg/kg | 390 | 11 | 2.3 | U | 2.3 | U | | | | | | | 2.2 | U | 2.2 | U | 2.2 | U | 2.1 | U | 2.1 | U | 3.3 | U |
| SILVER | mg/kg | 390 | 1 | 0.57 | U | 0.57 | U | | | | | | | 0.55 | U | 0.56 | U | 0.56 | U | 0.52 | U | 0.52 | U | 0.82 | U |
| SODIUM | mg/kg | NC | NC | 1100 | U | 1100 | U | | | | | | | 1100 | U | 1100 | U | 1100 | U | 1000 | U | 1000 | U | 1600 | U |
| THALLIUM | mg/kg | 5 | 3 | 1.1 | U | 1.1 | U | | | | | | | 1.1 | U | 1.1 | U | 1.1 | U | 1 | U | 1 | U | 1.6 | U |
| VANADIUM | mg/kg | 78 | NC | 18.2 | | 18.3 | | | | | | | | 12.7 | | 12.2 | | 11.2 | | 14.8 | | 10.0 | | 13.7 | |
| ZINC | mg/kg | 23000 | 930 | 57.8 | | 98.1 | | | | | | | | 39.1 | | 41.2 | | 18.7 | | 39.6 | | 26.9 | | 105 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE C

## Petroleum Soil Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-42-062714 | | 124-A_B-Pet-43-081414 | | 124-A_B-Pet-44-081414 | | 124-A_B-Pet-45-081414 | | 124-A_B-Pet-46-081914 | | 124-A_B-Pet-47-090514 | | 124-A_B-Pet-48-090514 | | 124-A_B-Pet-49-090514 | | 124-A_B-Pet-50-102414 | | 124-A_B-Pet-51-102414 | | 124-A_B-Pet-52-102414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB70484-5A | | JB74045-1 | | JB74045-2 | | JB74045-3 | | JB74372-1 | | JB75848-1 | | JB75848-2 | | JB75848-3 | | JB80064-1 | | JB80064-2 | | JB80064-3 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 06/27/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/19/2014 | | 09/05/2014 | | 09/05/2014 | | 09/05/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| ALUMINUM | mg/kg | 78000 | 6000 | **7790** | | **6440** | J | 3950 | J | 3900 | J | 5510 | J | 5430 | J | **7170** | J | 5780 | J | **6630** | | **6630** | | **7910** | |
| ANTIMONY | mg/kg | 31 | 6 | 2.7 | UJ | 2.3 | UJ | 2.2 | UJ | 2.3 | UJ | 2.3 | UJ | 2.1 | UJ | 2.2 | UJ | 2.2 | UJ | *6.2* | *U* | 2.4 | U | 2.1 | U |
| ARSENIC | mg/kg | 19 | 19 | **44.9** | | 5.5 | J | 2.5 | J | 3.2 | J | 4.8 | | 8.1 | | 10.7 | | 5.5 | | 12.6 | | 5.9 | | 6.4 | |
| BARIUM | mg/kg | 16000 | 2100 | 122 | | 60.1 | J | 39.2 | J | 47.8 | J | 94.9 | | 81.7 | | 97.7 | | 57.2 | | 1370 | | 161 | | 129 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | 0.43 | | 0.47 | J | 0.26 | J | 0.28 | J | 0.40 | | 0.41 | | 0.57 | | 0.38 | | 0.48 | | 0.46 | | 0.48 | |
| CADMIUM | mg/kg | 78 | 2 | 0.85 | | 0.57 | UJ | 0.56 | UJ | 0.58 | UJ | 0.58 | U | 0.52 | U | 0.54 | U | 0.56 | U | **5.0** | | 0.59 | U | 0.52 | U |
| CALCIUM | mg/kg | NC | NC | 3250 | J | 2920 | J | 1600 | J | 1990 | J | 2830 | J | 5240 | J | 3300 | J | 3200 | J | 17900 | | 11100 | | 18900 | |
| CHROMIUM | mg/kg | NC | NC | 415 | J | 245 | | 88.6 | | 137 | | 97.6 | | 350 | | 272 | | 218 | | 2540 | J | 813 | | 1620 | |
| COBALT | mg/kg | 590 | 90 | 6.8 | U | 5.7 | UJ | 5.6 | UJ | 5.8 | UJ | 5.8 | U | 5.2 | U | 7.1 | | 5.6 | U | 28.8 | | 9.4 | | 13.8 | |
| COPPER | mg/kg | 3100 | 11000 | 126 | | 22.3 | J | 11.4 | J | 10.4 | J | 17.9 | J | 29.2 | | 44.7 | | 21.3 | | 3000 | | 43.7 | | 90.7 | |
| IRON | mg/kg | NC | NC | 17400 | | 12700 | J | 7170 | J | 8310 | J | 11700 | J | 13500 | | 17300 | | 11600 | | 39300 | | 18400 | | 19800 | |
| LEAD | mg/kg | 400 | 90 | **183** | | 36.8 | J | 16.2 | J | 25.9 | J | 25.6 | J | 19.4 | | 19.9 | | 18.5 | | **608** | | 24.6 | | 27.0 | |
| MAGNESIUM | mg/kg | NC | NC | 3260 | | 2480 | J | 1430 | J | 1600 | J | 2630 | | 2290 | J | 2630 | J | 2310 | J | 4700 | | 4120 | | 5480 | |
| MANGANESE | mg/kg | 11000 | 65 | **186** | J | **165** | J | **79.9** | J | **98** | J | **196** | | **148** | J | **163** | J | **155** | J | **902** | | **245** | | **279** | |
| MERCURY | mg/kg | 23 | 0.1 | 0.048 | U | 0.046 | | 0.037 | | 0.071 | | **0.20** | | **0.22** | | **0.18** | | **0.11** | | **5.2** | | **0.76** | | **0.38** | |
| NICKEL | mg/kg | 1600 | 48 | 28.8 | | **85.5** | J | 8.4 | J | 9.3 | J | 12.4 | J | **98.9** | | **167** | | **90.8** | | **6070** | | **152** | | **169** | |
| POTASSIUM | mg/kg | NC | NC | 1450 | | 1180 | J | 1100 | UJ | 1200 | UJ | 1200 | U | 1000 | U | 1100 | U | 1100 | U | 1090 | | 1220 | | 1000 | U |
| SELENIUM | mg/kg | 390 | 11 | 2.7 | U | 2.3 | UJ | 2.2 | UJ | 2.3 | UJ | 2.3 | U | 2.1 | U | 2.2 | U | 2.2 | U | 2.1 | U | 2.4 | U | 2.1 | U |
| SILVER | mg/kg | 390 | 1 | **1.7** | | 0.57 | UJ | 0.56 | UJ | 0.58 | UJ | 0.69 | | 0.52 | U | 0.54 | U | 0.56 | U | **25.4** | | 0.94 | | **1.2** | |
| SODIUM | mg/kg | NC | NC | 1400 | U | 1100 | UJ | 1100 | UJ | 1200 | UJ | 1200 | U | 1000 | U | 1100 | U | 1100 | U | 1000 | U | 1200 | U | 1000 | U |
| THALLIUM | mg/kg | 5 | 3 | 1.4 | U | 1.1 | UJ | 1.1 | UJ | 1.2 | UJ | 1.2 | U | 1 | U | 1.1 | U | 1.1 | U | *3.1* | *U* | 1.2 | U | 1 | U |
| VANADIUM | mg/kg | 78 | NC | 21.5 | | 21.2 | J | 11.7 | J | 13.1 | J | 15.7 | | 23.5 | | 30.4 | | 18.5 | | 49.7 | | 33.8 | | 58.4 | |
| ZINC | mg/kg | 23000 | 930 | 264 | | 87.2 | J | 36.7 | J | 39.8 | J | 50 | J | 76.0 | | 57.7 | | 56.9 | | **6820** | | 649 | | 771 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE C

## Petroleum Soil Sample Results – Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-53-102414 | | 124-C-Pet-01-102414 | | 134-SB-604-0627 | |
|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB80064-4 | | JB80065-1 | | JB70486-1A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 10/24/2014 | | 10/24/2014 | | 06/27/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q |
| ALUMINUM | mg/kg | 78000 | 6000 | **8780** | | **9770** | **J** | | |
| ANTIMONY | mg/kg | 31 | 6 | *12* | *U* | 6 | J | | |
| ARSENIC | mg/kg | 19 | 19 | 11.5 | | 11.8 | | 5.5 | |
| BARIUM | mg/kg | 16000 | 2100 | **2200** | | **2750** | | 104 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | *1.2* | *U* | *1* | *U* | 0.39 | |
| CADMIUM | mg/kg | 78 | 2 | **2.1** | | **19.7** | | 0.53 | U |
| CALCIUM | mg/kg | NC | NC | 33400 | | 23100 | J | | |
| CHROMIUM | mg/kg | NC | NC | 6360 | | 1530 | J | 963 | J |
| COBALT | mg/kg | 590 | 90 | 9.9 | | 15.7 | | | |
| COPPER | mg/kg | 3100 | 11000 | 79.4 | | 245 | | 24.2 | |
| IRON | mg/kg | NC | NC | 21300 | | 32700 | J | | |
| LEAD | mg/kg | 400 | 90 | **93.2** | | **499** | | 56.6 | |
| MAGNESIUM | mg/kg | NC | NC | 4160 | | 4720 | J | | |
| MANGANESE | mg/kg | 11000 | 65 | **468** | | **1300** | **J** | | |
| MERCURY | mg/kg | 23 | 0.1 | **2.3** | | **10.5** | | **0.29** | |
| NICKEL | mg/kg | 1600 | 48 | **503** | | **784** | | **94.4** | |
| POTASSIUM | mg/kg | NC | NC | 1520 | | 1100 | | | |
| SELENIUM | mg/kg | 390 | 11 | 2.3 | U | 2 | U | 2.1 | U |
| SILVER | mg/kg | 390 | 1 | **4.7** | | **14.5** | | 0.53 | U |
| SODIUM | mg/kg | NC | NC | 1200 | U | 1000 | U | | |
| THALLIUM | mg/kg | 5 | 3 | *5.8* | *U* | *5* | *U* | | |
| VANADIUM | mg/kg | 78 | NC | 42.5 | | 41.1 | | 26.2 | |
| ZINC | mg/kg | 23000 | 930 | **16700** | | **14100** | **J** | 506 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE D

## Petroleum Soil Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-06-012814 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-08-012814 | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-11-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB57182-1/1A | | JB57182-2/2A | | JB58165-1/1A | | JB58764-1/1A | | JB58764-2/2A | | JB58764-3/3A | | JB58764-4/4A | | JB58764-5/5A | | JB58764-6/6A | | JB60759-1/1A | | JB60759-2/2A | |
| Date Sampled | | | | 01/08/2014 | | 01/08/2014 | | 01/20/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 02/27/2014 | | 02/27/2014 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | mg/kg | 3 | 4 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDE | mg/kg | 2 | 18 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDT | mg/kg | 2 | 11 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALDRIN | mg/kg | 0.04 | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-BHC | mg/kg | 0.1 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1016 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1221 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1232 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1242 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1248 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1254 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1260 | mg/kg | NC | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| AROCLOR-1262 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1268 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **TOTAL PCBs** | mg/kg | 0.2 | 0.2 | 0.037 | U | 0.039 | U | 0.041 | U | 0.035 | U | 0.036 | U | 0.041 | U | 0.04 | U | 0.038 | U | 0.041 | U | 0.037 | U | 0.036 | U |
| BETA-BHC | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BETA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHLORDANE | mg/kg | 0.2 | 0.05 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DELTA-BHC | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | mg/kg | 0.04 | 0.003 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN I | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN II | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN SULFATE | mg/kg | 470 | 2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN | mg/kg | 23 | 1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN ALDEHYDE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN KETONE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| GAMMA-BHC (LINDANE) | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR | mg/kg | 0.1 | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR EPOXIDE | mg/kg | 0.07 | 0.01 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| METHOXYCHLOR | mg/kg | 390 | 160 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | mg/kg | 3 | 0.3 | *0.36* | *U* | *0.38* | *U* | *0.42* | *U* | *0.38* | *U* | *0.36* | *U* | *0.36* | *U* | *0.37* | *U* | *0.35* | *U* | *0.38* | *U* | *0.36* | *U* | *0.35* | *U* |
| TOXAPHENE | mg/kg | 0.6 | 0.3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

P: Pesticide/Aroclor analyte has greater than 25% difference between the two GC columns

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

PCBs: Polychlorinated Biphenyls



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE D

## Petroleum Soil Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-13-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-15-022714 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-19-031214 | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-22-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB60759-3/3A | | JB60759-4/4A | | JB60759-5/5A | | JB60759-6/6A | | JB60759-7/7A | | JB61696-1/1A | | JB61696-2/2A | | JB61696-3/3A | | JB61696-4/4A | | JB62045-1/1A | | JB62045-2/2A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/14/2014 | | 03/14/2014 | |
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | mg/kg | 3 | 4 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDE | mg/kg | 2 | 18 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDT | mg/kg | 2 | 11 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALDRIN | mg/kg | 0.04 | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-BHC | mg/kg | 0.1 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1016 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1221 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1232 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1242 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1248 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1254 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1260 | mg/kg | NC | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| AROCLOR-1262 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1268 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| **TOTAL PCBs** | mg/kg | 0.2 | 0.2 | 0.035 | U | 0.038 | U | 0.038 | U | 0.044 | U | 0.035 | U | 0.035 | U | 0.034 | U | 0.038 | U | 0.033 | U | 0.036 | U | 0.039 | U |
| BETA-BHC | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BETA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHLORDANE | mg/kg | 0.2 | 0.05 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DELTA-BHC | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | mg/kg | 0.04 | 0.003 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN I | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN II | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN SULFATE | mg/kg | 470 | 2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN | mg/kg | 23 | 1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN ALDEHYDE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN KETONE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| GAMMA-BHC (LINDANE) | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR | mg/kg | 0.1 | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR EPOXIDE | mg/kg | 0.07 | 0.01 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| METHOXYCHLOR | mg/kg | 390 | 160 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | mg/kg | 3 | 0.3 | *0.38* | *U* | *0.38* | *U* | *0.42* | *U* | *0.46* | *U* | *0.37* | *U* | *0.35* | *U* | *0.38* | *U* | *0.39* | *U* | *0.34* | *U* | *0.34* | *U* | *0.34* | *U* |
| TOXAPHENE | mg/kg | 0.6 | 0.3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

P: Pesticide/Aroclor analyte has greater than 25% difference between the two GC columns

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

PCBs: Polychlorinated Biphenyls



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE D

## Petroleum Soil Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-23-031414 | | 124-A_B-Pet-24-031414 | | 124-A_B-Pet-25-042214 | | 124-A_B-Pet-26-042214 | | 124-A_B-Pet-27-052214 | | 124-A_B-Pet-28-052214 | | 124-A_B-Pet-29-052214 | | 124-A_B-Pet-30-052214 | | 124-A_B-Pet-31-052214 | | 124-A_B-Pet-32-052214 | | 124-A_B-Pet-33-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB62045-3/3A | | JB62045-4/4A | | JB65312-1/1A/1B | | JB65312-2/2A/2B | | JB67718-1A | | JB67718-2A | | JB67718-3A | | JB67718-4A | | JB67718-5A | | JB67718-6A | | JB67718-7A | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 03/14/2014 | | 03/14/2014 | | 04/22/2014 | | 04/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | |
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | mg/kg | 3 | 4 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.0018 | | 0.00076 | U | 0.0055 | | 0.0007 | U |
| 4,4'-DDE | mg/kg | 2 | 18 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.0022 | | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| 4,4'-DDT | mg/kg | 2 | 11 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.0036 | | 0.00076 | U | 0.0032 | | 0.0007 | U |
| ALDRIN | mg/kg | 0.04 | 0.2 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ALPHA-BHC | mg/kg | 0.1 | 0.002 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ALPHA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| AROCLOR-1016 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1221 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1232 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1242 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1248 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1254 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1260 | mg/kg | NC | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1262 | mg/kg | NC | 0.2 | - | | - | | - | | - | | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| AROCLOR-1268 | mg/kg | NC | 0.2 | - | | - | | - | | - | | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| **TOTAL PCBs** | mg/kg | 0.2 | 0.2 | 0.039 | U | 0.039 | U | 0.04 | U | 0.039 | U | 0.035 | U | 0.038 | U | 0.036 | U | 0.034 | U | 0.038 | U | 0.034 | U | 0.035 | U |
| BETA-BHC | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| BETA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| CHLORDANE | mg/kg | 0.2 | 0.05 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| DELTA-BHC | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| DIELDRIN | mg/kg | 0.04 | 0.003 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ENDOSULFAN I | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ENDOSULFAN II | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ENDOSULFAN SULFATE | mg/kg | 470 | 2 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ENDRIN | mg/kg | 23 | 1 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ENDRIN ALDEHYDE | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| ENDRIN KETONE | mg/kg | NC | NC | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| GAMMA-BHC (LINDANE) | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| HEPTACHLOR | mg/kg | 0.1 | 0.5 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| HEPTACHLOR EPOXIDE | mg/kg | 0.07 | 0.01 | - | | - | | - | | - | | 0.0007 | U | 0.00076 | U | 0.00071 | U | 0.00069 | U | 0.00076 | U | 0.00067 | U | 0.0007 | U |
| METHOXYCHLOR | mg/kg | 390 | 160 | - | | - | | - | | - | | 0.0014 | U | 0.0015 | U | 0.0014 | U | 0.0014 | U | 0.0015 | U | 0.0013 | U | 0.0014 | U |
| PENTACHLOROPHENOL | mg/kg | 3 | 0.3 | *0.37* | *U* | *0.37* | *U* | *0.36* | *U* | *0.37* | *U* | *0.36* | *U* | *0.35* | *U* | *0.35* | *U* | *0.33* | *U* | *0.35* | *U* | *0.35* | *U* | *0.33* | *U* |
| TOXAPHENE | mg/kg | 0.6 | 0.3 | - | | - | | - | | - | | 0.018 | U | 0.019 | U | 0.018 | U | 0.017 | U | 0.019 | U | 0.017 | U | 0.018 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

P: Pesticide/Aroclor analyte has greater than 25% difference between the two GC columns

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

PCBs: Polychlorinated Biphenyls



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE D

## Petroleum Soil Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-34-060414 | | 124-A_B-Pet-35-060414 | | 124-A_B-Pet-36-060414 | | 124-A_B-Pet-37-060414 | | 124-A_B-Pet-38-062714 | | 124-A_B-Pet-39-062714 | | 124-A_B-Pet-40-062714 | | 124-A_B-Pet-41-062714 | | 124-A_B-Pet-42-062714 | | 124-A_B-Pet-43-081414 | | 124-A_B-Pet-44-081414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB68443-1A | | JB68443-2A | | JB68443-3A | | JB68443-4A | | JB70484-1A | | JB70484-2A | | JB70484-3A | | JB70484-4A | | JB70484-5A | | JB74045-1 | | JB74045-2 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 08/14/2014 | | 08/14/2014 | |
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | mg/kg | 3 | 4 | 0.0013 | | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDE | mg/kg | 2 | 18 | 0.0011 | | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDT | mg/kg | 2 | 11 | 0.0019 | | 0.0017 | | 0.0011 | | 0.0009 | | - | | - | | - | | - | | - | | - | | - | |
| ALDRIN | mg/kg | 0.04 | 0.2 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-BHC | mg/kg | 0.1 | 0.002 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-CHLORDANE | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1016 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1221 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1232 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1242 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1248 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1254 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1260 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1262 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1268 | mg/kg | NC | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | - | | - | | - | | - | | - | | - | | - | |
| **TOTAL PCBs** | mg/kg | 0.2 | 0.2 | 0.036 | U | 0.037 | U | 0.036 | U | 0.036 | U | | | | | | | | | | | | | | |
| BETA-BHC | mg/kg | 0.4 | 0.002 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| BETA-CHLORDANE | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| CHLORDANE | mg/kg | 0.2 | 0.05 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| DELTA-BHC | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | mg/kg | 0.04 | 0.003 | 0.00073 | U | 0.0009 | | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN I | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN II | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN SULFATE | mg/kg | 470 | 2 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN | mg/kg | 23 | 1 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN ALDEHYDE | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN KETONE | mg/kg | NC | NC | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| GAMMA-BHC (LINDANE) | mg/kg | 0.4 | 0.002 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR | mg/kg | 0.1 | 0.5 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR EPOXIDE | mg/kg | 0.07 | 0.01 | 0.00073 | U | 0.00074 | U | 0.00073 | U | 0.00072 | U | - | | - | | - | | - | | - | | - | | - | |
| METHOXYCHLOR | mg/kg | 390 | 160 | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0014 | U | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | mg/kg | 3 | 0.3 | *0.38* | *U* | *0.34* | *U* | *0.34* | *U* | *0.34* | *U* | *0.35* | *U* | *0.36* | *U* | *0.38* | *U* | *0.5* | *U* | *0.49* | *U* | *0.35* | *U* | *0.37* | *U* |
| TOXAPHENE | mg/kg | 0.6 | 0.3 | 0.018 | U | 0.019 | U | 0.018 | U | 0.018 | U | - | | - | | - | | - | | - | | - | | - | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

P: Pesticide/Aroclor analyte has greater than 25% difference between the two GC columns

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

PCBs: Polychlorinated Biphenyls



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE D

## Petroleum Soil Sample Results – Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-45-081414 | | 124-A_B-Pet-46-081914 | | 124-A_B-Pet-47-090514 | | 124-A_B-Pet-48-090514 | | 124-A_B-Pet-49-090514 | | 124-A_B-Pet-50-102414 | | 124-A_B-Pet-51-102414 | | 124-A_B-Pet-52-102414 | | 124-A_B-Pet-53-102414 | | 124-C-Pet-01-102414 | | 134-SB-604-0627 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB74045-3 | | JB74372-1 | | JB75848-1 | | JB75848-2 | | JB75848-3 | | JB80064-1 | | JB80064-2 | | JB80064-3 | | JB80064-4 | | JB80065-1 | | JB70486-1A | |
| Date Sampled | | | | 08/14/2014 | | 08/19/2014 | | 09/05/2014 | | 09/05/2014 | | 09/05/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 06/27/2014 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| 4,4'-DDD | mg/kg | 3 | 4 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDE | mg/kg | 2 | 18 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 4,4'-DDT | mg/kg | 2 | 11 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALDRIN | mg/kg | 0.04 | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-BHC | mg/kg | 0.1 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ALPHA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| AROCLOR-1016 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1221 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1232 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1242 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1248 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1254 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1260 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1262 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| AROCLOR-1268 | mg/kg | NC | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.038 | U |
| **TOTAL PCBs** | mg/kg | 0.2 | 0.2 | | | | | | | | | | | | | | | | | | | | | 0.038 | U |
| BETA-BHC | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BETA-CHLORDANE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHLORDANE | mg/kg | 0.2 | 0.05 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DELTA-BHC | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIELDRIN | mg/kg | 0.04 | 0.003 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN I | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN II | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDOSULFAN SULFATE | mg/kg | 470 | 2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN | mg/kg | 23 | 1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN ALDEHYDE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ENDRIN KETONE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| GAMMA-BHC (LINDANE) | mg/kg | 0.4 | 0.002 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR | mg/kg | 0.1 | 0.5 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEPTACHLOR EPOXIDE | mg/kg | 0.07 | 0.01 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| METHOXYCHLOR | mg/kg | 390 | 160 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PENTACHLOROPHENOL | mg/kg | 3 | 0.3 | *0.36* | *U* | *0.36* | *U* | *0.35* | *U* | *0.36* | *U* | *0.36* | *U* | *0.42* | *U* | *0.38* | *U* | *0.33* | *U* | *0.38* | *U* | *0.43* | *U* | *0.38* | *U* |
| TOXAPHENE | mg/kg | 0.6 | 0.3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C.

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; las

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

P: Pesticide/Aroclor analyte has greater than 25% difference between the two GC columns

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

PCBs: Polychlorinated Biphenyls



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-04a-012914 | | 124-A_B-Pet-04b-012914 | | 124-A_B-Pet-04c-012914 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-05a-012914 | | 124-A_B-Pet-05b-012914 | | 124-A_B-Pet-05c-012914 | | 124-A_B-Pet-06-012814 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB57182-1R | | JB57182-2R | | JB58165-1 | | JB58764-1 | | JB58764-7 | | JB58764-8 | | JB58764-9 | | JB58764-2 | | JB58764-10 | | JB58764-11 | | JB58764-12 | | JB58764-3 | |
| | | Date Sampled | 01/08/2014 | | 01/08/2014 | | 01/20/2014 | | 01/28/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 01/28/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 01/28/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | 1070 | | 5550 | | 1880 | | 542 | | 170 | | 241 | | 258 | | 444 | | 186 | | 140 | | 41.3 | | 870 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | 13 | U | 13 | U | 31.1 | | 13 | U | 13 | U | 13 | U | 15 | U | 12 | U | 12 | U | 11 | U | 13 | U | 14 | U |
| Residual Range Organics, Aliphatic | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amended 8/9/2010

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value for total organic contaminants in the Soil Cleanup Criteria Table; last amended 5/12/1999

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-06a-012914 | | 124-A_B-Pet-06b-012914 | | 124-A_B-Pet-06c-012914 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-07a-012914 | | 124-A_B-Pet-07b-012914 | | 124-A_B-Pet-07c-012914 | | 124-A_B-Pet-07d-012914 | | 124-A_B-Pet-08-012814 | | 124-A_B-Pet-08a-012914 | | 124-A_B-Pet-08b-012914 | | 124-A_B-Pet-08c-012914 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB58764-13 | | JB58764-14 | | JB58764-15 | | JB58764-4 | | JB58764-16 | | JB58764-17 | | JB58764-18 | | JB58764-19 | | JB58764-5 | | JB58764-20 | | JB58764-21 | | JB58764-22 | |
| | | Date Sampled | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 01/28/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 01/28/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | 547 | | 1040 | | 325 | | 328 | | 1380 | | 130 | | 668 | | 737 | | 410 | | 3100 | | 191 | | 273 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | 14 | U | 10 | U | 13 | U | 14 | U | 12 | U | 13 | U | 12 | U | 12 | U | 13 | U | 12 | U | 11 | U | 12 | U |
| Residual Range Organics, Aliphatic | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | Client Sample ID | 124-A_B-Pet-08d-012914 | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-09a-012914 | | 124-A_B-Pet-09b-012914 | | 124-A_B-Pet-09c-012914 | | 124-A_B-Pet-09d-012914 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-10a-022714 | | 124-A_B-Pet-10b-022714 | | 124-A_B-Pet-10c-022714 | | 124-A_B-Pet-10d-022714 | | 124-A_B-Pet-11-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Lab Sample ID | JB58764-23 | | JB58764-6 | | JB58764-24 | | JB58764-25 | | JB58764-26 | | JB58764-27 | | JB60759-1 | | JB60759-8 | | JB60759-9 | | JB60759-10 | | JB60759-11 | | JB60759-2 | |
| | Date Sampled | 01/29/2014 | | 01/28/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 01/29/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 171 | | 370 | | 591 | | 752 | | 329 | | 420 | | 348 | | 336 | | 155 | | 627 | | 212 | | 196 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | 14 | U | 15 | U | 12 | U | 13 | U | 14 | U | 13 | U | 13 | U | 14 | U | 13 | U | 15 | U | 12 | U | 14 | U |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-11a-022714 | | 124-A_B-Pet-11b-022714 | | 124-A_B-Pet-11c-022714 | | 124-A_B-Pet-11d-022714 | | 124-A_B-Pet-11-EPH-071014 | | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-12a-022714 | | 124-A_B-Pet-12b-022714 | | 124-A_B-Pet-12c-022714 | | 124-A_B-Pet-12d-022714 | | 124-A_B-Pet-13-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB60759-12 | | JB60759-13 | | JB60759-14 | | JB60759-15 | | JB71450-1 | | JB60759-3 | | JB60759-16 | | JB60759-17 | | JB60759-18 | | JB60759-19 | | JB60759-4 | |
| Date Sampled | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 07/10/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 6.64 | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 21.4 | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 186 | | - | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 66.7 | | - | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 60.9 | | - | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | 342 | | - | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 303 | | 322 | | 501 | | 204 | | - | | 1090 | J | 2320 | | 1190 | | 2340 | | 1280 | | 842 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | 13 | U | 15 | U | 15 | U | 13 | U | - | | 13 | U | 13 | U | 13 | U | 12 | U | 14 | U | 14 | U |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | 89.0 | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | 253 | | - | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-13a-022714 | | 124-A_B-Pet-13b-022714 | | 124-A_B-Pet-13c-022714 | | 124-A_B-Pet-13d-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-14a-022714 | | 124-A_B-Pet-14b-022714 | | 124-A_B-Pet-14c-022714 | | 124-A_B-Pet-14d-022714 | | 124-A_B-Pet-14-EPH-071014 | | 124-A_B-Pet-15-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB60759-20 | | JB60759-21 | | JB60759-22 | | JB60759-23 | | JB60759-5 | | JB60759-24 | | JB60759-25 | | JB60759-26 | | JB60759-27 | | JB71450-2 | | JB60759-6 | |
| Date Sampled | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 07/10/2014 | | 02/27/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 5.5 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 5.5 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 5.5 | U | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 5.5 | U | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 19.2 | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 21.5 | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 25.2 | | - | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 66.0 | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 892 | | 575 | | 521 | | 807 | | 713 | | 381 | | 766 | | 284 | | 187 | | - | | 270 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | 12 | U | 14 | U | 14 | U | 13 | U | 15 | U | 13 | U | 15 | U | 13 | U | 19 | U | - | | 16 | U |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 25.2 | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 40.7 | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | 5.5 | U | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-15a-022714 | | 124-A_B-Pet-15b-022714 | | 124-A_B-Pet-15c-022714 | | 124-A_B-Pet-15d-022714 | | 124-A_B-Pet-15-EPH-071014 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-16a-022714 | | 124-A_B-Pet-16b-022714 | | 124-A_B-Pet-16c-022714 | | 124-A_B-Pet-16d-022714 | | 124-A_B-Pet-16-EPH-071014 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB60759-28 | | JB60759-29 | | JB60759-30 | | JB60759-31 | | JB71450-3 | | JB60759-7 | | JB60759-32 | | JB60759-33 | | JB60759-34 | | JB60759-35 | | JB71450-4 | |
| Date Sampled | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 07/10/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 07/10/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.4 | U | - | | - | | - | | - | | - | | 5.1 | U |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 5.4 | U | - | | - | | - | | - | | - | | 5.1 | U |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.4 | U | - | | - | | - | | - | | - | | 5.1 | U |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 5.4 | U | - | | - | | - | | - | | - | | 8.54 | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 28.3 | | - | | - | | - | | - | | - | | 26.6 | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 18.8 | | - | | - | | - | | - | | - | | 33.8 | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 23.0 | | - | | - | | - | | - | | - | | 33.5 | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | 70.1 | | - | | - | | - | | - | | - | | 102 | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 448 | | 559 | | 406 | | 374 | | - | | 186 | | 284 | | 268 | | 443 | | 333 | | - | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | 15 | U | 15 | U | 13 | U | 14 | U | - | | 13 | U | 15 | U | 13 | U | 13 | U | 14 | U | - | |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | 23.0 | | - | | - | | - | | - | | - | | 42.0 | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | 47.0 | | - | | - | | - | | - | | - | | 60.4 | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | 5.4 | U | - | | - | | - | | - | | - | | 5.1 | U |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-17a-031214 | | 124-A_B-Pet-17b-031214 | | 124-A_B-Pet-17c-031214 | | 124-A_B-Pet-17d-031214 | | 124-A_B-Pet-17-EPH-071014 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-18a-031214 | | 124-A_B-Pet-18b-031214 | | 124-A_B-Pet-18c-031214 | | 124-A_B-Pet-18d-031214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB61696-1 | | JB61696-5 | | JB61696-6 | | JB61696-7 | | JB61696-8 | | JB71450-5 | | JB61696-2 | | JB61696-9 | | JB61696-10 | | JB61696-11 | | JB61696-12 | |
| Date Sampled | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 07/10/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | 11.3 | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | 60.3 | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | 29.3 | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | 43.0 | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | - | | 144 | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 759 | | 861 | | 867 | | 495 | | 993 | | - | | 528 | | 322 | | 481 | | 514 | | 528 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | 12 | U | 12 | U | 14 | U | 13 | U | 11 | U | - | | 13 | U | 13 | U | 11 | U | 12 | U | 13 | U |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | - | | 54.3 | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | - | | 89.6 | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | | 124-A_B-Pet-18-EPH-071014 | | 124-A_B-Pet-19-031214 | | 124-A_B-Pet-19a-031214 | | 124-A_B-Pet-19b-031214 | | 124-A_B-Pet-19c-031214 | | 124-A_B-Pet-19d-031214 | | 124-A_B-Pet-19-EPH-071014 | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-20a-031214 | | 124-A_B-Pet-20b-031214 | | 124-A_B-Pet-20c-031214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | | JB71450-6 | | JB61696-3 | | JB61696-13 | | JB61696-14 | | JB61696-15 | | JB61696-16 | | JB71450-7 | | JB61696-4 | | JB61696-17 | | JB61696-18 | | JB61696-19 | |
| | | Date Sampled | | 07/10/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 07/10/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 5.5 | U | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | | 7.71 | | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 7.57 | | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | | 21.0 | | - | | - | | - | | - | | - | | 8.00 | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 118 | | - | | - | | - | | - | | - | | 27.3 | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 64.2 | | - | | - | | - | | - | | - | | 18.9 | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | | 88.1 | | - | | - | | - | | - | | - | | 38.7 | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | | | 307 | | - | | - | | - | | - | | - | | 92.9 | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | | - | | 1030 | | 712 | | 749 | | 721 | | 508 | | - | | 79.5 | | 157 | | 90.7 | | 131 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | | - | | 13 | U | 12 | U | 12 | U | 12 | U | 13 | U | - | | 12 | U | 12 | U | 12 | U | 12 | U |
| Residual Range Organics, Aliphatic | mg/kg | | | 117 | | - | | - | | - | | - | | - | | 46.7 | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | | | 190 | | - | | - | | - | | - | | - | | 46.1 | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | | 5.5 | U | - | | - | | - | | - | | - | | 5.1 | U | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-20d-031214 | | 124-A_B-Pet-20-EPH-071014 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-21a-031414 | | 124-A_B-Pet-21b-031414 | | 124-A_B-Pet-21c-031414 | | 124-A_B-Pet-21d-031414 | | 124-A_B-Pet-21-EPH-071014 | | 124-A_B-Pet-22-031414 | | 124-A_B-Pet-22a-031414 | | 124-A_B-Pet-22b-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB61696-20 | | JB71450-8 | | JB62045-1 | | JB62045-5 | | JB62045-6 | | JB62045-7 | | JB62045-8 | | JB71450-9 | | JB62045-2 | | JB62045-9 | | JB62045-10 | |
| Date Sampled | | 03/12/2014 | | 07/10/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 07/10/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | 5.8 | U | - | | - | | - | | - | | - | | 5.3 | U | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | 10.9 | | - | | - | | - | | - | | - | | 6.26 | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | 5.8 | U | - | | - | | - | | - | | - | | 5.3 | U | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | 19.8 | | - | | - | | - | | - | | - | | 12.7 | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | 44.6 | | - | | - | | - | | - | | - | | 19.1 | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | 42.8 | | - | | - | | - | | - | | - | | 29.0 | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | 67.9 | | - | | - | | - | | - | | - | | 59.3 | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | - | | 186 | | - | | - | | - | | - | | - | | 126 | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 122 | | - | | 366 | J | 227 | J | 176 | J | 122 | J | 104 | J | - | | 256 | J | 335 | J | 406 | J |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | 11 | U | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | - | | 98.6 | | - | | - | | - | | - | | - | | 78.3 | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | 87.3 | | - | | - | | - | | - | | - | | 48.1 | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | 5.8 | U | - | | - | | - | | - | | - | | 5.3 | U | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-22c-031414 | | 124-A_B-Pet-22d-031414 | | 124-A_B-Pet-23-031414 | | 124-A_B-Pet-23a-031414 | | 124-A_B-Pet-23b-031414 | | 124-A_B-Pet-23c-031414 | | 124-A_B-Pet-23d-031414 | | 124-A_B-Pet-24-031414 | | 124-A_B-Pet-24a-031414 | | 124-A_B-Pet-24b-031414 | | 124-A_B-Pet-24c-031414 | | 124-A_B-Pet-24d-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB62045-11 | | JB62045-12 | | JB62045-3 | | JB62045-13 | | JB62045-14 | | JB62045-15 | | JB62045-16 | | JB62045-4 | | JB62045-17 | | JB62045-18 | | JB62045-19 | | JB62045-20 | |
| | | Date Sampled | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | 952 | J | 138 | J | 1060 | J | 713 | J | 613 | J | 663 | J | 1740 | J | 128 | J | 35.2 | J | 72.3 | J | 58.5 | J | 157 | J |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-24-EPH-071014 | | 124-A_B-Pet-25-042214 | | 124-A_B-Pet-25a-042214 | | 124-A_B-Pet-25b-042214 | | 124-A_B-Pet-25c-042214 | | 124-A_B-Pet-25d-042214 | | 124-A_B-Pet-25-EPH-071014 | | 124-A_B-Pet-26-EPH-071014 | | 124-A_B-Pet-26a-042214 | | 124-A_B-Pet-26b-042214 | | 124-A_B-Pet-26c-042214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB71450-10 | | JB65312-1A | | JB65312-3 | | JB65312-4 | | JB65312-5 | | JB65312-6 | | JB71450-11 | | JB71450-12 | | JB65312-7 | | JB65312-8 | | JB65312-9 | |
| | | Date Sampled | 07/10/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 07/10/2014 | | 07/10/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | 5.6 | U | - | | - | | - | | - | | - | | 5.7 | U | 6.5 | U | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | 5.6 | U | - | | - | | - | | - | | - | | 25.5 | | 17.2 | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | 5.6 | U | - | | - | | - | | - | | - | | 9.62 | | 6.5 | U | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | 11.4 | | - | | - | | - | | - | | - | | 40.9 | | 81.0 | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | 40.1 | | - | | - | | - | | - | | - | | 24.9 | | 23.8 | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | 50.3 | | - | | - | | - | | - | | - | | 102 | | 99.1 | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | 75.6 | | - | | - | | - | | - | | - | | 246 | | 374 | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | | 177 | | - | | - | | - | | - | | - | | 449 | | 595 | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | - | | 1900 | | 1710 | | 907 | | 1010 | | 707 | | - | | - | | 599 | | 571 | | 986 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | | 87.0 | | - | | - | | - | | - | | - | | 312 | | 472 | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | | 90.5 | | - | | - | | - | | - | | - | | 137 | | 123 | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | 5.6 | U | - | | - | | - | | - | | - | | 5.7 | U | 6.5 | U | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-26d-042214 | | 124-A_B-Pet-26-042214 | | 124-A_B-Pet-27-052214 | | 124-A_B-Pet-27a-052214 | | 124-A_B-Pet-27b-052214 | | 124-A_B-Pet-27c-052214 | | 124-A_B-Pet-27d-052214 | | 124-A_B-Pet-27-EPH-072814 | | 124-A_B-Pet-28-052214 | | 124-A_B-Pet-28a-052214 | | 124-A_B-Pet-28b-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB65312-10 | | JB65312-2A | | JB67718-1A | | JB67718-8 | | JB67718-9 | | JB67718-10 | | JB67718-11 | | JB72707-1 | | JB67718-2A | | JB67718-12 | | JB67718-13 | |
| Date Sampled | | 04/22/2014 | | 04/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 5.8 | U | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 27.2 | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 5.8 | U | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 40.6 | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 21.3 | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 5.8 | U | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 29.1 | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | - | | - | | - | | 118 | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 1900 | | 575 | | 987 | | 3230 | | 828 | | 546 | | 813 | | - | | 362 | | 342 | | 319 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | - | | - | | - | | 96.9 | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | - | | - | | - | | 21.3 | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | - | | - | | - | | 5.8 | U | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-28c-052214 | | 124-A_B-Pet-28d-052214 | | 124-A_B-Pet-28-EPH-072814 | | 124-A_B-Pet-29-052214 | | 124-A_B-Pet-29a-052214 | | 124-A_B-Pet-29b-052214 | | 124-A_B-Pet-29c-052214 | | 124-A_B-Pet-29d-052214 | | 124-A_B-Pet-29-EPH-072814 | | 124-A_B-Pet-30-052214 | | 124-A_B-Pet-30a-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB67718-14 | | JB67718-15 | | JB72707-2 | | JB67718-3A | | JB67718-16 | | JB67718-17 | | JB67718-18 | | JB67718-19 | | JB72707-3 | | JB67718-4A | | JB67718-20 | |
| Date Sampled | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | | 05/22/2014 | | 05/22/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | 6.9 | U | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | 88.7 | | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | 6.9 | U | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | 133 | | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | 54.7 | | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | 97.3 | | - | | - | | - | | - | | - | | 23.0 | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | 369 | | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| Total EPH (C9-C40) | mg/kg | - | | - | | 768 | | - | | - | | - | | - | | - | | 23.0 | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 286 | | 257 | | - | | 299 | | 223 | | 228 | | 134 | | 155 | | - | | 119 | | 583 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | 616 | | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | 152 | | - | | - | | - | | - | | - | | 23.0 | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | 25.6 | | - | | - | | - | | - | | - | | 5.9 | U | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-30b-052214 | | 124-A_B-Pet-30c-052214 | | 124-A_B-Pet-30d-052214 | | 124-A_B-Pet-30-EPH-072814 | | 124-A_B-Pet-31-052214 | | 124-A_B-Pet-31a-052214 | | 124-A_B-Pet-31b-052214 | | 124-A_B-Pet-31c-052214 | | 124-A_B-Pet-31d-052214 | | 124-A_B-Pet-31-EPH-072814 | | 124-A_B-Pet-32-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB67718-21 | | JB67718-22 | | JB67718-23 | | JB72707-4 | | JB67718-5A | | JB67718-24 | | JB67718-25 | | JB67718-26 | | JB67718-27 | | JB72707-5 | | JB67718-6A | |
| | | Date Sampled | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | | 05/22/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 5.8 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | 71.3 | | - | | - | | - | | - | | - | | 44.5 | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 5.8 | U | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | 79.9 | | - | | - | | - | | - | | - | | 48.3 | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | 28.1 | | - | | - | | - | | - | | - | | 5.8 | U | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | 22.0 | | - | | - | | - | | - | | - | | 5.8 | U | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | 55.6 | | - | | - | | - | | - | | - | | 48.9 | | - | |
| Total EPH (C9-C40) | mg/kg | | - | | - | | - | | 282 | | - | | - | | - | | - | | - | | 142 | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | 194 | | 170 | | 194 | | - | | 390 | | 470 | | 641 | | 946 | | 371 | | - | | 40.1 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | | - | | - | | - | | 232 | | - | | - | | - | | - | | - | | 142 | | - | |
| Residual Range Organics, Aromatic | mg/kg | | - | | - | | - | | 50.2 | | - | | - | | - | | - | | - | | 5.8 | U | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | - | | - | | - | | 25.5 | | - | | - | | - | | - | | - | | 5.8 | U | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-32a-052214 | | 124-A_B-Pet-32b-052214 | | 124-A_B-Pet-32c-052214 | | 124-A_B-Pet-32d-052214 | | 124-A_B-Pet-32-EPH-072814 | | 124-A_B-Pet-33-052214 | | 124-A_B-Pet-33a-052214 | | 124-A_B-Pet-33b-052214 | | 124-A_B-Pet-33c-052214 | | 124-A_B-Pet-33d-052214 | | 124-A_B-Pet-33-EPH-072814 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB67718-28 | | JB67718-29 | | JB67718-30 | | JB67718-31 | | JB72707-6 | | JB67718-7A | | JB67718-32 | | JB67718-33 | | JB67718-34 | | JB67718-35 | | JB72707-7 | |
| Date Sampled | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 07/28/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 5.7 | U |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 35.7 | | - | | - | | - | | - | | - | | 115 | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 5.7 | U |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 33.7 | | - | | - | | - | | - | | - | | 125 | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 28.6 | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 5.7 | U |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | - | | - | | - | | - | | 54.9 | | - | | - | | - | | - | | - | | 82.7 | |
| Total EPH (C9-C40) | mg/kg | - | | - | | - | | - | | 124 | | - | | - | | - | | - | | - | | 369 | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | 110 | | 48.4 | | 46.0 | | 64.5 | | - | | 770 | | 1160 | | 682 | | 1150 | | 503 | | - | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | - | | - | | - | | - | | 124 | | - | | - | | - | | - | | - | | 341 | |
| Residual Range Organics, Aromatic | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 28.6 | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | - | | - | | - | | - | | 5.6 | U | - | | - | | - | | - | | - | | 17.9 | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-34-060414 | | 124-A_B-Pet-34a-060414 | | 124-A_B-Pet-34b-060414 | | 124-A_B-Pet-34c-060414 | | 124-A_B-Pet-34d-060414 | | 124-A_B-Pet-34-EPH-071014 | | 124-A_B-Pet-35-060414 | | 124-A_B-Pet-35a-060414 | | 124-A_B-Pet-35b-060414 | | 124-A_B-Pet-35c-060414 | | 124-A_B-Pet-35d-060414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB68443-1A | | JB68443-5 | | JB68443-6 | | JB68443-7 | | JB68443-8 | | JB71450-13 | | JB68443-2A | | JB68443-9 | | JB68443-10 | | JB68443-11 | | JB68443-12 | |
| | | Date Sampled | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 07/10/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | 6.91 | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | 169 | | - | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | 23.4 | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | 168 | | - | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | 68.1 | | - | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | - | | - | | - | | - | | 36.6 | | - | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | 83.3 | | - | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | | - | | - | | - | | - | | - | | 651 | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | 256 | | 457 | | 423 | | 353 | | 338 | | - | | 774 | | 981 | | 642 | | 812 | | 523 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | | - | | - | | - | | - | | - | | 516 | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | | - | | - | | - | | - | | - | | 135 | | - | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | - | | - | | - | | - | | - | | 95.9 | | - | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | 124-A_B-Pet-35-EPH-071014 | | 124-A_B-Pet-36-060414 | | 124-A_B-Pet-36a-060414 | | 124-A_B-Pet-36b-060414 | | 124-A_B-Pet-36c-060414 | | 124-A_B-Pet-36d-060414 | | 124-A_B-Pet-36-EPH-071014 | | 124-A_B-Pet-37-060414 | | 124-A_B-Pet-37a-060414 | | 124-A_B-Pet-37b-060414 | | 124-A_B-Pet-37c-060414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | JB71450-14 | | JB68443-3A | | JB68443-13 | | JB68443-14 | | JB68443-15 | | JB68443-16 | | JB71450-15 | | JB68443-4A | | JB68443-17 | | JB68443-18 | | JB68443-19 | |
| Date Sampled | | 07/10/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 07/10/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 5.6 | U | - | | - | | - | | - | | - | | 13.2 | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | 107 | | - | | - | | - | | - | | - | | 362 | | - | | - | | - | | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 13.9 | | - | | - | | - | | - | | - | | 57.5 | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | 92.7 | | - | | - | | - | | - | | - | | 312 | | - | | - | | - | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 39.2 | | - | | - | | - | | - | | - | | 126 | | - | | - | | - | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 27.9 | | - | | - | | - | | - | | - | | 40.5 | | - | | - | | - | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | 46.2 | | - | | - | | - | | - | | - | | 109 | | - | | - | | - | | - | |
| Total EPH (C9-C40) | mg/kg | 401 | | - | | - | | - | | - | | - | | 1230 | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | - | | 219 | | 317 | | 290 | | 278 | | 268 | | - | | 373 | | 416 | | 211 | | 272 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | 320 | | - | | - | | - | | - | | - | | 994 | | - | | - | | - | | - | |
| Residual Range Organics, Aromatic | mg/kg | 81.0 | | - | | - | | - | | - | | - | | 237 | | - | | - | | - | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | 73.6 | | - | | - | | - | | - | | - | | 211 | | - | | - | | - | | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | 124-A_B-Pet-37d-060414 | | 124-A_B-Pet-37-EPH-071014 | | 124-A_B-Pet-38-062714 | | 124-A_B-Pet-38-EPH-071814 | | 124-A_B-Pet-39-062714 | | 124-A_B-Pet-39-EPH-071814 | | 124-A_B-Pet-40-062714 | | 124-A_B-Pet-40-EPH-071814 | | 124-A_B-Pet-41-062714 | | 124-A_B-Pet-41-EPH-071814 | | 124-A_B-Pet-42-062714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | JB68443-20 | | JB71450-16 | | JB70484-1A | | JB72047-1 | | JB70484-2A | | JB72047-2 | | JB70484-3A | | JB72047-3 | | JB70484-4A | | JB72047-4 | | JB70484-5A | |
| | | Date Sampled | 06/04/2014 | | 07/10/2014 | | 06/27/2014 | | 07/18/2014 | | 06/27/2014 | | 07/18/2014 | | 06/27/2014 | | 07/18/2014 | | 06/27/2014 | | 07/18/2014 | | 06/27/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | 5.1 | U | - | | 5.9 | U | - | | 5.8 | U | - | | 5.9 | U | - | | 6.4 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | 67.9 | | - | | 5.9 | U | - | | 5.8 | U | - | | 5.9 | U | - | | 6.4 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | 5.40 | | - | | 5.9 | U | - | | 5.8 | U | - | | 5.9 | U | - | | 6.4 | U | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | 87.3 | | - | | 5.9 | U | - | | 5.8 | U | - | | 5.9 | U | - | | 18.4 | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | 29.5 | | - | | 35.6 | | - | | 5.8 | U | - | | 5.9 | U | - | | 31.6 | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | - | | 17.7 | | - | | 77.2 | | - | | 5.8 | U | - | | 21.6 | | - | | 57.6 | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | - | | 67.4 | | - | | 34.2 | | - | | 5.8 | U | - | | 30.3 | | - | | 81.4 | | - | |
| Total EPH (C9-C40) | mg/kg | | - | | 292 | | - | | 147 | | - | | 5.8 | U | - | | 52.0 | | - | | 189 | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | 367 | | - | | 16.3 | | - | | 84.9 | | - | | 99.6 | | - | | 31.6 | | - | | 48.3 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | | - | | 239 | | - | | 34.2 | | - | | 5.8 | U | - | | 30.3 | | - | | 99.8 | | - | |
| Residual Range Organics, Aromatic | mg/kg | | - | | 52.6 | | - | | 113 | | - | | 5.8 | U | - | | 21.6 | | - | | 89.2 | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | - | | 16.9 | | - | | 5.9 | U | - | | 5.8 | U | - | | 5.9 | U | - | | 6.4 | U | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | Client Sample ID | 124-A_B-Pet-42-EPH-071814 | | 124-A_B-Pet-43-081414 | | 124-A_B-Pet-43-081414 | | 124-A_B-Pet-44-081414 | | 124-A_B-Pet-44-081414 | | 124-A_B-Pet-45-081414 | | 124-A_B-Pet-45-081414 | | 124-A_B-Pet-46-081914 | | 124-A_B-Pet-47-090514 | | 124-A_B-Pet-48-090514 | | 124-A_B-Pet-49-090514 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Lab Sample ID | JB72047-5 | | JB74045-1 | | JB74045-1R | | JB74045-2 | | JB74045-2R | | JB74045-3 | | JB74045-3R | | JB74372-1 | | JB75848-1 | | JB75848-2 | | JB75848-3 | |
| | Date Sampled | 07/18/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/19/2014 | | 09/05/2014 | | 09/05/2014 | | 09/05/2014 | |
| **Parameter Name** | **Units** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 5.4 | U | - | | 6 | U | - | | 5.4 | U | - | | 5.6 | U | 16.0 | | 5.8 | U | 5.6 | U | 5.6 | U |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | 5.4 | U | - | | 18.8 | | - | | 5.4 | U | - | | 5.6 | U | 169 | | 5.8 | U | 5.6 | U | 5.6 | U |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 5.4 | U | - | | 6 | U | - | | 5.4 | U | - | | 5.6 | U | 87.3 | | 5.8 | U | 5.6 | U | 5.6 | U |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | 5.4 | U | - | | 30.0 | | - | | 5.4 | U | - | | 5.6 | U | 67.4 | | 5.8 | U | 5.6 | U | 5.6 | U |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 5.4 | U | - | | 15.5 | | - | | 5.4 | U | - | | 5.6 | U | 135 | | 5.8 | U | 5.6 | U | 5.6 | U |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | 5.4 | U | - | | 15.6 | | - | | 5.4 | U | - | | 5.6 | U | 34.7 | | 5.8 | U | 5.6 | U | 5.6 | U |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | 5.4 | U | - | | 29.0 | | - | | 5.4 | U | - | | 5.6 | U | 33.4 | | 5.8 | U | 5.6 | U | 5.6 | U |
| Total EPH (C9-C40) | mg/kg | 5.4 | U | - | | 109 | | - | | 5.4 | U | - | | 5.6 | U | 603 | | 5.8 | U | 5.6 | U | 5.6 | U |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | - | | 145 | | - | | 476 | | - | | 67.0 | | - | | - | | - | | - | | - | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | 5.4 | U | - | | 77.8 | | - | | 5.4 | U | - | | 5.6 | U | 330 | | 5.8 | U | 5.6 | U | 5.6 | U |
| Residual Range Organics, Aromatic | mg/kg | 5.4 | U | - | | 31.1 | | - | | 5.4 | U | - | | 5.6 | U | 273 | | 5.8 | U | 5.6 | U | 5.6 | U |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | 5.4 | U | - | | 6 | U | - | | 5.4 | U | - | | 5.6 | U | 60.7 | | 5.8 | U | 5.6 | U | 5.6 | U |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016
Reviewed by: JD 05/24/2016

# TABLE E

## Petroleum Soil Sample Results – EPH/Petroleum Hydrocarbons

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| | | Client Sample ID | | 124-A_B-Pet-50-102414 | | 124-A_B-Pet-51-102414 | | 124-A_B-Pet-52-102414 | | 124-A_B-Pet-53-102414 | | 124-C-Pet-01-102414 | | 134-SB-604-0627 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Lab Sample ID | | JB80064-1 | | JB80064-2 | | JB80064-3 | | JB80064-4 | | JB80065-1 | | JB70486-1A | |
| | | Date Sampled | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | | 06/27/2014 | |
| **Parameter Name** | **Units** | | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| C10-C12 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 6.6 | U | 5.7 | U | 5.4 | U | 6.4 | U | 6.8 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | | 69.2 | | 45.3 | | 24.3 | | 6.4 | U | 6.8 | U | - | |
| C12-C16 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 23.6 | | 17.2 | | 5.4 | U | 6.4 | U | 6.8 | U | - | |
| C16-C21 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | | 157 | | 55.3 | | 36.6 | | 6.4 | U | 44.8 | | - | |
| C16-C21 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 138 | | 69.9 | | 61.4 | | 6.4 | U | 32.7 | | - | |
| C21-C36 PETROLEUM HYDROCARBONS, AROMATIC | mg/kg | | | 185 | | 67.6 | | 58.8 | | 49.2 | | 124 | | - | |
| C21-C40 PETROLEUM HYDROCARBONS, ALIPHATIC | mg/kg | | | 348 | | 70.9 | | 60.9 | | 123 | | 414 | | - | |
| Total EPH (C9-C40) | mg/kg | | | 921 | | 326 | | 242 | | 172 | | 615 | | - | |
| PETROLEUM HYDROCARBONS C10-C28 | mg/kg | | | - | | - | | - | | - | | - | | 161 | |
| PETROLEUM HYDROCARBONS AS GASOLINE | mg/kg | | | - | | - | | - | | - | | - | | - | |
| Residual Range Organics, Aliphatic | mg/kg | | | 574 | | 171 | | 122 | | 123 | | 459 | | - | |
| Residual Range Organics, Aromatic | mg/kg | | | 347 | | 155 | | 120 | | 49.2 | | 156 | | - | |
| VOLATILE PETROLEUM HYDROCARBONS C9-C12 ALIPHATIC | mg/kg | | | 6.6 | U | 5.7 | U | 5.4 | U | 6.4 | U | 6.8 | U | - | |

Notes:

EPH: Extractable Petroleum Hydrocarbons

Criterion for EPH is EPH Ecological Concern Criteria of 1700 mg/kg; last amende

Criterion for total petroleum hydrocarbons based on 10,000 mg/kg cap value fo

**Bold and underlined concentrations exceed the Criteria**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JD 05/24/2016

# TABLE F

## Petroleum Soil Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-01-012914 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-02-012914 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-03-012914 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-06-012814 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-08-012814 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB57182-1A | | JB58756-1 | | JB57182-2A | | JB58756-2/2R | | JB58165-1A | | JB58756-3 | | JB58764-1/1A/1T | | JB58764-2/2A/2T | | JB58764-3/3A/3T | | JB58764-4/4A/4T | | JB58764-5/5A/5T | |
| Date Sampled | | | | 01/08/2014 | | 01/29/2014 | | 01/08/2014 | | 01/29/2014 | | 01/20/2014 | | 01/29/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CORROSIVITY | NEG | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CYANIDE | mg/kg | 1600 | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | - | | **28.5** | J | - | | 5.2 | | - | | **68** | J | 14.2 | J | 13.3 | J | **48.3** | J | 18.3 | J | 19.7 | J |
| Ignitability (liquids) Pensky-Martens | NEG | NC | NC | NEG | | - | | NEG | | - | | NEG | | - | | NEG | | NEG | | NEG | | NEG | | NEG | |
| OIL & GREASE, TOTAL REC | mg/kg | NC | NC | 2630 | | - | | 7510 | | - | | 1860 | | - | | 570 | U | 530 | U | 600 | U | 600 | U | 1010 | |
| PAINT FILTER TEST | ml/100g | NC | NC | 0.5 | U | - | | 0.5 | U | - | | 0.5 | U | - | | 2.5 | U | 2.5 | U | 2.5 | U | 2.5 | U | 2.5 | U |
| pH | S.U. | NC | NC | 7.98 | | - | | 8.08 | | - | | 7.92 | | - | | 7.84 | | 8.01 | | 8.19 | | 8.04 | | 8.26 | |
| REACTIVE CYANIDE | mg/kg | NC | NC | 12 | U | - | | 12 | U | - | | 13 | U | - | | 11 | U | 11 | U | 12 | U | 12 | U | 11 | U |
| REACTIVE SULFIDE | mg/kg | NC | NC | 120 | U | - | | 120 | U | - | | 130 | U | - | | 110 | U | 110 | U | 120 | U | 120 | U | 110 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE F

## Petroleum Soil Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-11-022714 | | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-13-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-15-022714 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-19-031214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB58764-6/6A/6T | | JB60759-1/1A/1R | | JB60759-2/2A/2R | | JB60759-3/3A | | JB60759-4/4A/4R | | JB60759-5/5A/5R | | JB60759-6/6A | | JB60759-7/7A/7R | | JB61696-1/1A/1R | | JB61696-2/2A/2R | | JB61696-3/3A | |
| Date Sampled | | | | 01/28/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | |
| Parameter Name | Units | NJ 2012 MOST STRINGENT SRS | NJ 2013 IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| CORROSIVITY | NEG | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CYANIDE | mg/kg | 1600 | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **33.4** | **J** | 15.8 | J | 16 | J | 6.2 | J | 13.2 | J | **21.4** | **J** | 11.1 | J | 15.8 | J | **21.5** | | **25.7** | | **23.2** | |
| Ignitability (liquids) Pensky-Martens | NEG | NC | NC | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | |
| OIL & GREASE, TOTAL REC | mg/kg | NC | NC | 2250 | | 1200 | U | 1250 | | 2070 | | 1200 | U | 1200 | U | 1300 | U | 1100 | U | 1050 | | 939 | | 1280 | |
| PAINT FILTER TEST | ml/100g | NC | NC | 2.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| pH | S.U. | NC | NC | 8.03 | | 7.64 | | 7.62 | | 8.10 | | 8.22 | | 7.95 | | 8.33 | | 7.84 | | | | 7.96 | | 7.96 | |
| REACTIVE CYANIDE | mg/kg | NC | NC | 12 | U | 12 | U | 12 | U | 12 | U | 12 | U | 13 | U | 14 | U | 12 | U | 11 | U | 12 | U | 12 | U |
| REACTIVE SULFIDE | mg/kg | NC | NC | 120 | U | 120 | U | 120 | U | 120 | U | 120 | U | 130 | U | 140 | U | 120 | U | 110 | U | 120 | U | 120 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE F

## Petroleum Soil Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-22-031414 | | 124-A_B-Pet-23-031414 | | 124-A_B-Pet-24-031414 | | 124-A_B-Pet-25-042214 | | 124-A_B-Pet-26-042214 | | 124-A_B-Pet-27-052214 | | 124-A_B-Pet-28-052214 | | 124-A_B-Pet-29-052214 | | 124-A_B-Pet-30-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB61696-4/4A/4R | | JB62045-1/1A | | JB62045-2/2A | | JB62045-3/3A | | JB62045-4/4A | | JB65312-1/1B | | JB65312-2/2B/2R | | JB67718-1/1A/1AB | | JB67718-2/2A/2AB | | JB67718-3/3A/3AB | | JB67718-4/4A/4AB | |
| Date Sampled | | | | 03/12/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 03/14/2014 | | 04/22/2014 | | 04/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CORROSIVITY | NEG | NC | NC | - | | - | | - | | - | | - | | - | | - | | NEG | | NEG | | NEG | | NEG | |
| CYANIDE | mg/kg | 1600 | 20 | - | | - | | - | | - | | - | | - | | - | | 0.25 | U | 0.25 | U | 0.24 | U | 0.24 | U |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | 13.4 | | **29.3** | J | **40.3** | J | **60.4** | J | **36.2** | J | 4.7 | | 17.4 | | 13.1 | | 14.0 | | 11.3 | | 7.9 | |
| Ignitability (liquids) Pensky-Martens | NEG | NC | NC | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | |
| OIL & GREASE, TOTAL REC | mg/kg | NC | NC | 550 | U | 1830 | | 1200 | U | 1540 | | 2640 | | 1450 | | 1240 | | - | | - | | - | | - | |
| PAINT FILTER TEST | ml/100g | NC | NC | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| pH | S.U. | NC | NC | 7.97 | | 8.38 | | 8.10 | | 7.80 | | 7.78 | | 7.34 | | 8.38 | | 8.06 | | 8.05 | | 8.00 | | 7.97 | |
| REACTIVE CYANIDE | mg/kg | NC | NC | 11 | U | 11 | U | 12 | U | 12 | U | 12 | U | 12 | U | 12 | U | 11 | U | 11 | U | 11 | U | 11 | U |
| REACTIVE SULFIDE | mg/kg | NC | NC | 110 | U | 110 | U | 120 | U | 120 | U | 120 | U | 120 | U | 120 | U | 110 | U | 110 | U | 110 | U | 110 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE F

## Petroleum Soil Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-31-052214 | | 124-A_B-Pet-32-052214 | | 124-A_B-Pet-33-052214 | | 124-A_B-Pet-34-060414 | | 124-A_B-Pet-35-060414 | | 124-A_B-Pet-36-060414 | | 124-A_B-Pet-37-060414 | | 124-A_B-Pet-38-062714 | | 124-A_B-Pet-39-062714 | | 124-A_B-Pet-40-062714 | | 124-A_B-Pet-41-062714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB67718-5/5A/5AB | | JB67718-6/6A/6AB | | JB67718-7/7A/7AB/7R | | JB68443-1/1A/1AB | | JB68443-2/2A/2AB | | JB68443-3/3A/3AB/3R | | JB68443-4/4A/4AB/4R | | JB70484-1/1R | | JB70484-2/2R | | JB70484-3/3R | | JB70484-4 | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | | 06/27/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| CORROSIVITY | NEG | NC | NC | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | - | | - | | - | | - | |
| CYANIDE | mg/kg | 1600 | 20 | 0.24 | U | 0.23 | U | 0.23 | U | 0.21 | U | 0.25 | U | 0.25 | U | 0.22 | U | - | | - | | - | | - | |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | 10.0 | | 10.3 | | 2.5 | | **21.6** | | **38.2** | | **29.8** | | **42.5** | | **21.7** | | **24.5** | | **62.2** | | 16.4 | |
| Ignitability (liquids) Pensky-Martens | NEG | NC | NC | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | NEG | | - | | - | | - | | - | |
| OIL & GREASE, TOTAL REC | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PAINT FILTER TEST | ml/100g | NC | NC | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | - | | - | | - | | - | |
| pH | S.U. | NC | NC | 8.27 | | 8.31 | | 8.16 | | 8.43 | | 8.13 | | 8.74 | | 8.18 | | - | | - | | - | | - | |
| REACTIVE CYANIDE | mg/kg | NC | NC | 12 | U | 11 | U | 11 | U | 11 | U | 11 | U | 11 | U | 11 | U | - | | - | | - | | - | |
| REACTIVE SULFIDE | mg/kg | NC | NC | 120 | U | 110 | U | 110 | U | 110 | U | 110 | U | 110 | U | 110 | U | - | | - | | - | | - | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE F

## Petroleum Soil Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-42-062714 | | 124-A_B-Pet-43-081414 | | 124-A_B-Pet-44-081414 | | 124-A_B-Pet-45-081414 | | 124-A_B-Pet-46-081914 | | 124-A_B-Pet-47-090514 | | 124-A_B-Pet-48-090514 | | 124-A_B-Pet-49-090514 | | 124-A_B-Pet-50-102414 | | 124-A_B-Pet-51-102414 | | 124-A_B-Pet-52-102414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB70484-5/5R | | JB74045-1 | | JB74045-2 | | JB74045-3 | | JB74372-1 | | JB75848-1 | | JB75848-2 | | JB75848-3 | | JB80064-1/1R | | JB80064-2/2R | | JB80064-3/3R | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 06/27/2014 | | 08/14/2014 | | 08/14/2014 | | 08/14/2014 | | 08/19/2014 | | 09/05/2014 | | 09/05/2014 | | 09/05/2014 | | 10/24/2014 | | 10/24/2014 | | 10/24/2014 | |
| Parameter Name | Units | STRINGENT SRS | IGW SOIL | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q | CONC | Q |
| CORROSIVITY | NEG | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CYANIDE | mg/kg | 1600 | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **55.1** | | **36.6** | | **20.4** | | **20.8** | | **45.7** | | 9.8 | | 9.3 | | 4.9 | | 16.6 | | **45.0** | | **37.1** | |
| Ignitability (liquids) Pensky-Martens | NEG | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| OIL & GREASE, TOTAL REC | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PAINT FILTER TEST | ml/100g | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| pH | S.U. | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| REACTIVE CYANIDE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| REACTIVE SULFIDE | mg/kg | NC | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE F

## Petroleum Soil Sample Results – General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-A_B-Pet-53-102414 | | 124-C-Pet-01-102414 | | 134-SB-604-0627 | |
|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | | JB80064-4 | | JB80065-1 | | JB70486-1/1A/1AB/1R | |
| Date Sampled | | NJ 2012 MOST | NJ 2013 | 10/24/2014 | | 10/24/2014 | | 06/27/2014 | |
| **Parameter Name** | **Units** | **STRINGENT SRS** | **IGW SOIL** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| CORROSIVITY | NEG | NC | NC | - | | - | | NEG | |
| CYANIDE | mg/kg | 1600 | 20 | - | | - | | 0.26 | U |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | **40.6** | | 9.2 | | **25.3** | |
| Ignitability (liquids) Pensky-Martens | NEG | NC | NC | - | | - | | NEG | |
| OIL & GREASE, TOTAL REC | mg/kg | NC | NC | - | | - | | - | |
| PAINT FILTER TEST | ml/100g | NC | NC | - | | - | | 1.5 | U |
| pH | S.U. | NC | NC | - | | - | | 7.75 | |
| REACTIVE CYANIDE | mg/kg | NC | NC | - | | - | | 12 | U |
| REACTIVE SULFIDE | mg/kg | NC | NC | - | | - | | 120 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE G

## Petroleum Soil Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | RCRA Toxicity Characteristics (40 CFR261.24) | 124-A_B-Pet-01-010814 | | 124-A_B-Pet-02-010814 | | 124-A_B-Pet-03-012014 | | 124-A_B-Pet-04-012814 | | 124-A_B-Pet-05-012814 | | 124-A_B-Pet-06-012814 | | 124-A_B-Pet-07-012814 | | 124-A_B-Pet-08-012814 | | 124-A_B-Pet-09-012814 | | 124-A_B-Pet-10-022714 | | 124-A_B-Pet-11-022714 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB57182-1A/1B | | JB57182-2A/2B | | JB58165-1A/1B | | JB58764-1A | | JB58764-2A | | JB58764-3A | | JB58764-4A | | JB58764-5A | | JB58764-6A | | JB60759-1A | | JB60759-2A | |
| Date Sampled | | | 01/08/2014 | | 01/08/2014 | | 01/20/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 01/28/2014 | | 02/27/2014 | | 02/27/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | mg/L | 100 | 1 | U | 1.1 | | 1.0 | | 1 | U | 1 | U | 1.1 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CADMIUM | mg/L | 1 | 0.0059 | | 0.005 | U | 0.025 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHROMIUM | mg/L | 5 | 0.056 | | 0.036 | | 0.015 | | 0.080 | | 0.15 | | 0.16 | | 0.056 | | 0.10 | | 0.14 | | 0.49 | | 0.063 | |
| COPPER | mg/L | NC | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| LEAD | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | mg/L | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| NICKEL | mg/L | NC | 0.076 | | 0.11 | | 0.10 | | 0.065 | | 0.096 | | 0.15 | | 0.053 | | 0.046 | | 0.04 | U | 0.073 | | 0.04 | U |
| SELENIUM | mg/L | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | mg/L | 5 | 0.01 | U | 0.03 | U | 0.05 | U | 0.03 | U | 0.03 | U | 0.05 | U | 0.03 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| ZINC | mg/L | NC | 50.3 | J | 76.7 | J | 129 | | 64.0 | | 54.4 | | 134 | | 56.3 | | 95.2 | | 139 | | 272 | J | 112 | J |
| 2,4,5-TP (SILVEX) | mg/L | 1 | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U |
| 2,4-D | mg/L | 10 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | mg/L | 0.03 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| ENDRIN | mg/L | 0.02 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| GAMMA-BHC (LINDANE) | mg/L | 0.4 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| HEPTACHLOR | mg/L | 0.008 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| HEPTACHLOR EPOXIDE | mg/L | NC | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| METHOXYCHLOR | mg/L | 10 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| PENTACHLOROPHENOL | mg/L | 100 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U |
| TOXAPHENE | mg/L | 0.5 | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U |
| CHEMICAL OXYGEN DEMAND | mg/L | NC | 20 | U | 20 | U | 20 | U | - | | - | | - | | - | | - | | - | | - | | - | |
| NITROGEN, AMMONIA (AS N) | mg/L | NC | 0.2 | U | 0.2 | U | 0.2 | U | - | | - | | - | | - | | - | | - | | - | | - | |
| OIL & GREASE, TOTAL REC | mg/L | NC | 5.1 | U | 5.1 | U | 5.1 | U | - | | - | | - | | - | | - | | - | | - | | - | |
| 1,1-DICHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 1,2-DICHLOROETHANE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 1,4-DICHLOROBENZENE | mg/L | 7.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 2-BUTANONE | mg/L | 200 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U |
| BENZENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CARBON TETRACHLORIDE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHLOROBENZENE | mg/L | 100 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHLOROFORM | mg/L | 6 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| TETRACHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| TRICHLOROETHENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| VINYL CHLORIDE | mg/L | 0.2 | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| 2,4,5-TRICHLOROPHENOL | mg/L | 400 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| 2,4,6-TRICHLOROPHENOL | mg/L | 2 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| 2,4-DINITROTOLUENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| 2-METHYLPHENOL | mg/L | 200 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| 3&4-METHYLPHENOL | mg/L | NC | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| HEXACHLOROBENZENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| HEXACHLOROBUTADIENE | mg/L | 0.5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |
| HEXACHLOROETHANE | mg/L | 3 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| NITROBENZENE | mg/L | 2 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| PYRIDINE | mg/L | 5 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |

Notes:

RCRA Toxicity Characteristics (40 CFR261.24)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics (40 CFR261.24)**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

TCLP: Toxicity Characteristic Leaching Procedure



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE G

## Petroleum Soil Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | RCRA Toxicity Characteristics (40 CFR261.24) | 124-A_B-Pet-12-022714 | | 124-A_B-Pet-13-022714 | | 124-A_B-Pet-14-022714 | | 124-A_B-Pet-15-022714 | | 124-A_B-Pet-16-022714 | | 124-A_B-Pet-17-031214 | | 124-A_B-Pet-18-031214 | | 124-A_B-Pet-19-031214 | | 124-A_B-Pet-20-031214 | | 124-A_B-Pet-21-031414 | | 124-A_B-Pet-22-031414 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB60759-3A | | JB60759-4A | | JB60759-5A | | JB60759-6A | | JB60759-7A | | JB61696-1A | | JB61696-2A | | JB61696-3A | | JB61696-4A | | JB62045-1A | | JB62045-2A | |
| Date Sampled | | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 02/27/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/12/2014 | | 03/14/2014 | | 03/14/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | mg/L | 100 | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1.2 | | 1.1 | |
| CADMIUM | mg/L | 1 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.025 | U | 0.01 | U | 0.025 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHROMIUM | mg/L | 5 | 0.054 | | 0.074 | | 0.051 | | 0.046 | | 0.086 | | 0.081 | | 0.14 | | 0.14 | | 0.30 | | 0.061 | | 0.12 | |
| COPPER | mg/L | NC | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| LEAD | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | mg/L | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| NICKEL | mg/L | NC | 0.046 | | 0.047 | | 0.057 | | 0.061 | | 0.057 | | 0.098 | | 0.12 | | 0.072 | | 0.04 | U | 0.30 | | 0.30 | |
| SELENIUM | mg/L | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | mg/L | 5 | 0.01 | U | 0.01 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.02 | U | 0.05 | U | 0.01 | U | 0.01 | U | 0.01 | U |
| ZINC | mg/L | NC | 28 | J | 49.3 | J | 247 | J | 151 | J | 168 | J | 144 | J | 61.4 | J | 159 | J | 22.8 | J | 78.8 | | 33.6 | |
| 2,4,5-TP (SILVEX) | mg/L | 1 | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U |
| 2,4-D | mg/L | 10 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | mg/L | 0.03 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| ENDRIN | mg/L | 0.02 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| GAMMA-BHC (LINDANE) | mg/L | 0.4 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| HEPTACHLOR | mg/L | 0.008 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| HEPTACHLOR EPOXIDE | mg/L | NC | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| METHOXYCHLOR | mg/L | 10 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| PENTACHLOROPHENOL | mg/L | 100 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U |
| TOXAPHENE | mg/L | 0.5 | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U |
| CHEMICAL OXYGEN DEMAND | mg/L | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| NITROGEN, AMMONIA (AS N) | mg/L | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| OIL & GREASE, TOTAL REC | mg/L | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 1,1-DICHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 1,2-DICHLOROETHANE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 1,4-DICHLOROBENZENE | mg/L | 7.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 2-BUTANONE | mg/L | 200 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U |
| BENZENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CARBON TETRACHLORIDE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHLOROBENZENE | mg/L | 100 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHLOROFORM | mg/L | 6 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| TETRACHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| TRICHLOROETHENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| VINYL CHLORIDE | mg/L | 0.2 | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| 2,4,5-TRICHLOROPHENOL | mg/L | 400 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| 2,4,6-TRICHLOROPHENOL | mg/L | 2 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| 2,4-DINITROTOLUENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| 2-METHYLPHENOL | mg/L | 200 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| 3&4-METHYLPHENOL | mg/L | NC | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| HEXACHLOROBENZENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| HEXACHLOROBUTADIENE | mg/L | 0.5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |
| HEXACHLOROETHANE | mg/L | 3 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| NITROBENZENE | mg/L | 2 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| PYRIDINE | mg/L | 5 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |

Notes:

RCRA Toxicity Characteristics (40 CFR261.24)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics (40 CFR261.24)**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

TCLP: Toxicity Characteristic Leaching Procedure



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE G

## Petroleum Soil Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | RCRA Toxicity Characteristics (40 CFR261.24) | 124-A_B-Pet-23-031414 | | 124-A_B-Pet-24-031414 | | 124-A_B-Pet-25-042214 | | 124-A_B-Pet-26-042214 | | 124-A_B-Pet-27-052214 | | 124-A_B-Pet-28-052214 | | 124-A_B-Pet-29-052214 | | 124-A_B-Pet-30-052214 | | 124-A_B-Pet-31-052214 | | 124-A_B-Pet-32-052214 | | 124-A_B-Pet-33-052214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB62045-3A | | JB62045-4A | | JB65312-1B | | JB65312-2B | | JB67718-1AB | | JB67718-2AB | | JB67718-3AB | | JB67718-4AB | | JB67718-5AB | | JB67718-6AB | | JB67718-7AB | |
| Date Sampled | | | 03/14/2014 | | 03/14/2014 | | 04/22/2014 | | 04/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | | 05/22/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | mg/L | 100 | 1.1 | | 1.3 | | 1.6 | | 1.7 | | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CADMIUM | mg/L | 1 | 0.0050 | | 0.0068 | | 0.018 | | 0.0078 | | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHROMIUM | mg/L | 5 | 0.096 | | 0.21 | | 0.41 | | 0.067 | | 0.081 | | 0.066 | | 0.055 | | 0.072 | | 0.044 | | 0.10 | | 0.076 | |
| COPPER | mg/L | NC | 0.025 | U | 0.025 | U | 0.01 | U | 0.01 | U | - | | - | | - | | - | | - | | - | | - | |
| LEAD | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | mg/L | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| NICKEL | mg/L | NC | 0.92 | | 0.53 | | 3.5 | | 0.90 | | - | | - | | - | | - | | - | | - | | - | |
| SELENIUM | mg/L | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | mg/L | 5 | 0.03 | U | 0.05 | U | 0.1 | U | 0.013 | | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |
| ZINC | mg/L | NC | 95.3 | | 155 | | 262 | | 14.1 | | - | | - | | - | | - | | - | | - | | - | |
| 2,4,5-TP (SILVEX) | mg/L | 1 | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U |
| 2,4-D | mg/L | 10 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | mg/L | 0.03 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| ENDRIN | mg/L | 0.02 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| GAMMA-BHC (LINDANE) | mg/L | 0.4 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| HEPTACHLOR | mg/L | 0.008 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| HEPTACHLOR EPOXIDE | mg/L | NC | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U |
| METHOXYCHLOR | mg/L | 10 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| PENTACHLOROPHENOL | mg/L | 100 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U |
| TOXAPHENE | mg/L | 0.5 | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U |
| CHEMICAL OXYGEN DEMAND | mg/L | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| NITROGEN, AMMONIA (AS N) | mg/L | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| OIL & GREASE, TOTAL REC | mg/L | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| 1,1-DICHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 1,2-DICHLOROETHANE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 1,4-DICHLOROBENZENE | mg/L | 7.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| 2-BUTANONE | mg/L | 200 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U |
| BENZENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.0182 | | 0.005 | U |
| CARBON TETRACHLORIDE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHLOROBENZENE | mg/L | 100 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| CHLOROFORM | mg/L | 6 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| TETRACHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U |
| TRICHLOROETHENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.0055 | | 0.005 | U | 0.005 | U | 0.005 | U |
| VINYL CHLORIDE | mg/L | 0.2 | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U |
| 2,4,5-TRICHLOROPHENOL | mg/L | 400 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| 2,4,6-TRICHLOROPHENOL | mg/L | 2 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| 2,4-DINITROTOLUENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| 2-METHYLPHENOL | mg/L | 200 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| 3&4-METHYLPHENOL | mg/L | NC | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| HEXACHLOROBENZENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| HEXACHLOROBUTADIENE | mg/L | 0.5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U |
| HEXACHLOROETHANE | mg/L | 3 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U |
| NITROBENZENE | mg/L | 2 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |
| PYRIDINE | mg/L | 5 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U |

Notes:

RCRA Toxicity Characteristics (40 CFR261.24)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics (40 CFR261.24)**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

TCLP: Toxicity Characteristic Leaching Procedure



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE G

## Petroleum Soil Sample Results – TCLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | RCRA Toxicity Characteristics (40 CFR261.24) | 124-A_B-Pet-34-060414 | | 124-A_B-Pet-35-060414 | | 124-A_B-Pet-36-060414 | | 124-A_B-Pet-37-060414 | | 124-WC-Pet-01-C-111014 | | 124-WC-Pet-50-AB-111014 | | 134-SB-604-0627 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB68443-1AB | | JB68443-2AB | | JB68443-3AB | | JB68443-4AB | | JB81370-2 | | JB81370-1 | | JB70486-1AB | |
| Date Sampled | | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 06/04/2014 | | 11/10/2014 | | 11/10/2014 | | 06/27/2014 | |
| **Parameter Name** | **Units** | | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| BARIUM | mg/L | 100 | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U | 1 | U |
| CADMIUM | mg/L | 1 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | 0.025 | | 0.051 | | 0.005 | U |
| CHROMIUM | mg/L | 5 | 0.056 | | 0.040 | | 0.025 | | 0.049 | | 0.05 | U | 0.81 | | 0.10 | |
| COPPER | mg/L | NC | - | | - | | - | | - | | 0.05 | U | 0.05 | U | 0.01 | U |
| LEAD | mg/L | 5 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| MERCURY | mg/L | 0.2 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U |
| NICKEL | mg/L | NC | - | | - | | - | | - | | 11.5 | | 1.2 | | 0.11 | |
| SELENIUM | mg/L | 1 | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U | 0.5 | U |
| SILVER | mg/L | 5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | 0.05 | U | 0.05 | U | 0.01 | U |
| ZINC | mg/L | NC | - | | - | | - | | - | | 14.6 | | 38.8 | | 12.8 | |
| 2,4,5-TP (SILVEX) | mg/L | 1 | 0.0015 | U | 0.0015 | U | 0.0015 | U | 0.0015 | U | - | | - | | - | |
| 2,4-D | mg/L | 10 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | - | |
| CONSTITUENTS OF CHLORDANE (ALPHA, BETA, AND GAMMA) | mg/L | 0.03 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | - | |
| ENDRIN | mg/L | 0.02 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | - | | - | | - | |
| GAMMA-BHC (LINDANE) | mg/L | 0.4 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | - | | - | | - | |
| HEPTACHLOR | mg/L | 0.008 | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | - | | - | | - | |
| HEPTACHLOR EPOXIDE | mg/L | NC | 0.0001 | U | 0.0001 | U | 0.0001 | U | 0.0001 | U | - | | - | | - | |
| METHOXYCHLOR | mg/L | 10 | 0.0002 | U | 0.0002 | U | 0.0002 | U | 0.0002 | U | - | | - | | - | |
| PENTACHLOROPHENOL | mg/L | 100 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | - | | - | | 0.1 | U |
| TOXAPHENE | mg/L | 0.5 | 0.0025 | U | 0.0025 | U | 0.0025 | U | 0.0025 | U | - | | - | | - | |
| CHEMICAL OXYGEN DEMAND | mg/L | NC | - | | - | | - | | - | | - | | - | | - | |
| NITROGEN, AMMONIA (AS N) | mg/L | NC | - | | - | | - | | - | | - | | - | | - | |
| OIL & GREASE, TOTAL REC | mg/L | NC | - | | - | | - | | - | | - | | - | | - | |
| 1,1-DICHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | 0.005 | U |
| 1,2-DICHLOROETHANE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | 0.005 | U |
| 1,4-DICHLOROBENZENE | mg/L | 7.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | 0.005 | U |
| 2-BUTANONE | mg/L | 200 | 0.1 | U | 0.1 | U | 0.1 | U | 0.1 | U | - | | - | | 0.1 | U |
| BENZENE | mg/L | 0.5 | 0.0191 | | 0.0064 | | 0.0219 | | 0.005 | U | - | | - | | 0.005 | U |
| CARBON TETRACHLORIDE | mg/L | 0.5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | - | | - | | 0.005 | U |
| CHLOROBENZENE | mg/L | 100 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | 0.004 | J |
| CHLOROFORM | mg/L | 6 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | - | | - | | 0.005 | U |
| TETRACHLOROETHENE | mg/L | 0.7 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | 0.0037 | J |
| TRICHLOROETHENE | mg/L | 0.5 | 0.005 | U | 0.005 | U | 0.005 | U | 0.005 | U | - | | - | | 0.005 | U |
| VINYL CHLORIDE | mg/L | 0.2 | 0.025 | U | 0.025 | U | 0.025 | U | 0.025 | U | - | | - | | 0.025 | U |
| 2,4,5-TRICHLOROPHENOL | mg/L | 400 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | - | | - | | 0.05 | U |
| 2,4,6-TRICHLOROPHENOL | mg/L | 2 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | - | | - | | 0.05 | U |
| 2,4-DINITROTOLUENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | - | | - | | 0.02 | U |
| 2-METHYLPHENOL | mg/L | 200 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | - | | - | | 0.02 | U |
| 3&4-METHYLPHENOL | mg/L | NC | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | - | | - | | 0.02 | U |
| HEXACHLOROBENZENE | mg/L | 0.13 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | - | | - | | 0.02 | U |
| HEXACHLOROBUTADIENE | mg/L | 0.5 | 0.01 | U | 0.01 | U | 0.01 | U | 0.01 | U | - | | - | | 0.01 | U |
| HEXACHLOROETHANE | mg/L | 3 | 0.05 | U | 0.05 | U | 0.05 | U | 0.05 | U | - | | - | | 0.05 | U |
| NITROBENZENE | mg/L | 2 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | - | | - | | 0.02 | U |
| PYRIDINE | mg/L | 5 | 0.02 | U | 0.02 | U | 0.02 | U | 0.02 | U | - | | - | | 0.02 | U |

Notes:

RCRA Toxicity Characteristics (40 CFR261.24)

NC: No criterion established

**Bold and shaded concentrations exceed the RCRA Toxicity Characteristics (40 CFR261.24)**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

TCLP: Toxicity Characteristic Leaching Procedure



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE H

## Petroleum Soil Sample Results – SPLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | 124-A_B-Pet-15a-061214 | | 124-A_B-Pet-15b-061214 | | 124-A_B-Pet-15c-061214 | | 124-A_B-Pet-18a-061214 | | 124-A_B-Pet-18b-061214 | | 124-A_B-Pet-18c-061214 | | 124-A_B-Pet-25a-042214 | | 124-A_B-Pet-25b-042214 | | 124-A_B-Pet-25c-042214 | | 124-A_B-Pet-26a-042214 | | 124-A_B-Pet-26b-042214 | | 124-A_B-Pet-26c-042214 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB69164-1 | | JB69164-2 | | JB69164-3 | | JB69166-1 | | JB69166-2 | | JB69166-3 | | 65312-3T | | 65312-4T | | 65312-5T | | 65312-7T | | 65312-8T | | 65312-9T | |
| Date Sampled | | NJ_Default Leachate | 06/12/2014 | | 06/12/2014 | | 06/12/2014 | | 06/12/2014 | | 06/12/2014 | | 06/12/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | | 04/22/2014 | |
| **Parameter Name** | **Units** | **Criteria for Class II GW** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | ug/l | 3 | - | | - | | - | | - | | - | | - | | 3 | U | 3 | U | 3 | U | **11.8** | | **15.8** | | **16.3** | |
| BARIUM | ug/l | 120000 | - | | - | | - | | - | | - | | - | | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U | 1000 | U |
| BERYLLIUM | ug/l | 20 | - | | - | | - | | - | | - | | - | | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U |
| CADMIUM | ug/l | 80 | - | | - | | - | | - | | - | | - | | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U | 5 | U |
| LEAD | ug/l | 100 | - | | - | | - | | - | | - | | - | | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U | 50 | U |
| MERCURY | ug/l | 40 | 0.2 | U | 0.2 | U | 0.2 | U | - | | - | | - | | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U |
| NICKEL | ug/l | 2000 | - | | - | | - | | - | | - | | - | | 570 | | 61.9 | | 413 | | 10 | U | 10 | U | 10 | U |
| ZINC | ug/l | 40000 | - | | - | | - | | - | | - | | - | | 695 | | 20 | U | 20 | U | 21 | | 20 | U | 20 | U |
| ACENAPHTHENE | ug/l | 4200 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ACENAPHTHYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ANTHRACENE | ug/l | 43 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BENZO(A)ANTHRACENE | ug/l | 1 | - | | - | | - | | 1 | U | 1 | U | 1 | U | - | | - | | - | | - | | - | | - | |
| BENZO(A)PYRENE | ug/l | 0.1 | - | | - | | - | | **1** | **U** | **1** | **U** | **1** | **U** | - | | - | | - | | - | | - | | - | |
| BENZO(B)FLUORANTHENE | ug/l | 1 | - | | - | | - | | 1 | U | 1 | U | 1 | U | - | | - | | - | | - | | - | | - | |
| BENZO(G,H,I)PERYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BENZO(K)FLUORANTHENE | ug/l | 0.8 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHRYSENE | ug/l | 2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIBENZO(A,H)ANTHRACENE | ug/l | 0.3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| FLUORANTHENE | ug/l | 210 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| FLUORENE | ug/l | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| INDENO(1,2,3-CD)PYRENE | ug/l | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| NAPHTHALENE | ug/l | 6000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PHENANTHRENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PYRENE | ug/l | 140 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:

NJ_Default Leachate Criteria for Class II Groundwater

NC: No criterion established

**Bold and shaded concentrations exceed the NJ_Default Leachate Criteria for Class II GW**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in micrograms per liter (ug/l)

B: Analyte found in sample and associated blank

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

SPLP: Synthetic Precipitation Leaching Procedure



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

# TABLE H
## Petroleum Soil Sample Results – SPLP
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID | | | 124-A_B-Pet-31a-061214 | | 124-A_B-Pet-31b-061214 | | 124-A_B-Pet-31c-061214 | | 124-A_B-Pet-35a-061914 | | 124-A_B-Pet-35b-061914 | | 124-A_B-Pet-35c-061914 | | 124-A_B-Pet-39a-071114 | | 124-A_B-Pet-39b-071114 | | 124-A_B-Pet-39c-071114 | | 124-A_B-Pet-42a-071114 | | 124-A_B-Pet-42b-071114 | | 124-A_B-Pet-42c-071114 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB69165-1 | | JB69165-2 | | JB69165-3 | | JB69908-1/1R | | JB69908-2/2R | | JB69908-3/3R | | JB71451-1 | | JB71451-2 | | JB71451-3 | | JB71451-4 | | JB71451-5 | | JB71451-6 | |
| Date Sampled | | NJ_Default Leachate | 06/12/2014 | | 06/12/2014 | | 06/12/2014 | | 06/19/2014 | | 06/19/2014 | | 06/19/2014 | | 07/11/2014 | | 07/11/2014 | | 07/11/2014 | | 07/11/2014 | | 07/11/2014 | | 07/11/2014 | |
| **Parameter Name** | **Units** | **Criteria for Class II GW** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | ug/l | 3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | **4.3** | | **3.5** | | 3 | U |
| BARIUM | ug/l | 120000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BERYLLIUM | ug/l | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CADMIUM | ug/l | 80 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| LEAD | ug/l | 100 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 50 | U | 50 | U | 50 | U |
| MERCURY | ug/l | 40 | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | - | | - | | - | |
| NICKEL | ug/l | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ZINC | ug/l | 40000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ACENAPHTHENE | ug/l | 4200 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ACENAPHTHYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ANTHRACENE | ug/l | 43 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BENZO(A)ANTHRACENE | ug/l | 1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BENZO(A)PYRENE | ug/l | 0.1 | - | | - | | - | | 0.1 | U | 0.1 | U | 0.1 | U | - | | - | | - | | 0.1 | U | 0.1 | U | 0.1 | U |
| BENZO(B)FLUORANTHENE | ug/l | 1 | - | | - | | - | | 0.1 | U | 0.1 | U | 0.1 | U | - | | - | | - | | - | | - | | - | |
| BENZO(G,H,I)PERYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BENZO(K)FLUORANTHENE | ug/l | 0.8 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CHRYSENE | ug/l | 2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| DIBENZO(A,H)ANTHRACENE | ug/l | 0.3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| FLUORANTHENE | ug/l | 210 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| FLUORENE | ug/l | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| INDENO(1,2,3-CD)PYRENE | ug/l | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| NAPHTHALENE | ug/l | 6000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PHENANTHRENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| PYRENE | ug/l | 140 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |

Notes:
NJ_Default Leachate Criteria for Class II Groundwater
NC: No criterion established
**Bold and shaded concentrations exceed the NJ_Default Leachate Criteria for Class II GW**
*Italicized values not detected: reporting limit exceeds criteria*
Depths reported in feet below ground surface
CONC: Concentration reported in micrograms per liter (ug/l)
B: Analyte found in sample and associated blank
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit
SPLP: Synthetic Precipitation Leaching Procedure



Prepared by: DP 04/04/2016
Reviewed by: JLD 05/24/2016

# TABLE H
## Petroleum Soil Sample Results – SPLP
Study Area 6 South
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID | | | 124-A_B-Pet-43a-082214 | | 124-A_B-Pet-43b-082214 | | 124-A_B-Pet-43c-082214 | | 124-A_B-Pet-46a-090514 | | 124-A_B-Pet-46b-090514 | | 124-A_B-Pet-46c-090514 | | 124-A_B-Pet-49a-092414 | | 124-A_B-Pet-49b-092414 | | 124-A_B-Pet-49c-092414 | | 124-A_B-Pet-51a-110514 | | 124-A_B-Pet-51b-110514 | | 124-A_B-Pet-51c-110514 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB74771-13 | | JB74771-14 | | JB74771-15 | | JB75849-1 | | JB75849-2 | | JB75849-3 | | JB77562-1 | | JB77562-2 | | JB77562-3 | | JB80971-1 | | JB80971-2 | | JB80971-3 | |
| Date Sampled | | NJ_Default Leachate | 08/22/2014 | | 08/22/2014 | | 08/22/2014 | | 09/05/2014 | | 09/05/2014 | | 09/05/2014 | | 09/24/2014 | | 09/24/2014 | | 09/24/2014 | | 11/05/2014 | | 11/05/2014 | | 11/05/2014 | |
| **Parameter Name** | **Units** | **Criteria for Class II GW** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | ug/l | 3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BARIUM | ug/l | 120000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| BERYLLIUM | ug/l | 20 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| CADMIUM | ug/l | 80 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| LEAD | ug/l | 100 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| MERCURY | ug/l | 40 | - | | - | | - | | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | - | | - | | - | |
| NICKEL | ug/l | 2000 | 10 | U | 10 | U | 10 | U | - | | - | | - | | 10 | U | 10 | U | 10 | U | - | | - | | - | |
| ZINC | ug/l | 40000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | | - | |
| ACENAPHTHENE | ug/l | 4200 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.131 | | 0.367 | | 0.410 | |
| ACENAPHTHYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.13 | U | 0.162 | |
| ANTHRACENE | ug/l | 43 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.206 | | 0.381 | | 0.278 | |
| BENZO(A)ANTHRACENE | ug/l | 1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.181 | | 0.11 | U |
| BENZO(A)PYRENE | ug/l | 0.1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | **0.13** | **U** | **0.11** | **U** |
| BENZO(B)FLUORANTHENE | ug/l | 1 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.13 | U | 0.11 | U |
| BENZO(G,H,I)PERYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.13 | U | 0.11 | U |
| BENZO(K)FLUORANTHENE | ug/l | 0.8 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.13 | U | 0.11 | U |
| CHRYSENE | ug/l | 2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.261 | | 0.11 | U |
| DIBENZO(A,H)ANTHRACENE | ug/l | 0.3 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.13 | U | 0.11 | U |
| FLUORANTHENE | ug/l | 210 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.204 | | 0.373 | | 0.224 | |
| FLUORENE | ug/l | 2000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.196 | | 0.416 | | 0.548 | |
| INDENO(1,2,3-CD)PYRENE | ug/l | 0.2 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.13 | U | 0.11 | U |
| NAPHTHALENE | ug/l | 6000 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.1 | U | 0.172 | | 0.11 | U |
| PHENANTHRENE | ug/l | NC | - | | - | | - | | - | | - | | - | | - | | - | | - | | 1.22 | B | 2.14 | B | 1.71 | |
| PYRENE | ug/l | 140 | - | | - | | - | | - | | - | | - | | - | | - | | - | | 0.488 | | 0.966 | | 0.518 | |

Notes:
NJ_Default Leachate Criteria for Class II Groundwater
NC: No criterion established
**Bold and shaded concentrations exceed the NJ_Default Leachate Criteria for Class II GW**
*Italicized values not detected: reporting limit exceeds criteria*
Depths reported in feet below ground surface
CONC: Concentration reported in micrograms per liter (ug/l)
B: Analyte found in sample and associated blank
Q: Data qualifier assigned by laboratory or data validator
U: Not detected above method detection limit
SPLP: Synthetic Precipitation Leaching Procedure



Prepared by: DP 04/04/2016
Reviewed by: JLD 05/24/2016

# TABLE H

## Petroleum Soil Sample Results – SPLP

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | 124-A_B-Pet-53a-103014 | | 124-A_B-Pet-53b-103014 | | 124-A_B-Pet-53c-103014 | | 134-SB-604a | | 134-SB-604b | | 134-SB-604c | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JB80622-1 | | JB80622-2 | | JB80622-3 | | JB71449-1 | | JB71449-2 | | JB71449-3 | |
| Date Sampled | | NJ_Default Leachate | 10/30/2014 | | 10/30/2014 | | 10/30/2014 | | 07/11/2014 | | 07/11/2014 | | 07/11/2014 | |
| **Parameter Name** | **Units** | **Criteria for Class II GW** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** | **CONC** | **Q** |
| ARSENIC | ug/l | 3 | - | | - | | - | | - | | - | | - | |
| BARIUM | ug/l | 120000 | 200 | U | 200 | U | 200 | U | - | | - | | - | |
| BERYLLIUM | ug/l | 20 | - | | - | | - | | - | | - | | - | |
| CADMIUM | ug/l | 80 | 5 | U | 5 | U | 5 | U | - | | - | | - | |
| LEAD | ug/l | 100 | 50 | U | 50 | U | 50 | U | - | | - | | - | |
| MERCURY | ug/l | 40 | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U | 0.2 | U |
| NICKEL | ug/l | 2000 | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| ZINC | ug/l | 40000 | - | | - | | - | | - | | - | | - | |
| ACENAPHTHENE | ug/l | 4200 | - | | - | | - | | - | | - | | - | |
| ACENAPHTHYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | |
| ANTHRACENE | ug/l | 43 | - | | - | | - | | - | | - | | - | |
| BENZO(A)ANTHRACENE | ug/l | 1 | - | | - | | - | | - | | - | | - | |
| BENZO(A)PYRENE | ug/l | 0.1 | - | | - | | - | | - | | - | | - | |
| BENZO(B)FLUORANTHENE | ug/l | 1 | - | | - | | - | | - | | - | | - | |
| BENZO(G,H,I)PERYLENE | ug/l | NC | - | | - | | - | | - | | - | | - | |
| BENZO(K)FLUORANTHENE | ug/l | 0.8 | - | | - | | - | | - | | - | | - | |
| CHRYSENE | ug/l | 2 | - | | - | | - | | - | | - | | - | |
| DIBENZO(A,H)ANTHRACENE | ug/l | 0.3 | - | | - | | - | | - | | - | | - | |
| FLUORANTHENE | ug/l | 210 | - | | - | | - | | - | | - | | - | |
| FLUORENE | ug/l | 2000 | - | | - | | - | | - | | - | | - | |
| INDENO(1,2,3-CD)PYRENE | ug/l | 0.2 | - | | - | | - | | - | | - | | - | |
| NAPHTHALENE | ug/l | 6000 | - | | - | | - | | - | | - | | - | |
| PHENANTHRENE | ug/l | NC | - | | - | | - | | - | | - | | - | |
| PYRENE | ug/l | 140 | - | | - | | - | | - | | - | | - | |

Notes:

NJ_Default Leachate Criteria for Class II Groundwater

NC: No criterion established

**Bold and shaded concentrations exceed the NJ_Default Leachate Criteria for Class II GW**

*Italicized values not detected: reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in micrograms per liter (ug/l)

B: Analyte found in sample and associated blank

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit

SPLP: Synthetic Precipitation Leaching Procedure



Prepared by: DP 04/04/2016

Reviewed by: JLD 05/24/2016

**APPENDIX J-3**
**QUARTERLY GROUNDWATER SAMPLING**

Honeywell

115 Tabor Road
Morris Plains, NJ 07950

May 16, 2016

***Via Electronic Mail***

The Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Re: Groundwater Sampling Results**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Dear Senator Torricelli:

In accordance with Section 4.0 of the October 2015 draft SA-6 Long Term Monitoring Plan (LTMP), Honeywell is providing the attached brief memorandum of groundwater sampling results prepared by Honeywell's engineering consultant, Amec Foster Wheeler. As we had indicated in our letter dated March 30, 2016, Amec Foster Wheeler implemented this initial round of post-remedial groundwater sampling in the Development AOC during the week of April 4, 2016. A description of the monitoring well installation, the groundwater sampling procedures, and the sample analytical results are provided in the attached memo.

Should you have any questions please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Director, Remediation
Design and Constructionp

WJH:dn/sgf

Encl: 05/16/16 Amec Foster Wheeler Memorandum: Summary of Post-Remedial Shallow Groundwater Sampling, First Quarterly Event, SA-6 South, Sites 073, 124, 125, 134, 140 and 163

cc: (electronic copy only)
Joe Clifford – Amec Foster Wheeler
Michael Daneker – Arnold & Porter LLP
Jeremy Karpatkin – Arnold & Porter LLP
Kim Hosea – Carpenter Environmental Associates, Inc.
Jeremy Farrell – City Hall
Jason Watson – City Hall
Agnieszka Antonian – Connell Foley LLP
Kevin Coakley, Esq. – Connell Foley LLP
Frank Borin – DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella – DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross – Disposal Safety, Inc.
David Isabel – Golub & Isabel PC

Tom Byrne – Honeywell
Maria Kaouris – Honeywell
John Morris – Honeywell
Alicia Clark Alcorn – Terris, Pravlik & Millian, LLP
Kathleen Millian – Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik – Terris, Pravlik & Millian, LLP
Steve Egnaczyk – The Louis Berger Group, Inc.
Thomas Lewis – The Louis Berger Group, Inc.
Liza Walsh – Walsh Pizzi O'Reilly Falanga LLP

# Memo

**Date:** May 16, 2016

**From:** Joe Clifford/Dennis Nagg – Amec Foster Wheeler

**To:** Bill Hague – Honeywell

**cc:** John Morris, Maria Kaouris, John Mojka – Honeywell
Jeremy Karpatkin, Michael Daneker – Arnold & Porter

**Subject:** Summary of Post-Remedial Shallow Groundwater Sampling, First Quarterly Event SA-6 South, Sites 073, 124, 125, 134, 140 and 163

Amec Foster Wheeler E & I (Amec Foster Wheeler), on behalf of Honeywell, has prepared this memorandum to summarize the initial round of post-remedial shallow groundwater sampling activities and analytical results for samples collected in the Development area of concern (AOC) at SA-6 South (Sites 073, 124, 125, 134, 140, and 163) (the Site).

## Introduction

Groundwater sampling is being conducted to evaluate the effectiveness of recently completed remediation of hexavalent chromium (Cr(VI)) impacted soils at the Site pursuant to the draft Long Term Monitoring Plan (LTMP) submitted to all Parties on October 9, 2015. As proposed in the LTMP, quarterly sampling will continue for one year, at which time Honeywell will evaluate the need for continued quarterly monitoring. Depending on the results of the monitoring of any four consecutive quarters, Honeywell may propose a revision to the frequency of monitoring, subject to review and approval by NJDEP, the SA 6 South Consent Decree parties and the Special Master.

The attached **Figure 1**, revised from the Development AOC Shallow Groundwater Monitoring Plan (SGWMP) included as Appendix D of the SA-6 South 100% Design Report, shows all twelve well designations and locations. Well designations are also listed below:

- 073-MW-06;
- 073-MW-07;
- 073-MW-08;

200 American Metro Blvd
Suite 113
Hamilton, NJ 08619
609-689-2829
amecfw.com

- 124-MW-12;
- 124-MW-13;
- 125-MW-02;
- 125-MW-03;
- 134-MW-03;
- 134-MW-04;
- 140-MW-09;
- 140-MW-10; and
- 163-MW-02R

Eleven of the twelve wells were recently installed in February 2016[1]. The first quarter of sampling was conducted on April 6, 7, and 8, 2016.

### Drilling and Groundwater Sampling Procedures

Amec Foster Wheeler's drilling subcontractor, B&B Drilling, mobilized a rotary drill rig to the Site to perform the drilling and install the post-remediation monitoring wells between February 10 and February 23, 2016. Hollow-stem augers were used to advance borings into the subsurface to the target drilling depths. Subsequently, 2-inch diameter, Schedule 40 polyvinyl chloride (PVC), pipe was lowered into the interior of the annulus, to construct the wells. Wells were installed as deep as 20 feet below grade and consist of a screened intervals (0.010" slot size) and solid riser pipe. A sand/gravel filter pack was installed in the borehole annular space and the boring was restored to grade with a cement grout. Constructed wells were then developed utilizing surging and pumping techniques. Monitoring well installation and development work was completed consistent with the NJDEP's "Well Construction and Maintenance, Sealing of Abandoned Wells Rules" (N.J.A.C. 7:9D; NJDEP, 2007) by a New Jersey Licensed driller (B&B Drilling). The post-remediation groundwater monitoring well installation documentation records will be included in the forthcoming final Remedial Action Report.

Prior to sampling, a round of synoptic groundwater level measurements was taken from all wells within the Development AOC. After the synoptic round, samples were collected via low-flow purging/sampling protocols per the NJDEP Field Sampling Procedures Manual and the Data Validation Report (Appendix H of SA-6 North 100% Design Report). Submersible pumps were utilized to extract the water from the wells and all non-dedicated/disposable sampling equipment was decontaminated before and after sampling of each well. Field parameters, including

[1] 163-MW-02R was an existing well installed on September 16, 2011 as a replacement for a previous monitoring well installed in a non-chromium AOC and retained after remediation for post-construction monitoring at Site 163.

temperature, specific conductivity, pH, dissolved oxygen (DO), salinity, turbidity and oxidation-reduction potential (ORP), were measured using a multiparameter water quality meter (Horiba U-52) and recorded during purging. Groundwater Sampling Forms summarizing the field sampling parameters will be provided in the forthcoming final Remedial Action Report.


Once purging was completed, laboratory-provided sample containers with appropriate preservatives were filled. Additionally, a portion of the water obtained from the wells was also field-filtered and placed in sample containers. Once filled, all containers were placed in coolers with ice. The samples were transported to Accutest Laboratories, Inc. of Dayton, New Jersey for analysis under chain of custody. Samples were analyzed for total and hexavalent chromium using USEPA Methods SW846 200.7 and SW846 7199, respectively, in accordance with the SGWMP. Additional analyses included field pH, which was measured in accordance with N.J.A.C 7:18, Subchapter 8, in a portion of the unfiltered water, and oxidation reduction potential.

### Groundwater Sample Analysis and Results

The analytical results for the unfiltered and filtered samples are summarized on the attached **Table 1**. Hexavalent chromium was either at or below the laboratory reporting limit of 5.5 µg/L at all locations, for both unfiltered and filtered samples. Total chromium concentrations in the unfiltered samples were below the NJDEP Groundwater Quality Standard (GWQS) of 70 µg/L at all but two of the twelve locations, with concentrations of 139 µg/L in 134-MW-04 and the highest observed concentration of 216 µg/L in 140-MW-09. However, the filtered data indicates that none of the samples contained total chromium above this standard, with the highest reported concentration being 62 µg/L in 140-MW-09.

**FIGURE 1**

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OF RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| 2 | 02/01/16 | UPDATE WITH NEW WELLS / REMOVE ABANDONED WELLS | STR | DEN |
| 1 | 04/10/13 | ADDED 2 NEW MONITORING WELLS | STR | DEN |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-MWL0-F900

*PREPARED/DATE:* STR 04/20/16

*CHECKED/DATE:* DEN 05/06/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 1**
MONITORING WELL LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\2007\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710-01\CURRENT DRAWINGS\3480150488-5710-MWL0-F900.dwg Tue, 03 May 2016 - 11:18am scott.rudkin Layout: F901

**TABLE 1**

TABLE 1
SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
Study Area 6 South Development AOC
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 073-MW-06-040616 | 073-MW-06-040616-F | 073-MW-07-040616 | 073-MW-07-040616-F | 073-MW-07-040616-DP | 073-MW-07-040616-DPF | 073-MW-08-040716 | 073-MW-08-040716-F | 124-MW-13-040816 | 124-MW-13-040816-F |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID:** | | | **JC17735-1** | **JC17735-1F** | **JC17735-2** | **JC17735-2F** | **JC17735-3** | **JC17735-3F** | **JC17835-1** | **JC17835-1F** | **JC17927-1** | **JC17927-1F** |
| **Date Sampled:** | | | **4/6/2016** | **4/6/2016** | **4/6/2016** | **4/6/2016** | **4/6/2016** | **4/6/2016** | **4/7/2016** | **4/7/2016** | **4/8/2016** | **4/8/2016** |
| **Matrix:** | | | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** |
| **Metals Analysis** | | | | | | | | | | | | |
| Chromium | 70 | ug/l | **13.1** | <10 | **21.8** | <10 | **21.1** | <10 | **25.8** | <10 | **19.2** | <10 |
| **General Chemistry** | | | | | | | | | | | | |
| Chromium, Hexavalent | - | mg/l | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 |

**Footnotes:**
Bold and highlighted values are above the GWQS.

Prepared By: DP 5/3/16
Checked By: JAB 5/3/16

TABLE 1
SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
Study Area 6 South Development AOC
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 124-MW-12-040816 | 124-MW-12-040816-F | 125-MW-02-040816 | 125-MW-02-040816-F | 125-MW-03-040816 | 125-MW-03-040816-F | 134-MW-03-040716 | 134-MW-03-040716-F | 134-MW-04-040716 | 134-MW-04-040716-F | 140-MW-09-040716 | 140-MW-09-040716-F |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID:** | | | **JC17927-2** | **JC17927-2F** | **JC17927-3** | **JC17927-3F** | **JC17927-4** | **JC17927-4F** | **JC17835-4** | **JC17835-4F** | **JC17835-2** | **JC17835-2F** | **JC17835-5** | **JC17835-5F** |
| **Date Sampled:** | | | **4/8/2016** | **4/8/2016** | **4/8/2016** | **4/8/2016** | **4/8/2016** | **4/8/2016** | **4/7/2016** | **4/7/2016** | **4/7/2016** | **4/7/2016** | **4/7/2016** | **4/7/2016** |
| **Matrix:** | | | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** |
| **Metals Analysis** | | | | | | | | | | | | | | |
| Chromium | 70 | ug/l | <10 | <10 | <10 | <10 | <10 | <10 | **11.8** | <10 | **139** | <10 | **216** | **62** |
| **General Chemistry** | | | | | | | | | | | | | | |
| Chromium, Hexavalent | - | mg/l | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0055 |

**Footnotes:**
Bold and highlighted values are above the GWQS

Prepared By: DP 5/3/16
Checked By: JAB 5/3/16

TABLE 1
SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
Study Area 6 South Development AOC
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 140-MW-10-040716 | 140-MW-10-040716-F | 163-MW-02R-040616 | 163-MW-02R-040616 | FB-040616 | FB-040716 | FB-040816 |
|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID:** | | | **JC17835-3** | **JC17835-3F** | **JC17735-4** | **JC17735-4F** | **JC17735-5** | **JC17835-6** | **JC17927-5** |
| **Date Sampled:** | | | **4/7/2016** | **4/7/2016** | **4/6/2016** | **4/6/2016** | **4/6/2016** | **4/7/2016** | **4/8/2016** |
| **Matrix:** | | | **Groundwater Unfiltered** | **Groundwater Filtered** | **Groundwater Unfiltered** | **Groundwater Filtered** | **Field Blank** | **Field Blank** | **Field Blank** |
| | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | |
| Chromium | 70 | ug/l | **63** | <10 | <10 | <10 | <10 | <10 | <10 |
| **General Chemistry** | | | | | | | | | |
| Chromium, Hexavalent | - | mg/l | **0.0055** | <0.0055 | <0.0055 | <0.0055 | <0.0055 | <0.0050 | <0.0055 |

**Footnotes:**
Bold and highlighted values are above the GWQS

Prepared By: DP 5/3/16
Checked By: JAB 5/3/16

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

September 1, 2016 ***via Electronic Mail***

The Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Re: Groundwater Sampling Results**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Dear Senator Torricelli:

In accordance with Section 4.0 of the October 2015 draft SA-6 Long Term Monitoring Plan (LTMP), Honeywell is providing the attached brief memorandum of groundwater sampling results prepared by Honeywell's engineering consultant, Amec Foster Wheeler. Monitoring well installation and the initial round of post-remedial groundwater sampling in the Development AOC was presented in a memo dated May 16, 2016. Amec Foster Wheeler implemented the second quarterly round of post-remedial groundwater sampling in the Development AOC during the week of July 4, 2016. The groundwater sampling procedures and the sample analytical results for this second round are provided in the attached memo.

Should you have any questions please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Director, Remediation
Design and Construction

WJH:dn/sgf

Encl: 09/01/16 Amec Foster Wheeler Memorandum: Summary of Post-Remedial Shallow Groundwater Sampling, Second Quarterly Event, SA-6 South, Sites 073, 124, 125, 134, 140 and 163

cc: (electronic copy only)
Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.

Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP

# Memo

**Date:** September 1, 2016

**From:** Joe Clifford/Dennis Nagg – Amec Foster Wheeler

**To:** Bill Hague – Honeywell

**cc:** John Morris, Maria Kaouris, John Mojka – Honeywell
Jeremy Karpatkin, Michael Daneker – Arnold & Porter

**Subject:** Summary of Post-Remedial Shallow Groundwater Sampling, Second Quarterly Event SA-6 South, Sites 073, 124, 125, 134, 140 and 163

Amec Foster Wheeler E & I (Amec Foster Wheeler), on behalf of Honeywell, has prepared this memorandum to summarize the second round of post-remedial shallow groundwater sampling activities and analytical results for samples collected in the Development area of concern (AOC) at SA-6 South (Sites 073, 124, 125, 134, 140, and 163) (the Site).

## Introduction

Groundwater sampling is being conducted to evaluate the effectiveness of recently completed remediation of hexavalent chromium (Cr(VI)) impacted soils at the Site pursuant to the draft Long Term Monitoring Plan (LTMP) submitted to all Parties on October 9, 2015.

The attached **Figure 1**, revised from the Development AOC Shallow Groundwater Monitoring Plan (SGWMP) included as Appendix D of the SA-6 South 100% Design Report, shows all twelve well designations and locations. Well designations are also listed below:

- 073-MW-06;
- 073-MW-07;
- 073-MW-08;
- 124-MW-12;
- 124-MW-13;
- 125-MW-02;
- 125-MW-03;
- 134-MW-03;

200 American Metro Blvd
Suite 113
Hamilton, NJ 08619
609-689-2829
amecfw.com

- 134-MW-04;
- 140-MW-09;
- 140-MW-10; and
- 163-MW-02R

Eleven of the twelve wells were installed in February 2016[1] with the first quarter of sampling conducted in April 2016. The well installation and first quarter event are described in further detail within Amec Foster Wheeler's May 16, 2016 memo entitled *Summary of Post-Remedial Shallow Groundwater Sampling, First Quarterly Event*. The second quarterly sampling event was conducted on July 5, 6, and 7, 2016 and is detailed herein.

## Groundwater Sampling Procedures

Prior to sampling, a round of synoptic groundwater level measurements was taken from all wells within the Development AOC. After the synoptic round, samples were collected via low-flow purging/sampling protocols per the NJDEP Field Sampling Procedures Manual and the Data Validation Report (Appendix H of SA-6 North 100% Design Report). Submersible pumps were utilized to extract the water from the wells and all non-dedicated/disposable sampling equipment was decontaminated before and after sampling of each well. Field parameters, including temperature, specific conductivity, pH, dissolved oxygen (DO), salinity, turbidity and oxidation-reduction potential (ORP), were measured using a multiparameter water quality meter (Horiba U-52) and recorded during purging. Groundwater Sampling Forms summarizing the field sampling parameters will be provided in the forthcoming final Remedial Action Report.

Once purging was completed, laboratory-provided sample containers with appropriate preservatives were filled. Additionally, a portion of the water obtained from the wells was also field-filtered and placed in sample containers. Once filled, all containers were placed in coolers with ice. The samples were transported to Accutest Laboratories, Inc. of Dayton, New Jersey for analysis under chain of custody. Samples were analyzed for total and hexavalent chromium using USEPA Methods SW846 200.7 and SW846 7199, respectively, in accordance with the SGWMP. Additional analyses included field pH, which was measured in accordance with N.J.A.C 7:18, Subchapter 8, in a portion of the unfiltered water, and oxidation reduction potential.

## Groundwater Sample Analysis and Results


The analytical results for the unfiltered and filtered samples are summarized on the attached **Table 1**. Hexavalent chromium was not detected at any of the locations, for both unfiltered and

[1] 163-MW-02R was an existing well installed on September 16, 2011 as a replacement for a previous monitoring well installed in a non-chromium AOC and retained after remediation for post-construction monitoring at Site 163.

filtered samples.  Total chromium concentrations exceeded the NJDEP Groundwater Quality Standard (GWQS) of 70 µg/L at only two of the twelve locations, with concentrations of 145 µg/L (unfiltered) and 123 µg/L (filtered) in 140-MW-09 and 71.3 µg/L (unfiltered) in 125-MW-03.

**FIGURE 1**

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OF RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| 2 | 02/01/16 | UPDATE WITH NEW WELLS / REMOVE ABANDONED WELLS | STR | DEN |
| 1 | 04/10/13 | ADDED 2 NEW MONITORING WELLS | STR | DEN |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-MWL0-F900

*PREPARED/DATE:* STR 04/20/16

*CHECKED/DATE:* DEN 05/06/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 1**
MONITORING WELL LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\2007\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710-01\CURRENT DRAWINGS\3480150488-5710-MWL0-F900.dwg Tue, 03 May 2016 - 11:18am scott.rudkin Layout: F901

**TABLE 1**

# TABLE 1
# SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 073-MW-06-070616 | | 073-MW-06-0701616F | | 073-MW-07-070516 | | 073-MW-07-070516F | | 073-MW-07-070516DP | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC23489-5 | | JC23489-5F | | JC23431-2 | | JC23431-2F | | JC23431-3 | |
| **Date Sampled:** | | | 07/06/2016 | | 07/06/2016 | | 07/05/2016 | | 07/05/2016 | | 07/05/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 15.1 | | 13.1 | | 16 | |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | UJ | 0.0055 | UJ | 0.0055 | UJ |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A.C 7:9C; last amended 7/20/2010

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 8/15/2016
Checked By: JAB 8/16/2016

# TABLE 1
# SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 073-MW-07-070516DPF | | 073-MW-08-070616 | | 073-MW-08-070616F | | 124-MW-12-070716 | | 124-MW-12-070716F | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC23431-3F | | JC23489-1 | | JC23489-1F | | JC23593-2 | | JC23593-2F | |
| **Date Sampled:** | | | 07/05/2016 | | 07/06/2016 | | 07/06/2016 | | 07/07/2016 | | 07/07/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Filtered | | Unfiltered | | Filtered | | Unfiltered | | Filtered | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 12.1 | | 18.2 | | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | UJ | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 8/15/2016
Checked By: JAB 8/16/2016

# TABLE 1
# SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 124-MW-13-070716 | | 124-MW-13-070716F | | 125-MW-02-070516 | | 125-MW-02-070516F | | 125-MW-03-070716 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC23593-1 | | JC23593-1F | | JC23431-6 | | JC23431-6F | | JC23593-3 | |
| **Date Sampled:** | | | 07/07/2016 | | 07/07/2016 | | 07/05/2016 | | 07/05/2016 | | 07/07/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 10 | U | 10 | U | **71.3** | |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | UJ | 0.0055 | UJ | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 8/15/2016
Checked By: JAB 8/16/2016

# TABLE 1
# SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 125-MW-03-070716F | | 134-MW-03-0701616 | | 134-MW-03-0701616F | | 134-MW-04-0701616 | | 134-MW-04-0701616F | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC23593-3F | | JC23489-2 | | JC23489-2F | | JC23489-3 | | JC23489-3F | |
| **Date Sampled:** | | | 07/07/2016 | | 07/06/2016 | | 07/06/2016 | | 07/06/2016 | | 07/06/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Filtered | | Unfiltered | | Filtered | | Unfiltered | | Filtered | |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 8/15/2016
Checked By: JAB 8/16/2016

# TABLE 1
# SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 140-MW-09-070516 | | 140-MW-09-070516F | | 140-MW-10-070716 | | 140-MW-10-070716F | | 163-MW-02R-070516 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC23431-1 | | JC23431-1F | | JC23593-5 | | JC23593-5F | | JC23431-4 | |
| **Date Sampled:** | | | 07/05/2016 | | 07/05/2016 | | 07/07/2016 | | 07/07/2016 | | 07/05/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **145** | | **123** | | 16.1 | | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | UJ | 0.0055 | UJ | 0.0055 | U | 0.0055 | U | 0.0055 | UJ |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 8/15/2016
Checked By: JAB 8/16/2016

# TABLE 1
# SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 163-MW-02R-070516F | | FB-070516 | | FB-070616 | | FB-070716 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Lab Sample ID | | | JC23431-4F | | JC23431-5 | | JC23489-4 | | JC23593-4 | |
| Date Sampled: | | | 07/05/2016 | | 07/05/2016 | | 07/06/2016 | | 07/07/2016 | |
| Matrix: | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| Filtered: | | | Filtered | | Unfiltered | | Unfiltered | | Unfiltered | |
| | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | UJ | 0.0055 | UJ | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 8/15/2016
Checked By: JAB 8/16/2016

Honeywell

115 Tabor Road
Morris Plains, NJ 07950

November 7, 2016 ***via Electronic Mail***

The Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Re: Initiation of Long Term Groundwater Monitoring**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Dear Senator Torricelli:

In accordance with the September 1, 2016 Revised Draft SA-6 Long Term Monitoring Plan (LTMP) and the Groundwater Level Monitoring Plan (GWLMP) which was Appendix J of the SA-6 North Chromium Remedy 100% Design Report, Honeywell is hereby providing notice to the Parties that we will initiate long-term groundwater monitoring activities at SA-6 South the week of November 14, 2016. While Honeywell acknowledges the LTMP has not been approved as final by the parties, Honeywell will act to meet the requirements of the current draft to move site activities forward. Since the Chromium Remedy at SA-6 South was substantially complete when the geomembrane liner was installed in October 2015, the 12-month "transition period" for groundwater specified in the LTMP and GWLMP ended in October 2016. We have authorized our environmental consultants, Amec Foster Wheeler and Cornerstone, to implement the following general activities at SA-6 South:

- Install data loggers in piezometers,
- Conduct manual water level gauging, and
- Implement quarterly groundwater sampling of the twelve specified monitoring wells in the Development AOC.

Similarly for SA-6 North, we are monitoring the groundwater level recovery following completion of excavation and geomembrane liner installation, and anticipate that the "transition period" will be complete in Spring 2017. At that time, we will initiate long-term monitoring at SA-6 North. The Spring 2017 monitoring will include the inspections associated with the cap vegetation.

In response to Plaintiffs' request to establish baseline groundwater quality conditions inside the Open Space Areas, Amec Foster Wheeler collected filtered and unfiltered groundwater samples from each piezometer on the interior of both Sites. The samples were analyzed for total and hexavalent chromium. A summary of this data is provided in the attached Table 1. The location of the piezometers is shown on the attached Figure 1.

Should the Parties wish to discuss this further, we will be prepared to discuss at the next All Parties meeting on November 15th. Should you have any questions in the meantime, please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:dn/sgf

Encl: Table 1: Summary of SA-6 North and South Interior Piezometer Groundwater Sample Data
Figure 1: SA-6 North and South Contingent Groundwater Extraction Trenches and Sampled Monitoring Well Locations

cc: (electronic copy only)
Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP

**TABLE 1**

**SUMMARY OF SA-6 NORTH & SOUTH INTERIOR PIEZOMETER GROUNDWATER SAMPLE ANALYTICAL RESULTS**
**Study Area 6 North & South**
**Honeywell International Inc.**
**Honeywell International Inc.**

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | Piezometer 087-PZ-02 | | Piezometer 087-PZ-04 | | Piezometer 087-PZ-06 | | Piezometer 087-PZ-08 | | Piezometer 087-PZ-10 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Type: | | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered |
| | Date Sampled: | | 09/06/2016 | 09/06/2016 | 09/06/2016 | 09/06/2016 | 10/14/2016 | 10/14/2016 | 09/02/2016 | 09/02/2016 | 09/02/2016 | 09/02/2016 |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **62.2** | <10 | **10.2** | <10 | **28.4** | <4 | **<10** | <10 | **29** | 12.6 |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | ug/L | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 |


Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS)
N.J.A.C 7:9C; last amended 7/20/2010
DUP: Duplicate Sample
J: Estimated concentration

**TABLE 1**

**SUMMARY OF SA-6 NORTH & SOUTH INTERIOR PIEZOMETER GROUNDWATER SAMPLE ANALYTICAL RESULTS**
**Study Area 6 North & South**
**Honeywell International Inc.**
**Honeywell International Inc.**

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | Piezometer 124-PZ-12 | | Piezometer 124-PZ-14 | | Piezometer 124-PZ-16 | | Piezometer 124-PZ-18 | | Piezometer 124-PZ-20 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Type: | | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered |
| | Date Sampled: | | 09/06/2016 | 09/06/2016 | 09/02/2016 | 09/02/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **24,200** | **23,300** | **37.3** | <10 | **1,720** | **1,690** | **83.7** | <4 | <4 | <4 |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | ug/L | **24,500** | **24,500** | <5.5 | <5.5 | **1,700 J** | **1,900** | <5.5 J | <5.5 | <5.5 J | <5.5 |

Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS)
N.J.A.C 7:9C; last amended 7/20/2010
DUP: Duplicate Sample
J: Estimated concentration




**Legend**

- Piezometer Location
- Existing Monitoring Well Location
- Groundwater Collection Manhole (approx.)
- Standpipe Location
- Perimeter Pool Location (approx.)
- Contingent Groundwater Trenches (approx.)
- Cap Area
- Study Area Boundary

Source:
New Jersey 2012 - 2013 High Resolution Orthophotography, NAD83 NJ State Plane Feet, MrSID Tile; NJ Office of Information Technology (NJOIT), Office of Geographic Information Systems (OGIS); Trenton, NJ; 2013/03.

120 60 0 120 240
SCALE IN FEET

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

*Amec Project No.*
3480130354

*Prepared/Date*
WSL 05/28/2014

*Checked/Date*

# Figure 1
## SA-6 North & South Contingent Groundwater Extraction Trenches and Sampled Monitoring Well Locations
Study Area 6 & Study Area 7
Jersey City, New Jersey

Path: P:\GIS\Projects\Honeywell\Study Area 6\North\20130909_Study Area 6 and 7 Monitoring Well Map\20141023 - Groundwater Extraction Trenches Map.mxd

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

November 30, 2016 ***via Electronic Mail***

The Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Re: Groundwater Sampling Results**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Dear Senator Torricelli:

In accordance with Section 4.0 of the September 2016 Revised Draft SA-6 Long Term Monitoring Plan (LTMP), Honeywell is providing the attached brief memorandum of groundwater sampling results prepared by Honeywell's engineering consultant, Amec Foster Wheeler. Monitoring well installation and the first two rounds of post-remedial groundwater sampling in the Development AOC were presented in memos dated May 16, 2016 and September 1, 2016. Amec Foster Wheeler implemented the third quarterly round of post-remedial groundwater sampling in the Development AOC during the week of October 3, 2016. The groundwater sampling procedures and the sample analytical results for this third round are provided in the attached memo. As mentioned in my email to All Parties on October 13, 2016, Amec Foster Wheeler also filtered the sample from two of the monitoring wells through a smaller filter size (0.1 micron) in addition to the standard filter size (0.45 micron). The objective of the extra filtering was to evaluate whether trivalent chromium detected in the monitoring wells during the previous sampling event is complexing on colloidal particles smaller than the standard 0.45 micron filters.

The analytical data provided in the attached Amec Foster Wheeler memo indicates that the post-remedy groundwater conditions at the SA-6 South Development AOC are now below NJDEP standards in all filtered samples. As indicated in Honeywell's October 13, 2016 email, the presence of total chromium in filtered groundwater samples may be related to trivalent chromium in soils complexing on small particles. The analytical data for the samples filtered through the 0.1 micron filter supports this conclusion. Further, we do not believe that COPR is the source of the total chromium. Instead, we note that the 140-MW-09 well is located within an area of historic fill, thus differences between total chromium and hexavalent chromium may be associated, at least in part, with non-COPR sources of chromium such as historic fill or other historical industries in this part of the site.

Should you have any questions please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:dn/sgf

Encl: 11/30/16 Amec Foster Wheeler Memorandum: Summary of Post-Remedial Shallow Groundwater Sampling, Third Quarterly Event, SA-6 South, Sites 073, 124, 125, 134, 140 and 163

cc: (electronic copy only)
Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP

# Memo

**Date:** November 30, 2016

**From:** Joe Clifford/Dennis Nagg – Amec Foster Wheeler

**To:** Bill Hague – Honeywell

**cc:** John Morris, Maria Kaouris, John Mojka – Honeywell
Jeremy Karpatkin, Michael Daneker – Arnold & Porter

**Subject:** Summary of Post-Remedial Shallow Groundwater Sampling, Third Quarterly Event SA-6 South, Sites 073, 124, 125, 134, 140 and 163

Amec Foster Wheeler E & I (Amec Foster Wheeler), on behalf of Honeywell, has prepared this memorandum to summarize the third round of post-remedial shallow groundwater sampling activities and analytical results for samples collected in the Development area of concern (AOC) at SA-6 South (Sites 073, 124, 125, 134, 140, and 163) (the Site).

## Introduction

Groundwater sampling is being conducted to evaluate the effectiveness of recently completed remediation of hexavalent chromium (Cr(VI)) impacted soils at the Site pursuant to the Revised Draft Long Term Monitoring Plan (LTMP) submitted to all Parties on September 1, 2016.

The attached **Figure 1**, revised from the Development AOC Shallow Groundwater Monitoring Plan (SGWMP) included as Appendix D of the SA-6 South 100% Design Report, shows all twelve well designations and locations. Well designations are also listed below:

- 073-MW-06;
- 073-MW-07;
- 073-MW-08;
- 124-MW-12;
- 124-MW-13;
- 125-MW-02;
- 125-MW-03;
- 134-MW-03;
- 134-MW-04;

200 American Metro Blvd
Suite 113
Hamilton, NJ 08619
609-689-2829
amecfw.com

- 140-MW-09;
- 140-MW-10; and
- 163-MW-02R

Eleven of the twelve wells were installed in February 2016[1] with the first quarter sampling conducted in April 2016 and the second quarter sampling conducted in July 2016. The well installation and first quarter event are described in further detail within Amec Foster Wheeler's May 16, 2016 memo entitled *Summary of Post-Remedial Shallow Groundwater Sampling, First Quarterly Event* and the second quarter event is summarized in Amec Foster Wheeler's September 1, 2016 memo entitled *Summary of Post-Remedial Shallow Groundwater Sampling, Second Quarterly Event*. The third quarterly sampling event was conducted on October 4, 5, and 6, 2016 and is detailed herein.

## Groundwater Sampling Procedures

Prior to sampling, a round of synoptic groundwater level measurements was taken from all wells within the Development AOC. After the synoptic round, samples were collected via low-flow purging/sampling protocols per the NJDEP Field Sampling Procedures Manual and the Data Validation Report (Appendix H of SA-6 North 100% Design Report). Submersible pumps were utilized to extract the water from the wells and all non-dedicated/disposable sampling equipment was decontaminated before and after sampling of each well. Field parameters, including temperature, specific conductivity, pH, dissolved oxygen (DO), salinity, turbidity and oxidation-reduction potential (ORP), were measured using a multiparameter water quality meter (Horiba U-52) and recorded during purging. Groundwater Sampling Forms summarizing the field sampling parameters will be provided in the forthcoming final Remedial Action Report.

Once purging was completed, laboratory-provided sample containers with appropriate preservatives were filled. Additionally, a portion of the water obtained from the wells was also field-filtered, utilizing a 0.45 micron (µ) filter for all wells. For wells 125-MW-03 and 140-MW-09, samples were also filtered through a 0.1 µ filter in addition to the 0.45 µ filter to evaluate whether trivalent chromium is complexing on particles smaller than the standard 0.45 micron filters. After filtering, the samples were placed in sample containers. Once filled, all containers were placed in coolers with ice and samples were transported to Accutest Laboratories, Inc. of Dayton, New Jersey for analysis under chain of custody. Samples were analyzed for total and hexavalent chromium using USEPA Methods SW846 200.7 and SW846 7199, respectively, in accordance with the SGWMP. Additional analyses included field pH, which was measured in accordance with N.J.A.C 7:18, Subchapter 8, in a portion of the unfiltered water, and oxidation reduction potential.


[1] 163-MW-02R was an existing well installed on September 16, 2011 as a replacement for a previous monitoring well installed in a non-chromium AOC and retained after remediation for post-construction monitoring at Site 163.

## Groundwater Sample Analysis and Results

The analytical results for the unfiltered and filtered samples are summarized on the attached **Table 1**. Hexavalent chromium was detected at low levels at only one location, 140-MW-10, with concentrations of 0.011 mg/L and 0.0099 mg/L for unfiltered and filtered samples, respectively. Total chromium concentrations exceeded the NJDEP Groundwater Quality Standard (GWQS) of 70 µg/L at only one of the twelve locations, with concentrations of 184 µg/L (unfiltered) and 134 µg/L (filtered w/ 0.45 µ filter) in 140-MW-09. However the total chromium for this well when sampled through the 0. 1 µ filter was 61.6 ug/L. An email from Honeywell to all Parties, dated October 13, 2016 provided additional explanation of the 140-MW-09 data.

**FIGURE 1**

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OF RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| 2 | 02/01/16 | UPDATE WITH NEW WELLS / REMOVE ABANDONED WELLS | STR | DEN |
| 1 | 04/10/13 | ADDED 2 NEW MONITORING WELLS | STR | DEN |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-MWL0-F900

*PREPARED/DATE:* STR 04/20/16

*CHECKED/DATE:* DEN 05/06/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 1**
MONITORING WELL LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\2007\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710-01\CURRENT DRAWINGS\3480150488-5710-MWL0-F900.dwg Tue, 03 May 2016 - 11:18am scott.rudkin Layout: F901

**TABLE 1**

# TABLE 1
## SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS - October 2016
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 073-MW-06-100516 | | 073-MW-06-100516F | | 073-MW-07-100516 | | 073-MW-07-100516F | | 073-MW-08-100516 | | 073-MW-08-100516F | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC29015-3 | | JC29015-3F | | JC29015-4 | | JC29015-4F | | JC29015-1 | | JC29015-1F | |
| **Date Sampled:** | | | 10/05/2016 | | 10/05/2016 | | 10/05/2016 | | 10/05/2016 | | 10/05/2016 | | 10/05/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | | Filtered | |
| **Metals Analysis** | | | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 24.2 | | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A.C 7:9C; last amended
**Bolded and highlighted concentrations exceed the GWQS**
U: Not detected above method detection limit
J: Estimated concentration



Prepared By: DP 10/31/2016
Checked By: JAB 11/01/2016

# TABLE 1
## SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS - October 2016
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 124-MW-12-100416 | | 124-MW-12-100416F | | 124-MW-13-100416 | | 124-MW-13-100416F | | 125-MW-02-100416 | | 125-MW-02-100416F | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC28915-2 | | JC28915-2F | | JC28915-1 | | JC28915-1F | | JC28915-8 | | JC28915-8F | |
| **Date Sampled:** | | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | | Filtered | |
| **Metals Analysis** | | | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A.C 7:9C; last amended

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 10/31/2016
Checked By: JAB 11/01/2016

# TABLE 1
## SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS - October 2016
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 125-MW-03-100416 | | 125-MW-03-100416DP | | 125-MW-03-100416F | | 125-MW-03-100416FA | | 125-MW-03-100416FADP | | 125-MW-03-100416FDP | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC28915-4 | | JC28915-6 | | JC28915-4F | | JC28915-5F | | JC28915-7F | | JC28915-6F | |
| **Date Sampled:** | | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | | 10/04/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Unfiltered | | Filtered-0.45 µ | | Filtered-0.1 µ | | Filtered | | Filtered | |
| **Metals Analysis** | | | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A.C 7:9C; last amended

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 10/31/2016
Checked By: JAB 11/01/2016

# TABLE 1
## SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS - October 2016
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 134-MW-03-100516 | | 134-MW-03-100516F | | 134-MW-04-100616 | | 134-MW-04-100616F | | 140-MW-09-100616 | | 140-MW-09-100616F | | 140-MW-09-100616FA | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC29015-2 | | JC29015-2F | | JC29084-3 | | JC29084-3F | | JC29084-1 | | JC29084-1F | | JC29084-2F | |
| **Date Sampled:** | | | 10/05/2016 | | 10/05/2016 | | 10/06/2016 | | 10/06/2016 | | 10/06/2016 | | 10/06/2016 | | 10/06/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | | Filtered-0.45 µ | | Filtered-0.1 µ | |
| **Metals Analysis** | | | | | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 31.5 | | 10 | U | 10 | U | 10 | U | **184** | | **134** | | 61.1 | |
| **General Chemistry** | | | | | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A.C 7:9C; last amended

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 10/31/2016
Checked By: JAB 11/01/2016

# TABLE 1
## SUMMARY OF GROUNDWATER SAMPLE ANALYTICAL RESULTS - October 2016
## Study Area 6 South Development AOC
## Honeywell International Inc.
## Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | 140-MW-10-100416 | | 140-MW-10-100416F | | 163-MW-02R-100516 | | 163-MW-02R-100516F | | 125-FB-100416 | | 163-FB-100516 | | 134-FB-100616 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Sample ID** | | | JC28915-3 | | JC28915-3F | | JC29015-5 | | JC29015-5F | | JC28915-9 | | JC29015-6 | | JC29084-4 | |
| **Date Sampled:** | | | 10/04/2016 | | 10/04/2016 | | 10/05/2016 | | 10/05/2016 | | 10/04/2016 | | 10/05/2016 | | 10/06/2016 | |
| **Matrix:** | | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | | Groundwater | |
| **Filtered:** | | | Unfiltered | | Filtered | | Unfiltered | | Filtered | | Unfiltered | | Unfiltered | | Unfiltered | |
| | | | | | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | 10.4 | | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U | 10 | U |
| **General Chemistry** | | | | | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | mg/L | 0.011 | | 0.0099 | | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U | 0.0055 | U |

Notes:

GWQS: NJDEP Ground Water Quality Standards (GWQS), N.J.A.C 7:9C; last amended

**Bolded and highlighted concentrations exceed the GWQS**

U: Not detected above method detection limit

J: Estimated concentration



Prepared By: DP 10/31/2016
Checked By: JAB 11/01/2016

# TABLE 1

## SUMMARY OF SA-6 NORTH & SOUTH INTERIOR PIEZOMETER GROUNDWATER SAMPLE ANALYTICAL RESULTS

Study Area 6 North & South
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | Piezometer 087-PZ-02 | | Piezometer 087-PZ-04 | | Piezometer 087-PZ-06 | | Piezometer 087-PZ-08 | | Piezometer 087-PZ-10 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Type: | | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered |
| | Date Sampled: | | 09/06/2016 | 09/06/2016 | 09/06/2016 | 09/06/2016 | 10/14/2016 | 10/14/2016 | 09/02/2016 | 09/02/2016 | 09/02/2016 | 09/02/2016 |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **62.2** | <10 | **10.2** | <10 | **28.4** | <4 | **<10** | <10 | **29** | 12.6 |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | ug/L | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 |

Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS)
N.J.A.C 7:9C; last amended 7/20/2010
DUP: Duplicate Sample
J: Estimated concentration

# TABLE 1

## SUMMARY OF SA-6 NORTH & SOUTH INTERIOR PIEZOMETER GROUNDWATER SAMPLE ANALYTICAL RESULTS

Study Area 6 North & South
Honeywell International Inc.
Jersey City, New Jersey

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | Piezometer 124-PZ-12 | | Piezometer 124-PZ-14 | | Piezometer 124-PZ-16 | | Piezometer 124-PZ-18 | | Piezometer 124-PZ-20 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Type: | | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered |
| | Date Sampled: | | 09/06/2016 | 09/06/2016 | 09/02/2016 | 09/02/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **24,200** | **23,300** | **37.3** | <10 | **1,720** | **1,690** | **83.7** | <4 | <4 | <4 |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | ug/L | **24,500** | **24,500** | <5.5 | <5.5 | **1,700 J** | **1,900** | <5.5 J | <5.5 | <5.5 J | <5.5 |

Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS)
N.J.A.C 7:9C; last amended 7/20/2010
DUP: Duplicate Sample
J: Estimated concentration

**APPENDIX J-4**
**SITE 073 DEFERRED AREA SAMPLING**

## Site 073 Deferred Area Sampling

The additional soil borings conducted to further investigate hexavalent chromium-impacted soils in the Site 073 deferred area are described in the Sections below. The samples were analyzed for hexavalent chromium as summarized in **Table 6C.**

### Phase I Borings

The Phase I borings were drilled with a hollow stem auger rig. Boring 073-SB-101 was drilled to a depth of 19 feet bgs to evaluate soil conditions below the concrete slab. Boring 073-SB-102 was drilled to a depth of 9 feet bgs to confirm shallow soil observations in boring 073-SB-101 south of the Site 073 20 mg/kg delineation line. The 5-foot thick concrete slab was encountered at boring 073-SB-101, but there was a band of soils containing COPR at 2 to 2.8 feet bgs, sandwiched between a concrete slab above and below at this location. A 3-foot thick concrete slab was observed at boring 073-SB-102, but COPR was not observed in soils underlying the slab to the end of the boring. Thus, samples collected from boring 073-SB-101 were analyzed for hexavalent chromium, but those collected from boring 073-SB-102 were not. The samples confirm conditions in the deferred area based upon RI and PDI sample results.

### Phase II Borings

The Phase II borings were drilled with a Geoprobe® rig. To assess soils as close as possible to the bulkhead, the borings were drilled on a 20º angle (from vertical) starting from a point located as far west as possible given the access constraints of the asphalt/concrete berm located along the river's edge in this area (see Photo 271). The NJ-licensed driller determined that 20º was the maximum angle at which the rig could operate and still advance the tooling/sampling equipment into the ground. Each boring was drilled 24 feet along the drilling axis. At the 20º angle, each boring was completed approximately 7 feet horizontally (west and closer to the bulkhead) of its starting position. By selecting a starting position as close as possible to the berm and angling the borings, samples were collected from soils farther west and closer to the bulkhead than had been collected previously in vertical borings (073-SB-067 through 073-SB-070) conducted during the PDI.

COPR was not observed in any of the Phase II borings. Based upon the analytical results from the previous PDI soil borings, soil samples from the Phase II borings were not collected from the 0 to 2 feet bgs interval. Instead, sampling started at 4 feet bgs and continued until 23 feet (measured along the drilling axis) was reached. Hexavalent chromium concentrations in soils collected from the Phase II angled borings were similar to those from the PDI vertical borings (073-SB-067 through 073-SB-070) in this area.

# APPENDIX J-5
# "ANOMALOUS" MATERIAL SAMPLING

**"Anomalous" Material Sampling**

Additional details regarding activities related to the so-called "anomalous" or "suspect" material observed during excavation activities are described below.

"Anomalous" material was visually identified as potentially chromium-impacted soil at several locations in the excavation sidewall at the previously delineated horizontal extent of the >20 mg/kg hexavalent chromium impacted soils. At such locations, Amec Foster Wheeler collected a sample of the visually-impacted material.

Three locations in the Kellogg Street Development AOC where the "anomalous" material was visually identified included the following locations are as shown on **Figure 11**:

- The southern excavation sidewall on Site 125 behind the 60 Kellogg Street building (Honeywell and Amec Foster Wheeler facility offices); and
- Two locations on the southern excavation sidewall on Site 140.

Post-excavation sidewall samples (125-SB-306, 140-SB-107, and 140-SB-108) were collected at these three locations. Amec Foster Wheeler submitted the post-excavation sidewall samples to Accutest for analysis for hexavalent chromium. **Table 6B** shows that the hexavalent chromium results were <20 mg/kg; therefore, no additional excavation or sampling was required for these three locations.

Another location in the Kellogg Street Development AOC where potentially chromium-impacted soil was observed was in the sidewall and bottom of the western portion of the excavation at Site 134 as shown on **Figure 12**. This portion of the excavation had been following the surface of the Stratum D. The visually anomalous material was a thin lens observed just above the Stratum D. Three samples, 134-SB-160, 134-SB-161, and 134-SB-162, were collected and analyzed by Accutest for hexavalent chromium in the sidewalls of this area as excavation advanced to the west, but each was >20 mg/kg for hexavalent chromium. Additional excavation was conducted to the west to remove the visible material, but eventually Honeywell and Amec Foster Wheeler decided to halt further excavation until the chromium-impacted material (>20 mg/kg for hexavalent chromium) could be delineated. Consequently, supplemental delineation borings, 134-SB-164 through 134-SB-175, were installed west of this initially identified anomaly at the locations shown on **Figure 12**.

The soil borings were conducted using a hollow stem auger drill rig provided by B&B Drilling. Each boring was logged by a representative of Amec Foster Wheeler and the logs

are provided in **Appendix H**. Soil samples were collected from the soil borings at generally the same elevation as the initially identified visual anomalous material and samples 134-SB-160, 134-SB-161, and 134-SB-162, and were analyzed by Accutest for hexavalent chromium.

As seen on **Table 6A**, hexavalent chromium in several samples collected from this area were >20 mg/kg. Thus, step-out soil borings were continued until this area was delineated to <20 mg/kg for hexavalent chromium. Once the limits were established, the excavation was expanded to those limits, and delineation samples that were <20 mg/kg for hexavalent chromium became the final sidewall samples. The southern extent of the expanded excavation area was not accessible for a soil boring due to an adjacent soil stockpile at the time delineation drilling was occurring. The stockpile was moved after the drill rig was demobilized and the excavation commenced to expand this anomalous area, so a post-excavation sidewall sample, 134-SB-177 was collected once the excavation was expanded to the south and this location was visually checked and confirmed that there was no visibly anomalous material in this area.

The material was handled similar to other SA-6 South excavated materials, in that it was segregated based upon its designation (A, B, C, or D) according to hexavalent chromium concentrations.

During excavation at Site 073 in the Kellogg Street Development AOC, a potentially chromium-impacted 1-foot thick concrete slab was observed lying immediately below the ground surface at approximately 1 to 2 feet bgs at the location shown on **Figure 13**. The stained side of the concrete slab was in contact with underlying soils. The stained concrete was broken up and removed for subsequent offsite disposal with D Material. Two post-excavation sidewall samples (073-SB-079 and 073-SB-080) were then collected from approximately 3 feet deep from the soils underlying the stained concrete and analyzed for hexavalent chromium. The hexavalent chromium results are shown on **Table 6B** and indicate that soils underlying the stained concrete at sample location 073-SB-079 were not chromium-impacted (<20 mg/kg for hexavalent chromium) and those at 073-SB-080 were chromium-impacted (>20 mg/kg for hexavalent chromium). Therefore, step-out soil borings were conducted with a Geoprobe® drill rig east of the 073-SB-080 sidewall sample location to 3.25 feet bgs. A soil sample collected from approximately 3 feet deep at the furthest step-out soil boring, 073-SB-082, was analyzed for hexavalent chromium. The results confirmed that soil at the 073-SB-082 location was not chromium-impacted (<20 mg/kg for hexavalent chromium). Thus, the excavation was expanded to the east approximately 4 feet to the 073-SB-082 soil boring sample location as shown on **Figure 13.**

**Suspect Material at Site 125 under 60 Kellogg Street Building Slab**

The suspect material observed in shallow soils within the 60 Kellogg Street building footprint during the demolition activities on April 29, 2016 was investigated and excavated. Initially, the excavation was completed to approximately 10 feet by 10 feet in size in accordance with the approach identified in the May 17, 2016 submittal. The bottom and sides of the excavation at the final limits were visually inspected by Amec personnel. Whitish discoloration was observed in several sidewall locations. The excavation was subsequently extended to approximately 14 feet by 14 feet to remove additional soil until no further discolorations were observed. The depth of excavation varied from approximately 2.9 feet to 4.2 feet bgs.

Once the final limits were reached and the whitish material observed in the sidewalls was determined, based upon previous observances and analysis of samples of such material, to most likely be un-impacted material, one post-excavation soil samples were collected from each sidewall and one post-excavation soil sample from the bottom of the excavation. This sampling frequency meets the approved frequencies established in the SA-6 South 100% Design Report.

# APPENDIX L

# BACKFILL DOCUMENTATION

# Imported Fill (NJCU) Soil Analytical Report

## VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| 1,1,1-TRICHLOROETHANE | mg/kg | 290 | 0.3 | 0.0038 | U |
| 1,1,2,2-TETRACHLOROETHANE | mg/kg | 1 | 0.007 | 0.0038 | U |
| 1,1,2-Trichloro-1,2,2-Trifluoroethane | mg/kg | NC | NC | 0.0096 | U |
| 1,1,2-TRICHLOROETHANE | mg/kg | 2 | 0.02 | 0.0038 | U |
| 1,1-DICHLOROETHANE | mg/kg | 8 | 0.2 | 0.0019 | U |
| 1,1-DICHLOROETHENE | mg/kg | 11 | 0.008 | 0.0019 | U |
| 1,2,3-TRICHLOROBENZENE | mg/kg | NC | NC | 0.0096 | U |
| 1,2,4-TRICHLOROBENZENE | mg/kg | 73 | 0.7 | 0.0096 | U |
| 1,2-DIBROMO-3-CHLOROPROPANE | mg/kg | 0.08 | 0.005 | *0.0096* | *U* |
| 1,2-DIBROMOETHANE | mg/kg | 0.008 | 0.005 | 0.0019 | U |
| 1,2-DICHLOROBENZENE | mg/kg | 5300 | 17 | 0.0019 | U |
| 1,2-DICHLOROETHANE | mg/kg | 0.9 | 0.005 | 0.0019 | U |
| 1,2-DICHLOROPROPANE | mg/kg | 2 | 0.005 | 0.0038 | U |
| 1,3-DICHLOROBENZENE | mg/kg | 5300 | 19 | 0.0019 | U |
| 1,4-DICHLOROBENZENE | mg/kg | 5 | 2 | 0.0019 | U |
| 2-BUTANONE | mg/kg | 3100 | 0.9 | 0.019 | U |
| 2-HEXANONE | mg/kg | NC | NC | 0.0096 | U |
| 4-METHYL-2-PENTANONE | mg/kg | NC | NC | 0.0096 | U |
| ACETONE | mg/kg | 70000 | 19 | 0.0165 | J |
| BENZENE | mg/kg | 2 | 0.005 | 0.00096 | U |
| BROMOCHLOROMETHANE | mg/kg | NC | NC | 0.0096 | U |
| BROMODICHLOROMETHANE | mg/kg | 1 | 0.005 | 0.0038 | U |
| BROMOFORM | mg/kg | 81 | 0.03 | 0.0096 | U |
| BROMOMETHANE | mg/kg | 25 | 0.04 | 0.0096 | U |
| CARBON DISULFIDE | mg/kg | 7800 | 6 | 0.0038 | U |
| CARBON TETRACHLORIDE | mg/kg | 0.6 | 0.005 | 0.0038 | U |
| CHLOROBENZENE | mg/kg | 510 | 0.6 | 0.0038 | U |
| CHLOROETHANE | mg/kg | 220 | NC | 0.0096 | U |
| CHLOROFORM | mg/kg | 0.6 | 0.4 | 0.0038 | U |
| CHLOROMETHANE | mg/kg | 4 | NC | 0.0096 | U |
| CIS-1,2-DICHLOROETHENE | mg/kg | 230 | 0.3 | 0.0019 | U |
| CIS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0038 | U |
| CYCLOHEXANE | mg/kg | NC | NC | 0.0038 | U |
| Dibromochloromethane | mg/kg | 3 | 0.005 | 0.0038 | U |
| DICHLORODIFLUOROMETHANE | mg/kg | 490 | 39 | 0.0096 | U |
| ETHYLBENZENE | mg/kg | 7800 | 13 | 0.0019 | U |
| ISOPROPYLBENZENE | mg/kg | NC | NC | 0.0096 | U |
| METHYL ACETATE | mg/kg | 78000 | 22 | 0.0096 | U |
| METHYL TERT-BUTYL ETHER | mg/kg | 110 | 0.2 | 0.0019 | U |
| METHYLCYCLOHEXANE | mg/kg | NC | NC | 0.0038 | U |
| METHYLENE CHLORIDE | mg/kg | 34 | 0.01 | 0.0096 | U |
| O-XYLENE | mg/kg | NC | NC | 0.0019 | U |
| STYRENE | mg/kg | 90 | 3 | 0.0038 | U |
| TETRACHLOROETHENE | mg/kg | 2 | 0.005 | 0.0019 | U |
| TOLUENE | mg/kg | 6300 | 7 | 0.0019 | U |
| TRANS-1,2-DICHLOROETHENE | mg/kg | 300 | 0.6 | 0.0019 | U |
| TRANS-1,3-DICHLOROPROPENE | mg/kg | NC | NC | 0.0038 | U |
| TRICHLOROETHENE | mg/kg | 7 | 0.01 | 0.0019 | U |
| TRICHLOROFLUOROMETHANE | mg/kg | 23000 | 34 | 0.0096 | U |
| VINYL CHLORIDE | mg/kg | 0.7 | 0.005 | 0.0038 | U |



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Imported Fill (NJCU) Soil Analytical Report

## VOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| XYLENES, M & P | mg/kg | NC | NC | 0.0019 | U |
| XYLENES, TOTAL | mg/kg | 12000 | 19 | 0.0019 | U |
| TOTAL TICS, ALKANES | mg/kg | NC | NC | 0.0000 | |
| TOTAL TICS, VOLATILES | mg/kg | NC | NC | 0.0000 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Imported Fill (NJCU) Soil Analytical Report

## SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| 1,1'-BIPHENYL | mg/kg | 3100 | 140 | 0.078 | U |
| 1,2,4,5-TETRACHLOROBENZENE | mg/kg | NC | NC | 0.2 | U |
| 1,4-DIOXANE | mg/kg | NC | NC | 0.039 | U |
| 2,2'-OXYBIS(1-CHLOROPROPANE) | mg/kg | 23 | 5 | 0.078 | U |
| 2,3,4,6-TETRACHLOROPHENOL | mg/kg | NC | NC | 0.2 | U |
| 2,4,5-TRICHLOROPHENOL | mg/kg | 6100 | 68 | 0.2 | U |
| 2,4,6-TRICHLOROPHENOL | mg/kg | 19 | 0.2 | 0.2 | U |
| 2,4-DICHLOROPHENOL | mg/kg | 180 | 0.2 | 0.2 | U |
| 2,4-DIMETHYLPHENOL | mg/kg | 1200 | 1 | 0.2 | U |
| 2,4-DINITROPHENOL | mg/kg | 120 | 0.3 | *0.78* | *U* |
| 2,4-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.039 | U |
| 2,6-DINITROTOLUENE | mg/kg | 0.7 | NC | 0.039 | U |
| 2-CHLORONAPHTHALENE | mg/kg | NC | NC | 0.078 | U |
| 2-CHLOROPHENOL | mg/kg | 310 | 0.8 | 0.078 | U |
| 2-METHYLNAPHTHALENE | mg/kg | 230 | 8 | 0.078 | U |
| 2-METHYLPHENOL | mg/kg | 310 | NC | 0.078 | U |
| 2-NITROANILINE | mg/kg | 39 | NC | 0.2 | U |
| 2-NITROPHENOL | mg/kg | NC | NC | 0.2 | U |
| 3&4-METHYLPHENOL | mg/kg | NC | NC | 0.078 | U |
| 3,3'-DICHLOROBENZIDINE | mg/kg | 1 | 0.2 | 0.078 | U |
| 3-NITROANILINE | mg/kg | NC | NC | 0.2 | U |
| 4,6-DINITRO-2-METHYLPHENOL | mg/kg | 6 | 0.3 | *0.78* | *U* |
| 4-BROMOPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.078 | U |
| 4-CHLORO-3-METHYLPHENOL | mg/kg | NC | NC | 0.2 | U |
| 4-CHLOROANILINE | mg/kg | NC | NC | 0.2 | U |
| 4-CHLOROPHENYL PHENYL ETHER | mg/kg | NC | NC | 0.078 | U |
| 4-NITROANILINE | mg/kg | NC | NC | 0.2 | U |
| 4-NITROPHENOL | mg/kg | NC | NC | 0.39 | U |
| ACENAPHTHENE | mg/kg | 3400 | 110 | 0.039 | U |
| ACENAPHTHYLENE | mg/kg | 300000 | NC | 0.039 | U |
| ACETOPHENONE | mg/kg | 2 | 3 | 0.2 | U |
| ANTHRACENE | mg/kg | 17000 | 2400 | 0.039 | U |
| ATRAZINE | mg/kg | 210 | 0.2 | 0.078 | U |
| BENZALDEHYDE | mg/kg | 6100 | NC | 0.2 | U |
| BENZO(A)ANTHRACENE | mg/kg | 0.6 | 0.8 | 0.0169 | J |
| BENZO(A)PYRENE | mg/kg | 0.2 | 0.2 | 0.0165 | J |
| BENZO(B)FLUORANTHENE | mg/kg | 0.6 | 2 | 0.0178 | J |
| BENZO(G,H,I)PERYLENE | mg/kg | 30000 | NC | 0.039 | U |
| BENZO(K)FLUORANTHENE | mg/kg | 6 | 25 | 0.039 | U |
| BIS(2-CHLOROETHOXY)METHANE | mg/kg | NC | NC | 0.078 | U |
| BIS(2-CHLOROETHYL)ETHER | mg/kg | 0.4 | 0.2 | 0.078 | U |
| BIS(2-ETHYLHEXYL)PHTHALATE | mg/kg | 35 | 1200 | 0.078 | U |
| BUTYLBENZYL PHTHALATE | mg/kg | 1200 | 230 | 0.078 | U |
| CAPROLACTAM | mg/kg | 31000 | 12 | 0.078 | U |
| CARBAZOLE | mg/kg | 24 | NC | 0.078 | U |
| CHRYSENE | mg/kg | 62 | 80 | 0.0175 | J |
| DI-N-BUTYL PHTHALATE | mg/kg | 6100 | 760 | 0.078 | U |
| DI-N-OCTYL PHTHALATE | mg/kg | 2400 | 3300 | 0.078 | U |
| DIBENZO(A,H)ANTHRACENE | mg/kg | 0.2 | 0.8 | 0.039 | U |
| DIBENZOFURAN | mg/kg | NC | NC | 0.078 | U |



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Imported Fill (NJCU) Soil Analytical Report

## SVOCs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| DIETHYL PHTHALATE | mg/kg | 49000 | 88 | 0.078 | U |
| DIMETHYL PHTHALATE | mg/kg | NC | NC | 0.078 | U |
| FLUORANTHENE | mg/kg | 2300 | 1300 | 0.0366 | J |
| FLUORENE | mg/kg | 2300 | 170 | 0.039 | U |
| HEXACHLOROBENZENE | mg/kg | 0.3 | 0.2 | 0.078 | U |
| HEXACHLOROBUTADIENE | mg/kg | 6 | 0.9 | 0.039 | U |
| HEXACHLOROCYCLOPENTADIENE | mg/kg | 45 | 320 | 0.39 | U |
| HEXACHLOROETHANE | mg/kg | 35 | 0.2 | 0.2 | U |
| INDENO(1,2,3-CD)PYRENE | mg/kg | 0.6 | 7 | 0.039 | U |
| ISOPHORONE | mg/kg | 510 | 0.2 | 0.078 | U |
| N-NITROSO-DI-N-PROPYLAMINE | mg/kg | 0.2 | 0.2 | 0.078 | U |
| N-NITROSODIPHENYLAMINE | mg/kg | 99 | 0.4 | 0.2 | U |
| NAPHTHALENE | mg/kg | 6 | 25 | 0.039 | U |
| NITROBENZENE | mg/kg | 31 | 0.2 | 0.078 | U |
| PHENANTHRENE | mg/kg | 300000 | NC | 0.0226 | J |
| PHENOL | mg/kg | 18000 | 8 | 0.078 | U |
| PYRENE | mg/kg | 1700 | 840 | 0.0315 | J |
| TOTAL TICS, ALKANES | mg/kg | | | 0.0000 | |
| TOTAL TICS, SEMI-VOLATILES | mg/kg | | | 0.0000 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and underlined concentrations exceed the NJ 2012 MOST STRINGENT SRS**

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

*Italicized values not detected; reporting limit exceeds criteria*

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

J: Estimated concentration

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Imported Fill (NJCU) Soil Analytical Report

## Metals

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| ALUMINUM | mg/kg | 78000 | 6000 | **10700** | |
| ANTIMONY | mg/kg | 31 | 6 | 2.6 | U |
| ARSENIC | mg/kg | 19 | 19 | 2.6 | U |
| BARIUM | mg/kg | 16000 | 2100 | 125 | |
| BERYLLIUM | mg/kg | 16 | 0.7 | 0.34 | |
| CADMIUM | mg/kg | 78 | 2 | 0.65 | U |
| CALCIUM | mg/kg | NC | NC | 7680 | |
| CHROMIUM | mg/kg | NC | NC | 21.2 | |
| COBALT | mg/kg | 590 | 90 | 10.7 | |
| COPPER | mg/kg | 3100 | 11000 | 39.1 | |
| IRON | mg/kg | NC | NC | 21100 | |
| LEAD | mg/kg | 400 | 90 | 25.8 | |
| MAGNESIUM | mg/kg | NC | NC | 6250 | |
| MANGANESE | mg/kg | 11000 | 65 | **249** | |
| MERCURY | mg/kg | 23 | 0.1 | 0.093 | |
| NICKEL | mg/kg | 1600 | 48 | 19.6 | |
| POTASSIUM | mg/kg | NC | NC | 5000 | |
| SELENIUM | mg/kg | 390 | 11 | 2.6 | U |
| SILVER | mg/kg | 390 | 1 | 0.65 | U |
| SODIUM | mg/kg | NC | NC | 1300 | U |
| THALLIUM | mg/kg | 5 | 3 | 1.3 | U |
| VANADIUM | mg/kg | 78 | NC | 39.6 | |
| ZINC | mg/kg | 23000 | 930 | 55.5 | |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

**Bold and shaded concentrations exceed the NJ 2013 IGW SOIL or both the NJ 2013 IGW SOIL and the NJ 2012 MOST STRINGENT SRS**

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

NS: Not sampled

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Imported Fill (NJCU) Soil Analytical Report

## Pesticides and PCBs

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| 2,2-DICHLOROPROPANOIC ACID | mg/kg | NC | NC | 0.0039 | U |
| 2,4,5-T | mg/kg | NC | NC | 0.0039 | U |
| 2,4,5-TP (SILVEX) | mg/kg | NC | NC | 0.0039 | U |
| 2,4-D | mg/kg | NC | NC | 0.019 | U |
| 2,4-DB | mg/kg | NC | NC | 0.019 | U |
| 4,4'-DDD | mg/kg | 3 | 4 | 0.00084 | U |
| 4,4'-DDE | mg/kg | 2 | 18 | 0.00084 | U |
| 4,4'-DDT | mg/kg | 2 | 11 | 0.000900 | |
| ALDRIN | mg/kg | 0.04 | 0.2 | 0.00084 | U |
| ALPHA-BHC | mg/kg | 0.1 | 0.002 | 0.00084 | U |
| ALPHA-CHLORDANE | mg/kg | NC | NC | 0.00084 | U |
| AROCLOR-1016 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1221 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1232 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1242 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1248 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1254 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1260 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1262 | mg/kg | NC | 0.2 | 0.042 | U |
| AROCLOR-1268 | mg/kg | NC | 0.2 | 0.042 | U |
| **Total PCBs** | mg/kg | 0.2 | 0.2 | 0.042 | U |
| BETA-BHC | mg/kg | 0.4 | 0.002 | 0.00084 | U |
| BETA-CHLORDANE | mg/kg | NC | NC | 0.00084 | U |
| CHLORDANE | mg/kg | 0.2 | 0.05 | 0.00084 | U |
| DELTA-BHC | mg/kg | NC | NC | 0.00084 | U |
| DICAMBA | mg/kg | NC | NC | 0.0039 | U |
| DICHLOROPROP | mg/kg | NC | NC | 0.019 | U |
| DIELDRIN | mg/kg | 0.04 | 0.003 | 0.00084 | U |
| DINOSEB | mg/kg | NC | NC | 0.019 | U |
| ENDOSULFAN I | mg/kg | NC | NC | 0.00084 | U |
| ENDOSULFAN II | mg/kg | NC | NC | 0.00084 | U |
| ENDOSULFAN SULFATE | mg/kg | 470 | 2 | 0.00084 | U |
| ENDRIN | mg/kg | 23 | 1 | 0.00084 | U |
| ENDRIN ALDEHYDE | mg/kg | NC | NC | 0.00084 | U |
| ENDRIN KETONE | mg/kg | NC | NC | 0.00084 | U |
| GAMMA-BHC (LINDANE) | mg/kg | 0.4 | 0.002 | 0.00084 | U |
| HEPTACHLOR | mg/kg | 0.1 | 0.5 | 0.00084 | U |
| HEPTACHLOR EPOXIDE | mg/kg | 0.07 | 0.01 | 0.00084 | U |
| MCPA | mg/kg | NC | NC | 1.9 | U |
| Mecoprop | mg/kg | NC | NC | 1.9 | U |
| METHOXYCHLOR | mg/kg | 390 | 160 | 0.0017 | U |
| PENTACHLOROPHENOL | mg/kg | 3 | 0.3 | 0.0019 | U |
| TOXAPHENE | mg/kg | 0.6 | 0.3 | 0.021 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by:DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Imported Fill (NJCU) Soil Analytical Report

## General Chemistry

Study Area 6 South

Honeywell International Inc.

Jersey City, New Jersey

| Client Sample ID | | | | 124-WC-NJCU1-020515 | |
|---|---|---|---|---|---|
| Lab Sample ID | | | | JB87709-1 | |
| Date Sampled | | | | 02/05/2015 | |
| **Parameter Name** | **Units** | **NJ 2012 MOST STRINGENT SRS** | **NJ 2013 IGW SOIL** | **CONC** | **Q** |
| HEXAVALENT CHROMIUM | mg/kg | 20 | NC | 0.51 | U |

Notes:

NJ 2012 MOST STRINGENT SRS- NJDEP Most Stringent Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

NJ 2013 IGW SOIL – NJDEP Impact to Groundwater Soil Screening Levels [N.J.A.C. 7:26D; last amended November 2013]

NC: No criterion established

Depths reported in feet below ground surface

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Q: Data qualifier assigned by laboratory or data validator

U: Not detected above method detection limit



Prepared by: DP 05/24/2016

Reviewed by: JLD 05/24/2016

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

# Backfill Sample Comparison to NJDEP Soil Standards
## Study Area 6
## 6/5/2017

| Clean Fill Comparison | | |

EXCAVATING MATERIALS & EQUIPMENT, INC.
849 ROUTE 539 • NEW EGYPT, NJ 08533 • 609.758.3400 • FAX: 609.758.5545

10-12-16

**GENERAL CONTRACTOR : Entach Corp**

**CERTIFICATION:** Clean Fill Certification

**PROJECT: Honeywell Jersey City NJ.**

Please accept this letter as our certification that the Clean Fill to be supplied to you through EME for the above referenced project is produced at our Plumsted Township Plant located at 849 Route 539, New Egypt, NJ 08533. Block 80 lot 4.

The material provided from our pit is:
Excavated from undisturbed geologic formations;
Obtained from a licensed quarry/mine;
Not been subject to a discharged hazardous substance at any time;
Not located on or impacted by other contaminant sources;
Not comingled with any other materials;
Not known or suspected of being contaminated.
Not adversely impacted by discharges of hazardous materials or chemical applications;
Not affected by conditions or processes that would result in the introduction of contaminates into the licensed quarry/mine material in concentrations above regulatory concern; and
Not affected by conditions or processes that would increase the concentrations of contaminants already present in the licensed quarry/mine to concentrations above regulatory concern.
Also please find a copy of our state mine registration.

If you need any further assistance, please feel free to contact me.

Sincerely,

Keith Prince
Vice President

State of New Jersey
Department of Labor and Workforce Development

Certificate No. 004218
Expiration Date 3/31/2017

# MINE REGISTRATION CERTIFICATE

ISSUED TO: EME Inc

LOCATION: 849 Route 539
New Egypt, NJ

BLK NO(S): 80
LOT NO(S): 4
COUNTY: Ocean

Issued pursuant to the provisions of N.J.S.A. 34:6-98.1 et. seq. Failure to comply with the provisions of the Act, and the Rules promulgated thereunder, shall be good cause for the revocation of this Certificate.

Harold J. Wirths
Commissioner

THIS CERTIFICATE MUST BE POSTED AT ALL TIMES

ES 140 (R-1-05)

# PARTAC PEAT CORPORATION

ONE KELSEY PARK, GREAT MEADOWS, NEW JERSEY 07838

800-247-BEAM (2326) • 908-637-4151 • FAX 908-637-8421

sales@beamclay.com • sales@partac.com

BEAM CLAY — THE PROFESSIONAL'S CHOICE ... SINCE 1922 — www.beamclay.com

Kelsey Park Sod Farms

PARTAC GOLF COURSE TOP-DRESSINGS — www.partac.com


October 18, 2016

EME, Inc.
849 Route 539
New Egypt, NJ 08533

Att: Keith Prince

Dear Keith:

This is to certify that our **SPHAGNUM PEAT MOSS** comes from a virgin, non-contaminated source in Maine.

Sincerely yours,

PARTAC PEAT CORPORATION

*Jim*

James C. Kelsey, President

# Nature's Choice Corporation

March 18, 2016

Caroline Panico
Entact Environmental Services Inc.
800 North Kings Highway, Suite 501
Cherry Hill, NJ 08034

RE: Topsoil located 20 Mansard Court, Wayne NJ 07470

Dear: Ms. Panico:

This letter is to certify that the above reference material is produced from a virgin source supply. All Material is excavated from the pre-existing location and put through a scalper prior to delivery.

Please contact me with any questions.

Very truly yours,

Matthew Vastano
Vice President

398 Lincoln Boulevard, Middlesex, New Jersey Phone 973.969.3299 Fax 732.469.0054

Horizon B, Page 1

**Rosano Trucking, Inc.**
26 Maple Avenue
Oceanport, New Jersey 07757
(732) 542-5009 • Fax (732) 542-5014

TANDEM TRUCK RENTAL
FILL DIRT
TOP SOIL
STONE

MAY 16, 2016

To Whom It May Concern:

This letter is to certify that the material Rosano Trucking, Inc. (RTI) supplies to the public comes from Blueberry Acres, located at Block 930; Lot 1 in Wall Township, New Jersey, comes from a virgin sand pit.

In addition, a sample of the soil from our sand pit was analyzed by a New Jersey certified laboratory for Target Compound List (TCL) and Target Analyte List (TAL parameters. The analytic results are below the New Jersey Department of Environmental Protection (NJDEP) Residential Direct Contact Soil Remediation Standards (RDCSRS) and the Impact to Ground Water Soil Screening Levels (IGWSSL).

A copy of the analytical data package is on file with out office and is available upon request. If you require further information, please feel free to contact us at (732)620-8400.

Sincerely,

Frank R. Rosano

Horizon B, Page 2

State of New Jersey
Department of Labor and Workforce Development

Certificate No. 004217
Expiration Date 3/31/2017

# MINE REGISTRATION CERTIFICATE

ISSUED TO: Rosano Trucking

LOCATION: School House Rd
Wall Township, NJ

BLK NO(S): 930
LOT NO(S): 1
COUNTY: Monmouth

Issued pursuant to the provisions of N.J.S.A. 34:6-98.1 et. seq. Failure to comply with the provisions of the Act, and the Rules promulgated thereunder, shall be good cause for the revocation of this Certificate.

Harold J. Wirths
Commissioner

THIS CERTIFICATE MUST BE POSTED AT ALL TIMES

ES-148 (R-1-05)

# Nature's Choice Corporation

March 18, 2016

Caroline Panico
Entact Environmental Services Inc.
800 North Kings Highway, Suite 501
Cherry Hill, NJ 08034

RE: Horizon C material located 476 Deans Rhode Hall Road, Cranbury, NJ

Dear: Ms. Panico:

This letter is to certify that the above reference material is produced from a virgin source supply. All Material is excavated from the pre-existing location and put through a scalper prior to delivery.

Please contact me with any questions.

Very truly yours,

Matthew Vastano
Vice President

398 Lincoln Boulevard, Middlesex, New Jersey Phone 973.969.3299 Fax 732.469.0054

State of New Jersey
Department of Labor and Workforce Development

Certificate No. 004285
Expiration Date 3/31/2017

# MINE REGISTRATION CERTIFICATE

ISSUED TO: A.B. Kurre Contracting Inc

LOCATION: PORTABLE

NJ

BLK NO(S): 18
LOT NO(S): 4
COUNTY: Middelsex

Issued pursuant to the provisions of N.J.S.A. 34:6-98.1 et. seq. Failure to comply with the provisions of the Act, and the Rules promulgated thereunder, shall be good cause for the revocation of this Certificate.

Harold J. Wirths
Commissioner

THIS CERTIFICATE MUST BE POSTED AT ALL TIMES

ES-148 (R-1-05)

# TILCON NEW YORK INC.

PHONE: 973-366-7741 • 625 MT. HOPE ROAD • WHARTON, NEW JERSEY 07885 • FAX: 973-659-3902

September 28, 2016

ENTACT, LLC
575 State Route 440
Jersey City, NJ 07305

Attn: Caroline Panico
Re: Honeywell SA6 South Cap Toe Drains

Caroline,

Tilcon NY Inc. New Jersey Division confirms that the materials produced from our Mt. Hope Quarry are defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mt. Hope Road, Block No(s) 20001, 70001, 20101 – Lot No(s) 5.01, 5.02, 7, 2, 6 Wharton Borough, Morris County NJ. The material is identified on the job with Tilcon NJ delivery tickets.

The material produced at the Mt. Hope quarry is processed through the plant to the various sizes with the source remaining the same. The 1 ½" stone is produced from the same quarry/material as the DGA.

Attached is also the analytical data for your reference.

Please feel free to contact me for any additional information.
Thank You,

Aleksandra Rogozinski
Quality Control Supervisor
Tilcon New York, Inc.
(973) 659-3790
arogozinski@tilconny.com

**TILCON-NY** **Mt. Hope Quarry** Fax 973-659-3978

625 Mount Hope Rd. • Wharton, N.J. 07946 • 973-366-7741


# Typical Gradation,DGABC

| Project |
|---|
| Honeywell SA6<br>Jersey City, NJ |

| Contractor |
|---|
| Entact |

| | |
|---|---|
| **Sp. Gr** | **2.71** |
| **Loose** | **95.7** |
| **Rodded** | **104** |

| | Typical | Prod. Target | |
|---|---|---|---|
| | % Pass | Low | High |
| **1 1/2** | **100** | 100 | 100 |
| **1"** | **95** | 55 | 100 |
| **3/4** | **82** | 55 | 90 |
| **1/2** | **65** | 25 | 90 |
| **3/8** | **58** | 25 | 90 |
| **#4** | **37** | 25 | 50 |
| **#50** | **15** | 5 | 20 |
| **#200** | **7** | 3 | 10 |




Tilcon Inc confirms that DGABC available at Mt. Hope Quarry conforms to section 901 of the ***New Jersey Department of Transportation StandardSpecifications for Road and Bridge Construction.*** The material is defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mount Hope Road, Block 20001-Lot 6.01 Wharton Borough, Morris County NJ. The material is identified on the job with Tilcon delivery tickets.

The unit weights and voids are for process control and should be verified by the contractor before use.

Common Borrow


# WELDON MATERIALS, INC.

**ENGINEERING DIVISION - TECHNICAL SERVICES**
**141 CENTRAL AVENUE, WESTFIELD, NJ 07090**
**(908) 233-4444 ext. 2288 FAX (908) 233-4215**
**email: ra@weldonmat.com**


**August 21, 2013**

**ENTACT, LLC**
**Fax: email**

**Attn: Caroline Panico**

**Reference: Honeywell Project**
**Jersey City, NJ**

**Material: QUARRY PROCESSED AGGREGATE**

**To whom it may concern:**

**We certify that the aggregate to be purchased for the project in reference is produced by Fanwood Crushed Stone Company established and mining since 1907, from sources of virgin basalt indigenous to the region. These aggregates are free from contamination when stockpiled at our quarries in Watchung, New Jersey.**

**Our Quarry is located at:**

**# 1 New Providence Road**
**Watchung, NJ**
**Somerset County.**
**Block #: 76.01, Lots #: 5 and 20**
**Mine Certificate #: 003455**

**Sincerely,**

RICARDO AROCHA
TECHNICAL SERVICES

Common Borrow


# WELDON MATERIALS, INC.

**ENGINEERING DIVISION - TECHNICAL SERVICES**
**141 CENTRAL AVENUE, WESTFIELD, NJ 07090**
**(908) 233-4444 ext. 2288 FAX (908) 233-4215**
**email: ra@weldonmat.com**


**July 31, 2014**

**ENTACT Environmental Services**
**Fax: email**

**Attn: Caroline Panico**

**Reference: Honeywell SA6 Property**
**Jersey City, NJ**

**Material: DUST / SCREENINGS**

**To whom it may concern:**

**We certify that the aggregate to be purchased for the project in reference is produced by Fanwood Crushed Stone Company established and mining since 1907, from sources of virgin basalt indigenous to the region. These aggregates are free from contamination when stockpiled at our quarries in Watchung, New Jersey.**

**Our Quarry is located at:**

**# 1 New Providence Road**
**Watchung, NJ**
**Somerset County.**
**Block #: 76.01, Lots #: 5 and 20**
**Mine Certificate #: 003951**

**Sincerely,**



Common Borrow


# WELDON MATERIALS, INC.

**ENGINEERING DIVISION - TECHNICAL SERVICES**
**141 CENTRAL AVENUE, WESTFIELD, NJ 07090**
**(908) 233-4444 ext. 2288 FAX (908) 233-4215**
**email: ra@weldonmat.com**


**September 25, 2014**

**ENTACT, LLC**

**Fax: Email**

**Attn: Caroline Panico**

**Reference: Honeywell Project**
**Jersey City, NJ**

**Material(s): Screenings/Dust and NJDOT DGA/TYPE 5A**

**To whom it may concern:**

**We certify that the aggregates to be purchased for the project in reference are produced by Weldon Quarry Company, from sources of virgin granite indigenous to the region. These aggregates are free from contamination when stockpiled at our quarry in Hopatcong, New Jersey.**

**Our Quarry is located at:**

**Route 181**
**Hopatcong, NJ**
**Sussex County.**
**Block #: 1, Lot #: 70001**
**Mine Certificate #: 003959**

**Sincerely,**



Common Borrow


# WELDON MATERIALS, INC.

**ENGINEERING DIVISION - TECHNICAL SERVICES**
**141 CENTRAL AVENUE, WESTFIELD, NJ 07090**
**(908) 233-4444 ext. 2288 FAX (908) 233-4215**
**email: ra@weldonmat.com**


**September 15, 2014**

**Contractor: ENTACT, LLC**
**Fax: email**

**Attn: Caroline Panico**

**Reference: Honeywell Project**
**Jersey City, NJ**

**Material: NJDOT DGA/TYPE 5A**

**To whom it may concern:**

**We certify that the aggregate to be purchased for the project in reference is produced by Fanwood Crushed Stone Company established and mining since 1907, from sources of virgin basalt indigenous to the region. These aggregates are free from contamination when stockpiled at our quarries in Watchung, New Jersey.**

**Our Quarry is located at:**

**# 1 New Providence Road**
**Watchung, NJ**
**Somerset County.**
**Block #: 76.01, Lots #: 5 and 20**
**Mine Certificate #: 003951**

**Sincerely,**



Structural Fill

July 10, 2015

LIBERTY AGGREGATES, LLC.

758 GARFIELD AVENUE

JERSEY CITY, NEW JERSEY 07305

PHONE: 201-240-4767

FAX: 201-432-6479

EMAIL: TPSenatore@aol.com

STATE OF NEW JERSEY PERMIT#: 004021 / CITY OF JERSEY CITY PERMIT#: P12-086

ENTACT, LLC.

ADAM EWERT

1 EAST OAK HILL DRIVE / SUITE 102

WESTMONT, IL. 60559

CELL: 630-675-9788

EMAIL: aewert@entact.com

Reference: Virgin Rock Certification

To Whom It May Concern,

Liberty Aggregates certifies that the aggregate (11/2" DGA and 3/4" clean) to be purchased for the Honeywell project in Jersey City, New Jersey are produced from clean, virgin rock excavated from the Mayrich project located at 524-530 East 74th Street, New York, New York. The depth of this excavation is approximately 50 feet and contains over 90,000 yards of material. This material is free from any contaminants and is stockpiled at our facility located at 34 Caven Point Avenue, Jersey City, New Jersey.

Sincerely,

Thomas P. Senatore

Managing Member

RALPH CLAYTON & SONS
CLAYTON BLOCK CO., INC.
CLAYTON SAND CO.

POST OFFICE BOX 3015
LAKEWOOD, NJ 08701
TOLL FREE 800-662-3044
WWW.CLAYTONCO.COM

CLAYTON
CONCRETE ▪ BLOCK ▪ SAND
*American Owned*

June 16, 2015

**CONTRACTOR:** Entact, LLC

**CERTIFICATION:** Clean Fill Certification

**PROJECT:** 60 Kellogg Street – Jersey City, NJ 07305

To Whom It May Concern:

Please accept this letter as our certification that the sand to be supplied to you for the above referenced project is clean sand from a "virgin bank" at our Woodmansie Plant located in Woodland Twp., New Jersey 08731.
Block No(s): 6401 /6402 Lot No(s): 4-4.01/8
If you need any further assistance, please feel free to contact me.

Sincerely,

Jerry Dooley
Sales and Technical Consultant
Clayton Sand Company

Sworn and subscribed to before me this 16th day

of June 2015 at Neptune, NJ 07753

CHERYLL MCCARTHY
Notary Public State of New Jersey
My Comm. Expires April 5, 2017

JD/cm

CERTIFICATION

"Celgene Soil" - New Source of Imported Clean Fill

In 2014, Honeywell identified a new source for backfill material to be used at SA-6 during the chromium remedy. The material was from a nearby construction site at the Celgene facility. The material was not from a quarry, but rather from a virgin portion of the Celgene property where a new underground structure and parking garage was being constructed. It was tested for environmental impacts and for geotechnical properties and was found to meet the NJDEP and the SA-6 100% Design requirements for use as clean fill at SA-6. Honeywell prepared correspondence entitled, "New Source of Imported Clean Fill," dated July 3, 2014 which was submitted to all the Parties. Given the above, the "Celgene Soil" is suitable for unrestricted use at SA-6.

CERTIFICATION

"Celgene Soil" - New Source of Imported Clean Fill

In 2014, Honeywell identified a new source for backfill material to be used at SA-6 during the chromium remedy. The material was from a nearby construction site at the Celgene facility. The material was not from a quarry, but rather from a virgin portion of the Celgene property where a new underground structure and parking garage was being constructed. It was tested for environmental impacts and for geotechnical properties and was found to meet the NJDEP and the SA-6 100% Design requirements for use as clean fill at SA-6. Honeywell prepared correspondence entitled, "New Source of Imported Clean Fill," dated July 3, 2014 which was submitted to all the Parties. Given the above, the "Celgene Soil" is suitable for unrestricted use at SA-6.

ENVIRON

July 12, 2012

MEMORANDUM

To: William J. Hague, P.E., Honeywell

From: Jose Sananes, P.E., ENVIRON
Gary DiPippo, P.E., Cornerstone
Mark Nielsen, P.E., ENVIRON

Subject: SA7 Contractor Submittal #15C - Earth Material Testing Report

ENVIRON and Cornerstone have reviewed Sevenson Environmental Services' (SES) submittal #15C (Earth Material Testing Report) for compliance with the project specifications. The testing report is applicable to all sand and stone materials to be used for the remedy construction at SA7. The materials will originate from Tilcon's Mount Hope Quarry.

As required in **Specification 35 43 00**, "cap materials shall not be obtained from an industrial site or from a source suspected to have been modified by the addition of man-made chemicals. For each source, material type prior to acceptance and for each 5,000 cubic yards, Contractor shall provide analytical data to indicate that the material is free from contamination, the total chromium concentration is below 370 mg/kg and the hexavalent chromium concentration is below 20 mg/kg, and a certificate of Clean Fill as per NJDEP requirements (N.J.A.C. 7:26E-6), unless other material is approved by the consent of the Parties" (i.e., the Special Master). Note that subsequent to the revision to the 100% Design Report we informed Sevenson that we are requiring a 1 mg/kg limit on hexavalent chromium.

In accordance with the NJDEP's Fill guidance (August 2011), SES has submitted a certification stating that the materials originate from a virgin source of rock not located on or impacted by any contaminated sources (see attached TILCON mining certificate and a certification prepared by S&S Environmental dated June 8, 2012). In addition, SES has provided analytical results for the materials (attached). Based on the information provided, we find the material to be acceptable, although we noted the following:

1. Beryllium was detected at a concentration of 0.549 ppm, which marginally exceeds the New Jersey impact-to-groundwater (IGW) soil screening level of 0.5 ppm. However,

    a. As per the NJDEP IGWSRS guideline and FAQs (http://www.nj.gov/dep/srp/guidance/rs/igw_faq.pdf), if detected concentrations are demonstrated to be due to background conditions as opposed to discharges, then no remediation is required (i.e., there is no AOC). As indicated above, SES has provided a certification from the quarry stating that the materials are not impacted by any contaminant source.

b. The detected concentration of beryllium is consistent with NJDEP's published median concentration for the urban piedmont region where the materials will be placed. Although the beryllium concentration is higher than the median concentration reported for rural areas of the New Jersey ridge and valley province where the quarry is located, the detected concentration is lower than the 90th percentile concentration (see NJDEP report on background: http://www.nj.gov/dep/dsr/research/ambient-levels-metal.pdf).

- NJ Urban Piedmont:
  - median=0.51 mg/kg;
  - $90^{th}$ Percentile = 0.82 mg/kg
- NJ Ridge& Valley Province:
  - median = <0.01 mg/kg;
  - $90^{th}$ Percentile = 0.91 mg/kg

c. The published EPA method 6020 QA/QC for beryllium indicates that the percent recovery on spiked samples is 75% to 125%. Given this range, the slightly elevated result in comparison to the default IGW soil screening level is within the level of accuracy of the analysis.

d. The IGW soil screening levels which are based on protection of potable drinking water are not necessarily applicable to this project. The sediment cap material is being placed in the Hackensack River (a saline surface water body) where there would be no potential for impact to potable water. If we consider the saline water quality criterion as the more appropriate end point, then the adjusted clean fill "IGW" soil screening level would be 21 mg/kg (i.e., a factor of 42 when changing from a groundwater quality criterion of1 ug/L to a saline surface water quality criterion of 42 ug/L) assuming all other factors remain the same.

e. The NJ Clean Fill Policy specifies that clean fill proposed for use at a site cannot impact sediment quality in a way that is "inconsistent with the proposed remedial action. In other words, the proposed remedial action for the receiving AOC must address all sediment issues whether from the existing contamination or the placement of the clean fill." In this regard, we note that the beryllium concentration in the quarry material is the approximately the same as the mean sediment concentration reported in the SA7 sediment investigation report (ENVIRON 2006).

2. Aluminum and Manganese concentrations in the quarry sample also exceeded the IGW soil screening levels, however, the NJDEP has determined that the IGW pathway does not need to be addressed for these contaminants unless there is cause to believe that their presence is due to a site discharge. As indicated above, SES has provided a certification from the quarry stating that the materials are not impacted by any contaminant source.

3. The quality of the materials will continue to be verified through the required testing every 5,000 CY.

# SA7 – Earth Material Testing Reports/Clean Fill Affidavit

Specification – 31 23 16; 1.4D, D

Revised 6.27.12 based on comments from June 6, 2012

1. Filtering criteria design results and xls file as a separate attachment
2. Letter from Tilcon on source of material
3. Letter from S and S Environmental for their site review on the Mount Hope Quarry
4. "Fines" analysis from S and S Environmental in accordance with NJDEP Site Remediation Program
5. Gradation curves for sand, filter material, and armor stone (Mount Hope Quarry)
    a. Dense Graded Aggregate (Roadways)
    b. Grits (Sand)
    c. ASTM 57 (Filter Layer)
    d. ASTM 5 (0.75" Armor Stone)
    e. ASTM 4 (1.0" Armor Stone)
    f. ASTM 1 (1.5", 1.6", 2.0" Armor Stone)
    g. 4's and 5's (3.5" Armor Stone)
    h. Light Stone Filling (6" Armor Stone)
    i. Medium Stone Filling (10" Armor Stone)

# 1.0 Filtering Criteria Design

**Filter Design Calculations**
**April 28, 2012 - Donegan**
**Jersey City SA7**
**Revised 6.28.12**

| Aggregate Specification/Type | D15 (in) | D50 (in) | D85 (in) | Proposed Layer |
|---|---|---|---|---|
| Insitu Material 1 - "coarse" | | | 0.0163 | Insitu Material 1 |
| Insitu Material 2 - "Fine" | | | 0.0025 | Insitu Material 2 |
| Grits Mount Hope Quarry (Sand) | 0.010 | 0.055 | 0.118 | Proposed "Sand Layer" |
| ASTM 5 (0.75" Armor) | 0.551 | 0.768 | 0.906 | Proposed 0.75" Material |
| ASTM 57 (Filter Layer) | 0.433 | 0.551 | 0.709 | Proposed Filter Layer |
| ASTM 4 (1.0" Armor) | 0.827 | 1.063 | 1.339 | Proposed 1" Material |
| ASTM1 (1.5", 1.6" and 2.0" Armor) | 1.673 | 2.638 | 3.287 | Proposed 1.5, 1.6, and 2.0" Material |
| 4's and 5's (3.5" Armor) | 2.953 | 3.543 | 5.118 | Proposed 3.5" Material |

**Filter Material Design Criteria**

Filter Criteria for Coarse Grained — D15 upper layer ≤ 5 x D85 lower layer
Filter Criteria for Fine Grained — D15 upper layer ≤ 9 x D85 lower layer

**Analysis of Sand and Armor Cap Materials Based Against and Permeability Criteria**

Note: Criteria results in red are outside of the acceptable range.

| Insitu Layer | | | | "Sand Material" | | | Filter Criteria |
|---|---|---|---|---|---|---|---|
| Type | | | D85(in) | Type | D15(in) | D50(in) | D15 armor / D85 sand |
| Insitu Material 1 - "coarse" | | | 0.0163 | Grits Mount Hope Quarry (Sand) | 0.010 | 0.055 | 0.605 |
| Insitu Material 2 - "Fine" | | | 0.0025 | Grits Mount Hope Quarry (Sand) | 0.010 | 0.055 | 3.900 |

| Sand Material | | | | Filter Layer | | | Filter Criteria |
|---|---|---|---|---|---|---|---|
| Type | D15(in) | D50(in) | D85(in) | Type | D15(in) | D50(in) | D15 armor / D85 sand |
| Grits Mount Hope Quarry (Sand) | 0.010 | 0.055 | 0.118 | ASTM 57 (Filter Layer) | 0.433 | 0.551 | 3.667 |

| Filter/Sand Layer | | | | Armor Cap | | | Filter Criteria |
|---|---|---|---|---|---|---|---|
| Type | D15(in) | D50(in) | D85(in) | Type | D15(in) | D50(in) | D15 armor / D85 sand |
| Grits Mount Hope Quarry (Sand) | 0.010 | 0.055 | 0.118 | ASTM 5 (0.75" Armor) | 0.551 | 0.768 | 4.667 |
| ASTM 57 (Filter Layer) | 0.433 | 0.551 | 0.709 | ASTM 4 (1.0" Armor) | 0.827 | 1.063 | 1.167 |
| ASTM 57 (Filter Layer) | 0.433 | 0.551 | 0.709 | ASTM1 (1.5", 1.6" and 2.0" Armor) | 1.673 | 2.638 | 2.361 |
| ASTM 57 (Filter Layer) | 0.433 | 0.551 | 0.709 | 4's and 5's (3.5" Armor) | 2.953 | 3.543 | 4.167 |

# 2.0 Letter from Tilcon

TILCON

# TILCON NEW YORK INC.

625 MT. HOPE ROAD • WHARTON, NEW JERSEY 07885 • PHONE 973-366-7741

June 26, 2012

Mr. Timothy Donegan, PE
Engineering Manager
Sevenson Environmental Services, Inc.
815 Ritchie Highway, Suite 107
Severna Park, MD 21146

RE: Quarry Source and NJDEP Residential Direct Soil Remediation Standards/Clean Fill Criteria

Mr. Donegan,

As discussed today, June 26, 2012, the table below provides a summary of the materials we intend to provide for the Jersey City SA7 project and the source (quarry). A sample report is provided as an attachment for our Mount Hope Quarry identified in table 1 below.

**Table 1 – Material Source Identification**

| Tilcon Material Type | Sevenson Designation | Quarry Source |
|---|---|---|
| Grits | Sand | Mount Hope Quarry |
| ASTM 57 | Filterlayer | Mount Hope Quarry |
| ASTM 5 | 0.75 Inch Armor | Mount Hope Quarry |
| ASTM 4 | 1.0 Inch Armor | Mount Hope Quarry |
| ASTM 1 | 1.5, 1.6 AND 2.0 Inch Armor | Mount Hope Quarry |
| 4's and 5's | 3.5 Inch Armor | Mount Hope Quarry |
| Light Stone Filling | 6" Armor Stone | Mount Hope Quarry |
| Medium Stone Filling | 10" Armor Stone | Mount Hope Quarry |
| DGA | Roadway Stone | Mount Hope Quarry |

All of the materials will be supplied from the Mount Hope Quarry and are durable and quarried from virgin gneiss. The materials identified come from the same location in the quarry as provided in the environmental analysis attached. All of the materials detailed above meet the NJDEP Residential Direct Soil Remediation Standards/Clean Fill Criteria. Please let us know if you have any questions.

Sincerely,

William H. Aspinall, IV
VP New Jersey Operations

cc: S. Laudone
S. O'Reilly
G. Labatte
C. Morris
R. Linton

# 3 - Letter from S and S Environmental Site Review of the Mount Hope Quarry

# S & S ENVIRONMENTAL SCIENCES, INC.

***Environmental Engineering, Testing and Consultation***

98 Sand Park Road, Cedar Grove, NJ 07009
Tel (973) 857-7188 Fax (973) 239-8380

Kamil Sor, Ph.D.
Yilmaz Arhan, Ph.D.
Orhun Sor, P.E.
Peter G. Micklus, P.E.
Kenneth J. Rowbotham, P.E.


June 8, 2012
Report No. 12-E-188

Tilcon New York Inc.
625 Mount Hope Road
Wharton, NJ 07885

Attention: Mr. Steve O'Reilly

Re: Mount Hope Rock Quarry, New Jersey

Dear Mr. O'Reilly:

As requested, I visited the referenced quarry site on June 7, 2012. The purpose of my site visit was to visually check the area of the quarry where granite rock is being surface mined from an undisturbed geologic formation. The rock which is mined at this location is blasted, transported to the on-site crushing operation, and then processed into various sized aggregates including ¾ inch stone which is sold to various customers. The stone is virgin material, and no chemicals and/or additives are added to the product.

A Site Review was conducted in accordance with the New Jersey Department of Environmental Protection (NJDEP) Site Remediation Program Fill Guidance at SRP Sites dated August 11, 2011.

TILCON has owned and operated the rock quarry since 2001. The area of the quarry site was also used for mining iron, beginning around 1710, and the Mount Hope iron mines operated for over 250 years. The area of the quarry where virgin rock is being surface mined has never been used for any other industrial or commercial purposes.

Based on my site visit of June 7, 2012, information provided by Tilcon New York, Inc. (TILCON) with respect to their ownership and use of the site, and according to the preliminary investigation regarding site development and use history, the rock which is being obtained from this quarry has not been located on or impacted by any contaminant sources.

If there are any questions or should you require additional information, please do not hesitate to contact me.

Very truly yours,

S & S ENVIRONMENTAL SCIENCES, INC.

Yilmaz Arhan, Ph.D.
Vice President

YA/ya

# 4 - “Fines” ! nalysis from S and S Environmental in Accordance With NJDEP Site Remediation Program

# S & S ENVIRONMENTAL SCIENCES, INC.

***Environmental Engineering, Testing and Consultation***

98 Sand Park Road, Cedar Grove, NJ 07009
Tel (973) 857-7188 Fax (973) 239-8380

Kamil Sor, Ph.D.
Yilmaz Arhan, Ph.D.
Orhun Sor, P.E.
Peter G. Micklus, P.E.
Kenneth J. Rowbotham, P.E.



This report is the confidential property of the Client, and information contained may not be published or reproduced without our written permission.


| | | | | | |
|---|---|---|---|---|---|
| **Client:** | TILCON New York, Inc. | | | | |
| **Project:** | Mount Hope, New Jersey | | | | |
| **Subject:** | Laboratory Analysis of Stone Fines | | | | |
| **Job No.:** | 07-E-34 | **Report Number:** | 12-E-206 | **Date:** | 06-15-2012 |

We present herewith the laboratory test results of the stone fines sample picked up by a representative of our firm on June 8, 2012. The sample was collected by a representative of TILCON on June 8, 2012.

As requested, the sample was analyzed for the U.S. EPA Target Compound List (TCL)+30/Target Analyte List (TAL) parameters, Extractable Petroleum Hydrocarbons (EPH), pH, and Hexavalent Chromium. The analyses were performed by Integrated Analytical Laboratories, LLC (IAL) (NJDEP Lab ID No. 14751).

The test results are summarized in Table Nos. 1 through 4. A copy of the IAL sample chain-of-custody form and a copy of the preliminary faxed IAL laboratory summary report are attached.

Based on the laboratory data, the sample meets all of the NJDEP Residential Direct Contact Soil Remediation Standards/Clean Fill Criteria.

If there are any questions or if we can be of further assistance in this matter please call us.

Very truly yours,

S & S ENVIRONMENTAL SCIENCES, INC.

Yilmaz Arhan, Ph.D.
Vice President

YA/ya

Attachments: (1) IAL Laboratory Summary Report and Sample Chain-of-Custody Form
(2) NJDEP Residential Soil Remediation Standards List

cc: (1) Client (Attn: Mr. Steve O'Reilly)

**TABLE 1 - SUMMARY OF LABORATORY TEST RESULTS**

| PARAMETERS | SAMPLE #12-121 RESULT | NJDEP SOIL REMEDIATION STANDARD(*) |
|---|---|---|
| **Organic Compounds** | | |
| Volatile Organic Compounds | Not Detected (See Table 2) | See Attached List |
| Semi-Volatile Organics | Not Detected (See Table 3) | See Attached List |
| Pesticides | Not Detected (See Table 4) | See Attached List |
| PCBs | Not Detected (See Table 4) | Total 0.20 |
| **Metals:** | | |
| Aluminum | 4,820 | 78,000 |
| Antimony | ND (<0.250) | 31 |
| Arsenic | 1.06 | 19 |
| Barium | 47.1 | 16,000 |
| Beryllium | 0.549 | 16 |
| Cadmium | ND (<0.125) | 78 |
| Calcium | 4,570 | NA |
| Chromium | 14.2 | 120,000 |
| Cobalt | 5.75 | 1,600 |
| Copper | 16.3 | 3,100 |
| Iron | 17,300 | NA |
| Lead | 1.78 | 400 |
| Magnesium | 3,680 | NA |
| Manganese | 170 | 11,000 |
| Mercury | ND (<0.00594) | 23 |
| Nickel | 7.69 | 1,600 |
| Potassium | 1,960 | NA |
| Selenium | ND (<1.00) | 390 |
| Silver | ND (<0.125) | 390 |
| Sodium | 126 | NA |
| Thallium | 0.147 J | 5 |
| Vanadium | 19.3 | 78 |
| Zinc | 19.0 | 23,000 |
| **Others** | | |
| Extractable Petroleum Hydrocarbons (EPH) (C9-C40) | ND (<9.00) | 1,000 |
| Cyanide | ND (<0.700) | 1,600 |
| Hexavalent Chromium | ND (<0.236) | 1(**) |
| pH, SU | 8.59 | NA |

*Results are in mg/kg (milligrams per kilogram) unless otherwise specified.*

*(*) NJDEP's most stringent "Residential Direct Contact Soil Remediation Standards"*

*(**)The hexavalent chromium standard is a site-specific requirement*

ND: N*ot Detected* < - Indicates less than (the value reported is the Method Detection Limit)
J – The concentration was detected at a value below the Reporting Limit and above the Method Detection Limit

## TABLE 2 - TEST RESULTS FOR VOLATILE ORGANIC COMPOUNDS

| SAMPLING DATE: 06-08-2012 (Client) | | SAMPLE MATRIX: Stone Fines |
|---|---|---|
| **PARAMETER** | **SAMPLE #12-121 RESULT** | **NJDEP SOIL REMEDIATION STANDARD(*)** |
| 1,1-Dichloroethane | ND | 8 |
| 1,1,1-Trichloroethane | ND | 290 |
| 1,1,2,2-Tetrachloroethane | ND | 1 |
| 1,1,2-Trichloroethane | ND | 2 |
| 1,1-Dichloroethene | ND | 11 |
| 1,2-Dichloroethene | ND | 230 |
| 1,2-Dichloropropane | ND | 2 |
| 1,3-Dichloropropene (cis and trans) | ND | 2 |
| 1,2-Dichloroethane | ND | 0.9 |
| 2-Butanone (MEK) | ND | 3100 |
| 4-Methyl-2-Pentanone (MIBK) | ND | NA |
| Acetone | ND | 70000 |
| Acrylonitrile | ND | 0.9 |
| Benzene | ND | 2 |
| Bromodichloromethane | ND | 1 |
| Bromoform | ND | 81 |
| Bromomethane | ND | 25 |
| Carbon tetrachloride | ND | 0.6 |
| Chlorobenzene | ND | 510 |
| Chloroform | ND | 0.6 |
| Chloromethane | ND | 4 |
| Cis-1,2-Dichloroethene | ND | 230 |
| Trans-1,2-Dichloroethene | ND | 300 |
| Dibromochloromethane | ND | 3 |
| Ethylbenzene | ND | 7800 |
| Methylene Chloride | ND | 34 |
| Styrene | ND | 90 |
| Naphthalene | ND | 6 |
| Tetrachloroethene (PCE) | ND | 2 |
| Toluene | ND | 6300 |
| Xylenes (Total) | ND | 12000 |
| Trichloroethene (TCE) | ND | 7 |
| Trichlorofluoromethane | ND | 23000 |
| Tertiary Butyl Alcohol | ND | 1400 |
| Vinyl Chloride | ND | 0.7 |
| Tentatively Identified Compounds | ND | NA |
| Total VO's and TICs | ND | NA |

*Results are in mg/kg (milligrams per kilogram) unless otherwise specified.*
*(*) NJDEP's most stringent "Residential Direct Contact Soil Remediation Standards"*
ND: NOT DETECTED (see laboratory report for detection limits) NA–NOT AVAILABLE

## TABLE 3 – TEST RESULTS FOR SEMI-VOLATILE ORGANIC COMPOUNDS

| **SAMPLING DATE:** | 06-08-2012 (Client) | **SAMPLE MATRIX:** Stone Fines |
|---|---|---|

| PARAMETER | SAMPLE #12-121 RESULT | NJDEP SOIL REMEDIATION STANDARD(*) |
|---|---|---|
| bis(2-chloroethyl) ether | ND | 0.4 |
| 1,3–Dichlorobenzene | ND | 5300 |
| 1,4–Dichlorobenzene | ND | 5 |
| 1,2–Dichlorobenzene | ND | 5300 |
| Benzyl alcohol | ND | NA |
| bis(2-chloroisopropyl) ether | ND | 23 |
| bis(2-ethylhexyl) phthalate | ND | 35 |
| Hexachloroethane | ND | 35 |
| n-Nitroso-di-n-propylamine | ND | 0.2 |
| Nitrobenzene | ND | 31 |
| Isophorone | ND | 510 |
| 1,2,4–Trichlorobenzene | ND | 73 |
| 4–Chloroaniline | ND | NA |
| Hexachloro-1,3-butadiene | ND | 6 |
| Hexachlorocyclopentadiene | ND | 45 |
| Dimethylphthalate | ND | NA |
| Diethylphthalate | ND | 49,000 |
| 2,4-Dinitrotoluene | ND | 0.7 |
| 2,6- Dinitrotoluene | ND | 0.7 |
| n-Nitrosodiphenylamine | ND | 99 |
| Hexachlorobenzene | ND | 0.3 |
| Butylbenzylphthalate | ND | 1200 |
| 4–Chloro-3-methylphenol | ND | NA |
| 2–Chlorophenol | ND | 310 |
| Di-n-butyl phthalate | ND | 6100 |
| Di-n-octyl phthalate | ND | 2400 |
| 3,3'-Dichlorobenzidine | ND | 1 |
| 2,4-Dichlorophenol | ND | 180 |

*Results are in mg/kg (milligrams per kilogram) unless otherwise specified.*

*(*) NJDEP's most stringent "Residential Direct Contact Soil Remediation Standards"*

ND: *Not Detected (see laboratory report for detection limits)*

NA – NOT APPLICABLE/NOT AVAILABLE

## TABLE 3 - TEST RESULTS FOR SEMI-VOLATILE ORGANIC COMPOUNDS (continued)

| SAMPLING DATE: | 06-08-2012 (Client) | SAMPLE MATRIX: Stone Fines |
|---|---|---|

| PARAMETER | SAMPLE #12-121 RESULT | NJDEP SOIL REMEDIATION STANDARD(*) |
|---|---|---|
| 2,4-Dimethylphenol | ND | 1200 |
| 2,4-Dinitrophenol | ND | 120 |
| 2-Methylphenol (o-Cresol) | ND | 310 |
| 4-Methylphenol (p-Cresol) | ND | 31 |
| Pentachlorophenol | ND | 3 |
| Phenol | ND | 18,000 |
| 2,4,5-Trichlorophenol | ND | 6100 |
| 2,4,6-Trichlorophenol | ND | 19 |
| Benzoic Acid | ND | NA |
| | | |
| Acenaphthene | ND | 3400 |
| Acenaphthylene | ND | NA |
| Anthracene | ND | 17,000 |
| Benzo[a]anthracene | ND | 0.6 |
| Benzo[a]pyrene | ND | 0.2 |
| Benzo[b]fluoranthene | ND | 0.6 |
| Benzo[k]fluoranthene | ND | 6 |
| Carbazole | ND | 24 |
| Chrysene | ND | 62 |
| Dibenz[a,h]anthracene | ND | 0.2 |
| Dibenzofuran | ND | NA |
| Fluoranthene | ND | 2300 |
| Fluorene | ND | 2300 |
| Indeno[1,2,3-cd]pyrene | ND | 0.6 |
| Naphthalene | ND | 6 |
| 2-Methylnaphthalene | ND | 230 |
| Pyrene | ND | 1700 |
| Benzo[g,h,i]perylene | ND | 380000 |
| Phenanthrene | ND | NA |
| Total | ND | NA |
| Tentatively Identified Compounds (TICs) | ND | NA |
| Total | ND | NA |

*Results are in mg/kg (milligrams per kilogram) unless otherwise specified.*
*(*) NJDEP's most stringent "Residential Direct Contact Soil Remediation Standards"*
ND: *Not Detected (see laboratory report for detection limits)*
NA - Not Applicable/Not Available
J – The concentration was detected at a value below the Reporting Limit and above the Method Detection Limit

## TABLE 4- TEST RESULTS FOR PESTICIDES AND PCBs

| **SAMPLING DATE:** | 06-08-2012 (Client) | **SAMPLE MATRIX:** Stone Fines |
|---|---|---|

| PARAMETER | SAMPLE #12-121 RESULT | NJDEP SOIL REMEDIATION STANDARDS(*) |
|---|---|---|
| **PESTICIDES** | | |
| Aldrin | ND | 0.04 |
| 4,4' – DDD | ND | 3 |
| 4,4' – DDE | ND | 2 |
| 4,4' – DDT | ND | 2 |
| Dieldrin | ND | 0.04 |
| Endosulfan I and Endosulfan II | ND | 470 |
| Endosulfan sulfate | ND | 470 |
| Endrin | ND | 23 |
| Heptachlor | ND | 0.1 |
| Heptachlor epoxide | ND | 0.07 |
| alpha-BHC | ND | 0.1 |
| beta-BHC | ND | 0.4 |
| gamma – BHC (Lindane) | ND | 0.4 |
| Methoxychlor | ND | 390 |
| Toxaphene | ND | 0.6 |
| Chlordane | ND | 0.2 |
| | | |
| **PCBs** | | |
| Aroclor - 1016 | ND | NA |
| Aroclor - 1221 | ND | NA |
| Aroclor - 1232 | ND | NA |
| Aroclor - 1242 | ND | NA |
| Aroclor - 1248 | ND | NA |
| Aroclor - 1254 | ND | NA |
| Aroclor - 1260 | ND | NA |
| Aroclor - 1262 | ND | NA |
| Aroclor - 1268 | ND | NA |
| Total PCBs | ND | 0.20 (TOTAL PCBs) |

*Results are in mg/kg (milligrams per kilogram) unless otherwise specified.*

*(*) NJDEP's most stringent "Residential Direct Contact Soil Remediation Standards"*

ND: *Not Detected (see laboratory report for detection limits)*
NA - Not Applicable/Not Available

# INTEGRATED ANALYTICAL LABORATORIES, LLC.

**SUMMARY REPORT**
**Client: S & S Environmental**
**Project: MT. HOPE**
**Lab Case No.: E12-05656**

| | | | |
|---|---|---|---|
| **Lab ID:** | **05656-001** | | |
| **Client ID:** | **12-121** | | |
| **Matrix:** | **Solid** | | |
| **Sampled Date** | **6/8/12** | | |
| **PARAMETER(Units)** | Conc | Q | MDL |
| **Volatiles (Units)** | *(mg/Kg-ppm)* | | |
| **TOTAL VO's:** | ND | | |
| **TOTAL TIC's:** | ND | | |
| **TOTAL VO's & TIC's:** | ND | | |
| **Semivolatiles - BNA (Units)** | *(mg/Kg-ppm)* | | |
| **TOTAL BNA'S:** | ND | | |
| **TOTAL TIC's:** | ND | | |
| **TOTAL BNA'S & TIC's:** | ND | | |
| **PCB's (Units)** | *(mg/Kg-ppm)* | | |
| Aroclor-1016 | ND | | 0.00066 |
| Aroclor-1221 | ND | | 0.00066 |
| Aroclor-1232 | ND | | 0.00066 |
| Aroclor-1242 | ND | | 0.00066 |
| Aroclor-1248 | ND | | 0.00066 |
| Aroclor-1254 | ND | | 0.00066 |
| Aroclor-1260 | ND | | 0.00066 |
| Aroclor-1262 | ND | | 0.00066 |
| Aroclor-1268 | ND | | 0.00066 |
| PCBs | ND | | 0.00066 |
| **Pesticides (Units)** | *(mg/Kg-ppm)* | | |
| alpha-BHC | ND | | 0.000165 |
| beta-BHC | ND | | 0.000165 |
| gamma-BHC (Lindane) | ND | | 0.000165 |
| delta-BHC | ND | | 0.000165 |
| Heptachlor | ND | | 0.000165 |
| Aldrin | ND | | 0.000165 |
| Heptachlor epoxide | ND | | 0.000165 |
| Endosulfan I | ND | | 0.000165 |
| 4,4'-DDE | ND | | 0.000165 |
| Dieldrin | ND | | 0.000165 |
| Endrin | ND | | 0.000165 |
| Endosulfan II | ND | | 0.000165 |
| 4,4'-DDD | ND | | 0.000165 |
| Endrin aldehyde | ND | | 0.000165 |
| Endosulfan sulfate | ND | | 0.000165 |
| 4,4'-DDT | ND | | 0.000165 |
| Endrin ketone | ND | | 0.000165 |
| Methoxychlor | ND | | 0.000165 |
| alpha-Chlordane | ND | | 0.000165 |
| gamma-Chlordane | ND | | 0.000165 |
| Toxaphene | ND | | 0.00198 |
| Endosulfan (I and II) | ND | | 0.000165 |
| Chlordane (alpha and gamma) | ND | | 0.000165 |

ND = Analyzed for but Not Detected at the MDL

# INTEGRATED ANALYTICAL LABORATORIES, LLC.

**SUMMARY REPORT**
**Client: S & S Environmental**
**Project: MT. HOPE**
**Lab Case No.: E12-05656**

| | | | |
|---|---|---|---|
| **Lab ID:** | **05656-001** | | |
| **Client ID:** | **12-121** | | |
| **Matrix:** | **Solid** | | |
| **Sampled Date** | **6/8/12** | | |
| **PARAMETER(Units)** | Conc | Q | MDL |
| **Hydrocarbons (Units)** | ***(mg/Kg-ppm)*** | | |
| C9-C40 | ND | | 9.00 |
| **Metals (Units)** | ***(mg/Kg-ppm)*** | | |
| Aluminum | 4820 | | 5.00 |
| Antimony | ND | | 0.250 |
| Arsenic | 1.06 | | 0.250 |
| Barium | 47.1 | | 2.50 |
| Beryllium | 0.549 | | 0.200 |
| Cadmium | ND | | 0.125 |
| Calcium | 4570 | | 25.0 |
| Chromium | 14.2 | | 0.500 |
| Cobalt | 5.75 | | 0.500 |
| Copper | 16.3 | | 0.500 |
| Iron | 17300 | | 12.5 |
| Lead | 1.78 | | 0.125 |
| Magnesium | 3680 | | 12.5 |
| Manganese | 170 | | 0.250 |
| Mercury | ND | | 0.00594 |
| Nickel | 7.69 | | 0.500 |
| Potassium | 1960 | | 12.5 |
| Selenium | ND | | 1.00 |
| Silver | ND | | 0.125 |
| Sodium | 126 | | 25.0 |
| Thallium | 0.147 | J | 0.125 |
| Vanadium | 19.3 | | 0.500 |
| Zinc | 19.0 | | 2.00 |
| **General Analytical (Units)** | | | |
| Hexavalent Chromium(mg/Kg-ppm) | ND | | 0.236 |
| Cyanide, Total(mg/Kg-ppm) | ND | | 0.700 |
| pH/Corrosivity(SU) | 8.59 | | NA |

ND = Analyzed for but Not Detected at the MDL
J = The concentration was detected at a value below the RL and above the MDL

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| Sample #: | | NJDEP SOIL REMEDIAT | 12-121 | | | |
|---|---|---|---|---|---|---|
| Field ID: | | STANDARDS | | | | |
| Lab ID: | | Residential | 05656-001 | | | |
| Date Sampled: | | SRS | 06/08/2012 | | | |
| Depth(ft): | | | | | | |
| | CAS | (mg/Kg) | | | | |
| **Volatiles (mg/Kg)** | | | Conc | Q | RL | MDL |
| Dichlorodifluoromethane | 75-71-8 | 490 | ND | | 0.00152 | 0.000608 |
| Chloromethane | 74-87-3 | 4 | ND | | 0.00152 | 0.000623 |
| Vinyl chloride | 75-01-4 | 0.7 | ND | | 0.00152 | 0.00073 |
| Bromomethane | 74-83-9 | 25 | ND | | 0.00304 | 0.000532 |
| Chloroethane | 75-00-3 | 220 | ND | | 0.00152 | 0.000684 |
| Trichlorofluoromethane | 75-69-4 | 23000 | ND | | 0.00152 | 0.000623 |
| 1,1-Dichloroethene | 75-35-4 | 11 | ND | | 0.00152 | 0.00076 |
| Acetone | 67-64-1 | 70000 | ND | | 0.0076 | 0.00106 |
| Carbon disulfide | 75-15-0 | 7800 | ND | | 0.00152 | 0.000517 |
| Methylene chloride | 75-09-2 | 34 | ND | | 0.00304 | 0.00301 |
| trans-1,2-Dichloroethene | 156-60-5 | 300 | ND | | 0.00152 | 0.000654 |
| Methyl tert-butyl ether (MTBE) | 1634-04-4 | 110 | ND | | 0.00152 | 0.00035 |
| 1,1-Dichloroethane | 75-34-3 | 8 | ND | | 0.00152 | 0.00041 |
| cis-1,2-Dichloroethene | 156-59-2 | 230 | ND | | 0.00152 | 0.000471 |
| 2-Butanone (MEK) | 78-93-3 | 3100 | ND | | 0.00152 | 0.000562 |
| Bromochloromethane | 74-97-5 | NS | ND | | 0.00152 | 0.000365 |
| Chloroform | 67-66-3 | 0.6 | ND | | 0.00152 | 0.000441 |
| 1,1,1-Trichloroethane | 71-55-6 | 290 | ND | | 0.00152 | 0.000502 |
| Carbon tetrachloride | 56-23-5 | 0.6 | ND | | 0.00152 | 0.000623 |
| 1,2-Dichloroethane (EDC) | 107-06-2 | 0.9 | ND | | 0.00152 | 0.000319 |
| Benzene | 71-43-2 | 2 | ND | | 0.00152 | 0.000365 |
| Trichloroethene | 79-01-6 | 7 | ND | | 0.00152 | 0.000486 |
| 1,2-Dichloropropane | 78-87-5 | 2 | ND | | 0.00152 | 0.000334 |
| 1,4-Dioxane | 123-91-1 | NS | ND | | 0.304 | 0.024 |
| Bromodichloromethane | 75-27-4 | 1 | ND | | 0.00152 | 0.000486 |
| cis-1,3-Dichloropropene | 10061-01-5 | NS | ND | | 0.00152 | 0.000395 |
| 4-Methyl-2-pentanone (MIBK) | 108-10-1 | NS | ND | | 0.00152 | 0.000365 |
| Toluene | 108-88-3 | 6300 | ND | | 0.00152 | 0.00038 |
| trans-1,3-Dichloropropene | 10061-02-6 | NS | ND | | 0.00152 | 0.000395 |
| 1,1,2-Trichloroethane | 79-00-5 | 2 | ND | | 0.00152 | 0.000304 |
| Tetrachloroethene | 127-18-4 | 2 | ND | | 0.00152 | 0.000395 |
| 2-Hexanone | 591-78-6 | NS | ND | | 0.00152 | 0.000547 |
| Dibromochloromethane | 124-48-1 | 3 | ND | | 0.00152 | 0.000334 |
| 1,2-Dibromoethane (EDB) | 106-93-4 | 0.008 | ND | | 0.00152 | 0.000319 |
| Chlorobenzene | 108-90-7 | 510 | ND | | 0.00152 | 0.000334 |
| Ethylbenzene | 100-41-4 | 7800 | ND | | 0.00152 | 0.000471 |
| Total Xylenes | 1330-20-7 | 12000 | ND | | 0.00304 | 0.00161 |
| Styrene | 100-42-5 | 90 | ND | | 0.00152 | 0.000456 |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| | | | | | | |
|---|---|---|---|---|---|---|
| Bromoform | 75-25-2 | **81** | ND | | 0.00152 | 0.000486 |
| Isopropylbenzene | 98-82-8 | **NS** | ND | | 0.00152 | 0.000623 |
| 1,1,2,2-Tetrachloroethane | 79-34-5 | **1** | ND | | 0.00152 | 0.00035 |
| 1,3-Dichlorobenzene | 541-73-1 | **5300** | ND | | 0.00152 | 0.000471 |
| 1,4-Dichlorobenzene | 106-46-7 | **5** | ND | | 0.00152 | 0.000471 |
| 1,2-Dichlorobenzene | 95-50-1 | **5300** | ND | | 0.00152 | 0.000547 |
| 1,2-Dibromo-3-chloropropane | 96-12-8 | **0.08** | ND | | 0.00152 | 0.00076 |
| 1,2,4-Trichlorobenzene | 120-82-1 | **73** | ND | | 0.00152 | 0.00079 |
| 1,2,3-Trichlorobenzene | 87-61-6 | **NS** | ND | | 0.00152 | 0.00073 |
| 1,1,2-Trichloro-1,2,2-trifluoroethane | 76-13-1 | **NS** | ND | | 0.00152 | 0.000836 |
| Methyl acetate | 79-20-9 | **78000** | ND | | 0.00152 | 0.000882 |
| Cyclohexane | 110-82-7 | **NS** | ND | | 0.00304 | 0.000638 |
| Methylcyclohexane | 108-87-2 | **NS** | ND | | 0.00152 | 0.00076 |
| 1,3-Dichloropropene (cis- and trans-) | 542-75-6 | **2** | ND | | 0.00152 | 0.000395 |
| TOTAL VO's: | | **NS** | ND | | | NA |
| TOTAL TIC's: | | **NS** | ND | | | NA |
| TOTAL VO's & TIC's: | | **NS** | ND | | | NA |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| Semivolatiles - BNA (mg/Kg) | | | Conc | Q | RL | MDL |
|---|---|---|---|---|---|---|
| Benzaldehyde | 100-52-7 | 6100 | ND | | 0.033 | 0.013 |
| Phenol | 108-95-2 | 18000 | ND | | 0.033 | 0.014 |
| Bis(2-chloroethyl) ether | 111-44-4 | 0.4 | ND | | 0.033 | 0.023 |
| 2-Chlorophenol | 95-57-8 | 310 | ND | | 0.033 | 0.014 |
| 2-Methylphenol | 95-48-7 | 310 | ND | | 0.033 | 0.026 |
| Bis(2-chloroisopropyl) ether | 108-60-1 | 23 | ND | | 0.033 | 0.012 |
| 4-Methylphenol ** | 106-44-5 | 31 | ND | | 0.033 | 0.019 |
| N-Nitrosodi-n-propylamine | 621-64-7 | 0.2 | ND | | 0.033 | 0.022 |
| Acetophenone | 98-86-2 | 2 | ND | | 0.033 | 0.011 |
| Hexachloroethane | 67-72-1 | 35 | ND | | 0.033 | 0.013 |
| Nitrobenzene | 98-95-3 | 31 | ND | | 0.033 | 0.029 |
| Isophorone | 78-59-1 | 510 | ND | | 0.033 | 0.021 |
| 2-Nitrophenol | 88-75-5 | NS | ND | | 0.033 | 0.024 |
| 2,4-Dimethylphenol | 105-67-9 | 1200 | ND | | 0.033 | 0.026 |
| Bis(2-chloroethoxy) methane | 111-91-1 | NS | ND | | 0.033 | 0.028 |
| 2,4-Dichlorophenol | 120-83-2 | 180 | ND | | 0.033 | 0.032 |
| Naphthalene | 91-20-3 | 6 | ND | | 0.033 | 0.025 |
| 4-Chloroaniline | 106-47-8 | NS | ND | | 0.033 | 0.031 |
| Hexachlorobutadiene | 87-68-3 | 6 | ND | | 0.033 | 0.032 |
| Caprolactam | 105-60-2 | 31000 | ND | | 0.033 | 0.021 |
| 4-Chloro-3-methylphenol | 59-50-7 | NS | ND | | 0.033 | 0.029 |
| 2-Methylnaphthalene | 91-57-6 | 230 | ND | | 0.033 | 0.027 |
| Hexachlorocyclopentadiene | 77-47-4 | 45 | ND | | 0.033 | 0.010 |
| 2,4,6-Trichlorophenol | 88-06-2 | 19 | ND | | 0.033 | 0.010 |
| 2,4,5-Trichlorophenol | 95-95-4 | 6100 | ND | | 0.033 | 0.013 |
| 1,1'-Biphenyl | 92-52-4 | 3100 | ND | | 0.033 | 0.00989 |
| 2-Chloronaphthalene | 91-58-7 | NS | ND | | 0.033 | 0.031 |
| 2-Nitroaniline | 88-74-4 | 39 | ND | | 0.033 | 0.020 |
| Dimethyl phthalate | 131-11-3 | NS | ND | | 0.033 | 0.00989 |
| 2,6-Dinitrotoluene | 606-20-2 | 0.7 | ND | | 0.033 | 0.019 |
| Acenaphthylene | 208-96-8 | NS | ND | | 0.033 | 0.023 |
| 3-Nitroaniline | 99-09-2 | NS | ND | | 0.033 | 0.00989 |
| Acenaphthene | 83-32-9 | 3400 | ND | | 0.033 | 0.026 |
| 2,4-Dinitrophenol | 51-28-5 | 120 | ND | | 0.033 | 0.013 |
| 4-Nitrophenol | 100-02-7 | NS | ND | | 0.033 | 0.024 |
| 2,4-Dinitrotoluene | 121-14-2 | 0.7 | ND | | 0.033 | 0.029 |
| Dibenzofuran | 132-64-9 | NS | ND | | 0.033 | 0.011 |
| Diethyl phthalate | 84-66-2 | 49000 | ND | | 0.033 | 0.024 |
| Fluorene | 86-73-7 | 2300 | ND | | 0.033 | 0.018 |
| 4-Chlorophenyl phenyl ether | 7005-72-3 | NS | ND | | 0.033 | 0.015 |
| 4-Nitroaniline | 100-01-6 | NS | ND | | 0.033 | 0.021 |
| 1,2,4,5-Tetrachlorobenzene | 95-94-3 | NS | ND | | 0.033 | 0.00989 |
| 2,3,4,6-Tetrachlorophenol | 58-90-2 | NS | ND | | 0.033 | 0.014 |
| 4,6-Dinitro-2-methylphenol | 534-52-1 | 6 | ND | | 0.033 | 0.019 |
| N-Nitrosodiphenylamine | 86-30-6 | 99 | ND | | 0.033 | 0.014 |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| | | | | | | |
|---|---|---|---|---|---|---|
| 4-Bromophenyl phenyl ether | 101-55-3 | **NS** | ND | | 0.033 | 0.019 |
| Hexachlorobenzene | 118-74-1 | **0.3** | ND | | 0.033 | 0.023 |
| Atrazine | 1912-24-9 | **210** | ND | | 0.033 | 0.023 |
| Pentachlorophenol | 87-86-5 | **3** | ND | | 0.033 | 0.014 |
| Phenanthrene | 85-01-8 | **NS** | ND | | 0.033 | 0.022 |
| Anthracene | 120-12-7 | **17000** | ND | | 0.033 | 0.032 |
| Carbazole | 86-74-8 | **24** | ND | | 0.033 | 0.019 |
| Di-n-butyl phthalate | 84-74-2 | **6100** | ND | | 0.033 | 0.023 |
| Fluoranthene | 206-44-0 | **2300** | ND | | 0.033 | 0.013 |
| Pyrene | 129-00-0 | **1700** | ND | | 0.033 | 0.024 |
| Butyl benzyl phthalate | 85-68-7 | **1200** | ND | | 0.033 | 0.021 |
| 3,3'-Dichlorobenzidine | 91-94-1 | **1** | ND | | 0.033 | 0.023 |
| Benzo[a]anthracene | 56-55-3 | **0.6** | ND | | 0.033 | 0.032 |
| Chrysene | 218-01-9 | **62** | ND | | 0.033 | 0.022 |
| Bis(2-ethylhexyl) phthalate | 117-81-7 | **35** | ND | | 0.033 | 0.016 |
| Di-n-octyl phthalate | 117-84-0 | **2400** | ND | | 0.033 | 0.013 |
| Benzo[b]fluoranthene | 205-99-2 | **0.6** | ND | | 0.033 | 0.017 |
| Benzo[k]fluoranthene | 207-08-9 | **6** | ND | | 0.033 | 0.012 |
| Benzo[a]pyrene | 50-32-8 | **0.2** | ND | | 0.033 | 0.018 |
| Indeno[1,2,3-cd]pyrene | 193-39-5 | **0.6** | ND | | 0.033 | 0.016 |
| Dibenz[a,h]anthracene | 53-70-3 | **0.2** | ND | | 0.033 | 0.020 |
| Benzo[g,h,i]perylene | 191-24-2 | **380000** | ND | | 0.033 | 0.010 |
| Dinitrotoluene (2,4- and 2,6-) | 25321-14-6 | **0.7** | ND | | 0.033 | 0.029 |
| TOTAL BNA'S: | | **NS** | ND | | | NA |
| TOTAL TIC's: | | **NS** | ND | | | NA |
| TOTAL BNA'S & TIC's: | | **NS** | ND | | | NA |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| PCB's (mg/Kg) | | | Conc | Q | RL | MDL |
|---|---|---|---|---|---|---|
| Aroclor-1016 | 12674-11-2 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1221 | 11104-28-2 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1232 | 11141-16-5 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1242 | 53469-21-9 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1248 | 12672-29-6 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1254 | 11097-69-1 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1260 | 11096-82-5 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1262 | 37324-23-5 | NS | ND | | 0.00165 | 0.00066 |
| Aroclor-1268 | 11100-14-4 | NS | ND | | 0.00165 | 0.00066 |
| PCBs | 1336-36-3 | 0.2 | ND | | 0.00165 | 0.00066 |

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| Pesticides (mg/Kg) | | | Conc | Q | RL | MDL |
|---|---|---|---|---|---|---|
| alpha-BHC | 319-84-6 | **0.1** | ND | | 0.00033 | 0.000165 |
| beta-BHC | 319-85-7 | **0.4** | ND | | 0.00033 | 0.000165 |
| gamma-BHC (Lindane) | 58-89-9 | **0.4** | ND | | 0.00033 | 0.000165 |
| delta-BHC | 319-86-8 | **NS** | ND | | 0.00033 | 0.000165 |
| Heptachlor | 76-44-8 | **0.1** | ND | | 0.00033 | 0.000165 |
| Aldrin | 309-00-2 | **0.04** | ND | | 0.00033 | 0.000165 |
| Heptachlor epoxide | 1024-57-3 | **0.07** | ND | | 0.00033 | 0.000165 |
| Endosulfan I | 959-98-8 | **NS** | ND | | 0.00033 | 0.000165 |
| 4,4'-DDE | 72-55-9 | **2** | ND | | 0.00033 | 0.000165 |
| Dieldrin | 60-57-1 | **0.04** | ND | | 0.00033 | 0.000165 |
| Endrin | 72-20-8 | **23** | ND | | 0.00033 | 0.000165 |
| Endosulfan II | 33213-65-9 | **NS** | ND | | 0.00033 | 0.000165 |
| 4,4'-DDD | 72-54-8 | **3** | ND | | 0.00033 | 0.000165 |
| Endrin aldehyde | 7421-93-4 | **NS** | ND | | 0.00033 | 0.000165 |
| Endosulfan sulfate | 1031-07-8 | **470** | ND | | 0.00033 | 0.000165 |
| 4,4'-DDT | 50-29-3 | **2** | ND | | 0.00033 | 0.000165 |
| Endrin ketone | 53494-70-5 | **NS** | ND | | 0.00033 | 0.000165 |
| Methoxychlor | 72-43-5 | **390** | ND | | 0.00033 | 0.000165 |
| alpha-Chlordane | 5103-71-9 | **NS** | ND | | 0.00033 | 0.000165 |
| gamma-Chlordane | 5103-74-2 | **NS** | ND | | 0.00033 | 0.000165 |
| Toxaphene | 8001-35-2 | **0.6** | ND | | 0.00413 | 0.00198 |
| Endosulfan (I and II) | 115-29-7 | **470** | ND | | 0.00033 | 0.000165 |
| Chlordane (alpha and gamma) | 57-74-9 | **0.2** | ND | | 0.00033 | 0.000165 |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| Hydrocarbons (mg/Kg) | | | Conc | Q | RL | MDL |
|---|---|---|---|---|---|---|
| C9-C40 | IALC9C40 | NS | ND | | 36.0 | 9.00 |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| Metals (mg/Kg) | | | Conc | Q | RL | MDL |
|---|---|---|---|---|---|---|
| Aluminum | 7429-90-5 | **78000** | 4820 | | 10.0 | 5.00 |
| Antimony | 7440-36-0 | **31** | ND | | 1.00 | 0.250 |
| Arsenic | 7440-38-2 | **19** | 1.06 | | 0.500 | 0.250 |
| Barium | 7440-39-3 | **16000** | 47.1 | | 10.0 | 2.50 |
| Beryllium | 7440-41-7 | **16** | 0.549 | | 0.500 | 0.200 |
| Cadmium | 7440-43-9 | **78** | ND | | 0.500 | 0.125 |
| Calcium | 7440-70-2 | **NS** | 4570 | | 50.0 | 25.0 |
| Chromium | 7440-47-3 | **NS** | 14.2 | | 2.00 | 0.500 |
| Cobalt | 7440-48-4 | **1600** | 5.75 | | 2.00 | 0.500 |
| Copper | 7440-50-8 | **3100** | 16.3 | | 2.00 | 0.500 |
| Iron | 7439-89-6 | **NS** | 17300 | | 25.0 | 12.5 |
| Lead | 7439-92-1 | **400** | 1.78 | | 0.500 | 0.125 |
| Magnesium | 7439-95-4 | **NS** | 3680 | | 50.0 | 12.5 |
| Manganese | 7439-96-5 | **11000** | 170 | | 1.00 | 0.250 |
| Mercury | 7439-97-6 | **23** | ND | | 0.012 | 0.00594 |
| Nickel | 7440-02-0 | **1600** | 7.69 | | 1.00 | 0.500 |
| Potassium | 7440-09-7 | **NS** | 1960 | | 50.0 | 12.5 |
| Selenium | 7782-49-2 | **390** | ND | | 2.00 | 1.00 |
| Silver | 7440-22-4 | **390** | ND | | 0.500 | 0.125 |
| Sodium | 7440-23-5 | **NS** | 126 | | 100 | 25.0 |
| Thallium | 7440-28-0 | **5** | 0.147 | J | 0.500 | 0.125 |
| Vanadium | 7440-62-2 | **78** | 19.3 | | 2.00 | 0.500 |
| Zinc | 7440-66-6 | **23000** | 19.0 | | 2.00 | 2.00 |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

S S Environmental
Project Name: MT. HOPE
IAL SDG No:E12-05656

| General Analytical | | | Conc | Q | RL | MDL |
|---|---|---|---|---|---|---|
| Hexavalent Chromium-mg/Kg | 18540-29-9 | **240** | ND | | 1.00 | 0.236 |
| Cyanide, Total-mg/Kg | 57-12-5 | **1600** | ND | | 1.00 | 0.700 |
| pH/Corrosivity-SU | SRP 6 | **NS** | 8.59 | | NA | NA |
| | | | | | | |
| NJDEP Soil Remediation Standards: Remediation Standards N.J.A.C. 7:26D, June 2008 | | | | | | |
| **BOLD Conc** | Indicates a concentration that exceeds applicable criteria. | | | | | |
| **BOLD RL** | Indicates RL that exceeds applicable criteria. | | | | | |
| **BOLD MDL** | Indicates MDL that exceeds applicable criteria. | | | | | |
| NS = No Standard Available | | | | | | |
| ND = Analyzed for but Not Detected at the MDL | | | | | | |
| J = The concentration was detected at a value below the RL and above the MDL | | | | | | |

Standards are based upon published regulatory information.
Users are encouraged to consult appropriate regulatory sources for current values and updates.
IAL assumes no responsibility for the accuracy of these values.

EDD created on 6/15/12

Integrated Analytical Labs
273 Franklin Road
Randolph, NJ 07869

Contact Us: 973-361-4252
Fax: 973-989-5288
Web: www.ialonline.com

| CUSTOMER INFO | REPORTING INFO |
|---|---|
| Company: STS | REPORT TO: |
| Address: 98 Sand Park Rd Cedar Grove, NJ 07009 | Address: Same |
| Telephone #: | Attn: |
| Fax #: | FAX # |
| Project Manager: Y. Arden, PhD | INVOICE TO: |
| EMAIL Address: | Address: Same |
| Sampler: EO | |
| Project Name: Mt. Hope | |
| Project Location (State): NJ | Attn: |
| Bottle Order #: | PO # 12-121 |
| Quote # : | |

Turnaround Time (starts the following day if samples rec'd at lab > 5PM)

*Lab notification is required for RUSH TAT prior to sample arrival. RUSH TAT IS NOT GUARANTEED WITHOUT LAB APPROVAL. **RUSH SURCHARGES WILL APPLY IF ABLE TO ACCOMMODATE

PHC - MUST CHOOSE

NJ EPH DRO (5 day TAT) NJ EPH Fractionated (5 day TAT)

NJ EPH - C40 (5 day TAT)

~~DRO-8015~~ (3-5 day TAT) QAM025 (5 day TAT)

Verbal/Fax: Std 2 wk unless otherwise specified

24 hr** 48 hr** 72 hr** 96 hr** 1 wk**

Other** (specify): 5 DAY

Hard Copy: Std 3 week * Other - call for price

Rush TAT Charge **: 24 hr - 100%... 48 hr - 75%.... 72 hr - 50%.... 96 hr - 35%.... 5 day - 25%.... 6-9 day 10%

Report Format: Results Only; Reduced; Regulatory - 15% Surcharge applies; Other (describe)

EDDs: SRP format; lab approved custom EDD; NO EDD/CD REQ'D

Cooler Temp 4 °C

## SAMPLE INFORMATION

Sample Matrix

DW - Drinking Water AQ - Aqueous WW - Waste Water
OI - Oil LIQ - Liquid (Specify) OT - Other (Specify)
S - Soil SL - Sludge SOL - Solid W - Wipe

ANALYTICAL PARAMETERS

# BOTTLES & PRESERVATIVES

| Client ID | Depth (ft only) | Sampling Date | Sampling Time | Matrix | # container | IAL # | TAL TCL + 30 | EPH | pH, Cr+6 | HCL | HNO3 | MeOH | Other | None | Encore |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 12-121 | | 6/8/12 | | OT | 6 | | ✓ | ✓ | ✓ | | | 1 | 2 | 3 | |

Mod # 13875 # 7642 # 7670

Known Hazard: Yes or No Describe:

Conc. Expected: Low Med High

MDL Req: GWQS (11/05) - SRS - SRS/IGW - SRS Residential - OTHER (SEE COMMENTS)

***Please print legibly and fill out completely. Samples cannot be processed and the turnaround time will not start until any ambiguities have been resolved.***

Carrier (check one): _____ IAL Courier _____ Client Courier _____ FedEx/UPS

| Signature/Company | Date | Time | Signature/Company | Date | Time |
|---|---|---|---|---|---|
| Relinquished by: | 6/8/12 | 2:45 | Received by: Kim James | 6/8/12 | 2:45 |
| Relinquished by: | | | Received by: | | |
| Relinquished by: | | | Received by: | | |
| Relinquished by: | | | Received by: | | |
| Relinquished by: | | | Received by: | | |

Comments: OT * - Rock Lines

Lab Case # 05656

PAGE: of

LAB COPIES - WHITE & YELLOW; CLIENT COPY - PINK

# INTEGRATED ANALYTICAL LABORATORIES, LLC

## SAMPLE RECEIPT VERIFICATION

CASE NO: **E 12** **05656** CLIENT: S+S

COOLER TEMPERATURE: 2° - 6°C: ✓ ( See Chain of Custody)

**Comments**

COC: (COMPLETE) / INCOMPLETE

**KEY**

✓ = YES/NA
✗ = NO

| | | Comments |
|---|---|---|
| ✓ | Bottles Intact | |
| ✓ | no-Missing Bottles | |
| ✓ | no-Extra Bottles | |
| ✓ | Sufficient Sample Volume | |
| ✓ | no-headspace/bubbles in VOs | |
| ✓ | Labels intact/correct | |
| ✓ | pH Check (exclude VOs)[1] | |
| ✓ | Correct bottles/preservative | |
| ✓ | Sufficient Holding/Prep Time[1] | |
| | Sample to be Subcontracted | |
| ✓ | **Chain of Custody is Clear** | |

[1] All samples with "Analyze Immediately" holding times will be analyzed by this laboratory past the holding time. This includes but is not limited to the following tests: pH, Temperature, Free Residual Chlorine, Total Residual Chlorine, Dissolved Oxygen, Sulfite.

ADDITIONAL COMMENTS:

SAMPLE(S) VERIFIED BY: INITIAL [ ] DATE 6/8/12

**CORRECTIVE ACTION REQUIRED:** **YES** [ ] (SEE BELOW) **NO** [ ]

If COC is **NOT** clear, ***STOP*** until you get client to authorize/clarify work.

CLIENT NOTIFIED: YES [ ] Date/ Time: _____ NO [ ]

PROJECT CONTACT:

SUBCONTRACTED LAB:

DATE SHIPPED:

ADDITIONAL COMMENTS:

VERIFIED/TAKEN BY: INITIAL KJ DATE 6/8/12

REV 03/2009

# CONFIRMATION FOR PROJECT

## E12-05656: MT. HOPE

**To:** Dr. Yilmaz Arhan
S & S Environmental
Fax: 1(973) 239-8380
EMail: angelal@sorlabs.com;Alig@sorlabs.com

**Report To**

S & S Environmental
98 Sand Park Road
Cedar Grove, NJ 07009
Attn: Dr. Yilmaz Arhan

**Bill To**

S & S Environmental
98 Sand Park Road
Cedar Grove, NJ 07009
Attn: Dr. Yilmaz Arhan

| Report Format | P.O. # | Received At Lab | TPHC Due | Verbal Due | Hardcopy Due |
|---|---|---|---|---|---|
| Reduced | | Jun 08, 2012 @ 14:45 | NA | Jun 15, 2012 | Jun 29, 2012 * |

* Any ***Conditional or Hold*** status will delay final hardcopy report sent date.

**Diskette Req.** Not Required

**** QC Requirement (must meet):** NJ IGW

| Lab ID | Client Sample ID | Depth | Sampling Time | Matrix | Unit | Field pH/Temp |
|---|---|---|---|---|---|---|
| 05656-001 | 12-121 | NA | 06/08/12 | Solid | mg/Kg (ppm) | |

| Sample # | Test | Status | QA Method | TAT | Holding Time Expires |
|---|---|---|---|---|---|
| 001 | TCL VO+10 | Analyze | 8260B | RUSH 1 WK | 6/22/2012 |
| | TCL BNA+20 | Analyze | 8270C | RUSH 1 WK | 6/22/2012 |
| | TCL Pesticides | Analyze | 8081A | RUSH 1 WK | 6/22/2012 |
| | NJ-EPH-Fractionated | Hold | Method 10.08 Re | RUSH 1 WK | 6/22/2012 |
| | NJ-EPH-C40 | Analyze | Method 10.08 Re | RUSH 1 WK | 6/22/2012 |
| | TCL PCB-9 | Analyze | 8082 | RUSH 1 WK | 6/22/2012 |
| | TAL Metals | Analyze | 6020/7471A | RUSH 1 WK | 7/6/2012 |
| | Cyanide, Total | Analyze | 9012B | RUSH 1 WK | 6/22/2012 |
| | Cr-VI (Hexavalent Chromium) | Analyze | 3060A/7196A | RUSH 1 WK | 7/8/2012 |
| | pH/Corrosivity | Analyze | 9045C | RUSH 1 WK | 7/6/2012 |

**Project Notes:**

**NOTE 1 taken by Ellen on 06/08/2012 03:26**
AS PER YILMAZ A., EPH = NJEPH-C40.



273 Franklin Road
Randolph, NJ 07869
Phone: 973 361 4252
Fax: 973 989 5288

IAL is a NELAC New Jersey Certified Lab (14751) and maintains certification in Connecticut (PH-0699), New York (11402), Rhode Island (00126), Florida (E87670) and in the Department of Navy IR QA Program

NOTE: THIS IS A COURTESY COPY OF THIS RULE. ALL OF THE DEPARTMENT'S RULES ARE COMPILED IN TITLE 7 OF THE NEW JERSEY ADMINISTRATIVE CODE.

APPENDIX 1 - SOIL REMEDIATION STANDARDS TABLES

**Table 1A - Residential Direct Contact Health Based Criteria and Soil Remediation Standards (mg/kg)**

| Contaminant | CAS No. | Ingestion-Dermal Health Based Criterion | Inhalation Health Based Criterion | Soil PQL | Residential Direct Contact Soil Remediation Standard |
|---|---|---|---|---|---|
| Acenaphthene | 83-32-9 | 3,400 | NA | 0.2 | 3,400 |
| Acenaphthylene | 208-96-8 | NA | NA | 0.2 | NA |
| Acetone (2-Propanone) | 67-64-1 | 70,000 | NA | 0.01 | 70,000 |
| Acetophenone | 98-86-2 | 6,100 | 2 | 0.2 | 2 |
| Acrolein | 107-02-8 | 39 | 0.5 | 0.5 | 0.5 |
| Acrylonitrile | 107-13-1 | 1 | 0.9 | 0.5 | 0.9 |
| Aldrin | 309-00-2 | 0.04 | 5 | 0.002 | 0.04 |
| Aluminum | 7429-90-5 | 78,000 | NA | 20 | 78,000 |
| Anthracene | 120-12-7 | 17,000 | 380,000 | 0.2 | 17,000 |
| Antimony | 7440-36-0 | 31 | 360,000 | 6 | 31 |
| Arsenic | 7440-38-2 | 0.4 | 980 | 1 | 19* |
| Atrazine | 1912-24-9 | 210 | NA | 0.2 | 210 |
| Barium | 7440-39-3 | 16,000 | 910,000 | 20 | 16,000 |
| Benzaldehyde | 100-52-7 | 6,100 | NA | 0.2 | 6100 |
| Benzene | 71-43-2 | 3 | 2 | 0.005 | 2 |
| Benzidine | 92-87-5 | 0.002 | 0.004 | 0.7 | 0.7 |
| Benzo(a)anthracene (1,2-Benzanthracene) | 56-55-3 | 0.6 | 38,000 | 0.2 | 0.6 |
| Benzo(a)pyrene | 50-32-8 | 0.06 | 3,800 | 0.2 | 0.2 |
| Benzo(b)fluoranthene (3,4-Benzofluoranthene) | 205-99-2 | 0.6 | 38,000 | 0.2 | 0.6 |
| Benzo(ghi)perylene | 191-24-2 | NA | 380,000 | 0.2 | 380,000 |
| Benzo(k)fluoranthene | 207-08-9 | 6 | 38,000 | 0.2 | 6 |
| Beryllium | 7440-41-7 | 16 | 1,800 | 0.5 | 16 |
| 1,1'-Biphenyl | 92-52-4 | 3,100 | NA | 0.2 | 3,100 |
| Bis(2-chloroethyl)ether | 111-44-4 | 0.4 | 0.6 | 0.2 | 0.4 |
| Bis(2-chloroisopropyl)ether | 108-60-1 | 2,400 | 23 | 0.2 | 23 |
| Bis(2-ethylhexyl) phthalate | 117-81-7 | 35 | NA | 0.2 | 35 |
| Bromodichloromethane (Dichlorobromomethane) | 75-27-4 | 10 | 1 | 0.005 | 1 |
| Bromoform | 75-25-2 | 81 | 98 | 0.005 | 81 |
| Bromomethane (Methyl bromide) | 74-83-9 | 110 | 25 | 0.005 | 25 |
| bromide) | | | | | |
| 2-Butanone (Methyl ethyl ketone) (MEK) | 78-93-3 | 3,100 | NA | 0.01 | 3,100 |
| Butyl benzyl phthalate | 85-68-7 | 1,200 | NA | 0.2 | 1,200 |
| Cadmium | 7440-43-9 | 78 | 1,000 | 0.5 | 78 |
| Caprolactam | 105-60-2 | 31,000 | NA | 0.2 | 31,000 |
| Carbazole | 86-74-8 | 24 | 740,000 | 0.2 | 24 |
| Carbon disulfide | 75-15-0 | 7,800 | NA | 0.5 | 7,800 |
| Carbon tetrachloride | 56-23-5 | 7 | 0.6 | 0.005 | 0.6 |

NOTE: THIS IS A COURTESY COPY OF THIS RULE. ALL OF THE DEPARTMENT'S RULES ARE COMPILED IN TITLE 7 OF THE NEW JERSEY ADMINISTRATIVE CODE.

| Contaminant | CAS No. | Ingestion-Dermal Health Based Criterion | Inhalation Health Based Criterion | Soil PQL | Residential Direct Contact Soil Remediation Standard |
|---|---|---|---|---|---|
| Chlordane (alpha and gamma) | 57-74-9 | 0.2 | 42,000 | 0.002 | 0.2 |
| Chlorobenzene | 108-90-7 | 510 | NA | 0.005 | 510 |
| Chloroethane (Ethyl chloride) | 75-00-3 | 220 | NA | 0.005 | 220 |
| Chloroform | 67-66-3 | 780 | 0.6 | 0.005 | 0.6 |
| Chloromethane (Methyl chloride) | 74-87-3 | NA | 4 | 0.005 | 4 |
| 2-Chlorophenol (o-Chlorophenol) | 95-57-8 | 310 | 910 | 0.2 | 310 |
| Chrysene | 218-01-9 | 62 | 380,000 | 0.2 | 62 |
| Cobalt | 7440-48-4 | 1,600 | 9,100 | 5 | 1,600 |
| Copper | 7440-50-8 | 3,100 | NA | 3 | 3,100 |
| Cyanide | 57-12-5 | 1,600 | NA | 3 | 1,600 |
| 4,4'-DDD | 72-54-8 | 3 | 61,000 | 0.003 | 3 |
| 4,4'-DDE | 72-55-9 | 2 | 670 | 0.003 | 2 |
| 4,4'-DDT | 50-29-3 | 2 | 44,000 | 0.003 | 2 |
| Dibenz(a,h)anthracene | 53-70-3 | 0.06 | 3,500 | 0.2 | 0.2 |
| Dibromochloromethane (Chlorodibromomethane) | 124-48-1 | 8 | 3 | 0.005 | 3 |
| 1,2-Dibromo-3-chloropropane | 96-12-8 | 0.3 | 0.08 | 0.005 | 0.08 |
| 1,2-Dibromoethane | 106-93-4 | 0.008 | 0.1 | 0.005 | 0.008 |
| 1,2-Dichlorobenzene (o-Dichlorobenzene) | 95-50-1 | 5,300 | NA | 0.005 | 5,300 |
| 1,3-Dichlorobenzene (m-Dichlorobenzene) | 541-73-1 | 5,300 | NA | 0.005 | 5,300 |
| 1,4-Dichlorobenzene (p-Dichlorobenzene) | 106-46-7 | 610 | 5 | 0.005 | 5 |
| 3,3'-Dichlorobenzidine | 91-94-1 | 1 | 3 | 0.2 | 1 |
| Dichlorodifluoromethane | 75-71-8 | 16,000 | 490 | 0.005 | 490 |
| 1,1-Dichloroethane | 75-34-3 | 510 | 8 | 0.005 | 8 |
| 1,2-Dichloroethane | 107-06-2 | 5 | 0.9 | 0.005 | 0.9 |
| 1,1-Dichloroethene | 75-35-4 | 11 | 61 | 0.005 | 11 |
| 1,2-Dichloroethene (cis) (c-1,2-Dichloroethylene) | 156-59-2 | 780 | 230 | 0.005 | 230 |
| 1,2-Dichloroethene (trans) (t-1,2-Dichloroethylene) | 156-60-5 | 1,300 | 300 | 0.005 | 300 |
| 2,4-Dichlorophenol | 120-83-2 | 180 | NA | 0.2 | 180 |
| 1,2-Dichloropropane | 78-87-5 | 9 | 2 | 0.005 | 2 |
| 1,3-Dichloropropene (cis and trans) | 542-75-6 | 6 | 2 | 0.005 | 2 |
| Dieldrin | 60-57-1 | 0.04 | 1 | 0.003 | 0.04 |
| Diethyl phthalate | 84-66-2 | 49,000 | NA | 0.2 | 49,000 |
| 2,4-Dimethyl phenol | 105-67-9 | 1,200 | NA | 0.2 | 1,200 |
| Di-n-butyl phthalate | 84-74-2 | 6,100 | NA | 0.2 | 6,100 |
| 4,6-Dinitro-2-methylphenol (4,6-Dinitro-o-cresol) | 534-52-1 | 6 | 730,000 | 0.3 | 6 |
| 2,4-Dinitrophenol | 51-28-5 | 120 | NA | 0.3 | 120 |
| 2,4-Dinitrotoluene | 121-14-2 | 0.7 | 6 | 0.2 | 0.7 |
| 2,6-Dinitrotoluene | 606-20-2 | 0.7 | 2 | 0.2 | 0.7 |
| 2,4-Dinitrotoluene/2,6-Dinitrotoluene (mixture) | 25321-14-6 | 0.7 | NA | 0.2 | 0.7 |
| Di-n-octyl phthalate | 117-84-0 | 2,400 | NA | 0.2 | 2,400 |
| 1,2-Diphenylhydrazine | 122-66-7 | 0.6 | 5 | 0.7 | 0.7 |

NOTE: THIS IS A COURTESY COPY OF THIS RULE. ALL OF THE DEPARTMENT'S RULES ARE COMPILED IN TITLE 7 OF THE NEW JERSEY ADMINISTRATIVE CODE.

| Contaminant | CAS No. | Ingestion-Dermal Health Based Criterion | Inhalation Health Based Criterion | Soil PQL | Residential Direct Contact Soil Remediation Standard |
|---|---|---|---|---|---|
| Endosulfan I and Endosulfan II (alpha and beta) | 115-29-7 | 470 | NA | 0.003 | 470 |
| Endosulfan sulfate | 1031-07-8 | 470 | NA | 0.003 | 470 |
| Endrin | 72-20-8 | 23 | NA | 0.003 | 23 |
| Ethyl benzene | 100-41-4 | 7,800 | NA | 0.005 | 7,800 |
| Fluoranthene | 206-44-0 | 2,300 | NA | 0.2 | 2,300 |
| Fluorene | 86-73-7 | 2,300 | NA | 0.2 | 2,300 |
| alpha-HCH (alpha-BHC) | 319-84-6 | 0.1 | 0.7 | 0.002 | 0.1 |
| beta-HCH (beta-BHC) | 319-85-7 | 0.4 | 8,000 | 0.002 | 0.4 |
| Heptachlor | 76-44-8 | 0.1 | 6 | 0.002 | 0.1 |
| Heptachlor epoxide | 1024-57-3 | 0.07 | 5 | 0.002 | 0.07 |
| Hexachlorobenzene | 118-74-1 | 0.3 | 1 | 0.2 | 0.3 |
| Hexachloro-1,3-butadiene | 87-68-3 | 6 | 12 | 0.2 | 6 |
| Hexachlorocyclopentadiene | 77-47-4 | 370 | 45 | 0.2 | 45 |
| Hexachloroethane | 67-72-1 | 35 | 83 | 0.2 | 35 |
| Indeno(1,2,3-cd)pyrene | 193-39-5 | 0.6 | 38,000 | 0.2 | 0.6 |
| Isophorone | 78-59-1 | 510 | NA | 0.2 | 510 |
| Lead | 7439-92-1 | 400 | 44,000 | 1 | 400 |
| Lindane (gamma-HCH) (gamma-BHC) | 58-89-9 | 0.4 | 3 | 0.002 | 0.4 |
| Manganese | 7439-96-5 | 11,000 | 91,000 | 2 | 11,000 |
| Mercury | 7439-97-6 | 23 | 27 | 0.1 | 23 |
| Methoxychlor | 72-43-5 | 390 | NA | 0.02 | 390 |
| Methyl acetate | 79-20-9 | 78,000 | NA | 0.005 | 78,000 |
| Methylene chloride (Dichloromethane) | 75-09-2 | 46 | 34 | 0.005 | 34 |
| 2-Methylnaphthalene | 91-57-6 | 230 | NA | 0.17 | 230 |
| 2-Methylphenol (o-Creosol) | 95-48-7 | 310 | NA | 0.2 | 310 |
| 4-Methylphenol (p-Creosol) | 106-44-5 | 31 | NA | 0.2 | 31 |
| Methyl tert-butyl ether (MTBE) | 1634-04-4 | 780 | 110 | 0.005 | 110 |
| Naphthalene | 91-20-3 | 2,400 | 6 | 0.2 | 6 |
| Nickel (Soluble salts) | 7440-02-0 | 1,600 | 360,000 | 4 | 1,600 |
| 2-Nitroaniline | 88-74-4 | NA | 39 | 0.3 | 39 |
| Nitrobenzene | 98-95-3 | 31 | 160 | 0.2 | 31 |
| N-Nitrosodimethylamine | 62-75-9 | 0.01 | 0.02 | 0.7 | 0.7 |
| N-Nitrosodi-n-propylamine | 621-64-7 | 0.07 | 0.2 | 0.2 | 0.2 |
| N-Nitrosodiphenylamine | 86-30-6 | 99 | NA | 0.2 | 99 |
| Pentachlorophenol | 87-86-5 | 3 | 590 | 0.3 | 3 |
| Phenanthrene | 85-01-8 | NA | NA | 0.2 | NA |
| Phenol | 108-95-2 | 18,000 | NA | 0.2 | 18,000 |
| Polychlorinated biphenyls (PCBs) | 1336-36-3 | 0.2 | 20 | 0.03 | 0.2 |
| Pyrene | 129-00-0 | 1,700 | NA | 0.2 | 1,700 |
| Selenium | 7782-49-2 | 390 | NA | 4 | 390 |
| Silver | 7440-22-4 | 390 | NA | 1 | 390 |

NOTE: THIS IS A COURTESY COPY OF THIS RULE. ALL OF THE DEPARTMENT'S RULES ARE COMPILED IN TITLE 7 OF THE NEW JERSEY ADMINISTRATIVE CODE.

| Contaminant | CAS No. | Ingestion-Dermal Health Based Criterion | Inhalation Health Based Criterion | Soil PQL | Residential Direct Contact Soil Remediation Standard |
|---|---|---|---|---|---|
| Styrene | 100-42-5 | 16,000 | 90 | 0.005 | 90 |
| Tertiary butyl alcohol (TBA) | 75-65-0 | 1,400 | 4,800 | 0.1 | 1,400 |
| 1,1,2,2-Tetrachloroethane | 79-34-5 | 10 | 1 | 0.005 | 1 |
| Tetrachloroethene (PCE) (Tetrachloroethylene) | 127-18-4 | 8 | 2 | 0.005 | 2 |
| Thallium | 7440-28-0 | 5 | 360,000 | 3 | 5 |
| Toluene | 108-88-3 | 6,300 | NA | 0.005 | 6,300 |
| Toxaphene | 8001-35-2 | 0.6 | 70 | 0.2 | 0.6 |
| 1,2,4-Trichlorobenzene | 120-82-1 | 73 | NA | 0.005 | 73 |
| 1,1,1-Trichloroethane | 71-55-6 | 290 | NA | 0.005 | 290 |
| 1,1,2-Trichloroethane | 79-00-5 | 31 | 2 | 0.005 | 2 |
| Trichloroethene (TCE) (Trichloroethylene) | 79-01-6 | 21 | 7 | 0.005 | 7 |
| Trichlorofluoromethane | 75-69-4 | 23,000 | NA | 0.005 | 23,000 |
| 2,4,5-Trichlorophenol | 95-95-4 | 6,100 | NA | 0.2 | 6,100 |
| 2,4,6-Trichlorophenol | 88-06-2 | 19 | 340 | 0.2 | 19 |
| Vanadium | 7440-62-2 | 78 | NA | 5 | 78 |
| Vinyl chloride | 75-01-4 | 2 | 0.7 | 0.005 | 0.7 |
| Xylenes | 1330-20-7 | 12,000 | NA | 0.005 | 12,000 |
| Zinc | 7440-66-6 | 23,000 | NA | 6 | 23,000 |

NA = Standard not available

* The direct contact standard for arsenic is based on natural background

# CHROMIUM SOIL CLEANUP CRITERIA

September 2008 Revised April 2010[1]

The Department did not develop soil remediation standards for trivalent or hexavalent chromium as part of its Remediation Standards rules at N.J.A.C. 7:26D. The Department was awaiting the release of the final report from the National Toxicology Program (NTP) study evaluating hexavalent chromium as an oral carcinogen prior to proposing soil remediation standards. The NTP report was released in August 2008. The Department is reviewing the report and will make a determination regarding the adoption of remediation standards for chromium. Until such time, the Department will continue to use the following soil cleanup criteria for trivalent and hexavalent chromium as guidance.

## Soil Cleanup Criteria for Chromium

| Residential (mg/kg) | | | | | | |
|---|---|---|---|---|---|---|
| **Contaminant** | **CAS No.** | **Ingestion-Dermal** | **Inhalation** | **Allergic Contact Dermatitis (ACD)** | **Soil PQL** | **Residential Criterion** |
| Trivalent Chromium | 16065-83-1 | 120,000 | NA | NA | 2 | 120,000 |
| Hexavalent Chromium | 18540-29-9 | 240 | 270 | Site-specific determination | 2 | 240 or ACD value whichever is lower |

| Non-Residential (mg/kg) | | | | | | |
|---|---|---|---|---|---|---|
| **Contaminant** | **CAS No.** | **Ingestion-Dermal** | **Inhalation** | **Allergic Contact Dermatitis** | **Soil PQL** | **Non-Residential Criterion** |
| Trivalent Chromium | 16065-83-1 | NA | NA | NA | 2 | Not Regulated |
| Hexavalent Chromium | 18540-29-9 | 6,100 | 20 | Site-specific determination | 2 | 20 |

NA = Standard not available

[1] This revision corrects the CAS numbers that were mistakenly used for trivalent and hexavalent chromium in the September 2008 version. The CAS numbers were inadvertently switched.

Impact to ground water soil remediation standards must be developed on a site-specific basis for chromium. For Class II ground water, the ground water quality standard is 70 ug/l measured as total chromium but assuming that it is all in the form of hexavalent chromium.

In addition to the cleanup criteria listed above, all remedial actions at sites that have hexavalent chromium must comply with Commissioner Jackson's memorandum dated February 8, 2007. A copy of this memorandum can be found on the Department web site at http://www.state.nj.us/dep/dsr/chromium/crmorlift200702.pdf

More information about the Department chromium work group and chromium research efforts are available on the NJDEP web site at http://www.state.nj.us/dep/dsr/chromium .

# 5 - Gradation Curves for Roadway Stone, Sand, Filter Material, and Armor Stone (Mount Hope Quarry)

# TILCON-NY Mt. Hope Quarry

Fax 973-659-3978

625 Mount Hope Rd. • Wharton, N.J. 07946 • 973-366-7741


Stone for Roadways (staging areas)


## Typical Gradation,Fine QP (3/4")

| Project |
|---|
| SA-7 Sediment Remediation<br>Jersey City, Kellog Street |

| Contractor |
|---|
| Sevenson Enviromental |

| | |
|---|---|
| **Sp. Gr** | **2.66** |
| **Loose** | **98** |
| **Rodded** | **110** |

| | Typical | Prod. Target | |
|---|---|---|---|
| **1 1/2"** | **100** | 100 | 100 |
| **1"** | **100** | 100 | 100 |
| **3/4** | **98** | 90 | 100 |
| **1/2** | **80** | 55 | 90 |
| **3/8** | **65** | 25 | 80 |
| **#4** | **52** | 25 | 60 |
| **#50** | **26** | 5 | 35 |
| **#200** | **14** | | 20 |




Tilcon Inc confirms that Fine QP (3/4") available at Mt. Hope Quarry conforms to section 901 of the ***New Jersey Department of Transportation StandardSpecifications for Road and Bridge Construction.*** The material is defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mount Hope Road, Block 20001-Lot 6.01 Wharton Borough, Morris County NJ. The material is identified on the job with Tilcon delivery tickets.

The unit weights and voids are for process control and should be verified by the contractor before use.

TILCON
an Oldcastle company

Proposed 0.75" Armor Stone

# Product Quality Summary Report

**Period** 01/01/2011 - 12/31/2011

**Plant** **06000418-Mt. Hope Quarry**

| | Product | ASTM #5 | 005 Grits |
|---|---|---|---|
| | **Specification** | ASTM 5 | Grits |
| 1 1/2" (37.5mm) | | 100.0 | |
| 1" (25mm) | | 93.5 | |
| 3/4" (19mm) | | 47.7 | |
| 1/2" (12.5mm) | | 5.6 | |
| 3/8" (9.5mm) | | 2.9 | 100 |
| #4 (4.75mm) | | | 100 |
| #8 (2.36mm) | | | 75 |
| #16 (1.18mm) | | | 42 |
| #30 (0.6mm) | | | 24 |
| Pan | | 0.00 | 0.0 |

Sand Layer

TILCON
an Oldcastle company

1.0" Armor Stone

# Product Quality Summary Report

**Period** 01/01/2012 - 05/11/2012
**Plant** **06000418-Mt. Hope Quarry**

| | Product | 1 1/2" ASTM 4 | 1015002 washed 3/4" |
|---|---|---|---|
| | **Specification** | ASTM 4 | ASTM 57 |
| 2" (50mm) | | 100 | |
| 1 1/2" (37.5mm) | | 100 | |
| 1" (25mm) | | 39 | 99.8 |
| 3/4" (19mm) | | 4 | 92.4 |
| 1/2" (12.5mm) | | 1 | 30.9 |
| 3/8" (9.5mm) | | 1 | 5.7 |
| #4 (4.75mm) | | | 1.1 |
| #8 (2.36mm) | | | 0.6 |
| Pan | | 0.0 | 0.00 |

Filter Layer

# TILCON-NY Mt. Hope Quarry

Fax 973-659-3978

625 Mount Hope Rd. • Wharton, N.J. 07946 • 973-366-7741


1.5", 1.6", and 2.0" Armor Stone


## Typical Gradation,#1 (3 1/2" Clean)

| Project |
|---|
| SA7 Project<br>Jersey City |

| Contractor |
|---|
| Sevenson Environmental |

| | |
|---|---|
| **Sp. Gr** | **2.68** |
| **Loose** | **75** |
| **Rodded** | **90** |

| | Typical | Prod. Target | |
|---|---|---|---|
| **4"** | **100** | 100 | 100 |
| **3 1/2"** | **95** | 90 | 100 |
| **2 1/2** | **42** | 25 | 60 |
| **2"** | **29** | | |
| **1 1/2"** | **7** | | 15 |
| **1"** | **4** | | |
| **3/4** | **1** | | 5 |




Tilcon Inc confirms that #1 (3 1/2" Clean) available at Mt. Hope Quarry conforms to section 901 of the ***New Jersey Department of Transportation StandardSpecifications for Road and Bridge Construction.*** The material is defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mount Hope Road, Block 20001-Lot 6.01 Wharton Borough, Morris County NJ. The material is identified on the job with Tilcon delivery tickets.

The unit weights and voids are for process control and should be verified by the contractor before use.

# TILCON NY - Mt. Hope Facility

## Mt Hope Surge (12" - 1/2") - Light Stone Filling
## Sevenson Environmental - SA7 Project, Jersey City

Tilcon-NJ confirms that the Surge available at Mt. Hope Quarry Conforms to the quality requirements of section 901 of ***The New Jersey Department of Transportation Standard Specifications for Road and Bridge Construction.*** It is defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mt. Hope Rd. Blk 20001-Lot 6.01Wharton Boro, Morris County NJ. The material is identified on the job with Tilcon NJ delivery tickets.
This Rip Rap has the following properties:

| | | |
|---|---|---|
| Sodium Sulfate Soundness | (ASTM C88) | **2.0% Loss** |
| Water Absorption | (ASTM C97) | **0.50%** |
| LA Abrasion | (ASTM-C535) | **13.65% Loss** |
| Bulk Specific Gravity | (ASTM-C97) | **2.72** |
| Freeze-Thaw Test | (ASTM-T103) | **2.4% Loss** |

And the following Gradation

| | |
|---|---|
| $D_{100}$ | 12" |
| $D_{60}$ | 6" |
| $D_{10}$ | 1/2" |

If you have anyquestions or concerns, please call.

(973)-366-3740
Central Materials Lab
Tilcon, NJ

# TILCON NY - Mt. Hope Facility

## Mt Hope Hammer Rock (20" - 6") - Medium Stone Filling
## Sevenson Environmental - SA7 Project, Jersey City

Tilcon-NJ confirms that the Hammer Rock available at Mt. Hope Quarry Conforms to the quality requirements of section 901 of ***The New Jersey Department of Transportation Standard Specifications for Road and Bridge Construction.*** It is defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mt. Hope Rd. Blk 20001-Lot 6.01Wharton Boro, Morris County NJ. The material is identified on the job with Tilcon NJ delivery tickets.
This Rip Rap has the following properties:

| | | |
|---|---|---|
| Sodium Sulfate Soundness | (ASTM C88) | **2.0% Loss** |
| Water Absorption | (ASTM C97) | **0.50%** |
| LA Abrasion | (ASTM-C535) | **13.65% Loss** |
| Bulk Specific Gravity | (ASTM-C97) | **2.72** |
| Freeze-Thaw Test | (ASTM-T103) | **2.4% Loss** |

And the following Gradation

| | |
|---|---|
| $D_{100}$ | 20" |
| $D_{50}$ | 12" |
| $D_{10}$ | 6" |

If you have anyquestions or concerns, please call.

(973)-366-3740
Central Materials Lab
Tilcon, NJ

# TILCON-NY Mt. Hope Quarry

Fax 973-659-3978

625 Mount Hope Rd. • Wharton, N.J. 07946 • 973-366-7741


3.5 Inch Stone


## Typical Gradation,Re-Crush - 4's & 5's

| Project |
|---|
| SA 7 Project<br>Jersey City, NJ 07302 |

| Contractor |
|---|
| Sevenson Environmental |

| | |
|---|---|
| Sp. Gr | 2.68 |
| Loose | |
| Rodded | |

| | Typical | Prod. Target | |
|---|---|---|---|
| 7" | 100 | | |
| 6" | 95.1 | | |
| 5" | 83.3 | | |
| 4" | 67.7 | | |
| 3 1/2" | 48.8 | | |
| 3" | 16.5 | | |
| 2 1/2" | 5.8 | | |




Tilcon Inc confirms that Re-Crush - 4's & 5's available at Mt. Hope Quarry conforms to section 901 of the ***New Jersey Department of Transportation StandardSpecifications for Road and Bridge Construction.*** The material is defined as virgin Gneiss mined at Mt. Hope Quarry, 625 Mount Hope Road, Block 20001-Lot 6.01 Wharton Borough, Morris County NJ. The material is identified on the job with Tilcon delivery tickets.

The unit weights and voids are for process control and should be verified by the contractor before use.

# APPENDIX M

# COMPACTION TESTS

**ATTACHMENT D-2**


**Figure Backfill Compaction Locations BF-01 to B-45**

**Figure Backfill Compaction Locations BF-46 to BF-94**

**Figure Backfill Compaction Locations BF-95 to BF-136**

**Figure Backfill Compaction Locations RF-01 to RF-21**

**Figure Backfill Compaction Locations RF 22 to RF-39**




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JN 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-01 TO BF-45

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-46 TO BF-94

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on reduced testing frequency specified in 02315 3.13 A. 3.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-01 TO RF-21

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 02315 3.13 A. 3.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39, SITE 163, AND LOAM

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT D-3**

**Field Density Test Summary Log Table (Pages 1 to 7)**

**Field Density Test Summary Log Table (Pages 1 to 4)**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01* | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02* | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Brid | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-62 | | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-62-1 | 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |
| 0 | BF-64 | | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-64-1 | 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 3 | BF-64-2 | 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-65 | | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-65-1 | 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 0 | BF-66 | | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-66-1 | 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 2 | BF-66-2 | 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 0 | BF-67 | | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-67-1 | 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-67-2 | 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-68 | | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-68-1 | 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-68-2 | 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 0 | BF-69 | | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-69-1 | 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-69-2 | 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-70 | | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-70-1 | 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-70-2 | 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| 0 | BF-71 | | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 5 | BF-71-1 | 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-72 | | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 3 | BF-72-1 | 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| 0 | BF-73 | | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 6 | BF-73-1 | 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 6 | BF-75-2 | 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 6 | BF-76-2 | 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 6 | BF-77-2 | 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 7 | BF-78-2 | 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 7 | BF-80-2 | 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 4 | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 7 | BF-81-2 | 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 6 | BF-82-2 | 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 6 | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 7 | BF-83-3 | 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 6 | BF-84-3 | 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 6 | BF-85-3 | 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-86-2 | 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.
Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again
= Area subject to re-compaction

* *Initial field testing indicated compaction of greater then 95% (see attached Sor Testing Lab (STL) memo). Laboratory results for initially provided Weldon WC QP sample indicated a maximum dry density of 136.7 pcf. Using this density the compaction results are greater than the 95%. Laboratory tests on later deliveries indicated density results of 142.6 pcf. This range is typical of what can be expected for this type of source. The Engineer of Record (EOR) directed that the results be reported using the higher more conservative value and that the STL field test report verifying the higher passing results be attached to the final documentation. It is further noted that the Design Documents do not designate this area for compaction as Structural Fill per Specification Section 02315 Section 3.12, Structural Fill 95%; Non Structural Fill 90% Standard Proctor. The 95% value noted in this Table was implemented to provide for uniform compaction in areas slated for future development. It is the EOR's opinion that these two samples meet the 100% Design and project requirements.*

# SOR TESTING LABORATORIES, INC.

*Geotechnical Engineering - Materials Testing - Forensic Studies*
98 Sand Park Rd., Cedar Grove, NJ 07009
(973) 239-6001 Fax (973) 239-8380

Kamil Sor, Ph.D.
Orhun Sor, P.E.
Yilmaz Arhan, Ph.D.
Kenneth Rowbotham, P.E.
Atilla Sencar, P.E.



This report is the confidential property of the Client, and information
Contained may not be published or reproduced without our written permission.


| | | | |
|---|---|---|---|
| Client: | Entact Environmental Services | | |
| Project: | Honeywell SA-6, Jersey City NJ | | |
| Subject: | In-Place Density Tests | | |
| Job No.: | 13-208 | Report No.: 13-1994 | Date: 12/3/13 |

At the request of the client, on November 22, 2013 a field technician from Sor Testing Laboratories, Inc. reported to the project site for the purpose of performing in-place density tests over previously compacted lifts of materials at locations indicated by the client's representative.

Using a nuclear density gauge, our technician performed two density tests at locations 01BF-2 and 02BF-2 per the client's instructions. The proctor value of 136.7 pcf at our optimum moisture content of 8.1% was also provided by the client.

Test results were 97.5% and 95.7% compaction.

Technician: J.C. Jean-Toussaint

Very truly yours,

SOR TESTING LABORATORIES, INC.

Atilla Sencar, P.E.
Senior Engineer

AS/jh
Attachment

cc: (1) Client, Attn: Craig Cymbor (Email: ccymbor@entact.com)
(1) Client, Attn: Caroline Panico (Email: cpanico@entact.com)
(1) Client, Attn: Andrew Rizzuto (Email: arizzuto@entact.com)

# SOR TESTING LABORATORIES, INC.

*Geotechnical Engineering · Materials Testing · Forensic Studies*

98 Sand Park Rd., Cedar Grove, N.J. 07009
(973) 239-6001 • Fax (973) 239-8380

Kamil Sor, Ph.D.
Orhun Sor, P.E.
Peter G. Mickus, P.E.


## NUCLEAR DENSITY TEST DATA

Client: Entact Date: 11-22-2013
Project: HoneyWell SA-6 Job No.: 13-208 Report No. 13-1994
Daily Standard Count: _____ Density: 1975 Moisture 627

| TEST NUMBER | 1 | X | 2 | X | | | |
|---|---|---|---|---|---|---|---|
| Station | | | | | | | |
| Offset | | | | | | | |
| Elevation | 01BF-2 | | 02BF-2 | | | | |
| Mode & Depth (inches) | NORMAL/+10" | | NORMAL +10" | | | | |
| Density Count | N/A | | N/A | | | | |
| Wet Density (P.C.F.) | 137.8 | | 134.6 | | | | |
| Moisture Count | N/A | | N/A | | | | |
| Dry Density (P.C.F.) | 133.3 | | 130.8 | | | | |
| Moisture (P.C.F.) | 4.5 | | 3.6 | | | | |
| Moisture (%) | 3.4 | | 2.8 | | | | |
| Proctor Density (P.C.F.) | 136.7 | | 136.7 | | | | |
| Optimum Moisture (%) | | | | | | | |
| % Compaction | 97.5 | | 95.7 | | | | |
| Moisture Correction | | | | | | | |

REMARKS:

Jean C. Jean Mouaint
INSPECTOR

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 1 | RF-14-2 | 11/5/2014 | 684662.9 | 602542.6 | 0.0 | 134.0 | 0.6 | 135.8 | 6.4 | 99 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-16-2 | 11/5/2014 | 684767.6 | 602428.4 | 1.2 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 67 | Weldon WC Screenings | | V5N |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-17-2 | 11/5/2014 | 684723.7 | 602387.9 | 1.5 | 124.0 | 3.8 | 128.9 | 12.1 | 96 | 95 | 70 | Weldon WC Screenings | | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| 6 | RF-18-2 | 11/5/2014 | 684636.8 | 602258.1 | 5.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 73 | Weldon WC Screenings | Placed on Type A material | V5N |
| | RF-19 | | 684790.8 | 602339.5 | -2.5 | | | | | | | 75 | Stratum D | Bottom of excavation elevation | |
| 3 | RF-19-1 | 11/5/2014 | 684776.9 | 602328.5 | 1.8 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 75 | Weldon WC Screenings | | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| 4 | RF-21-2 | 11/5/2014 | 684823.4 | 602288.0 | 1.8 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 79 | Tilcon MH DGA | | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| 5 | RF-23-04 | 11/5/2014 | 684877.6 | 602222.8 | 2.5 | 134.0 | 0.7 | 135.8 | 6.4 | 99 | 95 | 85 | Tilcon MH DGA | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| NA | RF-27-LOAM | 12/15/2014 | 685045.9 | 601945.1 | -4.4 | 129.0 | 3.0 | 135.8 | 6.4 | 95 | 95 | 106 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| NA | RF-28-LOAM | 12/15/2014 | 685085.0 | 601862.1 | -4.7 | 135.8 | 4.0 | 135.8 | 6.4 | 100 | 95 | 112 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 0 | Site 163-2 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-2-1 | 11/5/2014 | 685070.9 | 601614.2 | 6.1 | 122.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| 2 | Site 163-2-2 | 11/14/2014 | 685070.5 | 601616.0 | 7.5 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| | | | | | | | | | | | | | | | |

***Notes:*** Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID RF-01-01 where:

RF = Reduced Frequency
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again
= Area subject to re-compaction

**TRANSMITTAL FOR ACCEPTANCE OF REMEDIAL ACTION SUBMITTALS**

| Date: | Project Name and Contract No. | Location: | **Transmittal No.** |
|---|---|---|---|
| 6/17/16 | Honeywell SA6 North and South<br>ENTACT Job #8140C | Jersey City, NJ | **154** |

| **To:** | **From:** |
|---|---|
| AMEC<br>60 Kellogg Street<br>Jersey City, NJ 07305<br>Attn: Eric Christodoulatos | ENTACT<br>302 Unity Plaza<br>Latrobe, PA 15650<br>Preparer: Caroline Panico |

| No. Copies | Item No. | Description (Name, Type, Size, Capacity Use) | Spec. Sect. No. | Manufacturer/ Designer | **For AMEC's use** Action Code | Review |
|---|---|---|---|---|---|---|
| 1 | | SA6 South Cap Compaction Testing | 02315-3.13.A | | | |
| | 1 | Field Density Test Summary Log | | | | |
| | 2 | Test Location Drawings<br>• GDL Cover Soil<br>• Horizon C<br>• Structural Fill | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Special Instructions by Contractor/Vendor

AMEC's Comments

Checked by Contractor for Project Conformance:
Signed:/Title:
Caroline Panico
Quality Control Manager

**Acceptance Action Code:**

1. No exceptions taken
2. Make corrections noted
3. Amend and resubmit
4. Rejected - see remarks

■ Installation shall proceed only when acceptance code is #1 or #2.
■ Acceptance does not relieve Contractor from responsibility of compliance with all requirements of the Subcontract documents.
■ Acceptance coded 3 or 4 shall be resubmitted unless otherwise indicated.

Date Returned_____

by_____
AMEC

**IN-HOUSE SHOP DRAWING AND VENDOR DRAWING REVIEW**

| Seq. | Role | Individual | Initial | Date | Comments |
|---|---|---|---|---|---|
| | | | | | Review Period _____ days |
| | | | | | |
| | | | | | |
| | | | | | |

# 1.0 Field Density Test Summary Log

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-03-1 | 10/20/2015 | 685534.39 | 601506.6 | 17.45 | 114.3 | 3.3 | 117 | 8.6 | 97.7 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-04-1 | 10/20/2015 | 685573.6 | 601571 | 18.25 | 118 | 4.1 | 117 | 8.6 | 100.9 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-05-1 | 10/20/2015 | 685530.6 | 601543.8 | 17.84 | 116.6 | 6.4 | 117 | 8.6 | 99.7 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-06-1 | 10/20/2015 | 685488.8 | 601532.7 | 14.72 | 118.6 | 7.1 | 117 | 8.6 | 101.4 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-07-1 | 10/20/2015 | 685512.5 | 601575.8 | 17.71 | 115 | 5.9 | 117 | 8.6 | 98.3 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-08-1 | 10/20/2015 | 685536.3 | 601610.7 | 17.61 | 117.3 | 5.4 | 117 | 8.6 | 100.3 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-09-1 | 10/20/2015 | 685492.5 | 601601.9 | 16.43 | 122.4 | 3.7 | 117 | 8.6 | 104.6 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-10-1 | 10/20/2015 | 685448.8 | 601585.8 | 14.79 | 114.5 | 5.6 | 117 | 8.6 | 97.9 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-11-1 | 10/20/2015 | 685477.6 | 601634.6 | 17.08 | 122.2 | 5.8 | 117 | 8.6 | 104.4 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-12-1 | 10/20/2015 | 685503.5 | 601668.8 | 17.32 | 115.3 | 5.9 | 117 | 8.6 | 98.5 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-13-1 | 10/20/2015 | 685462.1 | 601659.8 | 16.59 | 115.5 | 4.5 | 117 | 8.6 | 98.7 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-14-1 | 10/20/2015 | 685423.8 | 601646.8 | 14.54 | 117.9 | 3.2 | 117 | 8.6 | 100.8 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-15-1 | 10/20/2015 | 685444.3 | 601687.7 | 14.73 | 114.8 | 5 | 117 | 8.6 | 98.1 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-16-1 | 10/20/2015 | 685460.2 | 601724.9 | 16.34 | 115.8 | 4 | 117 | 8.6 | 99.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-17-1 | 10/20/2015 | 685433.8 | 601722.1 | 14.62 | 113.7 | 7.3 | 117 | 8.6 | 97.2 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-18-1 | 10/20/2015 | 685394.4 | 601715.0 | 17.21 | 118.9 | 3.4 | 117 | 8.6 | 101.6 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-129-1 | 11/4/2015 | 684281.4 | 603180.2 | 8.75 | 120.2 | 8.0 | 117 | 8.6 | 102.7 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-130-1 | 11/4/2015 | 684216.2 | 603153.2 | 8.83 | 113.6 | 6.7 | 117 | 8.6 | 97.1 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-131-1 | 11/4/2015 | 684261.4 | 603206.7 | 8.42 | 114.1 | 10.9 | 117 | 8.6 | 97.5 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-132-1 | 11/4/2015 | 684292.4 | 603250.5 | 9.53 | 118.3 | 6.2 | 117 | 8.6 | 101.1 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-133-1 | 11/4/2015 | 684236.5 | 603231.2 | 8.64 | 111.6 | 8.1 | 117 | 8.6 | 95.4 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-134-1 | 11/4/2015 | 684175.3 | 603214.9 | 8.57 | 122.5 | 7.7 | 117 | 8.6 | 104.7 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-135-1 | 11/4/2015 | 684215.0 | 603254.8 | 8.32 | 118.4 | 6.6 | 117 | 8.6 | 101.2 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-136-1 | 11/4/2015 | 684251.9 | 603305.8 | 8.40 | 115.1 | 8.8 | 117 | 8.6 | 98.4 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-137-1 | 11/4/2015 | 684189.5 | 603274.7 | 7.64 | 116.9 | 9.3 | 117 | 8.6 | 99.9 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-138-1 | 11/4/2015 | 684143.3 | 603253.5 | 7.36 | 117.9 | 10.5 | 117 | 8.6 | 100.8 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-125-1 | 11/6/2015 | 684314.5 | 603125.9 | 7.68 | 111.2 | 8.2 | 117 | 8.6 | 95.0 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-126-1 | 11/6/2015 | 684270.3 | 603123.5 | 7.05 | 120.0 | 9.7 | 117 | 8.6 | 102.6 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-127-1 | 11/6/2015 | 684305.4 | 603158.0 | 7.55 | 115.7 | 7.6 | 117 | 8.6 | 98.9 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-128-1 | 11/6/2015 | 684334.4 | 603202.5 | 7.75 | 117.7 | 7.4 | 117 | 8.6 | 100.6 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | SF-17-1 | 11/6/2015 | 684184.8 | 603260.8 | 8.67 | 126.8 | 5.4 | 133 | 8.6 | 95.3 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | SF-18-1 | 11/6/2015 | 684230.8 | 603283.7 | 9.16 | 127.2 | 5.9 | 133 | 8.6 | 95.6 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | CS-117-1 | 11/10/2015 | 684405.2 | 603020.3 | 11.64 | 111.0 | 5.2 | 117 | 8.6 | 94.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-118-1 | 11/10/2015 | 684350.5 | 603002.3 | 9.66 | 115.2 | 7.3 | 117 | 8.6 | 98.5 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-119-1 | 11/10/2015 | 684384.6 | 603051.2 | 10.55 | 116.0 | 6.3 | 117 | 8.6 | 99.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-120-1 | 11/10/2015 | 684422.3 | 603088.8 | 11.72 | 115.7 | 6.6 | 117 | 8.6 | 98.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-122-1 | 11/10/2015 | 684307.2 | 603059.7 | 8.50 | 116.8 | 7.5 | 117 | 8.6 | 99.8 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-110-1 | 11/11/2015 | 684445.1 | 602994.4 | 13.50 | 115.5 | 9.7 | 117 | 8.6 | 98.7 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-111-1 | 11/11/2015 | 684477.2 | 602955.6 | 15.83 | 125.3 | 9.0 | 117 | 8.6 | 107.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-112-1 | 11/11/2015 | 684507.0 | 602999.4 | 16.21 | 122.7 | 9.0 | 117 | 8.6 | 104.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-113-1 | 11/11/2015 | 684455.2 | 602974.1 | 14.56 | 118.0 | 9.0 | 117 | 8.6 | 100.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-114-1 | 11/11/2015 | 684396.7 | 602954.9 | 12.21 | 120.6 | 10.0 | 117 | 8.6 | 103.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-115-1 | 11/11/2015 | 684426.7 | 603002.4 | 12.86 | 118.5 | 8.4 | 117 | 8.6 | 101.3 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-116-1 | 11/11/2015 | 684459.1 | 603046.2 | 13.60 | 122.3 | 8.1 | 117 | 8.6 | 104.5 | 90 | 4 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-121-1 | 11/11/2015 | 684364.2 | 603084.9 | 9.73 | 121.3 | 9.3 | 117 | 8.6 | 103.7 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-123-1 | 11/11/2015 | 684344.5 | 603105.3 | 9.51 | 119.7 | 10.3 | 117 | 8.6 | 102.3 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-124-1 | 11/11/2015 | 684370.5 | 603148.7 | 9.80 | 116.4 | 11.3 | 117 | 8.6 | 99.5 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | SF-15-1 | 11/11/2015 | 684280.3 | 603136.7 | 7.80 | 131.4 | 7.0 | 133 | 8.6 | 98.8 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-15-2 | 11/11/2015 | 684279.3 | 603138.5 | 9.15 | 129.9 | 6.8 | 133 | 8.6 | 97.7 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 3 | SF-15-3 | 11/11/2015 | 684271.2 | 603129.6 | 9.64 | 132.5 | 3.3 | 133 | 8.6 | 99.6 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 1 | SF-16-1 | 11/11/2015 | 684316.8 | 603171.2 | 8.29 | 133.6 | 6.8 | 133 | 8.6 | 100.5 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-16-2 | 11/11/2015 | 684319.3 | 603178.5 | 9.48 | 133.6 | 5.4 | 133 | 8.6 | 100.5 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 3 | SF-16-3 | 11/11/2015 | 684314.6 | 603172.8 | 10.70 | 135.6 | 5.0 | 133 | 8.6 | 102.0 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-17-2 | 11/11/2015 | 684184.9 | 603258.9 | 9.56 | 126.4 | 6.7 | 133 | 8.6 | 95.0 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 2 | SF-18-2 | 11/11/2015 | 684234.3 | 603282.9 | 9.71 | 133.9 | 6.3 | 133 | 8.6 | 100.7 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | HC-10-1 | 11/13/2015 | 685444.5 | 601588.5 | 15.22 | 114.6 | 9.5 | 126 | 9.5 | 91.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-11-1 | 11/13/2015 | 685477.6 | 601635.1 | 17.64 | 122.2 | 9.7 | 126 | 9.5 | 97.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-128-1 | 11/13/2015 | 684307.4 | 603209.5 | 9.94 | 114.5 | 10.8 | 126 | 9.5 | 90.9 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-129-1 | 11/13/2015 | 684280.0 | 603181.7 | 9.33 | 110.0 | 10.2 | 126 | 9.5 | 87.3 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-13-1 | 11/13/2015 | 685461.4 | 601657.1 | 17.20 | 122.5 | 9.3 | 126 | 9.5 | 97.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-131-1 | 11/13/2015 | 684261.3 | 603208.3 | 8.99 | 119.8 | 10.7 | 126 | 9.5 | 95.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-130-1 | 11/13/2015 | 684238.9 | 603170.2 | 9.33 | 121.4 | 10.6 | 126 | 9.5 | 96.3 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-132-1 | 11/13/2015 | 684294.6 | 603252.5 | 10.11 | 114.6 | 13.1 | 126 | 9.5 | 91.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-133-1 | 11/13/2015 | 684236.1 | 603230.2 | 9.14 | 124.7 | 11.3 | 126 | 9.5 | 99.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-134-1 | 11/13/2015 | 684173.7 | 603204.1 | 9.17 | 120.2 | 11 | 126 | 9.5 | 95.4 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-135-1 | 11/13/2015 | 684223.3 | 603252.6 | 8.92 | 120 | 11.5 | 126 | 9.5 | 95.2 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-136-1 | 11/13/2015 | 684264.7 | 603275 | 9.06 | 128.5 | 10.45 | 126 | 9.5 | 102.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-137-1 | 11/13/2015 | 684206.1 | 603237.7 | 9.16 | 118.4 | 10.5 | 126 | 9.5 | 94.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-138-1 | 11/13/2015 | 684160.6 | 603231.8 | 7.70 | 110.2 | 12.4 | 126 | 9.5 | 87.5 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-14-1 | 11/13/2015 | 685422.6 | 601647.6 | 15.13 | 117.4 | 9.9 | 126 | 9.5 | 93.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-15-1 | 11/13/2015 | 684443.2 | 601689.6 | 15.42 | 117.3 | 9.9 | 126 | 9.5 | 93.1 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | CS-106-1 | 11/17/2015 | 684477.6 | 602852.8 | 7.70 | 117.5 | 8.0 | 117 | 8.6 | 100.4 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-107-1 | 11/17/2015 | 684525.2 | 602897.0 | 7.36 | 108.0 | 4.3 | 117 | 8.6 | 92.3 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-108-1 | 11/17/2015 | 684553.4 | 602948.7 | 15.71 | 123.4 | 7.5 | 117 | 8.6 | 105.5 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-109-1 | 11/17/2015 | 684499.0 | 602921.5 | 14.74 | 119.4 | 5.9 | 117 | 8.6 | 102.1 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | HC-118-1 | 11/17/2015 | 684353.8 | 603000.7 | 10.34 | 113.6 | 11.1 | 126 | 9.5 | 90.2 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-119-1 | 11/17/2015 | 684385.6 | 603051.8 | 11.10 | 120.1 | 12.4 | 126 | 9.5 | 95.3 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-120-1 | 11/17/2015 | 684417.3 | 603086.2 | 12.07 | 128.7 | 10.9 | 126 | 9.5 | 102.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-121-1 | 11/17/2015 | 684363.8 | 603008.5 | 10.29 | 116.5 | 8.3 | 126 | 9.5 | 92.5 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-122-1 | 11/17/2015 | 684319.6 | 603062.6 | 9.47 | 115.4 | 10.1 | 126 | 9.5 | 91.6 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-123-1 | 11/17/2015 | 684343.7 | 603110.5 | 10.08 | 122.0 | 12.0 | 126 | 9.5 | 96.8 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-124-1 | 11/17/2015 | 684373.8 | 603148.2 | 10.36 | 116.8 | 9.5 | 126 | 9.5 | 92.7 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-125-1 | 11/17/2015 | 684322.9 | 603123.8 | 9.85 | 113.4 | 11.3 | 126 | 9.5 | 90.0 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-126-1 | 11/17/2015 | 684294.5 | 603104.5 | 9.33 | 113.7 | 9.7 | 126 | 9.5 | 90.2 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-127-1 | 11/17/2015 | 684344.3 | 603150.7 | 10.16 | 118.9 | 11.6 | 126 | 9.5 | 94.4 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-129-1R | 11/17/2015 | 684276.4 | 603183.7 | 9.24 | 113.4 | 9.2 | 126 | 9.5 | 90.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-138-1R | 11/17/2015 | 684162.8 | 603230.4 | 7.91 | 114.8 | 10.3 | 126 | 9.5 | 91.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-108-1 | 11/19/2015 | 684536.2 | 902967.2 | 18.62 | 113.4 | 10.0 | 126 | 9.5 | 90.0 | 90 | 5 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | HC-109-1 | 11/19/2015 | 684492.9 | 602930.4 | 18.27 | 127.2 | 10.0 | 126 | 9.5 | 101.0 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-110-1 | 11/19/2015 | 684449.3 | 602900.5 | 14.40 | 115.7 | 10.0 | 126 | 9.5 | 91.8 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-111-1 | 11/19/2015 | 684475.6 | 602955.2 | 16.38 | 118.6 | 11.3 | 126 | 9.5 | 94.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-112-1 | 11/19/2015 | 684507.3 | 602998.5 | 16.87 | 119.2 | 9.9 | 126 | 9.5 | 94.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-113-1 | 11/19/2015 | 684452.2 | 602978.3 | 14.98 | 121.1 | 12.1 | 126 | 9.5 | 96.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-114-1 | 11/19/2015 | 684397.7 | 602956.1 | 12.85 | 121.5 | 10.7 | 126 | 9.5 | 96.4 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-115-1 | 11/19/2015 | 684428.1 | 603001.7 | 13.53 | 125.5 | 9.9 | 126 | 9.5 | 99.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-116-1 | 11/19/2015 | 684461.4 | 603048.2 | 14.24 | 115.4 | 9.9 | 126 | 9.5 | 91.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-117-1 | 11/19/2015 | 684402.1 | 603019.3 | 12.08 | 121.6 | 10.5 | 126 | 9.5 | 96.5 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | SF-12-1 | 11/19/2015 | 684485.9 | 602888.7 | 15.10 | 129.8 | 3.5 | 133 | 8.6 | 97.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-13-1 | 11/19/2015 | 684515.4 | 602913.9 | 15.90 | 129.9 | 4.3 | 133 | 8.6 | 97.7 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-14-1 | 11/19/2015 | 684548.8 | 602937.5 | 16.40 | 125.4 | 3.5 | 133 | 8.6 | 94.3 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-14-1R | 11/19/2015 | 684548.8 | 602937.5 | 16.40 | 127.3 | 3.5 | 133 | 8.6 | 95.7 | 95 | 5 | Structural Fill -Liberty | Re-roll/re-test; D Street-shallow | V5N |
| 1 | SF-19-1 | 11/19/2015 | 684505.8 | 602882.5 | 8.54 | 129.3 | 3.3 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-19-2 | 11/19/2015 | 684507.6 | 602881.4 | 9.70 | 126.4 | 4.4 | 133 | 8.6 | 95.0 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 3 | SF-19-3 | 11/19/2015 | 684507.5 | 602880.7 | 10.66 | 131.5 | 3.7 | 133 | 8.6 | 98.9 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 4 | SF-19-4 | 11/19/2015 | 684508.0 | 602880.1 | 11.49 | 131.0 | 4.7 | 133 | 8.6 | 98.5 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | SF-20-1 | 11/19/2015 | 684546.3 | 602907.6 | 8.77 | 129.3 | 4.3 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-20-2 | 11/19/2015 | 684545.4 | 602907.4 | 9.83 | 129.9 | 3.2 | 133 | 8.6 | 97.7 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 3 | SF-20-3 | 11/19/2015 | 684547.9 | 602908.6 | 10.90 | 130.1 | 3.5 | 133 | 8.6 | 97.8 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 4 | SF-20-4 | 11/19/2015 | 684548.3 | 602910.0 | 11.78 | 129.3 | 3.5 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | CS-100-1 | 11/24/2015 | 684631.4 | 602847.9 | 21.61 | 115.7 | 8.1 | 117 | 8.6 | 98.9 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-101-1 | 11/24/2015 | 684579.4 | 602829.3 | 21.00 | 122.2 | 5.3 | 117 | 8.6 | 104.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-103-1 | 11/24/2015 | 684559.4 | 602849.9 | 20.50 | 117.0 | 4.5 | 117 | 8.6 | 100.0 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-104-1 | 11/24/2015 | 684591.9 | 602894.4 | 20.26 | 118.5 | 6.3 | 117 | 8.6 | 101.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-105-1 | 11/24/2015 | 684549.1 | 602875.2 | 19.46 | 116.3 | 8.1 | 117 | 8.6 | 99.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-93-1 | 11/24/2015 | 684673.4 | 602728.7 | 17.07 | 115.0 | 9.4 | 117 | 8.6 | 98.3 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-95-1 | 11/24/2015 | 684652.5 | 602744.8 | 17.71 | 126.5 | 5.5 | 117 | 8.6 | 108.1 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-96-1 | 11/24/2015 | 684681.1 | 602793.4 | 18.36 | 119.7 | 6.8 | 117 | 8.6 | 102.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-97-1 | 11/24/2015 | 684634.5 | 602782.1 | 18.43 | 115.4 | 6.5 | 117 | 8.6 | 98.6 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-98-1 | 11/24/2015 | 684578.8 | 602757.8 | 18.44 | 117.4 | 6.3 | 117 | 8.6 | 100.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-99-1 | 11/24/2015 | 684610.9 | 602806.5 | 18.70 | 118.6 | 6.8 | 117 | 8.6 | 101.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 5 | SF-19-5 | 11/24/2015 | 684507.1 | 602879.1 | 13.03 | 133.2 | 5.6 | 133 | 8.6 | 100.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 6 | SF-19-6 | 11/24/2015 | 684506.8 | 602882.9 | 14.10 | 131.8 | 3.7 | 133 | 8.6 | 99.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 7 | SF-19-7 | 11/24/2015 | 684510.4 | 602881.3 | 15.06 | 130.9 | 4.2 | 133 | 8.6 | 98.4 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 5 | SF-20-5 | 11/24/2015 | 684546.9 | 602907.7 | 12.52 | 126.8 | 6.7 | 133 | 8.6 | 95.3 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 6 | SF-20-6 | 11/24/2015 | 684545.9 | 602910.3 | 13.50 | 133.1 | 4.7 | 133 | 8.6 | 100.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 7 | SF-20-7 | 11/24/2015 | 684540.5 | 602910.5 | 14.48 | 129.1 | 4.7 | 133 | 8.6 | 97.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | CS-102-1 | 12/8/2015 | 684522.1 | 602789.6 | 9.92 | 119.0 | 9.9 | 117 | 8.6 | 101.7 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-86-1 | 12/8/2015 | 684691.4 | 602613.8 | 6.27 | 120.7 | 8.5 | 117 | 8.6 | 103.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-87-1 | 12/8/2015 | 684741.0 | 602650.3 | 9.32 | 120.8 | 8.7 | 117 | 8.6 | 103.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-88-1 | 12/8/2015 | 684774.1 | 602700.3 | 8.44 | 122.0 | 9.4 | 117 | 8.6 | 104.3 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-89-1 | 12/8/2015 | 684713.8 | 602685.9 | 19.10 | 113.6 | 5.5 | 117 | 8.6 | 97.1 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-90-1 | 12/8/2015 | 684663.9 | 602654.3 | 15.96 | 115.2 | 6.4 | 117 | 8.6 | 98.5 | 90 | 7 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-91-1 | 12/8/2015 | 684668.9 | 602109.2 | 19.40 | 113.2 | 8.2 | 117 | 8.6 | 96.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-92-1 | 12/8/2015 | 684729.2 | 602749.3 | 16.89 | 117.9 | 7.2 | 117 | 8.6 | 100.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-94-1 | 12/8/2015 | 684610.2 | 602684.0 | 7.41 | 116.3 | 9.6 | 117 | 8.6 | 99.4 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | HC-100-1 | 12/8/2015 | 684624.6 | 602844.3 | 22.22 | 116.6 | 10.6 | 126 | 9.5 | 92.5 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-101-1 | 12/8/2015 | 684579.3 | 602829.2 | 21.65 | 128.5 | 9.0 | 126 | 9.5 | 102.0 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-102-1 | 12/8/2015 | 684517.4 | 602793.0 | 10.54 | 115.0 | 11.3 | 126 | 9.5 | 91.3 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-103-1 | 12/8/2015 | 684558.5 | 602852.7 | 20.94 | 121.1 | 10.2 | 126 | 9.5 | 96.1 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-104-1 | 12/8/2015 | 684589.0 | 602899.7 | 20.69 | 119.1 | 11.1 | 126 | 9.5 | 94.5 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-105-1 | 12/8/2015 | 684547.5 | 602874.7 | 20.00 | 114.1 | 12.6 | 126 | 9.5 | 90.6 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-106-1 | 12/8/2015 | 684488.5 | 602824.5 | 11.23 | 117.5 | 10.4 | 126 | 9.5 | 93.3 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-97-1 | 12/8/2015 | 684634.5 | 602785.1 | 19.13 | 113.4 | 10.4 | 126 | 9.5 | 90.0 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-98-1 | 12/8/2015 | 684580.8 | 602761.3 | 19.04 | 114.9 | 10.3 | 126 | 9.5 | 91.2 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-99-1 | 12/8/2015 | 684613.8 | 602809.7 | 19.33 | 115.5 | 9.6 | 126 | 9.5 | 91.7 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | SF-10-1 | 12/8/2015 | 684712.0 | 602632.9 | 8.47 | 146.3 | 3.0 | 133 | 8.6 | 110.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 1 | SF-11-1 | 12/8/2015 | 684764.1 | 602680.4 | 9.70 | 138.2 | 4.8 | 133 | 8.6 | 103.9 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 2 | SF-12-2 | 12/8/2015 | 684486.5 | 602887.8 | 16.20 | 132.2 | 7.3 | 133 | 8.6 | 99.4 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-12-3 | 12/8/2015 | 684483.4 | 602896.1 | 17.66 | 129.1 | 8.2 | 133 | 8.6 | 97.1 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 2 | SF-13-2 | 12/8/2015 | 684519.0 | 602908.4 | 17.00 | 127.7 | 6.0 | 133 | 8.6 | 96.0 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-13-3 | 12/8/2015 | 684517.8 | 602915.5 | 18.34 | 130.7 | 6.3 | 133 | 8.6 | 98.3 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 2 | SF-14-2 | 12/8/2015 | 684545.3 | 602935.8 | 17.44 | 127.2 | 6.6 | 133 | 8.6 | 95.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-14-3 | 12/8/2015 | 684538.7 | 602936.2 | 18.35 | 127.2 | 7.0 | 133 | 8.6 | 95.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 8 | SF-19-8 | 12/8/2015 | 684511.3 | 602878.7 | 16.16 | 133.8 | 6.3 | 133 | 8.6 | 100.6 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 9 | SF-19-9 | 12/8/2015 | 684512.4 | 602884.5 | 17.40 | 120.8 | 7.0 | 133 | 8.6 | 90.8 | 95 | 5 | Structural Fill -Liberty | Re-roll Area | V5N |
| 9 | SF-19-9R | 12/8/2015 | 684512.0 | 602884.0 | 17.40 | 130.2 | 7.4 | 133 | 8.6 | 97.9 | 95 | 5 | Structural Fill -Liberty | Re-test lift after rolling | V5N |
| 8 | SF-20-8 | 12/8/2015 | 684559.3 | 602906.9 | 15.66 | 127.8 | 7.6 | 133 | 8.6 | 96.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 9 | SF-20-9 | 12/8/2015 | 684559.5 | 602915.7 | 17.27 | 126.7 | 7.4 | 133 | 8.6 | 95.3 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-10-2 | 12/10/2015 | 684716.8 | 602639.7 | 9.79 | 132.4 | 6.0 | 133 | 8.6 | 99.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-10-3 | 12/10/2015 | 684718.1 | 602641.1 | 10.74 | 129.7 | 3.0 | 133 | 8.6 | 97.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 2 | SF-11-2 | 12/10/2015 | 684763.0 | 602675.2 | 10.41 | 130.5 | 6.0 | 133 | 8.6 | 98.1 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-11-3 | 12/10/2015 | 684762.5 | 602675.9 | 11.33 | 125.7 | 3.0 | 133 | 8.6 | 94.5 | 95 | 7 | Structural Fill -Liberty | Re-roll Area | V5N |
| 4 | SF-10-4 | 12/14/2015 | 684719.5 | 602644.8 | 11.71 | 126.4 | 1.9 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 5 | SF-10-5 | 12/14/2015 | 684713.2 | 602644.6 | 12.77 | 126.4 | 2.5 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 6 | SF-10-6 | 12/14/2015 | 684716.5 | 602649.2 | 13.99 | 126.5 | 3.4 | 133 | 8.6 | 95.1 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-11-3R | 12/14/2015 | 684762.0 | 602675.0 | 11.33 | 126.4 | 1.5 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | Re-test lift after rolling | V5N |
| 4 | SF-11-4 | 12/14/2015 | 684761.3 | 602678.2 | 12.57 | 127.9 | 2.1 | 133 | 8.6 | 96.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 5 | SF-11-5 | 12/14/2015 | 684770.8 | 602673.9 | 13.60 | 126.6 | 3.2 | 133 | 8.6 | 95.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 6 | SF-11-6 | 12/14/2015 | 684762.3 | 602666.3 | 14.54 | 126.6 | 3.9 | 133 | 8.6 | 95.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 7 | SF-10-7 | 12/15/2015 | 684716.8 | 602641.2 | 15.03 | 131.0 | 5.3 | 133 | 8.6 | 98.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 8 | SF-10-8 | 12/15/2015 | 684716.0 | 602649.9 | 16.07 | 126.7 | 3.3 | 133 | 8.6 | 95.3 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 9 | SF-10-9 | 12/15/2015 | 684719.3 | 602639.9 | 16.86 | 128.9 | 5.7 | 133 | 8.6 | 96.9 | 95 | 7 | Structural Fill -Liberty | C Street Corridor-final el | V5N |
| 7 | SF-11-7 | 12/15/2015 | 684765.3 | 602680.3 | 15.76 | 126.3 | 3.4 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 8 | SF-11-8 | 12/15/2015 | 684762.4 | 602675.2 | 16.71 | 128.1 | 5.7 | 133 | 8.6 | 96.3 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 9 | SF-11-9 | 12/15/2015 | 684752.5 | 602686.1 | 16.86 | 130.0 | 7.4 | 133 | 8.6 | 97.7 | 95 | 7 | Structural Fill -Liberty | C Street Corridor-final el | V5N |
| 5 | SF-10-5R | 3/6/2016 | 684712.8 | 602643.3 | 13.55 | 108.2 | 2.5 | 112.2 | 9.7 | 96.4 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | SF-10-4R | 3/16/2016 | 684708.7 | 602643.3 | 12.47 | 111.6 | 2.8 | 112.2 | 9.7 | 99.5 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 4 | SF-11-4R | 3/16/2016 | 684760.2 | 602681.4 | 12.15 | 112.0 | 2.5 | 112.2 | 9.7 | 99.8 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 5 | SF-11-5R | 3/16/2016 | 684748.8 | 602679.9 | 13.15 | 108.0 | 2.4 | 112.2 | 9.7 | 96.3 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 6 | SF-10-6R | 3/17/2016 | 684707.5 | 602634.2 | 15.23 | 109.5 | 2.3 | 112.2 | 9.7 | 97.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 7 | SF-10-7R | 3/17/2016 | 684716.6 | 602642.7 | 16.50 | 114.0 | 3.2 | 112.2 | 9.7 | 101.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 6 | SF-11-6R | 3/17/2016 | 684750.5 | 602661.5 | 15.23 | 107.3 | 2.2 | 112.2 | 9.7 | 95.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 7 | SF-11-7R | 3/17/2016 | 684750.3 | 602672.5 | 16.40 | 115.4 | 2.5 | 112.2 | 9.7 | 102.9 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 1 | CS-12-1R | 4/14/2016 | 685504.9 | 601673 | 17.30 | 121.5 | 8.7 | 117 | 8.6 | 103.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-16-1R | 4/14/2016 | 685457.6 | 601721.7 | 16.30 | 117.9 | 7.8 | 117 | 8.6 | 100.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-17-1R | 4/14/2016 | 685434.6 | 601718.5 | 14.70 | 122.5 | 8.0 | 117 | 8.6 | 104.7 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-18-1R | 4/14/2016 | 685395.1 | 601714.8 | 17.20 | 120.3 | 5.3 | 117 | 8.6 | 102.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-19-1 | 4/14/2016 | 685414.3 | 601758.3 | 17.20 | 120.6 | 5.6 | 117 | 8.6 | 103.1 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-20-1 | 4/14/2016 | 685421.8 | 601782.3 | 17.30 | 122.8 | 7.0 | 117 | 8.6 | 105.0 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-21-1 | 4/14/2016 | 685388.8 | 601769.3 | 17.40 | 120.0 | 6.8 | 117 | 8.6 | 102.6 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-22-1 | 4/14/2016 | 685341.2 | 601751.2 | 17.60 | 119.0 | 8.0 | 117 | 8.6 | 101.7 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-23-1 | 4/14/2016 | 685366.5 | 601794.2 | 18.10 | 121.4 | 4.7 | 117 | 8.6 | 103.8 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-24-1 | 4/14/2016 | 685390.4 | 601829.7 | 18.20 | 114.8 | 6.0 | 117 | 8.6 | 98.1 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-25-1 | 4/14/2016 | 685348.8 | 601819.2 | 19.00 | 121.5 | 7.7 | 117 | 8.6 | 103.8 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-26-1 | 4/14/2016 | 685305.2 | 601804.9 | 19.30 | 117.9 | 5.4 | 117 | 8.6 | 100.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-27-1 | 4/14/2016 | 685325.1 | 601846.4 | 16.90 | 120.3 | 7.0 | 117 | 8.6 | 102.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-28-1 | 4/15/2016 | 685354.8 | 601891.6 | 16.00 | 125.7 | 6.8 | 117 | 8.6 | 107.4 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-29-1 | 4/15/2016 | 685310.4 | 601883.3 | 19.60 | 120.1 | 7.3 | 117 | 8.6 | 102.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-30-1 | 4/15/2016 | 685259.5 | 601859.9 | 17.30 | 120.9 | 6.7 | 117 | 8.6 | 103.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-31-1 | 4/15/2016 | 685289.6 | 601902.5 | 19.60 | 125.3 | 7.4 | 117 | 8.6 | 107.1 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | HC-08-1 | 4/15/2016 | 685535.1 | 601617.9 | 17.00 | 115.8 | 9.8 | 126 | 9.8 | 91.9 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-09-1 | 4/15/2016 | 685492.6 | 601603.4 | 17.10 | 116.4 | 9.7 | 126 | 9.5 | 92.4 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-12-1 | 4/15/2016 | 685500.6 | 601671.6 | 17.90 | 115.1 | 9.4 | 126 | 9.5 | 91.3 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-16-1 | 4/15/2016 | 685457.5 | 601729.1 | 16.80 | 120.2 | 9.4 | 126 | 9.5 | 95.4 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-04-01 | 4/18/2016 | 685309.3 | 601839.5 | 14.50 | 107.5 | 1.7 | 112.2 | 9.7 | 95.8 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-04-02 | 4/18/2016 | 685311.3 | 601840.4 | 16.00 | 110.5 | 1.6 | 112.2 | 9.7 | 98.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 3 | SF-04-03 | 4/18/2016 | 685289.9 | 601837.7 | 17.60 | 108.1 | 1.8 | 112.2 | 9.7 | 96.3 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | SF-05-01 | 4/18/2016 | 685325.3 | 601867.3 | 18.00 | 114.9 | 2.0 | 112.2 | 9.7 | 102.4 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | SF-06-01 | 4/18/2016 | 685357.4 | 601889.1 | 17.50 | 111.6 | 2.0 | 112.2 | 9.7 | 99.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 4 | SF-04-04 | 4/20/2016 | 685294.4 | 601842.4 | 19.10 | 106.6 | 2.0 | 112.2 | 9.7 | 95.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-05-02 | 4/20/2016 | 685320.8 | 601866.4 | 19.70 | 107.7 | 2.0 | 112.2 | 9.7 | 96.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-06-02 | 4/20/2016 | 685348.9 | 601890.6 | 19.50 | 106.6 | 2.0 | 112.2 | 9.7 | 95.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | HC-17-01 | 4/20/2016 | 685432.8 | 601721.6 | 15.20 | 122.4 | 9.5 | 126 | 9.5 | 97.1 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-18-01 | 4/20/2016 | 685393.5 | 601712.7 | 17.70 | 117.2 | 10.2 | 126 | 9.5 | 93.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-19-01 | 4/20/2016 | 685419.8 | 601751.3 | 15.30 | 117.4 | 9.5 | 126 | 9.5 | 93.2 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-20-01 | 4/20/2016 | 685423.4 | 601782.8 | 17.80 | 125.8 | 8.8 | 126 | 9.5 | 99.8 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-21-01 | 4/20/2016 | 685383.0 | 601770.6 | 18.20 | 127.3 | 8.9 | 126 | 9.5 | 101.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-22-01 | 4/20/2016 | 685340.2 | 601758.3 | 18.30 | 118.4 | 8.6 | 126 | 9.5 | 94.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-23-01 | 4/20/2016 | 685366.4 | 601793.6 | 18.50 | 122.2 | 8.8 | 126 | 9.5 | 97.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-24-01 | 4/20/2016 | 685392.1 | 601831.1 | 18.90 | 119.7 | 8.4 | 126 | 9.5 | 95.0 | 90 | 8 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | HC-25-01 | 4/20/2016 | 685351.7 | 601822.1 | 19.40 | 129.8 | 9.2 | 126 | 9.5 | 103.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-26-01 | 4/20/2016 | 685303.8 | 601806.5 | 19.90 | 113.4 | 8.1 | 126 | 9.5 | 90.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-27-01 | 4/20/2016 | 685361.7 | 601845.0 | 19.70 | 121.0 | 9.0 | 126 | 9.5 | 96.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | CS-01-01 | 4/20/2016 | 685552.1 | 601486.2 | 16.40 | 111.2 | 9.0 | 117 | 8.6 | 95.1 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-02-01 | 4/20/2016 | 685571.4 | 601519.1 | 18.50 | 120.5 | 9.1 | 117 | 8.6 | 103.0 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-47-01 | 4/22/2016 | 685133.2 | 602127.9 | 6.50 | 117.0 | 8.6 | 117 | 8.6 | 100.0 | 90 | 13 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | CS-48-01 | 4/22/2016 | 685161.9 | 602170.3 | 7.10 | 115.8 | 8.4 | 117 | 8.6 | 99.0 | 90 | 14 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | CS-49-01 | 4/22/2016 | 685114.8 | 602135.6 | 6.40 | 111.2 | 8.4 | 117 | 8.6 | 95.0 | 90 | 14 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | HC-05-01 | 4/22/2016 | 685511.7 | 601549.5 | 18.30 | 113.4 | 8.2 | 126 | 9.5 | 90.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-06-01 | 4/22/2016 | 685479.0 | 601533.4 | 15.00 | 119.7 | 8.0 | 126 | 9.5 | 95.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-07-01 | 4/22/2016 | 685514.3 | 601578.6 | 18.30 | 113.4 | 8.2 | 126 | 9.5 | 90.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-01-01 | 4/22/2016 | 685510.3 | 601523.6 | 16.60 | 107.7 | 8.0 | 112.2 | 9.7 | 96.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-02-01 | 4/22/2016 | 685547.6 | 601542.6 | 18.30 | 102.0 | 8.1 | 112.2 | 9.7 | 90.9 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-03-01 | 4/22/2016 | 685585.2 | 601572.6 | 18.20 | 106.6 | 8.2 | 112.2 | 9.7 | 95.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-02-01R | 4/22/2016 | 685547.6 | 601542.6 | 18.30 | 106.6 | 8.1 | 112.2 | 9.7 | 95.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; reroll and retes | V5N |
| 1 | HC-04-01 | 4/26/2016 | 685586.2 | 601559.0 | 19.40 | 117.5 | 9.1 | 126 | 9.5 | 93.3 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-02-01 | 4/26/2016 | 685575.9 | 601519.7 | 19.30 | 114.2 | 10.6 | 126 | 9.5 | 90.6 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-03-01 | 4/26/2016 | 685531.2 | 601505.9 | 17.90 | 124.3 | 8.1 | 126 | 9.5 | 98.7 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-01-01 | 4/26/2016 | 685554.0 | 601483.2 | 16.80 | 114.7 | 9.6 | 126 | 9.5 | 91.0 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 2 | SF-01-02 | 4/26/2016 | 685512.5 | 601525.3 | 17.50 | 118.2 | 7.0 | 112.2 | 9.7 | 105.3 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 2 | SF-02-02 | 4/26/2016 | 685553.1 | 601555.1 | 18.90 | 114.9 | 4.7 | 112.2 | 9.7 | 102.4 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 2 | SF-03-02 | 4/26/2016 | 685577.3 | 601575.2 | 19.30 | 120.3 | 4.9 | 112.2 | 9.7 | 107.2 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | CS-32-01 | 4/26/2016 | 685305.2 | 601932.9 | 19.50 | 117.6 | 7.2 | 117 | 8.6 | 100.5 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-33-01 | 4/26/2016 | 685271.2 | 601934.8 | 19.60 | 117.0 | 10.6 | 117 | 8.6 | 100.0 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-34-01 | 4/26/2016 | 685225.8 | 601921.4 | 19.80 | 117.7 | 9.8 | 117 | 8.6 | 100.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-35-01 | 4/26/2016 | 685251.7 | 601967.3 | 19.30 | 117.6 | 10.5 | 117 | 8.6 | 100.5 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-36-01 | 4/26/2016 | 685269.0 | 601997.3 | 18.80 | 114.6 | 9.7 | 117 | 8.6 | 97.9 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | SF-07-01 | 4/26/2016 | 685096.6 | 606106.8 | 7.10 | 130.5 | 6.2 | 112.2 | 9.7 | 116.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | SF-08-01 | 4/26/2016 | 685131.5 | 602130.1 | 7.40 | 129.9 | 5.8 | 112.2 | 9.7 | 115.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | SF-09-01 | 4/26/2016 | 685163.1 | 602153.3 | 7.60 | 127.8 | 5.7 | 112.2 | 9.7 | 113.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-07-02 | 4/26/2016 | 685098.7 | 602108.8 | 7.90 | 124.6 | 4.8 | 112.2 | 9.7 | 111.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-08-02 | 4/26/2016 | 685134.0 | 602134.2 | 8.20 | 116.8 | 3.7 | 112.2 | 9.7 | 104.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-09-02 | 4/26/2016 | 685173.6 | 602160.2 | 8.60 | 128.1 | 5.5 | 112.2 | 9.7 | 114.2 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-07-03 | 4/27/2016 | 685096.6 | 602106.8 | 9.40 | 113.2 | 2.8 | 112.2 | 9.7 | 100.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-08-03 | 4/27/2016 | 685131.5 | 602133.6 | 9.60 | 112.5 | 3.2 | 112.2 | 9.7 | 100.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-09-03 | 4/27/2016 | 685168.9 | 602159.4 | 10.00 | 116.2 | 2.9 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-07-04 | 4/28/2016 | 685089.9 | 602105.5 | 10.40 | 107.2 | 4.7 | 112.2 | 9.7 | 95.5 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-08-04 | 4/28/2016 | 685130.3 | 602135.1 | 10.50 | 108.4 | 2.6 | 112.2 | 9.7 | 96.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-09-04 | 4/28/2016 | 685158.3 | 602159.3 | 10.80 | 110.9 | 3.7 | 112.2 | 9.7 | 98.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-07-05 | 4/28/2016 | 658087.4 | 602109.5 | 11.30 | 106.9 | 4.6 | 112.2 | 9.7 | 95.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-08-05 | 4/28/2016 | 685126.7 | 602137.8 | 11.60 | 115.8 | 3.2 | 112.2 | 9.7 | 103.2 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-09-05 | 4/28/2016 | 685164.5 | 602163.5 | 11.50 | 112.6 | 3.3 | 112.2 | 9.7 | 100.4 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | CS-37-01 | 4/28/2016 | 685234.1 | 601983.7 | 18.80 | 121.7 | 8.8 | 117 | 8.6 | 104.0 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-38-01 | 4/28/2016 | 685185.5 | 601970.6 | 18.70 | 116.6 | 6.7 | 117 | 8.6 | 99.7 | 90 | 12 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-39-01 | 4/28/2016 | 685213.8 | 602102.2 | 18.20 | 122.0 | 8.3 | 117 | 8.6 | 104.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-40-01 | 4/28/2016 | 685227.8 | 602065.5 | 17.70 | 119.1 | 8.7 | 117 | 8.6 | 101.8 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-41-01 | 4/28/2016 | 685193.2 | 602041.5 | 17.40 | 120.0 | 10.9 | 117 | 8.6 | 102.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-42-01 | 4/28/2016 | 685152.5 | 602025.7 | 17.30 | 119.6 | 8.9 | 117 | 8.6 | 102.2 | 90 | 13 | GDL Cover Soil | | V5N |
| 6 | SF-07-06 | 4/29/2016 | 658082.9 | 602108.5 | 12.26 | 114.3 | 2.7 | 112.2 | 9.7 | 101.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 6 | SF-08-06 | 4/29/2016 | 685136.5 | 602126.5 | 12.47 | 110.8 | 2.4 | 112.2 | 9.7 | 98.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 6 | SF-09-06 | 4/29/2016 | 685146.5 | 602166.6 | 12.35 | 113.3 | 2.4 | 112.2 | 9.7 | 101.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | HC-28-01 | 4/29/2016 | 685334.6 | 601903.6 | 19.80 | 119.8 | 9.5 | 126 | 9.5 | 95.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-29-01 | 4/29/2016 | 685294.7 | 601866.8 | 20.20 | 128.7 | 8.4 | 126 | 9.5 | 102.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-30-01 | 4/29/2016 | 685258.9 | 601854.0 | 17.80 | 114.7 | 10.7 | 126 | 9.5 | 91.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-31-01 | 4/29/2016 | 685286.1 | 601905.7 | 20.20 | 124.7 | 9.2 | 126 | 9.5 | 99.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-32-01 | 4/29/2016 | 685294.9 | 601951.8 | 19.90 | 124.5 | 8.7 | 126 | 9.5 | 98.8 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-33-01 | 4/29/2016 | 685267.6 | 601932.2 | 20.10 | 114.7 | 10.2 | 126 | 9.5 | 91.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-35-01 | 4/29/2016 | 685251.4 | 601960.8 | 19.80 | 113.7 | 10.5 | 126 | 9.5 | 90.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 7 | SF-07-07 | 5/2/2016 | 685098.9 | 602107.7 | 13.20 | 113.7 | 2.2 | 112.2 | 9.7 | 101.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 7 | SF-08-07 | 5/2/2016 | 685131.4 | 602134.6 | 13.40 | 113.2 | 3.4 | 112.2 | 9.7 | 100.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 7 | SF-09-07 | 5/2/2016 | 685141.4 | 602154.3 | 13.20 | 113.0 | 2.1 | 112.2 | 9.7 | 100.7 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-07-08 | 5/2/2016 | 685090.8 | 602099.0 | 14.20 | 119.6 | 4.0 | 112.2 | 9.7 | 106.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-08-08 | 5/2/2016 | 685126.1 | 602130.8 | 14.50 | 116.2 | 2.6 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-09-08 | 5/2/2016 | 685060.5 | 602159.1 | 14.00 | 117.3 | 3.4 | 112.2 | 9.7 | 104.5 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | CS-43-01 | 5/2/2016 | 685178.7 | 602060.3 | 17.20 | 119.7 | 10.1 | 117 | 8.6 | 102.3 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-44-01 | 5/2/2016 | 685227.7 | 602065.5 | 17.70 | 115.8 | 7.3 | 117 | 8.6 | 99.0 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-45-01 | 5/2/2016 | 685152.4 | 602803.2 | 17.60 | 114.5 | 7.1 | 117 | 8.6 | 97.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-46-01 | 5/2/2016 | 685108.7 | 602067.4 | 15.00 | 109.9 | 7.8 | 117 | 8.6 | 93.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | HC-34-01 | 5/2/2016 | 685227.3 | 601914.0 | 20.50 | 117.5 | 10.3 | 126 | 9.5 | 93.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-36-01 | 5/2/2016 | 685269.4 | 601989.1 | 19.50 | 119.1 | 11.1 | 126 | 9.5 | 94.5 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-37-01 | 5/2/2016 | 685232.0 | 601988.5 | 19.30 | 115.0 | 9.8 | 126 | 9.5 | 91.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-38-01 | 5/2/2016 | 685181.9 | 601969.6 | 19.30 | 113.7 | 11.7 | 126 | 9.5 | 90.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-39-01 | 5/2/2016 | 685213.9 | 602004.5 | 18.70 | 116.0 | 8.9 | 126 | 9.5 | 92.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-40-01 | 5/2/2016 | 685226.0 | 602151.1 | 18.10 | 125.0 | 10.0 | 126 | 9.5 | 99.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-41-01 | 5/2/2016 | 685199.7 | 602037.5 | 18.00 | 120.1 | 10.4 | 126 | 9.5 | 95.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 9 | SF-07-09 | 5/5/2016 | 685008.1 | 602099.3 | 14.90 | 120.0 | 3.5 | 112.2 | 9.7 | 107.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 9 | SF-08-09 | 5/5/2016 | 685134.3 | 602127.7 | 15.00 | 123.4 | 3.2 | 112.2 | 9.7 | 110.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 9 | SF-09-09 | 5/5/2016 | 685169.3 | 602144.8 | 14.90 | 115.7 | 4.2 | 112.2 | 9.7 | 103.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-07-10 | 5/5/2016 | 685087.7 | 602155.6 | 16.50 | 120.4 | 4.4 | 112.2 | 9.7 | 107.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-08-10 | 5/5/2016 | 685117.3 | 602137.9 | 16.60 | 111.9 | 3.8 | 112.2 | 9.7 | 99.7 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-09-10 | 5/5/2016 | 685155.3 | 602167.4 | 16.30 | 107.8 | 3.1 | 112.2 | 9.7 | 96.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | HC-42-01 | 5/5/2016 | 685157.1 | 602028.8 | 17.80 | 117.3 | 11.6 | 126 | 9.5 | 93.1 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-43-01 | 5/5/2016 | 685169.9 | 602065.8 | 17.80 | 117.2 | 12.1 | 126 | 9.5 | 93.0 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-44-01 | 5/5/2016 | 685193.6 | 602102.8 | 18.00 | 124.0 | 11.7 | 126 | 9.5 | 98.4 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-45-01 | 5/5/2016 | 685166.2 | 602112.5 | 18.40 | 123.3 | 10.3 | 126 | 9.5 | 97.9 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-46-01 | 5/5/2016 | 685107.4 | 602064.3 | 15.40 | 125.5 | 11.6 | 126 | 9.5 | 99.6 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-47-01 | 5/5/2016 | 685140.2 | 602092.3 | 18.30 | 121.2 | 9.2 | 126 | 9.5 | 96.2 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | CS-50-01 | 5/11/2016 | 685060.3 | 602129.0 | 16.00 | 114.9 | 9.2 | 117 | 8.6 | 98.2 | 90 | 14 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-51-01 | 5/11/2016 | 685095.6 | 602173.6 | 18.80 | 115.3 | 9.2 | 117 | 8.6 | 98.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-52-01 | 5/11/2016 | 685118.1 | 602212.6 | 18.30 | 116.9 | 9.2 | 117 | 8.6 | 99.9 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-53-01 | 5/11/2016 | 685077.2 | 602198.8 | 18.80 | 115.3 | 9.8 | 117 | 8.6 | 98.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-54-01 | 5/11/2016 | 685018.9 | 602196.7 | 19.40 | 113.0 | 8.8 | 117 | 8.6 | 96.6 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-55-01 | 5/11/2016 | 685037.7 | 602225.0 | 16.90 | 112.7 | 13.2 | 117 | 8.6 | 96.3 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-57-01 | 5/11/2016 | 685029.4 | 602258.5 | 17.50 | 116.7 | 11.6 | 117 | 8.6 | 99.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-58-01 | 5/11/2016 | 684989.3 | 602236.4 | 20.10 | 117.6 | 9.4 | 117 | 8.6 | 100.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-59-01 | 5/11/2016 | 685005.7 | 602278.3 | 17.80 | 119.0 | 11.8 | 117 | 8.6 | 101.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-61-01 | 5/11/2016 | 684990.1 | 602311.3 | 18.30 | 112.5 | 14.7 | 117 | 8.6 | 96.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-62-01 | 5/11/2016 | 684954.1 | 602272.2 | 20.80 | 116.1 | 9.5 | 117 | 8.6 | 99.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-63-01 | 5/11/2016 | 684978.4 | 602338.7 | 18.70 | 110.8 | 6.8 | 117 | 8.6 | 94.7 | 90 | 15 | GDL Cover Soil | | V5N |
| 11 | SF-07-11 | 5/11/2016 | 685085.8 | 602102.0 | 17.60 | 108.4 | 2.1 | 112.2 | 9.7 | 96.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 11 | SF-08-11 | 5/11/2016 | 685120.0 | 602122.7 | 17.80 | 107.5 | 2.5 | 112.2 | 9.7 | 95.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 11 | SF-09-11 | 5/11/2016 | 685157.2 | 602150.4 | 17.70 | 109.8 | 2.6 | 112.2 | 9.7 | 97.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 3 | SF-01-03 | 5/11/2016 | 685512.3 | 601525.2 | 19.30 | 113.1 | 2.0 | 112.2 | 9.7 | 100.8 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 3 | SF-02-03 | 5/11/2016 | 685546.3 | 601552.4 | 19.40 | 116.2 | 2.4 | 112.2 | 9.7 | 103.6 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 3 | SF-03-03 | 5/11/2016 | 685585.6 | 601575.9 | 19.30 | 116.9 | 2.0 | 112.2 | 9.7 | 104.2 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 1 | HC-48-01 | 5/16/2016 | 685126.3 | 602180.8 | 19.30 | 114.6 | 14.9 | 126 | 9.5 | 91.0 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-49-01 | 5/16/2016 | 685093.4 | 602149.0 | 17.00 | 145.7 | 9.9 | 126 | 9.5 | 115.6 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-50-01 | 5/16/2016 | 685061.4 | 602128.9 | 16.50 | 119.8 | 13.2 | 126 | 9.5 | 95.1 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-51-01 | 5/16/2016 | 685096.6 | 602178.9 | 19.30 | 120.1 | 11.0 | 126 | 9.5 | 95.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-52-01 | 5/16/2016 | 685119.9 | 602212.3 | 18.80 | 114.5 | 11.6 | 126 | 9.5 | 90.9 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-53-01 | 5/16/2016 | 685054.2 | 602219.1 | 19.60 | 118.1 | 10.7 | 126 | 9.5 | 93.7 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-54-01 | 5/16/2016 | 685019.8 | 602191.5 | 19.80 | 114.2 | 12.4 | 126 | 9.5 | 90.6 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-55-01 | 5/16/2016 | 685054.2 | 602219.1 | 19.60 | 120.1 | 12.8 | 126 | 9.5 | 95.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-56-01 | 5/16/2016 | 685075.9 | 602263.9 | 19.80 | 116.8 | 12.7 | 126 | 9.5 | 92.7 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-57-01 | 5/16/2016 | 685032.7 | 602252.7 | 17.90 | 118.6 | 9.8 | 126 | 9.5 | 94.1 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-58-01 | 5/16/2016 | 684988.4 | 602235.8 | 20.60 | 114.7 | 11.1 | 126 | 9.5 | 91.0 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-59-01 | 5/16/2016 | 685010.1 | 602267.9 | 18.10 | 122.6 | 8.7 | 126 | 9.5 | 97.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | CS-56-01 | 5/16/2016 | 685025.1 | 602299.5 | 20.30 | 118.5 | 11.5 | 117 | 8.6 | 101.3 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-60-01 | 5/16/2016 | 685025.9 | 602329.2 | 18.00 | 113.1 | 11.9 | 117 | 8.6 | 96.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 5 | SF-04-05 | 5/16/2016 | 685352.5 | 601871.7 | 19.40 | 114.6 | 1.5 | 112.2 | 9.7 | 102.1 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 3 | SF-05-03 | 5/16/2016 | 685321.5 | 601855.6 | 19.70 | 117.7 | 1.8 | 112.2 | 9.7 | 104.9 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 3 | SF-06-03 | 5/16/2016 | 685289.7 | 601832.8 | 19.70 | 108.3 | 1.4 | 112.2 | 9.7 | 96.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 1 | CS-64-01 | 5/18/2016 | 684999.1 | 602372.6 | 18.70 | 115.6 | 7.7 | 117 | 8.6 | 98.8 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-65-01 | 5/18/2016 | 684995.4 | 602360.5 | 18.90 | 116.5 | 11.3 | 117 | 8.6 | 99.6 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-66-01 | 5/18/2016 | 684907.9 | 602343.4 | 19.00 | 120.8 | 9.0 | 117 | 8.6 | 103.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-67-01 | 5/18/2016 | 684935.3 | 602386.4 | 18.90 | 115.3 | 11.1 | 117 | 8.6 | 98.5 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-68-01 | 5/18/2016 | 684960.5 | 602427.3 | 18.80 | 112.6 | 9.6 | 117 | 8.6 | 96.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-69-01 | 5/18/2016 | 684918.4 | 602414.4 | 18.70 | 114.0 | 11.0 | 117 | 8.6 | 97.4 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-71-01 | 5/18/2016 | 684888.7 | 602434.3 | 18.00 | 116.7 | 12.4 | 117 | 8.6 | 99.7 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-72-01 | 5/18/2016 | 684917.8 | 602480.4 | 18.00 | 117.5 | 8.8 | 117 | 8.6 | 100.4 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | HC-49-01R | 5/18/2016 | 685093.4 | 602149.0 | 17.00 | 117.5 | 9.9 | 126 | 9.5 | 93.3 | 90 | 14 | Horizon C | Back Scatter; re-run test | V5N |
| 1 | CS-70-01 | 5/20/2016 | 684860.3 | 602329.6 | 18.20 | 111.8 | 7.6 | 117 | 8.6 | 95.6 | 90 | 16 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-73-01 | 5/20/2016 | 684869.9 | 602462.4 | 17.40 | 115.6 | 11.7 | 117 | 8.6 | 98.8 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-74-01 | 5/20/2016 | 684821.2 | 602444.5 | 16.60 | 116.4 | 12.6 | 117 | 8.6 | 99.5 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-75-01 | 5/20/2016 | 684852.3 | 602488.7 | 16.60 | 114.2 | 10.0 | 117 | 8.6 | 97.6 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | HC-60-01 | 5/20/2016 | 685036.3 | 602315.7 | 18.50 | 117.4 | 9.5 | 126 | 9.5 | 93.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-61-01 | 5/20/2016 | 685958.1 | 602318.7 | 19.30 | 123.7 | 11.9 | 126 | 9.5 | 98.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-62-01 | 5/20/2016 | 684943.1 | 602291.6 | 21.70 | 116.8 | 10.2 | 126 | 9.5 | 92.7 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-63-01 | 5/20/2016 | 684974.6 | 602334.4 | 19.20 | 116.1 | 13.3 | 126 | 9.5 | 92.1 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-64-01 | 5/20/2016 | 685000.9 | 602370.5 | 19.20 | 116.7 | 9.4 | 126 | 9.5 | 92.6 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-65-01 | 5/20/2016 | 684954.1 | 602361.6 | 19.50 | 120.6 | 13.2 | 126 | 9.5 | 95.7 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-66-01 | 5/20/2016 | 684906.2 | 602342.6 | 19.50 | 114.5 | 11.8 | 126 | 9.5 | 90.9 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-68-01 | 5/20/2016 | 684955.8 | 602413.4 | 19.40 | 120.4 | 12.5 | 126 | 9.5 | 95.6 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-69-01 | 5/20/2016 | 684906.3 | 602419.1 | 19.00 | 123.7 | 10.1 | 126 | 9.5 | 98.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-70-01 | 5/20/2016 | 684858.7 | 302396.2 | 18.70 | 124.3 | 11.1 | 126 | 9.5 | 98.7 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-71-01 | 5/20/2016 | 684882.1 | 602433.1 | 18.50 | 114.6 | 13.6 | 126 | 9.5 | 91.0 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-72-01 | 5/20/2016 | 684913.9 | 602473.4 | 18.60 | 124.6 | 11.3 | 126 | 9.5 | 98.9 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-73-01 | 5/20/2016 | 684870.2 | 602464.3 | 18.00 | 122.3 | 12.4 | 126 | 9.5 | 97.1 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-74-01 | 5/20/2016 | 684819.9 | 602423.5 | 16.90 | 124.6 | 11.3 | 126 | 9.5 | 98.9 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | CS-76-01 | 5/27/2016 | 684877.8 | 602531.3 | 19.20 | 107.5 | 6.6 | 117 | 8.6 | 91.9 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-77-01 | 5/27/2016 | 684831.7 | 602514.5 | 15.90 | 111.5 | 9.1 | 117 | 8.6 | 95.3 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-78-01 | 5/27/2016 | 684774.7 | 602493.1 | 14.40 | 111.0 | 8.8 | 117 | 8.6 | 94.9 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-79-01 | 5/27/2016 | 684809.3 | 602541.2 | 17.60 | 111.8 | 6.4 | 117 | 8.6 | 95.6 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-80-01 | 5/27/2016 | 684830.6 | 602582.9 | 15.20 | 113.6 | 9.0 | 117 | 8.6 | 97.1 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-81-01 | 5/27/2016 | 684786.1 | 602567.2 | 14.90 | 113.7 | 8.1 | 117 | 8.6 | 97.2 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-82-01 | 5/27/2016 | 684747.7 | 602551.4 | 14.30 | 108.8 | 8.0 | 117 | 8.6 | 93.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-83-01 | 5/27/2016 | 684775.8 | 602598.9 | 15.40 | 108.9 | 8.7 | 117 | 8.6 | 93.1 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-84-01 | 5/27/2016 | 684806.4 | 602648.6 | 15.30 | 107.6 | 10.1 | 117 | 8.6 | 92.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-85-01 | 5/27/2016 | 684758.7 | 602624.2 | 18.20 | 111.2 | 7.6 | 117 | 8.6 | 95.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | HC-67-01 | 5/27/2016 | 684934.5 | 602386.8 | 19.50 | 122.9 | 10.4 | 126 | 9.5 | 97.5 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-75-01 | 5/27/2016 | 684852.9 | 602485.9 | 17.20 | 114.0 | 7.0 | 126 | 9.5 | 90.5 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-76-01 | 6/2/2016 | 684876.3 | 602531.1 | 19.70 | 119.3 | 9.3 | 126 | 9.5 | 94.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-77-01 | 6/2/2016 | 684830.6 | 602514.8 | 16.40 | 122.3 | 8.4 | 126 | 9.5 | 97.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-78-01 | 6/2/2016 | 684776.0 | 602494.2 | 15.10 | 114.4 | 8.4 | 126 | 9.5 | 90.8 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-79-01 | 6/2/2016 | 684810.5 | 602540.7 | 18.10 | 122.2 | 7.3 | 126 | 9.5 | 97.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-80-01 | 6/2/2016 | 684834.1 | 602583.5 | 15.80 | 121.5 | 8.2 | 126 | 9.5 | 96.4 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-81-01 | 6/2/2016 | 684789.9 | 602568.2 | 15.50 | 122.3 | 12.2 | 126 | 9.5 | 97.1 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-82-01 | 6/2/2016 | 684752.2 | 602543.1 | 17.30 | 126.2 | 10.2 | 126 | 9.5 | 100.2 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-83-01 | 6/2/2016 | 684781.1 | 602601.8 | 16.00 | 118.6 | 10.2 | 126 | 9.5 | 94.1 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-84-01 | 6/2/2016 | 684801.5 | 602638.4 | 17.70 | 124.5 | 9.3 | 126 | 9.5 | 98.8 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-85-01 | 6/2/2016 | 684757.6 | 602625.7 | 18.70 | 121.4 | 8.7 | 126 | 9.5 | 96.3 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-86-01 | 6/2/2016 | 684704.4 | 602572.9 | 8.10 | 126.9 | 11.6 | 126 | 9.5 | 100.7 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-87-01 | 6/2/2016 | 684739.4 | 602607.5 | 18.30 | 124.2 | 9.8 | 126 | 9.5 | 98.6 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-88-01 | 6/2/2016 | 684755.1 | 602716.9 | 16.70 | 113.2 | 13.2 | 126 | 9.5 | 90.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-89-01 | 6/2/2016 | 684729.9 | 602698.7 | 19.60 | 115.7 | 11.8 | 126 | 9.5 | 91.8 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-90-01 | 6/2/2016 | 684676.0 | 602662.2 | 19.50 | 127.3 | 11.2 | 126 | 9.5 | 101.0 | 90 | 7 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | TEST | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | HC-91-01 | 6/2/2016 | 684684.9 | 602718.4 | 17.30 | 120.5 | 12.8 | 126 | 9.5 | 95.6 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-92-01 | 6/2/2016 | 684700.5 | 602765.4 | 20.60 | 113.6 | 9.3 | 126 | 9.5 | 90.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-93-01 | 6/2/2016 | 684673.2 | 602735.5 | 17.70 | 116.1 | 13.6 | 126 | 9.5 | 92.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-94-01 | 6/2/2016 | 684616.3 | 602716.8 | 18.00 | 125.0 | 9.4 | 126 | 9.5 | 99.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-95-01 | 6/2/2016 | 684650.6 | 602768.2 | 18.70 | 120.9 | 12.6 | 126 | 9.5 | 96.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-96-01 | 6/2/2016 | 684681.4 | 602798.3 | 18.90 | 113.5 | 12.7 | 126 | 9.5 | 90.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 8 | SF-10-8R | 6/2/2016 | 684712.5 | 602638.8 | 17.50 | 111.0 | 1.5 | 112.2 | 8.6 | 99.1 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 8 | SF-11-8R | 6/2/2016 | 684758.7 | 602671.8 | 17.40 | 110.5 | 1.8 | 112.2 | 8.6 | 98.7 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 9 | SF-10-9R | 6/2/2016 | 684715.2 | 602640.1 | 18.40 | 113.7 | 1.4 | 112.2 | 8.6 | 101.5 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 9 | SF-11-9R | 6/2/2016 | 684759.7 | 602673.9 | 18.40 | 115.7 | 1.4 | 112.2 | 8.6 | 103.3 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 10 | SF-19-10 | 6/15/2016 | 684509.5 | 602871.3 | 18.50 | 108.3 | 2.9 | 112.2 | 8.6 | 96.7 | 95 | 5 | Structural Fill - Tilcon | D Street Corridor-final el | V5N |
| 10 | SF-20-10 | 6/15/2016 | 684550.8 | 602901.1 | 19.00 | 108.7 | 2.6 | 112.2 | 8.6 | 97.0 | 95 | 5 | Structural Fill - Tilcon | D Street Corridor-final el | V5N |


Notes: Maximum Dry Density for Celgene GDL Cover Soil (CS) based on Vertical 5 Northeast Inc Sample ID 12691 approved in Entact Submittal 112B
Maximum Dry Density for 6 inch lift of Horizon C based on Vertical 5 Northeast Inc Sample ID 12934
Maximum Dry Density for Liberty Structural Fill (SF) based on Vertical 5 Northeast Inc Sample ID 12924 approved in Entact Submittal 117A
Maximum Dry Density for Tilcon Structural Fill (SF) based on Vertical 5 Northeast Inc Sample ID 13163 approved in Entact Submittal 128
Sample ID CS-1-2 Where:
CS=Cover Soil; HC=Horizon C; SF=Structural Fill
1 = Test Location as noted on Compaction Location Figures
2 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again

HC-107 became a Structural Fill test location after the D Street Corridor was widened

## 2.0 Test Location Drawings

- **GDL Cover Soil**
- **Horizon C**
- **Structural Fill**

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION CS-XX


GDL COVER SOIL ELEVATION CONTOURS


ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

| | |
|---|---|
| DRAWING NAME | GDL COVER SOIL COMPACTION LOCATIONS |
| PROJECT NAME & LOCATION | HONEYWELL SA-6 REMEDIATION<br>JERSEY CITY, NJ |

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | C. CYMBOR | APPROVED BY | | | |
| DATE | 10/15/15 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

2) HC-107 became a structural fill test location after the D street corridor was widened.

LEGEND:

COMPACTION TEST LOCATION HC-XX

GDL COVER SOIL ELEVATION CONTOURS



ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102



DRAWING NAME: HORIZON C PLANTING SOIL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | | |
| DATE | 06/17/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION SF-XX

PLANTING SOIL BOUNDARIES

STRUCTURAL FILL

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102


DRAWING NAME: STRUCTURAL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | | |
| DATE | 05/19/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |


# APPENDIX N

# SHEETPILE DOCUMENTATION




NOTES:

1. PLAN LOCATION AND TOP ELEVATION OF HYDRAULIC BARRIER BASED ON SURVEY COMPLETED UNDER SUPERVISON OF MASER AND REPRSENTS THE FINAL ELEVATION AFTER THE WALL WAS CUT TO MATCH DESIGN LINER GRADES.
2. BOTTOM OF HYDRAULIC BARRIER AND EXTENT OF EPOXY COATING BASED ON ENTACT TOP SURVEY AND SHEET PILE FABRICATION DRAWINGS. ALL SHEETS DELIVERED TO THE SITE WERE INSPECTED BY AMEC PERSONNEL TO VERIFY LENGTHS AND EPOXY COATING.
3. STRATUM D SHOWN FOR REFERENCE ONLY AND IS BASED ON GEOTECHNICAL BORINGS COMPLETED DURING THE PRELIMINARY DESIGN INVESTIGATION.




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 2/10/16 | TDD | TDD | RJR | TDD |

REVISION: DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT

| BY | APVD |
|---|---|
| TDD | SGS |

NJ PROFESSIONAL ENGINEER LICENSE NUMBER: SGS

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2629

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-201 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTED MATERIAL, AND IS LOANED SUBJECT TO RETURN UPON DEMAND. IT IS NOT TO BE REPRODUCED, IN WHOLE OR IN PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:06 PM




NOTES:

1. REFER TO NOTES 1 THRU 3 ON SHEET S-201




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| 1 | 2/10/16 | DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT | TDD | APVD | TDD | SGS |
| DSGN | | DR | RJR | TDD | | SGS |

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL


HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 585 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-202 |
| SHEET | OF |


FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:05 PM




MATCH LINE SHEET S-202


NOTES:

1. REFER TO NOTES 1 THRU 3 ON SHEET S-201




SEE NOTE HB19 ON SHEET GN-003

SHEET SEALING DETAIL (F)
NTS
SN-201 | CN-301




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 2/10/16 | TDD | RJR | TDD | |

DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT

REVISION BY TDD APVD SGS

NJ PROFESSIONAL ENGINEER LICENSE NUMBER SGS

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 588 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-203 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:02 PM

**APPENDIX O**

**VIBRATION MONITORING**
**(CD ONLY)**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

www.geocomp.com

# Vibration Monitoring

## Study Area 6 South
## Chromium Remedy

**Prepared by**
**Geocomp Engineering**
**August 13, 2013**

**Geocomp Engineering**
**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**Note**s:

- Activity for the day was sheets driving along 440 North and Jug handle
- Total number of sheets driven was two(2)
- Summary of sheet driving activity is as follows
    - Sheets driving started at 13:39 stopped at 13:42,
    - Started at 13:52 stopped at 13:57,
    - Started at 14:13 stopped at 14:14

Sheet driving activities were stopped early due to complications. Completion time was at 14:14.

**Crack Gauges**:

- Crack guages were checked at the end of day. Crack gauges show no movement.

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:51:50 August 12, 2013 |
| **Histogram Finish Time** | 11:41:55 August 13, 2013 |
| **Number of Intervals** | 46502 at 2 seconds |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |

**Notes**

| | |
|---|---|
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |


| | |
|---|---|
| **Serial Number** | BA14150 V 8.12-8.0 BlastMate III |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | July 17, 2008 by Instantel Inc. |
| **File Name** | P150EXKM.2E0 |

**Post Event Notes**
Base line data Jersey city diner Route 440 North
8-12-2013 to 8-13-2013
PPV = 0.04 in/s (Verticle)

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0400 | 0.01000 | in/s |
| **ZC Freq** | >100 | >100 | >100 | Hz |
| **Date** | Aug 12 /13 | Aug 12 /13 | Aug 12 /13 | |
| **Time** | 10:11:00 | 11:28:56 | 10:29:50 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.4 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.6 | 3.9 | |

**Peak Vector Sum** 0.0400 in/s on August 12, 2013 at 11:28:56




**Time Scale:** 10 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check

**Printed: August 13, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:07:36 August 13, 2013 |
| **Histogram Finish Time** | 15:16:23 August 13, 2013 |
| **Number of Intervals** | 3863 at 2 seconds |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |

**Notes**

| | |
|---|---|
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |

| | |
|---|---|
| **Serial Number** | BA14150 V 8.12-8.0 BlastMate III |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | July 17, 2008 by Instantel Inc. |
| **File Name** | P150EXMP.SO0 |

**Post Event Notes**


Jersey city diner Route 440 North
Data from 8-13-2013
TIme of Vibration is from 13:39 to 14:14 (2 sheets)
PPV = 0.035 in/s (Verticle) @ 13:39

**Extended Notes**

SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0350 | 0.01000 | in/s |
| **ZC Freq** | >100 | 37 | >100 | Hz |
| **Date** | Aug 13 /13 | Aug 13 /13 | Aug 13 /13 | |
| **Time** | 13:10:42 | 13:39:40 | 13:38:50 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.4 | 7.4 | Hz |
| **Overswing Ratio** | 3.6 | 3.6 | 3.8 | |

**Peak Vector Sum** 0.0357 in/s on August 13, 2013 at 13:39:40




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:13:38 August 13, 2013 |
| **Histogram Finish Time** | 15:09:01 August 13, 2013 |
| **Number of Intervals** | 115 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **File Name** | Q370EXMQ.2Q0 |

**Post Event Notes**
Utility line along Route 440 North
Vibration started from 13:39 to 14:14
PPV during the vibration period = 0.42 in/s (Verticle) @ 13:40

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.165 | 0.415 | 0.355 | in/s |
| **ZC Freq** | 37 | 30 | 30 | Hz |
| **Date** | Aug 13 /13 | Aug 13 /13 | Aug 13 /13 | |
| **Time** | 13:40:38 | 13:40:38 | 13:40:38 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.8 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.479 in/s on August 13, 2013 at 13:40:38




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check

**Printed:** August 13, 2013 (V 10.02 - 10.02) **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Date/Time** Vert at 13:39:52 August 13, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** Olushea
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BA15370 V 10.06-8.17 BlastMate III/8
**Battery Level** 6.1 Volts
**Unit Calibration** December 4, 2009 by Instantel inc.
N/A
**File Name** Q370EXMR.AG0


**Post Event Notes**
Utility line along Route 440 North
Vibration started from 13:39 to 14:14
PPV during the vibration period = 0.42 in/s (Verticle) @ 13:40

**Extended Notes**
Combo Mode August 13, 2013 13:13:37
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.165 | 0.415 | 0.355 | in/s |
| **ZC Freq** | 37 | 30 | 30 | Hz |
| **Time (Rel. to Trig)** | 0.366 | 0.390 | 0.137 | sec |
| **Peak Acceleration** | 0.119 | 0.371 | 0.199 | g |
| **Peak Displacement** | 0.00071 | 0.00218 | 0.00186 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.8 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.479 in/s at 0.388 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check
**Trigger =**

**Printed: August 13, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Vert at 13:39:52 August 13, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.1 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXMR.AG0 |
| **Operator/Setup:** | Olushea | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 13, 2013 13:13:37
SA-6 Utility line Vibration monitoring.


**Post Event Notes**

Utility line along Route 440 North
Vibration started from 13:39 to 14:14
PPV during the vibration period = 0.42 in/s (Verticle) @ 13:40






Format Copyrighted 2004-2005 Instantel Inc.





EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE


SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




KEY PLAN




Legend

Center line of Vibration Monitoring Locations

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46322

| NO. | DATE | REVISION | CHK | BY | APVD |
|---|---|---|---|---|---|
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | | |
| DSGN | G.S. | DR B.B. | G.P. | APVD P.W.D. | |

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ. 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 111173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-10-0027
DWG S-502
SHEET 60 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE RIGHTS, AND/OR COPYRIGHTABLE INFORMATION AND IS CONSIDERED CONFIDENTIAL. IT MAY NOT BE REPRODUCED THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: G:\DWGS\111\111173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

www.geocomp.com

# Vibration Monitoring Plan

## Study Area 6 South
## Chromium Remedy

**Prepared by**
**Geocomp Engineering**
**August 14, 2013**

**Geocomp Engineering**
**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**

Twelve sheets were driven in total for the day. The work commenced at 7:50am until 11:30am. The location of the seismograph was changed a total of 4 times to be at the closest distance possible to the utility lines.

A high exceedance was noted at 10:00am while the seismograph was in location 3 along jug handle. Work was stopped briefly. Meanwhile, I checked the crack gauges and did a walk-through of the basement of the diner. No changes were observed. I also checked the reading in the diner's seismograph and it showed a reading of **0.03 in/s** at the time of exceedance which is lower than the **threshold limit** of **0.375 in/s**. Upon the inspection of the geophone, I noticed that the sandbag had moved and geophone was loose. It is most likely that this was the cause of the high reading.

The exact start & stop times that the vibrations occurred were noted, as well as the time that seismograph locations were changed.

Sheet 2 –7:51 to 7:59(pair)

Sheet 3 – 8:11 to 8:12 (pair)

Sheet 4 – 8:23 to 8:24 (pair)

Sheet 5 – 9:11 to 9:12 (pair)

**Location of Geophone moved at 9:16**

Sheet 6 – 9:20 to 9:21 (pair)

**Location of Geophone moved at 9:24**

Sheet 7 – 9:27 to 9:28 (pair)

Sheet 8 – 9:43 to 9:44 (pair)

Sheet 9 – 9:53 to 9:54 (pair)

Sheet 10 – 10:01 to 10:01 (pair)

Sheet 11 – 10:25 to 10:26 (pair)

Sheet 12 – 10:32 to 10:34 (pair)

Sheet 13 – 10:44 to 10:44 (pair)

**Location of Geophone moved at 11:02**


Sheet 13 – 11:02 to 10:24 (pair)

Exceedance:

- Water/Force main Alert limit exceedance at 7:52am 0.72 in/s (Vert) , 0.61 in/s (Long)
- Water/Force main Alert limit exceedance at 9:28am 0.52in/s (Tran) , 0.61 in/s (Vert)
- Water/Force main Alert limit exceedance at 9:43am 0.71 in/s (Vert)
- Water/Force main Alert limit exceedance at 9:53am 0.675in/s (Tran) , 1.57 in/s (Vert), 1.17 in/s (Long)
- Water/Force main limit exceedance at 10:25:43 0.88 in/s (Tran), 0.98 in/s (Vert), 0.55 in/s (Long)
- Water/Force main Alert limit exceedance at 10:25:51am 0.61in/s (Tran) , 0.50in/s(Vert)
- Water/Force main Alert limit exceedance at 10:26am & 10:58am 0.88 in/s (Tran), 1.06 in/s (Vert), 0.85 in/s (Long)

Crack Guages:


Crack gauges were checked in the morning before work began, after the exceedance at 10:00 AM and afternoon after completion of work. There were no movements in cracks.





EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE


SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




KEY PLAN




Legend

Center line of Vibration Monitoring Locations

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46322

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | | | |
| DSGN | G.S. | DR | B.B. | G.P. | P.W.D. | |

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ. 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA - 225 WEST 34TH STREET, NEW YORK, NY 10122

FILE NUMBER 111173

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE RIGHTS, AND/OR COPYRIGHT INFORMATION AND IS NOT TO BE REPRODUCED THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: G:\DWGS\111\111173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report

**Histogram Start Time** 07:33:01 August 14, 2013
**Histogram Finish Time** 13:17:20 August 14, 2013
**Number of Intervals** 10329 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Operator/Setup:** `→^ xkÐ ! /NA
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BA14150 V 8.12-8.0 BlastMate III
**Battery Level** 6.7 Volts
**Unit Calibration** July 17, 2008 by Instantel Inc.
N/A
**File Name** P150EXO4.Z10

**Post Event Notes**
Jersey city diner Route 440
Data from 8-14-2013,
TIme of Vibration is from 7:50AM to 11:30AM (12 sheets)
PPV during vibration time = 0.035 in/s @ 9:27AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0450 | 0.0150 | in/s |
| **ZC Freq** | >100 | 10 | >100 | Hz |
| **Date** | Aug 14 /13 | Aug 14 /13 | Aug 14 /13 | |
| **Time** | 07:51:07 | 07:44:45 | 10:00:57 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.4 | 7.4 | Hz |
| **Overswing Ratio** | 3.6 | 3.7 | 3.8 | |

**Peak Vector Sum** 0.0456 in/s on August 14, 2013 at 07:44:45




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 07:40:55 August 14, 2013 |
| **Histogram Finish Time** | 09:14:54 August 14, 2013 |
| **Number of Intervals** | 93 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **File Name** | Q370EXO5.C70 |

**Post Event Notes**


Utility line along Route 440 North
Data from 8-14-2013
Location 1,
PPV during the vibration perid = 0.72in/s (Verticle) @ 7:52AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.150 | 0.720 | 0.610 | in/s |
| **ZC Freq** | 19 | 22 | 28 | Hz |
| **Date** | Aug 14 /13 | Aug 14 /13 | Aug 14 /13 | |
| **Time** | 07:52:55 | 07:52:55 | 07:52:55 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.8 | 7.4 | Hz |
| **Overswing Ratio** | 4.0 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.843 in/s on August 14, 2013 at 07:52:55




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

**Date/Time** Long at 07:52:17 August 14, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** ┘/NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BA15370 V 10.06-8.17 BlastMate III/8
**Battery Level** 6.2 Volts
**Unit Calibration** December 4, 2009 by Instantel inc.
N/A
**File Name** Q370EXO5.V50


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 1,
PPV during the vibration period = 0.72in/s (Verticle) @ 7:52AM

**Extended Notes**
Combo Mode August 14, 2013 07:40:55
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.150 | 0.720 | 0.610 | in/s |
| **ZC Freq** | 19 | 22 | 28 | Hz |
| **Time (Rel. to Trig)** | 0.141 | 0.188 | 0.154 | sec |
| **Peak Acceleration** | 0.186 | 0.716 | 0.331 | g |
| **Peak Displacement** | 0.00081 | 0.00504 | 0.00333 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.8 | 7.4 | Hz |
| **Overswing Ratio** | 4.0 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.843 in/s at 0.281 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check
**Trigger =** ▶——◀


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Long at 07:52:17 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.2 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXO5.V50 |
| **Operator/Setup:** | ┘/NA | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 14, 2013 07:40:55
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 1,
PPV during the vibration period = 0.72in/s (Verticle) @ 7:52AM





**Format Copyrighted 2004-2005 Instantel Inc.**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:16:45 August 14, 2013 |
| **Histogram Finish Time** | 09:22:46 August 14, 2013 |
| **Number of Intervals** | 6 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **File Name** | Q370EXO9.RX0 |

**Post Event Notes**


Utility line along Route 440 North
Data from 8-14-2013
Location 2 ,
PPV during the vibration period = 0.42 in/s (Longitude) @ 9:21AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.180 | 0.355 | 0.420 | in/s |
| **ZC Freq** | 51 | 39 | 39 | Hz |
| **Date** | Aug 14 /13 | Aug 14 /13 | Aug 14 /13 | |
| **Time** | 09:21:45 | 09:21:45 | 09:21:45 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.6 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.452 in/s on August 14, 2013 at 09:21:45




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

**Date/Time** Long at 09:21:26 August 14, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** ┼/NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BA15370 V 10.06-8.17 BlastMate III/8
**Battery Level** 6.2 Volts
**Unit Calibration** December 4, 2009 by Instantel inc.
N/A
**File Name** Q370EXO9.ZQ0


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 2
PPV during the vibration period = 0.42 in/s (Longitude) @ 9:21AM

**Extended Notes**
Combo Mode August 14, 2013 09:16:45
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.135 | 0.355 | 0.420 | in/s |
| **ZC Freq** | 57 | 39 | 39 | Hz |
| **Time (Rel. to Trig)** | 0.818 | 0.546 | 0.685 | sec |
| **Peak Acceleration** | 0.133 | 0.358 | 0.292 | g |
| **Peak Displacement** | 0.00031 | 0.00152 | 0.00149 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.6 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.452 in/s at 0.657 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check
**Trigger =**

Printed: August 15, 2013 (V 10.02 - 10.02) Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Long at 09:21:26 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.2 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXO9.ZQ0 |
| **Operator/Setup:** | ┼/NA | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 14, 2013 09:16:45
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 2
PPV during the vibration period = 0.42 in/s (Longitude) @ 9:21AM





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:24:51 August 14, 2013 |
| **Histogram Finish Time** | 10:15:49 August 14, 2013 |
| **Number of Intervals** | 50 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | /NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**
SA-6 Utility line Vibration monitoring.


| | **Tran** | **Vert** | **Long** | |
|---|---|---|---|---|
| **PPV** | 1.40 | 3.25 | 2.03 | in/s |
| **ZC Freq** | 47 | 27 | 28 | Hz |
| **Date** | Aug 14 /13 | Aug 14 /13 | Aug 14 /13 | |
| **Time** | 10:01:51 | 10:01:51 | 10:01:51 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 3.37 in/s on August 14, 2013 at 10:01:51

| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXOA.5F0 |

**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 3,
PPV during the vibration period = 3.25 in/s (Vertical) @ 10:01AM

Note: After the exceedance, inspection of the seismograph showed that the sandbag placed on geophone had moved and wasn't holding geophone in place. This was the cause of the high reading.




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.500 in/s/div Sensor Check

**Printed:** August 15, 2013 (V 10.02 - 10.02) **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Date/Time** | Tran at 09:28:00 August 14, 2013 |
| **Trigger Source** | Geo: 0.375 in/s |
| **Range** | Geo : 10.00 in/s |
| **Record Time** | 7.0 sec at 1024 sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | ¼ò7vU2þìÜá‼#U1ýº˩ úúùú ┼¿¶vec íÜÎ #5T0Ûª/NA |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXOA.AO0 |


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.61 in/s (Vertical) @ 9:28AM

**Extended Notes**
Combo Mode August 14, 2013 09:24:51
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.520 | 0.605 | 0.250 | in/s |
| **ZC Freq** | 34 | 32 | 32 | Hz |
| **Time (Rel. to Trig)** | 0.830 | 1.515 | 1.002 | sec |
| **Peak Acceleration** | 0.292 | 0.358 | 0.133 | g |
| **Peak Displacement** | 0.00221 | 0.00308 | 0.00115 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.651 in/s at 0.862 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check
**Trigger =**

Printed: August 15, 2013 (V 10.02 - 10.02) Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Tran at 09:28:00 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.2 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXOA.AO0 |
| **Operator/Setup:** | ¼ò7vU2þìÜá‼#U1ý°˩ úúùú ┼¿¶vec íÜÎ #5T0Ûª/NA | | |

**Notes**


Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6

**Extended Notes**

Combo Mode August 14, 2013 09:24:51
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.61 in/s (Vertical) @ 9:28AM





**Format Copyrighted 2004-2005 Instantel Inc.**

# Event Report

| | |
|---|---|
| **Date/Time** | Vert at 09:43:23 August 14, 2013 |
| **Trigger Source** | Geo: 0.375 in/s |
| **Range** | Geo : 10.00 in/s |
| **Record Time** | 7.0 sec at 1024 sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | d0ý½¬Ï "!ìÛÌð5WVT┼ÝÚ»à‼#!☼ü¼¬à%WgT íÛ¼ß/NA |
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. N/A |
| **File Name** | Q370EXOB.0B0 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Post Event Notes**


Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.71 in/s (Vertical) @ 9:43AM


**Extended Notes**

Combo Mode August 14, 2013 09:24:51
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.490 | 0.705 | 0.325 | in/s |
| **ZC Freq** | 37 | 34 | 34 | Hz |
| **Time (Rel. to Trig)** | 2.838 | 2.808 | 2.940 | sec |
| **Peak Acceleration** | 0.278 | 0.822 | 0.199 | g |
| **Peak Displacement** | 0.00188 | 0.00285 | 0.00138 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.735 in/s at 2.702 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check
**Trigger =**

**Printed: August 15, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Vert at 09:43:23 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.1 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXOB.0B0 |
| **Operator/Setup:** | d0ý½¬Ï "!ìÛÌð5WVT┼ÝÚ»à‼#!☼ü¼¬à%WgT íÛ¼ß/NA | | |

**Notes**


Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6

**Extended Notes**

Combo Mode August 14, 2013 09:24:51
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.71 in/s (Vertical) @ 9:43AM





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

| | |
|---|---|
| **Date/Time** | Vert at 09:53:27 August 14, 2013 |
| **Trigger Source** | Geo: 0.375 in/s |
| **Range** | Geo : 10.00 in/s |
| **Record Time** | 7.0 sec at 1024 sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | ¼ò7vU2þìÜá‼#U1ýº˩ úúùú ┼¿¶vec íÜÎ #5T0Ûª/NA |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXOB.H30 |


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 1.57 in/s (Vertical) @ 9:53AM

**Extended Notes**
Combo Mode August 14, 2013 09:24:51
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.675 | 1.57 | 1.17 | in/s |
| **ZC Freq** | 26 | 30 | 34 | Hz |
| **Time (Rel. to Trig)** | 5.317 | 5.525 | 4.868 | sec |
| **Peak Acceleration** | 0.636 | 1.48 | 0.835 | g |
| **Peak Displacement** | 0.00279 | 0.00585 | 0.00576 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 1.69 in/s at 5.525 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.500 in/s/div Sensor Check
**Trigger =**

Printed: August 15, 2013 (V 10.02 - 10.02) Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Vert at 09:53:27 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.1 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXOB.H30 |
| **Operator/Setup:** | ¼ò7vU2þìÜá‼#U1ý°˩ úúùú ┼¿¶vec íÜÎ #5T0Ûª/NA | | |

**Notes**


Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6

**Extended Notes**

Combo Mode August 14, 2013 09:24:51
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 1.57 in/s (Vertical) @ 9:53AM





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:16:30 August 14, 2013 |
| **Histogram Finish Time** | 11:02:07 August 14, 2013 |
| **Number of Intervals** | 45 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | |

| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXOC.JI0 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Post Event Notes**


Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 1.06 in/s (Vertical) @ 10:58AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.880 | 1.06 | 0.855 | in/s |
| **ZC Freq** | 30 | >100 | 28 | Hz |
| **Date** | Aug 14 /13 | Aug 14 /13 | Aug 14 /13 | |
| **Time** | 10:26:30 | 10:58:30 | 10:58:30 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 1.34 in/s on August 14, 2013 at 10:33:30




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Date/Time** Vert at 10:25:43 August 14, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** Äp[ /NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BA15370 V 10.06-8.17 BlastMate III/8
**Battery Level** 6.1 Volts
**Unit Calibration** December 4, 2009 by Instantel inc.
N/A
**File Name** Q370EXOC.YV0


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.98 in/s (Vertical) @ 10:25AM

**Extended Notes**
Combo Mode August 14, 2013 10:16:30
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.880 | 0.980 | 0.550 | in/s |
| **ZC Freq** | 30 | 30 | 30 | Hz |
| **Time (Rel. to Trig)** | 6.344 | 6.346 | 6.198 | sec |
| **Peak Acceleration** | 0.517 | 1.54 | 0.252 | g |
| **Peak Displacement** | 0.00464 | 0.00390 | 0.00279 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 1.31 in/s at 6.346 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.500 in/s/div Sensor Check
**Trigger =**


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Vert at 10:25:43 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.1 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXOC.YV0 |
| **Operator/Setup:** | Äp[ /NA | | |

**Notes**


Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6

**Extended Notes**

Combo Mode August 14, 2013 10:16:30
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.98 in/s (Vertical) @ 10:25AM





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

**Date/Time** Tran at 10:25:51 August 14, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** `d[ ↑┤•dq[ /NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BA15370 V 10.06-8.17 BlastMate III/8
**Battery Level** 6.1 Volts
**Unit Calibration** December 4, 2009 by Instantel inc.
N/A
**File Name** Q370EXOC.Z30


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.61 in/s (Transverse) @ 10:25AM

**Extended Notes**
Combo Mode August 14, 2013 10:16:30
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.610 | 0.500 | 0.265 | in/s |
| **ZC Freq** | 30 | 26 | 34 | Hz |
| **Time (Rel. to Trig)** | -0.233 | -0.027 | -0.242 | sec |
| **Peak Acceleration** | 0.345 | 0.530 | 0.133 | g |
| **Peak Displacement** | 0.00306 | 0.00203 | 0.00131 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.707 in/s at -0.230 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check
**Trigger =** ▶—— ——◀


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Tran at 10:25:51 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.1 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXOC.Z30 |
| **Operator/Setup:** | `d[ ↑┤•dq[ /NA | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 14, 2013 10:16:30
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.61 in/s (Transverse) @ 10:25AM





**Format Copyrighted 2004-2005 Instantel Inc.**

# Event Report

**Date/Time** Tran at 10:25:58 August 14, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 5.59 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** Që┐alg/NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6

**Serial Number** BA15370 V 10.06-8.17 BlastMate III/8
**Battery Level** 6.1 Volts
**Unit Calibration** December 4, 2009 by Instantel inc.
N/A
**File Name** Q370EXOC.ZA0


**Post Event Notes**
Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.43 in/s (Transverse) @ 10:25AM


**Extended Notes**
Combo Mode August 14, 2013 10:16:30
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.430 | 0.270 | 0.175 | in/s |
| **ZC Freq** | 37 | 32 | 32 | Hz |
| **Time (Rel. to Trig)** | 0.278 | 0.256 | -0.143 | sec |
| **Peak Acceleration** | 0.292 | 0.292 | 0.119 | g |
| **Peak Displacement** | 0.00176 | 0.00104 | 0.00083 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.457 in/s at 0.413 sec

**Monitor Log**
Aug 14 /13 10:25:58 Aug 14 /13 10:26:04 Event recorded. (Memory Full Exit)




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check
**Trigger =**


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Tran at 10:25:58 August 14, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.1 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 5.59 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXOC.ZA0 |
| **Operator/Setup:** | Që┐alg/NA | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 14, 2013 10:16:30
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-14-2013
Location 3
PPV during the vibration period = 0.43 in/s (Transverse) @ 10:25AM





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 11:03:34 August 14, 2013 |
| **Histogram Finish Time** | 13:13:09 August 14, 2013 |
| **Number of Intervals** | 129 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | ¬h[ ▪←Ã¹ê┐aøg/NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXOE.PY0 |

**Post Event Notes**


Utility line along Route 440 North
Data from 8-14-2013
Location 4 from 11:03:34am to 13:13:09am
PPV during the vibration period = 0.370 in/s (Vertical) @ 11:05AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.175 | 0.370 | 0.245 | in/s |
| **ZC Freq** | 32 | 32 | 37 | Hz |
| **Date** | Aug 14 /13 | Aug 14 /13 | Aug 14 /13 | |
| **Time** | 11:04:34 | 11:05:34 | 11:06:34 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.7 | 7.4 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 4.0 | |

**Peak Vector Sum** 0.406 in/s on August 14, 2013 at 11:05:34




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check

**Printed: August 15, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

www.geocomp.com

# Vibration Monitoring Plan

## Study Area 6 South
## Chromium Remedy

**Prepared by**
**Geocomp Engineering**
**August 15, 2013**

**Geocomp Engineering**
**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**

Ten sheets were driven in total for the day. The work commenced at 1:27PM until 2:43PM. The location of the seismograph was "Location 1" along route 440. The total distance of sheets driven for the day were from sta. 1+52 to sta. 1+94)

One exceedance was noted at 13:29 while the seismograph was in location 1. Distance of the sheet to the underground utility pipe was approximately 11 Feet.

The crack gauges in the diner were checked in the morning before work started and afternoon after completion of work. There were no discernable movements.

The exact start & stop time of vibration was noted. The times are as follows:-

Location 1 approx. 7.5 Feet from edge of sheet.

Sheet 1: Start time 1:27PM, stop time 1:28PM, Sta. 1+52

Sheet 2: Start time 1:42PM, stop time 1:44PM

Sheet 3: Start time 1:50PM, Stop time 1:51PM

Sheet 4: Start time 1:58PM, stop time 1:59PM

Sheet 5: Start time 2:08PM, stop time 2:09PM

Sheet 6: Start time 2:16PM, stop time 2:17PM

Sheet 7: Start time 2:24PM, stop time 2:25PM

Sheet 8: Start time 2:29PM, stop time 2:30PM

Sheet 9: Start time 2:37PM, stop time 2:38PM


Sheet 10: Start time 2:43PM, stop time 2:43, Sta. 1+94

Exceedance:

- Water/Force main threshold exceedance at 13:29. 0.42 in/s (Vert) & 0.61 in/s (Long)

Crack gauges:


There were no movements in crack gauges.





## EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




## KEY PLAN







**Legend**

Center line of Vibration Monitoring Locations

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| A | 04/15/13 | G.S. | B.B. | G.P. | P.W.D. | PWD | P.W.D. |

ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 585-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

# Event Report

**Histogram Start Time** 07:51:17 August 15, 2013
**Histogram Finish Time** 14:57:54 August 15, 2013
**Number of Intervals** 12798 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BA14150 V 8.12-8.0 BlastMate III
**Battery Level** 6.7 Volts
**Unit Calibration** July 17, 2008 by Instantel Inc.
**File Name** P150EXQ0.HH0

**Post Event Notes**
Jersey city diner Route 440
Data from 8-15-2013,
Location, Northern side of diners basement
PPV during Vbration period = 0.01in/s (Tran, Vert, Long)

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0300 | 0.01000 | in/s |
| **ZC Freq** | >100 | 14 | >100 | Hz |
| **Date** | Aug 15 /13 | Aug 15 /13 | Aug 15 /13 | |
| **Time** | 08:01:05 | 08:29:41 | 08:42:19 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.4 | 7.4 | Hz |
| **Overswing Ratio** | 3.6 | 3.6 | 3.8 | |

**Peak Vector Sum** 0.0304 in/s on August 15, 2013 at 08:29:41




**Time Scale:** 5 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Long at 13:28:37 August 15, 2013 | **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.3 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | Q370EXQG.3P0 |
| **Operator/Setup:** | !#C í¼Ýïïþðþ↕#B!┼!#B┼íÌÍïïï☼☼ò#B"┼"$2┼íÌÎï€?/s/NA | | |

**Notes**


Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6

**Extended Notes**

Combo Mode August 15, 2013 12:59:25
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-15-2013
Location 1,
PPV during the vibration period = 0.61 in/s (Verticle) @ 13:29





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

| | |
|---|---|
| **Date/Time** | Long at 13:28:37 August 15, 2013 |
| **Trigger Source** | Geo: 0.375 in/s |
| **Range** | Geo : 10.00 in/s |
| **Record Time** | 7.0 sec at 1024 sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | !#C í¼Ýïïþðþ↕#B!┼!#B┼íÌÍïïï☼☼ò#B"┼"$2┼íÌÎï€?/s/NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXQG.3P0 |


**Post Event Notes**
Utility line along Route 440 North
Data from 8-15-2013
Location 1,
PPV during the vibration period = 0.61 in/s (Verticle) @ 13:29

**Extended Notes**
Combo Mode August 15, 2013 12:59:25
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.135 | 0.420 | 0.605 | in/s |
| **ZC Freq** | 43 | 30 | 32 | Hz |
| **Time (Rel. to Trig)** | 0.299 | 0.385 | 0.380 | sec |
| **Peak Acceleration** | 0.119 | 0.345 | 0.384 | g |
| **Peak Displacement** | 0.00047 | 0.00156 | 0.00287 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.7 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.6 | 3.3 | 3.7 | |

**Peak Vector Sum** 0.605 in/s at 0.380 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check
**Trigger =**

**Printed: August 15, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 12:59:26 August 15, 2013 |
| **Histogram Finish Time** | 14:51:41 August 15, 2013 |
| **Number of Intervals** | 112 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| **File Name** | Q370EXQE.R20 |

**Post Event Notes**
Utility line along Route 440 North
Data from 8-15-2013
Location 1,
PPV during the vibration period = 0.61 in/s (Verticle) @ 13:29

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.135 | 0.420 | 0.605 | in/s |
| **ZC Freq** | 43 | 30 | 32 | Hz |
| **Date** | Aug 15 /13 | Aug 15 /13 | Aug 15 /13 | |
| **Time** | 13:29:26 | 13:29:26 | 13:29:26 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.7 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.6 | 3.3 | 3.7 | |

**Peak Vector Sum** 0.605 in/s on August 15, 2013 at 13:29:26




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check

**Printed: August 15, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

**www.geocomp.com**

# Vibration Monitoring Plan

## Study Area 6 South
## Chromium Remedy

**Prepared by**
**Geocomp Engineering**
**August 16, 2013**

**Geocomp Engineering**
**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**

Nine sheets were driven in total for the day. The work commenced at 9:21AM until 10:22AM. The location of the seismograph was "Location 1" along route 440. The sheets completed today were from Sta. 1+94 to Sta. 2+36.

Sheet driving activity moved from East to West. Seismograph was placed at Location 1, which is approximately 54' east of the first sheet installed for the day. Utility line was located at approximately 57' from first sheet. No exceedances were recorded for the duration of the sheet driving activity. .

The exact start & stop time of the vibratory machine are as follows -

Sheet 11: Start time 9:15AM, stop time 9:16AM, (Sta. 1+94)

Sheet 12: Start time 9:21AM, stop time 9:22AM

Sheet 13: Start time 9:29AM, Stop time 9:30AM

Sheet 14: Start time 9:38AM, stop time 9:39AM

Sheet 15: Start time 9:43AM, stop time 9:44AM

Sheet 16: Start time 9:48AM, stop time 9:49AM

Sheet 17: Start time 10:00AM, stop time 10:01AM

Sheet 18: Start time 10:15AM, stop time 10:16AM


Sheet 19: Start time 10:21AM, stop time 10:22AM, (Sta. 2+36)

Exceedance:

- No exceedances

Crack gauges:


There were no movements in crack gauges.





## EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'





## KEY PLAN




## SECTION A

SCALE: 1/4"=1'-0" S-502 S-502

4' 2' 0 4' 8'




## SECTION B

SCALE: 1/4"=1'-0" S-502 S-502

4' 2' 0 4' 8'

**Legend**

Center line of Vibration Monitoring Locations

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | P.W.D. |
| DSGN | G.S. | DR | CHK | B.B. | APVD | G.P. |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report

**Histogram Start Time** 07:40:55 August 16, 2013
**Histogram Finish Time** 10:32:18 August 16, 2013
**Number of Intervals** 5141 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BA14150 V 8.12-8.0 BlastMate III
**Battery Level** 6.6 Volts
**Unit Calibration** July 17, 2008 by Instantel Inc.
**File Name** P150EXRU.O70

**Post Event Notes**
Jersey city diner Route 440
Data from 8-16-2013,
TIme of Vibration is from 9:15AM to 10:22AM (9 sheets)
PPV during vibration time = 0.03 in/s (Vertical) @ 9:49AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0300 | 0.01000 | in/s |
| **ZC Freq** | >100 | 47 | >100 | Hz |
| **Date** | Aug 16 /13 | Aug 16 /13 | Aug 16 /13 | |
| **Time** | 07:53:01 | 09:49:45 | 09:15:45 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.4 | 7.4 | Hz |
| **Overswing Ratio** | 3.6 | 3.6 | 3.8 | |

**Peak Vector Sum** 0.0308 in/s on August 16, 2013 at 09:49:45




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 08:42:12 August 16, 2013 |
| **Histogram Finish Time** | 10:26:46 August 16, 2013 |
| **Number of Intervals** | 104 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | `ãs Ð©s ± /NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BA15370 V 10.06-8.17 BlastMate III/8 |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | December 4, 2009 by Instantel inc. |
| | N/A |
| **File Name** | Q370EXRX.IC0 |

**Post Event Notes**
Location 1, Utility line Monitoring
Data from 8-16-2013
Vibration time from 9:15AM to 10:22AM
PPV during the vibration period = 0.08 in/s (Long) @ 9:16AM

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.0650 | 0.0750 | in/s |
| **ZC Freq** | 73 | 28 | 37 | Hz |
| **Date** | Aug 16 /13 | Aug 16 /13 | Aug 16 /13 | |
| **Time** | 09:23:12 | 09:40:12 | 09:16:12 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.7 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.9 | |

**Peak Vector Sum** 0.0820 in/s on August 16, 2013 at 09:50:12




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

**www.geocomp.com**

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**
**August 28, 2013**

**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**

The vibration work commenced at 9:30AM until 11:50AM. The seismograph was placed along the jug handle at 2 locations. Location 1 is approximately 54' west of the utility lines and Location 2 is further west away from utilities. There were 2 exceedances recorded for the duration of the sheet driving activity.


Exceedance:

- Water/Sewer utility Alert limit exceedance of 0.5in/s at 9:34am = 0.920 in/s (Longitude)
  Note: The limit was reach at the beginning phase when sheet was attempting to break through asphalt. Vibration levels were below threshold values after the initial break.

- Water/Sewer utility Alert limit exceedance of 0.5in/s at 10:20am = 0.575 in/s(Longitude)
  Note: Limiting level of vibration was reached as a result of the sheet being pushed down making contact with adjoining sheet, thereby amplifying the vibration levels.

Crack gauges:


There were no movements in crack gauges.




EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"


30' 20' 10' 0 30' 60'




SECTION A S-502 S-502

SCALE: 1/4"=1'-0"

4' 2' 0 4' 8'





SECTION B S-502 S-502

SCALE: 1/4"=1'-0"

4' 2' 0 4' 8'

Legend

Center line of Vibration Monitoring Locations




KEY PLAN

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | P.W.D. |
| DSGN | | DR G.S. CHK B.B. | APVD G.P. | |

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-10-0027
DWG S-502
SHEET 60 OF 66

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report

**Histogram Start Time** 09:33:21 August 28, 2013
**Histogram Finish Time** 09:34:26 August 28, 2013
**Number of Intervals** 2 at 1 minute
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.3 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194EYE7.VL0

**Post Event Notes**
Utility line along Route 440 North
Data from 8-28-2013
Location 1, Along jug handle approx. 50ft from utility
PPV during the vibration period= 0.92 in/s(Long) at 9:34

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.310 | 0.565 | 0.920 | in/s |
| **ZC Freq** | 2.6 | 47 | 30 | Hz |
| **Date** | Aug 28 /13 | Aug 28 /13 | Aug 28 /13 | |
| **Time** | 09:34:26 | 09:34:26 | 09:34:26 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.5 | 3.7 | |

**Peak Vector Sum** 0.937 in/s on August 28, 2013 at 09:34:26




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Date/Time** Long at 09:34:18 August 28, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** $VS"53┼ü┘ øöøû┼á◀"┼ÿî/NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.3 Volts
**Unit Calibration** October 5, 2012 by Instantel
N/A
**File Name** N194EYE7.X60


**Post Event Notes**
Utility line along Route 440 North
Data from 8-28-2013
Location 1, Along jug handle approx. 50ft from utility
PPV during the vibration period= 0.92 in/s(Long) at 9:34

**Extended Notes**
Combo Mode August 28, 2013 09:33:20
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.310 | 0.565 | 0.920 | in/s |
| **ZC Freq** | 2.6 | 47 | 30 | Hz |
| **Time (Rel. to Trig)** | 3.315 | 3.024 | 4.033 | sec |
| **Peak Acceleration** | 0.292 | 0.451 | 0.557 | g |
| **Peak Displacement** | 0.0159 | 0.00201 | 0.00552 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.5 | 3.7 | |

**Peak Vector Sum** 0.937 in/s at 4.033 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.500 in/s/div Sensor Check
**Trigger =**


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Long at 09:34:18 August 28, 2013 | **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.3 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | October 5, 2012 by Instantel |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | N194EYE7.X60 |
| **Operator/Setup:** | $VS"53┼ü┘ øöøû┼á◀"┼ÿî/NA | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 28, 2013 09:33:20
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-28-2013
Location 1, Along jug handle approx. 50ft from utility
PPV during the vibration period= 0.92 in/s(Long) at 9:34





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:42:35 August 28, 2013 |
| **Histogram Finish Time** | 10:56:54 August 28, 2013 |
| **Number of Intervals** | 74 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194EYE8.AZ0 |

**Post Event Notes**


Utility line along Route 440 North
Data from 8-28-2013
Location 1, Along jug handle approx. 50ft from utility
PPV during the vibration period= 0.58 in/s(Long) at 10:20

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.350 | 0.475 | 0.575 | in/s |
| **ZC Freq** | 27 | 30 | 30 | Hz |
| **Date** | Aug 28 /13 | Aug 28 /13 | Aug 28 /13 | |
| **Time** | 10:20:35 | 10:20:35 | 10:20:35 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.4 | 3.7 | |

**Peak Vector Sum** 0.712 in/s on August 28, 2013 at 10:20:35




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check

**Printed: August 29, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Date/Time** Long at 10:19:49 August 28, 2013
**Trigger Source** Geo: 0.375 in/s
**Range** Geo : 10.00 in/s
**Record Time** 7.0 sec at 1024 sps
**Job Number:** 1
**Operator/Setup:** þÛªß‼B1"#332ÜÍ◄☼ÿÛªÎ"C"‼#332/NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.3 Volts
**Unit Calibration** October 5, 2012 by Instantel
N/A
**File Name** N194EYEA.110


**Post Event Notes**
Utility line along Route 440 North
Data from 8-28-2013
Location 1, Along jug handle approx. 50ft from utility
PPV during the vibration period= 0.58 in/s(Long) at 10:20

**Extended Notes**
Combo Mode August 28, 2013 09:42:35
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.350 | 0.475 | 0.575 | in/s |
| **ZC Freq** | 27 | 30 | 30 | Hz |
| **Time (Rel. to Trig)** | 1.474 | 1.820 | 1.438 | sec |
| **Peak Acceleration** | 0.239 | 0.239 | 0.384 | g |
| **Peak Displacement** | 0.00187 | 0.00234 | 0.00300 | in |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.4 | 3.7 | |

**Peak Vector Sum** 0.712 in/s at 1.473 sec




**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check
**Trigger =**


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# FFT Report

| | | | |
|---|---|---|---|
| **Date/Time** | Long at 10:19:49 August 28, 2013 | **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Trigger Source** | Geo: 0.375 in/s | **Battery Level** | 6.3 Volts |
| **Range** | Geo : 10.00 in/s | **Unit Calibration** | October 5, 2012 by Instantel |
| **Record Time** | 7.0 sec at 1024 sps | | N/A |
| **Job Number:** | 1 | **File Name** | N194EYEA.110 |
| **Operator/Setup:** | þÛªß‼B1"#332ÜÍ◄☼ÿÛªÎ"C"‼#332/NA | | |

**Notes**


| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

**Extended Notes**

Combo Mode August 28, 2013 09:42:35
SA-6 Utility line Vibration monitoring.

**Post Event Notes**

Utility line along Route 440 North
Data from 8-28-2013
Location 1, Along jug handle approx. 50ft from utility
PPV during the vibration period= 0.58 in/s(Long) at 10:20





Format Copyrighted 2004-2005 Instantel Inc.

# Event Report

**Histogram Start Time** 07:33:10 August 28, 2013
**Histogram Finish Time** 12:00:00 August 28, 2013
**Number of Intervals** 8005 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BE12235 V 10.40-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** February 4, 2013 by Instantel
**File Name** N235EYE2.BA0

**Post Event Notes**
Jersey city diner Route 440
Data from 8-28-2013,
TIme of Vibration is from 9:30AM to 11:50AM
PPV during vibration time = 0.05 in/s(Vert) @ 11:43AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0500 | 0.0150 | in/s |
| **ZC Freq** | >100 | 37 | 57 | Hz |
| **Date** | Aug 28 /13 | Aug 28 /13 | Aug 28 /13 | |
| **Time** | 07:33:34 | 11:43:50 | 11:01:44 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.2 | 3.8 | |

**Peak Vector Sum** 0.0512 in/s on August 28, 2013 at 11:43:50




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

www.geocomp.com

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**
**August 29, 2013**

**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**

The vibration work commenced at 7:30AM until 11:35AM and 12:50PM until 6:30PM. The seismograph was placed along the jug handle at total of 4 difference locations. The relocation times were at 9:22AM, 10:26AM and 11:35AM. There were a total of 2 exceedances recorded for the duration of the sheet driving activity.


Exceedance:

- Water/Sewer utility Alert limit exceedance at 12:51PM of 0.55 in/s (Longitude)

- Water/Sewer utility threshold limit exceedance of 13:14am of 0.42 in/s(Longitude)

Crack gauges:


There were no movements in crack gauges.





EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




KEY PLAN




SECTION A

SCALE: 1/4"=1'-0" S-502 S-502

4' 2' 0 4' 8'




SECTION B

SCALE: 1/4"=1'-0" S-502 S-502

4' 2' 0 4' 8'

**Legend**

Center line of Vibration Monitoring Locations

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | P.W.D. |
| DSGN | DR | CHK | APVD | |
| G.S. | B.B. | | G.P. | |

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 07:29:08 August 29, 2013 |
| **Histogram Finish Time** | 09:21:31 August 29, 2013 |
| **Number of Intervals** | 112 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | K/NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| | N/A |
| **File Name** | N194EYFW.SK0 |

**Post Event Notes**


Monitoring location was along jug handle
Data from 8-29-2013, Location 1
Vibration time from 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during recording period = 0.32 in/s (long) at 7:32AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.115 | 0.215 | 0.315 | in/s |
| **ZC Freq** | 34 | 37 | 32 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 07:32:08 | 07:39:08 | 07:32:08 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.5 | 3.7 | |

**Peak Vector Sum** 0.340 in/s on August 29, 2013 at 07:32:08




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check

**Printed:** August 29, 2013 (V 10.02 - 10.02) **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:23:19 August 29, 2013 |
| **Histogram Finish Time** | 10:24:55 August 29, 2013 |
| **Number of Intervals** | 61 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | K/NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| | N/A |
| **File Name** | N194EYG2.2V0 |

**Post Event Notes**


Monitoring location was along jug handle
Data from 8-29-2013, Location 2
Vibration time from 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during recording period = 0.09 in/s (Vertical) at 9:26AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.0900 | 0.0400 | in/s |
| **ZC Freq** | 37 | 37 | 43 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 09:26:19 | 09:26:19 | 09:43:19 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.0971 in/s on August 29, 2013 at 09:27:19




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:26:48 August 29, 2013 |
| **Histogram Finish Time** | 11:28:27 August 29, 2013 |
| **Number of Intervals** | 61 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194EYG5.0O0 |

**Post Event Notes**


Monitoring location was along jug handle
Data from 8-29-2013, Location 3
Vibration time from 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during recording period = 0.27 in/s (Longitude) at 10:27AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.170 | 0.115 | 0.265 | in/s |
| **ZC Freq** | 15 | 30 | 13 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 10:27:48 | 10:28:48 | 10:27:48 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.315 in/s on August 29, 2013 at 10:27:48




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check

**Printed:** August 29, 2013 (V 10.02 - 10.02) **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 12:44:49 August 29, 2013 |
| **Histogram Finish Time** | 18:30:20 August 29, 2013 |
| **Number of Intervals** | 345 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194EYGB.EP0 |

**Post Event Notes**


Monitoring location was along jug handle
Data from 8-29-2013, Location 4
Vibration time from 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during recording period = 0.55 in/s (long) at 12:51PM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.245 | 0.280 | 0.550 | in/s |
| **ZC Freq** | 39 | 30 | 32 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 13:23:49 | 12:51:49 | 12:51:49 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.7 | |

**Peak Vector Sum** 0.591 in/s on August 29, 2013 at 12:51:49




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check

**Printed: August 29, 2013 (V 10.02 - 10.02)** **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Histogram Start Time** 07:23:48 August 29, 2013
**Histogram Finish Time** 12:00:00 August 29, 2013
**Number of Intervals** 8286 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BE12235 V 10.40-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** February 4, 2013 by Instantel
**File Name** N235EYFW.JO0

**Post Event Notes**
Jersey city diner Route 440
Data from 8-29-2013,
TIme of Vibration was 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during vibration time = 0.05 in/s (Vertical) @ 7:38AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0450 | 0.0150 | in/s |
| **ZC Freq** | >100 | 37 | 47 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 07:24:02 | 07:38:42 | 07:38:38 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.3 | 3.7 | |

**Peak Vector Sum** 0.0461 in/s on August 29, 2013 at 07:38:42




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

**Histogram Start Time** 12:05:14 August 29, 2013
**Histogram Finish Time** 18:00:00 August 29, 2013
**Number of Intervals** 10643 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BE12235 V 10.40-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** February 4, 2013 by Instantel
**File Name** N235EYG9.KQ0

**Post Event Notes**
Jersey city diner Route 440
Data from 8-29-2013,
TIme of Vibration was 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during vibration time = 0.01 in/s (Longitude) @ 13:48AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0150 | 0.01000 | in/s |
| **ZC Freq** | >100 | 21 | >100 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 12:08:32 | 12:07:08 | 13:48:54 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.2 | 3.8 | |

**Peak Vector Sum** 0.0180 in/s on August 29, 2013 at 15:55:06




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Histogram Start Time** 18:05:14 August 29, 2013
**Histogram Finish Time** 18:36:59 August 29, 2013
**Number of Intervals** 952 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Operator/Setup:** xáe/NA
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BE12235 V 10.40-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** February 4, 2013 by Instantel
N/A
**File Name** N235EYGQ.8Q0

**Post Event Notes**
Jersey city diner Route 440
Data from 8-29-2013,
TIme of Vibration was 7:30AM to 11:35AM & 12:50PM to 6:30PM
PPV during vibration time = 0.02 in/s (Vertical) @ 18:12AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0150 | 0.00500 | in/s |
| **ZC Freq** | >100 | 85 | >100 | Hz |
| **Date** | Aug 29 /13 | Aug 29 /13 | Aug 29 /13 | |
| **Time** | 18:07:18 | 18:12:06 | 18:05:16 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.8 | 7.4 | Hz |
| **Overswing Ratio** | 3.6 | 3.2 | 3.8 | |

**Peak Vector Sum** 0.0166 in/s on August 29, 2013 at 18:16:06




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

**www.geocomp.com**

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**
**August 30, 2013**

**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**


The vibration work commenced at 7:46AM until 10:30AM. The activities for the day were sheets driving down to required grade. The seismograph was placed along the jug handle at total of 4 difference locations. The relocation times were at 9:12AM, 9:43AM and 10:16AM. There were no exceedances recorded for the duration of the sheet driving activity.

Exceedance:

None

Crack gauges:


There were no movements in crack gauges.





EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




KEY PLAN




SECTION A

SCALE: 1/4"=1'-0"

S-502 S-502

4' 2' 0 4' 8'




SECTION B

SCALE: 1/4"=1'-0"

S-502 S-502

4' 2' 0 4' 8'

**Legend**

Center line of Vibration Monitoring Locations

PETER W. DEMING

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | | DR | | | | P.W.D. |
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | B.B. | G.P. | PWD | |
| | | G.S. | | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report

**Histogram Start Time** 07:39:01 August 30, 2013
**Histogram Finish Time** 10:44:03 August 30, 2013
**Number of Intervals** 5550 at 2 seconds
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Operator/Setup:** ┘/NA
**Notes**
Location: Jersey City Diner
Cleint: ENTACT
User Name: Geocomp
General: SA-6 Vibration Monitoring


**Serial Number** BE12235 V 10.40-8.17 MiniMate Plus
**Battery Level** 6.4 Volts
**Unit Calibration** February 4, 2013 by Instantel
N/A
**File Name** N235EYHR.X10

**Post Event Notes**
Jersey city diner Route 440, Data from 8-30-2013,
Activity was driving sheets down to grade
Time of Vibration from 7:46AM to 10:36AM
PPV during vibration time = 0.045 in/s(Vertical) @ 10:13AM

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0450 | 0.0150 | in/s |
| **ZC Freq** | >100 | 37 | 47 | Hz |
| **Date** | Aug 30 /13 | Aug 30 /13 | Aug 30 /13 | |
| **Time** | 07:39:45 | 10:13:37 | 10:22:17 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.3 | 3.8 | |

**Peak Vector Sum** 0.0461 in/s on August 30, 2013 at 10:13:39




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 07:43:37 August 30, 2013 |
| **Histogram Finish Time** | 09:12:16 August 30, 2013 |
| **Number of Intervals** | 88 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194EYHS.4P0 |

**Post Event Notes**


Monitoring location along Jug handle, Location 1
Activity was driving sheets to grade, 8-30-2013
Vibration time from 7:46AM to 10:30AM
PPV during monitoring period = 0.235 in/s(Long) @ 8:05AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.130 | 0.140 | 0.235 | in/s |
| **ZC Freq** | 30 | 30 | 28 | Hz |
| **Date** | Aug 30 /13 | Aug 30 /13 | Aug 30 /13 | |
| **Time** | 08:13:37 | 08:05:37 | 08:05:37 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.236 in/s on August 30, 2013 at 08:05:37




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:13:52 August 30, 2013 |
| **Histogram Finish Time** | 09:43:19 August 30, 2013 |
| **Number of Intervals** | 29 at 1 minute |
| **Range** | Geo :10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Operator/Setup:** | a┐/NA |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| | N/A |
| **File Name** | N194EYHW.B40 |

**Post Event Notes**


Monitoring location along Jug handle, Location 2
Activity was driving sheets to grade, 8-30-2013
Vibration time from 7:46AM to 10:30AM
PPV during monitoring period = 0.08 in/s(Vert) @ 9:40AM

**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0400 | 0.0800 | 0.0600 | in/s |
| **ZC Freq** | 37 | 28 | 32 | Hz |
| **Date** | Aug 30 /13 | Aug 30 /13 | Aug 30 /13 | |
| **Time** | 09:41:52 | 09:40:52 | 09:29:52 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0826 in/s on August 30, 2013 at 09:41:52




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Histogram Start Time** 09:45:02 August 30, 2013
**Histogram Finish Time** 10:16:06 August 30, 2013
**Number of Intervals** 31 at 1 minute
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Operator/Setup:** 123456/NA
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.2 Volts
**Unit Calibration** October 5, 2012 by Instantel
N/A
**File Name** N194EYHX.R20

**Post Event Notes**
Monitoring location along Jug handle, Location 3
Activity was driving sheets to grade, 8-30-2013
Vibration time from 7:46AM to 10:30AM
PPV during monitoring period = 0.12 in/s(Vert) @ 9:49AM

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0300 | 0.120 | 0.0950 | in/s |
| **ZC Freq** | 32 | 28 | 30 | Hz |
| **Date** | Aug 30 /13 | Aug 30 /13 | Aug 30 /13 | |
| **Time** | 09:54:02 | 09:49:02 | 09:54:02 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.7 | |

**Peak Vector Sum** 0.150 in/s on August 30, 2013 at 09:49:02




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check

**Printed:** August 30, 2013 (V 10.02 - 10.02) **Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

# Event Report

**Histogram Start Time** 10:17:23 August 30, 2013
**Histogram Finish Time** 10:37:50 August 30, 2013
**Number of Intervals** 20 at 1 minute
**Range** Geo :10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.2 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194EYHZ.8Z0

**Post Event Notes**
Monitoring location along Jug handle, Location 4
Activity was driving sheets to grade, 8-30-2013
Vibration time from 7:46AM to 10:30AM
PPV during monitoring period = 0.13 in/s(Long) @ 10:22AM

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0850 | 0.110 | 0.130 | in/s |
| **ZC Freq** | 28 | 30 | 32 | Hz |
| **Date** | Aug 30 /13 | Aug 30 /13 | Aug 30 /13 | |
| **Time** | 10:22:23 | 10:22:23 | 10:22:23 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.7 | 7.4 | Hz |
| **Overswing Ratio** | 4.1 | 3.1 | 4.0 | |

**Peak Vector Sum** 0.164 in/s on August 30, 2013 at 10:22:23




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format Copyrighted 2006-2008 Instantel, a division of Xmark Corporation**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

**www.geocomp.com**

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**
**October 3, 2013**

**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**
The vibration work commenced at 8:05 AM until 6:20 PM. The seismograph was placed along the jug handle at 7 locations. Location 1 and 2 were on top of the gas pipeline parallel to Rte. 440 along the sidewalk, and locations 3-7 were along the jug handle: see the site plan.

Exceedance (PPV >.5 in/s):

Force Main Alerts (in/s):

(Location 1)

8:16 AM: 0.59
9:09 AM: 1.25
9:39 AM: 0.81
9:43 AM: 1.01
9:52 AM: 1.30
9:55 AM: 1.39
10:09 AM: 0.82


(Location 2)

10:52 AM: 0.51
10:56 AM: 0.79
11:06 AM: 0.96
11:17 AM: 1.13
11:24 AM: 0.63

Locations 3-7 had no limits due to not being in the proximity of the gas or force main line, but were monitored at the contractors request as work continued nearby. See attached Blastware reports for PPV's at these locations.

Crack gauges:


There were no movements in crack gauges.




EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"


30' 20' 10' 0 30' 60'




SECTION A S-502 S-502

SCALE: 1/4"=1'-0"

4' 2' 0 4' 8'





SECTION B S-502 S-502

SCALE: 1/4"=1'-0"

4' 2' 0 4' 8'

**Legend**

Center line of Vibration Monitoring Locations




KEY PLAN

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
P.W.D. LICENSE NUMBER 46522

| NO. | DATE | DSGN | REVISION | BY | APVD |
|---|---|---|---|---|---|
| A | 04/15/13 | G.S. | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | |
| | | DR | | | APVD |
| | | CHK | | B.B. | G.P. |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report


| | |
|---|---|
| **Histogram Start Time** | 07:36:43 October 3, 2013 |
| **Histogram Finish Time** | 12:00:00 October 3, 2013 |
| **Number of Intervals** | 7899.00 at 2 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Notes** | |
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |

| | |
|---|---|
| **Serial Number** | BE12235 V 10.40-8.17 MiniMate Plus |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | February 4, 2013 by Instantel |
| **File Name** | N235F08Q.H70 |

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0200 | 0.01000 | in/s |
| **ZC Freq** | >100 | 15 | >100 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 07:36:47 | 08:13:17 | 09:52:11 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.2 | 3.8 | |

**Peak Vector Sum** 0.0206 in/s on October 3, 2013 at 08:13:17




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report


| | |
|---|---|
| **Histogram Start Time** | 12:05:14 October 3, 2013 |
| **Histogram Finish Time** | 18:00:00 October 3, 2013 |
| **Number of Intervals** | 10643.00 at 2 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Notes** | |
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |

| | |
|---|---|
| **Serial Number** | BE12235 V 10.40-8.17 MiniMate Plus |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | February 4, 2013 by Instantel |
| **File Name** | N235F092.WQ0 |

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0300 | 0.01000 | in/s |
| **ZC Freq** | >100 | 32 | >100 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 12:09:00 | 13:31:58 | 13:06:38 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.2 | 3.8 | |

**Peak Vector Sum** 0.0308 in/s on October 3, 2013 at 15:39:10




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 08:00:26 October 3, 2013 |
| **Histogram Finish Time** | 08:16:45 October 3, 2013 |
| **Number of Intervals** | 16.00 at 1 minute |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.0 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F08R.KQ0 |

**Post Event Notes**
Location 1

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.600 | 0.370 | 0.540 | in/s |
| **ZC Freq** | 37 | 32 | 24 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 08:14:26 | 08:06:26 | 08:14:26 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.824 in/s on October 3, 2013 at 08:14:26




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 08:29:52 October 3, 2013 |
| **Histogram Finish Time** | 08:54:26 October 3, 2013 |
| **Number of Intervals** | 294.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 5.9 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F08S.XS0 |

**Post Event Notes**
Location 1

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0300 | 0.01000 | in/s |
| **ZC Freq** | >100 | 15 | >100 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 08:30:02 | 08:34:22 | 08:34:32 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.7 | 7.4 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0308 in/s on October 3, 2013 at 08:34:22




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:25:36 October 3, 2013 |
| **Histogram Finish Time** | 11:25:56 October 3, 2013 |
| **Number of Intervals** | 724.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.0 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F08Y.AO0 |

**Post Event Notes**

Location 2

The PPV listed is not a true reading as the bag was kicked. Actual PPV for this time period was 1.13 in/s.


**Extended Notes**

SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | *** | 6.44 | *** | in/s |
| **ZC Freq** | 39 | >100 | 2.9 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 11:24:26 | 11:24:26 | 11:24:26 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.8 | |

**Peak Vector Sum** *** in/s on October 3, 2013 at 11:24:26

*** **: Out of Range**




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 2.00 in/s/div Sensor Check



**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 11:38:41 October 3, 2013 |
| **Histogram Finish Time** | 11:55:54 October 3, 2013 |
| **Number of Intervals** | 206.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 5.9 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F091.OH0 |

**Post Event Notes**
Location 3

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.165 | 0.190 | 0.205 | in/s |
| **ZC Freq** | 30 | 28 | 30 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 11:39:01 | 11:39:01 | 11:38:56 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.4 | 3.7 | |

**Peak Vector Sum** 0.291 in/s on October 3, 2013 at 11:38:56




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report


| | |
|---|---|
| **Histogram Start Time** | 12:49:18 October 3, 2013 |
| **Histogram Finish Time** | 13:23:52 October 3, 2013 |
| **Number of Intervals** | 414.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |

| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.0 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F094.Y60 |

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.255 | 0.235 | 0.430 | in/s |
| **ZC Freq** | 39 | 30 | 32 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 13:05:28 | 13:05:28 | 13:22:18 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.4 | 3.6 | |

**Peak Vector Sum** 0.432 in/s on October 3, 2013 at 13:22:18




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:25:25 October 3, 2013 |
| **Histogram Finish Time** | 13:35:35 October 3, 2013 |
| **Number of Intervals** | 122.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.0 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F096.MD0 |

**Post Event Notes**
Location 4

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.110 | 0.140 | 0.130 | in/s |
| **ZC Freq** | 32 | 34 | 32 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 13:30:15 | 13:30:15 | 13:30:15 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.5 | 7.1 | Hz |
| **Overswing Ratio** | 3.1 | 3.4 | 3.4 | |

**Peak Vector Sum** 0.177 in/s on October 3, 2013 at 13:30:15




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:35:55 October 3, 2013 |
| **Histogram Finish Time** | 14:54:04 October 3, 2013 |
| **Number of Intervals** | 937.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 5.9 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F097.3V0 |

**Post Event Notes**
Location 4

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.145 | 0.150 | 0.160 | in/s |
| **ZC Freq** | 30 | 32 | 14 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 14:31:15 | 14:53:45 | 14:53:25 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.4 | 3.6 | |

**Peak Vector Sum** 0.200 in/s on October 3, 2013 at 14:53:45




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 14:56:10 October 3, 2013 |
| **Histogram Finish Time** | 16:28:32 October 3, 2013 |
| **Number of Intervals** | 1108.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 5.9 Volts (Battery Low) |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F09A.TM0 |

**Post Event Notes**
Location 5

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.235 | 0.355 | 0.195 | in/s |
| **ZC Freq** | 30 | 57 | 23 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 16:26:10 | 15:41:15 | 15:57:55 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 3.8 | 3.4 | 3.7 | |

**Peak Vector Sum** 0.363 in/s on October 3, 2013 at 15:41:15




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 16:30:25 October 3, 2013
**Histogram Finish Time** 17:46:13 October 3, 2013
**Number of Intervals** 909.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 5.9 Volts (Battery Low)
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194F09F.6P0

**Post Event Notes**
Location 6

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.350 | 1.27 | 0.420 | in/s |
| **ZC Freq** | 32 | 30 | 30 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 17:43:40 | 17:43:40 | 17:43:45 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.5 | 3.8 | |

**Peak Vector Sum** 1.29 in/s on October 3, 2013 at 17:43:40




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 17:58:02 October 3, 2013 |
| **Histogram Finish Time** | 18:21:38 October 3, 2013 |
| **Number of Intervals** | 283.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 5.9 Volts (Battery Low) |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F09J.8Q0 |

**Post Event Notes**
Location 7

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.215 | 0.160 | 0.280 | in/s |
| **ZC Freq** | 32 | 30 | 30 | Hz |
| **Date** | Oct 3 /13 | Oct 3 /13 | Oct 3 /13 | |
| **Time** | 18:10:52 | 18:10:57 | 18:10:52 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.1 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.5 | 2.6 | 3.7 | |

**Peak Vector Sum** 0.315 in/s on October 3, 2013 at 18:10:57




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

**www.geocomp.com**

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**
**October 4, 2013**


**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**
The vibration work commenced at 7:45 AM until 5:00 PM. The seismograph was placed along the jug handle at 3 locations following the piledriving at the contractor's request, although there were no utilities in that area. See attached Blastware reports for PPV's at these locations.


Crack gauges:
There was no movement in the crack gauges.





EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




KEY PLAN




**Legend**

Center line of Vibration Monitoring Locations

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

| NO. | DATE | DSGN | BY | CHK | APVD |
|---|---|---|---|---|---|
| A | 04/15/13 | G.S. | DR | B.B. | G.P. |

ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | APVD
REVISION
P.W.D.

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-502 |
| SHEET | 60 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report


| | |
|---|---|
| **Histogram Start Time** | 07:15:44 October 4, 2013 |
| **Histogram Finish Time** | 12:00:00 October 4, 2013 |
| **Number of Intervals** | 8528.00 at 2 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Notes** | |
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |

| | |
|---|---|
| **Serial Number** | BE12235 V 10.40-8.17 MiniMate Plus |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | February 4, 2013 by Instantel |
| **File Name** | N235F0AK.680 |

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0200 | 0.01000 | in/s |
| **ZC Freq** | >100 | 26 | >100 | Hz |
| **Date** | Oct 4 /13 | Oct 4 /13 | Oct 4 /13 | |
| **Time** | 07:20:26 | 07:28:52 | 08:00:00 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.3 | 3.8 | |

**Peak Vector Sum** 0.0212 in/s on October 4, 2013 at 08:31:50




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report


| | |
|---|---|
| **Histogram Start Time** | 12:05:14 October 4, 2013 |
| **Histogram Finish Time** | 17:07:39 October 4, 2013 |
| **Number of Intervals** | 9072.00 at 2 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Notes** | |
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |

| | |
|---|---|
| **Serial Number** | BE12235 V 10.40-8.17 MiniMate Plus |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | February 4, 2013 by Instantel |
| **File Name** | N235F0AX.KQ0 |

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0200 | 0.01000 | in/s |
| **ZC Freq** | >100 | 51 | >100 | Hz |
| **Date** | Oct 4 /13 | Oct 4 /13 | Oct 4 /13 | |
| **Time** | 12:07:28 | 14:56:12 | 13:16:48 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.8 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.2 | 3.8 | |

**Peak Vector Sum** 0.0224 in/s on October 4, 2013 at 16:56:22




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 07:26:46 October 4, 2013 |
| **Histogram Finish Time** | 11:00:29 October 4, 2013 |
| **Number of Intervals** | 2564.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F0AK.OM0 |

**Post Event Notes**
Location 1.

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.160 | 0.285 | 0.225 | in/s |
| **ZC Freq** | 32 | 30 | 22 | Hz |
| **Date** | Oct 4 /13 | Oct 4 /13 | Oct 4 /13 | |
| **Time** | 07:54:06 | 07:53:56 | 08:10:51 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.303 in/s on October 4, 2013 at 07:53:56




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 11:02:47 October 4, 2013
**Histogram Finish Time** 11:53:37 October 4, 2013
**Number of Intervals** 610.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.2 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194F0AU.ON0

**Post Event Notes**
Location 2.

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0600 | 0.140 | 0.0950 | in/s |
| **ZC Freq** | 28 | 30 | 30 | Hz |
| **Date** | Oct 4 /13 | Oct 4 /13 | Oct 4 /13 | |
| **Time** | 11:04:22 | 11:15:27 | 11:15:27 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 3.6 | 3.4 | 3.8 | |

**Peak Vector Sum** 0.148 in/s on October 4, 2013 at 11:15:27




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 12:53:05 October 4, 2013 |
| **Histogram Finish Time** | 13:20:28 October 4, 2013 |
| **Number of Intervals** | 328.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.3 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F0AZ.SH0 |

**Post Event Notes**
Location 2.

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0300 | 0.0350 | 0.0350 | in/s |
| **ZC Freq** | 34 | 27 | 32 | Hz |
| **Date** | Oct 4 /13 | Oct 4 /13 | Oct 4 /13 | |
| **Time** | 12:58:45 | 12:58:10 | 12:58:30 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 3.7 | 3.4 | 3.8 | |

**Peak Vector Sum** 0.0391 in/s on October 4, 2013 at 13:07:50




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:22:28 October 4, 2013 |
| **Histogram Finish Time** | 17:03:56 October 4, 2013 |
| **Number of Intervals** | 2657.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.2 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F0B1.5G0 |

**Post Event Notes**
Location 3.

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0450 | 0.110 | 0.175 | in/s |
| **ZC Freq** | 11 | 10 | 13 | Hz |
| **Date** | Oct 4 /13 | Oct 4 /13 | Oct 4 /13 | |
| **Time** | 15:07:38 | 15:20:28 | 15:06:18 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.7 | 7.4 | Hz |
| **Overswing Ratio** | 3.9 | 3.4 | 3.7 | |

**Peak Vector Sum** 0.189 in/s on October 4, 2013 at 15:06:18




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

Geocomp
ENGINEERING, INC.
*Technologies to manage risk for infrastructure*

Atlanta
Boston
Chicago
New York
San Francisco

**www.geocomp.com**

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**
**October 18, 2013**

**For ENTACT, LLC**

139 Fulton St., Suite 917 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631

**NOTES:**

**Summary of Work:**

The vibration work, driving HB sheets, commenced at 8:30 AM and ran until 12:00 PM. The seismograph was placed along Route 440 at 8 locations. These ran parallel to the gas and water lines and were approximately 15-20 feet from where the work occurred. See below for exceedances.

Exceedance (PPV >.5 in/s):

Water line exceedances (in/s):

(Location 1)

9:19 AM: 0.53

(Location 2)

9:30 AM: 0.83
9:32 AM: 0.58

(Location 3)

9:48 AM: 1.16

(Location 5)

9:56 AM: 0.64

(Location 6)


10:04 AM: 0.66

(Location 1)

11:40 AM: 0.51
11:41 AM: 1.25

Crack gauges:


There were no movements in crack gauges.




EXCAVATION AREA PARTIAL PLAN AT ROUTE 440 AND JUG HANDLE

SCALE: 1"=30'-0"


30' 20' 10' 0 30' 60'




SECTION A S-502 S-502

SCALE: 1/4"=1'-0"

4' 2' 0 4' 8'





SECTION B S-502 S-502

SCALE: 1/4"=1'-0"

4' 2' 0 4' 8'

Legend

Center line of Vibration Monitoring Locations




KEY PLAN

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | P.W.D. |
| DSGN | G.S. | DR | CHK | B.B. | APVD | G.P. |

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 46522

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTIONS

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-10-0027
DWG S-502
SHEET 60 OF 66

FILE NAME: G:\DWGS\111\11173\S-502.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM

# Event Report


| | |
|---|---|
| **Histogram Start Time** | 07:15:36 October 18, 2013 |
| **Histogram Finish Time** | 11:52:37 October 18, 2013 |
| **Number of Intervals** | 8310.00 at 2 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Notes** | |
| Location: | Jersey City Diner |
| Cleint: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 Vibration Monitoring |

| | |
|---|---|
| **Serial Number** | BE12235 V 10.40-8.17 MiniMate Plus |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | February 4, 2013 by Instantel |
| **File Name** | N235F10H.I00 |

**Extended Notes**
SA-6 vibration monitoring. Jersey CIty Diner Route 440.
Job #P8138

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0200 | 0.01000 | in/s |
| **ZC Freq** | >100 | 18 | >100 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 07:16:38 | 07:58:58 | 11:29:38 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.7 | 7.5 | Hz |
| **Overswing Ratio** | 3.6 | 3.3 | 3.8 | |

**Peak Vector Sum** 0.0212 in/s on October 18, 2013 at 07:58:58




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 08:20:32 October 18, 2013 |
| **Histogram Finish Time** | 09:23:12 October 18, 2013 |
| **Number of Intervals** | 751.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F10K.I80 |

**Post Event Notes**
Location 1

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.145 | 0.535 | 0.200 | in/s |
| **ZC Freq** | 28 | 32 | 30 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 09:15:32 | 09:15:32 | 09:09:32 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.572 in/s on October 18, 2013 at 09:15:32




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:24:52 October 18, 2013 |
| **Histogram Finish Time** | 09:34:25 October 18, 2013 |
| **Number of Intervals** | 114.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F10N.HG0 |

**Post Event Notes**
Location 2

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.210 | 0.830 | 0.135 | in/s |
| **ZC Freq** | 30 | 30 | 30 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 09:32:27 | 09:27:12 | 09:32:27 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.6 | 3.9 | |

**Peak Vector Sum** 0.840 in/s on October 18, 2013 at 09:27:12




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 09:35:47 October 18, 2013
**Histogram Finish Time** 09:48:59 October 18, 2013
**Number of Intervals** 158.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.1 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194F10N.ZN0

**Post Event Notes**
Location 3

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.255 | 1.16 | 0.275 | in/s |
| **ZC Freq** | 43 | 28 | 47 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 09:42:17 | 09:46:32 | 09:42:17 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.7 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.9 | |

**Peak Vector Sum** 1.17 in/s on October 18, 2013 at 09:46:32




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 09:50:37 October 18, 2013
**Histogram Finish Time** 09:53:00 October 18, 2013
**Number of Intervals** 28.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.1 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194F10O.OD0

**Post Event Notes**
Location 4

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.145 | 0.270 | 0.315 | in/s |
| **ZC Freq** | 39 | 43 | 37 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 09:51:42 | 09:51:32 | 09:51:32 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.7 | 7.2 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.386 in/s on October 18, 2013 at 09:51:32




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:54:51 October 18, 2013 |
| **Histogram Finish Time** | 09:59:06 October 18, 2013 |
| **Number of Intervals** | 50.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F10O.VF0 |

**Post Event Notes**
Location 5

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.175 | 0.450 | 0.645 | in/s |
| **ZC Freq** | 30 | 28 | 39 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 09:56:16 | 09:56:16 | 09:56:26 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.690 in/s on October 18, 2013 at 09:56:16




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:00:48 October 18, 2013 |
| **Histogram Finish Time** | 10:06:43 October 18, 2013 |
| **Number of Intervals** | 71.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F10P.5C0 |

**Post Event Notes**
Location 6

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.390 | 0.665 | 0.380 | in/s |
| **ZC Freq** | 32 | 34 | 30 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 10:04:28 | 10:04:33 | 10:04:33 | |
| **Sensor Check** | Passed | Check | Passed | |
| **Frequency** | 8.2 | 15.8 | 7.5 | Hz |
| **Overswing Ratio** | 3.6 | 1.0 | 2.9 | |

**Peak Vector Sum** 0.685 in/s on October 18, 2013 at 10:04:33




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:07:42 October 18, 2013 |
| **Histogram Finish Time** | 10:30:51 October 18, 2013 |
| **Number of Intervals** | 277.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location | Kellogg street & Route 440 North |
| Client: | ENTACT |
| User Name: | Geocomp |
| General: | SA-6 |


| | |
|---|---|
| **Serial Number** | BE12194 V 10.30-8.17 MiniMate Plus |
| **Battery Level** | 6.1 Volts |
| **Unit Calibration** | October 5, 2012 by Instantel |
| **File Name** | N194F10P.GU0 |

**Post Event Notes**
Location 7

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.270 | 0.470 | 0.200 | in/s |
| **ZC Freq** | 30 | 28 | 30 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 10:25:02 | 10:29:42 | 10:25:07 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.510 in/s on October 18, 2013 at 10:25:02




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 10:32:20 October 18, 2013
**Histogram Finish Time** 11:36:10 October 18, 2013
**Number of Intervals** 765.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.1 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194F10Q.LW0

**Post Event Notes**
Location 8

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.125 | 0.415 | 0.0950 | in/s |
| **ZC Freq** | 30 | 30 | 34 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 10:35:00 | 10:35:00 | 10:35:00 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 3.9 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.435 in/s on October 18, 2013 at 10:35:00




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 11:39:48 October 18, 2013
**Histogram Finish Time** 11:47:01 October 18, 2013
**Number of Intervals** 86.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location Kellogg street & Route 440 North
Client: ENTACT
User Name: Geocomp
General: SA-6


**Serial Number** BE12194 V 10.30-8.17 MiniMate Plus
**Battery Level** 6.1 Volts
**Unit Calibration** October 5, 2012 by Instantel
**File Name** N194F10T.QC0

**Post Event Notes**
Location 1

**Extended Notes**
SA-6 Utility line Vibration monitoring.

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.305 | 1.21 | 1.25 | in/s |
| **ZC Freq** | 28 | 28 | 28 | Hz |
| **Date** | Oct 18 /13 | Oct 18 /13 | Oct 18 /13 | |
| **Time** | 11:42:38 | 11:42:38 | 11:41:08 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.7 | 7.2 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.7 | |

**Peak Vector Sum** 1.56 in/s on October 18, 2013 at 11:41:08




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

Geocomp
Technologies to manage risk for infrastructure

Boston
Atlanta
Chicago
Los Angeles
New York
www.geocomp.com

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**

**August 4th, 2014**
**For ENTACT, LLC**

111 John Street, Suite 650 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631


**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 8:10 AM and ended at 5:30 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 6 inch gas main, and an Instantel Minimate was used to record vibrations at 60 Kellogg Street in the part of the building closest to where work was being done. .

40 sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismographs. See attached Blastware reports for PPV at these locations.

6 Inch Gas Main:
Trigger Level: 1.0 in/sec
Alert Level: 2.0 in/sec

60 Kellogg Street:
Trigger Level: N/A
Alert Level: N/A





EXCAVATION AREA PARTIAL PLAN
AT KELLOGG STREET

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'

60 Kellogg Street





SECTION A
SCALE: 1/4"=1'-0" S-503 S-503

4' 2' 0 4' 8'

Legend

Center line of proposed Vibration Monitoring Locations (proposed by ENTACT)




KEY PLAN

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
P.W.D. LICENSE NUMBER 46522

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| A | 04/15/13 | G.S. | B.B. | G.P. | | PWD | |

ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTION

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-503 |
| SHEET | 61 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-503.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM


# Event Report

| | |
|---|---|
| **Histogram Start Time** | 08:01:11 August 4, 2014 |
| **Histogram Finish Time** | 13:45:00 August 4, 2014 |
| **Number of Intervals** | 23.00 at 15 minutes |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | 60 Kellogg Street |
| Client: | Entact |
| User Name: | Geocomp Engineering |
| General: | Kellogg Street |

| | |
|---|---|
| **Serial Number** | BE16697 V 10.60-8.17 MiniMate Plus |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 28, 2014 by Instantel |
| **File Name** | R697FFXK.XZ0 |

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0300 | 0.0150 | in/s |
| **ZC Freq** | >100 | 9.5 | 32 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 08:16:11 | 13:01:11 | 13:01:11 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0304 in/s on August 4, 2014 at 13:01:11




**Time Scale:** 15 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation


# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:50:15 August 4, 2014 |
| **Histogram Finish Time** | 17:49:04 August 4, 2014 |
| **Number of Intervals** | 15.00 at 15 minutes |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | 60 Kellogg Street |
| Client: | Entact |
| User Name: | Geocomp Engineering |
| General: | Kellogg Street |

| | |
|---|---|
| **Serial Number** | BE16697 V 10.60-8.17 MiniMate Plus |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | January 28, 2014 by Instantel |
| **File Name** | R697FFY1.3R0 |

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0150 | 0.0250 | 0.0150 | in/s |
| **ZC Freq** | >100 | 6.6 | >100 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 14:20:15 | 14:20:15 | 14:20:15 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.5 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0260 in/s on August 4, 2014 at 14:20:15




**Time Scale:** 15 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

**Histogram Start Time** 08:11:00 August 4, 2014
**Histogram Finish Time** 08:39:52 August 4, 2014
**Number of Intervals** 346.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 South 6" gas line
Client: Entact
User Name: Geocomp
General: Kellogg Street


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.7 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371FFXL.EC0

**Post Event Notes**
VMP 1

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.175 | 0.555 | 0.330 | in/s |
| **ZC Freq** | 19 | 10 | 16 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 08:14:10 | 08:14:10 | 08:14:10 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.9 | 3.8 | |

**Peak Vector Sum** 0.576 in/s on August 4, 2014 at 08:14:10




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 08:42:30 August 4, 2014 |
| **Histogram Finish Time** | 09:48:39 August 4, 2014 |
| **Number of Intervals** | 793.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |

| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFXM.UU0 |


**Post Event Notes**

VMP 2

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.310 | 0.395 | 0.765 | in/s |
| **ZC Freq** | 43 | 26 | 30 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 09:20:10 | 09:20:05 | 09:20:10 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.7 | 3.8 | |

**Peak Vector Sum** 0.828 in/s on August 4, 2014 at 09:20:10




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check



**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 09:51:09 August 4, 2014 |
| **Histogram Finish Time** | 10:39:07 August 4, 2014 |
| **Number of Intervals** | 575.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFXQ.190 |

**Post Event Notes**
VMP 3

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.145 | 0.315 | 0.310 | in/s |
| **ZC Freq** | 34 | 28 | 32 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 10:36:34 | 10:36:24 | 10:16:59 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.8 | 3.8 | |

**Peak Vector Sum** 0.330 in/s on August 4, 2014 at 10:17:04




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:41:48 August 4, 2014 |
| **Histogram Finish Time** | 11:38:04 August 4, 2014 |
| **Number of Intervals** | 675.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFXS.DO0 |

**Post Event Notes**
VMP 4

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.330 | 0.880 | 0.565 | in/s |
| **ZC Freq** | 39 | 30 | 34 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 11:16:33 | 11:16:33 | 11:16:33 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.7 | 3.8 | |

**Peak Vector Sum** 0.966 in/s on August 4, 2014 at 11:16:33




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 11:40:07 August 4, 2014 |
| **Histogram Finish Time** | 11:53:46 August 4, 2014 |
| **Number of Intervals** | 163.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFXV.2V0 |

**Post Event Notes**
VMP 5

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.225 | 0.155 | 0.115 | in/s |
| **ZC Freq** | 30 | 37 | 30 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 11:48:47 | 11:48:47 | 11:48:52 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.4 | Hz |
| **Overswing Ratio** | 3.9 | 3.8 | 3.7 | |

**Peak Vector Sum** 0.249 in/s on August 4, 2014 at 11:48:47




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 12:41:48 August 4, 2014 |
| **Histogram Finish Time** | 13:56:33 August 4, 2014 |
| **Number of Intervals** | 897.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |

| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFXX.XO0 |


**Post Event Notes**

VMP 5

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.470 | 0.740 | 0.435 | in/s |
| **ZC Freq** | 34 | 30 | 32 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 12:45:28 | 13:17:43 | 13:17:48 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.8 | 3.7 | |

**Peak Vector Sum** 0.852 in/s on August 4, 2014 at 13:17:43




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check



Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 13:58:19 August 4, 2014
**Histogram Finish Time** 15:28:47 August 4, 2014
**Number of Intervals** 1085.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 South 6" gas line
Client: Entact
User Name: Geocomp
General: Kellogg Street


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.6 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371FFY1.H70

**Post Event Notes**
VMP 6

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.105 | 0.200 | 0.160 | in/s |
| **ZC Freq** | 32 | 32 | 30 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 14:20:29 | 14:20:29 | 14:04:39 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.4 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.8 | 3.8 | |

**Peak Vector Sum** 0.224 in/s on August 4, 2014 at 14:20:29




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 15:31:00 August 4, 2014 |
| **Histogram Finish Time** | 16:39:24 August 4, 2014 |
| **Number of Intervals** | 820.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFY5.RO0 |

**Post Event Notes**
VMP 7

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.160 | 0.145 | 0.135 | in/s |
| **ZC Freq** | 30 | 32 | 27 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 16:33:50 | 16:01:05 | 16:01:05 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.7 | 3.8 | |

**Peak Vector Sum** 0.174 in/s on August 4, 2014 at 16:33:50




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 16:41:30 August 4, 2014 |
| **Histogram Finish Time** | 17:32:56 August 4, 2014 |
| **Number of Intervals** | 617.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |

**Notes**

| | |
|---|---|
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |

| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFY9.160 |


**Post Event Notes**

VMP 8

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0900 | 0.210 | 0.200 | in/s |
| **ZC Freq** | 34 | 30 | 30 | Hz |
| **Date** | Aug 4 /14 | Aug 4 /14 | Aug 4 /14 | |
| **Time** | 16:53:10 | 16:48:55 | 16:56:20 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.4 | Hz |
| **Overswing Ratio** | 3.9 | 3.8 | 3.7 | |

**Peak Vector Sum** 0.244 in/s on August 4, 2014 at 16:48:55




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check



**Format © 1995-2013 Xmark Corporation**

Geocomp
Technologies to manage risk for infrastructure

Boston
Atlanta
Chicago
Los Angeles
New York
www.geocomp.com

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**

**August 5th, 2014**
**For ENTACT, LLC**

111 John Street, Suite 650 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631


**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 11:20 AM and ended at 2:00 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 6 inch gas main, and an Instantel Minimate was used to record vibrations at 60 Kellogg Street in the part of the building closest to where work was being done. .

4 sheets were driven, then all 44 sheets were brought to grade, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at these locations.

6 Inch Gas Main:
Trigger Level: 1.0 in/sec
Alert Level: 2.0 in/sec

60 Kellogg Street:
Trigger Level: N/A
Alert Level: N/A





EXCAVATION AREA PARTIAL PLAN
AT KELLOGG STREET

SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'

60 Kellogg Street





SECTION A
SCALE: 1/4"=1'-0" S-503 S-503

4' 2' 0 4' 8'

Legend

Center line of proposed Vibration Monitoring Locations (proposed by ENTACT)




KEY PLAN

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
P.W.D. LICENSE NUMBER 46522

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| A | 04/15/13 | G.S. | B.B. | G.P. | | PWD | |

ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTION

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-10-0027 |
| DWG | S-503 |
| SHEET | 61 OF 66 |

FILE NAME: G:\DWGS\111\11173\S-503.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM


# Event Report

**Histogram Start Time** 07:03:57 August 5, 2014
**Histogram Finish Time** 07:45:00 August 5, 2014
**Number of Intervals** 3.00 at 15 minutes
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: 60 Kellogg Street
Client: Entact
User Name: Geocomp Engineering
General: Kellogg Street

**Serial Number** BE16697 V 10.60-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** January 28, 2014 by Instantel
**File Name** R697FFZC.YL0

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0150 | 0.0200 | 0.01000 | in/s |
| **ZC Freq** | 18 | 9.0 | >100 | Hz |
| **Date** | Aug 5 /14 | Aug 5 /14 | Aug 5 /14 | |
| **Time** | 07:18:57 | 07:18:57 | 07:18:57 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.5 | 7.1 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0206 in/s on August 5, 2014 at 07:18:57




**Time Scale:** 15 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation


# Event Report

**Histogram Start Time** 07:50:15 August 5, 2014
**Histogram Finish Time** 13:45:00 August 5, 2014
**Number of Intervals** 24.00 at 15 minutes
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: 60 Kellogg Street
Client: Entact
User Name: Geocomp Engineering
General: Kellogg Street

**Serial Number** BE16697 V 10.60-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** January 28, 2014 by Instantel
**File Name** R697FFZF.3R0

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.01000 | 0.0250 | 0.0150 | in/s |
| **ZC Freq** | >100 | 6.9 | 16 | Hz |
| **Date** | Aug 5 /14 | Aug 5 /14 | Aug 5 /14 | |
| **Time** | 08:05:15 | 08:20:15 | 09:05:15 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.5 | 7.2 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0255 in/s on August 5, 2014 at 08:20:15




**Time Scale:** 15 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 10:35:54 August 5, 2014 |
| **Histogram Finish Time** | 11:55:37 August 5, 2014 |
| **Number of Intervals** | 956.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFZM.RU0 |

**Post Event Notes**
VMP 8
Please note that the PPV's listed on this report were not the result of any sheet driving, but the bag holding the geophone was disturbed.

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 1.25 | 1.78 | 0.580 | in/s |
| **ZC Freq** | N/A | N/A | N/A | Hz |
| **Date** | Aug 5 /14 | Aug 5 /14 | Aug 5 /14 | |
| **Time** | 11:55:34 | 11:55:34 | 11:55:34 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.6 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 3.9 | 3.8 | 3.7 | |

**Peak Vector Sum** 1.80 in/s on August 5, 2014 at 11:55:34
**N/A: Not Applicable**




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.200 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 12:55:03 August 5, 2014 |
| **Histogram Finish Time** | 13:30:32 August 5, 2014 |
| **Number of Intervals** | 425.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFZT.7R0 |

**Post Event Notes**
VMP 6

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.110 | 0.205 | 0.145 | in/s |
| **ZC Freq** | 30 | 28 | 26 | Hz |
| **Date** | Aug 5 /14 | Aug 5 /14 | Aug 5 /14 | |
| **Time** | 13:09:03 | 13:10:38 | 13:13:18 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 3.8 | 3.8 | 3.8 | |

**Peak Vector Sum** 0.227 in/s on August 5, 2014 at 13:14:08




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:32:58 August 5, 2014 |
| **Histogram Finish Time** | 13:51:18 August 5, 2014 |
| **Number of Intervals** | 219.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFZU.YY0 |

**Post Event Notes**
VMP 4

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.150 | 0.225 | 0.395 | in/s |
| **ZC Freq** | 30 | 27 | 30 | Hz |
| **Date** | Aug 5 /14 | Aug 5 /14 | Aug 5 /14 | |
| **Time** | 13:44:48 | 13:47:18 | 13:45:28 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 3.8 | 3.7 | 3.7 | |

**Peak Vector Sum** 0.417 in/s on August 5, 2014 at 13:45:28




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


**Format © 1995-2013 Xmark Corporation**

# Event Report

| | |
|---|---|
| **Histogram Start Time** | 13:52:53 August 5, 2014 |
| **Histogram Finish Time** | 14:07:44 August 5, 2014 |
| **Number of Intervals** | 178.00 at 5 seconds |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | SA 6 South 6" gas line |
| Client: | Entact |
| User Name: | Geocomp |
| General: | Kellogg Street |


| | |
|---|---|
| **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Battery Level** | 6.6 Volts |
| **Unit Calibration** | January 29, 2014 by Instantel |
| **File Name** | Q371FFZV.W50 |

**Post Event Notes**
VMP 2

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.155 | 0.465 | 0.340 | in/s |
| **ZC Freq** | 39 | 28 | 28 | Hz |
| **Date** | Aug 5 /14 | Aug 5 /14 | Aug 5 /14 | |
| **Time** | 13:58:08 | 13:56:53 | 13:55:28 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 3.8 | 3.7 | 3.7 | |

**Peak Vector Sum** 0.495 in/s on August 5, 2014 at 13:55:58




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.100 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

Geocomp

*Technologies to manage risk for infrastructure*

Boston
Atlanta
Chicago
Los Angeles
New York
www.geocomp.com

# Vibration Monitoring Report

## Study Area 6 South

**Prepared by**
**Geocomp Engineering**

**August 22nd, 2014**
**For ENTACT, LLC**

111 John Street, Suite 650 | New York, NY 10038 | Tel 212 566 6630 | Fax 212 566 6631


**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 7:40 AM and ended at 9:50 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 6 inch gas main, and an Instantel Minimate was used to record vibrations at 60 Kellogg Street in the part of the building closest to where work was being done.

8 sheets were driven, then all 8 sheets were brought to grade, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at these locations.


6 Inch Gas Main:
Trigger Level: 1.0 in/sec
Alert Level: 2.0 in/sec

60 Kellogg Street:
Trigger Level: N/A
Alert Level: N/A





EXCAVATION AREA PARTIAL PLAN
AT KELLOGG STREET
SCALE: 1"=30'-0"

30' 20' 10' 0 30' 60'




SECTION A
SCALE: 1/4"=1'-0"
S-503 S-503

4' 2' 0 4' 8'




KEY PLAN

Legend

Center line of proposed Vibration Monitoring Locations (proposed by ENTACT)

PETER W. DEMING
NJ PROFESSIONAL ENGINEER
P.W.D. LICENSE NUMBER 46522

| NO. | DATE | DR | CHK | APVD |
|---|---|---|---|---|
| DSGN | | G.S. | B.B. | G.P. |
| A | 04/15/13 | ISSUED FOR CONSTRUCTION SPECIAL MASTER REVIEW | PWD | APVD |
| | | REVISION | BY | P.W.D. |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
TEMPORARY
SUPPORT OF EXCAVATION
PARTIAL PLAN AND SECTION

FILE NUMBER 11173

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34TH STREET, NEW YORK, NY 10122

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-10-0027
DWG S-503
SHEET 61 OF 66

FILE NAME: G:\DWGS\111\11173\S-503.dwg PLOT DATE: Thu, 11 Apr 2013 PLOT TIME: 9:19 AM


# Event Report

| | |
|---|---|
| **Histogram Start Time** | 07:08:46 August 22, 2014 |
| **Histogram Finish Time** | 07:45:00 August 22, 2014 |
| **Number of Intervals** | 3.00 at 15 minutes |
| **Range** | Geo:10.00 in/s |
| **Sample Rate** | 1024sps |
| **Job Number:** | 1 |
| **Notes** | |
| Location: | 60 Kellogg Street |
| Client: | Entact |
| User Name: | Geocomp Engineering |
| General: | Kellogg Street |

| | |
|---|---|
| **Serial Number** | BE16697 V 10.60-8.17 MiniMate Plus |
| **Battery Level** | 6.7 Volts |
| **Unit Calibration** | January 28, 2014 by Instantel |
| **File Name** | R697FGUU.IM0 |

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0150 | 0.0200 | 0.0150 | in/s |
| **ZC Freq** | 19 | 8.5 | 7.1 | Hz |
| **Date** | Aug 22 /14 | Aug 22 /14 | Aug 22 /14 | |
| **Time** | 07:45:00 | 07:23:46 | 07:38:46 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.8 | |

**Peak Vector Sum** 0.0212 in/s on August 22, 2014 at 07:23:46




**Time Scale:** 15 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation


# Event Report

**Histogram Start Time** 07:50:15 August 22, 2014
**Histogram Finish Time** 10:06:13 August 22, 2014
**Number of Intervals** 9.00 at 15 minutes
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: 60 Kellogg Street
Client: Entact
User Name: Geocomp Engineering
General: Kellogg Street

**Serial Number** BE16697 V 10.60-8.17 MiniMate Plus
**Battery Level** 6.7 Volts
**Unit Calibration** January 28, 2014 by Instantel
**File Name** R697FGUW.FR0

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0150 | 0.0400 | 0.0150 | in/s |
| **ZC Freq** | 17 | 6.2 | >100 | Hz |
| **Date** | Aug 22 /14 | Aug 22 /14 | Aug 22 /14 | |
| **Time** | 09:20:15 | 10:05:15 | 08:35:15 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.3 | 7.6 | 7.2 | Hz |
| **Overswing Ratio** | 4.0 | 3.5 | 3.9 | |

**Peak Vector Sum** 0.0412 in/s on August 22, 2014 at 10:05:15




**Time Scale:** 15 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 07:17:38 August 22, 2014
**Histogram Finish Time** 09:57:15 August 22, 2014
**Number of Intervals** 1915.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 South 6" gas line
Client: Entact
User Name: Geocomp
General: Kellogg Street


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.7 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371FGUU.XE0

**Post Event Notes**
VMP 9

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0900 | 0.230 | 0.0900 | in/s |
| **ZC Freq** | 34 | 30 | 21 | Hz |
| **Date** | Aug 22 /14 | Aug 22 /14 | Aug 22 /14 | |
| **Time** | 08:32:38 | 08:44:38 | 09:13:33 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.4 | Hz |
| **Overswing Ratio** | 4.0 | 4.0 | 3.9 | |

**Peak Vector Sum** 0.236 in/s on August 22, 2014 at 08:44:38




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

**APPENDIX P**

**SURCHARGE REPORT**
**(CD ONLY)**

# STUDY AREA 6 NORTH
# &
# STUDY AREA 6 SOUTH

## SURCHARGE MONITORING PLAN
## MONTHLY REPORT NO. 16
## MARCH 2016 REPORTING PERIOD

JERSEY CITY, NEW JERSEY

*Prepared for*

Honeywell

115 Tabor Road
Morris Plains, New Jersey 07950

*Prepared by*

Amec Foster Wheeler Environment & Infrastructure, Inc.
200 American Metro Boulevard, Suite 113
Hamilton, New Jersey 08619

**APRIL 2016**

# INTRODUCTION

The surcharge monthly reports are generated to indicate the status of progress and/or indicate corrective actions needed as provided for in Appendix N (Surcharge Monitoring Plan, Section 5.0 Reporting). Report No. 13 July 2015 indicated completion of Area 1N, Area 2N, Area 1S, Area 2S and Area 3S.

Surcharge Instrumentation was installed in Area 3N and Area 4N subsequent to March 2015 in preparation for surcharge placement in those areas. Surcharge placement in Area 3N was complete on January 18, 2016. Surcharge placement in Area 4N was complete on January 29, 2016. This report is the third report for Area 3N and Area 4N. MRCE's March 29, 2016 letter confirms completion of Area 3N and Area 4N. This marks the formal end of the Surcharge Monitoring Program for the SA-6S and SA-6N project.

Report No. 16 will be the final report for the Surcharge Program.

The goal of the program was to "remove 100% of the Primary Consolidation that will result from the future development grading prior to cap installation". The reports have documented the successful attainment of that goal for each of the 7 designated areas. In general the magnitude of settlement and time for consolidation were consistent with the predicted settlements.

This report has been prepared consistent with the format and content of the prior reports with two notable exceptions.

1. Over the course of the program Installation Logs and instrument data plots were incorporated in one monthly report then incorporated by reference in subsequent reports. In this report a summary table is provided at the end of the Table of Contents that provides a matrix showing the report location for both monitoring data and installation logs by Area and Report Number.
2. All the MRCE approval letters have been included in the final report.

# REPORT CONTENTS

| SURCHARGE AREA | INCLUDED HEREIN | REPORT SECTION NO. |
|---|---|---|
| **AREA 1N** | **YES**** | **1.0** |
| **AREA 2N** | **YES**** | **2.0** |
| **AREA 3N** | **YES**** | **3.0** |
| **AREA 4N** | **YES**** | **4.0** |
| **AREA 1S** | **YES**** | **5.0** |
| **AREA 2S** | **YES**** | **6.0** |
| **AREA 3S** | **YES**** | **7.0** |

* Surcharge placement has not commenced.

** Surcharge is complete.

*** Surcharge Instrumentation Installed.

# TABLE OF CONTENTS

INTRODUCTION ..... I
REPORT CONTENTS ..... II
1.0 AREA 1N SUMMARY ..... 1
1.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 1
1.2 Surcharge Progress ..... 1
2.0 AREA 2N SUMMARY ..... 3
2.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 3
2.2 Surcharge Progress ..... 3
3.0 AREA 3N SUMMARY ..... 5
3.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 5
3.2 Surcharge Progress ..... 5
4.0 AREA 4N SUMMARY ..... 7
4.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 7
4.2 Surcharge Progress ..... 7
5.0 AREA 1S SUMMARY ..... 9
5.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 9
5.2 Surcharge Progress ..... 9
5.3 Proposed Modifications ..... 9
6.0 AREA 2S SUMMARY ..... 12
6.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 12
6.2 Surcharge Progress ..... 12
6.3 Proposed Modifications ..... 12
7.0 AREA 3S SUMMARY ..... 14
7.1 Surcharge Monitoring Data Trends/Anomalies/ Modifications ..... 14
7.2 Surcharge Progress ..... 14
7.3 Proposed Modifications ..... 14

**Boring Logs, Instrument Installation Diagrams and Monitoring Data Report Location Matrix**

| Attachment | Surcharge Area | Submitted | |
|---|---|---|---|
| | | Reporting Period | Report Number |
| Boring Logs & Instrument Installation Diagrams | 1N | June 2014 | 03 |
| | 2N | July 2014 | 04 |
| | 3N | June 2015 | 13 |
| | 4N | June 2015 | 13 |
| | 1S | June 2014 | 03 |
| | 2S | July 2014 | 04 |
| | 3S | February 2014 | 01 |
| Monitoring Data | 1N | July 2014 | 04 |
| | 2N | October 2014 | 07 |
| | 3N | March 2016 | 16 |
| | 4N | March 2016 | 16 |
| | 1S | October 2014 | 07 |
| | 2S | January 2015 | 10 |
| | 3S | March 2015 | 12 |

**SURCHARGE AREA 1N: FIGURES/ ATTACHMENTS**

Figure 1N-1: Instrumentation Location Plan.

Attachment 1N-1: Baseline Surcharge Analysis for Monitoring Points.

Attachment 1N-2: August 8, 2014 Mueser Rutledge Correspondence re: SA-6 North Surcharge Monitoring, Jersey City, NJ (Previously Submitted Report No. 4).

**SURCHARGE AREA 2N: FIGURES/ ATTACHMENTS**

Figure 2N-1: Instrumentation Location Plan.

Attachment 2N-1: Baseline Surcharge Analysis for Monitoring Points.

Attachment 2N-2: November 21, 2014 Mueser Rutledge Correspondence re: SA-6 North Surcharge Monitoring, Jersey City, NJ (Previously Submitted Report No. 8).

**SURCHARGE AREA 3N: FIGURES/ ATTACHMENTS**

Figure 3N-1: Instrumentation Location Plan.

Attachment 3N-1: Baseline Surcharge Analysis for Monitoring Points.

Attachment 3N-2: Surcharge Monitoring Data.

N_FS-08
N_FS-09
N_FS-10
N_FS-11
N_HS-10
N_HS-11
N_HS-12
N_RP-06
N_RP-07
N_SP-15
N_SP-21
N_SP-14
N_HS-13

Attachment 3N-3: March 29, 2016 Mueser Rutledge Correspondence re: Updated Area 3N and 4N Surcharge Review, SA-6 North, Jersey City, NJ.

**SURCHARGE AREA 4N: FIGURES/ ATTACHMENTS**

Figure 4N-1: Instrumentation Location Plan.

Attachment 4N-1: Baseline Surcharge Analysis for Monitoring Points.

Attachment 4N-2: Surcharge Monitoring Data.
N_FS-12
N_FS-13
N_SP-22
N_SP-23
N_SP-24
N_SP-25

Attachment 4N-3: March 29, 2016 Mueser Rutledge Correspondence re: Updated Area 3N and 4N Surcharge Review, SA-6 North, Jersey City, NJ.

**SURCHARGE AREA 1S: FIGURES/ ATTACHMENTS**

Figure 1S-1: Instrumentation Location Plan.

Attachment 1S-1: Baseline Surcharge Analysis for Monitoring Points

Attachment 1S-2: October 27, 2014 Mueser Rutledge Correspondence re: SA-6 South Surcharge Monitoring, Jersey City, NJ (Previously Submitted Report No. 7) .

**SURCHARGE AREA 2S: FIGURES/ ATTACHMENTS**

Figure 2S-1: Instrumentation Location Plan.

Attachment 2S-1: Baseline Surcharge Analysis for Monitoring Points.

Attachment 2S-2 February 6, 2015 Mueser Rutledge Correspondence re: SA-6 South Surcharge Monitoring, Jersey City, NJ. (Previously submitted Report No. 10).

**SURCHARGE AREA 3S: FIGURES/ ATTACHMENTS**

Figure 3S-1: Instrumentation Location Plan.

Attachment 3S-1: Baseline Surcharge Analysis for Monitoring Points.

Attachment 3S-2 April 24, 2015 Mueser Rutledge Correspondence re: SA-6 South Surcharge Monitoring, Jersey City, NJ.

# 1.0 AREA 1N SUMMARY

Surcharging was initiated in Area 1N on April 8, 2014. Final surcharge placement was completed on July 31, 2014.

## 1.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

**Table 1N-1** below summarizes the status of the surcharge. Surcharging is complete at all 11 monitoring stations.

## 1.2 SURCHARGE PROGRESS

As noted in Section 1.1 and as summarized in **Table 1N-1** the surcharge objective has been met in the Stratum D at all 11 monitoring locations. Surcharge removal was initiated adjacent to the 72 in. force main on August 29, 2014 and continued through October.

Tasks requiring acoustical monitoring (Barrier Wall installation and Surcharge placement and removal) were completed by the end of October. Acoustical monitoring has been discontinued by PVSC.

**TABLE 1N-1**
**SURCHARGE COMPLETION EVALUATION**
**SUMMARY OF EFFECTIVE STRESS**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **N_FS-01** | 2308 | 2605 | **113%** | Data as of August 2014 |
| **N_FS-02** | 2414 | 3186 | **132%** | Data as of August 2014 |
| **N_FS-03** | 2529 | 2810 | **111%** | Data as of August 2014 |
| **N_FS-04** | 2764 | 3076 | **111%** | Data as of August 2014 |
| **N_HS-01** | 2287 | 2772 | **121%** | Data as of August 2014 |
| **N_HS-02** | 2324 | 2824 | **122%** | Data as of August 2014 |
| **N_HS-03** | 2427 | 3161 | **130%** | Data as of August 2014 |
| **N_HS-04** | 2303 | 2522 | **109%** | Data as of August 2014 |
| **N_HS-05** | 2562 | 3911 | **153%** | Data as of August 2014 |
| **N_HS-07** | 2668 | 3577 | **134%** | Data as of August 2014 |
| **N_HS-09** | 2748 | 3521 | **128%** | Data as of August 2014 |

# 2.0 AREA 2N SUMMARY

Geotechnical instrumentation has been installed in Surcharge Area 2N consistent with the Surcharge Monitoring Plan (Amec, 2013) and Design Change Bulletin dated April 30, 2014. The installed instrument locations are depicted on **Figure 2N-1** (attached). Geotechnical Boring Records and Instrument Construction Diagrams for Area 2N were previously provided in Report No. 4.

The Baseline Surcharge Settlement Analysis for 2N is shown in **Attachment 2N-1.**

Surcharge placement continued in Area 2N throughout October. The surcharge Placement was completed on November 3, 2014.

## 2.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

Monitoring is no longer being performed.

## 2.2 SURCHARGE PROGRESS

As of October 28, 2014 Amec Foster Wheeler Environment and Infrastructure's (Amec Foster Wheeler's) evaluation concluded that the surcharge objective has been met at all three locations. **Table 2N-1** below summarizes the status of the surcharge.

**TABLE 2N-1**
**SURCHARGE COMPLETION EVALUATION**
**SUMMARY OF EFFECTIVE STRESS**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **N_FS-05** | 2766 | 2970 | **107%** | Data as of November 2014; Pore pressure elevated 9.2 ft. (Stratum D). |
| **N_FS-06** | 2833 | 3497 | **123%** | Data as of November 2014 |
| **N_FS-07** | 2588 | 3389 | **131%** | Data as of November 2014 |

# 3.0 AREA 3N SUMMARY

Geotechnical instrumentation has been installed in Surcharge Area 3N consistent with the Surcharge Monitoring Plan (Amec, 2013) and Design Change Bulletin dated April 30, 2014. The installed instrument locations are depicted on **Figure 3N-1** (attached). Geotechnical Boring Records and Instrument Construction Diagrams for Area 3N were previously provided in Report No. 13.

The Baseline Surcharge Settlement Analysis for 3N is shown in **Attachment 3N-1.**

Surcharge placement commenced in November 2015 in Area 3N and was completed on January 18, 2016.

## 3.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

Copies of the data plots are provided in **Attachment 3N-2.** Final Surcharge Grades in Area 3N were 1-2 ft. above the Design Surcharge Grades. All instruments performed as expected. Pumping of the contingent groundwater collection system has allowed for the desired pore pressure dissipation to take place at all monitoring locations.

## 3.2 SURCHARGE PROGRESS

All eight monitoring stations have met the 100% primary consolidation goal and the areas where fill was last placed have also met the required surcharge completion criteria. The surcharge completion summary for Area 3N is included in **Table 3N-1**.

**TABLE 3N-1**
**SURCHARGE COMPLETION EVALUATION**
**SUMMARY OF EFFECTIVE STRESS**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **N_FS-08** | 2401 | 2832 | **118%** | SP and VWP data through 3/9/16. |
| **N_FS-09** | 2218 | 2909 | **131%** | SP and VWP data through 3/9/16. |
| **N_FS-10** | 2619 | 2964 | **113%** | SP data through 3/9/16. VWP data through 3/15/16. |
| **N_FS-11** | 1920 | 2273 | **118%** | SP and VWP data through 3/9/16. |
| **N_HS-10** | 2216 | 2313 | **104%** | SP and VWP data through 3/9/16. |
| **N_HS-11** | 2280 | 2335 | **102%** | SP data through 3/9/16. VWP data through 3/24/16. |
| **N_HS-12** | 1932 | 2198 | **114%** | SP and VWP data through 3/9/16. |
| **N_HS-13** | 2050 | 2214 | **108%** | SP and VWP data through 3/9/16. |

# 4.0 AREA 4N SUMMARY

Geotechnical instrumentation has been installed in Surcharge Area 4N consistent with the Surcharge Monitoring Plan (Amec, 2013) and Design Change Bulletin dated April 30, 2014. The installed instrument locations are depicted on **Figure 4N-1** (attached). Geotechnical Boring Records and Instrument Construction Diagrams for Area 4N were previously provided in Report No. 13.

The Baseline Surcharge Settlement Analysis for 4N is shown in **Attachment 4N-1.**

Surcharge placement was completed in Area 4N on January 29, 2016.

## 4.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

Data plots for Area 4N are included in **Attachment 4N-2.** All instrumentation performed as intended.

## 4.2 SURCHARGE PROGRESS

There are only two Full Stations in Area 4N. Both locations now have met the surcharge goal and are therefore considered complete. The areas that were loaded last have also been loaded for an adequate duration. The surcharge completion summary for Area 4N is included in **Table 4N-1**.

**TABLE 4N-1**
**SURCHARGE COMPLETION EVALUATION**
**SUMMARY OF EFFECTIVE STRESS**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **N_FS-12** | 1869 | 1897 | **101%** | SP data through 3/9/16. VWP data through 3/24/16. |
| **N_FS-13** | 2064 | 2433 | **118%** | SP and VWP data through 3/9/16. |

# 5.0 AREA 1S SUMMARY

Geotechnical instrumentation has been installed in Surcharge Area 1S consistent with the Surcharge Monitoring Plan (Amec, 2013) and Design Change Bulletin dated April 30, 2014. The installed instrument locations are depicted on **Figure 1S-1** (attached). Geotechnical Boring Records and Instrument Construction Diagrams for Area 1S were included in Attachment 1S-3 Report No. 3.

The Baseline Surcharge Settlement Analysis for 1S is shown in **Attachment 1S-1.**

Surcharging was initiated in Area 1S on June 16, 2014 and continued through the week of September 26, 2014. Surcharging was noted as complete in Report No. 6, September 2014.

## 5.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

Monitoring is no longer being performed.

## 5.2 SURCHARGE PROGRESS

The Surcharge was considered complete (see **Table 1S-1**) at all locations as indicated in Report No. 6.

## 5.3 PROPOSED MODIFICATIONS

The grading of the surcharge pile has been modified at the Hackensack River to reduce load on the bulkhead and minimize the amount of rework in the deferred area. This information was issued in a Design Change Bulletin. The change moves the crest of the surcharge back approximately 16 ft. to the east.

**TABLE 1S-1**
**SURCHARGE COMPLETION EVALUATION**
**SUMMARY OF EFFECTIVE STRESS**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D | |
| | | | Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-01** | 2616 | 3236 | **124%** | Data as of November 2014. Pore pressure elevated 5 ft. in Stratum D and 3 ft. in Stratum RC. |
| **S_FS-02** | 2627 | 3201 | **122%** | Data as of November 2014. Pore pressure elevated 4.5 ft. in Stratum D. |
| **S_HS-01** | 3064 | 3292 | **107%** | Data as of November 2014. |
| **S_HS-02** | 2571 | 2962 | **115%** | Data as of November 2014. Pore pressure elevated 3 ft. in Stratum D. |
| **S_HS-03** | 2400 | 2541 | **106%** | Data as of November 2014. Pore pressure elevated 11 ft. in Stratum D and 5.5 ft. in Stratum RC. |
| **S_HS-04** | 2548 | 3053 | **120%** | Data as of November 2014. Pore pressure elevated 5 ft. in Stratum D. |
| **S_HS-05** | 2583 | 2919 | **113%** | Data as of November 2014. |
| **S_HS-06** | 2881 | 3205 | **111%** | Data as of November 2014. Pore pressure elevated 1.5 ft. in Stratum D and 7 ft. in Stratum RC. |

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D | |
| | | | Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_HS-07** | 2494 | 3130 | **126%** | Data as of November 2014. |
| **S_HS-08** | 2595 | 2880 | **111%** | Data as of November 2014. Pore pressure elevated 5 ft. in Stratum D. |

# 6.0 AREA 2S SUMMARY

Geotechnical instrumentation has been installed in Surcharge Area 2S consistent with the Surcharge Monitoring Plan (Amec, 2013) and Design Change Bulletin dated April 30, 2014. The installed instrument locations are depicted on **Figure 2S-1** (attached). Geotechnical Boring Records and Instrument Construction Diagrams for Area 2S were previously provided in Attachment 2S-2 of Report No. 4.

The Baseline Surcharge Settlement Analysis for 2S is shown in **Attachment 2S-1.**

Surcharging was initiated in Area 2S in July 2014 as subgrade fill placement progressing from Area 1S into Area 2S. Placement of subgrade fill was completed during the December reporting period. The placement of "Celgene and Novartis" imported fill was completed in the January reporting period.

Surcharging for Area 2S was noted as complete in Report No. 10.

## 6.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

Surcharge monitoring is no longer being conducted in Area 2S.

## 6.2 SURCHARGE PROGRESS

As of January 26, 2015 the reduced data at all 10 monitoring stations indicated that the completion criteria has been met. **Table 2S-1** below summarizes the status of the surcharge at each monitoring stations at the end of the January monitoring period.

## 6.3 PROPOSED MODIFICATIONS

There have been no modifications to the Surcharge Plan in Area 2S.

**TABLE 2S-1**
**SURCHARGE COMPLETION EVALUATION**
**AMEC CORRECTED RESULTS JANUARY 2015**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-03** | 2343 | 2984 | **127%** | VWP data through 1/12/15; SP data through 1/30/15. |
| **S_FS-04** | 2359 | 2909 | **123%** | VWP data through 1/18/15; SP data through 1/30/15. |
| **S_FS-05** | 1839 | 1833 | **100%** | VWP data through 1/29/15; SP data through 1/30/15. |
| **S_HS-09** | 2232 | 3194 | **143%** | VWP data through 1/12/15; SP data through 1/30/15. |
| **S_HS-10** | 2479 | 2777 | **112%** | VWP data through 1/12/15; SP data through 1/30/15. |
| **S_HS-11** | 2342 | 2656 | **113%** | VWP data through 1/12/15; SP data through 1/30/15. |
| **S_HS-12** | 2482 | 2877 | **116%** | VWP data through 1/12/15; SP data through 1/30/15. |
| **S_HS-13** | 2100 | 2412 | **115%** | VWP data as of 1/29/15; SP data through 1/30/15. |
| **S_HS-14** | 2138 | 2839 | **133%** | VWP data as of 1/12/15; SP data through 1/30/15. |
| **S_HS-15** | 2637 | 3234 | **123%** | VWP data as of 1/12/15; SP data through 1/30/15. |

# 7.0 AREA 3S SUMMARY

Geotechnical instrumentation has been installed in Surcharge Area 3S consistent with the Surcharge Monitoring Plan (Amec, 2013) and Design Change Bulletin dated April 30, 2014. The installed instrument locations are depicted on **Figure 3S-1** (attached). Geotechnical Boring Records and Instrument Construction Diagrams for Area 3S were previously provided in Attachment 3S-1 of Report No. 1.

The Baseline Surcharge Settlement Analysis for 3S is shown in **Attachment 3S-1.**

Surcharging was initiated in Area 3S in November 2014 as subgrade fill placement progressing from West to East. Completion of surcharge fill placement finished in the first week of March with the placement of a small volume of gravel surface at the east end of Area 3S.

## 7.1 SURCHARGE MONITORING DATA TRENDS/ANOMALIES/ MODIFICATIONS

Surcharge monitoring is no longer being conducted.

## 7.2 SURCHARGE PROGRESS

As of the close of the March, 2015 reporting period Amec Foster Wheeler's evaluation concludes that the surcharge objective has been met at all nine locations. **Table 3S-1,** below, summarizes the status of the surcharge.

MRCE have completed their peer review of the results. MRCE's letter dated April 24, 2015 (Attachment 3S-4 to Report No. 10) indicates that based on their analysis all stations met the surcharge program completion goal as of the end of the March 2015 reporting period.

## 7.3 PROPOSED MODIFICATIONS

The 0-12 ft. wide Deferred Area strip along Route 440 will not be surcharged. The surcharge design grades have been carried to the point of forming a stable slope at the Barrier Wall at elevation 11. A Design Change Bulletin has been filed documenting this Field Change. The development grades are similar to the existing grades along the "Deferred Area" (i.e. approximately + 0.5 ft.). The surcharge height

in this area was an artifact resulting from generating a simple surcharge pile geometry with a uniform slope. Therefore elimination of surcharge from this strip will have no impact on the Chromium Remedy.

The intent of SP-08 was to monitor settlement impacts on the perimeter pool. The original Settlement Platform SP-08 was located just south of the SA-7 barrier wall and not north of the wall over the perimeter pool. The platform was relocated mid-January 2015 to be over the perimeter pool. The platform was renamed SP-08 (2). Both plots are included in this report.


**TABLE 3S-1**
**SURCHARGE COMPLETION EVALUATION**


| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-06** | 2099 | 2664 | **127%** | Data through March 2015 |
| **S_FS-07** | 2376 | 2691 | **113%** | Data through March 2015 |
| **S_HS-16** | 2522 | 2619 | **104%** | Data through March 2015 |
| **S_HS-17** | 1751 | 2046 | **117%** | Data through March 2015 |
| **S_HS-18** | 970 | 1458 | **150%** | Data through March 2015 |
| **S_HS-19** | 845 | 1206 | **143%** | Data through March 2015 |
| **S_HS-20** | 2484 | 2499 | **101%** | Data through March 2015 |
| **S_HS-21** | 1504 | 1978 | **132%** | Data through March 2015 |
| **S_HS-22** | 966 | 1198 | **124%** | Data through March 2015 |

**SURCHARGE AREA 1N**
**FIGURES & ATTACHMENTS**

**Figure 1N-1**

**Instrumentation Location Plan**




SECTION A-A

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| VI-1 | 686110 | 602120 |
| VI-2 | 686042 | 602032 |
| VI-3 | 685922 | 602571 |
| VI-4 | 685860 | 602703 |
| FS1 | 685983 | 602116 |
| FS2 | 685854 | 602467 |
| FS3 | 685779 | 602684 |
| FS4 | 685727 | 602709 |
| HS1 | 685958 | 602431 |
| HS2 | 685922 | 602330 |
| HS3 | 685871 | 602301 |
| HS4 | 685928 | 602505 |
| HS5 | 685786 | 602416 |
| ~~HS6~~ | ~~685784.69~~ | ~~602649.85~~ |
| HS7 | 685700.10 | 602583.29 |
| ~~HS8~~ | ~~685826.15~~ | ~~602798.09~~ |
| HS9 | 685629 | 602684 |

| | | |
|---|---|---|
| SP1 | 685880 | 602205 |
| SP2 | 685757 | 602417 |
| SP3 | 685613 | 602663 |
| ~~SP4~~ | ~~685953.03~~ | ~~602533.39~~ |
| ~~SP5~~ | ~~685931.28~~ | ~~602578.16~~ |
| ~~SP6~~ | ~~685906.49~~ | ~~602633.51~~ |
| ~~SP7~~ | ~~685886.78~~ | ~~602676.31~~ |
| ~~SP8~~ | ~~685867.20~~ | ~~602721.11~~ |
| ~~SP9~~ | ~~685849.22~~ | ~~602763.68~~ |
| ~~SP10~~ | ~~685883.92~~ | ~~602781.17~~ |
| SUR MON 1 | 685952 | 602515 |
| SUR MON 2 | 685848 | 602762 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL - SETUP |
| HS-1 | SETTLEMENT MONITORING POINT HALF - SETUP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE |
| | 72-INCH FM ACOUSTICAL MONITORING POINT |
| SUR MON 1 | 72-INCH FM SURVEY MONITORING POINT |
| | STATION RELOCATED OR ELIMINATED DUE TO SURCHARGE PILE RECONFIGURATION |

0 15 30 60
SCALE IN FEET

Revised/Date: TDD 08/13/14
Checked/Date: SGS 08/13/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 NORTH<br>JERSEY CITY, NEW JERSEY<br>HONEYWELL SITE ID - 37472 | amec | INSTRUMENTATION LOCATION PLAN<br>AREA 1N<br>Project 3480-09-0006<br>Figure B1 |

Z:\Projects\HONEYWELL_MTR021 CITY\Dwg Design-Site-Civil\CAD\SAMR\100 Percent\Figure 1 Surcharge Settling Monitoring Plan - Area 1.dwg Thu, 14 Aug 2014 - 12:59pm mgm-fuller

**Attachment 1N-1**

**Baseline Surcharge Analysis for Monitoring Points**

# AREA 1N
## BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

### SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION

| SURCHARGE MONITORING POINT | REFERENCE/NEARBY GEOTECHNICAL EXPLORATIONS | EXISTING & PROPOSED GRADING (At Surcharge Monitoring Point) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE (100% Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | ESTIMATED SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | SF/O | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| **N_FS-01** | 087-SB-407 | 16.3 | 17.0 | 20.0 | 0.3 | 0.1 | 0.0 | 0.4 | 0.0 | 0.1 | 1.0 | **20.0** | **3.8** | **3.0** | **22%** | **0.3** | 0.2 | 2.4 | **2.6** |
| **N_FS-02** | 087-SB-411; 115-SB-214 | 14.8 | 19.5 | 26.5 | 1.5 | 1.1 | 0.0 | 2.6 | 0.0 | 0.6 | 5.8 | **26.5** | **11.8** | **7.0** | **48%** | **1.5** | 0.4 | 2.1 | **2.5** |
| **N_FS-03** | 087-SB-409; 087-CPT-006; 087-CPT-012 | 14.3 | 21.0 | 30.0 | 1.9 | 1.1 | 0.0 | 2.9 | 0.0 | 0.3 | 6.2 | **30.0** | **15.8** | **9.0** | **52%** | **1.0** | 0.3 | 1.6 | **1.9** |
| **N_FS-04** | 087-CPT-012 | 13.3 | 23.0 | 30.0 | 2.1 | 3.6 | 0.0 | 3.9 | 0.0 | 0.2 | 9.8 | **30.0** | **16.8** | **7.0** | **68%** | **2.4** | 0.7 | 1.5 | **2.2** |
| **N_HS-01** | 087-CPT-016; 087-SB-403 | 15.5 | 17.8 | 21.0 | 0.8 | 0.5 | 0.0 | 1.4 | 0.0 | 0.1 | 2.9 | **21.0** | **5.5** | **3.3** | **45%** | **1.7** | 0.4 | 2.5 | **2.9** |
| **N_HS-02** | 087-SB-408; 087-SB-411 | 14.3 | 18.0 | 22.5 | 1.3 | 0.8 | 0.0 | 2.2 | 0.0 | 0.5 | 4.8 | **22.5** | **8.3** | **4.5** | **51%** | **1.8** | 0.4 | 2.3 | **2.7** |
| **N_HS-03** | 087-SB-411; 115-SB-214 | 14.8 | 19.3 | 25.0 | 1.4 | 1.3 | 0.0 | 2.9 | 0.0 | 0.6 | 6.2 | **25.0** | **10.3** | **5.8** | **50%** | **2.4** | 0.5 | 2.5 | **3.1** |
| **N_HS-04** | 087-SB-411; 087-SB-403; 087-CPT-016 | 15.0 | 18.5 | 21.0 | 1.2 | 0.8 | 0.0 | 1.8 | 0.0 | 0.1 | 4.0 | **21.0** | **6.0** | **2.5** | **62%** | **2.3** | 0.4 | 2.0 | **2.4** |
| **N_HS-05** | 087-SB-411; 115-SB-214 | 13.3 | 20.0 | 32.0 | 2.0 | 1.8 | 0.0 | 4.6 | 0.0 | 0.2 | 8.6 | **32.0** | **18.8** | **12.0** | **46%** | **2.1** | 0.5 | 2.6 | **3.1** |
| **N_HS-07** | 087-SB-409; 115-SB-213; 087-CPT-012 | 12.5 | 22.0 | 30.0 | 2.3 | 2.3 | 0.0 | 4.3 | 0.0 | 0.3 | 9.1 | **30.0** | **17.5** | **8.0** | **65%** | **1.9** | 0.4 | 1.7 | **2.1** |
| **N_HS-09** | 115-SB-213; 087-CPT-012; 087-CPT-013 | 13.8 | 22.5 | 30.0 | 2.2 | 2.0 | 0.0 | 4.5 | 0.0 | 0.4 | 9.1 | **30.0** | **16.3** | **7.5** | **63%** | **2.5** | 0.4 | 2.1 | **2.5** |

Prepared By/Date: NDL/4-2-14
Checked By/Date: TCC/5-8-14

**Attachment 1N-2**
**August 8, 2014 Mueser Rutledge Correspondence re:**
**SA-6 North Surcharge Monitoring, Jersey City, NJ**
**(Previously Submitted Report No. 4)**

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

Alfred H. Brand
David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
*Partners*

David R. Good
Walter E. Kaeck
*Associate Partners*

James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Tony D. Canale
Jan Cermak
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
Sitotaw Y. Fantaye
*Senior Associates*

Michael J. Chow
Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

August 8, 2014

Geoff Shallard
AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Re: SA-6 North Surcharge Monitoring
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

Mueser Rutledge Consulting Engineers (MRCE) reviewed the settlement and piezometer monitoring data related to Area 1N provided by AMEC, on July 18th 2014. MRCE's review of the available data is summarized below:

1. AMEC indicated boring sampling performed was to define the compressible layer stratification and the Vibrating Wire Piezometers (VWP) were set at the center of the layers. Center of the layer provide the most conservative pore water pressure reading for the effective stress evaluation. MRCE effective stress calculations were made at the center of the layers.

2. MRCE obtained the 06/16/14 measured fill thickness from the "Settlement Platform – Data Report". MRCE calculated the total stress as of 06/16/14 based on the 06/16/14 fill thickness and the "Historic Pre-Construction Conditions" total stresses provided by AMEC. MRCE calculated the pore water pressures based from 06/16/14 piezometer readings on "Vibrating Wire Piezometer – Data Report" and calculated the 06/16/14 effective stresses, as presented in Table 1.

3. MRCE compared calculated 06/16/14 effective stresses with the effective stresses provided by AMEC for "Final Post-Development Conditions". The defined goal of surcharge program was to achieve an equal or greater effective stress than the "Final Post-Development Conditions" effective stress. Accordingly, MRCE evaluated 06/16/14 percentage completion, shown as "MRCE % Completion (06/16/14)" in Table 1. Table 1 also presents 06/30/14 percent completion evaluation of AMEC, "AMEC % Completion (06/30/14)", for comparison.

4. Two settlement monitoring locations, N_FS-04 and N_HS-04 (highlighted in Table 1), had percentage completion less than 100%. These monitoring points did not meet the defined goal of the surcharge program as of 06/16/14.

5. AMEC provided updated settlement and piezometer monitoring data on August 6th 2014. MRCE calculated effective stresses and the percent completion for N_FS-04 and N_HS-04 based on the updated monitoring data, as shown in Table 2.

6. MRCE agrees that the defined goal of the surcharge program of achieving an equal or greater effective stress than the "Final Post-Development Conditions" effective stress is met in all settlement monitoring locations.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

MP:F:\111\11173\SA-6 Surcharge Removal Review\MRCE SA-6 Surcharge Monitoring Review.docx

## Table 1. MRCE SA-6 Surcharge Monitoring Review (06/16/14)

| Source: | | AMEC | | | Settlement Monitoring Data | VWP Monitoring Data | MRCE | | | | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Settlement Monitoring Point | Layer | Center of the Layer EL. (ft) | Historic Pre-Construction Conditions Total Stress (psf) | Final Post-Development Conditions Effective Stress (psf) | Fill Thickness (ft) | Elevation Head (ft) | Total Stress 06/16/14 (psf) | Pore Water Pressure 06/16/14 (psf) | Effective Stress 06/16/14 (psf) | % Completion 06/16/14 | % Completion 06/30/14 |
| N_FS-01 | Center D | -10.8 | 3073 | 2308 | 2.6 | 6.1 | 3393 | 1058 | 2335 | 101% | 103% |
| N_FS-02 | Center O | -4.6 | 2262 | 2279 | 11.2 | 11.6 | 4048 | 1242 | 2418 | 106% | - |
| N_FS-02 | Center D | -8.3 | 2647 | 2414 | 11.2 | 15.4 | 3663 | 1245 | 2807 | 116% | 117% |
| N_FS-03 | Center O | -2.9 | 2118 | 2431 | 9.8 | 9.9 | 3628 | 1065 | 2443 | 100% | - |
| N_FS-03 | Center D | -7.2 | 2400 | 2529 | 9.8 | 11.5 | 3346 | 904 | 2563 | 101% | 105% |
| N_FS-04 | Center O | -2.2 | 1830 | 2598 | 10.9 | 12.9 | 3624 | 1206 | 2417 | **93%** | - |
| N_FS-04 | Center D | -6.5 | 2266 | 2764 | 10.9 | 10.1 | 3189 | 771 | 2418 | **87%** | 92% |
| N_FS-04 | RC | -43.2 | 6777 | 4984 | 10.9 | 2.7 | 8135 | 2866 | 5269 | 106% | - |
| N_HS-01 | Center D | -9.6 | 2886 | 2287 | 5.3 | 5.8 | 3552 | 959 | 2593 | 113% | 110% |
| N_HS-02 | Center D | -9.2 | 2723 | 2324 | 8.7 | 9.0 | 3813 | 1133 | 2680 | 115% | 115% |
| N_HS-03 | Center D | -8.7 | 2700 | 2427 | 10.9 | 5.6 | 4065 | 894 | 3171 | 131% | 130% |
| N_HS-04 | Center D | -8.6 | 2702 | 2303 | 3.7 | 5.7 | 3163 | 892 | 2271 | **99%** | 96% |
| N_HS-05 | Center D | -9.9 | 2654 | 2562 | 16.7 | 7.8 | 4746 | 1109 | 3637 | 142% | 145% |
| N_HS-05 | RC | -54.7 | 7323 | 4843 | 16.7 | -0.9 | 9415 | 3354 | 6061 | 125% | - |
| N_HS-07 | Center D | -7.6 | 2214 | 2668 | 12.0 | 12.0 | 4374 | 1224 | 3149 | 118% | 121% |
| N_HS-09 | Center D | -7.3 | 2428 | 2748 | 12.5 | 12.5 | 4429 | 1235 | 3194 | 116% | 119% |


## Table 2. MRCE Surcharge Monitoring Review (August 2014)

| Source: | | Settlement Monitoring Data | VWP Monitoring Data | MRCE | | | | AMEC |
|---|---|---|---|---|---|---|---|---|
| Settlement Monitoring Point | Layer | Fill Thickness (ft) | Elevation Head (ft) | Total Stress 06/16/14 (psf) | Pore Water Pressure 06/16/14 (psf) | Effective Stress 06/16/14 (psf) | % Completion August 14 | % Completion August 14 |
| N_FS-04 | Center O | 16.3 | 9.6 | 3867 | 738 | 3130 | **120%** | - |
| N_FS-04 | Center D | 16.3 | 9.6 | 4303 | 1003 | 3300 | **119%** | 118% |
| N_HS-04 | Center D | 9.4 | 5.0 | 3877 | 847 | 3030 | **132%** | 99% |

**SURCHARGE AREA 2N**
**FIGURES & ATTACHMENTS**

**Figure 2N-1**

**Instrumentation Location Plan**




| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS5 | 685543 | 602822 |
| FS6 | 685536 | 602927 |
| FS7 | 685433 | 603010 |
| SP15 | 685618 | 602844 |
| SP17 | 685556 | 602977 |
| SP18 | 685557 | 602761 |
| SP19 | 685518 | 602831 |
| SP20 | 685430 | 602979 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\Phi_{M-2}$ | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS12 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE |

Revised/Date: TDD 08/13/14
Checked/Date: SGS 08/13/14

0 15 30 60
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN
AREA 2N
Project 3480-09-0006
Figure C1

J:\Projects\CHROMIUM\JERSEY CITY\Dwg Design-SGS-CDR\GA\SA6N\100 Percent\Figure 2 Surcharge Settling Monitoring Plan - Area 2.dwg Wed, 13 Aug 2014 - 10:58am mgoh-chuter

**Attachment 2N-1**

**Baseline Surcharge Analysis for Monitoring Points**

# AREA 2N
## BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

**SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION**

| SURCHARGE MONITORING POINT | REFERENCE/NEARBY GEOTECHNICAL EXPLORATIONS | EXISTING & PROPOSED GRADING (At Surcharge Monitoring Point) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE (100% Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | ESTIMATED SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | SF/O | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| **N_FS-05** | 087-CPT-013; N_FS-06 | 13.1 | 22.5 | 28.5 | 2.2 | 3.9 | 0.0 | 1.4 | 0.0 | 0.3 | 7.8 | **28.5** | **15.4** | **6.0** | **70%** | **1.0** | 0.8 | 0.6 | **1.4** |
| **N_FS-06** | 087-CPT-013; N_FS-05; N_FS-07 | 12.7 | 22.8 | 28.5 | 2.3 | 3.3 | 0.0 | 3.1 | 0.0 | 0.1 | 8.8 | **28.5** | **15.8** | **5.8** | **72%** | **1.9** | 0.6 | 1.2 | **1.8** |
| **N_FS-07** | 087-CPT-013; N_FS-06; 087-CPT-014 | 13.0 | 20.8 | 28.0 | 2.2 | 1.0 | 0.0 | 1.5 | 0.0 | 0.1 | 4.7 | **28.0** | **15.0** | **7.3** | **61%** | **0.4** | 0.2 | 0.7 | **1.0** |

Prepared By/Date: NDL/8-14-14
Checked By/Date:

**Attachment 2N-2**

**November 21, 2014 Mueser Rutledge Correspondence re:**
**SA-6 North Surcharge Monitoring, Jersey City, NJ**
**(Previously Submitted Report No. 8).**

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

Alfred H. Brand
David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
*Partners*

David R. Good
Walter E. Kaeck
*Associate Partners*

James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Tony D. Canale
Jan Cermak
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
Sitotaw Y. Fantaye
*Senior Associates*

Michael J. Chow
Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

November 21, 2014

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 2N Surcharge Review
SA-6 North
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of November 17, 2014 AMEC settlement and piezometer monitoring data for Area 2N is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used measured fill thickness dated 10/28/14 from "Settlement Platform – Data Report" to calculate the total stress. Pore water was taken from the 10/28/14 "Vibrating Wire Piezometer – Data Report." Effective stress computed for 10/28/14, is presented in Table 1. MRCE compared the 10/28/14 calculated effective stress with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 2N monitoring locations have met the surcharge program goal as of 10/28/14.

Very truly yours,
**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

MP:F:\111\11173\2014 Surcharge Removal Review\SA-6_Area 2N_Surcharge Removal Review\MRCE SA-6 Surcharge Monitoring Review- Area 2N.112114.docx

## Table 1. MRCE SA-6 Surcharge Monitoring Review for Area 2N (10/28/14)


| Source: | | AMEC | | | | Settlement Monitoring Data | VWP Monitoring Data | MRCE | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Settlement Monitoring Point | Layer | Center of the Layer EL. (ft) | Pre-Surcharge Conditions Total Stress (psf) | Final Development Condition Effective Stress (psf) | Surcharge Conditions Effective Stress (psf) | Fill Thickness (ft) | Elevation Head (ft) | Total Stress 10/28/14 (psf) | Pore Water Pressure 10/28/14 (psf) | Effective Stress 10/28/14 (psf) | % Completion 10/28/14 | % Completion 10/28/14 |
| N_FS-05 | Center O | | | 2603.1 | | 14.29 | 7.12 | 3750.0 | 812.4 | 2937.6 | 113% | - |
| N_FS-05 | Center D | -7.3 | 2360.6 | 2765.9 | 3343.5 | 14.29 | 5.41 | 4146.9 | 799.3 | 3347.5 | 121% | 121% |
| N_FS-06 | Center O | | | 2685.9 | | 15.06 | 6.47 | 3837.5 | 640.8 | 3196.7 | 119% | - |
| N_FS-06 | Center D | -7.6 | 2360.6 | 2833.1 | 3387.6 | 15.06 | 5.96 | 4218.8 | 827.4 | 3391.3 | 120% | 120% |
| N_FS-06 | RC | | | 6075.3 | | 15.06 | 2.94 | 10752.5 | 3135.0 | 7617.5 | 125% | - |
| N_FS-07 | Center O | | | 2523.5 | | 10.69 | 6.61 | 3486.3 | 674.5 | 2811.7 | 111% | - |
| N_FS-07 | Center D | -6.7 | 2360.6 | 2588.0 | 2972.4 | 10.69 | 4.87 | 3660.0 | 740.7 | 2919.3 | 113% | 115% |

Notes:
1. % Completion is the ratio of measured effective stress under surcharge with respect to final effective stress in development condition.

**SURCHARGE AREA 3N**
**FIGURES & ATTACHMENTS**

**Figure 3N-1**

**Instrumentation Location Plan**




| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS8 | 685409 | 603096 |
| FS9 | 685493 | 603135 |
| FS10 | 685590 | 603173 |
| FS11 | 685388 | 603343 |
| HS10 | 685491 | 603322 |
| HS11 | 685332 | 603208 |
| HS12 | 685421 | 603404 |
| HS13 | 685256 | 603314 |
| SP14 | 685639 | 603121 |
| SP15 | 685561 | 603086 |
| SP21 | 685299 | 603197 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\Phi_{I-2}$ | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL - SET UP |
| HS-1 | SETTLEMENT MONITORING POINT HALF - SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE |

0 15 30 60
SCALE IN FEET

Revised/Date: TDD 09/30/15
Checked/Date: NDL 09/30/15

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN
AREA 3N
Project 3480-13-0377
Figure D1

J:\Projects\HONEYWELL\JERSEY CITY\Site Drawings\3480-4250\GA\GA3N\3N1.DGN Pennant\Figure 3 Surcharge Settling Monitoring Plan - Area 3.dwg Thu, 30 Jun 2015 - 3:39pm terry.donovan

**Attachment 3N-1**

**Baseline Surcharge Analysis for Monitoring Points**

## AREA 3N
### BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

**SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION**

| SURCHARGE MONITORING POINT | REFERENCE/NEARBY GEOTECHNICAL EXPLORATIONS | EXISTING & PROPOSED GRADING (At Surcharge Monitoring Point) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE (100% Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | ESTIMATED SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | SF/O | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| **N_FS-08** | 087-SB-410; 087-CPT-014 | 12.8 | 19.8 | 23.7 | 1.8 | 2.0 | 0.0 | 2.4 | 0.0 | 0.1 | 6.3 | **23.7** | **10.9** | **3.9** | **71%** | **1.5** | 0.5 | 1.2 | **1.7** |
| **N_FS-09** | 087-SB-410; 087-CPT-014; 087-CPT-015 | 13.2 | 18.3 | 23.7 | 1.3 | 2.1 | 0.0 | 1.8 | 0.0 | 0.1 | 5.3 | **23.7** | **10.6** | **5.4** | **56%** | **1.2** | 0.7 | 1.2 | **1.9** |
| **N_FS-10** | 087-CPT-015; 087-SB-405; 087-CPT-010; 088-CPT003 | 13.3 | 20.7 | 23.8 | 1.8 | 1.2 | 0.0 | 2.7 | 0.0 | 0.2 | 6.0 | **23.8** | **10.6** | **3.1** | **76%** | **1.9** | 0.3 | 1.4 | **1.7** |
| **N_FS-11** | 088-SB-307 | 12.4 | 15.5 | 18.4 | 0.9 | 1.3 | 0.0 | 0.5 | 0.0 | 0.1 | 2.7 | **18.4** | **6.0** | **2.9** | **56%** | **0.4** | 0.6 | 0.5 | **1.1** |
| **N_HS-10** | 088-SB-300; 088-SB-301; 088-SB-307 | 12.3 | 17.0 | 18.7 | 1.3 | 0.7 | 0.0 | 1.0 | 0.0 | 0.0 | 2.9 | **18.7** | **6.4** | **1.7** | **77%** | **0.6** | 0.2 | 0.7 | **1.0** |
| **N_HS-11** | 088-SB-307; 087-CPT-014; 115-SB-211 | 12.8 | 18.7 | 18.9 | 1.7 | 0.9 | 0.0 | 2.5 | 0.0 | 0.0 | 5.0 | **18.9** | **6.1** | **0.2** | **97%** | **4.9** | 0.2 | 1.4 | **1.7** |
| **N_HS-12** | 088-SB-307; 088-SB-301 | 13.1 | 14.5 | 18.3 | 0.4 | 0.4 | 0.0 | 0.2 | 0.0 | 0.1 | 1.0 | **18.3** | **5.2** | **3.8** | **30%** | **0.1** | 0.5 | 0.5 | **1.0** |
| **N_HS-13** | 115-SB-211; 088-SB-307; 088-SB-306 | 13.0 | 16.8 | 18.3 | 1.1 | 0.0 | 0.0 | 2.5 | 0.0 | 0.0 | 3.6 | **18.3** | **5.3** | **1.5** | **75%** | **2.7** | 0.0 | 2.2 | **2.2** |

Prepared By/Date: NDL/6-26-15
Checked By/Date:

**Attachment 3N-2**


**Surcharge Monitoring Data**

**Surcharge Monitoring Data**

**N_FS-08**


# Settlement Platform Data Summary






# Vibrating Wire Piezometer Data Summary






**Sondex System Data Summary**





# Standpipe Piezometer Data Summary






**Surcharge Monitoring Data**

**N_FS-09**


# Settlement Platform Data Summary






# Vibrating Wire Piezometer Data Summary






**Sondex System Data Summary**





**Standpipe Piezometer Data Summary**






**Surcharge Monitoring Data**

**N_FS-10**


# Settlement Platform Data Summary






**Vibrating Wire Piezometer Data Summary**






**Sondex System Data Summary**





# Standpipe Piezometer Data Summary






**Surcharge Monitoring Data**

**N_FS-11**


# Settlement Platform Data Summary






# Vibrating Wire Piezometer Data Summary






**Sondex System Data Summary**





**Standpipe Piezometer Data Summary**






**Surcharge Monitoring Data**

**N_HS-10**


# Settlement Platform Data Summary





# Vibrating Wire Piezometer Data Summary






**Surcharge Monitoring Data**

**N_HS-11**


# Settlement Platform Data Summary





# Vibrating Wire Piezometer Data Summary






**Surcharge Monitoring Data**

**N_HS-12**


# Settlement Platform Data Summary





# Vibrating Wire Piezometer Data Summary






**Surcharge Monitoring Data**

**N_HS-13**


# Settlement Platform Data Summary





# Vibrating Wire Piezometer Data Summary






**Surcharge Monitoring Data**

**N_SP-14**

# Settlement Platform Data Summary






**Surcharge Monitoring Data**

**N_SP-15**

# Settlement Platform Data Summary






**Surcharge Monitoring Data**

**N_SP-21**

# Settlement Platform Data Summary






**Surcharge Monitoring Data**

**N_RP-06**

**Riser Pipe Data Summary**






**Surcharge Monitoring Data**

**N_RP-07**

# Riser Pipe Data Summary





**Attachment 3N-3**

**March 29, 2016 Mueser Rutledge Correspondence re:**
**Updated Area 3N and 4N Surcharge Review, SA-6 North, Jersey City, NJ**

# Mueser Rutledge Consulting Engineers

**14 Penn Plaza · 225 West 34th Street · New York, NY 10122**
**Tel: (917) 339-9300 · Fax: (917) 339-9400**
**www.mrce.com**



Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

David M. Cacoilo
Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Frederick C. Rhyner
Steven R. Lowe
Andrew R. Tognon
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
James M. Tantalla
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
Farid F. Vastani
Jesse L. Richins
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*


March 29, 2016

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attn: Mr. Geoff Shallard

Re: Updated Area 3N and 4N Surcharge Review
SA-6 North
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of March 15th, 2016 AMEC settlement and piezometer monitoring data for Area 3N and 4N is summarized below:

AMEC indicated boring sampling was performed to define the soil profile and the Vibrating Wire Piezometer (VWP) was set at the center of the compressible layer, so that the pore water pressure reading is the most conservative for effective stress evaluation. All the effective stress calculations were made at the center of the layers.

MRCE used the latest measured elevation head dated March 15th, 2016 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated using fill thickness measurements from the "Settlement Platform – Data Report" taken on March 9th, 2016. Calculated post-surcharge effective stresses are presented in Table 1 and Table 2. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of the surcharge program was to achieve an effective stress greater than "Final Post-Development Conditions."

This review finds that with the March 15, 2016 readings all settlement monitoring locations, including the two settlement locations, N_HS-11 in Area 3N (Table 1) and N_FS-12 in Area 4N (Table 2), have met the surcharge program goal. This finding is in agreement with the AMEC data review and interpretation.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

F:\111\11173\2015 Surcharge Removal Review\MRCE Peer Review Area 3N and 4N final.pdf

FOR: SA-6 North Surcharge Monitoring Review

**Table 1. Area 3N Surcharge Review**

| Settlement Monitoring Point | Layer | Existing EL. (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| **N_FS-08** | Center D | -7.0 | 2226.3 | 2400.5 | 2/9/2016 | 2/22/2016 | 11.8 | 7.0 | 3697.5 | 876.1 | 2821.4 | **118%** | **114%** |
| **N_FS-09** | Center D | -4.9 | 2151.3 | 2217.8 | 2/9/2016 | 2/22/2016 | 12.0 | 6.4 | 3648.8 | 699.4 | 2949.4 | **133%** | **127%** |
| **N_FS-10** | Center O | -3.5 | 1937.5 | 2525.6 | 2/9/2016 | 2/22/2016 | 12.4 | 8.6 | 3485.0 | 756.7 | 2728.3 | **108%** | **109%** |
| | Center D | -6.0 | 2202.5 | 2619.0 | 2/9/2016 | 2/22/2016 | 12.4 | 6.7 | 3750.0 | 794.8 | 2955.2 | **113%** | |
| **N_FS-11** | Center D | -5.1 | 2032.5 | 1919.6 | 2/9/2016 | 2/22/2016 | 6.4 | 4.2 | 2837.5 | 579.8 | 2257.7 | **118%** | **118%** |
| **N_HS-10** | Center D | -5.2 | 2083.8 | 2216.4 | 2/9/2016 | 2/22/2016 | 7.5 | 6.4 | 3026.3 | 721.5 | 2304.7 | **104%** | **101%** |
| **N_HS-11** | Center D | -5.7 | 2147.5 | 2280.4 | 3/9/2016 | 3/15/2016 | 6.6 | 4.2 | 2975.0 | 617.3 | 2357.7 | **103%** | **102%** |
| **N_HS-12** | Center D | -4.4 | 2042.5 | 1931.7 | 2/9/2016 | 2/22/2016 | 5.5 | 4.5 | 2730.0 | 551.0 | 2179.0 | **113%** | **111%** |
| **N_HS-13** | Center D | -4.4 | 1991.3 | 2050.1 | 2/9/2016 | 2/22/2016 | 5.8 | 4.3 | 2711.3 | 539.3 | 2172.0 | **106%** | **107%** |

FOR: SA-6 North Surcharge Monitoring Review

**Table 2. Area 4N Surcharge Review**

| Settlement Monitoring Point | Layer | Existing EL. (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | **MRCE** | **AMEC** |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | **% Completion** | **% Completion** |
| **N_FS-12** | Center D | -4.1 | 1927.5 | 1869.2 | 3/9/2016 | 3/15/2016 | 3.4 | 3.5 | 2348.8 | 473.9 | 1874.9 | **100%** | **101%** |
| **N_FS-13** | Center D | -4.6 | 2248.8 | 2063.8 | 1/28/2016 | 2/22/2016 | 3.1 | -0.9 | 2640.0 | 232.2 | 2407.8 | **117%** | **119%** |

**SURCHARGE AREA 4N**
**FIGURES & ATTACHMENTS**

**Figure 4N-1**

**Instrumentation Location Plan**




| SETTELMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS12 | 685304 | 603416 |
| FS13 | 685208 | 603374 |
| SP22 | 685182 | 603355 |
| SP23 | 685359 | 603466 |
| SP24 | 685359 | 603491 |
| SP25 | 685072 | 603483 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS12 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS12 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE |

0 15 30 60
SCALE IN FEET

Revised/Date: TDD 08/30/15
Checked/Date: NDL 08/30/15

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN
AREA 4N
Project 3480-13-0377
Figure E1

Z:\Projects\HONEYWELL\JERSEY CITY\Site Data\p--3480-4250\GIS\MXD\Fig4 Surcharge Pile\Monitoring Plan - Area 4.dwg Thu, 30 Jun 2015 - 2:39pm kenji.ahnnen

**Attachment 4N-1**

**Baseline Surcharge Analysis for Monitoring Points**

# AREA 4N
## BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

**SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION**

| SURCHARGE MONITORING POINT | REFERENCE/NEARBY GEOTECHNICAL EXPLORATIONS | EXISTING & PROPOSED GRADING (At Surcharge Monitoring Point) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE (100% Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | ESTIMATED SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | SF/O | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| **N_FS-12** | 088-SB-307; 088-SB-306 | 12.9 | 14.4 | 16.5 | 0.5 | 0.0 | 0.0 | 0.7 | 0.0 | 0.0 | 1.2 | **16.5** | **3.6** | **2.1** | **45%** | **0.4** | 0.0 | 1.4 | **1.4** |
| **N_FS-13** | 088-SB-306; 115-SB-211 | 15.0 | 16.6 | 18.0 | 0.6 | 0.0 | 0.0 | 0.8 | 0.0 | 0.0 | 1.3 | **18.0** | **3.0** | **1.4** | **56%** | **0.8** | 0.0 | 1.7 | **1.7** |

Prepared By/Date: NDL/6-26-15
Checked By/Date:

**Attachment 4N-2**


**Surcharge Monitoring Data**

**Surcharge Monitoring Data**

**N_FS-12**

# Settlement Platform Data Summary






# Vibrating Wire Piezometer Data Summary




## N_FS-12_VWP




**Sondex System Data Summary**





# Standpipe Piezometer Data Summary






**Surcharge Monitoring Data**

**N_FS-13**

**Settlement Platform Data Summary**




# N_FS-13_SP




**Vibrating Wire Piezometer Data Summary**






**Sondex System Data Summary**





# Standpipe Piezometer Data Summary






**Surcharge Monitoring Data**

**N_SP-22**

# Settlement Platform Data Summary






**Surcharge Monitoring Data**

**N_SP-23**

# Settlement Platform Data Summary






**Surcharge Monitoring Data**

**N_SP-24**

# Settlement Platform Data Summary






**Surcharge Monitoring Data**

**N_SP-25**

# Settlement Platform Data Summary





**Attachment 4N-3**

**March 29, 2016 Mueser Rutledge Correspondence re:**
**Updated Area 3N and 4N Surcharge Review, SA-6 North, Jersey City, NJ**

# Mueser Rutledge Consulting Engineers

**14 Penn Plaza · 225 West 34th Street · New York, NY 10122**
**Tel: (917) 339-9300 · Fax: (917) 339-9400**
**www.mrce.com**



Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

David M. Cacoilo
Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Frederick C. Rhyner
Steven R. Lowe
Andrew R. Tognon
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
James M. Tantalla
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
Farid F. Vastani
Jesse L. Richins
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*


March 29, 2016

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attn: Mr. Geoff Shallard

Re: Updated Area 3N and 4N Surcharge Review
SA-6 North
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of March 15th, 2016 AMEC settlement and piezometer monitoring data for Area 3N and 4N is summarized below:

AMEC indicated boring sampling was performed to define the soil profile and the Vibrating Wire Piezometer (VWP) was set at the center of the compressible layer, so that the pore water pressure reading is the most conservative for effective stress evaluation. All the effective stress calculations were made at the center of the layers.

MRCE used the latest measured elevation head dated March 15th, 2016 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated using fill thickness measurements from the "Settlement Platform – Data Report" taken on March 9th, 2016. Calculated post-surcharge effective stresses are presented in Table 1 and Table 2. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of the surcharge program was to achieve an effective stress greater than "Final Post-Development Conditions."

This review finds that with the March 15, 2016 readings all settlement monitoring locations, including the two settlement locations, N_HS-11 in Area 3N (Table 1) and N_FS-12 in Area 4N (Table 2), have met the surcharge program goal. This finding is in agreement with the AMEC data review and interpretation.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

F:\111\11173\2015 Surcharge Removal Review\MRCE Peer Review Area 3N and 4N final.pdf

FOR: SA-6 North Surcharge Monitoring Review

**Table 1. Area 3N Surcharge Review**

| Settlement Monitoring Point | Layer | Existing EL. (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| **N_FS-08** | Center D | -7.0 | 2226.3 | 2400.5 | 2/9/2016 | 2/22/2016 | 11.8 | 7.0 | 3697.5 | 876.1 | 2821.4 | **118%** | **114%** |
| **N_FS-09** | Center D | -4.9 | 2151.3 | 2217.8 | 2/9/2016 | 2/22/2016 | 12.0 | 6.4 | 3648.8 | 699.4 | 2949.4 | **133%** | **127%** |
| **N_FS-10** | Center O | -3.5 | 1937.5 | 2525.6 | 2/9/2016 | 2/22/2016 | 12.4 | 8.6 | 3485.0 | 756.7 | 2728.3 | **108%** | **109%** |
| | Center D | -6.0 | 2202.5 | 2619.0 | 2/9/2016 | 2/22/2016 | 12.4 | 6.7 | 3750.0 | 794.8 | 2955.2 | **113%** | |
| **N_FS-11** | Center D | -5.1 | 2032.5 | 1919.6 | 2/9/2016 | 2/22/2016 | 6.4 | 4.2 | 2837.5 | 579.8 | 2257.7 | **118%** | **118%** |
| **N_HS-10** | Center D | -5.2 | 2083.8 | 2216.4 | 2/9/2016 | 2/22/2016 | 7.5 | 6.4 | 3026.3 | 721.5 | 2304.7 | **104%** | **101%** |
| **N_HS-11** | Center D | -5.7 | 2147.5 | 2280.4 | 3/9/2016 | 3/15/2016 | 6.6 | 4.2 | 2975.0 | 617.3 | 2357.7 | **103%** | **102%** |
| **N_HS-12** | Center D | -4.4 | 2042.5 | 1931.7 | 2/9/2016 | 2/22/2016 | 5.5 | 4.5 | 2730.0 | 551.0 | 2179.0 | **113%** | **111%** |
| **N_HS-13** | Center D | -4.4 | 1991.3 | 2050.1 | 2/9/2016 | 2/22/2016 | 5.8 | 4.3 | 2711.3 | 539.3 | 2172.0 | **106%** | **107%** |

FOR: SA-6 North Surcharge Monitoring Review


**Table 2. Area 4N Surcharge Review**


| Settlement Monitoring Point | Layer | Existing EL. (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | **MRCE** | **AMEC** |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | **% Completion** | **% Completion** |
| **N_FS-12** | Center D | -4.1 | 1927.5 | 1869.2 | 3/9/2016 | 3/15/2016 | 3.4 | 3.5 | 2348.8 | 473.9 | 1874.9 | **100%** | **101%** |
| **N_FS-13** | Center D | -4.6 | 2248.8 | 2063.8 | 1/28/2016 | 2/22/2016 | 3.1 | -0.9 | 2640.0 | 232.2 | 2407.8 | **117%** | **119%** |

**SURCHARGE AREA 1S**
**FIGURES & ATTACHMENTS**

**Figure 1S-1**

**Instrumentation Location Plan**




SECTION 1-1

| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-1 | 685274 | 601922 |
| FS-2 | 685321 | 601752 |
| HS-1 | 685597 | 601567 |
| HS-2 | 685494 | 601682 |
| HS-3 | 685422 | 601801 |
| HS-4 | 685302 | 601934 |
| HS-5 | 685488 | 601622 |
| HS-6 | 685519 | 601480 |
| HS-7 | 685413 | 601624 |
| HS-8 | 685212 | 601906 |
| VI-1 | 685825 | 601520 |
| VI-2 | 685577 | 601473 |
| SP-1 | 685579 | 601642 |
| SP-2 | 685419 | 601860 |
| SP-3 | 685286 | 602040 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

- VI-2 — INCLINOMETER LOCATION
- FS-1 — SETTLEMENT MONITORING POINT FULL - SET UP
- HS-1 — SETTLEMENT MONITORING POINT HALF - SET UP
- SP12 — SETTLEMENT MONITORING PLATFORM
- RP — APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 10/17/14
Checked/Date: SGS 10/17/14

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN
AREA 1S
Project 3480-12-0317
Figure F1

Z:\Projects\HONEYWELL\JERSEY CITY\Cdp Design-SA6-7\SA7\SA7MXD\Figure - Surcharge Area1 Instrumentation Plan.dwg Fri, 17 Oct 2014 - 11:08am roger.rueter

**Attachment 1S-1**

**Baseline Surcharge Analysis for Monitoring Points**

# AREA 1S
## BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

### SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION

| SURCHARGE MONITORING STATION NO. | NEARBY EXPLORATION NO(s). | ELEVATION DATA (At Surcharge Monitoring Station) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADES (Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | F-COPR | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| **S_FS-01** | 134-SB-503 | 7.9 | 20.5 | 28.0 | 2.5 | 3.2 | 0.0 | 9.6 | 1.6 | 0.9 | 17.8 | **28.0** | **20.1** | **7.5** | **75%** | **5.3** | 0.5 | 2.4 | **2.9** |
| **S_FS-02** | 073-SB-501 | 7.0 | 18.5 | 27.5 | 2.6 | 3.0 | 0.0 | 5.8 | 1.5 | 0.3 | 13.2 | **27.5** | **20.5** | **9.0** | **69%** | **2.7** | 0.5 | 1.7 | **2.2** |
| **S_HS-01** | 073-SB-005; 115-SB-202 | 8.3 | 22.0 | 24.0 | 3.0 | 3.1 | 0.0 | 3.4 | 1.4 | 1.4 | 12.3 | **24.0** | **15.7** | **2.0** | **91%** | **3.1** | 0.5 | 1.0 | **1.5** |
| **S_HS-02** | 073-PZ-001; 073-PZ-002; 115-SB-305; 115-SB-203 | 8.7 | 18.8 | 23.5 | 2.5 | 1.4 | 0.0 | 4.9 | 1.1 | 1.0 | 10.9 | **23.5** | **14.9** | **4.8** | **76%** | **2.6** | 0.3 | 1.7 | **2.0** |
| **S_HS-03** | 073-SB-501; 115-SB-306; 134-SB-503 | 8.1 | 18.3 | 25.0 | 1.8 | 4.8 | 0.0 | 7.8 | 1.3 | 0.3 | 16.1 | **25.0** | **16.9** | **6.8** | **71%** | **6.4** | 0.8 | 2.4 | **3.2** |
| **S_HS-04** | 134-SB-503; 115-SB-307 | 8.0 | 20.3 | 28.0 | 2.7 | 2.3 | 0.0 | 8.6 | 2.0 | 2.1 | 17.7 | **28.0** | **20.0** | **7.8** | **74%** | **3.9** | 0.4 | 2.2 | **2.5** |
| **S_HS-05** | 073-PZ-002; 073-CPT-003 | 9.2 | 19.0 | 23.0 | 2.0 | 3.0 | 0.0 | 3.3 | 1.0 | 1.4 | 10.8 | **23.0** | **13.8** | **4.0** | **78%** | **2.8** | 0.7 | 1.2 | **1.9** |
| **S_HS-06** | 073-SB-500; 073-CPT-001; 073-CPT-005 | 7.9 | 20.3 | 24.0 | 2.9 | 1.3 | 0.0 | 4.0 | 1.4 | 0.7 | 10.4 | **24.0** | **16.2** | **3.8** | **84%** | **1.8** | 0.2 | 1.2 | **1.4** |
| **S_HS-07** | 073-CPT-003 | 7.0 | 18.0 | 24.0 | 2.1 | 4.2 | 0.0 | 5.0 | 1.3 | 1.6 | 14.2 | **24.0** | **17.0** | **6.0** | **75%** | **3.4** | 0.7 | 1.4 | **2.2** |
| **S_HS-08** | 134-SB-500; 134-CPT-002 | 8.3 | 20.8 | 24.5 | 2.2 | 3.6 | 0.0 | 9.5 | 2.1 | 2.0 | 19.5 | **24.5** | **16.2** | **3.8** | **85%** | **7.9** | 0.5 | 2.4 | **2.9** |

Prepared By/Date: NDL/8-14-14

Checked By/Date:

**Attachment 1S-2**

**October 27, 2014 Mueser Rutledge Correspondence re:**
**SA-6 South Surcharge Monitoring, Jersey City, NJ**
**(Previously Submitted Report No. 7)**

# Mueser Rutledge Consulting Engineers

**14 Penn Plaza · 225 West 34th Street · New York, NY 10122**
**Tel: (917) 339-9300 · Fax: (917) 339-9400**
**www.mrce.com**



Alfred H. Brand
David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
*Partners*

David R. Good
Walter E. Kaeck
*Associate Partners*

James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Tony D. Canale
Jan Cermak
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
Sitotaw Y. Fantaye
*Senior Associates*

Michael J. Chow
Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*


October 27, 2014

Geoff Shallard
AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Re: SA-6 ~~North~~ Surcharge Monitoring
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

Mueser Rutledge Consulting Engineers (MRCE) reviewed the settlement and piezometer monitoring data related to Area 1S provided by AMEC, on October 17th 2014. MRCE's review of the available data is summarized below:

1. AMEC indicated boring sampling were performed and the Vibrating Wire Piezometer (VWP) was set at the center of the layer. Center of the layer provide the most conservative pore water pressure reading for the effective stress evaluation. All the effective stress calculations were made at the center of the layers.

2. MRCE used measured fill thickness dated 09/22/14 from provided "Settlement Platform – Data Report" and calculated the total stress as of 09/22/14 based on the fill thickness recorded on 09/22/14 and the "Historic Pre-Construction Conditions" total stresses provided by AMEC. MRCE evaluated the pore water pressures based on the piezometer reading on 09/23/14 from "Vibrating Wire Piezometer – Data Report" and calculated the effective stresses as of 09/23/14, as presented in Table 1.

3. MRCE compared calculated effective stresses of 09/23/14 with the effective stresses provided by AMEC for "Final Post-Development Conditions". The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions" effective stress. Percent completion computed by MRCE ("MRCE % Completion (09/23/14)" in Table 1) indicates effective stress compared to "Final Post-Development Conditions" effective stress; percent completion greater than 100 % indicates overconsolidation compared to "Final Post-Development Conditions" effective stress. Table 1 also presents percent completion evaluation of AMEC as of 09/26/14, "AMEC % Completion (09/26/14)" for comparison.

4. Settlement monitoring location S_FS-02 (highlighted in attached Table 1) has not yet met the surcharge program goal as of 09/23/14.

5. MRCE suggests leaving the surcharge on at S_FS-02 location until the pore water pressure dissipate such that the pore pressure head measured in the middle of Stratum D drops an additional 1.5 ft, or raising grade to increase the total stress to accelerate consolidation.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

MP:H:\111\11173\2014 Surcharge Removal Review\SA 6_Area 1S_Surcharge Removal Review\MRCE SA-6 Surcharge Monitoring Review- Area 1S.docx


## Table 1. MRCE SA-6 Surcharge Monitoring Review for Area 1S (09/23/14)

| Source: | | AMEC | | | | Settlement Monitoring Data | VWP Monitoring Data | MRCE | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Settlement Monitoring Point | Layer | Center of the Layer EL. (ft) | Pre-Surcharge Conditions Total Stress (psf) | Final Development Condition Effective Stress (psf) | Surcharge Conditions Effective Stress | Fill Thickness (ft) | Elevation Head (ft) | Total Stress 09/22/14 (psf) | Pore Water Pressure 09/23/14 (psf) | Effective Stress 09/23/14 (psf) | % Completion 09/23/14 | % Completion 09/26/14 |
| S_FS-01 | Center D | -8.6 | 1852.5 | 2616.3 | 2451.0 | 17.15 | -8.6 | 3996.3 | 1274.8 | 2721.4 | 104% | 94% |
| S_FS-02 | Center D | -11.16 | 2083.8 | 2627.1 | 2428.0 | 16.31 | -11.16 | 4122.6 | 1509.5 | 2613.1 | 99% | 92% |
| S_HS-01 | Center D | -11.2 | 2260.0 | 3064.0 | 3196.0 | 15.31 | -11.2 | 4173.8 | 891.7 | 3282.1 | 107% | 104% |
| S_HS-02 | Center D | -9.6 | 2103.8 | 2570.7 | 2774.0 | 15.22 | -9.6 | 4006.3 | 1042.7 | 2963.6 | 115% | 108% |
| S_HS-03 | Center D | -9.4 | 1942.5 | 2400.1 | 2440.0 | 15.9 | -9.4 | 3930.0 | 1347.2 | 2582.8 | 108% | 102% |
| S_HS-04 | Center D | -8.3 | 1841.3 | 2548.2 | 2595.0 | 15.54 | -9 | 3783.8 | 1148.2 | 2635.6 | 103% | 102% |
| S_HS-05 | Center D | -8.5 | 2031.3 | 2583.0 | 2703.0 | 13.89 | -9.3 | 3767.6 | 970.3 | 2797.2 | 108% | 105% |
| S_HS-06 | Center D | -10.4 | 2126.3 | 2880.7 | 3214.0 | 16.24 | -11.15 | 4156.3 | 867.4 | 3288.9 | 114% | 112% |
| S_HS-07 | Center D | -9.5 | 1867.5 | 2493.7 | 2894.0 | 17.84 | -9.5 | 4097.5 | 1007.8 | 3089.7 | 124% | 116% |
| S_HS-08 | Center D | -7.7 | 1787.5 | 2595.0 | 2707.0 | 16.29 | -7.7 | 3823.8 | 963.5 | 2860.3 | 110% | 104% |

**SURCHARGE AREA 2S**
**FIGURES & ATTACHMENTS**

**Figure 2S-1**

**Instrumentation Location Plan**




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-3 | 685140 | 602174 |
| FS-4 | 685005 | 602182 |
| FS-5 | 684727 | 602549 |
| HS-9 | 685219 | 602088 |
| HS-10 | 685007 | 602367 |
| HS-11 | 684870 | 602559 |
| HS-12 | 685124 | 602107 |
| HS-13 | 684730 | 602660 |
| HS-14 | 685122 | 602042 |
| HS-15 | 684875 | 602354 |
| SP-4 | 685204 | 602153 |
| SP-5 | 685074 | 602329 |
| SP-6 | 684935 | 602519 |
| SP-7 | 684797 | 602707 |

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS-1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP-12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 08/13/14
Checked/Date: TDD 08/13/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | INSTRUMENTATION LOCATION PLAN<br>AREA 2S<br>Project 3480-12-0317<br>Figure G1 |

Z:\Projects\HONEYWELL\479021 CITY\Dwg - Site-wide\DWG\MXD\Figure - Surcharge Area2 Instrumentation Plan.dwg Thu, 14 Aug 2014 - 12:48pm ingar.rhyder

**Attachment 2S-1**

**Baseline Surcharge Analysis for Monitoring Point**

# AREA 2S
## BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

### SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION

| SURCHARGE MONITORING STATION NO. | NEARBY EXPLORATION NO(s). | ELEVATION DATA (At Surcharge Monitoring Station) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADES (Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | F-COPR | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| S_FS-03 | 115-SB-308; 115-SB-309; 134-PZ-003; 134-PZ-004 | 8.3 | 19.5 | 27.5 | 2.3 | 2.8 | 0.0 | 8.6 | 1.9 | 1.4 | 17.0 | **27.5** | **19.3** | **8.0** | **72%** | **3.9** | 0.4 | 2.2 | **2.6** |
| S_FS-04 | 134-SB-501; 140-CPT-001 | 8.5 | 20.0 | 28.0 | 2.2 | 2.2 | 0.0 | 12.3 | 1.7 | 1.0 | 19.4 | **28.0** | **19.5** | **8.0** | **73%** | **6.3** | 0.3 | 3.0 | **3.3** |
| S_FS-05 | 140-SB-501; 140-CPT-003; 125-SB-501; S_HS-11 | 9.4 | 16.8 | 23.5 | 1.7 | 1.8 | 0.0 | 9.1 | 1.1 | 0.5 | 14.2 | **23.5** | **14.1** | **6.8** | **65%** | **5.0** | 0.4 | 3.0 | **3.4** |
| S_HS-09 | 115-SB-204; 134-SB-503 | 8.0 | 18.8 | 26.0 | 2.2 | 2.8 | 0.0 | 8.6 | 1.8 | 1.9 | 17.3 | **26.0** | **18.0** | **7.3** | **73%** | **4.0** | 0.4 | 2.2 | **2.6** |
| S_HS-10 | 115-SB-309; 140-CPT-001 | 13.4 | 22.0 | 25.5 | 2.2 | 1.3 | 0.0 | 3.0 | 0.6 | 1.0 | 8.0 | **25.5** | **12.1** | **3.5** | **78%** | **1.7** | 0.3 | 1.2 | **1.5** |
| S_HS-11 | 115-SB-310; 115-SB-311; 140--CPT-003; 140-SB-501 | 9.8 | 19.5 | 22.0 | 2.4 | 2.5 | 0.0 | 3.8 | 0.6 | 0.6 | 9.9 | **22.0** | **12.2** | **2.5** | **85%** | **2.9** | 0.5 | 1.2 | **1.7** |
| S_HS-12 | 134-SB-501; 134-CPT-003; 115-SB-308 | 8.6 | 19.8 | 25.0 | 2.4 | 2.1 | 0.0 | 9.1 | 1.3 | 1.2 | 16.2 | **25.0** | **16.4** | **5.3** | **78%** | **5.8** | 0.4 | 2.5 | **2.9** |
| S_HS-13 | 125-SB-501; 125-CPT-001; 140-SB-501 | 9.8 | 19.0 | 24.5 | 2.0 | 2.3 | 0.0 | 8.6 | 1.0 | 0.7 | 14.5 | **24.5** | **14.7** | **5.5** | **74%** | **5.0** | 0.4 | 2.5 | **2.9** |
| S_HS-14 | 134-CPT-003; S_HS-12; 134-SB-500; 134-SB-501 | 8.7 | 18.0 | 25.5 | 2.1 | 2.0 | 0.0 | 6.2 | 1.6 | 0.8 | 12.7 | **25.5** | **16.8** | **7.5** | **68%** | **2.4** | 0.4 | 1.8 | **2.2** |
| S_HS-15 | 140-SB-500; 140-CPT-002 | 11.5 | 22.0 | 28.0 | 2.6 | 1.8 | 0.0 | 2.5 | 0.8 | 1.0 | 8.7 | **28.0** | **16.5** | **6.0** | **73%** | **1.0** | 0.4 | 0.8 | **1.2** |

Prepared By/Date: NDL/8-14-14

Checked By/Date:

**Attachment 2S-2**

**February 6, 2015 Mueser Rutledge Correspondence re:**
**SA-6 South Surcharge Monitoring, Jersey City, NJ**
**(Previously submitted Report No. 10)**

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Michael J. Chow
Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

February 06, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 2S Surcharge Review
SA-6 North
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of February 06, 2015 AMEC settlement and piezometer monitoring data for Area 2S is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated between January 12-29, 2015 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken at corresponding dates, between January 14-30, 2015. Calculated post-surcharge effective stresses are presented in Table 1. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 2S monitoring locations have met the surcharge program goal as of 01/30/2015.

Very truly yours,
**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

Table 1. MRCE SA-6 Surcharge Monitoring Review for Area 2S


| Settlement Monitoring Point | Layer | Existing EL. (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| S_FS-03 | Center O | -3.3 | 1332.5 | 2208.4 | 1/14/2015 | 1/12/2015 | 19.7 | 9.9 | 3798.8 | 823.7 | 2975.1 | 135% | - |
| | Top D | -5.8 | 1525.0 | 2291.7 | | | 19.7 | 13.0 | 3991.3 | 1172.5 | 2818.8 | 123% | - |
| | Center D | -7.0 | 1716.3 | 2342.5 | | | 19.7 | 13.4 | 4182.6 | 1273.6 | 2909.0 | 124% | 145% |
| | Bottom D | -8.3 | 1907.5 | 2393.4 | | | 19.7 | 6.5 | 4373.8 | 926.0 | 3447.7 | 144% | - |
| S_FS-04 | Center O | -1.5 | 1204.5 | 2223.3 | 1/23/2015 | 1/18/2015 | 19.8 | 7.6 | 3683.3 | 566.0 | 3117.3 | 140% | - |
| | Top D | -4.5 | 1353.0 | 2287.6 | | | 19.8 | 12.4 | 3831.8 | 1050.2 | 2781.6 | 122% | - |
| | Center D | -6.2 | 1620.8 | 2358.7 | | | 19.8 | 13.0 | 4099.6 | 1196.8 | 2902.7 | 123% | 134% |
| | Bottom D | -7.7 | 1888.5 | 2429.9 | | | 19.8 | 10.6 | 4367.3 | 1143.8 | 3223.5 | 133% | - |
| | RC | -46.5 | 6613.5 | 4771.3 | | | 19.8 | 3.9 | 9092.3 | 3147.5 | 5944.8 | 125% | - |
| S_FS-05 | Center O | -0.6 | 1185.0 | 1696.9 | 1/30/2015 | 1/29/2015 | 14.5 | 5.9 | 2992.5 | 406.8 | 2585.7 | 152% | - |
| | Top D | -3.6 | 1350.0 | 1768.3 | | | 14.5 | 8.1 | 3157.5 | 730.1 | 2427.4 | 137% | - |
| | Center D | -5.1 | 1617.8 | 1839.5 | | | 14.5 | 20.3 | 3425.3 | 1583.1 | 1842.2 | 100% | 115% |
| | Bottom D | -6.6 | 1885.5 | 1910.7 | | | 14.5 | 9.8 | 3693.0 | 1022.7 | 2670.3 | 140% | - |
| S_HS-09 | Center O | -4.0 | 1272.5 | 2097.7 | 1/14/2015 | 1/12/2015 | 18.2 | 9.1 | 3547.5 | 818.7 | 2728.8 | 130% | - |
| | Center D | -8.0 | 1656.3 | 2231.9 | | | 18.2 | 6.4 | 3931.3 | 896.7 | 3034.6 | 136% | 156% |
| S_HS-10 | Center O | -2.1 | 1831.3 | 2384.9 | 1/14/2015 | 1/12/2015 | 12.6 | 6.6 | 3406.3 | 545.4 | 2860.9 | 120% | - |
| | Center D | -4.4 | 2088.8 | 2478.6 | | | 12.6 | 10.2 | 3663.8 | 912.3 | 2751.5 | 111% | 131% |
| S_HS-11 | Center O | -5.2 | 1660.0 | 2218.6 | 1/14/2015 | 1/12/2015 | 12.8 | 9.0 | 3253.8 | 887.3 | 2366.4 | 107% | - |
| | Center D | -7.5 | 1986.3 | 2342.0 | | | 12.8 | 7.4 | 3580.1 | 927.9 | 2652.2 | 113% | 132% |
| | RC | -50.2 | 7257.5 | 4930.1 | | | 12.8 | 3.8 | 8851.3 | 3372.7 | 5478.5 | 111% | - |
| S_HS-12 | Center O | -3.9 | 1485.0 | 2350.9 | 1/14/2015 | 1/12/2015 | 15.9 | 10.1 | 3477.5 | 871.7 | 2605.8 | 111% | - |
| | Center D | -7.9 | 1875.3 | 2482.1 | | | 15.9 | 9.4 | 3867.8 | 1076.4 | 2791.4 | 112% | 130% |
| | RC | -52.4 | 7238.0 | 5077.5 | | | 15.9 | 1.8 | 9230.5 | 3382.1 | 5848.4 | 115% | - |
| S_HS-13 | Center O | -2.0 | 1261.5 | 1962.8 | 1/30/2015 | 1/292015 | 16.0 | 17.0 | 3255.3 | 1183.7 | 2071.5 | 106% | - |
| | Center D | -5.2 | 1664.0 | 2100.1 | | | 16.0 | 14.9 | 3657.8 | 1253.6 | 2404.1 | 114% | 129% |
| S_HS-14 | Center O | -2.0 | 1365.0 | 2023.3 | 1/14/2015 | 1/12/2015 | 17.6 | 10.6 | 3563.8 | 783.7 | 2780.0 | 137% | - |
| | Center D | -6.3 | 1691.5 | 2137.6 | | | 17.6 | 10.4 | 3890.3 | 1039.6 | 2850.7 | 133% | 148% |
| S_HS-15 | Center O | -2.8 | 1858.8 | 2539.5 | 1/14/2015 | 1/12/2015 | 16.6 | 11.5 | 3928.8 | 889.8 | 3039.0 | 120% | - |
| | Center D | -6.8 | 2111.9 | 2636.6 | | | 4181.9 | 964.7 | 3217.2 | 122% | 3217.2 | 122% | 140% |

"Note that the Amec calculations referenced by MRCE were subsequently updated. Please refer to Table 2S-1 for the final values used. The correction does not impact the conclusion."

**SURCHARGE AREA 3S**
**FIGURES & ATTACHMENTS**

**Figure 3S-1**

**Instrumentation Location Plan**




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-6 | 684538 | 602919 |
| FS-7 | 684638 | 602751 |
| HS-16 | 684614 | 602849 |
| HS-17 | 684488 | 603027 |
| HS-18 | 684333 | 603198 |
| HS-19 | 684211 | 603277 |
| HS-20 | 684543 | 602776 |
| HS-21 | 684409 | 602931 |
| HS-22 | 684263 | 603093 |
| ~~SP-8~~ | ~~684726~~ | ~~602761~~ |
| SP-08(2) | 684642 | 602882 |

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS-1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP-12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 03/17/15
Checked/Date: TDD 03/17/15

Honeywell
101 COLUMBIA RD, BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN
AREA 3S
Project 3480-12-0317
Figure H1

J:\Projects\VENTRELLA,PERSEY CITY\Dwg Design-3dw-CSD\GAP\3480\Figure - Surcharge Panel Instrumentation Plan.dwg Tue, 17 Mar 2015 - 8:40am ingersfuller

**Attachment 3S-1**

**Baseline Surcharge Analysis for Monitoring Point**

# AREA 3S
## BASELINE SURCHARGE ANALYSIS FOR MONITORING POINTS

### SUMMARY OF EXISTING & PROPOSED GRADING, ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE, DESIGN SURCHARGE, and ESTIMATED SECONDARY COMPRESSION

| SURCHARGE MONITORING POINT | REFERENCE/NEARBY GEOTECHNICAL EXPLORATIONS | EXISTING & PROPOSED GRADING (At Surcharge Monitoring Point) | | | ESTIMATED SETTLEMENT DUE TO PROPOSED GRADE (100% Primary Consolidation) | | | | | | | SURCHARGE ANALYSIS (Targeting Removal of 100% Primary Consolidation Due to Proposed Grades) | | | | | ESTIMATED SECONDARY COMPRESSION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Soil Stratum | | | | | | Total | Design | | | Analysis Results | | Soil Stratum | | Total |
| | | Existing Grade | Proposed Grade | Top of Surcharge Grade | F | O | F-COPR | D | S1 | RC | | Top of Surcharge Grade | Surcharge Height Above Existing Grade | Surcharge Height Above Proposed Grade | Estimated Surcharge Consolidation to Achieve 100% of Primary Consolidation Due to Proposed Grade | Estimated Time to Achieve 100% of Primary Consolidation Due to Proposed Grade | O | D | |
| | | (feet) | (feet) | (feet) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (inches) | (feet) | (feet) | (feet) | (%) | (months) | (inches) | (inches) | (inches) |
| S_FS-06 | 115-SB-313; 124-SB-503; 125-SB-500; 125-CPT-002 | 9.9 | 18.5 | 23.5 | 1.9 | 0.9 | 0.0 | 9.1 | 0.7 | 0.6 | 13.3 | **23.5** | **13.7** | **5.0** | **74%** | **5.3** | 0.2 | 2.9 | **3.1** |
| S_FS-07 | 125-SB-500; 125-CPT-002; 115-SB-312 | 9.8 | 21.3 | 27.5 | 2.2 | 2.2 | 0.0 | 9.1 | 1.0 | 0.7 | 15.1 | **27.5** | **17.8** | **6.3** | **77%** | **4.4** | 0.3 | 2.3 | **2.6** |
| S_HS-16 | 125-SB-500; 125-CPT-002; 115-SB-312; 115-SB-313 | 9.7 | 22.3 | 27.0 | 2.3 | 1.2 | 0.0 | 11.8 | 1.4 | 0.8 | 17.5 | **27.0** | **17.3** | **4.8** | **82%** | **6.7** | 0.2 | 2.8 | **3.0** |
| S_HS-17 | 124-SB-503; 115-SB-207 | 9.2 | 15.8 | 19.5 | 1.4 | 1.6 | 0.0 | 5.3 | 0.4 | 0.2 | 9.0 | **19.5** | **10.3** | **3.8** | **73%** | **3.1** | 0.4 | 1.9 | **2.3** |
| S_HS-18 | 124-SB-503; 115-SB-315; 115-SB-208 | 9.7 | 10.0 | 11.5 | 0.1 | 0.0 | 0.0 | 0.3 | 0.0 | 0.0 | 0.5 | **11.5** | **1.8** | **1.5** | **17%** | **0.1** | 0.0 | 1.9 | **1.9** |
| S_HS-19 | 124-CPT-003; 124-SB-502; 124-SB-501 | 9.4 | 10.3 | 12.5 | 0.4 | 0.0 | 0.0 | 0.8 | 0.1 | 0.0 | 1.3 | **12.5** | **3.1** | **2.3** | **32%** | **0.2** | 0.0 | 1.4 | **1.4** |
| S_HS-20 | 125-SB-500; 125-CPT-002 | 8.8 | 21.8 | 25.5 | 2.4 | 1.5 | 0.0 | 9.8 | 1.6 | 0.8 | 16.1 | **25.5** | **16.7** | **3.8** | **86%** | **5.0** | 0.2 | 2.2 | **2.4** |
| S_HS-21 | 124-SB-500; 124-SB-503; 124-CPT-001 | 9.7 | 13.8 | 16.0 | 1.3 | 0.4 | 0.0 | 3.6 | 0.4 | 0.3 | 6.0 | **16.0** | **6.3** | **2.3** | **71%** | **2.4** | 0.2 | 2.0 | **2.2** |
| S_HS-22 | 124-SB-501; 124-CPT-002; 124-CPT-001; 124-SB-500 | 9.9 | 10.0 | 11.5 | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.2 | **11.5** | **1.6** | **1.5** | **9%** | **0.0** | 0.1 | 1.7 | **1.8** |

Prepared By/Date: NDL/03-18-14

Checked By/Date: TCC/03-20-14

**Attachment 3S-2**

**April 24, 2015 Mueser Rutledge Correspondence re:**
**SA-6 South Surcharge Monitoring, Jersey City, NJ**

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

April 24, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 3S Surcharge Review
SA-6 South
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of March 30, 2015 AMEC settlement and piezometer monitoring data for Area 3S is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated between March 24-13, 2015 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken on March 19, 2015. Calculated post-surcharge effective stresses are presented in Table 1. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 3S monitoring locations have met the surcharge program goal as of 03/30/2015.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

MP:F:\111\11173\2014 Surcharge Removal Review\SA-6_Area 3S\MRCE Review-Area 3S-April15.docx

Table 1. MRCE SA-6 South Surcharge Monitoring Review for Area 3S (April 2015)

| Settlement Monitoring Point | Layer | Existing EL. (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| S_FS-06 | Top D | -2.7 | 1365.0 | 2031.3 | 3/19/2015 | 3/24/2015 | 14.3 | 6.6 | 3148.8 | 574.1 | 2574.7 | 127% | - |
| | Center D | -3.9 | 1620.0 | 2099.1 | | | 14.3 | 7.2 | 3403.8 | 693.3 | 2710.5 | 129% | 127% |
| | Bottom D | -5.2 | 1875.0 | 2166.9 | | | 14.3 | 9.6 | 3658.8 | 919.8 | 2739.0 | 126% | - |
| S_FS-07 | Center O | -0.8 | 1234.0 | 2256.5 | 3/19/2015 | 3/24/2015 | 16.9 | 4.8 | 3346.5 | 348.9 | 2997.6 | 133% | - |
| | Top D | -3.0 | 1388.0 | 2323.2 | | | 16.9 | 5.2 | 3500.5 | 510.7 | 2989.8 | 129% | - |
| | Center D | -4.3 | 1587.8 | 2376.3 | | | 16.9 | 11.8 | 3700.3 | 999.5 | 2700.8 | 114% | 113% |
| | Bottom D | -5.5 | 1787.5 | 2429.4 | | | 16.9 | 6.9 | 3900.0 | 775.1 | 3124.9 | 129% | - |
| | RC | -34.3 | 5220.0 | 4145.9 | | | 16.9 | 3.4 | 7332.5 | 2352.4 | 4980.1 | 120% | - |
| S_HS-16 | Center O | -0.6 | 1222.5 | 2420.6 | 3/19/2015 | 3/24/2015 | 18.0 | 5.3 | 3472.5 | 368.2 | 3104.3 | 128% | - |
| | Center D | -4.1 | 1551.5 | 2521.8 | | | 18.0 | 14.7 | 3801.5 | 1173.1 | 2628.4 | 104% | 104% |
| S_HS-17 | Center D | -3.8 | 1460.0 | 1750.9 | 3/19/2015 | 3/24/2015 | 10.3 | 7.4 | 2743.8 | 697.6 | 2046.1 | 117% | 117% |
| S_HS-18 | Center D | -2.5 | 1406.0 | 969.9 | 3/19/2015 | 3/24/2015 | 3.5 | 3.6 | 1841.0 | 382.5 | 1458.5 | 150% | 150% |
| S_HS-19 | Center D | -0.6 | 1207.5 | 844.5 | 3/19/2015 | 3/24/2015 | 3.0 | 4.9 | 1578.8 | 345.1 | 1233.7 | 146% | 143% |
| S_HS-20 | Center O | -1.2 | 1209.5 | 2392.7 | 3/19/2015 | 3/24/2015 | 15.1 | 5.3 | 3093.3 | 403.7 | 2689.5 | 112% | - |
| | Center D | -4.4 | 1494.3 | 2484.0 | | 3/13/2015 | 15.1 | 9.7 | 3378.0 | 878.6 | 2499.4 | 101% | 101% |
| S_HS-21 | Center D | -4.3 | 1581.5 | 1503.7 | 3/19/2015 | 3/24/2015 | 6.1 | 1.6 | 2339.0 | 367.5 | 1971.5 | 131% | 132% |
| S_HS-22 | Center D | -2.6 | 1436.8 | 966.3 | 3/19/2015 | 3/24/2015 | 1.7 | 4.6 | 1651.8 | 450.5 | 1201.2 | 124% | 124% |

# *B&B Drilling. Inc.*

**PO Box 8**
**Netcong, New Jersey 07857**

**PH 973 347-2250**
**FX 973 347-3864**
**www.hrsdrilling.com**


April 26, 2016

Amec Foster Wheeler E&I, Inc.
200 American Metro Boulevard
Hamilton, New Jersey 08619

Attention: Eric Christodoulatos


Reference: Settlement Platform Decommissioning
Honeywell Site, Jersey City, New Jersey

Dear Eric,

B&B Drilling, Inc. (B&B) decommissioned settlement platforms at the north and south surcharge areas. Although settlement platforms were not NJDEP-permitted wells they were decommissioned in accordance with the NJDEP regulations for well abandonment (N.J.A.C. 7:9D-3.1). The only difference is that no formal decommissioning report submission to NJDEP was required.

Settlement platforms were constructed with a 1-inch galvanized steel casing inside a 4-inch PVC casing. A portion of the annular space between the 1 and 4-inch pipes was filled with bentonite when originally constructed. The decommissioning consisted of pressure tremie grouting both the 1-inch inner casing and the remaining open annular space in the 4-inch casings at each settlement platform.

Yours truly,



Andrew Wadden
Operations Manager

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316729**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 200 KELLOGG ST

Address: 200 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601515 Northing (Y): 685624
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** VI-1

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** INCLINOMETER

Other Use(s):

Diameter (in.): 3.34

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 45

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
LATION
DETAIL 11-
11- 2013.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316729**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316730**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 200 KELLOGG ST

Address: 200 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601462 Northing (Y): 685580
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** VI-2

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** INCLINOMETER

Other Use(s):

Diameter (in.): 3.34

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 45

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
LATION
DETAIL 11-
11- 2013.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316730**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316729**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 200 KELLOGG ST

Address: 200 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601515 Northing (Y): 685624
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** April 15, 2013

**DATE WELL COMPLETED:** April 16, 2013

**WELL USE:** INCLINOMETER

**Other Use(s):**

**Local ID:** VI-1

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 40 Finished Well Depth (ft.): 40 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 40 | 6 | | |
| Casing | 0 | 40 | 3.34 | PVC | Inclinometer Casing |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 30 | 6 | 3.34 | 18 | 82 | 18 |
| Grout | 30 | 40 | 6 | 3.34 | 8 | 140 | 8 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: m-scope/measured in adjacent well
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 12 - 16: BRN SM - Silty sands, sand-silt mixtures |
| 16 - 20: BRN-BLK PT - Peat, muck, and other highly organic soils |
| 20 - 28.5: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 28.5 - 40: RED - BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |

**ADDITIONAL INFORMATION:** Well installed in compliance with approved NJDEP Deviations.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316730**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 200 KELLOGG ST

Address: 200 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 1 Block: 24601

Easting (X): 601462 Northing (Y): 685580
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** April 18, 2014

**DATE WELL COMPLETED:** April 22, 2014

**WELL USE:** INCLINOMETER

**Other Use(s):**

**Local ID:** VI-2

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 65 Finished Well Depth (ft.): 65 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 65 | 6 | | |
| Casing | 0 | 65 | 3.34 | PVC | Inclinometer Casing |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 55 | 6 | 3.34 | 42 | 135 | 30 |
| Grout | 55 | 65 | 6 | 3.34 | 8 | 142 | 8 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: M-Scope
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid: Bentonite
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 12 - 17: BRN SM - Silty sands, sand-silt mixtures |
| 17 - 20: BLK-BRN PT - Peat, muck, and other highly organic soils |
| 20 - 29: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 29 - 46: RED-BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 46 - 55: RED-BRN CL - Inorganic clays of low to medium plasticity, gravelly/sandy/silty/lean clays |
| 55 - 65: RED BRN CH - Inorganic clays or high plasticity, fat clays |

**ADDITIONAL INFORMATION:** Well installed in compliance with approved NJDEP Deviations.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314998**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Sudy Area 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602920 Northing (Y): 684544
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 3, 2016

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-6

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 27

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 27 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 3 | 0 | 0 | 110 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314999**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Sudy Area 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602756 Northing (Y): 684631
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 3, 2016

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-7

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 27

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 27 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 3 | 0 | 0 | 110 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316716**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602166 Northing (Y): 685148
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 3, 2016

**WELL USE:** EXTENSOMETER REPLACEMENT

**Other Use(s):**

**Local ID:** SD-3

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 27

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 27 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 3 | 0 | 0 | 110 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316717**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602186 Northing (Y): 685010
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 3, 2016

**WELL USE:** EXTENSOMETER REPLACEMENT

**Other Use(s):**

**Local ID:** SD-4

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 28

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 28 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 28 | 3 | 0 | 0 | 112 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316718**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 80 KELLOGG ST

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602554 Northing (Y): 684734
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 3, 2016

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-5

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 27

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 27 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 3 | 0 | 0 | 110 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316722**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601916 Northing (Y): 685280
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 2, 2016

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-1

Reason for Decommissioning: New Well Drilled/Replaced

Finished Well Depth (ft.): 27

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 27 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 3 | 0 | 0 | 110 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316723**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601757 Northing (Y): 685325
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 3, 2016

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-2

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 27

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 27 | 3 | PVC | sondex casing |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 3 | 0 | 0 | 110 | 6 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314998**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Sudy Area 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602942 Northing (Y): 684556
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-6

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER

Other Use(s):

Diameter (in.): 3

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 35

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
Sondex Figure A2.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

**Approval Date:** October 17, 2013
**Expiration Date:** October 17, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314998**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | Please see attachments. |
| Unusual Conditions: | Please see attachments. |
| Reason for Deviation: | Please see attachments. |
| Proposed Well Construction | Please see attachments. |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314999**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348
**Permit Issued to:** B & B DRILLING INC
**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC
Organization: BAYFRONT REDEVELOPMENT, LLC
Address: 101 COLUMBIA ROAD
City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Sudy Area 6 South
Address: 427 Route 440
County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 603933 Northing (Y): 684562
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-7

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER
Other Use(s):
Diameter (in.): 3
Regulatory Program Requiring Wells/Borings:
Depth (ft.): 35
Case ID Number:
Pump Capacity (gpm): 0
Deviation Requested: Y
Drilling Method: Mud Rotary
Attachments: DEVIATION REQUEST 10-10-13.pdf
Sondex Figure A2.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

**Approval Date:** October 17, 2013
**Expiration Date:** October 17, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314999**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | Please see Attachments. |
| Unusual Conditions: | Please see Attachments. |
| Reason for Deviation: | Please see Attachments. |
| Proposed Well Construction | Please see Attachments. |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316716**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602186 Northing (Y): 685147
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-3

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER REPLACEMENT

Other Use(s):

Diameter (in.): 3

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 35

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
Sondex
Figure A2.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 14, 2013
**Expiration Date:** November 14, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316716**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316717**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602180 Northing (Y): 685000
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-4

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER REPLACEMENT

Other Use(s):

Diameter (in.): 3

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 35

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
Sondex
Figure A2.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316717**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316718**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 80 KELLOGG ST

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602531 Northing (Y): 684747
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-5

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER

Other Use(s):

Diameter (in.): 3

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 35

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
sondex
settlement
system.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316718**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316722**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601927 Northing (Y): 685276
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-1

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER

Other Use(s):

Diameter (in.): 3

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 35

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
sondex settlement system.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 14, 2013
**Expiration Date:** November 14, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316722**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316723**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601749 Northing (Y): 685324
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** SD-2

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** EXTENSOMETER

Other Use(s):

Diameter (in.): 3

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 35

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
sondex settlement system.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 14, 2013
**Expiration Date:** November 14, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316723**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | PLEASE SEE ATTACHED |
| Unusual Conditions: | PLEASE SEE ATTACHED |
| Reason for Deviation: | PLEASE SEE ATTACHED |
| Proposed Well Construction | PLEASE SEE ATTACHED |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314998**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Sudy Area 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602920 Northing (Y): 684544
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 6, 2013

**DATE WELL COMPLETED:** November 7, 2013

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-6

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 27 Finished Well Depth (ft.): 27 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 27 | 4.5 | | |
| Casing | 0 | 27 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 4.5 | 3 | 8 | 150 | 8.5 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: M-SCOPE/IN ADJACENT WELL
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 10.5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 10.5 - 17.5: DRK BRN PT - Peat, muck, and other highly organic soils |
| 17.5 - 18: GRAY SM - Silty sands, sand-silt mixtures |
| 18 - 22: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 22 - 27: RED-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:** Well was constructed in compliance with an approved NJDEP Deviation.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314999**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Sudy Area 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602756 Northing (Y): 684631
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 4, 2013

**DATE WELL COMPLETED:** November 5, 2013

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-7

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 27 Finished Well Depth (ft.): 27 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 27 | 4.5 | | |
| Casing | 0 | 27 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 4.5 | 3 | 8 | 150 | 8.5 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 8 ft. below land surface
Water Level Measure Tool: M-SCOPE/ADJACENT WELL
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 10: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 10 - 17: BRN-BLK PT - Peat, muck, and other highly organic soils |
| 17 - 22: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 22 - 27: RED-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:** Well was constructed in compliance with an approved NJDEP Deviation.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316716**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602166 Northing (Y): 685148
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 27, 2013

**DATE WELL COMPLETED:** December 2, 2013

**WELL USE:** EXTENSOMETER REPLACEMENT

**Other Use(s):**

**Local ID:** SD-3

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 27 Finished Well Depth (ft.): 27 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 27 | 4.5 | | |
| Casing | 0 | 27 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 4.5 | 3 | 8 | 150 | 8.5 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 13 ft. below land surface
Water Level Measure Tool: M-SCOPE/ADJACENT WELL
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 6: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 6 - 8.5: DRK GRAY SP - Poorly graded sands and gravelly sands, little or no fines FILL |
| 8.5 - 13: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 13 - 17.5: GRAY-BLK PT - Peat, muck, and other highly organic soils |
| 175 - 27: BRN SP - Poorly graded sands and gravelly sands, little or no fines |

**ADDITIONAL INFORMATION:** Well was constructed in compliance with an approved NJDEP Deviation.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316717**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602186 Northing (Y): 685010
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 22, 2013

**DATE WELL COMPLETED:** November 22, 2013

**WELL USE:** EXTENSOMETER REPLACEMENT

**Other Use(s):**

**Local ID:** SD-4

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 28 Finished Well Depth (ft.): 28 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 28 | 4.5 | | |
| Casing | 0 | 28 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 28 | 4.5 | 3 | 8 | 150 | 8.5 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: M-Scope/Adjacent Piezometer
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Gus Pech
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 6: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 6 - 18: GRAY SM - Silty sands, sand-silt mixtures |
| 18 - 19: BLK PT - Peat, muck, and other highly organic soils |
| 19 - 28: RED-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:** Please see Permit for Deviations.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316718**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 80 KELLOGG ST

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602554 Northing (Y): 684734
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 15, 2013

**DATE WELL COMPLETED:** November 15, 2013

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-5

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 27 Finished Well Depth (ft.): 27 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 27 | 4.5 | | |
| Casing | 0 | 27 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 4.5 | 3 | 7.75 | 150 | 8 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 8 ft. below land surface
Water Level Measure Tool: M-SCOPE I ADJACENT PIEZOMETER
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:

Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 6: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 6 - 17: GRAY SW - Well-graded sands and gravelly sands, little or no fines |
| 17 - 18: BLK OL - Organic silts and organic silty clays of low plasticity |
| 18 - 27: RED-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:** Please see Permit for Deviations.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316722**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601916 Northing (Y): 685280
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** December 18, 2013

**DATE WELL COMPLETED:** December 19, 2013

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-1

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 27 Finished Well Depth (ft.): 27 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 27 | 4.5 | | |
| Casing | 0 | 27 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 4.5 | 3 | 8 | 150 | 8.5 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 7 ft. below land surface
Water Level Measure Tool: M-Scope/Adfjacwnt Piezometer
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 7.5: BLK GP - Poorly graded gravels and gravel-sand mixtures, little or no fines FILL |
| 7.5 - 8: BRN-PINK MH - Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts COPR |
| 8 - 10: BRN-BLK ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 10 - 11.5: BRN MH - Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts COPR |
| 11.5 - 12: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 12 - 16.5: BRN PT - Peat, muck, and other highly organic soils |
| 16.5 - 18: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 18 - 27: RED-BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:** Well constructed in compliance with NJDEP approved Deviations.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316723**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601757 Northing (Y): 685325
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 27, 2013

**DATE WELL COMPLETED:** November 28, 2013

**WELL USE:** EXTENSOMETER

**Other Use(s):**

**Local ID:** SD-2

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 27 Finished Well Depth (ft.): 27 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 27 | 4.5 | | |
| Casing | 0 | 27 | 3 | PVC | SONDEX CASING |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 27 | 4.5 | 3 | 8 | 150 | 8.5 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 8 ft. below land surface
Water Level Measure Tool: m-scope/ in adjacent piezometer
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: Mobil B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 8: BRN GP - Poorly graded gravels and gravel-sand mixtures, little or no fines FILL |
| 8 - 12: BRN-GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 12 - 15.5: BRN ML - Inorganic silts, very fine sands, rock four, silty or clayey fine sands |
| 15.5 - 20: BRN PT - Peat, muck, and other highly organic soils |
| 20 - 27: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |

**ADDITIONAL INFORMATION:** Well was constructed in compliance with an approved NJDEP Deviation.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315003**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Sudy Area - 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 10 Block: 24601

Easting (X): 602944 Northing (Y): 685544
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 2, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-6

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 11

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 6 | 1 | PVC | sch 40 |
| Screen | 6 | 11 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 11 | 1 | 0 | 0 | 5 | 0.25 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315004**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Study Area - 6 South

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602745 Northing (Y): 684633
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 2, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-7

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 11.5

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 6.5 | 1 | PVC | sch 40 |
| Screen | 6.5 | 11.5 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 11.5 | 1 | 0 | 0 | 5 | 0.25 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316719**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602172 Northing (Y): 685138
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 2, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-3

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 12

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 7 | 1 | PVC | sch 40 |
| Screen | 7 | 12 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 12 | 1 | 0 | 0 | 6 | 0.33 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316720**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602174 Northing (Y): 685007
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 2, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-4

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 10

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 5 | 1 | PVC | sch 40 |
| Screen | 5 | 10 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 10 | 1 | 0 | 0 | 4.5 | 0.25 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316721**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 80 LELLOGG ST

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602560 Northing (Y): 684733
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 2, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-5

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 6

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 3 | 1 | PVC | sch 40 |
| Screen | 3 | 6 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 6 | 1 | 0 | 0 | 3 | 0.15 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316724**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601916 Northing (Y): 685280
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 1, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-1

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 8 | 1 | PVC | sch 40 |
| Screen | 8 | 13 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 1 | 0 | 0 | 6 | 0.33 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316725**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601752 Northing (Y): 685330
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 1, 2016

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-2

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 13

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 8 | 1 | PVC | sch 40 |
| Screen | 8 | 13 | 1 | PVC | 0.010" |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 13 | 1 | 0 | 0 | 6 | 0.33 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315003**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Sudy Area - 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602942 Northing (Y): 684551
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-6

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** October 16, 2013
**Expiration Date:** October 16, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315003**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315004**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Study Area - 6 South

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602754 Northing (Y): 684635
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-7

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** October 22, 2013
**Expiration Date:** October 22, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315004**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316719**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602188 Northing (Y): 685147
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-3

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316719**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316720**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602180 Northing (Y): 685000
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-4

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316720**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316721**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 80 LELLOGG ST

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602531 Northing (Y): 684747
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-5

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316721**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316724**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601927 Northing (Y): 685276
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-1

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316724**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316725**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601749 Northing (Y): 685324
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** STP-2

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** PIEZOMETER

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 20

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: N

Drilling Method: Hollow Stem Augers

Attachments:

**SPECIFIC CONDITIONS/REQUIREMENTS**

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

**Approval Date:** November 12, 2013
**Expiration Date:** November 12, 2014

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316725**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | |
| Unusual Conditions: | |
| Reason for Deviation: | |
| Proposed Well Construction | |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315003**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Sudy Area - 6 South

Address: 427 Route 440

County: Hudson Municipality: Jersey City Lot: 8 Block: 24601

Easting (X): 602944 Northing (Y): 685544
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** October 31, 2013

**DATE WELL COMPLETED:** October 31, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-6

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 11 Finished Well Depth (ft.): 11 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 11 | 6 | | |
| Casing | 0 | 6 | 1 | PVC | SH40 |
| Screen | 6 | 11 | 1 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 5 | 6 | 1 | 0 | 94 | 5.4 |
| Gravel Pack | 5 | 11 | 6 | 1 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 9 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 11: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: H. Robert Seybold, JOURNEYMAN LICENSE # 0001348 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201315004**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Study Area - 6 South

Address: 60 Kellogg St

County: Hudson Municipality: Jersey City Lot: 7 Block: 24601

Easting (X): 602745 Northing (Y): 684633
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** October 31, 2013

**DATE WELL COMPLETED:** October 31, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-7

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 11.5 Finished Well Depth (ft.): 11.5 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 11.5 | 6 | | |
| Casing | 0 | 6.5 | 1 | PVC | SH40 |
| Screen | 6.5 | 11.5 | 1 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 5.5 | 6 | 1 | 0 | 94 | 5.4 |
| Gravel Pack | 5.5 | 11.5 | 6 | 1 | MORIE#1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 9 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 11.5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316719**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602172 Northing (Y): 685138
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 27, 2013

**DATE WELL COMPLETED:** November 27, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-3

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 12 Finished Well Depth (ft.): 12 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 12 | 6 | | |
| Casing | 0 | 7 | 1 | PVC | SH40 |
| Screen | 7 | 12 | 1 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 6 | 6 | 1 | 0 | 94 | 5.4 |
| Gravel Pack | 6 | 12 | 6 | 1 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 8 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 12: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316720**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 100 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 5 Block: 24601

Easting (X): 602174 Northing (Y): 685007
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 22, 2013

**DATE WELL COMPLETED:** November 22, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-4

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 10 Finished Well Depth (ft.): 10 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 10 | 6 | | |
| Casing | 0 | 5 | 1 | PVC | SH40 |
| Screen | 5 | 10 | 1 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 4 | 6 | 1 | 0 | 62 | 3.5 |
| Gravel Pack | 4 | 10 | 6 | 1 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: GUS PECH
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 5: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 5 - 10: GRAY SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316721**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 80 LELLOGG ST

Address: 80 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 6 Block: 24601

Easting (X): 602560 Northing (Y): 684733
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 18, 2013

**DATE WELL COMPLETED:** November 18, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-5

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 6 Finished Well Depth (ft.): 6 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 6 | 6 | | |
| Casing | 0 | 3 | 1 | PVC | SH40 |
| Screen | 3 | 6 | 1 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 3 | 6 | 1 | 0 | 40 | 2 |
| Gravel Pack | 3 | 6 | 6 | 1 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 5 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 6: GRAY SM - Silty sands, sand-silt mixtures

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316724**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601916 Northing (Y): 685280
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** December 19, 2013

**DATE WELL COMPLETED:** December 19, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-1

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 13 Finished Well Depth (ft.): 13 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 13 | 6 | | |
| Casing | 0 | 8 | 1 | PVC | SH40 |
| Screen | 8 | 13 | 1 | PVC | 0.010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 7 | 6 | 1 | 0 | 94 | 5.6 |
| Gravel Pack | 7 | 13 | 6 | 1 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 13: BRN-BLK SM - Silty sands, sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201316725**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** 100 KELLOGG ST

Address: 130 KELLOGG ST

County: Hudson Municipality: Jersey City Lot: 3 Block: 24601

Easting (X): 601752 Northing (Y): 685330
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** November 28, 2013

**DATE WELL COMPLETED:** November 28, 2013

**WELL USE:** PIEZOMETER

**Other Use(s):**

**Local ID:** STP-2

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 13 Finished Well Depth (ft.): 13 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 13 | 6 | | |
| Casing | 0 | 8 | 1 | PVC | SH40 |
| Screen | 8 | 13 | 1 | PVC | 0010" |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 7 | 6 | 1 | 0 | 94 | 5.6 |
| Gravel Pack | 7 | 13 | 6 | 1 | MORIE #1 | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Hollow Stem Augers

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 7 ft. below land surface
Water Level Measure Tool: M-SCOPE
Well Development Period: 1 hrs.
Method of Development: AIR LIFT
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

**GEOLOGIC LOG**

0 - 13: BNR-BLK GM - Silty gravels, gravel-sand-silt mixtures FILL

**ADDITIONAL INFORMATION:**

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314518**

# WELL DECOMMISSIONING REPORT

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT C/O THOMPSON REU

Company/Organization: Bayfront Redevelopment

Address: PO Box 4900 Dept 356 Scotsdale, Arizona 85261

**WELL LOCATION:** Study Area 6 South

Address: Kekkogg Street & St. Hwy 440

County: Hudson Municipality: Jersey City Lot: 1 through 8 Block: 24601

Easting (X): 601600 Northing (Y): 685400
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL DECOMMISSIONED:** March 1, 2016

**WELL USE:** VIBRATING WIRE PIEZOMETER/SITEWIDE

**Other Use(s):**

**Local ID:** VWP - 1

Reason for Decommissioning: No longer in use

Finished Well Depth (ft.): 80

Was a New Well Drilled? N

Formation Type: Unconsolidated

New Well Permit Number:

**WELL DECOMMISSIONING INFORMATION**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | | | | | |
| Casing | 0 | 0 | 0 | Other | none installed |
| Screen | | | | | |

**MATERIALS USED**

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Sand/Gravel | | | | | | | |

**ADDITIONAL INFORMATION**

Obstructions: No

Authorization Official:

Obstruction Type:

Authorization Number:

Alternative Decomm. Method? No

Authorization Date:

Method Used

ATTACHMENTS:

Warren Blewett
JOURNEYMAN
Sealing Driller: LICENSE # 0014578

B & B DRILLING INC
BOX 8 RT 206
Company: Netcong (Morris), NJ 07857

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-03 PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314518**

# WELL PERMIT

The New Jersey Department of Environmental Protection grants this permit in accordance with your application, attachments accompanying same application, and applicable laws and regulations. This permit is also subject to further conditions and stipulations enumerated in the supporting documents which are agreed to by the permittee upon acceptance of the permit

**Certifying Driller:** H. ROBERT SEYBOLD, JOURNEYMAN LICENSE # 0001348

**Permit Issued to:** B & B DRILLING INC

**Company Address:** BOX 8 RT 206 NETCONG, NJ 07857

**PROPERTY OWNER**

Name: BAYFRONT REDEVELOPMENT, LLC

Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD

City: Morristown State: New Jersey Zip Code: 07962

**PROPOSED WELL LOCATION**

Facility Name: Study Area 6 South

Address: Kekkogg Street & St. Hwy 440

County: Hudson Municipality: Jersey City Lot: 1 through 8 Block: 24601

Easting (X): 602400 Northing (Y): 684750
Coordinate System: NJ State Plane (NAD83) - USFEET

**Local ID:** VWP - 1

**SITE CHARACTERISTICS**

**PROPOSED CONSTRUCTION**

**WELL USE:** VIBRATING WIRE PIEZOMETER/SITEWIDE

Other Use(s):

Diameter (in.): 1

Regulatory Program Requiring Wells/Borings:

Depth (ft.): 50

Case ID Number:

Pump Capacity (gpm): 0

Deviation Requested: Y

Drilling Method: Mud Rotary

Attachments: DEVIATION REQUEST 10-10-13.pdf
llation Detail 08-27-2011.pdf

**SPECIFIC CONDITIONS/REQUIREMENTS**

Well must be built in accordance with submitted deviation [N.J.A.C. 7.9D-2.8]

**Approval Date:** October 10, 2013
**Expiration Date:** October 10, 2014

Approved by the authority of:
Bob Martin
Commissioner

Terry D. Pilawski

Terry Pilawski, Chief
Bureau of Water Allocation and Well Permitting

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Wells
PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314518**

# WELL PERMIT

| DEVIATION INFORMATION | |
|---|---|
| Purpose: | Please see attached Engineer's Design Documentation. |
| Unusual Conditions: | Please see attached Engineer's Design Documentation. |
| Reason for Deviation: | Please see attached Engineer's Design Documentation. |
| Proposed Well Construction | Please see attached Engineer's Design Documentation. |

| GENERAL CONDITIONS/REQUIREMENTS |
|---|
| A copy of this permit shall be kept at the worksite / on the property and shall be exhibited upon request. [N.J.A.C. 7:9D-1] |
| A well record must be submitted by the well driller to the Bureau of Water Systems and Well Permitting. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the well record shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Record: within ninety (90) days after the well is completed.[N.J.A.C. 7:9D-1] |
| All well drilling/pump installation activities shall comply with N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| For this permit to remain valid, the well approved in this permit shall be constructed within one year of the effective date of the permit. [N.J.A.C. 7:9D-1] |
| If the pump capacity applied for is less than 70 gpm, no subsequent increase to 70 gpm or more shall be made without prior approval of the Bureau of Water Systems and Well Permitting. [N.J.A.C. 7:9D-1] |
| If the use of the well is to be changed a well permit for the proposed use of the well shall be submitted for review and approval. [N.J.A.C. 7:9D-1] |
| If you or a future property owner intend to redesignate this well as a Category 1 well (domestic, non-public, community water supply or public non-community water supply wells), the well must be constructed as a Category 1 well per the Well Construction and Abandonment Regulations at N.J.A.C. 7:0D-1.1 et seq. In addition, if the current or future property owner intends to have this well redesignated as a community water supply well, the well must be constructed by a Master well driller, which would include having a Master well driller on-site at all times during construction of the well, as specified in the Well Construction and Abandonment Regulations. Otherwise, the New Jersey Department of Environmental Protection will not allow the well to be redesignated, and a new well would have to be installed. [N.J.A.C. 7:9D-1.7((a))1i] |
| In accepting this permit the Property Owner and Driller agree to abide by the following terms and conditions [N.J.A.C. 7:9D-1] |
| In the event that this well is not constructed the well driller shall notify the Bureau of Water Systems and Well Permitting of the permit cancellation. Unless prior written approval is obtained from the Bureau of Water Systems and Well Permitting the Cancellation notification shall be submitted electronically through the New Jersey Department of Environmental Protection's Regulatory Services Portal Submit Well Permit Cancellation : by the expiration date of this permit.[N.J.A.C. 7:9D-1] |
| In the event this well is abandoned, the Owner or Well driller shall assume full responsibility for having the well decommissioned in a manner satisfactory to the New Jersey Department of Environmental Protection in accordance with the provisions of N.J.A.C. 7:9D-1 et seq. [N.J.A.C. 7:9D-1] |
| The granting of this permit shall not be construed in any way to affect the title or ownership of property, and shall not make the New Jersey Department of Environmental Protection or the State a party in any suit or question of ownership of property. [N.J.A.C. 7:9D-1] |
| The issuance of this permit shall not be deemed to affect in any way action by the New Jersey Department of Environmental Protection on any future application. [N.J.A.C. 7:9D-1] |
| This permit conveys no rights, either expressed, or implied to divert water. [N.J.A.C. 7:9D-1] |
| This permit does not waive the obtaining of Federal or other State or local Government consent when necessary. This permit is not valid and no work shall be undertaken until such time as all other required approvals and permits have been obtained. [N.J.A.C. 7:9D-1] |
| This permit is NONTRANSFERABLE [N.J.A.C. 7:9D] |
| This well shall not be used for the supply of potable / drinking water. [N.J.A.C. 7:9D-1] |

New Jersey State Department of Environmental Protection
Bureau of Water Allocation and Well Permitting
Mail Code 401-04Q PO BOX 420 Trenton, NJ 08625-0420 Tel: 609-984-6831

Well Permit Number
**E201314518**

# MONITORING WELL RECORD

**PROPERTY OWNER:** BAYFRONT REDEVELOPMENT, LLC

Company/Organization: BAYFRONT REDEVELOPMENT, LLC

Address: 101 COLUMBIA ROAD Morristown, New Jersey 07962

**WELL LOCATION:** Study Area 6 South

Address: Kekkogg Street & St. Hwy 440

County: Hudson Municipality: Jersey City Lot: 1 through 8 Block: 24601

Easting (X): 601600 Northing (Y): 685400
Coordinate System: NJ State Plane (NAD83) - USFEET

**DATE WELL STARTED:** October 31, 2013

**DATE WELL COMPLETED:** June 12, 2014

**WELL USE:** VIBRATING WIRE PIEZOMETER/SITEWIDE

**Other Use(s):**

**Local ID:** VWP - 1

**WELL CONSTRUCTION**

Total Depth Drilled (ft.): 80 Finished Well Depth (ft.): 80 Well Surface: Above Grade

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Diameter (inches) | Material | Wgt/Rating/Screen # Used (lbs/ch no.) |
|---|---|---|---|---|---|
| Borehole | 0 | 80 | 4 | | |
| Casing | 0 | 0 | 0 | Other | none installed |
| Screen | | | | | |

| | Depth to Top (ft.) | Depth to Bottom (ft.) | Outer Diameter (in.) | Inner Diameter (in) | Material | | |
|---|---|---|---|---|---|---|---|
| | | | | | Bentonite (lbs.) | Neat Cement (lbs.) | Water (gal.) |
| Grout | 0 | 80 | 4 | 0 | 0 | 570 | 32 |
| Gravel Pack | | | | | | | |

Grouting Method: Pressure method (Tremie Pipe) Drilling Method: Mud Rotary

**ADDITIONAL INFORMATION**

Protective Casing: Yes
Static Water Level: 10 ft. below land surface
Water Level Measure Tool: Transducers
Well Development Period: 0 hrs.
Method of Development: NA
Pump Type:

Pump Capacity: _ gpm
Total Design Head: _ ft.
Drilling Fluid:
Drill Rig: MOBIL B-61
Health and Safety Plan Submitted? Yes

**ATTACHMENTS:**

| **GEOLOGIC LOG** |
|---|
| 0 - 15: BRN GM - Silty gravels, gravel-sand-silt mixtures FILL |
| 15 - 20: DRK BRN PT - Peat, muck, and other highly organic soils |
| 20 - 45: GRAY SP - Poorly graded sands and gravelly sands, little or no fines |
| 45 - 80: RED BRN SM - Silty sands, sand-silt mixtures |

**ADDITIONAL INFORMATION:** SITE WIDE PERMIT - Wells were constructed in compliance with an approved NJDEP Deviation. Well depths varied between 20' & 80' with each containing a poor pressure transducer in targeted zones.

Driller of Record: Warren Blewett, JOURNEYMAN LICENSE # 0014578 Company: B & B DRILLING INC

# APPENDIX Q

# CAP GEOSYNTHETIC QUALITY ASSURANCE REPORT
# (CD ONLY)

LANGAN

ENGINEERING & ENVIRONMENTAL SERVICES

Technical Excellence
Practical Experience
Client Responsiveness

# Cap Geosynthetic Quality Assurance (QA) Report

## Honeywell SA-6 South

SA-6 South
Jersey City, New Jersey
**Project Number: 100530001**

April 2016

Honeywell





# Cap Geosynthetic Quality Assurance (QA) Report (SA-6 South)

# for

# SA-6 South
# Jersey City, New Jersey

***Prepared For:***

**Honeywell International, Inc.**
**115 Tabor Road**
**Morris Plains, New Jersey 07950**

***Prepared By:***

**Langan Engineering and Environmental Services, Inc.**
**300 Kimball Drive**
**Parsippany, NJ 07054**

**April 2016**
**Langan Project No. 100530001**

LANGAN

# CAP GEOSYNTHETIC QUALITY ASSURANCE (QA) REPORT

***Prepared By:***
**Langan Engineering & Environmental Services, Inc.**
**300 Kimball Drive**
**Parsippany, NJ 07054**

Dan Bosworth
Senior Staff Engineer

Jeffrey Stoicescu, P.E.
Associate
New Jersey Professional Engineer License No. 24GE04504400

LANGAN

# ENGINEER'S CONSTRUCTION CERTIFICATION

I certify that the placement of the SA-6 South geosynthetics was implemented in substantial compliance with the design documents, and that the activities were witnessed by myself, and/or a person under my direct supervision.

Print Name: Jeffrey Stoicescu, P.E. Title: Senior Associate

Signature:  Date: 4/28/16

# TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 1**

**2.0 SA-6 SOUTH CAP CONSTRUCTION AND DOCUMENTATION ..... 2**

2.1 General ..... 2

2.2 Survey Control / Subgrade Elevations ..... 2

2.3 Soil Subgrade Preparation ..... 3

2.4 SA-6 South Cap Components ..... 4

*2.4.1 Geotextiles* ..... 4

*2.4.2 Geocomposite Venting Layer (GVL)* ..... 6

*2.4.3 Geosynthetic Clay Liner (GCL)* ..... 8

2.4.3.1 Bentonite Sand Plug ..... 9

2.4.3.2 GCL to Barrier Wall Connection Details ..... 10

2.4.4 60-mil Low Linear Density Polyethylene (LLDPE) Geomembrane ..... 10

2.4.4.1 Trial Weld Logs ..... 12

2.4.4.2 Non-Destructive Testing Results ..... 12

2.4.4.3 Destructive Testing Results ..... 13

2.4.4.4 Repair Reports ..... 15

2.4.4.5 Geomembrane Penetrations & Pipe Boot Installation ..... 16

*2.4.4.5.1 Monitoring Wells* ..... 17

*2.4.4.5.2 Gas Vents* ..... 17

*2.4.4.5.3 Piezometers* ..... 17

*2.4.4.5.4 Pump Station and Access Manholes* ..... 17

2.4.5 Geocomposite Drainage Layer (GDL) ..... 17

2.4.6 Non-Compliance Issues ..... 18

**3.0 DECLARATIONS ..... 20**

3.1 General ..... 20

3.2 Limitations ..... 20


## TABLES


Table 1 LLDPE Geomembrane Seam Property Requirements

Table 2 Summary of ESI / Langan QA Testing - Extrusion Welds


## FIGURES


Figure 1 Typical Soil Subgrade Approved for Geomembrane Placement

Figure 2 16 oz. Geotextile Placed Over HB Wall (southern end of SA-6 South)

Figure 3 16 oz. Geotextile / GVL Over SCB Wall (northern end of SA-6 South)

Figure 4 Typical Placement of GVL & Joining of the Net with Plastic Fasteners

Figure 5 Typical Sewing of GVL (for top layer of geotextile)

Figure 6 ESI Securing GCL with Staples

Figure 7 ESI Placing Granular Bentonite along GCL Seams

Figure 8 Typical Construction of Bentonite Sand Plug along HB Wall

Figure 9 Typical Construction of a Geomembrane Pipe Boot

Figure 10 ESI Conducting Sewing of Geotextile (GDL)

## APPENDICES


| | |
|---|---|
| Appendix A | Record Drawings |
| | *A1. GVL / GCL Record Drawing* |
| | *A2. LLDPE Geomembrane Record Drawing* |
| | *A3. GDL Record Drawing* |
| Appendix B | Langan CQA Plan |
| Appendix C | SA-6 South Certificate of Completion |
| Appendix D | Survey Construction Details |
| | *D1. Final Maser Subgrade Tables* |
| | *D2. Subgrade Construction Control Grid* |
| Appendix E | Soil Subgrade Approval |
| | *E1. ESI Certificate of Subgrade Surface Acceptance* |
| | *E2. Langan Certificate of Soil Surface* |
| Appendix F | Langan Daily Reports & Supporting Photo Logs |
| Appendix G | Receiving Inspection Reports (RIRs) |
| Appendix H | GCL to Barrier Wall Connection Logs |
| Appendix I | ESI Panel Placement Logs |
| Appendix J | ESI Trial Weld Logs |
| Appendix K | ESI Seam Control (Non-Destructive) Test Logs |
| Appendix L | ESI Repair Report |
| Appendix M | ESI Destruct Sample Information Logs |
| Appendix N | Laboratory Destruct Test Results |
| Appendix O | Penetration & Pipe Boot Logs |
| Appendix P | Summary of Non-Compliance & Corrective Action Sheets |

## LIST OF ACRONYMS

AO – Add-On
AOC – Area of Concern
BO – Burnout
CF – Custom Fit Repairs
CQA – Construction Quality Assurance
DCB – Design Change Bulletin
DO – Damage By Others
DS – Destruct Sample (Fusion)
DSX – Destruct Sample (Extrusion)
EOR – Engineer of Record
FS – Failed Seam
GCL – Geosynthetic Clay Liner
GDL – Geocomposite Drainage Layer
GVL – Geocomposite Venting Layer
HB – Hydraulic Barrier
IFC – Issued for Construction
LF – Linear Feet
LLDPE – Linear Low-Density Polyethylene
PB – Pipe Boot
PSI – Pounds per Square Inch
RCRA – Resource Conservation & Recovery Act
RFI – Request for Information
RAR – Remedial Action Report
RIR – Receiving Inspection Report
RP - Repair
RW – Roller Wrinkle
SA-6 – Study Area 6
SCB – Soil Cement Bentonite
SI – Subgrade Irregularity
SJ – Seam Joint
QA - Quality Assurance
QA Report – Cap Geosynthetic Quality Assurance Report
QC – Quality Control
WR - Wrinkle

## 1.0 INTRODUCTION

The purpose of this Cap Geosynthetic Quality Assurance Report (QA Report) is to present the observations made, and data collected during the construction of an engineered cap placed within the Study Area 6 (SA-6) South Open Space Area of Concern (AOC) located in Jersey City, New Jersey (Site). The capping activities at SA-6 South included the preparation of the soil subgrade, placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), linear low-density polyethylene (LLDPE) geomembrane, and a geocomposite drainage layer (GDL). Langan Engineering & Environmental Services, Inc. (Langan) was contracted by Honeywell International, Inc. (Honeywell) to provide independent Quality Assurance (QA) for the installation of the geosynthetic components of the cap.

The Chromium Remedy *100% Design* Issued for Construction dated June 2013, (*100% Design*) was prepared by AMEC Foster Wheeler Environment & Infrastructure, Inc. (Amec Foster Wheeler) on behalf of Honeywell, to address chromium contamination at SA-6 South. The *100% Design* required installation of a Resource Conservation and Recovery Act (RCRA) – equivalent geosynthetic cap system, including a venting layer for naturally occurring methane, covering approximately eight acres of the designated Open Space AOC. As part of this QA Report, the Record Drawings, which outline the placement and construction of the various geosynthetic components of the cap, have been provided as *Appendix A*. Other design details discussed herein, including the Issued for Construction (IFC) drawings, geosynthetics specifications, and geosynthetic products approved for this site are incorporated by reference only. Refer to Amec Foster Wheeler documents titled "*100% Design*," dated June 2013, and "*Remedial Action Report (RAR) for Chromium*" for these details.

This QA Report documents the results of the QA Geosynthetic activities conducted during the construction of the cap at SA-6 South by both Langan and Amec Foster Wheeler field personnel. Refer to the Construction Quality Assurance (CQA) Plan prepared by Langan in June 2015 (attached as *Appendix B*) for a description of the scope conducted by Langan, as well as the roles and responsibilities of the owner, Engineer of Record (EOR), earthwork contractor, and liner contractor. Design Change Bulletins (DCBs) and Requests for Information (RFIs) which were generated subsequent to the *100% Design*, and relevant to the QA scope were reviewed and approved by the EOR, and are further summarized in the EOR Closure Report.

This QA Report specifically includes the following documentation of the cap construction activities:

- The Record Drawings;
- Summary of the various phases of the work observed as part of this QA Report;
- Daily Reports indicating the work activities completed each day and other pertinent information;
- Daily cap construction forms submitted by the Geosynthetic Installer which includes: Repair Reports, Trial Weld Logs, Panel Placement Forms, Seam Control Forms, Destructive & Non-Destructive Test Forms, and Subgrade Approval Forms;
- Field testing results for fusion welds and extrusion welds;
- Laboratory testing results for the destructive samples collected (i.e., fusion & extrusion welds);

- Photographs depicting daily work activities and the various phases of the capping activities; and
- Independent QA's certification that the placement of the SA-6 South geosynthetics was implemented in general compliance with the design documents.

This QA Report addresses the cap construction of SA-6 South only. The cap construction at SA-6 North is proposed to commence in the spring of 2016 and will be addressed in a separate QA Report (to be provided upon completion of the SA-6 North cap).

## 2.0 SA-6 SOUTH CAP CONSTRUCTION AND DOCUMENTATION

### 2.1 General

This Section describes the construction methods used and the Quality Control (QC) and QA documentation completed as part of the construction of SA-6 South. This Section also provides the results of the QC and QA testing that was performed during field activities by Langan (QA Engineer), Environmental Specialties International (ESI) as the Geosynthetic Installer, and Entact, LLC (Entact) as the Construction Contractor and QC.

QA activities commenced on July 7, 2015, with Langan conducting observation of the soil subgrade preparation for the western end of SA-6 South (near the Hackensack River). Geocomposite / geotextile placement began on July 20, 2015 and continued until capping activities were completed by November 4, 2015. Relevant observations and QA/QC testing during this timeframe are defined further in this section. A project Certificate of Completion (completed and verified by Entact) certifying that the SA-6 South cap has been constructed and completed in compliance with the project drawings and technical specifications is attached as *Appendix C*.

### 2.2 Survey Control / Subgrade Elevations

Entact subcontracted Maser Consulting, P.A. (Maser), a licensed New Jersey land surveyor, who provided surveying services during the construction of the cap. Maser completed surveying of the cap from the initial subgrade preparation phases to the placement of the geomembrane. Maser surveyed the subgrade elevations of the cap prior to material placement and tabulated the survey results as compared to the design elevations on the construction control grid. These survey activities included:

1. Measurement of elevations of the subgrade surface in accordance with a pre-determined Construction Control Grid. Conformance to the design lines and grades was verified by Amec Foster Wheeler and Entact by comparing the actual elevations with the design elevations on the Construction Control Grid. The accepted subgrade elevations, and corresponding Construction Control Grid for SA-6 South are provided within *Appendix D1* and *Appendix D2*, respectively.
2. Measurement of the as-built conditions including the perimeter or termination of the geomembrane and geotextile over the hydraulic barrier (HB), and Soil Cement Bentonite

(SCB) wall, as well as, the location of the geomembrane repairs, boots / penetrations, and other pertinent information related to the construction of the cap.

3. The subgrade surface was observed to verify uniformity of grade between the construction control grid points.

This survey information is shown on the final Record Drawings attached in *Appendix A.* Amec Foster Wheeler provided QA review and verification of the Maser survey data.

## 2.3 Soil Subgrade Preparation

Soil subgrade preparation was required prior to the placement of the geotextile and the geomembrane in the areas to be capped. Soil subgrade preparation for the cap was completed by Entact using the following procedures:

- Step 1: Entact conducted rough grading of the subgrade surfaces with the use of track-mounted dozers to prepare the appropriate grades and to clear the surface of large objects (i.e. rocks, metals, debris, etc.);
- Step 2: The subgrade surface was fine-graded and compacted in accordance with the project specifications presented in the *100% Design* package. Subgrade sections not meeting survey or compaction requirements were re-worked by Entact until specified conditions were achieved. At the conclusion of this step, Entact provided a certification that the surface met the grading and compaction requirements. The certifications included the Construction Control Grid tabulation prepared by Maser (as defined in *Section 2.2*) and issuance of a Certificate of Subgrade Surface Acceptance as defined in further detail below;
- Step 3: When precipitation was forecast, the prepared subgrade surface was temporarily covered with a polyethylene plastic sheet to protect the soil from overnight precipitation; and
- Step 4: The subgrade surface would be uncovered in approximate 100 ft. sections (moving from west to east across SA-6), followed by extra fine grading conducted by laborers who cleared the surface of extraneous materials greater than ½-inch in diameter, followed by repair and re-compaction of any areas that became inadvertently wetted.

Entact and ESI also conducted their own observation of the subgrade surface to confirm if the surface was acceptable for the placement of the geosynthetic material. Upon notification by Entact that the grading was acceptable, Langan conducted an independent observation to identify that the subgrade was prepared in general accordance with the *100% Design*.

If the soil subgrade surface was deemed acceptable with no additional re-work required, the Langan QA and Entact QC representative signed and submitted an acceptance form for the approved subgrade. The daily QA subgrade approval forms are provided in *Appendix E*, with the ESI Certificate of Subgrade Surface Acceptance forms provided in *Appendix E1*, and the Langan Certificate of Soil Surface provided in *Appendix E2.* In the event the subgrade surface was not

deemed acceptable, Steps 2, 3, and 4 outlined above were repeated until an acceptable subgrade surface was achieved (based on conditions outlined in the Langan Certificate of Soil Surface forms) and confirmed by Langan and Entact.

*Figure 1* below shows a typical section of subgrade approved for geomembrane placement. Additional photos and summaries of the subgrade preparation activities conducted each day are presented in the Daily Reports and Daily Photo Logs provided in *Appendix F.*

**Figure 1 – Typical Soil Subgrade Approved for Geomembrane Placement**



## 2.4 SA-6 South Cap Components

### *2.4.1 Geotextiles*

After approval of various sections of the subgrade surface, a 16 oz. geotextile layer was placed over the HB and SCB barrier walls around the perimeter of the capped area. According to the *100% Design* package, this geotextile layer was designed to protect the 60-mil LLDPE geomembrane from potential puncture damage from the perimeter barriers / walls. The approved 16 oz. non-woven geotextile fabric layer (i.e., defined as SKAPS GE-116 in Amec Foster Wheeler's *EOR Closure Report*) was delivered to the project site, offloaded, and staged onsite by Entact. For each delivery, Amec Foster Wheeler prepared a Receiving Inspection Report (RIR) to document receipt of acceptable materials. The RIRs outlining the date, material, quantity, and other pertinent details of the geotextile rolls delivered to the Site are provided in *Appendix G*.

The 16 oz. geotextile was installed by ESI at locations shown on the Record Drawings. Geotextile was placed along the boundaries of SA-6 South over the HB and SCB wall located along the western, northern, southern, and eastern boundaries of the cap. The 15 ft. wide geotextile panels were placed with approximately 13 ft. inbound of the perimeter of the HB and SCB walls, along with 2 ft. of geotextile extending outbound of the perimeter containment walls.

Geotextile panels were overlapped at least 12-inches and seamed using a dual hot wedge welder that melted the two surfaces together to form a bond (also referred to as leistering). The 16 oz. geotextile was placed along the boundary areas of SA-6 at locations above the Site water table (i.e. locations where geosynthetic clay liner was not required). The geotextile (on the interior of the Cap) overlapped the geocomposite venting layer and was leistered in place following the procedure outlined above. *Figure 2* below shows the 16 oz. geotextile being placed over the HB wall (southern end of SA-6 South cap), and *Figure 3* shows the geotextile overlapping the GVL Note, the GVL roll was placed in a general north to south direction across SA-6, while the 16 oz. geotextile roll was placed in a general east to west direction.

**Figure 2 – 16 oz. Geotextile Placed Over HB Wall (southern end of SA-6 South)**



**Figure 3 – 16 oz. Geotextile / GVL Over SCB Wall (northern end of SA-6 South)**



### *2.4.2 Geocomposite Venting Layer (GVL)*

Prior to placement of the 60-mil LLDPE geomembrane, GVL was placed over the soil subgrade at locations above the water table to serve as a venting layer for naturally occurring methane that may emanate from below the cap.

The approved GVL (i.e., defined as SKAPS TN-220-2-6 in *EOR Closure Report*) consisted of an extruded polyethylene drainage net structure (or geonet) sandwiched between two non-woven geotextile layers. The GVL was delivered to the Site, offloaded, and staged onsite by Entact. The RIRs for the GVL delivered to the Site are provided in *Appendix G*.

The GVL was placed by ESI, over the approved soil subgrade for areas above the Site water table at locations shown on the Record Drawings (*Appendix A1*).

The GVL rolls were typically oriented in a north to south direction. The leading edge of the GVL panels was held in place by sand bags until the subsequent panels could be placed and seamed. The placement strategy for this material was to limit the amount of GVL to be placed in a day, to an area that could also be covered by the LLDPE geomembrane that day. This strategy was used to minimize the risk of the GVL and underlying subgrade from becoming wet during overnight rain events. GVL panels were not placed during precipitation events, in the presence of excessive moisture, or during high winds.

GVL panels were placed according to Section 02380 – Gas Venting System as defined in *100% Design* package. GVL was generally placed with the predominant flow direction towards the edge of the cap with the GVL running parallel to any slopes or elevation changes (i.e. running up/down the slope and not across the slope). For adjacent GVL panels, the following minimum seaming requirements were met:

- Adjacent rolls of GVL were placed so that the geonet overlapped by 2 to 3-inches, and the geotextiles overlapped by at least 4-inches;
- The bottom layer of geotextile (underneath the geonet) was overlapped to ensure that no areas of the soil subgrade were exposed;
- White plastic fasteners were placed at a maximum of every 5 ft. along the seam to connect adjacent pieces of GVL. Additional fasteners were requested by the QA team when the seams extended down slopes or at significant subgrade elevation changes. *Figure 4* below shows placement of the white plastic fasteners; and
- Once the geonet was tied with a sufficient number of fasteners, the top geotextile of the GVL was continuously sewn as shown in *Figure 5* below.

**Figure 4 – Typical Placement of GVL & Joining of the Net with Plastic Fasteners**



**Figure 5 – Typical Sewing of GVL (for top layer of geotextile)**



During placement of the GVL, butt seams, rips, tears, or other damaged areas of the GVL were repaired by exposing an appropriate area of geonet, placing fasteners as defined in the project specifications, and covering the area with a new piece of geotextile which was leistered in-place. Additional details of the GVL placement are further described in the Langan Daily Reports and Photo Logs provided in *Appendix F*.

### *2.4.3 Geosynthetic Clay Liner (GCL)*

The approved GCL consisted of granular sodium bentonite clay sandwiched between, supported, and encapsulated by two geotextiles, and held together by needled punching. The approved GCL (i.e., Cetco Bentomat DN) was delivered to the Site, offloaded, and staged onsite by Entact. The RIRs for the GCL rolls delivered to the Site are provided within *Appendix G*.

The approved GCL was deployed by ESI in accordance with Section 02375 – Geosynthetic Clay Liner as defined in the *100% Design* package. GCL was placed directly over the approved soil subgrade, at locations situated below (to 1 ft. above) the Site water table. These areas generally consisted of: the bottom of utility corridors, the bottom of drainage swales and Site elevation changes, and the eastern end of SA-6 South (where the subgrade is depressed to allow the surface grading to tie in with Route 440). These locations are shown on the Record Drawings.


For areas where the edges of the GCL terminated on a slope, staples were used to secure the GCL in place as shown below in *Figure 6*. The staples were placed along the top 6-inches of the GCL edge and were placed through the GCL and secured into the underlying soil subgrade. The GVL overlapped the edge of the GCL a minimum of 12-inches and was then leistered to the GCL. When staples were used, the GVL was placed over the staples (at least of 1 ft. of overlap), to mitigate the potential of the staples coming in contact with the geomembrane.

**Figure 6 – ESI Securing GCL with Staples**



During placement of the GCL, granular bentonite was placed along the GCL seams as outlined in the project specifications and shown on *Figure 7* below. No GCL was placed during precipitation, in the presence of excessive moisture, or during high winds.

**Figure 7 – ESI Placing Granular Bentonite along GCL Seams**



Additional details on the placement of the GCL are further described in the Langan Daily Reports and supporting photo logs provided in *Appendix F*.

#### *2.4.3.1 Bentonite Sand Plug*

As outlined in specification Section 02375 – Geosynthetic Clay Liner of the *100% Design* package, a sand bentonite plug was constructed on the inboard side of the HB wall for the low-lying areas (below the Site groundwater table) along the edges of SA-6 South. This bentonite sand plug was constructed in the field by Entact by mixing clean sand with sodium montmorillonite at a 90% sand to 10% bentonite ratio.

The plug was constructed to a depth of approximately 18-inches below the HB wall elevation, and was approximately 2 ft. thick. Additional details on the edge connection details are provided below in *Section 2.4.3.2*. *Figure 8* below also shows the typical construction of the bentonite sand plug along the HB wall.

**Figure 8 – Typical Construction of Bentonite Sand Plug along HB Wall**



#### *2.4.3.2 GCL to Barrier Wall Connection Details*

GCL to Barrier Wall Logs are provided within *Appendix H*. As per the approved Langan CQA Plan, Amec Foster Wheeler completed a GCL to Barrier Wall (HB Wall & SCB) Connection Detail form for the low-lying areas of SA-6 South (below the Site water table). This form documented that the bentonite sand plug was appropriately constructed, that the barrier wall was clean and exposed, and that the appropriate GCL overlap (1 ft. minimum) was maintained.

### 2.4.4 60-mil Low Linear Density Polyethylene (LLDPE) Geomembrane

A textured LLDPE geomembrane manufactured to a nominal 60-mil thickness was placed over the GVL and GCL layers at the Site to mitigate groundwater infiltration through the cap. The rolls of the approved 60-mil LLDPE geomembrane were delivered to the Site, offloaded, and staged onsite by Entact. The RIRs for the LLDPE geomembrane are provided in *Appendix G*.

The 60-mil LLDPE geomembrane was placed directly over the GVL and GCL geotextiles. The 60-mil geomembrane was placed in accordance with specification Section 02372 – Cap Geomembrane Liner as defined in the *100% Design* Package. The location and placement of the LLDPE panels is documented on the ESI Panel Placement Logs provided in *Appendix I*.

ESI deployed the geomembrane rolls in a general north to south orientation. Hand clamps were used on the edge of the panels to aid in the final positioning, as required. The leading edge of the LLDPE geomembrane panels were held in place by sand bags until the subsequent panels

could be placed and seamed via fusion welding methodology. The number of panels deployed in a single day was limited to the amount that could be field seamed that day. No panels were placed during precipitation, in the presence of excessive moisture, or during high winds. The minimum temperature for seaming was specified as 32°F, with a maximum temperature of 104°F. No cold or hot weather seaming was conducted as temperatures did not reach below 32°F, or above 104°F during geomembrane installation.

Each individual LLDPE panel was observed for damage by ESI, Entact, and Langan during the installation process. Prior to seaming, the approved geomembrane was observed by Langan to ensure that the material was free of defects or damage prior to seaming. Areas observed to be damaged / defective, or areas where the geomembrane had to be custom cut to conform to the subgrade contours, were marked for repair. Repairs were completed in the field by ESI via patching and welding the geomembrane as further described below. All repairs were documented and recorded on the Record Drawings (*Appendix A2*). Additional details on the repair methodology and types of repairs are further described in *Section 2.4.4.4*.

The LLDPE geomembrane was seamed in the field by two welding methods: extrusion and double-fusion. Extrusion welding was used for repairs, short seams, and areas where the double fusion could not operate. Extrusion welding was performed with a hand held extrusion welding gun. The double-fusion seaming (fusion welding) was performed using a self-propelled "wedge welder" which formed an air channel between the two seams. Fusion welding was performed with a minimum of 4-inches overlap as per the project specifications.

The integrity of the welds was monitored by both destructive and non-destructive test methods. The destructive testing consisted of collecting samples from the completed seams at a minimum frequency of one sample per 500 ft. of weld (for both fusion and extrusion welds). A representative of Langan was onsite to confirm the locations of the destructive samples along with a representative of ESI.

The destructive samples were analyzed by Geotechnics, Inc. (Geotechnics) the Contractor's Material Quality Control Laboratory. Langan also collected additional QA samples (approximate 15% of total samples collected) and submitted samples to TRI Environmental, Inc. (TRI) for independent QA testing. Destructive sample locations were repaired in the field and tested with a vacuum box. All destructive sample locations have been recorded and are shown on the Record Drawings (*Appendix A2*). The laboratory results of the destruct samples are discussed further in *Section 2.4.4.3* below.

In addition to the destructive testing, non-destructive testing was completed by ESI during cap construction. Two types of non-destructive tests were used at the Site: air channel tests (pressure tests) and vacuum box tests as defined further below:

1. Pressure Testing - The pressure tests were conducted on 100% of all the double fusion welded seams where both ends of the seam were clamped and sealed and a pressure needle was inserted into the air channel. The air channel was then pressurized to thirty pounds per square inch (psi) and the pressure was maintained for a minimum of five minutes. If the pressure did not stabilize, or a pressure drop greater than four psi was noted over a five minute span, then the seam was deemed unacceptable and the faulty

area was isolated and repaired. Results of the non-destructive testing are discussed further in *Section 2.4.4.2* below.

2. Vacuum Box Testing - For patch / repair work and other areas where extrusion welding was required, the extrusion welds were vacuum box tested by ESI. A soapy solution was applied to the weld area, and a vacuum box was placed over the weld for a minimum of ten seconds and observed for the appearance of soap bubbles. Any areas where these bubbles appeared were marked, repaired, and retested. Any areas that failed the vacuum box test were identified as a non-compliance issue and are discussed further in *Section 2.4.6* below.

At seams or locations where vacuum box or pressure testing could not be conducted (i.e. boot penetrations), the extrusion welds were visually inspected by observing the welding process and checking the weld for uniformity and completeness. Individual forms were generated to document the installation of each boot / penetration. Additional details on the pipes / penetrations encountered on the cap are further described in *Section 2.4.4.5*.

For additional details on the geomembrane placement, destructive and non-destructive testing, patch / repair work, and other geomembrane related construction activities, refer to the Langan Daily Reports and Photo Logs provided in *Appendix F*.

#### *2.4.4.1 Trial Weld Logs*

Prior to any seaming of the geomembrane each day, the fusion and/or extrusion welding equipment was used to conduct trial welds (or test strips) to confirm that the material and equipment met the specification requirements. Test strips were collected (using the same 60 mil LLDPE geomembrane placed across the cap) by completing a sample fusion or extrusion weld. This activity included producing several types of seams to qualify that a specific seamer and apparatus would yield the desired specified performance requirements. These seam types included: smooth-to-smooth, smooth-to-textured, and textured-to-textured. It should be noted that the 60 mil geomembrane installed across the cap was textured (60-mil Microspike); however, the manufacturer's product has a smooth edge for welding.

The trial welds were cut and tested on a portable tensiometer by ESI. Langan and Entact observed the trial weld tests to confirm that the minimum peel and shear values were obtained (as per specification Section 02372 – Cap Geomembrane Liner defined in the *100% Design* package). These trial welds were completed prior to commencement of seaming at the start of each day, and once every four hours. The results of daily trial weld logs are provided in *Appendix J*.

#### *2.4.4.2 Non-Destructive Testing Results*

Non-Destructive Pressure Testing was conducted along the geomembrane panels, and the repaired / patched areas (i.e., using vacuum box testing) by ESI, as per the project specifications. The results of the non-destructive testing for each of the panel seams were provided in the Seam Control Logs shown in *Appendix K*. Additionally, the associated repairs

and the corresponding vacuum box testing results are presented in the ESI Repair Report attached in *Appendix L*.

During the construction of the cap at SA-6 South, there were two non-destructive tests (one pressure test and one vacuum box test) that failed during the field testing which consisted of the following:

1. Failed non-destructive (pressure) test for geomembrane panel seams Panel #7 / Panel #8 and identified as Repair (RP)-13 (as shown on the Record Drawings); and
2. Failed non-destructive test (vacuum box test) for repair RP-215 (Panel #50).

Both of these failures were subsequently repaired by ESI in general accordance with specification Section 02372 – Cap Geomembrane Liner and were documented as non-compliance issues which are further described in *Section 2.4.6* below.

#### *2.4.4.3 Destructive Testing Results*

Destructive testing was conducted for the fusion and extrusion welding that was completed along the edge of the geomembrane panels. Destruct samples were collected at a minimum sampling interval of 500 linear feet (LF) of seaming length for the initial twenty-five (25) samples. The locations of the destruct samples were identified in the field by the Independent QA Monitor (Langan) and are shown on the Record Drawings (*Appendix A2*). Once the destruct sample locations were determined, ESI cut and tested the destruct samples (as per the project specifications).

Six 1-inch wide specimens were cut from the destruct sample for field testing. These samples were then tested by a tensiometer equipped with a drive/pull apparatus rate of 20-inches per minute. Three of the specimens were tested for peel strength, and the remaining three for shear strength. The samples were tested to confirm that the geomembrane met the specified peel and shear strength values outlined in *Table 1* below. Additional details on the test results are provided on the Destructive Sample Information Logs attached as *Appendix M.*

**Table 1 – LLDPE Geomembrane Seam Property Requirements**

| Property | Test Method | 60-mil LLDPE Value |
|---|---|---|
| Shear Strength (min. avg.) | ASTM D 6392 | 90 lb/in |
| Peel Strength – Extrusion (min. avg.) | ASTM D 6392 | 66 lb/in |
| Peel Strength – Fusion (min. avg.) | ASTM D 6392 | 75 lb/in |

In addition to the field testing completed by ESI, a total of twenty-nine (29) fusion weld destruct samples, and fifteen (15) extrusion weld samples were sent to Geotechnics for lab verification.

A total of twenty-nine (29) fusion weld destruct samples (DS-1 through DS-29) were collected during the capping of SA-6. For the first 25 QA samples collected, all samples met the specified destructive testing requirements outlined in *Table 1*. As per the specification, the frequency of fusion weld destruct sampling was reduced from every 500 LF of welded seam to every 1,500 LF of welded seam. A summary of the peel and shear QA testing conducted for the 29 fusion weld samples collected is summarized in *Appendix N*.

A total of fifteen (15) extrusion destruct samples were collected throughout the capping of SA-6 South. *Table 2* below summarizes the results of the extrusion weld destruct samples collected as well as the corresponding laboratory data, peel and shear averages, and compliance with specification Section 02372 – Cap Geomembrane Liner outlined in the *100% Design* package.

**Table 2 – Summary of ESI / Langan QA Testing - Extrusion Welds**

| Honeywell SA-6 Capping | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| *Comparison of ESI / Langan (QA) Destruct Samples - Extrusion Welds* | | | | | | | | | | |
| ***Sample ID*** | ***Weld Type*** | ***Submitted By:*** | ***Test*** | ***Peel Strength (ppi)*** | | | | | **Avg. Strength (ppi)** | ***Meets Spec Requirement*** |
| EXT-DS-1 | Extrusion | Langan | Peel | 97 | 97 | 127 | 130 | 128 | **116** | **Yes** |
| DSX-1 | | Entact | Peel | 109.3 | 107.5 | 109.8 | 120.5 | 110 | **111.4** | **Yes** |
| EXT-DS-1 | | Langan | Shear | 133 | 172 | 148 | 181 | 146 | **156** | **Yes** |
| DSX-1 | | Entact | Shear | 115.7 | 119.8 | 118.1 | 117.5 | 116.2 | **117.5** | **Yes** |
| DSX-2 | Extrusion | Entact | Peel | 133.5 | 118.8 | 126.4 | 120.1 | 115.4 | **122.8** | **Yes** |
| | | | Shear | 132.7 | 150.3 | 145.5 | 135.4 | 130.3 | **138.8** | **Yes** |
| DSX-3 | Extrusion | Entact | Peel | 123.7 | 117.2 | 117.9 | 119.1 | 120.2 | **119.6** | **Yes** |
| | | | Shear | 126 | 128.6 | 125.1 | 124.5 | 125.1 | **125.9** | **Yes** |
| DSX-4 | Extrusion | Entact | Peel | 128.4 | 132.1 | 133.5 | 134.4 | 139.5 | **133.6** | **Yes** |
| | | | Shear | 144.7 | 143.7 | 141.8 | 150.7 | 145.7 | **145.3** | **Yes** |
| DSX-5 | Extrusion | Entact | Peel | 107.5 | 115.8 | 111.6 | 113.9 | 119.3 | **113.6** | **Yes** |
| | | | Shear | 131.7 | 136.9 | 151.8 | 137 | 149.5 | **141.4** | **Yes** |
| DSX-6 | Extrusion | Entact | Peel | 151.4 | 144.8 | 130.9 | 139.9 | 150.1 | **143.4** | **Yes** |
| | | | Shear | 164.9 | 162.3 | 151.5 | 155.6 | 159.7 | **158.8** | **Yes** |
| DSX-7 | Extrusion | Entact | Peel | 123.7 | 126.8 | 128.7 | 122.2 | 120.7 | **124.4** | **Yes** |
| | | | Shear | 134.6 | 133.7 | 134.8 | 136.2 | 135.5 | **135.0** | **Yes** |
| DSX-8 | Extrusion | Entact | Peel | 129.6 | 119.5 | 124.3 | 130.9 | 120 | **124.9** | **Yes** |
| | | | Shear | 131.6 | 130.7 | 129.7 | 134.4 | 127.8 | **130.8** | **Yes** |
| DSX-9 | Extrusion | Entact | Peel | 108.7 | 124.4 | 120.8 | 112 | 111.6 | **115.5** | **Yes** |
| | | | Shear | 132.8 | 126.8 | 133.9 | 116.1 | 122.8 | **126.5** | **Yes** |
| DSX-10 | Extrusion | Entact | Peel | 118.7 | 122.1 | 118.1 | 120.8 | 136.1 | **123.2** | **Yes** |
| | | | Shear | 123 | 145.2 | 149.5 | 130.7 | 145.6 | **138.8** | **Yes** |
| DSX-11 | Extrusion | Langan | Peel | 125 | 134 | 123 | 121 | 124 | **125** | **Yes** |
| | | Entact | Peel | 125.1 | 118.2 | 125.9 | 123.3 | 120.6 | **122.6** | **Yes** |
| | | Langan | Shear | 164 | 157 | 141 | 137 | 142 | **148** | **Yes** |
| | | Entact | Shear | 122.6 | 124.6 | 126.1 | 127.9 | 128.2 | **125.9** | **Yes** |
| DSX-12 | Extrusion | Entact | Peel | 130.4 | 121.3 | 148.4 | 118.2 | 138.9 | **131.4** | **Yes** |
| | | | Shear | 126.2 | 123.7 | 125 | 124.2 | 122.7 | **124.4** | **Yes** |
| DSX-13 | Extrusion | Entact | Peel | 117 | 97.9 | 123.5 | 66 | 55.6 | **92.0** | **No** |
| | | | Shear | 131.2 | 129 | 133 | 132.9 | 124.6 | **130.1** | **Yes** |
| DSX-14 | Extrusion | Entact | Peel | 119 | 119.7 | 118.8 | 123.3 | 122.6 | **120.7** | **Yes** |
| | | | Shear | 120.9 | 121.4 | 121.7 | 129.5 | 127.4 | **124.2** | **Yes** |
| DSX-15 | Extrusion | Entact | Peel | 119.5 | 114.1 | 123.8 | 111.4 | 106.8 | **115.1** | **Yes** |
| | | | Shear | 132.1 | 135.2 | 138.5 | 137.4 | 141.7 | **137.0** | **Yes** |

As highlighted above on *Table 2*, one destruct sample DSX-13 failed to meet the peel strength criteria for one of the five specimens tested. While the average of the five specimens tested for this specimen did comply with the project specifications, the extrusion weld in this area was designated as non-compliant. As such, the weld was subsequently patched, repaired, and re-tested and documented as Repair RP-487 in *Appendix L*. An additional extrusion weld destruct sample was collected and labeled as DSX-15. Additional details on this non-compliance issue are described in further detail in *Section 2.4.6*.

In addition, Langan collected a total of six QA samples (4 fusion weld samples and 2 extrusion weld samples) to verify the results of the Geosynthetic Installer's laboratory data. Langan's QA

samples were submitted to Texas Research Institute Environmental, Inc. (TRI). The results of the ESI and Langan destruct samples indicated that the peel and shear strength values met the requirements outlined in the project specifications. Furthermore, the additional QA samples collected by Langan yielded values that were in close proximity to the values obtained by ESI (which were generally lower than the values obtained by Langan's QA laboratory). The Laboratory Destruct Test Results are provided in *Appendix N*.

#### *2.4.4.4 Repair Reports*

The ESI Repair Report is provided in *Appendix L*. Several different types of repairs were observed and recorded during field activities by ESI. These corresponding repairs are shown on the Record Drawings (*Appendix A2*), and consisted of the following types:

- Custom Fit Repairs (CF) – Custom Fit Repairs consisted of areas of the geomembrane cap where the geomembrane was cut (and subsequently repaired) to allow the geomembrane to conform to the cap contours. These areas were typically located where there were abrupt elevation changes, such as drainage and utility swales, utility corridors, and planting areas;
- Wrinkles (WR) – Wrinkles consisted of areas where excess geomembrane was observed. Where the size of the wrinkle was determined to be detrimental to the geomembrane (i.e. wrinkles with the potential for folding), the wrinkle was cut, and the excess geomembrane was overlapped and sealed with an extrusion weld in accordance with the project specifications;
- Roller Wrinkles (RW) & Burnouts (BO) – Roller wrinkles can occur when slight differences in length between the two geomembrane edges being welded resulted in formation of a wrinkle along the geomembrane seam. Wedge burnouts occurred where the wedge became jammed thus causing the welder to burn / melt through the geomembrane seam. These areas were subsequently patched and repaired according to the project specifications;
- Destruct Samples (DS) – These areas consisted of the geomembrane destruct samples that were cut for laboratory testing. The removal of the sample creates a hole in the seam, thus these areas were subsequently patched according to the project specifications;
- Pipe Boots (PB) – Pipe boots were installed where penetrations of the geomembrane occurred such as at wells, piezometers, gas vents, and access manholes. Additional details are provided in *Section 2.4.4.5;*
- Add On (AO) – AO areas consisted of sections of SA-6 where an additional piece of geomembrane was required to finish a geomembrane run across the cap (from north to south);
- Seam Joints (SJ) – Seam joints consisted of the areas where non-destructive testing (pressure testing) was conducted along a "T" section of the geomembrane;
- Subgrade Irregularities (SI) – Subgrade Irregularities consisted of areas along the geomembrane cap where a rock or object larger than ½-inch in diameter was encountered underneath the geomembrane after the material had been placed. These

areas were subsequently cut, the rock/debris removed, and the area patched / repaired according to the project specifications. These SIs were identified as non-compliance issues and are discussed in further detail in *Section 2.4.6* below;

- Damage By Others (DO) – DO consisted of damage / punctures to the geomembrane cap caused by equipment or personnel during grading of the protective cover soil. These DO instances were identified as non-compliance issues and are discussed in further detail in *Section 2.4.6* below.
- Failed Seam (FS) – Failed seams consisted of fusion / extrusion weld samples that were collected, and failed to meet the strength criteria of the material as outlined in Section 02372 – Cap Geomembrane Liner presented in the *100% Design* Package (and summarized in *Table 1*). These FS instances were identified as non-compliance issues and are further described in *Section 2.4.6* below.


For additional details on the geomembrane repairs and non-compliance issues observed during field activities refer to the *Appendices L and P,* respectively.

#### *2.4.4.5 Geomembrane Penetrations & Pipe Boot Installation*

The geomembrane penetration and pipe boot logs are provided in *Appendix O*. The pipe boots were field fabricated by ESI, and the boots were installed at monitoring wells, gas vents, piezometers, and access manhole penetrations across the cap.

The geomembrane boots consisted of a vertical (minimum of 2 ft.) section of LLDPE being wrapped around the penetration (i.e. well, gas vent, etc.) from the base to the top of the penetration. The geomebrane wrap was then heat sealed and an extrusion weld was placed with a vertical seam connecting the two pieces of geomembrane. The end of the boot terminated in a skirt section which was placed over the boot. The skirt and the geomembrane overlapped a minimum of 18-inches and the skirt was welded to the geomembrane. A neoprene rubber gasket was used between the boot and the penetration and secured with a 1-inch wide stainless steel clamp (or two ½-inch clamps). An LLDPE sacrificial sheet was then placed between the boot and the clamp for protection and a butyl sealant was applied along the top of the boot. *Figure 9* below shows the typical construction of a geomembrane pipe boot in the field by ESI. The welding of each boot was observed by Langan, and each boot fabrication was documented on an individual boot fabrication form provided in *Appendix O*. The four typical types of penetrations present on the SA-6 South cap are defined below.

**Figure 9 – Typical Construction of a Geomembrane Pipe Boot**



*2.4.4.5.1 Monitoring Wells*

A total of four (4) monitoring wells were located within the SA-6 South cap. The monitoring wells were constructed with PVC and were encased in a 4-inch metal casing. Refer to *Appendix O* for the penetration and boot logs for monitoring wells: 073-MW-1BR, 115-E1A-SO, 115-W3-SO, and 115-W5-SO.

*2.4.4.5.2 Gas Vents*

A total of eight (8) gas vents were constructed through the cap. Gas vents were completed in accordance with Section 02380 – Gas Venting System of the *100% Design* Package to allow any naturally occurring methane to vent to the atmosphere. Refer to *Appendix O* for the penetration and boot logs for gas vents GV-0 through GV-7, with the corresponding locations shown on the Record Drawings (*Appendix A2*).

*2.4.4.5.3 Piezometers*

A total of five (5) piezometers were installed through the cap to allow the project team to compare the groundwater within capped area to the groundwater immediately outside of the cap. Piezometers were encased within a 4-inch steel casing. Refer to *Appendix O* for the penetration and boots logs for piezometers PZ-12, PZ-14, PZ-16, PZ-18, and PZ-20, and to the Record Drawings (*Appendix A2*) for the corresponding piezometer locations.

*2.4.4.5.4 Pump Station and Access Manholes*

A total of one pump station and three (3) access manholes were completed with field fabricated geomembrane boots. Refer to *Appendix O* for the penetration and boot logs for Access Manhole #1, Access Manhole #2, Access Manhole #3, and Access Manhole #4, with the corresponding locations shown on the Record Drawings (*Appendix A2).*


### 2.4.5 Geocomposite Drainage Layer (GDL)

To facilitate drainage and transport of infiltrated surface water off the cap, a geocomposite drainage layer (GDL) consisting of a geonet with a non-woven geotextile bonded to both sides (i.e., defined as SKAPS TN 330-2-6 ) was delivered to the Site, offloaded, and staged onsite by Entact in accordance with the project specifications. The RIRs for the delivered GDL rolls are provided in *Appendix G*. The GDL was placed at the Site by ESI and was placed directly over the geomembrane cap as shown on the Record Drawings (*Appendix A3*).

GDL panels were placed according to the specification Section 02374 – Geocomposite Drainage Layer as defined in the *100% Design* package. For adjacent GDL panels, the following minimum seaming requirements were met:

- Adjacent rolls of GDL were overlapped so that the geonet overlapped by 2 to 3-inches, and the geotextiles overlapped by at least 4-inches;
- The bottom layer of geotextile (underneath the geonet) was overlapped so that no areas of the underlying geomembrane were exposed;
- White plastic fasteners were placed at a maximum of every 5 ft. along the seam. Additional fasteners were requested by the QA team when the seams extended down the slopes or elevation changes were noted; and
- Once the geonet was tied with a sufficient number of fasteners, the top geotextile of the GDL was continuously sewn as shown in *Figure 10* below.

**Figure 10 – ESI Conducting Sewing of Geotextile (GDL)**



During placement of the GDL, butt seams, rips, tears, or other damaged areas of the GDL were repaired by exposing an appropriate area of geonet, placing fasteners as defined in the project specifications, and covering the area with a new piece of orange geotextile (same as the GDL geotextile) which was heat sealed in place.

Once the GDL was placed, Entact placed protective cover soil (i.e., 1 ft. layer of material) directly over the GDL. In addition, yellow caution tape was placed every 55-inches over the GDL prior to protective cover soil placement. The caution type had bold type which indicated "Danger Do Not Dig – Peligro No Excavar" in English and Spanish. Additional details on the GDL placement are provided in the Langan Daily Reports and Photo Logs provided in *Appendix F*.

### 2.4.6 Non-Compliance Issues

The Summary of Non-Compliance & Corrective Action Sheets are provided in *Appendix P*. During the SA-6 capping activities, any QA field tests, observations, or failed samples that did not comply with the project specifications were documented and recorded as a non-compliance issue. A total of twelve (12) non-compliance issues were identified throughout the capping of SA-6 South and are summarized below:

1. Subgrade Irregularities – Refer to Sheet Numbers 1, 2, 4, 6, and 8 of the Non-Compliance & Corrective Action Sheets (*Appendix P*). In general, the subgrade irregularities consisted of stones or other material greater than ½-inch in size that was encountered below the geomembrane cap after the material had been placed and

secured. These objects were removed by cutting the geomembrane, removing the object, and patching the geomembrane in accordance with the project specifications. The subgrade showed no indication of these items at the time of subgrade approval, and it is postulated that these items were dislodged from the subgrade as the GVL was drawn across the subgrade surface;

2. Subgrade Irregularity (Hydrated GCL) – Refer to Sheet Numbers 7, 9, and 10 (*Appendix P*). In general, the Hydrated GCL Subgrade Irregularities consisted of areas where the underlying GCL layer had become saturated following heavy rain events. The saturation of the GCL was due to the unfinished grading of the SA-6 cap, as well as equipment failures, which resulted in water ponding along the edges of the cap during high intensity rain events. This ponding caused the water to move laterally across limited portions of the cap thus wetting the GCL layer prior to cover soil placement. For these areas, the geomembrane was cut to expose the GCL followed by replacement of the wetted GCL. Visual observation of the underlying subgrade soils exhibited no damage or washout of the subgrade. Repair activities were conducted so that the resulting materials were placed in accordance with the project specifications;
3. Failed Vacuum Box Test – Refer to Sheet Number 5 (*Appendix P*). During vacuum box testing of repair RP-215, a failed extrusion weld was identified. As such, a new geomembrane patch (RP-222) was placed over the failed extrusion weld, and subsequently tested using the vacuum box to verify the integrity of the new weld;
4. Failed Non-Destruct Test – Refer to Sheet Number 3 (*Appendix P*). A failed non-destruct test (pressure test) was encountered along Panel Seams #7/8. Based on the length of the failed seam (approximately 6 ft. along the southern end of SA-6), the entire seam was patched and repaired (approximate 2 ft. by 6 ft. patch). Vacuum box testing was then conducted to confirm the integrity of the new extrusion welds;
5. Failed Destruct Sample – Refer to Sheet Number 11 (*Appendix P*). Extrusion weld destruct sample DSX-13, which was collected from repair RP-477, failed one of the five test specimens for peel strength testing (Note: averages of the five specimens conformed to the project specifications). A new patch was placed over RP-477, and was identified as a Failed Seam (FS). It should be noted that the new patch was identified as repair RP-486. Once completed, an additional extrusion weld destruct sample (DSX-15) was collected to confirm the new patch met the specification requirements. Subsequent laboratory testing confirmed that the DSX-15 destruct sample complied with the project specification strength requirements; and
6. Geomembrane Puncture (Equipment) – Refer to Sheet Number 12 (*Appendix P*). During final grading of the protective cover soil by Entact, an excavator bucket punctured the geomembrane liner along the northern end of SA-6 South (along the SCB Wall). This puncture was subsequently repaired / patched, welded, and vacuum box tested by ESI, according to the project specifications. The repair associated with the puncture was identified as repair RP-488, and was listed as Damage by Others (DO).

Additional details on the non-compliance issues encountered, as well as the subsequent repair activities, are further described in the Langan Daily Reports and Photo Logs provided in *Appendix F*.

# 3.0 DECLARATIONS

## 3.1 General

Langan personnel have monitored the construction and field activities completed for the capping of SA-6 South specific to the subgrade preparation and placement of the geotextile and geocomposite materials as defined herein. Based on the field observations made by Langan along with the field and laboratory test data collected by the Contractor and Subcontractors, it is our professional opinion that the construction observed at SA-6 South complied with the approved *100% Design* package. Additional details on the work and approval of materials is outlined in the *EOR Closure Report*.

## 3.2 Limitations

This Cap Geosynthetic Quality Assurance Report (QA Report) was prepared by Langan (in conjunction with Amec Foster Wheeler) for the exclusive use of Honeywell. This QA Report applies specifically to the subgrade preparation and construction of the geosynthetics components of the SA-6 South cap only.

The construction observations and monitoring were conducted under the conditions stated. Conclusions made in this report were based on these observations and data obtained from field and laboratory tests conducted on the QA samples collected.

The topographic survey measurements were completed by Entact and their licensed surveyor Maser and subject to review and approval by Amec Foster Wheeler. Langan did not independently verify the accuracy of this data.


Acceptance of the geosynthetic materials used for the SA-6 South cap construction was completed by Amec Foster Wheeler. Furthermore, the QC laboratory testing was completed by Geotechnics (under the direction of Entact) and QA laboratory testing was completed by TRI (under the direction of Langan).


The approval of all materials used for this project was completed by Amec Foster Wheeler in the *EOR Closure Report*. The geosynthetic production quality testing was completed by AGRU America, Inc. and their subcontracted companies working on their behalf. Langan did not independently verify the accuracy of the conformance test data.

# Appendix A : Record Drawings

*A1. GVL / GCL Record Drawing*
*A2. LLDPE Geomembrane Record Drawing*
*A3. GDL Record Drawing*

# *A1. GVL / GCL Record Drawing*




0 80 160
Feet

## LEGEND

- GEOCOMPOSITE GAS VENT LAYER (GVL)
- GEOSYNTHETIC CLAY LINER (GCL)
- Class A/16 oz Geotextile
- SCB WALL
- HB WALL (Inner Edge)
- GAS VENT PIPE
- GAS VENT (NOT TO SCALE)
- SPOT ELEVATION (ft) (X 0.0)


J.H. 01/28/2016


ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP GVL/GCL LAYOUT
Class A Geotextile/Gas Vent Layer/Geosythetic Clay Liner
01/28/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *A2. LLDPE Geomembrane Record Drawing*




## LEGEND

RP-1 (Repair Number)

LINER SEAM/EDGE

SCB WALL

HB WALL (Inner Edge)

RP: Repair

DSX: Destructive Extrusion Weld Test

DS: Destructive Fusion Weld Test

P: Panel

\- Bead

NOTE: Refer to ESI Repair Report for repair details

0 80 160 Feet

J.H. 01/28/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650


DRAWING NAME


SA6 SOUTH CAP PANEL LAYOUT
60 mil Textured LLDPE Geomembrane
01/28/16

PROJECT NAME & LOCATION

HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *A3. GDL Record Drawing*




LEGEND

GEOCOMPOSITE DRAINAGE LAYER (GDL)

SCB WALL

HB WALL (Inner Edge)

0 80 160 Feet

J.H. 01/27/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

SA6 SOUTH CAP GDL LAYOUT
GEOCOMPOSITE DRAINAGE LAYER 01/27/16

PROJECT NAME & LOCATION

HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Appendix B
# Langan CQA Plan

# CONSTRUCTION QUALITY ASSURANCE (CQA) PLAN

# for

# Geosynthetic Cap Installation
# Study Area 6
# Jersey City, New Jersey

***Prepared For:***

**Honeywell International, Inc.**
**101 Columbia Rd.**
**Box 2105**
**Morristown, NJ 07962**

***Prepared By:***

**Langan Engineering and Environmental Services, Inc.**
**River Drive Center 1, 619 River Drive**
**Elmwood Park, NJ 07407**

**July 2015**

**Langan Project No. 10053001**

LANGAN

# CONSTRUCTION QUALITY ASSURANCE (CQA) PLAN

***Prepared By:***
**Langan Engineering & Environmental Services, Inc.**
**River Drive Center 1**
**619 River Drive**
**Elmwood Park, NJ 07407**

Vikki Hon, EIT
Staff Engineer

Dan Bosworth
Senior Staff Engineer

Jeffrey Stoicescu, P.E.
Associate
New Jersey Professional Engineer License No. 24GE04504400

Rory Johnston, P.E.
Principal / Vice President
New Jersey Professional Engineer License No. GE04080500

LANGAN

LANGAN

# TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 1**
1.1 Purpose ..... 1
**2.0 PERSONNEL RESPONSBILITIES, AUTHORITY, AND QUALIFICATIONS ..... 2**
2.1 General ..... 2
2.2 Owner ..... 2
2.3 Design Engineer ..... 2
2.4 Construction Contractor ..... 3
2.5 Cap Geosynthetics Quality Assurance Engineer ..... 4
**3.0 QUALITY CONTROL MEETINGS ..... 6**
3.1 Daily Tailgate Safety Meeting ..... 6
3.2 QA/QC Coordination Meeting ..... 6
3.3 Progress Meeting ..... 6
3.4 Geosynthetic Pre-Installation Meeting ..... 7
3.5 Observation and Testing Records ..... 7
**4.0 CONSTRUCTION QUALITY ASSURANCE ..... 8**
4.1 General ..... 8
4.2 Subgrade Preparation ..... 8
4.2.1 Quality Assurance ..... 8
4.3 Gas Venting System ..... 9
4.3.1.1 Quality Assurance ..... 9
4.4 Geomembrane Layer ..... 10
4.4.1 Quality Assurance ..... 10
4.5 Geocomposite Drainage Layer 2 (Surface water infiltration drainage) ..... 11
4.5.1 Quality Assurance ..... 12
4.6 Root Barrier ..... 12
4.6.1 Quality Assurance ..... 13
4.7 Geosynthetic Clay Liner ..... 13
4.7.1 Quality Assurance ..... 13
4.8 Earthwork ..... 14
**5.0 CAP GEOSYNTHETICS QA REPORT ..... 14**

## TABLES

Table 1 Geosynthetic Material Testing Methods & Frequency

## FIGURES

Figure 1 SA-6 Liner Installation Organization Chart

## APPENDICES

Appendix A QA/QC Forms
- A1 – Certification of Completion
- A2 – Receiving Inspection Report Table
- A3 – Individual Photographic Log
- A4 – Geosynthetics Inventory and Certification Log
- A5 – Subgrade Surface Checklist
- A6 – Trial Weld Log
- A7 – Panel Placement Log
- A8 – Seam Testing Chain of Custody Form
- A9 – Seam Control and Non-Destructive Test Log
- A10 – Repair Log
- A11 – Conformance Test Chain of Custody Form
- A12 – Destructive Seam Field Test
- A13 – Destructive Sample Tracking Summary
- A14 – Penetration Sealing Observation / Cap to Barrier Installation Observation
- A15 – Geosynthetic Daily Inspection Report
- A16 – Notice of Non-Compliance and Corrective Action Form

## 1.0 INTRODUCTION

Honeywell International Inc. (Honeywell) is currently remediating Study Area 6 (SA-6), located in Jersey City, New Jersey (Site). SA-6 encompasses work in two areas: SA-6 North and SA-6 South, which are separated by Study Area 7 (SA-7). The Open Space areas at SA-6 North and SA-6 South will be covered with an engineered cap that includes a linear low-density polyethylene (LLDPE) geomembrane cover, a gas venting layer, a geocomposite drainage layer (GDL), a geosynthetic clay liner (GCL), and other related geosynthetic cap components. Technical specifications and design drawings for the engineered cap may be found in the document titled "100% Specification and Design Drawings."

Honeywell retained Langan Engineering and Environmental Services, Inc. (Langan) as the Independent Quality Assurance (QA) Engineer for the cap geosynthetics installation. This Construction Quality Assurance (CQA) Plan has been prepared in support of this site remediation project with pertinent supporting details outlined herein.

### 1.1 Purpose

The purpose of this CQA Plan is to describe the quality assurance and control procedures required for the construction of the geosynthetic components of the capping system for the Study Area 6 site, encompassing SA-6 North and SA-6 South.

The ultimate goal of this CQA program is to ensure that proper construction techniques and procedures are implemented throughout the course of this phase of the SA-6 project in accordance with the project specifications. Upon completion of the construction activities, a Cap Geosynthetics QA Report will be prepared.


All of the involved parties will receive a copy of this CQA Plan including the Owner, Construction Contractor, Capping System Subcontractor, Geosynthetic Installer, and the Independent Quality Assurance Engineer. The roles and responsibilities of these parties are outlined further in Section 2.0.

## 2.0 PERSONNEL RESPONSBILITIES, AUTHORITY, AND QUALIFICATIONS

### 2.1 General

The principal parties involved in the permitting, design, and construction of the final capping system for the SA-6 site include the Owner, Design Engineer, Construction Contractor, and the Independent Quality Assurance Engineer. Additional entities include the Geosynthetic Installer and Material Quality Control Laboratory. The project organization chart is shown on Figure 1. Descriptions of the individual parties are provided in the sections below.

**Figure 1 – SA-6 Liner Installation Organization Chart**




### 2.2 Owner

Honeywell, as Owner, is ultimately responsible for the construction of the capping of SA-6. The Owner has retained the Design Engineer, Construction Contractor, and the Independent Quality Assurance Engineer.

### 2.3 Design Engineer

Amec Foster Wheeler Environment & Infrastructure, Inc. (AmecFW), as the Design Engineer, was responsible for preparing the final design of the capping system, as well as plans and specifications for the construction work. The final design includes relevant aspects of the capping system, including details of the subgrade preparation, gas venting system, utility trenches, geosynthetic placement details, soil cover requirements, and other relevant design considerations. Samuel G. Shallard is the Engineer of Record (EOR) for AmecFW.

Technical specifications and design can be found in the document titled "100% Specifications and Design Drawings."

Personnel involved with the design engineering portions of the project are outlined herein:

- **Engineer-of-Record**
  Mr. Samuel Shallard shall serve as the Engineer of Record (EOR) and technical lead. Mr. Shallard will also be the lead engineer in resolving technical questions that arise during project execution.

- **Quality Assurance Manager**
  Mr. David Ambrose shall serve as the Quality Assurance (QA) Manager. He shall be directly responsible for subcontractor conformance to the technical specifications and project requirements.

- **Field Engineering**
  Ms. Ari Eslaminejad will serve as the EOR site representative.

### 2.4 Construction Contractor

AmecFW shall also serve as Construction Contractor (Contractor), and is responsible for constructing the soil capping system in accordance with the design criteria, plans, and specifications while using the necessary construction procedures and techniques. The Contractor has engaged ENTACT (Subcontractor) to support AmecFW with these activities.

A New Jersey licensed land surveyor will be contracted to conduct the licensed surveying tasks required in the contract documents and in this CQA Plan as well as to prepare the required record documents.

The Contractor shall provide sufficient project management and project supervision staff to ensure the submission and approval of materials, and that the execution of the work is completed in a timely manner and in accordance with the plans and specifications. Work shall be completed to the standards defined by this CQA plan and the plans and specifications. The Construction Manager, or a designated representative, shall be present during construction activities to oversee work by contractor personnel and/or subcontractor personnel. The Construction Manager or designated representative will coordinate activities directly with the Owner's representative and representatives of the Independent Quality Assurance (QA) Engineer. The Contractor shall be responsible for the repair or replacement of any items or work found defective. The Construction Manager will be supported by the AmecFW Quality Assurance Manager.

For the SA-6 capping project, AmecFW has provided a list of the capping construction team including subcontractors and corresponding responsibilities. A summary of these team members is provided below and presented on the organization chart shown on Figure 1.

- **Construction Manager**
  Mr. Stuart Bills shall serve as the AmecFW Construction Manager and Site Health & Safety Officer with the responsibility for the day-to-day Site activities. He shall report directly to the Honeywell Manager of Construction and the Honeywell Remediation Manager. Mr. Bills shall be responsible for the project implementation schedule, budget, and subcontractor oversight.

- **Project Controls**
  Mr. Eric Christodoulatos shall be responsible for coordinating and tracking submittal approvals and Request for Information (RFI) responses with the EOR. He will also be responsible for project financial cost and schedule tracking and projections.

- **Capping System Subcontractor – ENTACT**
  ENTACT is contracted to AmecFW to perform the cap construction. ENTACT will be responsible for installing the SA-6 capping system in accordance with "100% Specifications and Design Drawings." ENTACT will also be responsible for coordinating scheduling, project deviations, work plans, and any other pertinent construction details directly with the project team. ENTACT will report directly to AmecFW, and will provide the final construction details, including as-built drawings, upon project completion.

- **Geosynthetic Installer – ESI**
  ESI (Installer) is subcontracted to ENTACT. ESI will be responsible for installing the SA-6 geosynthetic materials in accordance with the project plans and specifications, and will work directly with ENTACT. ESI will also be responsible for coordinating scheduling, project deviations, work plans, and any other pertinent construction details directly with the project team.

- **Material Quality Control Laboratory – Geotechnics**
  Geotechnics is subcontracted to ENTACT. Geotechnics will be responsible for supplying laboratory testing results required as part of the capping project, such as destructive seam testing.

### 2.5 Cap Geosynthetics Quality Assurance Engineer

Langan has been retained by Honeywell to provide Independent Quality Assurance for the SA-6 Cap Geosynthetics installation. The Quality Assurance (QA) Engineer will perform the activities specified in this CQA Plan (i.e. monitoring, field oversight, and documentation) and provide a Cap Geoynthetics QA report at the conclusion of the project for the work observed. At a minimum, the Independent QA engineering staff will include a Geosynthetic QA Manager, QA Engineer, and on-site Field Technician, as outlined herein.

**Geosynthetic QA Manager – Mr. Jeffrey Stoicescu, P.E.**

**Duties:**

- Review design criteria, plans, and specifications for clarity and completeness so that the CQA Plan can be implemented.
- Advise the Lead Quality Assurance Engineer and On-Site Field Technician on CQA requirements and procedures. For similar projects, the project manager will support the EOR and field team members on a variety of Requests for Information and Submittals that will vary either the construction sequence or materials.
- Schedule and coordinate CQA inspection activities.
- Routinely update the Owner and Design Engineer on cap geosynthetic status throughout the duration of the geosynthetic portion of the project.
- Attend conference calls as required to provide potential solutions to requests when requested by the EOR.

**Authority:**

The Geosynthetic QA manager has the authority to determine whether or not materials, procedures, and/or installed materials meet the minimum project requirements, and to reject any materials, procedures, and/or installed work that fails to meet the project requirements. The project manager will advise the EOR, Contractor, and Owner of the rejection of materials, procedures, or installed work.

**Lead Quality Assurance Engineer – Mr. Dan Bosworth**

**Duties:**

- Direct and support the CQA personnel in performing observations and material tests;
- Confirm that the testing data is accurately recorded and maintained;
- Verify that the raw data is properly recorded, validated, reduced, summarized, and interpreted;
- Review and interpretation of data sheets and reports;
- Notify the Geosynthetic QA Manager of potential conflicts with the design drawings;
- Coordinate with the EOR to reject defective work and verify that corrective measures are implemented;
- Identify work that should be accepted, rejected, or uncovered for observation, or that may require special testing, inspection or approval.

**Authority:**

The Lead QA Engineer shall have the authority to observe and test any material and/or work, and render a decision as to whether the work is acceptable (based on the testing), and ensure that any work that does fail is removed and replaced with acceptable materials and/or workmanship.

**On-site Field Technician – Mr. Dan Bosworth and/or Mr. Connor Shields**

**Duties:**

- Perform site monitoring of the work in progress to assess compliance with the design criteria, plans, and specifications;
- Observe deliveries received on site as required on the Receiving Inspection Report provided as Appendix A2;
- Verify that the tests are conducted according to this CQA Plan;
- Report to the Lead QA Engineer results of inspections, including work that is not of acceptable quality or that fails to meet the specified design; and
- Complete inspection and testing forms as necessary.

**Authority:**

The on-site technician will have the authority to observe and test material and render a decision of whether the work is acceptable based on observation of testing and help ensure that work that does not conform to the approved plans and specifications is removed and replaced with acceptable materials and/or workmanship.

## 3.0 QUALITY CONTROL MEETINGS

### 3.1 Daily Tailgate Safety Meeting

A daily tailgate meeting will be held prior to commencement of any work activities for the day at approximately 6 A.M or time designated by the Construction Manager. The Contractor, Subcontractor, Geosynthetic Installer, and on-site quality assurance personnel involved in the field work procedures for that specific day shall be present at this meeting. The Daily Meeting shall include relevant aspects of the work for the day and its potential relationship to relevant health and safety (H&S) aspects outlined in their respective H&S plans. Individuals who arrive after the tailgate meeting has been conducted shall convene with the Construction Manager or other designate for the H&S briefing prior to starting work.

### 3.2 QA/QC Coordination Meeting

A QA/QC coordination meeting will be held prior to the construction of the capping system. Representatives of Honeywell, the EOR, the Construction Contractor, and the Independent QA Engineer will be present. The agenda for this meeting may include, but not be limited to:

- Familiarize each involved party with the CQA Plan and its role relative to the design criteria, site construction and closure plans, specifications, and construction documentation;
- Review the responsibilities of each involved party;
- Review the Contractor's projected work schedule and methodology;
- Determine any changes, if necessary, to the CQA Plan that are needed to ensure that the capping system will be constructed to meet the specific design;
- Review lines of authority and communication for each organization;
- Discuss the established procedures or protocol for observations and tests including sampling strategies;
- Discuss the established procedures or protocol for handling design change bulletins, construction deficiencies, repairs, and retesting;
- Review methods for documenting and reporting inspection data;
- Review methods for distributing and storing documents and reports;
- Review work area security and safety protocol;
- Review procedures for the location and protection of construction materials and for the prevention of damage to the materials from inclement weather or other adverse events;
- Conduct a site walk-around to review construction materials where available and to inspect equipment storage locations; and
- Minutes of the preconstruction meeting will be prepared by the Quality Assurance On-site field technician and will be distributed to all parties.

### 3.3 Progress Meeting

Progress meetings will be held once a week on Tuesdays at 8:30 A.M or at an alternate time designated by the Construction Manager. These meetings shall be scheduled between the primary parties involved with this project. At a minimum, a Representative of Honeywell, the Contractor's Construction Manager, the EOR, and a representative of the Independent QA team shall be present. At times, a subcontractor may be requested to attend as well.

### 3.4 Geosynthetic Pre-Installation Meeting

A progress meeting will be held prior to commencing installation of the geomembrane and/or geosynthetic materials. At a minimum the attendees shall be the Contractor's Construction Manager, the Lead Quality Assurance Engineer and On-Site Field Technician, as well as representatives from ENTACT and ESI. The agenda for this meeting will include but is not limited to the following:

- Discussion of CQA procedures and requirements;
- Review Panel Layouts;
- Review of Repair tracking methods and drawings;
- Discussion of procedures or protocol for observations and tests including sampling strategies;
- Installation sequence and methods;
- Projected work schedule; and
- Minutes of the geosynthetic pre-installation meeting will be prepared by the Project Controls representative and will be distributed to all parties.

### 3.5 Observation and Testing Records

There will be observation and testing records that will be utilized in conjunction with the construction oversight performed by the Quality Assurance (QA) Field Technician. The observation logs listed below contain the data to be recorded by the Quality Control Representative and can be found in Appendix A. The QA on-site field Technician will complete the following observation and testing records:

- Geomembrane Observation Records – The geomembrane inspection records forms consisting of:
    - Material delivery checklist (see Appendix A4)
    - Subgrade surface acceptance records (see Appendix A5)
    - Trial weld logs (see Appendix A6)
    - Panel placement record (see Appendices A7)
    - Panel seaming log (see Appendix A8)
    - Non-destructive testing log (see Appendix A9)
    - Repair log (see Appendix A10)
    - Conformance Test Chain of Custody Form (A11)
    - Destructive testing log (see Appendices A12 and A13)
    - Penetration Sealing Observation / Cap to Barrier Installation Observation (see Appendix A14)
    - Daily inspection report for the geomembrane liner (see Appendix A15)
- Other related forms including certification of completion (see Appendix A1), receiving inspection report table (see Appendix A2), and notice of non-compliance and corrective action form (see Appendix A16).

The QA on-site field technician overseeing geomembrane installation will independently document related data contained within the records listed above to provide the information to review the Contractor's geomembrane capping system subcontractor documentation prior to acceptance of the installed geomembrane cap. The Contractor shall provide access to the work

site and shall provide the QA on-site field technician access to all field data and records, as built drawings, and shall collect duplicate samples as required for testing by the QA on-site field technician laboratory subcontractor as required.

In addition, the on-site field technician will maintain a field notebook onsite to document observations, test results, weather conditions, work defects, etc. that occur during observation of construction activities.

## 4.0 CONSTRUCTION QUALITY ASSURANCE

### 4.1 General

The final capping system consists of the following layers, from bottom to top:

- A gas venting system (geocomposite drainage layer and vents);
- A 60-mil geomembrane LLDPE layer;
- A geocomposite drainage layer with warning layer;
- 12-inch thick geocomposite drainage layer cover soil;
- 16 oz woven geotextile root barrier; and
- Soil layers consisting of structural fills, planting soils, and capped with a 6-inch minimum topsoil layer.

The layers of the capping system are described in the sections below.

### 4.2 Subgrade Preparation

The subgrade layer of the capping system is shown on construction drawing C-301, provided in "100% Specifications and Design Drawings." The soil surface for the capping system (subgrade) is currently under construction to prepare the surface in accordance with the subgrade specification. These subgrade surface conditions will require review and approval by the Independent QA Engineer and Capping System Contractor and geosynthetics installer prior to placement of the geosynthetic materials as defined below.

#### 4.2.1 Quality Assurance

The subgrade observation and approval QA/QC forms have been provided in Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance to Section 02372 found in "100% Specifications and Design Drawings" and note deviations from the technical specifications;
- Observe subgrade preparation; and
- Review documentation to verify compliance.

Testing and installation documentation referenced above that is developed by the Subcontractor will be submitted to the QA Engineer for review. Copies of this documentation will be included as

part of the Cap Geosynthetics QA Report prepared by the Independent QA Engineer. The Cap Geosynthetics QA Report for the subgrade preparation shall, at a minimum, include the following:

- Documentation of qualifications of all contractors and CQA personnel.
- Daily reports prepared by the QA Engineer;
- Subgrade acceptance certificates for each area to be covered by the cap system, signed by the Geosynthetics Installer, the Subcontractor, and QA Engineer;
- Daily construction progress reports clearly showing subgrade preparation; and
- Quality control documentation, as detailed in this CQA Plan.

### 4.3 Gas Venting System

The gas vent layer shall be comprised of a layer of geocomposite drainage material and a gooseneck-shaped vent to facilitate communication between soil gas under the cap and the atmosphere. This gas venting system is shown on drawings C-121 and C-301 in "100% Specifications and Design Drawings."

Section 02374 from "100% Specifications and Design Drawings" is summarized on Table 1 and indicates the requirements for the geocomposite gas venting layer. Requirements include, but are not limited to:

- Packaging, shipment, and storage of material;
- Handling and placement requirements;
- Seaming procedures; and
- Material repairs.

The specification requirements for the goose-neck shaped vent, which have been provided in Section 02380 in "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Gas vent pipe materials; and
- Installation of the pipes via pipe laying, jointing, and pipe cutting.

#### 4.3.1.1 Quality Assurance

The GDL and gas vent QA/QC forms have been provided as Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Sections 02372 and 02380, provided in "100% Specifications and Design Drawings," and note deviations from technical specifications;
- Observe subgrade preparation;
- Overlapping of geocomposite and connection procedures;
- Material repairs;
- Observe pipe materials handling and storage;
- Observe installation of gas vent system; and
- Review of QC Documents to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Contractor will be submitted to the QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the QA Engineer. The Cap Geosynthetics QA Report for the geocomposite layer shall, at a minimum, include the following:

- Documentation of qualifications of all installers and CQA personnel;
- Daily reports prepared by the QA Engineer; and
- Daily construction progress reports clearly showing geocomposite and piping materials placed by date.

### 4.4 Geomembrane Layer

The geomembrane selected for use in the cover system is a 60-mil (0.060 inch) thick LLDPE. A microspike double-sided textured geomembrane has been approved for use on this project. Work shall consist of installing the LLDPE geomembrane and the overlying geocomposite in the areas as shown on the construction drawing C-301 provided in "100% Specifications and Design Drawings."

The specification requirements for the geomembrane layer, which have been provided in Section 02372 of "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Packaging, shipment, and storage of material;
- Handling and placement requirements;
- Non-destructive and destructive seam testing procedures; and
- Material repairs.

#### 4.4.1 Quality Assurance

Prior to the start of capping activities the geosynthetic installer shall provide the Design and Independent QA Engineers with a panel layout drawing.

The Subcontractor's installer shall furnish the certified test results for all geomembrane to be used to the EOR, or EOR representative, for review as part of the required shop submittals prior to shipment to the site. The EOR, or EOR representative, will review the test results for conformance with the criteria included in the contract specifications.

The geomembrane layer QA/QC forms have been provided as Appendix A. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Section 02372 provided in "100% Specifications and Design Drawings" and note deviations from technical specifications;
- Review subgrade preparation and approval to place geomembrane materials;
- Observe effect of weather conditions on geomembrane installation;
- Seam preparation;
- Seaming equipment and procedures;
- Overlapping and temporary bonding;
- Test seams;
- Non-destructive and destructive seam testing;

- Penetration sealing observations for gas vents, piezometers, and groundwater collection system manhole to the LLDPE.
    - Note cap to barrier exterior detail will be observed and documented by AmecFW field engineering representative.
- Repair procedures and testing ;
    - Defective areas may include:
        - Large holes, tears, cold bends, cracks, etc.:
        - Other localized flaws;
        - Small to large tears and large lengths of failed seams;
        - Areas of inadequate seams; and
- Documentation to demonstrate compliance.

Testing and installation documentation referenced above that is developed by the Capping System Subcontractor will be submitted to the QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the Independent QA Engineer. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The Cap Geosynthetics QA Report for the geomembrane layer shall, at a minimum, include the following:

- Summary of required submittals, documentation, and QC testing results outlined in Contractor's Construction Quality Assurance Plan (CQA)
- Daily reports prepared by the Quality Assurance Engineer.
- Record drawing(s) (panel layout with all associated data) received and approved by the QA Engineer.
- Subgrade acceptance certificates for each area to be covered by the cap system, signed by the Contractor's Installer and the Contractor.
- Relevant completed QA data sheets from Appendix A.

### 4.5 Geocomposite Drainage Layer 2 (Surface water infiltration drainage)

The cap cross-section will utilize two layers of drainage net. The geocomposite drainage layers (GDLs) will be both directly above and below the 60-mil geomembrane layer as shown on drawing C-301 in "100% Specifications and Design Drawings." The GDL above the membrane is allow for drainage and transport of infiltrated surface water, and the GDL below the membrane is for gas venting. This section focuses on the installation of the GDL above the membrane.

The specification requirements for the geomembrane layer, which have been provided in Section 02374 in "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Packaging, shipment, and storage of material;
- Handling and placement requirements;
- Seaming procedures;
- Material repairs; and
- Cover soil placement for the GDL above the geomembrane.

### 4.5.1 Quality Assurance

The geocomposite manufacturer shall provide certified copies of laboratory test results on the following specifications listed in Appendix A.

The Construction Contractor will furnish the certified test results for all geocomposite placed to the QA Engineer for review as part of the required shop submittals. The EOR, or EOR representative, will review the test results for conformance with the criteria included in the contract specifications.

The GDL QA/QC forms have been provided as Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Section 02372 of "100% Specifications and Design Drawings" and note deviations from technical specifications;
- Observe subgrade preparation;
- Overlapping and connection procedures;
- Material repairs; and
- Documentation to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Capping System Subcontractor will be submitted to the Independent QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the Independent QA Engineer. The report sections outlining the geocomposite layer shall, at a minimum, include the following:

- Daily reports prepared by the Independent QA Engineer; and
- Daily construction progress reports clearly showing geocomposite placed by date.

## 4.6 Root Barrier

The capping system shall contain a woven geotextile root barrier layer. This barrier layer is located directly above the GDL cover soil layer, as indicated in drawing C-301 in "100% Specifications and Design Drawings."

The specification requirements for the geotextile layer, which have been provided in Section 02373 of "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Product materials;
- Application of geotextile; and
- Installation of geotextile fabrics.

### 4.6.1 Quality Assurance

The QA/QC forms have been provided as Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Section 02373 of "100% Specifications and Design Drawings" and note deviations from technical specifications;
- Observe geotextile installation;
- Overlapping;
- Material repairs; and
- Documentation to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Contractor will be submitted to the QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the QA Engineer. The relevant sections of report outlining the geotextile layer shall, at a minimum, include the following:

- Daily reports prepared by the QA Engineer; and
- Daily construction progress reports clearly showing geotextiles placed by date.

## 4.7 Geosynthetic Clay Liner

The geosynthetic clay liner (GCL) shall be used as a secondary hydraulic barrier in locations where the cap may be submerged below the groundwater table, as indicated on drawing C-309 provided in "100% Specifications and Design Drawings."

The specification requirements for the clay liner, which have been provided in Section 02375 in "100% Specifications and Design Drawings" as well as summarized on Table 1, includes, but are not limited to:

- Material delivery, handling, and storage;
- GCL placement;
- Seaming; and
- Damage repairs.

### 4.7.1 Quality Assurance

The various technical specifications pertaining to the GCL are outlined within the QA/QC forms contained within Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, but are not limited to:

- Confirm work has been completed in accordance with Specification Section 02375 and note deviations from technical specifications;
- Observe geotextile installation;
- Observe overlapping and seaming of GCL;
- Material repairs;

- Observe GCL hydration; and
- Documentation to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Contractor will be submitted to the Independent QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the QA Engineer. The certification report for the GCL shall, at a minimum, include the following:

- Daily reports prepared by the QA Engineer; and
- Daily construction progress reports clearly showing GCL placed by date.

### 4.8 Earthwork

As shown on drawing C-301 in "100% Specifications and Design Drawings," the soil materials used in the construction of this capping system consist of the following layers:

- Geocomposite drainage soil;
- Planting soil layers consisting of topsoil underlain by soil layers capable of support tree and shrub growth;
- Structural fill to be placed under roadways;
- Common borrow placed in select areas under roadways or to raise the subgrade to appropriate elevations.

The relevant quality control/quality assurance observations and specifications governing placement and testing of each layer are summarized in a separate Construction Quality Control Plan prepared by AmecFW.

## 5.0 CAP GEOSYNTHETICS QA REPORT

The QA Engineer in conjunction with the EOR and Contractor shall prepare a Cap Geosynthetic QA Report documenting work completed in this CQA Plan. This report shall contain at a minimum:

- As-built drawings from the Contractor;
- Conformed technical specifications from the EOR;
- Summary of DCB, submittals, and RFIs by the EOR;
- Reference to the QC data reported by the Contractor;
- Summary of QA/QC forms outlined in Appendix A prepared by the Independent QA Engineer and Contractor; and
- Photographic logs and QA/QC forms by the Independent QA Engineer.

# Tables

Table 1 – Geosynthetic Material Testing Methods & Frequency

ENTACT

**TABLE 1: GEOSYNTHETIC MATERIAL TESTING METHODS & FREQUENCY**
**Honeywell SA6 South**
**Jersey City, New Jersey**

| Materials to be Tested | Sample Location | Parameter | Test Method | Frequency | Value | Specification/ Reference | Notes | QC Tests Needed | QC Tests Completed | QA Tests Completed | Material Quantity |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **60 mil LLDPE MicroSpike Double Sided Geomembrane** | Manufacturer - AgruAmerica | *Conformance Testing:* | | | | | | | | | ***394,910 Square Feet*** |
| | | Thickness | ASTM D5994 | 1/roll | 57 MARV | 02372-2.02 and Table 02372-1 | | 34 | 0 | 0 | ***34 rolls*** |
| | | Density | ASTM D1505/D792 | 1/200,00 lbs | 0.939 g/cc | | Density value change approved per Submittal 091 | 1 | 0 | 0 | ***129,200 lbs*** |
| | | Tensile Properties | ASTM D6693 | 1/20,000 lbs | 90 lbs/in (strength)/250% elongation | | | 7 | 0 | 0 | |
| | | Tear Resistance | ASTM D1004 | 1/45,000 lbs | 33 lbs | | | 3 | 0 | 0 | |
| | | Puncture Resistance | ASTM D4833 | 1/45,000 lbs | 66 lbs | | | 3 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603 | 1/20,000 lbs | 2%-3% | | | 7 | 0 | 0 | |
| | | Carbon Black Dispersion | ASTM D5596 | 1/45,000 lbs | 9 in Cat 1 or 2 and 1 in Cat 3 | | | 3 | 0 | 0 | |
| | | Asperity Height | ASTM D7466 | 1/Second roll | 10 mils (min) | | Asperity Test Method change approved per Submittal 091 | 17 | 0 | 0 | |
| | | Oxidative Induction Time | ASTM D3895 | 1/100,000 lbs | 100 minutes | | | 4 | 0 | 0 | |
| | QC Laboratory - Geotechnics | *3rd Party Laboratory Testing* | | | | | | | | | |
| | | Thickness | ASTM D5994 | 1/100,000 square feet | 57 MARV | 02372-2.02 and Table 02372-1 | | 4 | 0 | 0 | |
| | | Density | ASTM D1505/D792 | 1/100,000 square feet | 0.939 g/cc | | Density value change approved per Submittal 091 | 4 | 0 | 0 | |
| | | Tensile Properties | ASTM D6693 | 1/100,000 square feet | 90 lbs/in (strength)/250% elongation | | | 4 | 0 | 0 | |
| | | Tear Resistance | ASTM D1004 | 1/100,000 square feet | 33 lbs | | | 4 | 0 | 0 | |
| | | Puncture Resistance | ASTM D4833 | 1/100,000 square feet | 66 lbs | | | 4 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603 | 1/100,000 square feet | 2%-3% | | | 4 | 0 | 0 | |
| | | Carbon Black Dispersion | ASTM D5596 | 1/100,000 square feet | 9 in Cat 1 or 2 and 1 in Cat 3 | | | 4 | 0 | 0 | |
| | | Asperity Height | ASTM D7466 | 1/100,000 square feet | 10 mils (min) | | Asperity Test Method change approved per Submittal 091 | 4 | 0 | 0 | |
| | | Interface Strength | ASTM D5321 | 1/100,000 square feet | Peak = 26 degrees; Residual = 22.5 degrees | | | 4 | 0 | 0 | |
| | | *Field Quality Control Testing:* | | | | | | | | | |
| | | Start-Up Testing Peel (Tensiometer) | ASTM D6392 | Start of each shift and every 5 hrs | 66 lb/in & FTB (extrusion weld); 75 lb/in & FTB (fusion weld) | 02372-3.06.A.1 | Test 3 peel/3 shear | 100% | 0 | 0 | |
| | | Start-Up Testing Shear (Tensiometer) | ASTM D6392 | Start of each shift and every 5 hrs | 90 lb/in | 02372-3.06.A.1 | Test 3 peel/3 shear | 100% | 0 | 0 | |
| | | Non-Destructive Field Seam Continuity Testing | Vacuum Testing | Full seam length (extrusion weld) | No bubbles in viewing window for 10 seconds | 02372-3.06.B.2 | | 100% | 0 | 0 | |
| | | Non-Destructive Field Seam Continuity Testing | Air Pressure Testing | Full seam length (fusion weld) | <4 psi pressure loss over 5 min @ 25-30 psi pressure | 02372-3.06.B.3 | | 100% | 0 | 0 | |
| | | Destructive Testing Shear (Tensiometer) | ASTM D6392 | 1/500 ft of seam | 66 lb/in & FTB (extrusion weld); 75 lb/in & FTB (fusion weld) | 02372-3.07.D | Test 3 peel/3 shear | 35 | 0 | 0 | |
| | | Destructive Testing Peel (Tensiometer) | ASTM D6392 | 1/500 ft of seam | 90 lb/in | 02372-3.07.D | Test 3 peel/3 shear | 35 | 0 | 0 | |
| | Lab QC-Geotechnics | Destructive Testing Shear (Laboratory) | ASTM D6392 | 1/500 ft of seam | 66 lb/in & FTB (extrusion weld); 75 lb/in & FTB (fusion weld) | 02372-3.07.E | Test 5 peel/5 shear. 5 out of 5 must pass peel and shear | 35 | 0 | 0 | |
| | | Destructive Testing Peel (Laboratory) | ASTM D6392 | 1/500 ft of seam | 90 lb/in | 02372-3.07.E | Test 5 peel/5 shear. 5 out of 5 must pass peel and shear | 35 | 0 | 0 | |
| ***Transnet 33-2-6 Geocomposite w/Warning Layer (Drainage Layer)*** | Manufacturer - SKAPS | *Conformance Testing:* | | | | 02374-2.2.A | | | | | ***394,800 Square Feet*** |
| | | **Resin** | | | | | | | | | ***141 Rolls*** |
| | | Polymer Density | ASTM D1505 | 1/lot | >0.94 g/cm3 | | | TBD | | | |
| | | Melt Flow Index | ASTM D1238 | 1/lot | ≤1.0 g/10 min | | | TBD | | | |
| | | **Geonet** | | | | | | | | | |
| | | Thickness, min avg | ASTM D5199 | 1/50,000 sf | 200 mil | | | 8 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603/D4218 | 1/50,000 sf | 2-3% | | | 8 | 0 | 0 | |
| | | Tensile Strength, MD | ASTM D7179 | 1/50,000 sf | 45 lbs/in | | Most current ASTM test method for tensile strength | 8 | 0 | 0 | |
| | | **Geotextile** | | | | | | | | | |
| | | Mass/Unit Area, MARV | ASTM D5261 | 1/100,000 sf | 6 oz/sy | | | 4 | 0 | 0 | |
| | | Grab Tensile, MARV | ASTM D4632 | 1/100,000 sf | 158 lbs | | | 4 | 0 | 0 | |
| | | Tear Strength, MARV | ASTM D4533 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Puncture Strength, MARV | ASTM D4833 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Permittivity, MARV | ASTM D4491 | 1/500,000 sf | 0.5 $sec^{-1}$ | | | 1 | 0 | 0 | |
| | | AOS, US Sieve | ASTM D4751 | 1/500,000 sf | 0.25 mm | | | 1 | 0 | 0 | |
| | | UV Resistance | ASTM D4355/G 154 | 1/resin formulation | 90% retained after 500 hrs | | | 1 | 0 | 0 | |
| | | **Geocomposite** | | | | | | | | | |
| | | Transmissivitiy, min | ASTM D4716 | 1/200,000 sf | $8.0x10^{-4}$ | | Normal compressive load load should be 750 psf at gradient of 0.316 | 2 | 0 | 0 | |
| | | Ply Adhesion, min avg | ASTM D7005 | 1/100,000 sf | 0.5 lbs/in | | Ply AdhesionTest Method change approved per Submittal 081 | 4 | 0 | 0 | |
| | QC Laboratory - Geotechnics | *Testing with Site Specific Soils* | | | | | | | | | |
| | | Interface - GDL/Geomembrane | ASTM D5321 | 1/100,000 sf | | 02374-2.3 | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| | | Interface - GDL/Cover Soil (Celgene) | ASTM D5321 | 1/100,000 sf | Peak = 26 degrees; Residual = 22.5 degrees | | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| | | Transmissivity | ASTM D4716 | 1/100,000 sf | 8.0x10-4 | | Normal compressive load load should be 750 psf at gradient of 0.316 | 4 | 0 | 0 | |

| Materials to be Tested | Sample Location | Parameter | Test Method | Frequency | Value | Specification/ Reference | Notes | QC Tests Needed | QC Tests Completed | QA Tests Completed | Material Quantity |
|---|---|---|---|---|---|---|---|---|---|---|---|
| ***Transnet 22-2-6 Geocomposite (Gas Vent System)*** | Manufacturer - SKAPS | *Conformance Testing:* | | | | 02374-2.2.A | | | | | ***311,750 Square Feet*** |
| | | **Resin** | | | | | | | | | ***86 Rolls*** |
| | | Polymer Density | ASTM D1505 | 1/lot | >0.94 g/cm3 | | | TBD | 0 | 0 | |
| | | Melt Flow Index | ASTM D1238 | 1/lot | ≤1.0 g/10 min | | | TBD | 0 | 0 | |
| | | **Geonet** | | | | | | | | | |
| | | Thickness, min avg | ASTM D5199 | 1/50,000 sf | 200 mil | | | 7 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603/D4218 | 1/50,000 sf | 2-3% | | | 7 | 0 | 0 | |
| | | Tensile Strength, MD | ASTM D7179 | 1/50,000 sf | 45 lbs/in | | Most current ASTM test method for tensile strength | 7 | 0 | 0 | |
| | | **Geotextile** | | | | | | | | | |
| | | Mass/Unit Area, MARV | ASTM D5261 | 1/100,000 sf | 6 oz/sy | | | 4 | 0 | 0 | |
| | | Grab Tensile, MARV | ASTM D4632 | 1/100,000 sf | 158 lbs | | | 4 | 0 | 0 | |
| | | Tear Strength, MARV | ASTM D4533 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Puncture Strength, MARV | ASTM D4833 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Permittivity, MARV | ASTM D4491 | 1/500,000 sf | 0.5 $sec^{-1}$ | | | 1 | 0 | 0 | |
| | | AOS, US Sieve | ASTM D4751 | 1/500,000 sf | 0.25 mm | | | 1 | 0 | 0 | |
| | | UV Resistance | ASTM D4355/G 154 | 1/resin formulation | 90% retained after 500 hrs | | | TBD | | | |
| | | **Geocomposite** | | | | | | | | | |
| | | Transmissivitiy, min | ASTM D4716 | 1/200,000 sf | $8.0x10^{-4}$ | | Transmissivity requirement for gas vent system deleted per Addendum #5; Clarification #3 | 2 | 0 | 0 | |
| | | Ply Adhesion, min avg | ASTM D7005 | 1/100,000 sf | 0.5 lbs/in | | Ply Adhesion Test Method change approved per Submittal 081 | 4 | 0 | 0 | |
| | QC Laboratory - Geotechnics | *Testing with Site Specific Soils* | | | | | | | | | |
| | | Interface - GVS/Geomembrane | ASTM D5321 | 1/100,000 sf | | 02374-2.3 | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| | | Interface - GVS/Subgrade Soil | ASTM D5321 | 1/100,000 sf | Peak = 26 degrees; Residual = 22.5 degrees | | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| ***Bentomat DN Geosynthetic Clay Liner*** | Manufacturer - CETCO | *Manufacturer Certification:* | | | | | | | | | ***69,600*** |
| | | **Geotextile** | | | | 02375 - Tables 1 & 2 | | | | | ***32 Rolls*** |
| | | Mass/Unit Cap, MARV (Non-Woven) | ASTM D5261 | 1/200,000 sf | 6.0 oz/sy | | | 1 | 0 | 0 | ***83,200 lbs*** |
| | | Mass/Unit Carrier, MARV (Non-Woven) | ASTM D5261 | 1/200,000 sf | 6.0 oz/sy | | | 1 | 0 | 0 | |
| | | **Bentonite** | | | | | | | | | |
| | | Swell Index | ASTM D5890 | 1/100,000 lb | 24 ml min | | | 1 | 0 | 0 | |
| | | Moisture Content | ASTM D4643 | 1/100,000 lb | 35% max | | | 1 | 0 | 0 | |
| | | Fluid Loss | ASTM D5891 | 1/100,000 lb | 18 ml max | | | 1 | 0 | 0 | |
| | | **Finished GCL** | | | | | | | | | |
| | | Mass/Unit Area Bentonite | ASTM D5993 | 1/40,000 sf | 0.75 lb/sf MARV | | | 2 | 0 | 0 | |
| | | Tensile Strength, MD | ASTM D6768 | 1/40,000 sf | 50 lb/in MARV | | Testing frequency change approved per Submittal 092 | 2 | 0 | 0 | |
| | | Peel Strength | ASTM D6496 | 1/40,000 sf | 12 lb/in MARV | | | 2 | 0 | 0 | |
| | | | ASTM D4632 | 1/40,000 sf | 60 lb MARV | | | 2 | 0 | 0 | |
| | | Hydraulic Conductivity | ASTM D5887 | 1/Week | $5 \times 10^{-11}$ m/sec | | | TBD | | | |
| | | Index Flux | ASTM D5887 | 1/Week | $1 \times 10^{-8}$ $m^3/m^2$/sec | | | TBD | | | |
| | | Internal Shear Strength | ASTM D6243 | Periodically | 150 psf Typical (non-slope areas); 500 psf Typical | | | 1 | | | |
| | | | | | | | | | | | |

# Appendix A

# QA/QC Forms

A1 – Certification of Completion
A2 – Receiving Inspection Report Table
A3 – Individual Photographic Log
A4 – Geosynthetics Inventory and Certification Log
A5 – Subgrade Surface Checklist
A6 – Trial Weld Log
A7 – Panel Placement Log
A8 – Seam Testing Chain of Custody Form
A9 – Seam Control and Non-Destructive Test Log
A10 – Repair Log
A11 – Conformance Test Chain of Custody Form
A12 – Destructive Seam Field Test
A13 – Destructive Sample Tracking Summary
A14 – Penetration Sealing Observation / Cap to Barrier Installation Observation
A15 – Geosynthetic Daily Inspection
A16 – Notice of Non-Compliance and Corrective Action Form

# Appendix A1

# Certification of Completion

LANGAN

# Certificate of Completion

Sheet # _____

| | | | | | |
|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | |
| Project No. | | Layer | Primary | Secondary | Tertiary |
| Owner/ Contr. | | Type | Partial | Substantial | Final |
| QA Monitor | | Date | | | |

| Description and Area of Work Being Certified: |
|---|
| |

I hereby certify that the above identified work has been inspected and it has been properly installed. I further certify all required testing has been completed and the results are acceptable to the CQA Officer. The liner system is suitable for its intended use.

| **Independent CQA Monitor** | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | |

| **Geosynthetic Installer Representative** | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | |

| **Owner Representative** | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | |

| Notes, Observations, Comments: |
|---|
| |

# PROJECT COMPLETION REPORT

Project Name: _____ Project Manager: _____

Job Number: _____ Superintendent: _____

Date Completed: _____

| Item Number | Item Description | Completed Quantity |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | Total Linear Feet of Anchor Trench | |
| | Vertical Feet of Liner in Trench (per Detail) | |

| Item Number | Item Description | Completed Quantity |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | Total Linear Feet of Tie in to Existing | |
| | Total Linear Feet of Tie in Slope to Floor | |

The Quantities Listed Above Are Based On The Following :

- ☐ Field measurements
- ☐ Quantities are agreed to at this time
- ☐ Quantities listed include geosynthetics in anchor trench
- ☐ Job 100% complete
- ☐ Field change orders were Issued How Many? _____

**Check All Applicable Boxes Below:**

- ☐ Quantities listed include tie in / run out details
- ☐ Quantities to be verified by survey
- ☐ Quantities listed are per completed survey
- ☐ Job is partially complete.
- ☐ Anticipated remob date is: _____

☐ The project has been left, by ESI, in a clean and orderly fashion acceptable to customer.

_____
Initial by Customer / Rep

☐ All work has been found satisfactorily completed and the work satisfies the Project plans and specifications

_____
Initial by Customer / Rep

**ESI Owned Materials Left On Site**

| Material Description | Roll Count | Total Square Feet | Notes |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

_____
ESI Superintendent Signature

_____
Print Name

_____
Date

_____
Authorized Signature

_____
Print Name

_____
Title / Company

_____
Date

*Rev 2-10-10*

# Appendix A2

# Receiving Inspection Report Table

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: | | | | | | | | | Contract Number: |
| Received From: | | | | | | | | | Receiving Report Number: |
| Address: | | | | | | | | | Date: |
| QC Inspection by: | | QC Date: | | Inv. Or Packing Slip No.: | | Inv. Or Packing Slip Date: | | | PO Number: |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Reels | Total Packages | Received By: |
| | | | | | | | | | Received At: |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | | | | | |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: | | Car # | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.: | Freight Bill (Pro) No.: | Weight: | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# Appendix A3

# Individual Photographic Log

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** |
|---|---|---|
| **Date:** | | |
| **Direction Taken:** | | |
| **Description:** | | |

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

PHOTOGRAPHIC LOG
Photo #

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** |
|---|---|---|
| **Date:** | | |
| **Direction Taken:** | | |
| **Description:** | | |

# Appendix A4

# Geosynthetics Inventory and Certification Log

LANGAN

# Geosynthetics Inventory and Certification Log

Sheet # _____

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | | | | |
| Project No. | | Layer | Primary | | Secondary | | | Tertiary |
| Owner/ Contr. | | Material Type: | HDPE | GN | GT | GC | GCL | OTHER |
| QA Monitor | | Texture: Smooth | | | Thickness: | | Width: | |

| Roll Number | Lot/Batch Number | Roll Length | Roll Area | Date Roll Received | Date Cert.'s Received | Date Roll Approved |
|---|---|---|---|---|---|---|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| Total | | - | - | | | |
| Running Total | | | - | | | |
| Notes, Observations, Comments: | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Geosynthetic Installer Representative _____ Date _____

Independent CQA Monitor _____ Date _____

# Appendix A5

# Subgrade Surface Checklist & Data Sheet

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: _____ PROJECT NO: _____

LOCATION: _____

AREA ACCEPTED: _____

PANEL NUMBERS: _____

GRADE ACCEPTANCE: INSPECTOR: _____

GENERAL CONTRACTOR: _____

OWNER: _____

AUTHORIZED REPRESENTATIVE: _____

The undersigned, _____,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on _____ and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| _____ | _____ | _____ |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| _____ | _____ | _____ |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# Appendix A6

# Trial Weld Log

# Environmental Specialties International, Inc.
## Preweld Test Report

Page _____ of _____

**Project Name:** _____ **Job #** _____ **Superintendent:** _____

**Material Type:** _____

**Job Description:** _____

**Reported By** _____ **Other** _____

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

**Pond** ☐ **Cell** ☐ **Cap** ☐

**Peel Test Extrusion Minimum** _____ PPI

**Peel Test Fusion Minimum** _____ PPI

**Shear Test Minimum** _____ PPI

| Weld Date / Liner Type | Time am \| pm | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A \| B | Coupon 2 A \| B | Coupon 3 A \| B | Coupon 4 A \| B | Coupon 5 A \| B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |

# Appendix A7

# Panel Placement Log

# Daily Panel Placement

Page ____

Project Name: Honeywell Job # 12-11-1399 Deployment Date ____

Superintendent: Fortino Ayala Material Type: LLPE 60 MIL

[ ] Primary Secondary [ ] Cell [ ] Pond [ ] Cap [X] Other: ____

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 22.5

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| | Final Length Avg. | | LF |
| | Final Width Avg. | | LF |
| | Initial Length Avg. | | LF |
| | Initial Width Avg. | | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | - | SF |
| **Total Pay Area This Page** | - | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | - | SF |
| Total Panel SF To Date | - | SF |
| **Total Pay Area To Date Including Anchor Trench** | - | |
| Initial Quantity Previous | - | SF |
| Initial Quantity This Page | - | SF |
| Initial Quantity To Date | - | SF |

# Appendix A8

# Seam Testing Chain of Custody Form

## SEAM TESTING
# CHAIN OF CUSTODY FORM

SEND YOUR SEAMS TO

PROJECT NAME / PROJECT NUMBER: _____
PROJECT LOCATION: _____

| No. | Seam ID (Include Seam ID, Panel ID, welder, etc.) | MATERIAL DESCRIPTION | FUSION | EXTRUSION | Solvent Weld |
|---|---|---|---|---|---|
| 1 | | | | | |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |

TEST METHOD
*(Please check which test method is applicable)*

O SHEAR – ASTM 04437
PEEL – ASTM 04437

O SHEAR – ASTM 06214
PEEL – ASTM 06214

O SHEAR – ASTM 04437 NSF Modified
Crosshead Speed = 2"/min
PEEL – ASTM 04437 NSF Modified
Crosshead Speed = 2"/min

O SHEAR – ASTM 04437 NSF Modified
Crosshead Speed = 20"/min
PEEL – ASTM 04437 NSF Modified
Crosshead Speed 20"/min

O SHEAR – ASTM 06392
PEEL – ASTM 06392
HDPE

O SHEAR – ASTM 03083
Crosshead Speed = 20"/min
PEEL – ASTM 0413
Crosshead Speed = 2"/min

O SHEAR – ASTM 06392
PEEL – ASTM 06392
LLDPE/PVC

O SHEAR – ASTM 0751
PEEL – ASTM 0413
Crosshead Speed = 2"/min

SPECIFICATIONS/NOTES:
OPEN on SATURDAYS for SEAM TESTING.
To ensure that your package is delivered/received on Saturdays; please fax, e-mail or call to let us know the AIRBILL # of your package. This helps us track for SATURDAY DELIVERY.

Thickness required? O Yes O NO
SOLVENT WELD
Curing Time: _____ Curing Temp:_____

**REPORT TO:**
Name: _____
Company: _____
Address: _____
_____
Tel No.: _____
Fax No.: _____
E-mail: _____

**FIELD CONTACT:**
Name: _____
Pager: _____
Mobil: _____
Phone: _____
Fax: _____
E-mail: _____

**RELEASED BY:**
Name: _____
Company: _____
Date/Time: _____

**RECEIVED BY:**
Name: _____
Precision Geosynthetic Labs
Date/Time: _____

**Shipped Via**
O Fedex
O UPS
O Airborne
O DHL
O US Mail
O Hand Carry
O Others

# Appendix A9

# Seam Control and Non-Destructive Test Log

# Environmental Specialties International, Inc.

## Seam Control Form

Page _____ of _____

**Project Name:** _____ **Job #** _____ **Superintendent:** _____

**Material Type:** _____ **Cell** ☐ **Air Pressure Test** _____ **PSI**

**Job Description:** _____ **Pond** ☐ **Air Pressure Hold Time** _____ **Minutes**

**Reported By** _____ **Other** _____ **Cap** ☐ **Allowable Air Pressure Loss** _____ **PSI**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |

# Appendix A10

# Repair Log

# Environmental Specialties International, Inc.
## Repair Report

Page _____ of _____

**Reported By:** _____ **Superintendent:** _____ **Job # :** _____

**Project Name:** _____ **Cell** ☐ **Cap** ☐

**Material Type:** _____ **Pond** ☐ **Other** _____

**Job Description:** _____

| **Damage Codes** | | | | **SF Patch Material** | **Test Type** | **Abbrv.** | **Repair Types** |
|---|---|---|---|---|---|---|---|
| CR –Crease | BO –Burn Out | PB –Pipe Boot | CF –Custom Fit | | Vacuum | *S=South | C--Cap Strip |
| DS –Destruct Sample | FS --Failed Seam | MatD –Material Defect | LL –Lost Lap | | Air Pressure | *N=North | P--Patch |
| SI –Subgrade Irregularity | WR –Wrinkle | WS –Welder Restart | MD –Mechanical Damage | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ –Seam Joint | AV –Airvent | RW –Roller Wrinkle | DO –Damage By Others | | Air Lance | *E=East | |
| | AO –Add On | FM –Fishmouth | AT –Air test | | | | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |

# Appendix A11

# Conformance Test Chain of Custody Form

# CONFORMANCE TEST CHAIN OF CUSTODY FORM

Page _____ of _____

PROJECT NAME / PROJECT NUMBER: _____

PROJECT LOCATION: _____

**GEOMEMBRANE TESTING**

| Sample ID | Thickness ASTM D5199 or D5994 | Density ASTM D1505 Or D792 | Carbon Black Content ASTM D1603 | Carbon Dispersion D3015 / D5596 | Tensile ASTM D638 GM13 / NSF54 | Tear Resistance ASTM D1004 (Die C) | Puncture D4833 /101CM2065 | Melt Flow Index ASTM D1238, cond. E | Dimensional Stability ASTM D1204 | Low Temp. Brittleness D746 / D1790 | NCTL ASTM D5397 Hours _____ | Other ASTM _____ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

## NONWOVEN OR WOVEN GEOTXTILE TESTING

| Sample ID | Thickness ASTM D5199 Or D1777 | Mass Per Area ASTM D5261 or D3776 | Grab Tensile ASTM D4632 | Trapezoid Tear ASTM D4533 | Puncture Resistance ASTM D4833 | Mullen Burst ASTM D3776 | Permittivity ASTM D4491 | AOS ASTM D4751 | Wide Width Tensile ASTM D4595 | UV (hrs _____) ASTM D4355 | Other ASTM _____ | Other ASTM _____ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

## GEOCOMPOSITE / GEONET / GEOGRID TESTING

| Sample ID | Thickness ASTM D5199 or D1777 | Density ASTM1505 or D792 | Carbon Black Content ASTM D1603 | Mass Per Area ASRM D5261 or D3776 | Melt Flow Index ASTM D1238, cond. E | Peel ASTM D413 F904 or GRI-GC7 | Transmissivity* ASTM D4716 | Compression ASTM D1621 | Tensile Strength ASTM D1682 or D5035 | Wide Width Tensile ASTM D4595 | Rib Tensile Strength GRI-GG1 | Junction Strength GRI-GG2 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

* Transmissivity Test Parameters: Normal Load: _____, Gradient: _____, Seating Time: _____, Boundary Condition: _____

# CONFORMANCE TEST CHAIN OF CUSTODY FORM

Page _____ of _____

| **REPORT TO:** | **FIELD CONTACT:** | **Released by:** | **Shipped Via:** |
|---|---|---|---|
| Name: _____ | Name: _____ | Name: _____ | O Fedex |
| Company: _____ | Pager: _____ | Date/Time: _____ | O UPS |
| Address: _____ | Mobil: _____ | **Received by:** | O Airborne |
| _____ | Phone: _____ | Name: _____ | O DHL |
| Tel No.: _____ | Fax: _____ | PGL | O US Mail |
| Fax No.: _____ | E-mail: _____ | Date/Time: _____ | O Others |
| E-mail: _____ | | | |

# Appendix A12

# Destructive Seam Field Test

# Environmental Specialties International, Inc.
## Destructive Sample Information

Page _____ of _____

**Project Name:** _____ **Job #** _____ **Superintendent:** _____

**Material Type:** _____

**Job Description:** _____

**Reported By** _____ **Other** _____

**Cell** ☐ **Pond** ☐ **Cap** ☐

**Peel Test Extrusion Minimum** _____ PPI

**Peel Test Fusion Minimum** _____ PPI

**Shear Test Minimum** _____ PPI

| D.S No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |
| | | | | | | | | Peel | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | | | | | | |

*Rev 2-26-10*

# Appendix A13

# Destructive Sample Tracking Summary

LANGAN

# Geosynthetic Installer
# Destructive Sample Tracking Summary

Sheet #_____

| | | | | | | |
|---|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | | Notes, Observations, Comments: |
| Project No. | | Layer | Primary | Secondary | Tertiary | |
| Owner/Contr. | | | | | | |
| QA Monitor | | | | | | |

| DS No. | Seam No. | Machine/ Operator | Date Welded | Roll No. | Lot No. | QA Monitor | Average Test Results | | | | Overall (P/F) | Comments and Subsequent Tracking No.'s |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Lab (P/F) | | Field (P/F) | | | |
| | | | | | | | Peel | Shear | Peel | Shear | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | |

LANGAN

# Independent CQA Monitor
# Destructive Sample Tracking Summary

Sheet #_____

| | | | | | | |
|---|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | | Notes, Observations, Comments: |
| Project No. | | Layer | Primary | Secondary | Tertiary | |
| Owner/Contr. | | | | | | |
| QA Monitor | | | | | | |


| DS No. | Seam No. | Machine/ Operator | Date Welded | Roll No. | Lot No. | QA Monitor | Average Test Results | | | | Overall (P/F) | Comments and Subsequent Tracking No.'s |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Lab (P/F) | | Field (P/F) | | | |
| | | | | | | | Peel | Shear | Peel | Shear | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | |


# Appendix A14

# Penetration Sealing Observations / Cap to Barrier Installation Observation

| **Project:** Study Area 6 South | **Date:** _____ |
|---|---|

QA – Gas Vent and Piezometer Penetrations








| ***Check applicable Detail:**<br>☐ Prefabricated material design dimensions<br>☐ 18-in. overlap between boot and geomembrane<br>☐ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure<br>☐ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection<br>☐ If penetration is greater than 4-in. in diameter, a second clamp shall be used.<br>☐ Boot connection field tested to ensure seal (ex. vacuum box testing) | **Location:**<br><br>**Independent CQA Monitor Signature:**<br><br>_____ |
|---|---|

**Comments:**

| **Project:** Study Area 6 South | **Date:** _____ |
|---|---|

QA – Groundwater Collection Manhole Penetration




Note - GCL only required if the boot is located in an area where the LLDPE is below the water table

| ***Check applicable Detail:**<br>☐ Note any dimension changes in comments section<br>☐ 18-in. overlap between boot and geomembrane<br>☐ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure<br>☐ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection<br>☐ If penetration is greater than 4-in. in diameter, a second clamp shall be used<br>☐ Boot connection field tested to ensure seal (ex. vacuum box testing) | **Location:**<br><br>**Independent CQA Monitor Signature:**<br>_____ |
|---|---|

**Comments:**


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** _____ |
|---|---|

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) C-121 C-309

NTS

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) C-309

NTS

| ***Check applicable Detail:**<br>☐ Box Cut Dimension<br>☐ Barrier wall clean/exposed<br>☐ Sand Bentonite Mix | **Location:** |
|---|---|
| **Comments:** | **AmecFW QA Signature:** _____ |

# Appendix A15

# Geosynthetic Daily Inspection Report

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES



# SITE OBSERVATION REPORT

| | | |
|---|---|---|
| **PROJECT No.:**<br>**PROJECT:**<br><br>**LOCATION:** | **CLIENT:**<br><br>**TASK.:** | **DATE:**<br>**WEATHER:**<br>**TIME:** |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day** |

***Site Activities***

***Non-Conformance Item / Corrective Actions***

***Action Items Pending***

***Action Items – Weekly Completions***

***Near Misses / Incidents***

***Future Activities Scheduled***

***Photograph Log***

Cc

By:

| | | |
|---|---|---|
| **PROJECT No.:**<br>**PROJECT:**<br><br>**LOCATION:** | **CLIENT:**<br><br>**TASK.:** | **DATE:**<br><br>**WEATHER:**<br><br>**TIME:** |

| **Daily QA Documents Completed** | | | | | |
|---|---|---|---|---|---|
| | Sheet #'s | Comment | | Sheet #'s | Comment |
| A2 – Receiving and Inspection | | | A11 – Conformance Test Chain of Custody | | |
| A3 – Photo Log | | | A12 – Destructive Seam Field Test | | |
| A4 – Geosynthetic Inventory Log | | | A13 – Destructive Lab Sample Tracking Summary | | |
| A5 -Subgrade Surface | | | A14 – Penetration and Edge Detail Observations | | |
| A6 – Trial Weld Log | | | A16 – Notice Non-Compliance / Corrective Action | | |
| A7 – Panel Placement Log | | | *List Others:* | | |
| A8 – Seam Testing Chain of Custody | | | | | |
| A9 – Seam / Non-Destructive Test Log | | | | | |
| A10 – Repair Log | | | | | |

# Appendix A16

# Notice of Non-Compliance and Corrective Action Form

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # _____

| General Project Information | |
|---|---|
| Project Name<br>Project No.<br>Owner/Contr.<br>QA Monitor | Date<br>Contractor in NC<br>Non-Compliance No.<br>Notes: |
| **Reference** | |
| Item<br>Specification Sec. No. | Drawing No.<br>Other: |
| **Description of Non-Compliance** | |
| Cross Reference (QA Inspection Form & Sheet No.): | |
| **Contractor's Response** | |
| | |
| **Follow Up Action Required** | |
| | |
| **Follow Up Action Taken** | |
| Cross Reference (QA Inspection Form & Sheet No.): | |

Geosynthetic Installer Representative _____ Date _____

Independent CQA Monitor _____ Date _____

# Appendix C
# SA-6 South Certificate of Completion

***LANGAN***

# Certificate of Completion

Sheet # 1

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | LLDPE Geomembrane Cap | | |
| Project No. | 100530001 | Layer | **Primary** | Secondary | Tertiary |
| Owner/ Contr. | Honeywell / AmecFW | Type | Partial | Substantial | **Final** |
| QA Monitor | Langan | Date | 12/01/2015 | | |

Description and Area of Work Being Certified: Completion of capping of SA-6 South which included: placement of GVL/GCL, placement of LLDPE geomembrane, and placement of GDL. Material was placed in accordance with the Record Drawings and project specifications. To date, the geosynthetic components of SA-6 South are complete and summarized in the *QA Completion Report*.

I hereby certify that the above identified work has been inspected and it has been properly installed. I further certify all required testing has been completed and the results are acceptable to the CQA Officer. The liner system is suitable for its intended use.

| **Independent CQA Monitor** | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 3/30/16 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| **Geosynthetic Installer Representative** | |
|---|---|
| Name: | Fortino Ayala |
| Date: | 3/30/16 |
| Title | Superintendent |
| Representing: | Environmental Specialties International Inc. |
| Signature: | |

# Appendix D: Survey Construction Details

*D1. Final Maser Subgrade Tables*
*D2. Subgrade Construction Control Grid*

# *D1. Final Maser Subgrade Tables*

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Cap Subgrade: Grid Points (Table 1.0)

| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
|---|---|---|---|---|---|---|---|---|
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2 | 685518.44 | 601481.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 3 | 685543.44 | 601481.51 | 15.3 | GRID | 7/2/2015 | 15.3 | 0.0 | Point surveyed within Tolerance |
| 4 | 685493.44 | 601506.51 | 14.2 | GRID | 7/2/2015 | 14.2 | 0.0 | Point surveyed within Tolerance |
| 6 | 685543.44 | 601506.51 | 16.6 | GRID | 7/2/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 7 | 685568.44 | 601506.51 | 17.0 | GRID | 7/2/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |
| 8 | 685468.44 | 601531.51 | 13.1 | GRID | 7/2/2015 | 13.1 | 0.0 | Point surveyed within Tolerance |
| 9 | 685493.44 | 601531.51 | 13.7 | GRID | 7/2/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 10 | 685543.44 | 601531.51 | 14.8 | GRID | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 11 | 685568.44 | 601531.51 | 15.0 | GRID | 7/2/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 12 | 685593.44 | 601531.51 | 18.1 | GRID | 7/2/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 14 | 685468.44 | 601556.51 | 13.9 | GRID | 7/2/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 15 | 685493.44 | 601556.51 | 15.9 | GRID | 7/2/2015 | 15.8 | -0.1 | Point surveyed within Tolerance |
| 16 | 685518.44 | 601556.51 | 16.7 | GRID | 7/2/2015 | 16.8 | 0.1 | Point surveyed within Tolerance |
| 17 | 685543.44 | 601556.51 | 17.0 | GRID | 7/2/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 18 | 685568.44 | 601556.51 | 14.1 | GRID | 7/2/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 19 | 685593.44 | 601556.51 | 17.4 | GRID | 7/2/2015 | 17.5 | 0.1 | Point surveyed within Tolerance |
| 20 | 685443.44 | 601581.51 | 13.3 | GRID | 7/2/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 21 | 685468.44 | 601581.51 | 14.4 | GRID | 7/2/2015 | 14.4 | 0.0 | Point surveyed within Tolerance |
| 22 | 685493.44 | 601581.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 23 | 685518.44 | 601581.51 | 16.6 | GRID | 7/2/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 24 | 685543.44 | 601581.51 | 17.5 | GRID | 7/2/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 25 | 685568.44 | 601581.51 | 17.0 | GRID | 7/2/2015 | 17.1 | 0.1 | Point surveyed within Tolerance |
| 26 | 685418.44 | 601606.51 | 11.9 | GRID | 7/2/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 27 | 685443.44 | 601606.51 | 13.8 | GRID | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 29 | 685493.44 | 601606.51 | 15.3 | GRID | 7/2/2015 | 15.3 | 0.0 | Point surveyed within Tolerance |
| 30 | 685518.44 | 601606.51 | 16.2 | GRID | 7/2/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 31 | 685543.44 | 601606.51 | 16.7 | GRID | 7/2/2015 | 16.8 | 0.1 | Point surveyed within Tolerance |
| 32 | 685393.44 | 601631.51 | 11.4 | GRID | 7/2/2015 | 11.5 | 0.1 | Point surveyed within Tolerance |
| 33 | 685418.44 | 601631.51 | 13.2 | GRID | 7/2/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 34 | 685443.44 | 601631.51 | 13.8 | GRID | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 35 | 685468.44 | 601631.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 36 | 685493.44 | 601631.51 | 14.8 | GRID | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 37 | 685518.44 | 601631.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 38 | 685543.44 | 601631.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 39 | 685393.44 | 601656.51 | 12.6 | GRID | 7/2/2015 | 12.7 | 0.1 | Point surveyed within Tolerance |
| 40 | 685443.44 | 601656.51 | 13.7 | GRID | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 41 | 685468.44 | 601656.51 | 15.6 | GRID | 7/2/2015 | 15.7 | 0.1 | Point surveyed within Tolerance |
| 42 | 685493.44 | 601656.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 43 | 685518.44 | 601656.51 | 16.6 | GRID | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 44 | 685368.44 | 601681.51 | 11.6 | GRID | 7/2/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 45 | 685393.44 | 601681.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 46 | 685443.44 | 601681.51 | 13.7 | GRID | 7/2/2015 | 13.6 | -0.1 | Point surveyed within Tolerance |
| 47 | 685468.44 | 601681.51 | 15.5 | GRID | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 48 | 685493.44 | 601681.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 49 | 685343.44 | 601706.51 | 11.0 | GRID | 7/2/2015 | 10.9 | -0.1 | Point surveyed within Tolerance |
| 50 | 685393.44 | 601706.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 51 | 685443.44 | 601706.51 | 13.6 | GRID | 7/2/2015 | 13.5 | -0.1 | Point surveyed within Tolerance |
| 52 | 685468.44 | 601706.51 | 15.4 | GRID | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 53 | 685493.44 | 601706.51 | 14.3 | GRID | 7/2/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 54 | 685318.44 | 601731.51 | 10.7 | GRID | 7/2/2015 | 10.6 | -0.1 | Point surveyed within Tolerance |
| 55 | 685368.44 | 601731.51 | 16.2 | GRID | 7/2/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 56 | 685393.44 | 601731.51 | 16.3 | GRID | 7/2/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 57 | 685443.44 | 601731.51 | 13.5 | GRID | 7/2/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 58 | 685343.44 | 601756.51 | 16.6 | GRID | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 59 | 685368.44 | 601756.51 | 16.3 | GRID | 7/2/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 61 | 685443.44 | 601756.51 | 13.5 | GRID | 7/2/2015 | 13.6 | 0.1 | Point surveyed within Tolerance |
| 62 | 685293.44 | 601781.51 | 10.5 | GRID | 7/2/2015 | 10.4 | -0.1 | Point surveyed within Tolerance |
| 63 | 685318.44 | 601781.51 | 17.4 | GRID | 7/2/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 64 | 685343.44 | 601781.51 | 16.9 | GRID | 7/2/2015 | 16.9 | 0.0 | Point surveyed within Tolerance |
| 65 | 685368.44 | 601781.51 | 16.5 | GRID | 7/2/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 66 | 685393.44 | 601781.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 67 | 685418.44 | 601781.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 69 | 685268.44 | 601806.51 | 11.0 | GRID | 7/2/2015 | 11.0 | 0.0 | Point surveyed within Tolerance |
| 70 | 685318.44 | 601806.51 | 18.1 | GRID | 7/2/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 71 | 685343.44 | 601806.51 | 17.7 | GRID | 7/2/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 72 | 685368.44 | 601806.51 | 17.1 | GRID | 7/2/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 73 | 685393.44 | 601806.51 | 16.7 | GRID | 7/2/2015 | 16.6 | -0.1 | Point surveyed within Tolerance |
| 74 | 685418.44 | 601806.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 75 | 685243.44 | 601831.51 | 12.7 | GRID | 7/2/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 77 | 685318.44 | 601831.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 78 | 685343.44 | 601831.51 | 18.3 | GRID | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 79 | 685368.44 | 601831.51 | 17.7 | GRID | 7/2/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 80 | 685393.44 | 601831.51 | 17.2 | GRID | 7/2/2015 | 17.3 | 0.1 | Point surveyed within Tolerance |
| 81 | 685243.44 | 601856.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 82 | 685268.44 | 601856.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 83 | 685293.44 | 601856.51 | 15.7 | GRID | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 85 | 685368.44 | 601856.51 | 18.0 | GRID | 7/2/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 86 | 685218.44 | 601881.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 87 | 685243.44 | 601881.51 | 16.4 | GRID | 7/2/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 88 | 685268.44 | 601881.51 | 18.7 | GRID | 7/2/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 89 | 685293.44 | 601881.51 | 18.6 | GRID | 7/2/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 90 | 685343.44 | 601881.51 | 15.2 | GRID | 7/2/2015 | 15.2 | 0.0 | Point surveyed within Tolerance |
| 91 | 685368.44 | 601881.51 | 11.8 | GRID | 7/2/2015 | 11.8 | 0.0 | Point surveyed within Tolerance |
| 92 | 685193.44 | 601906.51 | 15.5 | GRID | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 93 | 685218.44 | 601906.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 94 | 685243.44 | 601906.51 | 18.7 | GRID | 7/2/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 95 | 685268.44 | 601906.51 | 18.6 | GRID | 7/2/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 96 | 685293.44 | 601906.51 | 18.5 | GRID | 7/2/2015 | 18.4 | -0.1 | Point surveyed within Tolerance |
| 97 | 685318.44 | 601906.51 | 18.3 | GRID | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 99 | 685193.44 | 601931.51 | 15.7 | GRID | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 101 | 685243.44 | 601931.51 | 18.6 | GRID | 7/2/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 102 | 685268.44 | 601931.51 | 18.5 | GRID | 7/2/2015 | 18.4 | -0.1 | Point surveyed within Tolerance |
| 103 | 685293.44 | 601931.51 | 18.4 | GRID | 7/2/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 104 | 685168.44 | 601956.51 | 14.6 | GRID | 7/2/2015 | 14.6 | 0.0 | Point surveyed within Tolerance |
| 105 | 685193.44 | 601956.51 | 18.0 | GRID | 7/14/2015 | 18.1 | 0.1 | Point surveyed within Tolerance |
| 107 | 685243.44 | 601956.51 | 18.3 | GRID | 7/14/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 108 | 685268.44 | 601956.51 | 18.3 | GRID | 7/14/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 109 | 685293.44 | 601956.51 | 18.2 | GRID | 7/14/2015 | 18.3 | 0.1 | Point surveyed within Tolerance |
| 110 | 685143.44 | 601981.51 | 13.6 | GRID | 7/14/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 111 | 685168.44 | 601981.51 | 17.2 | GRID | 7/14/2015 | 17.3 | 0.1 | Point surveyed within Tolerance |
| 112 | 685193.44 | 601981.51 | 17.4 | GRID | 7/14/2015 | 17.5 | 0.1 | Point surveyed within Tolerance |
| 113 | 685218.44 | 601981.51 | 17.7 | GRID | 7/14/2015 | 17.8 | 0.1 | Point surveyed within Tolerance |
| 114 | 685243.44 | 601981.51 | 17.8 | GRID | 7/14/2015 | 17.9 | 0.1 | Point surveyed within Tolerance |
| 115 | 685268.44 | 601981.51 | 17.9 | GRID | 7/14/2015 | 18.0 | 0.1 | Point surveyed within Tolerance |
| 116 | 685118.44 | 602006.51 | 13.0 | GRID | 7/14/2015 | 13.1 | 0.1 | Point surveyed within Tolerance |
| 117 | 685168.44 | 602006.51 | 16.6 | GRID | 7/14/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 118 | 685193.44 | 602006.51 | 16.8 | GRID | 7/14/2015 | 16.9 | 0.1 | Point surveyed within Tolerance |
| 119 | 685218.44 | 602006.51 | 17.1 | GRID | 7/14/2015 | 17.2 | 0.1 | Point surveyed within Tolerance |
| 121 | 685268.44 | 602006.51 | 17.5 | GRID | 7/14/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 122 | 685118.44 | 602031.51 | 13.0 | GRID | 7/14/2015 | 13.1 | 0.1 | Point surveyed within Tolerance |
| 123 | 685143.44 | 602031.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 124 | 685168.44 | 602031.51 | 16.2 | GRID | 7/14/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 125 | 685193.44 | 602031.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 126 | 685218.44 | 602031.51 | 16.5 | GRID | 7/14/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 127 | 685118.44 | 602056.51 | 14.0 | GRID | 7/14/2015 | 13.9 | -0.1 | Point surveyed within Tolerance |
| 128 | 685143.44 | 602056.51 | 16.2 | GRID | 7/14/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 129 | 685168.44 | 602056.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 130 | 685193.44 | 602056.51 | 16.2 | GRID | 7/14/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 131 | 685218.44 | 602056.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 132 | 685068.44 | 602081.51 | 4.4 | GRID | 7/14/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 134 | 685143.44 | 602081.51 | 16.5 | GRID | 7/14/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 135 | 685168.44 | 602081.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 136 | 685193.44 | 602081.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 137 | 685218.44 | 602081.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 140 | 685093.44 | 602106.51 | 4.8 | GRID | 7/14/2015 | 4.9 | 0.1 | Point surveyed within Tolerance |
| 141 | 685118.44 | 602106.51 | 5.0 | GRID | 7/14/2015 | 5.1 | 0.1 | Point surveyed within Tolerance |
| 142 | 685168.44 | 602106.51 | 16.6 | GRID | 7/14/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 143 | 685193.44 | 602106.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 146 | 685143.44 | 602131.51 | 5.4 | GRID | 7/14/2015 | 5.5 | 0.1 | Point surveyed within Tolerance |
| 138 | 685043.44 | 602106.51 | 4.6 | GRID | 7/24/2015 | 4.5 | -0.1 | Point surveyed within Tolerance |
| 144 | 685068.44 | 602131.51 | 15.0 | GRID | 7/24/2015 | 15.0 | 0.0 | Point surveyed within Tolerance |
| 145 | 685118.44 | 602131.51 | 5.2 | GRID | 7/24/2015 | 5.1 | -0.1 | Point surveyed within Tolerance |
| 147 | 685043.44 | 602156.51 | 15.1 | GRID | 7/24/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 148 | 685093.44 | 602156.51 | 17.9 | GRID | 7/24/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 149 | 685143.44 | 602156.51 | 5.6 | GRID | 7/24/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 150 | 685168.44 | 602156.51 | 5.8 | GRID | 7/24/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 151 | 684993.44 | 602181.51 | 5.6 | GRID | 7/24/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 152 | 685018.44 | 602181.51 | 15.7 | GRID | 7/24/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 153 | 685043.44 | 602181.51 | 15.2 | GRID | 7/24/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 154 | 685068.44 | 602181.51 | 17.5 | GRID | 7/24/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 155 | 685093.44 | 602181.51 | 17.5 | GRID | 7/24/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 156 | 685118.44 | 602181.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 157 | 685143.44 | 602181.51 | 14.7 | GRID | 7/24/2015 | 14.7 | 0.0 | Point surveyed within Tolerance |
| 159 | 684968.44 | 602206.51 | 6.1 | GRID | 7/24/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 160 | 685018.44 | 602206.51 | 18.3 | GRID | 7/24/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 161 | 685068.44 | 602206.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 162 | 684993.44 | 602231.51 | 18.8 | GRID | 7/24/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 163 | 685018.44 | 602231.51 | 16.0 | GRID | 7/24/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 164 | 685068.44 | 602231.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 165 | 685093.44 | 602231.51 | 15.0 | GRID | 7/24/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 166 | 684968.44 | 602256.51 | 19.4 | GRID | 7/24/2015 | 19.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 167 | 684993.44 | 602256.51 | 19.1 | GRID | 7/24/2015 | 19.1 | 0.0 | Point surveyed within Tolerance |
| 168 | 685018.44 | 602256.51 | 16.3 | GRID | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 169 | 685043.44 | 602256.51 | 18.4 | GRID | 7/24/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 170 | 685068.44 | 602256.51 | 18.1 | GRID | 7/24/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 171 | 684918.44 | 602281.51 | 7.1 | GRID | 7/24/2015 | 7.2 | 0.1 | Point surveyed within Tolerance |
| 172 | 684968.44 | 602281.51 | 19.6 | GRID | 7/24/2015 | 19.6 | 0.0 | Point surveyed within Tolerance |
| 173 | 684993.44 | 602281.51 | 16.8 | GRID | 7/24/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 174 | 685018.44 | 602281.51 | 19.0 | GRID | 7/24/2015 | 19.0 | 0.0 | Point surveyed within Tolerance |
| 175 | 685043.44 | 602281.51 | 18.7 | GRID | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 176 | 685068.44 | 602281.51 | 18.4 | GRID | 7/24/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 178 | 684943.44 | 602306.51 | 20.2 | GRID | 7/24/2015 | 20.2 | 0.0 | Point surveyed within Tolerance |
| 179 | 684968.44 | 602306.51 | 19.9 | GRID | 7/24/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 180 | 684993.44 | 602306.51 | 17.1 | GRID | 7/24/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 181 | 685018.44 | 602306.51 | 19.3 | GRID | 7/24/2015 | 19.3 | 0.0 | Point surveyed within Tolerance |
| 182 | 685043.44 | 602306.51 | 16.4 | GRID | 7/24/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 183 | 684918.44 | 602331.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 184 | 684943.44 | 602331.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 185 | 684968.44 | 602331.51 | 17.6 | GRID | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 186 | 684993.44 | 602331.51 | 19.8 | GRID | 7/24/2015 | 19.8 | 0.0 | Point surveyed within Tolerance |
| 187 | 685018.44 | 602331.51 | 17.0 | GRID | 7/24/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |
| 188 | 684893.44 | 602356.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 189 | 684918.44 | 602356.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 190 | 684943.44 | 602356.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 191 | 684968.44 | 602356.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 192 | 684993.44 | 602356.51 | 17.5 | GRID | 7/24/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 193 | 684843.44 | 602381.51 | 8.7 | GRID | 7/24/2015 | 8.7 | 0.0 | Point surveyed within Tolerance |
| 194 | 684868.44 | 602381.51 | 17.4 | GRID | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 195 | 684893.44 | 602381.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 196 | 684918.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 197 | 684943.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 198 | 684968.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 199 | 684993.44 | 602381.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 200 | 684868.44 | 602406.51 | 17.0 | GRID | 7/24/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 201 | 684893.44 | 602406.51 | 17.3 | GRID | 7/24/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 202 | 684918.44 | 602406.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 203 | 684943.44 | 602406.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 204 | 684968.44 | 602406.51 | 17.8 | GRID | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 206 | 684843.44 | 602431.51 | 16.1 | GRID | 7/24/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 207 | 684868.44 | 602431.51 | 16.6 | GRID | 7/24/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 208 | 684893.44 | 602431.51 | 17.0 | GRID | 7/24/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 209 | 684918.44 | 602431.51 | 17.4 | GRID | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 210 | 684943.44 | 602431.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 214 | 684868.44 | 602456.51 | 16.3 | GRID | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 215 | 684893.44 | 602456.51 | 16.7 | GRID | 7/24/2015 | 16.7 | 0.0 | Point surveyed within Tolerance |
| 216 | 684918.44 | 602456.51 | 17.1 | GRID | 7/24/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 222 | 684893.44 | 602481.51 | 16.4 | GRID | 7/24/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 223 | 684918.44 | 602481.51 | 16.9 | GRID | 7/24/2015 | 16.8 | -0.1 | Point surveyed within Tolerance |
| 205 | 684818.44 | 602431.51 | 15.0 | GRID | 8/10/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 211 | 684793.44 | 602456.51 | 14.0 | GRID | 8/10/2015 | 14.0 | 0.0 | Point surveyed within Tolerance |
| 212 | 684818.44 | 602456.51 | 15.2 | GRID | 8/10/2015 | 15.2 | 0.0 | Point surveyed within Tolerance |
| 213 | 684843.44 | 602456.51 | 15.7 | GRID | 8/10/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 218 | 684793.44 | 602481.51 | 14.3 | GRID | 8/10/2015 | 14.2 | -0.1 | Point surveyed within Tolerance |
| 219 | 684818.44 | 602481.51 | 14.9 | GRID | 8/10/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 220 | 684843.44 | 602481.51 | 15.4 | GRID | 8/10/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 221 | 684868.44 | 602481.51 | 15.9 | GRID | 8/10/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 224 | 684768.44 | 602506.51 | 13.3 | GRID | 8/10/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 225 | 684793.44 | 602506.51 | 14.0 | GRID | 8/10/2015 | 14.0 | 0.0 | Point surveyed within Tolerance |
| 226 | 684818.44 | 602506.51 | 14.6 | GRID | 8/10/2015 | 14.5 | -0.1 | Point surveyed within Tolerance |
| 227 | 684843.44 | 602506.51 | 15.1 | GRID | 8/10/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 228 | 684868.44 | 602506.51 | 15.6 | GRID | 8/10/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 229 | 684893.44 | 602506.51 | 16.1 | GRID | 8/10/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 232 | 684793.44 | 602531.51 | 16.3 | GRID | 8/10/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 233 | 684818.44 | 602531.51 | 16.8 | GRID | 8/10/2015 | 16.7 | -0.1 | Point surveyed within Tolerance |
| 234 | 684843.44 | 602531.51 | 17.3 | GRID | 8/10/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 235 | 684868.44 | 602531.51 | 17.9 | GRID | 8/10/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 239 | 684843.44 | 602556.51 | 17.1 | GRID | 8/10/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 240 | 684868.44 | 602556.51 | 17.6 | GRID | 8/10/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 217 | 684768.44 | 602481.51 | 13.2 | GRID | 8/12/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 230 | 684743.44 | 602531.51 | 12.6 | GRID | 8/12/2015 | 12.6 | 0.0 | Point surveyed within Tolerance |
| 231 | 684768.44 | 602531.51 | 15.8 | GRID | 8/12/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 245 | 684793.44 | 602581.51 | 14.1 | GRID | 8/12/2015 | 14.1 | 0.0 | Point surveyed within Tolerance |
| 246 | 684818.44 | 602581.51 | 14.1 | GRID | 8/12/2015 | 14.1 | 0.0 | Point surveyed within Tolerance |
| 247 | 684843.44 | 602581.51 | 14.3 | GRID | 8/12/2015 | 14.4 | 0.1 | Point surveyed within Tolerance |
| 252 | 684818.44 | 602606.51 | 14.3 | GRID | 8/12/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 236 | 684718.44 | 602556.51 | 7.5 | GRID | 8/13/2015 | 7.4 | -0.1 | Point surveyed within Tolerance |
| 237 | 684743.44 | 602556.51 | 15.6 | GRID | 8/13/2015 | 15.7 | 0.1 | Point surveyed within Tolerance |
| 241 | 684693.44 | 602581.51 | 5.8 | GRID | 8/13/2015 | 5.8 | 0.0 | Point surveyed within Tolerance |
| 242 | 684718.44 | 602581.51 | 13.2 | GRID | 8/13/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 243 | 684743.44 | 602581.51 | 15.7 | GRID | 8/13/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 244 | 684768.44 | 602581.51 | 13.9 | GRID | 8/13/2015 | 13.8 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.6) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 249 | 684743.44 | 602606.51 | 16.5 | GRID | 8/13/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 250 | 684768.44 | 602606.51 | 16.0 | GRID | 8/13/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 251 | 684793.44 | 602606.51 | 14.5 | GRID | 8/13/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 255 | 684768.44 | 602631.51 | 17.0 | GRID | 8/13/2015 | 17.1 | 0.1 | Point surveyed within Tolerance |
| 256 | 684793.44 | 602631.51 | 16.3 | GRID | 8/13/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 257 | 684818.44 | 602631.51 | 16.2 | GRID | 8/13/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 261 | 684793.44 | 602656.51 | 14.5 | GRID | 8/13/2015 | 14.6 | 0.1 | Point surveyed within Tolerance |
| 248 | 684693.44 | 602606.51 | 5.2 | GRID | 9/4/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 253 | 684693.44 | 602631.51 | 5.5 | GRID | 9/4/2015 | 5.5 | 0.0 | Point surveyed within Tolerance |
| 254 | 684718.44 | 602631.51 | 5.8 | GRID | 9/4/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 259 | 684718.44 | 602656.51 | 6.1 | GRID | 9/4/2015 | 6.0 | -0.1 | Point surveyed within Tolerance |
| 260 | 684743.44 | 602656.51 | 6.4 | GRID | 9/4/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 263 | 684743.44 | 602681.51 | 6.7 | GRID | 9/4/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 264 | 684768.44 | 602681.51 | 7.0 | GRID | 9/4/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 265 | 684793.44 | 602681.51 | 7.4 | GRID | 9/4/2015 | 7.3 | -0.1 | Point surveyed within Tolerance |
| 2069 | 684743.44 | 602706.51 | 17.8 | GRID | 9/4/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 2070 | 684743.44 | 602731.51 | 15.4 | GRID | 9/4/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 2071 | 684718.44 | 602756.51 | 15.8 | GRID | 9/4/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 2072 | 684718.44 | 602706.51 | 18.0 | GRID | 9/4/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 2073 | 684693.44 | 602706.51 | 15.4 | GRID | 9/4/2015 | 15.3 | -0.1 | Point surveyed within Tolerance |
| 2074 | 684693.44 | 602731.51 | 18.4 | GRID | 9/4/2015 | 18.5 | 0.1 | Point surveyed within Tolerance |
| 2075 | 684693.44 | 602756.51 | 18.8 | GRID | 9/4/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 2076 | 684693.44 | 602781.51 | 19.2 | GRID | 9/4/2015 | 19.3 | 0.1 | Point surveyed within Tolerance |
| 2079 | 684668.44 | 602756.51 | 16.4 | GRID | 9/4/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 2080 | 684668.44 | 602731.51 | 16.0 | GRID | 9/4/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 2081 | 684668.44 | 602706.51 | 18.3 | GRID | 9/4/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 2082 | 684668.44 | 602681.51 | 17.9 | GRID | 9/4/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 2083 | 684668.44 | 602656.51 | 14.9 | GRID | 9/4/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 2084 | 684643.44 | 602706.51 | 18.6 | GRID | 9/4/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 2085 | 684643.44 | 602731.51 | 16.3 | GRID | 9/4/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 2086 | 684643.44 | 602756.51 | 16.8 | GRID | 9/4/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 2090 | 684618.44 | 602731.51 | 16.6 | GRID | 9/4/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 2101 | 684593.44 | 602706.51 | 6.8 | GRID | 9/4/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2077 | 684668.44 | 602806.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2078 | 684668.44 | 602781.51 | 17.1 | GRID | 9/9/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 2087 | 684643.44 | 602781.51 | 17.3 | GRID | 9/9/2015 | 17.2 | -0.1 | Point surveyed within Tolerance |
| 2088 | 684643.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2089 | 684643.44 | 602831.51 | 17.7 | GRID | 9/9/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 2091 | 684618.44 | 602756.51 | 17.1 | GRID | 9/9/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 2092 | 684618.44 | 602781.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.7) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2093 | 684618.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2094 | 684618.44 | 602831.51 | 17.7 | GRID | 9/9/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 2095 | 684618.44 | 602856.51 | 20.3 | GRID | 9/9/2015 | 20.3 | 0.0 | Point surveyed within Tolerance |
| 2096 | 684593.44 | 602881.51 | 19.6 | GRID | 9/9/2015 | 19.5 | -0.1 | Point surveyed within Tolerance |
| 2097 | 684593.44 | 602856.51 | 19.9 | GRID | 9/9/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 2098 | 684593.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 2099 | 684593.44 | 602781.51 | 17.5 | GRID | 9/9/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 2100 | 684593.44 | 602756.51 | 17.2 | GRID | 9/9/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 2102 | 684568.44 | 602731.51 | 7.4 | GRID | 9/9/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 2103 | 684568.44 | 602781.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2104 | 684568.44 | 602831.51 | 19.9 | GRID | 9/9/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 2105 | 684568.44 | 602856.51 | 19.4 | GRID | 9/9/2015 | 19.4 | 0.0 | Point surveyed within Tolerance |
| 2106 | 684568.44 | 602881.51 | 18.8 | GRID | 9/9/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 2111 | 684543.44 | 602856.51 | 18.7 | GRID | 9/9/2015 | 18.8 | 0.1 | Point surveyed within Tolerance |
| 2112 | 684543.44 | 602831.51 | 19.5 | GRID | 9/9/2015 | 19.5 | 0.0 | Point surveyed within Tolerance |
| 2113 | 684543.44 | 602806.51 | 19.6 | GRID | 9/9/2015 | 19.6 | 0.0 | Point surveyed within Tolerance |
| 2114 | 684518.44 | 602831.51 | 18.6 | GRID | 9/9/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 2115 | 684518.44 | 602856.51 | 18.1 | GRID | 9/9/2015 | 18.2 | 0.1 | Point surveyed within Tolerance |
| 2126 | 684493.44 | 602831.51 | 9.6 | GRID | 9/9/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 2109 | 684543.44 | 602931.51 | 13.9 | GRID | 9/16/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 2110 | 684543.44 | 602906.51 | 6.4 | GRID | 9/16/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |
| 2116 | 684518.44 | 602906.51 | 12.9 | GRID | 9/16/2015 | 13.0 | 0.1 | Point surveyed within Tolerance |
| 2132 | 684468.44 | 602856.51 | 5.9 | GRID | 9/16/2015 | 6.0 | 0.1 | Point surveyed within Tolerance |
| 2108 | 684543.44 | 602956.51 | 14.3 | GRID | 9/18/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 2117 | 684518.44 | 602931.51 | 13.7 | GRID | 9/18/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 2118 | 684518.44 | 602956.51 | 16.8 | GRID | 9/18/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 2119 | 684518.44 | 602981.51 | 15.9 | GRID | 9/18/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 2121 | 684493.44 | 603006.51 | 14.5 | GRID | 9/18/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 2122 | 684493.44 | 602981.51 | 14.9 | GRID | 9/18/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 2123 | 684493.44 | 602956.51 | 15.5 | GRID | 9/18/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 2124 | 684493.44 | 602931.51 | 16.6 | GRID | 9/18/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 2125 | 684493.44 | 602906.51 | 13.4 | GRID | 9/18/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 2127 | 684468.44 | 603031.51 | 13.1 | GRID | 9/18/2015 | 13.1 | 0.0 | Point surveyed within Tolerance |
| 2128 | 684468.44 | 603006.51 | 13.5 | GRID | 9/18/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 2129 | 684468.44 | 602981.51 | 13.9 | GRID | 9/18/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 2130 | 684468.44 | 602956.51 | 14.4 | GRID | 9/18/2015 | 14.5 | 0.1 | Point surveyed within Tolerance |
| 2131 | 684468.44 | 602931.51 | 15.0 | GRID | 9/18/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 2133 | 684443.44 | 602881.51 | 7.9 | GRID | 9/18/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 2134 | 684443.44 | 602906.51 | 12.1 | GRID | 9/18/2015 | 12.1 | 0.0 | Point surveyed within Tolerance |
| 2135 | 684443.44 | 602931.51 | 13.8 | GRID | 9/18/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.8) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2136 | 684443.44 | 602956.51 | 13.3 | GRID | 9/18/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 2137 | 684443.44 | 602981.51 | 12.8 | GRID | 9/18/2015 | 12.9 | 0.1 | Point surveyed within Tolerance |
| 2138 | 684443.44 | 603006.51 | 12.4 | GRID | 9/18/2015 | 12.5 | 0.1 | Point surveyed within Tolerance |
| 2139 | 684443.44 | 603031.51 | 12.0 | GRID | 9/18/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 2146 | 684418.44 | 603006.51 | 11.3 | GRID | 9/18/2015 | 11.4 | 0.1 | Point surveyed within Tolerance |
| 2147 | 684418.44 | 602981.51 | 11.7 | GRID | 9/18/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 2148 | 684418.44 | 602956.51 | 12.1 | GRID | 9/18/2015 | 12.1 | 0.0 | Point surveyed within Tolerance |
| 2149 | 684418.44 | 602906.51 | 9.8 | GRID | 9/21/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 2150 | 684393.44 | 602931.51 | 8.6 | GRID | 9/18/2015 | 8.6 | 0.0 | Point surveyed within Tolerance |
| 2151 | 684393.44 | 602956.51 | 11.0 | GRID | 9/18/2015 | 10.9 | -0.1 | Point surveyed within Tolerance |
| 2152 | 684393.44 | 602981.51 | 10.5 | GRID | 9/18/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 2140 | 684443.44 | 603056.51 | 11.7 | GRID | 9/22/2015 | 11.6 | -0.1 | Point surveyed within Tolerance |
| 2141 | 684443.44 | 603081.51 | 11.4 | GRID | 9/22/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 2142 | 684418.44 | 603106.51 | 10.2 | GRID | 9/22/2015 | 10.2 | 0.0 | Point surveyed within Tolerance |
| 2143 | 684418.44 | 603081.51 | 10.4 | GRID | 9/22/2015 | 10.5 | 0.1 | Point surveyed within Tolerance |
| 2144 | 684418.44 | 603056.51 | 10.7 | GRID | 9/22/2015 | 10.6 | -0.1 | Point surveyed within Tolerance |
| 2145 | 684418.44 | 603031.51 | 10.9 | GRID | 9/22/2015 | 10.8 | -0.1 | Point surveyed within Tolerance |
| 2153 | 684393.44 | 603006.51 | 10.1 | GRID | 9/22/2015 | 10.1 | 0.0 | Point surveyed within Tolerance |
| 2154 | 684393.44 | 603031.51 | 9.9 | GRID | 9/22/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 2155 | 684393.44 | 603056.51 | 9.7 | GRID | 9/22/2015 | 9.6 | -0.1 | Point surveyed within Tolerance |
| 2156 | 684393.44 | 603106.51 | 9.4 | GRID | 9/23/2015 | 9.3 | -0.1 | Point surveyed within Tolerance |
| 2157 | 684393.44 | 603131.51 | 9.3 | GRID | 9/23/2015 | 9.2 | -0.1 | Point surveyed within Tolerance |
| 2161 | 684368.44 | 603131.51 | 8.6 | GRID | 9/23/2015 | 8.6 | 0.0 | Point surveyed within Tolerance |
| 2162 | 684368.44 | 603106.51 | 8.8 | GRID | 9/23/2015 | 8.7 | -0.1 | Point surveyed within Tolerance |
| 2163 | 684368.44 | 603056.51 | 8.8 | GRID | 9/22/2015 | 8.8 | 0.0 | Point surveyed within Tolerance |
| 2164 | 684368.44 | 603031.51 | 9.0 | GRID | 9/22/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 2165 | 684368.44 | 603006.51 | 9.2 | GRID | 9/22/2015 | 9.1 | -0.1 | Point surveyed within Tolerance |
| 2166 | 684368.44 | 602981.51 | 9.4 | GRID | 9/22/2015 | 9.3 | -0.1 | Point surveyed within Tolerance |
| 2167 | 684343.44 | 603006.51 | 8.3 | GRID | 9/22/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2168 | 684343.44 | 603031.51 | 8.1 | GRID | 9/22/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2169 | 684343.44 | 603056.51 | 8.2 | GRID | 9/23/2015 | 8.2 | 0.0 | Point surveyed within Tolerance |
| 2170 | 684343.44 | 603106.51 | 8.4 | GRID | 9/23/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2178 | 684318.44 | 603031.51 | 4.7 | GRID | 9/23/2015 | 4.8 | 0.1 | Point surveyed within Tolerance |
| 2179 | 684293.44 | 603056.51 | 4.3 | GRID | 9/23/2015 | 4.3 | 0.0 | Point surveyed within Tolerance |
| 2304 | 684318.44 | 603081.51 | 5.4 | GRID | 9/23/2015 | 5.3 | -0.1 | Point surveyed within Tolerance |
| 2160 | 684368.44 | 603156.51 | 8.6 | GRID | 9/23/2015 | 8.5 | -0.1 | Point surveyed within Tolerance |
| 2171 | 684343.44 | 603131.51 | 8.4 | GRID | 9/23/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2180 | 684293.44 | 603081.51 | 7.4 | GRID | 9/23/2015 | 7.3 | -0.1 | Point surveyed within Tolerance |
| 2195 | 684268.44 | 603081.51 | 5.8 | GRID | 9/23/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 2303 | 684293.44 | 603106.51 | 7.1 | GRID | 9/23/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.9) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2159 | 684368.44 | 603181.51 | 6.4 | GRID | 9/24/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 2172 | 684343.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2173 | 684343.44 | 603206.51 | 6.8 | GRID | 9/24/2015 | 6.7 | -0.1 | Point surveyed within Tolerance |
| 2174 | 684318.44 | 603231.51 | 8.8 | GRID | 9/28/2015 | 8.7 | -0.1 | Point surveyed within Tolerance |
| 2175 | 684318.44 | 603206.51 | 6.8 | GRID | 9/24/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2176 | 684318.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2177 | 684318.44 | 603156.51 | 6.2 | GRID | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2181 | 684293.44 | 603131.51 | 5.9 | GRID | 9/24/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2182 | 684293.44 | 603156.51 | 6.3 | GRID | 9/24/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 2183 | 684293.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.6 | 0.1 | Point surveyed within Tolerance |
| 2184 | 684293.44 | 603206.51 | 8.0 | GRID | 9/28/2015 | 8.0 | 0.0 | Point surveyed within Tolerance |
| 2185 | 684293.44 | 603231.51 | 8.3 | GRID | 9/28/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2190 | 684268.44 | 603206.51 | 7.4 | GRID | 9/28/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 2191 | 684268.44 | 603181.51 | 7.5 | GRID | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2192 | 684268.44 | 603156.51 | 6.2 | GRID | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2193 | 684268.44 | 603131.51 | 5.9 | GRID | 9/24/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2194 | 684268.44 | 603106.51 | 3.1 | GRID | 9/24/2015 | 3.1 | 0.0 | Point surveyed within Tolerance |
| 2196 | 684243.44 | 603131.51 | 3.0 | GRID | 9/24/2015 | 3.0 | 0.0 | Point surveyed within Tolerance |
| 2197 | 684243.44 | 603181.51 | 7.6 | GRID | 9/28/2015 | 7.5 | -0.1 | Point surveyed within Tolerance |
| 2198 | 684243.44 | 603206.51 | 7.3 | GRID | 9/28/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2206 | 684218.44 | 603156.51 | 7.7 | GRID | 9/28/2015 | 7.7 | 0.0 | Point surveyed within Tolerance |
| 2186 | 684293.44 | 603256.51 | 8.5 | GRID | 9/28/2015 | 8.5 | 0.0 | Point surveyed within Tolerance |
| 2188 | 684268.44 | 603256.51 | 8.2 | GRID | 9/28/2015 | 8.1 | -0.1 | Point surveyed within Tolerance |
| 2189 | 684268.44 | 603231.51 | 7.8 | GRID | 9/28/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 2199 | 684243.44 | 603231.51 | 7.5 | GRID | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2205 | 684218.44 | 603206.51 | 7.3 | GRID | 9/28/2015 | 7.2 | -0.1 | Point surveyed within Tolerance |
| 2208 | 684193.44 | 603181.51 | 7.5 | GRID | 9/28/2015 | 7.4 | -0.1 | Point surveyed within Tolerance |
| 2187 | 684268.44 | 603281.51 | 7.1 | GRID | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2200 | 684243.44 | 603256.51 | 7.8 | GRID | 10/7/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 2201 | 684243.44 | 603281.51 | 7.3 | GRID | 10/7/2015 | 7.2 | -0.1 | Point surveyed within Tolerance |
| 2202 | 684218.44 | 603281.51 | 6.9 | GRID | 10/7/2015 | 6.9 | 0.0 | Point surveyed within Tolerance |
| 2203 | 684218.44 | 603256.51 | 7.1 | GRID | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2204 | 684218.44 | 603231.51 | 7.4 | GRID | 10/7/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 2209 | 684193.44 | 603206.51 | 7.3 | GRID | 10/7/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2210 | 684193.44 | 603231.51 | 7.3 | GRID | 10/7/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2211 | 684193.44 | 603256.51 | 6.7 | GRID | 10/7/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 2212 | 684168.44 | 603256.51 | 6.5 | GRID | 10/7/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2213 | 684168.44 | 603231.51 | 6.4 | GRID | 10/7/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |
| 2214 | 684168.44 | 603206.51 | 7.6 | GRID | 10/7/2015 | 7.6 | 0.0 | Point surveyed within Tolerance |
| 2215 | 684143.44 | 603231.51 | 6.4 | GRID | 10/7/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.0) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 548 | 685583.37 | 601539.44 | 15.1 | BRK | 7/2/2015 | 15.2 | 0.1 | Point surveyed within Tolerance |
| 549 | 685595.90 | 601578.00 | 14.2 | BRK | 7/2/2015 | 14.3 | 0.1 | Point surveyed within Tolerance |
| 550 | 685562.63 | 601543.70 | 17.5 | BRK | 7/2/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 551 | 685559.49 | 601547.97 | 13.9 | BRK | 7/2/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 552 | 685555.56 | 601552.54 | 13.9 | BRK | 7/2/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 553 | 685552.50 | 601556.70 | 17.4 | BRK | 7/2/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 554 | 685602.63 | 601551.44 | 17.7 | BRK | 7/2/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 555 | 685524.90 | 601529.98 | 13.1 | BRK | 7/2/2015 | 13.2 | 0.1 | Point surveyed within Tolerance |
| 556 | 685521.85 | 601534.13 | 16.6 | BRK | 7/2/2015 | 16.4 | -0.2 | Point surveyed within Tolerance |
| 557 | 685518.43 | 601506.14 | 15.5 | BRK | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 559 | 685566.10 | 601602.95 | 17.4 | BRK | 7/2/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 560 | 685557.11 | 601621.51 | 16.2 | BRK | 7/2/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 583 | 685469.10 | 601609.94 | 16.0 | BRK | 7/2/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 584 | 685468.06 | 601601.70 | 14.5 | BRK | 7/2/2015 | 14.6 | 0.1 | Point surveyed within Tolerance |
| 585 | 685534.63 | 601655.70 | 15.5 | BRK | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 586 | 685515.15 | 601685.29 | 14.8 | BRK | 7/2/2015 | 14.6 | -0.2 | Point surveyed within Tolerance |
| 587 | 685503.84 | 601702.15 | 14.5 | BRK | 7/2/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 588 | 685484.63 | 601722.61 | 15.5 | BRK | 7/8/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 589 | 685482.47 | 601731.53 | 11.1 | BRK | 7/2/2015 | 11.1 | 0.0 | Point surveyed within Tolerance |
| 590 | 685467.89 | 601733.01 | 13.1 | BRK | 7/2/2015 | 13.2 | 0.1 | Point surveyed within Tolerance |
| 591 | 685467.14 | 601729.90 | 15.3 | BRK | 7/2/2015 | 15.2 | -0.1 | Point surveyed within Tolerance |
| 592 | 685465.84 | 601749.83 | 15.2 | BRK | 7/2/2015 | 15.1 | -0.1 | Point surveyed within Tolerance |
| 593 | 685444.26 | 601779.76 | 13.6 | BRK | 7/2/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 594 | 685429.29 | 601800.21 | 15.1 | BRK | 7/2/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 595 | 685453.48 | 601767.05 | 15.1 | BRK | 7/2/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 603 | 685418.25 | 601641.07 | 13.5 | BRK | 7/2/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 604 | 685415.60 | 601650.93 | 15.9 | BRK | 7/2/2015 | 15.6 | -0.3 | Point surveyed within Tolerance |
| 605 | 685417.81 | 601680.87 | 15.9 | BRK | 7/2/2015 | 15.8 | -0.1 | Point surveyed within Tolerance |
| 606 | 685421.62 | 601680.64 | 13.4 | BRK | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 607 | 685417.84 | 601705.42 | 16.1 | BRK | 7/2/2015 | 15.9 | -0.2 | Point surveyed within Tolerance |
| 608 | 685421.83 | 601705.56 | 13.4 | BRK | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 609 | 685420.68 | 601733.21 | 13.5 | BRK | 7/2/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 610 | 685416.60 | 601732.96 | 16.2 | BRK | 7/2/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 611 | 685420.69 | 601759.40 | 13.5 | BRK | 7/2/2015 | 13.6 | 0.1 | Point surveyed within Tolerance |
| 612 | 685417.42 | 601761.34 | 16.1 | BRK | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 613 | 685367.91 | 601704.46 | 13.3 | BRK | 7/2/2015 | 13.4 | 0.1 | Point surveyed within Tolerance |
| 614 | 685370.79 | 601706.98 | 15.9 | BRK | 7/2/2015 | 15.7 | -0.2 | Point surveyed within Tolerance |
| 615 | 685343.44 | 601731.17 | 13.7 | BRK | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 616 | 685345.91 | 601734.17 | 16.3 | BRK | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 617 | 685303.14 | 601806.86 | 18.3 | BRK | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 618 | 685298.77 | 601809.67 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 619 | 685294.54 | 601809.78 | 15.4 | BRK | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 620 | 685288.92 | 601805.68 | 10.7 | BRK | 7/2/2015 | 10.7 | 0.0 | Point surveyed within Tolerance |
| 621 | 685298.85 | 601821.38 | 15.8 | BRK | 7/2/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 622 | 685295.94 | 601825.31 | 12.5 | BRK | 7/2/2015 | 12.6 | 0.1 | Point surveyed within Tolerance |
| 623 | 685294.65 | 601831.82 | 12.5 | BRK | 7/2/2015 | 12.6 | 0.1 | Point surveyed within Tolerance |
| 624 | 685291.75 | 601835.75 | 15.8 | BRK | 7/2/2015 | 15.5 | -0.3 | Point surveyed within Tolerance |
| 625 | 685324.58 | 601840.13 | 15.9 | BRK | 7/2/2015 | 15.7 | -0.2 | Point surveyed within Tolerance |
| 626 | 685321.52 | 601844.26 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 627 | 685322.67 | 601852.58 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 628 | 685319.64 | 601856.68 | 15.8 | BRK | 7/2/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 629 | 685341.40 | 601852.72 | 15.7 | BRK | 7/2/2015 | 15.4 | -0.3 | Point surveyed within Tolerance |
| 630 | 685338.40 | 601856.76 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 631 | 685345.65 | 601844.39 | 15.9 | BRK | 7/2/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 632 | 685347.89 | 601841.36 | 18.4 | BRK | 7/8/2015 | 18.3 | -0.1 | Point surveyed within Tolerance |
| 633 | 685372.85 | 601864.55 | 15.3 | BRK | 7/2/2015 | 15.4 | 0.1 | Point surveyed within Tolerance |
| 634 | 685364.47 | 601869.99 | 15.2 | BRK | 7/8/2015 | 15.1 | -0.1 | Point surveyed within Tolerance |
| 635 | 685361.56 | 601873.92 | 12.0 | BRK | 7/2/2015 | 12.1 | 0.1 | Point surveyed within Tolerance |
| 636 | 685354.92 | 601876.46 | 12.0 | BRK | 7/2/2015 | 12.1 | 0.1 | Point surveyed within Tolerance |
| 637 | 685350.44 | 601879.24 | 15.3 | BRK | 7/2/2015 | 15.2 | -0.1 | Point surveyed within Tolerance |
| 639 | 685353.62 | 601747.98 | 16.4 | BRK | 7/8/2015 | 16.3 | -0.1 | Point surveyed within Tolerance |
| 640 | 685357.16 | 601746.52 | 13.8 | BRK | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 641 | 685361.58 | 601753.32 | 13.9 | BRK | 7/2/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 642 | 685364.98 | 601751.93 | 16.3 | BRK | 7/2/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 645 | 685381.55 | 601830.67 | 17.5 | BRK | 7/8/2015 | 17.4 | -0.1 | Point surveyed within Tolerance |
| 646 | 685385.39 | 601829.73 | 14.8 | BRK | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 647 | 685383.26 | 601850.36 | 17.6 | BRK | 7/8/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 648 | 685408.65 | 601820.74 | 16.6 | BRK | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 672 | 685359.01 | 601899.40 | 14.5 | BRK | 7/2/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 673 | 685328.78 | 601922.42 | 18.1 | BRK | 7/2/2015 | 18.2 | 0.1 | Point surveyed within Tolerance |
| 674 | 685299.89 | 601934.58 | 18.3 | BRK | 7/2/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 675 | 685300.62 | 601938.23 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 676 | 685305.79 | 601944.00 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 677 | 685308.02 | 601946.97 | 18.2 | BRK | 7/2/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 679 | 685305.33 | 601869.91 | 16.0 | BRK | 7/2/2015 | 16.1 | 0.1 | Point surveyed within Tolerance |
| 680 | 685303.05 | 601872.98 | 18.5 | BRK | 7/2/2015 | 18.1 | -0.4 | Point surveyed within Tolerance |
| 681 | 685268.99 | 601832.99 | 12.1 | BRK | 7/2/2015 | 12.2 | 0.1 | Point surveyed within Tolerance |
| 682 | 685272.64 | 601835.66 | 15.1 | BRK | 7/2/2015 | 14.7 | -0.4 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 683 | 685218.81 | 601931.92 | 18.6 | BRK | 7/2/2015 | 18.2 | -0.4 | Point surveyed within Tolerance |
| 684 | 685217.81 | 601935.62 | 16.0 | BRK | 7/2/2015 | 16.1 | 0.1 | Point surveyed within Tolerance |
| 979 | 685388.74 | 601749.07 | 13.5 | BRK | 7/2/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 980 | 685384.77 | 601750.03 | 16.2 | BRK | 7/2/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 678 | 685292.65 | 601972.35 | 18.1 | BRK | 7/14/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 685 | 685217.77 | 601956.54 | 18.2 | BRK | 7/14/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 686 | 685214.25 | 601958.05 | 15.7 | BRK | 7/14/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 688 | 685246.08 | 602006.05 | 17.3 | BRK | 7/14/2015 | 17.4 | 0.1 | Point surveyed within Tolerance |
| 689 | 685249.42 | 602007.82 | 14.8 | BRK | 7/14/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |
| 690 | 685250.13 | 602009.68 | 14.8 | BRK | 7/14/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 691 | 685253.44 | 602011.40 | 17.3 | BRK | 7/14/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 692 | 685256.80 | 602026.88 | 16.9 | BRK | 7/14/2015 | 17.0 | 0.1 | Point surveyed within Tolerance |
| 822 | 685209.17 | 602098.14 | 16.1 | BRK | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 823 | 685187.68 | 602127.24 | 16.4 | BRK | 7/14/2015 | 16.5 | 0.1 | Point surveyed within Tolerance |
| 824 | 685169.69 | 602121.14 | 16.9 | BRK | 7/14/2015 | 17.0 | 0.1 | Point surveyed within Tolerance |
| 825 | 685159.60 | 602134.77 | 5.6 | BRK | 7/14/2015 | 5.7 | 0.1 | Point surveyed within Tolerance |
| 826 | 685142.99 | 602100.91 | 16.8 | BRK | 7/14/2015 | 16.7 | -0.1 | Point surveyed within Tolerance |
| 827 | 685132.68 | 602114.85 | 5.2 | BRK | 7/14/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 828 | 685117.94 | 602082.20 | 16.5 | BRK | 7/14/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 829 | 685108.04 | 602096.62 | 4.9 | BRK | 7/14/2015 | 4.9 | 0.0 | Point surveyed within Tolerance |
| 830 | 685097.56 | 602070.88 | 13.7 | BRK | 7/14/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 831 | 685091.62 | 602084.47 | 4.6 | BRK | 7/14/2015 | 4.7 | 0.1 | Point surveyed within Tolerance |
| 832 | 685079.08 | 602074.23 | 4.4 | BRK | 7/14/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 833 | 685087.23 | 602063.24 | 5.1 | BRK | 7/14/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 834 | 685228.90 | 602033.89 | 16.5 | BRK | 7/14/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 835 | 685232.50 | 602033.47 | 14.1 | BRK | 7/14/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 836 | 685239.46 | 602034.31 | 14.1 | BRK | 7/14/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 837 | 685243.00 | 602035.55 | 16.6 | BRK | 7/14/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 838 | 685241.70 | 602050.98 | 16.3 | BRK | 7/14/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 839 | 685057.33 | 602100.46 | 4.4 | BRK | 7/24/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 840 | 685060.41 | 602121.19 | 14.5 | BRK | 7/24/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 841 | 685068.93 | 602108.10 | 4.6 | BRK | 7/24/2015 | 4.7 | 0.1 | Point surveyed within Tolerance |
| 842 | 685048.44 | 602112.41 | 4.6 | BRK | 7/24/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 843 | 685096.92 | 602128.82 | 5.0 | BRK | 7/24/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 844 | 685091.28 | 602143.63 | 15.2 | BRK | 7/24/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 845 | 685121.55 | 602147.05 | 5.3 | BRK | 7/24/2015 | 5.4 | 0.1 | Point surveyed within Tolerance |
| 846 | 685109.62 | 602161.54 | 17.8 | BRK | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 847 | 685117.56 | 602193.69 | 17.4 | BRK | 7/24/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 848 | 685118.92 | 602197.25 | 14.9 | BRK | 7/24/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 849 | 685119.73 | 602203.55 | 14.8 | BRK | 7/24/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 850 | 685121.10 | 602206.98 | 17.3 | BRK | 7/24/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 851 | 685114.98 | 602226.59 | 17.2 | BRK | 7/24/2015 | 17.1 | -0.1 | Point surveyed within Tolerance |
| 852 | 685105.19 | 602198.82 | 17.4 | BRK | 7/24/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 853 | 685103.22 | 602203.76 | 14.8 | BRK | 7/24/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 854 | 685088.02 | 602208.76 | 17.4 | BRK | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 855 | 685089.52 | 602212.18 | 14.9 | BRK | 7/24/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 856 | 685085.84 | 602227.09 | 15.1 | BRK | 7/24/2015 | 15.2 | 0.1 | Point surveyed within Tolerance |
| 857 | 685083.49 | 602230.12 | 17.6 | BRK | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 858 | 685094.99 | 602252.22 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 859 | 685081.79 | 602269.14 | 18.1 | BRK | 7/24/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 860 | 685047.09 | 602237.51 | 15.7 | BRK | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 861 | 685043.77 | 602234.95 | 18.2 | BRK | 7/24/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 862 | 685039.91 | 602232.72 | 15.7 | BRK | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 863 | 685042.37 | 602238.43 | 15.7 | BRK | 7/24/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 864 | 685066.11 | 602161.84 | 17.8 | BRK | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 865 | 685062.13 | 602161.07 | 15.3 | BRK | 7/24/2015 | 15.4 | 0.1 | Point surveyed within Tolerance |
| 866 | 685052.96 | 602208.15 | 17.8 | BRK | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 867 | 685049.31 | 602206.51 | 15.4 | BRK | 7/24/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 868 | 685045.11 | 602202.48 | 15.6 | BRK | 7/24/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 869 | 685042.10 | 602200.70 | 17.9 | BRK | 7/24/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 870 | 685022.96 | 602172.09 | 15.4 | BRK | 7/24/2015 | 15.3 | -0.1 | Point surveyed within Tolerance |
| 871 | 685044.91 | 602142.21 | 14.8 | BRK | 7/24/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 872 | 684994.42 | 602217.26 | 18.7 | BRK | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 873 | 684975.68 | 602242.79 | 19.1 | BRK | 7/24/2015 | 19.1 | 0.0 | Point surveyed within Tolerance |
| 874 | 685005.71 | 602243.75 | 18.8 | BRK | 7/24/2015 | 18.7 | -0.1 | Point surveyed within Tolerance |
| 875 | 685009.09 | 602245.47 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 876 | 685025.00 | 602263.80 | 16.2 | BRK | 7/24/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 877 | 685027.83 | 602266.24 | 18.7 | BRK | 7/24/2015 | 18.6 | -0.1 | Point surveyed within Tolerance |
| 878 | 685053.73 | 602299.58 | 18.7 | BRK | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 879 | 685053.33 | 602303.33 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 880 | 685060.48 | 602307.84 | 16.2 | BRK | 7/24/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 881 | 685039.62 | 602323.93 | 18.6 | BRK | 7/24/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 882 | 685021.34 | 602349.28 | 18.4 | BRK | 7/24/2015 | 18.3 | -0.1 | Point surveyed within Tolerance |
| 883 | 685006.56 | 602373.52 | 17.5 | BRK | 7/24/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 884 | 684985.52 | 602400.52 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 885 | 684968.75 | 602423.06 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 886 | 684958.59 | 602266.06 | 19.6 | BRK | 7/24/2015 | 19.5 | -0.1 | Point surveyed within Tolerance |
| 887 | 684944.51 | 602285.23 | 19.9 | BRK | 7/24/2015 | 20.0 | 0.1 | Point surveyed within Tolerance |
| 888 | 684924.17 | 602312.77 | 20.4 | BRK | 7/24/2015 | 20.3 | -0.1 | Point surveyed within Tolerance |
| 889 | 684896.37 | 602343.10 | 18.0 | BRK | 7/24/2015 | 17.9 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 890 | 684880.77 | 602362.80 | 17.8 | BRK | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 891 | 684869.32 | 602354.21 | 8.2 | BRK | 7/24/2015 | 8.3 | 0.1 | Point surveyed within Tolerance |
| 892 | 684884.22 | 602334.10 | 7.9 | BRK | 7/24/2015 | 8.0 | 0.1 | Point surveyed within Tolerance |
| 893 | 684908.58 | 602301.22 | 7.4 | BRK | 7/24/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 894 | 684928.96 | 602273.71 | 7.0 | BRK | 7/24/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 895 | 684943.18 | 602254.50 | 6.7 | BRK | 7/24/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 896 | 684960.30 | 602231.40 | 6.4 | BRK | 7/24/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 897 | 684979.15 | 602205.95 | 6.0 | BRK | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 898 | 685010.86 | 602163.13 | 5.3 | BRK | 7/24/2015 | 5.4 | 0.1 | Point surveyed within Tolerance |
| 899 | 685032.93 | 602133.34 | 4.9 | BRK | 7/24/2015 | 4.9 | 0.0 | Point surveyed within Tolerance |
| 900 | 684953.81 | 602443.85 | 17.6 | BRK | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 901 | 684933.84 | 602472.48 | 17.2 | BRK | 7/24/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 919 | 684835.00 | 602400.55 | 9.0 | BRK | 7/24/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 920 | 684843.87 | 602407.12 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 902 | 684913.09 | 602504.45 | 16.5 | BRK | 8/10/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 910 | 684887.04 | 602531.88 | 18.2 | BRK | 8/10/2015 | 18.2 | 0.0 | Point surveyed within Tolerance |
| 909 | 684858.28 | 602571.33 | 14.7 | BRK | 8/12/2015 | 14.8 | 0.1 | Point surveyed within Tolerance |
| 913 | 684795.24 | 602555.71 | 13.7 | BRK | 8/12/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 914 | 684795.33 | 602552.00 | 16.1 | BRK | 8/12/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 915 | 684770.38 | 602552.44 | 15.8 | BRK | 8/12/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 916 | 684771.04 | 602556.03 | 13.3 | BRK | 8/12/2015 | 13.4 | 0.1 | Point surveyed within Tolerance |
| 917 | 684841.91 | 602602.61 | 16.6 | BRK | 8/12/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 911 | 684720.03 | 602604.99 | 14.7 | BRK | 8/13/2015 | 14.6 | -0.1 | Point surveyed within Tolerance |
| 921 | 684754.50 | 602627.17 | 17.2 | BRK | 8/13/2015 | 17.1 | -0.1 | Point surveyed within Tolerance |
| 923 | 684774.69 | 602642.80 | 17.3 | BRK | 8/13/2015 | 17.2 | -0.1 | Point surveyed within Tolerance |
| 925 | 684807.26 | 602664.88 | 13.8 | BRK | 8/13/2015 | 13.7 | -0.1 | Point surveyed within Tolerance |
| 912 | 684710.93 | 602615.25 | 5.5 | BRK | 9/4/2015 | 5.6 | 0.1 | Point surveyed within Tolerance |
| 922 | 684744.74 | 602640.33 | 6.3 | BRK | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 924 | 684765.25 | 602655.54 | 6.7 | BRK | 9/4/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 927 | 684774.96 | 602705.07 | 7.4 | BRK | 9/4/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 929 | 684725.10 | 602668.09 | 6.3 | BRK | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 933 | 684699.13 | 602648.83 | 5.7 | BRK | 9/4/2015 | 5.8 | 0.1 | Point surveyed within Tolerance |
| 934 | 684677.32 | 602632.66 | 5.2 | BRK | 9/4/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 936 | 684665.76 | 602624.13 | 5.0 | BRK | 9/4/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 2216 | 684768.70 | 602713.78 | 14.5 | BRK | 9/4/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 2217 | 684755.49 | 602705.02 | 14.8 | BRK | 9/4/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |
| 2218 | 684750.54 | 602706.29 | 17.4 | BRK | 9/4/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 2219 | 684719.51 | 602728.09 | 18.1 | BRK | 9/4/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 2220 | 684721.25 | 602731.77 | 15.4 | BRK | 9/4/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2223 | 684714.82 | 602681.95 | 17.8 | BRK | 9/4/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 2224 | 684695.23 | 602678.31 | 15.2 | BRK | 9/4/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 2225 | 684691.16 | 602677.76 | 17.9 | BRK | 9/4/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 2226 | 684679.26 | 602656.42 | 17.5 | BRK | 9/4/2015 | 17.4 | -0.1 | Point surveyed within Tolerance |
| 2227 | 684678.94 | 602651.43 | 14.9 | BRK | 9/4/2015 | 14.8 | -0.1 | Point surveyed within Tolerance |
| 2228 | 684668.13 | 602643.12 | 14.5 | BRK | 9/4/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 2229 | 684657.26 | 602634.26 | 5.1 | BRK | 9/4/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 2230 | 684652.03 | 602663.18 | 15.1 | BRK | 9/4/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 2231 | 684641.00 | 602654.19 | 5.6 | BRK | 9/4/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 2232 | 684642.38 | 602682.88 | 18.2 | BRK | 9/4/2015 | 18.2 | 0.0 | Point surveyed within Tolerance |
| 2233 | 684640.23 | 602679.29 | 15.5 | BRK | 9/4/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 2234 | 684618.68 | 602681.55 | 6.2 | BRK | 9/4/2015 | 6.3 | 0.1 | Point surveyed within Tolerance |
| 2235 | 684632.71 | 602692.99 | 18.3 | BRK | 9/4/2015 | 18.2 | -0.1 | Point surveyed within Tolerance |
| 2236 | 684620.10 | 602708.58 | 18.7 | BRK | 9/4/2015 | 18.6 | -0.1 | Point surveyed within Tolerance |
| 2239 | 684603.43 | 602700.25 | 6.6 | BRK | 9/4/2015 | 6.7 | 0.1 | Point surveyed within Tolerance |
| 2312 | 684688.25 | 602662.99 | 17.6 | BRK | 9/4/2015 | 17.7 | 0.1 | Point surveyed within Tolerance |
| 2222 | 684686.52 | 602801.63 | 17.2 | BRK | 9/9/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 2240 | 684580.79 | 602728.00 | 7.2 | BRK | 9/9/2015 | 7.3 | 0.1 | Point surveyed within Tolerance |
| 2241 | 684592.09 | 602737.22 | 17.0 | BRK | 9/9/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 2245 | 684652.97 | 602837.52 | 18.0 | BRK | 9/9/2015 | 17.9 | -0.1 | Point surveyed within Tolerance |
| 2248 | 684632.99 | 602849.23 | 20.5 | BRK | 9/9/2015 | 20.5 | 0.0 | Point surveyed within Tolerance |
| 2249 | 684573.19 | 602760.13 | 17.4 | BRK | 9/9/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 2250 | 684562.02 | 602751.01 | 7.8 | BRK | 9/9/2015 | 7.9 | 0.1 | Point surveyed within Tolerance |
| 2251 | 684549.64 | 602787.35 | 17.3 | BRK | 9/9/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 2252 | 684539.27 | 602778.90 | 8.4 | BRK | 9/9/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2253 | 684568.32 | 602806.28 | 17.4 | BRK | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2254 | 684565.58 | 602809.03 | 20.0 | BRK | 9/9/2015 | 19.9 | -0.1 | Point surveyed within Tolerance |
| 2255 | 684590.81 | 602830.43 | 20.3 | BRK | 9/9/2015 | 20.3 | 0.0 | Point surveyed within Tolerance |
| 2256 | 684593.43 | 602827.27 | 17.6 | BRK | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2257 | 684611.57 | 602875.64 | 20.3 | BRK | 9/9/2015 | 20.2 | -0.1 | Point surveyed within Tolerance |
| 2261 | 684576.88 | 602901.09 | 18.3 | BRK | 9/9/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 2266 | 684529.13 | 602867.21 | 18.0 | BRK | 9/9/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 2269 | 684529.62 | 602815.05 | 19.2 | BRK | 9/9/2015 | 19.2 | 0.0 | Point surveyed within Tolerance |
| 2270 | 684517.71 | 602805.33 | 9.0 | BRK | 9/9/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 2313 | 684666.34 | 602822.94 | 17.7 | BRK | 9/9/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 2259 | 684588.87 | 602908.31 | 19.0 | BRK | 9/16/2015 | 19.1 | 0.1 | Point surveyed within Tolerance |
| 2262 | 684562.28 | 602912.39 | 6.5 | BRK | 9/16/2015 | 6.6 | 0.1 | Point surveyed within Tolerance |
| 2263 | 684546.99 | 602879.91 | 18.1 | BRK | 9/16/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 2264 | 684536.89 | 602894.42 | 6.3 | BRK | 9/16/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2265 | 684518.89 | 602881.69 | 6.2 | BRK | 9/16/2015 | 6.3 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.6) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2267 | 684498.05 | 602850.83 | 14.8 | BRK | 9/16/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 2268 | 684490.45 | 602861.57 | 6.0 | BRK | 9/16/2015 | 6.1 | 0.1 | Point surveyed within Tolerance |
| 2275 | 684469.16 | 602880.75 | 13.2 | BRK | 9/16/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 2278 | 684497.26 | 602878.64 | 6.1 | BRK | 9/16/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2279 | 684491.48 | 602886.80 | 12.8 | BRK | 9/16/2015 | 12.7 | -0.1 | Point surveyed within Tolerance |
| 2282 | 684569.90 | 602930.04 | 6.6 | BRK | 9/16/2015 | 6.6 | 0.0 | Point surveyed within Tolerance |
| 2283 | 684564.16 | 602938.23 | 13.2 | BRK | 9/16/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 2284 | 684462.82 | 602873.57 | 6.8 | BRK | 9/16/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2271 | 684492.19 | 603028.63 | 14.1 | BRK | 9/18/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 2272 | 684495.31 | 603031.35 | 11.3 | BRK | 9/18/2015 | 11.4 | 0.1 | Point surveyed within Tolerance |
| 2276 | 684420.78 | 602931.95 | 12.7 | BRK | 9/18/2015 | 12.7 | 0.0 | Point surveyed within Tolerance |
| 2277 | 684418.27 | 602928.58 | 9.9 | BRK | 9/18/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 2280 | 684466.73 | 602909.21 | 16.2 | BRK | 9/18/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 2281 | 684469.26 | 602906.05 | 13.5 | BRK | 9/18/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 2308 | 684541.16 | 602978.86 | 13.9 | BRK | 9/18/2015 | 13.8 | -0.1 | Point surveyed within Tolerance |
| 2309 | 684537.93 | 602976.16 | 16.7 | BRK | 9/18/2015 | 16.7 | 0.0 | Point surveyed within Tolerance |
| 2310 | 684519.64 | 603003.49 | 12.7 | BRK | 9/18/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 2311 | 684516.52 | 603000.77 | 15.4 | BRK | 9/18/2015 | 15.5 | 0.1 | Point surveyed within Tolerance |
| 2273 | 684467.44 | 603056.98 | 12.7 | BRK | 9/22/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 2274 | 684470.54 | 603059.69 | 10.0 | BRK | 9/22/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 2285 | 684396.21 | 603081.17 | 9.6 | BRK | 9/22/2015 | 9.5 | -0.1 | Point surveyed within Tolerance |
| 2286 | 684394.95 | 603084.82 | 7.0 | BRK | 9/22/2015 | 6.9 | -0.1 | Point surveyed within Tolerance |
| 2287 | 684370.17 | 603081.08 | 6.5 | BRK | 9/22/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2288 | 684369.73 | 603084.51 | 8.8 | BRK | 9/22/2015 | 8.8 | 0.0 | Point surveyed within Tolerance |
| 2291 | 684343.83 | 603080.68 | 5.9 | BRK | 9/23/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2292 | 684344.02 | 603084.27 | 8.3 | BRK | 9/23/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2293 | 684318.43 | 603058.47 | 7.6 | BRK | 9/23/2015 | 7.5 | -0.1 | Point surveyed within Tolerance |
| 2294 | 684314.63 | 603057.98 | 5.0 | BRK | 9/23/2015 | 5.1 | 0.1 | Point surveyed within Tolerance |
| 2306 | 684383.22 | 603153.36 | 9.0 | BRK | 9/23/2015 | 8.9 | -0.1 | Point surveyed within Tolerance |
| 2307 | 684386.53 | 603155.86 | 6.6 | BRK | 9/23/2015 | 6.5 | -0.1 | Point surveyed within Tolerance |
| 2289 | 684346.82 | 603155.61 | 8.4 | BRK | 9/24/2015 | 8.3 | -0.1 | Point surveyed within Tolerance |
| 2290 | 684344.28 | 603158.02 | 7.0 | BRK | 9/24/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 2296 | 684244.61 | 603103.27 | 6.2 | BRK | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2297 | 684317.01 | 603131.31 | 6.5 | BRK | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2298 | 684318.88 | 603129.97 | 8.1 | BRK | 9/24/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2299 | 684244.49 | 603157.76 | 7.5 | BRK | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2300 | 684238.78 | 603154.40 | 3.1 | BRK | 9/28/2015 | 3.1 | 0.0 | Point surveyed within Tolerance |
| 2301 | 684221.74 | 603183.65 | 7.8 | BRK | 9/28/2015 | 7.7 | -0.1 | Point surveyed within Tolerance |
| 2302 | 684225.10 | 603177.88 | 3.3 | BRK | 9/28/2015 | 3.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

Points in 0.1 - 0.5 ft. tolerance are due to a slight overcut in the top of slopes where it wouldn't be suitable for backfill due to compaction difficulties.

| SA-6 South Cap Subgrade: Boundary Points (Table 3.0) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 545 | 685526.43 | 601442.32 | 12.9 | BNDY | 7/2/2015 | 13.0 | 0.1 | Point surveyed within Tolerance |
| 546 | 685543.45 | 601459.45 | 13.4 | BNDY | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 547 | 685561.91 | 601478.03 | 14.2 | BNDY | 7/2/2015 | 14.2 | 0.0 | Point surveyed within Tolerance |
| 558 | 685516.84 | 601455.37 | 13.7 | BNDY | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 561 | 685572.96 | 601633.24 | 10.0 | BNDY | 7/2/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 562 | 685589.38 | 601610.88 | 10.2 | BNDY | 7/2/2015 | 10.1 | -0.1 | Point surveyed within Tolerance |
| 563 | 685606.33 | 601587.78 | 9.9 | BNDY | 7/2/2015 | 10.0 | 0.1 | Point surveyed within Tolerance |
| 564 | 685633.80 | 601550.37 | 9.8 | BNDY | 7/2/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 565 | 685622.62 | 601565.61 | 10.0 | BNDY | 7/2/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 566 | 685614.41 | 601530.85 | 15.7 | BNDY | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 567 | 685591.47 | 601507.77 | 15.0 | BNDY | 7/2/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 568 | 685577.88 | 601494.10 | 14.6 | BNDY | 7/2/2015 | 14.6 | 0.0 | Point surveyed within Tolerance |
| 569 | 685488.06 | 601495.42 | 14.3 | BNDY | 7/2/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 570 | 685501.08 | 601477.69 | 14.9 | BNDY | 7/2/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 571 | 685474.31 | 601513.30 | 13.6 | BNDY | 7/2/2015 | 13.6 | 0.0 | Point surveyed within Tolerance |
| 572 | 685459.92 | 601533.74 | 12.8 | BNDY | 7/2/2015 | 12.8 | 0.0 | Point surveyed within Tolerance |
| 573 | 685442.87 | 601556.12 | 12.4 | BNDY | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 574 | 685428.08 | 601576.27 | 12.2 | BNDY | 7/2/2015 | 12.2 | 0.0 | Point surveyed within Tolerance |
| 575 | 685413.27 | 601596.44 | 11.9 | BNDY | 7/2/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 576 | 685398.47 | 601616.59 | 11.4 | BNDY | 7/2/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 577 | 685383.68 | 601636.74 | 11.3 | BNDY | 7/2/2015 | 11.3 | 0.0 | Point surveyed within Tolerance |
| 578 | 685368.88 | 601656.89 | 11.3 | BNDY | 7/2/2015 | 11.2 | -0.1 | Point surveyed within Tolerance |
| 579 | 685558.28 | 601653.23 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 581 | 685543.38 | 601673.52 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 582 | 685528.60 | 601693.65 | 9.8 | BNDY | 7/2/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 596 | 685514.37 | 601713.04 | 9.8 | BNDY | 7/2/2015 | 9.7 | -0.1 | Point surveyed within Tolerance |
| 597 | 685499.50 | 601733.28 | 9.7 | BNDY | 7/2/2015 | 9.8 | 0.1 | Point surveyed within Tolerance |
| 598 | 685485.10 | 601752.90 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 599 | 685469.40 | 601774.28 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 600 | 685454.74 | 601794.25 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 601 | 685439.85 | 601814.53 | 9.7 | BNDY | 7/2/2015 | 9.6 | -0.1 | Point surveyed within Tolerance |
| 602 | 685425.01 | 601834.73 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 638 | 685354.08 | 601677.04 | 11.3 | BNDY | 7/2/2015 | 11.1 | -0.2 | Point surveyed within Tolerance |
| 643 | 685324.49 | 601717.35 | 10.8 | BNDY | 7/2/2015 | 10.6 | -0.2 | Point surveyed within Tolerance |
| 644 | 685339.29 | 601697.19 | 11.0 | BNDY | 7/2/2015 | 10.6 | -0.4 | Point surveyed within Tolerance |
| 649 | 685309.86 | 601737.62 | 10.6 | BNDY | 7/2/2015 | 10.6 | 0.0 | Point surveyed within Tolerance |
| 650 | 685295.20 | 601757.86 | 10.5 | BNDY | 7/2/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 651 | 685280.51 | 601778.09 | 10.4 | BNDY | 7/2/2015 | 10.3 | -0.1 | Point surveyed within Tolerance |
| 652 | 685265.70 | 601798.24 | 10.7 | BNDY | 7/2/2015 | 10.8 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 653 | 685250.90 | 601818.38 | 11.9 | BNDY | 7/2/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 654 | 685236.09 | 601838.53 | 15.1 | BNDY | 7/2/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 655 | 685221.28 | 601858.68 | 15.6 | BNDY | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 656 | 685206.48 | 601878.81 | 15.5 | BNDY | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 657 | 685191.67 | 601898.96 | 15.5 | BNDY | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 658 | 685176.87 | 601919.10 | 15.4 | BNDY | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 659 | 685410.29 | 601854.79 | 9.6 | BNDY | 7/2/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 660 | 685395.44 | 601875.02 | 9.6 | BNDY | 7/2/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 661 | 685380.66 | 601895.14 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 662 | 685365.91 | 601915.23 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 663 | 685351.03 | 601935.49 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 664 | 685336.28 | 601955.58 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 687 | 685162.06 | 601939.25 | 14.9 | BNDY | 7/2/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 665 | 685321.52 | 601975.69 | 10.0 | BNDY | 7/14/2015 | 9.9 | -0.1 | Point surveyed within Tolerance |
| 666 | 685306.70 | 601995.87 | 10.0 | BNDY | 7/14/2015 | 9.9 | -0.1 | Point surveyed within Tolerance |
| 667 | 685292.04 | 602015.84 | 10.0 | BNDY | 7/14/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 668 | 685277.22 | 602036.03 | 10.0 | BNDY | 7/14/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 669 | 685262.73 | 602055.75 | 9.9 | BNDY | 7/14/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 670 | 685247.66 | 602076.28 | 10.0 | BNDY | 7/14/2015 | 10.1 | 0.1 | Point surveyed within Tolerance |
| 671 | 685232.64 | 602096.74 | 10.2 | BNDY | 7/14/2015 | 10.1 | -0.1 | Point surveyed within Tolerance |
| 693 | 685147.26 | 601959.39 | 14.3 | BNDY | 7/14/2015 | 14.4 | 0.1 | Point surveyed within Tolerance |
| 694 | 685132.45 | 601979.53 | 13.7 | BNDY | 7/14/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 695 | 685117.65 | 601999.68 | 13.2 | BNDY | 7/14/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 696 | 685102.93 | 602019.90 | 10.3 | BNDY | 7/14/2015 | 10.4 | 0.1 | Point surveyed within Tolerance |
| 697 | 685088.04 | 602039.97 | 6.1 | BNDY | 7/14/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 698 | 685073.23 | 602060.11 | 4.7 | BNDY | 7/14/2015 | 4.8 | 0.1 | Point surveyed within Tolerance |
| 699 | 685058.42 | 602080.25 | 4.3 | BNDY | 7/14/2015 | 4.4 | 0.1 | Point surveyed within Tolerance |
| 705 | 685217.90 | 602116.82 | 10.4 | BNDY | 7/14/2015 | 10.3 | -0.1 | Point surveyed within Tolerance |
| 706 | 685203.10 | 602136.97 | 10.5 | BNDY | 7/14/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 700 | 685043.62 | 602100.40 | 4.5 | BNDY | 7/24/2015 | 4.4 | -0.1 | Point surveyed within Tolerance |
| 701 | 685028.81 | 602120.54 | 4.8 | BNDY | 7/24/2015 | 4.9 | 0.1 | Point surveyed within Tolerance |
| 702 | 685014.01 | 602140.69 | 5.1 | BNDY | 7/24/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 703 | 684999.20 | 602160.83 | 5.4 | BNDY | 7/24/2015 | 5.4 | 0.0 | Point surveyed within Tolerance |
| 704 | 684984.40 | 602180.97 | 5.7 | BNDY | 7/24/2015 | 5.7 | 0.0 | Point surveyed within Tolerance |
| 707 | 685188.31 | 602157.12 | 6.0 | BNDY | 7/24/2015 | 6.1 | 0.1 | Point surveyed within Tolerance |
| 708 | 685173.51 | 602177.27 | 6.0 | BNDY | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 709 | 685143.92 | 602217.57 | 11.2 | BNDY | 7/24/2015 | 11.2 | 0.0 | Point surveyed within Tolerance |
| 710 | 685158.71 | 602197.42 | 11.1 | BNDY | 7/24/2015 | 11.0 | -0.1 | Point surveyed within Tolerance |
| 711 | 685129.12 | 602237.73 | 11.4 | BNDY | 7/24/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 712 | 685114.32 | 602257.88 | 11.6 | BNDY | 7/24/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 713 | 685099.53 | 602278.03 | 11.8 | BNDY | 7/24/2015 | 11.7 | -0.1 | Point surveyed within Tolerance |
| 714 | 685084.73 | 602298.18 | 12.0 | BNDY | 7/24/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 715 | 685069.94 | 602318.33 | 12.0 | BNDY | 7/24/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 716 | 685055.15 | 602338.47 | 11.9 | BNDY | 7/24/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 717 | 685040.35 | 602358.63 | 11.9 | BNDY | 7/24/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 718 | 685025.55 | 602378.78 | 11.8 | BNDY | 7/24/2015 | 11.9 | 0.1 | Point surveyed within Tolerance |
| 719 | 685010.76 | 602398.93 | 11.8 | BNDY | 7/24/2015 | 11.9 | 0.1 | Point surveyed within Tolerance |
| 720 | 684995.96 | 602419.08 | 11.8 | BNDY | 7/24/2015 | 11.7 | -0.1 | Point surveyed within Tolerance |
| 721 | 684981.17 | 602439.24 | 11.7 | BNDY | 7/24/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 722 | 684966.37 | 602459.39 | 11.6 | BNDY | 7/24/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 723 | 684951.57 | 602479.54 | 11.5 | BNDY | 7/24/2015 | 11.5 | 0.0 | Point surveyed within Tolerance |
| 724 | 684936.78 | 602499.69 | 11.5 | BNDY | 7/24/2015 | 11.6 | 0.1 | Point surveyed within Tolerance |
| 731 | 684969.59 | 602201.11 | 6.0 | BNDY | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 732 | 684954.79 | 602221.26 | 6.3 | BNDY | 7/24/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 733 | 684939.98 | 602241.40 | 6.6 | BNDY | 7/24/2015 | 6.6 | 0.0 | Point surveyed within Tolerance |
| 734 | 684925.18 | 602261.55 | 6.9 | BNDY | 7/24/2015 | 6.8 | -0.1 | Point surveyed within Tolerance |
| 735 | 684910.37 | 602281.69 | 7.1 | BNDY | 7/24/2015 | 7.2 | 0.1 | Point surveyed within Tolerance |
| 736 | 684895.57 | 602301.83 | 7.4 | BNDY | 7/24/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 737 | 684880.76 | 602321.98 | 7.8 | BNDY | 7/24/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 738 | 684865.95 | 602342.12 | 8.2 | BNDY | 7/24/2015 | 8.2 | 0.0 | Point surveyed within Tolerance |
| 739 | 684851.15 | 602362.27 | 8.5 | BNDY | 7/24/2015 | 8.5 | 0.0 | Point surveyed within Tolerance |
| 740 | 684827.24 | 602394.80 | 9.0 | BNDY | 7/24/2015 | 8.9 | -0.1 | Point surveyed within Tolerance |
| 741 | 684821.28 | 602402.91 | 15.7 | BNDY | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 725 | 684921.98 | 602519.84 | 11.6 | BNDY | 8/10/2015 | 11.5 | -0.1 | Point surveyed within Tolerance |
| 726 | 684907.19 | 602539.99 | 11.6 | BNDY | 8/10/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 727 | 684892.39 | 602560.14 | 11.6 | BNDY | 8/10/2015 | 11.7 | 0.1 | Point surveyed within Tolerance |
| 728 | 684877.59 | 602580.30 | 11.6 | BNDY | 8/10/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 742 | 684806.74 | 602422.70 | 15.0 | BNDY | 8/10/2015 | 15.0 | 0.0 | Point surveyed within Tolerance |
| 743 | 684792.02 | 602442.92 | 14.4 | BNDY | 8/10/2015 | 14.4 | 0.0 | Point surveyed within Tolerance |
| 729 | 684862.80 | 602600.45 | 11.7 | BNDY | 8/12/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 730 | 684848.00 | 602620.60 | 11.7 | BNDY | 8/12/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 761 | 684777.12 | 602462.99 | 13.8 | BNDY | 8/12/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 762 | 684762.31 | 602483.14 | 13.2 | BNDY | 8/12/2015 | 13.1 | -0.1 | Point surveyed within Tolerance |
| 763 | 684747.51 | 602503.28 | 12.8 | BNDY | 8/12/2015 | 12.7 | -0.1 | Point surveyed within Tolerance |
| 744 | 684833.20 | 602640.76 | 11.7 | BNDY | 8/13/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 745 | 684818.41 | 602660.91 | 11.7 | BNDY | 8/13/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 764 | 684732.70 | 602523.42 | 12.5 | BNDY | 8/13/2015 | 12.4 | -0.1 | Point surveyed within Tolerance |
| 765 | 684717.90 | 602543.56 | 7.9 | BNDY | 8/13/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 766 | 684703.09 | 602563.72 | 6.7 | BNDY | 8/13/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 767 | 684687.11 | 602585.46 | 5.5 | BNDY | 8/13/2015 | 5.5 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 746 | 684803.61 | 602681.06 | 9.1 | BNDY | 9/4/2015 | 9.1 | 0.0 | Point surveyed within Tolerance |
| 747 | 684790.60 | 602698.78 | 7.5 | BNDY | 9/4/2015 | 7.6 | 0.1 | Point surveyed within Tolerance |
| 768 | 684672.87 | 602604.82 | 4.9 | BNDY | 9/4/2015 | 5.0 | 0.1 | Point surveyed within Tolerance |
| 769 | 684656.51 | 602623.72 | 5.0 | BNDY | 9/4/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 2000 | 684774.23 | 602717.67 | 12.4 | BNDY | 9/4/2015 | 12.5 | 0.1 | Point surveyed within Tolerance |
| 2001 | 684757.86 | 602736.57 | 12.9 | BNDY | 9/4/2015 | 12.8 | -0.1 | Point surveyed within Tolerance |
| 2002 | 684741.50 | 602755.47 | 13.2 | BNDY | 9/4/2015 | 13.1 | -0.1 | Point surveyed within Tolerance |
| 2003 | 684725.13 | 602774.36 | 13.5 | BNDY | 9/4/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 2004 | 684708.76 | 602793.26 | 13.8 | BNDY | 9/4/2015 | 13.7 | -0.1 | Point surveyed within Tolerance |
| 2065 | 684591.05 | 602699.29 | 6.7 | BNDY | 9/4/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 2066 | 684607.42 | 602680.39 | 6.3 | BNDY | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 2067 | 684623.78 | 602661.50 | 5.9 | BNDY | 9/4/2015 | 5.8 | -0.1 | Point surveyed within Tolerance |
| 2068 | 684640.15 | 602642.60 | 5.4 | BNDY | 9/4/2015 | 5.4 | 0.0 | Point surveyed within Tolerance |
| 2005 | 684692.39 | 602812.16 | 14.0 | BNDY | 9/9/2015 | 13.9 | -0.1 | Point surveyed within Tolerance |
| 2006 | 684676.02 | 602831.05 | 13.6 | BNDY | 9/9/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 2007 | 684659.66 | 602849.95 | 13.7 | BNDY | 9/9/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 2008 | 684643.29 | 602868.85 | 13.8 | BNDY | 9/9/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 2009 | 684626.92 | 602887.74 | 13.9 | BNDY | 9/9/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 2010 | 684610.55 | 602906.64 | 14.0 | BNDY | 9/9/2015 | 14.1 | 0.1 | Point surveyed within Tolerance |
| 2058 | 684476.47 | 602831.57 | 9.8 | BNDY | 9/9/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 2059 | 684492.84 | 602812.67 | 9.3 | BNDY | 9/9/2015 | 9.4 | 0.1 | Point surveyed within Tolerance |
| 2060 | 684509.31 | 602793.66 | 8.9 | BNDY | 9/9/2015 | 9.0 | 0.1 | Point surveyed within Tolerance |
| 2061 | 684525.58 | 602774.88 | 8.5 | BNDY | 9/9/2015 | 8.4 | -0.1 | Point surveyed within Tolerance |
| 2062 | 684541.94 | 602755.98 | 8.0 | BNDY | 9/9/2015 | 8.1 | 0.1 | Point surveyed within Tolerance |
| 2063 | 684558.31 | 602737.08 | 7.6 | BNDY | 9/9/2015 | 7.6 | 0.0 | Point surveyed within Tolerance |
| 2064 | 684574.68 | 602718.19 | 7.2 | BNDY | 9/9/2015 | 7.1 | -0.1 | Point surveyed within Tolerance |
| 2011 | 684589.12 | 602931.38 | 6.6 | BNDY | 9/16/2015 | 6.7 | 0.1 | Point surveyed within Tolerance |
| 2012 | 684575.96 | 602946.57 | 13.3 | BNDY | 9/16/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 2057 | 684459.70 | 602850.93 | 5.9 | BNDY | 9/16/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2013 | 684545.08 | 602982.23 | 13.8 | BNDY | 9/18/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 2014 | 684561.45 | 602963.33 | 14.7 | BNDY | 9/18/2015 | 14.8 | 0.1 | Point surveyed within Tolerance |
| 2015 | 684528.71 | 603001.12 | 12.8 | BNDY | 9/18/2015 | 12.8 | 0.0 | Point surveyed within Tolerance |
| 2016 | 684512.34 | 603020.02 | 11.9 | BNDY | 9/18/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 2017 | 684495.97 | 603038.92 | 11.0 | BNDY | 9/18/2015 | 11.1 | 0.1 | Point surveyed within Tolerance |
| 2051 | 684361.89 | 602963.84 | 6.7 | BNDY | 9/18/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 2052 | 684378.26 | 602944.95 | 7.7 | BNDY | 9/18/2015 | 7.8 | 0.1 | Point surveyed within Tolerance |
| 2053 | 684394.63 | 602926.05 | 8.9 | BNDY | 9/18/2015 | 9.0 | 0.1 | Point surveyed within Tolerance |
| 2054 | 684411.00 | 602907.15 | 10.1 | BNDY | 9/18/2015 | 10.0 | -0.1 | Point surveyed within Tolerance |
| 2055 | 684427.94 | 602887.59 | 8.4 | BNDY | 9/18/2015 | 8.5 | 0.1 | Point surveyed within Tolerance |
| 2056 | 684443.73 | 602869.36 | 10.4 | BNDY | 9/18/2015 | 10.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2018 | 684479.61 | 603057.81 | 10.1 | BNDY | 9/23/2015 | 10.1 | 0.0 | Point surveyed within Tolerance |
| 2019 | 684463.24 | 603076.71 | 9.2 | BNDY | 9/22/2015 | 9.1 | -0.1 | Point surveyed within Tolerance |
| 2020 | 684446.87 | 603095.61 | 8.3 | BNDY | 9/22/2015 | 8.3 | 0.0 | Point surveyed within Tolerance |
| 2021 | 684430.50 | 603114.50 | 7.5 | BNDY | 9/22/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2022 | 684414.13 | 603133.40 | 6.8 | BNDY | 9/23/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2023 | 684397.77 | 603152.30 | 6.3 | BNDY | 9/23/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2046 | 684280.05 | 603058.33 | 4.2 | BNDY | 9/23/2015 | 4.2 | 0.0 | Point surveyed within Tolerance |
| 2047 | 684296.42 | 603039.43 | 4.3 | BNDY | 9/23/2015 | 4.3 | 0.0 | Point surveyed within Tolerance |
| 2048 | 684312.79 | 603020.53 | 4.6 | BNDY | 9/23/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 2049 | 684329.16 | 603001.64 | 5.1 | BNDY | 9/22/2015 | 5.1 | 0.0 | Point surveyed within Tolerance |
| 2050 | 684345.53 | 602982.74 | 5.8 | BNDY | 9/22/2015 | 5.8 | 0.0 | Point surveyed within Tolerance |
| 2024 | 684381.40 | 603171.20 | 6.5 | BNDY | 9/23/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2045 | 684263.69 | 603077.22 | 5.9 | BNDY | 9/23/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2025 | 684365.03 | 603190.09 | 6.6 | BNDY | 9/24/2015 | 6.5 | -0.1 | Point surveyed within Tolerance |
| 2026 | 684348.66 | 603208.99 | 6.8 | BNDY | 9/24/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2027 | 684332.29 | 603227.89 | 6.8 | BNDY | 9/28/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2028 | 684315.93 | 603246.78 | 7.7 | BNDY | 9/28/2015 | 7.8 | 0.1 | Point surveyed within Tolerance |
| 2041 | 684198.59 | 603153.14 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2042 | 684214.58 | 603133.91 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2043 | 684230.98 | 603114.98 | 4.6 | BNDY | 9/24/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 2044 | 684247.32 | 603096.12 | 6.2 | BNDY | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2029 | 684299.56 | 603265.68 | 7.9 | BNDY | 9/28/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 2040 | 684182.05 | 603171.63 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2030 | 684283.19 | 603284.58 | 8.1 | BNDY | 10/7/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2031 | 684258.41 | 603313.18 | 8.2 | BNDY | 10/7/2015 | 8.1 | -0.1 | Point surveyed within Tolerance |
| 2032 | 684238.18 | 603303.29 | 7.1 | BNDY | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2033 | 684215.72 | 603292.32 | 6.8 | BNDY | 10/7/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2034 | 684193.26 | 603281.34 | 6.5 | BNDY | 10/7/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2035 | 684170.80 | 603270.36 | 6.4 | BNDY | 10/7/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 2036 | 684148.33 | 603259.38 | 6.3 | BNDY | 10/7/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2037 | 684124.13 | 603238.34 | 6.1 | BNDY | 10/7/2015 | 6.2 | 0.1 | Point surveyed within Tolerance |
| 2038 | 684149.11 | 603209.50 | 6.1 | BNDY | 10/7/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2039 | 684165.48 | 603190.60 | 6.1 | BNDY | 10/7/2015 | 6.2 | 0.1 | Point surveyed within Tolerance |
| 2305 | 684268.00 | 603302.11 | 8.1 | BNDY | 10/7/2015 | 8.2 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

**Per SPECIFICATION 01460 SURVEY. SECTION 1.05 F. Spot Elevations - Survey shall be constructed to provide an accuracy of 0.1 feet vertically. Ninety percent of all spot elevations placed on the maps shall have an accuracy of at least 0.1', and the remaining 10 percent shall not be in error by more than one-half (1/2) the contour interval (0.5'). Break points added to replace Grid Points that fell on slopes and Boundary Points will be treated as Spot Elevations as defined in Section 1.05 F.**

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Grid Points depicted in Table 1, Break Points in Table 2, Boundary Points in Table 3, and topographic spot elevations are correct, and representative of the as-built cap subgrade throughout the SA6 South cap.**


R. Thomas Hugg 2/12/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

# *D2. Subgrade Construction Control Grid*




MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER
12001151A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

CONSTRUCTION CONTROL GRID
CAP SUBGRADE SURVEY

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 2/12/16 | ISSUED FOR CLIENT REVIEW | | |

DSGN | DR | CHK | APVD

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

DATE 2/12/16
PROJ 3480-10-0027
DWG
SHEET 1 OF 1

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Users\bonton\Desktop\Trough\12001511A\Subgrade data\South Cap Subgrade Location Map - Final draft 2.dwg PLOT DATE: Fri, 12 Feb 2016 PLOT TIME: 2:56 PM

# Appendix E: Soil Subgrade Approval

*E1. ESI Certificate of Subgrade Surface Acceptance*

*E2. Langan Certificate of Soil Surface*

# *E1. ESI Certificate of Subgrade Surface Acceptance*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

**INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.**

PROJECT NAME: Honeywell PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Approx. 14,703 sf.

PANEL NUMBERS: 1 TO 4

GRADE ACCEPTANCE: INSPECTOR:

GENERAL CONTRACTOR: ENTACT

OWNER:

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala, certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/20/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Signature | Title | DATE |
|---|---|---|
| | Project Superintendent | 7/20/15 |

| | | |
|---|---|---|
| | INDEPENDENT CQA MONITOR | 7/20/15 |

OWNER REPRESENTATIVE

| Signature | Title | DATE |
|---|---|---|
| Carolina Ramos | QC Manager | 7/20/15 |

7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,680 SF.

PANEL NUMBERS: 5 TO 9 over composite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/21/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/21/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| | INDEPENDENT EQA MONITOR | 7/21/15 |
|---|---|---|

OWNER REPRESENTATIVE

| | QC Manager | 7-21-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,726 SF

PANEL NUMBERS: 10 TO 13 over Geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/22/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/22/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7-22-15 |

OWNER REPRESENTATIVE

| Carolyn Parnell | QC Manager | 7-22-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 18,495 SF

PANEL NUMBERS: 14 TO 18 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

NOTE: SUBGRADE APPROVED BUT NOT COVERED AREA, 11,300 SF.

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/23/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/23/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7-23-15 |

OWNER REPRESENTATIVE

| Carolyn Parnes | QC Manager Entact | 7-23-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 22,140 SF

PANEL NUMBERS: 19 to 24 Over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/24/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/24/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7/24/15 |

OWNER REPRESENTATIVE

| Carolyn Vorres | QC Manager - Entact | 7-24-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 22,005 S.F.

PANEL NUMBERS: 25 to 30 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/28/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 7/28/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7/28/15 |

OWNER REPRESENTATIVE

| | QC Manager - Entact | 7/28/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,693 SF

PANEL NUMBERS: 31 to 34 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/29/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 7/29/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7/29/15 |
| OWNER REPRESENTATIVE | | |
| Carolyn Parnell | QC Manager - Entact | 7/29/15 |
| *Signature* | *Title* | *DATE* |

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 20,226 sf

PANEL NUMBERS: 35 to 46 most over GCL

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/3/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/3/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | Independent CQA Monitor | 8/3/15 |

OWNER REPRESENTATIVE

| | QC Manager-Engr | 8-3-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 11003 sf

PANEL NUMBERS: 47 to 49 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/5/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/05/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 8/5/15 |

OWNER REPRESENTATIVE

| Caroline Ramos | QC Manager / Enfotech | 8/5/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 15,120 sf

PANEL NUMBERS: 90 to 94 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/6/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/6/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT QA MONITOR | 8/6/15 |

OWNER REPRESENTATIVE

| | QC Manager Entact | 8/6/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 13,230 sf

PANEL NUMBERS: 55 to 60 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/7/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/7/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 8/7/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| Carolyn Ramos | QC Manager - Entact | 8-7-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 18,309 SF

PANEL NUMBERS: 61 to 65 and perimeter soil tie

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/10/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 8/10/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 8/10/15 |

OWNER REPRESENTATIVE

| Carolyn Parnes | QC Manager Entact | 8/10/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 18,225 SF

PANEL NUMBERS: 66 to 71 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/13/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/13/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 8/13/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| Carolina Parra | QC Manager Entact | 8/13/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,705 SF

PANEL NUMBERS: P- 72 to 75 Over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 14-Aug and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 14-Aug |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 8/14/15 |

OWNER REPRESENTATIVE

| | QC Manager - Entact | 8-14-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER ENVIRONMENTAL SPECIALTIES INTERNATIONAL INC

PROJECT NAME Honeywell Chromium Area PROJECT NO 12-11-1399

LOCATION Jersey City, NJ

AREA ACCEPTED Aprox 14 705 SF

PANEL NUMBERS P- 76 to 86 over GCL

GRADE ACCEPTANCE INSPECTOR AMEC

GENERAL CONTRACTOR ENTACT

OWNER Honeywell

AUTHORIZED REPRESENTATIVE

The undersigned Fortino Ayala certifies that he/she is a representative of Environmental Specialties International Inc authorized to execute this certificate that he/she has visually inspected the subgrade surface described above on 9-Sep and found the surface to be acceptable for installation of the geomembrane

This certification is based on observation of the surface of the subgrade only No subsurface inspections or test have been performed and Environmental Specialties International Inc makes no representations or warranties regarding conditions which may exist below the surface of the subgrade

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 9-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| | INDEPENDENT CQA MONITOR | 9/9/15 |
|---|---|---|

OWNER REPRESENTATIVE

| Carolyn Ramos | QC Mgr - Entact | 9-9-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

7941 PECUE LANE SUITE A - BATON ROUGE, LA 70809 - PHONE 225 291 2700 - FAX 225-291 2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 15,075 SF

PANEL NUMBERS: P- 87 to 90 Over subgrade.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 15-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| *Fortino Ayala* | Project Superintendent | 15-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| [signature] | INDEPENDENT CQA MONITOR | 9/15/15 |

OWNER REPRESENTATIVE

| [signature] | QC Manager - Entact | 9-15-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,963 SF

PANEL NUMBERS: P- 91 to 94 Over subgrade.

GRADE ACCEPTANCE: INSPECTOR. AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 16-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 16-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/16/15 |

OWNER REPRESENTATIVE

| | QC Manager-Gator | 9-16-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 11,205 SF

PANEL NUMBERS: P- 95 to 97 Over subgrade.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 17-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 17-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

INDEPENDENT CQP MONITOR 9/17/15

OWNER REPRESENTATIVE

| Caroline Slamin | QC Manager | 9-17-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 11,070 SF

PANEL NUMBERS: P- 98 to 106 Over subgrade and some over GCL

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 18-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 18-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/18/15 |
| OWNER REPRESENTATIVE | | |
| Caroline Pavia | QC Manager | 9-18-15 |
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,625 SF

PANEL NUMBERS: P- 107 to 110 Over subgrade

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 22-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 22-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 9/22/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| Carlton Parris | QC Manager | 9-22-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,569 SF

PANEL NUMBERS: P- 111 to 114 Over subgrade

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 23-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 23-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/23/15 |

OWNER REPRESENTATIVE

| | QC Manager - Entact | 9-23-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,681 SF

PANEL NUMBERS: P- 115 to 118 Over subgrade

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 24-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 24-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/24/15 |

OWNER REPRESENTATIVE

| Carolyn Lanier | QC Manager Entact | 9-24-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 7,425 SF

PANEL NUMBERS: P- 119 to 120 Over subgrade, some liner over GCL at ditch design.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 25-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 25-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/25/15 |
| OWNER REPRESENTATIVE | | |
| Carolyn Lance | QC Manager Entact | 9-25-15 |
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,895 SF

PANEL NUMBERS: P- 121 to 125 Over subgrade, some liner over GCL at ditch and perim.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 29-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 29-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 9/29/15 |
|---|---|---|

| Jaclyn Pasco | QC Manager - Entact | 9-29-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 15,205 SF

PANEL NUMBERS: P- 126 to 134 Over subgrade, some liner over GCL At cap design .

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8-Oct and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8-Oct |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 10/8/15 |

OWNER REPRESENTATIVE

| Caroline Parnell | QC Mgr - Entact | 10/8/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# *E2. Langan Certificate of Soil Surface*

**LANGAN**

# Certificate of Soil Surface

Sheet # 1

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 24+35 TO STA 23+35 (WEST END) | | |
| QA Monitor | LANGAN | Date | 7/20/2015 | | |

Description of Soil Surface to be lined: WEST END OF SA-6 SOUTH (~STA. 24+35) TO APPROX. 100 FT. EAST (STA. 23+35) - RUNNING NORTH TO SOUTH THROUGH APPROX. GRID POINT ~~8~~ 13.09. SOIL APPEARS TO BE GRADED, COMPACTED AND FREE OF DEBRIS (> ½"), AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/20/15 |
| Title | ~~SENIOR STAFF~~ LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-20-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | WEST END | N-S | REFER TO PHOTOGRAPH LOG (11/20/15) |
| | 2 | WEST END | N-S | PHOTOS 2, 3, 4 W/ DESCRIPTIONS |
| 1. REFER TO PHOTO LOG (11/20/15) PHOTOS 2, 3, 4 FOR CORRESPONDING PHOTOS | | | | 2. |

**LANGAN**

# Certificate of Soil Surface

Sheet # 2

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 23+35 to ~Sta. 22+35 | | |
| QA Monitor | Langan | Date | 7/21/2015 | | |

Description of Soil Surface to be lined: Area immediately East from subgrade approval on 7/20/15. Located from approx. Sta. 23+35 to Sta. 22+35 (100 ft. East from installed GCL on 7/20/15. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/21/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-22-15 |
| Title | Install QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8.
GEOMEMBRANE CAP PANELS 5-9 PLACED OVER AREA.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | STA. 23+35 | LOOKING EAST | REFER TO PHOTO LOG (7/21/15), PHOTO #9 |
| | 2 PHOTO #10 | STA 23+35 | EAST/SOUTHEAST | REFER TO PHOTO LOG (7/21/15), PHOTO #10 |

1. REFER TO PHOTO LOG (7/21/15) PHOTOS 9,10 FOR SUPPORTING SUBGRADE PHOTOS

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 3

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530601 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 22+35 TO STA. 21+40 | | |
| QA Monitor | LANGAN | Date | 7/22/15 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST FROM PREVIOUSLY APPROVED SUBGRADE ON 7/21/15. LOCATED FROM APPROX. STA. 22+35 TO STA. 21+40 (APPROX. 95 FT EAST OF GEOMEMBRANE INSTALLED ON 7/21/15. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/22/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-23-15 |
| Title | QC Manager |
| Representing: | Enhul |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (7 ½")
As outlined in Section 02372-8

Geomembrane Cap Panels 10-13 Placed over Area

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo # 2 | | Looking East | Refer to Photo Log (7/22/15) Photo # 2 |
| | 2 Photo # 3 | | Looking NE | Refer to Photo Log (7/22/15) Photo # 3 |

1. Refer to Photo Log (7/22/15)
Photos 2, 3 for Supporting Subgrade Photos

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 4

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / ANECFW | Cell No. | ~STA. 21+40 TO STA. 19+90 | | |
| QA Monitor | LANGAN | Date | 7/23/15 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST FROM PREVIOUSLY APPROVED SUBGRADE ON 7/22/15. LOCATED FROM APPROXIMATE STATION STA. 21+40 (~P-13') TO STA. 19+90 (APPROX 150 FT. EAST OF GEOMEMBRANE INSTALLED ON 7/22/15). SOIL APPEARS TO BE GRADED, COMPACTED + FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/23/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-23-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: Soil Graded, Compacted, And Fiber of Debris (2½") As outlined In Section 023572-8.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #3 | Sta 21.40 | Looking East | Refer to Photo Log (7/23/15) Photo #3 |
| | 2 Photo #5 | Sta 21+00 | Looking NE | Refer to Photo Log (7/23/15) Photo #5 |
| 1. Refer to Photo Log (7/23/15) Photos 3.5 For Supporting Subgrade Photos Additional Subgrade Details Also Shown on Photos 4+6 | | | | 2. |

**LANGAN**

# Certificate of Soil Surface

Sheet # 5

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / ARMEC FW | Cell No. | ± STA. 19+90 TO STA. 19+00 | | |
| QA Monitor | LANGAN | Date | 7/24/15 | | |

Description of Soil Surface to be lined: ADDITIONAL ± 90 FT. SECTION OF SOIL APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 7/23/15 (P-18). SUBGRADE APPROVED FROM ± STA. 19+90 TO STA. 19+00 (SUBGRADE PREVIOUSLY APPROVED TO STA. 19+90) / GEOMEMBRANE INSTALLED TO ± STA. 20+25 ON 7/23/15). SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (> ½"), AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/24/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-24-15 |
| Title | QC Manager Entact |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02372-8.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #8 | STA 20+25 | LOOKING EAST | REFER TO PHOTO LOG (11/24/15) PHOTO #8 |
| | 2 PHOTO #9 | STA. 19+80 | LOOKING SOUTH | REFER TO PHOTO LOG (11/24/15) PHOTO #9 |

1. REFER TO PHOTO LOG (11/24/15) PHOTOS 8,9 FOR SUPPORTING SUBGRADE PHOTOS

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 6

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 19+00 TO STA. 18+20 | | |
| QA Monitor | LANGAN | Date | 7/28/15 | | |

Description of Soil Surface to be lined: ADDITIONAL ~80 FT. SECTION OF SOIL APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 7/24/15 (P-24). NO SUBGRADE APPROVED ON 7/27/15. SUBGRADE APPROVED FROM ~STA. 19+00 TO STA. 18+20. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/28/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Ponce |
| Date: | 7-28-15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

-ADDITIONAL ~40 FT. OF SOIL APPROVED AT END OF DAY TO ALLOW ESI TO INSTALL EXTRA 2 PANELS OF GEOMEMBRANE. SOIL APPROVED TO APPROX. STA 17+80.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~BD 6775.15 | LOOKING NW | REFER TO PHOTO LOG (11/25/15) PHOTO #3 |
| | 2 PHOTO #4 | ~19.00 | LOOKING EAST | REFER TO PHOTO LOG (11/25/15) PHOTO #4 |
| 1. REFER TO PHOTO LOG (11/25/15) PHOTOS 3, 4, 5 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

**LANGAN**

# Certificate of Soil Surface

Sheet # 7

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 117+80 to Sta. 117+00 | | |
| QA Monitor | Langan | Date | 7/29/15 | | |

Description of Soil Surface to be lined: ~80 ft. Section of Soil Approved East of Geomembrane Panels Installed on 7/28/15 (P-30). Subgrade Approved From Approx. Sta. 117+80 to Sta. 117+00, Soil Appears to Be Graded, Compacted, And Free of Debris (>½"), and in Conformance With Project Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/29/30 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/29/30 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED UP TO 1ST UTILITY CORRIDOR

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | STA. 17+80 | LOOKING N | REFER TO 7/29/15 PHOTO LOG PHOTO #5 |
| | 2 PHOTO #8 | SEND CAP | LOOKING E | REFER TO 7/29/15 PHOTO LOG PHOTO #8 |

1. REFER TO PHOTO LOG (7/29/15)
PHOTOS 5, 8 FOR SUPPORTING SUBGRADE PHOTOS

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 8

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 17+00 to Sta. 15+80 | | |
| QA Monitor | Langan | Date | 8/3/15 | | |

Description of Soil Surface to be lined: ~120 ft. Section of Soil Approved East of Geomembrane Panels Installed on 7/29/15 (P-34). Subgrade Approved From Approx. Sta. 17+00 to Sta. 15+80 (to East Side of 1st Utility Corridor) Through 1st Utility Corridor. Soil Appears to Be Graded, Compacted, And Free of Debris (>½") And in Conformance w/ Project Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/3/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | Cathleen Parrino - Entrust QC Manager |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED FOR GCL PLACEMENT WITHIN UTILITY CORRIDOR + GEOMEMBRANE / GVL PLACEMENT OUTSIDE OF CORRIDOR

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | CORRIDOR | LOOKING N | REFER TO 8/3/15 PHOTO LOG PHOTO #1 |
| | 2 PHOTO #3 | CORRIDOR | LOOKING S | REFER TO 8/3/15 PHOTO LOG PHOTO #3 |

1. REFER TO PHOTO LOG (8/3/15) PHOTOS 1, 2, 3 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 9

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 15+80 TO ~STA. 15+10 | | |
| QA Monitor | LANGAN | Date | 8/5/15 | | |

Description of Soil Surface to be lined: ~170 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/3/15 (P-42). SUBGRADE APPROVED FROM ~STA. 15+80 TO ~STA. 15+10. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/5/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-5-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7 ½")
AS OUTLINED IN SECTION 02372-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT ABOVE) GROUNDWATER ELEVATION

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | GP 165-15.4 | LOOKING W | REFER TO 8/5/15 PHOTO LOG PHOTO #5 |
| | 2 PHOTO #6 | STA. 15+80 | LOOKING S | REFER TO 8/5/15 PHOTO LOG PHOTO #6 |
| 1. REFER TO PHOTO LOG (8/5/15) PHOTOS 5, 6 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 10


| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 15+10 to ~Sta 14+00 | | |
| QA Monitor | Langan | Date | 8/6/15 | | |

Description of Soil Surface to be lined: ~110 ft. Section of soil subgrade approved East of Geomembrane Panels installed on 8/5/15 (P-49). Subgrade Approved From ~Sta. 15+10 to ~Sta. 14+00. Soil Appears to Be Graded, Compacted, And Free of Debris (7½") And In Conformance With Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/6/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-6-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #17 | ± STA. 15+10 | LOOKING E | REFER TO 8/6/15 PHOTO LOG (PHOTO #17) |
| | 2 PHOTO #9 | ± STA. 15+10 | LOOKING S | REFER TO 8/6/15 PHOTO LOG (PHOTO #9) |
| 1. REFER TO PHOTO LOG (8/6/15) PHOTOS 17, 8, AND 9 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 11

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 14+00 to ~Sta. 13+00 | | |
| QA Monitor | Langan | Date | 8/7/15 | | |

Description of Soil Surface to be lined: ~100 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 8/6/15 (P-54). Subgrade Approved From ~Sta. 14+00 to ~Sta. 13+00. Soil Appears to Be Graded, Compacted, And Free of Debris (7½") And in Conformance With Project Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/7/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/7/15 |
| Title | QC Manager |
| Representing: | Entech |
| Signature: | |

LANGAN

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (> 1/2")
As outlined in Section 02317Z-8.
- No GCL Placed As Area Was Above Water Table (~1 ft.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #6 | Sta. 14+00 | Looking E | Refer to 8/17/15 Photo Log (Photo #6) |
| | 2 | | | |

1. Refer to Photo Log (8/17/15) Photo 6 For Supporting Subgrade Photos

2.

LANGAN

# Certificate of Soil Surface

Sheet # 12

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 13+00 to ~Sta. 12+00 | | |
| QA Monitor | Langan | Date | 8/10/15 | | |

Description of Soil Surface to be lined: ~100 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 8/7/15 (P-60). Subgrade Approved From ~Sta. 13+00 to ~Sta. 12+00 Soil Appears to be Graded, Compacted, and Free of Debris (> ½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/10/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Parnio |
| Date: | 8/10/15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (> 1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | 2 STA. 13+00 | LOOKING N | REFER TO 8/10/15 PHOTO LOG (PHOTO #5) |
| | 2 PHOTO #6 | 2 STA. 13+00 | LOOKING E | REFER TO 8/10/15 PHOTO LOG (PHOTO #6) |

1. REFER TO PHOTO LOG (8/10/15) PHOTOS #5, 6 FOR SUPPORTING SUBGRADE PHOTOS.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 13

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 12+00 TO ~STA. 11+00 | | |
| QA Monitor | LANGAN | Date | 8/13/15 | | |

Description of Soil Surface to be lined: ~100 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/10/15 (P-65). SUBGRADE APPROVED FROM ~STA. 12+00 TO ~STA. 11+00. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | N/A |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/13/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-13-15 |
| Title | QC Manager |
| Representing: | Entrac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (>1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | @ STA 11+50 | LOOKING SW | REFER TO 8/13/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | @ STA 11+50 | LOOKING SE | REFER TO 8/13/15 PHOTO LOG (PHOTO #2) |

1. REFER TO PHOTO LOG (8/13/15) PHOTOS 1, 2 FOR SUPPORTING SUBGRADE PHOTOS.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 14


| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 11+00 TO ~STA. 10+20 | | |
| QA Monitor | LANGAN | Date | 8/14/15 | | |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/13/15 (P-171). SUBGRADE APPROVED FROM STA. 11+00 TO ~STA. 10+20. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/14/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-14-15 |
| Title | QC Manager |
| Representing: | Entrada |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |
| 1. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 15

| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | Honeywell / AmecFW | Cell No. | ~Sta. 10+20 to ~Sta. 9+50 |
| QA Monitor | Langan | Date | 9/9/15 |

Description of Soil Surface to be lined: ~770 ft. section of soil subgrade approved east of geomembrane panels installed on 8/14/15 (p.175). Subgrade approved through 2nd utility corridor from approx. Sta. 10+20 to Sta. 9+50. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/9/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/9/15 |
| Title | QC Manager |
| Representing: | ENTACT |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 023172-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG EASTERN + WESTERN SLOPES OF UTILITY CORRIDOR + SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN END OF SA-6 AREA BELOW (TO 1FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | ~STA 10+00 | LOOKING SW | REFER TO 9/9/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | ~STA. 10+00 | LOOKING NE | REFER TO 9/9/15 PHOTO LOG (PHOTO #3) |

1. REFER TO PHOTO LOG (9/9/15) PHOTOS 2,3 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 16

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) Operations LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 9+50 TO ~STA. 8+50 |
| QA Monitor | LANGAN | Date | 9/15/15 |

Description of Soil Surface to be lined: ~100 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/9/15 (P-86). SUBGRADE APPROVED EAST OF 2ND UTILITY CORRIDOR FROM APPROX. STA. 9+50 TO ~STA. 8+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/15/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-15-15 |
| Title | Entact QC Manager |
| Representing: | ENTACT |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8

~~THE~~ GCL PLACED ALONG SOUTHERN SLOPE OF SA-6 SOUTH (LOWER BENCH) AT AREA BELOW (TO 1FT. ABOVE) GROUNDWATER TABLE

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 9+50 | LOOKING S | REFER TO 9/15/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 9+50 | LOOKING E | REFER TO 9/15/15 PHOTO LOG |
| 1. REFER TO PHOTO LOG (9/15/15) PHOTOS 1,2 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 17

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 8+50 TO ~STA. 7+70 | | |
| QA Monitor | LANGAN | Date | 9/16/15 | | |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/15/15 (P-90). SUBGRADE APPROVED FROM APPROXIMATE STA. 8+50 (P-90) TO APPROX STA. 7+70. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/16/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/16/15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02372-8

NO GCL PLACED ALONG SA-6 AS AREAS OUTSIDE OF GROUNDWATER ZONE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #17 | ~STA 8+80 | LOOKING N/NE | REFER TO 9/16/15 PHOTO LOG (PHOTO #17) |
| | 2 | | | |

1. REFER TO PHOTO LOG (9/16/15) PHOTO #17 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 18

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell 5A-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Arlec FW | Cell No. | ~Sta. 7+70 to ~Sta. 7+00 | | |
| QA Monitor | Langan | Date | 9/17/15 | | |

Description of Soil Surface to be lined: ~70 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/16/15 (P-94). Subgrade Approved From Approximate Sta. 7+70 (P-94) to Approximate Sta. 7+00 (western slope of 3rd utility corridor). Soil Appears to be Graded, compacted, and Free of Debris (>1½") and in conformance with Project Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/17/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/17/15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (1 1/2") AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED ALONG SA-6 AS NO AREAS BELOW (TO 1 FT. ABOVE) GROUNDWATER

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |
| 1. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 19

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 7+00 TO ~STA. 6+40 | | |
| QA Monitor | LANGAN | Date | 9/18/15 | | |

Description of Soil Surface to be lined: ~60 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/17/15 (P-97). SUBGRADE APPROVED THROUGH 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 7+00 TO ~STA. 6+40 (EASTERN SIDE OF 3RD UTILITY CORRIDOR). SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/18/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/18/15 |
| Title: | QC Manager |
| Representing: | Entek |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 023172-8.

- GCL PLACED ALONG BOTTOM AND SIDE SLOPES (APPROX 2 FT. TO 3FT. EACH BOTTOM) OF 3RD UTILITY CORRIDOR (LOCATED AT APPROX. STA. 6+80). GCL ALSO PLACED ALONG SOUTHERN END OF CORRIDOR (LOWER BENCH) BELOW TO 1 FT. ABOVE WATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 6+80 | LOOKING S | REFER TO 9/18/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 6+86 | LOOKING N | REFER TO 9/18/15 PHOTO LOG (PHOTO #2) |
| 1 REFER TO PHOTO LOG (9/18/15) PHOTOS 1, 2 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2 |

LANGAN

# Certificate of Soil Surface


Sheet # 20


| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 6+40 TO ~STA. 5+30 | | |
| QA Monitor | LANGAN | Date | 9/22/15 | | |

Description of Soil Surface to be lined: ~110 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/18/15 (P-98-103 / EAST-WEST ORIENTATION). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 6+40 TO ~STA. 5+30. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/22/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-22-15 |
| Title: | QC manager |
| Representing: | Entact |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS APPROVED SUBGRADE OUTSIDE OF WATER TABLE INFLUENCE. ONLY GVL REQUIRED

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | 25TH. 6+40 | LOOKING N | REFER TO 9/22/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | 25TH 5+90 | LOOKING S | REFER TO 9/22/15 PHOTO LOG (PHOTO #3) |
| 1 REFER TO PHOTO LOG (9/22/15) PHOTOS 1, 2, 3 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2 |

LANGAN

# Certificate of Soil Surface

Sheet # 21

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 5+30 TO ~STA. 4+50 | | |
| QA Monitor | LANGAN | Date | 9/23/15 | | |

Description of Soil Surface to be lined: ~480 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEO-MEMBRANE PANELS INSTALLED ON 9/22/15 (PANEL #110). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 5+30 TO APPROX. STA. 4+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BUSWORTH |
| Date: | 9/23/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9-23-15 |
| Title: | QC Manager |
| Representing: | Caroline Panico |
| Signature: | ENTACT |

LANGAN

Notes, Observations, Comments SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8.

- GCL PLACED ALONG NORTHERN AND SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO 1FT. ABOVE) THE GROUNDWATER TABLE AS SHOWN ON PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 4+90 | LOOKING S | REFER TO 9/23/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 4+70 | LOOKING W | REFER TO 9/23/15 PHOTO LOG (PHOTO #2) |

1 REFER TO PHOTO LOG (9/23/15) PHOTOS 1, 2 FOR SUPPORTING SUBSURFACE PHOTOS

2

LANGAN

# Certificate of Soil Surface

Sheet # 22


| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / AMEC FW | Cell No. | ~Sta. 4+50 to ~Sta. 3+80 | | |
| QA Monitor | Langan | Date | 9/24/15 | | |

Description of Soil Surface to be lined: ~480 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/23/15 (Panel N114). Subgrade Approved for Area East of 3rd Utility Corridor From Approximate Sta. 4+50 to Approx. Sta. 3+80. Soil Appears to Be Graded, Compacted, and Free of Debris (>½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/24/15 |
| Title: | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-24-15 |
| Title: | QC Manager |
| Representing: | Entrie |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8

- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO 1FT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG BOTTOM + SLOPES OF UTILITY/DRAINAGE DITCHES RUNNING N-S THROUGH SA-6, AND AS SHOWN ON THE PROJECT DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 4+50 | LOOKING S | REFER TO 9/24/15 PHOTO LOG (PHOTO #3) |
| | 2 PHOTO #4 | ~STA. 4+50 | LOOKING E | REFER TO 9/24/15 PHOTO LOG (PHOTO #4) |

1 REFER TO PHOTO LOG (9/24/15) PHOTOS 3,4 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR PICTURES OF GCL

2

LANGAN

# Certificate of Soil Surface

Sheet # 23

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 3+80 to ~Sta. 3+30 | | |
| QA Monitor | Langan | Date | 9/25/15 | | |

Description of Soil Surface to be lined: ~ 50 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/24/15 (Panel #118). Subgrade Approved for Area East of 3rd Utility Corridor From Approximate Sta. 3+80 to Approx. Sta. 3+30. Soil Appears to Be Graded, Compacted, and Free of Debris (>½") and In Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/25/15 |
| Title: | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-25-15 |
| Title: | QC Manager |
| Representing: | Entuck |
| Signature: | Carolina Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8

- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AND AT AREAS BELOW (TO 1 FT. ABOVE) THE GROUNDWATER TABLE, AS DEFINED ON THE PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | ~STA. 3+50 | LOOKING E | REFER TO 9/25/15 PHOTO LOG (PHOTO #5) |
| | 2 PHOTO #6 | ~STA. 3+40 | LOOKING N | REFER TO 9/25/15 PHOTO LOG (PHOTO #6) |
| 1 REFER TO PHOTO LOG (9/25/15) PHOTOS 5,6 FOR SUPPORTING SUBGRADE PHOTOS (WITH GCL) | | | | 2 |

LANGAN

# Certificate of Soil Surface

Sheet # 24

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 3+30 TO ~STA. 2+50 |
| QA Monitor | LANGAN | Date | 9/29/15 |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/25/15 (PANEL #120). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 3+30 TO APPROX. STA. 2+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ¼, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name | DANIEL BOSWORTH |
| Date | 9/29/15 |
| Title | LEAD QA ENGINEER |
| Representing | LANGAN |
| Signature | |

| Geosynthetic Installer Representative | |
|---|---|
| Name | Carolina Panico |
| Date | 9-29-15 |
| Title | QC Manager |
| Representing | Entact |
| Signature | Carolina Panico |

LANGAN

Observations/Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AS OUTLINED IN SECTION 02372-8.

- GCL PLACED ALONG NORTHERN & SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW, (TO 1 FT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG LOWER BENCH ON EASTERN END OF SA-6 AS SHOWN ON THE PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | STA. 3+30 | LOOKING S | REFER TO 9/29/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | STA. 2+90 | LOOKING E | REFER TO 9/29/15 PHOTO LOG (PHOTO #3) |

1 REFER TO PHOTO LOG (9/29/15) PHOTOS 2,3 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR PICTURES OF GCL.

2

LANGAN

# Certificate of Soil Surface

Sheet # 25

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 2+50 to ~Sta 1+50 | | |
| QA Monitor | Langan | Date | 10/8/2015 | | |

Description of Soil Surface to be lined: ~100 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/29/15 (Panel # 125). Subgrade Approved for Area East of 3rd Utility Corridor from Approximate Sta. 2+50 to Approx. Sta. 1+50 (Eastern End of SA-6, Route 440). Soil Anchors to be Graded, Compacted, and Free of Debris (>½") and in Conformance w/ Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 10/8/2015 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 10/8/15 |
| Title | QC Manager |
| Representing: | ENTACT |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8
- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO LFT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG LOWER BENCH ON EASTERN END OF SA-6 AS SHOWN ON PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 1+70 | LOOKING N/NW | REFER TO 10/8/15 PHOTO LOG (PHOTO #3) |
| | 2 PHOTO #4 | ~STA. 2+00 | LOOKING S | REFER TO 10/8/15 PHOTO LOG (PHOTO #4) |
| 1 REFER TO PHOTO LOG (10/8/15) PHOTOS 3,4 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR SUPPORTING PHOTOS OF GVL + GCL | | | | 2 |

# Appendix F
# Langan Daily Reports & Supporting Photo Logs

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/7/2015 |
| **PROJECT:** | SA-6 Capping | | **WEATHER:** | 75/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Soil Subgrade Inspection | **TIME:** | 0600 – 1400 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #1** |
|---|---|
| **Thatcher Foundations**<br>*Equipment:* Dozer, Steel Drum Roller, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT**: Keith Goisse |

## ***Site Activities***

- Langan onsite to conduct soil subgrade inspection. Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area.
- Langan and ENTACT (two laborers) conducted visual inspection of the prepared soil subgrade. This area included the furthest western part of the cap (Sta. 24+00) to just east of Sta. 18+50.
- In general, the following soil subgrade properties were observed:
  - Some debris (wood fragments),small rocks, etc. were observed along the slopes and elevation changes from Sta. 24+00 to Sta. 18+50. It is recommended during the pull back and removal of the plastic tarp (in preparation for installation of liner), ENTACT should provide laborers with a wheelbarrow and equipment to collect various debris as it is encountered.
  - Along the slopes of the smaller swales, utility corridors, street channels, etc. some soft and loose material was noted. As recommended above, as the plastic is removed for liner installation activities, Entact should provide laborers to dress the slopes (i.e. remove any loose debris and conduct compaction (as required) with a hand tamper), as necessary.
- In addition to the general soil subgrade properties outlined above, some soft / wet areas (some with free standing water) were encountered. The location of these wet areas was in the general vicinity of the collection manhole (Sta. 21+00), where the soil subgrade was very soft (able to sink into the soil while walking). Langan conducted a site walk with AmecFW to collect GPS locations of these soft, underlying areas. The attached figure provides the swales, corridors, and trenches within vicinity of the collection manhole that do not meet the soil subgrade requirements. Additional grading / compaction activities will be required prior to liner installation within these areas.
  - Note: The locations on the attached figure do not represent every area that needs additional preparation activities. The general soil subgrade properties outlined above could represent varying locations as the entire soil area could not be observed due to the plastic being placed over the cap area. The locations outlined on the attached figure are meant to provide “critical” areas that may require more substantial work activities in order to have the subgrade properly prepared to the specifications.

Cc Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Observations Requiring Contractor / QA Engineer Review***

- Based on the soil subgrade inspection, the soil has not been approved for liner installation activities based on the wet / soft spots encountered (as outlined within this report). It is also recommended that laborers are provided when the plastic sheeting is removed so that the loose debris can be collected, and additional grading / compacting activities can be conducted (as required) along the slopes and contours.

***Action Items Pending***

- QA Engineer - Review SA-6 capping specifications and drawings. Review product submittals (as provided) and ensure that all data, drawings, and pertinent documents are ready for liner installation kickoff (planned for the week of 7/13).

***Action Items – Weekly Completions***

- None to Date

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Cap Installation Kickoff meeting scheduled for Thursday (7/9/15). At this time an additional soil subgrade inspection should be conducted with ESI representatives.

Cc: Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Photograph Log***



Photo 1: Completed soil subgrade with plastic sheeting cover (looking west toward Sta. 24+00).



Photo 2: Entact conducting grading and compacting activities to the area east of Sta. 19+00.

***Photograph Log (continued)***



Photo 3: Graded and compacted soil subgrade near Sta. 24+00 (acceptable subgrade).



Photo 4: Miscellaenouos debris (wood, rocks, etc.) encountered. Debris removed from subgrade, however, while plastic sheeting is removed in prep for installation, additional observations shall be conducted to ensure all debris is removed prior to liner installation.

***Photograph Log (continued)***



Photo 5: Loose material and debris encountered along swale slope.



Photo 6: Standing water encountered along northern drainage swale / tree bulb.

***Photograph Log (continued)***




Photo 7: Standing water / soft area in vicinity of collection manhole (Sta. 21+00).



Photo 8: Soft / wet soil in vicinity of manhole. Indentations / footprints visible.

LANGAN




Notes:
1. Locations GPS surveyed by Langan and AMEC for soil subgrade areas requiring additional preparation activities prior to liner placement.
2. This Figure represents critical locations that were observed by the project team and does not include every area that may require additional preparation work. As the plastic sheeting is removed from the cap, ENTACT should provide sufficient manpower to remove potential miscellaneous debris, and re-grade / compact slopes, as required.
3. Subgrade observations collected on 7/7/15 and 7/13/15 by Langan field personnel and represent the areas between the western most boundary (Sta 24+00), and east of Sta17+50. The area to the east of Sta. 17+50 has not yet been observed.

LANGAN
River Drive Center 1, 619 River Drive, Elmwood Park, NJ 07407-1338
T: 201.794.6900 F: 201.794.0366 www.langan.com
NEW JERSEY NEW YORK VIRGINIA CALIFORNIA
PENNSYLVANIA CONNECTICUT FLORIDA
ABU DHABI ATHENS DOHA
DUBAI ISTANBUL
Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.
Langan International LLC
Collectively known as Langan

Project
Honeywell
CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY
HUDSON COUNTY NEW JERSEY

Drawing Title
SA-6 SOUTH CAP SUBGRADE INSPECTIONS

| | |
|---|---|
| Project No. 100530001 | Figure 7 |
| Date 8/20/2015 | |
| Scale N.T.S. | |
| Drawn By ATR | |
| Last Revised 8/20/2015 | |

© 2013 Langan

Path: \\langan.com\data\EP\data0\100530001\ArcGIS\ArcMap_Documents\SA-6 South Cap Subgrade Inspections.mxd

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/13/2015 |
| **PROJECT:** | SA-6 Capping | | **WEATHER:** | 80/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Soil Subgrade Inspection | **TIME:** | 0600 – 1100 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #2** |
|---|---|
| **Thatcher Foundations**<br>*Equipment:* Dozers, Steel Drum Rollers, Misc. Hand Tools (shovels, rakes) | **AmecFW**:Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT**: Keith Goisse |

## ***Site Activities***

- Langan onsite to conduct soil subgrade inspection, and to observe placement of first layer of geocomposite (gas venting layer) for SA-6 south capping. Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area.
- Based on subsequent conversations with the project team, no material was to be placed during the day (GDL or LLDPE) as the geomembrane was undergoing final conformance testing requirements and had not yet been delivered to the Site. As such, Langan and AmecFW conducted a visual inspection of the prepared soil subgrade. These areas included the locations previously identified during the Day #1 soil subgrade inspection, as well as additional areas completed since that date from Sta. 18+50 to Sta. 17+50, as shown in the attached Figure (Sheet 7).
- In general, the following soil subgrade properties were observed:
  - ENTACT had opened and dried the areas immediately west of the collection manhole. Additionally, ENTACT provided laborers to dress and repair the slopes, as required. Refer to Sheet 3 for example of slope that would require dressing. The additional areas east of the collection manhole will also be opened and dried, with additional preparation being completed, as required. Refer to Sheet 7 for areas that ENTACT has repaired soil to appropriate subgrade.
  - The slopes of the smaller swales, utility corridors, street channels, etc. some soft and loose material was noted. As the plastic is removed for liner installation activities, ENTACT should provide laborers to dress the slopes (i.e. remove any loose debris and conduct compaction (as required) with a hand tamper), as necessary.
- In addition to the general soil subgrade properties outlined above, some soft / wet areas (some with free standing water) were encountered east of the previously inspected areas. The coordinates of these locations were collected and are shown on Sheet 7. Additional grading / compaction activities will be required prior to liner installation within these areas.
  - Note: The locations on the attached figure do not represent every area that needs additional preparation activities. The general soil subgrade properties outlined above could represent varying locations as the entire soil area could not be observed due to the plastic being placed over the cap area.

Cc Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

The locations outlined on the attached figure are meant to provide "critical" areas that may require more substantial work activities in order to have the subgrade properly prepared to the specifications.

***Observations Requiring Contractor / QA Engineer Review***

- Based on the soil subgrade inspection conducted to date, it appears that the soil west of the collection manhole is acceptable to commence with installation activities. However, ENTACT shall provide laborers as the plastic is removed to conduct slope dressing and re-compaction (as required), as well as, to remove any unacceptable debris (i.e. rocks, misc. debris, etc.) from the subgrade. If further soil deterioration is encountered prior to the placement of the GDL and liner material, additional re-grading and re-compaction of the soil subgrade may be required. As such, the final soil subgrade inspection form will not be completed until immediately prior to GDL and liner placement.
- Based on the wet / soft spots encountered (as outlined within this report) east of the collection manhole, it appears that this soil subgrade is not suitable for liner installation activities. Additional preparation work (i.e. drying, re-compaction, etc.) is required prior to liner placement. It is also recommended that laborers are provided when the plastic sheeting is removed so that any loose debris can be collected, and additional grading / compacting activities can be conducted (as required) along the slopes and contours.

***Action Items Pending***

- QA Engineer - Review SA-6 capping specifications and drawings. Review product submittals (as provided) and ensure that all data, drawings, and pertinent documents are ready for liner installation kickoff (planned to commence on 7/15).

***Action Items – Weekly Completions***

- None to Date

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work will be conducted tomorrow (7/14) by ENTACT.
- Preparation and coordination to ensure that liner placement can begin on Wednesday (7/15).

Cc: Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Photograph Log***



Photo 1: Example of washed slope that would require regarding and re-compaction activities.



Photo 2: Swale / root bulb with standing water and soft / wet bottom. Additional prep work required.

***Photograph Log (continued)***



Photo 3: ENTACT dressing slopes west of collection manhole.



Photo 4: Area west of collection manhole. Opened and dried. ENTACT dressing slopes (as required).

***Photograph Log (continued)***



Photo 5: Wet area located east of collection manhole on top deck (still requires drying and re-compaction).



Photo 6: Dry area re-compacted west of collection manhole.


***Photograph Log (continued)***




Photo 7: ENTACT filling and re-compacting depressions / voids in subgrade along southern edge of SA-6.



Photo 8: Grading and compacting soil east of collection manhole near Sta. 17+50.




## Legend

★ Respresents slopes and elevation changes that will require dressing (i.e. debris removal, re-compaction, etc.)

## Status

Represents areas that have been dried, regraded, and re-compacted. Soil appears acceptable for liner placement

Represents areas where ENTACT is presently drying and conducting regrading and re-compaction as required.

Represents areas that exhibit soft / wet subgrade. Soil not acceptable for liner placement.

Notes:
1. This Figure represents critical locations that were observed by the project team and does not include every area that may require additional preparation work. As the plastic sheeting is removed from the cap, ENTACT should provide sufficient manpower to remove potential miscellaneous debris, and re-grade / compact slopes, as required.
2. Subgrade observations collected on 7/7/15 and 7/13/15 by Langan field personnel and represent the areas between the western most boundary (Sta 24+00), and east of Sta17+50. The area to the east of Sta. 17+50 has not yet been observed.

LANGAN
River Drive Center 1, 619 River Drive
Elmwood Park, NJ 07407-1338
T: 201.794.6900 F: 201.794.0366 www.langan.com
Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.
Langan International LLC
Collectively known as Langan
NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project
Honeywell
CHROMIUM REMEDY STUDY AREA 6 SOUTH
JERSEY CITY
HUDSON COUNTY NEW JERSEY

Drawing Title
SA-6 SOUTH CAP SUBGRADE LANGAN FIELD OBSERVATIONS

| | |
|---|---|
| Project No. | 100530001 |
| Date | 7/13/2015 |
| Scale | N.T.S. |
| Drawn By | ATR |
| Last Revised | 7/14/2015 |
| SHEET | 7 |

© 2012 Langan

Path: \\langan.com\data\EP\data0\100530001\ArcGIS\ArcMap_Documents\SA-6 South Cap Subgrade Langan Field Observations.mxd

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/20/2015 |
| **PROJECT:** | SA-6 Capping | | **WEATHER:** | 80/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1900 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #3**<br>**AmecFW**:Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) starting at the west end of the SA-6 south. Material to be placed from the western end (west of Sta. 24+00, located at approximate Sta. 24+35) of SA-6 for approximately 100 ft. east to approximate Sta. 23+35.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area).
- Prior to placement of GVL or Cap, the plastic sheeting protecting the soil subgrade from the work area was removed. Final soil subgrade inspection was conducted for the area outlined above. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3, 4, and 5 of the daily photo log for 7/20/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the area of approximate Sta. 24+35 to Sta. 23+35 as outlined above.
- Upon soil subgrade approval, and prior to placement of the GVL and Liner, it was determined that an onsite meeting to discuss the revised panel layout and placement would be conducted between AmecFW, Langan, and ENTACT. During this meeting, the revised panel layout, seaming, soil subgrade approval, and other pertinent issues were discussed. Upon review of these topics, it was determined that ESI could begin with placement of GVL and Liner.
- ESI began by placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed on the western end of the Site (Sta. 24+35) moving east. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 7/20/15 Photo Log for supporting photographs.
- After installation of GVL, geomembrane liner was installed beginning at the western end of the Site and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from Sta. 24+35 to approximate Sta. 23+35. A total of four panels were installed (P-1, P-2,

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

P-3, and P-4), with seams overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing. The results of the pre-trial weld are provided in the associated QA form submitted for today (7/20), *Trial Weld Log.*

- Upon installation and welding of the geomembrane panels, based on required working permit hours, it was determined that non-destructive testing, and liner repair work would be conducted on 7/21/15. A destructive sample (DS-1) was collected, however, this sample was not shipped on 7/20/15 due to the extended working hours. Sample to be recorded on the *Destruct Log* and shipped on 7/21/15.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log. Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, etc.)
- Review laboratory results for destruct sample DS-1.

## ***Action Items – Weekly Completions***

- None to Date

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 23+35 to Sta. 22+35).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | |
| A2 – Receiving and Inspection | Sheet 1 (7/20) | RIR for 12 rolls of LLDPE delivered on 7/20/15 (Report Number 47) |
| A3 – Photo Log | Pages 1 - 8 | Total of 16 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date with LLDPE included until 7/20/15 |
| A5 – Subgrade Approval | Sheets 1 & ESI Form 7/20 | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 1 | One trial weld log provided by ESI and confirmed by Langan. |
| A7 – Panel Placement Log | Sheet 1 | One panel placement log provided by ESI and confirmed by Langan |
| A8 – Seam Testing COC | | N / A for 7/20/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A for 7/20/15 |
| A10 – Repair Log | | N / A no patch / repair work completed on 7/20 |
| A11 – Conformance COC | | N / A for 7/20/15 |
| A12 – Destructive Seam Field Test | | N / A DS-1 collected, however this repair and paperwork will be completed on 7/21 |
| A13 – Destruct. Sample Summary | | N / A to be updated on 7/21 |
| A14 – Penetration & Edge Form | | N / A penetrations for wells to be booted and completed at a later date |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking south away from SA-6

**Description:**

Entact / ESI offloading rolls of 60-mil geomembrane liner according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking west toward Sta. 24+00

**Description:**

Entact removing plastic sheeting to uncover and expose soil subgrade between Sta. 24+35 and Sta. 23+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking north toward Grid Point 11
15.00

**Description:**

Prepared soil subgrade approved for liner placement. Slopes compacted and free of loose debris > ½ inch.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking north along Sta. 23+50 corridor

**Description:**

Prepared soil subgrade approved for liner placement Soil compacted and free of loose debris (> ½ inch), based on visual observations.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking north along Sta. 24+00

**Description:**

Prepared soil subgrade approved for liner placement. Based on visual observations, soil is graded, compacted, and free of loose debris, as defined by the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking south / southeast along southern wall of SA-6 cap.

**Description:**

16 oz. geotextile installed along sheet pile wall according to specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking north / northwest near Sta. 24+00.

**Description:**

ESI placing GVL along western end of SA-6 cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking north near Sta. 24+00

**Description:**

White plastic fasteners placed at minimum 5 ft. intervals along GVL geonet as outlined in specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking north near Sta. 24+00.

**Description:**

ESI sewing geotextile seams along installed GVL panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking east near Grid Point 11
15.0

**Description:**

ESI cutting GVL to allow proper conforming within swale / tree bulb contour. Cut patched with GVL and



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking south away from SA-6 cap.

**Description:**

ESI conducting trial weld for LLDPE (geomembrane) seaming as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking south along western end of SA-6 cap.

**Description:**

Placement of LLDPE (geomembrane) along western end of cap (Sta. 24+35). Panel #1 (P-1) from approved geomembrane roll (Roll #283031).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking south away from SA-6 cap.

**Description:**

Placement of Panel #2 (P-2) east of P-1.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking south along western end of SA-6 cap.

**Description:**

Fusion welding conducted between Panel #1 (P-1) and Panel #2 (P-2).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking northwest along western end of SA-6 south cap.

**Description:**

Installed LLDPE geomembrane panels (P-1, P-2).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #16 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking northeast from western end of SA-6 South cap.

**Description:**

Installed LLDPE geomembrane panels (P-3 ,P-4)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/21/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 83/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #4**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #4 (P-4) installed on 7/20/15 (located at approximate Sta. 23+25) running approximately 100 ft. east (Sta. 22+35).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting non-destructive testing and patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/20/15 (Panels 1-4). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed with the project specifications (refer to *Preweld Test Report* for 7/21/15 for results).
- A total of eight repairs (RP-1 through RP-8) were observed and fixed (according to the project specifications) from Panel #1 through Panel #4. The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted, as outlined in the project specifications.
- Some non-conformance issues were observed, outside of the "custom fit" repairs noted above (refer to *Notice of Non-Compliance and Corrective Action* forms), and were documented on Sheet #1 and Sheet #2 as non-compliance. These issues were also recorded within the *Repair Log* as a subgrade irregularity and are identified as RP-3 and RP-8. The non-compliance issues encountered were identified based on debris / rocks that were observed underneath the geomembrane cap. The rocks were removed from these areas and the hole was patched / repaired according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – *Sheet #1* and *Sheet #2* for 7/21/15.
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/20/15, Entact removed the plastic sheeting protecting the soil subgrade for the next 100 ft. section of work area (approximate Sta. 23+35 to Sta. 22+35). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/21/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to *Photos #9 & 10* of the daily photo log for 7/21/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 23+35 to Sta. 22+35 as outlined above.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 23+35 (east of P-4) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *7/21/15 Photo Log* for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #4 (located at approximate Sta. 23+35) on 7/20/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 23+35 to Sta. 22+35. A total of four panel lengths were installed (P-5, P-6, P-7, P-8, P-9) by ESI. Note: Encountered the end of the geomembrane roll while placing Panel #6 (P-6). Butt seam required between P-6 and P-7. A destructive test sample (DS-2) was also collected from this seam (one sample for ESI, and one sample for Langan). The results of trial welding test for the destructive sample are outlined in the *Preweld Test Report* for 7/21/15. A total of ten 1-inch specimens were collected for peel and shear strength testing (5 tests for each).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/20), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted patch / repair work and non-destructive testing on Panels 5-9 (as outlined in the project specifications). During the non-destructive testing conducted between Panel 7 (P-7) and Panel 8 (P-8), the non-destruct test failed and a non-compliance issue was noted. Since P-7 only extended approximately 6 ft. (north to south), the entire seam would be patched and repaired (according to the project specifications) on 7/22/15.
- It should also be noted that pipe booting activities were conducted on piezometer PZ20 and well 073-MW-1BR as outlined in the project specifications. These two penetrations were sealed with geomembrane according to the project specifications. However, the final clamps with gasket have not yet been installed. The *Gas Vent and Piezometer Penetrations* Form will be filled and out and confirmed by Langan and ESI once these activities are completed.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 1 (Sheet #1) – Subgrade irregularity identified as RP-3 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #2). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 1 Notice of Non-Compliance*
- Non-Conformance No. 2 (Sheet #2) – Subgrade irregularity identified as RP-8 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #2). Stone was subsequently removed and hole was patched/repaired following project specs and further defined in *Sheet 2 Notice of Non-Compliance.*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Non-Conformance No. 3 (Proposed Sheet #3) – Failed seam
    - During non-destruct testing of P-7 and P-8 (6 ft. run north to south), the test failed as pressure could not be held within 4 psi (as outlined in project specifications). ESI will patch and repair the entire 6 ft. seam length (according to project specs) and this non-compliance issue will be documented on 7/22/15 and issued a repair number.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/21/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.)
- Review laboratory results for destruct sample DS-2. Note: QA destruct sample also collected (DS-2) by Langan.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Reviewed laboratory destruct sample results for samples DS-1. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 22+35 to Sta. 21+35).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/21/15 |
| A3 – Photo Log | Pages 1 – 9 | Total of 18 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date |
| A5 – Subgrade Approval | Sheet 2 & ESI (7/21/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A6 – Trial Weld Log | Sheet 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/21/15. |
| A7 – Panel Placement Log | Page 2 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/21/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | One Destruct Seam Testing COC for samples collected to date. |
| A9 – Seam/Non-Destruct. Test Log | Page 1 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/21/15. |
| A10 – Repair Log | Page 1 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/21/15 |
| A11 – Conformance COC | | N / A for 7/21/15 |
| A12 – Destructive Seam Field Test | Page 1 | Destructive Seam Field Test log completed by ESI and confirmed by Langan for samples on 7/21/15 |
| A13 – Destruct. Sample Summary | Sheet 1 | Destructive Sample Summary completed by ESI and confirmed by Langan on 7/21/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | Sheets 1 & 2 | Notice of Non-Compliance forms completed by Langan and confirmed by ESI/Entact for 7/21/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking north to the east of P-4

**Description:**

Entact preparing soil subgrade for liner placement between Sta. 23+35 and Sta. 22+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking down at installed geomembrane cap (near Break Point 548
15.12)

**Description:**

ESI conducting capping repair work around Break Point 548-15.12). Cap patched and sealed with extrusion welds (documented in Repair Log as RP-1).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east toward installed Panel #4 (P-4). Placed on 7/20/15

**Description:**

Non-destructive weld test performed by ESI between Panel #3 and Panel #4. Non-destruct conducted according to project specifications.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking north along approximate Sta. 24+00

**Description:**

ESI patching / repairing area along swale / contour to allow for geomembrane to conform to grade. Patching recorded in Repair Log as RP-1.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking west toward RP-3

**Description:**

ESI conducting extrusion welding on RP-3. RP-3 identified as non-conformance repair. Rock observed underneath geomembrane.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/21/15

**Direction Taken:**

Looking east down along geomembrane liner near Sta. 24+00.

**Description:**

ESI conducting vacuum box testing on extrusion welds as per project specifications. Vacuum box test being conducted on RP-1.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/21/15

**Direction Taken:**

Looking north toward well

**Description:**

ESI installing geomembrane boot around well 073-MW-1BR according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking west along western end of cap at well piezometer PZ20

**Description:**

ESI installing geomembrane boot around piezometer PZ20 as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east beyond Sta. 23+35 (east of P-4)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east along southern section of SA-6 (from approximate Sta. 23+35)

**Description:**

Prepared soil subgrade as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking northeast along northern end of SA-6

**Description:**

ESI placing 16 oz. geotextile around northern soil cement bentonite (SCB) wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking south near Sta. 23+35

**Description:**

ESI placing GVL (N-S orientation) to the east of installed geomembrane liner. GVL placed from approximate Sta. 23+35 to Sta. 22+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking south along SA-6

**Description:**

Plastic fasteners placed at maximum of 5 ft. spacing for tying adjacent panels of GVL (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

PHOTOGRAPHIC LOG
Photo #13 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking north near Sta. 23+35

**Description:**

ESI sewing top of geotextile seem on GVL as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/21/15

**Direction Taken:**

Looking south near Sta. 23+00

**Description:**

ESI placing 60-mil geomembrane cap, Panel #5 (P-5).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking north along northern slope of SA-6

**Description:**

ESI conducting fusion welding between geomembrane P-4 and P-5 panel seams (as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #17 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking south along geomembrane Panel #6 (P-6).

**Description:**

Installed geomembrane Panel #6 (P-6).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #18 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking north along SA-6 cap.

**Description:**

Installed geomembrane panels to approximate Sta. 22+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/22/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/82° F, Clear, Sunny, Wind (15 mph) |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #5**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #9 (P-9) installed on 7/21/15 (located at approximate Sta. 22+35) running approximately 95 ft. east to Sta. 21+40.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting non-destructive testing and patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/21/15 (Panels 5-9). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed with the project specifications (refer to *Preweld Test Report* for 7/22/15 for results. Extrusion testing identified with as EXT on form).
- A total of six repairs (RP-9 through RP-14) were observed and fixed (according to the project specifications) from Panel #5 through Panel #9. The majority of these repairs were associated with piezometer pipe boots and repairs for the destructive samples collected. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-conformance issue was observed, outside of the repairs noted above (refer to *Notice of Non-Compliance and Corrective Action* forms), and was documented on Sheet #3 as non-compliance. This issue was also recorded within the Repair Log as a failed seam test (non-destruct test) and identified as RP-13.
- The non-compliance issue encountered was a failed non-destructive seam test conducted between Panels 7/8. The failed seam was along the southern end of SA-6 and was only 6 ft. in total length (butt end of seam as outlined in the 7/21/15 report). As such, the seam was patched according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – Sheet #3 for 7/21/15.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Upon completion of the cap detailing, ESI began to install GDL panels beginning at the western end of the Site (Sta. 24+35) and moving east. The GDL panels were installed over the geomembrane cap previously placed on 7/20/15, and were installed to just before the first destructive sample collected (DS-1) along Panels 3/4.
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/21/15 and installing GDL, Entact removed the plastic sheeting protecting the soil subgrade for the next 95 ft. section of work area (approximate Sta. 22+35 to Sta. 21+40). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/22/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 & 3 of the daily photo log for 7/22/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 22+35 to Sta. 21+40 as outlined above.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 22+35 (east of P-9) moving east (for approximately 95 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 7/22/15 Photo Log for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #9 (located at approximate Sta. 22+35) on 7/21/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 22+35 to Sta. 21+40. A total of four panel lengths were installed (P-10, P-11, P-12, and P-13) by ESI.
- A destructive test sample (DS-3) was collected from the Panel 10/11 seam, within the 500 ft. linear foot requirement outlined in the project specifications. The results of trial welding test for the destructive sample are outlined in the *Preweld Test Report* for 7/22/15. A total of ten 1-inch specimens were collected for peel and shear strength testing (5 tests for each).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/22), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted patch / repair work and non-destructive testing on Panels 10-13 (as outlined in the project specifications). The patches associated with Panels 10-13 will be completed with extrusion welds on 7/23/15.
- It should also be noted that pipe booting activities were conducted well 115-W3-SO (located on Panel #8, northern slope) as outlined in the project specifications. The penetration was sealed with geomembrane according to the project specifications. However, the final clamps with gasket have not yet been installed. The *Gas Vent and Piezometer Penetrations* Form will be filled and out and confirmed by Langan and ESI once these activities are completed. Additionally, a gas vent pipe (GV-7) was covered with geomembrane, and will be cut, sealed, and booted according to the specifications at a future date.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 3 (Sheet #3) – Failed seam, identified as RP-13 on *Repair Log*
    - During non-destruct testing of P-7 and P-8 (6 ft. run north to south), the test failed as pressure could not be held within 4 psi (as outlined in project specifications). This area was patched and repaired along the entire 6 ft. seam length (according to project specs) as outlined on *Sheet #3*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

*Notice of Non-Compliance*.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/22/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/21/15.
- Review laboratory results for Destruct Sample (DS-3)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/21/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Destructive Sample Summary,* and *Certificate of Subgrade Acceptance* forms. Additional review of Preweld Test Report, Seam Control Form, and Repair Report required prior to acceptance.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-2, as well as Langan QA sample (DS-2). Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 21+40 to Sta. 20+40).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/22/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date |
| A5 – Subgrade Approval | Sheet 3 & ESI (7/22/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/22/15. |
| A7 – Panel Placement Log | Page 3 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/22/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | One Destruct Seam Testing COC for samples collected to date. |
| A9 – Seam/Non-Destruct. Test Log | Page 2 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/22/15. |
| A10 – Repair Log | Page 1 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/22/15 |
| A11 – Conformance COC | | N / A for 7/22/15 |
| A12 – Destructive Seam Field Test | Sheet 1 | Destructive Seam Field Test log completed by ESI and confirmed by Langan for samples on 7/22/15 |
| A13 – Destruct. Sample Summary | Page 1 | Destructive Sample Summary completed by ESI and confirmed by Langan on 7/22/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | Sheet 3 | Notice of Non-Compliance forms completed by Langan and confirmed by ESI/Entact for 7/22/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking northwest toward western end of SA-6 South.

**Description:**

ESI installing GDL along western end of SA-6, from Sta. 24+35 moving east (area previously covered with geomembrane liner on 7/20/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

Prepared soil subgrade for geomembrane placement. Approximate 95 ft. section east of geomembrane installed on 7/21/15, approved. Approximate location of Sta. 22+35 to Sta. 21+40.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking northeast through approximate Sta. 22+00 corridor.

**Description:**

Soil subgrade approved for geomembrane placement for 7/22/15. Soil graded, compacted, and free of debris (>1/2 inch) as outlined in the project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2215

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

16 oz. geotextile placed by ESI along southern wall of SA-6 with 2 ft. of overlap (outside of sheet pile wall) and one roll width inside.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking south along approx. Sta. 22+35.

**Description:**

ESI placing GVL along approved soil subgrade.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/22/15

**Direction Taken:**

Looking north along Sta. 22+35

**Description:**

White plastic fasteners placed at a maximum of 5 ft. intervals for tying adjacent panels (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking north along Sta. 22+35

**Description:**

ESI sewing geotextile along adjacent GVL panels (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking south along installed geomembrane panels.

**Description:**

ESI deploying geomembrane panels (P-10 through P-14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking north along panel P-10

**Description:**

Installed Panel #10 (P-10) labeled with roll number (282018).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking along geomembrane cap panels P-9 and P-10.

**Description:**

ESI conducting fusion welding between geomembrane P-9 and P-10 panel seams (as per project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking along geomembrane panels

**Description:**

ESI conducting non-destructive testing as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking northeast along installed geomembrane cap for 7/21/15

**Description:**

Installed geomembrane cap weighted at end of day with sand bags.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/23/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/82° F, Clear, Sunny, Wind |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #6**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #13 (P-13) installed on 7/22/15 (located at approximate Sta. 21+40) running approximately 150 ft. east to Sta. 19+90.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying GDL along the western end of the cap. Based on the minor repairs required from the geomembrane placement on 7/22/15, it was determined that extrusion weld repairs would be conducted tomorrow (7/24/15).
- A total of 11 rolls (7 north to south runs over SA-6; approximately 165 ft.) of GDL were deployed along the western end of SA-6. GDL was installed to cover the geomembrane panels placed on 7/20/15 and 7/21/15 (GLD installed up to P-9). Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and geotextile seams sewn along the geotextile for adjacent panels.
- While ESI was and installing GDL along the western end of SA-6, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 150 ft. section of work area (approximate Sta. 21+40 to Sta. 19+90). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/23/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3,4,5, and 6 of the daily photo log for 7/23/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 21+40 to Sta. 19+90 as outlined above.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After geotextile was placed, GVL was installed from approximate Sta. 21+40 (east of P-13) moving east (for approximately 150 ft.) to Sta. 19+90. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/23/15 Photo Log for supporting photographs.

- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #13 (located at approximate Sta. 21+40) on 7/22/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 21+40 to Sta. 19+90. A total of five panel lengths were installed (P-14, P-15, P-16, P-17 and P-18) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/23), *Trial Weld Log.*
- As outlined above, no extrusion welding and detailing activities were conducted by ESI. These activities are scheduled to be completed tomorrow (7/24) for the repairs associated with geomembrane capping from 7/22/15 and 7/23/15. It should also be noted that two destructive fusion weld samples will be collected on 7/24/15 from Panels 14-18. An extrusion weld sample will also be required once detailing activities commence in the morning.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items to be recorded from 7/23/15 as no repair work was completed.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/21/15 and 7/22/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- ESI – complete repair / patch work and collect appropriate destruct samples for fusion and extrusion welding (as outlined in project specifications.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, as well as reviewed and approved ESI submitted forms.
- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/21/15 and 7/22/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Destructive Sample Summary,* and *Certificate of Subgrade Acceptance* forms. Additional review of Preweld Test Report, Seam Control Form, and Repair Report required prior to acceptance.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-3. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 19+90 to Sta. 19+00).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/23/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/23/15 |
| A5 – Subgrade Approval | Sheet 4 & ESI (7/23/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/23/15. |
| A7 – Panel Placement Log | Page 4 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/23/15 |
| A8 – Destruct Seam Testing COC | | No destruct samples collected on 7/23/15. No updates |
| A9 – Seam/Non-Destruct. Test Log | Pages 3-4 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/23/15. |
| A10 – Repair Log | | N / A no repairs conducted on 7/23/15 |
| A11 – Conformance COC | | N / A for 7/23/15 |
| A12 – Destructive Seam Field Test | | N / A no destructive tests conducted on 7/23/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 7/23/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A16 – Notice of Non-Compliance | | N / A no repairs completed on 7/23/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/23/15

**Direction Taken:**

Looking north along western end of SA-6

**Description:**

GDL installed along western end of cap over geomembrane placed on 7/20/15 and 7/21/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking south along western end of SA-6

**Description:**

ESI placing GDL. Plastic fasteners spaced at maximum of 5 ft. and geotextile sewed along adjacent panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking east along southern boundary wall (sheet piling) of SA-6 from approximate Sta. 21+40

**Description:**

Soil subgrade approved for geomembrane placement for 7/23/15. Soil graded, compacted, and free of debris (>1/2 inch) as outlined in the project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2315

**Direction Taken:**

Looking north along SA-6 at approximate Sta. 21+40

**Description:**

Approved soil subgrade for geomembrane placement. Subgrade prepared in accordance with project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking northeast toward Sta. 21+00 (collection manhole)

**Description:**

Approved soil subgrade for geomembrane placement. Soil prepared in accordance with project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking at prepared soil subgrade around collection manhole. Located by approximate break point 979-13.50

**Description:**

Soil subgrade prepared around collection manhole.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/23/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 21+20.

**Description:**

ESI placing GVL according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking north along SA-6

**Description:**

GVL panels installed according to project specifications. Plastic fasteners placed at maximum of 5 ft. spacing and geotextile sewed along adjacent panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/23/15

**Direction Taken:**

Looking east through Sta. 21+00

**Description:**

Installed GVL to approximate Sta. 20+30.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking northeast at approximate Sta. 21+20

**Description:**

ESI placing geomembrane cap (Panels 14 & 15) on top of GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |


**Date:**
7/23/15

**Direction Taken:**

Looking northwestern by northern slope of SA-6

**Description:**

ESI conducting fusion welding between Panels 13/14



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/23/15

**Direction Taken:**

Looking south at southern end of SA-6

**Description:**

Installed geomembrane panel #14 (P-14) labeled with corresponding geomembrane roll number.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking north at approximate Sta. 20+90

**Description:**

ESI placing geomembrane panels. Material placed around collection manhole (Sta. 21+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Installed geomembrane cap with GDL visible at far western end.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/24/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 75/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1700 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #7**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #18 (P-18) installed on 7/23/15 (located at approximate Sta. 20+25) running approximately 90 ft. east to Sta. 19+00. Note: Soil subgrade approved to approximate Sta. 19+90 on 7/23/15. Geomembrane cap only installed to approximate Sta. 20+25 by ESI (additional 35 ft. of approved subgrade in addition to 90 ft. approved on 7/24/15).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/23/15 (Panels 14-18). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/24/15 for results (extrusion testing identified as EXT. on form).
- A total of seventeen repairs (RP-15 through RP-31) were observed and fixed (according to the project specifications) from Panel #9 through Panel #18 (repair / detailing work conducted on panels installed from 7/22/15 and 7/23/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Some additional repairs (including “custom fit” cuts to conform the geomembrane) required, however, these repairs will be completed on Monday (7/27) to allow ESI to continue to place geomembrane to the east.
- One extrusion weld destruct sample (DSX-1) was collected from Panel #13 (located on RP-17). Extrusion weld destruct samples collected every 500 lf. of welding (as outlined in project specs).
- One non-conformance issue was observed, outside of the repairs noted above (refer to *Notice of Non-Compliance and Corrective Action* forms), and was documented on Sheet #4 as non-compliance. This issue was also recorded within the Repair Log as a subgrade irregularity and was noted and repaired (RP-30) following the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was conducting cap detailing for the geomembrane cap placed on 7/22/15 and 7/23/15, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 90 ft. section of work area (approximate Sta. 19+90 to Sta. 19+00). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/24/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #8 & 9 of the daily photo log for 7/24/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 19+90 to Sta. 19+00 as outlined above.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 20+25 (east of P-18) moving east (for approximately 135 ft. total [35 ft. remaining from 7/23/15 + 90 ft. approved on 7/24]). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Along the slopes and elevation changes, additional fasteners were placed along the geonet to provide additional support within these sloped areas. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 7/24/15 Photo Log for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #18 (located at approximate Sta. 20+25) on 7/23/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 20+25 to Sta. 19+00. A total of six panel lengths were installed (P-19, P-20, P-21, P-22, P-23, P-24) by ESI.
- Two destructive test samples (DS-4 & DS-5) were collected from the Panel 14/15 and 17/18 seam, within the 500 ft. linear foot requirement outlined in the project specifications. The results of the trial welding tests for the destructive samples are outlined in the *Preweld Test Report* for 7/24/15. A total of ten 1-inch specimens were collected for peel and shear strength testing (5 tests for each) for each sample.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/24), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted non-destructive testing on Panels 19-24 (as outlined in the project specifications). No patch / repair work on the installed panels was conducted. Patches associated with Panels 19-24 will be completed with extrusion welds and vacuum box testing on Monday (7/27/15). Additionally, some additional patchwork for the panels installed on 7/23/15 will also be completed, as outlined above.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 4 (Sheet #4) – Subgrade irregularity identified as RP-30 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #17). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 4 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/24/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/23/15 forms.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Review laboratory test results for destruct samples DS-4 and DS-5 (fusion) and DSX-1 (extrusion). Note: QA sample (DSX-1) also collected by Langan.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/23/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Destructive Sample Summary,* and *Certificate of Subgrade Acceptance* forms. Submittal of additional forms from 7/23/15 and review of Seam Control Form, required prior to acceptance.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-3. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 19+00 to Sta. 18+00).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/24/15 |
| A3 – Photo Log | Pages 1 – 9 | Total of 18 photos outlining pertinent daily observations and descriptions for 7/24/15 |
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date |
| A5 – Subgrade Approval | Sheet 5 & ESI (7/24/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/24/15. |
| A7 – Panel Placement Log | Page 5 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/24/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A8 – Destruct Seam Testing COC | Sheet 1 | One Destruct Seam Testing COC for samples collected to date. |
| A9 – Seam/Non-Destruct. Test Log | Pages 4-5 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/24/15. |
| A10 – Repair Log | Pages 1-2 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/24/15 |
| A11 – Conformance COC | | N / A for 7/24/15 |
| A12 – Destructive Seam Field Test | Sheet 1 | Destructive Seam Field Test log completed by ESI and confirmed by Langan for samples on 7/24/15 |
| A13 – Destruct. Sample Summary | Page 1 | Destructive Sample Summary completed by ESI and confirmed by Langan on 7/24/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | Sheet 4 | Notice of Non-Compliance forms completed by Langan and confirmed by ESI/Entact for 7/24/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/24/15

**Direction Taken:**

Looking north/northwest at RP-17

**Description:**

ESI conducting patch / repair work to geomembrane. Areas of cap cut to allow geomembrane "custom fit" around slopes and contours.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking along geomembrane cap and extrusion welding RP-15.

**Description:**

ESI conducting extrusion welding on patches and repairs. Extrusion weld areas to be tested with vacuum box (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking along geomembrane cap at DS-3 area

**Description:**

ESI preparing to conduct extrusion welding on geomembrane patch repair. Repair placed along seam where destruct sample DS-3 was collected.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2415

**Direction Taken:**

Looking along geomembrane liner

**Description:**

ESI conducting vacuum box testing (as outlined in project specs)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/24/15

**Direction Taken:**

Looking south along geomembrane cap at DS-4 location.

**Description:**

ESI collecting destruct sample (DS-4) on northern slope of SA-6 as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/24/15

**Direction Taken:**

Looking south/southeast along collection manhole (approx. Sta. 21+00)

**Description:**

ESI conducting grinding and extrusion welding around patches /repairs to “custom fit” geomembrane cap around contours.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Inside ESI work trailer

**Description:**

Tensiometer (machine number: 2003) used to conduct destruct / trial weld sampling for fusion and extrusion welds (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Prepared soil subgrade from approximate Sta. 19+90 to Sta. 19+00. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking south at approximate Sta. 19+80

**Description:**

Soil subgrade prepared for soil placement (approved from approximate Sta. 19+90 to Sta. 19+00) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking west along geomembrane cap at Sta. 21+00

**Description:**

ESI conducting geomembrane repair work around collection manhole (following project specs). Temporary boot installed around collection manhole to seal cap for weekend. Permanent / final boot to be installed at a later date.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking east / southeast along southern end of SA-6

**Description:**

ESI placing 16 oz. geotextile along southern boundary of SA-6 (over sheet pile wall) with 2 ft. of overlap outside (width of roll overlapped onto SA-6), as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking north along SA-6 at approximate Sta. 20+25.

**Description:**

ESI placing rolls of GVL along approved soil subgrade.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/24/15

**Direction Taken:**

Looking south along SA-6 cap (approximate Sta. 20+25)

**Description:**

ESI placing white plastic fasteners (maximum of 5 ft. spacing) along geonet for adjacent GVL panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking south along SA-6

**Description:**

Additional plastic fasteners installed along slopes for GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking south along SA-6 (installed Panel #19)

**Description:**

ESI placing 60-mil geomembrane cap, Panel #19 (P-19) placed and labeled with corresponding roll number.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/24/15

**Direction Taken:**

Looking south / southwest along SA-6 cap

**Description:**

ESI conducting fusion welding between geomembrane P-19 and P-20 as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #17 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking north along installed geomembrane cap

**Description:**

Sand bags used to weight down geomembrane cap. Additional sandbags placed along slopes and elevation changes.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #18 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking east along SA-6 for installed geomembrane cap (to approx. Sta. 19+00)

**Description:**

Installed geomembrane panels to approximate Sta. 19+00.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/27/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 80/90° F, Hazy, Light Rain |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #8**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #24 (P-24) installed on 7/24/15 (located at approximate Sta. 19+00) running approximately 100 ft. east to Sta. 18+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying GDL along the western end of the cap. GDL was placed to approximate Sta. 21+00 (near collection manhole) which included the placement of 9 rolls (14 different panels) of GDL from P-9 (geomembrane installed on 7/21/15) to P-14 (geomembrane installed up to 7/23/15). Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and sewing of the geotextile completed for adjacent geocomposite panels.
- While ESI was and installing GDL along the western end of SA-6, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 80 ft. section of work area (approximate Sta. 19+00 to Sta. 18+20). Based on visual inspection of the soil, two areas were identified that did not meet the subgrade requirements.
    - The drainage swale located along Sta. 19+00 at Break Point 675-18.54 collected rainwater from storms on 7/26/15. As such the area was soft / wet and did not meet the subgrade requirements. The installed geomembrane and GVL (from 7/24/15) was pulled back and this area was left open to dry. Refer to Photo #2 of 7/27/15 Photo Log.
    - An additional location was identified to the southern end of the SA-6 cap near approximate Bound Point 655-15.58. The 16 oz. geotextile was pulled back from this area and the soil subgrade was allowed to dry. Refer to Photo 3 of 7/27/15 Photo Log.
- Based on the information outlined above, no soil subgrade was approved for GVL and geocomposite placement, as the soil did not conform with the project specifications. As such, no soil subgrade approval forms were completed for 7/27/15.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- With no subgrade approval for additional panel placement (no panel layout forms completed for 7/27/15), ESI conducted patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/23/15 and 7/24/15 (Panels 19-24). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/27/15 for results (extrusion testing identified as EXT. on form).
- A total of twenty-one repairs (RP-31 through RP-51) were observed and fixed (according to the project specifications) from Panels #18 through Panel #24 (repair / detailing work conducted on panels installed from 7/23/15 and 7/24/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Note: No non-compliance issues were observed as patch / repair work conducted consisted primarily of custom fit repairs to allow geomembrane to conform to SA-6 contours.
- A total of three non-destructive samples were collected for lab testing (as outlined in the project specs). Two fusion weld samples DS-6 (panel seams 20/21) and DS-7 (Panel seams 23/24), along with one extrusion weld sample DSX-2 (south end of SA-6 on P-15) were collected within the 500 linear foot specification requirements.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no new geomembrane panels were placed and the repairs associated with 7/27/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/21/15 and 7/22/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Review laboratory test results for destruct samples DS-6 and DS-7 (fusion) and sample DSX-2 (extrusion).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-5 (fusion) and destruct sample DSX-1 (extrusion). Note: QA sample (DSX-1) also reviewed and in compliance with project specs. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 19+00 to Sta. 18+00) to ensure soil subgrade complies with project specs.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/27/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/27/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 7/27/15 |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for pre and destruct welds completed up to 7/27/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 7/27/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with samples from 7/27/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 7/27/15 |
| A10 – Repair Log | Pages 2-3 | One repair report provided by ESI and confirmed by Langan for repairs conducted on 7/27/15. |
| A11 – Conformance COC | | N / A for 7/27/15 |
| A12 – Destructive Seam Field Test | Page 1 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 7/27/15. |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with sample information from 7/27/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | | No non-compliance issues identified as no new panels were installed |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/27/15

**Direction Taken:**

Looking south along SA-6 near Sta. 21+25.

**Description:**

ESI placing GDL along panels previously installed on 7/22/15 & 7/23/15 (GDL placed up to Panel #14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking northwest along Break Point 675-15.84.

**Description:**

GVL & Geomembrane cap pulled back to expose wet / soft area encountered from rain on 7/26/15. Area opened to dry prior to placing GVL and Geomembrane.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Additional wet / soft area identified along southern end of SA-6 (approximate Bound Point 655-15.58) Geotextile & GVL pulled back to allow area to dry prior to placing additional material.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/2715

**Direction Taken:**

Looking north / northeast along SA-6 (by geomembrane P-14).

**Description:**

ESI deploying GDL up to Panel #14 (P-14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking northwest – collection manhole in background (Sta.21+00)

**Description:**

ESI conducting vacuum box testing on RP-31 after completion of extrusion welding.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking along SA-6 cap at RP-26

**Description:**

ESI conducting vacuum box testing on RP-26 ( as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESi cutting destructive test DSX-2 for extrusion weld completed alongRP-32 (identified as RP-34 and located along southern edge of SA-6 cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking south along SA-6

**Description:**

Patch / repair work conducted on southern slope of SA-6. Repairs extrusion welded and vacuum box tested (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking west along SA-6 (panel 20/21 seam)

**Description:**

ESI collecting destruct sample along Panel 20/21 seam (DS-6).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

ESI collecting destruct along Panel 23/24 seam (DS-7).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking east along SA-6 cap (panel 23/24 seam)

**Description:**

ESI patching area for DS-7.DS-7 was patched, welded, and vacuum box tested (as outlined in project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking southwest along SA-6 cap

**Description:**

ESI completing the day with patch / repair work on “custom fit” patches around xx.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/28/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 78/92° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #9**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #24 (P-24) installed on 7/24/15 (located at approximate Sta. 19+00) running approximately 80 ft. east to Sta. 18+20. Note: No geomembrane placed on 7/27/15, as soil subgrade was not approved for two wet / soft areas identified at approx. Sta. 19+00 (further described in 7/27/15 report).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI finishing patch / repair work (cap detailing) and vacuum box testing for the geomembrane cap that was installed on 7/24/15 (Panels 19-24). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/28/15 for results (extrusion testing identified as EXT. on form).
- A total of thirty-six repairs (RP-52 through RP-87) were observed and fixed (according to the project specifications) from Panel #19 through Panel #24 (repair / detailing work conducted on panels installed on 7/24/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/24/15, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 100 ft. section of work area (approximate Sta. 19+00 to Sta. 18+00). The previously identified wet / soft areas along Sta. 19+00 were dried, graded, and compacted according to the project specs. Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/28/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3,4,5 of the daily photo log for 7/28/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

The soil subgrade inspection sheet was submitted for the approximate area of Sta. 19+00 to Sta. 17+80 (west of utility corridor).

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 19+00 (east of P-24) moving east (for approximately 80 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *7/28/15 Photo Log* for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #24 (located at approximate Sta. 19+00) on 7/24/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 19+00 to Sta. 18+20. An additional approximately 40 ft. section of subgrade was approved from approximate Sta. 18+20 to Sta. 17+80 to allow ESI to place an additional two panels to the east. A total of six panel lengths were installed (P-25, P-26, P-27, P-28, P-29, P-30) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/28), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted non-destructive testing on Panels 25-30 (as outlined in the project specifications). Additionally, one extrusion weld sample (DSX-3) was collected (as per project specifications) from RP-82 and sent to the approved laboratory for analysis. No patch / repair work on the installed panels was conducted. Patches associated with Panels 25-30 will be completed with extrusion welds and vacuum box testing on Wednesday (7/29/15). Additionally, two destruct samples for the fusion welding will be collected (as required by the project specs) on 7/29/15.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 7/28/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/28/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Repair Report identified on 7/27/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Review laboratory test results for destruct sample DSX-3 (extrusion).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15, 7/24/15, and 7/27/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-7 (fusion) and destruct sample DSX-1 through DSX-2 (extrusion). Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 17+80 to Sta. 17+00) through utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/24/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 7/28/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/28/15 |
| A5 – Subgrade Approval | Sheet 6 & ESI (7/28/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheets 1, 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/28/15. |
| A7 – Panel Placement Log | Page 6 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/28/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 7/28 |
| A9 – Seam/Non-Destruct. Test Log | Sheets 5,6,7 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/28/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A10 – Repair Log | Sheets 2,3,4,5 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/28/15 |
| A11 – Conformance COC | | N / A for 7/28/15 |
| A12 – Destructive Seam Field Test | Sheet 1 | Updated with information from destruct sample on 7/28 |
| A13 – Destruct. Sample Summary | Sheet 1 | Destruct Sample Summary provided by ESI and confirmed by Langan for sample DSX-3 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted as repair / patching in compliance with project specs. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along Panel #19 (P-19)

**Description:**

Completed repair / patch work (from7/27) along P-19. Repairs RP-46, RP-47, RP-48, and RP-49.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along Panel Seam 17/18

**Description:**

Completed repair / patch work along Panel 17/18 seam. Repair RP-31 shown.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking northwest along drainage swale near Break Point 675-15.84

**Description:**

Soil subgrade around drainage swale dried, graded, and compacted (according to specs). Area previously identified as soft/wet on 7/27/15. Based on visual observation area approved for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2815

**Direction Taken:**

Looking east along southern end of SA-6 cap.

**Description:**

Soil subgrade approved from approximate Sta. 19+00 to Sta.18+20.Area graded, compacted, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along Y-channel located at approximate Break Point 684-16.04

**Description:**

Soil subgrade approved for geomembrane placement. Soil graded, compacted, and free of debris (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along approx. Sta. 19+00

**Description:**

ESI placing geocomposite. White plastic fasteners placed at a maximum of 5ft., and geotextile sewn (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/28/15

**Direction Taken:**

Looking north at approximate Sta. 19+00

**Description:**

ESi sewing GVL geotextile for adjacent geocompoiste panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking south at approximate Sta. 19+00

**Description:**

ESI deploying geomembrane cap over GVL. Panel #25 (P-25) being placed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking south along Panel 24/25 seam (approximate Sta. 19+00)

**Description:**

ESI conducting fusion welding along Panel 24 (installed on 7/24) and Panel 25 (installed on 7/28).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking south along Panel #25 (P-25)

**Description:**

Panel #25 (P-25) placed and labeled with corresponding roll number shown.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking south at approximate Sta. 18+00

**Description:**

GVL installed to approximate Sta. 17+80



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking northeast along SA-6 cap

**Description:**

Installed geomembrane cap to approx. 17+80



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 7/29/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 77/92° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0600 – 1715 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #10**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #30 (P-30) installed on 7/28/15 (located at approximate Sta. 17+80) running approximately 80 ft. east to Sta. 17+00 (up to 1st utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI finishing patch / repair work (cap detailing) and vacuum box testing for the geomembrane cap that was installed on 7/28/15 (Panels 25-30). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/29/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-two repairs (RP-88 through RP-129) were observed and fixed (according to the project specifications) from Panel #25 through Panel #30 (repair / detailing work conducted on panels installed on 7/28/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Additionally, pipe boots were completed (with seals and clamps) for PZ-20, 073-MW-1BR, 115-W3-SO, and GV-7, however, the final butyl seal around the top of the boot is required prior to completion of the *Pipe Boot and Penetration Logs.*
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/28/15, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 80 ft. section of work area (approximate Sta. 17+80 to Sta. 17+00). Prior to soil approval, the area was spot checked for survey elevations and was approved as acceptable and within the grading requirements. Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/29/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Refer to Photos #5 and 8 of the daily photo log for 7/29/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 17+80 to Sta. 17+00 (up to 1st utility corridor).

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 17+80 (east of P-30) moving east (for approximately 80 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *7/29/15 Photo Log* for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #30 (located at approximate Sta. 17+80) on 7/28/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 17+80 to Sta. 17+00. A total of four panel lengths were installed (P-31, P-32, P-33, P-34) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/29), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted non-destructive testing on Panels 31-34 (as outlined in the project specifications). Additionally, three non-destruct samples were collected (DS-8, DS-9, and DSX-4). DS-8 was collected from Panel 26/27, DS-9 from Panel 29/30, and DSX-4 (extrusion weld) was collected from Panel #27 (RP-102).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 7/29/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/29/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Repair Report and Seam Control identified on 7/28/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Review laboratory test results for destruct sample DS-8 and DS-9 (fusion), along with DSX-4 (extrusion).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15, 7/24/15, and 7/27/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Completed Langan Daily Report, Photo Log, and Soil Subgrade Approval Form for 7/28/15. Revisions for Repair Report and Seam Control Form required prior to sign-off.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-7 (fusion) and destruct sample DSX-1 through DSX-3 (extrusion). Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 17+80 to Sta. 17+00) through utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/29/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 7/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/29/15 |
| A5 – Subgrade Approval | Sheet 7 & ESI (7/29/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/29/15. |
| A7 – Panel Placement Log | Page 7 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/29/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 7/28 |
| A9 – Seam/Non-Destruct. Test Log | Sheets 5,6,7 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/28/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A10 – Repair Log | Sheets 5,6,7 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/29/15 |
| A11 – Conformance COC | | N / A for 7/28/15 |
| A12 – Destructive Seam Field Test | Sheet 1, 2 | Updated with information from destruct sample on 7/28 |
| A13 – Destruct. Sample Summary | Sheet 1 | Destruct Sample Summary provided by ESI and updated for sample DSX-3 |
| A14 – Penetration & Edge Form | | N / A additional review of QA form required prior to completion |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 7/29 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking north along Panel 20/21 seam

**Description:**

Completed patch / repair work (from 7/28). RP-71 and RP-73



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/29/15

**Direction Taken:**

Looking at geomembrane at Panel 26/27

**Description:**

ESI collecting destruct sample (DS-8) along Panel 26/27 seam, located at northern slope of SA-6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along western end of SA-6

**Description:**

Final boot installed along well 073-MW-1BR, with supporting gasket and double clamps.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along western end of cap (PZ-20)

**Description:**

Geomembrane boot installed around PZ-20. Secured with gasket and double clamps.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking north along SA-6 (previously installed liner)

**Description:**

Prepared soil subgrade approved for liner placement. Based on visual observations, soil is graded, compacted, and free of loose debris, as defined by the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along SA-6 cap (eastern end of Panel 27)

**Description:**

ESI conducting vacuum box test on repair / patch extrusion weld (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/29/15

**Direction Taken:**

Looking north along SA-6 at approximate Sta. 17+80

**Description:**

ESI deploying GVL along approximate Sta. 17+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/29/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Entact placing sand / bentonite plug at southern end of utility corridor (approximate Sta. 16+20).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking south along approximate Sta. 17+80

**Description:**

ESI deploying geomembrane at approximate Sta. 17+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along SA-6 cap (from Panel #31).

**Description:**

ESI conducting fusion welding along Panel 30/31 seam as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/29/15

**Direction Taken:**

Looking south / southeast along southern end of SA-6 cap (P-32)

**Description:**

PZ-18 stickup located on southern and western end of SA-6 (on Panel #32). PZ-18 to be booted and sealed (as outlined in project specs) on 7/30/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/29/15

**Direction Taken:**

Looking northeast along SA-6 cap

**Description:**

Installed geomembrane panels (P-31 & P-32). ESI conducting fusion welding (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/30/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 76/85° F, Overcast, PM T-Storms |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1500 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #11**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL), and geocomposite clay liner (GVL), continuing from western end of SA-6 South. Material to be placed from Panel #34 (P-34) installed on 7/29/15 (located at approximate Sta. 17+00) through 1st utility corridor located at approximate Sta. 16+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/29/15 (Panels 31-34). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/30/15 for results (extrusion testing identified as EXT. on form).
- A total of fifteen repairs (RP-130 through RP-144) were observed and fixed (according to the project specifications) from Panels #31 through Panel #34 (repair / detailing work conducted on panels installed from 7/29/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), and also to remove wrinkles observed around changes in elevation. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- As outlined above, no non-conformance issues were observed during repair/patch work conducted on 7/30/15, as repairs were associated with conforming the geomembrane to the SA-6 contours.
- Based on the expected weather forecast of early afternoon thunderstorms, it was determined that no GCL would be placed within the utility corridor. As such, no soil subgrade was approved for GCL placement and no panel placement forms were completed.
- ESI instead deployed GDL along the western end of the cap. GDL was placed to approximate Sta. 20+00 which included the placement of 12 rolls (rolls from north to south of SA-6; 17 different panel numbers with butt seams) of GDL from P-14 to P-21. GDL Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and sewing of the geotextile completed for adjacent geocomposite panels (with orange fabric obtained from extra roll of GDL).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- In addition to GDL placement, Entact began to build an access ramp toward the western end of the SA-6 cap to bring in protective cover soil for placement over GDL. Prior to ramp construction, approved caution tape (as outlined in the project specs was placed at a maximum 55-inch distance on top of the GDL prior to protective cover soil being spread.
- A total of one non-destructive sample (DS-10) was collected for lab testing (as outlined in the project specs). DS-10 was comprised of a fusion weld sample from Panels 32/33.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 7/30/15 consisted of custom fit design or wrinkle removal to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/30/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 1 gas vent).
- Review laboratory destruct samples (peel and shear) for DS-10 and DSX-4

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-9, and DSX-1 through DSX-3. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 17+00 to Sta. 16+00) through the 1st utility corridor.
- Begin placement of GCL along 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/30/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/30/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 7/30/15 |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for pre and destruct welds completed up to 7/30/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 7/30/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample from 7/30/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 7/30/15 |
| A10 – Repair Log | Page 7 | One repair report provided by ESI and confirmed by Langan for repairs conducted on 7/30/15. |
| A11 – Conformance COC | | N / A for 7/30/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 7/30/15. |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with sample information from 7/30/15 |
| A14 – Penetration & Edge Form | | N / A to be completed for PZ-18 once final clamps and gaskets are installed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed on 7/30/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/30/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/30/15

**Direction Taken:**

Looking southeast along southern end of cap

**Description:**

ESI conducting booting activities for PZ-18 (located on P-32).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/30/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/30/15

**Direction Taken:**

Looking west along installed geomembrane cap (taken from approx. Sta. 17+50)

**Description:**

Installed geomembrane cap to date.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/30/15

**Direction Taken:**

Looking southwest along geomembrane cap

**Description:**

ESI conducting patch / repair work for panels installed on 7/29/15 (Panels 31-34).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/30/15

**Direction Taken:**

Looking southeast along SA=6 cap.

**Description:**

ESI conducting vacuum box testing (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/30/15

**Direction Taken:**

Looking north along SA-6

**Description:**

ESi deploying GDL over previously installed geomembrane cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/30/15

**Direction Taken:**

Looking west along SA-6 cap from approx. Sta. 17+50

**Description:**

Installed GDL up to approx. Sta. 21+00 (collection manhole).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/30/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/30/15

**Direction Taken:**

Looking west along northern slope of SA-6

**Description:**

Entact beginning to build ramp and access-way for soil placement over GDL. Warning tape placed at approx. 55-inch intervals over GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/30/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/30/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Ramp built up to SA-6 for placement of cover soil over installed GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/31/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 73/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1700 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #12**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## *Site Activities*

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from Panel #21 (P-21) to approximate Panel #33 (P-33). Based on the PM thunderstorms from 7/30/15, soil subgrade through the utility corridor could not be approved due to soft / wet areas identified. As such, ESI prepped to deploy GDL over the installed geomembrane areas.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI filling sand bags for GVL / geomembrane placement.
- While ESI was filling sandbags, Langan, AmecFW, and Entact conducted a review of the as-built panel layout to confirm repairs and associated panel locations. Once this information was confirmed, ESI began to deploy GDL over the installed geomembrane.
- ESI deployed GDL along the western end of the cap. GDL was placed from approximate Sta. 20+00 (approx. P-21 location) to approx. Sta. 17+00 (approx. P-33 location) which included the placement of 21 rolls (rolls from north to south of SA-6; 28 different panel numbers with butt seams) of GDL from P-21 to P-33. GDL Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and sewing of the geotextile completed for adjacent geocomposite panels (with orange fabric obtained from extra roll of GDL).
- No geomembrane patch / repair work was conducted as part of the 7/31/15 daily activities. Similarly, no new panels were installed as soil subgrade was not approved.

## *Non-Conformance Items / Corrective Actions*

- No non-conformance items observed for work activities completed on 7/31/15. No geomembrane panels installed, and no patch / repair work or sampling was conducted.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/31/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 1 gas vent).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work to remove soft / wet areas for the next 100 ft. run east (approximately from Sta. 17+00 to Sta. 16+00) through the 1st utility corridor.
- Begin placement of GCL along 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/31/15 |
| A3 – Photo Log | Pages 1 – 2 | Total of 4 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/31/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 7/31/15 |
| A6 – Trial Weld Log | | N / A – no trial welds conducted for 7/31/15 activities |
| A7 – Panel Placement Log | | N / A no panels placed on 7/30/15 |
| A8 – Destruct Seam Testing COC | | N / A no non-destruct samples collected on 7/31/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 7/31/15 |
| A10 – Repair Log | | N / A no repair report for 7/31/15 activities |
| A11 – Conformance COC | | N / A for 7/31/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 7/31/15 |
| A13 – Destruct. Sample Summary | | N / A no updates from 7/31/15 |
| A14 – Penetration & Edge Form | | N / A to be completed for PZ-18 once final clamps and gaskets are installed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed on 7/31/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/31/15

**Direction Taken:**

Looking north along 1st utility corridor (located at approx. Sta. 16+50

**Description:**

Utility corridor with wet / soft areas identified due to heavy rains. Soil subgrade not approved for GCL placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/31/15

**Direction Taken:**

Looking south along geomembrane cap (near approx. Sta. 19+90)

**Description:**

ESI deploying GCL over previously installed geomembrane panels near Sta. 19+90 (over Panels 21 & 22).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/31/15

**Direction Taken:**

Looking west along SA-6 (installed GDL)from approximate Sta. 17+20

**Description:**

Installed GDL up to approximate Sta. 17+20 along SA-6 (from western end).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/31/15

**Direction Taken:**

Looking west along northern end of SA-6 (at approx.. Sta. 18+00.

**Description:**

Installed GDL to date



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/3/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 73/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1945 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #13**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #34 (P-34) installed on 7/29/15 (located at approximate Sta. 17+00) running through first utility corridor approximately 120 ft. east to Sta. 15+80 (to eastern end of 1st utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing an additional two panels of GDL (moving east from Panel #33) to cover up to geomembrane Panel #34 (P-34). While GDL was being placed, Langan and Entact conducted soil subgrade approval from approximate Sta. 17+00 to Sta. 15+80 (through 1st utility corridor). Refer to *Soil Subgrade Approval* forms from 8/3/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1,2, and 3 of the daily photo log for 8/3/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 17+00 to Sta. 15+80 (to eastern side of 1st utility corridor).
- Geocomposite clay liner (GCL), GVL and Cap placement began with ESI placing the GCL along the bottom and slopes of the utility corridor (shown in the *8/3/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite. Note: Prior to GCL placement, a soil transition slope (approx. 2 ft. by 2 ft. was constructed along the northern slope of the utility corridor to allow the GCL to transition over the slope without having to conform to the 90 deg. turns of the SCB wall). This soil slope modification was approved prior to construction.
- In addition to the GCL (placed within the utility corridor), 16 oz. geotextile was placed along the boundaries of the SA-6 South Cap (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/3/15 Photo Log* for supporting photographs.

- After installation of GCL and GVL through the utility corridor, geomembrane cap was installed continuing east of previously installed Panel #34 (located at approximate Sta. 17+00) on 7/29/15. Panels were oriented from east to west through the utility corridor (as proposed in the approved Panel Layout) and were installed through the utility corridor (located at approx. Sta. 16+50) running from the top of the western slope to the top of the eastern slope. Additional panels were installed outside of the utility corridor and were T (butt seamed) into the east-west panels from inside the utility corridor (the panels outside of the utility corridor reverted back to the north-south orientation as indicated on the approved panel layout). A total of twelve panel lengths (different dimensions and sizes) were installed (P-35, P-36, P-37, P-38, P-39, P-40, P-41, P-42, P-43, P-44, P-45, and P-46) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/3), *Trial Weld Log.*
- Installation and welding of the geomembrane panels was conducted until approximately 8 pm to ensure that the utility corridor was properly covered and sealed due to expected overnight storms. As such, no non-destructive testing on the installed panels was conducted. Additionally, no patch / repair work was completed, and no destructive samples were collected. These activities will be completed tomorrow (8/4/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no patch / repair work was conducted on geomembrane cap.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/3/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 15+80 to Sta. 14+80) east of utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/3/15 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 7/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/3/15 |
| A5 – Subgrade Approval | Sheet 8 & ESI (8/3/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/3/15. |
| A7 – Panel Placement Log | Pages 8 & 9 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/3/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/3/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 8/3/15 |
| A10 – Repair Log | | N / A no repairs conducted on 8/3/15 |
| A11 – Conformance COC | | N / A for 8/3/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 8/3/15 |
| A13 – Destruct. Sample Summary | | N / A no updates to form (no samples collected on 8/3) |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/3/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking north along 1st utility corridor (located at approx. Sta. 16+50

**Description:**

Utility corridor subgrade dried, graded, and compacted after storm. Area approved for geomembrane placement (as per project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking west along northern end of SA-6

**Description:**

ESI constructing approx. 2 ft. by 2 ft. soil slope up to SCB wall. Approved change from having GCL and geomembrane with 90 deg. bends along SCB wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south along 1st utility corridor (approx. Sta. 16+50)

**Description:**

Approved soil subgrade for cap placement. Soil graded, compacted, and free of debris (>1/2"), as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south / southwest along utility corridor (approx. Sta. 16+50)

**Description:**

ESI installing GCL along bottom of utility corridor (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/03/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/3/15

**Direction Taken:**

Looking south along bottom of utility corridor

**Description:**

ESi overlapping GCL panels (minimum of 1 ft.) as outlined in project specs. Bentonite used to seal seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/03/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/3/15

**Direction Taken:**

Looking north along bottom of utility corridor

**Description:**

ESI placing granular bentonite along GCL seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking west along utility corridor (approx. Sta. 16+50)

**Description:**

ESI installing GCL along slopes of corridor to minimum elevation (approx. El. 14) as outlined in the project specifications. GCL overlapped a minimum of 1 ft. along seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking southwest along utility corridor.

**Description:**

GCL installed along base and western wall of utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south along western slope of utility corridor

**Description:**

GCL overlapped a minimum of 2 ft. over the top of the corridor slope. GCL secured with 6-inch staples along top of panel.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south along eastern end of utility corridor.

**Description:**

GVL panel installed over top of GCL (minimum of 1 ft. overlap) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south down along utility corridor

**Description:**

GCL installed throughout utility corridor. ESI prepping to cover GCL with geomembrane cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/3/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at utility corridor)

**Description:**

ESI placing geomembrane panels along southern end of utility corridor. Panels oriented in east to west direction (perpendicular to slope), as outlined in approved panel layout.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/3/15

**Direction Taken:**

Looking west / northwest at northern end of utility corridor.

**Description:**

ESI conducting fusion welding of Panels 35/36 located at northern end of utility corridor (oriented east to west).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking north along 1st utility corridor (located at approx. Sta. 16+50)

**Description:**

Geomembrane panels placed over GCL along utility corridor. Panels oriented perpendicular to slope (east to west).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking east along northern end of SA-6

**Description:**

ESI placing geomembrane panel along southern end of GCL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #16 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/3/15

**Direction Taken:**

Looking south along utility corridor

**Description:**

Geomembrane panels installed along utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/4/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/85° F, AM Rain, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #14**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from east of Panel #42 installed on 8/3/15 (located at approx. Sta. 15+80) moving east approximately 100 ft. to approximate Sta. 14+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Based on the AM storms / rain, ESI could not conduct patch / repair work (i.e. extrusion welding) on the geomembrane panels installed on 8/3/15 due to the inclement weather. Observation of the next section of soil subgrade (approx. Sta. 15+80 to 14+80) was conducted and soft / wet areas were identified with ponding water (due to the storms). As such, soil subgrade was not approved for additional panel placement. Refer to *8/4/15 Photo Log* for subgrade photos. ESI offsite until 12 PM for weather to clear.
- Entact removed the protective plastic layer covering the soil subgrade and conducted drying activities, re-grading, and re-compaction of the soil (as required).
- ESI back onsite at approximately 12 PM to conduct patch / repair work for the panels installed on 8/3/15 (Panels 35-46). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 8/4/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-one repairs (RP-145 through RP-185) were observed and fixed (according to the project specifications) from Panel #35 through Panel #46 (repair / detailing work conducted on panels installed on 8/3/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- No non-conformance issues were noted as repairs consisted of custom fit design or routine patch / repair work to allow geomembrane to conform to SA-6 contours.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of two destruct samples, DS-11 and DS-12 (fusion weld samples) were collected for laboratory analysis. DS-11 was collected from panel seam 36/37 and DS-12 was collected from panel seam 42/43

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 8/4/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/4/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).
- Review laboratory results for DS-11 and DS-12

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work to remove soft / wet areas for the next 80 ft. run east (approximately from Sta. 15+80 to Sta. 15+00) of 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/4/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 8/4/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 8/4/15 |
| A6 – Trial Weld Log | Page 2 | Preweld test form for 8/4/15 provided by ESI and confirmed by Langan for prewelds up to 8/4/15 |
| A7 – Panel Placement Log | | N / A no panels placed on 8/4/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 8/4/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 7,8,9,10,11 | Seam Control Form for 8/4/15 provided by ESI and confirmed by Langan for non-destruct tests completed up to 8/4/15 |
| A10 – Repair Log | Pages 7,8,9 | Repair Log for 8/4/15 provided by ESI and confirmed by Langan for repairs completed up to 8/4/15 |
| A11 – Conformance COC | | N / A for 8/4/15 |
| A12 – Destructive Seam Field Test | Sheet 2 | Destruct Sample Information provided by ESI and confirmed by Langan for destruct samples collected on 8/4/15 (DS-11 and DS-12) |
| A13 – Destruct. Sample Summary | Sheet 2 | Updated with destruct sample information from 8/4/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking south along SA-6 (at approx. Sta. 15+80)

**Description:**

Soil subgrade immediately east of previously installed panels (from 8/3) at approx. Sta. 15+80. Wet / soft areas identified and area not suitable for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking west along SA-6 (at approx. Sta. 15+80) at drainage swale / corridor located at Grid Point 165-15.01

**Description:**

Water ponding from rain storm from 8/3. Soil subgrade not acceptable for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking down along SA-6 utility corridor (southwestern slope) near Break Point 832-4.44

**Description:**

ESI conducting patch repair work along installed panels from 8/3 (Panels 35-46)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking east along SA-6 cap

**Description:**

ESI conducting vacuum box testing along patch / repair work from Panels 35-46.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking along the northwestern slope of utility corridor (looking at approximate Break Point 823-16.40)

**Description:**

Patch / repair work along northwestern slope of utility corridor (RP-151 & RP-157).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking north / northwest along utility corridor (looking at northwest slope).

**Description:**

ESI conducting patch / repair work along utility corridor. Also conducting extrusion welding and vacuum box testing (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking west along southern slope of SA-6 (near Break Point 842-4.57)

**Description:**

ESI collecting destruct sample (DS-12) along Panel 42/43 seam.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking west / northwest along SA=6 cap.

**Description:**

ESI labeling and marking repairs upon completion of vacuum box testing.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking east along SA-6 cap

**Description:**

ESI conducting extrusion weld along patches / repairs (as outlined in project specs).



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/5/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1700 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #15**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #42 (P-42) installed on 8/3/15 (located at approximate Sta. 15+80) running approximately 70 ft. east to Sta. 15+10.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work for three wrinkles (refer to *Repair Log* 8/5/15) that were identified along Panels 35-46 which were placed on 8/3/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/5/15).
- A total of nine repairs (RP-186 through RP-194) were observed and fixed (according to the project specifications) from Panel #35 and Panel #36. As outlined above, these repairs were associated with removing geomembrane wrinkles to allow the cap to conform to the contours of SA-6 South grade. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications. Note: no repairs of the geomembrane from 8/5/15 were identified as non-compliance issues.
- Additionally, while the geomembrane was being patched / repaired, ESI also installed the penetration boots for the wells, piezometers, and gas vents protruding through the cap (Note: Penetration logs will be completed once final sealant is placed around top of boot). Orange composite (GDL) was also placed over butt seams of the geocomposite and leistered in place. These patching activities were completed (as needed) to allow Entact to continue placing protective cover soil over the installed GDL along the western end of SA6. The final GDL layer was inspected by Entact and Langan to ensure that all repairs / patches were completed prior to soil placement.
- While patch / repair work was being conducted, Langan and Entact conducted soil subgrade approval from approximate Sta. 15+80 to Sta. 15+10. Refer to *Soil Subgrade Approval* forms from 8/5/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

that the surface was free of any loose material. Refer to Photos #5,6 of the daily photo log for 8/5/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 15+80 to Sta. 15+10.

- Cap placement began with ESI placing the GCL along the southern slope (lower bench along southern end of SA-6 located below the groundwater table) of the southern edge of SA-6 (refer to *8/5/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- In addition to the GCL (placed along the southern slope), 16 oz. geotextile was placed along the northern boundary of the SA-6 South Cap, and also along the southern boundary east of the GCL (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.
- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/5/15 Photo Log* for supporting photographs.
- After installation of GCL and GVL along the SA-6 boundaries, geomembrane cap was installed continuing east of previously installed Panel #42 (located at approximate Sta. 15+80) on 8/3/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GCL layers. A total of three panel lengths were installed (P-47, P-48, P-49) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/5), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. As such, no non-destructive testing on the installed panels was conducted. Additionally, no patch / repair work was completed, and no destructive samples were collected. These activities will be completed tomorrow (8/6/15). Note: An extrusion weld sample (DSX-5) was collected from the patch / repair work previously completed on 8/4/15.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as repair work was conducted to remove wrinkles from the cap to allow the geomembrane to properly conform to the contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/5/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).
- Review laboratory data for extrusion destruct sample DSX-5

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, and 8/4/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 15+10 to Sta. 14+10) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/5/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 8/5/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/5/15 |
| A5 – Subgrade Approval | Sheet 9 & ESI (8/5/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/5/15. |
| A7 – Panel Placement Log | Page 10 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/5/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with information from destruct sample (DSX-5) collected on 8/5/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 8/5/15 |
| A10 – Repair Log | Pages 9-10 | One Repair Log provided by ESI and confirmed by Langan for 8/5/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/5/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destruct sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/5/15 |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with destruct sample information from 8/5/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/5/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/5/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI finalizing GDL cap by covering and patching butt seams and associated repairs (as required).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking southwest along SA-6 cap (at GV-6 location)

**Description:**

ESI constructing boot and placing sacrificial sheet around GV-6 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking north at northeastern slope of utility corridor (located at approx. Grid Point 149-5.59

**Description:**

ESI conducting patch repair work for wrinkles identified from geomembrane panel placement (from 8/3/15).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south along southern edge of SA-6 cap (located at PZ-18)

**Description:**

Installed geomembrane boot around PZ-18 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking west (from approx. Sta. 15+80) at approximate Grid Point 165-15.01

**Description:**

Soil subgrade at approximate Grid Point 165-15.01. Soil has been dried, re-graded, and re-compacted for panel placement. Soil subgrade prepared in accordance with project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south at southern end of SA-6 cap (taken from approximate Sta. 15+80)

**Description:**

Previously identified soft / wet area from 8/4/15. Soil allowed to dry and was re-compacted (as required). Soil acceptable for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Entact spreading protective cover soil along previously installed GDL (located at western end of cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south along southern end of SA-6 (approximate Sta. 15+80)

**Description:**

ESI placing GCL along lower elevations (to 1 ft. above the groundwater table). Panels placed moving east from Sta. 15+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking north at tops of installed GCL panels

**Description:**

Support staples (with rounded heads) placed along the top of the GCL panels for support (as outlined in project specs). Staples to be overlapped with 1 ft. minimum of GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking north along SA-6 (immediately east of approx. Sta. 15+80).

**Description:**

ESI deploying GVL immediately east of approx. Sta. 15+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking north along SA-6 at Collection Manhole #2

**Description:**

ESI deploying geomembrane panels over installed GVL east of Sta. 15+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south along Panel #47 (P-47)

**Description:**

ESI conducting fusion welding along Panel seam 42/47 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/6/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #16**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #49 (P-49) installed on 8/5/15 (located at approximate Sta. 15+10) running approximately 110 ft. east to Sta. 14+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL over the previously installed geomembrane panels from 8/3/15. A total of 10 panel lengths of GDL were placed along the west side of the utility corridor and along the western slope of the utility corridor with end points of the GDL terminating along the approximate center of the utility corridor (east to west orientation). The GDL was placed north to south outside of the corridor and east to west within the corridor and secured with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile was sewn (according to the project specs).
- While GDL was being placed over the previously installed geomembrane, Langan and Entact conducted soil subgrade approval from approximate Sta. 15+10 to Sta. 14+00. Refer to *Soil Subgrade Approval* forms from 8/6/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #7,8, and 9 of the daily photo log for 8/6/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 15+10 to Sta. 14+00.
- Cap placement began with ESI placing the GCL along the southern slope (lower bench along southern end of SA-6 located below the groundwater table) of the southern edge of SA-6 (refer to *8/6/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with granular bentonite.
- Prior to deploying any geomembrane panels over the GCL, it was confirmed that the GCL maintained intimate contact between the material and the HB wall (southern boundary wall). Soil was removed from the top of the sheet piles (as required) by Entact. Refer to Photo #14 of the *Photo Log 8/6/15*.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- In addition to the GCL (placed along the southern slope), 16 oz. geotextile was placed along the northern boundary of the SA-6 South Cap, and also along the southern boundary east of the GCL (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.
- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/6/15 Photo Log* for supporting photographs.
- After installation of GCL, 16 oz. geotextile (along SA-6 boundaries) and GVL, geomembrane cap was installed continuing east of previously installed Panel #49 (located at approximate Sta. 15+10) on 8/5/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of four panel lengths (lengths defined as running the approximate 165 ft. north to south distance of the cap) were installed (P-50, P-51, P-52, P-53, P-54) by ESI. Note: P-51 terminated approximately 6 ft. short of the southern boundary of the SA-6 cap. As such, the remaining section was taken from an additional roll (G15C277060) and labeled as Panel #52 (P-52).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/6), *Trial Weld Log.*
- Upon panel installation and fusion welding, ESI conducted non-destructive seam testing in accordance with the project specs. No patch / repair work was completed, and no destructive samples were collected as work activities were completed after non-destruct testing was completed. These additional activities will be completed tomorrow (8/7/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as non-destruct testing was in conformance with the project specs and no patch / repair work, or vacuum box testing was conducted on 8/6/15.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/6/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, and 8/5/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-5. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 14+00 to Sta. 13+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/6/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 8/6/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/6/15 |
| A5 – Subgrade Approval | Sheet 10 & ESI (8/6/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Pages 2-3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/6/15. |
| A7 – Panel Placement Log | Page 11 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/6/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/6/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 11-12 | Seam Control Form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/6/15 |
| A10 – Repair Log | | N / A no repairs completed on 8/6/15 |
| A11 – Conformance COC | | N / A for 8/6/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 8/6/15 |
| A13 – Destruct. Sample Summary | | N / A no updates as no destruct samples collected |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/6/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/6/15

**Direction Taken:**

Looking north through utility corridor (at western slope of utility corridor)

**Description:**

ESI preparing to deploy GDL along utility corridor (over previously installed panels 35-46)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/6/15

**Direction Taken:**

Looking south along SA-6 (approximate Sta. 17+00)

**Description:**

ESI placing GDL over installed geomembrane panels (P-34 & P-35). White plastic fasteners spaced at maximum of 5 ft. intervals and geotextile seam sewn (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/6/15

**Direction Taken:**

Looking south / southeast at bottom of southeast utility corridor slope (located at approx. Break Point 831-4.62

**Description:**

ESI placing GDL along southeastern slope of utility corridor. Panels oriented east to west to run parallel with slope (as outlined in the approved panel layout).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/6/15

**Direction Taken:**

Looking northwest along western slope of utility corridor (approx. Sta. 16+50).

**Description:**

Installed GDL along utility corridor (western slope).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking north along southern slope of SA-6 (southern edge of SA-6).

**Description:**

ESI placing GCL along southern edge of SA-6 slope (east of Sta. 15+10). Pins / staples placed along top 6-inches of GCL to anchor into subgrade slope.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking south / southwest along southern slope of SA-6 (approximate Sta. 14+70).

**Description:**

ESI placing GCL along southern slope (lower bench) of SA-6. GCL placed at areas below (up to 1 ft. above) the Site water table.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking east along SA-6 (from approx. Sta. 15+10).

**Description:**

Soil subgrade along the southern end of SA-6 approved for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

Approved soil subgrade for geomembrane placement. Soil prepared as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/6/15

**Direction Taken:**

Looking south / southwest along SA-6 (at approximate Sta. 15+10)

**Description:**

Prepared soil subgrade according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/6/15

**Direction Taken:**

Looking north along SA-6 (east of approx. Sta. 15+10).

**Description:**

ESI deploying GVL. White plastic fasteners spaced at a minimum of 5 ft., and the top layer of geotextile sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking north along western end of SA-6 cap

**Description:**

Entact covering GDL along western end of cap with protective cover soil. Caution tape spaced at a maximum of 55-inches over GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking northwest along SA-6 cap (from approx. Sta. 14+00)

**Description:**

ESI placing geomembrane over GVL layer from approx. Sta. 15+10 to approx. Sta. 14+00



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking northwest along SA-6 cap (from approx. Sta. 14+30)

**Description:**

ESI conducting fusion welding along installed panel seams (Panels 50-54)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking east along southern wall of SA-6 cap (approx. Sta. 14+70)

**Description:**

Entact pulling back GCL to ensure that HB wall (southern boundary wall) maintains intimate contact with GCL.



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/7/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 68/82° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0600 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #17**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #54 (P-54) installed on 8/6/15 (located at approximate Sta. 14+00) running approximately 100 ft. east to Sta. 13+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 50-54 which were placed on 8/6/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/7/15).
- A total of twenty-three repairs (RP-195 through RP-217) were observed and fixed (according to the project specifications) from Panels #50 through Panel #54 (repair / detailing work conducted on panels installed on 8/6/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-conformance issue was observed for a failed vacuum box test during testing of RP-215. The failed weld was patched and re-welded as outlined on Sheet #5.
- A total of three destruct samples were collected (DS-13, DS-14, and DSX-6). DS-13 and DS-14 (fusion) were collected from Panels 47/48 and 50/51, respectively. DSX-6 (extrusion) was collected from Panel #48 on RP-198.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for Collection Manhole #2. Note: The penetration log for Collection Manhole #2 will be completed once the boot has been sealed and covered according to the project specifications (to be completed on 8/10/15), and the final sealant is placed around top of boot.
- Langan and Entact conducted soil subgrade approval from approximate Sta. 14+00 to Sta. 13+00 while

patch work was being completed by ESI. Refer to *Soil Subgrade Approval* forms from 8/7/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material.Refer to Photo #6 of the daily photo log for 8/7/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 14+00 to Sta. 13+00.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 14+00 (east of P-54) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/7/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #54 (located at approximate Sta. 14+00) on 8/6/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-55, P-56, P-57, P-58, P-59, P-60) by ESI. Note:, during placement of Panel #55 and #59, the roll of geomembrane was completed, thus, Panel #56 was placed for the last 11 ft. (from roll G15C283029) to complete the southern end and Panel #60 (P-60) was placed for the last 15 ft. (from roll G15C276053) to complete the northern end of SA-6.
- During installation of the Cap, geomembrane seams were overlapped a minimum of 4-inches for fusion welding (according to project specs). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specs. A total of six 1-inch specimens were collected for peel and shear testing (3 samples/each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/7), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. Once completed, non-destructive testing on the installed panels was conducted. Non-destruct testing was conducted in accordance with the project specs and is further summarized on the *Seam Control Form (8/7/15).* After non-destructive testing the work day was terminated and no patch / repair work was completed. These activities will be completed on Monday (8/10/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 5 (Sheet #5) – Failed vacuum box test of RP-215 on *Repair Log*
    - Failed vacuum box test of RP-215 (Panel #50). Failed weld was covered with a new patch and welded (RP-222) as per project specs and further defined in *Sheet 5 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/7/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 14+35).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-13, DS-14 and DSX-6

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, and 8/6/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-5. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 13+00 to Sta. 12+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/7/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/7/15 |
| A5 – Subgrade Approval | Sheet 11 & ESI (8/7/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/7/15. |
| A7 – Panel Placement Log | Page 12 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/7/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/7/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 12-14 | One Seam Control form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/7/15 |
| A10 – Repair Log | Pages 10-11 | One Repair Log provided by ESI and confirmed by Langan for 8/7/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/7/15 |
| A12 – Destructive Seam Field Test | Page 2 | Provided for destruct samples DS-13, DS-14, and DSX-6 collected for 8/7/15 |
| A13 – Destruct. Sample Summary | Sheet 2 | Updated with destruct samples collected on 8/7/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 5 | One Notice of Non-Compliance form created by Langan (Sheet #5) for failed vacuum box test |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/7/15

**Direction Taken:**

Looking south along SA-6 cap (RP-216)

**Description:**

ESI conducting vacuum box testing (according to project specs) on seam joint located on southern edge of SA-6 (Panels 50,51,52)




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/7/15

**Direction Taken:**

Looking south along SA-6 at Panels 50/51

**Description:**

ESI collecting destruct sample (DS-14) along fusion welded seam (Panels 50/51). Sample collected near northern edge of SA-6



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking south near approx. Sta. 15+70 (at Access Manhole #2)

**Description:**

ESI placing LLDPE boot (RP-218) around Access Manhole #2 (located at approximate Sta. 15+70).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking north along SA-6 cap (western end)

**Description:**

Entact spreading protective cover soil along western end of SA-6. Yellow caution tape placed at maximum of 55-inch spacing (as outlined in project specs)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking at geomembrane cap (RP-215) located at Panel #50

**Description:**

Failed vacuum box test at RP-215. Leak detected during vacuum box testing of extrusion weld. Failed weld to be patched / repaired as outlined in project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking east along SA-6 (from approximate Sta. 14+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking south along SA-6 (approx. Sta. 13+70)

**Description:**

ESI deploying GVL (approx. Sta. 13+70). White plastic fasteners spaced at maximum of 5 ft. (as outlined in project specs) and top geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 13+75)

**Description:**

ESI deploying geomembrane over GVL. (at approx. Sta. 13+75)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/7/15

**Direction Taken:**

Looking southeast along SA-6 (Panels 57/58)

**Description:**

ESI conducting fusion welding along Panel 57/58 seam (welding conducted according to project specs)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/7/15

**Direction Taken:**

Looking west along southern end of SA-6 (approximate Sta. 13+20)

**Description:**

ESI conducting fusion welding along Panels 58/59,down southern slope of SA-6



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/10/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/78° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #18**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #60 (P-60) installed on 8/7/15 (located at approximate Sta. 13+00) running approximately 100 ft. east to Sta. 12+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 55-60 which were placed on 8/7/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/10/15).
- A total of thirty-one repairs (RP-218 through RP-248) were observed and fixed (according to the project specifications) from Panels #55 through Panel #60 (repair / detailing work conducted on panels installed on 8/7/15). Refer to 8/10/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for well 115-W5-SO, and completed placing the geomembrane patch around Access Manhole #2. Note: The penetration log for well 115-W5-SO will be completed once the boot has been sealed and covered according to the project specifications and the final sealant is placed around top of boot.
- Langan and Entact conducted soil subgrade approval from approximate Sta. 13+00 to Sta. 12+00 while patch work was being completed by ESI. Refer to *Soil Subgrade Approval* forms from 8/10/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #5 and #6 of the daily photo log for 8/10/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 13+00 to Sta. 12+00.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 13+00 (east of P-60) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/10/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #60 (located at approximate Sta. 13+00) on 8/7/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-61, P-62, P-63, P-64, and P-65) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/10), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. Once completed, non-destructive testing on the installed panels was conducted. Non-destruct testing was conducted in accordance with the project specs and is further summarized on the *Seam Control Form (8/10/15).* After non-destructive testing the work day was terminated and no patch / repair work was completed.
- A total of three destructive samples were collected (two fusion and one extrusion weld). Fusion weld destruct samples (DS-15, DS-16) were collected from Panel Seams 54/55 and 59/61 respectively. DSX-7 was collected along Panel 53/54 seam. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/10/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-15, DS-16, DS-17, and DSX-7

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, and 8/7/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-14, and DSX-1 through DSX-6. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 12+00 to Sta. 11+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/10/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 8/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/10/15 |
| A5 – Subgrade Approval | Sheet 12 & ESI (8/10/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/10/15. |
| A7 – Panel Placement Log | Page 13 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/10/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct samples collected on 8/10/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 14 | One Seam Control form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/10/15 |
| A10 – Repair Log | Pages 11-12 | One Repair Log provided by ESI and confirmed by Langan for 8/10/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/10/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destruct sample information form provided by ESI and confirmed by Langan for 8/10/15 |
| A13 – Destruct. Sample Summary | Sheet 2 | Updated with destruct sample information from 8/10/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted on 8/10/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking south / southwest along geomembrane cap at Access Manhole #2 (approx. Sta. 15+70)

**Description:**

ESI installing geomembrane boot and patching cap around Access Manhole #2 (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI conducting patch / repair work for "custom fit" patches around slopes & contours. Patch work conducted as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/10/15

**Direction Taken:**

Looking west along SA-6 cap (at RP-215)

**Description:**

ESI conducting vacuum box testing (as outlined in project specs) on patch (RP-222) placed over RP-215 to repair failed extrusion weld.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/10/15

**Direction Taken:**

Looking north / northeast SA-6 (at RP-223)

**Description:**

ESI conducting extrusion welding along northern end of SA-6 at RP-223 (where DS-14 collected)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking north along SA-6 (from approx. Sta. 13+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (from approx. Sta. 13+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking west along SA-6 cap (at RP-215)

**Description:**

Failed vacuum box test (RP-215), patched and repaired (RP-222) according to project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (from approx. Sta. 13+00)

**Description:**

ESI deploying 16 oz. geotextile along southern boundary of SA-6. Textile overlapping HB wall by 2 ft. with remaining roll width inside SA-6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking north along SA-6 (from approx. Sta. 13+00)

**Description:**

ESI deploying GVL along approved soil subgrade.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking south along SA-6 (from approx. Sta. 12+50)

**Description:**

White plastic fasteners spaced at a maximum of 5 ft. along geonet with top layer of geotextile sewn (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/10/15

**Direction Taken:**

Looking north / northeast along SA-6 (at approximate Sta. 13+00)

**Description:**

ESi deploying geomembrane over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/10/15

**Direction Taken:**

Looking west along geomembrane (at Panels 60/61)

**Description:**

ESI conducting fusion welding along Panel Seam 60/61.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/10/15

**Direction Taken:**

Looking north along geomembrane cap (at Panels 62/63)

**Description:**

Patch / repair placed over destruct sample (DS-17) located at approximate center of SA-6 on Panels 62/63 seam.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/10/15

**Direction Taken:**

Looking south along geomembrane cap (at well 115-W5-S0)

**Description:**

ESI placing gasket and sealing GVL for placement of geomembrane boot around well 115-W5-SO.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/12/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 71/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #19**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-65) installed on 8/10/15 (located at approximate Sta. 12+00) running approximately 100 ft. east to Sta. 11+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 61-66 which were placed on 8/10/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/12/15).
- A total of four repairs (RP-249 through RP-252) were observed and fixed (according to the project specifications) from Panels #64 through Panel #66 (repair / detailing work conducted on panels installed on 8/10/15). Refer to 8/12/15 *Repair Report* for supporting information. The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed / construction penetration boots for well 115-W5-SO and gas vent #5 (GV-5). Note: These penetration logs will be completed once the final clamps and seal (butyl seal) have been completed according to the project specifications and the final sealant is placed around top of boot.
- While ESI was conducting repair / patch work, Langan and Entact conducted soil subgrade observation from approximate Sta. 12+00 to Sta. 11+00. Based on visual inspection, the soil subgrade appeared to contain areas of soft / wet subgrade due to rainstorms from 8/11/15. Based on these soft areas, soil subgrade was not approved for geomembrane placement. Entact conducted additional preparation work (i.e. drying the soil and re-grading and re-compacting) as required, to conform the subgrade to the project specifications (refer to Photo #7 of the daily photo log for 8/12/15)

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After completing patch / repair work from the panels installed on 8/10/15, ESI began to place GDL continuing east along the utility corridor. GDL was placed along the eastern slope of the utility corridor (located at approximate Sta. 16+50). Panels were oriented east to west within the utility corridor, and reverted back to the north and south orientation outside of the corridor (refer to the *8/12/15 Photo Log* for supporting photos)
- GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/12/15 Photo Log* for supporting photographs.
- No new geomembrane panels were placed as the soil subgrade for the next 100 ft. section was not approved. No destruct samples were collected, as DS-17 was collected on 8/10/15 during panel placement.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 5 ft. spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no new geomembrane panels were placed and the patch / repair work conducted on geomembrane cap was in compliance with the project specifications.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/12/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, and 8/10/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 12+00 to Sta. 11+00) east of utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/12/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/12/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/12/15 |
| A5 – Subgrade Approval | | N / A no subgrade approved due to soft / wet conditions observed from storms on 8/11/15 |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/12/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 8/12/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/12/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 14-15 | Updated with vacuum box test conducted from 8/12/15 on Panels 64/66 |
| A10 – Repair Log | Page 12 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 8/12/15 |
| A11 – Conformance COC | | N / A for 8/12/15 |
| A12 – Destructive Seam Field Test | | N / A no destructive samples collected on 8/12/15 |
| A13 – Destruct. Sample Summary | | N / A no destructive samples collected on 8/12/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/12/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking west along SA-6 cap (from approximate Sta. 19+00)

**Description:**

Entact spreading protective cover soil along western end of SA-6 (over previously installed geomembrane and GDL panels). Caution tape placed on top of GDL at maximum of 55-inch intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking west along northern end of SA-6 cap (at well 115-W5-SO)

**Description:**

ESI constructing geomembrane boot around monitoring well 115-W5-SO



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking east along northern end of SA-6 cap

**Description:**

ESI conducting extrusion welding (as per project specifications) along geomembrane boot (RP-246)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/12/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

ESI conducting vacuum box testing along monitoring well boot (extrusion weld) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking north / northwest along SA-6 cap (at approximate Sta. 16+00)

**Description:**

ESi welding geomembrane boot over gas vent (GV-5) as outlined in project specs (located at approx. Sta. 16+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking north along SA-6 cap (at approx. Sta. 16+00)

**Description:**

ESi conducting vacuum box testing along extrusion welds for geomembrane boot GV-5.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta. 12+00)

**Description:**

Entact conducting soil preparation activities for geomembrane placement on 8/13/15. Subgrade exhibitied soft / wet areas in the morning from rain storms on 8/11/15. Soil allowed to dry and re-graded and re-compacted (as required).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/12/15

**Direction Taken:**

Looking east along southern end of SA-6 through 1st utility corridor (approximate Sta. 16+50)

**Description:**

ESI deploying GDL along eastern end of 1st utility corridor (at approx. Sta. 16+50)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking east along SA-6 (through 1st utility corridor)

**Description:**

ESI deploying GDL along eastern slope of utility corridor (approximate Sta. 16+50) working from the south end to the north end of the corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking west along SA-6 cap (at approximate Sta. 16+00)

**Description:**

ESI placing clamps over geomembrane boot for SV-5 (sacrificial sheet placed prior to clamping as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/13/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #20**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-65) installed on 8/10/15 (located at approximate Sta. 12+00) running approximately 100 ft. east to Sta. 11+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 12+00 to Sta. 11+00. Refer to *Soil Subgrade Approval* forms from 8/13/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 8/13/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 12+00 to Sta. 11+00. Note: The soft / wet areas identified on 8/12/15 were allowed to dry and were repaired for geomembrane placement.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 12+00 (east of P-65) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/13/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #65 (located at approximate Sta. 12+00) on 8/10/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

installed (P-67, P-68, P-69, P-70, and P-71) by ESI.

- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/13), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 11+00, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (8/13/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, no patch / repair work was conducted, and any associated repairs will be completed on 8/14/15.
- After completing non-destructive testing along the panels installed today (8/13/15), ESI began to place GDL continuing east from the 1st utility corridor (located at approx. Sta. 16+50). Panels were oriented from north to south (as outlined in the proposed GDL layout). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/13/15 Photo Log* for supporting photographs.
- A total of two destructive samples were collected (two fusion welds). Fusion weld destruct samples (DS-18, DS-19) were collected from Panel Seams 64/65 and 68/69, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 55-inch spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17, DS-18, and DS-19 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, and 8/12/15 as well as reviewed and approved daily ESI form submittals.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 11+00 to Sta. 10+20) to Access Manhole #3 (ESI demobilization point).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/13/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/13/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/13/15 |
| A5 – Subgrade Approval | Sheet 13 & ESI (8/13/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/13/15. |
| A7 – Panel Placement Log | Page 14 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/13/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/13/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 15-16 | Updated with vacuum box test conducted from 8/13/15 on Panels 67 through 71 |
| A10 – Repair Log | | N / A no repairs completed on 8/13/15 |
| A11 – Conformance COC | | N / A for 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/13/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/13/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking south / southwest along SA-6 (from approximate Sta. 11+50)

**Description:**

Prepared soil subgrade for next approximate 100 ft. of geomembrane (from approximate Sta. 12+00 to Sta. 11+00). Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking south / southeast along SA-6 (at approximate Sta. 11+50)

**Description:**

Soil subgrade prepped for geomembrane placement. Soil graded, compacted, and free of loose debris (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 12+00)

**Description:**

ESI placing GVL along approved soil subgrade. White plastic fasteners spaced at maximum of 5 ft. intervals and top geotextile sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/13/15

**Direction Taken:**

Looking south along SA-6 cap (approximate Sta. 12+00)

**Description:**

ESI sewing top layer of geotextile along GVL (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/13/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/13/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 12+00)

**Description:**

ESi placing geomembrane cap over GVL (at approx. Sta. 12+00)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/13/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/13/15

**Direction Taken:**

Looking northwest along SA-6 cap (Panels 65/67)

**Description:**

ESi conducting fusion welding along Panel 65/67 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking west along geomembrane cap at DS-19 (RP-254)

**Description:**

Geomembrane patch leistered over DS-19 (RP-254). Patch to be completed on 8/14/15 with extrusion weld and vacuum box testing (as outlined in project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking northwest along SA-6 cap

**Description:**

ESI deploying GDL along western end of cap (located at approximate Sta. 15+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/14/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 78/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1430 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #21**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-71) installed on 8/13/15 (located at approximate Sta. 11+00) running approximately 80 ft. east to Sta. 10+20 (western slope of 2nd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 11+00 to Sta. 10+20. Refer to *Soil Subgrade Approval* forms from 8/14/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 11+00 to Sta. 10+20.
- Geocomposite clay liner (GCL), GVL and Cap placement began with ESI placing the GCL along the southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- In addition to the GCL (placed along the southern slope below the groundwater table), 16 oz. geotextile was placed along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 11+00 (east of P-71) moving east (for approximately 80 ft.) to Sta. 10+20. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/14/15 Photo Log* for supporting photographs.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #71 (located at approximate Sta. 11+00) on 8/13/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-72, P-73, P-74, and P-75) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/14), *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 10+20, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (8/14/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. ESI conducted patch / repair work for the panels installed on 8/13/15 (Panels 66-71) and 8/14/15 (Panels 72-75). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 8/14/15 for results (extrusion testing identified as EXT. on form).
- A total of ten repairs (RP-253 through RP-262) were observed and fixed (according to the project specifications) from Panel #71 through Panel #75 (repair / detailing work conducted on panels installed on 8/13/15 & 8/14/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Upon completion of patch / repair activities, ESI began to pack and load equipment for their 2-week demob from the Site.
- A total of two destructive samples were collected (two fusion welds). Fusion weld destruct samples (DS-20, DS-21) were collected from Panel Seams 70/71 and 74/75, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 55-inch spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17, DS-18, DS-19, DS-20, and DS-21 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, and 8/13/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South after 2-week demobilization is complete.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/14/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/14/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/14/15 |
| A5 – Subgrade Approval | Sheet 14 & ESI (8/14/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/14/15. |
| A7 – Panel Placement Log | Page 15 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/14/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 15-16 | Updated with vacuum box test conducted from 8/13/15 on Panels 67 through 71 and 8/14/15 on Panels 71 through 75 |
| A10 – Repair Log | Page 13 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 8/14/15 |
| A11 – Conformance COC | | N / A for 8/14/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/14/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/14/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking west along southern end of SA-6 (from approximate Sta. 11+00)

**Description:**

ESI placing GCL along southern slope of SA-6 (soil below to 1 ft. above the water table). Stakes / staples placed on top of slope (top 6-inches of GCL to hold GCL in-place).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Installed GCL panels along southern slope with anchor supports (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking north along SA-6 (from approximate Sta. 10+50)

**Description:**

GVL placed be ESI according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking north along SA-6 cap (from approximate Sta. 10+80

**Description:**

Geomembrane panels placed over GDL and fusion welded (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

ESi conducting fusion welding for Panels 71/72 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 cap (at Panel 74/75 seam)

**Description:**

ESi collecting destruct sample (DS-21) at Panel 74/75 seam (fusion weld).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking south along southern end of SA-6 cap (along lower bench)

**Description:**

Geomembrane panels 74 and 75 installed and labeled along southern end of cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 camp (Panel 74/75) seam at DS-21

**Description:**

Destruct sample (DS-21) patched and extrusion welded as per project specs. Noted as Repair RP-261 on Repair Log.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/9/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 75/86° F, Clear AM, Clouds & Rain PM |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1830 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #22**
**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Brian Shea
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #75 (P-75) installed on 8/14/15 (located at approximate Sta. 10+20 – western slope of utility corridor) running approximately 70 ft. east through 2nd utility corridor to approximate Sta. 9+50 (eastern slope of 2nd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 10+20 to Sta. 9+50. Refer to *Soil Subgrade Approval* forms from 9/9/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 10+20 to Sta. 9+50.
- While subgrade approval was being conducted, ESI completed patch / repair work for cap wrinkles that were observed from panel placement on 8/14/15. A total of thirty repairs (RP-263 through RP-292) were observed and fixed (according to the project specifications) from Panel #71 and Panel #73 (repair / detailing work conducted on panels installed on 8/14/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), where wrinkles were observed. These areas were subsequently patched and sealed with extrusion welds. No vacuum box testing was conducted on these repairs, and will be completed tomorrow (9/10).
- No non-conformance issues were recorded as patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GCL and Cap placement began with ESI placing the GCL along the eastern and western slopes of the utility corridor and southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #75 (located at approximate Sta. 10+20) on 8/14/15 and through the 2nd utility corridor. Panels were oriented from east to west (as proposed in the approved Panel Layout) and were placed on top of the GCL layer. A total of eleven panel lengths (panel lengths identified as the approximate 80 ft. run from east to west across the corridor, as well as geomembrane pieces which were used to complete the southern end of the corridor) were installed (P-76, P-77, P-78, P-79, P-80, P-81, P-82, P-83, P-84, P-85, and P-86) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/9), *Trial Weld Log.*
- No non-destructive testing or patch / repair work was conducted upon completion of geomembrane panel placement to approximate Sta. 9+50, as panel placement and fusion welded activities concluded the work day.
- One destructive sample was collected – DSX-8 (extrusion weld). Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact completed Site preparation activities for expectation of rainstorms tomorrow (9/10).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/9/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DSX-8 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, and 8/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/9/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 9/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/9/15 |
| A5 – Subgrade Approval | Sheet 15 & ESI (9/9/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/9/15. |
| A7 – Panel Placement Log | Pages 16-17 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 9/9/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 9/9/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no vacuum box testing conducted on 9/9/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Pages 13-14 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/9/15 |
| A11 – Conformance COC | | N / A for 9/9/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 9/9/15 |
| A13 – Destruct. Sample Summary | Page 3 | Updated with 9/9/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/9/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north / northwest along edge of GDL placed up to Panel #56 (approximate Sta. 14+20)

**Description:**

Protective cover soil placed from west end of SA-6 to approximate Sta. 14+20. Yellow caution tape spaced at maximum 55-inch intervals as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking southwest along 2nd utility corridor (located at approximate Sta. 10+00).

**Description:**

Prepared soil subgrade through 2nd utility corridor (approximate Sta. 10+00). Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north / northeast along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

Prepared soil subgrade through 2nd utility corridor. Soil graded, compacted, and free of debris as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along SA-6

**Description:**

ESI conducting patch / repair work along Panels 73/74. Wrinkles cut and geomembrane patched and repaired with extrusion weld as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approx. Sta. 10+00)

**Description:**

ESi deploying GCL along 2nd utility corridor. GCL placed north to south (along bottom of corridor) and east to west (along slopes of corridor).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along 2nd utility corridor

**Description:**

ESi placing granular bentonite along GCL seams (overlapped a minimum of 1 ft.) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/9/15

**Direction Taken:**

Looking east along southern end of SA-6 cap through 2nd utility corridor

**Description:**

GCL panels (oriented east to west) placed along eastern slope and southern end of utility corridor. Overlapped a minimum of 1 ft. (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/9/15

**Direction Taken:**

Looking east along northern end of SA-6 cap

**Description:**

ESI completing GCL placement along eastern slope of 2nd utility corridor (approximate Sta. 10+00)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

GCL deployed along 2nd utility corridor, as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor

**Description:**

ESI placing geomembrane cap over GCL. Panels oriented from east to west through utility corridor as outlined in the approved panel layout.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along southern end of SA-6 (through 2nd utility corridor)

**Description:**

ESi placing geomembrane cap over GCL along southern end of corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

ESI conducting fusion welding along Panel Seams 81/84



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

Geomembrane cap placed through 2nd utility corridor and seams fusion welded according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/11/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/77° F, Clear AM, Clouds & Rain PM |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #23**<br>**AmecFW**: Dave Ambrose<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from geomembrane Panel #56 (located at approximate Sta. 14+20 – location where GDL had previously been placed to along with protective cover soil) running approximately 220 ft. east to Panel #68 (approximate Sta. 12+00)..
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing for the repairs completed on 9/11/15 (as outlined in projecte specs). One vacuum box testing was complete, ESI began placing GDL from approximate Sta. 14+20 (Panel #56) to approximate Sta. 12+00 (Panel #68). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL were cut with the first wrap of geocomposite removed prior to use
    - Roll 64021010124 – 10 ft. removed
    - Roll 64021010133 – 8 ft. removed
    - Roll 64021010126 – 10 ft. removed
    - Roll 64021010116- 5 ft. removed
    - Roll 64021010112 – 10 ft. removed
        - Note: this roll was not identified during the GDL inspection, however based on damage to the protective plastic liner observed in the field, the outside layer of GDL was removed.
    - Roll 64021010119 – 10 ft. removed
- Due to the inclement weather from 9/10/15 and potential storms over the weekend, the protective plastic covering the soil subgrade to the east was not removed. As such, no soil subgrade approval was conducted and no additional geomembrane panels were placed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- One non-conformance issues was observed during placement of GDL. A rock was encountered underneath geomembrane panel #57. This non-conformance issue was recorded as RP-293 and will be patched and repaired on Monday (9/14).
- Upon completion of GDL placement to the approved panel location, a visual observation of the top of the western slope of the 2nd utility corridor was conducted by Langan and Entact. The geomembrane panels were pulled back to expose the GCL. Visual observation confirmed that the GCL was dry and no water had drained underneath the panels. The top of the slope was then sealed with a fusion weld "T-seams" along Panel #75 (oriented north to south) and Panel #76 through Panel #81 (oriented east to west).
- Geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/11), *Trial Weld Log.* Note: non-destructive testing was completed on the welded seams (to be completed Monday – 9/14/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 6 (Sheet #6) – Subgrade irregularity identified as RP-293 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #57). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 6 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/11/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 4 gas vents).
- Review laboratory results for DSX-8 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, and 8/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/11/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/11/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/11/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/11/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/11/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/11/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 9/11/15 |
| A10 – Repair Log | Pages 13-14 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/9/15 |
| A11 – Conformance COC | | N / A for 9/11/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/11/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/11/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet #6 | One non-compliance issue identified on 9/11/15 and recorded on Sheet #6 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI conducting vacuum box testing for extrusion welds for cap repairs (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 14+00)

**Description:**

ESI deploying GDL along SA-6 cap. GDL secured with white plastic fasteners (spaced at 5 ft. maximum intervals) and sewn along the top layer of geotextile (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 13+80).

**Description:**

ESI securing GDL with white plastic fasteners spaced at maximum of 5 ft. intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking west along SA-6

**Description:**

GDL placed to approximate Sta. 12+00



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI placed patch over subgrade irregularity (RP-293). Details of patch are outlined in non-conformance Sheet #6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking east along SA-6 cap (top western slope of 2nd utility corridor).

**Description:**

ESi conducting fusion welding between Panels 75 / 80 (top western slope of 2nd utility corridor) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/11/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/11/15

**Direction Taken:**

Looking north along SA-6 cap (at GV-

**Description:**

ESI constructing geomembrane boot around gas vent: GV-4 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/11/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/11/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta.

**Description:**

ESI completing geomembrane boot around GV-4.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/14/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 58/74° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #24**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from geomembrane Panel #68 (located at approximate Sta. 12+00 – location where GDL had previously been placed to - based on approved as-built drawings) running approximately 170 ft. east to Panel #74 located at top of western slope of 2nd utility corridor (approximate Sta. 10+30).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL from approximate Sta. 12+00 (Panel #68) to approximate Sta. 10+30 (Panel #75). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.
- While GDL was being placed, ESI conducted non-destructive testing (air pressure testing) of the geomembrane panel seams installed on 9/9/15 in accordance with the project specifications. Refer to *Seam Control Form* (9/14/15) for non-destructive testing details.
- Once non-destructive testing was completed, ESI completed patch / repair along the panels previously installed, Panels 76-86 which were placed on 9/9/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/14/15).
- A total of twenty-three repairs (RP-293 through RP-315) were observed and fixed (according to the project specifications) from Panels #76 through Panel #86 (repair / detailing work conducted on panels installed on 9/11/15). Refer to 9/14/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for gas vent GV-3, and completed placing the geomembrane patch around Access Manhole #3. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.
- One destructive sample (DS-22) was collected (fusion) from Panel Seams 79/80. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/14/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-22 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, and 9/11/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/14/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 9/14/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/14/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/11/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/14/15 |
| A8 – Destruct Seam Testing COC | | Updated with destruct sample information collected on 9/14/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 16-18 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/14/15 |
| A10 – Repair Log | Pages 14-16 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/14/15 |
| A11 – Conformance COC | | N / A for 9/14/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/14/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/14/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/14/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 11+80)

**Description:**

ESI sewing seams of GDL as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/14/15

**Direction Taken:**

Looking east along SA-6 cap (through 2nd utility corridor)

**Description:**

ESI conducting non-destructive testing as outlined in project specs. Pressure testing conducted between Panel Seams 76 / 77.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 11+20).

**Description:**

ESI securing GDL with white plastic fasteners spaced at maximum of 5 ft. intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap (approximate Sta. 10+40).

**Description:**

ESI constructing geomembrane boot around gas vent GV-3.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap (western slope of 2nd utility corridor).

**Description:**

ESI completed patch / repair over seam joint for non-destruct testing. Patch overlapped, sealed, and extrusion welded as outlined in project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/14/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Entact spreading protective cover soil over placed GDL. Warning caution tape spaced at maximum 55-inch intervals, as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Seam joint patches placed over non-destruct test seams and patched and repaired according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking southeast along SA-6 cap (at approximate Sta. 10+20).

**Description:**

ESI installing geomembrane boot around Access Manhole #3 located along western slope of 2nd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

Completed geomembrane boot with extrusion welds and vacuum box testing completed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/15/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #25**<br>**AmecFW**: Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), and continuing from eastern end of 2nd utility corridor. Material to be placed from Panels #76, 77, 78, 79, 80, 81, and 86 (panels running east to west through utility corridor) installed on 9/9/15 (located at approximate Sta. 9+50) running approximately 100 ft. east to Sta. 8+50. Panels installed today (9/15) will "T" into the panels outlined above as panels will revert back to north-south orientation outside of utility corridor (as per the approved panel layout).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 9+50 (eastern end of 2nd utility corridor) to Sta. 8+50. Refer to *Soil Subgrade Approval* forms from 9/15/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 9/15/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 9+50 to Sta. 8+50.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 9+50 (east of 2nd utility corridor) moving east (for approximately 100 ft.) to approximate Sta. 8+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/15/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panels #76-81, and #86 (running east-west through 2nd utility corridor) on 9/9/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-87, P-88, P-89, and P-90) by ESI.

- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/15), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 8+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/15/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/16/15.
- One destructive sample (DS-23) was collected (fusion) from Panel Seams 88/89. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- ESI pulled back the installed geomembrane panels along the northern and southern ends of the 2nd utility corridor to expose the underlying GCL. The GCL appeared to be hydrated (approximate 10 ft. wide section along southern end of corridor and approximate 4 ft. wide section along northern end of corridor) from rainwater infiltration that washed back underneath the cap due to the soil subgrade outside of the cap which was not yet completed to grade. These sections of GCL were cut and removed and the area was left open to dry overnight. New GCL pieces will be placed (according to the project specs) on 9/16/15.
- With cap activities complete, ESI filled sandbags for the remainder of the work day.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/15/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-23 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, and 9/14/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-22, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/15/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 9/15/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/15/15 |
| A5 – Subgrade Approval | Sheet 16 & ESI (9/15/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/15/15. |
| A7 – Panel Placement Log | Page 18 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/15/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/15/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 19-20 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/15/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | N / A no repairs completed for 9/15/15 |
| A11 – Conformance COC | | N / A for 9/15/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/15/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/15/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/15/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/15/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 9+50)

**Description:**

Soil subgrade approved for GVL and geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/15/15

**Direction Taken:**

Looking east along northern end of SA-6 cap (from approximate Sta. 9+50)

**Description:**

Soil subgrade prepared for GVL and geomembrane placement as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (from approximate Sta. 9+50 to Sta. 8+50)

**Description:**

ESI placing GCL along lower bench of southern slope of SA-6 cap (areas below to 1 ft. above the water table) as outlined in the project specs. GCL overlapped a minimum of 1 ft. and sealed with bentonite along the seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking north along southern slope of SA-6

**Description:**

Stakes / staples placed along top 6-inches of GCL to secure material.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking north along SA-6 cap (eastern top of 2nd utility corridor)

**Description:**

ESI deploying GVL as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking north along SA-6 cap

**Description:**

GVL placed from approximate Sta. 9+50 to approximate Sta. 8+50.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/15/15

**Direction Taken:**

Looking southwest along SA-6 cap (at approximate Sta. 9+20).

**Description:**

ESI conducting fusion welding along geomembrane seams (P-87 & P-88) as per project specifications



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/15/15

**Direction Taken:**

Looking east along southern slope of SA-6

**Description:**

Geomembrane panels pulled back to remove approximate 10’ wide piece of GCL along southern end of 2nd utility corridor. GCL removed was wet / hydrated from rainwater during storms. GCL cut and removed – to be replaced and sealed on 9/16/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 8+50).

**Description:**

GVL and geomembrane panels placed to approximate Sta. 8+50. Panels welded with non-destructive testing conducted (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/16/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 63/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #26**
**AmecFW**: Geoff Shallard, Dave Ambrose, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## *Site Activities*

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), and continuing from eastern end of 2nd utility corridor. Material to be placed from Panel #90 (P-90) installed on 9/15/15 and located at approximate Sta. 8+50 running approximately 80 ft. east to Sta. 7+70.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing on the repairs completed from 9/14/15 (through 2nd utility corridor). ESI also conducted patch / repair work for the panels installed on 9/15/15 (Panels 87-90). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 9/16/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-four repairs (RP-316 through RP-349) were observed and fixed (according to the project specifications) from Panel #87 through Panel #90 (repair / detailing work conducted on panels installed on 9/15/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Along with the repair work, ESI also placed the new pieces of GCL (refer to Photo Log) for the northern and southern areas along the 2nd utility corridor where the GCL was hydrated. One area along the southern section required the liner to be cut to pull back and expose the GCL. As such, this repair (RP-331) was identified as a non-conformance issue (subgrade irregularity) and is further defined below.
- While patch / repair work was being completed, Langan and Entact conducting soil subgrade approval from approximate Sta. 8+50 (moving east from P-90) to Sta. 7+70. Refer to *Soil Subgrade Approval* forms from 9/16/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photo #6 of the daily photo log for 9/16/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 8+50 to Sta. 7+70.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 8+50 (moving east of P-90) moving east (for approximately 80 ft.) to approximate Sta. 7+70. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/16/15 Photo Log* for supporting photographs.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, the following rolls of GVL were cut with the first wrap of geocomposite removed prior to use
    - Roll 65211010130 – 8 ft. removed
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #90 on 9/15/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-91, P-92, P-93, and P-94) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/16), *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 7+70, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/16/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/17/15.
- One destructive sample (DSX-9) was collected (extrusion weld) from Panel Seams 88/89. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 7 (Sheet #7) – Subgrade irregularity identified as RP-293 on *Repair Log*
    - GCL underneath geomembrane liner along southern end of utility corridor hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final). Geomembrane liner pulled back and cut to remove and replace sections of GCL. This patch was noted as a subgrade irregularity and was patched/repaired following project specs and is further defined on *Sheet 7 Notice of Non-Compliance*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/16/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DSX-9 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, and 9/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-23, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/16/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/16/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/16/15 |
| A5 – Subgrade Approval | Sheet 17 & ESI (9/16/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A6 – Trial Weld Log | Pages 4-5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/16/15. |
| A7 – Panel Placement Log | Page 19 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/16/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/16/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 20-21 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/16/15 |
| A10 – Repair Log | Pages 15-17 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/16/15 |
| A11 – Conformance COC | | N / A for 9/16/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/16/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/16/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 7 | One non-compliance issues identified and further defined on Sheet 7 for 9/16/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking south along western slope of 2nd utility corridor

**Description:**

ESI conducting vacuum box testing (as per project specs) for geomembrane boot around Access Manhole #3 (RP-262).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (southern section of 2nd utility corridor)

**Description:**

ESI placing new panels of GCL for hydrated areas that were previously removed on 9/15/15. New pieces overlapped a minimum of 1 ft. and sealed with granular bentonite along the seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking along southern end of SA-6 cap (along GCL)

**Description:**

ESI spreading granular bentonite along GCL seams (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking south along SA-6 cap (top southwest corner of 2nd utility corridor)

**Description:**

Vacuum box testing being conducted on RP-299 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking east along northern end of SA-6 cap (northern end of 2nd utility corridor)

**Description:**

New panel of GCL placed along SCB wall (northeast corner of 2nd utility corridor). GCL removed as area was hydrated from previous storms.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (southern end of 2nd utility corridor)

**Description:**

Geomembrane panels patched and repaired after exposing and replacing pieces of GCL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/16/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/16/15

**Direction Taken:**

Looking north / northeast along SA-6 Cap (from approximate Sta. 8+50).

**Description:**

ESI deploying GVL. Approved soil subgrade to the east. Soil compacted, graded, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/16/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/16/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 8+50).

**Description:**

ESi conducting sewing along the top layer of GVL as outlined in the project specs. White plastic fasteners spaced at a maximum of 5 ft. along the geonet also placed prior to sewing.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 8+10).

**Description:**

White plastic fasteners spaced at a maximum of 5 ft. along GVL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 8+20)

**Description:**

ESI deploying geomembrane panels over placed GVL (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking along SA-6 cap (Panels 90/91)

**Description:**

ESI conducting fusion welding along Panel Seams 90 / 91 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking along southern end of SA-6 cap

**Description:**

ESI conducting non-destructive testing (pressure testing) along Panel Seam 90 / 91 as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/17/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 65/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #27**<br>**AmecFW**: Stu, Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), continuing from eastern end of 2nd utility corridor. Material to be placed from Panel #94 (P-94) installed on 9/16/15 and located at approximate Sta. 7+70 running approximately 70 ft. east to Sta. 7+00 (top western slope of 3rd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work for the panels installed on 9/16/15 (Panels 91-94). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 9/17/15 for results (extrusion testing identified as EXT. on form).
- A total of seventeen repairs (RP-350 through RP-366) were observed and fixed (according to the project specifications) from Panel #91 through Panel #94 (repair / detailing work conducted on panels installed on 9/16/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications. Additionally, custom fit repairs were conducted along the top eastern slope of the 2nd utility corridor (Panel #80) to remove observed wrinkles in the geomembrane panels. Vacuum box testing was then completed on the repairs (as per the project specifications) to confirm the integrity of the extrusion welds.
- Once the patch / repair work was completed ESI began placing GDL from approximate Sta. 10+30 (Panel #75) to approximate Sta. 9+60 (Panel #87). GDL was placed through the 2nd utility corridor with the panels oriented east to west, and was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While GDL placement was being conducted, Langan and Entact completed soil subgrade approval from approximate Sta. 7+70 (moving east from P-94) to Sta. 7+00 (top western slope of 3rd utility corridor). Refer to *Soil Subgrade Approval* forms from 9/17/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 7+70 to Sta. 7+00.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 7+70 (moving east of P-94) moving east (for approximately 70 ft.) to approximate Sta. 7+00. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/17/15 Photo Log* for supporting photographs.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove first wrap of geocomposite prior to use
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #94 on 9/16/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of three panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-95, P-96, and P-97) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/17), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 7+00, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/17/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/18/15.
- One destructive sample (DS-24) was collected (fusion weld) from Panel Seams 91/92. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/17/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-24 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, and 9/16/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-23, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 through, and east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/17/15 |
| A3 – Photo Log | Pages 1 – 3 | Total of 6 photos outlining pertinent daily observations and descriptions for 9/17/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/17/15 |
| A5 – Subgrade Approval | Sheet 18 & ESI (9/17/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/17/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A7 – Panel Placement Log | Page 20 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/17/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/17/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 21 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/17/15 |
| A10 – Repair Log | Pages 15-18 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/16/15 and 9/17/15 |
| A11 – Conformance COC | | N / A for 9/17/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/17/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/17/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/17/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/17/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/17/15

**Direction Taken:**

Looking west along SA-6 cap (at destruct sample location DS-24)

**Description:**

ESI completing patch / repair work for destruct sample DS-24 collected along Panel 91 / 92 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/17/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/17/15

**Direction Taken:**

Looking north along SA-6 through 2nd utility corridor (approximate Sta. 10+00)

**Description:**

ESI placing GDL along 2nd utility corridor over placed geomembrane panels. One panel ran north-south through bottom of utility corridor. Remaining panels oriented east-west along slopes of corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/17/15

**Direction Taken:**

Looking south along SA-6 (through 2nd utility corridor)

**Description:**

ESI placing GDL panels along western slope of 2nd utility corridor. Panels oriented east to west and secured with white plastic fasteners and sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/17/15

**Direction Taken:**

Looking south along SA-6 cap (approximate Sta. 7+50).

**Description:**

ESI deploying GVL with white plastic fasteners spaced at maximum of 5 ft. and top layer of geotextile sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/17/15

**Direction Taken:**

Looking north along SA-6 cap (approximate Sta. 7+40).

**Description:**

ESI deploying geomembrane panels over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/17/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

Geomembrane panels placed and fusion welded (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/18/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #28**
**AmecFW**: Stu, Bills, Geoff Shallard, Dave Ambrose, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL) geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), through 3rd utility corridor (located at approximate Sta. 6+80). Material to be placed from Panel #97 (P-97) installed on 9/17/15 and located at approximate Sta. 7+00 running approximately 60 ft. east through 3rd utility corridor to Sta. 6+40 (top eastern side of 3rd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 7+00 (P-97 installed on 9/17/15) through the 3rd utility corridor to Sta. 6+40. Refer to *Soil Subgrade Approval* forms from 9/18/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 7+00 to Sta. 6+40.
- GCL and Cap placement began with ESI placing GVL along the eastern and western slopes of the 3rd utility corridor. GVL was placed at the areas above the groundwater table down the slopes of the corridor (GCL areas comprised the bottom of the utility corridor to approximately 2 ft. to 3 ft. up the side slopes). GVL was secured with white plastic fasteners spaced at a maximum of 5 ft. and was sewn along the top layer of geotextile (as outlined in the project specs).
- GCL was then placed along the bottom of the 3rd utility corridor, and along the eastern and western slopes of the utility corridor and southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite. The GVL overlapped the GCL a minimum of 1 ft. along the bottom slopes of the corridor, and the GCL was secured into the side slopes via soil stakes / staples.
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #97 (located at approximate Sta. 7+-00) on 9/17/15 and through the 3rd utility corridor. Panels

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

were oriented from east to west (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers.

- A total of nine panel lengths (panel lengths identified as the approximate 68 ft. run from east to west across the corridor, as well as geomembrane pieces which were used to complete the southern end of the corridor) were installed (P-98, P-99, P-100, P-101, P-102, P-103, P-104, P-105, and P-106) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/18), *Trial Weld Log.*
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- Upon completion of geomembrane panel placement to approximate Sta. 6+40, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/18/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/21/15.
- Two destructive samples (DS-25 and DS-26) were collected (fusion welds) from Panel Seams 94/95 and 97/97, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/18/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2$^{nd}$ utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 6 gas vents).
- Review laboratory results for DS-25 and DS-26 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, and 9/17/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-24, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 through, and east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/18/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/18/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/18/15 |
| A5 – Subgrade Approval | Sheet 19 & ESI (9/18/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/18/15. |
| A7 – Panel Placement Log | Page 21 & 22 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/18/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/18/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 22-24 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/18/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | N / A repairs patched and leistered, however, no welding or vacuum box testing completed |
| A11 – Conformance COC | | N / A for 9/18/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/18/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/18/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/18/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south through 3rd utility corridor (located at approximate Sta. 6+80).

**Description:**

Soil subgrade graded, compacted, and free of debris (>1/2") as outlined in the project specs. Subgrade approved through 3rd utility corridor (approximate Sta. 7+00 to Sta. 6+40).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/18/15

**Direction Taken:**

Looking north through 3rd utility corridor

**Description:**

Soil subgrade approved for panel placement through 3rd utility corridor. Subgrade prepared according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south along 3rd utility corridor (western slope).

**Description:**

ESI placing GVL along eastern and western slopes of 3rd utility corridor. GVL placed to approximate 2 ft. to 3 ft. from bottom of corridor (GCL proposed along bottom of corridor and up bottom slopes). GVL to overlap GCL a minimum of 1 ft. (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south through 3rd utility corridor

**Description:**

GVL deployed along western slope of 3rd utility (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking north through 3rd utility corridor

**Description:**

GVL placed along eastern and western slopes of 3rd utility corridor (placed according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south from within 3rd utility corridor

**Description:**

ESI placing GCL along bottom of 3rd utility corridor. GCL placed according to project specs (at areas below to 1 ft. above the water table). GVL overlapped a minimum of 1 ft. over GCL, and GCL anchored into slope with soil stakes / staples.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south through 3rd utility corridor

**Description:**

GCL and GVL placed along bottom and slopes of 3rd utility corridor (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/18/15

**Direction Taken:**

Looking north / northeast at northern end of 3rd utility corridor

**Description:**

ESi deploying geomembrane panels over GVL and GCL as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

ESI conducting fusion welding along panel seams 97 /100 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking north along top western slope of 3rd utility corridor

**Description:**

Geomembrane panels placed and welded (according to project specs). Panels oriented from east to west running through 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/18/15

**Direction Taken:**

Looking along SA-6 cap (Panels 1000/101)

**Description:**

ESI conducting non-destructive testing (air pressure tests) for Panel Seams 100 / 101 as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking north along 3rd utility corridor

**Description:**

Geomembrane panels placed and welded (according to project specs) through 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/21/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 66/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1500 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #29**
**AmecFW**: Dave Ambrose, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing through 2nd utility corridor (located at approximate Sta. 10+00).. Material to be placed from eastern slope of 2nd utility corridor (Panels 76-81; running east to west) located at approximate Sta. 10+30) running approximately 250 ft. east to Panel #93 (located at approximate Sta. 7+80).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL from approximate Sta. 10+30 (eastern slope of 2nd utility corridor) to approximate Sta. 7+80 (Panel #93). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.
- Once GDL was completed to the (based on the approved as-builts) , ESI completed patch / repair along the panels previously installed, Panels 95-106 which were placed on 9/17/15 and 9/18/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/21/15).
- A total of thirty-two repairs (RP-367 through RP-398) were observed and fixed (according to the project specifications) from Panels #95 through Panel #106 (repair / detailing work conducted on panels installed on 9/17/15 and 9/18/15). Refer to 9/21/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for gas vent GV-2. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- One destructive sample (DSX-10) was collected (extrusion) from RP-376. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/21/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 6 gas vents).
- Review laboratory data for destruct sample DSX-10 (extrusion) once received

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, and 9/18/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/21/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/21/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/21/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed for 9/21/15. |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/21/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/21/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/21/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 9/21/15 |
| A10 – Repair Log | Pages 18-19 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/21/15 |
| A11 – Conformance COC | | N / A for 9/21/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/21/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/21/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/21/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/21/15

**Direction Taken:**

Looking north / northeast along 2nd utility corridor (located at approximate Sta. 10+00).

**Description:**

ESI deploying GDL along eastern slope, northern end of 2nd utility corridor. GDL placed according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/21/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 9+00).

**Description:**

GDL deployed moving east from 2nd utility corridor. GDL secured with white plastic fasteners spaced at a maximum of 5 ft. intervals, and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at gas vent GV-2)

**Description:**

ESI constructing geomembrane boot around gas vent GV-2



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/21/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at RP-370).

**Description:**

ESI conducting patch / repair work and extrusion welds (according to project specs) for repairs from 9/17/15 and 9/18/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at GV-2)

**Description:**

ESI completing geomembrane boot around gas vent GV-2. Geomembrane skirt to be placed over penetration and extrusion welded with 18-inches of overlap (as outlined in project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at RP-367)

**Description:**

ESI conducting vacuum box testing on extrusion weld repairs (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at GV-2)

**Description:**

Final boot, skirt, and welds completed for GV-2 as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at DSX-10)

**Description:**

Patch / repair work completed for destruct sample DSX-10 (extrusion weld) collected from RP-376.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/22/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #30**
**AmecFW**: Stu Bills, Dave Ambrose, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), continuing past eastern side of 3rd utility corridor. Material to be placed from Panels #98, 99, 100, 101, 102, 103, and 106 (panels running east to west through 3rd utility corridor) installed on 9/18/15 (located at approximate Sta. 6+40) running approximately 110 ft. east to Sta. 5+30. Panels installed today (9/22) will "T" into the panels outlined above as panels will revert back to north-south orientation outside of utility corridor (as per the approved panel layout).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 6+40 (eastern end of 3rd utility corridor) to Sta. 5+30. Refer to *Soil Subgrade Approval* forms from 9/22/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 and #3 of the daily photo log for 9/22/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 6+40 to Sta. 5+30.
- While subgrade inspection was being conducted, ESI conducted vacuum box testing for the repairs completed on 9/21/15, and also installed the remaining panels of GDL from geomembrane Panel #93 to Panel #96.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, one roll of GDL was required to be cut to remove the first wrap of geocomposite prior to use – Roll #64021010086 (8 ft. cut).
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 6+40 (east of 3rd utility corridor) moving east (for approximately 110 ft.) to approximate Sta. 5+30. GVL was placed according to

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/22/15 Photo Log* for supporting photographs.

- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, one roll of GVL was required to be cut to remove the first wrap of geocomposite prior to use – Roll #65211010113 (8 ft. cut)
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panels #98-103, and #106 (running east-west through 3rd utility corridor) on 9/18/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-107, P-108, P-109, and P-110) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/22), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 5+30, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/22/15) for non-destructive testing details.
- Once non-destructive testing was completed, ESI conducted patch / repair along the panels installed, Panels 107-110. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/22/15).
- A total of nineteen repairs (RP-399 through RP-417) were observed and fixed (according to the project specifications) from Panels #107 through Panel #110 (repair / detailing work conducted on panels installed on 9/22/15). Refer to 9/22/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for piezometer PZ-14. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.
- No destructive samples were collected, as an RFI was submitted to AmecFW, and based on the results of the first 26 destruct samples – the sampling frequency was decreased from 500 LF to 1500 LF as samples yielded zero failures with all 26 exhibited shear and peel results greater than the minimum requirements (as per the project specs).
- During cap placement activities, Entact spread protective cover soil for the area immediately west of the 2nd utility corridor (approximate Sta. 10+20). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/15/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 4 piezometers, and 5 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, and 9/21/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/22/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/22/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/22/15 |
| A5 – Subgrade Approval | Sheet 20 & ESI (9/22/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/22/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A7 – Panel Placement Log | Page 23 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/22/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/22/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 24-25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/22/15 |
| A10 – Repair Log | Pages 19-20 | One repair log provided by ESI and confirmed by Langan for repairs completed for 9/22/15 |
| A11 – Conformance COC | | N / A for 9/22/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/22/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/22/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/22/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking east past 3rd utility corridor (past Sta. 6+40).

**Description:**

Soil subgrade approved for the area east of the 3rd utility corridor. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 6+40)

**Description:**

Soil subgrade approved for geomembrane placement (looking north along end of geomembrane previously installed on 9/18). Subgrade prepared according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking south along subgrade (east of 3rd utility corridor) at approximate Sta. 5+90

**Description:**

Soil subgrade prepared for geomembrane placement according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/22/15

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

ESI placing 16 oz. geotextile along southern boundary of SA-6 (sheet pile wall). Geotextile overlapped 2 ft. to the outside with remaining roll width inside as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 6+20)

**Description:**

ESI deploying GVL panels along approved soil subgrade. GVL secured with white plastic fasteners spaced at maximum 5 ft. intervals with top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 6+00)

**Description:**

GVL panels placed along soil subgrade. White plastic fasteners spaced at maximum 5 ft. intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/22/15

**Direction Taken:**

Looking south / southeast along SA-6 cap (at approximate Sta. 5+80)

**Description:**

ESI deploying geomembrane panels over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/22/15

**Direction Taken:**

Looking down along SA-6 cap (top eastern slope of 3rd utility corridor)

**Description:**

ESI conducting fusion welding between Panel Seams 101 / 107 as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along Panel #107 (east of 3rd utility corridor)

**Description:**

Panel #107 (running north to south) past top of eastern slope of 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking down at SA-6 cap (top eastern slope of 3rd utility corridor)

**Description:**

Non-destructive testing at Seam Joint 102/103/107. Testing conducted according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/22/15

**Direction Taken:**

Looking along SA-6 cap (at piezometer PZ-14)

**Description:**

ESI placing geomembrane boot around piezometer PZ-14 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/22/15

**Direction Taken:**

Looking west at northern end of 2nd utility corridor

**Description:**

ESI conducting patch / repair work (custom fit repair) along northern end of 2nd utility corridor (RP-412).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/23/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 58/79° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1700 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #31**<br>**AmecFW**: Stu Bills, Dave Ambrose, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing past eastern side of 3rd utility corridor. Material to be placed from Panels #110 installed on 9/22/15 (located at approximate Sta. 5+30) running approximately 80 ft. east to Sta. 4+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #96/97 (approximate Sta. 7+00) through 3rd utility corridor to approximate Sta. 5+30 (Panel #110 placed on 9/22/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL was required to be cut to remove the first wrap of geocomposite prior to use:
    - Roll #64021010103 - 5 ft. cut and removed
    - Roll #64021010105 – 8 ft. cut and removed
- Langan and Entact conducting soil subgrade approval from east of Panel #110 (located at approximate Sta. 5+30) to approximate Sta. 4+50. Refer to *Soil Subgrade Approval* forms from 9/23/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 9/23/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 5+30 to Sta. 4+50.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 5+30 (east of 3rd utility

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

corridor) moving east (for approximately 80 ft.) to approximate Sta. 4+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/23/15 Photo Log* for supporting photographs.

- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- In addition to the GVL, GCL was placed along the northern and southern edges of SA-6 at areas below (to 1 ft. above) the groundwater table (as shown on the drawings and outlined in the project specs). GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- After installation of the GVL and GCL, geomembrane cap was installed continuing east of previously installed Panel #110 on 9/22/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-111, P-112, P-113, and P-114) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, a trial weld (smooth to smooth) was conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/23), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 4+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/23/15) for non-destructive testing details.
- One patch / repair (RP-418) was completed as a pipe boot for well 115-E1A-SO located at Panel #109. The boot was constructed according to the project specs (final butyl seal still to be applied). No destruct samples were collected from 9/23/15.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and no patch / repair work was conducted.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, and 9/22/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/23/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/23/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/23/15 |
| A5 – Subgrade Approval | Sheet 21 & ESI (9/23/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 5-6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/23/15. |
| A7 – Panel Placement Log | Page 24 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/23/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/23/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/23/15 |
| A10 – Repair Log | Page 20 | One repair log provided by ESI and confirmed by Langan for repairs completed for 9/23/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A11 – Conformance COC | | N / A for 9/23/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/23/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/23/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/23/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 4+90)

**Description:**

Soil subgrade approved for the area east of Panel #110 (P-110) installed on 9/22/15. Subgrade graded, compacted, and free of debris (>1/2").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking west / northwest along SA-6 cap (looking toward place panels from 9/22/15)

**Description:**

Soil subgrade approved for geomembrane placement from approximate Sta. 5+30 to approximate Sta. 4+50.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/23/15

**Direction Taken:**

Looking south along 3rd utility corridor (approximate Sta. 6+80)

**Description:**

ESI deploying GDL panels (oriented from east to west) through 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking north along 3rd utility corridor (approximate Sta. 6+80)

**Description:**

ESI placing GDL panels (oriented from east to west) moving north along 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

ESI placing 16 oz. geotextile along southern boundary of SA-6. GCL also placed at marked areas below (to 1 ft. above the groundwater table) as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 5+00)

**Description:**

GVL panels placed along soil subgrade. White plastic fasteners spaced at maximum 5 ft. intervals as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 5+10)

**Description:**

ESI deploying geomembrane panels over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking down along SA-6 cap (Panels 110 / 111 seam)

**Description:**

ESI conducting fusion welding between Panel Seams 110 / 111 as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/24/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 59/80° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #32** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), and 60-mil geomembrane liner (Cap), continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #114 installed on 9/23/15 (located at approximate Sta. 4+50) running approximately 70 ft. east to Sta. 3+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair along the panels previously installed, Panels 111-114 which were placed on 9/23/15. Prior to repair work, a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/24/15).
- A total of seven repairs (RP-419 through RP-424) were observed and fixed (according to the project specifications) from Panels #111 through Panel #114 (repair / detailing work conducted on panels installed on 9/23/15). Refer to 9/24/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-compliance issue was observed and was noted on *Sheet #8 Notice of Non-Compliance and Corrective Action Form.* This non-compliance was also noted on the Repair Log as a subgrade irregularity and was identified as RP-423. This non-compliance issue was identified based on a rock that was observed underneath the geomembrane cap. The rock was removed from underneath the liner and the hole was patched / repaired according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – *Sheet #8* for 9/24/15.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for well 115-E1A-SO and Access Manhole #4. Note: The penetration logs for all boots to date will be completed once the boots have been sealed with butyl sealant (not yet completed).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was completing patch / repair work, Langan and Entact conducted soil subgrade approval from east of Panel #114 (located at approximate Sta. 4+50) to approximate Sta. 3+80. Refer to *Soil Subgrade Approval* forms from 9/24/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3 and #4 of the daily photo log for 9/24/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 4+50 to Sta. 3+80.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the areas within the SA-6 cap along the bottom and side slopes of the drainage/utility ditches located from approximate Sta. 4+50 to Sta. 3+80. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- After the GCL was placed, GVL was installed from approximate Sta. 4+50 (Panel #114) moving east (for approximately 70 ft.) to approximate Sta. 3+80. GVL was placed along the areas outside of the water GCL (outside of the water table influence) and according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/24/15 Photo Log* for supporting photographs. Note: The GVL was cut along the drainage / utility to expose the GCL as a minimum of 1 ft. of overlap was required along the ditches where the GVL and GCL intersected.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- After installation of the GVL and GCL, geomembrane cap was installed continuing east of previously installed Panel #114 on 9/23/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-115, P-116, P-117, and P-118) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, two trial welds (smooth to smooth and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/24), *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 4+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/24/15) for non-destructive testing details.
- No patch / repair work was conducted on Panels #115 through #118 as part of the activities on 9/24/15.
- Two destructive samples were collected for laboratory testing. DS-27 (fusion) was collected from Panel Seam 110/111 and is noted as RP-422 on the *Repair Log*. Fusion weld destruct samples collected at 1500 LF intervals (as per the approved RFI to reduce the sampling frequency from 500 LF to 1500 LF). One extrusion weld sample (DSX-11) was also collected from RP-421 and is noted as RP-424 on the *Repair Log*. Extrusion weld samples collected at 500 LF intervals as per the project specs.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 8 (Sheet #8) – Subgrade irregularity identified as RP-423 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #111). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 8 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/24/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory destruct data for destruct samples DS-27 and DSX-11.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, and 9/23/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/24/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 9/24/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/24/15 |
| A5 – Subgrade Approval | Sheet 22 & ESI (9/24/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/24/15. |
| A7 – Panel Placement Log | Page 25 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/24/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information from 9/24/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25-26 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/24/15 |
| A10 – Repair Log | Pages 20-21 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/24/15 |
| A11 – Conformance COC | | N / A for 9/24/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct sample information from 9/24/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | One destruct sample summary form provided by ESI and confirmed by Langan for 9/24/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 8 | One non-compliance issue identified on 9/24/15 and identified on Sheet #8 and the Repair Log as a subgrade irregularity. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/24/15

**Direction Taken:**

Looking west along SA-6 cap (Panel #110 / #111 seam)

**Description:**

Patch / repair work completed for destruct sample DS-27 collected at Panel #110/111 seam (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 cap (at well 115-E1A-SO)

**Description:**

ESI placing gaskets and seals and prepping well 115-E1A-SO for geomembrane boot.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 4+50)

**Description:**

Soil subgrade for next area graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking east / northeast along soil subgrade (from approximate Sta. 4+50)

**Description:**

Subgrade prepared according to project specs and approved for panel placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking south along SA-6 cap (at access manhole #4)

**Description:**

ESI constructing geomembrane boot and skirt for access manhole #4 (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking east along northern end of SA-6

**Description:**

ESI placing GCL along northern SCB wall for areas below (to 1 ft. above) the groundwater table (as per project drawings and specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |


**Date:**
9/24/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Completed geomembrane boot around Access Manhole #4. Patch placed per project specs and extrusion welded with vacuum box testing being completed.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
9/24/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

GCL placed along SCB wall as per project drawings. GCL anchored into slope of subgrade with soil stakes / staples. Seams overlapped a minimum of 1 ft. and sealed with granular bentonite.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 4+20)

**Description:**

ESI placing GCL along drainage/utility ditches/swales for areas below (to 1 ft. above the groundwater table). GCL placed according to the project specs and at the locations shown on the project drawings.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 4+10)

**Description:**

ESI placing GVL as per project specs with white plastic fasteners spaced at maximum of 5 ft. and the top layer of geotextile sewn



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking east along SA-6 cap

**Description:**

GVL cut along bottom of utility/drainage ditches to expose GCL. Minimum of 1 ft. of overlap along GVL and GCL edges.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+50)

**Description:**

ESI deploying geomembrane panels



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 (at panel seams 114/115)

**Description:**

ESI conducting fusion welding (as per project specifications) along Panel Seams 114 / 115.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/25/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 63/73° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #33**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #118 installed on 9/24/15 (located at approximate Sta. 3+80) running approximately 50 ft. east to Sta. 3+30.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair along the panels previously installed, Panels 114-118 which were placed on 9/24/15. Prior to repair work, a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/25/15).
- A total of twenty repairs (RP-425 through RP-444) were observed and fixed (according to the project specifications) from Panels #114 through Panel #118 (repair / detailing work conducted on panels installed on 9/24/15). Refer to 9/25/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. No non-compliance issues were identified as patch / repair work completed was custom fit repairs to allow geomembrane to conform to SA-6 contours. Note: RP-425 has been marked in the field by the project team, however, the repair (pipe boot for GV-2) has not yet been completed.
- Site activities commenced with ESI deploying rolls of GDL from Panel #110 (approximate Sta. 5+30) to approximate Sta. 4+50 (Panel #114 placed on 9/23/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #118 (located at approximate Sta. 3+80) to approximate Sta. 3+30. Refer to *Soil Subgrade Approval* forms from 9/25/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #5 and #6 of the daily photo log for 9/25/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 3+80 to Sta. 3+30.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 3+80 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs). Note: no GVL was placed as the subgrade required GCL placement for the entire area (below the water table elevation).
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #118 on 9/24/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL layer. A total of two panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-119 and P-120) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, two trial welds (smooth to smooth and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/25), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 3+30, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/25/15) for non-destructive testing details.
- ESI completed patch / repair work for the minor repairs associated with the placement of Panels 119 & 120 (RP-437 through RP-444) as identified previously in this report and reflected on the *Repair Log* from 9/25/15.
- No destructive samples were collected from 9/25/15
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of custom fit repairs to allow the geomembrane to conform to the SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/25/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, and 9/24/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/25/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/25/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/25/15 |
| A5 – Subgrade Approval | Sheet 23 & ESI (9/25/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/25/15. |
| A7 – Panel Placement Log | Page 26 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/25/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected for 9/25/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 26-27 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/25/15 |
| A10 – Repair Log | Pages 21-22 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/25/15 |
| A11 – Conformance COC | | N / A for 9/25/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected from 9/25/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected from 9/25/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered from 9/25/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/25/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/25/15

**Direction Taken:**

Looking along SA-6 cap (at Access Manhole #4)

**Description:**

Completed geomembrane boot placed around Access Manhole #4. Boot constructed according to project specs with geomembrane skirt and extrusion welds.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/25/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/25/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 4+60

**Description:**

ESI placing conducting patch / repair work (custom fit repairs) for panels placed on 9/24/15 as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/25/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/25/15

**Direction Taken:**

Looking east along northern end of SA-6 cap

**Description:**

ESI conducting vacuum box testing for extrusion weld repairs (as per project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/25/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/25/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+60)

**Description:**

ESI deploying GDL over geomembrane panels. GDL placed according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta. 3+80)

**Description:**

ESI placing GCL over soil subgrade. GCL placed at locations shown on the project drawings and according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 3+40)

**Description:**

ESI placing GCL as per project drawings. GCL placed according to project specs with minimum of 1 ft. overlap and sealed with granular bentonite.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 3+80)

**Description:**

ESI deploying geomembrane panels over GCL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at RP-439)

**Description:**

ESI conducting patch / repair work (custom fit repairs) for panels P-119 and P-120.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/29/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 69/79° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #34**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #120 installed on 9/25/15 (located at approximate Sta. 3+30) running approximately 80 ft. east to Sta. 2+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #114 (approximate Sta. 4+50) to approximate Sta. 3+80 (Panel #118 placed on 9/24/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use:
    - Roll #64021010072 – Approximately 8 ft. removed
    - Roll #64021010064 – Roll not on inspection list. Approximately 30 ft. removed due to damage observed from forklift
- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #120 (located at approximate Sta. 3+30) to approximate Sta. 2+50. Refer to *Soil Subgrade Approval* forms from 9/29/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 and #3 of the daily photo log for 9/29/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 3+30 to Sta. 2+50.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 3+30 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- Upon placement of the GCL, GVL was placed along the upper elevations within the areas outside of the water table influence (as shown on the project drawings). GVL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals and the top layer of geotextile sewn.
- After installation of the GCL and GVL, geomembrane cap was installed continuing east of previously installed Panel #120 on 9/25/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-120, P-121, P-122, P-123, P-124, and P-125) by ESI. Note: During placement of geomembrane panel P-123, the roll of geomembrane terminated within the SA-6 approximately 20 ft. from the southern end of the cap. Thus an additional panel (P-124) was required to complete the geomembrane run from north to south.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, three trial welds (smooth to smooth, smooth to texture, and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/29), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 2+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/29/15) for non-destructive testing details. Once, non-destructive testing was completed, ESI then conducted patch/ repair work for the panels installed.
- A total of eleven repairs (RP-445 through RP-455) were observed and fixed (according to the project specifications) from Panels #121 through Panel #125 (repair / detailing work conducted on panels installed on 9/24/15). Refer to 9/29/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. No non-compliance issues were identified as patch / repair work completed was custom fit repairs to allow geomembrane to conform to SA-6 contours.
- No destructive samples were collected from 9/29/15
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of custom fit repairs to allow the geomembrane to conform to the SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/29/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, and 9/25/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/29/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 9/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/29/15 |
| A5 – Subgrade Approval | Sheet 24 & ESI (9/29/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/29/15. |
| A7 – Panel Placement Log | Page 27 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/29/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected for 9/29/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 27-28 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/29/15 |
| A10 – Repair Log | Page 22 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/29/15 |
| A11 – Conformance COC | | N / A for 9/29/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected from 9/29/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected from 9/29/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered from 9/29/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+00)

**Description:**

ESI deploying GDL over installed geomembrane panels. GDL placed according to project specs with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta.3+30)

**Description:**

Soil subgrade east of Panel #120 prepared for panel placement. Subgrade prepared according to project specs (graded, compacted, and free of debris >1/2").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/25/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/25/15

**Direction Taken:**

Looking east along SA-6 (toward approximate Sta. 2+90)

**Description:**

Soil subgrade prepared for panel placement from approximate Sta. 3+30 to approximate Sta. 2+50.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 3+30)

**Description:**

ESI deploying GCL over approved soil subgrade. GCL placed at areas below (to 1 ft. above) the groundwater table as shown on the project drawings.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (along approximate Sta. 3+00)

**Description:**

ESI placing GCL over soil subgrade. GCL placed at locations shown on the project drawings and according to project specs. GCL overlapped a minimum of 1 ft. and sealed with granular bentonite.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 2+90)

**Description:**

GVL and GCL placed over approved subgrade prior to placement of geomembrane panels. GCL placed at areas below (to 1 ft. above) the groundwater table (as shown on project drawings) with GVL placed on the upper bench above water table areas.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 3+00)

**Description:**

ESI deploying geomembrane panels over GCL and GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/29/15

**Direction Taken:**

Looking west along SA-6 cap (at Panel Seams 121/122)

**Description:**

ESI conducting fusion welding (as per project specifications) along Panel Seams 121 / 122.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (along Panel 123 / 124)

**Description:**

Geomembrane panels placed on 9/29/15, welded, and tested according to project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking south along southern end of SA-6 (at RP-447 through RP-449)

**Description:**

ESI completing patch / repair work for custom fit repairs along Panels 122 and 124. Patch / repair work completed according to project specs with extrusion welded and vacuum box testing completed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 10/07/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 60/72° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #35**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor, and patch / repair work associated with panels placed from 9/29/15.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing patch / repair work for minor wrinkles from panels previously placed on 9/29/15 (Panels 121 – 125). During the patch / repair work it was observed that the GCL underlying the geomembrane panels was hydrated with standing water present at two areas:
    - Area 1 was comprised of the drainage / utility swale located along the southern end of SA-6 (approximate Sta. 3+50 to Sta. 2+60 ). At this area, a sump pump pit was located immediately outside of SA-6 cap to the south. During the storm events over the weekend, this pump at one point shut down thus causing a build-up (ponding) of water that extended laterally into the swale and hydrating the GCL.
    - Area 2 was located along the northern end of the cap (approximate Sta. 4+00 to Sta. 3+40) along the SCB wall. During the storm events water from the adjacent roadway (higher elevation than the SA-6 cap as final grading has not yet been completed) ran along the edges of SA-6 causing some soil washout, which allowed the water to infiltrate laterally over the SCB wall and onto the lower portion of SA-6.
- For both of these areas, the geomembrane cap was pulled back to expose the hydrated GCL. The GCL was then cut and removed to expose the underlying soil subgrade. Visual observation of the subgrade showed that the soil was in good condition (firm and unyielding) with no wet or wash out areas observed. New GCL was then placed in these areas with minimum of 1 ft. of overlap and granular bentonite placed along the seams as per project specifications. Refer to *10/7/15 Photograph Log* for supporting Site photos.
- Once the new GCL was placed, the geomembrane panels were patch / repaired (as required) over these areas.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of twenty repairs (RP-456 through RP-475) were observed and fixed (according to the project specifications) from Panels #119 through Panel #122 (repair / detailing work for replaced GCL on panels installed from 9/29/15). Refer to 10/7/15 *Repair Report.* The majority of these repairs were patch / repairs associated with the removal and replacing of the hydrated GCL. These repairs were identified as subgrade irregularities on the *Repair Report,* and were identified as non-compliance issues on *Sheet #9* and *Sheet #10 Notice of Non-Compliance* forms, respectively. Note: RP-457 which consisted of a pipe boot for GV-0 was marked in the field and noted on the Repair Report (as RP-457), however the boot and repair itself has not yet been completed.
- Two destructive samples were collected from 10/7/15. Destruct sample DS-28 (fusion) was collected from Panel #123/125, and sample DSX-12 was collected from RP-459 (Panel #123).
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 9 (Sheet #9) – Subgrade irregularity (hydrated GCL) identified as repairs RP-458 through RP-473 on *Repair Log*
    - GCL underneath geomembrane liner along southern end SA-6 (swale) hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final) and failure of sump pump in area during storm. Geomembrane liner pulled back and cut to remove and replace sections of GCL. These patches were noted as a subgrade irregularities and were completed following project specs and are further defined on *Sheet 9 Notice of Non-Compliance*
- Non-Conformance No. 10 (Sheet #10) – Subgrade irregularity (hydrated GCL) identified as RP-474 and RP-475 on *Repair Log*
    - GCL underneath geomembrane liner along northern end of SA-6 cap (along SCB wall) hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final). Geomembrane liner pulled back and cut to remove and replace sections of GCL. These patches were noted as a subgrade irregularities and were patched/repaired following project specs as further defined on *Sheet 10 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/7/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 7 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2$^{nd}$ utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DS-28 and DSX-12.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, and 9/29/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/7/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 10/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/7/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/7/15 |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/7/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/7/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected form 10/7/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 10/7/15 |
| A10 – Repair Log | Pages 22-23 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/7/15 |
| A11 – Conformance COC | | N / A for 10/7/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/7/15 |
| A13 – Destruct. Sample Summary | Sheet 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/7/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before logs can be completed |
| A16 – Notice of Non-Compliance | Sheet #9 and Sheet #10 | Two non-compliance forms completed (Sheet #9 and Sheet #10) for cutting and removal of hydrated GCL |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/7/15

**Direction Taken:**

Looking east along SA-6 cap (Panel 123 / 125 seam)

**Description:**

ESI collecting destruct sample DS-28 (fusion) along Panel 123 / 125 seam as per project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/7/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (swale at approximate Sta.

**Description:**

GCL hydrated / silted from stormwater during weekend rain events. Sump pump area located immediately outside of the cap failed, thus causing a water build-up and ponding that moved laterally into the swale and hydrating the GCL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/25/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (approximate Sta. 3+00)

**Description:**

Geomembrane cap pulled back to expose hydrated GCL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/7/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Hydrated GCL removed and soil subgrade exposed. Subgrade in good condition with no wet, or washed out areas observed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/7/15

**Direction Taken:**

Looking west along southern end of SA-6 cap

**Description:**

ESI placing new GCL over soil subgrade. GCL overlapped a minimum of 1 ft. and sealed with granular bentonite as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/7/15

**Direction Taken:**

Looking east along approximate Sta. 3+00

**Description:**

ESI conducting patch / repair work to the geomembrane cap after placing new GCL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
10/7/15

**Direction Taken:**

Looking east along northern end of SA-6 cap (along SCB wall)

**Description:**

Geomembrane cap pulled back to expose hydrated / wet GCL located along northern end of SA-6. GCL hydrated from water infiltrating from storm runoff and washout from the road (cap at lower elevation that roadway – final grading not completed outside of cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/7/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

Hydrated GCL along SCB wall (lower elevation than roadway outside of SA-6 cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/7/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

New GCL placed along northern end of SA-6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 10/08/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 62/77° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0630 – 1830 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #36** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #125 installed on 9/29/15 (located at approximate Sta. 2+50) running approximately 100 ft. east to Sta. 1+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #118 (approximate Sta. 3+80) to approximate Sta. 2+50 (Panel #125). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #125 (located at approximate Sta. 2+50) to approximate Sta. 1+50. Refer to *Soil Subgrade Approval* forms from 10/08/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3 and #4 of the daily photo log for 10/08/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 2+50 to Sta. 1+50.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 2+50 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- Upon placement of the GCL, GVL was placed along the upper elevations within the areas outside of the water table influence (as shown on the project drawings). GVL was placed according to project

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals and the top layer of geotextile sewn.

- After installation of the GCL and GVL, geomembrane cap was installed continuing east of previously installed Panel #125 on 9/29/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of ten varying panel lengths were placed by ESI (Panels #126-134). Note: the dimensions of these panel lengths varied as the geomembrane panels were conformed to fit along the eastern end of the SA-6 cap.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, three trial welds (smooth to smooth, smooth to texture, and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (10/8), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 1+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (10/08/15) for non-destructive testing details. Once, non-destructive testing was completed, ESI then conducted minor patch/ repair work for the panels installed (pipe boots PZ-12).
- A total of one repair (RP-476) was completed (according to the project specifications) for Panel #132 (pipe boot PZ-12). Refer to 10/8/15 *Repair Report* for additional details on the pipe boot. Note: no non-compliance issues were observed during the geomembrane placement and testing conducted on 10/8/15.
- One destructive sample was collected from 10/8/15. Destruct sample DS-29 (fusion) was collected from Panel #128/132 seam.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of pipe boot installations around PZ-12.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/8/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 5 piezometers, and 8 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2$^{nd}$ utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DS-29.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, and 10/07/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-28, and DSX-1 through DSX-12. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/8/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 10/8/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/8/15 |
| A5 – Subgrade Approval | Sheet 25 & ESI (10/8/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Pages 6-7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/8/15. |
| A7 – Panel Placement Log | Pages 28-29 | One panel placement log provided by ESI and confirmed by Langan for prewelds completed on 10/8/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/8/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 28-30 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 10/8/15 |
| A10 – Repair Log | Page 23 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 10/8/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/8/15 |
| A13 – Destruct. Sample Summary | Sheet 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/8/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before logs can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
10/8/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 3+80)

**Description:**

ESI deploying GDL over geomembrane panels (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
10/8/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 3+20)

**Description:**

ESI deploying GDL over geomembrane panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking north / northwest along SA-6 (at approximate Sta. 1+70)

**Description:**

Approved soil subgrade for GCL and GVL placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking south along eastern end of SA-6 cap (at approximate Sta. 2+00).

**Description:**

ESI placing GCL along eastern end of SA-6 cap (as shown in project drawings) as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast toward eastern end of SA-6

**Description:**

GVL and GCL placed over soil subgrade. GCL overlapped a minimum of 1 ft. with granular bentonite placed along seams (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast toward eastern end of SA-6

**Description:**

ESI deploying geomembrane panels over GVL and GCL (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast along SA-6

**Description:**

ESI deploying geomembrane over eastern section of SA-6 (adjacent to Route 440)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/8/15

**Direction Taken:**

Looking east at eastern end of SA-6 (along Route 440).

**Description:**

ESI conducting fusion welding along Panel Seams 132/133 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking northwest along SA-6 cap (at pipe boot for piezometer PZ-12).

**Description:**

Pipe boot and skirt patch / repair completed for piezometer PZ-12.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking northeast along SA-6

**Description:**

Pipe boot PZ-12 completed with extrusion welds and vacuum box tested to confirm integrity (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 10/09/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 58/75° F, Clear, Overcast, PM T'Storm |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1730 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #37**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor, and to eastern end of SA-6, and patch / repair work associated with panels placed from 10/8/15 (Panels #126-134).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing patch / repair work for panels previously placed on 10/8/15 (Panels #126-134). A total of nine repairs (RP-477 through RP-485) were observed and fixed (according to the project specifications) from Panels #126 through Panel #134. Refer to 10/9/15 *Repair Report* for additional details. The majority of these repairs were custom fit details (allow the geomembrane to conform to the SA-6 contours) or seam joint repairs (joints where non-destructive testing was completed). Repairs were patched, sealed with an extrusion weld, and vacuum box tested (according to project specs).
- Two destructive samples were collected from 10/9/15. Destruct sample DSX-13 (extrusion) was collected from RP-477 (Panel #125) and DSX-14 (extrusion) was collected from RP-480 (Panel #132).
- Upon completion of the patch / repair work, ESI completed the final monitoring well, piezometer, and gas vent boots by placing the final butyl sealant around the top of the boot. Additionally, 1-inch pipe bands were placed around the conical Access Manholes (as per project specs).
- With the pipe boots completed, ESI deployed GDL from Panel #125 to Panel #134 (panels placed on 10/9/15). GDL was placed according to project specs with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile sewn.
- Note: As per the AmecFW GDL Cover Soil Siltation Evaluation and Mitigation Measures Memo (Memo) submitted October 26, 2015, three areas in the field were identified where GDL was exposed and silts were deposited directly onto the GDL. In response to the protective cover soil siltation, three new pieces of GDL were placed directly over the potentially impacted areas to assist in drainage. Additional details of these areas and mitigation measures are further described in the AmecFW Memo, with supporting photographs provided.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.
- Upon completion of the daily activities, ESI demobilized from the Site, as SA-6 capping activities were completed.

***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as patch / repair work completed consisted of custom fit repairs and seam joint patches to allow the geomembrane to conform to the SA-6 contours.

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/9/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (for 3 wells, 5 piezometers, and 8 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1, and Manhole #2, Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DSX-13 and DSX-14.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, and 10/08/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-12. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue with protective cover soil placement along eastern end of SA-6.
- Ensure destruct samples are in compliance with project specs and complete associated paperwork and construction certification report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/9/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 10/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/8/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/9/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/9/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/9/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/9/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 10/9/15 |
| A10 – Repair Log | Pages 23-24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/9/15 |
| A11 – Conformance COC | | N / A for 10/9/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/9/15 |
| A13 – Destruct. Sample Summary | Page 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/9/15 |
| A14 – Penetration & Edge Form | Sheets #1-18 | Final penetration & edge forms completed for piezometers, wells, gas vents, and access manholes. |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

ESI preparing geomembrane seam for extrusion weld trial log



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (Panel #125)

**Description:**

ESI conducting patch / repair work after collecting destruct sample DSX-13 from RP-477 (Panel #125).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking east along southern end of SA-6 (Panel #125)

**Description:**

Completed patch / repair for RP-483 with extrusion welds and subsequent vacuum box testing (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6 (at piezometer PZ-12)

**Description:**

ESI placing final butyl seal around piezometer PZ-12



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6 (at PZ-12)

**Description:**

Final geomembrane boot around piezometer PZ-12 completed with butyl seal. Boot and skirt extrusion welded and vacuum box tested (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking east along SA-6

**Description:**

Final butyl seal placed around top of gas vent GV-1 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6

**Description:**

ESI placing final 1-inch band clamp around Manhole #4 with final butyl seal applied (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6

**Description:**

ESI deploying GDL over geomembrane panels placed on 10/9/15. GDL placed according to project spec with white plastic fasteners at a maximum of 5 ft. and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking northwest along SA-6 cap (along SCB wall leading to Lighting Utility Corridor)

**Description:**

New layer of GDL (approximate 50 ft. by 7.5 ft.) placed along SCB wall over areas where runoff may have caused potential siltation inside GDL. Additional details outlined in the AmecFW Memo.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking northeast along SA-6 (lighting corridor looking north)

**Description:**

New layer of GDL (approximate 20 ft. by 3.75 ft.) placed along lighting corridor (looking north) and identified as area where potential siltation may have occurred. Additional details are outlined in the AmecFW Memo.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 10/12/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 72° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 1520 – 1720 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #38**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of patch / repair work associated with a failed destruct test (DSX-13) for RP-477 located on Panel #125.
- Based on results of the laboratory destruct testing, 1 of 5 specimens exhibited a peel value less than the 66 lb/in value allotted (as per the project specs) for destruct sample DSX-13. Based on this one failure anomaly, the repair associated with DSX-13 (RP-477) was covered with a new patch, welded, and vacuum box tested (as per project specs). In addition, a new destruct sample DSX-15 was collected to confirm the integrity of the new welds associated with the new patch. Note: the average of the 5 peel specimens complied with the project specs (total of 92 lb/in).
- Site activities commenced with ESI completing patch / repair work for RP-477. A new 5 ft. by 15 ft. patch was placed over the repair, sealed with an extrusion weld, and vacuum box tested as per project specs. Once the new repair (RP-487) was complete, a new destruct sample, DSX-15, was collected to confirm the integrity of the weld.
- One destructive sample was collected from 10/12/15. Destruct sample DSX-15 (extrusion) was collected from RP-487 (placed over RP-477). Subsequent laboratory testing yielded peel and shear values that were in compliance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 11 (Sheet #11) – Failed destruct sample (DSX-13) collected from RP-477 from Panel #125 (failed one of the five specimens for peel testing)
    - Geomembrane patch was placed over RP-477, welded, and vacuum box tested (as per project specs). Additionally, a new destruct sample (DSX-15) was collected from the new patch (RP-487) to confirm the integrity of the new weld. This repair was noted as a failed destruct sample and was completed following project specs and as further defined on *Sheet 11 Notice of Non-Compliance.*

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/12/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory data for destruct samples DSX-15.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, 10/08/15, and 10/09/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-14. Laboratory results in compliance with shear and peel requirements as outlined in project specifications with the exception of DSX-13. Subsequent patch / repair work defined within this report for the failed destruct sample.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Ensure new destruct sample (DSX-15) adheres to project specifications. Subsequent review of the data yielded peel and shear values that were in compliance with the project specs.
- Complete associated paperwork and begin construction certification report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/12/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 10/12/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/12/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/12/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/12/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/12/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/12/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 10/12/15 |
| A10 – Repair Log | Page 24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/12/15 |
| A11 – Conformance COC | | N / A for 10/12/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/12/15 |
| A13 – Destruct. Sample Summary | Page 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/12/15 |
| A14 – Penetration & Edge Form | | N / A no penetration and edge forms completed for 10/12/15 |
| A16 – Notice of Non-Compliance | Sheet #11 | One non-compliance issue encountered on 10/12/15 and documented on *Sheet #11 Notice of Non-Compliance* |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking east along southern end of SA-6 (Panel #125)

**Description:**

ESI placing new patch over RP-477/RP-483 where destruct specimen (1 of 5 ) failed to meet project specs (Note: Average of 5 specimens was acceptable).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking south along southern end of SA-6 (Panel #125)

**Description:**

ESI leistering and grinding RP-487 for extrusion welding and subsequent vacuum box testing (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
10/12/15

**Direction Taken:**

Looking south along SA-6 (at RP-487)

**Description:**

ESI conducting extrusion welding (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Patch / repair RP-487 completed with extrusion welds (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESI conducting vacuum box testing (as per project specs) for RP-487



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESI cutting destruct sample DSX-15 from RP-487 to confirm integrity of welds.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

ESI conducting patch repair work for destruct sample DSX-15 (noted as RP-486 on Repair Report).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking north / northeast along southern end of SA-6

**Description:**

Final patch / repair work completed with extrusion welds and vacuum box testing (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 11/04/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 55 / 70° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0845 – 1215 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #39** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of patch / repair work associated with an equipment puncture that was observed along the northern end of SA-6 (at SCB wall) at approximate Sta. 2+95.
- Based on conversations with the project team, it is understood that during final grading of the area, the tooth of an excavator bucket punctured the GDL and underlying geomembrane cap. This error was attributed to malfunctioning GPS equipment, as the SCB wall (outside of the Cap) was not programmed into the GPS.
- Site activities commenced with ESI completing patch / repair work at the puncture location (along edge of SCB wall at approximate Sta. 2+95. A new piece of GCL was initially placed over the puncture area and a 2 ft. by 1.5 ft. geomembrane patch was then placed over the puncture, and sealed with an extrusion weld (as per project specs). Vacuum box testing could not be completed by ESI, as the patch / repair was located right on the edge of the SCB wall (refer to supporting photo log from 11/4/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 12 (Sheet #12) – Equipment puncture through geomembrane cap.
    - Geomembrane patch was placed over equipment puncture along SCB wall (at approximate Sta. 2+95) and extrusion welded (as per project specs). Prior to patch / repair work, a new piece of GCL was placed over the puncture. This repair was noted as an equipment puncture and was completed following the project specs and as further defined on *Sheet 12 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 11/04/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, 10/08/15, 10/09/15, and 10/12/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-15. Laboratory results in compliance with shear and peel requirements as outlined in project specifications with the exception of DSX-13 (details previously defined in *10/12/15 Daily Report*).

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Complete associated paperwork and begin construction certification report.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 11/04/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 7 photos outlining pertinent daily observations and descriptions for 11/04/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 11/4/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 11/4/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 11/4/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 11/4/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 11/4/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 11/4/15 |
| A10 – Repair Log | Page 24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 11/4/15 |
| A11 – Conformance COC | | N / A for 11/4/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 11/4/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 11/4/15 |
| A14 – Penetration & Edge Form | | N / A no penetration and edge forms completed for 11/4/15 |
| A16 – Notice of Non-Compliance | Sheet #12 | One non-compliance issue encountered on 11/4/15 and documented on *Sheet #12 Notice of Non-Compliance* |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking north along northern end of SA-6 cap (SCB wall) at approximate Sta. 2+95

**Description:**

Minor puncture along SCB wall from excavator bucket. Tooth of bucket penetrated through GDL and into underlying geomembrane layer.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall

**Description:**

Area around puncture cleared to allow ESI to complete patch / repair work (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking south along SCB wall

**Description:**

ESI replacing GCL underneath puncture at SCB wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall (northern end of SA-6)

**Description:**

New geomembrane patch leistered over puncture



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking east along SA-6 (at SCB wall)

**Description:**

ESI conducting extrusion welding over new patch / repair (RP-488).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall

**Description:**

Extrusion welding along patch completed (as per project specs). Vacuum box testing unable to be conducted based on the location of the patch (on edge of SCB wall). Weld visually inspected by Entact / Langan.



# Appendix G
# Receiving Inspection Reports (RIRs)

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02375 |
| Received From: CETCO | | | | | | | | | Receiving Report Number: 27 |
| Address: Lovell Plant, 92 HWY 37, Lovell WY 82431 | | | | | | | | | Date: 6/15/15 |
| QC Inspection by: CP | | QC Date: 6/15/15 | | Inv. Or Packing Slip No.: | | Inv. Or Packing Slip Date: 6/10/15 | | | PO Number: E8140C-082 |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | 5 | | | | | 43 | 48 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 15 | Rolls | Bentomat DN GCL for SA6 North and South Caps (32,625 SF/39,241 lbs)<br>Sammons Truck #2531; Shipper No - 031527601 | 0 | 0 |
| 2 | 14 | Rolls | Bentomat DN GCL for SA6 North and South Caps (30,450 SF/34,183 lbs)<br>Corcoran Truck #9805; Shipper No - 031527602 | 0 | 0 |
| 3 | 14 | Rolls | Bentomat DN GCL for SA6 North and South Caps (30,450 SF/39,067 lbs)<br>Adams Trucking Truck #347; Shipper No - 031527603 | 0 | 0 |
| 4 | 5 | Bags | Granular Bentonite (250 lbs)<br>Sammons Truck #2531; Shipper No - 031527601 | 0 | 0 |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Trailer Trucks (Sammons, Corcoran, Adams) | | Car #<br>See above | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:<br>BOL and Packing List Attached | Freight Bill (Pro) No.:<br>BOL and Packing List Attached | Weight:<br>112,741 lbs (total) | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527603** | **Previous Page**

**Straight Bill of Lading - Original** Loader: JANDER Time In: 6/11/15-15:22:37 Time Out: **6/11/15-16:42:11**

**Carrier**: ADAMS TRUCKING
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/10/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 347 Trailer #: 395/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 32625.0000 SF | 30450.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 39067.3500 |

Gross: 46000.0000 Tare: 0.0000 **Total**: 46000

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

**CETCO**

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:**

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation.

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527603
ORDER DATE: 5/05/2015
SHIP DATE:. 6/11/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574

| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004066 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004068 | 150.0 | 14.5 | 2175.0 | 3160.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004073 | 150.0 | 14.5 | 2175.0 | 3225.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004074 | 150.0 | 14.5 | 2175.0 | 3165.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004075 | 150.0 | 14.5 | 2175.0 | 3230.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004076 | 150.0 | 14.5 | 2175.0 | 3205.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004077 | 150.0 | 14.5 | 2175.0 | 3210.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004078 | 150.0 | 14.5 | 2175.0 | 3235.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004079 | 150.0 | 14.5 | 2175.0 | 3260.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004080 | 150.0 | 14.5 | 2175.0 | 3285.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004081 | 150.0 | 14.5 | 2175.0 | 3330.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004084 | 150.0 | 14.5 | 2175.0 | 3290.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004085 | 150.0 | 14.5 | 2175.0 | 3315.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004090 | 150.0 | 14.5 | 2175.0 | 3300.0 |
| | | | | | | | 30450.0 | |

ORDER TOTALS..... 45380.0

TOTAL ITEMS..... 14

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527601** | **Previous Page**

**Straight Bill of Lading - Original** Loader: HMCKI Time In: 6/9/15-17:41:01 Time Out: **6/9/15-19:01:07**

**Carrier**: SAMMONS
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/10/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 2531 Trailer #: 3232/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 34800.0000 SF | 32625.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 39241.7578 |
| 5.0000 EACH | 5.0000 EACH | | COMMODITY GRANULAR-50<br>(10902/024)<br>CLAY-BENTONITE-GROUND<br>CLASS 50 ITEM 48170 / 3295232<br>3295232 | 250.0000 |

Gross: 47700.0000 Tare: 0.0000 **Total**: 47700

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

CETCO

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:** 6-10-15 507599020

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527601
ORDER DATE: 5/05/2015
SHIP DATE:. 6/09/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574


| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004064 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004070 | 150.0 | 14.5 | 2175.0 | 3200.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004071 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004072 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004082 | 150.0 | 14.5 | 2175.0 | 3330.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004094 | 150.0 | 14.5 | 2175.0 | 3235.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004095 | 150.0 | 14.5 | 2175.0 | 3200.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004101 | 150.0 | 14.5 | 2175.0 | 3125.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004102 | 150.0 | 14.5 | 2175.0 | 3090.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004103 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004104 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004107 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004108 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004109 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004110 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| | | | | | | | 32625.0 | |
| LO-CG 50-LT | 50B | EA | | | | | 5.0 | 250.0 |
| | | | | | | | 5.0 | |

ORDER TOTALS..... 47720.0

TOTAL ITEMS..... 16

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527602** Previous Page

**Straight Bill of Lading - Original** Loader: DRICH Time In: 6/10/15-11:00:30 Time Out: **6/10/15-12:13:36**

**Carrier**: CORCORAN
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/10/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 9805 Trailer #: 547/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 34800.0000 SF | 30450.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 34183.9313 |

Gross: 44830.0000 Tare: 0.0000 **Total**: 44830

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

CETCO

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:**

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation.

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527602
ORDER DATE: 5/05/2015
SHIP DATE:. 6/10/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574

| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004086 | 150.0 | 14.5 | 2175.0 | 3335.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004087 | 150.0 | 14.5 | 2175.0 | 3270.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004088 | 150.0 | 14.5 | 2175.0 | 3305.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004089 | 150.0 | 14.5 | 2175.0 | 3290.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004091 | 150.0 | 14.5 | 2175.0 | 3250.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004092 | 150.0 | 14.5 | 2175.0 | 3190.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004093 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004096 | 150.0 | 14.5 | 2175.0 | 3210.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004097 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004098 | 150.0 | 14.5 | 2175.0 | 3125.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004099 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004100 | 150.0 | 14.5 | 2175.0 | 3120.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004105 | 150.0 | 14.5 | 2175.0 | 3120.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004106 | 150.0 | 14.5 | 2175.0 | 3145.0 |
| | | | | | | | ======== | |
| | | | | | | | 30450.0 | |
| | | | | | | | ======== | |

ORDER TOTALS..... 44830.0

TOTAL ITEMS..... 14

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02380 Gas Venting System |
| Received From: Advanced Drainage Systems, Inc. (ADS) | | | | | | | | | Receiving Report Number: 28 |
| Address: Logan Township NJ | | | | | | | | | Date: 6/15/15 |
| QC Inspection by: CP | | QC Date: 6/15/15 | | Inv. Or Packing Slip No.: BOL #2946738 | | Inv. Or Packing Slip Date: 6/13/15 | | | PO Number: E8140C-082 |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Reels | Total Packages | Received By: ENTACT |
| 4 | | | | 115 | | | | 119 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 2,300 | LF | 8" ADS Single Wall Heavy Duty Perforated Pipe (115 – 20' lengths) for gas venting system | 0 | 0 |
| 2 | 120 | EA | 8" ADS Internal Couplers | 0 | 0 |
| 3 | 10 | EA | 8" ADS Injection Molded Tees | 0 | 0 |
| 4 | 40 | EA | 8" ADS 45 Degree Bends | 0 | 0 |
| 5 | 2 | EA | 8" ADS Snap End Caps | 0 | 0 |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ADS | | Car # 25694 | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.: | Freight Bill (Pro) No.: BOL - 2946738 | Weight: 3090 lbs | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02375 |
| Received From: CETCO | | | | | | | | | Receiving Report Number: 29 |
| Address: Lovell Plant, 92 HWY 37, Lovell WY 82431 | | | | | | | | | Date: 6/18/15 |
| QC Inspection by: CP | | QC Date: 6/18/15 | | Inv. Or Packing Slip No.: | | Inv. Or Packing Slip Date: 6/15/15 | | | PO Number: E8140C-082 |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | | | | 4 | 4 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |


| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 4 | Rolls | Bentomat DN GCL for SA6 North and South Caps (8,700 SF/11,162 lbs)<br>SA Express Truck #9202; Shippers No 031527604 | 0 | 0 |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: SA Express | | Car # 031527604 | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:<br>BOL and Packing List Attached | Freight Bill (Pro) No.:<br>BOL and Packing List Attached | Weight:<br>11,162 lbs (total) | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527604** Previous Page

**Straight Bill of Lading - Original** Loader: JANDER Time In: 6/15/15-15:28:10 Time Out: **6/15/15-16:17:03**

**Carrier**: SA EXPRESS
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/16/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 9202 Trailer #: 53301/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257
**Quote #:**

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 8700.0000 SF | 8700.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 11162.1000 |

Gross: 0.0000 Tare: 0.0000 **Total**: 11162

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

CETCO

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:**

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation.

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527604
ORDER DATE: 5/05/2015
SHIP DATE:. 6/15/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574

| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004065 | 150.0 | 14.5 | 2175.0 | 3115.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004067 | 150.0 | 14.5 | 2175.0 | 3155.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004069 | 150.0 | 14.5 | 2175.0 | 3180.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004083 | 150.0 | 14.5 | 2175.0 | 3340.0 |
| | | | | | | | 8700.0 | |

ORDER TOTALS..... 12790.0

TOTAL ITEMS..... 4

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 33 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/7/15 |
| QC Inspection by: CP | | QC Date: 7/6/15 | | Inv. Or Packing Slip No.: C00008103 | | Inv. Or Packing Slip Date: 7/2/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (96,570 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Landstar | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008103 | Freight Bill (Pro) No.: Packing List Attached | Weight: 25,658 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008103
Ship Date: 7/2/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010001 | 3,625.00 |
| 2 | 0065211010002 | 3,625.00 |
| 3 | 0065211010003 | 3,625.00 |
| 4 | 0065211010004 | 3,625.00 |
| 5 | 0065211010005 | 3,625.00 |
| 6 | 0065211010006 | 3,625.00 |
| 7 | 0065211010007 | 3,625.00 |
| 8 | 0065211010008 | 3,625.00 |
| 9 | 0065211010009 | 3,625.00 |
| 10 | 0065211010010 | 3,625.00 |
| 11 | 0065211010011 | 3,625.00 |
| 12 | 0065211010012 | 3,625.00 |
| 13 | 0065211010013 | 3,625.00 |
| 14 | 0065211010014 | 3,625.00 |
| 15 | 0065211010015 | 3,625.00 |
| 16 | 0065211010016 | 3,625.00 |
| 17 | 0065211010017 | 3,625.00 |
| 18 | 0065211010018 | 3,625.00 |
| 19 | 0065211010019 | 3,625.00 |
| 20 | 0065211010020 | 3,625.00 |
| 21 | 0065211010021 | 3,625.00 |
| 22 | 0065211010022 | 3,625.00 |
| 23 | 0065211010023 | 3,625.00 |
| 24 | 0065211010024 | 2,320.00 |
| 25 | 0065211010025 | 3,625.00 |
| 26 | 0065211010026 | 3,625.00 |
| 27 | 0065211010027 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 96,570.00
Total Weight (lbs): 25,658.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Landstar
Date: 7/2/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5487399

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02373 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 33 |
| Address: 335 Athena Drive – Warehouse A001, Athens, GA 30601 | | | | | | | | | Date: 6/29/15 |
| QC Inspection by: CP | | QC Date: 6/29/15 | | Inv. Or Packing Slip No.: BOL-48066 | | Inv. Or Packing Slip Date: 6/26/15 | | | PO Number: 8140C-080 (IWT/Cargo-Guard) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | | | | 25 | 25 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 25 | Rolls | SKAPS GE116 – 180 x 360 (16 oz/sy non- woven geotextile)<br>(15,000 square yards) | 0 | 0 |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: SKAPS Industries | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.: | Freight Bill (Pro) No.: 48066<br>Packing List Attached | Weight: 15,292 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# Straight Bill of Lading

**Original - Not Negotiable**

**SKAPS Industries**
335 Athena Drive - Warehouse A001
Athens, GA 30601
UNITED STATES

Phone: 706-354-3700
Fax: 706-354-3737

| | |
|---|---|
| **Bill of Lading # DDA:** | 048066 |
| **BOL Date:** | 6/26/15 |
| **Sales Order # ORA:** | 038335 |
| **Customer PO #:** | 20252 |

**Prepay & Add**

| **Sold To:** | **Ship To:** |
|---|---|
| **Iwt/Cargo-Guard**<br>P.O. Box 454<br>Waretown, NJ, 08758<br>UNITED STATES | **Entact**<br>60 Kellogg St.<br>Jersey City, NJ 07305<br>UNITED STATES<br>Attn: Dan Harris<br>Phone: 405-206-4659 |

| **Trailer #** 6 | **Seal #** N/A | **Carrier** Medallion Transport & Logistic |
|---|---|---|

| Ln | Product | No. of Rolls | Weight (LBS) | Square Yards |
|---|---|---|---|---|
| 1 | GE116-180 x 360 | 25 | 15,292 | 15,000.00 |
| | | **25** | **15,292** | **15,000.00** |

## Comments:

**Any discrepancies must be reported, within 3 days of receipt of goods, to SKAPS Industries**

**Required delivery dates are subject to change.**

Construction job site delivery

Customer has equipment to off-load truck

Received at Athens, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route, to destination and as to each party at any time interested in all or any of said property, that every service performed hereunder shall be subject to either: (a) if the shipper noted herein is SKAPS Industries, as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the contract for truck transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries, then SKAPS Industries is acting solely as the agent for the denoted Shipper and thus every aspect of the service to be performed hereunder between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff, if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper, in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation Carrier, having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries, subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

| | |
|---|---|
| SHIPPER **SKAPS Industries - Athens, GA 30601** | CARRIER |
| PER | PER |
| EMERGENCY RESPONSE TELEPHONE NUMBER **706-354-3700** | DATE |

TIME IN: 10:55 am TIME OUT: 11:30 am PRO #:

DRIVER NAME: DRIVER PHONE:

RECEIVED BY: _____ SIGN _____ PHONE# _____

# Packing List

## BOL NO. 48066

**Customer** 271
**Customer PO** 20252
**Customer Name** Iwt/Cargo-Guard
**Ship To** Entact
60 Kellogg St.
Jersey City,NJ 07305

**Order No** ORA-038335
**Due Date**
**Site Location** Athens Warehouse 01

| Item Number | # OF ROLLS | Product Quantity | Label |
|---|---|---|---|
| 1 GE116-180 x 360 | 25 | 15,000 Y2 | |
| 38335.1 | 1 | 600 Y2 | 0001 |
| 38335.2 | 1 | 600 Y2 | 0001 |
| 38335.3 | 1 | 600 Y2 | 0001 |
| 38335.4 | 1 | 600 Y2 | 0001 |
| 38335.5 | 1 | 600 Y2 | 0001 |
| 38335.6 | 1 | 600 Y2 | 0001 |
| 38335.7 | 1 | 600 Y2 | 0001 |
| 38335.8 | 1 | 600 Y2 | 0001 |
| 38335.9 | 1 | 600 Y2 | 0001 |
| 38335.10 | 1 | 600 Y2 | 0001 |
| 38335.11 | 1 | 600 Y2 | 0001 |
| 38335.12 | 1 | 600 Y2 | 0001 |
| 38335.13 | 1 | 600 Y2 | 0001 |
| 38335.14 | 1 | 600 Y2 | 0001 |
| 38335.15 | 1 | 600 Y2 | 0001 |
| 38335.16 | 1 | 600 Y2 | 0001 |
| 38335.17 | 1 | 600 Y2 | 0001 |
| 38335.18 | 1 | 600 Y2 | 0001 |
| 38335.19 | 1 | 600 Y2 | 0001 |
| 38335.20 | 1 | 600 Y2 | 0001 |
| 38335.21 | 1 | 600 Y2 | 0001 |
| 38335.22 | 1 | 600 Y2 | 0001 |
| 38335.23 | 1 | 600 Y2 | 0001 |
| 38335.24 | 1 | 600 Y2 | 0001 |
| 38335.25 | 1 | 600 Y2 | 0001 |

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 34 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/7/15 |
| QC Inspection by: CP | | QC Date: 7/6/15 | | Inv. Or Packing Slip No.: C00008112 | | Inv. Or Packing Slip Date: 7/2/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (98,600 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Landmark | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008112 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,540 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

# STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

## SKAPS Industries

571 Industrial Parkway
Commerce, GA 30529
Ph: 706-336-7000 Fax: 706-336-7007

Bill of Lading # : C00008112
Ship Date : 7/2/2015
Sales Order #: C002021
Customer Name : ESI
Cust. P.O. # : 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal # :

SHIP-TO:
Project: Honeywell Chronium Area, NJ
Address: 60 Kellogg St
City, State, Zip : Jersey City, NJ 07605
Contact: Caroline Panico
Phone: 630-669-4257

**Product Code: TN**

| No | Roll# | Sq. Ft. |
|---|---|---|
| 1 | 0065211010028 | 3625 |
| 2 | 0065211010029 | 3625 |
| 3 | 0065211010030 | 3625 |
| 4 | 0065211010031 | 3625 |
| 5 | 0065211010032 | 3625 |
| 6 | 0065211010033 | 3625 |
| 7 | 0065211010034 | 3625 |
| 8 | 0065211010035 | 3625 |
| 9 | 0065211010036 | 3625 |
| 10 | 0065211010037 | 3625 |
| 11 | 0065211010038 | 3625 |
| 12 | 0065211010039 | 3625 |
| 13 | 0065211010040 | 4350 |
| 14 | 0065211010041 | 3625 |
| 15 | 0065211010042 | 3625 |
| 16 | 0065211010043 | 3625 |
| 17 | 0065211010044 | 3625 |
| 18 | 0065211010045 | 3625 |
| 19 | 0065211010046 | 3625 |
| 20 | 0065211010047 | 3625 |
| 21 | 0065211010048 | 3625 |
| 22 | 0065211010049 | 3625 |
| 23 | 0065211010050 | 3625 |
| 24 | 0065211010051 | 3625 |
| 25 | 0065211010052 | 3625 |
| 26 | 0065211010053 | 3625 |
| 27 | 0065211010054 | 3625 |
| Total Rolls : | | 27 |
| Total Sq. Feet: | | 98,600.00 |
| Total Weight (lbs): | | 29,540.00 |

Bags of ties : 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE , GA 30529

**ATTN RECEIVER : Please sign below if you have received the above mentioned items and any discrepancies must be reported to SKAPS Industries within 7 days of receipt of goods.**

| Receiver Print Name | Receiver's Signature |
|---|---|
| Received Date | Receiver's Company Name : |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings : _____
Driver's Name : _____
Driver's Sign : _____
Driver's Cell Phone # : _____
Trucking Co. : _____
Trucking Co. Phone # : _____
Broker : Landmark
Date : 7/2/2015
Truck Departure Time : _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5487484

**CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY**

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed hereunder shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for Truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be performed hereunder between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this is a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries. Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 35 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/8/15 |
| QC Inspection by: CP | | QC Date: 7/8/15 | | Inv. Or Packing Slip No.: C00008122 | | Inv. Or Packing Slip Date: 7/6/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Millennium Trucking | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008122 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,628 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008122
Ship Date: 7/6/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: Edwin Diaz

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010055 | 3,625.00 |
| 2 | 0065211010056 | 3,625.00 |
| 3 | 0065211010057 | 3,625.00 |
| 4 | 0065211010058 | 3,625.00 |
| 5 | 0065211010059 | 3,625.00 |
| 6 | 0065211010060 | 3,625.00 |
| 7 | 0065211010061 | 3,625.00 |
| 8 | 0065211010062 | 3,625.00 |
| 9 | 0065211010063 | 3,625.00 |
| 10 | 0065211010064 | 3,625.00 |
| 11 | 0065211010065 | 3,625.00 |
| 12 | 0065211010066 | 3,625.00 |
| 13 | 0065211010067 | 3,625.00 |
| 14 | 0065211010068 | 3,625.00 |
| 15 | 0065211010069 | 3,625.00 |
| 16 | 0065211010070 | 3,625.00 |
| 17 | 0065211010071 | 3,625.00 |
| 18 | 0065211010072 | 3,625.00 |
| 19 | 0065211010073 | 3,625.00 |
| 20 | 0065211010074 | 3,625.00 |
| 21 | 0065211010075 | 3,625.00 |
| 22 | 0065211010076 | 3,625.00 |
| 23 | 0065211010077 | 3,625.00 |
| 24 | 0065211010078 | 3,625.00 |
| 25 | 0065211010079 | 3,625.00 |
| 26 | 0065211010080 | 3,625.00 |
| 27 | 0065211010081 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 26,628.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items.**
**Driver's Sign:** Eric Brooks

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: Eric Brooks
Driver's Sign: Eric Brooks
Driver's Cell Phone #: 478-244-8201
Trucking Co.: Millennium Trucking
Trucking Co. Phone #: 770-817-1790
Broker: ATS Logistics
Date: 7/6/15
Truck Departure Time: 3:15 pm

**Comments:**
Driver please call 24 hours prior to delivery
Freight view shipper # : 5487537

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 36 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/8/15 |
| QC Inspection by: CP | | QC Date: 7/8/15 | | Inv. Or Packing Slip No.: C00008137 | | Inv. Or Packing Slip Date: 7/7/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Universal truckload, Inc | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008137 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,130 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008137
Ship Date: 7/7/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: Sara Pauly

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010082 | 3,625.00 |
| 2 | 0065211010083 | 3,625.00 |
| 3 | 0065211010084 | 3,625.00 |
| 4 | 0065211010085 | 3,625.00 |
| 5 | 0065211010086 | 3,625.00 |
| 6 | 0065211010087 | 3,625.00 |
| 7 | 0065211010088 | 3,625.00 |
| 8 | 0065211010089 | 3,625.00 |
| 9 | 0065211010090 | 3,625.00 |
| 10 | 0065211010091 | 3,625.00 |
| 11 | 0065211010092 | 3,625.00 |
| 12 | 0065211010093 | 3,625.00 |
| 13 | 0065211010094 | 3,625.00 |
| 14 | 0065211010095 | 3,625.00 |
| 15 | 0065211010096 | 3,625.00 |
| 16 | 0065211010097 | 3,625.00 |
| 17 | 0065211010098 | 3,625.00 |
| 18 | 0065211010099 | 3,625.00 |
| 19 | 0065211010100 | 3,625.00 |
| 20 | 0065211010101 | 3,625.00 |
| 21 | 0065211010102 | 3,625.00 |
| 22 | 0065211010103 | 3,625.00 |
| 23 | 0065211010104 | 3,625.00 |
| 24 | 0065211010105 | 3,625.00 |
| 25 | 0065211010106 | 3,625.00 |
| 26 | 0065211010107 | 3,625.00 |
| 27 | 0065211010108 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 26,130.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:**

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name:
Driver's Sign:
Driver's Cell Phone #: 254-541-7655
Trucking Co.: Emt Trucking LLC
Trucking Co. Phone #: 254-541-7655
Broker: Universal Truckload, Inc.
Date: 7/7/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5487538

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 37 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/10/15 |
| QC Inspection by: CP | | QC Date: 7/10/15 | | Inv. Or Packing Slip No.: C00008143 | | Inv. Or Packing Slip Date: 7/7/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Liberty Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008143 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,033 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008143
Ship Date: 7/7/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER:
SHIPPER ADDRESS: 571 INDUSTRIAL PKWY. COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010109 | 3,625.00 |
| 2 | 0065211010110 | 3,625.00 |
| 3 | 0065211010111 | 3,625.00 |
| 4 | 0065211010112 | 3,625.00 |
| 5 | 0065211010113 | 3,625.00 |
| 6 | 0065211010114 | 3,625.00 |
| 7 | 0065211010115 | 3,625.00 |
| 8 | 0065211010116 | 3,625.00 |
| 9 | 0065211010117 | 3,625.00 |
| 10 | 0065211010118 | 3,625.00 |
| 11 | 0065211010119 | 3,625.00 |
| 12 | 0065211010120 | 3,625.00 |
| 13 | 0065211010121 | 3,625.00 |
| 14 | 0065211010122 | 3,625.00 |
| 15 | 0065211010123 | 3,625.00 |
| 16 | 0065211010124 | 3,625.00 |
| 17 | 0065211010125 | 3,625.00 |
| 18 | 0065211010126 | 3,625.00 |
| 19 | 0065211010127 | 3,625.00 |
| 20 | 0065211010128 | 3,625.00 |
| 21 | 0065211010129 | 3,625.00 |
| 22 | 0065211010130 | 3,625.00 |
| 23 | 0065211010131 | 3,625.00 |
| 24 | 0065211010132 | 3,625.00 |
| 25 | 0065211010133 | 3,625.00 |
| 26 | 0065211010134 | 3,625.00 |
| 27 | 0065211010135 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 26,033.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**
**Driver's Sign:**

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries witnin 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**
1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.: LIBERTY LOGISTICS
Trucking Co. Phone #:
Broker: Meranu Leasing Inc. DBA Liberty Logistics
Date: 7/7/15
Truck Departure Time:

**Comments:**
Driver please call 24 hours prior to delivery
Freight view shipper # : 5487504

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) If the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occuring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 38 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/14/15 |
| QC Inspection by: CP | | QC Date: 7/15/15 | | Inv. Or Packing Slip No.: C00008174 | | Inv. Or Packing Slip Date: 7/10/15 | | | PO Number: IWT/Cargo-Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,040 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Load Pro | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008174 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,692 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008174
Ship Date: 7/10/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010002 | 2,800.00 |
| 2 | 0064021010003 | 2,800.00 |
| 3 | 0064021010004 | 2,800.00 |
| 4 | 0064021010005 | 2,800.00 |
| 5 | 0064021010006 | 2,800.00 |
| 6 | 0064021010007 | 2,240.00 |
| 7 | 0064021010008 | 2,800.00 |
| 8 | 0064021010009 | 2,800.00 |
| 9 | 0064021010010 | 2,800.00 |
| 10 | 0064021010011 | 2,800.00 |
| 11 | 0064021010012 | 2,800.00 |
| 12 | 0064021010013 | 2,800.00 |
| 13 | 0064021010014 | 2,800.00 |
| 14 | 0064021010015 | 2,800.00 |
| 15 | 0064021010016 | 2,800.00 |
| 16 | 0064021010017 | 2,800.00 |
| 17 | 0064021010018 | 2,800.00 |
| 18 | 0064021010019 | 2,800.00 |
| 19 | 0064021010020 | 2,240.00 |
| 20 | 0064021010021 | 3,360.00 |
| 21 | 0064021010022 | 2,800.00 |
| 22 | 0064021010023 | 2,800.00 |
| 23 | 0064021010024 | 2,800.00 |
| 24 | 0064021010025 | 2,800.00 |
| 25 | 0064021010026 | 2,800.00 |
| 26 | 0064021010027 | 2,800.00 |
| 27 | 0064021010028 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,040.00
Total Weight (lbs): 28,692.00

Bags of Ties: 2

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Load Pro
Date: 7/10/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5514893

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 39 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/14/15 |
| QC Inspection by: CP | | QC Date: 7/15/15 | | Inv. Or Packing Slip No.: C00008181 | | Inv. Or Packing Slip Date: 7/13/15 | | | PO Number: IWT/Cargo-Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,390 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: TQL | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008181 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,911 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008181
Ship Date: 7/13/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010029 | 2,800.00 |
| 2 | 0064021010030 | 2,800.00 |
| 3 | 0064021010031 | 2,660.00 |
| 4 | 0064021010032 | 2,800.00 |
| 5 | 0064021010033 | 2,800.00 |
| 6 | 0064021010034 | 2,800.00 |
| 7 | 0064021010035 | 2,800.00 |
| 8 | 0064021010036 | 2,800.00 |
| 9 | 0064021010037 | 2,730.00 |
| 10 | 0064021010038 | 2,800.00 |
| 11 | 0064021010039 | 2,800.00 |
| 12 | 0064021010040 | 2,800.00 |
| 13 | 0064021010041 | 2,800.00 |
| 14 | 0064021010042 | 2,800.00 |
| 15 | 0064021010043 | 2,800.00 |
| 16 | 0064021010044 | 2,800.00 |
| 17 | 0064021010045 | 2,800.00 |
| 18 | 0064021010046 | 2,800.00 |
| 19 | 0064021010047 | 2,800.00 |
| 20 | 0064021010048 | 2,800.00 |
| 21 | 0064021010049 | 2,800.00 |
| 22 | 0064021010050 | 2,800.00 |
| 23 | 0064021010051 | 2,800.00 |
| 24 | 0064021010052 | 2,800.00 |
| 25 | 0064021010053 | 2,800.00 |
| 26 | 0064021010054 | 2,800.00 |
| 27 | 0064021010055 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,390.00
Total Weight (lbs): 28,911.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: TQL
Date: 7/13/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5521502

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 40 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008185 | | Inv. Or Packing Slip Date: 7/13/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Landstar | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008185 | Freight Bill (Pro) No.: Packing List Attached | Weight: 27,625 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

7/15

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008185
Ship Date: 7/13/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010140 | 3,625.00 |
| 2 | 0065211010141 | 3,625.00 |
| 3 | 0065211010142 | 3,625.00 |
| 4 | 0065211010143 | 3,625.00 |
| 5 | 0065211010144 | 3,625.00 |
| 6 | 0065211010145 | 3,625.00 |
| 7 | 0065211010146 | 3,625.00 |
| 8 | 0065211010147 | 3,625.00 |
| 9 | 0065211010148 | 3,625.00 |
| 10 | 0065211010149 | 3,625.00 |
| 11 | 0065211010150 | 3,625.00 |
| 12 | 0065211010151 | 3,625.00 |
| 13 | 0065211010152 | 3,625.00 |
| 14 | 0065211010153 | 3,625.00 |
| 15 | 0065211010154 | 3,625.00 |
| 16 | 0065211010155 | 3,625.00 |
| 17 | 0065211010156 | 3,625.00 |
| 18 | 0065211010157 | 3,625.00 |
| 19 | 0065211010158 | 3,625.00 |
| 20 | 0065211010159 | 3,625.00 |
| 21 | 0065211010160 | 3,625.00 |
| 22 | 0065211010161 | 3,625.00 |
| 23 | 0065211010162 | 3,625.00 |
| 24 | 0065211010163 | 3,625.00 |
| 25 | 0065211010164 | 3,625.00 |
| 26 | 0065211010165 | 3,625.00 |
| 27 | 0065211010166 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 27,625.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name _____ Receiver's Signature _____

Receive Date _____ Receiver's Company Name _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Landstar
Date: 7/13/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery.
Freight view shipper # : 5523988

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 41 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008187 | | Inv. Or Packing Slip Date: 7/13/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (95,845 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Medallion Transport and Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008187 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,210 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008187
Ship Date: 7/13/15
Sales Order #: C002021
Custorner Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010136 | 3,625.00 |
| 2 | 0065211010137 | 3,625.00 |
| 3 | 0065211010138 | 3,625.00 |
| 4 | 0065211010139 | 3,625.00 |
| 5 | 0065211010167 | 3,625.00 |
| 6 | 0065211010168 | 3,625.00 |
| 7 | 0065211010169 | 3,625.00 |
| 8 | 0065211010170 | 3,625.00 |
| 9 | 0065211010171 | 3,625.00 |
| 10 | 0065211010172 | 3,625.00 |
| 11 | 0065211010173 | 3,625.00 |
| 12 | 0065211010174 | 3,625.00 |
| 13 | 0065211010175 | 1,595.00 |
| 14 | 0065211010176 | 3,625.00 |
| 15 | 0065211010177 | 3,625.00 |
| 16 | 0065211010178 | 3,625.00 |
| 17 | 0065211010179 | 3,625.00 |
| 18 | 0065211010180 | 3,625.00 |
| 19 | 0065211010181 | 3,625.00 |
| 20 | 0065211010182 | 3,625.00 |
| 21 | 0065211010183 | 3,625.00 |
| 22 | 0065211010184 | 3,625.00 |
| 23 | 0065211010185 | 3,625.00 |
| 24 | 0065211010186 | 3,625.00 |
| 25 | 0065211010187 | 3,625.00 |
| 26 | 0065211010188 | 3,625.00 |
| 27 | 0065211010189 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 95,845.00
Total Weight (lbs): 26,210.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Medallion Transport & Logistics LLC.
Date: 7/13/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5516945

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 42 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008193 | | Inv. Or Packing Slip Date: 7/14/15 | | | PO Number: IWT CargoGuard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,530 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Liberty Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008193 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,055 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008193
Ship Date: 7/14/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: Dhiru Patel

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010001 | 2,800.00 |
| 2 | 0064021010057 | 2,800.00 |
| 3 | 0064021010058 | 2,730.00 |
| 4 | 0064021010059 | 2,800.00 |
| 5 | 0064021010060 | 2,800.00 |
| 6 | 0064021010061 | 2,800.00 |
| 7 | 0064021010062 | 2,800.00 |
| 8 | 0064021010063 | 2,800.00 |
| 9 | 0064021010064 | 2,800.00 |
| 10 | 0064021010065 | 2,800.00 |
| 11 | 0064021010066 | 2,800.00 |
| 12 | 0064021010067 | 2,800.00 |
| 13 | 0064021010068 | 2,800.00 |
| 14 | 0064021010069 | 2,800.00 |
| 15 | 0064021010070 | 2,800.00 |
| 16 | 0064021010071 | 2,800.00 |
| 17 | 0064021010072 | 2,800.00 |
| 18 | 0064021010073 | 2,800.00 |
| 19 | 0064021010074 | 2,800.00 |
| 20 | 0064021010075 | 2,800.00 |
| 21 | 0064021010076 | 2,800.00 |
| 22 | 0064021010077 | 2,800.00 |
| 23 | 0064021010078 | 2,800.00 |
| 24 | 0064021010079 | 2,800.00 |
| 25 | 0064021010080 | 2,800.00 |
| 26 | 0064021010081 | 2,800.00 |
| 27 | 0064021010082 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,530.00
Total Weight (lbs): 29,055.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** Curtis Davis

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: Curtis Davis
Driver's Sign: CURTIS DAVIS
Driver's Cell Phone #: 601 339 4109
Trucking Co.: LIBERTY LOGISTIC
Trucking Co. Phone #: 601 339 4109
Broker: Meranu Leasing Inc. DBA Liberty Logistics
Date: 7/14/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5523946

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 43 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008200 | | Inv. Or Packing Slip Date: 7/15/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 16 | 18 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 16 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (75,530 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Coyote | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008200 | Freight Bill (Pro) No.: Packing List Attached | Weight: 16,243 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

7/14

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008200
Ship Date: 7/15/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: Julio Rodriguez

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010190 | 3,480.00 |
| 2 | 0065211010191 | 3,480.00 |
| 3 | 0065211010192 | 3,480.00 |
| 4 | 0065211010193 | 3,480.00 |
| 5 | 0065211010194 | 3,480.00 |
| 6 | 0065211010195 | 3,480.00 |
| 7 | 0065211010196 | 3,625.00 |
| 8 | 0065211010197 | 3,625.00 |
| 9 | 0065211010198 | 3,625.00 |
| 10 | 0065211010199 | 3,625.00 |
| 11 | 0065211010200 | 3,625.00 |
| 12 | 0065211010201 | 3,625.00 |
| 13 | 0065211010202 | 3,625.00 |
| 14 | 0065211010203 | 3,625.00 |
| 15 | 0065211010204 | 3,625.00 |
| 16 | 0065211010205 | 3,625.00 |

Total Rolls: 16
Total Sq Feet: 57,130.00
Total Weight (lbs): 16,243.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** x

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: FLOYD RISS
Driver's Sign:
Driver's Cell Phone #: 404 980 3304
Trucking Co.: FSK
Trucking Co. Phone #: SAME
Broker: Coyote 3:00 PM
Date: 7/15/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5516953

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 44 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008197 | | Inv. Or Packing Slip Date: 7/15/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 29 | 31 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 29 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (78,540 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Freightquote | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008197 | Freight Bill (Pro) No.: Packing List Attached | Weight: 30,326 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

7/16

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008197
Ship Date: 7/15/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: Roosh Patel
SHIPPER ADDRESS: 571 INDUSTRIAL PKWY. COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010056 | 2,240.00 |
| 2 | 0064021010110 | 2,800.00 |
| 3 | 0064021010111 | 2,240.00 |
| 4 | 0064021010112 | 3,150.00 |
| 5 | 0064021010113 | 2,800.00 |
| 6 | 0064021010114 | 2,800.00 |
| 7 | 0064021010115 | 2,800.00 |
| 8 | 0064021010116 | 2,800.00 |
| 9 | 0064021010117 | 2,800.00 |
| 10 | 0064021010118 | 2,800.00 |
| 11 | 0064021010119 | 2,800.00 |
| 12 | 0064021010120 | 2,800.00 |
| 13 | 0064021010121 | 3,430.00 |
| 14 | 0064021010122 | 2,170.00 |
| 15 | 00640210101221 | 1,120.00 |
| 16 | 0064021010123 | 2,800.00 |
| 17 | 0064021010124 | 2,800.00 |
| 18 | 0064021010125 | 2,590.00 |
| 19 | 0064021010126 | 2,870.00 |
| 20 | 0064021010127 | 3,080.00 |
| 21 | 0064021010128 | 2,450.00 |
| 22 | 0064021010129 | 2,800.00 |
| 23 | 0064021010130 | 2,800.00 |
| 24 | 0064021010131 | 2,800.00 |
| 25 | 0064021010132 | 2,800.00 |
| 26 | 0064021010133 | 2,800.00 |
| 27 | 0064021010134 | 2,800.00 |
| 28 | 0064021010135 | 2,800.00 |
| 29 | 0064021010136 | 2,800.00 |

Total Rolls: 29
Total Sq Feet: 78,540.00
Total Weight (lbs): 30,326.00

Bags of Ties: 2

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.:
Trucking Co. Phone #:
Broker: Freightquote
Date: 7/15/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5530510

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 45 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008201 | | Inv. Or Packing Slip Date: 7/15/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,600 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Coyote | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008201 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,088 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

7/16

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008201
Ship Date: 7/15/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: RooshiPatel

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010083 | 2,800.00 |
| 2 | 0064021010084 | 2,800.00 |
| 3 | 0064021010085 | 2,800.00 |
| 4 | 0064021010086 | 2,800.00 |
| 5 | 0064021010087 | 2,800.00 |
| 6 | 0064021010088 | 2,800.00 |
| 7 | 0064021010089 | 2,800.00 |
| 8 | 0064021010090 | 2,800.00 |
| 9 | 0064021010091 | 2,800.00 |
| 10 | 0064021010092 | 2,800.00 |
| 11 | 0064021010093 | 2,800.00 |
| 12 | 0064021010094 | 2,800.00 |
| 13 | 0064021010095 | 2,800.00 |
| 14 | 0064021010096 | 2,800.00 |
| 15 | 0064021010097 | 2,800.00 |
| 16 | 0064021010098 | 2,800.00 |
| 17 | 0064021010099 | 2,800.00 |
| 18 | 0064021010100 | 2,800.00 |
| 19 | 0064021010101 | 2,800.00 |
| 20 | 0064021010102 | 2,800.00 |
| 21 | 0064021010103 | 2,800.00 |
| 22 | 0064021010104 | 2,800.00 |
| 23 | 0064021010105 | 2,800.00 |
| 24 | 0064021010106 | 2,800.00 |
| 25 | 0064021010107 | 2,800.00 |
| 26 | 0064021010108 | 2,800.00 |
| 27 | 0064021010109 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,600.00
Total Weight (lbs): 29,088.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Coyote
Date: 7/15/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5530505

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02372 |
| Received From: Agru/America Inc. | | | | | | | | | Receiving Report Number: 46 |
| Address: 500 Garrison Road, Georgetown, SC 29440 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/17/15 | | Inv. Or Packing Slip No.: 046962 | | Inv. Or Packing Slip Date: 7/16/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Spools | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 12 | | | 12 | 24 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 12 | Rolls | 60 mil LLDPE MicroSpike Geomembrane (139,380 square feet) | 0 | 0 |
| 2 | 12 | Spools | LLDPE Welding Rod | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: LTL | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:046962 | Freight Bill (Pro) No.: Packing List Attached | Weight: 45,500 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# TRAIGHT BILL OF LADING - SHORT FORM - ORIGINAL - NOT NEGOTIABLE

B/L NO. 046962

AME OF CARRIER: BEST WAY FRT LTL | CARRIER'S NO. | DATE: 7/16/2015

CEIVED, subject to the classifications and lawfully filed tariffs in effect on the date of issue of this Bill of Lading,
property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below which said carrier (the word carrier beir
derstood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver t
other carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any
d property, that every service to be performed hereunder, shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the da
reof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
ipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification or tariff which governs the transportation of this shipment, and the said terms and conditior
hereby agreed to by the shipper and accepted for himself and his assigns.

**FROM:** SHIPPER (ORIGIN)

**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

EMERGENCY RESPONSE PHONE NO.

**TO:**
CONSIGNEE: HONEYWELL CHROMIUM AREA
ENVIRONMENTAL SPECIALTIES
STREET: 60 KELLOGG STREET
JERSEY CITY, NJ 07305
DANIEL HARRIS 405-206-4659
DESTINATION
ZIP

ELIVERING ARRIER | ROUTE | VEHICLE NUMBER

| NO. PACKAGES | + HM | KIND OF PACKAGE, DESCRIPTION OF ARTICLES SPECIAL MARKS AND EXCEPTIONS | *WEIGHT (SUBJECT TO CORR.) | CLASS OR RATE | ✓ | CHARGES (FOR CARRIER USE ONLY |
|---|---|---|---|---|---|---|
| 139,380<br>264 | | LL DBL MICRO 60MIL 23FT<br>WELD ROD MFG BLACK LDPE 5MM | | | | 36.923C<br>1706 |

| Item Key | Lot Number | Quantity |
|---|---|---|
| L-LL-MSDS-60-23 | G15C276054 | 11,615 |
| L-LL-MSDS-60-23 | G15C276055 | 11,615 |
| L-LL-MSDS-60-23 | G15C276057 | 11,615 |
| L-LL-MSDS-60-23 | G15C282013 | 11,615 |
| L-LL-MSDS-60-23 | G15C282014 | 11,615 |
| L-LL-MSDS-60-23 | G15C282017 | 11,615 |
| L-LL-MSDS-60-23 | G15C282020 | 11,615 |
| L-LL-MSDS-60-23 | G15C282023 | 11,615 |
| L-LL-MSDS-60-23 | G15C283027 | 11,615 |
| L-LL-MSDS-60-23 | G15C283028 | 11,615 |
| L-LL-MSDS-60-23 | G15C283029 | 11,615 |
| L-LL-MSDS-60-23 | G15C283030 | 11,615 |

Total Weight: ~~46,260 LB~~ 45,500 lbs.
Total Packages: ~~139,644~~ 12 Rolls
Order No.: 28919 Order Date: 05/04/15 Request Date: 06/30/15
Location: GTOWN P.O. No.: 21570
12 Spools - Weld Rod

**MIT C.O.D. TO:**
**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

**C.O.D.** Amt $

C.O.D. FEE
☑ Prepaid
☐ Collect $

the shipment moves between two ports by a carrier by ter, the law requires that the bill of lading shall state ether it is "carrier's or shipper's weight"

hipper's imprint in lieu of stamp; not a part of bill of lading roved by the Interstate Commerce Commission

NOTE: Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property.
**The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding**
$ per

Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement:
The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges
(Signature of Consignor)

**TOTAL CHARGES $**
Freight charges are PREPAID unless marked collect. ☐ Check box if charges are Collect

is is to certify that the above named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation, according to the applicable regulations of the Department of Transportation

Shipper, Per

Agent, Per


manent post office address of shipper
+ MARK WITH "X" TO DESIGNATE HAZARDOUS MATERIAL AS DEFINED IN TITLE 49 OF FEDERAL REGULATIONS.
hen transporting hazardous materials include the technical or chemical name for n.o.s. (not otherwise specified) or generic description of material with appropriate UN or NA number as defined in US DOT Emergency Response mmunication Standard (HM-126C). Provide emergency response phone number in case of incident or accident.

1

# Shipping Release

1706
369230

| OA # | 28919 | Date | 7/16/15 |
|---|---|---|---|

| Driver's Name/Truck Company | Customer | Destination | | | Pictures Taken |
|---|---|---|---|---|---|
| George Williams / LTL | Environmental Specialties | City: Jersey City | State: NJ | | YES ● NO (GALAX) |
| **Time In:** 8:57 | **Time Out:** 9:59 | Inspector: C.H. / J.S. | Loader: C.H. | | |

## Roll #

| | G | YEAR | | M | WK of YR | | DOW | ROLL # | | | External Visual | Straps OK | Core OK | Weld Rod OK |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | G | 1 | 5 | C | 2 | 7 | 6 | 0 | 5 | 4 | Yes ● No | Yes ● No | Yes ● No | Yes ● No |
| 2 | G | 1 | 5 | \| | 2 | 7 | 6 | 0 | 5 | 5 | Yes No | Yes No | Yes No | Yes No |
| 3 | G | 1 | 5 | \| | 2 | 7 | 6 | 0 | 5 | 7 | Yes No | Yes No | Yes No | Yes No |
| 4 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 1 | 3 | Yes No | Yes No | Yes No | Yes No |
| 5 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 1 | 4 | Yes No | Yes No | Yes No | Yes No |
| 6 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 1 | 7 | Yes No | Yes No | Yes No | Yes No |
| 7 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 2 | 0 | Yes No | Yes No | Yes No | Yes No |
| 8 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 2 | 3 | Yes No | Yes No | Yes No | Yes No |
| 9 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 2 | 7 | Yes No | Yes No | Yes No | Yes No |
| 10 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 2 | 8 | Yes No | Yes No | Yes No | Yes No |
| 11 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 2 | 9 | Yes No | Yes No | Yes No | Yes No |
| 12 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 3 | 0 | Yes No | Yes No | Yes No | Yes No |
| 13 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 14 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 15 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 16 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 17 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 18 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 19 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 20 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 21 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 22 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 23 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 24 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 25 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 26 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 27 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |

## CONTAINER/MISC

CONTAINER#

TIES

WELD ROD

12 spools 5mm LC BIA
CFD810090

BENTONITE BAGS

STRAPS

PALLETS

| | |
|---|---|
| External Visual Check: | Clean Roll; Damage (Holes, Tears); Telescoping; Liner Defects (Volds, Bug Marks, Etc.) Legible Markings on Roll |
| Strap Check: | 6' Foot Spacing; Check for Wear, Cuts |
| Core Check: | Check for Craks, Defects |
| Weld Rod Check: | (If Necessary): Secure Load; Lot # on BOL; Check Type |
| Comments: | |

Revised 11/11/14

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02372 |
| Received From: Agru/America Inc. | | | | | | | | | Receiving Report Number: 47 |
| Address: 500 Garrison Road, Georgetown, SC 29440 | | | | | | | | | Date: 7/20/15 |
| QC Inspection by: CP | | QC Date: 7/20/15 | | Inv. Or Packing Slip No.: 046977 | | Inv. Or Packing Slip Date: 7/16/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Spools | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 12 | | | 12 | 24 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 12 | Rolls | 60 mil LLDPE MicroSpike Geomembrane (139,380 square feet) | 0 | 0 |
| 2 | 12 | Spools | LLDPE Welding Rod | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Best Way Freight | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:046977 | Freight Bill (Pro) No.: Packing List Attached | Weight: 45,500 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# STRAIGHT BILL OF LADING - SHORT FORM - ORIGINAL - NOT NEGOTIABLE

B/L NO. 046977

| NAME OF CARRIER | CARRIER'S NO. | DATE |
|---|---|---|
| BEST WAY FRT Bishopville Spec. | | 7/16/2015 |

**RECEIVED, subject to the classifications and lawfully filed tariffs in effect on the date of issue of this Bill of Lading,**
the property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any of said property, that every service to be performed hereunder, shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
**Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification or tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.**

**FROM:**
SHIPPER
(ORIGIN)

**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

EMERGENCY RESPONSE PHONE NO.

**TO:**
CONSIGNEE HONEYWELL CHROMIUM AREA
ENVIRONMENTAL SPECIALTIES
STREET 60 KELLOGG STREET
JERSEY CITY, NJ 07305
DESTINATION DANIEL HARRIS 405-206-4659
ZIP

| DELIVERING CARRIER | ROUTE | VEHICLE NUMBER |
|---|---|---|
| | | |

| NO. PACKAGES | + HM | KIND OF PACKAGE, DESCRIPTION OF ARTICLES SPECIAL MARKS AND EXCEPTIONS | *WEIGHT (SUBJECT TO CORR.) | CLASS OR RATE | ✓ | CHARGES (FOR CARRIER USE ONLY) |
|---|---|---|---|---|---|---|
| 139,380 | | LL DBL MICRO 60MIL 23FT | | | | |

| Item Key | Lot Number | Quantity |
|---|---|---|
| L-LL-MSDS-60-23 | G15C276052 | 11,615 |
| L-LL-MSDS-60-23 | G15C276053 | 11,615 |
| L-LL-MSDS-60-23 | G15C276056 | 11,615 |
| L-LL-MSDS-60-23 | G15C277061 | 11,615 |
| L-LL-MSDS-60-23 | G15C277062 | 11,615 |
| L-LL-MSDS-60-23 | G15C277064 | 11,615 |
| L-LL-MSDS-60-23 | G15C282011 | 11,615 |
| L-LL-MSDS-60-23 | G15C282012 | 11,615 |
| L-LL-MSDS-60-23 | G15C282016 | 11,615 |
| L-LL-MSDS-60-23 | G15C282021 | 11,615 |
| L-LL-MSDS-60-23 | G15C283031 | 11,615 |
| L-LL-MSDS-60-23 | G15C283033 | 11,615 |

Total Weight: ~~45,996 LB~~ 45,500 lbs.
Total Packages: ~~139,380~~ 12 Rolls
Order No.: 28919 Order Date: 05/04/15 Request Date: 06/30/15
Location: GTOWN P.O. No.: 21570

**REMIT C.O.D. TO:**
**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

**C.O.D.** Amt $

**C.O.D. FEE**
☑ Prepaid
☐ Collect $

*If the shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's or shipper's weight".

† **Shipper's imprint in lieu of stamp; not a part of bill of lading approved by the Interstate Commerce Commission.**

NOTE: Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property.
**The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding**
$ per

Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement:
The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges.
(Signature of Consignor)

**TOTAL CHARGES $**

Freight charges are PREPAID unless marked collect. ☐ Check box if charges are Collect.

"This is to certify that the above named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation, according to the applicable regulations of the Department of Transportation".

Shipper, Per JB + Agent, Per Jim Beam

Page 1 of 1
Permanent post office address of shipper

**+ MARK WITH "X" TO DESIGNATE HAZARDOUS MATERIAL AS DEFINED IN TITLE 49 OF FEDERAL REGULATIONS.**
When transporting hazardous materials include the technical or chemical name for n.o.s. (not otherwise specified) or generic description of material with appropriate UN or NA number as defined in US DOT Emergency Response Communication Standard (HM-126C). Provide emergency response phone number in case of incident or accident.

1

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02372 |
| Received From: Agru/America Inc. | | | | | | | | | Receiving Report Number: 47 |
| Address: 500 Garrison Road, Georgetown, SC 29440 | | | | | | | | | Date: 7/21/15 |
| QC Inspection by: CP | | QC Date: 7/21/15 | | Inv. Or Packing Slip No.: 046973 | | Inv. Or Packing Slip Date: 7/16/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Spools | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 12 | | | 12 | 24 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 12 | Rolls | 60 mil LLDPE MicroSpike Geomembrane (139,380 square feet) | 0 | 0 |
| 2 | 12 | Spools | LLDPE Welding Rod | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Best Way Freight | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:046973 | Freight Bill (Pro) No.: Packing List Attached | Weight: 44,900 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

## STRAIGHT BILL OF LADING - SHORT FORM - ORIGINAL - NOT NEGOTIABLE

B/L NO. 046973

| NAME OF CARRIER | CARRIER'S NO. | DATE |
|---|---|---|
| BEST WAY FRT LTL | | 7/16/2015 |

**RECEIVED, subject to the classifications and lawfully filed tariffs in effect on the date of issue of this Bill of Lading,**
the property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any of said property, that every service to be performed hereunder, shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
**Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification or tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.**

**FROM:**
SHIPPER
(ORIGIN)

**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

EMERGENCY RESPONSE PHONE NO.

**TO:**
CONSIGNEE HONEYWELL CHROMIUM AREA
ENVIRONMENTAL SPECIALTIES
STREET 60 KELLOGG STREET
JERSEY CITY, NJ 07305
DESTINATION DANIEL HARRIS 405-206-4659
ZIP

| DELIVERING CARRIER | ROUTE | VEHICLE NUMBER |
|---|---|---|
| | | |

| NO. PACKAGES | + HM | KIND OF PACKAGE, DESCRIPTION OF ARTICLES SPECIAL MARKS AND EXCEPTIONS | *WEIGHT (SUBJECT TO CORR.) | CLASS OR RATE | ✓ | CHARGES (FOR CARRIER USE ONLY) |
|---|---|---|---|---|---|---|
| 139,380<br>264 | | LL DBL MICRO 60MIL 23FT<br>WELD ROD MFG BLACK LDPE 5MM | | | | |

| Item Key | Lot Number | Quantity |
|---|---|---|
| L-LL-MSDS-60-23 | G15C276058 | 11,615 |
| L-LL-MSDS-60-23 | G15C277059 | 11,615 |
| L-LL-MSDS-60-23 | G15C277060 | 11,615 |
| L-LL-MSDS-60-23 | G15C277065 | 11,615 |
| L-LL-MSDS-60-23 | G15C282015 | 11,615 |
| L-LL-MSDS-60-23 | G15C282018 | 11,615 |
| L-LL-MSDS-60-23 | G15C282019 | 11,615 |
| L-LL-MSDS-60-23 | G15C282022 | 11,615 |
| L-LL-MSDS-60-23 | G15C283024 | 11,615 |
| L-LL-MSDS-60-23 | G15C283025 | 11,615 |
| L-LL-MSDS-60-23 | G15C283026 | 11,615 |
| L-LL-MSDS-60-23 | G15C283032 | 11,615 |

44,900 lbs.
Total Weight: ~~46,260 LB~~
12 Rolls
Total Packages: ~~139,644~~
Order No.: 28919 Order Date: 05/04/15 Request Date: 06/30/15
Location: GTOWN P.O. No.: 21570
12 Spools - Weld Rod

**REMIT C.O.D. TO:**
**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

**C.O.D.** Amt $

**C.O.D. FEE**
☑ Prepaid
☐ Collect $

*If the shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's or shipper's weight".

† Shipper's imprint in lieu of stamp; not a part of bill of lading approved by the Interstate Commerce Commission.

NOTE: Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property.
**The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding**
$ per

Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement:
The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges.
(Signature of Consignor)

**TOTAL CHARGES $**
Freight charges are PREPAID unless marked collect. ☐ Check box if charges are Collect.

"This is to certify that the above named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation, according to the applicable regulations of the Department of Transportation".

Shipper, Per X Agent, Per

Page 1 of 1
Permanent post office address of shipper

**+ MARK WITH "X" TO DESIGNATE HAZARDOUS MATERIAL AS DEFINED IN TITLE 49 OF FEDERAL REGULATIONS.**
When transporting hazardous materials include the technical or chemical name for n.o.s. (not otherwise specified) or generic description of material with appropriate UN or NA number as defined in US DOT Emergency Response Communication Standard (HM-126C). Provide emergency response phone number in case of incident or accident.

1

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 49 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 9/30/15 |
| QC Inspection by: CP | | QC Date: 9/30/15 | | Inv. Or Packing Slip No.: C00008780 | | Inv. Or Packing Slip Date: 9/29/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,110 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Universal Truckload, Inc | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008780 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,827 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008780
Ship Date: 9/29/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010137 | 2,800.00 |
| 2 | 0064021010138 | 2,800.00 |
| 3 | 0064021010139 | 2,800.00 |
| 4 | 0064021010140 | 2,800.00 |
| 5 | 0064021010141 | 2,800.00 |
| 6 | 0064021010142 | 2,800.00 |
| 7 | 0064021010143 | 2,800.00 |
| 8 | 0064021010144 | 2,800.00 |
| 9 | 0064021010145 | 1,960.00 |
| 10 | 0064021010146 | 2,800.00 |
| 11 | 0064021010147 | 2,800.00 |
| 12 | 0064021010148 | 2,800.00 |
| 13 | 0064021010149 | 2,800.00 |
| 14 | 0064021010150 | 2,800.00 |
| 15 | 0064021010151 | 2,800.00 |
| 16 | 0064021010152 | 2,800.00 |
| 17 | 0064021010153 | 2,800.00 |
| 18 | 0064021010154 | 2,800.00 |
| 19 | 0064021010155 | 2,800.00 |
| 20 | 0064021010156 | 2,800.00 |
| 21 | 0064021010157 | 2,800.00 |
| 22 | 0064021010158 | 2,800.00 |
| 23 | 0064021010159 | 2,800.00 |
| 24 | 0064021010160 | 2,800.00 |
| 25 | 0064021010161 | 2,800.00 |
| 26 | 0064021010162 | 2,800.00 |
| 27 | 0064021010163 | 3,150.00 |

Total Rolls: 27
Total Sq Feet: 75,110.00
Total Weight (lbs): 28,827.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Carolina Garcia | |
| Receive Date | Receiver's Company Name |
| 9-30-15 | ENTACT |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Universal Truckload, Inc.
Date: 9/29/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5848420

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries. Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 50 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/19/15 |
| QC Inspection by: CP | | QC Date: 10/19/15 | | Inv. Or Packing Slip No.: C00008923 | | Inv. Or Packing Slip Date: 10/16/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,810 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Medallion Transport & Logistics, LLC | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008923 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,175 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008923
Ship Date: 10/16/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010191 | 2,800.00 |
| 2 | 0064021010192 | 3,010.00 |
| 3 | 0064021010193 | 2,800.00 |
| 4 | 0064021010194 | 2,800.00 |
| 5 | 0064021010195 | 2,800.00 |
| 6 | 0064021010196 | 2,800.00 |
| 7 | 0064021010197 | 2,800.00 |
| 8 | 0064021010198 | 2,800.00 |
| 9 | 0064021010199 | 2,800.00 |
| 10 | 0064021010200 | 2,800.00 |
| 11 | 0064021010201 | 2,800.00 |
| 12 | 0064021010202 | 2,800.00 |
| 13 | 0064021010203 | 2,800.00 |
| 14 | 0064021010204 | 2,800.00 |
| 15 | 0064021010205 | 2,800.00 |
| 16 | 0064021010206 | 2,800.00 |
| 17 | 0064021010207 | 2,800.00 |
| 18 | 0064021010208 | 2,800.00 |
| 19 | 0064021010209 | 2,800.00 |
| 20 | 0064021010210 | 2,800.00 |
| 21 | 0064021010211 | 2,800.00 |
| 22 | 0064021010213 | 2,800.00 |
| 23 | 0064021010214 | 2,800.00 |
| 24 | 0064021010215 | 2,800.00 |
| 25 | 0064021010216 | 2,800.00 |
| 26 | 0064021010217 | 2,800.00 |
| 27 | 0064021010218 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,810.00
Total Weight (lbs): 29,175.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Medallion Transport & Logistics LLC.
Date: 10/16/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5910099

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 51 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/19/15 |
| QC Inspection by: CP | | QC Date: 10/19/15 | | Inv. Or Packing Slip No.: C00008925 | | Inv. Or Packing Slip Date: 10/17/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (76,160 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Meranu Leasing Inc., DBA Liberty Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008925 | Freight Bill (Pro) No.: Packing List Attached | Weight: | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008925
Ship Date: 10/17/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010219 | 2,800.00 |
| 2 | 0064021010220 | 2,940.00 |
| 3 | 0064021010221 | 2,800.00 |
| 4 | 0064021010222 | 2,800.00 |
| 5 | 0064021010223 | 2,800.00 |
| 6 | 0064021010224 | 2,030.00 |
| 7 | 0064021010225 | 2,800.00 |
| 8 | 0064021010226 | 2,800.00 |
| 9 | 0064021010227 | 2,800.00 |
| 10 | 0064021010228 | 2,800.00 |
| 11 | 0064021010229 | 2,800.00 |
| 12 | 0064021010230 | 2,800.00 |
| 13 | 0064021010231 | 2,800.00 |
| 14 | 0064021010232 | 2,800.00 |
| 15 | 0064021010233 | 2,800.00 |
| 16 | 0064021010234 | 2,800.00 |
| 17 | 0064021010235 | 2,800.00 |
| 18 | 0064021010236 | 2,940.00 |
| 19 | 0064021010237 | 2,800.00 |
| 20 | 0064021010238 | 3,010.00 |
| 21 | 0064021010239 | 2,800.00 |
| 22 | 0064021010240 | 2,940.00 |
| 23 | 0064021010241 | 2,800.00 |
| 24 | 0064021010242 | 3,500.00 |
| 25 | 0064021010243 | 2,800.00 |
| 26 | 0064021010244 | 2,800.00 |
| 27 | 0064021010245 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 76,160.00
Total Weight (lbs): 49,561.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.:
Trucking Co. Phone #:
Broker: Meranu Leasing Inc. DBA Liberty Logistics
Date: 10/17/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919359

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries. Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 52 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/21/15 |
| QC Inspection by: CP | | QC Date: 10/21/15 | | Inv. Or Packing Slip No.: C00008954 | | Inv. Or Packing Slip Date: 10/20/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 29 | 31 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 29 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,390 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ATS Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008954 | Freight Bill (Pro) No.: Packing List Attached | Weight: 30,732 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008954
Ship Date: 10/20/15 10/21/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 00640210101691 | 1,330.00 |
| 2 | 0064021010212 | 1,960.00 |
| 3 | 00640210102121 | 910.00 |
| 4 | 0064021010258 | 1,960.00 |
| 5 | 0064021010274 | 2,800.00 |
| 6 | 0064021010275 | 2,800.00 |
| 7 | 0064021010276 | 2,940.00 |
| 8 | 0064021010277 | 2,100.00 |
| 9 | 00640210102771 | 980.00 |
| 10 | 0064021010278 | 3,640.00 |
| 11 | 0064021010279 | 2,800.00 |
| 12 | 0064021010280 | 2,940.00 |
| 13 | 0064021010281 | 2,800.00 |
| 14 | 0064021010282 | 2,800.00 |
| 15 | 0064021010283 | 3,360.00 |
| 16 | 0064021010284 | 2,800.00 |
| 17 | 0064021010285 | 2,800.00 |
| 18 | 0064021010286 | 2,660.00 |
| 19 | 0064021010288 | 2,800.00 |
| 20 | 0064021010289 | 2,800.00 |
| 21 | 0064021010290 | 2,800.00 |
| 22 | 0064021010291 | 2,800.00 |
| 23 | 0064021010292 | 2,800.00 |
| 24 | 0064021010293 | 2,800.00 |
| 25 | 0064021010294 | 2,800.00 |
| 26 | 0064021010295 | 3,010.00 |
| 27 | 0064021010296 | 2,800.00 |
| 28 | 0064021010297 | 2,800.00 |
| 29 | 0064021010298 | 2,800.00 |

Total Rolls: 29
Total Sq Feet: 75,390.00
Total Weight (lbs): 30,732.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: ROSS
Driver's Sign: _____
Driver's Cell Phone #: 844 2[illegible]
Trucking Co.: [illegible]
Trucking Co. Phone #: _____
Broker: ATS Logistics
Date: 10/20/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919743

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 53 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/21/15 |
| QC Inspection by: CP | | QC Date: 10/21/15 | | Inv. Or Packing Slip No.: C00008937 | | Inv. Or Packing Slip Date: 10/19/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 31 | 33 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 31 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (80,640 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Medallion Transport & Logistics LLC | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008937 | Freight Bill (Pro) No.: Packing List Attached | Weight: 31,321 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008937
Ship Date: 10/19/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 00640210102241 | 840.00 |
| 2 | 0064021010246 | 2,800.00 |
| 3 | 0064021010247 | 2,800.00 |
| 4 | 0064021010248 | 2,800.00 |
| 5 | 0064021010249 | 2,800.00 |
| 6 | 0064021010250 | 3,150.00 |
| 7 | 0064021010251 | 2,800.00 |
| 8 | 0064021010252 | 2,800.00 |
| 9 | 0064021010253 | 2,800.00 |
| 10 | 0064021010254 | 2,800.00 |
| 11 | 0064021010255 | 2,800.00 |
| 12 | 0064021010256 | 2,800.00 |
| 13 | 0064021010257 | 2,800.00 |
| 14 | 00640210102581 | 980.00 |
| 15 | 0064021010259 | 3,150.00 |
| 16 | 0064021010260 | 2,520.00 |
| 17 | 0064021010261 | 2,800.00 |
| 18 | 0064021010262 | 2,800.00 |
| 19 | 0064021010263 | 2,800.00 |
| 20 | 0064021010264 | 2,800.00 |
| 21 | 0064021010265 | 2,800.00 |
| 22 | 0064021010266 | 2,800.00 |
| 23 | 0064021010267 | 2,800.00 |
| 24 | 0064021010268 | 2,800.00 |
| 25 | 0064021010269 | 2,800.00 |
| 26 | 0064021010270 | 2,800.00 |
| 27 | 0064021010271 | 2,800.00 |
| 28 | 0064021010272 | 2,800.00 |
| 29 | 0064021010287 | 1,610.00 |
| 30 | 00640210102871 | 1,190.00 |
| 31 | 0064021010305 | 2,800.00 |

Total Rolls: 31
Total Sq Feet: 80,640.00
Total Weight (lbs): 31,321.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:**

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.:
Trucking Co. Phone #:
Broker: Medallion Transport & Logistics LLC.
Date: 10/19/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919713

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 54 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/22/15 |
| QC Inspection by: CP | | QC Date: 10/22/15 | | Inv. Or Packing Slip No.: C00008956 | | Inv. Or Packing Slip Date: 10/20/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (70,070 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ATS Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008956 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,718 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008956
Ship Date: 10/20/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010273 | 1,680.00 |
| 2 | 00640210102731 | 840.00 |
| 3 | 0064021010299 | 2,800.00 |
| 4 | 0064021010300 | 2,800.00 |
| 5 | 0064021010301 | 3,010.00 |
| 6 | 0064021010302 | 2,800.00 |
| 7 | 0064021010303 | 2,800.00 |
| 8 | 0064021010304 | 2,800.00 |
| 9 | 0064021010306 | 2,800.00 |
| 10 | 0064021010307 | 2,800.00 |
| 11 | 0064021010308 | 2,800.00 |
| 12 | 0064021010309 | 2,940.00 |
| 13 | 0064021010310 | 2,800.00 |
| 14 | 0064021010311 | 1,400.00 |
| 15 | 00640210103111 | 1,400.00 |
| 16 | 0064021010312 | 2,800.00 |
| 17 | 0064021010313 | 2,800.00 |
| 18 | 0064021010314 | 2,800.00 |
| 19 | 0064021010315 | 2,800.00 |
| 20 | 0064021010316 | 2,800.00 |
| 21 | 0064021010317 | 2,800.00 |
| 22 | 0064021010318 | 2,800.00 |
| 23 | 0064021010319 | 2,800.00 |
| 24 | 0064021010320 | 2,800.00 |
| 25 | 0064021010321 | 2,800.00 |
| 26 | 0064021010322 | 2,800.00 |
| 27 | 0064021010324 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 70,070.00
Total Weight (lbs): 28,718.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name _____ Receiver's Signature _____

Receive Date _____ Receiver's Company Name _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: ATS Logistics
Date: 10/20/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919766

Load# 166210

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 54 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/22/15 |
| QC Inspection by: CP | | QC Date: 10/22/15 | | Inv. Or Packing Slip No.: C00008956 | | Inv. Or Packing Slip Date: 10/20/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (70,070 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ATS Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008956 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,718 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008956
Ship Date: 10/20/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010273 | 1,680.00 |
| 2 | 00640210102731 | 840.00 |
| 3 | 0064021010299 | 2,800.00 |
| 4 | 0064021010300 | 2,800.00 |
| 5 | 0064021010301 | 3,010.00 |
| 6 | 0064021010302 | 2,800.00 |
| 7 | 0064021010303 | 2,800.00 |
| 8 | 0064021010304 | 2,800.00 |
| 9 | 0064021010306 | 2,800.00 |
| 10 | 0064021010307 | 2,800.00 |
| 11 | 0064021010308 | 2,800.00 |
| 12 | 0064021010309 | 2,940.00 |
| 13 | 0064021010310 | 2,800.00 |
| 14 | 0064021010311 | 1,400.00 |
| 15 | 00640210103111 | 1,400.00 |
| 16 | 0064021010312 | 2,800.00 |
| 17 | 0064021010313 | 2,800.00 |
| 18 | 0064021010314 | 2,800.00 |
| 19 | 0064021010315 | 2,800.00 |
| 20 | 0064021010316 | 2,800.00 |
| 21 | 0064021010317 | 2,800.00 |
| 22 | 0064021010318 | 2,800.00 |
| 23 | 0064021010319 | 2,800.00 |
| 24 | 0064021010320 | 2,800.00 |
| 25 | 0064021010321 | 2,800.00 |
| 26 | 0064021010322 | 2,800.00 |
| 27 | 0064021010324 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 70,070.00
Total Weight (lbs): 28,718.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name _____ Receiver's Signature _____

Receive Date _____ Receiver's Company Name _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: ATS Logistics
Date: 10/20/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919766

Load# 166210

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

# Appendix H
# GCL to Barrier Wall Connection Logs


Honeywell

STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** 9/16/15 |
|---|---|

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) C-121 | C-309

NTS

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) TYP C-309

NTS

| ***Check applicable Detail:** | **Location:** |
|---|---|
| ☑ Box Cut Dimension<br>☑ Barrier wall clean/exposed<br>☑ Sand Bentonite Mix | - **Hydraulic Barrier Wall stations 9+00 to 10+75 (approximately).**<br>- **South side of the C Street corridor.** |
| **Comments:**<br>- Roll #4109 was placed down the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/15/15.<br>- All strips on the east side of the corridor were placed on 9/15/15. On 9/15/15, Amec and Langan directed Entact to remove the wet SCB plug, and replace it with new GCL and SCB plug mix. The replacement process was completed on 9/16/15. | **Amec Foster Wheeler QA Signature:** B Shea |

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/18/15

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION
NTS
BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER
NTS
G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall stations 6+50 to 6+75 (approximately).**
- **South side of the D Street corridor.**

**Comments:**

- Roll #4070 was placed in the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/18/15.

**Amec Foster Wheeler QA Signature:** B Shea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/24/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall stations 4+00 to 5+00 (approximately).**

**Comments:**

- Roll #4064 was placed.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/24/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 3+25 to 4+00 (approximately)**

**Comments:**

- Rolls #4094 and #4095 were placed.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/25/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 3+00 to 3+25 (approximately)**

**Comments:**

- Rolls #4101 and #4090 were placed.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 9/29/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)
NTS
C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)
NTS
TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 2+30 to 3+00 (approximately)**

**Comments:**

- Rolls #4107, #4108, #4072 and #4110 were placed.

**Amec Foster Wheeler QA Signature:** _____

Honeywell


## STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 10/8/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)
NTS
C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)
NTS
TYP | C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 0 to 2+30 (approximately)**

**Comments:**

- Rolls #4086 and # 4102 were placed.

**Amec Foster Wheeler QA Signature:** _____

Honeywell


# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 8/6/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) C-121 | C-309
NTS

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) TYP C-309
NTS

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **South side of the B Street Corridor**
- **Stations 15+00 to 17+00**

**Comments:**

- Roll #4078 was placed over the sheet pile wall on 8/5/15 and 8/6/15.
- On 8/6/15 Amec Foster Wheeler directed Entact to fold back the GCL in order to ensure clean contact between the GCL and the top of the Hydraulic Barrier Wall.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 8/3/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)

NTS

C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)

NTS

TYP | C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **North side of the B Street Corridor**
- **Stations 14+60 to 15+00**

**Comments:**

- Roll #4078 was placed over the SCB Wall on 8/3/15.
- Entact installed a 45° "buffer" slope from the bottom of the corridor to the top corner of the SCB wall, in order to avoid forming a 90° angle with the GCL at the bottom corner of the wall. This method was approved by Geoff Shallard prior to installation.

**Amec Foster Wheeler QA Signature:** B Shea


Honeywell

STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** 9/9/15 |
|---|---|

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) NTS TYP C-309

| ***Check applicable Detail:** | **Location:** |
|---|---|
| ☑ Box Cut Dimension<br>☑ Barrier wall clean/exposed<br>☑ Sand Bentonite Mix | - **Soil Cement Bentonite Wall stations 8+00 to 8+50 (approximately).**<br>- **North side of the C Street corridor.** |
| **Comments:**<br>- Roll #4109 was placed down the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/9/15.<br>- Roll #4073 was placed on the northwest corner of the corridor slopes, overlapping the SCB Wall on 9/9/15.<br>- Roll #4087 was placed on the northeast corner of the corridor slopes, overlapping the SCB Wall on 9/9/15. | **Amec Foster Wheeler QA Signature:** BShea |


Honeywell

STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** 9/18/15 |
|---|---|

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) NTS TYP C-309

| ***Check applicable Detail:**<br>☑ Box Cut Dimension<br>☑ Barrier wall clean/exposed<br>☑ Sand Bentonite Mix | **Location:**<br>- **Soil Cement Bentonite Wall stations 5+00 to 5+75 (approximately).**<br>- **North side of the D Street corridor** |
|---|---|
| **Comments:**<br>- Roll #4070 was placed in the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/18/15. | **Amec Foster Wheeler QA Signature:** BShea |

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/24/15

QA - GCL to Barrier Wall Connection Detail





TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)

NTS

C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)

NTS

TYP | C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☐ Sand Bentonite Mix

**Location:**

- **Soil Cement Bentonite Wall stations 2+50 to 3+00 (approximately).**

**Comments:**

**Amec Foster Wheeler QA Signature:** _____

Honeywell


## STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 10/8/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) C-121 | C-309
NTS

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) TYP | C-309
NTS

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Soil Cement Bentonite Wall stations 0+00 to 2+50 (approximately).**

**Comments:**

- Rolls #4071 and #4102 were placed over the SCB Wall.

**Amec Foster Wheeler QA Signature:** _____

# Appendix I
# ESI Panel Placement Logs

INDEPENDENT CQA MONITOR

7/20/15

Daily Panel Placement

Page 1

**Project Name:** HONEYWELL Job # 12-11-1399 Deployment Date 7-20-15

**Superintendent:** FORTINO AYALA Material Type: LLDPE 60 MIL


☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other: CAP CONSTRUCTION

**Description** (i.e. Phase #, Cell #, Pond # etc.)

**Roll Stock Width** 23

**Panel # 1** | Roll # G15C283031

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,645 -
Lineal Feet Trench

**Panel # 2** | Roll # G15C283031

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,656.25 -
Lineal Feet Trench

**Panel # 3** | Roll # G15C283031

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,690 -
Lineal Feet Trench

**Panel # 4** | Roll # G15C292021

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF




Notes:

Initial SF -
Final SF 3,712.5 -
Lineal Feet Trench

**Panel # | Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF -
Final SF -
Lineal Feet Trench

**Panel # | Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF -
Final SF -
Lineal Feet Trench

**Panel # | Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF -
Final SF -
Lineal Feet Trench

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | - | SF |
| **Total Pay Area This Page** | - | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | - | SF |
| Total Panel SF To Date | - | SF |
| **Total Pay Area To Date Including Anchor Trench** | - | |
| Initial Quantity Previous | - | SF |
| Initial Quantity This Page | - | SF |
| Initial Quantity To Date | - | SF |

14,703.75 ☒

7/21/15

INDEPENDENT CQA MONITOR

**Daily Panel Placement** Page 2.

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date**


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap [X] **Other:**

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 22.5

**Panel #** 5 **Roll #** G15C282021

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,678.75 -
Lineal Feet Trench

**Panel #** 6 **Roll #** G15C282021

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,555 -
Lineal Feet Trench

**Panel #** 7 **Roll #** G15C277065

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 112.5 -
Lineal Feet Trench

**Panel #** 8 **Roll #** G15C277065

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,667.5 -
Lineal Feet Trench

**Panel #** 9 **Roll #** G15C277065

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,667.5 -
Lineal Feet Trench

**Panel #** **Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF




Notes:

Initial SF -
Final SF -
Lineal Feet Trench

**Panel #** **Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF




Notes:

Initial SF -
Final SF -
Lineal Feet Trench

**Panel #** **Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF



Notes:

Initial SF -
Final SF -
Lineal Feet Trench

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | **SF** |
| **Total Panel SF This Page** | - | **SF** |
| **Total Pay Area This Page** | - | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | - | SF |
| Total Panel SF To Date | - | SF |
| **Total Pay Area To Date Including Anchor Trench** | - | |
| Initial Quantity Previous | - | SF |
| Initial Quantity This Page | - | SF |
| Initial Quantity To Date | - | SF |

14,680.5

INDEPENDENT CQA MONITOR 7/22/15

## Daily Panel Placement

Page 3

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/22/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

Primary Secondary Cell Pond Cap [X] Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 10** | Roll # G15C282018

| | | |
|---|---|---|
| Final Length Avg. | 163.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,668 | |

**Panel # 11** | Roll # G15C282018

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel # 12** | Roll # G15C282018

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel # 13** | Roll # G15C276052

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel # / Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel # / Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel # / Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel # / Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | **-** | **SF** |
| **Total Panel SF This Page** | **14,726** | **SF** |
| **Total Pay Area This Page** | **14,726** | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 29,385 | SF |
| Total Panel SF To Date | 44,111 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **44,111** | |
| Initial Quantity Previous | 30,452 | SF |
| Initial Quantity This Page | 15,226 | SF |
| Initial Quantity To Date | 45,678 | SF |

INDEPENDENT CQA MONITOR 7-23-15

## Daily Panel Placement

Page 4

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/23/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 14** Roll # G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel # 15** Roll # G15C276052

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,701 | |

**Panel # 16** Roll # G15C277064

| | | |
|---|---|---|
| Final Length Avg. | 165.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,713 | |

**Panel # 17** Roll # G15C277064

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,830 | Lineal Feet Trench |
| Final SF | 3,701 | |

**Panel # 18** Roll # G15C277064

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel #** Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **18,495** | SF |
| **Total Pay Area This Page** | **18,495** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 44,111 | SF |
| Total Panel SF To Date | 62,606 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **62,606** | |
| Initial Quantity Previous | 45,678 | SF |
| Initial Quantity This Page | 19,171 | SF |
| Initial Quantity To Date | 64,849 | SF |

7/24/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 5

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/24/15

**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Notes: | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|---|
| 19 | G15C276056 | 164.00 LF | 22.50 LF | 166.00 LF | 23.00 LF | 166 / 164 / 164 / 166; 23 / 22.5 / 22.5 / 23 | 3,818 | 3,690 | |
| 20 | G15C276056 | 164.00 LF | 22.50 LF | 166.50 LF | 23.00 LF | 166 / 164 / 164 / 167; 23 / 22.5 / 22.5 / 23 | 3,830 | 3,690 | |
| 21 | G15C276056 | 164.00 LF | 22.50 LF | 166.50 LF | 23.00 LF | 167 / 164 / 164 / 166; 23 / 22.5 / 22.5 / 23 | 3,830 | 3,690 | |
| 22 | G15C277061 | 164.00 LF | 22.50 LF | 166.00 LF | 23.00 LF | 166 / 164 / 164 / 166; 23 / 22.5 / 22.5 / 23 | 3,818 | 3,690 | |
| 23 | G15C277061 | 164.00 LF | 22.50 LF | 166.00 LF | 23.00 LF | 166 / 164 / 164 / 166; 23 / 22.5 / 22.5 / 23 | 3,818 | 3,690 | |
| 24 | G15C277061 | 164.00 LF | 22.50 LF | 166.00 LF | 23.00 LF | 166 / 164 / 164 / 166; 23 / 22.5 / 22.5 / 23 | 3,818 | 3,690 | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **22,140** | SF |
| **Total Pay Area This Page** | **22,140** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 62,606 | SF |
| Total Panel SF To Date | 84,746 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **84,746** | |
| Initial Quantity Previous | 64,849 | SF |
| Initial Quantity This Page | 22,931 | SF |
| Initial Quantity To Date | 87,780 | SF |

7/29/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 6

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/28/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 25 | Roll # G15C277059 |
|---|---|
| Final Length Avg. | 163.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.50 LF |
| Initial Width Avg. | 23.00 LF |
| Notes: | |
| Initial SF | 3,807 |
| Final SF | 3,679 |
| Lineal Feet Trench | |

| Panel # 26 | Roll # G15C277059 |
|---|---|
| Final Length Avg. | 163.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.00 LF |
| Initial Width Avg. | 23.00 LF |
| Notes: | |
| Initial SF | 3,795 |
| Final SF | 3,668 |
| Lineal Feet Trench | |

| Panel # 27 | Roll # G15C277059 |
|---|---|
| Final Length Avg. | 163.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.50 LF |
| Initial Width Avg. | 23.00 LF |
| Notes: | |
| Initial SF | 3,784 |
| Final SF | 3,668 |
| Lineal Feet Trench | |

| Panel # 28 | Roll # G15C283028 |
|---|---|
| Final Length Avg. | 163.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.50 LF |
| Initial Width Avg. | 23.00 LF |
| Notes: | |
| Initial SF | 3,784 |
| Final SF | 3,679 |
| Lineal Feet Trench | |

| Panel # 29 | Roll # G15C283028 |
|---|---|
| Final Length Avg. | 164.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.00 LF |
| Initial Width Avg. | 23.00 LF |
| Notes: | |
| Initial SF | 3,795 |
| Final SF | 3,690 |
| Lineal Feet Trench | |

| Panel # 30 | Roll # G15C283028 |
|---|---|
| Final Length Avg. | 164.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.50 LF |
| Initial Width Avg. | 23.00 LF |
| Notes: | |
| Initial SF | 3,807 |
| Final SF | 3,690 |
| Lineal Feet Trench | |

| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |
| Notes: | |
| Initial SF | - |
| Final SF | - |
| Lineal Feet Trench | |

| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |
| Notes: | |
| Initial SF | - |
| Final SF | - |
| Lineal Feet Trench | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | 22,073 | SF |
| **Total Pay Area This Page** | 22,073 | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 84,746 | SF |
| Total Panel SF To Date | 106,819 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **106,819** | |
| Initial Quantity Previous | 87,780 | SF |
| Initial Quantity This Page | 22,770 | SF |
| Initial Quantity To Date | 110,550 | SF |

07/30/15

INDEPENDENT QA
MONITOR

## Daily Panel Placement

Page 7

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/29/15

**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|
| 31 | G15C282015 | 163.50 LF | 22.50 LF | 165.00 LF | 23.00 LF | 3,795 | 3,679 | |
| 32 | G15C282015 | 163.00 LF | 22.50 LF | 164.50 LF | 23.00 LF | 3,784 | 3,668 | |
| 33 | G15C282015 | 163.00 LF | 22.50 LF | 165.00 LF | 23.00 LF | 3,795 | 3,668 | |
| 34 | G15C276055 | 163.50 LF | 22.50 LF | 165.50 LF | 23.00 LF | 3,807 | 3,679 | |
| | | LF | LF | LF | LF | - | - | |
| | | LF | LF | LF | LF | - | - | |
| | | LF | LF | LF | LF | - | - | |
| | | LF | LF | LF | LF | - | - | |

Notes:

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,693** | SF |
| **Total Pay Area This Page** | **14,693** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 106,819 | SF |
| Total Panel SF To Date | 121,511 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **121,511** | |
| Initial Quantity Previous | 110,550 | SF |
| Initial Quantity This Page | 15,180 | SF |
| Initial Quantity To Date | 125,730 | SF |

8/4/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 8

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/03/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary **Secondary** ☐ **Cell** ☐ **Pond** ☐ **Cap** ☒ **Other:**

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 35 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 94.00 | LF |
| Final Width Avg. | 21.50 | LF |
| Initial Length Avg. | 95.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,185 | Lineal Feet Trench | |
| Final SF | 2,021 | | |

### Panel # 36 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 94.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 95.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,197 | Lineal Feet Trench | |
| Final SF | 2,126 | | |

### Panel # 37 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 96.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 98.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,254 | Lineal Feet Trench | |
| Final SF | 2,171 | | |

### Panel # 38 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 99.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 101.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,335 | Lineal Feet Trench | |
| Final SF | 2,239 | | |

### Panel # 39 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 101.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 103.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,369 | Lineal Feet Trench | |
| Final SF | 2,284 | | |

### Panel # 40 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 100.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 101.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,335 | Lineal Feet Trench | |
| Final SF | 2,261 | | |

### Panel # 41 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 35.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 37.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 851 | Lineal Feet Trench | |
| Final SF | 788 | | |

### Panel # 42 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 167.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,758 | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **17,647** | SF |
| **Total Pay Area This Page** | **17,647** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 121,511 | SF |
| Total Panel SF To Date | 139,159 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **139,159** | |
| Initial Quantity Previous | 125,730 | SF |
| Initial Quantity This Page | 18,412 | SF |
| Initial Quantity To Date | 144,141 | SF |

8/4/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 9

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/03/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 43 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 35.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 36.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 840 | Lineal Feet Trench | |
| Final SF | 799 | | |

Notes:

| Panel # 44 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 56.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 57.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,323 | Lineal Feet Trench | |
| Final SF | 1,260 | | |

Notes:

| Panel # 45 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 25.00 | LF | |
| Final Width Avg. | 10.00 | LF | |
| Initial Length Avg. | 28.00 | LF | |
| Initial Width Avg. | 11.00 | LF | |
| Initial SF | 308 | Lineal Feet Trench | |
| Final SF | 250 | | |

Notes:

| Panel # 46 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 27.00 | LF | |
| Final Width Avg. | 10.00 | LF | |
| Initial Length Avg. | 28.00 | LF | |
| Initial Width Avg. | 11.50 | LF | |
| Initial SF | 322 | Lineal Feet Trench | |
| Final SF | 270 | | |

Notes:
TRIM OFF P-45

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

Notes:

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

Notes:

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

Notes:

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **2,579** | SF |
| **Total Pay Area This Page** | **2,579** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 139,159 | SF |
| Total Panel SF To Date | 141,737 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **141,737** | |
| Initial Quantity Previous | 144,141 | SF |
| Initial Quantity This Page | 2,792 | SF |
| Initial Quantity To Date | 146,933 | SF |

8/7/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 10

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/05/15

**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Initial SF | Final SF |
|---|---|---|---|---|---|---|---|
| 47 | G15C276053 | 167.00 LF | 22.50 LF | 168.50 LF | 23.00 LF | 3,876 | 3,758 |
| 48 | G15C276053 | 167.00 LF | 22.50 LF | 168.00 LF | 23.00 LF | 3,864 | 3,758 |
| 49 | G15C283033 | 167.00 LF | 22.50 LF | 168.00 LF | 23.00 LF | 3,864 | 3,758 |

Panel 47 Notes: 23 / 22.5 / 169 167 167 168 / 22.5 / 23

Panel 48 Notes: 23 / 22.5 / 168 167 167 168 / 22.5 / 23

Panel 49 Notes: 23 / 22.5 / 168 167 167 168 / 22.5 / 23

Lineal Feet Trench

| Panel # | Roll # | Initial SF | Final SF |
|---|---|---|---|
| | | - | - |
| | | - | - |
| | | - | - |

Notes:

Lineal Feet Trench

| Panel # | Roll # | Initial SF | Final SF |
|---|---|---|---|
| | | - | - |
| | | - | - |

Notes:

Lineal Feet Trench

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **11,273** | SF |
| **Total Pay Area This Page** | **11,273** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 141,737 | SF |
| Total Panel SF To Date | 153,010 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **153,010** | |
| Initial Quantity Previous | 146,933 | SF |
| Initial Quantity This Page | 11,604 | SF |
| Initial Quantity To Date | 158,537 | SF |

8/7/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 11

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/06/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 50** | **Roll #** G15C283033

| | | |
|---|---|---|
| Final Length Avg. | 167.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 168.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,876 | Lineal Feet Trench |
| Final SF | 3,769 | |

**Panel # 51** | **Roll #** G15C283033

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,784 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel # 52** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 5.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 6.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 138 | Lineal Feet Trench |
| Final SF | 113 | |

**Panel # 53** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,899 | Lineal Feet Trench |
| Final SF | 3,780 | |

**Panel # 54** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,780 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **15,120** | SF |
| **Total Pay Area This Page** | **15,120** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 153,010 | SF |
| Total Panel SF To Date | 168,130 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **168,130** | |
| Initial Quantity Previous | 158,537 | SF |
| Initial Quantity This Page | 15,583 | SF |
| Initial Quantity To Date | 174,119 | SF |

8/10/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 12

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/07/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 55** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 157.00 | LF |
| Final Width Avg. | 11.25 | LF |
| Initial Length Avg. | 158.00 | LF |
| Initial Width Avg. | 11.50 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 1,817 | Lineal Feet Trench | |
| Final SF | 1,766 | | |

**Panel # 56** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 11.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 12.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 288 | Lineal Feet Trench | |
| Final SF | 248 | | |

**Panel # 57** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 167.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,769 | | |

**Panel # 58** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 168.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,864 | Lineal Feet Trench | |
| Final SF | 3,735 | | |

**Panel # 59** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 150.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 151.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,473 | Lineal Feet Trench | |
| Final SF | 3,375 | | |

**Panel # 60** | **Roll #** G15C276053

| | | |
|---|---|---|
| Final Length Avg. | 15.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 16.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 380 | Lineal Feet Trench | |
| Final SF | 338 | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **13,230** | SF |
| **Total Pay Area This Page** | **13,230** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 168,130 | SF |
| Total Panel SF To Date | 181,360 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **181,360** | |
| Initial Quantity Previous | 174,119 | SF |
| Initial Quantity This Page | 13,708 | SF |
| Initial Quantity To Date | 187,827 | SF |

8/13/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 13


**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/10/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23


| Panel # 61 | Roll # G15C282011 |
|---|---|
| Final Length Avg. | 164.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 166.00 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,818 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,701 | |


| Panel # 62 | Roll # G15C282011 |
|---|---|
| Final Length Avg. | 163.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.00 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,795 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,679 | |


| Panel # 63 | Roll # G15C282011 |
|---|---|
| Final Length Avg. | 163.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.50 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,784 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,668 | |


| Panel # 64 | Roll # G15C282013 |
|---|---|
| Final Length Avg. | 162.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.50 LF |
| Initial Width Avg. | 23.00 LF |




Notes:
190 SQ FT OFF P-64
.CORRECTED

| Initial SF | 3,784 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,467 | |


| Panel # 65 | Roll # G15C282013 |
|---|---|
| Final Length Avg. | 162.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.00 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,772 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,645 | |


| Panel # 66 | Roll # G15C282013 |
|---|---|
| Final Length Avg. | 15.50 LF |
| Final Width Avg. | 12.25 LF |
| Initial Length Avg. | 16.50 LF |
| Initial Width Avg. | 13.00 LF |




Notes:

| Initial SF | 215 | Lineal Feet Trench |
|---|---|---|
| Final SF | 190 | |


| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |

| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **18,349** | SF |
| **Total Pay Area This Page** | **18,349** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 181,360 | SF |
| Total Panel SF To Date | 199,709 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **199,709** | |
| Initial Quantity Previous | 187,827 | SF |
| Initial Quantity This Page | 19,167 | SF |
| Initial Quantity To Date | 206,994 | SF |

8/14/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 14

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/13/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

[ ] Primary [ ] Secondary [ ] Cell [ ] Pond [X] Cap [ ] Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 67** | **Roll #** G15C282013

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,761 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 68** | **Roll #** G15C282020

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 69** | **Roll #** G15C282020

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 70** | **Roll #** G15C282020

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 71** | **Roll #** G15C277062

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,761 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | 18,225 | SF |
| **Total Pay Area This Page** | 18,225 | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 199,709 | SF |
| Total Panel SF To Date | 217,934 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **217,934** | |
| Initial Quantity Previous | 206,994 | SF |
| Initial Quantity This Page | 18,768 | SF |
| Initial Quantity To Date | 225,762 | SF |

8/17/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 15

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/14/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary **Secondary** ☐ **Cell** ☐ **Pond** ☐ **Cap** ☒ **Other:**

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 72** | **Roll #** G15C277062

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel # 73** | **Roll #** G15C277062

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel # 74** | **Roll #** G15C276054

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,807 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel # 75** | **Roll #** G15C276054

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,704** | SF |
| **Total Pay Area This Page** | **14,704** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 217,934 | SF |
| Total Panel SF To Date | 232,638 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **232,638** | |
| Initial Quantity Previous | 225,762 | SF |
| Initial Quantity This Page | 15,169 | SF |
| Initial Quantity To Date | 240,930 | SF |

INDEPENDENT CQA MONITOR

9/16/15

## Daily Panel Placement

Page 16

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/09/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 76** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 78.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 79.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 1,817 | Lineal Feet Trench | |
| Final SF | 1,755 | | |

**Panel # 77** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 81.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 82.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 1,886 | Lineal Feet Trench | |
| Final SF | 1,823 | | |

**Panel # 78** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 84.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 87.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,001 | Lineal Feet Trench | |
| Final SF | 1,890 | | |

**Panel # 79** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 84.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 87.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,001 | Lineal Feet Trench | |
| Final SF | 1,890 | | |

**Panel # 80** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 83.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 84.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 1,944 | Lineal Feet Trench | |
| Final SF | 1,879 | | |

**Panel # 81** Roll # G15C276054

| | | |
|---|---|---|
| Final Length Avg. | 82.50 | LF |
| Final Width Avg. | 21.75 | LF |
| Initial Length Avg. | 85.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 1,955 | Lineal Feet Trench | |
| Final SF | 1,794 | | |

**Panel # 82** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 28.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 29.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 667 | Lineal Feet Trench | |
| Final SF | 630 | | |

**Panel # 83** Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 26.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 27.00 | LF |
| Initial Width Avg. | 23.00 | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | 621 | Lineal Feet Trench | |
| Final SF | 585 | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | **-** | **SF** |
| **Total Panel SF This Page** | **12,246** | **SF** |
| **Total Pay Area This Page** | **12,246** | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 232,638 | SF |
| Total Panel SF To Date | 244,884 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **244,884** | |
| Initial Quantity Previous | 240,930 | SF |
| Initial Quantity This Page | 12,892 | SF |
| Initial Quantity To Date | 253,822 | SF |

9/16/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 17

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/09/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Notes: | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|---|
| 84 | G15C276054 | 35.00 LF | 22.50 LF | 36.00 LF | 23.00 LF | | 828 | 788 | |
| 85 | G15C276054 | 17.00 LF | 5.00 LF | 18.00 LF | 11.50 LF | TRIM FROM P-85 | 207 | 85 | |
| 86 | G15C276054 | 10.00 LF | 5.00 LF | 11.00 LF | 11.50 LF | | 127 | 50 | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **923** | SF |
| **Total Pay Area This Page** | **923** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 244,884 | SF |
| Total Panel SF To Date | 245,806 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **245,806** | |
| Initial Quantity Previous | 253,822 | SF |
| Initial Quantity This Page | 1,162 | SF |
| Initial Quantity To Date | 254,983 | SF |

9/16/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 18

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/15/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 87 — Roll # G15C282012

| | | |
|---|---|---|
| Final Length Avg. | 166.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,853 | Lineal Feet Trench | |
| Final SF | 3,746 | | |

### Panel # 88 — Roll # G15C282012

| | | |
|---|---|---|
| Final Length Avg. | 167.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,769 | | |

### Panel # 89 — Roll # G15C282012

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 170.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,910 | Lineal Feet Trench | |
| Final SF | 3,780 | | |

### Panel # 90 — Roll # G15C276058

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,780 | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **15,075** | SF |
| **Total Pay Area This Page** | **15,075** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 245,806 | SF |
| Total Panel SF To Date | 260,881 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **260,881** | |
| Initial Quantity Previous | 254,983 | SF |
| Initial Quantity This Page | 15,537 | SF |
| Initial Quantity To Date | 270,520 | SF |

D136 9/18/15 Independent QA Monitor

## Daily Panel Placement

Page 19

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/16/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 91** | Roll # G15C276058

| | | |
|---|---|---|
| Final Length Avg. | 167.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 168.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,876 | Lineal Feet Trench |
| Final SF | 3,758 | |

**Panel # 92** | Roll # G15C276058

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,735 | |

**Panel # 93** | Roll # G15C283026

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,735 | |

**Panel # 94** | Roll # G15C283026

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,735 | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | **-** | **SF** |
| **Total Panel SF This Page** | **14,963** | **SF** |
| **Total Pay Area This Page** | **14,963** | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 261,032 | SF |
| Total Panel SF To Date | 275,995 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **275,995** | |
| Initial Quantity Previous | 270,559 | SF |
| Initial Quantity This Page | 15,399 | SF |
| Initial Quantity To Date | 285,958 | SF |

9/18/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 20

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/17/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Notes: | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|---|
| 95 | G15C283026 | 166.00 LF | 12.50 LF | 167.00 LF | 23.00 LF | 23 / 22.5 / 167 166 166 167 / 2.5 / 23 | 3,841 | 2,075 | |
| 96 | G15C276057 | 166.00 LF | 22.50 LF | 168.00 LF | 23.00 LF | 23 / 22.5 / 168 166 166 168 / 22.5 / 23 | 3,864 | 3,735 | |
| 97 | G15C276057 | 166.00 LF | 22.50 LF | 168.00 LF | 23.00 LF | 23 / 22.5 / 168 166 166 168 / 22.5 / 23 | 3,864 | 3,735 | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |
| | | | | | | | - | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **9,545** | SF |
| **Total Pay Area This Page** | **9,545** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 275,995 | SF |
| Total Panel SF To Date | 285,540 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **285,540** | |
| Initial Quantity Previous | 285,958 | SF |
| Initial Quantity This Page | 11,569 | SF |
| Initial Quantity To Date | 297,527 | SF |

9/21/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 21


**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/18/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:


**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 98 | Roll # G15C276057 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,530 | | |





Notes:

| Panel # 99 | Roll # G15C276057 | | |
|---|---|---|---|
| Final Length Avg. | 68.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,541 | | |





Notes:

| Panel # 100 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,541 | | |





Notes:

| Panel # 101 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,622 | Lineal Feet Trench | |
| Final SF | 1,530 | | |





Notes:

| Panel # 102 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,530 | | |





Notes:

| Panel # 103 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,530 | | |





Notes:

| Panel # 104 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 29.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 30.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 702 | Lineal Feet Trench | |
| Final SF | 664 | | |




Notes:

| Panel # 105 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 26.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 27.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 633 | Lineal Feet Trench | |
| Final SF | 596 | | |




Notes:

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **10,463** | SF |
| **Total Pay Area This Page** | **10,463** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 285,540 | SF |
| Total Panel SF To Date | 296,002 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **296,002** | |
| Initial Quantity Previous | 297,527 | SF |
| Initial Quantity This Page | 11,006 | SF |
| Initial Quantity To Date | 308,532 | SF |

9/21/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 22

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/18/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Notes: | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|---|
| 106 | G15C282022 | 31.00 LF | 22.50 LF | 32.50 LF | 23.00 LF | 23 / 22.5 / 27 / 26 / 36 / 38 / 22.5 / 23 | 748 | 698 | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **698** | SF |
| **Total Pay Area This Page** | **698** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 296,002 | SF |
| Total Panel SF To Date | 296,700 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **296,700** | |
| Initial Quantity Previous | 308,532 | SF |
| Initial Quantity This Page | 748 | SF |
| Initial Quantity To Date | 309,280 | SF |

9/23/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 23

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/22/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 107** | Roll # G15C283024

| | | |
|---|---|---|
| Final Length Avg. | 163.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,784 | Lineal Feet Trench |
| Final SF | 3,668 | |

**Panel # 108** | Roll # G15C283024

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel # 109** | Roll # G15C283024

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel # 110** | Roll # G15C282016

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,625** | SF |
| **Total Pay Area This Page** | **14,625** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 298,360 | SF |
| Total Panel SF To Date | 312,985 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **312,985** | |
| Initial Quantity Previous | 309,280 | SF |
| Initial Quantity This Page | 15,100 | SF |
| Initial Quantity To Date | 324,379 | SF |

INDEPENDENT CQA MONITOR

9/24/15

## Daily Panel Placement

Page 24

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/23/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Notes: | Initial SF | Final SF |
|---|---|---|---|---|---|---|---|---|
| 111 | G15C282016 | 162.00 LF | 22.50 LF | 164.00 LF | 23.00 LF | 164 / 162 / 162 / 164; 22.5 / 23 / 22.5 / 23 | 3,772 | 3,645 |
| 112 | G15C282016 | 162.00 LF | 22.50 LF | 163.00 LF | 23.00 LF | 163 / 162 / 162 / 163; 22.5 / 23 / 22.5 / 23 | 3,749 | 3,645 |
| 113 | G15C283032 | 162.00 LF | 22.50 LF | 163.00 LF | 23.00 LF | 163 / 162 / 162 / 163; 22.5 / 23 / 22.5 / 23 | 3,749 | 3,645 |
| 114 | G15C283032 | 161.50 LF | 22.50 LF | 113.00 LF | 23.00 LF | 163 / 162 / 161 / 63; 22.5 / 23 / 22.5 / 23 | 2,599 | 3,634 |
| | | LF | LF | LF | LF | | - | - |
| | | LF | LF | LF | LF | | - | - |
| | | LF | LF | LF | LF | | - | - |
| | | LF | LF | LF | LF | | - | - |

Lineal Feet Trench

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,569** | SF |
| **Total Pay Area This Page** | **14,569** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 312,985 | SF |
| Total Panel SF To Date | 327,553 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **327,553** | |
| Initial Quantity Previous | 324,379 | SF |
| Initial Quantity This Page | 13,869 | SF |
| Initial Quantity To Date | 338,248 | SF |

9/28/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 25

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/24/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 115** | **Roll #** G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 161.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,634 | |

**Panel # 116** | **Roll #** G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel # 117** | **Roll #** G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel # 118** | **Roll #** G15C283025

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,701 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,681** | SF |
| **Total Pay Area This Page** | **14,681** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 327,553 | SF |
| Total Panel SF To Date | 342,235 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **342,235** | |
| Initial Quantity Previous | 338,248 | SF |
| Initial Quantity This Page | 15,134 | SF |
| Initial Quantity To Date | 353,382 | SF |

10/6/15

INDEPENDENT C&A MONITOR

## Daily Panel Placement

Page 26

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/25/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 119** | **Roll #** G15C283025

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,701 | |

**Panel # 120** | **Roll #** G15C283025

| | | |
|---|---|---|
| Final Length Avg. | 165.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.50 | LF |
| Initial Width Avg. | 23.00 | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | 3,830 | Lineal Feet Trench |
| Final SF | 3,724 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |

Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |

Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |

Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |

Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |

Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **7,425** | SF |
| **Total Pay Area This Page** | **7,425** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 342,235 | SF |
| Total Panel SF To Date | 349,660 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **349,660** | |
| Initial Quantity Previous | 353,382 | SF |
| Initial Quantity This Page | 7,648 | SF |
| Initial Quantity To Date | 361,030 | SF |

10/7/15 | INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 27

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/29/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 121 — Roll # G15C283030

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 170.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,910 | Lineal Feet Trench | |
| Final SF | 3,735 | | |

### Panel # 122 — Roll # G15C283030

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 171.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,933 | Lineal Feet Trench | |
| Final SF | 3,735 | | |

### Panel # 123 — Roll # G15C283030

| | | |
|---|---|---|
| Final Length Avg. | 148.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 150.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,450 | Lineal Feet Trench | |
| Final SF | 3,330 | | |

### Panel # 124 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 18.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 19.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 437 | Lineal Feet Trench | |
| Final SF | 405 | | |

### Panel # 125 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench | |
| Final SF | 3,690 | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

### Material in Anchor Trench

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,895** | SF |
| **Total Pay Area This Page** | **14,895** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 349,660 | SF |
| Total Panel SF To Date | 364,555 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **364,555** | |
| Initial Quantity Previous | 361,030 | SF |
| Initial Quantity This Page | 15,525 | SF |
| Initial Quantity To Date | 376,555 | SF |

10/12/15

INDEPENDENT CQA MONITOR

**Daily Panel Placement** Page 28

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 10/08/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 126** Roll # G15C283027

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 4 FEET EXTRA REQUESTED BY CUSTOMER. (SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel # 127** Roll # G152823027

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 4 FEET EXTRA REQUESTED BY CUSTOMER ( SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 128** Roll # G15C283027

| | | |
|---|---|---|
| Final Length Avg. | 149.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 150.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 4 FEET EXTRA REQUESTED BY CUSTOMER ( SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 3,450 | Lineal Feet Trench |
| Final SF | 3,353 | |

**Panel # 129** Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 12.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 17.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 5 FEET EXTRA REQUESTED MY CUSTOMER. (SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 391 | Lineal Feet Trench |
| Final SF | 270 | |

**Panel # 130** Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 4.00 | LF |
| Final Width Avg. | 20.00 | LF |
| Initial Length Avg. | 9.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 207 | Lineal Feet Trench |
| Final SF | 80 | |

**Panel # 131** Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 8.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 11.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 265 | Lineal Feet Trench |
| Final SF | 180 | |

**Panel # 132** Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 160.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 5 FEET

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,600 | |

**Panel # 133** Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | 173 | Lineal Feet Trench |
| Final SF | 133 | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | 14,939 | SF |
| **Total Pay Area This Page** | 14,939 | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 364,555 | SF |
| Total Panel SF To Date | 379,494 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **379,494** | |
| Initial Quantity Previous | 376,555 | SF |
| Initial Quantity This Page | 16,055 | SF |
| Initial Quantity To Date | 392,609 | SF |

10/12/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 29

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 10/08/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 134** | **Roll # G15C282014**

| | | |
|---|---|---|
| Final Length Avg. | 38.00 | LF |
| Final Width Avg. | 7.00 | LF |
| Initial Length Avg. | 39.00 | LF |
| Initial Width Avg. | 8.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 312 | Lineal Feet Trench |
| Final SF | 266 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **266** | SF |
| **Total Pay Area This Page** | **266** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 379,494 | SF |
| Total Panel SF To Date | 379,760 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **379,760** | |
| Initial Quantity Previous | 392,609 | SF |
| Initial Quantity This Page | 312 | SF |
| Initial Quantity To Date | 392,921 | SF |

# Appendix J
# ESI Trial Weld Logs

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/20/15 | 17:03 | MODESTO L. | 2003 | 650 | 860 | | 95 | Peel | 96 | 101 | 95 | 109 | 99 | 99 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 102 | | 109 | | 105 | | | | | | |
| 7/21/15 | 6:50 | EMMANUEL V. | EXT 512 | | 530 | 530 | 80 | Peel | 96 | | 94 | | 98 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 99 | | 98 | | 98 | | | | | | |
| 7/21/15 | 13:45 | MODESTO L. | 2003 | 650 | 860 | | 93 | Peel | 102 | 97 | 102 | 98 | 100 | 102 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 103 | | 96 | | 105 | | | | | | |
| 7/21/15 | 14:09 | MODESTO L. | 2003 | 500 | 860 | | 93 | Peel | 95 | 99 | 95 | 100 | 98 | 101 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 102 | | 103 | | 92 | | | | | | |
| 7/21/15 | 15:14 | MODESTO L. | 2003 | 550 | 860 | | 90 | Peel | 89 | 92 | 90 | 85 | 89 | 91 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 98 | | 94 | | 98 | | | | | | |
| 7/22/15 | 6:37 | EMMANUEL V. | EXT 512 | | 500 | 490 | 70 | Peel | 98 | | 94 | | 93 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 117 | | 117 | | 118 | | | | | | |
| 7/22/15 | 13:14 | MODESTO L. | 2003 | 650 | 860 | | 83 | Peel | 100 | 99 | 107 | 95 | 102 | 104 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 117 | | 115 | | 116 | | | | | | |
| 7/22/15 | 14:58 | MODESTO L. | 2003 | 550 | 860 | | 84 | Peel | 92 | 98 | 97 | 98 | 90 | 103 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 125 | | 121 | | 118 | | | | | | |
| 7/23/15 | 13:19 | MODESTO L. | 2003 | 650 | 860 | | 83 | Peel | 107 | 102 | 107 | 103 | 107 | 98 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 116 | | 106 | | 112 | | | | | | |
| 7/23/15 | 13:25 | MODESTO L. | 2003 | 550 | 860 | | 83 | Peel | 127 | 118 | 123 | 122 | 123 | 116 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 130 | | 125 | | 130 | | | | | | |
| 7/24/15 | 6:50 | EMMANUEL V. | EXT 512 | | 500 | 490 | 69 | Peel | 90 | | 112 | | 103 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 127 | | 127 | | 128 | | | | | | |
| 7/24/15 | 13:14 | MODESTO L. | 2003 | 650 | 860 | | 83 | Peel | 97 | 101 | 96 | 106 | 103 | 101 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 120 | | 122 | | 119 | | | | | | |
| 7/24/15 | 13:17 | MODESTO L. | 2003 | 500 | 860 | | 83 | Peel | 96 | 101 | 101 | 106 | 96 | 105 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 117 | | 111 | | 118 | | | | | | |
| 7/24/15 | 13:21 | MODESTO L. | 2003 | 550 | 860 | | 83 | Peel | 93 | 102 | 97 | 100 | 105 | 95 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 111 | | 111 | | 110 | | | | | | |
| 7/27/15 | 13:15 | EMMANUEL V. | EXT 512 | | 500 | 450 | 85 | Peel | 122 | | 122 | | 121 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 118 | | 125 | | 126 | | | | | | |
| 7/28/15 | 7:00 | EMMANUEL V. | EXT 512 | | 500 | 450 | 75 | Peel | 102 | | 102 | | 107 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 137 | | 132 | | 131 | | | | | | |

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/28/15 | 13:14 | MODESTO L. | 2003 | 650 | 860 | | 90 | Peel | 99 | 101 | 96 | 94 | 97 | 94 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 103 | | 110 | | 111 | | | | | | |
| 7/28/15 | 13:17 | MODESTO L. | 2003 | 550 | 860 | | 90 | Peel | 97 | 100 | 98 | 94 | 98 | 94 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 101 | | 103 | | 104 | | | | | | |
| 7/28/15 | 13:19 | MODESTO L. | 2003 | 500 | 860 | | 90 | Peel | 99 | 102 | 105 | 104 | 100 | 101 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 110 | | 108 | | 107 | | | | | | |
| 7/29/15 | 6:45 | EMMANUEL V. | EXT 512 | | 490 | 400 | 75 | Peel | 98 | | 103 | | 104 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 121 | | 118 | | 120 | | | | | | |
| 7/29/15 | 15:08 | MODESTO L. | 2003 | 650 | 860 | | 94 | Peel | 101 | 92 | 103 | 92 | 101 | 93 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 108 | | 110 | | 110 | | | | | | |
| 7/30/15 | 6:40 | EMMANUEL V. | EXT 512 | | 480 | 400 | 79 | Peel | 114 | | 96 | | 110 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 116 | | 111 | | | | | | |
| 8/3/15 | 14:53 | MODESTO L. | 2003 | 450 | 860 | | 89 | Peel | 109 | 109 | 110 | 115 | 107 | 111 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 113 | | 117 | | 113 | | | | | | |
| 8/3/15 | 15:12 | MODESTO L. | 2003 | 650 | 860 | | 90 | Peel | 93 | 101 | 94 | 101 | 93 | 94 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 122 | | 125 | | 121 | | | | | | |
| 8/3/15 | 15:15 | MODESTO L. | 2003 | 400 | 860 | | 90 | Peel | 90 | 95 | 91 | 96 | 100 | 107 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 128 | | 116 | | 120 | | | | | | |
| 8/3/15 | 19:14 | MODESTO L. | 1480 | 450 | 860 | | 88 | Peel | 101 | 99 | 98 | 103 | 98 | 100 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 111 | | 110 | | 113 | | | | | | |
| 8/3/15 | 19:15 | MODESTO L. | 1480 | 400 | 860 | | 88 | Peel | 92 | 96 | 94 | 96 | 96 | 95 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 108 | | 110 | | 111 | | | | | | |
| 8/4/15 | 12:37 | PEDRO S. | EXT 512 | | 500 | 500 | 89 | Peel | 114 | | 118 | | 119 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 128 | | 135 | | 126 | | | | | | |
| 8/5/15 | 7:05 | PEDRO S. | EXT 512 | | 500 | 500 | 75 | Peel | 118 | | 117 | | 118 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 124 | | 126 | | 120 | | | | | | |
| 8/5/15 | 14:50 | MODESTO L. | 2025 | 450 | 860 | | 88 | Peel | 97 | 106 | 100 | 104 | 100 | 106 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 113 | | 115 | | 118 | | | | | | |
| 8/5/15 | 14:55 | MODESTO L. | 2025 | 600 | 860 | | 88 | Peel | 94 | 101 | 104 | 95 | 100 | 101 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 118 | | 119 | | 116 | | | | | | |
| 8/6/15 | 14:03 | MODESTO L. | 2025 | 450 | 860 | | 82 | Peel | 104 | 92 | 94 | 100 | 91 | 100 | | | | | PASS |
| S P T | PM | | | | | | | Shear | 116 | | 119 | | 119 | | | | | | |

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/6/15 | 14:06 | MODESTO L. | 2025 | 600 | 860 | | 82 | Peel | 92 | 100 | 94 | 100 | 93 | 103 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 111 | | 113 | | 116 | | | | | | |
| 8/6/15 | 14:08 | MODESTO L. | 2025 | 400 | 860 | | 82 | Peel | 112 | 110 | 112 | 112 | 111 | 109 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 115 | | 111 | | 113 | | | | | | |
| 8/7/15 | 6:43 | PEDRO S. | EXT 512 | | 530 | 530 | 69 | Peel | 123 | | 126 | | 126 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 133 | | 134 | | 130 | | | | | | |
| 8/7/15 | 13:11 | MODESTO L. | 2025 | 600 | 860 | | 84 | Peel | 99 | 104 | 100 | 100 | 95 | 102 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 113 | | 112 | | 115 | | | | | | |
| 8/7/15 | 13:15 | MODESTO L. | 2025 | 450 | 860 | | 84 | Peel | 100 | 97 | 98 | 103 | 105 | 99 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 112 | | 114 | | 116 | | | | | | |
| 8/7/15 | 13:18 | MODESTO L. | 2025 | 400 | 860 | | 84 | Peel | 114 | 114 | 107 | 107 | 110 | 105 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 112 | | 115 | | 116 | | | | | | |
| 8/10/15 | 6:54 | PEDRO S. | EXT 512 | | 530 | 530 | 70 | Peel | 127 | | 124 | | 131 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 135 | | 138 | | 135 | | | | | | |
| 8/10/15 | 10:55 | MODESTO L. | 2025 | 600 | 860 | | 80 | Peel | 97 | 93 | 97 | 91 | 104 | 99 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 113 | | 117 | | 119 | | | | | | |
| 8/10/15 | 14:00 | PEDRO S. | EXT 512 | | 530 | 530 | 81 | Peel | 120 | | 118 | | 111 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 128 | | 123 | | 124 | | | | | | |
| 8/10/15 | 15:20 | MODESTO L. | 2025 | 600 | 860 | | 81 | Peel | 104 | 104 | 106 | 101 | 100 | 109 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 122 | | 121 | | 121 | | | | | | |
| 8/12/15 | 8:15 | PEDRO S. | EXT 512 | | 530 | 530 | 72 | Peel | 119 | | 119 | | 116 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 128 | | 127 | | 123 | | | | | | |
| 8/13/15 | 8:30 | MODESTO L. | 2025 | 600 | 860 | | 72 | Peel | 104 | 99 | 105 | 101 | 98 | 100 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 122 | | 121 | | 122 | | | | | | |
| 8/14/15 | 9:00 | MODESTO L. | 2025 | 600 | 860 | | 77 | Peel | 93 | 99 | 91 | 97 | 91 | 100 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 116 | | 118 | | 119 | | | | | | |
| 8/14/15 | 9:03 | MODESTO L. | 2025 | 450 | 860 | | 77 | Peel | 99 | 97 | 101 | 99 | 108 | 96 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 115 | | 118 | | 116 | | | | | | |
| 8/14/15 | 9:05 | MODESTO L. | 2025 | 400 | 860 | | 77 | Peel | 112 | 113 | 114 | 113 | 114 | 116 | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 118 | | 119 | | 118 | | | | | | |
| 8/14/15 | 11:00 | EMMANUEL V. | EXT 512 | | 500 | 500 | 82 | Peel | 105 | | 111 | | 106 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 113 | | 115 | | | | | | |

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/9/15 | 7:50 | PEDRO S. | EXT 512 | | 550 | 550 | 76 | Peel | 104 | | 106 | | 103 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 114 | | 116 | | | | | | |
| 9/9/15 | 15:00 | PEDRO S. | 2025 | 400 | 860 | | 90 | Peel | 95 | 91 | 93 | 95 | 90 | 93 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 120 | | 117 | | 118 | | | | | | |
| 9/9/15 | 15:05 | PEDRO S. | 2025 | 350 | 860 | | 90 | Peel | 92 | 95 | 89 | 91 | 93 | 90 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 119 | | 121 | | 117 | | | | | | |
| 9/9/15 | 15:10 | PEDRO S. | 2025 | 300 | 860 | | 90 | Peel | 106 | 97 | 103 | 98 | 104 | 101 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 118 | | 119 | | 118 | | | | | | |
| 9/11/15 | 13:55 | PEDRO S. | 2025 | 300 | 860 | | 79 | Peel | 100 | 100 | 102 | 101 | 104 | 103 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 98 | | 101 | | 106 | | | | | | |
| 9/11/15 | 14:20 | EMMANUEL V. | EXT 512 | | 510 | 510 | 79 | Peel | 93 | | 93 | | 97 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 107 | | 109 | | 100 | | | | | | |
| 9/14/15 | 10:57 | EMMANUEL V. | EXT 512 | | 550 | 550 | 68 | Peel | 108 | | 106 | | 109 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 111 | | 110 | | | | | | |
| 9/14/15 | 13:30 | EMMANUEL V. | EXT 512 | | 540 | 540 | 74 | Peel | 111 | | 107 | | 114 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 116 | | 119 | | 115 | | | | | | |
| 9/15/15 | 9:50 | PEDRO S. | 2025 | 400 | 860 | | 70 | Peel | 105 | 100 | 106 | 103 | 102 | 103 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 120 | | 122 | | 123 | | | | | | |
| 9/15/15 | 9:51 | PEDRO S. | 2025 | 350 | 860 | | 70 | Peel | 103 | 102 | 106 | 108 | 108 | 102 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 118 | | 118 | | 116 | | | | | | |
| 9/15/15 | 9:52 | PEDRO S. | 2025 | 300 | 860 | | 70 | Peel | 102 | 103 | 101 | 102 | 102 | 99 | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 112 | | 110 | | 108 | | | | | | |
| 9/15/15 | 13:00 | PEDRO S. | 2025 | 350 | 860 | | 81 | Peel | 100 | 99 | 101 | 98 | 102 | 101 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 109 | | 106 | | 106 | | | | | | |
| 9/16/15 | 7:20 | EMMANUEL V. | EXT 512 | | 550 | 550 | 66 | Peel | 104 | | 106 | | 109 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 108 | | 111 | | 110 | | | | | | |
| 9/16/15 | 13:00 | PEDRO S. | 2025 | 450 | 860 | | 83 | Peel | 93 | 90 | 93 | 89 | 92 | 95 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 108 | | 104 | | 105 | | | | | | |
| 9/16/15 | 13:01 | PEDRO S. | 2025 | 350 | 860 | | 83 | Peel | 88 | 91 | 83 | 86 | 90 | 90 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 103 | | 102 | | 107 | | | | | | |
| 9/16/15 | 13:02 | PEDRO S. | 2025 | 300 | 860 | | 83 | Peel | 100 | 98 | 101 | 103 | 100 | 103 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 106 | | 107 | | 109 | | | | | | |

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/16/15 | 14:15 | EMMANUEL V. | EXT 512 | | 550 | 550 | 85 | Peel | 97 | | 94 | | 96 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 98 | | 100 | | 97 | | | | | | |
| 9/17/15 | 7:20 | EMMANUEL V. | EXT 512 | | 550 | 550 | 65 | Peel | 104 | | 99 | | 101 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 106 | | 106 | | 103 | | | | | | |
| 9/17/15 | 14:20 | PEDRO S. | 2025 | 450 | 860 | | 86 | Peel | 93 | 95 | 89 | 94 | 95 | 90 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 113 | | 109 | | 111 | | | | | | |
| 9/17/15 | 14:21 | PEDRO S. | 2025 | 350 | 860 | | 86 | Peel | 90 | 90 | 91 | 92 | 89 | 93 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 106 | | 103 | | 102 | | | | | | |
| 9/18/15 | 11:00 | PEDRO S. | 2025 | 450 | 860 | | 80 | Peel | 100 | 100 | 99 | 100 | 98 | 96 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 103 | | 102 | | 106 | | | | | | |
| 9/18/15 | 11:01 | PEDRO S. | 2025 | 350 | 860 | | 80 | Peel | 93 | 96 | 95 | 94 | 95 | 95 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 101 | | 104 | | 102 | | | | | | |
| 9/18/15 | 13:00 | PEDRO S. | 2025 | 450 | 860 | | 85 | Peel | 101 | 98 | 99 | 100 | 96 | 99 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 106 | | 105 | | 103 | | | | | | |
| 9/18/15 | 13:01 | PEDRO S. | 2025 | 350 | 860 | | 85 | Peel | 91 | 94 | 96 | 95 | 93 | 96 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 102 | | 102 | | 103 | | | | | | |
| 9/18/15 | 13:03 | PEDRO S. | 2025 | 300 | 860 | | 85 | Peel | 98 | 101 | 99 | 100 | 96 | 100 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 104 | | 103 | | 102 | | | | | | |
| 9/21/15 | 11:10 | EMMANUEL V. | EXT 512 | | 550 | 550 | 68 | Peel | 91 | | 90 | | 93 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 108 | | 103 | | 106 | | | | | | |
| 9/21/15 | 13:02 | EMMANUEL V. | EXT 512 | | 550 | 550 | 73 | Peel | 90 | | 90 | | 93 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 102 | | 103 | | 102 | | | | | | |
| 9/22/15 | 10:20 | PEDRO S. | 2025 | 450 | 860 | | 67 | Peel | 99 | 106 | 102 | 103 | 100 | 105 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 110 | | 107 | | 111 | | | | | | |
| 9/22/15 | 10:21 | PEDRO S. | 2025 | 350 | 860 | | 67 | Peel | 108 | 101 | 108 | 99 | 107 | 102 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 116 | | 115 | | 113 | | | | | | |
| 9/22/15 | 10:23 | PEDRO S. | 2025 | 300 | 860 | | 67 | Peel | 101 | 103 | 100 | 100 | 98 | 102 | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 106 | | 106 | | 109 | | | | | | |
| 9/22/15 | 13:05 | EMMANUEL V. | EXT 512 | | 550 | 550 | 73 | Peel | 98 | | 99 | | 101 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 106 | | 109 | | 107 | | | | | | |
| 9/23/15 | 7:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 62 | Peel | 93 | | 94 | | 97 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 111 | | 109 | | 108 | | | | | | |

## *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/23/15 | 15:25 | PEDRO S. | 2025 | 450 | 860 | | 79 | Peel | 93 | 92 | 96 | 96 | 92 | 93 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 102 | | 102 | | 102 | | | | | | |
| 9/24/15 | 7:20 | EMMANUEL V. | EXT 512 | | 550 | 550 | 62 | Peel | 118 | | 115 | | 112 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 122 | | 119 | | 118 | | | | | | |
| 9/24/15 | 14:30 | PEDRO S. | 2025 | 450 | 860 | | 80 | Peel | 89 | 89 | 88 | 89 | 87 | 88 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 100 | | 102 | | 102 | | | | | | |
| 9/24/15 | 14:31 | PEDRO S. | 2025 | 350 | 860 | | 80 | Peel | 85 | 87 | 85 | 91 | 86 | 89 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 101 | | 100 | | 103 | | | | | | |
| 9/25/15 | 7:00 | PEDRO S. | EXT 512 | | 550 | 550 | 65 | Peel | 106 | | 109 | | 110 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 112 | | 116 | | 119 | | | | | | |
| 9/25/15 | 14:15 | PEDRO S. | EXT 512 | 450 | 860 | | 74 | Peel | 89 | 89 | 89 | 90 | 91 | 88 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 100 | | 101 | | 100 | | | | | | |
| 9/25/15 | 14:17 | PEDRO S. | EXT 512 | | 550 | 550 | 73 | Peel | 99 | | 101 | | 100 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 103 | | 105 | | 102 | | | | | | |
| 9/29/15 | 14:30 | EMMANUEL V. | EXT 512 | | 550 | 550 | 80 | Peel | 98 | | 100 | | 99 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 106 | | 104 | | 103 | | | | | | |
| 9/29/15 | 14:30 | PEDRO S. | 2025 | 400 | 860 | | 80 | Peel | 92 | 91 | 94 | 90 | 89 | 87 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 103 | | 102 | | 102 | | | | | | |
| 9/29/15 | 14:31 | PEDRO S. | 2025 | 300 | 860 | | 80 | Peel | 93 | 90 | 89 | 91 | 88 | 90 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 103 | | 101 | | 102 | | | | | | |
| 9/29/15 | 14:32 | PEDRO S. | 2025 | 350 | 860 | | 80 | Peel | 90 | 88 | 89 | 93 | 92 | 90 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 104 | | 101 | | 101 | | | | | | |
| 10/7/15 | 8:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 59 | Peel | 96 | | 96 | | 108 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 130 | | 129 | | 127 | | | | | | |
| 10/7/15 | 13:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 73 | Peel | 93 | | 90 | | 92 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 126 | | 127 | | 124 | | | | | | |
| 10/8/15 | 14:00 | PEDRO S. | 2025 | 450 | 860 | | 73 | Peel | 103 | 108 | 103 | 107 | 101 | 104 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 124 | | 126 | | 123 | | | | | | |
| 10/8/15 | 14:01 | PEDRO S. | 2025 | 350 | 860 | | 73 | Peel | 109 | 108 | 112 | 108 | 109 | 105 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 127 | | 125 | | 126 | | | | | | |
| 10/8/15 | 14:03 | PEDRO S. | 2025 | 300 | 860 | | 73 | Peel | 119 | 126 | 121 | 121 | 120 | 121 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 123 | | 124 | | 123 | | | | | | |

## *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10/8/15 | 17:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 68 | Peel | 119 | | 119 | | 119 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 122 | | 123 | | 126 | | | | | | |
| 10/9/15 | 7:30 | PEDRO S. | EXT 512 | | 550 | 550 | 61 | Peel | 116 | | 118 | | 123 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 129 | | 131 | | 127 | | | | | | |
| 10/9/15 | 13:00 | PEDRO S. | EXT 512 | | 550 | 550 | 70 | Peel | 110 | | 113 | | 113 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 123 | | 124 | | 122 | | | | | | |
| 10/12/15 | 15:30 | EDFY N. | EXT 512 | | 550 | 550 | 76 | Peel | 114 | | 112 | | 117 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 125 | | 130 | | 123 | | | | | | |
| 11/4/15 | 10:40 | EDFY N. | EXT 77 | | 550 | 550 | 67 | Peel | 103 | | 94 | | 98 | | | | | | Pass |
| T TO T | AM | | | | | | | Shear | 131 | | 129 | | 125 | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |

# Appendix K
# ESI Seam Control (Non-Destructive) Test Logs

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell | **Job #** 12-11-1399 | **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST | **Primary** | **Pond**

**Job Description:** Cap Single Layer | **Secondary** | **Cell**

**Reported By** Lyssa Tran | **Cap** x

**Other** Cap construction

| | | | |
|---|---|---|---|
| **Air Pressure Test** | 30 | PSI |
| **Air Pressure Hold Time** | 5 | Minutes |
| **Allowable Air Pressure Loss** | 4 | PSI |

**17,515** Total LF of Welding to Date Combined | **Extrusion LF Weld Total To Date** 96 | **Fusion LF Weld Total To Date:** 17,419

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/20/15 | 1 / 2 | 135 | 17:25 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 6:35 / 30 | 6:40 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | SEOS TO 135'N (COVER BY RP-6 ) | | | | | |
| 7/20/15 | 1 / 2 | 28 | 17:46 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7:00 / 30 | 7:05 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | 135'N (COVER BY RP-6 ) TO NEOS | | | | | |
| 7/20/15 | 2 / 3 | 98 | 17:55 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 6:35 / 30 | 6:40 / 30 | 0 | PASS |
| Seam Notes | NEOS TO SEOS | | | | | | | | SEOS TO 98'N ( RP-1 ) | | | | | |
| 7/20/15 | 2 / 3 | 67 | 18:09 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7:01 / 30 | 7:06 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | 98'N ( RP-1 ) TO NEOS | | | | | |
| 7/20/15 | 3 / 4 | 94 | 18:20 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7:12 / 30 | 7:17 / 27 | 3 | PASS |
| Seam Notes | SEOS TO NEOS | | | | | | | | SEOS TO 94'N ( RP-2 ) | | | | | |
| 7/20/15 | 3 / 4 | 72 | 18:34 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7 :12 / 30 | 7:17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | 94'N ( RP-2 ) TO NEOS | | | | | |
| 7/21/15 | 4 / 5 | 165 | 14:14 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 14 46 / 30 | 14 51 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 6 / 7 | 22.5 | 14:30 PM | MODESTO L. | 2003 | 500 | 860 | | 7/21/15 | Air Pressure | 15 03 / 30 | 15 08 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 5 / 7 | 6 | 14:38 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 14 55 / 30 | 15 00 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/21/15 | 5 / 6 | 157 | 14:39 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 14 55 / 30 | 15 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 7 / 8 | 6 | 14:47 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Vacuum | | | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 6 / 8 | 157 | 14:48 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 15 16 / 30 | 15 21 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 8 / 9 | 163 | 15:17 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 15 46 / 30 | 15 51 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/22/15 | 9 / 10 | 52 | 13:30 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 11 / 30 | 14 16 / 27 | 3 | PASS |
| Seam Notes | SEOS TO 52'N (RP-15 ) | | | | | | | | | | | | | |
| 7/22/15 | 9 / 10 | 111 | 13:38 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 11 / 30 | 14 16 / 30 | 0 | PASS |
| Seam Notes | 52'N (RP-15 ) TO NEOS | | | | | | | | | | | | | |
| 7/22/15 | 10 / 11 | 164 | 13:50 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 12 / 30 | 14 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/22/15 | 11 / 12 | 164 | 14:10 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 21 / 30 | 14 26 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/22/15 | 12 / 13 | 164 | 15:00 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 15 17 / 30 | 15 22 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/23/15 | 13 / 14 | 46 | 13:30 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 16 20 / 30 | 16 25 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 46'S (RP-17 ) | | | | | | | | | | | | | |
| 7/23/15 | 13 / 14 | 118 | 13:37 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 16 26 / 30 | 16 31 / 27 | 3 | PASS |
| Seam Notes | 46'S (RP-17 ) TO SEOS | | | | | | | | | | | | | |
| 7/23/15 | 14 / 15 | 164 | 13:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 32 / 30 | 15 37 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/23/15 | 15 / 16 | 78 | 14:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 16 07 / 30 | 16 12 / 28 | 2 | PASS |
| Seam Notes | NEOS TO 78'S (RP-25 ) | | | | | | | | | | | | | |
| 7/23/15 | 15 / 16 | 87 | 14:27 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 40 / 30 | 15 45 / 30 | 0 | PASS |
| Seam Notes | 78'S (RP-25 ) TO SEOS | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 23 | 14:43 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 09 / 30 | 15 14 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 23'S (RP-22 ) | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 57 | 14:43 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 57 / 30 | 16 02 / 30 | 0 | PASS |
| Seam Notes | 23'S (RP-22 ) TO 80'S ( RP-27) | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 35 | 14:54 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 51 / 30 | 15 56 / 30 | 0 | PASS |
| Seam Notes | 80'S ( RP-27 ) TO 115'S (RP-28) | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 15 | 14:59 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 51 / 30 | 15 56 / 30 | 0 | PASS |
| Seam Notes | 115'S (RP-28 ) TO 130'S (RP-29) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/23/15 | 16 / 17 | 35 | 15:01 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 42 / 30 | 15 47 / 28 | 2 | PASS |
| Seam Notes | 130'S (RP-29) TO SEOS | | | | | | | | | | | | | |
| 7/23/15 | 17 / 18 | 101 | 15:07 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 55 / 30 | 16 00 / 27 | 3 | PASS |
| Seam Notes | NEOS TO 101'S (RP-31) | | | | | | | | | | | | | |
| 7/23/15 | 17 / 18 | 63 | 15:23 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 47 / 30 | 15 52 / 30 | 0 | PASS |
| Seam Notes | 101'S (RP-31) TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 18 / 19 | 55 | 14:25 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 48 / 30 | 16 53 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 55'S (RP-44) | | | | | | | | | | | | | |
| 7/24/15 | 18 / 19 | 109 | 14:33 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 02 / 30 | 16 07 / 28 | 2 | PASS |
| Seam Notes | 55'S (RP-44) TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 19 / 20 | 164 | 14:50 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 06 / 30 | 16 12 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/24/15 | 20 / 21 | 30 | 15:10 PM | MODESTO L. | 2003 | 550 | 860 | | 7/24/15 | Air Pressure | 16 44 / 30 | 16 49 / 28 | 2 | PASS |
| Seam Notes | NEOS TO 30'S (RP-51) | | | | | | | | | | | | | |
| 7/24/15 | 20 / 21 | 98 | 15:14 PM | MODESTO L. | 2003 | 550 | 860 | | 7/24/15 | Air Pressure | 16 42 / 30 | 16 47 / 28 | 2 | PASS |
| Seam Notes | 30'S (RP-51) TO 128'S (RP-40) | | | | | | | | | | | | | |
| 7/24/15 | 20 / 21 | 36 | 15:29 PM | MODESTO L. | 2003 | 550 | 860 | | 7/24/15 | Air Pressure | 16 12 / 30 | 16 17 / 28 | 2 | PASS |
| Seam Notes | 128'S (RP-40) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/24/15 | 21 / 22 | 84 | 15:35 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 36 / 30 | 16 41 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 84'S (RP-67) | | | | | | | | | | | | | |
| 7/24/15 | 21 / 22 | 80 | 15:48 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 27 / 30 | 16 32 / 30 | 0 | PASS |
| Seam Notes | 84'S (RP-67) TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 22 / 23 | 76 | 15:50 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 35 / 30 | 16 40 / 27 | 3 | PASS |
| Seam Notes | NEOS TO 76'S (RP-68) | | | | | | | | | | | | | |
| 7/24/15 | 22 / 23 | 21 | 16:01 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 38 / 30 | 16 43 / 30 | 0 | PASS |
| Seam Notes | 76'S (RP-68) TO 97'S (RP-76) | | | | | | | | | | | | | |
| 7/24/15 | 22 / 23 | 67 | 16:04 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 24 / 30 | 16 29 / 30 | 0 | PASS |
| Seam Notes | 97'S (RP-76)TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 23 / 24 | 164 | 16:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 52 / 30 | 16 57 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/28/15 | 24 / 25 | 127 | 13:25 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 01 / 30 | 16 06 / 29 | 1 | PASS |
| Seam Notes | NEOS TO 127'S (RP-88) | | | | | | | | | | | | | |
| 7/28/15 | 24 / 25 | 37 | 13:44 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 00 / 30 | 16 05 / 30 | 0 | PASS |
| Seam Notes | 127'S (RP-88 )TO SEOS | | | | | | | | | | | | | |
| 7/28/15 | 25 / 26 | 110 | 13:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 09 / 30 | 16 14 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 110'N (RP-95 ) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/29/15 | 25 / 26 | 19 | 7:45 AM | EMMANUEL V. | EXT 512 | | 490 | 400 | 7/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 110'N( RP-95 ) TO 129'N (RP-95 ) | | | | | | | | | | | | | |
| 7/28/15 | 25 / 26 | 34 | 14:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 13 / 30 | 16 18 / 30 | 0 | PASS |
| Seam Notes | 129'N (RP-95 )TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 26 / 27 | 71 | 13:53 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 16 / 30 | 16 21 / 27 | 3 | PASS |
| Seam Notes | SEOS TO 71'N (RP-97) | | | | | | | | | | | | | |
| 7/28/15 | 26 / 27 | 92 | 14:04 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 17 / 30 | 16 22 / 30 | 0 | PASS |
| Seam Notes | 71'N (RP-97) TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 27 / 28 | 34 | 14:22 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 22 / 30 | 16 27 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 34'N (RP-121) | | | | | | | | | | | | | |
| 7/28/15 | 27 / 28 | 129 | 14:27 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 22 / 30 | 16 27 / 30 | 0 | PASS |
| Seam Notes | 34'N (RP-121 ) TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 28 / 29 | 61 | 15:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 29 / 30 | 16 34 / 28 | 2 | PASS |
| Seam Notes | SEOS TO 61'N (RP-115) | | | | | | | | | | | | | |
| 7/29/15 | 28 / 29 | 12 | 10:45 AM | EMMANUEL V. | EXT 512 | | 490 | 400 | 7/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 61'N (RP-115)TO 73'N(RP-114) | | | | | | | | | | | | | |
| 7/28/15 | 28 / 29 | 47 | 16:01 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 32 / 30 | 16 37 / 30 | 0 | PASS |
| Seam Notes | 73'N (RP-114)TO 120'N (RP-105) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/28/15 | 28 / 29 | 44 | 16:09 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 36 / 30 | 16 41 / 29 | 1 | PASS |
| Seam Notes | 120'N (RP-105)TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 29 / 30 | 125 | 16:16 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 38 / 30 | 16 43 / 28 | 2 | PASS |
| Seam Notes | SEOS TO 125'N (RP-108) | | | | | | | | | | | | | |
| 7/28/15 | 29 / 30 | 39 | 16:26 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 38 / 30 | 16 43 / 28 | 2 | PASS |
| Seam Notes | 125'N (RP-108) TO NEOS | | | | | | | | | | | | | |
| 7/29/15 | 30 / 31 | 163 | 15:30 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 41 / 30 | 16 46 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/29/15 | 31 / 32 | 163 | 15:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 50 / 30 | 16 55 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/29/15 | 32 / 33 | 163 | 16:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 53 / 30 | 16 58 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/29/15 | 33 / 34 | 25 | 8:00 AM | EMMANUEL V. | EXT 512 | | 480 | 400 | 7/30/15 | Vacuum | | | 0 | PASS |
| Seam Notes | SEOS TO 21'N (RP-133) | | | | | | | | | | | | | |
| 7/29/15 | 33 / 34 | 139 | 16:33 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 54 / 30 | 16 59 / 29 | 1 | PASS |
| Seam Notes | 21'N (RP-133) TO NEOS | | | | | | | | | | | | | |
| 8/3/15 | 35 / 36 | 84 | 15:22 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 45 / 30 | 14 40 / 29 | 1 | PASS |
| Seam Notes | EEOS TO 84'W(RP-153) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 35 / 36 | 10 | 15:35 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 38 / 30 | 13 43 / 30 | 0 | PASS |
| Seam Notes | 84'W ( RP-153) TO WEOS | | | | | | | | | | | | | |
| 8/3/15 | 36 / 37 | 95 | 15:43 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 29 / 30 | 13 34 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 37 / 38 | 98 | 16:01 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 23 / 30 | 13 28 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 38 / 39 | 101 | 16:28 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 14 / 30 | 13 19 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 39 / 40 | 102 | 16:52 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 05 / 30 | 13 10 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 35 | 10 | 17:26 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 45 / 30 | 13 50 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 10'S (RP-157) | | | | | | | | | | | | | |
| 8/3/15 | 34 / 35 | 11 | 17:27 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 38 / 30 | 13 43 / 30 | 0 | PASS |
| Seam Notes | 10'S (RP-157) TO SEOS | | | | | | | | | | | | | |
| 8/3/15 | 34 / 36 | 22.5 | 17:29 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 31 / 30 | 13 36 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 37 | 22.5 | 17:34 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 20 / 30 | 13 25 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 34 / 38 | 22.5 | 17:39 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 09 / 30 | 13 14 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 39 | 22.5 | 17:44 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 05 / 30 | 13 10 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 40 | 22.5 | 17:47 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 12 36 / 30 | 12 41 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 41 | 38 | 17:50 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 12 30 / 30 | 13 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 42 / 43 | 38 | 18:11 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 14 13 / 30 | 14 18 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 40 / 42 | 22.5 | 18:13 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 14 / 30 | 14 19 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 39 / 42 | 22.5 | 18:16 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 07 / 30 | 14 12 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 38 / 42 | 22.5 | 18:19 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 07 / 30 | 14 12 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 37 / 42 | 22.5 | 18:21 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 36 / 42 | 22.5 | 18:24 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 53 / 30 | 13 58 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 35 / 42 | 22.5 | 18:28 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 53 / 30 | 13 58 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 45 / 46 | 10 | 18:36 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 12 48 / 30 | 12 53 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 44 / 46 | 27 | 18:39 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 12 48 / 30 | 12 48 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 44 / 45 | 25 | 18:41 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 12 42 / 30 | 12 47 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 43 / 46 | 10 | 18:48 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 14 25 / 30 | 14 30 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 43 / 44 | 23 | 18:49 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 14 19 / 30 | 14 24 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 40 / 43 | 17 | 18:55 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 14 16 / 30 | 14 21 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 40 / 44 | 48 | 18:57 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 17 / 30 | 14 22 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | EEOS TO 48'W (RP-184) | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 40 / 44 | 13 | 19:17 PM | MODESTO L. | 1480 | 400 | 860 | | 8/4/15 | Air Pressure | 13 00 / 30 | 13 05 / 30 | 0 | PASS |
| Seam Notes | 48'W (RP-184) TO WEOS | | | | | | | | | | | | | |
| 8/3/15 | 40 / 41 | 23 | 19:25 PM | MODESTO L. | 1480 | 450 | 860 | | 8/4/15 | Air Pressure | 12 30 / 30 | 12 35 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 41 / 44 | 18 | 19:28 PM | MODESTO L. | 1480 | 400 | 860 | | 8/4/15 | Air Pressure | 12 42 / 30 | 12 47 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 41 / 45 | 10 | 19:31 PM | MODESTO L. | 1480 | 400 | 860 | | 8/4/15 | Air Pressure | 12 42 / 30 | 12 47 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/5/15 | 42 / 47 | 167 | 16:20 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 26 / 30 | 15 31 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/5/15 | 47 / 48 | 106 | 16:50 PM | MODESTO L. | 2025 | 450 | 860 | | 8/6/15 | Air Pressure | 15 37 / 30 | 15 42 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 106'S (RP-195 ) | | | | | | | | | | | | | |
| 8/5/15 | 47 / 48 | 61 | 17:13 PM | MODESTO L. | 2025 | 450 | 860 | | 8/6/15 | Air Pressure | 15 37 / 30 | 15 42 / 30 | 0 | PASS |
| Seam Notes | 106'S (RP-195 ) TO SEOS | | | | | | | | | | | | | |
| 8/5/15 | 48 / 49 | 86 | 18:15 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 50 / 30 | 15 55 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 86'S (RP-196 ) | | | | | | | | | | | | | |
| 8/5/15 | 48 / 49 | 81 | 18:29 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 52 / 30 | 15 57 / 30 | 0 | PASS |
| Seam Notes | 86'S (RP-196 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/6/15 | 49 / 50 | 167 | 14:15 PM | MODESTO L. | 2025 | 450 | 860 | | 8/6/15 | Air Pressure | 15 54 / 30 | 15 59 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 51 / 52 | 22.5 | 14:45 PM | MODESTO L. | 2025 | 400 | 860 | | 8/6/15 | Air Pressure | 15 58 / 30 | 16 03 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 50 / 51 | 163 | 14:50 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 55 / 30 | 16 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 50 / 52 | 5 | 15:05 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 55 / 30 | 16 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 51 / 53 | 164 | 15:10 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 59 / 30 | 16 04 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 52 / 53 | 5 | 15:24 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 16 00 / 30 | 16 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 53 / 54 | 15 | 15:33 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 16 06 / 30 | 16 11 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 15'S (RP-197 ) | | | | | | | | | | | | | |
| 8/6/15 | 53 / 54 | 153 | 15:35 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 16 04 / 30 | 16 09 / 29 | 1 | PASS |
| Seam Notes | 15'S (RP-197 ) TO SEOS | | | | | | | | | | | | | |
| 8/7/15 | 55 / 56 | 22.5 | 13:30 PM | MODESTO L. | 2025 | 400 | 860 | | 8/7/15 | Air Pressure | 15 04 / 30 | 15 09 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/7/15 | 54 / 55 | 157 | 13:34 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 41 / 30 | 14 46 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 54 / 56 | 11 | 13:50 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 41 / 30 | 14 46 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 55 / 57 | 101 | 14:00 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 31 / 30 | 14 36 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 101'N (RP-220) | | | | | | | | | | | | | |
| 8/7/15 | 55 / 57 | 19 | 14:16 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 31 / 30 | 14 36 / 30 | 0 | PASS |
| Seam Notes | 101'N (RP-220) TO 120'N (RP-221 ) | | | | | | | | | | | | | |
| 8/7/15 | 55 / 57 | 37 | 14:19 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 48 / 30 | 14 53 / 30 | 0 | PASS |
| Seam Notes | 120'N (RP-221 ) TO NEOS | | | | | | | | | | | | | |
| 8/7/15 | 56 / 57 | 11 | 14:24 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 48 / 30 | 14 53 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 59 / 60 | 22.5 | 14:26 PM | MODESTO L. | 2025 | 400 | 860 | | 8/7/15 | Air Pressure | 15 11 / 30 | 15 16 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 57 / 58 | 167 | 14:28 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 15 02 / 30 | 15 07 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 58 / 59 | 150 | 14:57 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 15 30 / 30 | 15 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ]

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ]

**Reported By** Lyssa Tran **Cap** [x]

**Other** Cap construction

**Air Pressure Test** 30 PSI

**Air Pressure Hold Time** 5 Minutes

**Allowable Air Pressure Loss** 4 PSI

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/7/15 | 58 / 60 | 15 | 15:25 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 16 01 / 30 | 16 06 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 59 / 61 | 150 | 11:06 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 11 55 / 30 | 12 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 60 / 61 | 15 | 11:24 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 61 / 62 | 164 | 11:27 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 11 56 / 30 | 12 01 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 62 / 63 | 163 | 11:38 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 11 59 / 30 | 12 04 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 63 / 64 | 163 | 15:50 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 39 / 30 | 8 44 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 64 / 66 | 8 | 16:20 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 46 / 30 | 8 51 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | SEOS TO 8'N ( RP-252 ) | | | | | | |
| 8/10/15 | 64 / 66 | 13 | 16:21 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 48 / 30 | 8 52 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | 8'N (RP-252 ) TO NEOS | | | | | | |
| 8/10/15 | 64 / 65 | 141 | 16:25 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 38 / 30 | 8 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/12/15 | 64 / 66 | 24 | 8:30 AM | PEDRO S. | EXT 512 | | 530 | 530 | 8/12/15 | Vacuum | | | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 65 / 67 | 162 | 8:45 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 53 / 30 | 10 58 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 67 / 68 | 162 | 9:10 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 30 / 30 | 10 35 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 68 / 69 | 100 | 9:25 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 11 03 / 30 | 11 08 / 30 | 0 | PASS |
| Seam Notes | DS-19 WAS COLLECTED BEFORE NON-DESTRUCTIVE TESTING WAS COMPLETED | | | | | | | | SEOS TO 100'N (RP-254/DS-19 ) | | | | | |
| 8/13/15 | 68 / 69 | 62 | 9:32 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 11 00 / 30 | 11 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | 100'N (RP-254/DS-19 ) TO NEOS | | | | | |
| 8/13/15 | 69 / 70 | 162 | 9:39 PM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 32 / 30 | 10 37 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 70 / 71 | 162 | 10:05 PM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 33 / 30 | 10 38 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/14/15 | 71 / 72 | 57 | 9:45 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11 14 / 30 | 11 19 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | SEOS TO 57'N (RP-258 ) | | | | | |
| 8/14/15 | 71 / 72 | 76 | 9:51 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11 25 / 30 | 11 30 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | 57'N (RP-258 ) TO 133'N (RP-259 ) | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/14/15 | 71 / 72 | 29 | 10:03 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11:34 / 30 | 11:39 / 30 | 0 | PASS |
| Seam Notes | 133'N (RP-259 ) TO NEOS | | | | | | | | | | | | | |
| 8/14/15 | 72 / 73 | 163 | 10:14 AM | MODESTO L. | 2025 | 450 | 860 | | 8/14/15 | Air Pressure | 11:15 / 30 | 11:20 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/14/15 | 73 / 74 | 164 | 10:35 AM | MODESTO L. | 2025 | 450 | 860 | | 8/14/15 | Air Pressure | 11:16 / 30 | 11:21 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/14/15 | 74 / 75 | 60 | 10:54 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11:30 / 30 | 11:35 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 60'N (RP-260 ) | | | | | | | | | | | | | |
| 8/14/15 | 74 / 75 | 104 | 11:03 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11:30 / 30 | 11:35 / 30 | 0 | PASS |
| Seam Notes | 60'N (RP-260 ) TO NEOS | | | | | | | | | | | | | |
| 9/9/15 | 76 / 77 | 86 | 15:51 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 30 / 30 | 8 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 77 / 78 | 86 | 16:05 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 31 / 30 | 8 36 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 78 / 79 | 86 | 16:19 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 49 / 30 | 8 54 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 79 / 80 | 83 | 16:59 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 32 / 30 | 8 37 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/9/15 | 80 / 81 | 85 | 17:20 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 02 / 30 | 9 07 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 85 / 86 | 11 | 17:34 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 9 51 / 30 | 9 56 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 84 / 86 | 13 | 17:37 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 51 / 30 | 9 56 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 84 / 85 | 17 | 17:40 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 54 / 30 | 9 59 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 83 / 84 | 23 | 17:46 PM | PEDRO S. | 2025 | 350 | 860 | | 9/14/15 | Air Pressure | 9 30 / 30 | 9 35 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 83 / 85 | 3 | 17:48 PM | PEDRO S. | 2025 | 350 | 860 | | 9/16/15 | Vacuum | | | 0 | PASS |
| Seam Notes | | | | | | | | | | COVER BY SJ RP-302 | | | | |
| 9/9/15 | 82 / 83 | 26 | 17:50 PM | PEDRO S. | 2025 | 350 | 860 | | 9/14/15 | Air Pressure | 9 31 / 30 | 9 36 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 81 / 82 | 22.5 | 17:57 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 9 02 / 30 | 9 07 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 81 / 83 | 22.5 | 18:03 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 9 30 / 30 | 9 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/9/15 | 81 / 84 | 24 | 18:06 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 51 / 30 | 9 56 / 30 | 0 | PASS |
| Seam Notes | WEOS TO 24'E ( RP- 315 ) | | | | | | | | | | | | | |
| 9/9/15 | 81 / 84 | 12 | 18:08 PM | PEDRO S. | 2025 | 400 | 860 | | 9/16/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 24'E ( RP-315 ) TO EEOS | | | | | | | | | | | | | |
| 9/9/15 | 75 / 82 | 30 | 18:10 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 31 / 30 | 9 36 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 81 | 23 | 14:17 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 35 / 30 | 7 40 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 75 / 80 | 22.5 | 14:21 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 36 / 30 | 7 41 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 79 | 23 | 14:24 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 36 / 30 | 7 41 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 78 | 22.5 | 14:28 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 37 / 30 | 7 42 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 77 | 22.5 | 14:33 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 8 01 / 30 | 8 06 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 76 | 22.5 | 14:37 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 8 01 / 30 | 8 06 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/15/15 | 87 / 88 | 167 | 10:34 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 11 45 / 30 | 11 50 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 88 / 89 | 168 | 10:55 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 11 43 / 30 | 11 48 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 89 / 90 | 81 | 11:17 AM | PEDRO | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 11 45 / 30 | 11 50 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 81'N (RP-328 ) | | | | | | | | | | | | | |
| 9/15/15 | 89 / 90 | 64 | 11:30 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 13 00 / 30 | 13 05 / 30 | 0 | PASS |
| Seam Notes | 81'N (RP-328 ) TO 145'N (RP-326 ) | | | | | | | | | | | | | |
| 9/15/15 | 89 / 90 | 23 | 11:39 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 13 02 / 30 | 13 07 / 30 | 0 | PASS |
| Seam Notes | 145'N (RP-326 ) TO NEOS | | | | | | | | | | | | | |
| 9/15/15 | 81 / 87 | 8 | 11:43 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 30 / 30 | 14 35 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 8'N (RP-319 ) | | | | | | | | | | | | | |
| 9/15/15 | 81 / 87 | 14.5 | 11:44 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 25 / 30 | 14 30 / 30 | 0 | PASS |
| Seam Notes | 8'N (RP-319 ) TO NEOS | | | | | | | | | | | | | |
| 9/15/15 | 80 / 87 | 22.5 | 11:46 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 79 / 87 | 6 | 11:50 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 6'N (RP-322) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/15/15 | 79 / 87 | 12.5 | 11:51 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 40 / 30 | 13 45 / 28 | 2 | PASS |
| Seam Notes | 6'N (RP-322) TO NEOS | | | | | | | | | | | | | |
| 9/15/15 | 78 / 87 | 22.5 | 13:05 PM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 23 / 30 | 13 28 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 77 / 87 | 22.5 | 13:07 PM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 22 / 30 | 13 27 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 76 / 87 | 23 | 13:10 PM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 22 / 30 | 13 27 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/16/15 | 90 / 91 | 168 | 13:36 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 35 / 30 | 14 40 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/16/15 | 91 / 92 | 152 | 13:55 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 40 / 30 | 14 45 / 28 | 2 | PASS |
| Seam Notes | SEOS TO 151'N (RP-351 ) | | | | | | | | | | | | | |
| 9/16/15 | 91 / 92 | 15 | 14:10 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 44 / 30 | 14 49 / 29 | 1 | PASS |
| Seam Notes | 151'N ( RP-351 ) TO NEOS | | | | | | | | | | | | | |
| 9/16/15 | 92 / 93 | 167 | 14:16 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 40 / 30 | 14 45 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/16/15 | 93 / 94 | 144 | 14:34 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 50 / 30 | 14 55 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 144'N (RP-354 ) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/16/15 | 93 / 94 | 23 | 14:48 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 51 / 30 | 15 56 / 30 | 0 | PASS |
| Seam Notes | 144'N (RP-354 ) TO NEOS | | | | | | | | | | | | | |
| 9/17/15 | 94 / 95 | 33 | 14:31 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 28 / 30 | 15 33 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 33'N (RP-370 ) | | | | | | | | | | | | | |
| 9/17/15 | 94 / 95 | 92 | 14:35 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 15 / 30 | 15 20 / 30 | 0 | PASS |
| Seam Notes | 33'N(RP-370) TO 125'N (RP-368 ) | | | | | | | | | | | | | |
| 9/17/15 | 94 / 95 | 41 | 14:44 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 15 / 30 | 15 20 / 30 | 0 | PASS |
| Seam Notes | 125'N (RP-368 ) TO NEOS | | | | | | | | | | | | | |
| 9/17/15 | 95 / 96 | 128 | 14:51 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 25 / 30 | 15 30 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 128'S (RP-373) | | | | | | | | | | | | | |
| 9/17/15 | 95 / 96 | 38 | 15:06 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 26 / 30 | 15 31 / 30 | 0 | PASS |
| Seam Notes | 128'S (RP- 373 ) TO SEOS | | | | | | | | | | | | | |
| 9/17/15 | 96 / 97 | 101 | 15:13 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 30 / 30 | 15 35 / 28 | 2 | PASS |
| Seam Notes | NEOS TO 101'S (RP- 377 ) | | | | | | | | | | | | | |
| 9/17/15 | 96 / 97 | 16 | 13:48 PM | EMMANUEL V. | EXT 512 | | 550 | 550 | 9/21/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 101'S (RP-377 ) TO 117'S (RP- 376 ) | | | | | | | | | | | | | |
| 9/17/15 | 96 / 97 | 49 | 15:21 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 36 / 30 | 15 41 / 29 | 1 | PASS |
| Seam Notes | 117'S (RP-376 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/18/15 | 98 / 99 | 70 | 11:26 AM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 14 / 30 | 14 19 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 99 / 100 | 70 | 11:41 AM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 08 / 30 | 14 13 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 100 / 101 | 71 | 11:53 AM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 07 / 30 | 14 12 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 101 / 102 | 70 | 13:07 PM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 06 / 30 | 14 11 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 102 / 103 | 70 | 13:22 PM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 05 / 30 | 14 10 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 104 / 105 | 32 | 13:41 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 15 04 / 30 | 15 09 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 105 / 106 | 27 | 13:51 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 15 12 / 30 | 15 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 103 / 106 | 22.5 | 14:00 PM | PEDRO S. | 2025 | 300 | 860 | | 9/18/15 | Air Pressure | 15 12 / 30 | 15 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 103 / 105 | 23 | 14:06 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 15 04 / 30 | 15 09 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/18/15 | 103 / 104 | 16 | 14:10 PM | PEDRO S. | 2025 | 300 | 860 | | 9/18/15 | Air Pressure | 15 04 / 30 | 15 09 / 30 | 0 | PASS |
| Seam Notes | EEOS TO 16'W ( RP-383 ) | | | | | | | | | | | | | |
| 9/18/15 | 103 / 104 | 10 | 14:13 PM | PEDRO S. | 2025 | 300 | 860 | | 9/18/15 | Air Pressure | 14 55 / 30 | 15 00 / 30 | 0 | PASS |
| Seam Notes | 16'W (RP-383 ) TO WEOS | | | | | | | | | | | | | |
| 9/18/15 | 97 / 98 | 22.5 | 14:20 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 38 / 30 | 14 43 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 99 | 22.5 | 14:22 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 38 / 30 | 14 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 100 | 22.5 | 14:25 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 40 / 30 | 14 45 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 101 | 22.5 | 14:28 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 40 / 30 | 14 45 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 102 | 22.5 | 14:30 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 46 / 30 | 14 511 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 103 | 12 | 14:33 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 48 / 30 | 14 53 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 12'S (RP-384) | | | | | | | | | | | | | |
| 9/18/15 | 97 / 103 | 10.5 | 14:35 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 55 / 30 | 15 00 / 30 | 0 | PASS |
| Seam Notes | 12'S (RP-384 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/18/15 | 97 / 104 | 32 | 14:37 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 55 / 30 | 15 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 106 / 107 | 36 | 10:41 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 11 37 / 30 | 11 42 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 103 / 107 | 14 | 10:45 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 38 / 30 | 11 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 102 / 107 | 23 | 10:47 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 38 / 30 | 11 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 101 / 107 | 22.5 | 10:50 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 39 / 30 | 11 44 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 100 / 107 | 22.5 | 10:53 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 40 / 30 | 11 45 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 99 / 107 | 23 | 10:56 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 49 / 30 | 11 54 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 98 / 107 | 23 | 11:00 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 48 / 30 | 11 53 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 107 / 108 | 163 | 11:06 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 13 13 / 30 | 13 18 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/22/15 | 108 / 109 | 164 | 11:24 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 13 14 / 30 | 13 19 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 109 / 110 | 163 | 11:42 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 13 15 / 30 | 13 20 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/23/15 | 110 / 111 | 162 | 15:38 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 50 / 30 | 16 55 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/23/15 | 111 / 112 | 15 | 15:52 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 48 / 30 | 16 53 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 15'S (RP-419 ) | | | | | | | | | | | | | |
| 9/23/15 | 111 / 112 | 147 | 15:54 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 48 / 30 | 16 53 / 29 | 1 | PASS |
| Seam Notes | 15'S (RP-419 ) TO SEOS | | | | | | | | | | | | | |
| 9/23/15 | 112 / 113 | 162 | 16:12 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 51 / 30 | 16 56 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/23/15 | 113 / 114 | 28 | 16:42 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 53 / 30 | 16 58 / 29 | 1 | PASS |
| Seam Notes | NEOS TO 28'S (RP-421 ) | | | | | | | | | | | | | |
| 9/23/15 | 113 / 114 | 138 | 16:46 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 59 / 30 | 17 04 / 30 | 0 | PASS |
| Seam Notes | 28'S (RP-421 ) TO SEOS | | | | | | | | | | | | | |
| 9/24/15 | 114 / 115 | 162 | 14:51 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 46 / 30 | 15 51 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported By** Lyssa Tran **Cap** x

**Other** Cap construction

**Air Pressure Test** 30 PSI

**Air Pressure Hold Time** 5 Minutes

**Allowable Air Pressure Loss** 4 PSI

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/24/15 | 115 / 116 | 28 | 15:14 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 47 / 30 | 15 52 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 28'S (RP-426 ) | | | | | | | | | | | | | |
| 9/24/15 | 115 / 116 | 135 | 15:17 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 48 / 30 | 15 53 / 30 | 0 | PASS |
| Seam Notes | 28'S (RP-426 ) TO SEOS | | | | | | | | | | | | | |
| 9/24/15 | 116 / 117 | 164 | 15:31 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 52 / 30 | 15 57 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/24/15 | 117 / 118 | 121 | 15:51 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 16 04 / 30 | 16 09 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 121'S (RP-427 ) | | | | | | | | | | | | | |
| 9/24/15 | 117 / 118 | 44 | 16:02 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 16 13 / 30 | 16 18 / 30 | 0 | PASS |
| Seam Notes | 121'S (RP-427 ) TO SEOS | | | | | | | | | | | | | |
| 9/25/15 | 118 / 119 | 164 | 14:30 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 17 / 30 | 15 22 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 22 | 14:53 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 22 / 30 | 15 27 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 22'S (RP-438 ) | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 72 | 14:55 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 21 / 30 | 15 26 / 28 | 2 | PASS |
| Seam Notes | 22'S (RP-438 ) TO 94'S (RP-437 ) | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 33 | 15:00 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 21 / 30 | 15 26 / 30 | 0 | PASS |
| Seam Notes | 94'S (RP-437 ) TO 127'S (RP-439 ) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/25/15 | 119 / 120 | 12 | 15:58 PM | PEDRO S. | EXT 512 | | 550 | 550 | 9/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 127'S ( RP-439 ) TO 139'S (RP-440 ) | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 26 | 15:03 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 15<br>30 | 15 20<br>30 | 0 | PASS |
| Seam Notes | 139'S ( RP-440 ) TO SEOS | | | | | | | | | | | | | |
| 9/29/15 | 120 / 121 | 166 | 16:46 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 15 10<br>30 | 15 15<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 121 / 122 | 143 | 15:04 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 15 40<br>30 | 15 45<br>29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-445 / 122 | 17 | 15:30 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 52<br>30 | 15 57<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-446 / 122 | 5 | 15:34 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 51<br>30 | 15 56<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-445 / 121 | 17 | 15:38 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 52<br>30 | 15 57<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-446 / 121 | 5 | 15:41 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 51<br>30 | 15 56<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 123 / 124 | 22.5 | 15:45 PM | PEDRO S. | 2025 | 300 | 860 | | 9/29/15 | Air Pressure | 16 12<br>30 | 16 17<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/29/15 | 124 / 125 | 19 | 15:52 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 16 12 / 30 | 16 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 123 / 125 | 18 | 15:55 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 12 / 30 | 16 17 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 18'N (RP-454 ) | | | | | | | | | | | | | |
| 9/29/15 | 123 / 125 | 129 | 16:21 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 35 / 30 | 16 40 / 30 | 0 | PASS |
| Seam Notes | 18'N (RP-454 ) TO NEOS | | | | | | | | | | | | | |
| 9/29/15 | 122 / 124 | 19 | 15:58 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 10 / 30 | 16 15 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 122 / 123 | 23 | 16:00 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 10 / 30 | 16 15 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 23'N (RP-450 ) | | | | | | | | | | | | | |
| 9/29/15 | 122 / 123 | 126 | 16:03 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 40 / 30 | 16 45 / 30 | 0 | PASS |
| Seam Notes | 23'N (RP-450 ) TO NEOS | | | | | | | | | | | | | |
| 9/29/15 | RP-445 / RP-446 | 2 | 15:28 PM | PEDRO S. | 2025 | 300 | 860 | | 9/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | COVER BY RP-447 | | | | | | | | | | | | | |
| 10/8/15 | 125 / 126 | 159 | 15:00 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 16 45 / 30 | 16 50 / 29 | 1 | PASS |
| Seam Notes | NEOS TO 159'S ( RP-477 ) | | | | | | | | | | | | | |
| 10/8/15 | 125 / 126 | 5 | 15:33 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 15 / 30 | 17 20 / 30 | | PASS |
| Seam Notes | 159'N (RP-477 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10/8/15 | 126 / 127 | 163 | 15:38 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 16 45 / 30 | 16 50 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 128 / 129 | 22.5 | 16:05 PM | PEDRO S. | 2025 | 300 | 860 | | 10/8/15 | Air Pressure | 17 29 / 30 | 17 34 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 127 / 129 | 12 | 16:12 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 30 / 30 | 17 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 127 / 128 | 149 | 16:13 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 16 45 / 30 | 16 50 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 130 / 131 | 9 | 16:30 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 40 / 30 | 17 45 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 131 / 132 | 11 | 16:32 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 39 / 30 | 17 44 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 133 / 134 | 7 | 16:35 PM | PEDRO S. | 2025 | 300 | 860 | | 10/8/15 | Air Pressure | 17 47 / 30 | 17 52 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 129 / 132 | 12 | 16:43 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 30 / 30 | 17 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 128 / 132 | 81 | 16:44 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 31 / 30 | 17 36 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

SEOS TO 81'N (RP-476 )

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10/8/15 | 128 / 132 | 25 | 16:53 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 31<br>30 | 17 36<br>30 | 0 | PASS |
| Seam Notes | 81'N (RP-476 ) TO NEOS | | | | | | | | | | | | | |
| 10/8/15 | 128 / 131 | 22.5 | 16:55 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 39<br>30 | 17 44<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 128 / 130 | 20 | 16:59 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 40<br>30 | 17 45<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 132 / 134 | 38 | 17:06 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 48<br>30 | 17 52<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 132 / 133 | 38 | 17:11 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 45<br>30 | 17 50<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |

# Appendix L
# ESI Repair Report

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-1 | CF | 2/3 | | 98'N OF SEOS ( VALLEY DESIGN) | P | 2.5 | x | 63 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-2 | WR | 3/4 | | 94'N OF SEOS | P | 2 | x | 12 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-3 | SI | | 3 | 60'N OF 2/3 & 11'E | P | 2 | x | 2.5 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-4 | DS-1 | 3/4 | | 18'N OF SEOS | P | 2 | X | 28 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-5 | CF | | 3 | 140'N OF 2/3 & 6'E | P | 2 | x | 10 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-6 | PB | 1/2 | | 135'N OF SEOS (PB 8") | P | 5 | x | 5 | 52.5 | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-7 | PB | | 1 | 85'N OF 1/2 & 17'W (PB 4") | P | 3 | x | 4 | 36.58 | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-8 | SI | | 2 | 86'N OF 2/3 & 2'W | P | 1.5 | x | 2 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-9 | RW | 4/5 | | SEOS | P | 1.5 | x | 3 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-10 | SJ | 5/6/7 | | SJ 5/6/7 | P | 1.5 | X | 2 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-11 | RW | 5/7 | | SEOS | P | 2 | x | 4 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-12 | DS-2 | 6/7 | | 10'E OF WEOS | P | 2 | x | 5.5 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-13 | FS | 7/8 | | E.S. & COVER OVER SJ 6/7/8 | P | 2 | x | 6 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-14 | PB | | 8 | 147'N OF 6/8 & 4'E ( PB 8") | P | 5 | x | 5 | 52.5 | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-15 | BO | 9/10 | | 52'N OF SEOS | P | 2 | x | 3 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-16 | DS-3 | 11/12 | | 100'N OF SEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-17 | CF | 13/14 | | 46'S OF NEOS (VALLEY DESIGN) | P | 2 | x | 42 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-18 | DSX-1 | | 13 | ON RP-17 | P | 2 | X | 6 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-19 | DS-4 | 14/15 | | 16'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-20 | CF | 14/15 | 15 | 57'S OF NEOS | P | 2 | x | 20 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-21 | CF | 15/16 | | 37'S OF NEOS | P | 2 | x | 16 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-22 | BO | 16/17 | | 23'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | | 7/30/15 |
| RP-23 | DS-5 | 17/18 | | 75'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-24 | PB | 16 | | 80'S OF 16/17 & 13'W (MH 48") | P | 10 | x | 10 | 174.7 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-25 | CF | 15/16 | | 78'S OF NEOS | P | 2 | x | 15 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-26 | CF | | 16 | 100'S OF 16/17 & 15'W | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-27 | BO | 16/17 | | 80'S OF NEOS (PATCH)& 7'W (EXT) | P | 2 | x | 2 | 84 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-28 | BO | 16/17 | | 115'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-29 | BO | 16/17 | | 130'S OF NEOS | P | 2 | x | 8 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-30 | SI | | 17 | 110'S OF 17/18 & 4'W | P | 2 | x | 2 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-31 | BO | 17/18 | | 101'S OF NEOS | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-32 | AO | | 15 | SEOP (TRIANGLE ) | B | | x | | 324 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-33 | CF | | 16 | 134'S OF 16/17 & 6'W | P | 2 | x | 13 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-34 | DSX-2 | RP-32/15 | 15 | 10'E OF RP-32 | P | 2 | x | 4.5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-35 | WR | | 17 | 94'S OF 16/17 & 3'W | P | 2 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-36 | WR | | 17 | 88'S OF 16/17 & 3'W | P | 1.5 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-37 | WR | | 17 | 88'S OF 16/17 & 15'W | P | 2 | x | 6 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-38 | WR | | 17 | 101'S OF 16/17 & 10'W | P | 2 | x | 8 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-39 | DS-6 | 20/21 | | 155'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-40 | BO | 20/21 | | 128'S OF NEOS | P | 2 | x | 7 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-41 | WR | | 18 | 75'S OF 18/19 & 11'W | P | 2 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-42 | CR | 17/18 | | 60'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-43 | WR | | 18 | 55'S OF 18/19 & 8'W | P | 2 | x | 7 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-44 | BO | 18/19 | | 55'S OF NEOS | P | 2 | x | 6 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-45 | WR | | 19 | 33'S OF 19/20 & 10'W | P | 2 | X | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-46 | WR | 19/20 | | 29'S OF NEOS | P | 2 | x | 4.5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-47 | WR | | 19 | 33'S OF 19/20 &15'W | P | 1.5 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-48 | WR | | 19 | 21'S OF 19/20 & 9'W | P | 2 | x | 2 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-49 | WR | | 19 | 14'S OF 19/20 & 11'W | P | 1.5 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-50 | WR | | 20 | 30'S OF 20/21 & 14'W | P | 1.5 | x | 2 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-51 | BO | 20/21 | | 30'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-52 | WR | | 17 | BETWEEN RP-35 & RP-38 | B | | x | | 60 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-53 | WR | | 17 | BETWEEN RP-36 & RP-38 | B | | x | | 108 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-54 | WR | | 17 | BETWEEN RP-37 & RP-38 | B | | x | | 96 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-55 | CF | | 16 | BETWEEN RP-24 & RP-27 | B | | x | | 60 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-56 | CF | | 18 | BETWEEN RP-41 & RP-43 | B | | x | | 180 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-57 | CF | | 18 | BETWEEN RP-42 & RP-43 | B | | x | | 156 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-58 | CF | | 19 | BETWEEN RP-48 & RP-49 | B | | x | | 60 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-59 | CF | | 19 | BETWEEN RP-47 & RP-48 | B | | x | | 72 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-60 | CF | | 19 | BETWEEN RP-45,RP-46& RP-48 | B | | x | | 180 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-61 | CF | | 20 | BETWEEN RP-50 & RP-51 | B | | x | | 144 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-62 | WR | | 21 | 10'S OF 21/22 & 8'W | P | 2 | x | 14 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-63 | WR | | 21 | 6'S OF 21/22 & 13'W | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-64 | WR | | 21 | BETWEEN RP-63 & RP-65 | B | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-65 | WR | | 21 | 20'S OF 21/22 & 18'W | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-66 | WR | | 22 | 20'S OF 22/23 & 5'W | P | 1.5 | x | 12 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-67 | BO | 21/22 | | 84'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-68 | BO | 22/23 | | 76'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-69 | WR | | 22 | 130'S OF 21/22 & 6'E | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-70 | WR | | 22 | BETWEEN RP-69 & RP-71 | B | | x | | 60 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-71 | CR | 21/22 | | 137'S OF NEOS | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-72 | WR | | 21 | BETWEEN RP-71 & RP-73 | B | | x | | 24 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-73 | WR | | 21 | 130'S OF 21/22 & 4'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-74 | WR | | 21 | BETWEEN RP-73 & RP-75 | B | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-75 | WR | | 21 | 129'S OF 21/22 & 9'W | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-76 | BO | 22/23 | | 97'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-77 | WR | | 23 | 118'S OF 22/23 & 7'E | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-78 | WR | | 23 | BETWEEN RP-77 & RP-79 | B | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-79 | WR | | 23 | 124'S OF 22/23 & 7'E | P | 2 | x | 11 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-80 | WR | | 23 | BETWEEN RP-79 & RP-81 | B | | x | | 84 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-81 | WR | | 23 | 134'S 22/23 & 9'E | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-82 | DS-7 | 23/24 | | 87'S OF NEOS | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-83 | DSX-3 | RP-82/23 | | ON RP-82/83( 87'S OF NEOS) | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-84 | CR | 23/24 | | 116'S OF NEOS | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-85 | CF | | 23 | 125'S OF 23/24 & 3'W | P | 2 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-86 | CF | | 23 | BETWEEN RP-85 & RP-87 | B | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-87 | CF | | 23 | 140'S OF 23/24 & 10'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-88 | BO | 24/25 | | 127'S OF NEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-89 | WR | | 24 | BETWEEN RP-88 & RP-90 | B | | x | | 60 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-90 | WR | | 24 | 127'S OF 24/25 & 5'W | P | 2 | x | 2.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-91 | CF | | 25 | 100'N OF 25/26 & 6'W | P | 2 | x | 6 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-92 | CF | | 25 | BETWEEN RP-91 & RP-93 | B | | X | | 120 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-93 | CF | | 25 | 121'N OF 25/26 & 12'W ( T-SHAPE) | P | 2 | x | 22 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-94 | CF | | 25 | BETWEEN RP-93 & RP-95 | B | | x | | 84 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-95 | CF | 25/26 | | 110'N TO 129'N OF SEOS | P | 2 | x | 19 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-96 | DS-8 | 26/27 | | 128'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-97 | BO | 26/27 | | 71'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-98 | CF | | 27 | BETWEEN RP-97 & RP-100 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-99 | CR | 26/27 | | 38'N OF SEOS | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-100 | CF | | 27 | 55'N OF 26/27 & 13'E | P | 2 | x | 30 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-101 | CF | | 27 | BETWEEN RP-100 & RP-102 | B | | x | | 144 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-102 | CF | | 27 | 87'N OF 26/27 & 7'E | P | 2 | x | 6.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-103 | CF | 27/28 | | 117'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-104 | CF | | 28 | BETWEEN RP-103 & RP-105 | B | | x | | 156 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-105 | BO | 28/29 | | 120'N OF SEOS | P | 2 | x | 15 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-106 | CF | | 28 | BETWEEN RP-105 & RP-107 | B | | x | | 192 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-107 | CF | | 28 | 134'N OF 27/28 & 4'E | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-108 | BO | 29/30 | | 125'N OF SEOS | P | 2 | x | 10 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-109 | DS-9 | 29/30 | | 80'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-110 | CF | | 28 | 85'N OF 28/29 & 3'W | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-111 | CF | | 28 | BETWEEN RP-110 & RP-112 | B | | x | | 180 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-112 | WR | 28/29 | | 68'N OF SEOS | P | 2 | x | 8 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-113 | WR | | 28 | BETWEEN RP-112 & RP-114 | B | | x | | 36 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-114 | WS | 28/29 | | 73'N OF SEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-115 | BO | 28/29 | | 61'N OF SEOS | P | 1.5 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-116 | WR | | 28 | 29'N OF 27/28 & 1'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-117 | WR | | 28 | BETWEEN RP-116 & RP-118 | B | | x | | 72 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-118 | WR | | 28 | 29'N OF 27/28 &9'E | P | 2 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-119 | WR | | 28 | BETWEEN RP-118 & RP-120 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-120 | WR | | 28 | 29'N OF 27/28 & 13'E | P | 1 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-121 | BO | 27/28 | | 34'N OF SEOS | P | 2 | x | 7 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-122 | CF | | 27 | BETWEEN RP-121 & RP-123 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-123 | CF | | 27 | 34'N OF 27/28 & 5'W | P | 1.5 | x | 1.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-124 | CF | | 28 | 34'N OF 27/28 & 10'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-125 | CF | | 28 | BETWEEN RP-124 & RP-126 | B | | x | | 108 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-126 | CF | | 28 | 45'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-127 | CF | | 28 | BETWEEN RP-126 & RP-128 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-128 | CF | | 28 | 48'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-129 | PB | | 11 | 80'N OF 10/11 & 8'E (PB 8") | P | 3 | x | 3 | 52.5 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-130 | DS-10 | 32/33 | | 20'N OF SEOS | P | 2 | x | 5.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-131 | DSX-4 | RP-102/27 | | ON EASTSIDE OF RP-102/27 | P | 2 | x | 5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-132 | PB | | 32 | 13'N OF 31/32 & 1'E (PB 4") | P | 3 | x | 4 | 36.6 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-133 | WR | 33/34 | | SEOS TO 21'N | P | 2.5 | x | 21 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-134 | WR | | 34 | BETWEEN RP-133 & RP-135(N.SIDE) | B | | x | | 84 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-135 | WR | | 34 | 18'N OF 33/34 & 11'E | P | 3 | x | 10 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-136 | WR | | 34 | FROM RP-135 TO SEOP | B | | x | | 180 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-137 | WR | | 34 | BETWEEN RP-133 & RP-135(S.SIDE) | B | | x | | 120 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-138 | WR | | 34 | BETWEEN RP-137 & RP-139 | B | | x | | 36 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-139 | WR | | 34 | 13'N OF 33/34 & 6'E | P | 1.5 | x | 1.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-140 | WR | | 34 | BETWEEN RP-135 & RP-141 | B | | x | | 168 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-141 | WR | | 34 | 36'N OF 33/34 & 10'E | P | 1 | x | 2 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-142 | CF | | 30 | 112'N OF 29/30 & 5'E | P | 2 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-143 | CF | | 30 | BETWEEN RP-142 & RP-144 | B | | x | | 48 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-144 | CF | | 30 | 98'N OF 29/30 & 7'E | P | 1.5 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-145 | DS-11 | 36/37 | | 90'W OF EEOS & SJ 34/36/37 | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-146 | SJ | 41/44/45 | | SJ 41/44/45 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-147 | SJ | 44/45/46 | | SJ 44/45/46 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-148 | SJ | 40/41/44 | | SJ 40/41/44 | P | 2 | x | 5.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-149 | SJ | 34/40/41 | | SJ 34/40/41 | P | 3 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-150 | SJ | 34/39/40 | | SJ 34/39/40 | P | 1.5 | x | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-151 | SJ | 34/38/39 | | SJ 34/38/39 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-152 | SJ | 34/37/38 | | SJ 34/37/38 | P | 2 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-153 | BO | 35/36 | | 84'W OF EEOS | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-154 | WR | | 36 | BETWEEN RP-153 & RP-155 | B | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-155 | WR | | 36 | 84'W OF 35/36 & 5'S | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-156 | SJ | 34/35/36 | | SJ 34/35/36 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-157 | BO | 34/35 | | 10'S OF NEOS | P | 1.5 | X | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-158 | WR | | 35 | 65'W OF 35/36 & 11'N | P | 1.5 | X | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-159 | WR | | 35 | FROM RP-158 TO N.END OF P-35 | P | | x | | 144 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-160 | DS-12 | 42/43 | | 20'N OF SEOS | P | 2 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-161 | SJ | 43/44/46 | | SJ 43/44/46 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-162 | WR | 44/46 | | 5'W OF EEOS | P | 1.5 | X | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-163 | WR | | 44 | BETWEEN RP-162 & RP-164 | B | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-164 | WR | | 44 | 5'W OF 44/46 & 5'N | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-165 | WR | | 44 | BETWEEN RP-162 RP-166 | B | | x | | 216 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-166 | WR | 40/44 | | 16'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-167 | SJ | 40/42/43 | | SJ 40/42/43 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-168 | SJ | 39/40/42 | | SJ 39/40/42 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-169 | SJ | 38/39/42 | | SJ 38/39/42 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-170 | SJ | 37/38/42 | | SJ 37/38/42 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-171 | SJ | 36/37/42 | | SJ 36/37/42 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-172 | WR | 36/42 | | 6'S OF NEOS | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-173 | WR | | 42 | BETWEEN RP-172 & RP-174 | B | | x | | 108 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-174 | WR | | 42 | 6'S OF 36/42 & 10'E | P | 3 | x | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-175 | CR | 35/42 | | 15'S OF NEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-176 | WR | | 42 | BETWEEN RP-174 & RP-175 | B | | x | | 132 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-177 | SJ | 35/36/42 | | SJ 35/36/42 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-178 | CR | 35/36 | | 15'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-179 | WR | | 35 | 30'W OF 35/36 & 10'N | P | 2 | x | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-180 | WR | | 35 | FROM RP-179 TO N.END OF P-35 | B | | x | | 156 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-181 | CR | 44/45 | | 11'W OF EEOS | P | 1.5 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBIOX | P | 8/4/15 |
| RP-182 | WR | | 44 | BETWEEN RP-181 & RP-183 | B | | x | | 204 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-183 | CR | 40/44 | | 42'W OF EEOS | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-184 | BO | 40/44 | | 48'W OF EEOS | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-185 | SJ | 40/43/44 | | SJ 40/43/44 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-186 | DSX-5 | RP-160/42 | | ON RP-160/42 | P | 2 | x | 5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-187 | WR | | 42 | 7'N OF 39/42 &1'E TO 6'E | B | | x | | 78 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-188 | PB | | 25 | 74'S OF 24/25 & 5'E (PB 8") | P | 3 | x | 3 | 52.5 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-189 | WR | | 35 | 15'W OF 35/36 & 16'N | P | 2 | x | 7 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-190 | WR | | 35 | BETWEEN RP-189 & RP-191 | B | | x | | 84 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-191 | WR | | 35 | 15'W OF 35/36 & 6'N | P | 1.5 | x | 1.5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-192 | WR | | 36 | 10'W OF 36/37 & 7'N | P | 1.5 | x | 2 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-193 | WR | | 36 | BETWEEN RP-192 & RP-194 | B | | x | | 180 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-194 | WR | | 36 | 10'W OF 36/37 & 24'N | P | 2 | x | 4 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-195 | BO | 47/48 | | 106'S OF NEOS | P | 2 | x | 6.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-196 | BO | 48/49 | | 86'S OF NEOS | P | 2 | x | 4 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-197 | BO | 53/54 | | 15'S OF NEOS | P | 2 | x | 7 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-198 | WR | 48/49 | | 94'S OF NEOS | P | 2 | x | 28 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-199 | CR | 42/47 | | 50'S OF NEOS | P | 2 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-200 | CF | | 47 | 56'S OF NEOS(SURFACE DESIGN) | P | 2 | x | 38 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-201 | CF | | 47 | 38'S OF 42/47 & 8'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-202 | CF | | 47 | BETWEEN RP-201 & RP-203 | B | | x | | 240 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-203 | CF | | 47 | 59'S OF 42/47 & 18'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-204 | DS-13 | 47/48 | | 70'S OF NEOS | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-205 | CF | | 47 | FROM RP-200 TO MANHOLE | B | | x | | 216 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-206 | WR | | 48 | 46'S OF 47/48 & 4'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-207 | WR | | 48 | BETWEEN RP-206 & RP-208 | B | | x | | 180 | 8/7/15 | PEDRO S. | EXT 512 | VNOX | P | 8/7/15 |
| RP-208 | WR | | 48 | 64'S OF 48/49 & 6'W | P | 2 | x | 11 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-209 | WR | | 48 | BETWEEN RP-208 & RP-210 | B | | x | | 36 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-210 | WR | | 48 | 57'S OF 48/49 & 4'W | P | 2.5 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-211 | DSX-6 | RP-198/48 | | ON W.END OF RP-198/48 | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-212 | WR | 49/50 | | 72'S OF NEOS | P | 2 | x | 9 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-213 | WR | | 50 | 75'S OF 49/50 & 8'E | P | 2 | x | 7 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-214 | WR | | 50 | BETWEEN RP-213 & RP-215 | B | | x | | 24 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-215 | WR | | 50 | 78'S OF 49/50 & 2'E | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | F | 8/10/15 |
| RP-216 | SJ | 50/51/52 | | SJ 50/51/52 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-217 | SJ | 51/52/53 | | SJ 51/52/53 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-218 | PB | | 47 | 87'S OF 42/47 & 11'E(MH 48" ) | P | 9.5 | x | 9.5 | 175 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-219 | PB | | 38 | 3'W OF 37/38 & 3'S (PB 8") | P | 3.5 | x | 4 | 52.5 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-220 | BO | 55/57 | | 101'N OF SEOS | P | 2 | x | 2.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-221 | BO | 55/57 | | 120'N OF SEOS | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-222 | WR | | 50 | REPAIR LEAK OVER RP-215 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-223 | DS-14 | 50/51 | | 35'S OF NEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-224 | WR | 51/53 | | 20'S OF NEOS | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-225 | WR | | 53 | BETWEEN RP-224 & RP-226 | B | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-226 | WR | | 53 | 20'S OF 51/53 & 14'E | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-227 | WR | | 53 | 30'S OF 53/54 & 5'W | P | 1.5 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-228 | WR | | 53 | BETWEEN RP-227 & RP-229 | B | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-229 | WR | | 53 | 35'S OF 51/53 & 5'W | P | 2 | x | 11 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-230 | DS-15 | 54/55 | | 72'S OF NEOS | P | 2 | x | 4.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-231 | SJ | 54/55/56 | | SJ 54/55/56 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-232 | SJ | 55/56/57 | | SJ 55/56/57 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-233 | CF | | 55 | 76'N OF 55/57 & 3'W | P | 2 | X | 13 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-234 | CF | | 55 | BETWEEN RP-233 & RP-235 | B | | x | | 24 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-235 | CF | | 55 | 80'N OF 55/57 & 2'W | P | 2 | x | 3.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-236 | CF | | 58 | 128'S OF 57/58 7'E | P | 3 | x | 4 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-237 | CF | | 58 | BETWEEN RP-236 & RP-238 | B | | x | | 168 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-238 | CF | | 58 | 140'S OF 57/58 & 20'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-239 | CF | | 58 | BETWEEN RP-236 & RP-240 | B | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-240 | CF | | 58 | 125'S OF 57/58 & 17'E | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-241 | CF | | 58 | BETWEEN RP-239 & RP-242 | B | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-242 | CF | | 58 | 128'S OF 57/58 & 15'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-243 | PB | | 58 | 75'S OF 57/58 & 6'E (PB 8") | p | 4 | x | 4 | 52.5 | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-244 | SJ | 58/59/60 | | SJ 58/59/60 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-245 | DSX-7 | RP-197/53 | | ON RP-197/53 | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-246 | PB | | 62 | 135'N OF 61/62 & 2'E (PB 8") | P | 3 | x | 4 | 52.5 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-247 | SJ | 59/60/61 | | SJ 59/60/61 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-248 | DS-16 | 59/61 | | 6'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-249 | DS-17 | 62/63 | | 90'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-250 | CR | | 65 | 2'N OF 65/66 & 5'E | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-251 | SJ | 64/65/66 | | SJ 64/65/66 | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-252 | BO | 65/66 | | 8'N OF SEOS | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-253 | DS-18 | 64/65 | | 128'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-254 | DS-19 | 68/69 | | 100'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-255 | PB | | 71 | 9'N OF 71/72 & 5'W (PB 4") | P | 5 | x | 6 | 36.6 | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-256 | DS-20 | 72/73 | | 10'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-257 | PB | | 74 | 92'N OF 73/74 & 1'E (PB 8") | P | 3.5 | x | 4 | 52.5 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/14/15 |
| RP-258 | BO | 71/72 | | 57'N OF SEOS | P | 2 | x | 2 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-259 | BO | 71/72 | | 133'N OF SEOS | P | 2 | x | 2.5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-260 | BO | 74/75 | | 60'N OF SEOS | P | 2 | x | 6 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-261 | DS-21 | 74/75 | | 75'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-262 | PB | 78/79 | | WEOS (MH 48") | P | 10 | x | 11 | 175 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-263 | CF | | 73 | FROM RP-264 TO 4'N | B | | x | | 48 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-264 | CF | | 73 | 23'N OF 72/73 & 5'E | P | 2.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-265 | CF | | 73 | BETWEEN RP-264 & RP-266 | B | | x | | 84 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-266 | CF | | 73 | 14'N OF 72/73 & 7'E | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-267 | CF | | 73 | BETWEEN RP-266 & RP-272 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-268 | CF | | 73 | FROM RP-269 TO 3'W | B | | x | | 36 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-269 | CF | | 73 | 14'N OF 72/73 &18'E | P | 2 | x | 9 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-270 | CF | | 73 | BETWEEN RP-269 & RP-271 | B | | x | | 108 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-271 | CF | | 73 | 4'N OF 72/73 & 9'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-272 | CF | | 73 | 15'N OF 72/73 & 15'E | P | 2 | x | 10 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-273 | CF | | 73 | BETWEEN RP-272 & RP-274 | B | | x | | 36 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-274 | CF | | 73 | 23'N OF 72/73 & 15'E | P | 2 | x | 6 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-275 | CF | | 73 | FROM RP-274 TO 5'N | B | | x | | 60 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-276 | CF | | 73 | FROM RP-277 TO 12'E | B | | x | | 144 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-277 | CF | | 73 | 50'N OF 72/73 & 5'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-278 | CF | | 73 | 46'N OF 73/74 & 5'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-279 | CF | | 73 | BETWEEN RP-278 & RP-280 | B | | x | | 156 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-280 | CF | | 73 | 59'N OF 73/74 & 16'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-281 | CF | | 71 | 137'N OF 71/72 & 2'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-282 | CF | | 71 | BETWEEN RP-281 & RP-283 | B | | x | | 120 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-283 | CF | | 71 | 125'N OF 71/72 & 8'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-284 | CF | | 71 | 164'N OF 71/72 & 8'W | P | 2 | x | 4 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-285 | CF | | 71 | BETWEEN RP-284 & RP-286 | B | | x | | 132 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-286 | CF | | 71 | 142'N OF 71/72 & 3'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-287 | CF | | 71 | FROM RP-288 TO 8'N | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-288 | CF | | 71 | 137'N OF 71/72 & 9.5' W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-289 | DSX-8 | RP-284/71 | | ON RP-284/71 | P | 2 | x | 5 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-290 | WR | 68/69 | | 132'N OF SEOS | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-291 | WR | | 68 | BETWEEN RP-290 & RP-292 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-292 | WR | | 68 | 126'N OF 68/69 & 10'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-293 | SI | | 57 | 136'N OF 56/57 & 7'E | P | 2 | x | 2 | | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-294 | SJ | | | SJ 75/80/81 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-295 | SJ | | | SJ 75/79/80 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-296 | SJ | | | SJ 75/77/78 | P | 2 | x | 3 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-297 | SJ | | | SJ 75/76/77 | P | 1 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-298 | DS-22 | 79/80 | | 78'E OF WEOS | P | 2 | x | 4 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-299 | SJ | | | SJ 75/81/82 | P | 2.5 | x | 14 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-300 | SJ | | | SJ 81/82/83 | P | 1.5 | x | 1.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-301 | SJ | | | SJ 81/83/84 | P | 1 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-302 | SJ | | | SJ 83/84/85 | P | 2 | x | 4 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-303 | SJ | | | SJ 84/85/86 | P | 1 | x | 1 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-304 | WR | 84/85 | | 7'W OF EEOS | P | 1.5 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-305 | WR | | 84 | BETWEEN RP-304 & RP-306 | B | | x | | 204 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-306 | WR | | 84 | 7'W OF 84/85 & 17'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-307 | WR | | 84 | FROM RP-308 TO 12'SW | B | | x | | 144 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-308 | WR | | 84 | 20'E OF 81/84 & 13'S | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-309 | WR | 75/82 | | 14'N OF SEOS | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-310 | WR | | 82 | BETWEEN RP-309 & RP-311 | B | | x | | 240 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-311 | WR | 82/83 | | 15'N OF SEOS | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-312 | WR | | 82 | 6'N OF 82/83 & 6.5' W | P | 1.5 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-313 | WR | | 82 | BETWEEN RP-312 & RP-314 | B | | x | | 132 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-314 | WR | | 82 | 19'N OF 82/83 & 6'W | P | 1.5 | x | 1.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-315 | BO | 81/84 | | 24'E OF WEOS | | | x | | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-316 | DS-23 | 88/89 | | 116'N OF SEOS | p | 2 | x | 4.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-317 | WR | | 79 | BETWEEN RP-298 & RP-318 | B | | x | | 66 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-318 | WR | | 79 | 78'E OF 79/80 & 7'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-319 | BO | 81/87 | | 8'N OF SEOS | P | 2 | x | 5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-320 | SJ | | | SJ 80/81/87 | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-321 | SJ | | | SJ 79/80/87 | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-322 | WR | 79/87 | | 6'N OF SEOS | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-323 | SJ | | | SJ 78/79/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-324 | SJ | | | SJ 77/78/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-325 | SJ | | | SJ 76/77/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-326 | CF | 89/90 | | 145'N OF SEOS | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-327 | CF | | 89 | 145'N OF 89/90 & 6'W | B | | x | | 72 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-328 | CF | 89/90 | | 81'N OF NEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-329 | CF | | 89 | 81'N OF 89/90 & 5'W | B | | x | | 60 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-330 | DSX-9 | RP-316/88 | | RP-316/88 | P | 2 | x | 4.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-331 | SI | | 83 | 9'S OF 83/84 & 8'W (END OF PANEL) | P | 2 | x | 18 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-332 | SJ | | | SJ 84/86/87 | P | 3 | x | 12 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-333 | CR | | 84/86 | EEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-334 | WR | | 84 | BETWEEN RP-315 & RP-335 | B | | x | | 12 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-335 | WR | | 84 | 7'W OF 81/84 & 3.5'S | P | 3 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-336 | SJ | | | SJ 81/84/87 | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-337 | CF | 84/87 | | BETWEEN RP-332 & RP-336 | B | | x | | 216 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-338 | WR | 81/84 | | 24'E TO EEOS | B | | x | | 36 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-339 | WR | | 81 | 11'N OF 81/87 & 4'W | P | 1.5 | x | 1.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-340 | WR | | 81 | BETWEEN RP-339 & RP-341 | B | | x | | 138 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-341 | WR | | 81 | 13'W OF 81/84 & 3'N | P | 2 | x | 3.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-342 | AO | | 76 | ADD ON NORTH SIDE OF P-76 | P | 8 | x | 16 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-343 | CF | 76/77 | | 66'E OF WEOS | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-344 | CF | | 77 | BETWEEN RP-343 & RP-345 | B | | x | | 36 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-345 | CF | | 77 | 66'E OF 76/77 & 5'S | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-346 | CF | | 77 | BETWEEN RP-345 & RP-347 | B | | x | | 48 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-347 | CF | | 77 | 66'E OF 76/77 & 10'S | P | 1.5 | x | 1.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-348 | WR | | 85 | 4'W OF 84/85 & 4'S | B | | x | | 48 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-349 | WR | | 84 | 4'W OF 84/85 & 8'N | B | | x | | 96 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-350 | DS-24 | 91/92 | | 45'N OF SEOS | P | 2 | x | 5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-351 | CF | 91/92 | | 151'N OF SEOS | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-352 | CF | | 91 | BETWEEN RP-351 & RP-353 | B | | x | | 216 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-353 | CF | | 91 | 151'N OF 91/92 & 19.5'W | P | 3 | x | 3 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-354 | CF | 93/94 | | 144'N OF SEOS | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-355 | CF | | 94 | BETWEEN RP-354 & RP-356 | B | | x | | 72 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-356 | CF | | 94 | 144'N OF 93/94 & 10'E | P | 2 | x | 4.5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-357 | CF | | 90 | 29'N OF 90/91 & 4'W | P | 2 | x | 3 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-358 | CF | | 90 | BETWEEN RP-357 & RP-359 | B | | x | | 60 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-359 | CF | | 90 | 31'N OF 90/91 & 9'W | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-360 | CF | | 90 | BETWEEN RP-359 & RP-361 | B | | x | | 24 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-361 | CF | | 90 | 31'N OF 90/91 & 13'W | P | 2 | x | 2.5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-362 | WR | | 80 | 11'S OF 80/87 & 5'W | P | 1 | x | 2 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-363 | WR | | 80 | BETWEEN RP-362 & RP-365 | B | | x | | 54 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-364 | WR | 79/80 | | 8.5'W OF EEOS | P | 2 | x | 2 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-365 | WR | | 8O | 5'S OF 80/87 & 10'W | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-366 | WR | | 80 | BETWEEN RP-364 & RP-365 | B | | x | | 60 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-367 | DS-25 | 94/95 | | 100'N OF SEOS | P | 2 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-368 | CF | 94/95 | | 125'N OF SEOS | P | 2 | x | 6 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-369 | PB | | 95 | 95'N OF 94/95 & 6'E (PB 8") | P | 4 | x | 4.5 | 52.5 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-370 | CF | 94/95 | | 33'N OF SEOS | P | 2.5 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-371 | CF | | 95 | BETWEEN RP-370 & RP-372 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-372 | CF | | 95 | 33'N OF 94/95 & 6.5'E | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-373 | BO | 95/96 | | 128'S OF NEOS | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-374 | DS-26 | 96/97 | | 33'S OF NEOS | P | 2 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-375 | CF | 96/97 | | 95'S OF NEOS | P | 2 | x | 8 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-376 | CF | 96/97 | | FROM RP-377 TO 117'S | P | 2 | x | 14 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-377 | CF | | 96 | 101'S OF 96/97 TO 15'W | P | 4 | x | 15 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-378 | CF | | 96 | 105'S OF OF 96/97 & 13'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-379 | CF | | 96 | 101'S OF 96/97 & 17'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-380 | CF | | 96 | 93'S OF 96/97 & 8'W | P | 2.5 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-381 | CF | | 96 | BETWEEN RP-380 & RP-382 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-382 | CF | | 96 | 86.5'S OF 96/97 & 4'W | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-383 | BO | 103/104 | | 16'W OF EEOS | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-384 | BO | 97/103 | | 12'S OF NEOS | | | x | | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-385 | SI | | 94 | 126'N OF 94/95 & 8'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-386 | DSX-10 | RP-376/96 | | RP-376/96 (DSX-10 ) | P | 2 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-387 | SJ | | | SJ 97/103/104 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-388 | CF | | 97 | BETWEEN RP-384 & RP-389 | B | | x | | 24 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-389 | CF | | 97 | 12'S OF 97/103 & 3.5'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-390 | SJ | | | SJ 97/102/103 | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-391 | SJ | | | SJ 97/101/102 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-392 | SJ | | | SJ 97/100/101 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-393 | SJ | | | SJ 97/99/100 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-394 | SJ | | | SJ 97/98/99 | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-395 | CF | | 103 | FROM RP-383 TO 5'N | B | | x | | 60 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-396 | CF | | 103 | 4'N FROM RP-397 & 14'NW | B | | x | | 168 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-397 | SJ | | | SJ 103/104/105 | P | 2 | x | 3.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-398 | SJ | | | SJ 103/105/106 | P | 3 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-399 | CF | | 107 | 122'S OF 107/108 & 4'W | B | | x | | 192 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-400 | SJ | | | SJ 103/106/107 | P | 2 | x | 2.5 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-401 | SJ | | | SJ 102/103/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-402 | SJ | | | SJ 101/102/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-403 | SJ | | | SJ 100/101/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-404 | SJ | | | SJ 99/100/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-405 | SJ | | | SJ 98/99/107 | P | 1.5 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-406 | CF | | 98 | FROM RP-412 TO N.E. CORNER | B | | x | | 144 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-407 | CF | | 98 | FROM RP-412 TO N.W. CORNER | B | | x | | 168 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-408 | CF | | 107 | 13'S OF 107/108 & 4.5'W | P | 1.5 | x | 3 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-409 | CF | | 107 | BETWEEN RP-408 & RP-411 | B | | x | | 168 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-410 | CF | | 107 | 6'S OF 107/108 & 5'W | B | | x | | 60 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-411 | CF | | 107 | 5'S OF 98/107 & 4'E | P | 1.5 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-412 | CF | | 98 | BETWEEN RP-406 & RP-407 | P | 2 | x | 22 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-413 | CF | | 108 | 143'S OF 108/109 & 3'E | P | 1.5 | x | 1.5 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-414 | CF | | 108 | FROM RP-413 TO 17'S | B | | x | | 204 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-415 | CF | | 107 | FROM RP-416 TO 4'W | B | | x | | 48 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-416 | CF | | 107 | 154'S OF 107/108 & 6'W | P | 2 | x | 4 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-417 | CF | | 107 | FROM RP-416 TO 4'E | B | | x | | 48 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-418 | PB | | 109 | 152'S OF 108/109 & 2.5'E (PB 4") | P | 4 | x | 6 | 36.6 | 9/23/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/23/15 |
| RP-419 | PB | 111/112 | | 15'S OF NEOS (PB 8") | P | 3.5 | x | 4.5 | 52.5 | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-420 | PB | | 113 | 82'S OF 112/113 & 14' ( MH 48" ) | P | 9 | x | 11 | 175 | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-421 | BO | 113/114 | | 28'S OF NEOS | P | 2 | x | 4.5 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-422 | DS-27 | 110/111 | | 120'S OF NEOS | P | 2 | x | 5 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-423 | SI | | 111 | 15'S OF 111/112 & 6'E | P | 1.5 | x | 2 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-424 | DSX-11 | RP-421/114 | | RP-421/114 (DSX-11 ) | P | 2 | x | 6 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-425 | PB | 114/115 | | 68'S OF NEOS (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/8/15 |
| RP-426 | CF | 115/116 | | 28'S OF NEOS | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-427 | CF | 117/118 | | 121'S OF NEOS | P | 2 | x | 13 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-428 | WR | | 115 | 12'S OF 114/115 & 3'E | P | 2 | x | 3.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-429 | WR | | 115 | BETWEEN RP-428 & RP-430 | B | | x | | 120 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-430 | WR | | 115 | 12'S OF 114/115 &15.5'E | P | 2 | x | 3.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-431 | CF | | 115 | BETWEEN RP-426 & RP-432 | B | | x | | 48 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-432 | CF | | 115 | FROM RP-431 TO 15'NW | P | 2 | x | 15 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-433 | DO | | 117 | 123'S OF 117/118 & 6'E | P | 1.5 | x | 1.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-434 | CF | | 118 | BETWEEN RP-427 & RP-435 | B | | x | | 12 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-435 | CF | | 118 | FROM RP-436 TO 5'N | B | | x | | 60 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-436 | CF | | 118 | BETWEEN RP-434 & RP-435 | P | 2 | x | 14 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-437 | CF | 119/120 | | 94'S OF NEOS | P | 2 | x | 3 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-438 | CF | 119/120 | | 22'S OF NEOS | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-439 | CF | 119/120 | | 127'S OF NEOS | P | 2 | x | 9 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-440 | CF | 119/120 | | 139'S OF NEOS | P | 2.5 | x | 4 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-441 | CF | | 119 | FROM RP-437 TO 14'W | B | | x | | 168 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-442 | CF | | 119 | BETWEEN RP-440 & RP-443 | B | | x | | 192 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-443 | CF | | 119 | 149'S OF 119/120 & 17.5'W | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-444 | CF | 119/120 | | BETWEEN RP-439 & RP-440 | B | | x | | 144 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-445 | AO | RP-445 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-446 | AO | RP-446 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-447 | SJ | | | RP-445/RP-446/122 | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-448 | SJ | | | RP-446/121/122 | P | 2.5 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-449 | CF | | 122 | FROM RP-448 TO 10'E | B | | x | | 120 | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-450 | BO | 122/123 | | 23'N OF SEOS | P | 2.5 | x | 4 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-451 | SJ | | | P122/123/124 | P | 1.5 | x | 2 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-452 | SJ | | | P 123/124/125 | P | 1.5 | x | 1.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-453 | CF | | 125 | FROM RP-454 TO 11'S | P | 3.5 | x | 11 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-454 | CF | 123/125 | | 18'N OF SEOS | P | 3 | x | 9.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-455 | CF | | 125 | FROM RP-454 TO 10'N | P | 3.5 | x | 10 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-456 | DS-28 | 123/125 | | 90'N OF SEOS | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-457 | PB | | 125 | 68'S OF P125/126 & 4'W (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-458 | SI | | 125 | ON RP-453 & RP-455 | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-459 | SI | 120,121,122, | &123 | BETWEEN RP-454 TO RP-473 | P | 2 | x | 91 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-460 | DSX-12 | RP-459/123 | | N.SIDE OF RP-459 ( DSX-12 ) | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-461 | SI | | 122 | BETWEEN RP-450 & RP-459 | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-462 | SI | | 122 | FROM RP-461 TO 3'NW | B | | x | | 36 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-463 | SI | | 122 | FROM RP-459 TO 5'S | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-464 | SI | | | SJ 121/122/RP-459 | P | 2 | x | 4 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-465 | SI | | 121 | BETWEEN RP-459 & RP-468 | B | | x | | 6 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-466 | SI | 121/122 | | FROM RP-467 TO RP-465 & RP-468 | B | | x | | 108 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-467 | SI | | 121 | 9'SE OF RP-465 , RP-466 & RP-468 | P | 2 | x | 2.5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-468 | SI | | 121 | BETWEEN RP-465 & RP-469 | B | | x | | 42 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-469 | SI | | 121 | BETWEEN RP-468 & RP-470 | B | | x | | 132 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-470 | SI | | 121 | 11'SW OF RP-468 | P | 2 | x | 3 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-471 | SI | | 121 | BETWEEN RP-468 & RP-472 | B | | x | | 12 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-472 | SI | | 121 | FROM RP-471 TO SEOP | P | 2 | x | 23 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-473 | SI | 119/120 | | BETWEEN RP-439,RP-444& RP-440 | P | 2 | x | 17 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-474 | SI | 119/120 | | NEOS TO 16'S | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-475 | SI | | 117 | NEOP & 5'W OF 117/118 | P | 2 | x | 14 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-476 | PB | 128/132 | 132 | 81'N OF SEOS & 3'E (PB 4") | P | 3 | x | 6 | 36.6 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/9/15 |
| RP-477 | SI | 125/126 | 125 | 159'S OF NEOS & 13' W | P | 2 | x | 13 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-478 | SJ | | | P 127/128/129 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-479 | SJ | | | P 128/129/132 | P | 2 | x | 3 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-480 | DS-29 | 128/132 | | 25'N OF SEOS | P | 2 | x | 7 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-481 | SJ | | | P 128/131/132 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-482 | SJ | | | P 128/130/131 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-483 | DSX-13 | RP-477/125 | | N.SIDE OF RP-477 (DSX-13) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-484 | DSX-14 | RP-480/132 | | E.SIDE OF RP-480 ( DSX-14) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-485 | SJ | | | P 132/133/143 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-486 | DSX-15 | RP-487/125 | | N.SIDE OF RP-487 (DSX-15) | P | 2 | x | 5 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-487 | FS | | 125 | DS-13 FAIL (CAP OVER RP-477/RP-483) | P | 5 | x | 15 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-488 | DO | | 123 | 6' S OF NEOS ON SCB WALL EDGE | P | 3 | x | 2.5 | | 11/4/15 | EDFY E. | EXT 512 | NA | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |

# Appendix M
# ESI Destruct Sample Information Logs

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DS-1 | 3 / 4 | 7/20/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 109 | 101 | 107 | 103 | 108 | 105 | 102 | 105 | 104 | 107 | PASS |
| | | | | | | | | Shear | 113 | | 113 | | 102 | | 109 | | 112 | | |
| | DS Location and Notes | 18'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-2 | 6 / 7 | 7/21/15 | MODESTO L. | 2003 | 500 | 860 | | Peel | 78 | 99 | 102 | 98 | 112 | 108 | 106 | 103 | 107 | 111 | PASS |
| | | | | | | | | Shear | 115 | | 118 | | 120 | | 113 | | 119 | | |
| | DS Location and Notes | 10'E OF WEOS | | | | | | | | | | | | | | | | | |
| DS-3 | 11 / 12 | 7/22/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 106 | 103 | 105 | 105 | 107 | 104 | 103 | 104 | 109 | 97 | PASS |
| | | | | | | | | Shear | 111 | | 109 | | 108 | | 105 | | 108 | | |
| | DS Location and Notes | 100'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-4 | 14 / 15 | 7/23/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 121 | 113 | 115 | 108 | 112 | 117 | 102 | 115 | 118 | 113 | PASS |
| | | | | | | | | Shear | 126 | | 128 | | 129 | | 127 | | 125 | | |
| | DS Location and Notes | 16'S OF NEOS | | | | | | | | | | | | | | | | | |
| DS-5 | 17 / 18 | 7/23/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 119 | 114 | 115 | 101 | 113 | 114 | 118 | 102 | 116 | 110 | PASS |
| | | | | | | | | Shear | 121 | | 118 | | 120 | | 123 | | 122 | | |
| | DS Location and Notes | 75'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-1 | RP-17 / 13 | 7/24/15 | EMMANUEL V. | EXT 512 | | 500 | 490 | Peel | 102 | | 103 | | 107 | | 98 | | 99 | | PASS |
| | | | | | | | | Shear | 120 | | 121 | | 117 | | 121 | | 120 | | |
| | DS Location and Notes | ON RP-17 | | | | | | | | | | | | | | | | | |
| DSX-2 | RP-32 / 15 | 7/27/15 | EMMANUEL V. | EXT 512 | | 500 | 450 | Peel | 126 | | 120 | | 123 | | 122 | | 108 | | PASS |
| | | | | | | | | Shear | 122 | | 122 | | 120 | | 119 | | 116 | | |
| | DS Location and Notes | ON RP-32/15 (10'E OF WEOS) | | | | | | | | | | | | | | | | | |
| DS-6 | 20 / 21 | 7/24/15 | MODESTO L. | 2003 | 550 | 860 | | Peel | 101 | 101 | 100 | 103 | 104 | 106 | 105 | 106 | 110 | 99 | PASS |
| | | | | | | | | Shear | 114 | | 107 | | 111 | | 110 | | 111 | | |
| | DS Location and Notes | 155'S OF NEOS | | | | | | | | | | | | | | | | | |
| DS-7 | 23 / 24 | 7/24/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 106 | 106 | 103 | 105 | 104 | 104 | 100 | 102 | 103 | 102 | PASS |
| | | | | | | | | Shear | 109 | | 111 | | 107 | | 106 | | 108 | | |
| | DS Location and Notes | 87'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-3 | RP-82 / 23 | 7/28/15 | EMMANUEL V. | EXT 512 | | 500 | 450 | Peel | 99 | | 99 | | 104 | | 98 | | 102 | | PASS |
| | | | | | | | | Shear | 109 | | 115 | | 117 | | 112 | | 118 | | |
| | DS Location and Notes | RP-82/23 ( 87'S OF NEOS) | | | | | | | | | | | | | | | | | |
| DS-8 | 26 / 27 | 7/28/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 103 | 101 | 107 | 104 | 104 | 110 | 100 | 105 | 104 | 99 | PASS |
| | | | | | | | | Shear | 122 | | 120 | | 117 | | 120 | | 121 | | |
| | DS Location and Notes | 128'N OF SEOS | | | | | | | | | | | | | | | | | |

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DS-9 | 29 / 30 | 7/28/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 111 | 108 | 114 | 107 | 104 | 100 | 111 | 107 | 110 | 110 | PASS |
| | | | | | | | | Shear | 118 | | 118 | | 117 | | 119 | | 118 | | |
| | DS Location and Notes | 80'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-10 | 32 / 33 | 7/29/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 99 | 110 | 114 | 109 | 110 | 116 | 105 | 106 | 100 | 108 | PASS |
| | | | | | | | | Shear | 118 | | 118 | | 122 | | 121 | | 119 | | |
| | DS Location and Notes | 20'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-4 | RP-102 / 27 | 7/29/15 | EMMANUEL V. | EXT 512 | | 490 | 400 | Peel | 123 | | 125 | | 119 | | 120 | | 122 | | PASS |
| | | | | | | | | Shear | 127 | | 124 | | 130 | | 129 | | 128 | | |
| | DS Location and Notes | ON EAST SIDE OF RP-102/27 | | | | | | | | | | | | | | | | | |
| DS-11 | 36 / 37 | 8/3/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 104 | 99 | 104 | 104 | 98 | 104 | 97 | 106 | 98 | 107 | PASS |
| | | | | | | | | Shear | 113 | | 112 | | 112 | | 115 | | 113 | | |
| | DS Location and Notes | 90'W OF EEOS | | | | | | | | | | | | | | | | | |
| DS-12 | 42 / 43 | 8/3/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 101 | 105 | 106 | 103 | 110 | 100 | 109 | 104 | 101 | 103 | PASS |
| | | | | | | | | Shear | 111 | | 110 | | 115 | | 116 | | 116 | | |
| | DS Location and Notes | 20'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-5 | RP-160 / 42 | 8/4/15 | PEDRO S. | EXT 512 | | 500 | 500 | Peel | 91 | | 98 | | 111 | | 109 | | 111 | | PASS |
| | | | | | | | | Shear | 118 | | 119 | | 116 | | 115 | | 110 | | |
| | DS Location and Notes | ON RP-160/42 | | | | | | | | | | | | | | | | | |
| DS-13 | 47 / 48 | 8/5/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 118 | 101 | 113 | 103 | 112 | 105 | 110 | 100 | 103 | 116 | PASS |
| | | | | | | | | Shear | 129 | | 121 | | 123 | | 122 | | 122 | | |
| | DS Location and Notes | 70'S OF NEOS | | | | | | | | | | | | | | | | | |
| DS-14 | 50 / 51 | 8/6/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 109 | 112 | 117 | 108 | 113 | 110 | 114 | 112 | 112 | 111 | PASS |
| | | | | | | | | Shear | 132 | | 130 | | 128 | | 131 | | 132 | | |
| | DS Location and Notes | 35'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-6 | RP-198 / 48 | 8/6/15 | PEDRO S. | EXT 512 | | 530 | 530 | Peel | 121 | | 125 | | 122 | | 119 | | 116 | | PASS |
| | | | | | | | | Shear | 118 | | 119 | | 121 | | 118 | | 118 | | |
| | DS Location and Notes | ON RP-198/48 | | | | | | | | | | | | | | | | | |
| DS-15 | 54 / 55 | 8/7/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 101 | 107 | 105 | 107 | 106 | 103 | 101 | 99 | 100 | 106 | PASS |
| | | | | | | | | Shear | 121 | | 119 | | 119 | | 126 | | 120 | | |
| | DS Location and Notes | 72'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-7 | RP-197 / 53 | 8/10/15 | PEDRO S. | EXT 512 | | 530 | 530 | Peel | 109 | | 109 | | 110 | | 112 | | 109 | | PASS |
| | | | | | | | | Shear | 119 | | 121 | | 120 | | 123 | | 119 | | |
| | DS Location and Notes | ON RP-197/53 | | | | | | | | | | | | | | | | | |
| DS-16 | 59 / 61 | 8/10/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 106 | 110 | 100 | 98 | 103 | 100 | 101 | 105 | 100 | 99 | PASS |
| | | | | | | | | Shear | 121 | | 123 | | 119 | | 117 | | 124 | | |
| | DS Location and Notes | 6'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-17 | 62 / 63 | 8/10/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 111 | 112 | 113 | 105 | 113 | 111 | 109 | 111 | 108 | 111 | PASS |
| | | | | | | | | Shear | 124 | | 128 | | 126 | | 120 | | 125 | | |
| | DS Location and Notes | 90'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-18 | 64 / 65 | 8/10/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 111 | 105 | 110 | 113 | 109 | 111 | 108 | 101 | 108 | 109 | PASS |
| | | | | | | | | Shear | 121 | | 123 | | 124 | | 122 | | 123 | | |
| | DS Location and Notes | 128'N OF SEOS | | | | | | | | | | | | | | | | | |

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DS-19 | 68 / 69 | 8/13/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 101 | 106 | 100 | 103 | 103 | 107 | 104 | 105 | 103 | 106 | PASS |
| | | | | | | | | Shear | 122 | | 125 | | 121 | | 124 | | 126 | | |
| | DS Location and Notes | 100'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-20 | 72 / 73 | 8/14/15 | MODESTO L. | 2025 | 450 | 860 | | Peel | 96 | 102 | 98 | 102 | 100 | 106 | 96 | 98 | 99 | 102 | PASS |
| | | | | | | | | Shear | 115 | | 115 | | 114 | | 118 | | 115 | | |
| | DS Location and Notes | 10'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-21 | 74 / 75 | 8/14/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 103 | 103 | 103 | 107 | 106 | 105 | 104 | 105 | 103 | 105 | PASS |
| | | | | | | | | Shear | 119 | | 120 | | 123 | | 116 | | 118 | | |
| | DS Location and Notes | 75'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-8 | RP-284 / 71 | 9/9/15 | PEDRO S. | EXT 512 | | 550 | 550 | Peel | 106 | | 100 | | 100 | | 103 | | 101 | | PASS |
| | | | | | | | | Shear | 119 | | 116 | | 117 | | 120 | | 119 | | |
| | DS Location and Notes | ON RP-284/71 | | | | | | | | | | | | | | | | | |
| DS-22 | 79 / 80 | 9/9/15 | PEDRO S. | 2025 | 400 | 860 | | Peel | 119 | 115 | 116 | 118 | 114 | 113 | 113 | 113 | 116 | 118 | PASS |
| | | | | | | | | Shear | 117 | | 117 | | 116 | | 113 | | 112 | | |
| | DS Location and Notes | 78'E OF WEOS | | | | | | | | | | | | | | | | | |
| DS-23 | 88 / 89 | 9/15/15 | PEDRO S. | 2025 | 400 | 860 | | Peel | 97 | 95 | 101 | 102 | 97 | 94 | 96 | 95 | 97 | 96 | PASS |
| | | | | | | | | Shear | 113 | | 116 | | 117 | | 111 | | 116 | | |
| | DS Location and Notes | 116'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-9 | RP-316 / 88 | 9/16/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 100 | | 100 | | 99 | | 103 | | 105 | | PASS |
| | | | | | | | | Shear | 119 | | 119 | | 118 | | 116 | | 120 | | |
| | DS Location and Notes | RP-316/88 | | | | | | | | | | | | | | | | | |
| DS-24 | 91 / 92 | 9/16/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 109 | 98 | 110 | 96 | 108 | 100 | 105 | 97 | 98 | 108 | PASS |
| | | | | | | | | Shear | 111 | | 116 | | 112 | | 118 | | 113 | | |
| | DS Location and Notes | 45'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-25 | 94 / 95 | 9/17/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 114 | 109 | 114 | 109 | 114 | 110 | 116 | 104 | 113 | 107 | PASS |
| | | | | | | | | Shear | 126 | | 127 | | 122 | | 120 | | 126 | | |
| | DS Location and Notes | 100'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-26 | 96 / 97 | 9/17/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 98 | 85 | 100 | 98 | 100 | 100 | 98 | 92 | 96 | 98 | PASS |
| | | | | | | | | Shear | 104 | | 106 | | 109 | | 109 | | 110 | | |
| | DS Location and Notes | 33'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-10 | RP-376 / 96 | 9/21/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 95 | | 94 | | 99 | | 98 | | 98 | | PASS |
| | | | | | | | | Shear | 101 | | 101 | | 103 | | 105 | | 101 | | |
| | DS Location and Notes | RP-376/96 | | | | | | | | | | | | | | | | | |
| DS-27 | 110 / 111 | 9/23/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 112 | 116 | 114 | 116 | 105 | 120 | 109 | 114 | 110 | 115 | PASS |
| | | | | | | | | Shear | 127 | | 128 | | 127 | | 125 | | 125 | | |
| | DS Location and Notes | 120'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-11 | RP-421 / 114 | 9/24/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 117 | | 116 | | 108 | | 108 | | 112 | | PASS |
| | | | | | | | | Shear | 119 | | 112 | | 111 | | 116 | | 114 | | |
| | DS Location and Notes | RP-421/114 | | | | | | | | | | | | | | | | | |
| DS-28 | 123 / 125 | 9/29/15 | PEDRO S. | 2025 | 400 | 860 | | Peel | 115 | 127 | 112 | 123 | 119 | 117 | 109 | 113 | 106 | 126 | PASS |
| | | | | | | | | Shear | 141 | | 138 | | 133 | | 136 | | 137 | | |
| | DS Location and Notes | 90'N OF SEOS | | | | | | | | | | | | | | | | | |

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DSX-12 | RP-459 / 123 | 10/7/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 106 | | 110 | | 111 | | 105 | | 104 | | PASS |
| | | | | | | | | Shear | 128 | | 129 | | 128 | | 131 | | 127 | | |
| | DS Location and Notes | N.SIDE OF RP-459 | | | | | | | | | | | | | | | | | |
| DS-29 | 128 / 132 | 10/8/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 112 | 116 | 106 | 123 | 116 | 109 | 125 | 113 | 125 | 112 | PASS |
| | | | | | | | | Shear | 133 | | 139 | | 130 | | 136 | | 134 | | |
| | DS Location and Notes | 25'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-13 | RP-477 / 125 | 10/9/15 | PEDRO S. | EXT 512 | | 550 | 550 | Peel | 121 | | 118 | | 120 | | 119 | | 121 | | FAIL |
| | | | | | | | | Shear | 136 | | 133 | | 137 | | 136 | | 131 | | |
| | DS Location and Notes | N.SIDE OF RP-477 (DSX-13 FAIL AT LAB , TRACK TO DSX-15 ) | | | | | | | | | | | | | | | | | |
| DSX-14 | RP-480 / 132 | 10/9/15 | PEDRO S. | EXT 512 | | 550 | 550 | Peel | 118 | | 117 | | 125 | | 119 | | 120 | | PASS |
| | | | | | | | | Shear | 138 | | 139 | | 138 | | 136 | | 134 | | |
| | DS Location and Notes | E.SIDE OF RP-480 | | | | | | | | | | | | | | | | | |
| DSX-15 | RP-487 / 125 | 10/12/15 | EDFY N. | EXT 512 | | 550 | 550 | Peel | 122 | | 113 | | 114 | | 117 | | 108 | | PASS |
| | | | | | | | | Shear | 133 | | 117 | | 131 | | 128 | | 126 | | |
| | DS Location and Notes | N.SIDE OF RP-487/125 | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |

# Appendix N
# Laboratory Destruct Test Results

# *Entact / ESI – Fusion Weld Destruct Sample Laboratory Data*

# Honeywell SA-6 Capping

## *Comparison of ESI / Langan (QA) Destruct Samples - Fusion Weld*

| *Sample ID* | *Weld Type* | *Submitted By:* | *Test* | *Peel Strength (ppi)* | | | | | Avg. Strength (ppi) | *Meets Spec Requirement* |
|---|---|---|---|---|---|---|---|---|---|---|
| DS-1 | Fusion | Entact | Side A Peel | 126.4 | 122.5 | 125.3 | 125.4 | 124.7 | **124.9** | **Yes** |
| | | | Side B Peel | 120.8 | 118.5 | 118.9 | 117.8 | 116.5 | **118.5** | **Yes** |
| | | | Shear | 126.7 | 137.9 | 136.1 | 142.3 | 138.8 | **136.4** | **Yes** |
| DS-2 | Fusion | Langan | Side A Peel | 138 | 142 | 138 | 140 | 134 | **138** | **Yes** |
| | | Entact | Side A Peel | 126.3 | 125.8 | 126.5 | 128.8 | 129.3 | **127.3** | **Yes** |
| | | Langan | Side B Peel | 139 | 143 | 140 | 138 | 134 | **139** | **Yes** |
| | | Entact | Side B Peel | 121.8 | 123.1 | 124.6 | 123.1 | 124.3 | **123.4** | **Yes** |
| | | Langan | Shear | 139 | 146 | 143 | 147 | 145 | **144** | **Yes** |
| | | Entact | Shear | 127.9 | 133.2 | 138.3 | 135 | 132.4 | **133.4** | **Yes** |
| DS-3 | Fusion | Entact | Side A Peel | 127.5 | 120.8 | 122.1 | 123.2 | 123.7 | **123.5** | **Yes** |
| | | | Side B Peel | 124.2 | 118.4 | 121.2 | 119.7 | 120.1 | **120.7** | **Yes** |
| | | | Shear | 131.3 | 127.3 | 127.8 | 128.8 | 127.5 | **128.5** | **Yes** |
| DS-4 | Fusion | Entact | Side A Peel | 108.7 | 105 | 107.7 | 109.8 | 104.7 | **107.2** | **Yes** |
| | | | Side B Peel | 110.4 | 109 | 107.1 | 107.9 | 108.3 | **108.5** | **Yes** |
| | | | Shear | 115.3 | 115.1 | 117.8 | 115.6 | 115.4 | **115.8** | **Yes** |
| DS-5 | Fusion | Entact | Side A Peel | 112 | 110.3 | 114.6 | 111.8 | 112.2 | **112.2** | **Yes** |
| | | | Side B Peel | 107.3 | 101 | 105.6 | 105.2 | 104.2 | **104.7** | **Yes** |
| | | | Shear | 117.7 | 117.5 | 121.3 | 120.2 | 118.2 | **119.0** | **Yes** |
| DS-6 | Fusion | Entact | Side A Peel | 115.2 | 113.8 | 116.8 | 99.3 | 119.9 | **113.0** | **Yes** |
| | | | Side B Peel | 120.3 | 109.4 | 115.4 | 102.9 | 110.5 | **111.7** | **Yes** |
| | | | Shear | 125.1 | 123.5 | 124.6 | 125.6 | 122.2 | **124.2** | **Yes** |
| DS-7 | Fusion | Entact | Side A Peel | 117 | 115.9 | 119.8 | 115.7 | 116.1 | **116.9** | **Yes** |
| | | | Side B Peel | 113.1 | 113.6 | 115.8 | 110.9 | 111.7 | **113.0** | **Yes** |
| | | | Shear | 125.6 | 124.3 | 124 | 128.7 | 125.7 | **125.7** | **Yes** |
| DS-8 | Fusion | Entact | Side A Peel | 121.5 | 124.7 | 123.3 | 126.9 | 124.2 | **124.1** | **Yes** |
| | | | Side B Peel | 115.6 | 116.6 | 115.5 | 119.4 | 116.7 | **116.8** | **Yes** |
| | | | Shear | 135.4 | 127.5 | 130.7 | 127.8 | 126.1 | **129.5** | **Yes** |
| DS-9 | Fusion | Entact | Side A Peel | 122.8 | 123.5 | 124.5 | 123.4 | 128.6 | **124.6** | **Yes** |
| | | | Side B Peel | 120.1 | 120.1 | 119.9 | 121 | 124.1 | **121.0** | **Yes** |
| | | | Shear | 136.1 | 131.2 | 131.9 | 134.5 | 130.7 | **132.9** | **Yes** |
| DS-10 | Fusion | Langan | Side A Peel | 121 | 121 | 124 | 123 | 122 | **122.2** | **Yes** |
| | | Entact | Side A Peel | 119.3 | 119.8 | 118.3 | 125.2 | 119.4 | **120.4** | **Yes** |
| | | Langan | Side B Peel | 121 | 118 | 120 | 117 | 125 | **120.2** | **Yes** |
| | | Entact | Side B Peel | 116.7 | 118.5 | 109.6 | 113.5 | 113.9 | **114.4** | **Yes** |
| | | Langan | Shear | 134 | 133 | 134 | 129 | 130 | **132.0** | **Yes** |
| | | Entact | Shear | 135.9 | 132.1 | 132.1 | 134.7 | 134.2 | **133.8** | **Yes** |
| DS-11 | Fusion | Entact | Side A Peel | 127.4 | 124.6 | 126.7 | 125.4 | 123.5 | **125.5** | **Yes** |
| | | | Side B Peel | 126.5 | 120.8 | 128.3 | 123.9 | 123.5 | **124.6** | **Yes** |
| | | | Shear | 134.6 | 135.4 | 138.6 | 136.1 | 136.6 | **136.3** | **Yes** |
| DS-12 | Fusion | Entact | Side A Peel | 129.7 | 131.2 | 135.1 | 130.6 | 134.7 | **132.3** | **Yes** |
| | | | Side B Peel | 118.9 | 116.7 | 128.9 | 115.9 | 120.3 | **120.1** | **Yes** |
| | | | Shear | 146.2 | 141.4 | 143.3 | 142.2 | 141.7 | **143.0** | **Yes** |
| DS-13 | Fusion | Entact | Side A Peel | 121.3 | 114.1 | 110.8 | 123.4 | 118.8 | **117.7** | **Yes** |
| | | | Side B Peel | 113.9 | 121.3 | 116.3 | 120 | 119.6 | **118.2** | **Yes** |
| | | | Shear | 137.1 | 138.9 | 140.2 | 130.3 | 142.7 | **137.8** | **Yes** |
| DS-14 | Fusion | Entact | Side A Peel | 121.8 | 120.9 | 120.2 | 121.7 | 127.6 | **122.4** | **Yes** |
| | | | Side B Peel | 123.1 | 122.6 | 121.6 | 126.7 | 132.6 | **125.3** | **Yes** |
| | | | Shear | 141.2 | 143.6 | 142 | 139.6 | 140.9 | **141.5** | **Yes** |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| DS-15 | Fusion | Entact | Side A Peel | 106.6 | 109.7 | 106.8 | 108.7 | 107.2 | **107.8** | **Yes** |
| | | | Side B Peel | 113.7 | 108.9 | 110.1 | 109.7 | 107.2 | **109.9** | **Yes** |
| | | | Shear | 132.5 | 127.1 | 124.3 | 127.2 | 127.3 | **127.7** | **Yes** |
| DS-16 | Fusion | Entact | Side A Peel | 111.4 | 114.2 | 118.3 | 113.6 | 108.7 | **113.2** | **Yes** |
| | | | Side B Peel | 114.1 | 113.2 | 119.3 | 114 | 112.7 | **114.7** | **Yes** |
| | | | Shear | 113.6 | 133.4 | 136.1 | 132.2 | 135.1 | **130.1** | **Yes** |
| DS-17 | Fusion | Entact | Side A Peel | 121.1 | 121.9 | 122.3 | 122.4 | 120.6 | **121.7** | **Yes** |
| | | | Side B Peel | 121.9 | 116 | 118.1 | 123.6 | 121 | **120.1** | **Yes** |
| | | | Shear | 136.1 | 136.1 | 135.6 | 138.7 | 136.8 | **136.7** | **Yes** |
| DS-18 | Fusion | Entact | Side A Peel | 112.6 | 120.7 | 118.2 | 114.7 | 116.6 | **116.6** | **Yes** |
| | | | Side B Peel | 110.3 | 109.4 | 113.4 | 112 | 114.1 | **111.8** | **Yes** |
| | | | Shear | 138.8 | 135.9 | 133.9 | 136.1 | 136.7 | **136.3** | **Yes** |
| DS-19 | Fusion | Entact | Side A Peel | 114.6 | 118 | 113.7 | 112.8 | 112.9 | **114.4** | **Yes** |
| | | | Side B Peel | 118.1 | 121.2 | 117.2 | 118.6 | 119.1 | **118.8** | **Yes** |
| | | | Shear | 138.1 | 136.2 | 133.6 | 133.1 | 133.9 | **135.0** | **Yes** |
| DS-20 | Fusion | Entact | Side A Peel | 119.6 | 118.8 | 114.7 | 117.4 | 116.3 | **117.4** | **Yes** |
| | | | Side B Peel | 112.7 | 117.6 | 116.1 | 114.6 | 113.8 | **115.0** | **Yes** |
| | | | Shear | 140.9 | 135.7 | 140.4 | 142.7 | 141.4 | **140.2** | **Yes** |
| DS-21 | Fusion | Langan | Side A Peel | 113 | 115 | 114 | 116 | 115 | **114.6** | **Yes** |
| | | Entact | Side A Peel | 117.8 | 118.5 | 113.2 | 112.4 | 112.1 | **114.8** | **Yes** |
| | | Langan | Side B Peel | 120 | 119 | 122 | 130 | 128 | **123.8** | **Yes** |
| | | Entact | Side B Peel | 112.3 | 122.1 | 120 | 109.4 | 112 | **115.2** | **Yes** |
| | | Langan | Shear | 142 | 147 | 145 | 142 | 144 | **144.0** | **Yes** |
| | | Entact | Shear | 145.9 | 144.4 | 147.2 | 143.7 | 142.9 | **144.8** | **Yes** |
| DS-22 | Fusion | Entact | Side A Peel | 120 | 125.9 | 118.4 | 117.9 | 118.2 | **120.1** | **Yes** |
| | | | Side B Peel | 125.9 | 123.5 | 118.4 | 120.4 | 120.1 | **121.7** | **Yes** |
| | | | Shear | 137.9 | 131.6 | 134.7 | 132.4 | 133.5 | **134.0** | **Yes** |
| DS-23 | Fusion | Entact | Side A Peel | 108.9 | 113.2 | 109.4 | 109.7 | 113.9 | **111.0** | **Yes** |
| | | | Side B Peel | 118.3 | 114.9 | 109.3 | 111.3 | 122 | **115.2** | **Yes** |
| | | | Shear | 128.5 | 129.2 | 129.7 | 130.9 | 129.5 | **129.6** | **Yes** |
| DS-24 | Fusion | Entact | Side A Peel | 120 | 118.2 | 118.6 | 120.2 | 119.2 | **119.2** | **Yes** |
| | | | Side B Peel | 109.8 | 112.1 | 112.9 | 115.4 | 114.4 | **112.9** | **Yes** |
| | | | Shear | 128.9 | 132.4 | 135.2 | 135 | 124.9 | **131.3** | **Yes** |
| DS-25 | Fusion | Entact | Side A Peel | 117.6 | 110.4 | 117.8 | 116.8 | 118.4 | **116.2** | **Yes** |
| | | | Side B Peel | 119.6 | 125 | 120.3 | 125.5 | 126.9 | **123.5** | **Yes** |
| | | | Shear | 129.9 | 131.1 | 135.5 | 135.3 | 134.2 | **133.2** | **Yes** |
| DS-26 | Fusion | Entact | Side A Peel | 115.7 | 115.5 | 112.9 | 117.9 | 117.6 | **115.9** | **Yes** |
| | | | Side B Peel | 98.1 | 99.5 | 104.4 | 101.9 | 118.5 | **104.5** | **Yes** |
| | | | Shear | 130.9 | 126.7 | 133 | 126.4 | 130.8 | **129.6** | **Yes** |
| DS-27 | Fusion | Entact | Side A Peel | 111.1 | 105.2 | 109.7 | 109.1 | 108.5 | **108.7** | **Yes** |
| | | | Side B Peel | 121.6 | 114.8 | 120.1 | 125 | 121.6 | **120.6** | **Yes** |
| | | | Shear | 126 | 125.7 | 127.8 | 128.4 | 132.1 | **128.0** | **Yes** |
| DS-28 | Fusion | Entact | Side A Peel | 111.1 | 107.3 | 111.3 | 108.5 | 108.7 | **109.4** | **Yes** |
| | | | Side B Peel | 112.3 | 107.8 | 109.9 | 107.8 | 123.9 | **112.3** | **Yes** |
| | | | Shear | 132.8 | 129 | 129.7 | 128.6 | 134.3 | **130.9** | **Yes** |
| DS-29 | Fusion | Langan | Side A Peel | 111 | 112 | 110 | 112 | 114 | **111.8** | **Yes** |
| | | Entact | Side A Peel | 111.4 | 112.5 | 115.4 | 116.7 | 119.3 | **115.1** | **Yes** |
| | | Langan | Side B Peel | 113 | 124 | 111 | 121 | 115 | **116.8** | **Yes** |
| | | Entact | Side B Peel | 121.1 | 118.5 | 115.5 | 115.6 | 120.3 | **118.2** | **Yes** |
| | | Langan | Shear | 138 | 140 | 140 | 138 | 138 | **138.8** | **Yes** |
| | | Entact | Shear | 129.5 | 131.7 | 131.7 | 130.7 | 132.1 | **131.1** | **Yes** |

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-09
LAB ID NO.: L15084-09-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-1**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 126.4 | SE1 | <10 |
| 2 | 122.5 | SE1 | <10 |
| 3 | 125.3 | SE1 | <10 |
| 4 | 125.4 | SE1 | <10 |
| 5 | 124.7 | SE1 | <10 |
| **AVERAGE** | **124.9** | | |
| STD. DEV. | 1.30 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 120.8 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 118.9 | SE1 | <10 |
| 4 | 117.8 | SE1 | <10 |
| 5 | 116.5 | SE1 | <10 |
| **AVERAGE** | **118.5** | | |
| STD. DEV. | 1.41 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.7 | SE1 |
| 2 | 137.9 | SE1 |
| 3 | 136.1 | SE1 |
| 4 | 142.3 | SE1 |
| 5 | 138.8 | SE1 |
| **AVERAGE** | **136.4** | |
| STD. DEV. | 5.23 | |

CHECKED BY: JVC DATE: 7/22/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-09
LAB ID NO.: L15084-09-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-2**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 126.3 | SE1 | <10 |
| 2 | 125.8 | SE1 | <10 |
| 3 | 126.5 | SE1 | <10 |
| 4 | 128.8 | SE1 | <10 |
| 5 | 129.3 | SE1 | <10 |
| **AVERAGE** | **127.3** | | |
| STD. DEV. | 1.42 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.8 | SE1 | <10 |
| 2 | 123.1 | SE1 | <10 |
| 3 | 124.6 | SE1 | <10 |
| 4 | 123.1 | SE1 | <10 |
| 5 | 124.3 | SE1 | <10 |
| **AVERAGE** | **123.4** | | |
| STD. DEV. | 1.00 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 127.9 | SE1 |
| 2 | 133.2 | SE1 |
| 3 | 138.3 | SE1 |
| 4 | 135.0 | SE1 |
| 5 | 132.4 | SE1 |
| **AVERAGE** | **133.4** | |
| STD. DEV. | 3.40 | |

CHECKED BY: NC DATE: 7/22/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-11
LAB ID NO.: L15084-11-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-3**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 127.5 | SE1 | <10 |
| 2 | 120.8 | SE1 | <10 |
| 3 | 122.1 | SE1 | <10 |
| 4 | 123.2 | SE1 | <10 |
| 5 | 123.7 | SE1 | <10 |
| **AVERAGE** | **123.5** | | |
| STD. DEV. | 2.25 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 124.2 | SE1 | <10 |
| 2 | 118.4 | SE1 | <10 |
| 3 | 121.2 | SE1 | <10 |
| 4 | 119.7 | SE1 | <10 |
| 5 | 120.1 | SE1 | <10 |
| **AVERAGE** | **120.7** | | |
| STD. DEV. | 1.96 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.3 | SE1 |
| 2 | 127.3 | SE1 |
| 3 | 127.8 | SE1 |
| 4 | 128.8 | SE1 |
| 5 | 127.5 | SE1 |
| **AVERAGE** | **128.5** | |
| STD. DEV. | 1.47 | |

CHECKED BY: JAM DATE: 7/23/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-12
LAB ID NO.: L15084-12-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-4**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 108.7 | SE1 | <10 |
| 2 | 105.0 | SE1 | <10 |
| 3 | 107.7 | SE1 | <10 |
| 4 | 109.8 | SE1 | <10 |
| 5 | 104.7 | SE1 | <10 |
| **AVERAGE** | **107.2** | | |
| STD. DEV. | 2.02 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 110.4 | SE1 | <10 |
| 2 | 109.0 | SE1 | <10 |
| 3 | 107.1 | SE1 | <10 |
| 4 | 107.9 | SE1 | <10 |
| 5 | 108.3 | SE1 | <10 |
| **AVERAGE** | **108.5** | | |
| STD. DEV. | 1.11 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 115.3 | SE1 |
| 2 | 115.1 | SE1 |
| 3 | 117.8 | SE1 |
| 4 | 115.6 | SE1 |
| 5 | 115.4 | SE1 |
| **AVERAGE** | **115.8** | |
| STD. DEV. | 0.99 | |

CHECKED BY: JAM DATE: 7/27/15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-12 L  L15084-12-02  7/27/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-12
LAB ID NO.: L15084-12-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-5**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 112.0 | SE1 | <10 |
| 2 | 110.3 | SE1 | <10 |
| 3 | 114.6 | SE1 | <10 |
| 4 | 111.8 | SE1 | <10 |
| 5 | 112.2 | SE1 | <10 |
| **AVERAGE** | **112.2** | | |
| STD. DEV. | 1.38 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 107.3 | SE1 | <10 |
| 2 | 101.0 | SE1 | <10 |
| 3 | 105.6 | SE1 | <10 |
| 4 | 105.2 | SE1 | <10 |
| 5 | 104.2 | SE1 | <10 |
| **AVERAGE** | **104.7** | | |
| STD. DEV. | 2.09 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 117.7 | SE1 |
| 2 | 117.5 | SE1 |
| 3 | 121.3 | SE1 |
| 4 | 120.2 | SE1 |
| 5 | 118.2 | SE1 |
| **AVERAGE** | **119.0** | |
| STD. DEV. | 1.50 | |

CHECKED BY: JK DATE: 7/27/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-13
LAB ID NO.: L15084-13-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-6**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 115.2 | SE1 | <10 |
| 2 | 113.8 | SE1 | <10 |
| 3 | 116.8 | SE1 | <10 |
| 4 | 99.3 | SE1 | <10 |
| 5 | 119.9 | SE1 | <10 |
| **AVERAGE** | **113.0** | | |
| STD. DEV. | 7.14 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 120.3 | SE1 | <10 |
| 2 | 109.4 | SE1 | <10 |
| 3 | 115.4 | SE1 | <10 |
| 4 | 102.9 | SE1 | <10 |
| 5 | 110.5 | SE1 | <10 |
| **AVERAGE** | **111.7** | | |
| STD. DEV. | 5.86 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 125.1 | SE1 |
| 2 | 123.5 | SE1 |
| 3 | 124.6 | SE1 |
| 4 | 125.6 | SE1 |
| 5 | 122.2 | SE1 |
| **AVERAGE** | **124.2** | |
| STD. DEV. | 1.22 | |

CHECKED BY: NC DATE: 7/28/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-13
LAB ID NO.: L15084-13-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-7**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 117.0 | SE1 | <10 |
| 2 | 115.9 | SE1 | <10 |
| 3 | 119.8 | SE1 | <10 |
| 4 | 115.7 | SE1 | <10 |
| 5 | 116.1 | SE1 | <10 |
| **AVERAGE** | **116.9** | | |
| STD. DEV. | 1.52 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 113.1 | SE1 | <10 |
| 2 | 113.6 | SE1 | <10 |
| 3 | 115.8 | SE1 | <10 |
| 4 | 110.9 | SE1 | <10 |
| 5 | 111.7 | SE1 | <10 |
| **AVERAGE** | **113.0** | | |
| STD. DEV. | 1.69 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 125.6 | SE1 |
| 2 | 124.3 | SE1 |
| 3 | 124.0 | SE1 |
| 4 | 128.7 | SE1 |
| 5 | 125.7 | SE1 |
| **AVERAGE** | **125.7** | |
| STD. DEV. | 1.66 | |

CHECKED BY: NC DATE: 7/28/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-15
LAB ID NO.: L15084-15-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-8**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.5 | SE1 | <10 |
| 2 | 124.7 | SE1 | <10 |
| 3 | 123.3 | SE1 | <10 |
| 4 | 126.9 | SE1 | <10 |
| 5 | 124.2 | SE1 | <10 |
| **AVERAGE** | **124.1** | | |
| STD. DEV. | 1.77 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 115.6 | SE1 | <10 |
| 2 | 116.6 | SE1 | <10 |
| 3 | 115.5 | SE1 | <10 |
| 4 | 119.4 | SE1 | <10 |
| 5 | 116.7 | SE1 | <10 |
| **AVERAGE** | **116.8** | | |
| STD. DEV. | 1.41 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 135.4 | SE1 |
| 2 | 127.5 | SE1 |
| 3 | 130.7 | SE1 |
| 4 | 127.8 | SE1 |
| 5 | 126.1 | SE1 |
| **AVERAGE** | **129.5** | |
| STD. DEV. | 3.31 | |

CHECKED BY: JO DATE: 7.30-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-15
LAB ID NO.: L15084-15-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-9**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 122.8 | SE1 | <10 |
| 2 | 123.5 | SE1 | <10 |
| 3 | 124.5 | SE1 | <10 |
| 4 | 123.4 | SE1 | <10 |
| 5 | 128.6 | SE1 | <10 |
| **AVERAGE** | **124.6** | | |
| STD. DEV. | 2.09 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 120.1 | SE1 | <10 |
| 2 | 120.1 | SE1 | <10 |
| 3 | 119.9 | SE1 | <10 |
| 4 | 121.0 | SE1 | <10 |
| 5 | 124.1 | SE1 | <10 |
| **AVERAGE** | **121.0** | | |
| STD. DEV. | 1.58 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 136.1 | SE1 |
| 2 | 131.2 | SE1 |
| 3 | 131.9 | SE1 |
| 4 | 134.5 | SE1 |
| 5 | 130.7 | SE1 |
| **AVERAGE** | **132.9** | |
| STD. DEV. | 2.07 | |

CHECKED BY: JO DATE: 7-30-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-16
LAB ID NO.: L15084-16-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-10**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 119.3 | SE1 | <10 |
| 2 | 119.8 | SE1 | <10 |
| 3 | 118.3 | SE1 | <10 |
| 4 | 125.2 | SE1 | <10 |
| 5 | 119.4 | SE1 | <10 |
| **AVERAGE** | **120.4** | | |
| STD. DEV. | 2.45 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 116.7 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 109.6 | SE1 | <10 |
| 4 | 113.5 | SE1 | <10 |
| 5 | 113.9 | SE1 | <10 |
| **AVERAGE** | **114.4** | | |
| STD. DEV. | 3.04 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 135.9 | SE1 |
| 2 | 132.1 | SE1 |
| 3 | 132.1 | SE1 |
| 4 | 134.7 | SE1 |
| 5 | 134.2 | SE1 |
| **AVERAGE** | **133.8** | |
| STD. DEV. | 1.49 | |

CHECKED BY: JO DATE: 7-31-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-18
LAB ID NO.: L15084-18-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-11**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 127.4 | SE1 | <10 |
| 2 | 124.6 | SE1 | <10 |
| 3 | 126.7 | SE1 | <10 |
| 4 | 125.4 | SE1 | <10 |
| 5 | 123.5 | SE1 | <10 |
| **AVERAGE** | **125.5** | | |
| STD. DEV. | 1.40 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 126.5 | SE1 | <10 |
| 2 | 120.8 | SE1 | <10 |
| 3 | 128.3 | SE1 | <10 |
| 4 | 123.9 | SE1 | <10 |
| 5 | 123.5 | SE1 | <10 |
| **AVERAGE** | **124.6** | | |
| STD. DEV. | 2.59 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 134.6 | SE1 |
| 2 | 135.4 | SE1 |
| 3 | 138.6 | SE1 |
| 4 | 136.1 | SE1 |
| 5 | 136.6 | SE1 |
| **AVERAGE** | **136.3** | |
| STD. DEV. | 1.35 | |

CHECKED BY: JO DATE: 8-5-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-18
LAB ID NO.: L15084-18-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-12**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 129.7 | SE1 | <10 |
| 2 | 131.2 | SE1 | <10 |
| 3 | 135.1 | SE1 | <10 |
| 4 | 130.6 | SE1 | <10 |
| 5 | 134.7 | SE1 | <10 |
| **AVERAGE** | **132.3** | | |
| STD. DEV. | 2.21 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 118.9 | SE1 | <10 |
| 2 | 116.7 | SE1 | <10 |
| 3 | 128.9 | SE1 | <10 |
| 4 | 115.9 | SE1 | <10 |
| 5 | 120.3 | SE1 | <10 |
| **AVERAGE** | **120.1** | | |
| STD. DEV. | 4.65 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 146.2 | SE1 |
| 2 | 141.4 | SE1 |
| 3 | 143.3 | SE1 |
| 4 | 142.2 | SE1 |
| 5 | 141.7 | SE1 |
| **AVERAGE** | **143.0** | |
| STD. DEV. | 1.74 | |

CHECKED BY: J.O DATE: 8-5-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-18 L L15084-18-02 8/5/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-20
LAB ID NO.: L15084-20-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-13**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.3 | SE1 | <10 |
| 2 | 114.1 | SE1 | <10 |
| 3 | 110.8 | SE1 | <10 |
| 4 | 123.4 | SE1 | <10 |
| 5 | 118.8 | SE1 | <10 |
| **AVERAGE** | **117.7** | | |
| STD. DEV. | 4.63 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 113.9 | SE1 | <10 |
| 2 | 121.3 | SE1 | <10 |
| 3 | 116.3 | SE1 | <10 |
| 4 | 120.0 | SE1 | <10 |
| 5 | 119.6 | SE1 | <10 |
| **AVERAGE** | **118.2** | | |
| STD. DEV. | 2.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 137.1 | SE1 |
| 2 | 138.9 | SE1 |
| 3 | 140.2 | SE1 |
| 4 | 130.3 | SE1 |
| 5 | 142.7 | SE1 |
| **AVERAGE** | **137.8** | |
| STD. DEV. | 4.19 | |

CHECKED BY: JO DATE: 8-10-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-20
LAB ID NO.: L15084-20-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-14**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.8 | SE1 | <10 |
| 2 | 120.9 | SE1 | <10 |
| 3 | 120.2 | SE1 | <10 |
| 4 | 121.7 | SE1 | <10 |
| 5 | 127.6 | SE1 | <10 |
| **AVERAGE** | **122.4** | | |
| STD. DEV. | 2.64 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 123.1 | SE1 | <10 |
| 2 | 122.6 | SE1 | <10 |
| 3 | 121.6 | SE1 | <10 |
| 4 | 126.7 | SE1 | <10 |
| 5 | 132.6 | SE1 | <10 |
| **AVERAGE** | **125.3** | | |
| STD. DEV. | 4.03 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 141.2 | SE1 |
| 2 | 143.6 | SE1 |
| 3 | 142.0 | SE1 |
| 4 | 139.6 | SE1 |
| 5 | 140.9 | SE1 |
| **AVERAGE** | **141.5** | |
| STD. DEV. | 1.32 | |

CHECKED BY: JO DATE: 8-10-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-21
LAB ID NO.: L15084-21-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-15**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 106.6 | SE1 | <10 |
| 2 | 109.7 | SE1 | <10 |
| 3 | 106.8 | SE1 | <10 |
| 4 | 108.7 | SE1 | <10 |
| 5 | 107.2 | SE1 | <10 |
| **AVERAGE** | **107.8** | | |
| STD. DEV. | 1.20 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 113.7 | SE1 | <10 |
| 2 | 108.9 | SE1 | <10 |
| 3 | 110.1 | SE1 | <10 |
| 4 | 109.7 | SE1 | <10 |
| 5 | 107.2 | SE1 | <10 |
| **AVERAGE** | **109.9** | | |
| STD. DEV. | 2.14 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.5 | SE1 |
| 2 | 127.1 | SE1 |
| 3 | 124.3 | SE1 |
| 4 | 127.2 | SE1 |
| 5 | 127.3 | SE1 |
| **AVERAGE** | **127.7** | |
| STD. DEV. | 2.66 | |

CHECKED BY: JO DATE: 8-11-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-21
LAB ID NO.: L15084-21-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-16**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.4 | SE1 | <10 |
| 2 | 114.2 | SE1 | <10 |
| 3 | 118.3 | SE1 | <10 |
| 4 | 113.6 | SE1 | <10 |
| 5 | 108.7 | SE1 | <10 |
| **AVERAGE** | **113.2** | | |
| STD. DEV. | 3.18 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 114.1 | SE1 | <10 |
| 2 | 113.2 | SE1 | <10 |
| 3 | 119.3 | SE1 | <10 |
| 4 | 114.0 | SE1 | <10 |
| 5 | 112.7 | SE1 | <10 |
| **AVERAGE** | **114.7** | | |
| STD. DEV. | 2.38 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 113.6 | SE1 |
| 2 | 133.4 | SE1 |
| 3 | 136.1 | SE1 |
| 4 | 132.2 | SE1 |
| 5 | 135.1 | SE1 |
| **AVERAGE** | **130.1** | |
| STD. DEV. | 8.35 | |

CHECKED BY: JO DATE: 8-11-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-22
LAB ID NO.: L15084-22-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-17**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.1 | SE1 | <10 |
| 2 | 121.9 | SE1 | <10 |
| 3 | 122.3 | SE1 | <10 |
| 4 | 122.4 | SE1 | <10 |
| 5 | 120.6 | SE1 | <10 |
| **AVERAGE** | **121.7** | | |
| STD. DEV. | 0.70 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.9 | SE1 | <10 |
| 2 | 116.0 | SE1 | <10 |
| 3 | 118.1 | SE1 | <10 |
| 4 | 123.6 | SE1 | <10 |
| 5 | 121.0 | SE1 | <10 |
| **AVERAGE** | **120.1** | | |
| STD. DEV. | 2.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 136.1 | SE1 |
| 2 | 136.1 | SE1 |
| 3 | 135.6 | SE1 |
| 4 | 138.7 | SE1 |
| 5 | 136.8 | SE1 |
| **AVERAGE** | **136.7** | |
| STD. DEV. | 1.09 | |

CHECKED BY: JO DATE: 8-14-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-22 L L15084-22-01 8/14/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-22
LAB ID NO.: L15084-22-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-18**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 112.6 | SE1 | <10 |
| 2 | 120.7 | SE1 | <10 |
| 3 | 118.2 | SE1 | <10 |
| 4 | 114.7 | SE1 | <10 |
| 5 | 116.6 | SE1 | <10 |
| **AVERAGE** | **116.6** | | |
| STD. DEV. | 2.79 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 110.3 | SE1 | <10 |
| 2 | 109.4 | SE1 | <10 |
| 3 | 113.4 | SE1 | <10 |
| 4 | 112.0 | SE1 | <10 |
| 5 | 114.1 | SE1 | <10 |
| **AVERAGE** | **111.8** | | |
| STD. DEV. | 1.78 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 138.8 | SE1 |
| 2 | 135.9 | SE1 |
| 3 | 133.9 | SE1 |
| 4 | 136.1 | SE1 |
| 5 | 136.7 | SE1 |
| **AVERAGE** | **136.3** | |
| STD. DEV. | 1.57 | |

CHECKED BY: JO DATE: 8-14-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-22
LAB ID NO.: L15084-22-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-19**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 114.6 | SE1 | <10 |
| 2 | 118.0 | SE1 | <10 |
| 3 | 113.7 | SE1 | <10 |
| 4 | 112.8 | SE1 | <10 |
| 5 | 112.9 | SE1 | <10 |
| **AVERAGE** | **114.4** | | |
| STD. DEV. | 1.91 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 118.1 | SE1 | <10 |
| 2 | 121.2 | SE1 | <10 |
| 3 | 117.2 | SE1 | <10 |
| 4 | 118.6 | SE1 | <10 |
| 5 | 119.1 | SE1 | <10 |
| **AVERAGE** | **118.8** | | |
| STD. DEV. | 1.34 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 138.1 | SE1 |
| 2 | 136.2 | SE1 |
| 3 | 133.6 | SE1 |
| 4 | 133.1 | SE1 |
| 5 | 133.9 | SE1 |
| **AVERAGE** | **135.0** | |
| STD. DEV. | 1.89 | |

CHECKED BY: JO DATE: 8-14-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-23
LAB ID NO.: L15084-23-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-20**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 119.6 | SE1 | <10 |
| 2 | 118.8 | SE1 | <10 |
| 3 | 114.7 | SE1 | <10 |
| 4 | 117.4 | SE1 | <10 |
| 5 | 116.3 | SE1 | <10 |
| **AVERAGE** | **117.4** | | |
| STD. DEV. | 1.75 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 112.7 | SE1 | <10 |
| 2 | 117.6 | SE1 | <10 |
| 3 | 116.1 | SE1 | <10 |
| 4 | 114.6 | SE1 | <10 |
| 5 | 113.8 | SE1 | <10 |
| **AVERAGE** | **115.0** | | |
| STD. DEV. | 1.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 140.9 | SE1 |
| 2 | 135.7 | SE1 |
| 3 | 140.4 | SE1 |
| 4 | 142.7 | SE1 |
| 5 | 141.4 | SE1 |
| **AVERAGE** | **140.2** | |
| STD. DEV. | 2.39 | |

CHECKED BY: NC DATE: 8/17/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-23
LAB ID NO.: L15084-23-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-21**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 117.8 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 113.2 | SE1 | <10 |
| 4 | 112.4 | SE1 | <10 |
| 5 | 112.1 | SE1 | <10 |
| **AVERAGE** | **114.8** | | |
| STD. DEV. | 2.77 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 112.3 | SE1 | <10 |
| 2 | 122.1 | SE1 | <10 |
| 3 | 120.0 | SE1 | <10 |
| 4 | 109.4 | SE1 | <10 |
| 5 | 112.0 | SE1 | <10 |
| **AVERAGE** | **115.2** | | |
| STD. DEV. | 4.96 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 145.9 | SE1 |
| 2 | 144.4 | SE1 |
| 3 | 147.2 | SE1 |
| 4 | 143.7 | SE1 |
| 5 | 142.9 | SE1 |
| **AVERAGE** | **144.8** | |
| STD. DEV. | 1.55 | |

CHECKED BY: NC DATE: 8/17/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-25
LAB ID NO.: L15084-25-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-22**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 120.0 | SE1 | <10 |
| 2 | 125.9 | SE1 | <10 |
| 3 | 118.4 | SE1 | <10 |
| 4 | 117.9 | SE1 | <10 |
| 5 | 118.2 | SE1 | <10 |
| **AVERAGE** | **120.1** | | |
| STD. DEV. | 3.00 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 125.9 | SE1 | <10 |
| 2 | 123.5 | SE1 | <10 |
| 3 | 118.4 | SE1 | <10 |
| 4 | 120.4 | SE1 | <10 |
| 5 | 120.1 | SE1 | <10 |
| **AVERAGE** | **121.7** | | |
| STD. DEV. | 2.68 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 137.9 | SE1 |
| 2 | 131.6 | SE1 |
| 3 | 134.7 | SE1 |
| 4 | 132.4 | SE1 |
| 5 | 133.5 | SE1 |
| **AVERAGE** | **134.0** | |
| STD. DEV. | 2.20 | |

CHECKED BY: JO DATE: 9-15-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-26
LAB ID NO.: L15084-26-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-23**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 108.9 | SE1 | <10 |
| 2 | 113.2 | SE1 | <10 |
| 3 | 109.4 | SE1 | <10 |
| 4 | 109.7 | SE1 | <10 |
| 5 | 113.9 | SE1 | <10 |
| **AVERAGE** | **111.0** | | |
| STD. DEV. | 2.09 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 118.3 | SE1 | <10 |
| 2 | 114.9 | SE1 | <10 |
| 3 | 109.3 | SE1 | <10 |
| 4 | 111.3 | SE1 | <10 |
| 5 | 122.0 | SE1 | <10 |
| **AVERAGE** | **115.2** | | |
| STD. DEV. | 4.60 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 128.5 | SE1 |
| 2 | 129.2 | SE1 |
| 3 | 129.7 | SE1 |
| 4 | 130.9 | SE1 |
| 5 | 129.5 | SE1 |
| **AVERAGE** | **129.6** | |
| STD. DEV. | 0.78 | |

CHECKED BY: JAM DATE: 9/16/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-28
LAB ID NO.: L15084-28-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-24**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 120.0 | SE1 | <10 |
| 2 | 118.2 | SE1 | <10 |
| 3 | 118.6 | SE1 | <10 |
| 4 | 120.2 | SE1 | <10 |
| 5 | 119.2 | SE1 | <10 |
| **AVERAGE** | **119.2** | | |
| STD. DEV. | 0.77 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 109.8 | SE1 | <10 |
| 2 | 112.1 | SE1 | <10 |
| 3 | 112.9 | SE1 | <10 |
| 4 | 115.4 | SE1 | <10 |
| 5 | 114.4 | SE1 | <10 |
| **AVERAGE** | **112.9** | | |
| STD. DEV. | 1.94 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 128.9 | SE1 |
| 2 | 132.4 | SE1 |
| 3 | 135.2 | SE1 |
| 4 | 135.0 | SE1 |
| 5 | 124.9 | SE1 |
| **AVERAGE** | **131.3** | |
| STD. DEV. | 3.92 | |

CHECKED BY: J.O DATE: 9-18-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-29
LAB ID NO.: L15084-29-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-25**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 117.6 | SE1 | <10 |
| 2 | 110.4 | SE1 | <10 |
| 3 | 117.8 | SE1 | <10 |
| 4 | 116.8 | SE1 | <10 |
| 5 | 118.4 | SE1 | <10 |
| **AVERAGE** | **116.2** | | |
| STD. DEV. | 2.94 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 119.6 | SE1 | <10 |
| 2 | 125.0 | SE1 | <10 |
| 3 | 120.3 | SE1 | <10 |
| 4 | 125.5 | SE1 | <10 |
| 5 | 126.9 | SE1 | <10 |
| **AVERAGE** | **123.5** | | |
| STD. DEV. | 2.94 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 129.9 | SE1 |
| 2 | 131.1 | SE1 |
| 3 | 135.5 | SE1 |
| 4 | 135.3 | SE1 |
| 5 | 134.2 | SE1 |
| **AVERAGE** | **133.2** | |
| STD. DEV. | 2.28 | |

CHECKED BY: JAC DATE: 9/21/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-29
LAB ID NO.: L15084-29-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-26**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 115.7 | SE1 | <10 |
| 2 | 115.5 | SE1 | <10 |
| 3 | 112.9 | SE1 | <10 |
| 4 | 117.9 | SE1 | <10 |
| 5 | 117.6 | SE1 | <10 |
| **AVERAGE** | **115.9** | | |
| STD. DEV. | 1.79 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 98.1 | SE1 | <10 |
| 2 | 99.5 | SE1 | <10 |
| 3 | 104.4 | SE1 | <10 |
| 4 | 101.9 | SE1 | <10 |
| 5 | 118.5 | SE1 | <10 |
| **AVERAGE** | **104.5** | | |
| STD. DEV. | 7.33 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 130.9 | SE1 |
| 2 | 126.7 | SE1 |
| 3 | 133.0 | SE1 |
| 4 | 126.4 | SE1 |
| 5 | 130.8 | SE1 |
| **AVERAGE** | **129.6** | |
| STD. DEV. | 2.58 | |

CHECKED BY: JAM DATE: 9/21/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-31
LAB ID NO.: L15084-31-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-27**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.1 | SE1 | <10 |
| 2 | 105.2 | SE1 | <10 |
| 3 | 109.7 | SE1 | <10 |
| 4 | 109.1 | SE1 | <10 |
| 5 | 108.5 | SE1 | <10 |
| **AVERAGE** | **108.7** | | |
| STD. DEV. | 1.96 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.6 | SE1 | <10 |
| 2 | 114.8 | SE1 | <10 |
| 3 | 120.1 | SE1 | <10 |
| 4 | 125.0 | SE1 | <10 |
| 5 | 121.6 | SE1 | <10 |
| **AVERAGE** | **120.6** | | |
| STD. DEV. | 3.32 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.0 | SE1 |
| 2 | 125.7 | SE1 |
| 3 | 127.8 | SE1 |
| 4 | 128.4 | SE1 |
| 5 | 132.1 | SE1 |
| **AVERAGE** | **128.0** | |
| STD. DEV. | 2.29 | |

CHECKED BY: JD DATE: 9-25-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-32
LAB ID NO.: L15084-32-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-28**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.1 | SE1 | <10 |
| 2 | 107.3 | SE1 | <10 |
| 3 | 111.3 | SE1 | <10 |
| 4 | 108.5 | SE1 | <10 |
| 5 | 108.7 | SE1 | <10 |
| **AVERAGE** | **109.4** | | |
| STD. DEV. | 1.57 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 112.3 | SE1 | <10 |
| 2 | 107.8 | SE1 | <10 |
| 3 | 109.9 | SE1 | <10 |
| 4 | 107.8 | SE1 | <10 |
| 5 | 123.9 | SE1 | <10 |
| **AVERAGE** | **112.3** | | |
| STD. DEV. | 6.01 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.8 | SE1 |
| 2 | 129.0 | SE1 |
| 3 | 129.7 | SE1 |
| 4 | 128.6 | SE1 |
| 5 | 134.3 | SE1 |
| **AVERAGE** | **130.9** | |
| STD. DEV. | 2.26 | |

CHECKED BY: JPK DATE: 10-8-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-32 L L15084-32-02 10/8/2015

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-34
LAB ID NO.: L15084-34-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-29**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.4 | SE1 | <10 |
| 2 | 112.5 | SE1 | <10 |
| 3 | 115.4 | SE1 | <10 |
| 4 | 116.7 | SE1 | <10 |
| 5 | 119.3 | SE1 | <10 |
| **AVERAGE** | **115.1** | | |
| STD. DEV. | 2.85 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.1 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 115.5 | SE1 | <10 |
| 4 | 115.6 | SE1 | <10 |
| 5 | 120.3 | SE1 | <10 |
| **AVERAGE** | **118.2** | | |
| STD. DEV. | 2.32 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 129.5 | SE1 |
| 2 | 131.7 | SE1 |
| 3 | 131.7 | SE1 |
| 4 | 130.7 | SE1 |
| 5 | 132.1 | SE1 |
| **AVERAGE** | **131.1** | |
| STD. DEV. | 0.94 | |

CHECKED BY: JAM DATE: 10/12/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# *Langan – Fusion Weld Destruct Sample Laboratory Data*

Date: 2015-07-23

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17032** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17032**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-2 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 138 | 142 | 138 | 140 | 134 | **138** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 139 | 143 | 140 | 138 | 134 | **139** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 139 | 146 | 143 | 147 | 145 | **144** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-08-04

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

e-mail:dbosworth@langan.com

**Bill To:**

**Langan Environmental Services**
**100530001**

Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17198** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Melissa Hunter
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17198**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-10 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 121 | 121 | 124 | 123 | 122 | **122** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 121 | 118 | 120 | 117 | 125 | **120** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 134 | 133 | 134 | 129 | 130 | **132** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-08-27

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17632** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17632**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-21 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 113 | 115 | 114 | 116 | 115 | **115** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 120 | 119 | 122 | 130 | 128 | **124** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 142 | 147 | 145 | 142 | 144 | **144** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-10-14

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **18404** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 18404**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-29 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 111 | 112 | 110 | 112 | 114 | **112** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 113 | 124 | 111 | 121 | 115 | **117** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 138 | 140 | 140 | 138 | 138 | **139** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

# *Entact / ESI – Extrusion Weld Destruct Sample Laboratory Data*

# Honeywell SA-6 Capping

## *Comparison of ESI / Langan (QA) Destruct Samples - Extrusion Welds*

| ***Sample ID*** | ***Weld Type*** | ***Submitted By:*** | ***Test*** | ***Peel Strength (ppi)*** | | | | | **Avg. Strength (ppi)** | ***Meets Spec Requirement*** |
|---|---|---|---|---|---|---|---|---|---|---|
| EXT-DS-1 | Extrusion | Langan | Peel | 97 | 97 | 127 | 130 | 128 | **116** | **Yes** |
| DSX-1 | | Entact | Peel | 109.3 | 107.5 | 109.8 | 120.5 | 110 | **111.4** | **Yes** |
| EXT-DS-1 | | Langan | Shear | 133 | 172 | 148 | 181 | 146 | **156** | **Yes** |
| DSX-1 | | Entact | Shear | 115.7 | 119.8 | 118.1 | 117.5 | 116.2 | **117.5** | **Yes** |
| DSX-2 | Extrusion | Entact | Peel | 133.5 | 118.8 | 126.4 | 120.1 | 115.4 | **122.8** | **Yes** |
| | | | Shear | 132.7 | 150.3 | 145.5 | 135.4 | 130.3 | **138.8** | **Yes** |
| DSX-3 | Extrusion | Entact | Peel | 123.7 | 117.2 | 117.9 | 119.1 | 120.2 | **119.6** | **Yes** |
| | | | Shear | 126 | 128.6 | 125.1 | 124.5 | 125.1 | **125.9** | **Yes** |
| DSX-4 | Extrusion | Entact | Peel | 128.4 | 132.1 | 133.5 | 134.4 | 139.5 | **133.6** | **Yes** |
| | | | Shear | 144.7 | 143.7 | 141.8 | 150.7 | 145.7 | **145.3** | **Yes** |
| DSX-5 | Extrusion | Entact | Peel | 107.5 | 115.8 | 111.6 | 113.9 | 119.3 | **113.6** | **Yes** |
| | | | Shear | 131.7 | 136.9 | 151.8 | 137 | 149.5 | **141.4** | **Yes** |
| DSX-6 | Extrusion | Entact | Peel | 151.4 | 144.8 | 130.9 | 139.9 | 150.1 | **143.4** | **Yes** |
| | | | Shear | 164.9 | 162.3 | 151.5 | 155.6 | 159.7 | **158.8** | **Yes** |
| DSX-7 | Extrusion | Entact | Peel | 123.7 | 126.8 | 128.7 | 122.2 | 120.7 | **124.4** | **Yes** |
| | | | Shear | 134.6 | 133.7 | 134.8 | 136.2 | 135.5 | **135.0** | **Yes** |
| DSX-8 | Extrusion | Entact | Peel | 129.6 | 119.5 | 124.3 | 130.9 | 120 | **124.9** | **Yes** |
| | | | Shear | 131.6 | 130.7 | 129.7 | 134.4 | 127.8 | **130.8** | **Yes** |
| DSX-9 | Extrusion | Entact | Peel | 108.7 | 124.4 | 120.8 | 112 | 111.6 | **115.5** | **Yes** |
| | | | Shear | 132.8 | 126.8 | 133.9 | 116.1 | 122.8 | **126.5** | **Yes** |
| DSX-10 | Extrusion | Entact | Peel | 118.7 | 122.1 | 118.1 | 120.8 | 136.1 | **123.2** | **Yes** |
| | | | Shear | 123 | 145.2 | 149.5 | 130.7 | 145.6 | **138.8** | **Yes** |
| DSX-11 | Extrusion | Langan | Peel | 125 | 134 | 123 | 121 | 124 | **125** | **Yes** |
| | | Entact | Peel | 125.1 | 118.2 | 125.9 | 123.3 | 120.6 | **122.6** | **Yes** |
| | | Langan | Shear | 164 | 157 | 141 | 137 | 142 | **148** | **Yes** |
| | | Entact | Shear | 122.6 | 124.6 | 126.1 | 127.9 | 128.2 | **125.9** | **Yes** |
| DSX-12 | Extrusion | Entact | Peel | 130.4 | 121.3 | 148.4 | 118.2 | 138.9 | **131.4** | **Yes** |
| | | | Shear | 126.2 | 123.7 | 125 | 124.2 | 122.7 | **124.4** | **Yes** |
| DSX-13 | Extrusion | Entact | Peel | 117 | 97.9 | 123.5 | 66 | 55.6 | **92.0** | **No** |
| | | | Shear | 131.2 | 129 | 133 | 132.9 | 124.6 | **130.1** | **Yes** |
| DSX-14 | Extrusion | Entact | Peel | 119 | 119.7 | 118.8 | 123.3 | 122.6 | **120.7** | **Yes** |
| | | | Shear | 120.9 | 121.4 | 121.7 | 129.5 | 127.4 | **124.2** | **Yes** |
| DSX-15 | Extrusion | Entact | Peel | 119.5 | 114.1 | 123.8 | 111.4 | 106.8 | **115.1** | **Yes** |
| | | | Shear | 132.1 | 135.2 | 138.5 | 137.4 | 141.7 | **137.0** | **Yes** |

You created this PDF from an application that is not licensed to print to novaPDF printer (http://www.novapdf.com)

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-12
LAB ID NO.: L15084-12-01
MATERIAL: 60 MIL HDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-1**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 109.3 | SE3 | <10 |
| 2 | 107.5 | SE3 | <10 |
| 3 | 109.8 | SE3 | <10 |
| 4 | 120.5 | SE3 | <10 |
| 5 | 110.0 | SE3 | <10 |
| **AVERAGE** | **111.4** | | |
| STD. DEV. | 4.62 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 115.7 | SE1 |
| 2 | 119.8 | SE1 |
| 3 | 118.1 | SE1 |
| 4 | 117.5 | SE1 |
| 5 | 116.2 | SE1 |
| **AVERAGE** | **117.5** | |
| STD. DEV. | 1.45 | |

CHECKED BY: JO DATE: 7-27-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-13
LAB ID NO.: L15084-13-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-2**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| 1 | 133.5 | SE3 | <10 |
| 2 | 118.8 | SE3 | <10 |
| 3 | 126.4 | SE3 | <10 |
| 4 | 120.1 | SE3 | <10 |
| 5 | 115.4 | SE3 | <10 |
| **AVERAGE** | **122.8** | | |
| STD. DEV. | 6.41 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.7 | SE2 |
| 2 | 150.3 | SE1 |
| 3 | 145.5 | SE1 |
| 4 | 135.4 | SE1 |
| 5 | 130.3 | SE2 |
| **AVERAGE** | **138.8** | |
| STD. DEV. | 7.72 | |

CHECKED BY: NC DATE: 7/28/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-15
LAB ID NO.: L15084-15-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-3**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 123.7 | SE3 | <10 |
| 2 | 117.2 | SE3 | <10 |
| 3 | 117.9 | SE3 | <10 |
| 4 | 119.1 | SE3 | <10 |
| 5 | 120.2 | SE3 | <10 |
| **AVERAGE** | **119.6** | | |
| STD. DEV. | 2.28 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.0 | SE1 |
| 2 | 128.6 | SE1 |
| 3 | 125.1 | SE1 |
| 4 | 124.5 | SE1 |
| 5 | 125.1 | SE1 |
| **AVERAGE** | **125.9** | |
| STD. DEV. | 1.45 | |

CHECKED BY: JO DATE: 7-30-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-16
LAB ID NO.: L15084-16-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-4**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 128.4 | SE3 | <10 |
| 2 | 132.1 | SE3 | <10 |
| 3 | 133.5 | SE3 | <10 |
| 4 | 134.4 | SE3 | <10 |
| 5 | 139.5 | SE3 | <10 |
| **AVERAGE** | **133.6** | | |
| STD. DEV. | 3.60 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 144.7 | SE1 |
| 2 | 143.7 | SE1 |
| 3 | 141.8 | SE1 |
| 4 | 150.7 | SE1 |
| 5 | 145.7 | SE1 |
| **AVERAGE** | **145.3** | |
| STD. DEV. | 2.98 | |

CHECKED BY: JO DATE: 7-31-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-19
LAB ID NO.: L15084-19-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-5**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 107.5 | SE2 | <10 |
| 2 | 115.8 | SE2 | <10 |
| 3 | 111.6 | SE2 | <10 |
| 4 | 113.9 | SE2 | <10 |
| 5 | 119.3 | SE2 | <10 |
| **AVERAGE** | **113.6** | | |
| STD. DEV. | 3.97 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.7 | SE1 |
| 2 | 136.9 | SE1 |
| 3 | 151.8 | SE1 |
| 4 | 137.0 | SE1 |
| 5 | 149.5 | SE1 |
| **AVERAGE** | **141.4** | |
| STD. DEV. | 7.84 | |

CHECKED BY: JO DATE: 8-6-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-20
LAB ID NO.: L15084-20-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-6**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 151.4 | SE3 | <10 |
| 2 | 144.8 | SE3 | <10 |
| 3 | 130.9 | SE3 | <10 |
| 4 | 139.9 | SE3 | <10 |
| 5 | 150.1 | SE3 | <10 |
| **AVERAGE** | **143.4** | | |
| STD. DEV. | 7.47 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 164.9 | SE1 |
| 2 | 162.3 | SE1 |
| 3 | 151.5 | SE1 |
| 4 | 155.6 | SE1 |
| 5 | 159.7 | SE1 |
| **AVERAGE** | **158.8** | |
| STD. DEV. | 4.77 | |

CHECKED BY: JO DATE: 8-10-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-21
LAB ID NO.: L15084-21-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-7**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 123.7 | SE3 | <10 |
| 2 | 126.8 | SE3 | <10 |
| 3 | 128.7 | SE3 | <10 |
| 4 | 122.2 | SE3 | <10 |
| 5 | 120.7 | SE3 | <10 |
| **AVERAGE** | **124.4** | | |
| STD. DEV. | 2.94 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 134.6 | SE1 |
| 2 | 133.7 | SE1 |
| 3 | 134.8 | SE1 |
| 4 | 136.2 | SE1 |
| 5 | 135.5 | SE1 |
| **AVERAGE** | **135.0** | |
| STD. DEV. | 0.85 | |

CHECKED BY: JO DATE: 8-11-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-21 D L15084-21-03 8/11/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-24
LAB ID NO.: L15084-24-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-8**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 129.6 | SE3 | <10 |
| 2 | 119.5 | SE3 | <10 |
| 3 | 124.3 | SE3 | <10 |
| 4 | 130.9 | SE3 | <10 |
| 5 | 120.0 | SE3 | <10 |
| **AVERAGE** | **124.9** | | |
| STD. DEV. | 4.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.6 | SE1 |
| 2 | 130.7 | SE1 |
| 3 | 129.7 | SE1 |
| 4 | 134.4 | SE1 |
| 5 | 127.8 | SE1 |
| **AVERAGE** | **130.8** | |
| STD. DEV. | 2.18 | |

CHECKED BY: JO DATE: 9-11-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-27
LAB ID NO.: L15084-27-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-9**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 108.7 | SE3 | <10 |
| 2 | 124.4 | SE3 | <10 |
| 3 | 120.8 | SE3 | <10 |
| 4 | 112.0 | SE3 | <10 |
| 5 | 111.6 | SE3 | <10 |
| **AVERAGE** | **115.5** | | |
| STD. DEV. | 6.02 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.8 | SE1 |
| 2 | 126.8 | SE1 |
| 3 | 133.9 | SE1 |
| 4 | 116.1 | SE1 |
| 5 | 122.8 | SE1 |
| **AVERAGE** | **126.5** | |
| STD. DEV. | 6.58 | |

CHECKED BY: JAN DATE: 9/17/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-30
LAB ID NO.: L15084-30-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-10**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 118.7 | SE3 | <10 |
| 2 | 122.1 | SE3 | <10 |
| 3 | 118.1 | SE3 | <10 |
| 4 | 120.8 | SE3 | <10 |
| 5 | 136.1 | SE3 | <10 |
| **AVERAGE** | **123.2** | | |
| STD. DEV. | 6.63 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 123.0 | SE1 |
| 2 | 145.2 | SE1 |
| 3 | 149.5 | SE1 |
| 4 | 130.7 | SE1 |
| 5 | 145.6 | SE1 |
| **AVERAGE** | **138.8** | |
| STD. DEV. | 10.17 | |

CHECKED BY: JO DATE: 9-22-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-27 D L15084-30-01 9/22/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-31
LAB ID NO.: L15084-31-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-11**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 125.1 | SE3 | <10 |
| 2 | 118.2 | SE3 | <10 |
| 3 | 125.9 | SE3 | <10 |
| 4 | 123.3 | SE3 | <10 |
| 5 | 120.6 | SE3 | <10 |
| **AVERAGE** | **122.6** | | |
| STD. DEV. | 2.86 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 122.6 | SE1 |
| 2 | 124.6 | SE1 |
| 3 | 126.1 | SE1 |
| 4 | 127.9 | SE1 |
| 5 | 128.2 | SE1 |
| **AVERAGE** | **125.9** | |
| STD. DEV. | 2.09 | |

CHECKED BY: JO DATE: 9-25-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-31 D L15084-31-01 9/25/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-32
LAB ID NO.: L15084-32-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-12**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 130.4 | SE3 | <10 |
| 2 | 121.3 | SE3 | <10 |
| 3 | 148.4 | SE3 | <10 |
| 4 | 118.2 | SE3 | <10 |
| 5 | 138.9 | SE3 | <10 |
| **AVERAGE** | **131.4** | | |
| STD. DEV. | 11.16 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.2 | SE1 |
| 2 | 123.7 | SE1 |
| 3 | 125.0 | SE1 |
| 4 | 124.2 | SE1 |
| 5 | 122.7 | SE1 |
| **AVERAGE** | **124.4** | |
| STD. DEV. | 1.18 | |

CHECKED BY: JDK DATE: 10-8-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-32 D L15084-32-01 10/8/2015

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-34
LAB ID NO.: L15084-34-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-13**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| 1 | 117.0 | SE2 | <10 |
| 2 | 97.9 | SE2 | <10 |
| 3 | 123.5 | SE2 | <10 |
| 4 | 66.0 | AD1 | 100 |
| 5 | 55.6 | AD1 | 100 |
| **AVERAGE** | **92.0** | | |
| STD. DEV. | 27.04 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.2 | SE1 |
| 2 | 129.0 | SE1 |
| 3 | 133.0 | SE1 |
| 4 | 132.9 | SE1 |
| 5 | 124.6 | SE1 |
| **AVERAGE** | **130.1** | |
| STD. DEV. | 3.13 | |

CHECKED BY: JAM DATE: 10/12/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-34
LAB ID NO.: L15084-34-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-14**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 119.0 | SE2 | <10 |
| 2 | 119.7 | SE2 | <10 |
| 3 | 118.8 | SE2 | <10 |
| 4 | 123.3 | SE2 | <10 |
| 5 | 122.6 | SE2 | <10 |
| **AVERAGE** | **120.7** | | |
| STD. DEV. | 1.89 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 120.9 | SE1 |
| 2 | 121.4 | SE1 |
| 3 | 121.7 | SE1 |
| 4 | 129.5 | SE1 |
| 5 | 127.4 | SE1 |
| **AVERAGE** | **124.2** | |
| STD. DEV. | 3.56 | |

CHECKED BY: JAM DATE: 10/12/15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-34 D L15084-34-02 10/12/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-35
LAB ID NO.: L15084-35-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-15**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 119.5 | SE2 | <10 |
| 2 | 114.1 | SE2 | <10 |
| 3 | 123.8 | SE2 | <10 |
| 4 | 111.4 | SE2 | <10 |
| 5 | 106.8 | SE2 | <10 |
| **AVERAGE** | **115.1** | | |
| STD. DEV. | 5.98 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.1 | SE1 |
| 2 | 135.2 | SE1 |
| 3 | 138.5 | SE1 |
| 4 | 137.4 | SE1 |
| 5 | 141.7 | SE1 |
| **AVERAGE** | **137.0** | |
| STD. DEV. | 3.22 | |

CHECKED BY: JDK DATE: 10-13-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# *Langan – Extrusion Weld Destruct Sample Laboratory Data*

Date: 2015-07-28

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

e-mail:dbosworth@langan.com

**Bill To:**

**Langan Environmental Services**
**100530001**


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17111** |
| Material(s) Tested: | (1) Single Extrusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS - SINGLE TRACK
**TRI Client: Langan Environmental Services**
**Project: Honeywell SA-6 South Capping**

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17111**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: EXT DS-1 \| Weld: Single Extrusion** | | | | | | |
| **Side: Peel** | | | | | | **Peel** |
| Peel Strength (ppi) | 97 | 97 | 127 | 130 | 128 | **116** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 133 | 172 | 148 | 181 | 146 | **156** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-10-05

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com

Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **18270** |
| Material(s) Tested: | (1) Single Extrusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,

Melissa Hunter

Melissa Hunter
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS - SINGLE TRACK
**TRI Client: Langan Environmental Services**
**Project: Honeywell SA-6 South Capping**

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 18270**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DSX-11 \| Weld: Single Extrusion** | | | | | | |
| **Side: Peel** | | | | | | **Peel** |
| Peel Strength (ppi) | 125 | 134 | 123 | 121 | 124 | **125** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 164 | 157 | 141 | 137 | 142 | **148** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

# Appendix O
# Penetration & Pipe Boot Logs

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 7/22/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 073-MW-1BR located at western end of SA-6 Cap on Panel 1/2 seam (approx. 135 ft. north of south end of Cap). Identified as RP-6 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/21/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/25/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 115-E1A-SO located in proximity to northern boundary of SA-6 Cap on Panel #111 / 112 (approx. 15 ft. south of north end of Cap). Identified as RP-419 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing conducted on 9/24/15. Final butyl sealant applied at completion of project on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 7/23/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 115-W3-SO located along northern slope of SA-6 Cap on Panel #8 (approx. 147 ft. north of south end of Cap). Identified as RP-14 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/22/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 8/13/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 115-W5-SO located in proximity to northern boundary of SA-6 Cap on Panel #61 62 (approx. 135 ft. north of south end of Cap). Identified as RP-246 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing conducted on 8/12/15. Final butyl sealant applied at completion of project on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 10/09/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-0 located at approximate center of SA-6 Cap on Panel #125 (approximately 68 ft. south of north end of cap). Identified as RP-457 on *As Built* and *Repair Report*

**AmecFW QA Signature:** BShea 10/9/15

**Independent CQA Monitor Signature:** 10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 10/9/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 10/09/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-1 located at approximate center of SA-6 Cap on Panel #114 / 115 seam. Identified as RP-425 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 10/8/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/22/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-2 located at approximate center of SA-6 Cap on Panel #95. Identified as RP-369 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/21/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/15/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-3 located at approximate center of SA-6 Cap on Panel #74 (along Panel #73/74 seam). Identified as RP-257 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

RShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/14/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/14/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-4 located at approximate center of SA-6 Cap on Panel #58. Identified as RP-243 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BSlieg 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/11/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 8/13/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-5 located at approximate center of SA-6 Cap on Panel #38 (approx. 3 ft. west of Panel 37/38/42 joint). Identified as RP-219 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/12/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell


**STUDY AREA 6 - CAP INSTALLATION**

LANGAN

| **Project:** Study Area 6 South | **Date:** 8/6/2015 |
|---|---|

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-6 located at approximate center of SA-6 Cap on Panel #25 (approx. 74 ft. south of north end of Cap). Identified as RP-188 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/5/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 7/30/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-7 located at approximate center of SA-6 Cap on Panel #11 (approx. 80 ft. north of south end of Cap). Identified as RP-129 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

B.Shea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/29/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 10/9/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-12 located along eastern end of SA-6 (approx. 81 ft. north of south end of Cap). Identified as RP-476 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 10/8/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 9/24/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-14 located along southern edge of SA-6 Cap on Panel #109 (approx. 152 ft. south of north end of Cap). Identified as RP-418 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 9/23/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 8/17/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-16 located along southern edge of SA-6 Cap on Panel #71 (approx. 9 ft. north of south end of Cap). Identified as RP-255 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/14/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 7/31/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-18 located along southern edge of SA-6 Cap on Panel #31/32 seam (approx. 13 ft. north of south end of Cap). Identified as RP-132 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/30/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 7/22/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-20 located at western end of SA-6 Cap on Panel 1 seam (approx. 85 ft. north of south end of Cap). Identified as RP-7 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/21/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 7/27/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE

NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #1 located on Panel #16 (P-16) at approximate Sta. 19+25 (SCB Wall Sta. Numbering). Identified as RP-24 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/24/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 8/11/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE

NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #2 located on Panel #47 (P-47) at approximate Sta. 14+00 (SCB Wall Sta. Numbering). Identified as RP-218 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/10/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 9/15/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE
NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #3 located on Panel #75/78/79 seams (western slope of 2nd utility corridor). Identified as RP-262 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/14/15. Final butyl sealant applied at completion of project on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 9/25/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE
NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #4 located on Panel #113 (approximate center of SA-6), approximately 82 ft. south of north end of Cap. Identified as RP-420 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B.Shea 10/9/15

**Independent CQA Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/24/15. Final butyl sealant applied at completion of project on 10/9/15.

# Appendix P
# Summary of Non-Compliance & Corrective Action Sheets

**LANGAN**

## Notice of Non-Compliance and Corrective Action

Sheet # 1

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/21/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 1<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #3 (P-3). This non-compliance issue is also noted on the 7/21/15 Repair Report, and is identified as RP-3. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 2 ft. by 2.5 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to Photo #5 of 7/21/15 photo log for repair of RP-3.

Geosynthetic Installer Representative Carlos Ramos Date 7-21-15

Independent CQA Monitor [signature] Date 7-21-15

**LANGAN**

# Notice of Non-Compliance and Corrective Action

Sheet # 2

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/21/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 2<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #2 (P-2). This non-compliance issue is also noted on the 7/21/15 Repair Report, and is identified as RP-8. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 1.5 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolina Parris Date 7-21-15

Independent CQA Monitor  Date 7-21-15

**LANGAN**

# Notice of Non-Compliance and Corrective Action

Sheet # 3

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/22/15<br>Contractor in NC: ESI / Entact<br>Non-Compliance No.: 3<br>Notes: Non-Destructive Test |
| **Reference** | |
| Item: Non-Destructive Test Failure<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Failure of Non-Destructive Test along Panel seams 7/8 (located on southern end of SA-6). This non-compliance issue is also noted on the 7/22/15 Repair Report, and is identified as RP-13. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Failure of panel seam 7/8 during non-destructive testing confirmed. Based on length of failed seam (approximately 6 ft.), the entire seam length will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Based on length of seam to be repaired the area will be patched and sealed with extrusion welds following the project specifications and as outlined in the Contractor's Response above.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Based on length of failed seam (approximately 6 ft.), the entire seam was patched and repaired. This failure was repaired with approximate 2 ft. by 6 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolina Garcia Date 7-22-15

Independent CQA Monitor [signature] Date 7-22-15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 4

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/24/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 10<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #17 (P-17). This non-compliance issue is also noted on the 7/24/15 Repair Report, and is identified as RP-30. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 2 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolina Ramos Date 7/27/15

Independent CQA Monitor Date 7/27/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 5

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 8/7/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 5<br>Notes: Vacuum Box Test |
| **Reference** | |
| Item: Vacuum Box Test Failure<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Failed vacuum box test (i.e. leak) detected during vacuum box testing of RP-215 at Panel #50 (P-50). This non-compliance issue is also noted on the 8/7/15 Repair Report, and is identified as a failed test result ("F") for RP-215. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Failed vacuum box test for RP-215 identified and confirmed. Failed weld to be patched and welded according to project specifications, and confirmed via vacuum test.

**Follow Up Action Required**

Patch / repair failed weld with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Failed extrusion weld (identified during vacuum box testing) was patched with an approximate 2 ft. by 2 ft. geomembrane patch over the extrusion weld (Noted as RP-222 on Repair Log). The patch was overlapped a minimum of 4-inches beyond the edges of the failed weld, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to Photos 3,7 of the 8/10/15 Photo Log for supporting photographs.

Geosynthetic Installer Representative Carolina Parra Date 8/10/15

Independent CQA Monitor Date 8/10/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 6

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 9/11/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 6<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #57 (P-57). This non-compliance issue is also noted on the 9/11/15 Repair Report, and is identified as RP-293. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 1.5 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolyn Parnell Date 9/14/15

Independent CQA Monitor Date 9/14/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 7

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 9/16/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 7<br>Notes: Subgrade Irregularity |
| **Reference** | |
| Item: Subgrade Irregularity – Hydrated GCL<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane panel cut to expose underlying geosynthetic clay liner (GCL). GCL wet / hydrated from weekend storms. Ground surface elevation outside of the SA-6 cap (along southern end of SA-6) was higher than cap grades which caused surface water to flow towards the cap during a major rain event. Rainwater able to pool / pond and infiltrate underneath geomembrane panels thus hydrating GCL. This non-compliance issue is also noted on the 9/16/15 Repair Report, and is identified as RP-331. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Hydrated GCL confirmed as subgrade irregularity. GCL to be cut (where hydrated), removed, and replaced and the geomembrane will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove hydrated GCL from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane cap was cut and GCL was exposed. Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. The cut in the geomembrane was then repaired with approximate 2 ft. by 18 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to Photos #2 and #3 of 9/16/15 photo log for placement of new GCL

Geosynthetic Installer Representative Carolina Ramos Date 9/17/15

INDEPENDENT CQA MONITOR [signature] Date 9/17/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 8

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 9/24/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 8<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #111 (P-111). This non-compliance issue is also noted on the 9/24/15 Repair Report, and is identified as RP-423. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 1.5 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative _____ Date 9/25/15

Independent CQA Monitor _____ Date 9/25/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 9

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 10/7/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 9<br>Notes: Subgrade Irregularity |
| **Reference** | |
| Item: Subgrade Irregularity – Hydrated GCL<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane Panels #121-125 (southern end of SA-6 within swale) cut to expose underlying geosynthetic clay liner (GCL). GCL wet / hydrated from weekend storms. Ground surface elevation outside of the SA-6 cap (along southern end of SA-6) was higher than cap grades which caused surface water to flow towards the cap during a major rain event. Rainwater able to pool / pond and infiltrate underneath geomembrane panels from failure of pump during storms thus hydrating GCL along the southern end of SA-6. This non-compliance issue is also noted on the 10/7/15 Repair Report, and is identified as the following repairs (RP-458 through RP-473). The location of these repairs were recorded and logged (via GPS) by the team (southern swale of SA-6).

**Contractor's Response**

Hydrated GCL confirmed as subgrade irregularity. GCL to be cut (where hydrated), removed, and replaced and the geomembrane will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove hydrated GCL from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane cap was cut and GCL was exposed (southern swale of SA-6). Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. Various cuts in the geomembrane were then repaired. Patches were overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to *10/7/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carolina Ramos Date 10/8/15

Independent CQA Monitor [signature] Date 10/8/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 10

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 10/7/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 10<br>Notes: Subgrade Irregularity |
| **Reference** | |
| Item: Subgrade Irregularity – Hydrated GCL<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane Panels #117 and Panel #119/120 (northern end of SA-6 along SCB wall) cut to expose underlying geosynthetic clay liner (GCL). GCL wet / hydrated from weekend storms. Ground surface elevation outside of the SA-6 cap (along northern end of SA-6) was higher than cap grades which caused surface water to flow towards the cap during a major rain event. Rainwater and wash out along adjacent roadway (higher elevation) along northern end of SA-6 (SCB wall) able to infiltrate laterally and hydrate GCL. This non-compliance issue is also noted on the 10/7/15 Repair Report, and is identified as RP-474 and RP-475 (two cuts along geomembrane to fold back geomembrane cap). The location of these repairs were recorded and logged (via GPS) by the team.

**Contractor's Response**

Hydrated GCL confirmed as subgrade irregularity. GCL to be cut (where hydrated), removed, and replaced and the geomembrane will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove hydrated GCL from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane cap was cut and GCL was exposed (along northern end of SA-6 at SCB wall). Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. Various cuts in the geomembrane were then repaired (RP-474 & RP-475). Patches were overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to *10/7/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carolina Ramos Date 10/8/15

Independent CQA Monitor Date 10/8/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 11

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 10/12/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 11<br>Notes: Failed Destruct Sample |
| **Reference** | |
| Item: Failed Destruct Sample<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Destruct sample DSX-13 (RP-483) collected from RP-477 from Panel #125, failed on one of the five specimens for peel testing completed by the Geosynthetic Installer's Laboratory (Note: average of the five specimens was acceptable). Based on this failure, RP-477 (entire patch) was covered with a new patch and sealed with an extrusion weld. This non-compliance issue was also noted on the 10/12/15 Repair Report, and is identified as RP-486. The location of this repair was recorded and logged (via GPS) by the team (southern swale).

**Contractor's Response**

Destruct sample DSX-13 failure for one of five specimens confirmed. Repair associated with destruct sample (P-125 on southern end of SA-6) to be covered with new patch, sealed, and extrusion welded according to project specifications. Additional destruct sample to be taken from new extrusion weld (from new patch) to confirm repair.

**Follow Up Action Required**

Place patch over RP-477 and repaired and sealed with extrusion weld, according to project specs.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane patch was placed over RP-477 and was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the patch was properly sealed (as outlined in Section 02372). Additionally, once the new patch (RP-486) was completed, an additional extrusion destruct sample (DSX-15) was collected (referred to as RP-487) to confirm the integrity of the new weld. Refer to *10/12/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carolyn Ramos Date 10/13/15

Independent CQA Monitor Date 10/13/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 12

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 11/04/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 11<br>Notes: Equipment Puncture |
| **Reference** | |
| Item: Equipment Puncture through Cap<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Equipment puncture through geomembrance cap observed along SCB wall (northern end of SA-6 cap). Puncture to be patched / repaired according to project specs. Additional details on the patch / repair work completed are described in the *11/4/15 Daily Report* and *11/4/15 Photograph Log*. This non-compliance issue was also noted on the 11/04/15 Repair Report, and is identified as RP-488. The location of this repair was recorded and logged (via GPS) by the team (along SCB wall).

**Contractor's Response**

Equipment puncture through geomembrane along SCB wall confirmed. Puncture to be covered with new patch, sealed, and extrusion welded according to project specifications.

**Follow Up Action Required**

Place patch over puncture location and repair and seal with extrusion weld according to project specs.


**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane patch was placed over the equipment puncture and was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Prior to welding, a new piece of GCL was placed along the SCB wall over the puncture area. Upon completion of extrusion welding, vacuum box testing could not be completed based on the location of the patch (along edge of SCB wall). The welds were visually inspected by Entact and Langan. Refer to *11/04/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carlos Ramos Date 11/5/15

Independent CQA Monitor Date 11/5/15




- REPAIRS WERE CONDUCTED BETWEEN APRIL 6-13, 2016.
- "X" IDENTIFIES THE GENERAL LOCATION WHERE COVER SOIL HAD BEEN ERODED AND THE GDL EXPOSED FOR MORE THAN 30 DAYS.
- COVER SOIL CLEANED BACK 2 FT. BEYOND THE EXPOSED MARGIN TO PROVIDE WORKING AREA FOR THE REPAIR.
- AN ADDITIONAL LAYER OF SKAPS ORANGE GEOTEXTILE WAS PLACED OVER THE EXPOSED GDL.
- EDGES OF THE NEW GEOTEXTILE WERE "LYSTERED" (HEAT BONDED) TO THE ORIGINAL TOP LAYER OF GEOTEXTILE
- ERODED COVER SOIL WAS DISCARDED AND REPLACED WITH SOIL FROM THE SCREENED COVER SOIL STOCKPILE.

LEGEND

RGDL = REPAIRED GDL

0 15 30 60
SCALE IN FEET

Prepared/Date: RJR 06/07/16
Checked/Date: SGS 06/07/16

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019300

SA-6 South
Winter 2015-2016 GDL Repairs
Project 3480-13-0377
Figure 1

Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-6230\CAD\SA6S GA-6 South Construction Surveys\Figure - GDL Repair.dwg Wed, 08 Jun 2016 - 3:08pm roger.ripley

# APPENDIX R

# DRAFT DEED NOTICE DOCUMENATS (CD ONLY)

**DRAFT DEED NOTICE**

IN ACCORDANCE WITH N.J.S.A. 58:10B-13, THIS DOCUMENT IS TO BE RECORDED IN THE SAME MANNER AS ARE DEEDS AND OTHER INTERESTS IN REAL PROPERTY.

Prepared by: _____
[Signature]

_____
[Bayfront Redevelopment LLC]

Recorded by:

_____
[Signature, Officer of County Recording Office]

_____
[Print name below signature]

# DEED NOTICE CONCERNING CONTROLS INSTALLED TO CONTAIN CHROMIUM AND HISTORIC FILL CONTAMINATION UNDERLYING THE PROMENADE

This Deed Notice is made as of the __ day of _____, 2017, by ***Bayfront Redevelopment LLC, whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950***. Owner shall mean Bayfront Redevelopment LLC together with its successors and assigns, including all successors in interest in the Property which is the subject of this Deed Notice as described fully below. The Property (also referenced herein as the "Restricted Areas") shall consist of those lands particularly described by metes and bounds in Exhibit A-2 attached hereto.

1. THE PROPERTY. Bayfront Redevelopment LLC is the current owner in fee simple of certain real property designated as those portions of ***Block 24601, Lots 1 through 8*** and portions of ***Block 21901 Lot 8 on the tax map of the City of Jersey City, Hudson County*****, New Jersey**[1]; the New Jersey Department of Environmental Protection ("the Department") Program Interest ("PI") Numbers for the contaminated site which includes this property are ***Hudson County Chromate Site***

[1] All references to Block 24601 Lots 1 through 8 and Block 21901 Lot 8 in this Deed Notice shall mean the applicable portions of Block 24601 Lots 1 through 8 and portions of Block 21901 Lot 8 as shown in the metes and bounds description, regardless of whether the word "portion(s)" is specifically called out or not.

***No. 073 PI #G00000927, Hudson County Chromate Site No. 124 PI# G000008741, Hudson County Chromate Site No. 125 PI# G000008742, Hudson County Chromate Site No. 134 PI# 033312, Hudson County Chromate Site No. 140 PI# 003846*** (NJDEP PI# for non-chromium-related contaminants at the Property is #745719)**,** and known as the Open Space AOC pursuant to the First Amended Consent Decree Regarding the Remediation and Redevelopment of Study Area 6 South ("Consent Decree") which is attached hereto as Appendix I and is entered as an order of the Court in the following consolidated actions *JCMUA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-05955; *JCIA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-5993; and *Hackensack Riverkeeper, Inc. v. Honeywell International, Inc.,* D.N.J., Civ. No. 06-22 (consolidated under Civ. No. 95-2097). The approximate location of the Open Space AOC is also referred to as the Promenade in the Bayfront I Redevelopment Plan adopted by Jersey City on March 12, 2008. The Consent Decree restricts transfer, use and development of the Property. To the extent that there is any conflict or inconsistency between the terms of this Deed Notice and the terms of the Consent Decree, the Consent Decree shall govern.

2. REMEDIATION.

i. The Department's Bureau of State Case Management (BCM) is the entity within the Department that is responsible for the oversight of the chromium remediation of the Property. The matter was Hudson County Chromate Site No. 073 PI# G000000927, Hudson County Chromate Site No. 124 PI# G000008471, Hudson County Chromate Site No. 125 PI# G000008742, Hudson County Chromate Site No. 134 PI# 033312, and Hudson County Chromate Site No. 140 PI# 003846. The Department has approved this Deed Notice as an institutional control for the Property, which is part of the remediation of the Property.

ii. N.J.A.C. 7:26-C-7 requires the Owner, among other persons, including the responsible party Honeywell International Inc. ("Honeywell"), to obtain a soil remedial action permit for the soil remedial action at the Property. That permit will contain the monitoring, maintenance and biennial certification requirements that apply to the Property.

3. SOIL AND GROUNDWATER CONTAMINATION. Honeywell, a corporation of the State of Delaware, licensed to do business in the State of New Jersey whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950, has remediated SA-6 South to address chromium-related and non-chromium soil and shallow groundwater contamination, except for the Open Space Area Property and certain other deed noticed areas where engineering controls were implemented. The Remedial Action Work Plan ("RAWP") for chromium remedial actions was approved by the Department on March 24, 2009 for Hudson County Chromate Site Nos. 073, 124, 125, 134, and 140, which include the Property for chromium. The RAWP for non-chromium remedial actions was approved by the Department on June 28, 2013 for Hudson County Site Nos. 073, 124, 125, 134, and 140. Remedial actions for chromium were further approved pursuant to the Consent Decree.

Under both the Consent Decree and the RAWP, soil and groundwater contamination remain in the Property at concentrations that do not allow for the unrestricted use of the Property. A Remedial Action Report ("RAR") for SA-6 South was submitted to the Department on February 8, 2017. The Department approved the RAR on March 30, 2017. A Construction Completion Report

("CCR") for SA-6 South to document the implementation of the Chromium Remedy pursuant to Article III of the Consent Decree (the "Chromium Remedy") to address chromium-impacted soil and groundwater for SA-6 South was entered by the Court on [DATE], [CITE TO DOCKET AND DOCKET #].

The Property encompasses approximately 8 acres. The horizontal extents of the Property include an existing soil-cement bentonite ("SCB") wall along the northern boundary with SA-7 and the hydraulic barrier walls installed on the other three sides as part of the Chromium Remedy. The engineered barrier in the Property consists of the hydraulic barrier walls and an engineered Resource Conservation and Recovery Act ("RCRA") cap that includes a gas collection system, base protective layer, geomembrane liner, geocomposite drainage layer, filter fabric, warning layer, and cover soils. This Deed Notice includes the hydraulic barrier walls. The Property includes chromium, xylenes, and historic fill. Honeywell will restrict, or will cause Bayfront Redevelopment LLC to restrict, the future use of this area by implementing a conservation restriction, which has been recorded at the Office of the Hudson County Register, and transfer, or cause Bayfront Redevelopment LLC to transfer, title to the City of Jersey City (as called for in Paragraph 61(c)(ii)(3) of the Consent Decree). The provisions of the Long Term Monitoring Plan ("LTMP") and the Open Space Design Standards ("OSDS"), developed pursuant to the Consent Decree, will apply to the Property.

The soil contamination is described, including the type, concentration and specific location of such contaminants, in Exhibit B, which is attached hereto and made a part hereof. Groundwater within the property remains contaminated. Groundwater contaminant concentrations and restrictions for SA-6 South in its entirety are addressed in the Classification Exception Area (CEA) approved by the NJDEP on February 16, 2012 and in a forthcoming Remedial Action Permit for Groundwater. As a result of the remaining soil contamination, there is a statutory requirement for this Deed Notice and engineering controls in accordance with N.J.S.A. 58:10B-13. Under the terms of the Consent Decree and this Deed Notice, Honeywell is responsible for monitoring and maintaining the soil and groundwater remediation for the Property in perpetuity.

4. CONSIDERATION. In accordance with the Department's approval of the chromium and non-chromium RAWPs for the remediation for the Hudson County Chromate Site Nos. 073, 124, 125, 134, and 140 which includes the Property, and in consideration of the terms and conditions of that approval, and in accordance with the Consent Decree, and other good and valuable considerations, Owner has agreed to subject the Property to certain statutory and regulatory requirements which impose restrictions upon the use of the Property, to restrict certain uses of the Property, and to provide notice to subsequent owners, lessees and operators of the restrictions and the monitoring, maintenance, and biennial certification requirements outlined in this Deed Notice and required by law, as set forth herein.

5A. RESTRICTED AREAS. Due to the presence of these contaminants, Owner has agreed, as part of the remedial action for the Property, to restrict the use of the Property (the "Restricted Areas"); a narrative description of these restrictions, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C, which is attached hereto and made a part hereof. Owner will develop a binder containing a list of these restrictions

which will be maintained at either the onsite trailers or within the Groundwater Treatment Plant building, available for review and inspection by governmental enforcement officials if requested.

5B. RESTRICTED LAND USES. The following land use restrictions apply to the Property:

i. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(10), prohibits the conversion of a contaminated site, remediated to non-residential soil remediation standards that require the maintenance of engineering or institutional controls, to a child care facility, or public, private, or charter school without the Department's prior written approval, unless a presumptive remedy is implemented;

ii. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(12), prohibits the conversion of a landfill, with gas venting systems and or leachate collection systems, to a single family residence or a child care facility without the Department's prior written approval;

iii. The Consent Decree, paragraph 74, prohibits development in the Property except as allowed by paragraphs 74(j) and (k) of the Consent Decree; and

iv. The Conservation Restriction, recorded with the Hudson County Register of Deeds at Book 8722, page 105, restricts the use and development of the Property.[2]

5C. ENGINEERING CONTROLS. Due to the presence and concentration of these contaminants, the Owner has also agreed, as part of the remedial action for the Property, to the placement of certain engineering controls within the Property. A narrative description of these engineering controls, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C. Honeywell shall be responsible for monitoring and maintenance of engineering controls and biennial certification requirements as specified in the Consent Decree, the LTMP, and Paragraphs 8A and 8B herein.

5D. LONG TERM MONITORING PLAN. Pursuant to the Consent Decree, Honeywell has prepared an LTMP which sets forth requirements for monitoring, maintaining, and repairing or replacing the soil and groundwater chromium remedial measures including engineering controls within the Property, and requirements for notification and reporting pursuant to the Consent Decree, Deed Notice, and Soil Remedial Action Permit. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950. This Deed Notice is appended to the LTMP.

5E. OPEN SPACE DESIGN STANDARDS. Pursuant to the Consent Decree, Honeywell has prepared the OSDS which set forth the standards that must be met to ensure the protection of the Chromium Remedy during all development and other intrusive work conducted within the Property.

[2] In the future, after the remediation of the area known as the Bulkhead Deferred Area is completed and approved by the Special Master, the boundary of the existing conservation restriction recorded on the Property will be amended to conform to the location of the as-built hydraulic barrier walls.

5F. WORKER TRAINING MATERIALS. All maintenance workers engaged in maintenance at the Property shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy. Workers shall be trained using materials developed by Honeywell pursuant to the Consent Decree.

6A. CHANGE IN OWNERSHIP AND REZONING.

i. The Owner and the subsequent owners and lessees, shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. The Owner and the subsequent owners shall provide written notice to the Department of Environmental Protection on a form provided by the Department and available at www.nj.gov/srp/forms within thirty (30) calendar days after the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property.

iii. The Owner and the subsequent owners shall provide written notice to the Department, on a form available from the Department at www.nj.gov/srp/forms, within thirty (30) calendar days after the owner's petition for or filing of any document initiating a rezoning of the Property to residential.

6B. SUCCESSORS AND ASSIGNS. This Deed Notice shall be binding upon Owner and upon Owner's successors and assigns, and subsequent owners, lessees, and operators while each is an owner, lessee, or operator of the Property.

7A. ALTERATIONS, IMPROVEMENTS, AND DISTURBANCES.

i. The Owner and all subsequent owners and lessees shall notify any person of whom it has knowledge, including, without limitation, tenants, employees of tenants, developers, and contractors, intending to conduct invasive work or excavate within the Property, of the nature and location of known contamination in the Property, and, of the precautions necessary to protect the engineering controls and minimize potential human exposure to contaminants.

ii. Except as provided in the Consent Decree and Paragraph 7B below, no person shall make, or allow to be made, any alteration, improvement, or disturbance in, to, or about the Property which disturbs any engineering control at the Property except as (a) permitted in the Consent Decree and Conservation Restriction, (b) as is consistent with the OSDS, and (c) without first obtaining a Soil Remedial Action Permit modification from the Department. Nothing herein shall constitute a waiver of the obligation of any person to comply with all applicable laws and regulations including, without limitation, the applicable rules of the Occupational Safety and Health Administration.

iii. Notwithstanding subparagraph 7A.ii.(c), above, a Soil Remedial Action Permit modification is not required for any alteration, improvement, or disturbance provided that:

(A) Such action is taken in conformance with the Consent Decree, the OSDS, and this Deed Notice; and

(B) The Department of Environmental Protection is notified of the activity by calling the DEP Hotline, at 1-877-WARN-DEP or 1-877-927-6337, within twenty-four (24) hours after the beginning of each alteration, improvement, or disturbance; and

(C) Honeywell is notified of the activity by calling 855-727-2658; and

(D) Honeywell and/or the owner restores any disturbance of an engineering control to pre-disturbance conditions, consistent with the requirements of the Consent Decree and LTMP, within sixty (60) calendar days after the initiation of the alteration, improvement or disturbance; and

(E) All applicable worker health and safety laws and regulations are followed during the alteration, improvement, or disturbance, and during the restoration; and

(F) Appropriate measures are taken so that human exposure, and exposure of the environment outside the containment of the engineering controls, to contamination in excess of the applicable remediation standards does not occur; and

(G) The next biennial certification includes a description of the nature of the alteration, improvement, or disturbance, the dates and duration of the alteration, improvement, or disturbance, the name of key individuals and their affiliations conducting the alteration, improvement, or disturbance, a description of the notice the Owner gave to those persons prior to the disturbance, the amounts of soil generated for disposal, if any, the final disposition and any precautions taken to prevent exposure.

7B. EMERGENCIES. In the event of an emergency which presents, or may present, an unacceptable risk to the public health and safety, or to the environment, or immediate environmental concern, see N.J.S.A. 58:10C-2, any person may temporarily breach an engineering control provided that:

i. The Department of Environmental Protection is immediately notified of the emergency, by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

ii. Immediately after notifying NJDEP, Honeywell is notified of the emergency by calling 855-727-2658; and

iii. Both the actual disturbance and the time needed for the disturbance are limited to the minimum reasonably necessary to adequately respond to the emergency; and

iv. All measures necessary to limit actual or potential, present or future risk of exposure to humans or the environment to the contamination are implemented; and

v. The Department of Environmental Protection is notified when the emergency has ended by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

vi. Honeywell is notified when the emergency has ended by calling 855-727-2658; and

vii. Honeywell restores the engineering control to the pre-emergency conditions, consistent with the requirements of the Consent Decree and LTMP, as soon as possible, and submits a written report to the Department of Environmental Protection of such emergency and restoration efforts within sixty (60) calendar days after completion of the restoration of the engineering control. The report must include all information pertinent to the emergency, potential discharges of contaminants, and restoration measures that were implemented, which, at a minimum, should specify: (a) the nature and likely cause of the emergency, (b) the potential discharges of or exposures to contaminants, if any, that may have occurred, (c) the measures that have been taken to mitigate the effects of the emergency on human health and the environment, (d) the measures completed or implemented to restore the engineering control, and (e) the changes to the engineering control or site operation and maintenance plan to prevent recurrence of such conditions in the future. Honeywell shall submit the report to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413

8A. MONITORING AND MAINTENANCE OF DEED NOTICE, AND PROTECTIVENESS CERTIFICATION. The persons in any way responsible, pursuant to the Spill Compensation and Control Act, N.J.S.A. 58:10-23.11a et seq., for the hazardous substances that remain at the Property, the persons responsible for conducting the remediation, Honeywell, the Owner, and the subsequent owners, lessees, and operators, shall monitor and maintain this Deed Notice. The subsequent owners, lessees and operators have this obligation only during their ownership, tenancy, or operation. Honeywell shall certify to the Department on a biennial basis that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the deed notice shall include all of the following:

i. Monitoring and maintaining this Deed Notice according to the requirements in Article III of the Consent Decree, and Exhibit C herein, to ensure that the remedial action that includes the Deed Notice continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes this Deed Notice, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

8B. MONITORING AND MAINTENANCE OF ENGINEERING CONTROLS, AND PROTECTIVENESS CERTIFICATION. Honeywell shall maintain all engineering controls at the Property and certify to the Department on a biennial basis that the remedial action of which each engineering control is a part remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the engineering controls shall include the following:

i. Monitoring and maintaining each engineering control according to the requirements in Article III of the Consent Decree, the LTMP, and Exhibit C herein, so that the remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes the engineering control remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes the engineering control, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

9. ACCESS. The Owner, subsequent owners, lessees, and operators, agree to allow the Department, its agents and representatives access to the Property to inspect and evaluate the continued protectiveness of the remedial action that includes this Deed Notice and to conduct additional remediation to ensure the protection of the public health and safety and of the environment if the persons responsible for monitoring the protectiveness of the remedial action, as described in Paragraph 8, above, fail to conduct such remediation pursuant to this Deed Notice as required by law. The Owner, and the subsequent owners and lessees, shall also cause all leases, subleases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring that all holders thereof provide such access to the Department.

10. NOTICES.

i. Owner shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall be construed as limiting any obligation of

any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. Honeywell or the Owner shall notify any person intending to conduct invasive work or excavate within the Property of the nature and location of contamination and, of the precautions necessary to minimize potential human exposure, and exposure of the environment outside the containment of the engineering controls, to contaminants.

iii. Owner shall provide written notice to the Department of Environmental Protection at least thirty (30) calendar days before the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property. Any such conveyance, grant or gift must be consistent with the terms of the Consent Decree.

iv. Owner shall provide written notice to the Department within thirty (30) calendar days following the Owner's receiving notice of any petition for a rezoning of the Property. Any such rezoning must be consistent with the terms of the Consent Decree. The Owner shall submit the written notice to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413.

11. ENFORCEMENT OF VIOLATIONS.

i. This Deed Notice itself is not intended to create any interest in real estate in favor of the Department of Environmental Protection, nor to create a lien against the Property, but merely is intended to provide notice of certain conditions and restrictions on the Property and to reflect the regulatory and statutory obligations imposed as a conditional remedial action for this Property.

ii. The restrictions provided herein may be enforceable by the Department against any person who violates this Deed Notice. To enforce violations of this Deed Notice, the Department may initiate one or more enforcement actions pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C, and require additional remediation and assess damages pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C.

iii. This Deed Notice is also enforceable in the United States District Court for the District of New Jersey by all residents, owners, lessees, and all commercial tenants on Study Areas 6 and 7 pursuant to paragraphs 80 and 83 of the Consent Decree.

12. SEVERABILITY. If any court of competent jurisdiction determines that any provision of this Deed Notice requires modification, such provision shall be deemed to have been modified automatically to conform to such requirements. If a court of competent jurisdiction determines that

any provision of this Deed Notice is invalid or unenforceable and the provision is of such a nature that it cannot be modified, the provision shall be deemed deleted from this instrument as if the provision had never been included herein. In either case, the remaining provisions of this Deed Notice shall remain in full force and effect.

13. MODIFICATION AND TERMINATION.

i. Any person may request in writing, at any time, that the Department modify this Deed Notice where performance of subsequent remedial actions, a change of conditions at the Property, or the adoption of revised remediation standards suggest that modification of the Deed Notice would be appropriate, provided that any such modification is consistent with the requirements of the Consent Decree.

ii. Any person may request in writing, at any time, that the Department terminate this Deed Notice because the conditions which triggered the need for this Deed Notice are no longer applicable.

iii. Any person seeking a modification or termination of this Deed Notice must also have such modification approved by the United States District Court for the District of New Jersey pursuant to the Consent Decree until such time as the Consent Decree terminates with regard to the Property pursuant to the Consent Decree.

iv. If the United States District Court for the District of New Jersey and NJDEP have concluded that this Deed Notice shall be modified or terminated, such modification or termination will only be effective upon the filing of a Termination of Deed Notice, available at N.J.A.C. 7:26C Appendix C, with the office of the Register of Deeds of Hudson County, New Jersey, expressly modifying or terminating this Deed Notice.

v. Within thirty (30) calendar days after the filing of a Termination of Deed Notice, the owner of the Property shall apply to the Department for modification or termination of the Soil Remedial Action Permit pursuant to N.J.A.C. 7:26C-7.

vi. This Deed Notice may be modified only if it has first been terminated pursuant to subparagraphs 13v above, and upon filing of a modified Deed Notice, executed by the Owner of the Property, in the office of the Register of Deeds of Hudson County, New Jersey.

14A. EXHIBIT A. Exhibit A includes the following maps of the Property and the vicinity:

i. Exhibit A-1: Vicinity Map - A map that identifies by name the roads, and other important geographical features in the vicinity of the Property;

ii. Exhibit A-2: Metes and Bounds Description of Property - A metes and bounds description of the Property, including reference to tax lot and block numbers for the Property and a Tax Map;

iii. Exhibit A-3: Property Maps (Exhibits A-3A and A-3B) - Scaled maps of the Property, scaled at one inch to 200 feet or less, and if more than one map is submitted, the maps shall be presented as overlays, keyed to a base map; the map(s) shall include diagrams of major surface topographical features such as buildings, roads, and parking lots. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as buildings, roads, and parking lots.

14B. EXHIBIT B. Exhibit B includes the following descriptions of the Restricted Areas:

i. Exhibit B-1 and B-2 (Exhibits B-1A, B-1B, B-2A, B-2B, and B-2C): Restricted Area Maps - Maps for the Property that include, as applicable:

(A) As-built diagrams of each engineering control, including caps, fences, hydraulic barrier walls, ground water monitoring wells, and ground water pumping system including trenches and pumps;

(B) As-built diagrams of any buildings, roads, parking lots, utility corridors, and other structures that function as engineering controls; and

(C) Designation of all soil and/or sediment sample locations within the restricted areas that exceed any soil or sediment standard that are keyed into one of the tables described below.

ii. Exhibit B-3 (Table B-3): Restricted Area Data Tables - A separate table for each restricted area that includes either (A) or (B) through (F):

(A) Only for historic fill extending over the entire site or a portion of the site and for which analytical data are limited or do not exist, a narrative that states that historic fill is present at the site, a description of the fill material (e.g., ash, cinders, brick, dredge material), and a statement that such material may include, but is not limited to, contaminants such as PAHs and metals;

(B) Sample location designation from Restricted Area map (Exhibit B-1);

(C) Sample elevation based upon mean sea level;

(D) Name and chemical abstract service registry number of each contaminant with a concentration that exceeds the unrestricted use standard;

(E) The restricted and unrestricted use standards for each contaminant in the table; and

(F) The remaining concentration of each contaminant at each sample location at each elevation (or if historic fill, include data from the Department's default concentrations at N.J.A.C. 7:26E-4.6, Table 4-2).

14C. EXHIBIT C. Exhibit C includes narrative descriptions of the institutional controls and engineering controls as follows:

i. Exhibit C-1A through C-1D. Exhibit C-1A: Deed Notice as Institutional Control; Exhibit C-1B: Consent Decree as Institutional Control (attached); Exhibit C-1C: Zoning as Institutional Control; Exhibit C-1D: Conservation Restriction as Institutional Control (recorded at Hudson County Register of Deeds as indicated in Paragraph 3): Exhibit C-1 includes a narrative description of the restrictions and obligations of this Deed Notice that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
(1) Description and estimated size of the Restricted Areas as described above;
(2) Description of the restrictions on the Property by operation of this Deed Notice and the other Institutional Controls; and
(3) The objective of the restrictions;

(B) Description of the monitoring necessary to determine whether:
(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;
(2) There have been any land use changes subsequent to the filing of this Deed Notice and the other Institutional Controls or the most recent biennial certification, whichever is more recent;
(3) The current land use on the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls;
(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the Property; and
(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice and the other Institutional Controls, and conduct the necessary sampling; and

(C) Description of the following items that will be included in the biennial certification:
(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice and the other Institutional Controls;
(2) Land use at the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls; and
(3) The remedial action that includes this Deed Notice and the other Institutional Controls continues to be protective of the public health and safety and of the environment.

ii. Exhibit C-2A through C-2C. Exhibit C-2A: Engineering Controls: Clean Fill and Soil Capping System; Exhibit C-2B: Engineering Controls: Underground Containment Walls; Exhibit C-2C: Engineering Controls: Shallow Groundwater Collection and Treatment System.

Exhibit C-2 includes a narrative description of the engineering controls as follows:

(A) General Description of the engineering control:
(1) Description of the engineering control;
(2) The objective of the engineering control; and
(3) How the engineering control is intended to function.

(B) Description of the operation and maintenance necessary to ensure that:
(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;
(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;
(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering control;
(4) The engineering control is being inspected and maintained and its integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;
(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering control. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering control; and
(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling.

(C) Description of the following items that will be included in the biennial certification:
(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;
(2) The engineering control continues to operate as designed; and
(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

15. SIGNATURES. IN WITNESS WHEREOF, Owner has executed this Deed Notice as of the date first written above.

ATTEST: , LLC

_____ By_____
[Signature] [Signature]

_____ _____
[Print name and title] [Print name and title]

STATE OF NEW JERSEY SS.:
COUNTY OF _____

I certify that on _____ ___, 2017, _____ personally came before me, and this person acknowledged under oath, to my satisfaction, that:

(a) this person is the _____ of _____, LLC, the Limited Liability Corporation named in this document;

(b) this person is the attesting witness to the signing of this document by the proper corporate officer who is the _____ of the Limited Liability Corporation;

(c) this document was signed and delivered by the Limited Liability Corporation as its voluntary act and was duly authorized;

(d) this person knows the proper seal of the Limited Liability Corporation which was affixed to this document; and

(e) this person signed this proof to attest to the truth of these facts.

_____
[Signature]

_____
[Print name and title of attesting witness]

Signed and sworn before me on _____, 20__

_____, Notary Public

_____
[Print name and title]

**EXHIBIT A**
**Deed Notice #1 Property**

**A-1 Vicinity Map**

**A-2 Metes and Bounds Description of the Property and Tax Map**

**A-3 Property Maps portions of Block 24601, Lots 1 through 8 and a portion of Block 21901 Lot 8, City of Jersey City, New Jersey**

Exhibit A-1 Vicinity Map consists of a road map for the vicinity of the Property.

Exhibit A-2 consists of the metes and bounds and a tax map for the Property.


Exhibit A-3A and A-3B Property Maps consist of figures indicating major surface features and engineering control for the Property. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as buildings, roads, and parking lots.

**Exhibit A-1**
**Site Vicinity Map**

EXHIBIT A-1
SITE VICINITY MAP
STUDY AREA 6 SOUTH SITES 073, 124, 125, 134, and 140
JERSEY CITY, NEW JERSEY

CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS PREPARED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710104\deed notice\deed notice 1\5100\CURRENT DRAWINGS\3480150450-5100-A100-1000.dwg Fri, 10 Mar 2017 - 1:32pm




SOURCE: USGS QUADRANGLE MAP, 7.5 MIN SERIES
JERSEY CITY, NJ-NY 1967, PHOTO REVISED 1981

OPEN SPACE AOC
RESTRICTED AREA

**DRAFT**

0 1000 2000 4000
SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150450<br>*DRAWING:* 3480150450-5100-A100-1000 | |
| *PREPARED/DATE:* STR 01/28/16 | *CHECKED/DATE:* NW 01/31/17 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT A-1**
VICINITY MAP
BLOCK 24601 LOTS 1-8 &
BLOCK 21901 LOT 8
DEED NOTICE # 1 SA-6 SOUTH
OPEN SPACE AOC PROPERTY
JERSEY CITY, NEW JERSEY

**Exhibit A-2**
**Deed Notice #1 Property**
**Metes and Bounds Description**
**and Tax Map**

A-2 Metes and Bounds Description of Property **portions of** Block 24601, Lots 1 through 8 and a **portion of** Block 21901 Lot 8 City of Jersey City, New Jersey (see attached).

**If there is any discrepancy between the Metes and Bounds and the tax map or any other maps attached hereto, the Metes and Bounds prevails.**

The Property is identified as portions of Block 24601, Lots 1 through 8 and a portion of Block 21901 Lot 8 on the City of Jersey City tax maps, the Property being presently owned by Bayfront Redevelopment LLC. A copy of the current tax map which includes the general location of the Property is attached as Exhibit A-2.

MASER CONSULTING P.A.
Consulting, Municipal & Environmental Engineers
Planners ▪ Surveyors ▪ Landscape Architects

331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Tel: 732.383.1950 ▪ Fax: 732.383.1984

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**
**PROJECT NO. 10000292Q**

**DEED NOTICE AREA 1**
**SA-6 SOUTH OPEN SPACE AREA**
**LOTS 1 THROUGH 8, BLOCK 24601**
**& LOT 8, BLOCK 21901**
**DECEMBER 4, 2015**
**REVISED: FEBRUARY 2, 2017**

All that certain lot, tract or parcel of land situate lying and being in the City of Jersey, in the County of Hudson and State of New Jersey, and being a portion of Lots 1 through 8, Block 24601 and a portion of Lot 8 Block 21901, designated as Deed Notice Area 1 as shown on an exhibit entitled, "Deed Notice Area 1, SA6 South, Block 24601, Lots 1-8 & Block 21901, Lot 8, City of Jersey City, Hudson County, New Jersey," prepared by Maser Consulting P.A., dated April 6, 2016, revised February 2, 2017 and being more particularly bounded and described as follows, to wit:

**COMMENCING** at the intersection of the westerly line of New Jersey State Highway Route 440, and the division line between Lot 8 Block 21901, and Lot 8 Block 24601; thence-

A. **N 49°06'05" W, 9.97 feet**, along said division line to the intersection of the same with the easterly face of the hydraulic barrier wall, and **True** point of **BEGINNING**, and running; thence-

Running along said easterly hydraulic barrier wall face, the following two (2) courses:

1. **S 26°06'25" W, 122.87 feet,** thence-

2. **S 41°25'15" W, 32.00 feet,** to the southeasterly corner of said hydraulic barrier wall; thence-

Running along the southerly face of said hydraulic barrier wall, the following four (4) courses:

3. **N 49°11'45" W, 460.77 feet,** thence-

4. **N 48°55'10" W, 366.00 feet,** thence -

5. **N 53°42'49" W, 718.00 feet,** thence -

6. **N 53°41'21" W, 737.00 feet,** to the southwesterly corner thereof; thence –

7. **N 45°54'51" E, 157.25 feet,** along the westerly face of said hydraulic barrier wall, to the northwesterly corner thereof; thence-

Running along the northerly face of said hydraulic barrier wall, the following five (5) courses:

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**
**PROJECT NO. 10000292Q**

**DEED NOTICE AREA 1**
**SA-6 SOUTH OPEN SPACE AREA**
**LOTS 1 THROUGH 8, BLOCK 24601**
**& LOT 8, BLOCK 21901**
**DECEMBER 4, 2015**
**REVISED: FEBRUARY 2, 2017**

8. **S 49°21'28" E, 12.20 feet,** thence -

9. **S 53°44'48" E, 647.00 feet,** thence -

10. **S 53°47'16" E, 668.00 feet,** thence –

11. **S 53°59'54" E, 57.20 feet,** thence –

12. **S 51°14'03" E, 54.20 feet,** thence –

13. **S 49°01'05" E, 313.00 feet,** thence-

14. **S 49°10'40" E, 485.50 feet,** to the northeasterly corner thereof; thence-


15. **S 44°21'39" W, 3.70 feet,** along the aforesaid easterly wall face, to the point and place of **BEGINNING**.

**CONTAINING:** 350,023 S.F. of land more or less or 8.035 acres of land more or less.

02/02/17

GLEN J. LLOYD, P.L.S. DATE SIGNED
NEW JERSEY PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS037598

\\HQFAS1\General\Projects\2010\10000292Q\Survey\Description\Metes & Bounds, Deed Notice 1_REV_2-2-17.docx




HACKENSACK RIVER

N 45°34'51" E 157.25'

S 49°21'28" E 12.20'

N 53°41'21" W 737.00'

S 53°44'48" E 647.00'

BLOCK 24601
LOT 1
DB 8442 PG. 1

BLOCK 24601
LOT 2
DB 8902 PG. 221

BLOCK 24601
LOT 3
DB 8231 PG. 60

BLOCK 24601
LOT 4
DB 8231 PG. 60

BLOCK 24601
LOT 11
DB 8711 PG. 802

BLOCK 21901
LOT 8
DB 7452 PG. 62

BLOCK 24601
LOT 5
DB 8231 PG. 60

N 53°42'49" W 718.00'

S 53°47'16" E 668.00'

BLOCK 24601
LOT 6
DB 7345 PG. 1

BLOCK 28102
LOT 21

BLOCK 28102
LOT 1

DEED NOTICE AREA 1
AS-BUILT OPEN SPACE AREA
(HATCH AREA)
AREA=350,023± S.F.
8.035 Ac.

BLOCK 21901
LOT 10
DB 8531 PG. 196

S 53°59'54" E 57.20'

S 51°14'03" E 54.20'

BLOCK 24601
LOT 7
DB 7456 PG. 314

BLOCK 24601
LOT 12

N 45°35'10" W 368.00'

S 49°01'03" E 313.00'

BLOCK 24601
LOT 8
DB 7528 PG. 156

BLOCK 21901
LOTS 5–10 (EXCLUDING BLOCK 6)
& BLOCK 24601
LOTS 1–12

BLOCK 21901
LOT 7
DB 7452 PG. 62

KELLOGG STREET
(80' WIDE R.O.W.)

BLOCK 24601
LOT 10
DB 8637 PG. 640

BLOCK 24601
LOT 9
DB 8637 PG. 640

N 49°11'45" W 480.77'

S 49°10'40" E 485.50'

BLOCK 21901
LOT 5
DB 8642 PG. 118

BLOCK 21901
LOT 6
DB 8642 PG. 118

POINT OF BEGINNING

S 44°21'39" W 3.70'

S 41°25'15" W 32.00'

S 26°06'25" W
122.87'

N 49°08'05" W 8.87'

NEW JERSEY STATE HIGHWAY ROUTE 440
(112' WIDE R.O.W.)

200 160 120 80 40 0 100 200 400

SCALE : 1" = 200'

MASER CONSULTING P.A.

Customer Loyalty *through* Client Satisfaction
www.maserconsulting.com
Engineers ■ Planners ■ Surveyors
Landscape Architects ■ Environmental Scientists
State of N.J. Cert. of Authorization: 24GA27986500

Office Locations:
■ Red Bank, NJ ■ Albany, NY
■ Clinton, NJ ■ Chestnut Ridge, NY
■ Hamilton, NJ ■ Newburgh, NY
■ Marmora, NJ ■ Hawthorne, NY
■ Mt. Arlington, NJ ■ Lehigh Valley, PA
■ Mt. Laurel, NJ ■ Exton, PA
■ Sterling, VA ■ Philadelphia, PA
■ Norfolk, VA ■ Columbia, MD
■ Albuquerque, NM ■ Tampa, FL

Copyright © 2017 Maser Consulting P.A. All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Maser Consulting P.A.

| REV | DATE | DRAWN BY | DESCRIPTION |
|---|---|---|---|
| 1 | 2/9/16 | BSB | REMOVED LOT 7 REFERENCE IN BLOCK 21901 |
| 2. | 4/8/16 | CJK | REVISED BOUNDARY ALONG ROAD FRONTAGE |
| 3 | 2/2/17 | KAN | ADD "DEED NOTICE AREA" |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |

DEED NOTICE AREA 1
SA6 SOUTH

BLOCK 24601,LOTS 1-8 &
BLOCK 21901, LOT 8

CITY OF JERSEY CITY
HUDSON COUNTY
NEW JERSEY

811 PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE
Know what's below. Call before you dig.
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

RED BANK OFFICE
Corporate Headquarters
331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Phone: 732.383.1950
Fax: 732.383.1984


| SCALE: | DATE: | DRAWN BY: | CHECKED BY: |
|---|---|---|---|
| AS SHOWN | 12/4/15 | BSB | GJL |
| PROJECT NUMBER: 2010\1000 | | DRAWING NAME: V-EXBT-DN-1 | |

SHEET TITLE:
DEED NOTICE EXHIBIT

SHEET NUMBER:
1 of 1

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HOBOKEN\JERSEY CITY\SA 6 SOUTH\3480150485.5710\571004\deed notice\deed notice 1\5100\CURRENT DRAWINGS\3480150450-5100-A200-1000.dwg Fri, 10 Mar 2017 - 1:34pm scott.rudkin




**DRAFT**

0 150 300 600

SCALE IN FEET


| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A200-1000 | | **EXHIBIT A-2**<br>TAX MAP<br>BLOCK 24601 LOTS 1-8 &<br>BLOCK 21901 LOT 8<br>DEED NOTICE # 1 SA-6 SOUTH<br>OPEN SPACE AOC PROPERTY<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16 | CHECKED/DATE: NW 01/31/17 | |

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**Exhibit A-3A and A-3B**
**Property Maps**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (i) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (ii) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CAD\HOMEWELL\JERSEY CITY\SA 6 SOUTH\3480150485\5710\5710A\deed notice\deed notice\15100\CURRENT DRAWINGS\3480150450-5100-A300-1000.dwg Fri, 10 Mar 2017 - 1:34pm scott.rudkin




**DRAFT**


0 100 200 400

SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A300-1000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT A-3A**<br>PROPERTY AREA MAP<br>BLOCK 24601 LOTS 1-8 &<br>BLOCK 21901 LOT 8<br>DEED NOTICE # 1 SA-6 SOUTH<br>OPEN SPACE AOC PROPERTY<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16<br>CHECKED/DATE: NW 01/31/17 | | |


UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HOWELL\JERSEY CITY,SA 6 SOUTH\3480150488\5710\5710A\dsed notice\dsed notice 11_5100\CURRENT DRAWINGS\3480150450-5100-A300-1000.dwg Fri, 10 Mar 2017 - 1:34pm sestt.rudkin




LEGEND

| | |
|---|---|
| 24601 | BLOCK NUMBER |
| LOT 8 | LOT NUMBER |
| | BLOCK LINE |
| | LOT LINE |
| | RESTRICTED AREA |




KEY MAP
SCALE 1" = 500'

**DRAFT**

0 100 200 400
SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A300-1000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT A-3B**<br>PROPERTY AREA MAP<br>BLOCK 24601 LOTS 1-8 &<br>BLOCK 21901 LOT 8<br>DEED NOTICE # 1 SA-6 SOUTH<br>OPEN SPACE AOC PROPERTY<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16 | CHECKED/DATE: NW 01/31/17 | |

**EXHIBIT B**
**Deed Notice #1 Property**
**B-1A and B-1B Restricted Area Maps**
**B-2A and B-2B Chromium Remedy Components**
**B-3 Restricted Area Data Table**
**Portions of Block 24601, Lots 1 through 8 and a portion of Block 21901 Lot 8**
**City of Jersey City, New Jersey**

Exhibit B-1 Restricted Area Maps includes Exhibit B-1A and Exhibit B-1B (Restricted Area Soil Sample Locations).

Exhibit B-2 Chromium Remedy Components includes Exhibit B-2A (Chromium Remedy Components), Exhibit B-2B (Cap System Detail), and Exhibit B-2C (As-Built Restoration Plan).

Exhibit B-3 is a Restricted Area Data Table indicating soil sample locations with concentrations of contaminants remaining above the level established in the New Jersey Department of Environmental Protection (NJDEP) Chromium Policy and/or other applicable NJDEP Soil Quality Standards as described below.

**Restricted Area Map Notes:**

Exhibits B-1A and B-1B indicate engineering controls. The engineering controls include (1) underground containment walls, and (2) a capping system consisting of: a warning layer, impervious geo-membrane liner; geo-composite drainage layer; and clean soil cover with minimum 12 inches thickness in areas where pavement is proposed; and an average of 36-inches and a minimum 24-inches thickness in areas where landscaping is proposed.

Exhibit B-2B indicates engineering controls cap system detail.

Exhibits B-1A and B-1B indicate the restricted area for soil containing contaminants of concern, including hexavalent chromium above 20 milligrams per kilogram (mg/kg) pursuant to the Chromium Policy, total xylenes above the NJDEP Residential Direct Contact Soil Remediation Standard (RDCSRS) of 12,000 mg/kg, and soils that are consistent with NJDEP's definition of "historic fill material" found at N.J.A.C. 7:26E-1.8, as shown on Exhibit B-3.


Analytical results and soil borings indicate that historic fill is present onsite and extends over the entire Restricted Area. Historic fill onsite typically consists of the following: metals, PAHs, and miscellaneous debris (including but not limited to coal fragments, brick, timber, and other construction materials).

A table summarizing maximum concentrations of typical contaminants found in the historic fill material in the Restricted Area is included as Exhibit B-3.

**Exhibit B-1A and B-1B**
**Restricted Area Maps**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\57100\dwg\ notice\dwg\ notice\deed notice 1\5100\CURRENT DRAWINGS\3480150450-5100-B100-1000.dwg Fri, 10 Mar 2017 - 1:34pm scott.rodkin




KEY MAP
SCALE 1" = 500'


**DRAFT**

0 100 200 400
SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150450<br>*DRAWING:* 3480150450-5100-B100-1000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 |
| *PREPARED/DATE:* STR 01/28/16 · *CHECKED/DATE:* NW 01/31/17 | **EXHIBIT B-1A**<br>RESTRICTED AREA MAP<br>BLOCK 24601 LOTS 1-8 &<br>BLOCK 21901 LOT 8<br>DEED NOTICE # 1 SA-6 SOUTH<br>OPEN SPACE AOC PROPERTY<br>JERSEY CITY, NEW JERSEY |

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CANDY HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150450\5710\5710A\deed notice\deed notice 1\5100\CURRENT DRAWINGS\3480150450-5100-B100-1000.dwg Fri, 10 Mar 2017 - 1:42pm scott.nalin




KEY MAP
SCALE 1" = 500'

**DRAFT**

0 100 200 400
SCALE IN FEET

| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-B100-1000 | |
| PREPARED/DATE: STR 01/28/16 | CHECKED/DATE: NW 01/31/17 |

amec foster wheeler


ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT B-1B**
RESTRICTED AREA MAP
BLOCK 24601 LOTS 1-8 &
BLOCK 21901 LOT 8
DEED NOTICE # 1 SA-6 SOUTH
OPEN SPACE AOC PROPERTY
JERSEY CITY, NEW JERSEY

**Exhibits B-2A, B-2B and B-2C**
**Chromium Remedy Components, Cap System Details, and As-Built Restoration Plan**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT, (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND REPORTS THAT IS CONFIDENTIAL, AND MAY NOT BE COPIED OR DISCLOSED, AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS PREPARED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\dead notice\dead notice 1\5100\CURRENT DRAWINGS\3480150438-5710-CPCS-1000.dwg Fri, 10 Mar 2017 - 1:35pm




## CHROMIUM REMEDY COMPONENTS

NTS


**DRAFT**

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150488<br>*DRAWING:* 3480150438-5710-CPCS-1000 | |
| *PREPARED/DATE:* STR 03/10/16 | *CHECKED/DATE:* DEN 03/10/16 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT B-2A**
CHROMIUM REMEDY COMPONENTS
BLOCK 24601 LOTS 1-8 &
BLOCK 21901 LOT 8
DEED NOTICE #1 SA-6 SOUTH
OPEN SPACE AOC PROPERTY
JERSEY CITY, NEW JERSEY





## CAP SYSTEM DETAIL

NTS

**DRAFT**


| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150468<br>DRAWING: 3480150436-5710-CSD0-1000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE, Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 |
| PREPARED/DATE: STR 03/10/16 \| CHECKED/DATE: DEN 01/31/17 | EXHIBIT B-2B<br>CAP SYSTEM DETAIL<br>BLOCK 24601 LOTS 1-8 &<br>BLOCK 21901 LOT 8<br>DEED NOTICE # 1 SA-6 SOUTH<br>OPEN SPACE AOC<br>JERSEY CITY, NEW JERSEY |

W:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150468\5710\5710\dwg\deed notice\deed notice 11x17(D) CURRENT DRAWINGS\3480150436-5710-CSD0-1000.dwg Wed, 01 Feb 2017 - 3:




NOTE:

1. REFER TO FIGURE 2 FOR CONSTRUCTION CONTROL GRID AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE ON THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL AS SHOWN ON THE TYPICAL VEGETATED SLOPE DETAIL. THE VEGETATED SLOPE ALONG SA–7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. EXISTING PAVEMENT WAS FIELD INSPECTED BY LSRP AND SUBJECT TO MINOR CRACK FILLING TO SATISFY HISTORIC FILL CAP REQUIREMENTS.
4. STEEL SHEETPILE WALL WAS INSTALLED AS EXCAVATION SUPPORT ALONG THIS AREA AND THEN CUT BELOW CURRENT GRADE AND LEFT IN PLACE. THE TOP OF SHEETPILE IS GENERALLY 0.5 TO 2.0 FT BELOW CURRENT GRADES.




NOTE: NO HISTORIC FILL SHALL BE PLACED ON SA–7

TYPICAL VEGETATED SLOPE
NTS

EXHIBIT B-2C

STONE COVER
VEGETATED COVER
PAVEMENT COVER
CONCRETE COVER
STONE COVER IN PLANTER AREAS
RIPARIAN ZONE
DGA COVER
STONE TOE DRAIN
STEEL SHEETPILE WALL
STORM DRAIN PIPE
STORM DRAIN CATCH BASIN

0 80 160 FEET
SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: AS BUILT RESTORATION PLAN SA–6 SOUTH – SHEET 001 12/12/16

PROJECT NAME & LOCATION: HONEYWELL SA–6 REMEDIATION JERSEY CITY, NJ

**Exhibit B-3: Table B-3**
**Soil Sample Data Table**

**EXHIBIT B-3**

**RESTRICTED AREA DATA TABLE**

Deed Notice #1 SA-6 South Open Space AOC Property

Portions of Block 24601 Lots 1-8 a portion of Block 21901 Lot 8

Jersey City, New Jersey

| Location ID | Sample Date | Start Depth (feet bgs) | End Depth (feet bgs) | Sample Depth (feet bgs) | Sample Elevation (NAVD88) | Northing | Easting | Hexavalent Chromium | Q |
|---|---|---|---|---|---|---|---|---|---|
| 073-SB-001 | 07/14/2008 | 4.5 | 5 | 4.5 - 5 | -0.52 | 685535.00 | 601464.00 | 63.7 | J |
| 073-SB-001 | 07/14/2008 | 9 | 9.5 | 9 - 9.5 | -5.02 | 685535.00 | 601464.00 | 100 | J |
| 073-SB-001 | 07/14/2008 | 11.5 | 12 | 11.5 - 12 | -7.52 | 685535.00 | 601464.00 | 63.3 | J |
| 073-SB-001 | 07/14/2008 | 13 | 13.5 | 13 - 13.5 | -9.02 | 685535.00 | 601464.00 | 296 | J |
| 073-SB-005 | 07/31/2008 | 2.5 | 3 | 2.5 - 3 | 4.36 | 685448.00 | 601552.00 | 26.3 | |
| 073-SB-005 | 07/31/2008 | 5.5 | 6 | 5.5 - 6 | 1.36 | 685448.00 | 601552.00 | 2190 | |
| 073-SB-012 | 07/31/2008 | 3 | 3.5 | 3 - 3.5 | 5.15 | 685545.00 | 601613.00 | 420 | |
| 073-SB-012 | 07/31/2008 | 4 | 4.5 | 4 - 4.5 | 4.15 | 685545.00 | 601613.00 | 6360 | |
| 073-SB-013 | 07/31/2008 | 4.5 | 5 | 4.5 - 5 | 2.82 | 685464.00 | 601613.00 | 237 | |
| 073-SB-014 | 08/01/2008 | 0.5 | 1 | 0.5 - 1 | 6.54 | 685392.00 | 601661.00 | 37.2 | |
| 073-SB-014 | 08/01/2008 | 2 | 2.5 | 2 - 2.5 | 5.04 | 685392.00 | 601661.00 | 201 | |
| 073-SB-014 | 08/01/2008 | 4.5 | 5 | 4.5 - 5 | 2.54 | 685392.00 | 601661.00 | 54.2 | |
| 073-SB-015 | 08/01/2008 | 4.5 | 5 | 4.5 - 5 | 4.29 | 685427.00 | 601758.00 | 142 | |
| 073-SB-326 | 04/16/2010 | 1 | 1.5 | 1 - 1.5 | 5.86 | 685436.222855 | 601589.102771 | * | |
| 073-SB-AA12 | 07/28/1997 | 0 | 2 | 0 - 2 | 8.47 | 685572.70 | 601602.30 | 99.6 | J |
| 073-SB-AA12 | 07/28/1997 | 4 | 6 | 4 - 6 | 4.47 | 685572.70 | 601602.30 | 1720 | J |
| 073-SB-AA12 | 07/28/1997 | 6 | 8 | 6 - 8 | 2.47 | 685572.70 | 601602.30 | 8140 | J |
| 073-SB-AA12 | 07/28/1997 | 8 | 10 | 8 - 10 | 0.47 | 685572.70 | 601602.30 | 5030 | J |
| 073-SB-AA12 | 07/28/1997 | 10 | 12 | 10 - 12 | -1.53 | 685572.70 | 601602.30 | 287 | J |
| 073-SB-AA12 | 07/28/1997 | 12 | 14 | 12 - 14 | -3.53 | 685572.70 | 601602.30 | 1830 | J |
| 073-SB-AA12 | 07/28/1997 | 14 | 16 | 14 - 16 | -5.53 | 685572.70 | 601602.30 | 469 | J |
| 073-SB-AA12 | 07/28/1997 | 18 | 20 | 18 - 20 | -9.53 | 685572.70 | 601602.30 | 578 | J |
| 073-SB-AA12 | 07/28/1997 | 20 | 22 | 20 - 22 | -11.53 | 685572.70 | 601602.30 | 25.3 | J |
| 073-SB-X11 | 07/28/1997 | 0 | 2 | 0 - 2 | 8.55 | 685415.77 | 601752.10 | 24.1 | J |
| 073-SB-X11 | 07/28/1997 | 4 | 6 | 4 - 6 | 4.55 | 685415.77 | 601752.10 | 394 | J |
| 073-SB-X11 | 07/28/1997 | 6 | 8 | 6 - 8 | 2.55 | 685415.77 | 601752.10 | 8830 | J |
| 073-SB-X11 | 07/28/1997 | 8 | 10 | 8 - 10 | 0.55 | 685415.77 | 601752.10 | 4580 | J |
| 073-SB-X11 | 07/28/1997 | 10 | 12 | 10 - 12 | -1.45 | 685415.77 | 601752.10 | 222 | J |
| 073-SB-X11 | 07/28/1997 | 20 | 22 | 20 - 22 | -11.45 | 685415.77 | 601752.10 | 118 | J |
| 073-SB-Y10 | 07/29/1997 | 0 | 2 | 0 - 2 | 7.03 | 685387.55 | 601665.39 | 21.4 | J |
| 073-SB-Y10 | 07/29/1997 | 2 | 4 | 2 - 4 | 5.03 | 685387.55 | 601665.39 | 202 | J |
| 073-SB-Y10 | 07/29/1997 | 4 | 6 | 4 - 6 | 3.03 | 685387.55 | 601665.39 | 371 | J |
| 073-SB-Y10 | 07/29/1997 | 6 | 8 | 6 - 8 | 1.03 | 685387.55 | 601665.39 | 92.4 | J |
| 073-SB-Y10 | 07/29/1997 | 8 | 10 | 8 - 10 | -0.97 | 685387.55 | 601665.39 | 70.6 | J |
| 073-SB-Y10 | 07/29/1997 | 14 | 16 | 14 - 16 | -6.97 | 685387.55 | 601665.39 | 89.7 | J |
| 073-SB-Z11 | 07/28/1997 | 0 | 2 | 0 - 2 | 7.56 | 685471.66 | 601639.93 | 20.3 | |
| 073-SB-Z11 | 07/28/1997 | 4 | 6 | 4 - 6 | 3.56 | 685471.66 | 601639.93 | 51.1 | |
| 073-SB-Z11 | 07/28/1997 | 6 | 8 | 6 - 8 | 1.56 | 685471.66 | 601639.93 | 3740 | |
| 073-SB-Z11 | 07/28/1997 | 8 | 10 | 8 - 10 | -0.44 | 685471.66 | 601639.93 | 227 | |
| 073-SB-Z11 | 07/28/1997 | 16 | 18 | 16 - 18 | -8.44 | 685471.66 | 601639.93 | 156 | |
| 124-PT-07 | 03/12/2008 | 6 | 8 | 6 - 8 | 4 | 684534.00 | 602838.00 | 2420 | |
| 124-PT-07 | 03/12/2008 | 8 | 10 | 8 - 10 | 2 | 684534.00 | 602838.00 | 554 | J |
| 124-PT-07 | 03/12/2008 | 10 | 12 | 10 - 12 | 0 | 684534.00 | 602838.00 | 4740 | |
| 124-PT-08 | 03/13/2008 | 10 | 12 | 10 - 12 | 0 | 684570.00 | 602873.00 | 2470 | |
| 124-PT-10 | 03/14/2008 | 10 | 12 | 10 - 12 | 1 | 684520.00 | 602925.00 | 4420 | |
| 124-PT-10 | 03/14/2008 | 12 | 14 | 12 - 14 | -1 | 684520.00 | 602925.00 | 3320 | |
| 124-PT-11 | 03/14/2008 | 8 | 10 | 8 - 10 | 2.99 | 684483.00 | 602890.00 | 7190 | |
| 124-PT-11 | 03/14/2008 | 10 | 12 | 10 - 12 | 0.99 | 684483.00 | 602890.00 | 103 | |
| 124-SB-B05 | 05/08/1997 | 0 | 2 | 0 - 2 | 10.63 | 684244.29 | 603222.22 | 3210 | J |
| 124-SB-B05 | 05/08/1997 | 2 | 4 | 2 - 4 | 8.63 | 684244.29 | 603222.22 | 9970 | J |
| 124-SB-B05 | 05/08/1997 | 4 | 6 | 4 - 6 | 6.63 | 684244.29 | 603222.22 | 7460 | J |
| 124-SB-B05 | 05/08/1997 | 6 | 8 | 6 - 8 | 4.63 | 684244.29 | 603222.22 | 6980 | J |
| 124-SB-B05 | 05/08/1997 | 8 | 10 | 8 - 10 | 2.63 | 684244.29 | 603222.22 | 5160 | J |
| 124-SB-B05 | 05/08/1997 | 12 | 14 | 12 - 14 | -1.37 | 684244.29 | 603222.22 | 49 | J |
| 124-SB-D05 | 05/07/1997 | 0 | 2 | 0 - 2 | 10 | 684310.89 | 603076.37 | 9350 | |
| 124-SB-D05 | 05/07/1997 | 2 | 4 | 2 - 4 | 8 | 684310.89 | 603076.37 | 7450 | |
| 124-SB-D05 | 05/07/1997 | 4 | 6 | 4 - 6 | 6 | 684310.89 | 603076.37 | 8430 | |
| 124-SB-D05 | 05/07/1997 | 6 | 8 | 6 - 8 | 4 | 684310.89 | 603076.37 | 8350 | |
| 124-SB-D05 | 05/07/1997 | 8 | 10 | 8 - 10 | 2 | 684310.89 | 603076.37 | 9020 | |
| 124-SB-D05 | 05/07/1997 | 10 | 12 | 10 - 12 | 0 | 684310.89 | 603076.37 | 9560 | |
| 124-SB-E06 | 05/07/1997 | 0 | 2 | 0 - 2 | 10 | 684416.69 | 603037.14 | 213 | |
| 124-SB-E06 | 11/16/1998 | 2 | 4 | 2 - 4 | 8 | 684416.69 | 603037.14 | 15300 | J |
| 124-SB-E06 | 05/07/1997 | 4 | 6 | 4 - 6 | 6 | 684416.69 | 603037.14 | 6870 | |
| 124-SB-E06 | 05/07/1997 | 6 | 8 | 6 - 8 | 4 | 684416.69 | 603037.14 | 8600 | |
| 124-SB-E06 | 05/07/1997 | 8 | 10 | 8 - 10 | 2 | 684416.69 | 603037.14 | 7910 | |
| 124-SB-E06 | 05/07/1997 | 10 | 12 | 10 - 12 | 0 | 684416.69 | 603037.14 | 7780 | |
| 124-SB-E06 | 05/07/1997 | 16 | 18 | 16 - 18 | -6 | 684416.69 | 603037.14 | 2660 | |
| 124-SB-F07 | 05/07/1997 | 0 | 2 | 0 - 2 | 12.39 | 684521.78 | 602997.96 | 68.6 | J |
| 124-SB-F07 | 05/07/1997 | 2 | 4 | 2 - 4 | 10.39 | 684521.78 | 602997.96 | 6900 | J |
| 124-SB-F07 | 05/07/1997 | 4 | 6 | 4 - 6 | 8.39 | 684521.78 | 602997.96 | 3120 | J |
| 124-SB-F07 | 05/07/1997 | 6 | 8 | 6 - 8 | 6.39 | 684521.78 | 602997.96 | 3510 | J |

**EXHIBIT B-3**

**RESTRICTED AREA DATA TABLE**

Deed Notice #1 SA-6 South Open Space AOC Property

Portions of Block 24601 Lots 1-8 a portion of Block 21901 Lot 8

Jersey City, New Jersey

| Location ID | Sample Date | Start Depth (feet bgs) | End Depth (feet bgs) | Sample Depth (feet bgs) | Sample Elevation (NAVD88) | Northing | Easting | Hexavalent Chromium | Q |
|---|---|---|---|---|---|---|---|---|---|
| 124-SB-F07 | 05/07/1997 | 8 | 10 | 8 - 10 | 4.39 | 684521.78 | 602997.96 | 2480 | J |
| 124-SB-F07 | 05/07/1997 | 10 | 12 | 10 - 12 | 2.39 | 684521.78 | 602997.96 | 1350 | |
| 125-PT-18 | 04/16/2008 | 6.5 | 7 | 6.5 - 7 | 2.87 | 684593.00 | 602747.00 | 8740 | |
| 125-PT-19 | 04/16/2008 | 6 | 6.5 | 6 - 6.5 | 3.74 | 684641.00 | 602793.00 | 5270 | J |
| 125-PT-19 | 04/16/2008 | 8.5 | 9 | 8.5 - 9 | 1.24 | 684641.00 | 602793.00 | 24.1 | J |
| 125-PT-19 | 04/16/2008 | 10.5 | 11 | 10.5 - 11 | -0.76 | 684641.00 | 602793.00 | 5190 | J |
| 125-PT-23 | 04/17/2008 | 6.5 | 7 | 6.5 - 7 | 2.5 | 684563.00 | 602783.00 | 10600 | J |
| 125-PT-23 | 04/17/2008 | 9 | 9.5 | 9 - 9.5 | 0 | 684563.00 | 602783.00 | 86.6 | J |
| 125-PT-23 | 04/17/2008 | 11 | 11.5 | 11 - 11.5 | -2 | 684563.00 | 602783.00 | 2270 | J |
| 125-PT-24 | 04/17/2008 | 6 | 6.5 | 6 - 6.5 | 3.59 | 684611.00 | 602830.00 | 7260 | J |
| 125-PT-24 | 04/17/2008 | 10.5 | 11 | 10.5 - 11 | -0.91 | 684611.00 | 602830.00 | 4530 | |
| 125-SB-001 | 06/16/2005 | 11.5 | 12 | 11.5 - 12 | -1.49 | 684704.00 | 602680.00 | 6800 | |
| 125-SB-011 | 07/30/2008 | 1.5 | 2 | 1.5 - 2 | 8.51 | 684711.00 | 602569.00 | 31.1 | |
| 125-SB-011 | 07/30/2008 | 3 | 3.5 | 3 - 3.5 | 7.01 | 684711.00 | 602569.00 | 4460 | |
| 125-SB-011 | 07/30/2008 | 5.5 | 6 | 5.5 - 6 | 4.51 | 684711.00 | 602569.00 | 7860 | |
| 125-SB-I08 | 07/30/1997 | 0 | 2 | 0 - 2 | 12 | 684700.57 | 602787.09 | 52.1 | J |
| 125-SB-I08 | 07/30/1997 | 2 | 4 | 2 - 4 | 10 | 684700.57 | 602787.09 | 297 | |
| 125-SB-I08 | 07/30/1997 | 4 | 6 | 4 - 6 | 8 | 684700.57 | 602787.09 | 7550 | |
| 125-SB-I08 | 07/30/1997 | 6 | 8 | 6 - 8 | 6 | 684700.57 | 602787.09 | 6760 | |
| 125-SB-I08 | 07/30/1997 | 10 | 12 | 10 - 12 | 2 | 684700.57 | 602787.09 | 247 | |
| 125-SB-K08 | 07/30/1997 | 6 | 8 | 6 - 8 | 4 | 684743.16 | 602654.14 | 419 | |
| 125-SB-K08 | 07/30/1997 | 10 | 12 | 10 - 12 | 0 | 684743.16 | 602654.14 | 8170 | J |
| 125-SB-L07 | 11/16/1998 | 2 | 4 | 2 - 4 | 7.64 | 684697.16 | 602569.04 | 7140 | J |
| 125-SB-L07 | 07/30/1997 | 8 | 10 | 8 - 10 | 1.64 | 684697.16 | 602569.04 | 208 | |
| 125-SB-L07 | 07/30/1997 | 10 | 12 | 10 - 12 | -0.36 | 684697.16 | 602569.04 | 93.4 | |
| 134-SB-001 | 06/17/2005 | 15.5 | 16 | 15.5 - 16 | -5.81 | 685100.00 | 602217.00 | 5490 | |
| 134-SB-002 | 06/17/2005 | 3.5 | 4 | 3.5 - 4 | 4.58 | 685421.00 | 601802.00 | 9810 | |
| 134-SB-002 | 06/17/2005 | 6.5 | 7 | 6.5 - 7 | 1.58 | 685421.00 | 601802.00 | 10700 | |
| 134-SB-002 | 06/17/2005 | 10.5 | 11 | 10.5 - 11 | -2.42 | 685421.00 | 601802.00 | 23.2 | |
| 134-SB-035 | 06/24/2008 | 4 | 4.5 | 4 - 4.5 | 3.36 | 685351.00 | 601787.00 | 32.8 | |
| 134-SB-036 | 06/24/2008 | 2.5 | 3 | 2.5 - 3 | 5.5 | 685328.00 | 601925.00 | 4100 | |
| 134-SB-036 | 06/24/2008 | 4 | 4.5 | 4 - 4.5 | 4 | 685328.00 | 601925.00 | 10500 | |
| 134-SB-038 | 06/20/2008 | 2.5 | 3 | 2.5 - 3 | 6.5 | 685185.00 | 602106.00 | 1650 | |
| 134-SB-038 | 06/20/2008 | 5.5 | 6 | 5.5 - 6 | 3.5 | 685185.00 | 602106.00 | 3090 | |
| 134-SB-039 | 06/24/2008 | 3 | 3.5 | 3 - 3.5 | 6 | 685114.00 | 602136.00 | 4770 | |
| 134-SB-039 | 06/24/2008 | 5 | 5.5 | 5 - 5.5 | 4 | 685114.00 | 602136.00 | 6080 | |
| 134-SB-040 | 06/20/2008 | 1.5 | 2 | 1.5 - 2 | 7.5 | 685076.00 | 602204.00 | 4210 | |
| 134-SB-040 | 06/20/2008 | 3 | 3.5 | 3 - 3.5 | 6 | 685076.00 | 602204.00 | 8200 | |
| 134-SB-R09 | 11/18/1998 | 0 | 2 | 0 - 2 | 9 | 685087.33 | 602195.84 | 6970 | J |
| 134-SB-R09 | 05/29/1997 | 2 | 4 | 2 - 4 | 7 | 685087.33 | 602195.84 | 73.7 | J |
| 134-SB-R09 | 05/29/1997 | 4 | 6 | 4 - 6 | 5 | 685087.33 | 602195.84 | 289 | J |
| 134-SB-R09 | 05/29/1997 | 10 | 12 | 10 - 12 | -1 | 685087.33 | 602195.84 | 247 | J |
| 134-SB-S10 | 05/29/1997 | 6 | 8 | 6 - 8 | 3 | 685191.70 | 602116.15 | 9540 | J |
| 134-SB-S10 | 05/29/1997 | 10 | 12 | 10 - 12 | -1 | 685191.70 | 602116.15 | 425 | J |
| 134-SB-T09 | 05/29/1997 | 2 | 4 | 2 - 4 | 6.91 | 685148.41 | 602008.19 | 8350 | J |
| 134-SB-T09 | 05/29/1997 | 4 | 6 | 4 - 6 | 4.91 | 685148.41 | 602008.19 | 547 | J |
| 134-SB-T09 | 05/29/1997 | 6 | 8 | 6 - 8 | 2.91 | 685148.41 | 602008.19 | 342 | J |
| 134-SB-T09 | 05/29/1997 | 8 | 10 | 8 - 10 | 0.91 | 685148.41 | 602008.19 | 181 | J |
| 134-SB-T09 | 05/29/1997 | 10 | 12 | 10 - 12 | -1.09 | 685148.41 | 602008.19 | 58.9 | J |
| 134-SB-T09 | 05/29/1997 | 14 | 16 | 14 - 16 | -5.09 | 685148.41 | 602008.19 | 25.3 | J |
| 134-SB-U10 | 05/29/1997 | 4 | 6 | 4 - 6 | 4.4 | 685238.85 | 601960.33 | 427 | J |
| 134-SB-U10 | 05/29/1997 | 6 | 8 | 6 - 8 | 2.4 | 685238.85 | 601960.33 | 3820 | J |
| 134-SB-U10 | 05/29/1997 | 8 | 10 | 8 - 10 | 0.4 | 685238.85 | 601960.33 | 393 | J |
| 134-SB-U10 | 05/29/1997 | 10 | 12 | 10 - 12 | -1.6 | 685238.85 | 601960.33 | 157 | J |
| 134-SB-V11 | 06/03/1997 | 8 | 10 | 8 - 10 | 0 | 685338.22 | 601910.84 | 856 | J |
| 134-SB-V11 | 06/03/1997 | 4 | 6 | 4 - 6 | 4 | 685338.22 | 601910.84 | 9770 | J |
| 140-SB-001 | 06/20/2005 | 18 | 18.5 | 18 - 18.5 | -9 | 684806.00 | 602505.00 | 81.4 | J |
| 140-SB-002 | 06/20/2005 | 11.5 | 12 | 11.5 - 12 | 1.28 | 684930.00 | 602390.00 | 9810 | J |
| 140-SB-002 | 06/20/2005 | 15.5 | 16 | 15.5 - 16 | -2.72 | 684930.00 | 602390.00 | 248 | J |
| 140-SB-021 | 07/30/2008 | 5 | 5.5 | 5 - 5.5 | 6.53 | 684875.00 | 602366.00 | 42.6 | J |
| 140-SB-023 | 07/30/2008 | 1.5 | 2 | 1.5 - 2 | 8.61 | 684921.00 | 602468.00 | 295 | J |
| 140-SB-023 | 07/30/2008 | 2.5 | 3 | 2.5 - 3 | 7.61 | 684921.00 | 602468.00 | 337 | |
| 140-SB-023 | 07/30/2008 | 5 | 5.5 | 5 - 5.5 | 5.11 | 684921.00 | 602468.00 | 79.2 | J |
| 140-SB-M08 | 08/22/1997 | 2 | 4 | 2 - 4 | 7 | 684811.01 | 602509.83 | 40.1 | J |
| 140-SB-M08 | 08/22/1997 | 4 | 6 | 4 - 6 | 5 | 684811.01 | 602509.83 | 1070 | J |
| 140-SB-M08 | 08/22/1997 | 6 | 8 | 6 - 8 | 3 | 684811.01 | 602509.83 | 3890 | J |
| 140-SB-M08 | 08/22/1997 | 8 | 10 | 8 - 10 | 1 | 684811.01 | 602509.83 | 27.7 | J |
| 140-SB-M08 | 08/22/1997 | 10 | 12 | 10 - 12 | -1 | 684811.01 | 602509.83 | 382 | J |
| 140-SB-M08 | 08/22/1997 | 12 | 14 | 12 - 14 | -3 | 684811.01 | 602509.83 | 1040 | J |
| 140-SB-M08 | 08/22/1997 | 14 | 16 | 14 - 16 | -5 | 684811.01 | 602509.83 | 347 | J |
| 140-SB-N09 | 08/21/1997 | 0 | 2 | 0 - 2 | 10.52 | 684932.12 | 602464.54 | 49.1 | |

**EXHIBIT B-3**

**RESTRICTED AREA DATA TABLE**

Deed Notice #1 SA-6 South Open Space AOC Property

Portions of Block 24601 Lots 1-8 a portion of Block 21901 Lot 8

Jersey City, New Jersey

| Location ID | Sample Date | Start Depth (feet bgs) | End Depth (feet bgs) | Sample Depth (feet bgs) | Sample Elevation (NAVD88) | Northing | Easting | Hexavalent Chromium | Q |
|---|---|---|---|---|---|---|---|---|---|
| 140-SB-N09 | 08/21/1997 | 4 | 6 | 4 - 6 | 6.52 | 684932.12 | 602464.54 | 227 | |
| 140-SB-N09 | 08/21/1997 | 6 | 8 | 6 - 8 | 4.52 | 684932.12 | 602464.54 | 9930 | |
| 140-SB-N09 | 08/21/1997 | 10 | 12 | 10 - 12 | 0.52 | 684932.12 | 602464.54 | 7610 | |
| 140-SB-N09 | 08/21/1997 | 14 | 16 | 14 - 16 | -3.48 | 684932.12 | 602464.54 | 2920 | |
| 140-SB-P09 | 08/21/1997 | 10 | 12 | 10 - 12 | 0 | 684990.54 | 602300.01 | 91.9 | |
| 140-SB-P09 | 08/21/1997 | 14 | 16 | 14 - 16 | -4 | 684990.54 | 602300.01 | 113 | |
| 140-SB-P09 | 08/21/1997 | 6 | 8 | 6 - 8 | 4 | 684990.54 | 602300.01 | 6030 | |

**Notes:**

Results reported in mg/kg.

* Soil sample 073-SB-326 <20 mg/kg for hexavalent chromium; total xylenes detected at 33,900 mg/kg.

**Q -Data Qualifiers:**

J - Data indicates the presence of a compound that meets the identification criteria. The concentration given is an approximate value.

**Abbreviations:**

Feet bgs - Feet below ground surface

mg/kg - milligrams per kilogram

NAVD88 - North American Vertical Datum of 1988

NJDEP Chromium SCC - New Jersey Department of Environmental Protection Chromium Soil Cleanup Criteria, revised April 2010

NJDEP RDC - New Jersey Department of Environmental Protection Residential Direct Contact Soil Standard, revised 2012

| Contaminant | CAS No. | NJDEP RDC (mg/kg) |
|---|---|---|
| Hexavalent Chromium | 18540-29-9 | 20 |
| Total Xylenes | 1330-20-7 | 12000 |

**EXHIBIT B-3**

RESTRICTED AREA DATA TABLE-HISTORIC FILL

Deed Notice #1 SA-6 South Open Space AOC Property

Portions of Block 24601 Lots 1-8 a portion of Block 21901 Lot 8

Jersey City, New Jersey

| Compound>RDC | RDC | # of Samples >RDC | Maximum Conc. |
|---|---|---|---|
| **ANTIMONY** | **31** | 1 | 32.5 |
| **ARSENIC** | **19** | 1 | 126 |
| **BENZO(A)ANTHRACENE** | **5** | 12 | 9.2 |
| **BENZO(A)PYRENE** | **0.5** | 18 | 7.2 |
| **BENZO(B)FLUORANTHENE** | **5** | 12 | 7.1 |
| **DIBENZO(A,H)ANTHRACENE** | **0.5** | 8 | 1.73 |
| **LEAD** | **400** | 2 | 508 |
| **NAPHTHALENE** | **6** | 5 | 100 |
| **VANADIUM** | **78** | 15 | 1120 |

Notes:

RDC: NJDEP Residential Direct Contact Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].

CONC: Concentration reported in milligrams per kilogram (mg/kg)

Historic fill is present throughout the Site consisting of PAH and metals.

R or N: Rejected or negated by laboratory or data validator

**EXHIBIT C**
**Deed Notice #1 Property**

**C-1 Institutional Controls**
**C-2 Engineering Controls**
**Portions of Block 24601, Lots 1 through 8 and a Portion of Block 21901 Lot 8 City of Jersey City, New Jersey**

## C-1 Institutional Controls

C-1 Deed Notice, Consent Decree, Zoning, and Conservation Restriction as Institutional Controls: Exhibit C-1 (A through D) for that portion of Block 24601, Lots 1 through 8 and Block 21901 Lot 8, City of Jersey City, New Jersey known as the Property.

Exhibits C-1A through D. Exhibit C-1A: Deed Notice as Institutional Control; Exhibit C-1B: Consent Decree as Institutional Control (attached); Exhibit C-1C: Zoning as Institutional Control; Exhibit C-1D: Conservation Restriction as Institutional Control (recorded at the Office of Hudson County Register as indicated in Paragraph 3): Exhibits C-1A through C-1D include a narrative description of the restrictions and obligations of this Deed Notice and the other Institutional Controls that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
**The Property encompasses approximately 8 acres. The horizontal extent of the Property includes an existing soil-cement bentonite (SCB) wall along the northern boundary of the Property with SA-7 and the hydraulic barrier walls installed on the other three sides as part of the Chromium Remedy. The engineered barrier covering the contamination in the Property consists of an engineered Resource Conservation and Recovery Act (RCRA) cap that includes a gas collection system, base protective layer, geomembrane liner, geocomposite drainage layer, filter fabric, warning layer, and cover soils. The Property includes chromium, xylenes and historic fill. Honeywell has restricted the future use of this area by implementing a conservation restriction, which has been recorded at the Office of the Hudson County Register, and Honeywell will transfer, or cause Bayfront Redevelopment LLC to transfer, title to Jersey City (as called for in Paragraph 61(c)(ii)(3) of the Consent Decree). The provisions of the LTMP and the OSDS, developed pursuant to the Consent Decree, will apply to the Property.**

(1) Description and estimated size of the Restricted Areas as described above;

***The Property constitutes portions of Block 24601, Lots 1 through and 8 and a portion of Block 21901 Lot 8. The estimated size of the Property containing chromium-impacted soils (hexavalent chromium above 20 mg/kg) as identified on Exhibit B-1 is estimated at approximately 8 acres.***

(2) Description of the restrictions on the Property by operation of the Institutional Control;

***The Property shall only be used for activities consistent with this Deed Notice, the Consent Decree, including, but not limited to, Paragraphs 74(j) and 74 (k) of the Consent Decree, the applicable zoning standards, and the Conservation Restriction. Intrusive activities (i.e., excavation or digging) that breach the engineering controls (as described in Exhibit C-2) will not be permitted on the Property except in compliance with the terms of the Consent Decree and the LTMP developed thereunder, and this Deed Notice. See subsections 7A Alterations, Improvements, Disturbances, and 7B, Emergencies for additional information. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950.***

(3) The objective of the restrictions;

***The restrictions will prohibit contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg, soils containing xylenes above the NJDEP RDCSRS of 12,000 mg/kg for xylenes, and soils that are historic fill.***

(B) Description of the monitoring necessary to determine whether:

(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;

***Visual inspections of the Property and other monitoring as set forth in the Consent Decree and LTMP established thereunder.***

(2) There have been any land use changes subsequent to the filing of this Deed Notice or the most recent biennial certification, whichever is more recent;

***Same as (B)(1*).**

(3) The current land use on the Property is consistent with the restrictions in this Deed Notice;

***Same as (B)(1).***

(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the site; and

***Review of newly promulgated or modified requirements of applicable regulations or laws that potentially may apply to the Property.***

(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***Same as (B)(4).***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) Land use at the Property is consistent with the restrictions in the Consent Decree, this Deed Notice, the OSDS, the applicable zoning standards and the Conservation Restriction; and

(3) The remedial action that includes this Deed Notice continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including evaluation of any available documents as a result of changes in land use or incidents.***
- ***A report that determines whether or not the land use at the Property has remained consistent with the restrictions in the Consent Decree, this Deed Notice, the OSDS, the applicable zoning standards and the Conservation Restriction.***
- ***A report that determines whether or not the Deed Notice continues to be protective of the public health and safety and the environment.***

**C-2 Engineering Controls**
**Portion of Block 24601, Lots 1 through 8 and Block 21901 Lot 8**
**City of Jersey City, New Jersey**

Exhibits C-2A through C: Narrative description of the Engineering Controls including (A) the Clean Fill and Soil Capping System; (B) Underground Containment Walls; (C) Shallow Groundwater Collection and Treatment System as follows:

(A) General Description of the engineering controls:

(1) Description of the engineering controls;

***The Engineering Controls consist of the following: (A) a capping system consisting of: a root barrier, a warning layer, impervious geo-membrane liner; geo-composite drainage layer; and clean soil cover with minimum 12 inches thickness in areas where pavement is proposed; and an average of 36-inches and a minimum 24-inches thickness in areas where landscaping is proposed. For the purposes of this deed notice, the engineering controls exclude cover soils that are within 12 inches of the root barrier. (B) Engineering controls will also include underground containment walls around the perimeter of the Property. The Engineering Controls are more fully set forth in the Consent Decree. (C) Engineering controls will also include a system of wells, sumps, french drains, or other collection trenches and associated piping for the collection and treatment of shallow groundwater from the Property.***

(2) The objective of the engineering controls; and

***The objective of the controls is to prevent contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg, soils containing xylenes above the NJDEP RDCSRS of 12,000 mg/kg, and soils that are historic fill material, and to contain shallow groundwater above the NJDEP groundwater quality standard for total chromium.***

(3) How the engineering controls are intended to function.

***The soil engineering controls are intended to function as a barrier to underlying and adjacent impacted soils as defined above. The groundwater engineering controls are intended to restrict the flow of shallow groundwater, and to collect and treat contaminated groundwater within the Property. Monitoring requirements for the engineering controls are set forth in the LTMP.***

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

***Honeywell will perform monitoring by visual inspection of the Property pursuant to the Consent Decree. Other monitoring activities shall be performed as set forth in the LTMP developed pursuant to the Consent Decree.***

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

***Same as (B)(1) above.***

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering controls;

***Same as (B)(1) above. Also, see the Consent Decree and the Deed Notice for additional information: subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies.***

(4) The engineering controls are being inspected and maintained and their integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

***Same as (B)(1) above.***

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering controls. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering controls; and

***Records of the inspections are to be maintained as listed in (5). Should the activities carried out in conformance with the LTMP developed pursuant to the Consent Decree indicate that other activities are necessary, those activities will be listed and executed.***

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***A review of any new standards, regulations, or laws will be conducted. Should the review indicate that other activities are necessary, those activities will be listed and executed.***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering controls continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including an evaluation to determine whether or not the engineering controls are continuing to meet the original objective and intended function.***
- ***A report to determine whether or not the engineering controls continue to operate as designed.***
- ***A report to determine whether or not the engineering controls continue to be protective of the public health and safety and of the environment.***

**Appendix I**
**Consent Decree**

# APPENDIX I

UNITED STATES DISTRICT COURT
DISTRICT OF NEW JERSEY

| | |
|---|---|
| JERSEY CITY MUNICIPAL UTILITIES AUTHORITY,<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Docket No. 05-5955(DMC)<br>Consolidated under Docket No. 95-2097 (DMC) |
| JERSEY CITY INCINERATOR AUTHORITY<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Civil Action No. 05-5993<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 (DMC) |
| HACKENSACK RIVERKEEPER, INC., *et al.*<br><br>Plaintiffs,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC., *et al.*<br><br>Defendants. | Civil Action No. 06-22<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 |

**FIRST AMENDED CONSENT DECREE REGARDING REMEDIATION AND REDEVELOPMENT OF STUDY AREA 6 SOUTH**

# TABLE OF CONTENTS

**RECITALS** ..... 1

**ARTICLE I: DEFINITIONS** ..... 4

**ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED** ..... 11

**ARTICLE III: CHROMIUM REMEDIATION** ..... 12

A. GENERAL TERMS AND REQUIREMENTS ..... 12
50. Responsibility for Implementation of Chromium Remediation. ..... 12
51. Designation of Chromium Areas of Concern. ..... 12
52. Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan. ..... 12
53. General Scope of the Chromium Remedy. ..... 13
54. Development of a Schedule for the Chromium Remedy. ..... 13
B. INITIAL CHROMIUM REMEDY STEPS: DELINEATION, TREATMENT STUDY, AND REMEDIAL ACTION WORK PLAN ..... 15
55. Delineation of Development AOC. ..... 15
56. Conduct of a Treatment Study in the Development AOC . ..... 15
57. Continued Monitoring of the Treatment Study. ..... 16
58. Submission of a Remedial Action Work Plan. ..... 16
C. DEVELOPMENT AOC SOIL REMEDY ..... 16
59. Remedial Components ..... 16
60. Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium ..... 17
61. Treatment as a Remedial Component for 20 to 240 Soils ..... 18
62. Submissions Related to Site 163 ..... 20
63. Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium. ..... 20
64. Post-Treatment Monitoring for 20 to 1000 Soils ..... 21
D. OPEN SPACE AOC COMPONENTS OF THE CHROMIUM REMEDY ..... 21
65. Open Space AOC Soil Remedy ..... 21
E. DEMOLITION, GRADING, AND BACKFILL REQUIREMENTS ..... 23
66. Demolition and Grading Activities. ..... 23
67. Backfill Requirements. ..... 23
68. Vegetation of Clean Fill. ..... 23
F. GROUNDWATER COMPONENTS OF THE CHROMIUM REMEDY ..... 23
69. Shallow Groundwater Remedy for the Open Space AOC ..... 23
70. The Shallow Groundwater Remedy for the Development AOC. ..... 24
71. Off-Site Shallow Groundwater Remedy. ..... 25
72. L-Well Groundwater Remedy. ..... 26
G. PERMITS AND AUTHORIZATIONS ..... 26
73. Permits and Authorizations. ..... 26
H. LONG-TERM MONITORING, MAINTENANCE, AND PROTECTION OF ENGINEERING AND INSTITUTIONAL CONTROLS ..... 27

74. Protection of the Open Space AOC ..... 27
75. Honeywell's Ongoing Responsibility. ..... 39
76. Long-Term Monitoring Plan. ..... 39
77. Long-Term Monitoring Plan Objectives ..... 39
78. Monitoring and Remediation Under the Long-Term Monitoring Plan ..... 40
79. Monitoring and Reporting to Riverkeeper. ..... 44
80. Notice to Stakeholders ..... 44
81. Annual Letter to Riverkeeper on Notice to Stakeholders ..... 45
82. Future Notice to Stakeholders ..... 45
83. Stakeholder Enforcement. ..... 46
I. OVERSIGHT AND ENFORCEMENT BY THE SPECIAL MASTER AND NJDEP ..... 46
84. Federal Court Jurisdiction ..... 46
85. Appointment and Jurisdiction of the Special Master. ..... 46
86. Oversight of the Chromium Remedy. ..... 46
87. Retention of Professionals. ..... 53
88. Insurance for the Special Master. ..... 53
89. Reimbursement of Special Master Fees and Expenses. ..... 54
90. Expiration of Special Master's Appointment. ..... 54
J. INITIAL FINANCIAL ASSURANCES ..... 55
91. Chromium Remedy Letter of Credit ..... 55
92. Procedures for Review of the Proposed Chromium Remedy Letter of Credit ..... 56
93. Automatic Renewal. ..... 56
94. Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit ..... 57
95. Bankruptcy Protection. ..... 58
96. Exclusive Court Jurisdiction. ..... 58
97. Application of New York Law. ..... 59
98. Procedures upon Honeywell's Material Default of Its Obligations ..... 59
99. Placement of Proceeds in Court Registry Investment System Account. ..... 60
100. Termination of Chromium Remedy Letter of Credit ..... 61
K. LONG-TERM FINANCIAL ASSURANCES ..... 61
101. Long-Term Financial Assurances. ..... 61
102. Costs Subject to Long-Term Financial Assurances. ..... 61
103. Long-Term Financial Assurance Mechanisms ..... 62
104. Procedures for Review of the Proposed Long-Term Financial Assurances ..... 66
105. Temporary Maintenance of Chromium Remedy Letter of Credit. ..... 66
106. Adjustment of Amount Held in Long-Term Financial Assurances. ..... 67
107. Exclusive Court Jurisdiction. ..... 68
108. Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired: ..... 68
109. Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default ..... 69
110. Use of the Trust Fund in the Event of Honeywell's Default. ..... 70
111. Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109. ..... 70
112. Termination of the Long-Term Financial Assurances. ..... 70

**ARTICLE IV: TERMINATION** ..... 71

113. Termination of this Consent Decree ..... 71
114. Procedures for Withdrawal and Termination. ..... 72
115. Good-Faith Obligation to Avoid Termination ..... 72
116. Effect of Termination. ..... 72

**ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC** ..... 72

117. Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC. ..... 72

**ARTICLE VI: NOTICE** ..... 73

118. Notice ..... 73
119. Payment of Past Fees and Expenses ..... 74
120. Future Fees and Expenses. ..... 75

**ARTICLE VIII: MISCELLANEOUS PROVISIONS** ..... 76

121. Force Majeure. ..... 76
122. Bayfront Redevelopment LLC as a Party. ..... 76
123. Successors and Assigns. ..... 77
124. Successors to Hackensack Riverkeeper, Inc.. ..... 77
125. Reservation of Rights and Claims. ..... 77
126. Governing Law and Continuing Jurisdiction. ..... 77
127. Construction. ..... 78
128. Authority to Enter into Agreement. ..... 78
129. Measures to Effectuate This Consent Decree ..... 78
130. Modifications. ..... 78
131. Severability. ..... 78
132. Signatures. ..... 79

## RECITALS

**Whereas,** on June 30, 2003, the district court for the District of New Jersey (hereafter "the Court") issued a Final Judgment in *Interfaith Community Organization v. Honeywell International Inc.*, Civ. No. 95-2097 (DMC) (*"ICO v. Honeywell"*), ordering the remediation of an area designated by the New Jersey Department of Environmental Protection ("NJDEP") as Study Area 7 by excavation of all chromium contamination on the property, under the oversight of a court-appointed Special Master;

**Whereas**, on or about December 23, 2005, the Jersey City Municipal Utilities Authority ("JCMUA") filed litigation styled *Jersey City Municipal Utilities Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5955 (DMC), bringing claims against Honeywell International Inc. ("Honeywell") under, *inter alia*, Section 6972 of the Resource Conservation and Recovery Act ("RCRA"), and seeking remediation of chromium contamination on property then-owned by JCMUA and other relief;

**Whereas**, on or about December 28, 2005, the Jersey City Incinerator Authority ("JCIA") filed litigation styled *Jersey City Incinerator Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5993 (DMC), bringing claims against Honeywell under, *inter alia*, Section 6972 of RCRA, and seeking remediation of chromium contamination on property then-owned by JCIA and other relief;

**Whereas**, on or about January 4, 2006, the Hackensack Riverkeeper, Inc., Captain William Sheehan, Reverend Winston Clarke, and Lawrence Baker ("Riverkeeper") filed litigation styled *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.,* D.N.J., Civ. No. 06-022 (DMC), bringing a claim against Honeywell under RCRA and seeking remediation of chromium contamination to soils, groundwater, surface waters, and sediments associated with

various properties collectively designated by NJDEP as Study Areas 5, 6 North, which includes the properties formerly owned by JCMUA and JCIA, and 6 South;

**Whereas,** Study Areas 6 North and South are directly adjacent to Study Area 7 on the north and south sides, respectively;

**Whereas,** Study Area 5 is comprised of properties to the east of Study Areas 6 North, 6 South, and 7 across Route 440;

**Whereas,** Riverkeeper also named as defendants in *Riverkeeper v. Honeywell* owners of the properties comprising Study Areas 5, 6 South, and 6 North;

**Whereas,** *JCMUA v. Honeywell*, *JCIA v. Honeywell,* and *Riverkeeper v. Honeywell* were consolidated by the Court (hereinafter the "Consolidated Litigation");

**Whereas,** in the Consolidated Litigation, Riverkeeper has alleged that Honeywell bears responsibility for the presence and remediation of chromite ore processing residue ("COPR") and chromium in soils and groundwater on the Study Area 6 South property;

**Whereas,** on April 21, 2008, the Court entered the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North (hereafter "the Study Area 6 North Consent Decree") resolving issues between Honeywell, Riverkeeper, and the Jersey City Entities related to chromium contamination at Study Area 6 North;

**Whereas**, on April 21, 2008, the district court for the District of New Jersey entered the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. (hereafter "Jersey City/Honeywell Consent Order"), filed in the Consolidated Litigation simultaneously with the Study Area 6 North Decree, which resolved claims and cross-claims between Honeywell and the Jersey City Entities;

**Whereas**, on May 28, 2008, the Court entered the Consent Order on Sediment Remediation and Financial Assurances ("Sediment Consent Order"), resolving issues related to the remediation of chromium contaminated sediments in the Hackensack River in the vicinity of Study Areas 5, 6, and 7;

**Whereas**, on September 3, 2008, the Court entered the Deep Overburden and Bedrock Groundwater Remedies Consent Order (hereafter "the Deep Groundwater Consent Order") resolving all issues related to the remediation of deep overburden and bedrock groundwater in both *ICO v. Honeywell* and the Consolidated Litigation;

**Whereas,** on May 13, 2011, Plaintiffs sent Honeywell a RCRA citizen action suit notice letter with respect to Site 163, and the Parties agree that the incorporation of Site 163 into this Consent Decree resolves any claims asserted, or that could have been asserted, in the RCRA notice letter or in any RCRA citizen suit with respect to Site 163;

**Whereas**, the Parties to this Consent Decree each believe that it is in their mutual interest to move forward productively to resolve their differences so that they can implement environmental remediation at Study Area 6 South that ensures the continued protection of human health and the environment and so that Study Area 6 and Study Area 7 can be redeveloped in keeping with Jersey City's vision for a revitalized West Side;

**Whereas,** the Local Redevelopment and Housing Law, N.J.S.A. 40A:12A-1, *et seq.*, as amended and supplemented (the "Redevelopment Law") provides for municipalities to participate in the redevelopment and improvement of areas in need of redevelopment;

**Whereas**, Study Area 6 and Study Area 7 consist of parcels which by ordinance adopted by the City Council of Jersey City on February 27, 2008, have been determined to be "areas in

need of redevelopment" under the criteria of the Redevelopment Law because of conditions prevalent on those parcels;

**Whereas**, the settlement which is the subject matter of this Consent Decree contemplates the environmental remediation of Study Area 6 South and redevelopment of the parcels that comprise Study Areas 6 and 7 to create a major mixed use project in an important section of Jersey City; and

**Whereas**, each of the actions to implement this Consent Decree have been fully considered by the Honeywell, the Riverkeeper, and Jersey City as a means to accomplish the aforesaid purposes of this settlement:

NOW, THEREFORE, IT IS HEREBY ORDERED AND DECREED AS FOLLOWS:

## ARTICLE I: DEFINITIONS

For purposes of this Consent Decree, the following terms shall have the meanings set forth in this Article:

1. **"20 to 1000 Soils"** shall mean those soils containing less than 1000 mg/kg of hexavalent chromium, but greater than 20 mg/kg. **"20 to 240 Soils"** shall mean those soils containing less than 240 mg/kg of hexavalent chromium, but greater than 20 mg/kg.

2. **Bayfront Redevelopment LLC** shall have the meaning set forth in paragraph 4.1 of the Jersey City/Honeywell Consent Order.

3. **COPR** shall mean Chromite Ore Processing Residue.

4. **Chromium Remedy or Chromium Remediation** shall mean the remedy set forth in Article III.

5. **Consolidated Litigation** shall mean *Jersey City Municipal Utility Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5955 (DMC), *Jersey City Incinerator*

*Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5993 (DMC), and *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-022 (DMC).

6. The **Court** shall mean the United States District Court of the District of New Jersey, which has jurisdiction over the Consolidated Litigation.

7. **Deep Groundwater Consent Order** shall mean the Deep Overburden and Bedrock Groundwater Remedies Consent Order entered by the Court on September 3, 2008, in both *ICO v. Honeywell* and the Consolidated Litigation.

8. **Deep Groundwater Remedy** shall mean the deep overburden and bedrock groundwater pump and treat remedy as required by the Order Approving the Deep Overburden Groundwater Remediation, entered on October 6, 2006, the Stipulation on Consent Regarding the Schedule for Implementation of Deep Groundwater Remedial Actions, entered on August 15, 2008, in *ICO v. Honeywell,* and the remedies required under the Deep Groundwater Consent Order.

9. **Development Area of Concern** ("AOC") shall mean those portions of Study Area 6 South in which the hexavalent chromium concentration in the top 20 feet of soil below ground surfaces exceeds a concentration of 20 mg/kg, and for which future uses of the property may include commercial or residential development. The Open Space AOC shall not be part of the Development AOC and vice versa. The Development AOC consists of two parts: the Kellogg Street Development AOC and the Site 163 Development AOC. Collectively, the two parts shall be referred to as the "Development AOC." The approximate boundaries of the Development AOC as a whole and its two parts are shown on Exhibit A, but the boundaries may be further defined in the implementation of the Chromium Remedy. For the Kellogg Street Development AOC, remedial measures shall assume only a residential use. For the Site 163 Development AOC, remedial measures shall be implemented with the goal of unrestricted use, but limitations

on future uses (including prohibiting residential use) in some or all of the Site 163 Development AOC may be part of the remedy as set forth in paragraph 61.

10. **Hackensack River Watershed Land Trust** shall mean the dedicated fund of the Hackensack Riverkeeper, Inc., established under Section 501(c) of the Internal Revenue Code for the purpose of acquiring and preserving open space within the Hackensack River watershed and administered by the Board of Trustees of the Hackensack Riverkeeper, Inc.

11. **Honeywell** shall mean Honeywell International Inc. and its affiliates, including 425-445 Route 440 Property LLC, Kellogg Street 80 Property LLC, Kellogg Street 60 Property LLC, and Kellogg Street/440 Property LLC.

12. **Honeywell's Treatment Plant** shall mean the treatment plant currently located at 80 Kellogg Street that is used to treat, *inter alia*, chromium contaminated groundwater.

13. ***ICO v. Honeywell*** shall mean *Interfaith Community Organization v. Honeywell International Inc.*, D.N.J., Civ. No. 95-2097 (DMC).

14. **Including** shall mean including, but not limited to.

15. **JCIA** shall mean the Jersey City Incinerator Authority.

16. **JCMUA** shall mean the Jersey City Municipal Utilities Authority.

17. **Jersey City Entities** shall mean the City of Jersey City, including the Department of Public Works ("DPW") and other agencies and branches thereof, the JCIA, and the JCMUA.

18. **Jersey City/Honeywell Consent Order** shall mean the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. entered in the Consolidated Litigation on April 21, 2008.

19. **"L-Well Groundwater"** shall mean the groundwater found at the depth of the "L" wells on and near the former bowling alley property, NJDEP Site 124, located at 427 Route 440. The L-Well Groundwater is located within what has been referred to as the plume diversion area.

20. **NJDEP** shall mean the New Jersey Department of Environmental Protection.

21. **NJDEP Chromium Directive** shall mean the Chromium Directive issued by NJDEP on February 8, 2007, and attached as Exhibit B.

22. **Open Space AOC** shall mean the portion of Study Area 6 South that is identified as The Promenade park and Grand Boulevard extending from Route 440 to the Hackensack River on page 39 of the Redevelopment Plan and for which the future uses of the property shall be restricted pursuant to paragraph 74, following remediation pursuant to paragraph 65. The Development AOC shall not be part of the Open Space AOC and vice versa. The approximate boundaries of the Open Space AOC are shown on Exhibit A, and the boundaries may be further defined in the implementation of the Chromium Remedy.

23. **Party or Parties** shall mean any one or all of the signatories to this Consent Decree.

24. **RCRA** shall mean the Resource Conservation and Recovery Act, 42 U.S.C. § 6901, *et seq.*, as amended.

25. **Redevelopment Area** shall mean Study Area 6 North, Study Area 6 South, and Study Area 7, collectively.

26. **Redevelopment Law** shall mean the New Jersey Local Redevelopment and Housing Law, N.J.S.A. § 40A:12A1, *et seq.*, as amended and supplemented.

27. **Redevelopment Plan** shall mean the Bayfront I Redevelopment Plan as adopted by Jersey City on March 12, 2008.

28. **Remedial Investigation Work Plan Addendum or RIWP Addendum** shall mean the "Remedial Investigation Work Plan Addendum Study Area 6 South" submitted to NJDEP on June 27, 2008.

29. **Riverkeeper** shall mean the plaintiffs in *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-22 (DMC), and includes the Hackensack Riverkeeper, Inc., William Sheehan, Reverend Winston Clarke, and Lawrence Baker.

30. **Sediment Consent Order** shall mean the Consent Order on Sediment Remediation and Financial Assurances, entered by the Court in *ICO v. Honeywell* and this Consolidated Litigation on May 28, 2008.

31. **Shallow Groundwater** or **Shallow Level of Groundwater** shall mean groundwater above the meadow mat, groundwater at stratigraphically equivalent depths in locations where there is no meadow mat, and groundwater that is contaminated by recent contact with COPR or other chromium soil contamination above the meadow mat and subsequently flows downward through or past the meadow mat into the upper portion of the lacustrine sediments. This does not include groundwater found in the bedrock, the deep zone, or any plume of contamination that is in both the intermediate and deep zones, as those zones are defined in the Final Groundwater Investigation Report, prepared in *ICO v. Honeywell*, dated February 2007, p. 1-2.

32. **Site** shall mean Study Area 6 South.

33. **Site Preparation Activities** shall mean those activities necessary to begin implementation of the Chromium Remedy in Article III of this Consent Decree, including, if appropriate, the temporary or permanent relocation of current activities and operations conducted on Study Area 6 South.

34. **Soil** shall mean soils, historic fill, and/or COPR.

35. The **Special Master** shall mean Senator Robert G. Torricelli, appointed as the Special Master in *ICO v. Honeywell* and the Consolidated Litigation, and his successors or whomever the Court may appoint as Special Master.

36. **Stratum O** shall mean the layer composed of soft brown silty fine sand interlayered with soft gray silty clay and fine sandy to clayey silt generally located above the meadow mat below the Historic Fill and/or COPR.

37. **Study Area 5** shall mean that property comprising Sites 79, 90, 117, 153, and 184 of the Chromate Chemical Production Waste Sites designated by NJDEP, comprising approximately 42 acres and including (a) all such property owned by Bob Ciasulli consisting of Block 1291, Lot 76, and Block 1292, Lots 1F, 47, 48, 53, and 54PL, located at 540 Route 440, Jersey City, New Jersey, (b) all such property owned by Elisabeth and Rafael Rosario consisting of Block 1292, Lot 49, located at 93 Fisk Street, Jersey City, New Jersey, (c) all such property owned by Michael Vo consisting of Block 1292, Lot 50, located at 95 Fisk Street, Jersey City, New Jersey, (d) all such property owned by NJCU consisting of Block 1286, Lots 5 and 6D and Block 1286.5, Lots 1 and 2, Jersey City, New Jersey, (e) all such property owned by Inland Southeast Jersey City LLC consisting of Lot 1, Block 1285.5 located at 440 Route 440, Jersey City, New Jersey, and (f) all such property owned by 425/445 Route 440 Property LLC, consisting of Block 1289.5, Lot E, Jersey City, New Jersey.

38. **Study Area 6 North** shall mean the property comprising Sites 87 and 88 of the Chromate Chemical Production Waste Sites designated by NJDEP, which is subject to the Study Area 6 North Consent Decree.

39. **Study Area 6 North Consent Decree** shall mean the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North, entered by the Court on April 21, 2008, in the Consolidated Litigation.

40. **Study Area 6 South** shall mean (a) that property currently owned by Bayfront Redevelopment Property LLC consisting of Site 73, located at 200 Kellogg Street Jersey City, Hudson County, New Jersey; (b) that property currently owned by Bayfront Redevelopment LLC consisting of Site 134, located at 100 Kellogg Street Jersey City, Hudson County, New Jersey; (c) that property currently owned by Bayfront Redevelopment LLC consisting of Site 140 located at 80 Kellogg Street Jersey City, Hudson County, New Jersey; (d) that property currently owned by Bayfront Redevelopment LLC consisting of Site 125, located at 60 Kellogg Street Jersey City, Hudson County, New Jersey; (e) that property currently owned by Bayfront Redevelopment LLC consisting of Site 124, Jersey City, Hudson County, New Jersey; (f) that property currently owned by Kellogg St/Harsimus Cove Realty located at 150 Kellogg Street, Jersey City, Hudson County, New Jersey, (g) that property currently owned by Bayfront Redevelopment LLC located at 38 Kellogg Street, Jersey City, Hudson County, New Jersey; (h) that property currently owned by Bayfront Redevelopment LLC located at 28 Kellogg Street, Jersey City, Hudson County, New Jersey; and (i) that property currently owned by Bayfront Redevelopment LLC, consisting of Site 163, formerly the Colonial Concrete Company, located at 75 Kellogg Street in Jersey City, Hudson County, New Jersey.

41. **Study Area 6** shall mean Study Area 6 North and Study Area 6 South, collectively.

42. **Study Area 7** shall mean (a) that property currently owned by Bayfront Redevelopment LLC located at 425 and 445 Route 440, Jersey City, Hudson County, New Jersey, and (b) that

property currently owned by Bayfront Redevelopment LLC located at 465 Route 440, Jersey City, Hudson County, New Jersey.

43. **Technical Requirements for Site Remediation** shall mean the NJDEP Technical Requirements for Site Remediation, N.J.A.C. Chapter 26E, as duly and properly promulgated and amended.

44. **Unrestricted Use** shall mean that the contaminated medium is restored to a condition or quality suitable for all uses.

## ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED

45. This Court has jurisdiction over the Parties and subject matter of the Consolidated Litigation pursuant to Section 6972 of RCRA.

46. For purposes of this Consent Decree, the Riverkeeper Complaint in the Consolidated Litigation states claims upon which relief may be granted against Honeywell.

47. In the event that this Decree is not terminated by one or more Parties pursuant to paragraph 113, this Consent Decree resolves, settles, and satisfies all claims by Riverkeeper against Honeywell with respect to soils, shallow groundwater and L-Well groundwater at Study Area 6 South. This Consent Decree does not resolve any claims by Riverkeeper against Honeywell with respect to Study Area 5 or property owned by Regnal Realty consisting of Block 1288.2, lot 1, located at 420 Route 440, Jersey City, New Jersey.

48. Nothing in this Consent Decree shall be construed or interpreted to waive any claim or defense any Party has asserted or may assert against any third party in the Consolidated Litigation except as explicitly stated herein.

49. This Consent Decree does not constitute an admission of liability on the part of any Party with respect to any claims, cross-claims, or counter-claims in the Consolidated Litigation.

## ARTICLE III: CHROMIUM REMEDIATION

### A. General Terms and Requirements

50. **Responsibility for Implementation of Chromium Remediation.** As between the Parties, Honeywell shall be responsible for and shall undertake remediation of COPR and chromium present in Study Area 6 South at Honeywell's sole cost and expense. Remediation of COPR and chromium present in Study Area 6 South shall be undertaken in accordance with the terms of this Consent Decree.

51. **Designation of Chromium Areas of Concern.** For the purposes of remediation, Study Area 6 South shall consist of two AOC's, designated as the Open Space AOC and the Development AOC as shown approximately on Exhibit A. The exact boundaries of the two AOC's shall be subject to further delineation during the design and implementation of the Chromium Remedy.

52. **Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan.** The Chromium Remedy shall be consistent with the NJDEP Technical Requirements for Site Remediation, the Chromium Directive as issued by NJDEP on February 8, 2007 ("the NJDEP Chromium Directive"), and any Remedial Action Work Plan, including any modifications or addenda approved by NJDEP. Prior to submitting any Remedial Action Work Plan, Honeywell shall take all reasonable steps to ensure that the plan is consistent with the Chromium Remedy. However, this Consent Decree shall have precedence over any Remedial Action Work Plan in the event of any inconsistency. The approved Remedial Action Work Plan is a minimum standard, and the Chromium Remedy may be more protective than the remedy NJDEP approves.

53. **General Scope of the Chromium Remedy.** The Chromium Remedy shall address shallow groundwater and L-Well groundwater containing total chromium concentrations of 70 µg/l or greater and soil containing hexavalent chromium at concentrations of 20 mg/kg or greater within the top 20 feet of soil below the ground surface, and shall be consistent with the requirements set forth in this Article. The Chromium Remedy set forth in this Consent Decree addresses only the shallow and L-Well levels of groundwater (see paragraphs 69 - 72). The deep overburden and bedrock groundwater remediation, including source control, is addressed in the Deep Groundwater Consent Order.

54. **Development of a Schedule for the Chromium Remedy.** The Chromium Remedy shall be carried out diligently, and the development and implementation of any remedy required by NJDEP for non-chromium contamination shall not delay satisfaction of the milestones in the Schedule established pursuant to this paragraph. Within 90 days of entry of this Consent Decree, Honeywell shall propose a Master Schedule for the implementation of the Chromium Remedy .

(a) The Master Schedule shall incorporate the following dates:

(i) No later than August 15, 2008, Honeywell shall submit a Chromium Impacted Soils Pilot Test Work Plan to NJDEP and Riverkeeper;

(ii) No later than September 15, 2008, Honeywell shall complete field work in accordance with the RIWP Addendum;

(iii)No later than December 31, 2008, Honeywell shall submit an Initial Treatment Study Report and Remedial Action Work Plan pursuant to paragraph 86(c);

(iv) No later than July 31, 2012, Honeywell shall submit the soil and groundwater data from its 2010 and 2011 supplemental investigation of Site 163, a brief summary report, and

a designation of the boundaries of the Site 163 Development AOC to the Special Master pursuant to paragraph 86(c);

(v) No later than October 1, 2012, Honeywell shall submit an addendum to the Study Area 6 South 100% Design setting forth the 100% Design for the Site 163 Development AOC portion of the Study Area 6 South Chromium Remedy; and

(vi) Honeywell shall undertake, in good faith, to begin implementation of the Chromium Remedy by March 1, 2013.

(b) In addition, the Master Schedule shall propose deadlines for the following milestones:

(i) Submission of all documents subject to submission and review pursuant to paragraph 86(c);

(ii) Completion of those Site Preparation Activities necessary for the implementation of the Chromium Remedy;

(iii)Submission, following implementation of the soil components of the Chromium Remedy for the Development AOC, of the groundwater plans and reports required by paragraphs 70 and 72;

(iv)Completion of additional sampling for shallow groundwater delineation pursuant to paragraph 71 and a proposal for a remedy pursuant to paragraph 71, if needed;

(v) The submission of a 50% Design Report for the Chromium Remedy;

(vi) The submission of a 100% Design Report for the Chromium Remedy;

(vii) The date for completion of the installation of the Chromium Remedy;

(viii)Implementation of the long-term protections of the Open Space AOC established pursuant to paragraph 74; and

(ix) Transfer of the Open Space AOC to Jersey City pursuant to paragraph 74(a)(iii).

### B. Initial Chromium Remedy Steps: Delineation, Treatment Study, and Remedial Action Work Plan

55. **Delineation of Development AOC.** Honeywell shall conduct further soil sampling on Study Area 6 South in accordance with the RIWP Addendum. In addition to the locations set forth in the RIWP Addendum, Honeywell shall conduct further soil sampling pursuant to the provisions of the RIWP Addendum at the boring locations set forth in Exhibit E. Upon completion of the soil sampling required by this paragraph, Honeywell shall submit a Second Supplemental Remedial Investigation Report that sets forth the results of the sampling and Honeywell's proposal as to the delineation of the Development AOC. In conjunction with its proposal, Honeywell shall set forth its rationale as to whether prior sampling data should be included or excluded in the proposed delineation. The soil sampling and submission of a Second Supplemental Remedial Investigation Report shall be completed in accordance with the Schedule set forth in paragraph 54. Honeywell shall submit the Second Supplemental Remedial Investigation Report pursuant to paragraph 86(c). The Site 163 Development AOC shall be exempt from the requirements of paragraphs 55-58.

56. **Conduct of a Treatment Study in the Development AOC.** Honeywell shall conduct a field study of the efficacy of *in situ* treatment of 20 to 1000 Soils in accordance with the Chromium Impacted Soil Pilot Test Work Plan. The purpose of the pilot test shall be to evaluate whether *in situ* chemical treatment of 20 to 1000 Soils with one or more reductants can result in the permanent establishment of hexavalent chromium concentrations below 20 mg/kg under conditions in those areas of the Development AOC that may be subject to treatment as a remedy. Honeywell shall provide the raw data from the pilot test to NJDEP and Riverkeeper in scientifically useable electronic form as soon as the data become available. Honeywell shall

submit an Initial Treatment Study Report setting forth the initial results of the pilot test pursuant to paragraph 86(c) .

57. **Continued Monitoring of the Treatment Study.** As the result of the need to complete Study Area 7 remediation, to maintain Study Area 7 remediation support operations currently located on Study Area 6 South, and to conduct Site Preparation activities including the relocation of operating businesses on Study Area 6 South in advance of implementation of the Chromium Remedy, the Parties do not anticipate that implementation of field work for the Chromium Remedy will begin until March 1, 2013. Honeywell shall continue to monitor the performance of the pilot test and shall submit a Final Treatment Study Monitoring Report assessing the long term effectiveness of treatment for 20 to 1000 Soils in the Development AOC pursuant to paragraph 86(c) no later than December 31, 2011.

58. **Submission of a Remedial Action Work Plan.** On or before December 31, 2008, Honeywell shall submit a Remedial Action Work Plan for the Chromium Remedy pursuant to paragraph 86(c). The Remedial Action Work Plan shall be consistent with the Chromium Remedy set forth in this Consent Decree.

### C. Development AOC Soil Remedy

59. **Remedial Components.** In the Development AOC, soils containing hexavalent chromium at concentrations greater than 20 mg/kg shall be remediated as follows:

(a) Soils with a concentration greater than 1000 mg/kg shall be:

(i) Excavated and disposed of off-site at a waste disposal facility licensed to accept such waste; or

(ii) Treated *ex situ* and consolidated under the cap in the Open Space AOC provided the requirements of paragraphs 60 and 63 are satisfied and provided that such soils do not

require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a).

(b) 20 to 1000 Soils shall be:

(i) Excavated and consolidated within the Open Space AOC provided that such soils do not require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a); or

(ii) Excavated and disposed of off-site pursuant to the requirements of paragraph 59(a); or

(iii) Remediated pursuant to paragraphs 59(c) or 59(d) provided that such soils are also 20 to 240 soils and meet the requirements of paragraphs 59(c) or 59(d).

(c) 20 to 240 Soils may be remediated by excavation and consolidation within the Study Area 6 North AOC 1 Open Space Area, provided that such soils do not require venting of gases and shall not serve as the basis for the inclusion of gas venting as part of the Study Area 6 North AOC 1 Open Space Area remedy.

(d) 20 to 240 Soils within the Site 163 Development AOC may be remediated by *in situ* treatment, provided the requirements of paragraph 61 are satisfied.

60. **Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** *Ex situ* treatment and consolidation under the Open Space AOC cap may be used as a remedial component for soils containing greater than 1000 mg/kg hexavalent chromium provided that the requirements of this paragraph are satisfied:

(a) Honeywell demonstrates in the Final Treatment Study Monitoring Report that the proposed treatment will likely result in the reduction of the hexavalent chromium concentration of the treated soils such that the post-treatment total chromium concentration shown by Toxicity

Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C);

(b) Following a review of the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d), NJDEP agrees that Honeywell has made the demonstration required by paragraph 60(a).

(c) Plaintiffs have had an opportunity to review and comment on the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d)and pursuant to the Special Master review process set forth in paragraphs 86(e)-86(f); and

(d) Following review of the demonstration required by paragraph 60(a) pursuant to the Special Master review process set forth in paragraph 86(f), the Special Master issues a recommendation finding that Honeywell has made the demonstration required by paragraph 60(a) or the Court finds that Honeywell has made the demonstration required by paragraph 60(a) in the event that any Party seeks the Court's review of the Special Master's recommendations under this paragraph.

61. **Treatment as a Remedial Component for 20 to 240 Soils.** *In situ* treatment may be used as a remedial component for the 20 to 240 Soils in the Site 163 Development ACO, provided that such soils are 3 feet or more below ground surface and the requirements of this paragraph are satisfied:

(a) If Honeywell elects to treat *in situ* 20 to 240 Soils in the Site 163 Development AOC, Honeywell shall include in the 100% Design Addendum for Site 163 a plan for such treatment. Such treatment plan shall be comparable in detail and approach to the pipeline treatability plan which is Appendix F to the Study Area 6 North 100% Design. The goal of such *in situ* treatment

shall be to reduce hexavalent chromium soil concentrations to less than 20 mg/kg in soils 20 feet or less below ground surface;

(b) Three years after conducting the treatment set forth in subparagraph (a), Honeywell shall collect additional soil samples in the treated areas to evaluate the success of the treatment. These soil samples shall be analyzed for EH, pH, hexavalent chromium (using EPA/NJDEP Methods 3060A/7199), and sulfides (using EPA Method 9030B). Within 60 days of its receipt of the final data from such sampling, Honeywell shall submit a report with such data to the Special Master pursuant to paragraph 86(c);

(c) In the event that the sampling pursuant to subparagraph (b) shows that soils with greater than 20 mg/kg hexavalent chromium remain or that excess treatment reductant remains present, Honeywell may elect to pursue one or more of the following approaches after providing notice to the Special Master, Riverkeeper and the Jersey City Entities;

(i) In the case of excess treatment reductant remaining in the soil, continue to monitor such areas pursuant to subparagraph (b) until the excess reductant is no longer present;

(ii) In the case of soils with greater than 20 mg/kg hexavalent chromium:

(1) Excavate such soils and consolidate them under the cap in the Open Space AOC, consolidate them under the cap in the Study Area 6 North AOC 1 Open Space Area, and/or dispose of them off-site provided that in each instance the applicable requirements of paragraph 59 are satisfied;

(2) Conduct further *in situ* treatment using additional treatment reductant and submit a monitoring plan pursuant to paragraph 64; or

(3) In the event that the soils are within the areas depicted as River Front Park, Riverfront Drive or Kellogg Street on page 39 of the Redevelopment Plan, cover the affected

soils with a road, walkway, and/or other hardscape and restrict the use of that area through each of the following institutional controls:

(a) Issuance and recording of a conservation restriction comparable to that required under paragraphs 74(b) and 74(d);

(b) Transfer of title to that area to Jersey City pursuant to paragraphs 74(a)(iii) through 74(a)(iv)(2); and

(c) Issuance and recording of a deed notice comparable to that required under paragraphs 74(c) and 74(d).

62. **Submissions Related to Site 163.** Pursuant to the Schedule, Honeywell shall prepare and submit the following with regard to Site 163:

(a) A summary report of all chromium soil and groundwater data collected during site investigations in 2010 and 2011; and

(b) An addendum incorporating Site 163 into the 100% Design.

63. **Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** In the event that *ex situ* treatment is used as a final remedy for any portion of the soils containing greater than 1000 mg/kg pursuant to paragraph 59(a)(ii), Honeywell shall conduct post-treatment analysis of each treated batch of soil to demonstrate that the treatment has resulted in the reduction of the hexavalent chromium concentration such that the post-treatment total chromium concentration shown by Toxicity Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C). Such monitoring and demonstration shall be made prior to consolidation of the treated soils under the Open Space AOC cap pursuant to paragraph 59(a)(ii). In the event that Honeywell fails to make the demonstration required by this paragraph,

Honeywell shall dispose of the soils off-site at a waste disposal facility licensed to accept such waste.

64. **Post-Treatment Monitoring for 20 to 1000 Soils.** In the event that *in situ* treatment is used as a final remedy for any portion of the 20 to 1000 Soils, Honeywell shall conduct post-treatment monitoring to demonstrate that the treatment has resulted in permanent hexavalent chromium concentrations of less than 20 mg/kg in the treated area. Honeywell shall propose a program of post-treatment monitoring in a document that is submitted pursuant to paragraph 86(c). In the event that Honeywell fails to make the demonstration required by this paragraph, Honeywell shall propose further remedial actions pursuant to paragraph 59 in a document that is submitted pursuant to paragraph 86(c).

**D. Open Space AOC Components of the Chromium Remedy**

65. **Open Space AOC Soil Remedy.** In the Open Space AOC, the soil remedy shall consist of an engineered RCRA cap to isolate contaminated soils with gas venting, if necessary, to address the generation of methane and other naturally occurring gases in the Stratum O and/or Stratum D in the Open Space AOC. Soils consolidated under the cap, pursuant to paragraph 59(b)(i), shall not require gas venting and shall not be the basis for the inclusion of gas venting as a component of the cap. The cap shall be designed and constructed so that:

(a) The cap shall consist of a gas collection system, if gas venting is necessary, a base protective layer, an impervious geomembrane liner with a minimum thickness of 40 mil; a geocomposite drainage layer; a filter fabric; and a distinctive colored warning layer with markings in English and Spanish that would deter penetration of the cap in the event that digging occurred in the vicinity of the cap;

(b) All utilities, including those supporting the pump-and-treat system for groundwater remediation, with the exception of any extraction wells or collection trenches, shall be placed above the cap (but may be below the ground surface and/or contained within utility corridors). In the event that above-cap-grade gas collection and treatment is selected or is needed to meet current or future regulatory requirements, such collection and treatment facilities are prohibited in the Open Space AOC, except for piping to connect the sub-liner collection system with the treatment facilities; and

(c) Exclusive of roadways, the cap shall be overlain by layers of clean fill, backfill and/or overburden with an average depth of at least three feet and a minimum depth of at least two feet provided that any layer that incorporates overburden shall be below at least two feet of clean fill. Any clean fill or backfill soil brought to the Site will either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master. One foot of clean fill, covered with bituminous blacktop, shall be sufficient cover where roads, walkways, or other paved surfaces are located within the Open Space AOC. All clean soil fill in areas that will not involve paved roads, walkways, or other paved surfaces shall be vegetated in such a manner as to protect and maintain the required depth of the clean soil fill and to ensure that such vegetation shall not cause any interference with or penetration of the cap.

(d) The existing overburden soils in the Open Space AOC shall first be stripped off and set aside for use. If hexavalent chromium concentrations in the overburden exceed 20 mg/kg, the overburden shall be placed under the cap. If hexavalent chromium concentrations in the overburden do not exceed 20 mg/kg, the overburden may be placed above the cap but below the

two feet of clean fill required by paragraph 65(c). Excavated 20 to 1000 Soils from the Development AOC shall be placed and spread in the Open Space AOC under the cap. Both the chromium impacted soils and the previously stripped overburden shall be suitably compacted according to design specifications. Debris, to the extent it would interfere with the compaction specification requirements of the 100% Design, shall not be placed under the cap. The engineered cap shall be installed over the chromium-impacted soils exceeding 20 mg/kg hexavalent chromium.

**E. Demolition, Grading, and Backfill Requirements**

66. **Demolition and Grading Activities.** During demolition and grading activities, adequate protective measures shall be taken to protect site workers and the community from airborne dusts and exposures to contaminated soils.

67. **Backfill Requirements.** Soils excavated from the Development AOC shall be replaced with backfill soil. Any backfill soil brought to the Site shall either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master.

68. **Vegetation of Clean Fill.** All clean soil fill in areas that will not involve paved roads, sidewalks, paths, walkways, or building structures shall be vegetated in such a manner to protect and maintain the required depth of clean soil fill.

**F. Groundwater Components of the Chromium Remedy**

69. **Shallow Groundwater Remedy for the Open Space AOC.** The Open Space AOC shallow groundwater remedy shall consist of hydraulic barriers with a pump-and-treat system designed to isolate shallow groundwater and to intercept and treat shallow groundwater flowing

above the meadow mat in the Open Space AOC to the extent that such groundwater contains total chromium in concentrations in excess of 70 µg/l. The shallow groundwater remedy shall consist of the following:

(a) The existing soil/cement/bentonite wall on the boundary of Study Area 6 South and Study Area 7 shall be incorporated into the other engineering controls;

(b) Subterranean slurry walls or other hydraulic barriers shall be installed along the southern, eastern and western sides of the Open Space AOC and keyed into the meadow mat or Stratum O or to comparable depths below ground surface;

(c) A groundwater extraction system shall be established that shall consist of (i) one or more shallow extraction wells, sumps, or french drains within the Open Space AOC; (ii) pumps; and (iii) underground piping to convey any extracted water to Honeywell's Treatment Plant;

(d) The capture zone for the shallow groundwater remedy shall include at least the entire area of contaminated shallow groundwater within the Open Space AOC;

(e) A plan for control of water levels shall be developed;

(f) In the event that underground structures are demolished, the plans shall address the need for special attention for structures that extend below the meadow mat in order to control needed water levels; and

(g) Honeywell shall submit such information as is required to allow NJDEP to establish a classification exception area for groundwater at the Site, in accordance with NJDEP regulations.

70. **The Shallow Groundwater Remedy for the Development AOC.** Following implementation of the Development AOC soil components of the Chromium Remedy, Honeywell shall submit a report to (a) determine whether shallow groundwater remaining in the

Development AOC exceeds 70 µg/l total chromium and, (b) if so, evaluate the need for further remedial measures to address any such shallow groundwater remaining in the Development AOC with total chromium concentrations in excess of 70 µg/l. This evaluation shall be subject to review and comment by the Parties and approval by the Special Master.

(a) In the event that the evaluation demonstrates that further remedial measures are necessary, Honeywell shall propose such measures subject to review and comment by the Parties and approval by the Special Master;

(b) The capture zone of any remedy shall include at least the entire area of contaminated shallow groundwater except for shallow groundwater that is captured and subject to the shallow groundwater remedy for the Open Space AOC pursuant to paragraph 69;

(c) In the event that a pump-and-treat system is selected as a contingency measure for shallow groundwater in the Development AOC, all infrastructure for the pump-and-treat contingency system that is needed to ensure that the contingency system is fully operational, as required by paragraph 70(d), shall be installed prior to or in conjunction to any development of the Site. This includes at least one shallow extraction well, sump, or french drain, and the piping to convey any extracted groundwater to Honeywell's water treatment plant;

(d) If it is determined that the pump-and-treat contingency system must be activated, the pump-and-treat system shall be operational no later than six months after the date of the determination.

71. **Off-Site Shallow Groundwater Remedy.** Honeywell shall propose additional sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site. Honeywell shall submit a report of the results of such sampling and, in the event that contaminated shallow groundwater is found to extend off-site, a proposal for a remedy based on

such results. The report and the proposal for a remedy shall be subject to review and comment by the Parties and approval by the Special Master.

72. **L-Well Groundwater Remedy.** At the time this Decree is entered, the L-Well Groundwater is contained and not contributing to further contamination of surrounding waters and/or soils. However, in order to verify that this status continues following implementation of the Chromium Remedy, including any groundwater remedial measures pursuant to paragraphs 70 and 71, Honeywell shall propose a plan for one round of monitoring designed to evaluate whether the L-Well Groundwater remains contained. The plan shall include monitoring for total and hexavalent chromium and major ion chemistry to determine whether there has been movement in the L-Well Groundwater.

(a) In the event that no substantial change is detected in the major ion chemistry, no further action is required unless paragraph 72(c) is applicable.

(b) In the event that substantial changes are detected in the major ion chemistry, Honeywell shall propose a plan for further monitoring of the L-Well Groundwater. Such a plan shall be subject to review and comment by the Parties and approval by the Special Master.

(c) In the event that the initial monitoring or monitoring conducted pursuant to paragraph 72(b) demonstrates that proximate waters have total chromium concentrations in excess of 70 µg/l, regardless of whether there is a change in the major ion chemistry, Honeywell shall propose a remediation plan for the L-Well Groundwater. Such remediation plan shall be subject to review and comment by the Parties and approval by the Special Master.

### G. Permits and Authorizations

73. **Permits and Authorizations.** Honeywell shall obtain all necessary federal, state, and local permits and authorizations to carry out the Chromium Remedy as set forth in this Article.

## H. Long-Term Monitoring, Maintenance, and Protection of Engineering and Institutional Controls

74. **Protection of the Open Space AOC.** Except as provided in paragraphs 74(j) and 74(k), development in the Open Space AOC shall be prohibited. The Open Space AOC shall be protected against activities that may jeopardize the integrity of the cap and/or the groundwater remedial measures that shall be installed in the Open Space AOC pursuant to the Chromium Remedy or that may impede the long-term monitoring and maintenance of the cap and/or groundwater remedial measures. It is the intention of the Parties to implement different layers of protection, which alone or in concert, impose restrictions on development, run with the land, and survive all parties. Accordingly, the following actions shall be taken pursuant to the Schedule provided in paragraph 54:

(a) **Ownership of and Access to the Open Space AOC.** Ownership of and access to the Open Space AOC shall be in accordance with the following:

(i) Bayfront Redevelopment LLC, as the current owner in fee simple absolute of all property that comprises the Open Space AOC, shall not convey any rights or interests in any parcel that comprises the Open Space AOC property except as provided in this Decree. Within 90 days of entry of this decree, Bayfront Redevelopment LLC shall give Jersey City an option to buy all of the Open Space AOC property prior to the planned transfer pursuant to paragraph 74(a)(iii). Such option to buy shall be subject to the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall exercise the option to buy the Open Space AOC in the event that the conditions allowing for withdrawal of funds from the financial assurance mechanisms under paragraphs 98(c) or 98(d) are met;

(ii) Within 90 days of the entry of this Consent Decree, Bayfront Redevelopment LLC shall grant a conservation restriction for the Open Space AOC pursuant to the requirements of paragraph 74(b);

(iii) Upon the final construction of all roads and utility corridors within the Open Space AOC, Bayfront Development LLC shall donate good and marketable title to all the land comprising the Open Space AOC to Jersey City. In conjunction with such donation, Bayfront Redevelopment LLC shall petition to subdivide the properties within Study Area 6 South to create a new parcel(s) comprising the Open Space AOC. At the time of the donation, Jersey City shall grant Honeywell an easement for the purpose of monitoring and maintaining the Chromium Remedy. Jersey City shall also grant Honeywell all necessary access to the Open Space AOC by license or such other mechanisms as may be appropriate for purposes of monitoring and maintaining the Chromium Remedy. After it acquires title pursuant to this paragraph, Jersey City shall retain ownership of the Open Space AOC unless and until it shall have complied with the requirements of paragraph 74(a)(iv);

(iv)After it acquires title pursuant to this paragraph, Jersey City shall not convey or enter into any lease of the Open Space AOC to any other person or entity unless it has first satisfied either of the following conditions:

(1) Jersey City has obtained the Special Master's (or if the Special Master's appointment has expired, the Court's) approval to convey the Open Space AOC to a government entity that has the capacity and willingness to fulfill Jersey City's obligations under the Consent Decree with respect to the Open Space AOC and such entity agrees to submit to the Court's jurisdiction and to be bound by the requirements of the Consent Decree that Jersey City has committed to fulfill with respect to protection of the Open Space AOC pursuant to this paragraph

and routine maintenance of the permissible development in the Open Space AOC pursuant to paragraph 78(d); or

(2) The Open Space AOC has been remediated such that no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive, and Jersey City has demonstrated to the Special Master and/or the Court, as appropriate, that such remediation has been completed in accordance with all applicable requirements.

(b) **Conservation Restriction.** Prior to the grant of the option to buy pursuant to paragraph 74(a)(i), Bayfront Redevelopment LLC shall grant an open space conservation restriction, pursuant to N.J.S.A. 13:8-B-1, *et seq.*, over the Open Space AOC substantially in the form set forth in Exhibit C. Exhibit C is a conservation restriction that is consistent with the terms of this paragraph and this Consent Decree. The conservation restriction shall allow for the implementation, maintenance, monitoring, repair and replacement of the Chromium Remedy and development consistent with paragraphs 74(j) and 74(k), including the construction and placement of roads and utilities. The Conservation Restriction shall also allow for current uses of the Open Space AOC to continue until such time as construction of the Chromium Remedy begins. The Hackensack River Watershed Land Trust shall be the primary holder of the conservation restriction, with all rights of monitoring and enforcement. Riverkeeper shall propose an entity to serve as the secondary holder of the conservation restriction subject to comment by the Parties and review by the Special Master. The secondary holder shall have secondary rights of monitoring and enforcement.

(i) The conservation restriction shall be incorporated into this Consent Decree and made part of this Consent Decree. The final, executed conservation restriction shall be lodged with the Court and entered as an order of the Court. The conservation restriction shall be enforceable in this Court, in the same manner as this Consent Decree.

(ii) The conservation restrictions provided under this Consent Decree shall be consistent with the prohibited and permitted development of the Open Space AOC as set forth in paragraphs 74(j) and 74(k) below.

(iii) Jersey City shall not take any action, whether through exercise of any power of eminent domain, application to the State of New Jersey for approval of a diversion of public park or recreation land, legal challenge to the validity or enforceability of the conservation restriction, or otherwise, the effect of which would be to in any way terminate, abrogate, or diminish the terms, conditions, or purposes of the conservation restriction. If, notwithstanding the preceding sentence, Jersey City proceeds with a condemnation or other action, the result of which would be to terminate, abrogate, or otherwise diminish the terms, conditions, or purposes of the conservation restriction, Jersey City shall, before taking any such action satisfy all of the conditions set forth in paragraph 74(a)(iv)(2).

(iv) Notwithstanding the foregoing, the conservation restriction may be terminated upon application of any Party when no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive.

(c) **Deed Notice.** Upon completion of the Chromium Remedy, the Open Space AOC shall be subjected to the deed notice substantially in the form set forth in Exhibit D that restricts

future activities on the Open Space AOC. Nothing in the deed notice shall be construed as preventing the imposition of more stringent restrictions on the development allowed in the Open Space AOC pursuant to this paragraph and, in particular, the conservation restriction provided for in paragraph 74(b).

(d) **Recording of the Consent Decree, Conservation Restriction, and Deed Notice.** This Consent Decree, the conservation restriction imposed pursuant to paragraph 74(b), and the deed notice imposed pursuant to paragraph 74(c) shall be recorded, pursuant to N.J.S.A. §§ 46:15-1.1, 46:16-1.1, and 46:16-2, in the office of the Hudson County Register and a conspicuous reference to the Consent Decree, conservation restriction, and deed notice shall be included in all instruments concerning title to the Open Space AOC. Any Party shall have the right, periodically, but no more than once every 25 years, to record memoranda or other instruments that reference, incorporate, or attach this Consent Decree, the conservation restriction, the deed notice, and/or any further orders of the Court related to the Open Space AOC in the real estate records related to the Open Space AOC.

(e) **Zoning.** Pursuant to the Redevelopment Plan, the Open Space AOC is designated for open space and park. Jersey City shall not amend or change this designation unless it first satisfies the requirements of paragraph 74(a)(iv)(2).

(f) **Recreation and Open Space Inventory.** Upon acquiring fee simple absolute title to the Open Space AOC, Jersey City shall add those portions of the Open Space AOC not covered by roads, the pedestrian thoroughfare, and utility corridors adjacent to roads onto its Green Acres Program Recreation and Open Space Inventory ("ROSI") pursuant to N.J.A.C. § 7:36 and shall specify in such listing that it is subject to (i) Honeywell's prior easement to monitor, maintain, repair, and replace the Chromium Remedy; (ii) the actions necessary to implement, monitor,

maintain, repair, and replace the Chromium Remedy; (iii) the actions necessary to install any development permissible under paragraphs 74(j) and 74(k); and (iv) the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall also take all steps necessary or appropriate to notify the New Jersey Green Acres Program that such portions of the Open Space AOC have been added to its ROSI, such that those portions of the Open Space AOC shall thereafter be subject to all procedural and regulatory requirements applicable under the Green Acres Program, including prohibitions against diversion.

(g) **Eminent Domain.** If all or part of the Open Space AOC is taken in exercise of the power of eminent domain, or acquired by purchase in lieu of condemnation, by any public, corporate, or other authority so as to terminate, abrogate, or limit the restrictions created by this Consent Decree or the conservation restriction imposed pursuant to paragraph 74(b), in whole or in part, any Party may take appropriate actions to challenge such taking if there is a reasonable legal basis for doing so. In the event that the Parties are unable to prevent a taking notwithstanding their reasonable and appropriate efforts, any Party may take appropriate actions to recover the full value of the interests in the Open Space AOC subject to the taking or in lieu purchase, and all direct and incidental damages, costs, and fees occasioned thereby.

(h) **Environmental Covenant.** In the event that New Jersey enacts the Uniform Environmental Covenants Act or its substantial equivalent, the Parties shall address the issue of whether an environmental covenant shall be established for the Open Space AOC under the statute. If the Parties are unable to reach agreement on establishment of an environmental covenant, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of an environmental covenant if it would provide substantial additional protection for the Open Space AOC without

unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(i) **Future Protections.** Any Party shall have the right to propose consideration of additional or substitute protections for the Open Space AOC. If the Parties are unable to reach agreement with regard to the proposal, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of additional or substitute protections for the Open Space AOC if they would provide substantial additional protection for the Open Space AOC without unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(j) **Prohibited Development in Open Space AOC.** Only development satisfying the requirements of this paragraph and paragraph 74(k) shall be permitted in the Open Space AOC. All other development in the Open Space AOC shall be prohibited.

(i) Honeywell shall establish Open Space Design Standards that shall govern all development in the Open Space AOC regardless of when the construction or installation of permissible development occurs. The Open Space Design Standards shall satisfy each of the requirements set forth in paragraph 74(j)(v) and shall set forth the requirements for development that are necessary for the protection of the integrity of the Chromium Remedy.

(ii) The Initial Development in the Open Space AOC shall be the development undertaken following the completion of the Chromium Remedy in the Open Space AOC. The Initial Development may occur in one or more phases. Honeywell and Bayfront

Redevelopment LLC shall prepare a Development Plan before the initiation of each phase of the Initial Development. The Initial Development Period for each phase shall consist of the period covered by the Initial Development, plus a period of 10 years following the submission of the as-built documentation for the phase pursuant to paragraph 74(j)(viii).

(iii) The Special Master shall have jurisdiction to review the Open Space Design Standards and the Development Plan(s) solely for the purpose of ensuring that any development undertaken during the Initial Development Period is consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy. The Special Master's jurisdiction with regard to development in the Open Space AOC shall run through the Initial Development Period for each phase.

(iv) Honeywell shall ensure that the requirements of this paragraph and paragraph 74(k) are satisfied with regard to any development undertaken within the Initial Development Period. Honeywell shall also ensure that any development undertaken within the Initial Development Period is designed and installed in a manner consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy.

(v) Any development undertaken in the Open Space AOC, regardless of when undertaken, shall satisfy each of the following requirements:

(1) It shall not jeopardize the integrity of the Chromium Remedy;

(2) It shall be limited to the types of development permitted under paragraph 74(k);

(3) It shall be consistent with this Consent Decree, including the conservation restriction imposed pursuant to paragraph 74(b), and the Redevelopment Plan; however, in the

event of any conflict or inconsistency between this Decree and the Redevelopment Plan, this Decree shall govern;

(4) In total, at least 75% of the Open Space AOC, exclusive of the acreage used for roads and the pedestrian thoroughfare, shall be comprised of landscaping, as defined by paragraph 74(k)(xi);

(5) The portion of the Open Space Design Standards necessary for protection of the Chromium Remedy as related to all roads, the pedestrian thoroughfare and associated utility corridors as well as the general location of such items shall be included in the 100% Design of the Chromium Remedy;

(6) If the lowest elevation for the bedding for any utility line, including irrigation or sprinkler lines, is two feet from the top of the warning layer of the cap, the utility line shall be placed in a utility corridor;

(7) In any event, there shall be two feet of soil or more between the warning layer of the cap and the lowest elevation of the bedding for any irrigation or sprinkler lines; and

(8) No permanent concession facilities shall be permitted.

(vi) Honeywell shall submit the Open Space Design Standards and the Development Plan(s) for any development undertaken during the Initial Development Period pursuant to the requirements of paragraph 86(c), except that such documents need not be submitted to NJDEP. Following Honeywell's submission of such documents, the procedures of paragraphs 86(e) and 86(f) shall apply, except that the Special Master need not provide notice to NJDEP.

(vii) During the Initial Development Period, any development in the Open Space AOC shall require the preparation and submission of a Development Plan pursuant to

paragraph 74(j)(vi) and such Development Plan shall be subject to review by the Special Master pursuant to paragraph 74(j)(iii).

(viii) Upon completion of each phase of the Initial Development, Honeywell shall provide as-built documentation for the Initial Development to the Special Master, Riverkeeper, and Jersey City. Upon completion of any further development during the Initial Development Period for the phase, Honeywell shall also provide as-built documentation to the Special Master, Riverkeeper, and Jersey City for the additional development. Such additional as-built documentation for a phase shall not affect the running of the Initial Development Period for the phase.

(ix)During the Initial Development Period, replacement in-kind of development features or facilities included in the Initial Development or minor modifications to the development features or facilities included in the Initial Development shall not require the preparation of a Development Plan or be subject to review by the Special Master, provided that such replacement or modification satisfies the requirements of the Open Space Design Standards, the applicable Development Plan, and paragraphs 74(j)(v) and 74(j)(x)(3)(notice requirement).

(x) After the Initial Development Period, all development is prohibited unless one of the following conditions is met:

(1) Jersey City satisfies the conditions set forth in paragraph 74(a)(iv)(2);

(2) The development is a replacement in-kind and such replacement is made in conformance with the specifications of the Open Space Design Standards, the applicable Development Plan, and paragraph 74(j)(v); or

(3) The development meets the requirements of paragraphs 74(j)(v) and 74(j)(xi), and Jersey City provides notice of its intention to alter or add to the development undertaken in the Initial Development Period. Such notice shall be provided in writing to Honeywell, Riverkeeper, and the holders of the conservation restriction established pursuant to paragraph 74(b) at least 30 days prior to Jersey City's alteration or addition to development undertaken in the Initial Development Period. Honeywell, Riverkeeper, or any holder of the conservation restriction shall have the right to move the Court to prohibit such alteration or addition.

(xi) If any of the development features or facilities that Jersey City seeks to add pursuant to paragraph 74(j)(x) require utilities that would require utility corridors other than the utility corridors installed during the Initial Development Period, Jersey City shall obtain approval from the Court before installing such new utility corridors.

(xii) Jersey City shall provide Honeywell, Riverkeeper, and the holder(s) of the conservation restriction established pursuant to paragraph 74(b) with an annual report that describes any alterations or additions, including those activities under paragraph 74(j)(x)(2), to the development undertaken during the Initial Development Period.

(xiii) All development features or facilities, whether included in the Initial Development or added subsequent thereto, are subject to demolition and/or removal to the extent necessary to maintain, replace, or repair the Chromium Remedy.

(k) **Permissible Development in the Open Space AOC.** The Initial Development or any subsequent addition or alteration thereto may include any or all of the following types of development features or facilities, provided that such development features or facilities satisfy the conditions set forth in paragraph 74(j)(v):

(i) Roads and the pedestrian thoroughfare -- both crossing and running along the Open Space AOC, but no more extensive than provided for in the diagram on page 39 of the Redevelopment Plan;

(ii) Curbing and fences;

(iii) Sidewalks, paths, walkways, and nature trails;

(iv) Utilities and utility corridors, lighting, and restrooms;

(v) Irrigation or sprinkler components or systems;

(vi) Water features;

(vii) Above-ground storm water cisterns;

(viii) Signs, including the signs or display required by paragraph 74(l);

(ix) Benches, trash receptacles, and bicycle racks;

(x) Recreational facilities, such as playground equipment, bocce ball courts, tennis courts, basketball courts, and athletic fields; and

(xi) Landscaping, including natural grasses, small trees, shrubbery, flowers, and potted plants, provided that such landscaping and the anticipated root structure of each landscaping component do not and will not jeopardize the integrity of the Chromium Remedy. Any portion of an athletic field that is covered in natural grass shall be considered landscaping for purposes of the percentage set forth in paragraph 74(j)(v)(4).

(l) **Signs or Displays.** Honeywell shall develop a permanent plan for informing visitors to the Open Space AOC of the history of the chromium production, contamination, and its remediation. Such plan shall provide for appropriate signs or displays that communicate this information. Such plan shall be subject to review and comment by the Parties and approval by the Special Master.

75. **Honeywell's Ongoing Responsibility.** Honeywell shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy in perpetuity. Honeywell shall satisfy this responsibility through establishment and implementation of a Long-Term Monitoring Plan. In the event that Honeywell ceases to exist without a successor-in-interest or its obligations under this Consent Decree are stayed or limited due to a bankruptcy petition, the Court shall appoint an independent third-party fiduciary who shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy pursuant to the requirements of this Consent Decree and the Long-Term Monitoring Plan, unless Jersey City volunteers to assume these responsibilities for the Chromium Remedy.

76. **Long-Term Monitoring Plan.** In consultation with the Parties, and subject to approval by the Special Master and NJDEP, Honeywell shall develop a Long-Term Monitoring Plan to ensure the ongoing effectiveness of the Chromium Remedy to meet the objectives set forth in paragraphs 65, 69, 68, 69, 72, and 77. The Long-Term Monitoring Plan shall be consistent with the applicable EPA policies and guidance, including, among others, EPA's Comprehensive Five Year Review Guidance (2001) (or any subsequent revision) and with NJDEP's Technical Requirements for Site Remediation (or any subsequent revision).

77. **Long-Term Monitoring Plan Objectives.** Honeywell shall design the Long-Term Monitoring Plan to satisfy each of the following objectives:

(a) Provide monitoring to ensure that the integrity and effectiveness of the Chromium Remedy are maintained; and

(b) Provide monitoring to ensure that the restrictions of the institutional controls are being satisfied, including the prohibition on development in the Open Space AOC.

78. **Monitoring and Remediation Under the Long-Term Monitoring Plan.** The Long-Term Monitoring Plan shall include the monitoring and remediation activities set forth in this paragraph and other monitoring and remediation activities, if necessary, to meet the objectives of paragraph 77. Honeywell shall provide Riverkeeper, the Special Master, and NJDEP with annual reports on activities conducted under the Long-Term Monitoring Plan.

(a) **Monitoring Activities in the Long-Term Monitoring Plan.** Honeywell shall undertake the following monitoring activities at intervals to be specified in the Long-Term Monitoring Plan, but no less frequently than set forth below, and, if the monitoring shows it is necessary, Honeywell shall also undertake the remediation activities as set forth below:

(i) Quarterly visual inspection monitoring of the Open Space AOC to ensure that it is not being put to any use that is inconsistent with paragraphs 74(j) and 74(k) or any use that may compromise the integrity of the Chromium Remedy. The Long-Term Monitoring Plan shall include an inventory of the prohibited and permissible uses pursuant to paragraph 74 and a corresponding checklist to be used by the individuals conducting the monitoring. If Honeywell determines that the Open Space AOC is being used in a manner inconsistent with the protections or the integrity and effectiveness of the Chromium Remedy, Honeywell shall act as soon as possible to cause such use to cease and, if there has been damage to the Chromium Remedy, to repair or replace it to original specifications or to a level of protection equivalent to the original Chromium Remedy;

(ii) Quarterly visual inspection monitoring of the Open Space AOC grade and slope to identify whether erosion has occurred or is occurring. Honeywell shall remediate any significant erosion.

(iii)Quarterly visual inspection monitoring to determine whether noticeable differential settlement or subsidence has occurred or is occurring in the Open Space AOC such that the integrity of the Chromium Remedy may be materially impaired. If evidence of differential settlement or subsidence is found, Honeywell shall propose further investigative measures. Honeywell shall remediate any differential settlement or subsidence that is beyond the degree of differential settlement/subsidence allowed for in the 100% Design and repair the cap and/or the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(iv)A baseline topographic survey at the completion of the Chromium Remedy and three additional surveys conducted at five-year intervals beginning five years after the conduct of the baseline survey. The topographic survey shall be of sufficient precision and accuracy to present the results as one-foot contours;

(v) Quarterly visual inspection monitoring to determine whether the Chromium Remedy in the Open Space AOC has been disturbed. Any evidence of the distinctive warning layer materials or any other cap materials as described in paragraph 65(a) at the surface is an indication that the cap has been disturbed. In such an event, Honeywell shall propose further investigative measures to evaluate whether the integrity of the cap has been compromised. In the event that the investigative measures show that the cap integrity has been compromised, Honeywell shall repair or replace the cap and the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vi) Quarterly visual inspection monitoring to ensure that burrowing animals are not materially impairing the integrity of the Chromium Remedy. If evidence of burrowing animals is found, Honeywell shall follow humane removal procedures and repair or replace the cap and

the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vii) Quarterly visual inspection monitoring of the vegetative cover in the Open Space AOC to ensure that vegetative cover is in conformance with the landscaping provisions of the 100% Design and the Redevelopment Plan and will not materially impair the integrity of the Chromium Remedy. Maintenance of the vegetative cover shall include, at a minimum, mowing to ensure that tree species cannot become established and removal of any other vegetation with the potential to damage the Chromium Remedy;

(viii)Quarterly groundwater monitoring to ensure that groundwater levels are maintained in accordance with the requirement to maintain an outward gradient from Study Area 7 and in accordance with the water level control plan developed pursuant to paragraph 69(e);

(ix) Monitoring of vented gases and the gas venting system to ensure proper operation of the system, to evaluate any degradation of the system, to assess the need for treatment of vented gases, either initial, subsequent, or further depending on whether treatment has been previously provided, and to detect any condition that might endanger public health or safety. Such monitoring shall be conducted on a monthly basis for at least one year and, if the readings are stable, such monitoring may be conducted thereafter on a quarterly basis; and

(x) Any additional monitoring as required by specific details added in the design phase of the Open Space AOC.

(b) **Procedures for Proposing Changes to the Long-Term Monitoring Plan.** Any Party may, from time to time, propose changes to the scope of the monitoring activities under the Long-Term Monitoring Plan. If the Parties agree, the Long-Monitoring Plan shall be so changed

subject to approval by NJDEP and by the Special Master, if his appointment has not terminated, or otherwise, by the Court. If the Parties are unable to reach agreement over alterations to the monitoring and the Special Master's appointment has not terminated under this Consent Decree, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation. In the event that the dispute arises after the Special Master's appointment has terminated, any Party may file a motion seeking a resolution of the dispute by the Court.

(c) **Contingency Plan**. As part of the Long-Term Monitoring Plan, Honeywell shall develop a contingency plan to ensure the integrity of the remediation in the event of any planned penetration of the cap or otherwise planned activity that compromises the cap or any unplanned event or accident that penetrates the cap or otherwise compromises the integrity of the Chromium Remedy. The contingency plan shall include, at a minimum, an annually updated plan to notify the relevant persons, including the Special Master, NJDEP, and the Parties, of (i) the event penetrating the cap, compromising the cap, or compromising the integrity of the Chromium Remedy; (ii) the general steps to be taken to identify the extent of the problem; and (iii) the standards for remedying the problem.

(d) **Routine Maintenance**. The title owner of the Open Space AOC shall conduct maintenance of the Open Space AOC features or facilities that are permissible under paragraphs 74(j) and 74(k). The maintenance workers shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy. The training shall include the identification and reporting of any uses or features that are not permissible in the Open Space AOC or that may jeopardize the integrity of the Chromium Remedy. Honeywell shall provide all training materials. The title owner of Open Space AOC shall annually provide to the other Parties and

the Special Master a report describing the training which has been provided to its maintenance workers. The title owner of the Open Space AOC shall also provide to the Parties and the Special Master notice of any violations of the restrictions relating to the Open Space AOC identified by its workers during routine maintenance.

(e) **Recordkeeping**. Honeywell shall maintain written logs or other records of those monitoring and remediation activities undertaken pursuant to the Long-Term Monitoring Plan. Such logs shall be provided to Riverkeeper on a quarterly basis.

79. **Monitoring and Reporting to Riverkeeper.** Riverkeeper shall be provided with all documents submitted to NJDEP and/or the Special Master with respect to the Chromium Remedy, including the documents identified in paragraph 86(c).

80. **Notice to Stakeholders.** All residents, regardless of whether they are owners or lessees, and all commercial tenants on Study Areas 6 and 7 are hereby deemed stakeholders. Honeywell shall ensure that all stakeholders shall be provided at the time of their purchase or lease with notice of the contamination, the remedial actions that have been undertaken or are planned, and the importance of reporting activities that may appear to jeopardize the integrity of the engineering controls. Notice shall be accomplished in the following manner:

(a) Bold or otherwise conspicuous language on the first page of the deed provided to all purchasers in the Residential Area;

(b) A summary notice of the Chromium Remedy which:

(i) Has been subject to review and comment by the Parties and approval by the Special Master; and

(ii) Provides a reference to public websites and libraries and/or the future equivalents thereof, where the following can be found:

(1) Zoning and other Jersey City maps showing the Open Space AOC; and

(2) Documents describing the contamination and the remediation, including:

(a) This Consent Decree;

(b) The Remedial Investigation Report and the Final Remedial Action Report,

(c) The annual reports on long-term monitoring and maintenance and repair activities as required by paragraph 78 and annual reports on changes to the Initial Development as required by paragraph 74(j)(xii); and

(d) The Long-Term Monitoring Plan.

(c) The public provision of the maps and documents referred to in paragraph 80(b)(ii) via websites and libraries and/or the future equivalents thereof; and

(d) Notices to lessees and commercial tenants in all lease documents.

81. **Annual Letter to Riverkeeper on Notice to Stakeholders.** Each year beginning one year after the issuance of the first notice in a deed or lease pursuant to paragraph 80, Honeywell shall provide a letter to the Riverkeeper documenting its compliance with paragraph 80.

82. **Future Notice to Stakeholders.** Honeywell shall ensure that all stakeholders are provided with notice, at least annually, of long-term monitoring activities and any additional remediation activities undertaken with respect to the Chromium Remedy. Such notice shall be accomplished by notices on websites or future equivalents thereof, including Jersey City websites, any websites created to provide information about the Chromium Remediation or redevelopment of the Redevelopment Area, and one or more of the following:

(a) Any community message board or other similar site used and/or maintained by stakeholders or the manager(s) of the Redevelopment Area;

(b) Mailings to all stakeholders; and

(c) Posters and flyers throughout the Redevelopment Area.

83. **Stakeholder Enforcement.** Any stakeholder shall have the right to enforce the remedial obligations of this Consent Decree in the Court, including post-implementation monitoring and maintenance obligations, and the terms of any deed notice or use restriction.

**I. Oversight and Enforcement by the Special Master and NJDEP**

84. **Federal Court Jurisdiction.** The Court shall retain jurisdiction for the purpose of overseeing and enforcing this Consent Decree and to review any issue or dispute which is not resolved through the oversight process described in Article III.I.

85. **Appointment and Jurisdiction of the Special Master.** The Chromium Remedy provided for in this Consent Decree is hereby referred to a Special Master pursuant to Rule 53 of the Federal Rules of Civil Procedure. The Special Master is appointed in the Consolidated Litigation for the purpose of overseeing and enforcing the Chromium Remedy, the first five years of long-term monitoring of the Chromium Remedy, financial assurances for the Chromium Remedy, and the Initial Development Period for each phase of development in the Open Space AOC. The Special Master is also appointed in the Consolidated Litigation for the limited purpose of ensuring that the scheduling and implementation of any non-chromium related remedy, any site preparation activities, and any site redevelopment activities do not undermine the integrity of, unreasonably interfere with, or unnecessarily delay the effectuation of the Chromium Remedy, the Study Area 7 remedies, and other remedies within his jurisdiction as of the date of entry of this Consent Decree. The Special Master shall have jurisdiction over all matters for which he is appointed.

86. **Oversight of the Chromium Remedy.**

(a) **NJDEP Authority**. Nothing in or pursuant to this Consent Decree shall limit NJDEP's full statutory and regulatory authority with respect to the Study Area 6 South site, including (i) permitting authority; (ii) authority to review and approve the Treatment Study reports, the Remedial Action Work Plan, the 100% Design, and final Remedial Action Report for the Chromium Remedy; and (iii) authority to issue a no further action letter.

(b) **Special Master Responsibilities**. The Special Master shall have the following responsibilities:

(i) Ensuring that Honeywell's implementation of the Chromium Remedy satisfies the requirements of this Consent Decree;

(ii) Ensuring that Honeywell's implementation of the Chromium Remedy conforms with federal, state, and local permit requirements;

(iii) Establishing a reasonable schedule for the implementation of the Chromium Remedy and monitoring conformance with it;

(iv) Reviewing monthly progress reports and conducting periodic meetings with the Parties to review the progress of the implementation of the Chromium Remedy. NJDEP shall be invited, but not required, to participate in these meetings and the decision as to whether to participate shall be left to NJDEP's sole discretion;

(v) Submitting bi-monthly progress reports to the Court pursuant to the schedule for the submission of such reports established in *ICO v. Honeywell*;

(vi) Overseeing the financial assurances established pursuant to paragraphs 91 through 100, and, until the expiration of his term pursuant to paragraph 90, overseeing the financial assurances established pursuant to paragraphs 101 through 112;

(vii) Coordinating review of the documents as provided in paragraphs 86(c) through 86(g);

(viii) Overseeing all development undertaken in the Open Space AOC during the Initial Development Period pursuant to paragraph 74(j)(iii); and

(ix) To the extent that, in matters within the jurisdiction of the Special Master as set forth herein, a dispute arises between the Parties with respect to implementation of the Chromium Remedy, issuing a recommendation to the Court with respect to the dispute.

(c) **Submission of Documents by Honeywell.** Honeywell shall submit the following documents to Riverkeeper, Jersey City, the Special Master, and NJDEP:

(i) An overall schedule with milestones for the design and implementation of the remedy ("Schedule") consistent with paragraph 54 above;

(ii) A Second Supplemental Remedial Investigation Report reporting the results of the field work conducted pursuant to paragraph 55;

(iii)A Chromium Impacted Soils Pilot Test Work Plan and Analytical Protocol for conduct of the treatment study pursuant to paragraph 56, unless such documents are agreed to by NJDEP and Riverkeeper before the entry of this Consent Decree;

(iv)An Initial Treatment Study Report for the Development AOC;

(v) A Final Treatment Study Monitoring Report;

(vi) The documents for Site 163 submitted pursuant to paragraphs 54(a)(iv), 54(a)(v), 61, and 62;

(vii) A report to evaluate the need for remediation of any potentially remaining contaminated shallow groundwater in the Development AOC after implementation of the Development AOC Soils Remedy and, based on such an evaluation, a proposal;

(viii) A report of the results of the sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site pursuant to paragraph 71 and, based on the results, a proposal for a remedy;

(ix) A plan for one round of monitoring to evaluate whether the L-Well Groundwater remains contained pursuant to paragraph 72;

(x) A proposal for a remedy of the L-Well Groundwater, in the event L-Well Groundwater monitoring indicates the contaminated groundwater is no longer contained, pursuant to paragraph 72;

(xi) A Remedial Action Work Plan;

(xii) A 50% Design Report (which may include the Development AOC Conceptual Design Plan as a component) as well as design drawings and specifications at the 50% level for other components of the Chromium Remedy (hereinafter the 50% Design);

(xiii) Design drawings and specifications at the 100% level (after selection of the contractor) (hereafter "100% Design");

(xiv) The data validation plan, including quality control and quality assurance protocols;

(xv) The site-wide master health and safety plan;

(xvi) The Long-Term Monitoring Plan;

(xvii) The final Remedial Action Report or final construction report (including as-built drawings and such other reports as may be prepared of the remedy as implemented);

(xviii) A program for post-treatment monitoring pursuant to paragraph 63, and, depending on such results, a proposal for further remedial actions;

(xix) A report reviewing measured groundwater levels for the groundwater remedy;

(xx) Documents required during the Initial Development Period pursuant to paragraphs 74(j)(vi), 74(j)(vii), and 74(j)(viii); and

(xxi) Other post-implementation monitoring reports as required by the Long-Term Monitoring Plan.

(d) **Initial Review of Documents by NJDEP.** The Parties and Special Master shall allow the period of time set forth below for NJDEP to conduct its review of a submission (hereinafter "NJDEP Review Period") before the document is subject to the Special Master review and approval process. During the NJDEP Review Period, any Party may submit comments to NJDEP. For the Second Supplemental Remedial Investigation Report, the Remedial Action Work Plan, the Initial Treatment Study, and the Final Treatment Study Monitoring Report, the NJDEP Review Period shall be 90 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. For any other documents identified in paragraph 86(c), the NJDEP Review Period shall be 30 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. The NJDEP review period shall be extended an additional 30 days for any document for which NJDEP provides the Parties and the Special Master with notice that its review will require an additional 30 days. At the conclusion of the NJDEP Review Period, the comment and review process provided for in paragraphs 86(e) and 86(f) shall commence. In the event that any document has been revised during the NJDEP Review Period, Honeywell shall resubmit the applicable document for purposes of the comment and review provided for in paragraphs 86(e) and 86(f).

(e) **Comment on Submitted Documents**. For each of the documents submitted by Honeywell pursuant to paragraph 86(c), and following conclusion of the NJDEP Review Period as described in paragraph 86(d), the Special Master shall establish a schedule for the submission

of comments and responses to comments. For each of the documents submitted, Riverkeeper, Jersey City, the Special Master, and NJDEP shall have the right to submit comments to Honeywell. Honeywell shall address all comments received and submit a revised document. The revised document shall be submitted by Honeywell to Riverkeeper, Jersey City, the Special Master, and NJDEP. The revised document shall be subject to review and approval pursuant to paragraph 86(f), unless the Parties agree both on the revised document and that further review and approval pursuant to paragraph 86(f) is unnecessary. In that event, the Parties shall inform the Special Master that review under paragraph 82(f) is unnecessary and Honeywell shall proceed to implement the revised document.

(f) **Review and Approval of the Submitted/Revised Document**

(i) **Scope of Review**. Subject to the limitations in paragraph 82(e), all documents submitted by Honeywell, pursuant to paragraph 86(c) and 86(e), shall be subject to review and approval by the Special Master in accordance with the following procedure. All such documents, except the Schedule and the 100% Design, shall be subject to the review and approval process and shall not require an order of the Court. The Schedule and 100% Design documents shall be subject to the review and approval process, but shall also require an order of the Court as provided in paragraph 86(g). A document shall be approved if the document (1) complies with this Consent Decree; (2) complies with the Remedial Action Work Plan for the Chromium Remedy; and (3) complies with the Schedule and 100% Design.

(ii) **Procedure**. Prior to making a decision on a document, the Special Master shall notify NJDEP of his intention to rule on the document or make a recommendation to the Court on the document. Such notice shall notify NJDEP that the Special Master will consider any comments NJDEP wishes to submit on the document if such comments are submitted within

the timeframe established by the Special Master in the schedule for comments pursuant to paragraph 86(e). NJDEP shall in its sole discretion determine whether to submit comments to the Special Master.

(iii) **Court Review**. If any Party objects to the Special Master's recommendation to the Court or approval of any document pursuant to this paragraph, that Party may seek further relief from the Court with respect to the document.

(g) **Schedule and 100% Design Documents**. As to the Schedule and the 100% Design documents, Honeywell shall have the responsibility, within 30 days of the Special Master's approval of each document, of (i) moving for entry of an order by the Court approving the document as approved by the Special Master; or (ii) filing objections with the Court to the Special Master's approval (and any recommendations contained therein) and moving for entry of the Schedule or 100% Design (including any such recommendations of the Special Master to which Honeywell agrees). Riverkeeper shall have the right in these proceedings to raise any objections they might have to the Schedule or 100% Design as approved by the Special Master or to the submission by Honeywell to the Court. NJDEP shall receive notice of any motion filed with respect to the Schedule or the 100% Design.

(h) **Flexibility in 50% and 100% Design Documents**. The Parties recognize that work conducted to implement the Chromium Remedy may be conducted by Honeywell contractors and that Honeywell may establish performance-based criteria or specifications for its contractors. As a result, the Parties recognize that the 50% Design and 100% Design documents for the Chromium Remedy may include performance-based standards, criteria, and specifications. These documents shall be sufficiently prescriptive to enable the Parties and the Special Master to evaluate their conformance with the Remedial Action Work Plan and this Consent Decree. The

Parties also recognize that the 100% Design will be completed after Honeywell has selected a contractor. The Parties further recognize that completing the 100% Design after the selection of the contractor(s) shall not make the 100% Design subject to any less stringent or more deferential review. Honeywell's commitment to the contractor(s) shall not be cause to limit review by the Parties and the Special Master.

(i) **Changes to the Schedule.** The Parties recognize that changes to individual line items in the Schedule will occur. To the extent that (i) the Parties and the Special Master agree that such changes do not have a material impact on satisfaction of the Schedule milestones established for items set forth in paragraph 54; and (ii) such changes do not require modifications to any necessary permits or authorizations for the Chromium Remedy, such changes may be made upon agreement of the Parties and the Special Master without further order of the Court.

87. **Retention of Professionals.** The Special Master may retain the services of professionals and/or other technical personnel, as reasonably needed, to fulfill his obligations under this Consent Decree, and for which he will be reimbursed pursuant to paragraph 89.

88. **Insurance for the Special Master.** The Special Master shall obtain insurance coverage relating to the performance of the Special Master's duties and responsibilities under this Consent Decree. Such coverage shall be similar to the Special Master's existing coverage in *ICO v. Honeywell*, procured pursuant to the Court's November 11, 2005 Stipulation and Order Regarding Special Master's Application to Procure Insurance Coverage, and as extended to the Consolidated Litigation by the Sediment Consent Order. The insurance coverage shall be sufficiently extended in duration and scope to cover all additional duties and responsibilities as set forth hereunder. Honeywell shall pay the premiums and other administrative costs of the Special Master's insurance.

89. **Reimbursement of Special Master Fees and Expenses.** The Special Master shall submit fee applications to the Court for approval of reasonable fees and expenses incurred in the oversight of matters referred to him pursuant to this Consent Decree. Any Party may raise with the Court objections to such fee applications. Upon approval of a fee application by the Court, the reimbursement of the Special Master's fees and expenses shall be made from the escrow fund previously established by Honeywell for the purpose of paying the Special Master's fees and expenses in *ICO v. Honeywell* pursuant to this Court's September 15, 2003 Order Setting Financial Assurances and extended to the Consolidated Litigation by the Sediment Consent Order.

90. **Expiration of Special Master's Appointment.** The Special Master's appointment under this Consent Decree shall expire after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy and the Initial Development Period for each phase of development has been concluded as provided in paragraph 74(j)(ii). However, solely to the extent that the Special Master is still supervising other portions of the Consolidated Litigation or *ICO v. Honeywell* after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy or the Initial Development Period for each phase of development as provided in paragraph 74(j)(ii), whichever is later, the Special Master shall continue to have jurisdiction under this Consent Decree until he has completed his specifically enumerated responsibilities under the Final Judgment in *ICO v. Honeywell*, the Sediment Consent Order, the Deep Groundwater Consent Order, the Study Area 6 North Consent Decree, and any other future orders, decrees, or judgments in *ICO v. Honeywell* and the Consolidated Litigation. Enumerated responsibilities under any order, decree, or judgment shall include only those tasks specifically assigned to the Special Master in the order, decree, or judgment. Enumerated responsibilities

shall not include any continued jurisdiction exercised over long-term monitoring beyond the initial period specified in the order, decree, or judgment. For example, the Special Master has jurisdiction over the first five years of long-term monitoring under the Sediment Consent Order. Oversight during these five years shall be an enumerated responsibility, but any continued oversight of long-term monitoring, pursuant to the extension of the Special Master's jurisdiction beyond the first five years, as provided in paragraph 60 of the Sediment Consent Order, shall not be an enumerated responsibility. Such extensions of jurisdiction shall be effective only so long as specific enumerated responsibilities in any order, decree, or judgment have not been fulfilled.

**J. Initial Financial Assurances**

91. **Chromium Remedy Letter of Credit.** Honeywell shall obtain a one-year, irrevocable letter of credit (the "Chromium Remedy Letter of Credit") to be automatically renewed annually in an amount equal to the "Remedial Costs Subject to Financial Assurance."

(a) Remedial Costs Subject to Financial Assurance shall mean:

(i) The costs of implementing the Chromium Remedy calculated using factors, including inflation and discount rates, determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process;

(ii) The costs of monitoring and maintenance activities for five years, as required by the Long-Term Monitoring Plan, calculated using factors including inflation and discount rates determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process; and

(iii) A contingency of 25% with respect to those costs listed in paragraphs 91(a)(i) and 91(a)(ii).

(b) The Chromium Remedy Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution, provided that in either case, the financial institution shall be acceptable to the Special Master.

92. **Procedures for Review of the Proposed Chromium Remedy Letter of Credit.** No later than December 31, 2008, Honeywell shall submit to Riverkeeper and the Special Master for their review the proposed (a) amount of the Chromium Remedy Letter of Credit; (b) form of the Chromium Remedy Letter of Credit; and (c) name of the institution that will issue the Chromium Remedy Letter of Credit. If Riverkeeper does not agree to the terms of the Chromium Remedy Letter of Credit, the Parties shall meet and confer in an effort to resolve their differences. If the Parties are unable to reach agreement over the terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the Chromium Remedy Letter of Credit.

93. **Automatic Renewal.** The Chromium Remedy Letter of Credit shall be automatically renewed annually unless (a) no later than 120 days prior to the anniversary of the Chromium Remedy Letter of Credit issue date, the issuer provides notice of nonrenewal or (b) Honeywell seeks a reduction in the Chromium Remedy Letter of Credit, pursuant to paragraph 94, to correspond to the reduced estimate of Remedial Costs Subject to Financial Assurances. If the issuer provides notice of nonrenewal, Honeywell shall obtain a replacement irrevocable Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit. If Honeywell is not otherwise in default as provided in Article III.J, the Special Master shall direct the cancellation of the prior Chromium Remedy

Letter of Credit within 91 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit. In the event that the Special Master is entitled to draw upon a Chromium Remedy Letter of Credit because there are two Chromium Remedy Letters of Credit currently in place, the Special Master shall not draw an aggregate amount in excess of the highest valued Chromium Remedy Letter of Credit. Upon Honeywell's request, the Special Master may, at his option, decide not to require overlapping letters of credit in any year based on Honeywell's financial strength in that year, provided that Honeywell has submitted all necessary information so that the Special Master can make his determination at least 150 days prior to the expiration of the Chromium Remedy Letter of Credit.

94. **Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit.** Honeywell shall have the right annually to seek a reduction in the Chromium Remedy Letter of Credit. At the time of seeking such reduction, Honeywell shall submit to the Riverkeeper and the Special Master an estimate of the remaining Remedial Costs Subject to Financial Assurance, including the contingency as described in paragraph 91(a)(iii), and shall seek adjustment of the Chromium Remedy Letter of Credit so that the total estimated amount of remaining Remedial Costs Subject to Financial Assurance are covered by the Chromium Remedy Letter of Credit. However, the adjustment shall not result in reducing the Chromium Remedy Letter of Credit to an amount below the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), plus a contingency of 25% of the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), and shall not result in reducing the Chromium Remedy Letter of Credit to an amount less than $20,000,000 as expressed in 2008 dollars unless long-term financial assurances are in place pursuant to Article III.K. Before making any request to reduce the amount or modify the terms of the Chromium Remedy Letter of Credit, Honeywell shall first confer with the Riverkeeper and

in an effort to reach agreement on the modified amount or terms of the Chromium Remedy Letter of Credit. If the Parties are unable to reach agreement over the modified amount or terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall resolve the dispute. Any Party shall have the right to seek review by the Court of the Special Master's decision regarding the modified amount or terms of the Chromium Remedy Letter of Credit. Upon agreement on the amount of the reduction or modified terms of the Chromium Remedy Letter of Credit (or upon order of the Court directing that the Chromium Remedy Letter of Credit be reduced to an identified amount or otherwise modified), Honeywell shall obtain a replacement Chromium Remedy Letter of Credit in such amount and with such terms. If Honeywell is not otherwise in default as provided in Article III.J and the issuer of the primary Chromium Remedy Letter of Credit has not provided notice of non-renewal, within 30 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit, the Special Master shall direct the cancellation of the prior Chromium Remedy Letter of Credit.

95. **Bankruptcy Protection**. Neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy. The Chromium Remedy Letter of Credit shall contain the language necessary to assure that neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

96. **Exclusive Court Jurisdiction**. The Chromium Remedy Letter of Credit shall recite that the issuer submits to the exclusive jurisdiction of this Court for any and all disputes arising under the Letter of Credit.

97. **Application of New York Law.** The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Chromium Remedy Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

98. **Procedures upon Honeywell's Material Default of Its Obligations.** During the period in which the Special Master has jurisdiction pursuant to paragraph 85, the Chromium Remedy Letter of Credit shall be payable to the Special Master and shall not, prior to its expiration date, be revoked or terminated except consistent with this Consent Decree and with the consent of the Special Master and approval by the Court. The Special Master's ability to draw upon the Chromium Remedy Letter of Credit shall not be limited by any agreement between Honeywell and the issuer. The Special Master may, without further order or notice to this Court, draw upon the Chromium Remedy Letter of Credit upon the occurrence of default by Honeywell, which shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 93 to deliver a replacement Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 15 days after written notice to Honeywell thereof and either (i) Honeywell, in the opinion of the Special Master without further input from the Parties, shall have failed to cure the breach; (ii) during the 15-day period, the Court has not entered an order to prevent the Special Master from

drawing on the Chromium Remedy Letter of Credit; or (iii) the Court or the Special Master has not granted Honeywell additional time to cure the breach;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if involuntary filing has not been dismissed within 60 days; the appointment of a custodian, receiver, liquidator, or trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 98(c), and the failure of Honeywell to provide assurance to the Special Master, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

99. **Placement of Proceeds in Court Registry Investment System Account**. In the event that the Special Master draws upon the Chromium Remedy Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Chromium Remedy Letter of Credit which represent the remaining estimated Chromium Remedy costs under paragraphs 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), in an account with the Court Registry Investment System in accordance with Local Civil Rule 67.1 and not expend the proceeds of the Letter of Credit without further order of this Court. The

Special Master shall place all additional proceeds of the Chromium Remedy Letter of Credit in a trust fund pursuant to paragraph 103(b)(v).

100. **Termination of Chromium Remedy Letter of Credit**. The Chromium Remedy Letter of Credit may be withdrawn in its entirety upon the satisfaction of all of the following:

(a) The implementation of the Chromium Remedy; and

(b) Establishment of long-term financial assurance pursuant to Article III.K.

**K. Long-Term Financial Assurances**

101. **Long-Term Financial Assurances.** Honeywell shall fund long-term financial assurances to ensure that the activities set forth in paragraph 102(a) are carried out regardless of whether Honeywell is financially able to carry out such activities in perpetuity.

102. **Costs Subject to Long-Term Financial Assurances.**

(a) Long-term financial assurances shall provide enough funds to cover the costs of the following activities:

(i) Perpetual monitoring and maintenance of the Chromium Remedy, including installation, operation and monitoring of any above-cap-grade gas collection and/or treatment system as may be necessary, but such system is not part of the 100% Design;

(ii) Perpetual operation of the shallow groundwater remedies pursuant to paragraphs 69, 70, and 71;

(iii) Perpetual repair of the cap;

(iv) Perpetual replacement of the cap on a 75-year replacement interval; and

(v) The perpetual administration of the trust fund regardless of whether such trust fund is selected by Honeywell pursuant to paragraph 103(a) or is established from the Long-Term Letter of Credit pursuant to paragraphs 103(b)(ii), 103(b)(v), or 109.

(b) The costs that shall be subject to financial assurances is an amount that will provide the full payment for each of the activities set forth in paragraphs 102(a)(i) through 102(a)(v) plus a 25% contingency when the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to be performed. The costs subject to financial assurances are forward looking because they state an amount valued at the time the funds are needed. As such, they shall be stated in contemporary time as the present value (calculated on the basis of a discount rate of 4.75%) of the estimated future costs of the activities specified in paragraphs 102(a)(i) through 102(a)(v), plus a 25% contingency on those costs.

103. **Long-Term Financial Assurance Mechanisms.** Honeywell shall provide long-term financial assurances in the amount of the costs subject to long-term financial assurances in the form of a trust fund, a letter of credit, or some combination of the two. The selected mechanism(s) shall satisfy the following requirements:

(a) **Trust Fund.** In the event that Honeywell selects a trust fund, Honeywell shall create a trust fund such that it can provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(i) The trust fund shall be at arm's length from Honeywell and shall not be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The trust fund agreement shall contain the language necessary to assure that neither the trust fund nor the earnings of the trust fund shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The trust fund shall be managed by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution managing the

trust fund declares bankruptcy, the Court shall withdraw the funds and appoint another financial institution meeting the requirements of this paragraph to manage the trust.

(iii) No more frequently than once per year, Honeywell may apply to the Court for an order directing the trust manager to reimburse Honeywell for any costs that it has incurred to carry out the activities set forth in paragraphs 102(a)(i) through 102(a)(iv).

(b) **Long-Term Letter of Credit**. In the event that Honeywell selects a letter of credit, Honeywell shall obtain a one-year irrevocable letter of credit (the "Long-Term Letter of Credit") to be automatically renewed annually in an amount that provides sufficient funds such that a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a), could be created. The Long-Term Letter of Credit-funded trust, plus any trust fund established under paragraph 103(a), shall provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The amount of any Long-Term Letter of Credit shall therefore be adjusted periodically as the cap replacement interval is approached because, for example, the money needed in the 10th year to fund a trust that can provide for replacement of the cap in the 75th year is much less than the money that would be needed in the 40th year. Such periodic adjustments shall be proposed and approved by the Court in conjunction with the adjustments under paragraph 106.

(i) Neither the Long-Term Letter of Credit nor the proceeds of the Long-Term Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The Long-Term Letter of Credit shall contain the language necessary to assure that neither the Long-Term Letter of

Credit nor the proceeds of the Long-Term Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The Long-Term Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution issuing the Long-Term Letter of Credit declares bankruptcy, the Court shall authorize the drawing of funds from the Long-Term Letter of Credit and shall deposit those funds in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(iii) The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits) as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Long-Term Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

(iv) The Long-Term Letter of Credit shall be automatically renewed annually, unless, no later than 120 days prior to the anniversary of the Long-Term Letter of Credit issue date, the issuer provides notice of non-renewal. If the issuer provides notice of non-renewal, Honeywell shall obtain a replacement irrevocable Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit. If Honeywell is not otherwise in default as provided in this Article, the Court shall direct the cancellation of the prior Long-Term Letter of Credit within 91 days after delivery to the Court of any replacement of a Long-Term Letter of Credit. In the event that the Court is entitled to draw upon a Long-Term Letter of Credit when there are two Letters of Credit currently in place, the Court shall not draw an aggregate amount in excess of the highest valued Long-Term Letter of Credit.

(v) Prior to the expiration of the Special Master's appointment pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Special Master. During the time the Long-Term Letter of Credit is payable to the Special Master, the Special Master may draw on the Long-Term Letter of Credit as provided in paragraph 98. In the event that the Special Master draws upon the Long-Term Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a). After the Special Master's appointment expires pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Court and, in the event that the Court draws on the Long-Term Letter of Credit, the Court shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(vi) Whether the Long-Term Letter of Credit is payable to the Special Master or the Court, it shall not, prior to its expiration date, be revoked or terminated by Honeywell except consistent with this Consent Decree and with the approval of the Court. The ability of the Special Master or the Court to draw upon the Long-Term Letter of Credit shall not be limited by any agreement between Honeywell and the issuer.

(vii) In the event that the Long-Term Letter of Credit is drawn upon and invested pursuant to paragraph 103(b)(ii), 103(b)(v), or 109 and Honeywell has also selected a trust fund pursuant to paragraph 103(a), resulting in the existence of two trust funds, the two trust funds shall be managed so as to ensure that the combined amount of the trust funds is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(c) **Combination**. Honeywell may use some combination of a trust fund and a letter of credit to achieve the requirements of this paragraph. However, if a combination is used, Honeywell shall ensure that the combined amount of financial assurances is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The trust fund and the letter of credit shall otherwise satisfy all the requirements of paragraphs 103(a) and 103(b).

104. **Procedures for Review of the Proposed Long-Term Financial Assurances**. No later than June 1, 2009, Honeywell shall submit to Riverkeeper and the Special Master, for their review (a) the amount of the proposed long-term financial assurances; (b) the form(s) of the proposed long-term financial assurance mechanisms; and (c) the name(s) of the institution proposed to manage or issue the long-term financial assurances. If Riverkeeper agrees to the terms of the proposed long-term financial assurances, within 60 days of such agreement, Honeywell shall create a trust fund and/or secure a Long-Term Letter of Credit on those terms. If the Parties are unable to reach agreement over the terms of the long-term financial assurances, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the financial assurances.

105. **Temporary Maintenance of Chromium Remedy Letter of Credit**. Until the long-term financial assurances have been put into place, Honeywell shall maintain the Chromium Remedy Letter of Credit required by paragraph 91 in an amount equal to at least $20,000,000 in 2008 dollars. In the event of any default by Honeywell pursuant to paragraph 98 while the Chromium Remedy Letter of Credit is in place, the provisions of paragraph 103(b)(v) for the placement of the proceeds that exceed the remaining estimated Chromium Remedy costs under

paragraph 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), shall apply.

106. **Adjustment of Amount Held in Long-Term Financial Assurances**. Every five years as marked from the establishment of the first long-term financial assurances pursuant to paragraph 103, the Parties shall report to the Court whether the long-term financial assurances are adequately funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. At such time as the Parties report to the Court, any Party may seek an adjustment in the amount of the long-term financial assurances. The Party seeking an adjustment must demonstrate that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Such demonstration shall reflect the actual costs of implementing the remedy and/or any replacement of the remedy, once such actual costs are available. The demonstration shall also reflect the costs of work completed to date and the actual lifetime of the cap, once the cap has been replaced or has passed a replacement interval without requiring replacement. The demonstration shall further reflect the actual performance of the fund and its ability to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Any demonstration shall be forward looking and shall be based upon estimates of what the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to cost at the time they must be performed and the amount of funding projected to be available to undertake such activities at the time they must be performed. If, after reviewing the submission(s) received from the Parties, the Court determines that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to

long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary, the Court shall order an adjustment in the amount held in the long-term financial assurances to overcome the shortage or overage. In the event that the Court determines that the long-term financial assurances are under-funded, it shall order Honeywell to increase the amount held in the long-term financial assurances. In the event that the Court determines that any trust fund established pursuant to paragraph 103(a) is over-funded, the Court shall issue an order directing the trust manager to pay the overage to Honeywell. In the event that the Court determines that the Long-Term Letter of Credit is over-funded, the Court shall issue an order permitting Honeywell to reduce the amount covered during the next annual renewal of the Long-Term Letter of Credit pursuant to paragraph 103(b)(iv). Any adjustment to the amount of the Long-Term Letter of Credit pursuant to this paragraph shall be in addition to any adjustment of the amount of the Long-Term Letter of Credit required pursuant to paragraph 103(b).

107. **Exclusive Court Jurisdiction**. The trust fund agreement and/or the Long-Term Letter of Credit shall recite that the trust fund manager and/or issuer of the Long-Term Letter of Credit submit to the exclusive jurisdiction of this Court for any and all disputes arising under the trust fund or the Long-Term Letter of Credit. The requirements of this paragraph shall apply whether the trust fund is established pursuant to paragraph 103(a), 103(b)(ii), 103(b)(v), or 109.

108. **Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired.** Upon the occurrence of default by Honeywell, after the Special Master's appointment has expired, Riverkeeper may move the Court on an expedited basis for an order to withdraw funds from the trust fund or to draw on the Long-Term Letter of Credit. Default shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 103(b)(iv) to deliver a replacement Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 30 days after written notice by Riverkeeper to Honeywell of the alleged material failure, unless Honeywell cures the alleged breach within the 30-day notice period or such longer period as the Parties may agree to or the Court may order;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if the involuntary filing is not dismissed within 60 days; the appointment of a custodian, receiver, liquidator, trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 108(c), if Honeywell fails to provide assurance to Riverkeeper, and the Court, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

109. **Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default.** If the Court grants any motion by Riverkeeper or pursuant to paragraph 108 to draw on the Long-Term Letter of Credit, the sum approved by the Court's order granting the motion shall be

paid from the Long-Term Letter of Credit into a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

110. **Use of the Trust Fund in the Event of Honeywell's Default.** In the event of Honeywell's default, as defined in paragraphs 108(a) through 108(d), the money in the trust fund established pursuant to paragraph 103(a) shall be available to meet the obligations of paragraph 102(a), as well as for payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

111. **Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109.** In the event that a trust fund is established pursuant to paragraph 99, 103(b)(ii), 103(b)(v), or 109, the money in the trust fund shall be available to meet the obligations of paragraph 102(a), as well as for the payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

112. **Termination of the Long-Term Financial Assurances.** Honeywell's obligations under Article III.K shall be terminated and the long-term financial assurance mechanisms shall be terminated when the Court finds that no hexavalent or total chromium contamination remains in the Open Space AOC or on the Site, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive

standards for Unrestricted Use in place at the time, whichever is more restrictive. Upon determining that long-term financial assurances may be terminated, the Court shall order that any Long-Term Letter of Credit may be withdrawn in its entirety and any trust fund may be terminated. In conjunction with its order terminating any trust fund, the Court in its discretion shall designate a recipient(s) of any remaining trust funds.

## ARTICLE IV: TERMINATION

113. **Termination of this Consent Decree**. This Consent Decree shall terminate upon the withdrawal of any Party as provided for in this paragraph. Any Party may elect to withdraw from this Consent Decree due to the occurrence of one or more of the following events, provided that such Party provides written notice of withdrawal to the other Parties pursuant to paragraph 118:

(a) The Court fails to enter this Consent Decree or this Consent Decree is determined to be invalid on appeal; or

(b) NJDEP takes one of the following actions with respect to the Remedial Action Work Plan:

(i) Rejects or fails to approve the Remedial Action Work Plan for the Chromium Remedy within 180 days of submission of the plan;

(ii) Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in more than a 50% increase in the estimated costs of the Chromium Remedy as set forth in Article III; or

(iii)Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in a substantial reduction of the protection of human health and/or the environment.

114. **Procedures for Withdrawal and Termination.** Any Party electing to withdraw pursuant to paragraph 113 and thereby terminate this Consent Decree shall provide written notice of such withdrawal and termination to all other Parties within 30 days of the occurrence giving rise to the decision to withdraw. If any Party objects to termination of the Consent Decree, or believes that the conditions set forth in paragraph 113 have not been met, such objecting Party may move the Court for an expedited hearing on the issue of whether the conditions for termination have been effectuated.

115. **Good-Faith Obligation to Avoid Termination.** The Parties agree that they will each endeavor to fulfill the terms of this Consent Decree, that they will work diligently and in good faith to meet their obligations hereunder, and that they will promptly and timely take all reasonable steps to give effect to this Consent Decree and to avoid termination under paragraph 113.

116. **Effect of Termination.** If this Consent Decree is terminated pursuant to paragraph 113, the Consent Decree shall no longer be binding on the Parties and shall be of no further effect. In the event that this Consent Decree is terminated by one or more Parties pursuant to paragraph 113, each Party to this Consent Decree reserves all of its rights, claims, and defenses (both legal and factual) against the other Parties with respect to the matters at issue in the Consolidated Litigation and each Party remains free to pursue such rights, claims, and defenses.

## ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC

117. **Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC.** The transfer of title of Study Area 6 South and Study Area 7 properties to Bayfront Redevelopment LLC pursuant to the Jersey City/Honeywell Consent Order and any subsequent transfers shall not impede Honeywell's obligations to (a) complete the remediation of

Study Area 7 and implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or (b) complete the Chromium Remedy and conduct long-term monitoring and fulfill its other obligations set forth in this Consent Decree. Such transfers of Study Areas 6 South and Study Area 7 shall not include a transfer of Honeywell's obligations to implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or a transfer of Honeywell's obligations under this Consent Decree, but shall include a right of access or any other right required by Honeywell to complete the remediation. Any subsequent transfer of Study Area 6 South or Study Area 7 from Bayfront Redevelopment LLC to a redeveloper or other party shall provide all necessary agreements to allow Honeywell all necessary access to Study Area 6 South and Study Area 7 for purposes of completing Honeywell's obligations with respect to Study Area 6 South under this Consent Decree and completing the Study Area 7 remediation and implementing the Final Judgment and subsequent orders in *ICO v. Honeywell*.

## ARTICLE VI: NOTICE

118. **Notice**. Any and all notices given in connection with this Consent Decree shall be deemed adequately given only if in writing and addressed to the Party for whom such notices are intended at the addresses set forth in this paragraph. All notices shall be sent by Federal Express or other nationally recognized overnight messenger service or by first-class registered or certified mail, postage prepaid, return receipt requested. A written notice shall be deemed to have been given to the recipient party on the earlier of (a) the date it shall be delivered to the address set forth in this paragraph; (b) the date delivery shall have been refused at the address set forth in this paragraph; or (c) with respect to notices sent by mail, the date as of which the postal service shall have indicated such notice to be undeliverable at the address set forth in this paragraph.

Any and all notices referred to in this Consent Decree, or which any Party desires to give to the other, shall be addressed as follows:

If to Honeywell and/or
Bayfront Redevelopment LLC :

Tom Byrne, Esq.
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-2775

With copies to:

John Morris
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-4003

If to Jersey City:

William Matsikoudis
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NJ 07305
(201) 547-4667

If to Riverkeeper:

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th St., N.W.
Washington, DC 20005-4632
(202) 682-2100

Any party may change its designated recipients or addresses for notice in this paragraph by providing written notice of such change to all other Parties.

## ARTICLE VII: RIVERKEEPER'S ATTORNEYS' FEES

119. **Payment of Past Fees and Expenses.** Within 30 days of the entry of this Consent Decree, Honeywell shall pay Terris, Pravlik & Millian, LLP the sum of $813,000.00 which represents the following:

(a) A compromise of the attorneys' fees incurred by Riverkeeper in the litigation of Study Area 6 South portion of *Riverkeeper v. Honeywell* through August 31, 2008; and

(b) $353,746.67 in out-of-pocket expenses representing a portion of the expenses incurred by Riverkeeper in *Riverkeeper v. Honeywell* from the inception of the litigation after deducting the expenses paid pursuant to the Sediment Consent Order, the Deep Groundwater Consent Order, and the Study Area 6 North Consent Decree.

(c) Payment of the sum of $813,000.00 shall be in full satisfaction of all obligations, duties, and responsibilities of Honeywell with respect to the $879,317.92 in fees and expenses that Riverkeeper claimed with regard to the above described fees and expenses.

120. **Future Fees and Expenses.** Honeywell shall reimburse Riverkeeper's attorneys for reasonable fees and expenses incurred: (a) in negotiating this Consent Decree after August 31, 2008; (b) in the monitoring and enforcement of this Consent Decree; and (c) in participation in the Special Master process established pursuant to this Consent Decree. Honeywell shall also reimburse Riverkeeper for reasonable attorneys' fees and expenses for Riverkeeper's review of and participation in the Long-Term Monitoring Plan and monitoring and enforcement of this Consent Decree following the term of the Special Master. In the event that any dispute arises between the Parties under this Consent Decree that must be resolved by the Court, Riverkeeper shall be entitled to recover its attorneys' fees and expenses for litigation of the dispute to the extent allowed by federal law. Riverkeeper and Honeywell shall use the same informal procedure for attempting to settle fees issues as has been used for post-judgment monitoring fees in *ICO v. Honeywell*. In the event that Riverkeeper and Honeywell are unable to reach a settlement on fees, Riverkeeper shall apply to the Court for an award of attorneys' fees and expenses. If Honeywell objects to only a portion of the Riverkeeper's statement of attorneys' fees and expenses, Honeywell shall pay the undisputed portion within 60 days of Riverkeeper's submittal of the statement to Honeywell. The Court shall resolve any objections to

Riverkeeper's statement of attorneys' fees and expenses and shall enter an appropriate Order. In the event of Honeywell's default, Riverkeeper may seek attorneys' fees from any trust fund or court registry funds established pursuant to the financial assurances provisions of this Consent Decree.

## ARTICLE VIII: MISCELLANEOUS PROVISIONS

121. **Force Majeure.** Force Majeure, for the purposes of this Consent Decree, is defined as an event arising from causes beyond the control of any Party or Parties (or their agents, contractors, subcontractors, representatives, or assigns) which could not have been overcome by reasonable diligence and which delays or prevents the performance of any obligation under this Consent Decree. Examples of events which may constitute force majeure include the refusal of any federal or state governmental authority to grant a permit or authorization necessary for the completion of actions required by this Consent Decree, floods, hurricanes, tornadoes, and other extraordinary weather events, earthquakes and other natural disasters, terrorist attacks, war, and other national emergencies. Examples of events that are not force majeure events include normal inclement weather, increased costs or expense, the failure to timely and fully apply for a permit or authorization necessary for the completion of actions required by this Consent Decree, or financial difficulty of any Party. The Party claiming force majeure shall bear the burden of showing an event was a force majeure event.

122. **Bayfront Redevelopment LLC as a Party.** As a signatory to this Consent Decree, Bayfront Redevelopment LLC subjects itself to the Court's jurisdiction for the purpose of enforcing this Consent Decree and agrees to be bound by this Consent Decree. This Consent Decree shall be fully enforceable against Bayfront Redevelopment LLC.

123. **Successors and Assigns.** This Consent Decree shall be binding upon and shall inure to the benefit of the successors, assigns, heirs, corporate parents, subsidiaries, and affiliates of each Party. No assignment or delegation of the obligations hereunder shall release the assigning Party from its obligations under this Consent Decree.

124. **Successors to Hackensack Riverkeeper, Inc.** In the event that Hackensack Riverkeeper, Inc. disbands or otherwise ceases operations, it shall assign its rights under this Consent Decree to another qualified nonprofit organization. A nonprofit organization shall be qualified for assignment under this Consent Decree if it is a charitable organization under Section 501(c)(3) of the Internal Revenue Code or its substantial equivalent and has an established record of working to enhance or preserve the ecology, natural habitat, or environment. Any such assignment shall be subject to approval by the Court and Honeywell shall have the right to object to any proposed assignment. Any successor organization shall have the duty to assign its rights under this Consent Decree to another qualified nonprofit organization in the event that the successor disbands or otherwise ceases operations. In the event that a successor is not appointed at any given time, the New Jersey Attorney General or equivalent officer shall appoint a successor subject to approval by the Court and objection by Honeywell.

125. **Reservation of Rights and Claims.** Except as set forth expressly herein, this Consent Decree does not affect in any way any of the Parties' claims or defenses against third parties who have not signed the Consent Decree.

126. **Governing Law and Continuing Jurisdiction.** The Court shall retain jurisdiction over the matters addressed in this Consent Decree for purposes of enabling the Parties to apply to the Court for any further order as may be necessary to construe, carry out, or enforce the terms of this Consent Decree. This Consent Decree shall be interpreted and enforced under the laws of

the United States and the State of New Jersey by the United States District Court for the District of New Jersey.

127. **Construction.** Questions regarding the interpretation of this Consent Decree shall not be resolved against any Party on the ground that this Consent Decree has been drafted by that Party. This Consent Decree is the result of review, negotiation, and compromise by each Party.

128. **Authority to Enter into Agreement.** The undersigned representative for each Party represents, certifies, and warrants that he or she is duly authorized by the Party whom he or she represents to enter into the terms of this Consent Decree and bind such Party legally to this Consent Decree.

129. **Measures to Effectuate This Consent Decree.** Jersey City shall take all appropriate steps to ensure that commitments it has agreed to with regard to the Open Space AOC have been duly considered, ratified, and approved. Such steps include consideration of such commitments and an effectuating ordinance at a meeting of the City Council, open to the public, at which members of the public have the opportunity to comment on all aspects of the commitments made by Jersey City..

130. **Modifications.** This Consent Decree may be modified by mutual agreement of the Parties but such agreement must be in writing, duly and properly signed by all Parties, and shall be submitted to the Court for approval.

131. **Severability.** Each of the provisions in paragraph 74 of this Consent Decree shall be deemed severable and, in the event that one or more of such provisions is deemed invalid or unenforceable, it shall not affect the validity or enforceability of the other provisions of the Consent Decree.

132. **Signatures.** This Consent Decree may be signed simultaneously or in counterparts by the respective signatories, which shall be as fully valid and binding as if a single document was signed by all of the signatories. This Consent Decree may be signed electronically by any or all signatories, and such electronic signature shall be as fully valid and binding as a hand-written signature.

Consented to and approved for entry:

*s/Aurelio Vincitore*

William Matsikoudis
Aurelio Vincitore
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NY 07305
(201) 547-4667

*Counsel for the City of Jersey City*

*s/ David Sheehan*

David Sheehan
Baker Hostetler
45 Rockefeller Plaza
11th Floor
New York, NY 10111
(212) 589-4200

Michael D. Daneker
Arnold & Porter LLP
555 12th Street N.W.
Washington, DC 20004
(202) 942-5000

*Counsel for Honeywell International Inc. and Bayfront Redevelopment LLC*

*s/ Edward Lloyd*

Edward Lloyd
Columbia Law School
435 West 116th Street, Room 831
New York, NY 10027
(212) 854-4376

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th Street N.W.
Washington, DC 20005-4632
(202) 682-2100

*Counsel for the Hackensack Riverkeeper, William Sheehan, Reverend Winston Clarke, and Lawrence Baker*

APPROVED AND ENTERED as an Order of this Court this ___ day of _____, 2012.

Hon. Dennis M. Cavanaugh
United States District Judge

## EXHIBITS

**Exhibit A:** Remedial AOC's and Remedial Approach Map

**Exhibit B:** NJDEP Chromium Policy

**Exhibit C:** Conservation Restriction

**Exhibit D:** Deed Notice

**Exhibit E:** Additional Boring Locations

# Deed Notice

*Dated: _____, 2017*

**BAYFRONT REDEVELOPMENT LLC**

Grantor(s).

*Record and return to:*

**Waters, McPherson, McNeill, P.C.**
**P.O. Box 1560**
**300 Lighting Way**
**Secaucus, New Jersey 07096-1560**

**ATTN: _____, Esq**

**DRAFT DEED NOTICE**

IN ACCORDANCE WITH N.J.S.A. 58:10B-13, THIS DOCUMENT IS TO BE RECORDED IN THE SAME MANNER AS ARE DEEDS AND OTHER INTERESTS IN REAL PROPERTY.

Prepared by: _____
[Signature]

_____
[Bayfront Redevelopment LLC]

Recorded by:

_____
[Signature, Officer of County Recording Office]

_____
[Print name below signature]

# DEED NOTICE CONCERNING CONTROLS INSTALLED FOR CHROMIUM CONTAMINATION UNDERLYING THE PROPERTY

This Deed Notice is made as of the __ day of _____, 2017, by ***Bayfront Redevelopment LLC, whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950***. Owner shall mean Bayfront Redevelopment LLC together with its successors and assigns, including all successors in interest in the Property which is the subject of this Deed Notice as described fully below. The "Property" (also referenced herein as the "Restricted Area(s)" and the "Deferred Area") shall consist of those lands particularly described by metes and bounds in Exhibit A-2 attached hereto.

1. THE PROPERTY. Bayfront Redevelopment LLC is the current owner in fee simple of certain real property designated as a portion of ***Block 24601, Lot 8 on the tax map of the City of Jersey City, Hudson County, New Jersey***[1]; the New Jersey Department of Environmental Protection Program Interest Number for the contaminated site which includes this property is ***Hudson County Chromate Site No. 124 Program Interest ("PI") # G000008741*** (NJDEP PI# for non-chromium-related contaminants at the Property is #745719). Site 124 is part of Study Area 6 South ("SA-6

[1] All references to Block 24601 Lot 8 in this Deed Notice shall mean the applicable portion of Block 24601 Lot 8 as shown in the metes and bounds description, regardless of whether the word "portion(s)" is specifically called out or not.

South"). The Property is located adjacent to and along Route 440 as shown on Exhibit B-1 attached hereto. The Property shall constitute a "Deferred Area" as defined in Paragraph 3 that will be remediated for hexavalent chromium contamination pursuant to the First Amended Consent Decree Regarding the Remediation and Redevelopment of Study Area 6 South ("Consent Decree") which is attached hereto as Appendix I and is entered as an order of the Court in the following consolidated actions *JCMUA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-05955; *JCIA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-5993; and *Hackensack Riverkeeper, Inc. v. Honeywell International, Inc.,* D.N.J., Civ. No. 06-22 (consolidated under Civ. No. 95-2097). The Consent Decree restricts transfer, use and development of the Property. To the extent that there is any conflict or inconsistency between the terms of this Deed Notice and the terms of the Consent Decree, the Consent Decree shall govern.

2. REMEDIATION.

i. The Department's Bureau of State Case Management (BCM) is the entity within the Department that is responsible for the oversight of the chromium remediation of SA-6 South and the Property. The matter was Hudson County Chromate Site No. 124 PI# G000008741. The Department has approved this Deed Notice as an institutional control for the Property, which is part of the remediation of the Property.

ii. N.J.A.C. 7:26-C-7 requires the Owner, among other persons, including the responsible party Honeywell International Inc. ("Honeywell") to obtain a soil remedial action permit for the soil remedial action at the Property. That permit will contain the monitoring, maintenance and biennial certification requirements that apply to the Property.

3. SOIL AND GROUNDWATER CONTAMINATION. Honeywell, a corporation of the State of Delaware, licensed to do business in the State of New Jersey whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950, has remediated SA-6 South to address chromium-related soil and shallow groundwater contamination, except for the Property and certain other deed noticed areas where engineering controls were implemented. The Remedial Action Work Plan ("RAWP") for chromium remedial actions was approved by the Department on March 24, 2009 for Hudson County Chromate Site Nos. 073, 124, 125, 134, and 140, which includes the Property. Remedial actions were further approved pursuant to the Consent Decree.

Under both the Consent Decree and the RAWP, soil contamination remains in the Property at concentrations that do not allow for the unrestricted use of the Property. A Remedial Action Report ("RAR") for SA-6 South was submitted to the Department on February 8, 2017. The Department approved the RAR on March 30, 2017. A Construction Completion Report ("CCR") for SA-6 South to document the implementation of the Chromium Remedy pursuant to Article III of the Consent Decree (the "Chromium Remedy") to address chromium-impacted soil and groundwater for SA-6 South was entered by the Court on [DATE], [CITE TO DOCKET AND DOCKET #].

The Property, also known as the Deferred Area, is an approximately 15-foot wide by 88-foot long, 1,315 square foot area on SA-6 South between the Route 440 Right of Way ("ROW") and the hydraulic barrier along the eastern edge of the SA-6 South Open Space AOC. Public Service

Electric & Gas ("PSE&G") owns and operates a gas main on the Property, thus, excavation of chromium-impacted soil from the Property was not possible. Excavation of residual chromium contamination proximate to the gas line on the Property will be deferred by Honeywell until the gas line is relocated as part of the Route 440 Road Widening Project. Once the chromium-impacted soils on the Property are removed consistent with Article III of the Consent Decree, this deed notice will be terminated consistent with the requirements of paragraph 13 below. The provisions of the Long Term Monitoring Plan ("LTMP"), developed pursuant to the Consent Decree, will apply to the Property.

The soil contamination is described, including the type, concentration and specific location of such contaminants, in Exhibit B, which is attached hereto and made a part hereof. Groundwater contaminant concentrations and restrictions for SA-6 South in its entirety are addressed in the Classification Exception Area (CEA) approved by the NJDEP on February 16, 2012 and in a forthcoming Remedial Action Permit for Groundwater (recent groundwater samples for the Property do not indicate shallow groundwater contamination). As a result of the remaining soil contamination, there is a statutory requirement for this Deed Notice and engineering controls in accordance with N.J.S.A. 58:10B-13. Under the terms of the Consent Decree and this Deed Notice, Honeywell is responsible for monitoring and maintaining the soil remediation for the Property in perpetuity or until remediation is implemented that renders this Deed Notice unnecessary.

4. CONSIDERATION. In accordance with the Department's approval of the chromium RAWP for the remediation for the Hudson County Chromate Site Nos. 073, 124, 125, 134, and 140 which includes the Property, and in consideration of the terms and conditions of that approval, and in accordance with the Consent Decree, and other good and valuable considerations, Owner has agreed to subject the Property to certain statutory and regulatory requirements which impose restrictions upon the use of the Property, to restrict certain uses of the Property, and to provide notice to subsequent owners, lessees and operators of the restrictions and the monitoring, maintenance, and biennial certification requirements outlined in this Deed Notice and required by law, as set forth herein.

5A. RESTRICTED AREAS. Due to the presence of these contaminants, Owner has agreed, as part of the remedial action for the Property, to restrict the use of the Property (the "Restricted Areas"); a narrative description of these restrictions, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C, which is attached hereto and made a part hereof. Owner will develop a binder containing a list of these restrictions which will be maintained either at onsite trailers or within the Groundwater Treatment Plant building, available for review and inspection by governmental enforcement officials if requested.

5B. RESTRICTED LAND USES. The following land use restrictions apply to the Property:

i. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(10), prohibits the conversion of a contaminated site, remediated to non-residential soil remediation standards that require the maintenance of engineering or institutional controls, to a child care facility, or public, private, or charter school without the Department's prior written approval, unless a presumptive remedy is implemented;

ii. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(12), prohibits the conversion of a landfill, with gas venting systems and or leachate collection systems, to a single family residence or a child care facility without the Department's prior written approval; and

iii. The Consent Decree, paragraph 9, prohibits the unrestricted use of the Property until the Chromium Remedy set forth in Article III of the Consent Decree is implemented.

5C. ENGINEERING CONTROLS. Due to the presence and concentration of these contaminants, the Owner has also agreed, as part of the remedial action for the Property, to the placement of certain engineering controls on the Property. The engineering controls include clean cover materials to a depth of approximately 6-inches below ground surface A narrative description of these engineering controls, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C. Honeywell shall be responsible for monitoring and maintenance of engineering controls and biennial certification requirements as specified in the Consent Decree, the LMTP, and Paragraphs 8A and 8B herein.

5D. LONG TERM MONITORING PLAN. Pursuant to the Consent Decree, Honeywell has developed an LTMP which sets forth requirements for monitoring, maintaining, and repairing or replacing the soil and groundwater chromium remedial measures including engineering controls within the Property, and requirements for notification and reporting pursuant to the Consent Decree, Deed Notice, and Soil Remedial Action Permit. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950. This Deed Notice is appended to the LTMP.

5E. WORKER TRAINING MATERIALS. All maintenance workers engaged in maintenance at the Property shall be trained in maintenance procedures that do not jeopardize the integrity of the engineering controls. Workers shall be trained using material developed by Honeywell pursuant to the Consent Decree.

6A. CHANGE IN OWNERSHIP AND REZONING.

i. The Owner and the subsequent owners and lessees, shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. The Owner and the subsequent owners shall provide written notice to the Department of Environmental Protection on a form provided by the Department and available at www.nj.gov/srp/forms within thirty (30) calendar days after the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property.

iii. The Owner and the subsequent owners shall provide written notice to the Department, on a form available from the Department at www.nj.gov/srp/forms, within thirty (30) calendar days after

the owner's petition for or filing of any document initiating a rezoning of the Property to residential.

6B. SUCCESSORS AND ASSIGNS. This Deed Notice shall be binding upon Owner and upon Owner's successors and assigns, and subsequent owners, lessees, and operators while each is an owner, lessee, or operator of the Property.

7A. ALTERATIONS, IMPROVEMENTS, AND DISTURBANCES.

i. The Owner and all subsequent owners and lessees shall notify any person of whom it has knowledge, including, without limitation, tenants, employees of tenants, developers, and contractors, intending to conduct invasive work or excavate within the Property, of the nature and location of known contamination in the Property, and, of the precautions necessary to protect the engineering controls and minimize potential human exposure to contaminants.

ii. Except as provided in the Consent Decree and Paragraph 7B below, no person shall make, or allow to be made, any alteration, improvement, or disturbance in, to, or about the Property which disturbs any engineering control at the Property except as (a) permitted in the Consent Decree and (b) without first obtaining Soil Remedial Action Permit modification from the Department. Nothing herein shall constitute a waiver of the obligation of any person to comply with all applicable laws and regulations including, without limitation, the applicable rules of the Occupational Safety and Health Administration.

iii. Notwithstanding subparagraph 7A.ii.(b), above, a Soil Remedial Action Permit modification is not required for any alteration, improvement, or disturbance provided that:

(A) Such action is taken in conformance with the Consent Decree and this Deed Notice; and

(B) The Department of Environmental Protection is notified of the activity by calling the DEP Hotline, at 1-877-WARN-DEP or 1-877-927-6337, within twenty-four (24) hours after the beginning of each alteration, improvement, or disturbance; and

(C) Honeywell is notified of the activity by calling 855-727-2658; and

(D) Honeywell and/or the owner restores any disturbance of an engineering control to pre-disturbance conditions, consistent with the requirements of the Consent Decree and LTMP, within sixty (60) calendar days after the initiation of the alteration, improvement or disturbance; and

(E) All applicable worker health and safety laws and regulations are followed during the alteration, improvement, or disturbance, and during the restoration; and

(F) Appropriate measures are taken so that human exposure, and exposure of the environment outside the containment of the engineering controls, to contamination in excess of the applicable remediation standards does not occur; and

(G) The next biennial certification includes a description of the nature of the alteration, improvement, or disturbance, the dates and duration of the alteration, improvement, or disturbance, the name of key individuals and their affiliations conducting the alteration, improvement, or disturbance, a description of the notice the Owner gave to those persons prior to the disturbance, the amounts of soil generated for disposal, if any, the final disposition and any precautions taken to prevent exposure.

7B. EMERGENCIES. In the event of an emergency which presents, or may present, an unacceptable risk to the public health and safety, or to the environment, or immediate environmental concern, see N.J.S.A. 58:10C-2, any person may temporarily breach an engineering control provided that:

i. The Department of Environmental Protection is immediately notified of the emergency, by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

ii. Immediately after notifying NJDEP, Honeywell is notified of the emergency by calling 855-727-2658; and

iii. Both the actual disturbance and the time needed for the disturbance are limited to the minimum reasonably necessary to adequately respond to the emergency; and

iv. All measures necessary to limit actual or potential, present or future risk of exposure to humans or the environment to the contamination are implemented; and

v. The Department of Environmental Protection is notified when the emergency has ended by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

vi. Honeywell is notified when the emergency has ended by calling 855-727-2658; and

vii. Honeywell restores the engineering control to the pre-emergency conditions, consistent with the requirements of the Consent Decree and LTMP, as soon as possible, and submits a written report to the Department of Environmental Protection of such emergency and restoration efforts within sixty (60) calendar days after completion of the restoration of the engineering control. The report must include all information pertinent to the emergency, potential discharges of contaminants, and restoration measures that were implemented, which, at a minimum, should specify: (a) the nature and likely cause of the emergency, (b) the potential discharges of or exposures to contaminants, if any, that may have occurred, (c) the measures that have been taken to mitigate the effects of the emergency on human health and the environment, (d) the measures completed or implemented to restore the engineering control, and (e) the changes to the engineering control or site operation and maintenance plan to prevent recurrence of such conditions in the future. Honeywell shall submit the report to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring

Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413

8A. MONITORING AND MAINTENANCE OF DEED NOTICE, AND PROTECTIVENESS CERTIFICATION. The persons in any way responsible, pursuant to the Spill Compensation and Control Act, N.J.S.A. 58:10-23.11a et seq., for the hazardous substances that remain at the Property, the persons responsible for conducting the remediation, Honeywell, the Owner, and the subsequent owners, lessees, and operators, shall monitor and maintain this Deed Notice. The subsequent owners, lessees and operators have this obligation only during their ownership, tenancy, or operation. Honeywell shall certify to the Department on a biennial basis that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the deed notice shall include all of the following:

i. Monitoring and maintaining this Deed Notice according to the requirements in Article III of the Consent Decree, and Exhibit C herein, to ensure that the remedial action that includes the Deed Notice continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes this Deed Notice, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

8B. MONITORING AND MAINTENANCE OF ENGINEERING CONTROLS, AND PROTECTIVENESS CERTIFICATION. Honeywell shall maintain all engineering controls at the Property and certify to the Department on a biennial basis that the remedial action of which each engineering control is a part remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the engineering controls shall include the following:

i. Monitoring and maintaining each engineering control according to the requirements in Article III of the Consent Decree, the LTMP, and Exhibit C herein, so that the remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to

the Department pursuant to iii, below, so that the remedial action that includes the engineering control remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes the engineering control, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

9. ACCESS. The Owner, subsequent owners, lessees, and operators, agree to allow the Department, its agents and representatives access to the Property to inspect and evaluate the continued protectiveness of the remedial action that includes this Deed Notice and to conduct additional remediation to ensure the protection of the public health and safety and of the environment if the persons responsible for monitoring the protectiveness of the remedial action, as described in Paragraph 8, above, fail to conduct such remediation pursuant to this Deed Notice as required by law. The Owner, and the subsequent owners and lessees, shall also cause all leases, subleases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring that all holders thereof provide such access to the Department.

10. NOTICES.

i. Owner shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this paragraph shall be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. Honeywell or the Owner shall notify any person intending to conduct invasive work or excavate within the Property of the nature and location of contamination and, of the precautions necessary to minimize potential human exposure, and exposure of the environment outside the containment of the engineering controls, to contaminants.

iii. Owner shall provide written notice to the Department of Environmental Protection at least thirty (30) calendar days before the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property. Any such conveyance, grant or gift must be consistent with the terms of the Consent Decree.

iv. Owner shall provide written notice to the Department within thirty (30) calendar days following the Owner's receiving notice of any petition for a rezoning of the Property. Any such rezoning must be consistent with the terms of the Consent Decree. The Owner shall submit the written notice to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program

P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413.

11. ENFORCEMENT OF VIOLATIONS.

i. This Deed Notice itself is not intended to create any interest in real estate in favor of the Department of Environmental Protection, nor to create a lien against the Property, but merely is intended to provide notice of certain conditions and restrictions on the Property and to reflect the regulatory and statutory obligations imposed as a conditional remedial action for this Property.

ii. The restrictions provided herein may be enforceable by the Department against any person who violates this Deed Notice. To enforce violations of this Deed Notice, the Department may initiate one or more enforcement actions pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C, and require additional remediation and assess damages pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C.

iii. This Deed Notice is also enforceable in the United States District Court for the District of New Jersey by all residents, owners, lessees, and all commercial tenants on Study Areas 6 and 7 pursuant to paragraphs 80 and 83 of the Consent Decree.

12. SEVERABILITY. If any court of competent jurisdiction determines that any provision of this Deed Notice requires modification, such provision shall be deemed to have been modified automatically to conform to such requirements. If a court of competent jurisdiction determines that any provision of this Deed Notice is invalid or unenforceable and the provision is of such a nature that it cannot be modified, the provision shall be deemed deleted from this instrument as if the provision had never been included herein. In either case, the remaining provisions of this Deed Notice shall remain in full force and effect.

13. MODIFICATION AND TERMINATION.

i. Any person may request in writing, at any time, that the Department modify this Deed Notice where performance of subsequent remedial actions, a change of conditions at the Property, or the adoption of revised remediation standards suggest that modification of the Deed Notice would be appropriate, provided that any such modification is consistent with the requirements of the Consent Decree.

ii. Any person may request in writing, at any time, that the Department terminate this Deed Notice because the conditions which triggered the need for this Deed Notice are no longer applicable.

iii. Any person seeking a modification or termination of this Deed Notice must also have such modification approved by the United States District Court for the District of New Jersey pursuant to the Consent Decree until such time as the Consent Decree terminates with regard to the Property pursuant to the Consent Decree.

iv. If the United States District Court for the District of New Jersey and NJDEP have concluded that this Deed Notice shall be modified or terminated, such modification or termination will only be effective upon the filing of a Termination of Deed Notice, available at N.J.A.C. 7:26C Appendix C, with the office of the Register of Deeds of Hudson County, New Jersey, expressly modifying or terminating this Deed Notice.

v. Within thirty (30) calendar days after the filing of a Termination of Deed Notice, the owner of the Property shall apply to the Department for modification or termination of the Soil Remedial Action Permit pursuant to N.J.A.C. 7:26C-7.

vi. This Deed Notice may be modified only if it has first been terminated pursuant to subparagraphs 13v above, and upon filing of a modified Deed Notice, executed by the Owner of the Property, in the office of the Register of Deeds of Hudson County, New Jersey.

14A. EXHIBIT A. Exhibit A includes the following maps of the Property and the vicinity:

i. Exhibit A-1: Vicinity Map - A map that identifies by name the roads, and other important geographical features in the vicinity of the Property;

ii. Exhibit A-2: Metes and Bounds Description - A metes and bounds description of the Property, including reference to tax lot and block numbers for the Property and a Tax Map;

iii. Exhibit A-3: Property Map - A scaled map of the Property, scaled at one inch to 200 feet or less, and if more than one map is submitted, the maps shall be presented as overlays, keyed to a base map; the map(s) shall include diagrams of major surface topographical features such as buildings, roads, and parking lots. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as buildings, roads, and parking lots.

14B. EXHIBIT B. Exhibit B includes the following descriptions of the Restricted Areas:

i. Exhibit B-1: Restricted Area Map - Maps for the Property that include, as applicable:

(A) As-built diagrams of each engineering control, including caps, fences, hydraulic barrier walls, ground water monitoring wells, and ground water pumping system;

(B) As-built diagrams of any buildings, roads, parking lots and other structures that function as engineering controls; and

(C) Designation of all soil and/or sediment sample locations within the restricted areas that exceed any soil or sediment standard that are keyed into one of the tables described below.

ii. Exhibit B-2 (Table B-2): Restricted Area Data Tables - Table for the Property that includes:

(A) Sample location designation from Restricted Area maps (Exhibit B-1);

(B) Sample elevation based upon mean sea level;

(C) Name and chemical abstract service registry number of each contaminant with a concentration that exceeds the unrestricted use standard;

(D) The restricted and unrestricted use standards for each contaminant in the table; and

(E) The remaining concentration of each contaminant at each sample location at each elevation (or if historic fill, include data from the Department's default concentrations at N.J.A.C. 7:26E-4.6, Table 4-2).

14C. EXHIBIT C. Exhibit C includes narrative descriptions of the institutional controls and engineering controls as follows:

i. Exhibit C-1A through C-1C. Exhibit C-1A: Deed Notice as Institutional Control; Exhibit C-1B: Consent Decree as Institutional Control (attached); Exhibit C-1C: Zoning as Institutional Control; Exhibit C-1 includes a narrative description of the restrictions and obligations of this Deed Notice that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
(1) Description and estimated size of the Restricted Areas as described above;
(2) Description of the restrictions on the Property by operation of this Deed Notice and the other Institutional Controls; and
(3) The objective of the restrictions;

(B) Description of the monitoring necessary to determine whether:
(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;
(2) There have been any land use changes subsequent to the filing of this Deed Notice and the other Institutional Controls or the most recent biennial certification, whichever is more recent;
(3) The current land use on the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls;
(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the Property; and
(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice and the other Institutional Controls, and conduct the necessary sampling; and

(C) Description of the following items that will be included in the biennial certification:
(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of

the remedial action that includes this Deed Notice and the other Institutional Controls;

(2) Land use at the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls; and

(3) The remedial action that includes this Deed Notice and the other Institutional Controls continues to be protective of the public health and safety and of the environment.

ii. Exhibit C-2. Exhibit C-2: Engineering Controls: Asphalt Cover; Exhibit C-2 includes a narrative description of the engineering controls as follows:

(A) General Description of the engineering control:

(1) Description of the engineering control;

(2) The objective of the engineering control; and

(3) How the engineering control is intended to function.

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering control;

(4) The engineering control is being inspected and maintained and its integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering control. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering control; and

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling.

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering control continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

15. SIGNATURES. IN WITNESS WHEREOF, Owner has executed this Deed Notice as of the date first written above.

ATTEST: , LLC

_____ By_____
[Signature] [Signature]

_____ _____
[Print name and title] [Print name and title]

STATE OF NEW JERSEY SS.:
COUNTY OF _____

I certify that on _____ ___, 2017, _____ personally came before me, and this person acknowledged under oath, to my satisfaction, that:

(a) this person is the _____ of _____, LLC, the Limited Liability Corporation named in this document;

(b) this person is the attesting witness to the signing of this document by the proper corporate officer who is the _____ of the Limited Liability Corporation;

(c) this document was signed and delivered by the Limited Liability Corporation as its voluntary act and was duly authorized;

(d) this person knows the proper seal of the Limited Liability Corporation which was affixed to this document; and

(e) this person signed this proof to attest to the truth of these facts.

_____
[Signature]

_____
[Print name and title of attesting witness]

Signed and sworn before me on _____, 20__

_____, Notary Public

_____
[Print name and title]

**EXHIBIT A**
**Deed Notice #2 SA-6 South Deferred Area Adjacent to Route 440 ROW**

**A-1 Vicinity Map**

**A-2 Metes and Bounds Description and Tax Map**

**A-3 Property Map Portion of Block 24601, Lot 8, City of Jersey City, New Jersey**

Exhibit A-1 Vicinity Map consists of a road map for the vicinity of the Property.


Exhibit A-2 consists of metes and bounds and tax map for the Property.

Exhibit A-3 Property Map consists of a figure indicating major surface features and engineering control for the Property. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as roads, walkways and other hardscape.

**Exhibit A-1**
**Site Vicinity Map**
**Jersey City, New Jersey**

EXHIBIT A-1
SITE VICINITY MAP
PORTIONS OF STUDY AREA 6 SOUTH SITE 124
JERSEY CITY, NEW JERSEY

CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




SOURCE: USGS QUADRANGLE MAP, 7.5 MIN SERIES
JERSEY CITY, NJ-NY 1967, PHOTO REVISED 1981

SITE 124 ROUTE 440
UTILITY AREA

**DRAFT**

0 1000 2000 4000
SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150450<br>*DRAWING:* 3480150450-5100-A100-2000 | |
| *PREPARED/DATE:* STR 01/28/16 | *CHECKED/DATE:* NW 01/31/17 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT A-1**
VICINITY MAP
BLOCK 24601 LOT 8
DEED NOTICE #2 SA-6 SOUTH
DEFERED AREA ADJACENT TO ROUTE 440 R.O.W.
JERSEY CITY, NEW JERSEY

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\deed notice\deed notice 2\3480150450-5100-A100-2000.dwg Fri, 10 Mar 2017 - 1:34pm scott.rudkin

**Exhibit A-2**
**Deed Notice #2 SA-6 South Deferred Area Adjacent to Route 440 ROW**

**Metes and Bounds Description of Property: See Attached**
**Tax Map: See Attached**

A-2 Metes and Bounds Description of Property Portion of Block 24601, Lot 8
City of Jersey City, New Jersey

**If there is any discrepancy between the Metes and Bounds and the tax map, or any other maps attached thereto, the Metes and Bounds prevails.**

The Property is identified as a portion of Block 24601, Lot 8 on the City of Jersey City tax maps. A copy of the current tax map which includes the SA-6 South Deferred Area Adjacent to Route 440 ROW is attached as Exhibit A-2.

MASER CONSULTING P.A.
Consulting, Municipal & Environmental Engineers
Planners ▪ Surveyors ▪ Landscape Architects

331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Tel: 732.383.1950 ▪ Fax: 732.383.1984

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**
**PROJECT NO. 10000292Q**

**DEED NOTICE AREA 2**
**BLOCK 24601 LOT 8**
**APRIL 6, 2016**

All that certain lot, tract or parcel of land situate lying and being in the City of Jersey, in the County of Hudson and State of New Jersey, and being a portion of Lot 8 Block 24601, designated as Deed Notice Area 2 as shown on an exhibit entitled, "Deed Notice Area 2, SA6 South, Block 24601, Lot 8, City of Jersey City, Hudson County, New Jersey," prepared by Maser Consulting P.A., dated April 6, 2016 and being more particularly bounded and described as follows, to wit:

**BEGINNING** at the intersection of the westerly line of New Jersey State Highway Route 440 (112 foot wide right of way), and the division line between Lot 8 Block 21901, and Lot 8 Block 24601; thence-

1. **S 24°46'55" W, 72.64 feet,** along the westerly line of New Jersey State Highway route 440 to a point of curvature; thence-

2. **SOUTHWESTWARDLY**, on an arc to the right having a radius of **152.00 feet,** and arc length of **82.00 feet** (central angle of **30°54'31"**), said arc being connected by a chord bearing **S 40° 14'10" W,** a chord distance of **81.01 feet,** along the same, to the intersection of the same with the easterly face of a hydraulic barrier wall; thence-

   Running through said Lot 8 Block 24601, along said easterly wall face the following two (2) courses:

3. **N 41°25'15" E, 32.00 feet,** thence-

4. **N 26°06'25" E, 122.87 feet** to the point and place of **BEGINNING**.


**CONTAINING:** 1,315 S.F. of land more or less or 0.030 acres of land more or less.

04/06/16

GLEN J. LLOYD, P.L.S.
NEW JERSEY PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS037598

DATE SIGNED

R:\General\Projects\2010\10000292C\Descriptions\Metes & Bounds-Deed Notice 2.docx




MASER CONSULTING P.A.
Customer Loyalty *through* Client Satisfaction
www.maserconsulting.com
Engineers ■ Planners ■ Surveyors
Landscape Architects ■ Environmental Scientists
State of N.J. Cert. of Authorization: 24GA27986500
Office Locations:
■ Red Bank, NJ ■ Albany, NY
■ Clinton, NJ ■ Chestnut Ridge, NY
■ Hamilton, NJ ■ Newburgh, NY
■ Marmora, NJ ■ Hawthorne, NY
■ Mt. Arlington, NJ ■ Lehigh Valley, PA
■ Mt. Laurel, NJ ■ Exton, PA
■ Sterling, VA ■ Philadelphia, PA
■ Norfolk, VA ■ Columbia, MD
■ Albuquerque, NM ■ Tampa, FL
Copyright © 2016 Maser Consulting P.A. All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Maser Consulting P.A.

| REV | DATE | DRAWN BY | DESCRIPTION |
|---|---|---|---|
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |

DEED NOTICE AREA 2
SA6 SOUTH

BLOCK 24601
LOT 8

CITY OF JERSEY CITY
HUDSON COUNTY
NEW JERSEY

811 PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE
Know what's below. Call before you dig.
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM


RED BANK OFFICE
Corporate Headquarters
331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Phone: 732.383.1950
Fax: 732.383.1984

| SCALE: | DATE: | DRAWN BY: | CHECKED BY: |
|---|---|---|---|
| AS SHOWN | 4/6/2016 | HA | GJL |
| PROJECT NUMBER: 10000292C | | DRAWING NAME: V-EXBT-DN-2 | |

SHEET TITLE:
DEED NOTICE EXHIBIT

SHEET NUMBER:
1 of 1

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




DRAFT

0 150 300 600

SCALE IN FEET

P:\CADD\HOBEWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710A1.dwg notice\deed notice 2\3480150450-5100-A200-2000.dwg Fri, 10 Mar 2017 - 1:34pm acott.rudeh

| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A200-2000 | |
| PREPARED/DATE: STR 01/28/16 | CHECKED/DATE: NW 01/31/17 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

EXHIBIT A-2
TAX MAP
BLOCK 24601, LOT 8
DEED NOTICE #2 SA-6 SOUTH
DEFERRED AREA ADJACENT TO ROUTE 440 R.O.W.
JERSEY CITY, NEW JERSEY

**Exhibit A-3**
**Property Map**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\GROUP\HONEYWELL\JERSEY CITY\SA @ SOUTH\3480150368\3710\3710DN\deed notice\deed notice 2\3480150450-5100-A300-2000.dwg Fri, 10 Mar 2017 - 1:34pm scott.rudkin

LEGEND

21901 BLOCK NUMBER

LOT 8 LOT NUMBER

BLOCK LINE

LOT LINE

RESTRICTED AREA

N

KELLOGG STREET

LOT 12

LOT 7

24601

LOT 8

LOT 10

LOT 9

21901

LOT 8

LOT 7

LOT 1

NEW JERSEY STATE HIGHWAY ROUTE 440

DRAFT

0 50 100 200

SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A300-2000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT A-3**<br>PROPERTY AREA MAP<br>BLOCK 24601 LOT 8<br>DEED NOTICE #2 SA-6 SOUTH<br>DEFERRED AREA ADJACENT TO ROUTE 440 R.O.W.<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16<br>CHECKED/DATE: NW 02/01/16 | | |

**EXHIBIT B**
**Deed Notice #2 SA-6 South Deferred Area Adjacent to Route 440 ROW**

**B-1 Restricted Area Maps**
**B-2 Restricted Area Data Table**
**Portion of Block 24601, Lot 8**
**City of Jersey City, New Jersey**

Exhibit B-1 Restricted Area Maps include Exhibit B-1A (Restricted Area and Soil Sample Locations), Exhibit B-1B (Cap System Detail), and Exhibit B-1C (As-Built Restoration Plan).

Exhibit B-2 is a Restricted Area Data Table indicating soil sample locations with concentrations of hexavalent chromium remaining above the level established in the New Jersey Department of Environmental Protection (NJDEP) Chromium Policy of 20 milligrams per kilogram (mg/kg).

**Restricted Area Map Notes:**

Exhibit B-1 indicates engineering controls. For soils with hexavalent chromium concentrations above 20 mg/kg, the engineering control includes an asphalt cap.


**Exhibit B-1**
**Restricted Area Maps**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\deed notice\deed notice 2\3480150450-5100-B100-2000.dwg Fri, 10 Mar 2017 - 1:35pm scott.rudkin

LEGEND

- SOIL SAMPLE LOCATION WHERE HEXAVALENT CHROMIUM > 20mg/kg (SEE EXHIBIT B2)
- 21901 BLOCK NUMBER
- LOT 8 LOT NUMBER
- BLOCK LINE
- LOT LINE
- RESTRICTED AREA




DRAFT


0 50 100 200

SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-B100-2000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT B-1A**<br>RESTRICTED AREA MAP<br>BLOCK 24601 LOT 8<br>DEED NOTICE #2 SA-6 SOUTH<br>DEFERRED AREA ADJACENT TO ROUTE 440 R.O.W.<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16<br>CHECKED/DATE: NW 01/31/17 | | |

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.


P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\S710\S71004\deed notice\deed notice 2\3480150450-5100-B200-2000.dwg Fri, 10 Mar 2017 - 1:35pm scott.rudkin





## CAP SYSTEM DETAIL
NTS

**DRAFT**

| | | |
|---|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150488<br>*DRAWING:* 3480150450-5100-B200-2000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT B-1B**<br>CAP SYSTEM DETAIL<br>BLOCK 24601 LOT 8<br>DEED NOTICE #2 SA-6 SOUTH<br>DEFERRED AREA ADJACENT TO ROUTE 440 R.O.W.<br>JERSEY CITY, NEW JERSEY |
| *PREPARED/DATE:* STR 01/25/17 \| *CHECKED/DATE:* NW 01/31/17 | | |




NOTE: NO HISTORIC FILL SHALL BE PLACED ON SA–7

TYPICAL VEGETATED SLOPE
NTS

NOTE:

1. REFER TO FIGURE 2 FOR CONSTRUCTION CONTROL GRID AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE ON THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL AS SHOWN ON THE TYPICAL VEGETATED SLOPE DETAIL. THE VEGETATED SLOPE ALONG SA–7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. EXISTING PAVEMENT WAS FIELD INSPECTED BY LSRP AND SUBJECT TO MINOR CRACK FILLING TO SATISFY HISTORIC FILL CAP REQUIREMENTS.
4. STEEL SHEETPILE WALL WAS INSTALLED AS EXCAVATION SUPPORT ALONG THIS AREA AND THEN CUT BELOW CURRENT GRADE AND LEFT IN PLACE. THE TOP OF SHEETPILE IS GENERALLY 0.5 TO 2.0 FT BELOW CURRENT GRADES.

STONE COVER
VEGETATED COVER
PAVEMENT COVER
CONCRETE COVER
STONE COVER IN PLANTER AREAS
RIPARIAN ZONE
DGA COVER
STONE TOE DRAIN
STEEL SHEETPILE WALL
STORM DRAIN PIPE
STORM DRAIN CATCH BASIN

0 80 160 FEET
SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: AS BUILT RESTORATION PLAN SA–6 SOUTH – SHEET 001 12/12/16

PROJECT NAME & LOCATION: HONEYWELL SA–6 REMEDIATION JERSEY CITY, NJ

EXHIBIT B-1C

**Exhibit B-2: Table B-2**
**Soil Sample Data Table (Hexavalent Chromium)**

**EXHIBIT B-2**

**Restricted Area Data Table**

Deed Notice #2 SA-6 South Deferred Area Adjacent to Route 440 ROW

Portion of Block 24601, Lot 8

Jersey City, New Jersey

| Location | Top of Sample Depth (feet bgs) | Elevation (feet msl) NAVD88 | Contaminant | CASR# | NJDEP Chromium SCC (mg/kg) | Soil Concentration (mg/kg) |
|---|---|---|---|---|---|---|
| 124-SB-A04 | 0 | 8 | Hexavalent Chromium | 18540-29-9 | 20 | **445J** |
| 124-SB-A04 | 2 | 6 | Hexavalent Chromium | 18540-29-9 | 20 | **81.7J** |
| 124-SB-A04 | 4 | 4 | Hexavalent Chromium | 18540-29-9 | 20 | **831J** |
| 124-SB-A04 | 6 | 2 | Hexavalent Chromium | 18540-29-9 | 20 | **8250J** |

**Notes:**

Results reported in mg/kg.

**Data Qualifiers:**

J - Data indicates the presence of a compound that meets the identification criteria. The concentration given is an approximate value.

**Abbreviations:**

Feet bgs - Feet below ground surface

mg/kg - milligrams per kilogram

feet msl = feet mean sea level NAVD88 - North American Vertical Datum of 1988

NJDEP Chromium SCC - New Jersey Department of Environmental Protection Chromium Soil Cleanup Criteria, revised April 2010

**EXHIBIT C**
**Deed Notice #2 SA-6 South Deferred Area Adjacent to Route 440 ROW**

**C-1 Institutional Controls**
**C-2 Engineering Controls**
**Portion of Block 24601, Lot 8**
**City of Jersey City, New Jersey**

## C-1 Institutional Controls

C-1 Deed Notice, Consent Decree (attached), Zoning as Institutional Controls: Exhibit C-1 (A through C) for that portion of Block 24601, Lot 8, City of Jersey City, New Jersey known as the Deferred Area

Exhibits C-1A and C-1B. Exhibit C-1A: Deed Notice as Institutional Control; Exhibit C-1B: Consent Decree as Institutional Control; Exhibits C-1A and C-1B include a narrative description of the restrictions and obligations of this Deed Notice and the other Institutional Controls that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
**The Property is an approximately 15-foot wide, 1,315 square foot area on SA-6 South between the Route 440 Right of Way ("ROW") and the hydraulic barrier along the eastern edge of the SA-6 South Open Space AOC. Public Service Electric & Gas ("PSE&G") owns and operates a gas main on the Property, thus, excavation of chromium-impacted soil from the Property was not possible. Excavation of residual chromium contamination proximate to the gas line on the Property will be deferred by Honeywell until the gas line is relocated as part of the Route 440 Road Widening Project. Once the chromium-impacted soils on the Property are removed consistent with Article III of the Consent Decree, this deed notice will be terminated with the requirements of paragraph 13 above. The provisions of the LTMP, developed pursuant to the Consent Decree, will apply to the Property.**

(1) Description and estimated size of the Restricted Areas as described above;

***The Property constitutes a portion of Block 24601, Lot 8. The estimated size of the Area containing chromium-impacted soils (hexavalent chromium above 20 mg/kg) as identified on Exhibit B-1 is estimated at approximately 1315 square feet or approximately 0.03 acres.***

(2) Description of the restrictions on the Property by operation of the Institutional Control;

***The Property shall only be used for activities consistent with this Deed Notice, the Consent Decree, and the applicable zoning standards. Intrusive activities (i.e., excavation or digging) that breach the engineering controls (as described in Exhibit C-2) will not be permitted on the Property except in compliance with the***

***terms of the Consent Decree and the applicable portions of the LTMP developed thereunder, and this Deed Notice. See subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies for additional information. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950.***

(3) The objective of the restrictions;

***The restrictions will prohibit contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg.***

(B) Description of the monitoring necessary to determine whether:

(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;

***Visual inspections of the Property and other monitoring as set forth in the Consent Decree and the applicable portions of the LTMP developed thereunder.***

(2) There have been any land use changes subsequent to the filing of this Deed Notice or the most recent biennial certification, whichever is more recent;

***Same as (B)(1).***

(3) The current land use on the Property is consistent with the restrictions in this Deed Notice;

***Same as (B)(1).***

(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the site; and

***Review of newly promulgated or modified requirements of applicable regulations or laws that potentially may apply to the site.***

(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***Same as (B)(4).***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) Land use at the Property is consistent with the restrictions in the Consent Decree, this Deed Notice, the applicable zoning standards; and

(3) The remedial action that includes this Deed Notice continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including evaluation of any available documents as a result of changes in land use or incidents.***
- ***A report that determines whether or not the land use at the Property has remained consistent with the restrictions in the Consent Decree, this Deed Notice*, and *the applicable zoning standards.***
- ***A report that determines whether or not the Deed Notice continues to be protective of the public health and safety and the environment.***

**C-2 Engineering Controls**
**Deed Notice #2 SA-6 South Deferred Area Adjacent to Route 440 ROW**

**Portion of Block 24601, Lot 8**
**City of Jersey City, New Jersey**

Exhibits C-2: Narrative description of the Engineering Controls including Clean Fill as follows:

(A) General Description of the engineering controls:

(1) Description of the engineering controls;

***The Engineering Controls consist of an asphalt cap.***

(2) The objective of the engineering controls; and

***The objective of the controls is to prevent contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg.***

(3) How the engineering controls are intended to function.

***The soil engineering controls are intended to function as a barrier to underlying and adjacent soils containing hexavalent chromium above 20 mg/kg within the Property. Monitoring requirements for the engineering controls are set forth in the applicable portions of the LTMP developed pursuant to the Consent Decree.***

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

***Honeywell will perform monitoring by visual inspection of the Property pursuant to the Consent Decree. Other monitoring activities shall be performed as set forth in the applicable portions of the LTMP developed pursuant to the Consent Decree.***

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

***Same as (B)(1) above.***

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering controls;

***Same as (B)(1) above. Also, see the Consent Decree subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies for additional information.***

(4) The engineering controls are being inspected and maintained and their integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

***Same as (B)(1) above.***

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering controls. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering controls; and

***Records of the inspections are to be maintained as listed in (5). Other monitoring activities shall be performed as set forth in the applicable portions of the LTMP developed pursuant to the Consent Decree.***

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***A review of any new standards, regulations, or laws will be conducted. Should the review indicate that other activities are necessary, those activities will be listed and executed.***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering controls continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including an evaluation to determine whether or not the engineering controls are continuing to meet the original objective and intended function.***

- ***A report to determine whether or not the engineering controls continue to operate as designed.***
- ***A report to determine whether or not the engineering controls continue to be protective of the public health and safety and of the environment.***

**Appendix I**
**Consent Decree**

# APPENDIX I

UNITED STATES DISTRICT COURT
DISTRICT OF NEW JERSEY

| | |
|---|---|
| JERSEY CITY MUNICIPAL UTILITIES AUTHORITY,<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Docket No. 05-5955(DMC)<br>Consolidated under Docket No. 95-2097 (DMC) |
| JERSEY CITY INCINERATOR AUTHORITY<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Civil Action No. 05-5993<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 (DMC) |
| HACKENSACK RIVERKEEPER, INC., *et al.*<br><br>Plaintiffs,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC., *et al.*<br><br>Defendants. | Civil Action No. 06-22<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 |

**FIRST AMENDED CONSENT DECREE REGARDING REMEDIATION AND REDEVELOPMENT OF STUDY AREA 6 SOUTH**

# TABLE OF CONTENTS

**RECITALS** ..... 1

**ARTICLE I: DEFINITIONS** ..... 4

**ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED** ..... 11

**ARTICLE III: CHROMIUM REMEDIATION** ..... 12

A. GENERAL TERMS AND REQUIREMENTS ..... 12
50. Responsibility for Implementation of Chromium Remediation. ..... 12
51. Designation of Chromium Areas of Concern. ..... 12
52. Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan. ..... 12
53. General Scope of the Chromium Remedy. ..... 13
54. Development of a Schedule for the Chromium Remedy. ..... 13
B. INITIAL CHROMIUM REMEDY STEPS: DELINEATION, TREATMENT STUDY, AND REMEDIAL ACTION WORK PLAN ..... 15
55. Delineation of Development AOC. ..... 15
56. Conduct of a Treatment Study in the Development AOC . ..... 15
57. Continued Monitoring of the Treatment Study. ..... 16
58. Submission of a Remedial Action Work Plan. ..... 16
C. DEVELOPMENT AOC SOIL REMEDY ..... 16
59. Remedial Components ..... 16
60. Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium ..... 17
61. Treatment as a Remedial Component for 20 to 240 Soils ..... 18
62. Submissions Related to Site 163 ..... 20
63. Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium. ..... 20
64. Post-Treatment Monitoring for 20 to 1000 Soils ..... 21
D. OPEN SPACE AOC COMPONENTS OF THE CHROMIUM REMEDY ..... 21
65. Open Space AOC Soil Remedy ..... 21
E. DEMOLITION, GRADING, AND BACKFILL REQUIREMENTS ..... 23
66. Demolition and Grading Activities. ..... 23
67. Backfill Requirements. ..... 23
68. Vegetation of Clean Fill. ..... 23
F. GROUNDWATER COMPONENTS OF THE CHROMIUM REMEDY ..... 23
69. Shallow Groundwater Remedy for the Open Space AOC ..... 23
70. The Shallow Groundwater Remedy for the Development AOC. ..... 24
71. Off-Site Shallow Groundwater Remedy. ..... 25
72. L-Well Groundwater Remedy. ..... 26
G. PERMITS AND AUTHORIZATIONS ..... 26
73. Permits and Authorizations. ..... 26
H. LONG-TERM MONITORING, MAINTENANCE, AND PROTECTION OF ENGINEERING AND INSTITUTIONAL CONTROLS ..... 27

74. Protection of the Open Space AOC ..... 27
75. Honeywell's Ongoing Responsibility. ..... 39
76. Long-Term Monitoring Plan. ..... 39
77. Long-Term Monitoring Plan Objectives ..... 39
78. Monitoring and Remediation Under the Long-Term Monitoring Plan ..... 40
79. Monitoring and Reporting to Riverkeeper. ..... 44
80. Notice to Stakeholders ..... 44
81. Annual Letter to Riverkeeper on Notice to Stakeholders ..... 45
82. Future Notice to Stakeholders ..... 45
83. Stakeholder Enforcement. ..... 46
I. OVERSIGHT AND ENFORCEMENT BY THE SPECIAL MASTER AND NJDEP ..... 46
84. Federal Court Jurisdiction ..... 46
85. Appointment and Jurisdiction of the Special Master. ..... 46
86. Oversight of the Chromium Remedy. ..... 46
87. Retention of Professionals. ..... 53
88. Insurance for the Special Master. ..... 53
89. Reimbursement of Special Master Fees and Expenses. ..... 54
90. Expiration of Special Master's Appointment. ..... 54
J. INITIAL FINANCIAL ASSURANCES ..... 55
91. Chromium Remedy Letter of Credit ..... 55
92. Procedures for Review of the Proposed Chromium Remedy Letter of Credit ..... 56
93. Automatic Renewal. ..... 56
94. Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit ..... 57
95. Bankruptcy Protection. ..... 58
96. Exclusive Court Jurisdiction. ..... 58
97. Application of New York Law. ..... 59
98. Procedures upon Honeywell's Material Default of Its Obligations ..... 59
99. Placement of Proceeds in Court Registry Investment System Account. ..... 60
100. Termination of Chromium Remedy Letter of Credit ..... 61
K. LONG-TERM FINANCIAL ASSURANCES ..... 61
101. Long-Term Financial Assurances. ..... 61
102. Costs Subject to Long-Term Financial Assurances. ..... 61
103. Long-Term Financial Assurance Mechanisms ..... 62
104. Procedures for Review of the Proposed Long-Term Financial Assurances ..... 66
105. Temporary Maintenance of Chromium Remedy Letter of Credit. ..... 66
106. Adjustment of Amount Held in Long-Term Financial Assurances. ..... 67
107. Exclusive Court Jurisdiction. ..... 68
108. Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired: ..... 68
109. Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default ..... 69
110. Use of the Trust Fund in the Event of Honeywell's Default. ..... 70
111. Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109. ..... 70
112. Termination of the Long-Term Financial Assurances. ..... 70

**ARTICLE IV: TERMINATION** ..... 71

113. Termination of this Consent Decree ..... 71
114. Procedures for Withdrawal and Termination. ..... 72
115. Good-Faith Obligation to Avoid Termination ..... 72
116. Effect of Termination. ..... 72

**ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC** ..... 72

117. Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC. ..... 72

**ARTICLE VI: NOTICE** ..... 73

118. Notice ..... 73
119. Payment of Past Fees and Expenses ..... 74
120. Future Fees and Expenses. ..... 75

**ARTICLE VIII: MISCELLANEOUS PROVISIONS** ..... 76

121. Force Majeure. ..... 76
122. Bayfront Redevelopment LLC as a Party. ..... 76
123. Successors and Assigns. ..... 77
124. Successors to Hackensack Riverkeeper, Inc.. ..... 77
125. Reservation of Rights and Claims. ..... 77
126. Governing Law and Continuing Jurisdiction. ..... 77
127. Construction. ..... 78
128. Authority to Enter into Agreement. ..... 78
129. Measures to Effectuate This Consent Decree ..... 78
130. Modifications. ..... 78
131. Severability. ..... 78
132. Signatures. ..... 79

## RECITALS

**Whereas,** on June 30, 2003, the district court for the District of New Jersey (hereafter "the Court") issued a Final Judgment in *Interfaith Community Organization v. Honeywell International Inc.*, Civ. No. 95-2097 (DMC) (*"ICO v. Honeywell"*), ordering the remediation of an area designated by the New Jersey Department of Environmental Protection ("NJDEP") as Study Area 7 by excavation of all chromium contamination on the property, under the oversight of a court-appointed Special Master;

**Whereas**, on or about December 23, 2005, the Jersey City Municipal Utilities Authority ("JCMUA") filed litigation styled *Jersey City Municipal Utilities Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5955 (DMC), bringing claims against Honeywell International Inc. ("Honeywell") under, *inter alia*, Section 6972 of the Resource Conservation and Recovery Act ("RCRA"), and seeking remediation of chromium contamination on property then-owned by JCMUA and other relief;

**Whereas**, on or about December 28, 2005, the Jersey City Incinerator Authority ("JCIA") filed litigation styled *Jersey City Incinerator Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5993 (DMC), bringing claims against Honeywell under, *inter alia*, Section 6972 of RCRA, and seeking remediation of chromium contamination on property then-owned by JCIA and other relief;

**Whereas**, on or about January 4, 2006, the Hackensack Riverkeeper, Inc., Captain William Sheehan, Reverend Winston Clarke, and Lawrence Baker ("Riverkeeper") filed litigation styled *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.,* D.N.J., Civ. No. 06-022 (DMC), bringing a claim against Honeywell under RCRA and seeking remediation of chromium contamination to soils, groundwater, surface waters, and sediments associated with

various properties collectively designated by NJDEP as Study Areas 5, 6 North, which includes the properties formerly owned by JCMUA and JCIA, and 6 South;

**Whereas,** Study Areas 6 North and South are directly adjacent to Study Area 7 on the north and south sides, respectively;

**Whereas,** Study Area 5 is comprised of properties to the east of Study Areas 6 North, 6 South, and 7 across Route 440;

**Whereas,** Riverkeeper also named as defendants in *Riverkeeper v. Honeywell* owners of the properties comprising Study Areas 5, 6 South, and 6 North;

**Whereas,** *JCMUA v. Honeywell*, *JCIA v. Honeywell,* and *Riverkeeper v. Honeywell* were consolidated by the Court (hereinafter the "Consolidated Litigation");

**Whereas,** in the Consolidated Litigation, Riverkeeper has alleged that Honeywell bears responsibility for the presence and remediation of chromite ore processing residue ("COPR") and chromium in soils and groundwater on the Study Area 6 South property;

**Whereas,** on April 21, 2008, the Court entered the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North (hereafter "the Study Area 6 North Consent Decree") resolving issues between Honeywell, Riverkeeper, and the Jersey City Entities related to chromium contamination at Study Area 6 North;

**Whereas**, on April 21, 2008, the district court for the District of New Jersey entered the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. (hereafter "Jersey City/Honeywell Consent Order"), filed in the Consolidated Litigation simultaneously with the Study Area 6 North Decree, which resolved claims and cross-claims between Honeywell and the Jersey City Entities;

**Whereas**, on May 28, 2008, the Court entered the Consent Order on Sediment Remediation and Financial Assurances ("Sediment Consent Order"), resolving issues related to the remediation of chromium contaminated sediments in the Hackensack River in the vicinity of Study Areas 5, 6, and 7;

**Whereas**, on September 3, 2008, the Court entered the Deep Overburden and Bedrock Groundwater Remedies Consent Order (hereafter "the Deep Groundwater Consent Order") resolving all issues related to the remediation of deep overburden and bedrock groundwater in both *ICO v. Honeywell* and the Consolidated Litigation;

**Whereas,** on May 13, 2011, Plaintiffs sent Honeywell a RCRA citizen action suit notice letter with respect to Site 163, and the Parties agree that the incorporation of Site 163 into this Consent Decree resolves any claims asserted, or that could have been asserted, in the RCRA notice letter or in any RCRA citizen suit with respect to Site 163;

**Whereas**, the Parties to this Consent Decree each believe that it is in their mutual interest to move forward productively to resolve their differences so that they can implement environmental remediation at Study Area 6 South that ensures the continued protection of human health and the environment and so that Study Area 6 and Study Area 7 can be redeveloped in keeping with Jersey City's vision for a revitalized West Side;

**Whereas,** the Local Redevelopment and Housing Law, N.J.S.A. 40A:12A-1, *et seq.*, as amended and supplemented (the "Redevelopment Law") provides for municipalities to participate in the redevelopment and improvement of areas in need of redevelopment;

**Whereas**, Study Area 6 and Study Area 7 consist of parcels which by ordinance adopted by the City Council of Jersey City on February 27, 2008, have been determined to be "areas in

need of redevelopment" under the criteria of the Redevelopment Law because of conditions prevalent on those parcels;

**Whereas**, the settlement which is the subject matter of this Consent Decree contemplates the environmental remediation of Study Area 6 South and redevelopment of the parcels that comprise Study Areas 6 and 7 to create a major mixed use project in an important section of Jersey City; and

**Whereas**, each of the actions to implement this Consent Decree have been fully considered by the Honeywell, the Riverkeeper, and Jersey City as a means to accomplish the aforesaid purposes of this settlement:

NOW, THEREFORE, IT IS HEREBY ORDERED AND DECREED AS FOLLOWS:

## ARTICLE I: DEFINITIONS

For purposes of this Consent Decree, the following terms shall have the meanings set forth in this Article:

1. **"20 to 1000 Soils"** shall mean those soils containing less than 1000 mg/kg of hexavalent chromium, but greater than 20 mg/kg. **"20 to 240 Soils"** shall mean those soils containing less than 240 mg/kg of hexavalent chromium, but greater than 20 mg/kg.

2. **Bayfront Redevelopment LLC** shall have the meaning set forth in paragraph 4.1 of the Jersey City/Honeywell Consent Order.

3. **COPR** shall mean Chromite Ore Processing Residue.

4. **Chromium Remedy or Chromium Remediation** shall mean the remedy set forth in Article III.

5. **Consolidated Litigation** shall mean *Jersey City Municipal Utility Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5955 (DMC), *Jersey City Incinerator*

*Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5993 (DMC), and *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-022 (DMC).

6. The **Court** shall mean the United States District Court of the District of New Jersey, which has jurisdiction over the Consolidated Litigation.

7. **Deep Groundwater Consent Order** shall mean the Deep Overburden and Bedrock Groundwater Remedies Consent Order entered by the Court on September 3, 2008, in both *ICO v. Honeywell* and the Consolidated Litigation.

8. **Deep Groundwater Remedy** shall mean the deep overburden and bedrock groundwater pump and treat remedy as required by the Order Approving the Deep Overburden Groundwater Remediation, entered on October 6, 2006, the Stipulation on Consent Regarding the Schedule for Implementation of Deep Groundwater Remedial Actions, entered on August 15, 2008, in *ICO v. Honeywell,* and the remedies required under the Deep Groundwater Consent Order.

9. **Development Area of Concern** ("AOC") shall mean those portions of Study Area 6 South in which the hexavalent chromium concentration in the top 20 feet of soil below ground surfaces exceeds a concentration of 20 mg/kg, and for which future uses of the property may include commercial or residential development. The Open Space AOC shall not be part of the Development AOC and vice versa. The Development AOC consists of two parts: the Kellogg Street Development AOC and the Site 163 Development AOC. Collectively, the two parts shall be referred to as the "Development AOC." The approximate boundaries of the Development AOC as a whole and its two parts are shown on Exhibit A, but the boundaries may be further defined in the implementation of the Chromium Remedy. For the Kellogg Street Development AOC, remedial measures shall assume only a residential use. For the Site 163 Development AOC, remedial measures shall be implemented with the goal of unrestricted use, but limitations

on future uses (including prohibiting residential use) in some or all of the Site 163 Development AOC may be part of the remedy as set forth in paragraph 61.

10. **Hackensack River Watershed Land Trust** shall mean the dedicated fund of the Hackensack Riverkeeper, Inc., established under Section 501(c) of the Internal Revenue Code for the purpose of acquiring and preserving open space within the Hackensack River watershed and administered by the Board of Trustees of the Hackensack Riverkeeper, Inc.

11. **Honeywell** shall mean Honeywell International Inc. and its affiliates, including 425-445 Route 440 Property LLC, Kellogg Street 80 Property LLC, Kellogg Street 60 Property LLC, and Kellogg Street/440 Property LLC.

12. **Honeywell's Treatment Plant** shall mean the treatment plant currently located at 80 Kellogg Street that is used to treat, *inter alia*, chromium contaminated groundwater.

13. ***ICO v. Honeywell*** shall mean *Interfaith Community Organization v. Honeywell International Inc.*, D.N.J., Civ. No. 95-2097 (DMC).

14. **Including** shall mean including, but not limited to.

15. **JCIA** shall mean the Jersey City Incinerator Authority.

16. **JCMUA** shall mean the Jersey City Municipal Utilities Authority.

17. **Jersey City Entities** shall mean the City of Jersey City, including the Department of Public Works ("DPW") and other agencies and branches thereof, the JCIA, and the JCMUA.

18. **Jersey City/Honeywell Consent Order** shall mean the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. entered in the Consolidated Litigation on April 21, 2008.

19. **"L-Well Groundwater"** shall mean the groundwater found at the depth of the "L" wells on and near the former bowling alley property, NJDEP Site 124, located at 427 Route 440. The L-Well Groundwater is located within what has been referred to as the plume diversion area.

20. **NJDEP** shall mean the New Jersey Department of Environmental Protection.

21. **NJDEP Chromium Directive** shall mean the Chromium Directive issued by NJDEP on February 8, 2007, and attached as Exhibit B.

22. **Open Space AOC** shall mean the portion of Study Area 6 South that is identified as The Promenade park and Grand Boulevard extending from Route 440 to the Hackensack River on page 39 of the Redevelopment Plan and for which the future uses of the property shall be restricted pursuant to paragraph 74, following remediation pursuant to paragraph 65. The Development AOC shall not be part of the Open Space AOC and vice versa. The approximate boundaries of the Open Space AOC are shown on Exhibit A, and the boundaries may be further defined in the implementation of the Chromium Remedy.

23. **Party or Parties** shall mean any one or all of the signatories to this Consent Decree.

24. **RCRA** shall mean the Resource Conservation and Recovery Act, 42 U.S.C. § 6901, *et seq.*, as amended.

25. **Redevelopment Area** shall mean Study Area 6 North, Study Area 6 South, and Study Area 7, collectively.

26. **Redevelopment Law** shall mean the New Jersey Local Redevelopment and Housing Law, N.J.S.A. § 40A:12A1, *et seq.*, as amended and supplemented.

27. **Redevelopment Plan** shall mean the Bayfront I Redevelopment Plan as adopted by Jersey City on March 12, 2008.

28. **Remedial Investigation Work Plan Addendum or RIWP Addendum** shall mean the "Remedial Investigation Work Plan Addendum Study Area 6 South" submitted to NJDEP on June 27, 2008.

29. **Riverkeeper** shall mean the plaintiffs in *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-22 (DMC), and includes the Hackensack Riverkeeper, Inc., William Sheehan, Reverend Winston Clarke, and Lawrence Baker.

30. **Sediment Consent Order** shall mean the Consent Order on Sediment Remediation and Financial Assurances, entered by the Court in *ICO v. Honeywell* and this Consolidated Litigation on May 28, 2008.

31. **Shallow Groundwater** or **Shallow Level of Groundwater** shall mean groundwater above the meadow mat, groundwater at stratigraphically equivalent depths in locations where there is no meadow mat, and groundwater that is contaminated by recent contact with COPR or other chromium soil contamination above the meadow mat and subsequently flows downward through or past the meadow mat into the upper portion of the lacustrine sediments. This does not include groundwater found in the bedrock, the deep zone, or any plume of contamination that is in both the intermediate and deep zones, as those zones are defined in the Final Groundwater Investigation Report, prepared in *ICO v. Honeywell*, dated February 2007, p. 1-2.

32. **Site** shall mean Study Area 6 South.

33. **Site Preparation Activities** shall mean those activities necessary to begin implementation of the Chromium Remedy in Article III of this Consent Decree, including, if appropriate, the temporary or permanent relocation of current activities and operations conducted on Study Area 6 South.

34. **Soil** shall mean soils, historic fill, and/or COPR.

35. The **Special Master** shall mean Senator Robert G. Torricelli, appointed as the Special Master in *ICO v. Honeywell* and the Consolidated Litigation, and his successors or whomever the Court may appoint as Special Master.

36. **Stratum O** shall mean the layer composed of soft brown silty fine sand interlayered with soft gray silty clay and fine sandy to clayey silt generally located above the meadow mat below the Historic Fill and/or COPR.

37. **Study Area 5** shall mean that property comprising Sites 79, 90, 117, 153, and 184 of the Chromate Chemical Production Waste Sites designated by NJDEP, comprising approximately 42 acres and including (a) all such property owned by Bob Ciasulli consisting of Block 1291, Lot 76, and Block 1292, Lots 1F, 47, 48, 53, and 54PL, located at 540 Route 440, Jersey City, New Jersey, (b) all such property owned by Elisabeth and Rafael Rosario consisting of Block 1292, Lot 49, located at 93 Fisk Street, Jersey City, New Jersey, (c) all such property owned by Michael Vo consisting of Block 1292, Lot 50, located at 95 Fisk Street, Jersey City, New Jersey, (d) all such property owned by NJCU consisting of Block 1286, Lots 5 and 6D and Block 1286.5, Lots 1 and 2, Jersey City, New Jersey, (e) all such property owned by Inland Southeast Jersey City LLC consisting of Lot 1, Block 1285.5 located at 440 Route 440, Jersey City, New Jersey, and (f) all such property owned by 425/445 Route 440 Property LLC, consisting of Block 1289.5, Lot E, Jersey City, New Jersey.

38. **Study Area 6 North** shall mean the property comprising Sites 87 and 88 of the Chromate Chemical Production Waste Sites designated by NJDEP, which is subject to the Study Area 6 North Consent Decree.

39. **Study Area 6 North Consent Decree** shall mean the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North, entered by the Court on April 21, 2008, in the Consolidated Litigation.

40. **Study Area 6 South** shall mean (a) that property currently owned by Bayfront Redevelopment Property LLC consisting of Site 73, located at 200 Kellogg Street Jersey City, Hudson County, New Jersey; (b) that property currently owned by Bayfront Redevelopment LLC consisting of Site 134, located at 100 Kellogg Street Jersey City, Hudson County, New Jersey; (c) that property currently owned by Bayfront Redevelopment LLC consisting of Site 140 located at 80 Kellogg Street Jersey City, Hudson County, New Jersey; (d) that property currently owned by Bayfront Redevelopment LLC consisting of Site 125, located at 60 Kellogg Street Jersey City, Hudson County, New Jersey; (e) that property currently owned by Bayfront Redevelopment LLC consisting of Site 124, Jersey City, Hudson County, New Jersey; (f) that property currently owned by Kellogg St/Harsimus Cove Realty located at 150 Kellogg Street, Jersey City, Hudson County, New Jersey, (g) that property currently owned by Bayfront Redevelopment LLC located at 38 Kellogg Street, Jersey City, Hudson County, New Jersey; (h) that property currently owned by Bayfront Redevelopment LLC located at 28 Kellogg Street, Jersey City, Hudson County, New Jersey; and (i) that property currently owned by Bayfront Redevelopment LLC, consisting of Site 163, formerly the Colonial Concrete Company, located at 75 Kellogg Street in Jersey City, Hudson County, New Jersey.

41. **Study Area 6** shall mean Study Area 6 North and Study Area 6 South, collectively.

42. **Study Area 7** shall mean (a) that property currently owned by Bayfront Redevelopment LLC located at 425 and 445 Route 440, Jersey City, Hudson County, New Jersey, and (b) that

property currently owned by Bayfront Redevelopment LLC located at 465 Route 440, Jersey City, Hudson County, New Jersey.

43. **Technical Requirements for Site Remediation** shall mean the NJDEP Technical Requirements for Site Remediation, N.J.A.C. Chapter 26E, as duly and properly promulgated and amended.

44. **Unrestricted Use** shall mean that the contaminated medium is restored to a condition or quality suitable for all uses.

## ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED

45. This Court has jurisdiction over the Parties and subject matter of the Consolidated Litigation pursuant to Section 6972 of RCRA.

46. For purposes of this Consent Decree, the Riverkeeper Complaint in the Consolidated Litigation states claims upon which relief may be granted against Honeywell.

47. In the event that this Decree is not terminated by one or more Parties pursuant to paragraph 113, this Consent Decree resolves, settles, and satisfies all claims by Riverkeeper against Honeywell with respect to soils, shallow groundwater and L-Well groundwater at Study Area 6 South. This Consent Decree does not resolve any claims by Riverkeeper against Honeywell with respect to Study Area 5 or property owned by Regnal Realty consisting of Block 1288.2, lot 1, located at 420 Route 440, Jersey City, New Jersey.

48. Nothing in this Consent Decree shall be construed or interpreted to waive any claim or defense any Party has asserted or may assert against any third party in the Consolidated Litigation except as explicitly stated herein.

49. This Consent Decree does not constitute an admission of liability on the part of any Party with respect to any claims, cross-claims, or counter-claims in the Consolidated Litigation.

## ARTICLE III: CHROMIUM REMEDIATION

### A. General Terms and Requirements

50. **Responsibility for Implementation of Chromium Remediation.** As between the Parties, Honeywell shall be responsible for and shall undertake remediation of COPR and chromium present in Study Area 6 South at Honeywell's sole cost and expense. Remediation of COPR and chromium present in Study Area 6 South shall be undertaken in accordance with the terms of this Consent Decree.

51. **Designation of Chromium Areas of Concern.** For the purposes of remediation, Study Area 6 South shall consist of two AOC's, designated as the Open Space AOC and the Development AOC as shown approximately on Exhibit A. The exact boundaries of the two AOC's shall be subject to further delineation during the design and implementation of the Chromium Remedy.

52. **Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan.** The Chromium Remedy shall be consistent with the NJDEP Technical Requirements for Site Remediation, the Chromium Directive as issued by NJDEP on February 8, 2007 ("the NJDEP Chromium Directive"), and any Remedial Action Work Plan, including any modifications or addenda approved by NJDEP. Prior to submitting any Remedial Action Work Plan, Honeywell shall take all reasonable steps to ensure that the plan is consistent with the Chromium Remedy. However, this Consent Decree shall have precedence over any Remedial Action Work Plan in the event of any inconsistency. The approved Remedial Action Work Plan is a minimum standard, and the Chromium Remedy may be more protective than the remedy NJDEP approves.

53. **General Scope of the Chromium Remedy.** The Chromium Remedy shall address shallow groundwater and L-Well groundwater containing total chromium concentrations of 70 µg/l or greater and soil containing hexavalent chromium at concentrations of 20 mg/kg or greater within the top 20 feet of soil below the ground surface, and shall be consistent with the requirements set forth in this Article. The Chromium Remedy set forth in this Consent Decree addresses only the shallow and L-Well levels of groundwater (see paragraphs 69 - 72). The deep overburden and bedrock groundwater remediation, including source control, is addressed in the Deep Groundwater Consent Order.

54. **Development of a Schedule for the Chromium Remedy.** The Chromium Remedy shall be carried out diligently, and the development and implementation of any remedy required by NJDEP for non-chromium contamination shall not delay satisfaction of the milestones in the Schedule established pursuant to this paragraph. Within 90 days of entry of this Consent Decree, Honeywell shall propose a Master Schedule for the implementation of the Chromium Remedy .

(a) The Master Schedule shall incorporate the following dates:

(i) No later than August 15, 2008, Honeywell shall submit a Chromium Impacted Soils Pilot Test Work Plan to NJDEP and Riverkeeper;

(ii) No later than September 15, 2008, Honeywell shall complete field work in accordance with the RIWP Addendum;

(iii)No later than December 31, 2008, Honeywell shall submit an Initial Treatment Study Report and Remedial Action Work Plan pursuant to paragraph 86(c);

(iv) No later than July 31, 2012, Honeywell shall submit the soil and groundwater data from its 2010 and 2011 supplemental investigation of Site 163, a brief summary report, and

a designation of the boundaries of the Site 163 Development AOC to the Special Master pursuant to paragraph 86(c);

(v) No later than October 1, 2012, Honeywell shall submit an addendum to the Study Area 6 South 100% Design setting forth the 100% Design for the Site 163 Development AOC portion of the Study Area 6 South Chromium Remedy; and

(vi) Honeywell shall undertake, in good faith, to begin implementation of the Chromium Remedy by March 1, 2013.

(b) In addition, the Master Schedule shall propose deadlines for the following milestones:

(i) Submission of all documents subject to submission and review pursuant to paragraph 86(c);

(ii) Completion of those Site Preparation Activities necessary for the implementation of the Chromium Remedy;

(iii)Submission, following implementation of the soil components of the Chromium Remedy for the Development AOC, of the groundwater plans and reports required by paragraphs 70 and 72;

(iv)Completion of additional sampling for shallow groundwater delineation pursuant to paragraph 71 and a proposal for a remedy pursuant to paragraph 71, if needed;

(v) The submission of a 50% Design Report for the Chromium Remedy;

(vi) The submission of a 100% Design Report for the Chromium Remedy;

(vii) The date for completion of the installation of the Chromium Remedy;

(viii)Implementation of the long-term protections of the Open Space AOC established pursuant to paragraph 74; and

(ix) Transfer of the Open Space AOC to Jersey City pursuant to paragraph 74(a)(iii).

### B. Initial Chromium Remedy Steps: Delineation, Treatment Study, and Remedial Action Work Plan

55. **Delineation of Development AOC.** Honeywell shall conduct further soil sampling on Study Area 6 South in accordance with the RIWP Addendum. In addition to the locations set forth in the RIWP Addendum, Honeywell shall conduct further soil sampling pursuant to the provisions of the RIWP Addendum at the boring locations set forth in Exhibit E. Upon completion of the soil sampling required by this paragraph, Honeywell shall submit a Second Supplemental Remedial Investigation Report that sets forth the results of the sampling and Honeywell's proposal as to the delineation of the Development AOC. In conjunction with its proposal, Honeywell shall set forth its rationale as to whether prior sampling data should be included or excluded in the proposed delineation. The soil sampling and submission of a Second Supplemental Remedial Investigation Report shall be completed in accordance with the Schedule set forth in paragraph 54. Honeywell shall submit the Second Supplemental Remedial Investigation Report pursuant to paragraph 86(c). The Site 163 Development AOC shall be exempt from the requirements of paragraphs 55-58.

56. **Conduct of a Treatment Study in the Development AOC.** Honeywell shall conduct a field study of the efficacy of *in situ* treatment of 20 to 1000 Soils in accordance with the Chromium Impacted Soil Pilot Test Work Plan. The purpose of the pilot test shall be to evaluate whether *in situ* chemical treatment of 20 to 1000 Soils with one or more reductants can result in the permanent establishment of hexavalent chromium concentrations below 20 mg/kg under conditions in those areas of the Development AOC that may be subject to treatment as a remedy. Honeywell shall provide the raw data from the pilot test to NJDEP and Riverkeeper in scientifically useable electronic form as soon as the data become available. Honeywell shall

submit an Initial Treatment Study Report setting forth the initial results of the pilot test pursuant to paragraph 86(c) .

57. **Continued Monitoring of the Treatment Study.** As the result of the need to complete Study Area 7 remediation, to maintain Study Area 7 remediation support operations currently located on Study Area 6 South, and to conduct Site Preparation activities including the relocation of operating businesses on Study Area 6 South in advance of implementation of the Chromium Remedy, the Parties do not anticipate that implementation of field work for the Chromium Remedy will begin until March 1, 2013. Honeywell shall continue to monitor the performance of the pilot test and shall submit a Final Treatment Study Monitoring Report assessing the long term effectiveness of treatment for 20 to 1000 Soils in the Development AOC pursuant to paragraph 86(c) no later than December 31, 2011.

58. **Submission of a Remedial Action Work Plan.** On or before December 31, 2008, Honeywell shall submit a Remedial Action Work Plan for the Chromium Remedy pursuant to paragraph 86(c). The Remedial Action Work Plan shall be consistent with the Chromium Remedy set forth in this Consent Decree.

### C. Development AOC Soil Remedy

59. **Remedial Components.** In the Development AOC, soils containing hexavalent chromium at concentrations greater than 20 mg/kg shall be remediated as follows:

(a) Soils with a concentration greater than 1000 mg/kg shall be:

(i) Excavated and disposed of off-site at a waste disposal facility licensed to accept such waste; or

(ii) Treated *ex situ* and consolidated under the cap in the Open Space AOC provided the requirements of paragraphs 60 and 63 are satisfied and provided that such soils do not

require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a).

(b) 20 to 1000 Soils shall be:

(i) Excavated and consolidated within the Open Space AOC provided that such soils do not require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a); or

(ii) Excavated and disposed of off-site pursuant to the requirements of paragraph 59(a); or

(iii) Remediated pursuant to paragraphs 59(c) or 59(d) provided that such soils are also 20 to 240 soils and meet the requirements of paragraphs 59(c) or 59(d).

(c) 20 to 240 Soils may be remediated by excavation and consolidation within the Study Area 6 North AOC 1 Open Space Area, provided that such soils do not require venting of gases and shall not serve as the basis for the inclusion of gas venting as part of the Study Area 6 North AOC 1 Open Space Area remedy.

(d) 20 to 240 Soils within the Site 163 Development AOC may be remediated by *in situ* treatment, provided the requirements of paragraph 61 are satisfied.

60. **Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** *Ex situ* treatment and consolidation under the Open Space AOC cap may be used as a remedial component for soils containing greater than 1000 mg/kg hexavalent chromium provided that the requirements of this paragraph are satisfied:

(a) Honeywell demonstrates in the Final Treatment Study Monitoring Report that the proposed treatment will likely result in the reduction of the hexavalent chromium concentration of the treated soils such that the post-treatment total chromium concentration shown by Toxicity

Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C);

(b) Following a review of the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d), NJDEP agrees that Honeywell has made the demonstration required by paragraph 60(a).

(c) Plaintiffs have had an opportunity to review and comment on the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d)and pursuant to the Special Master review process set forth in paragraphs 86(e)-86(f); and

(d) Following review of the demonstration required by paragraph 60(a) pursuant to the Special Master review process set forth in paragraph 86(f), the Special Master issues a recommendation finding that Honeywell has made the demonstration required by paragraph 60(a) or the Court finds that Honeywell has made the demonstration required by paragraph 60(a) in the event that any Party seeks the Court's review of the Special Master's recommendations under this paragraph.

61. **Treatment as a Remedial Component for 20 to 240 Soils.** *In situ* treatment may be used as a remedial component for the 20 to 240 Soils in the Site 163 Development ACO, provided that such soils are 3 feet or more below ground surface and the requirements of this paragraph are satisfied:

(a) If Honeywell elects to treat *in situ* 20 to 240 Soils in the Site 163 Development AOC, Honeywell shall include in the 100% Design Addendum for Site 163 a plan for such treatment. Such treatment plan shall be comparable in detail and approach to the pipeline treatability plan which is Appendix F to the Study Area 6 North 100% Design. The goal of such *in situ* treatment

shall be to reduce hexavalent chromium soil concentrations to less than 20 mg/kg in soils 20 feet or less below ground surface;

(b) Three years after conducting the treatment set forth in subparagraph (a), Honeywell shall collect additional soil samples in the treated areas to evaluate the success of the treatment. These soil samples shall be analyzed for EH, pH, hexavalent chromium (using EPA/NJDEP Methods 3060A/7199), and sulfides (using EPA Method 9030B). Within 60 days of its receipt of the final data from such sampling, Honeywell shall submit a report with such data to the Special Master pursuant to paragraph 86(c);

(c) In the event that the sampling pursuant to subparagraph (b) shows that soils with greater than 20 mg/kg hexavalent chromium remain or that excess treatment reductant remains present, Honeywell may elect to pursue one or more of the following approaches after providing notice to the Special Master, Riverkeeper and the Jersey City Entities;

(i) In the case of excess treatment reductant remaining in the soil, continue to monitor such areas pursuant to subparagraph (b) until the excess reductant is no longer present;

(ii) In the case of soils with greater than 20 mg/kg hexavalent chromium:

(1) Excavate such soils and consolidate them under the cap in the Open Space AOC, consolidate them under the cap in the Study Area 6 North AOC 1 Open Space Area, and/or dispose of them off-site provided that in each instance the applicable requirements of paragraph 59 are satisfied;

(2) Conduct further *in situ* treatment using additional treatment reductant and submit a monitoring plan pursuant to paragraph 64; or

(3) In the event that the soils are within the areas depicted as River Front Park, Riverfront Drive or Kellogg Street on page 39 of the Redevelopment Plan, cover the affected

soils with a road, walkway, and/or other hardscape and restrict the use of that area through each of the following institutional controls:

(a) Issuance and recording of a conservation restriction comparable to that required under paragraphs 74(b) and 74(d);

(b) Transfer of title to that area to Jersey City pursuant to paragraphs 74(a)(iii) through 74(a)(iv)(2); and

(c) Issuance and recording of a deed notice comparable to that required under paragraphs 74(c) and 74(d).

62. **Submissions Related to Site 163.** Pursuant to the Schedule, Honeywell shall prepare and submit the following with regard to Site 163:

(a) A summary report of all chromium soil and groundwater data collected during site investigations in 2010 and 2011; and

(b) An addendum incorporating Site 163 into the 100% Design.

63. **Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** In the event that *ex situ* treatment is used as a final remedy for any portion of the soils containing greater than 1000 mg/kg pursuant to paragraph 59(a)(ii), Honeywell shall conduct post-treatment analysis of each treated batch of soil to demonstrate that the treatment has resulted in the reduction of the hexavalent chromium concentration such that the post-treatment total chromium concentration shown by Toxicity Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C). Such monitoring and demonstration shall be made prior to consolidation of the treated soils under the Open Space AOC cap pursuant to paragraph 59(a)(ii). In the event that Honeywell fails to make the demonstration required by this paragraph,

Honeywell shall dispose of the soils off-site at a waste disposal facility licensed to accept such waste.

64. **Post-Treatment Monitoring for 20 to 1000 Soils.** In the event that *in situ* treatment is used as a final remedy for any portion of the 20 to 1000 Soils, Honeywell shall conduct post-treatment monitoring to demonstrate that the treatment has resulted in permanent hexavalent chromium concentrations of less than 20 mg/kg in the treated area. Honeywell shall propose a program of post-treatment monitoring in a document that is submitted pursuant to paragraph 86(c). In the event that Honeywell fails to make the demonstration required by this paragraph, Honeywell shall propose further remedial actions pursuant to paragraph 59 in a document that is submitted pursuant to paragraph 86(c).

**D. Open Space AOC Components of the Chromium Remedy**

65. **Open Space AOC Soil Remedy.** In the Open Space AOC, the soil remedy shall consist of an engineered RCRA cap to isolate contaminated soils with gas venting, if necessary, to address the generation of methane and other naturally occurring gases in the Stratum O and/or Stratum D in the Open Space AOC. Soils consolidated under the cap, pursuant to paragraph 59(b)(i), shall not require gas venting and shall not be the basis for the inclusion of gas venting as a component of the cap. The cap shall be designed and constructed so that:

(a) The cap shall consist of a gas collection system, if gas venting is necessary, a base protective layer, an impervious geomembrane liner with a minimum thickness of 40 mil; a geocomposite drainage layer; a filter fabric; and a distinctive colored warning layer with markings in English and Spanish that would deter penetration of the cap in the event that digging occurred in the vicinity of the cap;

(b) All utilities, including those supporting the pump-and-treat system for groundwater remediation, with the exception of any extraction wells or collection trenches, shall be placed above the cap (but may be below the ground surface and/or contained within utility corridors). In the event that above-cap-grade gas collection and treatment is selected or is needed to meet current or future regulatory requirements, such collection and treatment facilities are prohibited in the Open Space AOC, except for piping to connect the sub-liner collection system with the treatment facilities; and

(c) Exclusive of roadways, the cap shall be overlain by layers of clean fill, backfill and/or overburden with an average depth of at least three feet and a minimum depth of at least two feet provided that any layer that incorporates overburden shall be below at least two feet of clean fill. Any clean fill or backfill soil brought to the Site will either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master. One foot of clean fill, covered with bituminous blacktop, shall be sufficient cover where roads, walkways, or other paved surfaces are located within the Open Space AOC. All clean soil fill in areas that will not involve paved roads, walkways, or other paved surfaces shall be vegetated in such a manner as to protect and maintain the required depth of the clean soil fill and to ensure that such vegetation shall not cause any interference with or penetration of the cap.

(d) The existing overburden soils in the Open Space AOC shall first be stripped off and set aside for use. If hexavalent chromium concentrations in the overburden exceed 20 mg/kg, the overburden shall be placed under the cap. If hexavalent chromium concentrations in the overburden do not exceed 20 mg/kg, the overburden may be placed above the cap but below the

two feet of clean fill required by paragraph 65(c). Excavated 20 to 1000 Soils from the Development AOC shall be placed and spread in the Open Space AOC under the cap. Both the chromium impacted soils and the previously stripped overburden shall be suitably compacted according to design specifications. Debris, to the extent it would interfere with the compaction specification requirements of the 100% Design, shall not be placed under the cap. The engineered cap shall be installed over the chromium-impacted soils exceeding 20 mg/kg hexavalent chromium.

**E. Demolition, Grading, and Backfill Requirements**

66. **Demolition and Grading Activities.** During demolition and grading activities, adequate protective measures shall be taken to protect site workers and the community from airborne dusts and exposures to contaminated soils.

67. **Backfill Requirements.** Soils excavated from the Development AOC shall be replaced with backfill soil. Any backfill soil brought to the Site shall either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master.

68. **Vegetation of Clean Fill.** All clean soil fill in areas that will not involve paved roads, sidewalks, paths, walkways, or building structures shall be vegetated in such a manner to protect and maintain the required depth of clean soil fill.

**F. Groundwater Components of the Chromium Remedy**

69. **Shallow Groundwater Remedy for the Open Space AOC.** The Open Space AOC shallow groundwater remedy shall consist of hydraulic barriers with a pump-and-treat system designed to isolate shallow groundwater and to intercept and treat shallow groundwater flowing

above the meadow mat in the Open Space AOC to the extent that such groundwater contains total chromium in concentrations in excess of 70 µg/l. The shallow groundwater remedy shall consist of the following:

(a) The existing soil/cement/bentonite wall on the boundary of Study Area 6 South and Study Area 7 shall be incorporated into the other engineering controls;

(b) Subterranean slurry walls or other hydraulic barriers shall be installed along the southern, eastern and western sides of the Open Space AOC and keyed into the meadow mat or Stratum O or to comparable depths below ground surface;

(c) A groundwater extraction system shall be established that shall consist of (i) one or more shallow extraction wells, sumps, or french drains within the Open Space AOC; (ii) pumps; and (iii) underground piping to convey any extracted water to Honeywell's Treatment Plant;

(d) The capture zone for the shallow groundwater remedy shall include at least the entire area of contaminated shallow groundwater within the Open Space AOC;

(e) A plan for control of water levels shall be developed;

(f) In the event that underground structures are demolished, the plans shall address the need for special attention for structures that extend below the meadow mat in order to control needed water levels; and

(g) Honeywell shall submit such information as is required to allow NJDEP to establish a classification exception area for groundwater at the Site, in accordance with NJDEP regulations.

70. **The Shallow Groundwater Remedy for the Development AOC.** Following implementation of the Development AOC soil components of the Chromium Remedy, Honeywell shall submit a report to (a) determine whether shallow groundwater remaining in the

Development AOC exceeds 70 µg/l total chromium and, (b) if so, evaluate the need for further remedial measures to address any such shallow groundwater remaining in the Development AOC with total chromium concentrations in excess of 70 µg/l. This evaluation shall be subject to review and comment by the Parties and approval by the Special Master.

(a) In the event that the evaluation demonstrates that further remedial measures are necessary, Honeywell shall propose such measures subject to review and comment by the Parties and approval by the Special Master;

(b) The capture zone of any remedy shall include at least the entire area of contaminated shallow groundwater except for shallow groundwater that is captured and subject to the shallow groundwater remedy for the Open Space AOC pursuant to paragraph 69;

(c) In the event that a pump-and-treat system is selected as a contingency measure for shallow groundwater in the Development AOC, all infrastructure for the pump-and-treat contingency system that is needed to ensure that the contingency system is fully operational, as required by paragraph 70(d), shall be installed prior to or in conjunction to any development of the Site. This includes at least one shallow extraction well, sump, or french drain, and the piping to convey any extracted groundwater to Honeywell's water treatment plant;

(d) If it is determined that the pump-and-treat contingency system must be activated, the pump-and-treat system shall be operational no later than six months after the date of the determination.

71. **Off-Site Shallow Groundwater Remedy.** Honeywell shall propose additional sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site. Honeywell shall submit a report of the results of such sampling and, in the event that contaminated shallow groundwater is found to extend off-site, a proposal for a remedy based on

such results. The report and the proposal for a remedy shall be subject to review and comment by the Parties and approval by the Special Master.

72. **L-Well Groundwater Remedy.** At the time this Decree is entered, the L-Well Groundwater is contained and not contributing to further contamination of surrounding waters and/or soils. However, in order to verify that this status continues following implementation of the Chromium Remedy, including any groundwater remedial measures pursuant to paragraphs 70 and 71, Honeywell shall propose a plan for one round of monitoring designed to evaluate whether the L-Well Groundwater remains contained. The plan shall include monitoring for total and hexavalent chromium and major ion chemistry to determine whether there has been movement in the L-Well Groundwater.

(a) In the event that no substantial change is detected in the major ion chemistry, no further action is required unless paragraph 72(c) is applicable.

(b) In the event that substantial changes are detected in the major ion chemistry, Honeywell shall propose a plan for further monitoring of the L-Well Groundwater. Such a plan shall be subject to review and comment by the Parties and approval by the Special Master.

(c) In the event that the initial monitoring or monitoring conducted pursuant to paragraph 72(b) demonstrates that proximate waters have total chromium concentrations in excess of 70 µg/l, regardless of whether there is a change in the major ion chemistry, Honeywell shall propose a remediation plan for the L-Well Groundwater. Such remediation plan shall be subject to review and comment by the Parties and approval by the Special Master.

### G. Permits and Authorizations

73. **Permits and Authorizations.** Honeywell shall obtain all necessary federal, state, and local permits and authorizations to carry out the Chromium Remedy as set forth in this Article.

## H. Long-Term Monitoring, Maintenance, and Protection of Engineering and Institutional Controls

74. **Protection of the Open Space AOC.** Except as provided in paragraphs 74(j) and 74(k), development in the Open Space AOC shall be prohibited. The Open Space AOC shall be protected against activities that may jeopardize the integrity of the cap and/or the groundwater remedial measures that shall be installed in the Open Space AOC pursuant to the Chromium Remedy or that may impede the long-term monitoring and maintenance of the cap and/or groundwater remedial measures. It is the intention of the Parties to implement different layers of protection, which alone or in concert, impose restrictions on development, run with the land, and survive all parties. Accordingly, the following actions shall be taken pursuant to the Schedule provided in paragraph 54:

(a) **Ownership of and Access to the Open Space AOC.** Ownership of and access to the Open Space AOC shall be in accordance with the following:

(i) Bayfront Redevelopment LLC, as the current owner in fee simple absolute of all property that comprises the Open Space AOC, shall not convey any rights or interests in any parcel that comprises the Open Space AOC property except as provided in this Decree. Within 90 days of entry of this decree, Bayfront Redevelopment LLC shall give Jersey City an option to buy all of the Open Space AOC property prior to the planned transfer pursuant to paragraph 74(a)(iii). Such option to buy shall be subject to the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall exercise the option to buy the Open Space AOC in the event that the conditions allowing for withdrawal of funds from the financial assurance mechanisms under paragraphs 98(c) or 98(d) are met;

(ii) Within 90 days of the entry of this Consent Decree, Bayfront Redevelopment LLC shall grant a conservation restriction for the Open Space AOC pursuant to the requirements of paragraph 74(b);

(iii) Upon the final construction of all roads and utility corridors within the Open Space AOC, Bayfront Development LLC shall donate good and marketable title to all the land comprising the Open Space AOC to Jersey City. In conjunction with such donation, Bayfront Redevelopment LLC shall petition to subdivide the properties within Study Area 6 South to create a new parcel(s) comprising the Open Space AOC. At the time of the donation, Jersey City shall grant Honeywell an easement for the purpose of monitoring and maintaining the Chromium Remedy. Jersey City shall also grant Honeywell all necessary access to the Open Space AOC by license or such other mechanisms as may be appropriate for purposes of monitoring and maintaining the Chromium Remedy. After it acquires title pursuant to this paragraph, Jersey City shall retain ownership of the Open Space AOC unless and until it shall have complied with the requirements of paragraph 74(a)(iv);

(iv)After it acquires title pursuant to this paragraph, Jersey City shall not convey or enter into any lease of the Open Space AOC to any other person or entity unless it has first satisfied either of the following conditions:

(1) Jersey City has obtained the Special Master's (or if the Special Master's appointment has expired, the Court's) approval to convey the Open Space AOC to a government entity that has the capacity and willingness to fulfill Jersey City's obligations under the Consent Decree with respect to the Open Space AOC and such entity agrees to submit to the Court's jurisdiction and to be bound by the requirements of the Consent Decree that Jersey City has committed to fulfill with respect to protection of the Open Space AOC pursuant to this paragraph

and routine maintenance of the permissible development in the Open Space AOC pursuant to paragraph 78(d); or

(2) The Open Space AOC has been remediated such that no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive, and Jersey City has demonstrated to the Special Master and/or the Court, as appropriate, that such remediation has been completed in accordance with all applicable requirements.

(b) **Conservation Restriction.** Prior to the grant of the option to buy pursuant to paragraph 74(a)(i), Bayfront Redevelopment LLC shall grant an open space conservation restriction, pursuant to N.J.S.A. 13:8-B-1, *et seq.*, over the Open Space AOC substantially in the form set forth in Exhibit C. Exhibit C is a conservation restriction that is consistent with the terms of this paragraph and this Consent Decree. The conservation restriction shall allow for the implementation, maintenance, monitoring, repair and replacement of the Chromium Remedy and development consistent with paragraphs 74(j) and 74(k), including the construction and placement of roads and utilities. The Conservation Restriction shall also allow for current uses of the Open Space AOC to continue until such time as construction of the Chromium Remedy begins. The Hackensack River Watershed Land Trust shall be the primary holder of the conservation restriction, with all rights of monitoring and enforcement. Riverkeeper shall propose an entity to serve as the secondary holder of the conservation restriction subject to comment by the Parties and review by the Special Master. The secondary holder shall have secondary rights of monitoring and enforcement.

(i) The conservation restriction shall be incorporated into this Consent Decree and made part of this Consent Decree. The final, executed conservation restriction shall be lodged with the Court and entered as an order of the Court. The conservation restriction shall be enforceable in this Court, in the same manner as this Consent Decree.

(ii) The conservation restrictions provided under this Consent Decree shall be consistent with the prohibited and permitted development of the Open Space AOC as set forth in paragraphs 74(j) and 74(k) below.

(iii) Jersey City shall not take any action, whether through exercise of any power of eminent domain, application to the State of New Jersey for approval of a diversion of public park or recreation land, legal challenge to the validity or enforceability of the conservation restriction, or otherwise, the effect of which would be to in any way terminate, abrogate, or diminish the terms, conditions, or purposes of the conservation restriction. If, notwithstanding the preceding sentence, Jersey City proceeds with a condemnation or other action, the result of which would be to terminate, abrogate, or otherwise diminish the terms, conditions, or purposes of the conservation restriction, Jersey City shall, before taking any such action satisfy all of the conditions set forth in paragraph 74(a)(iv)(2).

(iv) Notwithstanding the foregoing, the conservation restriction may be terminated upon application of any Party when no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive.

(c) **Deed Notice.** Upon completion of the Chromium Remedy, the Open Space AOC shall be subjected to the deed notice substantially in the form set forth in Exhibit D that restricts

future activities on the Open Space AOC. Nothing in the deed notice shall be construed as preventing the imposition of more stringent restrictions on the development allowed in the Open Space AOC pursuant to this paragraph and, in particular, the conservation restriction provided for in paragraph 74(b).

(d) **Recording of the Consent Decree, Conservation Restriction, and Deed Notice.** This Consent Decree, the conservation restriction imposed pursuant to paragraph 74(b), and the deed notice imposed pursuant to paragraph 74(c) shall be recorded, pursuant to N.J.S.A. §§ 46:15-1.1, 46:16-1.1, and 46:16-2, in the office of the Hudson County Register and a conspicuous reference to the Consent Decree, conservation restriction, and deed notice shall be included in all instruments concerning title to the Open Space AOC. Any Party shall have the right, periodically, but no more than once every 25 years, to record memoranda or other instruments that reference, incorporate, or attach this Consent Decree, the conservation restriction, the deed notice, and/or any further orders of the Court related to the Open Space AOC in the real estate records related to the Open Space AOC.

(e) **Zoning.** Pursuant to the Redevelopment Plan, the Open Space AOC is designated for open space and park. Jersey City shall not amend or change this designation unless it first satisfies the requirements of paragraph 74(a)(iv)(2).

(f) **Recreation and Open Space Inventory.** Upon acquiring fee simple absolute title to the Open Space AOC, Jersey City shall add those portions of the Open Space AOC not covered by roads, the pedestrian thoroughfare, and utility corridors adjacent to roads onto its Green Acres Program Recreation and Open Space Inventory ("ROSI") pursuant to N.J.A.C. § 7:36 and shall specify in such listing that it is subject to (i) Honeywell's prior easement to monitor, maintain, repair, and replace the Chromium Remedy; (ii) the actions necessary to implement, monitor,

maintain, repair, and replace the Chromium Remedy; (iii) the actions necessary to install any development permissible under paragraphs 74(j) and 74(k); and (iv) the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall also take all steps necessary or appropriate to notify the New Jersey Green Acres Program that such portions of the Open Space AOC have been added to its ROSI, such that those portions of the Open Space AOC shall thereafter be subject to all procedural and regulatory requirements applicable under the Green Acres Program, including prohibitions against diversion.

(g) **Eminent Domain.** If all or part of the Open Space AOC is taken in exercise of the power of eminent domain, or acquired by purchase in lieu of condemnation, by any public, corporate, or other authority so as to terminate, abrogate, or limit the restrictions created by this Consent Decree or the conservation restriction imposed pursuant to paragraph 74(b), in whole or in part, any Party may take appropriate actions to challenge such taking if there is a reasonable legal basis for doing so. In the event that the Parties are unable to prevent a taking notwithstanding their reasonable and appropriate efforts, any Party may take appropriate actions to recover the full value of the interests in the Open Space AOC subject to the taking or in lieu purchase, and all direct and incidental damages, costs, and fees occasioned thereby.

(h) **Environmental Covenant.** In the event that New Jersey enacts the Uniform Environmental Covenants Act or its substantial equivalent, the Parties shall address the issue of whether an environmental covenant shall be established for the Open Space AOC under the statute. If the Parties are unable to reach agreement on establishment of an environmental covenant, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of an environmental covenant if it would provide substantial additional protection for the Open Space AOC without

unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(i) **Future Protections.** Any Party shall have the right to propose consideration of additional or substitute protections for the Open Space AOC. If the Parties are unable to reach agreement with regard to the proposal, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of additional or substitute protections for the Open Space AOC if they would provide substantial additional protection for the Open Space AOC without unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(j) **Prohibited Development in Open Space AOC.** Only development satisfying the requirements of this paragraph and paragraph 74(k) shall be permitted in the Open Space AOC. All other development in the Open Space AOC shall be prohibited.

(i) Honeywell shall establish Open Space Design Standards that shall govern all development in the Open Space AOC regardless of when the construction or installation of permissible development occurs. The Open Space Design Standards shall satisfy each of the requirements set forth in paragraph 74(j)(v) and shall set forth the requirements for development that are necessary for the protection of the integrity of the Chromium Remedy.

(ii) The Initial Development in the Open Space AOC shall be the development undertaken following the completion of the Chromium Remedy in the Open Space AOC. The Initial Development may occur in one or more phases. Honeywell and Bayfront

Redevelopment LLC shall prepare a Development Plan before the initiation of each phase of the Initial Development. The Initial Development Period for each phase shall consist of the period covered by the Initial Development, plus a period of 10 years following the submission of the as-built documentation for the phase pursuant to paragraph 74(j)(viii).

(iii) The Special Master shall have jurisdiction to review the Open Space Design Standards and the Development Plan(s) solely for the purpose of ensuring that any development undertaken during the Initial Development Period is consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy. The Special Master's jurisdiction with regard to development in the Open Space AOC shall run through the Initial Development Period for each phase.

(iv) Honeywell shall ensure that the requirements of this paragraph and paragraph 74(k) are satisfied with regard to any development undertaken within the Initial Development Period. Honeywell shall also ensure that any development undertaken within the Initial Development Period is designed and installed in a manner consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy.

(v) Any development undertaken in the Open Space AOC, regardless of when undertaken, shall satisfy each of the following requirements:

(1) It shall not jeopardize the integrity of the Chromium Remedy;

(2) It shall be limited to the types of development permitted under paragraph 74(k);

(3) It shall be consistent with this Consent Decree, including the conservation restriction imposed pursuant to paragraph 74(b), and the Redevelopment Plan; however, in the

event of any conflict or inconsistency between this Decree and the Redevelopment Plan, this Decree shall govern;

(4) In total, at least 75% of the Open Space AOC, exclusive of the acreage used for roads and the pedestrian thoroughfare, shall be comprised of landscaping, as defined by paragraph 74(k)(xi);

(5) The portion of the Open Space Design Standards necessary for protection of the Chromium Remedy as related to all roads, the pedestrian thoroughfare and associated utility corridors as well as the general location of such items shall be included in the 100% Design of the Chromium Remedy;

(6) If the lowest elevation for the bedding for any utility line, including irrigation or sprinkler lines, is two feet from the top of the warning layer of the cap, the utility line shall be placed in a utility corridor;

(7) In any event, there shall be two feet of soil or more between the warning layer of the cap and the lowest elevation of the bedding for any irrigation or sprinkler lines; and

(8) No permanent concession facilities shall be permitted.

(vi) Honeywell shall submit the Open Space Design Standards and the Development Plan(s) for any development undertaken during the Initial Development Period pursuant to the requirements of paragraph 86(c), except that such documents need not be submitted to NJDEP. Following Honeywell's submission of such documents, the procedures of paragraphs 86(e) and 86(f) shall apply, except that the Special Master need not provide notice to NJDEP.

(vii) During the Initial Development Period, any development in the Open Space AOC shall require the preparation and submission of a Development Plan pursuant to

paragraph 74(j)(vi) and such Development Plan shall be subject to review by the Special Master pursuant to paragraph 74(j)(iii).

(viii) Upon completion of each phase of the Initial Development, Honeywell shall provide as-built documentation for the Initial Development to the Special Master, Riverkeeper, and Jersey City. Upon completion of any further development during the Initial Development Period for the phase, Honeywell shall also provide as-built documentation to the Special Master, Riverkeeper, and Jersey City for the additional development. Such additional as-built documentation for a phase shall not affect the running of the Initial Development Period for the phase.

(ix)During the Initial Development Period, replacement in-kind of development features or facilities included in the Initial Development or minor modifications to the development features or facilities included in the Initial Development shall not require the preparation of a Development Plan or be subject to review by the Special Master, provided that such replacement or modification satisfies the requirements of the Open Space Design Standards, the applicable Development Plan, and paragraphs 74(j)(v) and 74(j)(x)(3)(notice requirement).

(x) After the Initial Development Period, all development is prohibited unless one of the following conditions is met:

(1) Jersey City satisfies the conditions set forth in paragraph 74(a)(iv)(2);

(2) The development is a replacement in-kind and such replacement is made in conformance with the specifications of the Open Space Design Standards, the applicable Development Plan, and paragraph 74(j)(v); or

(3) The development meets the requirements of paragraphs 74(j)(v) and 74(j)(xi), and Jersey City provides notice of its intention to alter or add to the development undertaken in the Initial Development Period. Such notice shall be provided in writing to Honeywell, Riverkeeper, and the holders of the conservation restriction established pursuant to paragraph 74(b) at least 30 days prior to Jersey City's alteration or addition to development undertaken in the Initial Development Period. Honeywell, Riverkeeper, or any holder of the conservation restriction shall have the right to move the Court to prohibit such alteration or addition.

(xi) If any of the development features or facilities that Jersey City seeks to add pursuant to paragraph 74(j)(x) require utilities that would require utility corridors other than the utility corridors installed during the Initial Development Period, Jersey City shall obtain approval from the Court before installing such new utility corridors.

(xii) Jersey City shall provide Honeywell, Riverkeeper, and the holder(s) of the conservation restriction established pursuant to paragraph 74(b) with an annual report that describes any alterations or additions, including those activities under paragraph 74(j)(x)(2), to the development undertaken during the Initial Development Period.

(xiii) All development features or facilities, whether included in the Initial Development or added subsequent thereto, are subject to demolition and/or removal to the extent necessary to maintain, replace, or repair the Chromium Remedy.

(k) **Permissible Development in the Open Space AOC.** The Initial Development or any subsequent addition or alteration thereto may include any or all of the following types of development features or facilities, provided that such development features or facilities satisfy the conditions set forth in paragraph 74(j)(v):

(i) Roads and the pedestrian thoroughfare -- both crossing and running along the Open Space AOC, but no more extensive than provided for in the diagram on page 39 of the Redevelopment Plan;

(ii) Curbing and fences;

(iii) Sidewalks, paths, walkways, and nature trails;

(iv) Utilities and utility corridors, lighting, and restrooms;

(v) Irrigation or sprinkler components or systems;

(vi) Water features;

(vii) Above-ground storm water cisterns;

(viii) Signs, including the signs or display required by paragraph 74(l);

(ix) Benches, trash receptacles, and bicycle racks;

(x) Recreational facilities, such as playground equipment, bocce ball courts, tennis courts, basketball courts, and athletic fields; and

(xi) Landscaping, including natural grasses, small trees, shrubbery, flowers, and potted plants, provided that such landscaping and the anticipated root structure of each landscaping component do not and will not jeopardize the integrity of the Chromium Remedy. Any portion of an athletic field that is covered in natural grass shall be considered landscaping for purposes of the percentage set forth in paragraph 74(j)(v)(4).

(l) **Signs or Displays.** Honeywell shall develop a permanent plan for informing visitors to the Open Space AOC of the history of the chromium production, contamination, and its remediation. Such plan shall provide for appropriate signs or displays that communicate this information. Such plan shall be subject to review and comment by the Parties and approval by the Special Master.

75. **Honeywell's Ongoing Responsibility.** Honeywell shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy in perpetuity. Honeywell shall satisfy this responsibility through establishment and implementation of a Long-Term Monitoring Plan. In the event that Honeywell ceases to exist without a successor-in-interest or its obligations under this Consent Decree are stayed or limited due to a bankruptcy petition, the Court shall appoint an independent third-party fiduciary who shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy pursuant to the requirements of this Consent Decree and the Long-Term Monitoring Plan, unless Jersey City volunteers to assume these responsibilities for the Chromium Remedy.

76. **Long-Term Monitoring Plan.** In consultation with the Parties, and subject to approval by the Special Master and NJDEP, Honeywell shall develop a Long-Term Monitoring Plan to ensure the ongoing effectiveness of the Chromium Remedy to meet the objectives set forth in paragraphs 65, 69, 68, 69, 72, and 77. The Long-Term Monitoring Plan shall be consistent with the applicable EPA policies and guidance, including, among others, EPA's Comprehensive Five Year Review Guidance (2001) (or any subsequent revision) and with NJDEP's Technical Requirements for Site Remediation (or any subsequent revision).

77. **Long-Term Monitoring Plan Objectives.** Honeywell shall design the Long-Term Monitoring Plan to satisfy each of the following objectives:

(a) Provide monitoring to ensure that the integrity and effectiveness of the Chromium Remedy are maintained; and

(b) Provide monitoring to ensure that the restrictions of the institutional controls are being satisfied, including the prohibition on development in the Open Space AOC.

78. **Monitoring and Remediation Under the Long-Term Monitoring Plan.** The Long-Term Monitoring Plan shall include the monitoring and remediation activities set forth in this paragraph and other monitoring and remediation activities, if necessary, to meet the objectives of paragraph 77. Honeywell shall provide Riverkeeper, the Special Master, and NJDEP with annual reports on activities conducted under the Long-Term Monitoring Plan.

(a) **Monitoring Activities in the Long-Term Monitoring Plan.** Honeywell shall undertake the following monitoring activities at intervals to be specified in the Long-Term Monitoring Plan, but no less frequently than set forth below, and, if the monitoring shows it is necessary, Honeywell shall also undertake the remediation activities as set forth below:

(i) Quarterly visual inspection monitoring of the Open Space AOC to ensure that it is not being put to any use that is inconsistent with paragraphs 74(j) and 74(k) or any use that may compromise the integrity of the Chromium Remedy. The Long-Term Monitoring Plan shall include an inventory of the prohibited and permissible uses pursuant to paragraph 74 and a corresponding checklist to be used by the individuals conducting the monitoring. If Honeywell determines that the Open Space AOC is being used in a manner inconsistent with the protections or the integrity and effectiveness of the Chromium Remedy, Honeywell shall act as soon as possible to cause such use to cease and, if there has been damage to the Chromium Remedy, to repair or replace it to original specifications or to a level of protection equivalent to the original Chromium Remedy;

(ii) Quarterly visual inspection monitoring of the Open Space AOC grade and slope to identify whether erosion has occurred or is occurring. Honeywell shall remediate any significant erosion.

(iii)Quarterly visual inspection monitoring to determine whether noticeable differential settlement or subsidence has occurred or is occurring in the Open Space AOC such that the integrity of the Chromium Remedy may be materially impaired. If evidence of differential settlement or subsidence is found, Honeywell shall propose further investigative measures. Honeywell shall remediate any differential settlement or subsidence that is beyond the degree of differential settlement/subsidence allowed for in the 100% Design and repair the cap and/or the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(iv)A baseline topographic survey at the completion of the Chromium Remedy and three additional surveys conducted at five-year intervals beginning five years after the conduct of the baseline survey. The topographic survey shall be of sufficient precision and accuracy to present the results as one-foot contours;

(v) Quarterly visual inspection monitoring to determine whether the Chromium Remedy in the Open Space AOC has been disturbed. Any evidence of the distinctive warning layer materials or any other cap materials as described in paragraph 65(a) at the surface is an indication that the cap has been disturbed. In such an event, Honeywell shall propose further investigative measures to evaluate whether the integrity of the cap has been compromised. In the event that the investigative measures show that the cap integrity has been compromised, Honeywell shall repair or replace the cap and the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vi) Quarterly visual inspection monitoring to ensure that burrowing animals are not materially impairing the integrity of the Chromium Remedy. If evidence of burrowing animals is found, Honeywell shall follow humane removal procedures and repair or replace the cap and

the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vii) Quarterly visual inspection monitoring of the vegetative cover in the Open Space AOC to ensure that vegetative cover is in conformance with the landscaping provisions of the 100% Design and the Redevelopment Plan and will not materially impair the integrity of the Chromium Remedy. Maintenance of the vegetative cover shall include, at a minimum, mowing to ensure that tree species cannot become established and removal of any other vegetation with the potential to damage the Chromium Remedy;

(viii)Quarterly groundwater monitoring to ensure that groundwater levels are maintained in accordance with the requirement to maintain an outward gradient from Study Area 7 and in accordance with the water level control plan developed pursuant to paragraph 69(e);

(ix) Monitoring of vented gases and the gas venting system to ensure proper operation of the system, to evaluate any degradation of the system, to assess the need for treatment of vented gases, either initial, subsequent, or further depending on whether treatment has been previously provided, and to detect any condition that might endanger public health or safety. Such monitoring shall be conducted on a monthly basis for at least one year and, if the readings are stable, such monitoring may be conducted thereafter on a quarterly basis; and

(x) Any additional monitoring as required by specific details added in the design phase of the Open Space AOC.

(b) **Procedures for Proposing Changes to the Long-Term Monitoring Plan.** Any Party may, from time to time, propose changes to the scope of the monitoring activities under the Long-Term Monitoring Plan. If the Parties agree, the Long-Monitoring Plan shall be so changed

subject to approval by NJDEP and by the Special Master, if his appointment has not terminated, or otherwise, by the Court. If the Parties are unable to reach agreement over alterations to the monitoring and the Special Master's appointment has not terminated under this Consent Decree, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation. In the event that the dispute arises after the Special Master's appointment has terminated, any Party may file a motion seeking a resolution of the dispute by the Court.

(c) **Contingency Plan**. As part of the Long-Term Monitoring Plan, Honeywell shall develop a contingency plan to ensure the integrity of the remediation in the event of any planned penetration of the cap or otherwise planned activity that compromises the cap or any unplanned event or accident that penetrates the cap or otherwise compromises the integrity of the Chromium Remedy. The contingency plan shall include, at a minimum, an annually updated plan to notify the relevant persons, including the Special Master, NJDEP, and the Parties, of (i) the event penetrating the cap, compromising the cap, or compromising the integrity of the Chromium Remedy; (ii) the general steps to be taken to identify the extent of the problem; and (iii) the standards for remedying the problem.

(d) **Routine Maintenance**. The title owner of the Open Space AOC shall conduct maintenance of the Open Space AOC features or facilities that are permissible under paragraphs 74(j) and 74(k). The maintenance workers shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy. The training shall include the identification and reporting of any uses or features that are not permissible in the Open Space AOC or that may jeopardize the integrity of the Chromium Remedy. Honeywell shall provide all training materials. The title owner of Open Space AOC shall annually provide to the other Parties and

the Special Master a report describing the training which has been provided to its maintenance workers. The title owner of the Open Space AOC shall also provide to the Parties and the Special Master notice of any violations of the restrictions relating to the Open Space AOC identified by its workers during routine maintenance.

(e) **Recordkeeping**. Honeywell shall maintain written logs or other records of those monitoring and remediation activities undertaken pursuant to the Long-Term Monitoring Plan. Such logs shall be provided to Riverkeeper on a quarterly basis.

79. **Monitoring and Reporting to Riverkeeper.** Riverkeeper shall be provided with all documents submitted to NJDEP and/or the Special Master with respect to the Chromium Remedy, including the documents identified in paragraph 86(c).

80. **Notice to Stakeholders.** All residents, regardless of whether they are owners or lessees, and all commercial tenants on Study Areas 6 and 7 are hereby deemed stakeholders. Honeywell shall ensure that all stakeholders shall be provided at the time of their purchase or lease with notice of the contamination, the remedial actions that have been undertaken or are planned, and the importance of reporting activities that may appear to jeopardize the integrity of the engineering controls. Notice shall be accomplished in the following manner:

(a) Bold or otherwise conspicuous language on the first page of the deed provided to all purchasers in the Residential Area;

(b) A summary notice of the Chromium Remedy which:

(i) Has been subject to review and comment by the Parties and approval by the Special Master; and

(ii) Provides a reference to public websites and libraries and/or the future equivalents thereof, where the following can be found:

(1) Zoning and other Jersey City maps showing the Open Space AOC; and

(2) Documents describing the contamination and the remediation, including:

(a) This Consent Decree;

(b) The Remedial Investigation Report and the Final Remedial Action Report,

(c) The annual reports on long-term monitoring and maintenance and repair activities as required by paragraph 78 and annual reports on changes to the Initial Development as required by paragraph 74(j)(xii); and

(d) The Long-Term Monitoring Plan.

(c) The public provision of the maps and documents referred to in paragraph 80(b)(ii) via websites and libraries and/or the future equivalents thereof; and

(d) Notices to lessees and commercial tenants in all lease documents.

81. **Annual Letter to Riverkeeper on Notice to Stakeholders.** Each year beginning one year after the issuance of the first notice in a deed or lease pursuant to paragraph 80, Honeywell shall provide a letter to the Riverkeeper documenting its compliance with paragraph 80.

82. **Future Notice to Stakeholders.** Honeywell shall ensure that all stakeholders are provided with notice, at least annually, of long-term monitoring activities and any additional remediation activities undertaken with respect to the Chromium Remedy. Such notice shall be accomplished by notices on websites or future equivalents thereof, including Jersey City websites, any websites created to provide information about the Chromium Remediation or redevelopment of the Redevelopment Area, and one or more of the following:

(a) Any community message board or other similar site used and/or maintained by stakeholders or the manager(s) of the Redevelopment Area;

(b) Mailings to all stakeholders; and

(c) Posters and flyers throughout the Redevelopment Area.

83. **Stakeholder Enforcement.** Any stakeholder shall have the right to enforce the remedial obligations of this Consent Decree in the Court, including post-implementation monitoring and maintenance obligations, and the terms of any deed notice or use restriction.

**I. Oversight and Enforcement by the Special Master and NJDEP**

84. **Federal Court Jurisdiction.** The Court shall retain jurisdiction for the purpose of overseeing and enforcing this Consent Decree and to review any issue or dispute which is not resolved through the oversight process described in Article III.I.

85. **Appointment and Jurisdiction of the Special Master.** The Chromium Remedy provided for in this Consent Decree is hereby referred to a Special Master pursuant to Rule 53 of the Federal Rules of Civil Procedure. The Special Master is appointed in the Consolidated Litigation for the purpose of overseeing and enforcing the Chromium Remedy, the first five years of long-term monitoring of the Chromium Remedy, financial assurances for the Chromium Remedy, and the Initial Development Period for each phase of development in the Open Space AOC. The Special Master is also appointed in the Consolidated Litigation for the limited purpose of ensuring that the scheduling and implementation of any non-chromium related remedy, any site preparation activities, and any site redevelopment activities do not undermine the integrity of, unreasonably interfere with, or unnecessarily delay the effectuation of the Chromium Remedy, the Study Area 7 remedies, and other remedies within his jurisdiction as of the date of entry of this Consent Decree. The Special Master shall have jurisdiction over all matters for which he is appointed.

86. **Oversight of the Chromium Remedy.**

(a) **NJDEP Authority**. Nothing in or pursuant to this Consent Decree shall limit NJDEP's full statutory and regulatory authority with respect to the Study Area 6 South site, including (i) permitting authority; (ii) authority to review and approve the Treatment Study reports, the Remedial Action Work Plan, the 100% Design, and final Remedial Action Report for the Chromium Remedy; and (iii) authority to issue a no further action letter.

(b) **Special Master Responsibilities**. The Special Master shall have the following responsibilities:

(i) Ensuring that Honeywell's implementation of the Chromium Remedy satisfies the requirements of this Consent Decree;

(ii) Ensuring that Honeywell's implementation of the Chromium Remedy conforms with federal, state, and local permit requirements;

(iii) Establishing a reasonable schedule for the implementation of the Chromium Remedy and monitoring conformance with it;

(iv) Reviewing monthly progress reports and conducting periodic meetings with the Parties to review the progress of the implementation of the Chromium Remedy. NJDEP shall be invited, but not required, to participate in these meetings and the decision as to whether to participate shall be left to NJDEP's sole discretion;

(v) Submitting bi-monthly progress reports to the Court pursuant to the schedule for the submission of such reports established in *ICO v. Honeywell*;

(vi) Overseeing the financial assurances established pursuant to paragraphs 91 through 100, and, until the expiration of his term pursuant to paragraph 90, overseeing the financial assurances established pursuant to paragraphs 101 through 112;

(vii) Coordinating review of the documents as provided in paragraphs 86(c) through 86(g);

(viii) Overseeing all development undertaken in the Open Space AOC during the Initial Development Period pursuant to paragraph 74(j)(iii); and

(ix) To the extent that, in matters within the jurisdiction of the Special Master as set forth herein, a dispute arises between the Parties with respect to implementation of the Chromium Remedy, issuing a recommendation to the Court with respect to the dispute.

(c) **Submission of Documents by Honeywell.** Honeywell shall submit the following documents to Riverkeeper, Jersey City, the Special Master, and NJDEP:

(i) An overall schedule with milestones for the design and implementation of the remedy ("Schedule") consistent with paragraph 54 above;

(ii) A Second Supplemental Remedial Investigation Report reporting the results of the field work conducted pursuant to paragraph 55;

(iii)A Chromium Impacted Soils Pilot Test Work Plan and Analytical Protocol for conduct of the treatment study pursuant to paragraph 56, unless such documents are agreed to by NJDEP and Riverkeeper before the entry of this Consent Decree;

(iv)An Initial Treatment Study Report for the Development AOC;

(v) A Final Treatment Study Monitoring Report;

(vi) The documents for Site 163 submitted pursuant to paragraphs 54(a)(iv), 54(a)(v), 61, and 62;

(vii) A report to evaluate the need for remediation of any potentially remaining contaminated shallow groundwater in the Development AOC after implementation of the Development AOC Soils Remedy and, based on such an evaluation, a proposal;

(viii) A report of the results of the sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site pursuant to paragraph 71 and, based on the results, a proposal for a remedy;

(ix) A plan for one round of monitoring to evaluate whether the L-Well Groundwater remains contained pursuant to paragraph 72;

(x) A proposal for a remedy of the L-Well Groundwater, in the event L-Well Groundwater monitoring indicates the contaminated groundwater is no longer contained, pursuant to paragraph 72;

(xi) A Remedial Action Work Plan;

(xii) A 50% Design Report (which may include the Development AOC Conceptual Design Plan as a component) as well as design drawings and specifications at the 50% level for other components of the Chromium Remedy (hereinafter the 50% Design);

(xiii) Design drawings and specifications at the 100% level (after selection of the contractor) (hereafter "100% Design");

(xiv) The data validation plan, including quality control and quality assurance protocols;

(xv) The site-wide master health and safety plan;

(xvi) The Long-Term Monitoring Plan;

(xvii) The final Remedial Action Report or final construction report (including as-built drawings and such other reports as may be prepared of the remedy as implemented);

(xviii) A program for post-treatment monitoring pursuant to paragraph 63, and, depending on such results, a proposal for further remedial actions;

(xix) A report reviewing measured groundwater levels for the groundwater remedy;

(xx) Documents required during the Initial Development Period pursuant to paragraphs 74(j)(vi), 74(j)(vii), and 74(j)(viii); and

(xxi) Other post-implementation monitoring reports as required by the Long-Term Monitoring Plan.

(d) **Initial Review of Documents by NJDEP.** The Parties and Special Master shall allow the period of time set forth below for NJDEP to conduct its review of a submission (hereinafter "NJDEP Review Period") before the document is subject to the Special Master review and approval process. During the NJDEP Review Period, any Party may submit comments to NJDEP. For the Second Supplemental Remedial Investigation Report, the Remedial Action Work Plan, the Initial Treatment Study, and the Final Treatment Study Monitoring Report, the NJDEP Review Period shall be 90 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. For any other documents identified in paragraph 86(c), the NJDEP Review Period shall be 30 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. The NJDEP review period shall be extended an additional 30 days for any document for which NJDEP provides the Parties and the Special Master with notice that its review will require an additional 30 days. At the conclusion of the NJDEP Review Period, the comment and review process provided for in paragraphs 86(e) and 86(f) shall commence. In the event that any document has been revised during the NJDEP Review Period, Honeywell shall resubmit the applicable document for purposes of the comment and review provided for in paragraphs 86(e) and 86(f).

(e) **Comment on Submitted Documents**. For each of the documents submitted by Honeywell pursuant to paragraph 86(c), and following conclusion of the NJDEP Review Period as described in paragraph 86(d), the Special Master shall establish a schedule for the submission

of comments and responses to comments. For each of the documents submitted, Riverkeeper, Jersey City, the Special Master, and NJDEP shall have the right to submit comments to Honeywell. Honeywell shall address all comments received and submit a revised document. The revised document shall be submitted by Honeywell to Riverkeeper, Jersey City, the Special Master, and NJDEP. The revised document shall be subject to review and approval pursuant to paragraph 86(f), unless the Parties agree both on the revised document and that further review and approval pursuant to paragraph 86(f) is unnecessary. In that event, the Parties shall inform the Special Master that review under paragraph 82(f) is unnecessary and Honeywell shall proceed to implement the revised document.

(f) **Review and Approval of the Submitted/Revised Document**

(i) **Scope of Review**. Subject to the limitations in paragraph 82(e), all documents submitted by Honeywell, pursuant to paragraph 86(c) and 86(e), shall be subject to review and approval by the Special Master in accordance with the following procedure. All such documents, except the Schedule and the 100% Design, shall be subject to the review and approval process and shall not require an order of the Court. The Schedule and 100% Design documents shall be subject to the review and approval process, but shall also require an order of the Court as provided in paragraph 86(g). A document shall be approved if the document (1) complies with this Consent Decree; (2) complies with the Remedial Action Work Plan for the Chromium Remedy; and (3) complies with the Schedule and 100% Design.

(ii) **Procedure**. Prior to making a decision on a document, the Special Master shall notify NJDEP of his intention to rule on the document or make a recommendation to the Court on the document. Such notice shall notify NJDEP that the Special Master will consider any comments NJDEP wishes to submit on the document if such comments are submitted within

the timeframe established by the Special Master in the schedule for comments pursuant to paragraph 86(e). NJDEP shall in its sole discretion determine whether to submit comments to the Special Master.

(iii) **Court Review**. If any Party objects to the Special Master's recommendation to the Court or approval of any document pursuant to this paragraph, that Party may seek further relief from the Court with respect to the document.

(g) **Schedule and 100% Design Documents**. As to the Schedule and the 100% Design documents, Honeywell shall have the responsibility, within 30 days of the Special Master's approval of each document, of (i) moving for entry of an order by the Court approving the document as approved by the Special Master; or (ii) filing objections with the Court to the Special Master's approval (and any recommendations contained therein) and moving for entry of the Schedule or 100% Design (including any such recommendations of the Special Master to which Honeywell agrees). Riverkeeper shall have the right in these proceedings to raise any objections they might have to the Schedule or 100% Design as approved by the Special Master or to the submission by Honeywell to the Court. NJDEP shall receive notice of any motion filed with respect to the Schedule or the 100% Design.

(h) **Flexibility in 50% and 100% Design Documents**. The Parties recognize that work conducted to implement the Chromium Remedy may be conducted by Honeywell contractors and that Honeywell may establish performance-based criteria or specifications for its contractors. As a result, the Parties recognize that the 50% Design and 100% Design documents for the Chromium Remedy may include performance-based standards, criteria, and specifications. These documents shall be sufficiently prescriptive to enable the Parties and the Special Master to evaluate their conformance with the Remedial Action Work Plan and this Consent Decree. The

Parties also recognize that the 100% Design will be completed after Honeywell has selected a contractor. The Parties further recognize that completing the 100% Design after the selection of the contractor(s) shall not make the 100% Design subject to any less stringent or more deferential review. Honeywell's commitment to the contractor(s) shall not be cause to limit review by the Parties and the Special Master.

(i) **Changes to the Schedule.** The Parties recognize that changes to individual line items in the Schedule will occur. To the extent that (i) the Parties and the Special Master agree that such changes do not have a material impact on satisfaction of the Schedule milestones established for items set forth in paragraph 54; and (ii) such changes do not require modifications to any necessary permits or authorizations for the Chromium Remedy, such changes may be made upon agreement of the Parties and the Special Master without further order of the Court.

87. **Retention of Professionals.** The Special Master may retain the services of professionals and/or other technical personnel, as reasonably needed, to fulfill his obligations under this Consent Decree, and for which he will be reimbursed pursuant to paragraph 89.

88. **Insurance for the Special Master.** The Special Master shall obtain insurance coverage relating to the performance of the Special Master's duties and responsibilities under this Consent Decree. Such coverage shall be similar to the Special Master's existing coverage in *ICO v. Honeywell*, procured pursuant to the Court's November 11, 2005 Stipulation and Order Regarding Special Master's Application to Procure Insurance Coverage, and as extended to the Consolidated Litigation by the Sediment Consent Order. The insurance coverage shall be sufficiently extended in duration and scope to cover all additional duties and responsibilities as set forth hereunder. Honeywell shall pay the premiums and other administrative costs of the Special Master's insurance.

89. **Reimbursement of Special Master Fees and Expenses.** The Special Master shall submit fee applications to the Court for approval of reasonable fees and expenses incurred in the oversight of matters referred to him pursuant to this Consent Decree. Any Party may raise with the Court objections to such fee applications. Upon approval of a fee application by the Court, the reimbursement of the Special Master's fees and expenses shall be made from the escrow fund previously established by Honeywell for the purpose of paying the Special Master's fees and expenses in *ICO v. Honeywell* pursuant to this Court's September 15, 2003 Order Setting Financial Assurances and extended to the Consolidated Litigation by the Sediment Consent Order.

90. **Expiration of Special Master's Appointment.** The Special Master's appointment under this Consent Decree shall expire after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy and the Initial Development Period for each phase of development has been concluded as provided in paragraph 74(j)(ii). However, solely to the extent that the Special Master is still supervising other portions of the Consolidated Litigation or *ICO v. Honeywell* after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy or the Initial Development Period for each phase of development as provided in paragraph 74(j)(ii), whichever is later, the Special Master shall continue to have jurisdiction under this Consent Decree until he has completed his specifically enumerated responsibilities under the Final Judgment in *ICO v. Honeywell*, the Sediment Consent Order, the Deep Groundwater Consent Order, the Study Area 6 North Consent Decree, and any other future orders, decrees, or judgments in *ICO v. Honeywell* and the Consolidated Litigation. Enumerated responsibilities under any order, decree, or judgment shall include only those tasks specifically assigned to the Special Master in the order, decree, or judgment. Enumerated responsibilities

shall not include any continued jurisdiction exercised over long-term monitoring beyond the initial period specified in the order, decree, or judgment. For example, the Special Master has jurisdiction over the first five years of long-term monitoring under the Sediment Consent Order. Oversight during these five years shall be an enumerated responsibility, but any continued oversight of long-term monitoring, pursuant to the extension of the Special Master's jurisdiction beyond the first five years, as provided in paragraph 60 of the Sediment Consent Order, shall not be an enumerated responsibility. Such extensions of jurisdiction shall be effective only so long as specific enumerated responsibilities in any order, decree, or judgment have not been fulfilled.

**J. Initial Financial Assurances**

91. **Chromium Remedy Letter of Credit.** Honeywell shall obtain a one-year, irrevocable letter of credit (the "Chromium Remedy Letter of Credit") to be automatically renewed annually in an amount equal to the "Remedial Costs Subject to Financial Assurance."

(a) Remedial Costs Subject to Financial Assurance shall mean:

(i) The costs of implementing the Chromium Remedy calculated using factors, including inflation and discount rates, determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process;

(ii) The costs of monitoring and maintenance activities for five years, as required by the Long-Term Monitoring Plan, calculated using factors including inflation and discount rates determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process; and

(iii) A contingency of 25% with respect to those costs listed in paragraphs 91(a)(i) and 91(a)(ii).

(b) The Chromium Remedy Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution, provided that in either case, the financial institution shall be acceptable to the Special Master.

92. **Procedures for Review of the Proposed Chromium Remedy Letter of Credit.** No later than December 31, 2008, Honeywell shall submit to Riverkeeper and the Special Master for their review the proposed (a) amount of the Chromium Remedy Letter of Credit; (b) form of the Chromium Remedy Letter of Credit; and (c) name of the institution that will issue the Chromium Remedy Letter of Credit. If Riverkeeper does not agree to the terms of the Chromium Remedy Letter of Credit, the Parties shall meet and confer in an effort to resolve their differences. If the Parties are unable to reach agreement over the terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the Chromium Remedy Letter of Credit.

93. **Automatic Renewal.** The Chromium Remedy Letter of Credit shall be automatically renewed annually unless (a) no later than 120 days prior to the anniversary of the Chromium Remedy Letter of Credit issue date, the issuer provides notice of nonrenewal or (b) Honeywell seeks a reduction in the Chromium Remedy Letter of Credit, pursuant to paragraph 94, to correspond to the reduced estimate of Remedial Costs Subject to Financial Assurances. If the issuer provides notice of nonrenewal, Honeywell shall obtain a replacement irrevocable Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit. If Honeywell is not otherwise in default as provided in Article III.J, the Special Master shall direct the cancellation of the prior Chromium Remedy

Letter of Credit within 91 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit. In the event that the Special Master is entitled to draw upon a Chromium Remedy Letter of Credit because there are two Chromium Remedy Letters of Credit currently in place, the Special Master shall not draw an aggregate amount in excess of the highest valued Chromium Remedy Letter of Credit. Upon Honeywell's request, the Special Master may, at his option, decide not to require overlapping letters of credit in any year based on Honeywell's financial strength in that year, provided that Honeywell has submitted all necessary information so that the Special Master can make his determination at least 150 days prior to the expiration of the Chromium Remedy Letter of Credit.

94. **Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit.** Honeywell shall have the right annually to seek a reduction in the Chromium Remedy Letter of Credit. At the time of seeking such reduction, Honeywell shall submit to the Riverkeeper and the Special Master an estimate of the remaining Remedial Costs Subject to Financial Assurance, including the contingency as described in paragraph 91(a)(iii), and shall seek adjustment of the Chromium Remedy Letter of Credit so that the total estimated amount of remaining Remedial Costs Subject to Financial Assurance are covered by the Chromium Remedy Letter of Credit. However, the adjustment shall not result in reducing the Chromium Remedy Letter of Credit to an amount below the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), plus a contingency of 25% of the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), and shall not result in reducing the Chromium Remedy Letter of Credit to an amount less than $20,000,000 as expressed in 2008 dollars unless long-term financial assurances are in place pursuant to Article III.K. Before making any request to reduce the amount or modify the terms of the Chromium Remedy Letter of Credit, Honeywell shall first confer with the Riverkeeper and

in an effort to reach agreement on the modified amount or terms of the Chromium Remedy Letter of Credit. If the Parties are unable to reach agreement over the modified amount or terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall resolve the dispute. Any Party shall have the right to seek review by the Court of the Special Master's decision regarding the modified amount or terms of the Chromium Remedy Letter of Credit. Upon agreement on the amount of the reduction or modified terms of the Chromium Remedy Letter of Credit (or upon order of the Court directing that the Chromium Remedy Letter of Credit be reduced to an identified amount or otherwise modified), Honeywell shall obtain a replacement Chromium Remedy Letter of Credit in such amount and with such terms. If Honeywell is not otherwise in default as provided in Article III.J and the issuer of the primary Chromium Remedy Letter of Credit has not provided notice of non-renewal, within 30 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit, the Special Master shall direct the cancellation of the prior Chromium Remedy Letter of Credit.

95. **Bankruptcy Protection**. Neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy. The Chromium Remedy Letter of Credit shall contain the language necessary to assure that neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

96. **Exclusive Court Jurisdiction**. The Chromium Remedy Letter of Credit shall recite that the issuer submits to the exclusive jurisdiction of this Court for any and all disputes arising under the Letter of Credit.

97. **Application of New York Law.** The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Chromium Remedy Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

98. **Procedures upon Honeywell's Material Default of Its Obligations.** During the period in which the Special Master has jurisdiction pursuant to paragraph 85, the Chromium Remedy Letter of Credit shall be payable to the Special Master and shall not, prior to its expiration date, be revoked or terminated except consistent with this Consent Decree and with the consent of the Special Master and approval by the Court. The Special Master's ability to draw upon the Chromium Remedy Letter of Credit shall not be limited by any agreement between Honeywell and the issuer. The Special Master may, without further order or notice to this Court, draw upon the Chromium Remedy Letter of Credit upon the occurrence of default by Honeywell, which shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 93 to deliver a replacement Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 15 days after written notice to Honeywell thereof and either (i) Honeywell, in the opinion of the Special Master without further input from the Parties, shall have failed to cure the breach; (ii) during the 15-day period, the Court has not entered an order to prevent the Special Master from

drawing on the Chromium Remedy Letter of Credit; or (iii) the Court or the Special Master has not granted Honeywell additional time to cure the breach;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if involuntary filing has not been dismissed within 60 days; the appointment of a custodian, receiver, liquidator, or trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 98(c), and the failure of Honeywell to provide assurance to the Special Master, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

99. **Placement of Proceeds in Court Registry Investment System Account**. In the event that the Special Master draws upon the Chromium Remedy Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Chromium Remedy Letter of Credit which represent the remaining estimated Chromium Remedy costs under paragraphs 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), in an account with the Court Registry Investment System in accordance with Local Civil Rule 67.1 and not expend the proceeds of the Letter of Credit without further order of this Court. The

Special Master shall place all additional proceeds of the Chromium Remedy Letter of Credit in a trust fund pursuant to paragraph 103(b)(v).

100. **Termination of Chromium Remedy Letter of Credit**. The Chromium Remedy Letter of Credit may be withdrawn in its entirety upon the satisfaction of all of the following:

(a) The implementation of the Chromium Remedy; and

(b) Establishment of long-term financial assurance pursuant to Article III.K.

**K. Long-Term Financial Assurances**

101. **Long-Term Financial Assurances.** Honeywell shall fund long-term financial assurances to ensure that the activities set forth in paragraph 102(a) are carried out regardless of whether Honeywell is financially able to carry out such activities in perpetuity.

102. **Costs Subject to Long-Term Financial Assurances.**

(a) Long-term financial assurances shall provide enough funds to cover the costs of the following activities:

(i) Perpetual monitoring and maintenance of the Chromium Remedy, including installation, operation and monitoring of any above-cap-grade gas collection and/or treatment system as may be necessary, but such system is not part of the 100% Design;

(ii) Perpetual operation of the shallow groundwater remedies pursuant to paragraphs 69, 70, and 71;

(iii) Perpetual repair of the cap;

(iv) Perpetual replacement of the cap on a 75-year replacement interval; and

(v) The perpetual administration of the trust fund regardless of whether such trust fund is selected by Honeywell pursuant to paragraph 103(a) or is established from the Long-Term Letter of Credit pursuant to paragraphs 103(b)(ii), 103(b)(v), or 109.

(b) The costs that shall be subject to financial assurances is an amount that will provide the full payment for each of the activities set forth in paragraphs 102(a)(i) through 102(a)(v) plus a 25% contingency when the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to be performed. The costs subject to financial assurances are forward looking because they state an amount valued at the time the funds are needed. As such, they shall be stated in contemporary time as the present value (calculated on the basis of a discount rate of 4.75%) of the estimated future costs of the activities specified in paragraphs 102(a)(i) through 102(a)(v), plus a 25% contingency on those costs.

103. **Long-Term Financial Assurance Mechanisms.** Honeywell shall provide long-term financial assurances in the amount of the costs subject to long-term financial assurances in the form of a trust fund, a letter of credit, or some combination of the two. The selected mechanism(s) shall satisfy the following requirements:

(a) **Trust Fund.** In the event that Honeywell selects a trust fund, Honeywell shall create a trust fund such that it can provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(i) The trust fund shall be at arm's length from Honeywell and shall not be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The trust fund agreement shall contain the language necessary to assure that neither the trust fund nor the earnings of the trust fund shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The trust fund shall be managed by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution managing the

trust fund declares bankruptcy, the Court shall withdraw the funds and appoint another financial institution meeting the requirements of this paragraph to manage the trust.

(iii) No more frequently than once per year, Honeywell may apply to the Court for an order directing the trust manager to reimburse Honeywell for any costs that it has incurred to carry out the activities set forth in paragraphs 102(a)(i) through 102(a)(iv).

(b) **Long-Term Letter of Credit**. In the event that Honeywell selects a letter of credit, Honeywell shall obtain a one-year irrevocable letter of credit (the "Long-Term Letter of Credit") to be automatically renewed annually in an amount that provides sufficient funds such that a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a), could be created. The Long-Term Letter of Credit-funded trust, plus any trust fund established under paragraph 103(a), shall provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The amount of any Long-Term Letter of Credit shall therefore be adjusted periodically as the cap replacement interval is approached because, for example, the money needed in the 10th year to fund a trust that can provide for replacement of the cap in the 75th year is much less than the money that would be needed in the 40th year. Such periodic adjustments shall be proposed and approved by the Court in conjunction with the adjustments under paragraph 106.

(i) Neither the Long-Term Letter of Credit nor the proceeds of the Long-Term Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The Long-Term Letter of Credit shall contain the language necessary to assure that neither the Long-Term Letter of

Credit nor the proceeds of the Long-Term Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The Long-Term Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution issuing the Long-Term Letter of Credit declares bankruptcy, the Court shall authorize the drawing of funds from the Long-Term Letter of Credit and shall deposit those funds in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(iii) The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits) as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Long-Term Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

(iv) The Long-Term Letter of Credit shall be automatically renewed annually, unless, no later than 120 days prior to the anniversary of the Long-Term Letter of Credit issue date, the issuer provides notice of non-renewal. If the issuer provides notice of non-renewal, Honeywell shall obtain a replacement irrevocable Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit. If Honeywell is not otherwise in default as provided in this Article, the Court shall direct the cancellation of the prior Long-Term Letter of Credit within 91 days after delivery to the Court of any replacement of a Long-Term Letter of Credit. In the event that the Court is entitled to draw upon a Long-Term Letter of Credit when there are two Letters of Credit currently in place, the Court shall not draw an aggregate amount in excess of the highest valued Long-Term Letter of Credit.

(v) Prior to the expiration of the Special Master's appointment pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Special Master. During the time the Long-Term Letter of Credit is payable to the Special Master, the Special Master may draw on the Long-Term Letter of Credit as provided in paragraph 98. In the event that the Special Master draws upon the Long-Term Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a). After the Special Master's appointment expires pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Court and, in the event that the Court draws on the Long-Term Letter of Credit, the Court shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(vi) Whether the Long-Term Letter of Credit is payable to the Special Master or the Court, it shall not, prior to its expiration date, be revoked or terminated by Honeywell except consistent with this Consent Decree and with the approval of the Court. The ability of the Special Master or the Court to draw upon the Long-Term Letter of Credit shall not be limited by any agreement between Honeywell and the issuer.

(vii) In the event that the Long-Term Letter of Credit is drawn upon and invested pursuant to paragraph 103(b)(ii), 103(b)(v), or 109 and Honeywell has also selected a trust fund pursuant to paragraph 103(a), resulting in the existence of two trust funds, the two trust funds shall be managed so as to ensure that the combined amount of the trust funds is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(c) **Combination**. Honeywell may use some combination of a trust fund and a letter of credit to achieve the requirements of this paragraph. However, if a combination is used, Honeywell shall ensure that the combined amount of financial assurances is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The trust fund and the letter of credit shall otherwise satisfy all the requirements of paragraphs 103(a) and 103(b).

104. **Procedures for Review of the Proposed Long-Term Financial Assurances**. No later than June 1, 2009, Honeywell shall submit to Riverkeeper and the Special Master, for their review (a) the amount of the proposed long-term financial assurances; (b) the form(s) of the proposed long-term financial assurance mechanisms; and (c) the name(s) of the institution proposed to manage or issue the long-term financial assurances. If Riverkeeper agrees to the terms of the proposed long-term financial assurances, within 60 days of such agreement, Honeywell shall create a trust fund and/or secure a Long-Term Letter of Credit on those terms. If the Parties are unable to reach agreement over the terms of the long-term financial assurances, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the financial assurances.

105. **Temporary Maintenance of Chromium Remedy Letter of Credit**. Until the long-term financial assurances have been put into place, Honeywell shall maintain the Chromium Remedy Letter of Credit required by paragraph 91 in an amount equal to at least $20,000,000 in 2008 dollars. In the event of any default by Honeywell pursuant to paragraph 98 while the Chromium Remedy Letter of Credit is in place, the provisions of paragraph 103(b)(v) for the placement of the proceeds that exceed the remaining estimated Chromium Remedy costs under

paragraph 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), shall apply.

106. **Adjustment of Amount Held in Long-Term Financial Assurances**. Every five years as marked from the establishment of the first long-term financial assurances pursuant to paragraph 103, the Parties shall report to the Court whether the long-term financial assurances are adequately funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. At such time as the Parties report to the Court, any Party may seek an adjustment in the amount of the long-term financial assurances. The Party seeking an adjustment must demonstrate that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Such demonstration shall reflect the actual costs of implementing the remedy and/or any replacement of the remedy, once such actual costs are available. The demonstration shall also reflect the costs of work completed to date and the actual lifetime of the cap, once the cap has been replaced or has passed a replacement interval without requiring replacement. The demonstration shall further reflect the actual performance of the fund and its ability to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Any demonstration shall be forward looking and shall be based upon estimates of what the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to cost at the time they must be performed and the amount of funding projected to be available to undertake such activities at the time they must be performed. If, after reviewing the submission(s) received from the Parties, the Court determines that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to

long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary, the Court shall order an adjustment in the amount held in the long-term financial assurances to overcome the shortage or overage. In the event that the Court determines that the long-term financial assurances are under-funded, it shall order Honeywell to increase the amount held in the long-term financial assurances. In the event that the Court determines that any trust fund established pursuant to paragraph 103(a) is over-funded, the Court shall issue an order directing the trust manager to pay the overage to Honeywell. In the event that the Court determines that the Long-Term Letter of Credit is over-funded, the Court shall issue an order permitting Honeywell to reduce the amount covered during the next annual renewal of the Long-Term Letter of Credit pursuant to paragraph 103(b)(iv). Any adjustment to the amount of the Long-Term Letter of Credit pursuant to this paragraph shall be in addition to any adjustment of the amount of the Long-Term Letter of Credit required pursuant to paragraph 103(b).

107. **Exclusive Court Jurisdiction**. The trust fund agreement and/or the Long-Term Letter of Credit shall recite that the trust fund manager and/or issuer of the Long-Term Letter of Credit submit to the exclusive jurisdiction of this Court for any and all disputes arising under the trust fund or the Long-Term Letter of Credit. The requirements of this paragraph shall apply whether the trust fund is established pursuant to paragraph 103(a), 103(b)(ii), 103(b)(v), or 109.

108. **Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired.** Upon the occurrence of default by Honeywell, after the Special Master's appointment has expired, Riverkeeper may move the Court on an expedited basis for an order to withdraw funds from the trust fund or to draw on the Long-Term Letter of Credit. Default shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 103(b)(iv) to deliver a replacement Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 30 days after written notice by Riverkeeper to Honeywell of the alleged material failure, unless Honeywell cures the alleged breach within the 30-day notice period or such longer period as the Parties may agree to or the Court may order;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if the involuntary filing is not dismissed within 60 days; the appointment of a custodian, receiver, liquidator, trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 108(c), if Honeywell fails to provide assurance to Riverkeeper, and the Court, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

109. **Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default.** If the Court grants any motion by Riverkeeper or pursuant to paragraph 108 to draw on the Long-Term Letter of Credit, the sum approved by the Court's order granting the motion shall be

paid from the Long-Term Letter of Credit into a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

110. **Use of the Trust Fund in the Event of Honeywell's Default.** In the event of Honeywell's default, as defined in paragraphs 108(a) through 108(d), the money in the trust fund established pursuant to paragraph 103(a) shall be available to meet the obligations of paragraph 102(a), as well as for payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

111. **Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109.** In the event that a trust fund is established pursuant to paragraph 99, 103(b)(ii), 103(b)(v), or 109, the money in the trust fund shall be available to meet the obligations of paragraph 102(a), as well as for the payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

112. **Termination of the Long-Term Financial Assurances.** Honeywell's obligations under Article III.K shall be terminated and the long-term financial assurance mechanisms shall be terminated when the Court finds that no hexavalent or total chromium contamination remains in the Open Space AOC or on the Site, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive

standards for Unrestricted Use in place at the time, whichever is more restrictive. Upon determining that long-term financial assurances may be terminated, the Court shall order that any Long-Term Letter of Credit may be withdrawn in its entirety and any trust fund may be terminated. In conjunction with its order terminating any trust fund, the Court in its discretion shall designate a recipient(s) of any remaining trust funds.

## ARTICLE IV: TERMINATION

113. **Termination of this Consent Decree**. This Consent Decree shall terminate upon the withdrawal of any Party as provided for in this paragraph. Any Party may elect to withdraw from this Consent Decree due to the occurrence of one or more of the following events, provided that such Party provides written notice of withdrawal to the other Parties pursuant to paragraph 118:

(a) The Court fails to enter this Consent Decree or this Consent Decree is determined to be invalid on appeal; or

(b) NJDEP takes one of the following actions with respect to the Remedial Action Work Plan:

(i) Rejects or fails to approve the Remedial Action Work Plan for the Chromium Remedy within 180 days of submission of the plan;

(ii) Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in more than a 50% increase in the estimated costs of the Chromium Remedy as set forth in Article III; or

(iii)Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in a substantial reduction of the protection of human health and/or the environment.

114. **Procedures for Withdrawal and Termination.** Any Party electing to withdraw pursuant to paragraph 113 and thereby terminate this Consent Decree shall provide written notice of such withdrawal and termination to all other Parties within 30 days of the occurrence giving rise to the decision to withdraw. If any Party objects to termination of the Consent Decree, or believes that the conditions set forth in paragraph 113 have not been met, such objecting Party may move the Court for an expedited hearing on the issue of whether the conditions for termination have been effectuated.

115. **Good-Faith Obligation to Avoid Termination.** The Parties agree that they will each endeavor to fulfill the terms of this Consent Decree, that they will work diligently and in good faith to meet their obligations hereunder, and that they will promptly and timely take all reasonable steps to give effect to this Consent Decree and to avoid termination under paragraph 113.

116. **Effect of Termination.** If this Consent Decree is terminated pursuant to paragraph 113, the Consent Decree shall no longer be binding on the Parties and shall be of no further effect. In the event that this Consent Decree is terminated by one or more Parties pursuant to paragraph 113, each Party to this Consent Decree reserves all of its rights, claims, and defenses (both legal and factual) against the other Parties with respect to the matters at issue in the Consolidated Litigation and each Party remains free to pursue such rights, claims, and defenses.

## ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC

117. **Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC.** The transfer of title of Study Area 6 South and Study Area 7 properties to Bayfront Redevelopment LLC pursuant to the Jersey City/Honeywell Consent Order and any subsequent transfers shall not impede Honeywell's obligations to (a) complete the remediation of

Study Area 7 and implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or (b) complete the Chromium Remedy and conduct long-term monitoring and fulfill its other obligations set forth in this Consent Decree. Such transfers of Study Areas 6 South and Study Area 7 shall not include a transfer of Honeywell's obligations to implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or a transfer of Honeywell's obligations under this Consent Decree, but shall include a right of access or any other right required by Honeywell to complete the remediation. Any subsequent transfer of Study Area 6 South or Study Area 7 from Bayfront Redevelopment LLC to a redeveloper or other party shall provide all necessary agreements to allow Honeywell all necessary access to Study Area 6 South and Study Area 7 for purposes of completing Honeywell's obligations with respect to Study Area 6 South under this Consent Decree and completing the Study Area 7 remediation and implementing the Final Judgment and subsequent orders in *ICO v. Honeywell*.

## ARTICLE VI: NOTICE

118. **Notice**. Any and all notices given in connection with this Consent Decree shall be deemed adequately given only if in writing and addressed to the Party for whom such notices are intended at the addresses set forth in this paragraph. All notices shall be sent by Federal Express or other nationally recognized overnight messenger service or by first-class registered or certified mail, postage prepaid, return receipt requested. A written notice shall be deemed to have been given to the recipient party on the earlier of (a) the date it shall be delivered to the address set forth in this paragraph; (b) the date delivery shall have been refused at the address set forth in this paragraph; or (c) with respect to notices sent by mail, the date as of which the postal service shall have indicated such notice to be undeliverable at the address set forth in this paragraph.

Any and all notices referred to in this Consent Decree, or which any Party desires to give to the other, shall be addressed as follows:

If to Honeywell and/or
Bayfront Redevelopment LLC :

Tom Byrne, Esq.
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-2775

With copies to:

John Morris
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-4003

If to Jersey City:

William Matsikoudis
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NJ 07305
(201) 547-4667

If to Riverkeeper:

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th St., N.W.
Washington, DC 20005-4632
(202) 682-2100

Any party may change its designated recipients or addresses for notice in this paragraph by providing written notice of such change to all other Parties.

## ARTICLE VII: RIVERKEEPER'S ATTORNEYS' FEES

119. **Payment of Past Fees and Expenses.** Within 30 days of the entry of this Consent Decree, Honeywell shall pay Terris, Pravlik & Millian, LLP the sum of $813,000.00 which represents the following:

(a) A compromise of the attorneys' fees incurred by Riverkeeper in the litigation of Study Area 6 South portion of *Riverkeeper v. Honeywell* through August 31, 2008; and

(b) $353,746.67 in out-of-pocket expenses representing a portion of the expenses incurred by Riverkeeper in *Riverkeeper v. Honeywell* from the inception of the litigation after deducting the expenses paid pursuant to the Sediment Consent Order, the Deep Groundwater Consent Order, and the Study Area 6 North Consent Decree.

(c) Payment of the sum of $813,000.00 shall be in full satisfaction of all obligations, duties, and responsibilities of Honeywell with respect to the $879,317.92 in fees and expenses that Riverkeeper claimed with regard to the above described fees and expenses.

120. **Future Fees and Expenses.** Honeywell shall reimburse Riverkeeper's attorneys for reasonable fees and expenses incurred: (a) in negotiating this Consent Decree after August 31, 2008; (b) in the monitoring and enforcement of this Consent Decree; and (c) in participation in the Special Master process established pursuant to this Consent Decree. Honeywell shall also reimburse Riverkeeper for reasonable attorneys' fees and expenses for Riverkeeper's review of and participation in the Long-Term Monitoring Plan and monitoring and enforcement of this Consent Decree following the term of the Special Master. In the event that any dispute arises between the Parties under this Consent Decree that must be resolved by the Court, Riverkeeper shall be entitled to recover its attorneys' fees and expenses for litigation of the dispute to the extent allowed by federal law. Riverkeeper and Honeywell shall use the same informal procedure for attempting to settle fees issues as has been used for post-judgment monitoring fees in *ICO v. Honeywell*. In the event that Riverkeeper and Honeywell are unable to reach a settlement on fees, Riverkeeper shall apply to the Court for an award of attorneys' fees and expenses. If Honeywell objects to only a portion of the Riverkeeper's statement of attorneys' fees and expenses, Honeywell shall pay the undisputed portion within 60 days of Riverkeeper's submittal of the statement to Honeywell. The Court shall resolve any objections to

Riverkeeper's statement of attorneys' fees and expenses and shall enter an appropriate Order. In the event of Honeywell's default, Riverkeeper may seek attorneys' fees from any trust fund or court registry funds established pursuant to the financial assurances provisions of this Consent Decree.

## ARTICLE VIII: MISCELLANEOUS PROVISIONS

121. **Force Majeure.** Force Majeure, for the purposes of this Consent Decree, is defined as an event arising from causes beyond the control of any Party or Parties (or their agents, contractors, subcontractors, representatives, or assigns) which could not have been overcome by reasonable diligence and which delays or prevents the performance of any obligation under this Consent Decree. Examples of events which may constitute force majeure include the refusal of any federal or state governmental authority to grant a permit or authorization necessary for the completion of actions required by this Consent Decree, floods, hurricanes, tornadoes, and other extraordinary weather events, earthquakes and other natural disasters, terrorist attacks, war, and other national emergencies. Examples of events that are not force majeure events include normal inclement weather, increased costs or expense, the failure to timely and fully apply for a permit or authorization necessary for the completion of actions required by this Consent Decree, or financial difficulty of any Party. The Party claiming force majeure shall bear the burden of showing an event was a force majeure event.

122. **Bayfront Redevelopment LLC as a Party.** As a signatory to this Consent Decree, Bayfront Redevelopment LLC subjects itself to the Court's jurisdiction for the purpose of enforcing this Consent Decree and agrees to be bound by this Consent Decree. This Consent Decree shall be fully enforceable against Bayfront Redevelopment LLC.

123. **Successors and Assigns.** This Consent Decree shall be binding upon and shall inure to the benefit of the successors, assigns, heirs, corporate parents, subsidiaries, and affiliates of each Party. No assignment or delegation of the obligations hereunder shall release the assigning Party from its obligations under this Consent Decree.

124. **Successors to Hackensack Riverkeeper, Inc.** In the event that Hackensack Riverkeeper, Inc. disbands or otherwise ceases operations, it shall assign its rights under this Consent Decree to another qualified nonprofit organization. A nonprofit organization shall be qualified for assignment under this Consent Decree if it is a charitable organization under Section 501(c)(3) of the Internal Revenue Code or its substantial equivalent and has an established record of working to enhance or preserve the ecology, natural habitat, or environment. Any such assignment shall be subject to approval by the Court and Honeywell shall have the right to object to any proposed assignment. Any successor organization shall have the duty to assign its rights under this Consent Decree to another qualified nonprofit organization in the event that the successor disbands or otherwise ceases operations. In the event that a successor is not appointed at any given time, the New Jersey Attorney General or equivalent officer shall appoint a successor subject to approval by the Court and objection by Honeywell.

125. **Reservation of Rights and Claims.** Except as set forth expressly herein, this Consent Decree does not affect in any way any of the Parties' claims or defenses against third parties who have not signed the Consent Decree.

126. **Governing Law and Continuing Jurisdiction.** The Court shall retain jurisdiction over the matters addressed in this Consent Decree for purposes of enabling the Parties to apply to the Court for any further order as may be necessary to construe, carry out, or enforce the terms of this Consent Decree. This Consent Decree shall be interpreted and enforced under the laws of

the United States and the State of New Jersey by the United States District Court for the District of New Jersey.

127. **Construction.** Questions regarding the interpretation of this Consent Decree shall not be resolved against any Party on the ground that this Consent Decree has been drafted by that Party. This Consent Decree is the result of review, negotiation, and compromise by each Party.

128. **Authority to Enter into Agreement.** The undersigned representative for each Party represents, certifies, and warrants that he or she is duly authorized by the Party whom he or she represents to enter into the terms of this Consent Decree and bind such Party legally to this Consent Decree.

129. **Measures to Effectuate This Consent Decree.** Jersey City shall take all appropriate steps to ensure that commitments it has agreed to with regard to the Open Space AOC have been duly considered, ratified, and approved. Such steps include consideration of such commitments and an effectuating ordinance at a meeting of the City Council, open to the public, at which members of the public have the opportunity to comment on all aspects of the commitments made by Jersey City..

130. **Modifications.** This Consent Decree may be modified by mutual agreement of the Parties but such agreement must be in writing, duly and properly signed by all Parties, and shall be submitted to the Court for approval.

131. **Severability.** Each of the provisions in paragraph 74 of this Consent Decree shall be deemed severable and, in the event that one or more of such provisions is deemed invalid or unenforceable, it shall not affect the validity or enforceability of the other provisions of the Consent Decree.

132. **Signatures.** This Consent Decree may be signed simultaneously or in counterparts by the respective signatories, which shall be as fully valid and binding as if a single document was signed by all of the signatories. This Consent Decree may be signed electronically by any or all signatories, and such electronic signature shall be as fully valid and binding as a hand-written signature.

Consented to and approved for entry:

*s/Aurelio Vincitore*

William Matsikoudis
Aurelio Vincitore
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NY 07305
(201) 547-4667

*Counsel for the City of Jersey City*

*s/ David Sheehan*

David Sheehan
Baker Hostetler
45 Rockefeller Plaza
11th Floor
New York, NY 10111
(212) 589-4200

Michael D. Daneker
Arnold & Porter LLP
555 12th Street N.W.
Washington, DC 20004
(202) 942-5000

*Counsel for Honeywell International Inc. and Bayfront Redevelopment LLC*

*s/ Edward Lloyd*

Edward Lloyd
Columbia Law School
435 West 116th Street, Room 831
New York, NY 10027
(212) 854-4376

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th Street N.W.
Washington, DC 20005-4632
(202) 682-2100

*Counsel for the Hackensack Riverkeeper, William Sheehan, Reverend Winston Clarke, and Lawrence Baker*

APPROVED AND ENTERED as an Order of this Court this ___ day of _____, 2012.

Hon. Dennis M. Cavanaugh
United States District Judge

## EXHIBITS

**Exhibit A:** Remedial AOC's and Remedial Approach Map

**Exhibit B:** NJDEP Chromium Policy

**Exhibit C:** Conservation Restriction

**Exhibit D:** Deed Notice

**Exhibit E:** Additional Boring Locations

# Deed Notice

*Dated: _____, 2017*

**BAYFRONT REDEVELOPMENT LLC**

Grantor(s).

*Record and return to:*

**Waters, McPherson, McNeill, P.C.**
**P.O. Box 1560**
**300 Lighting Way**
**Secaucus, New Jersey 07096-1560**

**ATTN: _____, Esq**

**DRAFT DEED NOTICE**

IN ACCORDANCE WITH N.J.S.A. 58:10B-13, THIS DOCUMENT IS TO BE RECORDED IN THE SAME MANNER AS ARE DEEDS AND OTHER INTERESTS IN REAL PROPERTY.

Prepared by: _____
[Signature]

_____
[Bayfront Redevelopment LLC]

Recorded by:

_____
[Signature, Officer of County Recording Office]

_____
[Print name below signature]

# DEED NOTICE CONCERNING CONTROLS INSTALLED FOR CHROMIUM AND HISTORIC FILL CONTAMINATION UNDERLYING THE PROPERTY

This Deed Notice is made as of the __ day of _____, 2017, by ***Bayfront Redevelopment LLC, whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950***. "Owner" shall mean Bayfront Redevelopment LLC together with its successors and assigns, including all successors in interest in the Property which is the subject of this Deed Notice as described fully below. The Property (also referred to herein as the "Restricted Area(s)") shall consist of those lands particularly described by metes and bounds in Exhibit A-2 attached.

1. THE PROPERTY. Bayfront Redevelopment LLC is the current owner in fee simple of certain real property designated as a portion of ***Block 24601, Lot 11 on the tax map of the City of Jersey City, Hudson County, New Jersey***[1]; the New Jersey Department of Environmental Protection Program Interest Number for the contaminated site which includes this property is ***Hudson County Chromate Site No. 163 (a.k.a. Posnak & Turkish) Program Interest ("PI") #010374*** [NJDEP PI# for non-chromium-related contaminants at the Property is #745719], and known as the Site 163

[1] All references to Block 24601 Lot 11 in this Deed Notice shall mean the applicable portions of Block 24601 Lot 11 as shown in the metes and bounds description, regardless of whether the word "portion(s)" is specifically called out or not.

Development Area of Concern ("AOC") pursuant to the First Amended Consent Decree Regarding the Remediation and Redevelopment of Study Area 6 South ("Consent Decree") which is attached hereto as Appendix I and is entered as an order of the Court in the following consolidated actions *JCMUA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-05955; *JCIA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-5993; and *Hackensack Riverkeeper, Inc. v. Honeywell International, Inc.,* D.N.J., Civ. No. 06-22 (consolidated under Civ. No. 95-2097). The Property is part of Study Area 6 South ("SA-6 South"), a group of sites containing chromium contamination being addressed by Honeywell International Inc. ("Honeywell") as described in Paragraph 3. The Property is located along Droyers Cove as shown in Exhibit B-1 attached hereto.

This deed notice applies only to a portion of the Site 163 Development AOC which will become the Future Kellogg Street/Riverside Drive/Riverwalk during site redevelopment. The Consent Decree restricts transfer, use and development of the Property. To the extent that there is any conflict or inconsistency between the terms of this Deed Notice and the terms of the Consent Decree, the Consent Decree shall govern.

2. REMEDIATION.

i. The Department's Bureau of State Case Management (BCM) is the entity within the Department that is responsible for the chromium oversight of the remediation of the SA-6 South. The matter was Hudson County Chromate Site No. 163 PI No. 010374. The Department has approved this Deed Notice as an institutional control for the Property, which is part of the remediation of the Property.

ii. N.J.A.C. 7:26-C-7 requires the Owner, among other persons, including the responsible party Honeywell International Inc. ("Honeywell"), to obtain a soil remedial action permit for the soil remedial action at the Property. That permit will contain the monitoring, maintenance and biennial certification requirements that apply to the Property.

3. SOIL AND GROUNDWATER CONTAMINATION. Honeywell, a corporation of the State of Delaware, licensed to do business in the State of New Jersey whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950, has remediated SA-6 South to address chromium-related and non-chromium soil and shallow groundwater contamination, except for the Property and certain other deed noticed areas where engineering controls were implemented. The Remedial Action Work Plan ("RAWP") for chromium remedial actions was approved by the Department on June 22, 2012 for Hudson County Chromate Site No. 163, which includes remedial actions for chromium at the Property. The RAWP for non-chromium remedial actions pertaining to Site 163 was submitted to the Licensed Site Remediation Professional on March 21, 2011. Remedial actions were further approved pursuant to the Consent Decree.

Under both the Consent Decree and the RAWP, soil contamination remains at the Site 163 Property which contains contaminants at concentrations that do not allow for the unrestricted use of the Property. A Remedial Action Report ("RAR") was submitted to the Department on February 8, 2017. The Department approved the RAR on March 30, 2017. A Construction Completion Report ("CCR") for SA-6 South to document the implementation of the Chromium Remedy pursuant to Article III of the Consent Decree (the "Chromium Remedy") to address chromium-impacted soil

and groundwater for SA-6 South was entered by the Court on [DATE], [CITE TO DOCKET AND DOCKET #].

The Property is a portion of Site 163 at SA-6 South where remaining chromium-impacted soils were identified in the area south of the northern curbline of the future River Front Park/Riverside Drive/Kellogg Street. This deed notice area includes chromium and historic fill. The engineering control barrier on the Property includes clean fill material to a depth of approximately 4-feet below ground surface. During redevelopment of the Property additional engineering control barriers in the form of a roadway, walkway, and/or other hardscape will be constructed on the Property as required by paragraph 61(c)(ii)(3) of the Consent Decree. Honeywell will, or cause Bayfront Redevelopment LLC to, restrict the future use of this area by implementing a conservation restriction, which will be been recorded at the Hudson County Register of Deeds, and transfer, or cause Bayfront Redevelopment LLC to transfer, title to the City of Jersey City (as called for in Paragraph 61(c)(ii)(3) of the Consent Decree). The provisions of the Long Term Monitoring Plan ("LTMP"), developed pursuant to the Consent Decree, will apply to the Property.

The soil contamination is described, including the type, concentration and specific location of such contaminants, in Exhibit B, which is attached hereto and made a part hereof. Groundwater contaminant concentrations and restrictions for SA-6 South in its entirety are addressed in the Classification Exception Area (CEA) approved by the NJDEP on February 16, 2012 and in a forthcoming Remedial Action Permit for Groundwater (recent groundwater samples for the Property do not indicate shallow groundwater contamination). As a result of the remaining soil contamination, there is a statutory requirement for this Deed Notice and engineering controls in accordance with N.J.S.A. 58:10B-13. Under the terms of the Consent Decree and this Deed Notice, Honeywell is responsible for monitoring and maintaining the soil remediation for the Property in perpetuity.

4. CONSIDERATION. In accordance with the Department's approval of the chromium and non-chromium RAWPs for the remediation for the Hudson County Chromate Site No. 163 which includes the Property, and in consideration of the terms and conditions of that approval, and in accordance with the Consent Decree, and other good and valuable considerations, Owner has agreed to subject the Property to certain statutory and regulatory requirements which impose restrictions upon the use of the Property, to restrict certain uses of the Property, and to provide notice to subsequent owners, lessees and operators of the restrictions and the monitoring, maintenance, and biennial certification requirements outlined in this Deed Notice and required by law, as set forth herein.

5A. RESTRICTED AREAS. Due to the presence of contamination remaining at concentrations that do not allow for unrestricted use, Owner has agreed, as part of the remedial action for the Property, to restrict the use of the Property (the "Restricted Areas"); a narrative description of these restrictions, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C, which is attached hereto and made a part hereof. Owner will develop a binder containing a list of these restrictions which will be maintained either on on-site trailers or within the Groundwater Treatment Plant building, available for inspection by governmental enforcement officials if requested.

5B. RESTRICTED LAND USES. The following land use restrictions apply to the Property:

i. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(10), prohibits the conversion of a contaminated site, remediated to non-residential soil remediation standards that require the maintenance of engineering or institutional controls, to a child care facility, or public, private, or charter school without the Department's prior written approval, unless a presumptive remedy is implemented;

ii. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(12), prohibits the conversion of a landfill, with gas venting systems and or leachate collection systems, to a single family residence or a child care facility without the Department's prior written approval;

iii. The Consent Decree, paragraph 61(c), restricts the ownership, use, and development of the Property; and

iv. The Conservation Restriction, to be recorded with the Hudson County Register of Deeds, will restrict the use and development of the Property.

5C. ENGINEERING CONTROLS. Due to the presence and concentration of these contaminants, the Owner has also agreed, as part of the remedial action for the Property, to the placement of certain engineering controls on the Property. A narrative description of these engineering controls, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C. Honeywell shall be responsible for monitoring and maintenance of engineering controls and biennial certification requirements as specified in the Consent Decree, the LTMP, and Paragraphs 8A and 8B herein.

5D. LONG TERM MONITORING PLAN. Pursuant to the Consent Decree, Honeywell has developed an LTMP which sets forth requirements for monitoring, maintaining, and repairing or and replacing the soil and groundwater chromium remedial measures including engineering controls within the Property, and requirements for notification and reporting pursuant to the Consent Decree, Deed Notice, and Soil Remedial Action Permit. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950. This Deed Notice is appended to the LTMP.

5E. WORKER TRAINING MATERIALS. All maintenance workers engaged in maintenance at the Property shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy Workers shall be trained using materials developed by Honeywell pursuant to the Consent Decree.

6A. CHANGE IN OWNERSHIP AND REZONING.

i. The Owner and the subsequent owners and lessees, shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall

be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. The Owner and the subsequent owners shall provide written notice to the Department of Environmental Protection on a form provided by the Department and available at www.nj.gov/srp/forms within thirty (30) calendar days after the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property.

iii. The Owner and the subsequent owners shall provide written notice to the Department, on a form available from the Department at www.nj.gov/srp/forms, within thirty (30) calendar days after the owner's petition for or filing of any document initiating a rezoning of the Property to residential.

6B. SUCCESSORS AND ASSIGNS. This Deed Notice shall be binding upon Owner and upon Owner's successors and assigns, and subsequent owners, lessees and operators while each is an owner, lessee, or operator of the Property.

7A. ALTERATIONS, IMPROVEMENTS, AND DISTURBANCES.

i. The Owner and all subsequent owners and lessees shall notify any person of whom it has knowledge, including, without limitation, tenants, employees of tenants, developers, and contractors, intending to conduct invasive work or excavate within the Restricted Areas, of the nature and location of known contamination in the Restricted Areas, and, of the precautions necessary to protect the engineering controls and minimize potential human exposure to contaminants.

ii. Except as provided in the Consent Decree and Paragraph 7B below, no person shall make, or allow to be made, any alteration, improvement, or disturbance in, to, or about the Property which disturbs any engineering control at the Property except as (a) permitted in the Consent Decree and Conservation Restriction, and (b) without first obtaining a Soil Remedial Action Permit modification from the Department. Nothing herein shall constitute a waiver of the obligation of any person to comply with all applicable laws and regulations including, without limitation, the applicable rules of the Occupational Safety and Health Administration.

iii. Notwithstanding subparagraph 7A.ii.(b), above, a Soil Remedial Action Permit modification is not required for any alteration, improvement, or disturbance provided that:

(A) Such action is taken in conformance with the Consent Decree and this Deed Notice; and

(B) The Department of Environmental Protection is notified of the activity by calling the DEP Hotline, at 1-877-WARN-DEP or 1-877-927-6337, within twenty-four (24) hours after the beginning of each alteration, improvement, or disturbance; and

(C) Honeywell is notified of the activity by calling 855-727-2658; and

(D) Honeywell and/or the owner restores any disturbance of an engineering control to pre-disturbance conditions, consistent with the requirements of the Consent Decree and LTMP, within sixty (60) calendar days after the initiation of the alteration, improvement or disturbance; and

(E) All applicable worker health and safety laws and regulations are followed during the alteration, improvement, or disturbance, and during the restoration; and

(F) Appropriate measures are taken so that human exposure, and exposure of the environment outside the containment of the engineering controls, to contamination in excess of the applicable remediation standards does not occur; and

(G) The next biennial certification includes a description of the nature of the alteration, improvement, or disturbance, the dates and duration of the alteration, improvement, or disturbance, the name of key individuals and their affiliations conducting the alteration, improvement, or disturbance, a description of the notice the Owner gave to those persons prior to the disturbance, the amounts of soil generated for disposal, if any, the final disposition and any precautions taken to prevent exposure.

7B. EMERGENCIES. In the event of an emergency which presents, or may present, an unacceptable risk to the public health and safety, or to the environment, or immediate environmental concern, see N.J.S.A. 58:10C-2, any person may temporarily breach an engineering control provided that:

i. The Department of Environmental Protection is immediately notified of the emergency, by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

ii. Immediately after notifying NJDEP, Honeywell is notified of the emergency by calling 855-727-2658; and

iii. Both the actual disturbance and the time needed for the disturbance are limited to the minimum reasonably necessary to adequately respond to the emergency; and

iv. All measures necessary to limit actual or potential, present or future risk of exposure to humans or the environment to the contamination are implemented; and

v. The Department of Environmental Protection is notified when the emergency has ended by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

vi. Honeywell is notified when the emergency has ended by calling 855-727-2658; and

vii. Honeywell restores the engineering control to the pre-emergency conditions, consistent with the requirements of the Consent Decree and LTMP, as soon as possible, and submits a written report to the Department of Environmental Protection of such emergency and restoration efforts within sixty (60) calendar days after completion of the restoration of the engineering control. The report must include all information pertinent to the emergency, potential discharges of

contaminants, and restoration measures that were implemented, which, at a minimum, should specify: (a) the nature and likely cause of the emergency, (b) the potential discharges of or exposures to contaminants, if any, that may have occurred, (c) the measures that have been taken to mitigate the effects of the emergency on human health and the environment, (d) the measures completed or implemented to restore the engineering control, and (e) the changes to the engineering control or site operation and maintenance plan to prevent recurrence of such conditions in the future. Honeywell shall submit the report to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413

8A. MONITORING AND MAINTENANCE OF DEED NOTICE, AND PROTECTIVENESS CERTIFICATION. The persons in any way responsible, pursuant to the Spill Compensation and Control Act, N.J.S.A. 58:10-23.11a et seq., for the hazardous substances that remain at the Property, the persons responsible for conducting the remediation, Honeywell, the Owner, and the subsequent owners, lessees, and operators, shall monitor and maintain this Deed Notice. The subsequent owners, lessees and operators have this obligation only during their ownership, tenancy, or operation. Honeywell shall certify to the Department on a biennial basis that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the deed notice shall include all of the following:

i. Monitoring and maintaining this Deed Notice according to the requirements in Article III of the Consent Decree, and Exhibit C herein, to ensure that the remedial action that includes the Deed Notice continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes this Deed Notice, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

8B. MONITORING AND MAINTENANCE OF ENGINEERING CONTROLS, AND PROTECTIVENESS CERTIFICATION. Honeywell shall maintain all engineering controls at the Property and certify to the Department on a biennial basis that the remedial action of which each engineering control is a part remains protective of the public health and safety and of the

environment. The specific obligations to monitor and maintain the engineering controls shall include the following:

i. Monitoring and maintaining each engineering control according to the requirements in Article III of the Consent Decree, the LTMP, and Exhibit C here, so that the remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes the engineering control remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes the engineering control, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

9. ACCESS. The Owner, subsequent owners, lessees, and operators, agree to allow the Department, its agents and representatives access to the Property to inspect and evaluate the continued protectiveness of the remedial action that includes this Deed Notice and to conduct additional remediation to ensure the protection of the public health and safety and of the environment if the persons responsible for monitoring the protectiveness of the remedial action, as described in Paragraph 8, above, fail to conduct such remediation pursuant to this Deed Notice as required by law. The Owner, and the subsequent owners and lessees, shall also cause all leases, subleases, grants, and other written transfers of an interest in the Restricted Areas to contain a provision expressly requiring that all holders thereof provide such access to the Department.

10. NOTICES.

i. Owner shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. Honeywell or the Owner shall notify any person intending to conduct invasive work or excavate within the Property of the nature and location of contamination and, of the precautions necessary to minimize potential human exposure, and exposure of the environment outside the containment of the engineering controls, to contaminants.

iii. Owner shall provide written notice to the Department of Environmental Protection at least thirty (30) calendar days before the effective date of any conveyance, grant, gift, or other transfer,

in whole or in part, of the owner's interest in the Property . Any such conveyance, grant or gift must be consistent with the terms of the Consent Decree.

iv. Owner shall provide written notice to the Department within thirty (30) calendar days following the Owner's receiving notice of any petition for a rezoning of the Property. Any such rezoning must be consistent with the terms of the Consent Decree. The Owner shall submit the written notice to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413.

11. ENFORCEMENT OF VIOLATIONS.

i. This Deed Notice itself is not intended to create any interest in real estate in favor of the Department of Environmental Protection, nor to create a lien against the Property, but merely is intended to provide notice of certain conditions and restrictions on the Property and to reflect the regulatory and statutory obligations imposed as a conditional remedial action for this Property.

ii. The restrictions provided herein may be enforceable by the Department against any person who violates this Deed Notice. To enforce violations of this Deed Notice, the Department may initiate one or more enforcement actions pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C, and require additional remediation and assess damages pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C.

iii. This Deed Notice is also enforceable in the United States District Court for the District of New Jersey by all residents, owners, lessees, and all commercial tenants on Study Areas 6 and 7 pursuant to paragraphs 80 and 83 of the Consent Decree.

12. SEVERABILITY. If any court of competent jurisdiction determines that any provision of this Deed Notice requires modification, such provision shall be deemed to have been modified automatically to conform to such requirements. If a court of competent jurisdiction determines that any provision of this Deed Notice is invalid or unenforceable and the provision is of such a nature that it cannot be modified, the provision shall be deemed deleted from this instrument as if the provision had never been included herein. In either case, the remaining provisions of this Deed Notice shall remain in full force and effect.

13. MODIFICATION AND TERMINATION.

i. Any person may request in writing, at any time, that the Department modify this Deed Notice where performance of subsequent remedial actions, a change of conditions at the Property, or the adoption of revised remediation standards suggest that modification of the Deed Notice

would be appropriate, provided that any such modification is consistent with the requirements of the Consent Decree.

ii. Any person may request in writing, at any time, that the Department terminate this Deed Notice because the conditions which triggered the need for this Deed Notice are no longer applicable.

iii. Any person seeking a modification or termination of this Deed Notice must also have such modification approved by the United States District Court for the District of New Jersey pursuant to the Consent Decree until such time as the Consent Decree terminates with regard to the Property pursuant to the Consent Decree.

iv. If the United States District Court for the District of New Jersey and NJDEP have concluded that this Deed Notice shall be modified or terminated, such modification or termination will only be effective upon the filing of a Termination of Deed Notice, available at N.J.A.C. 7:26C Appendix C, with the office of the Register of Deeds of Hudson County, New Jersey, expressly modifying or terminating this Deed Notice.

v. Within thirty (30) calendar days after the filing of a Termination of Deed Notice, the owner of the Property shall apply to the Department for modification or termination of the Soil Remedial Action Permit pursuant to N.J.A.C. 7:26C-7.

vi. This Deed Notice may be modified only if it has first been terminated pursuant to subparagraphs 13v above, and upon filing of a modified Deed Notice, executed by the Owner of the Property, in the office of the Register of Deeds of Hudson County, New Jersey.

14A. EXHIBIT A. Exhibit A includes the following maps of the Property and the vicinity:

i. Exhibit A-1: Vicinity Map - A map that identifies by name the roads, and other important geographical features in the vicinity of the Property;

ii. Exhibit A-2: Metes and Bounds Description - A metes and bounds description of the Property, including reference to tax lot and block numbers for the Property and a Tax Map;

iii. Exhibit A-3: Property Map - A scaled map of the Property, scaled at one inch to 200 feet or less, and if more than one map is submitted, the maps shall be presented as overlays, keyed to a base map; the map(s) shall include diagrams of major surface topographical features such as buildings, roads, and parking lots. After development of the Property, this Deed Notice shall be modified to show further engineering controls and topographical features constructed on the Property, such as roads, walkways or other hardscape.

14B. EXHIBIT B. Exhibit B includes the following descriptions of the Restricted Areas:

i. Exhibit B-1: Restricted Area Map - Maps for the Property that include, as applicable:

(A) As-built diagrams of each engineering control, including caps, fences, hydraulic barrier walls, ground water monitoring wells, and ground water pumping system;

(B) As-built diagrams of any buildings, roads, parking lots, utility corridors, and other structures that function as engineering controls; and

(C) Designation of all soil and/or sediment sample locations within the restricted areas that exceed any soil or sediment standard that are keyed into one of the tables described below.

ii. Exhibit B-2 (Table B-2): Restricted Area Data Tables - A separate table for each restricted area that includes either (A) or (B) through (F):

(A) Only for historic fill extending over the entire site or a portion of the site and for which analytical data are limited or do not exist, a narrative that states that historic fill is present at the site, a description of the fill material (e.g., ash, cinders, brick, dredge material), and a statement that such material may include, but is not limited to, contaminants such as PAHs and metals;

(B) Sample location designation from Restricted Area map (Exhibit B-1);

(C) Sample elevation based upon mean sea level;

(D) Name and chemical abstract service registry number of each contaminant with a concentration that exceeds the unrestricted use standard;

(E) The restricted and unrestricted use standards for each contaminant in the table; and

(F) The remaining concentration of each contaminant at each sample location at each elevation (or if historic fill, include data from the Department's default concentrations at N.J.A.C. 7:26E-4.6, Table 4-2).

14C. EXHIBIT C. Exhibit C includes narrative descriptions of the institutional controls and engineering controls as follows:

i. Exhibit C-1A through C. Exhibit C-1A: Institutional Controls; Exhibit C-1B: Consent Decree as Institutional Control (attached); Exhibit C-1C: Zoning as Institutional Control; Exhibit C-1D: Conservation Restriction as Institutional Control (recorded at Hudson County Register of Deeds as indicated in Paragraph 3): Exhibit C-1 (A through D) includes a narrative description of the restrictions and obligations of this Deed Notice that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:

(1) Description and estimated size of the Restricted Areas as described above;

(2) Description of the restrictions on the Property by operation of this Deed Notice and the other Institutional Controls; and

(3) The objective of the restrictions;

(B) Description of the monitoring necessary to determine whether:

(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;

(2) There have been any land use changes subsequent to the filing of this Deed Notice and the other Institutional Controls or the most recent biennial certification, whichever is more recent;

(3) The current land use on the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls;

(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the Property; and

(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice and the other Institutional Controls, and conduct the necessary sampling.

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice and the other Institutional Controls;

(2) Land use at the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls; and

(3) The remedial action that includes this Deed Notice and the other Institutional Controls continues to be protective of the public health and safety and of the environment.

ii. Exhibit C-2. Exhibit C-2: Engineering Controls: Clean Fill Cover; Exhibit C-2 includes a narrative description of the engineering controls as follows:

(A) General Description of the engineering control:

(1) Description of the engineering control;

(2) The objective of the engineering control; and

(3) How the engineering control is intended to function.

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering control;

(4) The engineering control is being inspected and maintained and its integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering control. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering control; and

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling.

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering control continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

15. SIGNATURES. IN WITNESS WHEREOF, Owner has executed this Deed Notice as of the date first written above.

ATTEST: , LLC

_____ By_____
[Signature] [Signature]

_____ _____
[Print name and title] [Print name and title]

STATE OF NEW JERSEY SS.:
COUNTY OF _____

I certify that on _____ ___, 2017, _____ personally came before me, and this person acknowledged under oath, to my satisfaction, that:

(a) this person is the _____ of _____, LLC, the Limited Liability Corporation named in this document;

(b) this person is the attesting witness to the signing of this document by the proper corporate officer who is the _____ of the Limited Liability Corporation;

(c) this document was signed and delivered by the Limited Liability Corporation as its voluntary act and was duly authorized;

(d) this person knows the proper seal of the Limited Liability Corporation which was affixed to this document; and

(e) this person signed this proof to attest to the truth of these facts.

_____
[Signature]

_____
[Print name and title of attesting witness]

Signed and sworn before me on _____, 20__

_____, Notary Public

_____
[Print name and title]

**EXHIBIT A**
**Deed Notice #3 Site 163**

**A-1 Vicinity Map**

**A-2 Metes and Bounds Description and Tax Map**

**A-3 Property Map Portion of Block 24601, Lot 11, City of Jersey City, New Jersey**

Exhibit A-1 Vicinity Map consists of a road map for the vicinity of the Property.

Exhibit A-2 consists of a metes and bounds and a tax map for the Property.


Exhibit A-3 Property Map consists of a figure indicating major surface features and engineering control for the Property. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as buildings, roads, and parking lots.

**Exhibit A-1**
**Site Vicinity Map**
**Jersey City, New Jersey**

EXHIBIT A-1
SITE VICINITY MAP
PORTIONS OF STUDY AREA 6 SOUTH SITE 163
JERSEY CITY, NEW JERSEY

CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\deed notice\deed notice 3\3480150450-5100-A100-3000.dwg Fri, 10 Mar 2017 - 1:35pm scott.rudkin




SOURCE: USGS QUADRANGLE MAP, 7.5 MIN SERIES
JERSEY CITY, NJ-NY 1967, PHOTO REVISED 1981

RESTRICTED AREA

**DRAFT**

0 1000 2000 4000
SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150450<br>*DRAWING:* 3480150450-5100-A100-3000 | |
| *PREPARED/DATE:* STR 01/28/16 | *CHECKED/DATE:* NW 01/31/17 |

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT A-1**
VICINITY MAP
BLOCK 24601, LOT 11
DEED NOTICE #3 SA-6 SOUTH SITE 163
JERSEY CITY, NEW JERSEY

**Exhibit A-2**
**Deed Notice #3 Site 163**
**Metes and Bounds Description of Property: See Attached**
**Tax Map: See Attached**

A-2 Metes and Bounds Description of Property Portion of Block 24601, Lot 11
City of Jersey City, New Jersey

**If there is any discrepancy between the Metes and Bounds and the tax map, or any other maps attached hereto, the Metes and Bounds prevails.**

The Property is identified as a portion of Block 24601, Lot 11 on the City of Jersey City tax maps, the Property being presently owned by Bayfront Redevelopment LLC. A copy of the current tax map which includes the Property is attached as Exhibit A-2.

MASER CONSULTING P.A.
Consulting, Municipal & Environmental Engineers
Planners ▪ Surveyors ▪ Landscape Architects

331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Tel: 732.383.1950 ▪ Fax: 732.383.1984

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**

**DEED NOTICE AREA 3**
**BLOCK 24601 LOT 11**
**PROJECT NO. 10000292R**
**APRIL 12, 2016**
**REVISED SEPTEMBER 11, 2017**

All that certain lot, tract or parcel of land situate lying and being in the City of Jersey, in the County of Hudson and State of New Jersey, and being a portion of Lot 11 Block 24601, designated as Deed Notice Area 3 as shown on an exhibit entitled, "Deed Notice Area 3, SA6 South, Block 24601 Lot 11, City of Jersey City, Hudson County, New Jersey," prepared by Maser Consulting P.A., dated April 6, 2016, revised September 11, 2017 and being more particularly bounded and described as follows, to wit:

**COMMENCING** at the intersection of the division line between Lots 5 and 11, Block 24601, with the northwesterly terminus of Kellogg Street (80 foot wide right of way); thence-

A. **S40°39'55" W, 3.74 feet**, along said northwesterly terminus to the **True** point of **BEGINNING**, and running; thence-

1. **S40° 39' 55"W, 80.21 feet,** along the same; thence-

Running through Lot 11 the following three (3) courses:

2. **N51°13'02" W, 1,061.96 feet,** to a point of curvature; thence-

3. **NORTHWESTWARDLY**, on an arc to the right having a radius of **26.00 feet,** and arc length of **43.82 feet** (central angle of **96°33'55"**), said arc being connected by a chord bearing **N 02° 56'04" W,** a chord distance of **38.81 feet**, to a point of tangency; thence-

4. **N45°20'54" E, 82.45 feet,** to the division line between Lots 11 and 1; thence-

5. **S51° 06' 45"E, 184.04 feet,** along said division line to a point of non-tangent curvature; thence -

Running through said Lot 11 the following twenty-three (23) courses:

6. **SOUTHEASTWARDLY**, on an arc to the left having a radius of **273.50 feet,** and arc length of **42.65 feet** (central angle of **08°56'07"**), said arc being connected by a chord bearing **S 03° 18'43" E,** a chord distance of **42.61 feet,** to a point of non-tangency; thence –

7. **S50° 24' 32"W, 42.19 feet,** thence -

8. **S18° 06' 16"W, 7.09 feet,** to a point of non-tangent curvature; thence -

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**

**DEED NOTICE AREA 3**
**BLOCK 24601 LOT 11**
**PROJECT NO. 10000292R**
**APRIL 12, 2016**
**REVISED SEPTEMBER 11, 2017**

9. **SOUTHEASTWARDLY**, on an arc to the left having a radius of **250.97 feet,** and arc length of **16.39 feet** (central angle of **03°44'31"**), said arc being connected by a chord bearing **S 18° 13'05" E,** a chord distance of **16.39 feet,** to a point of non-tangency; thence –

10. **S50° 24' 32"E, 244.78 feet,** thence –

11. **N39° 35' 28"E, 19.37 feet**; thence-

12. **S52° 20' 21"E, 20.65 feet,** thence -

13. **S36° 31' 45"W, 10.78 feet,** to a point of non-tangent curvature; thence -

14. **SOUTHWESTWARDLY**, on an arc to the left having a radius of **19.33 feet,** and arc length of **9.87 feet** (central angle of **29°14'30"**), said arc being connected by a chord bearing **S 21° 54'30" W,** a chord distance of **9.76 feet**, to a point of non-tangency; thence-

15. **S50° 24' 32"E, 130.38 feet,** thence –

16. **S53° 28' 08"E, 14.33 feet,** thence –

17. **S87° 26' 31"E, 12.53 feet**; thence –

18. **S53° 28' 08"E, 89.62 feet**; thence-

19. **S18° 28' 37"E, 12.21 feet**; thence –

20. **S53° 27' 19"E, 50.67 feet**, to a point of non-tangent curvature; thence –

21. **NORTHEASTWARDLY**, on an arc to the left having a radius of **19.33 feet,** and arc length of **10.91 feet** (central angle of **32°20'50"**), said arc being connected by a chord bearing **N 52° 42'11" E,** a chord distance of **10.77 feet**, to a point of non-tangency; thence -

22. **N36° 31' 45"E, 9.88 feet**; thence –

23. **S51° 06' 45"E, 25.36 feet**; thence –

24. **S36° 31' 45"W, 8.86 feet**, to a point of non-tangent curvature; thence –

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**

**DEED NOTICE AREA 3**
**BLOCK 24601 LOT 11**
**PROJECT NO. 10000292R**
**APRIL 12, 2016**
**REVISED SEPTEMBER 11, 2017**

25. **SOUTHWESTWARDLY**, on an arc to the left having a radius of **19.33 feet,** and arc length of **10.90 feet** (central angle of **32°18'35"**), said arc being connected by a chord bearing **S 20° 22'28" W,** a chord distance of **10.76 feet,** to a point of non-tangency; thence –

26. **S53° 27' 19"E, 34.71 feet**; thence –

27. **S88° 21' 24"E, 12.23 feet**; thence –

28. **S53° 26' 10"E, 160.18 feet**, to the point and place of **BEGINNING**.

**CONTAINING:** 81,406 S.F. of land more or less or 1.869 acres of land more or less.


09/11/2017

GLEN J. LLOYD, P.L.S. DATE SIGNED
NEW JERSEY PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS037598

R:\General\Projects\2010\10000292Q\Survey\Description\Metes & Bounds-Deed Notice 3_REV 9-11-17.docx

| LINE DATA | | |
|---|---|---|
| SEGMENT | DIRECTION | LENGTH |
| L1 | N 45°20'54" E | 82.45' |
| L2 | S 51°06'45" E | 184.04' |
| L3 | S 50°24'32" E | 42.19' |
| L4 | S 18°06'16" W | 7.09' |
| L5 | S 50°24'32" E | 244.78' |
| L6 | N 39°35'28" E | 19.37' |
| L7 | S 52°20'21" E | 20.65' |
| L8 | S 36°31'45" W | 10.78' |
| L9 | S 50°24'32" E | 130.38' |
| L10 | S 53°28'08" E | 14.33' |
| L11 | S 87°26'31" E | 12.53' |
| L12 | S 53°28'08" E | 89.62' |
| L13 | S 18°28'37" E | 12.21' |
| L14 | S 53°27'19" E | 50.67' |
| L15 | N 36°31'45" E | 9.88' |
| L16 | S 51°06'45" E | 25.36' |
| L17 | S 36°31'45" W | 8.86' |
| L18 | S 53°27'19" E | 34.71' |
| L19 | S 88°21'24" E | 12.23' |
| L20 | S 53°26'10" E | 160.18' |

| CURVE DATA | | | | |
|---|---|---|---|---|
| SEGMENT | RADIUS | LENGTH | DELTA | CHORD |
| C1 | 26.00' | 43.82' | 96° 33' 55" | N 02°56'04" W 38.81' |
| C2 | 273.50' | 42.65' | 8° 56' 07" | S 03°18'43" E 42.61' |
| C3 | 250.97' | 16.39' | 3° 44' 31" | S 18°13'05" E 16.39' |
| C4 | 19.33' | 9.87' | 29° 14' 30" | S 21°54'30" W 9.76' |
| C5 | 19.33' | 10.91' | 32° 20' 50" | N 52°42'11" E 10.77' |
| C6 | 19.33' | 10.90' | 32° 18' 35" | S 20°22'28" W 10.76' |





MASER CONSULTING P.A

Customer Loyalty *through* Client Satisfaction
www.maserconsulting.com
Engineers ■ Planners ■ Surveyors
Landscape Architects ■ Environmental Scientists

State of N.J. Cert. of Authorization: 24GA27986500

Office Locations:
■ Red Bank, NJ ■ Albany, NY
■ Clinton, NJ ■ Chestnut Ridge, NY
■ Hamilton, NJ ■ Newburgh, NY
■ Marmora, NJ ■ Hawthorne, NY
■ Mt. Arlington, NJ ■ Lehigh Valley, PA
■ Mt. Laurel, NJ ■ Exton, PA
■ Sterling, VA ■ Philadelphia, PA
■ Norfolk, VA ■ Columbia, MD
■ Albuquerque, NM ■ Tampa, FL



Copyright © 2017. Maser Consulting P.A. All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Maser Consulting, P.A.


| REV | DATE | DRAWN BY | DESCRIPTION |
|---|---|---|---|
| 1 | 9/11/17 | HA | REVISE DEED NOTICE LINE |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |
| . | . | . | . |

DEED NOTICE AREA 3
SA6 SOUTH

BLOCK 24601
LOT 11

CITY OF JERSEY CITY
HUDSON COUNTY
NEW JERSEY

811 Know what's below. Call before you dig.

PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM


RED BANK OFFICE
Corporate Headquarters
331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Phone: 732.383.1950
Fax: 732.383.1984


| SCALE: | DATE: | DRAWN BY: | CHECKED BY: |
|---|---|---|---|
| AS SHOWN | 4/6/2016 | HA | GJL |


PROJECT NUMBER: 10000292C
DRAWING NAME: V-EXBT-DN-3_REV

SHEET TITLE:
DEED NOTICE EXHIBIT

SHEET NUMBER:
1 of 1

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150450_5710\5710A\deed notice\deed notice 3\3480150450-5100-A200-3000.dwg Fri, 10 Mar 2017 - 1:35pm sethr.rudkin




**DRAFT**

0 150 300 600


SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A200-3000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT A-2**<br>TAX MAP<br>BLOCK 24601, LOT 11<br>DEED NOTICE #3 SA-6 SOUTH SITE 163<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16<br>CHECKED/DATE: NW 01/31/17 | | |

**Exhibit A-3**
**Property Map**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND PROPRIETARY TO AMEC FOSTER WHEELER AND (2) THIS DOCUMENT MAY NOT BE DISCLOSED, USED OR RELIED UPON BY ANY PERSON OTHER THAN THE CLIENT, AND MAY NOT BE ADOPTED OR USED BY THE CLIENT FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT HAS BEEN DELIVERED, AND OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY

P:\CA09\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710dA\deed notice\deed notice 3\3480150450-5100-A300-3000.dwg Fri, 10 Mar 2017 - 1:35pm scott.rudkin




DRAFT

0 75 150 300

SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A300-3000 | amec foster wheeler | **EXHIBIT A-3**<br>PROPERTY AREA MAP<br>BLOCK 24601 LOT 11<br>DEED NOTICE #3 SA-6 SOUTH SITE 163<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16 · CHECKED/DATE: NW 01/31/17 | ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | |

**EXHIBIT B**
**Deed Notice #3 Site 163**
**B-1 Restricted Area Maps**
**B-2 Restricted Area Data Table**
**Portion of Block 24601, Lot 11**
**City of Jersey City, New Jersey**

Exhibit B-1 Restricted Area Maps include Exhibit B-1A (Restricted Area and Soil Sample Locations), Exhibit B-1B (Cap System Detail), and Exhibit B-1C (As-Built Restoration Plan).

Exhibit B-2 is a Restricted Area Data Table indicating soil sample locations with concentrations of contaminants remaining above the level established in the New Jersey Department of Environmental Protection (NJDEP) Chromium Policy and/or other applicable NJDEP Soil Quality Standards as described below.

**Restricted Area Map Notes:**

Exhibit B-1 indicates engineering controls. The engineering controls include 4 to 6-inches crushed stone cover overlying 4 to 6-feet of clean soils above the impacted soil. (As part of the Bayfront Redevelopment Plan, the engineering control will also include a paved road, walkway or other hardscape. At that time, this Deed Notice will be revised to reflect the revision to the engineering controls.).

Exhibits B-1A indicates the restricted area for soil containing contaminants of concern, including hexavalent chromium above 20 milligrams per kilogram (mg/kg) pursuant to the Chromium Policy, and soils that are consistent with NJDEP's definition of "historic fill material" found at N.J.A.C. 7:26E-1.8, as shown on Exhibit B-3.


Analytical results and soil borings indicate that historic fill is present onsite and extends over the entire Restricted Area. Historic fill onsite typically consists of the following: metals, PAHs, and miscellaneous debris (including but not limited to coal fragments, brick, timber, and other construction materials).

A table summarizing maximum concentrations of typical contaminants found in the historic fill material in the Restricted Area is included as Exhibit B-2.

**Exhibit B-1**
**Restricted Area Maps**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\JOB\HONEWELL\JERSEY CITY\SA 6 SOUTH\3480150450\5710\5710014.dsed notice\dsed notice 3\3480150450-5100-B100-3000.dwg Fri, 10 Mar 2017 - 1:36pm scott.rudkin




LEGEND

- SOIL SAMPLE LOCATION WHERE HEXAVALANT CHROMIUM > 20 mg/kg
- MONITORING WELL LOCATION
- 21901 — BLOCK NUMBER
- LOT 8 — LOT NUMBER
- BLOCK LINE
- LOT LINE
- VERTICAL HYDRAULIC BARRIER WALL
- RESTRICTED AREA FOR HISTORIC FILL AND HEXAVALENT CHROMIUM (SEE EXHIBIT B-2) (ASPHALT OR SOIL COVER) CEA AREA

**DRAFT**

0 75 150 300

SCALE IN FEET

| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-B100-3000 | |
| PREPARED/DATE: STR 01/28/16 | CHECKED/DATE: NW 01/31/17 |


amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT B-1A**
RESTRICTED AREA MAP
BLOCK 24601 LOT 11
DEED NOTICE # 3 SA-6 SOUTH SITE 163
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.


P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\deed notice\deed notice 3\3480150450-5100-B200-3000.dwg Fri, 10 Mar 2017 - 1:36pm scott.rubin




## CAP SYSTEM DETAIL
NTS


**DRAFT**

| | | |
|---|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150488<br>*DRAWING:* 3480150450-5100-B200-3000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT B-1B**<br>CAP SYSTEM DETAIL<br>BLOCK 24601 LOT 11<br>DEED NOTICE # 3 SA-6 SOUTH SITE 163<br>JERSEY CITY, NEW JERSEY |
| *PREPARED/DATE:* STR 01/25/17 \| *CHECKED/DATE:* NW 01/31/17 | | |




NOTE:

1. REFER TO FIGURE 2 FOR CONSTRUCTION CONTROL GRID AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE ON THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL AS SHOWN ON THE TYPICAL VEGETATED SLOPE DETAIL. THE VEGETATED SLOPE ALONG SA–7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. EXISTING PAVEMENT WAS FIELD INSPECTED BY LSRP AND SUBJECT TO MINOR CRACK FILLING TO SATISFY HISTORIC FILL CAP REQUIREMENTS.
4. STEEL SHEETPILE WALL WAS INSTALLED AS EXCAVATION SUPPORT ALONG THIS AREA AND THEN CUT BELOW CURRENT GRADE AND LEFT IN PLACE. THE TOP OF SHEETPILE IS GENERALLY 0.5 TO 2.0 FT BELOW CURRENT GRADES.




NOTE: NO HISTORIC FILL SHALL BE PLACED ON SA–7

TYPICAL VEGETATED SLOPE
NTS

EXHIBIT B-1C

STONE COVER | STONE COVER IN PLANTER AREAS | STEEL SHEETPILE WALL
VEGETATED COVER | RIPARIAN ZONE | STORM DRAIN PIPE
PAVEMENT COVER | DGA COVER | STORM DRAIN CATCH BASIN
CONCRETE COVER | STONE TOE DRAIN

0 80 160 FEET
SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: AS BUILT RESTORATION PLAN SA–6 SOUTH – SHEET 001 12/12/16

PROJECT NAME & LOCATION: HONEYWELL SA–6 REMEDIATION JERSEY CITY, NJ

**Exhibit B-2: Table B-2**
**Soil Sample Data Table**

**EXHIBIT B-2**

**Restricted Area Data Table**

Deed Notice #3 Site 163

Portions of Block 24601, Lot 11

Jersey City, New Jersey

| Location ID | Elevation (feet msl) NAVD88 | Start Depth (feet bgs) | End Depth (feet bgs) | Hexavalent Chromium Concentration (mg/kg) | CASR# | NJDEP Chromium SCC (mg/kg) |
|---|---|---|---|---|---|---|
| 163-SB-002 | -10.00 | 17 | 17.5 | 33.6 | 18540-29-9 | 20 |
| 163-SB-006 | -1.70 | 8.5 | 9 | 24.7J | 18540-29-9 | 20 |
| 163-SB-008 | 1.70 | 6.5 | 7 | 22.5 | 18540-29-9 | 20 |
| 163-SB-009 | 0.70 | 8 | 8.5 | 85.7J | 18540-29-9 | 20 |
| 163-SB-017 | 6.10 | 1 | 1.5 | 1.5 | 18540-29-9 | 20 |
| 163-SB-017 | 0.60 | 6.5 | 7 | 24.6 | 18540-29-9 | 20 |
| 163-SB-018 | -5.50 | 14 | 14.5 | 22.8 | 18540-29-9 | 20 |
| 163-SB-023 | -4.70 | 14 | 14.5 | 40.4 | 18540-29-9 | 20 |
| 163-SB-025 | -2.90 | 12 | 12.5 | 32.9 | 18540-29-9 | 20 |
| 163-SB-033 | -2.90 | 12 | 12.5 | 23.6 | 18540-29-9 | 20 |
| 163-SB-041 | 1.10 | 6 | 6.5 | 31.8 | 18540-29-9 | 20 |
| 163-SB-049 | 0.2 | 8.5 | 9 | 24.9J | 18540-29-9 | 20 |
| 163-SB-065 | 0.7 | 8 | 8.5 | 27.1 | 18540-29-9 | 20 |
| 163-SB-200 | -2.90 | 12 | 13 | 9.9 | 18540-29-9 | 20 |
| 163-SB-200 | -3.90 | 13 | 14 | 10.6 | 18540-29-9 | 20 |
| 163-SB-201 | -4.70 | 14 | 15 | 21.1 | 18540-29-9 | 20 |
| 163-SB-201 | -5.70 | 15 | 16 | 16.4 | 18540-29-9 | 20 |
| 163-SB-203 | -1.7 | 10 | 11 | 6.2 | 18540-29-9 | 20 |
| 163-SB-203 | -2.7 | 11 | 12 | 9.2 | 18540-29-9 | 20 |
| 163-SB-203 | -3.7 | 12 | 13 | 14.8 | 18540-29-9 | 20 |
| 163-SB-203 | -4.7 | 13 | 14 | 11.3 | 18540-29-9 | 20 |
| 163-SB-214 | -4.7 | 12 | 13 | 3.7 | 18540-29-9 | 20 |
| 163-SB-214 | -5.7 | 13 | 14 | 3.8 | 18540-29-9 | 20 |
| 163-SB-215 | -6 | 13 | 14 | 1.8 | 18540-29-9 | 20 |
| 163-SB-215 | -7 | 14 | 15 | 2.4 | 18540-29-9 | 20 |
| 163-SB-224 | 1.2 | 6 | 7 | 17 | 18540-29-9 | 20 |
| 163-SB-224 | 0.2 | 7 | 8 | 17.7 | 18540-29-9 | 20 |
| 163-SB-225 | 1 | 6 | 7 | <0.51 | 18540-29-9 | 20 |
| 163-SB-225 | 0 | 7 | 8 | 0.53 | 18540-29-9 | 20 |
| 163-SB-226 | -9 | 16 | 17 | 1.4 | 18540-29-9 | 20 |
| 163-SB-226 | -10 | 17 | 18 | 5.7 | 18540-29-9 | 20 |
| 163-SB-227 | -0.2 | 7 | 8 | 16.9 | 18540-29-9 | 20 |
| 163-SB-227 | -1.2 | 8 | 9 | 8.3 | 18540-29-9 | 20 |
| 163-SB-228 | 1.2 | 6 | 7 | 8.4 | 18540-29-9 | 20 |
| 163-SB-228 | 0.2 | 7 | 8 | 8.4 | 18540-29-9 | 20 |
| 163-SB-229 | 0.7 | 8 | 9 | 57.2 | 18540-29-9 | 20 |
| 163-SB-229 | -0.3 | 9 | 10 | 79.3 | 18540-29-9 | 20 |
| 163-SB-230 | -1.8 | 10.5 | 11.5 | 27.7 | 18540-29-9 | 20 |
| 163-SB-230 | -2.8 | 11.5 | 12.5 | 40.7 | 18540-29-9 | 20 |
| 163-SB-236 | -3.7 | 11 | 12 | 50.6 | 18540-29-9 | 20 |
| 163-SB-236 | -4.7 | 12 | 13 | 11.5 | 18540-29-9 | 20 |
| 163-SB-237 | -2.7 | 11 | 12 | 34.3 | 18540-29-9 | 20 |
| 163-SB-237 | -3.7 | 12 | 13 | 38.7 | 18540-29-9 | 20 |
| 163-SB-237 | -4.7 | 13 | 14 | 31.3 | 18540-29-9 | 20 |
| 163-SB-237 | -5.7 | 14 | 15 | 80.6 | 18540-29-9 | 20 |
| 163-SB-238 | -4.4 | 13 | 14 | 18.4 | 18540-29-9 | 20 |
| 163-SB-238 | -5.4 | 14 | 15 | 31.6 | 18540-29-9 | 20 |
| 163-SB-240 | -4.8 | 14 | 15 | 27.2 | 18540-29-9 | 20 |
| 163-SB-240 | -5.8 | 15 | 16 | 13.1 | 18540-29-9 | 20 |
| 163-SB-241 | -2.9 | 12 | 13 | 22.2 | 18540-29-9 | 20 |
| 163-SB-241 | -3.9 | 13 | 14 | 30.6 | 18540-29-9 | 20 |
| 163-SB-242 | -5.5 | 14 | 15 | 27.3 | 18540-29-9 | 20 |
| 163-SB-242 | -6.5 | 15 | 16 | 92.5 | 18540-29-9 | 20 |

**EXHIBIT B-2**

**Restricted Area Data Table**

Deed Notice #3 Site 163

Portions of Block 24601, Lot 11

Jersey City, New Jersey

| Location ID | Elevation (feet msl) NAVD88 | Start Depth (feet bgs) | End Depth (feet bgs) | Hexavalent Chromium Concentration (mg/kg) | CASR# | NJDEP Chromium SCC (mg/kg) |
|---|---|---|---|---|---|---|
| 163-SB-246 | 0.7 | 8 | 9 | 44.5 | 18540-29-9 | 20 |
| 163-SB-246 | -0.3 | 9 | 10 | 39.7 | 18540-29-9 | 20 |
| 163-SB-247 | 0.7 | 8 | 9 | 7.7 | 18540-29-9 | 20 |
| 163-SB-247 | -0.3 | 9 | 10 | 4.2 | 18540-29-9 | 20 |
| 163-SB-250 | 1 | 6 | 7 | 0.5 | 18540-29-9 | 20 |
| 163-SB-250 | 0 | 7 | 8 | 0.64 | 18540-29-9 | 20 |

**Notes:**

Results reported in mg/kg.

Results from In-Situ Post Treatment included even if <20 mg/kg.

**Data Qualifiers:**

J - Data indicates the presence of a compound that meets the identification criteria. The concentration given is an approximate value.

**Abbreviations:**

Feet bgs - Feet below ground surface

mg/kg - milligrams per kilogram

feet msl - feet mean sea level NAVD88 - North American Vertical Datum of 1988

NJDEP Chromium SCC - New Jersey Department of Environmental Protection Chromium Soil Cleanup Criteria, revised April 2010

**EXHIBIT B-2**
**HISTORIC FILL COMPOUNDS ABOVE STANDARD**
Deed Notice #3 Site 163
Portions of Block 24601, Lot 11
Jersey City, New Jersey

| Compound>RDC | RDC | # of Samples >RDC | Maximum Conc. |
|---|---|---|---|
| **BENZO(A)ANTHRACENE** | **0.6** | 3 | 1.35 |
| **BENZO(A)PYRENE** | **0.2** | 8 | 1.01 |
| **BENZO(B)FLUORANTHENE** | **0.6** | 3 | 1.4 |
| **NAPHTHALENE** | **6** | 1 | 11.9 |

Notes:
RDC: NJDEP Residential Direct Contact Soil Remediation Standards [N.J.A.C. 7:26D; last amended 5/7/2012].
CONC: Concentration reported in milligrams per kilogram (mg/kg)
Historic fill is present throughout the Site consisting of PAH and metals.
R or N: Rejected or negated by laboratory or data validator

**EXHIBIT C**
**Deed Notice #3 Site 163**

**C-1 Institutional Controls**
**C-2 Engineering Controls**
**Portion of Block 24601, Lot 11**
**City of Jersey City, New Jersey**

## C-1 Institutional Controls

C-1 Deed Notice, Consent Decree, Zoning, Conservation Restriction as Institutional Controls: Exhibit C-1 (A through D) for that portion of Block 24601, Lot 11, City of Jersey City, New Jersey known as Site 163.

Exhibits C-1A through D. Exhibit C-1A: Deed Notice as Institutional Control; Exhibit C-1B: Consent Decree as Institutional Control (attached); Exhibit C-1C: Zoning as Institutional Control; Exhibit C-1D: Conservation Restriction as Institutional Control (recorded at Hudson County Register of Deeds as indicated in Paragraph 3): Exhibits C-1A through C-1D include a narrative description of the restrictions and obligations of this Deed Notice and the other Institutional Controls that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
**The Property is a portion of Site 163 at SA-6 South where remaining chromium-impacted soils were identified in the area south of the northern curbline of the future River Front Park/Riverside Drive/Kellogg Street. This deed notice area includes chromium and historic fill. Honeywell will restrict, or will cause Bayfront Redevelopment LLC to restrict, the future use of this area by implementing a conservation restriction, which will be recorded at the Office of the Hudson County Register. In addition, Honeywell will transfer, or will cause Bayfront Redevelopment LLC to transfer title to the Property to Jersey City (as called for in Paragraph 61(c)(ii)(3) of the Consent Decree). The provisions of the LTMP, developed pursuant to the Consent Decree, will apply to the Property.**

(1) Description and estimated size of the Restricted Areas as described above;

***The Property constitutes a portion of Block 24601, Lot 11. The estimated size of the Area containing chromium-impacted soils (hexavalent chromium above 20 mg/kg) as identified on Exhibit B-1 is estimated at approximately 82,868 square feet or approximately 1.902 acres.***

(2) Description of the restrictions on the Property by operation of the Institutional Control;

***The Property shall only be used for activities consistent with this Deed Notice, the Consent Decree, the applicable zoning standards, and the Conservation Restriction. Intrusive activities (i.e., excavation or digging) that breach the***

***engineering controls (as described in Exhibit C-2) will not be permitted on the Property except in compliance with the terms of the Consent Decree and the applicable portions of the LTMP developed thereunder, and this Deed Notice. See subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies for additional information. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950.***

(3) The objective of the restrictions;

***The restrictions will prohibit contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg and soils that are historic fill.***

(B) Description of the monitoring necessary to determine whether:

(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;

***Visual inspections of the Property and other monitoring as set forth in the Consent Decree and the applicable portions of the LTMP established thereunder.***

(2) There have been any land use changes subsequent to the filing of this Deed Notice or the most recent biennial certification, whichever is more recent;

***Same as (B)(1).***

(3) The current land use on the Property is consistent with the restrictions in this Deed Notice;

***Same as (B)(1).***

(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the site; and

***Review of newly promulgated or modified requirements of applicable regulations or laws that potentially may apply to the site.***

(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***Same as (B)(4).***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) Land use at the Property is consistent with the restrictions in the Consent Decree, this Deed Notice, the applicable zoning standards and the Conservation Restriction; and

(3) The remedial action that includes this Deed Notice continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including evaluation of any available documents as a result of changes in land use or incidents.***
- ***A report that determines whether or not the land use at the Property has remained consistent with the restrictions in the Consent Decree, this Deed Notice, the applicable zoning standards and the Conservation Restriction.***
- ***A report that determines whether or not the Deed Notice continues to be protective of the public health and safety and the environment.***

**C-2 Engineering Controls**
**Deed Notice #3 Site 163**
**Portion of Block 24601, Lot 11**
**City of Jersey City, New Jersey**

Exhibits C-2A through C: Narrative description of the Engineering Controls including Clean Fill as follows:

(A) General Description of the engineering controls:

(1) Description of the engineering controls;

***The Engineering Controls consist of the following: 4 to 6-inches crushed stone cover overlying 4 to 6-feet of clean soils above the hexavalent chromium impacted soil. (As part of the Bayfront Redevelopment Plan, the engineering control will also include a paved road, walkway or other hardscape. At that time, this Deed Notice will be revised to reflect the revision to the engineering controls.)***

(2) The objective of the engineering controls; and

***The objective of the controls is to prevent contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg and soils that are historic fill.***

(3) How the engineering controls are intended to function.

***The soil engineering controls are intended to function as a barrier to underlying and adjacent soils containing hexavalent chromium above 20 mg/kg and soils that are historic fill within the Property. Monitoring requirements for the engineering controls are set forth in the applicable portions of the LTMP.***

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

***Honeywell will perform monitoring by visual inspection of the Property pursuant to the Consent Decree. Other monitoring activities shall be performed as set forth in the applicable portions of the LTMP developed pursuant to the Consent Decree.***

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

***Same as (B)(1) above.***

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering controls;

***Same as (B)(1) above. Also, see the Consent Decree and subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies for additional information.***

(4) The engineering controls are being inspected and maintained and their integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

***Same as (B)(1) above.***

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering controls. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering controls; and

***Records of the inspections are to be maintained as listed in (5). Should the activities carried out in conformance with the applicable portions of the LTMP developed pursuant to the Consent Decree indicate that other activities are necessary, those activities will be listed and executed.***

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***A review of any new standards, regulations, or laws will be conducted. Should the review indicate that other activities are necessary, those activities will be listed and executed.***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering controls continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including an evaluation to determine whether or not the engineering controls are continuing to meet the original objective and intended function.***
- ***A report to determine whether or not the engineering controls continue to operate as designed.***
  ***A report to determine whether or not the engineering controls continue to be protective of the public health and safety and of the environment.***

**Appendix I**
**Consent Decree**

# APPENDIX I

UNITED STATES DISTRICT COURT
DISTRICT OF NEW JERSEY

| | |
|---|---|
| JERSEY CITY MUNICIPAL UTILITIES AUTHORITY,<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Docket No. 05-5955(DMC)<br>Consolidated under Docket No. 95-2097 (DMC) |
| JERSEY CITY INCINERATOR AUTHORITY<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Civil Action No. 05-5993<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 (DMC) |
| HACKENSACK RIVERKEEPER, INC., *et al.*<br><br>Plaintiffs,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC., *et al.*<br><br>Defendants. | Civil Action No. 06-22<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 |

**FIRST AMENDED CONSENT DECREE REGARDING REMEDIATION AND REDEVELOPMENT OF STUDY AREA 6 SOUTH**

# TABLE OF CONTENTS

**RECITALS** ..... 1

**ARTICLE I: DEFINITIONS** ..... 4

**ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED** ..... 11

**ARTICLE III: CHROMIUM REMEDIATION** ..... 12

A. GENERAL TERMS AND REQUIREMENTS ..... 12
50. Responsibility for Implementation of Chromium Remediation. ..... 12
51. Designation of Chromium Areas of Concern. ..... 12
52. Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan. ..... 12
53. General Scope of the Chromium Remedy. ..... 13
54. Development of a Schedule for the Chromium Remedy. ..... 13
B. INITIAL CHROMIUM REMEDY STEPS: DELINEATION, TREATMENT STUDY, AND REMEDIAL ACTION WORK PLAN ..... 15
55. Delineation of Development AOC. ..... 15
56. Conduct of a Treatment Study in the Development AOC . ..... 15
57. Continued Monitoring of the Treatment Study. ..... 16
58. Submission of a Remedial Action Work Plan. ..... 16
C. DEVELOPMENT AOC SOIL REMEDY ..... 16
59. Remedial Components ..... 16
60. Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium ..... 17
61. Treatment as a Remedial Component for 20 to 240 Soils ..... 18
62. Submissions Related to Site 163 ..... 20
63. Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium. ..... 20
64. Post-Treatment Monitoring for 20 to 1000 Soils ..... 21
D. OPEN SPACE AOC COMPONENTS OF THE CHROMIUM REMEDY ..... 21
65. Open Space AOC Soil Remedy ..... 21
E. DEMOLITION, GRADING, AND BACKFILL REQUIREMENTS ..... 23
66. Demolition and Grading Activities. ..... 23
67. Backfill Requirements. ..... 23
68. Vegetation of Clean Fill. ..... 23
F. GROUNDWATER COMPONENTS OF THE CHROMIUM REMEDY ..... 23
69. Shallow Groundwater Remedy for the Open Space AOC ..... 23
70. The Shallow Groundwater Remedy for the Development AOC. ..... 24
71. Off-Site Shallow Groundwater Remedy. ..... 25
72. L-Well Groundwater Remedy. ..... 26
G. PERMITS AND AUTHORIZATIONS ..... 26
73. Permits and Authorizations. ..... 26
H. LONG-TERM MONITORING, MAINTENANCE, AND PROTECTION OF ENGINEERING AND INSTITUTIONAL CONTROLS ..... 27

74. Protection of the Open Space AOC ..... 27
75. Honeywell's Ongoing Responsibility. ..... 39
76. Long-Term Monitoring Plan. ..... 39
77. Long-Term Monitoring Plan Objectives ..... 39
78. Monitoring and Remediation Under the Long-Term Monitoring Plan ..... 40
79. Monitoring and Reporting to Riverkeeper. ..... 44
80. Notice to Stakeholders ..... 44
81. Annual Letter to Riverkeeper on Notice to Stakeholders ..... 45
82. Future Notice to Stakeholders ..... 45
83. Stakeholder Enforcement. ..... 46
I. OVERSIGHT AND ENFORCEMENT BY THE SPECIAL MASTER AND NJDEP ..... 46
84. Federal Court Jurisdiction ..... 46
85. Appointment and Jurisdiction of the Special Master. ..... 46
86. Oversight of the Chromium Remedy. ..... 46
87. Retention of Professionals. ..... 53
88. Insurance for the Special Master. ..... 53
89. Reimbursement of Special Master Fees and Expenses. ..... 54
90. Expiration of Special Master's Appointment. ..... 54
J. INITIAL FINANCIAL ASSURANCES ..... 55
91. Chromium Remedy Letter of Credit ..... 55
92. Procedures for Review of the Proposed Chromium Remedy Letter of Credit ..... 56
93. Automatic Renewal. ..... 56
94. Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit ..... 57
95. Bankruptcy Protection. ..... 58
96. Exclusive Court Jurisdiction. ..... 58
97. Application of New York Law. ..... 59
98. Procedures upon Honeywell's Material Default of Its Obligations ..... 59
99. Placement of Proceeds in Court Registry Investment System Account. ..... 60
100. Termination of Chromium Remedy Letter of Credit ..... 61
K. LONG-TERM FINANCIAL ASSURANCES ..... 61
101. Long-Term Financial Assurances. ..... 61
102. Costs Subject to Long-Term Financial Assurances. ..... 61
103. Long-Term Financial Assurance Mechanisms ..... 62
104. Procedures for Review of the Proposed Long-Term Financial Assurances ..... 66
105. Temporary Maintenance of Chromium Remedy Letter of Credit. ..... 66
106. Adjustment of Amount Held in Long-Term Financial Assurances. ..... 67
107. Exclusive Court Jurisdiction. ..... 68
108. Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired: ..... 68
109. Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default ..... 69
110. Use of the Trust Fund in the Event of Honeywell's Default. ..... 70
111. Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109. ..... 70
112. Termination of the Long-Term Financial Assurances. ..... 70

**ARTICLE IV: TERMINATION** ..... 71

113. Termination of this Consent Decree ..... 71
114. Procedures for Withdrawal and Termination. ..... 72
115. Good-Faith Obligation to Avoid Termination ..... 72
116. Effect of Termination. ..... 72

**ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC** ..... 72

117. Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC. ..... 72

**ARTICLE VI: NOTICE** ..... 73

118. Notice ..... 73
119. Payment of Past Fees and Expenses ..... 74
120. Future Fees and Expenses. ..... 75

**ARTICLE VIII: MISCELLANEOUS PROVISIONS** ..... 76

121. Force Majeure. ..... 76
122. Bayfront Redevelopment LLC as a Party. ..... 76
123. Successors and Assigns. ..... 77
124. Successors to Hackensack Riverkeeper, Inc.. ..... 77
125. Reservation of Rights and Claims. ..... 77
126. Governing Law and Continuing Jurisdiction. ..... 77
127. Construction. ..... 78
128. Authority to Enter into Agreement. ..... 78
129. Measures to Effectuate This Consent Decree ..... 78
130. Modifications. ..... 78
131. Severability. ..... 78
132. Signatures. ..... 79

## RECITALS

**Whereas,** on June 30, 2003, the district court for the District of New Jersey (hereafter "the Court") issued a Final Judgment in *Interfaith Community Organization v. Honeywell International Inc.*, Civ. No. 95-2097 (DMC) (*"ICO v. Honeywell"*), ordering the remediation of an area designated by the New Jersey Department of Environmental Protection ("NJDEP") as Study Area 7 by excavation of all chromium contamination on the property, under the oversight of a court-appointed Special Master;

**Whereas**, on or about December 23, 2005, the Jersey City Municipal Utilities Authority ("JCMUA") filed litigation styled *Jersey City Municipal Utilities Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5955 (DMC), bringing claims against Honeywell International Inc. ("Honeywell") under, *inter alia*, Section 6972 of the Resource Conservation and Recovery Act ("RCRA"), and seeking remediation of chromium contamination on property then-owned by JCMUA and other relief;

**Whereas**, on or about December 28, 2005, the Jersey City Incinerator Authority ("JCIA") filed litigation styled *Jersey City Incinerator Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5993 (DMC), bringing claims against Honeywell under, *inter alia*, Section 6972 of RCRA, and seeking remediation of chromium contamination on property then-owned by JCIA and other relief;

**Whereas**, on or about January 4, 2006, the Hackensack Riverkeeper, Inc., Captain William Sheehan, Reverend Winston Clarke, and Lawrence Baker ("Riverkeeper") filed litigation styled *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.,* D.N.J., Civ. No. 06-022 (DMC), bringing a claim against Honeywell under RCRA and seeking remediation of chromium contamination to soils, groundwater, surface waters, and sediments associated with

various properties collectively designated by NJDEP as Study Areas 5, 6 North, which includes the properties formerly owned by JCMUA and JCIA, and 6 South;

**Whereas,** Study Areas 6 North and South are directly adjacent to Study Area 7 on the north and south sides, respectively;

**Whereas,** Study Area 5 is comprised of properties to the east of Study Areas 6 North, 6 South, and 7 across Route 440;

**Whereas,** Riverkeeper also named as defendants in *Riverkeeper v. Honeywell* owners of the properties comprising Study Areas 5, 6 South, and 6 North;

**Whereas,** *JCMUA v. Honeywell*, *JCIA v. Honeywell,* and *Riverkeeper v. Honeywell* were consolidated by the Court (hereinafter the "Consolidated Litigation");

**Whereas,** in the Consolidated Litigation, Riverkeeper has alleged that Honeywell bears responsibility for the presence and remediation of chromite ore processing residue ("COPR") and chromium in soils and groundwater on the Study Area 6 South property;

**Whereas,** on April 21, 2008, the Court entered the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North (hereafter "the Study Area 6 North Consent Decree") resolving issues between Honeywell, Riverkeeper, and the Jersey City Entities related to chromium contamination at Study Area 6 North;

**Whereas**, on April 21, 2008, the district court for the District of New Jersey entered the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. (hereafter "Jersey City/Honeywell Consent Order"), filed in the Consolidated Litigation simultaneously with the Study Area 6 North Decree, which resolved claims and cross-claims between Honeywell and the Jersey City Entities;

**Whereas**, on May 28, 2008, the Court entered the Consent Order on Sediment Remediation and Financial Assurances ("Sediment Consent Order"), resolving issues related to the remediation of chromium contaminated sediments in the Hackensack River in the vicinity of Study Areas 5, 6, and 7;

**Whereas**, on September 3, 2008, the Court entered the Deep Overburden and Bedrock Groundwater Remedies Consent Order (hereafter "the Deep Groundwater Consent Order") resolving all issues related to the remediation of deep overburden and bedrock groundwater in both *ICO v. Honeywell* and the Consolidated Litigation;

**Whereas,** on May 13, 2011, Plaintiffs sent Honeywell a RCRA citizen action suit notice letter with respect to Site 163, and the Parties agree that the incorporation of Site 163 into this Consent Decree resolves any claims asserted, or that could have been asserted, in the RCRA notice letter or in any RCRA citizen suit with respect to Site 163;

**Whereas**, the Parties to this Consent Decree each believe that it is in their mutual interest to move forward productively to resolve their differences so that they can implement environmental remediation at Study Area 6 South that ensures the continued protection of human health and the environment and so that Study Area 6 and Study Area 7 can be redeveloped in keeping with Jersey City's vision for a revitalized West Side;

**Whereas,** the Local Redevelopment and Housing Law, N.J.S.A. 40A:12A-1, *et seq.*, as amended and supplemented (the "Redevelopment Law") provides for municipalities to participate in the redevelopment and improvement of areas in need of redevelopment;

**Whereas**, Study Area 6 and Study Area 7 consist of parcels which by ordinance adopted by the City Council of Jersey City on February 27, 2008, have been determined to be "areas in

need of redevelopment" under the criteria of the Redevelopment Law because of conditions prevalent on those parcels;

**Whereas**, the settlement which is the subject matter of this Consent Decree contemplates the environmental remediation of Study Area 6 South and redevelopment of the parcels that comprise Study Areas 6 and 7 to create a major mixed use project in an important section of Jersey City; and

**Whereas**, each of the actions to implement this Consent Decree have been fully considered by the Honeywell, the Riverkeeper, and Jersey City as a means to accomplish the aforesaid purposes of this settlement:

NOW, THEREFORE, IT IS HEREBY ORDERED AND DECREED AS FOLLOWS:

## ARTICLE I: DEFINITIONS

For purposes of this Consent Decree, the following terms shall have the meanings set forth in this Article:

1. **"20 to 1000 Soils"** shall mean those soils containing less than 1000 mg/kg of hexavalent chromium, but greater than 20 mg/kg. **"20 to 240 Soils"** shall mean those soils containing less than 240 mg/kg of hexavalent chromium, but greater than 20 mg/kg.

2. **Bayfront Redevelopment LLC** shall have the meaning set forth in paragraph 4.1 of the Jersey City/Honeywell Consent Order.

3. **COPR** shall mean Chromite Ore Processing Residue.

4. **Chromium Remedy or Chromium Remediation** shall mean the remedy set forth in Article III.

5. **Consolidated Litigation** shall mean *Jersey City Municipal Utility Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5955 (DMC), *Jersey City Incinerator*

*Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5993 (DMC), and *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-022 (DMC).

6. The **Court** shall mean the United States District Court of the District of New Jersey, which has jurisdiction over the Consolidated Litigation.

7. **Deep Groundwater Consent Order** shall mean the Deep Overburden and Bedrock Groundwater Remedies Consent Order entered by the Court on September 3, 2008, in both *ICO v. Honeywell* and the Consolidated Litigation.

8. **Deep Groundwater Remedy** shall mean the deep overburden and bedrock groundwater pump and treat remedy as required by the Order Approving the Deep Overburden Groundwater Remediation, entered on October 6, 2006, the Stipulation on Consent Regarding the Schedule for Implementation of Deep Groundwater Remedial Actions, entered on August 15, 2008, in *ICO v. Honeywell,* and the remedies required under the Deep Groundwater Consent Order.

9. **Development Area of Concern** ("AOC") shall mean those portions of Study Area 6 South in which the hexavalent chromium concentration in the top 20 feet of soil below ground surfaces exceeds a concentration of 20 mg/kg, and for which future uses of the property may include commercial or residential development. The Open Space AOC shall not be part of the Development AOC and vice versa. The Development AOC consists of two parts: the Kellogg Street Development AOC and the Site 163 Development AOC. Collectively, the two parts shall be referred to as the "Development AOC." The approximate boundaries of the Development AOC as a whole and its two parts are shown on Exhibit A, but the boundaries may be further defined in the implementation of the Chromium Remedy. For the Kellogg Street Development AOC, remedial measures shall assume only a residential use. For the Site 163 Development AOC, remedial measures shall be implemented with the goal of unrestricted use, but limitations

on future uses (including prohibiting residential use) in some or all of the Site 163 Development AOC may be part of the remedy as set forth in paragraph 61.

10. **Hackensack River Watershed Land Trust** shall mean the dedicated fund of the Hackensack Riverkeeper, Inc., established under Section 501(c) of the Internal Revenue Code for the purpose of acquiring and preserving open space within the Hackensack River watershed and administered by the Board of Trustees of the Hackensack Riverkeeper, Inc.

11. **Honeywell** shall mean Honeywell International Inc. and its affiliates, including 425-445 Route 440 Property LLC, Kellogg Street 80 Property LLC, Kellogg Street 60 Property LLC, and Kellogg Street/440 Property LLC.

12. **Honeywell's Treatment Plant** shall mean the treatment plant currently located at 80 Kellogg Street that is used to treat, *inter alia*, chromium contaminated groundwater.

13. ***ICO v. Honeywell*** shall mean *Interfaith Community Organization v. Honeywell International Inc.*, D.N.J., Civ. No. 95-2097 (DMC).

14. **Including** shall mean including, but not limited to.

15. **JCIA** shall mean the Jersey City Incinerator Authority.

16. **JCMUA** shall mean the Jersey City Municipal Utilities Authority.

17. **Jersey City Entities** shall mean the City of Jersey City, including the Department of Public Works ("DPW") and other agencies and branches thereof, the JCIA, and the JCMUA.

18. **Jersey City/Honeywell Consent Order** shall mean the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. entered in the Consolidated Litigation on April 21, 2008.

19. **"L-Well Groundwater"** shall mean the groundwater found at the depth of the "L" wells on and near the former bowling alley property, NJDEP Site 124, located at 427 Route 440. The L-Well Groundwater is located within what has been referred to as the plume diversion area.

20. **NJDEP** shall mean the New Jersey Department of Environmental Protection.

21. **NJDEP Chromium Directive** shall mean the Chromium Directive issued by NJDEP on February 8, 2007, and attached as Exhibit B.

22. **Open Space AOC** shall mean the portion of Study Area 6 South that is identified as The Promenade park and Grand Boulevard extending from Route 440 to the Hackensack River on page 39 of the Redevelopment Plan and for which the future uses of the property shall be restricted pursuant to paragraph 74, following remediation pursuant to paragraph 65. The Development AOC shall not be part of the Open Space AOC and vice versa. The approximate boundaries of the Open Space AOC are shown on Exhibit A, and the boundaries may be further defined in the implementation of the Chromium Remedy.

23. **Party or Parties** shall mean any one or all of the signatories to this Consent Decree.

24. **RCRA** shall mean the Resource Conservation and Recovery Act, 42 U.S.C. § 6901, *et seq.*, as amended.

25. **Redevelopment Area** shall mean Study Area 6 North, Study Area 6 South, and Study Area 7, collectively.

26. **Redevelopment Law** shall mean the New Jersey Local Redevelopment and Housing Law, N.J.S.A. § 40A:12A1, *et seq.*, as amended and supplemented.

27. **Redevelopment Plan** shall mean the Bayfront I Redevelopment Plan as adopted by Jersey City on March 12, 2008.

28. **Remedial Investigation Work Plan Addendum or RIWP Addendum** shall mean the "Remedial Investigation Work Plan Addendum Study Area 6 South" submitted to NJDEP on June 27, 2008.

29. **Riverkeeper** shall mean the plaintiffs in *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-22 (DMC), and includes the Hackensack Riverkeeper, Inc., William Sheehan, Reverend Winston Clarke, and Lawrence Baker.

30. **Sediment Consent Order** shall mean the Consent Order on Sediment Remediation and Financial Assurances, entered by the Court in *ICO v. Honeywell* and this Consolidated Litigation on May 28, 2008.

31. **Shallow Groundwater** or **Shallow Level of Groundwater** shall mean groundwater above the meadow mat, groundwater at stratigraphically equivalent depths in locations where there is no meadow mat, and groundwater that is contaminated by recent contact with COPR or other chromium soil contamination above the meadow mat and subsequently flows downward through or past the meadow mat into the upper portion of the lacustrine sediments. This does not include groundwater found in the bedrock, the deep zone, or any plume of contamination that is in both the intermediate and deep zones, as those zones are defined in the Final Groundwater Investigation Report, prepared in *ICO v. Honeywell*, dated February 2007, p. 1-2.

32. **Site** shall mean Study Area 6 South.

33. **Site Preparation Activities** shall mean those activities necessary to begin implementation of the Chromium Remedy in Article III of this Consent Decree, including, if appropriate, the temporary or permanent relocation of current activities and operations conducted on Study Area 6 South.

34. **Soil** shall mean soils, historic fill, and/or COPR.

35. The **Special Master** shall mean Senator Robert G. Torricelli, appointed as the Special Master in *ICO v. Honeywell* and the Consolidated Litigation, and his successors or whomever the Court may appoint as Special Master.

36. **Stratum O** shall mean the layer composed of soft brown silty fine sand interlayered with soft gray silty clay and fine sandy to clayey silt generally located above the meadow mat below the Historic Fill and/or COPR.

37. **Study Area 5** shall mean that property comprising Sites 79, 90, 117, 153, and 184 of the Chromate Chemical Production Waste Sites designated by NJDEP, comprising approximately 42 acres and including (a) all such property owned by Bob Ciasulli consisting of Block 1291, Lot 76, and Block 1292, Lots 1F, 47, 48, 53, and 54PL, located at 540 Route 440, Jersey City, New Jersey, (b) all such property owned by Elisabeth and Rafael Rosario consisting of Block 1292, Lot 49, located at 93 Fisk Street, Jersey City, New Jersey, (c) all such property owned by Michael Vo consisting of Block 1292, Lot 50, located at 95 Fisk Street, Jersey City, New Jersey, (d) all such property owned by NJCU consisting of Block 1286, Lots 5 and 6D and Block 1286.5, Lots 1 and 2, Jersey City, New Jersey, (e) all such property owned by Inland Southeast Jersey City LLC consisting of Lot 1, Block 1285.5 located at 440 Route 440, Jersey City, New Jersey, and (f) all such property owned by 425/445 Route 440 Property LLC, consisting of Block 1289.5, Lot E, Jersey City, New Jersey.

38. **Study Area 6 North** shall mean the property comprising Sites 87 and 88 of the Chromate Chemical Production Waste Sites designated by NJDEP, which is subject to the Study Area 6 North Consent Decree.

39. **Study Area 6 North Consent Decree** shall mean the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North, entered by the Court on April 21, 2008, in the Consolidated Litigation.

40. **Study Area 6 South** shall mean (a) that property currently owned by Bayfront Redevelopment Property LLC consisting of Site 73, located at 200 Kellogg Street Jersey City, Hudson County, New Jersey; (b) that property currently owned by Bayfront Redevelopment LLC consisting of Site 134, located at 100 Kellogg Street Jersey City, Hudson County, New Jersey; (c) that property currently owned by Bayfront Redevelopment LLC consisting of Site 140 located at 80 Kellogg Street Jersey City, Hudson County, New Jersey; (d) that property currently owned by Bayfront Redevelopment LLC consisting of Site 125, located at 60 Kellogg Street Jersey City, Hudson County, New Jersey; (e) that property currently owned by Bayfront Redevelopment LLC consisting of Site 124, Jersey City, Hudson County, New Jersey; (f) that property currently owned by Kellogg St/Harsimus Cove Realty located at 150 Kellogg Street, Jersey City, Hudson County, New Jersey, (g) that property currently owned by Bayfront Redevelopment LLC located at 38 Kellogg Street, Jersey City, Hudson County, New Jersey; (h) that property currently owned by Bayfront Redevelopment LLC located at 28 Kellogg Street, Jersey City, Hudson County, New Jersey; and (i) that property currently owned by Bayfront Redevelopment LLC, consisting of Site 163, formerly the Colonial Concrete Company, located at 75 Kellogg Street in Jersey City, Hudson County, New Jersey.

41. **Study Area 6** shall mean Study Area 6 North and Study Area 6 South, collectively.

42. **Study Area 7** shall mean (a) that property currently owned by Bayfront Redevelopment LLC located at 425 and 445 Route 440, Jersey City, Hudson County, New Jersey, and (b) that

property currently owned by Bayfront Redevelopment LLC located at 465 Route 440, Jersey City, Hudson County, New Jersey.

43. **Technical Requirements for Site Remediation** shall mean the NJDEP Technical Requirements for Site Remediation, N.J.A.C. Chapter 26E, as duly and properly promulgated and amended.

44. **Unrestricted Use** shall mean that the contaminated medium is restored to a condition or quality suitable for all uses.

## ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED

45. This Court has jurisdiction over the Parties and subject matter of the Consolidated Litigation pursuant to Section 6972 of RCRA.

46. For purposes of this Consent Decree, the Riverkeeper Complaint in the Consolidated Litigation states claims upon which relief may be granted against Honeywell.

47. In the event that this Decree is not terminated by one or more Parties pursuant to paragraph 113, this Consent Decree resolves, settles, and satisfies all claims by Riverkeeper against Honeywell with respect to soils, shallow groundwater and L-Well groundwater at Study Area 6 South. This Consent Decree does not resolve any claims by Riverkeeper against Honeywell with respect to Study Area 5 or property owned by Regnal Realty consisting of Block 1288.2, lot 1, located at 420 Route 440, Jersey City, New Jersey.

48. Nothing in this Consent Decree shall be construed or interpreted to waive any claim or defense any Party has asserted or may assert against any third party in the Consolidated Litigation except as explicitly stated herein.

49. This Consent Decree does not constitute an admission of liability on the part of any Party with respect to any claims, cross-claims, or counter-claims in the Consolidated Litigation.

## ARTICLE III: CHROMIUM REMEDIATION

### A. General Terms and Requirements

50. **Responsibility for Implementation of Chromium Remediation.** As between the Parties, Honeywell shall be responsible for and shall undertake remediation of COPR and chromium present in Study Area 6 South at Honeywell's sole cost and expense. Remediation of COPR and chromium present in Study Area 6 South shall be undertaken in accordance with the terms of this Consent Decree.

51. **Designation of Chromium Areas of Concern.** For the purposes of remediation, Study Area 6 South shall consist of two AOC's, designated as the Open Space AOC and the Development AOC as shown approximately on Exhibit A. The exact boundaries of the two AOC's shall be subject to further delineation during the design and implementation of the Chromium Remedy.

52. **Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan.** The Chromium Remedy shall be consistent with the NJDEP Technical Requirements for Site Remediation, the Chromium Directive as issued by NJDEP on February 8, 2007 ("the NJDEP Chromium Directive"), and any Remedial Action Work Plan, including any modifications or addenda approved by NJDEP. Prior to submitting any Remedial Action Work Plan, Honeywell shall take all reasonable steps to ensure that the plan is consistent with the Chromium Remedy. However, this Consent Decree shall have precedence over any Remedial Action Work Plan in the event of any inconsistency. The approved Remedial Action Work Plan is a minimum standard, and the Chromium Remedy may be more protective than the remedy NJDEP approves.

53. **General Scope of the Chromium Remedy.** The Chromium Remedy shall address shallow groundwater and L-Well groundwater containing total chromium concentrations of 70 µg/l or greater and soil containing hexavalent chromium at concentrations of 20 mg/kg or greater within the top 20 feet of soil below the ground surface, and shall be consistent with the requirements set forth in this Article. The Chromium Remedy set forth in this Consent Decree addresses only the shallow and L-Well levels of groundwater (see paragraphs 69 - 72). The deep overburden and bedrock groundwater remediation, including source control, is addressed in the Deep Groundwater Consent Order.

54. **Development of a Schedule for the Chromium Remedy.** The Chromium Remedy shall be carried out diligently, and the development and implementation of any remedy required by NJDEP for non-chromium contamination shall not delay satisfaction of the milestones in the Schedule established pursuant to this paragraph. Within 90 days of entry of this Consent Decree, Honeywell shall propose a Master Schedule for the implementation of the Chromium Remedy .

(a) The Master Schedule shall incorporate the following dates:

(i) No later than August 15, 2008, Honeywell shall submit a Chromium Impacted Soils Pilot Test Work Plan to NJDEP and Riverkeeper;

(ii) No later than September 15, 2008, Honeywell shall complete field work in accordance with the RIWP Addendum;

(iii)No later than December 31, 2008, Honeywell shall submit an Initial Treatment Study Report and Remedial Action Work Plan pursuant to paragraph 86(c);

(iv) No later than July 31, 2012, Honeywell shall submit the soil and groundwater data from its 2010 and 2011 supplemental investigation of Site 163, a brief summary report, and

a designation of the boundaries of the Site 163 Development AOC to the Special Master pursuant to paragraph 86(c);

(v) No later than October 1, 2012, Honeywell shall submit an addendum to the Study Area 6 South 100% Design setting forth the 100% Design for the Site 163 Development AOC portion of the Study Area 6 South Chromium Remedy; and

(vi) Honeywell shall undertake, in good faith, to begin implementation of the Chromium Remedy by March 1, 2013.

(b) In addition, the Master Schedule shall propose deadlines for the following milestones:

(i) Submission of all documents subject to submission and review pursuant to paragraph 86(c);

(ii) Completion of those Site Preparation Activities necessary for the implementation of the Chromium Remedy;

(iii)Submission, following implementation of the soil components of the Chromium Remedy for the Development AOC, of the groundwater plans and reports required by paragraphs 70 and 72;

(iv)Completion of additional sampling for shallow groundwater delineation pursuant to paragraph 71 and a proposal for a remedy pursuant to paragraph 71, if needed;

(v) The submission of a 50% Design Report for the Chromium Remedy;

(vi) The submission of a 100% Design Report for the Chromium Remedy;

(vii) The date for completion of the installation of the Chromium Remedy;

(viii)Implementation of the long-term protections of the Open Space AOC established pursuant to paragraph 74; and

(ix) Transfer of the Open Space AOC to Jersey City pursuant to paragraph 74(a)(iii).

### B. Initial Chromium Remedy Steps: Delineation, Treatment Study, and Remedial Action Work Plan

55. **Delineation of Development AOC.** Honeywell shall conduct further soil sampling on Study Area 6 South in accordance with the RIWP Addendum. In addition to the locations set forth in the RIWP Addendum, Honeywell shall conduct further soil sampling pursuant to the provisions of the RIWP Addendum at the boring locations set forth in Exhibit E. Upon completion of the soil sampling required by this paragraph, Honeywell shall submit a Second Supplemental Remedial Investigation Report that sets forth the results of the sampling and Honeywell's proposal as to the delineation of the Development AOC. In conjunction with its proposal, Honeywell shall set forth its rationale as to whether prior sampling data should be included or excluded in the proposed delineation. The soil sampling and submission of a Second Supplemental Remedial Investigation Report shall be completed in accordance with the Schedule set forth in paragraph 54. Honeywell shall submit the Second Supplemental Remedial Investigation Report pursuant to paragraph 86(c). The Site 163 Development AOC shall be exempt from the requirements of paragraphs 55-58.

56. **Conduct of a Treatment Study in the Development AOC.** Honeywell shall conduct a field study of the efficacy of *in situ* treatment of 20 to 1000 Soils in accordance with the Chromium Impacted Soil Pilot Test Work Plan. The purpose of the pilot test shall be to evaluate whether *in situ* chemical treatment of 20 to 1000 Soils with one or more reductants can result in the permanent establishment of hexavalent chromium concentrations below 20 mg/kg under conditions in those areas of the Development AOC that may be subject to treatment as a remedy. Honeywell shall provide the raw data from the pilot test to NJDEP and Riverkeeper in scientifically useable electronic form as soon as the data become available. Honeywell shall

submit an Initial Treatment Study Report setting forth the initial results of the pilot test pursuant to paragraph 86(c) .

57. **Continued Monitoring of the Treatment Study.** As the result of the need to complete Study Area 7 remediation, to maintain Study Area 7 remediation support operations currently located on Study Area 6 South, and to conduct Site Preparation activities including the relocation of operating businesses on Study Area 6 South in advance of implementation of the Chromium Remedy, the Parties do not anticipate that implementation of field work for the Chromium Remedy will begin until March 1, 2013. Honeywell shall continue to monitor the performance of the pilot test and shall submit a Final Treatment Study Monitoring Report assessing the long term effectiveness of treatment for 20 to 1000 Soils in the Development AOC pursuant to paragraph 86(c) no later than December 31, 2011.

58. **Submission of a Remedial Action Work Plan.** On or before December 31, 2008, Honeywell shall submit a Remedial Action Work Plan for the Chromium Remedy pursuant to paragraph 86(c). The Remedial Action Work Plan shall be consistent with the Chromium Remedy set forth in this Consent Decree.

### C. Development AOC Soil Remedy

59. **Remedial Components.** In the Development AOC, soils containing hexavalent chromium at concentrations greater than 20 mg/kg shall be remediated as follows:

(a) Soils with a concentration greater than 1000 mg/kg shall be:

(i) Excavated and disposed of off-site at a waste disposal facility licensed to accept such waste; or

(ii) Treated *ex situ* and consolidated under the cap in the Open Space AOC provided the requirements of paragraphs 60 and 63 are satisfied and provided that such soils do not

require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a).

(b) 20 to 1000 Soils shall be:

(i) Excavated and consolidated within the Open Space AOC provided that such soils do not require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a); or

(ii) Excavated and disposed of off-site pursuant to the requirements of paragraph 59(a); or

(iii) Remediated pursuant to paragraphs 59(c) or 59(d) provided that such soils are also 20 to 240 soils and meet the requirements of paragraphs 59(c) or 59(d).

(c) 20 to 240 Soils may be remediated by excavation and consolidation within the Study Area 6 North AOC 1 Open Space Area, provided that such soils do not require venting of gases and shall not serve as the basis for the inclusion of gas venting as part of the Study Area 6 North AOC 1 Open Space Area remedy.

(d) 20 to 240 Soils within the Site 163 Development AOC may be remediated by *in situ* treatment, provided the requirements of paragraph 61 are satisfied.

60. **Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** *Ex situ* treatment and consolidation under the Open Space AOC cap may be used as a remedial component for soils containing greater than 1000 mg/kg hexavalent chromium provided that the requirements of this paragraph are satisfied:

(a) Honeywell demonstrates in the Final Treatment Study Monitoring Report that the proposed treatment will likely result in the reduction of the hexavalent chromium concentration of the treated soils such that the post-treatment total chromium concentration shown by Toxicity

Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C);

(b) Following a review of the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d), NJDEP agrees that Honeywell has made the demonstration required by paragraph 60(a).

(c) Plaintiffs have had an opportunity to review and comment on the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d)and pursuant to the Special Master review process set forth in paragraphs 86(e)-86(f); and

(d) Following review of the demonstration required by paragraph 60(a) pursuant to the Special Master review process set forth in paragraph 86(f), the Special Master issues a recommendation finding that Honeywell has made the demonstration required by paragraph 60(a) or the Court finds that Honeywell has made the demonstration required by paragraph 60(a) in the event that any Party seeks the Court's review of the Special Master's recommendations under this paragraph.

61. **Treatment as a Remedial Component for 20 to 240 Soils.** *In situ* treatment may be used as a remedial component for the 20 to 240 Soils in the Site 163 Development ACO, provided that such soils are 3 feet or more below ground surface and the requirements of this paragraph are satisfied:

(a) If Honeywell elects to treat *in situ* 20 to 240 Soils in the Site 163 Development AOC, Honeywell shall include in the 100% Design Addendum for Site 163 a plan for such treatment. Such treatment plan shall be comparable in detail and approach to the pipeline treatability plan which is Appendix F to the Study Area 6 North 100% Design. The goal of such *in situ* treatment

shall be to reduce hexavalent chromium soil concentrations to less than 20 mg/kg in soils 20 feet or less below ground surface;

(b) Three years after conducting the treatment set forth in subparagraph (a), Honeywell shall collect additional soil samples in the treated areas to evaluate the success of the treatment. These soil samples shall be analyzed for EH, pH, hexavalent chromium (using EPA/NJDEP Methods 3060A/7199), and sulfides (using EPA Method 9030B). Within 60 days of its receipt of the final data from such sampling, Honeywell shall submit a report with such data to the Special Master pursuant to paragraph 86(c);

(c) In the event that the sampling pursuant to subparagraph (b) shows that soils with greater than 20 mg/kg hexavalent chromium remain or that excess treatment reductant remains present, Honeywell may elect to pursue one or more of the following approaches after providing notice to the Special Master, Riverkeeper and the Jersey City Entities;

(i) In the case of excess treatment reductant remaining in the soil, continue to monitor such areas pursuant to subparagraph (b) until the excess reductant is no longer present;

(ii) In the case of soils with greater than 20 mg/kg hexavalent chromium:

(1) Excavate such soils and consolidate them under the cap in the Open Space AOC, consolidate them under the cap in the Study Area 6 North AOC 1 Open Space Area, and/or dispose of them off-site provided that in each instance the applicable requirements of paragraph 59 are satisfied;

(2) Conduct further *in situ* treatment using additional treatment reductant and submit a monitoring plan pursuant to paragraph 64; or

(3) In the event that the soils are within the areas depicted as River Front Park, Riverfront Drive or Kellogg Street on page 39 of the Redevelopment Plan, cover the affected

soils with a road, walkway, and/or other hardscape and restrict the use of that area through each of the following institutional controls:

(a) Issuance and recording of a conservation restriction comparable to that required under paragraphs 74(b) and 74(d);

(b) Transfer of title to that area to Jersey City pursuant to paragraphs 74(a)(iii) through 74(a)(iv)(2); and

(c) Issuance and recording of a deed notice comparable to that required under paragraphs 74(c) and 74(d).

62. **Submissions Related to Site 163.** Pursuant to the Schedule, Honeywell shall prepare and submit the following with regard to Site 163:

(a) A summary report of all chromium soil and groundwater data collected during site investigations in 2010 and 2011; and

(b) An addendum incorporating Site 163 into the 100% Design.

63. **Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** In the event that *ex situ* treatment is used as a final remedy for any portion of the soils containing greater than 1000 mg/kg pursuant to paragraph 59(a)(ii), Honeywell shall conduct post-treatment analysis of each treated batch of soil to demonstrate that the treatment has resulted in the reduction of the hexavalent chromium concentration such that the post-treatment total chromium concentration shown by Toxicity Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C). Such monitoring and demonstration shall be made prior to consolidation of the treated soils under the Open Space AOC cap pursuant to paragraph 59(a)(ii). In the event that Honeywell fails to make the demonstration required by this paragraph,

Honeywell shall dispose of the soils off-site at a waste disposal facility licensed to accept such waste.

64. **Post-Treatment Monitoring for 20 to 1000 Soils.** In the event that *in situ* treatment is used as a final remedy for any portion of the 20 to 1000 Soils, Honeywell shall conduct post-treatment monitoring to demonstrate that the treatment has resulted in permanent hexavalent chromium concentrations of less than 20 mg/kg in the treated area. Honeywell shall propose a program of post-treatment monitoring in a document that is submitted pursuant to paragraph 86(c). In the event that Honeywell fails to make the demonstration required by this paragraph, Honeywell shall propose further remedial actions pursuant to paragraph 59 in a document that is submitted pursuant to paragraph 86(c).

**D. Open Space AOC Components of the Chromium Remedy**

65. **Open Space AOC Soil Remedy.** In the Open Space AOC, the soil remedy shall consist of an engineered RCRA cap to isolate contaminated soils with gas venting, if necessary, to address the generation of methane and other naturally occurring gases in the Stratum O and/or Stratum D in the Open Space AOC. Soils consolidated under the cap, pursuant to paragraph 59(b)(i), shall not require gas venting and shall not be the basis for the inclusion of gas venting as a component of the cap. The cap shall be designed and constructed so that:

(a) The cap shall consist of a gas collection system, if gas venting is necessary, a base protective layer, an impervious geomembrane liner with a minimum thickness of 40 mil; a geocomposite drainage layer; a filter fabric; and a distinctive colored warning layer with markings in English and Spanish that would deter penetration of the cap in the event that digging occurred in the vicinity of the cap;

(b) All utilities, including those supporting the pump-and-treat system for groundwater remediation, with the exception of any extraction wells or collection trenches, shall be placed above the cap (but may be below the ground surface and/or contained within utility corridors). In the event that above-cap-grade gas collection and treatment is selected or is needed to meet current or future regulatory requirements, such collection and treatment facilities are prohibited in the Open Space AOC, except for piping to connect the sub-liner collection system with the treatment facilities; and

(c) Exclusive of roadways, the cap shall be overlain by layers of clean fill, backfill and/or overburden with an average depth of at least three feet and a minimum depth of at least two feet provided that any layer that incorporates overburden shall be below at least two feet of clean fill. Any clean fill or backfill soil brought to the Site will either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master. One foot of clean fill, covered with bituminous blacktop, shall be sufficient cover where roads, walkways, or other paved surfaces are located within the Open Space AOC. All clean soil fill in areas that will not involve paved roads, walkways, or other paved surfaces shall be vegetated in such a manner as to protect and maintain the required depth of the clean soil fill and to ensure that such vegetation shall not cause any interference with or penetration of the cap.

(d) The existing overburden soils in the Open Space AOC shall first be stripped off and set aside for use. If hexavalent chromium concentrations in the overburden exceed 20 mg/kg, the overburden shall be placed under the cap. If hexavalent chromium concentrations in the overburden do not exceed 20 mg/kg, the overburden may be placed above the cap but below the

two feet of clean fill required by paragraph 65(c). Excavated 20 to 1000 Soils from the Development AOC shall be placed and spread in the Open Space AOC under the cap. Both the chromium impacted soils and the previously stripped overburden shall be suitably compacted according to design specifications. Debris, to the extent it would interfere with the compaction specification requirements of the 100% Design, shall not be placed under the cap. The engineered cap shall be installed over the chromium-impacted soils exceeding 20 mg/kg hexavalent chromium.

**E. Demolition, Grading, and Backfill Requirements**

66. **Demolition and Grading Activities.** During demolition and grading activities, adequate protective measures shall be taken to protect site workers and the community from airborne dusts and exposures to contaminated soils.

67. **Backfill Requirements.** Soils excavated from the Development AOC shall be replaced with backfill soil. Any backfill soil brought to the Site shall either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master.

68. **Vegetation of Clean Fill.** All clean soil fill in areas that will not involve paved roads, sidewalks, paths, walkways, or building structures shall be vegetated in such a manner to protect and maintain the required depth of clean soil fill.

**F. Groundwater Components of the Chromium Remedy**

69. **Shallow Groundwater Remedy for the Open Space AOC.** The Open Space AOC shallow groundwater remedy shall consist of hydraulic barriers with a pump-and-treat system designed to isolate shallow groundwater and to intercept and treat shallow groundwater flowing

above the meadow mat in the Open Space AOC to the extent that such groundwater contains total chromium in concentrations in excess of 70 µg/l. The shallow groundwater remedy shall consist of the following:

(a) The existing soil/cement/bentonite wall on the boundary of Study Area 6 South and Study Area 7 shall be incorporated into the other engineering controls;

(b) Subterranean slurry walls or other hydraulic barriers shall be installed along the southern, eastern and western sides of the Open Space AOC and keyed into the meadow mat or Stratum O or to comparable depths below ground surface;

(c) A groundwater extraction system shall be established that shall consist of (i) one or more shallow extraction wells, sumps, or french drains within the Open Space AOC; (ii) pumps; and (iii) underground piping to convey any extracted water to Honeywell's Treatment Plant;

(d) The capture zone for the shallow groundwater remedy shall include at least the entire area of contaminated shallow groundwater within the Open Space AOC;

(e) A plan for control of water levels shall be developed;

(f) In the event that underground structures are demolished, the plans shall address the need for special attention for structures that extend below the meadow mat in order to control needed water levels; and

(g) Honeywell shall submit such information as is required to allow NJDEP to establish a classification exception area for groundwater at the Site, in accordance with NJDEP regulations.

70. **The Shallow Groundwater Remedy for the Development AOC.** Following implementation of the Development AOC soil components of the Chromium Remedy, Honeywell shall submit a report to (a) determine whether shallow groundwater remaining in the

Development AOC exceeds 70 µg/l total chromium and, (b) if so, evaluate the need for further remedial measures to address any such shallow groundwater remaining in the Development AOC with total chromium concentrations in excess of 70 µg/l. This evaluation shall be subject to review and comment by the Parties and approval by the Special Master.

(a) In the event that the evaluation demonstrates that further remedial measures are necessary, Honeywell shall propose such measures subject to review and comment by the Parties and approval by the Special Master;

(b) The capture zone of any remedy shall include at least the entire area of contaminated shallow groundwater except for shallow groundwater that is captured and subject to the shallow groundwater remedy for the Open Space AOC pursuant to paragraph 69;

(c) In the event that a pump-and-treat system is selected as a contingency measure for shallow groundwater in the Development AOC, all infrastructure for the pump-and-treat contingency system that is needed to ensure that the contingency system is fully operational, as required by paragraph 70(d), shall be installed prior to or in conjunction to any development of the Site. This includes at least one shallow extraction well, sump, or french drain, and the piping to convey any extracted groundwater to Honeywell's water treatment plant;

(d) If it is determined that the pump-and-treat contingency system must be activated, the pump-and-treat system shall be operational no later than six months after the date of the determination.

71. **Off-Site Shallow Groundwater Remedy.** Honeywell shall propose additional sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site. Honeywell shall submit a report of the results of such sampling and, in the event that contaminated shallow groundwater is found to extend off-site, a proposal for a remedy based on

such results. The report and the proposal for a remedy shall be subject to review and comment by the Parties and approval by the Special Master.

72. **L-Well Groundwater Remedy.** At the time this Decree is entered, the L-Well Groundwater is contained and not contributing to further contamination of surrounding waters and/or soils. However, in order to verify that this status continues following implementation of the Chromium Remedy, including any groundwater remedial measures pursuant to paragraphs 70 and 71, Honeywell shall propose a plan for one round of monitoring designed to evaluate whether the L-Well Groundwater remains contained. The plan shall include monitoring for total and hexavalent chromium and major ion chemistry to determine whether there has been movement in the L-Well Groundwater.

(a) In the event that no substantial change is detected in the major ion chemistry, no further action is required unless paragraph 72(c) is applicable.

(b) In the event that substantial changes are detected in the major ion chemistry, Honeywell shall propose a plan for further monitoring of the L-Well Groundwater. Such a plan shall be subject to review and comment by the Parties and approval by the Special Master.

(c) In the event that the initial monitoring or monitoring conducted pursuant to paragraph 72(b) demonstrates that proximate waters have total chromium concentrations in excess of 70 µg/l, regardless of whether there is a change in the major ion chemistry, Honeywell shall propose a remediation plan for the L-Well Groundwater. Such remediation plan shall be subject to review and comment by the Parties and approval by the Special Master.

### G. Permits and Authorizations

73. **Permits and Authorizations.** Honeywell shall obtain all necessary federal, state, and local permits and authorizations to carry out the Chromium Remedy as set forth in this Article.

## H. Long-Term Monitoring, Maintenance, and Protection of Engineering and Institutional Controls

74. **Protection of the Open Space AOC.** Except as provided in paragraphs 74(j) and 74(k), development in the Open Space AOC shall be prohibited. The Open Space AOC shall be protected against activities that may jeopardize the integrity of the cap and/or the groundwater remedial measures that shall be installed in the Open Space AOC pursuant to the Chromium Remedy or that may impede the long-term monitoring and maintenance of the cap and/or groundwater remedial measures. It is the intention of the Parties to implement different layers of protection, which alone or in concert, impose restrictions on development, run with the land, and survive all parties. Accordingly, the following actions shall be taken pursuant to the Schedule provided in paragraph 54:

(a) **Ownership of and Access to the Open Space AOC.** Ownership of and access to the Open Space AOC shall be in accordance with the following:

(i) Bayfront Redevelopment LLC, as the current owner in fee simple absolute of all property that comprises the Open Space AOC, shall not convey any rights or interests in any parcel that comprises the Open Space AOC property except as provided in this Decree. Within 90 days of entry of this decree, Bayfront Redevelopment LLC shall give Jersey City an option to buy all of the Open Space AOC property prior to the planned transfer pursuant to paragraph 74(a)(iii). Such option to buy shall be subject to the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall exercise the option to buy the Open Space AOC in the event that the conditions allowing for withdrawal of funds from the financial assurance mechanisms under paragraphs 98(c) or 98(d) are met;

(ii) Within 90 days of the entry of this Consent Decree, Bayfront Redevelopment LLC shall grant a conservation restriction for the Open Space AOC pursuant to the requirements of paragraph 74(b);

(iii) Upon the final construction of all roads and utility corridors within the Open Space AOC, Bayfront Development LLC shall donate good and marketable title to all the land comprising the Open Space AOC to Jersey City. In conjunction with such donation, Bayfront Redevelopment LLC shall petition to subdivide the properties within Study Area 6 South to create a new parcel(s) comprising the Open Space AOC. At the time of the donation, Jersey City shall grant Honeywell an easement for the purpose of monitoring and maintaining the Chromium Remedy. Jersey City shall also grant Honeywell all necessary access to the Open Space AOC by license or such other mechanisms as may be appropriate for purposes of monitoring and maintaining the Chromium Remedy. After it acquires title pursuant to this paragraph, Jersey City shall retain ownership of the Open Space AOC unless and until it shall have complied with the requirements of paragraph 74(a)(iv);

(iv)After it acquires title pursuant to this paragraph, Jersey City shall not convey or enter into any lease of the Open Space AOC to any other person or entity unless it has first satisfied either of the following conditions:

(1) Jersey City has obtained the Special Master's (or if the Special Master's appointment has expired, the Court's) approval to convey the Open Space AOC to a government entity that has the capacity and willingness to fulfill Jersey City's obligations under the Consent Decree with respect to the Open Space AOC and such entity agrees to submit to the Court's jurisdiction and to be bound by the requirements of the Consent Decree that Jersey City has committed to fulfill with respect to protection of the Open Space AOC pursuant to this paragraph

and routine maintenance of the permissible development in the Open Space AOC pursuant to paragraph 78(d); or

(2) The Open Space AOC has been remediated such that no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive, and Jersey City has demonstrated to the Special Master and/or the Court, as appropriate, that such remediation has been completed in accordance with all applicable requirements.

(b) **Conservation Restriction.** Prior to the grant of the option to buy pursuant to paragraph 74(a)(i), Bayfront Redevelopment LLC shall grant an open space conservation restriction, pursuant to N.J.S.A. 13:8-B-1, *et seq.*, over the Open Space AOC substantially in the form set forth in Exhibit C. Exhibit C is a conservation restriction that is consistent with the terms of this paragraph and this Consent Decree. The conservation restriction shall allow for the implementation, maintenance, monitoring, repair and replacement of the Chromium Remedy and development consistent with paragraphs 74(j) and 74(k), including the construction and placement of roads and utilities. The Conservation Restriction shall also allow for current uses of the Open Space AOC to continue until such time as construction of the Chromium Remedy begins. The Hackensack River Watershed Land Trust shall be the primary holder of the conservation restriction, with all rights of monitoring and enforcement. Riverkeeper shall propose an entity to serve as the secondary holder of the conservation restriction subject to comment by the Parties and review by the Special Master. The secondary holder shall have secondary rights of monitoring and enforcement.

(i) The conservation restriction shall be incorporated into this Consent Decree and made part of this Consent Decree. The final, executed conservation restriction shall be lodged with the Court and entered as an order of the Court. The conservation restriction shall be enforceable in this Court, in the same manner as this Consent Decree.

(ii) The conservation restrictions provided under this Consent Decree shall be consistent with the prohibited and permitted development of the Open Space AOC as set forth in paragraphs 74(j) and 74(k) below.

(iii) Jersey City shall not take any action, whether through exercise of any power of eminent domain, application to the State of New Jersey for approval of a diversion of public park or recreation land, legal challenge to the validity or enforceability of the conservation restriction, or otherwise, the effect of which would be to in any way terminate, abrogate, or diminish the terms, conditions, or purposes of the conservation restriction. If, notwithstanding the preceding sentence, Jersey City proceeds with a condemnation or other action, the result of which would be to terminate, abrogate, or otherwise diminish the terms, conditions, or purposes of the conservation restriction, Jersey City shall, before taking any such action satisfy all of the conditions set forth in paragraph 74(a)(iv)(2).

(iv) Notwithstanding the foregoing, the conservation restriction may be terminated upon application of any Party when no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive.

(c) **Deed Notice.** Upon completion of the Chromium Remedy, the Open Space AOC shall be subjected to the deed notice substantially in the form set forth in Exhibit D that restricts

future activities on the Open Space AOC. Nothing in the deed notice shall be construed as preventing the imposition of more stringent restrictions on the development allowed in the Open Space AOC pursuant to this paragraph and, in particular, the conservation restriction provided for in paragraph 74(b).

(d) **Recording of the Consent Decree, Conservation Restriction, and Deed Notice.** This Consent Decree, the conservation restriction imposed pursuant to paragraph 74(b), and the deed notice imposed pursuant to paragraph 74(c) shall be recorded, pursuant to N.J.S.A. §§ 46:15-1.1, 46:16-1.1, and 46:16-2, in the office of the Hudson County Register and a conspicuous reference to the Consent Decree, conservation restriction, and deed notice shall be included in all instruments concerning title to the Open Space AOC. Any Party shall have the right, periodically, but no more than once every 25 years, to record memoranda or other instruments that reference, incorporate, or attach this Consent Decree, the conservation restriction, the deed notice, and/or any further orders of the Court related to the Open Space AOC in the real estate records related to the Open Space AOC.

(e) **Zoning.** Pursuant to the Redevelopment Plan, the Open Space AOC is designated for open space and park. Jersey City shall not amend or change this designation unless it first satisfies the requirements of paragraph 74(a)(iv)(2).

(f) **Recreation and Open Space Inventory.** Upon acquiring fee simple absolute title to the Open Space AOC, Jersey City shall add those portions of the Open Space AOC not covered by roads, the pedestrian thoroughfare, and utility corridors adjacent to roads onto its Green Acres Program Recreation and Open Space Inventory ("ROSI") pursuant to N.J.A.C. § 7:36 and shall specify in such listing that it is subject to (i) Honeywell's prior easement to monitor, maintain, repair, and replace the Chromium Remedy; (ii) the actions necessary to implement, monitor,

maintain, repair, and replace the Chromium Remedy; (iii) the actions necessary to install any development permissible under paragraphs 74(j) and 74(k); and (iv) the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall also take all steps necessary or appropriate to notify the New Jersey Green Acres Program that such portions of the Open Space AOC have been added to its ROSI, such that those portions of the Open Space AOC shall thereafter be subject to all procedural and regulatory requirements applicable under the Green Acres Program, including prohibitions against diversion.

(g) **Eminent Domain.** If all or part of the Open Space AOC is taken in exercise of the power of eminent domain, or acquired by purchase in lieu of condemnation, by any public, corporate, or other authority so as to terminate, abrogate, or limit the restrictions created by this Consent Decree or the conservation restriction imposed pursuant to paragraph 74(b), in whole or in part, any Party may take appropriate actions to challenge such taking if there is a reasonable legal basis for doing so. In the event that the Parties are unable to prevent a taking notwithstanding their reasonable and appropriate efforts, any Party may take appropriate actions to recover the full value of the interests in the Open Space AOC subject to the taking or in lieu purchase, and all direct and incidental damages, costs, and fees occasioned thereby.

(h) **Environmental Covenant.** In the event that New Jersey enacts the Uniform Environmental Covenants Act or its substantial equivalent, the Parties shall address the issue of whether an environmental covenant shall be established for the Open Space AOC under the statute. If the Parties are unable to reach agreement on establishment of an environmental covenant, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of an environmental covenant if it would provide substantial additional protection for the Open Space AOC without

unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(i) **Future Protections.** Any Party shall have the right to propose consideration of additional or substitute protections for the Open Space AOC. If the Parties are unable to reach agreement with regard to the proposal, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of additional or substitute protections for the Open Space AOC if they would provide substantial additional protection for the Open Space AOC without unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(j) **Prohibited Development in Open Space AOC.** Only development satisfying the requirements of this paragraph and paragraph 74(k) shall be permitted in the Open Space AOC. All other development in the Open Space AOC shall be prohibited.

(i) Honeywell shall establish Open Space Design Standards that shall govern all development in the Open Space AOC regardless of when the construction or installation of permissible development occurs. The Open Space Design Standards shall satisfy each of the requirements set forth in paragraph 74(j)(v) and shall set forth the requirements for development that are necessary for the protection of the integrity of the Chromium Remedy.

(ii) The Initial Development in the Open Space AOC shall be the development undertaken following the completion of the Chromium Remedy in the Open Space AOC. The Initial Development may occur in one or more phases. Honeywell and Bayfront

Redevelopment LLC shall prepare a Development Plan before the initiation of each phase of the Initial Development. The Initial Development Period for each phase shall consist of the period covered by the Initial Development, plus a period of 10 years following the submission of the as-built documentation for the phase pursuant to paragraph 74(j)(viii).

(iii) The Special Master shall have jurisdiction to review the Open Space Design Standards and the Development Plan(s) solely for the purpose of ensuring that any development undertaken during the Initial Development Period is consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy. The Special Master's jurisdiction with regard to development in the Open Space AOC shall run through the Initial Development Period for each phase.

(iv) Honeywell shall ensure that the requirements of this paragraph and paragraph 74(k) are satisfied with regard to any development undertaken within the Initial Development Period. Honeywell shall also ensure that any development undertaken within the Initial Development Period is designed and installed in a manner consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy.

(v) Any development undertaken in the Open Space AOC, regardless of when undertaken, shall satisfy each of the following requirements:

(1) It shall not jeopardize the integrity of the Chromium Remedy;

(2) It shall be limited to the types of development permitted under paragraph 74(k);

(3) It shall be consistent with this Consent Decree, including the conservation restriction imposed pursuant to paragraph 74(b), and the Redevelopment Plan; however, in the

event of any conflict or inconsistency between this Decree and the Redevelopment Plan, this Decree shall govern;

(4) In total, at least 75% of the Open Space AOC, exclusive of the acreage used for roads and the pedestrian thoroughfare, shall be comprised of landscaping, as defined by paragraph 74(k)(xi);

(5) The portion of the Open Space Design Standards necessary for protection of the Chromium Remedy as related to all roads, the pedestrian thoroughfare and associated utility corridors as well as the general location of such items shall be included in the 100% Design of the Chromium Remedy;

(6) If the lowest elevation for the bedding for any utility line, including irrigation or sprinkler lines, is two feet from the top of the warning layer of the cap, the utility line shall be placed in a utility corridor;

(7) In any event, there shall be two feet of soil or more between the warning layer of the cap and the lowest elevation of the bedding for any irrigation or sprinkler lines; and

(8) No permanent concession facilities shall be permitted.

(vi) Honeywell shall submit the Open Space Design Standards and the Development Plan(s) for any development undertaken during the Initial Development Period pursuant to the requirements of paragraph 86(c), except that such documents need not be submitted to NJDEP. Following Honeywell's submission of such documents, the procedures of paragraphs 86(e) and 86(f) shall apply, except that the Special Master need not provide notice to NJDEP.

(vii) During the Initial Development Period, any development in the Open Space AOC shall require the preparation and submission of a Development Plan pursuant to

paragraph 74(j)(vi) and such Development Plan shall be subject to review by the Special Master pursuant to paragraph 74(j)(iii).

(viii) Upon completion of each phase of the Initial Development, Honeywell shall provide as-built documentation for the Initial Development to the Special Master, Riverkeeper, and Jersey City. Upon completion of any further development during the Initial Development Period for the phase, Honeywell shall also provide as-built documentation to the Special Master, Riverkeeper, and Jersey City for the additional development. Such additional as-built documentation for a phase shall not affect the running of the Initial Development Period for the phase.

(ix)During the Initial Development Period, replacement in-kind of development features or facilities included in the Initial Development or minor modifications to the development features or facilities included in the Initial Development shall not require the preparation of a Development Plan or be subject to review by the Special Master, provided that such replacement or modification satisfies the requirements of the Open Space Design Standards, the applicable Development Plan, and paragraphs 74(j)(v) and 74(j)(x)(3)(notice requirement).

(x) After the Initial Development Period, all development is prohibited unless one of the following conditions is met:

(1) Jersey City satisfies the conditions set forth in paragraph 74(a)(iv)(2);

(2) The development is a replacement in-kind and such replacement is made in conformance with the specifications of the Open Space Design Standards, the applicable Development Plan, and paragraph 74(j)(v); or

(3) The development meets the requirements of paragraphs 74(j)(v) and 74(j)(xi), and Jersey City provides notice of its intention to alter or add to the development undertaken in the Initial Development Period. Such notice shall be provided in writing to Honeywell, Riverkeeper, and the holders of the conservation restriction established pursuant to paragraph 74(b) at least 30 days prior to Jersey City's alteration or addition to development undertaken in the Initial Development Period. Honeywell, Riverkeeper, or any holder of the conservation restriction shall have the right to move the Court to prohibit such alteration or addition.

(xi) If any of the development features or facilities that Jersey City seeks to add pursuant to paragraph 74(j)(x) require utilities that would require utility corridors other than the utility corridors installed during the Initial Development Period, Jersey City shall obtain approval from the Court before installing such new utility corridors.

(xii) Jersey City shall provide Honeywell, Riverkeeper, and the holder(s) of the conservation restriction established pursuant to paragraph 74(b) with an annual report that describes any alterations or additions, including those activities under paragraph 74(j)(x)(2), to the development undertaken during the Initial Development Period.

(xiii) All development features or facilities, whether included in the Initial Development or added subsequent thereto, are subject to demolition and/or removal to the extent necessary to maintain, replace, or repair the Chromium Remedy.

(k) **Permissible Development in the Open Space AOC.** The Initial Development or any subsequent addition or alteration thereto may include any or all of the following types of development features or facilities, provided that such development features or facilities satisfy the conditions set forth in paragraph 74(j)(v):

(i) Roads and the pedestrian thoroughfare -- both crossing and running along the Open Space AOC, but no more extensive than provided for in the diagram on page 39 of the Redevelopment Plan;

(ii) Curbing and fences;

(iii) Sidewalks, paths, walkways, and nature trails;

(iv) Utilities and utility corridors, lighting, and restrooms;

(v) Irrigation or sprinkler components or systems;

(vi) Water features;

(vii) Above-ground storm water cisterns;

(viii) Signs, including the signs or display required by paragraph 74(l);

(ix) Benches, trash receptacles, and bicycle racks;

(x) Recreational facilities, such as playground equipment, bocce ball courts, tennis courts, basketball courts, and athletic fields; and

(xi) Landscaping, including natural grasses, small trees, shrubbery, flowers, and potted plants, provided that such landscaping and the anticipated root structure of each landscaping component do not and will not jeopardize the integrity of the Chromium Remedy. Any portion of an athletic field that is covered in natural grass shall be considered landscaping for purposes of the percentage set forth in paragraph 74(j)(v)(4).

(l) **Signs or Displays.** Honeywell shall develop a permanent plan for informing visitors to the Open Space AOC of the history of the chromium production, contamination, and its remediation. Such plan shall provide for appropriate signs or displays that communicate this information. Such plan shall be subject to review and comment by the Parties and approval by the Special Master.

75. **Honeywell's Ongoing Responsibility.** Honeywell shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy in perpetuity. Honeywell shall satisfy this responsibility through establishment and implementation of a Long-Term Monitoring Plan. In the event that Honeywell ceases to exist without a successor-in-interest or its obligations under this Consent Decree are stayed or limited due to a bankruptcy petition, the Court shall appoint an independent third-party fiduciary who shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy pursuant to the requirements of this Consent Decree and the Long-Term Monitoring Plan, unless Jersey City volunteers to assume these responsibilities for the Chromium Remedy.

76. **Long-Term Monitoring Plan.** In consultation with the Parties, and subject to approval by the Special Master and NJDEP, Honeywell shall develop a Long-Term Monitoring Plan to ensure the ongoing effectiveness of the Chromium Remedy to meet the objectives set forth in paragraphs 65, 69, 68, 69, 72, and 77. The Long-Term Monitoring Plan shall be consistent with the applicable EPA policies and guidance, including, among others, EPA's Comprehensive Five Year Review Guidance (2001) (or any subsequent revision) and with NJDEP's Technical Requirements for Site Remediation (or any subsequent revision).

77. **Long-Term Monitoring Plan Objectives.** Honeywell shall design the Long-Term Monitoring Plan to satisfy each of the following objectives:

(a) Provide monitoring to ensure that the integrity and effectiveness of the Chromium Remedy are maintained; and

(b) Provide monitoring to ensure that the restrictions of the institutional controls are being satisfied, including the prohibition on development in the Open Space AOC.

78. **Monitoring and Remediation Under the Long-Term Monitoring Plan.** The Long-Term Monitoring Plan shall include the monitoring and remediation activities set forth in this paragraph and other monitoring and remediation activities, if necessary, to meet the objectives of paragraph 77. Honeywell shall provide Riverkeeper, the Special Master, and NJDEP with annual reports on activities conducted under the Long-Term Monitoring Plan.

(a) **Monitoring Activities in the Long-Term Monitoring Plan.** Honeywell shall undertake the following monitoring activities at intervals to be specified in the Long-Term Monitoring Plan, but no less frequently than set forth below, and, if the monitoring shows it is necessary, Honeywell shall also undertake the remediation activities as set forth below:

(i) Quarterly visual inspection monitoring of the Open Space AOC to ensure that it is not being put to any use that is inconsistent with paragraphs 74(j) and 74(k) or any use that may compromise the integrity of the Chromium Remedy. The Long-Term Monitoring Plan shall include an inventory of the prohibited and permissible uses pursuant to paragraph 74 and a corresponding checklist to be used by the individuals conducting the monitoring. If Honeywell determines that the Open Space AOC is being used in a manner inconsistent with the protections or the integrity and effectiveness of the Chromium Remedy, Honeywell shall act as soon as possible to cause such use to cease and, if there has been damage to the Chromium Remedy, to repair or replace it to original specifications or to a level of protection equivalent to the original Chromium Remedy;

(ii) Quarterly visual inspection monitoring of the Open Space AOC grade and slope to identify whether erosion has occurred or is occurring. Honeywell shall remediate any significant erosion.

(iii)Quarterly visual inspection monitoring to determine whether noticeable differential settlement or subsidence has occurred or is occurring in the Open Space AOC such that the integrity of the Chromium Remedy may be materially impaired. If evidence of differential settlement or subsidence is found, Honeywell shall propose further investigative measures. Honeywell shall remediate any differential settlement or subsidence that is beyond the degree of differential settlement/subsidence allowed for in the 100% Design and repair the cap and/or the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(iv)A baseline topographic survey at the completion of the Chromium Remedy and three additional surveys conducted at five-year intervals beginning five years after the conduct of the baseline survey. The topographic survey shall be of sufficient precision and accuracy to present the results as one-foot contours;

(v) Quarterly visual inspection monitoring to determine whether the Chromium Remedy in the Open Space AOC has been disturbed. Any evidence of the distinctive warning layer materials or any other cap materials as described in paragraph 65(a) at the surface is an indication that the cap has been disturbed. In such an event, Honeywell shall propose further investigative measures to evaluate whether the integrity of the cap has been compromised. In the event that the investigative measures show that the cap integrity has been compromised, Honeywell shall repair or replace the cap and the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vi) Quarterly visual inspection monitoring to ensure that burrowing animals are not materially impairing the integrity of the Chromium Remedy. If evidence of burrowing animals is found, Honeywell shall follow humane removal procedures and repair or replace the cap and

the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vii) Quarterly visual inspection monitoring of the vegetative cover in the Open Space AOC to ensure that vegetative cover is in conformance with the landscaping provisions of the 100% Design and the Redevelopment Plan and will not materially impair the integrity of the Chromium Remedy. Maintenance of the vegetative cover shall include, at a minimum, mowing to ensure that tree species cannot become established and removal of any other vegetation with the potential to damage the Chromium Remedy;

(viii)Quarterly groundwater monitoring to ensure that groundwater levels are maintained in accordance with the requirement to maintain an outward gradient from Study Area 7 and in accordance with the water level control plan developed pursuant to paragraph 69(e);

(ix) Monitoring of vented gases and the gas venting system to ensure proper operation of the system, to evaluate any degradation of the system, to assess the need for treatment of vented gases, either initial, subsequent, or further depending on whether treatment has been previously provided, and to detect any condition that might endanger public health or safety. Such monitoring shall be conducted on a monthly basis for at least one year and, if the readings are stable, such monitoring may be conducted thereafter on a quarterly basis; and

(x) Any additional monitoring as required by specific details added in the design phase of the Open Space AOC.

(b) **Procedures for Proposing Changes to the Long-Term Monitoring Plan.** Any Party may, from time to time, propose changes to the scope of the monitoring activities under the Long-Term Monitoring Plan. If the Parties agree, the Long-Monitoring Plan shall be so changed

subject to approval by NJDEP and by the Special Master, if his appointment has not terminated, or otherwise, by the Court. If the Parties are unable to reach agreement over alterations to the monitoring and the Special Master's appointment has not terminated under this Consent Decree, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation. In the event that the dispute arises after the Special Master's appointment has terminated, any Party may file a motion seeking a resolution of the dispute by the Court.

(c) **Contingency Plan**. As part of the Long-Term Monitoring Plan, Honeywell shall develop a contingency plan to ensure the integrity of the remediation in the event of any planned penetration of the cap or otherwise planned activity that compromises the cap or any unplanned event or accident that penetrates the cap or otherwise compromises the integrity of the Chromium Remedy. The contingency plan shall include, at a minimum, an annually updated plan to notify the relevant persons, including the Special Master, NJDEP, and the Parties, of (i) the event penetrating the cap, compromising the cap, or compromising the integrity of the Chromium Remedy; (ii) the general steps to be taken to identify the extent of the problem; and (iii) the standards for remedying the problem.

(d) **Routine Maintenance**. The title owner of the Open Space AOC shall conduct maintenance of the Open Space AOC features or facilities that are permissible under paragraphs 74(j) and 74(k). The maintenance workers shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy. The training shall include the identification and reporting of any uses or features that are not permissible in the Open Space AOC or that may jeopardize the integrity of the Chromium Remedy. Honeywell shall provide all training materials. The title owner of Open Space AOC shall annually provide to the other Parties and

the Special Master a report describing the training which has been provided to its maintenance workers. The title owner of the Open Space AOC shall also provide to the Parties and the Special Master notice of any violations of the restrictions relating to the Open Space AOC identified by its workers during routine maintenance.

(e) **Recordkeeping**. Honeywell shall maintain written logs or other records of those monitoring and remediation activities undertaken pursuant to the Long-Term Monitoring Plan. Such logs shall be provided to Riverkeeper on a quarterly basis.

79. **Monitoring and Reporting to Riverkeeper.** Riverkeeper shall be provided with all documents submitted to NJDEP and/or the Special Master with respect to the Chromium Remedy, including the documents identified in paragraph 86(c).

80. **Notice to Stakeholders.** All residents, regardless of whether they are owners or lessees, and all commercial tenants on Study Areas 6 and 7 are hereby deemed stakeholders. Honeywell shall ensure that all stakeholders shall be provided at the time of their purchase or lease with notice of the contamination, the remedial actions that have been undertaken or are planned, and the importance of reporting activities that may appear to jeopardize the integrity of the engineering controls. Notice shall be accomplished in the following manner:

(a) Bold or otherwise conspicuous language on the first page of the deed provided to all purchasers in the Residential Area;

(b) A summary notice of the Chromium Remedy which:

(i) Has been subject to review and comment by the Parties and approval by the Special Master; and

(ii) Provides a reference to public websites and libraries and/or the future equivalents thereof, where the following can be found:

(1) Zoning and other Jersey City maps showing the Open Space AOC; and

(2) Documents describing the contamination and the remediation, including:

(a) This Consent Decree;

(b) The Remedial Investigation Report and the Final Remedial Action Report,

(c) The annual reports on long-term monitoring and maintenance and repair activities as required by paragraph 78 and annual reports on changes to the Initial Development as required by paragraph 74(j)(xii); and

(d) The Long-Term Monitoring Plan.

(c) The public provision of the maps and documents referred to in paragraph 80(b)(ii) via websites and libraries and/or the future equivalents thereof; and

(d) Notices to lessees and commercial tenants in all lease documents.

81. **Annual Letter to Riverkeeper on Notice to Stakeholders.** Each year beginning one year after the issuance of the first notice in a deed or lease pursuant to paragraph 80, Honeywell shall provide a letter to the Riverkeeper documenting its compliance with paragraph 80.

82. **Future Notice to Stakeholders.** Honeywell shall ensure that all stakeholders are provided with notice, at least annually, of long-term monitoring activities and any additional remediation activities undertaken with respect to the Chromium Remedy. Such notice shall be accomplished by notices on websites or future equivalents thereof, including Jersey City websites, any websites created to provide information about the Chromium Remediation or redevelopment of the Redevelopment Area, and one or more of the following:

(a) Any community message board or other similar site used and/or maintained by stakeholders or the manager(s) of the Redevelopment Area;

(b) Mailings to all stakeholders; and

(c) Posters and flyers throughout the Redevelopment Area.

83. **Stakeholder Enforcement.** Any stakeholder shall have the right to enforce the remedial obligations of this Consent Decree in the Court, including post-implementation monitoring and maintenance obligations, and the terms of any deed notice or use restriction.

**I. Oversight and Enforcement by the Special Master and NJDEP**

84. **Federal Court Jurisdiction.** The Court shall retain jurisdiction for the purpose of overseeing and enforcing this Consent Decree and to review any issue or dispute which is not resolved through the oversight process described in Article III.I.

85. **Appointment and Jurisdiction of the Special Master.** The Chromium Remedy provided for in this Consent Decree is hereby referred to a Special Master pursuant to Rule 53 of the Federal Rules of Civil Procedure. The Special Master is appointed in the Consolidated Litigation for the purpose of overseeing and enforcing the Chromium Remedy, the first five years of long-term monitoring of the Chromium Remedy, financial assurances for the Chromium Remedy, and the Initial Development Period for each phase of development in the Open Space AOC. The Special Master is also appointed in the Consolidated Litigation for the limited purpose of ensuring that the scheduling and implementation of any non-chromium related remedy, any site preparation activities, and any site redevelopment activities do not undermine the integrity of, unreasonably interfere with, or unnecessarily delay the effectuation of the Chromium Remedy, the Study Area 7 remedies, and other remedies within his jurisdiction as of the date of entry of this Consent Decree. The Special Master shall have jurisdiction over all matters for which he is appointed.

86. **Oversight of the Chromium Remedy.**

(a) **NJDEP Authority**. Nothing in or pursuant to this Consent Decree shall limit NJDEP's full statutory and regulatory authority with respect to the Study Area 6 South site, including (i) permitting authority; (ii) authority to review and approve the Treatment Study reports, the Remedial Action Work Plan, the 100% Design, and final Remedial Action Report for the Chromium Remedy; and (iii) authority to issue a no further action letter.

(b) **Special Master Responsibilities**. The Special Master shall have the following responsibilities:

(i) Ensuring that Honeywell's implementation of the Chromium Remedy satisfies the requirements of this Consent Decree;

(ii) Ensuring that Honeywell's implementation of the Chromium Remedy conforms with federal, state, and local permit requirements;

(iii) Establishing a reasonable schedule for the implementation of the Chromium Remedy and monitoring conformance with it;

(iv) Reviewing monthly progress reports and conducting periodic meetings with the Parties to review the progress of the implementation of the Chromium Remedy. NJDEP shall be invited, but not required, to participate in these meetings and the decision as to whether to participate shall be left to NJDEP's sole discretion;

(v) Submitting bi-monthly progress reports to the Court pursuant to the schedule for the submission of such reports established in *ICO v. Honeywell*;

(vi) Overseeing the financial assurances established pursuant to paragraphs 91 through 100, and, until the expiration of his term pursuant to paragraph 90, overseeing the financial assurances established pursuant to paragraphs 101 through 112;

(vii) Coordinating review of the documents as provided in paragraphs 86(c) through 86(g);

(viii) Overseeing all development undertaken in the Open Space AOC during the Initial Development Period pursuant to paragraph 74(j)(iii); and

(ix) To the extent that, in matters within the jurisdiction of the Special Master as set forth herein, a dispute arises between the Parties with respect to implementation of the Chromium Remedy, issuing a recommendation to the Court with respect to the dispute.

(c) **Submission of Documents by Honeywell.** Honeywell shall submit the following documents to Riverkeeper, Jersey City, the Special Master, and NJDEP:

(i) An overall schedule with milestones for the design and implementation of the remedy ("Schedule") consistent with paragraph 54 above;

(ii) A Second Supplemental Remedial Investigation Report reporting the results of the field work conducted pursuant to paragraph 55;

(iii)A Chromium Impacted Soils Pilot Test Work Plan and Analytical Protocol for conduct of the treatment study pursuant to paragraph 56, unless such documents are agreed to by NJDEP and Riverkeeper before the entry of this Consent Decree;

(iv)An Initial Treatment Study Report for the Development AOC;

(v) A Final Treatment Study Monitoring Report;

(vi) The documents for Site 163 submitted pursuant to paragraphs 54(a)(iv), 54(a)(v), 61, and 62;

(vii) A report to evaluate the need for remediation of any potentially remaining contaminated shallow groundwater in the Development AOC after implementation of the Development AOC Soils Remedy and, based on such an evaluation, a proposal;

(viii) A report of the results of the sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site pursuant to paragraph 71 and, based on the results, a proposal for a remedy;

(ix) A plan for one round of monitoring to evaluate whether the L-Well Groundwater remains contained pursuant to paragraph 72;

(x) A proposal for a remedy of the L-Well Groundwater, in the event L-Well Groundwater monitoring indicates the contaminated groundwater is no longer contained, pursuant to paragraph 72;

(xi) A Remedial Action Work Plan;

(xii) A 50% Design Report (which may include the Development AOC Conceptual Design Plan as a component) as well as design drawings and specifications at the 50% level for other components of the Chromium Remedy (hereinafter the 50% Design);

(xiii) Design drawings and specifications at the 100% level (after selection of the contractor) (hereafter "100% Design");

(xiv) The data validation plan, including quality control and quality assurance protocols;

(xv) The site-wide master health and safety plan;

(xvi) The Long-Term Monitoring Plan;

(xvii) The final Remedial Action Report or final construction report (including as-built drawings and such other reports as may be prepared of the remedy as implemented);

(xviii) A program for post-treatment monitoring pursuant to paragraph 63, and, depending on such results, a proposal for further remedial actions;

(xix) A report reviewing measured groundwater levels for the groundwater remedy;

(xx) Documents required during the Initial Development Period pursuant to paragraphs 74(j)(vi), 74(j)(vii), and 74(j)(viii); and

(xxi) Other post-implementation monitoring reports as required by the Long-Term Monitoring Plan.

(d) **Initial Review of Documents by NJDEP.** The Parties and Special Master shall allow the period of time set forth below for NJDEP to conduct its review of a submission (hereinafter "NJDEP Review Period") before the document is subject to the Special Master review and approval process. During the NJDEP Review Period, any Party may submit comments to NJDEP. For the Second Supplemental Remedial Investigation Report, the Remedial Action Work Plan, the Initial Treatment Study, and the Final Treatment Study Monitoring Report, the NJDEP Review Period shall be 90 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. For any other documents identified in paragraph 86(c), the NJDEP Review Period shall be 30 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. The NJDEP review period shall be extended an additional 30 days for any document for which NJDEP provides the Parties and the Special Master with notice that its review will require an additional 30 days. At the conclusion of the NJDEP Review Period, the comment and review process provided for in paragraphs 86(e) and 86(f) shall commence. In the event that any document has been revised during the NJDEP Review Period, Honeywell shall resubmit the applicable document for purposes of the comment and review provided for in paragraphs 86(e) and 86(f).

(e) **Comment on Submitted Documents**. For each of the documents submitted by Honeywell pursuant to paragraph 86(c), and following conclusion of the NJDEP Review Period as described in paragraph 86(d), the Special Master shall establish a schedule for the submission

of comments and responses to comments. For each of the documents submitted, Riverkeeper, Jersey City, the Special Master, and NJDEP shall have the right to submit comments to Honeywell. Honeywell shall address all comments received and submit a revised document. The revised document shall be submitted by Honeywell to Riverkeeper, Jersey City, the Special Master, and NJDEP. The revised document shall be subject to review and approval pursuant to paragraph 86(f), unless the Parties agree both on the revised document and that further review and approval pursuant to paragraph 86(f) is unnecessary. In that event, the Parties shall inform the Special Master that review under paragraph 82(f) is unnecessary and Honeywell shall proceed to implement the revised document.

(f) **Review and Approval of the Submitted/Revised Document**

(i) **Scope of Review**. Subject to the limitations in paragraph 82(e), all documents submitted by Honeywell, pursuant to paragraph 86(c) and 86(e), shall be subject to review and approval by the Special Master in accordance with the following procedure. All such documents, except the Schedule and the 100% Design, shall be subject to the review and approval process and shall not require an order of the Court. The Schedule and 100% Design documents shall be subject to the review and approval process, but shall also require an order of the Court as provided in paragraph 86(g). A document shall be approved if the document (1) complies with this Consent Decree; (2) complies with the Remedial Action Work Plan for the Chromium Remedy; and (3) complies with the Schedule and 100% Design.

(ii) **Procedure**. Prior to making a decision on a document, the Special Master shall notify NJDEP of his intention to rule on the document or make a recommendation to the Court on the document. Such notice shall notify NJDEP that the Special Master will consider any comments NJDEP wishes to submit on the document if such comments are submitted within

the timeframe established by the Special Master in the schedule for comments pursuant to paragraph 86(e). NJDEP shall in its sole discretion determine whether to submit comments to the Special Master.

(iii) **Court Review**. If any Party objects to the Special Master's recommendation to the Court or approval of any document pursuant to this paragraph, that Party may seek further relief from the Court with respect to the document.

(g) **Schedule and 100% Design Documents**. As to the Schedule and the 100% Design documents, Honeywell shall have the responsibility, within 30 days of the Special Master's approval of each document, of (i) moving for entry of an order by the Court approving the document as approved by the Special Master; or (ii) filing objections with the Court to the Special Master's approval (and any recommendations contained therein) and moving for entry of the Schedule or 100% Design (including any such recommendations of the Special Master to which Honeywell agrees). Riverkeeper shall have the right in these proceedings to raise any objections they might have to the Schedule or 100% Design as approved by the Special Master or to the submission by Honeywell to the Court. NJDEP shall receive notice of any motion filed with respect to the Schedule or the 100% Design.

(h) **Flexibility in 50% and 100% Design Documents**. The Parties recognize that work conducted to implement the Chromium Remedy may be conducted by Honeywell contractors and that Honeywell may establish performance-based criteria or specifications for its contractors. As a result, the Parties recognize that the 50% Design and 100% Design documents for the Chromium Remedy may include performance-based standards, criteria, and specifications. These documents shall be sufficiently prescriptive to enable the Parties and the Special Master to evaluate their conformance with the Remedial Action Work Plan and this Consent Decree. The

Parties also recognize that the 100% Design will be completed after Honeywell has selected a contractor. The Parties further recognize that completing the 100% Design after the selection of the contractor(s) shall not make the 100% Design subject to any less stringent or more deferential review. Honeywell's commitment to the contractor(s) shall not be cause to limit review by the Parties and the Special Master.

(i) **Changes to the Schedule.** The Parties recognize that changes to individual line items in the Schedule will occur. To the extent that (i) the Parties and the Special Master agree that such changes do not have a material impact on satisfaction of the Schedule milestones established for items set forth in paragraph 54; and (ii) such changes do not require modifications to any necessary permits or authorizations for the Chromium Remedy, such changes may be made upon agreement of the Parties and the Special Master without further order of the Court.

87. **Retention of Professionals.** The Special Master may retain the services of professionals and/or other technical personnel, as reasonably needed, to fulfill his obligations under this Consent Decree, and for which he will be reimbursed pursuant to paragraph 89.

88. **Insurance for the Special Master.** The Special Master shall obtain insurance coverage relating to the performance of the Special Master's duties and responsibilities under this Consent Decree. Such coverage shall be similar to the Special Master's existing coverage in *ICO v. Honeywell*, procured pursuant to the Court's November 11, 2005 Stipulation and Order Regarding Special Master's Application to Procure Insurance Coverage, and as extended to the Consolidated Litigation by the Sediment Consent Order. The insurance coverage shall be sufficiently extended in duration and scope to cover all additional duties and responsibilities as set forth hereunder. Honeywell shall pay the premiums and other administrative costs of the Special Master's insurance.

89. **Reimbursement of Special Master Fees and Expenses.** The Special Master shall submit fee applications to the Court for approval of reasonable fees and expenses incurred in the oversight of matters referred to him pursuant to this Consent Decree. Any Party may raise with the Court objections to such fee applications. Upon approval of a fee application by the Court, the reimbursement of the Special Master's fees and expenses shall be made from the escrow fund previously established by Honeywell for the purpose of paying the Special Master's fees and expenses in *ICO v. Honeywell* pursuant to this Court's September 15, 2003 Order Setting Financial Assurances and extended to the Consolidated Litigation by the Sediment Consent Order.

90. **Expiration of Special Master's Appointment.** The Special Master's appointment under this Consent Decree shall expire after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy and the Initial Development Period for each phase of development has been concluded as provided in paragraph 74(j)(ii). However, solely to the extent that the Special Master is still supervising other portions of the Consolidated Litigation or *ICO v. Honeywell* after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy or the Initial Development Period for each phase of development as provided in paragraph 74(j)(ii), whichever is later, the Special Master shall continue to have jurisdiction under this Consent Decree until he has completed his specifically enumerated responsibilities under the Final Judgment in *ICO v. Honeywell*, the Sediment Consent Order, the Deep Groundwater Consent Order, the Study Area 6 North Consent Decree, and any other future orders, decrees, or judgments in *ICO v. Honeywell* and the Consolidated Litigation. Enumerated responsibilities under any order, decree, or judgment shall include only those tasks specifically assigned to the Special Master in the order, decree, or judgment. Enumerated responsibilities

shall not include any continued jurisdiction exercised over long-term monitoring beyond the initial period specified in the order, decree, or judgment. For example, the Special Master has jurisdiction over the first five years of long-term monitoring under the Sediment Consent Order. Oversight during these five years shall be an enumerated responsibility, but any continued oversight of long-term monitoring, pursuant to the extension of the Special Master's jurisdiction beyond the first five years, as provided in paragraph 60 of the Sediment Consent Order, shall not be an enumerated responsibility. Such extensions of jurisdiction shall be effective only so long as specific enumerated responsibilities in any order, decree, or judgment have not been fulfilled.

**J. Initial Financial Assurances**

91. **Chromium Remedy Letter of Credit.** Honeywell shall obtain a one-year, irrevocable letter of credit (the "Chromium Remedy Letter of Credit") to be automatically renewed annually in an amount equal to the "Remedial Costs Subject to Financial Assurance."

(a) Remedial Costs Subject to Financial Assurance shall mean:

(i) The costs of implementing the Chromium Remedy calculated using factors, including inflation and discount rates, determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process;

(ii) The costs of monitoring and maintenance activities for five years, as required by the Long-Term Monitoring Plan, calculated using factors including inflation and discount rates determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process; and

(iii) A contingency of 25% with respect to those costs listed in paragraphs 91(a)(i) and 91(a)(ii).

(b) The Chromium Remedy Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution, provided that in either case, the financial institution shall be acceptable to the Special Master.

92. **Procedures for Review of the Proposed Chromium Remedy Letter of Credit.** No later than December 31, 2008, Honeywell shall submit to Riverkeeper and the Special Master for their review the proposed (a) amount of the Chromium Remedy Letter of Credit; (b) form of the Chromium Remedy Letter of Credit; and (c) name of the institution that will issue the Chromium Remedy Letter of Credit. If Riverkeeper does not agree to the terms of the Chromium Remedy Letter of Credit, the Parties shall meet and confer in an effort to resolve their differences. If the Parties are unable to reach agreement over the terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the Chromium Remedy Letter of Credit.

93. **Automatic Renewal.** The Chromium Remedy Letter of Credit shall be automatically renewed annually unless (a) no later than 120 days prior to the anniversary of the Chromium Remedy Letter of Credit issue date, the issuer provides notice of nonrenewal or (b) Honeywell seeks a reduction in the Chromium Remedy Letter of Credit, pursuant to paragraph 94, to correspond to the reduced estimate of Remedial Costs Subject to Financial Assurances. If the issuer provides notice of nonrenewal, Honeywell shall obtain a replacement irrevocable Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit. If Honeywell is not otherwise in default as provided in Article III.J, the Special Master shall direct the cancellation of the prior Chromium Remedy

Letter of Credit within 91 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit. In the event that the Special Master is entitled to draw upon a Chromium Remedy Letter of Credit because there are two Chromium Remedy Letters of Credit currently in place, the Special Master shall not draw an aggregate amount in excess of the highest valued Chromium Remedy Letter of Credit. Upon Honeywell's request, the Special Master may, at his option, decide not to require overlapping letters of credit in any year based on Honeywell's financial strength in that year, provided that Honeywell has submitted all necessary information so that the Special Master can make his determination at least 150 days prior to the expiration of the Chromium Remedy Letter of Credit.

94. **Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit.** Honeywell shall have the right annually to seek a reduction in the Chromium Remedy Letter of Credit. At the time of seeking such reduction, Honeywell shall submit to the Riverkeeper and the Special Master an estimate of the remaining Remedial Costs Subject to Financial Assurance, including the contingency as described in paragraph 91(a)(iii), and shall seek adjustment of the Chromium Remedy Letter of Credit so that the total estimated amount of remaining Remedial Costs Subject to Financial Assurance are covered by the Chromium Remedy Letter of Credit. However, the adjustment shall not result in reducing the Chromium Remedy Letter of Credit to an amount below the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), plus a contingency of 25% of the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), and shall not result in reducing the Chromium Remedy Letter of Credit to an amount less than $20,000,000 as expressed in 2008 dollars unless long-term financial assurances are in place pursuant to Article III.K. Before making any request to reduce the amount or modify the terms of the Chromium Remedy Letter of Credit, Honeywell shall first confer with the Riverkeeper and

in an effort to reach agreement on the modified amount or terms of the Chromium Remedy Letter of Credit. If the Parties are unable to reach agreement over the modified amount or terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall resolve the dispute. Any Party shall have the right to seek review by the Court of the Special Master's decision regarding the modified amount or terms of the Chromium Remedy Letter of Credit. Upon agreement on the amount of the reduction or modified terms of the Chromium Remedy Letter of Credit (or upon order of the Court directing that the Chromium Remedy Letter of Credit be reduced to an identified amount or otherwise modified), Honeywell shall obtain a replacement Chromium Remedy Letter of Credit in such amount and with such terms. If Honeywell is not otherwise in default as provided in Article III.J and the issuer of the primary Chromium Remedy Letter of Credit has not provided notice of non-renewal, within 30 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit, the Special Master shall direct the cancellation of the prior Chromium Remedy Letter of Credit.

95. **Bankruptcy Protection**. Neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy. The Chromium Remedy Letter of Credit shall contain the language necessary to assure that neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

96. **Exclusive Court Jurisdiction**. The Chromium Remedy Letter of Credit shall recite that the issuer submits to the exclusive jurisdiction of this Court for any and all disputes arising under the Letter of Credit.

97. **Application of New York Law.** The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Chromium Remedy Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

98. **Procedures upon Honeywell's Material Default of Its Obligations.** During the period in which the Special Master has jurisdiction pursuant to paragraph 85, the Chromium Remedy Letter of Credit shall be payable to the Special Master and shall not, prior to its expiration date, be revoked or terminated except consistent with this Consent Decree and with the consent of the Special Master and approval by the Court. The Special Master's ability to draw upon the Chromium Remedy Letter of Credit shall not be limited by any agreement between Honeywell and the issuer. The Special Master may, without further order or notice to this Court, draw upon the Chromium Remedy Letter of Credit upon the occurrence of default by Honeywell, which shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 93 to deliver a replacement Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 15 days after written notice to Honeywell thereof and either (i) Honeywell, in the opinion of the Special Master without further input from the Parties, shall have failed to cure the breach; (ii) during the 15-day period, the Court has not entered an order to prevent the Special Master from

drawing on the Chromium Remedy Letter of Credit; or (iii) the Court or the Special Master has not granted Honeywell additional time to cure the breach;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if involuntary filing has not been dismissed within 60 days; the appointment of a custodian, receiver, liquidator, or trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 98(c), and the failure of Honeywell to provide assurance to the Special Master, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

99. **Placement of Proceeds in Court Registry Investment System Account**. In the event that the Special Master draws upon the Chromium Remedy Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Chromium Remedy Letter of Credit which represent the remaining estimated Chromium Remedy costs under paragraphs 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), in an account with the Court Registry Investment System in accordance with Local Civil Rule 67.1 and not expend the proceeds of the Letter of Credit without further order of this Court. The

Special Master shall place all additional proceeds of the Chromium Remedy Letter of Credit in a trust fund pursuant to paragraph 103(b)(v).

100. **Termination of Chromium Remedy Letter of Credit**. The Chromium Remedy Letter of Credit may be withdrawn in its entirety upon the satisfaction of all of the following:

(a) The implementation of the Chromium Remedy; and

(b) Establishment of long-term financial assurance pursuant to Article III.K.

**K. Long-Term Financial Assurances**

101. **Long-Term Financial Assurances.** Honeywell shall fund long-term financial assurances to ensure that the activities set forth in paragraph 102(a) are carried out regardless of whether Honeywell is financially able to carry out such activities in perpetuity.

102. **Costs Subject to Long-Term Financial Assurances.**

(a) Long-term financial assurances shall provide enough funds to cover the costs of the following activities:

(i) Perpetual monitoring and maintenance of the Chromium Remedy, including installation, operation and monitoring of any above-cap-grade gas collection and/or treatment system as may be necessary, but such system is not part of the 100% Design;

(ii) Perpetual operation of the shallow groundwater remedies pursuant to paragraphs 69, 70, and 71;

(iii) Perpetual repair of the cap;

(iv) Perpetual replacement of the cap on a 75-year replacement interval; and

(v) The perpetual administration of the trust fund regardless of whether such trust fund is selected by Honeywell pursuant to paragraph 103(a) or is established from the Long-Term Letter of Credit pursuant to paragraphs 103(b)(ii), 103(b)(v), or 109.

(b) The costs that shall be subject to financial assurances is an amount that will provide the full payment for each of the activities set forth in paragraphs 102(a)(i) through 102(a)(v) plus a 25% contingency when the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to be performed. The costs subject to financial assurances are forward looking because they state an amount valued at the time the funds are needed. As such, they shall be stated in contemporary time as the present value (calculated on the basis of a discount rate of 4.75%) of the estimated future costs of the activities specified in paragraphs 102(a)(i) through 102(a)(v), plus a 25% contingency on those costs.

103. **Long-Term Financial Assurance Mechanisms.** Honeywell shall provide long-term financial assurances in the amount of the costs subject to long-term financial assurances in the form of a trust fund, a letter of credit, or some combination of the two. The selected mechanism(s) shall satisfy the following requirements:

(a) **Trust Fund.** In the event that Honeywell selects a trust fund, Honeywell shall create a trust fund such that it can provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(i) The trust fund shall be at arm's length from Honeywell and shall not be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The trust fund agreement shall contain the language necessary to assure that neither the trust fund nor the earnings of the trust fund shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The trust fund shall be managed by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution managing the

trust fund declares bankruptcy, the Court shall withdraw the funds and appoint another financial institution meeting the requirements of this paragraph to manage the trust.

(iii) No more frequently than once per year, Honeywell may apply to the Court for an order directing the trust manager to reimburse Honeywell for any costs that it has incurred to carry out the activities set forth in paragraphs 102(a)(i) through 102(a)(iv).

(b) **Long-Term Letter of Credit**. In the event that Honeywell selects a letter of credit, Honeywell shall obtain a one-year irrevocable letter of credit (the "Long-Term Letter of Credit") to be automatically renewed annually in an amount that provides sufficient funds such that a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a), could be created. The Long-Term Letter of Credit-funded trust, plus any trust fund established under paragraph 103(a), shall provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The amount of any Long-Term Letter of Credit shall therefore be adjusted periodically as the cap replacement interval is approached because, for example, the money needed in the 10th year to fund a trust that can provide for replacement of the cap in the 75th year is much less than the money that would be needed in the 40th year. Such periodic adjustments shall be proposed and approved by the Court in conjunction with the adjustments under paragraph 106.

(i) Neither the Long-Term Letter of Credit nor the proceeds of the Long-Term Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The Long-Term Letter of Credit shall contain the language necessary to assure that neither the Long-Term Letter of

Credit nor the proceeds of the Long-Term Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The Long-Term Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution issuing the Long-Term Letter of Credit declares bankruptcy, the Court shall authorize the drawing of funds from the Long-Term Letter of Credit and shall deposit those funds in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(iii) The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits) as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Long-Term Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

(iv) The Long-Term Letter of Credit shall be automatically renewed annually, unless, no later than 120 days prior to the anniversary of the Long-Term Letter of Credit issue date, the issuer provides notice of non-renewal. If the issuer provides notice of non-renewal, Honeywell shall obtain a replacement irrevocable Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit. If Honeywell is not otherwise in default as provided in this Article, the Court shall direct the cancellation of the prior Long-Term Letter of Credit within 91 days after delivery to the Court of any replacement of a Long-Term Letter of Credit. In the event that the Court is entitled to draw upon a Long-Term Letter of Credit when there are two Letters of Credit currently in place, the Court shall not draw an aggregate amount in excess of the highest valued Long-Term Letter of Credit.

(v) Prior to the expiration of the Special Master's appointment pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Special Master. During the time the Long-Term Letter of Credit is payable to the Special Master, the Special Master may draw on the Long-Term Letter of Credit as provided in paragraph 98. In the event that the Special Master draws upon the Long-Term Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a). After the Special Master's appointment expires pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Court and, in the event that the Court draws on the Long-Term Letter of Credit, the Court shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(vi) Whether the Long-Term Letter of Credit is payable to the Special Master or the Court, it shall not, prior to its expiration date, be revoked or terminated by Honeywell except consistent with this Consent Decree and with the approval of the Court. The ability of the Special Master or the Court to draw upon the Long-Term Letter of Credit shall not be limited by any agreement between Honeywell and the issuer.

(vii) In the event that the Long-Term Letter of Credit is drawn upon and invested pursuant to paragraph 103(b)(ii), 103(b)(v), or 109 and Honeywell has also selected a trust fund pursuant to paragraph 103(a), resulting in the existence of two trust funds, the two trust funds shall be managed so as to ensure that the combined amount of the trust funds is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(c) **Combination**. Honeywell may use some combination of a trust fund and a letter of credit to achieve the requirements of this paragraph. However, if a combination is used, Honeywell shall ensure that the combined amount of financial assurances is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The trust fund and the letter of credit shall otherwise satisfy all the requirements of paragraphs 103(a) and 103(b).

104. **Procedures for Review of the Proposed Long-Term Financial Assurances**. No later than June 1, 2009, Honeywell shall submit to Riverkeeper and the Special Master, for their review (a) the amount of the proposed long-term financial assurances; (b) the form(s) of the proposed long-term financial assurance mechanisms; and (c) the name(s) of the institution proposed to manage or issue the long-term financial assurances. If Riverkeeper agrees to the terms of the proposed long-term financial assurances, within 60 days of such agreement, Honeywell shall create a trust fund and/or secure a Long-Term Letter of Credit on those terms. If the Parties are unable to reach agreement over the terms of the long-term financial assurances, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the financial assurances.

105. **Temporary Maintenance of Chromium Remedy Letter of Credit**. Until the long-term financial assurances have been put into place, Honeywell shall maintain the Chromium Remedy Letter of Credit required by paragraph 91 in an amount equal to at least $20,000,000 in 2008 dollars. In the event of any default by Honeywell pursuant to paragraph 98 while the Chromium Remedy Letter of Credit is in place, the provisions of paragraph 103(b)(v) for the placement of the proceeds that exceed the remaining estimated Chromium Remedy costs under

paragraph 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), shall apply.

106. **Adjustment of Amount Held in Long-Term Financial Assurances**. Every five years as marked from the establishment of the first long-term financial assurances pursuant to paragraph 103, the Parties shall report to the Court whether the long-term financial assurances are adequately funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. At such time as the Parties report to the Court, any Party may seek an adjustment in the amount of the long-term financial assurances. The Party seeking an adjustment must demonstrate that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Such demonstration shall reflect the actual costs of implementing the remedy and/or any replacement of the remedy, once such actual costs are available. The demonstration shall also reflect the costs of work completed to date and the actual lifetime of the cap, once the cap has been replaced or has passed a replacement interval without requiring replacement. The demonstration shall further reflect the actual performance of the fund and its ability to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Any demonstration shall be forward looking and shall be based upon estimates of what the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to cost at the time they must be performed and the amount of funding projected to be available to undertake such activities at the time they must be performed. If, after reviewing the submission(s) received from the Parties, the Court determines that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to

long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary, the Court shall order an adjustment in the amount held in the long-term financial assurances to overcome the shortage or overage. In the event that the Court determines that the long-term financial assurances are under-funded, it shall order Honeywell to increase the amount held in the long-term financial assurances. In the event that the Court determines that any trust fund established pursuant to paragraph 103(a) is over-funded, the Court shall issue an order directing the trust manager to pay the overage to Honeywell. In the event that the Court determines that the Long-Term Letter of Credit is over-funded, the Court shall issue an order permitting Honeywell to reduce the amount covered during the next annual renewal of the Long-Term Letter of Credit pursuant to paragraph 103(b)(iv). Any adjustment to the amount of the Long-Term Letter of Credit pursuant to this paragraph shall be in addition to any adjustment of the amount of the Long-Term Letter of Credit required pursuant to paragraph 103(b).

107. **Exclusive Court Jurisdiction**. The trust fund agreement and/or the Long-Term Letter of Credit shall recite that the trust fund manager and/or issuer of the Long-Term Letter of Credit submit to the exclusive jurisdiction of this Court for any and all disputes arising under the trust fund or the Long-Term Letter of Credit. The requirements of this paragraph shall apply whether the trust fund is established pursuant to paragraph 103(a), 103(b)(ii), 103(b)(v), or 109.

108. **Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired.** Upon the occurrence of default by Honeywell, after the Special Master's appointment has expired, Riverkeeper may move the Court on an expedited basis for an order to withdraw funds from the trust fund or to draw on the Long-Term Letter of Credit. Default shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 103(b)(iv) to deliver a replacement Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 30 days after written notice by Riverkeeper to Honeywell of the alleged material failure, unless Honeywell cures the alleged breach within the 30-day notice period or such longer period as the Parties may agree to or the Court may order;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if the involuntary filing is not dismissed within 60 days; the appointment of a custodian, receiver, liquidator, trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 108(c), if Honeywell fails to provide assurance to Riverkeeper, and the Court, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

109. **Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default.** If the Court grants any motion by Riverkeeper or pursuant to paragraph 108 to draw on the Long-Term Letter of Credit, the sum approved by the Court's order granting the motion shall be

paid from the Long-Term Letter of Credit into a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

110. **Use of the Trust Fund in the Event of Honeywell's Default.** In the event of Honeywell's default, as defined in paragraphs 108(a) through 108(d), the money in the trust fund established pursuant to paragraph 103(a) shall be available to meet the obligations of paragraph 102(a), as well as for payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

111. **Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109.** In the event that a trust fund is established pursuant to paragraph 99, 103(b)(ii), 103(b)(v), or 109, the money in the trust fund shall be available to meet the obligations of paragraph 102(a), as well as for the payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

112. **Termination of the Long-Term Financial Assurances.** Honeywell's obligations under Article III.K shall be terminated and the long-term financial assurance mechanisms shall be terminated when the Court finds that no hexavalent or total chromium contamination remains in the Open Space AOC or on the Site, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive

standards for Unrestricted Use in place at the time, whichever is more restrictive. Upon determining that long-term financial assurances may be terminated, the Court shall order that any Long-Term Letter of Credit may be withdrawn in its entirety and any trust fund may be terminated. In conjunction with its order terminating any trust fund, the Court in its discretion shall designate a recipient(s) of any remaining trust funds.

## ARTICLE IV: TERMINATION

113. **Termination of this Consent Decree**. This Consent Decree shall terminate upon the withdrawal of any Party as provided for in this paragraph. Any Party may elect to withdraw from this Consent Decree due to the occurrence of one or more of the following events, provided that such Party provides written notice of withdrawal to the other Parties pursuant to paragraph 118:

(a) The Court fails to enter this Consent Decree or this Consent Decree is determined to be invalid on appeal; or

(b) NJDEP takes one of the following actions with respect to the Remedial Action Work Plan:

(i) Rejects or fails to approve the Remedial Action Work Plan for the Chromium Remedy within 180 days of submission of the plan;

(ii) Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in more than a 50% increase in the estimated costs of the Chromium Remedy as set forth in Article III; or

(iii)Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in a substantial reduction of the protection of human health and/or the environment.

114. **Procedures for Withdrawal and Termination.** Any Party electing to withdraw pursuant to paragraph 113 and thereby terminate this Consent Decree shall provide written notice of such withdrawal and termination to all other Parties within 30 days of the occurrence giving rise to the decision to withdraw. If any Party objects to termination of the Consent Decree, or believes that the conditions set forth in paragraph 113 have not been met, such objecting Party may move the Court for an expedited hearing on the issue of whether the conditions for termination have been effectuated.

115. **Good-Faith Obligation to Avoid Termination.** The Parties agree that they will each endeavor to fulfill the terms of this Consent Decree, that they will work diligently and in good faith to meet their obligations hereunder, and that they will promptly and timely take all reasonable steps to give effect to this Consent Decree and to avoid termination under paragraph 113.

116. **Effect of Termination.** If this Consent Decree is terminated pursuant to paragraph 113, the Consent Decree shall no longer be binding on the Parties and shall be of no further effect. In the event that this Consent Decree is terminated by one or more Parties pursuant to paragraph 113, each Party to this Consent Decree reserves all of its rights, claims, and defenses (both legal and factual) against the other Parties with respect to the matters at issue in the Consolidated Litigation and each Party remains free to pursue such rights, claims, and defenses.

## ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC

117. **Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC.** The transfer of title of Study Area 6 South and Study Area 7 properties to Bayfront Redevelopment LLC pursuant to the Jersey City/Honeywell Consent Order and any subsequent transfers shall not impede Honeywell's obligations to (a) complete the remediation of

Study Area 7 and implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or (b) complete the Chromium Remedy and conduct long-term monitoring and fulfill its other obligations set forth in this Consent Decree. Such transfers of Study Areas 6 South and Study Area 7 shall not include a transfer of Honeywell's obligations to implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or a transfer of Honeywell's obligations under this Consent Decree, but shall include a right of access or any other right required by Honeywell to complete the remediation. Any subsequent transfer of Study Area 6 South or Study Area 7 from Bayfront Redevelopment LLC to a redeveloper or other party shall provide all necessary agreements to allow Honeywell all necessary access to Study Area 6 South and Study Area 7 for purposes of completing Honeywell's obligations with respect to Study Area 6 South under this Consent Decree and completing the Study Area 7 remediation and implementing the Final Judgment and subsequent orders in *ICO v. Honeywell*.

## ARTICLE VI: NOTICE

118. **Notice**. Any and all notices given in connection with this Consent Decree shall be deemed adequately given only if in writing and addressed to the Party for whom such notices are intended at the addresses set forth in this paragraph. All notices shall be sent by Federal Express or other nationally recognized overnight messenger service or by first-class registered or certified mail, postage prepaid, return receipt requested. A written notice shall be deemed to have been given to the recipient party on the earlier of (a) the date it shall be delivered to the address set forth in this paragraph; (b) the date delivery shall have been refused at the address set forth in this paragraph; or (c) with respect to notices sent by mail, the date as of which the postal service shall have indicated such notice to be undeliverable at the address set forth in this paragraph.

Any and all notices referred to in this Consent Decree, or which any Party desires to give to the other, shall be addressed as follows:

If to Honeywell and/or
Bayfront Redevelopment LLC :

Tom Byrne, Esq.
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-2775

With copies to:

John Morris
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-4003

If to Jersey City:

William Matsikoudis
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NJ 07305
(201) 547-4667

If to Riverkeeper:

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th St., N.W.
Washington, DC 20005-4632
(202) 682-2100

Any party may change its designated recipients or addresses for notice in this paragraph by providing written notice of such change to all other Parties.

## ARTICLE VII: RIVERKEEPER'S ATTORNEYS' FEES

119. **Payment of Past Fees and Expenses.** Within 30 days of the entry of this Consent Decree, Honeywell shall pay Terris, Pravlik & Millian, LLP the sum of $813,000.00 which represents the following:

(a) A compromise of the attorneys' fees incurred by Riverkeeper in the litigation of Study Area 6 South portion of *Riverkeeper v. Honeywell* through August 31, 2008; and

(b) $353,746.67 in out-of-pocket expenses representing a portion of the expenses incurred by Riverkeeper in *Riverkeeper v. Honeywell* from the inception of the litigation after deducting the expenses paid pursuant to the Sediment Consent Order, the Deep Groundwater Consent Order, and the Study Area 6 North Consent Decree.

(c) Payment of the sum of $813,000.00 shall be in full satisfaction of all obligations, duties, and responsibilities of Honeywell with respect to the $879,317.92 in fees and expenses that Riverkeeper claimed with regard to the above described fees and expenses.

120. **Future Fees and Expenses.** Honeywell shall reimburse Riverkeeper's attorneys for reasonable fees and expenses incurred: (a) in negotiating this Consent Decree after August 31, 2008; (b) in the monitoring and enforcement of this Consent Decree; and (c) in participation in the Special Master process established pursuant to this Consent Decree. Honeywell shall also reimburse Riverkeeper for reasonable attorneys' fees and expenses for Riverkeeper's review of and participation in the Long-Term Monitoring Plan and monitoring and enforcement of this Consent Decree following the term of the Special Master. In the event that any dispute arises between the Parties under this Consent Decree that must be resolved by the Court, Riverkeeper shall be entitled to recover its attorneys' fees and expenses for litigation of the dispute to the extent allowed by federal law. Riverkeeper and Honeywell shall use the same informal procedure for attempting to settle fees issues as has been used for post-judgment monitoring fees in *ICO v. Honeywell*. In the event that Riverkeeper and Honeywell are unable to reach a settlement on fees, Riverkeeper shall apply to the Court for an award of attorneys' fees and expenses. If Honeywell objects to only a portion of the Riverkeeper's statement of attorneys' fees and expenses, Honeywell shall pay the undisputed portion within 60 days of Riverkeeper's submittal of the statement to Honeywell. The Court shall resolve any objections to

Riverkeeper's statement of attorneys' fees and expenses and shall enter an appropriate Order. In the event of Honeywell's default, Riverkeeper may seek attorneys' fees from any trust fund or court registry funds established pursuant to the financial assurances provisions of this Consent Decree.

## ARTICLE VIII: MISCELLANEOUS PROVISIONS

121. **Force Majeure.** Force Majeure, for the purposes of this Consent Decree, is defined as an event arising from causes beyond the control of any Party or Parties (or their agents, contractors, subcontractors, representatives, or assigns) which could not have been overcome by reasonable diligence and which delays or prevents the performance of any obligation under this Consent Decree. Examples of events which may constitute force majeure include the refusal of any federal or state governmental authority to grant a permit or authorization necessary for the completion of actions required by this Consent Decree, floods, hurricanes, tornadoes, and other extraordinary weather events, earthquakes and other natural disasters, terrorist attacks, war, and other national emergencies. Examples of events that are not force majeure events include normal inclement weather, increased costs or expense, the failure to timely and fully apply for a permit or authorization necessary for the completion of actions required by this Consent Decree, or financial difficulty of any Party. The Party claiming force majeure shall bear the burden of showing an event was a force majeure event.

122. **Bayfront Redevelopment LLC as a Party.** As a signatory to this Consent Decree, Bayfront Redevelopment LLC subjects itself to the Court's jurisdiction for the purpose of enforcing this Consent Decree and agrees to be bound by this Consent Decree. This Consent Decree shall be fully enforceable against Bayfront Redevelopment LLC.

123. **Successors and Assigns.** This Consent Decree shall be binding upon and shall inure to the benefit of the successors, assigns, heirs, corporate parents, subsidiaries, and affiliates of each Party. No assignment or delegation of the obligations hereunder shall release the assigning Party from its obligations under this Consent Decree.

124. **Successors to Hackensack Riverkeeper, Inc.** In the event that Hackensack Riverkeeper, Inc. disbands or otherwise ceases operations, it shall assign its rights under this Consent Decree to another qualified nonprofit organization. A nonprofit organization shall be qualified for assignment under this Consent Decree if it is a charitable organization under Section 501(c)(3) of the Internal Revenue Code or its substantial equivalent and has an established record of working to enhance or preserve the ecology, natural habitat, or environment. Any such assignment shall be subject to approval by the Court and Honeywell shall have the right to object to any proposed assignment. Any successor organization shall have the duty to assign its rights under this Consent Decree to another qualified nonprofit organization in the event that the successor disbands or otherwise ceases operations. In the event that a successor is not appointed at any given time, the New Jersey Attorney General or equivalent officer shall appoint a successor subject to approval by the Court and objection by Honeywell.

125. **Reservation of Rights and Claims.** Except as set forth expressly herein, this Consent Decree does not affect in any way any of the Parties' claims or defenses against third parties who have not signed the Consent Decree.

126. **Governing Law and Continuing Jurisdiction.** The Court shall retain jurisdiction over the matters addressed in this Consent Decree for purposes of enabling the Parties to apply to the Court for any further order as may be necessary to construe, carry out, or enforce the terms of this Consent Decree. This Consent Decree shall be interpreted and enforced under the laws of

the United States and the State of New Jersey by the United States District Court for the District of New Jersey.

127. **Construction.** Questions regarding the interpretation of this Consent Decree shall not be resolved against any Party on the ground that this Consent Decree has been drafted by that Party. This Consent Decree is the result of review, negotiation, and compromise by each Party.

128. **Authority to Enter into Agreement.** The undersigned representative for each Party represents, certifies, and warrants that he or she is duly authorized by the Party whom he or she represents to enter into the terms of this Consent Decree and bind such Party legally to this Consent Decree.

129. **Measures to Effectuate This Consent Decree.** Jersey City shall take all appropriate steps to ensure that commitments it has agreed to with regard to the Open Space AOC have been duly considered, ratified, and approved. Such steps include consideration of such commitments and an effectuating ordinance at a meeting of the City Council, open to the public, at which members of the public have the opportunity to comment on all aspects of the commitments made by Jersey City..

130. **Modifications.** This Consent Decree may be modified by mutual agreement of the Parties but such agreement must be in writing, duly and properly signed by all Parties, and shall be submitted to the Court for approval.

131. **Severability.** Each of the provisions in paragraph 74 of this Consent Decree shall be deemed severable and, in the event that one or more of such provisions is deemed invalid or unenforceable, it shall not affect the validity or enforceability of the other provisions of the Consent Decree.

132. **Signatures.** This Consent Decree may be signed simultaneously or in counterparts by the respective signatories, which shall be as fully valid and binding as if a single document was signed by all of the signatories. This Consent Decree may be signed electronically by any or all signatories, and such electronic signature shall be as fully valid and binding as a hand-written signature.

Consented to and approved for entry:

*s/Aurelio Vincitore*

William Matsikoudis
Aurelio Vincitore
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NY 07305
(201) 547-4667

*Counsel for the City of Jersey City*

*s/ David Sheehan*

David Sheehan
Baker Hostetler
45 Rockefeller Plaza
11th Floor
New York, NY 10111
(212) 589-4200

Michael D. Daneker
Arnold & Porter LLP
555 12th Street N.W.
Washington, DC 20004
(202) 942-5000

*Counsel for Honeywell International Inc. and Bayfront Redevelopment LLC*

*s/ Edward Lloyd*

Edward Lloyd
Columbia Law School
435 West 116th Street, Room 831
New York, NY 10027
(212) 854-4376

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th Street N.W.
Washington, DC 20005-4632
(202) 682-2100

*Counsel for the Hackensack Riverkeeper, William Sheehan, Reverend Winston Clarke, and Lawrence Baker*

APPROVED AND ENTERED as an Order of this Court this ___ day of _____, 2012.

Hon. Dennis M. Cavanaugh
United States District Judge

## EXHIBITS

**Exhibit A:** Remedial AOC's and Remedial Approach Map

**Exhibit B:** NJDEP Chromium Policy

**Exhibit C:** Conservation Restriction

**Exhibit D:** Deed Notice

**Exhibit E:** Additional Boring Locations

# Deed Notice

*Dated: _____, 2017*

**BAYFRONT REDEVELOPMENT LLC**

Grantor(s).

*Record and return to:*

**Waters, McPherson, McNeill, P.C.**
**P.O. Box 1560**
**300 Lighting Way**
**Secaucus, New Jersey 07096-1560**

**ATTN: _____, Esq**

**DRAFT DEED NOTICE**

IN ACCORDANCE WITH N.J.S.A. 58:10B-13, THIS DOCUMENT IS TO BE RECORDED IN THE SAME MANNER AS ARE DEEDS AND OTHER INTERESTS IN REAL PROPERTY.

Prepared by: _____
[Signature]

_____
[Bayfront Redevelopment LLC]

Recorded by:

_____
[Signature, Officer of County Recording Office]

_____
[Print name below signature]

# DEED NOTICE CONCERNING CONTROLS INSTALLED FOR CHROMIUM CONTAMINATION UNDERLYING THE PROPERTY

This Deed Notice is made as of the __ day of _____, 2017, by ***Bayfront Redevelopment LLC, whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950***. "Owner" shall mean Bayfront Redevelopment LLC together with its successors and assigns, including all successors in interest in the Property which is the subject of this Deed Notice as described fully below. The Property (also referenced herein as the "Restricted Area(s)") shall consist of those lands particularly described by metes and bounds in Exhibit A-2 attached.

1. THE PROPERTY. Bayfront Redevelopment LLC is the current owner in fee simple of certain real property designated as a portion of ***Block 24601, Lot 1 and Block 21901 Lots 8 and 10 on the tax map of the City of Jersey City, Hudson County, New Jersey***[1]; the New Jersey Department of Environmental Protection Program Interest Numbers for the contaminated site which includes this property are ***Hudson County Chromate Site No. 073 Program Interest ("PI") No. G000000927 and Hudson County Chromate Site No. 115 PI No. G000002548*** (NJDEP PI# for non-chromium-related contaminants at the Property is #745719). The Property is located between the Hackensack

[1] All references to Block 24601 Lot 1 and Block 21901 Lots 8 and 10 in this Deed Notice shall mean those applicable portions of Block 24601 Lot 1 and applicable portions of Block 21901 Lots 8 and 10 as shown in the metes and bounds description, regardless of whether the word "portion(s)" is specifically called out or not.

River bulkhead and the western hydraulic barrier walls installed within Study Areas 6 South and 7 as shown on Exhibit B-1, attached hereto. A portion of the Property (Tract 1) is part of the site referred to as Study Area 7 (Site 115) and the subject of an Administrative Consent Order (ACO) between Honeywell International Inc. ("Honeywell") and the Department dated June 17, 1993, and a Court-Ordered Remedy pursuant to the U.S. District Court for the District of New Jersey ("Court") Final Judgment in *Interfaith Community Organization v. Honeywell International Inc*., Case No. 95-2097, entered on June 30, 2003. The second portion of the Property (Tract 2) is subject to the ACO and to litigation captioned *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J. Civ. No. 05-5955, and *Jersey City Incinerator Authority v. Honeywell International Inc.*, D.N.J. Civ. No. 05-5993. Study Area 7 was previously remediated by Honeywell and received a No Further Action/Covenant Not to Sue letter, dated December 23, 2010, which did not include Tract 1. Tract 2 of the Property is part of the site referred to as Study Area 6 South (Site 073) for which Honeywell recently completed the Chromium Remedy pursuant to the First Amended Consent Decree Regarding the Remediation and Redevelopment of Study Area 6 South ("Consent Decree") which is attached hereto as Appendix I and is entered as an order of the Court in the following consolidated actions *JCMUA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-05955; *JCIA v. Honeywell International, Inc.,* D.N.J., Civ. No. 05-5993; and *Hackensack Riverkeeper, Inc. v. Honeywell International, Inc.,* D.N.J., Civ. No. 06-22 (consolidated under Civ. No. 95-2097). The Consent Decree restricts transfer, use, and development of the Property. To the extent that there is any conflict or inconsistency between the terms of this Deed Notice and the terms of the Consent Decree, the Consent Decree shall govern.

2. REMEDIATION.

i. The Department's Bureau of State Case Management (BCM) is the entity within the Department that is responsible for the chromium oversight of the remediation of SA-6 South and SA-7. The matter for SA-6 South was Hudson County Chromate Site No. 073 Program Interest (PI) No. G000000927. The matter for SA-7 was Hudson County Chromate Site No. 115 PI No. G000002548. The Department has approved this Deed Notice as an institutional control for the Property, which is part of the remediation of the Property.

ii. N.J.A.C. 7:26-C-7 requires the Owner, among other persons, including the responsible party Honeywell International Inc. ("Honeywell"), to obtain a soil remedial action permit for the soil remedial action at the Property. That permit will contain the monitoring, maintenance and biennial certification requirements that apply to the Property.

3. SOIL AND GROUNDWATER CONTAMINATION. Honeywell, a corporation of the State of Delaware, licensed to do business in the State of New Jersey whose post office address is 115 Tabor Road, Morris Plains, New Jersey 07950, has remediated SA-6 South and SA-7 to address chromium-related soil and shallow groundwater contamination, except for the Property and certain other deed noticed areas where engineering controls were implemented.

For SA-6 South, the Remedial Action Work Plan ("RAWP") was approved by the Department on March 24, 2009 for Hudson County Chromate Site Nos. 073, 124, 125, 134, and 140, which included portions of the Property. Remedial actions were further approved pursuant to the Consent Decree. Under both the Consent Decree and the RAWP, soil contamination remains in the

Property at concentrations that do not allow for the unrestricted use of the Property. A Remedial Action Report ("RAR") for SA-6 South was submitted to the Department on February 8, 2017. The Department approved the RAR on March 30, 2017. A Construction Completion Report ("CCR") for SA-6 South to document the implementation of the Chromium Remedy pursuant to Article III of the Consent Decree (the "Chromium Remedy") to address chromium-impacted soil and groundwater for SA-6 South was entered by the Court on [DATE], [CITE TO DOCKET AND DOCKET #].

For SA-7, the Court-Ordered Remedy 100% Design was approved by the Court on March 14, 2005. Remediation was completed to comply with the court order to remove all materials containing hexavalent chromium in excess of 240 milligrams per kilogram ("mg/kg"). The remedial action achieved compliance with the Department's current most stringent soil cleanup criteria of 20 mg/kg, with the exception of a small portion of the Property at the bulkhead along the Hackensack River where excavation was technically impractical (the Technically Impracticable Area (or "TI Area")) (*i.e.*, Tract 1). Completion of the excavation remedy at SA-7 was acknowledged by the Court in the Amended Order Modifying the Judgment, January 13, 2012, ECF No. 1116, in Interfaith Community Organization v. Honeywell International Inc., Civ. No. 95-2097. Remedial actions for soils are also documented in a Remedial Action Report for Soils ("RAR") submitted to the New Jersey Department of Environmental Protection during December 2010.

The Property is comprised of two tracts of land; Tract 1 is on a portion of SA-7 and Tract 2 is on a portion of Site 073 on SA-6 South. Tract 1 is an approximately 22,323 square foot area on SA-7 between the bulkhead and the western hydraulic barrier installed at SA-7. Tract 1 includes the western hydraulic barrier of SA-7. Tract 1 is the "Technically Impracticable Area or TI Area" identified in the SA-7 RAR. NJDEP issued a conditional No Further Action letter for SA-7 soils on December 23, 2010, that excludes the TI Area. Soils within Tract 1 do not meet the 20 mg/kg objective in the NJDEP Chromium Policy. Tract 1 soils exceeding 20 mg/kg hexavalent chromium are covered by at least 7 feet of clean soils. Tract 1 will not be remediated by Honeywell; instead the 7-foot thick clean soil cap will remain in place and Tract 1 will be subject to this Deed Notice. Tract 1 also includes two steel sheetpile "wing walls" that project toward the bulkhead from the northern and southern corners of the hydraulic barrier intersections. These wing walls are part of the SA-7 Remedy in that they act to minimize re-contamination of the clean backfill material placed in the TI area from either the north or south. The Riverwalk feature including bulkhead improvements, additional fill soils and hardscape features will be constructed over the top of the Tract 1 Deed Notice Area. The provisions of the Long Term Monitoring Plan ("LTMP"), developed pursuant to the Consent Decree, will apply to Tract 1 of the Property.

Tract 2 is an approximately 11,689 square foot area adjacent to the bulkhead partially between the western boundary of the SA 6 South western hydraulic barrier wall and the bulkhead and extending south. The 100% Design plan for the Tract 2 area was to excavate the top 4 feet of soils within the area and defer additional excavation below a depth of 4 feet until implementation of the Bayfront Redevelopment Project when the bulkhead will either be repaired or replaced. Because an approximately 5-foot thick concrete slab was unexpectedly encountered while excavating in this area and because removal of this concrete would jeopardize the integrity of the bulkhead, excavation of residual chromium-impacted soil at any depth in Tract 2 will be coordinated with

bulkhead improvement work to be implemented during the Bayfront Redevelopment Project. Tract 2 soils exceeding 20 mg/kg hexavalent chromium are covered by at least 1 foot of clean soils.

Honeywell is instituting this deed notice on the Property (both Tracts 1 and 2 together). Once the remediation of the Tract 2 area is complete (*i.e.*, the excavation of soils with hexavalent chromium concentration of 20 mg/kg or greater to a depth of 20 feet below ground surface), Honeywell will terminate the deed notice for Tract 2 consistent with the requirements of Paragraph 13 below. In the meantime, the provisions of the LTMP, developed pursuant to the Consent Decree, will apply to Tract 2 of the Property.

The soil contamination is described, including the type, concentration and specific location of such contaminants, in Exhibit B, which is attached hereto and made a part hereof. Groundwater contaminant concentrations and restrictions for SA-6 South in its entirety are addressed in the Classification Exception Area (CEA) approved by the NJDEP on February 16, 2012 and in a forthcoming Remedial Action Permit for Groundwater (recent groundwater samples collected in the Tract 1 portion of the Property do not indicate shallow groundwater contamination within the Property). As a result of the remaining soil contamination, there is a statutory requirement for this Deed Notice and engineering controls in accordance with N.J.S.A. 58:10B-13. Under the terms of the Consent Decree (for Tract 2), Honeywell is responsible for monitoring and maintaining the soil remediation for the Property in perpetuity or until remediation is implemented that renders this Deed Notice unnecessary.

4. CONSIDERATION. In accordance with the Department's approval of the chromium RAWP for the Hudson County Chromate Site Nos. 073, 124, 125, 134, and 140 and the Department's issuance of the No Further Action/Covenant Not to Sue letter for soils at SA-7, and in consideration of the terms and conditions of that approval, and in accordance with the Consent Decree, and other good and valuable considerations, Owner has agreed to subject the Property to certain statutory and regulatory requirements which impose restrictions upon the use of the Property, to restrict certain uses of the Property, and to provide notice to subsequent owners, lessees and operators of the restrictions and the monitoring, maintenance, and biennial certification requirements outlined in this Deed Notice and required by law, as set forth herein.

5A. RESTRICTED AREAS. Due to the presence of contamination remaining at concentrations that do not allow for unrestricted use, Owner has agreed, as part of the remedial action for the Property, to restrict the use of the Property (the "Restricted Areas"); a narrative description of these restrictions, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C, which is attached hereto and made a part hereof. Owner will develop a binder containing a list of these restrictions which will be maintained either at onsite trailers or within the Groundwater Treatment Plant building, available for review and inspection by governmental enforcement officials if requested.

5B. RESTRICTED LAND USES. The following land use restrictions apply to the Property:

i. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(10), prohibits the conversion of a contaminated site, remediated to non-residential soil remediation standards that require the maintenance of engineering or institutional controls, to a child care

facility, or public, private, or charter school without the Department's prior written approval, unless a presumptive remedy is implemented;

ii. The Brownfield and Contaminated Site Remediation Act, N.J.S.A. 58:10B-12.g(12), prohibits the conversion of a landfill, with gas venting systems and or leachate collection systems, to a single-family residence or a child care facility without the Department's prior written approval;

iii. The Consent Decree, paragraph 9, prohibits the unrestricted use of Tract 2 of the Property until the Chromium Remedy set forth in Article III of the Consent Decree is implemented; and

iv. The Conservation Restriction, recorded with the Hudson County Register of Deeds at Book 8772, page 105, restricts the use and development of Tract 2 of the Property; the Conservation Restriction will be removed if the Chromium Remedy set forth in Article III of the Consent Decree is implemented and the Deed Notice for Tract 2 is terminated.

5C. ENGINEERING CONTROLS. Due to the presence and concentration of these contaminants, the Owner has also agreed, as part of the remedial action for the Property, to the placement of certain engineering controls within the Property. A narrative description of these engineering controls, along with the associated monitoring and maintenance activities and the biennial certification requirements are provided in Exhibit C. Honeywell shall be responsible for monitoring and maintenance of engineering controls and biennial certification requirements as specified in the Consent Decree, the LTMP, and Paragraphs 8A and 8B herein.

5D. LONG TERM MONITORING PLAN. Pursuant to the Consent Decree, Honeywell has developed an LTMP which sets forth requirements for monitoring, maintenance, and repairing or replacing the soil and groundwater chromium remedial measures including engineering controls within the Property, with limitations for Tract 1 of the Property as described above, and requirements for notification and reporting pursuant to the Consent Decree, Deed Notice, and Soil Remedial Action Permit. A copy of the LTMP is maintained by Honeywell at 115 Mount Tabor Road, Morris Plains, NJ 07950. This Deed Notice is appended to the LTMP.

5F. WORKER TRAINING MATERIALS. All maintenance workers engaged in maintenance at the Property shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy. Workers shall be trained using materials developed by Honeywell pursuant to the Consent Decree.

6A. CHANGE IN OWNERSHIP AND REZONING.

i. The Owner and the subsequent owners and lessees, shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. The Owner and the subsequent owners shall provide written notice to the Department of Environmental Protection on a form provided by the Department and available at www.nj.gov/srp/forms within thirty (30) calendar days after the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property.

iii. The Owner and the subsequent owners shall provide written notice to the Department, on a form available from the Department at www.nj.gov/srp/forms, within thirty (30) calendar days after the owner's petition for or filing of any document initiating a rezoning of the Property to residential.

6B. SUCCESSORS AND ASSIGNS. This Deed Notice shall be binding upon Owner and upon Owner's successors and assigns, and subsequent owners, lessees, and operators while each is an owner, lessee, or operator of the Property.

7A. ALTERATIONS, IMPROVEMENTS, AND DISTURBANCES.

i. The Owner and all subsequent owners and lessees shall notify any person of whom it has knowledge, including, without limitation, tenants, employees of tenants, developers, and contractors, intending to conduct invasive work or excavate within the Restricted Areas, of the nature and location of known contamination in the Restricted Areas, and, of the precautions necessary to protect the engineering controls and minimize potential human exposure to contaminants.

ii. Except as provided in the Consent Decree and Paragraph 7B below, no person shall make, or allow to be made, any alteration, improvement, or disturbance in, to, or about the Property which disturbs any engineering control at the Property except as (a) permitted in the Consent Decree and Conservation Restriction, and (b) without first obtaining a Soil Remedial Action Permit modification from the Department. Nothing herein shall constitute a waiver of the obligation of any person to comply with all applicable laws and regulations including, without limitation, the applicable rules of the Occupational Safety and Health Administration.

iii. Notwithstanding subparagraph 7A.ii.(b), above, a Soil Remedial Action Permit modification is not required for any alteration, improvement, or disturbance provided that:

(A) Such action is taken in conformance with the Consent Decree and this Deed Notice; and

(B) The Department of Environmental Protection is notified of the activity by calling the DEP Hotline, at 1-877-WARN-DEP or 1-877-927-6337, within twenty-four (24) hours after the beginning of each alteration, improvement, or disturbance; and

(C) Honeywell is notified of the activity by calling 855-727-2658; and

(D) Honeywell and/or the owner restores any disturbance of an engineering control to pre-disturbance conditions, consistent with the requirements of the Consent Decree and

LTMP, within sixty (60) calendar days after the initiation of the alteration, improvement or disturbance; and

(E) All applicable worker health and safety laws and regulations are followed during the alteration, improvement, or disturbance, and during the restoration; and

(F) Appropriate measures are taken so that human exposure, and exposure of the environment outside the containment of the engineering controls, to contamination in excess of the applicable remediation standards does not occur; and

(G) The next biennial certification includes a description of the nature of the alteration, improvement, or disturbance, the dates and duration of the alteration, improvement, or disturbance, the name of key individuals and their affiliations conducting the alteration, improvement, or disturbance, a description of the notice the Owner gave to those persons prior to the disturbance, the amounts of soil generated for disposal, if any, the final disposition and any precautions taken to prevent exposure.

7B. EMERGENCIES. In the event of an emergency which presents, or may present, an unacceptable risk to the public health and safety, or to the environment, or immediate environmental concern, see N.J.S.A. 58:10C-2, any person may temporarily breach an engineering control provided that:

i. The Department of Environmental Protection is immediately notified of the emergency, by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

ii. Immediately after notifying NJDEP, Honeywell is notified of the emergency by calling 855-727-2658; and

iii. Both the actual disturbance and the time needed for the disturbance are limited to the minimum reasonably necessary to adequately respond to the emergency; and

iv. All measures necessary to limit actual or potential, present or future risk of exposure to humans or the environment to the contamination are implemented; and

v. The Department of Environmental Protection is notified when the emergency has ended by calling the DEP Hotline at 1-877-WARNDEP or 1-877-927-6337; and

vi. Honeywell is notified when the emergency has ended by calling 855-727-2658; and

vii. Honeywell restores the engineering control to the pre-emergency conditions, consistent with the requirements of the Consent Decree and LTMP, as soon as possible, and submits a written report to the Department of Environmental Protection of such emergency and restoration efforts within sixty (60) calendar days after completion of the restoration of the engineering control. The report must include all information pertinent to the emergency, potential discharges of contaminants, and restoration measures that were implemented, which, at a minimum, should specify: (a) the nature and likely cause of the emergency, (b) the potential discharges of or

exposures to contaminants, if any, that may have occurred, (c) the measures that have been taken to mitigate the effects of the emergency on human health and the environment, (d) the measures completed or implemented to restore the engineering control, and (e) the changes to the engineering control or site operation and maintenance plan to prevent recurrence of such conditions in the future. Honeywell shall submit the report to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413

8A. MONITORING AND MAINTENANCE OF DEED NOTICE, AND PROTECTIVENESS CERTIFICATION. The persons in any way responsible, pursuant to the Spill Compensation and Control Act, N.J.S.A. 58:10-23.11a et seq., for the hazardous substances that remain at the Property, the persons responsible for conducting the remediation, Honeywell, the Owner, and the subsequent owners, lessees, and operators, shall monitor and maintain this Deed Notice. The subsequent owners, lessees and operators have this obligation only during their ownership, tenancy, or operation. Honeywell shall certify to the Department on a biennial basis that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the deed notice shall include all of the following:

i. Monitoring and maintaining this Deed Notice according to the requirements in Article III of the Consent Decree and Exhibit C herein, to ensure that the remedial action that includes the Deed Notice continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes this Deed Notice remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes this Deed Notice, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

8B. MONITORING AND MAINTENANCE OF ENGINEERING CONTROLS, AND PROTECTIVENESS CERTIFICATION. Honeywell shall maintain all engineering controls at the Property and certify to the Department on a biennial basis that the remedial action of which each engineering control is a part remains protective of the public health and safety and of the environment. The specific obligations to monitor and maintain the engineering controls shall include the following:

i. Monitoring and maintaining each engineering control according to the requirements in Article III of the Consent Decree, the LTMP, and Exhibit C herein, to ensure that the remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment; and

ii. Conducting any additional remedial investigations and implementing any additional remedial actions, that are necessary to correct, mitigate, or abate each problem related to the protectiveness of the remedial action for the Property prior to the date that the certification is due to the Department pursuant to iii, below, so that the remedial action that includes the engineering control remains protective of the public health and safety and of the environment; and

iii. Certifying to the Department of Environmental Protection the continued protectiveness of the remedial action that includes the engineering control, on a form provided by the Department and consistent with N.J.A.C. 7:26C-1.2 (a)1, every two years on the anniversary of the date stamped on the Deed Notice that indicates when the Deed Notice was recorded.

9. ACCESS. The Owner, subsequent owners, lessees, and operators, agree to allow the Department, its agents and representatives access to the Property to inspect and evaluate the continued protectiveness of the remedial action that includes this Deed Notice and to conduct additional remediation to ensure the protection of the public health and safety and of the environment if the persons responsible for monitoring the protectiveness of the remedial action, as described in Paragraph 8, above, fail to conduct such remediation pursuant to this Deed Notice as required by law. The Owner, and the subsequent owners and lessees, shall also cause all leases, subleases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring that all holders thereof provide such access to the Department.

10. NOTICES.

i. Owner shall cause all leases, grants, and other written transfers of an interest in the Property to contain a provision expressly requiring all holders thereof to take the Property subject to the restrictions contained herein and to comply with all, and not to violate any of the conditions of this Deed Notice. Nothing contained in this Paragraph shall be construed as limiting any obligation of any person to provide any notice required by any law, regulation, or order of any governmental authority.

ii. Honeywell or the Owner shall notify any person intending to conduct invasive work or excavate within the Property of the nature and location of contamination and, of the precautions necessary to minimize potential human exposure, and exposure of the environment outside the containment of the engineering controls, to contaminants.

iii. Owner shall provide written notice to the Department of Environmental Protection at least thirty (30) calendar days before the effective date of any conveyance, grant, gift, or other transfer, in whole or in part, of the owner's interest in the Property. Any such conveyance, grant or gift must be consistent with the terms of the Consent Decree.

iv. Owner shall provide written notice to the Department within thirty (30) calendar days following the Owner's receiving notice of any petition for a rezoning of the Property. Any such rezoning must be consistent with the terms of the Consent Decree. The Owner shall submit the written notice to:

Department of Environmental Protection
Division of Remediation Management and Response
Bureau of Operation, Maintenance and Monitoring
Deed Notice Inspection Program
P.O. Box 413
401 E. State Street
Trenton, NJ 08625-0413.

11. ENFORCEMENT OF VIOLATIONS.

i. This Deed Notice itself is not intended to create any interest in real estate in favor of the Department of Environmental Protection, nor to create a lien against the Property, but merely is intended to provide notice of certain conditions and restrictions on the Property and to reflect the regulatory and statutory obligations imposed as a conditional remedial action for this Property.

ii. The restrictions provided herein may be enforceable by the Department against any person who violates this Deed Notice. To enforce violations of this Deed Notice, the Department may initiate one or more enforcement actions pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C, and require additional remediation and assess damages pursuant to N.J.S.A. 58:10-23.11, and N.J.S.A. 58:10C.

iii. This Deed Notice as to Tract 2 is also enforceable in the United States District Court for the District of New Jersey by all residents, owners, lessees, and all commercial tenants on Study Areas 6 and 7 pursuant to paragraphs 80 and 83 of the Consent Decree.

12. SEVERABILITY. If any court of competent jurisdiction determines that any provision of this Deed Notice requires modification, such provision shall be deemed to have been modified automatically to conform to such requirements. If a court of competent jurisdiction determines that any provision of this Deed Notice is invalid or unenforceable and the provision is of such a nature that it cannot be modified, the provision shall be deemed deleted from this instrument as if the provision had never been included herein. In either case, the remaining provisions of this Deed Notice shall remain in full force and effect.

13. MODIFICATION AND TERMINATION.

i. Any person may request in writing, at any time, that the Department modify this Deed Notice where performance of subsequent remedial actions, a change of conditions at the Property, or the adoption of revised remediation standards suggest that modification of the Deed Notice would be appropriate, provided that any such modification is consistent with the requirements of the Consent Decree.

ii. Any person may request in writing, at any time, that the Department terminate this Deed Notice because the conditions which triggered the need for this Deed Notice are no longer applicable.

iii. Any person seeking a modification or termination of this Deed Notice must also have such modification approved by the United States District Court for the District of New Jersey pursuant to the Consent Decree until such time as the Consent Decree terminates with regard to the Property pursuant to the Consent Decree.

iv. If the United States District Court for the District of New Jersey and NJDEP have concluded that this Deed Notice shall be modified or terminated, such modification or termination will only be effective upon the filing of a Termination of Deed Notice, available at N.J.A.C. 7:26C Appendix C, with the office of the Register of Deeds of Hudson County, New Jersey, expressly modifying or terminating this Deed Notice.

v. Within thirty (30) calendar days after the filing of a Termination of Deed Notice, the owner of the Property shall apply to the Department for modification or termination of the Soil Remedial Action Permit pursuant to N.J.A.C. 7:26C-7.

vi. This Deed Notice may be modified only if it has first been terminated pursuant to subparagraphs 13v above, and upon filing of a modified Deed Notice, executed by the Owner of the Property, in the office of the Register of Deeds of Hudson County, New Jersey.

14A. EXHIBIT A. Exhibit A includes the following maps of the Property and the vicinity:

i. Exhibit A-1: Vicinity Map - A map that identifies by name the roads, and other important geographical features in the vicinity of the Property;

ii. Exhibit A-2: Metes and Bounds Description - A metes and bounds description of the Property, including reference to tax lot and block numbers for the Property and a Tax Map;

iii. Exhibit A-3: Property Map - A scaled map of the Property, scaled at one inch to 200 feet or less, and if more than one map is submitted, the maps shall be presented as overlays, keyed to a base map; the map(s) shall include diagrams of major surface topographical features such as buildings, roads, and parking lots. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as roads, walkways and other hardscape.

14B. EXHIBIT B. Exhibit B includes the following descriptions of the Restricted Areas:

i. Exhibit B-1: Restricted Area Map - Maps for the Property that include, as applicable:

(A) As-built diagrams of each engineering control, including caps, fences, hydraulic barrier walls, ground water monitoring wells, and ground water pumping system;

(B) As-built diagrams of any buildings, roads, parking lots, utility corridors, and other structures that function as engineering controls; and

(C) Designation of all soil and/or sediment sample locations within the restricted areas that exceed any soil or sediment standard that are keyed into one of the tables described below.

ii. Exhibit B-2 (Table B-2): Restricted Area Data Tables - Table for the Property that includes:

(A) Sample location designation from Restricted Area maps (Exhibit B-1);

(B) Sample elevation based upon mean sea level;

(C) Name and chemical abstract service registry number of each contaminant with a concentration that exceeds the unrestricted use standard;

(D) The restricted and unrestricted use standards for each contaminant in the table; and

(E) The remaining concentration of each contaminant at each sample location at each elevation (or if historic fill, include data from the Department's default concentrations at N.J.A.C. 7:26E-4.6, Table 4-2).

14C. EXHIBIT C. Exhibit C includes narrative descriptions of the institutional controls and engineering controls as follows:

i. Exhibit C-1A and B. Exhibit C-1-A: Deed Notice as Institutional Control; Exhibit C-1-B: Consent Decree as Institutional Control (attached): Exhibit C-1 (A and B) includes a narrative description of the restrictions and obligations of this Deed Notice that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
(1) Description and estimated size of the Restricted Areas as described above;
(2) Description of the restrictions on the Property by operation of this Deed Notice and the other Institutional Controls; and
(3) The objective of the restrictions;

(B) Description of the monitoring necessary to determine whether:
(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;
(2) There have been any land use changes subsequent to the filing of this Deed Notice and the other Institutional Controls or the most recent biennial certification, whichever is more recent;
(3) The current land use on the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls;
(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the Property; and

(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice and the other Institutional Controls, and conduct the necessary sampling.

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice and the other Institutional Controls;

(2) Land use at the Property is consistent with the restrictions in this Deed Notice and the other Institutional Controls; and

(3) The remedial action that includes this Deed Notice and the other Institutional Controls continues to be protective of the public health and safety and of the environment.

ii. Exhibit C-2. Exhibit C-2: Engineering Controls: Clean Fill/Crushed Stone Cover; Exhibit C-2 includes a narrative description of the engineering controls as follows:

(A) General Description of the engineering control:

(1) Description of the engineering control;

(2) The objective of the engineering control; and

(3) How the engineering control is intended to function.

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering control;

(4) The engineering control is being inspected and maintained and its integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering control. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering control; and

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling.

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering control continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

15. SIGNATURES. IN WITNESS WHEREOF, Owner has executed this Deed Notice as of the date first written above.

ATTEST: , LLC

_____ By_____
[Signature] [Signature]

_____ _____
[Print name and title] [Print name and title]

STATE OF NEW JERSEY SS.:
COUNTY OF _____

I certify that on _____ ___, 2017, _____ personally came before me, and this person acknowledged under oath, to my satisfaction, that:

(a) this person is the _____ of _____, LLC, the Limited Liability Corporation named in this document;

(b) this person is the attesting witness to the signing of this document by the proper corporate officer who is the _____ of the Limited Liability Corporation;

(c) this document was signed and delivered by the Limited Liability Corporation as its voluntary act and was duly authorized;

(d) this person knows the proper seal of the Limited Liability Corporation which was affixed to this document; and

(e) this person signed this proof to attest to the truth of these facts.

_____
[Signature]

_____
[Print name and title of attesting witness]

Signed and sworn before me on _____, 20__

_____, Notary Public

_____
[Print name and title]

**EXHIBIT A**
**Deed Notice #4 Site 073 and SA-7**

**A-1 Vicinity Map**

**A-2 Metes and Bounds Description and Tax Map**

**A-3 Property Map Portions of Block 24601, Lot 1 and Portions of Block 21901 Lots 8 and 10, City of Jersey City, New Jersey**

Exhibit A-1 Vicinity Map consists of a road map for the vicinity of the Property.

Exhibit A-2 consists of the metes and bounds and a tax map for the Property.


Exhibit A-3 Property Map consists of a figure indicating major surface features and engineering control for the Property. After development of the Property, this Deed Notice shall be modified to show topographical features constructed on the Property such as roads, walkways and other hardscape.

**Exhibit A-1**
**Site Vicinity Map**
**Jersey City, New Jersey**

EXHIBIT A-1
SITE VICINITY MAP
PORTIONS OF STUDY AREA 6 SOUTH SITES 073 and PORTIONS OF STUDY AREA 7
SITE 115
JERSEY CITY, NEW JERSEY

CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (ii) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\deed notice\deed notice 4\3480150450-5100-A100-4000.dwg Fri, 30 Jun 2017 - 11:08am scott.rudkin




SOURCE: USGS QUADRANGLE MAP, 7.5 MIN SERIES
JERSEY CITY, NJ-NY 1967, PHOTO REVISED 1981

SA–6 SITE 073 DEFERRED AREA AND SA–7

**DRAFT**

0 1000 2000 4000
SCALE IN FEET

| | |
|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150450<br>*DRAWING:* 3480150450–5100–A100–4000 | |
| *PREPARED/DATE:* STR 01/28/16 | *CHECKED/DATE:* NW 01/31/17 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT A-1**
VICINITY MAP
BLOCK 24601 LOT 1 AND
BLOCK 21901 LOTS 8 &10
DEED NOTICE # 4 SA-6 SOUTH
SITE 073 DEFERRED AREA AND SA-7
JERSEY CITY, NEW JERSEY

**Exhibit A-2**
**Deed Notice #4 Site 073 and SA-7**
**Metes and Bounds Description of Property: See Attached**
**Tax Map: See Attached**

A-2 Metes and Bounds Description of Property Portions of Block 24601, Lot 1 and Portions of Block 21901 Lots 8 and 10
City of Jersey City, New Jersey

**If there is any discrepancy between the Metes and Bounds and the tax map, or any other maps attached hereto, the Metes and Bounds prevails.**

The Property is identified as a portion of Block 24601, Lot 1 and portion of Block 21901 Lots 8 and 10 on the City of Jersey City tax maps, the Property being presently owned by Bayfront Redevelopment LLC. A copy of the current tax map which includes the Property is attached as Exhibit A-2.

MASER CONSULTING P.A.
Consulting, Municipal & Environmental Engineers
Planners ▪ Surveyors ▪ Landscape Architects

331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Tel: 732.383.1950 ▪ Fax: 732.383.1984

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**
**PROJECT NO. 10000292Q**

**DEED NOTICE AREA 4**
**BLOCK 24601 LOT 1**
**& BLOCK 21901 LOTS 8 & 10**
**APRIL 6, 2016**
**REVISED: JUNE 28, 2017**

All that certain lot, tract or parcel of land situate lying and being in the City of Jersey, in the County of Hudson and State of New Jersey, and being a portion of Lot 1 Block 24601, and a portion of Lot 8 Block 21901, designated as Deed Notice Area 4 as shown on an exhibit entitled, "Deed Notice Area 4, SA6 South, Block 21901, Lot 8, Block 24601, Lot 1, City of Jersey City, Hudson County, New Jersey," prepared by Maser Consulting P.A., dated April 6, 2016, revised June 28, 2017 and being more particularly bounded and described as follows, to wit:

**TRACT I:**

**COMMENCING** at the intersection of the division line between Lots 8 and 10, Block 21901, with the northwesterly line of said Lot 8; thence-

A. **S 59°39'05" E, 23.69 feet**, along said division line to the **True** point of **BEGINNING**, and running; thence-

1. **N 44° 21' 38" E, 6.65 feet,** through a portion of Lot 10, Block 21901; thence-

2. **S 50° 26' 45" E, 40.33 feet,** through said Lot 10 to a point in said division line between Lots 8 and 10, Block 21901; thence-

Running through said Lot 8, Block 21901 the following two (2) courses, as shown on aforementioned exhibit map:

3. **S 45°51'07" W, 569.68 feet**; thence-

4. **S 45°54'51" W, 4.10 feet,** to the division line between Lot 1, Block 24601 and Lot 8, Block 21901; thence-

5. **N 53° 42' 45" W, 40.04 feet,** along said division line; thence –

Running through said Lot 8, Block 21901 the following three (3) courses, as shown on aforementioned exhibit map:

6. **N 45° 37' 13" E, 5.46 feet**; thence –

7. **N 45° 57' 38" E, 511.35 feet**; thence-

8. **N 44° 21' 38" E, 52.57 feet,** to the point and place of **BEGINNING**.

**CONTAINING:** 22,457 S.F. of land more or less or 0.516 acres of land more or less.

**TRACT II:**

**COMMENCING** at the intersection of the division line between Lot 1, Block 24601 and Lot 8, Block 21901, with the northwesterly line of said Lot 8; thence-

A. **S 53° 42' 45" E, 23.85 feet**, along said division line to the **True** point of **BEGINNING**, and running; thence-

1. **S 53° 42' 45" E, 40.04 feet,** along said division line; thence-

Running through said Lot 1, Block 24601 the following ten (10) courses, as shown on aforementioned exhibit map:

2. **S 45°54'51" W, 153.16 feet,** thence –
3. **S 53° 41' 21" E, 12.04 feet**; thence-
4. **S 36° 26' 04" W, 6.50 feet,** thence –
5. **S 38° 36' 29" W, 41.58 feet,** thence –
6. **S 40° 39' 53" W, 9.05 feet,** thence-
7. **N 88° 57' 37" W, 27.39 feet,** thence -
8. **S 26° 56' 10" W, 17.04 feet,** thence -
9. **S 54° 23' 40" W, 30.23 feet,** thence –
10. **N 46° 36' 39" W, 38.87 feet,** thence –
11. **N 45° 37' 13" E, 268.17 feet,** to the point and place of **BEGINNING**.

**DESCRIPTION OF PROPERTY**
**CITY OF JERSEY CITY**
**HUDSON COUNTY, NEW JERSEY**
**PROJECT NO. 10000292Q**


**DEED NOTICE AREA 4**
**BLOCK 24601 LOT 1**
**& BLOCK 21901 LOTS 8 & 10**
**APRIL 6, 2016**
**REVISED: JUNE 28, 2017**

**CONTAINING:** 11,689 S.F. of land more or less or 0. 0.268 acres of land more or less.

06/28/17

GLEN J. LLOYD, P.L.S. DATE SIGNED
NEW JERSEY PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS037598

\\HQFAS1\General\Projects\2010\10000292Q\Survey\Description\Metes & Bounds-Deed Notice 4_REV_6-28-17.docx




| LINE DATA | | |
|---|---|---|
| SEGMENT | DIRECTION | LENGTH |
| L1 | S 53° 41' 21" E | 12.04' |
| L2 | S 36° 26' 04" W | 6.50' |
| L3 | S 38° 36' 29" W | 41.58' |
| L4 | S 40° 39' 53" W | 9.05' |
| L5 | N 88° 57' 37" W | 27.39' |
| L6 | S 26° 56' 10" W | 17.04' |
| L7 | S 54° 23' 40" W | 30.23' |


MASER CONSULTING P.A.
Customer Loyalty through Client Satisfaction
www.maserconsulting.com
Engineers ▪ Planners ▪ Surveyors
Landscape Architects ▪ Environmental Scientists
Office Locations:
▪ Red Bank, NJ ▪ Albany, NY
▪ Clinton, NJ ▪ Chestnut Ridge, NY
▪ Hamilton, NJ ▪ Newburgh, NY
▪ Marmora, NJ ▪ Hawthorne, NY
▪ Mt. Arlington, NJ ▪ Lehigh Valley, PA
▪ Mt. Laurel, NJ ▪ Exton, PA
▪ Sterling, VA ▪ Philadelphia, PA
▪ Norfolk, VA ▪ Tampa, FL
▪ Albuquerque, NM ▪ Miami, FL
▪ Columbia, MD
State of N.J. Cert. of Authorization: 24GA27906500


Copyright © 2017, Maser Consulting P.A. All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reused, disclosed, distributed or relied upon for any other purpose without the express written consent of Maser Consulting P.A.


811 PROTECT YOURSELF
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE
Know what's below. Call before you dig.
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

| REV | DATE | DRAWN BY | DESCRIPTION |
|---|---|---|---|
| 1 | 2/2/17 | KAN | DIVIDED DN-4 INTO TWO TRACTS |
| 2 | 6/28/17 | HA | REVISE DN-4 TRACT I SOUTHEASTERLY LINE NEAR LOT 10 |

DEED NOTICE AREA 4
SA6 SOUTH
FOR

BLOCK 21901, LOT 8
BLOCK 24601, LOT 1
CITY OF JERSEY CITY
HUDSON COUNTY
NEW JERSEY


RED BANK OFFICE
Corporate Headquarters
331 Newman Springs Road
Suite 203
Red Bank, NJ 07701
Phone: 732.383.1950
Fax: 732.383.1984



| SCALE: | DATE: | DRAWN BY: | CHECKED BY: |
|---|---|---|---|
| AS SHOWN | 4/6/2016 | HA | GJL |
| PROJECT NUMBER: 10000292C | | DRAWING NAME: V-EXBT-DN-4_REV | |

SHEET TITLE: DEED NOTICE EXHIBIT

SHEET NUMBER: 1 of 1

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CAD\HONEYWELL_JERSEY CITY\SA 6 SOUTH\3480150468\5710\5710-1\deed notice\deed notice 4\3480150450-5100-A200-4000.dwg Fri, 30 Jun 2017 - 9:53am scott.rudkin




NEW JERSEY STATE HIGHWAY ROUTE 440

**DRAFT**

0 150 300 600


SCALE IN FEET

| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A200-4000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT A-2**<br>TAX MAP<br>BLOCK 24601 LOT 1 AND<br>BLOCK 21901 LOTS 8 & 10<br>DEED NOTICE # 4 SA-6 SOUTH<br>SITE 073 DEFERRED AREA AND SA-7<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16<br>CHECKED/DATE: NW 01/31/17 | | |

**Exhibit A-3**
**Property Map**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.


P:\CADD\HOWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710A\deed notice\deed notice 4\3480150450-5100-A300-4000.dwg Fri, 30 Jun 2017 - 10:04am scott.austin




KEY MAP
SCALE 1" = 600'

LEGEND

| | |
|---|---|
| 21901 | BLOCK NUMBER |
| LOT 8 | LOT NUMBER |
| ——— | BLOCK LINE |
| - - - - | LOT LINE |




DRAFT

0 100 200 400
SCALE IN FEET

| | |
|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-A300-4000 | |
| PREPARED/DATE: STR 01/28/16 | CHECKED/DATE: NW 01/31/17 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**EXHIBIT A-3**
PROPERTY AREA MAP
BLOCK 24601, LOT 1 AND
BLOCK 21901, LOTS 8 & 10
DEED NOTICE # 4 SA-6 SOUTH
SITE 073 DEFERRED AREA AND SA-7
JERSEY CITY, NEW JERSEY

**EXHIBIT B**
**Deed Notice #4 Site 073 and SA-7**
**B-1 Restricted Area Maps**
**B-2 Restricted Area Data Table**
**Block 24601, Lot 1 and Block 21901 Lots 8 and 10**
**City of Jersey City, New Jersey**

Exhibit B-1 Restricted Area Maps include Exhibit B-1A (Restricted Area and Soil Sample Locations), Exhibit B-1B (Cap System Details), and Exhibit B-1C (As-Built Restoration Plan).

Exhibit B-2 is a Restricted Area Data Table indicating soil sample locations with concentrations of hexavalent chromium remaining above the level established in the New Jersey Department of Environmental Protection (NJDEP) Chromium Policy of 20 milligrams per kilogram (mg/kg).


**Restricted Area Map Notes:**

Exhibit B-1 indicates the engineering controls for the chromium remedy components. For soils with hexavalent chromium concentrations above 20 mg/kg, the engineering controls include a minimum of 7 to 14 feet of clean soil cover/crushed stone in the Tract 1 area and a minimum 1 foot of clean soil cover plus asphalt in the Tract 2 area.

**Exhibit B-1**
**Restricted Area Maps**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150450\5710\5710DA\deed notice\deed notice 4\3480150450-5100-B100-4000.dwg Fri, 30 Jun 2017 - 10:12am smith.caitlin




DRAFT


0 150 300 600

SCALE IN FEET


| | | |
|---|---|---|
| Amec Foster Wheeler PROJECT No. 3480150450<br>DRAWING: 3480150450-5100-B100-4000 | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT B-1**A<br>RESTRICTED AREA MAP<br>BLOCK 24601 LOT 1 &<br>BLOCK 21901 LOTS 8 & 10<br>DEED NOTICE # 4 SA-6 SOUTH<br>SITE 073 DEFERRED AREA AND SA-7<br>JERSEY CITY, NEW JERSEY |
| PREPARED/DATE: STR 01/28/16<br>CHECKED/DATE: NW 01/31/17 | | |

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (i) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (ii) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CADD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\571004\deed notice\deed notice 4\3480150450-5100-B200-4000.dwg Fri, 30 Jun 2017 - 10:06am scott.rudkin





CAP SYSTEM DETAIL
TRACT 1
NTS





CAP SYSTEM DETAIL
TRACT 2
NTS

**DRAFT**

| | | | |
|---|---|---|---|
| *Amec Foster Wheeler PROJECT No.* 3480150488<br>*DRAWING:* 3480150450-5100-B200-4000 | | amec foster wheeler<br>ENVIRONMENT & INFRASTRUCTURE. Inc.<br>200 AMERICAN METRO BLVD, SUITE 113<br>HAMILTON, NEW JERSEY 08619 | **EXHIBIT B-1B**<br>CAP SYSTEM DETAILS<br>BLOCK 24601 LOT 1 &<br>BLOCK 21901 LOTS 8 & 10<br>DEED NOTICE # 4 SA-6 SOUTH<br>SITE 073 DEFERRED AREA AND SA-7<br>JERSEY CITY, NEW JERSEY |
| *PREPARED/DATE:* STR 01/25/17 | *CHECKED/DATE:* NW 01/31/17 | | |




NOTE: NO HISTORIC FILL SHALL BE PLACED ON SA–7

TYPICAL VEGETATED SLOPE
NTS

NOTE:

1. REFER TO FIGURE 2 FOR CONSTRUCTION CONTROL GRID AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE ON THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL AS SHOWN ON THE TYPICAL VEGETATED SLOPE DETAIL. THE VEGETATED SLOPE ALONG SA–7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. EXISTING PAVEMENT WAS FIELD INSPECTED BY LSRP AND SUBJECT TO MINOR CRACK FILLING TO SATISFY HISTORIC FILL CAP REQUIREMENTS.
4. STEEL SHEETPILE WALL WAS INSTALLED AS EXCAVATION SUPPORT ALONG THIS AREA AND THEN CUT BELOW CURRENT GRADE AND LEFT IN PLACE. THE TOP OF SHEETPILE IS GENERALLY 0.5 TO 2.0 FT BELOW CURRENT GRADES.

STONE COVER
VEGETATED COVER
PAVEMENT COVER
CONCRETE COVER
STONE COVER IN PLANTER AREAS
RIPARIAN ZONE
DGA COVER
STONE TOE DRAIN
STEEL SHEETPILE WALL
STORM DRAIN PIPE
STORM DRAIN CATCH BASIN

0 80 160 FEET
SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: AS BUILT RESTORATION PLAN SA–6 SOUTH – SHEET 001 12/12/16

PROJECT NAME & LOCATION: HONEYWELL SA–6 REMEDIATION JERSEY CITY, NJ

EXHIBIT B-1C

**Exhibit B-2: Table B-2**
**Soil Sample Data Table (Hexavalent Chromium)**

**EXHIBIT B-2**

**Restricted Area Data Table**

Deed Notice #4 Tract 2 Site 073 and Tract 1 SA-7

Portion of Block 24601, Lot 1 and Portion of Block 21901 Lot 8

Jersey City, New Jersey

| Location | Elevation (feet msl) | Contaminant | CASR# | NJDEP Chromium SCC (mg/kg) | Soil Concentration (mg/kg) |
|---|---|---|---|---|---|
| 115-CF-BH1S | -0.8 | Hexavalent Chromium | 18540-29-9 | 20 | 27.9 |
| 115-CF-BH2N | 0.058 | Hexavalent Chromium | 18540-29-9 | 20 | 30.6 |
| 115-CF-BH2S | -0.311 | Hexavalent Chromium | 18540-29-9 | 20 | 21.2 |
| 115-CF-BH3N | 0.051 | Hexavalent Chromium | 18540-29-9 | 20 | 36.3 |
| 115-CF-BH4N | -0.129 | Hexavalent Chromium | 18540-29-9 | 20 | 22.7 J |
| 115-CF-BH5N | -0.525 | Hexavalent Chromium | 18540-29-9 | 20 | 36.4 J |
| 115-CF-BH5S | -0.154 | Hexavalent Chromium | 18540-29-9 | 20 | 25.3 J |
| 115-CF-BH6S | -1.639 | Hexavalent Chromium | 18540-29-9 | 20 | 46.9 |
| 115-CF-BH7N | -2.118 | Hexavalent Chromium | 18540-29-9 | 20 | 31.8 |
| 115-CF-BH7S | -1.981 | Hexavalent Chromium | 18540-29-9 | 20 | 20.9 |
| 115-CF-BH93 | -2.579 | Hexavalent Chromium | 18540-29-9 | 20 | 34.6 |
| 115-CF-BH94 | -2.556 | Hexavalent Chromium | 18540-29-9 | 20 | 21.7 |
| 115-CF-BH96 | -3.164 | Hexavalent Chromium | 18540-29-9 | 20 | 28.7 |
| 115-CF-BH101 | -5.224 | Hexavalent Chromium | 18540-29-9 | 20 | 45.6 |
| 115-CF-BH102 | -5.657 | Hexavalent Chromium | 18540-29-9 | 20 | 36.8 |
| 115-CF-BH103 | -5.617 | Hexavalent Chromium | 18540-29-9 | 20 | 42.2 |
| 115-CF-BH104 | -5.645 | Hexavalent Chromium | 18540-29-9 | 20 | 32.2 |
| 115-CF-BH105 | -5.563 | Hexavalent Chromium | 18540-29-9 | 20 | 113 |
| 115-CF-BH106 | -5.597 | Hexavalent Chromium | 18540-29-9 | 20 | 26 |
| 115-CF-BH111 | -5.291 | Hexavalent Chromium | 18540-29-9 | 20 | 75.1 |
| 115-CF-BH112 | -5.533 | Hexavalent Chromium | 18540-29-9 | 20 | 105 |
| 115-CF-BH113 | -5.696 | Hexavalent Chromium | 18540-29-9 | 20 | 68.9 |
| 115-CF-BH114 | -5.646 | Hexavalent Chromium | 18540-29-9 | 20 | 83.7 |
| 115-CF-BH115 | -5.718 | Hexavalent Chromium | 18540-29-9 | 20 | 39.9 |
| 115-CF-BH116 | -5.477 | Hexavalent Chromium | 18540-29-9 | 20 | 61.1 |
| 115-CF-BH12E | -7 | Hexavalent Chromium | 18540-29-9 | 20 | 75.9 |
| 115-CF-BH12W | -7 | Hexavalent Chromium | 18540-29-9 | 20 | 53.8 |
| 073-SB-002 | 8.5 | Hexavalent Chromium | 18540-29-11 | 20 | 534 J |
| 073-SB-002 | 6 | Hexavalent Chromium | 18540-29-12 | 20 | 721 |
| 073-SB-002 | 5 | Hexavalent Chromium | 18540-29-13 | 20 | 1100 |
| 073-SB-002 | 3 | Hexavalent Chromium | 18540-29-14 | 20 | 27.9 J |
| 073-SB-024 | 3.2 | Hexavalent Chromium | 18540-29-15 | 20 | 22 |
| 073-SB-025 | 8 | Hexavalent Chromium | 18540-29-15 | 20 | 25.6 |
| 073-SB-025 | 7 | Hexavalent Chromium | 18540-29-16 | 20 | 52.6 |
| 073-SB-053 | 6.8 | Hexavalent Chromium | 18540-29-17 | 20 | 356 |
| 073-SB-054 | 6.4 | Hexavalent Chromium | 18540-29-18 | 20 | 71.6 |
| 073-SB-067 | 8.7 | Hexavalent Chromium | 18540-29-24 | 20 | 36.3 |
| 073-SB-067 | 5.7 | Hexavalent Chromium | 18540-29-25 | 20 | 1370 |
| 073-SB-067 | 3.7 | Hexavalent Chromium | 18540-29-26 | 20 | 211 |
| 073-SB-067 | 2.7 | Hexavalent Chromium | 18540-29-27 | 20 | 62.4 |
| 073-SB-067 | 0.7 | Hexavalent Chromium | 18540-29-19 | 20 | 54.3 |
| 073-SB-067 | -1.3 | Hexavalent Chromium | 18540-29-20 | 20 | 33.3 |
| 073-SB-067 | -4.3 | Hexavalent Chromium | 18540-29-21 | 20 | 132 |
| 073-SB-067 | -5.3 | Hexavalent Chromium | 18540-29-22 | 20 | 86.3 |
| 073-SB-067 | -7.8 | Hexavalent Chromium | 18540-29-23 | 20 | 201 |
| 073-SB-068 | 4.5 | Hexavalent Chromium | 18540-29-33 | 20 | 179 |
| 073-SB-068 | 2.5 | Hexavalent Chromium | 18540-29-34 | 20 | 35.1 |
| 073-SB-068 | 1 | Hexavalent Chromium | 18540-29-35 | 20 | 42.1 |
| 073-SB-068 | -2 | Hexavalent Chromium | 18540-29-28 | 20 | 23.9 |
| 073-SB-068 | -3.5 | Hexavalent Chromium | 18540-29-29 | 20 | 28.2 |
| 073-SB-068 | -5.5 | Hexavalent Chromium | 18540-29-30 | 20 | 66.3 |
| 073-SB-068 | -7.5 | Hexavalent Chromium | 18540-29-31 | 20 | 112 |
| 073-SB-068 | -10 | Hexavalent Chromium | 18540-29-32 | 20 | 81.2 |
| 073-SB-069 | 4.4 | Hexavalent Chromium | 18540-29-39 | 20 | 176 |
| 073-SB-069 | 1.9 | Hexavalent Chromium | 18540-29-40 | 20 | 23.8 |

**EXHIBIT B-2**

**Restricted Area Data Table**

Deed Notice #4 Tract 2 Site 073 and Tract 1 SA-7

Portion of Block 24601, Lot 1 and Portion of Block 21901 Lot 8

Jersey City, New Jersey

| Location | Elevation (feet msl) | Contaminant | CASR# | NJDEP Chromium SCC (mg/kg) | Soil Concentration (mg/kg) |
|---|---|---|---|---|---|
| 073-SB-069 | 0.4 | Hexavalent Chromium | 18540-29-41 | 20 | 20.1 |
| 073-SB-069 | -3.6 | Hexavalent Chromium | 18540-29-36 | 20 | 24.5 |
| 073-SB-069 | -7.6 | Hexavalent Chromium | 18540-29-37 | 20 | 106 |
| 073-SB-069 | -10.1 | Hexavalent Chromium | 18540-29-38 | 20 | 24.5 |
| 073-SB-101 | 7.7 | Hexavalent Chromium | 18540-29-43 | 20 | 705 |
| 073-SB-101 | -1.3 | Hexavalent Chromium | 18540-29-42 | 20 | 21.1 |
| 073-SB-103 | 3.75 | Hexavalent Chromium | 18540-29-43 | 20 | 71.6 |
| 073-SB-103 | 1.7 | Hexavalent Chromium | 18540-29-44 | 20 | 1490 |
| 073-SB-103 | -0.3 | Hexavalent Chromium | 18540-29-45 | 20 | 523 |
| 073-SB-103 | -2.3 | Hexavalent Chromium | 18540-29-46 | 20 | 35 |
| 073-SB-103 | -4.3 | Hexavalent Chromium | 18540-29-47 | 20 | 23.6 |
| 073-SB-103 | -6.3 | Hexavalent Chromium | 18540-29-48 | 20 | 136 |
| 073-SB-103 | -8.3 | Hexavalent Chromium | 18540-29-49 | 20 | 35.4 |
| 073-SB-103 | -10.3 | Hexavalent Chromium | 18540-29-50 | 20 | 76 |
| 073-SB-104 | 4.5 | Hexavalent Chromium | 18540-29-51 | 20 | 362 |
| 073-SB-104 | 2.5 | Hexavalent Chromium | 18540-29-52 | 20 | 4710 |
| 073-SB-104 | 0.5 | Hexavalent Chromium | 18540-29-53 | 20 | 118 |
| 073-SB-104 | -1.5 | Hexavalent Chromium | 18540-29-54 | 20 | 144 |
| 073-SB-104 | -3.5 | Hexavalent Chromium | 18540-29-55 | 20 | 112 |
| 073-SB-104 | -5.5 | Hexavalent Chromium | 18540-29-56 | 20 | 25.7 |
| 073-SB-104 | -7.5 | Hexavalent Chromium | 18540-29-57 | 20 | 54.6 |
| 073-SB-104 | -9.5 | Hexavalent Chromium | 18540-29-58 | 20 | 87.3 |
| 073-SB-104 | -11.5 | Hexavalent Chromium | 18540-29-59 | 20 | 67.4 |
| 073-SB-105 | 0.6 | Hexavalent Chromium | 18540-29-60 | 20 | 52.6 |
| 073-SB-105 | -1.4 | Hexavalent Chromium | 18540-29-60 | 20 | 36.7 |
| 073-SB-105 | -3.4 | Hexavalent Chromium | 18540-29-60 | 20 | 69.4 |
| 073-SB-105 | -7.4 | Hexavalent Chromium | 18540-29-60 | 20 | 125 |
| 073-SB-105 | -9.4 | Hexavalent Chromium | 18540-29-60 | 20 | 264 |
| 073-SB-105 | -11.4 | Hexavalent Chromium | 18540-29-60 | 20 | 142 |
| 073-SB-106 | 2.5 | Hexavalent Chromium | 18540-29-60 | 20 | 36.7 |
| 073-SB-106 | -1.5 | Hexavalent Chromium | 18540-29-60 | 20 | 76.1 |
| 073-SB-106 | -3.5 | Hexavalent Chromium | 18540-29-60 | 20 | 50.3 |
| 073-SB-106 | -5.5 | Hexavalent Chromium | 18540-29-60 | 20 | 57.7 |
| 073-SB-106 | -7.5 | Hexavalent Chromium | 18540-29-60 | 20 | 59.3 |
| 073-SB-106 | -9.5 | Hexavalent Chromium | 18540-29-60 | 20 | 23 |
| 073-SB-106 | -11.5 | Hexavalent Chromium | 18540-29-60 | 20 | 88.7 |

**Notes:**

Results reported in mg/kg.

**Data Qualifiers:**

J-Data indicates the presence of a compound that meets the identification criteria. The concentration is an approximate value.

**Abbreviations:**

Feet bgs - Feet below ground surface

mg/kg - milligrams per kilogram

feet msl = feet mean seal level NAVD88 - North American Vertical Datum of 1988

NJDEP Chromium SCC - New Jersey Department of Environmental Protection Chromium Soil Cleanup Criteria, revised April 2010

**EXHIBIT C**
**Deed Notice #4 Site 073 and SA-7**

**C-1 Institutional Controls**
**C-2 Engineering Controls**
**Portion of Block 24601, Lot 1 and a portion of Block 21901 Lots 8 and 10**
**City of Jersey City, New Jersey**

## C-1 Institutional Controls

C-1 Deed Notice, Consent Decree (attached), as Institutional Controls: Exhibit C-1 (A and B) for those portions of Block 24601, Lot 1 and of Block 21901 Lots 8 and 10, City of Jersey City, New Jersey known as Tracts 1 and 2.

Exhibits C-1A and C-1B. Exhibit C-1A: Deed Notice as Institutional Control; Exhibit C-1B: Consent Decree as Institutional Control; Exhibits C-1A and C-1B include a narrative description of the restrictions and obligations of this Deed Notice and the other Institutional Controls that are in addition to those described above, as follows:

(A) General Description of the Institutional Control:
**The Property is comprised of two tracts of land; Tract 1 is on a portion of SA-7 and Tract 2 is on a portion of Site 073 on SA-6 South. Tract 1 is an approximately 22,323 square foot area on SA-7 between the bulkhead and the western hydraulic barrier installed at SA-7. Tract 1 includes the western hydraulic barrier wall of SA-7. Tract 1 is the "Technically Impracticable Area or TI Area" identified in the SA-7 RAR. NJDEP issued a conditional No Further Action letter for SA-7 soils on December 23, 2010, that excludes the TI Area. Soils within Tract 1 do not meet the 20 mg/kg objective in the NJDEP Chromium Policy. Tract 1 soils exceeding 20 mg/kg hexavalent chromium are covered by at least 7 feet of clean soils. Tract 1 will not be remediated by Honeywell; instead the 7-foot thick clean soil cap will remain in place and Tract 1 will be subject to this Deed Notice. Tract 1 also includes two steel sheetpile "wing walls" that project toward the bulkhead from the northern and southern corners of the hydraulic barrier intersections. These wing walls are part of the SA-7 Remedy in that they act to minimize re-contamination of the clean backfill material placed in the TI area from either the north or south. The Riverwalk feature including bulkhead improvements, additional fill soils and hardscape features will be constructed over top of the Tract 1 Deed Notice Area. The provisions of the LTMP, developed pursuant to the Consent Decree, will apply to Tract 1 of the Property.**

**Tract 2 is an approximately 11,689 square foot area adjacent to the bulkhead partially between the western boundary of the SA 6 South western hydraulic barrier wall and the bulkhead and partially south. The 100% Design plan for the Tract 2 area was to excavate the top 4 feet of soils within the area and defer additional excavation below a depth of 4 feet until implementation of the Bayfront Redevelopment Plan when the bulkhead will either be repaired or replaced. Because an approximately 5-foot thick concrete slab was unexpectedly encountered while excavating in this area and because**

**removal of this concrete would jeopardize the integrity of the bulkhead, excavation of residual chromium-impacted soil at any depth in Tract 2 will be coordinated with bulkhead improvement work to be implemented during the Bayfront Redevelopment Project. Tract 2 soils exceeding 20 mg/kg hexavalent chromium are covered by at least 1 foot of clean soils. In the meantime, Honeywell will institute this deed notice on this area which will include both Tracts 1 and 2. Once the remediation of the Tract 2 area is complete and soils in Tract 2 have a hexavalent chromium concentration of less than 20 mg/kg to a depth of 20 feet below ground surface, Honeywell will terminate the deed notice for Tract 2 with approval of the Court and the Department pursuant to Paragraph 13 above. In the meantime, the LTMP, developed pursuant to the Consent Decree, will apply to Tract II of the Property.**

(1) Description and estimated size of the Restricted Areas as described above;

***The Property constitutes a portion of Block 24601, Lot 1 and a portion of Block 21901 Lots 8 and 10. The estimated size of the Area containing chromium-impacted soils (hexavalent chromium above 20 mg/kg) as identified on Exhibit B-1 is estimated at approximately 34,000 square feet or approximately 0.781 acres.***

(2) Description of the restrictions on the Property by operation of the Institutional Control;

***The Property shall only be used for activities consistent with this Deed Notice, the Consent Decree, and the applicable zoning standards. Intrusive activities (i.e., excavation or digging) that breach the engineering controls (as described in Exhibit C-2) will not be permitted on the Property except in compliance with the terms of the Consent Decree and the applicable portions of the LTMP developed thereunder, and this Deed Notice. See subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies for additional information. A copy of the LTMP is maintained by Honeywell at 115 Tabor Road, Morris Plains, NJ 07950.***

(3) The objective of the restrictions;

***The restrictions will prohibit contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy Criteria of 20 mg/kg.***

(B) Description of the monitoring necessary to determine whether:

(1) Any disturbances of the soil in the Restricted Areas resulted in the unacceptable exposure to the soil contamination;

***Visual inspections of the Property and other monitoring as set forth in the Consent Decree and the applicable portions of the LTMP developed thereunder.***

(2) There have been any land use changes subsequent to the filing of this Deed Notice or the most recent biennial certification, whichever is more recent;

***Same as (B)(1*).**

(3) The current land use on the Property is consistent with the restrictions in this Deed Notice;

***Same as (B)(1).***

(4) Any newly promulgated or modified requirements of applicable regulations or laws apply to the site; and

***Review of newly promulgated or modified requirements of applicable regulations or laws that potentially may apply to the site.***

(5) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***Same as (B)(4)*.**

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) Land use at the Property is consistent with the restrictions in the Consent Decree, this Deed Notice, and the applicable zoning standards; and

(3) The remedial action that includes this Deed Notice continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including evaluation of any available documents as a result of changes in land use or incidents.***
- ***A report that determines whether or not the land use at the Property has remained consistent with the restrictions in the Consent Decree, this Deed Notice*, and *the applicable zoning standards.***
- ***A report that determines whether or not the Deed Notice continues to be protective of the public health and safety and the environment.***

**C-2 Engineering Controls**
**Deed Notice #4 Site 073 and SA-7**
**Portion of Block 24601, Lot 1 and Portion of Block 21901 Lots 8 and 10**
**City of Jersey City, New Jersey**

Exhibits C-2: Narrative description of the Engineering Controls including Clean Fill as follows:

(A) General Description of the engineering controls:

(1) Description of the engineering controls;

***The Engineering Controls consist of the following: The engineering controls for Tract 1 Study Area 7 (Site 115) include a minimum 7 to 14 feet of clean soil cover (crushed stone) and for Tract 2 Study Area 6 South (Site 073) a minimum of 1 foot of clean soil cover plus asphalt pavement as shown on Exhibit B-1.***

(2) The objective of the engineering controls; and

***The objective of the controls is to prevent contact with soils containing hexavalent chromium above the level established in the NJDEP Chromium Policy of 20 mg/kg.***

(3) How the engineering controls are intended to function.

***The soil engineering controls are intended to function as a barrier to underlying and adjacent soils containing hexavalent chromium above 20 mg/kg within the Property. Monitoring requirements for the engineering controls are set forth in the applicable portions of the LTMP.***

(B) Description of the operation and maintenance necessary to ensure that:

(1) Periodic inspections of each engineering control are performed in order to determine its integrity, operability, and effectiveness;

***Honeywell will perform monitoring by visual inspection of the Property pursuant to the Consent Decree for the portion of the Property that lies within SA-6 South. Other monitoring activities shall be performed as set forth in the applicable portions of the LTMP developed pursuant to the Consent Decree.***

(2) Each engineering control continues as designed and intended to protect the public health and safety and the environment;

***Same as (B)(1) above.***

(3) Each alteration, excavation or disturbance of any engineering control is timely and appropriately addressed to maintain the integrity of the engineering controls;

***Same as (B)(1) above. Also, see the Consent Decree and subsections 7A Alterations, Improvements, Disturbances, and 7B Emergencies for additional information.***

(4) The engineering controls are being inspected and maintained and their integrity remains so that the remedial action continues to be protective of the public health and safety and of the environment;

***Same as (B)(1) above.***

(5) A record of the self-inspection dates, name of the inspector, results of the inspection and condition(s) of the engineering controls. Sampling, for example, may be necessary if it is not possible to visually evaluate the integrity/performance of the engineering controls; and

***Records of the inspections are to be maintained as listed in (5). Other monitoring activities shall be performed as set forth in the applicable portions of the LTMP developed pursuant to the Consent Decree.***

(6) Any new standards, regulations, or laws apply to the Property that might necessitate additional sampling in order to evaluate the protectiveness of the remedial action which includes this Deed Notice, and conduct the necessary sampling; and

***A review of any new standards, regulations, or laws will be conducted. Should the review indicate that other activities are necessary, those activities will be listed and executed.***

(C) Description of the following items that will be included in the biennial certification:

(1) A monitoring report that describes the specific activities, pursuant to (A) and (B), above, conducted in support of the biennial certification of the protectiveness of the remedial action that includes this Deed Notice;

(2) The engineering controls continues to operate as designed; and

(3) The remedial action that includes the engineering control continues to be protective of the public health and safety and of the environment.

***The monitoring report will be included in the biennial certification. Components of the monitoring report will include the following:***

- ***A report of all conditions set forth in sections (A) and (B) above to assure that they have been adhered to, including an evaluation to determine whether or not the engineering controls are continuing to meet the original objective and intended function.***
- ***A report to determine whether or not the engineering controls continue to operate as designed.***
  ***A report to determine whether or not the engineering controls continue to be protective of the public health and safety and of the environment.***

**Appendix I**
**Consent Decree**

# APPENDIX I

UNITED STATES DISTRICT COURT
DISTRICT OF NEW JERSEY

| | |
|---|---|
| JERSEY CITY MUNICIPAL UTILITIES AUTHORITY,<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Docket No. 05-5955(DMC)<br>Consolidated under Docket No. 95-2097 (DMC) |
| JERSEY CITY INCINERATOR AUTHORITY<br><br>Plaintiff,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC.,<br><br>Defendant. | Civil Action No. 05-5993<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 (DMC) |
| HACKENSACK RIVERKEEPER, INC., *et al.*<br><br>Plaintiffs,<br><br>v.<br><br>HONEYWELL INTERNATIONAL INC., *et al.*<br><br>Defendants. | Civil Action No. 06-22<br>Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097 |

**FIRST AMENDED CONSENT DECREE REGARDING REMEDIATION AND REDEVELOPMENT OF STUDY AREA 6 SOUTH**

# TABLE OF CONTENTS

**RECITALS** ..... 1

**ARTICLE I: DEFINITIONS** ..... 4

**ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED** ..... 11

**ARTICLE III: CHROMIUM REMEDIATION** ..... 12

A. GENERAL TERMS AND REQUIREMENTS ..... 12
50. Responsibility for Implementation of Chromium Remediation. ..... 12
51. Designation of Chromium Areas of Concern. ..... 12
52. Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan. ..... 12
53. General Scope of the Chromium Remedy. ..... 13
54. Development of a Schedule for the Chromium Remedy. ..... 13
B. INITIAL CHROMIUM REMEDY STEPS: DELINEATION, TREATMENT STUDY, AND REMEDIAL ACTION WORK PLAN ..... 15
55. Delineation of Development AOC. ..... 15
56. Conduct of a Treatment Study in the Development AOC . ..... 15
57. Continued Monitoring of the Treatment Study. ..... 16
58. Submission of a Remedial Action Work Plan. ..... 16
C. DEVELOPMENT AOC SOIL REMEDY ..... 16
59. Remedial Components ..... 16
60. Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium ..... 17
61. Treatment as a Remedial Component for 20 to 240 Soils ..... 18
62. Submissions Related to Site 163 ..... 20
63. Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium. ..... 20
64. Post-Treatment Monitoring for 20 to 1000 Soils ..... 21
D. OPEN SPACE AOC COMPONENTS OF THE CHROMIUM REMEDY ..... 21
65. Open Space AOC Soil Remedy ..... 21
E. DEMOLITION, GRADING, AND BACKFILL REQUIREMENTS ..... 23
66. Demolition and Grading Activities. ..... 23
67. Backfill Requirements. ..... 23
68. Vegetation of Clean Fill. ..... 23
F. GROUNDWATER COMPONENTS OF THE CHROMIUM REMEDY ..... 23
69. Shallow Groundwater Remedy for the Open Space AOC ..... 23
70. The Shallow Groundwater Remedy for the Development AOC. ..... 24
71. Off-Site Shallow Groundwater Remedy. ..... 25
72. L-Well Groundwater Remedy. ..... 26
G. PERMITS AND AUTHORIZATIONS ..... 26
73. Permits and Authorizations. ..... 26
H. LONG-TERM MONITORING, MAINTENANCE, AND PROTECTION OF ENGINEERING AND INSTITUTIONAL CONTROLS ..... 27

74. Protection of the Open Space AOC ..... 27
75. Honeywell's Ongoing Responsibility. ..... 39
76. Long-Term Monitoring Plan. ..... 39
77. Long-Term Monitoring Plan Objectives ..... 39
78. Monitoring and Remediation Under the Long-Term Monitoring Plan ..... 40
79. Monitoring and Reporting to Riverkeeper. ..... 44
80. Notice to Stakeholders ..... 44
81. Annual Letter to Riverkeeper on Notice to Stakeholders ..... 45
82. Future Notice to Stakeholders ..... 45
83. Stakeholder Enforcement. ..... 46
I. OVERSIGHT AND ENFORCEMENT BY THE SPECIAL MASTER AND NJDEP ..... 46
84. Federal Court Jurisdiction ..... 46
85. Appointment and Jurisdiction of the Special Master. ..... 46
86. Oversight of the Chromium Remedy. ..... 46
87. Retention of Professionals. ..... 53
88. Insurance for the Special Master. ..... 53
89. Reimbursement of Special Master Fees and Expenses. ..... 54
90. Expiration of Special Master's Appointment. ..... 54
J. INITIAL FINANCIAL ASSURANCES ..... 55
91. Chromium Remedy Letter of Credit ..... 55
92. Procedures for Review of the Proposed Chromium Remedy Letter of Credit ..... 56
93. Automatic Renewal. ..... 56
94. Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit ..... 57
95. Bankruptcy Protection. ..... 58
96. Exclusive Court Jurisdiction. ..... 58
97. Application of New York Law. ..... 59
98. Procedures upon Honeywell's Material Default of Its Obligations ..... 59
99. Placement of Proceeds in Court Registry Investment System Account. ..... 60
100. Termination of Chromium Remedy Letter of Credit ..... 61
K. LONG-TERM FINANCIAL ASSURANCES ..... 61
101. Long-Term Financial Assurances. ..... 61
102. Costs Subject to Long-Term Financial Assurances. ..... 61
103. Long-Term Financial Assurance Mechanisms ..... 62
104. Procedures for Review of the Proposed Long-Term Financial Assurances ..... 66
105. Temporary Maintenance of Chromium Remedy Letter of Credit. ..... 66
106. Adjustment of Amount Held in Long-Term Financial Assurances. ..... 67
107. Exclusive Court Jurisdiction. ..... 68
108. Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired: ..... 68
109. Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default ..... 69
110. Use of the Trust Fund in the Event of Honeywell's Default. ..... 70
111. Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109. ..... 70
112. Termination of the Long-Term Financial Assurances. ..... 70

**ARTICLE IV: TERMINATION** ..... 71

113. Termination of this Consent Decree ..... 71
114. Procedures for Withdrawal and Termination. ..... 72
115. Good-Faith Obligation to Avoid Termination ..... 72
116. Effect of Termination. ..... 72

**ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC** ..... 72

117. Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC. ..... 72

**ARTICLE VI: NOTICE** ..... 73

118. Notice ..... 73
119. Payment of Past Fees and Expenses ..... 74
120. Future Fees and Expenses. ..... 75

**ARTICLE VIII: MISCELLANEOUS PROVISIONS** ..... 76

121. Force Majeure. ..... 76
122. Bayfront Redevelopment LLC as a Party. ..... 76
123. Successors and Assigns. ..... 77
124. Successors to Hackensack Riverkeeper, Inc.. ..... 77
125. Reservation of Rights and Claims. ..... 77
126. Governing Law and Continuing Jurisdiction. ..... 77
127. Construction. ..... 78
128. Authority to Enter into Agreement. ..... 78
129. Measures to Effectuate This Consent Decree ..... 78
130. Modifications. ..... 78
131. Severability. ..... 78
132. Signatures. ..... 79

## RECITALS

**Whereas,** on June 30, 2003, the district court for the District of New Jersey (hereafter "the Court") issued a Final Judgment in *Interfaith Community Organization v. Honeywell International Inc.*, Civ. No. 95-2097 (DMC) (*"ICO v. Honeywell"*), ordering the remediation of an area designated by the New Jersey Department of Environmental Protection ("NJDEP") as Study Area 7 by excavation of all chromium contamination on the property, under the oversight of a court-appointed Special Master;

**Whereas**, on or about December 23, 2005, the Jersey City Municipal Utilities Authority ("JCMUA") filed litigation styled *Jersey City Municipal Utilities Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5955 (DMC), bringing claims against Honeywell International Inc. ("Honeywell") under, *inter alia*, Section 6972 of the Resource Conservation and Recovery Act ("RCRA"), and seeking remediation of chromium contamination on property then-owned by JCMUA and other relief;

**Whereas**, on or about December 28, 2005, the Jersey City Incinerator Authority ("JCIA") filed litigation styled *Jersey City Incinerator Authority v. Honeywell International Inc.,* D.N.J., Civ. No. 05-5993 (DMC), bringing claims against Honeywell under, *inter alia*, Section 6972 of RCRA, and seeking remediation of chromium contamination on property then-owned by JCIA and other relief;

**Whereas**, on or about January 4, 2006, the Hackensack Riverkeeper, Inc., Captain William Sheehan, Reverend Winston Clarke, and Lawrence Baker ("Riverkeeper") filed litigation styled *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.,* D.N.J., Civ. No. 06-022 (DMC), bringing a claim against Honeywell under RCRA and seeking remediation of chromium contamination to soils, groundwater, surface waters, and sediments associated with

various properties collectively designated by NJDEP as Study Areas 5, 6 North, which includes the properties formerly owned by JCMUA and JCIA, and 6 South;

**Whereas,** Study Areas 6 North and South are directly adjacent to Study Area 7 on the north and south sides, respectively;

**Whereas,** Study Area 5 is comprised of properties to the east of Study Areas 6 North, 6 South, and 7 across Route 440;

**Whereas,** Riverkeeper also named as defendants in *Riverkeeper v. Honeywell* owners of the properties comprising Study Areas 5, 6 South, and 6 North;

**Whereas,** *JCMUA v. Honeywell*, *JCIA v. Honeywell,* and *Riverkeeper v. Honeywell* were consolidated by the Court (hereinafter the "Consolidated Litigation");

**Whereas,** in the Consolidated Litigation, Riverkeeper has alleged that Honeywell bears responsibility for the presence and remediation of chromite ore processing residue ("COPR") and chromium in soils and groundwater on the Study Area 6 South property;

**Whereas,** on April 21, 2008, the Court entered the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North (hereafter "the Study Area 6 North Consent Decree") resolving issues between Honeywell, Riverkeeper, and the Jersey City Entities related to chromium contamination at Study Area 6 North;

**Whereas**, on April 21, 2008, the district court for the District of New Jersey entered the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. (hereafter "Jersey City/Honeywell Consent Order"), filed in the Consolidated Litigation simultaneously with the Study Area 6 North Decree, which resolved claims and cross-claims between Honeywell and the Jersey City Entities;

**Whereas**, on May 28, 2008, the Court entered the Consent Order on Sediment Remediation and Financial Assurances ("Sediment Consent Order"), resolving issues related to the remediation of chromium contaminated sediments in the Hackensack River in the vicinity of Study Areas 5, 6, and 7;

**Whereas**, on September 3, 2008, the Court entered the Deep Overburden and Bedrock Groundwater Remedies Consent Order (hereafter "the Deep Groundwater Consent Order") resolving all issues related to the remediation of deep overburden and bedrock groundwater in both *ICO v. Honeywell* and the Consolidated Litigation;

**Whereas,** on May 13, 2011, Plaintiffs sent Honeywell a RCRA citizen action suit notice letter with respect to Site 163, and the Parties agree that the incorporation of Site 163 into this Consent Decree resolves any claims asserted, or that could have been asserted, in the RCRA notice letter or in any RCRA citizen suit with respect to Site 163;

**Whereas**, the Parties to this Consent Decree each believe that it is in their mutual interest to move forward productively to resolve their differences so that they can implement environmental remediation at Study Area 6 South that ensures the continued protection of human health and the environment and so that Study Area 6 and Study Area 7 can be redeveloped in keeping with Jersey City's vision for a revitalized West Side;

**Whereas,** the Local Redevelopment and Housing Law, N.J.S.A. 40A:12A-1, *et seq.*, as amended and supplemented (the "Redevelopment Law") provides for municipalities to participate in the redevelopment and improvement of areas in need of redevelopment;

**Whereas**, Study Area 6 and Study Area 7 consist of parcels which by ordinance adopted by the City Council of Jersey City on February 27, 2008, have been determined to be "areas in

need of redevelopment" under the criteria of the Redevelopment Law because of conditions prevalent on those parcels;

**Whereas**, the settlement which is the subject matter of this Consent Decree contemplates the environmental remediation of Study Area 6 South and redevelopment of the parcels that comprise Study Areas 6 and 7 to create a major mixed use project in an important section of Jersey City; and

**Whereas**, each of the actions to implement this Consent Decree have been fully considered by the Honeywell, the Riverkeeper, and Jersey City as a means to accomplish the aforesaid purposes of this settlement:

NOW, THEREFORE, IT IS HEREBY ORDERED AND DECREED AS FOLLOWS:

## ARTICLE I: DEFINITIONS

For purposes of this Consent Decree, the following terms shall have the meanings set forth in this Article:

1. **"20 to 1000 Soils"** shall mean those soils containing less than 1000 mg/kg of hexavalent chromium, but greater than 20 mg/kg. **"20 to 240 Soils"** shall mean those soils containing less than 240 mg/kg of hexavalent chromium, but greater than 20 mg/kg.

2. **Bayfront Redevelopment LLC** shall have the meaning set forth in paragraph 4.1 of the Jersey City/Honeywell Consent Order.

3. **COPR** shall mean Chromite Ore Processing Residue.

4. **Chromium Remedy or Chromium Remediation** shall mean the remedy set forth in Article III.

5. **Consolidated Litigation** shall mean *Jersey City Municipal Utility Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5955 (DMC), *Jersey City Incinerator*

*Authority v. Honeywell International Inc.*, D.N.J., Civ. No. 05-5993 (DMC), and *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-022 (DMC).

6. The **Court** shall mean the United States District Court of the District of New Jersey, which has jurisdiction over the Consolidated Litigation.

7. **Deep Groundwater Consent Order** shall mean the Deep Overburden and Bedrock Groundwater Remedies Consent Order entered by the Court on September 3, 2008, in both *ICO v. Honeywell* and the Consolidated Litigation.

8. **Deep Groundwater Remedy** shall mean the deep overburden and bedrock groundwater pump and treat remedy as required by the Order Approving the Deep Overburden Groundwater Remediation, entered on October 6, 2006, the Stipulation on Consent Regarding the Schedule for Implementation of Deep Groundwater Remedial Actions, entered on August 15, 2008, in *ICO v. Honeywell,* and the remedies required under the Deep Groundwater Consent Order.

9. **Development Area of Concern** ("AOC") shall mean those portions of Study Area 6 South in which the hexavalent chromium concentration in the top 20 feet of soil below ground surfaces exceeds a concentration of 20 mg/kg, and for which future uses of the property may include commercial or residential development. The Open Space AOC shall not be part of the Development AOC and vice versa. The Development AOC consists of two parts: the Kellogg Street Development AOC and the Site 163 Development AOC. Collectively, the two parts shall be referred to as the "Development AOC." The approximate boundaries of the Development AOC as a whole and its two parts are shown on Exhibit A, but the boundaries may be further defined in the implementation of the Chromium Remedy. For the Kellogg Street Development AOC, remedial measures shall assume only a residential use. For the Site 163 Development AOC, remedial measures shall be implemented with the goal of unrestricted use, but limitations

on future uses (including prohibiting residential use) in some or all of the Site 163 Development AOC may be part of the remedy as set forth in paragraph 61.

10. **Hackensack River Watershed Land Trust** shall mean the dedicated fund of the Hackensack Riverkeeper, Inc., established under Section 501(c) of the Internal Revenue Code for the purpose of acquiring and preserving open space within the Hackensack River watershed and administered by the Board of Trustees of the Hackensack Riverkeeper, Inc.

11. **Honeywell** shall mean Honeywell International Inc. and its affiliates, including 425-445 Route 440 Property LLC, Kellogg Street 80 Property LLC, Kellogg Street 60 Property LLC, and Kellogg Street/440 Property LLC.

12. **Honeywell's Treatment Plant** shall mean the treatment plant currently located at 80 Kellogg Street that is used to treat, *inter alia*, chromium contaminated groundwater.

13. ***ICO v. Honeywell*** shall mean *Interfaith Community Organization v. Honeywell International Inc.*, D.N.J., Civ. No. 95-2097 (DMC).

14. **Including** shall mean including, but not limited to.

15. **JCIA** shall mean the Jersey City Incinerator Authority.

16. **JCMUA** shall mean the Jersey City Municipal Utilities Authority.

17. **Jersey City Entities** shall mean the City of Jersey City, including the Department of Public Works ("DPW") and other agencies and branches thereof, the JCIA, and the JCMUA.

18. **Jersey City/Honeywell Consent Order** shall mean the Settlement Consent Order by and between the Jersey City Entities and Honeywell International Inc. entered in the Consolidated Litigation on April 21, 2008.

19. **"L-Well Groundwater"** shall mean the groundwater found at the depth of the "L" wells on and near the former bowling alley property, NJDEP Site 124, located at 427 Route 440. The L-Well Groundwater is located within what has been referred to as the plume diversion area.

20. **NJDEP** shall mean the New Jersey Department of Environmental Protection.

21. **NJDEP Chromium Directive** shall mean the Chromium Directive issued by NJDEP on February 8, 2007, and attached as Exhibit B.

22. **Open Space AOC** shall mean the portion of Study Area 6 South that is identified as The Promenade park and Grand Boulevard extending from Route 440 to the Hackensack River on page 39 of the Redevelopment Plan and for which the future uses of the property shall be restricted pursuant to paragraph 74, following remediation pursuant to paragraph 65. The Development AOC shall not be part of the Open Space AOC and vice versa. The approximate boundaries of the Open Space AOC are shown on Exhibit A, and the boundaries may be further defined in the implementation of the Chromium Remedy.

23. **Party or Parties** shall mean any one or all of the signatories to this Consent Decree.

24. **RCRA** shall mean the Resource Conservation and Recovery Act, 42 U.S.C. § 6901, *et seq.*, as amended.

25. **Redevelopment Area** shall mean Study Area 6 North, Study Area 6 South, and Study Area 7, collectively.

26. **Redevelopment Law** shall mean the New Jersey Local Redevelopment and Housing Law, N.J.S.A. § 40A:12A1, *et seq.*, as amended and supplemented.

27. **Redevelopment Plan** shall mean the Bayfront I Redevelopment Plan as adopted by Jersey City on March 12, 2008.

28. **Remedial Investigation Work Plan Addendum or RIWP Addendum** shall mean the "Remedial Investigation Work Plan Addendum Study Area 6 South" submitted to NJDEP on June 27, 2008.

29. **Riverkeeper** shall mean the plaintiffs in *Hackensack Riverkeeper, Inc. v. Honeywell International Inc.*, D.N.J., Civ. No. 06-22 (DMC), and includes the Hackensack Riverkeeper, Inc., William Sheehan, Reverend Winston Clarke, and Lawrence Baker.

30. **Sediment Consent Order** shall mean the Consent Order on Sediment Remediation and Financial Assurances, entered by the Court in *ICO v. Honeywell* and this Consolidated Litigation on May 28, 2008.

31. **Shallow Groundwater** or **Shallow Level of Groundwater** shall mean groundwater above the meadow mat, groundwater at stratigraphically equivalent depths in locations where there is no meadow mat, and groundwater that is contaminated by recent contact with COPR or other chromium soil contamination above the meadow mat and subsequently flows downward through or past the meadow mat into the upper portion of the lacustrine sediments. This does not include groundwater found in the bedrock, the deep zone, or any plume of contamination that is in both the intermediate and deep zones, as those zones are defined in the Final Groundwater Investigation Report, prepared in *ICO v. Honeywell*, dated February 2007, p. 1-2.

32. **Site** shall mean Study Area 6 South.

33. **Site Preparation Activities** shall mean those activities necessary to begin implementation of the Chromium Remedy in Article III of this Consent Decree, including, if appropriate, the temporary or permanent relocation of current activities and operations conducted on Study Area 6 South.

34. **Soil** shall mean soils, historic fill, and/or COPR.

35. The **Special Master** shall mean Senator Robert G. Torricelli, appointed as the Special Master in *ICO v. Honeywell* and the Consolidated Litigation, and his successors or whomever the Court may appoint as Special Master.

36. **Stratum O** shall mean the layer composed of soft brown silty fine sand interlayered with soft gray silty clay and fine sandy to clayey silt generally located above the meadow mat below the Historic Fill and/or COPR.

37. **Study Area 5** shall mean that property comprising Sites 79, 90, 117, 153, and 184 of the Chromate Chemical Production Waste Sites designated by NJDEP, comprising approximately 42 acres and including (a) all such property owned by Bob Ciasulli consisting of Block 1291, Lot 76, and Block 1292, Lots 1F, 47, 48, 53, and 54PL, located at 540 Route 440, Jersey City, New Jersey, (b) all such property owned by Elisabeth and Rafael Rosario consisting of Block 1292, Lot 49, located at 93 Fisk Street, Jersey City, New Jersey, (c) all such property owned by Michael Vo consisting of Block 1292, Lot 50, located at 95 Fisk Street, Jersey City, New Jersey, (d) all such property owned by NJCU consisting of Block 1286, Lots 5 and 6D and Block 1286.5, Lots 1 and 2, Jersey City, New Jersey, (e) all such property owned by Inland Southeast Jersey City LLC consisting of Lot 1, Block 1285.5 located at 440 Route 440, Jersey City, New Jersey, and (f) all such property owned by 425/445 Route 440 Property LLC, consisting of Block 1289.5, Lot E, Jersey City, New Jersey.

38. **Study Area 6 North** shall mean the property comprising Sites 87 and 88 of the Chromate Chemical Production Waste Sites designated by NJDEP, which is subject to the Study Area 6 North Consent Decree.

39. **Study Area 6 North Consent Decree** shall mean the Consent Decree and Order Regarding Remediation and Redevelopment of Study Area 6 North, entered by the Court on April 21, 2008, in the Consolidated Litigation.

40. **Study Area 6 South** shall mean (a) that property currently owned by Bayfront Redevelopment Property LLC consisting of Site 73, located at 200 Kellogg Street Jersey City, Hudson County, New Jersey; (b) that property currently owned by Bayfront Redevelopment LLC consisting of Site 134, located at 100 Kellogg Street Jersey City, Hudson County, New Jersey; (c) that property currently owned by Bayfront Redevelopment LLC consisting of Site 140 located at 80 Kellogg Street Jersey City, Hudson County, New Jersey; (d) that property currently owned by Bayfront Redevelopment LLC consisting of Site 125, located at 60 Kellogg Street Jersey City, Hudson County, New Jersey; (e) that property currently owned by Bayfront Redevelopment LLC consisting of Site 124, Jersey City, Hudson County, New Jersey; (f) that property currently owned by Kellogg St/Harsimus Cove Realty located at 150 Kellogg Street, Jersey City, Hudson County, New Jersey, (g) that property currently owned by Bayfront Redevelopment LLC located at 38 Kellogg Street, Jersey City, Hudson County, New Jersey; (h) that property currently owned by Bayfront Redevelopment LLC located at 28 Kellogg Street, Jersey City, Hudson County, New Jersey; and (i) that property currently owned by Bayfront Redevelopment LLC, consisting of Site 163, formerly the Colonial Concrete Company, located at 75 Kellogg Street in Jersey City, Hudson County, New Jersey.

41. **Study Area 6** shall mean Study Area 6 North and Study Area 6 South, collectively.

42. **Study Area 7** shall mean (a) that property currently owned by Bayfront Redevelopment LLC located at 425 and 445 Route 440, Jersey City, Hudson County, New Jersey, and (b) that

property currently owned by Bayfront Redevelopment LLC located at 465 Route 440, Jersey City, Hudson County, New Jersey.

43. **Technical Requirements for Site Remediation** shall mean the NJDEP Technical Requirements for Site Remediation, N.J.A.C. Chapter 26E, as duly and properly promulgated and amended.

44. **Unrestricted Use** shall mean that the contaminated medium is restored to a condition or quality suitable for all uses.

## ARTICLE II: SCOPE OF THE CONSENT DECREE, JURISDICTION, AND CLAIMS RESOLVED

45. This Court has jurisdiction over the Parties and subject matter of the Consolidated Litigation pursuant to Section 6972 of RCRA.

46. For purposes of this Consent Decree, the Riverkeeper Complaint in the Consolidated Litigation states claims upon which relief may be granted against Honeywell.

47. In the event that this Decree is not terminated by one or more Parties pursuant to paragraph 113, this Consent Decree resolves, settles, and satisfies all claims by Riverkeeper against Honeywell with respect to soils, shallow groundwater and L-Well groundwater at Study Area 6 South. This Consent Decree does not resolve any claims by Riverkeeper against Honeywell with respect to Study Area 5 or property owned by Regnal Realty consisting of Block 1288.2, lot 1, located at 420 Route 440, Jersey City, New Jersey.

48. Nothing in this Consent Decree shall be construed or interpreted to waive any claim or defense any Party has asserted or may assert against any third party in the Consolidated Litigation except as explicitly stated herein.

49. This Consent Decree does not constitute an admission of liability on the part of any Party with respect to any claims, cross-claims, or counter-claims in the Consolidated Litigation.

## ARTICLE III: CHROMIUM REMEDIATION

### A. General Terms and Requirements

50. **Responsibility for Implementation of Chromium Remediation.** As between the Parties, Honeywell shall be responsible for and shall undertake remediation of COPR and chromium present in Study Area 6 South at Honeywell's sole cost and expense. Remediation of COPR and chromium present in Study Area 6 South shall be undertaken in accordance with the terms of this Consent Decree.

51. **Designation of Chromium Areas of Concern.** For the purposes of remediation, Study Area 6 South shall consist of two AOC's, designated as the Open Space AOC and the Development AOC as shown approximately on Exhibit A. The exact boundaries of the two AOC's shall be subject to further delineation during the design and implementation of the Chromium Remedy.

52. **Consistency of the Chromium Remedy with NJDEP Guidance and Remedial Action Work Plan.** The Chromium Remedy shall be consistent with the NJDEP Technical Requirements for Site Remediation, the Chromium Directive as issued by NJDEP on February 8, 2007 ("the NJDEP Chromium Directive"), and any Remedial Action Work Plan, including any modifications or addenda approved by NJDEP. Prior to submitting any Remedial Action Work Plan, Honeywell shall take all reasonable steps to ensure that the plan is consistent with the Chromium Remedy. However, this Consent Decree shall have precedence over any Remedial Action Work Plan in the event of any inconsistency. The approved Remedial Action Work Plan is a minimum standard, and the Chromium Remedy may be more protective than the remedy NJDEP approves.

53. **General Scope of the Chromium Remedy.** The Chromium Remedy shall address shallow groundwater and L-Well groundwater containing total chromium concentrations of 70 µg/l or greater and soil containing hexavalent chromium at concentrations of 20 mg/kg or greater within the top 20 feet of soil below the ground surface, and shall be consistent with the requirements set forth in this Article. The Chromium Remedy set forth in this Consent Decree addresses only the shallow and L-Well levels of groundwater (see paragraphs 69 - 72). The deep overburden and bedrock groundwater remediation, including source control, is addressed in the Deep Groundwater Consent Order.

54. **Development of a Schedule for the Chromium Remedy.** The Chromium Remedy shall be carried out diligently, and the development and implementation of any remedy required by NJDEP for non-chromium contamination shall not delay satisfaction of the milestones in the Schedule established pursuant to this paragraph. Within 90 days of entry of this Consent Decree, Honeywell shall propose a Master Schedule for the implementation of the Chromium Remedy .

(a) The Master Schedule shall incorporate the following dates:

(i) No later than August 15, 2008, Honeywell shall submit a Chromium Impacted Soils Pilot Test Work Plan to NJDEP and Riverkeeper;

(ii) No later than September 15, 2008, Honeywell shall complete field work in accordance with the RIWP Addendum;

(iii)No later than December 31, 2008, Honeywell shall submit an Initial Treatment Study Report and Remedial Action Work Plan pursuant to paragraph 86(c);

(iv) No later than July 31, 2012, Honeywell shall submit the soil and groundwater data from its 2010 and 2011 supplemental investigation of Site 163, a brief summary report, and

a designation of the boundaries of the Site 163 Development AOC to the Special Master pursuant to paragraph 86(c);

(v) No later than October 1, 2012, Honeywell shall submit an addendum to the Study Area 6 South 100% Design setting forth the 100% Design for the Site 163 Development AOC portion of the Study Area 6 South Chromium Remedy; and

(vi) Honeywell shall undertake, in good faith, to begin implementation of the Chromium Remedy by March 1, 2013.

(b) In addition, the Master Schedule shall propose deadlines for the following milestones:

(i) Submission of all documents subject to submission and review pursuant to paragraph 86(c);

(ii) Completion of those Site Preparation Activities necessary for the implementation of the Chromium Remedy;

(iii)Submission, following implementation of the soil components of the Chromium Remedy for the Development AOC, of the groundwater plans and reports required by paragraphs 70 and 72;

(iv)Completion of additional sampling for shallow groundwater delineation pursuant to paragraph 71 and a proposal for a remedy pursuant to paragraph 71, if needed;

(v) The submission of a 50% Design Report for the Chromium Remedy;

(vi) The submission of a 100% Design Report for the Chromium Remedy;

(vii) The date for completion of the installation of the Chromium Remedy;

(viii)Implementation of the long-term protections of the Open Space AOC established pursuant to paragraph 74; and

(ix) Transfer of the Open Space AOC to Jersey City pursuant to paragraph 74(a)(iii).

### B. Initial Chromium Remedy Steps: Delineation, Treatment Study, and Remedial Action Work Plan

55. **Delineation of Development AOC.** Honeywell shall conduct further soil sampling on Study Area 6 South in accordance with the RIWP Addendum. In addition to the locations set forth in the RIWP Addendum, Honeywell shall conduct further soil sampling pursuant to the provisions of the RIWP Addendum at the boring locations set forth in Exhibit E. Upon completion of the soil sampling required by this paragraph, Honeywell shall submit a Second Supplemental Remedial Investigation Report that sets forth the results of the sampling and Honeywell's proposal as to the delineation of the Development AOC. In conjunction with its proposal, Honeywell shall set forth its rationale as to whether prior sampling data should be included or excluded in the proposed delineation. The soil sampling and submission of a Second Supplemental Remedial Investigation Report shall be completed in accordance with the Schedule set forth in paragraph 54. Honeywell shall submit the Second Supplemental Remedial Investigation Report pursuant to paragraph 86(c). The Site 163 Development AOC shall be exempt from the requirements of paragraphs 55-58.

56. **Conduct of a Treatment Study in the Development AOC.** Honeywell shall conduct a field study of the efficacy of *in situ* treatment of 20 to 1000 Soils in accordance with the Chromium Impacted Soil Pilot Test Work Plan. The purpose of the pilot test shall be to evaluate whether *in situ* chemical treatment of 20 to 1000 Soils with one or more reductants can result in the permanent establishment of hexavalent chromium concentrations below 20 mg/kg under conditions in those areas of the Development AOC that may be subject to treatment as a remedy. Honeywell shall provide the raw data from the pilot test to NJDEP and Riverkeeper in scientifically useable electronic form as soon as the data become available. Honeywell shall

submit an Initial Treatment Study Report setting forth the initial results of the pilot test pursuant to paragraph 86(c) .

57. **Continued Monitoring of the Treatment Study.** As the result of the need to complete Study Area 7 remediation, to maintain Study Area 7 remediation support operations currently located on Study Area 6 South, and to conduct Site Preparation activities including the relocation of operating businesses on Study Area 6 South in advance of implementation of the Chromium Remedy, the Parties do not anticipate that implementation of field work for the Chromium Remedy will begin until March 1, 2013. Honeywell shall continue to monitor the performance of the pilot test and shall submit a Final Treatment Study Monitoring Report assessing the long term effectiveness of treatment for 20 to 1000 Soils in the Development AOC pursuant to paragraph 86(c) no later than December 31, 2011.

58. **Submission of a Remedial Action Work Plan.** On or before December 31, 2008, Honeywell shall submit a Remedial Action Work Plan for the Chromium Remedy pursuant to paragraph 86(c). The Remedial Action Work Plan shall be consistent with the Chromium Remedy set forth in this Consent Decree.

### C. Development AOC Soil Remedy

59. **Remedial Components.** In the Development AOC, soils containing hexavalent chromium at concentrations greater than 20 mg/kg shall be remediated as follows:

(a) Soils with a concentration greater than 1000 mg/kg shall be:

(i) Excavated and disposed of off-site at a waste disposal facility licensed to accept such waste; or

(ii) Treated *ex situ* and consolidated under the cap in the Open Space AOC provided the requirements of paragraphs 60 and 63 are satisfied and provided that such soils do not

require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a).

(b) 20 to 1000 Soils shall be:

(i) Excavated and consolidated within the Open Space AOC provided that such soils do not require venting of gases and do not serve as the basis for gas venting as set forth in paragraph 65(a); or

(ii) Excavated and disposed of off-site pursuant to the requirements of paragraph 59(a); or

(iii) Remediated pursuant to paragraphs 59(c) or 59(d) provided that such soils are also 20 to 240 soils and meet the requirements of paragraphs 59(c) or 59(d).

(c) 20 to 240 Soils may be remediated by excavation and consolidation within the Study Area 6 North AOC 1 Open Space Area, provided that such soils do not require venting of gases and shall not serve as the basis for the inclusion of gas venting as part of the Study Area 6 North AOC 1 Open Space Area remedy.

(d) 20 to 240 Soils within the Site 163 Development AOC may be remediated by *in situ* treatment, provided the requirements of paragraph 61 are satisfied.

60. **Treatment and Consolidation of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** *Ex situ* treatment and consolidation under the Open Space AOC cap may be used as a remedial component for soils containing greater than 1000 mg/kg hexavalent chromium provided that the requirements of this paragraph are satisfied:

(a) Honeywell demonstrates in the Final Treatment Study Monitoring Report that the proposed treatment will likely result in the reduction of the hexavalent chromium concentration of the treated soils such that the post-treatment total chromium concentration shown by Toxicity

Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C);

(b) Following a review of the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d), NJDEP agrees that Honeywell has made the demonstration required by paragraph 60(a).

(c) Plaintiffs have had an opportunity to review and comment on the demonstration required by paragraph 60(a) pursuant to the NJDEP review process set forth in paragraph 86(d)and pursuant to the Special Master review process set forth in paragraphs 86(e)-86(f); and

(d) Following review of the demonstration required by paragraph 60(a) pursuant to the Special Master review process set forth in paragraph 86(f), the Special Master issues a recommendation finding that Honeywell has made the demonstration required by paragraph 60(a) or the Court finds that Honeywell has made the demonstration required by paragraph 60(a) in the event that any Party seeks the Court's review of the Special Master's recommendations under this paragraph.

61. **Treatment as a Remedial Component for 20 to 240 Soils.** *In situ* treatment may be used as a remedial component for the 20 to 240 Soils in the Site 163 Development ACO, provided that such soils are 3 feet or more below ground surface and the requirements of this paragraph are satisfied:

(a) If Honeywell elects to treat *in situ* 20 to 240 Soils in the Site 163 Development AOC, Honeywell shall include in the 100% Design Addendum for Site 163 a plan for such treatment. Such treatment plan shall be comparable in detail and approach to the pipeline treatability plan which is Appendix F to the Study Area 6 North 100% Design. The goal of such *in situ* treatment

shall be to reduce hexavalent chromium soil concentrations to less than 20 mg/kg in soils 20 feet or less below ground surface;

(b) Three years after conducting the treatment set forth in subparagraph (a), Honeywell shall collect additional soil samples in the treated areas to evaluate the success of the treatment. These soil samples shall be analyzed for EH, pH, hexavalent chromium (using EPA/NJDEP Methods 3060A/7199), and sulfides (using EPA Method 9030B). Within 60 days of its receipt of the final data from such sampling, Honeywell shall submit a report with such data to the Special Master pursuant to paragraph 86(c);

(c) In the event that the sampling pursuant to subparagraph (b) shows that soils with greater than 20 mg/kg hexavalent chromium remain or that excess treatment reductant remains present, Honeywell may elect to pursue one or more of the following approaches after providing notice to the Special Master, Riverkeeper and the Jersey City Entities;

(i) In the case of excess treatment reductant remaining in the soil, continue to monitor such areas pursuant to subparagraph (b) until the excess reductant is no longer present;

(ii) In the case of soils with greater than 20 mg/kg hexavalent chromium:

(1) Excavate such soils and consolidate them under the cap in the Open Space AOC, consolidate them under the cap in the Study Area 6 North AOC 1 Open Space Area, and/or dispose of them off-site provided that in each instance the applicable requirements of paragraph 59 are satisfied;

(2) Conduct further *in situ* treatment using additional treatment reductant and submit a monitoring plan pursuant to paragraph 64; or

(3) In the event that the soils are within the areas depicted as River Front Park, Riverfront Drive or Kellogg Street on page 39 of the Redevelopment Plan, cover the affected

soils with a road, walkway, and/or other hardscape and restrict the use of that area through each of the following institutional controls:

(a) Issuance and recording of a conservation restriction comparable to that required under paragraphs 74(b) and 74(d);

(b) Transfer of title to that area to Jersey City pursuant to paragraphs 74(a)(iii) through 74(a)(iv)(2); and

(c) Issuance and recording of a deed notice comparable to that required under paragraphs 74(c) and 74(d).

62. **Submissions Related to Site 163.** Pursuant to the Schedule, Honeywell shall prepare and submit the following with regard to Site 163:

(a) A summary report of all chromium soil and groundwater data collected during site investigations in 2010 and 2011; and

(b) An addendum incorporating Site 163 into the 100% Design.

63. **Post-Treatment Analysis of Soils Containing Greater than 1000 mg/kg Hexavalent Chromium.** In the event that *ex situ* treatment is used as a final remedy for any portion of the soils containing greater than 1000 mg/kg pursuant to paragraph 59(a)(ii), Honeywell shall conduct post-treatment analysis of each treated batch of soil to demonstrate that the treatment has resulted in the reduction of the hexavalent chromium concentration such that the post-treatment total chromium concentration shown by Toxicity Characteristic Leaching Procedure SW-846, Test Method 1311, is less than 5 mg/l and the soils are no longer classified as hazardous waste under 40 C.F.R. 261.24 (Subpart C). Such monitoring and demonstration shall be made prior to consolidation of the treated soils under the Open Space AOC cap pursuant to paragraph 59(a)(ii). In the event that Honeywell fails to make the demonstration required by this paragraph,

Honeywell shall dispose of the soils off-site at a waste disposal facility licensed to accept such waste.

64. **Post-Treatment Monitoring for 20 to 1000 Soils.** In the event that *in situ* treatment is used as a final remedy for any portion of the 20 to 1000 Soils, Honeywell shall conduct post-treatment monitoring to demonstrate that the treatment has resulted in permanent hexavalent chromium concentrations of less than 20 mg/kg in the treated area. Honeywell shall propose a program of post-treatment monitoring in a document that is submitted pursuant to paragraph 86(c). In the event that Honeywell fails to make the demonstration required by this paragraph, Honeywell shall propose further remedial actions pursuant to paragraph 59 in a document that is submitted pursuant to paragraph 86(c).

**D. Open Space AOC Components of the Chromium Remedy**

65. **Open Space AOC Soil Remedy.** In the Open Space AOC, the soil remedy shall consist of an engineered RCRA cap to isolate contaminated soils with gas venting, if necessary, to address the generation of methane and other naturally occurring gases in the Stratum O and/or Stratum D in the Open Space AOC. Soils consolidated under the cap, pursuant to paragraph 59(b)(i), shall not require gas venting and shall not be the basis for the inclusion of gas venting as a component of the cap. The cap shall be designed and constructed so that:

(a) The cap shall consist of a gas collection system, if gas venting is necessary, a base protective layer, an impervious geomembrane liner with a minimum thickness of 40 mil; a geocomposite drainage layer; a filter fabric; and a distinctive colored warning layer with markings in English and Spanish that would deter penetration of the cap in the event that digging occurred in the vicinity of the cap;

(b) All utilities, including those supporting the pump-and-treat system for groundwater remediation, with the exception of any extraction wells or collection trenches, shall be placed above the cap (but may be below the ground surface and/or contained within utility corridors). In the event that above-cap-grade gas collection and treatment is selected or is needed to meet current or future regulatory requirements, such collection and treatment facilities are prohibited in the Open Space AOC, except for piping to connect the sub-liner collection system with the treatment facilities; and

(c) Exclusive of roadways, the cap shall be overlain by layers of clean fill, backfill and/or overburden with an average depth of at least three feet and a minimum depth of at least two feet provided that any layer that incorporates overburden shall be below at least two feet of clean fill. Any clean fill or backfill soil brought to the Site will either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master. One foot of clean fill, covered with bituminous blacktop, shall be sufficient cover where roads, walkways, or other paved surfaces are located within the Open Space AOC. All clean soil fill in areas that will not involve paved roads, walkways, or other paved surfaces shall be vegetated in such a manner as to protect and maintain the required depth of the clean soil fill and to ensure that such vegetation shall not cause any interference with or penetration of the cap.

(d) The existing overburden soils in the Open Space AOC shall first be stripped off and set aside for use. If hexavalent chromium concentrations in the overburden exceed 20 mg/kg, the overburden shall be placed under the cap. If hexavalent chromium concentrations in the overburden do not exceed 20 mg/kg, the overburden may be placed above the cap but below the

two feet of clean fill required by paragraph 65(c). Excavated 20 to 1000 Soils from the Development AOC shall be placed and spread in the Open Space AOC under the cap. Both the chromium impacted soils and the previously stripped overburden shall be suitably compacted according to design specifications. Debris, to the extent it would interfere with the compaction specification requirements of the 100% Design, shall not be placed under the cap. The engineered cap shall be installed over the chromium-impacted soils exceeding 20 mg/kg hexavalent chromium.

**E. Demolition, Grading, and Backfill Requirements**

66. **Demolition and Grading Activities.** During demolition and grading activities, adequate protective measures shall be taken to protect site workers and the community from airborne dusts and exposures to contaminated soils.

67. **Backfill Requirements.** Soils excavated from the Development AOC shall be replaced with backfill soil. Any backfill soil brought to the Site shall either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with a beneficial soil reuse plan that is approved by NJDEP and subject to review and comment by the Parties and approval by the Special Master.

68. **Vegetation of Clean Fill.** All clean soil fill in areas that will not involve paved roads, sidewalks, paths, walkways, or building structures shall be vegetated in such a manner to protect and maintain the required depth of clean soil fill.

**F. Groundwater Components of the Chromium Remedy**

69. **Shallow Groundwater Remedy for the Open Space AOC.** The Open Space AOC shallow groundwater remedy shall consist of hydraulic barriers with a pump-and-treat system designed to isolate shallow groundwater and to intercept and treat shallow groundwater flowing

above the meadow mat in the Open Space AOC to the extent that such groundwater contains total chromium in concentrations in excess of 70 µg/l. The shallow groundwater remedy shall consist of the following:

(a) The existing soil/cement/bentonite wall on the boundary of Study Area 6 South and Study Area 7 shall be incorporated into the other engineering controls;

(b) Subterranean slurry walls or other hydraulic barriers shall be installed along the southern, eastern and western sides of the Open Space AOC and keyed into the meadow mat or Stratum O or to comparable depths below ground surface;

(c) A groundwater extraction system shall be established that shall consist of (i) one or more shallow extraction wells, sumps, or french drains within the Open Space AOC; (ii) pumps; and (iii) underground piping to convey any extracted water to Honeywell's Treatment Plant;

(d) The capture zone for the shallow groundwater remedy shall include at least the entire area of contaminated shallow groundwater within the Open Space AOC;

(e) A plan for control of water levels shall be developed;

(f) In the event that underground structures are demolished, the plans shall address the need for special attention for structures that extend below the meadow mat in order to control needed water levels; and

(g) Honeywell shall submit such information as is required to allow NJDEP to establish a classification exception area for groundwater at the Site, in accordance with NJDEP regulations.

70. **The Shallow Groundwater Remedy for the Development AOC.** Following implementation of the Development AOC soil components of the Chromium Remedy, Honeywell shall submit a report to (a) determine whether shallow groundwater remaining in the

Development AOC exceeds 70 µg/l total chromium and, (b) if so, evaluate the need for further remedial measures to address any such shallow groundwater remaining in the Development AOC with total chromium concentrations in excess of 70 µg/l. This evaluation shall be subject to review and comment by the Parties and approval by the Special Master.

(a) In the event that the evaluation demonstrates that further remedial measures are necessary, Honeywell shall propose such measures subject to review and comment by the Parties and approval by the Special Master;

(b) The capture zone of any remedy shall include at least the entire area of contaminated shallow groundwater except for shallow groundwater that is captured and subject to the shallow groundwater remedy for the Open Space AOC pursuant to paragraph 69;

(c) In the event that a pump-and-treat system is selected as a contingency measure for shallow groundwater in the Development AOC, all infrastructure for the pump-and-treat contingency system that is needed to ensure that the contingency system is fully operational, as required by paragraph 70(d), shall be installed prior to or in conjunction to any development of the Site. This includes at least one shallow extraction well, sump, or french drain, and the piping to convey any extracted groundwater to Honeywell's water treatment plant;

(d) If it is determined that the pump-and-treat contingency system must be activated, the pump-and-treat system shall be operational no later than six months after the date of the determination.

71. **Off-Site Shallow Groundwater Remedy.** Honeywell shall propose additional sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site. Honeywell shall submit a report of the results of such sampling and, in the event that contaminated shallow groundwater is found to extend off-site, a proposal for a remedy based on

such results. The report and the proposal for a remedy shall be subject to review and comment by the Parties and approval by the Special Master.

72. **L-Well Groundwater Remedy.** At the time this Decree is entered, the L-Well Groundwater is contained and not contributing to further contamination of surrounding waters and/or soils. However, in order to verify that this status continues following implementation of the Chromium Remedy, including any groundwater remedial measures pursuant to paragraphs 70 and 71, Honeywell shall propose a plan for one round of monitoring designed to evaluate whether the L-Well Groundwater remains contained. The plan shall include monitoring for total and hexavalent chromium and major ion chemistry to determine whether there has been movement in the L-Well Groundwater.

(a) In the event that no substantial change is detected in the major ion chemistry, no further action is required unless paragraph 72(c) is applicable.

(b) In the event that substantial changes are detected in the major ion chemistry, Honeywell shall propose a plan for further monitoring of the L-Well Groundwater. Such a plan shall be subject to review and comment by the Parties and approval by the Special Master.

(c) In the event that the initial monitoring or monitoring conducted pursuant to paragraph 72(b) demonstrates that proximate waters have total chromium concentrations in excess of 70 µg/l, regardless of whether there is a change in the major ion chemistry, Honeywell shall propose a remediation plan for the L-Well Groundwater. Such remediation plan shall be subject to review and comment by the Parties and approval by the Special Master.

### G. Permits and Authorizations

73. **Permits and Authorizations.** Honeywell shall obtain all necessary federal, state, and local permits and authorizations to carry out the Chromium Remedy as set forth in this Article.

## H. Long-Term Monitoring, Maintenance, and Protection of Engineering and Institutional Controls

74. **Protection of the Open Space AOC.** Except as provided in paragraphs 74(j) and 74(k), development in the Open Space AOC shall be prohibited. The Open Space AOC shall be protected against activities that may jeopardize the integrity of the cap and/or the groundwater remedial measures that shall be installed in the Open Space AOC pursuant to the Chromium Remedy or that may impede the long-term monitoring and maintenance of the cap and/or groundwater remedial measures. It is the intention of the Parties to implement different layers of protection, which alone or in concert, impose restrictions on development, run with the land, and survive all parties. Accordingly, the following actions shall be taken pursuant to the Schedule provided in paragraph 54:

(a) **Ownership of and Access to the Open Space AOC.** Ownership of and access to the Open Space AOC shall be in accordance with the following:

(i) Bayfront Redevelopment LLC, as the current owner in fee simple absolute of all property that comprises the Open Space AOC, shall not convey any rights or interests in any parcel that comprises the Open Space AOC property except as provided in this Decree. Within 90 days of entry of this decree, Bayfront Redevelopment LLC shall give Jersey City an option to buy all of the Open Space AOC property prior to the planned transfer pursuant to paragraph 74(a)(iii). Such option to buy shall be subject to the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall exercise the option to buy the Open Space AOC in the event that the conditions allowing for withdrawal of funds from the financial assurance mechanisms under paragraphs 98(c) or 98(d) are met;

(ii) Within 90 days of the entry of this Consent Decree, Bayfront Redevelopment LLC shall grant a conservation restriction for the Open Space AOC pursuant to the requirements of paragraph 74(b);

(iii) Upon the final construction of all roads and utility corridors within the Open Space AOC, Bayfront Development LLC shall donate good and marketable title to all the land comprising the Open Space AOC to Jersey City. In conjunction with such donation, Bayfront Redevelopment LLC shall petition to subdivide the properties within Study Area 6 South to create a new parcel(s) comprising the Open Space AOC. At the time of the donation, Jersey City shall grant Honeywell an easement for the purpose of monitoring and maintaining the Chromium Remedy. Jersey City shall also grant Honeywell all necessary access to the Open Space AOC by license or such other mechanisms as may be appropriate for purposes of monitoring and maintaining the Chromium Remedy. After it acquires title pursuant to this paragraph, Jersey City shall retain ownership of the Open Space AOC unless and until it shall have complied with the requirements of paragraph 74(a)(iv);

(iv)After it acquires title pursuant to this paragraph, Jersey City shall not convey or enter into any lease of the Open Space AOC to any other person or entity unless it has first satisfied either of the following conditions:

(1) Jersey City has obtained the Special Master's (or if the Special Master's appointment has expired, the Court's) approval to convey the Open Space AOC to a government entity that has the capacity and willingness to fulfill Jersey City's obligations under the Consent Decree with respect to the Open Space AOC and such entity agrees to submit to the Court's jurisdiction and to be bound by the requirements of the Consent Decree that Jersey City has committed to fulfill with respect to protection of the Open Space AOC pursuant to this paragraph

and routine maintenance of the permissible development in the Open Space AOC pursuant to paragraph 78(d); or

(2) The Open Space AOC has been remediated such that no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive, and Jersey City has demonstrated to the Special Master and/or the Court, as appropriate, that such remediation has been completed in accordance with all applicable requirements.

(b) **Conservation Restriction.** Prior to the grant of the option to buy pursuant to paragraph 74(a)(i), Bayfront Redevelopment LLC shall grant an open space conservation restriction, pursuant to N.J.S.A. 13:8-B-1, *et seq.*, over the Open Space AOC substantially in the form set forth in Exhibit C. Exhibit C is a conservation restriction that is consistent with the terms of this paragraph and this Consent Decree. The conservation restriction shall allow for the implementation, maintenance, monitoring, repair and replacement of the Chromium Remedy and development consistent with paragraphs 74(j) and 74(k), including the construction and placement of roads and utilities. The Conservation Restriction shall also allow for current uses of the Open Space AOC to continue until such time as construction of the Chromium Remedy begins. The Hackensack River Watershed Land Trust shall be the primary holder of the conservation restriction, with all rights of monitoring and enforcement. Riverkeeper shall propose an entity to serve as the secondary holder of the conservation restriction subject to comment by the Parties and review by the Special Master. The secondary holder shall have secondary rights of monitoring and enforcement.

(i) The conservation restriction shall be incorporated into this Consent Decree and made part of this Consent Decree. The final, executed conservation restriction shall be lodged with the Court and entered as an order of the Court. The conservation restriction shall be enforceable in this Court, in the same manner as this Consent Decree.

(ii) The conservation restrictions provided under this Consent Decree shall be consistent with the prohibited and permitted development of the Open Space AOC as set forth in paragraphs 74(j) and 74(k) below.

(iii) Jersey City shall not take any action, whether through exercise of any power of eminent domain, application to the State of New Jersey for approval of a diversion of public park or recreation land, legal challenge to the validity or enforceability of the conservation restriction, or otherwise, the effect of which would be to in any way terminate, abrogate, or diminish the terms, conditions, or purposes of the conservation restriction. If, notwithstanding the preceding sentence, Jersey City proceeds with a condemnation or other action, the result of which would be to terminate, abrogate, or otherwise diminish the terms, conditions, or purposes of the conservation restriction, Jersey City shall, before taking any such action satisfy all of the conditions set forth in paragraph 74(a)(iv)(2).

(iv) Notwithstanding the foregoing, the conservation restriction may be terminated upon application of any Party when no hexavalent or total chromium contamination remains in the Open Space AOC, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive standards for Unrestricted Use in place at the time, whichever is more restrictive.

(c) **Deed Notice.** Upon completion of the Chromium Remedy, the Open Space AOC shall be subjected to the deed notice substantially in the form set forth in Exhibit D that restricts

future activities on the Open Space AOC. Nothing in the deed notice shall be construed as preventing the imposition of more stringent restrictions on the development allowed in the Open Space AOC pursuant to this paragraph and, in particular, the conservation restriction provided for in paragraph 74(b).

(d) **Recording of the Consent Decree, Conservation Restriction, and Deed Notice.** This Consent Decree, the conservation restriction imposed pursuant to paragraph 74(b), and the deed notice imposed pursuant to paragraph 74(c) shall be recorded, pursuant to N.J.S.A. §§ 46:15-1.1, 46:16-1.1, and 46:16-2, in the office of the Hudson County Register and a conspicuous reference to the Consent Decree, conservation restriction, and deed notice shall be included in all instruments concerning title to the Open Space AOC. Any Party shall have the right, periodically, but no more than once every 25 years, to record memoranda or other instruments that reference, incorporate, or attach this Consent Decree, the conservation restriction, the deed notice, and/or any further orders of the Court related to the Open Space AOC in the real estate records related to the Open Space AOC.

(e) **Zoning.** Pursuant to the Redevelopment Plan, the Open Space AOC is designated for open space and park. Jersey City shall not amend or change this designation unless it first satisfies the requirements of paragraph 74(a)(iv)(2).

(f) **Recreation and Open Space Inventory.** Upon acquiring fee simple absolute title to the Open Space AOC, Jersey City shall add those portions of the Open Space AOC not covered by roads, the pedestrian thoroughfare, and utility corridors adjacent to roads onto its Green Acres Program Recreation and Open Space Inventory ("ROSI") pursuant to N.J.A.C. § 7:36 and shall specify in such listing that it is subject to (i) Honeywell's prior easement to monitor, maintain, repair, and replace the Chromium Remedy; (ii) the actions necessary to implement, monitor,

maintain, repair, and replace the Chromium Remedy; (iii) the actions necessary to install any development permissible under paragraphs 74(j) and 74(k); and (iv) the conservation restriction imposed pursuant to paragraph 74(b). Jersey City shall also take all steps necessary or appropriate to notify the New Jersey Green Acres Program that such portions of the Open Space AOC have been added to its ROSI, such that those portions of the Open Space AOC shall thereafter be subject to all procedural and regulatory requirements applicable under the Green Acres Program, including prohibitions against diversion.

(g) **Eminent Domain.** If all or part of the Open Space AOC is taken in exercise of the power of eminent domain, or acquired by purchase in lieu of condemnation, by any public, corporate, or other authority so as to terminate, abrogate, or limit the restrictions created by this Consent Decree or the conservation restriction imposed pursuant to paragraph 74(b), in whole or in part, any Party may take appropriate actions to challenge such taking if there is a reasonable legal basis for doing so. In the event that the Parties are unable to prevent a taking notwithstanding their reasonable and appropriate efforts, any Party may take appropriate actions to recover the full value of the interests in the Open Space AOC subject to the taking or in lieu purchase, and all direct and incidental damages, costs, and fees occasioned thereby.

(h) **Environmental Covenant.** In the event that New Jersey enacts the Uniform Environmental Covenants Act or its substantial equivalent, the Parties shall address the issue of whether an environmental covenant shall be established for the Open Space AOC under the statute. If the Parties are unable to reach agreement on establishment of an environmental covenant, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of an environmental covenant if it would provide substantial additional protection for the Open Space AOC without

unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(i) **Future Protections.** Any Party shall have the right to propose consideration of additional or substitute protections for the Open Space AOC. If the Parties are unable to reach agreement with regard to the proposal, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. The Special Master shall recommend adoption of additional or substitute protections for the Open Space AOC if they would provide substantial additional protection for the Open Space AOC without unreasonably harming the interests of any Party. Any Party shall have the right to seek review by the Court of the Special Master's recommendation or consideration by the Court of the dispute in the event that the Special Master's appointment has expired.

(j) **Prohibited Development in Open Space AOC.** Only development satisfying the requirements of this paragraph and paragraph 74(k) shall be permitted in the Open Space AOC. All other development in the Open Space AOC shall be prohibited.

(i) Honeywell shall establish Open Space Design Standards that shall govern all development in the Open Space AOC regardless of when the construction or installation of permissible development occurs. The Open Space Design Standards shall satisfy each of the requirements set forth in paragraph 74(j)(v) and shall set forth the requirements for development that are necessary for the protection of the integrity of the Chromium Remedy.

(ii) The Initial Development in the Open Space AOC shall be the development undertaken following the completion of the Chromium Remedy in the Open Space AOC. The Initial Development may occur in one or more phases. Honeywell and Bayfront

Redevelopment LLC shall prepare a Development Plan before the initiation of each phase of the Initial Development. The Initial Development Period for each phase shall consist of the period covered by the Initial Development, plus a period of 10 years following the submission of the as-built documentation for the phase pursuant to paragraph 74(j)(viii).

(iii) The Special Master shall have jurisdiction to review the Open Space Design Standards and the Development Plan(s) solely for the purpose of ensuring that any development undertaken during the Initial Development Period is consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy. The Special Master's jurisdiction with regard to development in the Open Space AOC shall run through the Initial Development Period for each phase.

(iv) Honeywell shall ensure that the requirements of this paragraph and paragraph 74(k) are satisfied with regard to any development undertaken within the Initial Development Period. Honeywell shall also ensure that any development undertaken within the Initial Development Period is designed and installed in a manner consistent with this Consent Decree and with protection of the integrity of the Chromium Remedy.

(v) Any development undertaken in the Open Space AOC, regardless of when undertaken, shall satisfy each of the following requirements:

(1) It shall not jeopardize the integrity of the Chromium Remedy;

(2) It shall be limited to the types of development permitted under paragraph 74(k);

(3) It shall be consistent with this Consent Decree, including the conservation restriction imposed pursuant to paragraph 74(b), and the Redevelopment Plan; however, in the

event of any conflict or inconsistency between this Decree and the Redevelopment Plan, this Decree shall govern;

(4) In total, at least 75% of the Open Space AOC, exclusive of the acreage used for roads and the pedestrian thoroughfare, shall be comprised of landscaping, as defined by paragraph 74(k)(xi);

(5) The portion of the Open Space Design Standards necessary for protection of the Chromium Remedy as related to all roads, the pedestrian thoroughfare and associated utility corridors as well as the general location of such items shall be included in the 100% Design of the Chromium Remedy;

(6) If the lowest elevation for the bedding for any utility line, including irrigation or sprinkler lines, is two feet from the top of the warning layer of the cap, the utility line shall be placed in a utility corridor;

(7) In any event, there shall be two feet of soil or more between the warning layer of the cap and the lowest elevation of the bedding for any irrigation or sprinkler lines; and

(8) No permanent concession facilities shall be permitted.

(vi) Honeywell shall submit the Open Space Design Standards and the Development Plan(s) for any development undertaken during the Initial Development Period pursuant to the requirements of paragraph 86(c), except that such documents need not be submitted to NJDEP. Following Honeywell's submission of such documents, the procedures of paragraphs 86(e) and 86(f) shall apply, except that the Special Master need not provide notice to NJDEP.

(vii) During the Initial Development Period, any development in the Open Space AOC shall require the preparation and submission of a Development Plan pursuant to

paragraph 74(j)(vi) and such Development Plan shall be subject to review by the Special Master pursuant to paragraph 74(j)(iii).

(viii) Upon completion of each phase of the Initial Development, Honeywell shall provide as-built documentation for the Initial Development to the Special Master, Riverkeeper, and Jersey City. Upon completion of any further development during the Initial Development Period for the phase, Honeywell shall also provide as-built documentation to the Special Master, Riverkeeper, and Jersey City for the additional development. Such additional as-built documentation for a phase shall not affect the running of the Initial Development Period for the phase.

(ix)During the Initial Development Period, replacement in-kind of development features or facilities included in the Initial Development or minor modifications to the development features or facilities included in the Initial Development shall not require the preparation of a Development Plan or be subject to review by the Special Master, provided that such replacement or modification satisfies the requirements of the Open Space Design Standards, the applicable Development Plan, and paragraphs 74(j)(v) and 74(j)(x)(3)(notice requirement).

(x) After the Initial Development Period, all development is prohibited unless one of the following conditions is met:

(1) Jersey City satisfies the conditions set forth in paragraph 74(a)(iv)(2);

(2) The development is a replacement in-kind and such replacement is made in conformance with the specifications of the Open Space Design Standards, the applicable Development Plan, and paragraph 74(j)(v); or

(3) The development meets the requirements of paragraphs 74(j)(v) and 74(j)(xi), and Jersey City provides notice of its intention to alter or add to the development undertaken in the Initial Development Period. Such notice shall be provided in writing to Honeywell, Riverkeeper, and the holders of the conservation restriction established pursuant to paragraph 74(b) at least 30 days prior to Jersey City's alteration or addition to development undertaken in the Initial Development Period. Honeywell, Riverkeeper, or any holder of the conservation restriction shall have the right to move the Court to prohibit such alteration or addition.

(xi) If any of the development features or facilities that Jersey City seeks to add pursuant to paragraph 74(j)(x) require utilities that would require utility corridors other than the utility corridors installed during the Initial Development Period, Jersey City shall obtain approval from the Court before installing such new utility corridors.

(xii) Jersey City shall provide Honeywell, Riverkeeper, and the holder(s) of the conservation restriction established pursuant to paragraph 74(b) with an annual report that describes any alterations or additions, including those activities under paragraph 74(j)(x)(2), to the development undertaken during the Initial Development Period.

(xiii) All development features or facilities, whether included in the Initial Development or added subsequent thereto, are subject to demolition and/or removal to the extent necessary to maintain, replace, or repair the Chromium Remedy.

(k) **Permissible Development in the Open Space AOC.** The Initial Development or any subsequent addition or alteration thereto may include any or all of the following types of development features or facilities, provided that such development features or facilities satisfy the conditions set forth in paragraph 74(j)(v):

(i) Roads and the pedestrian thoroughfare -- both crossing and running along the Open Space AOC, but no more extensive than provided for in the diagram on page 39 of the Redevelopment Plan;

(ii) Curbing and fences;

(iii) Sidewalks, paths, walkways, and nature trails;

(iv) Utilities and utility corridors, lighting, and restrooms;

(v) Irrigation or sprinkler components or systems;

(vi) Water features;

(vii) Above-ground storm water cisterns;

(viii) Signs, including the signs or display required by paragraph 74(l);

(ix) Benches, trash receptacles, and bicycle racks;

(x) Recreational facilities, such as playground equipment, bocce ball courts, tennis courts, basketball courts, and athletic fields; and

(xi) Landscaping, including natural grasses, small trees, shrubbery, flowers, and potted plants, provided that such landscaping and the anticipated root structure of each landscaping component do not and will not jeopardize the integrity of the Chromium Remedy. Any portion of an athletic field that is covered in natural grass shall be considered landscaping for purposes of the percentage set forth in paragraph 74(j)(v)(4).

(l) **Signs or Displays.** Honeywell shall develop a permanent plan for informing visitors to the Open Space AOC of the history of the chromium production, contamination, and its remediation. Such plan shall provide for appropriate signs or displays that communicate this information. Such plan shall be subject to review and comment by the Parties and approval by the Special Master.

75. **Honeywell's Ongoing Responsibility.** Honeywell shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy in perpetuity. Honeywell shall satisfy this responsibility through establishment and implementation of a Long-Term Monitoring Plan. In the event that Honeywell ceases to exist without a successor-in-interest or its obligations under this Consent Decree are stayed or limited due to a bankruptcy petition, the Court shall appoint an independent third-party fiduciary who shall be responsible for implementing, monitoring, maintaining, repairing and replacing the Chromium Remedy pursuant to the requirements of this Consent Decree and the Long-Term Monitoring Plan, unless Jersey City volunteers to assume these responsibilities for the Chromium Remedy.

76. **Long-Term Monitoring Plan.** In consultation with the Parties, and subject to approval by the Special Master and NJDEP, Honeywell shall develop a Long-Term Monitoring Plan to ensure the ongoing effectiveness of the Chromium Remedy to meet the objectives set forth in paragraphs 65, 69, 68, 69, 72, and 77. The Long-Term Monitoring Plan shall be consistent with the applicable EPA policies and guidance, including, among others, EPA's Comprehensive Five Year Review Guidance (2001) (or any subsequent revision) and with NJDEP's Technical Requirements for Site Remediation (or any subsequent revision).

77. **Long-Term Monitoring Plan Objectives.** Honeywell shall design the Long-Term Monitoring Plan to satisfy each of the following objectives:

(a) Provide monitoring to ensure that the integrity and effectiveness of the Chromium Remedy are maintained; and

(b) Provide monitoring to ensure that the restrictions of the institutional controls are being satisfied, including the prohibition on development in the Open Space AOC.

78. **Monitoring and Remediation Under the Long-Term Monitoring Plan.** The Long-Term Monitoring Plan shall include the monitoring and remediation activities set forth in this paragraph and other monitoring and remediation activities, if necessary, to meet the objectives of paragraph 77. Honeywell shall provide Riverkeeper, the Special Master, and NJDEP with annual reports on activities conducted under the Long-Term Monitoring Plan.

(a) **Monitoring Activities in the Long-Term Monitoring Plan.** Honeywell shall undertake the following monitoring activities at intervals to be specified in the Long-Term Monitoring Plan, but no less frequently than set forth below, and, if the monitoring shows it is necessary, Honeywell shall also undertake the remediation activities as set forth below:

(i) Quarterly visual inspection monitoring of the Open Space AOC to ensure that it is not being put to any use that is inconsistent with paragraphs 74(j) and 74(k) or any use that may compromise the integrity of the Chromium Remedy. The Long-Term Monitoring Plan shall include an inventory of the prohibited and permissible uses pursuant to paragraph 74 and a corresponding checklist to be used by the individuals conducting the monitoring. If Honeywell determines that the Open Space AOC is being used in a manner inconsistent with the protections or the integrity and effectiveness of the Chromium Remedy, Honeywell shall act as soon as possible to cause such use to cease and, if there has been damage to the Chromium Remedy, to repair or replace it to original specifications or to a level of protection equivalent to the original Chromium Remedy;

(ii) Quarterly visual inspection monitoring of the Open Space AOC grade and slope to identify whether erosion has occurred or is occurring. Honeywell shall remediate any significant erosion.

(iii)Quarterly visual inspection monitoring to determine whether noticeable differential settlement or subsidence has occurred or is occurring in the Open Space AOC such that the integrity of the Chromium Remedy may be materially impaired. If evidence of differential settlement or subsidence is found, Honeywell shall propose further investigative measures. Honeywell shall remediate any differential settlement or subsidence that is beyond the degree of differential settlement/subsidence allowed for in the 100% Design and repair the cap and/or the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(iv)A baseline topographic survey at the completion of the Chromium Remedy and three additional surveys conducted at five-year intervals beginning five years after the conduct of the baseline survey. The topographic survey shall be of sufficient precision and accuracy to present the results as one-foot contours;

(v) Quarterly visual inspection monitoring to determine whether the Chromium Remedy in the Open Space AOC has been disturbed. Any evidence of the distinctive warning layer materials or any other cap materials as described in paragraph 65(a) at the surface is an indication that the cap has been disturbed. In such an event, Honeywell shall propose further investigative measures to evaluate whether the integrity of the cap has been compromised. In the event that the investigative measures show that the cap integrity has been compromised, Honeywell shall repair or replace the cap and the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vi) Quarterly visual inspection monitoring to ensure that burrowing animals are not materially impairing the integrity of the Chromium Remedy. If evidence of burrowing animals is found, Honeywell shall follow humane removal procedures and repair or replace the cap and

the overlying layers to original 100% Design specifications or to a level of protection at least equivalent to the original Chromium Remedy;

(vii) Quarterly visual inspection monitoring of the vegetative cover in the Open Space AOC to ensure that vegetative cover is in conformance with the landscaping provisions of the 100% Design and the Redevelopment Plan and will not materially impair the integrity of the Chromium Remedy. Maintenance of the vegetative cover shall include, at a minimum, mowing to ensure that tree species cannot become established and removal of any other vegetation with the potential to damage the Chromium Remedy;

(viii)Quarterly groundwater monitoring to ensure that groundwater levels are maintained in accordance with the requirement to maintain an outward gradient from Study Area 7 and in accordance with the water level control plan developed pursuant to paragraph 69(e);

(ix) Monitoring of vented gases and the gas venting system to ensure proper operation of the system, to evaluate any degradation of the system, to assess the need for treatment of vented gases, either initial, subsequent, or further depending on whether treatment has been previously provided, and to detect any condition that might endanger public health or safety. Such monitoring shall be conducted on a monthly basis for at least one year and, if the readings are stable, such monitoring may be conducted thereafter on a quarterly basis; and

(x) Any additional monitoring as required by specific details added in the design phase of the Open Space AOC.

(b) **Procedures for Proposing Changes to the Long-Term Monitoring Plan.** Any Party may, from time to time, propose changes to the scope of the monitoring activities under the Long-Term Monitoring Plan. If the Parties agree, the Long-Monitoring Plan shall be so changed

subject to approval by NJDEP and by the Special Master, if his appointment has not terminated, or otherwise, by the Court. If the Parties are unable to reach agreement over alterations to the monitoring and the Special Master's appointment has not terminated under this Consent Decree, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation. In the event that the dispute arises after the Special Master's appointment has terminated, any Party may file a motion seeking a resolution of the dispute by the Court.

(c) **Contingency Plan**. As part of the Long-Term Monitoring Plan, Honeywell shall develop a contingency plan to ensure the integrity of the remediation in the event of any planned penetration of the cap or otherwise planned activity that compromises the cap or any unplanned event or accident that penetrates the cap or otherwise compromises the integrity of the Chromium Remedy. The contingency plan shall include, at a minimum, an annually updated plan to notify the relevant persons, including the Special Master, NJDEP, and the Parties, of (i) the event penetrating the cap, compromising the cap, or compromising the integrity of the Chromium Remedy; (ii) the general steps to be taken to identify the extent of the problem; and (iii) the standards for remedying the problem.

(d) **Routine Maintenance**. The title owner of the Open Space AOC shall conduct maintenance of the Open Space AOC features or facilities that are permissible under paragraphs 74(j) and 74(k). The maintenance workers shall be trained in maintenance procedures that do not jeopardize the integrity of the Chromium Remedy. The training shall include the identification and reporting of any uses or features that are not permissible in the Open Space AOC or that may jeopardize the integrity of the Chromium Remedy. Honeywell shall provide all training materials. The title owner of Open Space AOC shall annually provide to the other Parties and

the Special Master a report describing the training which has been provided to its maintenance workers. The title owner of the Open Space AOC shall also provide to the Parties and the Special Master notice of any violations of the restrictions relating to the Open Space AOC identified by its workers during routine maintenance.

(e) **Recordkeeping**. Honeywell shall maintain written logs or other records of those monitoring and remediation activities undertaken pursuant to the Long-Term Monitoring Plan. Such logs shall be provided to Riverkeeper on a quarterly basis.

79. **Monitoring and Reporting to Riverkeeper.** Riverkeeper shall be provided with all documents submitted to NJDEP and/or the Special Master with respect to the Chromium Remedy, including the documents identified in paragraph 86(c).

80. **Notice to Stakeholders.** All residents, regardless of whether they are owners or lessees, and all commercial tenants on Study Areas 6 and 7 are hereby deemed stakeholders. Honeywell shall ensure that all stakeholders shall be provided at the time of their purchase or lease with notice of the contamination, the remedial actions that have been undertaken or are planned, and the importance of reporting activities that may appear to jeopardize the integrity of the engineering controls. Notice shall be accomplished in the following manner:

(a) Bold or otherwise conspicuous language on the first page of the deed provided to all purchasers in the Residential Area;

(b) A summary notice of the Chromium Remedy which:

(i) Has been subject to review and comment by the Parties and approval by the Special Master; and

(ii) Provides a reference to public websites and libraries and/or the future equivalents thereof, where the following can be found:

(1) Zoning and other Jersey City maps showing the Open Space AOC; and

(2) Documents describing the contamination and the remediation, including:

(a) This Consent Decree;

(b) The Remedial Investigation Report and the Final Remedial Action Report,

(c) The annual reports on long-term monitoring and maintenance and repair activities as required by paragraph 78 and annual reports on changes to the Initial Development as required by paragraph 74(j)(xii); and

(d) The Long-Term Monitoring Plan.

(c) The public provision of the maps and documents referred to in paragraph 80(b)(ii) via websites and libraries and/or the future equivalents thereof; and

(d) Notices to lessees and commercial tenants in all lease documents.

81. **Annual Letter to Riverkeeper on Notice to Stakeholders.** Each year beginning one year after the issuance of the first notice in a deed or lease pursuant to paragraph 80, Honeywell shall provide a letter to the Riverkeeper documenting its compliance with paragraph 80.

82. **Future Notice to Stakeholders.** Honeywell shall ensure that all stakeholders are provided with notice, at least annually, of long-term monitoring activities and any additional remediation activities undertaken with respect to the Chromium Remedy. Such notice shall be accomplished by notices on websites or future equivalents thereof, including Jersey City websites, any websites created to provide information about the Chromium Remediation or redevelopment of the Redevelopment Area, and one or more of the following:

(a) Any community message board or other similar site used and/or maintained by stakeholders or the manager(s) of the Redevelopment Area;

(b) Mailings to all stakeholders; and

(c) Posters and flyers throughout the Redevelopment Area.

83. **Stakeholder Enforcement.** Any stakeholder shall have the right to enforce the remedial obligations of this Consent Decree in the Court, including post-implementation monitoring and maintenance obligations, and the terms of any deed notice or use restriction.

**I. Oversight and Enforcement by the Special Master and NJDEP**

84. **Federal Court Jurisdiction.** The Court shall retain jurisdiction for the purpose of overseeing and enforcing this Consent Decree and to review any issue or dispute which is not resolved through the oversight process described in Article III.I.

85. **Appointment and Jurisdiction of the Special Master.** The Chromium Remedy provided for in this Consent Decree is hereby referred to a Special Master pursuant to Rule 53 of the Federal Rules of Civil Procedure. The Special Master is appointed in the Consolidated Litigation for the purpose of overseeing and enforcing the Chromium Remedy, the first five years of long-term monitoring of the Chromium Remedy, financial assurances for the Chromium Remedy, and the Initial Development Period for each phase of development in the Open Space AOC. The Special Master is also appointed in the Consolidated Litigation for the limited purpose of ensuring that the scheduling and implementation of any non-chromium related remedy, any site preparation activities, and any site redevelopment activities do not undermine the integrity of, unreasonably interfere with, or unnecessarily delay the effectuation of the Chromium Remedy, the Study Area 7 remedies, and other remedies within his jurisdiction as of the date of entry of this Consent Decree. The Special Master shall have jurisdiction over all matters for which he is appointed.

86. **Oversight of the Chromium Remedy.**

(a) **NJDEP Authority**. Nothing in or pursuant to this Consent Decree shall limit NJDEP's full statutory and regulatory authority with respect to the Study Area 6 South site, including (i) permitting authority; (ii) authority to review and approve the Treatment Study reports, the Remedial Action Work Plan, the 100% Design, and final Remedial Action Report for the Chromium Remedy; and (iii) authority to issue a no further action letter.

(b) **Special Master Responsibilities**. The Special Master shall have the following responsibilities:

(i) Ensuring that Honeywell's implementation of the Chromium Remedy satisfies the requirements of this Consent Decree;

(ii) Ensuring that Honeywell's implementation of the Chromium Remedy conforms with federal, state, and local permit requirements;

(iii) Establishing a reasonable schedule for the implementation of the Chromium Remedy and monitoring conformance with it;

(iv) Reviewing monthly progress reports and conducting periodic meetings with the Parties to review the progress of the implementation of the Chromium Remedy. NJDEP shall be invited, but not required, to participate in these meetings and the decision as to whether to participate shall be left to NJDEP's sole discretion;

(v) Submitting bi-monthly progress reports to the Court pursuant to the schedule for the submission of such reports established in *ICO v. Honeywell*;

(vi) Overseeing the financial assurances established pursuant to paragraphs 91 through 100, and, until the expiration of his term pursuant to paragraph 90, overseeing the financial assurances established pursuant to paragraphs 101 through 112;

(vii) Coordinating review of the documents as provided in paragraphs 86(c) through 86(g);

(viii) Overseeing all development undertaken in the Open Space AOC during the Initial Development Period pursuant to paragraph 74(j)(iii); and

(ix) To the extent that, in matters within the jurisdiction of the Special Master as set forth herein, a dispute arises between the Parties with respect to implementation of the Chromium Remedy, issuing a recommendation to the Court with respect to the dispute.

(c) **Submission of Documents by Honeywell.** Honeywell shall submit the following documents to Riverkeeper, Jersey City, the Special Master, and NJDEP:

(i) An overall schedule with milestones for the design and implementation of the remedy ("Schedule") consistent with paragraph 54 above;

(ii) A Second Supplemental Remedial Investigation Report reporting the results of the field work conducted pursuant to paragraph 55;

(iii)A Chromium Impacted Soils Pilot Test Work Plan and Analytical Protocol for conduct of the treatment study pursuant to paragraph 56, unless such documents are agreed to by NJDEP and Riverkeeper before the entry of this Consent Decree;

(iv)An Initial Treatment Study Report for the Development AOC;

(v) A Final Treatment Study Monitoring Report;

(vi) The documents for Site 163 submitted pursuant to paragraphs 54(a)(iv), 54(a)(v), 61, and 62;

(vii) A report to evaluate the need for remediation of any potentially remaining contaminated shallow groundwater in the Development AOC after implementation of the Development AOC Soils Remedy and, based on such an evaluation, a proposal;

(viii) A report of the results of the sampling to complete delineation of contaminated shallow groundwater in the area to the southeast of the Site pursuant to paragraph 71 and, based on the results, a proposal for a remedy;

(ix) A plan for one round of monitoring to evaluate whether the L-Well Groundwater remains contained pursuant to paragraph 72;

(x) A proposal for a remedy of the L-Well Groundwater, in the event L-Well Groundwater monitoring indicates the contaminated groundwater is no longer contained, pursuant to paragraph 72;

(xi) A Remedial Action Work Plan;

(xii) A 50% Design Report (which may include the Development AOC Conceptual Design Plan as a component) as well as design drawings and specifications at the 50% level for other components of the Chromium Remedy (hereinafter the 50% Design);

(xiii) Design drawings and specifications at the 100% level (after selection of the contractor) (hereafter "100% Design");

(xiv) The data validation plan, including quality control and quality assurance protocols;

(xv) The site-wide master health and safety plan;

(xvi) The Long-Term Monitoring Plan;

(xvii) The final Remedial Action Report or final construction report (including as-built drawings and such other reports as may be prepared of the remedy as implemented);

(xviii) A program for post-treatment monitoring pursuant to paragraph 63, and, depending on such results, a proposal for further remedial actions;

(xix) A report reviewing measured groundwater levels for the groundwater remedy;

(xx) Documents required during the Initial Development Period pursuant to paragraphs 74(j)(vi), 74(j)(vii), and 74(j)(viii); and

(xxi) Other post-implementation monitoring reports as required by the Long-Term Monitoring Plan.

(d) **Initial Review of Documents by NJDEP.** The Parties and Special Master shall allow the period of time set forth below for NJDEP to conduct its review of a submission (hereinafter "NJDEP Review Period") before the document is subject to the Special Master review and approval process. During the NJDEP Review Period, any Party may submit comments to NJDEP. For the Second Supplemental Remedial Investigation Report, the Remedial Action Work Plan, the Initial Treatment Study, and the Final Treatment Study Monitoring Report, the NJDEP Review Period shall be 90 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. For any other documents identified in paragraph 86(c), the NJDEP Review Period shall be 30 days from the date of submission of the document to NJDEP, the Special Master, and the Parties. The NJDEP review period shall be extended an additional 30 days for any document for which NJDEP provides the Parties and the Special Master with notice that its review will require an additional 30 days. At the conclusion of the NJDEP Review Period, the comment and review process provided for in paragraphs 86(e) and 86(f) shall commence. In the event that any document has been revised during the NJDEP Review Period, Honeywell shall resubmit the applicable document for purposes of the comment and review provided for in paragraphs 86(e) and 86(f).

(e) **Comment on Submitted Documents**. For each of the documents submitted by Honeywell pursuant to paragraph 86(c), and following conclusion of the NJDEP Review Period as described in paragraph 86(d), the Special Master shall establish a schedule for the submission

of comments and responses to comments. For each of the documents submitted, Riverkeeper, Jersey City, the Special Master, and NJDEP shall have the right to submit comments to Honeywell. Honeywell shall address all comments received and submit a revised document. The revised document shall be submitted by Honeywell to Riverkeeper, Jersey City, the Special Master, and NJDEP. The revised document shall be subject to review and approval pursuant to paragraph 86(f), unless the Parties agree both on the revised document and that further review and approval pursuant to paragraph 86(f) is unnecessary. In that event, the Parties shall inform the Special Master that review under paragraph 82(f) is unnecessary and Honeywell shall proceed to implement the revised document.

(f) **Review and Approval of the Submitted/Revised Document**

(i) **Scope of Review**. Subject to the limitations in paragraph 82(e), all documents submitted by Honeywell, pursuant to paragraph 86(c) and 86(e), shall be subject to review and approval by the Special Master in accordance with the following procedure. All such documents, except the Schedule and the 100% Design, shall be subject to the review and approval process and shall not require an order of the Court. The Schedule and 100% Design documents shall be subject to the review and approval process, but shall also require an order of the Court as provided in paragraph 86(g). A document shall be approved if the document (1) complies with this Consent Decree; (2) complies with the Remedial Action Work Plan for the Chromium Remedy; and (3) complies with the Schedule and 100% Design.

(ii) **Procedure**. Prior to making a decision on a document, the Special Master shall notify NJDEP of his intention to rule on the document or make a recommendation to the Court on the document. Such notice shall notify NJDEP that the Special Master will consider any comments NJDEP wishes to submit on the document if such comments are submitted within

the timeframe established by the Special Master in the schedule for comments pursuant to paragraph 86(e). NJDEP shall in its sole discretion determine whether to submit comments to the Special Master.

(iii) **Court Review**. If any Party objects to the Special Master's recommendation to the Court or approval of any document pursuant to this paragraph, that Party may seek further relief from the Court with respect to the document.

(g) **Schedule and 100% Design Documents**. As to the Schedule and the 100% Design documents, Honeywell shall have the responsibility, within 30 days of the Special Master's approval of each document, of (i) moving for entry of an order by the Court approving the document as approved by the Special Master; or (ii) filing objections with the Court to the Special Master's approval (and any recommendations contained therein) and moving for entry of the Schedule or 100% Design (including any such recommendations of the Special Master to which Honeywell agrees). Riverkeeper shall have the right in these proceedings to raise any objections they might have to the Schedule or 100% Design as approved by the Special Master or to the submission by Honeywell to the Court. NJDEP shall receive notice of any motion filed with respect to the Schedule or the 100% Design.

(h) **Flexibility in 50% and 100% Design Documents**. The Parties recognize that work conducted to implement the Chromium Remedy may be conducted by Honeywell contractors and that Honeywell may establish performance-based criteria or specifications for its contractors. As a result, the Parties recognize that the 50% Design and 100% Design documents for the Chromium Remedy may include performance-based standards, criteria, and specifications. These documents shall be sufficiently prescriptive to enable the Parties and the Special Master to evaluate their conformance with the Remedial Action Work Plan and this Consent Decree. The

Parties also recognize that the 100% Design will be completed after Honeywell has selected a contractor. The Parties further recognize that completing the 100% Design after the selection of the contractor(s) shall not make the 100% Design subject to any less stringent or more deferential review. Honeywell's commitment to the contractor(s) shall not be cause to limit review by the Parties and the Special Master.

(i) **Changes to the Schedule.** The Parties recognize that changes to individual line items in the Schedule will occur. To the extent that (i) the Parties and the Special Master agree that such changes do not have a material impact on satisfaction of the Schedule milestones established for items set forth in paragraph 54; and (ii) such changes do not require modifications to any necessary permits or authorizations for the Chromium Remedy, such changes may be made upon agreement of the Parties and the Special Master without further order of the Court.

87. **Retention of Professionals.** The Special Master may retain the services of professionals and/or other technical personnel, as reasonably needed, to fulfill his obligations under this Consent Decree, and for which he will be reimbursed pursuant to paragraph 89.

88. **Insurance for the Special Master.** The Special Master shall obtain insurance coverage relating to the performance of the Special Master's duties and responsibilities under this Consent Decree. Such coverage shall be similar to the Special Master's existing coverage in *ICO v. Honeywell*, procured pursuant to the Court's November 11, 2005 Stipulation and Order Regarding Special Master's Application to Procure Insurance Coverage, and as extended to the Consolidated Litigation by the Sediment Consent Order. The insurance coverage shall be sufficiently extended in duration and scope to cover all additional duties and responsibilities as set forth hereunder. Honeywell shall pay the premiums and other administrative costs of the Special Master's insurance.

89. **Reimbursement of Special Master Fees and Expenses.** The Special Master shall submit fee applications to the Court for approval of reasonable fees and expenses incurred in the oversight of matters referred to him pursuant to this Consent Decree. Any Party may raise with the Court objections to such fee applications. Upon approval of a fee application by the Court, the reimbursement of the Special Master's fees and expenses shall be made from the escrow fund previously established by Honeywell for the purpose of paying the Special Master's fees and expenses in *ICO v. Honeywell* pursuant to this Court's September 15, 2003 Order Setting Financial Assurances and extended to the Consolidated Litigation by the Sediment Consent Order.

90. **Expiration of Special Master's Appointment.** The Special Master's appointment under this Consent Decree shall expire after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy and the Initial Development Period for each phase of development has been concluded as provided in paragraph 74(j)(ii). However, solely to the extent that the Special Master is still supervising other portions of the Consolidated Litigation or *ICO v. Honeywell* after Honeywell has completed the first five years of long-term monitoring of the Chromium Remedy or the Initial Development Period for each phase of development as provided in paragraph 74(j)(ii), whichever is later, the Special Master shall continue to have jurisdiction under this Consent Decree until he has completed his specifically enumerated responsibilities under the Final Judgment in *ICO v. Honeywell*, the Sediment Consent Order, the Deep Groundwater Consent Order, the Study Area 6 North Consent Decree, and any other future orders, decrees, or judgments in *ICO v. Honeywell* and the Consolidated Litigation. Enumerated responsibilities under any order, decree, or judgment shall include only those tasks specifically assigned to the Special Master in the order, decree, or judgment. Enumerated responsibilities

shall not include any continued jurisdiction exercised over long-term monitoring beyond the initial period specified in the order, decree, or judgment. For example, the Special Master has jurisdiction over the first five years of long-term monitoring under the Sediment Consent Order. Oversight during these five years shall be an enumerated responsibility, but any continued oversight of long-term monitoring, pursuant to the extension of the Special Master's jurisdiction beyond the first five years, as provided in paragraph 60 of the Sediment Consent Order, shall not be an enumerated responsibility. Such extensions of jurisdiction shall be effective only so long as specific enumerated responsibilities in any order, decree, or judgment have not been fulfilled.

**J. Initial Financial Assurances**

91. **Chromium Remedy Letter of Credit.** Honeywell shall obtain a one-year, irrevocable letter of credit (the "Chromium Remedy Letter of Credit") to be automatically renewed annually in an amount equal to the "Remedial Costs Subject to Financial Assurance."

(a) Remedial Costs Subject to Financial Assurance shall mean:

(i) The costs of implementing the Chromium Remedy calculated using factors, including inflation and discount rates, determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process;

(ii) The costs of monitoring and maintenance activities for five years, as required by the Long-Term Monitoring Plan, calculated using factors including inflation and discount rates determined to be appropriate in the Study Area 6 North Consent Decree financial assurance comment and approval process; and

(iii) A contingency of 25% with respect to those costs listed in paragraphs 91(a)(i) and 91(a)(ii).

(b) The Chromium Remedy Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution, provided that in either case, the financial institution shall be acceptable to the Special Master.

92. **Procedures for Review of the Proposed Chromium Remedy Letter of Credit.** No later than December 31, 2008, Honeywell shall submit to Riverkeeper and the Special Master for their review the proposed (a) amount of the Chromium Remedy Letter of Credit; (b) form of the Chromium Remedy Letter of Credit; and (c) name of the institution that will issue the Chromium Remedy Letter of Credit. If Riverkeeper does not agree to the terms of the Chromium Remedy Letter of Credit, the Parties shall meet and confer in an effort to resolve their differences. If the Parties are unable to reach agreement over the terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the Chromium Remedy Letter of Credit.

93. **Automatic Renewal.** The Chromium Remedy Letter of Credit shall be automatically renewed annually unless (a) no later than 120 days prior to the anniversary of the Chromium Remedy Letter of Credit issue date, the issuer provides notice of nonrenewal or (b) Honeywell seeks a reduction in the Chromium Remedy Letter of Credit, pursuant to paragraph 94, to correspond to the reduced estimate of Remedial Costs Subject to Financial Assurances. If the issuer provides notice of nonrenewal, Honeywell shall obtain a replacement irrevocable Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit. If Honeywell is not otherwise in default as provided in Article III.J, the Special Master shall direct the cancellation of the prior Chromium Remedy

Letter of Credit within 91 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit. In the event that the Special Master is entitled to draw upon a Chromium Remedy Letter of Credit because there are two Chromium Remedy Letters of Credit currently in place, the Special Master shall not draw an aggregate amount in excess of the highest valued Chromium Remedy Letter of Credit. Upon Honeywell's request, the Special Master may, at his option, decide not to require overlapping letters of credit in any year based on Honeywell's financial strength in that year, provided that Honeywell has submitted all necessary information so that the Special Master can make his determination at least 150 days prior to the expiration of the Chromium Remedy Letter of Credit.

94. **Annual Right to Seek Reduction in Amount of Chromium Remedy Letter of Credit.** Honeywell shall have the right annually to seek a reduction in the Chromium Remedy Letter of Credit. At the time of seeking such reduction, Honeywell shall submit to the Riverkeeper and the Special Master an estimate of the remaining Remedial Costs Subject to Financial Assurance, including the contingency as described in paragraph 91(a)(iii), and shall seek adjustment of the Chromium Remedy Letter of Credit so that the total estimated amount of remaining Remedial Costs Subject to Financial Assurance are covered by the Chromium Remedy Letter of Credit. However, the adjustment shall not result in reducing the Chromium Remedy Letter of Credit to an amount below the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), plus a contingency of 25% of the remaining estimated costs under paragraphs 91(a)(i) and 91(a)(ii), and shall not result in reducing the Chromium Remedy Letter of Credit to an amount less than $20,000,000 as expressed in 2008 dollars unless long-term financial assurances are in place pursuant to Article III.K. Before making any request to reduce the amount or modify the terms of the Chromium Remedy Letter of Credit, Honeywell shall first confer with the Riverkeeper and

in an effort to reach agreement on the modified amount or terms of the Chromium Remedy Letter of Credit. If the Parties are unable to reach agreement over the modified amount or terms of the Chromium Remedy Letter of Credit, the Parties shall submit the dispute to the Special Master, who shall resolve the dispute. Any Party shall have the right to seek review by the Court of the Special Master's decision regarding the modified amount or terms of the Chromium Remedy Letter of Credit. Upon agreement on the amount of the reduction or modified terms of the Chromium Remedy Letter of Credit (or upon order of the Court directing that the Chromium Remedy Letter of Credit be reduced to an identified amount or otherwise modified), Honeywell shall obtain a replacement Chromium Remedy Letter of Credit in such amount and with such terms. If Honeywell is not otherwise in default as provided in Article III.J and the issuer of the primary Chromium Remedy Letter of Credit has not provided notice of non-renewal, within 30 days after delivery to the Special Master of any replacement of a Chromium Remedy Letter of Credit, the Special Master shall direct the cancellation of the prior Chromium Remedy Letter of Credit.

95. **Bankruptcy Protection**. Neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy. The Chromium Remedy Letter of Credit shall contain the language necessary to assure that neither the Chromium Remedy Letter of Credit nor the proceeds of the Chromium Remedy Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

96. **Exclusive Court Jurisdiction**. The Chromium Remedy Letter of Credit shall recite that the issuer submits to the exclusive jurisdiction of this Court for any and all disputes arising under the Letter of Credit.

97. **Application of New York Law.** The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Chromium Remedy Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

98. **Procedures upon Honeywell's Material Default of Its Obligations.** During the period in which the Special Master has jurisdiction pursuant to paragraph 85, the Chromium Remedy Letter of Credit shall be payable to the Special Master and shall not, prior to its expiration date, be revoked or terminated except consistent with this Consent Decree and with the consent of the Special Master and approval by the Court. The Special Master's ability to draw upon the Chromium Remedy Letter of Credit shall not be limited by any agreement between Honeywell and the issuer. The Special Master may, without further order or notice to this Court, draw upon the Chromium Remedy Letter of Credit upon the occurrence of default by Honeywell, which shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 93 to deliver a replacement Chromium Remedy Letter of Credit at least 95 days prior to the expiration date of the existing Chromium Remedy Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 15 days after written notice to Honeywell thereof and either (i) Honeywell, in the opinion of the Special Master without further input from the Parties, shall have failed to cure the breach; (ii) during the 15-day period, the Court has not entered an order to prevent the Special Master from

drawing on the Chromium Remedy Letter of Credit; or (iii) the Court or the Special Master has not granted Honeywell additional time to cure the breach;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if involuntary filing has not been dismissed within 60 days; the appointment of a custodian, receiver, liquidator, or trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 98(c), and the failure of Honeywell to provide assurance to the Special Master, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

99. **Placement of Proceeds in Court Registry Investment System Account**. In the event that the Special Master draws upon the Chromium Remedy Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Chromium Remedy Letter of Credit which represent the remaining estimated Chromium Remedy costs under paragraphs 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), in an account with the Court Registry Investment System in accordance with Local Civil Rule 67.1 and not expend the proceeds of the Letter of Credit without further order of this Court. The

Special Master shall place all additional proceeds of the Chromium Remedy Letter of Credit in a trust fund pursuant to paragraph 103(b)(v).

100. **Termination of Chromium Remedy Letter of Credit**. The Chromium Remedy Letter of Credit may be withdrawn in its entirety upon the satisfaction of all of the following:

(a) The implementation of the Chromium Remedy; and

(b) Establishment of long-term financial assurance pursuant to Article III.K.

**K. Long-Term Financial Assurances**

101. **Long-Term Financial Assurances.** Honeywell shall fund long-term financial assurances to ensure that the activities set forth in paragraph 102(a) are carried out regardless of whether Honeywell is financially able to carry out such activities in perpetuity.

102. **Costs Subject to Long-Term Financial Assurances.**

(a) Long-term financial assurances shall provide enough funds to cover the costs of the following activities:

(i) Perpetual monitoring and maintenance of the Chromium Remedy, including installation, operation and monitoring of any above-cap-grade gas collection and/or treatment system as may be necessary, but such system is not part of the 100% Design;

(ii) Perpetual operation of the shallow groundwater remedies pursuant to paragraphs 69, 70, and 71;

(iii) Perpetual repair of the cap;

(iv) Perpetual replacement of the cap on a 75-year replacement interval; and

(v) The perpetual administration of the trust fund regardless of whether such trust fund is selected by Honeywell pursuant to paragraph 103(a) or is established from the Long-Term Letter of Credit pursuant to paragraphs 103(b)(ii), 103(b)(v), or 109.

(b) The costs that shall be subject to financial assurances is an amount that will provide the full payment for each of the activities set forth in paragraphs 102(a)(i) through 102(a)(v) plus a 25% contingency when the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to be performed. The costs subject to financial assurances are forward looking because they state an amount valued at the time the funds are needed. As such, they shall be stated in contemporary time as the present value (calculated on the basis of a discount rate of 4.75%) of the estimated future costs of the activities specified in paragraphs 102(a)(i) through 102(a)(v), plus a 25% contingency on those costs.

103. **Long-Term Financial Assurance Mechanisms.** Honeywell shall provide long-term financial assurances in the amount of the costs subject to long-term financial assurances in the form of a trust fund, a letter of credit, or some combination of the two. The selected mechanism(s) shall satisfy the following requirements:

(a) **Trust Fund.** In the event that Honeywell selects a trust fund, Honeywell shall create a trust fund such that it can provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(i) The trust fund shall be at arm's length from Honeywell and shall not be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The trust fund agreement shall contain the language necessary to assure that neither the trust fund nor the earnings of the trust fund shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The trust fund shall be managed by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution managing the

trust fund declares bankruptcy, the Court shall withdraw the funds and appoint another financial institution meeting the requirements of this paragraph to manage the trust.

(iii) No more frequently than once per year, Honeywell may apply to the Court for an order directing the trust manager to reimburse Honeywell for any costs that it has incurred to carry out the activities set forth in paragraphs 102(a)(i) through 102(a)(iv).

(b) **Long-Term Letter of Credit**. In the event that Honeywell selects a letter of credit, Honeywell shall obtain a one-year irrevocable letter of credit (the "Long-Term Letter of Credit") to be automatically renewed annually in an amount that provides sufficient funds such that a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a), could be created. The Long-Term Letter of Credit-funded trust, plus any trust fund established under paragraph 103(a), shall provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The amount of any Long-Term Letter of Credit shall therefore be adjusted periodically as the cap replacement interval is approached because, for example, the money needed in the 10th year to fund a trust that can provide for replacement of the cap in the 75th year is much less than the money that would be needed in the 40th year. Such periodic adjustments shall be proposed and approved by the Court in conjunction with the adjustments under paragraph 106.

(i) Neither the Long-Term Letter of Credit nor the proceeds of the Long-Term Letter of Credit shall be considered the property of Honeywell or property of the estate in the event of Honeywell's bankruptcy, dissolution, privatization, or sale. The Long-Term Letter of Credit shall contain the language necessary to assure that neither the Long-Term Letter of

Credit nor the proceeds of the Long-Term Letter of Credit shall be affected or restricted in any way by operation of the automatic stay in 11 U.S.C. § 362.

(ii) The Long-Term Letter of Credit shall be issued by a financial institution domiciled in the United States or by a United States subsidiary of a non-U.S. financial institution acceptable to Riverkeeper or approved by the Court. In the event that the financial institution issuing the Long-Term Letter of Credit declares bankruptcy, the Court shall authorize the drawing of funds from the Long-Term Letter of Credit and shall deposit those funds in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(iii) The then-current provisions of the Uniform Customs and Practice ("UCP") for Documentary Credits) as published by the International Chamber of Commerce or such successor organization and New York law shall apply to the Long-Term Letter of Credit at the time that Honeywell obtains such letter of credit or any replacements thereafter.

(iv) The Long-Term Letter of Credit shall be automatically renewed annually, unless, no later than 120 days prior to the anniversary of the Long-Term Letter of Credit issue date, the issuer provides notice of non-renewal. If the issuer provides notice of non-renewal, Honeywell shall obtain a replacement irrevocable Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit. If Honeywell is not otherwise in default as provided in this Article, the Court shall direct the cancellation of the prior Long-Term Letter of Credit within 91 days after delivery to the Court of any replacement of a Long-Term Letter of Credit. In the event that the Court is entitled to draw upon a Long-Term Letter of Credit when there are two Letters of Credit currently in place, the Court shall not draw an aggregate amount in excess of the highest valued Long-Term Letter of Credit.

(v) Prior to the expiration of the Special Master's appointment pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Special Master. During the time the Long-Term Letter of Credit is payable to the Special Master, the Special Master may draw on the Long-Term Letter of Credit as provided in paragraph 98. In the event that the Special Master draws upon the Long-Term Letter of Credit due to an event of default, the Special Master shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a). After the Special Master's appointment expires pursuant to paragraph 90, the Long-Term Letter of Credit shall be payable to the Court and, in the event that the Court draws on the Long-Term Letter of Credit, the Court shall place the proceeds of the Long-Term Letter of Credit in a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

(vi) Whether the Long-Term Letter of Credit is payable to the Special Master or the Court, it shall not, prior to its expiration date, be revoked or terminated by Honeywell except consistent with this Consent Decree and with the approval of the Court. The ability of the Special Master or the Court to draw upon the Long-Term Letter of Credit shall not be limited by any agreement between Honeywell and the issuer.

(vii) In the event that the Long-Term Letter of Credit is drawn upon and invested pursuant to paragraph 103(b)(ii), 103(b)(v), or 109 and Honeywell has also selected a trust fund pursuant to paragraph 103(a), resulting in the existence of two trust funds, the two trust funds shall be managed so as to ensure that the combined amount of the trust funds is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary.

(c) **Combination**. Honeywell may use some combination of a trust fund and a letter of credit to achieve the requirements of this paragraph. However, if a combination is used, Honeywell shall ensure that the combined amount of financial assurances is sufficient to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. The trust fund and the letter of credit shall otherwise satisfy all the requirements of paragraphs 103(a) and 103(b).

104. **Procedures for Review of the Proposed Long-Term Financial Assurances**. No later than June 1, 2009, Honeywell shall submit to Riverkeeper and the Special Master, for their review (a) the amount of the proposed long-term financial assurances; (b) the form(s) of the proposed long-term financial assurance mechanisms; and (c) the name(s) of the institution proposed to manage or issue the long-term financial assurances. If Riverkeeper agrees to the terms of the proposed long-term financial assurances, within 60 days of such agreement, Honeywell shall create a trust fund and/or secure a Long-Term Letter of Credit on those terms. If the Parties are unable to reach agreement over the terms of the long-term financial assurances, the Parties shall submit the dispute to the Special Master, who shall recommend a resolution of the dispute. Any Party shall have the right to seek review by the Court of the Special Master's recommendation regarding the terms of the financial assurances.

105. **Temporary Maintenance of Chromium Remedy Letter of Credit**. Until the long-term financial assurances have been put into place, Honeywell shall maintain the Chromium Remedy Letter of Credit required by paragraph 91 in an amount equal to at least $20,000,000 in 2008 dollars. In the event of any default by Honeywell pursuant to paragraph 98 while the Chromium Remedy Letter of Credit is in place, the provisions of paragraph 103(b)(v) for the placement of the proceeds that exceed the remaining estimated Chromium Remedy costs under

paragraph 91(a)(i), plus a contingency of 25% of the remaining estimated costs under paragraph 91(a)(i), shall apply.

106. **Adjustment of Amount Held in Long-Term Financial Assurances**. Every five years as marked from the establishment of the first long-term financial assurances pursuant to paragraph 103, the Parties shall report to the Court whether the long-term financial assurances are adequately funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. At such time as the Parties report to the Court, any Party may seek an adjustment in the amount of the long-term financial assurances. The Party seeking an adjustment must demonstrate that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Such demonstration shall reflect the actual costs of implementing the remedy and/or any replacement of the remedy, once such actual costs are available. The demonstration shall also reflect the costs of work completed to date and the actual lifetime of the cap, once the cap has been replaced or has passed a replacement interval without requiring replacement. The demonstration shall further reflect the actual performance of the fund and its ability to provide the full amount of the costs subject to long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary. Any demonstration shall be forward looking and shall be based upon estimates of what the activities in paragraphs 102(a)(i) through 102(a)(v) are expected to cost at the time they must be performed and the amount of funding projected to be available to undertake such activities at the time they must be performed. If, after reviewing the submission(s) received from the Parties, the Court determines that the long-term financial assurances are under-funded or over-funded to provide the full amount of the costs subject to

long-term financial assurances, as set forth in paragraph 102(b), at the time those funds are necessary, the Court shall order an adjustment in the amount held in the long-term financial assurances to overcome the shortage or overage. In the event that the Court determines that the long-term financial assurances are under-funded, it shall order Honeywell to increase the amount held in the long-term financial assurances. In the event that the Court determines that any trust fund established pursuant to paragraph 103(a) is over-funded, the Court shall issue an order directing the trust manager to pay the overage to Honeywell. In the event that the Court determines that the Long-Term Letter of Credit is over-funded, the Court shall issue an order permitting Honeywell to reduce the amount covered during the next annual renewal of the Long-Term Letter of Credit pursuant to paragraph 103(b)(iv). Any adjustment to the amount of the Long-Term Letter of Credit pursuant to this paragraph shall be in addition to any adjustment of the amount of the Long-Term Letter of Credit required pursuant to paragraph 103(b).

107. **Exclusive Court Jurisdiction**. The trust fund agreement and/or the Long-Term Letter of Credit shall recite that the trust fund manager and/or issuer of the Long-Term Letter of Credit submit to the exclusive jurisdiction of this Court for any and all disputes arising under the trust fund or the Long-Term Letter of Credit. The requirements of this paragraph shall apply whether the trust fund is established pursuant to paragraph 103(a), 103(b)(ii), 103(b)(v), or 109.

108. **Procedures upon Honeywell's Material Default of Its Obligations after the Special Master's Appointment Has Expired.** Upon the occurrence of default by Honeywell, after the Special Master's appointment has expired, Riverkeeper may move the Court on an expedited basis for an order to withdraw funds from the trust fund or to draw on the Long-Term Letter of Credit. Default shall include:

(a) The failure of Honeywell, in the event that notice is given pursuant to paragraph 103(b)(iv) to deliver a replacement Long-Term Letter of Credit at least 95 days prior to the expiration date of the existing Long-Term Letter of Credit;

(b) The material failure of Honeywell to proceed with diligence and in good faith to carry out the terms of this Consent Decree and the continuance of such a material breach for a period of 30 days after written notice by Riverkeeper to Honeywell of the alleged material failure, unless Honeywell cures the alleged breach within the 30-day notice period or such longer period as the Parties may agree to or the Court may order;

(c) The filing by Honeywell of a petition seeking relief, or the granting of relief, under the Federal Bankruptcy Code or any similar federal or state statute; any assignment for the benefit of creditors made by Honeywell; the involuntary filing of any of the foregoing against Honeywell if the involuntary filing is not dismissed within 60 days; the appointment of a custodian, receiver, liquidator, trustee, or other similar official for Honeywell or for a substantial part of Honeywell's property; any action by Honeywell to effect any of the foregoing; or if Honeywell becomes insolvent as defined in Section 101(32) of the Federal Bankruptcy Code; or

(d) The dissolution, liquidation, merger, consolidation, or reorganization of Honeywell or the institution of any proceeding to effect any of the foregoing, other than under paragraph 108(c), if Honeywell fails to provide assurance to Riverkeeper, and the Court, within 15 days after written notice, that such an event will not impair Honeywell's ability to carry out the terms of this Consent Decree.

109. **Drawing on the Long-Term Letter of Credit in the Event of Honeywell's Default.** If the Court grants any motion by Riverkeeper or pursuant to paragraph 108 to draw on the Long-Term Letter of Credit, the sum approved by the Court's order granting the motion shall be

paid from the Long-Term Letter of Credit into a trust fund, separate from any trust fund created under paragraph 103(a) but satisfying the requirements of paragraph 103(a).

110. **Use of the Trust Fund in the Event of Honeywell's Default.** In the event of Honeywell's default, as defined in paragraphs 108(a) through 108(d), the money in the trust fund established pursuant to paragraph 103(a) shall be available to meet the obligations of paragraph 102(a), as well as for payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

111. **Use of a Trust Fund Established Pursuant to Paragraph 99, 103(b)(ii), 103(b)(v), or 109.** In the event that a trust fund is established pursuant to paragraph 99, 103(b)(ii), 103(b)(v), or 109, the money in the trust fund shall be available to meet the obligations of paragraph 102(a), as well as for the payment of future attorneys' fees and expenses pursuant to paragraph 120. Riverkeeper shall file motions with the Court seeking orders directing how the money in the trust fund shall be used. The Court shall consider motions on an expedited basis and shall enter appropriate orders. The Court may enter an order allowing for automatic withdrawal of regular expenses without separate motion to the Court by Riverkeeper.

112. **Termination of the Long-Term Financial Assurances.** Honeywell's obligations under Article III.K shall be terminated and the long-term financial assurance mechanisms shall be terminated when the Court finds that no hexavalent or total chromium contamination remains in the Open Space AOC or on the Site, whether in soils or in groundwater, in excess of the levels specified for Unrestricted Use in the NJDEP Chromium Directive or any more restrictive

standards for Unrestricted Use in place at the time, whichever is more restrictive. Upon determining that long-term financial assurances may be terminated, the Court shall order that any Long-Term Letter of Credit may be withdrawn in its entirety and any trust fund may be terminated. In conjunction with its order terminating any trust fund, the Court in its discretion shall designate a recipient(s) of any remaining trust funds.

## ARTICLE IV: TERMINATION

113. **Termination of this Consent Decree**. This Consent Decree shall terminate upon the withdrawal of any Party as provided for in this paragraph. Any Party may elect to withdraw from this Consent Decree due to the occurrence of one or more of the following events, provided that such Party provides written notice of withdrawal to the other Parties pursuant to paragraph 118:

(a) The Court fails to enter this Consent Decree or this Consent Decree is determined to be invalid on appeal; or

(b) NJDEP takes one of the following actions with respect to the Remedial Action Work Plan:

(i) Rejects or fails to approve the Remedial Action Work Plan for the Chromium Remedy within 180 days of submission of the plan;

(ii) Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in more than a 50% increase in the estimated costs of the Chromium Remedy as set forth in Article III; or

(iii)Approves the Remedial Action Work Plan for the Chromium Remedy, but conditions such approval on changes in the Work Plan that result in a substantial reduction of the protection of human health and/or the environment.

114. **Procedures for Withdrawal and Termination.** Any Party electing to withdraw pursuant to paragraph 113 and thereby terminate this Consent Decree shall provide written notice of such withdrawal and termination to all other Parties within 30 days of the occurrence giving rise to the decision to withdraw. If any Party objects to termination of the Consent Decree, or believes that the conditions set forth in paragraph 113 have not been met, such objecting Party may move the Court for an expedited hearing on the issue of whether the conditions for termination have been effectuated.

115. **Good-Faith Obligation to Avoid Termination.** The Parties agree that they will each endeavor to fulfill the terms of this Consent Decree, that they will work diligently and in good faith to meet their obligations hereunder, and that they will promptly and timely take all reasonable steps to give effect to this Consent Decree and to avoid termination under paragraph 113.

116. **Effect of Termination.** If this Consent Decree is terminated pursuant to paragraph 113, the Consent Decree shall no longer be binding on the Parties and shall be of no further effect. In the event that this Consent Decree is terminated by one or more Parties pursuant to paragraph 113, each Party to this Consent Decree reserves all of its rights, claims, and defenses (both legal and factual) against the other Parties with respect to the matters at issue in the Consolidated Litigation and each Party remains free to pursue such rights, claims, and defenses.

## ARTICLE V: TRANSFER OF TITLE TO BAYFRONT REDEVELOPMENT LLC

117. **Transfer of Title of Study Areas 6 South and 7 to and from Bayfront Redevelopment LLC.** The transfer of title of Study Area 6 South and Study Area 7 properties to Bayfront Redevelopment LLC pursuant to the Jersey City/Honeywell Consent Order and any subsequent transfers shall not impede Honeywell's obligations to (a) complete the remediation of

Study Area 7 and implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or (b) complete the Chromium Remedy and conduct long-term monitoring and fulfill its other obligations set forth in this Consent Decree. Such transfers of Study Areas 6 South and Study Area 7 shall not include a transfer of Honeywell's obligations to implement the Final Judgment and subsequent orders in *ICO v. Honeywell* or a transfer of Honeywell's obligations under this Consent Decree, but shall include a right of access or any other right required by Honeywell to complete the remediation. Any subsequent transfer of Study Area 6 South or Study Area 7 from Bayfront Redevelopment LLC to a redeveloper or other party shall provide all necessary agreements to allow Honeywell all necessary access to Study Area 6 South and Study Area 7 for purposes of completing Honeywell's obligations with respect to Study Area 6 South under this Consent Decree and completing the Study Area 7 remediation and implementing the Final Judgment and subsequent orders in *ICO v. Honeywell*.

## ARTICLE VI: NOTICE

118. **Notice**. Any and all notices given in connection with this Consent Decree shall be deemed adequately given only if in writing and addressed to the Party for whom such notices are intended at the addresses set forth in this paragraph. All notices shall be sent by Federal Express or other nationally recognized overnight messenger service or by first-class registered or certified mail, postage prepaid, return receipt requested. A written notice shall be deemed to have been given to the recipient party on the earlier of (a) the date it shall be delivered to the address set forth in this paragraph; (b) the date delivery shall have been refused at the address set forth in this paragraph; or (c) with respect to notices sent by mail, the date as of which the postal service shall have indicated such notice to be undeliverable at the address set forth in this paragraph.

Any and all notices referred to in this Consent Decree, or which any Party desires to give to the other, shall be addressed as follows:

If to Honeywell and/or
Bayfront Redevelopment LLC :

Tom Byrne, Esq.
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-2775

With copies to:

John Morris
Honeywell International Inc.
101 Columbia Road
Morristown, NJ 07962
(973) 455-4003

If to Jersey City:

William Matsikoudis
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NJ 07305
(201) 547-4667

If to Riverkeeper:

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th St., N.W.
Washington, DC 20005-4632
(202) 682-2100

Any party may change its designated recipients or addresses for notice in this paragraph by providing written notice of such change to all other Parties.

## ARTICLE VII: RIVERKEEPER'S ATTORNEYS' FEES

119. **Payment of Past Fees and Expenses.** Within 30 days of the entry of this Consent Decree, Honeywell shall pay Terris, Pravlik & Millian, LLP the sum of $813,000.00 which represents the following:

(a) A compromise of the attorneys' fees incurred by Riverkeeper in the litigation of Study Area 6 South portion of *Riverkeeper v. Honeywell* through August 31, 2008; and

(b) $353,746.67 in out-of-pocket expenses representing a portion of the expenses incurred by Riverkeeper in *Riverkeeper v. Honeywell* from the inception of the litigation after deducting the expenses paid pursuant to the Sediment Consent Order, the Deep Groundwater Consent Order, and the Study Area 6 North Consent Decree.

(c) Payment of the sum of $813,000.00 shall be in full satisfaction of all obligations, duties, and responsibilities of Honeywell with respect to the $879,317.92 in fees and expenses that Riverkeeper claimed with regard to the above described fees and expenses.

120. **Future Fees and Expenses.** Honeywell shall reimburse Riverkeeper's attorneys for reasonable fees and expenses incurred: (a) in negotiating this Consent Decree after August 31, 2008; (b) in the monitoring and enforcement of this Consent Decree; and (c) in participation in the Special Master process established pursuant to this Consent Decree. Honeywell shall also reimburse Riverkeeper for reasonable attorneys' fees and expenses for Riverkeeper's review of and participation in the Long-Term Monitoring Plan and monitoring and enforcement of this Consent Decree following the term of the Special Master. In the event that any dispute arises between the Parties under this Consent Decree that must be resolved by the Court, Riverkeeper shall be entitled to recover its attorneys' fees and expenses for litigation of the dispute to the extent allowed by federal law. Riverkeeper and Honeywell shall use the same informal procedure for attempting to settle fees issues as has been used for post-judgment monitoring fees in *ICO v. Honeywell*. In the event that Riverkeeper and Honeywell are unable to reach a settlement on fees, Riverkeeper shall apply to the Court for an award of attorneys' fees and expenses. If Honeywell objects to only a portion of the Riverkeeper's statement of attorneys' fees and expenses, Honeywell shall pay the undisputed portion within 60 days of Riverkeeper's submittal of the statement to Honeywell. The Court shall resolve any objections to

Riverkeeper's statement of attorneys' fees and expenses and shall enter an appropriate Order. In the event of Honeywell's default, Riverkeeper may seek attorneys' fees from any trust fund or court registry funds established pursuant to the financial assurances provisions of this Consent Decree.

## ARTICLE VIII: MISCELLANEOUS PROVISIONS

121. **Force Majeure.** Force Majeure, for the purposes of this Consent Decree, is defined as an event arising from causes beyond the control of any Party or Parties (or their agents, contractors, subcontractors, representatives, or assigns) which could not have been overcome by reasonable diligence and which delays or prevents the performance of any obligation under this Consent Decree. Examples of events which may constitute force majeure include the refusal of any federal or state governmental authority to grant a permit or authorization necessary for the completion of actions required by this Consent Decree, floods, hurricanes, tornadoes, and other extraordinary weather events, earthquakes and other natural disasters, terrorist attacks, war, and other national emergencies. Examples of events that are not force majeure events include normal inclement weather, increased costs or expense, the failure to timely and fully apply for a permit or authorization necessary for the completion of actions required by this Consent Decree, or financial difficulty of any Party. The Party claiming force majeure shall bear the burden of showing an event was a force majeure event.

122. **Bayfront Redevelopment LLC as a Party.** As a signatory to this Consent Decree, Bayfront Redevelopment LLC subjects itself to the Court's jurisdiction for the purpose of enforcing this Consent Decree and agrees to be bound by this Consent Decree. This Consent Decree shall be fully enforceable against Bayfront Redevelopment LLC.

123. **Successors and Assigns.** This Consent Decree shall be binding upon and shall inure to the benefit of the successors, assigns, heirs, corporate parents, subsidiaries, and affiliates of each Party. No assignment or delegation of the obligations hereunder shall release the assigning Party from its obligations under this Consent Decree.

124. **Successors to Hackensack Riverkeeper, Inc.** In the event that Hackensack Riverkeeper, Inc. disbands or otherwise ceases operations, it shall assign its rights under this Consent Decree to another qualified nonprofit organization. A nonprofit organization shall be qualified for assignment under this Consent Decree if it is a charitable organization under Section 501(c)(3) of the Internal Revenue Code or its substantial equivalent and has an established record of working to enhance or preserve the ecology, natural habitat, or environment. Any such assignment shall be subject to approval by the Court and Honeywell shall have the right to object to any proposed assignment. Any successor organization shall have the duty to assign its rights under this Consent Decree to another qualified nonprofit organization in the event that the successor disbands or otherwise ceases operations. In the event that a successor is not appointed at any given time, the New Jersey Attorney General or equivalent officer shall appoint a successor subject to approval by the Court and objection by Honeywell.

125. **Reservation of Rights and Claims.** Except as set forth expressly herein, this Consent Decree does not affect in any way any of the Parties' claims or defenses against third parties who have not signed the Consent Decree.

126. **Governing Law and Continuing Jurisdiction.** The Court shall retain jurisdiction over the matters addressed in this Consent Decree for purposes of enabling the Parties to apply to the Court for any further order as may be necessary to construe, carry out, or enforce the terms of this Consent Decree. This Consent Decree shall be interpreted and enforced under the laws of

the United States and the State of New Jersey by the United States District Court for the District of New Jersey.

127. **Construction.** Questions regarding the interpretation of this Consent Decree shall not be resolved against any Party on the ground that this Consent Decree has been drafted by that Party. This Consent Decree is the result of review, negotiation, and compromise by each Party.

128. **Authority to Enter into Agreement.** The undersigned representative for each Party represents, certifies, and warrants that he or she is duly authorized by the Party whom he or she represents to enter into the terms of this Consent Decree and bind such Party legally to this Consent Decree.

129. **Measures to Effectuate This Consent Decree.** Jersey City shall take all appropriate steps to ensure that commitments it has agreed to with regard to the Open Space AOC have been duly considered, ratified, and approved. Such steps include consideration of such commitments and an effectuating ordinance at a meeting of the City Council, open to the public, at which members of the public have the opportunity to comment on all aspects of the commitments made by Jersey City..

130. **Modifications.** This Consent Decree may be modified by mutual agreement of the Parties but such agreement must be in writing, duly and properly signed by all Parties, and shall be submitted to the Court for approval.

131. **Severability.** Each of the provisions in paragraph 74 of this Consent Decree shall be deemed severable and, in the event that one or more of such provisions is deemed invalid or unenforceable, it shall not affect the validity or enforceability of the other provisions of the Consent Decree.

132. **Signatures.** This Consent Decree may be signed simultaneously or in counterparts by the respective signatories, which shall be as fully valid and binding as if a single document was signed by all of the signatories. This Consent Decree may be signed electronically by any or all signatories, and such electronic signature shall be as fully valid and binding as a hand-written signature.

Consented to and approved for entry:

*s/Aurelio Vincitore*

William Matsikoudis
Aurelio Vincitore
Corporation Counsel
City of Jersey City
280 Grove Street
Jersey City, NY 07305
(201) 547-4667

*Counsel for the City of Jersey City*

*s/ David Sheehan*

David Sheehan
Baker Hostetler
45 Rockefeller Plaza
11th Floor
New York, NY 10111
(212) 589-4200

Michael D. Daneker
Arnold & Porter LLP
555 12th Street N.W.
Washington, DC 20004
(202) 942-5000

*Counsel for Honeywell International Inc. and Bayfront Redevelopment LLC*

*s/ Edward Lloyd*

Edward Lloyd
Columbia Law School
435 West 116th Street, Room 831
New York, NY 10027
(212) 854-4376

Bruce J. Terris
Carolyn Smith Pravlik
Kathleen L. Millian
Terris, Pravlik & Millian, LLP
1121 12th Street N.W.
Washington, DC 20005-4632
(202) 682-2100

*Counsel for the Hackensack Riverkeeper, William Sheehan, Reverend Winston Clarke, and Lawrence Baker*

APPROVED AND ENTERED as an Order of this Court this ___ day of _____, 2012.

Hon. Dennis M. Cavanaugh
United States District Judge

## EXHIBITS

**Exhibit A:** Remedial AOC's and Remedial Approach Map

**Exhibit B:** NJDEP Chromium Policy

**Exhibit C:** Conservation Restriction

**Exhibit D:** Deed Notice

**Exhibit E:** Additional Boring Locations

# Deed Notice

*Dated: _____, 2017*

**BAYFRONT REDEVELOPMENT LLC**

Grantor(s).

*Record and return to:*

**Waters, McPherson, McNeill, P.C.**
**P.O. Box 1560**
**300 Lighting Way**
**Secaucus, New Jersey 07096-1560**

**ATTN: _____, Esq**

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 1 OF 25**

- **Groundwater Memo 11/07/2016**
- **2013 Monthly Reports**
- **2014 Monthly Reports Part 1**

**GROUNDWATER MEMO 11/07/2016**

Honeywell

115 Tabor Road
Morris Plains, NJ 07950

November 7, 2016 ***via Electronic Mail***

The Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Re: Initiation of Long Term Groundwater Monitoring**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Dear Senator Torricelli:

In accordance with the September 1, 2016 Revised Draft SA-6 Long Term Monitoring Plan (LTMP) and the Groundwater Level Monitoring Plan (GWLMP) which was Appendix J of the SA-6 North Chromium Remedy 100% Design Report, Honeywell is hereby providing notice to the Parties that we will initiate long-term groundwater monitoring activities at SA-6 South the week of November 14, 2016. While Honeywell acknowledges the LTMP has not been approved as final by the parties, Honeywell will act to meet the requirements of the current draft to move site activities forward. Since the Chromium Remedy at SA-6 South was substantially complete when the geomembrane liner was installed in October 2015, the 12-month "transition period" for groundwater specified in the LTMP and GWLMP ended in October 2016. We have authorized our environmental consultants, Amec Foster Wheeler and Cornerstone, to implement the following general activities at SA-6 South:

- Install data loggers in piezometers,
- Conduct manual water level gauging, and
- Implement quarterly groundwater sampling of the twelve specified monitoring wells in the Development AOC.

Similarly for SA-6 North, we are monitoring the groundwater level recovery following completion of excavation and geomembrane liner installation, and anticipate that the "transition period" will be complete in Spring 2017. At that time, we will initiate long-term monitoring at SA-6 North. The Spring 2017 monitoring will include the inspections associated with the cap vegetation.

In response to Plaintiffs' request to establish baseline groundwater quality conditions inside the Open Space Areas, Amec Foster Wheeler collected filtered and unfiltered groundwater samples from each piezometer on the interior of both Sites. The samples were analyzed for total and hexavalent chromium. A summary of this data is provided in the attached Table 1. The location of the piezometers is shown on the attached Figure 1.

Should the Parties wish to discuss this further, we will be prepared to discuss at the next All Parties meeting on November 15th. Should you have any questions in the meantime, please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:dn/sgf

Encl: Table 1: Summary of SA-6 North and South Interior Piezometer Groundwater Sample Data
Figure 1: SA-6 North and South Contingent Groundwater Extraction Trenches and Sampled Monitoring Well Locations

cc: (electronic copy only)
Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP

**TABLE 1**

**SUMMARY OF SA-6 NORTH & SOUTH INTERIOR PIEZOMETER GROUNDWATER SAMPLE ANALYTICAL RESULTS**
**Study Area 6 North & South**
**Honeywell International Inc.**
**Honeywell International Inc.**

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | Piezometer 087-PZ-02 | | Piezometer 087-PZ-04 | | Piezometer 087-PZ-06 | | Piezometer 087-PZ-08 | | Piezometer 087-PZ-10 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Type: | | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered |
| | Date Sampled: | | 09/06/2016 | 09/06/2016 | 09/06/2016 | 09/06/2016 | 10/14/2016 | 10/14/2016 | 09/02/2016 | 09/02/2016 | 09/02/2016 | 09/02/2016 |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **62.2** | <10 | **10.2** | <10 | **28.4** | <4 | **<10** | <10 | **29** | 12.6 |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | ug/L | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 | <5.5 |


Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS)
N.J.A.C 7:9C; last amended 7/20/2010
DUP: Duplicate Sample
J: Estimated concentration

**TABLE 1**

**SUMMARY OF SA-6 NORTH & SOUTH INTERIOR PIEZOMETER GROUNDWATER SAMPLE ANALYTICAL RESULTS**
**Study Area 6 North & South**
**Honeywell International Inc.**
**Honeywell International Inc.**

| Client Sample ID: | Ground Water Quality Standard (GWQS) | Units | Piezometer 124-PZ-12 | | Piezometer 124-PZ-14 | | Piezometer 124-PZ-16 | | Piezometer 124-PZ-18 | | Piezometer 124-PZ-20 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Sample Type: | | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered | Unfiltered | Filtered |
| | Date Sampled: | | 09/06/2016 | 09/06/2016 | 09/02/2016 | 09/02/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 | 09/01/2016 |
| | | | | | | | | | | | | |
| **Metals Analysis** | | | | | | | | | | | | |
| CHROMIUM | 70 | ug/L | **24,200** | **23,300** | **37.3** | <10 | **1,720** | **1,690** | **83.7** | <4 | <4 | <4 |
| **General Chemistry** | | | | | | | | | | | | |
| HEXAVALENT CHROMIUM | - | ug/L | **24,500** | **24,500** | <5.5 | <5.5 | **1,700 J** | **1,900** | <5.5 J | <5.5 | <5.5 J | <5.5 |

Notes:
GWQS: NJDEP Ground Water Quality Standards (GWQS)
N.J.A.C 7:9C; last amended 7/20/2010
DUP: Duplicate Sample
J: Estimated concentration




**Legend**

- Piezometer Location
- Existing Monitoring Well Location
- Groundwater Collection Manhole (approx.)
- Standpipe Location
- Perimeter Pool Location (approx.)
- Contingent Groundwater Trenches (approx.)
- Cap Area
- Study Area Boundary

Source:
New Jersey 2012 - 2013 High Resolution Orthophotography, NAD83 NJ State Plane Feet, MrSID Tile; NJ Office of Information Technology (NJOIT), Office of Geographic Information Systems (OGIS); Trenton, NJ; 2013/03.

120 60 0 120 240
SCALE IN FEET

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

*Amec Project No.*
3480130354

*Prepared/Date*
WSL 05/28/2014

*Checked/Date*

# Figure 1
## SA-6 North & South Contingent Groundwater Extraction Trenches and Sampled Monitoring Well Locations
Study Area 6 & Study Area 7
Jersey City, New Jersey

Path: P:\GIS\Projects\Honeywell\Study Area 6\North\20130909_Study Area 6 and 7 Monitoring Well Map\20141023 - Groundwater Extraction Trenches Map.mxd

**2013 MONTHLY REPORTS**

**4/12/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 12, 2013

Office of the Special Master
Robert G. Torricelli
49 Bridge Street
Suite 2
Lambertville, NJ 08530

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 58**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from March 1 – March 31, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
William Matsikoudis - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Joni Noble McDonnell - Genova, Burns & Giantomasi
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Michelle Weaver - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 58
## Project SA-6N/6S Remediation

# March 2013
**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/12/13 | Progress Report No. 57 | The Honorable Robert G. Torricelli<br>Office of the Special Master<br>49 Bridge Street, Suite 2<br>Lambertville, NJ 08530 |
| 03/18/13 | Appendix L: Open Space Design Standards for the Bayfront Redevelopment | The Honorable Robert G. Torricelli<br>Office of the Special Master<br>49 Bridge Street, Suite 2<br>Lambertville, NJ 08530 |
| 03/19/13 | Special Master Meeting (Study Area 6) | n/a |
| 03/21/12 | Incident No. 1302-21-16-44-40<br>Study Area 6 North<br>Chromium Site 087 Jersey City Incineration Authority<br>JCMUA UST AOC<br>555 Route 440, Jersey City, NJ<br>NJDEP PI# 002633 | The Honorable Robert G. Torricelli<br>Office of the Special Master<br>49 Bridge Street, Suite 2<br>Lambertville, NJ 08530 |
| 03/22/13 | Notification of Utility Construction<br>Honeywell Groundwater Treatment Plant (GWTP) – Site Utility Relocation Work<br>Study Area SA-6 North, Bayfront Redevelopment LLC | Chuck Lee, P.E., P.P., C.M.E.<br>City Engineer<br>City of Jersey City<br>Department of Public Works<br>575 Route 440<br>Jersey City, NJ 07305 |
| 03/22/13 | Notification of Construction<br>Groundwater Treatment Plant - Study Area 6 North<br>Jersey City, Hudson County, New Jersey<br>Modification of the CAFRA GP#15/Waterfront Development Permit - Upland/Flood Hazard Area Individual Permit/Water Quality Certification<br>NJDEP File No: 0906-08-0002.6<br>FHA120001/WFD120001<br>(Former Permit #0906-10-0004.1 WFD 100001, 0906-08-0002.1 FHA080001/CAF080001) | Suzanne U. Dietrick<br>New Jersey Department of Environmental Protection<br>Site Remediation Program<br>Office of Dredging and Sediment Technology<br>401 E. State Street, 401-04P<br>Trenton, NJ 08625-0028 |

## Key Activities – Last Month (March 2013)

**Study Area 6 North Sites 087 and 088**

- Honeywell and Amec continued finalization of the Issued for Construction Design Packages for both SA-6 North and SA-6 South Chromium Remedy projects.
- Honeywell and Amec continued to coordinate implementation of the Site Preparation Plan activities for facility demolition and planned relocation of the Jersey City (JC) Entities.
    - Honeywell and Amec met with the Jersey City Entities to continue to advance the Site Preparation Activities including clearing of vehicles and materials from the surcharge area.
    - On March 27, 2013, Arcadis submitted the draft Construction Completion Report documenting the activities related to removal of residual oil materials from the Sedimentation Basin.
    - On February 21, 2013, Amec collected groundwater samples from three (3) monitoring wells in the vicinity of the Sedimentation Basin for analysis of total petroleum hydrocarbons – diesel range organics (TPH-DRO).
- Honeywell continued to work with Plaintiffs to resolve the outstanding comments on the Open Space Design Standards.
- Honeywell continued efforts to develop an access agreement for the Trenk property.
- Honeywell and Amec continued to meet with the Chromium Remedy contractor on a weekly basis to implement action items developed during the Constructability Review meetings.

The following activities are noted as part of the Non-Chromium PDI:

- On March 12, 2013, Amec met with representatives of the manufacturer of the SVE/GWE System at the JCMUA UST area to perform a root-cause analysis following the software malfunction on February 20, 2013. Based on successfully testing all system fault shut-down procedures, Amec restarted the SVE/GWE System on March 15, 2013.
- On March 25, 2013, NJDEP issued a Discharge to Groundwater (DWG) Permit by Rule Authorization for continued Phase II EAB implementation at the JCIA and JCDPW UST areas in 2013.
- Amec continued monthly inspections of the select monitoring wells installed within the UST areas where separate phase product has been observed.
- Honeywell continued to work with offsite property owners to advance discussions on Access Agreement finalization.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).
    - The site utility contractor, Creamer, mobilized to the site on March 28, 2013.
    - Submittal and request for information (RFI) phase are in process with the Site Utility Relocation Contractor and the Building Contractor.
    - Footings and Foundation Permit was obtained from Jersey City.
- On March 14, 2013, Amec and Honeywell hosted a pre-bid meeting at SA-6 South for the In-Situ Chemical Reduction Treatment Program at Site 163.
- The following activities are noted as part of the Non-Chromium PDI:
    - Amec continues to evaluate data from additional soil samples collected in February as part of pre-design investigation activities at Site 163 in accordance with the NJDEP-approved combined RIR/RASR/RAWP for Non-Chromium.

## Key Activities Planned for This Month (April 2013)

**Study Area 6 North Sites 087 and 088**

- On April 16, 2013, Honeywell and Amec will submit the Issued for Construction Design Packages for both SA-6 North and SA-6 South Chromium Remedy projects to NJDEP, the Special Master, Plaintiffs, and stakeholders.
- Honeywell and Amec will continue to work with Plaintiffs to finalize the Open Space Design Standards with anticipated submittal as part of the Issued for Construction Design Packages on April 16, 2013.
- Amec will continue preparation of construction-related permit applications for submittal to governing agencies for the SA-6 North and SA-6 South Chromium Remedy projects.
- Honeywell will continue efforts to develop an access agreement for the Trenk property.
- Honeywell and its consultants will continue the Non-Chromium activities including:
    - Amec will continue to operate and maintain the SVE/GWE system.
    - Amec will perform ongoing monthly inspections of the JCMUA-1A monitoring wells and product recovery as needed from the JCIA-1B and JCDPW UST Areas.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Honeywell and Amec will continue to evaluate contractor bids for implementing the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South).
- Honeywell and Amec will continue to advance the new GWTP construction project.
- As part of the Non-Chromium remedial design process, Honeywell and Amec will:

- Continue to support the JCRA in the Eminent Domain process at the former Harsimus Property including removal and disposal of the remaining boats.
- Continue to evaluate additional pre-design investigation step-out boring analytical data in recently collected soil samples from Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**5/13/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

May 13, 2013

Office of the Special Master
Robert G. Torricelli
49 Bridge Street
Suite 2
Lambertville, NJ 08530

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 59**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from April 1 – April 30, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
William Matsikoudis - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Joni Noble McDonnell - Genova, Burns & Giantomasi
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Michelle Weaver - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 59
## Project SA-6N/6S Remediation

## April 2013
**Study Area 6 North and South**
**Jersey City, NJ**

### Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 04/02/13 | Submittal: Notification of Treatment Works Approval (TWA) Application Submittal to NJDEP Remedial Action – Study Area 6 North and Study Area 6 South Jersey City, Hudson County, New Jersey | Passaic Valley Sewerage Commission (PVSC)<br>Jersey City Environmental Commission<br>Municipal Planning Board – Jersey City<br>Jersey City Municipal Utilities Authority (JCMUA) |
| 04/03/13 | Submittal: Response to Comments for a Temporary Dewatering Permit - New Program Interest No.: 1304D, Activity No.: DWP130001, SA-6 North and South Chromium Remedy, Jersey City, Hudson County, New Jersey | Carolyn Olynyk<br>New Jersey Department of Environmental Protection<br>Bureau of Water Allocation and Well Permitting |
| 04/03/13 | Submittal: TWA Permit Application to JCMUA | Jersey City Municipal Utilities Authority (JCMUA) |
| 04/12/13 | Submittal: Study Area 6 North and South - Progress Report No. 58 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/12/13 | Submittal: Revised Work Plan for In-Situ Treatment of Chromium Impacted Soils (ISOTEC Chromium Treatment Program Operations Plan), SA-6 North Chromium Remedy, Sites 087 and 088, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/15/13 | Submittal: Integrated Annual Groundwater Performance Report for 2012, Study Areas 5, 6, and 7 - Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 4/16/13 | Meeting: SA-6 & SA-7 Special Master All-Hands Conference Call | n/a |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 04/16/13 | Submittal: Chromium Remedy 100% Design Submittal, Issued for Construction (Special Master Review), SA-6 North Sites 087 and 088, SA-6 South Sites 073, 124 125, 134, 140, and 163, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/18/13 | Submittal: Revised Master Schedule for Study Area 6 North and South | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/23/13 | Submittal: NJDEP Correspondence re: Treatment Works Approval No. 12-0196 Study Area 6, Jersey City, Hudson County | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## Key Activities – Last Month (April 2013)

**Study Area 6 North Sites 087 and 088**

- On April 16, 2013, Honeywell and Amec finalized and submitted the Issued for Construction (Special Master Review) Design Packages for both SA-6 North and SA-6 South Chromium Remedy projects.
- On May 1, 2013, Honeywell issued an Errata letter regarding a correction to the Legend on select drawings associated with SA-6 South.
- Honeywell and Amec continued to coordinate implementation of the Site Preparation Plan activities for facility demolition and planned relocation of the Jersey City (JC) Entities.
    - Honeywell and Amec continued to coordinate with the Jersey City Entities regarding clearing of vehicles and materials from the surcharge area.
    - On May 1, 2013, Arcadis submitted the revised draft Construction Completion Report documenting the activities related to removal of residual oil materials from the Sedimentation Basin.
- Honeywell and Plaintiffs resolved the outstanding comments on the Open Space Design Standards (OSDS). The OSDS was provided as Appendix L in the Issued for Construction (Special Master Review) Design Packages submitted on April 16, 2013.
- Honeywell continued efforts to develop an access agreement for the Trenk property.
- Honeywell and Amec continued to coordinate with PVSC regarding the condition assessment of the 72-inch Force Main. While technical details have been addressed between PVSC and Honeywell it appears additional reviews at NJDEP may impact overall remedy schedule.
- Honeywell and Amec continued to meet with the Chromium Remedy contractor on a weekly basis to implement action items developed during the Constructability Review meetings.

The following activities are noted as part of the Non-Chromium PDI:

- The SVE/GWE System has been operating continuously since being re-started on March 15, 2013.
- Amec continued monthly inspections of the select monitoring wells installed within the UST areas where separate phase product has been observed.
- Honeywell continued to work with offsite property owners to advance discussions on Access Agreement finalization.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).
  - The site utility contractor, Creamer, continued their construction activities, including installation of the storm sewer lines and relocation of an existing water line.
  - Amec is continuing to work with PVSC to obtain an indirect discharge permit and NJDEP to modify the existing air permit for the existing GWTP.
  - Amec and the building erection contractor, Oradel, continue to work through administrative submittals in advance of mobilization for the building foundation work.
- On April 12, 2013, Honeywell and Amec obtained best and final bids for SA-6 South for the In-Situ Chemical Reduction Treatment Program at Site 163.
- On April 26, 2013, Honeywell and Amec obtained best and final bids for the above-grade demolition of 60 Kellogg Warehouse and 80 Kellogg structures.
- On April 26, 2013, Arecon Ltd., mobilized to the site to begin removal of the boats on the Harsimus Property.
- The following activities are noted as part of the Non-Chromium PDI:
  - Amec continues to evaluate data from additional soil samples collected in February as part of pre-design investigation activities at Site 163 in accordance with the NJDEP-approved combined RIR/RASR/RAWP for Non-Chromium.

## Key Activities Planned for This Month (May 2013)

**Study Area 6 North Sites 087 and 088**

- On May 3, 2013, Amec submitted the Soil Erosion and Sedimentation Control Permit to Hudson-Essex-Passaic Soil Conservation District.
- Amec will continue preparation of construction-related permit applications for submittal to governing agencies for the SA-6 North and SA-6 South Chromium Remedy projects.
- Honeywell and Amec will continue to coordinate with PVSC regarding the condition assessment of the 72-inch Force Main.
- Honeywell will continue efforts to develop an access agreement for the Trenk property.

- Amec will coordinate with ISOTEC and Jersey City Entities on the mobilization and implementation schedule for the in-situ treatment of the three designated areas.
- Honeywell and its consultants will continue the Non-Chromium activities including:
    - Amec will continue to operate and maintain the SVE/GWE system.
    - Amec will perform ongoing monthly inspections of the JCMUA-1A monitoring wells and product recovery as needed from the JCIA-1B and JCDPW UST Areas.
    - Arcadis will perform additional groundwater monitoring to evaluate the progress of the Enhanced Anerobic Bioremediation work on JCIA-1A and JCDPW-1A.
    - Honeywell will continue to work with offsite property owners to advance discussions on Access Agreement finalization.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Honeywell and Amec will complete evaluation of contractor bids for implementing the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South) and execute a contract with the successful bidder.
- Honeywell and Amec will continue to advance the new GWTP construction project.
- As part of the Non-Chromium remedial design process, Honeywell and Amec will:
    - Continue to support the JCRA in the Eminent Domain process at the former Harsimus Property and complete removal and disposal of the remaining boats.
    - Continue to evaluate additional pre-design investigation step-out soil boring analytical data from Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**6/12/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

June 12, 2013

Office of the Special Master
Robert G. Torricelli
49 Bridge Street
Suite 2
Lambertville, NJ 08530

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 60**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from May 1 – May 31, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
William Matsikoudis - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Joni Noble McDonnell - Genova, Burns & Giantomasi
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 60
## Project SA-6N/6S Remediation

## May 2013
**Study Area 6 North and South**
**Jersey City, NJ**

### Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 05/01/13 | Submittal: Errata Notification - Chromium Remedy 100% Design Submittal Issued for Construction (Special Master Review) SA-6 North and South | Honorable Robert G. Torricelli Office of the Special Master |
| 05/02/13 | Submittal: Request for Approval of Statements of Consent Form WQM-003 Treatment Works Approval (TWA) Permit Application for Discharge of Construction Water to Jersey City Municipal Utilities Authority (JCMUA) Wet Well Remedial Action Study Area 6 North (SA-6 North) and Study Area 6 South (SA-6 South) Jersey City, Hudson County, New Jersey | Passaic Valley Sewerage Commission (PVSC) |
| 05/03/13 | Submittal: Application for Soil Erosion and Sediment Control Plan Certification, Chromium Remedy - Study Area 6 North (SA-6 North) and Study Area 6 South (SA-6 South), Jersey City, Hudson County, New Jersey | Hudson-Essex-Passaic Soil Conservation District (HEPSCD) |
| 05/13/13 | Submittal: Progress Report No. 59 | The Honorable Robert G. Torricelli Office of the Special Master |
| 05/21/13 | Meeting: Special Master Meeting | n/a |
| 05/23/13 | Submittal: Response to Comments for a Temporary Dewatering Permit – New Program Interest No.: 1304D Activity No.: DWP130001 SA-6 North and SA-6 South Chromium Remedy Jersey City, Hudson County, New Jersey | The Honorable Robert G. Torricelli Office of the Special Master |
| 05/28/13 | Submittal: Letter of Authorization - NJDEP Stormwater Construction E-Permit, Study Area 6 Imported Novartis Fill Stockpile Block: 21901 --- Lot: 6,7,8 HEPSCD 251 ID code #212-H-3046, plan dated 7/27/2012 | Hudson-Essex-Passaic Soil Conservation District and New Jersey Department of Environmental Protection |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 05/28/13 | Submittal May 21, 2013 Special Master Presentation (PPS) SA-6 Chromium Remedy Overview | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/31/13 | Submittal: Response to Comments re Chromium Remedy 100% Design Submittal, Issued for Construction, SA-6 North Sites 087 and 088/ SA-6 South Sites 073, 124 125, 134, 140, and 163 Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |

## Key Activities – Last Month (May 2013)

### Study Area 6 North Sites 087 and 088

- On May 14, 2013, Honeywell received comments from the Plaintiffs on the Issued for Construction (Special Master Review) Design Packages for both SA-6 North and SA-6 South Chromium Remedy projects submitted in April 2013.
- On May 20, 2013, Honeywell received comments from the Special Master on the Issued for Construction (Special Master Review) Design Packages for both SA-6 North and SA-6 South Chromium Remedy projects submitted in April 2013.
- On May 20, 2013, Honeywell received Soil Erosion and Sedimentation Control Permit from Hudson-Essex-Passaic Soil Conservation District for both SA-6 North and SA-6 South Chromium Remedy projects.
- On May 29, 2013, Honeywell received the Authorization to Discharge – 5G3 Construction Activity Stormwater (GP) from NJDEP for both SA-6 North and SA-6 South Chromium Remedy projects.
- Honeywell and Amec continued to coordinate implementation of the Site Preparation Plan activities for facility demolition and planned relocation of the Jersey City (JC) Entities.
    - Honeywell and Amec continued to coordinate with the Jersey City Entities regarding clearing of vehicles and materials from the surcharge area.
    - On June 7, 2013, Arcadis submitted the final revised draft Construction Completion Report documenting the activities related to removal of residual oil materials from the Sedimentation Basin.
- Honeywell continued efforts to develop an access agreement for the Trenk property.
- Honeywell and Amec continued to coordinate with PVSC regarding the condition assessment of the 72-inch Force Main. While technical details have been addressed between PVSC and Honeywell it appears additional reviews scheduled for June 11, 2013 with NJDEP may impact overall remedy schedule.
- Honeywell and Amec continued to meet with the Chromium Remedy contractor on a weekly basis to implement action items developed during the Constructability Review meetings.

- On May 13, 2013, Amec conducted a kick-off meeting with Amec's in-situ injection subcontractor, ISOTEC, and Jersey City Entities to discuss the mobilization and implementation schedule for the in-situ treatment of the three designated areas.

The following activities are noted as part of the Non-Chromium PDI:

  - The SVE/GWE System has been operating continuously since being re-started on March 15, 2013.
  - Amec continued monthly inspections of the select monitoring wells installed within the UST areas where separate phase product has been observed.
  - On May 19 and 20, 2013, Arcadis collected groundwater samples from the two (2) underground storage tank (UST) areas of concern (AOCs) in which Arcadis previously conducted enhanced anaerobic in-situ bioremediation (EAISB) injections to update groundwater contaminant concentrations.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).
  - The site utility contractor, Creamer, completed installation of the storm sewer lines and relocation of an existing water line. Also, installation of new 6-inch water service and two new fire hydrants was completed.
  - Amec is continuing to work with PVSC to obtain an indirect discharge permit and NJDEP to modify the existing air permit for the existing GWTP.
  - The building contractor, Oradel, commenced construction of the building foundations.
- Honeywell and Amec completed evaluation of contractor bids for implementing the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South) and issued notice to proceed with ERFS.
- The following activities are noted as part of the Non-Chromium PDI:
  - Amec continues to evaluate data from additional soil samples as part of pre-design investigation activities at Site 163 in accordance with the NJDEP-approved combined RIR/RASR/RAWP for Non-Chromium.

## Key Activities Planned for This Month (June 2013)

**Study Area 6 North Sites 087 and 088**

- Amec will continue preparation of construction-related permit applications for submittal to governing agencies for the SA-6 North and SA-6 South Chromium Remedy projects.
- Honeywell and Amec will continue to coordinate with PVSC regarding the condition assessment of the 72-inch Force Main. On June 11, 2013, Honeywell and Amec will meet with PVSC, all Parties, and NJDEP on this matter.

- Amec and ISOTEC will continue to prepare for the commencement of in-situ treatment of the three designated areas and coordinate with Jersey City Entities on the mobilization and implementation schedule.
- Honeywell and its consultants will continue the Non-Chromium activities including:
    - Amec will continue to operate and maintain the SVE/GWE system.
    - Amec will perform ongoing monthly inspections of the JCMUA-1A monitoring wells and product recovery as needed from the JCIA-1B and JCDPW UST Areas.
    - Arcadis and Amec will evaluate the additional groundwater results to evaluate the progress of the Enhanced Anaerobic Bioremediation work on JCIA-1A and JCDPW-1A AOCs.
    - Honeywell will meet with offsite property owners to coordinate the remaining offsite investigation field work for delineating the JCDPW UST area.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Amec and ERFS will prepare the Contractor Work Plan for the In-Situ Chemical Reduction Treatment Program at Site 163.
- Honeywell and Amec will continue to advance the new GWTP construction project.
- As part of the Non-Chromium remedial design process, Honeywell and Amec will:
    - Continue to support the JCRA in the Eminent Domain process at the former Harsimus Property.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**7/10/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

July 10, 2013

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 61**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from June 1 – June 30, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
Jeremy Farrell - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Joni Noble McDonnell - Genova, Burns & Giantomasi
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 61
## Project SA-6N/6S Remediation

## June 2013
**Study Area 6 North and South**
**Jersey City, NJ**

### Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/05/13 | Construction Completion Report<br>Sedimentation Basin Sludge Removal<br>Study Area 6 North<br>Hudson County Chromate Sites 087 & 088, Jersey City, New Jersey | New Jersey Department of Environmental Protection |
| 06/11/13 | Public Notification Letters (SA-6 062613 Public Meeting ) | *Distribution List* |
| 06/11/13 | TWA Permit Application to NJDEP | New Jersey Department of Environmental Protection |
| 06/11/13 | Bi-Annual Update to Public Notification Letters | *Distribution List* |
| 06/12/13 | Progress Report No. 60 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/13/13 | Public Meeting Notification Letter | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/17/13 | Draft Contractual Indirect Discharger Agreement, Customer ID # 31630016<br>New Groundwater Treatment Plant<br>Honeywell International Inc.<br>Bayfront Redevelopment LLC<br>Jersey City, New Jersey | Passaic Valley Sewerage Commission |
| 06/18/13 | Public Notification Update<br>Honeywell Study Area 6 North, Sites 087 and 088, Jersey City, Hudson County, NJ, NJDEP PI#s: G0000008710 and G0000008711 | City of Jersey City Municipal Clerk<br>Hudson Regional Health Commission |
| 06/18/13 | Conference Call: Special Master Meeting | n/a |
| 06/20/13 | 72" Force Main Relocation-Stress Analysis, Study Area 6 North (SA-6N)<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/27/13 | Draft Sewer Use Permit # 31630016<br>New Groundwater Treatment Plant<br>Bayfront Redevelopment LLC<br>Honeywell International Inc.<br>Jersey City, New Jersey | Passaic Valley Sewerage Commission |
| 06/27/13 | Response to Plaintiffs' June 11, 2013 Comments on the 100% Design Report<br>Study Area 6 North and South<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/28/13 | Response to Comments Provided by Connell Foley LLP on June 12, 2013 SA-6 North and South 100% Design Study Area 6 North and South Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |
| 06/28/13 | Chromium Remedy 100% Design Submittal, Final - Issued for Construction, SA-6 North Sites 087 and 088, SA-6 South Sites 073, 124 125, 134, 140, and 163, Jersey City, New Jersey | Honorable Robert G. Torricelli Office of the Special Master |

## Key Activities – Last Month (June 2013)

**Study Area 6 North Sites 087 and 088**

- In June 2013, Amec completed measurement of groundwater pH at selected locations along the hydraulic barrier alignment at both the SA-6 North and South Sites.
- Honeywell and Amec continued to coordinate implementation of the Site Preparation Plan activities for facility demolition and planned relocation of the Jersey City (JC) Entities.
    - Honeywell and Amec advanced the engineering cost estimate for the above-grade demolition of the JCIA structures.
- On June 11, 2013, Honeywell and Amec met with PVSC, Hatch Mott MacDonald (HMM), NJDEP, and all Parties to discuss the existing condition assessment of the 72-inch Force Main and the potential relocation of the hydraulic barrier wall. Honeywell and Amec will continue to work through technical details and will submit proposed remedial design revisions to all Parties once finalized.
- Honeywell and Amec continued to import Novartis surcharge materials to the site. The additional 30,000 cubic yards of material is expected to be onsite in early July 2013.
- On June 17, 2013, Entact, the chromium remedy excavation contractor, initiated mobilization activities at the site.
- On June 17, 2013, Amec and the in-situ injection subcontractor, ISOTEC, mobilized and initiated the in-situ treatment of two of the three designated treatment areas (Treatment Area 7 and 8). The third area (Treatment Area 10) is on hold until the potential relocation of the hydraulic barrier wall proximate to the 72-inch Force Main is finalized.
- On June 26, 2013, Honeywell held separate project update meetings with the Mayor-elect and the general public which were attended by all Parties.
- Honeywell continued efforts to develop an access agreement for the Trenk property.

The following activities are noted as part of the Non-Chromium PDI:

- The SVE/GWE System appears to be reaching asymptotic levels and Amec is collecting performance data to determine future operation.
- Amec continued monthly inspections of the select monitoring wells installed within the UST areas where separate phase product has been observed.
- Arcadis received and started evaluating analytical data from groundwater samples collected from the two (2) underground storage tank (UST) areas of concern (AOCs) in which Arcadis previously conducted enhanced anaerobic in-situ bioremediation (EAISB) injections to update groundwater contaminant concentrations.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).
  - The site utility contractor, Creamer, completed initial activities and demobilized.
  - The building contractor, Oradell, continued construction of the building foundations.
  - We continued to advance remaining permits pending with NJDEP for the air permit and Jersey City Building Department for the GWTP Building permit.
- The in-situ injection subcontractor for the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South), ERFS, continued to prepare the Implementation Work Plan.
- The following activities are noted as part of the Non-Chromium PDI:
  - Amec continues to evaluate data from additional soil samples as part of pre-design investigation activities at Site 163 in accordance with the NJDEP-approved combined RIR/RASR/RAWP for Non-Chromium.

## Key Activities Planned for This Month (July 2013)

**Study Area 6 North Sites 087 and 088**

- Honeywell will enter the 100% Designs for SA-6 North and South with the Court.
- Amec will continue preparation of construction-related permit applications for submittal to governing agencies for the SA-6 North and SA-6 South Chromium Remedy projects.
- Honeywell and Amec will continue to coordinate with PVSC regarding resolution of the barrier wall location relative to the 72-inch Force Main.
- Amec and Entact will continue mobilization activities including placement of trailers, construction of erosion controls and processing of historic fill stockpiles for surcharge.
- Honeywell and its consultants will continue the Non-Chromium activities including:
  - Amec will evaluate the need for additional operation of the SVE/GWE system.
  - Amec will perform ongoing monthly inspections of the JCMUA-1A monitoring wells and product recovery as needed from the JCIA-1B and JCDPW UST Areas.

  - Arcadis and Amec will continue to evaluate the additional groundwater results to evaluate additional full-scale implementation of the Enhanced Anaerobic Bioremediation work on JCIA-1A and JCDPW-1A AOCs.
  - Honeywell will meet with offsite property owners to coordinate the remaining offsite investigation field work for delineating the JCDPW UST area.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Amec and ERFS will prepare the Contractor Work Plan for the In-Situ Chemical Reduction Treatment Program at Site 163.
- Honeywell and Amec will continue to advance the new GWTP construction project.
- As part of the Non-Chromium remedial design process, Honeywell and Amec will:
  - Continue to support the JCRA in the Eminent Domain process at the former Harsimus Property.
  - Implement additional delineation soil samples as part of pre-design investigation activities at Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**8/12/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

August 12, 2013

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608


**Re: SA-6 North and SA-6 South Remediation Progress Report No. 62**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from July 1 – July 31, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,



William J. Hague
Director, Remediation
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
Jeremy Farrell - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Joni Noble McDonnell - Genova, Burns & Giantomasi
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 62

**Project SA-6N/6S Remediation**

## July 2013

**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 07/10/13 | Progress Report No. 61 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/23/13 | Special Master Meeting | n/a |
| 07/25/13 | Study Area 6 Excavation Approach<br>(7/23/13 SM Presentation) | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/25/13 | Application for Letter of Authorization and Contractual Indirect Discharge Agreement, Discharge of Construction Water to JCMUA Wet Well<br>Remedial Action – Study Area 6 North (SA-6 North) and Study Area 6 South (SA-6 South), Jersey City, Hudson County, New Jersey | Passaic Valley Sewerage Commission |
| 07/30/13 | Response to Comments Pertaining to the 4th Integrated Annual Groundwater Performance Report for 2012<br>Study Areas 5, 6, and 7<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## Key Activities – Last Month (July 2013)

### Study Area 6 North Sites 087 and 088

- On July 10, 2013, Honeywell entered the Final 100% Design Reports for SA-6 North and South with the Court.
- Amec and Entact continued Chromium Remedy activities:
  - Completed mobilization activities including placement of trailers and perimeter fencing;
  - Continued construction of erosion controls, and
  - Initiated processing of historic fill stockpiles for use as surcharge.
- Honeywell and Amec continued to coordinate implementation of the Site Preparation Plan activities for facility demolition and planned relocation of the Jersey City (JC) Entities.

  - Honeywell submitted the engineering cost estimate for the above-grade demolition of the JCIA structures.

- Honeywell and Amec continued technical discussions with PVSC, Hatch Mott MacDonald (HMM), NJDEP, and all Parties regarding the existing condition assessment of the 72-inch Force Main and the planned relocation of the hydraulic barrier wall.
- On August 1, 2013, Honeywell submitted technical memorandums to Special Master independently prepared by Amec and HMM indicating that the structural integrity of the 72-inch Force Main can be protected by relocating the hydraulic barrier wall 15 feet to the south of the position depicted in the 100% Design.
- Honeywell and Amec completed importation of Novartis surcharge materials to the site.
- Honeywell and Amec will prepare an amendment to the NJDEP-Discharge to Groundwater (DGW) Work Plan to address the in-situ approach for the new area resulting from the planned 15-foot relocation of the hydraulic barrier wall proximate to the 72-inch Force Main.
- Honeywell continued efforts to develop an access agreement for the Trenk property.

The following activities are noted as part of the Non-Chromium PDI:

  - The SVE/GWE System appears to be reaching asymptotic levels and Amec collected the final performance data to determine future operation.
  - Amec continued monthly inspections of the select monitoring wells installed within the UST areas where separate phase product has been observed.
  - Arcadis completed evaluating analytical data from groundwater samples collected from the two (2) underground storage tank (UST) areas of concern (AOCs) in which Arcadis previously conducted enhanced anaerobic in-situ bioremediation (EAISB) injections to update groundwater contaminant concentrations. Arcadis is currently finalizing their recommendations to Honeywell for further actions in these AOCs.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Amec and Entact continued Chromium Remedy activities.
  - Initiated collection of waste characterization soil samples from areas on SA-6 South where soil is designated for offsite disposal;
  - Initiated pre-trenching activities of the hydraulic barrier alignment and temporary excavation support sheet pile alignments; and
  - Initiated drilling and installation of shallow construction dewatering wells at Site 124.
- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).
  - All Jersey City Building Department permits for the GWTP were obtained.
  - The building contractor, Oradell, substantially completed construction of the building foundations, roughed in all sub-slab utilities, and the building floor slab.

  - The groundwater extraction piping system modification contractor, ENR, started the submittal process for extraction piping power and control modifications.
  - The building steel erection contractor, BCA, began mobilization activities.
  - On July 19, 2013, we submitted the application for the NJDEP air permit for the GWTP system.
- The in-situ injection subcontractor for the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South), ERFS, continued to prepare the Implementation Work Plan.
- The following activities are noted as part of the Non-Chromium PDI:
  - On July 24, 2013, Amec collected additional step-out soil samples as part of pre-design investigation activities at Site 163 in accordance with the NJDEP-approved combined RIR/RASR/RAWP for Non-Chromium.

## Key Activities Planned for This Month (August 2013)

### Study Area 6 North Sites 087 and 088

- Honeywell and Amec will submit design revisions to accommodate the barrier wall relocation relative to the 72-inch Force Main.
- Amec and Entact will continue Chromium Remedy activities:
  - Processing of historic fill stockpiles for surcharge; and
  - Initiate utility abandonment.
- Honeywell and its consultants will continue the Non-Chromium activities including:
  - Amec will terminate operation of the SVE/GWE system and demobilize the system.
  - Amec will perform ongoing monthly inspections of the JCMUA-1A monitoring wells and product recovery as needed from the JCIA-1B and JCDPW UST Areas.
  - Arcadis will finalize recommendations to Honeywell concerning additional full-scale implementation of the Enhanced Anaerobic Bioremediation work on JCIA-1A and JCDPW-1A AOCs.
  - On August 7, 2013, Amec collected groundwater samples from temporary well points installed on the offsite property to complete delineation of the JCDPW UST area.

### Study Area 6 South Sites 073, 124, 125, 134, 140, and 163

- Amec and Entact will continue Chromium Remedy activities:
  - Drilling and installing dewatering wells;
  - Initiate hydraulic barrier wall installation; and
  - Evaluate waste characterization soil sample results and initiate the waste profiling process.
- Amec and ERFS will complete the draft Contractor Work Plan for the In-Situ Chemical Reduction Treatment Program at Site 163.

- Honeywell and Amec will continue to advance the new GWTP construction project:
    - Pouring of remaining concrete building floor slabs;
    - Substantially complete the building shell erection; and
    - Complete the sanitary lift station.
- As part of the Non-Chromium remedial design process, Honeywell and Amec will:
    - Continue to support the JCRA in the Eminent Domain process at the former Harsimus Property.
    - Evaluate the data from the additional delineation soil samples as part of pre-design investigation activities at Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**9/12/2013**
**MONTHLY REPORT**

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

September 12, 2013

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608


**Re: SA-6 North and SA-6 South Remediation Progress Report No. 63**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from August 1 – August 31, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,



William J. Hague
Director, Remediation
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
Jeremy Farrell - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 63

**Project SA-6N/6S Remediation**

# August 2013

**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 08/01/13 | Barrier Wall Alignment w/ PVSC Force Main, Study Area 6 North<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/07/13 | Hydraulic Barrier Alignment Modification Along 72-Inch Force Main<br>SA-6 North Sites 087 and 088<br>Jersey City, NJ | Mr. Tom Cozzi, Assistant Director<br>New Jersey Department of Environmental Protection |
| 08/12/13 | Progress Report No. 62 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/13/13 | Notification of Construction<br>Remedial Action of Study Areas 6 North and South (SA-6 North and South)<br>Jersey City, Hudson County, New Jersey<br>SA-6 North: Waterfront Development Individual Permit – Upland<br>NJDEP File No: 0906-10-0004.1<br>WFD100001<br>SA-6 South: Flood Hazard Area Individual Permit/Verification<br>Coastal General Permit No. 15<br>NJDEP File No: 0906-12-0007.1<br>FHA120001/FHA120002/CAF120001 | Suzanne U. Dietrick<br>New Jersey Department of Environmental Protection |
| 08/20/13 | Special Master Meeting | n/a |

## Key Activities – Last Month (August 2013)

### Study Area 6 North Sites 087 and 088

- Amec and Entact continued Chromium Remedy activities as follow:
  - Completed construction of erosion controls;
  - Continued processing of historic fill stockpiles for use as surcharge;
  - Initiated utility abandonment; and
  - Completed the construction access road across SA-7 and the ramp and new gate between SA-6 North and SA-7.
- Honeywell and Amec continued to coordinate implementation of the Site Preparation Plan activities for facility demolition and planned relocation of the Jersey City (JC) Entities.

- Honeywell and Amec continued technical discussions with PVSC, Hatch Mott MacDonald (HMM), NJDEP, and all Parties regarding the existing condition assessment of the 72-inch Force Main and the planned relocation of the hydraulic barrier wall.
- Honeywell and Amec continued to amend the NJDEP-Discharge to Groundwater (DGW) Work Plan to address the in-situ approach for the new area resulting from the planned 15-foot relocation of the hydraulic barrier wall proximate to the 72-inch Force Main.
- Honeywell continued efforts to develop an access agreement for the Trenk property.

The following activities are noted as part of the Non-Chromium PDI:

  - Operation of the SVE/GWE System was terminated and the System trailer was decontaminated and demobilized from the Site and the electrical service drop was removed.
  - Amec continued monthly inspections of the select monitoring wells installed within the UST areas where separate phase product has been observed.
  - Amec evaluated groundwater sample results from temporary well points installed on the offsite property to complete delineation of the JCDPW UST area. Results indicate delineation is complete.
  - Arcadis is finalizing proposals for remaining enhanced anaerobic in-situ bioremediation (EAISB) injections.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Amec and Entact continued Chromium Remedy activities as follow:
  - Continued collection of waste characterization soil samples from areas where soil is designated for offsite disposal (including soils with hexavalent chromium >1,000 mg/kg and non-chromium soils areas which are being remediated concurrently);
  - Initiated vibration monitoring at the diner located on the Kellogg Street jughandle;
  - Continued pre-trenching activities and initiated installation of sheeting within the hydraulic barrier alignment on Sites 073, 124, 125, and 134 and temporary excavation support sheet pile alignments;
  - Continued drilling and installation of shallow construction dewatering wells at Site 124 and initiated installation of the construction groundwater extraction system; and
  - Completed coordination with PSE&G Electrical group for temporary rerouting of overhead electric for installation of the 150 linear foot of hydraulic barrier wall running along the NJDOT right of way; and,
  - Continued reviews with NJDOT regarding a temporary use permit for temporary sheeting, excavating and grading proximate to the Kellogg Street jughandle.
- Amec and Ontario Specialty Contracting completed permitting, asbestos abatement, and initiated demolition of the warehouse portion of the 60 Kellogg Street building.
- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).

  - The building contractor, Oradell, substantially completed installation of the sanitary sewer lift station and substantially completed the exterior truck loading pad, and continued working on process control equipment submittals.
  - The groundwater extraction piping system modification contractor, ENR, continued the submittal process for extraction piping power and control modifications.
  - BCA/Clinton Steel, began steel erection activities of the building shell.
  - On September 9, 2013, we submitted responses to NJDEP technical review comments received in August regarding the NJDEP air permit for the GWTP system.
- On September 6, 2013, Honeywell submitted the contractor work plan for the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South).
- The following activities are noted as part of the Non-Chromium PDI:
  - Amec evaluated the analytical results from the additional at Site 163 in accordance with the NJDEP-approved combined RIR/RASR/RAWP for Non-Chromium and concluded that delineation is complete.

## Key Activities Planned for This Month (September 2013)

**Study Area 6 North Sites 087 and 088**

- Honeywell and Amec will submit revised design drawings to depict the agreed upon barrier wall relocation of 25 feet from the 72-inch Force Main centerline.
- Amec and Entact will continue Chromium Remedy activities:
  - Processing of historic fill stockpiles for surcharge;
  - Initiate construction of the construction water treatment system; and,
  - Installation of surcharge monitoring and acoustical monitoring equipment.
- Honeywell and its consultants will continue the Non-Chromium activities including:
  - Amec will perform ongoing monthly inspections of the JCMUA-1A monitoring wells and product recovery as needed from the JCIA-1B and JCDPW UST Areas.
  - Arcadis will continue to modify the Discharge to Groundwater-Permit By Rule Authorization, and plan for mobilization by the end of October.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

- Amec and Entact will continue Chromium Remedy activities:
  - Drilling and installing dewatering wells and installation of the groundwater extraction system;
  - Complete pre-trenching for the hydraulic barrier at Sites 125 and 134;
  - Continue hydraulic barrier wall installation, including grouting the joints between the sheets in the hydraulic barrier;
  - Continue installation of sheeting for temporary excavation support; and

  - Continue to evaluate waste characterization soil sample results and initiate the waste profiling process.

- Honeywell and Amec will continue to advance the new GWTP construction project:
  - Initiate installation of groundwater extraction treatment system modifications;
  - Substantially complete the building shell erection; and
  - Initiate installation of process control equipment.
- As part of the Non-Chromium remedial design process, Honeywell and Amec will:
  - Continue to support the JCRA in the Eminent Domain process at the former Harsimus Property.
  - Finalize the design of the excavation based on the additional soil delineation data collected at Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**10/11/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

October 11, 2013

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 64**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from September 1 – September 30, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Derek Fanciullo – City Hall
Jeremy Farrell - City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 64
## Project SA-6N/6S Remediation

# September 2013
**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 09/03/13 | Adjustment of Barrier Wall for Study Area 6 North | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/06/13 | ERFS' In-Situ Chemical Reduction Implementation Work Plan<br>SA-6 South Site 163<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/12/13 | Progress Report No. 63 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/12/13 | Supplemental Chromium Remedy 100% Design Submittal<br>Hydraulic Barrier Wall Alignment<br>Study Area 6 North Sites 087 and 088<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/17/13 | Special Master Meeting | n/a |
| 09/19/13 | Public Notification Update<br>Study Areas 1, 3, 5, 6 and 7<br>Jersey City, NJ | Mr. David Doyle, Case Manager<br>New Jersey Department of Environmental Protection |
| 09/19/13 | Public Notification Update<br>Honeywell Study Areas 1, 3, 5, 6 and 7<br>Jersey City, Hudson County, NJ | Robert Byrne<br>City of Jersey City Municipal Clerk<br><br>Carrie Nawrocki, Executive Director<br>Hudson Regional Health Commission |

## Key Activities –September 2013

### Study Area 6 North Sites 087 and 088

Amec and Entact continued Chromium Remedy activities as follow:

- Completed construction of the temporary construction water treatment plant (CWTP).
- Completed construction of the double-walled piping for transfer of construction water from SA-6 South across SA-7 to the CWTP on SA-6 North.
- Installed settlement plates in the Sedimentation Basin and surrounding area for monitoring consolidation of subsurface strata during surcharging.

The following activities are noted as part of the Non-Chromium PDI:

- On behalf of Honeywell, Amec submitted requests to terminate permits obtained from NJDEP and PVSC for operation of the SVE/GWE System.
- Arcadis finalized their proposal for remaining enhanced anaerobic in-situ bioremediation (EAISB) injections.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

Amec and Entact continued Chromium Remedy activities as follows:

- Continued vibration monitoring at the diner located on the Kellogg Street jughandle.
- Completed installation of sheeting within the hydraulic barrier alignment on Sites 073, 124, 125, and most of Site 134, and temporary excavation support sheet pile alignments.
- Completed grouting of sheet pile interlocks on the installed hydraulic barrier alignment.
- Completed pre-trenching of temporary excavation support sheet pile alignments along the northern boundary of Site 163.
- Completed drilling and installation of shallow and deep construction dewatering wells at Site 124 and completed the installation of the construction groundwater extraction system.
- Completed coordination with PSE&G Electrical group for temporary rerouting of overhead electric for installation of the 150 linear foot of hydraulic barrier wall running along the NJDOT right of way.
- Completed reviews with NJDOT and obtained a temporary use permit for temporary sheeting, excavating and grading proximate to the Kellogg Street jughandle.

Activities by others:

- Amec and Ontario Specialty Contracting completed demolition of the warehouse portion of the 60 Kellogg Street building.
- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP).
- On September 25, 2013, Honeywell received comments from the Plaintiffs on the contractor work plan for the In-Situ Chemical Reduction Treatment Program at Site 163 (SA-6 South). Honeywell is currently preparing a response.

## Key Activities Planned for This Month (October 2013)

**Study Area 6 North Sites 087 and 088**

Amec and Entact will continue Chromium Remedy activities:

- Processing of historic fill stockpiles for surcharge.
- Coordinate PVSC and JCMUA inspections on the construction water treatment system.
- Installation of surcharge monitoring and acoustical monitoring equipment.

Activities by others:

- Honeywell and Amec will submit revised design drawings to depict the agreed upon barrier wall relocation relative to the 72-inch Force Main centerline.
- Arcadis will submit a modification to the NJDEP Discharge to Groundwater-Permit By Rule Authorization.
- Arcadis will finalize their report summarizing the results of their Phase I EAISB in the JCIA UST AOC. Honeywell will submit this report to NJDEP and ask for closure of the UST Case Number.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

Amec and Entact will continue Chromium Remedy activities:

- Initiate dewatering and excavation at Site 124.
- Continue hydraulic barrier wall installation, including grouting the joints between the sheets in the hydraulic barrier at Site 134.
- Continue installation of sheeting for temporary excavation support.
- Continue the waste profiling process.
- Continue to advance the new GWTP construction project.

As part of the Non-Chromium remedial design process, Honeywell and Amec will:

- Finalize the design of the excavation based on the additional soil delineation data collected at Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**11/12/2013**
**MONTHLY REPORT**

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

November 12, 2013

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608


**Re: SA-6 North and SA-6 South Remediation Progress Report No. 65**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from October 1 – October 31, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,



William J. Hague
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 65
## Project SA-6N/6S Remediation

# October 2013
**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 10/08/13 | Non-Chromium Remedy Update - JCIA-1 UST AOC Study Area 6 North Hudson County Chromate Site 088, Jersey City, New Jersey | Mr. Thomas Cozzi, Assistant Director New Jersey Department of Environmental Protection |
| 10/09/13 | Response to Comments Provided by PVSC in September 9, 2013 letter Draft Sewer Use Permit # 31630019 Study Area 6 North and Study Area 6 South, Jersey City, New Jersey | Anthony Gammaro Assistant Manager, User Charge and Permit Management Passaic Valley Sewerage Commission |
| 10/11/13 | Study Area 6 North and South Progress Report No. 64 | Honorable Robert G. Torricelli Office of the Special Master |
| 10/15/13 | Special Master Conference Call | n/a |
| 10/21/13 | Posted to The Louis Berger SharePoint Site: Public Notification Update Study Areas 1, 3, 5, 6 and 7 Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |
| 10/23/13 | Posted to The Louis Berger SharePoint Site: Study Area 6 North and South: First Amendment to Memorandum of Understanding Between Honeywell and PVSC | Honorable Robert G. Torricelli Office of the Special Master |
| 10/24/13 | Response to Comments Provided by Terris, Pravlik & Millian, LLP Honeywell Chromium Remedy In-Situ Contractor Implementation Work Plan SA-6 South Site 163 Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |
| 10/24/13 | Arnold & Porter Correspondence: Consent Order Entering Revised Drawings for Study Area 6 North Barrier Wall | Honorable Robert G. Torricelli Office of the Special Master |
| 10/29/13 | Posted to The Louis Berger SharePoint Site: PVSC Sewer Use Permit - 31630016 | Honorable Robert G. Torricelli Office of the Special Master |

## Key Activities –October 2013

### Study Area 6 North Sites 087 and 088

Amec and Entact continued Chromium Remedy activities as follow:

- On October 8, 2013, Passaic Valley Sewerage Commission (PVSC) inspected the discharge piping and flow meter calibration prior to startup of the temporary construction water treatment system (CWTS).
- Continued processing historic fill stockpiles for use as surcharge.

The following activities are noted as part of the Non-Chromium PDI:

- Amec initiated an evaluation of debris disposal options, which is being screened from the historic fill soil piles located at SA-6 North and is unsuitable for surcharge.
- Arcadis initiated modifications to the existing NJDEP-approved EAISB Work Plan/Discharge to Groundwater-Permit by Rule, dated March 25, 2013 and is preparing to implement the remaining enhanced anaerobic in-situ bioremediation (EAISB) injections.

### Study Area 6 South Sites 073, 124, 125, 134, 140, and 163

Amec and Entact continued Chromium Remedy activities as follows:

- Continued hydraulic barrier wall installation, including the eastern edge of the open space area along Route 440, and continued grouting the joints between the sheets in the hydraulic barrier at Site 134.
- Initiated drilling and installation of surcharge monitoring instrumentation in the cap areas at Site 124 and Site 125.
- Initiated dewatering and excavation at Site 124 and offsite transportation and disposal of soils impacted with hexavalent chromium >1,000 milligrams per kilogram (mg/kg).
- Initiated sampling of less than 20 mg/kg soils in accordance with approved plans.

Activities by others:

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP). The building is complete and the major treatment components are in-place with piping and process control wiring installation continuing.

## Key Activities Planned for This Month (November 2013)

### Study Area 6 North Sites 087 and 088

Amec and Entact will continue Chromium Remedy activities:

- Processing of historic fill stockpiles for surcharge.
- Installing the surcharge monitoring instrumentation proximate to the 72-inch forcemain.

Activities by others:

- Arcadis will prepare a modification to the NJDEP Discharge to Groundwater-Permit By Rule Authorization.
- Honeywell and Amec will coordinate with PVSC and Hatch Mott McDonald to install acoustical monitoring equipment proximate to the 72-inch forcemain.
- Honeywell and Amec will continue to develop the in-situ approach for Treatment Area 10 proximate to the 72-inch forcemain.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

Amec and Entact will continue Chromium Remedy activities:

- Continue dewatering and excavation at Site 124, including offsite transportation and disposal of soils impacted with hexavalent chromium >1,000 mg/kg.
- Complete hydraulic barrier wall installation except proximate to 80 Kellogg Street which is inaccessible until demolition.
- Continue installation of sheeting for temporary excavation support.
- Continue the waste profiling process.
- Continue to advance the new GWTP construction project.

Activity by others:

- Honeywell and Amec will coordinate potential mobilization dates with ERFS to begin in-situ treatment of soils at Site 163.

As part of the Non-Chromium remedial design process, Honeywell and Amec will:

- Finalize the disposal selection for non-chromium impacted materials on Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**12/13/2013**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

December 13, 2013

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 66**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from November 1 – November 30, 2013.

We are in the process of evaluating the SA-6 North and South, and SA-7 Progress Reports, with plans of combining and expanding the content with regards to operation data in 2014 (February 2014 report focusing on January 2014 activities). We anticipate having a draft outline prepared in January which we will share with the Parties.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 66
## Project SA-6N/6S Remediation

# November 2013
**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 11/06/13 | Revised Master Schedule for Study Area 6 North and South | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/07/13 | Integrated Groundwater Sampling and Analysis Plan<br>(Study Areas 5, 6, and 7) | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/11/2013 | Filed Order with Court on Location of Hydraulic Barrier Wall | U.S. District Court (D.NJ) |
| 11/12/13 | SA-6 North and South Progress Report No. 65 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/13/13 | SA-6 Chromium Remedy<br>Waste Characterization Sampling Plan<br>SA-6 North Sites 087 and 088<br>SA-6 South Sites 073, 124, 125, 134, 140, and 163<br>Jersey City, New Jersey | Mr. David Doyle, Case Manager<br>New Jersey Department of Environmental Protection |
| 11/15/13 | Correspondence on Droyer's Cove Beneficial Environmental Project (Study Areas 6 and 7) | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/15/13 | Draft Study Area 6 Excavation Declaration | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/19/13 | Special Master Meeting | n/a |
| 11/21/13 | Draft Sewer Use Permit # 31630019<br>Study Area 6 North and Study Area 6 South<br>Bayfront Redevelopment LLC<br>Honeywell International Inc.<br>Jersey City, New Jersey | Anthony Gammaro<br>Passaic Valley Sewerage Commission |

## Key Activities –November 2013

### Study Area 6 North Sites 087 and 088

Amec and Entact continued Chromium Remedy activities as follow:

- Used soft dig approach to uncover the crown of the 72-inch force main for installation of surcharge monitoring instrumentation on the pipeline. Passaic Valley Sewerage Commission (PVSC) and their subcontractors Hatch Mott MacDonald and Pure Technologies concurrently installed the acoustical monitoring equipment.
- Continued processing historic fill stockpiles for use as surcharge.

- Honeywell and Amec continued to develop the revised in-situ work plan to address the expanded Treatment Area 10 footprint proximate to the 72-inch force main.

The following activities are noted as part of the Non-Chromium PDI:

- Arcadis continued modifications to the existing NJDEP-approved EAISB Work Plan/Discharge to Groundwater-Permit by Rule, dated March 25, 2013 and is preparing to implement the remaining enhanced anaerobic in-situ bioremediation (EAISB) injections.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

Amec and Entact continued Chromium Remedy activities as follows:

- Completed hydraulic barrier wall installation, except proximate to 60 Kellogg Street and 80 Kellogg Street which is inaccessible until demolition. Completed installation locations include the western edge of the Open Space Area near the Hackensack River, and grouting the joints between the installed sheets in the hydraulic barrier at Site 134.
- Continued dewatering and excavation at Site 124 and offsite transportation and disposal of soils impacted with hexavalent chromium >1,000 milligrams per kilogram (mg/kg).
- Initiated backfilling of completed excavation areas in the eastern part of Site 124.
- Continued drilling and installation of surcharge monitoring instrumentation in the cap areas at Site 124 and Site 125.
- Continued sampling of less than 20 mg/kg soils in accordance with approved plans. Data was obtained from the first pile sampled in October and approved to be reused.

Activities by others:

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP). The primary activities include continuing installation of process piping and process control wiring.

## Key Activities Planned for This Month (December 2013)

**Study Area 6 North Sites 087 and 088**

Amec and Entact will continue Chromium Remedy activities:

- Processing of historic fill stockpiles for surcharge.
- Continue to install surcharge monitoring instrumentation.

Activities by others:

- Arcadis will continue to prepare the modification to the NJDEP Discharge to Groundwater-Permit By Rule Authorization.
- Honeywell and Amec will continue to coordinate with PVSC and Hatch Mott MacDonald on the acoustical monitoring instrumentation installed on the 72-inch force main.
- Honeywell and Amec will complete the revisions to the in-situ work plan for the expanded Treatment Area 10 footprint proximate to the 72-inch force main.

**Study Area 6 South Sites 073, 124, 125, 134, 140, and 163**

Amec and Entact will continue Chromium Remedy activities:

- Continue dewatering and excavation at Site 124, including offsite transportation and disposal of soils impacted with hexavalent chromium >1,000 mg/kg.
- Continue installation of sheeting for temporary excavation support.
- Continue the waste profiling process.
- Continue to advance the new GWTP construction project.

Activity by others:

- Honeywell and Amec will schedule a technical meeting or conference call with all Parties to as requested by Plaintiffs in their letter dated November 18, 2013 on the Site 163 Contractor In-situ Work Plan.

As part of the Non-Chromium remedial design process, Honeywell and Amec will:

- Finalize the disposal selection for non-chromium impacted materials on Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**2014 MONTHLY REPORTS**
**PART 1**

**1/14/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

January 14, 2014

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Re: SA-6 North and SA-6 South Remediation Progress Report No. 67**

Dear Senator Torricelli:

Attached is the Chromium Remedy Monthly Progress Report for Study Areas 6 North and South for activities conducted by Honeywell during the period from December 1 – December 31, 2013.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Engineering and Construction

WJH:sg

Encl.

cc: (electronic)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# HEALTH, SAFETY, ENVIRONMENTAL AND REMEDIATION
# MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 67
## Project SA-6N/6S Remediation

# December 2013
**Study Area 6 North and South**
**Jersey City, NJ**

## Submittals and Meetings

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 12/05/13 | Arnold & Porter correspondence to the Special Master re Consolidation of Cases Related to Study Areas 5, 6, and 7 | Honorable Robert G. Torricelli Office of the Special Master |
| 12/10/13 | Application for Permit<br>Type 4 Permit for Chemical Storage<br>Groundwater Treatment Plant<br>Bayfront Redevelopment, LLC<br>Block 21901; Lots 9 & 10 (Formerly Block 1290.A; Lot, 2E & 2D)<br>Jersey City, Hudson County, New Jersey | Jersey City Fire Department<br>Fire Prevention Division |
| 12/10/13 | Revised Master Schedule for Study Area 6 North and South | Honorable Robert G. Torricelli Office of the Special Master |
| 12/13/13 | Progress Report No. 66 | Honorable Robert G. Torricelli Office of the Special Master |
| 12/17/13 | Special Master Conference Call | n/a |
| 12/20/13 | Re: Request for Extension for Submittal of Local Limit Baseline Monitoring Report & Slug Control Questionnaire<br>Permit # 31630016, New Groundwater Treatment Plant<br>Honeywell International Inc.<br>Jersey City, Hudson County, New Jersey | Andrew Caltagirone - Passaic Valley Sewerage Commission |
| 12/20/13 | SA-6 Chromium Remedy, Certificate of Authority to Operate (CAO) a Beneficial Use Project Application (BUD)<br>SA-6 North Sites 087 and 088<br>SA-6 South Sites 073, 124, 125, 134, 140, and 163, Jersey City, New Jersey | New Jersey Department of Environmental Protection |
| 12/20/13 | Notification of upload of the following submittal to the LB SharePoint Site:<br>SA-6 Chromium Remedy, Certificate of Authority to Operate (CAO) a Beneficial Use Project Application (BUD)<br>SA-6 North Sites 087 and 088<br>SA-6 South Sites 073, 124, 125, 134, 140, and 163, Jersey City, New Jersey | Honorable Robert G. Torricelli Office of the Special Master |
| 12/20/13 | SA-6 Chromium Remedy<br>Waste Characterization Sampling Plan<br>SA-6 North Sites 087 and 088<br>SA-6 South Sites 073, 124, 125, 134, 140, and 163. Jersey City, New Jersey | Mr. David Doyle - New Jersey Department of Environmental Protection |

## Key Activities –December 2013

### Study Area 6 North Sites 087 and 088

Amec and Entact continued Chromium Remedy activities as follow:

- Completed installation of surcharge monitoring instrumentation on the 72-inch force main. Passaic Valley Sewerage Commission (PVSC) and their subcontractors Hatch Mott MacDonald and Pure Technologies initiated baseline acoustical monitoring.
- Completed processing historic fill stockpiles for use as surcharge and demobilized the screening equipment.
- Honeywell and Amec continued to develop the revised in-situ work plan to address the expanded Treatment Area 10 footprint proximate to the 72-inch force main.

The following activities are noted as part of the Non-Chromium PDI:

- Arcadis continued modifications to the existing NJDEP-approved EAISB Work Plan/Discharge to Groundwater-Permit by Rule, dated March 25, 2013 and is preparing to implement the remaining enhanced anaerobic in-situ bioremediation (EAISB) injections.

### Study Area 6 South Sites 073, 124, 125, 134, 140, and 163

Amec and Entact continued Chromium Remedy activities as follows:

- Continued to receive shipments of steel sheet pile in preparation for completing 60 Kellogg, 80 Kellogg and the SA-6 North section of barrier wall installation proximate to the 72-inch force main.
- Continued dewatering and excavation at Site 124 and offsite transportation and disposal of soils impacted with hexavalent chromium >1,000 milligrams per kilogram (mg/kg).
- Continued backfilling of completed excavation areas in the eastern and central parts of Site 124.
- Continued drilling and installation of surcharge monitoring instrumentation in the cap areas at Site 134.
- Continued sampling of less than 20 mg/kg soils in accordance with approved plans. Data was obtained from the stockpiles sampled in November and December and approved for reuse.

Activities by others:

- Honeywell and Amec continued to advance activities associated with construction of the new Groundwater Treatment Plant (GWTP). The primary activities include final installation of process piping and process control wiring and completion of punch list items on the building for final Jersey City inspections.

## Key Activities Planned for This Month (January 2014)

### Study Area 6 North Sites 087 and 088

Amec and Entact will continue Chromium Remedy activities:

- Relocation of non-suitable debris (generated from processing historic fill stockpiles) out of active work areas.
- Continue drilling and installation of surcharge monitoring instrumentation in the western portion of the cap area.
- Initiate abandonment of the former 54-inch Sedimentation Basin discharge pipe.

Activities by others:

- Arcadis will finalize the modification to the NJDEP Discharge to Groundwater-Permit By Rule Authorization.
- PVSC, Hatch Mott MacDonald, and Pure Technologies will continue acoustical monitoring as needed.
- Honeywell and Amec will complete the revisions to the in-situ work plan for the expanded Treatment Area 10 footprint proximate to the 72-inch force main.

### Study Area 6 South Sites 073, 124, 125, 134, 140, and 163

Amec and Entact will continue Chromium Remedy activities:

- Continue dewatering and excavation at Site 124, including offsite transportation and disposal of soils impacted with hexavalent chromium >1,000 mg/kg.
- Initiate stockpile sampling of soils with presumed hexavalent chromium >1,000 mg/kg.
- Continue the waste profiling process.
- Continue to advance the new GWTP construction project including initiating commissioning activities.

Activity by others:

- Honeywell and Amec will schedule a technical meeting or conference call with all Parties as requested by Plaintiffs in their letter dated November 18, 2013 on the Site 163 Contractor In-situ Work Plan.

As part of the Non-Chromium remedial design process, Honeywell and Amec will:

- Finalize the disposal selection for non-chromium impacted materials on Site 163.

Prepared By:
W.J. Hague - Honeywell
J.T. Clifford - Amec

**2/14/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

February 14, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Progress Report No. 2014-01**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for both Study Areas 6 and 7 for activities conducted by Honeywell during the period from January 1 – January 31, 2014. This report follows the updated outline which was provided to the Parties in our January 14, 2014 correspondence. Please note that we have taken this opportunity to change the Progress Report numbering system more accurately to tie-in to the reporting month.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: January 2014 SA-6/7 Combined Monthly Progress Report No. 2014-01

cc: Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)

Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2014-01
### Project SA-6 & 7 Remediation

## January 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 01/02/14 | SA-6 Chromium Remedy<br>Waste Characterization Sampling Plan<br>SA-6 North Sites 087 and 088<br>SA-6 South Sites 073, 124, 125, 134, 140, and 163,<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/07/14 | Response to Comments Provided by<br>Terris, Pravlik & Millian, LLP<br>Chromium Remedy Backfill<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/07/14 | Arnold & Porter correspondence: SA-7 Sediment<br>Consent Order – Revised Master Schedule<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/14/14 | Progress Report No. 67<br>Study Area 6, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/14/14 | Progress Report No. 128<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/14/14 | Draft Combined Remediation Monthly Progress<br>Report<br>Study Area 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/16/14 | PVSC MR1/MR2 (Discharge of Tannin Construction<br>Water)<br>Study Area 7, Jersey City, NJ | Andy Caltagirone<br>Passaic Valley Sewerage<br>Commissioners |
| 01/21/14 | Meeting: Special Master All Hands Meeting | N/A |
| 01/23/14 | Surface Water DMR (December 2013)<br>Study Area 7, Jersey City, NJ *(see **Attachment 12**)* | State of New Jersey<br>Department of Environmental<br>Protection |
| 01/23/14 | Excavation Bottom Approach Special Master Meeting<br>(1/21/14 Presentation)<br>Study Area 6 South, Jersey City, NJ | Uploaded to the Louis Berger<br>SharePoint Site |
| 01/28/14 | Arnold and Porter Correspondence on Study Area 7<br>Sediment Declaration | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/29/14 | Work Plan for In-Situ Treatment of Chromium-<br>Impacted Soils<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/29/14 | Revised Master Schedule<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/05/14 | 01/12/14 | 01/19/14 | 01/26/14 | 02/02/14 |
| Construction Management (AMEC) | 4 | 9 | 9 | 9 | 9 |
| Engineering (AMEC) | 2 | 2 | 2 | 2 | 1 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 26 | 34 | 33 | 30 | 37 |
| Arecon/US Ecology Subcontractors | 1 | 2 | 2 | 2 | 3 |
| Oradell (SA-6N GWTP Building Mech/ Plumbing/HVAC) | 8 | 8 | 7 | 3 | 5 |
| ENR (SA-6N GWTP Utilities) | 3 | 5 | 4 | 5 | 3 |
| BCA (SA-6N Building Construction) | 1 | 1 | 0 | 0 | 0 |
| Siemens | 1 | 3 | 4 | 1 | 1 |
| HBS (SA-6N GWTP Security System) | 0 | 0 | 1 | 1 | 1 |
| HPS (SA-6N GWTP Process Controls) | 0 | 1 | 1 | 1 | 0 |
| Other | 0 | 0 | 0 | 0 | 0 |
| **TOTAL** | **50** | **69** | **67** | **58** | **64** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued new Ground Water Treatment Plant (GWTP) construction activities to include completion of operational commissioning, and PW-1 and PW-2 piping connections into new GWTP.
- Passed final Jersey City Inspections for GWTP Building Electrical, Plumbing, Fire & Life Safety and placed initial order for GWTP chemical deliveries.
- Initiated decommissioning activities for exterior ModuTanks at 80 Kellogg Street WWTP.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Completed numerous snow removal events on SA-6N and SA-6S.
- Collected PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Non-chromium activities, ARCADIS continues to work with NJDEP on the modification to the existing NJDEP-Discharge to Groundwater Permit by Rule for additional Enhanced Anaerobic in-situ bioremediation (EAISB) injections planned for JCMUA and JCDPW UST Areas.

## C. 80 KELLOGG GROUND WATER TREATMENT PLANT

- Hydrochloric acid cleaning was performed for three micro filter trains (MF-1).
- Filter cake container changed-out (Arecon-FCI) on January 13th.
- January monthly and quarterly effluent DMR samples were collected.
- Began cleaning sludge tanks in treatment plant.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/05/14 | 01/12/14 | 01/19/14 | 01/26/14 | 02/02/14 |
| Avg. Gallons Treated & Discharged (per day) | 84,034 | 86,312 | 89,299 | 76,112 | 86,558 |
| Average Flow (gpm) for Operating Period | 156 | 140 | 167 | 161 | 171 |
| Avg. Hours of Plant Operation | 9 | 11 | 9 | 8 | 8 |
| GWTP ModuTanks (gal.) | 151,880 | 149,120 | 148,760 | 111,360 | 144,180 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in Cells 25 through 37.
- Petroleum-impacted soils were identified during excavation activities via field observations and PID. These materials were separately stockpiled and sampled for off-site disposal.
- Completed pre-trench activities for Vertical Hydraulic Barrier Wall within the 60 Kellogg employee parking lot.
- Continued storm-water management activities.
- Continued dewatering activities and associated discharge to the construction water treatment facility.
- Continued backfill placement activities and associated compaction testing.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 19.50 | 19.50 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 150 | 21.86 | 3,278.36 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Entact/ Venerio** | Tri-axle Dump | Middlesex City Landfill | NA | Hg Impacted material (non–haz) | 3 | 21.50 | 64.50 |
| **Entact/ Tilcon** | Tri-axle Dump | Tilcon | NA | Asphalt for Recycling | 27 | 25.09 | 677.45 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 36, 37 |
| **Excavation Completed** | Cell Number(s) 25 through 35 |
| **Backfill in Progress** | Cell Number(s) 1 through 20 |

### 3. BACKFILL MATERIALS USED

| Source | Pre 12/31/13 Summaries | (Week Ending) | | | | |
|---|---|---|---|---|---|---|
| | | 01/05/14 | 01/12/14 | 01/19/14 | 01/26/14 | 02/02/14 |
| <20ppm re-use, CY | 500 | 0 | 0 | 0 | 0 | 0 |
| Weldon, Import-Tons | 4,769.01 | 1,383.31 | 1743 | 1,035.01 | 1725.36 | 3,344.31 |
| Tilcon, Import-Tons | 4,290.83 | 0 | 0 | 0 | 0 | 0 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Instrumentation Installation ~30% complete. No Surcharge Initiated.
- Area 2S: Instrumentation Installation ~75% complete. Completion dependent upon Building Demolition. No Surcharge Initiated.
- Area 3S: Instrumentation Installation 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. Surcharge placement not initiated.
- Area 1N: Instrumentation Installation ~60% complete. No Surcharge initiated.
- Area 2N: No instrumentation installed. Settlement platforms have been installed in the sedimentation basin to the north of Area 2 and portion of the Sedimentation Basin has been temporarily filled with screened materials that will be used for Surcharging the designated Surcharge Areas.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/15 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/12 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP | SA-6 Chromium Remedy | Final anticipated Feb 2014, Using Temp Permit Now Issued 9/1/13 | Pending | Pending | - |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/15 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/14 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2015 | 6/23/2015 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/12 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/13 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## G. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete abandonment in place of the former 54-inch discharge pipe from the Sedimentation Basin.
- Initiate steel sheeting installation of barrier wall proximate to the 72-inch force main (FM), pending delivery of the spare FM section and coordination with PVSC.
- Initiate dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 36 through 46.
- Beginning with Cell 31, stockpile potential >1,000 mg/kg soils for sampling.
- Complete waste characterization and coordinate off-site disposal of petroleum-impacted soils.
- Continue backfill and associated compaction test activities.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Complete new GWTP commissioning.
- Continue decommissioning of 80 Kellogg Ground Water Treatment Plant.
- Continue SWPPP inspections.
- Complete PVSC compliance sampling.


**ATTACHMENTS:**

1: Schedule – 6 Month Look Ahead
2: Site Photographs
3: Excavation and Backfill
   - Progression Chart
   - Weekly Excavation and Survey Data (Excavation Bottom Elevations and corresponding Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/Sidewall Confirmatory Points)
   - Backfill Compaction Locations
   - Field Density Test Summary Log
4: Dewatering Operations Update
   - Figure 6: Well Point Dewatering System *(included in initial submittal only)*
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-1)
   - SA-6 South Deep Well Data (DW-2)
5: SA-6 Construction Water Discharge Data (To PVSC)
6: Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7: Perimeter Pools Update
8: Quality and Level Data in GWET Wells *( not included in this submittal -provided on a quarterly basis)*
9: Surcharge Monitoring Update
   - Surcharge Monitoring Plan Report Figures *(included in initial submittal only)*
10: Sheet Pile Update
   - Hydraulic Barrier Wall Plan & Profile
   - Sheet Deflection Along Open Excavation
11: Weekly SWPPP Reports
12: 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (December 2013 Correction and January 2014 DMR)

## Attachment 1:  Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Tue 2/4/14

Task  Milestone  Summary  Critical

## Attachment 2: Site Photographs




**Site Photograph 1:** A worker decons a truck leaving the EZ.




**Site Photograph 2:** Backfill is piled against the sheetpile hydraulic barrier.




**Site Photograph 3:** Backfill lift being installed over crushed concrete.




**Site Photograph 4:** Contractor breaks up the 60 Kellogg warehouse slab.




**Site Photograph 5:** Contractor clears snow from the backfill area.




**Site Photograph 6:** Contractor excavates in Cell No 30.




**Site Photograph 7:** Contractor pushes out a lift of backfill material.




**Site Photograph 8:** Contractor scrapes the Stratum D excavation floor.

## Attachment 3: Excavation and Backfill

- Progression Chart
- Weekly Excavation and Survey Data (Excavation Bottom Elevations and corresponding Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/Sidewall Confirmatory Points)
- Backfill Compaction Locations
- Field Density Test Summary Log

# Jersey City & Kellogg Street Properties Remedies
# Progress as of February 1, 2014

January 2014 SA-6/7 Progress Report
Attachment 3: Excavation and Backfill

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties


Former Roosevelt Drive-In Site
(Remediation Complete)

Kellogg Street Properties

Route 440

Hackensack River

Kellogg Street




LEGEND

- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 12-13-13 TO 01-09-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points

| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7* | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5* | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6* | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7* | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9* | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9* | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1* | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4* | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area

* Elevation based on Surveyed Center Point

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

Note: Data shown is for recent months activity


| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Sidewall Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 4.9 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |

Note: Data shown is for recent months activity




LEGEND

| | |
|---|---|
| 0.0 POINT ELEVATION | CONFIRMATORY BOTTOM SAMPLE ELEVATION |
| POINT POINT DESCRIPTION | CONFIRMATORY SIDEWALL SAMPLE ELEVATION |
| BOTTOM CENTER POINT ELEVATION STRATUM D | BOTTOM CENTER POINT ELEVATION <20 PPM |
| PREVIOUSLY SUBMITTED DATA | CURRENT EXCAVATION TO STRATUM D |
| CURRENT EXCAVATION TO <20 PPM | |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 01-10-14 TO 01-16-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points

| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7* | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5* | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6* | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7* | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9* | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9* | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1* | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4* | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3* | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4* | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1* | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area

* Elevation based on Surveyed Center Point

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |


Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Sidewall Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 4.9 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |




LEGEND

| | |
|---|---|
| X 0.0 POINT ELEVATION | |
| POINT POINT DESCRIPTION | |
| CONFIRMATORY BOTTOM SAMPLE ELEVATION | BOTTOM CENTER POINT ELEVATION STRATUM D |
| CONFIRMATORY SIDEWALL SAMPLE ELEVATION | BOTTOM CENTER POINT ELEVATION <20 PPM |
| PREVIOUSLY SUBMITTED DATA | |
| CURRENT EXCAVATION TO STRATUM D | |
| CURRENT EXCAVATION TO <20 PPM | |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 01-17-14 TO 01-23-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points

| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7* | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5* | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6* | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7* | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9* | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9* | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1* | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4* | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3* | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4* | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1* | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684392.6 | 602878.7 | -2.8 | 124-SB-123 | 30 | 1/23/2014 | -2.4 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 30 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684381.0 | 602861.0 | -2.3 | 124-SB-110 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684362.9 | 602837.4 | 3.2 | 124-SB-124 | 31 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684340.0 | 602818.0 | 3.2 | 124-SB-109 | 31 | 1/23/2014 | -1.6 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 31 | 1/23/2014 | 1.9* | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area

* Elevation based on Surveyed Center Point

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

Note: Data shown is for recent months activity


| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |
| 684373.5 | 602871.7 | -2.5 | C-30 | 30 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684311.9 | 602821.5 | 2.1 | C-30-1 | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684384.9 | 602861.2 | -2.5 | C-31 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684318.6 | 602806.8 | 2.1 | C-31-1 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Sidewall Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 4.9 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684301.0 | 602795.0 | 2.6 | 124-SB-108 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |

Note: Data shown is for recent months activity




NOTES: Proposed Test locations are approximate and based on meeting the maximum testing frequency specified in 012315–15 3.13 A. 2.

Sample frequency may be reduced in accordance with 3.13 A. 3.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

# FIELD DENSITY TEST SUMMARY LOG
## HONEYWELL STUDY AREA 7 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | PROCTOR NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.40 | 603182.80 | -0.5 | | | | | | 4 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-01-01 | 12/5/2013 | 684144.22 | 603184.16 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 4 | Weldon WC QP | |
| 3 | BF-01-02 | 12/5/2013 | 684137.77 | 603181.67 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | |
| 4 | BF-01-03 | 12/6/2013 | 684140.20 | 603182.66 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | |
| 5 | BF-01-04 | 12/6/2013 | 684136.62 | 603189.99 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | |
| 6 | BF-01-05 | 12/6/2013 | 684134.87 | 603186.67 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 4 | Weldon WC QP | |
| 7 | BF-01-06 | 12/6/2013 | 684141.06 | 603182.62 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | |
| 8 | BF-01-07 | 12/10/2013 | 684147.62 | 603186.80 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 4 | Weldon WC QP | |
| 9 | BF-01-08 | 12/10/2013 | 684140.19 | 603189.62 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 4 | Weldon WC Screenings | recompact lift |
| 9 | BF-01-08R | 12/10/2013 | 684140.19 | 603189.62 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 4 | Weldon WC Screenings | second reading after addl compaction |
| 10 | BF-01-09 | 12/12/2013 | 684130.07 | 603175.51 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 4 | Weldon WC Screenings | |
| 11 | BF-01-10 | 12/31/2013 | 684140.00 | 603184.30 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 4 | Weldon WC Screenings | |
| 1 | BF-02 | | 684153.80 | 603153.90 | -0.6 | | | | | | 6 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-02-01 | 12/5/2013 | 684162.75 | 603161.31 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 6 | Weldon WC QP | |
| 3 | BF-02-02 | 12/5/2013 | 684160.82 | 603162.33 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 6 | Weldon WC QP | |
| 4 | BF-02-03 | 12/6/2013 | 684157.71 | 603161.30 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 6 | Weldon WC QP | |
| 5 | BF-02-04 | 12/6/2013 | 684145.73 | 603162.11 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 6 | Weldon WC QP | |
| 6 | BF-02-05 | 12/6/2013 | 684156.93 | 603171.05 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 6 | Weldon WC QP | |
| 7 | BF-02-06 | 12/6/2013 | 684150.07 | 603155.35 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 6 | Weldon WC QP | |
| 8 | BF-02-07 | 12/10/2013 | 684135.46 | 603153.45 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 6 | Weldon WC QP | |
| 9 | BF-02-08 | 12/10/2013 | 684157.93 | 603174.92 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 6 | Weldon WC Screenings | |
| 1 | BF-03 | | 684179.90 | 603119.50 | -1.2 | | | | | | 9 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-03 | | | | | | | | | | 9 | Type A Material | No compaction testing required |
| 3 | BF-03-01 | 11/22/2013 | 684198.06 | 603131.60 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 9 | Weldon WC QP | |
| 4 | BF-03-02 | 11/22/2013 | 684155.72 | 603111.63 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 9 | Weldon WC QP | |
| 5 | BF-03-03 | 12/5/2013 | 684177.45 | 603121.50 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 9 | Weldon WC Screenings | |
| 6 | BF-03-04 | 12/12/2013 | 684180.46 | 603126.88 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 9 | Weldon WC Screenings | |
| 7 | BF-03-05 | 12/12/2013 | 684177.07 | 603132.39 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 9 | Weldon WC Screenings | |
| 8 | BF-03-06 | 12/16/2013 | 684172.40 | 603128.53 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 9 | Weldon WC Screenings | |
| 9 | BF-03-07 | 1/6/2014 | 684177.12 | 603113.81 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 9 | Weldon WC Screenings | |
| 10 | BF-03-08 | 1/9/2014 | 684178.20 | 603121.80 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 9 | Weldon WC Screenings | |
| 1 | BF-04 | | 684195.70 | 603093.10 | -1.5 | | | | | | 11 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-04 | | | | | | | | | | 11 | Type A Material | No compaction testing required |
| 3 | BF-04-01 | 12/5/2013 | 684198.04 | 603094.76 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | |
| 4 | BF-04-02 | 12/12/2013 | 684206.60 | 603104.72 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 11 | Weldon WC Screenings | |
| 5 | BF-04-03 | 12/16/2013 | 684217.51 | 603111.14 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 11 | Weldon WC Screenings | |
| 6 | BF-04-04 | 12/31/2013 | 684213.60 | 603115.00 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 11 | Weldon WC Screenings | |
| 7 | BF-04-05 | 1/9/2014 | 684195.80 | 603100.00 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | |
| 1 | BF-05 | | 684200.80 | 603078.40 | -1.8 | | | | | | 12 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-05 | | | | | | | | | | 12 | Type A Material | No compaction testing required |
| 3 | BF-05-01 | 12/5/2013 | 684185.18 | 603057.89 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 12 | Weldon WC Screenings | |
| 4 | BF-05-02 | 12/12/2013 | 684179.86 | 603057.68 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 12 | Weldon WC Screenings | recompact lift |
| 4 | BF-05-02R | 12/16/2013 | 684186.21 | 603070.22 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 12 | Weldon WC Screenings | second reading after addl compaction |
| 5 | BF-05-03 | 12/31/2013 | 684181.60 | 603060.80 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 12 | Weldon WC Screenings | |
| 6 | BF-05-04 | 1/9/2013 | 684186.10 | 603053.50 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 12 | Weldon WC Screenings | |
| 7 | BF-05-05 | 1/9/2013 | 684180.60 | 603048.60 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 12 | Weldon WC Screenings | |
| 1 | BF-06 | | 684214.80 | 603050.60 | -1.7 | | | | | | 14 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-06 | | | | | | | | | | 14 | Crushed concrete | No compaction testing required |
| 3 | BF-06-01 | 12/31/2013 | 684229.90 | 603061.30 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 14 | Weldon WC Screenings | |



Note: Data shown is for recent months activity

# FIELD DENSITY TEST SUMMARY LOG
## HONEYWELL STUDY AREA 7 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | PROCTOR NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | BF-06-02 | 12/31/2013 | 684228.80 | 603062.80 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | |
| 5 | BF-06-03 | 1/6/2014 | 684234.03 | 603066.82 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 14 | Weldon WC Screenings | |
| 6 | BF-06-04 | 1/9/2014 | 684230.80 | 603071.30 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | |
| 7 | BF-06-05 | 1/9/2014 | 684213.90 | 603095.70 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 14 | Weldon WC Screenings | |
| 1 | BF-07 | | 684222.70 | 603033.30 | -0.8 | | | | | | 15 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-07 | | | | | | | | | | 15 | Crushed concrete | No compaction testing required |
| 3 | BF-07-01 | 12/31/2013 | 684196.20 | 603014.90 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | |
| 4 | BF-07-02 | 12/31/2013 | 684192.80 | 603021.10 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 |
| 6 | BF-07-04 | 1/9/2014 | 684196.90 | 603018.80 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 15 | Weldon WC Screenings | recompact lift |
| 6 | BF-07-04R | 1/9/2014 | 684196.90 | 603018.80 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction |
| 7 | BF-07-05 | 1/9/2014 | 684195.00 | 603021.00 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 15 | Weldon WC Screenings | |
| 1 | BF-08 | | 684221.80 | 603013.00 | -0.7 | | | | | | 16 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-08 | | | | | | | | | | 16 | Crushed concrete | No compaction testing required |
| 3 | BF-08-01 | 12/31/2013 | 684246.90 | 603039.80 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | |
| 4 | BF-08-02 | 12/31/2013 | 684240.50 | 603043.20 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 16 | Weldon WC Screenings | |
| 5 | BF-08-03 | 1/6/2014 | 684231.74 | 603038.78 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | |
| 6 | BF-08-04 | 1/9/2014 | 684242.30 | 603046.80 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | |
| 7 | BF-08-05 | 1/9/2014 | 684236.30 | 603066.00 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | |
| 1 | BF-09 | | 684208.50 | 602989.40 | -0.5 | | | | | | 17 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-09 | | 684208.50 | 602989.40 | | | | | | | 17 | Crushed concrete | No compaction testing required |
| 3 | BF-09-01 | 1/28/2014 | 684209.70 | 602987.60 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | |
| 4 | BF-09-02 | 1/28/2014 | 684213.60 | 602980.40 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | |
| 5 | BF-09-03 | 1/28/2014 | 684204.20 | 602981.50 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 17 | Weldon WC Screenings | |
| 1 | BF-10 | | 684269.00 | 603014.00 | -0.5 | | | | | | 18 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-10 | | 684208.50 | 602989.40 | | | | | | | 18 | Crushed concrete | No compaction testing required |
| 3 | BF-10-01 | 1/20/2014 | 684275.40 | 603018.20 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | |
| 4 | BF-10-02 | 1/28/2014 | 684267.50 | 603026.10 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost |
| 4 | BF-10-02R | 1/28/2014 | 684267.50 | 603026.10 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | second reading after addl compaction |
| 5 | BF-10-03 | 1/28/2014 | 684271.80 | 603014.40 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | |
| 1 | BF-11 | | | | -1.0 | | | | | | 19 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-11 | | 684208.50 | 602989.40 | | | | | | | 19 | Crushed concrete | No compaction testing required |
| 3 | BF-11-01 | 1/28/2014 | 684216.60 | 602952.70 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 19 | Weldon WC Screenings | |
| 4 | BF-11-02 | 1/28/2014 | 684223.40 | 602953.80 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 19 | Weldon WC Screenings | |
| 5 | BF-11-03 | 1/28/2014 | 684211.60 | 602949.00 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 19 | Weldon WC Screenings | |
| 1 | BF-12 | | | | -1.7 | | | | | | 20 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-12 | | 684208.50 | 602989.40 | | | | | | | 20 | Crushed concrete | No compaction testing required |
| 3 | BF-12-01 | 1/20/2014 | 684291.70 | 602995.20 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 20 | Weldon WC Screenings | |
| 4 | BF-12-02 | 1/28/2014 | 684288.50 | 602989.80 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost |
| 4 | BF-12-02R | 1/28/2014 | 684288.50 | 602989.80 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 20 | Weldon WC Screenings | second reading after addl compaction |
| 5 | BF-12-03 | 1/28/2014 | 684291.30 | 602995.40 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 20 | Weldon WC Screenings | |
| 1 | BF-13 | | | | -1.9 | | | | | | 22 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-13 | | 684235.70 | 602919.60 | | | | | | | 22 | Crushed concrete | No compaction testing required |
| 3 | BF-13-01 | 1/28/2014 | 684235.60 | 602919.10 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 22 | Weldon WC Screenings | |
| 1 | BF-14 | | | | -0.9 | | | | | | 23 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-14 | | 684312.10 | 602956.00 | | | | | | | 23 | Crushed concrete | No compaction testing required |
| 3 | BF-14-01 | 1/20/2014 | 684312.70 | 602965.20 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 23 | Weldon WC Screenings | |
| 1 | BF-15 | | | | -0.9 | | | | | | 24 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-15 | | 684260.70 | 602896.70 | | | | | | | 24 | Crushed concrete | No compaction testing required |



Note: Data shown is for recent months activity

# FIELD DENSITY TEST SUMMARY LOG
## HONEYWELL STUDY AREA 7 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | PROCTOR NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | BF-15-01 | 1/28/2014 | 684259.00 | 602897.10 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 24 | Weldon WC Screenings | |
| 1 | BF-16 | | | | -1.1 | | | | | | 25 | Crushed concrete | Bottom of excavation elevation |
| 2 | BF-16 | | 684326.70 | 602937.00 | | | | | | | 25 | Crushed concrete | No compaction testing required |
| 3 | BF-16-01 | 1/20/2014 | 684331.90 | 602942.70 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 25 | Weldon WC Screenings | |

XX = Test number conducted at that test location

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill

01 = Test Location (as noted on Backfill Compaction Location Figure)


01 = Number of test performed at that location (sequential)

## Attachment 4: Dewatering Operations Update

- Figure 6: Well Point Dewatering System *(included in initial submittal only)*
- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-1)
- SA-6 South Deep Well Data (DW-2)

# SA-6 NORTH

# SA-6 SOUTH




**DEWATERING PHASE 3**
**WELL POINT SYSTEM START: 12/6/13**
**EXCAVATION START: 1/16/14**
**WELL POINT SYSTEM DISMANTLING: 2/28/14**
**EXCAVATION COMPLETE: 3/6/14**

**DEWATERING PHASE 4**
**WELL POINT SYSTEM START: 2/4/14**
**EXCAVATION START: 3/6/14**
**WELL POINT SYSTEM DISMANTLING: 4/28/14**
**EXCAVATION COMPLETE: 5/8/14**

**DEWATERING PHASE 2**
**WELL POINT SYSTEM START: 10/2/13**
**EXCAVATION START: 11/1/13**
**WELL POINT SYSTEM DISMANTLING: 12/13/13**
**EXCAVATION COMPLETE: 1/6/14**

**DEWATERING PHASE 1**
**WELL POINT SYSTEM START: 8/5/13**
**EXCAVATION START: 9/3/13**
**WELL POINT SYSTEM DISMANTLING: 10/25/13**
**EXCAVATION COMPLETE: 11/1/13**

NOTES:

1). THE INFORMATION HEREIN IS CONFIDENTIAL IN NATURE AND IS NOT TO BE REPRODUCED OR RE-USED WITHOUT THE EXPRESSED WRITTEN PERMISSION OF ENTACT.

2.) SCHEDULE IS BASED ON AN ASSUMED EXCAVATION RATE OF 800 CY/DAY AND AN EXCAVATION START DATE OF 9/3/12.

LEGEND:

- EXTRACTION WELL POINT
- SPLIT SPOON INVESTIGATION BORING WITHIN 10 FEET OF THIS WELL POINT
- DEEP WELL (APPROXIMATE LOCATION)
- EXCAVATION AREA BORDER
- TOP OF EXCAVATION SLOPE
- SOIL RETENTION SYSTEM

| REV | DATE | BY | CHK'D | APR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| 3 | 8/29/13 | JH | KG | KG | RELOCATED HEADER 1 DUE TO R.O.W. CONFLICT |
| 2 | 7/29/13 | JH | KG | KG | ADDED NUMBERING AND SPLIT SPOON SAMPLING LOCATIONS |
| 1 | 7/2/13 | JH | KG | KG | REMOVED DEEP WELLS FROM SA-6 NORTH |

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

| | |
|---|---|
| DRAWING NAME | FIGURE 6<br>WELL POINT DEWATERING SYSTEM |
| PROJECT NAME & LOCATION | HONEYWELL SA-6 REMEDIATION<br>JERSEY CITY, NJ |

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOUGH | APPROVED BY | K. GRIFFIN | | 3 |
| DATE | 3/4/13 | DATE | 3/4/13 | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 10/04/13 | 1 | 6 | 2, EPS | 12 | N/A | N/A | 6,500 | 6,500 | 18.1 | Not installed |
| 10/07/13 | 1 | 7 | 1,2,3,EPS | 43 | N/A | N/A | 2,700 | 9,200 | 6.4 | Not installed |
| 10/08/13 | 1 | 1.5 | 1,2,3,EPS | 43 | N/A | N/A | 2,200 | 11,400 | 24.4 | Not installed |
| 10/09/13 | 1 | 9 | 1,2,3,EPS | 43 | N/A | N/A | 4,500 | 15,900 | 8.3 | Not installed |
| 10/10/13 | 1 | 10.5 | 1,2,3,EPS | 44 | N/A | N/A | 4,500 | 20,400 | 7.1 | Not installed |
| 10/11/13 | 1 | 10 | 1,2,3,EPS | 53 | N/A | N/A | 4,200 | 24,600 | 7.0 | Not installed |
| 10/14/13 | 1 | 10 | 1,2,3,4,EPS | 63 | N/A | N/A | 5,500 | 30,100 | 9.2 | Not installed |
| 10/15/13 | 1 | 24 | 1,2,3,4,EPS | 63 | N/A | N/A | 12,800 | 42,900 | 8.9 | Not installed |
| 10/16/13 | 1 | 24 | 1,2,3,4,EPS | 63 | N/A | N/A | 11,450 | 54,350 | 8.0 | Not installed |
| 10/17/13 | 1 | 24 | 1,2,3,4,EPS | 64 | N/A | N/A | 14,800 | 69,150 | 10.3 | Not installed |
| 10/18/13 | 1 | 24 | 1,2,3,4,5,EPS | 77 | N/A | N/A | 11,220 | 80,370 | 7.8 | Not installed |
| 10/21/13 | 1 | 72 | 1,2,3,4,5,EPS | 78 | Not Installed | 2,403 | 23,550 | 103,920 | 5.5 | Flow meter installed midway through daily cycle. Reading was from tank gauging and meter reading at day's end. |
| 10/22/13 | 1 | 24 | 1,2,3,4,5,EPS | 77 | 2,403 | 7,574 | 5,171 | 109,091 | 3.6 | |
| 10/23/13 | 1 | 24 | 1,2,3,4,5,EPS | 77 | 7,574 | 11,468 | 3,894 | 112,985 | 2.7 | |
| 10/24/13 | 2 | 24 | 1,2,3,EPS | 32 | N/A | N/A | 2,500 | 115,485 | 1.7 | Not installed |
| 10/24/13 | 1 | 24 | 4,5,6,EPS | 34 | 11,468 | 17,456 | 5,988 | 121,473 | 4.2 | |
| 10/25/13 | 2 | 24 | 1,2,3,EPS | 32 | N/A | N/A | 5,210 | 126,683 | 3.6 | Not installed |
| 10/25/13 | 1 | 24 | 4,5,6,EPS | 34 | 17,456 | 26,720 | 9,264 | 135,947 | 6.4 | |
| 10/28/13 | 2 | 67 | 1,2,3,EPS | 32 | N/A | N/A | 14,400 | 150,347 | 3.6 | Not installed |
| 10/28/13 | 1 | 72 | 4,5,6,EPS | 34 | 26,720 | 44,982 | 18,262 | 168,609 | 4.2 | |
| 10/29/13 | 1 | 24 | 1,2,3,4,5,6,EPS | 66 | 44,982 | 49,327 | 4,345 | 172,954 | 3.0 | |
| 10/30/13 | 1 | 24 | 1,2,3,4,5,6,EPS | 66 | 49,327 | 53,293 | 3,966 | 176,920 | 2.8 | |
| 10/31/13 | 1 | 24 | 1,2,3,4,5,6,EPS | 66 | 53,293 | 57,299 | 4,006 | 180,926 | 2.8 | |
| 11/01/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 57,299 | 60,953 | 3,654 | 184,580 | 2.5 | Header 1 removed 11/1/13 |
| 11/04/13 | 1 | 72 | 2,3,4,5,6,EPS | 53 | 60,953 | 76,409 | 15,456 | 200,036 | 3.6 | |
| 11/05/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 76,409 | 78,991 | 2,582 | 202,618 | 1.8 | |
| 11/06/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 78,991 | 82,289 | 3,298 | 205,916 | 2.3 | |
| 11/07/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 82,289 | 85,894 | 3,605 | 209,521 | 2.5 | |
| 11/08/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 85,894 | 88,233 | 2,339 | 211,860 | 1.6 | |
| 11/11/13 | 1 | 72 | 2,3,4,5,6,EPS | 53 | 88,233 | 90,472 | 2,239 | 214,099 | 0.5 | |
| 11/12/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 90,472 | 92,021 | 1,549 | 215,648 | 1.1 | |
| 11/13/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 92,021 | 95,451 | 3,430 | 219,078 | 2.4 | |
| 11/14/13 | 1 | 24 | 2,3,4,5,6,EPS | 51 | 95,451 | 98,850 | 3,399 | 222,477 | 2.4 | |
| 11/15/13 | 1 | 24 | 2,3,4,5,6,EPS | 51 | 98,850 | 102,200 | 3,350 | 225,827 | 2.3 | |
| 11/18/13 | 1 | 72 | 2,3,4,5,6,EPS | 51 | 102,200 | 107,680 | 5,480 | 231,307 | 1.3 | |
| 11/19/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 107,680 | 114,159 | 6,479 | 237,786 | 4.5 | Header 2 removed 11/18/13 |
| 11/20/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 114,159 | 122,549 | 8,390 | 246,176 | 5.8 | |
| 11/21/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 122,549 | 123,061 | 512 | 246,688 | 0.4 | |
| 11/22/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 123,061 | 129,534 | 6,473 | 253,161 | 4.5 | |
| 11/25/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 0 | 103 | 103 | 253,264 | 0.1 | |
| 11/26/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 103 | 8,559 | 8,456 | 261,720 | 5.9 | |
| 11/27/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 8,559 | 20,117 | 11,558 | 273,278 | 8.0 | |
| 12/02/13 | 1 | 120 | 3,4,5,6,EPS | 40 | 20,117 | 79,516 | 59,399 | 332,677 | 8.2 | |
| 12/03/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 79,516 | 91,854 | 12,338 | 345,015 | 8.6 | |
| 12/04/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 91,854 | 103,283 | 11,429 | 356,444 | 7.9 | |

Note: Data shown is for recent months activity

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 12/05/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 103,283 | 112,785 | 9,502 | 365,946 | 6.6 | |
| 12/06/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 112,785 | 122,330 | 9,545 | 375,491 | 6.6 | |
| 12/09/13 | 1 | 72 | 3,4,5,6,EPS | 55 | 122,330 | 170,188 | 47,858 | 423,349 | 11.1 | |
| 12/10/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 170,188 | 185,509 | 15,321 | 438,670 | 10.6 | |
| 12/11/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 185,509 | 200,920 | 15,411 | 454,081 | 10.7 | |
| 12/12/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 200,920 | 214,877 | 13,957 | 468,038 | 9.7 | |
| 12/13/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 214,877 | 229,603 | 14,726 | 482,764 | 10.2 | |
| 12/16/13 | 1 | 72 | 4,5,6,EPS | 49 | 229,603 | 266,010 | 36,407 | 519,171 | 8.4 | Header 3 removed 12/13/13 |
| 12/17/13 | 1 | 24 | 4,5,6,EPS | 49 | 266,010 | 281,247 | 15,237 | 534,408 | 10.6 | |
| 12/18/13 | 1 | 24 | 4,5,6,EPS | 49 | 281,247 | 294,671 | 13,424 | 547,832 | 9.3 | |
| 12/19/13 | 1 | 24 | 4,5,6,EPS | 49 | 294,671 | 304,097 | 9,426 | 557,258 | 6.5 | |
| 12/20/13 | 1 | 24 | 4,5,6,EPS | 49 | 304,097 | 315,151 | 11,054 | 568,312 | 7.7 | |
| 12/23/13 | 1 | 72 | 4,5,6,EPS | 49 | 315,151 | 352,173 | 37,022 | 605,334 | 8.6 | |
| 12/24/13 | 1 | 24 | 4,5,6,EPS | 49 | 352,173 | 362,335 | 10,162 | 615,496 | 7.1 | |
| 12/30/13 | 1 | 144 | 4,5,6,EPS | 49 | 362,335 | 415,250 | 52,915 | 668,411 | 6.1 | |
| 12/31/13 | 1 | 24 | 4,5,6,EPS | 44 | 415,250 | 431,429 | 16,179 | 684,590 | 11.2 | |
| 01/02/14 | 1 | 48 | 4,5,6,EPS | 44 | 431,429 | 466,166 | 34,737 | 719,327 | 12.1 | |
| 01/06/14 | 1 | 96 | 4,5,6,EPS | 44 | 466,166 | 513,613 | 47,447 | 766,774 | 8.2 | |
| 01/07/14 | 1 | 24 | 4,5,6,EPS | 44 | N/A | N/A | 13,220 | 779,994 | 9.2 | Meter Innacurate Due to Temp |
| 01/08/14 | 1 | 24 | 4,5,6,EPS | 44 | N/A | N/A | 13,450 | 793,444 | 9.3 | Meter Innacurate Due to Temp |
| 01/09/14 | 1 | 24 | 4,5,6,EPS | 44 | N/A | 3,749 | 15,100 | 808,544 | 10.5 | Flow Meter Reset, Header 4 removed |
| 01/10/14 | 1 | 24 | 5,6,EPS | 44 | 3,749 | 15,043 | 11,294 | 819,838 | 7.8 | |
| 01/13/14 | 1 | 72 | 5,6,7,EPS | 60 | 15,043 | 52,782 | 37,739 | 857,577 | 8.7 | |
| 01/14/14 | 1 | 24 | 5,6,7,EPS | 60 | 52,782 | 68,191 | 15,409 | 872,986 | 10.7 | |
| 01/15/14 | 1 | 24 | 5,6,7,EPS | 60 | 68,191 | 86,290 | 18,099 | 891,085 | 12.6 | |
| 01/16/14 | 1 | 24 | 5,6,7,EPS | 60 | 86,290 | 103,647 | 17,357 | 908,442 | 12.1 | |
| 01/17/14 | 1 | 24 | 5,6,7,EPS | 60 | 103,647 | 120,724 | 17,077 | 925,519 | 11.9 | |
| 01/20/14 | 1 | 72 | 5,6,7,EPS | 60 | 120,724 | 177,150 | 56,426 | 981,945 | 13.1 | |
| 01/21/14 | 1 | 24 | 5,6,7,EPS | 60 | 177,150 | 192,354 | 15,204 | 997,149 | 10.6 | |
| 01/23/14 | 1 | 48 | 5,6,7,EPS | 60 | 192,354 | 209,564 | 17,210 | 1,014,359 | 6.0 | |
| 01/24/14 | 1 | 24 | 5,6,7,EPS | 60 | 209,564 | 219,596 | 10,032 | 1,024,391 | 7.0 | |
| 01/27/14 | 1 | 72 | 5,6,7,EPS | 60 | 219,596 | 241,870 | 22,274 | 1,046,665 | 5.2 | |
| 01/28/14 | 1 | 24 | 5,6,7,EPS | 60 | 241,870 | 249,752 | 7,882 | 1,054,547 | 5.5 | |
| 01/29/14 | 1 | 24 | 5,6,7,EPS | 60 | 249,752 | 256,270 | 6,518 | 1,061,065 | 4.5 | Header 5 removed 01/29/14 |
| 01/30/14 | 1 | 24 | 6,7,EPS | 51 | 256,270 | 262,157 | 5,887 | 1,066,952 | 4.1 | |
| 01/31/14 | 1 | 24 | 6,7,EPS | 51 | 262,157 | 268,122 | 5,965 | 1,072,917 | 4.1 | |
| 02/03/14 | 1 | 72 | 6,7,EPS | 51 | 268,122 | 292,592 | 24,470 | 1,097,387 | 5.7 | |
| 02/04/14 | 1 | 24 | 6,7,EPS | 51 | 292,592 | 299,040 | 6,448 | 1,103,835 | 4.5 | |
| 02/05/14 | 1 | 24 | 6,7,EPS | 51 | 299,040 | 309,154 | 10,114 | 1,113,949 | 7.0 | |
| 02/06/14 | 1 | 24 | 6,7,EPS | 51 | 309,154 | 318,585 | 9,431 | 1,123,380 | 6.5 | |

Notes: Active Header numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System

Note: Data shown is for recent months activity

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-1)

| DATE | HOURS OF OPERATION | DEEP WELL FLOW METER START (Gal) | DEEP WELL FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 10/23/13 | 29 | 0 | 24,640 | 24,640 | 24,640 | 14.2 | |
| 10/24/13 | 24 | 24,640 | 31,757 | 7,117 | 31,757 | 4.9 | |
| 10/25/13 | 24 | 31,757 | 39,567 | 7,810 | 39,567 | 5.4 | Slight blockage cleaned from meter |
| 10/28/13 | 72 | 39,567 | 91,820 | 52,253 | 91,820 | 12.1 | |
| 10/29/13 | 24 | 91,820 | 101,672 | 9,852 | 101,672 | 6.8 | |
| 10/30/13 | 24 | 101,672 | 111,472 | 9,800 | 111,472 | 6.8 | |
| 10/31/13 | 24 | 111,472 | 120,558 | 9,086 | 120,558 | 6.3 | |
| 11/01/13 | 24 | 120,558 | 128,248 | 7,690 | 128,248 | 5.3 | |
| 11/04/13 | 72 | 128,248 | 162,721 | 34,473 | 162,721 | 8.0 | |
| 11/05/13 | 24 | 162,721 | 173,853 | 11,132 | 173,853 | 7.7 | |
| 11/06/13 | 24 | 173,853 | 189,770 | 15,917 | 189,770 | 11.1 | |
| 11/07/13 | 24 | 189,770 | 210,266 | 20,496 | 210,266 | 14.2 | |
| 11/08/13 | 24 | 210,266 | 220,964 | 10,698 | 220,964 | 7.4 | |
| 11/11/13 | 72 | 220,964 | 235,035 | 14,071 | 235,035 | 3.3 | |
| 11/12/13 | 24 | 235,035 | 254,720 | 19,685 | 254,720 | 13.7 | |
| 11/13/13 | 24 | 254,720 | 272,758 | 18,038 | 272,758 | 12.5 | |
| 11/14/13 | 24 | 272,758 | 275,336 | 2,578 | 275,336 | 1.8 | |
| 11/15/13 | 24 | 275,336 | 281,413 | 6,077 | 281,413 | 4.2 | |
| 11/18/13 | 72 | 281,413 | 318,812 | 37,399 | 318,812 | 8.7 | |
| 11/19/13 | 24 | 318,812 | 328,059 | 9,247 | 328,059 | 6.4 | Well Taken Offline for Excavation |
| 11/27/13 | 24 | 328,059 | 351,245 | 23,186 | 351,245 | 16.1 | |
| 12/02/13 | 120 | 351,245 | 414,031 | 62,786 | 414,031 | 8.7 | Well Shut Off for Excavation Activities |
| 12/04/13 | 24 | 430,536 | 446,631 | 16,095 | 430,126 | 11.2 | |
| 12/05/13 | 24 | 446,631 | 459,826 | 13,195 | 443,321 | 9.2 | |
| 12/06/13 | 24 | 459,826 | 468,837 | 9,011 | 452,332 | 6.3 | |
| 12/09/13 | 72 | 468,837 | 499,005 | 30,168 | 482,500 | 7.0 | |
| 12/10/13 | 24 | 499,005 | 508,914 | 9,909 | 492,409 | 6.9 | |
| 12/11/13 | 24 | 508,914 | 519,185 | 10,271 | 502,680 | 7.1 | |
| 12/12/13 | 24 | 519,185 | 528,500 | 9,315 | 511,995 | 6.5 | |
| 12/13/13 | 24 | 528,500 | 535,384 | 6,884 | 518,879 | 4.8 | |
| 12/16/13 | 72 | 535,384 | 555,625 | 20,241 | 539,120 | 4.7 | |
| 12/17/13 | 24 | 555,625 | 563,870 | 8,245 | 547,365 | 5.7 | |
| 12/18/13 | 24 | 563,870 | 572,558 | 8,688 | 556,053 | 6.0 | |
| 12/19/13 | 24 | 572,588 | 578,579 | 5,991 | 562,044 | 4.2 | |
| 12/20/13 | 24 | 578,579 | 585,086 | 6,507 | 568,551 | 4.5 | |
| 12/23/13 | 72 | 585,086 | 604,411 | 19,325 | 587,876 | 4.5 | |
| 12/24/13 | 24 | 604,411 | 613,829 | 9,418 | 597,294 | 6.5 | |
| 12/30/13 | 144 | 613,829 | 669,247 | 55,418 | 652,712 | 6.4 | |
| 12/31/13 | 24 | 669,247 | 678,171 | 8,924 | 661,636 | 6.2 | |
| 01/02/14 | 48 | 678,171 | 697,609 | 19,438 | 681,074 | 6.7 | |
| 01/06/14 | 96 | 697,609 | 733,339 | 35,730 | 716,804 | 6.2 | Well Taken Offline |

Note: Data shown is for recent months activity

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-2)

| DATE | HOURS OF OPERATION | DEEP WELL FLOW METER START (Gal) | DEEP WELL FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/19/13 | 4 | 0 | 3,866 | 3,866 | 3,866 | 16.1 | |
| 11/20/13 | 24 | 3,866 | 18,857 | 14,991 | 18,857 | 10.4 | |
| 11/21/13 | 24 | 18,857 | 31,307 | 12,450 | 31,307 | 8.6 | |
| 11/22/13 | 24 | 31,307 | 52,611 | 21,304 | 52,611 | 14.8 | |
| 11/25/13 | 72 | 52,611 | 62,866 | 10,255 | 62,866 | 2.4 | |
| 11/26/13 | 24 | 62,866 | 69,596 | 6,730 | 69,596 | 4.7 | |
| 11/27/13 | 24 | 0 | 15,926 | 15,926 | 85,522 | 11.1 | |
| 12/02/13 | 120 | 15,926 | 81,682 | 65,756 | 151,278 | 9.1 | |
| 12/03/13 | 24 | 81,682 | 94,975 | 13,293 | 164,571 | 9.2 | |
| 12/04/13 | 24 | 94,682 | 108,260 | 13,578 | 178,149 | 9.4 | |
| 12/05/13 | 24 | 108,260 | 122,026 | 13,766 | 191,915 | 9.6 | |
| 12/06/13 | 24 | 122,026 | 134,343 | 12,317 | 204,232 | 8.6 | |
| 12/09/13 | 72 | 134,343 | 164,429 | 30,086 | 234,318 | 7.0 | |
| 12/10/13 | 24 | 164,429 | 174,915 | 10,486 | 244,804 | 7.3 | |
| 12/11/13 | 24 | 174,915 | 183,567 | 8,652 | 253,456 | 6.0 | |
| 12/12/13 | 24 | 183,567 | 193,229 | 9,662 | 263,118 | 6.7 | |
| 12/13/13 | 24 | 193,229 | 202,100 | 8,871 | 271,989 | 6.2 | |
| 12/16/13 | 72 | 202,100 | 229,583 | 27,483 | 299,472 | 6.4 | |
| 12/17/13 | 24 | 229,583 | 237,924 | 8,341 | 307,813 | 5.8 | |
| 12/18/13 | 24 | 237,924 | 246,510 | 8,586 | 316,399 | 6.0 | |
| 12/19/13 | 24 | 246,510 | 255,486 | 8,976 | 325,375 | 6.2 | |
| 12/20/13 | 24 | 255,486 | 263,423 | 7,937 | 333,312 | 5.5 | |
| 12/23/13 | 72 | 263,423 | 286,843 | 23,420 | 356,732 | 5.4 | |
| 12/24/13 | 24 | 286,843 | 297,632 | 10,789 | 367,521 | 7.5 | |
| 12/30/13 | 144 | 297,632 | 360,191 | 62,559 | 430,080 | 7.2 | |
| 12/31/13 | 24 | 360,191 | 369,462 | 9,271 | 439,351 | 6.4 | |
| 01/02/14 | 48 | 369,462 | 390,036 | 20,574 | 459,925 | 7.1 | |
| 01/06/14 | 96 | 390,036 | 429,927 | 39,891 | 499,816 | 6.9 | |
| 01/07/14 | 24 | 429,927 | 440,516 | 10,589 | 510,405 | 7.4 | |
| 01/08/14 | 24 | 440,516 | 459,411 | 18,895 | 529,300 | 13.1 | |
| 01/09/14 | 24 | 459,411 | 472,954 | 13,543 | 542,843 | 9.4 | |
| 01/10/14 | 24 | 472,954 | 486,509 | 13,555 | 556,398 | 9.4 | |
| 01/13/14 | 72 | 486,509 | 529,157 | 42,648 | 599,046 | 9.9 | |
| 01/24/14 | 24 | 529,157 | 543,032 | 13,875 | 612,921 | 9.6 | |
| 01/15/14 | 24 | 543,032 | 557,261 | 14,229 | 627,150 | 9.9 | |
| 01/16/14 | 24 | 557,261 | 571,278 | 14,017 | 641,167 | 9.7 | |
| 01/17/14 | 24 | 571,278 | 585,429 | 14,151 | 655,318 | 9.8 | |
| 01/20/14 | 72 | 585,429 | 627,704 | 42,275 | 697,593 | 9.8 | |
| 01/21/14 | 24 | 627,704 | 641,168 | 13,464 | 711,057 | 9.4 | |
| 01/23/14 | 48 | 641,168 | 666,348 | 25,180 | 736,237 | 8.7 | |
| 01/24/14 | 24 | 666,348 | 684,142 | 17,794 | 754,031 | 12.4 | |
| 01/27/14 | 72 | 684,142 | 726,325 | 42,183 | 796,214 | 9.8 | |
| 01/28/14 | 24 | 726,325 | 740,701 | 14,376 | 810,590 | 10.0 | |
| 01/29/14 | 24 | 740,701 | 754,662 | 13,961 | 824,551 | 9.7 | |
| 01/30/14 | 24 | 754,662 | 767,882 | 13,220 | 837,771 | 9.2 | |
| 01/31/14 | 24 | 767,882 | 782,573 | 14,691 | 852,462 | 10.2 | |
| 02/03/14 | 72 | 782,573 | 827,501 | 44,928 | 897,390 | 10.4 | |

Note: Data shown is for recent months activity

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-2)

| DATE | HOURS OF OPERATION | DEEP WELL FLOW METER START (Gal) | DEEP WELL FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 02/04/14 | 24 | 827,501 | 838,572 | 11,071 | 908,461 | 7.7 | |
| 02/05/14 | 24 | 838,572 | 853,159 | 14,587 | 923,048 | 10.1 | |
| 02/06/14 | 24 | 853,159 | 866,882 | 13,723 | 936,771 | 9.5 | |

Note: Data shown is for recent months activity

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER START (KGal) | DISCHARGE FLOW METER FINISH (KGal) | DISCHARGED VOLUME (Gal) DAILY | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 10/17/13 | 1.5 | 0.45 | 19.49 | 19,040 | 19,040 | Test Operation: Potable Water |
| 10/18/13 | 1.0 | 19.49 | 27.50 | 8,010 | 27,050 | |
| 10/22/13 | 4.0 | 27.50 | 85.74 | 58,240 | 85,290 | |
| 10/23/13 | 2.0 | 85.74 | 116.87 | 31,130 | 116,420 | |
| 10/24/13 | 1.3 | 116.87 | 135.20 | 18,330 | 134,750 | |
| 10/28/13 | 4.5 | 135.20 | 200.88 | 65,680 | 200,430 | PVSC Compliance Sample collected |
| 10/29/13 | 4.0 | 200.88 | 258.53 | 57,650 | 258,080 | |
| 11/01/13 | 4.3 | 258.53 | 300.34 | 41,810 | 299,890 | |
| 11/04/13 | 4.8 | 300.34 | 368.43 | 68,090 | 367,980 | |
| 11/05/13 | 4.3 | 368.43 | 408.77 | 40,340 | 408,320 | |
| 11/06/13 | 1.5 | 408.77 | 425.89 | 17,120 | 425,440 | |
| 11/07/13 | 1.0 | 425.89 | 453.88 | 27,990 | 453,430 | |
| 11/08/13 | 1.0 | 453.88 | 478.10 | 24,220 | 477,650 | |
| 11/12/13 | 4.5 | 478.10 | 526.82 | 48,720 | 526,370 | |
| 11/14/13 | 1.3 | 526.82 | 556.26 | 29,440 | 555,810 | |
| 11/18/13 | 5.0 | 556.26 | 619.36 | 63,100 | 618,910 | PVSC Compliance Sample collected |
| 11/21/13 | 4.0 | 619.36 | 652.91 | 33,550 | 652,460 | |
| 11/26/13 | 6.0 | 652.91 | 719.80 | 66,890 | 719,350 | |
| 11/27/13 | 6.0 | 719.80 | 784.49 | 64,690 | 784,040 | |
| 11/29/13 | 5.0 | 784.49 | 840.47 | 55,980 | 840,020 | |
| 12/02/13 | 6.5 | 840.47 | 923.11 | 82,640 | 922,660 | |
| 12/03/13 | 7.0 | 923.11 | 1,011.32 | 88,210 | 1,010,870 | PVSC Compliance Sample collected |
| 12/05/13 | 8.0 | 1,011.32 | 1,103.37 | 92,050 | 1,102,920 | |
| 12/06/13 | 4.0 | 1,103.37 | 1,143.07 | 39,700 | 1,142,620 | |
| 12/09/13 | 6.5 | 1,143.07 | 1,224.23 | 81,160 | 1,223,780 | |
| 12/10/13 | 6.0 | 1,224.23 | 1,286.03 | 61,800 | 1,285,580 | |
| 12/13/13 | 8.0 | 1,286.03 | 1,374.91 | 88,880 | 1,374,460 | |
| 12/16/13 | 8.0 | 1,374.91 | 1,485.04 | 110,130 | 1,484,590 | |
| 12/17/13 | 6.0 | 1,485.04 | 1,551.22 | 66,180 | 1,550,770 | |
| 12/18/13 | 7.0 | 1,551.22 | 1,628.26 | 77,040 | 1,627,810 | |
| 12/19/13 | 4.5 | 1,628.26 | 1,678.47 | 50,210 | 1,678,020 | |
| 12/20/13 | 5.0 | 1,678.47 | 1,732.93 | 54,460 | 1,732,480 | |
| 12/23/13 | 8.0 | 1,732.93 | 1,894.96 | 162,030 | 1,894,510 | |
| 12/24/13 | 7.0 | 1,894.96 | 1,989.84 | 94,880 | 1,989,390 | |
| 12/27/13 | 5.0 | 1,989.84 | 2,054.25 | 64,410 | 2,053,800 | |
| 12/30/13 | 8.0 | 2,054.25 | 2,147.46 | 93,210 | 2,147,010 | |
| 12/31/13 | 8.0 | 2,147.46 | 2,244.54 | 97,080 | 2,244,090 | |
| 01/02/14 | 8.0 | 2,244.54 | 2,368.54 | 124,000 | 2,368,090 | |
| 01/06/14 | 8.0 | 2,368.54 | 2,485.40 | 116,860 | 2,484,950 | |
| 01/09/14 | 8.0 | 2,485.40 | 2,567.15 | 81,750 | 2,566,700 | PVSC Compliance Sample collected |
| 01/10/14 | 8.0 | 2,567.15 | 2,635.97 | 68,820 | 2,635,520 | |
| 01/13/14 | 6.0 | 2,635.97 | 2,719.26 | 83,290 | 2,718,810 | |
| 01/14/14 | 8.0 | 2,719.26 | 2,864.73 | 145,470 | 2,864,280 | |
| 01/15/14 | 8.0 | 2,864.73 | 2,981.21 | 116,480 | 2,980,760 | |
| 01/16/14 | 8.0 | 2,981.21 | 3,111.28 | 130,070 | 3,110,830 | |
| 01/17/14 | 8.0 | 3,111.28 | 3,190.67 | 79,390 | 3,190,220 | |
| 01/20/14 | 8.0 | 3,190.67 | 3,297.59 | 106,920 | 3,297,140 | |
| 01/21/14 | 8.0 | 3,297.59 | 3,338.21 | 40,620 | 3,337,760 | |
| 01/27/14 | 8.0 | 3,338.21 | 3,438.26 | 100,050 | 3,437,810 | |
| 01/31/14 | 8.0 | 3,438.26 | 3,516.69 | 78,430 | 3,516,240 | |
| 02/04/14 | 8.0 | 3,516.69 | 3,628.15 | 111,460 | 3,627,700 | |

Note: Data shown is for recent months activity

## Attachment 6: Backfill Analytical Data

- Stockpiled Material Tracking and Sampling Log

## Stockpiled Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | Off-Site Disposal |
| 1-7 | <20 | 7-20-a | 124-7-20-a1 | 10/31/2013 | 14:20 | 5.8 | 10, 11, 12, 13 | | |
| 1-7 | <20 | 7-20-a | 124-7-20-a2 | 10/31/2013 | 14:25 | 7.8 | 10, 11, 12, 13 | | |
| 1-7 | <20 | 7-20-a | 124-7-20-a3 | 10/31/2013 | 14:30 | 4.6 | 10, 11, 12, 13 | | |
| 1-7 | <20 | 7-20-a | 124-7-20-a4 | 10/31/2013 | 14:35 | 4.7 | 10, 11, 12, 13 | | |
| 7-12 | <20 | 12-20-a | 124-12-20-a1 | 11/26/2013 | 15:00 | 26.1 | | Yes | |
| 7-12 | <20 | 12-20-a | 124-12-20-a2 | 11/26/2013 | 15:05 | 2.9 | ** | | |
| 7-12 | <20 | 12-20-a | 124-12-20-a3 | 11/26/2013 | 15:10 | 7.8 | ** | | |
| 7-12 | <20 | 12-20-a | 124-12-20-a4 | 11/26/2013 | 15:15 | 23.2 | | Yes | |
| 7-12 | <20 | 12-20-b | 124-12-20-b1 | 11/26/2013 | 15:20 | 4.3 | ** | | |
| 7-12 | <20 | 12-20-b | 124-12-20-b2 | 11/26/2013 | 15:25 | 2.5 | ** | | |
| 7-12 | <20 | 12-20-b | 124-12-20-b3 | 11/26/2013 | 15:30 | 5.1 | ** | | |
| 7-12 | <20 | 12-20-b | 124-12-20-b4 | 11/26/2013 | 15:35 | 5.8 | ** | | |
| 12-22 | <20 | 22-20-a | 124-22-20-a1 | 12/13/2013 | 13:30 | 5.5 | ** | | |
| 12-22 | <20 | 22-20-a | 124-22-20-a2 | 12/13/2013 | 13:35 | 11.9 | ** | | |
| 12-22 | <20 | 22-20-a | 124-22-20-a3 | 12/13/2013 | 13:40 | 1.3 | ** | | |
| 12-22 | <20 | 22-20-a | 124-22-20-a4 | 12/13/2013 | 13:45 | 2.3 | ** | | |
| 12-25 | <20 | 25-20-a | 124-25-20-a1 | 12/23/2013 | 9:00 | 1.6 | ** | | |
| 12-25 | <20 | 25-20-a | 124-25-20-a2 | 12/23/2013 | 9:05 | 1.7 | ** | | |
| 12-25 | <20 | 25-20-a | 124-25-20-a3 | 12/23/2013 | 9:10 | 10.8 | ** | | |
| 12-25 | <20 | 25-20-a | 124-25-20-a4 | 12/23/2013 | 9:15 | 17.4 | ** | | |
| 20-29 | <20 | 29-20-a | 124-29-20-a1 | 1/13/2014 | 14:00 | 0.31 | ** | | |
| 20-29 | <20 | 29-20-a | 124-29-20-a2 | 1/13/2014 | 14:05 | 0.84 | ** | | |
| 20-29 | <20 | 29-20-a | 124-29-20-a3 | 1/13/2014 | 14:10 | 3.4 | ** | | |
| 20-29 | <20 | 29-20-a | 124-29-20-a4 | 1/13/2014 | 14:15 | 1.9 | ** | | |

**Notes:**
*Material placement locations are approximate.
**Material currently stockpiled.



Note: Data shown is for recent months activity

# Attachment 7:  Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
N4
N3
N2
N1
087-MW-Y20
087-MW-S19
087-MW-O19
087-MW-O01
088-MW-G19
090-MW-E1
STA. N1+10
STA. N6+35
STA. N6+80
STA. N10+23
STA. N19+73
STA. N13+10
STA. N13+80
STA. N20+25
W1-S0
W6-S0
E5-S0
E4-S0
S-C-B BARRIER (TYP.)
STA. E0+50
E1
E3-S0
POOL E1 ELEV.+9.0 325'
117-MW-A99
STATE ROUTE
NEW JERSEY
STA. E3+75
STA. E4+50
E2
E2-S0
117-MW-A85
POOL E2 ELEV.+8 270'
STA. E7+25
118-PZ-6
118-PZ-5
118-PZ-4
INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0
INTERIOR POOL ELEV. +4.0
UNDERDRAINAGE SYSTEM (TYP.)
COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)
COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)
W3-S0
W5-S0
E1-S0
E1A-S0
S4
S3
S2
S1
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'
STA. S22+05
STA. S17+98
STA. S17+50
STA. S11+10
STA. S10+80
STA. S4+50
STA. S3+86
STA. S0+50
073-MW-BB11
073-MW-Y10
134-MW-V09
134-MW-Q08
140-MW-06
140-MW-07
125-MW-L03
MW-124-103L
MW-124-103D
MW-124-102T
117-MW-A89
KELLOGG STREET

LEGEND
FILL TYPE A CLAY
FILL TYPE B GRANULAR FILL

GRAPHIC SCALE
100' 50' 0 100' 200'


IN PROGRESS
04-19-2010

STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS
NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET
FILE NO. 10210
DRAWING NO. PP-1




Apr 19, 2010 at 3:12pm
G:\DWGS\102\10210\Dewatering\Perimeter Pool Data.dwg
lreva





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data


| | | | | | | | | | | 087-MW- | | | 134-MW- | | 073-MW- | | 140- | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | Y20 | 001 | O19 | V09 | Q08 | BB-11 | Y10 | MW-06 | MW-07 |
| Date | | | | | | | | | | | | | | | | | | |
| 7/2/2013 | 7.0 | 6.1 | 6.6 | 6.5 | 7.3 | 9.3 | 5.0 | 8.0 | 7.8 | 4.6 | | 8.3 | | | | | | |
| 7/3/2013 | | | | | | | | | | | | | 5.4 | 6.7 | 3.2 | 4.0 | 7.1 | 5.6 |
| 7/12/2013 | | | | | | | | | | | | | 5.2 | 6.1 | 3.2 | 3.7 | 6.8 | 5.3 |
| 7/15/2013 | 6.1 | 6.0 | 6.6 | 6.7 | 7.3 | 9.3 | 4.7 | 7.5 | 7.4 | 4.5 | | 8.7 | | | | | | |
| 7/19/2013 | | | | | | | | | | | | | 5.3 | 6.0 | | 3.6 | 6.6 | 5.2 |
| 7/26/2013 | | | | | | | | | | | | | 5.2 | 5.9 | 4.3 | 3.9 | 6.4 | 5.3 |
| 7/29/2013 | 5.9 | 5.9 | 6.4 | 6.4 | 6.9 | 9.2 | 4.6 | 7.2 | 7.3 | 4.6 | 6.8 | 8.3 | | | | | | |
| 8/2/2013 | | | | | | | | | | | | | 5.2 | 6.1 | 4.6 | 3.7 | 7.0 | 5.2 |
| 8/9/2013 | | | | | | | | | | | | | 5.1 | 6.0 | 3.4 | 3.8 | 6.5 | 5.3 |
| 8/16/2013 | 6.5 | 5.8 | 6.2 | 6.1 | 6.8 | 9.4 | 4.7 | 7.4 | 7.4 | 4.6 | 6.8 | 8.4 | 5.4 | 6.3 | 3.2 | 3.8 | 7.1 | 5.5 |
| 8/23/2013 | | | | | | | | | | | | | 5.9 | 6.2 | 3.9 | 3.8 | 6.6 | 6.1 |
| 8/29/2013 | 6.2 | 5.9 | 6.4 | 6.3 | 7.1 | 9.3 | 4.8 | 7.4 | 7.3 | 4.6 | 6.6 | 8.2 | | | | | | |
| 8/30/2013 | | | | | | | | | | | | | 5.8 | 6.1 | 3.2 | 4.0 | 6.6 | 5.4 |
| 9/5/2013 | | | | | | | | | | | | | 5.2 | 5.6 | 3.2 | 3.5 | 6.2 | 5.4 |
| 9/13/2013 | 5.9 | 5.7 | 6.0 | 5.8 | 6.1 | 9.5 | 4.6 | 6.9 | 7.4 | 4.7 | 5.4 | 8.3 | | | | | | |
| 9/16/2013 | | | | | | | | | | | | | 5.5 | 5.6 | 3.2 | 3.7 | 6.0 | 5.0 |
| 10/2/2013 | 5.7 | 5.6 | 5.9 | 5.5 | 5.8 | 9.4 | 4.4 | 6.6 | 7.3 | 4.8 | 5.9 | 7.8 | | | | | | |
| 10/4/2013 | | | | | | | | | | | | | 4.7 | 6.1 | 3.3 | 4.1 | 6.2 | 5.5 |
| 10/10/2013 | | | | | | | | | | | | | 5.2 | 5.5 | 4.2 | 3.9 | 6.1 | 5.0 |
| 10/17/2013 | | | | | | | | | | | | | 4.8 | 5.3 | 3.1 | 3.7 | 5.9 | 5.1 |
| 10/18/2013 | 5.5 | 5.5 | 5.6 | 5.3 | 5.8 | 9.4 | 4.4 | 6.3 | 7.4 | 4.8 | 6.2 | 7.9 | | | | | | |
| 10/25/2013 | | | | | | | | | | | | | 4.3 | 5.2 | 3.1 | 3.9 | 5.8 | 5.5 |
| 11/4/2013 | 5.4 | 5.4 | 5.4 | 5.1 | 5.6 | 9.3 | 4.3 | 6.2 | 7.1 | 4.7 | 6.1 | 7.7 | | | | | | |
| 11/15/2013 | | | | | | | | | | | | | 3.7 | 5.0 | 3.9 | 4.4 | 5.8 | 4.8 |
| 11/22/2013 | 5.3 | 5.3 | 5.1 | 4.9 | 5.6 | 9.3 | 4.6 | 6.1 | 7.1 | 4.7 | 6.4 | 7.9 | | | | | | |
| 12/4/2013 | 7.6 | 4.7 | 5.1 | 5.1 | 6.0 | 9.3 | 4.9 | 6.3 | 7.5 | 5.2 | 6.5 | 8.1 | 5.2 | 5.8 | 7.0 | | 6.9 | 5.1 |
| 12/17/2013 | | 4.7 | 4.7 | 5.7 | 6.5 | 9.5 | 4.6 | 8.1 | 7.7 | 4.5 | 6.3 | 7.8 | | | | | 7.6 | 5.7 |
| 12/31/2013 | | 4.8 | 5.6 | 6.0 | 7.1 | 9.9 | 7.5 | | 8.6 | 5.0 | 6.6 | 8.1 | | | | | | |
| 1/2/2014 | | | | | | | | | | | | | 5.9 | 7.0 | 7.2 | | 7.2 | 6.5 |
| 1/9/2014 | | | | | | | | 7.9 | | | | | | | | | | |
| 1/15/2014 | | | | | | | | | | | | | 6.5 | 7.3 | 7.0 | | 7.0 | 7.2 |
| 1/16/2014 | | 5.3 | 6.0 | 6.3 | 7.3 | | 7.6 | 7.8 | 8.3 | 4.9 | 7.5 | 8.7 | | | | | | |


## Attachment 8:  Quality and Level Data in GWET Wells

(not provided in this submittal - provided on a quarterly basis)

## Attachment 9: Surcharge Monitoring Update

- Surcharge Monitoring Plan Report Figures *(included in initial submittal only)*




SECTION A-A

NOTES:


1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. COMMENCE FILL AT THE SEDIMENTATION BASIN AND WORK TOWARDS THE HACKENSACK RIVER.
5. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
6. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1-1 | SETTLEMENT MONITORING POINT FULL - SETUP |
| HS-1-1 | SETTLEMENT MONITORING POINT HALF - SETUP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| ▼ | 72-INCH FM ACOUSTICAL MONITORING POINT |
| ● | 72-INCH FM SURVEY MONITORING POINT |
| X | STATION RELOCATED OR ELIMINATED DUE TO SURCHARGE PILE RECONFIGURATION |

0 15 30 60
SCALE IN FEET

Revised/Date: TDD 2/4/14
Checked/Date: SGS 2/4/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 NORTH<br>JERSEY CITY, NEW JERSEY<br>HONEYWELL SITE ID - 37472 | amec | INSTRUMENTATION LOCATION PLAN 1N<br>Project 3480-09-0006<br>Figure B1 |




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| I-2 | INCLINOMETER LOCATION |
| FS-1-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS12 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

Revised/Date: TDD 2/4/14
Checked/Date: SGS 2/4/14


0 15 30 60
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 2N
Project 3480-09-0006
Figure C1




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\oplus_{I-2}$ | INCLINOMETER LOCATION |
| $\blacksquare^{FS-1-1}$ | SETTLEMENT MONITORING POINT FULL – SET UP |
| $\blacksquare^{HS-1-1}$ | SETTLEMENT MONITORING POINT HALF – SET UP |
| $\boxtimes^{SP12}$ | SETTLEMENT MONITORING PLATFORM |
| $\bigcirc^{RP}$ | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

Revised/Date: TDD 2/4/14
Checked/Date: SGS 2/4/24

0 15 30 60
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 3N
Project 3480-09-0006
Figure D1




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\oplus_{VI-2}$ | INCLINOMETER LOCATION |
| FS12 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS12 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

Revised/Date: TDD 2/4/14
Checked/Date: SGB 2/4/14


0 15 30 60
SCALE IN FEET


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 4N
Project 3480-09-0006
Figure E1




SECTION A–A

NOTES:


1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

| | |
|---|---|
| ⊕ VI–2 | INCLINOMETER LOCATION |
| ■ FS–1–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| ■ HS–1–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| ⊠ SP12 | SETTLEMENT MONITORING PLATFORM |
| ○ RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 06/18/13
Checked/Date: AE 06/18/13

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | INSTRUMENTATION LOCATION PLAN 1S<br>Figure F1 |




| | | |
|---|---|---|
| VI-2 | INCLINOMETER LOCATION | |
| FS-1 | SETTLEMENT MONITORING POINT FULL – SET UP | |
| HS-1 | SETTLEMENT MONITORING POINT HALF – SET UP | |
| SP-12 | SETTLEMENT MONITORING PLATFORM | |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) | |


NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
4. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

0 20 40 80
SCALE IN FEET

Revised/Date: TDD 2/4/14
Checked/Date: SGB 2/4/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | INSTRUMENTATION LOCATION PLAN 2S<br>Figure G1 |




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARDS ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP–12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

0 20 40 80
SCALE IN FEET

Revised/Date: TDD 2/4/14
Checked/Date: SGB 2/4/14

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN 3S

Figure H1



Z:\Projects\VANTAGE\JERSEY CITY\Dwg Design-Site-CAD\CAD\SA-6 North and South Au-Subs\SA-6 North and South Surcharge Monitoring\Mit Figure – Surcharge Instrumentation Plan.dwg Tue, 04 Feb 2014 – 8:56pm tony.dickerson

## Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation

FILE NAME: Z:\Projects\HONEYWELL\RESRV CITY\Civil Design\SA6-C-301\CAD\SA6SIC0R3.S-301 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Wed 22 May 2013 PLOT TIME: 1:09 PM

VERTICAL SCALE: 1" = 10'
SCALE IN FEET
0 5 10 20

HORIZONTAL SCALE: 1" = 40'
SCALE IN FEET
0 20 40 80

Time Frame for:
←|: Hydraulic Barrier Driven
←|: Angles Grouted

NOTES:
1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "8E" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIERS | STATION | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 1+54 | -3 | AZ 19-700 |
| STRUCTURAL | 1+54 | 5+00 | -19 | AZ 19-700 |
| STRUCTURAL | 5+00 | 12+60 | -22 | AZ 19-700 |

PRELIMINARY SHEET PILE TIP ELEVATION (TYP)
EXISTING GROUND ELEVATION (TYP)
BOTTOM OF EXCAVATION ELEVATION (TYP)
STRATUM D (TYP)
EXCAVATION GRADE (TYP)
LINER GRADE / TOP OF FINAL HYDRAULIC BARRIER (TYP) (SEE NOTE FP2 ON SHEET G-004)
EXISTING GRADE (TYP)
FINAL REMEDY GRADE (TYP)
STA 1+54
10/18/13 10/3/13 8/15/13 8/19/13 8/20/13 8/22/13 8/23/13 8/26/13 10/18/13
10/23/13 10/22/13 9/9/13 9/10/13 9/11/13 9/12/13 9/13/13 10/24/13
10.00 10.00 9.42 9.26 9.84 9.85 10.00 10.66 8.94 9.76
0+00 1+00 2+00 3+00 4+00 5+00 6+00 7+00 8+00

NEW JERSEY STATE HIGHWAY ROUTE 440

HYDRAULIC BARRIER
SEE NOTE HB21 ON SHEET G-003
UTILITY CORRIDOR
EXISTING SOIL CEMENT BENTONITE WALL
HYDRAULIC BARRIER AND CEMENT BENTONITE WALL CONNECTION
B S-201 C-301

MATCH LINE SHEET S-202

| DSGN | DR | CHK | APVD | BY | APVD | NO. | DATE | REVISION |
|---|---|---|---|---|---|---|---|---|
| TDD | TDD | RJR | TDD | TDD | SHM | 0 | 06/07/13 | ISSUED FOR CONSTRUCTION |

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY


STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04302400
5/24/13

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-12-0317
DWG S-201
SHEET 53 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTABLE INFORMATION CONTAINED THEREIN, AND IS TO BE RETURNED UPON REQUEST. ANY REPRODUCTION, IN PART OR WHOLE, OR USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC, TO REPRODUCE THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 5+00 | 12+60 | -22 | AZ 19-700 |
| STRUCTURAL | 12+60 | 17+80 | -30 | AZ 19-700 |
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |




NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL
5/24/13
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | TDD | RJR | TDD |

ISSUED FOR CONSTRUCTION

| REVISION | BY | APVD |
|---|---|---|
| | TDD | SHM |

SHM

Honeywell
101 COLUMBIA RD. BOX 2150, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


DATE
PROJ 3480-12-0317
DWG S-202
SHEET 54 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE USE OF THE DRAWINGS FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Civil Design\SA6-C3D\CAD\SA6SCR54-S-202 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Wed, 22 May 2013 PLOT TIME: 2:57 PM




BEFORE DRIVING SHEETS




SHEET SEALING DETAIL
NTS
BF
TYP S-203

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |
| STRUCTURAL | 19+00 | 21+20 | -19 | AZ 19-700 |
| STRUCTURAL | 21+20 | 23+20 | -15 | AZ 19-700 |
| STRUCTURAL | 23+20 | 24+37 | -12 | AZ 19-700 |
| NON STRUCTURAL | 24+37 | 25+89 | -12 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | RJR | TDD | SHM |

ISSUED FOR CONSTRUCTION
REVISION
TDD SHM
BY APVD
SHM

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.
THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER PLAN & PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG S-203
SHEET 55 OF 66


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design-SA6-C3D\CAD\SA6SICR55-S-203 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Wed, 22 May 2013 PLOT TIME: 3:01 PM

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.




Note: Data shown is for recent months activity




NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 02-05-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

## Attachment 11:  Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 7, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 4 |
| Flood Protection | X | | | |
| Sediment Outside of Controls | | X | | 5 |
| Storm Drain Filter Baskets | | X | | 6 |
| | | | | |
| | | | | |
| SA-6 North | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 7 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| SA-7 | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 8 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 9 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Orange fencing around EZ requires maintenance. |
| 2 | IA2Q4A1AL8 | Soil stockpile on Teal slab requires erosion control at toe. |
| 3 | IA2Q4A1AL8 | Berm on east side of EZ requires maintenance/enhancement. |
| 4 | IA2Q4A1AL8 | Tracking pad required for truck decon station at EZ exit. |
| 5 | IA2Q4A1AL8 | Sediment outside of flood barrier on parking lot asphalt. |
| 6 | IA2Q4A1AL8 | Catch basin filter fabric requires replacement. |
| 7 | EHWG3RTMXR | Silt fence along ENR excavation alignment requires maintenance. |
| 8 | IA2Q4A1AL8 | Silt fence at SES stiockpile area requires repair. |
| 9 | EEPSQUO2YB | Novartis stockpile at top of containment measures on north side. |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature George Pfeiffer **Date:** 01/09/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | | |
| 2 | | |
| 3 | | |
| 4 | | |
| 5 | | |
| 6 | | |
| 7 | | |
| 8 | | |
| 9 | | |
| | | |

**Construction Manager:** _____ **Date:** _____

Received from Exhibit 01/17/14

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
RFA PI ID #: 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
RFA PI ID #: 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
RFA PI ID #:
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Orange fencing around EZ requires maintenance. ✓ Fri |
| 2 | IA2Q4A1AL8 | Soil stockpile on Teal slab requires erosion control at toe 1/16 |
| 3 | IA2Q4A1AL8 | Berm on east side of EZ requires maintenance/enhancement. Mon |
| 4 | IA2Q4A1AL8 | Tracking pad required for truck decon station at EZ exit. |
| 5 | IA2Q4A1AL8 | Sediment outside of flood barrier on parking lot asphalt. 1/16 |
| 6 | IA2Q4A1AL8 | Catch basin filter fabric requires replacement. Tues 1/15 |
| 7 | EHWG3RTMXR | Silt fence along ENR excavation alignment requires maintenance. |
| 8 | IA2Q4A1AL8 | Silt fence at SES stockpile area requires repair. 1/16 |
| 9 | EEPSQUO2YB | Novartis stockpile at top of containment measures on north side. |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 01/09/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | | |
| 2 | | |
| 3 | | |
| 4 | | |
| 5 | | |
| 6 | | |
| 7 | | |
| 8 | | |
| 9 | | |
| | | |

**Construction Manager:** _____ **Date:** _____

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: January 15, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☐ Fair ☑ Cloudy ☐ Other Fog
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 3 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 4 |
| Flood Protection | X | | | |
| Sediment Outside of Controls | | X | | 5 |
| Storm Drain Filter Baskets | | X | | 6 |
| Ponded Storm Water | | X | | 7 |
| | | | | |
| **SA-6 North** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 8 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | | |
| Flood Protection | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| SA-7 | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 9 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 10 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 01/15/14

**SWPPP Observer:** _____ (George Pfeiffer)
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence on outboard side of sheetpile requires maintenance. |
| 2 | IA2Q4A1AL8 | Orange fencing on south side of EZ requires maintenance/repair. |
| 3 | IA2Q4A1AL8 | <20 ppm pile A-5 requires erosion protection. <20 ppm staging area on the former boatyard property requires fabric installed over bin blocks. |
| 4 | IA2Q4A1AL8 | Tracking pad required for truck decon station at EZ exit. |
| 5 | IA2Q4A1AL8 | Sediment outside of flood barrier on parking lot asphalt. |
| 6 | IA2Q4A1AL8 | Catch basin filter fabric requires replacement. |
| 7 | EHWG3RTMXR | Storm water ponded in eastern EZ and on the former Teal/Degen properties. |
| 8 | IA2Q4A1AL8 | Silt fence along ENR excavation alignment requires maintenance and/or repair. |
| 9 | EEPSQUO2YB | Hay bales degraded on west side of Novartis pile; replace. Silt fence at Sevenson stone staging area requires repair. |
| 10 | EEPSQUO2YB | Novartis stockpile overtopping containment measures on north side, inboard material removal required. |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 01/15/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | | |
| 2 | Repeat - Entact | |
| 3 | | |
| 4 | Repeat - Entact | |
| 5 | Repeat - Entact | |
| 6 | Repeat - Entact | |
| 7 | | |
| 8 | Repeat - ENR | |
| 9 | | |
| 10 | Repeat - Entact | |

**Construction Manager:** _____ **Date:** 01/15/14

Received from Entact
01/17/14

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence on outboard side of sheetpile requires maintenance. 1-16 |
| 2 | IA2Q4A1AL8 | ~~Orange fencing on south side of EZ requires maintenance/repair.~~ 1/16 |
| 3 | IA2Q4A1AL8 | <20 ppm pile A-5 requires erosion protection. ~~<20 ppm staging area on the former boatyard property requires~~ fabric installed over bin blocks. 1/16 |
| 4 | IA2Q4A1AL8 | Tracking pad required for truck decon station at EZ exit. |
| 5 | IA2Q4A1AL8 | Sediment outside of flood barrier on parking lot asphalt. 1/16 |
| 6 | IA2Q4A1AL8 | ~~Catch basin filter fabric requires replacement.~~ 1/15 |
| 7 | EHWG3RTMXR | Storm water ponded in eastern EZ and on the former Teal/Degen properties. 1-17 |
| 8 | ~~IA2Q4A1AL8~~ | Silt fence along ENR excavation alignment requires maintenance and/or repair. |
| 9 | EEPSQUO2YB | Hay bales degraded on west side of Novartis pile; replace. Silt fence at Sevenson stone staging area requires repair. 1/16 Haybales are ordered. |
| 10 | EEPSQUO2YB | Novartis stockpile overtopping containment measures on north side, inboard material removal required. |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** [signature] Signature **Date:** 01/15/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | | |
| 2 | Repeat - Entact | |
| 3 | | |
| 4 | Repeat - Entact | |
| 5 | Repeat - Entact | |
| 6 | Repeat - Entact | |
| 7 | | |
| 8 | Repeat - ENR | |
| 9 | | |
| 10 | Repeat - Entact | |

**Construction Manager:** [signature] **Date:** 01/15/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 21, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☑ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 3 |
| Flood Protection | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| | | | | |
| | | | | |
| | | | | |
| SA-6 North | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Work Zone Barriers | | X | | 5 |
| | | | | |
| | | | | |
| | | | | |
| SA-7 | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 7 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**NOTE: All comments are numbered for reference and included on the comment section below.**

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence to the west of sheet pile barrier wall requires maintenance. |
| 2 | IA2Q4A1AL8 | Filter fabric on concrete bin blocks surrounding <20 ppm staged material requires maintenance. |
| 3 | IA2Q4A1AL8 | Truck and equipment decontamination area requires the installation of a tracking pad. |
| 4 | IA2Q4A1AL8 | Windscreen on perimeter fencing requires maintenance. |
| 5 | IA2Q4A1AL8 | Work zone barrier along the south side of the H-Building has a gap. Replace missing Jersey barrier. |
| 6 | EEPSQUO2YB | Hay bales degraded. Replace weathered bales. |
| 7 | EEPSQUO2YB | Sediment over-topping the stockpile containment barrier. Remove material on inside of barrier to restore containment. |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 01/22/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repeat item. Entact to address immediately. | |
| 2 | Re-install fabric which has blown from surface of blocks and secure. Fabric should be installed on all bin blocks in containment structure. | |
| 3 | Repeat item. Entact to address immediately. | |
| 4 | Secure windscreen along JCIA perimeter fenceline. | |
| 5 | Replace Jersey barrier and confirm that there are no gaps in the vehicle barrier separating the SA-6 North work area from the Jersey City occupied area. | |
| 6 | Repeat item. Entact to address immediately. | |
| 7 | Repeat item. Entact to address immediately. | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 01/22/14

Received from ENTACT 01/28/14

**Honeywell**

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence to the west of sheet pile barrier wall requires maintenance. completed / removed 1/23 |
| 2 | IA2Q4A1AL8 | Filter fabric on concrete bin blocks surrounding <20 ppm staged material requires maintenance. completed 1/24 ~~1/23~~ |
| 3 | IA2Q4A1AL8 | Truck and equipment decontamination area requires the installation of a tracking pad. completed 1/23 |
| 4 | IA2Q4A1AL8 | Windscreen on perimeter fencing requires maintenance. |
| 5 | IA2Q4A1AL8 | Work zone barrier along the south side of the H-Building has a gap. Replace missing Jersey barrier. completed 1/24 |
| 6 | EEPSQUO2YB | Hay bales degraded. Replace weathered bales. started 1/24 |
| 7 | EEPSQUO2YB | Sediment over-topping the stockpile containment barrier. Remove material on inside of barrier to restore containment. completed 1/24 |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 01/22/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repeat item. Entact to address immediately. | 1/23/14 |
| 2 | Re-install fabric which has blown from surface of blocks and secure. Fabric should be installed on all bin blocks in containment structure. | 1/24/14 |
| 3 | Repeat item. Entact to address immediately. | 1/23/14 |
| 4 | Secure windscreen along JCIA perimeter fenceline. | 1/27/14 |
| 5 | Replace Jersey barrier and confirm that there are no gaps in the vehicle barrier separating the SA-6 North work area from the Jersey City occupied area. | 1/24/14 |
| 6 | Repeat item. Entact to address immediately. | 1/27/14 |
| 7 | Repeat item. Entact to address immediately. | 1/24/14 |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 01/22/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 28, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 2 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | X | | | |
| Storm Drain Protection | | X | | 3 |
| | | | | |
| SA-6 North and GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North and GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Work Zone Barriers | | X | | 6 |
| Storm Drain Protection | | | X | |
| | | | | |
| SA-7 and Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 7 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | | X | | 8 |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Entact- Orange Exclusion Zone fencing on southern perimeter of excavation requires repair. |
| 2 | IA2Q4A1AL8 | Entact- Petroleum and propylene glycol drums requre secondary containment. |
| 3 | IA2Q4A1AL8 | Entact- Storm drain catch basin to the north of the Guard Shack requires sediment protection. |
| 4 | EHWG3RTMXR | ENR- Silt fence along the GWET line alignment requires maintenance at the southwest corner of SA-6 North. |
| 5 | IA2Q4A1AL8 | Entact- The perimeter fence between SA-6 North and SA-7 has a gap in the chain link fabric (where the construction water lines cross the SCB wall) that requires repair. |
| 6 | EHWG3RTMXR | ENR- The excavation in the southwest corner of SA-6 North requires installation of work zone barriers. |
| 7 | EEPSQUO2YB | Entact- Silt fencing on the northwest corner of the SES stockpile area requires maintenance. |
| 8 | EHWG3RTMXR | ENR- The excavation in the northwest corner of SA-7 requires installation of work zone barriers. |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWPPP Observer:** (G. Pfeiffer) **Date:** 01/29/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 2 | Spill pallets or comparable methods are acceptable. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** _____

Received from ENR
02/04/14 DP

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Entact- Orange Exclusion Zone fencing on southern perimeter of excavation requires repair 1-30 |
| 2 | IA2Q4A1AL8 | Entact- Petroleum and propylene glycol drums requre secondary containment. ✓ spill pallets ordered + arriving on 2-4 |
| 3 | IA2Q4A1AL8 | Entact- Storm drain catch basin to the north of the Guard Shack requires sediment protection. 1-29 |
| 4 | EHWG3RTMXR | ENR- Silt fence along the GWET line alignment requires maintenance at the southwest corner of SA-6 North Completed By ENR DP |
| 5 | IA2Q4A1AL8 | Entact- The perimeter fence between SA-6 North and SA-7 has a gap in the chain link fabric (where the construction water lines cross the SCB wall) that requires repair 1-31 |
| 6 | EHWG3RTMXR | ENR- The excavation in the southwest corner of SA-6 North requires installation of work zone barriers. Completed By ENR DP |
| 7 | EEPSQUO2YB | Entact- Silt fencing on the northwest corner of the SES stockpile area requires maintenance. ENR keeps removing the silt fence for access to fill materials Snow + ice have not allowed for the repairs to be made. |
| 8 | EHWG3RTMXR | ENR- The excavation in the northwest corner of SA-7 requires installation of work zone barriers COMPLETED By ENR DP |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWPPP Observer:** (G. Pfeiffer) Date: 01/29/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 2 | Spill pallets or comparable methods are acceptable. | See Above DP |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** Date: 02/04/14

## Attachment 12: 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (December 2013 Correction and January 2014)

The Monitoring Report originally submitted to the NJDEP on January 23, 2014, erroneously contained January 2014 data and was resubmitted with along with the January 2014 Report on February 12, 2014.

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

February 11, 2014

Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: December 2013 correction and January 2014 Surface Water Discharge Monitoring Reports**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

On January 23, 2014, I submitted an incorrect December 2013 DMR. I had mistakenly reported the January 2014 sampling results on the December 2013 DMR. Attached please find the corrected December 2013 DMR and the January 2014 DMR. I apologize for this error and have instituted a checking mechanism so that it does not occur again.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: File
US Filter WWTP File

PI 234822

New Jersey Department of Environmental Protection
Division of Water Quality

**Surface Water Discharge Monitoring Report Submittal Form**

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 12 | 1 | 2013 | To | 12 | 31 | 2013 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☐ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J Morris, Remediation Director — —

**NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **GRADE AND REGISTRY NUMBER (IF APPLICABLE)**

John J Morris JM 2/11/14 — 1/23/2014 — 973-455-4003

**SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **DATE** | **AREA CODE/PHONE NUMBER**

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J Morris, Remediation Director — John J Morris JM 2/11/14 — 1/23/2014 — 973-455-4003

**NAME AND TITLE** | **SIGNATURE** | **DATE** | **AREA CODE/PHONE NUMBER**

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 12/1/2013 TO 12/31/2013 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | 71,735 | 104,150 | GPD | ****** | ****** | ****** | ****** | 0 | Continuous | Meter |
| | PERMIT REQUIREMENT | REPORT<br>01MOAV | REPORT<br>01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | 7.61 | ****** | 7.61 | SU | 0 | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0<br>01MOMN | ****** | 9.0<br>01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | Code N | ****** | ****** | %EFFL | 0 | 1/Year | Compos |
| | PERMIT REQUIREMENT | ****** | ****** | | 50<br>01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | Code N | ****** | ****** | %EFFL | 0 | 1/Year | Compos |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT<br>01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <5.1 | ND, <5.1 | MG/L | 0 | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10<br>01MOAV | 15<br>01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 5.5 | 5.5 | MG/L | 0 | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 20<br>01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 10/1/2013*

JM 2/11/14

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 12/1/2013 TO 12/31/2013 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 14.5 | 14.5 | UG/L | 0 | 1/Month | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

JM 2/11/14



*Pre-Print Creation Date: 10/1/2013*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 12/1/2013 TO 12/31/2013 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50<br>01MOAV | 100<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | REPORT<br>01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 0.025<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 8.8<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 46<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | Code N | Code N | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 54<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

JM 2/11/14



*Pre-Print Creation Date: 10/1/2013*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 12/1/2013 TO 12/31/2013 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | 12028 | 03547 | - | - | - | - | - | - | - | - |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

JM 2/11/14

# Honeywell Flume Flow Daily Totals

| | |
|---|---|
| Year: | 2013 |
| Month: | December |

| Day | Meter Reading | Flows (gpm) | Volume Treated (gpd) | Run Time (hr/day) |
|---|---|---|---|---|
| 12/1/2013 | 341053508 | 152.81 | 82,520 | 9 |
| 12/2/2013 | 341136028 | 125.83 | 90,600 | 12 |
| 12/3/2013 | 341226628 | 151.90 | 82,028 | 9 |
| 12/4/2013 | 341308656 | 173.92 | 83,480 | 8 |
| 12/5/2013 | 341392136 | 125.53 | 90,380 | 12 |
| 12/6/2013 | 341482516 | 153.16 | 82,704 | 9 |
| 12/7/2013 | 341565220 | 125.31 | 82,704 | 11 |
| 12/8/2013 | 341647924 | 165.73 | 89,496 | 9 |
| 12/9/2013 | 341737420 | 100.92 | 84,776 | 14 |
| 12/10/2013 | 341822196 | 184.70 | 88,656 | 8 |
| 12/11/2013 | 341910852 | 152.48 | 73,192 | 8 |
| 12/12/2013 | 341984044 | 198.18 | 95,124 | 8 |
| 12/13/2013 | 342079168 | 95.39 | 17,170 | 3 |
| 12/14/2013 | 342096338 | 95.39 | 17,170 | 3 |
| 12/15/2013 | 342113508 | 87.11 | 15,680 | 3 |
| 12/16/2013 | 342129188 | 92.42 | 16,636 | 3 |
| 12/17/2013 | 342145824 | 134.73 | 24,252 | 3 |
| 12/18/2013 | 342170076 | 133.62 | 48,104 | 6 |
| 12/19/2013 | 342218180 | 181.30 | 21,756 | 2 |
| 12/20/2013 | 342239936 | 150.24 | 72,116 | 8 |
| 12/21/2013 | 342312052 | 92.46 | 72,116 | 13 |
| 12/22/2013 | 342384168 | 140.33 | 84,200 | 10 |
| 12/23/2013 | 342468368 | 107.01 | 102,728 | 16 |
| 12/24/2013 | 342571096 | 102.50 | 86,100 | 14 |
| 12/25/2013 | 342657196 | 89.69 | 86,100 | 16 |
| 12/26/2013 | 342743295 | 123.99 | 104,150 | 14 |
| 12/27/2013 | 342847445 | 104.24 | 81,305 | 13 |
| 12/28/2013 | 342928750 | 150.56 | 81,305 | 9 |
| 12/29/2013 | 343010055 | 149.96 | 89,977 | 10 |
| 12/30/2013 | 343100032 | 134.42 | 88,720 | 11 |
| 12/31/2013 | 343188752 | 163.95 | 88,534 | 9 |
| | | | | |
| | | | | |
| Totals | 2135244 | | | 283 |
| Average | | 133.54 | 71,735 | |
| Maximum | | | 104,150 | |

Arecon Ltd (NJ Lab Cert. # 03547)
40 US Highway Route 130
Bordentown, NJ 08505
(609)-298-0770, Fax (609-)291-8186

# Chain Of Custody / Analysis Request

COC #:
Lab Use Only
Lab Proj #
Lab ID 03547

Privileged & Confidential: Y
Site Name:
Location of Site:
PAGE 1 of 1
Job No.

Client Contact: (name, co., address)
Helen Fahy
101 Columbia Road
Morristown, NJ 07961
hfahy@honeywell.com

Hardcopy Report To: Helen Fahy
Invoice To: Helen Fahy

Sampler:
P O #
Analysis Turnaround Time:
Standard -
Rush Charges Authorized for -
2 weeks -
1 week -
Next Day -

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Grab/Composite | Field Filtered Sample ? | Preservative | | | | | | | | | | | | | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | | | 0 | 0 | 0 | 0 | 0 | | | | | | | | | |
| | | | | | NW | | | | | | Units | | mg/L | - | | | | | | | | | | | | |
| 1 | WTP | | | Effluent | 11/13/2015 | | Grab | water | pH | | | | | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | |

pH 7.61 @ 11.1 °C

| Relinquished by | Company | Date/Time | Received by | Company | Date/Time | Condition | Cooler Temp. | Custody Seals Intact |
|---|---|---|---|---|---|---|---|---|
| | Arecon | 11/13 0920 | | | | | | |
| Relinquished by | Company | Date/Time | Received by | Company | Date/Time | Condition | Cooler Temp. | Custody Seals Intact |
| | | | | | | | | |

Preservatives: 0 = None; 1 = HCL; 2 = HNO3; 3 = H2SO4; 4 = NaOH; 5 = Zn. Acetate; 6 = MeOH; 7 = NaHSO4; 8 = Other (specify)

JM 2/11/14

New Jersey Department of Environmental Protection
Division of Water Quality

PI 234822

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 1 | 1 | 2014 | To | 1 | 31 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☐ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J. Morris, Remediation Director — —

**NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **GRADE AND REGISTRY NUMBER (IF APPLICABLE)**

John J Morris 2/11/2014 973.455.4003

**SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **DATE** | **AREA CODE/PHONE NUMBER**

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6E(5) that I have received and reviewed the attached discharge monitoring reports.

John J. Morris, Remediation Director John J Morris 2/11/2014 973.455.4003

**NAME AND TITLE** | **SIGNATURE** | **DATE** | **AREA CODE/PHONE NUMBER**

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 1/1/2014 TO 1/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | 84,126 | 102,404 | GPD | ****** | ****** | ****** | ****** | O | Continuous | Meter |
| | PERMIT REQUIREMENT | REPORT<br>01MOAV | REPORT<br>01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | 7.69 | ****** | 7.69 | SU | O | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0<br>01MOMN | ****** | 9.0<br>01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | Code N | ****** | ****** | %EFFL | O | 1/Year | Composite |
| | PERMIT REQUIREMENT | ****** | ****** | | 50<br>01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | Code N | ****** | ****** | %EFFL | O | 1/Year | Composite |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT<br>01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <5.0 | ND, <5.0 | MG/L | O | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10<br>01MOAV | 15<br>01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 5.3 | 5.3 | MG/L | O | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 20<br>01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 1/1/2014 TO 1/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 19.8 | 19.8 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 10 | 10 | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <10 | ND, <10 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 20.9 | 20.9 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <0.5 | ND, <0.5 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 19.8 | 19.8 | UG/L | 0 | 1/Month | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |



Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 1/1/2014 TO 1/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <10 | ND, <10 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50<br>01MOAV | 100<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <10 | ND, <10 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | REPORT<br>01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <0.2 | ND, <0.2 | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 0.025<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 1.0 | 1.0 | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 8.8<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 13.1 | 13.1 | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 46<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 23.2 | 23.2 | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 54<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 1/1/2014 TO 1/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | 12028 | 03547 | – | – | – | – | – | – | – | – |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |



Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Honeywell Flume Flow Daily Totals

| | |
|---|---|
| Year: | 2014 |
| Month: | January |

| Day | Meter Reading | Flows (gpm) | Volume Treated (gpd) | Run Time (hr/day) |
|---|---|---|---|---|
| 1/1/2014 | 343277286 | 163.95 | 88,534 | 9 |
| 1/2/2014 | 343365820 | 155.47 | 83,956 | 9 |
| 1/3/2014 | 343449776 | 173.48 | 83,272 | 8 |
| 1/4/2014 | 343533048 | 126.17 | 83,272 | 11 |
| 1/5/2014 | 343616320 | 156.14 | 74,948 | 8 |
| 1/6/2014 | 343691268 | 137.82 | 90,964 | 11 |
| 1/7/2014 | 343782232 | 91.59 | 82,432 | 15 |
| 1/8/2014 | 343864664 | 184.93 | 99,864 | 9 |
| 1/9/2014 | 343964528 | 168.08 | 80,680 | 8 |
| 1/10/2014 | 344045208 | 136.89 | 73,920 | 9 |
| 1/11/2014 | 344119128 | 88.00 | 73,920 | 14 |
| 1/12/2014 | 344193048 | 170.67 | 102,404 | 10 |
| 1/13/2014 | 344295452 | 174.56 | 94,264 | 9 |
| 1/14/2014 | 344389716 | 115.09 | 89,772 | 13 |
| 1/15/2014 | 344479488 | 179.72 | 97,048 | 9 |
| 1/16/2014 | 344576536 | 187.97 | 90,224 | 8 |
| 1/17/2014 | 344666760 | 171.28 | 82,216 | 8 |
| 1/18/2014 | 344748976 | 152.25 | 82,216 | 9 |
| 1/19/2014 | 344831192 | 186.16 | 89,356 | 8 |
| 1/20/2014 | 344920548 | 177.70 | 95,956 | 9 |
| 1/21/2014 | 345016504 | 148.21 | 80,036 | 9 |
| 1/22/2014 | 345096540 | 158.41 | 76,036 | 8 |
| 1/23/2014 | 345172576 | 155.25 | 37,260 | 4 |
| 1/24/2014 | 345209836 | 178.85 | 85,850 | 8 |
| 1/25/2014 | 345295686 | 158.98 | 85,850 | 9 |
| 1/26/2014 | 345381536 | 149.58 | 71,796 | 8 |
| 1/27/2014 | 345453332 | 162.86 | 87,944 | 9 |
| 1/28/2014 | 345541276 | 173.62 | 93,756 | 9 |
| 1/29/2014 | 345635032 | 172.18 | 82,648 | 8 |
| 1/30/2014 | 345717680 | 159.88 | 76,744 | 8 |
| 1/31/2014 | 345794424 | 189.07 | 90,754 | 8 |
| | | | | |
| Average | | 158.22 | 84,126 | |
| Maximum | | | 102,404 | |

**Arecon Ltd (NJ Lab Cert. # 03547)**
90 US Highway Route 130
Bordentown, NJ 08505
(609)-298-0770, Fax: (609-)291-8386

# Chain Of Custody / Analysis Request

COC #:
Lab Use Only
Lab Proj #
Lab ID: 03547
PAGE 1 of 1
Job No.

Privileged & Confidential: Y
EDD To:
Sampler:
PO #:
Site Name:
Location of Site:

Client Contact: (name, co., address)
Helen Fahy
101 Columbia Road
Morristown, NJ 07961
Helen.Fahy@honeywell.com

Hardcopy Report To: Helen Fahy
Invoice To: Helen Fahy

Analysis Turnaround Time:
Standard -
Rush Charges Authorized for -
2 weeks -
1 week -
Next Day -

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Grab/Composite | Field Filtered Sample? | Preservative | | | |

**3/13/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

March 13, 2014 ***Via Express Mail***

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Progress Report No. 2014-02**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from February 1 – February 28, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: February 2014 SA-6/7 Combined Monthly Progress Report No. 2014-02

cc: Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-02

**Project SA-6 & 7 Remediation**

## February 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 02/06/14 | Multiple Responses to Comments Provided by Plaintiffs - January 28, 2014, SA-6 South – Excavation of Cells 17 through 20/January 31, 2014, SA-6 South – Excavation of Cells 21 through 29<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/10/14 | Response to Comments Provided by Plaintiffs, January 28, 2014, Certificate to Operate (CAO) a Beneficial Use Project Application (BUD),<br>SA-6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/12/14 | Surface Water DMR (December 2013 correction and Jan 2014)<br>Study Area 7, Jersey City, NJ | State of New Jersey Department of Environmental Protection<br>Office of Permit Management<br>Division of Water Quality |
| 02/14/14 | Combined Monthly Progress/Highlights Report No. 2014-01<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/17/14 | 2013 Annual Hazardous Waste Export Report for USEPA ID # NJD986581437, EPA Notice No.: 004954/5E/12 and 007142/5E/13<br>Study Area 7, Jersey City, NJ | US Environmental Protection Agency |
| 02/17/14 | PVSC MR1/MR2 (Discharge of Tannin Construction Water)<br>Study Area 7, Jersey City, NJ | Andrew Caltagirone<br>Passaic Valley Sewerage Commission |
| 02/18/14 | Special Master All Hands Conference Call | N/A |
| 02/25/14 | Ownership of Kellogg St. 80 Property, LLC<br>Block 1290.1, Lot No. 18<br>Study Area 6, Jersey City, NJ | City of Jersey City<br>Tax Collector's Offices |
| 02/26/14 | Re: Request for Extension for Submittal of Local Limit Baseline Monitoring Report & Slug Control Questionnaire, Permit # 31630016<br>New Groundwater Treatment Plant<br>Study Areas 6 and 7, Jersey City, NJ | Andrew Caltagirone<br>Passaic Valley Sewerage Commission |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 2/9/2014 | 2/16/2014 | 2/23/2014 | 3/2/2014 |
| Construction Management (AMEC) | 10 | 10 | 10 | 11 |
| Engineering (AMEC) | 2 | 2 | 2 | 2 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 35 | 27 | 30 | 35 |
| Arecon/US Ecology Subcontractors | 3 | 2 | 6 | 5 |
| Oradell (SA-6N GWTP Building Mech/ Plumbing/HVAC) | 1 | 1 | 0 | 0 |
| ENR (SA-6N GWTP Utilities) | 2 | 1 | 0 | 0 |
| BCA (SA-6N Building Construction) | 0 | 0 | 0 | 0 |
| Siemens | 2 | 2 | 2 | 2 |
| HBS (SA-6N GWTP Security System) | 0 | 0 | 0 | 0 |
| HPS (SA-6N GWTP Process Controls) | 0 | 0 | 0 | 0 |
| Other | 0 | 0 | 0 | 0 |
| **TOTAL** | **59** | **49** | **56** | **59** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued new Ground Water Treatment Plant (GWTP) commissioning activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Continued numerous snow removal events on SA-6N and SA-6S.
- Initiated abandonment of former 54" Sedimentation Basin outfall pipe on SA-6N.
- Terminated operation of the 80 Kellogg St WWTP on February 28, 2014.
- Collected February PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Non-chromium activities, ARCADIS continues to work with NJDEP on the modification to the existing NJDEP-Discharge to Groundwater Permit by Rule for additional Enhanced Anaerobic in-situ bioremediation (EAISB) injections planned for JCMUA and JCDPW UST Areas.

## C. 80 KELLOGG GROUND WATER TREATMENT PLANT

- Hydrochloric acid cleaning was performed for all micro filter trains.
- Filter cake container changed-out (Arecon-FCI) on. February 10th.
- February monthly and quarterly effluent DMR samples were collected.
- Continued decommissioning activities for exterior ModuTanks, sludge tanks, microfilters and performed electrical disconnect and lockout/tagout procedures on pumps and equipment.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 2/9/2014 | 2/16/2014 | 2/23/2014 | 3/2/2014 |
| Avg. Gallons Treated & Discharged (per day) | 86,274 | 25,347 | 24,668 | 30,549 |
| Average Flow (gpm) for Operating Period | 162 | 126 | 94 | 144 |
| Avg. Hours of Plant Operation | 9 | 3 | 4 | 4 |
| GWTP ModuTanks (gal.) | 142,700 | 136,960 | 140,280 | 148,875 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in Cells 38 through 43.
- Completed initial sampling, waste characterization and initiated off-site T&D of petroleum-impacted soils that were identified during excavation activities via field observations and PID readings.
- Began pre-trench activities for Vertical Hydraulic Barrier Wall on SA-6N proximate to the 72-inch force main.
- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Compaction tests were not performed due to inclement weather during the month.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 18.0 | 18.0 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 75 | 21.52 | 1,614.16 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Entact/ Venerio** | Tri-axle Dump | Middlesex City Landfill | NA | Petroleum Impacted Soils (non–haz) | 20 | 24.63 | 492.78 |
| **Entact/ Montecalvo** | Tri-axle Dump | Bayshore Recycling | NA | Petroleum Impacted Soils (non-haz) | 98 | 24.94 | 2,444.22 |
| **Entact/ Montecalvo** | 30 cubic Yard Roll off | Bayshore Recycling | NA | Creosote Debris (non- haz) | 4 | 11.78 | 47.13 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 42,43 |
| **Excavation Completed** | Cell Number(s) 36 through 41<br>Volume Excavated - Total for Reporting Period: 5,551 CY/ Total to Date:30,879 CY |
| **Backfill in Progress** | Cell Number(s) 1 through 39 |

### 3. BACKFILL MATERIALS USED

| Source | (Week Ending) | | | |
|---|---|---|---|---|
| | 2/9/2014 | 2/16/2014 | 2/23/2014 | 3/2/201 |
| <20ppm re-use, CY | 0 | 0 | 0 | 0 |
| Weldon, Import-Tons | 0 | 426.83 | 0 | 0 |
| Tilcon, Import-Tons | 0 | 0 | 0 | 1,309.23 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Instrumentation Installation ~60% complete. Access limitations due to ice and demolition materials. No Surcharge Initiated.
- Area 2S: Instrumentation Installation ~75% complete. Completion of instrument installation deferred pending completion of demolition activities. No Surcharge Initiated.
- Area 3S: Instrumentation Installation 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. No Surcharge initiated.
- Area 1N: Instrumentation Installation ~80% complete. No Surcharge initiated. The installation of the inclinometers (V1-1 through V1-4), HS1, HS2, FS3 will be installed following completion of the Barrier Wall along the 72-inch force main. SP1, SP2, and SP-3 will be installed prior to fill placement along SA-7.
- Area 2N: No instrumentation installed. Settlement platforms have been installed in the sedimentation basin to the north of Area 2 and portion of the Sedimentation Basin has been temporarily filled with screened materials that will be used for surcharging the designated Surcharge Areas.

- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see Attachment 10)*

- Hydraulic Barrier installation was initiated adjacent to the 72-inch force main. Vibration and acoustical monitoring results show no responses of concern.
- Vibration Monitoring indicated maximum accelerations continue to be within allowable range (0.2 in/sec observed, while the allowable acceleration is 1.0 in/sec).
- Acoustical Monitoring. PVSC/Hatch Mott MacDonald (HMM) report that there were no wire breaks recorded during the current reporting period.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/15 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/12 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP | SA-6 Chromium Remedy | Final anticipated Feb 2014, Using Temp Permit Now Issued 9/1/13 | Pending | Pending | - |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/15 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/14 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/12 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/13 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete abandonment in place of the former 54-inch discharge pipe from the Sedimentation Basin.
- Complete installation of vertical hydraulic barrier wall proximate to the 72-inch force main.
- Initiate placement of surcharge materials in SA-6N Area 1N.

- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 43 through 53.
- Continue stockpiling potential >1,000 mg/kg soils for sampling.
- Continue off-site disposal of petroleum-impacted soils.
- Resume backfill placement and associated compaction testing activities.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Complete permanent piping tie-ins to PW-1/PW-2 and 215-BR and continue full-scale SA-6N Ground Water Treatment Plant operational activities.
- Complete decommissioning of 80 Kellogg Ground Water Treatment Plant.
- Mobilize demolition contractor for equipment salvage at the 80 Kellogg Ground Water Treatment Plant.
- Continue SWPPP inspections.
- Complete PVSC compliance sampling.
- Conduct quarterly LTMP groundwater level measurements.
- Conduct S-3 Sand Injection Event No.12 in well 088-IW-01.

**ATTACHMENTS:**

1: Schedule – 6 Month Look Ahead
2: Site Photographs
3: Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/Sidewall Confirmatory Points
   - Backfill Compaction Locations *(no update for this reporting period/not provided in this submittal)*
   - Field Density Test Summary Log *(no update for this reporting period/not provided in this submittal)*
4: Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-1)
   - SA-6 South Deep Well Data (DW-2)
5: SA-6 Construction Water Discharge Data (To PVSC)
6: Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7: Perimeter Pools Update
8: Quality and Level Data in GWET Wells *( not included in this submittal -provided on a quarterly basis)*
9: Surcharge Monitoring Update
   - Surcharge Monitoring Plan Report Figures B1 and F1 *(figures updated to show installed locations)*


10: Sheet Pile Update
- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Pile Repair Log/Photos

11: Weekly SWPPP Reports

12: 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (January 2014) *(not provided in this submittal – this information was previously provided in Progress Report 2014-01)*

## Attachment 1:  Schedule – 6 Month Look Ahead

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |



## Attachment 2: Site Photographs




**Site Photograph 1:** Barrier wall installation progress on Kellogg St. properties looking east.




**Site Photograph 2:** Equipment installs barrier wall sheet pile on Kellogg St. properties.




**Site Photograph 3:** Excavation and backfill progress Kellogg St. properties looking south.




**Site Photograph 4:** Excavation continues on Kellogg St. properties looking north.




**Site Photograph 5:** Excavation continues on Kellogg St. properties looking west.




**Site Photograph 6:** Former discharge pipeline being demolished on Jersey City properties.




**Site Photograph 7:** New GWTP final construction.





**Site Photograph 8:** Spare repair section of sewer pipe arrives on-site.

## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/Sidewall Confirmatory Points)
- Backfill Compaction Locations (no update for this reporting period/not provided in this submittal)
- Field Density Test Summary Log (no update for this reporting period/not provided in this submittal)

# Jersey City & Kellogg Street Properties Remedies
# Progress as of March 1, 2014

February 2014 SA-6/7 Progress Report - Attachment 3: Excavation and Backfill




## Legend


- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete




ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 02-14-14 TO 02-20-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points

| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7* | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5* | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6* | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7* | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9* | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9* | Stratum D Reached |
| 684204.7 | 602890.7 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1* | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4* | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3* | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4* | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1* | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684392.6 | 602878.7 | -2.8 | 124-SB-123 | 30 | 1/23/2014 | -2.4 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 30 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684381.0 | 602861.0 | -2.3 | 124-SB-110 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684362.9 | 602837.4 | 3.2 | 124-SB-124 | 31 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684340.0 | 602818.0 | 3.2 | 124-SB-109 | 31 | 1/23/2014 | -1.6 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 31 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684416.9 | 602861.1 | -2.8 | 124-SB-029 | 32 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 32 | 1/30/2014 | 2.0* | Target Elevation Reached |
| 684411.9 | 602839.0 | -2.2 | 124-SB-092 | 33 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 33 | 1/30/2014 | 2.0* | Target Elevation Reached |
| 684372.0 | 602797.0 | 2.6 | 124-PT-14 | 34 | 2/4/2014 | -1.9 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684458.4 | 602838.3 | -2.3 | 124-SB-027 | 35 | 2/4/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684440.8 | 602806.0 | -2.8 | 124-SB-091 | 36 | 2/11/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 36 | 2/11/2014 | 2.1* | Target Elevation Reached |
| 684394.0 | 602777.3 | 4.7 | 124-SB-117A | 36 | 2/11/2014 | -1.6 | Stratum D Reached |
| 684473.9 | 602819.4 | -2.8 | 124-SB-026 | 37 | 2/11/2014 | -2.9 | Stratum D Reached |
| 684430.7 | 602784.0 | -1.3 | 124-SB-023 | 37 | 2/11/2014 | -3.6 | Stratum D Reached |
| 684412.9 | 602766.1 | 2 | 124-SB-121A | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684400.0 | 602762.0 | -0.1 | 124-PT-04 | 37 | 2/11/2014 | -2.2 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 37 | 2/11/2014 | 2.1* | Target Elevation Reached |
| 684463.2 | 602783.7 | -2.3 | 124-SB-136 | 38 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021R | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684448.4 | 602763.0 | 4.7 | 124-SB-022 | 39 | 2/20/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area

* Elevation based on Surveyed Center Point

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |
| 684373.5 | 602871.7 | -2.5 | C-30 | 30 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684311.9 | 602821.5 | 2.1 | C-30-1 | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684384.9 | 602861.2 | -2.5 | C-31 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684318.6 | 602806.8 | 2.1 | C-31-1 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684383.8 | 602841.5 | -2.5 | C-32 | 32 | 1/30/2014 | -1.8 | Stratum D Reached |
| 684335.2 | 602800.6 | 2.1 | C-32-1 | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684393.5 | 602830.6 | -2.5 | C-33 | 33 | 1/30/2014 | -1.9 | Stratum D Reached |
| 684348.7 | 602791.2 | 2.1 | C-33-1 | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684412.7 | 602824.5 | -2.5 | C-34 | 34 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684355.8 | 602781.0 | 2.1 | C-34-1 | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684422.4 | 602815.2 | -2.5 | C-35 | 35 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684367.5 | 602768.5 | 2.1 | C-35-1 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684432.1 | 602801.8 | -2.5 | C-36 | 36 | 2/11/2014 | -2.4 | Stratum D Reached |
| 684371.2 | 602753.4 | 2.1 | C-36-1 | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684440.7 | 602791.6 | -2.5 | C-37 | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684380.7 | 602742.6 | 2.1 | C-37-1 | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684460.4 | 602787.7 | -2.5 | C-38 | 38 | 2/20/2014 | -2.8 | Stratum D Reached |
| 684397.4 | 602736.2 | 2.1 | C-38-1 | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684471.9 | 602777.2 | -2.5 | C-39 | 39 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684416.4 | 602732.1 | 2.1 | C-39-1 | 39 | 2/20/2014 | 2.1 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Sidewall Confirmatory Points | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | Actual Coordinates | | |
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 4.9 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684301.0 | 602795.0 | 2.6 | 124-SB-108 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684328.2 | 602790.2 | 3.3 | 124-SB-063 | 32 | 1/30/2014 | 1.8 | Target Elevation Reached |
| 684338.1 | 602786.6 | 4.7 | 124-SB-056 | 33 | 1/30/2014 | 1.7 | Target Elevation Reached |
| 684348.0 | 602746.0 | 3.4 | 124-PT-02 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684386.0 | 602707.0 | 3.3 | 124-PT-01 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |

Note: Data shown is for recent months activity

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-1)
- SA-6 South Deep Well Data (DW-2)

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 10/04/13 | 1 | 6 | 2, EPS | 12 | NA | NA | 6,500 | 6,500 | 18.1 | Not installed |
| 10/07/13 | 1 | 7 | 1,2,3,EPS | 43 | NA | NA | 2,700 | 9,200 | 6.4 | Not installed |
| 10/08/13 | 1 | 1.5 | 1,2,3,EPS | 43 | NA | NA | 2,200 | 11,400 | 24.4 | Not installed |
| 10/09/13 | 1 | 9 | 1,2,3,EPS | 43 | NA | NA | 4,500 | 15,900 | 8.3 | Not installed |
| 10/10/13 | 1 | 10.5 | 1,2,3,EPS | 44 | NA | NA | 4,500 | 20,400 | 7.1 | Not installed |
| 10/11/13 | 1 | 10 | 1,2,3,EPS | 53 | NA | NA | 4,200 | 24,600 | 7.0 | Not installed |
| 10/14/13 | 1 | 10 | 1,2,3,4,EPS | 63 | NA | NA | 5,500 | 30,100 | 9.2 | Not installed |
| 10/15/13 | 1 | 24 | 1,2,3,4,EPS | 63 | NA | NA | 12,800 | 42,900 | 8.9 | Not installed |
| 10/16/13 | 1 | 24 | 1,2,3,4,EPS | 63 | NA | NA | 11,450 | 54,350 | 8.0 | Not installed |
| 10/17/13 | 1 | 24 | 1,2,3,4,EPS | 64 | NA | NA | 14,800 | 69,150 | 10.3 | Not installed |
| 10/18/13 | 1 | 24 | 1,2,3,4,5,EPS | 77 | NA | NA | 11,220 | 80,370 | 7.8 | Not installed |
| 10/21/13 | 1 | 72 | 1,2,3,4,5,EPS | 78 | Not Installed | 2,403 | 23,550 | 103,920 | 5.5 | Flow meter installed midway through daily cycle. Reading was from tank gauging and meter reading at day's end. |
| 10/22/13 | 1 | 24 | 1,2,3,4,5,EPS | 77 | 2,403 | 7,574 | 5,171 | 109,091 | 3.6 | |
| 10/23/13 | 1 | 24 | 1,2,3,4,5,EPS | 77 | 7,574 | 11,468 | 3,894 | 112,985 | 2.7 | |
| 10/24/13 | 2 | 24 | 1,2,3,EPS | 32 | NA | NA | 2,500 | 115,485 | 1.7 | Not installed |
| 10/24/13 | 1 | 24 | 4,5,6,EPS | 34 | 11,468 | 17,456 | 5,988 | 121,473 | 4.2 | |
| 10/25/13 | 2 | 24 | 1,2,3,EPS | 32 | NA | NA | 5,210 | 126,683 | 3.6 | Not installed |
| 10/25/13 | 1 | 24 | 4,5,6,EPS | 34 | 17,456 | 26,720 | 9,264 | 135,947 | 6.4 | |
| 10/28/13 | 2 | 67 | 1,2,3,EPS | 32 | NA | NA | 14,400 | 150,347 | 3.6 | Not installed |
| 10/28/13 | 1 | 72 | 4,5,6,EPS | 34 | 26,720 | 44,982 | 18,262 | 168,609 | 4.2 | |
| 10/29/13 | 1 | 24 | 1,2,3,4,5,6,EPS | 66 | 44,982 | 49,327 | 4,345 | 172,954 | 3.0 | |
| 10/30/13 | 1 | 24 | 1,2,3,4,5,6,EPS | 66 | 49,327 | 53,293 | 3,966 | 176,920 | 2.8 | |
| 10/31/13 | 1 | 24 | 1,2,3,4,5,6,EPS | 66 | 53,293 | 57,299 | 4,006 | 180,926 | 2.8 | |
| 11/01/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 57,299 | 60,953 | 3,654 | 184,580 | 2.5 | Header 1 removed 11/1/13 |
| 11/04/13 | 1 | 72 | 2,3,4,5,6,EPS | 53 | 60,953 | 76,409 | 15,456 | 200,036 | 3.6 | |
| 11/05/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 76,409 | 78,991 | 2,582 | 202,618 | 1.8 | |
| 11/06/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 78,991 | 82,289 | 3,298 | 205,916 | 2.3 | |
| 11/07/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 82,289 | 85,894 | 3,605 | 209,521 | 2.5 | |
| 11/08/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 85,894 | 88,233 | 2,339 | 211,860 | 1.6 | |
| 11/11/13 | 1 | 72 | 2,3,4,5,6,EPS | 53 | 88,233 | 90,472 | 2,239 | 214,099 | 0.5 | |
| 11/12/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 90,472 | 92,021 | 1,549 | 215,648 | 1.1 | |
| 11/13/13 | 1 | 24 | 2,3,4,5,6,EPS | 53 | 92,021 | 95,451 | 3,430 | 219,078 | 2.4 | |
| 11/14/13 | 1 | 24 | 2,3,4,5,6,EPS | 51 | 95,451 | 98,850 | 3,399 | 222,477 | 2.4 | |
| 11/15/13 | 1 | 24 | 2,3,4,5,6,EPS | 51 | 98,850 | 102,200 | 3,350 | 225,827 | 2.3 | |
| 11/18/13 | 1 | 72 | 2,3,4,5,6,EPS | 51 | 102,200 | 107,680 | 5,480 | 231,307 | 1.3 | |
| 11/19/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 107,680 | 114,159 | 6,479 | 237,786 | 4.5 | Header 2 removed 11/18/13 |
| 11/20/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 114,159 | 122,549 | 8,390 | 246,176 | 5.8 | |
| 11/21/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 122,549 | 123,061 | 512 | 246,688 | 0.4 | |
| 11/22/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 123,061 | 129,534 | 6,473 | 253,161 | 4.5 | |
| 11/25/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 0 | 103 | 103 | 253,264 | 0.1 | |
| 11/26/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 103 | 8,559 | 8,456 | 261,720 | 5.9 | |
| 11/27/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 8,559 | 20,117 | 11,558 | 273,278 | 8.0 | |
| 12/02/13 | 1 | 120 | 3,4,5,6,EPS | 40 | 20,117 | 79,516 | 59,399 | 332,677 | 8.2 | |
| 12/03/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 79,516 | 91,854 | 12,338 | 345,015 | 8.6 | |
| 12/04/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 91,854 | 103,283 | 11,429 | 356,444 | 7.9 | |
| 12/05/13 | 1 | 24 | 3,4,5,6,EPS | 40 | 103,283 | 112,785 | 9,502 | 365,946 | 6.6 | |
| 12/06/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 112,785 | 122,330 | 9,545 | 375,491 | 6.6 | |
| 12/09/13 | 1 | 72 | 3,4,5,6,EPS | 55 | 122,330 | 170,188 | 47,858 | 423,349 | 11.1 | |
| 12/10/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 170,188 | 185,509 | 15,321 | 438,670 | 10.6 | |
| 12/11/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 185,509 | 200,920 | 15,411 | 454,081 | 10.7 | |
| 12/12/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 200,920 | 214,877 | 13,957 | 468,038 | 9.7 | |
| 12/13/13 | 1 | 24 | 3,4,5,6,EPS | 55 | 214,877 | 229,603 | 14,726 | 482,764 | 10.2 | |
| 12/16/13 | 1 | 72 | 4,5,6,EPS | 49 | 229,603 | 266,010 | 36,407 | 519,171 | 8.4 | Header 3 removed 12/13/13 |

Data shown is for recent months activity

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 12/17/13 | 1 | 24 | 4,5,6,EPS | 49 | 266,010 | 281,247 | 15,237 | 534,408 | 10.6 | |
| 12/18/13 | 1 | 24 | 4,5,6,EPS | 49 | 281,247 | 294,671 | 13,424 | 547,832 | 9.3 | |
| 12/19/13 | 1 | 24 | 4,5,6,EPS | 49 | 294,671 | 304,097 | 9,426 | 557,258 | 6.5 | |
| 12/20/13 | 1 | 24 | 4,5,6,EPS | 49 | 304,097 | 315,151 | 11,054 | 568,312 | 7.7 | |
| 12/23/13 | 1 | 72 | 4,5,6,EPS | 49 | 315,151 | 352,173 | 37,022 | 605,334 | 8.6 | |
| 12/24/13 | 1 | 24 | 4,5,6,EPS | 49 | 352,173 | 362,335 | 10,162 | 615,496 | 7.1 | |
| 12/30/13 | 1 | 144 | 4,5,6,EPS | 49 | 362,335 | 415,250 | 52,915 | 668,411 | 6.1 | |
| 12/31/13 | 1 | 24 | 4,5,6,EPS | 44 | 415,250 | 431,429 | 16,179 | 684,590 | 11.2 | |
| 01/02/14 | 1 | 48 | 4,5,6,EPS | 44 | 431,429 | 466,166 | 34,737 | 719,327 | 12.1 | |
| 01/06/14 | 1 | 96 | 4,5,6,EPS | 44 | 466,166 | 513,613 | 47,447 | 766,774 | 8.2 | |
| 01/07/14 | 1 | 24 | 4,5,6,EPS | 44 | N/A | N/A | 13,220 | 779,994 | 9.2 | Meter Innacurate Due to Temp |
| 01/08/14 | 1 | 24 | 4,5,6,EPS | 44 | N/A | N/A | 13,450 | 793,444 | 9.3 | Meter Innacurate Due to Temp |
| 01/09/14 | 1 | 24 | 4,5,6,EPS | 44 | N/A | 3,749 | 15,100 | 808,544 | 10.5 | Flow Meter Reset, Header 4 removed |
| 01/10/14 | 1 | 24 | 5,6,EPS | 44 | 3,749 | 15,043 | 11,294 | 819,838 | 7.8 | |
| 01/13/14 | 1 | 72 | 5,6,7,EPS | 60 | 15,043 | 52,782 | 37,739 | 857,577 | 8.7 | |
| 01/14/14 | 1 | 24 | 5,6,7,EPS | 60 | 52,782 | 68,191 | 15,409 | 872,986 | 10.7 | |
| 01/15/14 | 1 | 24 | 5,6,7,EPS | 60 | 68,191 | 86,290 | 18,099 | 891,085 | 12.6 | |
| 01/16/14 | 1 | 24 | 5,6,7,EPS | 60 | 86,290 | 103,647 | 17,357 | 908,442 | 12.1 | |
| 01/17/14 | 1 | 24 | 5,6,7,EPS | 60 | 103,647 | 120,724 | 17,077 | 925,519 | 11.9 | |
| 01/20/14 | 1 | 72 | 5,6,7,EPS | 60 | 120,724 | 177,150 | 56,426 | 981,945 | 13.1 | |
| 01/21/14 | 1 | 24 | 5,6,7,EPS | 60 | 177,150 | 192,354 | 15,204 | 997,149 | 10.6 | |
| 01/23/14 | 1 | 48 | 5,6,7,EPS | 60 | 192,354 | 209,564 | 17,210 | 1,014,359 | 6.0 | |
| 01/24/14 | 1 | 24 | 5,6,7,EPS | 60 | 209,564 | 219,596 | 10,032 | 1,024,391 | 7.0 | |
| 01/27/14 | 1 | 72 | 5,6,7,EPS | 60 | 219,596 | 241,870 | 22,274 | 1,046,665 | 5.2 | |
| 01/28/14 | 1 | 24 | 5,6,7,EPS | 60 | 241,870 | 249,752 | 7,882 | 1,054,547 | 5.5 | |
| 01/29/14 | 1 | 24 | 5,6,7,EPS | 60 | 249,752 | 256,270 | 6,518 | 1,061,065 | 4.5 | Header 5 removed 01/29/14 |
| 01/30/14 | 1 | 24 | 6,7,EPS | 51 | 256,270 | 262,157 | 5,887 | 1,066,952 | 4.1 | |
| 01/31/14 | 1 | 24 | 6,7,EPS | 51 | 262,157 | 268,122 | 5,965 | 1,072,917 | 4.1 | |
| 02/03/14 | 1 | 72 | 6,7,EPS | 51 | 268,122 | 292,592 | 24,470 | 1,097,387 | 5.7 | |
| 02/04/14 | 1 | 24 | 6,7,EPS | 51 | 292,592 | 299,040 | 6,448 | 1,103,835 | 4.5 | |
| 02/05/14 | 1 | 24 | 6,7,EPS | 51 | 299,040 | 309,154 | 10,114 | 1,113,949 | 7.0 | |
| 02/06/14 | 1 | 24 | 6,7,EPS | 51 | 309,154 | 318,585 | 9,431 | 1,123,380 | 6.5 | |
| 02/07/14 | 1 | 24 | 6,7,EPS | 51 | 318,585 | 328,074 | 9,489 | 1,132,869 | 6.6 | |
| 02/10/14 | 1 | 72 | 6,7,EPS | 51 | 328,074 | 344,536 | 16,462 | 1,149,331 | 3.8 | |
| 02/11/14 | 1 | 24 | 6,7,EPS | 51 | 344,536 | 347,331 | 2,795 | 1,152,126 | 1.9 | |
| 02/12/14 | 1 | 24 | 6,7,EPS | 47 | 347,331 | 349,076 | 1,745 | 1,153,871 | 1.2 | System Temporarily Disable for Relocation |
| 02/18/14 | 1 | 144 | 6,7,EPS | 47 | 349,076 | 349,084 | 8 | 1,153,879 | 0.0 | Pump maintenance and Freezing Delays |
| 02/19/14 | 1 | 24 | 6,7,EPS | 47 | 349,084 | 351,236 | 2,152 | 1,156,031 | 1.5 | |
| 02/20/14 | 1 | 24 | 6,7,EPS | 47 | 351,236 | 358,591 | 7,355 | 1,163,386 | 5.1 | |
| 02/21/14 | 1 | 24 | 6,7,8,EPS | 65 | 358,591 | 369,538 | 10,947 | 1,174,333 | 7.6 | |
| 02/24/14 | 1 | 72 | 7,8,EPS | 59 | 369,538 | 385,722 | 16,184 | 1,190,517 | 3.7 | |
| 02/25/14 | 1 | 24 | 7,8,EPS | 59 | 385,722 | 389,100 | 3,378 | 1,193,895 | 2.3 | |
| 02/26/14 | 1 | 24 | 7,8,EPS | 59 | 389,100 | 392,185 | 3,085 | 1,196,980 | 2.1 | |
| 02/27/14 | 1 | 24 | 7,8,EPS | 59 | 392,185 | 394,083 | 1,898 | 1,198,878 | 1.3 | |
| 02/28/14 | 1 | 24 | 7,8,EPS | 59 | 394,083 | 394,858 | 775 | 1,199,653 | 0.5 | |
| 03/03/14 | 1 | 72 | 7,8,9,EPS | 66 | N/A | N/A | 12,100 | 1,211,753 | 2.8 | Flowmeter Froze (Read by Gauging Tank) |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-1)

| DATE | HOURS OF OPERATION | DEEP WELL FLOW METER START (Gal) | DEEP WELL FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 10/23/13 | 29 | 0 | 24,640 | 24,640 | 24,640 | 14.2 | |
| 10/24/13 | 24 | 24,640 | 31,757 | 7,117 | 31,757 | 4.9 | |
| 10/25/13 | 24 | 31,757 | 39,567 | 7,810 | 39,567 | 5.4 | Slight blockage cleaned from meter |
| 10/28/13 | 72 | 39,567 | 91,820 | 52,253 | 91,820 | 12.1 | |
| 10/29/13 | 24 | 91,820 | 101,672 | 9,852 | 101,672 | 6.8 | |
| 10/30/13 | 24 | 101,672 | 111,472 | 9,800 | 111,472 | 6.8 | |
| 10/31/13 | 24 | 111,472 | 120,558 | 9,086 | 120,558 | 6.3 | |
| 11/01/13 | 24 | 120,558 | 128,248 | 7,690 | 128,248 | 5.3 | |
| 11/04/13 | 72 | 128,248 | 162,721 | 34,473 | 162,721 | 8.0 | |
| 11/05/13 | 24 | 162,721 | 173,853 | 11,132 | 173,853 | 7.7 | |
| 11/06/13 | 24 | 173,853 | 189,770 | 15,917 | 189,770 | 11.1 | |
| 11/07/13 | 24 | 189,770 | 210,266 | 20,496 | 210,266 | 14.2 | |
| 11/08/13 | 24 | 210,266 | 220,964 | 10,698 | 220,964 | 7.4 | |
| 11/11/13 | 72 | 220,964 | 235,035 | 14,071 | 235,035 | 3.3 | |
| 11/12/13 | 24 | 235,035 | 254,720 | 19,685 | 254,720 | 13.7 | |
| 11/13/13 | 24 | 254,720 | 272,758 | 18,038 | 272,758 | 12.5 | |
| 11/14/13 | 24 | 272,758 | 275,336 | 2,578 | 275,336 | 1.8 | |
| 11/15/13 | 24 | 275,336 | 281,413 | 6,077 | 281,413 | 4.2 | |
| 11/18/13 | 72 | 281,413 | 318,812 | 37,399 | 318,812 | 8.7 | |
| 11/19/13 | 24 | 318,812 | 328,059 | 9,247 | 328,059 | 6.4 | Well Taken Offline for Excavation |
| 11/27/13 | 24 | 328,059 | 351,245 | 23,186 | 351,245 | 16.1 | |
| 12/02/13 | 120 | 351,245 | 414,031 | 62,786 | 414,031 | 8.7 | Well Shut Off for Excavation Activities |
| 12/04/13 | 24 | 430,536 | 446,631 | 16,095 | 430,126 | 11.2 | |
| 12/05/13 | 24 | 446,631 | 459,826 | 13,195 | 443,321 | 9.2 | |
| 12/06/13 | 24 | 459,826 | 468,837 | 9,011 | 452,332 | 6.3 | |
| 12/09/13 | 72 | 468,837 | 499,005 | 30,168 | 482,500 | 7.0 | |
| 12/10/13 | 24 | 499,005 | 508,914 | 9,909 | 492,409 | 6.9 | |
| 12/11/13 | 24 | 508,914 | 519,185 | 10,271 | 502,680 | 7.1 | |
| 12/12/13 | 24 | 519,185 | 528,500 | 9,315 | 511,995 | 6.5 | |
| 12/13/13 | 24 | 528,500 | 535,384 | 6,884 | 518,879 | 4.8 | |
| 12/16/13 | 72 | 535,384 | 555,625 | 20,241 | 539,120 | 4.7 | |
| 12/17/13 | 24 | 555,625 | 563,870 | 8,245 | 547,365 | 5.7 | |
| 12/18/13 | 24 | 563,870 | 572,558 | 8,688 | 556,053 | 6.0 | |
| 12/19/13 | 24 | 572,588 | 578,579 | 5,991 | 562,044 | 4.2 | |
| 12/20/13 | 24 | 578,579 | 585,086 | 6,507 | 568,551 | 4.5 | |
| 12/23/13 | 72 | 585,086 | 604,411 | 19,325 | 587,876 | 4.5 | |
| 12/24/13 | 24 | 604,411 | 613,829 | 9,418 | 597,294 | 6.5 | |
| 12/30/13 | 144 | 613,829 | 669,247 | 55,418 | 652,712 | 6.4 | |
| 12/31/13 | 24 | 669,247 | 678,171 | 8,924 | 661,636 | 6.2 | |
| 01/02/14 | 48 | 678,171 | 697,609 | 19,438 | 681,074 | 6.7 | |
| 01/06/14 | 96 | 697,609 | 733,339 | 35,730 | 716,804 | 6.2 | Well Taken Offline |

Data shown is for recent months activity

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-2)

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/19/13 | 4 | 0 | 3,866 | 3,866 | 3,866 | 16.1 | |
| 11/20/13 | 24 | 3,866 | 18,857 | 14,991 | 18,857 | 10.4 | |
| 11/21/13 | 24 | 18,857 | 31,307 | 12,450 | 31,307 | 8.6 | |
| 11/22/13 | 24 | 31,307 | 52,611 | 21,304 | 52,611 | 14.8 | |
| 11/25/13 | 72 | 52,611 | 62,866 | 10,255 | 62,866 | 2.4 | |
| 11/26/13 | 24 | 62,866 | 69,596 | 6,730 | 69,596 | 4.7 | |
| 11/27/13 | 24 | 0 | 15,926 | 15,926 | 85,522 | 11.1 | |
| 12/02/13 | 120 | 15,926 | 81,682 | 65,756 | 151,278 | 9.1 | |
| 12/03/13 | 24 | 81,682 | 94,975 | 13,293 | 164,571 | 9.2 | |
| 12/04/13 | 24 | 94,682 | 108,260 | 13,578 | 178,149 | 9.4 | |
| 12/05/13 | 24 | 108,260 | 122,026 | 13,766 | 191,915 | 9.6 | |
| 12/06/13 | 24 | 122,026 | 134,343 | 12,317 | 204,232 | 8.6 | |
| 12/09/13 | 72 | 134,343 | 164,429 | 30,086 | 234,318 | 7.0 | |
| 12/10/13 | 24 | 164,429 | 174,915 | 10,486 | 244,804 | 7.3 | |
| 12/11/13 | 24 | 174,915 | 183,567 | 8,652 | 253,456 | 6.0 | |
| 12/12/13 | 24 | 183,567 | 193,229 | 9,662 | 263,118 | 6.7 | |
| 12/13/13 | 24 | 193,229 | 202,100 | 8,871 | 271,989 | 6.2 | |
| 12/16/13 | 72 | 202,100 | 229,583 | 27,483 | 299,472 | 6.4 | |
| 12/17/13 | 24 | 229,583 | 237,924 | 8,341 | 307,813 | 5.8 | |
| 12/18/13 | 24 | 237,924 | 246,510 | 8,586 | 316,399 | 6.0 | |
| 12/19/13 | 24 | 246,510 | 255,486 | 8,976 | 325,375 | 6.2 | |
| 12/20/13 | 24 | 255,486 | 263,423 | 7,937 | 333,312 | 5.5 | |
| 12/23/13 | 72 | 263,423 | 286,843 | 23,420 | 356,732 | 5.4 | |
| 12/24/13 | 24 | 286,843 | 297,632 | 10,789 | 367,521 | 7.5 | |
| 12/30/13 | 144 | 297,632 | 360,191 | 62,559 | 430,080 | 7.2 | |
| 12/31/13 | 24 | 360,191 | 369,462 | 9,271 | 439,351 | 6.4 | |
| 01/02/14 | 48 | 369,462 | 390,036 | 20,574 | 459,925 | 7.1 | |
| 01/06/14 | 96 | 390,036 | 429,927 | 39,891 | 499,816 | 6.9 | |
| 01/07/14 | 24 | 429,927 | 440,516 | 10,589 | 510,405 | 7.4 | |
| 01/08/14 | 24 | 440,516 | 459,411 | 18,895 | 529,300 | 13.1 | |
| 01/09/14 | 24 | 459,411 | 472,954 | 13,543 | 542,843 | 9.4 | |
| 01/10/14 | 24 | 472,954 | 486,509 | 13,555 | 556,398 | 9.4 | |
| 01/13/14 | 72 | 486,509 | 529,157 | 42,648 | 599,046 | 9.9 | |
| 01/24/14 | 24 | 529,157 | 543,032 | 13,875 | 612,921 | 9.6 | |
| 01/15/14 | 24 | 543,032 | 557,261 | 14,229 | 627,150 | 9.9 | |
| 01/16/14 | 24 | 557,261 | 571,278 | 14,017 | 641,167 | 9.7 | |
| 01/17/14 | 24 | 571,278 | 585,429 | 14,151 | 655,318 | 9.8 | |
| 01/20/14 | 72 | 585,429 | 627,704 | 42,275 | 697,593 | 9.8 | |
| 01/21/14 | 24 | 627,704 | 641,168 | 13,464 | 711,057 | 9.4 | |
| 01/23/14 | 48 | 641,168 | 666,348 | 25,180 | 736,237 | 8.7 | |
| 01/24/14 | 24 | 666,348 | 684,142 | 17,794 | 754,031 | 12.4 | |
| 01/27/14 | 72 | 684,142 | 726,325 | 42,183 | 796,214 | 9.8 | |
| 01/28/14 | 24 | 726,325 | 740,701 | 14,376 | 810,590 | 10.0 | |
| 01/29/14 | 24 | 740,701 | 754,662 | 13,961 | 824,551 | 9.7 | |
| 01/30/14 | 24 | 754,662 | 767,882 | 13,220 | 837,771 | 9.2 | |
| 01/31/14 | 24 | 767,882 | 782,573 | 14,691 | 852,462 | 10.2 | |
| 02/03/14 | 72 | 782,573 | 827,501 | 44,928 | 897,390 | 10.4 | |
| 02/04/14 | 24 | 827,501 | 838,572 | 11,071 | 908,461 | 7.7 | |
| 02/05/14 | 24 | 838,572 | 853,159 | 14,587 | 923,048 | 10.1 | |
| 02/06/14 | 24 | 853,159 | 866,882 | 13,723 | 936,771 | 9.5 | |
| 02/07/14 | 24 | 866,882 | 881,016 | 14,134 | 950,905 | 9.8 | |
| 02/10/14 | 72 | 881,016 | 923,079 | 42,063 | 992,968 | 9.7 | |
| 02/11/14 | 24 | 923,079 | 936,961 | 13,882 | 1,006,850 | 9.6 | |
| 02/12/14 | 24 | 936,961 | 950,902 | 13,941 | 1,020,791 | 9.7 | |

Data shown is for recent months activity

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-2)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 02/13/14 | 24 | 950,902 | 976,618 | 25,716 | 1,046,507 | 17.9 | |
| 02/14/14 | 24 | 976,618 | 990,724 | 14,106 | 1,060,613 | 9.8 | |
| 02/18/14 | 86 | 990,724 | 1,051,980 | 61,256 | 1,121,869 | 11.9 | |
| 02/19/14 | 24 | 1,053,780 | 1,073,780 | 20,000 | 1,141,869 | 13.9 | |
| 02/20/14 | 24 | 1,073,780 | 1,083,940 | 10,160 | 1,152,029 | 7.1 | |
| 02/21/14 | 24 | 1,083,940 | 1,114,610 | 30,670 | 1,182,699 | 21.3 | |
| 02/24/14 | 72 | 1,114,610 | 1,163,430 | 48,820 | 1,231,519 | 11.3 | |
| 02/25/14 | 24 | 1,163,430 | 1,184,280 | 20,850 | 1,252,369 | 14.5 | |
| 02/26/14 | 24 | 0 | 4,180 | 4,180 | 1,256,549 | 2.9 | Flowmeter Reset |
| 02/27/14 | 24 | 4,180 | 9,643 | 5,463 | 1,262,012 | 3.8 | |
| 02/28/14 | 24 | 9,643 | 14,717 | 5,074 | 1,267,086 | 3.5 | |
| 03/03/14 | 72 | 14,717 | 43,855 | 29,138 | 1,296,224 | 6.7 | |

Data shown is for recent months activity

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER START (KGal) | DISCHARGE FLOW METER FINISH (KGal) | DISCHARGED VOLUME (Gal) DAILY | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 10/17/13 | 1.5 | 0.45 | 19.49 | 19,040 | 19,040 | Test Operation: Potable Water |
| 10/18/13 | 1.0 | 19.49 | 27.50 | 8,010 | 27,050 | |
| 10/22/13 | 4.0 | 27.50 | 85.74 | 58,240 | 85,290 | |
| 10/23/13 | 2.0 | 85.74 | 116.87 | 31,130 | 116,420 | |
| 10/24/13 | 1.3 | 116.87 | 135.20 | 18,330 | 134,750 | |
| 10/28/13 | 4.5 | 135.20 | 200.88 | 65,680 | 200,430 | PVSC Compliance Sample collected |
| 10/29/13 | 4.0 | 200.88 | 258.53 | 57,650 | 258,080 | |
| 11/01/13 | 4.3 | 258.53 | 300.34 | 41,810 | 299,890 | |
| 11/04/13 | 4.8 | 300.34 | 368.43 | 68,090 | 367,980 | |
| 11/05/13 | 4.3 | 368.43 | 408.77 | 40,340 | 408,320 | |
| 11/06/13 | 1.5 | 408.77 | 425.89 | 17,120 | 425,440 | |
| 11/07/13 | 1.0 | 425.89 | 453.88 | 27,990 | 453,430 | |
| 11/08/13 | 1.0 | 453.88 | 478.10 | 24,220 | 477,650 | |
| 11/12/13 | 4.5 | 478.10 | 526.82 | 48,720 | 526,370 | |
| 11/14/13 | 1.3 | 526.82 | 556.26 | 29,440 | 555,810 | |
| 11/18/13 | 5.0 | 556.26 | 619.36 | 63,100 | 618,910 | PVSC Compliance Sample collected |
| 11/21/13 | 4.0 | 619.36 | 652.91 | 33,550 | 652,460 | |
| 11/26/13 | 6.0 | 652.91 | 719.80 | 66,890 | 719,350 | |
| 11/27/13 | 6.0 | 719.80 | 784.49 | 64,690 | 784,040 | |
| 11/29/13 | 5.0 | 784.49 | 840.47 | 55,980 | 840,020 | |
| 12/02/13 | 6.5 | 840.47 | 923.11 | 82,640 | 922,660 | |
| 12/03/13 | 7.0 | 923.11 | 1,011.32 | 88,210 | 1,010,870 | PVSC Compliance Sample collected |
| 12/05/13 | 8.0 | 1,011.32 | 1,103.37 | 92,050 | 1,102,920 | |
| 12/06/13 | 4.0 | 1,103.37 | 1,143.07 | 39,700 | 1,142,620 | |
| 12/09/13 | 6.5 | 1,143.07 | 1,224.23 | 81,160 | 1,223,780 | |
| 12/10/13 | 6.0 | 1,224.23 | 1,286.03 | 61,800 | 1,285,580 | |
| 12/13/13 | 8.0 | 1,286.03 | 1,374.91 | 88,880 | 1,374,460 | |
| 12/16/13 | 8.0 | 1,374.91 | 1,485.04 | 110,130 | 1,484,590 | |
| 12/17/13 | 6.0 | 1,485.04 | 1,551.22 | 66,180 | 1,550,770 | |
| 12/18/13 | 7.0 | 1,551.22 | 1,628.26 | 77,040 | 1,627,810 | |
| 12/19/13 | 4.5 | 1,628.26 | 1,678.47 | 50,210 | 1,678,020 | |
| 12/20/13 | 5.0 | 1,678.47 | 1,732.93 | 54,460 | 1,732,480 | |
| 12/23/13 | 8.0 | 1,732.93 | 1,894.96 | 162,030 | 1,894,510 | |
| 12/24/13 | 7.0 | 1,894.96 | 1,989.84 | 94,880 | 1,989,390 | |
| 12/27/13 | 5.0 | 1,989.84 | 2,054.25 | 64,410 | 2,053,800 | |
| 12/30/13 | 8.0 | 2,054.25 | 2,147.46 | 93,210 | 2,147,010 | |
| 12/31/13 | 8.0 | 2,147.46 | 2,244.54 | 97,080 | 2,244,090 | |
| 01/02/14 | 8.0 | 2,244.54 | 2,368.54 | 124,000 | 2,368,090 | |
| 01/06/14 | 8.0 | 2,368.54 | 2,485.40 | 116,860 | 2,484,950 | |
| 01/09/14 | 8.0 | 2,485.40 | 2,567.15 | 81,750 | 2,566,700 | |
| 01/10/14 | 8.0 | 2,567.15 | 2,635.97 | 68,820 | 2,635,520 | |
| 01/13/14 | 6.0 | 2,635.97 | 2,719.26 | 83,290 | 2,718,810 | |
| 01/14/14 | 8.0 | 2,719.26 | 2,864.73 | 145,470 | 2,864,280 | |
| 01/15/14 | 8.0 | 2,864.73 | 2,981.21 | 116,480 | 2,980,760 | |
| 01/16/14 | 8.0 | 2,981.21 | 3,111.28 | 130,070 | 3,110,830 | |
| 01/17/14 | 8.0 | 3,111.28 | 3,190.67 | 79,390 | 3,190,220 | |
| 01/20/14 | 8.0 | 3,190.67 | 3,297.59 | 106,920 | 3,297,140 | |
| 01/21/14 | 8.0 | 3,297.59 | 3,338.21 | 40,620 | 3,337,760 | |
| 01/27/14 | 8.0 | 3,338.21 | 3,438.26 | 100,050 | 3,437,810 | |
| 01/31/14 | 8.0 | 3,438.26 | 3,516.69 | 78,430 | 3,516,240 | |
| 02/04/14 | 8.0 | 3,516.69 | 3,628.15 | 111,460 | 3,627,700 | PVSC Compliance Sample collected |
| 02/07/14 | 8.0 | 3,628.15 | 3,733.31 | 105,160 | 3,732,860 | |
| 02/11/14 | 8.0 | 3,733.31 | 3,854.45 | 121,140 | 3,854,000 | |
| 02/12/14 | 2.0 | 3,854.45 | 3,884.29 | 29,840 | 3,883,840 | |
| 02/14/14 | 6.0 | 3,884.29 | 3,933.69 | 49,400 | 3,933,240 | |
| 02/15/14 | 8.0 | 3,933.69 | 4,032.69 | 99,000 | 4,032,240 | |
| 02/18/14 | 8.0 | 4,032.69 | 4,123.91 | 91,220 | 4,123,460 | |
| 02/20/14 | 8.0 | 4,123.91 | 4,251.33 | 127,420 | 4,250,880 | |

Data shown is for recent months activity

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER START (KGal) | DISCHARGE FLOW METER FINISH (KGal) | DISCHARGED VOLUME (Gal) DAILY | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 02/21/14 | 8.0 | 4,251.33 | 4,412.37 | 161,040 | 4,411,920 | |
| 02/22/14 | 8.0 | 4,412.37 | 4,536.78 | 124,410 | 4,536,330 | |
| 02/24/14 | 8.0 | 4,536.78 | 4,660.60 | 123,820 | 4,660,150 | |
| 02/25/14 | 8.0 | 4,660.60 | 4,850.50 | 189,900 | 4,850,050 | |
| 02/26/14 | 8.0 | 4,850.50 | 4,970.69 | 120,190 | 4,970,240 | |

Data shown is for recent months activity

## Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Stockpiled Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID (One Sample Per Stockpile Quadrant) | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 7-Jan | <20 | 7-20-a | 500 | 124-7-20-a1 | 10/31/2013 | 14:20 | 5.8 | 10, 11, 12, 13 | | |
| | | | | 124-7-20-a2 | 10/31/2013 | 14:25 | 7.8 | 10, 11, 12, 13 | | |
| | | | | 124-7-20-a3 | 10/31/2013 | 14:30 | 4.6 | 10, 11, 12, 13 | | |
| | | | | 124-7-20-a4 | 10/31/2013 | 14:35 | 4.7 | 10, 11, 12, 13 | | |
| 7-12 | <20 | 12-20-a | 500 | 124-12-20-a1 | 11/26/2013 | 15:00 | 26.1 | | Yes | |
| | | | | 124-12-20-a2 | 11/26/2013 | 15:05 | 2.9 | ** | | |
| | | | | 124-12-20-a3 | 11/26/2013 | 15:10 | 7.8 | ** | | |
| | | | | 124-12-20-a4 | 11/26/2013 | 15:15 | 23.2 | | Yes | |
| 7-12 | <20 | 12-20-b | 500 | 124-12-20-b1 | 11/26/2013 | 15:20 | 4.3 | ** | | |
| | | | | 124-12-20-b2 | 11/26/2013 | 15:25 | 2.5 | ** | | |
| | | | | 124-12-20-b3 | 11/26/2013 | 15:30 | 5.1 | ** | | |
| | | | | 124-12-20-b4 | 11/26/2013 | 15:35 | 5.8 | ** | | |
| 12-22 | <20 | 22-20-a | 600 | 124-22-20-a1 | 12/13/2013 | 13:30 | 5.5 | ** | | |
| | | | | 124-22-20-a2 | 12/13/2013 | 13:35 | 11.9 | ** | | |
| | | | | 124-22-20-a3 | 12/13/2013 | 13:40 | 1.3 | ** | | |
| | | | | 124-22-20-a4 | 12/13/2013 | 13:45 | 2.3 | ** | | |
| 12-25 | <20 | 25-20-a | 1000 | 124-25-20-a1 | 12/23/2013 | 9:00 | 1.6 | ** | | |
| | | | | 124-25-20-a2 | 12/23/2013 | 9:05 | 1.7 | ** | | |
| | | | | 124-25-20-a3 | 12/23/2013 | 9:10 | 10.8 | ** | | |
| | | | | 124-25-20-a4 | 12/23/2013 | 9:15 | 17.4 | ** | | |
| 20-29 | <20 | 29-20-a | 500 | 124-29-20-a1 | 1/13/2014 | 14:00 | 0.31 | ** | | |
| | | | | 124-29-20-a2 | 1/13/2014 | 14:05 | 0.84 | ** | | |
| | | | | 124-29-20-a3 | 1/13/2014 | 14:10 | 3.4 | ** | | |
| | | | | 124-29-20-a4 | 1/13/2014 | 14:15 | 1.9 | ** | | |
| 30-41 | >1000 | 41-1000-a | 750 | 124-41-1000-a1 | 2/25/2014 | 12:40 | 1,750 | | | Pending |
| | | | | 124-41-1000-a2 | 2/25/2014 | 12:45 | 3,690 | | | Pending |
| | | | | 124-41-1000-a3 | 2/25/2014 | 12:50 | 3,410 | | | Pending |
| | | | | 124-41-1000-a4 | 2/25/2014 | 12:55 | 453 | | Pending | |
| 30-41 | >1000 | 41-1000-b | 750 | 124-41-1000-b1 | 2/25/2014 | 13:00 | 490 | | Pending | |
| | | | | 124-41-1000-b2 | 2/25/2014 | 13:05 | 1,110 | | | Pending |
| | | | | 124-41-1000-b3 | 2/25/2014 | 13:10 | 669 | | Pending | |
| | | | | 124-41-1000-b4 | 2/25/2014 | 13:15 | 1,920 | | | Pending |

**Notes:**
*Material placement locations are approximate.
**Material currently stockpiled.

## Attachment 7:  Perimeter Pools Update




LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL

GRAPHIC SCALE

100' 50' 0 100' 200'

**IN PROGRESS**
04-19-2010

STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




G:\DWGS\102\10210\Dewatering\Perimeter Pool Data.dwg
Apr 19, 2010 at 3:12pm
ireva





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data


| | | | | | | | | | | 087-MW- | | | 134-MW- | | 073-MW- | | 140- | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | Y20 | 001 | O19 | V09 | Q08 | BB-11 | Y10 | MW-06 | MW-07 |
| Date | | | | | | | | | | | | | | | | | | |
| 8/2/2013 | | | | | | | | | | | | | 5.2 | 6.1 | 4.6 | 3.7 | 7.0 | 5.2 |
| 8/9/2013 | | | | | | | | | | | | | 5.1 | 6.0 | 3.4 | 3.8 | 6.5 | 5.3 |
| 8/16/2013 | 6.5 | 5.8 | 6.2 | 6.1 | 6.8 | 9.4 | 4.7 | 7.4 | 7.4 | 4.6 | 6.8 | 8.4 | 5.4 | 6.3 | 3.2 | 3.8 | 7.1 | 5.5 |
| 8/23/2013 | | | | | | | | | | | | | 5.9 | 6.2 | 3.9 | 3.8 | 6.6 | 6.1 |
| 8/29/2013 | 6.2 | 5.9 | 6.4 | 6.3 | 7.1 | 9.3 | 4.8 | 7.4 | 7.3 | 4.6 | 6.6 | 8.2 | | | | | | |
| 8/30/2013 | | | | | | | | | | | | | 5.8 | 6.1 | 3.2 | 4.0 | 6.6 | 5.4 |
| 9/5/2013 | | | | | | | | | | | | | 5.2 | 5.6 | 3.2 | 3.5 | 6.2 | 5.4 |
| 9/13/2013 | 5.9 | 5.7 | 6.0 | 5.8 | 6.1 | 9.5 | 4.6 | 6.9 | 7.4 | 4.7 | 5.4 | 8.3 | | | | | | |
| 9/16/2013 | | | | | | | | | | | | | 5.5 | 5.6 | 3.2 | 3.7 | 6.0 | 5.0 |
| 10/2/2013 | 5.7 | 5.6 | 5.9 | 5.5 | 5.8 | 9.4 | 4.4 | 6.6 | 7.3 | 4.8 | 5.9 | 7.8 | | | | | | |
| 10/4/2013 | | | | | | | | | | | | | 4.7 | 6.1 | 3.3 | 4.1 | 6.2 | 5.5 |
| 10/10/2013 | | | | | | | | | | | | | 5.2 | 5.5 | 4.2 | 3.9 | 6.1 | 5.0 |
| 10/17/2013 | | | | | | | | | | | | | 4.8 | 5.3 | 3.1 | 3.7 | 5.9 | 5.1 |
| 10/18/2013 | 5.5 | 5.5 | 5.6 | 5.3 | 5.8 | 9.4 | 4.4 | 6.3 | 7.4 | 4.8 | 6.2 | 7.9 | | | | | | |
| 10/25/2013 | | | | | | | | | | | | | 4.3 | 5.2 | 3.1 | 3.9 | 5.8 | 5.5 |
| 11/4/2013 | 5.4 | 5.4 | 5.4 | 5.1 | 5.6 | 9.3 | 4.3 | 6.2 | 7.1 | 4.7 | 6.1 | 7.7 | | | | | | |
| 11/15/2013 | | | | | | | | | | | | | 3.7 | 5.0 | 3.9 | 4.4 | 5.8 | 4.8 |
| 11/22/2013 | 5.3 | 5.3 | 5.1 | 4.9 | 5.6 | 9.3 | 4.6 | 6.1 | 7.1 | 4.7 | 6.4 | 7.9 | | | | | | |
| 12/4/2013 | 7.6 | 4.7 | 5.1 | 5.1 | 6.0 | 9.3 | 4.9 | 6.3 | 7.5 | 5.2 | 6.5 | 8.1 | 5.2 | 5.8 | 7.0 | | 6.9 | 5.1 |
| 12/17/2013 | | 4.7 | 4.7 | 5.7 | 6.5 | 9.5 | 4.6 | 8.1 | 7.7 | 4.5 | 6.3 | 7.8 | | | | | 7.3 | 5.7 |
| 12/31/2013 | | 4.8 | 5.6 | 6.0 | 7.1 | 9.9 | 7.5 | | 8.6 | 5.0 | 6.6 | 8.1 | | | | | | |
| 1/2/2014 | | | | | | | | | | | | | 5.9 | 7.0 | 7.4 | | 7.4 | 5.8 |
| 1/9/2014 | | | | | | | | 7.9 | | | | | | | | | | |
| 1/15/2014 | | | | | | | | | | | | | 6.5 | 7.3 | 7.2 | | 7.2 | 6.5 |
| 1/16/2014 | | 5.3 | 6.0 | 6.3 | 7.3 | | 7.6 | 7.8 | 8.3 | 4.9 | 7.5 | 8.7 | | | | | | |
| 2/3/2014 | | | | | | | | | | | | | 6.2 | 7.1 | 7.0 | | 7.0 | 7.2 |
| 2/4/2014 | | | | 6.4 | 6.7 | | 7.5 | | | 4.7 | 7.2 | 8.2 | | | | | | |
| 2/17/2014 | | | | | | | | | | | | | | 6.8 | | | 6.8 | 5.7 |
| 2/21/2014 | | | | 6.2 | 7.2 | | 7.4 | | | 4.8 | | 8.0 | | | | | | |


## Attachment 8: Quality and Level Data in GWET Wells

(Not provided in this submittal - provided on a quarterly basis)

## Attachment 9: Surcharge Monitoring Update

- Surcharge Monitoring Plan Report Figures B1 and F1 *(figures updated to show installed locations)*




SECTION A–A

Installed Instrumentation Locations

Instrumentation Locations Not Installed

| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–1 | 685276.02 | 601927.05 |
| FS–2 | 685323.86 | 601748.51 |
| HS–1 | 685597.02 | 601567.16 |
| HS–2 | 685511.42 | 601690.72 |
| HS–3 | 685421.98 | 601800.88 |
| HS–4 | 685313.18 | 601947.19 |
| HS–5 | 685480.23 | 601623.90 |
| HS–6 | 685518.78 | 601480.25 |
| HS–7 | 685413.06 | 601624.11 |
| HS–8 | 685204.27 | 601911.97 |
| VI–1 | 685624.44 | 601515.06 |
| VI–2 | 685578.58 | 601462.08 |
| VRC–1 | 685505.92 | 601505.39 |
| VRC–2 | 685434.27 | 601785.68 |
| VRC–3 | 685262.85 | 601914.43 |
| SP–1 | 685567.71 | 601633.29 |
| SP–2 | 685410.62 | 601852.31 |
| SP–3 | 685276.93 | 602033.96 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 07/19/13
Checked/Date: AE 07/19/13

Honeywell
101 COLUMBIA RD., BOX 2106
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN 1S

Figure F1



J:\Projects\HONEYWELL\CORE\ CITY\Dwg Design-SA6-(SA7)\SA6(SA7)Figure - Surcharge Area Instrumentation Plan.dwg Fri, 19 Jul 2013 - 12:29pm mgershfeld

EXCAVATE MATERIAL ABOVE FORCE MAIN TO PLACE SP4–SP10 IN DIRECT CONTACT WITH STRUCTURE

EXISTING 72" PVSC FORCE MAIN

AS BUILT SENSOR LOCATION 686080.23 602774.18 ELEV=11.97

AS BUILT SENSOR LOCATION 686125.20 602179.75 ELEV=12.74

AS BUILT SENSOR LOCATION 686022.45 602394.16 ELEV=11.04

AS BUILT SENSOR LOCATION 685961.96 602514.81 ELEV=9.88


AS BUILT SENSOR LOCATION 685904.43 602635.42 ELEV=8.85

AS BUILT SENSOR LOCATION 685848.02 602762.07 ELEV=7.32

INCLINOMETERS BETWEEN HYDRAULIC BARRIER AND 72" FORCE MAIN

SEE NOTE 7 (TYP)


SA-7 FINAL GRADE (ACTUAL GRADES VARY)




SECTION A–A

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| VI–1 | 686123 | 602109 |
| VI–2 | 686029 | 602048 |
| VI–3 | 685927 | 602572 |
| VI–4 | 685866 | 602701 |
| FS1 | 685981 | 602115 |
| FS2 | 685863 | 602451 |
| FS3 | 685811 | 602689 |
| FS4 | 685723 | 602723 |
| HS1 | 685959 | 602414 |
| HS2 | 685929 | 602333 |
| HS3 | 685865 | 602294 |
| HS4 | 685920 | 602491 |
| HS5 | 685787 | 602414 |
| ~~HS6~~ | ~~685785~~ | ~~602650~~ |
| HS7 | 685696 | 602582 |
| ~~HS8~~ | ~~685826~~ | ~~602796~~ |
| HS9 | 685624 | 602691 |

| | | |
|---|---|---|
| SP1 | 685881 | 602205 |
| SP2 | 685757 | 602416 |
| SP3 | 685613 | 602662 |
| ~~SP4~~ | ~~685953~~ | ~~602533~~ |
| ~~SP5~~ | ~~685931~~ | ~~602578~~ |
| ~~SP6~~ | ~~685906~~ | ~~602634~~ |
| ~~SP7~~ | ~~685887~~ | ~~602676~~ |
| ~~SP8~~ | ~~685867~~ | ~~602721~~ |
| ~~SP9~~ | ~~685849~~ | ~~602764~~ |
| ~~SP10~~ | ~~685884~~ | ~~602781~~ |




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. COMMENCE FILL AT THE SEDIMENTATION BASIN AND WORK TOWARDS THE HACKENSACK RIVER.
6. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
7. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
8. AT ALL SURVEY LOCATIONS CLEAN ADEQUATELY A SUFFICIENT AREA ON THE TOP SURFACE OF THE 72 INCH FORCE MAIN TO EPOXY THE SURVEY MARKER AND ELECTRONIC EQUIPMENT.

Installed Instrumentation Locations

Instrumentation Locations Not Installed

VI–2 INCLINOMETER LOCATION
FS–1–1 SETTLEMENT MONITORING POINT FULL – SETUP
HS–1–1 SETTLEMENT MONITORING POINT HALF – SETUP
SP12 SETTLEMENT MONITORING PLATFORM
RP APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7)
VRC1 VIBRATING WIRE PIEZOMETER IN STRATUM RC
A1 ACOUSTICAL LOCATION FOR DISCUSSION PURPOSES ONLY
AS3 ACOUSTICAL/SURVEY LOCATION FOR DISCUSSION PURPOSES ONLY
STATION RELOCATED OR ELIMINATED DUE TO SURCHARGE PILE RECONFIGURATION

0 15 30 60
SCALE IN FEET

Prepared/Date: RJR 08/16/13
Checked/Date: AE 08/16/13

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec


INSTRUMENTATION LOCATION PLAN 1N
Project 3480-09-0006
Figure B1




J:\Projects\HONEYWELL\JERSEY CITY\Dwg Design–SA6–CSD\CAD\SA6N\100 Percent\Figure 1 Surcharge Settling Monitoring Plan – Area 1.dwg Tue, 21 Jan 2014 – 7:11am roger.ripster

## Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Pile Repair Log/Photos




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/13/13 | TDD | RJR | RJR | SGS |
| 0 | 06/07/13 | TDD | TDD | TDD | SGS |

HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION BY APVD

THIS DRAWING IS THE PROPERTY OF AMEC+ INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN THE SPECIFICALLY PERMITTED IN WRITING BY AMEC+.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS:
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design\SA6-CSD\CAD SA6\N 100 Percent\CR16-SN-203 HBW Design Plan Profile.dgn PLOT DATE: Fri 18 Oct 2013 PLOT TIME: 10:31 AM

MATCH LINE SHEET S-202

HYDRAULIC BARRIER AND CEMENT BENTONITE WALL CONNECTION (B) S-201 C-301

EXISTING SOIL CEMENT BENTONITE WALL

UTILITY CORRIDOR

SEE NOTE HB21 ON SHEET G-003

NEW JERSEY STATE HIGHWAY ROUTE 440

HYDRAULIC BARRIER

Leak 2 (1/13/14) STA 7+82.0

Leak 1 (1/13/14) STA 5+64.4

STA 14+51

FINAL REMEDY GRADE (TYP)

EXISTING GRADE (TYP)

LINER GRADE / TOP OF FINAL HYDRAULIC BARRIER (TYP) (SEE NOTE FP2 ON SHEET G-004)

EXCAVATION GRADE (TYP)

STRATUM D (TYP)

PRELIMINARY SHEET PILE TIP ELEVATION (TYP)

EXISTING GROUND ELEVATION (TYP)

BOTTOM OF EXCAVATION ELEVATION (TYP)

2/20/14 10/18/13 8/26/13 8/23/13 8/22/13 8/20/13 8/19/13 8/16/13 8/15/13 10/3/13 10/18/13

9.76 8.34 10.66 10.00 9.95 9.84 9.26 9.42 10.00 10.00

10/24/13 9/13/13 9/12/13 9/11/13 9/10/13 9/9/13 10/22/13 10/22/13

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET REF. |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 1+44 | -3' | A2.16-A2.17 |
| STRUCTURAL | 1+44 | 6+00 | -3' | A2.16-A2.17 |
| STRUCTURAL | 6+00 | 7+09 | -3' | A2.16-A2.17 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

Time Frame for:
→←1: Hydraulic Barrier Driven
→←1: Angles Grouted

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

STEPHEN H. MITCHELL 5/14/13
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03722400

| NO | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | TDD | RJR | TDD |

ISSUED FOR CONSTRUCTION
REVISION

| BY | APVD |
|---|---|
| TDD | S.H.M |

SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INC., AND SHALL NOT BE USED IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT WAS PREPARED. ANY REUSE, REPRODUCTION OF THE DRAWING, IN WHOLE OR IN PART, OR ANY MODIFICATION TO THE MATERIAL DEPICTED HEREON WITHOUT THE EXPRESS WRITTEN CONSENT OF AMEC, INC. IS PROHIBITED. ANY UNAUTHORIZED USE OF THE MATERIAL DEPICTED HEREON SHALL BE AT THE SOLE RISK OF THE PERSON OR ENTITY USING SUCH MATERIAL AND WITHOUT LIABILITY TO AMEC, INC.

Honeywell
101 COLUMBIA RD. P.O. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE


amec
Environment & Infrastructure, Inc.
200 Automation Mercer Blvd, Suite 113
Hamilton, NJ, 08619
(609) 588 - 2829
NJ Certificate of Authorization Number 24GA28011900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3460-12-0317 |
| DWG | S-201 |
| SHEET | 53 OF 66 |




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 5+00 | 12+00 | -22 | AZ 19-700 |
| STRUCTURAL | 12+80 | 17+80 | -30 | AZ 19-700 |
| STRUCTURAL | 17+80 | 18+00 | -5 | AZ 19-700 |




NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

Time Frame for:

→ ← : Hydraulic Barrier Driven

→ ← : Angles Grouted

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER # 24GE04032400

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | RJR | TDD | | TDD | SHM |

ISSUED FOR CONSTRUCTION
REVISION

Honeywell
101 COLUMBIA RD P.O. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS:
100 PERCENT DESIGN DRAWINGS

CIVIL


HYDRAULIC BARRIER
PLAN & PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 21SA26781600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-202 |
| SHEET | 54 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INC. LICENSING ALL PATENTED AND PATENTABLE FEATURES, AND NON-CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWINGS FOR ANY PURPOSE OTHER THAN SPECIFICALLY INTENDED BY AMEC.




BEFORE DRIVING SHEETS




SHEET SEALING DETAIL (BF)
NTS
TYP S-203

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |
| STRUCTURAL | 19+00 | 21+20 | -19 | AZ 19-700 |
| STRUCTURAL | 21+20 | 23+20 | -15 | AZ 19-700 |
| STRUCTURAL | 23+20 | 24+37 | -12 | AZ 19-700 |
| NON STRUCTURAL | 24+37 | 25+89 | -12 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04132400

| NO | DATE | DSGN | REVISION | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | DR | TDD | SHM |

ISSUED FOR CONSTRUCTION

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER PLAN & PROFILE

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 110
Hamilton, N.J. 08619
(609) 689 - 2829
Full Certification of Authorization Number 24GA28119500


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
IF NOT ONE INCH ADJUST SCALE ACCORDINGLY


DATE
PROJ 3480-12-0317
DWG S-203
SHEET 55 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INC. (OTHERWISE NOTED) AND IS NOT TO BE REPRODUCED, THE DRAWINGS IN WHOLE OR IN PART, NOR THE MATERIAL EMBODIED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY AUTHORIZED BY AMEC.

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.






NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 02-05-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 3PI-15
Date Exposed: 10/31/2013
Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13
Inspected by: M. Senna
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 3PI-17
Date Exposed: 10/31/13
Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13
Inspected by: M. Senna
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 3PI-18
Date Exposed: 10/31/13
Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13
Inspected by: M. Senna
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 3PI-19
Date Exposed: 10/31/13
Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13
Inspected by: M. Senna
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 3P1-20

Date Exposed: 10/31/13

Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 3P1-21

Date Exposed: 10/31/13

Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13

Inspected by: M. Senna

Describe Repair: clean grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 3P1-22

Date Exposed: 10/31/13

Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/4/13

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/4/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 5P1-9

Date Exposed: 11/20/13

Describe Damage: Spots of Base metal

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/25/13

Inspected by: M. Senna.

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/25/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-11

Date Exposed: 11/20/13

Describe Damage: Damaged by the bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/25/13

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/25/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-12

Date Exposed: 11/20/13

Describe Damage: Spots of bare metal

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/25/13

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/25/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-14

Date Exposed: 11/20/13

Describe Damage: Spots of bare metal

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/25/13

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/25/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-16

Date Exposed: 11/20/13

Describe Damage: Bare metal on center interlock

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/25/13

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/25/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-17

Date Exposed: 11/20/13

Describe Damage: Spots of bare metal along the corner of the sheetpile

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 11/25/13

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/25/13

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

# SA-6 South Hydraulic Barrier Epoxy Repair within the Excavation

## Damage to Epoxy Coating




AMEC Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
Tel 609-689-2829
Fax 609-689-2838
amec.com


11.04.2013 10:43


# Epoxy Repair Preparation




11.04.2013 11:46

# Finished Epoxy Repair




11.05.2013 09:34


11.05.2013 09:33


11.05.2013 09:33




11.04.2013 11:38

## Attachment 11:  Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 4, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 1 |
| Flood Protection | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Work Zone Barriers | X | | | |
| Storm Drain Protection | | X | | 3 |
| | | | | |
| SA-6 North and GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North and GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | X | | | |
| Storm Drain Protection | | | X | |
| | | | | |
| SA-7 and Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | X | | | |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE
**February 4, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence requires maintenance/repair two locations immediately north of the Kellogg Street jughandle on Rt.440 and immediately west of the Guard Shack on Kellogg Street. |
| 2 | IA2Q4A1AL8 | One storm water catch basin requires maintenance of sediment protection. It is located to the north of the Guard Shack, just to the east of the fire hydrant. |
| 3 | IA2Q4A1AL8 | The stone decon pad at the Eastern Exclusion Zone exit requires maintenance to remove sediment build-up. |
| 4 | | |
| 5 | | |
| 6 | | |
| 7 | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey
**SWPPP Observer:** (L. Pfeiffer) **Date:** 02/05/14

Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Windscreen to be repaired or replaced as needed. | 2/6/14 RAD |
| 2 | Filter fabric to be re-installed. | 2/6/14 RAD |
| 3 | Stone pad to be cleaned out to restore proper function. | 2/7/14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** **Date:** 02/10/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 12, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 2 |
| Flood Protection | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | X | | | |
| Storm Drain Protection | X | | | |
| | | | | |
| SA-6 North and GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North and GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | | X | | 3 |
| Storm Drain Protection | | | X | |
| | | | | |
| SA-7 and Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Perimeter Fencing/Windscreen | X | | | |
| Work Zone Barriers | X | | | |
| Storm Drain Protection | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE
## February 12, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA3Q4A1AL8 | A twenty foot section of the orange Exclusion Zone fencing on the southern side of the active excavation is sagging and requires maintenance. |
| 2 | IA3Q4A1AL8 | The haul road to the east of the new >1000 PPM staging area is muddy. It requires cleaning and pothole repair. |
| 3 | IA3Q4A1AL8 | The two gates on the SA-6 North/SA-7 fenceline must be closed at the end of each work day. |
| 4 | | |
| 5 | | |
| 6 | | |
| 7 | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWPPP Observer:** [signature] (George Pfeiffer) **Date:** 02/12/14

Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Truck haul road to the east of the new >1000 PPM stockpile area requires cleaning and maintenance. | 2-18-14 RAD |
| 2 | Exclusion Zone fencing to the south of the active excavation requries maintenance. | 2-18-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** [signature] **Date:** 02/18/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 19, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 2 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| | | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| | | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 7 |
| Storm Drain Protection | X | | | |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, February 19, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| | IA2Q4A1AL8 | In addition to the current signage, the Western Exclusion Zone on the former Old Dominion property requires orange fencing around the perimeter. This fencing should extend across the entrance/exit during periods of inactivity. |
| | IA2Q4A1AL8 | Kerosene drums are stored on the former Old Dominion property without required spill control measures. All drums are to be stored wit secondary containment or on-spill pallets. Sammy |
| 3 | IA2Q4A1AL8 | The haul road to the east of the Western Exclusion Zone on Study Area 6 South requires maintenance for potholes and muddy conditions. Thorne |
| | IA2Q4A1AL8 | The sediment basket in the storm water catch basin immediately to the north of the Guard Shack requires maintenance. |
| | IA2Q4A1AL8 | Markers on the crane mat bridge over the 72" force main on Study Area 6 North have been moved/buried by snow plowing/removal. These markers must be reinstalled to clearly delineate the edges of the bridge. ~~Brett~~ Ross / Justin |
| 6 | EEPSQUO2YB | Silt fence surrounding the clean material stockpiles on the western end of Study Area 7 requires maintenance. truck line-guys |
| | EEPSQUO2YB | Windscreen on the Study Area 7 perimeter fence is sagging at various locations and requires maintenance. truck line-guys |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 02/19/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Fencing will be installed after the snow melts in this area. No way to stage fence right now. | |
| 2 | Kerosene drums in use are now on secondary containment in this area. Completed | 2-20-14 RAD |
| 3 | Stone dumped in area. will be complete once operator is available | |
| 4 | Completed | 2-20-14 RAD |
| 5 | Completed. Staged barricades w/ water inside along bridge exterior | 2-20-14 RAD |
| 6 | Silt fence will be installed after snow has melted & ground not frozen | |
| 7 | Completed | 2-21-14 RAD |
| | | |

**Construction Manager:** _____ **Date:** 02/25/14

Completed 02/28/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 26, 2014

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| | | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| | | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 2/26/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Wednesday, February 26, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Repair Exclusion Zone Fencing along the eastern edge of the 60 Kellogg slab and along the HBW between Cells 9 and 17 |
| 2 | IA2Q4A1AL8 | The haul road to the east of the western Exclusion zone on Study Area 6 south requires maintenacne for potholes |
| 3 | IA2Q4A1AL8 | The sediment basket in the storm water catch basin locted on the NE corner of the modutanks requires maintennce |
| 4 | IA2Q4A1AL8 | Repair silt fence north of the Construction Water Treatment Plant |
| 5 | EEPSQUO2YB | Silt fence surrounding the clean material stockpiles on the western portion of SA7 requires repair. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** Signature **Date:** 2/26/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Completed | 2-27-14 |
| 2 | Completed | 2-28-14 |
| 3 | Completed | 2-27-14 |
| 4&5 | impossible to do until ground thaws | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** **Date:** 2-28-14

## Attachment 12: 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (January 2014)

(Not provided in this submittal – this information was previously provided in Progress Report 2014-01)

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 2 OF 25**

- **2014 Monthly Reports Part 2**

**4/16/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 16, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-03**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from March 1 – March 31, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: March 2014 SA-6/7 Combined Monthly Progress Report No. 2014-03

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-03

**Project SA-6 & 7 Remediation**

## March 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/04/14 | Two-Year Summary Report for In-Situ Chromium Mass Removal from S-3 Sand<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/12/14 | Response to Comments Provided by Plaintiffs re. Combined Monthly Progress/Highlights Report<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/12/14 | Design Change Bulletin – Surcharge Monitoring Plan<br>Study Area 6, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/13/14 | Combined Monthly Progress/Highlights Report No. 2014-02<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/18/14 | Response to Comments Provided by Dr. Ben Ross January 27, 2014, Revised Integrated Groundwater Sampling and Analysis Plan<br>Study Areas 5, 6, and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/18/14 | Discharge of Tannin Construction Water<br>Customer ID# 31630005-1<br>Study Area 7, Jersey City, NJ | Andy Caltagirone<br>PVSC |
| 03/18/14 | Bayfront Redevelopment at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016 | Andy Caltagirone<br>PVSC |
| 03/18/14 | NJPDES Permit NJ0156311: February 2014 Surface Water Discharge Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | NJDEP<br>Office of Permit Management<br>Division of Water Quality |
| 03/18/14 | Response to Comments Provided by Dr. Ben Ross February 12, 2014 re. Recommendation Regarding Bedrock Monitoring Wells on Kearny Point and NJCU<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/25/14 | Special Master All Hands Conference Call | N/A |
| 03/25/14 | Design Change Bulletin – Trench Layout for Contingent Groundwater Extraction System<br>Study Area 6, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/26/14 | Study Area 5 Shallow Groundwater<br>Arnold & Porter RTC re Plaintiffs' 1/2/14 Correspondence re. Long-Term Monitoring and Controls | Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/31/14 | Table D to the 3/18/14 Revised Integrated Groundwater Sampling and Analysis Plan Study Areas 5, 6, and 7 Jersey City, New Jersey | Honorable Robert G. Torricelli Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 03/09/2014 | 03/16/2014 | 03/23/2014 | 03/30/2014 |
| **Construction Management (AMEC)** | 10 | 10 | 10 | 10 |
| **Engineering (AMEC)** | 2 | 2 | 2 | 2 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 38 | 36 | 39 | 43 |
| **Arecon/US Ecology Subcontractors** | 4 | 5 | 5 | 5 |
| **OSC (-80 Kellogg Demolition** | 0 | 2 | 5 | 8 |
| **ENR (SA-6N GWTP Utilities)** | 5 | 5 | 0 | 0 |
| **BCA (SA-6N Building Construction)** | 0 | 0 | 0 | 0 |
| **Siemens** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **HPS (SA-6N GWTP Process Controls)** | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 0 | 0 |
| **TOTAL** | **64** | **65** | **66** | **73** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Conducted quarterly LTMP groundwater level measurement round.
- Conducted S-3 Injection/Mass Removal Event No.12 in well 088-IW-01.
- Completed new Ground Water Treatment Plant (GWTP) commissioning activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Completed abandonment of former 54" Sedimentation Basin outfall pipe on SA-6N.
- Continued well abandonment activities in accordance with approved Monitoring Well Abandonment Plan.
- Began 80 Kellogg St GWTP demolition activities.

- Completed decommissioning activities associated with the 80 Kellogg GWTP to include exterior ModuTanks, sludge tanks, microfilters and miscellaneous equipment.
- Completed all scheduled crane lifts for 80 Kellogg salvage equipment removals, two (2) sludge tanks, one (1) filter press and one (1) generator.
- Collected March PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Non-chromium activities, ARCADIS continues to work with NJDEP on the modification to the existing NJDEP-Discharge to Groundwater Permit by Rule for additional Enhanced Anaerobic in-situ bioremediation (EAISB) injections planned for JCMUA and JCDPW UST Areas.

## C. SA-6 N GROUND WATER TREATMENT PLANT

- Completed permanent connection of PW-2 to the GWTP.
- Complete permanent connection of PW-1 to the GWTP.
- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer tank using the original Siemens' formula (300 cc powder per 100 gallon drum batch).

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 03/09/2014 | 03/16/2014 | 03/23/2014 | 03/30/2014 |
| Avg. Gallons Treated & Discharged (per day) | 71,112 | 53,872 | 77,063 | 79,192 |
| Average Flow (gpm) for Operating Period | 49 | 43 | 54 | 55 |
| Avg. Hours of Plant Operation | 24 | 18 | 24 | 24 |
| GWTP ModuTanks (gal.) | 4,680 | 4,668 | 4,800 | 6,240 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in Cells 43 through 56.
- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 21.3 | 21.3 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 110 | 21.69 | 2,386.93 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | 240-1000 mg/kg soils | 15 | 21.65 | 324.89 |
| **Entact/ Venerio** | Tri-axle Dump | Middlesex City Landfill | NA | Petroleum Impacted Soils (non–haz) | 42 | 24.53 | 1030.44 |
| **Entact/ Montecalvo** | Tri-axle Dump | Bayshore Recycling | NA | Petroleum Impacted Soils (non-haz) | 65 | 25.67 | 1669.12 |
| **Entact/ Montecalvo** | 30 cubic Yard Roll off | Bayshore Recycling | NA | Creosote Debris (non-haz) | 1 | 8.1 | 8.1 |
| **Entact/Tilcon** | Tri-axle Dump | Tilcon, Mt. Hope | NA | Asphalt | 28 | 22.91 | 641.49 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 55,56 |
| **Excavation Completed** | Cell Number(s) 42 through 52<br>Volume Excavated - Total for Reporting Period: 10,712 CY/ Total to Date:41,592 CY |
| **Backfill in Progress** | Cell Number(s) 1 through 43 |

### 3. BACKFILL MATERIALS USED

| Source | (Week Ending) | | | |
|---|---|---|---|---|
| | 03/09/2014 | 03/16/2014 | 03/23/2014 | 03/30/2014 |
| <20ppm re-use, CY | 0 | 0 | 0 | 0 |
| Weldon, Import-Tons | 0 | 863.90 | 1,628.19 | 3,145.29 |
| Tilcon, Import-Tons | 518.04 | 3,973.37 | 2,801.16 | 908.06 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Instrumentation Installation ~60% complete. Access limitations due to ice and demolition materials. No Surcharge Initiated.
- Area 2S: Instrumentation Installation ~75% complete. Completion of instrument installation deferred pending completion of demolition activities. No Surcharge Initiated.
- Area 3S: Instrumentation Installation 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. No Surcharge initiated.
- Area 1N: Instrumentation Installation ~100% complete. No Surcharge initiated.

- Area 2N: No instrumentation installed. Settlement platforms have been installed in the sedimentation basin to the north of Area 2 and portion of the Sedimentation Basin has been temporarily filled with screened materials that will be used for surcharging the designated Surcharge Areas.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Hydraulic Barrier installation was completed adjacent to the 72-inch force main. Vibration Monitoring indicated maximum accelerations continue to be within allowable range (0.2 in/sec observed, while the allowable acceleration is 1.0 in/sec).
- Acoustical Monitoring. PVSC/Hatch Mott MacDonald (HMM) report that there was no wire breaks recorded during the current reporting period.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/15 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/12 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP | SA-6 Chromium Remedy | Obtained 3/26/2014 | Renewal Not Needed | 8/31/2018 | - |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/15 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/14 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/12 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/13 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Initiate placement of surcharge materials in SA-6N Area 1N.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 56 through 60 and Cells 156 to 132.

- Continue stockpiling potential >1,000 mg/kg soils for sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Initiate construction of SA-6S Contingent Groundwater Trench System.
- Continue demolition activities associated with 80 Kellogg.
- Continue SWPPP inspections.
- Complete PVSC compliance sampling.


**ATTACHMENTS:**

1: Schedule – 6 Month Look Ahead
2: Site Photographs
3: Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/Sidewall Confirmatory Points
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
4: Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-1)
   - SA-6 South Deep Well Data (DW-2)
5: SA-6 Construction Water Discharge Data (To PVSC)
6: Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7: Perimeter Pools Update
8: Groundwater Quality Data in GWET Wells *(provided on a quarterly basis - not available as of this report date)*
9: Surcharge Monitoring Update
   - Instrumentation Location Plan 1N
   - Instrumentation Installation Data
10: Sheet Pile Update
   - Hydraulic Barrier Wall Plan & Profile
   - Sheet Deflection Along Open Excavation
   - Sheet Pile Repair Log
11: Weekly SWPPP Reports
12: 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (February 2014)

## Attachment 1:  Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Tue 4/1/14

Task  Milestone  Summary  Critical

## Attachment 2:  Site Photographs




**Site Photograph 1:** Former timber piles removed as part of excavation.




**Site Photograph 2:** Standing water removed prior to backfilling.




**Site Photograph 3:** Excavation reaches the 60 Kellogg warehouse foundation.




**Site Photograph 4:** Installation of stormwater control measures on Kellogg St Properties.




**Site Photograph 5:** Contractor crushes concrete debris at JC Properties.




**Site Photograph 6:** 80 Kellogg St WWTP tank cleanout prior to demo.




**Site Photograph 7:** Salvage of tanks for reuse at other facilities.





**Site Photograph 8:** Sheetpile installation along Sewer Line at JC Properties.

## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/Sidewall Confirmatory Points)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of April 1, 2014

March 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill




## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**

- Planned
- Complete

**Excavation**


- Planned
- Complete

**Soil Compaction**

- In Progress
- Complete

**Open Space Containment**

- In Progress
- Complete




LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM O EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 03-14-14 TO 03-20-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7* | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684138.4 | 603182.8 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5* | Stratum D Reached |
| 684146.2 | 603165.7 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6* | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1.0 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2.0 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684221.8 | 603013.0 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7* | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684272.8 | 602944.8 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9* | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684293.5 | 602922.8 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9* | Stratum D Reached |
| 684227.9 | 602869.9 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1* | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4* | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684273.8 | 602864.2 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3* | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684285.9 | 602856.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4* | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684305.4 | 602833.3 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1* | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684392.6 | 602878.7 | -2.8 | 124-SB-123 | 30 | 1/23/2014 | -2.4 | Stratum D Reached |
| 684311.9 | 602821.5 | 3.5 | 124-SB-021R | 30 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684381.0 | 602861.0 | -2.3 | 124-SB-110 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684362.9 | 602837.4 | 3.2 | 124-SB-124 | 31 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684340.0 | 602818.0 | 3.2 | 124-SB-109 | 31 | 1/23/2014 | -1.6 | Stratum D Reached |
| 684318.6 | 602806.8 | 3.5 | 124-SB-021R | 31 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684416.9 | 602861.1 | -2.8 | 124-SB-029 | 32 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684335.2 | 602800.6 | 3.5 | 124-SB-021R | 32 | 1/30/2014 | 2.0* | Target Elevation Reached |
| 684411.9 | 602839.0 | -2.2 | 124-SB-092 | 33 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684348.7 | 602791.2 | 3.5 | 124-SB-021R | 33 | 1/30/2014 | 2.0* | Target Elevation Reached |
| 684372.0 | 602797.0 | 2.6 | 124-PT-14 | 34 | 2/4/2014 | -1.9 | Stratum D Reached |
| 684355.8 | 602781.0 | 3.5 | 124-SB-021R | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684458.4 | 602838.3 | -2.3 | 124-SB-027 | 35 | 2/4/2014 | -2.7 | Stratum D Reached |
| 684367.5 | 602768.5 | 3.5 | 124-SB-021R | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684440.8 | 602806.0 | -2.8 | 124-SB-091 | 36 | 2/11/2014 | -2.7 | Stratum D Reached |
| 684371.2 | 602753.4 | 3.5 | 124-SB-021R | 36 | 2/11/2014 | 2.1* | Target Elevation Reached |
| 684394.0 | 602777.3 | 4.7 | 124-SB-117A | 36 | 2/11/2014 | -1.6 | Stratum D Reached |
| 684473.9 | 602819.4 | -2.8 | 124-SB-026 | 37 | 2/11/2014 | -2.9 | Stratum D Reached |
| 684430.7 | 602784.0 | -1.3 | 124-SB-023 | 37 | 2/11/2014 | -3.6 | Stratum D Reached |
| 684412.9 | 602766.1 | 2.0 | 124-SB-121A | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684400.0 | 602762.0 | -0.1 | 124-PT-04 | 37 | 2/11/2014 | -2.2 | Stratum D Reached |
| 684380.7 | 602742.6 | 3.5 | 124-SB-021R | 37 | 2/11/2014 | 2.1* | Target Elevation Reached |
| 684463.2 | 602783.7 | -2.3 | 124-SB-136 | 38 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684397.4 | 602736.2 | 3.5 | 124-SB-021R | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684448.4 | 602763.0 | 4.7 | 124-SB-022 | 39 | 2/20/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684505.3 | 602786.0 | -2.8 | 124-SB-024 | 40 | 2/27/2014 | -3.4 | Stratum D Reached |
| 684482.9 | 602770.8 | -3.3 | 124-SB-025 | 40 | 2/27/2014 | -3.0 | Stratum D Reached |
| 684430.0 | 602730.0 | 1.7 | 124-PT-03 | 40 | 2/27/2014 | 0.0 | Target Elevation Reached |
| 684468.5 | 602745.2 | 1.8 | 124-SB-066 | 40 | 2/27/2014 | -2.2 | Stratum D Reached |
| 684491.3 | 602754.6 | -2.3 | 124-SB-136R | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | 125-SB-029R | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684524.5 | 602765.0 | -3.5 | 125-SB-017 | 42 | 3/5/2014 | -3.1 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | 125-SB-029R | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684513.0 | 602736.0 | -4.3 | 125-PT-22 | 43 | 3/5/2014 | -3.5 | Stratum D Reached |
| 684496.0 | 602718.9 | -1.7 | 125-SB-086 | 43 | 3/5/2014 | -2.6 | Stratum D Reached |
| 684473.0 | 602698.0 | 0.3 | 125-PT-21 | 43 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684446.6 | 602677.9 | 0.5 | 125-SB-028 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684543.1 | 602743.1 | -3.9 | 125-SB-018 | 44 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684431.0 | 602654.0 | 0.7 | 125-PT-20 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684467.4 | 602652.6 | 1.0 | 125-SB-027 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684495.1 | 602674.9 | 0.4 | 125-SB-025 | 45 | 3/11/2014 | 0.3 | Target Elevation Reached |
| 684512.8 | 602689.3 | 0.3 | 125-SB-024 | 45 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684561.9 | 602720.2 | -3.3 | 125-SB-019 | 46 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684543.0 | 602699.0 | -4.7 | 125-PT-17 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684539.5 | 602702.1 | -3.7 | 125-SB-022 | 46 | 3/17/2014 | -3.3 | Stratum D Reached |
| 684503.0 | 602661.0 | 1.0 | 125-PT-16 | 46 | 3/17/2014 | -2.9 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | 125-SB-029R | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.3 | 124-SB-136R | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684481.2 | 602625.7 | 1.7 | 125-SB-089 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684488.7 | 602626.5 | 1.3 | 125-SB-026 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684581.0 | 602697.1 | -3.4 | 125-SB-020 | 48 | 3/20/2014 | -2.9 | Stratum D Reached |
| 684558.6 | 602678.9 | -4.0 | 125-SB-021 | 48 | 3/20/2014 | -3.4 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | 125-SB-029R | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |
| 684373.5 | 602871.7 | -2.5 | C-30 | 30 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684311.9 | 602821.5 | 2.1 | C-30-1 | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684384.9 | 602861.2 | -2.5 | C-31 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684318.6 | 602806.8 | 2.1 | C-31-1 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684383.8 | 602841.5 | -2.5 | C-32 | 32 | 1/30/2014 | -1.8 | Stratum D Reached |
| 684335.2 | 602800.6 | 2.1 | C-32-1 | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684393.5 | 602830.6 | -2.5 | C-33 | 33 | 1/30/2014 | -1.9 | Stratum D Reached |
| 684348.7 | 602791.2 | 2.1 | C-33-1 | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684412.7 | 602824.5 | -2.5 | C-34 | 34 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684355.8 | 602781.0 | 2.1 | C-34-1 | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684422.4 | 602815.2 | -2.5 | C-35 | 35 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684367.5 | 602768.5 | 2.1 | C-35-1 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684432.1 | 602801.8 | -2.5 | C-36 | 36 | 2/11/2014 | -2.4 | Stratum D Reached |
| 684371.2 | 602753.4 | 2.1 | C-36-1 | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684440.7 | 602791.6 | -2.5 | C-37 | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684380.7 | 602742.6 | 2.1 | C-37-1 | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684460.4 | 602787.7 | -2.5 | C-38 | 38 | 2/20/2014 | -2.8 | Stratum D Reached |
| 684397.4 | 602736.2 | 2.1 | C-38-1 | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684471.9 | 602777.2 | -2.5 | C-39 | 39 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684416.4 | 602732.1 | 2.1 | C-39-1 | 39 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684481.8 | 602765.6 | -2.5 | C-40 | 40 | 2/27/2014 | -3.1 | Stratum D Reached |
| 684427.0 | 602721.5 | 0.4 | C-40-1 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684491.3 | 602754.6 | -2.5 | C-41 | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | C-41-1 | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

Note: Data shown is for recent months activity

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684496.7 | 602740.4 | -2.5 | C-42 | 42 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | C-42-1 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684507.5 | 602729.5 | -2.5 | C-43 | 43 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684447.1 | 602679.0 | 0.4 | C-43-1 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684524.2 | 602722.2 | -2.5 | C-44 | 44 | 3/11/2014 | -3.5 | Stratum D Reached |
| 684454.3 | 602665.7 | 0.4 | C-44-1 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684536.0 | 602714.2 | -2.5 | C-45 | 45 | 3/11/2014 | -3.2 | Stratum D Reached |
| 684464.6 | 602655.3 | 0.4 | C-45-1 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684535.1 | 602693.1 | -2.5 | C-46 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | C-46-1 | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.5 | C-47 | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684483.8 | 602632.5 | 0.4 | C-47-1 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684551.5 | 602667.8 | -2.5 | C-48 | 48 | 3/20/2014 | -3.0 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | C-48-1 | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.


Note: Data shown is for recent months activity

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 4.9 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684301.0 | 602795.0 | 2.6 | 124-SB-108 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684328.2 | 602790.2 | 3.3 | 124-SB-063 | 32 | 1/30/2014 | 1.8 | Target Elevation Reached |
| 684338.1 | 602786.6 | 4.7 | 124-SB-056 | 33 | 1/30/2014 | 1.7 | Target Elevation Reached |
| 684348.0 | 602746.0 | 3.4 | 124-PT-02 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684386.0 | 602707.0 | 3.3 | 124-PT-01 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684411.1 | 602714.2 | 3.9 | 124-SB-065 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684408.4 | 602664.2 | 2.2 | 125-SB-088 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684419.7 | 602644.6 | 1.8 | 125-SB-067 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684457.0 | 602620.0 | 1.1 | 125-PT-15 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

Note: Data shown is for recent months activity





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.40 | 603182.30 | -0.5 | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.22 | 603184.16 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.77 | 603181.67 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.20 | 603182.66 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.62 | 603189.99 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.87 | 603186.67 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.06 | 603182.62 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.62 | 603186.80 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.19 | 603189.62 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.19 | 603189.62 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.07 | 603175.51 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.00 | 603184.30 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.80 | 603153.90 | -0.6 | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.75 | 603161.31 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.82 | 603162.33 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.71 | 603161.30 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.73 | 603162.11 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.93 | 603171.05 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.07 | 603155.35 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.46 | 603153.45 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.93 | 603174.92 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.90 | 603119.50 | -1.2 | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.06 | 603131.60 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.72 | 603111.63 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.45 | 603121.50 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.46 | 603126.88 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.07 | 603132.39 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.40 | 603128.53 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.12 | 603113.81 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.20 | 603121.80 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.70 | 603093.10 | -1.5 | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.04 | 603094.76 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.60 | 603104.72 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.51 | 603111.14 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.60 | 603115.00 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.80 | 603100.00 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.80 | 603078.40 | -1.8 | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.18 | 603057.89 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.86 | 603057.68 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.21 | 603070.22 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.60 | 603060.80 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.10 | 603053.50 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.60 | 603048.60 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.60 | 603060.40 | 7.5 | 122.5 | 4.9 | 128.9 | 21.1 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.80 | 603050.60 | -1.7 | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.90 | 603061.30 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.80 | 603062.80 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.03 | 603066.82 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.80 | 603071.30 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.90 | 603095.70 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.70 | 603033.30 | -0.8 | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.20 | 603014.90 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.80 | 603021.10 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.90 | 603018.80 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.90 | 603018.80 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.00 | 603021.00 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.80 | 603013.00 | -0.7 | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.90 | 603039.80 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.50 | 603043.20 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 16 | Weldon WC Screenings | | Sor |

Note: Data shown is for recent months activity

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 5 | BF-08-03 | 1/6/2014 | 684231.74 | 603038.78 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.30 | 603046.80 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.30 | 603066.00 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.50 | 602989.40 | -0.5 | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.70 | 602987.60 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.60 | 602980.40 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.20 | 602981.50 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.00 | 603014.00 | -0.5 | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.40 | 603018.20 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.50 | 603026.10 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.50 | 603026.10 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.80 | 603014.40 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.90 | 603017.50 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.50 | 602989.40 | -1.0 | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.60 | 602952.70 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.40 | 602953.80 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.60 | 602949.00 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.70 | 602988.60 | -1.7 | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.70 | 602995.20 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.50 | 602989.80 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.50 | 602989.80 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.30 | 602995.40 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.70 | 602919.60 | -0.9 | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.60 | 602919.10 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.50 | 602922.00 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-13-02 | 3/12/2014 | 684238.40 | 602918.20 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 22 | Tilcon MH DGA | | Vertical 5 |
| 5 | BF-13-03 | 3/19/2014 | 684235.10 | 602916.00 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | Vertical 5 |
| 1 | BF-14 | | 684312.10 | 602956.00 | -0.9 | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.70 | 602965.20 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.60 | 602935.70 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-14-02 | 3/14/2014 | 684301.90 | 602952.70 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 23 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-15 | | 684260.70 | 602896.70 | -0.9 | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.00 | 602897.10 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.50 | 602902.20 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-15-02 | 3/12/2014 | 684260.50 | 602900.20 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 24 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-16 | | 684326.70 | 602937.00 | -1.1 | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.90 | 602942.70 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.00 | 602937.20 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-16-02 | 3/14/2014 | 684326.70 | 602930.00 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 25 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-17 | | 684283.70 | 602879.00 | 0.4 | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.60 | 602882.10 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-17-02 | 3/14/2014 | 684273.70 | 602879.10 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 26 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-18 | | 684350.80 | 602909.60 | -1.5 | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.50 | 602885.60 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-18-02 | 3/14/2014 | 684344.00 | 602911.50 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 27 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-19 | | 684313.20 | 602860.40 | 0.3 | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.10 | 602872.70 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-19-02 | 3/17/2014 | 684301.40 | 602851.50 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 28 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-20 | | 684370.90 | 602887.40 | -1.7 | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.50 | 602862.10 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 1 | BF-21 | | 684330.40 | 602835.90 | 1.9 | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.30 | 602842.20 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | Vertical 5 |
| 3 | BF-21-02 | 3/17/2014 | 684307.40 | 602827.30 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | Vertical 5 |

Note: Data shown is for recent months activity

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | BF-21-03 | 3/19/2014 | 684314.60 | 602830.90 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | Vertical 5 |
| 5 | BF-21-04 | 3/20/2014 | 684314.40 | 602815.10 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | Vertical 5 |
| 6 | BF-21-05 | 3/20/2014 | 684321.10 | 602814.10 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | Vertical 5 |
| 7 | BF-21-06 | 3/20/2014 | 684308.30 | 602802.20 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | Vertical 5 |
| 8 | BF-21-07 | 3/20/2014 | 684305.80 | 602806.30 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | Vertical 5 |
| 9 | BF-21-08 | 3/20/2014 | 684314.40 | 602804.80 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | Vertical 5 |
| 10 | BF-21-09 | 3/20/2014 | 684310.50 | 602806.60 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | Vertical 5 |
| 1 | BF-22 | | 684391.20 | 602864.30 | -2.3 | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.30 | 602845.00 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 1 | BF-23 | | 684350.90 | 602814.50 | -1.6 | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.90 | 602818.80 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-23-02 | 3/17/2014 | 684339.80 | 602809.60 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 32 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-24 | | 684411.00 | 602842.40 | -1.8 | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.40 | 602827.40 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 1 | BF-25 | | 684369.50 | 602729.20 | -1.8 | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.50 | 602796.30 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-25-02 | 3/17/2014 | 684354.80 | 602790.50 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 34 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-26 | | 684433.40 | 602818.80 | -2.1 | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.90 | 602828.30 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | Vertical 5 |
| 4 | BF-26-02 | 3/18/2014 | 684431.70 | 602817.70 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 35 | Tilcon MH DGA | | Vertical 5 |
| 1 | BF-27 | | 684389.40 | 602765.00 | -1.8 | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.20 | 602773.80 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 36 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-28 | | 684457.00 | 602790.80 | -2.8 | | | | | | 38 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-28-01 | 3/12/2014 | 684461.20 | 602789.30 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 38 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-29 | | 684418.80 | 602735.20 | 2.1 | | | | | | 39 | Stratum O | Bottom of excavation elevation - Stratum O | |
| 1 | BF-29-01 | 3/26/2014 | 684404.60 | 602731.30 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 39 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-30 | | 684476.80 | 602765.10 | -3.1 | | | | | | 40 | Stratum D | Bottom of excavation elevation | |
| 2 | BF-30-01 | 3/12/2014 | 684478.90 | 602766.20 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 40 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-31 | | 684436.00 | 602712.80 | 0.1 | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.70 | 602739.50 | -2.2 | | | | | | 42 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-32-01 | 3/12/2014 | 684496.60 | 602743.00 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 42 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-33 | | 684453.00 | 602683.20 | 0.1 | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.50 | 602716.80 | -2.5 | | | | | | 44 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-34-01 | 3/12/2014 | 684515.60 | 602715.40 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 44 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-35 | | 684471.30 | 602661.20 | 0.2 | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.20 | 602694.60 | -3.0 | | | | | | 46 | Stratum D | Bottom of excavartion elevation | |
| 1 | BF-36-01 | 3/18/2014 | 684535.10 | 602700.70 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 46 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-37 | | 684490.00 | 602636.80 | 0.2 | | | | | | 47 | Stratum O | | |
| 0 | BF-38 | | 684558.40 | 602671.70 | -3.0 | | | | | | 48 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-38-01 | 3/21/2014 | 684551.40 | 602683.60 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 48 | Tilcon MH DGA | | Vertical 5 |
| 0 | BF-39 | | 684510.60 | 602614.80 | 0.4 | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.40 | 602644.90 | -3.6 | | | | | | 50 | Stratum D | Bottom of excavation elevation | |
| | BF-40-01 | 3/26/2014 | 684572.20 | 602653.50 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 50 | Tilcon MH DGA | | Vertical 5 |
| | BF-41 | | | | | | | | | | 51 | Crushed concrete | | |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.
Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID BF-01-01 where:
BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again

Note: Data shown is for recent months activity

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | RF-01 | | 684158.60 | 603152.40 | | | | | | | 6 | | | |
| | RF-02 | | 684190.60 | 603063.90 | | | | | | | 12 | | | |
| | RF-03 | | 684270.20 | 603012.00 | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.90 | 603017.50 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.20 | 602919.80 | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.00 | 602916.60 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.50 | 602908.50 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.80 | 602904.90 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.80 | 602926.90 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.80 | 602926.90 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-05 | | 684328.50 | 602935.00 | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.10 | 602947.50 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.12 | 602942.00 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.40 | 602937.80 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.00 | 602933.40 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684334.97 | 602869.13 | | | | | | | 25 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.70 | 602908.80 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.80 | 602904.90 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.90 | 602890.50 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 29 | Weldon WC Screenings | | V5N |
| | RF-07 | | 684392.90 | 602838.10 | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.20 | 602890.40 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.60 | 602854.90 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.90 | 602771.10 | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.70 | 602797.10 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again

Note: Data shown is for recent months activity

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-1)
- SA-6 South Deep Well Data (DW-2)

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 02/03/14 | 1 | 72 | 6,7,EPS | 51 | 268,122 | 292,592 | 24,470 | 1,097,387 | 5.7 | |
| 02/04/14 | 1 | 24 | 6,7,EPS | 51 | 292,592 | 299,040 | 6,448 | 1,103,835 | 4.5 | |
| 02/05/14 | 1 | 24 | 6,7,EPS | 51 | 299,040 | 309,154 | 10,114 | 1,113,949 | 7.0 | |
| 02/06/14 | 1 | 24 | 6,7,EPS | 51 | 309,154 | 318,585 | 9,431 | 1,123,380 | 6.5 | |
| 02/07/14 | 1 | 24 | 6,7,EPS | 51 | 318,585 | 328,074 | 9,489 | 1,132,869 | 6.6 | |
| 02/10/14 | 1 | 72 | 6,7,EPS | 51 | 328,074 | 344,536 | 16,462 | 1,149,331 | 3.8 | |
| 02/11/14 | 1 | 24 | 6,7,EPS | 51 | 344,536 | 347,331 | 2,795 | 1,152,126 | 1.9 | |
| 02/12/14 | 1 | 24 | 6,7,EPS | 47 | 347,331 | 349,076 | 1,745 | 1,153,871 | 1.2 | System Temporarily Disable for Relocation |
| 02/18/14 | 1 | 144 | 6,7,EPS | 47 | 349,076 | 349,084 | 8 | 1,153,879 | 0.0 | Pump maintenance and Freezing Delays |
| 02/19/14 | 1 | 24 | 6,7,EPS | 47 | 349,084 | 351,236 | 2,152 | 1,156,031 | 1.5 | |
| 02/20/14 | 1 | 24 | 6,7,EPS | 47 | 351,236 | 358,591 | 7,355 | 1,163,386 | 5.1 | |
| 02/21/14 | 1 | 24 | 6,7,8,EPS | 65 | 358,591 | 369,538 | 10,947 | 1,174,333 | 7.6 | |
| 02/24/14 | 1 | 72 | 7,8,EPS | 59 | 369,538 | 385,722 | 16,184 | 1,190,517 | 3.7 | |
| 02/25/14 | 1 | 24 | 7,8,EPS | 59 | 385,722 | 389,100 | 3,378 | 1,193,895 | 2.3 | |
| 02/26/14 | 1 | 24 | 7,8,EPS | 59 | 389,100 | 392,185 | 3,085 | 1,196,980 | 2.1 | |
| 02/27/14 | 1 | 24 | 7,8,EPS | 59 | 392,185 | 394,083 | 1,898 | 1,198,878 | 1.3 | |
| 02/28/14 | 1 | 24 | 7,8,EPS | 59 | 394,083 | 394,858 | 775 | 1,199,653 | 0.5 | |
| 03/03/14 | 1 | 72 | 7,8,9,EPS | 66 | N/A | N/A | 12,100 | 1,211,753 | 2.8 | Flowmeter Frozen (Read by Gauging Tank) |
| 03/04/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 4,600 | 1,216,353 | 3.2 | |
| 03/05/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 3,900 | 1,220,253 | 2.7 | |
| 03/06/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 3,700 | 1,223,953 | 2.6 | |
| 03/07/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 2,500 | 1,226,453 | 1.7 | |
| 03/10/14 | 1 | 72 | 7,8,9,EPS | 66 | N/A | N/A | 1,700 | 1,228,153 | 0.4 | |
| 03/11/14 | 1 | 24 | 7,8,9,EPS | 66 | 394858 | 394,948 | 90 | 1,228,243 | 0.1 | |
| 03/12/14 | 1 | 24 | 7,8,9,EPS | 66 | 394948 | 395,094 | 146 | 1,228,389 | 0.1 | Flowmeter Blockage Cleared and Reset |
| 03/14/14 | 1 | 24 | 7,8,9,EPS | 67 | 0 | 8,194 | 8,194 | 1,236,583 | 5.7 | |
| 03/17/14 | 1 | 72 | 8,9,EPS | 56 | 8,194 | 32,805 | 24,611 | 1,261,194 | 5.7 | |
| 03/18/14 | 1 | 24 | 8,9,EPS | 52 | 32,805 | 41,005 | 8,200 | 1,269,394 | 5.7 | |
| 03/19/14 | 1 | 24 | 8,9,EPS | 52 | 41,005 | 53,281 | 12,276 | 1,281,670 | 8.5 | |
| 03/20/14 | 1 | 24 | 8,9,EPS | 52 | 53,281 | 68,164 | 14,883 | 1,296,553 | 10.3 | |
| 03/21/14 | 1 | 24 | 8,9,EPS | 44 | 68,164 | 82,672 | 14,508 | 1,311,061 | 10.1 | |
| 03/24/14 | 1 | 72 | 9,EPS | 44 | 82,672 | 112,690 | 30,018 | 1,341,079 | 6.9 | |
| 03/25/14 | 1 | 24 | 9,EPS | 14 | 112,690 | 136,290 | 23,600 | 1,364,679 | 16.4 | |
| 03/26/14 | 1 | 24 | 9,EPS | 14 | 136,290 | 159,720 | 23,430 | 1,388,109 | 16.3 | |
| 03/27/14 | 1 | 24 | 9,EPS | 14 | 159,720 | 173,928 | 14,208 | 1,402,317 | 9.9 | |
| 03/28/14 | 1 | 24 | 9,EPS | 14 | 173,928 | 188,251 | 14,323 | 1,416,640 | 9.9 | |
| 03/31/14 | 1 | 72 | 9,EPS | 14 | 188,251 | 234,816 | 46,565 | 1,463,205 | 10.8 | |
| 04/01/14 | 1 | 24 | 9,EPS | 14 | 234,816 | 254,072 | 19,256 | 1,482,461 | 13.4 | |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013

Note: Data shown is for recent months activity

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-1)**

| DATE | HOURS OF OPERATION | DEEP WELL FLOW METER START (Gal) | DEEP WELL FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 01/02/14 | 48 | 678,171 | 697,609 | 19,438 | 681,074 | 6.7 | |
| 01/06/14 | 96 | 697,609 | 733,339 | 35,730 | 716,804 | 6.2 | Well Taken Offline |
| 03/11/14 | 24 | 0 | 13,985 | 13,985 | 730,789 | 9.7 | Well Online |
| 03/12/14 | 24 | 13,985 | 28,186 | 14,201 | 744,990 | 9.9 | |
| 03/13/14 | 24 | 28,186 | 29,780 | 1,594 | 746,584 | 1.1 | |
| 03/14/14 | 24 | 29,780 | 31,460 | 1,680 | 748,264 | 1.2 | |
| 03/17/14 | 72 | 31,460 | 36,200 | 4,740 | 753,004 | 1.1 | |
| 03/18/14 | 24 | 36,200 | 37,460 | 1,260 | 754,264 | 0.9 | |
| 03/19/14 | 24 | 37,460 | 46,700 | 9,240 | 763,504 | 6.4 | |
| 03/20/14 | 24 | 46,700 | 55,760 | 9,060 | 772,564 | 6.3 | |
| 03/21/14 | 24 | 55,760 | 63,390 | 7,630 | 780,194 | 5.3 | |
| 03/24/14 | 72 | 63,390 | 96,110 | 32,720 | 812,914 | 7.6 | |
| 03/25/14 | 24 | 96,110 | 107,450 | 11,340 | 824,254 | 7.9 | |
| 03/26/14 | 24 | 107,450 | 116,401 | 8,951 | 833,205 | 6.2 | Well Taken Offline |

Note: Data shown is for recent months activity

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-2)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 02/03/14 | 72 | 782,573 | 827,501 | 44,928 | 897,390 | 10.4 | |
| 02/04/14 | 24 | 827,501 | 838,572 | 11,071 | 908,461 | 7.7 | |
| 02/05/14 | 24 | 838,572 | 853,159 | 14,587 | 923,048 | 10.1 | |
| 02/06/14 | 24 | 853,159 | 866,882 | 13,723 | 936,771 | 9.5 | |
| 02/07/14 | 24 | 866,882 | 881,016 | 14,134 | 950,905 | 9.8 | |
| 02/10/14 | 72 | 881,016 | 923,079 | 42,063 | 992,968 | 9.7 | |
| 02/11/14 | 24 | 923,079 | 936,961 | 13,882 | 1,006,850 | 9.6 | |
| 02/12/14 | 24 | 936,961 | 950,902 | 13,941 | 1,020,791 | 9.7 | |
| 02/13/14 | 24 | 950,902 | 976,618 | 25,716 | 1,046,507 | 17.9 | |
| 02/14/14 | 24 | 976,618 | 990,724 | 14,106 | 1,060,613 | 9.8 | |
| 02/18/14 | 86 | 990,724 | 1,051,980 | 61,256 | 1,121,869 | 11.9 | |
| 02/19/14 | 24 | 1,053,780 | 1,073,780 | 20,000 | 1,141,869 | 13.9 | |
| 02/20/14 | 24 | 1,073,780 | 1,083,940 | 10,160 | 1,152,029 | 7.1 | |
| 02/21/14 | 24 | 1,083,940 | 1,114,610 | 30,670 | 1,182,699 | 21.3 | |
| 02/24/14 | 72 | 1,114,610 | 1,163,430 | 48,820 | 1,231,519 | 11.3 | |
| 02/25/14 | 24 | 1,163,430 | 1,184,280 | 20,850 | 1,252,369 | 14.5 | |
| 02/26/14 | 24 | 0 | 4,180 | 4,180 | 1,256,549 | 2.9 | Flowmeter Reset |
| 02/27/14 | 24 | 4,180 | 9,643 | 5,463 | 1,262,012 | 3.8 | |
| 02/28/14 | 24 | 9,643 | 14,717 | 5,074 | 1,267,086 | 3.5 | |
| 03/03/14 | 72 | 14,717 | 43,855 | 29,138 | 1,296,224 | 6.7 | |
| 03/04/14 | 24 | 43,855 | 50,452 | 6,597 | 1,302,821 | 4.6 | |
| 03/05/14 | 24 | 50,452 | 61,014 | 10,562 | 1,313,383 | 7.3 | |
| 03/06/14 | 24 | 61,014 | 71,934 | 10,920 | 1,324,303 | 7.6 | Well Taken Offline for Excavation |
| 03/27/14 | 8 | 71,934 | 74,639 | 2,705 | 1,327,008 | 5.6 | Well Online |
| 03/28/14 | 24 | 74,639 | 85,721 | 11,082 | 1,338,090 | 7.7 | |
| 03/31/14 | 72 | 85,721 | 123,254 | 37,533 | 1,375,623 | 8.7 | |
| 04/01/14 | 24 | 0 | 17,708 | 17,708 | 1,393,331 | 12.3 | Flowmeter Reset |

Note: Data shown is for recent months activity

## Attachment 5:  Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER START (KGal) | DISCHARGE FLOW METER FINISH (KGal) | DISCHARGED VOLUME (Gal) DAILY | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 02/04/14 | 8.0 | 3,516.69 | 3,628.15 | 111,460 | 3,627,700 | PVSC Compliance Sample collected |
| 02/07/14 | 8.0 | 3,628.15 | 3,733.31 | 105,160 | 3,732,860 | |
| 02/11/14 | 8.0 | 3,733.31 | 3,854.45 | 121,140 | 3,854,000 | |
| 02/12/14 | 2.0 | 3,854.45 | 3,884.29 | 29,840 | 3,883,840 | |
| 02/14/14 | 6.0 | 3,884.29 | 3,933.69 | 49,400 | 3,933,240 | |
| 02/15/14 | 8.0 | 3,933.69 | 4,032.69 | 99,000 | 4,032,240 | |
| 02/18/14 | 8.0 | 4,032.69 | 4,123.91 | 91,220 | 4,123,460 | |
| 02/20/14 | 8.0 | 4,123.91 | 4,251.33 | 127,420 | 4,250,880 | |
| 02/21/14 | 8.0 | 4,251.33 | 4,412.37 | 161,040 | 4,411,920 | |
| 02/22/14 | 8.0 | 4,412.37 | 4,536.78 | 124,410 | 4,536,330 | |
| 02/24/14 | 8.0 | 4,536.78 | 4,660.60 | 123,820 | 4,660,150 | |
| 02/25/14 | 8.0 | 4,660.60 | 4,850.50 | 189,900 | 4,850,050 | |
| 02/26/14 | 8.0 | 4,850.50 | 4,970.69 | 120,190 | 4,970,240 | |
| 03/04/14 | 8.0 | 4,970.69 | 5,064.73 | 94,040 | 5,064,280 | PVSC Compliance Sample collected |
| 03/05/14 | 8.0 | 5,064.73 | 5,170.07 | 105,340 | 5,169,620 | |
| 03/10/14 | 8.0 | 5,170.07 | 5,299.77 | 129,700 | 5,299,320 | |
| 03/11/14 | 8.0 | 5,299.77 | 5,368.86 | 69,090 | 5,368,410 | |
| 03/12/14 | 8.0 | 5,368.86 | 5,433.63 | 64,770 | 5,433,180 | |
| 03/17/14 | 8.0 | 5,433.63 | 5,590.00 | 156,370 | 5,589,550 | |
| 03/18/14 | 8.0 | 5,590.00 | 5,690.00 | 100,000 | 5,689,550 | |
| 03/19/14 | 8.0 | 5,690.00 | 5,849.46 | 159,460 | 5,849,010 | |
| 03/20/14 | 8.0 | 5,849.46 | 5,912.45 | 62,990 | 5,912,000 | |
| 03/21/14 | 8.0 | 5,912.45 | 6,024.94 | 112,490 | 6,024,490 | |
| 03/24/14 | 8.0 | 6,024.94 | 6,125.64 | 100,700 | 6,125,190 | |
| 03/25/14 | 8.0 | 6,125.64 | 6,175.64 | 50,000 | 6,175,190 | |
| 03/26/14 | 8.0 | 6,175.64 | 6,248.89 | 73,250 | 6,248,440 | |
| 03/27/14 | 8.0 | 6,248.89 | 6,310.44 | 61,550 | 6,309,990 | |
| 03/28/14 | 8.0 | 6,310.44 | 6,380.45 | 70,010 | 6,380,000 | |
| 03/31/14 | 8.0 | 6,380.45 | 6,575.85 | 195,400 | 6,575,400 | |

Note: Data shown is for recent months activity

## Attachment 6: Backfill Analytical Data

- Stockpiled Material Tracking and Sampling Log


**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL* | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 30-41 | >1000 | 41-1000-a | 750 | 124-41-1000-a1 | 2/25/2014 | 12:40 | 1,750 | | | Yes |
| | | | | 124-41-1000-a2 | 2/25/2014 | 12:45 | 3,690 | | | Yes |
| | | | | 124-41-1000-a3 | 2/25/2014 | 12:50 | 3,410 | | | Yes |
| | | | | 124-41-1000-a4 | 2/25/2014 | 12:55 | 453 | | Yes | |
| 30-41 | >1000 | 41-1000-b | 750 | 124-41-1000-b1 | 2/25/2014 | 13:00 | 490 | | Yes | |
| | | | | 124-41-1000-b2 | 2/25/2014 | 13:05 | 1,110 | | | Yes |
| | | | | 124-41-1000-b3 | 2/25/2014 | 13:10 | 669 | | Yes | |
| | | | | 124-41-1000-b4 | 2/25/2014 | 13:15 | 1,920 | | | Yes |
| 37-46 | <20 | 46-20-a | 750 | 124-46-20-a1 | 3/12/2014 | 14:00 | 3.2 | ** | | |
| | | | | 124-46-20-a2 | 3/12/2014 | 14:05 | 2.2 | ** | | |
| | | | | 124-46-20-a3 | 3/12/2014 | 14:10 | 3.9 | ** | | |
| | | | | 124-46-20-a4 | 3/12/2014 | 14:15 | 2 | ** | | |
| 37-46 | <20 | 46-20-b | 750 | 124-46-20-b1 | 3/12/2014 | 14:20 | 2.9 | ** | | |
| | | | | 124-46-20-b2 | 3/12/2014 | 14:25 | 3.8 | ** | | |
| | | | | 124-46-20-b3 | 3/12/2014 | 14:30 | 2.2 | ** | | |
| | | | | 124-46-20-b4 | 3/12/2014 | 14:35 | 2.6 | ** | | |
| 41-49 | >1000 | 124-49-1000-a | 1000 | 124-49-1000-a1 | 3/24/2014 | 9:15 | 3490 | | | Pending |
| | | | | 124-49-1000-a2 | 3/24/2014 | 9:20 | 3850 | | | Pending |
| | | | | 124-49-1000-a3 | 3/24/2014 | 9:25 | 2580 | | | Pending |
| | | | | 124-49-1000-a4 | 3/24/2014 | 9:30 | 5570 | | | Pending |
| 41-49 | >1000 | 124-49-1000-b | 1000 | 124-49-1000-b1 | 3/24/2014 | 9:35 | 8840 | | | Pending |
| | | | | 124-49-1000-b2 | 3/24/2014 | 9:40 | 2340 | | | Pending |
| | | | | 124-49-1000-b3 | 3/24/2014 | 9:45 | 2 | | Pending | |
| | | | | 124-49-1000-b4 | 3/24/2014 | 9:50 | 4250 | | | Pending |

**Notes:**
*Material placement locations are approximate.
**Material currently stockpiled.

Note: Data shown is for recent months activity

## Attachment 7:  Perimeter Pools Update




IN PROGRESS
04-19-2010


STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Apr 19, 2010 at 3:12pm
G:\DWGS\102\10210\Dewatering\Perimeter Pool Data.dwg
lreva





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 087-MW- | | | 134-MW- | | 073-MW- | | 140- | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | ** E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | ** W1-SO | W3-SO | W5-SO | ** W6-SO | * Y20 | *001 | * O19 | ** V09 | *Q08 | * BB-11 | Y10 | MW-06 | MW-07 |
| Date | | | | | | | | | | | | | | | | | | |
| 9/5/2013 | | | | | | | | | | | | | 5.2 | 5.6 | 3.2 | 3.5 | 6.2 | 5.4 |
| 9/13/2013 | 5.9 | 5.7 | 6.0 | 5.8 | 6.1 | 9.5 | 4.6 | 6.9 | 7.4 | 4.7 | 5.4 | 8.3 | | | | | | |
| 9/16/2013 | | | | | | | | | | | | | 5.5 | 5.6 | 3.2 | 3.7 | 6.0 | 5.0 |
| 10/2/2013 | 5.7 | 5.6 | 5.9 | 5.5 | 5.8 | 9.4 | 4.4 | 6.6 | 7.3 | 4.8 | 5.9 | 7.8 | | | | | | |
| 10/4/2013 | | | | | | | | | | | | | 4.7 | 6.1 | 3.3 | 4.1 | 6.2 | 5.5 |
| 10/10/2013 | | | | | | | | | | | | | 5.2 | 5.5 | 4.2 | 3.9 | 6.1 | 5.0 |
| 10/17/2013 | | | | | | | | | | | | | 4.8 | 5.3 | 3.1 | 3.7 | 5.9 | 5.1 |
| 10/18/2013 | 5.5 | 5.5 | 5.6 | 5.3 | 5.8 | 9.4 | 4.4 | 6.3 | 7.4 | 4.8 | 6.2 | 7.9 | | | | | | |
| 10/25/2013 | | | | | | | | | | | | | 4.3 | 5.2 | 3.1 | 3.9 | 5.8 | 5.5 |
| 11/4/2013 | 5.4 | 5.4 | 5.4 | 5.1 | 5.6 | 9.3 | 4.3 | 6.2 | 7.1 | 4.7 | 6.1 | 7.7 | | | | | | |
| 11/15/2013 | | | | | | | | | | | | | 3.7 | 5.0 | 3.9 | 4.4 | 5.8 | 4.8 |
| 11/22/2013 | 5.3 | 5.3 | 5.1 | 4.9 | 5.6 | 9.3 | 4.6 | 6.1 | 7.1 | 4.7 | 6.4 | 7.9 | | | | | | |
| 12/4/2013 | 7.6 | 4.7 | 5.1 | 5.1 | 6.0 | 9.3 | 4.9 | 6.3 | 7.5 | 5.2 | 6.5 | 8.1 | 5.2 | 5.8 | 7.0 | | 6.9 | 5.1 |
| 12/17/2013 | | 4.7 | 4.7 | 5.7 | 6.5 | 9.5 | 4.6 | 8.1 | 7.7 | 4.5 | 6.3 | 7.8 | | | | | 7.3 | 5.7 |
| 12/31/2013 | | 4.8 | 5.6 | 6.0 | 7.1 | 9.9 | 7.5 | | 8.6 | 5.0 | 6.6 | 8.1 | | | | | | |
| 1/2/2014 | | | | | | | | | | | | | 5.9 | 7.0 | 7.4 | | 7.4 | 5.8 |
| 1/9/2014 | | | | | | | | 7.9 | | | | | | | | | | |
| 1/15/2014 | | | | | | | | | | | | | 6.5 | 7.3 | 7.2 | | 7.2 | 6.5 |
| 1/16/2014 | | 5.3 | 6.0 | 6.3 | 7.3 | | 7.6 | 7.8 | 8.3 | 4.9 | 7.5 | 8.7 | | | | | | |
| 2/3/2014 | | | | | | | | | | | | | 6.2 | 7.1 | 7.0 | | 7.0 | 7.2 |
| 2/4/2014 | | | | 6.4 | 6.7 | | 7.5 | | | 4.7 | 7.2 | 8.2 | | | | | | |
| 2/17/2014 | | | | | | | | | | | | | | 6.8 | | | 6.8 | 5.7 |
| 2/21/2014 | | | | 6.2 | 7.2 | | 7.4 | | | 4.8 | | 8.0 | | | | | | |
| 3/3/2014 | | | | | | | | | | | | | | | | | 7.3 | 5.0 |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | | | | | | | 7.4 | 4.1 |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | |

* Monitoring well abandoned per 100% Design Report
** Temporarily unavailable due to construction activities

## Attachment 8:  Quality and Level Data in GWET Wells

(Not available as of this report date - provided on a quarterly basis)

## Attachment 9: Surcharge Monitoring Update

- Instrumentation Location Plan 1N
- Instrumentation Installation Data

EXCAVATE MATERIAL ABOVE FORCE MAIN TO PLACE SP4–SP10 IN DIRECT CONTACT WITH STRUCTURE

EXISTING 72" PVSC FORCE MAIN

AS BUILT SENSOR LOCATION 686080.23 602274.18 ELEV=11.97

AS BUILT SENSOR LOCATION 686125.20 602179.75 ELEV=12.74

AS BUILT SENSOR LOCATION 686022.45 602394.16 ELEV=11.04

AS BUILT SENSOR LOCATION 685961.96 602514.81 ELEV=9.88


AS BUILT SENSOR LOCATION 685904.43 602635.42 ELEV=8.85

AS BUILT SENSOR LOCATION 685848.02 602762.07 ELEV=7.32

INCLINOMETERS BETWEEN HYDRAULIC BARRIER AND 72" FORCE MAIN


SEE NOTE 7 (TYP)

SA–7 FINAL GRADE (ACTUAL GRADES VARY)




| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| VI–1 | 686123 | 602109 |
| VI–2 | 686029 | 602048 |
| VI–3 | 685927 | 602572 |
| VI–4 | 685866 | 602701 |
| FS1 | 685981 | 602115 |
| FS2 | 685863 | 602451 |
| FS3 | 685811 | 602689 |
| FS4 | 685723 | 602723 |
| HS1 | 685959 | 602414 |
| HS2 | 685929 | 602333 |
| HS3 | 685865 | 602294 |
| HS4 | 685920 | 602491 |
| HS5 | 685787 | 602414 |
| ~~HS6~~ | ~~685785~~ | ~~602650~~ |
| HS7 | 685696 | 602582 |
| ~~HS8~~ | ~~685826~~ | ~~602796~~ |
| HS9 | 685624 | 602691 |

| | | |
|---|---|---|
| SP1 | 685881 | 602205 |
| SP2 | 685757 | 602416 |
| SP3 | 685613 | 602662 |
| ~~SP4~~ | ~~685953~~ | ~~602533~~ |
| ~~SP5~~ | ~~685931~~ | ~~602578~~ |
| ~~SP6~~ | ~~685906~~ | ~~602634~~ |
| ~~SP7~~ | ~~685887~~ | ~~602676~~ |
| ~~SP8~~ | ~~685867~~ | ~~602721~~ |
| ~~SP9~~ | ~~685849~~ | ~~602764~~ |
| ~~SP10~~ | ~~685884~~ | ~~602781~~ |




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. COMMENCE FILL AT THE SEDIMENTATION BASIN AND WORK TOWARDS THE HACKENSACK RIVER.
6. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
7. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
8. AT ALL SURVEY LOCATIONS CLEAN ADEQUATELY A SUFFICIENT AREA ON THE TOP SURFACE OF THE 72 INCH FORCE MAIN TO EPOXY THE SURVEY MARKER AND ELECTRONIC EQUIPMENT.

Installed Instrumentation Locations

Instrumentation Locations Not Installed

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SETUP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SETUP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |
| A1 | ACOUSTICAL LOCATION FOR DISCUSSION PURPOSES ONLY |
| AS3 | ACOUSTICAL/SURVEY LOCATION FOR DISCUSSION PURPOSES ONLY |
| X | STATION RELOCATED OR ELIMINATED DUE TO SURCHARGE PILE RECONFIGURATION |

0 15 30 60
SCALE IN FEET

Prepared/Date: RJR 08/16/13
Checked/Date: AE 08/16/13

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 1N
Project 3480-09-0006
Figure B1




Z:\Projects\HONEYWELL\JERSEY CITY\Corp Design–2340–2580\2430\2430A\190 Percent\Figure 1 Surcharge Settling Monitoring Plan – Area 1.dwg Tue, 21 Jan 2014 – 7:11am roger.rauler

# SURCHARGE AREA N1

# INSTRUMENT INSTALLATION DATA

# FS-01




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-01_VWP |
| **DRILLED:** | 12/20/13 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-01_VWP |
| **DRILLED:** | 12/20/13 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2


amec




Notes:

1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_FS-01_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/12-30-13 |
| **Boring No.:** | N_FS-01_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 12/20/2013 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to 29' bgs. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-01_SS |
| **DRILLED:** | 12/23/13 - 12/24/13 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to 29' bgs. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-01_SS |
| **DRILLED:** | 12/23/13 - 12/24/13 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec




| Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. Sondex System manufactured by Slope Indicator.
4. Refer to Boring Record N_FS-01_SS for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | Sondex System Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-8-14 |
| **Boring No.:** | N_FS-01_SS | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 12/24/2013 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

| DEPTH (ft) | SOIL DESCRIPTION AND REMARKS<br>SEE KEY TO SYMBOLS AND DESCRIPTIONS FOR EXPLANATION OF SYMBOLS, TERMINOLOGY, AND ABBREVIATIONS | LEGEND | ELEV (ft) | SAMPLES: IDENT | SAMPLES: TYPE | SAMPLES: BLOW COUNT (1st 6" / 2nd 6" / 3rd 6" / 4th 6" / Or RQD / % REC) |
|---|---|---|---|---|---|---|
| 0 | FILL<br><br>- No geotechnical testing/sampling was performed in this boring.<br><br>- Refer to N_FS-01_VWP and N_FS-01_SS for soil descriptions/stratigraphy and geotechnical testing/sampling for this monitoring point. | | 16.2 | | | |
| 5 | | | 11.2 | | | |
| 10 | | | 6.2 | | | |
| 15 | | | 1.2 | | | |
| 20 | End of exploration at 20.0' bgs | | -3.8 | | | |

PL (%) NM (%) LL (%)
▲ FINES (%) ● SPT (N-value) ✪ ORG (%)
10 20 30 40 50 60 70 80 90
0 10 20 30 40 50 60 70 80 90 100

BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

DRILLER: B&B
RIG TYPE: Gustech Brat 22
METHOD: Hollow-Stem Augers
HOLE DIAM.: 4.25" ID
SPTs: N/A
REMARKS: Installed standpipe piezometer. Drill cuttings containerized upon completion.


LOGGED BY: AE CHECKED BY/DATE: TCC/04-07-14

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

**BORING NO.:** N_FS-01_SPP
**DRILLED:** 12/30/13
**PROJECT:** SA-6 Surcharge Monitoring
**LOCATION:** Jersey City, New Jersey
**PROJECT NO.:** 3480130377 **PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | Gustech Brat 22 |
| METHOD: | Hollow-Stem Augers |
| HOLE DIAM.: | 4.25" ID |
| SPTs: | N/A |
| REMARKS: | Installed standpipe piezometer. Drill cuttings containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD


| | |
|---|---|
| **BORING NO.:** | N_FS-01_SPP |
| **DRILLED:** | 12/30/13 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec


| AMEC E&I, Inc. | | | | STANDPIPE PIEZOMETER CONSTRUCTION DIAGRAM |
|---|---|---|---|---|
| **Project:** | SA-6 Surcharge Monitoring | **Project Number:** | 3480130377 | **N_FS-01_SPP** |
| **Location:** | Jersey City, NJ | | | |
| **Client:** | Honeywell | **Date:** | 3/13/2014 | |
| **Drilling Method:** | 4.25-inch ID HSA | | | **Measuring Point** |
| **Installed Date:** | 12/30/2013 | | | **Type:** Top of Riser |
| **Installed By:** | AE | | | **Elevation (ft):** 21.1 |

| Item | Depth (ft bgs) | Elevation (ft) | Description |
|---|---|---|---|
| Top of Riser | -4.9 | 21.1 | Stickup Type: PVC (sch. 40); Stickup Diameter: 1-inch |
| Ground Surface | 0.0 | 16.2 | |
| | | | Backfill/Grout Type: N.J.A.C. 7:9D-2.9 Table 2 |
| | | | Riser Pipe Type: PVC (sch. 40); Riser Pipe ID: 1-inch |
| | | | Borehole Diameter: 9-inches |
| Top of Seal | 5.0 | 11.2 | |
| | | | Type of Seal: Bentonite Chips |
| Top of Filter Pack | 8.0 | 8.2 | |
| Top of Screen | 10.0 | 6.2 | |
| | | | Screen Type: PVC (sch. 40); Screen ID: 1-inch |
| | | | Screen Slot Size: 0.010-inch |
| | | | Screen Length: 10 feet |
| | | | Filter/Sand Pack Type: Filter Sand (#1) |
| Base of Screen | 20.0 | -3.8 | |
| End Cap | 20.0 | -3.8 | Sump: N/A |
| Drilled Depth | 20.0 | -3.8 | Fallback/Backfill: N/A |
| Total Depth | 20.0 | -3.8 | |



**Notes:** 1. Elevation Datum NGVD 29.

# FS-02




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 2 VWPs. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-02_VWP |
| **DRILLED:** | 01/13/14 - 01/14/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 2 VWPs. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.


## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-02_VWP |
| **DRILLED:** | 01/13/14 - 01/14/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec

# N_FS-02_VWP




| Center O VWP | |
|---|---|
| **Designation:** | N_FS-02_VWP-O |
| **Serial No.:** | 1303630 |
| **Depth (ft bgs):** | 19.3 |
| **Elevation (ft):** | -4.5 |


| Center D VWP | |
|---|---|
| **Designation:** | N_FS-02_VWP-D |
| **Serial No.:** | 1303336 |
| **Depth (ft bgs):** | 23.0 |
| **Elevation (ft):** | -8.3 |

**Target Cement-Bentonite Grout Mix**

| Material | Weight | Ratio by Weight |
|---|---|---|
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_FS-02_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1/14/14 |
| **Boring No.:** | N_FS-02_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/14/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to 28' bgs. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-02_SS |
| **DRILLED:** | 01/15/14 - 01/16/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to 28' bgs. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-02_SS |
| **DRILLED:** | 01/15/14 - 01/16/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |


**PAGE** 2 **OF** 2

amec

# N_FS-02_SS

Initial Top of Inner Casing Elevation = 18.0 ft
Baseline Ground Surface Elevation = 14.8 ft

Northing: 685860.14
Easting: 602456.81




**FILL**

Top of Stratum O — Depth 17.2 ft bgs; Elevation -2.5 ft

**STRATUM O**

Bottom of Stratum O — Depth 20.8 ft bgs; Elevation -6.0 ft

Top of Stratum D — Depth 20.8 ft bgs; Elevation -6.0 ft

**STRATUM D**

Bottom of Stratum D — Depth 25.2 ft bgs; Elevation -10.5 ft

Top of Stratum S1/S2 — Depth 25.2 ft bgs; Elevation -10.5 ft

**STRATUM S1 or S2**

Bottom of Sondex — Depth 37.0 ft bgs; Elevation -22.3 ft


| | | | |
|---|---|---|---|
| Ring 1 | Depth 7.3 ft bgs | Elevation 7.4 ft | |
| Ring 2 | Depth 15.4 ft bgs | Elevation -0.6 ft | |
| Ring 3 | Depth 16.3 ft bgs | Elevation -1.6 ft | |
| Ring 4 | Depth 17.3 ft bgs | Elevation -2.6 ft | |
| Ring 5 | Depth 18.3 ft bgs | Elevation -3.5 ft | |
| Ring 6 | Depth 19.2 ft bgs | Elevation -4.5 ft | |
| Ring 7 | Depth 20.2 ft bgs | Elevation -5.4 ft | |
| Ring 8 | Depth 21.2 ft bgs | Elevation -6.5 ft | |
| Ring 9 | Depth 22.2 ft bgs | Elevation -7.4 ft | |
| Ring 10 | Depth 23.2 ft bgs | Elevation -8.4 ft | |
| Ring 11 | Depth 24.2 ft bgs | Elevation -9.5 ft | |
| Ring 12 | Depth 25.2 ft bgs | Elevation -10.5 ft | |
| Ring 13 | Depth 26.2 ft bgs | Elevation -11.4 ft | |
| Ring 14 | Depth 27.1 ft bgs | Elevation -12.4 ft | |
| Ring 15 | Depth 35.9 ft bgs | Elevation -21.1 ft | |

**Cement-Bentonite Grout Mix**

| Material | Weight | Ratio by Weight |
|---|---|---|
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. Sondex System manufactured by Slope Indicator.
4. Refer to Boring Record N_FS-02_SS for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | Sondex System Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/3-27-14 |
| **Boring No.:** | N_FS-02_SS | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/16/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Hollow-Stem Augers |
| HOLE DIAM.: | 4.25" ID |
| SPTs: | N/A |
| REMARKS: | Installed standpipe piezometer. Drill cuttings containerized upon completion. |

LOGGED BY: AE CHECKED BY/DATE: TCC/04-07-14


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-02_SPP |
| **DRILLED:** | 01/14/14 - 01/15/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Hollow-Stem Augers |
| HOLE DIAM.: | 4.25" ID |
| SPTs: | N/A |
| REMARKS: | Installed standpipe piezometer. Drill cuttings containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD


| | |
|---|---|
| **BORING NO.:** | N_FS-02_SPP |
| **DRILLED:** | 01/14/14 - 01/15/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec


| AMEC E&I, Inc. | | | | STANDPIPE PIEZOMETER CONSTRUCTION DIAGRAM |
|---|---|---|---|---|
| **Project:** | SA-6 Surcharge Monitoring | **Project Number:** | 3480130377 | **N_FS-02_SPP** |
| **Location:** | Jersey City, NJ | | | |
| **Client:** | Honeywell | **Date:** | 3/13/2014 | |
| **Drilling Method:** | 4.25-inch ID HSA | | | **Measuring Point** |
| **Installed Date:** | 1/15/2014 | | | **Type:** Top of Riser |
| **Installed By:** | AE | | | **Elevation (ft):** 19.4 |

| Item | Depth (ft bgs) | Elevation (ft) | Description |
|---|---|---|---|
| Top of Riser | -4.7 | 19.4 | Stickup Type: PVC (sch. 40) |
| | | | Stickup Diameter: 1-inch |
| Ground Surface | 0.0 | 14.8 | |
| | | | Backfill/Grout Type: N.J.A.C. 7:9D-2.9 Table 2 |
| | | | Riser Pipe Type: PVC (sch. 40) |
| | | | Riser Pipe ID: 1-inch |
| | | | Borehole Diameter: 9-inches |
| Top of Seal | 5.0 | 9.8 | |
| | | | Type of Seal: Bentonite Chips |
| Top of Filter Pack | 8.0 | 6.8 | |
| Top of Screen | 10.0 | 4.8 | |
| | | | Screen Type: PVC (sch. 40) |
| | | | Screen ID: 1-inch |
| | | | Screen Slot Size: 0.010-inch |
| | | | Screen Length: 10 feet |
| | | | Filter/Sand Pack Type: Filter Sand (#1) |
| Base of Screen | 20.0 | -5.3 | |
| End Cap | 20.0 | -5.3 | Sump: N/A |
| Drilled Depth | 20.0 | -5.3 | Fallback/Backfill: N/A |
| Total Depth | 20.0 | -5.3 | |



**Notes:** 1. Elevation Datum NGVD 29.

# FS-03




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 2 VWPs. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-03_VWP |
| **DRILLED:** | 01/21/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 2 VWPs. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-03_VWP |
| **DRILLED:** | 01/21/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec




| Center O VWP | |
|---|---|
| **Designation:** | N_FS-03_VWP-O |
| **Serial No.:** | 1303563 |
| **Depth (ft bgs):** | 17.3 |
| **Elevation (ft):** | -2.9 |


| Center D VWP | |
|---|---|
| **Designation:** | N_FS-03_VWP-D |
| **Serial No.:** | 1303637 |
| **Depth (ft bgs):** | 21.5 |
| **Elevation (ft):** | -7.2 |

**Target Cement-Bentonite Grout Mix**

| Material | Weight | Ratio by Weight |
|---|---|---|
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_FS-03_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1/24/14 |
| **Boring No.:** | N_FS-03_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/21/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to 23.5' bgs. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | MS CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-03_SS |
| **DRILLED:** | 1/30/14 - 1/31/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to 23.5' bgs. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-03_SS |
| **DRILLED:** | 1/30/14 - 1/31/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2


amec




| Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. Sondex System manufactured by Slope Indicator.
4. Refer to Boring Record N_FS-03_SS for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | Sondex System Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/3-27-14 |
| **Boring No.:** | N_FS-03_SS | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/31/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | Gustech Brat 22 |
| METHOD: | Hollow-Stem Augers |
| HOLE DIAM.: | 4.25" ID |
| SPTs: | N/A |
| REMARKS: | Installed standpipe piezometer. Drill cuttings containerized upon completion. |

LOGGED BY: AE CHECKED BY/DATE: TCC/04-07-14

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.


## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-03_SPP |
| **DRILLED:** | 1/30/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 1


amec

| AMEC E&I, Inc. | | | | STANDPIPE PIEZOMETER CONSTRUCTION DIAGRAM | |
|---|---|---|---|---|---|
| **Project:** | SA-6 Surcharge Monitoring | | **Project Number:** 3480130377 | **N_FS-03_SPP** | |
| **Location:** | Jersey City, NJ | | | | |
| **Client:** | Honeywell | | **Date:** 3/13/2014 | | |
| **Drilling Method:** | 4.25-inch ID HSA | | | **Measuring Point** | |
| **Installed Date:** | 1/30/2014 | | | **Type:** | Top of Riser |
| **Installed By:** | AE | | | **Elevation (ft):** | 16.2 |

| Item | Depth (ft bgs) | Elevation (ft) | Legend | Description | |
|---|---|---|---|---|---|
| Top of Riser | -1.9 | 16.2 |  | Stickup Type: | PVC (sch. 40) |
| | | | | Stickup Diameter: | 1-inch |
| Ground Surface | 0.0 | 14.3 | | | |
| | | | | Backfill/Grout Type: | N.J.A.C. 7:9D-2.9 Table 2 |
| | | | | Riser Pipe Type: | PVC (sch. 40) |
| | | | | Riser Pipe ID: | 1-inch |
| | | | | Borehole Diameter: | 9-inches |
| Top of Seal | 3.0 | 11.3 | | | |
| | | | | Type of Seal: | Bentonite Chips |
| Top of Filter Pack | 6.0 | 8.3 | | | |
| Top of Screen | 8.0 | 6.3 | | | |
| | | | | Screen Type: | PVC (sch. 40) |
| | | | | Screen ID: | 1-inch |
| | | | | Screen Slot Size: | 0.010-inch |
| | | | | Screen Length: | 10 ft |
| | | | | Filter/Sand Pack Type: | Filter Sand (#1) |
| Base of Screen | 18.0 | -3.7 | | | |
| End Cap | 18.0 | -3.7 | | Sump: | N/A |
| Drilled Depth | 18.0 | -3.7 | | Fallback/Backfill: | N/A |
| Total Depth | 18.0 | -3.7 | | | |

**Notes:** 1. Elevation Datum NGVD 29.

# FS-04




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 2 VWPs. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_VWP |
| **DRILLED:** | 02/18/14 - 02/19/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 2 VWPs. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.


## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_VWP |
| **DRILLED:** | 02/18/14 - 02/19/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec

# N_FS-04_VWP




| Center O VWP | |
|---|---|
| **Designation:** | N_FS-04_VWP-O |
| **Serial No.:** | 1303321 |
| **Depth (ft bgs):** | 15.5 |
| **Elevation (ft):** | -2.2 |


| Center D VWP | |
|---|---|
| **Designation:** | N_FS-04_VWP-D |
| **Serial No.:** | 1303344 |
| **Depth (ft bgs):** | 19.8 |
| **Elevation (ft):** | -6.5 |

**Target Cement-Bentonite Grout Mix**

| Material | Weight | Ratio by Weight |
|---|---|---|
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_FS-04_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/3-27-14 |
| **Boring No.:** | N_FS-04_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 2/19/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | MS CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_VWP-RC |
| **DRILLED:** | 02/19/14 - 02/20/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_VWP-RC |
| **DRILLED:** | 02/19/14 - 02/20/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_VWP-RC |
| **DRILLED:** | 02/19/14 - 02/20/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 3 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_VWP-RC |
| **DRILLED:** | 02/19/14 - 02/20/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 4 **OF** 4

amec





| Center RC VWP | |
|---|---|
| **Designation:** | N_FS-04_VWP-RC |
| **Serial No.:** | 1302488 |
| **Depth (ft bgs):** | 56.5 |
| **Elevation (ft):** | -43.2 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611024.
4. Refer to Boring Record N_FS-04_VWP-RC for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/3-27-14 |
| **Boring No.:** | N_FS-04_VWP-RC | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 2/20/2014 | **Project No.** | 3480-13-0377 | **Scale:** | NTS |




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | MS CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_SS |
| **DRILLED:** | 02/21/14 - 02/24/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash (Variable) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Installed Sondex System. CB grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_SS |
| **DRILLED:** | 02/21/14 - 02/24/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2


amec




| Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. Sondex System manufactured by Slope Indicator.
4. Refer to Boring Record N_FS-04_SS for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | Sondex System Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/3-27-14 |
| **Boring No.:** | N_FS-04_SS | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 2/24/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Hollow-Stem Augers |
| HOLE DIAM.: | 4.25" ID |
| SPTs: | N/A |
| REMARKS: | Installed standpipe piezometer. Drill cuttings containerized upon completion. |

LOGGED BY: AE CHECKED BY/DATE: TCC/04-07-14

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_FS-04_SPP |
| **DRILLED:** | 02/21/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 1


amec

| AMEC E&I, Inc. | | | | STANDPIPE PIEZOMETER CONSTRUCTION DIAGRAM | |
|---|---|---|---|---|---|
| **Project:** | SA-6 Surcharge Monitoring | | **Project Number:** 3480130377 | **N_FS-04_SPP** | |
| **Location:** | Jersey City, NJ | | | | |
| **Client:** | Honeywell | | **Date:** 3/13/2014 | | |
| **Drilling Method:** | 4.25-inch ID HSA | | | **Measuring Point** | |
| **Installed Date:** | 2/21/2014 | | | **Type:** | Top of Riser |
| **Installed By:** | AE | | | **Elevation (ft):** | 15.8 |

| Item | Depth (ft bgs) | Elevation (ft) | Legend | Description | |
|---|---|---|---|---|---|
| Top of Riser | -2.5 | 15.8 | | Stickup Type: | PVC (sch. 40) |
| | | | | Stickup Diameter: | 1-inch |
| Ground Surface | 0.0 | 13.3 | | | |
| | | | | Backfill/Grout Type: | N.J.A.C. 7:9D-2.9 Table 2 |
| | | | | Riser Pipe Type: | PVC (sch. 40) |
| | | | | Riser Pipe ID: | 1-inch |
| | | | | Borehole Diameter: | 9-inches |
| Top of Seal | 2.5 | 10.8 | | | |
| | | | | Type of Seal: | Bentonite Chips |
| Top of Filter Pack | 5.5 | 7.8 | | | |
| Top of Screen | 7.5 | 5.8 | | | |
| | | | | Screen Type: | PVC (sch. 40) |
| | | | | Screen ID: | 1-inch |
| | | | | Screen Slot Size: | 0.010-inch |
| | | | | Screen Length: | 5 feet |
| | | | | Filter/Sand Pack Type: | Filter Sand (#1) |
| Base of Screen | 12.5 | 0.8 | | | |
| End Cap | 12.5 | 0.8 | | Sump: | N/A |
| Drilled Depth | 12.5 | 0.8 | | Fallback/Backfill: | N/A |
| Total Depth | 12.5 | 0.8 | | | |

**Notes:** 1. Elevation Datum NGVD 29.

# HS-01




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-01_VWP |
| **DRILLED:** | 03/25/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-01_VWP |
| **DRILLED:** | 03/25/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec





| Center D VWP | |
|---|---|
| **Designation:** | N_HS-01_VWP-D |
| **Serial No.:** | 1303335 |
| **Depth (ft bgs):** | 25.0 |
| **Elevation (ft):** | -9.6 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-01_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/4-1-14 |
| **Boring No.:** | N_HS-01_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 3/25/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

# HS-02




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-02_VWP |
| **DRILLED:** | 01/13/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-02_VWP |
| **DRILLED:** | 01/13/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec





| Center D VWP | |
|---|---|
| **Designation:** | N_HS-02_VWP-D |
| **Serial No.:** | 1303627 |
| **Depth (ft bgs):** | 23.5 |
| **Elevation (ft):** | -9.2 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-02_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-13-14 |
| **Boring No.:** | N_HS-02_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/13/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

# HS-03




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |

LOGGED BY: AE CHECKED BY/DATE: TCC/04-07-14


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-03_VWP |
| **DRILLED:** | 12/31/13 - 01/02/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-03_VWP |
| **DRILLED:** | 12/31/13 - 01/02/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec





| Center D VWP | |
|---|---|
| **Designation:** | N_HS-03_VWP-D |
| **Serial No.:** | 1303341 |
| **Depth (ft bgs):** | 23.5 |
| **Elevation (ft):** | -8.7 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-03_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-7-14 |
| **Boring No.:** | N_HS-03_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/2/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

# HS-04




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-04_VWP |
| **DRILLED:** | 03/26/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-04_VWP |
| **DRILLED:** | 03/26/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec





| Center D VWP | |
|---|---|
| **Designation:** | N_HS-04_VWP-D |
| **Serial No.:** | 1303329 |
| **Depth (ft bgs):** | 23.5 |
| **Elevation (ft):** | -8.6 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-04_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/4-1-14 |
| **Boring No.:** | N_HS-04_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 3/26/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

# HS-05




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-05_VWP |
| **DRILLED:** | 01/02/14 - 01/06/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-05_VWP |
| **DRILLED:** | 01/02/14 - 01/06/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec




| Center D VWP | |
|---|---|
| **Designation:** | N_HS-05_VWP-D |
| **Serial No.:** | 1303564 |
| **Depth (ft bgs):** | 23.3 |
| **Elevation (ft):** | -10.0 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-05_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-7-14 |
| **Boring No.:** | N_HS-05_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/6/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

| DEPTH (ft) | SOIL DESCRIPTION AND REMARKS<br>SEE KEY TO SYMBOLS AND DESCRIPTIONS FOR EXPLANATION OF SYMBOLS, TERMINOLOGY, AND ABBREVIATIONS | LEGEND | ELEV (ft) | SAMPLES: IDENT | SAMPLES: TYPE | SAMPLES: BLOW COUNT (1st 6" / 2nd 6" / 3rd 6" / 4th 6") Or RQD / % REC |
|---|---|---|---|---|---|---|
| 0 | FILL<br><br>- 0.0' to 55.0' bgs: No geotechnical testing/sampling performed. Description(s) based on observation of drilling, N_HS-05_VWP, and/or interpretation of nearby pre-design geotechnical explorations. | | 13.3 | | | |
| 5 | | | 8.3 | | | |
| 10 | | | 3.3 | | | |
| 15 | | | -1.7 | | | |
| 20 | STRATUM O | | -6.7 | | | |
| | STRATUM D | | | | | |

PL (%) NM (%) LL (%)
▲ FINES (%) ● SPT (N-value) ✪ ORG (%)
10 20 30 40 50 60 70 80 90

0 10 20 30 40 50 60 70 80 90 100

BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-05_VWP-RC |
| **DRILLED:** | 01/06/14 - 01/10/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-05_VWP-RC |
| **DRILLED:** | 01/06/14 - 01/10/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 4

amec




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-05_VWP-RC |
| **DRILLED:** | 01/06/14 - 01/10/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 3 **OF** 4

amec




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 4" casing into Stratum D. Casing flushed. 4" casing advanced to Stratum RC. Installed 1 VWP. CB grout pumped from bottom to top via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-05_VWP-RC |
| **DRILLED:** | 01/06/14 - 01/10/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 4 **OF** 4

amec





| Center RC VWP | |
|---|---|
| **Designation:** | N_HS-05_VWP-RC |
| **Serial No.:** | 1302491 |
| **Depth (ft bgs):** | 68.0 |
| **Elevation (ft):** | -54.7 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611024.
4. Refer to Boring Record N_HS-05_VWP-RC for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-13-14 |
| **Boring No.:** | N_HS-05_VWP-RC | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/10/2014 | **Project No.** | 3480-13-0377 | **Scale:** | NTS |

# HS-07




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |

LOGGED BY: AE CHECKED BY/DATE: TCC/04-07-14


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-07_VWP |
| **DRILLED:** | 01/17/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-07_VWP |
| **DRILLED:** | 01/17/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec





| Center D VWP | |
|---|---|
| **Designation:** | N_HS-07_VWP-D |
| **Serial No.:** | 1303633 |
| **Depth (ft bgs):** | 20.0 |
| **Elevation (ft):** | -7.6 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-07_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-20-14 |
| **Boring No.:** | N_HS-07_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/17/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

# HS-09




| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-09_VWP |
| **DRILLED:** | 01/20/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 2

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 4" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | Installed 1 VWP. Cement-bentonite grout placed (pumped) from bottom to top via tremie pipe. Drill cuttings and fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_HS-09_VWP |
| **DRILLED:** | 01/20/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 2

amec





| Center D VWP | |
|---|---|
| **Designation:** | N_HS-09_VWP-D |
| **Serial No.:** | 1303635 |
| **Depth (ft bgs):** | 21.0 |
| **Elevation (ft):** | -7.3 |

| Target Cement-Bentonite Grout Mix | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 50 gal | 4.4 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 30-39 lbs (as required) | 0.4 B : 1.0 C |

Notes:
1. Elevation Datum NGVD 29.
2. Horizontal Datum NAD 83.
3. VWPs manufactured by Slope Indicator; Part No. 52611028.
4. Refer to Boring Record N_HS-09_VWP for subsurface conditions encountered.

| | | | | | |
|---|---|---|---|---|---|
| **Title:** | VWP Construction Diagram | **Client:** | Honeywell | **By/Date:** | NDL/1-21-14 |
| **Boring No.:** | N_HS-09_VWP | **Project:** | SA-6 | **Ck/Date:** | TCC/4-7-14 |
| **Date Installed:** | 1/20/2014 | **Project No.:** | 3480-13-0377 | **Scale:** | NTS |

# VI-01




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-01 |
| **DRILLED:** | 03/14/14 - 03/17/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-01 |
| **DRILLED:** | 03/14/14 - 03/17/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-01 |
| **DRILLED:** | 03/14/14 - 03/17/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 3 **OF** 4

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-01 |
| **DRILLED:** | 03/14/14 - 03/17/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |


**PAGE** 4 **OF** 4

amec

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **Inclinometer #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | **N_VI-01** |

# INCLINOMETER CONSTRUCTION DIAGRAM

| | | | |
|---|---|---|---|
| **Existing Grade (ft.):** | 17.9 | **Cable No.:** | 2448 |
| **A+ Axis Orientation:** | Perpendicular to bulkhead | **Cable Length:** | 140 feet |
| **Installation Date:** | 3/17/2014 | **Readout SN:** | 10412 |
| **Northing:** | 686110.45 | **Probe SN:** | 29233 |
| **Easting:** | 602120.77 | **Installed By:** | AE |




| Subsurface Profile | |
|---|---|
| Stratum | ft bgs |
| Fill | 0.0 - 26.0 |
| O | - |
| D | 26.0 - 28.5 |
| S1 | 28.5 - 43.0 |
| S2 | 43.0 - 60.0 |


| "Soft" Grout Mix (0 - 36 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs | 0.4 B : 1.0 C |

| "Stiff" Grout Mix (36 to 60 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 8.3 gal | 0.75 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 5 lbs | 0.05 B : 1.0 C |

| | | |
|---|---|---|
| Bottom of Inclinometer Casing Depth: | 60.0 | ft bgs |
| Bottom of Inclinometer Casing EL. | -42.1 | ft |

Notes:
1. Elevation Datum NGVD 29.
2. Inclinometer manufactured by Slope Indicator.
3. Refer to Boring Record N_VI-01 for subsurface conditions encountered.

# VI-02




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-02 |
| **DRILLED:** | 03/18/14 - 03/19/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 3

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-02 |
| **DRILLED:** | 03/18/14 - 03/19/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 3

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-02 |
| **DRILLED:** | 03/18/14 - 03/19/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |


**PAGE** 3 **OF** 3

amec

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **Inclinometer #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | **N_VI-02** |

# INCLINOMETER CONSTRUCTION DIAGRAM

| | | | |
|---|---|---|---|
| **Existing Grade (ft.):** | 17.5 | **Cable No.:** | 2448 |
| **A+ Axis Orientation:** | Perpendicular to bulkhead | **Cable Length:** | 140 feet |
| **Installation Date:** | 3/19/2014 | **Readout SN:** | 10412 |
| **Northing:** | 686042.24 | **Probe SN:** | 29233 |
| **Easting:** | 602032.58 | **Installed By:** | AE |




| Subsurface Profile | |
|---|---|
| Stratum | ft bgs |
| Fill | 0.0 - 26.0 |
| O | - |
| D | 26.0 - 28.5 |
| S1 | 28.5 - 38.5 |
| S2 | 38.5 - 50.0 |


| "Soft" Grout Mix (0 - 33 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs | 0.4 B : 1.0 C |

| "Stiff" Grout Mix (33 to 50 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 8.3 gal | 0.75 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 5 lbs | 0.05 B : 1.0 C |

| | | |
|---|---|---|
| Bottom of Inclinometer Casing Depth: | 50.0 | ft bgs |
| Bottom of Inclinometer Casing EL. | -32.5 | ft |

Notes:
1. Elevation Datum NGVD 29.
2. Inclinometer manufactured by Slope Indicator.
3. Refer to Boring Record N_VI-02 for subsurface conditions encountered.

# VI-03




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-03 |
| **DRILLED:** | 03/19/14 - 03/21/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 3

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-03 |
| **DRILLED:** | 03/19/14 - 03/21/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 3

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-03 |
| **DRILLED:** | 03/19/14 - 03/21/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |


**PAGE** 3 **OF** 3

amec

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **Inclinometer #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | **N_VI-03** |

# INCLINOMETER CONSTRUCTION DIAGRAM

| | | | |
|---|---|---|---|
| **Existing Grade (ft.):** | 15.1 | **Cable No.:** | 2448 |
| **A+ Axis Orientation:** | Perpendicular to forcemain | **Cable Length:** | 140 feet |
| **Installation Date:** | 3/21/2014 | **Readout SN:** | 10412 |
| **Northing:** | 685921.65 | **Probe SN:** | 29233 |
| **Easting:** | 602571.16 | **Installed By:** | AE |




| Subsurface Profile | |
|---|---|
| Stratum | ft bgs |
| Fill | 0.0 - 14.0 |
| O | 14.0 - 19.5 |
| D | 19.5 - 23.8 |
| S1 | 23.8 - 43.0 |
| S2 | 43.0 - 55.0 |


| "Soft" Grout Mix (0 - 33 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs | 0.4 B : 1.0 C |

| "Stiff" Grout Mix (33 to 55 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 8.3 gal | 0.75 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 5 lbs | 0.05 B : 1.0 C |

| | | |
|---|---|---|
| Bottom of Inclinometer Casing Depth: | 55.0 | ft bgs |
| Bottom of Inclinometer Casing EL. | -39.9 | ft |

Notes:
1. Elevation Datum NGVD 29.
2. Inclinometer manufactured by Slope Indicator.
3. Refer to Boring Record N_VI-03 for subsurface conditions encountered.

# VI-04




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |
| LOGGED BY: | AE CHECKED BY/DATE: TCC/04-07-14 |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-04 |
| **DRILLED:** | 03/21/14 - 03/24/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 1 **OF** 3

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |


THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-04 |
| **DRILLED:** | 03/21/14 - 03/24/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |

**PAGE** 2 **OF** 3

amec




BOREHOLE: STANDARD (0-2500 PSF) SA-6 INSTRUMENTATION LOGS.GPJ 2007_12-12_PORT_DTMPLT.GDT 4/7/14

| | |
|---|---|
| DRILLER: | B&B |
| RIG TYPE: | B-61 Mobile |
| METHOD: | Rotary Wash with Water (Cased) |
| HOLE DIAM.: | 6" |
| SPTs: | Spooling-Winch; Safety Hammer; NWJ Drill Rods |
| REMARKS: | 6" casing to Stratum D. Casing flushed. Then mud rotary to depth. Restored as Inclinometer. CB grout placed (pumped) via tremie pipe. Drill cuttings/fluids containerized upon completion. |

THIS BORING RECORD PRESENTS A REASONABLE INTERPRETATION OF THE SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS MAY DIFFER. STRATA INTERFACES (AS SHOWN) ARE APPROXIMATE. ACTUAL TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

## GEOTECHNICAL BORING RECORD

| | |
|---|---|
| **BORING NO.:** | N_VI-04 |
| **DRILLED:** | 03/21/14 - 03/24/14 |
| **PROJECT:** | SA-6 Surcharge Monitoring |
| **LOCATION:** | Jersey City, New Jersey |
| **PROJECT NO.:** | 3480130377 |


**PAGE** 3 **OF** 3

amec

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **Inclinometer #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | **N_VI-04** |

# INCLINOMETER CONSTRUCTION DIAGRAM

| | | | |
|---|---|---|---|
| **Existing Grade (ft.):** | 14.5 | **Cable No.:** | 2448 |
| **A+ Axis Orientation:** | Perpendicular to forcemain | **Cable Length:** | 140 feet |
| **Installation Date:** | 3/24/2014 | **Readout SN:** | 10412 |
| **Northing:** | 685859.50 | **Probe SN:** | 29233 |
| **Easting:** | 602702.68 | **Installed By:** | AE |




| Subsurface Profile | |
|---|---|
| Stratum | ft bgs |
| Fill | 0.0 - 14.0 |
| O | 14.0 - 19.3 |
| D | 19.3 - 23.5 |
| S1 | 23.5 - 27.0 |
| S2 | 27.0 - 47.0 |

| "Soft" Grout Mix (0 - 27 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 75 gal | 6.6 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 39 lbs | 0.4 B : 1.0 C |


| "Stiff" Grout Mix (27 to 47 ft bgs) | | |
|---|---|---|
| **Material** | **Weight** | **Ratio by Weight** |
| Water (W) | 8.3 gal | 0.75 W : 1.0 C |
| Cement (C) | 94 lbs | - |
| Bentonite (B) | 5 lbs | 0.05 B : 1.0 C |

| | | |
|---|---|---|
| Bottom of Inclinometer Casing Depth: | 47.0 | ft bgs |
| Bottom of Inclinometer Casing EL. | -32.5 | ft |

Notes:
1. Elevation Datum NGVD 29.
2. Inclinometer manufactured by Slope Indicator.
3. Refer to Boring Record N_VI-04 for subsurface conditions encountered.

## Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Pile Repair Log




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |

Time frame for:
→ 4 HB sheets driven

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 10/10/13 | TDD | RJR | TDD | RJR | TDD | SGS |
| 0 | 06/07/13 | | | | | | SGS |

HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

Honeywell
101 COLUMBIA RD. BOX 4755, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Pln Prof.dwg PLOT DATE: Mon, 07 Oct 2013 PLOT TIME: 4:04 PM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | TDD | DR TDD CHK RJR APVD | | SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.






NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SHEET MONITORING LOCATIONS
03-12-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:

Entact ID: SP1-6

Date Exposed:

Describe Damage:

Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature:

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:

Entact ID: SP1-7

Date Exposed:

Describe Damage:

Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature:

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:

Entact ID: SP1-8

Date Exposed:

Describe Damage:

Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature:

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:

Entact ID: SP1-9

Date Exposed:

Describe Damage:

AE

~~Damage by bucket during excavation~~

Damaged by dozer during backfill

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature:

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-10

Date Exposed: _____

Describe Damage: _____

Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-11

Date Exposed: _____

Describe Damage: _____

AE

~~Damage by bucket during excavation~~

Damaged by dozer during backfill

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-12

Date Exposed: _____

Describe Damage: _____

AE

~~Damage by bucket during excavation~~

Damaged by dozer during backfill

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-13

Date Exposed: _____

Describe Damage: _____

Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-14

Date Exposed: _____

Describe Damage: _____

AE
~~Damage by bucket during excavation~~

Damaged by dozer during backfill

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: ~~AE~~ AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-15

Date Exposed: _____

Describe Damage: _____

Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-16

Date Exposed: _____

Describe Damage: _____

AE
~~Damage by bucket during excavation~~

Damaged by dozer during backfill

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-17

Date Exposed: _____

Describe Damage: _____

~~Damage by bucket during excavation~~ AE

Damaged by dozer during backfill

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-18

Date Exposed: _____

Describe Damage: Damage by bucked during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-19

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-20

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-21

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-22

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-23

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-24

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-25

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-26

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-27

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-28

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-29

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-30

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-31

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-32

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-33

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-34

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-37

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/13/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-38

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-41

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-42

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-43

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-44

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-1

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-2

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-3

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-5

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-6

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-7

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-8

Date Exposed: _____

Describe Damage: Damage by bucked during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-9

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-10

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-11

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-12

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-13

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-14

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-15

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-16

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-17

Date Exposed: _____

Describe Damage: Damage by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/11/14

Inspected by: AE

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-18

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: MS

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: 3/25/14

Date: [signature]

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-19

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: MS

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-20

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: MS

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-21

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: MS

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6P1-22

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: MS

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-1

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-2

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-3

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-4

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, repair

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-5

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-6

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-7

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation.

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-8

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-9

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-10

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-11

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-12

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 7P1-13

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8-P1-1

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-2

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-3

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-4

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-5

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-6

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-7

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-8

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-9

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-10

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-11

Date Exposed: _____

Describe Damage: _____

Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: MM

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-12

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-13

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-14

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-15

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-16

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-17

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-18

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-19

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-20

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-21

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-22

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-23

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-24

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-25

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-26

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

## Attachment 11:  Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 5, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| | | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | | | X | |
| | | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| | | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/05/14

SWPPP Observer: (G. Pfeiffer)
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, March 05, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Entact- The Western Exclusion Zone fencing on the former Old Dominion property requires maintenance, particularly the western face. |
| 2 | IA2Q4A1AL8, EHWG3RTMXR | Entact- The silt fence to the north of the CWTP requires maintenance- *Repeat*. ENR- The silt fence at SW corner of SA-6 North requires maintenance/re-installation. |
| 3 | IA2Q4A1AL8 | Entact- Warning fencing along southern perimeter of the former MUA settlement tank requires maintenance. |
| 4 | IA2Q4A1AL8 | Entact- The silt fence surrounding the former SES stockpile area requires maintenance/re-installation at locations on all four sides. |
| 5 | | |
| 6 | | |
| 7 | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 03/05/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Entact- Tighten fencing, re-install along the western perimeter. | 3-10-14 RAD |
| 2 | Entact- *Repeat Item.* Confirm proper installation buried fabric toe. ENR- Repair or replace. Confirm that fabric is toed-in. | 3-11-14 RAD |
| 3 | Entact- Orange construction fencing along the SA-6 North haul road is sagging/down. Re-install. | 3-10-14 RAD |
| 4 | Entact- Repair or replace silt fencing, confirming proper toed-in installation. | 3-11-14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 03/12/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 12, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/13/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Wednesday, March 12, 2014

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | A lubricant drums which is currently in use is not on a spill pallet or other form of secondary containment. |
| 2 | IA2Q4A1AL8 | The containment measures surrounding the western non-haz material staging area require maintenance. |
| 3 | IA2Q4A1AL8 | Ponded storm water should be pumped, treated and discharged to PVSC. |
| 4 | EHWG3RTMXR | **Repeat Item:** Silt fence at the southwestern corner of Study Area 6 North requires maintenance/repair. |
| 5 | IA2Q4A1AL8 | Fencing along the western perimeter of the former sedimentation basin must be modified/enhanced to mitigate a fall hazard of greater than 6 feet. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** G. Pfeiffer (Signature) **Date:** 03/13/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | All product drums are to be protected by some form of secondary containment. | 3-13-14 RAD |
| 2 | The fabric and liner has become detached from the bin blocks on the northern perimeter of the non-haz staging area. | 3-13-14 RAD |
| 3 | The fabric and liner has become detached from the bin blocks on the northern perimeter of the non-haz staging area. | 3-14-14 RAD |
| 4 | Surface water from the melting snow and ice has ponded on the former Teal property. Remove the ponded water from both sides of the sheet pile hydraulic barrier. | 3-14-14 RAD |
| 5 | Fencing along the western perimeter of the sed basin does not hinder access to a fall hazard of greater than 6 feet. Reposition the existing or install additional fencing. | 3-14-14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** (Signature) **Date:** 03/17/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 19, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/19/14

SWPPP Observer: _____ (G. PFEIFER)
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, March 19, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | **Repeat Item:** Ponded storm water on the former Degen Oil property requires pumping to the Construction Water Treatment Plant. |
| 2 | EHWG3RTMXR | **Repeat Item:** Silt fence at the southwestern corner of Study Area 6 North requires maintenance/repair ENR |
| 3 | IA2Q4A1AL8 | Silt fence surrounding the sediment remedy stockpile area on SA-7 requires repair. |
| 4 | IA2Q4A1AL8 | Filter baskets in two storm water catch basins on the eastern SA-7 perimeter haul road require replacement. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 03/19/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | **REPEAT ITEM** Surface water from storm events has ponded on the former Teal property. Remove the ponded water. | 3-24-14 RAD |
| 2 | REPEAT ITEM The silt fence along a section of the Hackensack riverfront requires repair. | ENR |
| 3 | The silt fence surrounding the sed. remedy stockpile area has sustained wind damage. | 3-24-14 RAD |
| 4 | Filter fabric in two catch basins on the eastern raceway is blinded. Replace. | 3-24-14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 03/25/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 26, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☑ Other Wind
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 1 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/27/14

SWPPP Observer: D. Pfeiffer (D. Pfeiffer)
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Wednesday, March 26, 2014

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | **Entact-** Material spilled over containment on southern edge of non-haz stockpile area. |
| 2 | IA2Q4A1AL8 | **Entact-** Ponded water on haul road at northwest corner of haz containment area. |
| 3 | EHWG3RTMXR | **ENRC- Repeat** Silt fence in southwest corner of Study Area 6 North requires maintenance. |
| 4 | IA2Q4A1AL8 | **Entact-** Silt fence surrounding the sediment remedy stockpile area requires maintenance. Blown down in today's high winds. |
| 5 | IA2Q4A1AL8 | **Entact-** Windscreen on the perimeter fence bordering the JCIA property requires maintenance/repair. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 03/27/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Material to be shoveled back into containment area. Edges of stockpiles should not extend more than 1/2 way up the containment structures. | 3-28-14 RAD |
| 2 | Stone should be placed in the areas where ponded water occurs. | 3-28-14 RAD |
| 3 | Repeat Item- Repair and maintain silt fence until such time as the disturbed soil in the area is stabilized. | ENR |
| 4 | Silt fence to be maintained until the permit is closed out. Stock piles being removed | 3-31-14 RAD |
| 5 | Re-secure the windscreen material to the perimeter fence. | 3-28-14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 04/01/14

**Attachment 12: 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (February 2014)**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

March 18, 2014

Mr. Brian Salvo
Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: February 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

Dear Mr. Salvo:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the February 2014 Surface Water Discharge Monitoring Report for Outfall 001A. This is the last DMR for Permit NJ0156311.

Please be advised that the Groundwater Treatment Plant's last day of discharge was February 28, 2014. The Plant is currently being demolished. A new Groundwater Treatment Plant has been built and is treating groundwater for discharge to the Passaic Valley Sewerage Commission treatment plant.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Scott Serino - GWTT
Frank Schroyer - Parsons
Angle Trujillo, Operator, Evoqua

New Jersey Department of Environmental Protection
Division of Water Quality

PI 234822

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 2 | 1 | 2014 | To | 2 | 28 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☐ **No Discharge this Monitoring Period** ☒ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J Morris, Remediation Director — —

**NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** **GRADE AND REGISTRY NUMBER (IF APPLICABLE)**

John J Morris 3/14/2014 973.455.4003

**SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** **DATE** **AREA CODE/PHONE NUMBER**

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J Morris, Remediation Director John J Morris 3/14/2014 973.455.4003

**NAME AND TITLE** **SIGNATURE** **DATE** **AREA CODE/PHONE NUMBER**

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 2/1/2014 TO 2/28/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | 44,372 | 106,632 | GPD | ****** | ****** | ****** | ****** | 0 | Continuous | Meter |
| | PERMIT REQUIREMENT | REPORT<br>01MOAV | REPORT<br>01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | 7.76 | ****** | 7.76 | SU | 0 | 1/Month | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0<br>01MOMN | ****** | 9.0<br>01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | CODE N * | ****** | ****** | %EFFL | 0 | 1/Year | Compos |
| | PERMIT REQUIREMENT | ****** | ****** | | 50<br>01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | CODE N * | ****** | ****** | %EFFL | 0 | 1/Year | Compos |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT<br>01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | ND, <5.0 | ND, <5.0 | MG/L | 0 | 1/Month | GRAB |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10<br>01MOAV | 15<br>01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 4.7 | 4.7 | MG/L | 0 | 1/Month | GRAB |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 20<br>01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

* See attached letters

Pre-Print Creation Date: 1/1/2014

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 2/1/2014 TO 2/28/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | CODE N | CODE N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | CODE N | CODE N | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | CODE N | CODE N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | CODE N | CODE N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | CODE N | CODE N | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | 31.0 | 31.0 | UG/L | 0 | 1/Month | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 1/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 2/1/2014 TO 2/28/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | 0 | 1/Quarter | Comp 24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 0.025 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.8 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 46 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | 0 | 1/Quarter | Grab |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 54 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 1/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 2/1/2014 TO 2/28/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | 12028 | 03547 | - | - | - | - | - | - | - | - |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 1/1/2014*

## Graham, Stephanie

**From:** Fahy, Helen
**Sent:** Monday, March 10, 2014 6:32 PM
**To:** Graham, Stephanie
**Subject:** SA7; WWTP Bioassay Lab Failure

Stephanie,
We need to add this e-mail to the February DMR, please.
Thank you,

Helen Fahy
Fahy Associates
Remediation Manager
c/o Honeywell
101 Columbia Rd
Morristown, NJ 07962
Tel: 973-455-2989
Cell: 814-571-4912
<mailto:helen.fahy@honeywell.com>

---

**From:** Schroyer, Franklin [mailto:Franklin.Schroyer@parsons.com]
**Sent:** Tuesday, February 11, 2014 1:45 PM
**To:** Fahy, Helen
**Cc:** Bills, Stuart B; Kessler, Timothy; Mojka, John
**Subject:** SA7; WWTP Bioassay Lab Failure

Helen,

I was informed about noon today by QC Laboratories' manager Robert Martino that their Southampton, PA lab was without power and phone for several days last week due to extreme storm conditions. Consequently they lost all bioassays then in progress, including ours.

We will be getting an official notification of the failure from QC in the next several days.

Regards,
Frank
(973) 722-5240

QC LABORATORIES

February 10th, 2014

Dear Valued Customer,

QC Laboratories was without power for approximately between February 4th and 6th due to the ice storm that took out power lines feeding our laboratory.

Although generators were employed we were unable to maintain the required test condition specified in EPA and state regulations. It was decided to invalidate all studies running that week. Although a costly decision, it was the only one we could make that would ensure that no client would be negatively impacted.

All studies affected have been or are in the process of being rescheduled. It was been a tough winter and we certainly appreciate your patience in this matter.

Regards,
Robert Martino
Director, Aquatic Toxicology and Sciences

1205 Industrial Blvd., P.O. Box 514, Southampton, PA 18966-0514 · Toll Free: 800-289-8378 · Phone: 215-355-3900 · Fax: 215-355-7231 · www.qclaboratories.com

# Honeywell Flume Flow Daily Totals

| | |
|---|---|
| **Year:** | **2014** |
| **Month:** | **February** |

| Day | Meter Reading | Flows (gpm) | Volume Treated (gpd) | Run Time (hr/day) |
|---|---|---|---|---|
| 2/1/2014 | 345885178 | 168.06 | 90,754 | 9 |
| 2/2/2014 | 345975932 | 173.57 | 83,312 | 8 |
| 2/3/2014 | 346059244 | 162.58 | 87,792 | 9 |
| 2/4/2014 | 346147036 | 177.72 | 106,632 | 10 |
| 2/5/2014 | 346253668 | 171.58 | 82,360 | 8 |
| 2/6/2014 | 346336028 | 149.11 | 89,464 | 10 |
| 2/7/2014 | 346425492 | 171.06 | 82,110 | 8 |
| 2/8/2014 | 346507602 | 152.06 | 82,110 | 9 |
| 2/9/2014 | 346589712 | 153.03 | 73,452 | 8 |
| 2/10/2014 | 346663164 | 143.12 | 34,348 | 4 |
| 2/11/2014 | 346697512 | 119.47 | 21,504 | 3 |
| 2/12/2014 | 346719016 | 147.00 | 26,460 | 3 |
| 2/13/2014 | 346745476 | 118.53 | 21,336 | 3 |
| 2/14/2014 | 346766812 | 164.90 | 39,576 | 4 |
| 2/15/2014 | 346806388 | 89.58 | 16,124 | 3 |
| 2/16/2014 | 346822512 | 100.47 | 18,084 | 3 |
| 2/17/2014 | 346840596 | 85.98 | 15,476 | 3 |
| 2/18/2014 | 346856072 | 66.84 | 12,032 | 3 |
| 2/19/2014 | 346868104 | 109.96 | 19,792 | 3 |
| 2/20/2014 | 346887896 | 103.16 | 18,568 | 3 |
| 2/21/2014 | 346906464 | 106.43 | 57,472 | 9 |
| 2/22/2014 | 346963936 | 147.30 | 17,676 | 2 |
| 2/23/2014 | 346981612 | 132.73 | 23,892 | 3 |
| 2/24/2014 | 347005504 | 181.37 | 43,528 | 4 |
| 2/25/2014 | 347049032 | 123.70 | 29,688 | 4 |
| 2/26/2014 | 347078720 | 104.98 | 18,896 | 3 |
| 2/27/2014 | 347097616 | 166.58 | 19,216 | 3 |
| 2/28/2014 | 347127600 | 59.82 | 10,768 | 3 |
| | | | | |
| | | | | |
| **Totals** | 1242422 | | | 145 |
| **Average** | | 133.95 | 44,372 | |
| **Maximum** | | | 106,632 | |

Arcon Ltd (NJ Lab Cert. # 03547)
90 US Highway Route 130
Bordentown, NJ 08505
(609)-298-0770, Fax: (609-)291-8386

# Chain Of Custody / Analysis Request

COC #:
Lab Use Only
Lab Proj #
Lab ID 03547
PAGE 1 of 1
Job No.

Privileged & Confidential: Y
PWD ID:
Site Name: Honeywell
Location of Site: GWTP
Sampler:
PO #:
Analysis Turnaround Time:
Standard -
Rush Charges Authorized for -
2 weeks -
1 week -
Next Day -

Client Contact: (name, co., address)
Helen Fahy
101 Columbia Road
Morristown, NJ 07961
Helen.Fahy@honeywell.com

Hardcopy Report to: Helen Fahy
Invoice to: Helen Fahy

Preservative: 0 0 0 0 0 — pH

| | Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Grab/Composite | Field Filtered Sample # | Units | mg/kg | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | WTP | | | EFFLUENT | 2/11/14 | 0736 | GRAB | WATER | pH | | | | | X | |
| 2 | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | |

pH @ 7.76 @ 14.9 °C

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by | Company: Arcon | Received by | Company | Condition | Custody Seals Intact | | |
| | Date/Time: 2/11/14 0736 | | Date/Time | Cooler Temp. | | | |
| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact | | |
| | Date/Time | | Date/Time | Cooler Temp. | | | |

Preservatives: 0 = None; 1 = HCl; 2 = HNO3; 3 = H2SO4; 4 = NaOH; 5 = Zn Acetate; 6 = MeOH; 7 = NaHSO4; 8 = Other (specify)

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 3 OF 25**

- **2014 Monthly Reports Part 3**

**5/14/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

May 14, 2014

***Via Express Mail***

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-04**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from April 1 – April 30, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: April 2014 SA-6/7 Combined Monthly Progress Report No. 2014-04

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-04

**Project SA-6 & 7 Remediation**

# April 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 04/09/14 | Integrated Annual Groundwater Performance Report for 2013<br>Study Areas 5, 6, and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/14/14 | Deflection of Barrier Wall<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/15/14 | NJPDES Permit NJ0156311: March 2014 Surface Water Discharge Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | New Jersey Department of Environmental Protection<br>Division of Water Quality |
| 04/15/14 | NJDEP Division of Water Quality New Jersey Pollutant Request for Permit Revocation<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | New Jersey Department of Environmental Protection |
| 04/15/14 | Discharge of Tannin Construction Water<br>Customer ID# 31630005-1<br>Study Area 7, Jersey City, NJ | Andy Caltagirone<br>PVSC |
| 04/15/14 | Bayfront Redevelopment at 525 & 575 Route 440, Jersey City MR 1 and MR 2<br>Permit ID# 31630016<br>*(see **Attachment 12**)* | Andy Caltagirone<br>PVSC |
| 04/16/14 | Combined Monthly Progress Report No. 2014-03<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/17/14 | Response to Comments Provided by Plaintiffs, April 11, 2004 - Excavation of Cells 44 Through 52<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/22/14 | Special Master All Hands Meeting | N/A |
| 04/23/14 | Response to Comments Provided by Plaintiffs, April 17, 2014 - Design Change Bulletin (DCB) – Trench Layout for Contingent Groundwater Extraction System<br>Study Area 6 (SA-6) North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/24/14 | Response to Comments Provided by Plaintiffs, March 13, 2014 - Revised In-Situ Work Plan for Treatment Area 10<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/24/14 | Response to Comments Provided by Plaintiffs, April 11, 2004 - Standard Operating Procedure for Confirmation of Excavation Limits | Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| | Study Area 6 South, Jersey City, NJ | |
| 04/29/14 | Response to Comments Provided by Dr. Ben Ross April 8, 2014 - Revised Integrated Groundwater Sampling and Analysis Plan Study Areas 5, 6, and 7, Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |
| 04/30/14 | Recommendations Regarding Bedrock Monitoring Wells 90-MW-18BR and KP-MW-6BR Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |
| 04/30/14 | Response to Comments Provided by Plaintiffs, April 17, 2014 - Design Change Bulletin (DCB) – Surcharge Plan Design Change Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 04/06/014 | 04/13/2014 | 04/20/2014 | 04/27/2014 |
| **Construction Management (AMEC)** | 9 | 10 | 10 | 9 |
| **Engineering (AMEC)** | 2 | 2 | 2 | 2 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 42 | 40 | 35 | 40 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 1 |
| **OSC (-80 Kellogg Demolition** | 0 | 0 | 4 | 5 |
| **ENR (SA-6N GWTP Utilities)** | 0 | 0 | 0 | 0 |
| **BCA (SA-6N Building Construction)** | 0 | 0 | 0 | 0 |
| **Siemens** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 1 | 0 | 0 | 0 |
| **HPS (SA-6N GWTP Process Controls)** | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 0 | 0 |
| **TOTAL** | **60** | **58** | **57** | **62** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Conducted quarterly LTMP groundwater level measurement round.

- Conducted S-3 Injection/Mass Removal Event No.13 in well 088-IW-03.
- Continued new Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Completed installation of the temporary SA-6 North Surcharge area dewatering system.
- Continued well abandonment activities in accordance with approved Monitoring Well Abandonment Plan.
- Continued former 80 Kellogg St GWTP and truck wash demolition activities.
- Collected April PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Based upon a final inspection the Hudson, Essex and Passaic Soil Conservation District issued a Report of Compliance on 4/21/2014 for the SA-7 Sediment Remediation Project.
- Non-chromium activities, ARCADIS continues to work with NJDEP on the modification to the existing NJDEP-Discharge to Groundwater Permit by Rule for additional Enhanced Anaerobic in-situ bioremediation (EAISB) injections planned for JCMUA and JCDPW UST Areas.

## C. SA-6 N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received fully compliant monthly lab results for the GWTP effluent PVSC sampling conducted on March 28, 2014.
- Changed out sludge box from the ground water treatment plant.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 04/06/2014 | 04/13/2014 | 04/20/2014 | 04/27/2014 |
| Avg. Gallons Treated & Discharged (per day) | 78,664 | 78,458 | 77,874 | 78,925 |
| Average Flow (gpm) for Operating Period | 55 | 54 | 54 | 55 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP InfluentTanks (gal.) | 11,520 | 12,240 | 11,400 | 9,293 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in Cells 56 through 59 and Cells 152A through 135A and 146B through 142B
- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.

- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 15.92 | 15.92 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 195 | 21.69 | 4,250.24 |
| **Entact/ Montecalvo** | 30 cubic Yard Roll off | Bayshore Recycling | NA | Creosote Debris (non- haz) | 2 | 11.58 | 23.17 |
| **Entact/Tilcon** | Tri-axle Dump | Tilcon, Mt. Hope | NA | Asphalt | 37 | 24 | 890.20 |
| **OSC** | 30yd Roll Off | 375 RT 1-9 South Jersey | IWS | C&D | 33 | TBD | TBD |
| **OSC** | 40yd Roll Off | Cinelli JC | Cinelli | Light Iron | 21 | TBD | TBD |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 146B-142B, 137A-135A |
| **Excavation Completed** | Cell Number(s) 55 through 58, 152A-140A<br>Volume Excavated - Total for Reporting Period: 9,607CY/ Total to Date:51,199 CY |
| **Backfill in Progress** | Cell Number(s) 1 through 58, 152A-140A |

### 3. BACKFILL MATERIALS USED

| Source | (Week Ending) | | | |
|---|---|---|---|---|
| | 04/6/2014 | 04/13/2014 | 04/20/2014 | 04/27/2014 |
| <20ppm re-use, CY | 0 | 0 | 0 | 1,598 |
| Weldon, Import-Tons | 4,592.86 | 5,195.18 | 6645.69 | 2,082.82 |
| Tilcon, Import-Tons | 0 | 0 | 50.61 | 308.24 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Instrumentation Installation ~85% complete. Instrumentation installation scheduled for completion in May 2014. No Surcharge initiated.
- Area 2S: Instrumentation Installation ~75% complete. Completion of instrument installation deferred pending completion of 80 Kellogg demolition activities. No Surcharge initiated.

- Area 3S: Instrumentation Installation 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. No Surcharge initiated.
- Area 1N: Instrumentation Installation ~100% complete. Placement of surcharge material initiated on April 8, 2014.
- Area 2N: No instrumentation installed. Initial surcharge instrument data to be submitted under separate cover.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Two (2) pairs driven on the hydraulic barrier wall at Sta 25+65 on SA-6 South.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue placement of surcharge materials in SA-6N Area 1N.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 135-120.

- Continue stockpiling of potential <20 mg/kg and >1,000 mg/kg hexavalent chromium soils for sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Complete demolition activities associated with the former 80 Kellogg Ground Water Treatment Plant and Truck Wash Building.
- Continue SWPPP inspections.
- Complete PVSC compliance sampling.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-1)
   - SA-6 South Deep Well Data (DW-2)
   - SA-6 South Deep Well Data (DW-5)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. Groundwater Quality Data Surcharge Monitoring Update
   - Summary of Groundwater Quality Data from GWET Wells
   - Quarterly Water Wells
   - Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells
9. Surcharge Monitoring Update
   - Instrumentation Location Plan 1N
   - Instrumentation Location Plan 1S
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Deflection Along Open Excavation
    - Sheet Pile Repair Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (March 2014)
    - Request to NJDEP re Permit NJG0156311 Permit Revocation
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (March 2014)

## Attachment 1:  Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Mon 5/5/14

Task  Milestone  Summary  Critical

## Attachment 2:  Site Photographs




**Site Photograph 1:** Backfill is placed at the western end of the Kellogg St. excavation.




**Site Photograph 2:** Contractor breaks up concrete slab prior to excavation along Kellogg St.




**Site Photograph 3:** Contractor continues to backfill eastern area of excavation at Kellogg St.




**Site Photograph 4:** Contractor excavates against the temporary sheet pile along western portion of Kellogg St.




**Site Photograph 5:** Contractor loads soils for use as surcharge material on JC property.




**Site Photograph 6:** Contractor places surcharge soil over white geotextile fabric on JC property.





**Site Photograph 7:** Demolition of the 80 Kellogg building is started.


## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points)
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of May 1, 2014

April 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill







LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM O EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE
- LIMIT OF EXCAVATION AREA

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 04-07-14 TO 04-10-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LIMIT OF ANTICIPATED STRATUM D EXPOSURE PER DESIGN (TYP)

-3.8 BOE ELEVATION AT EDGE OF STRATUM D PER THIRD PARTY SURVEY (TYP)

0 5 10 20
SCALE IN FEET

Prepared/Date: TDD 4/22/14
Checked/Date: SGS 4/22/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | SA-6 SOUTH<br>STRATUM D CELLS 53 THRU 58<br>FIGURE 1 |

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7* | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684138.4 | 603182.8 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5* | Stratum D Reached |
| 684146.2 | 603165.7 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6* | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1.0 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2.0 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684221.8 | 603013.0 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7* | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0* | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684272.8 | 602944.8 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9* | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9* | Target Elevation Reached |
| 684293.5 | 602922.8 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9* | Stratum D Reached |
| 684227.9 | 602869.9 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1* | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4* | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684273.8 | 602864.2 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3* | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684285.9 | 602856.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4* | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684305.4 | 602833.3 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1* | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684392.6 | 602878.7 | -2.8 | 124-SB-123 | 30 | 1/23/2014 | -2.4 | Stratum D Reached |
| 684311.9 | 602821.5 | 3.5 | 124-SB-021R | 30 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684381.0 | 602861.0 | -2.3 | 124-SB-110 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684362.9 | 602837.4 | 3.2 | 124-SB-124 | 31 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684340.0 | 602818.0 | 3.2 | 124-SB-109 | 31 | 1/23/2014 | -1.6 | Stratum D Reached |
| 684318.6 | 602806.8 | 3.5 | 124-SB-021R | 31 | 1/23/2014 | 1.9* | Target Elevation Reached |
| 684416.9 | 602861.1 | -2.8 | 124-SB-029 | 32 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684335.2 | 602800.6 | 3.5 | 124-SB-021R | 32 | 1/30/2014 | 2.0* | Target Elevation Reached |
| 684411.9 | 602839.0 | -2.2 | 124-SB-092 | 33 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684348.7 | 602791.2 | 3.5 | 124-SB-021R | 33 | 1/30/2014 | 2.0* | Target Elevation Reached |
| 684372.0 | 602797.0 | 2.6 | 124-PT-14 | 34 | 2/4/2014 | -1.9 | Stratum D Reached |
| 684355.8 | 602781.0 | 3.5 | 124-SB-021R | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684458.4 | 602838.3 | -2.3 | 124-SB-027 | 35 | 2/4/2014 | -2.7 | Stratum D Reached |
| 684367.5 | 602768.5 | 3.5 | 124-SB-021R | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684440.8 | 602806.0 | -2.8 | 124-SB-091 | 36 | 2/11/2014 | -2.7 | Stratum D Reached |
| 684371.2 | 602753.4 | 3.5 | 124-SB-021R | 36 | 2/11/2014 | 2.1* | Target Elevation Reached |
| 684394.0 | 602777.3 | 4.7 | 124-SB-117A | 36 | 2/11/2014 | -1.6 | Stratum D Reached |
| 684473.9 | 602819.4 | -2.8 | 124-SB-026 | 37 | 2/11/2014 | -2.9 | Stratum D Reached |
| 684430.7 | 602784.0 | -1.3 | 124-SB-023 | 37 | 2/11/2014 | -3.6 | Stratum D Reached |
| 684412.9 | 602766.1 | 2.0 | 124-SB-121A | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684400.0 | 602762.0 | -0.1 | 124-PT-04 | 37 | 2/11/2014 | -2.2 | Stratum D Reached |
| 684380.7 | 602742.6 | 3.5 | 124-SB-021R | 37 | 2/11/2014 | 2.1* | Target Elevation Reached |
| 684463.2 | 602783.7 | -2.3 | 124-SB-136 | 38 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684397.4 | 602736.2 | 3.5 | 124-SB-021R | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684448.4 | 602763.0 | 4.7 | 124-SB-022 | 39 | 2/20/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684505.3 | 602786.0 | -2.8 | 124-SB-024 | 40 | 2/27/2014 | -3.4 | Stratum D Reached |
| 684482.9 | 602770.8 | -3.3 | 124-SB-025 | 40 | 2/27/2014 | -3.0 | Stratum D Reached |
| 684430.0 | 602730.0 | 1.7 | 124-PT-03 | 40 | 2/27/2014 | 0.0 | Target Elevation Reached |
| 684468.5 | 602745.2 | 1.8 | 124-SB-066 | 40 | 2/27/2014 | -2.2 | Stratum D Reached |
| 684491.3 | 602754.6 | -2.3 | 124-SB-136R | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | 125-SB-029R | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684524.5 | 602765.0 | -3.5 | 125-SB-017 | 42 | 3/5/2014 | -3.1 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | 125-SB-029R | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684513.0 | 602736.0 | -4.3 | 125-PT-22 | 43 | 3/5/2014 | -3.5 | Stratum D Reached |
| 684496.0 | 602718.9 | -1.7 | 125-SB-086 | 43 | 3/5/2014 | -2.6 | Stratum D Reached |
| 684473.0 | 602698.0 | 0.3 | 125-PT-21 | 43 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684446.6 | 602677.9 | 0.5 | 125-SB-028 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684543.1 | 602743.1 | -3.9 | 125-SB-018 | 44 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684431.0 | 602654.0 | 0.7 | 125-PT-20 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684467.4 | 602652.6 | 1.0 | 125-SB-027 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684495.1 | 602674.9 | 0.4 | 125-SB-025 | 45 | 3/11/2014 | 0.3 | Target Elevation Reached |
| 684512.8 | 602689.3 | 0.3 | 125-SB-024 | 45 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684561.9 | 602720.2 | -3.3 | 125-SB-019 | 46 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684543.0 | 602699.0 | -4.7 | 125-PT-17 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684539.5 | 602702.1 | -3.7 | 125-SB-022 | 46 | 3/17/2014 | -3.3 | Stratum D Reached |
| 684503.0 | 602661.0 | 1.0 | 125-PT-16 | 46 | 3/17/2014 | -2.9 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | 125-SB-029R | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.3 | 124-SB-136R | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684481.2 | 602625.7 | 1.7 | 125-SB-089 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684488.7 | 602626.5 | 1.3 | 125-SB-026 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684581.0 | 602697.1 | -3.4 | 125-SB-020 | 48 | 3/20/2014 | -2.9 | Stratum D Reached |
| 684558.6 | 602678.9 | -4.0 | 125-SB-021 | 48 | 3/20/2014 | -3.4 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | 125-SB-029R | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |
| 684545.6 | 602650.2 | -3.3 | 125-SB-038 | 49 | 3/20/2014 | -3.3 | Stratum D Reached |
| 684597.3 | 602676.1 | -3.5 | 125-SB-037 | 49 | 3/25/2014 | -2.6 | Stratum D Reached |
| 684574.9 | 602657.9 | -3.4 | 125-SB-039 | 49 | 3/25/2014 | -3.3 | Stratum D Reached |
| 684535.1 | 602625.9 | 0.6 | 125-SB-032 | 49 | 3/25/2014 | -3.3 | Stratum D Reached |
| 684516.6 | 602611.2 | 1.1 | 125-SB-031 | 49 | 3/25/2014 | 0.1 | Target Elevation Reached |
| 684511.6 | 602592.1 | -1.0 | 125-SB-090 | 50 | 3/25/2014 | -1.3 | Target Elevation Reached |
| 684526.0 | 602608.3 | 0.4 | 125-SB-029R | 50 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684574.8 | 602647.4 | -2.3 | 124-SB-136R | 50 | 3/25/2014 | -3.6 | Stratum D Reached |
| 684514.6 | 602580.4 | -1.0 | 125-SB-090R | 51 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684535.3 | 602597.8 | 0.4 | 125-SB-029R | 51 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684584.1 | 602636.9 | -2.3 | 124-SB-136R | 51 | 3/28/2014 | -3.0 | Stratum D Reached |
| 684619.0 | 602648.6 | -1.5 | 125-SB-035 | 52 | 3/28/2014 | -2.5 | Stratum D Reached |

| 684596.6 | 602630.5 | -3.6 | 125-SB-034 | 52 | 3/28/2014 | -3.0 | Stratum D Reached |
|---|---|---|---|---|---|---|---|
| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684574.5 | 602612.8 | 0.7 | 125-SB-033 | 52 | 3/28/2014 | -3.4 | Stratum D Reached |
| 684556.8 | 602598.4 | 0.8 | 125-SB-030 | 52 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684538.3 | 602583.7 | 0.4 | 125-SB-029 | 52 | 3/28/2014 | 0.4 | Target Elevation Reached |
| 684523.8 | 602562.3 | -0.9 | 125-SB-078 | 52 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684579.0 | 602588.0 | 0.9 | 125-SB-009 | 53 | 4/1/2014 | -2.2 | Stratum D Reached |
| 684557.0 | 602576.5 | 0.4 | 125-SB-029R | 53 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684533.6 | 602556.0 | -1.0 | 125-SB-090R | 53 | 4/1/2014 | -1.4 | Target Elevation Reached |
| 684620.4 | 602605.9 | 0.4 | 125-SB-065 | 54 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684641.2 | 602623.7 | -2.1 | 125-SB-070 | 54 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684597.0 | 602588.0 | -2.7 | 125-SB-009A | 54 | 4/1/2014 | -2.2 | Stratum D Reached |
| 684573.7 | 602577.0 | 0.7 | 125-SB-044 | 54 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684557.6 | 602564.1 | 1.2 | 125-SB-050 | 54 | 4/1/2014 | 0.2 | Target Elevation Reached |
| 684632.0 | 602597.9 | -1.4 | 140-SB-083R | 55 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684576.2 | 602552.1 | 0.4 | 125-SB-029R | 55 | 4/4/2014 | 0.3 | Target Elevation Reached |
| 684664.6 | 602597.6 | -3.3 | 125-SB-071 | 56 | 4/4/2014 | -2.5 | Stratum D Reached |
| 684642.2 | 602579.5 | 0.2 | 125-SB-053 | 56 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684601.1 | 602556.0 | 3.1 | 125-SB-045 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684583.0 | 602540.8 | 0.6 | 125-SB-066 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684576.6 | 602529.9 | 2.1 | 125-SB-069 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684574.5 | 602511.9 | 2.1 | 125-SB-069R | 57 | 4/9/2014 | 1.6 | Target Elevation Reached |
| 684606.0 | 602536.9 | 0.4 | 125-SB-029R | 57 | 4/9/2014 | 0.1 | Target Elevation Reached |
| 684636.4 | 602554.1 | -2.4 | 125-SB-052 | 57 | 4/9/2014 | -1.2 | Stratum D Reached |
| 684591.8 | 602507.6 | 2.1 | 125-SB-069R | 58 | 4/9/2014 | 1.5 | Target Elevation Reached |
| 684679.9 | 602578.9 | -2.3 | 125-SB-062 | 58 | 4/9/2014 | -2.6 | Stratum D Reached |
| 684620.0 | 602524.0 | 0.6 | 125-SB-007 | 58 | 4/9/2014 | 0.2 | Target Elevation Reached |
| 684600.1 | 602523.2 | 0.6 | 125-SB-049 | 58 | 4/9/2014 | -0.1 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |
| 684373.5 | 602871.7 | -2.5 | C-30 | 30 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684311.9 | 602821.5 | 2.1 | C-30-1 | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684384.9 | 602861.2 | -2.5 | C-31 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684318.6 | 602806.8 | 2.1 | C-31-1 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684383.8 | 602841.5 | -2.5 | C-32 | 32 | 1/30/2014 | -1.8 | Stratum D Reached |
| 684335.2 | 602800.6 | 2.1 | C-32-1 | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684393.5 | 602830.6 | -2.5 | C-33 | 33 | 1/30/2014 | -1.9 | Stratum D Reached |
| 684348.7 | 602791.2 | 2.1 | C-33-1 | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684412.7 | 602824.5 | -2.5 | C-34 | 34 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684355.8 | 602781.0 | 2.1 | C-34-1 | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684422.4 | 602815.2 | -2.5 | C-35 | 35 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684367.5 | 602768.5 | 2.1 | C-35-1 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684432.1 | 602801.8 | -2.5 | C-36 | 36 | 2/11/2014 | -2.4 | Stratum D Reached |
| 684371.2 | 602753.4 | 2.1 | C-36-1 | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684440.7 | 602791.6 | -2.5 | C-37 | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684380.7 | 602742.6 | 2.1 | C-37-1 | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684460.4 | 602787.7 | -2.5 | C-38 | 38 | 2/20/2014 | -2.8 | Stratum D Reached |
| 684397.4 | 602736.2 | 2.1 | C-38-1 | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684471.9 | 602777.2 | -2.5 | C-39 | 39 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684416.4 | 602732.1 | 2.1 | C-39-1 | 39 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684481.8 | 602765.6 | -2.5 | C-40 | 40 | 2/27/2014 | -3.1 | Stratum D Reached |
| 684427.0 | 602721.5 | 0.4 | C-40-1 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684491.3 | 602754.6 | -2.5 | C-41 | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | C-41-1 | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684496.7 | 602740.4 | -2.5 | C-42 | 42 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | C-42-1 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684507.5 | 602729.5 | -2.5 | C-43 | 43 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684447.1 | 602679.0 | 0.4 | C-43-1 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684524.2 | 602722.2 | -2.5 | C-44 | 44 | 3/11/2014 | -3.5 | Stratum D Reached |
| 684454.3 | 602665.7 | 0.4 | C-44-1 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684536.0 | 602714.2 | -2.5 | C-45 | 45 | 3/11/2014 | -3.2 | Stratum D Reached |
| 684464.6 | 602655.3 | 0.4 | C-45-1 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684535.1 | 602693.1 | -2.5 | C-46 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | C-46-1 | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.5 | C-47 | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684483.8 | 602632.5 | 0.4 | C-47-1 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684551.5 | 602667.8 | -2.5 | C-48 | 48 | 3/20/2014 | -3.0 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | C-48-1 | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |
| 684564.6 | 602658.9 | -2.5 | C-49 | 49 | 3/25/2014 | -3.0 | Stratum D Reached |
| 684501.1 | 602607.9 | 0.4 | C-49-1 | 49 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684574.8 | 602647.4 | -2.5 | C-50 | 50 | 3/25/2014 | -3.6 | Stratum D Reached |
| 684526.0 | 602608.3 | 0.4 | C-50-1 | 50 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684507.7 | 602591.7 | -1.2 | C-50-2 | 50 | 3/25/2014 | -1.3 | Target Elevation Reached |
| 684584.1 | 602636.9 | -2.5 | C-51 | 51 | 3/28/2014 | -3.0 | Stratum D Reached |
| 684535.3 | 602597.8 | 0.4 | C-51-1 | 51 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684514.6 | 602580.4 | -1.2 | C-51-2 | 51 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684596.7 | 602626.3 | -2.5 | C-52 | 52 | 3/28/2014 | -2.9 | Stratum D Reached |
| 684547.0 | 602587.9 | 0.4 | C-52-1 | 52 | 3/28/2014 | 0.2 | Target Elevation Reached |
| 684524.8 | 602569.7 | -1.2 | C-52-2 | 52 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684602.1 | 602612.0 | -2.5 | C-53 | 53 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684557.0 | 602576.5 | 0.4 | C-53-1 | 53 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684533.6 | 602556.0 | -1.2 | C-53-2 | 53 | 4/1/2014 | -1.4 | Target Elevation Reached |
| 684610.8 | 602599.7 | -2.5 | C-54 | 54 | 4/4/2014 | -2.0 | Stratum D Reached |
| 684560.2 | 602558.1 | 0.4 | C-54-1 | 54 | 4/4/2014 | 0.3 | Target Elevation Reached |
| 684632.0 | 602597.9 | -2.5 | C-55 | 55 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684576.2 | 602552.1 | 0.4 | C-55-1 | 55 | 4/4/2014 | 0.3 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684641.4 | 602586.6 | -2.5 | C-56 | 56 | 4/4/2014 | -2.5 | Stratum D Reached |
| 684586.1 | 602541.3 | 0.4 | C-56-1 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684656.7 | 602578.2 | -2.5 | C-57 | 57 | 4/9/2014 | -2.4 | Stratum D Reached |
| 684606.0 | 602536.9 | 0.4 | C-57-1 | 57 | 4/9/2014 | 0.1 | Target Elevation Reached |
| 684574.5 | 602511.9 | 2.1 | C-57-2 | 57 | 4/9/2014 | 1.6 | Target Elevation Reached |
| 684662.3 | 602565.2 | -2.5 | C-58 | 58 | 4/9/2014 | -2.7 | Stratum D Reached |
| 684616.2 | 602527.5 | 0.4 | C-58-1 | 58 | 4/9/2014 | 0.3 | Target Elevation Reached |
| 684591.8 | 602507.6 | 2.1 | C-58-2 | 58 | 4/9/2014 | 1.5 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

## SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0)

| Sidewall Target Coordinates | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 4.9 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684301.0 | 602795.0 | 2.6 | 124-SB-108 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684328.2 | 602790.2 | 3.3 | 124-SB-063 | 32 | 1/30/2014 | 1.8 | Target Elevation Reached |
| 684338.1 | 602786.6 | 4.7 | 124-SB-056 | 33 | 1/30/2014 | 1.7 | Target Elevation Reached |
| 684348.0 | 602746.0 | 3.4 | 124-PT-02 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684386.0 | 602707.0 | 3.3 | 124-PT-01 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684411.1 | 602714.2 | 3.9 | 124-SB-065 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684408.4 | 602664.2 | 2.2 | 125-SB-088 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684419.7 | 602644.6 | 1.8 | 125-SB-067 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684457.0 | 602620.0 | 1.1 | 125-PT-15 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684479.5 | 602597.5 | 3.7 | 125-SB-081 | 49 | 3/20/2014 | 0.1 | Target Elevation Reached |
| 684495.3 | 602579.6 | 0.8 | 125-SB-091 | 50 | 3/25/2014 | -1.4 | Target Elevation Reached |
| 684499.2 | 602575.0 | 2.3 | 125-SB-080 | 51 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684513.9 | 602557.6 | 0.6 | 125-SB-092 | 52 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684519.3 | 602551.3 | 2.5 | 125-SB-079 | 53 | 4/1/2014 | -1.5 | Target Elevation Reached |
| 684552.7 | 602504.6 | 3.5 | 125-SB-087 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 4/14/14

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 21.1 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 2 | BF-07 | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | 38 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | 39 | Stratum O | Bottom of excavation elevation - Stratum O | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | 40 | Stratum D | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | 42 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | 44 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | 46 | Stratum D | Bottom of excavartion elevation | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | 48 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | 50 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | 140 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.


Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 5 Tests per Acre**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-01 | | 684158.6 | 603152.4 | | | | | | | 6 | | | |
| | RF-02 | | 684190.6 | 603063.9 | | | | | | | 12 | | | |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | 25 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 44 | Weldon WC Screenings | Placed on Tye A Material | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 48 | Weldon WC Screenings | Against HB wall | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 5 Tests per Acre**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 54 | Weldon WC Screenings | Against HB | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | 152 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 151 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 151 | Weldon WC Screenings | | V5N |
| 3 | RF-39-04 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 151 | Weldon WC Screenings | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-1)
- SA-6 South Deep Well Data (DW-2)
- SA-6 South Deep Well Data (DW-5)

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 03/03/14 | 1 | 72 | 7,8,9,EPS | 66 | N/A | N/A | 12,100 | 1,211,753 | 2.8 | Flowmeter Frozen (Read by Gauging Tank) |
| 03/04/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 4,600 | 1,216,353 | 3.2 | |
| 03/05/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 3,900 | 1,220,253 | 2.7 | |
| 03/06/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 3,700 | 1,223,953 | 2.6 | |
| 03/07/14 | 1 | 24 | 7,8,9,EPS | 66 | N/A | N/A | 2,500 | 1,226,453 | 1.7 | |
| 03/10/14 | 1 | 72 | 7,8,9,EPS | 66 | N/A | N/A | 1,700 | 1,228,153 | 0.4 | |
| 03/11/14 | 1 | 24 | 7,8,9,EPS | 66 | 394858 | 394,948 | 90 | 1,228,243 | 0.1 | |
| 03/12/14 | 1 | 24 | 7,8,9,EPS | 66 | 394948 | 395,094 | 146 | 1,228,389 | 0.1 | Flowmeter Blockage Cleared and Reset |
| 03/14/14 | 1 | 24 | 7,8,9,EPS | 67 | 0 | 8,194 | 8,194 | 1,236,583 | 5.7 | |
| 03/17/14 | 1 | 72 | 8,9,EPS | 56 | 8,194 | 32,805 | 24,611 | 1,261,194 | 5.7 | |
| 03/18/14 | 1 | 24 | 8,9,EPS | 52 | 32,805 | 41,005 | 8,200 | 1,269,394 | 5.7 | |
| 03/19/14 | 1 | 24 | 8,9,EPS | 52 | 41,005 | 53,281 | 12,276 | 1,281,670 | 8.5 | |
| 03/20/14 | 1 | 24 | 8,9,EPS | 52 | 53,281 | 68,164 | 14,883 | 1,296,553 | 10.3 | |
| 03/21/14 | 1 | 24 | 8,9,EPS | 44 | 68,164 | 82,672 | 14,508 | 1,311,061 | 10.1 | |
| 03/24/14 | 1 | 72 | 9,EPS | 44 | 82,672 | 112,690 | 30,018 | 1,341,079 | 6.9 | |
| 03/25/14 | 1 | 24 | 9,EPS | 14 | 112,690 | 136,290 | 23,600 | 1,364,679 | 16.4 | |
| 03/26/14 | 1 | 24 | 9,EPS | 14 | 136,290 | 159,720 | 23,430 | 1,388,109 | 16.3 | |
| 03/27/14 | 1 | 24 | 9,EPS | 14 | 159,720 | 173,928 | 14,208 | 1,402,317 | 9.9 | |
| 03/28/14 | 1 | 24 | 9,EPS | 14 | 173,928 | 188,251 | 14,323 | 1,416,640 | 9.9 | |
| 03/31/14 | 1 | 72 | 9,EPS | 14 | 188,251 | 234,816 | 46,565 | 1,463,205 | 10.8 | |
| 04/01/14 | 1 | 24 | 9,EPS | 14 | 234,816 | 254,072 | 19,256 | 1,482,461 | 13.4 | |
| 04/02/14 | 1 | 24 | 9,EPS | 14 | 254,072 | 272,724 | 18,652 | 1,501,113 | 13.0 | |
| 04/03/14 | 1 | 24 | 9,EPS | 14 | 272,724 | 292,383 | 19,659 | 1,520,772 | 13.7 | |
| 04/04/14 | 1 | 24 | 9,EPS | 14 | 292,383 | 310,862 | 18,479 | 1,539,251 | 12.8 | |
| 04/07/14 | 1 | 72 | 9,EPS | 14 | 310,862 | 361,008 | 50,146 | 1,589,397 | 11.6 | |
| 04/08/14 | 1 | 24 | 9,EPS | 14 | 361,008 | 375,723 | 14,715 | 1,604,112 | 10.2 | |
| 04/09/14 | 1 | 24 | 9,EPS | 14 | 375,723 | 389,220 | 13,497 | 1,617,609 | 9.4 | |
| 04/10/14 | 1 | 24 | 9,EPS | 14 | 389,220 | 403,320 | 14,100 | 1,631,709 | 9.8 | |
| 04/11/14 | 1 | 24 | 9,EPS | 14 | 403,320 | 416,137 | 12,817 | 1,644,526 | 8.9 | |
| 04/14/14 | 1 | 72 | 9,EPS | 14 | 416,137 | 453,580 | 37,443 | 1,681,969 | 8.7 | |
| 04/15/14 | 1 | 24 | 9,EPS | 14 | 453,580 | 464,088 | 10,508 | 1,692,477 | 7.3 | |
| 04/16/14 | 1 | 24 | 9,EPS | 14 | 464,088 | 473,709 | 9,621 | 1,702,098 | 6.7 | |
| 04/17/14 | 1 | 24 | 9,EPS | 14 | 473,709 | 484,453 | 10,744 | 1,712,842 | 7.5 | |
| 04/18/14 | 1 | 24 | 9,EPS | 14 | 484,453 | 492,855 | 8,402 | 1,721,244 | 5.8 | |
| 04/18/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | N/A | N/A | 21,000 | 1,742,244 | 14.6 | Flow meter not installed. Volumes based on tank gauging |
| 04/21/14 | 1 | 72 | 9,EPS | 14 | 492,855 | 518,050 | 25,195 | 1,767,439 | 5.8 | |
| 04/18/14 | 2 | 72 | 16,17,18,WPS-1 | 40 | N/A | N/A | 62,000 | 1,829,439 | 14.4 | Flow meter not installed. Volumes based on tank gauging |
| 04/22/14 | 1 | 24 | 9,EPS | 14 | 518,050 | 523,548 | 5,498 | 1,834,937 | 3.8 | |
| 04/22/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | N/A | N/A | 19,500 | 1,854,437 | 13.5 | Flow meter not installed. Volumes based on tank gauging |
| 04/23/14 | 1 | 24 | 9,EPS | 14 | 523,548 | 528,369 | 4,821 | 1,859,258 | 3.3 | |
| 04/23/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | 0 | 15,441 | 15,441 | 1,874,699 | 10.7 | |
| 04/24/14 | 1 | 24 | 9,EPS | 14 | 528,369 | 532,995 | 4,626 | 1,879,325 | 3.2 | |
| 04/24/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | 15,441 | 30,198 | 14,757 | 1,894,082 | 10.2 | |
| 04/25/14 | 1 | 24 | 9,EPS | 14 | 532,995 | 537,006 | 4,011 | 1,898,093 | 2.8 | |
| 04/25/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | 30,198 | 41,737 | 11,539 | 1,909,632 | 8.0 | |
| 04/28/14 | 1 | 72 | 9,EPS | 12 | 537,006 | 552,302 | 15,296 | 1,924,928 | 3.5 | |
| 04/28/14 | 2 | 72 | 16,17 | 18 | 41,737 | 59,981 | 18,244 | 1,943,172 | 4.2 | |
| 04/29/14 | 1 | 24 | 9,EPS | 12 | 552,302 | 555,724 | 3,422 | 1,946,594 | 2.4 | |
| 04/29/14 | 2 | 24 | 16,17 | 18 | 59,981 | 62,592 | 2,611 | 1,949,205 | 1.8 | |

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 04/30/14 | 1 | 24 | 9,EPS | 12 | 555,724 | 560,143 | 4,419 | 1,953,624 | 3.1 | |
| 04/30/14 | 2 | 24 | 16,17 | 18 | 62,592 | 65,318 | 2,726 | 1,956,350 | 1.9 | |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013
Previous information is trunketed. Only last month and current month information is provided.

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-1)**

| DATE | HOURS OF OPERATION | DEEP WELL FLOW METER START (Gal) | DEEP WELL FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 10/23/13 | 29 | 0 | 24,640 | 24,640 | 24,640 | 14.2 | |
| 10/24/13 | 24 | 24,640 | 31,757 | 7,117 | 31,757 | 4.9 | |
| 10/25/13 | 24 | 31,757 | 39,567 | 7,810 | 39,567 | 5.4 | Slight blockage cleaned from meter |
| 10/28/13 | 72 | 39,567 | 91,820 | 52,253 | 91,820 | 12.1 | |
| 10/29/13 | 24 | 91,820 | 101,672 | 9,852 | 101,672 | 6.8 | |
| 10/30/13 | 24 | 101,672 | 111,472 | 9,800 | 111,472 | 6.8 | |
| 10/31/13 | 24 | 111,472 | 120,558 | 9,086 | 120,558 | 6.3 | |
| 11/01/13 | 24 | 120,558 | 128,248 | 7,690 | 128,248 | 5.3 | |
| 11/04/13 | 72 | 128,248 | 162,721 | 34,473 | 162,721 | 8.0 | |
| 11/05/13 | 24 | 162,721 | 173,853 | 11,132 | 173,853 | 7.7 | |
| 11/06/13 | 24 | 173,853 | 189,770 | 15,917 | 189,770 | 11.1 | |
| 11/07/13 | 24 | 189,770 | 210,266 | 20,496 | 210,266 | 14.2 | |
| 11/08/13 | 24 | 210,266 | 220,964 | 10,698 | 220,964 | 7.4 | |
| 11/11/13 | 72 | 220,964 | 235,035 | 14,071 | 235,035 | 3.3 | |
| 11/12/13 | 24 | 235,035 | 254,720 | 19,685 | 254,720 | 13.7 | |
| 11/13/13 | 24 | 254,720 | 272,758 | 18,038 | 272,758 | 12.5 | |
| 11/14/13 | 24 | 272,758 | 275,336 | 2,578 | 275,336 | 1.8 | |
| 11/15/13 | 24 | 275,336 | 281,413 | 6,077 | 281,413 | 4.2 | |
| 11/18/13 | 72 | 281,413 | 318,812 | 37,399 | 318,812 | 8.7 | |
| 11/19/13 | 24 | 318,812 | 328,059 | 9,247 | 328,059 | 6.4 | Well Taken Offline for Excavation |
| 11/27/13 | 24 | 328,059 | 351,245 | 23,186 | 351,245 | 16.1 | |
| 12/02/13 | 120 | 351,245 | 414,031 | 62,786 | 414,031 | 8.7 | Well Shut Off for Excavation Activities |
| 12/04/13 | 24 | 430,536 | 446,631 | 16,095 | 430,126 | 11.2 | |
| 12/05/13 | 24 | 446,631 | 459,826 | 13,195 | 443,321 | 9.2 | |
| 12/06/13 | 24 | 459,826 | 468,837 | 9,011 | 452,332 | 6.3 | |
| 12/09/13 | 72 | 468,837 | 499,005 | 30,168 | 482,500 | 7.0 | |
| 12/10/13 | 24 | 499,005 | 508,914 | 9,909 | 492,409 | 6.9 | |
| 12/11/13 | 24 | 508,914 | 519,185 | 10,271 | 502,680 | 7.1 | |
| 12/12/13 | 24 | 519,185 | 528,500 | 9,315 | 511,995 | 6.5 | |
| 12/13/13 | 24 | 528,500 | 535,384 | 6,884 | 518,879 | 4.8 | |
| 12/16/13 | 72 | 535,384 | 555,625 | 20,241 | 539,120 | 4.7 | |
| 12/17/13 | 24 | 555,625 | 563,870 | 8,245 | 547,365 | 5.7 | |
| 12/18/13 | 24 | 563,870 | 572,558 | 8,688 | 556,053 | 6.0 | |
| 12/19/13 | 24 | 572,588 | 578,579 | 5,991 | 562,044 | 4.2 | |
| 12/20/13 | 24 | 578,579 | 585,086 | 6,507 | 568,551 | 4.5 | |
| 12/23/13 | 72 | 585,086 | 604,411 | 19,325 | 587,876 | 4.5 | |
| 12/24/13 | 24 | 604,411 | 613,829 | 9,418 | 597,294 | 6.5 | |
| 12/30/13 | 144 | 613,829 | 669,247 | 55,418 | 652,712 | 6.4 | |
| 12/31/13 | 24 | 669,247 | 678,171 | 8,924 | 661,636 | 6.2 | |
| 01/02/14 | 48 | 678,171 | 697,609 | 19,438 | 681,074 | 6.7 | |
| 01/06/14 | 96 | 697,609 | 733,339 | 35,730 | 716,804 | 6.2 | Well Taken Offline |
| 03/11/14 | 24 | 0 | 13,985 | 13,985 | 730,789 | 9.7 | Well Online |
| 03/12/14 | 24 | 13,985 | 28,186 | 14,201 | 744,990 | 9.9 | |
| 03/13/14 | 24 | 28,186 | 29,780 | 1,594 | 746,584 | 1.1 | |
| 03/14/14 | 24 | 29,780 | 31,460 | 1,680 | 748,264 | 1.2 | |
| 03/17/14 | 72 | 31,460 | 36,200 | 4,740 | 753,004 | 1.1 | |
| 03/18/14 | 24 | 36,200 | 37,460 | 1,260 | 754,264 | 0.9 | |
| 03/19/14 | 24 | 37,460 | 46,700 | 9,240 | 763,504 | 6.4 | |
| 03/20/14 | 24 | 46,700 | 55,760 | 9,060 | 772,564 | 6.3 | |
| 03/21/14 | 24 | 55,760 | 63,390 | 7,630 | 780,194 | 5.3 | |
| 03/24/14 | 72 | 63,390 | 96,110 | 32,720 | 812,914 | 7.6 | |
| 03/25/14 | 24 | 96,110 | 107,450 | 11,340 | 824,254 | 7.9 | |
| 03/26/14 | 24 | 107,450 | 116,401 | 8,951 | 833,205 | 6.2 | Well Taken Offline |

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-2)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 03/03/14 | 72 | 14,717 | 43,855 | 29,138 | 1,296,224 | 6.7 | |
| 03/04/14 | 24 | 43,855 | 50,452 | 6,597 | 1,302,821 | 4.6 | |
| 03/05/14 | 24 | 50,452 | 61,014 | 10,562 | 1,313,383 | 7.3 | |
| 03/06/14 | 24 | 61,014 | 71,934 | 10,920 | 1,324,303 | 7.6 | Well Taken Offline for Excavation |
| 03/27/14 | 8 | 71,934 | 74,639 | 2,705 | 1,327,008 | 5.6 | Well Online |
| 03/28/14 | 24 | 74,639 | 85,721 | 11,082 | 1,338,090 | 7.7 | |
| 03/31/14 | 72 | 85,721 | 123,254 | 37,533 | 1,375,623 | 8.7 | |
| 04/01/14 | 24 | 0 | 17,708 | 17,708 | 1,393,331 | 12.3 | Flowmeter Reset |
| 04/02/14 | 24 | 17,708 | 25,981 | 8,273 | 1,401,604 | 5.7 | |
| 04/03/14 | 24 | 25,981 | 32,617 | 6,636 | 1,408,240 | 4.6 | |
| 04/04/14 | 24 | 32,617 | 40,149 | 7,532 | 1,415,772 | 5.2 | |
| 04/07/14 | 72 | 40,149 | 67,243 | 27,094 | 1,442,866 | 6.3 | |
| 04/08/14 | 24 | 67,243 | 74,368 | 7,125 | 1,449,991 | 4.9 | |
| 04/09/14 | 24 | 74,368 | 81,094 | 6,726 | 1,456,717 | 4.7 | |
| 04/10/14 | 24 | 81,094 | 88,044 | 6,950 | 1,463,667 | 4.8 | |
| 04/11/14 | 24 | 88,044 | 98,156 | 10,112 | 1,473,779 | 7.0 | |
| 04/14/14 | 72 | 98,156 | 129,352 | 31,196 | 1,504,975 | 7.2 | |
| 04/15/14 | 24 | 0 | 19,074 | 19,074 | 1,524,049 | 13.2 | Flowmeter Reset |
| 04/16/14 | 24 | 19,074 | 29,017 | 9,943 | 1,533,993 | 6.9 | |
| 04/17/14 | 24 | 29,017 | 39,400 | 10,383 | 1,544,376 | 7.2 | |
| 04/18/14 | 24 | 39,400 | 41,632 | 2,232 | 1,546,608 | 1.6 | |
| 04/21/14 | 72 | 41,632 | 48,331 | 6,699 | 1,553,307 | 1.6 | |
| 04/22/14 | 24 | 48,331 | 50,392 | 2,061 | 1,555,368 | 1.4 | |
| 04/23/14 | 24 | 50,392 | 59,341 | 8,949 | 1,564,317 | 6.2 | |
| 04/24/14 | 24 | 59,341 | 67,205 | 7,864 | 1,572,181 | 5.5 | Well Taken Offline |

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-5)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 04/25/14 | 24 | 0 | 6,883 | 6,883 | 6,883 | 4.8 | |
| 04/28/14 | 72 | 6,883 | 30,393 | 23,510 | 30,393 | 5.4 | |
| 04/29/14 | 24 | 30,393 | 37,639 | 7,246 | 37,639 | 5.0 | |
| 04/30/14 | 24 | 37,639 | 43,518 | 5,879 | 43,518 | 4.1 | |

## Attachment 5:  Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER START (KGal) | DISCHARGE FLOW METER FINISH (KGal) | DISCHARGED VOLUME (Gal) DAILY | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 03/04/14 | 8.0 | 4,970.69 | 5,064.73 | 94,040 | 5,064,280 | PVSC Compliance Sample collected |
| 03/05/14 | 8.0 | 5,064.73 | 5,170.07 | 105,340 | 5,169,620 | |
| 03/10/14 | 8.0 | 5,170.07 | 5,299.77 | 129,700 | 5,299,320 | |
| 03/11/14 | 8.0 | 5,299.77 | 5,368.86 | 69,090 | 5,368,410 | |
| 03/12/14 | 8.0 | 5,368.86 | 5,433.63 | 64,770 | 5,433,180 | |
| 03/17/14 | 8.0 | 5,433.63 | 5,590.00 | 156,370 | 5,589,550 | |
| 03/18/14 | 8.0 | 5,590.00 | 5,690.00 | 100,000 | 5,689,550 | |
| 03/19/14 | 8.0 | 5,690.00 | 5,849.46 | 159,460 | 5,849,010 | |
| 03/20/14 | 8.0 | 5,849.46 | 5,912.45 | 62,990 | 5,912,000 | |
| 03/21/14 | 8.0 | 5,912.45 | 6,024.94 | 112,490 | 6,024,490 | |
| 03/24/14 | 8.0 | 6,024.94 | 6,125.64 | 100,700 | 6,125,190 | |
| 03/25/14 | 8.0 | 6,125.64 | 6,175.64 | 50,000 | 6,175,190 | |
| 03/26/14 | 8.0 | 6,175.64 | 6,248.89 | 73,250 | 6,248,440 | |
| 03/27/14 | 8.0 | 6,248.89 | 6,310.44 | 61,550 | 6,309,990 | |
| 03/28/14 | 8.0 | 6,310.44 | 6,380.45 | 70,010 | 6,380,000 | |
| 03/31/14 | 8.0 | 6,380.45 | 6,575.85 | 195,400 | 6,575,400 | |
| 04/01/14 | 8.0 | 6,575.85 | 6,717.81 | 141,960 | 6,717,360 | |
| 04/02/14 | 8.0 | 6,717.81 | 6,951.38 | 233,570 | 6,950,930 | |
| 04/03/14 | 8.0 | 6,951.38 | 7,050.47 | 99,090 | 7,050,020 | PVSC Compliance Sample collected |
| 04/04/14 | 8.0 | 7,050.47 | 7,173.74 | 123,270 | 7,173,290 | |
| 04/05/14 | 8.0 | 7,173.74 | 7,250.14 | 76,400 | 7,249,690 | |
| 04/08/14 | 8.0 | 7,250.14 | 7,452.80 | 202,660 | 7,452,350 | |
| 04/09/14 | 8.0 | 7,452.80 | 7,538.06 | 85,260 | 7,537,610 | |
| 04/10/14 | 8.0 | 7,538.06 | 7,687.85 | 149,790 | 7,687,400 | |
| 04/11/14 | 8.0 | 7,687.85 | 7,810.35 | 122,500 | 7,809,900 | |
| 04/14/14 | 6.0 | 7,810.35 | 7,883.23 | 72,880 | 7,882,780 | |
| 04/15/14 | 6.0 | 7,883.23 | 7,948.35 | 65,120 | 7,947,900 | |
| 04/16/14 | 8.0 | 7,948.35 | 8,036.99 | 88,640 | 8,036,540 | |
| 04/17/14 | 8.0 | 8,036.99 | 8,120.52 | 83,530 | 8,120,070 | |
| 04/18/14 | 8.0 | 8,120.52 | 8,241.81 | 121,290 | 8,241,360 | |
| 04/19/14 | 8.0 | 8,241.81 | 8,416.26 | 174,450 | 8,415,810 | |
| 04/21/14 | 8.0 | 8,416.26 | 8,503.96 | 87,700 | 8,503,510 | |
| 04/22/14 | 8.0 | 8,503.96 | 8,649.60 | 145,640 | 8,649,150 | |
| 04/23/14 | 8.0 | 8,649.60 | 8,775.22 | 125,620 | 8,774,770 | |
| 04/24/14 | 8.0 | 8,775.22 | 8,877.66 | 102,440 | 8,877,210 | |
| 04/25/14 | 8.0 | 8,877.66 | 8,949.22 | 71,560 | 8,948,770 | |
| 04/26/14 | 8.0 | 8,949.22 | 9,030.24 | 81,020 | 9,029,790 | |
| 04/28/14 | 8.0 | 9,030.24 | 9,133.26 | 103,020 | 9,132,810 | |
| 04/29/14 | 8.0 | 9,133.26 | 9,211.40 | 78,140 | 9,210,950 | |
| 04/30/14 | 8.0 | 9,211.40 | 9,371.72 | 160,320 | 9,371,270 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data

- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log


| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 1-7 | <20 | 7-20-a | 500 | 124-7-20-a1 | 10/31/2013 | 14:20 | 5.8 | Yes | | |
| | | | | 124-7-20-a2 | 10/31/2013 | 14:25 | 7.8 | Yes | | |
| | | | | 124-7-20-a3 | 10/31/2013 | 14:30 | 4.6 | Yes | | |
| | | | | 124-7-20-a4 | 10/31/2013 | 14:35 | 4.7 | Yes | | |
| 7-12 | <20 | 12-20-a | 500 | 124-12-20-a1 | 11/26/2013 | 15:00 | 26.1 | | Yes | |
| | | | | 124-12-20-a2 | 11/26/2013 | 15:05 | 2.9 | Yes | | |
| | | | | 124-12-20-a3 | 11/26/2013 | 15:10 | 7.8 | Yes | | |
| | | | | 124-12-20-a4 | 11/26/2013 | 15:15 | 23.2 | | Yes | |
| 7-12 | <20 | 12-20-b | 500 | 124-12-20-b1 | 11/26/2013 | 15:20 | 4.3 | Yes | | |
| | | | | 124-12-20-b2 | 11/26/2013 | 15:25 | 2.5 | Yes | | |
| | | | | 124-12-20-b3 | 11/26/2013 | 15:30 | 5.1 | Yes | | |
| | | | | 124-12-20-b4 | 11/26/2013 | 15:35 | 5.8 | Yes | | |
| 12-22 | <20 | 22-20-a | 600 | 124-22-20-a1 | 12/13/2013 | 13:30 | 5.5 | Yes | | |
| | | | | 124-22-20-a2 | 12/13/2013 | 13:35 | 11.9 | Yes | | |
| | | | | 124-22-20-a3 | 12/13/2013 | 13:40 | 1.3 | Yes | | |
| | | | | 124-22-20-a4 | 12/13/2013 | 13:45 | 2.3 | Yes | | |
| 12-25 | <20 | 25-20-a | 1000 | 124-25-20-a1 | 12/23/2013 | 9:00 | 1.6 | Yes | | |
| | | | | 124-25-20-a2 | 12/23/2013 | 9:05 | 1.7 | Yes | | |
| | | | | 124-25-20-a3 | 12/23/2013 | 9:10 | 10.8 | Yes | | |
| | | | | 124-25-20-a4 | 12/23/2013 | 9:15 | 17.4 | Yes | | |
| 20-29 | <20 | 29-20-a | 500 | 124-29-20-a1 | 1/13/2014 | 14:00 | 0.31 | Yes | | |
| | | | | 124-29-20-a2 | 1/13/2014 | 14:05 | 0.84 | Yes | | |
| | | | | 124-29-20-a3 | 1/13/2014 | 14:10 | 3.4 | Yes | | |
| | | | | 124-29-20-a4 | 1/13/2014 | 14:15 | 1.9 | Yes | | |
| 30-41 | >1000 | 41-1000-a | 750 | 124-41-1000-a1 | 2/25/2014 | 12:40 | 1,750 | | | Yes |
| | | | | 124-41-1000-a2 | 2/25/2014 | 12:45 | 3,690 | | | Yes |
| | | | | 124-41-1000-a3 | 2/25/2014 | 12:50 | 3,410 | | | Yes |
| | | | | 124-41-1000-a4 | 2/25/2014 | 12:55 | 453 | | Yes | |
| 30-41 | >1000 | 41-1000-b | 750 | 124-41-1000-b1 | 2/25/2014 | 13:00 | 490 | | Yes | |
| | | | | 124-41-1000-b2 | 2/25/2014 | 13:05 | 1,110 | | | Yes |
| | | | | 124-41-1000-b3 | 2/25/2014 | 13:10 | 669 | | Yes | |
| | | | | 124-41-1000-b4 | 2/25/2014 | 13:15 | 1,920 | | | Yes |
| 37-46 | <20 | 46-20-a | 750 | 124-46-20-a1 | 3/12/2014 | 14:00 | 3.2 | Yes | | |
| | | | | 124-46-20-a2 | 3/12/2014 | 14:05 | 2.2 | Yes | | |
| | | | | 124-46-20-a3 | 3/12/2014 | 14:10 | 3.9 | Yes | | |
| | | | | 124-46-20-a4 | 3/12/2014 | 14:15 | 2 | Yes | | |
| 37-46 | <20 | 46-20-b | 750 | 124-46-20-b1 | 3/12/2014 | 14:20 | 2.9 | Yes | | |
| | | | | 124-46-20-b2 | 3/12/2014 | 14:25 | 3.8 | Yes | | |
| | | | | 124-46-20-b3 | 3/12/2014 | 14:30 | 2.2 | Yes | | |
| | | | | 124-46-20-b4 | 3/12/2014 | 14:35 | 2.6 | Yes | | |
| 41-49 | >1000 | 124-49-1000-a | 1000 | 124-49-1000-a1 | 3/24/2014 | 9:15 | 3490 | | | Yes |
| | | | | 124-49-1000-a2 | 3/24/2014 | 9:20 | 3850 | | | Yes |
| | | | | 124-49-1000-a3 | 3/24/2014 | 9:25 | 2580 | | | Yes |
| | | | | 124-49-1000-a4 | 3/24/2014 | 9:30 | 5570 | | | Yes |
| 41-49 | >1000 | 124-49-1000-b | 1000 | 124-49-1000-b1 | 3/24/2014 | 9:35 | 8840 | | | Yes |
| | | | | 124-49-1000-b2 | 3/24/2014 | 9:40 | 2340 | | | Yes |
| | | | | 124-49-1000-b3 | 3/24/2014 | 9:45 | 2 | | Yes | |
| | | | | 124-49-1000-b4 | 3/24/2014 | 9:50 | 4250 | | | Yes |
| 47-57 | <20 | 124-57-20-a | 860 | 124-57-20-a1 | 4/4/2014 | 12:30 | 17.0 | Yes | | |
| | | | | 124-57-20-a2 | 4/4/2014 | 12:35 | 3.8 | Yes | | |
| | | | | 124-57-20-a3 | 4/4/2014 | 12:40 | 4.2 | Yes | | |
| | | | | 124-57-20-a4 | 4/4/2014 | 12:45 | <0.52 | Yes | | |

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 47-57 | <20 | 124-57-20-b | 860 | 124-57-20-b1 | 4/4/2014 | 12:50 | 4.1 | Yes | | |
| | | | | 124-57-20-b2 | 4/4/2014 | 12:55 | 14.2 | Yes | | |
| | | | | 124-57-20-b3 | 4/4/2014 | 13:00 | 15.7 | Yes | | |
| | | | | 124-57-20-b4 | 4/4/2014 | 13:05 | <0.49 | Yes | | |
| 47-57 | <20 | 124-57-20-c | 860 | 124-57-20-c1 | 4/4/2014 | 13:10 | 10.3 | Yes | | |
| | | | | 124-57-20-c2 | 4/4/2014 | 13:15 | 11.6 | Yes | | |
| | | | | 124-57-20-c3 | 4/4/2014 | 13:20 | 8.9 | Yes | | |
| | | | | 124-57-20-c4 | 4/4/2014 | 13:25 | 41.4 | | Yes | |
| 49-59 | >1000 | 124-59-1000-a | 800 | 124-59-1000-a1 | 4/11/2014 | 8:00 | 11,000 | | | Yes |
| | | | | 124-59-1000-a2 | 4/11/2014 | 8:05 | 26,900 | | | Yes |
| | | | | 124-59-1000-a3 | 4/11/2014 | 8:10 | 11,900 | | | Yes |
| | | | | 124-59-1000-a4 | 4/11/2014 | 8:15 | 32,700 | | | Yes |
| 57,58 144-152 | <20 | 124-152-20-a | 800 | 124-152-20-a1 | 4/23/2014 | 15:00 | 0.73 | Yes | | |
| | | | | 124-152-20-a2 | 4/23/2014 | 15:05 | 0.76 | Yes | | |
| | | | | 124-152-20-a3 | 4/23/2014 | 15:10 | 0.42 | Yes | | |
| | | | | 124-152-20-a4 | 4/23/2014 | 15:15 | 1.2 | Yes | | |

**Notes:**
**Material currently stockpiled.

## Attachment 7:  Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
05-07-2014


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP–1


May 07, 2014 at 4:13pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | 134- | 140- | | North | | | | South | | | |
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-1 | FS-3 | FS-4 | FS-5 |
| Date | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | | 7.0 | 8.3 | 7.3 | 7.5 | 7.5 | 7.9 | 7.7 | 5.9 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells and perimeter pool risers are temporarily inaccessible:
134-MW-V09, N3W, N4E, N4W, W3-SO, E1A-SO

## Attachment 8: Quality and Level Data in GWET Wells

- Summary of Groundwater Quality Data from GWET Wells
- Quarterly Water Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells

**Table 1**
Summary of Groundwater Quality Data from GWET Wells

Honeywell

| Parameter | 3-Jun-13 | | | 20-Sep-13 | | | 3-Dec-13 | | | 1-Apr-14 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-203BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-203BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-203BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 3.9 | 5.5 | ND | 3.1 | 4.4 | ND | 3.4 | 5.2 | ND | 2.9 | 4.0 | ND |
| Carbon Tetrachloride | 5.8 | 3.5 | 1.9 | 4.6 | 3.1 | 1.4 | 5.8 | 4.8 | 2.5 | 4.4J | 2.8 | 1.9 |
| Chloroform | 30.3 | 27.2 | ND | 27.4 | 17.9 | ND | 31.0 | 16.8 | ND | 26.5 | 12.0 | ND |
| 1,1-Dichloroethene | 0.82J | ND | ND | 0.55 | ND | ND | 0.07 | ND | ND | 0.42J | ND | ND |
| cis-1,2-Dichloroethene | 173 | 17.0 | ND | 148 | 13.8 | ND | 135 | 12.3 | ND | 96 | 8.1 | ND |
| trans-1,2-Dichloroethene | 5.8 | 0.47 | ND | 4.5 | 0.76 | ND | 4.9 | 0.35 | ND | 3.4 | ND | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 118 | 63.3 | ND | 95.1 | 52.6 | ND | 113.0 | 63.0 | ND | 91.3 | 43.4 | ND |
| 1,1-Dichloroethane | 0.47 | ND | ND | 0.45 | ND | ND | 0.47 | ND | ND | 0.45J | ND | ND |
| Methylene chloride | 1.3 | 0.76 | ND | 0.84 | ND | ND | 0.87 | 0.31 | ND | 0.77J | ND | ND |
| Vinyl chloride | 10.6 | 4.4 | ND | 12.6 | ND | ND | 14.2 | 4.8 | ND | 13.5 | 2.7 | ND |
| 1,2-Dichlorobenzene | 0.81 | ND | ND | 0.66 | ND | ND | 0.72 | ND | ND | 0.72J | ND | ND |
| Chlorobenzene | 0.48 | ND | ND | 0.38 | ND | ND | 0.39 | ND | ND | 0.38J | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 34,000 | 13,000 | 15,700 | 38,200 | 11,400 | 16,700 | 39,600 | 11,300 | 16,500 | 33,400 | 12,500 | 15,100 |
| Total Chromium | 48,500 | 28,000 | 21,000 | 39,900 | 13,500 | 17,000 | 34,200 | 10,600 | 14,900 | 36,900 | 16,400 | 16,600 |

NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.


Note:
Starting with 1st quarter 2014, well 115-MW-215BR is being pumped and sampled.


**TABLE 2**
**Quarterly Water Levels**
**March 2014**

Honeywell


| Wells<br>Date: March 13, 2014 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments |
|---|---|---|---|---|
| 087-MW-25D | 18.17 | 12.62 | 5.55 | GW Elevations are not corrected for tidal influence |
| 087-MW-25T | 18.19 | 16.50 | 1.69 | |
| 087-MW-35 | 18.29 | 16.66 | 1.63 | |
| 087-OBS-1D | 15.13 | N/A | N/A | Well not accessible |
| 087-OBS-1L | 15.27 | N/A | N/A | Well not accessible |
| 087-OBS-1T | 15.23 | N/A | N/A | Well not accessible |
| 087-PW-2 | 13.02 | 10.82 | 2.20 | Well off line for maintanence |
| 087-MW-08 | 12.98 | 10.78 | 2.20 | |
| 087-OBS-3L | 12.88 | 10.72 | 2.16 | |
| 087-MW-13 | 12.93 | 10.65 | 2.28 | |
| 087-OBS-5D | 12.72 | 10.68 | 2.04 | |
| 087-OBS-5T | 12.62 | 11.78 | 0.84 | |
| 087-PW-1 | 12.66 | 33.51 | -20.85 | |
| 087-MW-34 | 12.73 | 12.42 | 0.31 | |
| 087-OBS-2D | 12.68 | 13.55 | -0.87 | |
| SA6-MW-AA1D | 19.36 | 17.13 | 2.23 | |
| SA6-MW-AA1T | 15.31 | 13.33 | 1.98 | |
| SA6-MW-5BR-1 | 17.06 | 14.85 | 2.21 | |
| 087-OBS-4T | 11.6 | 10.07 | 1.53 | |
| 087-MW-O29D | 10.32 | 8.08 | 2.24 | |
| 087-MW-O29T | 9.98 | 7.48 | 2.50 | |
| 087-MW-03 | 13.77 | N/A | N/A | Well not accessible |
| 087-MW-02 | 12.57 | N/A | N/A | |
| 115-MW-203BR* | 8.7 | N/A | N/A | |
| 073-MW-1BR-1 | 7.58 | 8.82 | -1.24 | |
| 073-MW-10BR-1 | 6.67 | 7.17 | -0.50 | |
| 115-MW-215BR* | 8.82 | 12.75 | -3.93 | |

* Reference point elevation to be confirmed.





Note: Well 115-MW-203BR has been replaced with well 115-MW-215BR





Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR

## Attachment 9: Surcharge Monitoring Update


- Instrumentation Location Plan 1N
- Instrumentation Location Plan 1S




| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| VI–1 | 686123 | 602109 |
| VI–2 | 686029 | 602048 |
| VI–3 | 685927 | 602572 |
| VI–4 | 685866 | 602701 |
| FS1 | 685981 | 602115 |
| FS2 | 685863 | 602451 |
| FS3 | 685811 | 602689 |
| FS4 | 685723 | 602723 |
| HS1 | 685959 | 602414 |
| HS2 | 685929 | 602333 |
| HS3 | 685865 | 602294 |
| HS4 | 685920 | 602491 |
| HS5 | 685787 | 602414 |
| ~~HS6~~ | ~~685785~~ | ~~602650~~ |
| HS7 | 685696 | 602582 |
| ~~HS8~~ | ~~685826~~ | ~~602796~~ |
| HS9 | 685624 | 602691 |

| | | |
|---|---|---|
| SP1 | 685881 | 602205 |
| SP2 | 685757 | 602416 |
| SP3 | 685613 | 602662 |
| ~~SP4~~ | ~~685953~~ | ~~602533~~ |
| ~~SP5~~ | ~~685931~~ | ~~602578~~ |
| ~~SP6~~ | ~~685906~~ | ~~602634~~ |
| ~~SP7~~ | ~~685887~~ | ~~602676~~ |
| ~~SP8~~ | ~~685867~~ | ~~602721~~ |
| ~~SP9~~ | ~~685849~~ | ~~602764~~ |
| ~~SP10~~ | ~~685884~~ | ~~602781~~ |




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. COMMENCE FILL AT THE SEDIMENTATION BASIN AND WORK TOWARDS THE HACKENSACK RIVER.
6. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
7. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
8. AT ALL SURVEY LOCATIONS CLEAN ADEQUATELY A SUFFICIENT AREA ON THE TOP SURFACE OF THE 72 INCH FORCE MAIN TO EPOXY THE SURVEY MARKER AND ELECTRONIC EQUIPMENT.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SETUP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SETUP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |
| A1 | ACOUSTICAL LOCATION FOR DISCUSSION PURPOSES ONLY |
| AS3 | ACOUSTICAL/SURVEY LOCATION FOR DISCUSSION PURPOSES ONLY |
| X | STATION RELOCATED OR ELIMINATED DUE TO SURCHARGE PILE RECONFIGURATION |

Installed Instrumentation Locations


Instrumentation Locations Not Installed


0 15 30 60
SCALE IN FEET

Prepared/Date: RJR 08/16/13
Checked/Date: AE 08/16/13

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 NORTH<br>JERSEY CITY, NEW JERSEY<br>HONEYWELL SITE ID - 37472 | amec | INSTRUMENTATION LOCATION PLAN 1N<br>Project 3480-09-0006<br>Figure B1 |

Z:\Projects\HONEYWELL\JERSEY CITY\Dwg Design–SA6–CSD\CAD\SA6N\100 Percent\Figure 1 Surcharge Settling Monitoring Plan – Area 1.dwg Tue, 21 Jan 2014 – 7:11am roger.ryder




| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–1 | 685276.02 | 601927.05 |
| FS–2 | 685323.86 | 601748.51 |
| HS–1 | 685597.02 | 601567.16 |
| HS–2 | 685511.42 | 601690.72 |
| HS–3 | 685421.98 | 601800.88 |
| HS–4 | 685313.18 | 601947.19 |
| HS–5 | 685480.23 | 601623.90 |
| HS–6 | 685518.78 | 601480.25 |
| HS–7 | 685413.06 | 601624.11 |
| HS–8 | 685204.27 | 601911.97 |
| VI–1 | 685624.44 | 601515.06 |
| VI–2 | 685578.58 | 601462.08 |
| VRC–1 | 685505.92 | 601505.39 |
| VRC–2 | 685434.27 | 601785.68 |
| VRC–3 | 685262.85 | 601914.43 |
| SP–1 | 685567.71 | 601633.29 |
| SP–2 | 685410.62 | 601852.31 |
| SP–3 | 685276.93 | 602033.96 |

Installed Instrumentation Locations

Instrumentation Locations Not Installed

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

- VI–2 — INCLINOMETER LOCATION
- FS–1–1 — SETTLEMENT MONITORING POINT FULL – SET UP
- HS–1–1 — SETTLEMENT MONITORING POINT HALF – SET UP
- SP12 — SETTLEMENT MONITORING PLATFORM
- RP — APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7)
- VRC1 — VIBRATING WIRE PIEZOMETER IN STRATUM RC

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 07/19/13
Checked/Date: AE 07/19/13

Revised DCB 001 7/29/13

Honeywell
101 COLUMBIA RD., BOX 2106
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY


amec


INSTRUMENTATION LOCATION PLAN 1S

Figure F1

## Attachment 10: Sheet Pile Update


- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Pile Repair Log




SHEET SEALING DETAIL (BF TYP S-203)
NTS

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |
| STRUCTURAL | 19+00 | 21+20 | -19 | AZ 19-700 |
| STRUCTURAL | 21+20 | 23+20 | -15 | AZ 19-700 |
| STRUCTURAL | 23+20 | 24+37 | -12 | AZ 19-700 |
| NON STRUCTURAL | 24+37 | 25+89 | -12 | AZ 19-700 |




NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL 5/14/13
STATE OF NEW JERSEY — STEPHEN H. MITCHELL — No. 24GE04322400 — PROFESSIONAL ENGINEER
Stephen H. Mitchell

| NO. | DATE | DR | CHK | APVD | BY |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | RJR | TDD | TDD SHM |

ISSUED FOR CONSTRUCTION
REVISION
APVD
SHM

NJ PROFESSIONAL ENGINEER LICENSE NUMBER 24GE04322400

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.
THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, N.J. 08619
(609) 890-3939
NJ Certificate of Authorization Number 24GA28016900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-203 |
| SHEET | 55 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SAR-C3D\CAD\SA6S\CR55-S-203 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Wed, 22 May 2013 PLOT TIME: 3:01 PM

# Sheet Deflection Along Open Excavation- East


Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the



# Sheet Deflection Along Open Excavation- West




Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.





NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 03-12-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 03-20-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-24

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-25

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-26

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/21/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 3/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-27

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-28

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, repair (coat)

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-29

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, repair (coat)

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-30

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation.

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SP1-31

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-32

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-33

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-34

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BP1-35

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-36

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-37

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-38

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8P1-39

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BPI-40

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BPI-41

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BPI-42

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: BPI-43

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, repair

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 8PI-44

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25PI-1

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25PI-2

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25P-3

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-4

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-5

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-6

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-7

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25P1-8

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25P1-9

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25P1-10

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 25P1-11

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-12

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-13

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 2SP1-14

Date Exposed: _____

Describe Damage: Damaged by bucket during excavation

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 3/31/14

Inspected by: M. Senna

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 4/4/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

## Attachment 11:  Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 2, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 1 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/02/14

SWPPP Observer: (G. Pfeiffer)
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Wednesday, April 02, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Petroleum impacted soils in the eastern exclusion zone on SA-6 South are nearing the top of the containment walls on the side abutting the SA-7 SCB wall. |
| 2 | IA2Q4A1AL8 | Ponded water has accumulated outside the northern perimeter of the >1000 ppm stockpile area on the west end of SA-6 South. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 04/02/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Excavate the edge of the stockpile to reduce the risk of material overtopping the containment barriers. | 4/7/14 RAD. |
| 2 | Pump the storm water from the affected area, place stone in the low areas to prevent recurrence. | 4/7/14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 04/08/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 9, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 2 |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/10/14

SWPPP Observer: _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Wednesday, April 09, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing and signage is not in place along the southern perimeter of the >1000 PPM Cr stockpile area. |
| 2 | IA2Q4A1AL8 | Gasoline cans are not collected at the end of each day and returned to the flammable liquid storage cabinet. |
| 3 | IA2Q4A1AL8 | A pile of backfill material adjacent toe the Hackensack River bulkhead (remaining from snow removal efforts over the winter) has no erosion protection system in place. |
| 4 | IA2Q4A1AL8 | The western side of the SA-7 to SA-6N ramp is no longer protected by a geotextile cover or other erosion prevention measures. |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City New Jersey

SWAP Observer: _____ Date: 04/10/14
Signature
(Geosyntec: Pfe, ffe)

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install fencing and/or signage as appropriate to delineate the EZ as seen from the top of the former Teal Trucking warehouse slab. | 4-11-14 ROD |
| 2 | Pump the storm water from the affected area, place stone in the low areas to prevent recurrence. | 4-15-14 RAD |
| 3 | Place all gasoline cans in the flammable liquid storage cabinet at the end of each workday. Check for cans around pumps, generators, etc.... | 4-11-14 RAD |
| 4 | A cover system should be in place to prevent erosion of ramp material into the SA-7 North sluiceway. | 4-11-14 RAD |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 04/15/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 16, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/17/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Wednesday, April 16, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen at the Kellogg Steet jughandle requires maintenance. |
| 2 | IA2Q4A1AL8 | The 80 Kellogg GWET sump is full of water |
| 3 | IA2Q4A1AL8 | The newly-installed temporary perimeter fence on Study Area 6 North has a gap on its eastern end. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 04/17/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Refasten the windscreen to the perimeter fence. | 4-18-14 RAD |
| 2 | Pump the sump water to the Construction Water Treatment System. | 4-21-14 RAD |
| 3 | Install additional temporary fence panels on the east end of the new fenceline to close the gap by the southeast corner of the DPW H Building | 4-18-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 04/21/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 23, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other Windy
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 2 |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |

NOTE: All comments are numbered for reference and included on the comment section below.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/24/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, April 23, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | 5 gallon gasoline cans stored in Entact's storage shed area overnight, outside of Flammable Storage Cabinet. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing at eastern EZ entrance/exit requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature **Date:** 04/24/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Review flammable liquid storage requirements with all Entact personnel and obtain an additional flammables cabinet if required to accommodate all gas cans on site | 4-25-14 RAD |
| 2 | Repair and maintain orange EZ fencing surrounding the eastern EZ. | 4-25-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 04/28/14

## Attachment 12: GWTP Update

- 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (March 2014)
- Request to NJDEP re Permit NJG0156311 Permit Revocation
- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (March 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 15, 2014

New Jersey Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: March 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the March 2014 Surface Water Discharge Monitoring Report for Outfall 001A.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Scott Serino - GWTT
Frank Schroyer - Parsons

New Jersey Department of Environmental Protection
Division of Water Quality

PI 234822

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 3 | 1 | 2014 | To | 3 | 31 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☒ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

| John J. Morris, Remediation Director | — | |
|---|---|---|
| NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR | GRADE AND REGISTRY NUMBER (IF APPLICABLE) | |
| John J Morris | 4/15/2014 | 973.455.4003 |
| SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR | DATE | AREA CODE/PHONE NUMBER |

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

| John J. Morris, Remediation Director | John J Morris | 4/15/2014 | 973.455.4003 |
|---|---|---|---|
| NAME AND TITLE | SIGNATURE | DATE | AREA CODE/PHONE NUMBER |

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 3/1/2014 TO 3/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | | | GPD | ****** | ****** | ****** | ****** | | | |
| | PERMIT REQUIREMENT | REPORT 01MOAV | REPORT 01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | | SU | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0 01MOMN | ****** | 9.0 01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 50 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10 01MOAV | 15 01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 20 01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 3/1/2014 TO 3/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 1/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 3/1/2014 TO 3/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable 01119 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr) 01220 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | | |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable 71901 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 0.025 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride 32102 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | GRAB |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.8 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform 32106 2 Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | GRAB |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 46 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene 39180 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | GRAB |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 54 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 1/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 3/1/2014 TO 3/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | | | | | | | | | | |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 1/1/2014*

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 15, 2014

New Jersey Department of Environmental Protection
Mail Code 401-02B
Permit Administration Section
Division of Water Quality
P.O. Box 420
Trenton, NJ 08625-0420

**RE: NJDEP Division of Water Quality New Jersey Pollutant**
**Request for Permit Revocation**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

Attached please find the completed New Jersey Pollutant Discharge Elimination System request for permit revocation for NJPDES Permit NJG0156311.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Scott Serino - GWTT
Frank Schroyer - Parsons

Reset Form

# State of New Jersey
# Department of Environmental Protection
# Division of Water Quality
# New Jersey Pollutant Discharge Elimination System

## Request for Permit Revocation / Certification of Closure

### 1. APPLICANT(S)/OPERATING ENTITY(IES)

NJPDES Permit # NJG0156311 P.I. # 234822

Name Honeywell International Inc.

Mailing Address 101 Columbia Rd

City or Town Morristown State NJ Zip Code 07962

Telephone ( 973 ) 455-2989 E-Mail helen.fahy@honeywell.com

### 2. LOCATION OF FACILITY/SITE

Name of Facility/Site Honeywell Study Area 7

Street Address/Location 441 RT 440 S

City or Town Jersey City State NJ Zip Code 07305

### 3. FACILITY CONTACT (Person Familiar with the Facility/Site and this Application)

Name Helen Fahy Telephone ( 973 ) 455-2989

Affiliation Fahy Associates, Remediation Manager

Fax ( 973 ) 695-2444 E-Mail helen.fahy@honeywell.com

### 4. Treatment plant/units or storage units closed, including the date closed (e.g., sludge facilities, lagoons, equalization tanks, trickling filters, clarifiers, sludge digesters, etc.). If the entire plant has been closed write "entire." The units closed are as follows:

- entire
- _____
- _____
- _____
- _____
- _____
- _____
- _____

### 5. The plant or units described in Item 4 above have been closed because of one of the following:

- [x] Facility has been closed.
- [ ] Connection to Sewerage Entity (e.g., connection to another wastewater treatment plant).
- [ ] Other – Describe: _____

6. All wastes and components of the treatment plant or other units described in Item 4 above have been properly managed, disposed and secured as follows where applicable:

| ACTIVITY | YES | N/A |
|---|---|---|
| • Influent and effluent pipes have been sealed. | ✓ | |
| • The affected units have been closed in such a manner so as to protect public safety and health, and to assure that no cont amination of ground or surface w ater will occur as a result of removing such facilities and equipment from service, either through the act of closure or through continuing the discharge of pollut ants into or through equipment; or through leaking, leaching, or discharge of pollutants from w astewater or residuals or other by-products remaining in facilities or equipment which has been removed or remains on site. | ✓ | |
| • All residual materials and all other solids from the treatment process including, but not limited to, liquid and dried sludges, grit and screenings, scum and sand bed materials have been removed and/or managed in a manner approved by the Department. | ✓ | |
| • Other, explain: _____ | | |

After verifying that the applicant no longer requires a permit for the discharge, the appropriate Water Compliance and Enforcement Bureau will advise the Office of Permit Management to revoke the NJPDES permit or GP Authorization.

I understand that it is a violation of the "Water Pollution Control Act", N.J.S.A. 58:10A-1 et seq., to discharge pollutants except in conformity with a NJPDES permit and that I may be subject to significant civil/criminal penalties for said violation.

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based upon my inquiry of the person(s) who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for purposely, knowingly, recklessly, or negligently submitting false information."

John J. Morris
Signature of/for Permittee

4/15/2014
Date

John J. Morris
Print or Type: Name

Honeywell Remediation Director
Print or Type: Position

## WHO MUST SIGN?

A Responsible Official is defined in N.J.A.C. 7:14A – 4.9 as follows:

For a corporation: A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision making functions for the corporation; or the manager of one or more manufacturing, production, or operating facilities, provided:

(1) The manager is authorized to make management decisions that govern the operation of the regulated facility, including having the explicit or implicit duty of recommending major capital investment, initiating and directing comprehensive measures to assure long term compliance with environmental laws and regulations, and ensuring that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; or
(2) The authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

For a partnership or sole proprietorship: A general partner or the proprietor.

For a government agency: A ranking elected official; or the chief executive officer of the agency; or a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator).

A duly authorized representative as defined in N.J.A.C. 7:14A-4.9(b).

**Please send completed copies to:**

Mail Code 401-02B
Permit Administration Section
Division of Water Quality
P.O. Box 420
Trenton, NJ 08625-0420

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 15, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Bayfront Redevelopment at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the March 2014 discharge monitoring reports, MR 1 and MR 2, for the Bayfront Redevelopment treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc., Bayfront Redevelopment

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 3 | 01 | 14 | 3 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 70,682 | 97,341 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.36 | 0.50 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.08994 | 0.08994 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

4/15/2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc., Bayfront Redevelopment

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 3 | 01 | 14 | 3 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,191,140 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 3,310,963 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 3/28/2014 | 9.5 | 12.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 4/15/2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Bayfront Redevelopment; GWTP (Permit #31630016) | | | | | | | | MONTH: March 2014 | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 3/1/2014 | Angel Trujillo | 1119823 | 1210327 | 90,504 | 0.090504 | 7.40 | 0.616 | | | | | | | | | 0.46 |
| 3/2/2014 | Angel Trujillo | 1210327 | 1265848 | 55,521 | 0.055521 | 7.40 | 0.616 | | | | | | | | | 0.29 |
| 3/3/2014 | Angel Trujillo | 1265848 | 1324567 | 58,719 | 0.058719 | 7.43 | 0.616 | | | | | | | | | 0.30 |
| 3/4/2014 | Angel Trujillo | 1324567 | 1388969 | 64,402 | 0.064402 | 7.47 | 0.616 | | | | | | | | | 0.33 |
| 3/5/2014 | Angel Trujillo | 1388969 | 1457281 | 68,312 | 0.068312 | 7.45 | 0.616 | | | | | | | | | 0.35 |
| 3/6/2014 | Angel Trujillo | 1457281 | 1526001 | 68,720 | 0.06872 | 7.33 | 0.616 | | | | | | | | | 0.35 |
| 3/7/2014 | Angel Trujillo | 1526001 | 1593805 | 67,804 | 0.067804 | 7.34 | 0.616 | | | | | | | | | 0.35 |
| 3/8/2014 | Angel Trujillo | 1593805 | 1688090 | 94,285 | 0.094285 | 7.24 | 0.616 | | | | | | | | | 0.48 |
| 3/9/2014 | Angel Trujillo | 1688090 | 1749158 | 61,068 | 0.061068 | 7.35 | 0.616 | | | | | | | | | 0.31 |
| 3/10/2014 | Angel Trujillo | 1749158 | 1822349 | 73,191 | 0.073191 | 7.38 | 0.616 | | | | | | | | | 0.38 |
| 3/11/2014 | Angel Trujillo | 1822349 | 1853758 | 31,409 | 0.031409 | 7.19 | 0.616 | | | | | | | | | 0.16 |
| 3/12/2014 | Angel Trujillo | 1853758 | 1860986 | 7,228 | 0.007228 | 7.26 | 0.616 | | | | | | | | | 0.04 |
| 3/13/2014 | Angel Trujillo | 1860986 | 1905775 | 44,789 | 0.044789 | 7.41 | 0.616 | | | | | | | | | 0.23 |
| 3/14/2014 | Angel Trujillo | 1905775 | 1976617 | 70,842 | 0.070842 | 7.42 | 0.616 | | | | | | | | | 0.36 |
| 3/15/2014 | Angel Trujillo | 1976617 | 2061099 | 84,482 | 0.084482 | 7.40 | 0.616 | | | | | | | | | 0.43 |
| 3/16/2014 | Angel Trujillo | 2061099 | 2145582 | 84,483 | 0.084483 | 7.48 | 0.616 | | | | | | | | | 0.43 |
| 3/17/2014 | Angel Trujillo | 2145582 | 2217173 | 71,591 | 0.071591 | 7.46 | 0.616 | | | | | | | | | 0.37 |
| 3/18/2014 | Angel Trujillo | 2217173 | 2294552 | 77,379 | 0.077379 | 7.42 | 0.616 | | | | | | | | | 0.40 |
| 3/19/2014 | Angel Trujillo | 2294552 | 2374885 | 80,333 | 0.080333 | 7.52 | 0.616 | | | | | | | | | 0.41 |
| 3/20/2014 | Angel Trujillo | 2374885 | 2454558 | 79,673 | 0.079673 | 7.49 | 0.616 | | | | | | | | | 0.41 |
| 3/21/2014 | Angel Trujillo | 2454558 | 2532030 | 77,472 | 0.077472 | 7.50 | 0.616 | | | | | | | | | 0.40 |
| 3/22/2014 | Angel Trujillo | 2532030 | 2627583 | 95,553 | 0.095553 | 7.52 | 0.616 | | | | | | | | | 0.49 |
| 3/23/2014 | Angel Trujillo | 2627583 | 2693443 | 65,860 | 0.06586 | 7.27 | 0.616 | | | | | | | | | 0.34 |
| 3/24/2014 | Angel Trujillo | 2693443 | 2756617 | 63,174 | 0.063174 | 7.04 | 0.616 | | | | | | | | | 0.32 |
| 3/25/2014 | Angel Trujillo | 2756617 | 2839354 | 82,737 | 0.082737 | 7.41 | 0.616 | | | | | | | | | 0.43 |
| 3/26/2014 | Angel Trujillo | 2839354 | 2920077 | 80,723 | 0.080723 | 7.43 | 0.616 | <5.1 | 9.5 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.41 |
| 3/27/2014 | Angel Trujillo | 2920077 | 3000078 | 80,001 | 0.0800 | 7.52 | 0.616 | | | | | | | | | 0.41 |
| 3/28/2014 | Angel Trujillo | 3000078 | 3078623 | 78,545 | 0.078545 | 7.51 | 0.616 | | | | | | | | | 0.40 |
| 3/29/2014 | Angel Trujillo | 3078623 | 3175964 | 97,341 | 0.097341 | 7.45 | 0.616 | | | | | | | | | 0.50 |
| 3/30/2014 | Angel Trujillo | 3175964 | 3241501 | 65,537 | 0.065537 | 7.46 | 0.616 | | | | | | | | | 0.34 |
| 3/31/2014 | Angel Trujillo | 3241501 | 3310963 | 69,462 | 0.069462 | 7.46 | 0.616 | | | | | | | | | 0.36 |
| TOTAL | | | | 2,191,140 | 2.19114 | | | <5.1 | 9.5 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 97,341 | | | | | | | | | | | High: | 0.50 |
| | | | Average: | 70,682 | | | | | | | | | | | Average: | 0.36 |

WW

E

JB63247

| | | |

Accutest LabLink@788347 10:55 08-Apr-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-032814-A | | |
| Lab Sample ID: | JB63247-1 | Date Sampled: | 03/28/14 |
| Matrix: | AQ - Water | Date Received: | 03/28/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 616 | 10 | ug/l | 1 | 03/31/14 | 04/02/14 | RR | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 03/31/14 | 04/02/14 | RR | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 03/31/14 | 04/03/14 | ND | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 03/31/14 | 03/31/14 | DP | SW846 7470A [1] | SW846 7470A [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 03/31/14 | 04/02/14 | RR | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 03/31/14 | 04/02/14 | RR | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA33637
(2) Instrument QC Batch: MA33658
(3) Instrument QC Batch: MA33671
(4) Prep QC Batch: MP78641
(5) Prep QC Batch: MP78649

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@788347 10:55 08-Apr-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-032814-A | | |
| **Lab Sample ID:** | JB63247-1 | **Date Sampled:** | 03/28/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/28/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 9.5 | 3.4 | mg/l | 1 | 03/28/14 19:17 | LS | SM5210 B-01 |
| Solids, Total Suspended | 12.0 | 4.0 | mg/l | 1 | 03/31/14 | KP | SM2540 D-11 |
| pH [a] | 6.75 | | su | 1 | 03/28/14 17:35 | MB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@788347 10:55 08-Apr-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-032814-B | | |
| Lab Sample ID: | JB63247-2 | Date Sampled: | 03/28/14 |
| Matrix: | AQ - Water | Date Received: | 03/28/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T196385.D | 1 | 03/31/14 | DS | n/a | n/a | VT8000 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA PPL List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.8 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.9 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.31 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 21.8 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.4 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.63 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 56.1 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 97% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 101% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 97% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 98% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@788347 10:55 08-Apr-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-032814-B | | |
| **Lab Sample ID:** | JB63247-2 | **Date Sampled:** | 03/28/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/28/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 03/30/14 | JOO | EPA 1664A |

RL = Reporting Limit

Accutest LabLink@788347 10:55 08-Apr-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWI-032814 | | |
| Lab Sample ID: | JB63247-3 | Date Sampled: | 03/28/14 |
| Matrix: | AQ - Water | Date Received: | 03/28/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T196426.D | 1 | 04/01/14 | DS | n/a | n/a | VT8002 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA PPL List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 3.4 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 6.7 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.38 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 25.6 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | 0.46 | 1.0 | 0.24 | ug/l | J |
| 156-60-5 | trans-1,2-Dichloroethene | 4.1 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.70 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 103 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | 14.9 | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 95% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 102% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 96% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 96% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

**6/13/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

June 13, 2014

***Via Express Mail***

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-05**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from May 1 – May 31, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: May 2014 SA-6/7 Combined Monthly Progress Report No. 2014-05

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2014-05
## Project SA-6 & 7 Remediation

# May 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 05/02/14 | Summary of Hydrocarbon-Impacted Soil Encountered<br>Study Area 6 South, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/06/14 | Summary of the Technical Evaluation Program of the SiteVision Technology<br>Chromium Remedy In-Situ Treatment Program<br>SA-6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/14/14 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2014-04<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/15/14 | NJPDES Permit NJ0156311: April 2014 Surface Water Discharge Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | New Jersey Department of Environmental Protection<br>Division of Water Quality |
| 05/15/14 | Bayfront Redevelopment at 525 & 575 Route 440, Jersey City, MR 1 and MR 2<br>Permit ID# 31630016<br>*(see **Attachment 12**)* | Andy Caltagirone<br>PVSC |
| 05/15/14 | Discharge of Tannin Construction Water<br>Customer ID# 31630005-1<br>Study Area 7, Jersey City, NJ | Andy Caltagirone<br>PVSC |
| 05/16/14 | Response to Comments Provided by Plaintiffs, April 8, 2014, Two-Year Summary Report for In-Situ Chromium Mass Removal from S-3 Sand<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/16/14 | Surcharge Monitoring Plan – Monthly Report No. 1<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/19/14 | Design Change Bulletin – Degen Deferred Area<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/22/14 | Special Master All Hands Conference Call | N/A |
| 05/27/14 | Documentation and Remedial Action Summary Report<br>Study Area 7 Sediment Remedy, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/28/14 | Long Term Monitoring Program - First Five Year Implementation Plan<br>Study Area 7 Sediment Remedy, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 05/04/2014 | 05/11/2014 | 05/18/2014 | 05/25/2014 | 06/01/2014 |
| Construction Management (AMEC) | 9 | 10 | 10 | 10 | 10 |
| Engineering (AMEC) | 2 | 2 | 2 | 1 | 1 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 32 | 40 | 42 | 47 | 45 |
| Arecon/US Ecology Subcontractors | 1 | 1 | 1 | 1 | 1 |
| OSC (80 Kellogg Demolition) | 5 | 3 | 0 | 0 | 0 |
| ENR (SA-6N GWTP Utilities) | 0 | 0 | 0 | 1 | 3 |
| Siemens | 1 | 1 | 1 | 1 | 1 |
| HBS (SA-6N GWTP Security System) | 1 | 0 | 0 | 0 | 0 |
| Other | 0 | 0 | 0 | 0 | 0 |
| **TOTAL** | **55** | **61** | **60** | **65** | **65** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued new Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Continued well abandonment activities in accordance with approved Monitoring Well Abandonment Plan.
- Completed former 80 Kellogg St GWTP and truck wash demolition activities.
- Collected May PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Non-chromium activities, ARCADIS continues to work with NJDEP on the modification to the existing NJDEP-Discharge to Groundwater Permit by Rule for additional Enhanced Anaerobic in-situ bioremediation (EAISB) injections planned for JCMUA and JCDPW UST Areas.

## C. SA-6 N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on April 23, 2014.

- Completed installation of asphalt ramps associated with the north and south tanker offloading pads and the roll off garage door

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 05/04/2014 | 05/11/2014 | 05/18/2014 | 05/25/2014 | 06/01/2014 |
| Avg. Gallons Treated & Discharged (per day) | 79,342 | 78,825 | 79,068 | 81,360 | 78,896 |
| Average Flow (gpm) for Operating Period | 55 | 54 | 55 | 56 | 55 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 | 24 |
| GWTP InfluentTanks (gal.) | 13,132 | 11,058 | 12,258 | 11,560 | 12,698 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in Cells 139A through 125A and 146B through 126B.
- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 0 | 0 | 0 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 223 | 21.8 | 4,868 |
| **Entact/ Montecalvo** | Tri-axle Dump | Bayshore Recycling | NA | Non Haz Petroleum Soil | 041 | 24.98 | 1,024. |
| **Entact/ Montecalvo** | 30yd Roll Off | NJMC Landfill | NA | Non Haz Concrete | 21 | 22.3 | 468 |
| **OSC** | 30yd Roll Off | 375 RT 1-9 South Jersey | IWS | C&D | 30 | 13.1 | 393 |
| **OSC** | 40yd Roll Off | Cinelli JC | Cinelli | Light Iron | 9 | 6.1 | 55.6 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 128B-126B, 126A-125A |
| **Excavation Completed** | Cell Number(s) 139A –127A, 146B-129B Volume Excavated - Total for Reporting Period: 11,420 CY/ Total to Date: 62,619 CY |
| **Backfill in Progress** | Cell Number(s) 1 through 58, 152-128A, 146B-136B |

### 3. BACKFILL MATERIALS USED

| Source | (Week Ending) | | | | |
|---|---|---|---|---|---|
| | 05/04/2014 | 05/11/2014 | 05/18/2014 | 05/25/2014 | 06/01/2014 |
| <20ppm re-use, CY | 1,755 | 3,489 | 0 | 0 | 315 |
| Weldon, Import-Tons | 1,550. | 4,603 | 4,563 | 3,108 | 0 |
| Tilcon, Import-Tons DGA | 1,186 | 1,785 | 1,520 | 550 | 302 |
| Tilcon, Import Tons – 1.5" Stone | 0 | 0 | 126.07 | 0 | 201 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Instrumentation Installation ~90% complete. One instrument location and the settlement platforms over the perimeter pool remain to be installed. Completion of instrumentation installation is scheduled for June2014. No Surcharge initiated.
- Area 2S: Instrumentation Installation ~75% complete. Completion of instrument installation deferred pending completion of 80 Kellogg demolition activities. No Surcharge initiated.
- Area 3S: Instrumentation Installation 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. No Surcharge initiated.
- Area 1N: Instrumentation Installation ~100% complete. Placement of surcharge material initiated on April 8, 2014. As of May 30$^{th}$ approx. 80% of surcharge has been placed. The results of the monitoring provided in Surcharge Monitoring Report #2 to be submitted under separate cover.
- Area 2N: No instrumentation installed. Initial surcharge instrument data to be submitted under separate cover.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Forty Eight (48) pairs driven on the hydraulic barrier wall from Sta 12+70 to 14+90+65 on SA-6 South.
- The grout angle on one sheet pair (designated 20P-15) was dislodged from the sheet during driving. A new angle will be installed when the joint is exposed during excavation. The angle will be flushed and grouted following backfill.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete placement of surcharge materials in SA-6N Area 1N.
- Begin placement of surcharge materials in SA-6S Area 1S.
- Continue installation of the contingent groundwater system on SA-6S.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 125to 108. Continue stockpiling of presumed <20 mg/kg for additional sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Conduct S-3 Injection/Mass Removal Event No.14 in well 088-IW-03 (completed on June 1, 2014.)

- Conduct quarterly LTMP groundwater level measurement round.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-5)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. Groundwater Quality Data Surcharge Monitoring Update *(provided on a quarterly basis - not available as of this report date)*
   - Summary of Groundwater Quality Data from GWET Wells
   - Quarterly Water Wells
   - Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells
9. Surcharge Monitoring Update
   - Instrumentation Location Plan 1S
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Deflection Along Open Excavation
    - Sheet Pile Repair Log
    - Vibration Monitoring Update
11. Weekly SWPPP Reports
12. GWTP Update
    - 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (April 2014)
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (April 2014)
13. SA-6 North & South Design Change Tracking Log

## Attachment 1:  Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Wed 5/28/14

Task Milestone Summary Critical

## Attachment 2:  Site Photographs




**Site Photograph 1:** Backfill material is placed in the excavation.




**Site Photograph 2:** Contractor excavates materials in western area of Kellogg St.




**Site Photograph 3:** Contractor installs hydraulic barrier sheetpile on Kellogg St Properties.




**Site Photograph 4:** Contractor loads out soil for off-site disposal.




**Site Photograph 5:** Contractor loads surcharge material for use on JC Properties.




**Site Photograph 6:** Contractor performs compaction testing on Kellogg St Properties.




**Site Photograph 7:** Drilling contractor install settlement monitoring equipment.





**Site Photograph 8:** Geotextile is placed in preparation for backfilling.


## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points)
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of June 1, 2014

May 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill




LEGEND
CONFIRMATORY BOTTOM SAMPLE ELEVATION
CONFIRMATORY SIDEWALL SAMPLE ELEVATION
0.0 POINT ELEVATION
POINT POINT DESCRIPTION
BOTTOM CENTER POINT ELEVATION STRATUM D
BOTTOM CENTER POINT ELEVATION <20 PPM
BOTTOM CORNER POINT ELEVATION <20 PPM
DESIGNED STRATUM O EXCAVATION LIMIT
PREVIOUSLY SUBMITTED DATA
CURRENT EXCAVATION TO STRATUM D
CURRENT EXCAVATION TO <20 PPM
TOP OF EXCAVATION SLOPE
LIMIT OF EXCAVATION AREA
ENTACT 302 Unity Plaza Latrobe, PA 15650
DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 05-22-14 TO 06-05-14
PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |

2 This is the Bottom Elevation identified In the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**



6/6/14

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 21.1 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 2 | BF-07 | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | 38 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | 39 | Stratum O | Bottom of excavation elevation - Stratum O | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | 40 | Stratum D | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | 42 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | 44 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | 46 | Stratum D | Bottom of excavartion elevation | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | 48 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | 50 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.


Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run agair





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 5 Tests per Acre**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-01 | | 684158.6 | 603152.4 | | | | | | | 6 | | | |
| | RF-02 | | 684190.6 | 603063.9 | | | | | | | 12 | | | |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | 25 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | 44 | Type A Material | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 5 Tests per Acre**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 126.8 | 4.5 | 124.5 | 12.1 | 102 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 124.5 | 12.1 | 100 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | 140 (B) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 140 (B) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 140 (B) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | 142 (A) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 142 (A) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 142 (A) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | 152 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 151 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 151 | Weldon WC Screenings | | V5N |
| 3 | RF-39-04 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 151 | Weldon WC Screenings | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b.

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C.

Bottom of excavation elevation based on Maser survey data (Center Point elevations).


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-5)

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 04/01/14 | 1 | 24 | 9,EPS | 14 | 234,816 | 254,072 | 19,256 | 1,482,461 | 13.4 | |
| 04/02/14 | 1 | 24 | 9,EPS | 14 | 254,072 | 272,724 | 18,652 | 1,501,113 | 13.0 | |
| 04/03/14 | 1 | 24 | 9,EPS | 14 | 272,724 | 292,383 | 19,659 | 1,520,772 | 13.7 | |
| 04/04/14 | 1 | 24 | 9,EPS | 14 | 292,383 | 310,862 | 18,479 | 1,539,251 | 12.8 | |
| 04/07/14 | 1 | 72 | 9,EPS | 14 | 310,862 | 361,008 | 50,146 | 1,589,397 | 11.6 | |
| 04/08/14 | 1 | 24 | 9,EPS | 14 | 361,008 | 375,723 | 14,715 | 1,604,112 | 10.2 | |
| 04/09/14 | 1 | 24 | 9,EPS | 14 | 375,723 | 389,220 | 13,497 | 1,617,609 | 9.4 | |
| 04/10/14 | 1 | 24 | 9,EPS | 14 | 389,220 | 403,320 | 14,100 | 1,631,709 | 9.8 | |
| 04/11/14 | 1 | 24 | 9,EPS | 14 | 403,320 | 416,137 | 12,817 | 1,644,526 | 8.9 | |
| 04/14/14 | 1 | 72 | 9,EPS | 14 | 416,137 | 453,580 | 37,443 | 1,681,969 | 8.7 | |
| 04/15/14 | 1 | 24 | 9,EPS | 14 | 453,580 | 464,088 | 10,508 | 1,692,477 | 7.3 | |
| 04/16/14 | 1 | 24 | 9,EPS | 14 | 464,088 | 473,709 | 9,621 | 1,702,098 | 6.7 | |
| 04/17/14 | 1 | 24 | 9,EPS | 14 | 473,709 | 484,453 | 10,744 | 1,712,842 | 7.5 | |
| 04/18/14 | 1 | 24 | 9,EPS | 14 | 484,453 | 492,855 | 8,402 | 1,721,244 | 5.8 | |
| 04/18/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | N/A | N/A | 21,000 | 1,742,244 | 14.6 | Flow meter not installed. Volumes based on tank gauging |
| 04/21/14 | 1 | 72 | 9,EPS | 14 | 492,855 | 518,050 | 25,195 | 1,767,439 | 5.8 | |
| 04/18/14 | 2 | 72 | 16,17,18,WPS-1 | 40 | N/A | N/A | 62,000 | 1,829,439 | 14.4 | Flow meter not installed. Volumes based on tank gauging |
| 04/22/14 | 1 | 24 | 9,EPS | 14 | 518,050 | 523,548 | 5,498 | 1,834,937 | 3.8 | |
| 04/22/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | N/A | N/A | 19,500 | 1,854,437 | 13.5 | Flow meter not installed. Volumes based on tank gauging |
| 04/23/14 | 1 | 24 | 9,EPS | 14 | 523,548 | 528,369 | 4,821 | 1,859,258 | 3.3 | |
| 04/23/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | 0 | 15,441 | 15,441 | 1,874,699 | 10.7 | |
| 04/24/14 | 1 | 24 | 9,EPS | 14 | 528,369 | 532,995 | 4,626 | 1,879,325 | 3.2 | |
| 04/24/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | 15,441 | 30,198 | 14,757 | 1,894,082 | 10.2 | |
| 04/25/14 | 1 | 24 | 9,EPS | 14 | 532,995 | 537,006 | 4,011 | 1,898,093 | 2.8 | |
| 04/25/14 | 2 | 24 | 16,17,18,WPS-1 | 40 | 30,198 | 41,737 | 11,539 | 1,909,632 | 8.0 | |
| 04/28/14 | 1 | 72 | 9,EPS | 12 | 537,006 | 552,302 | 15,296 | 1,924,928 | 3.5 | |
| 04/28/14 | 2 | 72 | 16,17 | 18 | 41,737 | 59,981 | 18,244 | 1,943,172 | 4.2 | |
| 04/29/14 | 1 | 24 | 9,EPS | 12 | 552,302 | 555,724 | 3,422 | 1,946,594 | 2.4 | |
| 04/29/14 | 2 | 24 | 16,17 | 18 | 59,981 | 62,592 | 2,611 | 1,949,205 | 1.8 | |
| 04/30/14 | 1 | 24 | 9,EPS | 12 | 555,724 | 560,143 | 4,419 | 1,953,624 | 3.1 | |
| 04/30/14 | 2 | 24 | 16,17 | 18 | 62,592 | 65,318 | 2,726 | 1,956,350 | 1.9 | |
| 05/01/14 | 1 | 24 | 9,EPS | 12 | 560,143 | 563,407 | 3,264 | 1,959,614 | 2.3 | |
| 05/01/14 | 2 | 24 | 16,17 | 18 | 65,318 | 67,350 | 2,032 | 1,961,646 | 1.4 | |
| 05/02/14 | 1 | 24 | 9,EPS | 12 | 563,407 | 571,007 | 7,600 | 1,969,246 | 5.3 | |
| 05/02/14 | 2 | 24 | 16,17 | 18 | 67,350 | 69,321 | 1,971 | 1,971,217 | 1.4 | |
| 05/05/14 | 1 | 72 | 9,EPS | 12 | 571,007 | 596,817 | 25,810 | 1,997,027 | 6.0 | |
| 05/05/14 | 2 | 72 | 16,17 | 18 | 69,321 | 75,193 | 5,872 | 2,002,899 | 1.4 | |
| 05/06/14 | 1 | 24 | 9,EPS | 12 | 596,817 | 604,513 | 7,696 | 2,010,595 | 5.3 | |
| 05/06/14 | 2 | 24 | 16,17 | 18 | 75,193 | 77,224 | 2,031 | 2,012,626 | 1.4 | |
| 05/07/14 | 1 | 24 | 9,EPS | 12 | 604,513 | 612,024 | 7,511 | 2,020,137 | 5.2 | |
| 05/07/14 | 2 | 24 | 16,17 | 18 | 0 | 361 | 361 | 2,020,498 | 0.3 | Flowmeter Reset |
| 05/08/14 | 1 | 24 | 9,EPS | 12 | 612,024 | 617,958 | 5,934 | 2,026,432 | 4.1 | |
| 05/08/14 | 2 | 24 | 16 | 12 | 361 | 4,243 | 3,882 | 2,030,314 | 2.7 | |
| 05/09/14 | 1 | 24 | 9,EPS | 12 | 617,958 | 618,262 | 304 | 2,030,618 | 0.2 | |
| 05/09/14 | 2 | 24 | 16 | 12 | 4,243 | 4,886 | 643 | 2,031,261 | 0.4 | |
| 05/12/14 | 1 | 72 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,031,261 | 0.0 | |
| 05/12/14 | 2 | 72 | 16 | 12 | 4,886 | 6,201 | 1,315 | 2,032,576 | 0.3 | |
| 05/13/14 | 1 | 24 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 05/14/14 | 1 | 24 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 05/15/14 | 1 | 24 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 05/19/14 | 1 | 72 | 9,EPS | 13 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013; Vac plant #1 taken out of service May 19, 2014
Previous information is trunketed. Only last month and current month information is provided.

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-5)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 04/25/14 | 24 | 0 | 6,883 | 6,883 | 6,883 | 4.8 | |
| 04/28/14 | 72 | 6,883 | 30,393 | 23,510 | 30,393 | 5.4 | |
| 04/29/14 | 24 | 30,393 | 37,639 | 7,246 | 37,639 | 5.0 | |
| 04/30/14 | 24 | 37,639 | 43,518 | 5,879 | 43,518 | 4.1 | |
| 05/01/14 | 24 | 43,518 | 51,195 | 7,677 | 51,195 | 5.3 | |
| 05/02/14 | 24 | 51,195 | 57,459 | 6,264 | 57,459 | 4.4 | |
| 05/05/14 | 72 | 57,459 | 62,329 | 4,870 | 62,329 | 1.1 | Flowmeter Reset |
| 05/06/14 | 24 | 0 | 27,630 | 27,630 | 89,959 | 19.2 | |
| 05/07/14 | 24 | 27,630 | 31,613 | 3,983 | 93,942 | 2.8 | |
| 05/08/14 | 24 | N/A | N/A | 7,500 | 101,442 | 5.2 | Flowmeter Blockage (Tank Measured) |
| 05/09/14 | 24 | N/A | N/A | 8,000 | 109,442 | 5.6 | Flowmeter Blockage (Tank Measured) |
| 05/12/14 | 72 | N/A | N/A | 25,500 | 134,942 | 5.9 | Flowmeter Blockage (Tank Measured) |
| 05/13/14 | 24 | 31,613 | 32,142 | 529 | 135,471 | 0.4 | |
| 05/14/14 | 24 | 32,142 | 34,250 | 2,108 | 137,579 | 1.5 | |
| 05/15/14 | 24 | 34,250 | 36,358 | 2,108 | 139,687 | 1.5 | Well Taken Offline for Excavation |
| 05/29/14 | 24 | 0 | 4,322 | 4,322 | 144,009 | 3.0 | |
| 05/30/14 | 24 | 4,322 | 8,634 | 4,312 | 148,321 | 3.0 | |

Notes: Deep Wells DW-1 and DW-2 had no flows during May.

## Attachment 5:  Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER START (KGal) | DISCHARGE FLOW METER FINISH (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 04/01/14 | 8.0 | 6,575.85 | 6,717.81 | 141,960 | 6,717,360 | |
| 04/02/14 | 8.0 | 6,717.81 | 6,951.38 | 233,570 | 6,950,930 | |
| 04/03/14 | 8.0 | 6,951.38 | 7,050.47 | 99,090 | 7,050,020 | PVSC Compliance Sample collected |
| 04/04/14 | 8.0 | 7,050.47 | 7,173.74 | 123,270 | 7,173,290 | |
| 04/05/14 | 8.0 | 7,173.74 | 7,250.14 | 76,400 | 7,249,690 | |
| 04/08/14 | 8.0 | 7,250.14 | 7,452.80 | 202,660 | 7,452,350 | |
| 04/09/14 | 8.0 | 7,452.80 | 7,538.06 | 85,260 | 7,537,610 | |
| 04/10/14 | 8.0 | 7,538.06 | 7,687.85 | 149,790 | 7,687,400 | |
| 04/11/14 | 8.0 | 7,687.85 | 7,810.35 | 122,500 | 7,809,900 | |
| 04/14/14 | 6.0 | 7,810.35 | 7,883.23 | 72,880 | 7,882,780 | |
| 04/15/14 | 6.0 | 7,883.23 | 7,948.35 | 65,120 | 7,947,900 | |
| 04/16/14 | 8.0 | 7,948.35 | 8,036.99 | 88,640 | 8,036,540 | |
| 04/17/14 | 8.0 | 8,036.99 | 8,120.52 | 83,530 | 8,120,070 | |
| 04/18/14 | 8.0 | 8,120.52 | 8,241.81 | 121,290 | 8,241,360 | |
| 04/19/14 | 8.0 | 8,241.81 | 8,416.26 | 174,450 | 8,415,810 | |
| 04/21/14 | 8.0 | 8,416.26 | 8,503.96 | 87,700 | 8,503,510 | |
| 04/22/14 | 8.0 | 8,503.96 | 8,649.60 | 145,640 | 8,649,150 | |
| 04/23/14 | 8.0 | 8,649.60 | 8,775.22 | 125,620 | 8,774,770 | |
| 04/24/14 | 8.0 | 8,775.22 | 8,877.66 | 102,440 | 8,877,210 | |
| 04/25/14 | 8.0 | 8,877.66 | 8,949.22 | 71,560 | 8,948,770 | |
| 04/26/14 | 8.0 | 8,949.22 | 9,030.24 | 81,020 | 9,029,790 | |
| 04/27/14 | 0.0 | 9,030.24 | 9,030.24 | 0 | 9,029,790 | |
| 04/28/14 | 8.0 | 9,030.24 | 9,133.26 | 103,020 | 9,132,810 | |
| 04/29/14 | 9.0 | 9,133.26 | 9,371.72 | 238,460 | 9,371,270 | |
| 04/30/14 | 0.0 | 9,371.72 | 9,371.72 | 0 | 9,371,270 | |
| 05/01/14 | 12.0 | 9,371.72 | 9,550.80 | 179,080 | 9,550,350 | |
| 05/02/14 | 23.5 | 9,665.35 | 9,775.14 | 224,340 | 9,774,690 | Includes system operation from 05/01/12 |
| 05/03/14 | 21.0 | 9,921.23 | 10,020.57 | 245,430 | 10,020,120 | Includes system operation from 05/02/13 |
| 05/05/14 | 37.0 | 10,377.22 | 10,584.99 | 564,420 | 10,584,540 | Includes system operation through 5/3, 5/4 and 05/04/14 |
| 05/06/14 | 9.5 | 10,584.99 | 10,825.62 | 240,630 | 10,825,170 | |
| 05/07/14 | 7.5 | 10,825.62 | 11,006.06 | 180,440 | 11,005,610 | PVSC Compliance Sample collected |
| 05/08/14 | 4.5 | 11,006.06 | 11,112.94 | 106,880 | 11,112,490 | |
| 05/09/14 | 6.0 | 1,112.94 | 11,253.32 | 140,380 | 11,252,870 | |
| 05/12/14 | 7.0 | 11,253.32 | 11,439.87 | 186,550 | 11,439,420 | |
| 05/13/14 | 7.0 | 11,439.87 | 11,600.00 | 160,130 | 11,599,550 | |
| 05/14/14 | 6.5 | 11,600.00 | 11,712.86 | 112,860 | 11,712,410 | |
| 05/15/14 | 5.5 | 11,712.86 | 11,810.42 | 97,560 | 11,809,970 | |
| 05/16/14 | 6.0 | 11,810.42 | 11,885.46 | 75,040 | 11,885,010 | |
| 05/18/14 | 2.8 | 11,885.46 | 11,960.68 | 75,220 | 11,960,230 | |
| 05/19/14 | 7.0 | 11,960.68 | 12,098.90 | 138,220 | 12,098,450 | |
| 05/20/14 | 7.0 | 12,098.90 | 12,188.74 | 89,840 | 12,188,290 | |
| 05/21/14 | 5.0 | 12,188.74 | 12,262.55 | 73,810 | 12,262,100 | |
| 05/22/14 | 7.5 | 12,262.55 | 12,329.43 | 66,880 | 12,328,980 | |
| 05/23/14 | 7.5 | 12,329.43 | 12,405.66 | 76,230 | 12,405,210 | |
| 05/24/14 | 5.0 | 12,405.66 | 12,482.60 | 76,940 | 12,482,150 | |
| 05/25/14 | 2.0 | 12,482.60 | 12,527.46 | 44,860 | 12,527,010 | |
| 05/27/14 | 5.5 | 12,527.46 | 12,662.13 | 134,670 | 12,661,680 | |
| 05/28/14 | 2.0 | 12,662.13 | 12,696.70 | 34,570 | 12,696,250 | |
| 05/29/14 | 7.0 | 12,696.70 | 12,809.54 | 112,840 | 12,809,090 | |
| 05/30/14 | 7.0 | 12,809.54 | 12,906.92 | 97,380 | 12,906,470 | |

Notes: Previous Information is truncated. Only last month and current morth information is provided.
Yellow cells contain information that was revised after the 2014-04 Report submittal.

## Attachment 6:  Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 47-57 | <20 | 124-57-20-a | 860 | 124-57-20-a1 | 4/4/2014 | 12:30 | 17.0 | Yes | | |
| | | | | 124-57-20-a2 | 4/4/2014 | 12:35 | 3.8 | Yes | | |
| | | | | 124-57-20-a3 | 4/4/2014 | 12:40 | 4.2 | Yes | | |
| | | | | 124-57-20-a4 | 4/4/2014 | 12:45 | <0.52 | Yes | | |
| 47-57 | <20 | 124-57-20-b | 860 | 124-57-20-b1 | 4/4/2014 | 12:50 | 4.1 | Yes | | |
| | | | | 124-57-20-b2 | 4/4/2014 | 12:55 | 14.2 | Yes | | |
| | | | | 124-57-20-b3 | 4/4/2014 | 13:00 | 15.7 | Yes | | |
| | | | | 124-57-20-b4 | 4/4/2014 | 13:05 | <0.49 | Yes | | |
| 47-57 | <20 | 124-57-20-c | 860 | 124-57-20-c1 | 4/4/2014 | 13:10 | 10.3 | Yes | | |
| | | | | 124-57-20-c2 | 4/4/2014 | 13:15 | 11.6 | Yes | | |
| | | | | 124-57-20-c3 | 4/4/2014 | 13:20 | 8.9 | Yes | | |
| | | | | 124-57-20-c4 | 4/4/2014 | 13:25 | 41.4 | | Yes | |
| 49-59 | >1000 | 124-59-1000-a | 800 | 124-59-1000-a1 | 4/11/2014 | 8:00 | 11,000 | | | Yes |
| | | | | 124-59-1000-a2 | 4/11/2014 | 8:05 | 26,900 | | | Yes |
| | | | | 124-59-1000-a3 | 4/11/2014 | 8:10 | 11,900 | | | Yes |
| | | | | 124-59-1000-a4 | 4/11/2014 | 8:15 | 32,700 | | | Yes |
| 57,58 144-152 | <20 | 124-152-20-a | 800 | 124-152-20-a1 | 4/23/2014 | 15:00 | 0.73 | Yes | | |
| | | | | 124-152-20-a2 | 4/23/2014 | 15:05 | 0.76 | Yes | | |
| | | | | 124-152-20-a3 | 4/23/2014 | 15:10 | 0.42 | Yes | | |
| | | | | 124-152-20-a4 | 4/23/2014 | 15:15 | 1.2 | Yes | | |
| 135,141,143-145 | <20 | 124-145-20-a | 675 | 124-145-20-a1 | 5/9/2014 | 9:00 | 22.8 | | Yes | |
| | | | | 124-145-20-a2 | 5/9/2014 | 9:05 | 0.4 | Yes | | |
| | | | | 124-145-20-a3 | 5/9/2014 | 9:10 | 5.4 | Yes | | |
| | | | | 124-145-20-a4 | 5/9/2014 | 9:15 | 3.0 | Yes | | |
| 139-142B, 131-132A | <20 | 124-142-20-a | 1000 | 124-142-20-a1 | 5/15/2014 | 11:00 | 2.1 | Yes | | |
| | | | | 124-142-20-a2 | 5/15/2014 | 11:05 | 8.7 | Yes | | |
| | | | | 124-142-20-a3 | 5/15/2014 | 11:10 | 5.9 | Yes | | |
| | | | | 124-142-20-a4 | 5/15/2014 | 11:15 | 4.3 | Yes | | |
| 135-138B, 131A | <20 | 124-138-20-a, b | 1500 | 124-138-20-a1 | 5/19/2014 | 10:45 | 4.0 | Yes | | |
| | | | | 124-138-20-a2 | 5/19/2014 | 10:50 | 10.2 | Yes | | |
| | | | | 124-138-20-a3 | 5/19/2014 | 10:55 | 5.7 | Yes | | |
| | | | | 124-138-20-a4 | 5/19/2014 | 11:00 | 3.9 | Yes | | |
| | | | | 124-138-20-b1 | 5/19/2014 | 11:05 | 1.2 | Yes | | |
| | | | | 124-138-20-b2 | 5/19/2014 | 11:10 | 4.9 | Yes | | |
| | | | | 124-138-20-b3 | 5/19/2014 | 11:15 | 2.7 | Yes | | |
| | | | | 124-138-20-b4 | 5/19/2014 | 11:20 | 5.4 | Yes | | |
| 129-134 | <20 | 124-134-20-a, b | 1250 | 124-134-20-a1 | 5/21/2014 | 13:10 | 7.5 | ** | | |
| | | | | 124-134-20-a2 | 5/21/2014 | 13:15 | 7.8 | ** | | |
| | | | | 124-134-20-a3 | 5/21/2014 | 13:20 | 4.2 | ** | | |
| | | | | 124-134-20-a4 | 5/21/2014 | 13:25 | 30.5 | | ** | |
| | | | | 124-134-20-b1 | 5/21/2014 | 13:30 | 10.7 | ** | | |
| | | | | 124-134-20-b2 | 5/21/2014 | 13:35 | 2.5 | ** | | |
| | | | | 124-134-20-b3 | 5/21/2014 | 13:40 | 4.9 | ** | | |
| | | | | 124-134-20-b4 | 5/21/2014 | 13:45 | 7.3 | ** | | |

**Notes:**
*Material currently stockpiled. Pending final placement.

## Attachment 7:  Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
05-07-2014


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


May 07, 2014 at 4:13pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | | 134- | 140- | | North | | | | South | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-1 | FS-3 | FS-4 | FS-5 |
| Date | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | 7.5 | 7.9 | 7.7 | 5.9 |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | 7.7 | 8.1 | 7.9 | 7.2 |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | 7.6 | 7.8 | 7.6 | 8.0 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells and perimeter pool risers are temporarily inaccessible:
134-MW-V09, N3W, N4E, N4W, E1A-SO


## Attachment 8: Quality and Level Data in GWET Wells


(not available as of this report date - provided on a quarterly basis)

- Summary of Groundwater Quality Data from GWET Wells
- Quarterly Water Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells

## Attachment 9:  Surcharge Monitoring Update

- Instrumentation Location Plan 1S




Installed Instrumentation Locations

Instrumentation Locations Not Installed

Revised DCB 001 7/29/13

| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–1 | 685276.02 | 601927.05 |
| FS–2 | 685323.86 | 601748.51 |
| HS–1 | 685597.02 | 601567.16 |
| HS–2 | 685511.42 | 601690.72 |
| HS–3 | 685421.98 | 601800.88 |
| HS–4 | 685313.18 | 601947.19 |
| HS–5 | 685480.23 | 601623.90 |
| HS–6 | 685518.78 | 601480.25 |
| HS–7 | 685413.06 | 601624.11 |
| HS–8 | 685204.27 | 601911.97 |
| VI–1 | 685624.44 | 601515.06 |
| VI–2 | 685578.58 | 601462.08 |
| VRC–1 | 685505.92 | 601505.39 |
| VRC–2 | 685434.27 | 601785.68 |
| VRC–3 | 685262.85 | 601914.43 |
| SP–1 | 685567.71 | 601633.29 |
| SP–2 | 685410.62 | 601852.31 |
| SP–3 | 685276.93 | 602033.96 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 07/19/13
Checked/Date: AE 07/19/13

Honeywell
101 COLUMBIA RD., BOX 2106
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY


amec

INSTRUMENTATION LOCATION PLAN 1S


Figure F1

## Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Monitoring Locations
- Sheet Pile Repair Log
- Vibration Monitoring Update




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 5+00 | 12+80 | -20' | AZ 19-700 |
| STRUCTURAL | 12+80 | 17+80 | -30' | AZ 19-700 |
| STRUCTURAL | 17+80 | 19+00 | -9' | AZ 19-700 |




NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04932400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | | RJR | TDD |

ISSUED FOR CONSTRUCTION

| BY | APVD |
|---|---|
| TDD | SHM |

REVISION

SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INC. LOANING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE


amec
Environment & Infrastructure, Inc
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-202 |
| SHEET | 54 OF 66 |

PLOT DATE: Wed 22 May 2013 PLOT TIME: 2:47 PM




BEFORE DRIVING SHEETS




SHEET SEALING DETAIL (BF) TYP S-203
NTS

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |
| STRUCTURAL | 19+00 | 21+20 | -19 | AZ 19-700 |
| STRUCTURAL | 21+20 | 23+20 | -15 | AZ 19-700 |
| STRUCTURAL | 23+20 | 24+37 | -12 | AZ 19-700 |
| NON STRUCTURAL | 24+37 | 25+89 | -12 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

0 20 40 80 SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

0 5 10 20 SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | TDD | RJR | TDD |

ISSUED FOR CONSTRUCTION

| BY | APVD |
|---|---|
| TDD | SHM |

SHM LICENSE NUMBER 24GF04012240 NJ PROFESSIONAL ENGINEER

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED BY WRITING BY AMEC.

Honeywell
101 COLUMBIA RD BOX 2105 MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 -2829
NJ Certificate of Authorization Number 24GA28016900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-203 |
| SHEET | 55 OF 66 |

# Sheet Deflection Along Open Excavation-West




Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.
8. Deflections were not measurable due to the limited depth of cut for BM 98-100.




NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SHEET MONITORING LOCATIONS
03-20-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-7

Entact ID:

Date Exposed:

Describe Damage: (9) minor scrapes by excavator bucket - range in size from 1"Ø to 1"x10"

Damage Location (ft below top of sheet, inboard side outboard side): 7' - 10' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" brush

Repair Log Closure: AMEC Signature: BSL

Date: 5/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-6

Entact ID:

Date Exposed:

Describe Damage: (5) minor scrapes by excavator bucket - Range in size from 1/2" Ø to 1"x8"

Damage Location (ft below top of sheet, inboard side outboard side): 7'-10' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" Brush

Repair Log Closure: AMEC Signature: BSL

Date: 5/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14-P-8

Entact ID:

Date Exposed:

Describe Damage: (5) minor scapes by excavator bucket. Range in size 1/2" Ø to 1/2" x 10"

Damage Location (ft below top of sheet, inboard side outboard side): 7' to 12' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" brush

Repair Log Closure: AMEC Signature: BSL

Date: 5/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-9

Entact ID:

Date Exposed:

Describe Damage: (15) minor scrapes by excavator bucket. Range in size from

Damage Location (ft below top of sheet, inboard side outboard side): 6' to 12' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" brush

Repair Log Closure: AMEC Signature: BSL

Date: 5/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-10

Entact ID:

Date Exposed:

Describe Damage: (13) minor scapes by excavator bucket - range in size from 1"Ø - 4"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 6' - 12' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-11

Entact ID:

Date Exposed:

Describe Damage: (11) minor scrapes by excavator bucket - range in size from 2"Ø - ½" x 24"

Damage Location (ft below top of sheet, inboard side outboard side): 6' - 12' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-12

Entact ID:

Date Exposed:

Describe Damage: (11) minor scrapes by excavator bucket - range in size from 1"Ø - ½" x 24"

Damage Location (ft below top of sheet, inboard side outboard side): 6' - 12' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Epoxy applied w/ 3" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-13

Entact ID:

Date Exposed:

Describe Damage: (5) minor scrapes by excavator bucket - range in size from ½"Ø - 3" x 12"

Damage Location (ft below top of sheet, inboard side outboard side): 6' - 12' outboard

Date Repaired: 5/5/14

Inspected by: Brian Shea

Describe Repair: Carboline epoxy applied w/ 3" brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14-P-14

Entact ID:

Date Exposed: 5/7/14

Describe Damage

(1) Minor scrape by the excavator bucket - ½" x 2"

Damage Location (ft below top of sheet, inboard side outboard side)

9' outboard

Date Repaired: 5/8/14

Inspected by: Brian Shea

Describe Repair: pressure wash, grind w/ wire brush, apply epoxy w/ 4" brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-15

Entact ID:

Date Exposed:

Describe Damage: 5/7/14

(5) Minor scrapes by the excavator bucket - ½"x2", 1"Ø, ½"Ø

Damage Location (ft below top of sheet, inboard side outboard side)

6'-10' outboard

Date Repaired: 5/8/14

Inspected by: Brian Shea

Describe Repair: Pressure washed, prepared w/ wire brush, epoxy applied w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-16

Entact ID:

Date Exposed: 5/7/14

Describe Damage

(1) Minor scrape by the excavator bucket - 1"x4"

Damage Location (ft below top of sheet, inboard side outboard side)

8', outboard

Date Repaired: 5/8/14

Inspected by: Brian Shea

Describe Repair: pressure wash, grind w/ wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-17

Entact ID:

Date Exposed: 5/7/14

Describe Damage:

(5) Minor scrapes by the excavator bucket - ½"Ø, 1"Ø, 1"x5", 1x2", ½"Ø

Damage Location (ft below top of sheet, inboard side outboard side)

range from 6' to 10' - outboard

Date Repaired: 5/8/14

Inspected by: Brian Shea

Describe Repair: pressure wash, grind w/ wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-18

Entact ID:

Date Exposed: 5/8/14

Describe Damage:

(3) minor scrapes by the excavator bucket to expose bare steel- 1x2", 1"Ø, 2"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 8'-10' outboard

Date Repaired: 5/8/14

Inspected by: Brian Shea

Describe Repair: pressure wash, grind w/ wire brush, apply epoxy w/ 4" wire brush

Repair Log Closure: AMEC Signature:

Date:

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-19

Entact ID:

Date Exposed: 5/8/14

Describe Damage:

(3) large scrapes by the excavator bucket- 1x6", 3x6", 5"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 7-10' - outboard

Date Repaired: 5/8/14

Inspected by: Brian Shea

Describe Repair: pressure wash area, grind surface w/ wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature:

Date:

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 14P-26

Entact ID:

Date Exposed: ~~5/8~~ 5/9

Describe Damage:

(2) minor scrapes by the excavator bucket to expose bare steel- 1/2Ø, 1"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 11' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" brush

Repair Log Closure: AMEC Signature: BSL

Date: 5/22

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-1

Entact ID:

Date Exposed:

Describe Damage:

(5) scrapes by the excavator ~~(illegible)~~ 349E bucket to expose bare steel- 3" long, 1/2"Ø 4" x 1/2", 1" x 1/2", 3" x 1/2"

Damage Location (ft below top of sheet, inboard side outboard side): 1'-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, w/ 4" brush apply epoxy

Repair Log Closure: AMEC Signature: BSL

Date: 5/22

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-2

Entact ID:

Date Exposed:

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1"Ø, 3"x½", ½"Ø 2"x1", 7"x1/2"

Damage Location (ft below top of sheet, inboard side outboard side): 6'-9' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-4

Entact ID:

Date Exposed:

Describe Damage: (4) minor scrapes by the excavator bucket - 1x2", 2"x6", ½"Ø, 1"Ø, ~~5x6~~

Damage Location (ft below top of sheet, inboard side outboard side): 5'-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-3

Entact ID:

Date Exposed:

Describe Damage: (10) scrapes by Cat 349E excavator bucket - 1"Ø, 3"x½", ½"Ø, 1"Ø, 7"x1", 2"Ø, 3"x½", ½"Ø, 1"x2", 1"x3"

Damage Location (ft below top of sheet, inboard side outboard side): 4-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-5

Entact ID:

Date Exposed:

Describe Damage: (9) scrapes by Cat 349E excavator bucket - 1/2"Ø, ½"Ø, ¼"x6", 1"Ø, ½"x3", 1"Ø, ¼"x6", 2"Ø, ½"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 4'-8" outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-6

Entact ID:

Date Exposed:

Describe Damage:
(9) scrapes by Cat 349E excavator - 1/2"x4", 1"Ø, 1"x2", 1"Ø, 1/2"x24", 1/2"x3", 1/4"x36", 1/2"Ø

Damage Location (ft below top of sheet, inboard side outboard side):
3'-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure Wash, wire brush, apply epoxy w/ 4" wire brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-7

Entact ID:

Date Exposed:

Describe Damage:
(4) miner scrapes by Cat 349E excavator bucket - 1/2"Ø, 1/2"Ø, 1"x3", 1"x6".

Damage Location (ft below top of sheet, inboard side outboard side):
6'-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" wire brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-8

Entact ID:

Date Exposed:

Describe Damage:
(10) scrapes by the Cat 349E excavator bucket - 1/2"Ø, 1x2", 1"Ø, 1/2"x4", 1/2"Ø, 1"Ø, 1/2"x7", 1x2", 1/2"x12", 1/2"x18"

Damage Location (ft below top of sheet, inboard side outboard side): 7'-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-9

Entact ID:

Date Exposed:

Describe Damage:
(6) scrapes by the cat 349E excavator bucket - 1/4"x6", 1"Ø, 1"Ø, 1/2"x6", 1x2", 1/2Ø

Damage Location (ft below top of sheet, inboard side outboard side):
6'-10' outboard

Date Repaired:

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BS

Date: 5/22/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**February 27th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 2:12 PM until 3:12 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

Four sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


Vibration
Monitoring Point
WORK
AREA
HACKENSACK RIVER
CONSERVATION
EASEMENT
HYDRAULIC BARRIER
EXISTING SOIL CEMENT
BENTONITE WALL
GEOMEMBRANE GRADE
CONTOURS (TYP)

# Event Report

| | | | |
|---|---|---|---|
| **Histogram Start Time** | 14:12:45 February 27, 2014 | **Serial Number** | BA15371 V 10.60-8.17 BlastMate III/8 |
| **Histogram Finish Time Number** | 15:12:38 February 27, 2014 | **Battery Level** | 6.9 Volts |
| **of Intervals Range** | 766.00 at 5 seconds | **Unit Calibration** | January 29, 2014 by Instantel |
| **Sample Rate** | Geo:10.00 in/s | **File Name** | Q3715KE7.K90 |
| **Job Number:** | 1024sps | | |

**Notes** 1
Location: SA-6 North 72" in Force Main
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Post Event Notes**

**Extended Notes**

**Microphone**
**PSPL**
**ZC Freq**
**Channel Test**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.1000 | 0.190 | 0.0650 | in/s |
| **ZC Freq** | 32 | 43 | 28 | Hz |
| **Date** | Feb 27 /14 | Feb 27 /14 | Feb 27 /14 | |
| **Time** | 15:10:05 | 14:50:10 | 14:30:05 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.2 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.2 | |

**Peak Vector Sum** 0.196 in/s on February 27, 2014 at 14:50:10




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Mic: 0.00050 psi(L)/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 5th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 10:00 AM until 5:15 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

26 sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


HACKENSACK RIVER
VMP 1
VMP 2
VMP 3
VMP 4
WORK
AREA
ACTIVE 72" FORC. MAIN
CONSERVATION EASEMENT
HYDRAULIC BARRIER
EXISTING SOIL CEMENT BENTONITE WALL
GEOMEMBRANE GRADE CONTOURS (TYP)

# Event Report

**Histogram Start Time** 10:00 AM March 5, 2014
**Histogram Finish Time** 10:55 AM March 5, 2014
**Number of Intervals** 623.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q3715KDW.3A0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

VMP 1

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.145 | 0.0450 | in/s |
| **ZC Freq** | 39 | 30 | 27 | Hz |
| **Date** | Mar 5 /14 | Mar 5 /14 | Mar 5 /14 | |
| **Time** | 10:03:53 | 10:39:58 | 10:39:58 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.3 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.146 in/s on September 1, 1995 at 12:39:58




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div

Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 11:10:56 March 5, 2014
**Histogram Finish Time** 11:46:53 March 5, 2014
**Number of Intervals** 431.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F84C.E80

**Post Event Notes**
VMP 2

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0350 | 0.130 | 0.1000 | in/s |
| **ZC Freq** | 43 | 37 | 13 | Hz |
| **Date** | Mar 5 /14 | Mar 5 /14 | Mar 5 /14 | |
| **Time** | 11:14:56 | 11:31:21 | 11:11:56 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.2 | 7.4 | 7.4 | Hz |
| **Overswing Ratio** | 5.0 | 4.4 | 2.8 | |

**Peak Vector Sum** 0.131 in/s on March 5, 2014 at 11:31:21




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 11:47:42 March 5, 2014
**Histogram Finish Time** 12:07:17 March 5, 2014
**Number of Intervals** 234.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F84E.3I0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 2

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0400 | 0.1000 | 0.0400 | in/s |
| **ZC Freq** | 34 | 39 | 28 | Hz |
| **Date** | Mar 5 /14 | Mar 5 /14 | Mar 5 /14 | |
| **Time** | 11:58:02 | 11:51:07 | 12:05:37 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.2 | |

**Peak Vector Sum** 0.100 in/s on March 5, 2014 at 11:51:07




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 13:15:00 March 5, 2014
**Histogram Finish Time** 15:38:45 March 5, 2014
**Number of Intervals** 1725.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F84I.500


**Post Event Notes**

VMP 3

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0550 | 0.0600 | 0.0700 | in/s |
| **ZC Freq** | 34 | 32 | 28 | Hz |
| **Date** | Mar 5 /14 | Mar 5 /14 | Mar 5 /14 | |
| **Time** | 13:46:20 | 13:46:20 | 14:07:30 | |
| **Sensor Check** | Passed | Passed | Check | |
| **Frequency** | 7.6 | 7.3 | 7.8 | Hz |
| **Overswing Ratio** | 4.3 | 4.1 | 3.9 | |

**Peak Vector Sum** 0.0745 in/s on March 5, 2014 at 14:07:30




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 15:41:20 March 5, 2014
**Histogram Finish Time** 17:17:59 March 5, 2014
**Number of Intervals** 1159.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F84O.WW0

**Post Event Notes**
VMP 4

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.115 | 0.245 | 0.170 | in/s |
| **ZC Freq** | 28 | 28 | 27 | Hz |
| **Date** | Mar 5 /14 | Mar 5 /14 | Mar 5 /14 | |
| **Time** | 17:14:25 | 17:10:40 | 17:11:35 | |
| **Sensor Check** | Check | Passed | Passed | |
| **Frequency** | 7.8 | 7.3 | 7.5 | Hz |
| **Overswing Ratio** | 4.3 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.266 in/s on March 5, 2014 at 17:11:35




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 6th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 1:20 PM until 3:30 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

Five sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


HACKENSACK RIVER
VMP 1
VMP 5
WORK AREA
WORK AREA
CONSERVATION EASEMENT
HYDRAULIC BARRIER
EXISTING SOIL CEMENT BENTONITE WALL
GEOMEMBRANE GRADE CONTOURS (TYP)

# Event Report

**Histogram Start Time** 13:24:41 March 6, 2014
**Histogram Finish Time** 13:37:26 March 6, 2014
**Number of Intervals** 153.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F86D.950

**Post Event Notes**
VMP 1

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0450 | 0.0750 | 0.0750 | in/s |
| **ZC Freq** | 43 | 28 | 27 | Hz |
| **Date** | Mar 6 /14 | Mar 6 /14 | Mar 6 /14 | |
| **Time** | 13:33:11 | 13:33:11 | 13:33:11 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.0886 in/s on March 6, 2014 at 13:33:11




**Time Scale:** 5 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 13:49:49 March 6, 2014
**Histogram Finish Time** 15:29:00 March 6, 2014
**Number of Intervals** 1190.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F86E.F10


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 5

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0300 | 0.0600 | 0.0500 | in/s |
| **ZC Freq** | 37 | 34 | 28 | Hz |
| **Date** | Mar 6 /14 | Mar 6 /14 | Mar 6 /14 | |
| **Time** | 15:11:19 | 15:20:09 | 15:11:19 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.2 | 7.2 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.2 | |

**Peak Vector Sum** 0.0610 in/s on March 6, 2014 at 15:20:09




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 7th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 9:45 AM until 3:30 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

Twelve sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


HACKENSACK RIVER
VMP 6
VMP 7
WORK AREA
ACTIVE 72" FORC. MAIN
CONSERVATION EASEMENT
HYDRAULIC BARRIER
EXISTING SOIL CEMENT BENTONITE WALL
GEOMEMBRANE GRADE CONTOURS (TYP)

# Event Report

**Histogram Start Time** 09:46:05 March 7, 2014
**Histogram Finish Time** 14:57:11 March 7, 2014
**Number of Intervals** 3733.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F87X.ST0

**Post Event Notes**
VMP 6

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0850 | 0.115 | 0.175 | in/s |
| **ZC Freq** | 43 | 26 | 28 | Hz |
| **Date** | Mar 7 /14 | Mar 7 /14 | Mar 7 /14 | |
| **Time** | 13:16:35 | 13:28:20 | 14:25:15 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.3 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.183 in/s on March 7, 2014 at 14:25:15




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 15:00:12 March 7, 2014
**Histogram Finish Time** 15:39:10 March 7, 2014
**Number of Intervals** 467.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F88C.CC0

**Post Event Notes**
VMP 7

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.0600 | 0.0500 | in/s |
| **ZC Freq** | 47 | 39 | 28 | Hz |
| **Date** | Mar 7 /14 | Mar 7 /14 | Mar 7 /14 | |
| **Time** | 15:04:47 | 15:04:47 | 15:04:27 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.0634 in/s on March 7, 2014 at 15:04:47




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 8th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 8:50 AM until 12:35 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

19 sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


HACKENSACK RIVER
VMP 7
VMP 8
WORK
AREA
CONSERVATION EASEMENT
ACTIVE 22" FORCE MAIN
EXISTING SOIL CEMENT BENTONITE WALL
GEOMEMBRANE GRADE CONTOURS (TYP)

# Event Report

**Histogram Start Time** 08:50:20 March 8, 2014
**Histogram Finish Time** 10:40:45 March 8, 2014
**Number of Intervals** 1325.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F89P.VW0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 7

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.110 | 0.0500 | in/s |
| **ZC Freq** | 51 | 16 | 28 | Hz |
| **Date** | Mar 8 /14 | Mar 8 /14 | Mar 8 /14 | |
| **Time** | 09:26:20 | 09:17:35 | 09:11:15 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.2 | |

**Peak Vector Sum** 0.113 in/s on March 8, 2014 at 09:17:35




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 10:43:17 March 8, 2014
**Histogram Finish Time** 12:36:05 March 8, 2014
**Number of Intervals** 1353.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F89V.450

**Post Event Notes**
VMP 8

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0550 | 0.0750 | 0.0900 | in/s |
| **ZC Freq** | 30 | 13 | 30 | Hz |
| **Date** | Mar 8 /14 | Mar 8 /14 | Mar 8 /14 | |
| **Time** | 12:31:52 | 11:10:52 | 11:11:22 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 4.2 | 4.0 | 4.0 | |

**Peak Vector Sum** 0.0935 in/s on March 8, 2014 at 11:11:22




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 10th, 2014**
**For ENTACT, LLC**


**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 11:30 AM and ended at 5:05 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

30 sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


HACKENSACK RIVER
VMP 9
VMP 10
WORK
AREA
CONSERVATION EASEMENT
ACTIVE 72" FORCE MAIN
EXISTING SOIL CEMENT BENTONITE WALL
GEOMEMBRANE GRADE CONTOURS (TYP)


VMP 11
Work Area

# Event Report

**Histogram Start Time** 11:30:36 March 10, 2014
**Histogram Finish Time** 13:38:03 March 10, 2014
**Number of Intervals** 1529.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8DM.N00


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 9

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.155 | 0.165 | in/s |
| **ZC Freq** | 34 | 22 | 51 | Hz |
| **Date** | Mar 10 /14 | Mar 10 /14 | Mar 10 /14 | |
| **Time** | 11:33:21 | 11:33:21 | 11:33:26 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.3 | Hz |
| **Overswing Ratio** | 4.1 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.186 in/s on March 10, 2014 at 11:54:36




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 13:40:24 March 10, 2014
**Histogram Finish Time** 15:15:31 March 10, 2014
**Number of Intervals** 1141.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8DS.NC0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 10

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0500 | 0.140 | 0.0750 | in/s |
| **ZC Freq** | 34 | 32 | 32 | Hz |
| **Date** | Mar 10 /14 | Mar 10 /14 | Mar 10 /14 | |
| **Time** | 13:48:59 | 14:45:24 | 13:49:04 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.2 | 7.2 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.146 in/s on March 10, 2014 at 14:45:24




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 15:17:54 March 10, 2014
**Histogram Finish Time** 17:08:22 March 10, 2014
**Number of Intervals** 1325.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8DX.5U0

**Post Event Notes**
VMP 11

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0450 | 0.125 | 0.0800 | in/s |
| **ZC Freq** | 34 | 32 | 30 | Hz |
| **Date** | Mar 10 /14 | Mar 10 /14 | Mar 10 /14 | |
| **Time** | 17:02:14 | 17:01:34 | 16:06:59 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 4.1 | 4.0 | 4.1 | |

**Peak Vector Sum** 0.145 in/s on March 10, 2014 at 17:01:34




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 11th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 8:10 AM and ended at 6:40 PM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

44 sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


VMP 12
VMP 13
VMP 14
VMP 15
VMP 16
Work Area

# Event Report

**Histogram Start Time** 08:07:50 March 11, 2014
**Histogram Finish Time** 09:59:23 March 11, 2014
**Number of Intervals** 1338.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8F7.X20


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 12

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0200 | 0.130 | 0.0450 | in/s |
| **ZC Freq** | 43 | 15 | 17 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 08:15:45 | 09:26:45 | 08:15:00 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.2 | |

**Peak Vector Sum** 0.132 in/s on March 11, 2014 at 09:26:45




**Time Scale:** 1 minute /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 10:01:54 March 11, 2014
**Histogram Finish Time** 13:41:17 March 11, 2014
**Number of Intervals** 2632.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8FD.760


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 13

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.165 | 0.0850 | in/s |
| **ZC Freq** | 39 | 17 | 32 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 10:16:54 | 11:02:59 | 11:14:44 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.3 | Hz |
| **Overswing Ratio** | 4.1 | 4.0 | 4.0 | |

**Peak Vector Sum** 0.169 in/s on March 11, 2014 at 11:02:59




**Time Scale:** 2 minutes /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 13:43:06 March 11, 2014
**Histogram Finish Time** 15:14:40 March 11, 2014
**Number of Intervals** 1098.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8FN.FU0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 14

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.120 | 0.0450 | in/s |
| **ZC Freq** | 39 | 30 | 30 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 13:45:06 | 14:18:06 | 13:45:06 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.9 | 4.0 | |

**Peak Vector Sum** 0.122 in/s on March 11, 2014 at 14:18:06




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 15:17:04 March 11, 2014
**Histogram Finish Time** 15:55:36 March 11, 2014
**Number of Intervals** 462.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8FR.SG0

**Post Event Notes**
VMP 15

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0350 | 0.115 | 0.0400 | in/s |
| **ZC Freq** | 34 | 30 | 34 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 15:36:34 | 15:35:54 | 15:35:54 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 4.0 | 3.9 | 4.0 | |

**Peak Vector Sum** 0.119 in/s on March 11, 2014 at 15:35:54




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 15:57:20 March 11, 2014
**Histogram Finish Time** 16:30:19 March 11, 2014
**Number of Intervals** 395.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8FT.NK0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 14

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0350 | 0.160 | 0.0450 | in/s |
| **ZC Freq** | 39 | 30 | 30 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 16:26:30 | 16:23:00 | 16:20:20 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.0 | 3.9 | 3.9 | |

**Peak Vector Sum** 0.164 in/s on March 11, 2014 at 16:23:00




**Time Scale:** 10 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 16:32:48 March 11, 2014
**Histogram Finish Time** 17:59:40 March 11, 2014
**Number of Intervals** 1042.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8FV.AO0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 15

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0300 | 0.115 | 0.130 | in/s |
| **ZC Freq** | 37 | 30 | 30 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 17:47:13 | 17:47:13 | 17:34:53 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.3 | 7.2 | Hz |
| **Overswing Ratio** | 4.1 | 3.9 | 4.0 | |

**Peak Vector Sum** 0.161 in/s on March 11, 2014 at 17:34:53




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 18:01:28 March 11, 2014
**Histogram Finish Time** 18:40:22 March 11, 2014
**Number of Intervals** 466.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8FZ.EG0

**Post Event Notes**
VMP 16

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0400 | 0.1000 | 0.0400 | in/s |
| **ZC Freq** | 34 | 30 | 32 | Hz |
| **Date** | Mar 11 /14 | Mar 11 /14 | Mar 11 /14 | |
| **Time** | 18:39:03 | 18:36:58 | 18:37:08 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.4 | Hz |
| **Overswing Ratio** | 3.8 | 3.7 | 3.9 | |

**Peak Vector Sum** 0.100 in/s on March 11, 2014 at 18:36:58




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Vibration Monitoring Report

## Study Area 6 North

**Prepared by**
**Geocomp Engineering**


**March 12th, 2014**
**For ENTACT, LLC**

**NOTES:**

**Summary of Work:**
Sheet pile driving commenced at 8:00 AM and ended at 10:40 AM. An Instantel Blastmate III was used to record vibrations via a geophone placed on the ground over the 72 inch force main.

16 sheets were driven, and no exceedances were recorded. See attached plan for area of work and location of the seismograph. See attached Blastware reports for PPV at this location.

Trigger Level: 0.5 in/sec
Alert Level: 1.0 in/sec


VMP 17
VMP 16
VMP 12
Work Area

# Event Report

**Histogram Start Time** 07:50:17 March 12, 2014
**Histogram Finish Time** 08:43:20 March 12, 2014
**Number of Intervals** 636.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1

**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8H1.RT0


**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440

**Post Event Notes**
VMP 16

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0250 | 0.110 | 0.0750 | in/s |
| **ZC Freq** | 51 | 32 | 30 | Hz |
| **Date** | Mar 12 /14 | Mar 12 /14 | Mar 12 /14 | |
| **Time** | 08:06:47 | 08:13:22 | 08:07:22 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.2 | 7.3 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.119 in/s on March 12, 2014 at 08:13:12




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 08:45:37 March 12, 2014
**Histogram Finish Time** 09:50:52 March 12, 2014
**Number of Intervals** 783.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.9 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8H4.C10

**Post Event Notes**
VMP 17

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.0950 | 0.275 | 0.215 | in/s |
| **ZC Freq** | 34 | 30 | 34 | Hz |
| **Date** | Mar 12 /14 | Mar 12 /14 | Mar 12 /14 | |
| **Time** | 09:18:12 | 09:18:12 | 09:18:12 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.4 | 7.2 | 7.1 | Hz |
| **Overswing Ratio** | 4.3 | 4.1 | 4.2 | |

**Peak Vector Sum** 0.320 in/s on March 12, 2014 at 09:18:12




**Time Scale:** 30 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

# Event Report

**Histogram Start Time** 09:54:53 March 12, 2014
**Histogram Finish Time** 10:40:53 March 12, 2014
**Number of Intervals** 552.00 at 5 seconds
**Range** Geo:10.00 in/s
**Sample Rate** 1024sps
**Job Number:** 1
**Notes**
Location: SA 6 North 72" Forcemain
Client: Entact
User Name: Geocomp
General: Kellogg Street and Route 440


**Serial Number** BA15371 V 10.60-8.17 BlastMate III/8
**Battery Level** 6.8 Volts
**Unit Calibration** January 29, 2014 by Instantel
**File Name** Q371F8H7.JH0

**Post Event Notes**
VMP 18

**Extended Notes**

| | Tran | Vert | Long | |
|---|---|---|---|---|
| **PPV** | 0.250 | 0.260 | 0.205 | in/s |
| **ZC Freq** | 32 | 37 | 28 | Hz |
| **Date** | Mar 12 /14 | Mar 12 /14 | Mar 12 /14 | |
| **Time** | 10:23:33 | 10:23:33 | 10:38:53 | |
| **Sensor Check** | Passed | Passed | Passed | |
| **Frequency** | 7.5 | 7.3 | 7.3 | Hz |
| **Overswing Ratio** | 4.2 | 4.1 | 4.1 | |

**Peak Vector Sum** 0.310 in/s on March 12, 2014 at 10:23:33




**Time Scale:** 15 seconds /div **Amplitude Scale:** Geo: 0.0500 in/s/div Sensor Check


Format © 1995-2013 Xmark Corporation

## Attachment 11:  Weekly SWPPP Reports

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: April 30, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 1 |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 North & GWTP** | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-7 & Novartis Stockpile** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 3 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 5 |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/01/14

**SWPPP Observer:** _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Wednesday, April 30, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | There is ponded stormwater at several locations inside the SA-6 South exclusion zones. |
| 2 | IA2Q4A1AL8 | A new access road has been constructed along the eastern side of the SA-6 North sedimentation basin. No fencing is present between the roadway and the sed basin. |
| 3 | EEPSQUO2YB | Stormwater runoff is overtopping the containment measures at the southwestern corner of the Novartis stockpile area |
| 4 | IA2Q4A1AL8 | Windscreen on the eastern SA-7 perimeter fence requires maintenance. |
| 5 | IA2Q4A1AL8 | Wind-blown garbage has accumulated along the inside of the eastern SA-7 perimeter fence. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 05/01/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pump the ponded stormwater to the Construction Water Treatment Facility. | 5-2-14 RAD |
| 2 | Install required fencing to protect pedestrian traffic in the area. | 5-2-14 RAD |
| 3 | Regrade and/or install silt dams as necessary to alleviate sediment-laden runoff. | 5-1-14 RAD |
| 4 | Repair windscreen on the Rt. 440 fenceline | 5-2-14 RAD |
| 5 | Remove wind-blown garbage from along the base of the Rt. 440 perimeter fence. | 5-2-14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 05/02/14

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 7, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 3 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 4 |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | X | | 6 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | | |
| Stockpile Tarping/Containment | | X | | 7 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/08/14

**SWPPP Observer:** _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, May 07, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | No erosion control at toe of woody debris/soil pile on SA-6 South. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing along the western edge of the active excavation in SA-6 South requires maintenance and additional signage. |
| 3 | IA2Q4A1AL8 | Several of the Jersey barriers surrounding the new <20 PPM stockpile area on SA-6 South are not covered in geotextile. |
| 4 | IA2Q4A1AL8 | There is ponded stormwater in the SA-6 South eastern Exclusion Zone. |
| 5 | IA2Q4A1AL8 | Silt fence along the southern toe of the N-1 surcharge area on SA-7 requires maintenance. |
| 6 | EEPSQUO2YB | Hay bales western end of the South SA-7 swale require replacement. |
| 7 | EEPSQUO2YB | Novartis surcharge material has accumulated against the containment measures on the north side of the stockpile. |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 05/08/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place hay bales or silt fence along the toe of the stockpile. | 5/8/14 RAD |
| 2 | Install/maintain EZ fencing to more clearly delineate work areas. | 5/12/14 RAD |
| 3 | Install geotextile on Jersey barriers. | 5/9/14 RAD |
| 4 | Pump ponded stormwater from the areas around the stockpiles in the eastern EZ. | 5/12/14 RAD |
| 5 | Repair/maintain the silt fence surrounding the surcharge pile toe. | 5/9/14 RAD |
| 6 | Replace the hay bales at the western end of the southern SA-7 swale. | 5/9/14 RAD |
| 7 | Remove material from against the containment berm on the northern perimeter of the Novartis stockpile area to prevent storm water run-off from overtopping the containemnt. | 5/9/14 RAD |
| | | |

**Construction Manager:** _____ **Date:** 05/12/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 14, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 1 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 05/15/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, May 14, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Stockpiled <20 PPM material has overtopped the Jersey barrier/fabric containment structure which surrounds the new <200 PPM Stockpile Area. |
| 2 | IA2Q4A1AL8 | Clay and soils are being tracked from the surcharge operation on SA-6 North onto the SA-7 North paved roadway. |
| 3 | IA2Q4A1AL8 | **Repeat Item-** There is ponded storm water in the SA-6 South eastern Exclusion Zone. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ (signature) Date: 05/15/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place the spilled material in the containment area and reshape the stockpile to prevent recurrence. | 5-20-14 RAD |
| 2 | Modify the ramp and haul road to prevent excessive tracking of material by the off-road dump trucks. | 5-20-14 RAD |
| 3 | Pump ponded stormwater from the areas around the stockpiles in the eastern EZ. | 5-20-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 05/20/14

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 22, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☐ Fair ☑ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | X | | 4 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/22/14

**SWPPP Observer:** (G. Pfeiffer)
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, May 22, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Erosion control measures are absent around the pretrench excavation to the west of the 80 Kellogg building slab. |
| 2 | IA2Q4A1AL8 | Stormwater is present in the unused 80 Kellogg Steet GWTP influent sump. |
| 3 | IA2Q4A1AL8 | Silt fence along the southern toe of the SA-6 North surcharge area requires maintenance. |
| 4 | IA2Q4A1AL8 | Erosion control measures at the SA-7 North stormwater discharge weir structure require improvement. |
| 5 | IA2Q4A1AL8 | The north roadway on SA-7 requires cleaning of sediment buildup resulting from the hauling of Novartis stockpile material. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature **Date:** 05/22/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install hay bales or waddle around pretrench spoils to prevent sediment run-off. | 5-23-14 RAD |
| 2 | Pump the accumulated storm water from the unused GWTP influent sump located to the north of the 80 Kellogg slab. Secure the fencing to limit access to the sump. | 5-27-14 RAD |
| 3 | Repair or reinstall the unsecured sections of silt fence along the southern toe of the N-1 surcharge area. | 5-27-14 RAD |
| 4 | Install straw waddle in the northern SA-7 swale to the east of the discharge weir structure. | 5-23-14 RAD |
| 5 | Clean roadway with water truck and/or street sweeper. Implement additional measures to minimize the tracking of soils/sediments. | 5-23-14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 05/27/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 29, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | | |
| Stockpile Tarping/Containment | | | | |
| Proper Chemical Storage | | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/29/14

**SWPPP Observer:** (George Pfeiffer)
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, May 29, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment controls in a catch basin to the north of the original guard shack require maintenance/replacement. |
| 2 | IA2Q4A1AL8 | The hose which supplies the shower trailer is leaking and requires repair |
| 3 | IA2Q4A1AL8 | Silt fence along the north side of the N-1 surcharge pile is not properly installed. |
| 4 | IA2Q4A1AL8 | The surcharge material haul road along the northern perimeter of Study Area 7 has excessive sediment/soil material on it's surface and requires cleaning/maintenance. |
| 5 | IA2Q4A1AL8 | Fencing is needed at the southeast corner of the N-1 surcharge pile. The grade change due to surcharge material placement now allows access to the spill-over tank on the southern side of the sedimenation basin and fencing is required for safety. |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Signature Date: 05/29/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace filter fabric in the catch basin. | 6/3/14 RAD |
| 2 | Repair hose and/or hose bib. | 5/30/14 RAD |
| 3 | Toe in silt fence as per specifications. | 6/2/14 RAD |
| 4 | Clean the asphalt roadway and install hay bales as necessary to alleviate run-off of sediment. | 6/3/14 RAD |
| 5 | Install fencing and/or restrict access to the spill-over tank located to the south of the sedimentation basin on SA-6 North. | 6/3/14 RAD |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 06/04/14

## Attachment 12: GWTP Update

- 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (April 2014)
- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (April 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

May 15, 2014

New Jersey Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: April 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the April 2014 Surface Water Discharge Monitoring Report for Outfall 001A. Please note that there was no discharge this monitoring period.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Frank Schroyer - Parsons

New Jersey Department of Environmental Protection
Division of Water Quality

PI 234822

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 4 | 1 | 2014 | To | 4 | 30 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☒ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J. Morris, Remediation Director — —

NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR — GRADE AND REGISTRY NUMBER (IF APPLICABLE)

John J. Morris — 5/14/2014 — 973.455.4003

SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR — DATE — AREA CODE/PHONE NUMBER

*For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J. Morris, Remediation Director — John J. Morris — 5/14/2014 — 973.455.4003

NAME AND TITLE — SIGNATURE — DATE — AREA CODE/PHONE NUMBER

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 4/1/2014 TO 4/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | | | GPD | ****** | ****** | ****** | ****** | | | |
| | PERMIT REQUIREMENT | REPORT 01MOAV | REPORT 01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | | SU | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0 01MOMN | ****** | 9.0 01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 50 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10 01MOAV | 15 01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 20 01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 4/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 4/1/2014 TO 4/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 4/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 4/1/2014 TO 4/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 0.025 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.8 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 46 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 54 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 4/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 4/1/2014 TO 4/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | | | | | | | | | | |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 4/1/2014*

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

May 15, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Bayfront Redevelopment at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the April 2014 discharge monitoring reports, MR 1 and MR 2, for the Bayfront Redevelopment treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy

Helen Fahy
Remediation Manager
Fahy Associates

cc: Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc., Bayfront Redevelopment

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 4 | 01 | 14 | 4 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 78,308 | 92,462 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 1.29 | 1.52 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.050 | <0.050 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.2 | <5.2 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.0839 | 0.0839 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT


Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

May 14, 2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc., Bayfront Redevelopment

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 4 | 01 | 14 | 4 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,349,250 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 5,660,213 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 4/23/2014 | 39.3 | 10.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE May 14, 2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Bayfront Redevelopment; GWTP (Permit #31630016) | | | | | | | | MONTH: April 2014 | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 4/1/2014 | Angel Trujillo | 3310963 | 3392049 | 81,086 | 0.081086 | 7.37 | 1.970 | | | | | | | | | 1.33 |
| 4/2/2014 | Angel Trujillo | 3392049 | 3472201 | 80,152 | 0.080152 | 7.47 | 1.970 | | | | | | | | | 1.32 |
| 4/3/2014 | Angel Trujillo | 3472201 | 3551241 | 79,040 | 0.07904 | 7.31 | 1.970 | | | | | | | | | 1.30 |
| 4/4/2014 | Angel Trujillo | 3551241 | 3630423 | 79,182 | 0.079182 | 7.74 | 1.970 | | | | | | | | | 1.30 |
| 4/5/2014 | Angel Trujillo | 3630423 | 3722885 | 92,462 | 0.092462 | 7.59 | 1.970 | | | | | | | | | 1.52 |
| 4/6/2014 | Angel Trujillo | 3722885 | 3790127 | 67,242 | 0.067242 | 7.46 | 1.970 | | | | | | | | | 1.10 |
| 4/7/2014 | Angel Trujillo | 3790127 | 3861609 | 71,482 | 0.071482 | 7.52 | 1.970 | | | | | | | | | 1.17 |
| 4/8/2014 | Angel Trujillo | 3861609 | 3938419 | 76,810 | 0.07681 | 7.70 | 1.970 | | | | | | | | | 1.26 |
| 4/9/2014 | Angel Trujillo | 3938419 | 4015416 | 76,997 | 0.076997 | 7.69 | 1.970 | | | | | | | | | 1.27 |
| 4/10/2014 | Angel Trujillo | 4015416 | 4094327 | 78,911 | 0.078911 | 7.71 | 1.970 | | | | | | | | | 1.30 |
| 4/11/2014 | Angel Trujillo | 4094327 | 4168700 | 74,373 | 0.074373 | 7.70 | 1.970 | | | | | | | | | 1.22 |
| 4/12/2014 | Angel Trujillo | 4168700 | 4249999 | 81,299 | 0.081299 | 7.76 | 1.970 | | | | | | | | | 1.34 |
| 4/13/2014 | Angel Trujillo | 4249999 | 4336560 | 86,561 | 0.086561 | 7.74 | 1.970 | | | | | | | | | 1.42 |
| 4/14/2014 | Angel Trujillo | 4336560 | 4410816 | 74,256 | 0.074256 | 7.77 | 1.970 | | | | | | | | | 1.22 |
| 4/15/2014 | Angel Trujillo | 4410816 | 4484706 | 73,890 | 0.07389 | 7.75 | 1.970 | | | | | | | | | 1.21 |
| 4/16/2014 | Angel Trujillo | 4484706 | 4561960 | 77,254 | 0.077254 | 7.77 | 1.970 | | | | | | | | | 1.27 |
| 4/17/2014 | Angel Trujillo | 4561960 | 4640229 | 78,269 | 0.078269 | 7.74 | 1.970 | | | | | | | | | 1.29 |
| 4/18/2014 | Angel Trujillo | 4640229 | 4720310 | 80,081 | 0.080081 | 7.72 | 1.970 | | | | | | | | | 1.32 |
| 4/19/2014 | Angel Trujillo | 4720310 | 4803443 | 83,133 | 0.083133 | 7.67 | 1.970 | | | | | | | | | 1.37 |
| 4/20/2014 | Angel Trujillo | 4803443 | 4881981 | 78,538 | 0.078538 | 7.71 | 1.970 | | | | | | | | | 1.29 |
| 4/21/2014 | Angel Trujillo | 4881981 | 4955934 | 73,953 | 0.073953 | 7.73 | 1.970 | | | | | | | | | 1.22 |
| 4/22/2014 | Angel Trujillo | 4955934 | 5035774 | 79,840 | 0.07984 | 7.76 | 1.970 | | | | | | | | | 1.31 |
| 4/23/2014 | Angel Trujillo | 5035774 | 5115447 | 79,673 | 0.079673 | 7.10 | 1.970 | <5.2 | 39.3 | | <0.010 | <0.030 | <0.050 | <0.0002 | <0.020 | 1.31 |
| 4/24/2014 | Angel Trujillo | 5115447 | 5194972 | 79,525 | 0.079525 | 7.74 | 1.970 | | | | | | | | | 1.31 |
| 4/25/2014 | Angel Trujillo | 5194972 | 5273422 | 78,450 | 0.07845 | 7.53 | 1.970 | | | | | | | | | 1.29 |
| 4/26/2014 | Angel Trujillo | 5273422 | 5353408 | 79,986 | 0.079986 | 7.54 | 1.970 | | | | | | | | | 1.31 |
| 4/27/2014 | Angel Trujillo | 5353408 | 5428101 | 74,693 | 0.0747 | 7.67 | 1.970 | | | | | | | | | 1.23 |
| 4/28/2014 | Angel Trujillo | 5428101 | 5508412 | 80,311 | 0.080311 | 7.33 | 1.970 | | | | | | | | | 1.32 |
| 4/29/2014 | Angel Trujillo | 5508412 | 5583939 | 75,527 | 0.075527 | 7.62 | 1.970 | | | | | | | | | 1.24 |
| 4/30/2014 | Angel Trujillo | 5583939 | 5660213 | 76,274 | 0.076274 | 7.51 | 1.970 | | | | | | | | | 1.25 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,349,250 | 2.34925 | | | <5.2 | 39.3 | | <0.010 | <0.030 | <0.050 | <0.0002 | <0.020 | |
| | | | High: | 92,462 | | | | | | | | | | | High: | 1.52 |
| | | | Average: | 78,308 | | | | | | | | | | | Average: | 1.29 |

E

WW

JB65396

Accutest Labs
2235 ROUTE 130
Dayton, NJ 8810
732-329-0200

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 41782.58875
COC#
Lab Proj # (SDG):
Lab ID
Site ID
Lab Job #: HWMJ582015
Authorized User: Honeywell

Site Name: Hudson County
Location of Site: Jersey City, NJ
Phase: CS
Sampling Program: 087: JCIA

Sampling Co.: Parsons
Client Contact: (name, co., address)
Helen Fahy P: (973) 455-2668 E: helen.fahy@honeywell.com
Honeywell International
101 Columbia Road Morristown, NJ 07962
Hard Copy To: Helen Fahy (Honeywell)
Invoice To: Helen Fahy (Honeywell)

EDD To:
Sampler: Frank Schroyer
PO #
Analysis Turnaround Time (TAT): 3
Coordinator: CR2M
Full Report TAT: 28 Days

Copyright AESI Version 3.0 Unauthorized use strictly prohibited.

| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Units | | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | EPA 245.1 Hg | Method 1 Biological Oxygen Demand | EPA 624 TVOC | EPA 8260A SVOC-MSM | EPA 152.1 PH | SM2540 D Total Suspended Solids | EPA VSM-AE VOCs, see attached speciation list | | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-042314-A | 4/23/2014 | 14:50 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | -1 | | | | | | | 6.84 pH | |
| 2 | 087-WW | | | 087-WWE-042314-B | 4/23/2014 | 14:40 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | -2 | | | | | | | | |
| 3 | 087-WW | | | 087-WWI-042314 | 4/23/2014 | 14:26 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | -3 | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

L19
L72
A7
G23

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: | 4/23/14 | Company: Parsons | Received by: | Company: Accutest | Condition: | | Custody Seals Intact: |
| Frank Schroyer pH = 7.10 s.u. | Date/Time: | | | Date/Time: 4/23/14 1600 | Cooler Temp: | 3.0C | |
| Relinquished by: | | Company: Accutest | Received by: | Company: ACCUTEST | Condition: | | Custody Seals Intact: |
| | Date/Time: 4/23/14 1720 | | | Date/Time: 4/23 1600 | Cooler Temp: | | |

Preservatives: (Other Specify): None

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 HC H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); 99 (special instructions)

JK

Accutest LabLink@792117 07:28 29-Apr-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-042314-A | | |
| Lab Sample ID: | JB65396-1 | Date Sampled: | 04/23/14 |
| Matrix: | AQ - Water | Date Received: | 04/23/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1970 | 10 | ug/l | 1 | 04/24/14 | 04/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 04/24/14 | 04/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 04/24/14 | 04/28/14 | ND | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 04/25/14 | 04/25/14 | JW | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel [a] | < 50 | 50 | ug/l | 5 | 04/24/14 | 04/28/14 | ND | EPA 200.7 [3] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 04/24/14 | 04/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA33870
(2) Instrument QC Batch: MA33871
(3) Instrument QC Batch: MA33890
(4) Prep QC Batch: MP79076
(5) Prep QC Batch: MP79129

(a) Elevated detection limit due to dilution required for matrix interference.

RL = Reporting Limit

Accutest LabLink@792117 07:28 29-Apr-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-042314-A | | |
| **Lab Sample ID:** | JB65396-1 | **Date Sampled:** | 04/23/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/23/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 39.3 | 3.4 | mg/l | 1 | 04/23/14 19:29 | LS | SM5210 B-01 |
| Solids, Total Suspended | 10.0 | 4.0 | mg/l | 1 | 04/25/14 | KP | SM2540 D-11 |
| pH [a] | 6.84 | | su | 1 | 04/23/14 17:35 | OS | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@792117 07:28 29-Apr-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-042314-B | | |
| **Lab Sample ID:** | JB65396-2 | **Date Sampled:** | 04/23/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/23/14 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N234196.D | 1 | 04/24/14 | DC | n/a | n/a | VN9917 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA PPL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.5 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.3 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.27 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 19.2 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 2.8 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.60 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 55.2 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 81% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 99% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 93% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 95% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

**Draft: 3 of 5**

Accutest LabLink@792117 07:28 29-Apr-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-042314-B | | |
| Lab Sample ID: | JB65396-2 | Date Sampled: | 04/23/14 |
| Matrix: | AQ - Water | Date Received: | 04/23/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.2 | 5.2 | mg/l | 1 | 04/28/14 | LS | EPA 1664A |

RL = Reporting Limit

## Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending May 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area; Update the list of monitoring wells to be abandoned / retained | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead | Submitted to all Parties on May 19, 2014. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 4 OF 25**

- **2014 Monthly Reports Part 4**

**7/11/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

July 11, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-06**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from June 1 – June30, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: June 2014 SA-6/7 Combined Monthly Progress Report No. 2014-06

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2014-06
### Project SA-6 & 7 Remediation

## June 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/02/14 | SA-6 - PVSC Permit - E-mail Notification<br>Study Area 6, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/02/14 | Responses to Comments Provided by Plaintiffs<br>Summary of Hydrocarbon-Impacted Soil Encountered<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/06/14 | Response to Comments Provided by Plaintiffs, May 14, 2014, Design Change Bulletin (DCB) – Trench Layout for Contingent Groundwater Extraction System<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/09/14 | Bench Scale Work Plan to Test Efficacy of Treatment of Chromium-Impacted Soil Using 3DME Organic Substrate<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/12/14 | Response to Comments Provided by Plaintiffs, June 3, 2014, Surcharge Plan Design Change<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/13/14 | Combined Monthly Progress/Highlights Report No. 2014-04<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/17/14 | Response to Comments – 2013 Annual Integrated GW Performance Report<br>Study Areas 5, 6, and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/17/14 | Surcharge Observation Proximate to PVSC Force Main<br>Study Areas 6, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/18/14 | NJPDES Permit NJ0156311: May 2014 Surface Water Discharge Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | NJ Department of Environmental Protection<br>Division of Water Quality |
| 06/18/14 | Termination of Sewer Use Permit ID 31630005<br>80 Kellogg Street<br>Study Area 6, Jersey City, NJ | Anthony Gammaro<br>Passaic Valley Sewerage Commission |
| 06/18/14 | Court Ordered Regional Groundwater Remedy Treatment Plant - MR 1 and MR 2<br>Permit ID# 31630016<br>Located at 525 & 575 Route 440, Jersey City, NJ<br>*(see **Attachment 12**)* | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 06/19/14 | Declarations for Performance Certifications<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/24/14 | Special Master All Hands Meeting | N/A |
| 06/25/14 | PVSC - Acoustic Monitoring Reports<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 06/08/14 | 06/15/14 | 06/22/14 | 06/29/14 |
| **Construction Management (AMEC)** | 9 | 13 | 13 | 12 |
| **Engineering (AMEC)** | 1 | 2 | 2 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 44 | 42 | 37 | 37 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 1 |
| **OSC (80 Kellogg Demolition)** | 0 | 0 | 0 | 0 |
| **ENR (SA-6N GWTP Utilities)** | 2 | 0 | 0 | 0 |
| **Siemens** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 1 | 2 |
| **TOTAL** | **62** | **63** | **59** | **58** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Collected June PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- On June 11, met with JCIA and JCRA representatives to discuss relocation schedule and finalization of the bid documents for the Above-grade Demolition of the designated JCIA Structures.
- On June 30, excavation contractor encountered a previously unknown underground storage tank while excavating in Cell 114. The site designated LSRP was notified and is responsible for registering and closing the UST in accordance with NJDEP requirements as part of the non-chromium remedial action being conducted concurrently.

## C. SA-6 N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on May 13, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 06/08/14 | 06/15/14 | 06/22/14 | 06/29/14 |
| Avg. Gallons Treated & Discharged (per day) | 76,998 | 80,687 | 78,742 | 79,710 |
| Average Flow (gpm) for Operating Period | 53 | 56 | 54 | 55 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP InfluentTanks (gal.) | 9,410 | 13,658 | 13,987 | 11,625 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in cells 127B – 116B, 124A – 114A.
- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 0 | 0 | 0 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 32 | 21.7 | 693.60 |
| **Entact/ Montecalvo** | Tri-axle Dump | Bayshore Recycling | NA | Non Haz Petroleum Soil | 105 | 25.7 | 2703.22 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 127B – 116B, 124A – 114A |
| **Excavation Completed** | Cell Number(s) 128B – 118B, 125A – 115A<br>Volume Excavated - Total for Reporting Period: 15,127 CY/ Total to Date: 77,746 CY |
| **Backfill in Progress** | Cell Number(s) 152A-114A, 146B-128B |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 06/08/14 | 06/15/14 | 06/22/14 | 06/29/14 |
| <20ppm re-use, CY | 1,779 | 968 | 1,037 | 1,531 |
| Weldon, Import-Tons | 0 | 4,603 | 811.11 | 2,125.7 |
| Tilcon, Import-Tons DGA | 1,260 | 359 | 0 | 0 |
| Tilcon, Import Tons – 1.5" Stone | 379.7 | 0 | 0 | 0 |
| Weldon, Imported Tons - QP | 0 | 250.34 | 1,367.7 | 3,290 |
| Celgene - Loads | 0 | 0 | 0 | 240 |
| Tilcon, Imported Tons – 2.5" Stone | 0 | 0 | 0 | 51.13 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Instrumentation Installation ~95% complete. The settlement platforms over the perimeter pool remain to be installed. They will be installed prior to construction of the slope. Surcharge initiated June 16th.
- Area 2S: Instrumentation Installation ~95% complete. The settlement platforms over the perimeter pool remain to be installed. They will be installed prior to construction of the slope.
- Area 3S: Instrumentation Installation 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. No Surcharge initiated.
- Area 1N: Instrumentation Installation ~100% complete. Continued placement of surcharge material initiated on April 8, 2014. As of June 27th, ~95% of surcharge has been placed. The results of the monitoring provided in Surcharge Monitoring Report #3 to be submitted under separate cover. Surcharge placement was stopped due to detected movements and V1-4. Amec has been in regular communication with PVSC regarding these readings.
- Area 2N: Instrumentation Installation ~85% complete. Initial surcharge instrument data to be submitted under separate cover.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Two single sheets driven on the hydraulic barrier wall at Sta 12+68 for the Closure Piece 1, SA-6 South.

## PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## G. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Initiate bidding process for the Above-grade Demolition of the four designated JCIA Structures.
- Complete placement of surcharge materials in SA-6N Area 1N.
- Continue placement of surcharge materials in SA-6S Area 1S.
- Begin placement of surcharge materials in SA-6N Area 2N.
- Continue installation of the contingent groundwater system on SA-6S.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 108 to 88.
- Continue stockpiling of presumed <20 mg/kg for additional sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Conduct S-3 Injection/Mass Removal Event No.15 in well 088-IW-01.
- Conduct quarterly LTMP groundwater level measurement round.

- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-5)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. Groundwater Quality Data Update *(provided on a quarterly basis)*
   - Summary of Groundwater Quality Data from GWET Wells
   - Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells
9. Surcharge Monitoring Update
   - Instrumentation Location Plan 1S
   - Instrumentation Location Plan 2N
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Deflection Along Open Excavation
    - Sheet Pile Repair Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (May 2014)
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (May 2014)
13. SA-6 North & South Design Change Tracking Log

## Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Thu 7/3/14

Task Milestone Summary Critical

## Attachment 2: Site Photographs




**Site Photograph 1:** Backfill compaction activities.




**Site Photograph 2:** Contractor continues excavation activities.




**Site Photograph 3:** Contractor placing backfill with dozer.




**Site Photograph 4:** Spreading the first lift of DGA over fabric - facing southwest.




**Site Photograph 5:** Surcharge instrumentation installation at JC Properties.





**Site Photograph 6:** The western excavation face.


## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points)
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of July 1, 2014

June 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill




LEGEND
CONFIRMATORY BOTTOM SAMPLE ELEVATION
CONFIRMATORY SIDEWALL SAMPLE ELEVATION
0.0 POINT ELEVATION
POINT POINT DESCRIPTION
BOTTOM CENTER POINT ELEVATION STRATUM D
BOTTOM CENTER POINT ELEVATION <20 PPM
BOTTOM CORNER POINT ELEVATION <20 PPM
DESIGNED STRATUM O EXCAVATION LIMIT
PREVIOUSLY SUBMITTED DATA
CURRENT EXCAVATION TO STRATUM D
CURRENT EXCAVATION TO <20 PPM
TOP OF EXCAVATION SLOPE
LIMIT OF EXCAVATION AREA
ENTACT 302 Unity Plaza Latrobe, PA 15650
DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 06-12-14 TO 06-26-14
PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.
Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.7 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.9 | Stratum D Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.7 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-4 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 7/2/14

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 21.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 2 | BF-19 | | | | | | | | | | | | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation - Stratum O | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavartion elevation | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.6 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.6 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.6 | 95 | 95 | | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.6 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.6 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.6 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.6 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.6 | 97 | 95 | | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.6 | 95 | 95 | | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.6 | 95 | 95 | | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.6 | 98 | 95 | | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b


Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)

01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 25 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 126.8 | 4.5 | 124.5 | 12.1 | 102 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 124.5 | 12.1 | 100 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 (No) | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.5 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/1/2014 | 685263.1 | 601755.8 | 2.6 | 122.4 | 7.3 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.1719 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 0 | RF-34 | | 685278.423 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | | | | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 152 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 151 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 151 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 151 | Weldon WC Screenings | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS 5 TESTS PER ACRE

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-5)

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 05/01/14 | 1 | 24 | 9,EPS | 12 | 560,143 | 563,407 | 3,264 | 1,959,614 | 2.3 | |
| 05/01/14 | 2 | 24 | 16,17 | 18 | 65,318 | 67,350 | 2,032 | 1,961,646 | 1.4 | |
| 05/02/14 | 1 | 24 | 9,EPS | 12 | 563,407 | 571,007 | 7,600 | 1,969,246 | 5.3 | |
| 05/02/14 | 2 | 24 | 16,17 | 18 | 67,350 | 69,321 | 1,971 | 1,971,217 | 1.4 | |
| 05/05/14 | 1 | 72 | 9,EPS | 12 | 571,007 | 596,817 | 25,810 | 1,997,027 | 6.0 | |
| 05/05/14 | 2 | 72 | 16,17 | 18 | 69,321 | 75,193 | 5,872 | 2,002,899 | 1.4 | |
| 05/06/14 | 1 | 24 | 9,EPS | 12 | 596,817 | 604,513 | 7,696 | 2,010,595 | 5.3 | |
| 05/06/14 | 2 | 24 | 16,17 | 18 | 75,193 | 77,224 | 2,031 | 2,012,626 | 1.4 | |
| 05/07/14 | 1 | 24 | 9,EPS | 12 | 604,513 | 612,024 | 7,511 | 2,020,137 | 5.2 | |
| 05/07/14 | 2 | 24 | 16,17 | 18 | 0 | 361 | 361 | 2,020,498 | 0.3 | Flowmeter Reset |
| 05/08/14 | 1 | 24 | 9,EPS | 12 | 612,024 | 617,958 | 5,934 | 2,026,432 | 4.1 | |
| 05/08/14 | 2 | 24 | 16 | 12 | 361 | 4,243 | 3,882 | 2,030,314 | 2.7 | |
| 05/09/14 | 1 | 24 | 9,EPS | 12 | 617,958 | 618,262 | 304 | 2,030,618 | 0.2 | |
| 05/09/14 | 2 | 24 | 16 | 12 | 4,243 | 4,886 | 643 | 2,031,261 | 0.4 | |
| 05/12/14 | 1 | 72 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,031,261 | 0.0 | |
| 05/12/14 | 2 | 72 | 16 | 12 | 4,886 | 6,201 | 1,315 | 2,032,576 | 0.3 | |
| 05/13/14 | 1 | 24 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 05/14/14 | 1 | 24 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 05/15/14 | 1 | 24 | 9,EPS | 12 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 05/19/14 | 1 | 72 | 9,EPS | 13 | 618,262 | 618,262 | 0 | 2,032,576 | 0.0 | |
| 06/04/14 | 2 | 24 | 14, WPS-2 | 35 | 0 | 8,325 | 8,325 | 2,040,901 | 5.8 | |
| 06/05/14 | 2 | 24 | 14, WPS-2 | 35 | 8,325 | 13,042 | 4,717 | 2,045,618 | 3.3 | |
| 06/06/14 | 2 | 24 | 14, WPS-2 | 35 | 13,042 | 22,720 | 9,678 | 2,055,296 | 6.7 | |
| 06/09/14 | 2 | 72 | 14, WPS-2 | 35 | 22,720 | 41,093 | 18,373 | 2,073,669 | 4.3 | |
| 06/10/14 | 2 | 24 | 14, WPS-2 | 35 | 41,093 | 54,801 | 13,708 | 2,087,377 | 9.5 | |
| 06/11/14 | 2 | 24 | 14, WPS-2 | 35 | 54,801 | 61,975 | 7,174 | 2,094,551 | 5.0 | |
| 06/12/14 | 2 | 24 | 14, WPS-2 | 35 | 61,975 | 69,411 | 7,436 | 2,101,987 | 5.2 | |
| 06/13/14 | 2 | 24 | 14, WPS-2 | 35 | 69,411 | 75,445 | 6,034 | 2,108,021 | 4.2 | |
| 06/16/14 | 2 | 72 | 14, WPS-2 | 35 | 75,445 | 95,783 | 20,338 | 2,128,359 | 4.7 | |
| 06/17/14 | 2 | 24 | 14, WPS-2 | 35 | 95,783 | 102,708 | 6,925 | 2,135,284 | 4.8 | |
| 06/18/14 | 2 | 24 | 13,14, WPS-2 | 48 | 102,708 | 117,105 | 14,397 | 2,149,681 | 10.0 | |
| 06/19/14 | 2 | 24 | 13,14, WPS-2 | 48 | 117,105 | 131,389 | 14,284 | 2,163,965 | 9.9 | |
| 06/20/14 | 2 | 24 | 13,14, WPS-2 | 48 | 131,389 | 142,678 | 11,289 | 2,175,254 | 7.8 | |
| 06/23/14 | 2 | 72 | 13,14, WPS-2 | 48 | 142,678 | 172,492 | 29,814 | 2,205,068 | 6.9 | |
| 06/24/14 | 2 | 24 | 13,14, WPS-2 | 48 | 172,492 | 182,523 | 10,031 | 2,215,099 | 7.0 | |
| 06/25/14 | 2 | 24 | 13,14, WPS-2 | 48 | 182,523 | 191,134 | 8,611 | 2,223,710 | 6.0 | |
| 06/26/14 | 2 | 24 | 13,14, WPS-2 | 48 | 191,134 | 200,723 | 9,589 | 2,233,299 | 6.7 | |
| 06/27/14 | 2 | 24 | 13,14, WPS-2 | 48 | 200,723 | 212,575 | 11,852 | 2,245,151 | 8.2 | |
| 06/30/14 | 2 | 72 | 13,14, WPS-2 | 48 | 212,575 | 247,628 | 35,053 | 2,280,204 | 8.1 | |
| 07/01/14 | 2 | 24 | 13,14, WPS-2 | 48 | 247,628 | 259,680 | 12,052 | 2,292,256 | 8.4 | |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013
Previous information is truncated. Only last month and current month information is provided.

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-5)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 05/01/14 | 24 | 43,518 | 51,195 | 7,677 | 51,195 | 5.3 | |
| 05/02/14 | 24 | 51,195 | 57,459 | 6,264 | 57,459 | 4.4 | |
| 05/05/14 | 72 | 57,459 | 62,329 | 4,870 | 62,329 | 1.1 | Flowmeter Reset |
| 05/06/14 | 24 | 0 | 27,630 | 27,630 | 89,959 | 19.2 | |
| 05/07/14 | 24 | 27,630 | 31,613 | 3,983 | 93,942 | 2.8 | |
| 05/08/14 | 24 | N/A | N/A | 7,500 | 101,442 | 5.2 | Flowmeter Blockage (Tank Measured) |
| 05/09/14 | 24 | N/A | N/A | 8,000 | 109,442 | 5.6 | Flowmeter Blockage (Tank Measured) |
| 05/12/14 | 72 | N/A | N/A | 25,500 | 134,942 | 5.9 | Flowmeter Blockage (Tank Measured) |
| 05/13/14 | 24 | 31,613 | 32,142 | 529 | 135,471 | 0.4 | |
| 05/14/14 | 24 | 32,142 | 34,250 | 2,108 | 137,579 | 1.5 | |
| 05/15/14 | 24 | 34,250 | 36,358 | 2,108 | 139,687 | 1.5 | Well Taken Offline for Excavation |
| 05/29/14 | 24 | 0 | 4,322 | 4,322 | 144,009 | 3.0 | |
| 05/30/14 | 24 | 4,322 | 8,634 | 4,312 | 148,321 | 3.0 | |
| 06/02/14 | 72 | 8,634 | 20,324 | 11,690 | 160,011 | 2.7 | |
| 06/03/14 | 24 | 20,324 | 33,537 | 13,213 | 173,224 | 9.2 | |
| 06/04/14 | 24 | 33,537 | 61,661 | 28,124 | 201,348 | 19.5 | |
| 06/05/14 | 24 | 61,661 | 83,362 | 21,701 | 223,049 | 15.1 | |
| 06/06/14 | 24 | 83,362 | 90,354 | 6,992 | 230,041 | 4.9 | |
| 06/09/14 | 72 | 90,354 | 116,742 | 26,388 | 256,429 | 6.1 | |
| 06/10/14 | 24 | 0 | 11,717 | 11,717 | 268,146 | 8.1 | Flowmeter Reset |
| 06/11/14 | 24 | N/A | N/A | 10,500 | 278,646 | 7.3 | Flowmeter Blockage (Tank Measured) |
| 06/12/14 | 24 | N/A | N/A | 11,200 | 289,846 | 7.8 | Flowmeter Blockage (Tank Measured) |
| 06/13/14 | 24 | N/A | N/A | 11,100 | 300,946 | 7.7 | Flowmeter Blockage (Tank Measured) |
| 06/16/14 | 72 | N/A | N/A | 34,500 | 335,446 | 8.0 | Flowmeter Blockage (Tank Measured) |
| 06/17/14 | 24 | 0 | 12,405 | 12,405 | 347,851 | 8.6 | Flowmeter Reset |
| 06/18/14 | 24 | 12,405 | 20,193 | 7,788 | 355,639 | 5.4 | |
| 06/19/14 | 24 | N/A | N/A | 9,200 | 364,839 | 6.4 | Flowmeter Blockage (Tank Measured) |
| 06/20/14 | 24 | 20,193 | 23,966 | 3,773 | 368,612 | 2.6 | |
| 06/23/14 | 72 | 23,966 | 30,285 | 6,319 | 374,931 | 1.5 | |
| 06/24/14 | 24 | N/A | N/A | 2,500 | 377,431 | 1.7 | Flowmeter Blockage (Tank Measured) |
| 06/25/14 | 24 | N/A | N/A | 5,000 | 382,431 | 3.5 | Flowmeter Blockage (Tank Measured) |
| 06/26/14 | 24 | N/A | N/A | 5,100 | 387,531 | 3.5 | Flowmeter Blockage (Tank Measured) |
| 06/27/14 | 24 | 0 | 6,090 | 6,090 | 393,621 | 4.2 | |
| 06/30/14 | 72 | 6,090 | 24,309 | 18,219 | 411,840 | 4.2 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 05/01/14 | 12.0 | 9,371.72 | 9,550.80 | 179,080 | 9,550,350 | |
| 05/02/14 | 23.5 | 9,665.35 | 9,775.14 | 224,340 | 9,774,690 | Includes system operation through 05/01/12 |
| 05/03/14 | 21.0 | 9,921.23 | 10,020.57 | 245,430 | 10,020,120 | Includes system operation through 05/02/13 |
| 05/05/14 | 37.0 | 10,377.22 | 10,584.99 | 564,420 | 10,584,540 | Includes system operation through 05/04/14 |
| 05/06/14 | 9.5 | 10,584.99 | 10,825.62 | 240,630 | 10,825,170 | |
| 05/07/14 | 7.5 | 10,825.62 | 11,006.06 | 180,440 | 11,005,610 | PVSC Compliance Sample Collected |
| 05/08/14 | 4.5 | 11,006.06 | 11,112.94 | 106,880 | 11,112,490 | |
| 05/09/14 | 6.0 | 1,112.94 | 11,253.32 | 140,380 | 11,252,870 | |
| 05/12/14 | 7.0 | 11,253.32 | 11,439.87 | 186,550 | 11,439,420 | |
| 05/13/14 | 7.0 | 11,439.87 | 11,600.00 | 160,130 | 11,599,550 | |
| 05/14/14 | 6.5 | 11,600.00 | 11,712.86 | 112,860 | 11,712,410 | |
| 05/15/14 | 5.5 | 11,712.86 | 11,810.42 | 97,560 | 11,809,970 | |
| 05/16/14 | 6.0 | 11,810.42 | 11,885.46 | 75,040 | 11,885,010 | |
| 05/18/14 | 2.8 | 11,885.46 | 11,960.68 | 75,220 | 11,960,230 | |
| 05/19/14 | 7.0 | 11,960.68 | 12,098.90 | 138,220 | 12,098,450 | |
| 05/20/14 | 7.0 | 12,098.90 | 12,188.74 | 89,840 | 12,188,290 | |
| 05/21/14 | 5.0 | 12,188.74 | 12,262.55 | 73,810 | 12,262,100 | |
| 05/22/14 | 7.5 | 12,262.55 | 12,329.43 | 66,880 | 12,328,980 | |
| 05/23/14 | 7.5 | 12,329.43 | 12,405.66 | 76,230 | 12,405,210 | |
| 05/24/14 | 5.0 | 12,405.66 | 12,482.60 | 76,940 | 12,482,150 | |
| 05/25/14 | 2.0 | 12,482.60 | 12,527.46 | 44,860 | 12,527,010 | |
| 05/27/14 | 5.5 | 12,527.46 | 12,662.13 | 134,670 | 12,661,680 | |
| 05/28/14 | 2.0 | 12,662.13 | 12,696.70 | 34,570 | 12,696,250 | |
| 05/29/14 | 7.0 | 12,696.70 | 12,809.54 | 112,840 | 12,809,090 | |
| 05/30/14 | 7.0 | 12,809.54 | 12,906.92 | 97,380 | 12,906,470 | |
| 06/02/14 | 6:30 | 12,906.92 | 13,081.94 | 175,020 | 13,081,490 | |
| 06/04/14 | 7:00 | 13,081.94 | 13,233.54 | 151,600 | 13,233,090 | PVSC Compliance Sample Collected |
| 06/05/14 | 8:30 | 13,233.54 | 13,391.28 | 157,740 | 13,390,830 | |
| 06/06/14 | 8:00 | 13,391.28 | 13,444.66 | 53,380 | 13,444,210 | |
| 06/08/14 | 5:00 | 13,444.66 | 13,498.28 | 53,620 | 13,497,830 | |
| 06/09/14 | 6:15 | 13,498.28 | 13,667.07 | 168,790 | 13,666,620 | |
| 06/10/14 | 5:40 | 13,667.07 | 13,839.23 | 172,160 | 13,838,780 | |
| 06/11/14 | 4:50 | 13,839.23 | 13,952.75 | 113,520 | 13,952,300 | |
| 06/12/14 | 6:50 | 13,952.75 | 14,138.23 | 185,480 | 14,137,780 | |
| 06/13/14 | 13:15 | 14,138.23 | 14,296.51 | 158,280 | 14,296,060 | |
| 06/14/14 | 7:50 | 14,296.51 | 14,447.78 | 151,270 | 14,447,330 | |
| 06/16/14 | 8:20 | 14,447.78 | 14,602.88 | 155,100 | 14,602,430 | |
| 06/17/14 | 7:55 | 14,602.88 | 14,717.27 | 114,390 | 14,716,820 | |
| 06/18/14 | 8:00 | 14,717.27 | 14,832.09 | 114,820 | 14,831,640 | |
| 06/19/14 | 7:20 | 14,832.09 | 14,937.60 | 105,510 | 14,937,150 | |
| 06/20/14 | 8:20 | 14,937.60 | 15,083.23 | 145,630 | 15,082,780 | |
| 06/21/14 | 3:00 | 15,083.23 | 15,127.76 | 44,530 | 15,127,310 | |
| 06/23/14 | 7:50 | 15,127.76 | 15,294.76 | 167,000 | 15,294,310 | |
| 06/24/14 | 8:30 | 15,294.76 | 15,348.15 | 53,390 | 15,347,700 | |
| 06/25/14 | 8:15 | 15,348.15 | 15,452.33 | 104,180 | 15,451,880 | |
| 06/26/14 | 7:50 | 15,452.33 | 15,551.63 | 99,300 | 15,551,180 | |
| 06/27/14 | 7:45 | 15,551.63 | 15,616.53 | 64,900 | 15,616,080 | |
| 06/30/14 | 8:00 | 15,616.53 | 15,754.00 | 137,470 | 15,753,550 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 135,141,143-145 | <20 | 124-145-20-a | 675 | 124-145-20-a1 | 5/9/2014 | 9:00 | 22.8 | | Yes | |
| | | | | 124-145-20-a2 | 5/9/2014 | 9:05 | 0.4 | Yes | | |
| | | | | 124-145-20-a3 | 5/9/2014 | 9:10 | 5.4 | Yes | | |
| | | | | 124-145-20-a4 | 5/9/2014 | 9:15 | 3.0 | Yes | | |
| 139-142B, 131-132A | <20 | 124-142-20-a | 1000 | 124-142-20-a1 | 5/15/2014 | 11:00 | 2.1 | Yes | | |
| | | | | 124-142-20-a2 | 5/15/2014 | 11:05 | 8.7 | Yes | | |
| | | | | 124-142-20-a3 | 5/15/2014 | 11:10 | 5.9 | Yes | | |
| | | | | 124-142-20-a4 | 5/15/2014 | 11:15 | 4.3 | Yes | | |
| 135-138B, 131A | <20 | 124-138-20-a, b | 1500 | 124-138-20-a1 | 5/19/2014 | 10:45 | 4.0 | Yes | | |
| | | | | 124-138-20-a2 | 5/19/2014 | 10:50 | 10.2 | Yes | | |
| | | | | 124-138-20-a3 | 5/19/2014 | 10:55 | 5.7 | Yes | | |
| | | | | 124-138-20-a4 | 5/19/2014 | 11:00 | 3.9 | Yes | | |
| | | | | 124-138-20-b1 | 5/19/2014 | 11:05 | 1.2 | Yes | | |
| | | | | 124-138-20-b2 | 5/19/2014 | 11:10 | 4.9 | Yes | | |
| | | | | 124-138-20-b3 | 5/19/2014 | 11:15 | 2.7 | Yes | | |
| | | | | 124-138-20-b4 | 5/19/2014 | 11:20 | 5.4 | Yes | | |
| 129-134 | <20 | 124-134-20-a, b | 1250 | 124-134-20-a1 | 5/21/2014 | 13:10 | 7.5 | Yes | | |
| | | | | 124-134-20-a2 | 5/21/2014 | 13:15 | 7.8 | Yes | | |
| | | | | 124-134-20-a3 | 5/21/2014 | 13:20 | 4.2 | Yes | | |
| | | | | 124-134-20-a4 | 5/21/2014 | 13:25 | 30.5 | | Yes | |
| | | | | 124-134-20-b1 | 5/21/2014 | 13:30 | 10.7 | Yes | | |
| | | | | 124-134-20-b2 | 5/21/2014 | 13:35 | 2.5 | Yes | | |
| | | | | 124-134-20-b3 | 5/21/2014 | 13:40 | 4.9 | Yes | | |
| | | | | 124-134-20-b4 | 5/21/2014 | 13:45 | 7.3 | Yes | | |
| 139-142B, 131-132A | <20 | 124-128-20-a | 1000 | 124-128-20-a1 | 6/3/2014 | 10:45 | 32.4 | | Yes | |
| | | | | 124-128-20-a2 | 6/3/2014 | 10:50 | 38.4 | | Yes | |
| | | | | 124-128-20-a3 | 6/3/2014 | 10:55 | 17.0 | Yes | | |
| | | | | 124-128-20-a4 | 6/3/2014 | 11:00 | 45.1 | | Yes | |
| 124-126 | <20 | 124-126-20-a, b | 1450 | 124-126-20-a1 | 6/13/2014 | 11:00 | 41.1 | | Yes | |
| | | | | 124-126-20-a2 | 6/13/2014 | 11:05 | 13.9 | Yes | | |
| | | | | 124-126-20-a3 | 6/13/2014 | 11:10 | 15.0 | Yes | | |
| | | | | 124-126-20-a4 | 6/13/2014 | 11:15 | 2.9 | Yes | | |
| | | | | 124-126-20-b1 | 6/13/2014 | 11:20 | 12.9 | Yes | | |
| | | | | 124-126-20-b2 | 6/13/2014 | 11:25 | 8.6 | Yes | | |
| | | | | 124-126-20-b3 | 6/13/2014 | 11:30 | 59.4 | | Yes | |
| | | | | 124-126-20-b4 | 6/13/2014 | 11:35 | 8.0 | Yes | | |
| 119-124 | <20 | 124-124-20-a, b | 2000 | 124-124-20-a1 | 6/25/2014 | 6:40 | ** | | | |
| | | | | 124-124-20-a2 | 6/25/2014 | 6:45 | ** | | | |
| | | | | 124-124-20-a3 | 6/25/2014 | 6:50 | ** | | | |
| | | | | 124-124-20-a4 | 6/25/2014 | 6:55 | ** | | | |
| | | | | 124-124-20-b1 | 6/25/2014 | 7:00 | ** | | | |
| | | | | 124-124-20-b2 | 6/25/2014 | 7:05 | ** | | | |
| | | | | 124-124-20-b3 | 6/25/2014 | 7:10 | ** | | | |
| | | | | 124-124-20-b4 | 6/25/2014 | 7:15 | ** | | | |
| 119-125 | >1000 | 124-125-1000-a | 550 | 124-125-1000-a1 | 6/25/2014 | 6:15 | ** | | | |
| | | | | 124-125-1000-a2 | 6/25/2014 | 6:20 | ** | | | |
| | | | | 124-125-1000-a3 | 6/25/2014 | 6:25 | ** | | | |
| | | | | 124-125-1000-a4 | 6/25/2014 | 6:30 | ** | | | |
| 115-119 | <20 | 124-119-20-a | 1000 | 124-119-20-a1 | 6/27/2014 | 13:00 | ** | | | |
| | | | | 124-119-20-a2 | 6/27/2014 | 13:05 | ** | | | |
| | | | | 124-119-20-a3 | 6/27/2014 | 13:10 | ** | | | |
| | | | | 124-119-20-a4 | 6/27/2014 | 13:15 | ** | | | |

**Notes:**
*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

## Attachment 7:  Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
05-07-2014

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP–1




May 07, 2014 at 4:13pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | South | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-1 | FS-3 | FS-4 | FS-5 |
| Date | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | 7.5 | 7.9 | 7.7 | 5.9 |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | 7.7 | 8.1 | 7.9 | 7.2 |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | 7.6 | 7.8 | 7.6 | 8.0 |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | 7.4 | 8.0 | 8.0 | 8.6 |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | 7.4 | 8.4 | 8.4 | 9.4 |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | 6.1 | 7.9 | 7.6 | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO

## Attachment 8: Quality and Level Data in GWET Wells

(provided on a quarterly basis)

- Summary of Groundwater Quality Data from GWET Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells


**Table 1**
Summary of Groundwater Quality Data from GWET Wells


Honeywell

| Parameter | 20-Sep-13 | | | 3-Dec-13 | | | 1-Apr-14 | | | 28-May-14 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-203BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-203BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 3.1 | 4.4 | ND | 3.4 | 5.2 | ND | 2.9 | 4.0 | ND | 3.4 | 4.7 | ND |
| Carbon Tetrachloride | 4.6 | 3.1 | 1.4 | 5.8 | 4.8 | 2.5 | 4.4J | 2.8 | 1.9 | 7.0 | 4.3 | 2.7 |
| Chloroform | 27.4 | 17.9 | ND | 31.0 | 16.8 | ND | 26.5 | 12.0 | ND | 31.3 | 14.0 | 0.25J |
| 1,1-Dichloroethene | 0.55 | ND | ND | 0.07 | ND | ND | 0.42J | ND | ND | 0.77J | ND | ND |
| cis-1,2-Dichloroethene | 148 | 13.8 | ND | 135 | 12.3 | ND | 96 | 8.1 | ND | 144 | ND | ND |
| trans-1,2-Dichloroethene | 4.5 | 0.76 | ND | 4.9 | 0.35 | ND | 3.4 | ND | ND | 5.3 | ND | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 95.1 | 52.6 | ND | 113.0 | 63.0 | ND | 91.3 | 43.4 | ND | 119 | 54.8 | ND |
| 1,1-Dichloroethane | 0.45 | ND | ND | 0.47 | ND | ND | 0.45J | ND | ND | 0.61J | ND | ND |
| Methylene chloride | 0.84 | ND | ND | 0.87 | 0.31 | ND | 0.77J | ND | ND | 0.92J | ND | ND |
| Vinyl chloride | 12.6 | ND | ND | 14.2 | 4.8 | ND | 13.5 | 2.7 | ND | 21.2 | 3.8 | ND |
| 1,2-Dichlorobenzene | 0.66 | ND | ND | 0.72 | ND | ND | 0.72J | ND | ND | 0.70J | ND | ND |
| Chlorobenzene | 0.38 | ND | ND | 0.39 | ND | ND | 0.38J | ND | ND | 0.40J | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 38,200 | 11,400 | 16,700 | 39,600 | 11,300 | 16,500 | 33,400 | 12,500 | 15,100 | 34,700 | 12,700 | 19,700 |
| Total Chromium | 39,900 | 13,500 | 17,000 | 34,200 | 10,600 | 14,900 | 36,900 | 16,400 | 16,600 | 35,500 | 14,500 | 19,600 |


NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.

Note:
Starting with 1st quarter 2014, well 115-MW-215BR is being pumped and sampled.





Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR

## Attachment 9: Surcharge Monitoring Update

- Instrumentation Location Plan 1S
- Instrumentation Location Plan 2N




| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS5 | 685595.33 | 602744.87 |
| FS6 | 685557.42 | 602879.95 |
| FS7 | 685445.18 | 603001.32 |
| SP11 | 685784.33 | 602832.31 |
| SP12 | 685740.52 | 602811.34 |
| SP13 | 685682.87 | 602934.55 |
| SP14 | 685624.73 | 603120.29 |
| SP15 | 685568.20 | 603092.95 |
| SP16 | 685617.61 | 602843.89 |
| SP17 | 685555.82 | 602977.36 |
| SP18 | 685562.79 | 602751.98 |
| SP19 | 685530.51 | 602838.96 |
| SP20 | 685429.14 | 602978.06 |
| VRC4 | 685521.71 | 602848.37 |

Installed Insturment Locations

Insturment Locations Not Installed

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
6. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

VI-2 INCLINOMETER LOCATION

FS-1-1 SETTLEMENT MONITORING POINT FULL – SET UP

HS12 SETTLEMENT MONITORING POINT HALF – SET UP

SP12 SETTLEMENT MONITORING PLATFORM

RP APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7)

VRC1 VIBRATING WIRE PIEZOMETER IN STRATUM RC

Prepared/Date: RJR 08/15/13
Checked/Date: AE 08/15/13

0 15 30 60
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472


amec

INSTRUMENTATION LOCATION PLAN 2N
Project 3480-09-0006
Figure C1



Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-6-2013\CAD\SA6N\100 Percent\Figure 2- Surcharge Settling Monitoring Plan – Area 2.dwg Thu, 15 Aug 2013 - 4:07pm roger.hulder




SECTION A–A

Installed Instrumentation Locations

Instrumentation Locations Not Installed

| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–1 | 685276.02 | 601927.05 |
| FS–2 | 685323.86 | 601748.51 |
| HS–1 | 685597.02 | 601567.16 |
| HS–2 | 685511.42 | 601690.72 |
| HS–3 | 685421.98 | 601800.88 |
| HS–4 | 685313.18 | 601947.19 |
| HS–5 | 685480.23 | 601623.90 |
| HS–6 | 685518.78 | 601480.25 |
| HS–7 | 685413.06 | 601624.11 |
| HS–8 | 685204.27 | 601911.97 |
| VI–1 | 685624.44 | 601515.06 |
| VI–2 | 685578.58 | 601462.08 |
| VRC–1 | 685505.92 | 601505.39 |
| VRC–2 | 685434.27 | 601785.68 |
| VRC–3 | 685262.85 | 601914.43 |
| SP–1 | 685567.71 | 601633.29 |
| SP–2 | 685410.62 | 601852.31 |
| SP–3 | 685276.93 | 602033.96 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 07/19/13
Checked/Date: AE 07/19/13

Honeywell
101 COLUMBIA RD., BOX 2106
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY


amec


INSTRUMENTATION LOCATION PLAN 1S

Figure F1


## Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Monitoring Locations
- Sheet Pile Repair Log




BEFORE DRIVING SHEETS




SHEET SEALING DETAIL (BF) TYP S-203
NTS

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |
| STRUCTURAL | 19+00 | 21+20 | -19 | AZ 19-700 |
| STRUCTURAL | 21+20 | 23+20 | -15 | AZ 19-700 |
| STRUCTURAL | 23+20 | 24+37 | -12 | AZ 19-700 |
| NON STRUCTURAL | 24+37 | 25+89 | -12 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04352400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | DR | RJR | TDD |

ISSUED FOR CONSTRUCTION
REVISION

| TDD | SHM |
|---|---|
| BY | APVD |

SHM

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING, FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD BOX 2105 MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER PLAN & PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton NJ 08619
(609) 587-2829
NJ Certificate of Authorization Number 24GA28016900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


DATE
PROJ 3480-12-0317
DWG S-203
SHEET 55 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND IS NOT TO BE REPRODUCED THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.






NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 03-20-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-10

Entact ID:

Date Exposed: 5/21/14

Describe Damage: (6) Miner scrapes by the Cat 349E Excavator Bucket- Range from 1/2"Ø to 1"x3" (Cell 128)

Damage Location (ft below top of sheet, inboard side,outboard side): 7'-10' outboard side

Date Repaired: 6/2/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-11

Entact ID:

Date Exposed: 5/21/14

Describe Damage: (5) Miner scrapes by the Cat 349E Excavator Bucket- (Cell 128)

Damage Location (ft below top of sheet, inboard side outboard side): 7'-10' outboard side

Date Repaired: 6/2/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-12

Entact ID:

Date Exposed: 5/21/14

Describe Damage: (4) Scrapes by the Cat 349E Excavator bucket - (Cell 128)

Damage Location (ft below top of sheet, inboard side outboard side): 5'-10' outboard

Date Repaired: 6/2/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-13

Entact ID:

Date Exposed: 5/21/14

Describe Damage: (8) scrapes by the CAT349E Excavator Bucket - (Cell 128)

Damage Location (ft below top of sheet, inboard side outboard side): 6-10' outboard

Date Repaired: 6/2/14

Inspected by: Brian Shea

Describe Repair: Pressure Wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 15P-14

Entact ID:

Date Exposed: 5/23

Describe Damage:

(3) minor scrapes by the Cat 349E Excavator bucket - cell 127

Damage Location (ft below top of sheet, inboard side outboard side):

6'-10' outboard

Date Repaired: 6/2/14

Inspected by: Mike Senna

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: B Shea

Date: 6/5/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 15P-15

Entact ID:

Date Exposed: 5/23

Describe Damage:

(4) minor scrapes by the Cat 349E Excavator bucket - cell 127

Damage Location (ft below top of sheet, inboard side outboard side):

6'-10' outboard side

Date Repaired: 6/2/14

Inspected by: Mike Senna

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: B Shea

Date: 6/5/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 15P-16

Entact ID:

Date Exposed: 5/23

Describe Damage:

(4) minor scrapes by the Cat 349E Excavator Bucket - (Cell 127)

Damage Location (ft below top of sheet, inboard side outboard side):

7-10' outboard side

Date Repaired: 6/2/14

Inspected by: Mike Senna

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: B Shea

Date: 6/5/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 15P-17

Entact ID:

Date Exposed: 5/27/14

Describe Damage:

(3) Minor scrapes by the Cat 349E Excavator Bucket (Cell 126)

Damage Location (ft below top of sheet, inboard side outboard side):

6'-10' outboard

Date Repaired: 6/2/14

Inspected by: Mike Senna

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: B Shea

Date: 6/5/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15 P-18

Entact ID:

Date Exposed: 5/27/14

Describe Damage: Scrapes by Cat 349E excavator bucket- 1"Ø, 1/2"Ø, 1/2"x4" - Cell 126

Damage Location (ft below top of sheet, inboard side outboard side): 8-10' outboard

Date Repaired: 6/3/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, and apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15 P-19

Entact ID:

Date Exposed: 5/27/14

Describe Damage: (3) Scrapes by the Cat 349E excavator bucket- 1"Ø, 1/2x2", 2" - Cell 126

Damage Location (ft below top of sheet, inboard side outboard side): 7-9' outboard

Date Repaired: 6/3/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-20

Entact ID:

Date Exposed: 5/27/14

Describe Damage: (7) Scrapes by the Cat 349E excavator bucket - 1"Ø, 1x4", 1x5", 1/2"Ø, 1/2"Ø, 2"Ø, 1/2"x14", - Cell 125

Damage Location (ft below top of sheet, inboard side outboard side): 6-10' outboard

Date Repaired: 6/3/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" Paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 15P-21

Entact ID:

Date Exposed: 5/27/14

Describe Damage: (4) scrapes by the Cat 349E Excavator bucket - 1/2"Ø, 1/2x6", 3"Ø, 2"Ø - Cell 125

Damage Location (ft below top of sheet, inboard side outboard side): 6-10' outboard

Date Repaired: 6/3/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire wash, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 15P-26

Entact ID:

Date Exposed: 6/5/14

Describe Damage: (7) minor scrapes by the Cat 349E Excavator bucket- 1/2"Ø, 1"Ø, 1"x3", 2"Ø, 1"x40", 1/2"Ø, 1"x2". (Cell 124)

Damage Location (ft below top of sheet, inboard side outboard side): 5'-10' outbeard

Date Repaired: 6/11/14

Inspected by: Brian Shea

Describe Repair: Pressure washed, wire brushed, epoxy applied w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/13/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-1

Entact ID:

Date Exposed: 6/6/14

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1"Ø, 1"x2", 1/2"Ø, 1/2"x3", 1/2"x50". (Cell 123)

Damage Location (ft below top of sheet, inboard side outboard side): 11'-15' outbeard

Date Repaired: 6/11/14

Inspected by: Brian Shea

Describe Repair: Pressure washed, wire brushed, epoxy applied w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 6/13/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-2

Entact ID:

Date Exposed: 6/6/14

Describe Damage: (8) scrapes by Cat 349E excavator bucket - 1"Ø, 1"Ø, 1/2"Ø, 1"x2", 1"Ø, 2"Ø, 1"x36", 1/2"x24". (Cell 123)

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outbeard

Date Repaired: 6/11/14

Inspected by: Brian Shea

Describe Repair: Pressure washed, wire brushed, applied epoxy w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 6/13/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-6

Entact ID:

Date Exposed: 6/9/14

Describe Damage: (2) scrapes by the CAT 349E excavator bucket - 1/2"x36", 1"Ø (Cell 123)

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outbeard

Date Repaired: 6/13/14

Inspected by: Brian Shea

Describe Repair: pressure washed, iron brushed, epoxy applied w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/13/14

*A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-10

Entact ID:

Date Exposed: 6/9/14

Describe Damage: (9) scrapes by the Cat 349E excavator bucket - 1"x36", 5 - ½"Ø, 1"Ø, 1"x2", 1"x5". (Cell 123)

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outboard

Date Repaired: 6/13/14

Inspected by: Brian Shea

Describe Repair: pressure washed, wire brushed, applied epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/13/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-16

Entact ID:

Date Exposed: 6/10/14

Describe Damage: (6) scrapes by the Cat 349E excavator bucket - 1"x24", 1"Ø, 2"Ø, ½"x3", ½"x5", ½"Ø (cell 122)

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outboard

Date Repaired: 6/13/14

Inspected by: Brian Shea

Describe Repair: pressure washed, wire brushed, applied epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/13/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-9

Entact ID:

Date Exposed: 6/13/14

Describe Damage: (9) scrapes by the Cat 349E excavator bucket - 2"x12", 2"Ø, 1"Ø, 2x2", 2"x6", 1"Ø, ½"Ø, 2"Ø, 1"Ø, ½"Ø (cell 122)

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outboard side

Date Repaired: 6/17/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/18/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-7

Entact ID:

Date Exposed: 6/13/14

Describe Damage: (6) scrapes by the Cat 349E excavator bucket - ½"Ø, 1"x3", ½"x18", ½"x12", 1"x24", 1"Ø (Cell 121)

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outboard

Date Repaired: 6/17/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/18/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-8

Entact ID:

Date Exposed: 6/13/14

Describe Damage: (18) Scrapes by the Cat 349E excavator bucket - 1/2ø, 1"ø, 1"ø, 2"x10", 1"x6", 2"ø, 1/2"x12", 1"x14", 1"x20", 1/2"ø, 1/2"ø, 1"ø, 1/2"ø, 1"x8", 2"ø, 1/2"ø

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard side

Date Repaired: 6/17/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/18/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-9

Entact ID:

Date Exposed: 6/18/14

Describe Damage: (10) Scrapes by the Cat 349E excavator bucket - 1x8", 4x12", 1/2x10", 1"ø, 1/2x6", 1x4" - Cell 121

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/19/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/20/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-10

Entact ID:

Date Exposed: 6/18/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 1x8", 1"ø, 1x12", 1/2"ø, 1x24", 1/2x8, 1/2x30", 1x5" - Cell 121/120

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/19/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/20/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 16P-11

Entact ID:

Date Exposed: 6/18/14

Describe Damage: (9) scrapes by the cat 349E excavator bucket - 1"ø, 1/2x3", 1x8", 1"ø, 1"ø, 1"ø, 1x36", 1x40", 1/2"ø - Cell 120

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/19/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 6/20/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-12

Entact ID:

Date Exposed: 6/18/14

Describe Damage: (4) scrapes by the Cat 349E excavator bucket - 1/2"x8", 2"Ø, 2x6", 1/2"Ø - Cell 120

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/19/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/20/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-13

Entact ID:

Date Exposed: 6/18/14

Describe Damage: (9) scrapes by Cat 349E excavator bucket - 4x8", 1x18", (7) 1"Ø - Cell 120

Damage Location (ft below top of sheet, inboard side outboard side): 10'-15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-14

Entact ID:

Date Exposed: 6/18/14

Describe Damage: (3) scrapes by Cat 349E excavator bucket - 1"Ø, 1/2"Ø, 1/2x6"

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/24/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-15

Entact ID:

Date Exposed:

Describe Damage: 6/18/14 (8) Scrapes by Cat 349E excavator bucket - 1"Ø, (3) 1/2"Ø, 1x24", 1/2"Ø, 2"Ø, 1"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/24/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16-P16

Entact ID:

Date Exposed: 6/19/14

Describe Damage: (9) scrapes by Cat 349E excavator bucket - 1"Ø, 1/2x2", 1x4", 1x8", 1/2"Ø, 1x12", (3) 1/2"Ø

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-17

Entact ID:

Date Exposed: 6/19/14

Describe Damage: (3) scrapes by Cat 349E excavator bucket 1/2x18", 1/2"Ø, 1/2x10"

Damage Location (ft below top of sheet, inboard side outboard side): 10-13' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-18

Entact ID:

Date Exposed: 6/19/14

Describe Damage: (3) scrapes by Cat 349E excavator bucket - 1/2x6", 1/2x3", 1/2"x10".

Damage Location (ft below top of sheet, inboard side outboard side): 12-15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-19

Entact ID:

Date Exposed: 6/19/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket- 1"Ø, 1/2x18", 1/2x12", 1/2"Ø, 2"Ø, 1/2"Ø, 1/2x8, 2"Ø - Cell 118

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" wire brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-20
Entact ID:
Date Exposed: 6/23/14
Describe Damage:
(5) scrapes by the Cat 349E excavator bucket- 2"Ø, 1/2"Ø, 1/2x48", 1/2x30", 1/2x8" - Cell 117

Damage Location (ft below top of sheet, inboard side outboard side):
9-15' outboard

Date Repaired: 6/24/14
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-21
Entact ID:
Date Exposed: 6/23/14
Describe Damage: 6/23/14
(3) scrapes by the Cat 349E excavator bucket- 1/2x10", 1"x30", 2x3" - Cell 117

Damage Location (ft below top of sheet, inboard side outboard side):
10ft - 15ft outboard

Date Repaired: 6/24/14
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 16P-22
Entact ID:
Date Exposed: 6/23/14
Describe Damage:
(14) scrapes by the Cat 349E excavator bucket- (5) 1/2"Ø, 1/4"x10", 1"Ø, 2"Ø, 1/2x18", 1"Ø, 1/2x30", 2x10", 1/4x4" - Cell 117

Damage Location (ft below top of sheet, inboard side outboard side): 10-15'
outboard

Date Repaired: 6/24/14
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P-1
Entact ID:
Date Exposed: 6/23/14
Describe Damage: 6/23/14
(6) scrapes by the Cat 349E excavator bucket- 1/2x18", 1x24", 1/2"Ø, 1"Ø, 1/2x10", 1/2"x24" - Cell 117

Damage Location (ft below top of sheet, inboard side outboard side):
9-15' outboard

Date Repaired: 6/24/14
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P-2

Entact ID:

Date Exposed: 6/24/14

Describe Damage: (10) scrapes by the Cat 349E excavator bucket - 1x10", 1x6", 1"Ø, 1/2"Ø, 1"Ø, 1x2", 1/2x3", 5x36", 1x36" 1/2"Ø - Cell 116

Damage Location (ft below top of sheet, inboard side outboard side): 10/15' outboard

Date Repaired: 6/24/14

Inspected by: Brian Shea

Describe Repair: Prossure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P-3

Entact ID:

Date Exposed: 6/24/14

Describe Damage: (13) scrapes by the cat 349E excavator bucket- (7) 1/2"Ø, (4) 1"Ø, 1x8", 1/2x60", - Cell 116

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 6/26/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/26/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P1-4

Entact ID:

Date Exposed: 6/24/14

Describe Damage: (8) scrapes by Cat 349E excavator bucket - 1/2"x6", 1/4x3", 1x12", 2x10", 1/2x3", 1/2"Ø, 1/2x8", 12"Ø, - Cell 116

Damage Location (ft below top of sheet, inboard side outboard side): 10-15 outboard

Date Repaired: 6/26/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/26/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P1-5

Entact ID:

Date Exposed: 6/24/14

Describe Damage: (6) scrapes by the Cat 349E excavator bucket - 1x18", 1x30", 1/2x1", 1/2x4", 1/2x8", 12"Ø - cell 115

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/26/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/26/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P1-7

Entact ID:

Date Exposed: 6/24/14

Describe Damage:

(7) scrapes by the Cat 349E excavator bucket- 1/2x48", 1/2"Ø, 2x6", 2"Ø, 1x24", 2"Ø, 3"Ø.- Cell 115

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 6/26/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/26/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P1-6

Entact ID:

Date Exposed: 6/24/14

Describe Damage:

(15) scrapes by the Cat 349E excavator bucket - 1/2x3", 1x4", 1/2x24", 1/2"Ø, 1/2"Ø 1/2"Ø, 3x12", (4) 1"Ø, 1x18", 1x2", 1x4", 2"Ø,- Cell 115

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 6/26/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 6/26/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

## Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 5, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2,3,4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 5 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/05/14

SWPPP Observer: (George Pfeiffer)
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Thursday, June 05, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | A catch basin to the west of the scalehouse requires silt protection. |
| 2 | IA2Q4A1AL8 | A cut-out in the 18" asphalt berm which is located on the western edge of the western SA-7 roadway requires silt protection. |
| 3 | IA2Q4A1AL8 | Silt fencing along the southern toe of the N-1 surcharge area requires maintenance. |
| 4 | IA2Q4A1AL8 | Straw waddle on the northern SA-7 roadway requires replacement. |
| 5 | IA2Q4A1AL8 | A small pile of backfill material located to the east of the SA-7 river bulkhead requires removal. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature Date: 06/05/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace filter fabric in the catch basin. | 6-17-14 |
| 2 | Place waddle or hay bales in the gap in the berm to prevent sediment run-off. | 6-12-14 |
| 3 | Maintain silt fence, restapling fabric to the stakes. Toe in fabric as required. | 6-16-14 |
| 4 | Replace the straw waddle on the northern SA-7 roadway. | 6-12-14 |
| 5 | Remove the small pile of quarry screening material from the SA-7 bulkhead area. Use light equipment and maintain a distance of at least 30' from the wooden bulkhead. | 6-13-14 |
| | | |
| | | |
| | | |

**Construction Manager:** _____ Date: 06/17/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 12, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2,3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 4 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 5 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/12/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, June 12, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone signs on the orange fencing immediately west of the scale house are not needed and should be removed to avoid confusion. |
| 2 | IA2Q4A1AL8 | REPEAT: A cut-out in the 18" asphalt berm which is located on the western edge of the western SA-7 roadway requires silt protection. |
| 3 | IA2Q4A1AL8 | REPEAT: Silt fencing along the southern toe of the N-1 surcharge area requires maintenance. |
| 4 | IA2Q4A1AL8 | The truck entrance/exit to the Novartis stockpile containment area requires additional measures to prevent the tracking of material out onto Study Area 7. |
| 5 | IA2Q4A1AL8 | REPEAT: A small pile of backfill material located to the east of the SA-7 river bulkhead requires removal. The material was transported to this area during snow removal activities over the previous winter. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature **Date:** 06/12/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove the unnecessary signage from the orange fence. The area behind this section of fencing is not currently an Exclusion Zone. | 6-13-14 |
| 2 | Place waddle or hay bales in the gap in the berm to prevent sediment run-off. | 6-12-14 |
| 3 | Maintain silt fence, restapling fabric to the stakes. Toe in fabric as required. | 6-16-14 |
| 4 | Install a tracking pad or other control measures to minimize the tracking of surcharge material out of the containment area. | 6-13-14 |
| 5 | Remove the small pile of quarry screening material from the SA-7 bulkhead area. Use light equipment and maintain a distance of at least 30' from the wooden bulkhead. | 6-13-14 |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 06/17/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 19, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | | X | | 5 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/20/14

SWPPP Observer: G. Pfeiffer
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, June 19, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing along the southern perimeter of the western excavation requires maintenance. |
| 2 | IA2Q4A1AL8 | An electrical road box just to the west of the scale house has a collapsed lid. |
| 3 | IA2Q4A1AL8 | There are no markers showing the southern edge of the N-1 surcharge pile or the ramp on its eastern end. |
| 4 | IA2Q4A1AL8 | Orange warning fencing at the southwest corner of the sedimentation basin requires maintenance. |
| 5 | IA2Q4A1AL8 | A semdiment check dam is needed in the swale at the southwest corner of Study Area 7. |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 06/20/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair Exclusion Zone fencing to the south of the <20 ppm stockpile. | 6-20-14 |
| 2 | Repair the road box located in the southwestern haul road. | 6-23-14 |
| 3 | Place traffic cones or other appropriate markers at intervals along the top of the slope of the N-1 surcharge pile and along the edges of its eastern access ramp. | 6-23-14 |
| 4 | Repair the warning fence to block access from the N-1 surcharge pile to the concrete overflow tank abutting it. | 6-23-14 |
| 5 | Install a sediment check dam just to the east of the straw waddle in the southern SA-7 stormwater discharge weir. | 6-20-14 |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 06/24/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 26, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/27/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, June 26, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing along the southern perimeter of the western excavation requires maintenance. |
| 2 | IA2Q4A1AL8 | Stone in the southeastern exit tracking pad is blinded and requires maintenance |
| 3 | IA2Q4A1AL8 | A 10 MPH speed limit sign (or multiple signs) are required on the eastern SA-7 paved access road for the trucks delivering surcharge material. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 06/27/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair Exclusion Zone fencing along the southern perimeter of the excavation area. | 7-1-14 RAD |
| 2 | Clean or replace the stone in the tracking pad located to the east of the 60 Kellogg building. | 7-2-14 RAD |
| 3 | Install the reflective 10 MPH speed limit sign which is currently located under the Entact office trailer. | 6-30-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/02/14

## Attachment 12: GWTP Update

- 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (April 2014)
- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (April 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

June 18, 2014

New Jersey Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: May 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the May 2014 Surface Water Discharge Monitoring Report for Outfall 001A. Please note that there was no discharge this monitoring period.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Frank Schroyer - Parsons

PI 234822

New Jersey Department of Environmental Protection
Division of Water Quality

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 5 | 1 | 2014 | To | 5 | 31 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☒ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J Morris , Remediation Director — —

**NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** **GRADE AND REGISTRY NUMBER (IF APPLICABLE)**

John J. Morris IV 06/17/2014 973.455.4003

**SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** **DATE** **AREA CODE/PHONE NUMBER**

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J Morris , Remediation Director John J. Morris IV 06/17/2014 973.455.4003

**NAME AND TITLE** **SIGNATURE** **DATE** **AREA CODE/PHONE NUMBER**

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 5/1/2014 TO 5/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | | | GPD | ****** | ****** | ****** | ****** | | | |
| | PERMIT REQUIREMENT | REPORT 01MOAV | REPORT 01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | | SU | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0 01MOMN | ****** | 9.0 01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 50 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10 01MOAV | 15 01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 20 01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 5/1/2014 TO 5/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 5/1/2014 TO 5/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50<br>01MOAV | 100<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | REPORT<br>01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 0.025<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 8.8<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 46<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 54<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 5/1/2014 TO 5/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | | | | | | | | | | |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

June 18, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the May 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc., Bayfront Redevelopment

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 5 | 01 | 14 | 5 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 79,469 | 88,443 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 1.73 | 1.93 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.2 | <5.2 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.077 | 0.077 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

June 13, 2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc., Bayfront Redevelopment

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 5 | 01 | 14 | 5 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,463,526 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 8,123,739 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 5/13/2014 | <10 | 6.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE June 13, 2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Bayfront Redevelopment; GWTP (Permit #31630016) | | | | | | | | MONTH: May 2014 | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 5/1/2014 | Angel Trujillo | 5660213 | 5741873 | 81,660 | 0.08166 | 7.61 | 2.610 | | | | | | | | | 1.78 |
| 5/2/2014 | Angel Trujillo | 5741873 | 5823281 | 81,408 | 0.081408 | 7.73 | 2.610 | | | | | | | | | 1.77 |
| 5/3/2014 | Angel Trujillo | 5823281 | 5909094 | 85,813 | 0.085813 | 7.64 | 2.610 | | | | | | | | | 1.87 |
| 5/4/2014 | Angel Trujillo | 5909094 | 5989437 | 80,343 | 0.080343 | 7.55 | 2.610 | | | | | | | | | 1.75 |
| 5/5/2014 | Angel Trujillo | 5989437 | 6063807 | 74,370 | 0.07437 | 7.59 | 2.610 | | | | | | | | | 1.62 |
| 5/6/2014 | Angel Trujillo | 6063807 | 6141420 | 77,613 | 0.077613 | 8.03 | 2.610 | | | | | | | | | 1.69 |
| 5/7/2014 | Angel Trujillo | 6141420 | 6220321 | 78,901 | 0.078901 | 8.01 | 2.610 | | | | | | | | | 1.72 |
| 5/8/2014 | Angel Trujillo | 6220321 | 6296105 | 75,784 | 0.075784 | 7.82 | 2.610 | | | | | | | | | 1.65 |
| 5/9/2014 | Angel Trujillo | 6296105 | 6377235 | 81,130 | 0.08113 | 7.61 | 2.610 | | | | | | | | | 1.77 |
| 5/10/2014 | Angel Trujillo | 6377235 | 6462763 | 85,528 | 0.085528 | 7.82 | 2.610 | | | | | | | | | 1.86 |
| 5/11/2014 | Angel Trujillo | 6462763 | 6540118 | 77,355 | 0.077355 | 7.76 | 2.610 | | | | | | | | | 1.68 |
| 5/12/2014 | Angel Trujillo | 6540118 | 6615585 | 75,467 | 0.075467 | 7.68 | 2.610 | | | | | | | | | 1.64 |
| 5/13/2014 | Angel Trujillo | 6615585 | 6692802 | 77,217 | 0.077217 | 7.53 | 2.610 | <5.2 | <10 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 1.68 |
| 5/14/2014 | Angel Trujillo | 6692802 | 6769848 | 77,046 | 0.077046 | 7.81 | 2.610 | | | | | | | | | 1.68 |
| 5/15/2014 | Angel Trujillo | 6769848 | 6849228 | 79,380 | 0.07938 | 7.70 | 2.610 | | | | | | | | | 1.73 |
| 5/16/2014 | Angel Trujillo | 6849228 | 6927706 | 78,478 | 0.078478 | 7.57 | 2.610 | | | | | | | | | 1.71 |
| 5/17/2014 | Angel Trujillo | 6927706 | 7012269 | 84,563 | 0.084563 | 7.86 | 2.610 | | | | | | | | | 1.84 |
| 5/18/2014 | Angel Trujillo | 7012269 | 7092708 | 80,439 | 0.080439 | 7.69 | 2.610 | | | | | | | | | 1.75 |
| 5/19/2014 | Angel Trujillo | 7092708 | 7169062 | 76,354 | 0.076354 | 7.64 | 2.610 | | | | | | | | | 1.66 |
| 5/20/2014 | Angel Trujillo | 7169062 | 7248209 | 79,147 | 0.079147 | 7.82 | 2.610 | | | | | | | | | 1.72 |
| 5/21/2014 | Angel Trujillo | 7248209 | 7328272 | 80,063 | 0.080063 | 7.18 | 2.610 | | | | | | | | | 1.74 |
| 5/22/2014 | Angel Trujillo | 7328272 | 7405612 | 77,340 | 0.07734 | 7.63 | 2.610 | | | | | | | | | 1.68 |
| 5/23/2014 | Angel Trujillo | 7405612 | 7484852 | 79,240 | 0.07924 | 7.78 | 2.610 | | | | | | | | | 1.72 |
| 5/24/2014 | Angel Trujillo | 7484852 | 7565811 | 80,959 | 0.080959 | 7.81 | 2.610 | | | | | | | | | 1.76 |
| 5/25/2014 | Angel Trujillo | 7565811 | 7641138 | 75,327 | 0.075327 | 7.92 | 2.610 | | | | | | | | | 1.64 |
| 5/26/2014 | Angel Trujillo | 7641138 | 7729581 | 88,443 | 0.088443 | 7.84 | 2.610 | | | | | | | | | 1.93 |
| 5/27/2014 | Angel Trujillo | 7729581 | 7805733 | 76,152 | 0.0762 | 7.58 | 2.610 | | | | | | | | | 1.66 |
| 5/28/2014 | Angel Trujillo | 7805733 | 7881663 | 75,930 | 0.07593 | 7.86 | 2.610 | | | | | | | | | 1.65 |
| 5/29/2014 | Angel Trujillo | 7881663 | 7960797 | 79,134 | 0.079134 | 7.69 | 2.610 | | | | | | | | | 1.72 |
| 5/30/2014 | Angel Trujillo | 7960797 | 8039909 | 79,112 | 0.079112 | 7.83 | 2.610 | | | | | | | | | 1.72 |
| 5/31/2014 | Angel Trujillo | 8039909 | 8123739 | 83,830 | 0.08383 | 7.84 | 2.610 | | | | | | | | | 1.82 |
| TOTAL | | | | 2,463,526 | 2.463526 | | | <5.2 | <10 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 88,443 | | | | | | | | | | | High: | 1.93 |
| | | | Average: | 79,469 | | | | | | | | | | | Average: | 1.73 |

WW

E

JB66860

| | | |

Accutest LabLink@798422 09:51 05-Jun-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051314-A | | |
| **Lab Sample ID:** | JB66860-1 | **Date Sampled:** | 05/13/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/13/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 2610 | 10 | ug/l | 1 | 05/14/14 | 05/15/14 | RR | EPA 200.7 [1] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 05/14/14 | 05/15/14 | RR | EPA 200.7 [1] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 05/14/14 | 05/16/14 | RR | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 05/16/14 | 05/16/14 | DP | EPA 245.1 [2] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 05/14/14 | 05/15/14 | RR | EPA 200.7 [1] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 05/14/14 | 05/15/14 | RR | EPA 200.7 [1] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA34018
(2) Instrument QC Batch: MA34034
(3) Instrument QC Batch: MA34036
(4) Prep QC Batch: MP79497
(5) Prep QC Batch: MP79511

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@798422 09:51 05-Jun-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051314-A | | |
| **Lab Sample ID:** | JB66860-1 | **Date Sampled:** | 05/13/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/13/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | 6.0 | 4.0 | mg/l | 1 | 05/15/14 | RP | SM2540 D-11 |
| pH [a] | 7.07 | | su | 1 | 05/13/14 16:53 | IM | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@798422 09:51 05-Jun-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087 WWE 051314-A | | |
| Lab Sample ID: | JB66860-1A | Date Sampled: | 05/13/14 |
| Matrix: | AQ - Water | Date Received: | 05/13/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.2

4

General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 10 | 10 | mg/l | 1 | 05/14/14 18:53 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@798422 09:51 05-Jun-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-051314-B | | |
| Lab Sample ID: | JB66860-2 | Date Sampled: | 05/13/14 |
| Matrix: | AQ - Water | Date Received: | 05/13/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | 2C118845.D | 1 | 05/16/14 | TP | n/a | n/a | V2C5462 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA PPL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.1 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.6 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.26 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 18.1 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.4 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | ND | 1.0 | 0.20 | ug/l | |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 49.5 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 105% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 98% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 91% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 98% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@798422 09:51 05-Jun-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-051314-B | | |
| Lab Sample ID: | JB66860-2 | Date Sampled: | 05/13/14 |
| Matrix: | AQ - Water | Date Received: | 05/13/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.2 | 5.2 | mg/l | 1 | 05/15/14 | AA | EPA 1664A |

RL = Reporting Limit

## Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending June 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area; Update the list of monitoring wells to be abandoned / retained | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead | Submitted to all Parties on May 19, 2014. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**8/14/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

August 14, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-07**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from July 1 – July 31, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: July 2014 SA-6/7 Combined Monthly Progress Report No. 2014-07

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-07

**Project SA-6 & 7 Remediation**

## July 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 07/01/14 | Surcharge Monitoring Plan – Monthly Report No. 2<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/03/14 | Response to Plaintiff's June 25, 2014 E-Mail<br>Sediment Coring and Cap Thickness Determinations<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/03/14 | New Source of Imported Clean Fill<br>Study Area 6m Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/10/14 | Design Change Bulletin – 1S Surcharge Pile Geometry<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/10/14 | Responses to Comments Provided by Plaintiffs<br>Data Validation for Materials Excavated from Study Area 6<br>Study Areas 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/10/14 | NJPDES Permit NJ0156311: June 2014 Surface Water Discharge<br>Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | New Jersey Department of Environmental Protection<br>Division of Water Quality |
| 07/10/14 | Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>*(see **Attachment 12**)* | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 07/10/14 | PVSC - Acoustic Monitoring Report<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/11/14 | Combined Monthly Progress/Highlights Report No. 2014-06<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/22/14 | Special Master All Hands Meeting | N/A |
| 07/24/14 | Hydrocarbon-Impacted Soil Summary<br>Study Area 6 South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 07/31/14 | Surcharge Monitoring Plan – Monthly Report No. 3<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 07/06/14 | 07/13/14 | 07/20/14 | 07/27/14 |
| **Construction Management (AMEC)** | 12 | 13 | 13 | 12 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 36 | 37 | 37 | 42 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 0 |
| **ERFS In Situ Treatment** | 0 | 0 | 0 | 2 |
| **ENR (SA-6N GWTP Utilities)** | 0 | 0 | 0 | 0 |
| **Siemens** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 0 | 2 |
| **TOTAL** | **55** | **57** | **57** | **64** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Collected July PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed S-3 Injection/Mass Removal Event #15 in well 088-IW-01.
- On July 29, met with JCIA and JCRA representatives to discuss demolition and relocation schedule. Conducted pre- bid meetings on July 8th and July 15th for the JCIA structures demolition project.
- On, July 2nd and July 3rd the excavation contractor encountered two additional unknown underground storage tanks while excavating in Cells 114 to 111. The site designated LSRP was notified and observed removal of the tanks and associated sampling. The LSRP is responsible for registering and closing the UST in accordance with NJDEP requirements as part of the non-chromium remedial action being conducted concurrently.

- Initiated In-Situ treatment activities on SA6 South. Site 163. A total of 10 temporary well points were installed during the reporting period.

## C. SA-6 N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on June 11, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 07/06/14 | 07/13/14 | 07/20/14 | 07/27/14 |
| Avg. Gallons Treated & Discharged (per day) | 74,039 | 79,231 | 78,632 | 78,615 |
| Average Flow (gpm) for Operating Period | 50 | 55 | 55 | 57 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP InfluentTanks (gal.) | 10,541 | 12,321 | 11,570 | 15,509 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in cells 113A-103A, 115B – 106B.
- Continued storm-water management activities.
- Completed UST removal activities. A total of 3 UST were removed and staged on site for registration and disposal.
- Collected an additional soil bottom of excavation sample for hexavalent chromium analysis from the UST area (beneath the second UST). Laboratory data confirmed that the result is less than 20 mg/kg (2.1 mg/kg).
- Collected two additional sidewall soil samples for hexavalent chromium analysis from a visually suspect area along Cell 149. One of the samples was less than 20 mg/kg (4.7 mg/kg); however the second location was greater than 20 mg/kg (42.3 mg/kg) and resulted in minor additional material excavation up to 4 feet below grade. A subsequent sidewall sample was collected and data indicated that the less that 20 mg/kg was met (7.9 mg/kg).
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 0 | 0 | 0 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 0 | 0 | 0 |
| **Entact/ Montecalvo** | Tri-axle Dump | Bayshore Recycling | NA | Non Haz Petroleum Soil | 0 | 0 | 0 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 113A-103A, 115B – 106B |
| **Excavation Completed** | Cell Number(s) 114A-105A, 117B – 106B<br>Volume Excavated - Total for Reporting Period: 11,199 CY/ Total to Date: 88,945 CY |
| **Backfill in Progress** | Cell Number(s) 146B – 106B, 152A – 105A |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 07/06/14 | 07/13/14 | 07/20/14 | 07/27/14 |
| <20ppm re-use, CY | 0 | 0 | 1,373 | 675 |
| Weldon, Import-Tons Screenings | 3,337 | 2,771 | 3,790 | 5,915 |
| Tilcon, Import-Tons DGA | 0 | 0 | 306 | 932 |
| Tilcon, Import Tons – 1.5” Stone | 308 | 759 | 30 | 0 |
| Weldon, Imported Tons - QP | 814 | 1,646 | 223 | 1,125 |
| Celgene - Loads | 611 | 946 | 802 | 777 |
| Tilcon, Imported Tons – 2.5” Stone | 0 | 0 | 0 | 0 |

## E. SURCHARGE OPERATIONS *(see **Attachment 9**)*

- Area 1S: Surcharge subgrade placement continued though the month using soils with hexavalent chromium impacted soils.
- Area 2S: Surcharging continued from 1S into the western portion of 2 S. Settlement Platforms have been placed along the perimeter pools.
- Area 3S: Instrumentation installation is 100% complete as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles in area. No Surcharge initiated.
- Area 1N: Surcharge material placement was completed to the design grade in the southeast quadrant the first week in July. Additional surcharge was placed on the north slope near HS-4 to bring that area to the surcharge design grade the during the week ending August 1st. Results

indicate that surcharge is now complete in Area 1N and fill materials are ready for removal by contractor. Details to be provided in the next Surcharge Monitoring Report.

- Area 2N: Instrumentation Installation 100 % complete. Initial surcharge instrument data to be submitted under separate cover.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- One single sheet driven on the hydraulic barrier wall at Sta 13+30 for the Closure Piece 2, SA-6S. This completes he hydraulic barrier wall installation on SA-6S.

## PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## G. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Finalize bidding process for the Above-grade Demolition of the four designated JCIA Structures. Bid opening scheduled for August 13, 2014.
- Complete In-Situ treatment activities at Site 163.
- Continue placement of surcharge materials in SA-6S Area 1S.

- Begin placement of surcharge materials in SA-6N Area 2N.
- Continue installation of the contingent groundwater system on SA-6S.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 103 to 70.
- Continue stockpiling of presumed <20 mg/kg for additional sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Continue dewatering and storm-water management activities.
- Continue surcharge monitoring instrument installation activities on SA-6N and SA-6S.
- Conduct S-3 Injection/Mass Removal Event No.16 in well 088-IW-03.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.

**ATTACHMENTS:**


1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-4)
   - SA-6 South Deep Well Data (DW-5)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. Groundwater Quality Data Surcharge Monitoring Update *(provided on a quarterly basis - not available as of this report date)*
   - Summary of Groundwater Quality Data from GWET Wells
   - Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells
9. Surcharge Monitoring Update
   - Instrumentation Location Plan 1S
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Deflection Along Open Excavation
    - Sheet Pile Repair Log
11. Weekly SWPPP Reports

12. GWTP Update
    - 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (June 2014)
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (June 2014)
13. SA-6 North & South Design Change Tracking Log

## Attachment 1:  Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Wed 7/30/14

Task Milestone Summary Critical


## Attachment 2: Site Photographs




**Site Photograph 1:** Clean backfill is compacted.




**Site Photograph 2:** Clean backfill is spread.




**Site Photograph 3:** Clean concrete is reused as backfill.




**Site Photograph 4:** Excavation progress along Droyers Cove.




**Site Photograph 5:** Placement of separation fabric.




**Site Photograph 6:** Placing backfill around instrumentation station.





**Site Photograph 7:** Surcharge material is placed around well MW-1 BR.


## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points)
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of August 1, 2014

July 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill






LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM O EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE
- LIMIT OF EXCAVATION AREA
- TOE OF CHLOROBENZENE AREA

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 07-03-14 TO 07-24-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.
Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -0.6 | 134-SB-019 | 114A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.3 | 601878.4 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.7 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| | | | | | | | |
| | | | | | | | |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-114-3 | 114B | 7/17/2014 | -2.0 | UST Area |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | UST Area |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-112-3 | 112B | 7/17/2014 | -1.8 | UST Area |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.7 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Target Elevation Reached |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685094.6 | 601890.3 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 685081.0 | 601928.0 | -0.1 | 134-SB-021 | 109A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 685080.6 | 601935.9 | 3.0 | 134-SB-092 | 108A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Target Elevation Reached |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | |
|---|---|
| Sidewall Target Coordinates | As-built Elevations |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 7/28/14

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | | | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation - Stratum O | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavartion elevation | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (S0) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (S0) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 25 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 6.4 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.1719 | 601631.644 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 0 | RF-34 | | 685278.423 | 601673.304 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 6.4 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 6.4 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 6.4 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-4)
- SA-6 South Deep Well Data (DW-5)

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 06/04/14 | 2 | 24 | 14, WPS-2 | 35 | 0 | 8,325 | 8,325 | 2,040,901 | 5.8 | |
| 06/05/14 | 2 | 24 | 14, WPS-2 | 35 | 8,325 | 13,042 | 4,717 | 2,045,618 | 3.3 | |
| 06/06/14 | 2 | 24 | 14, WPS-2 | 35 | 13,042 | 22,720 | 9,678 | 2,055,296 | 6.7 | |
| 06/09/14 | 2 | 72 | 14, WPS-2 | 35 | 22,720 | 41,093 | 18,373 | 2,073,669 | 4.3 | |
| 06/10/14 | 2 | 24 | 14, WPS-2 | 35 | 41,093 | 54,801 | 13,708 | 2,087,377 | 9.5 | |
| 06/11/14 | 2 | 24 | 14, WPS-2 | 35 | 54,801 | 61,975 | 7,174 | 2,094,551 | 5.0 | |
| 06/12/14 | 2 | 24 | 14, WPS-2 | 35 | 61,975 | 69,411 | 7,436 | 2,101,987 | 5.2 | |
| 06/13/14 | 2 | 24 | 14, WPS-2 | 35 | 69,411 | 75,445 | 6,034 | 2,108,021 | 4.2 | |
| 06/16/14 | 2 | 72 | 14, WPS-2 | 35 | 75,445 | 95,783 | 20,338 | 2,128,359 | 4.7 | |
| 06/17/14 | 2 | 24 | 14, WPS-2 | 35 | 95,783 | 102,708 | 6,925 | 2,135,284 | 4.8 | |
| 06/18/14 | 2 | 24 | 13,14, WPS-2 | 48 | 102,708 | 117,105 | 14,397 | 2,149,681 | 10.0 | |
| 06/19/14 | 2 | 24 | 13,14, WPS-2 | 48 | 117,105 | 131,389 | 14,284 | 2,163,965 | 9.9 | |
| 06/20/14 | 2 | 24 | 13,14, WPS-2 | 48 | 131,389 | 142,678 | 11,289 | 2,175,254 | 7.8 | |
| 06/23/14 | 2 | 72 | 13,14, WPS-2 | 48 | 142,678 | 172,492 | 29,814 | 2,205,068 | 6.9 | |
| 06/24/14 | 2 | 24 | 13,14, WPS-2 | 48 | 172,492 | 182,523 | 10,031 | 2,215,099 | 7.0 | |
| 06/25/14 | 2 | 24 | 13,14, WPS-2 | 48 | 182,523 | 191,134 | 8,611 | 2,223,710 | 6.0 | |
| 06/26/14 | 2 | 24 | 13,14, WPS-2 | 48 | 191,134 | 200,723 | 9,589 | 2,233,299 | 6.7 | |
| 06/27/14 | 2 | 24 | 13,14, WPS-2 | 48 | 200,723 | 212,575 | 11,852 | 2,245,151 | 8.2 | |
| 06/30/14 | 2 | 72 | 13,14, WPS-2 | 48 | 212,575 | 247,628 | 35,053 | 2,280,204 | 8.1 | |
| 07/01/14 | 2 | 24 | 13,14, WPS-2 | 48 | 247,628 | 259,680 | 12,052 | 2,292,256 | 8.4 | |
| 07/02/14 | 2 | 24 | 13,14, WPS-2 | 48 | 259,680 | 266,319 | 6,639 | 2,298,895 | 4.6 | |
| 03/13/00 | 2 | 24 | 13,14, WPS-2 | 48 | 266,319 | 270,103 | 3,784 | 2,302,679 | 2.6 | |
| 07/07/14 | 2 | 86 | 13,14, WPS-2 | 48 | 270,103 | 285,239 | 15,136 | 2,317,815 | 2.9 | |
| 07/08/14 | 2 | 24 | 13,14, WPS-2 | 45 | 285,239 | 288,158 | 2,919 | 2,320,734 | 2.0 | |
| 07/09/14 | 2 | 24 | 13,14, WPS-2 | 45 | 288,158 | 289,792 | 1,634 | 2,322,368 | 1.1 | |
| 07/10/14 | 2 | 24 | 13, WPS-2 | 27 | 289,792 | 292,235 | 2,443 | 2,324,811 | 1.7 | |
| 07/11/14 | 2 | 24 | 13, WPS-2 | 27 | 292,235 | 295,728 | 3,493 | 2,328,304 | 2.4 | |
| 07/14/14 | 2 | 72 | 13, WPS-2 | 27 | 295,728 | 306,209 | 10,481 | 2,338,785 | 2.4 | |
| 07/15/14 | 2 | 24 | 13, WPS-2 | 27 | 306,209 | 309,704 | 3,495 | 2,342,280 | 2.4 | |
| 07/16/14 | 2 | 24 | 13, WPS-2 | 27 | 309,704 | 311,299 | 1,595 | 2,343,875 | 1.1 | |
| 07/17/14 | 2 | 24 | 13, WPS-2 | 27 | 311,299 | 312,848 | 1,549 | 2,345,424 | 1.1 | |
| 07/18/14 | 2 | 24 | 13, WPS-2 | 27 | 312,848 | 313,958 | 1,110 | 2,346,534 | 0.8 | |
| 07/21/14 | 2 | 72 | 13, WPS-2 | 27 | 313,958 | 317,809 | 3,851 | 2,350,385 | 0.9 | |
| 07/22/14 | 2 | 24 | 13, WPS-2 | 27 | 317,809 | 318,844 | 1,035 | 2,351,420 | 0.7 | |
| 07/23/14 | 2 | 24 | 13, WPS-2 | 27 | 318,844 | 319,048 | 204 | 2,351,624 | 0.1 | |
| 07/24/14 | 2 | 24 | 13, WPS-2 | 22 | 319,048 | 319,062 | 14 | 2,351,638 | 0.0 | |
| 07/25/14 | 2 | 24 | 13, WPS-2 | 22 | N/A | N/A | 450 | 2,352,088 | 0.3 | Flowmeter Blockage - Tank Measured |
| 07/28/14 | 2 | 72 | 13, WPS-2 | 22 | N/A | N/A | 1,650 | 2,353,738 | 0.4 | Flowmeter Blockage - Tank Measured |
| 07/29/14 | 2 | 24 | 13, WPS-2 | 22 | N/A | N/A | 550 | 2,354,288 | 0.4 | Flowmeter Blockage - Tank Measured |
| 07/30/14 | 2 | 24 | 13, WPS-3 | 22 | N/A | N/A | 500 | 2,354,788 | 0.3 | System Disabled or Relocation |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-4)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 07/16/14 | 24 | 0 | 4,141 | 4,141 | 4,141 | 2.9 | |
| 07/17/14 | 24 | 4,141 | 8,184 | 4,043 | 8,184 | 2.8 | |
| 07/18/14 | 24 | 8,184 | 12,120 | 3,936 | 12,120 | 2.7 | |
| 07/21/14 | 72 | 0 | 16,253 | 16,253 | 28,373 | 3.8 | Flowmeter Reset |
| 07/22/14 | 24 | 16,253 | 19,898 | 3,645 | 32,018 | 2.5 | |
| 07/23/14 | 24 | N/A | N/A | 4,000 | 36,018 | 2.8 | Flowmeter Blockage, Tank Measured |
| 07/24/14 | 24 | N/A | N/A | 4,200 | 40,218 | 2.9 | Pump Taken Offline for Excavation |

Notes: DW-4 was activated on July 16, 2014.

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-5)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 05/30/14 | 24 | 4,322 | 8,634 | 4,312 | 148,321 | 3.0 | |
| 06/02/14 | 72 | 8,634 | 20,324 | 11,690 | 160,011 | 2.7 | |
| 06/03/14 | 24 | 20,324 | 33,537 | 13,213 | 173,224 | 9.2 | |
| 06/04/14 | 24 | 33,537 | 61,661 | 28,124 | 201,348 | 19.5 | |
| 06/05/14 | 24 | 61,661 | 83,362 | 21,701 | 223,049 | 15.1 | |
| 06/06/14 | 24 | 83,362 | 90,354 | 6,992 | 230,041 | 4.9 | |
| 06/09/14 | 72 | 90,354 | 116,742 | 26,388 | 256,429 | 6.1 | |
| 06/10/14 | 24 | 0 | 11,717 | 11,717 | 268,146 | 8.1 | Flowmeter Reset |
| 06/11/14 | 24 | N/A | N/A | 10,500 | 278,646 | 7.3 | Flowmeter Blockage (Tank Measured) |
| 06/12/14 | 24 | N/A | N/A | 11,200 | 289,846 | 7.8 | Flowmeter Blockage (Tank Measured) |
| 06/13/14 | 24 | N/A | N/A | 11,100 | 300,946 | 7.7 | Flowmeter Blockage (Tank Measured) |
| 06/16/14 | 72 | N/A | N/A | 34,500 | 335,446 | 8.0 | Flowmeter Blockage (Tank Measured) |
| 06/17/14 | 24 | 0 | 12,405 | 12,405 | 347,851 | 8.6 | Flowmeter Reset |
| 06/18/14 | 24 | 12,405 | 20,193 | 7,788 | 355,639 | 5.4 | |
| 06/19/14 | 24 | N/A | N/A | 9,200 | 364,839 | 6.4 | Flowmeter Blockage (Tank Measured) |
| 06/20/14 | 24 | 20,193 | 23,966 | 3,773 | 368,612 | 2.6 | |
| 06/23/14 | 72 | 23,966 | 30,285 | 6,319 | 374,931 | 1.5 | |
| 06/24/14 | 24 | N/A | N/A | 2,500 | 377,431 | 1.7 | Flowmeter Blockage (Tank Measured) |
| 06/25/14 | 24 | N/A | N/A | 5,000 | 382,431 | 3.5 | Flowmeter Blockage (Tank Measured) |
| 06/26/14 | 24 | N/A | N/A | 5,100 | 387,531 | 3.5 | Flowmeter Blockage (Tank Measured) |
| 06/27/14 | 24 | 0 | 6,090 | 6,090 | 393,621 | 4.2 | Flowmeter Reset |
| 06/30/14 | 72 | 6,090 | 24,309 | 18,219 | 411,840 | 4.2 | |
| 07/01/14 | 24 | 24,309 | 30,453 | 6,144 | 417,984 | 4.3 | |
| 07/02/14 | 24 | 30,453 | 40,122 | 9,669 | 427,653 | 6.7 | |
| 07/03/14 | 24 | 40,122 | 48,137 | 8,015 | 435,668 | 5.6 | |
| 07/07/14 | 86 | 48,137 | 80,200 | 32,063 | 467,731 | 6.2 | |
| 07/08/14 | 24 | 80,200 | 98,037 | 17,837 | 485,568 | 12.4 | |
| 07/09/14 | 24 | 98,037 | 98,557 | 520 | 486,088 | 0.4 | |
| 07/10/14 | 24 | 98,557 | 99,431 | 874 | 486,962 | 0.6 | Well Taken Offline |

Notes: Previous information is trunketed. Only last month and current month information is provided.

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 06/02/14 | 6:30 | 12,906.92 | 13,081.94 | 175,020 | 13,081,490 | |
| 06/04/14 | 7:00 | 13,081.94 | 13,233.54 | 151,600 | 13,233,090 | PVSC Compliance Sample Collected |
| 06/05/14 | 8:30 | 13,233.54 | 13,391.28 | 157,740 | 13,390,830 | |
| 06/06/14 | 8:00 | 13,391.28 | 13,444.66 | 53,380 | 13,444,210 | |
| 06/08/14 | 5:00 | 13,444.66 | 13,498.28 | 53,620 | 13,497,830 | |
| 06/09/14 | 6:15 | 13,498.28 | 13,667.07 | 168,790 | 13,666,620 | |
| 06/10/14 | 5:40 | 13,667.07 | 13,839.23 | 172,160 | 13,838,780 | |
| 06/11/14 | 4:50 | 13,839.23 | 13,952.75 | 113,520 | 13,952,300 | |
| 06/12/14 | 6:50 | 13,952.75 | 14,138.23 | 185,480 | 14,137,780 | |
| 06/13/14 | 13:15 | 14,138.23 | 14,296.51 | 158,280 | 14,296,060 | |
| 06/14/14 | 7:50 | 14,296.51 | 14,447.78 | 151,270 | 14,447,330 | |
| 06/16/14 | 8:20 | 14,447.78 | 14,602.88 | 155,100 | 14,602,430 | |
| 06/17/14 | 7:55 | 14,602.88 | 14,717.27 | 114,390 | 14,716,820 | |
| 06/18/14 | 8:00 | 14,717.27 | 14,832.09 | 114,820 | 14,831,640 | |
| 06/19/14 | 7:20 | 14,832.09 | 14,937.60 | 105,510 | 14,937,150 | |
| 06/20/14 | 8:20 | 14,937.60 | 15,083.23 | 145,630 | 15,082,780 | |
| 06/21/14 | 3:00 | 15,083.23 | 15,127.76 | 44,530 | 15,127,310 | |
| 06/23/14 | 7:50 | 15,127.76 | 15,294.76 | 167,000 | 15,294,310 | |
| 06/24/14 | 8:30 | 15,294.76 | 15,348.15 | 53,390 | 15,347,700 | |
| 06/25/14 | 8:15 | 15,348.15 | 15,452.33 | 104,180 | 15,451,880 | |
| 06/26/14 | 7:50 | 15,452.33 | 15,551.63 | 99,300 | 15,551,180 | |
| 06/27/14 | 7:45 | 15,551.63 | 15,616.53 | 64,900 | 15,616,080 | |
| 06/30/14 | 8:00 | 15,616.53 | 15,754.00 | 137,470 | 15,753,550 | |
| 07/02/14 | 8:30 | 15,754.00 | 15,879.17 | 125,170 | 15,878,720 | PVSC Compliance Sample Collected |
| 07/03/14 | 5:15 | 15,879.17 | 15,995.15 | 115,980 | 15,994,700 | |
| 07/04/14 | 7:15 | 15,995.15 | 16,174.96 | 179,810 | 16,174,510 | |
| 07/05/14 | 7:00 | 16,174.96 | 16,354.58 | 179,620 | 16,354,130 | |
| 07/06/14 | 5:55 | 16,354.58 | 16,443.35 | 88,770 | 16,442,900 | |
| 07/07/14 | 9:05 | 16,443.35 | 16,582.28 | 138,930 | 16,581,830 | |
| 07/08/14 | 8:05 | 16,582.28 | 16,719.12 | 136,840 | 16,718,670 | |
| 07/09/14 | 7:30 | 16,719.12 | 16,813.21 | 94,090 | 16,812,760 | |
| 07/10/14 | 7:15 | 16,813.21 | 16,861.07 | 47,860 | 16,860,620 | |
| 07/11/14 | 6:00 | 16,861.07 | 16,927.80 | 66,730 | 16,927,350 | |
| 07/14/14 | 7:35 | 17,039.50 | 17,039.50 | 111,700 | 17,039,050 | |
| 07/15/14 | 8:10 | 17,151.47 | 17,151.47 | 111,970 | 17,151,020 | |
| 07/16/14 | 7:30 | 17,151.47 | 17,277.51 | 126,040 | 17,277,060 | |
| 07/17/14 | 5:15 | 17,277.51 | 17,369.50 | 91,990 | 17,369,050 | |
| 07/18/14 | 7:45 | 17,369.50 | 17,470.26 | 100,760 | 17,469,810 | |
| 07/21/14 | 8:30 | 17,470.26 | 17,603.88 | 133,620 | 17,603,430 | |
| 07/22/14 | 8:00 | 17,603.88 | 17,697.76 | 93,880 | 17,697,310 | |
| 07/23/14 | 7:30 | 17,697.76 | 17,756.61 | 58,850 | 17,756,160 | |
| 07/24/14 | 7:30 | 17,756.61 | 17,794.18 | 37,570 | 17,793,730 | |
| 07/25/14 | 7:00 | 17,794.18 | 17,849.88 | 55,700 | 17,849,430 | |
| 07/28/14 | 8:00 | 17,849.88 | 17,964.12 | 114,240 | 17,963,670 | |
| 07/29/14 | 8:00 | 17,964.12 | 18,017.49 | 53,370 | 18,017,040 | |
| 07/30/14 | 7:50 | 18,017.49 | 18,060.14 | 42,650 | 18,059,690 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 139-142B, 131-132A | <20 | 124-128-20-a | 1000 | 124-128-20-a1 | 6/3/2014 | 10:45 | 32.4 | | Yes | |
| | | | | 124-128-20-a2 | 6/3/2014 | 10:50 | 38.4 | | Yes | |
| | | | | 124-128-20-a3 | 6/3/2014 | 10:55 | 17.0 | Yes | | |
| | | | | 124-128-20-a4 | 6/3/2014 | 11:00 | 45.1 | | Yes | |
| 124-126 | <20 | 124-126-20-a, b | 1450 | 124-126-20-a1 | 6/13/2014 | 11:00 | 41.1 | | Yes | |
| | | | | 124-126-20-a2 | 6/13/2014 | 11:05 | 13.9 | Yes | | |
| | | | | 124-126-20-a3 | 6/13/2014 | 11:10 | 15.0 | Yes | | |
| | | | | 124-126-20-a4 | 6/13/2014 | 11:15 | 2.9 | Yes | | |
| | | | | 124-126-20-b1 | 6/13/2014 | 11:20 | 12.9 | Yes | | |
| | | | | 124-126-20-b2 | 6/13/2014 | 11:25 | 8.6 | Yes | | |
| | | | | 124-126-20-b3 | 6/13/2014 | 11:30 | 59.4 | | Yes | |
| | | | | 124-126-20-b4 | 6/13/2014 | 11:35 | 8.0 | Yes | | |
| 119-124 | <20 | 124-124-20-a, b | 2000 | 124-124-20-a1 | 6/25/2014 | 6:40 | 11.2 | Yes | | |
| | | | | 124-124-20-a2 | 6/25/2014 | 6:45 | 14.6 | Yes | | |
| | | | | 124-124-20-a3 | 6/25/2014 | 6:50 | 12.2 | Yes | | |
| | | | | 124-124-20-a4 | 6/25/2014 | 6:55 | 8.0 | Yes | | |
| | | | | 124-124-20-b1 | 6/25/2014 | 7:00 | 19.4 | Yes | | |
| | | | | 124-124-20-b2 | 6/25/2014 | 7:05 | 4.8 | Yes | | |
| | | | | 124-124-20-b3 | 6/25/2014 | 7:10 | 2.1 | Yes | | |
| | | | | 124-124-20-b4 | 6/25/2014 | 7:15 | 10.5 | Yes | | |
| 119-125 | >1000 | 124-125-1000-a | 550 | 124-125-1000-a1 | 6/25/2014 | 6:15 | 42.1 | | Yes | |
| | | | | 124-125-1000-a2 | 6/25/2014 | 6:20 | 652.0 | | Yes | |
| | | | | 124-125-1000-a3 | 6/25/2014 | 6:25 | 346.0 | | Yes | |
| | | | | 124-125-1000-a4 | 6/25/2014 | 6:30 | 400.0 | | Yes | |
| 115-119 | <20 | 124-119-20-a | 1000 | 124-119-20-a1 | 6/27/2014 | 13:00 | 9.6 | Yes | | |
| | | | | 124-119-20-a2 | 6/27/2014 | 13:05 | 7.8 | Yes | | |
| | | | | 124-119-20-a3 | 6/27/2014 | 13:10 | 6.0 | Yes | | |
| | | | | 124-119-20-a4 | 6/27/2014 | 13:15 | 28.8 | | Yes | |
| 110-118 | <20 | 124-118-20-a | 1000 | 124-118-20-a1 | 7/9/2014 | 13:00 | 20.3 | | Yes | |
| | | | | 124-118-20-a2 | 7/9/2014 | 13:05 | 19.7 | Yes | | |
| | | | | 124-118-20-a3 | 7/9/2014 | 13:10 | 37.1 | | Yes | |
| | | | | 124-118-20-a4 | 7/9/2014 | 13:15 | 61.1 | | Yes | |

**Notes:**
*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

## Attachment 7:  Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
05-07-2014


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


May 07, 2014 at 4:13pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | South | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-1 | FS-3 | FS-4 | FS-5 |
| Date | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | 7.5 | 7.9 | 7.7 | 5.9 |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | 7.7 | 8.1 | 7.9 | 7.2 |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | 7.6 | 7.8 | 7.6 | 8.0 |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | 7.4 | 8.0 | 8.0 | 8.6 |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | 7.4 | 8.4 | 8.4 | 9.4 |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | 6.1 | 7.9 | 7.6 | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | 4.3 | 7.5 | 7.8 | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | 3.3 | 5.3 | 9.0 | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO, W5-SO, South FS-5


## Attachment 8: Quality and Level Data in GWET Wells


(not available as of this report date - provided on a quarterly basis)

- Summary of Groundwater Quality Data from GWET Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells

## Attachment 9: Surcharge Monitoring Update

- Instrumentation Location Plan 1S




SECTION A–A

Installed Instrumentation Locations

Instrumentation Locations Not Installed

| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–1 | 685276.02 | 601927.05 |
| FS–2 | 685323.86 | 601748.51 |
| HS–1 | 685597.02 | 601567.16 |
| HS–2 | 685511.42 | 601690.72 |
| HS–3 | 685421.98 | 601800.88 |
| HS–4 | 685313.18 | 601947.19 |
| HS–5 | 685480.23 | 601623.90 |
| HS–6 | 685518.78 | 601480.25 |
| HS–7 | 685413.06 | 601624.11 |
| HS–8 | 685204.27 | 601911.97 |
| VI–1 | 685624.44 | 601515.06 |
| VI–2 | 685578.58 | 601462.08 |
| VRC–1 | 685505.92 | 601505.39 |
| VRC–2 | 685434.27 | 601785.68 |
| VRC–3 | 685262.85 | 601914.43 |
| SP–1 | 685567.71 | 601633.29 |
| SP–2 | 685410.62 | 601852.31 |
| SP–3 | 685276.93 | 602033.96 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 07/19/13
Checked/Date: AE 07/19/13

Honeywell
101 COLUMBIA RD., BOX 2106
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY


amec

INSTRUMENTATION LOCATION PLAN 1S


Figure F-1

## Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Monitoring Locations
- Sheet Pile Repair Log




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 5+00 | 12+60 | -22 | AZ 19-700 |
| STRUCTURAL | 12+60 | 17+80 | -30 | AZ 19-700 |
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |




NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GH04932400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | TDD | RJR | TDD |

ISSUED FOR CONSTRUCTION

| BY | APVD |
|---|---|
| TDD | SHM |

SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

HYDRAULIC BARRIER
PLAN & PROFILE


amec
Environment & Infrastructure, Inc
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-202 |
| SHEET | 54 OF 66 |

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.






NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 03-20-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 17P1-8

Entact ID:

Date Exposed: 6/27/14

Describe Damage:
(7) scrapes by Cat 349E excavator bucket - 1/2x4", 1/2"Ø, 1/2x8", 1"Ø, 1x3", 1/2x5", 1/4"x2" - (Cell 114)

Damage Location (ft below top of sheet, inboard side outboard side):
9-15' outboard

Date Repaired: 7/2/14

Inspected by: Brian Shea

Describe Repair: Pressure washed, wire brushed, epoxy applied w/ 4" Paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/2/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 17P1-9

Entact ID:

Date Exposed: 6/27/14

Describe Damage:
(28) Scrapes by cat 349E excavator bucket - 1"x14", 1/2x10", 1"x24", 2-1"Ø, 1/2x10", 3"Ø, 2"x6", 1/4x1", 5x14", 1"x6", 1x8", 1x3", 15-1"Ø - Cell 114

Damage Location (ft below top of sheet, inboard side outboard side):
9-16' outboard

Date Repaired: 7/2/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, epoxy applied w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/2/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 17P1-10

Entact ID:

Date Exposed: 6/27/14

Describe Damage:
(2) scrapes by the Cat 349E excavator bucket - 2"Ø, 2x4" (Cell 114)

Damage Location (ft below top of sheet, inboard side outboard side):
11-13' outboard

Date Repaired: 7/2/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/2/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 17P1-11

Entact ID:

Date Exposed: 6/27/14

Describe Damage:
(1) scrape by the Cat 349E excavator bucket - Cell 113 - 84" scrape

Note: Sheet is covered w/ hardened grout from elv. 10.0' to the BOE.

Damage Location (ft below top of sheet, inboard side outboard side):
9'-16' outboard

Date Repaired: 7/2/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/2/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-1

Entact ID:

Date Exposed: 6/27/14

Describe Damage: (4) scrapes by Cat 349E excavator bucket - 1x30", 1/2x6", 2"Ø, 1/2x10" (Cell 113)

Note: Sheet is covered w/ hardened grout from elv. 8.0' to the BoE.

Damage Location (ft below top of sheet, inboard side outboard side): 10'-7' outboard

Date Repaired: 7/2/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/2/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-3

Entact ID:

Date Exposed: 7/2/14

Describe Damage: (3) Scrapes by the Cat 349E excavator - 1x48", 1"Ø, 1x6". Cell 113/112.

Note: Sheet is covered w/ hardened grout from elv. 5.0' - 0.0'.

Damage Location (ft below top of sheet, inboard side outboard side): 7'-15' outboard

Date Repaired: 7/7/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/7/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-4

Entact ID:

Date Exposed: 7/2/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 2"Ø, 1x3", 1"Ø, 1/2"Ø, 1x12", (2) 1/2x3", 2x4". Cell 112.

Note: Sheet is covered w/ hardened grout from elv. 8.0' to elv. 0.0 (BoE).

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 7/7/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/7/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-5

Entact ID:

Date Exposed: 7/2/14

Describe Damage: (6) scrapes by the Cat 349E Excavator bucket - 3"Ø, 1"x18", 1"Ø, 1/2"x10", 1"Ø, 1x4". Cell 112.

Note: Sheet is covered w/ hardened grout from elv. 8.0 to the BoE.

Damage Location (ft below top of sheet, inboard side outboard side): 10-13' outboard

Date Repaired: 7/7/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/9/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 17P2-6

Entact ID:

Date Exposed: 7/2/14

Describe Damage: (10) scrapes by the cat 349E excavator bucket - (4) 1"Ø, 1x6", (3) 1/2"Ø, 1/2x14", 2"Ø. Cell 112. Note: Sheet covered by hardened grout from elv. 6.0' to the BOE.

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 7/9/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure AMEC Signature: BShea

Date: 7/9/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 17P2-7

Entact ID:

Date Exposed: 7/7/14

Describe Damage: (12) scrapes by the Cat 349E excavator bucket - (6) 1/2"Ø, 1/2"x12", 1x3", (2) 1"Ø, 1x2", 4"Ø - Cell 111. Note: Sheet is covered by hardened grout from elv. 5.0' to 1.0'.

Damage Location (ft below top of sheet, inboard side outboard side): 11-15' outboard

Date Repaired: 7/9/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/9/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 17P2-8

Entact ID:

Date Exposed: 7/7/14

Describe Damage: (9) scrapes by the cat 349E excavator bucket - 1/2"x6", 1"Ø, 2"Ø, 1/2x4", 1"x3", (4) 1/2"Ø, Cell 111. Note: Sheet is covered by hardened grout from elv. 5.0' to 1.0'.

Damage Location (ft below top of sheet, inboard side outboard side): 11-15' outboard

Date Repaired: 7/9/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush.

Repair Log Closure AMEC Signature: BShea

Date: 7/9/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 17P2-9

Entact ID:

Date Exposed: 7/7/14

Describe Damage: (8) scrapes by Cat 349E excavator bucket - 1"Ø, 1/2x24", 1"Ø, 1x2", 1x4", 1/2x18", 2x4", 1/2x8". Cell 111. Note: Sheet is covered w/ hardened grout from elv. 5.0' to 1.0'.

Damage Location (ft below top of sheet, inboard side outboard side): 8-14' outboard

Date Repaired: 7/9/14

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure AMEC Signature: BShea

Date: 7/9/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-10
Entact ID:
Date Exposed: 7/9/14
Describe Damage: (4) Scrapes by the Cat 349E excavator bucket- 1"ø, 2×6", 1/2×12", 2"ø- cell 110

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 7/10/14
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: B.Shea
Date: 7/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-11
Entact ID:
Date Exposed: 7/9/14
Describe Damage: (20) Scrapes by the Cat 349E excavator bucket- 1×18", 1/4×2", 1×6", 1/2"ø, 1/2×36", 1/2×8", 1/4×3", 1"ø, 2×10", 3×12", 4×8", 3×12", 1"ø, (4) 1"ø, 1/2×3", 2"ø, 1/4×1"- Cell 110

Damage Location (ft below top of sheet, inboard side outboard side): 9-13' outboard

Date Repaired: 7/10/14
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: B.Shea
Date: 7/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-12
Entact ID:
Date Exposed: 7/9/14
Describe Damage: (11) Scrapes by the Cat 349E excavator bucket- 1/4"ø, 1"ø, 3×6", 3×8", 1×4", 2×10", 1/2×24", 1/2×3", 1"ø, 2×8", 1/2×10"- cell 110

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 7/10/14
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: B.Shea
Date: 7/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-13
Entact ID:
Date Exposed: 7/9/14
Describe Damage: (15) scrapes by the Cat 349E excavator bucket- 1"ø, 1×6", 1×3", 1/2"ø, 1×5", 8"×18", 2×6", 1"×18", 1/2"ø, 1"ø, 1/2×3", 2"ø, 1/2"ø, 2×36", 3"ø- Cell 110/109.

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 7/10/14
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush
Repair Log Closure: AMEC Signature: B.Shea
Date: 7/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-14

Entact ID:

Date Exposed: 7/9/14

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - (3) 1"ø, 1x2", 1/2"ø, Cell 109

Damage Location (ft below top of sheet, inboard side outboard side): 11-15' outboard

Date Repaired: 7/10/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 17P2-15

Entact ID:

Date Exposed: 7/9/14

Describe Damage: (14) scrapes by the Cat 349E excavator bucket - 1/2x4, 1/2S, 1"ø, 1/2x2", (4) 1/2"ø, 3x24", 1x12", 2x18", 1/4x3", 2x6", 1"ø. cell 109

Damage Location (ft below top of sheet, inboard side outboard side): 5-12' outboard

Date Repaired: 7/10/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4' paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 18P-1

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1"x6", 1"ø, 1x8", 2"ø, 4"ø. Cell 109/108

Note: Sheet is covered w/ hardened epoxy from Elv 6.0' to 1.5'

Damage Location (ft below top of sheet, inboard side outboard side): 6'-12' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 18P-2

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (12) scrapes by the Cat 349E excavator - 1/2x4", 1"ø, 2x4", 3"ø, 1x3", 1"ø, 3"ø, 1x4", 1/2x6", 1"ø, 1/2x3", 2x10", Cell 108

N

Damage Location (ft below top of sheet, inboard side outboard side): 6-12' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4' paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-3

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 1/2x12", 2"ø, 1"x6", 2x8", 1/2x6", 3x10", 1x14", 1"x18". Cell 108

Damage Location (ft below top of sheet, inboard side outboard side): 6-12' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date:

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-4

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (7) scrapes by the Cat 349E excavator bucket - 1x6", 3"ø, 1/2x8", 1"ø, 1"ø, 1x3", 1/2x12". Cell 108

Damage Location (ft below top of sheet, inboard side outboard side): 8-17' outboard

Date Repaired: 7/18/18

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-5

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (11) scrapes by the Cat 349E excavator bucket - 1/2 x 24", 1x2", 2"ø, 1/2x4", 1"ø, 1"ø, 2x4", 1/2x 2, 1/2"ø, 1x5", 1"ø. Cell 108

Damage Location (ft below top of sheet, inboard side outboard side): 8-16' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-6

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1/2x18", 1"ø, 1x3", 1/2x6", 1x3" cell 107

Damage Location (ft below top of sheet, inboard side outboard side): 8-16' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 18P-7

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (4) Scrapes by the Cat 349E excavator bucket - 1"x6", 1"Ø, 1/2"Ø, 1/2x3", 1x3", Cell 107

Damage Location (ft below top of sheet, inboard side outboard side): 13-17' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 18P-8

Entact ID:

Date Exposed: 7/16/14

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1/2x24", 1x5", 2"Ø, 1"Ø, 1/2x12". Cells 107/106

Damage Location (ft below top of sheet, inboard side outboard side): 12-17' outboard

Date Repaired: 7/18/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/18/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 18P-9

Entact ID:

Date Exposed: 7/17/14

Describe Damage: (9) scrapes by the Cat 349E excavator bucket - 1/2x4", 3"Ø, 1/2x1", 1"Ø, 1/2x2", 1"Ø 1/2x12", 2"Ø, 1/2x18", Cell 106

Damage Location (ft below top of sheet, inboard side outboard side): 12-18' outboard

Date Repaired: 7/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 7/24/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG*

Sheet Number/DB ID: 18P-10

Entact ID:

Date Exposed: 7/17/14

Describe Damage: (16) scrapes by the cat 349E excavator bucket - (6) 1"Ø, 1/2x30", 1/2x6", 1x3", 2"Ø, 3x6", 1/2"Ø, 1/2"Ø, 1x8", 2x6", 2"Ø, Cell 106

Damage Location (ft below top of sheet, inboard side outboard side): 12-18' outboard

Date Repaired: 7/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/24/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-11

Entact ID:

Date Exposed: 7/17/14

Describe Damage: (11) scrapes by the Cat 349E excavator bucket - (5) 1/2"Ø, (3) 1"Ø, 2x10", 1/2x36", 1"x18". Cell 106/105

Damage Location (ft below top of sheet, inboard side outboard side): 13-18' outboard

Date Repaired: 7/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/24/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-12

Entact ID:

Date Exposed: 7/21/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 1/2x12", 2"Ø, 1/2x8", 1/2x30", 1x12", 2x5", 1/2x60", 3"Ø. Cell 105

Damage Location (ft below top of sheet, inboard side outboard side): 11-18' outboard

Date Repaired: 7/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/24/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-13

Entact ID:

Date Exposed: 7/21/14

Describe Damage: (6) scrapes by the Cat 349E excavator bucket- 1/2x4", 1"Ø, 1x5", 1x12", 2"Ø, 1/2"Ø. Cell 105. Note: sheet is covered by hardened grout from elv 8.0'-(2.5')

Damage Location (ft below top of sheet, inboard side outboard side): 14-17' outboard

Date Repaired: 7/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/24/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 18P-14

Entact ID:

Date Exposed: 7/21/14

Describe Damage: (7) scrapes by the Cat 349E excavator bucket - 1x8", (3) 1"Ø, 1/2x10", 1/2x24", 1/2x2", 1x4", 2"Ø. Cell 105. Note: Sheet is partially covered w/ hardened epoxy from elv. 1.0'-(4.0')

Damage Location (ft below top of sheet, inboard side outboard side): 14-18' outboard

Date Repaired: 7/24/14

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 7/24/14

* A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

## Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 3, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/03/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, July 03, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**PERMIT CLOSED**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The haul road to the west of Kellogg Street has several large potholes which accumulate stormwater and mud. |
| 2 | IA2Q4A1AL8 | Sediment has escaped from the north side of the N-1 surcharge pile onto the DPW roadway. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 07/03/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place stone in the potholes to the west of the Kellogg Street gate to prevent the tracking of mud onto Kellogg Street. | 7-7-14 RAD |
| 2 | Review/improve erosion control measures along the northern edge of the N-1 surcharge pile. | 7-8-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/08/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 10, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1,2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | | X | | 6 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/11/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, July 10, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The restricted area warning tape along the top of the temporary sheet pile alignment must be extended to the east in order to keep workers a minimum of 6 feet from unprotected sheet pile wall (fall hazard). |
| 2 | IA2Q4A1AL8 | Sediment must be removed from the asphalt surfaces in the areas of the SA-6 South western excavation which are not being excavated. |
| 3 | IA2Q4A1AL8 | Sediment along the toes of material stockpiles in eastern SA-6 South is accumulating against the SA-7 SCB wall and must be cast back to prevent overtopping of the SCB wall and migration onto the SA-7 site. |
| 4 | IA2Q4A1AL8 | Stone in the tracking pad at the truck exit gate is compacted and requires cleaning/reworking |
| 5 | IA2Q4A1AL8 | A sinkhole has developed along the north side of the ramp which is located at the eastern end of the N-1 surcharge stockpile. This sinkhole requires repairs. |
| 6 | IA2Q4A1AL8 | A section fo temporary fencing is open to the south of the JCDPW H-building. This opening should be closed off and the perimeter fencing in this area maintained. |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature **Date:** 07/11/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Extend the caution tape which runs to the south of the sheetpile alignemnt eastwards to the point where the sheetpile ends. | 7-16-14 RAD |
| 2 | Clean the asphalt surface with the longstick excavator/blade bucket. | 7-11-14 RAD |
| 3 | Remove material to assure that storm water runoff from the SA-6 South stockpiles does not run onto SA-7. | 7-11-14 RAD |
| 4 | Rework or replace the stone in the tracking pad. | 7-15-14 RAD |
| 5 | Cut out and repair the sinkhole area. Cordon off the area until the work is complete. | 7-15-14 RAD |
| 6 | Close and resecure the fencing panel. | 7-11-14 RAD |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/16/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 17, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 5 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/17/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, July 17, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The ramp between SA-6 South and SA-7 is muddy and has potholes. |
| 2 | IA2Q4A1AL8 | Stormwater has ponded on the eastern backfill in SA-6 South. |
| 3 | IA2Q4A1AL8 | Traffic barrels and orange fencing have blown down at the western edge of the excavation. |
| 4 | IA2Q4A1AL8 | The ramp between SA-6 North and SA-7 is muddy and has potholes. |
| 5 | IA2Q4A1AL8 | Erosion/sediment containment measures (hay bales, sediment dams) are damaged or missing along the northern side of the surcharge stockpile area on SA-7 |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 07/17/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install stone or otherwise maintain the roadway to prevent the tracking of sediment onto SA-7. | 7/21/14 RAD |
| 2 | Pump down the surface water and regrade to prevent ponding in the future. | 7/21/14 RAD |
| 3 | Re-establish the warning barrier around the drop-off into the excavation. | 7/18/14 RAD |
| 4 | Install stone or otherwise maintain the roadway to prevent the tracking of sediment onto SA-7 | 7/18/14 RAD |
| 5 | Re-stablish sediment controls along the northern edge of the Novartis/Celgene stockpile area. | 7/21/14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/21/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: July 24, 2014**

**Type of Inspection:** ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | | |
| Stockpile Tarping/Containment | | | | |
| Proper Chemical Storage | | | | |
| Containment Around Exclusion Zones | | | | |
| Water Truck Wet- Down Operation | | | | |
| Truck De-Con Operation | | | | |
| Flood Protection | | | | |
| Haul Road Maintenance | | | | |
| Perimeter Fencing/Windscreen | | | | |
| Storm Drain Protection | | | | |
| Ponded Storm Water | | | | |
| Housekeeping | | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 North & GWTP** | | | | |
| Stockpile Tarping/Containment | | | | |
| Proper Chemical Storage | | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2, 3 |
| Perimeter Fencing/Windscreen | | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | | | | |
| Housekeeping | | | | |
| **SA-7 & Novartis Stockpile** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4, 5 |
| River Discharge Weir | | | | |
| Swale Check Dams | | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | | |
| Stockpile Tarping/Containment | | | | |
| Proper Chemical Storage | | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | | | |
| Perimeter Fencing/Windscreen | | | | |
| Storm Drain Protection | | | | |
| Ponded Storm Water | | | | |
| Housekeeping | | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 7-24-14

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, July 24, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
PERMIT CLOSED

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The exclusion zone fencing along Kellogg Street requires repair |
| 2 | IA2Q4A1AL8 | Silt fence requires repair at the location indicated on the attached drawing |
| 3 | IA2Q4A1AL8 | Observed build up of stone and sediment adjacent to the SA7 Northern raceway on the east side of the GTWT access ramp. |
| 4 | EEPSQUO2YB | Observed a section of hay bails missing at the NW corner of the Celgene stockpile. |
| 5 | EEPSQUO2YB | Build up of sediment observed along the southern perimeter of the stockpile. |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: ~~Jersey City~~, New Jersey
SWAP Observer: Signature Date: 7/24/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair fencing as required | 7/28/14 RAD |
| 2 | Repair silt fence as required | 7/28/14 RAD |
| 3 | Clean up sediment and remove to opposite side of silt fence | 7/29/14 RAD |
| 4 | Replace and repair hay bails at Norhwest corner of the Celgene stockpile | 7/29/14 RAD |
| 5 | Remove sediment from inside of stockpile | 7/30/14 RAD |
| | | |
| | | |
| | | |

Construction Manager: Date: 07/30/14

## Attachment 12: GWTP Update

- 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (June 2014)
- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (June 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

July 10, 2014

New Jersey Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: June 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the June 2014 Surface Water Discharge Monitoring Report for Outfall 001A. Please note that there was no discharge this monitoring period.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Frank Schroyer - Parsons

New Jersey Department of Environmental Protection
Division of Water Quality

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 6 | 1 | 2014 | To | 6 | 30 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☒ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J Morris, Remediation Director — —

**NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **GRADE AND REGISTRY NUMBER (IF APPLICABLE)**

John J. Morris HF — 7/9/2014 — 973.455.4003

**SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **DATE** | **AREA CODE/PHONE NUMBER**

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J Morris, Remediation Director — John J Morris HF — 7/9/2014 — 973.455.4003

**NAME AND TITLE** | **SIGNATURE** | **DATE** | **AREA CODE/PHONE NUMBER**

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 6/1/2014 TO 6/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | | | GPD | ****** | ****** | ****** | ****** | | | |
| | PERMIT REQUIREMENT | REPORT 01MOAV | REPORT 01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | | SU | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0 01MOMN | ****** | 9.0 01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 50 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10 01MOAV | 15 01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 20 01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 6/1/2014 TO 6/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 4/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 6/1/2014 TO 6/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50<br>01MOAV | 100<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | REPORT<br>01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 0.025<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 8.8<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 46<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 54<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 4/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 6/1/2014 TO 6/30/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | | | | | | | | | | |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 4/1/2014*

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

July 10, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the June 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 6 | 01 | 14 | 6 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 79,108 | 85,552 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 2.10 | 2.27 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.0881 | 0.0881 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

## PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris HG

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

7/8/2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 6 | 01 | 14 | 6 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,373,230 | GALS |
| CU. FT X 7.48 - GALLONS | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 10,496,969 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 6/11/2014 | 4.5 | 8.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris MF | John J. Morris | (973) 455-4003 |
| | | DATE 7/8/2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | MONTH: June 2014 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 6/1/2014 | Angel Trujillo | 8123739 | 8202795 | 79,056 | 0.079056 | 7.62 | 3.180 | | | | | | | | | 2.10 |
| 6/2/2014 | Angel Trujillo | 8202795 | 8281386 | 78,591 | 0.078591 | 7.51 | 3.180 | | | | | | | | | 2.08 |
| 6/3/2014 | Angel Trujillo | 8281386 | 8348247 | 66,861 | 0.066861 | 7.56 | 3.180 | | | | | | | | | 1.77 |
| 6/4/2014 | Angel Trujillo | 8348247 | 8426865 | 78,618 | 0.078618 | 7.85 | 3.180 | | | | | | | | | 2.09 |
| 6/5/2014 | Angel Trujillo | 8426865 | 8504478 | 77,613 | 0.077613 | 7.53 | 3.180 | | | | | | | | | 2.06 |
| 6/6/2014 | Angel Trujillo | 8504478 | 8583582 | 79,104 | 0.079104 | 7.45 | 3.180 | | | | | | | | | 2.10 |
| 6/7/2014 | Angel Trujillo | 8583582 | 8663790 | 80,208 | 0.080208 | 7.79 | 3.180 | | | | | | | | | 2.13 |
| 6/8/2014 | Angel Trujillo | 8663790 | 8744324 | 80,534 | 0.080534 | 7.45 | 3.180 | | | | | | | | | 2.14 |
| 6/9/2014 | Angel Trujillo | 8744324 | 8820375 | 76,051 | 0.076051 | 7.55 | 3.180 | | | | | | | | | 2.02 |
| 6/10/2014 | Angel Trujillo | 8820375 | 8899484 | 79,109 | 0.079109 | 7.64 | 3.180 | | | | | | | | | 2.10 |
| 6/11/2014 | Angel Trujillo | 8899484 | 8978575 | 79,091 | 0.079091 | 7.05 | 3.180 | <5.0 | 4.5 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 2.10 |
| 6/12/2014 | Angel Trujillo | 8978575 | 9064127 | 85,552 | 0.085552 | 7.99 | 3.180 | | | | | | | | | 2.27 |
| 6/13/2014 | Angel Trujillo | 9064127 | 9138884 | 74,757 | 0.074757 | 7.89 | 3.180 | | | | | | | | | 1.98 |
| 6/14/2014 | Angel Trujillo | 9138884 | 9222821 | 83,937 | 0.083937 | 8.05 | 3.180 | | | | | | | | | 2.23 |
| 6/15/2014 | Angel Trujillo | 9222821 | 9302595 | 79,774 | 0.079774 | 7.91 | 3.180 | | | | | | | | | 2.12 |
| 6/16/2014 | Angel Trujillo | 9302595 | 9379187 | 76,592 | 0.076592 | 7.81 | 3.180 | | | | | | | | | 2.03 |
| 6/17/2014 | Angel Trujillo | 9379187 | 9456705 | 77,518 | 0.077518 | 7.94 | 3.180 | | | | | | | | | 2.06 |
| 6/18/2014 | Angel Trujillo | 9456705 | 9536842 | 80,137 | 0.080137 | 7.91 | 3.180 | | | | | | | | | 2.13 |
| 6/19/2014 | Angel Trujillo | 9536842 | 9616176 | 79,334 | 0.079334 | 7.95 | 3.180 | | | | | | | | | 2.10 |
| 6/20/2014 | Angel Trujillo | 9616176 | 9697349 | 81,173 | 0.081173 | 7.73 | 3.180 | | | | | | | | | 2.15 |
| 6/21/2014 | Angel Trujillo | 9697349 | 9782475 | 85,126 | 0.085126 | 7.71 | 3.180 | | | | | | | | | 2.26 |
| 6/22/2014 | Angel Trujillo | 9782475 | 9862491 | 80,016 | 0.080016 | 7.76 | 3.180 | | | | | | | | | 2.12 |
| 6/23/2014 | Angel Trujillo | 9862491 | 9938998 | 76,507 | 0.076507 | 7.66 | 3.180 | | | | | | | | | 2.03 |
| 6/24/2014 | Angel Trujillo | 9938998 | 10020677 | 81,679 | 0.081679 | 7.71 | 3.180 | | | | | | | | | 2.17 |
| 6/25/2014 | Angel Trujillo | 10020677 | 10098524 | 77,847 | 0.077847 | 7.63 | 3.180 | | | | | | | | | 2.06 |
| 6/26/2014 | Angel Trujillo | 10098524 | 10177699 | 79,175 | 0.079175 | 7.64 | 3.180 | | | | | | | | | 2.10 |
| 6/27/2014 | Angel Trujillo | 10177699 | 10256990 | 79,291 | 0.0793 | 7.48 | 3.180 | | | | | | | | | 2.10 |
| 6/28/2014 | Angel Trujillo | 10256990 | 10338087 | 81,097 | 0.081097 | 7.82 | 3.180 | | | | | | | | | 2.15 |
| 6/29/2014 | Angel Trujillo | 10338087 | 10419275 | 81,188 | 0.081188 | 7.78 | 3.180 | | | | | | | | | 2.15 |
| 6/30/2014 | Angel Trujillo | 10419275 | 10496969 | 77,694 | 0.077694 | 7.55 | 3.180 | | | | | | | | | 2.06 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,373,230 | 2.37323 | | | <5.0 | 4.5 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 85,552 | | | | | | | | | | | High: | 2.27 |
| | | | Average: | 79,108 | | | | | | | | | | | Average: | 2.10 |

WW

JB69043

E

# Honeywell — Chain Of Custody / Analysis Request

t Labs
E 130
8910

| | | | |
|---|---|---|---|
| Co.: | Parsons | EDD To: | |
| ntact: (name, co., address) | | Sampler: | Frank Schroyer |
| P: (973) 455-2989 E: helen.fahy@honeywell.com | | PO # | |
| rnational | | Analysis Turnaround Time (TAT): | 3 |
| a Road Morristown, NJ 07962 | | Consultant | CH2M |
| To | Helen Fahy (Honeywell) | Full Report TAT: | 28 Days |
| | Helen Fahy (Honeywell) | | |

| | | | |
|---|---|---|---|
| Site Name: | Hudson County | Phase: | CS |
| Location of Site: | Jersey City, NJ | Sampling Program | 087: JCIA |

AESI Ref: 41901.64818
COC#: 087-WW-081114
Lab Proj # (SDG):
Lab ID: ACO
Site ID:
Lab Job #: HWINJM32515
Authorized User: Honeywell

Copyright AESI Version 3.0 Unauthorized use strictly prohibited.

| Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite Grab | Field Filtered Samples ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | EPA 245.1 Hg | 5405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached spedal list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| ion ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 7-WW | | | 087-WWS-081114-A | 8/11/2014 | 14:50 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | L25 |
| 7-WW | | | 087-WWS-081114-B | 8/11/2014 | 14:45 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | V706 |
| 7-WW | | | 087-WWI-081114 | 8/11/2014 | 15:00 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | A20 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | M19 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| ed by | Company | Parsons | Received by | Chris Lord | Company | Accutest | Condition | | Custody Seals Intact | |
| | Date/Time | 6/11/14 | | | Date/Time | 6/11/14/1615 | Cooler Temp. | 3.0°C | | |
| ed by | Company | Accutest | Received by | | Company | Accutest | Condition | | Custody Seals Intact | |
| =7.05 SU. FCS | Date/Time | 6/11/14/1715 | | | Date/Time | 6/11/14 1715 | Cooler Temp. | | | |
| ives: (Other; Specify): | | | 0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions) | | | | | | | |

ALL SAMPLES RECEIVED
PRESERVED AS APPLICABLE

pH = 7.20 @ 6/11/14

Accutest LabLink@801172 13:04 23-Jun-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-061114-A | | |
| Lab Sample ID: | JB69043-1 | Date Sampled: | 06/11/14 |
| Matrix: | AQ - Water | Date Received: | 06/11/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 3180 | 10 | ug/l | 1 | 06/12/14 | 06/13/14 | RR | EPA 200.7 [1] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 06/12/14 | 06/13/14 | RR | EPA 200.7 [1] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 06/12/14 | 06/13/14 | RR | EPA 200.7 [2] | EPA 200.7 [5] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 06/13/14 | 06/13/14 | JW | EPA 245.1 [3] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 06/12/14 | 06/13/14 | RR | EPA 200.7 [1] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 06/12/14 | 06/13/14 | RR | EPA 200.7 [1] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA34228
(2) Instrument QC Batch: MA34234
(3) Instrument QC Batch: MA34237
(4) Prep QC Batch: MP79997
(5) Prep QC Batch: MP80019

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@801172 13:04 23-Jun-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-061114-A | | |
| Lab Sample ID: | JB69043-1 | Date Sampled: | 06/11/14 |
| Matrix: | AQ - Water | Date Received: | 06/11/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | 8.0 | 4.0 | mg/l | 1 | 06/13/14 | RP | SM2540 D-11 |
| pH [a] | 7.20 | | su | 1 | 06/11/14 18:42 | JK | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@801172 13:04 23-Jun-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-061114-A | | |
| Lab Sample ID: | JB69043-1A | Date Sampled: | 06/11/14 |
| Matrix: | AQ - Water | Date Received: | 06/11/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 4.5 | 3.4 | mg/l | 1 | 06/11/14 19:23 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@801172 13:04 23-Jun-2014 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-061114-B | | |
| Lab Sample ID: | JB69043-2 | Date Sampled: | 06/11/14 |
| Matrix: | AQ - Water | Date Received: | 06/11/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N235746.D | 1 | 06/14/14 | DC | n/a | n/a | VN10001 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA PPL List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.5 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.4 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.26 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 19.9 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.4 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.55 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 56.7 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.4 | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 94% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 106% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 98% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@801172 13:04 23-Jun-2014 Preliminary Data

## Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-061114-B | | |
| Lab Sample ID: | JB69043-2 | Date Sampled: | 06/11/14 |
| Matrix: | AQ - Water | Date Received: | 06/11/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 06/16/14 | CW | EPA 1664A |

RL = Reporting Limit

## Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending June 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Pending submittal |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to Contractor only. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal |
| **DC 2014** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Pending submittal |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 5 OF 25**

- **2014 Monthly Reports Part 5**

**9/12/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

September 12, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-08**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from August 1 – August 31, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: August 2014 SA-6/7 Combined Monthly Progress Report No. 2014-08

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-08

**Project SA-6 & 7 Remediation**

# August 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 08/14/14 | Combined Monthly Progress/Highlights Report No. 2014-07<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/14/14 | NJPDES Permit NJ0156311: June 2014 Surface Water Discharge<br>Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | New Jersey Department of Environmental Protection<br>Division of Water Quality |
| 08/14/14 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014<br>*(see **Attachment 12**)* | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 08/18/14 | Combined Monthly Progress/Highlights Report No. 2014-07<br>Perimeter Pool Update Correction<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/19/14 | Special Master Conference Call | N/A |
| 08/19/14 | Design Change Bulletin – Barrier Wall Alignment Sedimentation Basin<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/19/14 | SA-6 Chromium Remedy<br>Asphalt Disposition Variance<br>Study Area 6 North and South, Jersey City | Mr. David Doyle, Case Manager<br>New Jersey Department of Environmental Protection |
| 08/20/14 | August 06, 2014 NJDEP E-mail Correspondence Accepting the Data Validation Revision (QAPP)<br>Study Area 6, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/20/14 | Variance for Consolidation of Asphalt on Study Area 6 (Arnold & Porter Correspondence)<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/20/14 | Response to Comments Provided by Plaintiffs, July 28, | Honorable Robert G. Torricelli |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| | 2014<br>Surcharge Grading Design Change Area 1S<br>Study Area 6 South, Jersey City, NJ | Office of the Special Master |
| 08/21/14 | Response to Plaintiffs' July 28, 2014 Comments Long Term Monitoring Program First Five Year Implementation Plan<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/21/14 | PVSC - Acoustic Monitoring Report<br>(Report 5 - JULY 08, 2014 TO AUGUST 20, 2014)<br>Study Area 6 North, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/25/14 | Surcharge Monitoring Plan – Monthly Report No. 4<br>Study Area 6 North and South, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/25/14 | August 06, 2014 NJDEP E-mail Correspondence Accepting the Data Validation Revision (QAPP) -- CORRECTION<br>Study Area 6, Jersey City, NJ | Upload to LB SharePoint Site |
| 08/28/14 | Redevelopment of Injection Well 088-IW-01<br>Study Area 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/29/14 | Incident No. 14-08-15-1405-34<br>Study Area 6 South<br>Chromium Site 163 (aka Colonial Concrete Company)<br>75 Kellogg Street, Jersey City, NJ<br>NJDEP PI#010374 | Ms. Kirstin Pointin-Hahn<br>Mr. David Doyle<br>New Jersey Department of Environmental Protection |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 8/3/14 | 8/10/14 | 8/17/14 | 8/24/14 | 8/31/14 |
| **Construction Management (AMEC)** | 12 | 13 | 12 | 11 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 40 | 40 | 45 | 46 | 45 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 1 | 1 |
| **ERFS In Situ Treatment** | 3 | 4 | 4 | 2 | 0 |
| **Summit Drilling** | 3 | 2 | 2 | 1 | 0 |
| **Siemens** | 1 | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 0 | 1 | 1 |
| **TOTAL** | **65** | **66** | **70** | **68** | **62** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Collected August PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed S-3 Injection/Mass Removal Event #16 in well 088-IW-03.
- On August 13, 2014, participated in the public bid opening for the JCIA Structures Demolition project.
- Completed In-Situ treatment field implementation activities on SA6 South- Site 163. A total of 57 temporary well points and 119 injection points were installed. Successfully injected 2,228 gallons of stock 29% CAPs solution (62,492 gallons of diluted solution) in the 15 designated areas during the reporting period.
- On August15, 2014, daylighting of CAPs was observed in Droyer's Cove during one in-situ injection in Area F. Injection operations were stopped at this location, and the NJDEP hotline notified.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 2**0**1 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on August 22, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 8/3/14 | 8/10/14 | 8/17/14 | 8/24/14 | 8/31/14 |
| Avg. Gallons Treated & Discharged (per day) | 79,753 | 78,183 | 78,219 | 78,087 | 78,149 |
| Average Flow (gpm) for Operating Period | 55 | 55 | 54 | 55 | 54 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 | 24 |
| GWTP InfluentTanks (gal.) | 7,677 | 11,555 | 10,427 | 9,852 | 9,408 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in cells 102-83.
- Continued storm-water management activities.
- On July 30, 2014, we collected a soil sample from a visually anomalous material observed in a thin lens located above Stratum D. Laboratory analysis received on August 18, 2014 indicated the result was 713 mg/kg. On August 19, 2014, Amec collected two additional soil samples for hexavalent chromium analysis from this lens above Stratum D in the southern portion of Cell 105.

Both of the sample results were greater than 20 mg/kg, (230 mg/kg) and (198 mg/kg). Further delineation and sampling of the anomaly is pending.

- Installed 44 pair of temporary sheets for excavation support along Kellogg Street.
- On July 30, 2014 a 12-inch diameter transite pipe was encounter during pre-trenching activities associated with installation of the temporary sheets along Kellogg Street. Excavation activities were suspended and an abatement contractor was mobilized to remove pipe. A total of 115 linear ft. of 12- inch diameter transite pipe was removed, wrapped in poly-sheeting, placed in a roll-off, and staged on site for future disposal.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

## 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 0 | 0 | 0 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 20 | 21.51 | 430.2 |
| **Entact/ Montecalvo** | 30 cyd roll-off | Bayshore Recycling | NA | Non Haz Creosote Debris | 8 | 10.9 | 87.10 |

## 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 102-83 |
| **Excavation Completed** | Cell Number(s) 102-85<br>Volume Excavated - Total for Reporting Period: 18,482 CY/ Total to Date: 102,627 CY |
| **Backfill in Progress** | Cell Number(s) 129-85 |

## 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 8/03/14 | 8/10/14 | 8/17/14 | 8/24/14 | 8/31/14 |
| <20ppm re-use, CY | 0 | 0 | 0 | 0 | 250 |
| Weldon, Import-Tons Screenings | 8,166 | 8,546 | 7,576 | 1,396 | 3,523 |
| Tilcon, Import-Tons DGA | 0 | 0 | 0 | 0 | 656 |
| Tilcon, Import Tons – 1.5” Stone | 0 | 0 | 259 | 0 | 487 |
| Weldon, Imported Tons - QP | 590 | 1,221 | 825 | 1,070 | 0 |
| Weldon, Imported Tons - DGA | 0 | 0 | 0 | 0 | 326 |
| Celgene - Loads | 411 | 724 | 0 | 0 | 0 |
| Tilcon, Imported Tons – 2.5” Stone | 0 | 0 | 309 | 0 | 0 |

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharge continued with placement of both chromium impacted soils to the design subgrade and imported Celgene soils between the subgrade and surcharge design grade. Surcharge placement is approximately 85% complete.
- Area 2S: Surcharging continued from 1S into the western portion of 2S. Surcharge placement consisted of subgrade fill and is approximately 15% complete.
- Area 3S: Instrumentation installation was completed as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles are located in this area. No Surcharge has been initiated.
- Area 1N: Surcharge is completed. Surcharge removal is scheduled to commence in September. Details were provided in the August Surcharge Monitoring Report No. 4.
- Area 2N: Instrumentation Installation 100 % complete. Surcharge removed from 1N will be relocated to Area 2N.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- No sheets were driven associated with the hydraulic barrier wall during this reporting period.
- On August 27, 2014, a test pit was excavated to field verify the location of a 90 degree bend in the 72-inch force main. This activity identified that the actual location was approximately 4 feet farther to the east necessitating a design change bulletin to address the needed relocation of the barrier wall.

## G. PERMIT STATUS

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Pre-construction meeting for the Above-grade Demolition of the four designated JCIA Structures scheduled for September 4, 2014.
- Complete In-Situ treatment injection/temporary monitoring point abandonment activities at Site 163.
- Continue placement of surcharge materials in SA-6S Area 1S and 2S.
- Begin off loading of surcharge materials from SA-6N Area 1N.
- Begin placement of surcharge materials in SA-6N Area 2N.
- Continue installation of the contingent groundwater system trench on SA-6S.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 83-70.
- Continue stockpiling of presumed <20 mg/kg for additional sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Continue dewatering and storm-water management activities.
- Conduct S-3 Injection/Mass Removal Event No.17 in well 088-IW-02.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations


- Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-3)
   - SA-6 South Deep Well Data (DW-4)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. *Groundwater Quality Data Surcharge Monitoring Update (provided on a quarterly basis - not available as of this report date)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Sheet Deflection Along Open Excavation
    - Sheet Monitoring Locations
    - Sheet Pile Repair Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (July 2014)
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (July 2014)
13. SA-6 North & South Design Change Tracking Log

## Attachment 1:  Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Wed 9/3/14

Task | Milestone | Summary | Critical

## Attachment 2: Site Photographs




**Site Photograph 1:** Cleaning the steel sheets during excavation.




**Site Photograph 2:** Construction Water Treatment Plant on Jersey City Properties.




**Site Photograph 3:** Contractor compacts clean fill on Kellogg St. Properties.




**Site Photograph 4:** Contractor places surcharge on western area of site.




**Site Photograph 5:** Contractor processes concrete for reuse.





**Site Photograph 6:** Overview of Excavation and backfill operations.

## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables (SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points)
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of September 1, 2014

August 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill




## Legend


- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete




ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 08-07-14 TO 08-21-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -0.6 | 134-SB-019 | 114A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.3 | 601878.4 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.5 | 601974.0 | 1.2 | 134-SB-061 | 106A | 7/23/2014 | -5.2 | Stratum D Reached |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.8 | 601978.1 | -7.5 | 134-SB-113 | 103 | 7/29/2014 | -7.2 | Stratum D Reached |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | UST Area |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | UST Area |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | UST Area |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Target Elevation Reached |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685094.6 | 601890.3 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 685081.0 | 601928.0 | -0.1 | 134-SB-021 | 109A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 685080.6 | 601935.9 | 3.0 | 134-SB-092 | 108A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Target Elevation Reached |
| 684999.7 | 601940.5 | -0.5 | 134-SB-097 | 104 | 7/29/2014 | -7.2 | Stratum D Reached |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 8/22/14

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.


Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | | |
| 1 | RF-24-01 | 9/2/2014 | 684298.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602036.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.1719 | 601631.644 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.423 | 601673.304 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-3)
- SA-6 South Deep Well Data (DW-4)

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 07/01/14 | 2 | 24 | 13,14, WPS-2 | 48 | 247,628 | 259,680 | 12,052 | 2,292,256 | 8.4 | |
| 07/02/14 | 2 | 24 | 13,14, WPS-2 | 48 | 259,680 | 266,319 | 6,639 | 2,298,895 | 4.6 | |
| 03/13/00 | 2 | 24 | 13,14, WPS-2 | 48 | 266,319 | 270,103 | 3,784 | 2,302,679 | 2.6 | |
| 07/07/14 | 2 | 86 | 13,14, WPS-2 | 48 | 270,103 | 285,239 | 15,136 | 2,317,815 | 2.9 | |
| 07/08/14 | 2 | 24 | 13,14, WPS-2 | 45 | 285,239 | 288,158 | 2,919 | 2,320,734 | 2.0 | |
| 07/09/14 | 2 | 24 | 13,14, WPS-2 | 45 | 288,158 | 289,792 | 1,634 | 2,322,368 | 1.1 | |
| 07/10/14 | 2 | 24 | 13, WPS-2 | 27 | 289,792 | 292,235 | 2,443 | 2,324,811 | 1.7 | |
| 07/11/14 | 2 | 24 | 13, WPS-2 | 27 | 292,235 | 295,728 | 3,493 | 2,328,304 | 2.4 | |
| 07/14/14 | 2 | 72 | 13, WPS-2 | 27 | 295,728 | 306,209 | 10,481 | 2,338,785 | 2.4 | |
| 07/15/14 | 2 | 24 | 13, WPS-2 | 27 | 306,209 | 309,704 | 3,495 | 2,342,280 | 2.4 | |
| 07/16/14 | 2 | 24 | 13, WPS-2 | 27 | 309,704 | 311,299 | 1,595 | 2,343,875 | 1.1 | |
| 07/17/14 | 2 | 24 | 13, WPS-2 | 27 | 311,299 | 312,848 | 1,549 | 2,345,424 | 1.1 | |
| 07/18/14 | 2 | 24 | 13, WPS-2 | 27 | 312,848 | 313,958 | 1,110 | 2,346,534 | 0.8 | |
| 07/21/14 | 2 | 72 | 13, WPS-2 | 27 | 313,958 | 317,809 | 3,851 | 2,350,385 | 0.9 | |
| 07/22/14 | 2 | 24 | 13, WPS-2 | 27 | 317,809 | 318,844 | 1,035 | 2,351,420 | 0.7 | |
| 07/23/14 | 2 | 24 | 13, WPS-2 | 27 | 318,844 | 319,048 | 204 | 2,351,624 | 0.1 | |
| 07/24/14 | 2 | 24 | 13, WPS-2 | 22 | 319,048 | 319,062 | 14 | 2,351,638 | 0.0 | |
| 07/25/14 | 2 | 24 | 13, WPS-2 | 22 | N/A | N/A | 450 | 2,352,088 | 0.3 | Flowmeter Blockage - Tank Measured |
| 07/28/14 | 2 | 72 | 13, WPS-2 | 22 | N/A | N/A | 1,650 | 2,353,738 | 0.4 | Flowmeter Blockage - Tank Measured |
| 07/29/14 | 2 | 24 | 13, WPS-2 | 22 | N/A | N/A | 550 | 2,354,288 | 0.4 | Flowmeter Blockage - Tank Measured |
| 07/30/14 | 2 | 24 | 13, WPS-2 | 22 | N/A | N/A | 500 | 2,354,788 | 0.3 | System Disabled or Relocation |
| 08/05/14 | 1 | 4 | 10, 11, 12, EPS | 61 | 0 | 1,893 | 1,893 | 2,356,681 | 7.9 | |
| 08/06/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 1,893 | 23,795 | 21,902 | 2,378,583 | 15.2 | |
| 08/07/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 23,795 | 44,386 | 20,591 | 2,399,174 | 14.3 | |
| 08/08/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 0 | 8,014 | 8,014 | 2,407,188 | 5.6 | |
| 08/11/14 | 1 | 72 | 10, 11, 12, EPS | 61 | 8,014 | 32,057 | 24,043 | 2,431,231 | 5.6 | |
| 08/12/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 32,057 | 40,072 | 8,015 | 2,439,246 | 5.6 | |
| 08/13/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 40,072 | 59,407 | 19,335 | 2,458,581 | 13.4 | |
| 08/14/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 59,407 | 89,000 | 29,593 | 2,488,174 | 20.6 | |
| 08/18/14 | 1 | 72 | 10, 11, 12, EPS | 61 | 0 | 47,911 | 47,911 | 2,536,085 | 11.1 | Flowmeter Reset |
| 08/19/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 47,911 | 61,590 | 13,679 | 2,549,764 | 9.5 | |
| 08/20/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 61,590 | 75,268 | 13,678 | 2,563,442 | 9.5 | |
| 08/21/14 | 1 | 24 | 10, 11, 12, EPS | 50 | N/A | N/A | 14,000 | 2,577,442 | 9.7 | Flowmeter Blockage - Tank Measured |
| 08/22/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 75,268 | 77,640 | 2,372 | 2,579,814 | 1.6 | |
| 08/25/14 | 1 | 72 | 10, 11, 12, EPS | 50 | 0 | 20,218 | 20,218 | 2,600,032 | 4.7 | Flowmeter Reset |
| 08/26/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 20,218 | 42,158 | 21,940 | 2,621,972 | 15.2 | |
| 08/27/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 42,158 | 47,944 | 5,786 | 2,627,758 | 4.0 | |
| 08/28/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 47,944 | 54,589 | 6,645 | 2,634,403 | 4.6 | |
| 08/29/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 54,589 | 61,819 | 7,230 | 2,641,633 | 5.0 | |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-3)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 08/06/14 | 24 | 0 | 1,340 | 1,340 | 1,340 | 0.9 | |
| 08/07/14 | 24 | 1,340 | 2,525 | 1,185 | 2,525 | 0.8 | |
| 08/08/14 | 24 | N/A | N/A | 5,500 | 8,025 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/11/14 | 72 | N/A | N/A | 17,500 | 25,525 | 4.1 | Flowmeter blockage - Tank Measured |
| 08/12/14 | 24 | 0 | 3,528 | 3,528 | 29,053 | 2.5 | Flowmeter Reset |
| 08/13/14 | 24 | N/A | N/A | 5,500 | 34,553 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/14/14 | 24 | N/A | N/A | 5,000 | 39,553 | 3.5 | Flowmeter blockage - Tank Measured |
| 08/15/14 | 24 | N/A | N/A | 5,500 | 45,053 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/18/14 | 72 | N/A | N/A | 16,500 | 61,553 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/19/14 | 24 | N/A | N/A | 6,000 | 67,553 | 4.2 | Flowmeter Not Installed - Tank Measured |
| 08/20/14 | 24 | N/A | N/A | 6,500 | 74,053 | 4.5 | Flowmeter Not Installed - Tank Measured |
| 08/21/14 | 24 | N/A | N/A | 6,000 | 80,053 | 4.2 | Flowmeter Not Installed - Tank Measured |
| 08/22/14 | 24 | N/A | N/A | 6,250 | 86,303 | 4.3 | Flowmeter Not Installed - Tank Measured |
| 08/25/14 | 72 | N/A | N/A | 17,500 | 103,803 | 4.1 | Flowmeter Not Installed - Tank Measured |
| 08/26/14 | 24 | N/A | N/A | 5,750 | 109,553 | 4.0 | Flowmeter Not Installed - Tank Measured |
| 08/27/14 | 24 | N/A | N/A | 5,700 | 115,253 | 4.0 | Flowmeter Not Installed - Tank Measured |
| 08/28/14 | 24 | N/A | N/A | 5,500 | 120,753 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 08/29/14 | 24 | N/A | N/A | 5,500 | 126,253 | 3.8 | Flowmeter Not Installed - Tank Measured |

Note: Well DW-3 was activated on August 6, 2014.

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-4)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 07/16/14 | 24 | 0 | 4,141 | 4,141 | 4,141 | 2.9 | |
| 07/17/14 | 24 | 4,141 | 8,184 | 4,043 | 8,184 | 2.8 | |
| 07/18/14 | 24 | 8,184 | 12,120 | 3,936 | 12,120 | 2.7 | |
| 07/21/14 | 72 | 0 | 16,253 | 16,253 | 28,373 | 3.8 | Flowmeter Reset |
| 07/22/14 | 24 | 16,253 | 19,898 | 3,645 | 32,018 | 2.5 | |
| 07/23/14 | 24 | N/A | N/A | 4,000 | 36,018 | 2.8 | Flowmeter Blockage, Tank Measured |
| 07/24/14 | 24 | N/A | N/A | 4,200 | 40,218 | 2.9 | Pump Taken Offline for Excavation |
| 08/13/14 | 24 | N/A | N/A | 6,000 | 46,218 | 4.2 | Flowmeter Not Installed - Tank Measured |
| 08/14/14 | 24 | N/A | N/A | 5,500 | 51,718 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 08/15/14 | 24 | N/A | N/A | 5,500 | 57,218 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 08/18/14 | 72 | N/A | N/A | 5,750 | 62,968 | 1.3 | Flowmeter Not Installed - Tank Measured |
| 08/19/14 | 24 | N/A | N/A | 5,750 | 68,718 | 4.0 | Flowmeter Not Installed - Tank Measured |
| 08/20/14 | 24 | N/A | N/A | 5,500 | 74,218 | 3.8 | Pump Taken Offline |

Notes: DW-4 was activated on July 16, 2014 and taken offline on August 20, 2014.

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 07/02/14 | 8:30 | 15,754.00 | 15,879.17 | 125,170 | 15,878,720 | PVSC Compliance Sample Collected |
| 07/03/14 | 5:15 | 15,879.17 | 15,995.15 | 115,980 | 15,994,700 | |
| 07/04/14 | 7:15 | 15,995.15 | 16,174.96 | 179,810 | 16,174,510 | |
| 07/05/14 | 7:00 | 16,174.96 | 16,354.58 | 179,620 | 16,354,130 | |
| 07/06/14 | 5:55 | 16,354.58 | 16,443.35 | 88,770 | 16,442,900 | |
| 07/07/14 | 9:05 | 16,443.35 | 16,582.28 | 138,930 | 16,581,830 | |
| 07/08/14 | 8:05 | 16,582.28 | 16,719.12 | 136,840 | 16,718,670 | |
| 07/09/14 | 7:30 | 16,719.12 | 16,813.21 | 94,090 | 16,812,760 | |
| 07/10/14 | 7:15 | 16,813.21 | 16,861.07 | 47,860 | 16,860,620 | |
| 07/11/14 | 6:00 | 16,861.07 | 16,927.80 | 66,730 | 16,927,350 | |
| 07/14/14 | 7:35 | 17,039.50 | 17,039.50 | 111,700 | 17,039,050 | |
| 07/15/14 | 8:10 | 17,151.47 | 17,151.47 | 111,970 | 17,151,020 | |
| 07/16/14 | 7:30 | 17,151.47 | 17,277.51 | 126,040 | 17,277,060 | |
| 07/17/14 | 5:15 | 17,277.51 | 17,369.50 | 91,990 | 17,369,050 | |
| 07/18/14 | 7:45 | 17,369.50 | 17,470.26 | 100,760 | 17,469,810 | |
| 07/21/14 | 8:30 | 17,470.26 | 17,603.88 | 133,620 | 17,603,430 | |
| 07/22/14 | 8:00 | 17,603.88 | 17,697.76 | 93,880 | 17,697,310 | |
| 07/23/14 | 7:30 | 17,697.76 | 17,756.61 | 58,850 | 17,756,160 | |
| 07/24/14 | 7:30 | 17,756.61 | 17,794.18 | 37,570 | 17,793,730 | |
| 07/25/14 | 7:00 | 17,794.18 | 17,849.88 | 55,700 | 17,849,430 | |
| 07/28/14 | 8:00 | 17,849.88 | 17,964.12 | 114,240 | 17,963,670 | |
| 07/29/14 | 8:00 | 17,964.12 | 18,017.49 | 53,370 | 18,017,040 | |
| 07/30/14 | 7:50 | 18,017.49 | 18,060.14 | 42,650 | 18,059,690 | |
| 08/04/14 | 2:15 | 18,060.14 | 18,144.28 | 84,140 | 18,143,830 | |
| 08/05/14 | 8:00 | 18,144.28 | 18,237.50 | 93,220 | 18,237,050 | PVSC Compliance Sample Collected |
| 08/06/14 | 7:45 | 18,237.50 | 18,289.93 | 52,430 | 18,289,480 | |
| 08/07/14 | 5:30 | 18,289.93 | 18,324.27 | 34,340 | 18,323,820 | |
| 08/08/14 | 7:20 | 18,324.27 | 18,357.38 | 33,110 | 18,356,930 | |
| 08/11/14 | 9:00 | 18,357.38 | 18,450.45 | 93,070 | 18,450,000 | |
| 08/12/14 | 7:00 | 18,450.45 | 18,524.19 | 73,740 | 18,523,740 | |
| 08/13/14 | 6:15 | 18,524.19 | 18,579.42 | 55,230 | 18,578,970 | |
| 08/14/14 | 7:00 | 18,579.42 | 18,610.35 | 30,930 | 18,609,900 | |
| 08/15/14 | 6:00 | 18,610.35 | 18,630.29 | 19,940 | 18,629,840 | |
| 08/17/14 | 6:00 | 18,630.29 | 18,701.73 | 71,440 | 18,701,280 | |
| 08/19/14 | 8:00 | 18,701.73 | 18,805.82 | 104,090 | 18,805,370 | |
| 08/20/14 | 6:00 | 18,805.82 | 18,884.84 | 79,020 | 18,884,390 | |
| 08/21/14 | 8:00 | 18,884.84 | 18,986.62 | 101,780 | 18,986,170 | |
| 08/22/14 | 7:45 | 18,986.62 | 19,094.08 | 107,460 | 19,093,630 | |
| 08/25/14 | 8:00 | 19,094.08 | 19,193.73 | 99,650 | 19,193,280 | |
| 08/26/14 | 8:45 | 19,193.73 | 19,298.14 | 104,410 | 19,297,690 | |
| 08/27/14 | 7:30 | 19,298.14 | 19,368.93 | 70,790 | 19,368,480 | |
| 08/28/14 | 8:45 | 19,368.93 | 19,461.76 | 92,830 | 19,461,310 | |
| 08/29/14 | 5:45 | 19,461.76 | 19,495.63 | 33,870 | 19,495,180 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 110-118 | <20 | 124-118-20-a | 1000 | 124-118-20-a1 | 7/9/2014 | 13:00 | 20.3 | | Yes | |
| | | | | 124-118-20-a2 | 7/9/2014 | 13:05 | 19.7 | Yes | | |
| | | | | 124-118-20-a3 | 7/9/2014 | 13:10 | 37.1 | | Yes | |
| | | | | 124-118-20-a4 | 7/9/2014 | 13:15 | 61.1 | | Yes | |
| 102-119 | >1000 | 124-119-1000-a | 800 | 124-119-1000-a1 | 7/29/2014 | 11:00 | 174 | | Yes | |
| | | | | 124-119-1000-a2 | 7/29/2014 | 11:05 | 302 | | Yes | |
| | | | | 124-119-1000-a3 | 7/29/2014 | 11:10 | 149 | | Yes | |
| | | | | 124-119-1000-a4 | 7/29/2014 | 11:15 | 2,180 | | | Yes |
| 101-112 | <20 | 124-112-20-a,b,c | 2800 | 124-112-20-a1 | 7/30/2014 | 12:45 | 16.1 | Yes | | |
| | | | | 124-112-20-a2 | 7/30/2014 | 12:50 | 6.7 | Yes | | |
| | | | | 124-112-20-a3 | 7/30/2014 | 12:55 | 8.7 | Yes | | |
| | | | | 124-112-20-a4 | 7/30/2014 | 13:00 | 11.0 | Yes | | |
| | | | | 124-112-20-b1 | 7/30/2014 | 13:05 | 2.4 | Yes | | |
| | | | | 124-112-20-b2 | 7/30/2014 | 13:10 | 2.6 | Yes | | |
| | | | | 124-112-20-b3 | 7/30/2014 | 13:15 | 14.7 | Yes | | |
| | | | | 124-112-20-b4 | 7/30/2014 | 13:20 | 1.6 | Yes | | |
| | | | | 124-112-20-c1 | 7/30/2014 | 13:25 | 24.0 | | * | |
| | | | | 124-112-20-c2 | 7/30/2014 | 13:30 | 3.4 | * | | |
| | | | | 124-112-20-c3 | 7/30/2014 | 13:35 | 6.0 | * | | |
| | | | | 124-112-20-c4 | 7/30/2014 | 13:40 | 2.6 | * | | |
| 92-102 | >1000 | 124-102-1000-a,b | 2100 | 124-102-1000-a1 | 8/14/2014 | 12:25 | ** | | | |
| | | | | 124-102-1000-a2 | 8/14/2014 | 12:30 | ** | | | |
| | | | | 124-102-1000-a3 | 8/14/2014 | 12:35 | ** | | | |
| | | | | 124-102-1000-a4 | 8/14/2014 | 12:40 | ** | | | |
| | | | | 124-102-1000-b1 | 8/14/2014 | 12:45 | ** | | | |
| | | | | 124-102-1000-b2 | 8/14/2014 | 12:50 | ** | | | |
| | | | | 124-102-1000-b3 | 8/14/2014 | 12:55 | ** | | | |
| | | | | 124-102-1000-b3 | 8/14/2014 | 13:00 | ** | | | |
| 88-101 | <20 | 124-101-20-a, b, c | 2850 | 124-101-20-a1 | 8/22/2014 | 9:35 | ** | | | |
| | | | | 124-101-20-a2 | 8/22/2014 | 9:40 | ** | | | |
| | | | | 124-101-20-a3 | 8/22/2014 | 9:45 | ** | | | |
| | | | | 124-101-20-a4 | 8/22/2014 | 9:50 | ** | | | |
| | | | | 124-101-20-b1 | 8/22/2014 | 9:55 | ** | | | |
| | | | | 124-101-20-b2 | 8/22/2014 | 10:00 | ** | | | |
| | | | | 124-101-20-b3 | 8/22/2014 | 10:05 | ** | | | |
| | | | | 124-101-20-b4 | 8/22/2014 | 10:10 | ** | | | |
| | | | | 124-101-20-c1 | 8/22/2014 | 10:15 | ** | | | |
| | | | | 124-101-20-c2 | 8/22/2014 | 10:20 | ** | | | |
| | | | | 124-101-20-c3 | 8/22/2014 | 10:25 | ** | | | |
| | | | | 124-101-20-c4 | 8/22/2014 | 10:30 | ** | | | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

## Attachment 7:  Perimeter Pools Update




IN PROGRESS
05-07-2014


STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


May 07, 2014 at 4:13pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | South | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-1 | FS-3 | FS-4 | FS-5 |
| Date | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | 7.5 | 7.9 | 7.7 | 5.9 |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | 7.7 | 8.1 | 7.9 | 7.2 |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | 7.6 | 7.8 | 7.6 | 8.0 |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | 7.4 | 8.0 | 8.0 | 8.6 |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | 7.4 | 8.4 | 8.4 | 9.4 |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | 6.1 | 7.9 | 7.6 | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | 4.3 | 7.5 | 7.8 | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | 3.3 | 5.3 | 9.0 | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | 4.1 | 5.5 | 8.9 | 8.9 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO, W5-SO

## Attachment 8: Quality and Level Data in GWET Wells

(not available as of this report date - provided on a quarterly basis)

- Summary of Groundwater Quality Data from GWET Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells

## Attachment 9: Surcharge Monitoring Update


(not included in this reporting period)


## Attachment 10: Sheet Pile Update

- Sheet Deflection Along Open Excavation
- Sheet Monitoring Locations
- Sheet Pile Repair Log

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.







NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SHEET MONITORING LOCATIONS
03-20-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SHEET MONITORING LOCATIONS
08-19-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 18P-11
Entact ID:
Date Exposed: 7/17/14
Describe Damage: (11) Scrapes by the Cat 349E excavator bucket - (5) 1/2"Ø, (3) 1"Ø, 2×10", 1/2×36", 1×18". Cell 106/105

Damage Location (ft below top of sheet, inboard side outboard side): 13-18' outboard

Date Repaired: 7/24/14 Partial, 8/5/14 Remaining
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 4" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 18P-12
Entact ID:
Date Exposed: 7/17/14
Describe Damage: (8) Scrapes by the Cat 349E excavator bucket - 1/2×12", 2"Ø, 1/2×8", 1/2×30", 1×12", 2×5", 1/2×60", 3"Ø. Cell 105

Damage Location (ft below top of sheet, inboard side outboard side): 11-18' outboard

Date Repaired: 7/24/14 Partial, 8/5/14 Remaining
Inspected by: Bnan Shea
Describe Repair: Pressure Wash, wire brush, apply epoxy w/ 4" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 18P-13
Entact ID:
Date Exposed: 7/21/14
Describe Damage: (6) scrapes by the Cat 349E excavator bucket - 1/2×4", 1"Ø, 1×5", 1×12", 2"Ø, 1/2"Ø. Cell 105. Sheet is covered w/ hardened grout from elv. 8.0' - (2.5')

Damage Location (ft below top of sheet, inboard side outboard side): 14-17' outboard

Date Repaired: 7/24/14
Inspected by: Bnan Shea
Describe Repair: Pressure Wash, wire brush, apply epoxy w/ 4" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 7/24/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:
Entact ID:
Date Exposed:
Describe Damage:

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired:
Inspected by:
Describe Repair:
Repair Log Closure: AMEC Signature:
Date:

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-1

Entact ID:

Date Exposed: 7/22/14

Describe Damage: (9) scrapes by the Cat 349E excavator bucket- (6) 1/2"Ø, 1/2x36", 1"Ø, 2"Ø. Cell 105/104

Damage Location (ft below top of sheet, inboard side outboard side): 8-12' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/5/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-2

Entact ID:

Date Exposed: 7/22/14

Describe Damage: (6) scrapes by the Cat 349E excavator bucket - 1x3", 2"Ø, 1/2x6", 3x12", (2) 1/2"Ø, Cell 104.

Damage Location (ft below top of sheet, inboard side outboard side): 8-14' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-3

Entact ID:

Date Exposed: 7/24/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 1/2x6", 2"Ø, 1/2x36", 1/2x3", 1x36", 1x18", 1/2x6", 1"Ø. Cell 104

Damage Location (ft below top of sheet, inboard side outboard side): 2-14' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-4

Entact ID:

Date Exposed: 7/24/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 1/2x6", 1"Ø, 1/2x3", 2"Ø, 1/2x24", 1x12", 1x48", 1/2x48". C-104

Damage Location (ft below top of sheet, inboard side outboard side): 3-14' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-5
Entact ID:
Date Exposed: 7/25/14
Describe Damage: (6) scrapes by the Cat 349E excavator bucket - 1"Ø, 2"Ø, 1/2x8", 1/2x36", 1/2x2". 104/103.

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-6
Entact ID:
Date Exposed: 7/25/14
Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1"x84", 1x48", 2x12", 1/2x18", 1"Ø. Cell 103
Sheet is covered w/ hardened grout from elv. 8.0' - 0.0'.

Damage Location (ft below top of sheet, inboard side outboard side): 1-10' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Remaining
Inspected by: Brian Shea
Describe Repair: Pressure washed, wire brushed, and applied epoxy w/ a 4" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-7
Entact ID:
Date Exposed: 7/25/14
Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 5x60", (3) 1"Ø, 1/2x48", 1/2x24", 1x2", 1/2"Ø. Cell 103.
Hardened grout covering sheet from elv. 8.0' to (2.0')

Damage Location (ft below top of sheet, inboard side outboard side): 1-15' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Remaining
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-8
Entact ID:
Date Exposed: 7/28/14
Describe Damage: (6) scrapes by the Cat 349E excavator bucket - 1x24", 1/2x36", 1"Ø, (3) 1x3". Cell 103/102.
Sheet is covered w/ hardened grout from elv. 9.0' to (3.0').

Damage Location (ft below top of sheet, inboard side outboard side): 6-15' outboard

Date Repaired: 7/29/14 Partial, 8/6/14 Remaining
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 4" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-9

Entact ID:

Date Exposed: 7/29/14

Describe Damage: (5) Scrapes by the Cat 349E excavator bucket - 1/2 x 18", 1"Ø, 1"Ø, 1/2 x 6", 1/2"Ø. Cell 102

Note: Sheet is covered w/ hardened grout from elv. 7.0' to (4.0').

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 8/5/14 Partial, 8/6/14 Remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-10

Entact ID:

Date Exposed: 7/29/14

Describe Damage: (6) Scrapes by the Cat 349E excavator bucket - 1/2 x 30", 1x6", 1"Ø, 1/2"Ø, 1/2"Ø, 1x12". Cell 102.

Note: Sheet is covered w/ hardened grout from elv. 0.0' to (4.0').

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 8/5/14 Partial, 8/6/14 Remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-11

Entact ID:

Date Exposed: 7/29/14

Describe Damage: (4) scrapes by the Cat 349E excavator bucket - 1x8", 1/2x12", 1/2x6", 2x4". Cell 102

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 8/5/14 Partial, 8/6/14 remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-12

Entact ID:

Date Exposed: 7/30/14

Describe Damage: (8) scrapes by the Cat 349E excavator bucket - 1/2x36", 1"Ø, 2x8", 1/2x6", 1/4x3", 2x4", 4"Ø, 1/2x12". Cell 101

Note. Sheet is covered by hardened grout from elv. 5.0' to (5.0').

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 8/5/14 Partial, 8/6/14 Remaining

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-13
Entact ID:
Date Exposed: 7/30/14
Describe Damage: (8) Scrapes by the Cat 349E excavator bucket - 1x36", (2) 1/2"Ø, 10x14", 1x72", 1/2x3", 1x60", 1x36", and a small leak in the interlock weld. Cell 101

Damage Location (ft below top of sheet, inboard side outboard side): Scrapes 9-15' outboard leak 17' outboard
Date Repaired: 8/5/14 Partial, 8/6/14 Remaining
Inspected by: Bnan Shea
Describe Repair: Scrapes - pressure washed and epoxy painted on w/ a 2" brush. Leak - cleaned, covered/welded by a 5" steel angle, covered w/ epoxy, backfilled, and grouted.
Repair Log Closure: AMEC Signature:
Date: BShea 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-14
Entact ID:
Date Exposed: 7/30/14
Describe Damage: (10) Scrapes by the Cat 349E excavator bucket - 1x60", (3) 1"Ø, 4x8", (2) 1/2"Ø, 1x30", 1x48", 3"Ø, Cell 101

Damage Location (ft below top of sheet, inboard side outboard side): 2-16' outboard
Date Repaired: 8/5/14 Partial, 8/6/14 Remaining
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-15
Entact ID:
Date Exposed: 7/31/14
Describe Damage: (10) scrapes by the Cat349E excavator bucket - (6) 1"Ø, 1/2x24", 1/2x3", 1/2x6", 1/2x48". Cell 101/100. Sheet is covered w/ hardened grout from elv. 8.0' to (4.0').

Damage Location (ft below top of sheet, inboard side outboard side): 2-16' outboard
Date Repaired: 8/5/14 Partial, 8/6/14 Remaining
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-16
Entact ID:
Date Exposed: 7/31/14
Describe Damage: (7) Scrapes by the Cat349E excavator bucket - 1/2x4", 1/2x6", 1/2x24", 1x12", 1"Ø, 1x36", 1x12". Cell 100 Sheet is covered w/ hardened grout from elv. 7.0' to (4.0')

Damage Location (ft below top of sheet, inboard side outboard side): 1-15' outboard
Date Repaired: 8/5/14 Partial, 8/6/14 Remaining
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/6/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-17

Extact ID:

Date Exposed: 8/5/14

Describe Damage: (15) Scrapes by the Cat 349E excavator bucket- (2) 1×60", 1×24", 1×72", (4) 1/2×12", (4) 1" ø, 1/2×8", 1/2×3, 3" ø.

Cell 100

Damage Location (ft below top of sheet, inboard side, outboard side): 2-15' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure, wire brush, apply epoxy w/ 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and treated as repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-18

Extact ID:

Date Exposed: 8/5/14

Describe Damage: (12) Scrapes by the Cat 349E excavator bucket- 1/4×72", 1/2×24", 1×6", 1×6", 1" ø, 1/2×2", (2) 3" ø, (2) 1/2×12", (2) 1/2" ø.

Cell 100. Sheet is covered w/ hardened grout from elv 5.0' to 1.0'

Damage Location (ft below top of sheet, inboard side, outboard side): 2-15' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and treated as repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-19

Extact ID:

Date Exposed: 8/5/14

Describe Damage: (11) Scrapes by the Cat 349E excavator bucket- (6) 1/2" ø, 1×8", 1/2×4", (2) 1×60", 3×8".

Cell 99

Sheet is covered w/ hardened grout from elv. 7.0' to 3.0'.

Damage Location (ft below top of sheet, inboard side, outboard side): 1-15' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and treated as repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-20

Extact ID:

Date Exposed: 8/5/14

Describe Damage: (8) Scrapes by the Cat 349E excavator bucket- (4) 1" ø, 1×36", 1/2×60", (2) 1×12".

Cell 99

Sheet is covered w/ hardened grout from elv. 6.0' to 1.0'

Damage Location (ft below top of sheet, inboard side, outboard side): 4-15' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and treated as repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-21

Entact ID:

Date Exposed: 8/6/14

Describe Damage: (6) Scrapes by the Cat 349E excavator bucket - 1"ø, 1"x24", 1x36", 1x12", 1/2x6", 3"ø. Cell 99

Damage Location (ft below top of sheet, inboard side outboard side): 2-12' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-22

Entact ID:

Date Exposed: 8/6/14

Describe Damage: (8) Scrapes by the Cat 349E excavator bucket - 1/2x12", 1/2x12", 1/2x8", 1/4x18", 4"ø, 1x6", 1/2"ø, 1/2x3". Cell 98

Damage Location (ft below top of sheet, inboard side outboard side): 2x12' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-23

Entact ID:

Date Exposed: 8/6/14

Describe Damage: (5) scrapes by the Cat 349E excavator bucket - 1x36", 1/2x8", 1x8", 1/2x48", 1/4x24". Cell 98.

Damage Location (ft below top of sheet, inboard side outboard side): 4-10' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-24

Entact ID:

Date Exposed: 8/6/14

Describe Damage: (12) Scrapes by the Cat 349E excavator bucket - (2) 1/2x14", 10"ø, 1/2x3", 1/2x6", 1/2x10", 1"ø, 1/2"ø, 2"ø, 1/2x36", 1"ø, 1/2x6". Cell 98

Damage Location (ft below top of sheet, inboard side outboard side): 2-10' outboard

Date Repaired: 8/6/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-25

Extact ID:

Date Exposed: 8/7/14

Describe Damage: (7) Scrapes by the Cat 349E excavator bucket - 1/2x48", (2) 1"ø, 1/2x12", 2x6", 2"ø, 1x12", Cell 97

Damage Location (ft below top of sheet, inboard side, outboard side): 3-13' outbaard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log shall be completed for each sheet pile section that is exposed and repaired if repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-26

Extact ID:

Date Exposed: 8/7/14

Describe Damage: (6) Scrapes by the Cat 349E excavator bucket - (2) 1"ø, 1/2x18", 1/2x24", 1/2x8", 1x24". Cell 97

Damage Location (ft below top of sheet, inboard side, outboard side): 8-13' outboard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log shall be completed for each sheet pile section that is exposed and repaired if repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-27

Extact ID:

Date Exposed: 8/7/14

Describe Damage: (4) Scrapes by the Cat 349E and Cat 322C excavator buckets - 1/4x3", 1/2x4", 1/2x6", 1"ø. Cell 97. Sheet is covered w/ hardened grout from elv. 7.0' to (4.0')

Damage Location (ft below top of sheet, inboard side, outboard side): 10-14' outboard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure washed, wire brushed, applied epoxy w/ 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log shall be completed for each sheet pile section that is exposed and repaired if repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-28

Extact ID:

Date Exposed: 8/7/14

Describe Damage: (8) Scrapes by the Cat 349E and Cat 322C excavator buckets - 1/2x36", 1/2x24", 1"ø, 1x12", 1x12", 2x8", 1x14", 1/2"ø. Cell 96.

Damage Location (ft below top of sheet, inboard side, outboard side): 10-14' outboard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure washed, wire brushed, applied epoxy w/ 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log shall be completed for each sheet pile section that is exposed and repaired if repair

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-29

Entact ID:

Date Exposed: 8/8/14

Describe Damage: (7) Scrapes by the Cat 349E and Cat 322C excavator buckets- 1/2x36", 1"ø, 1x6", 12"ø, 1/2x48", 1x18", 1/2x24". Cell 96.

Damage Location (ft below top of sheet, inboard side outboard side): 10-14' outboard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-30

Entact ID:

Date Exposed: 8/8/14

Describe Damage: (9) scrapes by the Cat 349E and Cat 322C excavator buckets- 2"x60", 1x36", 1x24", 10"ø, 1x30", 2"ø, 1x18", 1/2x36", 1/2x12"! Cell 96

Damage Location (ft below top of sheet, inboard side outboard side): 2-14' outboard.

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-31

Entact ID:

Date Exposed: 8/8/14

Describe Damage: (5) scrapes by the Cat 349E and Cat 322C excavator buckets- 1x36", 1x12", 2"ø, 2x12", 1/2x24", cell 96/95

Damage Location (ft below top of sheet, inboard side outboard side): 6-15' outboard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: BranShea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 19P-32

Entact ID:

Date Exposed: 8/8/14

Describe Damage: (4) Scrapes by the Cat 349E excavator bucket - 1/2x60", 3"ø, 1x24", 1x12", Cell 95.

Damage Location (ft below top of sheet, inboard side outboard side): 6-15' outboard

Date Repaired: 8/13/14 Partial, 8/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply, epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/15/14

A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-33

Entact ID:

Date Exposed: 8/11/14

Describe Damage: (8) Scrapes by the Cat 349E and Cat 322C excavator buckets- 1/2×2", 1×8", 1/2×4", 1×48", 3"Ø, 6"Ø, 2"×48", 1×12", Cell 95

Damage Location (ft below top of sheet, inboard side outboard side): 2-15' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-34

Entact ID:

Date Exposed: 8/11/14

Describe Damage: (16) Scrapes by the Cat 349E and Cat 322C excavator buckets- 1×36", 1×48", 2"Ø, 3×8", 1×3", 1×8", 1/2"Ø, 1"Ø, 1×4", 1/4×6", (2) 2"Ø, 1×2", 1/2×36", 1/2"Ø, 1"Ø. Cell 95

Damage Location (ft below top of sheet, inboard side outboard side): 4-15' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-35

Entact ID:

Date Exposed: 8/11/14

Describe Damage: (8) scrapes by the Cat 349E and 322C excavator buckets- 4×12", 1×12", 2×48", 1×18", 1/4×12", 3"Ø, 1/2×18", 1"Ø. Cell 94

Damage Location (ft below top of sheet, inboard side outboard side): 1-13' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Brian Shea

Describe Repair: pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-36

Entact ID:

Date Exposed: 8/11/14

Describe Damage: (10) scrapes by the Cat 349E and Cat 322C excavator buckets- 1×6", 1/2×6", 1"Ø, 1/2×36", 1/2×12", 2×5", 2×48", 1×18", 1×24", 2×36". Cell 94

Damage Location (ft below top of sheet, inboard side outboard side): 1-15' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-37

Entact ID:

Date Exposed: 8/11/14

Describe Damage: (8) scrapes by the Cat 349E and Cat 322C excavator buckets- 2"Ø, 2×48", 1×6", 1"Ø, 1/2×12", 1/2×24", 1/2×3", 1/2×12"; Cell 94

Damage Location (ft below top of sheet, inboard side outboard side): 4-14' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-38

Entact ID:

Date Exposed: 8/13/14

Describe Damage: (10) scrapes by the Cat 349E and Cat 322C excavator buckets- 2"Ø, (3)1"Ø, 1/2×60", 1/2×6", 3×24", 1/2×12", 1/2"Ø, 1/2×2"; Cell 93

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-39

Entact ID:

Date Exposed: 8/13/14

Describe Damage: (9) Scrapes by the Cat 349E and Cat 322C excavator buckets- 7×24", 2×10", 1×3", (2)1×24", 1/2×48", 2"Ø, 3'Ø, 1/4×4"; Cell 93

Damage Location (ft below top of sheet, inboard side outboard side): 6-14' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-40

Entact ID:

Date Exposed: 8/13/14

Describe Damage: (11) Scrapes by the Cat 349E and Cat 322C excavator buckets- (6)1"Ø, (2)1/2×24", 1/2×14", 1×3", 3'Ø. Cell 93/92

Damage Location (ft below top of sheet, inboard side outboard side): 4-15' outboard

Date Repaired: 8/15/14 Partial, 8/21/14 total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-41
Entact ID:
Date Exposed: 8/14/14
Describe Damage: (12) Scrapes by the Cat 349E and 322C excavator buckets- (5) 1"Ø, 1/2×12", 1/2×18", 2×12", 2×6", 1×36", (2) 3"Ø. Cell 92

Damage Location (ft below top of sheet, inboard side outboard side): 4-14' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-42
Entact ID:
Date Exposed: 8/14/14
Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets- (2) 1/2×3", 1/2×24", (2) 1×48", 1×24", 3×8", 1/2×6". Cell 92

Damage Location (ft below top of sheet, inboard side outboard side): 2-14' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-43
Entact ID:
Date Exposed: 8/14/14
Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets- 1×36", 1/2×6", 1/2×4", 1×2", 1×12", (3) 1"Ø. Cell 92

Damage Location (ft below top of sheet, inboard side outboard side): 1-14' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-44
Entact ID:
Date Exposed: 8/14/14
Describe Damage: (9) Scrapes by the Cat 349E and 322C excavator buckets- (2) 2"Ø, 3"Ø, 1/2×8", (2) 1/2×6", 1×36", 2×5", 1/2×3". Cell 92/91

Damage Location (ft below top of sheet, inboard side outboard side): 2-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-45

Entact ID:

Date Exposed: 8/18/14

Describe Damage: (4) Scrapes by the Cat 349E and 322C excavator buckets - (2) 3"Ø, 1×24", 1/2×12". Cell 91

Damage Location (ft below top of sheet, inboard side outboard side): 7-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: AP-46

Entact ID:

Date Exposed: 8/18/14

Describe Damage: (3) Scrapes by the Cat 349E and 322C excavator buckets - 1×6", 1×12", 1/4"×6". Cell 91

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-47

Entact ID:

Date Exposed: 8/18/14

Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets - (5) 1"Ø, 1×8", 1/2×6", 1/2×12". Cell 91

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-48

Entact ID:

Date Exposed: 8/18/14

Describe Damage: (13) Scrapes by the Cat 349E and 322C excavator buckets - (2) 1/2×18", 2×6", 6×12", (5) 1"Ø, (3) 1/2"Ø, 1×8". Cell 90

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-49

Entact ID:

Date Exposed: 8/18/14

Describe Damage: (8) Scrapes by the Cat 349E excavator bucket- (2) 1"Ø, 2x12", 1/2x12", 1/4x4", 1/4"x8", 1x3", 1x12", Cell 90

Damage Location (ft below top of sheet, inboard side outboard side): 4-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-50

Entact ID:

Date Exposed: 8/18/14

Describe Damage: (11) Scrapes by the Cat 349E and 322C excavator buckets- (3) 1"Ø, 1x12", 1x36", 1x18", 1/4x12", (2) 2x4", 1/2x24", 1/2x3", Cell 90

Damage Location (ft below top of sheet, inboard side outboard side): 4-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-51

Entact ID:

Date Exposed: 8/19/14

Describe Damage: (10) Scrapes by the Cat 349E and 322C excavator buckets- 1/4x4", 1/2x12", 1/2x14", 2"Ø, 1"Ø, 1x18", 1/2x3", 1/2x6", 1/2x6", 1"Ø, 1/2"Ø. Cell 90/89.

Damage Location (ft below top of sheet, inboard side outboard side): 4-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-52

Entact ID:

Date Exposed: 8/19/14

Describe Damage: (14) Scrapes by the Cat 349E and 322C excavator buckets- 12"Ø, (4) 1"Ø, 1x36", 1x12", 1/2x36", (4) 1/2x4", 1/4x6", 1/2"Ø. Cell 89

Damage Location (ft below top of sheet, inboard side outboard side): 4-15' outboard

Date Repaired: 8/20/14 Partial, 8/21/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 8/21/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

## Attachment 11:  Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 31, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/31/14

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Thursday, July 31, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Pretrenching and other activities along the western end of Kellogg Street may result in material or sediment washing into the street during storm events. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing around the Contamination Reduction Zone on SA-6 South requires maintenance. |
| 3 | IA2Q4A1AL8 | Surcharge material at the west end of the SA-6 South cap area is close to the top of the sheet pile containment and erosion run-off from a storm may result in material washing into the backfill area or onto SA-7. |
| 4 | IA2Q4A1AL8 | Used PPE is being stockpiled in plastic garbage bags at various locations throughout SA-6 South |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 07/31/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt dams or other erosion control measures along the southern perimeter of the pre-trench work zone to prevent sediment run-off onto Kellogg Street. | |
| 2 | Repair EZ fencing around the CRZ. | 8-1-14 RAD |
| 3 | Install erosion control measures around the cap area EZ on SA-6 south as required to prevent sediment run-off onto the excavation area or SA-7. | 8-4-14 RAD |
| 4 | Stockpile used PPE bags in one protected location. Dispose of the material as soon as practical. | 8-5-14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 08/05/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 7, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | X | | 3 |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 6 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 7 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/07/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, August 07, 2014

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | silt fence installation is not yet complete along the top of Cap Area S-1 |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing around the Exclusion Zone and the Contamination Reduction Zone at the western end of SA-6 South requires maintenance. The CRZ should be labelled with additional signs. |
| 3 | IA2Q4A1AL8 | Sections of flood protection for the western excavation were lost when Entact removed te temporary sheet pile in that area. |
| 4 | IA2Q4A1AL8 | A soil pile associated with the relocation of a Kellogg Street fire hydrant blocks parking spaces in the employee parking area. |
| 5 | IA2Q4A1AL8 | Roadways and ramps on the N-1 Surcharge Area require additional delineation. |
| 6 | IA2Q4A1AL8 | Drums and other miscellaneouse debris are located on SA-6 North. |
| 7 | IA2Q4A1AL8 | Drums and hoses are located near the recently-modified FLUT well on SA-7 |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ Signature **Date:** 08/07/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Complete the silt fence installation to prevent run-off of sediment from the cap area. | 8-11-14 RAD |
| 2 | Repair/maintain EZ fencing. Reconfigure the CRZ into a well-labelled corridor between the EZ and the support zone. | 8-11-14 RAD |
| 3 | Evaluate the excavation area for flood protection requirements and determine a procedure for implementation in the event of a major weather event. | 8-8-14 RAD |
| 4 | Remove the soil pile | 8-8-14 RAD |
| 5 | Place traffic cones or other forms of delineation along the eastern ramp and along the top of the southern face of Surcharge Area N-1. | 8-11-14 RAD |
| 6 | Remove the drums to a central staging area. | 8-8-14 RAD |
| 7 | Remove the drums to a central staging area. Pick up the hoses. | 8-8-14 RAD |
| | | |

**Construction Manager:** _____ **Date:** 08/12/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 14, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 2 |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 5 |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

NOTE: All comments are numbered for reference and included on the included comment section.

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/14/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, August 14, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Water has accumulated in the secondary containment of the Entact waste oil tank. |
| 2 | IA2Q4A1AL8 | The Entact conex box contains several unlabeled plastic containers dry chemical. |
| 3 | IA2Q4A1AL8 | Sediment control measures at the Exclusion Zone entrance for the western excavation area are inadequate. |
| 4 | IA2Q4A1AL8 | Many of the steel drums located in the eastern end of the Exclusion Zone and elsewhere on the site are damaged and no longer servicable. |
| 5 | IA2Q4A1AL8 | Lengths of lay-flat hose remain on the ground at the SA-7 southwest spillway |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 08/14/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove the accumulated storm water from the secondary containment. | 8-18-14 RAD |
| 2 | Properly label the chemical containers or else remove them from the site. | 8-18-14 RAD |
| 3 | Instal silt dams or other comperable measures to prevent sediment from leaving the EZ during storm events. | 8-20-14 RAD |
| 4 | Discard of any drums on site which are no longer used due to damge. | 8-15-14 RAD |
| 5 | Remove the lengths of hose. | 8-18-14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 08/20/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 22, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☑ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 2 |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 4 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/22/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Friday, August 22, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Orange Exclusion Zone fencing requires is damaged at several locations around the Study Area 6 South EZ. |
| 2 | IA2Q4A1AL8 | A 55 gallon drum containing lubricant is improperly stored on a broken pallet in the mechanics area on SA-6 South. |
| 3 | IA2Q4A1AL8 | Windscreen on the perimeter fence at the Kellogg Street jughandle is detached at the bottom. |
| 4 | IA2Q4A1AL8 | Following last night's rain event, stormwater has ponded on the western end of Kellogg Street. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ Signature **Date:** 08/22/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the orange EZ fencing as required. | 8/25/14 RAD |
| 2 | Remove the broken pallet and store the drum properly (on a spill pallet if it is currently in use). | 8/25/14 RAD |
| 3 | Re-attach the windscreen material along the bottom edge. | 8/25/14 RAD |
| 4 | Pump the ponded storm water into the site for handling. | 8/25/14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 08/25/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 28, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | X | | 1 |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 3 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | X | | 4 |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/29/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, August 28, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | There are insufficient erosion control measures present between the recently-installed surcharge material on the outside of the SA-6 South hydraulic barrier and the swale in the northwestern corner of SA-6 South. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing surrounding the material stockpiles on the south side of the excavation is not continuous and the Exclusion Zone is open on the western perimeter. |
| 3 | IA2Q4A1AL8 | Storm water has accumulated in the secondary containment of the waste oil storage tank. |
| 4 | IA2Q4A1AL8 | Flood control measures are inadequate around the excavation and stockpile areas on SA-6 South. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 08/29/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install a sufficient sediment check dam or silt fencing across the top of the SW corner swale which leads to the Hackensack River. | 9/2/14 RAD |
| 2 | Install EZ fencing to properly delineate the perimeter of the Exclusion Zone. | 9/3/14 RAD |
| 3 | Remove the accumulated storm water from the secondary containment basin, restoring it's capacity to a full tank volume. | 9/3/14 RAD |
| 4 | Install/repair/update flood control measures on SA-6 South to meet contract requirements. Perform elevation checks on measures to confirm the they meet specs. | 9/3/14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 09/03/14

## Attachment 12: GWTP Update

- 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (July 2014)
- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (July 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

August 14, 2014

New Jersey Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: July 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the July 2014 Surface Water Discharge Monitoring Report for Outfall 001A. Please note that there was no discharge this monitoring period.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Frank Schroyer - Parsons

New Jersey Department of Environmental Protection
Division of Water Quality

PI 234822

# Surface Water Discharge Monitoring Report Submittal Form

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 7 | 1 | 2014 | To | 7 | 31 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☒ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J Morris, Remediation Director — —

**NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **GRADE AND REGISTRY NUMBER (IF APPLICABLE)**

John J Morris — 8/14/2014 — 973-455-4003

**SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR** | **DATE** | **AREA CODE/PHONE NUMBER**

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J. Morris, Remediation Director — John J Morris — 8/14/2014 — 973-455-4003

**NAME AND TITLE** | **SIGNATURE** | **DATE** | **AREA CODE/PHONE NUMBER**

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 7/1/2014 TO 7/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | | | GPD | ****** | ****** | ****** | ****** | | | |
| | PERMIT REQUIREMENT | REPORT 01MOAV | REPORT 01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | | SU | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0 01MOMN | ****** | 9.0 01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 50 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10 01MOAV | 15 01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 20 01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 7/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 7/1/2014 TO 7/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Month | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 7/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 7/1/2014 TO 7/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable 01119 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr) 01220 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable 71901 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 0.025 01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride 32102 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.8 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform 32106 2 Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 46 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene 39180 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 54 01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 7/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 7/1/2014 TO 7/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | | | | | | | | | | |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

August 14, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the July 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 7 | 01 | 14 | 7 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,957 | 84,291 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.91 | 0.98 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.0941 | 0.0941 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris
Signature of Principal
Executive or Authorized Agent

John J. Morris
Remediation Portfolio Director
Type Name and Title

8/14/14
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 7 | 01 | 14 | 7 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,416,653 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 12,913,622 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 7/22/2014 | <10 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 8/14/14 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | MONTH: July 2014 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 7/1/2014 | Angel Trujillo | 10496969 | 10575542 | 78,573 | 0.078573 | 7.22 | 1.400 | | | | | | | | | 0.92 |
| 7/2/2014 | Angel Trujillo | 10575542 | 10654885 | 79,343 | 0.079343 | 7.54 | 1.400 | | | | | | | | | 0.93 |
| 7/3/2014 | Angel Trujillo | 10654885 | 10732944 | 78,059 | 0.078059 | 7.85 | 1.400 | | | | | | | | | 0.91 |
| 7/4/2014 | Angel Trujillo | 10732944 | 10816023 | 83,079 | 0.083079 | 7.53 | 1.400 | | | | | | | | | 0.97 |
| 7/5/2014 | Angel Trujillo | 10816023 | 10871944 | 55,921 | 0.055921 | 7.89 | 1.400 | | | | | | | | | 0.65 |
| 7/6/2014 | Angel Trujillo | 10871944 | 10941902 | 69,958 | 0.069958 | 7.64 | 1.400 | | | | | | | | | 0.82 |
| 7/7/2014 | Angel Trujillo | 10941902 | 11015239 | 73,337 | 0.073337 | 7.57 | 1.400 | | | | | | | | | 0.86 |
| 7/8/2014 | Angel Trujillo | 11015239 | 11094128 | 78,889 | 0.078889 | 7.96 | 1.400 | | | | | | | | | 0.92 |
| 7/9/2014 | Angel Trujillo | 11094128 | 11173903 | 79,775 | 0.079775 | 7.65 | 1.400 | | | | | | | | | 0.93 |
| 7/10/2014 | Angel Trujillo | 11173903 | 11250619 | 76,716 | 0.076716 | 7.80 | 1.400 | | | | | | | | | 0.90 |
| 7/11/2014 | Angel Trujillo | 11250619 | 11331169 | 80,550 | 0.08055 | 7.68 | 1.400 | | | | | | | | | 0.94 |
| 7/12/2014 | Angel Trujillo | 11331169 | 11414478 | 83,309 | 0.083309 | 7.83 | 1.400 | | | | | | | | | 0.97 |
| 7/13/2014 | Angel Trujillo | 11414478 | 11492799 | 78,321 | 0.078321 | 7.54 | 1.400 | | | | | | | | | 0.91 |
| 7/14/2014 | Angel Trujillo | 11492799 | 11569859 | 77,060 | 0.07706 | 7.59 | 1.400 | | | | | | | | | 0.90 |
| 7/15/2014 | Angel Trujillo | 11569859 | 11650526 | 80,667 | 0.080667 | 7.57 | 1.400 | | | | | | | | | 0.94 |
| 7/16/2014 | Angel Trujillo | 11650526 | 11728824 | 78,298 | 0.078298 | 7.84 | 1.400 | | | | | | | | | 0.91 |
| 7/17/2014 | Angel Trujillo | 11728824 | 11805272 | 76,448 | 0.076448 | 7.43 | 1.400 | | | | | | | | | 0.89 |
| 7/18/2014 | Angel Trujillo | 11805272 | 11883969 | 78,697 | 0.078697 | 7.33 | 1.400 | | | | | | | | | 0.92 |
| 7/19/2014 | Angel Trujillo | 11883969 | 11965276 | 81,307 | 0.081307 | 7.35 | 1.400 | | | | | | | | | 0.95 |
| 7/20/2014 | Angel Trujillo | 11965276 | 12044437 | 79,161 | 0.079161 | 7.34 | 1.400 | | | | | | | | | 0.92 |
| 7/21/2014 | Angel Trujillo | 12044437 | 12120280 | 75,843 | 0.075843 | 7.24 | 1.400 | | | | | | | | | 0.89 |
| 7/22/2014 | Angel Trujillo | 12120280 | 12198999 | 78,719 | 0.078719 | 7.34 | 1.400 | <5.0 | <10 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | 0.92 |
| 7/23/2014 | Angel Trujillo | 12198999 | 12268740 | 69,741 | 0.069741 | 7.28 | 1.400 | | | | | | | | | 0.81 |
| 7/24/2014 | Angel Trujillo | 12268740 | 12349396 | 80,656 | 0.080656 | 7.39 | 1.400 | | | | | | | | | 0.94 |
| 7/25/2014 | Angel Trujillo | 12349396 | 12427044 | 77,648 | 0.077648 | 7.24 | 1.400 | | | | | | | | | 0.91 |
| 7/26/2014 | Angel Trujillo | 12427044 | 12511335 | 84,291 | 0.084291 | 7.31 | 1.400 | | | | | | | | | 0.98 |
| 7/27/2014 | Angel Trujillo | 12511335 | 12593097 | 81,762 | 0.0818 | 7.37 | 1.400 | | | | | | | | | 0.95 |
| 7/28/2014 | Angel Trujillo | 12593097 | 12670158 | 77,061 | 0.077061 | 7.38 | 1.400 | | | | | | | | | 0.90 |
| 7/29/2014 | Angel Trujillo | 12670158 | 12752346 | 82,188 | 0.082188 | 7.64 | 1.400 | | | | | | | | | 0.96 |
| 7/30/2014 | Angel Trujillo | 12752346 | 12833164 | 80,818 | 0.080818 | 7.30 | 1.400 | | | | | | | | | 0.94 |
| 7/31/2014 | Angel Trujillo | 12833164 | 12913622 | 80,458 | 0.080458 | 7.32 | 1.400 | | | | | | | | | 0.94 |
| TOTAL | | | | 2,416,653 | 2.416653 | | | <5.0 | <10 | | <0.010 | <0.015 | <0.010 | <0.0002 | ≤0.020 | |
| | | | High: | 84,291 | | | | | | | | | | | High: | 0.98 |
| | | | Average: | 77,957 | | | | | | | | | | | Average: | 0.91 |

WW

JB72245

E

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 41842.41914
COC#: 072214
Lab Proj # (SDG):
Lab ID: PCTD
Site ID:
Lab Job #: HWNJM32815
Authorized User: Honeywell

Site Name: Hudson County
Location of Site: Jersey City, NJ
Phase:
Sampling Program: 087: JCIA
CS

Company: Parsons
Contact: (name, co., address)
ph P: (973) 455-2969 E: helen.fahy@honeywell.com
ll International
mble Road Morristown, NJ 07962
Copy To: Helen Fahy (Honeywell)
To: Helen Fahy (Honeywell)

EDD To:
Sampler: Frank Schroyer
PO #
Analysis Turnaround Time (TAT): 3
Consultant: CH2M
Full Report TAT: 28 Days

Preservative: 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2

| Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Units | | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| ation ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | | | | | | | | | | | | | | |
| 087-WW | | | 087-WWE-072214-A | 7/22/2014 | 14:45 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | pH = 7.34 FLS | |
| 087-WW | | | 087-WWE-072214-B | 7/22/2014 | 14:40 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | |
| 087-WW | | | 087-WWI-072214 | 7/22/2014 | 15:00 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | L27 |
| | | | | | | | | | | | | | | | | | | | | | | | V1217 |
| | | | | | | | | | | | | | | | | | | | | | | | A7 |
| | | | | | | | | | | | | | | | | | | | | | | | C45 |

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE JK

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Relinquished by: pH = 7.34 FLS | Company: Parsons | Received by: | Company: Accutest | Condition: | | Custody Seals Intact: V | #109 |
| Relinquished by: | Date/Time: 7/22/14 | Received by: | Date/Time: 7/22/14/16W | Cooler Temp.: | 2.5°C | | |
| Relinquished by: | Company: Accutest | Received by: | Company: Accutest | Condition: | | Custody Seals Intact: | |
| | Date/Time: 7/22/14 16:55 | | Date/Time: 7/22/14 1655 | Cooler Temp.: | | | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

A

JK

Accutest LabLink@807560 10:06 31-Jul-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-072214-A | | |
| Lab Sample ID: | JB72245-1 | Date Sampled: | 07/22/14 |
| Matrix: | AQ - Water | Date Received: | 07/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1400 | 10 | ug/l | 1 | 07/23/14 | 07/24/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 07/23/14 | 07/24/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 07/23/14 | 07/24/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 07/23/14 | 07/23/14 | JW | EPA 245.1 [1] | EPA 245.1 [3] |
| Nickel | < 10 | 10 | ug/l | 1 | 07/23/14 | 07/24/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 07/23/14 | 07/24/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA34518
(2) Instrument QC Batch: MA34535
(3) Prep QC Batch: MP80648
(4) Prep QC Batch: MP80810

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@807560 10:06 31-Jul-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-072214-A | | |
| Lab Sample ID: | JB72245-1 | Date Sampled: | 07/22/14 |
| Matrix: | AQ - Water | Date Received: | 07/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 07/24/14 | KP | SM2540 D-11 |
| pH [a] | 7.39 | | su | 1 | 07/22/14 17:36 | MB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@807560 10:06 31-Jul-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-072214-A | | |
| Lab Sample ID: | JB72245-1A | Date Sampled: | 07/22/14 |
| Matrix: | AQ - Water | Date Received: | 07/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



## General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 10 | 10 | mg/l | 1 | 07/23/14 16:24 | KP | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@807560 10:06 31-Jul-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-072214-B | | |
| **Lab Sample ID:** | JB72245-2 | **Date Sampled:** | 07/22/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/22/14 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N237060.D | 1 | 07/23/14 | DC | n/a | n/a | VN10060 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA PPL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.7 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.9 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.27 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 20.2 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.8 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.62 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 60.0 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.6 | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 98% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 98% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 100% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 101% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@807560 10:06 31-Jul-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-072214-B | | |
| Lab Sample ID: | JB72245-2 | Date Sampled: | 07/22/14 |
| Matrix: | AQ - Water | Date Received: | 07/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 07/23/14 | LS | EPA 1664A |

RL = Reporting Limit

## Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending August 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to Contractor only. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 6 OF 25**

- **2014 Monthly Reports Part 6**

**10/14/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

October 14, 2014 ***Via Express Mail***

Honorable Robert G. Torricelli
Office of the Special Master
49 Bridge Street, Suite 2
Lambertville, NJ 08530

**Subject: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-09**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from September 1 – September 30, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: September 2014 SA-6/7 Combined Monthly Progress Report No. 2014-09

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-09

**Project SA-6 & 7 Remediation**

## September 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 09/02/14 | Droyers Cove Beneficial Environmental Project Pre-Application Meeting<br>Study Area 7 Sediment, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/04/14 | Design Change Bulletin: Re-align Barrier Wall Due to 72 in. FM Field Verified Location<br>Study Area 6 North/South, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/05/14 | Summary of In-Situ Treatment of Hexavalent Chromium Impacted Soils (Site 163)<br>Study Area 6 South Chromium Remedy, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/05/14 | Incident No. 14-08-15-1405-34<br>Chromium Site 163 (aka Colonial Concrete Company)<br>NJDEP PI#010374<br>75 Kellogg Street<br>Study Area 6 South, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/12/14 | SA-6 North Treatability – Areas 7 & 8<br>CAS Injection Test Results<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/12/14 | Combined Monthly Progress/Highlights Report No. 2014-08<br>Study Areas 6 and 7, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/15/14 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014<br>*(see **Attachment 12**)* | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 09/15/14 | NJPDES Permit NJ0156311: August 2014 Surface Water Discharge Monitoring Report<br>Study Area 7, Jersey City, NJ<br>*(see **Attachment 12**)* | New Jersey Department of Environmental Protection<br>Division of Water Quality |
| 09/15/14 | Response to Plaintiffs' Comments on Study Area 6 | Honorable Robert G. Torricelli |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| | North and South Request for Variance for Asphalt Consolidation and Proposed Revisions to Study Area 6 North and South Soil Management Plan (Arnold & Porter Correspondence) Jersey City, NJ | Office of the Special Master |
| 09/16/14 | Special Master Meeting | N/A |
| 09/22/14 | Study Area 6 South Consent Decree - Excavation Completion of Cells 100-104A Jersey City, NJ | The Honorable Robert G. Torricelli Office of the Special Master |
| 09/24/14 | Study Area 6 (SA-6) North Treatability Program Bench Scale System Set Up Jersey City, NJ | The Honorable Robert G. Torricelli Office of the Special Master |
| 09/24/14 | New Source of Imported Clean Fill Study Area 6 (SA-6) Jersey City, NJ | The Honorable Robert G. Torricelli Office of the Special Master |
| 09/30/14 | Surcharge Monitoring Plan – Monthly Report No. 5 Study Area 6 North/South Jersey City, NJ | Honorable Robert G. Torricelli Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 9/7/14 | 9/14/14 | 9/21/14 | 9/28/14 |
| **Construction Management (AMEC)** | 11 | 11 | 11 | 12 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 47 | 49 | 49 | 47 |
| **Arecon/US Ecology Subcontractors** | 1 | 0 | 1 | 1 |
| **ERFS In Situ Treatment** | 1 | 0 | 0 | 0 |
| **Summit Drilling** | 1 | 0 | 0 | 0 |
| **Siemens** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 0 | 1 |
| **TOTAL** | **67** | **66** | **67** | **67** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Collected September PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed S-3 Injection/Mass Removal Event #17 in well 088-IW-02.
- Conducted Pre-construction meeting for the Above-grade Demolition of the four designated JCIA Structures on September 4, 2014.
- Issued Limited Notice to Proceedto the JCRA demolition contractor on September 17, 2014.
- Collected groundwater parameter measurements from 15 selected temporary well points associated with the in situ treatment activities at Site 163.
- Abandoned all 57 temporary well points associated with the in situ treatment activities at Site 163.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 2**0**1 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on September 11, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 9/7/14 | 9/14/14 | 9/21/14 | 9/28/14 |
| Avg. Gallons Treated & Discharged (per day) | 77,717 | 76,980 | 77,592 | 76,809 |
| Average Flow (gpm) for Operating Period | 55 | 53 | 55 | 54 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP InfluentTanks (gal.) | 10,116 | 5,760 | 6,720 | 5,877 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued excavation activities in cells 83-73.
- Continued storm-water management activities.
- Continued delineation activities associated with anomalous material in the southern portion of Cell 105. A summary of the results and boring locations is presented on attached figure.
- On September 23, 2014, an abatement contractor was mobilized to remove a total of 800 sq. ft.of ceramic and mastic ACM from the former footprint of the concrete plant garage.

- Excavated approximately 100 cubic yards of soil outside the temporary sheets as part of the non-chromium remedy.
- Continued installation of the Contingent Groundwater Extraction System Pipe.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

## 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 21.35 | 21.35 |
| **Entact/ Horowith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 20 | 21.33 | 426.68 |
| **Entact/ Montecalvo** | 30 cyd roll-off | Bayshore Recycling | NA | Non Haz Creosote Debris | 3 | 13.01 | 39.03 |

## 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 83-73 |
| **Excavation Completed** | Cell Number(s) 84-76<br>Volume Excavated - Total for Reporting Period: 14,495CY/ Total to Date: 117,122 CY |
| **Backfill in Progress** | Cell Number(s) 104-76 |

## 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 9/7/14 | 9/14/14 | 9/21/14 | 9/28/14 |
| <20ppm re-use, CY | 0 | 68 | 721 | 720 |
| Weldon, Import-Tons Screenings | 3,245 | 4,367 | 2,073 | 4,666 |
| Tilcon, Import-Tons DGA | 608 | 0 | 0 | 0 |
| Tilcon, Import Tons – 1.5” Stone | 0 | 254 | 0 | 178 |
| Weldon, Imported Tons - QP | 590 | 1,221 | 1,999 | 0 |
| Weldon, Imported Tons - DGA | 0 | 0 | 0 | 0 |
| Celgene - Loads | 0 | 0 | 0 | 0 |
| Tilcon, Imported Tons – 2.5” Stone | 0 | 0 | 309 | 0 |

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharge continued with placement of imported Celgene soils between the subgrade and surcharge design grade. Surcharge placement is approximately 95% complete.
- Area 2S: Surcharging continued from 1S into the western portion of 2S. Surcharge placement consisted of both chromium impacted soils to the design subgrade and imported Celgene soils and is approximately 50% complete.
- Area 3S: Instrumentation installation was completed as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles are located in this area. No Surcharge has been initiated.
- Area 1N: Began Surcharge removal activities on 8/29/14. Surcharge removal activities area approximately 50% complete. Details were provided in the September Surcharge Monitoring Report No. 5.
- Area 2N: Instrumentation Installation 100% complete. Surcharge being removed from Area 1N is being relocated to Area 2N. Surcharge placement is approximately 60% complete.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- A total of 14 pair of sheet pile was driven on SA6 North from Sta14+00 to 14+60.

## G. PERMIT STATUS

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 | Pending | Pending | Pending |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 | Pending | Pending | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete final walkthrough of the Jersey City Incinerator Authority structures with representatives from JCIA and JCRA.
- Begin mobilization activities for the above grade demolition of the four designated JCIA Structures.
- Continue placement of surcharge materials in SA-6S Area 1S and 2S.
- Continue off loading of surcharge materials from SA-6N Area 1N.
- Continue placement of surcharge materials in SA-6N Area 2N.
- Continue installation of the contingent groundwater system trench on SA-6S.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Continue excavation activities in SA-6S Cells 71-59.
- Continue stockpiling of presumed <20 mg/kg for additional sampling.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Begin excavation activities associated with Site 163.
- Continue dewatering and storm-water management activities.
- Conduct S-3 Injection/Mass Removal Event No. 18 in injection well to be determined.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Begin cap thickness verification inspections, pore water sampling, bathymetric surveys and biological sampling of SA7 sediments pursuant to Long Term Monitoring Plan.

**ATTACHMENTS:**


1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Lens of Anomalous Material – Supplemental Boring Locations
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-3)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. Groundwater Quality Data Surcharge Monitoring Update
   - Summary of Groundwater Quality Data from GWET Wells
   - Quarterly Water Wells
   - Trichloroethene/Chloroform/Hexavalent Chromium in GWET Wells
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Deflection Along Open Excavation
    - Sheet Monitoring Locations
    - Sheet Pile Repair Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (August 2014)
    - 9/15/14 NJDEP Correspondence re: Administrative Revocation NJDPES Permit #NJG0156311
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (August 2014)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

September 2014 SA-6/7 Progress Report
Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Thu 10/2/14

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Contractor backfilling excavations on Kellogg St. property.




**Site Photograph 2:** Contractor completing excavation segment on Kellogg St. property.




**Site Photograph 3:** Contractor Demolishing a foundation on Kellogg St. property 9/17/14.




**Photograph 4:** Contractor places surcharge soils on Kellogg St Property.




**Site Photograph 5:** Contractor places surcharge soils on Jersey City Property.





**Site Photograph 6:** Loading soils for onsite transport.

## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
- Lens of Anomalous Material – Supplemental Boring Locations
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies
# Progress as of October 1, 2014

September 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill




## Legend


- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete




LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM O EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE
- LIMIT OF EXCAVATION AREA
- TOE OF CHLOROBENZENE AREA

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 08-21-14 TO 09-04-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.
Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -0.6 | 134-SB-019 | 114A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.3 | 601878.4 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.5 | 601974.0 | 1.2 | 134-SB-061 | 106A | 7/23/2014 | -5.2 | Stratum D Reached |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.8 | 601978.1 | -7.5 | 134-SB-113 | 103 | 7/29/2014 | -7.2 | Stratum D Reached |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |
| 684908.2 | 602155.7 | -8.0 | 134-SB-049 | 89 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684943.6 | 602214.1 | -6.9 | 140-SB-035 | 88 | 8/25/2014 | -6.7 | Stratum D Reached |
| 684905.5 | 602180.6 | -7.8 | 140-SB-063 | 88 | 8/25/2014 | -6.1 | Stratum D Reached |
| 684875.3 | 602175.3 | -7.8 | 140-SB-062 | 87 | 8/25/2014 | -5.8 | Stratum D Reached |
| 684875.5 | 602187.9 | -7.3 | 140-SB-103 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684915.0 | 602239.0 | -6.1 | 140-SB-007 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |
| 684896.1 | 602229.3 | -6.6 | 140-SB-038 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684862.9 | 602228.0 | -6.1 | 134-SB-032R | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| | | | | | | | |
| | | | | | | | |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | UST Area |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | UST Area |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | UST Area |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |
| 684922.3 | 602179.9 | -4.3 | C-89 | 89 | 8/20/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684912.0 | 602189.2 | -4.3 | C-88 | 88 | 8/25/2014 | -6.3 | Stratum D Reached |
| 684895.8 | 602194.1 | -4.3 | C-87 | 87 | 8/25/2014 | -6.0 | Stratum D Reached |
| 684880.8 | 602203.6 | -4.3 | C-86 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684872.8 | 602212.7 | -4.3 | C-85 | 85 | 8/29/2014 | -5.2 | Stratum D Reached |
| 684862.9 | 602228.0 | -4.3 | C-84 | 84 | 9/4/2014 | -5.6 | Stratum D Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685471.0 | 601475.6 | 4.3 | 073-SB-079 | 148 | 7/31/2014 | 4.3 | Target Elevation Reached |
| 685451.0 | 601460.9 | 7.1 | 073-SB-082 | 148 | 7/31/2014 | 2.2 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Target Elevation Reached |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685094.6 | 601890.3 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 685081.0 | 601928.0 | -0.1 | 134-SB-021 | 109A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 685080.6 | 601935.9 | 3.0 | 134-SB-092 | 108A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Target Elevation Reached |
| 684999.7 | 601940.5 | -0.5 | 134-SB-097 | 104 | 7/29/2014 | -7.2 | Stratum D Reached |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |
| 684887.0 | 602147.0 | -2.1 | 134-SB-100 | 89 | 8/20/2014 | -5.8 | Stratum D Reached |
| 684821.2 | 602190.7 | -4.8 | 140-SB-060 | 84 | 9/4/2014 | -5.2 | Stratum D Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 9/25/14

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

1 120 119 118 117 116 115 114 113 112 111 110 109 108 107 106 105 104 103 102 101 100

HYDRAULIC BARRIER WALL (TYP)

LIMIT OF EXCAVATION (100 PERCENT DESIGN)

134-SB-021 < 20

134-SB-092 < 20

134-SB-075 < 20

134-SB-174 177.0

134-SB-074 < 20

134-SB-169 175.0

134-SB-161 230.0

134-SB-160 848.0

134-SB-162 198.0

134-SB-173 276.0

134-SB-165 < 0.6J

134-SB-097 < 20

134-SB-172 1220.0

134-SB-171 8.6

134-SB-164 57.0

134-SB-168 403.0

134-SB-167 328.0

134-SB-170 19.6

134-SB-166 114.0

134-SB-175 2.2

LEGEND

134-SB-170 19.6 — SUPPLEMENTAL BORING AND HEX CR RESULTS (PPM)

134-SB-075 < 20 — SIDEWALL SAMPLE COLLECTED DURING PDI DELINEATING LIMIT OF EXCAVATION

Prepared/Date: TDD 10/9/14
Checked/Date: DEN 10/9/14

0 5 10 20
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

LENS OF ANOMALOUS MATERIAL
SUPPLEMENTAL BORING LOCATIONS
FIGURE 1

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 4 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | PROCTOR OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | PROCTOR OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 1 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | PROCTOR OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 3 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY


| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | PROCTOR OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | PROCTOR OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.
Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID RF-01-01 where:

RF = Reduced Frequency
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS 5 TESTS PER ACRE

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

# Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-3)

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 08/05/14 | 1 | 4 | 10, 11, 12, EPS | 61 | 0 | 1,893 | 1,893 | 2,356,681 | 7.9 | |
| 08/06/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 1,893 | 23,795 | 21,902 | 2,378,583 | 15.2 | |
| 08/07/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 23,795 | 44,386 | 20,591 | 2,399,174 | 14.3 | |
| 08/08/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 0 | 8,014 | 8,014 | 2,407,188 | 5.6 | |
| 08/11/14 | 1 | 72 | 10, 11, 12, EPS | 61 | 8,014 | 32,057 | 24,043 | 2,431,231 | 5.6 | |
| 08/12/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 32,057 | 40,072 | 8,015 | 2,439,246 | 5.6 | |
| 08/13/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 40,072 | 59,407 | 19,335 | 2,458,581 | 13.4 | |
| 08/14/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 59,407 | 89,000 | 29,593 | 2,488,174 | 20.6 | |
| 08/18/14 | 1 | 72 | 10, 11, 12, EPS | 61 | 0 | 47,911 | 47,911 | 2,536,085 | 11.1 | Flowmeter Reset |
| 08/19/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 47,911 | 61,590 | 13,679 | 2,549,764 | 9.5 | |
| 08/20/14 | 1 | 24 | 10, 11, 12, EPS | 61 | 61,590 | 75,268 | 13,678 | 2,563,442 | 9.5 | |
| 08/21/14 | 1 | 24 | 10, 11, 12, EPS | 50 | N/A | N/A | 14,000 | 2,577,442 | 9.7 | Flowmeter Blockage - Tank Measured |
| 08/22/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 75,268 | 77,640 | 2,372 | 2,579,814 | 1.6 | |
| 08/25/14 | 1 | 72 | 10, 11, 12, EPS | 50 | 0 | 20,218 | 20,218 | 2,600,032 | 4.7 | Flowmeter Reset |
| 08/26/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 20,218 | 42,158 | 21,940 | 2,621,972 | 15.2 | |
| 08/27/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 42,158 | 47,944 | 5,786 | 2,627,758 | 4.0 | |
| 08/28/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 47,944 | 54,589 | 6,645 | 2,634,403 | 4.6 | |
| 08/29/14 | 1 | 24 | 10, 11, 12, EPS | 50 | 54,589 | 61,819 | 7,230 | 2,641,633 | 5.0 | |
| 09/02/14 | 1 | 96 | 10,11,EPS | 41 | 61,819 | 95,797 | 33,978 | 2,675,611 | 5.9 | |
| 09/03/14 | 1 | 24 | 10,11,EPS | 41 | 95,797 | 103,042 | 7,245 | 2,682,856 | 5.0 | |
| 09/04/14 | 1 | 24 | 10,11,EPS | 41 | 103,042 | 111,280 | 8,238 | 2,691,094 | 5.7 | |
| 09/05/14 | 1 | 24 | 10,11,EPS | 41 | 111,280 | 120,132 | 8,852 | 2,699,946 | 6.1 | |
| 09/08/14 | 1 | 72 | 10,11,EPS | 41 | 120,132 | 142,954 | 22,822 | 2,722,768 | 5.3 | |
| 09/09/14 | 1 | 24 | 10,11,EPS | 41 | 142,954 | 149,419 | 6,465 | 2,729,233 | 4.5 | |
| 09/10/14 | 1 | 24 | 10,11,EPS | 41 | 149,419 | 155,362 | 5,943 | 2,735,176 | 4.1 | |
| 09/11/14 | 1 | 24 | 10,11,EPS | 41 | 155,362 | 160,305 | 4,943 | 2,740,119 | 3.4 | |
| 09/12/14 | 1 | 24 | 10,11,EPS | 41 | 160,305 | 165,438 | 5,133 | 2,745,252 | 3.6 | |
| 09/15/14 | 1 | 72 | 10,11,EPS | 41 | 165,438 | 182,610 | 17,172 | 2,762,424 | 4.0 | |
| 09/16/14 | 1 | 24 | 10,11,EPS | 41 | 182,610 | 186,925 | 4,315 | 2,766,739 | 3.0 | |
| 09/17/14 | 1 | 24 | 10,11,EPS | 41 | 186,925 | 191,256 | 4,331 | 2,771,070 | 3.0 | |
| 09/18/14 | 1 | 24 | 10,11,EPS | 41 | 191,256 | 196,210 | 4,954 | 2,776,024 | 3.4 | |
| 09/19/14 | 1 | 24 | 10,11,EPS | 41 | 196,210 | 201,455 | 5,245 | 2,781,269 | 3.6 | |
| 09/22/14 | 1 | 24 | 10,EPS | 20 | 201,455 | 216,358 | 14,903 | 2,796,172 | 10.3 | |
| 09/23/14 | 1 | 24 | 10,EPS | 20 | 216,358 | 220,880 | 4,522 | 2,800,694 | 3.1 | |
| 09/24/14 | 1 | 24 | 10,EPS | 20 | 220,880 | 222,951 | 2,071 | 2,802,765 | 1.4 | |
| 09/25/14 | 1 | 24 | 10,EPS | 20 | 222,951 | 226,142 | 3,191 | 2,805,956 | 2.2 | |
| 09/26/14 | 1 | 24 | 10,EPS | 20 | 226,142 | 230,921 | 4,779 | 2,810,735 | 3.3 | |
| 09/29/14 | 1 | 72 | 10,EPS | 20 | 230,921 | 236,427 | 5,506 | 2,816,241 | 1.3 | |
| 09/30/14 | 1 | 24 | 10,EPS | 11 | 236,427 | 238,184 | 1,757 | 2,817,998 | 1.2 | |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-3)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 08/06/14 | 24 | 0 | 1,340 | 1,340 | 1,340 | 0.9 | |
| 08/07/14 | 24 | 1,340 | 2,525 | 1,185 | 2,525 | 0.8 | |
| 08/08/14 | 24 | N/A | N/A | 5,500 | 8,025 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/11/14 | 72 | N/A | N/A | 17,500 | 25,525 | 4.1 | Flowmeter blockage - Tank Measured |
| 08/12/14 | 24 | 0 | 3,528 | 3,528 | 29,053 | 2.5 | Flowmeter Reset |
| 08/13/14 | 24 | N/A | N/A | 5,500 | 34,553 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/14/14 | 24 | N/A | N/A | 5,000 | 39,553 | 3.5 | Flowmeter blockage - Tank Measured |
| 08/15/14 | 24 | N/A | N/A | 5,500 | 45,053 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/18/14 | 72 | N/A | N/A | 16,500 | 61,553 | 3.8 | Flowmeter blockage - Tank Measured |
| 08/19/14 | 24 | N/A | N/A | 6,000 | 67,553 | 4.2 | Flowmeter Not Installed - Tank Measured |
| 08/20/14 | 24 | N/A | N/A | 6,500 | 74,053 | 4.5 | Flowmeter Not Installed - Tank Measured |
| 08/21/14 | 24 | N/A | N/A | 6,000 | 80,053 | 4.2 | Flowmeter Not Installed - Tank Measured |
| 08/22/14 | 24 | N/A | N/A | 6,250 | 86,303 | 4.3 | Flowmeter Not Installed - Tank Measured |
| 08/25/14 | 72 | N/A | N/A | 17,500 | 103,803 | 4.1 | Flowmeter Not Installed - Tank Measured |
| 08/26/14 | 24 | N/A | N/A | 5,750 | 109,553 | 4.0 | Flowmeter Not Installed - Tank Measured |
| 08/27/14 | 24 | N/A | N/A | 5,700 | 115,253 | 4.0 | Flowmeter Not Installed - Tank Measured |
| 08/28/14 | 24 | N/A | N/A | 5,500 | 120,753 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 08/29/14 | 24 | N/A | N/A | 5,500 | 126,253 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/02/14 | 96 | N/A | N/A | 17,000 | 143,253 | 3.0 | Flowmeter Not Installed - Tank Measured |
| 09/03/14 | 24 | N/A | N/A | 5,000 | 148,253 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/04/14 | 24 | N/A | N/A | 5,250 | 153,503 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/05/14 | 24 | N/A | N/A | 5,500 | 159,003 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/08/14 | 72 | N/A | N/A | 16,500 | 175,503 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/09/14 | 24 | N/A | N/A | 5,000 | 180,503 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/10/14 | 24 | N/A | N/A | 5,250 | 185,753 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/11/14 | 24 | N/A | N/A | 5,000 | 190,753 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/12/14 | 24 | N/A | N/A | 5,500 | 196,253 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/15/14 | 72 | N/A | N/A | 17,500 | 213,753 | 4.1 | Flowmeter Not Installed - Tank Measured |
| 09/16/14 | 24 | N/A | N/A | 5,250 | 219,003 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/17/14 | 24 | N/A | N/A | 5,000 | 224,003 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/18/14 | 24 | N/A | N/A | 5,500 | 229,503 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/19/14 | 24 | N/A | N/A | 5,500 | 235,003 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/22/14 | 72 | N/A | N/A | 16,500 | 251,503 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/23/14 | 24 | N/A | N/A | 5,250 | 256,753 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/24/14 | 24 | N/A | N/A | 4,500 | 261,253 | 3.1 | Flowmeter Not Installed - Tank Measured |
| 09/25/14 | 24 | N/A | N/A | 4,500 | 265,753 | 3.1 | Flowmeter Not Installed - Tank Measured |
| 09/26/14 | 24 | N/A | N/A | 4,500 | 270,253 | 3.1 | Flowmeter Not Installed - Tank Measured |
| 09/29/14 | 72 | N/A | N/A | 12,300 | 282,553 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 09/30/14 | 24 | N/A | N/A | 4,000 | 286,553 | 2.8 | Flowmeter Not Installed - Tank Measured |

Note: Well DW-3 was activated on August 6, 2014.

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 07/30/14 | 7:50 | 18,017.49 | 18,060.14 | 42,650 | 18,059,690 | |
| 08/04/14 | 2:15 | 18,060.14 | 18,144.28 | 84,140 | 18,143,830 | |
| 08/05/14 | 8:00 | 18,144.28 | 18,237.50 | 93,220 | 18,237,050 | PVSC Compliance Sample Collected |
| 08/06/14 | 7:45 | 18,237.50 | 18,289.93 | 52,430 | 18,289,480 | |
| 08/07/14 | 5:30 | 18,289.93 | 18,324.27 | 34,340 | 18,323,820 | |
| 08/08/14 | 7:20 | 18,324.27 | 18,357.38 | 33,110 | 18,356,930 | |
| 08/11/14 | 9:00 | 18,357.38 | 18,450.45 | 93,070 | 18,450,000 | |
| 08/12/14 | 7:00 | 18,450.45 | 18,524.19 | 73,740 | 18,523,740 | |
| 08/13/14 | 6:15 | 18,524.19 | 18,579.42 | 55,230 | 18,578,970 | |
| 08/14/14 | 7:00 | 18,579.42 | 18,610.35 | 30,930 | 18,609,900 | |
| 08/15/14 | 6:00 | 18,610.35 | 18,630.29 | 19,940 | 18,629,840 | |
| 08/17/14 | 6:00 | 18,630.29 | 18,701.73 | 71,440 | 18,701,280 | |
| 08/19/14 | 8:00 | 18,701.73 | 18,805.82 | 104,090 | 18,805,370 | |
| 08/20/14 | 6:00 | 18,805.82 | 18,884.84 | 79,020 | 18,884,390 | |
| 08/21/14 | 8:00 | 18,884.84 | 18,986.62 | 101,780 | 18,986,170 | |
| 08/22/14 | 7:45 | 18,986.62 | 19,094.08 | 107,460 | 19,093,630 | |
| 08/25/14 | 8:00 | 19,094.08 | 19,193.73 | 99,650 | 19,193,280 | |
| 08/26/14 | 8:45 | 19,193.73 | 19,298.14 | 104,410 | 19,297,690 | |
| 08/27/14 | 7:30 | 19,298.14 | 19,368.93 | 70,790 | 19,368,480 | |
| 08/28/14 | 8:45 | 19,368.93 | 19,461.76 | 92,830 | 19,461,310 | |
| 08/29/14 | 5:45 | 19,461.76 | 19,495.63 | 33,870 | 19,495,180 | |
| 08/31/14 | 5:00 | 19,495.63 | 19,566.27 | 70,640 | 19,565,820 | |
| 09/02/14 | 8:00 | 19,566.27 | 19,626.24 | 59,970 | 19,625,790 | PVSC Compliance Sample Collected |
| 09/03/14 | 6:00 | 19,626.24 | 19,683.38 | 57,140 | 19,682,930 | |
| 09/04/14 | 6:30 | 19,683.38 | 19,752.78 | 69,400 | 19,752,330 | |
| 09/05/14 | 3:30 | 19,752.78 | 19,779.42 | 26,640 | 19,778,970 | |
| 09/06/14 | 5:00 | 19,779.42 | 19,824.20 | 44,780 | 19,823,750 | |
| 09/07/14 | 5:00 | 19,824.20 | 19,853.23 | 29,030 | 19,852,780 | |
| 09/08/14 | 7:15 | 19,853.23 | 19,922.16 | 68,930 | 19,921,710 | |
| 09/11/14 | 8:45 | 19,922.16 | 20,004.70 | 82,540 | 20,004,250 | |
| 09/12/14 | 1:30 | 20,004.70 | 20,053.63 | 48,930 | 20,053,180 | |
| 09/14/14 | 3:30 | 20,053.63 | 20,068.27 | 14,640 | 20,067,820 | |
| 09/15/14 | 7:00 | 20,068.77 | 20,133.27 | 65,000 | 20,132,820 | |
| 09/16/14 | 7:30 | 20,133.27 | 20,179.69 | 46,420 | 20,179,240 | |
| 09/17/14 | 7:00 | 20,179.69 | 20,231.28 | 51,590 | 20,230,830 | |
| 09/18/14 | 7:30 | 20,231.28 | 20,263.94 | 32,660 | 20,263,490 | |
| 09/19/14 | 8:30 | 20,263.94 | 20,347.22 | 83,280 | 20,346,770 | |
| 09/21/14 | 4:00 | 20,347.22 | 20,396.72 | 49,500 | 20,396,270 | |
| 09/22/14 | 8:20 | 20,396.72 | 20,491.07 | 94,350 | 20,490,620 | |
| 09/23/14 | 8:30 | 20,491.07 | 20,558.92 | 67,850 | 20,558,470 | |
| 09/24/14 | 8:15 | 20,558.92 | 20,654.42 | 95,500 | 20,653,970 | |
| 09/25/14 | 5:00 | 20,654.42 | 20,703.09 | 48,670 | 20,702,640 | |
| 09/26/14 | 7:30 | 20,703.09 | 20,732.78 | 29,690 | 20,732,330 | |
| 09/29/14 | 8:00 | 20,732.78 | 20,810.38 | 77,600 | 20,809,930 | |
| 09/30/14 | 7:30 | 20,810.38 | 20,855.01 | 44,630 | 20,854,560 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 92-102 | >1000 | 124-102-1000-a,b | 2100 | 124-102-1000-a1 | 8/14/2014 | 12:25 | 1,680 | | | Yes |
| | | | | 124-102-1000-a2 | 8/14/2014 | 12:30 | 487 | | Yes | |
| | | | | 124-102-1000-a3 | 8/14/2014 | 12:35 | 446 | | Yes | |
| | | | | 124-102-1000-a4 | 8/14/2014 | 12:40 | 299 | | Yes | |
| | | | | 124-102-1000-b1 | 8/14/2014 | 12:45 | 38.4 | | Yes | |
| | | | | 124-102-1000-b2 | 8/14/2014 | 12:50 | 139 | | Yes | |
| | | | | 124-102-1000-b3 | 8/14/2014 | 12:55 | 64.8 | | Yes | |
| | | | | 124-102-1000-b3 | 8/14/2014 | 13:00 | 663 | | Yes | |
| 88-101 | <20 | 124-101-20-a, b, c | 2850 | 124-101-20-a1 | 8/22/2014 | 9:35 | 22.4 | | Yes | |
| | | | | 124-101-20-a2 | 8/22/2014 | 9:40 | 13.3 | Yes | | |
| | | | | 124-101-20-a3 | 8/22/2014 | 9:45 | 23.8 | | Yes | |
| | | | | 124-101-20-a4 | 8/22/2014 | 9:50 | 24.6 | | Yes | |
| | | | | 124-101-20-b1 | 8/22/2014 | 9:55 | 22.5 | | Yes | |
| | | | | 124-101-20-b2 | 8/22/2014 | 10:00 | 17.2 | Yes | | |
| | | | | 124-101-20-b3 | 8/22/2014 | 10:05 | 11.5 | Yes | | |
| | | | | 124-101-20-b4 | 8/22/2014 | 10:10 | 21.8 | | Yes | |
| | | | | 124-101-20-c1 | 8/22/2014 | 10:15 | 6.8 | Yes | | |
| | | | | 124-101-20-c2 | 8/22/2014 | 10:20 | 25.0 | | Yes | |
| | | | | 124-101-20-c3 | 8/22/2014 | 10:25 | 13.6 | Yes | | |
| | | | | 124-101-20-c4 | 8/22/2014 | 10:30 | 4.2 | Yes | | |
| 83-88 | <20 | 124-88-20-a,b,c (A24) | 2800 | 124-88-20-a1 | 9/3/2014 | 7:10 | 7.1 | * | | |
| | | | | 124-88-20-a2 | 9/3/2014 | 7:15 | 10.9 | * | | |
| | | | | 124-88-20-a3 | 9/3/2014 | 7:20 | 15.4 | Yes | | |
| | | | | 124-88-20-a4 | 9/3/2014 | 7:25 | 3.3 | Yes | | |
| | | | | 124-88-20-b1 | 9/3/2014 | 7:30 | 9.6 | * | | |
| | | | | 124-88-20-b2 | 9/3/2014 | 7:35 | 26.6 | | * | |
| | | | | 124-88-20-b3 | 9/3/2014 | 7:40 | 6.9 | Yes | | |
| | | | | 124-88-20-b4 | 9/3/2014 | 7:45 | 4.4 | Yes | | |
| | | | | 124-88-20-c1 | 9/3/2014 | 7:50 | 18.3 | Yes | | |
| | | | | 124-88-20-c2 | 9/3/2014 | 7:55 | 2.6 | Yes | | |
| | | | | 124-88-20-c3 | 9/3/2014 | 8:00 | 9.4 | Yes | | |
| | | | | 124-88-20-c4 | 9/3/2014 | 8:05 | 16.2 | Yes | | |
| 79-82 | <20 | 124-82-20-a,b,c (A25) | 2800 | 124-82-20-a1 | 9/17/2014 | 8:10 | 23.9 | | * | |
| | | | | 124-82-20-a2 | 9/17/2014 | 8:15 | 16.8 | * | | |
| | | | | 124-82-20-a3 | 9/17/2014 | 8:20 | 35.3 | | * | |
| | | | | 124-82-20-a4 | 9/17/2014 | 8:25 | 12.9 | * | | |
| | | | | 124-82-20-b1 | 9/17/2014 | 8:30 | 34.6 | | * | |
| | | | | 124-82-20-b2 | 9/17/2014 | 8:35 | 142.0 | | * | |
| | | | | 124-82-20-b3 | 9/17/2014 | 8:40 | 25.4 | | * | |
| | | | | 124-82-20-b4 | 9/17/2014 | 8:45 | 12.8 | * | | |
| | | | | 124-82-20-c1 | 9/17/2014 | 8:50 | 33.7 | | * | |
| | | | | 124-82-20-c2 | 9/17/2014 | 8:55 | 16.5 | * | | |
| | | | | 124-82-20-c3 | 9/17/2014 | 9:00 | 26.8 | | * | |
| | | | | 124-82-20-c4 | 9/17/2014 | 9:05 | 39.2 | | * | |
| 73-78 | <20 | 124-78-20-a,b,c (A26) | 2300 | 124-78-20-a1 | 9/30/2014 | 7:45 | ** | | | |
| | | | | 124-78-20-a2 | 9/30/2014 | 7:50 | ** | | | |
| | | | | 124-78-20-a3 | 9/30/2014 | 7:55 | ** | | | |
| | | | | 124-78-20-a4 | 9/30/2014 | 8:00 | ** | | | |
| | | | | 124-78-20-b1 | 9/30/2014 | 8:05 | ** | | | |
| | | | | 124-78-20-b2 | 9/30/2014 | 8:10 | ** | | | |
| | | | | 124-78-20-b3 | 9/30/2014 | 8:15 | ** | | | |
| | | | | 124-78-20-b4 | 9/30/2014 | 8:20 | ** | | | |
| | | | | 124-78-20-c1 | 9/30/2014 | 8:25 | ** | | | |
| | | | | 124-78-20-c2 | 9/30/2014 | 8:30 | ** | | | |
| | | | | 124-78-20-c3 | 9/30/2014 | 8:35 | ** | | | |
| | | | | 124-78-20-c4 | 9/30/2014 | 8:40 | ** | | | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

# Attachment 7: Perimeter Pools Update




IN PROGRESS
10-02-2014


STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP–1


Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO

# Attachment 8: Groundwater Quality Data Surcharge Monitoring Update

- Summary of Groundwater Quality Data from GWET Wells
- Trichloroethene/Chloroform/Hexavalent Chromium in GWET Wells
- Quarterly Water Wells


Honeywell


## Summary of Groundwater Quality Data from GWET Wells

| Parameter | 3-Dec-13 | | | 1-Apr-14 | | | 28-May-14 | | | 9-Sep-14 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-203BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 3.4 | 5.2 | ND | 2.9 | 4.0 | ND | 3.4 | 4.7 | ND | 3.7 | 4.7 | ND |
| Carbon Tetrachloride | 5.8 | 4.8 | 2.5 | 4.4J | 2.8 | 1.9 | 7.0 | 4.3 | 2.7 | 7.3 | 4.8 | 3.0 |
| Chloroform | 31.0 | 16.8 | ND | 26.5 | 12.0 | ND | 31.3 | 14.0 | 0.25J | 28.1 | 11.3 | ND |
| 1,1-Dichloroethene | 0.07 | ND | ND | 0.42J | ND | ND | 0.77J | ND | ND | 0.62J | ND | ND |
| cis-1,2-Dichloroethene | 135 | 12.3 | ND | 96 | 8.1 | ND | 144 | ND | ND | 128 | 9.6 | ND |
| trans-1,2-Dichloroethene | 4.9 | 0.35 | ND | 3.4 | ND | ND | 5.3 | ND | ND | 4.5 | ND | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 113.0 | 63.0 | ND | 91.3 | 43.4 | ND | 119 | 54.8 | ND | 123 | 57.4 | ND |
| 1,1-Dichloroethane | 0.47 | ND | ND | 0.45J | ND | ND | 0.61J | ND | ND | 0.55J | ND | ND |
| Methylene chloride | 0.87 | 0.31 | ND | 0.77J | ND | ND | 0.92J | ND | ND | 0.74J | ND | ND |
| Vinyl chloride | 14.2 | 4.8 | ND | 13.5 | 2.7 | ND | 21.2 | 3.8 | ND | 25.2 | 3.8 | ND |
| 1,2-Dichlorobenzene | 0.72 | ND | ND | 0.72J | ND | ND | 0.70J | ND | ND | 0.82J | ND | ND |
| Chlorobenzene | 0.39 | ND | ND | 0.38J | ND | ND | 0.40J | ND | ND | 0.42J | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 39,600 | 11,300 | 16,500 | 33,400 | 12,500 | 15,100 | 34,700 | 12,700 | 19,700 | 34,200 | 11,100 | 15,700 |
| Total Chromium | 34,200 | 10,600 | 14,900 | 36,900 | 16,400 | 16,600 | 35,500 | 14,500 | 19,600 | 37,600 | 19,300 | 17,900 |


NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.

Note:
Starting with 1st quarter 2014, well 115-MW-215BR is being pumped and sampled.




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR

Honeywell

## Quarterly Water Levels
## September 2014

| Wells<br>Date: June XX, 2014 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments |
|---|---|---|---|---|
| 087-MW-25D | 18.17 | 15.07 | 3.10 | GW Elevations are not corrected for tidal influence |
| 087-MW-25T | 18.19 | 15.96 | 2.23 | |
| 087-MW-35 | 18.29 | 15.51 | 2.78 | |
| 087-OBS-1D | 15.13 | 11.71 | 3.42 | |
| 087-OBS-1L | 15.27 | 12.66 | 2.61 | |
| 087-OBS-1T | 15.23 | 12.22 | 3.01 | |
| 087-PW-2 | 13.02 | 30.15 | -17.13 | |
| 087-MW-08 | 12.98 | 10.76 | 2.22 | |
| 087-OBS-3L | 12.88 | 12.25 | 0.63 | |
| 087-MW-13 | 12.93 | 12.78 | 0.15 | |
| 087-OBS-5D | 12.72 | 10.70 | 2.02 | |
| 087-OBS-5T | 12.62 | 11.90 | 0.72 | |
| 087-PW-1 | 12.66 | 27.35 | -14.69 | |
| 087-MW-34 | 12.73 | 12.69 | 0.04 | |
| 087-OBS-2D | 12.68 | 13.75 | -1.07 | |
| SA6-MW-AA1D | 19.36 | 17.57 | 1.79 | |
| SA6-MW-AA1T | 15.31 | 13.72 | 1.59 | |
| SA6-MW-5BR-1 | 17.06 | | 17.06 | |
| 087-OBS-4T | 11.6 | 10.60 | 1.00 | |
| 087-MW-O29D | 10.32 | 8.68 | 1.64 | |
| 087-MW-O29T | 9.98 | 7.82 | 2.16 | |
| 087-MW-03 | 13.77 | N/A | N/A | Well not accessible |
| 087-MW-02 | 12.57 | N/A | N/A | |
| 115-MW-203BR* | 8.7 | 6.81 | N/A* | |
| 073-MW-1BR-1 | 7.58 | 25.12 | N/A* | |
| 073-MW-10BR-1 | 6.67 | 22.97 | -16.30 | |
| 115-MW-215BR* | 8.82 | 11.56 | N/A* | |


* Reference point elevation to be confirmed.

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Deflection Along Open Excavation
- Sheet Monitoring Locations
- Sheet Pile Repair Log




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS | |
| | | REVISION | BY | APVD | |
| | | TDD | RJR | TDD | BCO |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2245, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the  open space side of the barrier wall with the objective of reducing deflection during excavation.







NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 03-20-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 08-19-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-53

Entact ID:

Date Exposed: 8/19/14

Describe Damage: (15) Scrapes by the Cat 349E and 322C excavator buckets- (10) 1"Ø, 1/2x24, 1x12", 1x6", 1/2x48", 1/2x3". Cell 89

Damage Location (ft below top of sheet, inboard side outboard side): 3-16' outboard

Date Repaired: 8/26/14, 9/11/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 9/11/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-54

Entact ID:

Date Exposed: 8/22/14

Describe Damage: (5) scrapes by the Cat 349E and 322C excavator buckets- 1x48", 1x8", 1x6", 1/2x36", 1x36". Cell 88

Damage Location (ft below top of sheet, inboard side outboard side): 2-16' outboard

Date Repaired: 8/26/14, 9/15/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-55

Entact ID:

Date Exposed: 8/22/14

Describe Damage: (5) Scrapes by the Cat 349E and 322C excavator buckets- 1/2x24", 1/4x48", 5"Ø, 2x4", 1x6". Cell 88

Damage Location (ft below top of sheet, inboard side outboard side): 2-15' outboard

Date Repaired: 8/26/14 Partial, 9/15/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-56

Entact ID:

Date Exposed: 8/22/14

Describe Damage: (16) scrapes by the Cat 349E and 322C excavator buckets- 4x10", (5)1x6", 1x60", (2)1"Ø, 2x36", 1x36", 2x4", 1/2x3", (2)1x12", 1/4x12". Cell 88

Damage Location (ft below top of sheet, inboard side outboard side): 1-14' outboard

Date Repaired: 8/26/14 Partial, 9/15/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-57
Entact ID:
Date Exposed: 8/21/14
Describe Damage: (7) Scrapes by the Cat 349E and 322e excavator buckets- 1x60", 1x36", 1x12", (4) 1"Ø. Cell 88/87

Damage Location (ft below top of sheet, inboard side outboard side): 5-14' outboard

Date Repaired: 8/26/14 Partial, 9/15/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-58
Entact ID:
Date Exposed: 8/22/14
Describe Damage: (7) scrapes by the Cat 349E and 322C excavator buckets - (2)1x8", 3x10", 1x48", 1/4x4", 2"Ø, 1/2x3": Cell 87

Damage Location (ft below top of sheet, inboard side outboard side): 10 - 15' outboard

Date Repaired: 8/26/14 Partial, 9/15/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-59
Entact ID:
Date Exposed: 8/22/14
Describe Damage: (14) Scrapes by the Cat 349E and 322C excavator buckets- 3x12", 4"x24", 1x60", 3"Ø, 5"Ø, (2)1x3", (3)1x6", 2x10", 1/2x18", 1/2x4", 1"Ø. Cell 87.

Damage Location (ft below top of sheet, inboard side outboard side): 3-14" outboard

Date Repaired: 8/26/14 Partial, 9/15/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-60
Entact ID:
Date Exposed: 8/22/14
Describe Damage: (13) scrapes by the Cat 349E and 322C excavator buckets- 1/4x24", 1/2x48", (3)1/2x6", 1x48", (2)3"Ø, 1/2x60", 1x24", (3)1"Ø. Cell 87/8886

Damage Location (ft below top of sheet, inboard side outboard side): ~~8/15~~ 8-15' outboard

Date Repaired: 8/29/14 Partial, 9/15/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-61

Entact ID:

Date Exposed: 8/25/14

Describe Damage: (18) Scrapes by the Cat 349E and 322C excavator buckets - 1x36", 2x60", 1/2x36", 1x24", (2) 1/2x24", (7) 1"Ø, (2) 3"Ø, 1/2x3", 1x5", 12"Ø. Cell 86

Damage Location (ft below top of sheet, inboard side outboard side): 6-15' outboard

Date Repaired: 8/29/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-62

Entact ID:

Date Exposed: 8/26/14

Describe Damage: (15) Scrapes by the Cat 349E and 322C excavator buckets - (6) 1"Ø, 1x18", 1x36", 2x4", 10"Ø, (2) 1x24, 2"x36", 4"Ø, 1/4x84". Cell 86

Damage Location (ft below top of sheet, inboard side outboard side): 6-15' outboard

Date Repaired: 8/29/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-63

Entact ID:

Date Exposed: 8/26/14

Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets - (2) 1/2x6", 2"Ø, 2x18", 1/2"Ø, 10x48", 1x24", 1x5". Cell 86/85

Damage Location (ft below top of sheet, inboard side outboard side): 2-15' outboard

Date Repaired: 8/29/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-64

Entact ID:

Date Exposed: 8/26/14

Describe Damage: (13) scrapes by the Cat 349E and 322C excavator buckets - (4) 1"Ø, 1x24", 1x4", 2x48", 1x36", (2) 2"Ø, (2) 1x3", 12"Ø. Cell 85

Damage Location (ft below top of sheet, inboard side outboard side): 7-15' outboard

Date Repaired: 8/29/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-65

Entact ID:

Date Exposed: 8/27/14

Describe Damage: (15) scrapes by the Cat 349E excavator bucket- (3) 1/2x12", (2) 1x36", 1x12, 10"Ø, 1x120", 2"Ø, 24"Ø, 1x18", 1/4x60", 1x3", (2) 1/2x6", Cell 85

Damage Location (ft below top of sheet, inboard side outboard side): 4-16' outboard

Date Repaired: 8/29/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14 Total

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-66

Entact ID:

Date Exposed: 8/27/14

Describe Damage: (9) scrapes by the Cat 349E and 322C excavator buckets - 1x48", 1x36", (4) 1x6", (2) 1x3"), 2"Ø. Cell 85/84

Damage Location (ft below top of sheet, inboard side outboard side): 1-15' outboard

Date Repaired: 9/4/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14 Total

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-67

Entact ID:

Date Exposed: 8/29/14

Describe Damage: (7) Scrapes by the Cat 349E and 322C excavator buckets- 1x96", 1x84", 1x36", (2) 2"Ø, 1x6", 1"Ø. Cell 84

Damage Location (ft below top of sheet, inboard side outboard side): 3-15' outboard

Date Repaired: 9/4/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" Paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-68

Entact ID:

Date Exposed: 8/29/14

Describe Damage: (18) scrapes by the Cat 349E and 322C excavator buckets- (3) 1x3", (4) 1"Ø, (2) 12"Ø, 1x6", 2x6", 5"Ø, 3"Ø, 1x120", 1/2x24", 1x48", 1x8", 1/4x18", Cell 84

Damage Location (ft below top of sheet, inboard side outboard side): 6"-15' outboard

Date Repaired: 9/4/14 Partial, 9/15/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 9/15/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 4, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/04/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, September 04, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing on the south side of the excavation is not continuous and the Exclusion Zone is open on the western perimeter. |
| 2 | IA2Q4A1AL8 | Windscreen along the perimeter fenceline at the Kellogg Street jughandle is detached along the bottom edge. |
| 3 | IA2Q4A1AL8 | Sediment has built up along the north side of Kellogg street by the 80 Kellogg slab. |
| 4 | IA2Q4A1AL8 | Concrete parking space chocks have been pushed out of position outside of the 60 Kellogg building. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ Signature **Date:** 09/04/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install EZ fencing to properly delineate the perimeter of the Exclusion Zone. | 9-5-14 RAD |
| 2 | Repair and/or re-attach windscreen fabric on the perimeter fence. | 9-5-14 RAD |
| 3 | Remove sediment from the north side of Kellogg Street. | 9-8-14 RAD |
| 4 | Reposition parking space chocks. | 9-8-14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 09/09/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 11, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | | X | | 5 |
| Housekeeping | | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 6 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 09/11/14

**SWPPP Observer:** _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Thursday, September 11, 2014

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone signs are absent along the sheet pile wall bordering the south side of the 1-S cap area. |
| 2 | IA2Q4A1AL8 | Tarps have partially blown off of the >1000 PPM material stockpile |
| 3 | IA2Q4A1AL8 | Sediment and mud are accumulating on the eastern haul road adjacent to Rt. 440. |
| 4 | IA2Q4A1AL8 | A catch basin on Kellogg Street south of the 80 Kellogg slab does not have sediment protection. |
| 5 | IA2Q4A1AL8 | Sediment and mud are accumulating along the south side of the western end of Kellogg Street. |
| 6 | IA2Q4A1AL8 | Safety fencing around the western end of the sedimentation basin overflow structure requires maintenance. |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 09/11/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place Exclusion Zone signs on the hydraulic barrier wall where it borders exposed cap material. | 9/15/14 RAD |
| 2 | Replace tarps over >1000 PPM material. | 9/12/14 RAD |
| 3 | Clean up sediment and mud on the eastern SA-6 South haul road and re-cover the area with stone. | 9/15/14 RAD |
| 4 | Place filter fabric under the catch basin grate for sediment protection. | 9/16/14 RAD |
| 5 | Clean up all accumulated sediment from the south side of the western end of Kellogg Street | 9/17/14 RAD |
| 6 | Repair or replace the orange warning fencing surrounding the western end of the sed basin overflow structure. | 9/16/14 RAD |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 09/17/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 18, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 2 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 3,4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 09/19/14

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
Thursday, September 18, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing is damaged at the eastern end of the EZ adjacent to Rt. 440. |
| 2 | IA2Q4A1AL8 | Lubricant drums in the mechanics area are not placed on spill pallets. |
| 3 | IA2Q4A1AL8 | Stone in the tracking pad located on the east side of the 60 Kellogg building has become blinded with backfill material. |
| 4 | IA2Q4A1AL8 | Sediment which was removed from Kellogg Street has been dumped inside of the site to the north of the western-most Kellogg Street gate. |
| 5 | IA2Q4A1AL8 | Two catch basins located along the north side of Kellogg Street adjacent to the 80 Kellogg slab do not have silt protection. |
| 6 | IA2Q4A1AL8 | Silt fencing in the northwestern corner of surcharge area 1-S is not properly toed in. |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/19/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair/replace orange fencing and/or the fence post in the northeast corner of the SA-6 South EZ. | 9-19-14 RAD |
| 2 | Place drums in the mechanic's area on the unused spill pallet which is currentlly located by the Entact C-boxes. | 9-22-14 RAD |
| 3 | Scarify the stone in the tracking pad at the eastern exit gate to restore the function of the pad. | 9-22-14 RAD |
| 4 | Relocate the sediment/mud from the area of the western Kellogg Street gate. | 9-22-14 RAD |
| 5 | Install filter fabric beneath the grates of the two unprotected catch basins to the south of the 80 Kellogg slab. | 9-22-14 RAD |
| 6 | Completed the installation of silt fence at the northwestern corner of the 1-S surcharge area | 9-22-14 RAD |
| | | |
| | | |

Construction Manager: _____ Date: 09/22/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 24, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | | X | | 4 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 5 |
| Proper Chemical Storage | | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/24/14

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Wednesday, September 24, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence at the western end if the north side of the 1-S surcharge pile is missing in one location. |
| 2 | IA2Q4A1AL8 | The orange plastic warning fencing on the eastern side of the sedimentation basin requires maintenance/repair |
| 3 | IA2Q4A1AL8 | The silt fence which runs along the bottom of the chain link perimeter fence in the southeast corner of Study Area 7 has accumulated sediment to within 6 inches of its top. |
| 4 | IA2Q4A1AL8 | Straw waddle in on the north and south roadways of Study Area 7 is worn out and no longer effective. |
| 5 | IA2Q4A1AL8 | The containment measures surrounding the Novartis stockpile area on Study Area 7 require maintenance/repair. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ Signature **Date:** 09/24/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace or re-install the missing section of silt fence at the toe of the 1-S surcharge pile. | 9/25/14 RAD |
| 2 | Replace or repair the orange warning fencing located on the eastern side of the sedimentation basin. | 10/1/14 RAD |
| 3 | Remove accumulated sediment from against the silt fence in the southeast corner of Study Area 7 (along the Rt. 440 perimeter fence). | 9/25/14 RAD |
| 4 | Replace straw waddle on the SA-7 roadways and protect with wood dunnage or other material. | 9/25/14 RAD |
| 5 | Re-install plastic sheeting over the containment hay bales; replace degraded bales. | 10/1/14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 10/01/14

# Attachment 12: GWTP Update

- 80 Kellogg Ground Water Treatment Plant Discharge Monitoring Report (August 2014)
- 9/15/14 NJDEP Correspondence re: Administrative Revocation NJDPES Permit #NJG0156311
- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (August 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

September 15, 2014

New Jersey Department of Environmental Protection
Division of Water Quality
Bureau of Permit Management
P.O. Box 029
Trenton, NJ 08625-0029

**RE: NJPDES Permit NJ0156311: August 2014 Surface Water Discharge Monitoring Report**
**Study Area 7, Jersey City, NJ**

To Whom It May Concern:

In accordance with the Honeywell International NJPDES Permit NJ0156311, enclosed please find the August 2014 Surface Water Discharge Monitoring Report for Outfall 001A. Please note that there was no discharge this monitoring period.

Please contact me at 973-455-2989 should you have any questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Program Manager
Fahy Associates
c/o Honeywell International

Enc.

cc: Angle Trujillo - Evoqua
Frank Schroyer - Parsons

New Jersey Department of Environmental Protection
Division of Water Quality

**Surface Water Discharge Monitoring Report Submittal Form**

| NJPDES PERMIT | MONITORING PERIOD | | | | | | | MONITORED LOCATION: |
|---|---|---|---|---|---|---|---|---|
| | Month | Day | Year | | Month | Day | Year | |
| NJG0156311 | 8 | 1 | 2014 | To | 8 | 31 | 2014 | 001A - Remediated Groundwater |

**PERMITTEE:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**LOCATION OF ACTIVITY:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

**REPORT RECIPIENT:**
Honeywell International Inc
ATT: HELEN FAHY
101 COLUMBIA ROAD
MORRISTOWN, NJ 07962

**REGION / COUNTY: Northern / Hudson County**

**CHECK IF APPLICABLE:** ☒ **No Discharge this Monitoring Period** ☐ **Monitoring Report Comments Attached**

**WHO MUST SIGN** The highest ranking official having day-to-day managerial and operational responsibilities for the discharging facility shall sign the certification or, in his absence a person designated by that person. For a local agency, the highest ranking operator of the treatment works shall sign the certification. Where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that reponsibility or person designated by that person shall also sign the second certification at the bottom of this page. If the local agency has contracted with another entity to operate the treatment works, the highest-ranking official of the contracted entity shall sign the certification.

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and/or imprisonment, pursuant to N.J.A.C. 7:14A-6.9(B). The New Jersey Water Pollution Control Act provides for penalties up to $50,000 per violation.

John J Morris, Remediation Director — —

NAME AND TITLE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR — GRADE AND REGISTRY NUMBER (IF APPLICABLE)

John J Morris — 9/4/2014 — 973.455.4003

SIGNATURE OF PRINCIPAL EXECUTIVE OFFICER, AUTHORIZED AGENT, OR *LICENSED OPERATOR — DATE — AREA CODE/PHONE NUMBER

**For a local agency where the highest ranking operator does not have the ability to authorize capital expenditures and hire personnel, a person having that responsibility or person designated by that person shall sign the following certification:*

I certify under penalty of law and in accordance with N.J.S.A. 58:10A-6F(5) that I have received and reviewed the attached discharge monitoring reports.

John J Morris, Remediation Director — John J Morris — 9/4/2014 — 973.455.4003

NAME AND TITLE — SIGNATURE — DATE — AREA CODE/PHONE NUMBER

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 8/1/2014 TO 8/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Flow, In Conduit or Thru Treatment Plant<br>50050 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | | | GPD | ****** | ****** | ****** | ****** | | | |
| | PERMIT REQUIREMENT | REPORT 01MOAV | REPORT 01DAMX | | ****** | ****** | ****** | | | 1/Month | METER |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| pH<br>00400 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | | SU | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 6.0 01MOMN | ****** | 9.0 01MOMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| LC50 Statre 96hr Acu Mysid Bahia<br>TAN3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | 50 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | RQL | ****** | ****** | | ****** | ****** | ****** | | | | |
| IC25 Statre 7day Chr Mysid Bahia<br>TBP3E 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | | ****** | ****** | %EFFL | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | REPORT 01RPMN | ****** | ****** | | | 1/Year | COMPOS |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Petroleum Hydrocarbons<br>00551 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 10 01MOAV | 15 01RPINMX | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Carbon, Tot Organic (TOC)<br>00680 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | MG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 20 01WKAV | | | 1/Month | GRAB |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.

*Pre-Print Creation Date: 7/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 8/1/2014 TO 8/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Chromium Trivalent (as Cr) Total Recov. *PS06 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | REPORT 01DAMX | | | | |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Cyanide, Total (as CN) 00720 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | GRAB |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 40 | 40 | | | | |
| Nickel, Total Recoverable 01074 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT 01MOAV | 8.3 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Zinc, Total Recoverable 01094 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 100 01MOAV | 200 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 30 | 30 | | | | |
| Lead, Total Recoverable 01114 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Quarter | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 79 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Total Recoverable 01118 1 Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | 1/Month | COMP24 |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50 01MOAV | 100 01DAMX | | | | |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 7/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 8/1/2014 TO 8/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Copper, Total Recoverable<br>01119 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | 50<br>01MOAV | 100<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 10 | 10 | | | | |
| Chromium, Hexavalent Dissolved (as Cr)<br>01220 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | REPORT<br>01DAMX | | | 1/Quarter | COMP24 |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |
| Mercury Total Recoverable<br>71901 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 0.025<br>01DAMX | | | 1/Quarter | COMP24 |
| | RQL | ****** | ****** | | ****** | 1 | 1 | | | | |
| Carbon Tetrachloride<br>32102 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 8.8<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 6 | 6 | | | | |
| Chloroform<br>32106 2<br>Effluent Net Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 46<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |
| Trichloroethylene<br>39180 1<br>Effluent Gross Value | SAMPLE MEASUREMENT | ****** | ****** | ****** | ****** | | | UG/L | | | |
| | PERMIT REQUIREMENT | ****** | ****** | | ****** | REPORT<br>01MOAV | 54<br>01DAMX | | | 1/Quarter | GRAB |
| | RQL | ****** | ****** | | ****** | 5 | 5 | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 7/1/2014*

# Surface Water Discharge Monitoring Report

PI 234822

| PERMIT NUMBER: | MONITORED LOCATION: | MONITORING PERIOD: | FACILITY NAME: |
|---|---|---|---|
| NJG0156311 | 001A Remediated Groundwat | 8/1/2014 TO 8/31/2014 | HONEYWELL STUDY AREA 7 |

| PARAMETER | | QUANTITY OR LOADING | | UNITS | QUALITY OR CONCENTRATION | | | UNITS | NO. EX. | FREQ. OF ANALYSIS | SAMPLE TYPE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Lab Certification # | SAMPLE MEASUREMENT | | | | | | | | | | |
| 99999 99 Lab | PERMIT REQUIREMENT | REPORT Lab # | REPORT Lab # | | REPORT Lab # | REPORT Lab # | REPORT Lab # | | | Not Applic | NOT AP |
| | QL | ****** | ****** | | ****** | ****** | ****** | | | | |

Comments: If there are any questions concerning this form, please contact Brian Salvo, Bureau of Point Source Permitting via email at Brian.Salvo@dep.state.nj.us or via phone at (609) 292-4860.



*Pre-Print Creation Date: 7/1/2014*

REC'D SEP 22 2014

# State of New Jersey

CHRIS CHRISTIE
*Governor*

KIM GUADAGNO
*Lt. Governor*

DEPARTMENT OF ENVIRONMENTAL PROTECTION
Mail Code - 401-02B
Division of Water Quality
Office of Permit Management
P.O. Box 420 – 401 E State St
Trenton, NJ 08625-0420
Phone: (609) 984-4428 / Fax: (609) 777-0432

BOB MARTIN
*Commissioner*

## Notice of Administrative Revocation

September 15, 2014

JOHN MORRIS
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

RE: Administrative Revocation
Discharge Category(s): BGR
NJPDES Permit #NJG0156311
HONEYWELL STUDY AREA 7
Jersey City, Hudson County

Dear Mr. Morris:

Please be advised that the Department has confirmed that you are no longer performing any activities requiring a permit under the New Jersey Pollutant Discharge Elimination System (NJPDES) permitting program. Therefore, your NJPDES permit is administratively revoked effective 04/29/2014.

The Water Pollution Control Act prohibits the discharge of pollutants except as authorized by a NJPDES permit. If you plan to discharge pollutants to the surface or ground waters of the state of New Jersey, you must submit a new application at least 180 days before proposing to discharge.

If you have any questions please contact me at (609) 984-4428 or via email at Terry.Beym@dep.nj.gov.

Sincerely,

Terry Beym

Terry Beym, Acting Section Chief
Office of Permit Management

c: Bureau of Surface Water Permitting, Brian Salvo
Central File-Correspondence – MF: 179223 / PI: 234822

*New Jersey is an Equal Opportunity Employer*
*Recycled Paper*

# NEW JERSEY POLLUTANT DISCHARGE ELIMINATION SYSTEM

The New Jersey Department of Environmental Protection hereby grants you a NJPDES permit for the facility/activity named in this document. This permit is the regulatory mechanism used by the Department to help ensure your discharge will not harm the environment. By complying with the terms and conditions specified, you are assuming an important role in protecting New Jersey's valuable water resources. Your acceptance of this permit is an agreement to conform with all of its provisions when constructing, installing, modifying, or operating any facility for the collection, treatment, or discharge of pollutants to waters of the state. If you have any questions about this document, please feel free to contact the Department representative listed in the permit cover letter. Your cooperation in helping us protect and safeguard our state's environment is appreciated.

**Permit Number: NJG0156311**

**Final: Surface Water GPA Revocation**

**Permittee:**
HONEYWELL INTERNATIONAL INC
101 COLUMBIA RD
MORRISTOWN, NJ 07962

**Co-Permittee:**

**Property Owner:**
ECARG
5 BECKER FARM RD
ROSELAND, NJ 07068

**Location Of Activity:**
HONEYWELL STUDY AREA 7
441 RT 440 S
JERSEY CITY, NJ 07305

| Authorization(s) Covered Under This Approval | Issuance Date | Effective Date | Status |
|---|---|---|---|
| BGR -General Remediation Clean-up (GP) | 09/15/2014 | 04/29/2014 | **Revoked** |

**By Authority of:**
**Commissioner's Office**

**DEP AUTHORIZATION**
**Melisse Carasia Auriti, Section Chief**
**Bureau of Surface Water Permitting**
**Division of Water Quality**

(Terms, conditions and provisions attached hereto)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

September 15, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the August 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 8 | 01 | 14 | 8 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 78,308 | 87,127 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 1.04 | 1.16 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.082 | 0.082 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).


Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

09/04/2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 8 | 01 | 14 | 8 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,427,535 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 15,341,157 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 8/22/2014 | 8.0 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE 09/04/2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | MONTH: August 2014 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 8/1/2014 | Angel Trujillo | 12913622 | 12992582 | 78,960 | 0.07896 | 7.30 | 1.600 | | | | | | | | | 1.05 |
| 8/2/2014 | Angel Trujillo | 12992582 | 13079709 | 87,127 | 0.087127 | 7.77 | 1.600 | | | | | | | | | 1.16 |
| 8/3/2014 | Angel Trujillo | 13079709 | 13156390 | 76,681 | 0.076681 | 7.71 | 1.600 | | | | | | | | | 1.02 |
| 8/4/2014 | Angel Trujillo | 13156390 | 13228426 | 72,036 | 0.072036 | 7.89 | 1.600 | | | | | | | | | 0.96 |
| 8/5/2014 | Angel Trujillo | 13228426 | 13308624 | 80,198 | 0.080198 | 7.84 | 1.600 | | | | | | | | | 1.07 |
| 8/6/2014 | Angel Trujillo | 13308624 | 13389741 | 81,117 | 0.081117 | 7.80 | 1.600 | | | | | | | | | 1.08 |
| 8/7/2014 | Angel Trujillo | 13389741 | 13468385 | 78,644 | 0.078644 | 7.26 | 1.600 | | | | | | | | | 1.05 |
| 8/8/2014 | Angel Trujillo | 13468385 | 13546827 | 78,442 | 0.078442 | 7.30 | 1.600 | | | | | | | | | 1.05 |
| 8/9/2014 | Angel Trujillo | 13546827 | 13628240 | 81,413 | 0.081413 | 7.24 | 1.600 | | | | | | | | | 1.09 |
| 8/10/2014 | Angel Trujillo | 13628240 | 13710561 | 82,321 | 0.082321 | 7.31 | 1.600 | | | | | | | | | 1.10 |
| 8/11/2014 | Angel Trujillo | 13710561 | 13775706 | 65,145 | 0.065145 | 7.10 | 1.600 | | | | | | | | | 0.87 |
| 8/12/2014 | Angel Trujillo | 13775706 | 13853562 | 77,856 | 0.077856 | 7.39 | 1.600 | | | | | | | | | 1.04 |
| 8/13/2014 | Angel Trujillo | 13853562 | 13934782 | 81,220 | 0.08122 | 7.31 | 1.600 | | | | | | | | | 1.08 |
| 8/14/2014 | Angel Trujillo | 13934782 | 14014289 | 79,507 | 0.079507 | 7.40 | 1.600 | | | | | | | | | 1.06 |
| 815/2014 | Angel Trujillo | 14014289 | 14091101 | 76,812 | 0.076812 | 7.40 | 1.600 | | | | | | | | | 1.02 |
| 8/16/2014 | Angel Trujillo | 14091101 | 14171774 | 80,673 | 0.080673 | 7.37 | 1.600 | | | | | | | | | 1.08 |
| 8/17/2014 | Angel Trujillo | 14171774 | 14253195 | 81,421 | 0.081421 | 7.36 | 1.600 | | | | | | | | | 1.09 |
| 8/18/2014 | Angel Trujillo | 14253195 | 14323236 | 70,041 | 0.070041 | 7.37 | 1.600 | | | | | | | | | 0.93 |
| 8/19/2014 | Angel Trujillo | 14323236 | 14401179 | 77,943 | 0.077943 | 7.50 | 1.600 | | | | | | | | | 1.04 |
| 8/20/2014 | Angel Trujillo | 14401179 | 14478608 | 77,429 | 0.077429 | 7.40 | 1.600 | | | | | | | | | 1.03 |
| 8/21/2014 | Angel Trujillo | 14478608 | 14556375 | 77,767 | 0.077767 | 7.48 | 1.600 | | | | | | | | | 1.04 |
| 8/22/2014 | Angel Trujillo | 14556375 | 14634647 | 78,272 | 0.078272 | 7.19 | 1.600 | <5.1 | 8.0 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 1.04 |
| 8/23/2014 | Angel Trujillo | 14634647 | 14716994 | 82,347 | 0.082347 | 7.55 | 1.600 | | | | | | | | | 1.10 |
| 8/24/2014 | Angel Trujillo | 14716994 | 14794455 | 77,461 | 0.077461 | 7.52 | 1.600 | | | | | | | | | 1.03 |
| 8/25/2014 | Angel Trujillo | 14794455 | 14869844 | 75,389 | 0.075389 | 7.56 | 1.600 | | | | | | | | | 1.01 |
| 8/26/2014 | Angel Trujillo | 14869844 | 14946336 | 76,492 | 0.076492 | 7.59 | 1.600 | | | | | | | | | 1.02 |
| 8/27/2014 | Angel Trujillo | 14946336 | 15024505 | 78,169 | 0.0782 | 7.58 | 1.600 | | | | | | | | | 1.04 |
| 8/28/2014 | Angel Trujillo | 15024505 | 15102734 | 78,229 | 0.078229 | 7.56 | 1.600 | | | | | | | | | 1.04 |
| 8/29/2014 | Angel Trujillo | 15102734 | 15180860 | 78,126 | 0.078126 | 7.54 | 1.600 | | | | | | | | | 1.04 |
| 8/30/2014 | Angel Trujillo | 15180860 | 15261008 | 80,148 | 0.080148 | 7.54 | 1.600 | | | | | | | | | 1.07 |
| 8/31/2014 | Angel Trujillo | 15261008 | 15341157 | 80,149 | 0.080149 | 7.55 | 1.600 | | | | | | | | | 1.07 |
| TOTAL | | | | 2,427,535 | 2.427535 | | | <5.1 | 8.0 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 87,127 | | | | | | | | | | | High: | 1.16 |
| | | | Average: | 78,308 | | | | | | | | | | | Average: | 1.04 |

E

JB74827

# Honeywell — Chain Of Custody / Analysis Request

est Labs
UTE 130
NJ 8810
8260

ng Co.: Parsons
Contact: (name, co., address)
w P: (973) 455-2989 E: helen.fahy@honeywell.com
l International
nbia Road Morristown, NJ 07962
y To: Helen Fahy (Honeywell)
o: Helen Fahy (Honeywell)

EDD To:
Sampler: Frank Schroyer
PO #
Analysis Turnaround Time (TAT): 3
Consultant: CH2M
Full Report TAT: 28 Days

Site Name: Hudson County
Location of Site: Jersey City, NJ
Phase: CS
Sampling Program: 087: JCIA

AESI Ref: 41873.63968
COC#: 087-WW-082214
Lab Proj # (SDG):
Lab ID: ACTD
Site ID:
Lab Job #: HWNJM32815
Authorized User: Honeywell

Copyright AESI Version 8.0 Unauthorized use strictly prohibited.

| Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Filtered/Preserved | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cr, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | |
| 087-WW | | | 087-WWE-082214-A | 8/22/2014 | 13:45 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | | | | -1 |
| 087-WW | | | 087-WWE-082214-B | 8/22/2014 | 13:40 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | | | | -2 |
| 087-WW | | | 087-WWI-082214 | 8/22/2014 | 14:00 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | | | | -3 |

A23 G48 L32 V375

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| ed by pH=7.19 @ | 5.6°C IR#5 Company | Parsons 1502 | Received by | Company | | Condition | Custody Seals Intact |
| royer: | Date/Time | 8/22/14 | Received by | Date/Time 8/22 1502 | | Cooler Temp. | |
| ed by | Company | | Received by | Company ACCUTEST | | Condition | Custody Seals Intact |
| | Date/Time 8-22 1730 | | | Date/Time 8/22/14 1730 | | Cooler Temp. | |

ives: [Other; Specify]:

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

04.5 °IP

DNR

D.G.

Accutest LabLink@812392 10:40 02-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-082214-A | | |
| **Lab Sample ID:** | JB74827-1 | **Date Sampled:** | 08/22/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/22/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1600 | 10 | ug/l | 1 | 08/23/14 | 08/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 08/23/14 | 08/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 08/23/14 | 08/27/14 | ND | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 08/25/14 | 08/25/14 | JW | EPA 245.1 [1] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 08/23/14 | 08/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 08/23/14 | 08/25/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA34759
(2) Instrument QC Batch: MA34770
(3) Instrument QC Batch: MA34784
(4) Prep QC Batch: MP81266
(5) Prep QC Batch: MP81440

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@812392 10:40 02-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-082214-A | | |
| Lab Sample ID: | JB74827-1 | Date Sampled: | 08/22/14 |
| Matrix: | AQ - Water | Date Received: | 08/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 08/26/14 | RP | SM2540 D-11 |
| pH [a] | 7.09 | | su | 1 | 08/22/14 20:20 | DG | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@812392 10:40 02-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-082214-A | | |
| Lab Sample ID: | JB74827-1A | Date Sampled: | 08/22/14 |
| Matrix: | AQ - Water | Date Received: | 08/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.2
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 8.0 | 5.0 | mg/l | 1 | 08/22/14 20:28 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@812392 10:40 02-Sep-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-082214-B | | |
| Lab Sample ID: | JB74827-2 | Date Sampled: | 08/22/14 |
| Matrix: | AQ - Water | Date Received: | 08/22/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 08/27/14 | AA | EPA 1664A |

RL = Reporting Limit

Accutest LabLink@812392 10:40 02-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-082214-B | | |
| Lab Sample ID: | JB74827-2 | Date Sampled: | 08/22/14 |
| Matrix: | AQ - Water | Date Received: | 08/22/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N238180.D | 1 | 08/25/14 | DC | n/a | n/a | VN10108 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA PPL List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.3 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.5 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.23 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 18.4 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.3 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.47 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 51.7 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.1 | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 99% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 101% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 97% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 99% | | 78-115% |

ND = Not detected MDL = Method Detection Limit J = Indicates an estimated value
RL = Reporting Limit B = Indicates analyte found in associated method blank
E = Indicates value exceeds calibration range N = Indicates presumptive evidence of a compound

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending September 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. Responded on September 11, 2014 to Plaintiffs' September 9, 2014 request for clarification. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**11/14/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

November 14, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
49 Bridge Street, Suite 2
Lambertville, NJ 08530

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-10**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from October 1 – October 31, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: October 2014 SA-6/7 Combined Monthly Progress Report No. 2014-10

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-10

**Project SA-6 & 7 Remediation**

## October 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 10/09/14 | NJDEP Correspondence re:<br>Retraction for the December 20, 2013 Application for Certificate of Authority to Operate (CAO) a Beneficial Use Project for the Use of Concrete from Study Area 6 North and South Sites to be used On-site as Backfill Material located at 60/80 Kellogg Street, Jersey City, NJ 07305. PI No. NJD 002 144 57, CTO 130001<br>Study Area 6 North/South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/09/14 | Response to Special Master Comments<br>Hydrocarbon-Impacted Soil Encountered<br>Study Area 6 South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/14/14 | Arnold & Porter Correspondence: ICO v. Honeywell Consolidated Litigation<br>Study Area 6 Financial Assurances | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/14/14 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2014-09<br>Study Areas 6 and 7<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/20/14 | SA-6 Chromium Remedy - Asphalt Disposition Variance<br>Study Areas 6<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/20/14 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014<br>*(see **Attachment 12**)* | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 10/21/14 | Special Master Conference Call | N/A |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 10/22/14 | Long Term Monitoring Program<br>First Five Year Implementation Plan<br>Study Area 7 Sediment Remedy<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 10/5/14 | 10/12/14 | 10/19/14 | 10/26/14 | 11/2/14 |
| **Construction Management (AMEC)** | 11 | 11 | 11 | 12 | 12 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 50 | 48 | 47 | 43 | 44 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 1 | 1 |
| **Evoqua** | 1 | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 | 0 |
| **Other** | 0 | 0 | 0 | 0 | 0 |
| **TOTAL** | **68** | **66** | **65** | **62** | **63** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6S and SA-6N.
- Collected October PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed S-3 Injection/Mass Removal Event #18 in well 088-IW-03.
- Issued Unrestricted Notice to Proceed to the JCIA demolition contractor on October 7, 2014.
- Began mobilization activities at the JCIA demolition project on October 9, 2014.
- Environ and Aquasurvey representatives performed long term monitoring activities in accordance with the sediment monitoring plan, including the bathometric survey, cap thickness verifications, sediment profile imaging (SPI), biological sampling, and pore water sampling.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on October 14, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 10/5/14 | 10/12/14 | 10/19/14 | 10/26/14 | 11/2/14 |
| Avg. Gallons Treated & Discharged (per day) | 76,883 | 75,961 | 77,733 | 76,422 | 77,950 |
| Average Flow (gpm) for Operating Period | 55 | 53 | 55 | 53 | 54 |
| Avg. Hours of Plant Operation | 23 | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 10,900 | 7,821 | 12,463 | 11,147 | 14,262 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Completed excavation activities in cells 73-59.
- Continued storm-water management activities.
- On October 8, 2014 we collected a soil sample from a visually anomalous material observed in a thin lens located in the southern portion of Cell 70. Laboratory analysis received on October 16, 2014 indicated the result was 6.5 mg/kg. No further action was required.
- Began Site 163 excavation activities.
- Continued installation of the Contingent Groundwater Extraction Trench Pipe.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 20.0 | 20.0 |
| **Entact/ Horwith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 0 | 0 | 0 |
| **Entact/ Montecalvo** | 30 cyd roll-off | Bayshore Recycling | NA | Non Haz Creosote Debris | 3 | 14.14 | 42.42 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Entact/ FCI** | 30 cyd roll off | Tullytown, Pa | WM Grows | ACM Tile & Mastic | 1 | 12.0 | 12.0 |
| **Entact/ FCI** | Tri-axle Dump | Kearny, NJ | NJ Meadowlands | Dieldrin Stained Concrete | 4 | 21.12 | 84.5 |
| **Entact/ Arecon** | Tri-axle Dump | Keasbey, NJ | Bayshore | TCE Impacted Soil | 9 | 26.1 | 235.6 |
| **Entact/ Arecon** | Tri-axle Dump | Keasbey, NJ | Bayshore | Mercury Impacted Soil | 3 | 26.36 | 79.09 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Under Excavation** | Cell Number(s) 73-59 |
| **Excavation Completed** | Cell Number(s) 75-59<br>Volume Excavated - Total for Reporting Period: 34,191 CY/ Total to Date: 151,313 CY |
| **Backfill in Progress** | Cell Number(s) 104-59 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | **10/5/14** | **10/12/14** | **10/19/14** | **10/26/14** | **11/2/14** |
| <20ppm re-use, CY | 878 | 3,309 | 2,633 | 248 | 270 |
| Weldon, Import-Tons Screenings | 103 | 0 | 0 | 0 | 3,946 |
| Tilcon, Import-Tons DGA | 688 | 1,719 | 994 | 1,876 | 1,229 |
| Tilcon, Import Tons – 1.5” Stone | 317 | 26 | 0 | 0 | 101 |
| Weldon, Imported Tons - QP | 0 | 0 | 207 | 0 | 0 |
| Weldon, Imported Tons - DGA | 0 | 0 | 0 | 0 | 0 |
| –Tilcon, Imported 6”-8” stone | 0 | 0 | 0 | 0 | 92.08 |
| Tilcon, Imported Tons – 2.5” Stone | 0 | 0 | 0 | 50 | 0 |

## E. SURCHARGE OPERATIONS

- Area 1S: Completed placement of imported Celgene soils between the sub-grade and surcharge design grade on the eastern portion. Began offloading western 100 ft. of 1S on October 24, 2014.
- Area 2S: Surcharging continued on Area 2S. Surcharge placement consisted of both chromium impacted soils to the design sub-grade and both imported Celgene and Novartis soils. Surcharge placement is approximately 80% complete.

- Area 3S: Instrumentation installation was completed as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles are located in this area. No surcharge has been initiated.
- Area 1N: Continued surcharge removal activities. Surcharge removal activities area approximately 75% complete. Details were provided in the October 2014 Surcharge Monitoring Report No. 5.
- Area 2N: Instrumentation Installation 100% complete. Surcharge being removed from Area 1N is being relocated to Area 2N. Surcharge placement is approximately 95% complete.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Began grouting angles of 19P1 Sheets.

## G. PERMIT STATUS

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 | Pending | Pending | Pending |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 | Pending | Pending | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue JCIA Structures Demolition activities to include site preparation and abatement activities.
- Continue placement of surcharge materials in SA-6S Area 2S.
- Begin placement of surcharge material in SA-6S Area 3S.
- Continue off loading of surcharge materials from SA-6N Area 1N.
- Initiate off loading of surcharge materials from SA-6S Area 1S.
- Complete placement of surcharge materials in SA-6N Area 2N.
- Continue installation of the contingent groundwater system trench on SA-6S.
- Continue dewatering of well points/sumps installed within the SA-6S open space area.
- Complete Site 163 excavation and backfilling activities.
- Complete excavation of standalone Areas 41 and 43.
- Begin excavation of the lens of anomalous material proximate to Cell 104.
- Continue loadout and transportation and disposal activities at SA-6S.
- Continue backfill placement and associated compaction testing activities at SA-6S.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Complete sediment long term monitoring activities and final report preparation.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Dewatering Data (Headers)
   - SA-6 South Deep Well Data (DW-3)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. *Groundwater Quality Data Surcharge Monitoring Update (not included in this reporting period)*
9. Surcharge Monitoring Update
   - Figure C1: Instrumentation Location Plan 2N
   - Figure G1: Instrumentation Location Plan 2S
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Deflection Along Open Excavation
    - Sheet Monitoring Locations
    - Sheet Pile Repair Log
    - Sheet Pile Angle Grout Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (September 2014)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** | **Mon 3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** | **Mon 3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 | Wed 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 | Mon 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 | Thu 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 | Fri 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 | Mon 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 | Mon 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** | **Wed 4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** | **Wed 4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 | Thu 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 | Wed 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** | **Mon 5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 | Wed 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 | Wed 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** | **Fri 6/28/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 | Fri 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** | **Fri 10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 | Tue 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 | Fri 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 | Fri 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 | Tue 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 | Fri 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** | **Thu 4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** | **Thu 4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 | Fri 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 | Fri 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 | Thu 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** | **Fri 5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 | Thu 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 | Mon 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 | Fri 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 | Fri 5/30/14 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** | **Wed 9/30/15** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** | **Tue 9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 | Thu 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 | Thu 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 | Tue 9/2/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** | **Wed 9/30/15** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 | Wed 9/30/15 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 | Tue 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** | **Fri 2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 | Fri 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 | Wed 12/30/15 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** | **Fri 4/15/16** |
| 67a | Restoration | 164 days | Tue 9/1/15 | Fri 4/15/16 |
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** | **Mon 5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Tue 11/4/14

Task Milestone Summary Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Compacting backfill north of Kellogg Street.




**Site Photograph 2:** Contractor begins backfilling with a geotextile.




**Site Photograph 3:** Contractor constructs a new bermed area.




**Photograph 4:** Contractor loads surcharge material from the stockpile**.**




**Site Photograph 5:** Contractor places geotextile on the excavation bottom.




**Site Photograph 6:** Cutting former wooden pilings.




**Site Photograph 7:** Excavation continues in Kellogg Street properties.





**Site Photograph 8:** Separation fabric placed for surcharge.


## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of November 1, 2014

October 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill






ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 10-02-14 TO 10-16-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ENTACT**
**302 Unity Plaza**
**Latrobe, PA 15650**

ENTACT
www.entact.com

# Letter of Transmittal
# Honeywell SA6 North and South
# Jersey City, New Jersey

| | |
|---|---|
| **To:** | Eric Christodoulatis – AMEC |
| **From:** | Caroline Panico – ENTACT |
| **CC:** | Kurt Gimbel – ENTACT |
| | Keith Goisse – ENTACT |
| | Jim Hosgood – ENTACT |
| **Project Number/Title:** | E8140C/Honeywell SA6 North and South |
| **Transmittal Title:** | Survey Data and Verification |
| | Cells 75-69 |
| **Submission Date:** | October 21, 2014 |

**Documents Attached:**

1) Excavation Confirmatory Points (Maser Consulting P.A.)
2) Excavation Bottom Elevations
3) Excavation Progress Map

**Survey Data Verification:**

Entact verifies that Maser Consulting P.A. has surveyed the bottom of excavations and that the final excavation grade(s) are at or below the design excavation grades throughout the corresponding excavation cells.

**Signature:** Caroline Panico **Date:** 10-21-14

Caroline Panico
ENTACT Quality Control

MASER CONSULTING P.A.
Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -0.6 | 134-SB-019 | 114A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.3 | 601878.4 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.5 | 601974.0 | 1.2 | 134-SB-061 | 106A | 7/23/2014 | -5.2 | Stratum D Reached |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.8 | 601978.1 | -7.5 | 134-SB-113 | 103 | 7/29/2014 | -7.2 | Stratum D Reached |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |
| 684908.2 | 602155.7 | -8.0 | 134-SB-049 | 89 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684943.6 | 602214.1 | -6.9 | 140-SB-035 | 88 | 8/25/2014 | -6.7 | Stratum D Reached |
| 684905.5 | 602180.6 | -7.8 | 140-SB-063 | 88 | 8/25/2014 | -6.1 | Stratum D Reached |
| 684875.3 | 602175.3 | -7.8 | 140-SB-062 | 87 | 8/25/2014 | -5.8 | Stratum D Reached |
| 684875.5 | 602187.9 | -7.3 | 140-SB-103 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684915.0 | 602239.0 | -6.1 | 140-SB-007 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |
| 684896.1 | 602229.3 | -6.6 | 140-SB-038 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684862.9 | 602228.0 | -6.1 | 134-SB-032R | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684901.7 | 602269.3 | -5.3 | 140-SB-040 | 83 | 9/4/2014 | -5.7 | Stratum D Reached |
| 684826.5 | 602208.8 | -6.5 | 140-SB-051 | 83 | 9/4/2014 | -4.7 | Stratum D Reached |
| 684854.3 | 602237.3 | -6.7 | 140-SB-041 | 83 | 9/4/2014 | -4.9 | Stratum D Reached |
| 684771.0 | 602188.4 | -4.8 | 140-SB-044 | 82 | 9/10/2014 | -5.2 | Stratum D Reached |
| 684800.2 | 602210.9 | -6.5 | 140-SB-042 | 82 | 9/10/2014 | -4.7 | Stratum D Reached |
| 684865.2 | 602271.1 | -6.2 | 140-SB-064 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684830.9 | 602252.5 | -6.3 | 140-SB-066 | 81 | 9/17/2014 | -3.1 | Stratum D Reached |
| 684716.6 | 602169.4 | -0.2 | 140-SB-043 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684755.4 | 602222.4 | -5.7 | 140-SB-047 | 80 | 9/23/2014 | -4.6 | Stratum D Reached |
| 684823.4 | 602275.4 | -5.0 | 140-SB-048 | 80 | 9/17/2014 | -2.8 | Stratum D Reached |
| 684687.1 | 602171.5 | 0.3 | 140-SB-049 | 79 | 9/23/2014 | -3.9 | Stratum D Reached |
| 684721.0 | 602200.6 | -4.2 | 140-SB-046 | 79 | 9/23/2014 | -5.1 | Stratum D Reached |
| 684680.8 | 602178.0 | -3.3 | 140-SB-075 | 79 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684695.5 | 602194.5 | -4.8 | 140-SB-018 | 79 | 9/23/2014 | -4.4 | Stratum D Reached |
| 684767.0 | 602244.0 | -4.4 | 140-SB-010 | 79 | 9/23/2014 | -4.0 | Stratum D Reached |
| 684818.0 | 602299.0 | -5.4 | 140-SB-009 | 78 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684855.0 | 602329.0 | -5.8 | 140-SB-065 | 78 | 9/23/2014 | -2.7 | Stratum D Reached |
| 684656.0 | 602192.0 | -2.7 | 140-SB-026 | 77 | 9/29/2014 | -2.3 | Stratum D Reached |
| 684740.4 | 602255.2 | -5.4 | 140-SB-082 | 77 | 9/29/2014 | -3.5 | Stratum D Reached |
| 684815.0 | 602348.7 | -3.4 | 140-SB-094 | 76 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684787.4 | 602330.2 | -0.4 | 140-SB-086 | 75 | 10/2/2014 | -4.0 | Stratum D Reached |
| 684744.9 | 602306.7 | -1.4 | 140-SB-083 | 75 | 10/2/2014 | -4.5 | Stratum D Reached |
| 684713.1 | 602276.0 | -0.4 | 140-SB-081 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684668.4 | 602240.2 | 0.1 | 140-SB-079 | 75 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684643.7 | 602221.3 | -4.2 | 140-SB-050 | 75 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684628.7 | 602233.7 | -2.9 | 140-SB-074 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684703.0 | 602285.6 | 2.6 | 140-SB-080 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684733.7 | 602322.4 | 0.6 | 140-SB-084 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.9 | 602371.9 | 0.1 | 140-SB-088 | 74 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684653.9 | 602259.3 | -1.4 | 140-SB-078 | 73 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684755.3 | 602343.3 | 0.6 | 140-SB-085 | 73 | 10/7/2014 | -1.6 | Stratum D Reached |
| 684660.7 | 602300.1 | 0.9 | 140-SB-089 | 72 | 10/9/2014 | -2.8 | Stratum D Reached |
| 684693.1 | 602326.3 | -3.0 | 140-SB-090 | 72 | 10/7/2014 | -3.3 | Stratum D Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Confirmatory Points (Table 1.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684745.4 | 602367.1 | 1.0 | 140-SB-091 | 72 | 10/7/2014 | -0.1 | Target Elevation Reached |
| 684640.0 | 602295.0 | 1.9 | 140-SB-011 | 71 | 10/9/2014 | -4.0 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | 125-SB-029R | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684629.9 | 602309.5 | 5.8 | 140-SB-033 | 70 | 10/9/2014 | 2.4 | Target Elevation Reached |
| 684725.2 | 602383.8 | 0.4 | 125-SB-029R | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684642.9 | 602315.4 | 0.9 | 140-SB-089R | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684764.0 | 602429.2 | -7.0 | 140-SB-N07 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | 125-SB-029R | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684632.0 | 602327.7 | 5.8 | 140-SB-033R | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | UST Area |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | UST Area |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | UST Area |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |
| 684922.3 | 602179.9 | -4.3 | C-89 | 89 | 8/20/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684912.0 | 602189.2 | -4.3 | C-88 | 88 | 8/25/2014 | -6.3 | Stratum D Reached |
| 684895.8 | 602194.1 | -4.3 | C-87 | 87 | 8/25/2014 | -6.0 | Stratum D Reached |
| 684880.8 | 602203.6 | -4.3 | C-86 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684872.8 | 602212.7 | -4.3 | C-85 | 85 | 8/29/2014 | -5.2 | Stratum D Reached |
| 684862.9 | 602228.0 | -4.3 | C-84 | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684820.9 | 602207.7 | -2.5 | C-83 | 83 | 9/4/2014 | -4.5 | Stratum D Reached |
| 684812.4 | 602218.7 | -2.5 | C-82 | 82 | 9/10/2014 | -4.1 | Stratum D Reached |
| 684788.9 | 602227.5 | -2.5 | C-81 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684778.7 | 602237.4 | -2.5 | C-80 | 80 | 9/17/2014 | -4.6 | Stratum D Reached |
| 684759.2 | 602240.0 | -2.5 | C-79 | 79 | 9/23/2014 | -4.1 | Stratum D Reached |
| 684758.4 | 602256.3 | -2.5 | C-78 | 78 | 9/23/2014 | -3.4 | Stratum D Reached |
| 684753.6 | 602273.9 | -2.5 | C-77 | 77 | 9/29/2014 | -3.8 | Stratum D Reached |
| 684731.1 | 602272.7 | -2.5 | C-76 | 76 | 9/29/2014 | -3.0 | Stratum D Reached |
| 684735.0 | 602292.1 | -2.5 | C-75 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684732.6 | 602313.2 | -2.5 | C-74 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.5 | 602381.3 | -2.5 | C-73 | 73 | 10/7/2014 | -2.7 | Stratum D Reached |
| 684752.7 | 602351.0 | 0.4 | C-73-1 | 73 | 10/7/2014 | 0.1 | Target Elevation Reached |
| 684662.4 | 602274.6 | -2.5 | C-73-2 | 73 | 10/7/2014 | -2.1 | Stratum D Reached |
| 684788.0 | 602395.1 | -2.5 | C-72 | 72 | 10/7/2014 | -2.5 | Stratum D Reached |
| 684743.1 | 602361.9 | 0.4 | C-72-1 | 72 | 10/7/2014 | -0.2 | Target Elevation Reached |
| 684664.8 | 602296.2 | -2.5 | C-72-2 | 72 | 10/7/2014 | -3.0 | Stratum D Reached |
| 684783.1 | 602411.4 | -2.5 | C-71 | 71 | 10/9/2014 | -2.7 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | C-71-1 | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684652.0 | 602308.3 | -2.5 | C-71-2 | 71 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684772.6 | 602425.4 | -2.5 | C-70 | 70 | 10/9/2014 | -2.5 | Stratum D Reached |
| 684725.2 | 602383.8 | 0.4 | C-70-1 | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684674.6 | 602346.3 | -2.5 | C-70-2 | 70 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684642.9 | 602315.4 | 2.1 | C-70-3 | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684626.5 | 602306.7 | 5.7 | C-70-4 | 70 | 10/9/2014 | 4.8 | Target Elevation Reached |
| 684762.8 | 602431.3 | -2.5 | C-69 | 69 | 10/14/2014 | -2.7 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | C-69-1 | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684670.5 | 602360.9 | -2.5 | C-69-2 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684632.0 | 602327.7 | 5.7 | C-69-3 | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .


| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685471.0 | 601475.6 | 4.3 | 073-SB-079 | 148 | 7/31/2014 | 4.3 | Target Elevation Reached |
| 685451.0 | 601460.9 | 7.1 | 073-SB-082 | 148 | 7/31/2014 | 2.2 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Target Elevation Reached |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685094.6 | 601890.3 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 685081.0 | 601928.0 | -0.1 | 134-SB-021 | 109A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 685080.6 | 601935.9 | 3.0 | 134-SB-092 | 108A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Target Elevation Reached |
| 684999.7 | 601940.5 | -0.5 | 134-SB-097 | 104 | 7/29/2014 | -7.2 | Stratum D Reached |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |
| 684887.0 | 602147.0 | -2.1 | 134-SB-100 | 89 | 8/20/2014 | -5.8 | Stratum D Reached |
| 684821.2 | 602190.7 | -4.8 | 140-SB-060 | 84 | 9/4/2014 | -5.2 | Stratum D Reached |
| 684779.8 | 602174.6 | -0.8 | 140-SB-059 | 83 | 9/10/2014 | -5.6 | Stratum D Reached |
| 684727.5 | 602143.2 | 0.7 | 140-SB-076 | 83 | 9/10/2014 | -4.5 | Stratum D Reached |
| 684701.3 | 602132.8 | -0.8 | 140-SB-003 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684686.4 | 602158.8 | -0.8 | 140-SB-105 | 80 | 9/17/2014 | -4.8 | Stratum D Reached |
| 684651.0 | 602180.0 | -2.1 | 140-SB-027 | 77 | 9/29/2014 | -2.8 | Stratum D Reached |
| 684630.0 | 602210.0 | -1.9 | 140-SB-077 | 75 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684622.2 | 602287.4 | -2.0 | 140-SB-034 | 71 | 10/9/2014 | -3.0 | Stratum D Reached |
| 684597.0 | 602258.0 | -3.2 | 140-SB-025 | 71 | 10/9/2014 | -3.1 | Stratum D Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 10/20/14

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**




## LEGEND

| | |
|---|---|
| 134-SB-170 <20 PPM | SUPPLEMENTAL BORING AND HEX CR RESULTS |
| 134-SB-075 < 20 PPM | SIDEWALL SAMPLE COLLECTED DURING PDI |

NOTE: SUPPLEMENTAL SAMPLE 140-SB-108 WAS COLLECTED APPROXIMATELY 2 FEET BGS BASED ON VISUALLY IDENTIFIED WHITISH MATERIAL. ANALYTICAL RESULTS REVEALED LESS THAN 20 PPM HEXAVALENT CHROMIUM WHICH IS CONSISTENT WITH SAMPLES COLLECTED IN THIS AREA DURING THE PDI.

Prepared/Date: TDD 10/24/14
Checked/Date: SGS 10/24/14

0 5 10 20
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

LENS OF WHITE ANOMALOUS MATERIAL
SUPPLEMENTAL BORING LOCATION
FIGURE 1



G:\Drawings\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Confirmation Samples\Figure 19 Anomalous Lens Boring Locations.dwg FRI, 24 OCT, 2014 - 2:52pm kacy.dawson

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-62 | | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-62-1 | 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 0 | BF-64 | | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-64-1 | 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 3 | BF-64-2 | 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-65 | | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-65-1 | 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 0 | BF-66 | | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-66-1 | 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 2 | BF-66-2 | 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 0 | BF-67 | | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-67-1 | 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-67-2 | 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-68 | | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-68-1 | 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-68-2 | 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 0 | BF-69 | | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-69-1 | 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-69-2 | 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-70 | | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-70-1 | 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-70-2 | 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| 0 | BF-71 | | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 5 | BF-71-1 | 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-72 | | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 3 | BF-72-1 | 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| 0 | BF-73 | | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 6 | BF-73-1 | 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 6 | BF-75-2 | 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 6 | BF-76-2 | 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 6 | BF-77-2 | 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 7 | BF-78-2 | 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 7 | BF-80-2 | 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 4 | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 7 | BF-81-2 | 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 6 | BF-82-2 | 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 6 | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 7 | BF-83-3 | 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 6 | BF-84-3 | 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 6 | BF-85-3 | 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-86-2 | 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.


Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF
BF-95 TO BF-136

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 4: Dewatering Operations Update

- SA-6 South Dewatering Data (Headers)
- SA-6 South Deep Well Data (DW-3)

## STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 09/02/14 | 1 | 96 | 10,11,EPS | 41 | 61,819 | 95,797 | 33,978 | 2,675,611 | 5.9 | |
| 09/03/14 | 1 | 24 | 10,11,EPS | 41 | 95,797 | 103,042 | 7,245 | 2,682,856 | 5.0 | |
| 09/04/14 | 1 | 24 | 10,11,EPS | 41 | 103,042 | 111,280 | 8,238 | 2,691,094 | 5.7 | |
| 09/05/14 | 1 | 24 | 10,11,EPS | 41 | 111,280 | 120,132 | 8,852 | 2,699,946 | 6.1 | |
| 09/08/14 | 1 | 72 | 10,11,EPS | 41 | 120,132 | 142,954 | 22,822 | 2,722,768 | 5.3 | |
| 09/09/14 | 1 | 24 | 10,11,EPS | 41 | 142,954 | 149,419 | 6,465 | 2,729,233 | 4.5 | |
| 09/10/14 | 1 | 24 | 10,11,EPS | 41 | 149,419 | 155,362 | 5,943 | 2,735,176 | 4.1 | |
| 09/11/14 | 1 | 24 | 10,11,EPS | 41 | 155,362 | 160,305 | 4,943 | 2,740,119 | 3.4 | |
| 09/12/14 | 1 | 24 | 10,11,EPS | 41 | 160,305 | 165,438 | 5,133 | 2,745,252 | 3.6 | |
| 09/15/14 | 1 | 72 | 10,11,EPS | 41 | 165,438 | 182,610 | 17,172 | 2,762,424 | 4.0 | |
| 09/16/14 | 1 | 24 | 10,11,EPS | 41 | 182,610 | 186,925 | 4,315 | 2,766,739 | 3.0 | |
| 09/17/14 | 1 | 24 | 10,11,EPS | 41 | 186,925 | 191,256 | 4,331 | 2,771,070 | 3.0 | |
| 09/18/14 | 1 | 24 | 10,11,EPS | 41 | 191,256 | 196,210 | 4,954 | 2,776,024 | 3.4 | |
| 09/19/14 | 1 | 24 | 10,11,EPS | 41 | 196,210 | 201,455 | 5,245 | 2,781,269 | 3.6 | |
| 09/22/14 | 1 | 24 | 10,EPS | 20 | 201,455 | 216,358 | 14,903 | 2,796,172 | 10.3 | |
| 09/23/14 | 1 | 24 | 10,EPS | 20 | 216,358 | 220,880 | 4,522 | 2,800,694 | 3.1 | |
| 09/24/14 | 1 | 24 | 10,EPS | 20 | 220,880 | 222,951 | 2,071 | 2,802,765 | 1.4 | |
| 09/25/14 | 1 | 24 | 10,EPS | 20 | 222,951 | 226,142 | 3,191 | 2,805,956 | 2.2 | |
| 09/26/14 | 1 | 24 | 10,EPS | 20 | 226,142 | 230,921 | 4,779 | 2,810,735 | 3.3 | |
| 09/29/14 | 1 | 72 | 10,EPS | 20 | 230,921 | 236,427 | 5,506 | 2,816,241 | 1.3 | |
| 09/30/14 | 1 | 24 | 10,EPS | 11 | 236,427 | 238,184 | 1,757 | 2,817,998 | 1.2 | |
| 10/01/14 | 1 | 24 | 10,EPS | 11 | 238,184 | 239,452 | 1,268 | 2,819,266 | 0.9 | |
| 10/02/14 | 1 | 24 | 10,EPS | 11 | 239,452 | 240,551 | 1,099 | 2,820,365 | 0.8 | |
| 10/03/14 | 1 | 24 | 10,EPS | 11 | 240,551 | 241,824 | 1,273 | 2,821,638 | 0.9 | |
| 10/06/14 | 1 | 72 | 10,EPS | 11 | 241,824 | 244,358 | 2,534 | 2,824,172 | 0.6 | System taken offline for excavation |

Notes: Active Header Numbers refer to H-1, H-2, H-3, etc., as shown on Figure 6 Well Point Dewatering System
EPS - East Perimeter System
WPS - West Perimeter System
Vac plant #2 taken out of service in October, 2013

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-3)

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 09/02/14 | 96 | N/A | N/A | 17,000 | 143,253 | 3.0 | Flowmeter Not Installed - Tank Measured |
| 09/03/14 | 24 | N/A | N/A | 5,000 | 148,253 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/04/14 | 24 | N/A | N/A | 5,250 | 153,503 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/05/14 | 24 | N/A | N/A | 5,500 | 159,003 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/08/14 | 72 | N/A | N/A | 16,500 | 175,503 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/09/14 | 24 | N/A | N/A | 5,000 | 180,503 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/10/14 | 24 | N/A | N/A | 5,250 | 185,753 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/11/14 | 24 | N/A | N/A | 5,000 | 190,753 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/12/14 | 24 | N/A | N/A | 5,500 | 196,253 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/15/14 | 72 | N/A | N/A | 17,500 | 213,753 | 4.1 | Flowmeter Not Installed - Tank Measured |
| 09/16/14 | 24 | N/A | N/A | 5,250 | 219,003 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/17/14 | 24 | N/A | N/A | 5,000 | 224,003 | 3.5 | Flowmeter Not Installed - Tank Measured |
| 09/18/14 | 24 | N/A | N/A | 5,500 | 229,503 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/19/14 | 24 | N/A | N/A | 5,500 | 235,003 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/22/14 | 72 | N/A | N/A | 16,500 | 251,503 | 3.8 | Flowmeter Not Installed - Tank Measured |
| 09/23/14 | 24 | N/A | N/A | 5,250 | 256,753 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 09/24/14 | 24 | N/A | N/A | 4,500 | 261,253 | 3.1 | Flowmeter Not Installed - Tank Measured |
| 09/25/14 | 24 | N/A | N/A | 4,500 | 265,753 | 3.1 | Flowmeter Not Installed - Tank Measured |
| 09/26/14 | 24 | N/A | N/A | 4,500 | 270,253 | 3.1 | Flowmeter Not Installed - Tank Measured |
| 09/29/14 | 72 | N/A | N/A | 12,300 | 282,553 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 09/30/14 | 24 | N/A | N/A | 4,000 | 286,553 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 10/01/14 | 24 | N/A | N/A | 4,000 | 290,553 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 10/02/14 | 24 | N/A | N/A | 4,000 | 294,553 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 10/03/14 | 24 | N/A | N/A | 4,000 | 298,553 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 10/06/14 | 72 | N/A | N/A | 15,500 | 314,053 | 3.6 | Flowmeter Not Installed - Tank Measured |
| 10/07/14 | 24 | N/A | N/A | 4,000 | 318,053 | 2.8 | Flowmeter Not Installed - Tank Measured |
| 10/08/14 | 24 | N/A | N/A | 4,000 | 322,053 | 2.8 | Well Taken offline for Excavation |

Note: Well DW-3 was activated on August 6, 2014.

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 09/02/14 | 8:00 | 19,566.27 | 19,626.24 | 59,970 | 19,625,790 | PVSC Compliance Sample Collected |
| 09/03/14 | 6:00 | 19,626.24 | 19,683.38 | 57,140 | 19,682,930 | |
| 09/04/14 | 6:30 | 19,683.38 | 19,752.78 | 69,400 | 19,752,330 | |
| 09/05/14 | 3:30 | 19,752.78 | 19,779.42 | 26,640 | 19,778,970 | |
| 09/06/14 | 5:00 | 19,779.42 | 19,824.20 | 44,780 | 19,823,750 | |
| 09/07/14 | 5:00 | 19,824.20 | 19,853.23 | 29,030 | 19,852,780 | |
| 09/08/14 | 7:15 | 19,853.23 | 19,922.16 | 68,930 | 19,921,710 | |
| 09/11/14 | 8:45 | 19,922.16 | 20,004.70 | 82,540 | 20,004,250 | |
| 09/12/14 | 1:30 | 20,004.70 | 20,053.63 | 48,930 | 20,053,180 | |
| 09/14/14 | 3:30 | 20,053.63 | 20,068.27 | 14,640 | 20,067,820 | |
| 09/15/14 | 7:00 | 20,068.77 | 20,133.27 | 65,000 | 20,132,820 | |
| 09/16/14 | 7:30 | 20,133.27 | 20,179.69 | 46,420 | 20,179,240 | |
| 09/17/14 | 7:00 | 20,179.69 | 20,231.28 | 51,590 | 20,230,830 | |
| 09/18/14 | 7:30 | 20,231.28 | 20,263.94 | 32,660 | 20,263,490 | |
| 09/19/14 | 8:30 | 20,263.94 | 20,347.22 | 83,280 | 20,346,770 | |
| 09/21/14 | 4:00 | 20,347.22 | 20,396.72 | 49,500 | 20,396,270 | |
| 09/22/14 | 8:20 | 20,396.72 | 20,491.07 | 94,350 | 20,490,620 | |
| 09/23/14 | 8:30 | 20,491.07 | 20,558.92 | 67,850 | 20,558,470 | |
| 09/24/14 | 8:15 | 20,558.92 | 20,654.42 | 95,500 | 20,653,970 | |
| 09/25/14 | 5:00 | 20,654.42 | 20,703.09 | 48,670 | 20,702,640 | |
| 09/26/14 | 7:30 | 20,703.09 | 20,732.78 | 29,690 | 20,732,330 | |
| 09/29/14 | 8:00 | 20,732.78 | 20,810.38 | 77,600 | 20,809,930 | |
| 09/30/14 | 7:30 | 20,810.38 | 20,855.01 | 44,630 | 20,854,560 | |
| 10/02/14 | 8:30 | 20,855.01 | 20,938.29 | 83,280 | 20,937,840 | |
| 10/03/14 | 6:00 | 20,938.29 | 20,977.59 | 39,300 | 20,977,140 | |
| 10/05/14 | 4:30 | 20,977.59 | 21,023.46 | 45,870 | 21,023,010 | |
| 10/06/14 | 7:45 | 21,023.46 | 21,102.23 | 78,770 | 21,101,780 | |
| 10/09/14 | 8:00 | 21,102.23 | 21,182.13 | 79,900 | 21,181,680 | PVSC Compliance Sample Collected |
| 10/10/14 | 7:30 | 21,182.13 | 21,208.69 | 26,560 | 21,208,240 | |
| 10/12/14 | 4:30 | 21,208.69 | 21,228.53 | 19,840 | 21,228,080 | |
| 10/13/14 | 6:30 | 21,228.53 | 21,289.72 | 61,190 | 21,289,270 | |
| 10/14/14 | 2:00 | 21,289.72 | 21,292.46 | 2,740 | 21,292,010 | |
| 10/15/14 | 8:00 | 21,292.46 | 21,349.49 | 57,030 | 21,349,040 | |
| 10/16/14 | 8:00 | 21,349.49 | 21,411.09 | 61,600 | 21,410,640 | |
| 10/17/14 | 7:00 | 21,411.09 | 21,463.04 | 51,950 | 21,462,590 | |
| 10/19/14 | 5:00 | 21,463.04 | 21,523.23 | 60,190 | 21,522,780 | |
| 10/21/14 | 7:00 | 21,523.23 | 21,574.85 | 51,620 | 21,574,400 | |
| 10/22/14 | 8:00 | 21,574.85 | 21,611.86 | 37,010 | 21,611,410 | |
| 10/23/14 | 9:30 | 21,611.86 | 21,728.57 | 116,710 | 21,728,120 | |
| 10/24/14 | 7:00 | 21,728.57 | 21,795.15 | 66,580 | 21,794,700 | |
| 10/25/14 | 4:00 | 21,795.15 | 21,836.74 | 41,590 | 21,836,290 | |
| 10/27/14 | 8:00 | 21,836.74 | 21,934.46 | 97,720 | 21,934,010 | |
| 10/29/14 | 4:15 | 21,934.46 | 21,979.83 | 45,370 | 21,979,380 | |
| 10/30/14 | 2:00 | 21,979.83 | 21,987.45 | 7,620 | 21,987,000 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log


| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 83-88 | <20 | 124-88-20-a,b,c (A24) | 2800 | 124-88-20-a1 | 9/3/2014 | 7:10 | 7.1 | Yes | | |
| | | | | 124-88-20-a2 | 9/3/2014 | 7:15 | 10.9 | Yes | | |
| | | | | 124-88-20-a3 | 9/3/2014 | 7:20 | 15.4 | Yes | | |
| | | | | 124-88-20-a4 | 9/3/2014 | 7:25 | 3.3 | Yes | | |
| | | | | 124-88-20-b1 | 9/3/2014 | 7:30 | 9.6 | Yes | | |
| | | | | 124-88-20-b2 | 9/3/2014 | 7:35 | 26.6 | | Yes | |
| | | | | 124-88-20-b3 | 9/3/2014 | 7:40 | 6.9 | Yes | | |
| | | | | 124-88-20-b4 | 9/3/2014 | 7:45 | 4.4 | Yes | | |
| | | | | 124-88-20-c1 | 9/3/2014 | 7:50 | 18.3 | Yes | | |
| | | | | 124-88-20-c2 | 9/3/2014 | 7:55 | 2.6 | Yes | | |
| | | | | 124-88-20-c3 | 9/3/2014 | 8:00 | 9.4 | Yes | | |
| | | | | 124-88-20-c4 | 9/3/2014 | 8:05 | 16.2 | Yes | | |
| 79-82 | <20 | 124-82-20-a,b,c (A25) | 2800 | 124-82-20-a1 | 9/17/2014 | 8:10 | 23.9 | | * | |
| | | | | 124-82-20-a2 | 9/17/2014 | 8:15 | 16.8 | Yes | | |
| | | | | 124-82-20-a3 | 9/17/2014 | 8:20 | 35.3 | | * | |
| | | | | 124-82-20-a4 | 9/17/2014 | 8:25 | 12.9 | Yes | | |
| | | | | 124-82-20-b1 | 9/17/2014 | 8:30 | 34.6 | | * | |
| | | | | 124-82-20-b2 | 9/17/2014 | 8:35 | 142.0 | | * | |
| | | | | 124-82-20-b3 | 9/17/2014 | 8:40 | 25.4 | | * | |
| | | | | 124-82-20-b4 | 9/17/2014 | 8:45 | 12.8 | Yes | | |
| | | | | 124-82-20-c1 | 9/17/2014 | 8:50 | 33.7 | | * | |
| | | | | 124-82-20-c2 | 9/17/2014 | 8:55 | 16.5 | Yes | | |
| | | | | 124-82-20-c3 | 9/17/2014 | 9:00 | 26.8 | | * | |
| | | | | 124-82-20-c4 | 9/17/2014 | 9:05 | 39.2 | | * | |
| 75-78 | <20 | 124-78-20-a,b,c (A26) | 2300 | 124-78-20-a1 | 9/30/2014 | 7:45 | 9.2 | Yes | | |
| | | | | 124-78-20-a2 | 9/30/2014 | 7:50 | 23.3 | | * | |
| | | | | 124-78-20-a3 | 9/30/2014 | 7:55 | 15.3 | Yes | | |
| | | | | 124-78-20-a4 | 9/30/2014 | 8:00 | 11.9 | Yes | | |
| | | | | 124-78-20-b1 | 9/30/2014 | 8:05 | 15.7 | Yes | | |
| | | | | 124-78-20-b2 | 9/30/2014 | 8:10 | 9.3 | Yes | | |
| | | | | 124-78-20-b3 | 9/30/2014 | 8:15 | 25.8 | | * | |
| | | | | 124-78-20-b4 | 9/30/2014 | 8:20 | 21.2 | | * | |
| | | | | 124-78-20-c1 | 9/30/2014 | 8:25 | 19.5 | Yes | | |
| | | | | 124-78-20-c2 | 9/30/2014 | 8:30 | 20.4 | | * | |
| | | | | 124-78-20-c3 | 9/30/2014 | 8:35 | 25.4 | | * | |
| | | | | 124-78-20-c4 | 9/30/2014 | 8:40 | 39.0 | | * | |
| 67-75 | <20 | 124-75-20-a,b (A27) | 1200 | 124-75-20-a1 | 10/16/2014 | 11:20 | 9.6 | * | | |
| | | | | 124-75-20-a2 | 10/16/2014 | 11:25 | 7.6 | * | | |
| | | | | 124-75-20-a3 | 10/16/2014 | 11:30 | 11.0 | * | | |
| | | | | 124-75-20-a4 | 10/16/2014 | 11:35 | 25.3 | | * | |
| | | | | 124-75-20-b1 | 10/16/2014 | 11:40 | 17.3 | * | | |
| | | | | 124-75-20-b2 | 10/16/2014 | 11:45 | 15.6 | * | | |
| | | | | 124-75-20-b3 | 10/16/2014 | 11:50 | 29.3 | | * | |
| | | | | 124-75-20-b4 | 10/16/2014 | 11:55 | 65.3 | | * | |

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 58-67 | <20 | 124-67-20-a,b (A28) | 1665 | 124-67-20-a1 | 10/28/2014 | 11:30 | ** | | | |
| | | | | 124-67-20-a2 | 10/28/2014 | 11:35 | ** | | | |
| | | | | 124-67-20-a3 | 10/28/2014 | 11:40 | ** | | | |
| | | | | 124-67-20-a4 | 10/28/2014 | 11:45 | ** | | | |
| | | | | 124-67-20-b1 | 10/28/2014 | 11:50 | ** | | | |
| | | | | 124-67-20-b2 | 10/28/2014 | 11:55 | ** | | | |
| | | | | 124-67-20-b3 | 10/28/2014 | 12:00 | ** | | | |
| | | | | 124-67-20-b4 | 10/28/2014 | 12:05 | ** | | | |
| 75-58 | >1000 | 124-75-1000-a,b | 1600 | 124-75-1000-a1 | 10/29/2014 | 13:15 | ** | | | |
| | | | | 124-75-1000-a2 | 10/29/2014 | 13:20 | ** | | | |
| | | | | 124-75-1000-a3 | 10/29/2014 | 13:25 | ** | | | |
| | | | | 124-75-1000-a4 | 10/29/2014 | 13:30 | ** | | | |
| | | | | 124-75-1000-b1 | 10/29/2014 | 13:35 | ** | | | |
| | | | | 124-75-1000-b2 | 10/29/2014 | 13:40 | ** | | | |
| | | | | 124-75-1000-b3 | 10/29/2014 | 13:45 | ** | | | |
| | | | | 124-75-1000-b4 | 10/29/2014 | 13:50 | ** | | | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
10-02-2014

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1

Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos

## Perimeter Pools





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)

## Perimeter Pools





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)

## Perimeter Pools





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)

## Perimeter Pools





**Perimeter Pool S1** (Sta. S0+50 to S3+88)





**Perimeter Pool S2** (Sta. S4+38 to S10+60)

## Perimeter Pools




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

**Table 1**

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | | | | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO, FS-4


## Attachment 8: Quality and Level Data in GWET Wells

(not available as of this report date - provided on a quarterly basis)

- Summary of Groundwater Quality Data from GWET Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells

# Attachment 9: Surcharge Monitoring Update

- Figure C1: Instrumentation Location Plan 2N
- Figure G1: Instrumentation Location Plan 2S




| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS5 | 685595.33 | 602744.87 |
| FS6 | 685557.42 | 602879.95 |
| FS7 | 685445.18 | 603001.32 |
| SP11 | 685784.33 | 602832.31 |
| SP12 | 685740.52 | 602811.34 |
| SP13 | 685682.87 | 602934.55 |
| SP14 | 685624.73 | 603120.29 |
| SP15 | 685568.20 | 603092.95 |
| SP16 | 685617.61 | 602843.89 |
| SP17 | 685555.82 | 602977.36 |
| SP18 | 685562.79 | 602751.98 |
| SP19 | 685530.51 | 602838.96 |
| SP20 | 685429.14 | 602978.06 |
| VRC4 | 685521.71 | 602848.37 |

Installed Insturment Locations

Insturment Locations Not Installed

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
6. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS12 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |

Prepared/Date: RJR 08/15/13
Checked/Date: AE 08/15/13

0 15 30 60
SCALE IN FEET


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 2N
Project 3480-09-0006
Figure C1

Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SAE-6-7\CAD\SAR\100 Percent\Figure 2- Surcharge Settling Monitoring Plan – Area 2.dwg Thu, 15 Aug 2013 - 4:07pm roger.hulder




Instrumentation Locations Not Installed

Installed Instrumentation Locations

*Settlement Platforms have not been installed.

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
4. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–3 | 685146.51 | 602186.05 |
| FS–4 | 685000.10 | 602180.49 |
| FS–5 | 684747.04 | 602531.06 |
| HS–9 | 685225.80 | 602078.13 |
| HS–10 | 685015.29 | 602358.48 |
| HS–11 | 684872.76 | 602565.65 |
| HS–12 | 685121.52 | 602109.26 |
| HS–13 | 684729.05 | 602659.83 |
| HS–14 | 685107.56 | 602031.99 |
| HS–15 | 684880.03 | 602355.29 |
| SP–4 | 685191.86 | 602145.03 |
| SP–5 | 685065.13 | 602322.45 |
| SP–6 | 684931.76 | 602507.08 |
| SP–7 | 684731.82 | 602765.99 |
| VRC–4 | 685128.94 | 602095.79 |
| VRC–5 | 684991.20 | 602189.91 |
| VRC–6 | 684854.69 | 602569.90 |

VI–2 INCLINOMETER LOCATION

FS–1 SETTLEMENT MONITORING POINT FULL – SET UP

HS–1 SETTLEMENT MONITORING POINT HALF – SET UP

SP–12 SETTLEMENT MONITORING PLATFORM

RP APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7)

VRC1 VIBRATING WIRE PIEZOMETER IN STRATUM RC

0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 07/19/13
Checked/Date: AE 07/19/13

Revised DCB 001 7/29/13

| | | | |
|---|---|---|---|
| Honeywell 101 COLUMBIA RD., BOX 2105 MORRISTOWN, NJ 07962 | CHROMIUM REMEDY STUDY AREA 6 SOUTH JERSEY CITY, NEW JERSEY | amec | INSTRUMENTATION LOCATION PLAN 2S |


Figure G1

# Attachment 10: Sheet Pile Update

- Sheet Deflection Along Open Excavation
- Sheet Monitoring Locations
- Sheet Pile Repair Log
- Sheet Pile Angle Grout Log

# Sheet Deflection Along Open Excavation

Notes:
1. Deflection monitoring points are established at the top of the barrier wall at approximately 50 ft intervals. See Plan.
2. The barrier wall location was surveyed following installation.
3. Deflection readings are initiated at each Monitoring point in advance of the excavation.
4. Initial x-axis data point uses installed location inserted on a date immediately prior to excavation.
5. - - -The difference between the initial survey and the first reading prior to excavation is shown with a dashed line.
6. Movement during excavation is shown with a solid line.
7. Amec has initiated measures including removal of deadload and lowering the groundwater table on the open space side of the barrier wall with the objective of reducing deflection during excavation.







NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 03-20-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTES:

- Survey data collected with Trimble SPS882 and TSC2 Data Collector.
- Horizontal accuracy of 0.026 ft.
- Deflection measured at the top of the sheet.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SHEET MONITORING LOCATIONS 08-19-14

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-69
Entact ID:
Date Exposed: 8/29/14
Describe Damage: (13) Scrapes by the Cat 349E and 322C excavator buckets - 12"x48", (3) 1"ø, 1x8", 1/4x2", 1/2x3", 2"ø, 1x48", 1/2x12", 1/2x6", 1x5", 1/4x8". Cell 84

Damage Location (ft below top of sheet, inboard side outboard side): 9-14' outboard

Date Repaired: 9-4-14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-70
Entact ID:
Date Exposed: 8/29/14
Describe Damage: (9) Scrapes by the Cat 349E & 322C excavator buckets- 1x72", 1x60", (4) 1"ø, 1x3", 1/2x12", 1/2x8". Cell 83

Damage Location (ft below top of sheet, inboard side outboard side): 7-15' outboard

Date Repaired: 9/4/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-71
Entact ID:
Date Exposed: 8/29/14
Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets - (2) 2"ø, 3"x48", 1x48", 1x8", 1x12", 1/2x36", 1/2x12". Cell 83

Damage Location (ft below top of sheet, inboard side outboard side): 7-15' outboard

Date Repaired: 9/4/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-72
Entact ID:
Date Exposed: 8/29/14
Describe Damage: (7) Scrapes by the Cat 349E and 322C excavator buckets - 3"ø, 3x12", 1/2x3", 2x24", 2x12", 1x18", 1"ø. Cell 83

Damage Location (ft below top of sheet, inboard side outboard side): 5-15' outboard

Date Repaired: 9/11/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-75
Entact ID:
Date Exposed: 9/2/14
Describe Damage: (10) scrapes by the Cat 349E and 322C excavator buckets - 1/2 x 48", (4) 1x12", 1x6", 1x60", 1/4x24", 3x24", 2"Ø. Cell 82

Damage Location (ft below top of sheet, inboard side outboard side): 7-15' outboard

Date Repaired: 9/11/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-76
Entact ID:
Date Exposed: 9/2/14
Describe Damage: (7) Scrapes by the Cat 349E and 322C excavator buckets - 12"Ø, 1/4x12", 1x4", 1x18", 1/2x2", 1/2x6", 1"Ø. Cell 82.

Damage Location (ft below top of sheet, inboard side outboard side): 7-15' outboard

Date Repaired: 9/11/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-73
Entact ID:
Date Exposed: 9/2/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets - (3) 1x12", 1x48", (4) 1"Ø, 1/2x24", (2) 2"Ø, 1x4". Cell 83/82

Damage Location (ft below top of sheet, inboard side outboard side): 8-15' outboard

Date Repaired: 9/11/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-74
Entact ID:
Date Exposed: 9/2/14
Describe Damage: (6) scrapes by the Cat 349E and 322C excavator buckets - 1x6", 1x12", 1/2x36", (2) 1/2x24", 1/4x12". Cell 82

Damage Location (ft below top of sheet, inboard side outboard side): 9-15' outboard

Date Repaired: 9/11/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-77
Entact ID:
Date Exposed: 9/9/14
Describe Damage: (9) Scrapes by the Cat 349E and 322C excavator buckets ~ 48x6", (3) 1"Ø, 1x12", 1/2x18", 1x48", 1/2x6", 3"Ø. Cell 81

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 9/17/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-78
Entact ID:
Date Exposed: 9/9/14
Describe Damage: (3) Scrapes by the Cat 349E and Cat 322C excavator buckets- (2) 1"Ø, 1/2"Ø. Cell 81

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired: 9/17/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-79
Entact ID:
Date Exposed: 9/9/14
Describe Damage: (7) Scrapes by the Cat 349E and 322C excavator Buckets- 1x6", 1/2x36", (3) 1"Ø, 1/2x12", 2"Ø. Cell 81

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 10/3/14 Total, 9/17/14 Partial
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-80
Entact ID:
Date Exposed: 9/16/14
Describe Damage: (5) Scrapes by the Cat 349E and 322C excavator buckets- (2) 1/2x6", 1"Ø, 1x18", 4"Ø. Cell 80

Damage Location (ft below top of sheet, inboard side outboard side): 6-13' outboard

Date Repaired: 9/17/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-81

Entact ID:

Date Exposed: 9/16/14

Describe Damage: (10) Scrapes by the Cat 349E and 322C excavator buckets - (3) 1"Ø, (3) 1/2 x 12", 1x4", 6x36", 1/2x18", 3"Ø. Cell 80

Damage Location (ft below top of sheet, inboard side outboard side): 2-13' outboard

Date Repaired: 9/17/14 Partial, 9/25/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 9/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-82

Entact ID:

Date Exposed: 9/16/14

Describe Damage: (4) Scrapes by the Cat 349EExcavator bucket - 1/2x72", 1/2x60", 1"x24", 1/2x12". Cell 80.

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 9/17/14 Partial, 9/25/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 9/25/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 19P-83

Entact ID:

Date Exposed: 9/17/14

Describe Damage: (7) Scrapes by the Cat 349E and 322 C excavator buckets - 1/2x60", (3) 1"Ø, 1/2x6", 3"Ø, 1x12". Cell 79

Damage Location (ft below top of sheet, inboard side outboard side): 2-11' outboard

Date Repaired: 9/23/14 Partial, 10/3/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-1

Entact ID:

Date Exposed: 9/18/14

Describe Damage: (10) Scrapes by the Cat 349E and 322C excavator buckets - (4) 1"Ø, 1x24", 8"Ø, 1/2x36", 1/2x6", 2x4", 1/4x12". Cell 79.

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 9/23/14 Partial, 10/3/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-2
Entact ID:
Date Exposed: 9/18/14
Describe Damage: (6) scrapes by the Cat 349E and 322C excavator buckets- 6"Ø, (2) 1/2x12", 1/2x24", 1x4", 1x8". Cell 79

Damage Location (ft below top of sheet, inboard side outboard side): 3-13' outboard

Date Repaired: 9/23/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-3
Entact ID:
Date Exposed: 9/19/14
Describe Damage: (9) scrapes by the Cat 349E and 322C excavator buckets- 1x12", 1x48", 1/2x6", (3) 1"Ø, 1/4x60", 2x12", 3"Ø, 1x24". Cell 79/78

Damage Location (ft below top of sheet, inboard side outboard side): 5-12' outboard

Date Repaired: 9/23/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-4
Entact ID:
Date Exposed: 9/19/14
Describe Damage: (8) scrapes by the Cat 349E and 322C excavator buckets- (3) 1/2x24", 1/4x12", 1/4x24", 1x36", 5"Ø, 1/2x6". Cell 78

Damage Location (ft below top of sheet, inboard side outboard side): 2-12' outboard

Date Repaired: 9/23/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14 * x <

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-5
Entact ID:
Date Exposed: 9/19/14
Describe Damage: (7) scrapes by the Cat 349E and 322C excavator buckets- (2) 1/2x36", (2) 1/2"Ø, 1/2x12", 1x12", 1x6". Cell 78.

Damage Location (ft below top of sheet, inboard side outboard side): 5-12' outboard

Date Repaired: 9/23/14 Partial, 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-6
Entact ID:
Date Exposed: 9/19/14
Describe Damage: (8) scrapes by the Cat 349E and 322C excavator buckets - (3) 1"Ø, 1×48", 1×6, ½×18", 3×24", 12"Ø. Cell ~~78~~

Damage Location (ft below top of sheet, inboard side outboard side): 1 - 13' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: B.Shea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-7
Entact ID:
Date Exposed: 9/23/14
Describe Damage: (12) scrapes by the Cat 349E and 322 C excavator buckets - ½×60", 2×24", ¼×72", (2) ½"Ø, (2) 2Ø", 1×6", 3×6", 12"×36", ¼×12", 3"Ø. Cell 77

Damage Location (ft below top of sheet, inboard side outboard side): 2-13' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: B.Shea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-8
Entact ID:
Date Exposed: 9/23/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets - ½×48", 1×18", 3"Ø, 1×12", ¼×48", (3) 1"Ø, (3) 2"Ø, 2×10". Cell 77.

Damage Location (ft below top of sheet, inboard side outboard side): 6" - 12' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: B.Shea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-9
Entact ID:
Date Exposed: 9/23/14
Describe Damage: (11) scrapes by the Cat 349E and 322C excavator buckets - 1"Ø, 4"Ø, ½×2", ½×6", 1×36", 1×18", ½×24", 2×6", 2"Ø ¼×3", 3×12". Cell 77/76

Damage Location (ft below top of sheet, inboard side outboard side): 3-12' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: B.Shea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-10

Entact ID:

Date Exposed: 9/23/14

Describe Damage: (10) scrapes by the Cat 349E and 322C excavator buckets- 6x18", 1/2x48", 1/2x48", 1x24", 1x8", 2"ø, 1"ø, 1/2x72", 2x18", 1"ø,. Cell 76

Damage Location (ft below top of sheet, inboard side outboard side): 3-13' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-11

Entact ID:

Date Exposed: 9/23/14

Describe Damage: (7) Scrapes by the Cat 349E and 322C excavator buckets- 1/4x84", 1/2x72", 1x8", 4"ø, 1x12", 1/2"ø, 1x2". Cell 76

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-12

Entact ID:

Date Exposed: 9/26/14

Describe Damage: (12) Scrapes by the Cat 349E and 322C excavator buckets- 1x18", 1x6", 1x12", 1x2", 1/2x48", (2)1"ø, 1/2x24", (3) 1/2"ø, 2x6", Cell 76

Damage Location (ft below top of sheet, inboard side outboard side): 1-13' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-13

Entact ID:

Date Exposed: 9/26/14

Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets- 1/2x6", (2) 1/2x8", 1x12", 1x36", 4"ø, 18"ø, 1/4x24". Cell 75

Damage Location (ft below top of sheet, inboard side outboard side): 3-12' outboard

Date Repaired: 9/29/14 Partial, 10/3/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 20P1-14
Entact ID:
Date Exposed: 9/29/14
Describe Damage: (10) scrapes by the Cat 349E and 322C excavator buckets- 1/2x2", 1/2x6", (3) 1/2"ø, 2x12", 3x12", 1/2x24", 1/4x96", 1x4". Cell 75

Damage Location (ft below top of sheet, inboard side outboard side): 2-12' outboard

Date Repaired: 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 20P1-15
Entact ID:
Date Exposed: 9/29/14
Describe Damage: (9) scrapes by the Cat 349E and 322C excavator buckets- 1x48", (6) 1"ø, 1x8", 2x8". Cell 75.

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 10/3/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/3/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 23P1A-1
Entact ID:
Date Exposed: 9/29/14
Describe Damage: (13) scrapes by the Cat 349E and 322C excavator buckets- (5) 1"ø, 1x36", 1/2x12", 1/2x36", 1x6", 2x4", 1/2"ø, 1/4x48", 1/4x6". Cell 75/74

Angle damaged during driving process. New 5x5" angle welded back on and grouted.

Damage Location (ft below top of sheet, inboard side outboard side): 10-16' outboard

Date Repaired: 10/1/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-1
Entact ID:
Date Exposed: 9/30/14
Describe Damage: (21) Scrapes by the Cat 349E excavator bucket - 6x24", (16) 1"ø, 1/2x3", 1x4", 1/2x12", 1/4x84", 2"ø. Cell 74

Damage Location (ft below top of sheet, inboard side outboard side): 7-16' outboard

Date Repaired: 10/1/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-2
Entact ID:
Date Exposed: 10/1/14
Describe Damage: (10) Scrapes by the Cat 349E and 322C excavator buckets- 3"Ø, (4)1"Ø, 1"x84", 1x36", 2x18", 2x12", 3x6". Cell 74

Damage Location (ft below top of sheet, inboard side outboard side): 7-16' outboard

Date Repaired: 10/1/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 21P1-3
Entact ID:
Date Exposed: 10/1/14
Describe Damage: (12) Scrapes by the Cat 349E and 322C excavator buckets- 1x2", 1x8", 1x36", 1/2x78", 1x72", 1/2x6", 2x12", 1/2x8", 1/2x24", 2"Ø, 1x4", 1x18". Cell 74/73

Damage Location (ft below top of sheet, inboard side outboard side): 5-17' outboard

Date Repaired: 10/7/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-4
Entact ID:
Date Exposed: 10/1/14
Describe Damage: (16) scrapes by the Cat 349E and 322C excavator buckets- (9)1"Ø, 1x2", 1/2x12", 1/2x60", 3"x72", 1x36", 1x72", 2"Ø. Cell 73

Damage Location (ft below top of sheet, inboard side outboard side): 6-17' outboard

Date Repaired: 10/7/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-5
Entact ID:
Date Exposed: 10/2/14
Describe Damage: (6) Scrapes by the Cat 349E and 322C excavator buckets- 1/4x24", 1x8", 1x3", 1x18", 1/4x4", 2x4". Cell 73

Damage Location (ft below top of sheet, inboard side outboard side): 10-17' outboard

Date Repaired: 10/7/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-6
Entact ID:
Date Exposed: 10/2/14
Describe Damage: (9) scrapes by the Cat 349E and 322C excavator buckets- 1/2x3", 6x18", 1x12", 1/2x12", 1x12", 2x8", 1x8", 1/4x36", 6x24". Cell 73-72

Damage Location (ft below top of sheet, inboard side outboard side): 10-17' outboard

Date Repaired: 10/7/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-7
Entact ID:
Date Exposed: 10/2/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets- 1/2x84", 1/2x36", 1"Ø, 1x24", 1"Ø, 3x12", 2"x48", (2)1x6", 1x2", 1/4x18", 1/4x12". Cell 72

Damage Location (ft below top of sheet, inboard side outboard side): 7-17 outboard

Date Repaired: 10/7/14 Partial, 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-8
Entact ID:
Date Exposed: 10/2/14
Describe Damage: (14) scrapes by the Cat 349E and 322C excavator buckets- 1x84", 2"Ø, (3)1x2", 1/2x72", 1/2x8", 1"Ø, 1x96", 1/4x24", 1/4x18", 4"Ø, 1x4", 1/4x12". Cell 72

Damage Location (ft below top of sheet, inboard side outboard side): 1-17 outboard

Date Repaired: 10/7/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-9
Entact ID:
Date Exposed: 10/2/14
Describe Damage: (17) scrapes by the Cat 349E and 322 C excavator buckets- 2x6", (3)1"Ø, 1x84", 3x48", 1x12", 6x18", 1x3", 1/2x84", 1/2x36", 1x6", (2)1/2x12", (2)1/4x18", 6"Ø. Cell 72

Damage Location (ft below top of sheet, inboard side outboard side): 2-17 outboard

Date Repaired: 10/7/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-10
Entact ID:
Date Exposed: 10/6/14
Describe Damage: (10) scrapes by the Cat 349E and 322C excavator buckets- 1"Ø, 2×18", 1×48", 1/2"Ø, 1×6", (3)1×12", 1/2×84", 12"Ø. Cell 71

Damage Location (ft below top of sheet, inboard side outboard side): 7- 17" outboard

Date Repaired: 10/10/14 Total
Inspected by: BnanShea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG

Sheet Number/DB ID: 21P1-11
Entact ID:
Date Exposed: 10/6/14
Describe Damage: (11) scrapes by the Cat 349E and 322C excavator buckets- 1×120", 2"Ø, 1×36", 3"Ø, 1×18", 2×12", 1/2×60", 1/2×48", 1×6", 3×12", 1/2×4". Cell 71

Damage Location (ft below top of sheet, inboard side outboard side): 5-17' outboard

Date Repaired: 10/10/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire bwsh, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-12
Entact ID:
Date Exposed: 10/6/14
Describe Damage: (16) scrapes by the Cat 349E and 322C excavator buckets- 2"Ø, 10"Ø, 1/2×48", 1"Ø, (3) 1/2"Ø, 1/4×2", 1/4×60", 1×48", 1×8", 1×3", 3"Ø, 6×18". Cell 71

Damage Location (ft below top of sheet, inboard side outboard side): 10-17' outboard

Date Repaired: 10/10/14 Total
Inspected by: BnanShea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 21P1-13
Entact ID:
Date Exposed: 10/6/14
Describe Damage: (10) scrapes by the Cat 349E and 322C excavator buckets- 18"Ø, 3"Ø, 1×18", 1/2×48", 1/4×96", 1/2×18", 1×36", (3)1"Ø. Cell 71-70.

Damage Location (ft below top of sheet, inboard side outboard side): 6-17' outboard

Date Repaired: 10/10/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/10/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-1
Entact ID:
Date Exposed: 10/7/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets- (6) 1"Ø, 1/2 x 60", 1 x 8", 1/2 x 12", 2 x 12", 2 x 4", 1/4 x 18". Cell 70

Damage Location (ft below top of sheet, inboard side outboard side): 7-16' outboard

Date Repaired: 10/10/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-2
Entact ID:
Date Exposed: 10/7/14
Describe Damage: (7) Scrapes by the Cat 349E and 322 C excavator buckets- 1/2 x 60", 1 x 36", (2) 1 x 12", 4 x 36", (2) 1"Ø. Cell 70

Damage Location (ft below top of sheet, inboard side outboard side): 6-16' outboard

Date Repaired: 10/10/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-3
Entact ID:
Date Exposed: 10/8/14
Describe Damage: (13) Scrapes by the Cat 349E and 322C excavator buckets- 1/2 x 24", 1 x 24", 1 x 48", 1 x 8", 1/2 x 6", 1/2 x 36", (2) 1/2 x 12", 1/4 x 6", 1/4 x 24", 2 x 6", 1"Ø, 1/2 x 2". Cell 70/69

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 10/14/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-4
Entact ID:
Date Exposed: 10/8/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets- 2 x 48", 2 x 6", 1 x 30", 1 x 18", (2) 1"Ø, 1/2 x 36", 1/4 x 12", 1/4 x 4", 1/2 x 8", 3 x 8", 3"Ø. Cell 69.

Damage Location (ft below top of sheet, inboard side outboard side): 7-13' outboard

Date Repaired: 10/14/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-5
Entact ID:
Date Exposed: 10/10/14
Describe Damage: (15) scrapes by the Cat 349E and 322C excavator buckets- 6×84", 2×36", 8"Ø, (3)1"Ø, 1/4×48", 1/2×6", 1×4", 1/4×6", 1×24", 1/2×3", (2)1/2"Ø, 4"Ø. Cell 69.
Damage Location (ft below top of sheet, inboard side outboard side): 6-16' outboard
Date Repaired: 10/14/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-6
Entact ID:
Date Exposed: 10/10/14
Describe Damage: (14) scrapes by the Cat 349E and 322C excavator buckets- (3)1/2"Ø, 2×24", 4"Ø, 1/2×8", 1"Ø, 1×12", 1×36", 1×60", 1/4×60", 1×8", 1×6", 1/2×36". Cell 69.
Damage Location (ft below top of sheet, inboard side outboard side): 4-16' outboard
Date Repaired: 10/14/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-7
Entact ID:
Date Exposed: 10/10/14
Describe Damage: (16) scrapes by the Cat 349E and 322C excavator buckets- 1/4×48", 6"×120", (4)1/2"Ø, (3)1"Ø, 1/2×24", 1×8", 1×18", 1×48", 1/4×4", 1×3", 1×18". Cell 68.
Damage Location (ft below top of sheet, inboard side outboard side): 7-16' outboard
Date Repaired: 10/14/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-8
Entact ID:
Date Exposed: 10/10/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets- 1×120", 2"Ø, 2×48", 1×6", 1/2×4", (3)1"Ø, 1×108", 1/2×18", 3"Ø, 1"Ø. Cell 68
Damage Location (ft below top of sheet, inboard side outboard side): 6-16' outboard
Date Repaired: 10/14/14 Partial, 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P-9

Entact ID:

Date Exposed: 10/13/14

Describe Damage: (19) Scrapes by the Cat 349E and 322C excavator buckets - (8) 1"Ø, 1x12", 4"Ø, 4x84", 1/2x72", 2x12", 1/2x4", 1x4", (3) 1/2x8", 1/4x60". Cell 68.

Damage Location (ft below top of sheet, inboard side outboard side): 10-16' outboard

Date Repaired: 10/14/14 partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-10

Entact ID:

Date Exposed: 10/13/14

Describe Damage: (13) scrapes by the Cat 349E and 322C excavator buckets (6) 1"Ø, 1/2x84", (2) 1/2x12", 1x8", 1/4x36", (2) 1x4". Cell 67

Damage Location (ft below top of sheet, inboard side outboard side): 10-17' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-11

Entact ID:

Date Exposed: 10/14/14

Describe Damage: (15) Scrapes by the Cat 349E and 322C excavator buckets (4) 1/2"Ø, (3) 1"Ø, (2) 1x48", 1x18", 2x10", 1/2x6", 1/2x3", 4"Ø, 2"Ø. Cell 67

Damage Location (ft below top of sheet, inboard side outboard side): 10-17' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P-12

Entact ID:

Date Exposed: 10/14/14

Describe Damage: (10) scrapes by the Cat 349E and 322 C excavator buckets - 1/2x36", 1/2x24", 1x12, (4) 1/2"Ø, (2) 1x6", 1/4x24". Cell 67.

Damage Location (ft below top of sheet, inboard side outboard side): 10-15' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22PI-13
Entact ID:
Date Exposed: 10/21/14
Describe Damage: (13) scrapes by the Cat 349E and 322C excavator buckets- (6) 1/2"Ø, (3) 1/2x12", 2x12", 1/2x18", 1/2x3", 3"Ø. Cell 67/66

Damage Location (ft below top of sheet, inboard side outboard side): 11-15' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22PI-14
Entact ID:
Date Exposed: 10/21/14
Describe Damage: (20) scrapes by the Cat 349E and 322C excavator buckets- (10) 1/2"Ø, 1x12", 1x6", 4"Ø, (3) 1"Ø, 1/2x6", 1/2x3", 1/2x12", 1x4". Cell 66.

Damage Location (ft below top of sheet, inboard side outboard side): 8-14' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22PI-15
Entact ID:
Date Exposed: 10/21/14
Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets- (4) 1"Ø, 1/2"Ø, 1x12", 1/2x6", 1/2x24", 3x6", 1x2", 1/4x3", 1x4". Cell 66

Damage Location (ft below top of sheet, inboard side outboard side): 9-13' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22PI-16
Entact ID:
Date Exposed: 10/21/14
Describe Damage: (9) scrapes by the Cat 349E and 322C excavator buckets- 1x3, 1x4, (3) 1"Ø, (2) 1/2"Ø, 1x36", 1/2x24. Cell 66/65

Damage Location (ft below top of sheet, inboard side outboard side): 2-13' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-17

Entact ID:

Date Exposed: 10/21/14

Describe Damage: (10) scrapes by the Cat 349E and 322C excavator buckets- 1/2x48", 1x12", 1x8", 1/2x3", 1/2x24", (4) 1"Ø, 6"Ø. Cell 65

Damage Location (ft below top of sheet, inboard side outboard side): 7-13' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-18

Entact ID:

Date Exposed: 10/21/14

Describe Damage: (8) Scrapes by the Cat 349E and 322C excavator buckets- 1/2x12", 12x24", (2) 1/2x6", 1"Ø, 4"Ø, 1/2x36", 1x8". Cell 65

Damage Location (ft below top of sheet, inboard side outboard side): 3-13' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-19

Entact ID:

Date Exposed: 10/21/14

Describe Damage: (8) scrapes by the Cat 349E and 322C excavator buckets- 1x18", 4x12", 3"Ø, (3) 1/2"Ø, 1x24, 1/4x24". Cell 65

Damage Location (ft below top of sheet, inboard side outboard side): 4-14' outboard

Date Repaired: 10/21/14 Partial, 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-20

Entact ID:

Date Exposed: 10/21/14

Describe Damage: (10) Scrapes by the Cat 349E and 322C excavator buckets- 8"Ø, (5) 1"Ø, 1/2x36", 1/2x8", 1/4x18", 3"Ø. Cell 64

Damage Location (ft below top of sheet, inboard side outboard side): 6-14' outboard

Date Repaired: 10/27/14 Partial, 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-21

Entact ID:

Date Exposed: 10/21/14

Describe Damage: (12) scrapes by the Cat 349E and 322C excavator buckets- 1x24", 1x18", 1/2x66", 2x8", 10"Ø, (4) 1"Ø, 1x48", (2) 1/2"Ø. Cell 64

Damage Location (ft below top of sheet, inboard side outboard side): 4-14' outboard

Date Repaired: 10/27/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Presssure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-22

Entact ID:

Date Exposed: 10/21/14

Describe Damage: (11) Scrapes by the Cat 349E and 322C excavator buckets- 1/2x18", 1/2x2", 1/2x6", (2) 1x12", 3x18", 1/4x8, 1/4x12", 3"Ø, (2) 1/2"Ø. Cell 64/63

Damage Location (ft below top of sheet, inboard side outboard side): 5-14' outboard

Date Repaired: 10/27/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-23

Entact ID:

Date Exposed: 10/24/14

Describe Damage: (14) Scrapes by the Cat 349E ~~exc~~ 322 excavator buckets- 1/4x12", 2"Ø, 1x36", 1x18", 1"Ø, 1/2"Ø, (2) 1x6", 1/2x3", 1/4x48", (2) 1x4", 3"Ø, 3x12". Cell 63

Damage Location (ft below top of sheet, inboard side outboard side): 4-14' outboard

Date Repaired: 10/27/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-24

Entact ID:

Date Exposed: 10/24/14

Describe Damage: (14) Scrapes by the Cat 349E and 322C excavator buckets- 1/2x12", (2) 1x36", 1/2x48", 1x6", 1x24", 1x36", 3"Ø, (4) 1"Ø, 1/2x12", 1/2x3". Cell 63

Damage Location (ft below top of sheet, inboard side outboard side): 2-14' outboard

Date Repaired: 10/27/14 Partial, 10/29/14 Total

Inspected by: Bnan Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-25
Entact ID:
Date Exposed: 10/24/14
Describe Damage: (19) scrapes by the Cat 349E and 322C excavator buckets - 1x36", 1x18", (2)3"Ø, 1/2x36", 3x8", 1x6", 1x8", (4)1/2x4", 6x36", (6)1"Ø. Cell 63

Damage Location (ft below top of sheet, inboard side outboard side): 3-13' outboard

Date Repaired: 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-26
Entact ID:
Date Exposed: 10/24/14
Describe Damage: (15) scrapes by the Cat 349E and 322C excavator buckets - (7)1"Ø, 4x72", (2)1x12", 1x6", 3x12", 1/2"Ø, (2)2"Ø. Cell 63/62.

Damage Location (ft below top of sheet, inboard side outboard side): 3-13' outboard

Date Repaired: 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 22P1-27
Entact ID:
Date Exposed: 10/24/14
Describe Damage: (21) scrapes by the Cat 349E and 322C excavator buckets - (11)1"Ø, 1x48", (2)1/2x36", (2)1x6", 1x3", 1/2x12", (3)2x4". Cell 62.

Damage Location (ft below top of sheet, inboard side outboard side): 4-13' outboard

Date Repaired: 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-1
Entact ID:
Date Exposed: 10/24/14
Describe Damage: (21) scrapes by the Cat 349E and 322C excavator buckets - (10)1"Ø, 1/2x2", 1/2x18", 1x36", 1x24", 1/4x8", 1x12", 2"Ø, 1x6", 1/2x12", 2x6", 1/4x6". Cell 62

Damage Location (ft below top of sheet, inboard side outboard side): 3-12' outboard

Date Repaired: 10/29/14 Total
Inspected by: Brian Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-2
Entact ID:
Date Exposed: 10/24/14
Describe Damage: (12) Scrapes by the Cat 349E and 322C excavator buckets- 1x84", (4) 1"Ø, 1x36", 1/2x4", 1/2x2", 2x12", 1x6", (2) 1/2"Ø. Cell 62

Damage Location (ft below top of sheet, inboard side outboard side): 1-13 outboard

Date Repaired: 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-3
Entact ID:
Date Exposed: 10/28/14
Describe Damage: (19) Scrapes by the Cat 349E and 322C excavator buckets- (9) 1"Ø, 1x72", 1x18", 1/2x36", 1/2"x12", (2) 1x6", (2) 1/2x24", 1x48", 1/4x36". Cell 61

Damage Location (ft below top of sheet, inboard side outboard side): 2-13' outboard

Date Repaired: 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-4
Entact ID:
Date Exposed: 10/28/14
Describe Damage: (20) Scrapes by the Cat 349E and 322C excavator buckets- (4) 1x36", 1x72", (7) 1"Ø, (3) 1x6", 1/4x24", 1/4x8", 1/2x6", 1/2"3", 1/2"Ø. Cell 61

Damage Location (ft below top of sheet, inboard side outboard side): 1-12' outboard

Date Repaired: 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-5
Entact ID:
Date Exposed: 10/28/14
Describe Damage: (21) scrapes by the Cat 349E and 322C excavator buckets- (8) 1"Ø, (4) 1/2"Ø, (2) 1x6", 1/4x72", 2"Ø, 2x4", 1/2x6", 1/2x10", 2"Ø, 3'Ø. Cell 61

Damage Location (ft below top of sheet, inboard side outboard side): 2-13' outboard

Date Repaired: 10/29/14 Total
Inspected by: Bnan Shea
Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.
Repair Log Closure: AMEC Signature: BShea
Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-6

Entact ID:

Date Exposed: 10/28/14

Describe Damage: (27) scrapes by the Cat 349E and 322C excavator buckets- (4) 1×12", (2) 1×48", 1/2×36", 3×12", (3) 1×6", 3×8", 3"Ø, (3) 2"Ø, (11) 1"Ø. Cell 61/60

Damage Location (ft below top of sheet, inboard side outboard side): 1-13' outboard

Date Repaired: 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-7

Entact ID:

Date Exposed: 10/28/14

Describe Damage: (27) scrapes by the Cat 349E & 322C excavator buckets- (6) 1×6", 3×18", (6) 1"Ø, 1/2×36", 2×18", 12"Ø, (3) 2"Ø, 1×24", 1/4×36", 1×3", (5) 1/2"Ø. Cell 60

Damage Location (ft below top of sheet, inboard side outboard side): 0 - 13' outboard

Date Repaired: 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-8

Entact ID:

Date Exposed: 10/28/14

Describe Damage: (29) Scrapes by the Cat 349E and 322C excavator buckets- (11) 1"Ø, (8) 1×6", (3) 1×24", 3×6", 2×18", 6"Ø, (4) 1/2"Ø. Cell 60.

Damage Location (ft below top of sheet, inboard side outboard side): 1-13' outboard

Date Repaired: 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-9

Entact ID:

Date Exposed: 10/28/14

Describe Damage: (39) scrapes by the Cat 349E and 322C excavator buckets- 24"Ø, (17) 1"Ø, 6"Ø, (3) 3"Ø, (9) 1×6", 1/2×48", 1/2×24", 1/4×36", 5"Ø, (4) 1/2"Ø. Cell 60/59

Damage Location (ft below top of sheet, inboard side outboard side): 1-13' outboard

Date Repaired: 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-10

Entact ID:

Date Exposed: 10/28/14

Describe Damage: (35) scrapes by the Cat 349E and 322C excavator buckets - 18×36", (15)1"Ø, (3)1/2"Ø, (2)1×36", (3)1×18", (5)1×6", (2)1/2×12", 2×8", 4"Ø, 2"Ø, 1/2×2". Cell 59.

Damage Location (ft below top of sheet, inboard side outboard side): 0-13' outboard

Date Repaired: 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: 24P1-11

Entact ID:

Date Exposed: 10/28/14

Describe Damage: (12) Scrapes by the Cat 349E and 322C excavator buckets - 6"Ø, 1×48", (2)1×24", (3)2"Ø, (3)1×6", 1×18", 3×24". Cell 59

Damage Location (ft below top of sheet, inboard side outboard side): 5-13' outboard

Date Repaired: 10/29/14 Total

Inspected by: Brian Shea

Describe Repair: Pressure wash, wire brush, apply epoxy w/ a 2" paint brush.

Repair Log Closure: AMEC Signature: BShea

Date: 10/29/14

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:

Entact ID:

Date Exposed:

Describe Damage:

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired:

Inspected by:

Describe Repair:

Repair Log Closure: AMEC Signature:

Date:

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:

Entact ID:

Date Exposed:

Describe Damage:

Damage Location (ft below top of sheet, inboard side outboard side):

Date Repaired:

Inspected by:

Describe Repair:

Repair Log Closure: AMEC Signature:

Date:

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

10/15/2014
SA-6 South Sheet Pile Angle Grout Log

| Batch | Time | Sheets |
|---|---|---|
| 89 | 9:11 | 19P1-52 |
| | | |
| 90 | 9:18 | 19P1-53 |
| 90 | 9:21 | 19P1-55* |
| | | |
| 91 | 9:28 | 19P1-55* |
| 91 | 9:30 | 19P1-56 |
| | | |
| 92 | 9:32 | 19P1-57 |
| 92 | 9:34 | 19P1-58 |
| 92 | 9:35 | 19P1-59 |
| 92 | 9:37 | 19P1-60* |
| | | |
| 93 | 9:39 | 19P1-60* |
| 93 | 9:41 | 19P1-61 |
| 93 | 9:42 | 19P1-62 |
| 93 | 9:43 | 19P1-66 |
| | | |
| 94 | 9:52 | 19P1-68 |
| 94 | 9:55 | 19P1-69 |
| 94 | 9:56 | 19P1-70 |
| 94 | 10:00 | 19P1-71 |
| | | |
| 95 | 10:10 | Top off |
| | | 19P1-52 to |
| | | 19P1-71 |
| 95 | 10:14 | 19P1-73 |
| 95 | 10:16 | 19P1-74 |
| | | |
| 96 | 13:45 | 19P1-63 |
| | | |
| | | |

| Batch | Time | Sheets |
|---|---|---|
| 97+98 | 13:55 | Top off |
| | | 19P1-52 to |
| | | 19P1-74 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

* Partial Angle

# Attachment 11: Weekly SWPPP Reports

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 3, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 2,3,4 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 5 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 6,7 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | | X | | 8 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 9 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/03/14

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, October 03, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence on both the northern and the southern slopes of surcharge area 1-S is improperly toed in or requires maintenance. |
| 2 | IA2Q4A1AL8 | Exclusion Zone signage on the temporary sheet pile at the west end of Kellogg Street is still in place after the area has been excavated and partially backfilled and is no longer considered an EZ. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing requires maintenance or is completely missing at several locations along the northern perimeter of SA-6 South EZ. |
| 4 | IA2Q4A1AL8 | No Exclusion Zone signage or barrier is present between the clean surcharge area and the consolidated cap material in surcharge area 2-S. |
| 5 | IA2Q4A1AL8 | No silt dams are present at the toe of the 2-S surcharge area along the north side. |
| 6 | IA2Q4A1AL8 | An installed well vault in the SA-6 South backfill area sticks up 3"-4" above surrounding grade. |
| 7 | IA2Q4A1AL8 | The stone on the roadway outside of the eastern exit of the SA-6 South Exclusion Zone is becoming blinded with sediment. |
| 8 | IA2Q4A1AL8 | Straw wattle at the gaps in the 12" berm along the western SA-7 roadway has degraded and is no longer functional. |
| 9 | IA2Q4A1AL8 | Sediment is present on the southern and northern SA-7 roadways. |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 10/03/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or re-install the missing or damaged sections of silt fence at the toe of the 1-S surcharge pile. Insure that all silt fence is properly toed in. | 10-8-14 RAD |
| 2 | Remove all Exclusion Zone signage which is no longer required. | 10-3-14 RAD |
| 3 | Repair or replace any sections of orange warning fencing which surrounds the SA-6 South EZ. Install fencing to eliminate any gaps which may be present. | 10-3-14 RAD |
| 4 | Install Exclusion Zone signs to delineate the western edge of the EZ in surcharge area 2-S. | 10-6-14 RAD |
| 5 | Construct silt dams or install acceptable erosion control measures along the northern edge of the 2-S surcharge area. | 10-3-14 RAD |
| 6 | Install backfill material around the well vault in the western backfill area of SA-6 South, bringing it to grade and protecting the vault and/or vehicles from damage. | 10-7-14 RAD |
| 7 | Remove and replace any stone containing sediment on the outside of the eastern SA-6 South CRZ. | 10-7-14 RAD |
| 8 | Replace any degraded straw wattle along the western SA-7 roadway. | 10-6-14 RAD |
| 9 | Clean the northern and southern SA-7 roadways. | 10-8-14 RAD |

**Construction Manager:** _____ **Date:** 10/08/14

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 9, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 North & GWTP** | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-7 & Novartis Stockpile** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/09/14

**SWPPP Observer:** _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, October 09, 2014**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence on both the northern and the southern slopes of surcharge area 1-S is improperly toed in or missing and requires maintenance. Silt dams are not present at toe of slope. |
| 2 | IA2Q4A1AL8 | Erosion control fabric on the western end of surcharge stockpile 1-S his blown loose around the edges and requires maintenance. Additional fabric is required on the northwest corner of the stockpile. |
| 3 | IA2Q4A1AL8 | Material stockpiles in the eastern end of the SA-6 South exclusion zone are piled to within 6 inches of the top of their containment along the north side abutting SA-7. |
| 4 | IA2Q4A1AL8 | Silt baskets in the storm water catch basins located on the eastern roadway of SA-7 are accumulating sediment. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 10/09/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair/install the damaged or missing sections of silt fence at the toe of the 1-S surcharge pile. Install stone-filled silt dams along toes as required. | 10/10/14 RAD |
| 2 | Re-anchor the erosion control fabric on the western end of the 1-S stockpile. Install additional fabric to protect the recently completed northwest corner of the pile. | 10/14/14 RAD |
| 3 | Remove stockpile material that has accumulated to within 12" of the top of the northern containment wall. | 10/14/14 RAD |
| 4 | Replace the filter fabric in the storm water catch basins located on the eastern SA-7 roadway. | 10/15/14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 10/15/14

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 16, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☑ Post Storm

**Weather Conditions:** ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 1 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 4 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/16/14

**SWPPP Observer:** _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Thursday, October 16, 2014

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Storm water run-off has created approximately ten rills/gullies in the north face of the 1-S surcharge stockpile. |
| 2 | IA2Q4A1AL8 | Storm water is ponded at various locations inside the eastern SA-6 South exclusion zone. |
| 3 | IA2Q4A1AL8 | Silt fence along the toe of the north side of the 1-S surcharge pile has been compromised at several locations. |
| 4 | IA2Q4A1AL8 | Silt dams along the toe of the 2-S surcharge pile are damaged at several locations. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 10/16/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Fill in the erosions in the northern face of the stockpile and tight-roll or otherwise stabilize the top of the pile and the slope face. | 10/20/14 RAD |
| 2 | Pump ponded storm water to the Construction Water Treatment Plant for treatment and discharge to PVSC. | 10/17/14 RAD |
| 3 | Repair/re-install silt fence as required. Install additional erosion control measures as necessary to prevent sediment from breaching protective measures in the area. | 10/22/14 RAD |
| 4 | Replace or augment the damaged soil-filled sediment check dams at the northern toe of surcharge area 2-S with stone-filled check dams. | 10/21/14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 10/22/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: October 23, 2014

Type of Inspection: ☑ Regular ☑ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 3 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 4 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | | X | | 6 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 7 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 8 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 9 |
| Perimeter Fencing/Windscreen | | X | | 10 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 10/23/14

SWPPP Observer: _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, October 23, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence along the southern side of the 1-S surcharge stockpile requires maintenance/repair |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing on the north side of the EZ requires maintenance/repair |
| 3 | IA2Q4A1AL8 | Cover fabric on the western end of the 1-S surcharge stockpile has blown out of place. |
| 4 | IA2Q4A1AL8 | Storm water is ponded at various locations on the backfill area and in the haul roads. |
| 5 | IA2Q4A1AL8 | A stone tracking pad is required on the on the haul road which runs between SA-7 and SA-6 to the east of the sedimentation basin. |
| 6 | IA2Q4A1AL8 | The perimeter fence at the northeastern corner of the sedimentation basin has gaps between fence panels. |
| 7 | IA2Q4A1AL8 | Silt fence along the northern side of the 1-S surcharge stockpile requires maintenance/repair and the removal of accumulated sediment on the inboard side. |
| 8 | IA2Q4A1AL8 | REPEAT ITEM: Sediment containment measures along the northern toe of the 1-S surcharge stockpile are inadequat and require substantial improvement. |
| 9 | IA2Q4A1AL8 | Sediment has accumulated on the SA-7 access roadways. |
| 10 | IA2Q4A1AL8 | Windscreen on the northern perimeter of SA-7 adjacent to the former JCIA facility requires maintenance. |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ (Signature) Date: 10/23/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Maintain or re-install silt fencing to contract specifications. | 10/29/14 RAD |
| 2 | Maintain or repair orance EZ fencing. Check daily to confirm the integrity of the fenceline. | 10/24/14 RAD |
| 3 | Repair/re-install silt fence as required. Install additional erosion control measures as necessary to prevent sediment from breaching protective measures in the area. | 10/29/14 RAD |
| 4 | Replace or augment the damaged soil-filled sediment check dams at the northern toe of surcharge area 2-S with stone-filled check dams. | 10/24/14 |
| 5 | Install a stone tracking pad to reduce the tracking of sediment from SA-6 North to SA-7 | 10/23/14 RAD |
| 6 | Install additional fencing panels and/or wire the existing panels together to eliminate gaps in the perimeter fenceline. | 10/24/14 RAD |
| 7 | Maintain/repair the silt fence. Remove accumulated sediment where required. | 10/24/14 RAD |
| 8 | Install additional erosion control measures as required to prevent sediment from reaching the southern SA-7 roadway. | 10/24/14 RAD |
| 9 | Remove accumulated sediment from all paved roadways on SA-7 and wash down with the water truck as needed. | 10/27/14 RAD |
| 10 | Re-attach windscreen material where required. | 10/24/14 RAD |

Construction Manager: _____ Date: 10/29/14

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 30, 2014**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 5 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 6 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/31/14

**SWPPP Observer:** _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, October 30, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone signs are still present on the eastern end of the recently completed excavation area. |
| 2 | IA2Q4A1AL8 | The southwestern corner of the surcharge area 1-S stockpile has no protective fabric over the toe of slope or where it abuts the hydraulic barrier sheetpile wall. |
| 3 | IA2Q4A1AL8 | The stone in the vehicle tracking pad at the western end of Kellogg Street has become blinded with sediment. |
| 4 | IA2Q4A1AL8 | The sediment bags in the catch basins along Kellogg Street have become blinded with sediment. |
| 5 | IA2Q4A1AL8 | Sediment is accumulating along the north side of Kellogg Street by the temporary sheetpile |
| 6 | IA2Q4A1AL8 | No safety barrier is present between the sedimentation basin cap area and the concrete spill-over chamber to its south. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 10/31/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove Exclusion Zone signs. | 11/3/14 RAD |
| 2 | Place protective fabric over the material in this area, covering the exposed toe and draping it over the sheetpile wall. | 10/31/14 RAP |
| 3 | Clean or replace the stone in the tracking pad to restore function. | 10/31/14 RAD |
| 4 | Replace the filter fabric in the catch basins at the western end of Kellogg Street. | 11/4/14 RAD |
| 5 | Remove any accumulated sediment from the north side of Kellogg street adjacent to the excavation area. | 11/5/14 RAD |
| 6 | Install fencing or a warning barrier along the northern edge of the spill-over chamber per OSHA requirements | 11/5/14 RAD |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date** 11/06/14

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (September 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

October 20, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the September 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 9 | 01 | 14 | 9 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,235 | 85,068 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.63 | 0.70 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.0824 | 0.0824 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

## PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

10/17/2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 9 | 01 | 14 | 9 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,317,052 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 17,658,209 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 9/11/2014 | <7.0 | 5.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 10/17/2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | | | | MONTH: September 2014 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 9/1/2014 | Angel Trujillo | 15341157 | 15418889 | 77,732 | 0.077732 | 7.59 | 0.980 | | | | | | | | | 0.64 |
| 9/2/2014 | Angel Trujillo | 15418889 | 15494305 | 75,416 | 0.075416 | 7.63 | 0.980 | | | | | | | | | 0.62 |
| 9/3/2014 | Angel Trujillo | 15494305 | 15571551 | 77,246 | 0.077246 | 7.53 | 0.980 | | | | | | | | | 0.63 |
| 9/4/2014 | Angel Trujillo | 15571551 | 15646502 | 74,951 | 0.074951 | 7.04 | 0.980 | | | | | | | | | 0.61 |
| 9/5/2014 | Angel Trujillo | 15646502 | 15722895 | 76,393 | 0.076393 | 7.41 | 0.980 | | | | | | | | | 0.62 |
| 9/6/2014 | Angel Trujillo | 15722895 | 15807963 | 85,068 | 0.085068 | 7.04 | 0.980 | | | | | | | | | 0.70 |
| 9/7/2014 | Angel Trujillo | 15807963 | 15888130 | 80,167 | 0.080167 | 7.05 | 0.980 | | | | | | | | | 0.66 |
| 9/8/2014 | Angel Trujillo | 15888130 | 15962908 | 74,778 | 0.074778 | 7.06 | 0.980 | | | | | | | | | 0.61 |
| 9/9/2014 | Angel Trujillo | 15962908 | 16039741 | 76,833 | 0.076833 | 7.05 | 0.980 | | | | | | | | | 0.63 |
| 9/10/2014 | Angel Trujillo | 16039741 | 16116938 | 77,197 | 0.077197 | 7.06 | 0.980 | | | | | | | | | 0.63 |
| 9/11/2014 | Angel Trujillo | 16116938 | 16194384 | 77,446 | 0.077446 | 7.04 | 0.980 | <5.0 | <7.0 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | 0.63 |
| 9/12/2014 | Angel Trujillo | 16194384 | 16271780 | 77,396 | 0.077396 | 7.03 | 0.980 | | | | | | | | | 0.63 |
| 9/13/2014 | Angel Trujillo | 16271780 | 16352187 | 80,407 | 0.080407 | 7.02 | 0.980 | | | | | | | | | 0.66 |
| 9/14/2014 | Angel Trujillo | 16352187 | 16430616 | 78,429 | 0.078429 | 6.98 | 0.980 | | | | | | | | | 0.64 |
| 9/15/2014 | Angel Trujillo | 16430616 | 16501766 | 71,150 | 0.07115 | 7.01 | 0.980 | | | | | | | | | 0.58 |
| 9/16/2014 | Angel Trujillo | 16501766 | 16577681 | 75,915 | 0.075915 | 7.00 | 0.980 | | | | | | | | | 0.62 |
| 9/17/2014 | Angel Trujillo | 16577681 | 16657169 | 79,488 | 0.079488 | 7.08 | 0.980 | | | | | | | | | 0.65 |
| 9/18/2014 | Angel Trujillo | 16657169 | 16736120 | 78,951 | 0.078951 | 7.11 | 0.980 | | | | | | | | | 0.65 |
| 9/19/2014 | Angel Trujillo | 16736120 | 16813598 | 77,478 | 0.077478 | 7.14 | 0.980 | | | | | | | | | 0.63 |
| 9/20/2014 | Angel Trujillo | 16813598 | 16892980 | 79,382 | 0.079382 | 7.04 | 0.980 | | | | | | | | | 0.65 |
| 9/21/2014 | Angel Trujillo | 16892980 | 16968566 | 75,586 | 0.075586 | 7.08 | 0.980 | | | | | | | | | 0.62 |
| 9/22/2014 | Angel Trujillo | 16968566 | 17044907 | 76,341 | 0.076341 | 7.05 | 0.980 | | | | | | | | | 0.62 |
| 9/23/2014 | Angel Trujillo | 17044907 | 17122232 | 77,325 | 0.077325 | 6.96 | 0.980 | | | | | | | | | 0.63 |
| 9/24/2014 | Angel Trujillo | 17122232 | 17199357 | 77,125 | 0.077125 | 7.02 | 0.980 | | | | | | | | | 0.63 |
| 9/25/2014 | Angel Trujillo | 17199357 | 17276081 | 76,724 | 0.076724 | 7.04 | 0.980 | | | | | | | | | 0.63 |
| 9/26/2014 | Angel Trujillo | 17276081 | 17351830 | 75,749 | 0.075749 | 7.38 | 0.980 | | | | | | | | | 0.62 |
| 9/27/2014 | Angel Trujillo | 17351830 | 17433664 | 81,834 | 0.0818 | 7.17 | 0.980 | | | | | | | | | 0.67 |
| 9/28/2014 | Angel Trujillo | 17433664 | 17513139 | 79,475 | 0.079475 | 7.18 | 0.980 | | | | | | | | | 0.65 |
| 9/29/2014 | Angel Trujillo | 17513139 | 17582573 | 69,434 | 0.069434 | 7.18 | 0.980 | | | | | | | | | 0.57 |
| 9/30/2014 | Angel Trujillo | 17582573 | 17658209 | 75,636 | 0.075636 | 6.87 | 0.980 | | | | | | | | | 0.62 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,317,052 | 2.317052 | | | <5.0 | <7.0 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 85,068 | | | | | | | | | | | High: | 0.70 |
| | | | Average: | 77,235 | | | | | | | | | | | Average: | 0.63 |

WW

JB76317

E

# Honeywell — Chain Of Custody / Analysis Request

| | | | |
|---|---|---|---|
| Co.: | Parsons | Site Name: | Hudson County |
| Contact: (name, co., address) | | Location of Site: | Jersey City, NJ |
| P: (973) 455-2999 E: helen.fahy@honeywell.com | | Phase: | CS |
| International | | Sampling Program | 087: JCIA |
| bie Road Morristown, NJ 07962 | | AESI Ref: | 41693.43396 |
| To | Helen Fahy (Honeywell) | COC# | 087-WW-091114 |
| : | Helen Fahy (Honeywell) | Lab Proj # (EDG): | |
| EDD To: | | Lab ID | |
| Sampler: | Frank Schroyer | Site ID | |
| PO # | | Lab Job # | HWN.8432815 |
| Analysis Turnaround Time (TAT): Consultant | 3 CH2M | Authorized User: | Honeywell |
| Full Report TAT: | 28 Days | | |

Copyright AESI Version 5.0 Unauthorized use strictly prohibited.

| Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Units | Composite Flag | Filtered Sample? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | 5465.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | |
| 87-WW | | PH 7.06 @ | 087-WWE-091114-A | 9/11/2014 | 14:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | -1 | |
| 87-WW | | | 087-WWE-091114-B | 9/11/2014 | 14:10 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | -2 | | L27 |
| 87-WW | | | 087-WWI-091114 | 9/11/2014 | 14:20 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | -3 | | U614 |
| | | | | | | | | | | | | | | | | | | | | | | | A14 |
| | | | | | | | | | | | | | | | | | | | | | | | G13 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| d by pH=7.04 S.U. @ 7.5°C | Company | Received by | Company | | Condition | | Custody Seals Intact | |
| | Date/Time 9/11/14 | | Date/Time 9/11/14 1570 | | Cooler Temp. | | | |
| | Company | Received by | Company | 9/11/14 | Condition | | Custody Seals Intact | |
| | Date/Time 9/11/14 1810 | | Date/Time | 1810 | Cooler Temp. | 4.0 °C-B | | |

ess (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

9

NM

Accutest LabLink@815349 13:04 19-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091114-A | | |
| Lab Sample ID: | JB76317-1 | Date Sampled: | 09/11/14 |
| Matrix: | AQ - Water | Date Received: | 09/11/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 980 | 10 | ug/l | 1 | 09/12/14 | 09/13/14 | ND | EPA 200.7 [1] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 09/12/14 | 09/13/14 | ND | EPA 200.7 [1] | EPA 200.7 [4] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 09/12/14 | 09/15/14 | ND | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 09/13/14 | 09/13/14 | DP | EPA 245.1 [2] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 09/12/14 | 09/13/14 | ND | EPA 200.7 [1] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 09/12/14 | 09/13/14 | ND | EPA 200.7 [1] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA34917
(2) Instrument QC Batch: MA34919
(3) Instrument QC Batch: MA34927
(4) Prep QC Batch: MP81875
(5) Prep QC Batch: MP81898

(a) Elevated detection limit due to dilution required for matrix interference.

RL = Reporting Limit

Accutest LabLink@815349 13:04 19-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091114-A | | |
| Lab Sample ID: | JB76317-1 | Date Sampled: | 09/11/14 |
| Matrix: | AQ - Water | Date Received: | 09/11/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | 5.0 | 4.0 | mg/l | 1 | 09/12/14 | RP | SM2540 D-11 |
| pH [a] | 7.06 | | su | 1 | 09/11/14 19:30 | MB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@815349 13:04 19-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091114-A | | |
| **Lab Sample ID:** | JB76317-1A | **Date Sampled:** | 09/11/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/11/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 7.0 | 7.0 | mg/l | 1 | 09/12/14 18:48 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@815349 13:04 19-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091114-B | | |
| Lab Sample ID: | JB76317-2 | Date Sampled: | 09/11/14 |
| Matrix: | AQ - Water | Date Received: | 09/11/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T201464.D | 1 | 09/13/14 | DC | n/a | n/a | VT8254 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA PPL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.5 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.3 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.26 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 18.8 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.0 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.40 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 53.1 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 99% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 97% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 100% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@815349 13:04 19-Sep-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091114-B | | |
| **Lab Sample ID:** | JB76317-2 | **Date Sampled:** | 09/11/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/11/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 09/16/14 | AA | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending October 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal to Parties' per request. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 7 OF 25**

- **2014 Monthly Reports Part 7**

**12/15/2014**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

December 15, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
49 Bridge Street, Suite 2
Lambertville, NJ 08530

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-11**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from November 1 – November 30, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: November 2014 SA-6/7 Combined Monthly Progress Report No. 2014-11

cc: Joe Clifford - AMEC (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-11

**Project SA-6 & 7 Remediation**

## November 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 11/07/14 | Treatability Program<br>Bench Scale System Set Up for Treatment Area 10<br>Study Area 6 North<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/11/14 | Surcharge Monitoring Plan – Monthly Report No. 6<br>Study Area 6 North and South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/13/14 | Treatability Program<br>Area 10 Barrier Wall Alignment<br>Study Area 6 North<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/14/14 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2014-10<br>Study Areas 6 and 7<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/17/14 | Arnold & Porter Correspondence<br>Long Term Financial Assurances | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/18/14 | Special Master Conference Call | N/A |
| 11/19/14 | Design Change Bulletin<br>Hydrocarbon Soils in Cap Area<br>Study Area 6 North and South<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/19/14 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 11/9/14 | 11/16/14 | 11/23/14 | 11/30/14 |
| Construction Management (AMEC) | 12 | 11 | 12 | 11 |
| Engineering (AMEC) | 1 | 1 | 1 | 1 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 36 | 36 | 34 | 34 |
| Arecon/US Ecology Subcontractors | 1 | 1 | 1 | 1 |
| Evoqua | 1 | 1 | 1 | 1 |
| HBS (SA-6N GWTP Security System) | 0 | 0 | 0 | 0 |
| Gramercy | 21 | 20 | 17 | 22 |
| **TOTAL STAFF** | **76** | **74** | **70** | **74** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected November PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- PVSC collected yearly compliance samples associated with the Construction Water Treatment Plant and the Ground Water Treatment Plant on November 5, 2014.
- Continued site preparation, universal waste removal and asbestos abatements activities at the JCIA demolition project.
- Environ and Aquasurvey representatives completed long term monitoring activities in accordance with the SA-7 sediment monitoring plan, including the bathometric survey, cap thickness verifications, sediment profile imaging (SPI), biological sampling, and pore water sampling on November 3, 2014.
- Completed bench testing of candidate redevelopment chemicals for use in injections well 088-IW-01.
- Continued to advance permit application and discussions with New Jersey Department of Transportation (NJDOT) regarding Highway Occupancy and Drainage Permits for upcoming SA-6 activities proximate to the Rt. 440 frontage.

- On December 8, 2014, a leaking diesel line was identified on a water truck. This necessitated several yards of surficial soil to be removed and segregated. The incident was called in to the NJDEP hotline and Incident no. for this non-emergency incident is: 14-12-08-1503-35.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on November 12, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 11/9/14 | 11/16/14 | 11/23/14 | 11/30/14 |
| Avg. Gallons Treated & Discharged (per day) | 74,758 | 76,857 | 76,584 | 75,300 |
| Average Flow (gpm) for Operating Period | 53 | 53 | 54 | 52 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 5,690 | 7,932 | 7,078 | 6,900 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued storm-water management activities.
- Completed Site 163 shallow soil excavation activities on November 12, 2014.
- Collected a post-excavation sidewall sample, 134-SB-177, from the southeast side of the anomalous material excavation on December 2, 2014, results are pending and will be reported when final.
- On November 11 and 12, 2014, encountered and removed a former unidentified 550-gallon underground storage tank in the eastern portion of the Site 163 excavation. Peter Jaran, LSRP was contacted and a representative was onsite to oversee the UST removal and soil sampling in accordance with NJDEP requirements.
- Continued Site 163 backfill activities.
- Began excavation activities associated with the lens of anomalous material on SA-6 South proximate to Cell 104.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

## 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 0 | 0 | 0 |
| **Entact/ Horwith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 50 | 21.35 | 1,067.75 |
| **Entact/ Montecalvo** | 30 cyd roll-off | Bayshore Recycling | NA | Non Haz Creosote Debris | 0 | 0 | 0 |
| **Entact/ FCI** | 30 cyd roll off | Tullytown, Pa | WM Grows | ACM Tile & Mastic | 0 | 0 | 0 |
| **Entact/ FCI** | Tri-axle Dump | Kearny, NJ | NJ Meadowlands | Dieldrin Stained Concrete | 12 | 21.75 | 261 |
| **Entact/ Arecon** | Tri-axle Dump | Keasbey, NJ | Bayshore | TCE Impacted Soil | 0 | 0 | 0 |
| **Entact/ Arecon** | Tri-axle Dump | Keasbey, NJ | Bayshore | Mercury Impacted Soil | 0 | 0 | 0 |

## 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Cell Number(s) 75-59<br>Volume Excavated - Total for Reporting Period: 0 CY/ Total to Date: 151,313 CY |
| **Backfill in Progress** | Cell Number(s) 104-59 |

## 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 11/9/14 | 11/16/14 | 11/23/14 | 11/30/14 |
| <20ppm re-use, CY | 0 | 0 | 0 | 0 |
| Weldon, Import-Tons Screenings | 4,248 | 4,756 | 713 | 0 |
| Tilcon, Import-Tons DGA | 884 | 0 | 508 | 451 |
| Tilcon, Import Tons – 1.5” Stone | 0 | 0 | 0 | 0 |
| Weldon, Imported Tons - QP | 0 | 0 | 0 | 0 |
| Weldon, Imported Tons - DGA | 0 | 0 | 134 | 0 |
| Tilcon, Imported 6”-8” stone | 61 | 0 | 0 | 0 |
| Tilcon, Imported Tons – 2.5” Stone | 0 | 50 | 50 | 0 |

## E. SURCHARGE OPERATIONS

- Area 1S: Continue offloading 1S from west to east, approximately 50% complete.
- Area 2S: Surcharging continued on Area 2S. Surcharge placement consisted of both chromium impacted soils to the design sub-grade and both imported Celgene and Novartis soils. Surcharge placement is approximately 85% complete.
- Area 3S: Instrumentation installation was completed as of November 6, 2013 and all baseline readings recorded. Temporary stockpiles are located in this area. Surcharge has been initiated and is approximately 10% complete surcharge
- Area 1N: Continued surcharge removal activities. Surcharge removal activities area approximately 75% complete. Details were provided in the November 2014 Surcharge Monitoring Report No. 6.
- Area 2N: Instrumentation Installation 100% complete. Surcharge placement is complete. Surcharge placement is 100% complete.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Continue grouting angles of sheet pile at SA-6 South.
- Excavation proximate to the SA-6 South barrier wall was completed in October 28, 2014 and backfill has been progressed in all areas against the SA-6 South barrier wall. Deflection readings are therefore no longer required.

## G. PERMIT STATUS

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 | Pending | Pending | Pending |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | Pending | Pending | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue JCIA Structures Demolition activities to include site preparation, abatement activities, and utility disconnect activities.
- Continue placement of surcharge materials in SA-6 South Area 2S and Area 3S.
- Continue off loading of surcharge materials from SA-6 South Area 1S.
- Continue installation of the contingent groundwater system trench on SA-6 South.
- Complete Site 163 excavation and backfilling activities.
- Complete excavation of standalone Areas 41 and 43.
- Complete excavation of the lens of anomalous material proximate to Cell 104.
- Continue loadout and transportation and disposal activities at SA-6 South.
- Continue backfill placement and associated compaction testing activities at SA-6 South.
- Begin accepting delivery of steel sheetpile for SA-6 North barrier wall installation.
- Complete well cleaning of injection well 088-IW-01 on SA-6N.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Complete sediment long term monitoring activities and final report preparation.

- Obtain NJDOT Highway Occupancy Permit for upcoming SA-6 North activities proximate to Rt. 440 frontage.
- Conduct semi-annual sampling of S-3 mass removal injection and related monitoring wells.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Deep Well Data (DW-4)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. *Groundwater Quality Data Surcharge Monitoring Update (not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Sheet Pile Angle Grout Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (October 2014)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

Study Areas 6 and 7 Combined Progress Report No. 2014-11
Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration |
|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** |
| 19 | Develop Site Relocation Master Plan | 38 days |
| 20 | Submit Site Relocation Master Plan | 0 days |
| 21 | JC Construction of New Facilities | 1309 days |
| 22 | Relocation Contractor Procurement | 392 days |
| 23 | JCIA and JCDPW Relocation | 753 days |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days |
| 24a | Demolition of JCIA Structures | 151 days |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** |
| **57** | **SA-6 South Relocation** | **616 days** |
| 58 | New GWTP Construction Completion | 502 days |
| 59 | Demolition of 80 Kellogg | 857 days |
| **60** | **SA-6 North/South Field Implementation** | **838 days** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** |
| 61a | Mobilization | 87 days |
| **62** | **Surcharge Install/Instrumentation** | **620 days** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days |
| **63** | **Barrier Wall Install** | **489 days** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days |
| **64** | **Excavation** | **507 days** |
| 64a | SA 6N Excavation | 218 days |
| **64b** | **SA 6S Excavation** | **226 days** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days |
| **65** | **Backfill** | **493 days** |
| 65a | SA 6N Backfill | 218 days |
| 65b | SA 6S Backfill | 232 days |
| **66** | **Capping and Cover Soil Placement** | **315 days** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days |
| **67** | **Restoration** | **164 days** |
| 67a | Restoration | 164 days |
| **68** | **Demobilization** | **21 days** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Fri 12/5/14

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Contractor begins abatement activities at former JC buildings.




**Site Photograph 2:** Contractor begins excavation along Droyers Cove.




**Site Photograph 3:** Contractor begins restoration of area along Droyers Cove.




**Site Photograph 4:** Excavation continues along Droyers Cove.




**Photograph 5:** Droyers Cove excavation backfilled and graded**.**




**Site Photograph 6:** Excavation continues along Kellogg St. properties.





**Site Photograph 7:** The contractor removes a former tank.


## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies
# Progress as of December 1, 2014

November 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill






ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 10-16-14 TO 10-30-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.
Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -0.6 | 134-SB-019 | 114A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.3 | 601878.4 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.5 | 601974.0 | 1.2 | 134-SB-061 | 106A | 7/23/2014 | -5.2 | Stratum D Reached |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.8 | 601978.1 | -7.5 | 134-SB-113 | 103 | 7/29/2014 | -7.2 | Stratum D Reached |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |
| 684908.2 | 602155.7 | -8.0 | 134-SB-049 | 89 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684943.6 | 602214.1 | -6.9 | 140-SB-035 | 88 | 8/25/2014 | -6.7 | Stratum D Reached |
| 684905.5 | 602180.6 | -7.8 | 140-SB-063 | 88 | 8/25/2014 | -6.1 | Stratum D Reached |
| 684875.3 | 602175.3 | -7.8 | 140-SB-062 | 87 | 8/25/2014 | -5.8 | Stratum D Reached |
| 684875.5 | 602187.9 | -7.3 | 140-SB-103 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684915.0 | 602239.0 | -6.1 | 140-SB-007 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |
| 684896.1 | 602229.3 | -6.6 | 140-SB-038 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684862.9 | 602228.0 | -6.1 | 134-SB-032R | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684901.7 | 602269.3 | -5.3 | 140-SB-040 | 83 | 9/4/2014 | -5.7 | Stratum D Reached |
| 684826.5 | 602208.8 | -6.5 | 140-SB-051 | 83 | 9/4/2014 | -4.7 | Stratum D Reached |
| 684854.3 | 602237.3 | -6.7 | 140-SB-041 | 83 | 9/4/2014 | -4.9 | Stratum D Reached |
| 684771.0 | 602188.4 | -4.8 | 140-SB-044 | 82 | 9/10/2014 | -5.2 | Stratum D Reached |
| 684800.2 | 602210.9 | -6.5 | 140-SB-042 | 82 | 9/10/2014 | -4.7 | Stratum D Reached |
| 684865.2 | 602271.1 | -6.2 | 140-SB-064 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684830.9 | 602252.5 | -6.3 | 140-SB-066 | 81 | 9/17/2014 | -3.1 | Stratum D Reached |
| 684716.6 | 602169.4 | -0.2 | 140-SB-043 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684755.4 | 602222.4 | -5.7 | 140-SB-047 | 80 | 9/23/2014 | -4.6 | Stratum D Reached |
| 684823.4 | 602275.4 | -5.0 | 140-SB-048 | 80 | 9/17/2014 | -2.8 | Stratum D Reached |
| 684687.1 | 602171.5 | 0.3 | 140-SB-049 | 79 | 9/23/2014 | -3.9 | Stratum D Reached |
| 684721.0 | 602200.6 | -4.2 | 140-SB-046 | 79 | 9/23/2014 | -5.1 | Stratum D Reached |
| 684680.8 | 602178.0 | -3.3 | 140-SB-075 | 79 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684695.5 | 602194.5 | -4.8 | 140-SB-018 | 79 | 9/23/2014 | -4.4 | Stratum D Reached |
| 684767.0 | 602244.0 | -4.4 | 140-SB-010 | 79 | 9/23/2014 | -4.0 | Stratum D Reached |
| 684818.0 | 602299.0 | -5.4 | 140-SB-009 | 78 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684855.0 | 602329.0 | -5.8 | 140-SB-065 | 78 | 9/23/2014 | -2.7 | Stratum D Reached |
| 684656.0 | 602192.0 | -2.7 | 140-SB-026 | 77 | 9/29/2014 | -2.3 | Stratum D Reached |
| 684740.4 | 602255.2 | -5.4 | 140-SB-082 | 77 | 9/29/2014 | -3.5 | Stratum D Reached |
| 684815.0 | 602348.7 | -3.4 | 140-SB-094 | 76 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684787.4 | 602330.2 | -0.4 | 140-SB-086 | 75 | 10/2/2014 | -4.0 | Stratum D Reached |
| 684744.9 | 602306.7 | -1.4 | 140-SB-083 | 75 | 10/2/2014 | -4.5 | Stratum D Reached |
| 684713.1 | 602276.0 | -0.4 | 140-SB-081 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684668.4 | 602240.2 | 0.1 | 140-SB-079 | 75 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684643.7 | 602221.3 | -4.2 | 140-SB-050 | 75 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684628.7 | 602233.7 | -2.9 | 140-SB-074 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684703.0 | 602285.6 | 2.6 | 140-SB-080 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684733.7 | 602322.4 | 0.6 | 140-SB-084 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.9 | 602371.9 | 0.1 | 140-SB-088 | 74 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684653.9 | 602259.3 | -1.4 | 140-SB-078 | 73 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684755.3 | 602343.3 | 0.6 | 140-SB-085 | 73 | 10/7/2014 | -1.6 | Stratum D Reached |
| 684660.7 | 602300.1 | 0.9 | 140-SB-089 | 72 | 10/9/2014 | -2.8 | Stratum D Reached |
| 684693.1 | 602326.3 | -3.0 | 140-SB-090 | 72 | 10/7/2014 | -3.3 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684745.4 | 602367.1 | 1.0 | 140-SB-091 | 72 | 10/7/2014 | -0.1 | Target Elevation Reached |
| 684640.0 | 602295.0 | 1.9 | 140-SB-011 | 71 | 10/9/2014 | -4.0 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | 125-SB-029R | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684629.9 | 602309.5 | 5.8 | 140-SB-033 | 70 | 10/9/2014 | 2.4 | Target Elevation Reached |
| 684725.2 | 602383.8 | 0.4 | 125-SB-029R | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684642.9 | 602315.4 | 0.9 | 140-SB-089R | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684764.0 | 602429.2 | -7.0 | 140-SB-N07 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | 125-SB-029R | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684632.0 | 602327.7 | 5.8 | 140-SB-033R | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684669.3 | 602386.6 | -0.6 | 140-SB-070 | 68 | 10/21/2014 | -2.3 | Stratum D Reached |
| 684679.0 | 602393.0 | 0.0 | 140-SB-013 | 68 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684760.1 | 602448.4 | -1.4 | 140-SB-083R | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | 125-SB-029R | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684629.6 | 602343.1 | 5.8 | 140-SB-033R | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684749.9 | 602465.0 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684700.0 | 602423.0 | 0.8 | 140-SB-012 | 67 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684715.4 | 602440.1 | -1.0 | 140-SB-029 | 67 | 10/21/2014 | -1.4 | Stratum D Reached |
| 684662.8 | 602394.7 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -1.4 | 140-SB-083R | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | 125-SB-073R | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684666.6 | 602417.0 | -2.7 | 140-SB-068 | 66 | 10/21/2014 | -3.0 | Stratum D Reached |
| 684735.5 | 602488.2 | -1.4 | 140-SB-083R | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | 125-SB-029R | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | 125-SB-073R | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | 125-SB-029R | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -1.4 | 140-SB-083R | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684666.2 | 602452.6 | 2.5 | 140-SB-030 | 64 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684735.4 | 602510.4 | -3.6 | 140-SB-067 | 64 | 10/24/2014 | -2.3 | Stratum D Reached |
| 684713.8 | 602503.3 | 4.3 | 140-SB-028 | 63 | 10/27/2014 | -2.4 | Stratum D Reached |
| 684727.7 | 602515.9 | -2.0 | 140-SB-104 | 63 | 10/27/2014 | -2.2 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | 125-SB-029R | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | 125-SB-073R | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | 125-SB-029R | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684653.2 | 602490.5 | 0.2 | 125-SB-057 | 61 | 10/24/2014 | -2.6 | Stratum D Reached |
| 684675.4 | 602508.2 | -1.2 | 125-SB-073 | 61 | 10/27/2014 | -2.5 | Stratum D Reached |
| SA-6 South Excavation: Confirmatory Points (Table 1.8) | | | | | | | |

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684697.8 | 602526.3 | -2.2 | 125-SB-055 | 61 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684707.1 | 602549.9 | -3.4 | 125-SB-072 | 61 | 10/28/2014 | -2.8 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | 125-SB-029R | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | 125-SB-073R | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | 125-SB-029R | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | 125-SB-069R | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684678.4 | 602552.4 | -2.4 | 125-SB-061 | 59 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684615.0 | 602501.1 | 0.5 | 125-SB-048 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684633.9 | 602516.6 | 0.6 | 125-SB-046 | 59 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684656.3 | 602534.7 | -1.4 | 125-SB-074 | 59 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684604.5 | 602498.0 | 2.1 | 125-SB-069R | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | UST Area |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | UST Area |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | UST Area |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |
| 684922.3 | 602179.9 | -4.3 | C-89 | 89 | 8/20/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684912.0 | 602189.2 | -4.3 | C-88 | 88 | 8/25/2014 | -6.3 | Stratum D Reached |
| 684895.8 | 602194.1 | -4.3 | C-87 | 87 | 8/25/2014 | -6.0 | Stratum D Reached |
| 684880.8 | 602203.6 | -4.3 | C-86 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684872.8 | 602212.7 | -4.3 | C-85 | 85 | 8/29/2014 | -5.2 | Stratum D Reached |
| 684862.9 | 602228.0 | -4.3 | C-84 | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684820.9 | 602207.7 | -2.5 | C-83 | 83 | 9/4/2014 | -4.5 | Stratum D Reached |
| 684812.4 | 602218.7 | -2.5 | C-82 | 82 | 9/10/2014 | -4.1 | Stratum D Reached |
| 684788.9 | 602227.5 | -2.5 | C-81 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684778.7 | 602237.4 | -2.5 | C-80 | 80 | 9/17/2014 | -4.6 | Stratum D Reached |
| 684759.2 | 602240.0 | -2.5 | C-79 | 79 | 9/23/2014 | -4.1 | Stratum D Reached |
| 684758.4 | 602256.3 | -2.5 | C-78 | 78 | 9/23/2014 | -3.4 | Stratum D Reached |
| 684753.6 | 602273.9 | -2.5 | C-77 | 77 | 9/29/2014 | -3.8 | Stratum D Reached |
| 684731.1 | 602272.7 | -2.5 | C-76 | 76 | 9/29/2014 | -3.0 | Stratum D Reached |
| 684735.0 | 602292.1 | -2.5 | C-75 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684732.6 | 602313.2 | -2.5 | C-74 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.5 | 602381.3 | -2.5 | C-73 | 73 | 10/7/2014 | -2.7 | Stratum D Reached |
| 684752.7 | 602351.0 | 0.4 | C-73-1 | 73 | 10/7/2014 | 0.1 | Target Elevation Reached |
| 684662.4 | 602274.6 | -2.5 | C-73-2 | 73 | 10/7/2014 | -2.1 | Stratum D Reached |
| 684788.0 | 602395.1 | -2.5 | C-72 | 72 | 10/7/2014 | -2.5 | Stratum D Reached |
| 684743.1 | 602361.9 | 0.4 | C-72-1 | 72 | 10/7/2014 | -0.2 | Target Elevation Reached |
| 684664.8 | 602296.2 | -2.5 | C-72-2 | 72 | 10/7/2014 | -3.0 | Stratum D Reached |
| 684783.1 | 602411.4 | -2.5 | C-71 | 71 | 10/9/2014 | -2.7 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | C-71-1 | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684652.0 | 602308.3 | -2.5 | C-71-2 | 71 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684772.6 | 602425.4 | -2.5 | C-70 | 70 | 10/9/2014 | -2.5 | Stratum D Reached |
| 684725.2 | 602383.8 | 0.4 | C-70-1 | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684674.6 | 602346.3 | -2.5 | C-70-2 | 70 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684642.9 | 602315.4 | 2.1 | C-70-3 | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684626.5 | 602306.7 | 5.7 | C-70-4 | 70 | 10/9/2014 | 4.8 | Target Elevation Reached |
| 684762.8 | 602431.3 | -2.5 | C-69 | 69 | 10/14/2014 | -2.7 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | C-69-1 | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684670.5 | 602360.9 | -2.5 | C-69-2 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684632.0 | 602327.7 | 5.7 | C-69-3 | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684760.1 | 602448.4 | -2.5 | C-68 | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | C-68-1 | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684671.6 | 602375.8 | -2.5 | C-68-2 | 68 | 10/14/2014 | -2.2 | Stratum D Reached |
| 684629.6 | 602343.1 | 5.7 | C-68-3 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684749.9 | 602465.0 | -2.5 | C-67 | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684698.4 | 602419.3 | 0.4 | C-67-1 | 67 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684662.8 | 602394.7 | -2.5 | C-67-2 | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -2.5 | C-66 | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | C-66-1 | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | C-66-2 | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | C-66-3 | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684664.0 | 602411.1 | -2.5 | C-66-4 | 66 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684735.5 | 602488.2 | -2.5 | C-65 | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | C-65-1 | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | C-65-2 | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | C-65-3 | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -2.5 | C-65-4 | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684713.4 | 602487.7 | -1.2 | C-64 | 64 | 10/24/2014 | -1.8 | Stratum D Reached |
| 684653.2 | 602444.8 | 0.4 | C-64-1 | 64 | 10/21/2014 | -4.0 | Increased excavation depth - UST location |
| 684701.6 | 602502.1 | -1.2 | C-63 | 63 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | C-63-1 | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | C-62 | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | C-62-1 | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684689.4 | 602527.1 | -1.2 | C-61 | 61 | 10/28/2014 | -2.7 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | C-61-1 | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | C-60 | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | C-60-1 | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | C-60-2 | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684665.2 | 602547.7 | -1.2 | C-59 | 59 | 10/27/2014 | -2.8 | Stratum D Reached |
| 684620.0 | 602510.0 | 0.4 | C-59-1 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684604.5 | 602498.0 | 2.1 | C-59-2 | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685471.0 | 601475.6 | 4.3 | 073-SB-079 | 148 | 7/31/2014 | 4.3 | Target Elevation Reached |
| 685451.0 | 601460.9 | 7.1 | 073-SB-082 | 148 | 7/31/2014 | 2.2 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Target Elevation Reached |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685094.6 | 601890.3 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 685081.0 | 601928.0 | -0.1 | 134-SB-021 | 109A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 685080.6 | 601935.9 | 3.0 | 134-SB-092 | 108A | 7/10/2014 | -1.6 | Target Elevation Reached |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Target Elevation Reached |
| 684999.7 | 601940.5 | -0.5 | 134-SB-097 | 104 | 7/29/2014 | -7.2 | Stratum D Reached |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |
| 684887.0 | 602147.0 | -2.1 | 134-SB-100 | 89 | 8/20/2014 | -5.8 | Stratum D Reached |
| 684821.2 | 602190.7 | -4.8 | 140-SB-060 | 84 | 9/4/2014 | -5.2 | Stratum D Reached |
| 684779.8 | 602174.6 | -0.8 | 140-SB-059 | 83 | 9/10/2014 | -5.6 | Stratum D Reached |
| 684727.5 | 602143.2 | 0.7 | 140-SB-076 | 83 | 9/10/2014 | -4.5 | Stratum D Reached |
| 684701.3 | 602132.8 | -0.8 | 140-SB-003 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684686.4 | 602158.8 | -0.8 | 140-SB-105 | 80 | 9/17/2014 | -4.8 | Stratum D Reached |
| 684651.0 | 602180.0 | -2.1 | 140-SB-027 | 77 | 9/29/2014 | -2.8 | Stratum D Reached |
| 684630.0 | 602210.0 | -1.9 | 140-SB-077 | 75 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684622.2 | 602287.4 | -2.0 | 140-SB-034 | 71 | 10/9/2014 | -3.0 | Stratum D Reached |
| 684597.0 | 602258.0 | -3.2 | 140-SB-025 | 71 | 10/9/2014 | -3.1 | Stratum D Reached |
| 684626.0 | 602343.0 | 6.8 | 140-SB-014 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684613.7 | 602330.2 | 6.1 | 140-SB-072 | 68 | 10/14/2014 | 4.5 | Target Elevation Reached |
| 684649.1 | 602367.2 | -1.0 | 140-SB-071 | 68 | 10/14/2014 | -2.8 | Stratum D Reached |
| 684648.1 | 602370.8 | -0.8 | 140-SB-032 | 67 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684649.1 | 602409.4 | -2.3 | 140-SB-069 | 65 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684629.1 | 602423.3 | 1.5 | 140-SB-031 | 64 | 10/21/2014 | -3.5 | Stratum D Reached |
| 684633.2 | 602474.4 | 0.4 | 125-SB-058 | 61 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684616.1 | 602485.8 | 3.0 | 125-SB-068 | 60 | 10/21/2014 | 1.8 | Target Elevation Reached |
| 684588.4 | 602494.2 | 100.0 | 125-SB-119 | 59 | 10/21/2014 | 1.5 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 11/17/14

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-62 | | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-62-1 | 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | BF-64 | | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-64-1 | 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 3 | BF-64-2 | 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-65 | | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-65-1 | 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 0 | BF-66 | | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-66-1 | 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 2 | BF-66-2 | 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 0 | BF-67 | | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-67-1 | 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-67-2 | 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-68 | | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-68-1 | 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-68-2 | 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 0 | BF-69 | | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-69-1 | 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-69-2 | 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-70 | | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-70-1 | 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-70-2 | 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| 0 | BF-71 | | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 5 | BF-71-1 | 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-72 | | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 3 | BF-72-1 | 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| 0 | BF-73 | | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 6 | BF-73-1 | 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 6 | BF-75-2 | 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 6 | BF-76-2 | 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 6 | BF-77-2 | 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 7 | BF-78-2 | 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 7 | BF-80-2 | 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 4 | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 7 | BF-81-2 | 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 6 | BF-82-2 | 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 6 | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 7 | BF-83-3 | 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 6 | BF-84-3 | 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 6 | BF-85-3 | 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-86-2 | 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION | | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | NORTHING | EASTING | | | | | | | | | | | |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION | | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | NORTHING | EASTING | | | | | | | | | | | |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 1 | RF-14-2 | 11/5/2014 | 684662.9 | 602542.6 | 0.0 | 134.0 | 0.6 | 135.8 | 6.4 | 99 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-16-2 | 11/5/2014 | 684767.6 | 602428.4 | 1.2 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 67 | Weldon WC Screenings | | V5N |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-17-2 | 11/5/2014 | 684723.7 | 602387.9 | 1.5 | 124.0 | 3.8 | 128.9 | 12.1 | 96 | 95 | 70 | Weldon WC Screenings | | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| 6 | RF-18-2 | 11/5/2014 | 684636.8 | 602258.1 | 5.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 73 | Weldon WC Screenings | Placed on Type A material | V5N |
| | RF-19 | | 684790.8 | 602339.5 | -2.5 | | | | | | | 75 | Stratum D | Bottom of excavation elevation | |
| 3 | RF-19-1 | 11/5/2014 | 684776.9 | 602328.5 | 1.8 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 75 | Weldon WC Screenings | | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| 4 | RF-21-2 | 11/5/2014 | 684823.4 | 602288.0 | 1.8 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 79 | Tilcon MH DGA | | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION | | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | NORTHING | EASTING | | | | | | | | | | | |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| 5 | RF-23-04 | 11/5/2014 | 684877.6 | 602222.8 | 2.5 | 134.0 | 0.7 | 135.8 | 6.4 | 99 | 95 | 85 | Tilcon MH DGA | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION | | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | NORTHING | EASTING | | | | | | | | | | | |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |

FIELD DENSITY TEST SUMMARY LOG
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION | | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | NORTHING | EASTING | | | | | | | | | | | |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 0 | Site 163-2 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-2-1 | 11/5/2014 | 685070.9 | 601614.2 | 6.1 | 122.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| 2 | Site 163-2-2 | 11/14/2014 | 685070.5 | 601616.0 | 7.5 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |

***Notes:***

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS 5 TESTS PER ACRE

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 4: Dewatering Operations Update

- SA-6 South Deep Well Data (DW-4)

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-4)

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/14/14 | 24 | N/A | N/A | 6,500 | 80,718 | 4.5 | Pump Online for LOAM Excavation |
| 11/17/14 | 72 | N/A | N/A | 19,500 | 100,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/18/14 | 24 | N/A | N/A | 6,500 | 106,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/19/14 | 24 | N/A | N/A | 6,500 | 113,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/20/14 | 24 | N/A | N/A | 6,500 | 119,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/21/14 | 24 | N/A | N/A | 6,500 | 126,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/22/14 | 24 | N/A | N/A | 6,500 | 132,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/24/14 | 48 | N/A | N/A | 13,000 | 145,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/25/14 | 24 | N/A | N/A | 6,500 | 152,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/28/14 | 72 | N/A | N/A | 19,500 | 171,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/30/14 | 48 | N/A | N/A | 12,500 | 184,218 | 4.3 | Flow Meter Not Intsalled Tank Measured |

# Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|
| 10/02/14 | 8:30 | 20,855.01 | 20,938.29 | 83,280 | 20,937,840 | |
| 10/03/14 | 6:00 | 20,938.29 | 20,977.59 | 39,300 | 20,977,140 | |
| 10/05/14 | 4:30 | 20,977.59 | 21,023.46 | 45,870 | 21,023,010 | |
| 10/06/14 | 7:45 | 21,023.46 | 21,102.23 | 78,770 | 21,101,780 | |
| 10/09/14 | 8:00 | 21,102.23 | 21,182.13 | 79,900 | 21,181,680 | PVSC Compliance Sample Collected |
| 10/10/14 | 7:30 | 21,182.13 | 21,208.69 | 26,560 | 21,208,240 | |
| 10/12/14 | 4:30 | 21,208.69 | 21,228.53 | 19,840 | 21,228,080 | |
| 10/13/14 | 6:30 | 21,228.53 | 21,289.72 | 61,190 | 21,289,270 | |
| 10/14/14 | 2:00 | 21,289.72 | 21,292.46 | 2,740 | 21,292,010 | |
| 10/15/14 | 8:00 | 21,292.46 | 21,349.49 | 57,030 | 21,349,040 | |
| 10/16/14 | 8:00 | 21,349.49 | 21,411.09 | 61,600 | 21,410,640 | |
| 10/17/14 | 7:00 | 21,411.09 | 21,463.04 | 51,950 | 21,462,590 | |
| 10/19/14 | 5:00 | 21,463.04 | 21,523.23 | 60,190 | 21,522,780 | |
| 10/21/14 | 7:00 | 21,523.23 | 21,574.85 | 51,620 | 21,574,400 | |
| 10/22/14 | 8:00 | 21,574.85 | 21,611.86 | 37,010 | 21,611,410 | |
| 10/23/14 | 9:30 | 21,611.86 | 21,728.57 | 116,710 | 21,728,120 | |
| 10/24/14 | 7:00 | 21,728.57 | 21,795.15 | 66,580 | 21,794,700 | |
| 10/25/14 | 4:00 | 21,795.15 | 21,836.74 | 41,590 | 21,836,290 | |
| 10/27/14 | 8:00 | 21,836.74 | 21,934.46 | 97,720 | 21,934,010 | |
| 10/29/14 | 4:15 | 21,934.46 | 21,979.83 | 45,370 | 21,979,380 | |
| 10/30/14 | 2:00 | 21,979.83 | 21,987.45 | 7,620 | 21,987,000 | |
| 11/05/14 | 7:00 | 21,987.45 | 22,068.71 | 81,260 | 22,068,260 | PVSC Compliance Sample Collected |
| 11/07/14 | 5:00 | 22,068.71 | 22,093.24 | 24,530 | 22,092,790 | |
| 11/10/14 | 6:30 | 22,093.24 | 22,125.00 | 31,760 | 22,124,550 | CGWES pumped and isolated from 930 to 1530 |
| 11/11/14 | 5:00 | 22,125.00 | 22,151.18 | 26,180 | 22,150,730 | |
| 11/12/14 | 8:00 | 22,151.18 | 22,205.08 | 53,900 | 22,204,630 | |
| 11/13/14 | 8:00 | 22,205.08 | 22,232.39 | 27,310 | 22,231,940 | |
| 11/14/14 | 5:00 | 22,232.39 | 22,270.23 | 37,840 | 22,269,780 | |
| 11/15/14 | 3:45 | 22,270.23 | 22,327.83 | 57,600 | 22,327,380 | |
| 11/16/14 | 4:00 | 22,327.83 | 22,387.57 | 59,740 | 22,387,120 | |
| 11/17/14 | 7:00 | 22,387.57 | 22,488.01 | 100,440 | 22,487,560 | |
| 11/18/14 | 7:30 | 22,488.01 | 22,568.74 | 80,730 | 22,568,290 | |
| 11/19/14 | 7:30 | 22,568.74 | 22,653.22 | 84,480 | 22,652,770 | |
| 11/20/14 | 5:00 | 22,653.22 | 22,692.55 | 39,330 | 22,692,100 | |
| 11/21/14 | 8:00 | 22,692.55 | 22,747.08 | 54,530 | 22,746,630 | |
| 11/22/14 | 4:00 | 22,747.08 | 22,783.08 | 36,000 | 22,782,630 | |
| 11/24/14 | 8:30 | 22,783.08 | 22,833.40 | 50,320 | 22,832,950 | |
| 11/26/14 | 7:30 | 22,833.40 | 22,889.40 | 56,000 | 22,888,950 | |
| 11/28/14 | 5:00 | 22,889.40 | 22,984.22 | 94,820 | 22,983,770 | |
| 11/30/14 | 10:00 | 22,984.22 | 23,021.47 | 37,250 | 23,021,020 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 67-75 | <20 | 124-75-20-a,b (A27) | 1200 | 124-75-20-a1 | 10/16/2014 | 11:20 | 9.6 | Yes | | |
| | | | | 124-75-20-a2 | 10/16/2014 | 11:25 | 7.6 | Yes | | |
| | | | | 124-75-20-a3 | 10/16/2014 | 11:30 | 11.0 | Yes | | |
| | | | | 124-75-20-a4 | 10/16/2014 | 11:35 | 25.3 | | Yes | |
| | | | | 124-75-20-b1 | 10/16/2014 | 11:40 | 17.3 | * | | |
| | | | | 124-75-20-b2 | 10/16/2014 | 11:45 | 15.6 | * | | |
| | | | | 124-75-20-b3 | 10/16/2014 | 11:50 | 29.3 | | Yes | |
| | | | | 124-75-20-b4 | 10/16/2014 | 11:55 | 65.3 | | Yes | |
| 58-67 | <20 | 124-67-20-a,b (A28) | 1665 | 124-67-20-a1 | 10/28/2014 | 11:30 | 0.45 | * | | |
| | | | | 124-67-20-a2 | 10/28/2014 | 11:35 | 98.2 | | Yes | |
| | | | | 124-67-20-a3 | 10/28/2014 | 11:40 | 2.6 | * | | |
| | | | | 124-67-20-a4 | 10/28/2014 | 11:45 | 5.2 | * | | |
| | | | | 124-67-20-b1 | 10/28/2014 | 11:50 | 71.9 | | Yes | |
| | | | | 124-67-20-b2 | 10/28/2014 | 11:55 | 340 | | Yes | |
| | | | | 124-67-20-b3 | 10/28/2014 | 12:00 | 29.6 | | Yes | |
| | | | | 124-67-20-b4 | 10/28/2014 | 12:05 | 23.3 | | Yes | |
| 75-58 | >1000 | 124-75-1000-a,b | 1600 | 124-75-1000-a1 | 10/29/2014 | 13:15 | 1,410 | | | * |
| | | | | 124-75-1000-a2 | 10/29/2014 | 13:20 | 750 | | Yes | |
| | | | | 124-75-1000-a3 | 10/29/2014 | 13:25 | 1,360 | | | * |
| | | | | 124-75-1000-a4 | 10/29/2014 | 13:30 | 2,050 | | | * |
| | | | | 124-75-1000-b1 | 10/29/2014 | 13:35 | 2,060 | | | * |
| | | | | 124-75-1000-b2 | 10/29/2014 | 13:40 | 454 | | Yes | |
| | | | | 124-75-1000-b3 | 10/29/2014 | 13:45 | 591 | | Yes | |
| | | | | 124-75-1000-b4 | 10/29/2014 | 13:50 | 2,860 | | | * |
| Site 163 | >1000 | 163-122-1000-a | 850 | 163-122-1000-a1 | 11/18/2014 | 11:00 | 4.5 | | Yes | |
| | | | | 163-122-1000-a2 | 11/12/2014 | 14:05 | 4 | | Yes | |
| | | | | 163-122-1000-a3 | 11/18/2014 | 11:05 | 80.1 | | Yes | |
| | | | | 163-122-1000-a4 | 11/12/2014 | 14:15 | 38.1 | | Yes | |
| 103-106 | <20 | 124-106-20-a (A29) | 950 | 124-106-20-a1 | 11/21/2014 | 7:55 | 9.2 | * | | |
| | | | | 124-106-20-a2 | 11/21/2014 | 8:00 | 12.1 | * | | |
| | | | | 124-106-20-a3 | 11/21/2014 | 8:05 | 15.6 | * | | |
| | | | | 124-106-20-a4 | 11/21/2014 | 8:10 | 20 | | * | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

# Attachment 7: Perimeter Pools Update




LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE

100' 50' 0 100' 200'

IN PROGRESS
10-02-2014


STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

**Table 1**

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | | | | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO, FS-4

## Attachment 8: Quality and Level Data in GWET Wells

(not available as of this report date - provided on a quarterly basis)

- Summary of Groundwater Quality Data from GWET Wells
- Trichloroethene//Chloroform/Hexavalent Chromium in GWET Wells

## Attachment 9: Surcharge Monitoring Update

(not available as of this report date - provided on a quarterly basis)

- ## Attachment 10: Sheet Pile Update

- Sheet Pile Angle Grout Log

Batch: 94# Cement Type II
6.58# Bentonite
8 gal $H_2O$

**Amec**
**SA-6 South Grouted Angles** (5")

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 6.6# | 11/7/14 | 99 | 1:10 | SP -21 |
| | | | | SP -22 |
| 6.6# | | 100 | 1:30 | SP -23 |
| | | | | Top off SP 21-22 |
| | | | | SP-24 |
| | | | | SP-25 |
| | | | | SP-26 |
| 7# | | 101 | 2:00 | SP-26 |
| | | | | Top off 21-25 |
| | | | | SP-27 |
| | | | | SP-28 |
| 7# | | 102 | 2:30 | SP-28 |
| | | | | Top off SP 26-27 |
| | | | | SP-29 |
| | | | | Top off SP 23-25 |
| | | | | SP-30 |
| | | | | |
| 7# | 11/10/14 | 103 | 9:05 | SP-30 |
| | | | | SP-31 |
| | | | | SP-32 |
| | | | | SP-33 |
| 7# | | 104 | 9:21 | Top off SP -32 |
| | | | | SP-33 |
| | | | | SP-34 |
| | | | | SP-35 |
| 7# | | 105 | 9:43 | SP-35 |
| | | | | Top off SP31-34 |
| 7# | | 106 | 10:05 | SP-36 |
| | | | | SP-37 |
| | | | | SP-35 |
| | | | | SP-38 |
| 7# | | 107 | 10:25 | SP-38 |
| | | | | SP-39 |
| | | | | SP-40 |
| 7# | | 108 | 10:44 | SP-40 |
| | | | | SP-41 |
| | | | | SP-42 |
| | | | | SP-43 |
| 7# | | 109 | 11:03 | SP-43 |
| | | | | SP-44 |
| | | | | 6P-1 |
| | | | | 6P-2 |
| 7# | | 110 | 11:19 | 6P-2 |
| | | | | 6P-3 |
| | | | | 6P-4 |
| 7# | | 111 | 11:36 | 6P-5 |
| | | | | 6P-3 |
| | | | | 6P-6 |

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 7# | 11/10/14 | 111 | 10:36 | Top off 6P2-4 |
| 7# | | 112 | 1:40 | Top off SP21-32 |
| 7# | | 113 | 1:55 | Top off SP32-44 |
| 7# | | 114 | 2:10 | Top off SP42-6P5 |
| | | | | 6P-6 |
| | | | | 6P-7 |
| | | | | |
| 7# | 11/11/14 | 115 | 10:07 | Top off 6P-7 |
| | | | | 6P-8 |
| | | | | 6P-9 |
| 7# | | 116 | 10:27 | 6P-9 |
| | | | | 6P-10 |
| | | | | 6P-11 |
| 7# | | 117 | 10:42 | 6P-11 |
| | | | | 6P-12 |
| | | | | 6P-13 |
| 7# | | 118 | 11:02 | 6P-13 |
| | | | | 6P-14 |
| | | | | Top off 6P 11-12 |
| 7# | | 119 | 12:50 | Top off 6P8-13 |
| | | | | 6P-14 |
| 7# | | 120 | 1:10 | 6P-14 |
| | | | | |
| 7# | 11/12/14 | 121 | 9:05 | 6P-14 |
| | | | | 6P-15 |
| | | | | 6P-16 |
| | | | | 6P-17 |
| 7# | | 122 | | 6P-17 |
| | | | | 6P18 |
| | | | | 6P-19 |
| 7# | | 123 | | 6P-19 |
| | | | | 6P-20 |
| | | | | 6P-21 |
| 7# | | 124 | 11:06 | 6P-21 |
| | | | | 6P-22 |
| 6.6# | | 125 | 12:55 | 6P-22 |
| | | | | 7P-1 |
| | | | | 7P-2 |
| 6.6# | | 126 | | 7P-2 |
| | | | | 7P-3 |
| | | | | Top off 6P-19-23 |
| 6.6# | | 127 | 1:42 | 7P-4 |
| | | | | 7P-5 |
| | | | | 7P-6 |
| | | | | Top off 7P4-6P1 |
| 6.6# | | 128 | 1:55 | Not Used |
| | | | | |
| | | | | |

**Amec**
**SA-6 South Grouted Angles** (5")

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 6.6# | 11/13/14 | 129 | 8:59 | Top off 6P14-7P6 |
| | | | | 7P-10 |
| 6.6# | | 130 | 9:29 | 7P-10 |
| | | | | 7P-11 |
| | | | | 7P-12 |
| 6.6# | | 131 | 9:56 | 7P-12 |
| | | | | 7P-13 |
| | | | | Top off 7P10-11 |
| 6.6# | | 132 | 10:35 | 7P-4 |
| | | | | 7P-7 |
| | | | | 7P-8 |
| 6.6# | | 133 | 10:58 | 7P-8 |
| | | | | Top off sheets |
| 6.6# | | 134 | 1:35 | Top off 7P-8 |
| | | | | 7P-9 |
| 6.6# | | 135 | | 7P-9 |
| | | | | 7P-10 |
| | | | | 7P-11 |
| | | | | 7P-12 |
| 6.6# | | 136 | 2:30 | 7P-12 |
| | | | | 7P-13 |
| | | | | 8P-1 |
| | | | | Top off 7P9-12 |
| | | | | 8P-2 |
| | | | | |
| 6.6# | 11/14/14 | 137 | 10:05 | Batch twisted |
| 6.6# | | 138 | | 8P-2 |
| | | | | 8P-3 |
| 6.6# | | 139 | | 8P-3 |
| | | | | 8P-4 |
| | | | | 8P-5 |
| | | | | 8P-6 |
| 6.6# | | 140 | | 8P-7 |
| | | | | 8P-8 |
| 6.6# | | 141 | | 8P-8 |
| | | | | 8P-9 |
| 6.6# | | 142 | | 8P-10 |
| | | | | 8P-11 |
| 6.6# | | 143 | 12:55 | 8P-12 |
| | | | | 8P-13 |
| | | | | 8P-14 |
| | | | | 8P-15 |
| 6.6# | | 144 | 1:30 | 8P-15 |
| | | | | 8P-16 |
| | | | | 8P-17 |
| | | | | 8P-18 |
| 6.6# | | 145 | 1:48 | 8P-18 |
| | | | | 8P-19 |

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 6.6# | 11/14/14 | 146 | 2:08 | 8P-19 |
| | | | | 8P-20 |
| 6.6# | | 147 | 2:25 | Top off sheets |
| | | | | |
| 6.6# | 11/17/14 | 148 | 7:52 | Top off sheets |
| | | | | 7P-3,8,9,10 8P-10 |
| 6.6# | | 149 | 9:10 | Top off sheets |
| | | | | 8P-11 to 8P-20 |
| | | | | |
| 6.6# | 11/18/14 | 150 | 9:30 | 8P-20 |
| | | | | 8P-21 |
| 6.6# | | 151 | 9:45 | 8P-21 |
| | | | | 8P-22 |
| 6.6# | | 152 | 10:00 | 8P-22 |
| | | | | 8P-23 |
| 6.6# | | 153 | 10:12 | 8P-24 |
| | | | | 8P-25 |
| 6.6# | | 154 | 10:34 | 8P-26 |
| | | | | 8P-27 |
| 6.6# | | 155 | 10:45 | Top off 8P20-27 |
| | | | | |
| 6.6# | | 156 | 11:05 | 8P-33 |
| | | | | 8P-34 |
| 6.6# | | 157 | 1:03 | 8P-34 |
| | | | | 8P-35 |
| 6.6# | | 158 | 1:20 | 8P-36 |
| | | | | |
| 6.6# | | 159 | 1:36 | 8P-36 |
| | | | | 8P-37 |
| | | | | 8P-38 |
| 6.6# | | 160 | 1:50 | 8P-38 |
| | | | | 8P-39 |
| | | | | 8P-40 |
| 6.6# | | 161 | 2:10 | 8P-40 |
| | | | | 8P-41 |
| 6.6# | | 162 | 2:30 | Top off 8P20-27 |
| | | | | 8P33-39 |
| | | | | |
| 6.6# | 11/19/14 | 163 | 10:20 | 8P-42 |
| | | | | 8P-43 |
| 6.6# | | 164 | 10.43 | 8P-43 |
| | | | | 8P-44 |
| 6.6# | | 165 | 11:00 | Top off 8P44-33 |
| 6.6# | | 166 | 12:53 | 8P-28 |
| | | | | 8P-29 |
| 6.6# | | 167 | 1.16 | 8P-30 |
| | | | | 8P-31 |
| | | | | 8P-32 |
| 6.6# | | 168 | 1:43 | Top off 8P28-32,40-44 |

Batch: 94# Cement Type II
6.58# Bentonite
8 gal H2O

**Amec**
**SA-6 South Grouted Angles (2")**

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 6.6# | 11/20/14 | 169 | | 25P-28 |
| | | | | 25P-27 |
| 6.6# | | 170 | | 25P-27 |
| | | | | 25P-26 |
| 13.2# | | 171 | | 25P-25 |
| | | | | 25P-24 |
| | | | | 25P-23 |
| | | | | 25P-22 |
| | | | | 25P-21 |
| | | | | 25P-20 |
| 13.2# | | 172 | 9:58 | 25P-20 |
| | | | | 25P-19 |
| | | | | 25P-18 |
| | | | | 25P-17 |
| | | | | 25P-16 |
| | | | | 25P-15 |
| | | | | Top off 25P-15-8P40 |
| | | | | |
| 13.2# | | 173 | 1:56 | 25P-14 |
| | | | | 25P-13 |
| | | | | 25P-12 |
| | | | | 25P-11 |
| | | | | Top off 25P-11 1021 |
| | | | | |
| 13.2# | 11/21/14 | 174 | 8:20 | 25P-10 |
| | | | | 25P-9 |
| | | | | 25P-6 |
| | | | | Top off sheets |
| 13.2# | | 175 | 9:18 | 25P-5 |
| | | | | 25P-4 |
| | | | | 25P-2 |
| | | | | 24P-18 |
| | | | | 24P-17 |
| | | | | Top off sheets |
| 13.2# | | 176 | 10:42 | 25P-8 |
| | | | | 25P-7 |
| | | | | 25P-3 |
| | | | | 25P-1 |
| | | | | 24P-16 |
| | | | | 24P-15 |
| 13.2# | | 177 | 12:58 | 24P-14 |
| | | | | 24P-13 |
| | | | | 24P-12 |
| | | | | Top off all sheets |
| | | | | grouted today |
| | | | | |
| | | | | |
| | | | | |

| | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 13.2# | 11/24/14 | 178 | 10:02 | 23P-13 |
| | | | | 23P-12 |
| | | | | 23P-11 |
| | | | | 23P-10 |
| | | | | 23P-9 |
| | | | | 23P-8 |
| 13.2# | | 179 | 10:42 | 23P-8 |
| | | | | 23P-7 |
| | | | | 23P-6 |
| | | | | 23P-5 |
| 13.2# | | 180 | 11:11 | 23P-5 |
| | | | | 23P-4 |
| | | | | 23P-3 |
| | | | | 23P-2 |
| | | | | 23P-1 |
| | | | | Top off sheets |
| 13.2# | | 181 | 1:36 | 22P-13 |
| | | | | 22P-12 |
| | | | | 22P-11 |
| 13.2# | | 182 | 2:01 | 22P-11 |
| | | | | 22P-10 |
| | | | | 22P-9 |
| | | | | 22P-8 |
| 13.6# | | 183 | 2:20 | Top off sheets |
| | | | | |
| 13.2# | 11/25/14 | 184 | 9:13 | Top off sheets |
| | | | | 22P-13-8, all 23Ps |
| | | | | 22P-7 |
| | | | | 22P-6 |
| 19.8# | | 185 | 9:46 | 22P-5 |
| | | | | 22P-4 |
| | | | | 22P-3 |
| | | | | 22P-2 |
| | | | | 22P-1 |
| | | | | 21P-12 |
| 13.2# | | 186 | 10:33 | Top off sheets |
| | | | | |
| 13.2# | 11/26/14 | 187 | 8:20 | 21P-9 |
| | | | | 21P-8 |
| | | | | Topped off 22P 1-7 |
| 13.2# | | 188 | 10:10 | 21P-8 @ 20' |
| | | | | 21P-6 |
| | | | | 21P-5 |
| | | | | 21P-4 |
| | | 189 | 11:00 | 21P-2 |
| | | | | 21P-1 |
| | | | | Topped off sheets |
| 13.2# | | 190 | — | Batch wasted |

**Amec**
**SA-6 South Grouted Angles** (2")

| B. | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 13.2# | 12/1/14 | 191 | 9:08 | 23P1-A |
| | | | | 20P-15 |
| 13.2# | | 192 | 9:56 | 20P-15 |
| | | | | 20P-14 |
| | | | | 20P-13 |
| | | | | 20P-12 |
| | | | | 20P-11 |
| | | | | 20P-10 |
| 13.2# | | 193 | 10:24 | 20P-9 |
| | | | | 20P-8 |
| | | | | 20P-7 |
| | | | | 20P-3 |
| | | | | 20P-2 |
| | | | | 20P-1 |
| | | | | Special 19P E |
| 13.2# | | 194 | 12:50 | Special 19P W |
| | | | | Top off SP19-22Ps |
| | | | | |
| 13.2# | 12/2/14 | 195 | 1:45 | 19P-64 |
| | | | | 19P-63 |
| 19.8# | | 196 | 2:35 | 19P-64 |
| | | | | 19P-63 |
| | | | | 19P-66 |
| | | | | Top off 19P63-22P7 |
| | | | | |
| 13.2# | 12/3/14 | 197 | 9:33 | 19P-53 |
| 13.2# | | 198 | 10:15 | 19P-53 |
| 13.2# | | 199 | 11:05 | 19P-74 |
| 13.2# | | 200 | 1:00 | 19P-74 |
| 21# | (7#B/batch) | 201 | 2:20 | 19P-71 |
| | | | | 19P-74 |
| | | | | 19P-76 |
| | | | | |
| 14# | 12/4/14 | 202 | 9:19 | 19P-75 |
| | (7#B/batch) | | | Top off 71-76 |
| | | | | 19P-77 |
| | | | | 19P-78 |
| 14# | | 203 | 11:20 | 19P-78 |
| | | | | 19P-79 |
| 14# | | 204 | 2:05 | 19P-80 @ 18.5 |
| | | | | 19P-81 |
| | | | | 19P-82 |
| | | | | Top off sheets |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|
| | | | |
| | | | |
| | | | |

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 07, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | X | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/07/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Friday, November 07, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence at the northwest corner of Surcharge Area 1-S (where it meets the SA-7 SCB wall) requires maintenance. |
| 2 | IA2Q4A1AL8 | REPEAT- Sediment is accumulating along the north and south sides of Kellogg Street in the area of the temporary sheetpile. |
| 3 | IA2Q4A1AL8 | Silt fence along the south side of Surcharge Area 2-N requires maintenance. |
| 4 | IA2Q4A1AL8 | The western section of the southern paved road on Study Area 7 is coated with sediment and the bottom of the ramp which leads from the 2-S surcharge stockpile onto SA-7 has accumulated excess mud. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 11/07/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the silt fence. | 11-11-14 RAD |
| 2 | Remove the sediment from both side of the western end of Kellogg Street and dispose of on site. | 11-10-14 RAD |
| 3 | Repair or replace the silt fence. | 11-11-14 RAD |
| 4 | Clean the roadway and place stone as needed at the toe of the 2-S ramp | 11-10-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 11/12/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 13, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/13/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, November 13, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The stone tracking pad for the vehicle gate at the west end of Kellogg Street is blinded with sediment and requires maintenance. |
| 2 | IA2Q4A1AL8 | A drum is located on the western end of surcharge area 1-N. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Date: 11/13/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Rework the tracking pad and add stone as necessary to restore function. | 11-14-14 RAD |
| 2 | Relocate the drum to the proper storage area. | 11-14-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 11/17/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 20, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/21/14

SWPPP Observer: _____
Signature

Diana Nickens 973 677 4573 HR Fax 630 986 5211

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, November 20, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone signs are not present along the hydraulic barrier wall which borders the south side of the southern cap area. |
| 2 | IA2Q4A1AL8 | Storm water is ponded in the bottom of the Study Area 6 South excavation |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing surrounding the EZ in the sedimentation basin requires maintenance/repair. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Signature Date: 11/21/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install Exclusion Zone signs as required | 11/24/14 RAD |
| 2 | Pump the ponded storm water to the Construction Water Treatment plant when conditions permit. | 11/25/14 RAD |
| 3 | Maintain/repair the orange fencing which surrounds the sedimentation basin EZ. | 11/21/14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 11/26/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 25, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☑ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/25/14

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
Tuesday, November 25, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence along the southern toe of the 1-S surcharge area requires maintenance. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing surrounding the LOAM excavation area requires maintenance/repair. |
| 3 | IA2Q4A1AL8 | Ponded storm water is present in the bottom of the main excavation on Study Area 6 South |
| 4 | IA2Q4A1AL8 | The perimeter fencing adjacent to the JCMUA and the JCIA buildings on Study Area 6 North has openings left from the utility cut-off which took place last night. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ (Signature) Date: 11/25/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Properly reinstall the silt fence where it has fallen down. | 12-1-14 RAD |
| 2 | Repair or replace the exclusion zone fencing as required | 12-1-14 RAD |
| 3 | Pump the ponded storm water to the Construction Water Treatment plant when conditions permit. | 12-2-14 RAD |
| 4 | Reinstall fencing panels as required to close the gaps between Study Area 6 North and the JCMUA/JCIA properties. | 11-26-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 12/02/14

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (October 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

November 19, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the October 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 10 | 01 | 14 | 10 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,763 | 81,406 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.52 | 0.56 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00021 | 0.00021 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.078 | 0.078 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT


Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

Nov. 17, 2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 10 | 01 | 14 | 10 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,379,666 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 20,037,875 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 10/14/2014 | 6.8 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |


| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE Nov. 17, 2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | MONTH: October 2014 | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 10/1/2014 | Angel Trujillo | 17658209 | 17737498 | 79,289 | 0.079289 | 7.01 | 0.819 | | | | | | | | | 0.54 |
| 10/2/2014 | Angel Trujillo | 17737498 | 17809440 | 71,942 | 0.071942 | 6.97 | 0.819 | | | | | | | | | 0.49 |
| 10/3/2014 | Angel Trujillo | 17809440 | 17889143 | 79,703 | 0.079703 | 7.59 | 0.819 | | | | | | | | | 0.54 |
| 10/4/2014 | Angel Trujillo | 17889143 | 17969739 | 80,596 | 0.080596 | 7.61 | 0.819 | | | | | | | | | 0.55 |
| 10/5/2014 | Angel Trujillo | 17969739 | 18048669 | 78,930 | 0.07893 | 7.62 | 0.819 | | | | | | | | | 0.54 |
| 10/6/2014 | Angel Trujillo | 18048669 | 18120755 | 72,086 | 0.072086 | 7.58 | 0.819 | | | | | | | | | 0.49 |
| 10/7/2014 | Angel Trujillo | 18120755 | 18197176 | 76,421 | 0.076421 | 7.57 | 0.819 | | | | | | | | | 0.52 |
| 10/8/2014 | Angel Trujillo | 18197176 | 18273255 | 76,079 | 0.076079 | 7.26 | 0.819 | | | | | | | | | 0.52 |
| 10/9/2014 | Angel Trujillo | 18273255 | 18351504 | 78,249 | 0.078249 | 7.54 | 0.819 | | | | | | | | | 0.53 |
| 10/10/2014 | Angel Trujillo | 18351504 | 18428643 | 77,139 | 0.077139 | 7.51 | 0.819 | | | | | | | | | 0.53 |
| 10/11/2014 | Angel Trujillo | 18428643 | 18503995 | 75,352 | 0.075352 | 7.56 | 0.819 | | | | | | | | | 0.51 |
| 10/12/2014 | Angel Trujillo | 18503995 | 18579380 | 75,385 | 0.075385 | 7.52 | 0.819 | | | | | | | | | 0.51 |
| 10/13/2014 | Angel Trujillo | 18579380 | 18652486 | 73,106 | 0.073106 | 7.60 | 0.819 | | | | | | | | | 0.50 |
| 10/14/2014 | Angel Trujillo | 18652486 | 18732296 | 79,810 | 0.07981 | 7.18 | 0.819 | <5.1 | 6.8 | | <0.010 | <0.030 | <0.010 | 0.00021 | <0.020 | 0.55 |
| 10/15/2014 | Angel Trujillo | 18732296 | 18811766 | 79,470 | 0.07947 | 7.64 | 0.819 | | | | | | | | | 0.54 |
| 10/16/2014 | Angel Trujillo | 18811766 | 18889704 | 77,938 | 0.077938 | 7.54 | 0.819 | | | | | | | | | 0.53 |
| 10/17/2014 | Angel Trujillo | 18889704 | 18967139 | 77,435 | 0.077435 | 7.54 | 0.819 | | | | | | | | | 0.53 |
| 10/18/2014 | Angel Trujillo | 18967139 | 19046494 | 79,355 | 0.079355 | 7.59 | 0.819 | | | | | | | | | 0.54 |
| 10/19/2014 | Angel Trujillo | 19046494 | 19123486 | 76,992 | 0.076992 | 7.59 | 0.819 | | | | | | | | | 0.53 |
| 10/20/2014 | Angel Trujillo | 19123486 | 19196617 | 73,131 | 0.073131 | 7.60 | 0.819 | | | | | | | | | 0.50 |
| 10/21/2014 | Angel Trujillo | 19196617 | 19272778 | 76,161 | 0.076161 | 7.64 | 0.819 | | | | | | | | | 0.52 |
| 10/22/2014 | Angel Trujillo | 19272778 | 19349216 | 76,438 | 0.076438 | 7.60 | 0.819 | | | | | | | | | 0.52 |
| 10/23/2014 | Angel Trujillo | 19349216 | 19424758 | 75,542 | 0.075542 | 7.57 | 0.819 | | | | | | | | | 0.52 |
| 10/24/2014 | Angel Trujillo | 19424758 | 19501958 | 77,200 | 0.0772 | 7.57 | 0.819 | | | | | | | | | 0.53 |
| 10/25/2014 | Angel Trujillo | 19501958 | 19583364 | 81,406 | 0.081406 | 7.20 | 0.819 | | | | | | | | | 0.56 |
| 10/26/2014 | Angel Trujillo | 19583364 | 19663053 | 79,689 | 0.079689 | 7.35 | 0.819 | | | | | | | | | 0.54 |
| 10/27/2014 | Angel Trujillo | 19663053 | 19731713 | 68,660 | 0.0687 | 7.41 | 0.819 | | | | | | | | | 0.47 |
| 10/28/2014 | Angel Trujillo | 19731713 | 19808186 | 76,473 | 0.076473 | 7.36 | 0.819 | | | | | | | | | 0.52 |
| 10/29/2014 | Angel Trujillo | 19808186 | 19884950 | 76,764 | 0.076764 | 7.61 | 0.819 | | | | | | | | | 0.52 |
| 10/30/2014 | Angel Trujillo | 19884950 | 19961849 | 76,899 | 0.076899 | 7.60 | 0.819 | | | | | | | | | 0.53 |
| 10/31/2014 | Angel Trujillo | 19961849 | 20037875 | 76,026 | 0.076026 | 7.53 | 0.819 | | | | | | | | | 0.52 |
| TOTAL | | | | 2,379,666 | 2.379666 | | | <5.1 | 6.8 | | <0.010 | <0.030 | <0.010 | 0.00021 | <0.020 | |
| | | | High: | 81,406 | | | | | | | | | | | High: | 0.56 |
| | | | Average: | 76,763 | | | | | | | | | | | Average: | 0.52 |



**Honeywell** — Chain Of Custody / Analysis Request

JB79184

| | | |

Accutest LabLink@821623 17:03 24-Oct-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101414-A | | |
| Lab Sample ID: | JB79184-1 | Date Sampled: | 10/14/14 |
| Matrix: | AQ - Water | Date Received: | 10/14/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 819 | 10 | ug/l | 1 | 10/16/14 | 10/17/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 10/16/14 | 10/17/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 10/16/14 | 10/17/14 | ND | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | 0.21 | 0.20 | ug/l | 1 | 10/16/14 | 10/16/14 | JW | EPA 245.1 [1] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 10/16/14 | 10/17/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 10/16/14 | 10/17/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA35182
(2) Instrument QC Batch: MA35183
(3) Instrument QC Batch: MA35192
(4) Prep QC Batch: MP82580
(5) Prep QC Batch: MP82614

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@821623 17:03 24-Oct-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101414-A | | |
| Lab Sample ID: | JB79184-1 | Date Sampled: | 10/14/14 |
| Matrix: | AQ - Water | Date Received: | 10/14/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 10/17/14 | KP | SM2540 D-11 |
| pH [a] | 7.79 | | su | 1 | 10/14/14 08:27 | JM | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@821623 17:03 24-Oct-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-101414-A | | |
| **Lab Sample ID:** | JB79184-1A | **Date Sampled:** | 10/14/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 10/14/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 6.8 | 2.0 | mg/l | 1 | 10/15/14 19:07 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@821623 17:03 24-Oct-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101414-B | | |
| Lab Sample ID: | JB79184-2 | Date Sampled: | 10/14/14 |
| Matrix: | AQ - Water | Date Received: | 10/14/14 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N240051.D | 1 | 10/16/14 | DC | n/a | n/a | VN10187 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA PPL List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.4 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.4 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.22 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 18.3 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.2 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.48 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 47.5 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.5 | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 103% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 101% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 100% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@821623 17:03 24-Oct-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101414-B | | |
| Lab Sample ID: | JB79184-2 | Date Sampled: | 10/14/14 |
| Matrix: | AQ - Water | Date Received: | 10/14/14 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 10/16/14 | BM | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending November 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal to Parties' per request. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 8 OF 25**

- **2015 Monthly Reports Part 1**

**1/14/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

January 14, 2015 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
49 Bridge Street, Suite 2
Lambertville, NJ 08530

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2014-12**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from December 1 – December 31, 2014.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: December 2014 SA-6/7 Combined Monthly Progress Report No. 2014-12

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2014-12

**Project SA-6 & 7 Remediation**

## December 2014

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 12/03/14 | SA-7 Groundwater Pump & Treat System Performance<br>In-Situ Sampling beneath Hackensack River Sediments<br>Study Area 7<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 12/03/14 | Deep Overburden Injection Program<br>Redevelopment of Injection Well -088-IW-01<br>Study Area 7<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 12/15/14 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2014-11<br>Study Areas 6 and 7<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 12/16/14 | Special Master Conference Call | N/A |
| 12/18/14 | Revised In-situ Work Plan for Treatment Area 10<br>Study Area 6 North<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 12/19/14 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 12/7/14 | 12/14/14 | 12/21/14 | 12/28/14 |
| **Construction Management (AMEC)** | 11 | 11 | 12 | 8 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 0 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 33 | 33 | 29 | 29 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **Gramercy** | 22 | 19 | 8 | 7 |
| **TOTAL STAFF** | **73** | **70** | **56** | **49** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected December PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed universal waste removal and asbestos abatements activities at the JCIA demolition project. Contractor continued site preparation and began trash pit protection activities.
- Conducted a round of quarterly groundwater level measurements. Conducted quarterly groundwater sampling of GWET extraction wells.
- Conducted semi-annual groundwater sampling under the S-3 Mass Removal Injection program.
- Continued to advance permit application and discussions with New Jersey Department of Transportation (NJDOT) regarding Highway Occupancy and Drainage Permits for upcoming SA-6 activities proximate to the Rt. 440 frontage.
- On December 8, 2014, a leaking diesel line was identified on a water truck. This necessitated several yards of surficial soil to be removed and segregated. The incident was called in to the NJDEP hotline, and Incident number for this non-emergency incident is: 14-12-08-1503-35.

- On December 29, 2014, obtained the JCIA Structures Demolition Permit from the City of Jersey City.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on December 9, 2014.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 12/7/14 | 12/14/14 | 12/21/14 | 12/28/14 |
| Avg. Gallons Treated & Discharged (per day) | 76,366 | 76,513 | 75,612 | 77,129 |
| Average Flow (gpm) for Operating Period | 53 | 53 | 53 | 54 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 6,840 | 6,916 | 5,566 | 10,356 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued storm-water management activities.
- Completed excavation activities associated with the lens of anomalous material on SA-6 South proximate to Cell 104.
- Collected a post-excavation sidewall sample, 134-SB-177, from the southeast side of the anomalous material excavation on December 2, 2014. Laboratory analysis received on December 12, 2014 indicated the result was 2.6 mg/kg. Submitted the certification of excavation complete to the parties with all sampling results on January 7, 2015.
- Completed excavation of locations designated as Area 41 and Area 43. Began backfill activities associated with the anomalous material excavation, Site 163 and Area 41.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued compaction testing associated with imported backfill. Adjusted the frequency of testing in accordance with specifications.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 0 | 0 | 0 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Entact/ Horwith** | Tri-axle Dump | PA Transload | US Ecology | >1000 mg/kg Soils | 65 | 21.54 | 1400.5 |
| **Entact/ Montecalvo** | 30 cyd roll-off | Bayshore Recycling | Bayshore | Non Haz Creosote Debris | 1 | 10.46 | 10.46 |
| **Gramercy-(JCIA Demo)** | 40 cyd roll off | West Babylon, NY | 110 Sand Company | Non Friable ACM | 6 | 17.40 | 104.44 |
| **Gramercy-(JCIA Demo)** | 40 cyd rol off | Newburg, PA | Cumberland County Landfill | Friable ACM | 1 | * | * |
| **Entact/ Arecon** | Tri-axle Dump | Keasbey, NJ | Bayshore | Petroleum Impacted Soil | 20 | 24.34 | 486.85 |
| **Entact/ Arecon** | Tri-axle Dump | Keasbey, NJ | Bayshore | Non-HAZ PAH_PET 124/140 | 19 | 25.0 | 476.41 |

** Not currently available. To be provided in Progress Report No. 2015-01*

## 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Anomalous Material near Cell 104, Site 163, Area 41<br>Volume Excavated - Total for Reporting Period: 10,910CY/ Total to Date: 162,210CY |
| **Backfill in Progress** | Cell Number(s) 104-59, Site 163, Area 41 |

## 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 12/7/14 | 12/14/14 | 121/21/14 | 12/28/14 |
| <20ppm re-use, CY | 0 | 113 | 1,598 | 0 |
| Weldon, Import-Tons Screenings | 0 | 0 | 0 | 0 |
| Tilcon, Import-Tons DGA | 755 | 0 | 0 | 0 |
| Tilcon, Import Tons – 1.5” Stone | 0 | 0 | 0 | 0 |
| Weldon, Imported Tons - QP | 0 | 0 | 0 | 0 |
| Weldon, Imported Tons - DGA | 0 | 0 | 0 | 0 |
| Tilcon, Imported 6”-8” stone | 0 | 0 | 0 | 0 |
| Tilcon, Imported Tons – 2.5” Stone | 0 | 0 | 0 | 0 |

## E. SURCHARGE OPERATIONS

- Area 1S: Continue offloading Celgene material from 1S and relocating to 2S approximately 75% complete.
- Area 2S: Surcharging continued on Area 2S. Surcharge placement consisted of both chromium impacted soils to the design sub-grade and both imported Celgene and Novartis soils. Surcharge placement is approximately 90% complete.
- Area 3S: Surcharge placement continued on Area 3S and is approximately 40% complete.
- Area 1N: Continued surcharge removal activities. Surcharge removal activities are approximately 80% complete. Details were provided in the December 2014 Surcharge Monitoring Report No. 7.
- Area 2N: Surcharge placement is 100% complete. Monitoring data (provided in Surcharge Monitoring Report No. 7) indicates that surcharge has attained the goals per the 100% Design and may be removed.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

## F. SHEET PILE OPERATIONS *(see **Attachment 10**)*

- Continue grouting angles of sheet pile at SA-6 South.
- Excavation proximate to the SA-6 South barrier wall was completed on October 28, 2014 and backfill has been progressed in all areas against the SA-6 South barrier wall. Deflection readings are therefore no longer required.

## G. PERMIT STATUS

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |

| PERMIT | SITE | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 | Pending | Pending | Pending |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | Pending | Pending | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue JCIA Structures Demolition activities to include trash pit protection and initiation of above-grade structure demolition activities.
- Continue placement of surcharge materials in SA-6 South Area 2S and Area 3S.
- Continue off loading of surcharge materials from SA-6 South Area 1S.
- Continue installation of the contingent groundwater system trench on SA-6 South.
- Complete excavation of Area 42 and the remaining soil on the eastern side of Site 163.
- Continue loadout and transportation and disposal activities at SA-6 South.
- Continue backfill placement and associated compaction testing activities at SA-6 South.
- Continue accepting delivery of steel sheetpile for SA-6 North Barrier Wall installation.
- Conduct well development of injection well 088-IW-01 on SA-6 North.
- Conduct well development of GWET extraction well PW-2.
- Conduct acid cleaning of the PW-2 force main.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Complete sediment long term monitoring activities and final report preparation.

- Obtain NJDOT Highway Occupancy Permit for upcoming SA-6 North activities proximate to Rt. 440 frontage.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
   - Figure 1: Lens of Anomalous Material Supplemental Boring Locations
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Deep Well Data (DW-4)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. Groundwater Quality Data Surcharge Monitoring Update
   - Summary of Groundwater Quality Data from GWET Wells
   - Quarterly Water Wells
   - Trichloroethene/Chloroform/Hexavalent Chromium in GWET Wells
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Hydraulic Barrier Wall Plan & Profile
    - Sheet Pile Angle Grout Log
11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (November 2014)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

Study Areas 6 and 7 Combined Progress Report No. 2014-12
Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration |
|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** |
| 19 | Develop Site Relocation Master Plan | 38 days |
| 20 | Submit Site Relocation Master Plan | 0 days |
| 21 | JC Construction of New Facilities | 1309 days |
| 22 | Relocation Contractor Procurement | 392 days |
| 23 | JCIA and JCDPW Relocation | 753 days |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days |
| 24a | Demolition of JCIA Structures | 151 days |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** |
| **57** | **SA-6 South Relocation** | **616 days** |
| 58 | New GWTP Construction Completion | 502 days |
| 59 | Demolition of 80 Kellogg | 857 days |
| **60** | **SA-6 North/South Field Implementation** | **838 days** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** |
| 61a | Mobilization | 87 days |
| **62** | **Surcharge Install/Instrumentation** | **620 days** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days |
| **63** | **Barrier Wall Install** | **489 days** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days |
| **64** | **Excavation** | **507 days** |
| 64a | SA 6N Excavation | 218 days |
| **64b** | **SA 6S Excavation** | **226 days** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days |
| **65** | **Backfill** | **493 days** |
| 65a | SA 6N Backfill | 218 days |
| 65b | SA 6S Backfill | 232 days |
| **66** | **Capping and Cover Soil Placement** | **315 days** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days |
| **67** | **Restoration** | **164 days** |
| 67a | Restoration | 164 days |
| **68** | **Demobilization** | **21 days** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | |




Project: SA-6 Remediation Schedule
Revision 3
Date: Mon 1/5/15

Task | Milestone | Summary | Critical

# Attachment 2: Site Photographs



**Site Photograph 1:** Abatement and removal activities Former JCIA Building.



**Site Photograph 2:** Contractor completes utility disconnects Former JCIA Property.




**Site Photograph 3:** Contractor excavates along Kellogg Street.




**Site Photograph 4:** Contractor removes roofing Former JCIA Salt Dome.




**Photograph 5:** PSEG removing transformers Former JCIA Buildings.





**Site Photograph 6:** Surcharge placement continues Open Space Areas.

## Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables: SA-6 South Excavation: Confirmatory/Center/ Sidewall Confirmatory Points
- Figure 1: Lens of Anomalous Material Supplemental Boring Locations
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies Progress as of January 1, 2015

December 2014 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM O EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE
- LIMIT OF EXCAVATION AREA

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS LENS AREA & AREA 41
PERIOD 11-13-14 TO 12-08-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.
Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | * Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | * Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | * Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | * Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -5.5 | 134-SB-019 | 114A | 12/8/2014 | -5.7 | Stratum D (Re-Excavated) |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.4 | 601974.0 | -3.3 | 134-SB-061 | 106A | 11/20/2014 | -5.7 | Stratum D Reached (Re-Excavated) |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.7 | 601978.2 | -7.5 | 134-SB-113 | 103 | 11/20/2014 | -7.6 | Stratum D Reached (Re-Excavated) |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |
| 684908.2 | 602155.7 | -8.0 | 134-SB-049 | 89 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684943.6 | 602214.1 | -6.9 | 140-SB-035 | 88 | 8/25/2014 | -6.7 | Stratum D Reached |
| 684905.5 | 602180.6 | -7.8 | 140-SB-063 | 88 | 8/25/2014 | -6.1 | Stratum D Reached |
| 684875.3 | 602175.3 | -7.8 | 140-SB-062 | 87 | 8/25/2014 | -5.8 | Stratum D Reached |
| 684875.5 | 602187.9 | -7.3 | 140-SB-103 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684915.0 | 602239.0 | -6.1 | 140-SB-007 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |
| 684896.1 | 602229.3 | -6.6 | 140-SB-038 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684862.9 | 602228.0 | -6.1 | 134-SB-032R | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684901.7 | 602269.3 | -5.3 | 140-SB-040 | 83 | 9/4/2014 | -5.7 | Stratum D Reached |
| 684826.5 | 602208.8 | -6.5 | 140-SB-051 | 83 | 9/4/2014 | -4.7 | Stratum D Reached |
| 684854.3 | 602237.3 | -6.7 | 140-SB-041 | 83 | 9/4/2014 | -4.9 | Stratum D Reached |
| 684771.0 | 602188.4 | -4.8 | 140-SB-044 | 82 | 9/10/2014 | -5.2 | Stratum D Reached |
| 684800.2 | 602210.9 | -6.5 | 140-SB-042 | 82 | 9/10/2014 | -4.7 | Stratum D Reached |
| 684865.2 | 602271.1 | -6.2 | 140-SB-064 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684830.9 | 602252.5 | -6.3 | 140-SB-066 | 81 | 9/17/2014 | -3.1 | Stratum D Reached |
| 684716.6 | 602169.4 | -0.2 | 140-SB-043 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684755.4 | 602222.4 | -5.7 | 140-SB-047 | 80 | 9/23/2014 | -4.6 | Stratum D Reached |
| 684823.4 | 602275.4 | -5.0 | 140-SB-048 | 80 | 9/17/2014 | -2.8 | Stratum D Reached |
| 684687.1 | 602171.5 | 0.3 | 140-SB-049 | 79 | 9/23/2014 | -3.9 | Stratum D Reached |
| 684721.0 | 602200.6 | -4.2 | 140-SB-046 | 79 | 9/23/2014 | -5.1 | Stratum D Reached |
| 684680.8 | 602178.0 | -3.3 | 140-SB-075 | 79 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684695.5 | 602194.5 | -4.8 | 140-SB-018 | 79 | 9/23/2014 | -4.4 | Stratum D Reached |
| 684767.0 | 602244.0 | -4.4 | 140-SB-010 | 79 | 9/23/2014 | -4.0 | Stratum D Reached |
| 684818.0 | 602299.0 | -5.4 | 140-SB-009 | 78 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684855.0 | 602329.0 | -5.8 | 140-SB-065 | 78 | 9/23/2014 | -2.7 | Stratum D Reached |
| 684656.0 | 602192.0 | -2.7 | 140-SB-026 | 77 | 9/29/2014 | -2.3 | Stratum D Reached |
| 684740.4 | 602255.2 | -5.4 | 140-SB-082 | 77 | 9/29/2014 | -3.5 | Stratum D Reached |
| 684815.0 | 602348.7 | -3.4 | 140-SB-094 | 76 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684787.4 | 602330.2 | -0.4 | 140-SB-086 | 75 | 10/2/2014 | -4.0 | Stratum D Reached |
| 684744.9 | 602306.7 | -1.4 | 140-SB-083 | 75 | 10/2/2014 | -4.5 | Stratum D Reached |
| 684713.1 | 602276.0 | -0.4 | 140-SB-081 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684668.4 | 602240.2 | 0.1 | 140-SB-079 | 75 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684643.7 | 602221.3 | -4.2 | 140-SB-050 | 75 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684628.7 | 602233.7 | -2.9 | 140-SB-074 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684703.0 | 602285.6 | 2.6 | 140-SB-080 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684733.7 | 602322.4 | 0.6 | 140-SB-084 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.9 | 602371.9 | 0.1 | 140-SB-088 | 74 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684653.9 | 602259.3 | -1.4 | 140-SB-078 | 73 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684755.3 | 602343.3 | 0.6 | 140-SB-085 | 73 | 10/7/2014 | -1.6 | Stratum D Reached |
| 684660.7 | 602300.1 | 0.9 | 140-SB-089 | 72 | 10/9/2014 | -2.8 | Stratum D Reached |
| 684693.1 | 602326.3 | -3.0 | 140-SB-090 | 72 | 10/7/2014 | -3.3 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684745.4 | 602367.1 | 1.0 | 140-SB-091 | 72 | 10/7/2014 | -0.1 | Target Elevation Reached |
| 684640.0 | 602295.0 | 1.9 | 140-SB-011 | 71 | 10/9/2014 | -4.0 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | 125-SB-029R | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684629.9 | 602309.5 | 5.8 | 140-SB-033 | 70 | 10/9/2014 | 2.4 | Target Elevation Reached |
| 684725.2 | 602383.8 | 0.4 | 125-SB-029R | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684642.9 | 602315.4 | 0.9 | 140-SB-089R | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684764.0 | 602429.2 | -7.0 | 140-SB-N07 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | 125-SB-029R | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684632.0 | 602327.7 | 5.8 | 140-SB-033R | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684669.3 | 602386.6 | -0.6 | 140-SB-070 | 68 | 10/21/2014 | -2.3 | Stratum D Reached |
| 684679.0 | 602393.0 | 0.0 | 140-SB-013 | 68 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684760.1 | 602448.4 | -1.4 | 140-SB-083R | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | 125-SB-029R | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684629.6 | 602343.1 | 5.8 | 140-SB-033R | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684749.9 | 602465.0 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684700.0 | 602423.0 | 0.8 | 140-SB-012 | 67 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684715.4 | 602440.1 | -1.0 | 140-SB-029 | 67 | 10/21/2014 | -1.4 | Stratum D Reached |
| 684662.8 | 602394.7 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -1.4 | 140-SB-083R | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | 125-SB-073R | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684666.6 | 602417.0 | -2.7 | 140-SB-068 | 66 | 10/21/2014 | -3.0 | Stratum D Reached |
| 684735.5 | 602488.2 | -1.4 | 140-SB-083R | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | 125-SB-029R | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | 125-SB-073R | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | 125-SB-029R | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -1.4 | 140-SB-083R | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684666.2 | 602452.6 | 2.5 | 140-SB-030 | 64 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684735.4 | 602510.4 | -3.6 | 140-SB-067 | 64 | 10/24/2014 | -2.3 | Stratum D Reached |
| 684713.8 | 602503.3 | 4.3 | 140-SB-028 | 63 | 10/27/2014 | -2.4 | Stratum D Reached |
| 684727.7 | 602515.9 | -2.0 | 140-SB-104 | 63 | 10/27/2014 | -2.2 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | 125-SB-029R | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | 125-SB-073R | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | 125-SB-029R | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684653.2 | 602490.5 | 0.2 | 125-SB-057 | 61 | 10/24/2014 | -2.6 | Stratum D Reached |
| 684675.4 | 602508.2 | -1.2 | 125-SB-073 | 61 | 10/27/2014 | -2.5 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.8) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684697.8 | 602526.3 | -2.2 | 125-SB-055 | 61 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684707.1 | 602549.9 | -3.4 | 125-SB-072 | 61 | 10/28/2014 | -2.8 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | 125-SB-029R | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | 125-SB-073R | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | 125-SB-029R | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | 125-SB-069R | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684678.4 | 602552.4 | -2.4 | 125-SB-061 | 59 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684615.0 | 602501.1 | 0.5 | 125-SB-048 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684633.9 | 602516.6 | 0.6 | 125-SB-046 | 59 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684656.3 | 602534.7 | -1.4 | 125-SB-074 | 59 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684604.5 | 602498.0 | 2.1 | 125-SB-069R | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684916.0 | 601955.0 | -1.2 | 134-SB-026 | Area 41 | 12/10/2014 | -2.0 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | UST Area |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | UST Area |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | UST Area |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |
| 684922.3 | 602179.9 | -4.3 | C-89 | 89 | 8/20/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684912.0 | 602189.2 | -4.3 | C-88 | 88 | 8/25/2014 | -6.3 | Stratum D Reached |
| 684895.8 | 602194.1 | -4.3 | C-87 | 87 | 8/25/2014 | -6.0 | Stratum D Reached |
| 684880.8 | 602203.6 | -4.3 | C-86 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684872.8 | 602212.7 | -4.3 | C-85 | 85 | 8/29/2014 | -5.2 | Stratum D Reached |
| 684862.9 | 602228.0 | -4.3 | C-84 | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684820.9 | 602207.7 | -2.5 | C-83 | 83 | 9/4/2014 | -4.5 | Stratum D Reached |
| 684812.4 | 602218.7 | -2.5 | C-82 | 82 | 9/10/2014 | -4.1 | Stratum D Reached |
| 684788.9 | 602227.5 | -2.5 | C-81 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684778.7 | 602237.4 | -2.5 | C-80 | 80 | 9/17/2014 | -4.6 | Stratum D Reached |
| 684759.2 | 602240.0 | -2.5 | C-79 | 79 | 9/23/2014 | -4.1 | Stratum D Reached |
| 684758.4 | 602256.3 | -2.5 | C-78 | 78 | 9/23/2014 | -3.4 | Stratum D Reached |
| 684753.6 | 602273.9 | -2.5 | C-77 | 77 | 9/29/2014 | -3.8 | Stratum D Reached |
| 684731.1 | 602272.7 | -2.5 | C-76 | 76 | 9/29/2014 | -3.0 | Stratum D Reached |
| 684735.0 | 602292.1 | -2.5 | C-75 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684732.6 | 602313.2 | -2.5 | C-74 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.5 | 602381.3 | -2.5 | C-73 | 73 | 10/7/2014 | -2.7 | Stratum D Reached |
| 684752.7 | 602351.0 | 0.4 | C-73-1 | 73 | 10/7/2014 | 0.1 | Target Elevation Reached |
| 684662.4 | 602274.6 | -2.5 | C-73-2 | 73 | 10/7/2014 | -2.1 | Stratum D Reached |
| 684788.0 | 602395.1 | -2.5 | C-72 | 72 | 10/7/2014 | -2.5 | Stratum D Reached |
| 684743.1 | 602361.9 | 0.4 | C-72-1 | 72 | 10/7/2014 | -0.2 | Target Elevation Reached |
| 684664.8 | 602296.2 | -2.5 | C-72-2 | 72 | 10/7/2014 | -3.0 | Stratum D Reached |
| 684783.1 | 602411.4 | -2.5 | C-71 | 71 | 10/9/2014 | -2.7 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | C-71-1 | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684652.0 | 602308.3 | -2.5 | C-71-2 | 71 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684772.6 | 602425.4 | -2.5 | C-70 | 70 | 10/9/2014 | -2.5 | Stratum D Reached |
| 684725.2 | 602383.8 | 0.4 | C-70-1 | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684674.6 | 602346.3 | -2.5 | C-70-2 | 70 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684642.9 | 602315.4 | 0.4 | C-70-3 | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684626.5 | 602306.7 | 5.7 | C-70-4 | 70 | 10/9/2014 | 4.8 | Target Elevation Reached |
| 684762.8 | 602431.3 | -2.5 | C-69 | 69 | 10/14/2014 | -2.7 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | C-69-1 | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684670.5 | 602360.9 | -2.5 | C-69-2 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684632.0 | 602327.7 | 5.7 | C-69-3 | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684760.1 | 602448.4 | -2.5 | C-68 | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | C-68-1 | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684671.6 | 602375.8 | -2.5 | C-68-2 | 68 | 10/14/2014 | -2.2 | Stratum D Reached |
| 684629.6 | 602343.1 | 5.7 | C-68-3 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684749.9 | 602465.0 | -2.5 | C-67 | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684698.4 | 602419.3 | 0.4 | C-67-1 | 67 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684662.8 | 602394.7 | -2.5 | C-67-2 | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -2.5 | C-66 | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | C-66-1 | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | C-66-2 | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | C-66-3 | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684664.0 | 602411.1 | -2.5 | C-66-4 | 66 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684735.5 | 602488.2 | -2.5 | C-65 | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | C-65-1 | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | C-65-2 | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | C-65-3 | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -2.5 | C-65-4 | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684713.4 | 602487.7 | -1.2 | C-64 | 64 | 10/24/2014 | -1.8 | Stratum D Reached |
| 684653.2 | 602444.8 | 0.4 | C-64-1 | 64 | 10/21/2014 | -4.0 | Increased excavation depth - UST location |
| 684701.6 | 602502.1 | -1.2 | C-63 | 63 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | C-63-1 | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | C-62 | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | C-62-1 | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684689.4 | 602527.1 | -1.2 | C-61 | 61 | 10/28/2014 | -2.7 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | C-61-1 | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | C-60 | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | C-60-1 | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | C-60-2 | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684665.2 | 602547.7 | -1.2 | C-59 | 59 | 10/27/2014 | -2.8 | Stratum D Reached |
| 684620.0 | 602510.0 | 0.4 | C-59-1 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684604.5 | 602498.0 | 2.1 | C-59-2 | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 685023.9 | 601966.6 | -2.5 | C-104L | 104 | 11/20/2014 | -6.9 | Stratum D Reached |
| 685033.9 | 601960.1 | -2.5 | C-105L | 105 | 11/20/2014 | -6.6 | Stratum D Reached |
| 685039.4 | 601938.6 | -2.5 | C-106L | 106 | 11/20/2014 | -6.3 | Stratum D Reached |
| 685043.6 | 601927.9 | Stratum D | C-107L | Lens Area | 11/25/2014 | -6.2 | Stratum D Reached |
| 685042.9 | 601906.9 | Stratum D | C-108L | Lens Area | 11/25/2014 | -6.8 | Stratum D Reached |
| 685057.6 | 601895.2 | Stratum D | C-109L | Lens Area | 12/8/2014 | -6.6 | Stratum D Reached |
| 685055.4 | 601873.1 | Stratum D | C-110L | Lens Area | 12/8/2014 | -7.5 | Stratum D Reached |
| 685071.5 | 601867.1 | Stratum D | C-111L | Lens Area | 12/8/2014 | -7.6 | Stratum D Reached |
| 685086.2 | 601861.8 | Stratum D | C-112L | Lens Area | 12/8/2014 | -7.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| 685092.3 | 601848.6 | Stratum D | C-113L | Lens Area | 12/8/2014 | -7.0 | Stratum D Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685471.0 | 601475.6 | 4.3 | 073-SB-079 | 148 | 7/31/2014 | 4.3 | Target Elevation Reached |
| 685451.0 | 601460.9 | 7.1 | 073-SB-082 | 148 | 7/31/2014 | 2.2 | Target Elevation Reached |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Target Elevation Reached |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685081.0 | 601928.1 | -5.5 | 134-SB-021 | 109A | 11/25/2014 | -5.8 | Stratum D Reached (Re-Excavated) |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 684999.6 | 601940.6 | -4.5 | 134-SB-097 | 104 | 11/20/2014 | -7.2 | Stratum D Reached (Re-Excavated) |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |


| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |
| 684887.0 | 602147.0 | -2.1 | 134-SB-100 | 89 | 8/20/2014 | -5.8 | Stratum D Reached |
| 684821.2 | 602190.7 | -4.8 | 140-SB-060 | 84 | 9/4/2014 | -5.2 | Stratum D Reached |
| 684779.8 | 602174.6 | -0.8 | 140-SB-059 | 83 | 9/10/2014 | -5.6 | Stratum D Reached |
| 684727.5 | 602143.2 | 0.7 | 140-SB-076 | 83 | 9/10/2014 | -4.5 | Stratum D Reached |
| 684701.3 | 602132.8 | -0.8 | 140-SB-003 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684686.4 | 602158.8 | -0.8 | 140-SB-105 | 80 | 9/17/2014 | -4.8 | Stratum D Reached |
| 684651.0 | 602180.0 | -2.1 | 140-SB-027 | 77 | 9/29/2014 | -2.8 | Stratum D Reached |
| 684630.0 | 602210.0 | -1.9 | 140-SB-077 | 75 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684622.2 | 602287.4 | -2.0 | 140-SB-034 | 71 | 10/9/2014 | -3.0 | Stratum D Reached |
| 684597.0 | 602258.0 | -3.2 | 140-SB-025 | 71 | 10/9/2014 | -3.1 | Stratum D Reached |
| 684626.0 | 602343.0 | 6.8 | 140-SB-014 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684613.7 | 602330.2 | 6.1 | 140-SB-072 | 68 | 10/14/2014 | 4.5 | Target Elevation Reached |
| 684649.1 | 602367.2 | -1.0 | 140-SB-071 | 68 | 10/14/2014 | -2.8 | Stratum D Reached |
| 684648.1 | 602370.8 | -0.8 | 140-SB-032 | 67 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684649.1 | 602409.4 | -2.3 | 140-SB-069 | 65 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684629.1 | 602423.3 | 1.5 | 140-SB-031 | 64 | 10/21/2014 | -3.5 | Stratum D Reached |
| 684633.2 | 602474.4 | 0.4 | 125-SB-058 | 61 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684616.1 | 602485.8 | 3.0 | 125-SB-068 | 60 | 10/21/2014 | 1.8 | Target Elevation Reached |
| 684588.4 | 602494.2 | 100.0 | 125-SB-119 | 59 | 10/21/2014 | 1.5 | Target Elevation Reached |
| 685087.0 | 601829.1 | Stratum D | 134-SB-171 | Lens Area | 12/8/2014 | -6.1 | Stratum D Reached |
| 685053.5 | 601827.8 | Stratum D | 134-SB-170 | Lens Area | 12/8/2014 | -6.8 | Stratum D Reached |
| 685029.7 | 601840.0 | Stratum D | 134-SB-175 | Lens Area | 12/8/2014 | -6.7 | Stratum D Reached |
| 685003.5 | 601868.2 | Stratum D | 134-SB-177 | Lens Area | 12/8/2014 | -5.9 | Stratum D Reached |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| 684917.7 | 601947.9 | -1.2 | 134-SB-087 | Area 41 | 12/10/2014 | -2.1 | Target Elevation Reached |
| 684936.3 | 601954.8 | -1.2 | 134-SB-088 | Area 41 | 12/10/2014 | -2.4 | Target Elevation Reached |
| 684918.0 | 601975.0 | -1.2 | 134-SB-089 | Area 41 | 12/10/2014 | -1.7 | Target Elevation Reached |
| 684904.3 | 601963.0 | -1.2 | 134-SB-090 | Area 41 | 12/10/2014 | -1.6 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 12/23/14

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**




Revised/Date: TDD 12/11/14
Checked/Date: DEN 12/11/14

| | | | |
|---|---|---|---|
| Honeywell 101 COLUMBIA RD., BOX 2105 MORRISTOWN, NJ 07962 | CHROMIUM REMEDY STUDY AREA 6 SOUTH JERSEY CITY, NEW JERSEY | amec | LENS OF ANOMALOUS MATERIAL SUPPLEMENTAL BORING LOCATIONS FIGURE 1 |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01 | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02 | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-62 | | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-62-1 | 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 0 | BF-64 | | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-64-1 | 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 3 | BF-64-2 | 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-65 | | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-65-1 | 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 0 | BF-66 | | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-66-1 | 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 2 | BF-66-2 | 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 0 | BF-67 | | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-67-1 | 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-67-2 | 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-68 | | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-68-1 | 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-68-2 | 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 0 | BF-69 | | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-69-1 | 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-69-2 | 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-70 | | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-70-1 | 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-70-2 | 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| 0 | BF-71 | | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 5 | BF-71-1 | 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-72 | | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 3 | BF-72-1 | 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| 0 | BF-73 | | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 6 | BF-73-1 | 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 6 | BF-75-2 | 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 6 | BF-76-2 | 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 6 | BF-77-2 | 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 7 | BF-78-2 | 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 7 | BF-80-2 | 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 4 | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 7 | BF-81-2 | 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 6 | BF-82-2 | 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 6 | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 7 | BF-83-3 | 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 6 | BF-84-3 | 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 6 | BF-85-3 | 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-86-2 | 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 1 | RF-14-2 | 11/5/2014 | 684662.9 | 602542.6 | 0.0 | 134.0 | 0.6 | 135.8 | 6.4 | 99 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-16-2 | 11/5/2014 | 684767.6 | 602428.4 | 1.2 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 67 | Weldon WC Screenings | | V5N |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-17-2 | 11/5/2014 | 684723.7 | 602387.9 | 1.5 | 124.0 | 3.8 | 128.9 | 12.1 | 96 | 95 | 70 | Weldon WC Screenings | | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| 6 | RF-18-2 | 11/5/2014 | 684636.8 | 602258.1 | 5.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 73 | Weldon WC Screenings | Placed on Type A material | V5N |
| | RF-19 | | 684790.8 | 602339.5 | -2.5 | | | | | | | 75 | Stratum D | Bottom of excavation elevation | |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | RF-19-1 | 11/5/2014 | 684776.9 | 602328.5 | 1.8 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 75 | Weldon WC Screenings | | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| 4 | RF-21-2 | 11/5/2014 | 684823.4 | 602288.0 | 1.8 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 79 | Tilcon MH DGA | | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| 5 | RF-23-04 | 11/5/2014 | 684877.6 | 602222.8 | 2.5 | 134.0 | 0.7 | 135.8 | 6.4 | 99 | 95 | 85 | Tilcon MH DGA | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| NA | RF-27-LOAM | 12/15/2014 | 685045.9 | 601945.1 | -4.4 | 129.0 | 3.0 | 135.8 | 6.4 | 95 | 95 | 106 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| NA | RF-28-LOAM | 12/15/2014 | 685085.0 | 601862.1 | -4.7 | 135.8 | 4.0 | 135.8 | 6.4 | 100 | 95 | 112 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |

| | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 0 | Site 163-2 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-2-1 | 11/5/2014 | 685070.9 | 601614.2 | 6.1 | 122.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| 2 | Site 163-2-2 | 11/14/2014 | 685070.5 | 601616.0 | 7.5 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |

***Notes:***

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)


Sample ID RF-01-01 where:

RF = Reduced Frequency

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT

01 = Test Location (as noted on Backfill Compaction Location Figure)

01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39, RF-163-01. RF-163-02

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 4: Dewatering Operations Update

- SA-6 South Deep Well Data (DW-4)

## STUDY AREA 6 SOUTH DEEP WELL DATA (DW-4)

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/14/14 | 24 | N/A | N/A | 6,500 | 80,718 | 4.5 | Pump Online for LOAM Excavation |
| 11/17/14 | 72 | N/A | N/A | 19,500 | 100,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/18/14 | 24 | N/A | N/A | 6,500 | 106,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/19/14 | 24 | N/A | N/A | 6,500 | 113,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/20/14 | 24 | N/A | N/A | 6,500 | 119,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/21/14 | 24 | N/A | N/A | 6,500 | 126,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/22/14 | 24 | N/A | N/A | 6,500 | 132,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/24/14 | 48 | N/A | N/A | 13,000 | 145,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/25/14 | 24 | N/A | N/A | 6,500 | 152,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/28/14 | 72 | N/A | N/A | 19,500 | 171,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 11/30/14 | 48 | N/A | N/A | 12,500 | 184,218 | 4.3 | Flow Meter Not Intsalled Tank Measured |
| 12/01/14 | 24 | N/A | N/A | 6,500 | 190,718 | 4.5 | Flow Meter Not Intsalled Tank Measured |
| 12/02/14 | 24 | N/A | N/A | 6,500 | 197,218 | 4.5 | Flow Meter Not Intsalled Tank Measured |

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 10/30/14 | 9:00 | 11:00 | 2:00 | 21,979.83 | 21,987.45 | 7,620 | 21,987,000 | |
| 11/05/14 | 8:00 | 15:00 | 7:00 | 21,987.45 | 22,068.71 | 81,260 | 22,068,260 | PVSC Compliance Sample Collected |
| 11/07/14 | 10:00 | 15:00 | 5:00 | 22,068.71 | 22,093.24 | 24,530 | 22,092,790 | |
| 11/10/14 | 8:00 | 14:30 | 6:30 | 22,093.24 | 22,125.00 | 31,760 | 22,124,550 | CGWES pumped and isolated from 930 to 1530 |
| 11/11/14 | 11:00 | 16:00 | 5:00 | 22,125.00 | 22,151.18 | 26,180 | 22,150,730 | |
| 11/12/14 | 7:15 | 15:15 | 8:00 | 22,151.18 | 22,205.08 | 53,900 | 22,204,630 | |
| 11/13/14 | 7:30 | 15:30 | 8:00 | 22,205.08 | 22,232.39 | 27,310 | 22,231,940 | |
| 11/14/14 | 7:00 | 12:00 | 5:00 | 22,232.39 | 22,270.23 | 37,840 | 22,269,780 | |
| 11/15/14 | 11:00 | 14:45 | 3:45 | 22,270.23 | 22,327.83 | 57,600 | 22,327,380 | |
| 11/16/14 | 10:00 | 14:00 | 4:00 | 22,327.83 | 22,387.57 | 59,740 | 22,387,120 | |
| 11/17/14 | 9:00 | 16:00 | 7:00 | 22,387.57 | 22,488.01 | 100,440 | 22,487,560 | |
| 11/18/14 | 8:00 | 15:30 | 7:30 | 22,488.01 | 22,568.74 | 80,730 | 22,568,290 | |
| 11/19/14 | 8:00 | 15:30 | 7:30 | 22,568.74 | 22,653.22 | 84,480 | 22,652,770 | |
| 11/20/14 | 7:30 | 12:30 | 5:00 | 22,653.22 | 22,692.55 | 39,330 | 22,692,100 | |
| 11/21/14 | 8:00 | 16:00 | 8:00 | 22,692.55 | 22,747.08 | 54,530 | 22,746,630 | |
| 11/22/14 | 8:00 | 12:00 | 4:00 | 22,747.08 | 22,783.08 | 36,000 | 22,782,630 | |
| 11/24/14 | 7:00 | 15:30 | 8:30 | 22,783.08 | 22,833.40 | 50,320 | 22,832,950 | |
| 11/26/14 | 7:30 | 15:00 | 7:30 | 22,833.40 | 22,889.40 | 56,000 | 22,888,950 | |
| 11/28/14 | 11:00 | 16:00 | 5:00 | 22,889.40 | 22,984.22 | 94,820 | 22,983,770 | |
| 11/30/14 | 14:00 | 16:20 | 2:20 | 22,984.22 | 23,021.47 | 37,250 | 23,021,020 | |
| 12/01/14 | 8:30 | 14:30 | 6:00 | 23,021.47 | 23,125.75 | 104,280 | 23,125,300 | |
| 12/02/14 | 7:00 | 15:00 | 8:00 | 23,125.75 | 23,223.33 | 97,580 | 23,222,880 | PVSC Compliance Sample Collected |
| 12/03/14 | 7:30 | 15:00 | 7:30 | 23,223.33 | 23,306.88 | 83,550 | 23,306,430 | |
| 12/04/14 | 7:30 | 15:15 | 7:45 | 23,306.88 | 23,418.88 | 112,000 | 23,418,430 | |
| 12/05/14 | 7:30 | 15:00 | 7:30 | 23,418.88 | 23,505.57 | 86,690 | 23,505,120 | |
| 12/06/14 | 12:30 | 16:30 | 4:00 | 23,505.57 | 23,547.36 | 41,790 | 23,546,910 | |
| 12/08/14 | 6:30 | 16:45 | 10:15 | 23,547.36 | 23,734.14 | 186,780 | 23,733,690 | |
| 12/09/14 | 7:00 | 17:00 | 10:00 | 23,734.14 | 23,938.58 | 204,440 | 23,938,130 | |
| 12/10/14 | 6:30 | 15:30 | 9:00 | 23,938.58 | 24,127.10 | 188,520 | 24,126,650 | |
| 12/11/14 | 7:00 | 15:00 | 8:00 | 24,127.10 | 24,278.59 | 151,490 | 24,278,140 | |
| 12/12/14 | 7:00 | 14:30 | 7:30 | 24,278.59 | 24,400.95 | 122,360 | 24,400,500 | |
| 12/13/14 | 7:00 | 14:00 | 7:00 | 24,400.95 | 24,465.38 | 64,430 | 24,464,930 | |
| 12/15/14 | 7:00 | 15:30 | 8:30 | 24,465.38 | 24,642.32 | 176,940 | 24,641,870 | |
| 12/16/14 | 7:00 | 16:00 | 9:00 | 24,642.32 | 24,790.34 | 148,020 | 24,789,890 | |
| 12/17/14 | 7:00 | 15:00 | 8:00 | 24,790.34 | 24,891.32 | 100,980 | 24,890,870 | |
| 12/18/14 | 7:00 | 14:30 | 7:30 | 24,891.32 | 24,942.66 | 51,340 | 24,942,210 | |
| 12/19/14 | 7:00 | 14:30 | 7:30 | 24,942.66 | 24,984.39 | 41,730 | 24,983,940 | |
| 12/22/14 | 7:00 | 15:00 | 8:00 | 24,984.39 | 25,135.32 | 150,930 | 25,134,870 | |
| 12/23/14 | 8:00 | 15:45 | 7:45 | 25,135.32 | 25,225.78 | 90,460 | 25,225,330 | |
| 12/24/14 | 7:00 | 14:00 | 7:00 | 25,225.78 | 25,261.74 | 35,960 | 25,261,290 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
**Material Tracking and Sampling Log**

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| Site 163 | >1000 | 163-122-1000-a | 850 | 163-122-1000-a1 | 11/18/2014 | 11:00 | 4.5 | | * | |
| | | | | 163-122-1000-a2 | 11/12/2014 | 14:05 | 4 | | * | |
| | | | | 163-122-1000-a3 | 11/18/2014 | 11:05 | 80.1 | | * | |
| | | | | 163-122-1000-a4 | 11/12/2014 | 14:15 | 38.1 | | * | |
| 103-106 | <20 | 124-106-20-a (A29) | 950 | 124-106-20-a1 | 11/21/2014 | 7:55 | 9.2 | Yes | | |
| | | | | 124-106-20-a2 | 11/21/2014 | 8:00 | 12.1 | Yes | | |
| | | | | 124-106-20-a3 | 11/21/2014 | 8:05 | 15.6 | Yes | | |
| | | | | 124-106-20-a4 | 11/21/2014 | 8:10 | 20 | | * | |
| 106-110 | <20 | 124-110-20-a,b,c (A30) | 2400 | 124-110-20-a1 | 12/2/2014 | 13:00 | 25 | | * | |
| | | | | 124-110-20-a2 | 12/2/2014 | 13:05 | 44 | | * | |
| | | | | 124-110-20-a3 | 12/2/2014 | 13:10 | 29.1 | | * | |
| | | | | 124-110-20-a4 | 12/2/2014 | 13:15 | 14.8 | Yes | | |
| | | | | 124-110-20-b1 | 12/2/2014 | 13:20 | 23.1 | | * | |
| | | | | 124-110-20-b2 | 12/2/2014 | 13:25 | 12.9 | Yes | | |
| | | | | 124-110-20-b3 | 12/2/2014 | 13:30 | 3 | Yes | | |
| | | | | 124-110-20-b4 | 12/2/2014 | 13:35 | 1.8 | Yes | | |
| | | | | 124-110-20-c1 | 12/2/2014 | 13:40 | 12.9 | Yes | | |
| | | | | 124-110-20-c2 | 12/2/2014 | 13:45 | 15.6 | Yes | | |
| | | | | 124-110-20-c3 | 12/2/2014 | 13:50 | 29.1 | | * | |
| | | | | 124-110-20-c4 | 12/2/2014 | 13:55 | 179 | | * | |
| 110-114 | <20 | 124-114-20-a (A31) | 1000 | 124-114-20-a1 | 12/16/2014 | 10:40 | 29.8 | | * | |
| | | | | 124-114-20-a2 | 12/16/2014 | 10:45 | 34.5 | | * | |
| | | | | 124-114-20-a3 | 12/16/2014 | 10:50 | 49.3 | | * | |
| | | | | 124-114-20-a4 | 12/16/2014 | 10:55 | 19.9 | Yes | | |
| Site 41 | <20 | 124-114-20-b | 135 | 124-114-20-b1 | 12/16/2014 | 11:00 | 10.6 | Yes | | |
| 110-114 | >1,000 | 124-114-1000-a (East D 6) | 625 | 124-114-1000-a1 | 12/16/2014 | 13:15 | 42.3 | | Yes | |
| | | | | 124-114-1000-a2 | 12/16/2014 | 13:20 | 65 | | Yes | |
| | | | | 124-114-1000-a3 | 12/16/2014 | 13:25 | 75.3 | | Yes | |
| | | | | 124-114-1000-a4 | 12/16/2014 | 13:30 | 16.5 | | Yes | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

# Attachment 7: Perimeter Pools Update




LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE

100' 50' 0 100' 200'

IN PROGRESS
10-02-2014

STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




*Temporary rise in water levels was identified to be associated with pumping issue that has been corrected.*

**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | | | | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | | | | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | | | | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | | | | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO, North FS-4

# Attachment 8: Groundwater Quality Data Surcharge Monitoring Update

- Summary of Groundwater Quality Data from GWET Wells
- Quarterly Water Wells
- Trichloroethene/Chloroform/Hexavalent Chromium in GWET Wells

**Table 1**
Summary of Groundwater Quality Data from GWET Wells

Honeywell

| Parameter | 1-Apr-14 | | | 28-May-14 | | | 9-Sep-14 | | | 18-Dec-14 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 2.9 | 4.0 | ND | 3.4 | 4.7 | ND | 3.7 | 4.7 | ND | 3.2 | 4.0 | ND |
| Carbon Tetrachloride | 4.4J | 2.8 | 1.9 | 7.0 | 4.3 | 2.7 | 7.3 | 4.8 | 3.0 | 5.2 | 4.2 | 2.9 |
| Chloroform | 26.5 | 12.0 | ND | 31.3 | 14.0 | 0.25J | 28.1 | 11.3 | ND | 25.8 | 9.4 | ND |
| 1,1-Dichloroethene | 0.42J | ND | ND | 0.77J | ND | ND | 0.62J | ND | ND | 0.57 | ND | ND |
| cis-1,2-Dichloroethene | 96 | 8.1 | ND | 144 | ND | ND | 128 | 9.6 | ND | 112 | 8.6 | ND |
| trans-1,2-Dichloroethene | 3.4 | ND | ND | 5.3 | ND | ND | 4.5 | ND | ND | 3.5 | ND | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 91.3 | 43.4 | ND | 119 | 54.8 | ND | 123 | 57.4 | ND | 97 | 44.4 | ND |
| 1,1-Dichloroethane | 0.45J | ND | ND | 0.61J | ND | ND | 0.55J | ND | ND | 0.46 | ND | ND |
| Methylene chloride | 0.77J | ND | ND | 0.92J | ND | ND | 0.74J | ND | ND | 0.77 | 0.20 | ND |
| Vinyl chloride | 13.5 | 2.7 | ND | 21.2 | 3.8 | ND | 25.2 | 3.8 | ND | 15.4 | 2.5 | ND |
| 1,2-Dichlorobenzene | 0.72J | ND | ND | 0.70J | ND | ND | 0.82J | ND | ND | 0.66 | ND | ND |
| Chlorobenzene | 0.38J | ND | ND | 0.40J | ND | ND | 0.42J | ND | ND | 0.37 | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 33,400 | 12,500 | 15,100 | 34,700 | 12,700 | 19,700 | 34,200 | 11,100 | 15,700 | 35,900 | 12,200 | 15,900 |
| Total Chromium | 36,900 | 16,400 | 16,600 | 35,500 | 14,500 | 19,600 | 37,600 | 19,300 | 17,900 | 34,100 | 12,700 | 15,900 |

NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.


Note:
Starting with 1st quarter 2014, well 115-MW-215BR is being pumped and sampled.


**TABLE 2**
**Quarterly Water Levels**
**December 2014**

Honeywell


| Wells<br>Date: December 15, 2014 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments |
|---|---|---|---|---|
| 087-MW-25D | 18.17 | 17.32 | 0.85 | GW Elevations are not corrected for tidal influence |
| 087-MW-25T | 18.19 | 17.37 | 0.82 | |
| 087-MW-35 | 18.29 | 17.37 | 0.92 | |
| 087-OBS-1D | 15.13 | 14.19 | 0.94 | |
| 087-OBS-1L | 15.27 | 13.68 | 1.59 | |
| 087-OBS-1T | 15.23 | 14.40 | 0.83 | |
| 087-PW-2 | 13.02 | 33.97 | -20.95 | |
| 087-MW-08 | 12.98 | 12.14 | 0.84 | |
| 087-OBS-3L | 12.88 | 13.15 | -0.27 | |
| 087-MW-13 | 12.93 | 12.92 | 0.01 | |
| 087-OBS-5D | 12.72 | 12.33 | 0.39 | |
| 087-OBS-5T | 12.62 | 12.96 | -0.34 | |
| 087-PW-1 | 12.66 | 35.64 | -22.98 | |
| 087-MW-34 | 12.73 | 13.51 | -0.78 | |
| 087-OBS-2D | 12.68 | 14.68 | -2.00 | |
| SA6-MW-AA1D | 19.36 | 18.73 | 0.63 | |
| SA6-MW-AA1T | 15.31 | 14.58 | 0.73 | |
| SA6-MW-5BR-1 | 17.06 | NA | NA | Well not accessible |
| 087-OBS-4T | 11.6 | 10.83 | 0.77 | |
| 087-MW-O29D | 10.32 | 8.75 | 1.57 | |
| 087-MW-O29T | 9.98 | 8.32 | 1.66 | |
| 087-MW-03 | 13.77 | NA | N/A | Well not accessible |
| 087-MW-02 | 12.57 | NA | N/A | |
| 115-MW-203BR* | 8.7 | NA | N/A* | Well not accessible |
| 073-MW-1BR-1 | 7.58 | 27.03 | N/A* | |
| 073-MW-10BR-1 | 6.67 | 5.14 | 1.53 | |
| 115-MW-215BR* | 8.82 | 12.77 | N/A* | |

* Reference point elevation to be confirmed.




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR





Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

- Hydraulic Barrier Wall Plan & Profile
- Sheet Pile Angle Grout Log




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 1+54 | -3 | AZ 19-700 |
| STRUCTURAL | 1+54 | 5+00 | -19 | AZ 19-700 |
| STRUCTURAL | 5+00 | 12+60 | -22 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

STEPHEN H. MITCHELL 5/14/13
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | ISSUED FOR CONSTRUCTION / REVISION | BY | APVD |
|---|---|---|---|---|
| 0 | 06/07/13 | | TDD | SHM |
| DSGN | TDD | DR | CHK | APVD |
| | | RJR | TDD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER PLAN & PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 588 - 2629
NJ Certificate of Authorization Number 24GA28013900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-201 |
| SHEET | 53 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Can Design-SA6-C3D\CAD\SA6SICR51-S-201 Hydraulic Barrier Wall Pass Profile.dwg PLOT DATE: Wed 22 May 2013 PLOT TIME: 1:09 PM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 5+00 | 12+60 | -22 | AZ 19-700 |
| STRUCTURAL | 12+60 | 17+80 | -30 | AZ 19-700 |
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |




NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL 5/21/13
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | TDD | RJR | TDD | TDD | SHM |

ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHERE THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


HYDRAULIC BARRIER
PLAN & PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2333
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-202 |
| SHEET | 54 OF 66 |

FILE NAME: J:\Projects\HONEYWELL\JERSEY CITY\Civil Design\SA6-7\3D\CAD\SA6SCR54-S-202 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Wed, 22 May 2013 PLOT TIME: 2:57 PM




BEFORE DRIVING SHEETS





SHEET SEALING DETAIL
NTS
BF
TYP S-203

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 17+80 | 19+00 | -9 | AZ 19-700 |
| STRUCTURAL | 19+00 | 21+20 | -19 | AZ 19-700 |
| STRUCTURAL | 21+20 | 23+20 | -15 | AZ 19-700 |
| STRUCTURAL | 23+20 | 24+37 | -12 | AZ 19-700 |
| NON STRUCTURAL | 24+37 | 25+89 | -12 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE




0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

STEPHEN H. MITCHELL
5/24/13
STATE OF NEW JERSEY
NO. 24GE04322400
PROFESSIONAL ENGINEER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | TDD | RJR | TDD | TDD | SHM |

ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN & PROFILE

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28519500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-203 |
| SHEET | 55 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR55-S-203 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Wed, 22 May 2013 PLOT TIME: 3:01 PM

**Amec**

**SA-6 South Grouted Angles** (2")

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 13.2# | 12/1/14 | 191 | 9:08 | 23P1-A |
| | | | | 20P-15 |
| 13.2# | | 192 | 9:56 | 20P-15 |
| | | | | 20P-14 |
| | | | | 20P-13 |
| | | | | 20P-12 |
| | | | | 20P-11 |
| | | | | 20P-10 |
| 13.2# | | 193 | 10:24 | 20P-9 |
| | | | | 20P-8 |
| | | | | 20P-7 |
| | | | | 20P-3 |
| | | | | 20P-2 |
| | | | | 20P-1 |
| | | | | Special 19P E |
| 13.2# | | 194 | 12:50 | Special 19P W |
| | | | | Top off SP19-22Ps |
| | | | | |
| 13.2# | 12/2/14 | 195 | 1:45 | 19P-64 |
| | | | | 19P-63 |
| 19.8# | | 196 | 2:35 | 19P-64 |
| | | | | 19P-63 |
| | | | | 19P-66 |
| | | | | Top off 19P63-22P7 |
| | | | | |
| 13.2# | 12/3/14 | 197 | 9:33 | 19P-53 |
| 13.2# | | 198 | 10:15 | 19P-53 |
| 13.2# | | 199 | 11:05 | 19P-74 |
| 13.2# | | 200 | 1:00 | 19P-74 |
| 21# | (7#B/batch) | 201 | 2:20 | 19P-71 |
| | | | | 19P-74 |
| | | | | 19P-76 |
| | | | | |
| 14# | 12/4/14 | 202 | 9:19 | 19P-75 |
| | (7#B/batch) | | | Top off 71-76 |
| | | | | 19P-77 |
| | | | | 19P-78 |
| 14# | | 203 | 11:20 | 19P-78 |
| | | | | 19P-79 |
| 14# | | 204 | 2:05 | 19P-80 @ 18.5 |
| | | | | 19P-81 |
| | | | | 19P-82 |
| | | | | Top off sheets |
| 14# | 12/5/14 | 205 | 8:10 | 20P-6 |
| | (7#B/batch) | | | 20P-5 |
| 7# | | 206 | 10:17 | 20P-7 |
| 21# | | 207 | 2:40 | 21P1-7 |
| | | | | 21P-13 |

| B | Date | Batch # | Batch Time | Sheetpile ID |
|---|---|---|---|---|
| 14# | 12/8/14 | 208 | 10:35 | 21P-11 |
| 14# | | 209 | 11:10 | 21P-11 |
| 14# | | 210 | 2:12 | 24P-1 |
| | | | | 24P-3 |
| | | | | |
| 13.2# | 12/10/14 | 211 | 8:30 | 24P-11 |
| | | | | 24P-10 |
| | | | | 24P-9 |
| | | | | 24P-8 |
| 19.8# | | 212 | 9:30 | 24P-8 |
| | | | | 24P-7 |
| | | | | 24P-6 |
| | | | | 24P-5 |
| | | | | 24P-4 |
| | | | | 24P-2 |
| | | | | 23P-14 |
| | | | | |
| | | 213 | 1:14 | 21P-3 |
| | | 214 | 2:00 | 21P-3 |
| | | | | |
| 19.8# | 12/11/14 | 215 | 8:15 | 21P-10 |

* No angles were grouted on 12/9/14 23P-14 to 24P-11 were fully jetted



2/2

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 5, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | X | | 2 |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 12/05/14

**SWPPP Observer:** _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, December 05, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing surrounding the LOAM excavation area requires maintenance/repair |
| 2 | IA2Q4A1AL8 | Flood protection barriers (jersey barriers, berms, bin blocks) are not either not present or else not staged in locations where they may be required. |
| 3 | IA2Q4A1AL8 | Ponded storm water is present in the bottom of the main excavation on Study Area 6 South and on the surrounding backfill surface. |
| 4 | IA2Q4A1AL8 | Garbage and debris have accumulated along Kellogg Street and at the jughandle. |
| 5 | IA2Q4A1AL8 | Gaps are present in the perimeter fencing by the northeast corner of the sedimentation basin. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Date: 12/05/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the exclusion zone fencing as required. | 12-8-14 RAD |
| 2 | Confirm that sufficient flood control measures are on hand which can be deployed across haul roads in during a flood event. Install/maintain measures wherever practical. | 12-9-14 RAD |
| 3 | Pump the ponded storm water to the Construction Water Treatment plant when conditions permit. | 12-9-14 RAD |
| 4 | Pick up garbage debris along the SA-6/SA-7 road front. | 12-8-14 RAD |
| 5 | Repair gaps in the perimeter fenceline on SA-6 North. | 12-8-14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date 12/09/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 11, 2014

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/11/14

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, December 11, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt Fence along the surcharge area requires repair |
| 2 | IA2Q4A1AL8 | Exclusion zone fencing requires repair at location indicated |
| 3 | IA2Q4A1AL8 | Ponded water present in areas of backfill on SA6 South |
| 4 | EHWG3RTMXR | Silt Fence on the north side of the SA7 raceway requires repair at the locations indicated |
| 5 | EHWG3RTMXR | Wind Screen requires repair at the location adjacent to the JCIA property. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** David Rhose (Signature) **Date:** 12/11/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair silt fence as required. | 12/15/14 RAD |
| 2 | Repair exclusion zone fence at the location indicated on attached drawing. | 12/12/14 RAD |
| 3 | Pump ponded water to the Construction Water Treatment plant when conditions allow. | 12/12/14 RAD |
| 4 | Repair Silt fence at location indicated on attached drawing | 12/15/14 RAD |
| 5 | Repair wind screen at location indicated on attached drawing. | 12/12/14 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** [signature] **Date:** 12/15/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 17, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 4 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 7 |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 8 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/17/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, December 17, 2014**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The haul road on the eastern end of SA-6 South has depressions containing ponded storm water |
| 2 | IA2Q4A1AL8 | Ponded storm water is present in the bottom of the main excavation on Study Area 6 South and on the surrounding backfill surface. |
| 3 | IA2Q4A1AL8 | Bags containing used PPE and numerous used steel drums are present at the east end of the SA-6 South Exclusion Zone. |
| 4 | IA2Q4A1AL8 | The orange Exclusion Zone fencing on the western side of the Sedmentation basin requires maintenance. |
| 5 | IA2Q4A1AL8 | The haul road on the eastern side of the SA-6 North sedimentation basin has depressions containing ponded storm water and mud. |
| 6 | IA2Q4A1AL8 | **Repeat Item:** The silt fence along the southern perimeter of the 1-N/2-N surcharge stockpile area requires maintenance or replacement in two locations. |
| 7 | IA2Q4A1AL8 | Pallets of hydrochloric acid are stacked unevenly in the southern frac tank containment area. |
| 8 | IA2Q4A1AL8 | Sediment has accumulated in the stone to the west of the western haul road on SA-7 |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 12/17/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove the ponded water and either fill the depressions with suitable material or else regrade the area to eliminate the low spots. | ~~12/22/14~~ RAD |
| 2 | Pump the ponded storm water to the Construction Water Treatment plant when conditions permit. | |
| 3 | Relocate the garbage bags of used PPE to the D material stockpile for loadout with the material. Crush and dispose of any drums which are no longer suitable for use on site. | 12/18/14 RAD |
| 4 | Repair or replace the orange EZ fencing as required. | 12/18/14 RAD |
| 5 | Remove the ponded water and either fill the depressions with suitable material or else regrade the area to eliminate the low spots | |
| 6 | Repair or replace the silt fence as required. | 12/18/14 RAD |
| 7 | Stack the pallets in an orderly fashion to prevent toppling or spillage. | 12/18/14 RAD |
| 8 | Remove sediment that has accumulated in the surface stone between the paved haul road and the river bulkhead. Regrade the stone following removal of sediment. | 12/18/14 RAD |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 12/22/14

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 24, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 1 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 2 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 4 |
| Housekeeping | | X | | 5 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | | X | | 7 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/24/14

SWPPP Observer: _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Wednesday, December 24, 2014

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Stockpile areas on the western end of Study Area 6 South require containment berm maintenance |
| 2 | IA2Q4A1AL8 | Material is piled against the containment berm at the eastern end of the SA-6 South Exclusion Zone. |
| 3 | IA2Q4A1AL8 | The haul road on the eastern side of the SA-6 South backfill area has additional depressions containing ponded storm water and mud. |
| 4 | IA2Q4A1AL8 | Storm water is ponded in the floor of the Study Area 6 South excavation. |
| 5 | IA2Q4A1AL8 | Debris and packing materials are present on the ground in the area to the north of Droyer's Cove. |
| 6 | IA2Q4A1AL8 | There is no silt fence installed along the eastern toe of the 2-N surcharge area. |
| 7 | IA2Q4A1AL8 | The swale check dams on the Study Area 7 paved roadway require maintenance. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 12/24/14

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Reinstall or replace geotextile over Jersey barriers where they are used as stockpile containemnt structures; replace plastic sheeting as required on berms. | 12/30/14 RAD |
| 2 | Reconfigure stockpiles so that they do not approach the top of containment berms. | 12/29/14 RAD |
| 3 | Regrade additional sections of the haul road in the Study Area 6 backfill area as required. | 12/31/14 RAD |
| 4 | Pump ponded storm water to the CWTP as necessary to eliminate surface ponds. | 12/29/14 RAD |
| 5 | Pick up packing materials and construction debris from the support zone as required. | 12/29/14 RAD |
| 6 | Install silt fence along the eastern toe of surcharge pile 2-N. Repair/replace other silt fence in the area as required. | 12/30/14 RAD |
| 7 | Repair fabric/stone swale check dams on the SA-7 roadway as required. | 12/31/14 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 12/31/14

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (November 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

December 19, 2014

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the November 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 11 | 01 | 14 | 11 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,575 | 83,081 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.37 | 0.41 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.003 | <0.003 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.0787 | 0.0787 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

## PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

Dec 17, 2014

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 11 | 01 | 14 | 11 | 30 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,297,244 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 22,335,119 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 11/12/2014 | 8.7 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J Morris HR | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE Dec 17, 2014 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | MONTH: November 2014 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 11/1/2014 | Angel Trujillo | 20037875 | 20118808 | 80,933 | 0.080933 | 7.51 | 0.586 | | | | | | | | | 0.40 |
| 11/2/2014 | Angel Trujillo | 20118808 | 20201889 | 83,081 | 0.083081 | 6.92 | 0.586 | | | | | | | | | 0.41 |
| 11/3/2014 | Angel Trujillo | 20201889 | 20277096 | 75,207 | 0.075207 | 6.97 | 0.586 | | | | | | | | | 0.37 |
| 11/4/2014 | Angel Trujillo | 20277096 | 20354215 | 77,119 | 0.077119 | 6.98 | 0.586 | | | | | | | | | 0.38 |
| 11/5/2014 | Angel Trujillo | 20354215 | 20433874 | 79,659 | 0.079659 | 7.00 | 0.586 | | | | | | | | | 0.39 |
| 11/6/2014 | Angel Trujillo | 20433874 | 20510194 | 76,320 | 0.07632 | 7.00 | 0.586 | | | | | | | | | 0.37 |
| 11/7/2014 | Angel Trujillo | 20510194 | 20586889 | 76,695 | 0.076695 | 6.69 | 0.586 | | | | | | | | | 0.37 |
| 11/8/2014 | Angel Trujillo | 20586889 | 20665698 | 78,809 | 0.078809 | 6.98 | 0.586 | | | | | | | | | 0.39 |
| 11/9/2014 | Angel Trujillo | 20665698 | 20738508 | 72,810 | 0.07281 | 6.96 | 0.586 | | | | | | | | | 0.36 |
| 11/10/2014 | Angel Trujillo | 20738508 | 20808861 | 70,353 | 0.070353 | 7.00 | 0.586 | | | | | | | | | 0.34 |
| 11/11/2014 | Angel Trujillo | 20808861 | 20891149 | 82,288 | 0.082288 | 6.95 | 0.586 | | | | | | | | | 0.40 |
| 11/12/2014 | Angel Trujillo | 20891149 | 20967321 | 76,172 | 0.076172 | 7.10 | 0.586 | <5.0 | 8.7 | | <0.010 | <0.003 | <0.010 | <0.0002 | <0.020 | 0.37 |
| 11/13/2014 | Angel Trujillo | 20967321 | 21042784 | 75,463 | 0.075463 | 7.00 | 0.586 | | | | | | | | | 0.37 |
| 11/14/2014 | Angel Trujillo | 21042784 | 21118538 | 75,754 | 0.075754 | 6.97 | 0.586 | | | | | | | | | 0.37 |
| 11/15/2014 | Angel Trujillo | 21118538 | 21199482 | 80,944 | 0.080944 | 7.00 | 0.586 | | | | | | | | | 0.40 |
| 11/16/2014 | Angel Trujillo | 21199482 | 21275229 | 75,747 | 0.075747 | 6.94 | 0.586 | | | | | | | | | 0.37 |
| 11/17/2014 | Angel Trujillo | 21275229 | 21347230 | 72,001 | 0.072001 | 6.96 | 0.586 | | | | | | | | | 0.35 |
| 11/18/2014 | Angel Trujillo | 21347230 | 21426478 | 79,248 | 0.079248 | 6.98 | 0.586 | | | | | | | | | 0.39 |
| 11/19/2014 | Angel Trujillo | 21426478 | 21501857 | 75,379 | 0.075379 | 7.00 | 0.586 | | | | | | | | | 0.37 |
| 11/20/2014 | Angel Trujillo | 21501857 | 21576920 | 75,063 | 0.075063 | 7.02 | 0.586 | | | | | | | | | 0.37 |
| 11/21/2014 | Angel Trujillo | 21576920 | 21656299 | 79,379 | 0.079379 | 6.96 | 0.586 | | | | | | | | | 0.39 |
| 11/22/2014 | Angel Trujillo | 21656299 | 21731024 | 74,725 | 0.074725 | 7.01 | 0.586 | | | | | | | | | 0.37 |
| 11/23/2014 | Angel Trujillo | 21731024 | 21809064 | 78,040 | 0.07804 | 6.94 | 0.586 | | | | | | | | | 0.38 |
| 11/24/2014 | Angel Trujillo | 21809064 | 21883321 | 74,257 | 0.074257 | 6.90 | 0.586 | | | | | | | | | 0.36 |
| 11/25/2014 | Angel Trujillo | 21883321 | 21957929 | 74,608 | 0.074608 | 6.88 | 0.586 | | | | | | | | | 0.36 |
| 11/26/2014 | Angel Trujillo | 21957929 | 22033245 | 75,316 | 0.075316 | 7.09 | 0.586 | | | | | | | | | 0.37 |
| 11/27/2014 | Angel Trujillo | 22033245 | 22111351 | 78,106 | 0.0781 | 7.06 | 0.586 | | | | | | | | | 0.38 |
| 11/28/2014 | Angel Trujillo | 22111351 | 22186307 | 74,956 | 0.074956 | 7.09 | 0.586 | | | | | | | | | 0.37 |
| 11/29/2014 | Angel Trujillo | 22186307 | 22261895 | 75,588 | 0.075588 | 7.07 | 0.586 | | | | | | | | | 0.37 |
| 11/30/2014 | Angel Trujillo | 22261895 | 22335119 | 73,224 | 0.073224 | 7.10 | 0.586 | | | | | | | | | 0.36 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,297,244 | 2.297244 | | | <5.0 | 8.7 | | <0.010 | <0.003 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 83,081 | | | | | | | | | | | High: | 0.41 |
| | | | Average: | 76,575 | | | | | | | | | | | Average: | 0.37 |

Accutest LabLink@827964 11:50 03-Dec-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111214-A | | |
| **Lab Sample ID:** | JB81602-1 | **Date Sampled:** | 11/12/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 586 | 10 | ug/l | 1 | 11/14/14 | 11/15/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 11/14/14 | 11/15/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead | < 3.0 | 3.0 | ug/l | 1 | 11/14/14 | 11/15/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 11/13/14 | 11/13/14 | DP | EPA 245.1 [1] | EPA 245.1 [3] |
| Nickel | < 10 | 10 | ug/l | 1 | 11/14/14 | 11/15/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 11/14/14 | 11/15/14 | ND | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA35416
(2) Instrument QC Batch: MA35425
(3) Prep QC Batch: MP83238
(4) Prep QC Batch: MP83265

RL = Reporting Limit

Accutest LabLink@827964 11:50 03-Dec-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111214-A | | |
| **Lab Sample ID:** | JB81602-1 | **Date Sampled:** | 11/12/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 11/13/14 | KP | SM2540 D-11 |
| pH [a] | 6.88 | | su | 1 | 11/12/14 19:02 | AR | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@827964 11:50 03-Dec-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111214-A | | |
| **Lab Sample ID:** | JB81602-1A | **Date Sampled:** | 11/12/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 8.7 | 5.0 | mg/l | 1 | 11/12/14 21:46 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@827964 11:50 03-Dec-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111214-B | | |
| **Lab Sample ID:** | JB81602-2 | **Date Sampled:** | 11/12/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/14 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N241119.D | 1 | 11/14/14 | DC | n/a | n/a | VN10228 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA PPL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 71-43-2 | Benzene | 2.5 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.5 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.24 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 67-66-3 | Chloroform | 19.0 | 1.0 | 0.14 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.1 | 1.0 | 0.24 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.16 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-09-2 | Methylene chloride | 0.58 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 48.8 | 1.0 | 0.17 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 97% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 101% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 98% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 99% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@827964 11:50 03-Dec-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111214-B | | |
| **Lab Sample ID:** | JB81602-2 | **Date Sampled:** | 11/12/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 11/14/14 | LS | EPA 1664A |

RL = Reporting Limit

WW

E

JB81602

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 41965.44379 |
|---|---|---|---|---|
| 2236 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County / Phase: CS | COC# | 087-WW-111214 |
| Sampling Co.: Parsons | EDD To: | Location of Site: Jersey City, NJ / Sampling Program: 087: JCIA | Lab Proj # (SDG): | |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | Lab ID | ACTD |
| Helen Fahy P (973) 455-2989 E helen.fahy@honeywell.com | PO # | Preservative: 3 | Site ID | HudsonCo |
| Honeywell International<br>101 Columbia Road Morristown, NJ 07962 | Analysis Turnaround Time (TAT): 3<br>Consultant: CH2M | | Lab Job # | HWINJM32815 |
| Preliminary Data To | | | Authorized User: | Honeywell |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | Text & Excel File Drive | Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E408.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | Units | | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-111214-A | 11/12/2014 | 14:20 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | L28 |
| 2 | 087-WW | | | 087-WWE-111214-B | 11/12/2014 | 14:30 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | V292 |
| 3 | 087-WW | | | 087-WWI-111214 | 11/12/2014 | 14:50 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | All |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | GS |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

LES RECEIVED
PRESERVED AS APPLICABLE

| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact |
|---|---|---|---|---|---|
| Frank Schroyer pH=7.10@6.8° C | Parsons | | | | |
| | Date/Time 11/12/14 | Date/Time 11-12-14 1430 | | Cooler Temp. | |
| Relinquished by | Company | Received by | Company A.L.N.T | Condition | Custody Seals Intact |
| | Date/Time 11.12.14 18:10 | | Date/Time 11/12 1810 | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

JM

I 34C

1B/a

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending December 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal to Parties' per request. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**2/12/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

February 12, 2015 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
c/o Kate Farley, Rosemont Associates
73 Kingwood Stockton Road
Stockton,NJ 08559

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-01**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from January 1 – January 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: January 2015 SA-6/7 Combined Monthly Progress Report No. 2015-01

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-01

**Project SA-6 & 7 Remediation**

## January 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 01/05/15 | Surcharge Monitoring Plan – Monthly Report No. 7<br>Study Area 6 North and South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/07/15 | Surcharge Monitoring Plan – Monthly Report No. 8<br>Study Area 6 North and South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/14/15 | Combined Monthly Progress/Highlights Report No. 2014-12<br>Study Areas 6 and 7<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/19/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 01/20/15 | Special Master Conference Call | N/A |
| 01/23/15 | Underground Storage Tank<br>Remedial Action Report<br>100 Kellogg Street<br>Block 24601/Lots 3 and 4<br>NJDEP Case No. 14-08-05-0956-44<br>Study Area 6 South - Site 134<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/28/15 | Design Change Bulletin<br>Study Area 6 South - Site 163 Shallow Excavation<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/04/15 | 01/11/15 | 01/18/15 | 01/25/15 | 02/01/15 |
| Construction Management (AMEC) | 8 | 10 | 11 | 11 | 9 |
| Engineering (AMEC) | 1 | 1 | 1 | 1 | 0 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 | 1 |
| Security (Securitas) | 2 | 2 | 2 | 2 | 2 |
| Entact/Subcontractors | 30 | 29 | 26 | 23 | 29 |
| Arecon/US Ecology Subcontractors | 0 | 0 | 0 | 1 | 1 |
| Evoqua | 1 | 1 | 1 | 1 | 1 |
| HBS (SA-6N GWTP Security System) | 0 | 0 | 0 | 0 | 0 |
| Gramercy | 7 | 6 | 8 | 10 | 11 |
| **TOTAL STAFF** | **50** | **50** | **50** | **50** | **54** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected January PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed protection of JCIA incinerator building trash pit.
- On January 5, 2015, began demolition and load out of the JCIA structures.
- Fence contractor installed new fence and gate posts at entrance to the Department of Public Works (DPW).
- Received confirmation from New Jersey Department of Transportation (NJDOT) that the Drainage Permit at SA-6 North is no longer needed.
- On December 8, 2014 a leaking diesel line was identified on a water truck. Sampling of the impacted soil was performed and laboratory analysis received on January 5, 2015 indicated the result was Non-Hazardous. On January 15, 2015 the surficial soil was transported off site to non-hazardous disposal facility.

- On January 21, 2015, meeting was held with representatives of the City of Jersey City and DPW to review progress of the remaining relocation activities.
- On February 10, submitted Year 1 Implementation Report for Study Area 7 Sediment Remedy Long-term Monitoring Program.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on January 16. 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/04/15 | 01/11/15 | 01/18/15 | 01/25/15 | 02/01/15 |
| Avg. Gallons Treated & Discharged (per day) | 76,532 | 75,901 | 75,971 | 75,238 | 76,089 |
| Average Flow (gpm) for Operating Period | 56 | 53 | 53 | 53 | 53 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 11,840 | 6,556 | 8,173 | 10,308 | 6,256 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart, Weekly Excavation and Survey Data, Backfill Compaction Locations, and Field Density Test Summary Log)*

- Continued storm-water management activities.
- Completed excavation of locations designated as Site 163-1, Area 42 and Area 43.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/ FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 17.31 | 17.31 |
| **Gramercy/ Horwith *** | 40 Cyd Roll off | Newburg, PA | Cumberland County Landfill | Friable ACM | 2 | 3.61 | 7.23 |
| **Gramercy- (JCIA Demo)** | 20 cyd rol off | Jersey City, NJ | Sims Metal | Aluminum | 1 | 1.4 | 1.4 |
| **Gramercy- (JCIA Demo)** | 40 Cyd Roll off | Jersey City, NJ | Sims Metal | Metal | 41 | 9.4 | 386.1 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Gramercy- (JCIA Demo)** | 40 Cyd Roll off | North Bergen, NJ | Cardella Waste | C&D | 14 | 12.5 | 175.2 |
| **Gramercy- (JCIA Demo)** | 30 cyd roll off | Bayonne, NJ | Durable Recycling | Concrete | 57 | 14.1 | 803.4 |
| **Gramercy- (JCIA Demo)** | 40 Cyd Roll off | Bayonne, NJ | Durable Recycling | Brick/Masonry | 2 | 18.3 | 36.5 |
| **Entact/ Arecon** | Tri-axle Dump | South Brunswick, NJ | MCUA | Petroleum Impacted Soil | 121 | 25.1 | 3,045.50 |
| **Entact/ Arecon** | Tri-axle Dump | South Brunswick, NJ | MCUA | Diesel Impacted Soil | 2 | 14 | 28 |

** December 2014 Transport*

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Anomalous Material near Site 163-1, Area 42, Area 43 |
| **Backfill in Progress** | No backfill occurred during the reporting period |

### 3. BACKFILL MATERIALS USED

No backfill occurred and dropping table this month.

## E. SURCHARGE OPERATIONS

- Area 1S: Continue offloading Celgene material from 1S and relocating to 2S approximately 80% complete.
- Area 2S: Surcharging continued on Area 2S. Surcharge placement consisted of both chromium impacted soils to the design sub-grade and both imported Celgene and Novartis soils. Surcharge placement is approximately 95% complete.
- Area 3S: Surcharge placement continued on Area 3S and is approximately 60% complete.
- Area 1N: Continued surcharge removal activities. Surcharge removal activities are approximately 85% complete. Details will be provided in the January 2015 Surcharge Monitoring Report No. 10.
- Area 2N: Surcharge placement is 100% complete. Monitoring data (provided in Surcharge Monitoring Report No. 7) indicates that surcharge has attained the goals per the 100% Design and may be removed.
- Area 3N: No activity in this area pending JCIA Demolition.
- Area 4N: No activity in this area pending JCIA Demolition.

- Active Monitoring for Surcharge is currently limited to Areas 2S and 3S. The combination of snow and temperatures are preventing personnel from taking readings at many locations in these areas at the frequency stated in the Surcharge Monitoring Plan Monitoring will resume at all points when it is feasible and safe to do so.

## F. SHEET PILE OPERATIONS

- Excavation proximate to the SA-6 South barrier wall was completed on October 28, 2014 and backfill has been progressed in all areas against the SA-6 South barrier wall. Deflection readings are therefore no longer required.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue JCIA Structures Demolition and load out activities.
- Continue placement of surcharge materials in SA-6 South Area 2S and Area 3S.
- Continue loadout and transportation and disposal activities at SA-6 South.
- Continue accepting delivery of steel sheetpile for remaining SA-6 North Barrier Wall installation.
- Conduct well development of injection well 088-IW-01 on SA-6 North.
- Conduct well development of GWET extraction well PW-2.
- Conduct acid cleaning of the PW-2 force main.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Obtain NJDOT Highway Occupancy Permit for upcoming SA-6 North activities proximate to Rt. 440 frontage.
- Continue the SA-6 North Bench-Scale treatability study for Treatment Area 10 proximate to force main.
- Continue to coordinate with the JCDPW on their off-site relocation of remaining equipment from SA-6 North.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
   - Excavation Bottom Elevations
   - Maser Survey Tables: SA-6 South Excavation: Confirmatory Points
   - Figure 2: Color Coded Excavation Bottom
   - Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
   - Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)
4. Dewatering Operations Update
   - SA-6 South Deep Well Data (DW-4)
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
   - Stockpiled Material Tracking and Sampling Log
7. Perimeter Pools Update
8. *Groundwater Quality Data (sampled quarterly, not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. *Sheet Pile Update (not included in this reporting period)*
11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (December 2014)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** |
| 67a | Restoration | 164 days | Tue 9/1/15 |




Project: SA-6 Remediation Schedule
Revision 3
Date: Tue 2/3/15

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs



**Site Photograph 1:** Contractor grades surcharge material after placement.




**Site Photograph 2:** Contractor loads out soils for off-site disposal.



**Site Photograph 3:** Contractor loads out surcharge material.




**Site Photograph 4:** Contractor removes surcharge material.



**Photograph 5:** JCIA Demo loading scrap steel.




**Site Photograph 6:** JCIA Demo sorting steel and masonry.

# Attachment 3: Excavation and Backfill

- Progression Chart
- Excavation Bottom Elevations
- Maser Survey Tables: SA-6 South Excavation: Confirmatory Points
- Figure 2: Color Coded Excavation Bottom
- Field Density Test Summary Log (Every 2,500SF/5 Tests per Acre)
- Backfill Compaction Locations (Every 2,500SF/5 Tests per Acre)

# Jersey City & Kellogg Street Properties Remedies
# Progress as of February 1, 2015

January 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill




## Legend


- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete




LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM D EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- AREA DEFERRED TO PRESERVE BULKHEAD
- LIMIT OF EXCAVATION AREA
- TOP OF EXCAVATION SLOPE

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS Area 42 & 163-1
PERIOD 12-10-14 TO 12-22-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South Excavation (Site 163): Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685185.6 | 601432.8 | 5.8 | 163-SB-107 | N/A | 10/30/2014 | 5.0 | Area 43 - Target Elevation Reached |
| 685169.6 | 601446.1 | 6.0 | 163-SB-020 | N/A | 10/30/2014 | 4.8 | Area 43 - Target Elevation Reached |
| 685102.9 | 601588.4 | 5.2 | 163-SB-015 | N/A | 10/30/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685125.0 | 601586.5 | 6.3 | 163-SB-043 | N/A | 10/30/2014 | 5.7 | Area 163 - Target Elevation Reached |
| 685037.6 | 601660.2 | 4.5 | 163-SB-010 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685029.9 | 601632.6 | 5.2 | 163-SB-013 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685028.1 | 601625.3 | 6.8 | 163-SB-064 | N/A | 11/5/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 685064.3 | 601635.5 | 4.9 | 163-SB-112 | N/A | 11/5/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685069.7 | 601654.2 | 5.0 | 163-SB-011 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685054.7 | 601600.3 | 3.6 | 163-SB-063 | N/A | 10/31/2014 | 3.5 | Area 163 - Target Elevation Reached |
| 685062.5 | 601603.2 | 4.6 | 163-SB-014 | N/A | 10/31/2014 | 3.4 | Area 163 - Target Elevation Reached |
| 685100.1 | 601617.6 | 5.3 | 163-SB-012 | N/A | 10/31/2014 | 3.7 | Area 163 - Target Elevation Reached |
| 684984.0 | 601680.9 | 5.5 | 163-SB-113 | N/A | 11/7/2014 | 5.0 | Area 163 - Target Elevation Reached |
| 684997.7 | 601696.5 | 5.5 | 163-SB-093 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685012.8 | 601711.3 | 5.6 | 163-SB-092 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685001.4 | 601739.4 | 6.6 | 163-SB-086 | N/A | 11/7/2014 | 4.8 | Area 163 - Target Elevation Reached |
| 684854.7 | 601827.8 | 5.7 | 163-SB-008 | N/A | 11/12/2014 | 5.1 | Area 163 - Target Elevation Reached |
| 684889.4 | 601833.1 | 6.2 | 163-SB-072 | N/A | 11/12/2014 | 4.7 | Area 163 - Target Elevation Reached |
| 684901.6 | 601758.2 | 7.6 | 163-SB-085 | N/A | 11/12/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 684913.3 | 601758.5 | 5.7 | 163-SB-009 | N/A | 11/12/2014 | 5.1 | Area 163 - Target Elevation Reached |
| 684943.7 | 601757.2 | 5.9 | 163-SB-073 | N/A | 11/12/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684970.6 | 601767.7 | 3.3 | 163-SB-007 | N/A | 11/12/2014 | 3.1 | Area 163 - Target Elevation Reached |
| 684970.3 | 601782.2 | 3.3 | 163-SB-060 | N/A | 11/12/2014 | 2.6 | Area 163 - Target Elevation Reached |
| 684784.2 | 602004.7 | 4.9 | 134-SB-114 | N/A | 12/12/2014 | 4.0 | Area 42 - Target Elevation Reached |
| 684779.6 | 601989.9 | 4.8 | 134-SB-003 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |
| 684756.5 | 602015.6 | 5.8 | 134-SB-108 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Target Reached. Over excavation conducted as directed by engineer.

## SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0)

| Sidewall Target Coordinates | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| 685197.1 | 601418.1 | 5.2 | 163-SB-097 | N/A | 10/30/2014 | 5.0 | Area 43 - Target Elevation Reached |
| 685181.4 | 601455.3 | 6.0 | 163-SB-035 | N/A | 10/30/2014 | 5.1 | Area 43 - Target Elevation Reached |
| 685158.1 | 601437.3 | 7.0 | 163-SB-061 | N/A | 10/30/2014 | 8.9 | Area 43 - deferred to preserve Bulk Head |
| 685160.1 | 601457.8 | 7.5 | 163-SB-036 | N/A | 10/30/2014 | 4.6 | Area 43 - Target Elevation Reached |
| 685026.9 | 601624.6 | 7.8 | 163-SB-076 | N/A | 11/5/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 685045.9 | 601596.1 | 7.9 | 163-SB-077 | N/A | 10/31/2014 | 3.2 | Area 163 - Target Elevation Reached |
| 685072.2 | 601547.5 | 7.1 | 163-SB-062 | N/A | 10/30/2014 | 3.6 | Area 163 - Target Elevation Reached |
| 684993.2 | 601662.1 | 6.4 | 163-SB-100 | N/A | 11/7/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 684961.1 | 601691.9 | 7.3 | 163-SB-113 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684871.6 | 601791.8 | 5.6 | 163-SB-066 | N/A | 11/12/2014 | 7.2 | Area deferred to preserve Bulk Head |
| 684893.3 | 601758.8 | 5.6 | 163-SB-085 | N/A | 11/12/2014 | 4.8 | Area 163 - Target Elevation Reached |
| 684929.4 | 601730.4 | 5.2 | 163-SB-084 | N/A | 11/12/2014 | 5.0 | Area 163 - Target Elevation Reached |
| 684891.6 | 601853.5 | 6.9 | 163-SB-051 | N/A | 11/12/2014 | 4.5 | Area 163 - Target Elevation Reached |
| 684852.1 | 601829.3 | 5.6 | 163-SB-052 | N/A | 11/12/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684843.0 | 601829.0 | 5.6 | 163-SB-067 | N/A | 11/12/2014 | 6.8 | Area 163 (deferred to preserve Bulk Head) |
| 684797.0 | 601966.1 | 5.7 | 134-SB-069 | N/A | 12/12/2014 | 4.1 | Area 42 - Target Elevation Reached |
| 684807.5 | 602016.1 | 5.9 | 134-SB-146 | N/A | 12/12/2014 | 4.1 | Area 42 - Target Elevation Reached |
| 684750.1 | 602027.2 | 6.4 | 134-SB-091 | N/A | 12/12/2014 | 4.5 | Area 42 - Target Elevation Reached |
| 684747.0 | 601998.4 | 6.0 | 134-SB-058 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |
| 684751.6 | 601971.2 | 5.6 | 134-SB-071 | N/A | 12/12/2014 | 4.2 | Area 42 - Target Elevation Reached |
| 685138.0 | 601563.6 | 6.2 | 163-SB-078 | N/A | 12/22/2014 | 4.7 | Area 163-1 - Target Elevation reached |
| 685083.7 | 601558.5 | 6.0 | 163-SB-017 | N/A | 12/22/2014 | 4.3 | Area 163-1 - Target Elevation reached |
| 685165.5 | 601546.0 | 6.5 | 163-SB-080 | N/A | 12/22/2014 | 5.6 | Area 163-1 - Target Elevation reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 1/7/15

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

NEW JERSEY STATE HIGHWAY ROUTE 440

MATCH LINE SEE BELOW

SOIL RETENTION SYSTEM (TYP)

KELLOGG STREET

HACKENSACK RIVER

CAP AREA (TYP)

EXISTING BULKHEAD (TYP)

MATCH LINE SEE ABOVE

LIMIT OF LOAM EXCAVATION BOT EXC TO STRATUM D

BOT OF EXC AREA 163 VARIES 6.00 TO 3.30

BOT OF EXC AREA 163-1 VARIES 6.00 TO 5.50

- EXCAVATION BOTTOM ELEVATION 5.7
- EXCAVATION BOTTOM ELEVATION 4.2
- EXCAVATION BOTTOM ELEVATION 2.1
- EXCAVATION BOTTOM ELEVATION 0.4
- EXCAVATION BOTTOM ELEVATION (1.2)
- EXCAVATION BOTTOM ELEVATION (2.5)
- EXCAVATION BOTTOM ELEVATION (4.3)
- EXCAVATION BOTTOM ELEVATION (7.5)
- EXCAVATION BOTTOM ELEVATION (8.4)
- EXCAVATION BOTTOM ELEVATION (8.7)
- EXCAVATION BOTTOM ELEVATION (8.9)
- REVISIONS TO ORIGINAL FIGURE (SEE NOTES 3 THRU 4)

NOTES:

1. CONTOURS ON THIS SHEET REPRESENT BOTTOM OF EXCAVATION.
2. THE APPROVED 100% DESIGN DOCUMENTS OUTLINE CONDITIONS WHERE THE FINAL EXCAVATION BOTTOM MAY BE SHALLOWER IF STRATUM D IS ENCOUNTERED.
3. LENS OF ANOMALOUS MATERIAL VISUALLY IDENTIFIED AND FURTHER DELINEATED THROUGH FIELD SAMPLING HAS BEEN ADDED AND IDENTIFIED AS LOAM AREA.
4. EXCAVATION AREAS 163, 163-1, 42, AND 43 HAVE BEEN ADDED TO THE ORIGINAL COLOR CODED EXCAVATION BOTTOM FIGURE.

Revision/Date: TDD 12/16/14
Checked/Date: SGS 12/16/14

0 25 50 100
SCALE IN FEET

Honeywell
101 COLUMBIA RD, BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

SA-6 SOUTH
COLOR CODED EXCAVATION BOTTOM
FIGURE 2

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |
| 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |
| | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Bridge Lift | V5N |
| 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced with DGA | V5N |
| 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |
| | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DGA | V5N |
| | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 1 Test/2,500 Square Feet
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |
| | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.

Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.


Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again





NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
EVERY 2,500 SF
BF-95 TO BF-136

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 2. a.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 1 | RF-14-2 | 11/5/2014 | 684662.9 | 602542.6 | 0.0 | 134.0 | 0.6 | 135.8 | 6.4 | 99 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-16-2 | 11/5/2014 | 684767.6 | 602428.4 | 1.2 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 67 | Weldon WC Screenings | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-17-2 | 11/5/2014 | 684723.7 | 602387.9 | 1.5 | 124.0 | 3.8 | 128.9 | 12.1 | 96 | 95 | 70 | Weldon WC Screenings | | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| 6 | RF-18-2 | 11/5/2014 | 684636.8 | 602258.1 | 5.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 73 | Weldon WC Screenings | Placed on Type A material | V5N |
| | RF-19 | | 684790.8 | 602339.5 | -2.5 | | | | | | | 75 | Stratum D | Bottom of excavation elevation | |
| 3 | RF-19-1 | 11/5/2014 | 684776.9 | 602328.5 | 1.8 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 75 | Weldon WC Screenings | | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| 4 | RF-21-2 | 11/5/2014 | 684823.4 | 602288.0 | 1.8 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 79 | Tilcon MH DGA | | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| 5 | RF-23-04 | 11/5/2014 | 684877.6 | 602222.8 | 2.5 | 134.0 | 0.7 | 135.8 | 6.4 | 99 | 95 | 85 | Tilcon MH DGA | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| NA | RF-27-LOAM | 12/15/2014 | 685045.9 | 601945.1 | -4.4 | 129.0 | 3.0 | 135.8 | 6.4 | 95 | 95 | 106 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| NA | RF-28-LOAM | 12/15/2014 | 685085.0 | 601862.1 | -4.7 | 135.8 | 4.0 | 135.8 | 6.4 | 100 | 95 | 112 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
Testing Frequency - 5 Tests per Acre
HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 0 | Site 163-2 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-2-1 | 11/5/2014 | 685070.9 | 601614.2 | 6.1 | 122.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| 2 | Site 163-2-2 | 11/14/2014 | 685070.5 | 601616.0 | 7.5 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| | | | | | | | | | | | | | | | |

***Notes:***

Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.

Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.


Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b

Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C

Bottom of excavation elevation based on Maser survey data (Center Point elevations)

Sample ID RF-01-01 where:

RF = Reduced Frequency
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again




NOTE:


Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39, RF-163-01. RF-163-02

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 012315 3.13 A. 3.

Weldon Watchung screenings testing frequency reduced as of 2/11/14.

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 4: Dewatering Operations Update

- SA-6 South Deep Well Data (DW-4)

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-4)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/14/14 | 24 | N/A | N/A | 6,500 | 80,718 | 4.5 | Pump Online for LOAM Excavation |
| 11/17/14 | 72 | N/A | N/A | 19,500 | 100,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/18/14 | 24 | N/A | N/A | 6,500 | 106,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/19/14 | 24 | N/A | N/A | 6,500 | 113,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/20/14 | 24 | N/A | N/A | 6,500 | 119,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/21/14 | 24 | N/A | N/A | 6,500 | 126,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/22/14 | 24 | N/A | N/A | 6,500 | 132,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/24/14 | 48 | N/A | N/A | 13,000 | 145,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/25/14 | 24 | N/A | N/A | 6,500 | 152,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/28/14 | 72 | N/A | N/A | 19,500 | 171,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 11/30/14 | 48 | N/A | N/A | 12,500 | 184,218 | 4.3 | Flow Meter Not Installed - Tank Measured |
| 12/01/14 | 24 | N/A | N/A | 6,500 | 190,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 12/02/14 | 24 | N/A | N/A | 6,500 | 197,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 12/03/14 | 24 | N/A | N/A | 6,500 | 203,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 12/4/2014 | 24 | N/A | N/A | 6,500 | 210,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 12/5/2014 | 24 | N/A | N/A | 6,500 | 216,718 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 12/6/2014 | 24 | N/A | N/A | 6,500 | 223,218 | 4.5 | Flow Meter Not Installed - Tank Measured |
| 12/8/2014 | 48 | N/A | N/A | 12,500 | 235,718 | 4.3 | Pump Taken Offline |

# Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 12/01/14 | 8:30 | 14:30 | 6:00 | 23,021.47 | 23,125.75 | 104,280 | 23,125,300 | |
| 12/02/14 | 7:00 | 15:00 | 8:00 | 23,125.75 | 23,223.33 | 97,580 | 23,222,880 | PVSC Compliance Sample Collected |
| 12/03/14 | 7:30 | 15:00 | 7:30 | 23,223.33 | 23,306.88 | 83,550 | 23,306,430 | |
| 12/04/14 | 7:30 | 15:15 | 7:45 | 23,306.88 | 23,418.88 | 112,000 | 23,418,430 | |
| 12/05/14 | 7:30 | 15:00 | 7:30 | 23,418.88 | 23,505.57 | 86,690 | 23,505,120 | |
| 12/06/14 | 12:30 | 16:30 | 4:00 | 23,505.57 | 23,547.36 | 41,790 | 23,546,910 | |
| 12/08/14 | 6:30 | 16:45 | 10:15 | 23,547.36 | 23,734.14 | 186,780 | 23,733,690 | |
| 12/09/14 | 7:00 | 17:00 | 10:00 | 23,734.14 | 23,938.58 | 204,440 | 23,938,130 | |
| 12/10/14 | 6:30 | 15:30 | 9:00 | 23,938.58 | 24,127.10 | 188,520 | 24,126,650 | |
| 12/11/14 | 7:00 | 15:00 | 8:00 | 24,127.10 | 24,278.59 | 151,490 | 24,278,140 | |
| 12/12/14 | 7:00 | 14:30 | 7:30 | 24,278.59 | 24,400.95 | 122,360 | 24,400,500 | |
| 12/13/14 | 7:00 | 14:00 | 7:00 | 24,400.95 | 24,465.38 | 64,430 | 24,464,930 | |
| 12/15/14 | 7:00 | 15:30 | 8:30 | 24,465.38 | 24,642.32 | 176,940 | 24,641,870 | |
| 12/16/14 | 7:00 | 16:00 | 9:00 | 24,642.32 | 24,790.34 | 148,020 | 24,789,890 | |
| 12/17/14 | 7:00 | 15:00 | 8:00 | 24,790.34 | 24,891.32 | 100,980 | 24,890,870 | |
| 12/18/14 | 7:00 | 14:30 | 7:30 | 24,891.32 | 24,942.66 | 51,340 | 24,942,210 | |
| 12/19/14 | 7:00 | 14:30 | 7:30 | 24,942.66 | 24,984.39 | 41,730 | 24,983,940 | |
| 12/22/14 | 7:00 | 15:00 | 8:00 | 24,984.39 | 25,135.32 | 150,930 | 25,134,870 | |
| 12/23/14 | 8:00 | 15:45 | 7:45 | 25,135.32 | 25,225.78 | 90,460 | 25,225,330 | |
| 12/24/14 | 7:00 | 14:00 | 7:00 | 25,225.78 | 25,261.74 | 35,960 | 25,261,290 | |
| 12/29/14 | 7:00 | 16:15 | 9:15 | 25,261.74 | 25,355.68 | 93,940 | 25,355,230 | |
| 12/30/14 | 7:00 | 16:00 | 9:00 | 25,355.68 | 25,472.64 | 116,960 | 25,472,190 | |
| 12/31/14 | 7:00 | 14:00 | 7:00 | 25,472.64 | 25,613.83 | 141,190 | 25,613,380 | |
| 01/02/15 | 7:00 | 14:30 | 7:30 | 25,613.83 | 25,704.93 | 91,100 | 25,704,480 | |
| 01/05/15 | 7:00 | 16:45 | 9:45 | 25,704.93 | 25,803.51 | 98,580 | 25,803,060 | |
| 01/06/15 | 7:00 | 15:15 | 8:15 | 25,803.51 | 25,934.54 | 131,030 | 25,934,090 | |
| 01/07/15 | 7:00 | 15:00 | 8:00 | 25,934.54 | 26,010.92 | 76,380 | 26,010,470 | |
| 01/11/15 | 9:00 | 14:00 | 5:00 | 26,010.92 | 26,076.69 | 65,770 | 26,076,240 | |
| 01/12/15 | 13:30 | 16:00 | 2:30 | 26,076.69 | 26,123.43 | 46,740 | 26,122,980 | |
| 01/13/15 | 13:30 | 16:00 | 2:30 | 26,123.43 | 26,242.94 | 119,510 | 26,242,490 | PVSC Compliance Sample Collected |
| 01/14/15 | 10:15 | 16:00 | 5:45 | 26,242.94 | 26,294.50 | 51,560 | 26,294,050 | |
| 01/15/15 | 7:30 | 15:00 | 7:30 | 26,294.50 | 26,374.46 | 79,960 | 26,374,010 | |
| 01/16/15 | 7:30 | 14:00 | 6:30 | 26,374.46 | 26,431.98 | 57,520 | 26,431,530 | |
| 01/19/15 | 7:00 | 16:00 | 9:00 | 26,431.98 | 26,544.34 | 112,360 | 26,543,890 | |
| 01/20/15 | 7:00 | 16:30 | 9:30 | 26,544.34 | 26,671.53 | 127,190 | 26,671,080 | |
| 01/21/15 | 7:00 | 16:00 | 9:00 | 26,671.53 | 26,795.65 | 124,120 | 26,795,200 | |
| 01/22/15 | 7:00 | 15:30 | 8:30 | 26,795.65 | 26,937.52 | 141,870 | 26,937,070 | |
| 01/23/15 | 7:00 | 15:00 | 8:00 | 26,937.52 | 27,077.78 | 140,260 | 27,077,330 | |
| 01/28/15 | 7:00 | 14:30 | 7:30 | 27,077.78 | 27,127.82 | 50,040 | 27,127,370 | |
| 01/29/15 | 7:00 | 15:00 | 8:00 | 27,127.82 | 27,180.82 | 53,000 | 27,180,370 | |
| 01/30/15 | 7:00 | 14:00 | 7:00 | 27,180.82 | 27,268.67 | 87,850 | 27,268,220 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data


- Stockpiled Material Tracking and Sampling Log

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 106-110 | <20 | 124-110-20-a,b,c (A30) | 2400 | 124-110-20-a1 | 12/2/2014 | 13:00 | 25 | | Yes | |
| | | | | 124-110-20-a2 | 12/2/2014 | 13:05 | 44 | | Yes | |
| | | | | 124-110-20-a3 | 12/2/2014 | 13:10 | 29.1 | | Yes | |
| | | | | 124-110-20-a4 | 12/2/2014 | 13:15 | 14.8 | Yes | | |
| | | | | 124-110-20-b1 | 12/2/2014 | 13:20 | 23.1 | | Yes | |
| | | | | 124-110-20-b2 | 12/2/2014 | 13:25 | 12.9 | Yes | | |
| | | | | 124-110-20-b3 | 12/2/2014 | 13:30 | 3 | Yes | | |
| | | | | 124-110-20-b4 | 12/2/2014 | 13:35 | 1.8 | Yes | | |
| | | | | 124-110-20-c1 | 12/2/2014 | 13:40 | 12.9 | Yes | | |
| | | | | 124-110-20-c2 | 12/2/2014 | 13:45 | 15.6 | Yes | | |
| | | | | 124-110-20-c3 | 12/2/2014 | 13:50 | 29.1 | | Yes | |
| | | | | 124-110-20-c4 | 12/2/2014 | 13:55 | 179 | | Yes | |
| 110-114 | <20 | 124-114-20-a (A31) | 1000 | 124-114-20-a1 | 12/16/2014 | 10:40 | 29.8 | | Yes | |
| | | | | 124-114-20-a2 | 12/16/2014 | 10:45 | 34.5 | | Yes | |
| | | | | 124-114-20-a3 | 12/16/2014 | 10:50 | 49.3 | | Yes | |
| | | | | 124-114-20-a4 | 12/16/2014 | 10:55 | 19.9 | Yes | | |
| Site 41 | <20 | 124-114-20-b | 135 | 124-114-20-b1 | 12/16/2014 | 11:00 | 10.6 | Yes | | |
| 110-114 | >1,000 | 124-114-1000-a (East D 6) | 625 | 124-114-1000-a1 | 12/16/2014 | 13:15 | 42.3 | | Yes | |
| | | | | 124-114-1000-a2 | 12/16/2014 | 13:20 | 65 | | Yes | |
| | | | | 124-114-1000-a3 | 12/16/2014 | 13:25 | 75.3 | | Yes | |
| | | | | 124-114-1000-a4 | 12/16/2014 | 13:30 | 16.5 | | Yes | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
10-02-2014

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

**Table 1**

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | | | | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | | | | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | | | | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | | | | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | | | | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | | | | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | 3.2 | 4.9 | 4.6 | | 3.8 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E1A-SO, W1-SO, North FS-4, North FS-6

## Attachment 8: Groundwater Quality Data Surcharge Monitoring Update

(not available as of this report date - provided on a quarterly basis)

# Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

## Attachment 10: Sheet Pile Update

(not included in this reporting period)

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 31, 2014

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 4 |
| Housekeeping | | X | | 5 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 6 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/31/14

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Wednesday, December 31, 2014

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Orange safety fencing has fallen over at the western-most excavation in Site 163 on SA-6 South. |
| 2 | IA2Q4A1AL8 | The containment berm surrounding the western-most material stockpile in the SA-6 South backfill area requires maintenance. |
| 3 | IA2Q4A1AL8 | The haul road on the eastern side of the SA-6 South backfill area has additional depressions containing ponded storm water and mud. |
| 4 | IA2Q4A1AL8 | Storm water is ponded in the floor of the Study Area 6 South excavation |
| 5 | IA2Q4A1AL8 | Trash and debris are accumulating outside of the perimeter fence on Rt.440 and Kellogg Street. |
| 6 | IA2Q4A1AL8 | Sediment has accumulated on the western and southern SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 12/31/14
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Reinstall and maintain the orange safety fencing surrounding the two shallow excavations on Site 163. | 1/5/15 RAD |
| 2 | Build up the containment berm surrounding the stockpile area as required and re-cover with plastic sheeting to prevent erosion. | 1/5/15 RAD |
| 3 | Regrade additional sections of the haul road in the Study Area 6 backfill area as necessary. | 1/5/15 RAD |
| 4 | Pump ponded storm water to the CWTP as necessary to eliminate surface ponds. | 1/5/15 RAD |
| 5 | Pick up trash and debris from the roadside and the grass areas along Kellogg Street and the Rt. 440 jughandle. | 1/5/15 RAD |
| 6 | Remove sediment from the SA-7 haul roads and wash the roadways down. | 1/5/15 RAD |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/06/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 8, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 01/08/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, January 08, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | No silt fence is present along the eastern end of the south toe of the 2-S surcharge stockpile. |
| 2 | IA2Q4A1AL8 | Silt fence along the eastern toe of the 2-N surcharge stockpile has been damaged by wind and vehicle traffic. |
| 3 | IA2Q4A1AL8 | Sediment has accumulated in the southwestern corner of the SA-7 paved roadway. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 01/08/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt fence along the southern toe of the 2-S stockpile where it is missing. | ground frozen - both will be |
| 2 | Repair or replace the silt fence along the eastern toe of the 2-N stockpile as needed. | completed next week on 1-19-14 RAD |
| 3 | Remove the accumulated sediment from the southwestern corner of the SA-7 roadway. | 1-9-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 01/14/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 16, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 6 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 01/16/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, January 16, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | **REPEAT DUE TO FROZEN SITE CONDITIONS:** No silt fence is present along the eastern end of the south toe of the 2-S surcharge stockpile. |
| 2 | IA2Q4A1AL8 | Sediment has accumulated along the northern edge of the west end of Kellogg Street. |
| 3 | IA2Q4A1AL8 | Storm water has accumulated on the floor of the SA-6 South main excavation. |
| 4 | IA2Q4A1AL8 | The silt fence along the southern toe of the 1-S surcharge stockpile area requires maintenance. |
| 5 | IA2Q4A1AL8 | **REPEAT DUE TO FROZEN SITE CONDITIONS:** Sediment has accumulated in the southwestern corner of the SA-7 paved roadway. |
| 6 | IA2Q4A1AL8 | Garbage and other debris has accumulated both on and along the inboard side of the eastern SA-7 perimeter fence. |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Date: 01/16/15
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt fence along the southern toe of the 2-S stockpile where it is required. | 1-16-15 RAD |
| 2 | Remove accumulated sediment from along the street. | 1-22-15 |
| 3 | Pump the accumulated storm water to the Construction Water Treatment Plant. | 1-21-15 RAD |
| 4 | Repair or replace the damaged silt fence as necessary. | 1-21-15 RAD |
| 5 | Removed the accumulated sediment from the roadway. | 1-21-15 RAD |
| 6 | Remove and dispose of any accumulated trash debris from the fenceline. Remove the empty propylene glycol container. | 1-21-15 RAD |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/22/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 23, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | X | | 4 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 01/23/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Friday, January 23, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Additional silt fence is required along the southern toe of the 2-S stockpile area. |
| 2 | IA2Q4A1AL8 | Potholes have formed on the eastern haul road on SA-6 South |
| 3 | IA2Q4A1AL8 | Ponded storm water has drained from the westernmost Site 163 open excavation through the Droyer's Cove bulkhead, creating a void. |
| 4 | IA2Q4A1AL8 | Type B material has accumulated against the northern containment berm in the sedimentation basin, creating the potential for storm water run-off escaping the EZ. |
| 5 | IA2Q4A1AL8 | Sediment has accumulated around the perimeter pool riser grate on the northern SA-7 roadway by Construction Water Treatment Plant access ramp. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 01/23/15
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install additional silt fence along the southern toe of the 2-S surcharge area as required. | Snow covered and frozen conditions |
| 2 | Grade out or fill the potholes in the haul road. | are preventing these from |
| 3 | Repair the void in the Droyer's Cove bulkhead as per the engineers design. | being completed. |
| 4 | Remove accumulated material along the inboard side of the containment berm to allow storm water to flow towards the installed sump or increase the size of the berm. | 1-26-15 RMS |
| 5 | Remove the accumulated sediment from the area around the perimeter pool grate. | 1-23-15 RMS |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/28/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 30, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other Snow cover on site
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 01/30/15

SWPPP Observer: _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, January 30, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Additional silt fence is required along the southern toe of the 2-S stockpile area. |
| 2 | IA2Q4A1AL8 | REPEAT: Potholes have formed on the eastern haul road on SA-6 South |
| 3 | IA2Q4A1AL8 | REPEAT: Ponded storm water has drained from the westernmost Site 163 open excavation through the Droyer's Cove bulkhead, creating a void. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 01/30/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install additional silt fence along the southern toe of the 2-S surcharge area as required | ——— |
| 2 | Grade out or fill the potholes in the haul road. | 2-4-15 RAD |
| 3 | Repair the void in the Droyer's Cove bulkhead as per the engineers design | ——— |
| | Items 1 and 3 can not be completed due to site being covered by a sheet of ice | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 02/04/15

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (December 2014)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

January 19, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the December 2014 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 12 | 01 | 14 | 12 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,516 | 91,665 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.48 | 0.58 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.6 | <5.6 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1299 | 0.1299 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J Morris IV
Signature of Principal
Executive or Authorized Agent

John J. Morris
Remediation Portfolio Director
Type Name and Title

Jan 13, 2015
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 12 | 01 | 14 | 12 | 31 | 14 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,372,010 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 24,707,129 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 12/9/2014 | <3.4 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J Morris HE | John J. Morris | (973) 455-4003 |
| | | DATE Jan 13, 2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | | MONTH: December 2014 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 12/1/2014 | Angel Trujillo | 22335119 | 22410123 | 75,004 | 0.075004 | 7.15 | 0.755 | | | | | | | | | 0.47 |
| 12/2/2014 | Angel Trujillo | 22410123 | 22490599 | 80,476 | 0.080476 | 8.08 | 0.755 | | | | | | | | | 0.51 |
| 12/3/2014 | Angel Trujillo | 22490599 | 22566499 | 75,900 | 0.0759 | 7.73 | 0.755 | | | | | | | | | 0.48 |
| 12/4/2014 | Angel Trujillo | 22566499 | 22644015 | 77,516 | 0.077516 | 7.64 | 0.755 | | | | | | | | | 0.49 |
| 12/5/2014 | Angel Trujillo | 22644015 | 22720870 | 76,855 | 0.076855 | 7.57 | 0.755 | | | | | | | | | 0.48 |
| 12/6/2014 | Angel Trujillo | 22720870 | 22799524 | 78,654 | 0.078654 | 7.67 | 0.755 | | | | | | | | | 0.50 |
| 12/7/2014 | Angel Trujillo | 22799524 | 22876176 | 76,652 | 0.076652 | 7.66 | 0.755 | | | | | | | | | 0.48 |
| 12/8/2014 | Angel Trujillo | 22876176 | 22950558 | 74,382 | 0.074382 | 7.63 | 0.755 | | | | | | | | | 0.47 |
| 12/9/2014 | Angel Trujillo | 22950558 | 23026014 | 75,456 | 0.075456 | 7.37 | 0.755 | <5.6 | <3.4 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.48 |
| 12/10/2014 | Angel Trujillo | 23026014 | 23101942 | 75,928 | 0.075928 | 7.67 | 0.755 | | | | | | | | | 0.48 |
| 12/11/2014 | Angel Trujillo | 23101942 | 23178600 | 76,658 | 0.076658 | 7.58 | 0.755 | | | | | | | | | 0.48 |
| 12/12/2014 | Angel Trujillo | 23178600 | 23256990 | 78,390 | 0.07839 | 7.61 | 0.755 | | | | | | | | | 0.49 |
| 12/13/2014 | Angel Trujillo | 23256990 | 23335980 | 78,990 | 0.07899 | 7.64 | 0.755 | | | | | | | | | 0.50 |
| 12/14/2014 | Angel Trujillo | 23335980 | 23411354 | 75,374 | 0.075374 | 7.47 | 0.755 | | | | | | | | | 0.47 |
| 12/15/2014 | Angel Trujillo | 23411354 | 23486154 | 74,800 | 0.0748 | 7.67 | 0.755 | | | | | | | | | 0.47 |
| 12/16/2014 | Angel Trujillo | 23486154 | 23563690 | 77,536 | 0.077536 | 7.62 | 0.755 | | | | | | | | | 0.49 |
| 12/17/2014 | Angel Trujillo | 23563690 | 23640367 | 76,677 | 0.076677 | 7.58 | 0.755 | | | | | | | | | 0.48 |
| 12/18/2014 | Angel Trujillo | 23640367 | 23715804 | 75,437 | 0.075437 | 7.61 | 0.755 | | | | | | | | | 0.48 |
| 12/19/2014 | Angel Trujillo | 23715804 | 23791334 | 75,530 | 0.07553 | 7.55 | 0.755 | | | | | | | | | 0.48 |
| 12/20/2014 | Angel Trujillo | 23791334 | 23870759 | 79,425 | 0.079425 | 7.58 | 0.755 | | | | | | | | | 0.50 |
| 12/21/2014 | Angel Trujillo | 23870759 | 23944230 | 73,471 | 0.073471 | 7.57 | 0.755 | | | | | | | | | 0.46 |
| 12/22/2014 | Angel Trujillo | 23944230 | 24015436 | 71,206 | 0.071206 | 7.54 | 0.755 | | | | | | | | | 0.45 |
| 12/23/2014 | Angel Trujillo | 24015436 | 24096377 | 80,941 | 0.080941 | 7.51 | 0.755 | | | | | | | | | 0.51 |
| 12/24/2014 | Angel Trujillo | 24096377 | 24171160 | 74,783 | 0.074783 | 7.57 | 0.755 | | | | | | | | | 0.47 |
| 12/25/2014 | Angel Trujillo | 24171160 | 24262825 | 91,665 | 0.091665 | 7.50 | 0.755 | | | | | | | | | 0.58 |
| 12/26/2014 | Angel Trujillo | 24262825 | 24327099 | 64,274 | 0.064274 | 7.55 | 0.755 | | | | | | | | | 0.40 |
| 12/27/2014 | Angel Trujillo | 24327099 | 24407222 | 80,123 | 0.0801 | 7.57 | 0.755 | | | | | | | | | 0.50 |
| 12/28/2014 | Angel Trujillo | 24407222 | 24484406 | 77,184 | 0.077184 | 7.48 | 0.755 | | | | | | | | | 0.49 |
| 12/29/2014 | Angel Trujillo | 24484406 | 24555341 | 70,935 | 0.070935 | 7.57 | 0.755 | | | | | | | | | 0.45 |
| 12/30/2014 | Angel Trujillo | 24555341 | 24628602 | 73,261 | 0.073261 | 7.46 | 0.755 | | | | | | | | | 0.46 |
| 12/31/2014 | Angel Trujillo | 24628602 | 24707129 | 78,527 | 0.078527 | 7.52 | 0.755 | | | | | | | | | 0.49 |
| TOTAL | | | | 2,372,010 | 2.37201 | | | <5.6 | <3.4 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 91,665 | | | | | | | | | | | High: | 0.58 |
| | | | Average: | 76,516 | | | | | | | | | | | Average: | 0.48 |

WW

JB83662

E

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 41982.48610 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-120914 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | Preservative 3 | 3 3 1 2 2 0 0 2 | Site ID Hudson Co |
| Honeywell International<br>101 Columbia Road Morristown, NJ 07962 | Analysis Turnaround Time (TAT): 3<br>Consultant CH2M | | | Lab Job # HWINJM32815 |
| Preliminary Data To | | | | Authorized User: Honeywell |
| Sample Receipt Acknowledgement To | | | | Label & Test Fax Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Various ILS Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA W224-SL VOCs; see attached specific list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-120914-A | 12/9/2014 | 14:25 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | -1 | | | | | L27 |
| 2 | 087-WW | | | 087-WWE-120914-B | 12/9/2014 | 14:40 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | -2 | | | | | V605 |
| 3 | 087-WW | | | 087-WWI-120914 | 12/9/2014 | 14:55 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | -3 | | | | | M17 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

12-9-14 1m

AES SAMPLES RECEIVED

RECEIVED AS APPLICABLE

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Relinquished by: Frank Schroyer | 7-3754@ | 6.9°C | Company: AMEC Foster Wheeler | Received by: | | Company: | | Condition: | Custody Seals Intact: |
| | Date/Time: | | 12/9/14 1330 | | | Date/Time: 12/9/14 1550 | | Cooler Temp. | |
| Relinquished by: | | Company: | | Received by: | | Company: | AESI | Condition: | Custody Seals Intact: N/A |
| | Date/Time: 12/9/14 1655 | | | | | Date/Time: | 12/9 1655 | Cooler Temp. 0.0°C-B | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

1Amm

W

Accutest LabLink@831116 10:16 22-Dec-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120914-A | | |
| **Lab Sample ID:** | JB83662-1 | **Date Sampled:** | 12/09/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/09/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 755 | 10 | ug/l | 1 | 12/10/14 | 12/11/14 | KF | EPA 200.7 [1] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 12/10/14 | 12/11/14 | KF | EPA 200.7 [1] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 12/10/14 | 12/12/14 | KF | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 12/11/14 | 12/11/14 | JW | EPA 245.1 [2] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 12/10/14 | 12/11/14 | KF | EPA 200.7 [1] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 12/10/14 | 12/11/14 | KF | EPA 200.7 [1] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA35632
(2) Instrument QC Batch: MA35636
(3) Instrument QC Batch: MA35643
(4) Prep QC Batch: MP83774
(5) Prep QC Batch: MP83805

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@831116 10:16 22-Dec-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120914-A | | |
| **Lab Sample ID:** | JB83662-1 | **Date Sampled:** | 12/09/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/09/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 12/11/14 | JS | SM2540 D-11 |
| pH [a] | 7.06 | | su | 1 | 12/09/14 17:09 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@831116 10:16 22-Dec-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120914-A | | |
| **Lab Sample ID:** | JB83662-1A | **Date Sampled:** | 12/09/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/09/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 3.4 | 3.4 | mg/l | 1 | 12/10/14 20:21 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@831116 10:16 22-Dec-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120914-B | | |
| **Lab Sample ID:** | JB83662-2 | **Date Sampled:** | 12/09/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/09/14 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.6 | 5.6 | mg/l | 1 | 12/12/14 | BM | EPA 1664A |

RL = Reporting Limit

Accutest LabLink@831116 10:16 22-Dec-2014

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120914-B | | |
| **Lab Sample ID:** | JB83662-2 | **Date Sampled:** | 12/09/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/09/14 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N241979.D | 1 | 12/11/14 | DC | n/a | n/a | VN10263 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.2 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 2.8 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.21 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.78 | ug/l | |
| 67-66-3 | Chloroform | 17.5 | 1.0 | 0.14 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.16 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.20 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.39 | 1.0 | 0.11 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.12 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.46 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.29 | 1.0 | 0.15 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 60.7 | 1.0 | 0.23 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.3 | 1.0 | 0.24 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.20 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 89 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.51 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@831116 10:16 22-Dec-2014

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120914-B | | |
| **Lab Sample ID:** | JB83662-2 | **Date Sampled:** | 12/09/14 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/09/14 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 42.0 | 1.0 | 0.17 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.31 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.12 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 100% | | 71-128% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 79-117% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 97% | | 81-114% |
| 1868-53-7 | Dibromofluoromethane (S) | 100% | | 78-115% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending December 2014**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014** | Direction on the handling of petroleum soils under the cap. | Pending submittal to Parties' per request. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**3/13/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

March 13, 2015 *Via Electronic Delivery*

Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-02**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from February 1 – February 28, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: February 2015 SA-6/7 Combined Monthly Progress Report No. 2015-02

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-02

**Project SA-6 & 7 Remediation**

## February 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 02/04/15 | Arnold & Porter Submittal: Study Area 6 North and South -- In Situ Treatment of Hexavalent Chromium Impacted Soils | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/04/15 | Surcharge Monitoring Plan – Monthly Report No. 9<br>Study Area 6 North and South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/10/15 | Long Term Monitoring Program - Year 1 Implementation Report<br>Study Area 7 Sediment Remedy Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/12/15 | Public Notification Signs<br>NJDEP Hudson County Chromate Site 087 SA-6N And Sites 073, 124, 125, 134, 140, & 163 SA-6S<br>Jersey City, Hudson County, NJ<br>SA-6 North NJDEP SRP PI NOs: 019985 & 002633<br>SA-6 South NJDEP SRP PI NOs: G0000000927, G0000008741, G0000008742, 033312, 003846, & 010374 | NJ Department of Environmental Protection |
| 02/12/15 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2015-01 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/17/15 | Special Master Conference Call | N/A |
| 02/19/15 | New Source of Imported Clean Fill<br>Study Area 6 (SA-6)<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/19/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 02/8/15 | 02/15/15 | 02/22/15 | 03/1/15 |
| **Construction Management (AMEC)** | 11 | 11 | 11 | 11 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 24 | 26 | 25 | 25 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 0 | 1 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **Gramercy** | 10 | 10 | 9 | 8 |
| **TOTAL STAFF** | **52** | **54** | **51** | **51** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected February PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed above-grade demolition of the former Waste Management Garage and the JCIA Garage. Continued above-grade demolition and load out of the JCIA Incinerator Building.
- On February 2 and 3, 2015, Cornerstone personnel re-developed GWET extraction well 087-PW-2. The acid flushing of PW-2 force main to the GWTP was also completed at this time.
- On February 4, 2015, Cornerstone personnel re-developed injection well 088-IW-01. Cornerstone performed a follow-up yield test of the well on March 2, 2015.
- On February 10, 2015, the Year 1 Implementation Report for SA-7 Sediment Remedy Long-term Monitoring Program was submitted.
- On February 19, 2015, contractor removed the Site 163 UST from SA-6 South, Facility ID number 010374. The closure report was finalized by the LSRP and submitted to all parties on March 3, 2015.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on February 18, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 02/8/15 | 02/15/15 | 02/22/15 | 03/1/15 |
| Avg. Gallons Treated & Discharged (per day) | 65,621 | 78,547 | 77,756 | 78,169 |
| Average Flow (gpm) for Operating Period | 55 | 55 | 54 | 54 |
| Avg. Hours of Plant Operation | 20 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 9,897 | 6,876 | 5,018 | 5,573 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Completed installation of the contingent groundwater system (collection trench piping and sumps) within the SA-6 South Open Space Area.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Gramercy- (JCIA Demo)** | 20 cyd roll off | Jersey City, NJ | Sims Metal | Aluminum | 1 | 2.59 | 2.59 |
| **Gramercy- (JCIA Demo)** | 40 cyd roll off | Jersey City, NJ | Sims Metal | Metal | 17 | 15.5 | 263.9 |
| **Gramercy- (JCIA Demo)** | 40 cyd roll off | North Bergen, NJ | Cardella Waste | C&D | 1 | 11.03 | 11.03 |
| **Gramercy- (JCIA Demo)** | 30 cyd roll off | Bayonne, NJ | Durable Recycling | Concrete | 21 | 16.4 | 344.52 |
| **Gramercy- (JCIA Demo)** | 40 cyd roll off | Bayonne, NJ | Durable Recycling | Brick/Masonry | 6 | 18.42 | 110.54 |
| **Entact/ Arecon** | Tri-axle Dump | South Brunswick, NJ | MCUA | Petroleum Impacted Soil | 75 | 24.7 | 1,859.72 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | No update for the reporting period |
| **Backfill in Progress** | Cell number(s): 77-70 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 02/8/15 | 02/15/15 | 02/22/15 | 03/01/15 |
| Tilcon, Import Tons – 1.5" Stone | 73.62 | 204.6 | 0 | 0 |
| NJCU Borrow Material, CY | 0 | 0 | 0 | 4,942 |

- Clean borrow material (from NJCU Surcharge Program) was delivered to the site during the week of February 23, 2015 through February 27, 2015. A total of 353 loads were delivered totaling approximately 4,942 cubic yards. Borrow material is stockpiled within the excavation and will be placed weather permitting.

## E. SURCHARGE OPERATIONS

- Area 1S: Completed offloading Celgene material from 1S and relocating to 2S and temporary stockpile area.
- Area 2S: Surcharging complete on Area 2S. Began offloading Celgene material on February 23, 2015 from west to east, and offload is approximately 30% complete.
- Area 3S: Surcharge placement continued on Area 3S and isnow fully constructed.
- Area 1N: Surcharge removal activities were discontinued in February in Area 1N. Surcharge removal activities in this area remain at approximately 85% complete.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: No activity in this area pending demobilization of the JCIA Demolition contractor.
- Area 4N: No activity in this area pending demobilization of the JCIA Demolition contractor.
- Active Monitoring for Surcharge is currently limited to Area 3S. The combination of snow and temperatures are preventing personnel from taking readings at the frequency stated in the Surcharge Monitoring Plan Monitoring will resume at all points when it is feasible and safe to do so.

## F. SHEET PILE OPERATIONS

- Resumed delivery of sheet pile for the remaining barrier wall at SA-6 North.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete JCIA Structures Demolition and demobilize.
- Continue loadout and transportation and disposal activities of non-hazardous petroleum impacted soils at SA-6 South.
- Complete delivery of steel sheetpile for remaining SA-6 North Barrier Wall installation.
- Complete removal of temporary sheetpile on the south side of the SA-6 south excavation area.
- Resume Vertical Hydraulic Barrier wall installation activities on SA6 North.

- Continue monitoring well abandonment activities on SA6 South.
- Complete installation of utility pole sleeves associated with PSEG overhead line relocation activities.
- Collect round of quarterly groundwater levels.
- Conduct S-3 Mass Removal Injection Event No.19.
- Conduct quarterly GWET well sampling.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Continue the SA-6 North Bench-Scale Treatability Study for Treatment Area 10 proximate to force main.
- Continue to coordinate with the JCDPW on their off-site relocation of remaining equipment from SA-6 North.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. *Backfill Analytical Data (not included in this reporting period)*
7. Perimeter Pools Update
8. *Groundwater Quality Data (sampled quarterly, not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. *Sheet Pile Update (not included in this reporting period)*
11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (January 2015)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

amec foster wheeler

| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** |
| 67a | Restoration | 164 days | Tue 9/1/15 |




Project: SA-6 Remediation Schedule
Revision 3
Date: Wed 3/4/15

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Contractor continues demolition of incinerator building.




**Site Photograph 2:** Contractor demolishes incinerator trash pit.




**Site Photograph 3:** Contractor grading on Kellogg St. properties.




**Site Photograph 4:** Contractor loading stone bedding material.



**Photograph 5:** Contractor moving surcharge material into place.





**Site Photograph 6:** Contractor stockpiling clean backfill material.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of March 1, 2015

February 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)


| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 01/02/15 | 7:00 | 14:30 | 7:30 | 25,613.83 | 25,704.93 | 91,100 | 25,704,480 | |
| 01/05/15 | 7:00 | 16:45 | 9:45 | 25,704.93 | 25,803.51 | 98,580 | 25,803,060 | |
| 01/06/15 | 7:00 | 15:15 | 8:15 | 25,803.51 | 25,934.54 | 131,030 | 25,934,090 | |
| 01/07/15 | 7:00 | 15:00 | 8:00 | 25,934.54 | 26,010.92 | 76,380 | 26,010,470 | |
| 01/11/15 | 9:00 | 14:00 | 5:00 | 26,010.92 | 26,076.69 | 65,770 | 26,076,240 | |
| 01/12/15 | 13:30 | 16:00 | 2:30 | 26,076.69 | 26,123.43 | 46,740 | 26,122,980 | |
| 01/13/15 | 13:30 | 16:00 | 2:30 | 26,123.43 | 26,242.94 | 119,510 | 26,242,490 | PVSC Compliance Sample Collected |
| 01/14/15 | 10:15 | 16:00 | 5:45 | 26,242.94 | 26,294.50 | 51,560 | 26,294,050 | |
| 01/15/15 | 7:30 | 15:00 | 7:30 | 26,294.50 | 26,374.46 | 79,960 | 26,374,010 | |
| 01/16/15 | 7:30 | 14:00 | 6:30 | 26,374.46 | 26,431.98 | 57,520 | 26,431,530 | |
| 01/19/15 | 7:00 | 16:00 | 9:00 | 26,431.98 | 26,544.34 | 112,360 | 26,543,890 | |
| 01/20/15 | 7:00 | 16:30 | 9:30 | 26,544.34 | 26,671.53 | 127,190 | 26,671,080 | |
| 01/21/15 | 7:00 | 16:00 | 9:00 | 26,671.53 | 26,795.65 | 124,120 | 26,795,200 | |
| 01/22/15 | 7:00 | 15:30 | 8:30 | 26,795.65 | 26,937.52 | 141,870 | 26,937,070 | |
| 01/23/15 | 7:00 | 15:00 | 8:00 | 26,937.52 | 27,077.78 | 140,260 | 27,077,330 | |
| 01/28/15 | 7:00 | 14:30 | 7:30 | 27,077.78 | 27,127.82 | 50,040 | 27,127,370 | |
| 01/29/15 | 7:00 | 15:00 | 8:00 | 27,127.82 | 27,180.82 | 53,000 | 27,180,370 | |
| 01/30/15 | 7:00 | 14:00 | 7:00 | 27,180.82 | 27,268.67 | 87,850 | 27,268,220 | |
| 02/04/15 | 7:00 | 12:30 | 5:30 | 27,268.67 | 27,317.51 | 48,840 | 27,317,060 | PVSC Compliance Sample Collected |
| 02/05/15 | 7:30 | 15:00 | 7:30 | 27,317.51 | 27,437.11 | 119,600 | 27,436,660 | |
| 02/09/15 | 9:30 | 14:30 | 5:00 | 27,437.11 | 27,484.85 | 47,740 | 27,484,400 | |
| 02/10/15 | 9:30 | 16:15 | 6:45 | 27,484.85 | 27,587.00 | 102,150 | 27,586,550 | |
| 02/11/15 | 8:00 | 14:30 | 6:30 | 27,587.00 | 27,626.34 | 39,340 | 27,625,890 | |
| 02/12/15 | 8:00 | 14:30 | 6:30 | 27,626.34 | 27,687.34 | 61,000 | 27,686,890 | |
| 02/20/15 | 10:30 | 12:15 | 1:45 | 27,687.34 | 27,702.61 | 15,270 | 27,702,160 | |
| 02/23/15 | 7:30 | 15:30 | 8:00 | 27,702.61 | 27,758.65 | 56,040 | 27,758,200 | |
| 02/25/15 | 7:30 | 15:00 | 7:30 | 27,758.65 | 27,788.98 | 30,330 | 27,788,530 | |
| 02/26/15 | 7:30 | 14:00 | 6:30 | 27,788.98 | 27,806.88 | 17,900 | 27,806,430 | |
| 03/02/15 | 10:30 | 14:30 | 4:00 | 27,806.88 | 27,853.74 | 46,860 | 27,853,290 | |

Notes: Previous information is trunketed. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

(not included in this reporting period)

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
10-02-2014

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

**Table 1**

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3/3/2014 | | | | | | | | | | | 7.3 | 5.0 | | | | | | | | | | | | | |
| 3/6/2014 | | 6.2 | 6.8 | 6.5 | 7.3 | | 7.4 | | | | | | | | | | | | | | | | | | |
| 3/13/2014 | | | | | | | | | | | 7.4 | 4.1 | | | | | | | | | | | | | |
| 3/20/2014 | | 5.6 | 6.7 | 7.2 | 7.4 | | 7.8 | 8.2 | | | | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | | | | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | | | | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | | | | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | | | | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | | | | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | | | | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | | | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, E2-SO, W1-SO, W6-SO, North FS-4, South FS-3

## Attachment 8: Groundwater Quality Data

(not available as of this report date - provided on a quarterly basis)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

## Attachment 10: Sheet Pile Update

(not included in this reporting period)

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 5, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☑ Other Snow Cover
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

NOTE: All comments are numbered for reference and included on the included comment section.

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/06/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Thursday, February 05, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Additional silt fence is required along the southern toe of the 2-S stockpile area. |
| 2 | IA2Q4A1AL8 | Windscreen on the Kellogg Street perimeter fence requires maintenance. |
| 3 | IA2Q4A1AL8 | REPEAT: Ponded storm water has drained from the westernmost Site 163 open excavation through the Dreyer's Cove bulkhead, creating a void. |
| 4 | IA2Q4A1AL8 | Sediment is present on the southern SA-7 roadway due to off-road dump truck traffic. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ Signature **Date:** 02/06/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install additional silt fence along the southern toe of the 2-S surcharge area as required | |
| 2 | Re-attach windscreen to the chain link fabric | 2-9-15 RAD |
| 3 | Repair the void in the Dreyer's Cove bulkhead as per the engineers design. | |
| 4 | Clean the sediment from the SA-7 roadway and install erosion control measures (tracking pads, etc.) as required to minimize sediment accumulation on the pavement | 2-6-15 RAD |
| | 1 & 3 can not be completed due to site being covered in a sheet of ice | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 02/11/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 13, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

- - 1 - -

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/13/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, February 13, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Additional silt fence is required along the southern toe of the 2-S stockpile area. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 02/13/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install additional silt fence along the southern toe of the 2-S surcharge area as required. Silt fence should extend eastwards along the slope of the area recently surcharged. | Site is covered in a sheet of ice and cannot be completed until thawed (RAD) |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Silt fence to be installed once ground thaws. RP

**Construction Manager:** _____ **Date:** 02/18/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 20, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other Temps < 20°f
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/20/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, February 20, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT. Additional silt fence is required along the southern toe of the S stockpile area |
| 2 | IA2Q4A1AL8 | Windscreen on the Kellogg Street perimeter fence has blown loose in several locations. |
| 3 | IA2Q4A1AL8 | Windscreen on the perimeter fence between SA and SA-6 North has blown loose in several locations. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: [signature] Date: 02/20/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install additional silt fence along the southern toe of the S stockpile area as required. Silt fence should extend [illegible] along the slope of the [illegible] | Cannot be completed due to frozen ground |
| 2 | Re-attach windscreen fabric to the perimeter fence as required | 2-25-15 RAD |
| 3 | Re-attach windscreen fabric to the perimeter fence as required | 2-25-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: [signature] Date: 02/25/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 25, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☑ Other Site Frozen/Snow Covered
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 4 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 5 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/25/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Wednesday, February 25, 2015**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Additional silt fence is required along the southern toe of the 2-S stockpile area. |
| 2 | IA2Q4A1AL8 | The vehicle tracking pad at the site exit to the east of 60 Kellogg Street is blinded with snow/ice/sediment. |
| 3 | IA2Q4A1AL8 | The storm drain at the site exit to the east of 60 Kellogg Street does not have a sediment filter installed. |
| 4 | IA2Q4A1AL8 | the orange exclusion zone fencing on the western side of the sedimentation basin is down and requires maintenance. |
| 5 | IA2Q4A1AL8 | There is a gap in the perimeter fenceline on SA-6 North where the CWTP discharge line exits the containment area. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 02/25/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install additional silt fence along the southern toe of the 2-S surcharge area as required. Silt fence should extend eastwards along the slope of the area recently surcharged. | Can not complete ground is frozen |
| 2 | Resurface the stone tracking pad as required to restore function. | 2-25-15 RAD |
| 3 | Install filter fabric in the storm water catch basin located outside of the eastern 60 Kellogg gate. | 2-25-15 RAD |
| 4 | Repair or replace the orange warning fencing on the western side of the sed basin exclusion zone. | 2-25-15 RAD |
| 5 | Install a fencing panel in the area where the CWTP discharge line exits the secondary containment area. | 2-25-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 02/26/15

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (January 2015)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

February 19, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the January 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA
Frank Schroyer - Parsons

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 1 | 01 | 15 | 1 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,112 | 91,413 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.89 | 1.07 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1628 | 0.1628 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris HF

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

Feb 17, 2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 1 | 01 | 15 | 1 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,359,467 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 27,066,596 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 1/16/2015 | 6.7 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J Morris IV | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE February 17, 2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | | MONTH: January 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 1/1/2015 | Angel Trujillo | 24707129 | 24791602 | 84,473 | 0.084473 | 7.55 | 1.400 | | | | | | | | | 0.99 |
| 1/2/2015 | Angel Trujillo | 24791602 | 24865808 | 74,206 | 0.074206 | 7.62 | 1.400 | | | | | | | | | 0.87 |
| 1/3/2015 | Angel Trujillo | 24865808 | 24942146 | 76,338 | 0.076338 | 7.44 | 1.400 | | | | | | | | | 0.89 |
| 1/4/2015 | Angel Trujillo | 24942146 | 24999653 | 57,507 | 0.057507 | 7.12 | 1.400 | | | | | | | | | 0.67 |
| 1/5/2015 | Angel Trujillo | 24999653 | 25091066 | 91,413 | 0.091413 | 7.03 | 1.400 | | | | | | | | | 1.07 |
| 1/6/2015 | Angel Trujillo | 25091066 | 25165920 | 74,854 | 0.074854 | 7.13 | 1.400 | | | | | | | | | 0.87 |
| 1/7/2015 | Angel Trujillo | 25165920 | 25240372 | 74,452 | 0.074452 | 7.16 | 1.400 | | | | | | | | | 0.87 |
| 1/8/2015 | Angel Trujillo | 25240372 | 25317444 | 77,072 | 0.077072 | 7.09 | 1.400 | | | | | | | | | 0.90 |
| 1/9/2015 | Angel Trujillo | 25317444 | 25395018 | 77,574 | 0.077574 | 7.15 | 1.400 | | | | | | | | | 0.91 |
| 1/10/2015 | Angel Trujillo | 25395018 | 25472650 | 77,632 | 0.077632 | 7.22 | 1.400 | | | | | | | | | 0.91 |
| 1/11/2015 | Angel Trujillo | 25472650 | 25553397 | 80,747 | 0.080747 | 7.14 | 1.400 | | | | | | | | | 0.94 |
| 1/12/2015 | Angel Trujillo | 25553397 | 25622374 | 68,977 | 0.068977 | 7.19 | 1.400 | | | | | | | | | 0.81 |
| 1/13/2015 | Angel Trujillo | 25622374 | 25698800 | 76,426 | 0.076426 | 7.16 | 1.400 | | | | | | | | | 0.89 |
| 1/14/2015 | Angel Trujillo | 25698800 | 25774022 | 75,222 | 0.075222 | 7.06 | 1.400 | | | | | | | | | 0.88 |
| 1/15/2015 | Angel Trujillo | 25774022 | 25850341 | 76,319 | 0.076319 | 7.10 | 1.400 | | | | | | | | | 0.89 |
| 1/16/2015 | Angel Trujillo | 25850341 | 25924633 | 74,292 | 0.074292 | 7.16 | 1.400 | <5.1 | 6.7 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.87 |
| 1/17/2015 | Angel Trujillo | 25924633 | 26005981 | 81,348 | 0.081348 | 7.11 | 1.400 | | | | | | | | | 0.95 |
| 1/18/2015 | Angel Trujillo | 26005981 | 26082830 | 76,849 | 0.076849 | 7.10 | 1.400 | | | | | | | | | 0.90 |
| 1/19/2015 | Angel Trujillo | 26082830 | 26156177 | 73,347 | 0.073347 | 7.10 | 1.400 | | | | | | | | | 0.86 |
| 1/20/2015 | Angel Trujillo | 26156177 | 26229773 | 73,596 | 0.073596 | 7.07 | 1.400 | | | | | | | | | 0.86 |
| 1/21/2015 | Angel Trujillo | 26229773 | 26292737 | 62,964 | 0.062964 | 6.78 | 1.400 | | | | | | | | | 0.74 |
| 1/22/2015 | Angel Trujillo | 26292737 | 26376215 | 83,478 | 0.083478 | 7.08 | 1.400 | | | | | | | | | 0.97 |
| 1/23/2015 | Angel Trujillo | 26376215 | 26453039 | 76,824 | 0.076824 | 7.11 | 1.400 | | | | | | | | | 0.90 |
| 1/24/2015 | Angel Trujillo | 26453039 | 26535988 | 82,949 | 0.082949 | 7.06 | 1.400 | | | | | | | | | 0.97 |
| 1/25/2015 | Angel Trujillo | 26535988 | 26608368 | 72,380 | 0.07238 | 7.14 | 1.400 | | | | | | | | | 0.85 |
| 1/26/2015 | Angel Trujillo | 26608368 | 26682845 | 74,477 | 0.074477 | 7.07 | 1.400 | | | | | | | | | 0.87 |
| 1/27/2015 | Angel Trujillo | 26682845 | 26767908 | 85,063 | 0.0851 | 7.11 | 1.400 | | | | | | | | | 0.99 |
| 1/28/2015 | Angel Trujillo | 26767908 | 26836053 | 68,145 | 0.068145 | 7.10 | 1.400 | | | | | | | | | 0.80 |
| 1/29/2015 | Angel Trujillo | 26836053 | 26910845 | 74,792 | 0.074792 | 7.08 | 1.400 | | | | | | | | | 0.87 |
| 1/30/2015 | Angel Trujillo | 26910845 | 26987499 | 76,654 | 0.076654 | 7.09 | 1.400 | | | | | | | | | 0.90 |
| 1/31/2015 | Angel Trujillo | 26987499 | 27066596 | 79,097 | 0.079097 | 7.42 | 1.400 | | | | | | | | | 0.92 |
| TOTAL | | | | 2,359,467 | 2.359467 | | | <5.1 | 6.7 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 91,413 | | | | | | | | | | | High: | 1.07 |
| | | | Average: | 76,112 | | | | | | | | | | | Average: | 0.89 |

WW

E

JB86591

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42020.66259 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-011615 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P. (973) 455-2989 E. helen.fahy@honeywell.com | PO # | Preservative 3 3 3 1 2 2 0 0 2 | | Site ID HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | | | Lab Job # HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant CH2M | | | Authorized User: Honeywell |
| Preliminary Data To | | | | Text & Excel File Drive / Excel & Text File Order |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Version 6.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-011615-A | 1/16/2015 | 14:20 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | |
| 2 | 087-WW | | | 087-WWE-011615-B | 1/16/2015 | 14:35 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | LZ1 |
| 3 | 087-WW | | | 087-WWI-011615 | 1/16/2015 | 14:50 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | V1025 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | A14 |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | G21 |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: pH = 7.16 SU @ 6.8°C | Company: AMEC Foster Wheeler | Received by: | Company: | | Condition: | | Custody Seals Intact: | |
| Frank Schroyer | Date/Time: 1/16/15 | | Date/Time: 1/16/14 4:05pm | | Cooler Temp. | | | |
| Relinquished by: | Company: | Received by: | Company: | | Condition: | | Custody Seals Intact: | |
| | Date/Time: 1/16/15 19:10 | | Date/Time: | 1/16/15 1820 | Cooler Temp. | 0.3 °F | | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

JM

3BWM

ALL SAMPLES RECEIVED
PRESERVED AS APPLICABLE

Accutest LabLink@837523 11:28 06-Feb-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-011615-A | | |
| **Lab Sample ID:** | JB86591-1 | **Date Sampled:** | 01/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1400 | 10 | ug/l | 1 | 01/19/15 | 01/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 01/19/15 | 01/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 01/19/15 | 01/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 01/19/15 | 01/19/15 | JW | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 01/19/15 | 01/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 01/19/15 | 01/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA35880
(2) Instrument QC Batch: MA35888
(3) Prep QC Batch: MP84483
(4) Prep QC Batch: MP84493

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@837523 11:28 06-Feb-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-011615-A | | |
| **Lab Sample ID:** | JB86591-1 | **Date Sampled:** | 01/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 01/17/15 | JS | SM2540 D-11 |
| pH [a] | 7.06 | | su | 1 | 01/16/15 18:26 | HL | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@837523 11:28 06-Feb-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-011615-A | | |
| **Lab Sample ID:** | JB86591-1A | **Date Sampled:** | 01/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 6.7 | 3.4 | mg/l | 1 | 01/16/15 19:11 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@837523 11:28 06-Feb-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-011615-B | | |
| **Lab Sample ID:** | JB86591-2 | **Date Sampled:** | 01/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/16/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | U191899.D | 1 | 01/20/15 | NH | n/a | n/a | VU8860 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.3 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.4 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.22 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.78 | ug/l | |
| 67-66-3 | Chloroform | 18.1 | 1.0 | 0.14 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.16 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.20 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.42 | 1.0 | 0.11 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.12 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.46 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.35 | 1.0 | 0.15 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 85.1 | 1.0 | 0.23 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.3 | 1.0 | 0.24 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.20 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 89 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.49 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@837523 11:28 06-Feb-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-011615-B | | |
| **Lab Sample ID:** | JB86591-2 | **Date Sampled:** | 01/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/16/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 48.1 | 1.0 | 0.17 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.31 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.12 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 102% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 102% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 103% | | 74-112% |
| 1868-53-7 | Dibromofluoromethane (S) | 101% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@837523 11:28 06-Feb-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-011615-B | | |
| **Lab Sample ID:** | JB86591-2 | **Date Sampled:** | 01/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 01/20/15 | JOO | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending February 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**4/15/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 15, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-03**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from March 1 – March 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: March 2015 SA-6/7 Combined Monthly Progress Report No. 2015-03

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-03

**Project SA-6 & 7 Remediation**

## March 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/03/15 | Underground Storage Tank<br>Remedial Action Report<br>75 Kellogg Street<br>Jersey City (Hudson County), New Jersey<br>Block 24601/Lot 11<br>NJDEP PI No. 010374<br>Study Area 6, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/04/15 | Response to Comments Provided by Dr. Ben Ross<br>January 9, 2015<br>In-situ Groundwater Sampling Beneath Riverbed Sediments<br>Study Area 7, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/09/15 | Response to Comments provided by Terris, Pravlik & Millian, LLP and<br>O'Connell & Lawrence<br>Surcharge Monitoring Plan Reports No. 7, 8 and 9<br>Study Areas 6 North and South, Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/13/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016<br>June 2014 | Andy Caltagirone<br>Manager of Industrial & Pollution Control<br>Passaic Valley Sewerage Commission |
| 03/13/15 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2015-02<br>Study Areas 6 and 7, Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/17/15 | Special Master Meeting | N/A |
| 03/30/15 | SA-6 North Treatment Areas 7 & 8<br>SA-6 South Site 163<br>Summary of In-Situ Treatment of Hexavalent Chromium Impacted Soils<br>Study Areas 6 North and South, Jersey City, NJ | Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/31/15 | Plume Pull-Back Presentation | Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 03/8/15 | 03/15/15 | 03/22/15 | 03/22/15 |
| **Construction Management (AMEC)** | 10 | 10 | 11 | 10 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 27 | 29 | 27 | 27 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 2 | 2 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **Gramercy** | 9 | 9 | 8 | 0 |
| **TOTAL STAFF** | **53** | **55** | **54** | **45** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected March PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- On March 18, 2015, Gramercy completed the above-grade demolition of the former JCIA Building Structures. Site cleanup and demobilization activities were completed on March 23, 2015.
- After demobilization of Gramercy, the former JCIA parcel was incorporated into the perimeter fencing to allow for hydraulic barrier installation and subsequent chromium remediation in this portion of SA-6 North.

- On March 22, 23, and 24th, 2015, Cornerstone personnel conducted S-3 Mass Removal Injection Event #19 in Injection Well 088-IW-01.
- Installed three (3) utility pole sleeves along Route 440 for future PSE&G overhead power line relocation.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on March 11, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 03/8/15 | 03/15/15 | 03/22/15 | 03/29/15 |
| Avg. Gallons Treated & Discharged (per day) | 76,688 | 77,070 | 77,533 | 76,391 |
| Average Flow (gpm) for Operating Period | 54 | 54 | 54 | 53 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 5,532 | 5,408 | 4,954 | 5,078 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed abandonment of Deep wells DW1, DW2 DW3, DW4 and DW5. The Deep Wells were associated with the temporary construction dewatering activities installed by Entact in the SA-6 South Backfill area.
- Began well abandonment activities on SA-6 North.
- Continued loadout of non-hazardous petroleum impacted soils from SA-6 South.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Gramercy- (JCIA Demo)** | 40 cyd roll off | Jersey City, NJ | Sims Metal | Metal | 9 | 11.0 | 99.2 |
| **Gramercy- (JCIA Demo)** | 40 cyd roll off | North Bergen, NJ | Cardella Waste | C&D | 13 | 17.2 | 224.73 |

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Gramercy- (JCIA Demo)** | 30 cyd roll off | Bayonne, NJ | Durable Recycling | Concrete | 11 | 15.0 | 165 |
| **Gramercy- (JCIA Demo)** | 40 cyd roll off | Bayonne, NJ | Durable Recycling | Brick/Masonry | 62 | 17.9 | 1,112.8 |
| **Entact/ Arecon** | Tri-axle Dump | South Brunswick, NJ | MCUA | Petroleum Impacted Soil | 534 | 26.6 | 14,239 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | No update for the reporting period |
| **Backfill in Progress** | No update for the reporting period |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 03/8/15 | 03/15/15 | 03/22/15 | 03/29/15 |
| NJCU Borrow Material, CY | 3,735 | 6,765 | 0 | 0 |

- Clean borrow material (from NJCU Surcharge Program) was delivered to the site during the weeks of March 2, 2015 through March 13, 2015. A total of 700 loads were delivered totaling approximately 10,500 cubic yards. Borrow material is stockpiled in the eastern area of SA-6 South and will be placed as backfill weather permitting.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging complete on Area 2S. Continue offloading Celgene and Novartis surcharge material (approximately 65% complete).
- Area 3S: Surcharge placement completed on Area 3S and monitoring ongoing.
- Area 1N: Surcharge removal activities were discontinued in February in Area 1N. Surcharge removal activities in this area remain at approximately 85% complete.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: No activity in this area pending installation of surcharge monitoring instrumentation.
- Area 4N: No activity in this area pending installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- Completed delivery of sheet pile for the remaining barrier wall at SA-6 North with exception of several specialty pieces.
- Completed removal of temporary sheet pile on SA-6 South.
- Continued vertical barrier wall installation activities on SA-6 North. Installed vertical barrier wall sheet pile from west of the sedimentation basin eastward through the sedimentation basin and through a portion of the former JCIA property ending east of the trash pit, STA 14+00 to STA 5+25. Vertical barrier wall was also installed on the western perimeter of the SA-6 North cap area from STA 21+75 to STA 23+42.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete loadout and transportation and disposal activities of non-hazardous petroleum impacted soils at SA-6 South.
- Continue Vertical Hydraulic Barrier wall installation activities on SA6 North.
- Remove standing water within the JCIA trash pit and begin removal and loadout of putrescible trash.
- Resume backfilling placement activities at SA-6 South.
- Complete installation of sleeves for anchors associated with Verizon overhead line relocation activities.
- Conduct S-3 Mass Removal Injection Event No. 20.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Continue the SA-6 North Bench-Scale Treatability Study for Treatment Area 10 proximate to force main.
- Continue to coordinate with the JCDPW on their off-site relocation of remaining equipment from SA-6 North.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. *Groundwater Quality Data (sampled quarterly, not available for this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
11. Weekly SWPPP Reports

12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (February 2015)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** |
| 67a | Restoration | 164 days | Tue 9/1/15 |




Project: SA-6 Remediation Schedule
Revision 3
Date: Mon 3/30/15

Task | Milestone | Summary | Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Breaking up concrete for sheet pile installation.



**Site Photograph 2:** Grading Clean Fill.



**Site Photograph 3:** Installing Sheet Pile on JC Properties.




**Site Photograph 4:** Moving surcharge material to stockpile area.



**Photograph 5:** Relocated surcharge soils stockpile.




**Site Photograph 6:** Unloading Clean Fill.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of April 1, 2015

March 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 01/30/15 | 7:00 | 14:00 | 7:00 | 27,180.82 | 27,268.67 | 87,850 | 27,268,220 | |
| 02/04/15 | 7:00 | 12:30 | 5:30 | 27,268.67 | 27,317.51 | 48,840 | 27,317,060 | PVSC Compliance Sample Collected |
| 02/05/15 | 7:30 | 15:00 | 7:30 | 27,317.51 | 27,437.11 | 119,600 | 27,436,660 | |
| 02/09/15 | 9:30 | 14:30 | 5:00 | 27,437.11 | 27,484.85 | 47,740 | 27,484,400 | |
| 02/10/15 | 9:30 | 16:15 | 6:45 | 27,484.85 | 27,587.00 | 102,150 | 27,586,550 | |
| 02/11/15 | 8:00 | 14:30 | 6:30 | 27,587.00 | 27,626.34 | 39,340 | 27,625,890 | |
| 02/12/15 | 8:00 | 14:30 | 6:30 | 27,626.34 | 27,687.34 | 61,000 | 27,686,890 | |
| 02/20/15 | 10:30 | 12:15 | 1:45 | 27,687.34 | 27,702.61 | 15,270 | 27,702,160 | |
| 02/23/15 | 7:30 | 15:30 | 8:00 | 27,702.61 | 27,758.65 | 56,040 | 27,758,200 | |
| 02/25/15 | 7:30 | 15:00 | 7:30 | 27,758.65 | 27,788.98 | 30,330 | 27,788,530 | |
| 02/26/15 | 7:30 | 14:00 | 6:30 | 27,788.98 | 27,806.88 | 17,900 | 27,806,430 | |
| 03/02/15 | 10:30 | 14:30 | 4:00 | 27,806.88 | 27,853.74 | 46,860 | 27,853,290 | |
| 03/04/15 | 7:30 | 14:00 | 6:30 | 27,853.74 | 27,955.09 | 101,350 | 27,954,640 | PVSC Compliance Sample Collected |
| 03/05/15 | 8:00 | 14:00 | 6:00 | 27,955.09 | 28,075.85 | 120,760 | 28,075,400 | |
| 03/06/15 | 7:30 | 14:30 | 7:00 | 28,075.85 | 28,200.09 | 124,240 | 28,199,640 | |
| 03/09/15 | 7:30 | 15:00 | 7:30 | 28,200.09 | 28,324.06 | 123,970 | 28,323,610 | |
| 03/10/15 | 7:30 | 15:00 | 7:30 | 28,324.06 | 28,458.25 | 134,190 | 28,457,800 | |
| 03/11/15 | 8:00 | 14:30 | 6:30 | 28,458.25 | 28,520.01 | 61,760 | 28,519,560 | |
| 03/12/15 | 9:00 | 15:00 | 6:00 | 28,520.01 | 28,571.66 | 51,650 | 28,571,210 | |
| 03/13/15 | 8:00 | 15:00 | 7:00 | 28,571.66 | 28,691.97 | 120,310 | 28,691,520 | |
| 03/14/15 | 8:00 | 16:30 | 8:30 | 28,691.97 | 28,827.02 | 135,050 | 28,826,570 | |
| 03/15/15 | 10:00 | 17:00 | 7:00 | 28,827.02 | 28,912.43 | 85,410 | 28,911,980 | |
| 03/16/15 | 7:30 | 15:15 | 7:45 | 28,912.43 | 29,086.98 | 174,550 | 29,086,530 | |
| 03/17/15 | 8:00 | 14:30 | 6:30 | 29,086.98 | 29,181.23 | 94,250 | 29,180,780 | |
| 03/18/15 | 7:30 | 15:00 | 7:30 | 29,181.23 | 29,228.98 | 47,750 | 29,228,530 | |
| 03/19/15 | 7:30 | 15:15 | 7:45 | 29,228.98 | 29,340.87 | 111,890 | 29,340,420 | |
| 03/20/15 | 8:00 | 14:00 | 6:00 | 29,340.87 | 29,436.92 | 96,050 | 29,436,470 | |
| 03/23/15 | 8:30 | 15:00 | 6:30 | 29,436.92 | 29,533.78 | 96,860 | 29,533,330 | |
| 03/24/15 | 7:30 | 15:00 | 7:30 | 29,533.78 | 29,615.04 | 81,260 | 29,614,590 | |
| 03/25/15 | 7:30 | 15:15 | 7:45 | 29,615.04 | 29,748.59 | 133,550 | 29,748,140 | |
| 03/26/15 | 7:30 | 15:30 | 8:00 | 29,748.59 | 29,862.15 | 113,560 | 29,861,700 | |
| 03/27/15 | 7:30 | 15:30 | 8:00 | 29,862.15 | 29,986.08 | 123,930 | 29,985,630 | |
| 03/28/15 | 9:00 | 15:00 | 6:00 | 29,986.08 | 30,091.41 | 105,330 | 30,090,960 | |


Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

| Excavated Material Location (Grid No.) | Material Designation (<20 or >1,000) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <1,000 Placed Under Cap | >1,000 Shipped Off Site as Haz |
| 106-110 | <20 | 124-110-20-a,b,c (A30) | 2400 | 124-110-20-a1 | 12/2/2014 | 13:00 | 25 | | Yes | |
| | | | | 124-110-20-a2 | 12/2/2014 | 13:05 | 44 | | Yes | |
| | | | | 124-110-20-a3 | 12/2/2014 | 13:10 | 29.1 | | Yes | |
| | | | | 124-110-20-a4 | 12/2/2014 | 13:15 | 14.8 | Yes | | |
| | | | | 124-110-20-b1 | 12/2/2014 | 13:20 | 23.1 | | Yes | |
| | | | | 124-110-20-b2 | 12/2/2014 | 13:25 | 12.9 | Yes | | |
| | | | | 124-110-20-b3 | 12/2/2014 | 13:30 | 3 | Yes | | |
| | | | | 124-110-20-b4 | 12/2/2014 | 13:35 | 1.8 | Yes | | |
| | | | | 124-110-20-c1 | 12/2/2014 | 13:40 | 12.9 | Yes | | |
| | | | | 124-110-20-c2 | 12/2/2014 | 13:45 | 15.6 | Yes | | |
| | | | | 124-110-20-c3 | 12/2/2014 | 13:50 | 29.1 | | Yes | |
| | | | | 124-110-20-c4 | 12/2/2014 | 13:55 | 179 | | Yes | |
| 110-114 | <20 | 124-114-20-a (A31) | 1000 | 124-114-20-a1 | 12/16/2014 | 10:40 | 29.8 | | Yes | |
| | | | | 124-114-20-a2 | 12/16/2014 | 10:45 | 34.5 | | Yes | |
| | | | | 124-114-20-a3 | 12/16/2014 | 10:50 | 49.3 | | Yes | |
| | | | | 124-114-20-a4 | 12/16/2014 | 10:55 | 19.9 | Yes | | |
| Site 41 | <20 | 124-114-20-b | 135 | 124-114-20-b1 | 12/16/2014 | 11:00 | 10.6 | Yes | | |
| 110-114 | >1,000 | 124-114-1000-a (East D 6) | 625 | 124-114-1000-a1 | 12/16/2014 | 13:15 | 42.3 | | Yes | |
| | | | | 124-114-1000-a2 | 12/16/2014 | 13:20 | 65 | | Yes | |
| | | | | 124-114-1000-a3 | 12/16/2014 | 13:25 | 75.3 | | Yes | |
| | | | | 124-114-1000-a4 | 12/16/2014 | 13:30 | 16.5 | | Yes | |

*Material currently stockpiled. Pending final placement.
**Waiting on results from the laboratory.

# Attachment 7: Perimeter Pools Update




## LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

## GRAPHIC SCALE

100' 50' 0 100' 200'

**IN PROGRESS**
10-02-2014


# STUDY AREA 7
# PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP–1


Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4/1/2014 | | | | | | | | | | | | 4.0 | | | | | | | | | | | | | |
| 4/3/2014 | | 5.6 | 6.6 | 7.3 | 7.7 | | 7.5 | 8.3 | | | | | | | | | | | | | | | | | |
| 4/15/2014 | | 5.6 | 6.5 | 7.3 | 7.4 | 8.2 | 7.5 | 8.4 | 7.3 | | | 2.9 | 7.0 | 8.3 | 7.3 | 7.5 | | | | 7.5 | 7.9 | 7.7 | 5.9 | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | | | | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | | | | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | | | | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | | | | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | | | | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | | | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | | | | 4.1 | 6.6 | 5.9 | | 5.8 | 5.8 | 5.8 | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | | | | 5.6 | 6.6 | | | 6.0 | 5.9 | 6.5 | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | | | | 5.7 | 6.8 | | | 5.7 | 5.6 | 5.3 | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO, North FS-3 and FS-4, South FS-5


## Attachment 8: Groundwater Quality Data

(not available as of this report date - provided on a quarterly basis)

# Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)


# Attachment 10: Sheet Pile Update




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET GN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |




Time frame for:
→ 4 HB sheets driven

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 10/10/13 | TDD | RJR | TDD | SGS | RJR | SGS |
| 0 | 06/07/13 | | | | | TDD | SGS |

HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

Honeywell
101 COLUMBIA RD. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Pln Prof.dwg PLOT DATE: Mon, 07 Oct 2013 PLOT TIME: 4:04 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | | | |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | REVISION | BY | APVD |
| | TDD | DR CHK | TDD | APVD |
| | | RJR | | BCO |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105 MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS:
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWINGS, IN WHOLE OR PART, NOR THE INFORMATION THEREON, NOR TITLE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N 100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 09/13/13 | TDD | RJR | TDD | RJR | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD | SGS |
| | | REVISION | | | | BY | APVD |

1 HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 6, 2015

Type of Inspection: ☐ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☒ Other Snow Covered
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 3/6/15

SWPPP Observer: Rich Chase
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, March 06, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Additional Silt fence required along the southern toe of the 2S and 3S surcharge area. |
| 2 | IA2Q4A1AL8 | The silt bag within the storm drain at the site exit to 60 Kellogg Street needs to be repaired. |
| 3 | IA2Q4A1AL8 | Repair silt fence as required along the Northern raceway south of 1N and 2N surcharge areas. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City New Jersey

SWAP Observer: Ed Chase Date: 3/6/15
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt fence as required. | 3/11/15 RAD |
| 2 | Repair filter fabric within the catch basin located at the site exit onto 60 Kellogg. | 3/11/15 RAD |
| 3 | Repair silt fence as required. | 3/11/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: Date: 03/11/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 11, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other Snow Cover Melting
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | X | | 3 |
| Haul Road Maintenance | | X | | 4,5 |
| Perimeter Fencing/Windscreen | | X | | 6 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 7 |
| Housekeeping | | X | | 8 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 9 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/11/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Wednesday, March 11, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence is not present along the south side of the excavation area where it borders Kellogg Street |
| 2 | IA2Q4A1AL8 | Erosion control measures are not present along the southern and northern edges of Surcharge Areas 2-S and 3-S. |
| 3 | IA2Q4A1AL8 | Flood protection measures are not in place on the western end of the SA-6 South excavation area. |
| 4 | IA2Q4A1AL8 | The tracking pad at the western end of Kellogg Street is blinded with sediment. |
| 5 | IA2Q4A1AL8 | The haul road through the bottom of the SA-6 South excavation is not usable. |
| 6 | IA2Q4A1AL8 | Perimeter fence windscreen to the west of the 60 Kellogg Building requires maintenance. |
| 7 | IA2Q4A1AL8 | Storm water/snowmelt is ponded in the bottom of the SA-6 South excavation and in the bottom of the LOAM excavation. |
| 8 | IA2Q4A1AL8 | Garbage and debris has accumulated outside of the perimeter fenceline along Rt. 440 and Kellogg Street. |
| 9 | IA2Q4A1AL8 | Sediment has accumulated on the SA-7 roadway and on the western SA-7 to SA-6 North access ramp. |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 03/11/15
Signature

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt fence along the southern side of the SA-6 South excavation area as required. | 3-12-15 RAD |
| 2 | Install fabric-wrapped jersey barriers/bin blocks or hay bales along the toe of the 2-S and 3-S surcharge stockpile areas as required. | 3-17-15 RAD |
| 3 | Place flood protection measure as necessary to conform to flood protection specifications. | 3-18-15 RAD |
| 4 | Clean/replace the stone in the tracking pad as necessary to restore function. | 3-12-15 RAD |
| 5 | Re-establish the roadway in the bottom of the excavation on SA-6 South. | 3-18-15 RAD waiting for area to dry prior to building road |
| 6 | Repair/replace windscreen material as necessary. | 3-16-15 RAD |
| 7 | Continue to pump ponded storm water as required | ongoing RAD |
| 8 | Pick up garbage/debris on the outside of the SA-6 and SA-7 pereimeter fence. | 3-13-15 RAD |
| 9 | Clean SA-7 roadways of accumulated sediment. | 3-13-15 RAD |
| | | |

Construction Manager: _____ Date: 03/18/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 20, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | | X | | 3,4 |
| Ponded Storm Water | | X | | 5 |
| Housekeeping | | X | | 6 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 7 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 8 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 9 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/20/15

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, March 20, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: The haul road in the bottom of the SA-6 South excavation is not usable. |
| 2 | IA2Q4A1AL8 | A section of temporary fencing is down along the Droyer's Cove bulkhead |
| 3 | IA2Q4A1AL8 | Sediment is present on the north side of Kellogg Street by the western gate. |
| 4 | IA2Q4A1AL8 | The catch basin by the 60 Kellogg gate requires replacement of the filter fabric. |
| 5 | IA2Q4A1AL8 | Ponded storm water is present in the LOAM excavation. |
| 6 | IA2Q4A1AL8 | Geotextile fabric is lying on the ground to the west of surcharge area 1-S |
| 7 | IA2Q4A1AL8 | Silt fence at the western SA-7 to SA-6 North ramp requires maintenance. |
| 8 | IA2Q4A1AL8 | Sediment is present on the southwestern corner of the SA-7 access roadway. |
| 9 | IA2Q4A1AL8 | Broken pallets and other debris are present along the eastern SA-7 access roadway. |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 03/20/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | REPEAT: Re-establish the roadway in the bottom of the excavation on SA-6 South. | Sump installed - waiting for area to dry out |
| 2 | Re-establish a continuous fence line along the eastern edge of Droyer's Cove. | 3/23/15 RAD |
| 3 | Remove the accumulated sediment from the north side of Kellogg Street | 3/23/15 RAD |
| 4 | Replace protective filter fabric in the catch basin. | 3/23/15 RAD |
| 5 | Pump the ponded storm water as required | ongoing |
| 6 | Remove the unused protective geotextile. | 3/25/15 RAD |
| 7 | Repair/replace the silt fence as required | 3/24/15 RAD |
| 8 | Remove accumulated sediment from the access roadway | 3/24/15 RAD |
| 9 | Remove/dispose of debris. | 3/23/15 RAD |
| | | |

**Construction Manager:** _____ **Date:** 03/25/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 27, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 4 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 5 |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/27/15

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, March 27, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Orange warning fencing around the open excavation adjacent to Droyers Cove requires maintenance. |
| 2 | IA2Q4A1AL8 | **REPEAT:** Ponded storm water is present in the LOAM excavation |
| 3 | IA2Q4A1AL8 | Silt fence on the southern edge of the 1-N and 2-N surcharge areas requires maintenance. |
| 4 | IA2Q4A1AL8 | Erosion control measures (fabric-wrapped Jersey barriers or bin blocks) are not present along the eastern end of the 2-S surcharge area on the SA-7 paved access roadway. |
| 5 | IA2Q4A1AL8 | Ponded storm water is present on the access roadway in the southwest corner of SA-7 |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Signature Date: 03/27/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace orange warning fence as required. | 3-27-15 RAD |
| 2 | Pump ponded storm water from the LOAM excavation. | 3-31-15 RAD |
| 3 | Repair or replace silt fence as required. | 4-1-15 RAD |
| 4 | Relocate erosion control measures from the western roadway areas where it is no longer required to the eastern roadway. | 3-30-15 RAD |
| 5 | Remove ponded storm water, channel for future drainage. | 3-31-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 04/01/15

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (February 2015)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

March 13, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016**

Dear Mr. Caltagirone:

Honeywell is submitting the February 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely

Helen Fahy

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 2 | 01 | 15 | 2 | 28 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 75,054 | 87,385 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.47 | 0.55 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | 0.0112 | 0.0112 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1693 | 0.1693 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).


Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

3/6/15

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION**

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 2 | 01 | 15 | 2 | 28 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,101,522 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 29,168,118 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 2/18/2015 | 6.5 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE 3/6/15 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | | | | MONTH: February 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 2/1/2015 | Angel Trujillo | 27066596 | 27142124 | 75,528 | 0.075528 | 7.42 | 0.751 | | | | | | | | | 0.47 |
| 2/2/2015 | Angel Trujillo | 27142124 | 27215472 | 73,348 | 0.073348 | 7.31 | 0.751 | | | | | | | | | 0.46 |
| 2/3/2015 | Angel Trujillo | 27215472 | 27227935 | 12,463 | 0.012463 | 7.38 | 0.751 | | | | | | | | | 0.08 |
| 2/4/2015 | Angel Trujillo | 27227935 | 27272073 | 44,138 | 0.044138 | 7.44 | 0.751 | | | | | | | | | 0.28 |
| 2/5/2015 | Angel Trujillo | 27272073 | 27352314 | 80,241 | 0.080241 | 7.41 | 0.751 | | | | | | | | | 0.50 |
| 2/6/2015 | Angel Trujillo | 27352314 | 27434128 | 81,814 | 0.081814 | 7.41 | 0.751 | | | | | | | | | 0.51 |
| 2/7/2015 | Angel Trujillo | 27434128 | 27521513 | 87,385 | 0.087385 | 7.49 | 0.751 | | | | | | | | | 0.55 |
| 2/8/2015 | Angel Trujillo | 27521513 | 27599346 | 77,833 | 0.077833 | 7.50 | 0.751 | | | | | | | | | 0.49 |
| 2/9/2015 | Angel Trujillo | 27599346 | 27674819 | 75,473 | 0.075473 | 7.43 | 0.751 | | | | | | | | | 0.47 |
| 2/10/2015 | Angel Trujillo | 27674819 | 27753945 | 79,126 | 0.079126 | 7.39 | 0.751 | | | | | | | | | 0.50 |
| 2/11/2015 | Angel Trujillo | 27753945 | 27829513 | 75,568 | 0.075568 | 7.41 | 0.751 | | | | | | | | | 0.47 |
| 2/12/2015 | Angel Trujillo | 27829513 | 27913271 | 83,758 | 0.083758 | 7.46 | 0.751 | | | | | | | | | 0.52 |
| 2/13/2015 | Angel Trujillo | 27913271 | 27990053 | 76,782 | 0.076782 | 7.43 | 0.751 | | | | | | | | | 0.48 |
| 2/14/2015 | Angel Trujillo | 27990053 | 28072622 | 82,569 | 0.082569 | 7.45 | 0.751 | | | | | | | | | 0.52 |
| 2/15/2015 | Angel Trujillo | 28072622 | 28152936 | 80,314 | 0.080314 | 7.36 | 0.751 | | | | | | | | | 0.50 |
| 2/16/2015 | Angel Trujillo | 28152936 | 28224652 | 71,716 | 0.071716 | 7.41 | 0.751 | | | | | | | | | 0.45 |
| 2/17/2015 | Angel Trujillo | 28224652 | 28304897 | 80,245 | 0.080245 | 7.30 | 0.751 | | | | | | | | | 0.50 |
| 2/18/2015 | Angel Trujillo | 28304897 | 28379729 | 74,832 | 0.074832 | 7.16 | 0.751 | <5.0 | 6.5 | | <0.010 | <0.030 | 0.0112 | <0.0002 | <0.020 | 0.47 |
| 2/19/2015 | Angel Trujillo | 28379729 | 28457588 | 77,859 | 0.077859 | 7.42 | 0.751 | | | | | | | | | 0.49 |
| 2/20/2015 | Angel Trujillo | 28457588 | 28536231 | 78,643 | 0.078643 | 7.46 | 0.751 | | | | | | | | | 0.49 |
| 2/21/2015 | Angel Trujillo | 28536231 | 28616427 | 80,196 | 0.080196 | 7.46 | 0.751 | | | | | | | | | 0.50 |
| 2/22/2015 | Angel Trujillo | 28616427 | 28697543 | 81,116 | 0.081116 | 7.27 | 0.751 | | | | | | | | | 0.51 |
| 2/23/2015 | Angel Trujillo | 28697543 | 28768945 | 71,402 | 0.071402 | 7.35 | 0.751 | | | | | | | | | 0.45 |
| 2/24/2015 | Angel Trujillo | 28768945 | 28847926 | 78,981 | 0.078981 | 7.40 | 0.751 | | | | | | | | | 0.49 |
| 2/25/2015 | Angel Trujillo | 28847926 | 28927164 | 79,238 | 0.079238 | 7.45 | 0.751 | | | | | | | | | 0.50 |
| 2/26/2015 | Angel Trujillo | 28927164 | 29004030 | 76,866 | 0.076866 | 7.42 | 0.751 | | | | | | | | | 0.48 |
| 2/27/2015 | Angel Trujillo | 29004030 | 29084115 | 80,085 | 0.0801 | 7.47 | 0.751 | | | | | | | | | 0.50 |
| 2/28/2015 | Angel Trujillo | 29084115 | 29168118 | 84,003 | 0.084003 | 7.49 | 0.751 | | | | | | | | | 0.53 |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| **TOTAL** | | | | **2,101,522** | **2.101522** | | | <5.0 | 6.5 | | <0.010 | <0.030 | 0.0112 | <0.0002 | <0.020 | |
| | | | **High:** | **87,385** | | | | | | | | | | | **High:** | **0.55** |
| | | | **Average:** | **75,054** | | | | | | | | | | | **Average:** | **0.47** |

E

WW Implase.

JB88438

| Accutest Labs | Honeywell — Chain Of Custody / Analysis Request | AESI Ref: 42053.56541 |
|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | COC# 087-WW-021815 |
| Sampling Co.: MACTEC | EDD To: | Site Name: Hudson County; Phase: CS; Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | Location of Site: Jersey City, NJ; Sampling Program: 087: JCIA; Lab ID: ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | Site ID: HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | Lab Job #: HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant: CH2M | Authorized User: Honeywell |
| Preliminary Data To | | Text & Excel File Drive: Excel & Text File Order |
| Sample Receipt Acknowledgement To: Frank Schroyer | | |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | |
| Invoice To: Helen Fahy (Honeywell) | | |

Copyright AESI: Version 6.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-021815-A | 2/18/2015 | 15:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | | |
| 2 | 087-WW | | | 087-WWE-021815-B | 2/18/2015 | 15:15 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | | |
| 3 | 087-WW | | | 087-WWI-021815 | 2/18/2015 | 15:25 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | | L22 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | V59 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | A27 |
| 6 | | | | | | | | | | | | | | | | | | | | | | | M18 |
| 7 | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | |

INITIAL ASSESSMENT MBJA

LABEL VERIFICATION VM

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: Frank Schroyer — pH = 7.16 s.u. @ 6.2°C | Company: AMEC Foster Wheeler | Received by: #3 | Company | | Condition | | Custody Seals Intact | |
| Date/Time: 2/18/15 | Date/Time: 2/18/15 1730 | Date/Time: 2.18.15 1730 | | | Cooler Temp. | | | |
| Relinquished by: #3 | Company | Received by | Company | | Condition | | Custody Seals Intact | |
| Date/Time: 2-18-15 1930 | | Date/Time | | | Cooler Temp. | | | |

Preservatives: (Other; Specify):

0 (None); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

2.1°C IP

Accutest LabLink@840803 16:14 03-Mar-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021815-A | | |
| **Lab Sample ID:** | JB88438-1 | **Date Sampled:** | 02/18/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/18/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 751 | 10 | ug/l | 1 | 02/19/15 | 02/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 02/19/15 | 02/23/15 | GT | EPA 200.7 [3] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 02/19/15 | 02/23/15 | GT | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 02/19/15 | 02/19/15 | JW | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | 11.2 | 10 | ug/l | 1 | 02/19/15 | 02/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 02/19/15 | 02/20/15 | GT | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA36091
(2) Instrument QC Batch: MA36098
(3) Instrument QC Batch: MA36106
(4) Prep QC Batch: MP84931
(5) Prep QC Batch: MP84962

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@840803 16:14 03-Mar-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021815-A | | |
| **Lab Sample ID:** | JB88438-1 | **Date Sampled:** | 02/18/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/18/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 02/19/15 09:50 | JS | SM2540 D-11 |
| pH [a] | 6.96 | | su | 1 | 02/18/15 17:37 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@840803 16:14 03-Mar-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021815-A | | |
| **Lab Sample ID:** | JB88438-1A | **Date Sampled:** | 02/18/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/18/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 6.5 | 3.4 | mg/l | 1 | 02/18/15 18:39 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@840803 16:14 03-Mar-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021815-B | | |
| **Lab Sample ID:** | JB88438-2 | **Date Sampled:** | 02/18/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/18/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T205765.D | 1 | 02/20/15 | DC | n/a | n/a | VT8441 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 2.1 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.3 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.6 | 1.0 | 0.12 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.18 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.32 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.9 | 1.0 | 0.16 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.27 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.45 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.78 | ug/l | |
| 67-66-3 | Chloroform | 20.3 | 1.0 | 0.14 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.16 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.19 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.20 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.50 | 1.0 | 0.11 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.12 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.46 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.41 | 1.0 | 0.15 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.24 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 84.2 | 1.0 | 0.23 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.7 | 1.0 | 0.24 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.20 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 89 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.093 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.71 | 1.0 | 0.20 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.13 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@840803 16:14 03-Mar-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021815-B | | |
| **Lab Sample ID:** | JB88438-2 | **Date Sampled:** | 02/18/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/18/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.15 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.29 | ug/l | |
| 79-01-6 | Trichloroethene | 49.7 | 1.0 | 0.17 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.31 | ug/l | |
| 75-01-4 | Vinyl chloride | 2.0 | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.12 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 101% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 108% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 112% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@840803 16:14 03-Mar-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021815-B | | |
| **Lab Sample ID:** | JB88438-2 | **Date Sampled:** | 02/18/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/18/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 02/23/15 | BM | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending March 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**5/14/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

May 14, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-04**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from April 1 – April 30, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: April 2015 SA-6/7 Combined Monthly Progress Report No. 2015-04

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-04

**Project SA-6 & 7 Remediation**

## April 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 04/03/15 | Site 163 Post-Remediation Sampling<br>Study Area 6 South, Jersey City, New Jersey | Robert G. Torricelli<br>Office of the Special Master |
| 04/06/15 | Surcharge Monitoring Plan – Monthly Report No. 10<br>Study Area 6 North and South, Jersey City, NJ | Robert G. Torricelli<br>Office of the Special Master |
| 04/09/15 | Surcharge Monitoring Plan – Monthly Report No. 11<br>Study Area 6 North and South, Jersey City, NJ | Robert G. Torricelli<br>Office of the Special Master |
| 04/15/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights<br>Report No. 2015-03 | Robert G. Torricelli<br>Office of the Special Master |
| 04/17/15 | Sediment Remedy Long Term Monitoring Program<br>Year 1 Implementation Report<br>Study Area 7, Jersey City, NJ | Robert G. Torricelli<br>Office of the Special Master |
| 04/20/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 31630016 (current number) #20630025 (future permit ID number) | Andy Caltagirone<br>Manager of Industrial & Pollution Control<br>Passaic Valley Sewerage Commission |
| 04/20/15 | Deep Overburden Plume Groundwater Extraction and Treatment (GWET) System<br>Study Area 7, Jersey City, NJ | Robert G. Torricelli<br>Office of the Special Master |
| 04/21/15 | Special Master Conference Call | N/A |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 4/5/15 | 4/12/15 | 4/19/15 | 4/26/15 |
| **Construction Management (AMEC)** | 10 | 10 | 10 | 12 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 27 | 26 | 26 | 27 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 |
| **B&B Drilling** | 0 | 0 | 0 | 1 |
| **TOTAL STAFF** | **44** | **43** | **42** | **46** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected April PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- On April 26, 27, and 28, 2015, Cornerstone personnel conducted S-3 Mass Removal Injection Event No.20 in Injection Well 088-IW-03.
- Removed standing water from within the JCIA trash pit and discharged to PVSC through CWTP.
- Changed out pump from within the northern sump on SA-7 to increase flow to the perimeter pool system.
- The Fire Department of Jersey City (FDJC) and the Jersey City Police Department (JCPD) K-9 unit completed training activities in the former Jersey City Department of Public Works “H” Building.
- Removed trees and wood debris from south end of the Jersey City Department of Public Works “H” building into Jersey City Incinerator Authority (JCIA) roll-off boxes which were transported off site by JCIA.

- B&B Drilling completed 57 direct push soil borings and Amec Foster Wheeler collected a total of 114 soil samples at Site 163 as part of the 6-month performance assessment to monitor in-situ treatability status. The sampling included 34 borings conducted as originally proposed in the approved Work Plan and an additional 23 borings as requested by Plaintiffs.
- NJDEP visited SA-6 to inspect the location of the former SA-6 South GWTP and the former outfall discharge on April 23, 2015.
- Installed two (2) utility pole sleeves for anchors along Route 440 for future Verizon overhead line relocation activities.
- PSEG began switching power to the North Bound side of Route 440.
- Entact Installed utility pole at the northeast corner of SA-7 to power the northeast 400 amp service panel.
- Celgene soils to be used as protective cover above the geosynthetics is staged at SA-7 awaiting mobilization of screening unit.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on April 9, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 4/5/15 | 4/12/15 | 4/19/15 | 4/26/15 |
| Avg. Gallons Treated & Discharged (per day) | 76,197 | 77,987 | 78,259 | 78,438 |
| Average Flow (gpm) for Operating Period | 54 | 54 | 54 | 54 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 6,848 | 6,898 | 5,004 | 4,872 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Installed Manhole No. 2 associated with the SA-6 North Contingent Ground Water Extraction System.
- Completed loadout of non-hazardous petroleum impacted soils from SA-6 South.
- Completed compaction testing associated with bridge lift material on SA6-South.
- Began to haul screened historic fill from N1 and place it as backfill in the west side of SA-6 South backfill area.

- Began placement of soils with hexavalent chromium concentrations between 20 and 240 ppm within the sedimentation basin south of the Vertical Hydraulic Barrier Wall on SA-6 North.
- Began placement of historic fill within the sedimentation basin north of the Vertical Hydraulic Barrier Wall on SA-6 North.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-Off | TSDF | Stablex-Canada | WWTP Filter Cake | 1 | 16.79 | 16.79 |
| **Entact/ Arecon** | Tri-axle Dump | South Brunswick, NJ | MCUA | Petroleum Impacted Soil | 86 | 26.7 | 2,302.97 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | No update for the reporting period |
| **Backfill in Progress** | NJCU Borrow material - Cells (10-125), Historic Fill - Cells (10-20), (110-125) |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 4/5/15 | 4/12/15 | 4/19/15 | 4/26/15 |
| Tilcon Mt Hope DGA | 377.87 | 0 | 0 | 0 |
| Tilcon Mt. Hope 1-1.5" Stone | 300.13 | 307.14 | 0 | 263.65 |

- Historic Fill was transferred from 1N surcharge area beginning on April 7, 2015. A total of 279 loads, totaling approximately 5,580 cubic yards was placed as backfill in SA6 South during the reporting period.
- Clean borrow material (from NJCU Surcharge Program) that was stockpiled in the eastern area of SA-6 South was placed as backfill in Cells (10-125).

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging complete on Area 2S. Continue offloading Celgene and Novartis surcharge material (approximately 95% complete).
- Area 3S: Surcharge placement completed on Area 3S. MRCE peer review completed verifying that the surcharge goal had been met.

- Area 1N: Began removal of screened historic fill on April 7, 2015. Surcharge removal activities in this area are approximately 95% complete.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Began installation of surcharge monitoring instrumentation.
- Area 4N: No activity in this area pending installation of surcharge monitoring instrumentation.
- As noted in the transmittal of Surcharge Monitoring Report No. 12, we will not be submitting monthly surcharge monitoring reports until remaining instrumentation is installed in Areas 3N and 4N.

## F. SHEET PILE OPERATIONS

- Continued vertical barrier wall installation activities on SA-6 North. Installed vertical barrier wall sheet pile from, STA 5+25 to STA 3+10.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Install Vertical Hydraulic Barrier wall closure pieces associated with the connection to the exterior of the JCIA trash pit concrete walls.
- Complete water supply disconnects to the Department of Public Works "H" Building and the JCIA garage.
- Begin removal and loadout of putrescible trash within the JCIA trash pit.
- Assist JCDPW personnel in the removal of materials and equipment from the Department of Public Works "H" Building.
- Continue backfill placement activities at SA-6 South.
- Begin to install SA-6 North Contingent Ground Water Extraction System piping.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Complete the SA-6 North Bench-Scale Treatability Study for Treatment Area 10 proximate to force main.
- Continue to coordinate with the JCDPW on their off-site relocation of remaining equipment from SA-6 North.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. *Backfill Analytical Data (not included in this reporting period)*
7. Perimeter Pools Update
8. *Groundwater Quality Data (not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
11. Weekly SWPPP Reports

12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Repot (March 2015)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **Fri 1/4/08** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 753 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 151 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | Fri 11/15/13 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | Mon 6/2/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Mon 3/2/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | Mon 10/20/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | Mon 3/3/14 |
| **63** | **Barrier Wall Install** | **489 days** | **Mon 6/17/13** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **Mon 12/2/13** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | Mon 12/2/13 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | Mon 2/17/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | Mon 6/23/14 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **Mon 6/17/13** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | Mon 6/17/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | Fri 8/16/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | Thu 10/3/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | Mon 11/11/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| **64b** | **SA 6S Excavation** | **226 days** | **Tue 10/22/13** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | Tue 10/22/13 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | Fri 1/3/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | Fri 5/9/14 |
| **65** | **Backfill** | **493 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 218 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 232 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | Tue 9/1/15 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **164 days** | **Tue 9/1/15** |
| 67a | Restoration | 164 days | Tue 9/1/15 |





Project: SA-6 Remediation Schedule
Revision 3
Date: Mon 5/4/15

Task  Milestone  Summary  Critical

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start |
|---|---|---|---|
| **68** | **Demobilization** | **21 days** | **Mon 4/18/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | |
| **69** | **SA-6 North Project Closeout** | **310 days** | **Thu 10/1/15** |
| 75 | **SA-6 South Project Closeout** | **310 days** | **Thu 10/1/15** |




Project: SA-6 Remediation Schedule
Revision 3
Date: Mon 5/4/15

Task | Milestone | Summary | Critical

# Attachment 2: Site Photographs



**Site Photograph 1:** Contractor compacting fill in Kellogg Street properties.



**Site Photograph 2:** Contractor compacting material within former Sed basin.




**Site Photograph 3:** Contractor conducts drilling at Site 87.



**Site Photograph 4:** Contractor installs hydraulic barrier in former JC property.




**Photograph 5:** Contractor removes tree stumps from former JC property.





**Site Photograph 6:** Contractor removing surcharge material.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of May 1, 2015

April 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)


| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 02/26/15 | 7:30 | 14:00 | 6:30 | 27,788.98 | 27,806.88 | 17,900 | 27,806,430 | |
| 03/02/15 | 10:30 | 14:30 | 4:00 | 27,806.88 | 27,853.74 | 46,860 | 27,853,290 | |
| 03/04/15 | 7:30 | 14:00 | 6:30 | 27,853.74 | 27,955.09 | 101,350 | 27,954,640 | PVSC Compliance Sample Collected |
| 03/05/15 | 8:00 | 14:00 | 6:00 | 27,955.09 | 28,075.85 | 120,760 | 28,075,400 | |
| 03/06/15 | 7:30 | 14:30 | 7:00 | 28,075.85 | 28,200.09 | 124,240 | 28,199,640 | |
| 03/09/15 | 7:30 | 15:00 | 7:30 | 28,200.09 | 28,324.06 | 123,970 | 28,323,610 | |
| 03/10/15 | 7:30 | 15:00 | 7:30 | 28,324.06 | 28,458.25 | 134,190 | 28,457,800 | |
| 03/11/15 | 8:00 | 14:30 | 6:30 | 28,458.25 | 28,520.01 | 61,760 | 28,519,560 | |
| 03/12/15 | 9:00 | 15:00 | 6:00 | 28,520.01 | 28,571.66 | 51,650 | 28,571,210 | |
| 03/13/15 | 8:00 | 15:00 | 7:00 | 28,571.66 | 28,691.97 | 120,310 | 28,691,520 | |
| 03/14/15 | 8:00 | 16:30 | 8:30 | 28,691.97 | 28,827.02 | 135,050 | 28,826,570 | |
| 03/15/15 | 10:00 | 17:00 | 7:00 | 28,827.02 | 28,912.43 | 85,410 | 28,911,980 | |
| 03/16/15 | 7:30 | 15:15 | 7:45 | 28,912.43 | 29,086.98 | 174,550 | 29,086,530 | |
| 03/17/15 | 8:00 | 14:30 | 6:30 | 29,086.98 | 29,181.23 | 94,250 | 29,180,780 | |
| 03/18/15 | 7:30 | 15:00 | 7:30 | 29,181.23 | 29,228.98 | 47,750 | 29,228,530 | |
| 03/19/15 | 7:30 | 15:15 | 7:45 | 29,228.98 | 29,340.87 | 111,890 | 29,340,420 | |
| 03/20/15 | 8:00 | 14:00 | 6:00 | 29,340.87 | 29,436.92 | 96,050 | 29,436,470 | |
| 03/23/15 | 8:30 | 15:00 | 6:30 | 29,436.92 | 29,533.78 | 96,860 | 29,533,330 | |
| 03/24/15 | 7:30 | 15:00 | 7:30 | 29,533.78 | 29,615.04 | 81,260 | 29,614,590 | |
| 03/25/15 | 7:30 | 15:15 | 7:45 | 29,615.04 | 29,748.59 | 133,550 | 29,748,140 | |
| 03/26/15 | 7:30 | 15:30 | 8:00 | 29,748.59 | 29,862.15 | 113,560 | 29,861,700 | |
| 03/27/15 | 7:30 | 15:30 | 8:00 | 29,862.15 | 29,986.08 | 123,930 | 29,985,630 | |
| 03/28/15 | 9:00 | 15:00 | 6:00 | 29,986.08 | 30,091.41 | 105,330 | 30,090,960 | |
| 03/30/15 | 7:30 | 15:30 | 8:00 | 30,091.41 | 30,203.08 | 111,670 | 30,202,630 | |
| 03/31/15 | 7:30 | 14:30 | 7:00 | 30,203.08 | 30,378.43 | 175,350 | 30,377,980 | |
| 04/01/15 | 7:30 | 15:00 | 7:30 | 30,378.43 | 30,506.05 | 127,620 | 30,505,600 | PVSC Compliance Sample Collected |
| 04/02/15 | 7:15 | 15:15 | 8:00 | 30,506.05 | 30,637.07 | 131,020 | 30,636,620 | |
| 04/04/15 | 7:30 | 15:30 | 8:00 | 30,637.07 | 30,677.37 | 40,300 | 30,676,920 | |
| 04/06/15 | 7:00 | 15:00 | 8:00 | 30,677.37 | 30,776.12 | 98,750 | 30,775,670 | |
| 04/07/15 | 7:15 | 15:00 | 7:45 | 30,776.12 | 30,842.73 | 66,610 | 30,842,280 | |
| 04/08/15 | 7:15 | 15:00 | 7:45 | 30,842.73 | 30,910.48 | 67,750 | 30,910,030 | |
| 04/09/15 | 8:30 | 15:00 | 6:30 | 30,910.48 | 30,974.48 | 64,000 | 30,974,030 | |
| 04/10/15 | 7:30 | 15:00 | 7:30 | 30,974.48 | 31,065.01 | 90,530 | 31,064,560 | |
| 04/13/15 | 11:45 | 16:15 | 4:30 | 31,065.01 | 31,142.89 | 77,880 | 31,142,440 | |
| 04/14/15 | 7:30 | 15:00 | 7:30 | 31,142.89 | 31,231.27 | 88,380 | 31,230,820 | |
| 04/15/15 | 7:30 | 14:00 | 6:30 | 31,231.27 | 31,277.99 | 46,720 | 31,277,540 | |
| 04/17/15 | 7:15 | 12:00 | 4:45 | 31,277.99 | 31,315.22 | 37,230 | 31,314,770 | |
| 04/20/15 | 7:30 | 15:15 | 7:45 | 31,315.22 | 31,405.02 | 89,800 | 31,404,570 | |
| 04/21/15 | 7:00 | 14:00 | 7:00 | 31,405.02 | 31,446.44 | 41,420 | 31,445,990 | |
| 04/22/15 | 7:30 | 13:00 | 5:30 | 31,446.44 | 31,498.34 | 51,900 | 31,497,890 | |
| 04/23/15 | 7:00 | 13:30 | 6:30 | 31,498.34 | 31,544.28 | 97,840 | 31,543,830 | |
| 04/24/15 | 7:30 | 14:00 | 6:30 | 31,544.28 | 31,600.00 | 153,560 | 31,599,550 | |
| 04/27/15 | 7:30 | 14:30 | 7:00 | 31,600.00 | 31,637.05 | 138,710 | 31,636,600 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

(not included in this reporting period)

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
10-02-2014

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

**Table 1**

Shallow Groundwater Data

| | | | | | | | | | | 134- | 140- | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | MW-V09 | MW-06 | MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5/1/2014 | | | | | | | | | | | | 4.8 | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | | | 7.2 | | 7.3 | 7.3 | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | | | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | | | 6.0 | 7.4 | 7.4 | 6.7 | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | | | 6.0 | 7.4 | 7.2 | 6.7 | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | | | 5.6 | 7.1 | 7.1 | 6.6 | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | | | 5.5 | 7.1 | 7.1 | 6.3 | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | | | 5.3 | 7.0 | 6.8 | 6.1 | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | | | 5.1 | 6.8 | 6.7 | 6.1 | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | | | 4.8 | 6.7 | 6.3 | 5.6 | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | | | 4.8 | 6.5 | 6.1 | 5.6 | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | | | 4.7 | 6.5 | 6.0 | 5.6 | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | | | | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | | | | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | | | | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | | | | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | | | | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | | | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | | | | 4.1 | 6.6 | 5.9 | | 5.8 | 5.8 | 5.8 | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | | | | 5.6 | 6.6 | | | 6.0 | 5.9 | 6.5 | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | | | | 5.7 | 6.8 | | | 5.7 | 5.6 | 5.3 | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | | | | 5.5 | 6.8 | 6.2 | | 5.1 | 5.2 | 5.9 | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO, North FS-4, South FS-5


# Attachment 8: Groundwater Quality Data

(not available as of this report date - provided on a quarterly basis)

# Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET GN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |

| NO. | DATE | REVISION | BY | CHK |
|---|---|---|---|---|
| 1 | 10/10/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR | APVD | |
| TDD | | TDD | RJR | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Plin Prof.dwg PLOT DATE: Mon, 07 Oct 2013 PLOT TIME: 4:04 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | | RJR SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | TDD SGS |
| | | REVISION | | | BY APVD |

TDD RJR TDD BCO

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS:
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N-100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR TDD CHK RJR APVD TDD | | SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 028
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 Ainsworth Metro Blvd, Suite 113
Hasbrouck Heights, NJ 07604
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28910900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 3, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/03/15

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, April 03, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt has accumulated against the silt fence in the southeast corner of SA-7 along the Rt. 440 fenceline. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 04/03/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove the accumulated silt, maintain the silt fence as necessary and shovel up any silt which may have gotten past the silt fencing. | 4/7/15 RAS |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 04/09/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 10, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4,5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/10/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Friday, April 10, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Secondary containment of spill pallets in mechanics area has accumulated storm water. |
| 2 | IA2Q4A1AL8 | Storm water is ponded on the floor of the LOAM excavation |
| 3 | IA2Q4A1AL8 | A section of the northern toe of the 2-S stockpile area is missing erosion protection measures. |
| 4 | IA2Q4A1AL8 | Sediment has accumulated on the southwestern corner of the SA-7 access roadway. |
| 5 | IA2Q4A1AL8 | Sediment has accumulated on the northeastern corner of the SA-7 access roadway |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 04/10/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Drain the spill pallets as required. | 4/16/15 RAD |
| 2 | Pump accumulated storm water to the CWTP as required | 4/16/15 RAD |
| 3 | Install fabric-wrapped Jersey barriers or concrete bin blocks as required | 4/16/15 RAD |
| 4 | Clean sediment from the roadway. | 4/16/15 RAD |
| 5 | Clean sediment from the roadway | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 04/17/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 17, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/17/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, April 17, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence along the JCIA Rt. 440 fenceline is not toed in properly. |
| 2 | IA2Q4A1AL8 | Gaps in the trash pit safety fence are not properly protected or labelled. |
| 3 | IA2Q4A1AL8 | Sediment has accumulated on the western SA-7 access roadway. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** Signature **Date:** 04/17/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Toe in the bottom of the silt fence as required. | 4/21/15 RAD |
| 2 | Install additional barriers and signage as required to restrict access to the trash pit. | 4/21/15 RAD |
| 3 | Clean accumulated sediment from the roadway. | 4/20/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** **Date:** 04/21/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 24, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | X | | 1 |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | | X | | 4 |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/24/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, April 24, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Storm water run off has channeled and created a void in the Droyer's Cove seawall |
| 2 | IA2Q4A1AL8 | Stone and sediment are present on the west end of Kellogg Street adjacent to the western gate. |
| 3 | IA2Q4A1AL8 | Silt fence along the northern Study Area 7 roadway requires maintenance. |
| 4 | IA2Q4A1AL8 | Sediment has accumulated against the swale check dam at the southwestern corner of Study Area 7 |
| 5 | IA2Q4A1AL8 | Sediment has accumulated near the toe of the western SA-6 North to SA-7 access ramp. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ (Signature) Date: 04/24/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair the void in the Droyer's Cove bulkhead as per the engineer's specifications. | 4-26-15 RAD |
| 2 | Remove the stone and sediment from the western end of Kellogg Street. | 4-27-15 RAD |
| 3 | Repair or replace the damaged sections of silt fence as required | 4-27-15 RAD |
| 4 | Remove accumulated sediment from the back side of the southern SA-7 river discharge silt dam | 4-29-15 RAD |
| 5 | Remove accumulated sediment from the area around the toe of the SA-6N to SA-7 access ramp. | 4-29-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date 04/29/15

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (March 2015)

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 20, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 31630016 (current number) #20630025 (future permit ID number)**

Dear Mr. Caltagirone:

Honeywell is submitting the March 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

You have informed us that our Permit ID number will be changing any day now. Therefore, we have placed the future ID on the MR1 and MR2 forms along with the current ID number.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy /SCF

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 31630016 (20630025 New) OLD OUTLET DESIGNATION:

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 3 | 01 | 15 | 3 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,700 | 80,394 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.69 | 0.72 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.050 | <0.050 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1459 | 0.1459 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

## PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

April 16, 2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 31630016 **OLD OUTLET DESIGNATION** 20630025 new

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 3 | 01 | 15 | 3 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,377,687 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 31,545,805 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 3/11/2015 | <50 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE April 16, 2015 |

**PVSC FORM MR-2 REV.3 6/93**

New Permit # 20630025

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #31630016) | | | | | | | MONTH: March 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 3/1/2015 | Angel Trujillo | 29168118 | 29242408 | 74,290 | 0.07429 | 7.44 | 1.080 | | | | | | | | | 0.67 |
| 3/2/2015 | Angel Trujillo | 29242408 | 29316130 | 73,722 | 0.073722 | 7.49 | 1.080 | | | | | | | | | 0.66 |
| 3/3/2015 | Angel Trujillo | 29316130 | 29392285 | 76,155 | 0.076155 | 7.02 | 1.080 | | | | | | | | | 0.69 |
| 3/4/2015 | Angel Trujillo | 29392285 | 29471105 | 78,820 | 0.07882 | 7.28 | 1.080 | | | | | | | | | 0.71 |
| 3/5/2015 | Angel Trujillo | 29471105 | 29548254 | 77,149 | 0.077149 | 7.15 | 1.080 | | | | | | | | | 0.69 |
| 3/6/2015 | Angel Trujillo | 29548254 | 29626836 | 78,582 | 0.078582 | 7.23 | 1.080 | | | | | | | | | 0.71 |
| 3/7/2015 | Angel Trujillo | 29626836 | 29706532 | 79,696 | 0.079696 | 7.22 | 1.080 | | | | | | | | | 0.72 |
| 3/8/2015 | Angel Trujillo | 29706532 | 29783315 | 76,783 | 0.076783 | 7.13 | 1.080 | | | | | | | | | 0.69 |
| 3/9/2015 | Angel Trujillo | 29783315 | 29852950 | 69,635 | 0.069635 | 7.16 | 1.080 | | | | | | | | | 0.63 |
| 3/10/2015 | Angel Trujillo | 29852950 | 29929944 | 76,994 | 0.076994 | 7.15 | 1.080 | | | | | | | | | 0.69 |
| 3/11/2015 | Angel Trujillo | 29929944 | 30005722 | 75,778 | 0.075778 | 6.91 | 1.080 | <5.1 | <50 | | <0.010 | <0.015 | <0.050 | <0.0002 | <0.020 | 0.68 |
| 3/12/2015 | Angel Trujillo | 30005722 | 30081079 | 75,357 | 0.075357 | 7.10 | 1.080 | | | | | | | | | 0.68 |
| 3/13/2015 | Angel Trujillo | 30081079 | 30157709 | 76,630 | 0.07663 | 7.15 | 1.080 | | | | | | | | | 0.69 |
| 3/14/2015 | Angel Trujillo | 30157709 | 30238103 | 80,394 | 0.080394 | 7.16 | 1.080 | | | | | | | | | 0.72 |
| 3/15/2015 | Angel Trujillo | 30238103 | 30317291 | 79,188 | 0.079188 | 7.06 | 1.080 | | | | | | | | | 0.71 |
| 3/16/2015 | Angel Trujillo | 30317291 | 30392442 | 75,151 | 0.075151 | 7.20 | 1.080 | | | | | | | | | 0.68 |
| 3/17/2015 | Angel Trujillo | 30392442 | 30469180 | 76,738 | 0.076738 | 7.15 | 1.080 | | | | | | | | | 0.69 |
| 3/18/2015 | Angel Trujillo | 30469180 | 30546930 | 77,750 | 0.07775 | 7.45 | 1.080 | | | | | | | | | 0.70 |
| 3/19/2015 | Angel Trujillo | 30546930 | 30625760 | 78,830 | 0.07883 | 7.25 | 1.080 | | | | | | | | | 0.71 |
| 3/20/2015 | Angel Trujillo | 30625760 | 30703986 | 78,226 | 0.078226 | 7.24 | 1.080 | | | | | | | | | 0.70 |
| 3/21/2015 | Angel Trujillo | 30703986 | 30784266 | 80,280 | 0.08028 | 7.21 | 1.080 | | | | | | | | | 0.72 |
| 3/22/2015 | Angel Trujillo | 30784266 | 30861668 | 77,402 | 0.077402 | 7.21 | 1.080 | | | | | | | | | 0.70 |
| 3/23/2015 | Angel Trujillo | 30861668 | 30935174 | 73,506 | 0.073506 | 7.27 | 1.080 | | | | | | | | | 0.66 |
| 3/24/2015 | Angel Trujillo | 30935174 | 31010640 | 75,466 | 0.075466 | 7.21 | 1.080 | | | | | | | | | 0.68 |
| 3/25/2015 | Angel Trujillo | 31010640 | 31087656 | 77,016 | 0.077016 | 7.25 | 1.080 | | | | | | | | | 0.69 |
| 3/26/2015 | Angel Trujillo | 31087656 | 31164779 | 77,123 | 0.077123 | 7.22 | 1.080 | | | | | | | | | 0.69 |
| 3/27/2015 | Angel Trujillo | 31164779 | 31240856 | 76,077 | 0.0761 | 7.17 | 1.080 | | | | | | | | | 0.69 |
| 3/28/2015 | Angel Trujillo | 31240856 | 31320473 | 79,617 | 0.079617 | 7.20 | 1.080 | | | | | | | | | 0.72 |
| 3/29/2015 | Angel Trujillo | 31320473 | 31396064 | 75,591 | 0.075591 | 7.21 | 1.080 | | | | | | | | | 0.68 |
| 3/30/2015 | Angel Trujillo | 31396064 | 31469914 | 73,850 | 0.07385 | 7.13 | 1.080 | | | | | | | | | 0.67 |
| 3/31/2015 | Angel Trujillo | 31469914 | 31545805 | 75,891 | 0.075891 | 7.13 | 1.080 | | | | | | | | | 0.68 |
| TOTAL | | | | 2,377,687 | 2.377687 | | | <5.1 | <50 | | <0.010 | <0.015 | <0.050 | <0.0002 | <0.020 | |
| | | | High: | 80,394 | | | | | | | | | | | High: | 0.72 |
| | | | Average: | 76,700 | | | | | | | | | | | Average: | 0.69 |

WW

E / X 3/11/15

| Accutest Labs | Honeywell — Chain Of Custody / Analysis Request | JB89722. | AESI Ref: | 42074.49749 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC#: 087-WW-031116 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program: 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID: ACTD |
| Helen Fahy P. (973) 455-2989 E. helen.fahy@honeywell.com | PO # | | | Site ID: HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | | | Lab Job #: HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant: CH2M | | | Authorized User: Honeywell |
| Preliminary Data To | | | | Test & Excel File Drive: Excel & Test File Order |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | Units | | | | | | | | | | | | | | | | | |
| | Preservative | | | | | | | | | | | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | | | | |
| 1 | 087-WW | | | 087-WWE-031115-A | 3/11/2015 | 14:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | C31 |
| 2 | 087-WW | | | 087-WWE-031115-B | 3/11/2015 | 14:15 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | V271 |
| 3 | 087-WW | | | 087-WWI-031115 | 3/11/2015 | 14:25 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | G12 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

INITIAL ASESSMENT 1A/ek

LABEL VERIFICATION NA

| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact |
|---|---|---|---|---|---|
| Frank Schroyer — pH = 6.91 s.u. @ 6.60° C | AMEC Foster Wheeler | | | | |
| Date/Time: 3/11/15 | | | Date/Time: 3/11/15 1500 | Cooler Temp. | |
| Relinquished by | Company | Received by | Company: ACW7077 | Condition | Custody Seals Intact: N/A |
| | Date/Time: 3/11/15 1850 | | Date/Time: 3/11/15 1850 | Cooler Temp: 0.0°C-B | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE ek

Accutest LabLink@845239 10:54 01-Apr-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031115-A | | |
| **Lab Sample ID:** | JB89722-1 | **Date Sampled:** | 03/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1080 | 10 | ug/l | 1 | 03/12/15 | 03/13/15 | BS | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 03/12/15 | 03/13/15 | BS | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 03/12/15 | 03/13/15 | BS | EPA 200.7 [2] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 03/12/15 | 03/12/15 | DP | EPA 245.1 [1] | EPA 245.1 [3] |
| Nickel [b] | < 50 | 50 | ug/l | 5 | 03/12/15 | 03/13/15 | BS | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 03/12/15 | 03/13/15 | BS | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA36219
(2) Instrument QC Batch: MA36226
(3) Prep QC Batch: MP85189
(4) Prep QC Batch: MP85244

(a) Elevated detection limit due to dilution required for high interfering element.
(b) Elevated detection limit due to dilution required for matrix interference (indicated by failing internal standard on original analysis).

RL = Reporting Limit

Accutest LabLink@845239 10:54 01-Apr-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031115-A | | |
| **Lab Sample ID:** | JB89722-1 | **Date Sampled:** | 03/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 03/13/15 | JS | SM2540 D-11 |
| pH [a] | 6.84 | | su | 1 | 03/11/15 19:34 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@845239 10:54 01-Apr-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031115-A | | |
| **Lab Sample ID:** | JB89722-1A | **Date Sampled:** | 03/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 50 | 50 | mg/l | 1 | 03/12/15 19:03 | TT | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@845239 10:54 01-Apr-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031115-B | | |
| **Lab Sample ID:** | JB89722-2 | **Date Sampled:** | 03/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T206121.D | 1 | 03/12/15 | DC | n/a | n/a | VT8458 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.2 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.6 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.22 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 17.8 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.41 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.40 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 71.6 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.6 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.66 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@845239 10:54 01-Apr-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031115-B | | |
| **Lab Sample ID:** | JB89722-2 | **Date Sampled:** | 03/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 44.1 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.3 | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 101% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 98% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 104% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 102% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@845239 10:54 01-Apr-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031115-B | | |
| **Lab Sample ID:** | JB89722-2 | **Date Sampled:** | 03/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 03/15/15 | CW | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending April 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| DC 2013-7-29 | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| DC 2013-8-14 | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| DC 2013-8-14 | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| DC 2013-9-12 | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| DC 2013-9-24 | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| DC 2013-12-12 | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| DC 2014-3-25 | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| DC 2013-8-14 | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| DC 2014-5-6 | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| DC 2014-5-19 | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| DC 2014-7-28 | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| DC 2014-10-28 | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| DC 2014-8-13 | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| DC 2014-9-2 | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| DC 2014-10-31 | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| DC 2014-12-01 | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| DC 2015-01-22 | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 02 feet of historic fill soils from selected locations throughout the SA6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA6 South. | Submitted to Contractor only. |
| DC 2015-01-22 | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| DC 2015-03-03 | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. |
| DC 2015-03-30 | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to Contractor only. |
| DC 2015-03-04 | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 9 OF 25**

- **2015 Monthly Reports Part 2**

**6/12/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

June 12, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-05**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from May 1 – May 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: May 2015 SA-6/7 Combined Monthly Progress Report No. 2015-05

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2015-05
### Project SA-6 & 7 Remediation

# May 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 05/01/15 | Response to Comments provided by Terris, Pravlik & Millian, LLP<br>Surcharge Monitoring Plan Reports No. 7-9<br>Study Area 6, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/05/15 | Surcharge Monitoring Plan – Monthly Report No. 12<br>Study Area 6, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/05/15 | SA-6 North Treatment Area 10<br>Bench Scale Reactor Summary - 6 Month Reactor Data<br>Study Area 6 North, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/14/15 | Draft SA-6 South Declaration<br>Study Area 6 South, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/14/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights<br>Report No. 2015-04 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/19/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Manager of Industrial & Pollution Control<br>Passaic Valley Sewerage Commission |
| 05/19/15 | Special Master Meeting | N/A |
| 05/27/15 | SA-6N - Design Change Bulletins<br>MRCE Temporary Support of Excavation Design<br>Barrier Wall Realignment SA-6N Station 8+25<br>Study Area 6 North, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/27/15 | Response to Plaintiff May 5, 2015 Comments<br>Honeywell's April 20, 2015 proposal to install a new GWET extraction well (PW-3), in replacement of existing extraction well PW-2<br>Study Area 7, Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 05/3/2015 | 05/10/15 | 05/17/15 | 05/24/15 | 05/31/15 |
| **Construction Management (AMEC)** | 9 | 10 | 9 | 10 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 35 | 37 | 37 | 38 | 36 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 | 1 |
| **HBS (SA-6N GWTP Security System)** | 0 | 0 | 0 | 0 | 0 |
| **B&B Drilling** | 1 | 2 | 2 | 2 | 2 |
| **TOTAL STAFF** | 51 | 55 | 54 | 56 | 53 |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected May PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- On May 31, June 1, and 2, 2015, Cornerstone personnel conducted S-3 Mass Removal Injection Event No.21 in Injection Well 088-IW-02.
- Cornerstone conducted semi-annual groundwater sampling for the S-3 Mass Removal program and quarterly sampling of the GWET well discharge.
- Completed Removal of standing water and residual municipal waste from within the JCIA trash pit. The water was discharged to PVSC through CWTP and the residual municipal waste was loaded out and transported off site for disposal by JCIA.
- Assisted JCDPW personnel in the removal of materials from within the former Jersey City Department of Public Works “H” building.
- Completed water supply disconnects to the Department of Public Works “H” Building and the maintenance garage. A total of 7 lines were disconnected and capped.

- B&B drilled and grouted columns of the east and west trash pit walls for low permeability connection of the special Hydraulic Barrier Sheets.
- PSEG completed switching overhead electrical power and Cable Vision completed moving overhead telecommunication wires to the North Bound side of Route 440.
- PSEG completed installation of power to the utility pole at the northeast corner of SA-7. Century Electric completed electrical connections from the utility pole to the electrical panel at the Northeast corner of SA-7 which feeds power to the perimeter pool pump and transducer.
- **L**oaded, transported and delivered World Trade Center Beams from SA-6 north to the new Jersey City Municipal Services Complex on Linden Avenue.
- Continued to evaluate Site 163 interim in-situ treatment performance sampling data.
- Continued to stockpile Celgene material for future screening operations.
- Ordered three new Honeywell office trailers to be located at SA-6 North.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on May 18, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 05/3/15 | 05/10/15 | 05/17/15 | 05/24/15 | 05/31/15 |
| Avg. Gallons Treated & Discharged (per day) | 77,624 | 77,562 | 77,850 | 78,263 | 76,616 |
| Average Flow (gpm) for Operating Period | 56 | 54 | 54 | 54 | 55 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 7,133 | 6,600 | 7,601 | 9,122 | 9,738 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued installation of SA-6 North Contingent Ground Water Extraction System piping. A total of 700 linear feet of piping and one access manhole was installed
- Installed Catch Basin 5 in the SA-6 South backfill area along Kellogg Street, to include a total of 200 linear feet of piping.
- Continued to haul screened historic fill from N1 and place it as backfill in the west side of SA-6 South backfill area.

- Continued placement of soils with hexavalent chromium concentrations between 20 and 240 ppm within the sedimentation basin south of the Vertical Hydraulic Barrier Wall on SA-6 North.
- Continued placement of historic fill within the sedimentation basin north of the Vertical Hydraulic Barrier Wall on SA-6 North.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| No update for the reporting period | | | | | | | |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | No update for the reporting period |
| **Backfill in Progress** | Historic Fill - SA6 South western backfill area. |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 05/3/15 | 05/10/15 | 05/17/15 | 05/24/15 | 05/31/15 |
| Tilcon Mt Hope DGA | 620 | 0 | 0 | 0 | 0 |
| Tilcon Mt. Hope 3/8" Stone | 0 | 0 | 182 | 0 | 0 |
| Tilcon Mt. Hope 1-1.5" Stone | 0 | 308 | 0 | 333 | 0 |

- Historic Fill was transferred from 1N surcharge area beginning on April 7, 2015. A total of 118 loads, totaling approximately 2,360 cubic yards was placed as backfill in SA-6 South during the reporting period.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Begin surcharge removal. Offloading Novartis and relocating 20 to 240 ppm material to SA-6 North cap area (approximately 60% complete).
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Continued installation of surcharge monitoring instrumentation.
- Area 4N: Began installation of surcharge monitoring instrumentation.

- As noted in the transmittal of Surcharge Monitoring Report No. 12, we will not be submitting monthly surcharge monitoring reports until remaining instrumentation is installed in Areas 3N and 4N.

## F. SHEET PILE OPERATIONS

- Installed Vertical Hydraulic Barrier wall closure pieces associated with the connection to the exterior of the JCIA trash pit concrete walls.

## G. CAPPING OPERATIONS

- Continued general Cap Subgrade preparation in Area 1S.
- Continued Utility Corridor and roadway subgrade preparation.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 7/7/2015 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete set up Traffic Controls and Southbound shoulder closure associated with excavations along Route 440 frontage with SA-6 North in accordance with the NJDOT permit.
- Begin excavation of Areas EA-7 and EA-8.
- Begin pre-trenching for installation of temporary shoring related to the excavations along Route 440.
- Begin Soldier Pile installation associated with the temporary shoring along Route 440.
- Continue Cap Subgrade and utility corridor preparation activities.
- Verizon will complete switching communication lines to the North Bound side of Route 440.
- Begin Stratum D repair of the JCIA Trash Pit Area.
- Continue backfill placement activities at SA-6 South.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Develop the revised plan for the SA-6 North Treatment Area 10 proximate to force main.
- Complete the L-Well sampling of locations where geoprobe is required.
- Continue to work with owner on access for the planned PW-3 extraction well installation.

**ATTACHMENTS:**


1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. *Backfill Analytical Data (not included in this reporting period)*
7. Perimeter Pools Update
8. *Groundwater Quality Data (not included in this reporting period)*
9. Surcharge Monitoring Update
10. Sheet Pile Update

11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (April 2015)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **1/4/08** | **3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **8/11/08** | **3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | 10/17/11 | 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | 9/1/14 | 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **3/1/13** | **5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | 6/17/13 | 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | 11/15/13 | 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **6/17/13** | **10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | 6/2/14 | 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 3/2/15 | 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | 10/20/14 | 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | 3/3/14 | 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **6/17/13** | **4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **12/2/13** | **4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | 12/2/13 | 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | 2/17/14 | 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | 6/23/14 | 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **6/17/13** | **5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | 6/17/13 | 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | 8/16/13 | 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | 10/3/13 | 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | 11/11/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **10/22/13** | **9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | 10/22/13 | 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | 1/3/14 | 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | 5/9/14 | 9/2/14 |
| **65** | **Backfill** | **493 days** | **11/11/13** | **9/30/15** |
| 65a | SA 6N Backfill | 218 days | 12/1/14 | 9/30/15 |
| 65b | SA 6S Backfill | 232 days | 11/11/13 | 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **12/1/14** | **2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | 9/1/15 | 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **164 days** | **9/1/15** | **4/15/16** |
| 67a | Restoration | 164 days | 9/1/15 | 4/15/16 |




Project: SA-6 Remediation Schedule
Revision 3
Date: 6/2/15

Task  Milestone  Summary  Critical

Note: The schedule will be revised following completion of the JCDPW relocation.


Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



amec foster wheeler

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **68** | **Demobilization** | **21 days** | **4/18/16** | **5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **310 days** | **10/1/15** | **12/7/16** |
| 75 | **SA-6 South Project Closeout** | **310 days** | **10/1/15** | **12/7/16** |




Project: SA-6 Remediation Schedule
Revision 3
Date: 6/2/15

Task Milestone Summary Critical

Note: The schedule will be revised following completion of the JCDPW relocation.

# Attachment 2: Site Photographs



**Site Photograph 1:** Contractor compacting material on former City properties.




**Site Photograph 2:** Contract removing tree stumps from the former City properties.



**Site Photograph 3:** Contractor compacting screened historic fill.




**Site Photograph 4:** Contractor conducts drilling at former JCIA property.



**Photograph 5:** Contractor installs hydraulic barrier at former JCIA property.




**Site Photograph 6:** Contractor loading surcharge material.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of June 1, 2015

May 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 04/01/15 | 7:30 | 15:00 | 7:30 | 30,378.43 | 30,506.05 | 127,620 | 30,505,600 | PVSC Compliance Sample Collected |
| 04/02/15 | 7:15 | 15:15 | 8:00 | 30,506.05 | 30,637.07 | 131,020 | 30,636,620 | |
| 04/04/15 | 7:30 | 15:30 | 8:00 | 30,637.07 | 30,677.37 | 40,300 | 30,676,920 | |
| 04/06/15 | 7:00 | 15:00 | 8:00 | 30,677.37 | 30,776.12 | 98,750 | 30,775,670 | |
| 04/07/15 | 7:15 | 15:00 | 7:45 | 30,776.12 | 30,842.73 | 66,610 | 30,842,280 | |
| 04/08/15 | 7:15 | 15:00 | 7:45 | 30,842.73 | 30,910.48 | 67,750 | 30,910,030 | |
| 04/09/15 | 8:30 | 15:00 | 6:30 | 30,910.48 | 30,974.48 | 64,000 | 30,974,030 | |
| 04/10/15 | 7:30 | 15:00 | 7:30 | 30,974.48 | 31,065.01 | 90,530 | 31,064,560 | |
| 04/13/15 | 11:45 | 16:15 | 4:30 | 31,065.01 | 31,142.89 | 77,880 | 31,142,440 | |
| 04/14/15 | 7:30 | 15:00 | 7:30 | 31,142.89 | 31,231.27 | 88,380 | 31,230,820 | |
| 04/15/15 | 7:30 | 14:00 | 6:30 | 31,231.27 | 31,277.99 | 46,720 | 31,277,540 | |
| 04/17/15 | 7:15 | 12:00 | 4:45 | 31,277.99 | 31,315.22 | 37,230 | 31,314,770 | |
| 04/20/15 | 7:30 | 15:15 | 7:45 | 31,315.22 | 31,405.02 | 89,800 | 31,404,570 | |
| 04/21/15 | 7:00 | 14:00 | 7:00 | 31,405.02 | 31,446.44 | 41,420 | 31,445,990 | |
| 04/22/15 | 7:30 | 13:00 | 5:30 | 31,446.44 | 31,498.34 | 51,900 | 31,497,890 | |
| 04/23/15 | 7:00 | 13:30 | 6:30 | 31,498.34 | 31,544.28 | 45,940 | 31,543,830 | |
| 04/24/15 | 7:30 | 14:00 | 6:30 | 31,544.28 | 31,600.00 | 55,720 | 31,599,550 | |
| 04/27/15 | 7:30 | 14:30 | 7:00 | 31,600.00 | 31,637.05 | 37,050 | 31,636,600 | |
| 04/29/15 | 9:30 | 15:00 | 5:30 | 31,637.05 | 31,706.56 | 69,510 | 31,706,110 | |
| 04/30/15 | 8:00 | 15:00 | 7:00 | 31,706.56 | 31,755.10 | 48,540 | 31,754,650 | |
| 05/01/15 | 10:00 | 14:30 | 4:30 | 31,755.10 | 31,779.92 | 24,820 | 31,779,470 | |
| 05/05/15 | 7:00 | 14:00 | 7:00 | 31,779.92 | 31,862.76 | 82,840 | 31,862,310 | PVSC Compliance Sample Collected |
| 05/08/15 | 7:30 | 14:30 | 7:00 | 31,862.76 | 31,923.11 | 60,350 | 31,922,660 | |
| 05/11/15 | 10:00 | 15:00 | 5:00 | 31,923.11 | 31,978.26 | 55,150 | 31,977,810 | |
| 05/14/15 | 10:00 | 15:00 | 5:00 | 31,978.26 | 32,016.71 | 38,450 | 32,016,260 | |
| 05/18/15 | 7:30 | 14:30 | 7:00 | 32,016.71 | 32,102.90 | 86,190 | 32,102,450 | |
| 05/19/15 | 7:30 | 14:00 | 6:30 | 32,102.90 | 32,136.78 | 33,880 | 32,136,330 | |
| 05/20/15 | 7:30 | 15:00 | 7:30 | 32,136.78 | 32,157.02 | 20,240 | 32,156,570 | |
| 05/21/15 | 7:00 | 13:30 | 6:30 | 32,157.02 | 32,194.76 | 37,740 | 32,194,310 | |
| 05/22/15 | 8:00 | 12:00 | 4:00 | 32,194.76 | 32,208.64 | 13,880 | 32,208,190 | |
| 05/24/15 | 10:00 | 14:00 | 4:00 | 32,208.64 | 32,256.26 | 47,620 | 32,255,810 | |
| 05/27/15 | 6:30 | 13:30 | 7:00 | 32,256.26 | 32,322.85 | 66,590 | 32,322,400 | |
| 05/29/15 | 10:00 | 14:15 | 4:15 | 32,322.85 | 32,377.97 | 55,120 | 32,377,520 | |

Notes: Previous information is trunkated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

(not included in this reporting period)

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'

N4 N3 N2 N1 E1 E2 S4 S3 S2 S1

087-MW-Y20 087-MW-S19 NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1 117-MW-A99 117-MW-A85 117-MW-A89

W6-SO W1-SO S-C-B BARRIER (TYP.) E5-SO E4-SO E3-SO E2-SO E1-SO W3-SO W5-SO

115-PZ-6 115-PZ-5 115-PZ-4

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH FS-7 SOUTH-FS-5 SOUTH-FS-6

073-MW-BB11 073-MW-Y10 134-MW-V09 134-MW-Q08 140-MW-06 140-MW-07 125-MW-L03 MW-124-103L MW-124-102D MW-124-103D MW-124-102T

STA. N11+10 STA. N15+35 STA. N16+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. E3+75 STA. E4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+38 STA. S3+85 STA. S0+50

KELLOGG STREET

STATE ROUTE 3 (MEADOWLANDS PARKWAY)

LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE
100' 50' 0 100' 200'

IN PROGRESS
10-02-2014


STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Oct 03, 2014 at 10:39am
G:\DWGS\102\10210\Dewatering\PP-1.dwg
edelossantos





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

**Table 1**

Shallow Groundwater Data

| | | | | | | | | | | | North | | | | | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | 140-MW-07 | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-8 | FS-9 | FS-10 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5/1/2014 | | | | | | | | | | 4.8 | | | | | | | | | | | | | | | | | |
| 5/5/2014 | | 5.5 | 6.7 | 7.0 | 8.0 | 7.5 | | 8.6 | 7.1 | | 7.2 | | 7.3 | 7.3 | | | | | | | | 7.7 | 8.1 | 7.9 | 7.2 | | |
| 5/15/2014 | | 5.7 | 6.6 | 7.3 | 7.2 | | 5.4 | 8.0 | 6.5 | 3.5 | 6.3 | 7.4 | 8.0 | 6.9 | | | | | | | | 7.6 | 7.8 | 7.6 | 8.0 | | |
| 6/2/2014 | | 5.6 | 6.5 | 7.1 | 6.8 | | 6.7 | 8.4 | 6.3 | | 6.0 | 7.4 | 7.4 | 6.7 | | | | | | | | 7.4 | 8.0 | 8.0 | 8.6 | | |
| 6/16/2014 | | 5.7 | 6.5 | 7.1 | 7.3 | | 4.6 | 9.1 | 6.4 | | 6.0 | 7.4 | 7.2 | 6.7 | | | | | | | | 7.4 | 8.4 | 8.4 | 9.4 | | |
| 6/30/2014 | | 5.5 | 6.4 | 6.9 | 6.7 | | 3.9 | 8.6 | 5.9 | | 5.6 | 7.1 | 7.1 | 6.6 | | | | | | | | 6.1 | 7.9 | 7.6 | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | | 4.2 | | 5.9 | | 5.5 | 7.1 | 7.1 | 6.3 | | | | | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | | 3.1 | | 5.6 | | 5.3 | 7.0 | 6.8 | 6.1 | | | | | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | | 2.8 | | 5.5 | | 5.1 | 6.8 | 6.7 | 6.1 | | | | | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | | 2.7 | 5.6 | 5.2 | | 4.8 | 6.7 | 6.3 | 5.6 | | | | | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | | 2.6 | 5.0 | 5.1 | | 4.8 | 6.5 | 6.1 | 5.6 | | | | | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | | 2.6 | 3.6 | 5.0 | | 4.7 | 6.5 | 6.0 | 5.6 | | | | | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | | 2.3 | 3.0 | 5.0 | | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | | | | | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | | | | | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | | | | | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | | | | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | | | | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | | | | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | | | | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | | | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | | | | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | | 4.1 | 6.6 | 5.9 | | 5.8 | 5.8 | 5.8 | | | | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | | 5.6 | 6.6 | | | 6.0 | 5.9 | 6.5 | | | | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | | 5.7 | 6.8 | | | 5.7 | 5.6 | 5.3 | | | | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | | 5.5 | 6.8 | 6.2 | | 5.1 | 5.2 | 5.9 | | | | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | | 5.6 | 6.8 | 6.2 | | 5.3 | 5.2 | 5.7 | | 1.8 | | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | | 5.4 | 6.2 | 5.8 | | 4.9 | 4.9 | 5.2 | 4.5 | 2.8 | 3.0 | 5.3 | | | | 2.8 | 3.5 | 2.8 |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.


The following wells have been abandoned:
South FS-1, FS-3, FS-4, FS-5.

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO, North FS-4, South FS-5

# Attachment 8: Groundwater Quality Data

(not available as of this report date - provided on a quarterly basis)

# Attachment 9: Surcharge Monitoring Update




Installed Instrumentation Locations

Instrumentation Locations Not Installed

| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS8 | 685406.37 | 603094.37 |
| FS9 | 685500.70 | 603127.22 |
| FS10 | 685858.02 | 603165.50 |
| FS11 | 685387.04 | 603338.90 |
| HS10 | 685499.90 | 603327.97 |
| HS11 | 685328.97 | 603205.81 |
| HS12 | 685428.53 | 603407.96 |
| HS13 | 685253.14 | 603316.22 |
| SP21 | 685302.66 | 603197.35 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
6. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| I-2 | INCLINOMETER LOCATION |
| FS-1-1 | SETTLEMENT MONITORING POINT FULL - SET UP |
| HS-1-1 | SETTLEMENT MONITORING POINT HALF - SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

Prepared/Date: RJR 07/19/2013
Checked/Date: AE 07/19/2013

0 15 30 60
SCALE IN FEET


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 3N
Project 3480-09-0068
Figure D1


# Attachment 10: Sheet Pile Update




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET GN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |




| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 10/10/13 | TDD | RJR | TDD | SGS | RJR |
| 0 | 06/07/13 | TDD | RJR | TDD | SGS | TDD |

HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Pln Prof.dwg PLOT DATE: Mon, 07 Oct 2013 PLOT TIME: 4:04 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/13/13 | TDD | RJR | TDD | BCO |
| 0 | 06/07/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | | |
| | | ISSUED FOR CONSTRUCTION | | | |
| | | REVISION | | BY | APVD |

RJR SGS
TDD SGS

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTABLE IDEAS, AND/OR COMMERCIAL INFORMATION AND USE IS CONDITIONED UPON THE AGREEMENT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, OR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N-100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/13/13 | TDD | RJR | RJR | TDD |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | |

1 HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM — RJR SGS
BY APVD

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2629
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG SN-203
SHEET 56 OF 70

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 1, 2015**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | | X | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/01/15

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 01, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The silt fence at the eastern end if SA-6 South adjacent to Route 440 requires maintenance. |
| 2 | IA2Q4A1AL8 | Erosion protection measures are absent along the northern edge if surcharge area 3-S. |
| 3 | IA2Q4A1AL8 | Discarded silt fence is piled on the northwest corner if SA-7 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Signature Date: 05/01/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace silt fence as required. | 5-7-15 (240) |
| 2 | Install fabric-wrapped Jersey barriers or concrete bin blocks along the toe of the surcharge area as required. | 5-6-15 RJD |
| 3 | Remove the pile if discarded silt fence. | 5-5-15 RJD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 05/07/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 8, 2015**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/08/15

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, May 08, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Filter fabric in the stormwater catch basins located by the southwestern corner of of the trash pit and by the southern JCIA Rt. 440 gate requires changing due to sediment build-up and/or perforation. |
| 2 | IA2Q4A1AL8 | Sweepings on the eastern Study Area 7 roadway have not been picked up. |
| 3 | IA2Q4A1AL8 | Filter fabric in the stormwater catch basins located to the north and south of the SA-7 scalehouse have sediment build-up and/or perforation. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Signature Date 05/08/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace filter fabric in the two catch basins as required | 5/11/15 RAD |
| 2 | Remove the two piles of sediment/debris sweepings from the eastern SA-7 roadway. | 5/12/15 RAD |
| 3 | Replace filter fabric in the two catch basins as required | 5/13/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 05/14/15

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 15, 2015**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/15/15

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, May 15, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence had degraded along the bottom of the perimeter fence to the east of the 60 Kellogg building |
| 2 | IA2Q4A1AL8 | Windscreen has blown loose from the perimeter fence at the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | A pile of material left over from the conduit re-routing in the northeastern corner of Study Area 7 has not been removed from the SA-7 paved roadway. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Signature Date: 05/15/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the degraded silt fence on the perimeter fence east of 60 Kellogg. | 5-19-15 RAD |
| 2 | Re-attach windscreen along the Kellogg Street jughandle as required | 5-18-15 RAD |
| 3 | Remove the remaining pile of material in the northeast corner of SA-7 | 5-18-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 05/21/15

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 22, 2015**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 2 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 5 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/22/15

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 22, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing has fallen down at a location on the southern perimeter of Surcharge Area 2-S. |
| 2 | IA2Q4A1AL8 | Containment measure along the northern perimeter of the Exclusion Zone on Surcharge Area 2-S are inadequate. |
| 3 | IA2Q4A1AL8 | The perimeter fencing between the SA-6 North work area and the MUA property has several gaps. |
| 4 | IA2Q4A1AL8 | A pile of debris (old silt fence, etc.) is present on the far northeastern corner of the JCIA property |
| 5 | IA2Q4A1AL8 | Sediment has overtopped the silt fence on the northern side of the Novartis stockpile area Plastic-wrapped hay bales have degraded on the southern side and are no longer effective for erosion control. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** Signature **Date:** 05/27/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair the orange Exclusion Zone fencing as requried. | 5/27/15 RAD |
| 2 | Install sediment control measures as per contract specifications. | 5/27/15 RAD |
| 3 | Reposition the fence-topped Jersey barriers or install temporary fence panels as needed to close the gaps in the fenceline. | 5/28/15 RAD |
| 4 | Remove the debris pile. | 5/28/15 RAD |
| 5 | Maintain, install or repair erosion control measures as required. | 5/29/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** **Date:** 05/29/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: May 29, 2015**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 05/29/15

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 29, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fencing along the southern perimeter of surcharge area 3-S requires maintenance. |
| 2 | IA2Q4A1AL8 | Windscreen on the perimeter fenceline at the Kellogg Street jughandle has torn loose and requires maintenance. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing on the western perimeter of the sedimentation basin EZ requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 05/29/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair the silt fencing as required. | 6/1/15 RAD |
| 2 | Repair and re-attach windscreen material as required. | 6/2/15 RAD |
| 3 | Repair the orange Exclusion Zone fencing as requried. | 6/3/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 06/03/15

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (April 2015)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

May 19, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the April 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 4 | 01 | 15 | 4 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow gal/day~~ | | |
| Total Flow-gal/day | 77,680 | 84,026 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.50 | 0.55 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1378 | 0.1378 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

5/15/15

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 4 | 01 | 15 | 4 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,330,414 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 33,876,219 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 4/9/2015 | <20 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE 5/15/15 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | | | | | MONTH: April, 2015 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 4/1/2015 | Angel Trujillo | 31545805 | 31620433 | 74,628 | 0.074628 | 7.14 | 0.778 | | | | | | | | | 0.48 |
| 4/2/2015 | Angel Trujillo | 31620433 | 31691737 | 71,304 | 0.071304 | 7.64 | 0.778 | | | | | | | | | 0.46 |
| 4/3/2015 | Angel Trujillo | 31691737 | 31770247 | 78,510 | 0.07851 | 7.60 | 0.778 | | | | | | | | | 0.51 |
| 4/4/2015 | Angel Trujillo | 31770247 | 31853193 | 82,946 | 0.082946 | 7.52 | 0.778 | | | | | | | | | 0.54 |
| 4/5/2015 | Angel Trujillo | 31853193 | 31929866 | 76,673 | 0.076673 | 7.48 | 0.778 | | | | | | | | | 0.50 |
| 4/6/2015 | Angel Trujillo | 31929866 | 32003294 | 73,428 | 0.073428 | 7.53 | 0.778 | | | | | | | | | 0.48 |
| 4/7/2015 | Angel Trujillo | 32003294 | 32080391 | 77,097 | 0.077097 | 7.57 | 0.778 | | | | | | | | | 0.50 |
| 4/8/2015 | Angel Trujillo | 32080391 | 32156632 | 76,241 | 0.076241 | 7.41 | 0.778 | | | | | | | | | 0.49 |
| 4/9/2015 | Angel Trujillo | 32156632 | 32234984 | 78,352 | 0.078352 | 6.93 | 0.778 | <5.0 | <20 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.51 |
| 4/10/2015 | Angel Trujillo | 32234984 | 32313569 | 78,585 | 0.078585 | 7.57 | 0.778 | | | | | | | | | 0.51 |
| 4/11/2015 | Angel Trujillo | 32313569 | 32397270 | 83,701 | 0.083701 | 7.54 | 0.778 | | | | | | | | | 0.54 |
| 4/12/2015 | Angel Trujillo | 32397270 | 32474170 | 76,900 | 0.0769 | 7.58 | 0.778 | | | | | | | | | 0.50 |
| 4/13/2015 | Angel Trujillo | 32474170 | 32549207 | 75,037 | 0.075037 | 7.61 | 0.778 | | | | | | | | | 0.49 |
| 4/14/2015 | Angel Trujillo | 32549207 | 32627564 | 78,357 | 0.078357 | 7.53 | 0.778 | | | | | | | | | 0.51 |
| 4/15/2015 | Angel Trujillo | 32627564 | 32705759 | 78,195 | 0.078195 | 7.54 | 0.778 | | | | | | | | | 0.51 |
| 4/16/2015 | Angel Trujillo | 32705759 | 32785297 | 79,538 | 0.079538 | 7.62 | 0.778 | | | | | | | | | 0.52 |
| 4/17/2015 | Angel Trujillo | 32785297 | 32863528 | 78,231 | 0.078231 | 7.60 | 0.778 | | | | | | | | | 0.51 |
| 4/18/2015 | Angel Trujillo | 32863528 | 32940401 | 76,873 | 0.076873 | 7.64 | 0.778 | | | | | | | | | 0.50 |
| 4/19/2015 | Angel Trujillo | 32940401 | 33021305 | 80,904 | 0.080904 | 7.60 | 0.778 | | | | | | | | | 0.52 |
| 4/20/2015 | Angel Trujillo | 33021305 | 33097022 | 75,717 | 0.075717 | 7.54 | 0.778 | | | | | | | | | 0.49 |
| 4/21/2015 | Angel Trujillo | 33097022 | 33173755 | 76,733 | 0.076733 | 7.56 | 0.778 | | | | | | | | | 0.50 |
| 4/22/2015 | Angel Trujillo | 33173755 | 33253928 | 80,173 | 0.080173 | 7.55 | 0.778 | | | | | | | | | 0.52 |
| 4/23/2015 | Angel Trujillo | 33253928 | 33332479 | 78,551 | 0.078551 | 7.30 | 0.778 | | | | | | | | | 0.51 |
| 4/24/2015 | Angel Trujillo | 33332479 | 33410332 | 77,853 | 0.077853 | 7.56 | 0.778 | | | | | | | | | 0.51 |
| 4/25/2015 | Angel Trujillo | 33410332 | 33490031 | 79,699 | 0.079699 | 7.58 | 0.778 | | | | | | | | | 0.52 |
| 4/26/2015 | Angel Trujillo | 33490031 | 33567787 | 77,756 | 0.077756 | 7.52 | 0.778 | | | | | | | | | 0.50 |
| 4/27/2015 | Angel Trujillo | 33567787 | 33646091 | 78,304 | 0.0783 | 7.59 | 0.778 | | | | | | | | | 0.51 |
| 4/28/2015 | Angel Trujillo | 33646091 | 33715172 | 69,081 | 0.069081 | 7.59 | 0.778 | | | | | | | | | 0.45 |
| 4/29/2015 | Angel Trujillo | 33715172 | 33799198 | 84,026 | 0.084026 | 7.64 | 0.778 | | | | | | | | | 0.55 |
| 4/30/2015 | Angel Trujillo | 33799198 | 33876219 | 77,021 | 0.077021 | 7.54 | 0.778 | | | | | | | | | 0.50 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,330,414 | 2.330414 | | | <5.0 | <20 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 84,026 | | | | | | | | | | | High: | 0.55 |
| | | | Average: | 77,680 | | | | | | | | | | | Average: | 0.50 |

WW

JB 92002

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42103.47186 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-040915 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087. JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P (973) 455-2989 F: helen.fahy@honeywell.com | PO # | Preservative 3 | 3 3 1 2 2 0 0 2 | Site ID HudsonCo |
| Honeywell International<br>101 Columbia Road Morristown, NJ 07962 | Analysis Turnaround Time (TAT): 3<br>Consultant CH2M | | | Lab Job # HWINJM32815 |
| Preliminary Data To | | | | Authorized User: Honeywell |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | Text & Excel File Drive / Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-040915-A | 4/9/2015 | 14:15 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | C38 |
| 2 | 087-WW | | | 087-WWE-040915-B | 4/9/2015 | 14:30 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | V683 |
| 3 | 087-WW | | | 087-WWI-040915 | 4/9/2015 | 14:40 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | A10 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | G13 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: 6.93 SH @ 7.7°C | Company: AMEC Foster Wheeler | Received by: | Company: | | Condition: | | Custody Seals Intact: | |
| Frank Schroyer | Date/Time: 4/9/15 1530 | | Date/Time: 4/9/15 1530 | | Cooler Temp: | | | |
| Relinquished by: | Company: | Received by: | Company: Accutest | | Condition: | | Custody Seals Intact: | |
| | Date/Time: 4/9/15 1640 | | Date/Time: 4/9/15 1640 | | Cooler Temp: | 2.0°C-B | | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2), 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

INITIAL ASESSMENT JF 3B

LABEL VERIFICATION

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE JK

Accutest LabLink@851976 13:21 08-May-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-040915-A | | |
| **Lab Sample ID:** | JB92002-1 | **Date Sampled:** | 04/09/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/09/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 778 | 10 | ug/l | 1 | 04/10/15 | 04/11/15 | VC | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 04/10/15 | 04/13/15 | VC | EPA 200.7 [3] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 04/10/15 | 04/13/15 | VC | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 04/10/15 | 04/10/15 | MA | EPA 245.1 [1] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 04/10/15 | 04/11/15 | VC | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 04/10/15 | 04/11/15 | VC | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA36404
(2) Instrument QC Batch: MA36406
(3) Instrument QC Batch: MA36416
(4) Prep QC Batch: MP85722
(5) Prep QC Batch: MP85742

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@851976 13:21 08-May-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-040915-A | | |
| **Lab Sample ID:** | JB92002-1 | **Date Sampled:** | 04/09/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/09/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 04/13/15 | KP | SM2540 D-11 |
| pH [a] | 7.05 | | su | 1 | 04/09/15 16:57 | JK | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@851976 13:21 08-May-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-040915-A | | |
| **Lab Sample ID:** | JB92002-1A | **Date Sampled:** | 04/09/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/09/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 20 | 20 | mg/l | 1 | 04/09/15 20:43 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@851976 13:21 08-May-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-040915-B | | |
| **Lab Sample ID:** | JB92002-2 | **Date Sampled:** | 04/09/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/09/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N244722.D | 1 | 04/14/15 | DC | n/a | n/a | VN10376 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 1.9 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.3 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.22 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 16.3 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.37 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.30 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 66.2 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.1 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.57 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@851976 13:21 08-May-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-040915-B | | |
| **Lab Sample ID:** | JB92002-2 | **Date Sampled:** | 04/09/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/09/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 44.3 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.2 | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 104% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 96% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 101% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 104% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@851976 13:21 08-May-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-040915-B | | |
| **Lab Sample ID:** | JB92002-2 | **Date Sampled:** | 04/09/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/09/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 04/13/15 19:30 | LS | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending May 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending May 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**7/14/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

July 14, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-06**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from June 1 – June 30, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: June 2015 SA-6/7 Combined Monthly Progress Report No. 2015-06

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Dr. Bruce Bell - Carpenter Environmental Associates, Inc. (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)

Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-06

**Project SA-6 & 7 Remediation**

## June 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/10/15 | Summary of 6-Month Performance Assessment Soil Sampling of Hexavalent Chromium Impacted Soils<br>Study Area 6 South, Site 163<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/11/15 | Sediment Remedy Long Term Monitoring Program Year 1 Implementation Report<br>Study Area 7<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/12/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Combined Monthly Progress/Highlights Report No. 2015-05<br>Study Areas 6 and 7<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/18/15 | Integrated Annual Groundwater Performance Report for 2014<br>Study Areas 5, 6, and 7<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/18/15 | Design Change Bulletin<br>SA-6 South Open Space Design Utility Corridor Modification<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/22/15 | Summary of Proposed Additional In-Situ Injection of Calcium Polysulfide for Treatment of Chromium Impacted Soils<br>Study Area 6 South, Site 163<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/22/15 | Summary of Proposed In-Situ Injection of Calcium Polysulfide for Treatment of Chromium Impacted Soils – Area 10 North Section<br>Study Area 6 North, Site 087<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/22/15 | Revised Master Schedule<br>Study Area 6 North and South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/22/15 | Upload to LB SharePoint Site:<br>Ramboll Environ Correspondence:<br>Request for Pre-Application Meeting<br>Waterfront Development Permit<br>SA-7 Beneficial Environmental Project<br>Pedestrian Bridge Element<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/22/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 06/23/15 | Special Master Conference Call | N/A |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 7/7/15 | 7/14/15 | 7/21/15 | 7/28/15 |
| **Construction Management (AMEC)** | 9 | 8 | 8 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 31 | 33 | 33 | 37 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 2 | 1 | 0 | 0 |
| **TOTAL STAFF** | 48 | 48 | 47 | 52 |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.

- Collected June PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Verizon continued relocating communication lines to the North Bound side of Route 440.
- On, June 1 and 2, 2015, Cornerstone personnel completed S-3 Mass Removal Injection Event No. 21 in Injection Well 088-IW-02.
- Cornerstone conducted a round of quarterly ground water level measurements.
- Continued to stockpile Celgene material for future screening operations.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on June 11, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 7/7/2015 | 714/2015 | 7/21/2015 | 7/28/2015 |
| Avg. Gallons Treated & Discharged (per day) | 77,715 | 77,015 | 77,664 | 75,857 |
| Average Flow (gpm) for Operating Period | 54 | 54 | 54 | 53 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 7,092 | 7,003 | 8,498 | 7,336 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed excavation activities associated with Area EA-7.
- Performed excavation of EA-8 to design extents. Completion of the EA-8 excavation is pending post excavation sampling results.
- Completed pre-trenching for installation of temporary shoring related to the excavations along Route 440.
- Completed field verification of the JCMUA 48-inch storm sewer and BMUA 36-inch sewer force main.
- Installed traffic controls for shoulder closing associated with excavation along Route 440 south frontage with SA-6 North in accordance with the NJDOT permit.
- Lindie Griffith mobilized drill rig and equipment for installation of drilled soldier piles associated with temporary shoring for EA-2 and EA-3 along Rt. 440 frontage.

- Continued to haul screened historic fill from N1 and place it as backfill in the west side of SA-6 South backfill area.
- Completed placement of soils with hexavalent chromium concentrations between 20 and 240 ppm within the sedimentation basin south of the Vertical Hydraulic Barrier Wall on SA-6 North.
- Continued placement of historic fill within the sedimentation basin north of the Vertical Hydraulic Barrier Wall on SA-6 North.
- Completed groundwater sampling of four of the L-wells at SA-6 South, Site 124 using geoprobe/temporary well points.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| No update for the reporting period | | | | | | | |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Excavation Areas EA-7 and EA-8<br>Volume Excavated - Total for Reporting Period: 2,843.58 CY / Total to Date: 2,843.58 CY |
| **Backfill in Progress** | Historic Fill - SA6 South western backfill area. |

- Screened historic Fill was transferred from 1N surcharge area and placed as backfill in SA-6 South. A total of 110 loads, totaling approximately 2,200 cubic yards was placed as backfill in SA-6 South during the reporting period.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Completed installation of surcharge monitoring instrumentation.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- No sheet pile operations occurred during the reporting period.

## G. CAPPING OPERATIONS

- Continued general Cap Subgrade preparation in Area 1S and 2S.
- Continued Utility Corridor and roadway subgrade preparation.
- Continued cutting hydraulic barrier sheet of the SA-6 South cap area.
- Began breaking and removing asphalt on top of the SCB wall on the north side of the cap area.
- Began delivery and receiving inspections of geo-synthetic cap materials.
- Held kick-off meeting with Langan Environmental (independent liner QA) and initiated development of the QA Plan.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete excavation of Area EA-8 pending post excavation sampling results.
- Complete excavated waste load out for soils with hexavalent chromium concentrations greater than 240 ppm.
- Begin excavation of Area EA-4.
- Complete installation of drilled piles associated with the temporary shoring along Route 440.
- Complete installation of SA-6 South piezometers.
- Continue installation of the vertical hydraulic barrier wall east of the Trash Pit and along Route 440.
- Begin installation of dewatering wells associated with the SA-6 North Excavation Areas EA-2 and EA-3.
- Continue Cap Subgrade and utility corridor preparation activities on SA-6 South.
- Mobilize the geosynthetics crew and independent QA contractor and begin geo-synthetic cap placement activities on SA-6 South Area 1S.
- Mobilize screening equipment and begin screening Celgene material for use as cap cover soils.
- Verizon will complete relocation of communication lines to the North Bound side of Route 440.
- Begin Stratum D repair of the JCIA Trash Pit Area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Conduct S-3 Mass Removal injection Event No. 22 in well 088-IW-01.
- Complete PVSC Monthly compliance sampling.
- Submit the revised plan for the SA-6 North Treatment Area 10 proximate to force main.
- Continue to work with owner on access for the planned PW-3 extraction well installation.
- Finalize and submit Surcharge Monitoring Report No. 13 which will include the baseline installation data for Areas 3N and 4N.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data
9. Surcharge Monitoring Update
10. *Sheet Pile Update (not included in this reporting period)*
11. Weekly SWPPP Reports
12. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (May 2015)
13. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **1/4/08** | **3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **8/11/08** | **3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | 10/17/11 | 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | 9/1/14 | 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **3/1/13** | **5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | 6/17/13 | 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | 11/15/13 | 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **6/17/13** | **10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | 6/2/14 | 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 3/2/15 | 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | 10/20/14 | 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | 3/3/14 | 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **6/17/13** | **4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **12/2/13** | **4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | 12/2/13 | 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | 2/17/14 | 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | 6/23/14 | 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **6/17/13** | **5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | 6/17/13 | 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | 8/16/13 | 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | 10/3/13 | 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | 11/11/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **10/22/13** | **9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | 10/22/13 | 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | 1/3/14 | 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | 5/9/14 | 9/2/14 |
| **65** | **Backfill** | **493 days** | **11/11/13** | **9/30/15** |
| 65a | SA 6N Backfill | 218 days | 12/1/14 | 9/30/15 |
| 65b | SA 6S Backfill | 232 days | 11/11/13 | 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **12/1/14** | **2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | 9/1/15 | 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **164 days** | **9/1/15** | **4/15/16** |
| 67a | Restoration | 164 days | 9/1/15 | 4/15/16 |




Project: SA-6 Remediation Schedule
Revision 3
Date: 7/7/15

Task  Milestone  Summary  Critical

Note: The schedule will be revised following completion of the JCDPW relocation.

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **68** | **Demobilization** | **21 days** | **4/18/16** | **5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **310 days** | **10/1/15** | **12/7/16** |
| 75 | **SA-6 South Project Closeout** | **310 days** | **10/1/15** | **12/7/16** |




Project: SA-6 Remediation Schedule
Revision 3
Date: 7/7/15

Task | Milestone | Summary | Critical

Note: The schedule will be revised following completion of the JCDPW relocation.

# Attachment 2: Site Photographs




**Site Photograph 1:** Excavation to confirm 36-inch sewer main location on former JC properties.




**Site Photograph 2:** Excavation to confirm utilities locations along Rt. 440.




**Site Photograph 3:** Installation of Traffic Controls along Rt. 440.




**Site Photograph 4:** Loading end dump on plastic at former JC properties.




**Site Photograph 5:** Offloading remaining surcharge material at Kellogg St properties.




**Site Photograph 6:** Staging screened historic fill on former JC properties.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of July 1, 2015

June 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties

Former Roosevelt Drive-In Site
(Remediation Complete)

Kellogg Street Properties

Hackensack River

Route 440

Kellogg Street

# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 04/30/15 | 8:00 | 15:00 | 7:00 | 31,706.56 | 31,755.10 | 48,540 | 31,754,650 | |
| 05/01/15 | 10:00 | 14:30 | 4:30 | 31,755.10 | 31,779.92 | 24,820 | 31,779,470 | |
| 05/05/15 | 7:00 | 14:00 | 7:00 | 31,779.92 | 31,862.76 | 82,840 | 31,862,310 | PVSC Compliance Sample Collected |
| 05/08/15 | 7:30 | 14:30 | 7:00 | 31,862.76 | 31,923.11 | 60,350 | 31,922,660 | |
| 05/11/15 | 10:00 | 15:00 | 5:00 | 31,923.11 | 31,978.26 | 55,150 | 31,977,810 | |
| 05/14/15 | 10:00 | 15:00 | 5:00 | 31,978.26 | 32,016.71 | 38,450 | 32,016,260 | |
| 05/18/15 | 7:30 | 14:30 | 7:00 | 32,016.71 | 32,102.90 | 86,190 | 32,102,450 | |
| 05/19/15 | 7:30 | 14:00 | 6:30 | 32,102.90 | 32,136.78 | 33,880 | 32,136,330 | |
| 05/20/15 | 7:30 | 15:00 | 7:30 | 32,136.78 | 32,157.02 | 20,240 | 32,156,570 | |
| 05/21/15 | 7:00 | 13:30 | 6:30 | 32,157.02 | 32,194.76 | 37,740 | 32,194,310 | |
| 05/22/15 | 8:00 | 12:00 | 4:00 | 32,194.76 | 32,208.64 | 13,880 | 32,208,190 | |
| 05/24/15 | 10:00 | 14:00 | 4:00 | 32,208.64 | 32,256.26 | 47,620 | 32,255,810 | |
| 05/27/15 | 6:30 | 13:30 | 7:00 | 32,256.26 | 32,322.85 | 66,590 | 32,322,400 | |
| 05/29/15 | 10:00 | 14:15 | 4:15 | 32,322.85 | 32,377.97 | 55,120 | 32,377,520 | |
| 06/01/15 | 9:00 | 15:45 | 6:45 | 32,377.97 | 32,528.67 | 150,700 | 32,528,220 | |
| 06/02/15 | 7:00 | 14:00 | 7:00 | 32,528.67 | 32,620.67 | 92,000 | 32,620,220 | |
| 06/04/15 | 6:30 | 14:00 | 7:30 | 32,620.67 | 32,756.41 | 135,740 | 32,755,960 | PVSC Compliance Sample Collected |
| 06/05/15 | 6:30 | 13:30 | 7:00 | 32,756.41 | 32,833.26 | 76,850 | 32,832,810 | |
| 06/08/15 | 7:00 | 14:00 | 7:00 | 32,833.26 | 32,958.71 | 125,450 | 32,958,260 | |
| 06/10/15 | 10:00 | 16:00 | 6:00 | 32,958.71 | 33,019.45 | 60,740 | 33,019,000 | |
| 06/11/15 | 7:00 | 16:00 | 9:00 | 33,019.45 | 33,086.57 | 67,120 | 33,086,120 | |
| 06/12/15 | 6:30 | 12:00 | 5:30 | 33,086.57 | 33,146.46 | 59,890 | 33,146,010 | |
| 06/15/15 | 6:30 | 12:15 | 5:45 | 33,146.46 | 33,183.12 | 36,660 | 33,182,670 | |
| 06/16/15 | 7:00 | 14:15 | 7:15 | 33,183.12 | 33,226.73 | 43,610 | 33,226,280 | |
| 06/17/15 | 6:30 | 16:00 | 9:30 | 33,226.73 | 33,276.97 | 50,240 | 33,276,520 | |
| 06/18/15 | 6:30 | 14:30 | 8:00 | 33,276.97 | 33,338.90 | 61,930 | 33,338,450 | |
| 06/19/15 | 6:30 | 14:00 | 7:30 | 33,338.90 | 33,439.40 | 100,500 | 33,438,950 | |
| 06/21/15 | 9:30 | 13:30 | 4:00 | 33,439.40 | 33,485.10 | 45,700 | 33,484,650 | |
| 06/22/15 | 6:30 | 14:00 | 7:30 | 33,485.10 | 33,567.88 | 82,780 | 33,567,430 | |
| 06/23/15 | 11:30 | 14:00 | 2:30 | 33,567.88 | 33,609.80 | 41,920 | 33,609,350 | |
| 06/24/15 | 9:00 | 13:30 | 4:30 | 33,609.80 | 33,646.89 | 37,090 | 33,646,440 | |
| 06/26/15 | 8:00 | 14:00 | 6:00 | 33,646.89 | 33,720.85 | 73,960 | 33,720,400 | |
| 06/29/15 | 7:00 | 14:30 | 7:30 | 33,720.85 | 33,738.82 | 17,970 | 33,738,370 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA-8 | <20 | 087-EA8-20-a,b | 1500 | 087-EA8-20-a1 | 6/24/2015 | 7:35 | ** | | | |
| | | | | 087-EA8-20-a2 | 6/24/2015 | 7:40 | ** | | | |
| | | | | 087-EA8-20-a3 | 6/24/2015 | 7:45 | ** | | | |
| | | | | 087-EA8-20-a4 | 6/24/2015 | 7:50 | ** | | | |
| | | | | 087-EA8-20-b1 | 6/24/2015 | 7:55 | ** | | | |
| | | | | 087-EA8-20-b2 | 6/24/2015 | 8:00 | ** | | | |
| | | | | 087-EA8-20-b3 | 6/24/2015 | 8:05 | ** | | | |
| | | | | 087-EA8-20-b4 | 6/24/2015 | 8:10 | ** | | | |
| EA-8 | <20 | 087-EA8-20-c (bermed / trench material) | 250 | 087-EA8-20-c1 | 6/24/2015 | 11:40 | ** | | | |
| | | | | 087-EA8-20-c2 | 6/24/2015 | 11:45 | ** | | | |
| | | | | 087-EA8-20-c3 | 6/24/2015 | 11:50 | ** | | | |
| | | | | 087-EA8-20-c4 | 6/24/2015 | 11:55 | ** | | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'

N4 N3 N2 N1
S4 S3 S2 S1
E1 E2

NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1
073-MW-BB11 073-MW-Y10 134-MW-V09 134-MW-Q08 140-MW-06 140-MW-07 125-MW-L03
MW-124-103L MW-124-102D MW-124-103D MW-124-102T
117-MW-A99 117-MW-A85 117-MW-A89
115-PZ-6 115-PZ-5 115-PZ-4

W6-SO W1-SO W3-SO W5-SO E5-SO E4-SO E3-SO E2-SO E1-SO E1-SO

STA. N1+10 STA. N5+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N11+10 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. E3+75 STA. E4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S10+80 STA. S4+38 STA. S3+85 STA. S0+50

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

ROUTE 1&9 STATE HIGHWAY

KELLOGG STREET

KELLOGG STREET

**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | North | | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 7/16/2014 | | 5.8 | 6.4 | 6.8 | 6.8 | 4.2 | | 5.9 | 5.5 | 7.1 | 7.1 | 6.3 | | | | | 4.3 | 7.5 | 7.8 | | | |
| 7/29/2014 | | 5.6 | 6.4 | 6.6 | 6.5 | 3.1 | | 5.6 | 5.3 | 7.0 | 6.8 | 6.1 | | | | | 3.3 | 5.3 | 9.0 | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | 2.8 | | 5.5 | 5.1 | 6.8 | 6.7 | 6.1 | | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | 2.7 | 5.6 | 5.2 | 4.8 | 6.7 | 6.3 | 5.6 | | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | 2.6 | 5.0 | 5.1 | 4.8 | 6.5 | 6.1 | 5.6 | | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | 2.6 | 3.6 | 5.0 | 4.7 | 6.5 | 6.0 | 5.6 | | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | 2.3 | 3.0 | 5.0 | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | 2.8 | 3.1 | 5.1 | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | 3.8 | 5.1 | 5.0 | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | 5.3 | 6.6 | 5.2 | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | 6.8 | 6.7 | 5.5 | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | 8.6 | 7.3 | 5.4 | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | 3.5 | 3.1 | | 5.6 | 6.6 | | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 5.0 | 6.6 | | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 4.2 | 6.7 | | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO, North FS-4

# Attachment 8: Groundwater Quality Data


Honeywell


**Table 1**
Summary of Groundwater Quality Data from GWET Wells

| Parameter | 9-Sep-14 | | | 18-Dec-14 | | | 17-Mar-15 | | | 28-May-15 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 3.7 | 4.7 | ND | 3.2 | 4.0 | ND | 3.1 | 3.9 | ND | 3.1 | 3.8 | ND |
| Carbon Tetrachloride | 7.3 | 4.8 | 3.0 | 5.2 | 4.2 | 2.9 | 5.8 | 4.6 | 2.1 | 5.7 | 4.5 | 3.0 |
| Chloroform | 28.1 | 11.3 | ND | 25.8 | 9.4 | ND | 23.1 | 7.8 | 0.21 | 23.5 | 7.8 | 0.24J |
| 1,1-Dichloroethene | 0.62J | ND | ND | 0.57 | ND | ND | 0.63 | ND | ND | 0.61J | ND | ND |
| cis-1,2-Dichloroethene | 128 | 9.6 | ND | 112 | 8.6 | ND | 111 | 8.1 | ND | 131 | 9.6 | ND |
| trans-1,2-Dichloroethene | 4.5 | ND | ND | 3.5 | ND | ND | 3.8 | ND | ND | 3.9 | ND | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 123 | 57.4 | ND | 97 | 44.4 | ND | 101 | 45.0 | ND | 94.9 | 40.7 | ND |
| 1,1-Dichloroethane | 0.55J | ND | ND | 0.46 | ND | ND | 0.51 | ND | ND | 0.56J | ND | ND |
| Methylene chloride | 0.74J | ND | ND | 0.77 | 0.20 | ND | 0.71 | ND | ND | 0.73J | ND | ND |
| Vinyl chloride | 25.2 | 3.8 | ND | 15.4 | 2.5 | ND | 16.9 | 2.5 | ND | 18.1 | 3.0 | ND |
| 1,2-Dichlorobenzene | 0.82J | ND | ND | 0.66 | ND | ND | 0.70 | ND | ND | 0.67J | ND | ND |
| Chlorobenzene | 0.42J | ND | ND | 0.37 | ND | ND | 0.41 | ND | ND | 0.38J | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 34,200 | 11,100 | 15,700 | 35,900 | 12,200 | 15,900 | 34,700 | 13,500 | 15,100 | 36,100 | 13,500 | 16,800 |
| Total Chromium | 37,600 | 19,300 | 17,900 | 34,100 | 12,700 | 15,900 | 34,700 | 15,100 | 14,800 | 32,600 | 15,600 | 16,700 |


NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.

Note:
Starting with 1st quarter 2014, well 115-MW-215BR is being pumped and sampled.




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR





Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR

**TABLE 2**
**Quarterly Water Levels**
**June 2015**

| Wells<br>Date: June 10, 2015 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments |
|---|---|---|---|---|
| | | | | *GW Elevations are not corrected for tidal influence* |
| 087-MW-25D | 18.17 | 18.32 | -0.15 | |
| 087-MW-25T | 18.19 | 18.22 | -0.03 | |
| 087-MW-35 | 18.29 | NA | NA | Well abandoned |
| 087-OBS-1D | 15.13 | 14.92 | 0.21 | |
| 087-OBS-1L | 15.27 | 14.15 | 1.12 | |
| 087-OBS-1T | 15.23 | 15.14 | 0.09 | |
| 087-PW-2 | 13.02 | 31.40 | -18.38 | |
| 087-MW-08 | 12.98 | 13.01 | -0.03 | |
| 087-OBS-3L | 12.88 | 13.34 | -0.46 | |
| 087-MW-13 | 12.93 | 12.59 | 0.34 | |
| 087-OBS-5D | 12.72 | 12.70 | 0.02 | |
| 087-OBS-5T | 12.62 | 13.51 | -0.89 | |
| 087-PW-1 | 12.66 | 37.56 | -24.90 | |
| 087-MW-34 | 12.73 | 13.96 | -1.23 | |
| 087-OBS-2D | 12.68 | 15.20 | -2.52 | |
| SA6-MW-AA1D | 19.36 | 19.18 | 0.18 | |
| SA6-MW-AA1T | 15.31 | 15.01 | 0.30 | |
| SA6-MW-5BR-1 | 17.06 | 15.30 | 1.76 | |
| 087-OBS-4T | 11.60 | 11.18 | 0.42 | |
| 087-MW-O29D | 10.32 | 9.15 | 1.17 | |
| 087-MW-O29T | 9.98 | 8.77 | 1.21 | |
| 087-MW-03 | 13.77 | NA | N/A | Well not accessible |
| 087-MW-02 | 12.57 | NA | N/A | Well not accessible |
| 115-MW-203BR* | 8.70 | 8.28 | 0.42 | |
| 073-MW-1BR-1 | 7.58 | NA | N/A* | Well not accessible |
| 073-MW-10BR-1 | 6.67 | 12.56 | -5.89 | |
| 115-MW-215BR* | 8.82 | 13.02 | N/A* | |

* Reference point elevation to be confirmed.

# Attachment 9: Surcharge Monitoring Update




Installed Instrumentation Locations

Instrumentation Locations Not Installed

| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS8 | 685406.37 | 603094.37 |
| FS9 | 685500.70 | 603127.22 |
| FS10 | 685858.02 | 603165.50 |
| FS11 | 685387.04 | 603338.90 |
| HS10 | 685499.90 | 603327.97 |
| HS11 | 685328.97 | 603205.81 |
| HS12 | 685428.53 | 603407.96 |
| HS13 | 685253.14 | 603316.22 |
| SP21 | 685302.66 | 603197.35 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. PILE GEOMETRY IS BASED ON THE ASSUMPTION THAT THE SEDIMENTATION BASIN WALLS ARE IN PLACE AT THE TIME OF SURCHARGING.
5. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
6. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\oplus_{I-2}$ | INCLINOMETER LOCATION |
| $\blacksquare^{FS-1-1}$ | SETTLEMENT MONITORING POINT FULL - SET UP |
| $\blacksquare^{HS-1-1}$ | SETTLEMENT MONITORING POINT HALF - SET UP |
| $\boxtimes^{SP12}$ | SETTLEMENT MONITORING PLATFORM |
| $\bigcirc^{RP}$ | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

Prepared/Date: RJR 07/19/2013
Checked/Date: AE 07/19/2013

0 15 30 60
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN 3N
Project 3480-09-0006
Figure 9a

# Attachment 10: Sheet Pile Update

(not included in this reporting period)

# Attachment 11: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 5, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 2 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 4 |
| Housekeeping | | X | | 5 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 6 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 7 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 8 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/05/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, June 05, 2015

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence on the southern perimeter of the 3-S surcharge area requires maintenance. |
| 2 | IA2Q4A1AL8 | Spill pallets and secondary containment for storage tanks have accumulated storm water. |
| 3 | IA2Q4A1AL8 | Novartis/Celgene surcharge material overtops the sheetpile hydraulic barrier at several locations in surcharge areas 1-S and 2-S. |
| 4 | IA2Q4A1AL8 | Storm water is ponded on SA-6 South to the north of the 60 Kellogg building. |
| 5 | IA2Q4A1AL8 | Garbage/debris has accumulated on the grass areas outside of the perimeter fenceline at the Kellogg Street jughandle. |
| 6 | IA2Q4A1AL8 | Several gaps are present between fence panels in the perimeter fence between SA-6 North and the MUA complex. |
| 7 | IA2Q4A1AL8 | Sediment has overtopped erosion control measures surrounding the Novartis stockpile area on SA-7 Erosion control measures are compromised on the eastern, southern and western sides. |
| 8 | IA2Q4A1AL8 | Sediment has accumulated on both the northern and the southern SA-7 access roadways |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** Signature **Date:** 06/05/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair/replace silt fence as required. | 6/8/15 RAD |
| 2 | Drain storm water from secondary containment areas as required. | 6/9/15 RAD |
| 3 | Remove the surplus surcharge material to bring the grade in the SA-6 South cap area below the top of the HB sheets. Grade to prevent storm water runoff over the sheets. | 6/8/15 RAD |
| 4 | Pump ponded storm water to the Construction Water Treatment Plant as required. | 6/9/15 RAD |
| 5 | Pick up and dispose of garbage/debris. | 6/8/15 RAD |
| 6 | Close gaps in the perimeter fence. | 6/8/15 RAD |
| 7 | Repair/replace/install erosion control measures as required to provide acceptable containment around the expanding stockpile area. | 6/9/15 RAD |
| 8 | Remove sediment from the paved roadways and install tracking pads if required to prevent the buildup of sediment during normal work activities. | 6/10/15 RAD |
| | | |
| | | |

**Construction Manager:** **Date:** 06/10/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: June 12, 2015**

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 2 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 5 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 6 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 7 |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 8 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 9 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 10 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 11 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 06/12/15

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, June 12, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing is inadequate at various locations along the southern perimeter of the SA-6 South cap area. |
| 2 | IA2Q4A1AL8 | Backfill material meets the top of the sheet pile hydraulic barrier wall at several locations along the southern perimeter of the SA-6 South cap area. |
| 3 | IA2Q4A1AL8 | Windscreen has pulled loose from the perimeter fence at two locations adjacent to the Kellogg Street jughandle. |
| 4 | IA2Q4A1AL8 | Sections of removed storm drain pipe and other debris are present on the backfill in the western end of SA-6 South. |
| 5 | IA2Q4A1AL8 | Exclusion Zone fencing around the SA-6 North contingent groundwater system requires maintenance and additional signage. |
| 6 | IA2Q4A1AL8 | The historic fill stockpile to the south of the MUA building requires additional erosion control measures. |
| 7 | IA2Q4A1AL8 | Plastic sheeting at the Exclusion Zone truck exit east of the sedimentation basin is inadequate. |
| 8 | IA2Q4A1AL8 | Empty drums are staged on SA-6 North to the south of the JCIA trash pit. |
| 9 | IA2Q4A1AL8 | Erosion control measures around the Novartis stockpile area on SA-7 are inadequate or missing. |
| 10 | IA2Q4A1AL8 | Sediment has accumulated on the SA-7 paved and unpaved haul roads. |
| 11 | IA2Q4A1AL8 | Pallets and other debris are present on the stoned areas of SA-7 |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 06/12/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or amend exclusion zone fencing as required. | |
| 2 | Remove material or regrade as needed to prevent sediment from overtopping the hydraulic barrier wall during a rain event. | 6-17-15 RAD |
| 3 | Re-attach windscreen material as required. | 6-17-15RAD |
| 4 | Remove debris from the SA-6 South backfill area. | |
| 5 | Repair or amend exclusion zone fencing as required. | 6-17-15RAD |
| 6 | Install berms or silt dams as required. | |
| 7 | Replace plastic sheeting in the truck route as needed to maintain a clean surface. | 6-17-15RAD |
| 8 | Relocate the drums to the meter building garage. | 6-17-15RAD |
| 9 | Install addional silt fence or other erosion control measures aroundt he Novartis stockpile area to meet erosion control requirements. | |
| 10 | Thoroughly clean sediment from all SA-7 roadways. | 6-17-15RAD |
| 11 | Remove and discard of all debris or trash which is present on the SA-7 stone areas. | 6-17-15RAD |

1,4,6 and 9 unable to complete at this time

**Construction Manager:** _____ **Date:** 06/17/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: June 19, 2015**

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☑ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 3 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 4 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 5 |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 6 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 06/19/15

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, June 19, 2015**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Sections of removed storm drain pipe and other debris are present on the backfill in the western end of SA-6 South. |
| 2 | IA2Q4A1AL8 | REPEAT: Exclusion Zone fencing around the SA-6 North contingent groundwater system requires maintenance and additional signage. |
| 3 | IA2Q4A1AL8 | REPEAT: The historic fill stockpile to the south of the MUA building requires additional erosion control measures. |
| 4 | IA2Q4A1AL8 | Erosion control measures on the northern side of the Type C stockpile area on SA-6 north are inadequate. |
| 5 | IA2Q4A1AL8 | Plastic sheeting at the Exclusion Zone truck exit east of the sedimentation basin is inadequate. |
| 6 | IA2Q4A1AL8 | REPEAT: Erosion control measures around the Novartis stockpile area on SA-7 are inadequate or missing. |
| 7 | | |
| 8 | | |
| 9 | | |
| 10 | | |
| 11 | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 06/19/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove debris from the SA-6 South backfill area. | 6/25/15 RAD |
| 2 | Repair or amend exclusion zone fencing as required. | 6/25/15 RAD |
| 3 | Install berms or silt dams as required. | 6/25/15 RAD |
| 4 | Install containement measures as required. | 6/25/15 RAD |
| 5 | Replace plastic sheeting in the truck route as needed to maintain a clean surface. | 6/25/15 RAD |
| 6 | Install addional silt fence or other erosion control measures aroundt he Novartis stockpile area to meet erosion control requirements. | 6/25/15 RAD |
| 7 | | |
| 8 | | |
| 9 | | |
| 10 | | |
| 11 | | |

**Construction Manager:** _____ **Date:** 06/26/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 26, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | 1 | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 4 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 6 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/26/15

SWPPP Observer: _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
~~Friday, June 19, 2015~~ June 26, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencepost down at NE corner of EZ. Additional EZ signs required around the Exclusion Zone perimeter. |
| 2 | IA2Q4A1AL8 | Windscreen has blown loose from the perimeter fenceline at the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing around the eastern EZ requires more signs. |
| 4 | IA2Q4A1AL8 | Inadequate sediment control measures are present on the western side of the Sedimentation Basin Exclusion Zone. |
| 5 | IA2Q4A1AL8 | Silt fence along the western end of the SA-7 northern roadway is not properly toed in. |
| 6 | IA2Q4A1AL8 | **REPEAT:** Erosion control measures around the Novartis stockpile area on SA-7 are inadequate or missing. |
| 7 | | |
| 8 | | |
| 9 | | |
| 10 | | |
| 11 | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION
**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** _____ (Signature) **Date:** 06/26/15

| Comment Number | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair the EZ fencing as necessary and install additional Exclusion Zone signs. | 7-1-15 RAD |
| 2 | Repair/re-install windscreen as required. | 7-1-15 RAD |
| 3 | Install additional Exclusion Zone signage as required. | 7-1-15 RAD |
| 4 | Install erosion control measures and stormwater run-off measures as required. | 7-1-15 RAD |
| 5 | Reinstall or toe in silt fence as required. | 7-1-15 RAD |
| 6 | Install addional silt fence or other erosion control measures aroundt he Novartis stockpile area to meet erosion control requirements. | Screening operations prohibited |
| 7 | | |
| 8 | | |
| 9 | | |
| 10 | | |
| 11 | | |

**Construction Manager:** _____ **Date:** 07/01/15

# Attachment 12: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (May 2015)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

June 22, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the May 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy /SEF

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 5 | 01 | 15 | 5 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,826 | 83,031 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.53 | 0.57 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.2 | <5.2 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1337 | 0.1337 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

June 17, 2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 5 | 01 | 15 | 5 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,412,594 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 36,288,813 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 5/19/2015 | 7.5 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE June 17, 2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | | MONTH: May 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 5/1/2015 | Angel Trujillo | 33876219 | 33953737 | 77,518 | 0.077518 | 7.58 | 0.822 | | | | | | | | | 0.53 |
| 5/2/2015 | Angel Trujillo | 33953737 | 34035418 | 81,681 | 0.081681 | 7.36 | 0.822 | | | | | | | | | 0.56 |
| 5/3/2015 | Angel Trujillo | 34035418 | 34113680 | 78,262 | 0.078262 | 7.31 | 0.822 | | | | | | | | | 0.54 |
| 5/4/2015 | Angel Trujillo | 34113680 | 34189482 | 75,802 | 0.075802 | 7.34 | 0.822 | | | | | | | | | 0.52 |
| 5/5/2015 | Angel Trujillo | 34189482 | 34268659 | 79,177 | 0.079177 | 7.56 | 0.822 | | | | | | | | | 0.54 |
| 5/6/2015 | Angel Trujillo | 34268659 | 34342535 | 73,876 | 0.073876 | 7.47 | 0.822 | | | | | | | | | 0.51 |
| 5/7/2015 | Angel Trujillo | 34342535 | 34419711 | 77,176 | 0.077176 | 7.56 | 0.822 | | | | | | | | | 0.53 |
| 5/8/2015 | Angel Trujillo | 34419711 | 34502742 | 83,031 | 0.083031 | 7.57 | 0.822 | | | | | | | | | 0.57 |
| 5/9/2015 | Angel Trujillo | 34502742 | 34579671 | 76,929 | 0.076929 | 7.34 | 0.822 | | | | | | | | | 0.53 |
| 5/10/2015 | Angel Trujillo | 34579671 | 34657335 | 77,664 | 0.077664 | 7.27 | 0.822 | | | | | | | | | 0.53 |
| 5/11/2015 | Angel Trujillo | 34657335 | 34732417 | 75,082 | 0.075082 | 7.24 | 0.822 | | | | | | | | | 0.51 |
| 5/12/2015 | Angel Trujillo | 34732417 | 34810281 | 77,864 | 0.077864 | 7.26 | 0.822 | | | | | | | | | 0.53 |
| 5/13/2015 | Angel Trujillo | 34810281 | 34889426 | 79,145 | 0.079145 | 7.27 | 0.822 | | | | | | | | | 0.54 |
| 5/14/2015 | Angel Trujillo | 34889426 | 34967851 | 78,425 | 0.078425 | 7.29 | 0.822 | | | | | | | | | 0.54 |
| 5/15/2015 | Angel Trujillo | 34967851 | 35045403 | 77,552 | 0.077552 | 7.29 | 0.822 | | | | | | | | | 0.53 |
| 5/16/2015 | Angel Trujillo | 35045403 | 35126749 | 81,346 | 0.081346 | 7.34 | 0.822 | | | | | | | | | 0.56 |
| 5/17/2015 | Angel Trujillo | 35126749 | 35200190 | 73,441 | 0.073441 | 7.29 | 0.822 | | | | | | | | | 0.50 |
| 5/18/2015 | Angel Trujillo | 35200190 | 35277372 | 77,182 | 0.077182 | 7.33 | 0.822 | | | | | | | | | 0.53 |
| 5/19/2015 | Angel Trujillo | 35277372 | 35354134 | 76,762 | 0.076762 | 7.06 | 0.822 | <5.2 | 7.5 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.53 |
| 5/20/2015 | Angel Trujillo | 35354134 | 35431944 | 77,810 | 0.07781 | 7.34 | 0.822 | | | | | | | | | 0.53 |
| 5/21/2015 | Angel Trujillo | 35431944 | 35509187 | 77,243 | 0.077243 | 7.25 | 0.822 | | | | | | | | | 0.53 |
| 5/22/2015 | Angel Trujillo | 35509187 | 35588761 | 79,574 | 0.079574 | 7.30 | 0.822 | | | | | | | | | 0.55 |
| 5/23/2015 | Angel Trujillo | 35588761 | 35668683 | 79,922 | 0.079922 | 7.32 | 0.822 | | | | | | | | | 0.55 |
| 5/24/2015 | Angel Trujillo | 35668683 | 35747027 | 78,344 | 0.078344 | 7.29 | 0.822 | | | | | | | | | 0.54 |
| 5/25/2015 | Angel Trujillo | 35747027 | 35825211 | 78,184 | 0.078184 | 7.31 | 0.822 | | | | | | | | | 0.54 |
| 5/26/2015 | Angel Trujillo | 35825211 | 35899798 | 74,587 | 0.074587 | 7.32 | 0.822 | | | | | | | | | 0.51 |
| 5/27/2015 | Angel Trujillo | 35899798 | 35978906 | 79,108 | 0.0791 | 7.36 | 0.822 | | | | | | | | | 0.54 |
| 5/28/2015 | Angel Trujillo | 35978906 | 36053442 | 74,536 | 0.074536 | 7.31 | 0.822 | | | | | | | | | 0.51 |
| 5/29/2015 | Angel Trujillo | 36053442 | 36123270 | 69,828 | 0.069828 | 7.29 | 0.822 | | | | | | | | | 0.48 |
| 5/30/2015 | Automode | 36123270 | 36206041 | 82,771 | 0.082771 | 7.60 | 0.822 | | | | | | | | | 0.57 |
| 5/31/2015 | Angel Trujillo | 36206041 | 36288813 | 82,772 | 0.082772 | 7.59 | 0.822 | | | | | | | | | 0.57 |
| TOTAL | | | | 2,412,594 | 2.412594 | | | <5.2 | 7.5 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 83,031 | | | | | | | | | | | High: | 0.57 |
| | | | Average: | 77,826 | | | | | | | | | | | Average: | 0.53 |

WW

JB95035

C

**Accutest Labs**
2235 ROUTE 130
Dayton, NJ 8810
732-329-0200

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 42142.55886
COC#: 087-WW-051915

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Privileged & Confidential | | | Site Name: | Hudson County | Phase: | CS | Lab Proj # (SDG): |
| EDD To: | | | Location of Site: | Jersey City, NJ | Sampling Program | 087: JCIA | Lab ID: ACTD |
| Sampler: | Frank Schroyer | | | | | | Site ID: HudsonCo |
| PO # | | | | | | | Lab Job #: HWINJM32815 |
| Analysis Turnaround Time (TAT): | 3 | | | | | | Authorized User: Honeywell |
| Consultant | CH2M | | | | | | |
| | | | | | | | Text & Excel File Drive / Excel & Text File Order |
| Full Report TAT: | 28 Days | | | | | | |

**Sampling Co.:** MACTEC

**Client Contact: (name, co., address)**
Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com
Honeywell International
101 Columbia Road Morristown, NJ 07962

Preliminary Data To:
Sample Receipt Acknowledgement To: Frank Schroyer
Hard Copy To: Helen Fahy (Honeywell)
Invoice To: Helen Fahy (Honeywell)

Copyright AESI; Version 8.0 Unauthorized use strictly prohibited.

| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | Units | | | | | | | | | | | | | | | | | | |
| | Preservative | | | | | | | | | | | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | | | | |
| 1 | 087-WW | | | 087-WWE-051915-A | 5/19/2015 | 9:45 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | | C22 |
| 2 | 087-WW | | | 087-WWE-051915-B | 5/19/2015 | 10:00 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | | V1135 |
| 3 | 087-WW | | | 087-WWI-051915 | 5/19/2015 | 10:10 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | | A26 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | G42 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: 7.06 S.U. @ 9.4°C | Company: AMEC Foster Wheeler | Received by: | Company: | | Condition: | | Custody Seals Intact: |
| Frank Schroyer | 5/19/15 Date/Time | | 5/19/15 Date/Time: 1340 | | Cooler Temp. | | |
| Relinquished by: | Company | Received by: | Company: ACCUTEST | | Condition: | | Custody Seals Intact: |
| | Date/Time: 5/19/15 1650 | 1 | Date/Time: 5/19/15 1650 | | Cooler Temp. | 4.0°C-E | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE (N)

INITIAL ASESSMENT 2B (N)

LABEL VERIFICATION NL

Accutest LabLink@857275 16:09 10-Jun-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051915-A | | |
| **Lab Sample ID:** | JB95035-1 | **Date Sampled:** | 05/19/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/19/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 822 | 10 | ug/l | 1 | 05/20/15 | 05/21/15 | BS | EPA 200.7 [2] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 05/20/15 | 05/21/15 | BS | EPA 200.7 [2] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 05/20/15 | 05/21/15 | BS | EPA 200.7 [2] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 05/21/15 | 05/21/15 | MA | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 05/20/15 | 05/21/15 | BS | EPA 200.7 [2] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 05/20/15 | 05/21/15 | BS | EPA 200.7 [2] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA36709
(2) Instrument QC Batch: MA36710
(3) Prep QC Batch: MP86588
(4) Prep QC Batch: MP86636

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@857275 16:09 10-Jun-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051915-A | | |
| **Lab Sample ID:** | JB95035-1 | **Date Sampled:** | 05/19/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/19/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 05/21/15 | KP | SM2540 D-11 |
| pH [a] | 7.09 | | su | 1 | 05/19/15 18:51 | AM | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@857275 16:09 10-Jun-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051915-A | | |
| **Lab Sample ID:** | JB95035-1A | **Date Sampled:** | 05/19/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/19/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 7.5 | 5.0 | mg/l | 1 | 05/20/15 18:23 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@857275 16:09 10-Jun-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051915-B | | |
| **Lab Sample ID:** | JB95035-2 | **Date Sampled:** | 05/19/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/19/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T208144.D | 1 | 05/22/15 | DC | n/a | n/a | VT8545 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.0 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.3 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 14.6 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.36 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.34 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 68.6 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.4 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.42 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@857275 16:09 10-Jun-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051915-B | | |
| **Lab Sample ID:** | JB95035-2 | **Date Sampled:** | 05/19/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/19/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 40.7 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 101% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 99% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 99% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 103% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@857275 16:09 10-Jun-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051915-B | | |
| **Lab Sample ID:** | JB95035-2 | **Date Sampled:** | 05/19/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/19/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.2 | 5.2 | mg/l | 1 | 05/21/15 09:15 | BM | EPA 1664A |

RL = Reporting Limit

# Attachment 13: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending June 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending June 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor. Submitted to all Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor. Submitted to all Parties on June 18, 2015. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Contractor only. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on June 22, 2015. |

**SA-6 North/South Field Change Log - Month Ending June 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on June 22, 2015. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**8/14/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

August 14, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-07**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from July 1 – July 31, 2015.

Per prior discussion, Honeywell has included a new section pertaining to liner quality assurance.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: July 2015 SA-6/7 Combined Monthly Progress Report No. 2015-07

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP

Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-07

**Project SA-6 & 7 Remediation**

## July 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 07/02/15 | Upload to LBG SharePoint Site:<br>DCB 3S Surcharge Pile Geometry on East End<br>Study Area 6 South<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/08/15 | Discharge to Groundwater Permit-By-Rule Authorization Request<br>Study Area 6 North, Site 087<br>PI No. G000008710<br>Jersey City, New Jersey | New Jersey Department of Environmental Protection<br>Bureau of Case Assignment & Initial Notice<br>Site Remediation Program |
| 7/10/2015 | Summary of Interim L-Well Sampling<br>Study Area 6 South, Site 124<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/13/15 | Droyers Cove Beneficial Environmental Project 100% Design Report<br>Study Area 7 Sediment<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/14/15 | Study Areas 6 and 7 Combined Monthly Progress/Highlights<br>Report No. 2015-06 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/14/15 | Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 07/20/15 | Summary of Proposed In-Situ Injection of Calcium Polysulfide for Treatment of Chromium Impacted Soils (Addendum)<br>Study Area 6 North<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/21/15 | Surcharge Monitoring Plan<br>Monthly Report No. 13<br>Study Area 6 North and South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 07/21/15 | Arnold & Porter Correspondence: Study Area 6 North In-Situ Treatment -- Response to Plaintiffs' Correspondence of July 1, 2015<br>Study Area 6 North<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/21/15 | Special Master Conference Call | N/A |
| 07/29/15 | Application for General Permit 24<br>Droyers Cove Beneficial Environmental Project<br>Study Area 7, Sediment Remedy<br>Jersey City, New Jersey | New Jersey Department of Environmental Protection<br>Division of Land Use Regulation |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 7/5/15 | 7/12/15 | 7/19/15 | 7/26/15 | 8/2/15 |
| **Construction Management (AMEC)** | 9 | 10 | 10 | 10 | 11 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 44 | 39 | 38 | 46 | 49 |
| **Arecon/US Ecology Subcontractors** | 1 | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 2 | 2 | 2 | 2 | 0 |
| **TOTAL STAFF** | 62 | 57 | 56 | 64 | 66 |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected July PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Verizon completed relocating overhead communication lines to the North Bound side of Route 440.

- On July 6 through 8, Cornerstone personnel completed S-3 Mass Removal Injection Event No. 22 in Injection Well 088-IW-01.
- On July17, Summit Drilling conducted soil sampling to a depth of 40 feet at the proposed PW-3 location on the Difeo car dealership property. The drill rig malfunctioned during drilling operations resulting in a demobilization and rescheduling of the work activities.
- Continued screening of Celgene material for use as protective cover soils above geosynthetics.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on July 16, 2015.
- PVSC collected annual compliance sample from the GWTP and the CWTP.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 7/5/15 | 7/12/15 | 7/19/15 | 7/26/15 | 8/2/15 |
| Avg. Gallons Treated & Discharged (per day) | 76,308 | 78,678 | 78,254 | 77,495 | 77,502 |
| Average Flow (gpm) for Operating Period | 54 | 54 | 54 | 53 | 54 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 11,616 | 7,838 | 9,276 | 8,606 | 7,882 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completion of the EA-8 excavation is pending post excavation sampling results.
- Lindie Griffith completed installation of drilled and driven soldier piles associated with temporary shoring for EA-2 and EA-3 along Route 440 frontage.
- Completed installation of well points for dewatering EA-5 on SA-6 North.
- Continued to haul screened historic fill from N1 and place it as backfill in the west side of SA-6 South backfill area.
- Continued relocating soils from Area 3S to the SA-6 North Cap Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Canada | Stablex | WWTP Filter Cake | 1 | 23 | 15.4 |
| **Entact/Horwith** | Tri-axle Dump | PA Transload | US Ecology | >1,000 mg/kg soils | 25 | 21.63 | 540.78 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Excavation Areas EA-7 and EA-8<br>Volume Excavated - Total for Reporting Period: 0 CY / Total to Date: 2,843.58 CY |
| **Backfill in Progress** | Historic Fill – SA-6 South western backfill area. |

- Screened historic Fill was transferred from 1N surcharge area and placed as backfill in SA-6 South. A total of 75 loads, totaling approximately 1,500 cubic yards was placed as backfill in SA-6 South during the reporting period.
- Screened Celgene material was placed as protective cover soil in the SA-6 South cap area. A total of 17 loads, totaling approximately 383 cubic yards was placed as backfill in SA-6 South during the reporting period.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Completed installation of surcharge monitoring instrumentation.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- Completed pre-trenching for vertical hydraulic barrier wall alignment along Route 440.
- Began installation of temporary sheet pile along Route 440.
- Continued installation of the vertical hydraulic barrier wall east of the Trash Pit and along Route 440 from STA 0+00 to STA 3+10 (Completed on August 5th 2015). Vibration monitoring was performed during driving activities.

## G. CAPPING OPERATIONS

- A total of 121,511 sq. ft. of liner totaling 35% of the total cap area, was deployed during the reporting period.
- Began installation of geosynthetic cap components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite Drainage layer.
- Continued general liner subgrade preparation in Area 2S and 3S.
- Continued cutting hydraulic barrier sheets to final elevation in SA-6 South Open Space Area.
- Completed installation of piezometers associated with the SA-6 South Open Space Area.
- Continued removing asphalt on top of the SCB wall and smooth coating as necessary for geosynthetics installation detail.
- Began installation of gas vent pipe installation.
- Continued delivery and receiving inspections of geosynthetic cap materials.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete excavation of Area EA-8 pending post excavation sampling results.
- Begin excavation of Area EA-4 and EA-5.
- Complete installation of the vertical hydraulic barrier wall within the Trash Pit
- Begin installation of dewatering wells associated with the SA-6 North Excavation Areas EA-2 and EA-3.
- Continue liner subgrade and utility corridor preparation activities on SA-6 South.
- Continue screening Celgene material for use as liner protective cover soils.
- Continue Celgene material screening activities.
- Continue dewatering and storm-water management activities.
- Complete installation of Sonic Boring associated with planned PW-3.
- Continue SWPPP inspections.
- Conduct S-3 Mass Removal injection Event No. 23 in well 088-IW-03.
- Complete soil sieve analyses from the PW-3 location on Difeo property.
- Complete PVSC Monthly compliance sampling.
- Implement the in-situ plan for the SA-6 North Treatment Area 10 proximate to force main.
- Continue to work with owner on access for the planned PW-3 extraction well/trench installation.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data (*conducted quarterly, not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
11. Capping Update
    - SA-6 South Cap Subgrade Progress Map
    - Repair Log
    - Non-conformance Log
    - Subgrade Approval Forms
    - QA Photo Log
12. Weekly SWPPP Reports
13. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (June 2015)
14. SA-6 North & South Design Change Tracking Log


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1891 days** | **1/4/08** | **3/30/15** |
| **18** | **JCIA/JCDPW Relocation** | **1735 days** | **8/11/08** | **3/30/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 753 days | 10/17/11 | 8/29/14 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 151 days | 9/1/14 | 3/30/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **838 days** | **3/1/13** | **5/16/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 403 days | 6/17/13 | 12/31/14 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 294 days | 11/15/13 | 12/31/14 |
| **61** | **Mobilization (Inclues new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **620 days** | **6/17/13** | **10/30/15** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instrumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 195 days | 6/2/14 | 2/27/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 3/2/15 | 10/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 182 days | 10/20/14 | 6/30/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 195 days | 3/3/14 | 11/28/14 |
| **63** | **Barrier Wall Install** | **489 days** | **6/17/13** | **4/30/15** |
| **63a** | **SA 6N Installation of Barrier Wall** | **369 days** | **12/2/13** | **4/30/15** |
| 63b | SA-6N Barrier Wall Delivery and Installation Preparation | 55 days | 12/2/13 | 2/14/14 |
| 63c | SA-6N Stations 23+38 to 14+25 | 90 days | 2/17/14 | 6/20/14 |
| 63d | SA-6N Stations 14+25 to 0+00 | 224 days | 6/23/14 | 4/30/15 |
| **63f** | **SA 6S Installation of Barrier Wall** | **250 days** | **6/17/13** | **5/30/14** |
| 63g | SA-6S Barrier Wall Delivery and Installation Preparation | 44 days | 6/17/13 | 8/15/13 |
| 63h | SA-6S Stations 1+54 to 8+37 | 7 days | 8/16/13 | 8/26/13 |
| 63i | SA-6S Stations 0+00 to 1+54; 8+37 to 8+60; 24+40 to 14+87; 24+40 to 25+89 | 27 days | 10/3/13 | 11/8/13 |
| 63j | SA-6S Stations 8+60 to 14+87 | 145 days | 11/11/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| **64b** | **SA 6S Excavation** | **226 days** | **10/22/13** | **9/2/14** |
| 64c | SA-6S Excavation of Cells 1 - 25 | 53 days | 10/22/13 | 1/2/14 |
| 64d | SA-6S Excavation of Cells 26 - 60 | 90 days | 1/3/14 | 5/8/14 |
| 64e | SA-6S Excavation of Cells 156 - 61 | 83 days | 5/9/14 | 9/2/14 |
| **65** | **Backfill** | **493 days** | **11/11/13** | **9/30/15** |
| 65a | SA 6N Backfill | 218 days | 12/1/14 | 9/30/15 |
| 65b | SA 6S Backfill | 232 days | 11/11/13 | 9/30/14 |
| **66** | **Capping and Cover Soil Placement** | **315 days** | **12/1/14** | **2/12/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 119 days | 9/1/15 | 2/12/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **164 days** | **9/1/15** | **4/15/16** |
| 67a | Restoration | 164 days | 9/1/15 | 4/15/16 |




Project: SA-6 Remediation Schedule
Revision 3
Date: 7/31/15


Task  Milestone  Summary  Critical

Note: The schedule will be revised following completion of the JCDPW relocation.

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **68** | **Demobilization** | **21 days** | **4/18/16** | **5/16/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **310 days** | **10/1/15** | **12/7/16** |
| 75 | **SA-6 South Project Closeout** | **310 days** | **10/1/15** | **12/7/16** |




Project: SA-6 Remediation Schedule
Revision 3
Date: 7/31/15

Task | Milestone ◆ | Summary | Critical

Note: The schedule will be revised following completion of the JCDPW relocation.

# Attachment 2: Site Photographs




**Site Photograph 1:** Fine grading of soils along slope of open space area Kellogg Street properties.




**Site Photograph 2:** Fine grading of soils in flatter open space area Kellogg Street Properties.




**Site Photograph 3:** Finishing the concrete barrier wall with smooth coat.




**Site Photograph 4:** Fusion Welding liner panels in Area 1S.




**Site Photograph 5:** Loading materials at Jersey City properties for offsite disposal.




**Site Photograph 6:** Onsite screening of soils to remove gravel.




**Site Photograph 7:** Sewing the seam between venting layer panels.





**Site Photograph 8:** Specialty equipment installs shoring for utility protection.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of August 1, 2015

July 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 05/29/15 | 10:00 | 14:15 | 4:15 | 32,322.85 | 32,377.97 | 55,120 | 32,377,520 | |
| 06/01/15 | 9:00 | 15:45 | 6:45 | 32,377.97 | 32,528.67 | 150,700 | 32,528,220 | |
| 06/02/15 | 7:00 | 14:00 | 7:00 | 32,528.67 | 32,620.67 | 92,000 | 32,620,220 | |
| 06/04/15 | 6:30 | 14:00 | 7:30 | 32,620.67 | 32,756.41 | 135,740 | 32,755,960 | PVSC Compliance Sample Collected |
| 06/05/15 | 6:30 | 13:30 | 7:00 | 32,756.41 | 32,833.26 | 76,850 | 32,832,810 | |
| 06/08/15 | 7:00 | 14:00 | 7:00 | 32,833.26 | 32,958.71 | 125,450 | 32,958,260 | |
| 06/10/15 | 10:00 | 16:00 | 6:00 | 32,958.71 | 33,019.45 | 60,740 | 33,019,000 | |
| 06/11/15 | 7:00 | 16:00 | 9:00 | 33,019.45 | 33,086.57 | 67,120 | 33,086,120 | |
| 06/12/15 | 6:30 | 12:00 | 5:30 | 33,086.57 | 33,146.46 | 59,890 | 33,146,010 | |
| 06/15/15 | 6:30 | 12:15 | 5:45 | 33,146.46 | 33,183.12 | 36,660 | 33,182,670 | |
| 06/16/15 | 7:00 | 14:15 | 7:15 | 33,183.12 | 33,226.73 | 43,610 | 33,226,280 | |
| 06/17/15 | 6:30 | 16:00 | 9:30 | 33,226.73 | 33,276.97 | 50,240 | 33,276,520 | |
| 06/18/15 | 6:30 | 14:30 | 8:00 | 33,276.97 | 33,338.90 | 61,930 | 33,338,450 | |
| 06/19/15 | 6:30 | 14:00 | 7:30 | 33,338.90 | 33,439.40 | 100,500 | 33,438,950 | |
| 06/21/15 | 9:30 | 13:30 | 4:00 | 33,439.40 | 33,485.10 | 45,700 | 33,484,650 | |
| 06/22/15 | 6:30 | 14:00 | 7:30 | 33,485.10 | 33,567.88 | 82,780 | 33,567,430 | |
| 06/23/15 | 11:30 | 14:00 | 2:30 | 33,567.88 | 33,609.80 | 41,920 | 33,609,350 | |
| 06/24/15 | 9:00 | 13:30 | 4:30 | 33,609.80 | 33,646.89 | 37,090 | 33,646,440 | |
| 06/26/15 | 8:00 | 14:00 | 6:00 | 33,646.89 | 33,720.85 | 73,960 | 33,720,400 | |
| 06/29/15 | 7:00 | 14:30 | 7:30 | 33,720.85 | 33,738.82 | 17,970 | 33,738,370 | |
| 06/30/15 | 7:00 | 13:00 | 6:00 | 33,738.82 | 33,791.38 | 52,560 | 33,790,930 | |
| 07/01/15 | 6:30 | 14:00 | 7:30 | 33,791.38 | 33,923.97 | 132,590 | 33,923,520 | PVSC Compliance Sample Collected |
| 07/02/15 | 6:30 | 13:00 | 6:30 | 33,923.97 | 34,000.38 | 76,410 | 33,999,930 | |
| 07/06/15 | 7:00 | 13:30 | 6:30 | 34,000.38 | 34,066.66 | 66,280 | 34,066,210 | |
| 07/07/15 | 8:00 | 14:00 | 6:00 | 34,066.66 | 34,125.32 | 58,660 | 34,124,870 | |
| 07/08/15 | 6:30 | 13:30 | 7:00 | 34,125.32 | 34,199.65 | 74,330 | 34,199,200 | |
| 07/09/15 | 6:30 | 13:30 | 7:00 | 34,199.65 | 34,252.75 | 53,100 | 34,252,300 | |
| 07/10/15 | 6:30 | 12:00 | 5:30 | 34,252.75 | 34,298.94 | 46,190 | 34,245,390 | |
| 07/13/15 | 7:00 | 11:45 | 4:45 | 34,298.94 | 34,325.94 | 27,000 | 34,226,200 | |
| 07/14/15 | 6:30 | 12:30 | 6:00 | 34,325.94 | 34,396.15 | 70,210 | 34,269,410 | |
| 07/15/15 | 7:00 | 14:00 | 7:00 | 34,396.15 | 34,474.85 | 78,700 | 34,331,000 | |
| 07/16/15 | 6:30 | 13:00 | 6:30 | 34,474.85 | 34,526.84 | 51,990 | 34,382,990 | |
| 07/17/15 | 12:00 | 14:00 | 2:00 | 34,526.84 | 34,556.84 | 30,000 | 34,412,990 | |
| 07/21/15 | 6:30 | 14:30 | 8:00 | 34,556.84 | 34,653.22 | 96,380 | 34,509,370 | |
| 07/23/15 | 6:30 | 13:30 | 7:00 | 34,653.22 | 34,690.24 | 37,020 | 34,546,390 | |
| 07/24/15 | 10:30 | 13:30 | 3:00 | 34,690.24 | 34,702.10 | 11,860 | 34,558,250 | |
| 07/27/15 | 6:30 | 14:00 | 7:30 | 34,702.10 | 34,790.64 | 88,540 | 34,646,790 | |
| 07/31/15 | 6:30 | 14:30 | 8:00 | 34,790.64 | 34,908.04 | 117,400 | 34,764,190 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

**SA-6 NORTH AND SOUTH**
Material Tracking and Sampling Log

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA-8 | <20 | 087-EA8-20-a,b | 1500 | 087-EA8-20-a1 | 6/24/2015 | 7:35 | <2.3 | * | | |
| | | | | 087-EA8-20-a2 | 6/24/2015 | 7:40 | <2.3 | * | | |
| | | | | 087-EA8-20-a3 | 6/24/2015 | 7:45 | <1.9 | * | | |
| | | | | 087-EA8-20-a4 | 6/24/2015 | 7:50 | <1.9 | * | | |
| | | | | 087-EA8-20-b1 | 6/24/2015 | 7:55 | <2.1 | * | | |
| | | | | 087-EA8-20-b2 | 6/24/2015 | 8:00 | 0.78 | * | | |
| | | | | 087-EA8-20-b3 | 6/24/2015 | 8:05 | 2.10 | * | | |
| | | | | 087-EA8-20-b4 | 6/24/2015 | 8:10 | <2.0 | * | | |
| EA-8 | <20 | 087-EA8-20-c (bermed / trench material) | 250 | 087-EA8-20-c1 | 6/24/2015 | 11:40 | <1.9 | * | | |
| | | | | 087-EA8-20-c2 | 6/24/2015 | 11:45 | <2.1 | * | | |
| | | | | 087-EA8-20-c3 | 6/24/2015 | 11:50 | <2.1 | * | | |
| | | | | 087-EA8-20-c4 | 6/24/2015 | 11:55 | <1.9 | * | | |
| EA7 | <20 | 087-EA7-20-a (bermed/trench material) | 900 | 087-EA7-20-a1 | 6/26/2015 | 13:15 | <1.8 | * | | |
| | | | | 087-EA7-20-a2 | 6/26/2015 | 13:20 | <1.4 | * | | |
| | | | | 087-EA7-20-a3 | 6/26/2015 | 13:25 | <1.4 | * | | |
| | | | | 087-EA7-20-a4 | 6/26/2015 | 13:30 | 5.50 | * | | |
| EA7 | <20 | 087-EA7-20-b West Pile | 600 | 087-EA7-20-b1 | 7/14/2015 | 8:52 | 4:48 | * | | |
| | | | | 087-EA7-20-b2 | 7/14/2015 | 8:56 | 2.6 | * | | |
| | | | | 087-EA7-20-b3 | 7/14/2015 | 9:00 | 4.3 | * | | |
| | | | | 087-EA7-20-b4 | 7/14/2015 | 9:03 | 2.80 | * | | |
| EA7 | <20 | 087-EA7-20-c East Pile | 200 | 087-EA7-20-c1 | 7/14/2015 | 9:06 | <.47 | * | | |
| | | | | 087-EA7-20-c2 | 7/14/2015 | 9:11 | <1.6 | * | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'

N4 N3 N2 N1
S4 S3 S2 S1
E1 E2

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1
NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
S-C-B BARRIER (TYP.)
W6-SO W1-SO E5-SO E4-SO E3-SO
117-MW-A99
115-PZ-6 115-PZ-5 115-PZ-4
INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0
INTERIOR POOL ELEV. +4.0
COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)
COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)
W3-SO W5-SO E2-SO E1-SO
117-MW-A85
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6
073-MW-BB11 073-MW-Y10
134-MW-V09 134-MW-Q08
140-MW-06 140-MW-07
MW-124-103L MW-124-102D MW-124-103D MW-124-102T
125-MW-L03
117-MW-A89
KELLOGG STREET
STATE ROUTE 495

STA. N11+10 STA. N6+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. E3+75 STA. E4+50 STA. E7+25
STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+38 STA. S3+85 STA. S0+50

**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'


**IN PROGRESS**
06-10-2015

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**
NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | North | | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 8/15/2014 | | 5.3 | 6.1 | 6.2 | 6.2 | 2.8 | | 5.5 | 5.1 | 6.8 | 6.7 | 6.1 | | | | | 4.1 | 5.5 | 8.9 | 8.9 | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | 2.7 | 5.6 | 5.2 | 4.8 | 6.7 | 6.3 | 5.6 | | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | 2.6 | 5.0 | 5.1 | 4.8 | 6.5 | 6.1 | 5.6 | | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | 2.6 | 3.6 | 5.0 | 4.7 | 6.5 | 6.0 | 5.6 | | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | 2.3 | 3.0 | 5.0 | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | 2.8 | 3.1 | 5.1 | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | 3.8 | 5.1 | 5.0 | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | 5.3 | 6.6 | 5.2 | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | 6.8 | 6.7 | 5.5 | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | 8.6 | 7.3 | 5.4 | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | 3.5 | 3.1 | | 5.6 | 6.6 | | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 5.0 | 6.6 | | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 4.2 | 6.7 | | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | 3.2 | 2.6 | 6.2 | | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | 2.3 | 2.0 | 6.0 | | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO, North FS-4


# Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET GN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 10/10/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR TDD CHK RJR | APVD TDD | SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Pln Prof.dwg PLOT DATE: Mon, 07 Oct 2013 PLOT TIME: 4:04 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | TDD | DR TDD CHK RJR APVD BCO | | |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWINGS, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2106 MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR CHK APVD | | SGS |
| | | TDD RJR TDD | | |

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

COPYRIGHTING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 890-2329
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Capping Update

- SA-6 South Cap Subgrade Progress Map
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log




LEGEND

- SUBGRADE GRADING UNDERWAY
- SUBGRADE COMPLETE AND SURVEYED
- APPROVED FOR GEOSYNTHETIC DEPLOYMENT
- LINER DEPLOYED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP SUBGRADE PROGRESS MAP
07/24/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 1730.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 2368.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-1 | CF | 2/3 | | 98'N OF SEOS ( VALLEY DESIGN) | P | 2.5 | x | 63 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-2 | WR | 3/4 | | 94'N OF SEOS | P | 2 | x | 12 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-3 | SI | | 3 | 60'N OF 2/3 & 11'E | P | 2 | x | 2.5 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-4 | DS-1 | 3/4 | | 18'N OF SEOS | P | 2 | X | 28 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-5 | CF | | 3 | 140'N OF 2/3 & 6'E | P | 2 | x | 10 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-6 | PB | 1/2 | | 135'N OF SEOS ( 6" PB) | P | 5 | x | 5 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-7 | PB | | 1 | 85'N OF 1/2 & 17'W ( 4" PB) | P | 3 | x | 4 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-8 | SI | | 2 | 86'N OF 2/3 & 2'W | P | 1.5 | x | 2 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-9 | RW | 4/5 | | SEOS | P | 1.5 | x | 3 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-10 | SJ | 5/6/7 | | SJ 5/6/7 | P | 1.5 | X | 2 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-11 | RW | 5/7 | | SEOS | P | 2 | x | 4 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-12 | DS-2 | 6/7 | | 10'E OF WEOS | P | 2 | x | 5.5 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-13 | FS | 7/8 | | E.S. & COVER OVER SJ 6/7/8 | P | 2 | x | 6 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-14 | PB | | 8 | 147'N OF 6/8 & 4'E ( 6" PB) | P | 5 | x | 5 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-15 | BO | 9/10 | | 52'N OF SEOS | P | 2 | x | 3 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-16 | DS-3 | 11/12 | | 100'N OF SEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-17 | CF | 13/14 | | 46'S OF NEOS (VALLEY DESIGN) | P | 2 | x | 42 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-18 | DSX-1 | | 13 | ON RP-17 | P | 2 | X | 6 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-19 | DS-4 | 14/15 | | 16'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-20 | CF | 14/15 | 15 | 57'S OF NEOS | P | 2 | x | 20 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-21 | CF | 15/16 | | 37'S OF NEOS | P | 2 | x | 16 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |

## *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CR | --Crease | FS | --Failed Seam | MatD | --Material Defect | LL | --Lost Lap | CF | --Custom Fit |
| DS | --Destruct Sample | WR | --Wrinkle | WS | --Welder Restart | MD | --Mechanical Damage | PB | --Pipe Boot |
| SI | --Subgrade Irregularity | AV | --Airvent | RW | --Roller Wrinkle | DO | --Damage By Others | BO | --Burn Out |
| SJ | --Seam Joint | AO | --Add On | CS | --Concrete Structure | | | AT | -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 1730.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 2368.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-22 | BO | 16/17 | | 23'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | | 7/30/15 |
| RP-23 | DS-5 | 17/18 | | 75'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-24 | CF | 16 | | 80'S OF 16/17 & 13'W (MANHOLE) | P | 10 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-25 | CF | 15/16 | | 78'S OF NEOS | P | 2 | x | 15 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-26 | CF | | 16 | 100'S OF 16/17 & 15'W | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-27 | BO | 16/17 | | 80'S OF NEOS (PATCH)& 7'W (EXT) | P | 2 | x | 2 | 84 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-28 | BO | 16/17 | | 115'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-29 | BO | 16/17 | | 130'S OF NEOS | P | 2 | x | 8 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-30 | SI | | 17 | 110'S OF 17/18 & 4'W | P | 2 | x | 2 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-31 | BO | 17/18 | | 101'S OF NEOS | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-32 | AO | | 15 | SEOP (TRIANGLE ) | | | x | | 324 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-33 | CF | | 16 | 134'S OF 16/17 & 6'W | P | 2 | x | 13 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-34 | DSX-2 | RP-32/15 | 15 | 10'E OF RP-32 | P | 2 | x | 4.5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-35 | WR | | 17 | 94'S OF 16/17 & 3'W | P | 2 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-36 | WR | | 17 | 88'S OF 16/17 & 3'W | P | 1.5 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-37 | WR | | 17 | 88'S OF 16/17 & 15'W | P | 2 | x | 6 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-38 | WR | | 17 | 101'S OF 16/17 & 10'W | P | 2 | x | 8 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-39 | DS-6 | 20/21 | | 155'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-40 | BO | 20/21 | | 128'S OF NEOS | P | 2 | x | 7 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-41 | WR | | 18 | 75'S OF 18/19 & 11'W | P | 2 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-42 | CR | 17/18 | | 60'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |

## *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

## *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 1730.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 2368.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-64 | WR | | 21 | BETWEEN RP-63 & RP-65 | | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-65 | WR | | 21 | 20'S OF 21/22 & 18'W | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-66 | WR | | 22 | 20'S OF 22/23 & 5'W | P | 1.5 | x | 12 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-67 | BO | 21/22 | | 84'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-68 | BO | 22/23 | | 76'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-69 | WR | | 22 | 130'S OF 21/22 & 6'E | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-70 | WR | | 22 | BETWEEN RP-69 & RP-71 | | | x | | 60 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-71 | CR | 21/22 | | 137'S OF NEOS | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-72 | WR | | 21 | BETWEEN RP-71 & RP-73 | | | x | | 24 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-73 | WR | | 21 | 130'S OF 21/22 & 4'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-74 | WR | | 21 | BETWEEN RP-73 & RP-75 | | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-75 | WR | | 21 | 129'S OF 21/22 & 9'W | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-76 | BO | 22/23 | | 97'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-77 | WR | | 23 | 118'S OF 22/23 & 7'E | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-78 | WR | | 23 | BETWEEN RP-77 & RP-79 | | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-79 | WR | | 23 | 124'S OF 22/23 & 7'E | P | 2 | x | 11 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-80 | WR | | 23 | BETWEEN RP-79 & RP-81 | | | x | | 84 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-81 | WR | | 23 | 134'S 22/23 & 9'E | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-82 | DS-7 | 23/24 | | 87'S OF NEOS | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-83 | DSX-3 | RP-82/23 | | RP-82/83( 87'S OF NEOS) | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-84 | CR | 23/24 | | 116'S OF NEOS | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

## *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 1730.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 2368.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-85 | CF | | 23 | 125'S OF 23/24 & 3'W | P | 2 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-86 | CF | | 23 | BETWEEN RP-85 & RP-87 | | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-87 | CF | | 23 | 140'S OF 23/24 & 10'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-88 | BO | 24/25 | | 127'S OF NEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-89 | WR | | 24 | BETWEEN RP-88 & RP-90 | | | x | | 60 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-90 | WR | | 24 | 127'S OF 24/25 & 5'W | P | 2 | x | 2.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-91 | CF | | 25 | 100'N OF 25/26 & 6'W | P | 2 | x | 6 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-92 | CF | | 25 | BETWEEN RP-91 & RP-93 | | | X | | 120 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-93 | CF | | 25 | 121'N OF 25/26 & 12'W ( T-SHAPE) | P | 2 | x | 22 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-94 | CF | | 25 | BETWEEN RP-93 & RP-95 | | | x | | 84 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-95 | CF | 25/26 | | 110'N TO 129'N OF SEOS | P | 2 | x | 19 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-96 | DS-8 | 26/27 | | 128'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-97 | BO | 26/27 | | 71'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-98 | CF | | 27 | BETWEEN RP-97 & RP-100 | | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-99 | CR | 26/27 | | 38'N OF SEOS | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-100 | CF | | 27 | 55'N OF 26/27 & 13'E | P | 2 | x | 30 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-101 | CF | | 27 | BETWEEN RP-100 & RP-102 | | | x | | 144 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-102 | CF | | 27 | 87'N OF 26/27 & 7'E | P | 2 | x | 6.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-103 | CF | 27/28 | | 117'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-104 | CF | | 28 | BETWEEN RP-103 & RP-105 | | | x | | 156 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-105 | BO | 28/29 | | 120'N OF SEOS | P | 2 | x | 15 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

## *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 1730.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 2368.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-106 | CF | | 28 | BETWEEN RP-105 & RP-107 | | | x | | 192 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-107 | CF | | 28 | 134'N OF 27/28 & 4'E | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-108 | BO | 29/30 | | 125'N OF SEOS | P | 2 | x | 10 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-109 | DS-9 | 29/30 | | 80'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-110 | CF | | 28 | 85'N OF 28/29 & 3'W | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-111 | CF | | 28 | BETWEEN RP-110 & RP-112 | | | x | | 180 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-112 | WR | 28/29 | | 68'N OF SEOS | P | 2 | x | 8 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-113 | WR | | 28 | BETWEEN RP-112 & RP-114 | | | x | | 36 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-114 | WS | 28/29 | | 73'N OF SEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-115 | BO | 28/29 | | 61'N OF SEOS | P | 1.5 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-116 | WR | | 28 | 29'N OF 27/28 & 1'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-117 | WR | | 28 | BETWEEN RP-116 & RP-118 | | | x | | 72 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-118 | WR | | 28 | 29'N OF 27/28 &9'E | P | 2 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-119 | WR | | 28 | BETWEEN RP-118 & RP-120 | | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-120 | WR | | 28 | 29'N OF 27/28 & 13'E | P | 1 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-121 | BO | 27/28 | | 34'N OF SEOS | P | 2 | x | 7 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-122 | CF | | 27 | BETWEEN RP-121 & RP-123 | | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-123 | CF | | 27 | 34'N OF 27/28 & 5'W | P | 1.5 | x | 1.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-124 | CF | | 28 | 34'N OF 27/28 & 10'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-125 | CF | | 28 | BETWEEN RP-124 & RP-126 | | | x | | 108 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-126 | CF | | 28 | 45'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 1730.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 2368.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-127 | CF | | 28 | BETWEEN RP-126 & RP-128 | | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-128 | CF | | 28 | 48'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-129 | PB | | 11 | 80'N OF 10/11 & 8'E | P | 3 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-130 | DS-10 | 32/33 | | 20'N OF SEOS | P | 2 | x | 5.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-131 | DSX-4 | RP-102/27 | | ON EASTSIDE OF RP-102/27 | P | 2 | x | 5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-132 | PB | | 32 | 13'N OF 31/32 & 1'E | P | 3 | x | 4 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-133 | WR | 33/34 | | SEOS TO 21'N | P | 2.5 | x | 21 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-134 | WR | | 34 | BETWEEN RP-133 & RP-135 (N side) | | | x | | 84 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-135 | WR | | 34 | 18'N OF 33/34 & 11'E | P | 3 | x | 10 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-136 | WR | | 34 | FROM RP-135 TO SEOP | | | x | | 180 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-137 | WR | | 34 | BETWEEN RP-133 & RP-135 (S side) | | | x | | 120 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-138 | WR | | 34 | BETWEEN RP-137 & RP-139 | | | x | | 36 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-139 | WR | | 34 | 13'N OF 33/34 & 6'E | P | 1.5 | x | 1.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-140 | WR | | 34 | BETWEEN RP-135 & RP-141 | | | x | | 168 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-141 | WR | | 34 | 36'N OF 33/34 & 10'E | P | 1 | x | 2 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-142 | CF | | 30 | 112'N OF 29/30 & 5'E | P | 2 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-143 | CF | | 30 | BETWEEN RP-142 & RP-144 | | | x | | 48 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-144 | CF | | 30 | 98'N OF 29/30 & 7'E | P | 1.5 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-145 | | | | | | | x | | | | | | | | |
| RP-146 | | | | | | | x | | | | | | | | |
| RP-147 | | | | | | | x | | | | | | | | |

## Summary of Non-Compliance & Corrective Action Forms

***SA-6 South Cap Installation***

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 1 | 7/21/2015 | Subgrade Irregularity | RP-3 | Panel #2 (P-2) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2.5 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 2 | 7/21/2015 | Subgrade Irregularity | RP-8 | Panel #2 (P-2) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2.5 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 3 | 7/22/2015 | Failed Non-Destruct Test | RP-13 | Panel #7 (P-7) & Panel #8 (P-8) seam | Based on length of failed seam (approximately 6 ft.) the entire seam was patched and repaired (approximate 2 ft. by 6 ft. patch). The patch was overlapped a minimum of 4-inches, with rounded edges, and sealed with an extrusion weld. Vacuum box testing was then conducted in accordance with Section 02372-8 to confirm the weld. |
| 4 | 7/24/2015 | Subgrade Irregularity | RP-30 | Panel #17 (P-17) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 5 | 8/7/2015 | Failed Vacuum Box Test | RP-215 | Panel #50 (P-50) | Failed extrusion weld (identified during vacuum box testing) was patched with an approximate 2 ft. by 2 ft. geomembrane patch over the extrusion weld (noted as RP-222 on Repair Log). The patch was overlapped a minimum of 4-inches beyond the edges of the failed weld, conformed so that the edges were rounded, and sealed with an extrusion weld. Vacuum box testing was conducted along the seams to confirm the seams were properly patched and repaired. |

LANGAN

# Certificate of Soil Surface

Sheet # 1

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 10053001 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 24+35 TO STA 23+35 (WEST END) | | |
| QA Monitor | LANGAN | Date | 7/20/2015 | | |

Description of Soil Surface to be lined: WEST END OF SA-6 SOUTH (~STA. 24+35) TO APPROX. 100 FT. EAST (STA. 23+35) - RUNNING NORTH TO SOUTH THROUGH APPROX. GRID POINT ~~8~~ 13.09. SOIL APPEARS TO BE GRADED, COMPACTED AND FREE OF DEBRIS (> ½"), AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/20/15 |
| Title | ~~SENIOR STAFF~~ LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-20-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½") AS OUTLINED IN SECTION 02372-8

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | WEST END | N-S | REFER TO PHOTOGRAPH LOG (11/20/15) |
| | 2 | WEST END | N-S | PHOTOS 2, 3, 4 W/ DESCRIPTIONS |

1. REFER TO PHOTO LOG (11/20/15) PHOTOS 2, 3, 4 FOR CORRESPONDING PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 2

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 23+35 TO ~STA. 22+35 | | |
| QA Monitor | LANGAN | Date | 7/21/2015 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST FROM SUBGRADE APPROVAL ON 7/20/15. LOCATED FROM APPROX. STA. 23+35 TO STA. 22+35 (100 FT. EAST FROM INSTALLED CAP ON 7/20/15. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/21/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-22-15 |
| Title | Entrak QC Manager |
| Representing: | Entrak |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8.
GEOMEMBRANE CAP PANELS 5-9 PLACED OVER AREA.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | STA. 23+35 | LOOKING EAST | REFER TO PHOTO LOG (7/21/15), PHOTO #9 |
| | 2 PHOTO #10 | STA 23+35 | EAST/SOUTHEAST | REFER TO PHOTO LOG (7/21/15), PHOTO #10 |
| 1. REFER TO PHOTO LOG (7/21/15) PHOTOS 9,10 FOR SUPPORTING SUBGRADE PHOTOS. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 3

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530601 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | Sta. 22+35 to Sta. 21+40 | | |
| QA Monitor | Langan | Date | 7/22/15 | | |

Description of Soil Surface to be lined: Area immediately east from previously approved subgrade on 7/21/15. Located from approx. Sta. 22+35 to Sta. 21+40 (approx. 95 ft east of geomembrane installed on 7/21/15. Soil appears to be graded, compacted, and free of debris (1½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/22/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-23-15 |
| Title | QC Manager |
| Representing: | Entrust |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (7 ½")
As outlined in Section 02372-8

Geomembrane Cap Panels 10-13 Placed over Area

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo # 2 | | Looking East | Refer to Photo Log (7/22/15) Photo # 2 |
| | 2 Photo # 3 | | Looking NE | Refer to Photo Log (7/22/15) Photo # 3 |

1. Refer to Photo Log (7/22/15)
Photos 2, 3 for Supporting Substrate Photos

2.

LANGAN

# Certificate of Soil Surface

Sheet # 4

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / ANECFW | Cell No. | ~STA. 21+40 TO STA. 19+90 | | |
| QA Monitor | LANGAN | Date | 7/23/15 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST FROM PREVIOUSLY APPROVED SUBGRADE ON 7/22/15. LOCATED FROM APPROXIMATE STATION STA. 21+40 (~P-13) TO STA. 19+90 (APPROX 150 FT. EAST OF GEOMEMBRANE INSTALLED ON 7/22/15). SOIL APPEARS TO BE GRADED, COMPACTED + FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/23/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-23-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: Soil Graded, Compacted, And Fiber of Debris (2 ½")
As outlined in Section 023-72-8.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #3 | Sta 21+40 | Looking East | Refer to Photo Log (7/23/15) Photo #3 |
| | 2 Photo #5 | Sta 22+00 | Looking NE | Refer to Photo Log (7/23/15) Photo #5 |
| 1. Refer to Photo Log (7/23/15) Photos 3.5 for supporting subgrade photos<br>Additional subgrade details also shown on Photos 4+6 | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 5

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / ARNEC FW | Cell No. | ~STA. 19+90 TO STA. 19+00 | | |
| QA Monitor | LANGAN | Date | 7/24/15 | | |

Description of Soil Surface to be lined: ADDITIONAL ~90 FT. SECTION OF SOIL APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 7/23/15 (P-18). SUBGRADE APPROVED FROM ~STA. 19+90 TO STA. 19+00 (SUBGRADE PREVIOUSLY APPROVED TO STA. 19+90); GEOMEMBRANE INSTALLED TO ~STA. 20+25 ON 7/23/15), SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (≤ ½"), AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/24/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-24-15 |
| Title | QC Manager Entact |
| Representing: | Entact |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02372-8.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #8 | STA 20+25 | LOOKING EAST | REFER TO PHOTO LOG (11/24/15) PHOTO #8 |
| | 2 PHOTO #9 | STA. 19+80 | LOOKING SOUTH | REFER TO PHOTO LOG (11/24/15) PHOTO #9 |
| 1. REFER TO PHOTO LOG (11/24/15) PHOTOS 8,9 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 6

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | N Sta. 19+00 to Sta. 18+20 | | |
| QA Monitor | Langan | Date | 7/28/15 | | |

Description of Soil Surface to be lined: Additional ~80 ft. Section of Soil Approved East of Geomembrane Panels Installed on 7/24/15 (P-24). No Subgrade Approved on 7/27/15. Subgrade Approved From ~ Sta. 19+00 to Sta. 18+20. Soil Appears to Be Graded, Compacted, And Free of Debris (7½") And In Conformance With Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/28/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-28-15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 023172-8
- ADDITIONAL ~40 FT. OF SOIL APPROVED AT END OF DAY TO ALLOW ESI TO INSTALL EXTRA 2 PANELS OF GEOMEMBRANE SOIL APPROVED TO APPROX. STA 17+80.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~BD 6775-1584 | LOOKING NW | REFER TO PHOTO LOG (11/28/15) PHOTO #2 |
| | 2 PHOTO #4 | ~19.00 | LOOKING EAST | REFER TO PHOTO LOG (11/28/15) PHOTO #3 |
| 1. REFER TO PHOTO LOG (11/28/15) PHOTOS 3, 4, 5 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 7

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 179+80 TO STA. 177+00 | | |
| QA Monitor | LANGAN | Date | 7/29/15 | | |

Description of Soil Surface to be lined: ~280 FT. SECTION OF SOIL APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 7/28/15 (P-30). SUBGRADE APPROVED FROM APPROX. STA. 179+80 TO STA. 177+00, SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½"), AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/29/30 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/29/30 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED UP TO 1ST UTILITY CORRIDOR

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | STA. 17+80 | LOOKING N | REFER TO 7/29/15 PHOTO LOG PHOTO #5 |
| | 2 PHOTO #8 | SEND CAP | LOOKING E | REFER TO 7/29/15 PHOTO LOG PHOTO #8 |
| 1. REFER TO PHOTO LOG (7/29/15) PHOTOS 5, 8 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/20/15

**Direction Taken:**
Looking north toward Grid Point 11

**Description:**

Prepared soil subgrade approved for liner placement. Slopes compacted and free of loose debris > ½ inch.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/20/15

**Direction Taken:**

Looking north near Sta. 24+00

**Description:**

White plastic fasteners placed at minimum 5 ft. intervals along GVL geonet as outlined in specifications



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3(07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east along southern section of SA-6 (from approximate Sta. 23+35)

**Description:**

Prepared soil subgrade as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking north near Sta. 23+35

**Description:**

ESI sewing top of geotextile seem on GVL as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/22/15

**Direction Taken:**

Looking south along installed geomembrane panels.

**Description:**

ESI deploying geomembrane panels (P-10 through P-14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/22/15

**Direction Taken:**

Looking along geomembrane cap panels P-9 and P-10.

**Description:**

ESI conducting fusion welding between geomembrane P-9 and P-10 panel seams (as per project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/22/15

**Direction Taken:**

Looking along geomembrane panels

**Description:**

ESI conducting non-destructive air testing as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/23/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Installed geomembrane cap with GDL visible at far western end.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/24/15

**Direction Taken:**

Looking along geomembrane cap and extrusion welding RP-15.

**Description:**

ESI conducting extrusion welding on patches and repairs. Extrusion weld areas to be tested with vacuum box (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/27/15

**Direction Taken:**

Looking west along SA-6 (panel 20/21 seam)

**Description:**

ESI collecting destruct along Panel 23/24 seam (DS-7).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/27/15

**Direction Taken:**

Looking northwest – collection manhole in background (Sta.21+00)

**Description:**

ESI conducting vacuum box testing on RP-31 after completion of extrusion welding.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/29/15

**Direction Taken:**

Looking northeast along SA-6 cap

**Description:**

Installed geomembrane panels (P-31 & P-32). ESI conducting fusion welding (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #13 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/30/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Ramp built up to SA-6 for placement of cover soil over installed GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #14 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/30/15

**Direction Taken:**

Looking southeast along southern end of cap

**Description:**

ESI conducting booting activities for PZ-18 (located on P-32).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #15 (07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/31/15

**Direction Taken:**

Looking west along SA-6 (installed GDL)from approximate Sta. 17+20

**Description:**

Installed GDL up to approximate Sta. 17+20 along SA-6 (from western end).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #16 (07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/31/15

**Direction Taken:**

Looking south along geomembrane cap (near approx. Sta. 19+90)

**Description:**

ESI deploying GDL over previously installed geomembrane panels near Sta. 19+90 (over Panels 21 & 22).



# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 2, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 2 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 5 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 6 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 7 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 8 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 9 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/02/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
Thursday, July 02, 2015

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Exclusion Zone fencing is missing along the southwestern edge of the cap area. |
| 2 | IA2Q4A1AL8 | Spill pallets and other secondary containment vessels have accumulated stormwater. |
| 3 | IA2Q4A1AL8 | The cap area to the north of the 60 Kellogg building is graded to shed stormwater over the sheetpile hydraulic barrier. |
| 4 | IA2Q4A1AL8 | Gaps are present in the perimeter fence panels at the western end of Kellogg Street. |
| 5 | IA2Q4A1AL8 | Stormwater is ponded to the south of the hydraulic barrier on SA-6 South. |
| 6 | IA2Q4A1AL8 | The remaining Type C material stockpile requires a containment berm or tarping. |
| 7 | IA2Q4A1AL8 | Gaps are present in the perimeter fence to the west of the CWTP |
| 8 | IA2Q4A1AL8 | Additional erosion control measures are required around the soil screening operation on SA-7. |
| 9 | IA2Q4A1AL8 | Sediment is present on the southern SA-7 haul road. |
| 10 | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 07/02/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Reinstall Exclusion Zone fencing | 7-6-15 RAD |
| 2 | Drain stormwater from secondary containment vessels. | 7-7-15 RAD |
| 3 | Regrade the cap area (shape a swale and/or berm) to divert stormwater run-off to a low area within the EZ. | 7-7-15 RAD |
| 4 | Install clamps between temporary fence panels to keep them in alignment. | 7-7-15 RAD |
| 5 | Pump ponded stormwater to the CWTP | 7-7-15 RAD |
| 6 | Construct a containment berm around or tarp over the remaining Type C stockpile. | 7-7-15 RAD |
| 7 | Reposition the Jersey barriers/fence panels to close the gaps in the perimeter fence. | 7-6-15 RAD |
| 8 | Install silt fence or other comperable erosion control measures around the soil screening area and the new stockpiles. | 7-8-15 RAD |
| 9 | Clean up the remaining sediment on the SA-7 roadway. | 7-6-15 RAD |
| 10 | | |

**Construction Manager:** _____ **Date:** 07/09/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 10, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/10/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, July 10, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Erosion control measures are not present along the western toe of the SA-6 South cap area outside of the Exclusion Zone. |
| 2 | IA2Q4A1AL8 | There are gaps in the placement of the Exclusion Zone signs on the fencing surrounding the SA-6 south cap area |
| 3 | IA2Q4A1AL8 | Mud and silt has accumulated in the stone at the foot of the western SA-6 North to SA-7 ramp. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 07/10/15

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install erosion control measures as required. | 7-15-15 RAD |
| 2 | Install additional Exclusion Zone signs on the EZ fenceline as required. | 7-14-15 RAD |
| 3 | Clean accumulated sediment from the stone as needed. | 7-13-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/16/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 17, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 5 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 6 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 7 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/17/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, July 17, 2015

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | **REPEAT**: Erosion control measures are not present along the western toe of the SA-6 South cap area outside of the Exclusion Zone. |
| 2 | IA2Q4A1AL8 | A gap is present in the Exclusion Zone fencing on the western end of the SA-6 South cap area. |
| 3 | IA2Q4A1AL8 | The three stormwater catchbasins inside of the site at the western end of Kellogg Street require maintenance of silt protection measures. |
| 4 | IA2Q4A1AL8 | Pieces of removed storm drain pipe and other debris are present on the SA-6 South backfill area. |
| 5 | IA2Q4A1AL8 | The Exclusion Zone fence located on SA-6 North to the south of the trash pit requires additional signage |
| 6 | IA2Q4A1AL8 | The tarp covering the stockpile of Type C material on SA-6 North requires maintenance. |
| 7 | IA2Q4A1AL8 | Debris is present at various locations on the stone surface of SA-7 |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 07/17/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install erosion control measures at the gap in the bulkhead where the Degen Oil outfall is located. | 7-20-15 RAD |
| 2 | Install additional Exclusion Zone fencing as required. | 7-23-15 RAD |
| 3 | Clean accumulated sediment from the stone as needed. | 7-23-15 RAD |
| 4 | Install filter fabric baskets inside or silt fencing around the three catch basins. | 7-23-15 RAD |
| 5 | Install additional Exclusion Zone signs as required. | will be done next week |
| 6 | Reinstall the cover tarp on the stockpile. | Next week. |
| 7 | Pick up and remove the debris (fabric, silt fence, dunnage, etc.) located on the SA-7 stone areas. | 7-23-15 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/23/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 24, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 4 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/24/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, July 24, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Weeds/vegetation are present around the foundation wall of the 60 Kellogg Building. |
| 2 | IA2Q4A1AL8 | Silt fence along the western perimeter of the EA-8 excavation on SA-6 North requires maintenance. |
| 3 | IA2Q4A1AL8 | REPEAT: The Exclusion Zone fence located on SA-6 North to the south of the trash pit requires additional signage. |
| 4 | IA2Q4A1AL8 | REPEAT: The tarp covering the stockpile of Type C material on SA-6 North requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature **Date:** 07/24/15

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove and dispose of the vegatation. | 7-27-15 RAD |
| 2 | Re-install/maintain the silt fence as required. | 7-29-15 RAD |
| 3 | Install additional Exclusion Zone signs as required. | 7-27-15 RAD |
| 4 | Reinstall the cover tarp on the stockpile. | 7-26-15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 07/30/15

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (June 2015)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

July 14, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the June 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 6 | 01 | 15 | 6 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,050 | 82,612 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.43 | 0.46 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.050 | <0.050 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.2 | <5.2 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1189 | 0.1189 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

July 8, 2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 6 | 01 | 15 | 6 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,311,487 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 38,600,300 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 6/11/2015 | 7.8 | 6.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE July 8, 2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: June, 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 6/1/2015 | Angel Trujillo | 36288813 | 36361522 | 72,709 | 0.072709 | 7.62 | 0.673 | | | | | | | | | 0.41 |
| 6/2/2015 | Angel Trujillo | 36361522 | 36439287 | 77,765 | 0.077765 | 7.17 | 0.673 | | | | | | | | | 0.44 |
| 6/3/2015 | Angel Trujillo | 36439287 | 36517346 | 78,059 | 0.078059 | 7.26 | 0.673 | | | | | | | | | 0.44 |
| 6/4/2015 | Angel Trujillo | 36517346 | 36596563 | 79,217 | 0.079217 | 7.54 | 0.673 | | | | | | | | | 0.44 |
| 6/5/2015 | Angel Trujillo | 36596563 | 36673355 | 76,792 | 0.076792 | 7.45 | 0.673 | | | | | | | | | 0.43 |
| 6/6/2015 | Angel Trujillo | 36673355 | 36753779 | 80,424 | 0.080424 | 7.24 | 0.673 | | | | | | | | | 0.45 |
| 6/7/2015 | Angel Trujillo | 36753779 | 36829655 | 75,876 | 0.075876 | N/A | 0.673 | | | | | | | | | 0.43 |
| 6/8/2015 | Angel Trujillo | 36829655 | 36905531 | 75,876 | 0.075876 | 7.26 | 0.673 | | | | | | | | | 0.43 |
| 6/9/2015 | Angel Trujillo | 36905531 | 36982499 | 76,968 | 0.076968 | 7.24 | 0.673 | | | | | | | | | 0.43 |
| 6/10/2015 | Angel Trujillo | 36982499 | 37060139 | 77,640 | 0.07764 | 7.46 | 0.673 | | | | | | | | | 0.44 |
| 6/11/2015 | Angel Trujillo | 37060139 | 37136537 | 76,398 | 0.076398 | 6.94 | 0.673 | <5.2 | 7.8 | | <0.010 | <0.015 | <0.050 | <0.0002 | <0.020 | 0.43 |
| 6/12/2015 | Angel Trujillo | 37136537 | 37212028 | 75,491 | 0.075491 | 7.60 | 0.673 | | | | | | | | | 0.42 |
| 6/13/2015 | Angel Trujillo | 37212028 | 37291215 | 79,187 | 0.079187 | N/A | 0.673 | | | | | | | | | 0.44 |
| 6/14/2015 | Angel Trujillo | 37291215 | 37370403 | 79,188 | 0.079188 | 7.64 | 0.673 | | | | | | | | | 0.44 |
| 6/15/2015 | Angel Trujillo | 37370403 | 37444640 | 74,237 | 0.074237 | 7.55 | 0.673 | | | | | | | | | 0.42 |
| 6/16/2015 | Angel Trujillo | 37444640 | 37522990 | 78,350 | 0.07835 | 7.61 | 0.673 | | | | | | | | | 0.44 |
| 6/17/2015 | Angel Trujillo | 37522990 | 37599866 | 76,876 | 0.076876 | 7.59 | 0.673 | | | | | | | | | 0.43 |
| 6/18/2015 | Angel Trujillo | 37599866 | 37678614 | 78,748 | 0.078748 | 7.56 | 0.673 | | | | | | | | | 0.44 |
| 6/19/2015 | Angel Trujillo | 37678614 | 37756585 | 77,971 | 0.077971 | 7.54 | 0.673 | | | | | | | | | 0.44 |
| 6/20/2015 | Angel Trujillo | 37756585 | 37839197 | 82,612 | 0.082612 | 7.57 | 0.673 | | | | | | | | | 0.46 |
| 6/21/2015 | Angel Trujillo | 37839197 | 37913745 | 74,548 | 0.074548 | N/A | 0.673 | | | | | | | | | 0.42 |
| 6/22/2015 | Angel Trujillo | 37913745 | 37988293 | 74,548 | 0.074548 | 7.62 | 0.673 | | | | | | | | | 0.42 |
| 6/23/2015 | Angel Trujillo | 37988293 | 38064500 | 76,207 | 0.076207 | 7.58 | 0.673 | | | | | | | | | 0.43 |
| 6/24/2015 | Angel Trujillo | 38064500 | 38138184 | 73,684 | 0.073684 | 7.49 | 0.673 | | | | | | | | | 0.41 |
| 6/25/2015 | Angel Trujillo | 38138184 | 38215633 | 77,449 | 0.077449 | 7.61 | 0.673 | | | | | | | | | 0.43 |
| 6/26/2015 | Angel Trujillo | 38215633 | 38294192 | 78,559 | 0.078559 | 7.58 | 0.673 | | | | | | | | | 0.44 |
| 6/27/2015 | Angel Trujillo | 38294192 | 38375663 | 81,471 | 0.0815 | 7.61 | 0.673 | | | | | | | | | 0.46 |
| 6/28/2015 | Angel Trujillo | 38375663 | 38448936 | 73,273 | 0.073273 | N/A | 0.673 | | | | | | | | | 0.41 |
| 6/29/2015 | Angel Trujillo | 38448936 | 38522209 | 73,273 | 0.073273 | 7.53 | 0.673 | | | | | | | | | 0.41 |
| 6/30/2015 | Angel Trujillo | 38522209 | 38600300 | 78,091 | 0.078091 | 7.64 | 0.673 | | | | | | | | | 0.44 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,311,487 | 2.311487 | | | <5.2 | 7.8 | | <0.010 | <0.015 | <0.050 | <0.0002 | <0.020 | |
| | | | High: | 82,612 | | | | | | | | | | | High: | 0.46 |
| | | | Average: | 77,050 | | | | | | | | | | | Average: | 0.43 |

WW

JB96767

E

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42166.41177 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County / Phase: CS | COC# | 087-WW-061115 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ / Sampling Program: 087: JCIA | Lab Proj # (SDG): | |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | Lab ID | ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | Preservative: 3 / 3 / 3 / 1 / 2 / 2 / 0 / 0 / 2 | Site ID | HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | | Lab Job # | HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant: CH2M | | Authorized User: | Honeywell |
| Preliminary Data To | | | Text & Excel File Drive | Excel & Text File Order |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | Units | | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-061115-A | 6/11/2015 | 15:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | L23 |
| 2 | 087-WW | | | 087-WWE-061115-B | 6/11/2015 | 15:15 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | V204 |
| 3 | 087-WW | | | 087-WWI-061115 | 6/11/2015 | 15:25 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | G53 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Relinquished by: Frank Schroyer | pH= 6.94 S.U. @ 10.2° C | Company: AMEC Foster Wheeler | Received by | Company | | Condition | | Custody Seals Intact | |
| | Date/Time: 6/11/15 | | | Date/Time: 6-11-15 16:00 | | Cooler Temp. | | | |
| Relinquished by | | Company | Received by | Company | 6/11/15 | Condition | | Custody Seals Intact | |
| | Date/Time: 6/11/15 17:00 | | | Date/Time | 1700 | Cooler Temp. | 3.3 °F | | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

INITIAL ASESSMENT 3B (RK)

LABEL VERIFICATION (RK)

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE

Accutest LabLink@861664 13:47 07-Jul-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-061115-A | | |
| **Lab Sample ID:** | JB96767-1 | **Date Sampled:** | 06/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 673 | 10 | ug/l | 1 | 06/13/15 | 06/15/15 | BS | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 06/13/15 | 06/15/15 | BS | EPA 200.7 [2] | EPA 200.7 [5] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 06/13/15 | 06/16/15 | ND | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 06/13/15 | 06/13/15 | MA | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel [b] | < 50 | 50 | ug/l | 5 | 06/13/15 | 06/15/15 | BS | EPA 200.7 [2] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 06/13/15 | 06/15/15 | BS | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA36869
(2) Instrument QC Batch: MA36875
(3) Instrument QC Batch: MA36885
(4) Prep QC Batch: MP87083
(5) Prep QC Batch: MP87089

(a) Elevated detection limit due to dilution required for high interfering element.
(b) Elevated detection limit due to dilution required for matrix interference (indicated by failing internal standard on original analysis).

RL = Reporting Limit

Accutest LabLink@861664 13:47 07-Jul-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-061115-A | | |
| **Lab Sample ID:** | JB96767-1 | **Date Sampled:** | 06/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | 6.0 | 4.0 | mg/l | 1 | 06/15/15 | SP | SM2540 D-11 |
| pH [a] | 6.93 | | su | 1 | 06/11/15 17:06 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@861664 13:47 07-Jul-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-061115-A | | |
| **Lab Sample ID:** | JB96767-1A | **Date Sampled:** | 06/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 7.8 | 3.4 | mg/l | 1 | 06/11/15 20:20 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@861664 13:47 07-Jul-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-061115-B | | |
| **Lab Sample ID:** | JB96767-2 | **Date Sampled:** | 06/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T208804.D | 1 | 06/15/15 | DC | n/a | n/a | VT8571 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 1.7 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 2.7 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.25 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 13.6 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.44 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.27 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 59.4 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 2.5 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | ND | 1.0 | 0.22 | ug/l | |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-061115-B | | |
| **Lab Sample ID:** | JB96767-2 | **Date Sampled:** | 06/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 38.0 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 101% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 96% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 108% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 96% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@861664 13:47 07-Jul-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-061115-B | | |
| **Lab Sample ID:** | JB96767-2 | **Date Sampled:** | 06/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.2 | 5.2 | mg/l | 1 | 06/15/15 10:15 | BM | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending June 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. Submited to all Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor. Subimtted to all Parties on June 18, 2015. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Contractor only. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on June 22, 2015. |

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Contractor only. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the lIDPE up and over the SCB Wall. The prior detail showed both the GDl and geomembrane terminating at the wall. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 10 OF 25**

- **2015 Monthly Reports Part 3**

**9/11/2015**
**MONTHLY REPORT**

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

September 11, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Subject:** **Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-08**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from August 1 – August 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: August 2015 SA-6/7 Combined Monthly Progress Report No. 2015-08

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)

Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-08

**Project SA-6 & 7 Remediation**

## August 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 08/14/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights - Report No. 2015-07 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/18/15 | Special Master Conference Call | N/A |
| 08/20/15 | Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2, Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 08/21/15 | Updated Work Plan for In-Situ Treatment of Chromium-Impacted Soils<br>Treatment Area 10-1 Only<br>Study Area 6 North (Site 087)<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/24/15 | July 2015 Daily Quality Assurance (QA) Reports<br>Study Area 6 South<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/27/15 | Design Change Bulletins Response<br>Study Area 6<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/27/15 | Requested Design Change Bulletins<br>Study Area 6<br>Jersey City, New Jersey | Upload to the Louis Berger Group SharePoint Site |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 08/09/15 | 08/16/15 | 08/23/15 | 08/30/15 |
| Construction Management (AMEC) | 9 | 9 | 9 | 9 |
| Engineering (AMEC) | 1 | 1 | 1 | 1 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 49 | 48 | 40 | 39 |
| Arecon/US Ecology Subcontractors | 0 | 3 | 3 | 0 |
| Evoqua | 1 | 1 | 1 | 1 |
| B&B Drilling | 0 | 0 | 0 | 1 |
| **TOTAL STAFF** | **64** | **66** | **58** | **55** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected August PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- On August 16 through 18, Cornerstone personnel completed S-3 Mass Removal Injection Event No. 23 in Injection Well 088-IW-03.
- On August 5, Summit Drilling completed soil sampling to a depth of 70 feet at the at the proposed PW-3 location on the Difeo car dealership property. Laboratory grain size determinations were completed of selected soil samples from this boring.
- Continued screening of Celgene material for use as protective cover soils above geosynthetics.
- Continued abandonment of monitoring wells on SA-6 North. The wells that where abandoned include the following: 088-MW-002, 088-MW-102, 088-MW-103, 088-MW-115, 088-PZ-001, 088-PZ-002, and 115-E4-DO.

# C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed /refilled the polymer.

- Cleaned upstream process (tank 201 and tank 202) pH probes, and the tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on August 11, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 08/09/15 | 08/16/15 | 08/23/15 | 08/30/15 |
| Avg. Gallons Treated & Discharged (per day) | 77,459 | 77,432 | 78,222 | 78,560 |
| Average Flow (gpm) for Operating Period | 55 | 54 | 54 | 55 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 24 |
| GWTP Influent Tanks (gal.) | 9,582 | 7,147 | 7,000 | 6,852 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completion of the Excavation Area EA-8 excavation is pending post excavation sampling results.
- Completed excavation of Excavation Area EA-4.
- Completed excavation of relief trench on the cap side of the vertical hydraulic barrier wall adjacent to Excavation Area EA-5 in preparation for excavation.
- Began excavation of Excavation Area EA-5.
- Completed backfill placement in Excavation Area EA-7.
- Continued relocating soils from Area 3S to the SA-6 North Cap Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Entact/Horwith** | Tri-axle Dump | South Brunswick, NJ | MCUA | AB-10 Material | 9 | 25.91 | 2,410.37 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Excavation Areas EA-4 and EA-5<br>Volume Excavated - Total for Reporting Period: 899.11CY / Total to Date: 3,742.69 CY |
| **Backfill in Progress** | Historic Fill – SA-6 South western backfill area EA-7 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 08/09/15 | 8/16/15 | 8/23/15 | 8/30/15 |
| Mt. Hope 3/8" Stone | 101.93 | 0 | 0 | 0 |

- Screened Historic Fill was transferred and placed as backfill in EA-7. A total of 2 loads, totaling approximately 40 cubic yards was placed as backfill in EA-7. In addition, a total of 57 loads of less than 20ppm material, totaling approximately 608 cubic yards was placed as backfill in EA-7.
- Screened Celgene material was placed as protective cover soil in the SA-6 South cap area. A total approximately 6,000 cubic yards was placed as protective cover soil during the reporting period.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Completed installation of surcharge monitoring instrumentation.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- Continued installation of temporary sheet pile along Route 440. On August 4, 2015 the contractor broke an unmarked 6" water service to JCMUA. Repair of the 6" line was completed on August 5, 2015. Installation of the temporary sheet pile has been postponed until utilities are further delineated.
- Continued installation of the vertical hydraulic barrier wall east of the Trash Pit and along Route 440 from STA 0+00 to STA 3+10 (completed on August 5, 2015).

## G. CAPPING OPERATIONS

- A total of 111,127 sq. ft. of liner totaling 31% of the total cap area was deployed during the reporting period. The total liner area deployed to date is now 66%.
- Continued installation of geosynthetic cap components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- Continued general liner subgrade preparation in Area 2S and 3S.
- Continued cutting hydraulic barrier sheets to final elevation in SA-6 South Open Space Area.

- Continued removing asphalt on top of the SCB wall and smooth coating as necessary for geosynthetics installation detail.
- Continued installation of gas vent pipe installation.
- Began placement of protective cover soils and demarcation tape over the geocomposite drainage layer.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2015 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 | Not Specified, Est. 6/11/2014 | 9/11/2014, 1 yr. extension granted 10/6/14 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Not Specified, Est. 3/31/2014 | 6/23/2014 | 11/20/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete excavation of Area EA-8.
- Complete excavation of Area EA-5.
- Complete backfilling of excavation area EA-4 and EA-5.
- Initiate installation of the vertical hydraulic barrier wall within the Trash Pit.
- Continue installation of dewatering wells associated with the SA-6 North Excavation Areas EA-2 and EA-3.
- Begin Trash Pit Meadow Mat Repair.
- Continue liner subgrade and utility corridor preparation activities on SA-6 South.
- Continue installation of geosynthetic cap components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite Drainage layer.
- Continue screening Celgene material for use as liner protective cover soils.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Conduct S-3 Mass Removal injection Event No. 24 in well 088-IW-02.
- Complete PVSC Monthly compliance sampling.
- Implement the in-situ plan for the SA-6 North Treatment Area 10.
- Continue to coordinate the planned PW-3 extraction well/trench installation.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. *Groundwater Quality Data (conducted quarterly, not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
11. Capping Update
    - SA-6 South Cap Subgrade Progress Map
    - Repair Log
    - Non-conformance Log
    - Subgrade Approval Forms
    - QA Photo Log
    - Daily QA Reports (Langan)
12. Weekly SWPPP Reports
13. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (July 2015)
14. SA-6 North & South Design Change Tracking Log


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule

Study Areas 6 and 7 Combined Progress Report No. 2015-08
Attachment 1: Schedule – 6 Month Look Ahead

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/28/15

Task Milestone Summary Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Contractor fine grading along edge of Open Space Area.





**Site Photograph 2:** Covering geotextile with screened clean fill Kellogg St. properties.




**Site Photograph 3:** Fusion-welding two liner panels in Open Space Area.




**Site Photograph 4:** Installing sheet pile along Route 440 former City properties.




**Site Photograph 5:** Placement of geotextile along Kellogg St. properties.




**Site Photograph 6:** Screening of clean fill onsite to remove larger gravel.




**Site Photograph 7:** Spreading clean fill Kellogg St. properties.




**Site Photograph 8:** Trimming top elevation of barrier wall Kellogg St. properties.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of September 1, 2015

August 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties

Former Roosevelt Drive-In Site
(Remediation Complete)

Kellogg Street Properties

Hackensack River

Route 440

Kellogg Street

# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 07/01/15 | 6:30 | 14:00 | 7:30 | 33,791.38 | 33,923.97 | 132,590 | 33,923,520 | PVSC Compliance Sample Collected |
| 07/02/15 | 6:30 | 13:00 | 6:30 | 33,923.97 | 34,000.38 | 76,410 | 33,999,930 | |
| 07/06/15 | 7:00 | 13:30 | 6:30 | 34,000.38 | 34,066.66 | 66,280 | 34,066,210 | |
| 07/07/15 | 8:00 | 14:00 | 6:00 | 34,066.66 | 34,125.32 | 58,660 | 34,124,870 | |
| 07/08/15 | 6:30 | 13:30 | 7:00 | 34,125.32 | 34,199.65 | 74,330 | 34,199,200 | |
| 07/09/15 | 6:30 | 13:30 | 7:00 | 34,199.65 | 34,252.75 | 53,100 | 34,252,300 | |
| 07/10/15 | 6:30 | 12:00 | 5:30 | 34,252.75 | 34,298.94 | 46,190 | 34,245,390 | |
| 07/13/15 | 7:00 | 11:45 | 4:45 | 34,298.94 | 34,325.94 | 27,000 | 34,226,200 | |
| 07/14/15 | 6:30 | 12:30 | 6:00 | 34,325.94 | 34,396.15 | 70,210 | 34,269,410 | |
| 07/15/15 | 7:00 | 14:00 | 7:00 | 34,396.15 | 34,474.85 | 78,700 | 34,331,000 | |
| 07/16/15 | 6:30 | 13:00 | 6:30 | 34,474.85 | 34,526.84 | 51,990 | 34,382,990 | |
| 07/17/15 | 12:00 | 14:00 | 2:00 | 34,526.84 | 34,556.84 | 30,000 | 34,412,990 | |
| 07/21/15 | 6:30 | 14:30 | 8:00 | 34,556.84 | 34,653.22 | 96,380 | 34,509,370 | |
| 07/23/15 | 6:30 | 13:30 | 7:00 | 34,653.22 | 34,690.24 | 37,020 | 34,546,390 | |
| 07/24/15 | 10:30 | 13:30 | 3:00 | 34,690.24 | 34,702.10 | 11,860 | 34,558,250 | |
| 07/27/15 | 6:30 | 14:00 | 7:30 | 34,702.10 | 34,790.64 | 88,540 | 34,646,790 | |
| 07/31/15 | 6:30 | 14:30 | 8:00 | 34,790.64 | 34,908.04 | 117,400 | 34,764,190 | |
| 08/03/15 | 9:00 | 13:30 | 4:30 | 34,908.04 | 34,940.20 | 32,160 | 34,796,350 | |
| 08/04/15 | 10:30 | 21:30 | 11:00 | 34,940.20 | 35,081.91 | 141,710 | 34,938,060 | |
| 08/07/15 | 6:30 | 12:30 | 6:00 | 35,081.91 | 35,221.03 | 139,120 | 35,077,180 | PVSC Compliance Sample Collected |
| 08/10/15 | 6:15 | 12:00 | 5:45 | 35,221.03 | 35,298.93 | 77,900 | 35,155,080 | |
| 08/11/15 | 6:35 | 14:30 | 7:55 | 35,298.93 | 35,398.03 | 99,100 | 35,254,180 | |
| 08/12/15 | 6:30 | 13:30 | 7:00 | 35,398.03 | 35,457.13 | 59,100 | 35,313,280 | |
| 08/13/15 | 7:00 | 13:30 | 6:30 | 35,457.13 | 35,497.93 | 40,800 | 35,354,080 | |
| 08/14/15 | 7:00 | 13:00 | 6:00 | 34,497.93 | 35,552.43 | 54,500 | 35,408,580 | |
| 08/17/15 | 6:30 | 12:30 | 6:00 | 35,552.43 | 35,618.63 | 66,200 | 35,474,780 | |
| 08/19/15 | 8:00 | 15:00 | 7:00 | 35,618.63 | 35,662.04 | 43,410 | 35,518,190 | |
| 08/20/15 | 7:00 | 14:00 | 7:00 | 35,662.04 | 35,706.84 | 44,800 | 35,562,990 | |
| 08/21/15 | 7:00 | 13:30 | 6:30 | 35,706.84 | 35,724.91 | 18,070 | 35,581,060 | |
| 08/25/15 | 8:00 | 14:00 | 6:00 | 35,724.91 | 35,790.40 | 65,490 | 35,646,550 | |
| 08/28/15 | 7:00 | 13:00 | 6:00 | 35,790.40 | 35,841.14 | 50,740 | 35,697,290 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA-8 | <20 | 087-EA8-20-a,b | 1500 | 087-EA8-20-a1 | 6/24/2015 | 7:35 | <2.3 | Yes | | |
| | | | | 087-EA8-20-a2 | 6/24/2015 | 7:40 | <2.3 | Yes | | |
| | | | | 087-EA8-20-a3 | 6/24/2015 | 7:45 | <1.9 | Yes | | |
| | | | | 087-EA8-20-a4 | 6/24/2015 | 7:50 | <1.9 | Yes | | |
| | | | | 087-EA8-20-b1 | 6/24/2015 | 7:55 | <2.1 | Yes | | |
| | | | | 087-EA8-20-b2 | 6/24/2015 | 8:00 | 0.78 | Yes | | |
| | | | | 087-EA8-20-b3 | 6/24/2015 | 8:05 | 2.10 | Yes | | |
| | | | | 087-EA8-20-b4 | 6/24/2015 | 8:10 | <2.0 | Yes | | |
| EA-8 | <20 | 087-EA8-20-c (bermed / trench material) | 250 | 087-EA8-20-c1 | 6/24/2015 | 11:40 | <1.9 | * | | |
| | | | | 087-EA8-20-c2 | 6/24/2015 | 11:45 | <2.1 | * | | |
| | | | | 087-EA8-20-c3 | 6/24/2015 | 11:50 | <2.1 | * | | |
| | | | | 087-EA8-20-c4 | 6/24/2015 | 11:55 | <1.9 | * | | |
| EA7 | <20 | 087-EA7-20-a (bermed/trench material) | 900 | 087-EA7-20-a1 | 6/26/2015 | 13:15 | <1.8 | Yes | | |
| | | | | 087-EA7-20-a2 | 6/26/2015 | 13:20 | <1.4 | Yes | | |
| | | | | 087-EA7-20-a3 | 6/26/2015 | 13:25 | <1.4 | Yes | | |
| | | | | 087-EA7-20-a4 | 6/26/2015 | 13:30 | 5.5 | Yes | | |
| EA7 | <20 | 087-EA7-20-b West Pile | 600 | 087-EA7-20-b1 | 7/14/2015 | 8:52 | 5.2 | Yes | | |
| | | | | 087-EA7-20-b2 | 7/14/2015 | 8:56 | 2.6 | Yes | | |
| | | | | 087-EA7-20-b3 | 7/14/2015 | 9:00 | 4.3 | Yes | | |
| | | | | 087-EA7-20-b4 | 7/14/2015 | 9:03 | 2.8 | Yes | | |
| EA7 | <20 | 087-EA7-20-c East Pile | 200 | 087-EA7-20-c1 | 7/14/2015 | 9:06 | <.47 | Yes | | |
| | | | | 087-EA7-20-c2 | 7/14/2015 | 9:11 | <1.6 | Yes | | |
| 3S cap material | <240 | 124-3S-EX-a,b,c,d (Excess 3S material) | 3500 | 124-3S-EX-a1 | 8/10/2015 | 12:10 | 51.6 | | Yes | |
| | | | | 124-3S-EX-a2 | 8/10/2015 | 12:15 | 18.6 | * | | |
| | | | | 124-3S-EX-a3 | 8/10/2015 | 12:18 | 37.1 | | Yes | |
| | | | | 124-3S-EX-a4 | 8/10/2015 | 12:20 | 18.9 | * | | |
| | | | | 124-3S-EX-b1 | 8/10/2015 | 12:21 | 24.8 | | Yes | |
| | | | | 124-3S-EX-b2 | 8/10/2015 | 12:22 | 49.3 | | Yes | |
| | | | | 124-3S-EX-b3 | 8/10/2015 | 12:23 | 37.9 | | Yes | |
| | | | | 124-3S-EX-b4 | 8/10/2015 | 12:24 | 40.4 | | Yes | |
| | | | | 124-3S-EX-c1 | 8/10/2015 | 12:25 | 24.7 | | Yes | |
| | | | | 124-3S-EX-c2 | 8/10/2015 | 12:26 | 36.3 | | Yes | |
| | | | | 124-3S-EX-c3 | 8/10/2015 | 12:27 | 46.7 | | Yes | |
| | | | | 124-3S-EX-c4 | 8/10/2015 | 12:28 | 8.1 | * | | |
| | | | | 124-3S-EX-d1 | 8/10/2015 | 12:29 | 25.6 | | Yes | |
| | | | | 124-3S-EX-d2 | 8/10/2015 | 12:30 | 32.1 | | Yes | |
| | | | | 124-3S-EX-d3 | 8/10/2015 | 12:31 | 74.6 | | Yes | |
| | | | | 124-3S-EX-d4 | 8/10/2015 | 12:32 | 34.7 | | Yes | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'

N4 N3 N2 N1
S4 S3 S2 S1
E1 E2

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1
NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
S-C-B BARRIER (TYP.)
W6-SO W1-SO E5-SO E4-SO E3-SO
117-MW-A99

115-PZ-6
115-PZ-5
115-PZ-4
INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0
INTERIOR POOL ELEV. +4.0
COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)
COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

W3-SO W5-SO E1-SO E2-SO
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6
073-MW-BB11 073-MW-Y10 134-MW-V09 134-MW-Q08 140-MW-06 140-MW-07 125-MW-L03
MW-124-103L MW-124-102D MW-124-103D MW-124-102T
117-MW-A89 117-MW-A85

KELLOGG STREET
STATE ROUTE 139

STA. N1+10 STA. N5+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. E3+75 STA. E4+50 STA. E7+25
STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+80 STA. S4+38 STA. S3+85 STA. S0+50

LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE
100' 50' 0 100' 200'

IN PROGRESS
06-10-2015


STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | North | | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 9/3/2014 | | 5.3 | 5.9 | 6.1 | 5.9 | 2.7 | 5.6 | 5.2 | 4.8 | 6.7 | 6.3 | 5.6 | | | | | 3.4 | 4.2 | 4.3 | 7.2 | 8.8 | 8.6 |
| 9/18/2014 | | 5.0 | 5.8 | 5.9 | 5.7 | 2.6 | 5.0 | 5.1 | 4.8 | 6.5 | 6.1 | 5.6 | | | | | 2.9 | 3.8 | 4.1 | 6.9 | 5.4 | 8.6 |
| 9/30/2014 | | 5.0 | 5.7 | 5.8 | 5.8 | 2.6 | 3.6 | 5.0 | 4.7 | 6.5 | 6.0 | 5.6 | | | | | 4.5 | 3.1 | 3.7 | 5.6 | 4.1 | 4.8 |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | 2.3 | 3.0 | 5.0 | 4.6 | 6.4 | 5.9 | | 5.7 | 5.2 | 5.6 | | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | 2.8 | 3.1 | 5.1 | 4.7 | 6.7 | 6.2 | | 5.6 | 5.3 | 5.7 | | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | 3.8 | 5.1 | 5.0 | 4.6 | 6.5 | 6.4 | | 5.6 | 5.3 | 5.7 | | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | 5.3 | 6.6 | 5.2 | 4.9 | 6.9 | 6.9 | | 6.0 | 5.9 | 6.2 | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | 6.8 | 6.7 | 5.5 | 5.2 | 7.3 | 6.9 | | 6.4 | 6.2 | 6.7 | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | 8.6 | 7.3 | 5.4 | 5.0 | 7.2 | 6.7 | | 6.0 | 5.8 | 6.3 | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | 3.5 | 3.1 | | 5.6 | 6.6 | | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 5.0 | 6.6 | | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 4.2 | 6.7 | | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | 3.2 | 2.6 | 6.2 | | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | 2.3 | 2.0 | 6.0 | | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | 1.7 | 1.8 | 6.1 | | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO, North FS-4

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

EXISTING JCIA TRASH PIT

CONSERVATION EASEMENT

HYDRAULIC BARRIER (TYP)

STA. 0+00 TO 5+00 SEE SPECIAL INSTRUCTIONS FOR SEALING SHEETS SEE NOTE HB19 ON SHEET GN-004.

SEE NOTE HB21 ON SHEET GN-003

NEW JERSEY STATE HIGHWAY ROUTE 440

GEOMEMBRANE GRADE CONTOURS (TYP)

EXISTING SOIL CEMENT BENTONITE WALL

HYDRAULIC BARRIER AND SLURRY CEMENT BENTONITE WALL CONNECTION SN-201 SN-301

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET GN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |

MATCH LINE SHEET SN-202

Corner + 1 pair

088-SB-300 STA=7+74.70 OFFSET=2.7R EL=12.30

088-SB-301 STA=6+91.41 OFFSET=28.6R EL=12.50

088-SB-302 STA=3+89.99 OFFSET=1.3L EL=14.80

088-CPT-003 STA=3+33.68 OFFSET=22.7L EL=13.50

088-SB-303 STA=2+59.52 OFFSET=16.4L EL=10.70

088-CPT-001 STA=2+58.78 OFFSET=17.0L EL=10.70

088-CPT-004 STA=1+68.47 OFFSET=28.8L EL=10.80

088-CPT-005 STA=0+31.17 OFFSET=63.1L EL=13.20

087-CPT-002 STA=8+71.77 OFFSET=39.6R EL=12.30

Special EXISTING GRADE 5/5/15

Special 4/29/15

JCIA BUILDING

STA. 5+80 JCIA TRASH PIT
STA. 4+60 JCIA TRASH PIT

3/23/15 3/25/15 3/26/15 3/27/15 3/30/15 3/31/15 4/1/15 7/29/15 8/5/15 7/22/15 SCB-7/20/15 7/21/15

TYPICAL UTILITY CORRIDOR/ HYDRAULIC BARRIER CROSSING DETAIL C SN-201 CN-301

GEOMEMBRANE GRADE

HISTORIC FILL

SITE HISTORIC WATER TABLE (SEE NOTE 3)

STRATUM O

STRATUM D

STRATUM S1

JCIA TRASH PIT SEE NOTE JC2 ON SHEET GN-004

B SN-301

STA. 0+00 TO STA 5+00
SPECIAL INSTRUCTIONS FOR SEALING SHEETS SEE NOTE HB19 ON SHEET GN-004

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 10/10/13 | TDD | RJR | TDD | SGS | RJR |
| 0 | 06/07/13 | TDD | RJR | TDD | SGS | TDD |

HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWINGS FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Pln Prof.dwg PLOT DATE: Mon, 07 Oct 2013 PLOT TIME: 4:04 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | TDD | DR TDD CHK RJR | APVD | BCO |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2106 MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR | CHK | APVD |
| | TDD | TDD | RJR | SGS |

NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43507

COPYRIGHTING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 890-2329
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Capping Update

- SA-6 South Cap Subgrade Progress Map
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports




LEGEND

- SUBGRADE GRADING UNDERWAY
- SUBGRADE COMPLETE AND SURVEYED
- APPROVED FOR GEOSYNTHETIC DEPLOYMENT
- LINER DEPLOYED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP SUBGRADE PROGRESS MAP
08/13/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-127 | CF | | 28 | BETWEEN RP-126 & RP-128 | | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-128 | CF | | 28 | 48'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-129 | PB | | 11 | 80'N OF 10/11 & 8'E (PB 8") | P | 3 | x | 3 | 8 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-130 | DS-10 | 32/33 | | 20'N OF SEOS | P | 2 | x | 5.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-131 | DSX-4 | RP-102/27 | | ON EASTSIDE OF RP-102/27 | P | 2 | x | 5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-132 | PB | | 32 | 13'N OF 31/32 & 1'E (PB 8") | P | 3 | x | 4 | 8 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-133 | WR | 33/34 | | SEOS TO 21'N | P | 2.5 | x | 21 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-134 | WR | | 34 | BETWEEN RP-133 & RP-135(N.SIDE) | | | x | | 84 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-135 | WR | | 34 | 18'N OF 33/34 & 11'E | P | 3 | x | 10 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-136 | WR | | 34 | FROM RP-135 TO SEOP | | | x | | 180 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-137 | WR | | 34 | BETWEEN RP-133 & RP-135(S.SIDE) | | | x | | 120 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-138 | WR | | 34 | BETWEEN RP-137 & RP-139 | | | x | | 36 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-139 | WR | | 34 | 13'N OF 33/34 & 6'E | P | 1.5 | x | 1.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-140 | WR | | 34 | BETWEEN RP-135 & RP-141 | | | x | | 168 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-141 | WR | | 34 | 36'N OF 33/34 & 10'E | P | 1 | x | 2 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-142 | CF | | 30 | 112'N OF 29/30 & 5'E | P | 2 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-143 | CF | | 30 | BETWEEN RP-142 & RP-144 | | | x | | 48 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-144 | CF | | 30 | 98'N OF 29/30 & 7'E | P | 1.5 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-145 | DS-11 | 36/37 | | 90'W OF EEOS & SJ 34/36/37 | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-146 | SJ | 41/44/45 | | SJ 41/44/45 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-147 | SJ | 44/45/46 | | SJ 44/45/46 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-148 | SJ | 40/41/44 | | SJ 40/41/44 | P | 2 | x | 5.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-149 | SJ | 34/40/41 | | SJ 34/40/41 | P | 3 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-150 | SJ | 34/39/40 | | SJ 34/39/40 | P | 1.5 | x | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-151 | SJ | 34/38/39 | | SJ 34/38/39 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-152 | SJ | 34/37/38 | | SJ 34/37/38 | P | 2 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-153 | BO | 35/36 | | 84'W OF EEOS | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-154 | WR | | 36 | BETWEEN RP-153 & RP-155 | | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-155 | WR | | 36 | 84'W OF 35/36 & 5'S | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-156 | SJ | 34/35/36 | | SJ 34/35/36 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-157 | BO | 34/35 | | 10'S OF NEOS | P | 1.5 | X | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-158 | WR | | 35 | 65'W OF 35/36 & 11'N | P | 1.5 | X | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-159 | WR | | 35 | FROM RP-158 TO N.END OF P-35 | P | | x | | 144 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-160 | DS-12 | 42/43 | | 20'N OF SEOS | P | 2 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-161 | SJ | 43/44/46 | | SJ 43/44/46 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-162 | WR | 44/46 | | 5'W OF EEOS | P | 1.5 | X | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-163 | WR | | 44 | BETWEEN RP-162 & RP-164 | | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-164 | WR | | 44 | 5'W OF 44/46 & 5'N | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-165 | WR | | 44 | BETWEEN RP-162 RP-166 | | | x | | 216 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-166 | WR | 40/44 | | 16'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-167 | SJ | 40/42/43 | | SJ 40/42/43 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-168 | SJ | 39/40/42 | | SJ 39/40/42 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-169 | SJ | 38/39/42 | | SJ 38/39/42 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-170 | SJ | 37/38/42 | | SJ 37/38/42 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-171 | SJ | 36/37/42 | | SJ 36/37/42 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-172 | WR | 36/42 | | 6'S OF NEOS | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-173 | WR | | 42 | BETWEEN RP-172 & RP-174 | | | x | | 108 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-174 | WR | | 42 | 6'S OF 36/42 & 10'E | P | 3 | x | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-175 | CR | 35/42 | | 15'S OF NEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-176 | WR | | 42 | BETWEEN RP-174 & RP-175 | | | x | | 132 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-177 | SJ | 35/36/42 | | SJ 35/36/42 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-178 | CR | 35/36 | | 15'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-179 | WR | | 35 | 30'W OF 35/36 & 10'N | P | 2 | x | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-180 | WR | | 35 | FROM RP-179 TO N.END OF P-35 | | | x | | 156 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-181 | CR | 44/45 | | 11'W OF EEOS | P | 1.5 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBIOX | P | 8/4/15 |
| RP-182 | WR | | 44 | BETWEEN RP-181 & RP-183 | | | x | | 204 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-183 | CR | 40/44 | | 42'W OF EEOS | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-184 | BO | 40/44 | | 48'W OF EEOS | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-185 | SJ | 40/43/44 | | SJ 40/43/44 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-186 | DSX-5 | RP-160/42 | | ON RP-160/42 | P | 2 | x | 5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-187 | WR | | 42 | 7'N OF 39/42 &1'E TO 6'E | | | x | | 78 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-188 | PB | | 25 | 74'S OF 24/25 & 5'E (PB 8") | P | 3 | x | 3 | 8 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-189 | WR | | 35 | 15'W OF 35/36 & 16'N | P | 2 | x | 7 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-190 | WR | | 35 | BETWEEN RP-189 & RP-191 | | | x | | 84 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-191 | WR | | 35 | 15'W OF 35/36 & 6'N | P | 1.5 | x | 1.5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-192 | WR | | 36 | 10'W OF 36/37 & 7'N | P | 1.5 | x | 2 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-193 | WR | | 36 | BETWEEN RP-192 & RP-194 | | | x | | 180 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-194 | WR | | 36 | 10'W OF 36/37 & 24'N | P | 2 | x | 4 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-195 | BO | 47/48 | | 106'S OF NEOS | P | 2 | x | 6.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-196 | BO | 48/49 | | 86'S OF NEOS | P | 2 | x | 4 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-197 | BO | 53/54 | | 15'S OF NEOS | P | 2 | x | 7 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-198 | WR | 48/49 | | 94'S OF NEOS | P | 2 | x | 28 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-199 | CR | 42/47 | | 50'S OF NEOS | P | 2 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-200 | CF | | 47 | 56'S OF NEOS(SURFACE DESIGN) | P | 2 | x | 38 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-201 | CF | | 47 | 38'S OF 42/47 & 8'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-202 | CF | | 47 | BETWEEN RP-201 & RP-203 | | | x | | 240 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-203 | CF | | 47 | 59'S OF 42/47 & 18'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-204 | DS-13 | 47/48 | | 70'S OF NEOS | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-205 | CF | | 47 | FROM RP-200 TO MANHOLE | | | x | | 216 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-206 | WR | | 48 | 46'S OF 47/48 & 4'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-207 | WR | | 48 | BETWEEN RP-206 & RP-208 | | | x | | 180 | 8/7/15 | PEDRO S. | EXT 512 | VNOX | P | 8/7/15 |
| RP-208 | WR | | 48 | 64'S OF 48/49 & 6'W | P | 2 | x | 11 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-209 | WR | | 48 | BETWEEN RP-208 & RP-210 | | | x | | 36 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-210 | WR | | 48 | 57'S OF 48/49 & 4'W | P | 2.5 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-211 | DSX-6 | RP-198/48 | | ON W.END OF RP-198/48 | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-212 | WR | 49/50 | | 72'S OF NEOS | P | 2 | x | 9 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-213 | WR | | 50 | 75'S OF 49/50 & 8'E | P | 2 | x | 7 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-214 | WR | | 50 | BETWEEN RP-213 & RP-215 | | | x | | 24 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-215 | WR | | 50 | 78'S OF 49/50 & 2'E | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | F | 8/10/15 |
| RP-216 | SJ | 50/51/52 | | SJ 50/51/52 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-217 | SJ | 51/52/53 | | SJ 51/52/53 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-218 | PB | | 47 | 87'S OF 42/47 & 11'E(MANHOLE ) | P | 9.5 | x | 9.5 | 48 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-219 | PB | | 38 | 3'W OF 37/38 & 3'S (PB 8") | P | 3.5 | x | 4 | 8 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-220 | BO | 55/57 | | 101'N OF SEOS | P | 2 | x | 2.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-221 | BO | 55/57 | | 120'N OF SEOS | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-222 | WR | | 50 | REPAIR LEAK OVER RP-215 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-223 | DS-14 | 50/51 | | 35'S OF NEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-224 | WR | 51/53 | | 20'S OF NEOS | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-225 | WR | | 53 | BETWEEN RP-224 & RP-226 | | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-226 | WR | | 53 | 20'S OF 51/53 & 14'E | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-227 | WR | | 53 | 30'S OF 53/54 & 5'W | P | 1.5 | 2 | | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-228 | WR | | 53 | BETWEEN RP-227 & RP-229 | | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-229 | WR | | 53 | 35'S OF 51/53 & 5'W | P | 2 | x | 11 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-230 | DS-15 | 54/55 | | 72'S OF NEOS | P | 2 | x | 4.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-231 | SJ | 54/55/56 | | SJ 54/55/56 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-232 | SJ | 55/56/57 | | SJ 55/56/57 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-233 | CF | | 55 | 76'N OF 55/57 & 3'W | P | 2 | X | 13 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-234 | CF | | 55 | BETWEEN RP-233 & RP-235 | | | x | | 24 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-235 | CF | | 55 | 80'N OF 55/57 & 2'W | P | 2 | x | 3.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-236 | CF | | 58 | 128'S OF 57/58 7'E | P | 3 | x | 4 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-237 | CF | | 58 | BETWEEN RP-236 & RP-238 | | | x | | 168 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-238 | CF | | 58 | 140'S OF 57/58 & 20'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-239 | CF | | 58 | BETWEEN RP-236 & RP-240 | | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-240 | CF | | 58 | 125'S OF 57/58 & 17'E | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-241 | CF | | 58 | BETWEEN RP-239 & RP-242 | | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-242 | CF | | 58 | 128'S OF 57/58 & 15'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-243 | PB | | 58 | 75'S OF 57/58 & 6'E (PB 8") | | | x | | 8 | | | | | | |
| RP-244 | SJ | 58/59/60 | | SJ 58/59/60 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-245 | DSX-7 | RP-197/53 | | ON RP-197/53 | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-246 | PB | | 62 | 135'N OF 61/62 & 2'E (PB 8") | P | 3 | x | 4 | 8 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-247 | SJ | 59/60/61 | | SJ 59/60/61 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-248 | DS-16 | 59/61 | | 6'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-249 | DS-17 | 62/63 | | 90'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-250 | CR | | 65 | 2'N OF 65/66 & 5'E | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-251 | SJ | 64/65/66 | | SJ 64/65/66 | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-252 | BO | 65/66 | | 8'N OF SEOS | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap construction **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 2617 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 3766.83 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-253 | DS-18 | 64/65 | | 128'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-254 | DS-19 | 68/69 | | 100'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-255 | PB | | 71 | 9'N OF 71/72 & 5'W | P | 5 | x | 6 | 4 | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-256 | DS-20 | 72/73 | | 10'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-257 | PB | | 74 | 92'N OF 73/74 & 1'E (PB 8") | | | x | | | | | | | | |
| RP-258 | BO | 71/72 | | 57'N OF SEOS | P | 2 | x | 2 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-259 | BO | 71/72 | | 133'N OF SEOS | P | 2 | x | 2.5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-260 | BO | 74/75 | | 60'N OF SEOS | P | 2 | x | 6 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-261 | DS-21 | 74/75 | | 75'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-262 | PB | | | MANHOLE | | | x | | | | | | | | |
| RP-263 | | | | | | | x | | | | | | | | |
| RP-264 | | | | | | | x | | | | | | | | |
| RP-265 | | | | | | | x | | | | | | | | |
| RP-266 | | | | | | | x | | | | | | | | |
| RP-267 | | | | | | | x | | | | | | | | |
| RP-268 | | | | | | | x | | | | | | | | |
| RP-269 | | | | | | | x | | | | | | | | |
| RP-270 | | | | | | | x | | | | | | | | |
| RP-271 | | | | | | | x | | | | | | | | |
| RP-272 | | | | | | | x | | | | | | | | |
| RP-273 | | | | | | | x | | | | | | | | |

| Summary of Non-Compliance & Corrective Action Forms | | | | | |
|---|---|---|---|---|---|
| *SA-6 South Cap Installation* | | | | | |
| **Notice of Non-Compliance & Corrective Action Sheet Number** | **Date** | **Item** | **Associated Repair Number** | **Approx. Location** | **Follow Up Action Taken** |
| 5 | 8/7/2015 | Failed Vacuum Box Test | RP-215 | Panel #50 (P-50) | Failed extrusion weld (identified during vacuum box testing) was patched with an approximate 2 ft. by 2 ft. geomembrane patch over the extrusion weld (noted as RP-222 on Repair Log). The patch was overlapped a minimum of 4-inches beyond the edges of the failed weld, conformed so that the edges were rounded, and sealed with an extrusion weld. Vacuum box testing was conducted along the seams to confirm the seams were properly patched and repaired. |

LANGAN

# Certificate of Soil Surface

Sheet # 8

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 10053000.1 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 17+00 to Sta. 15+80 | | |
| QA Monitor | Langan | Date | 8/3/15 | | |

Description of Soil Surface to be lined: ~120 ft. section of soil approved east of geomembrane panels installed on 7/29/15 (P-34). Subgrade approved from approx. Sta. 17+00 to Sta. 15+80 (to east side of 1st utility corridor) through 1st utility corridor. Soil appears to be graded, compacted, and free of debris (>½") and in conformance w/ project specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - no changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/3/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | Cathleen Parrino - Entech QC Manager |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED FOR GCL PLACEMENT WITHIN UTILITY CORRIDOR + GEOMEMBRANE / GVL PLACEMENT OUTSIDE OF CORRIDOR

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | CORRIDOR | LOOKING N | REFER TO 8/3/15 PHOTO LOG PHOTO #1 |
| | 2 PHOTO #3 | CORRIDOR | LOOKING S | REFER TO 8/3/15 PHOTO LOG PHOTO #3 |
| 1. REFER TO PHOTO LOG (8/3/15) PHOTOS 1, 2, 3 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 9

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 15+80 TO ~STA. 15+10 | | |
| QA Monitor | LANGAN | Date | 8/5/15 | | |

Description of Soil Surface to be lined: ~170 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/3/15 (P-42). SUBGRADE APPROVED FROM ~STA. 15+80 TO ~STA. 15+10. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/5/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-5-15 |
| Title | QC Manager Entact |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7 ½")
AS OUTLINED IN SECTION 02372-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT ABOVE) GROUNDWATER ELEVATION

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | GP 165-15.4 | LOOKING W | REFER TO 8/5/15 PHOTO LOG PHOTO #5 |
| | 2 PHOTO #6 | STA. 15+80 | LOOKING S | REFER TO 8/5/15 PHOTO LOG PHOTO #6 |
| 1. REFER TO PHOTO LOG (8/5/15) PHOTOS 5, 6 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 10

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 15+10 TO ~STA 14+00 | | |
| QA Monitor | LANGAN | Date | 8/6/15 | | |

Description of Soil Surface to be lined: ~110 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/5/15 (P-49). SUBGRADE APPROVED FROM ~STA. 15+10 TO ~STA. 14+00. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/6/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-6-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #17 | ± STA. 15+10 | LOOKING E | REFER TO 8/6/15 PHOTO LOG (PHOTO #17) |
| | 2 PHOTO #9 | ± STA. 15+10 | LOOKING S | REFER TO 8/6/15 PHOTO LOG (PHOTO #9) |
| 1. REFER TO PHOTO LOG (8/6/15) PHOTOS 17, 8, AND 9 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 11

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~ STA. 14+00 TO ~ STA. 13+00 | | |
| QA Monitor | LANGAN | Date | 8/7/15 | | |

Description of Soil Surface to be lined: ~100 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/6/15 (P-54). SUBGRADE APPROVED FROM ~ STA. 14+00 TO ~ STA. 13+00. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/7/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/7/15 |
| Title | QC Manager |
| Representing: | Entech |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (> ½")
As outlined in Section 02317Z-8.
" No GCL Placed As Area Was Above Water Table (~1 ft.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #6 | Sta. 14+00 | Looking E | Refer to 8/17/15 Photo Log (Photo #6) |
| | 2 | | | |
| 1. Refer to Photo Log (8/17/15) Photo 6 For Supporting Subgrade Photos | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 12


| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Anec FW | Cell No. | ~Sta. 13+00 to ~Sta. 12+00 | | |
| QA Monitor | Langan | Date | 8/10/15 | | |

Description of Soil Surface to be lined: ~100 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 8/7/15 (P-60). Subgrade Approved From ~Sta. 13+00 to ~Sta. 12+00 Soil Appears to Be Graded, Compacted, And Free of Debris (> ½") And In Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/10/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Parnio |
| Date: | 8/10/15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (> 1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | 25TA. 13+00 | LOOKING N | REFER TO 8/10/15 PHOTO LOG (PHOTO #5) |
| | 2 PHOTO #6 | 25TA. 13+00 | LOOKING E | REFER TO 8/10/15 PHOTO LOG (PHOTO #6) |
| 1. REFER TO PHOTO LOG (8/10/15) PHOTOS #5, 6 FOR SUPPORTING SUBGRADE PHOTOS. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 13

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 12+00 TO ~STA. 11+00 | | |
| QA Monitor | LANGAN | Date | 8/13/15 | | |

Description of Soil Surface to be lined: ~100 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/10/15 (P-65). SUBGRADE APPROVED FROM ~STA. 12+00 TO ~STA. 11+00. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/13/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-13-15 |
| Title | QC Manager |
| Representing: | Entrac |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (>1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | @ STA 11+50 | LOOKING SW | REFER TO 8/13/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | @ STA 11+50 | LOOKING SE | REFER TO 8/13/15 PHOTO LOG (PHOTO #2) |

1. REFER TO PHOTO LOG (8/13/15) PHOTOS 1, 2 FOR SUPPORTING SUBGRADE PHOTOS.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 14

| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | Honeywell / AMEC FW | Cell No. | ~Sta. 11+00 to ~Sta. 10+20 |
| QA Monitor | Langan | Date | 8/14/15 |

Description of Soil Surface to be lined: ~80 ft. section of soil subgrade approved east of geomembrane panels installed on 8/13/15 (P-171). Subgrade approved from Sta. 11+00 to ~Sta. 10+20. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/14/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-14-15 |
| Title | QC Manager |
| Representing: | Entrada |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (> ½")
As outlined In Section 02372-8

- Soil Approved For GCL Placement Along Southern Slope (Lower Bench) of Southern Edge of SA-6 Area Below (to 1 ft. Above) Groundwater Table.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |
| 1. | | | | 2. |

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (08/03/2015)


| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/3/15

**Direction Taken:**
Looking south

**Description:**

GCL installed throughout utility corridor. ESI preparing to cover GCL with geomembrane cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (08/03/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/3/15

**Direction Taken:**

Looking west

**Description:**

ESI deploying geomembrane at northern end of utility corridor (oriented east to west)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3(08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking north/northwest along utility corridor

**Description:**

ESI conducting patch/repair work along utility corridor. Also conducting extrusion welding and vacuum box testing (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking southwest at (GV-6 location)

**Description:**

ESI constructing boot and placing sacrificial sheet around GV-6 (as outlined in project specification).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |


**Date:**
8/6/15

**Direction Taken:**

Looking south along SA-6 (approximate Sta 17+00)

**Description:**

ESI placing GDL over installed geomembrane panels (P-34 & P-35). White plastic fasteners spaced at a maximum of 5 ft. internals and geotextile seam sewn (according to project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/6/15

**Direction Taken:**

Looking northwest along western slope of utility corridor (approximately Sta. 16+50)

**Description:**

Installed GDL along utility corridor (western slope)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/6/15

**Direction Taken:**

Looking north along western end of SA-6 cap

**Description:**

Entact covering GDL along western end of cap with protective cover soils.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/6/15

**Direction Taken:**

Looking northwest along SA-6 cap at approximately Sta. 14+30)

**Description:**

ESI conducting fusion welding along installed panel seams (Panel 50-54).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/7/15

**Direction Taken:**

Looking South (RP-216)

**Description:**

ESI conducting vacuum box testing on seam joint located on southern edge of SA-6 (Panels 50, 51, 52).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/7/15

**Direction Taken:**

Looking north along SA-6 (approximately Sta. 13+75)

**Description:**

ESI deploying geomembrane over GVL (at approximately Sta. 13+75)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/10/15

**Direction Taken:**

Looking north along SA-6 (from approx. Sta. 13+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/10/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/10/15

**Direction Taken:**

Looking north along SA-6 (from approx. Sta. 13+00)

**Description:**

ESI deploying GVL along approved soil subgrade



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #13 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/12/15

**Direction Taken:**

Looking west along northern end of SA-6 cap (at well 115-W5-SO)

**Description:**

ESI constructing geomembrane boot around monitoring well 115-W5-SO



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #14 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/12/15

**Direction Taken:**

Looking east along SA-6 (through 1st utility corridor)

**Description:**

ESI deploying GDL along eastern slope of utility corridor (approximate Sta. 16+50) working from the south end to the north end of the corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #15 (08/13/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/13/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 12+00)

**Description:**

ESI placing geomembrane cap over GVL (at approx. Sta. 12+00)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #16 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 cap (at Panel 74/75 seam)

**Description:**

ESI collecting destruct sample (DS-21) at Panel 74/75 seam (fusion weld).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 8/3/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 73/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0600 – 1945 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #13** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #34 (P-34) installed on 7/29/15 (located at approximate Sta. 17+00) running through first utility corridor approximately 120 ft. east to Sta. 15+80 (to eastern end of 1st utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing an additional two panels of GDL (moving east from Panel #33) to cover up to geomembrane Panel #34 (P-34). While GDL was being placed, Langan and Entact conducted soil subgrade approval from approximate Sta. 17+00 to Sta. 15+80 (through 1st utility corridor). Refer to *Soil Subgrade Approval* forms from 8/3/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1,2, and 3 of the daily photo log for 8/3/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 17+00 to Sta. 15+80 (to eastern side of 1st utility corridor).
- Geocomposite clay liner (GCL), GVL and Cap placement began with ESI placing the GCL along the bottom and slopes of the utility corridor (shown in the *8/3/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite. Note: Prior to GCL placement, a soil transition slope (approx. 2 ft. by 2 ft. was constructed along the northern slope of the utility corridor to allow the GCL to transition over the slope without having to conform to the 90 deg. turns of the SCB wall). This soil slope modification was approved prior to construction.
- In addition to the GCL (placed within the utility corridor), 16 oz. geotextile was placed along the boundaries of the SA-6 South Cap (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/3/15 Photo Log* for supporting photographs.

- After installation of GCL and GVL through the utility corridor, geomembrane cap was installed continuing east of previously installed Panel #34 (located at approximate Sta. 17+00) on 7/29/15. Panels were oriented from east to west through the utility corridor (as proposed in the approved Panel Layout) and were installed through the utility corridor (located at approx. Sta. 16+50) running from the top of the western slope to the top of the eastern slope. Additional panels were installed outside of the utility corridor and were T (butt seamed) into the east-west panels from inside the utility corridor (the panels outside of the utility corridor reverted back to the north-south orientation as indicated on the approved panel layout). A total of twelve panel lengths (different dimensions and sizes) were installed (P-35, P-36, P-37, P-38, P-39, P-40, P-41, P-42, P-43, P-44, P-45, and P-46) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/3), *Trial Weld Log.*
- Installation and welding of the geomembrane panels was conducted until approximately 8 pm to ensure that the utility corridor was properly covered and sealed due to expected overnight storms. As such, no non-destructive testing on the installed panels was conducted. Additionally, no patch / repair work was completed, and no destructive samples were collected. These activities will be completed tomorrow (8/4/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no patch / repair work was conducted on geomembrane cap.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/3/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 15+80 to Sta. 14+80) east of utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/3/15 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 7/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/3/15 |
| A5 – Subgrade Approval | Sheet 8 & ESI (8/3/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/3/15. |
| A7 – Panel Placement Log | Page 8 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/3/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/3/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 8/3/15 |
| A10 – Repair Log | | N / A no repairs conducted on 8/3/15 |
| A11 – Conformance COC | | N / A for 8/3/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 8/3/15 |
| A13 – Destruct. Sample Summary | | N / A no updates to form (no samples collected on 8/3) |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/3/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/4/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/85° F, AM Rain, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #14** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from east of Panel #42 installed on 8/3/15 (located at approx. Sta. 15+80) moving east approximately 100 ft. to approximate Sta. 14+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Based on the AM storms / rain, ESI could not conduct patch / repair work (i.e. extrusion welding) on the geomembrane panels installed on 8/3/15 due to the inclement weather. Observation of the next section of soil subgrade (approx. Sta. 15+80 to 14+80) was conducted and soft / wet areas were identified with ponding water (due to the storms). As such, soil subgrade was not approved for additional panel placement. Refer to *8/4/15 Photo Log* for subgrade photos. ESI offsite until 12 PM for weather to clear.
- Entact removed the protective plastic layer covering the soil subgrade and conducted drying activities, re-grading, and re-compaction of the soil (as required).
- ESI back onsite at approximately 12 PM to conduct patch / repair work for the panels installed on 8/3/15 (Panels 35-46). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 8/4/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-one repairs (RP-145 through RP-185) were observed and fixed (according to the project specifications) from Panel #35 through Panel #46 (repair / detailing work conducted on panels installed on 8/3/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- No non-conformance issues were noted as repairs consisted of custom fit design or routine patch / repair work to allow geomembrane to conform to SA-6 contours.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of two destruct samples, DS-11 and DS-12 (fusion weld samples) were collected for laboratory analysis. DS-11 was collected from panel seam 36/37 and DS-12 was collected from panel seam 42/43

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 8/4/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/4/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).
- Review laboratory results for DS-11 and DS-12

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work to remove soft / wet areas for the next 80 ft. run east (approximately from Sta. 15+80 to Sta. 15+00) of 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/4/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 8/4/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 8/4/15 |
| A6 – Trial Weld Log | Page 2 | Preweld test form for 8/4/15 provided by ESI and confirmed by Langan for prewelds up to 8/4/15 |
| A7 – Panel Placement Log | | N / A no panels placed on 8/4/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 8/4/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 7,8,9 | Seam Control Form for 8/4/15 provided by ESI and confirmed by Langan for non-destruct tests completed up to 8/4/15 |
| A10 – Repair Log | Pages 7,8,9 | Repair Log for 8/4/15 provided by ESI and confirmed by Langan for repairs completed up to 8/4/15 |
| A11 – Conformance COC | | N / A for 8/4/15 |
| A12 – Destructive Seam Field Test | Sheet 2 | Destruct Sample Information provided by ESI and confirmed by Langan for destruct samples collected on 8/4/15 (DS-11 and DS-12) |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with destruct sample information from 8/4/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 8/5/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 70/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0600 – 1700 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #15** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #42 (P-42) installed on 8/3/15 (located at approximate Sta. 15+80) running approximately 70 ft. east to Sta. 15+10.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work for three wrinkles (refer to *Repair Log* 8/5/15) that were identified along Panels 35-46 which were placed on 8/3/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/5/15).
- A total of nine repairs (RP-186 through RP-194) were observed and fixed (according to the project specifications) from Panel #35 and Panel #36. As outlined above, these repairs were associated with removing geomembrane wrinkles to allow the cap to conform to the contours of SA-6 South grade. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications. Note: no repairs of the geomembrane from 8/5/15 were identified as non-compliance issues.
- Additionally, while the geomembrane was being patched / repaired, ESI also installed the penetration boots for the wells, piezometers, and gas vents protruding through the cap (Note: Penetration logs will be completed once final sealant is placed around top of boot). Orange composite (GDL) was also placed over butt seams of the geocomposite and leistered in place. These patching activities were completed (as needed) to allow Entact to continue placing protective cover soil over the installed GDL along the western end of SA6. The final GDL layer was inspected by Entact and Langan to ensure that all repairs / patches were completed prior to soil placement.
- While patch / repair work was being conducted, Langan and Entact conducted soil subgrade approval from approximate Sta. 15+80 to Sta. 15+10. Refer to *Soil Subgrade Approval* forms from 8/5/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

the surface was free of any loose material. Refer to Photos #5,6 of the daily photo log for 8/5/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 15+80 to Sta. 15+10.

- Cap placement began with ESI placing the GCL along the southern slope (lower bench along southern end of SA-6 located below the groundwater table) of the southern edge of SA-6 (refer to *8/5/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- In addition to the GCL (placed along the southern slope), 16 oz. geotextile was placed along the northern boundary of the SA-6 South Cap, and also along the southern boundary east of the GCL (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.
- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/5/15 Photo Log* for supporting photographs.
- After installation of GCL and GVL along the SA-6 boundaries, geomembrane cap was installed continuing east of previously installed Panel #42 (located at approximate Sta. 15+80) on 8/3/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GCL layers. A total of three panel lengths were installed (P-47, P-48, P-49) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/5), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. As such, no non-destructive testing on the installed panels was conducted. Additionally, no patch / repair work was completed, and no destructive samples were collected. These activities will be completed tomorrow (8/6/15). Note: An extrusion weld sample (DSX-5) was collected from the patch / repair work previously completed on 8/4/15.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as repair work was conducted to remove wrinkles from the cap to allow the geomembrane to properly conform to the contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/5/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).
- Review laboratory data for extrusion destruct sample DSX-5

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, and 8/4/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 15+10 to Sta. 14+10) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/5/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 8/5/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/5/15 |
| A5 – Subgrade Approval | Sheet 9 & ESI (8/5/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/5/15. |
| A7 – Panel Placement Log | Page 10 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/5/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with information from destruct sample (DSX-5) collected on 8/5/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 8/5/15 |
| A10 – Repair Log | Pages 9-10 | One Repair Log provided by ESI and confirmed by Langan for 8/5/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/5/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destruct sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/5/15 |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with destruct sample information from 8/5/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/5/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/6/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1600 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #16** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #49 (P-49) installed on 8/5/15 (located at approximate Sta. 15+10) running approximately 110 ft. east to Sta. 14+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL over the previously installed geomembrane panels from 8/3/15. A total of 10 panel lengths of GDL were placed along the west side of the utility corridor and along the western slope of the utility corridor with end points of the GDL terminating along the approximate center of the utility corridor (east to west orientation). The GDL was placed north to south outside of the corridor and east to west within the corridor and secured with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile was sewn (according to the project specs).
- While GDL was being placed over the previously installed geomembrane, Langan and Entact conducted soil subgrade approval from approximate Sta. 15+10 to Sta. 14+00. Refer to *Soil Subgrade Approval* forms from 8/6/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #7,8, and 9 of the daily photo log for 8/6/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 15+10 to Sta. 14+00.
- Cap placement began with ESI placing the GCL along the southern slope (lower bench along southern end of SA-6 located below the groundwater table) of the southern edge of SA-6 (refer to *8/6/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with granular bentonite.
- Prior to deploying any geomembrane panels over the GCL, it was confirmed that the GCL maintained intimate contact between the material and the HB wall (southern boundary wall). Soil was removed from the top of the sheet piles (as required) by Entact. Refer to Photo #14 of the *Photo Log 8/6/15*.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- In addition to the GCL (placed along the southern slope), 16 oz. geotextile was placed along the northern boundary of the SA-6 South Cap, and also along the southern boundary east of the GCL (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.
- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/6/15 Photo Log* for supporting photographs.
- After installation of GCL, 16 oz. geotextile (along SA-6 boundaries) and GVL, geomembrane cap was installed continuing east of previously installed Panel #49 (located at approximate Sta. 15+10) on 8/5/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of four panel lengths (lengths defined as running the approximate 165 ft. north to south distance of the cap) were installed (P-50, P-51, P-52, P-53, P-54) by ESI. Note: P-51 terminated approximately 6 ft. short of the southern boundary of the SA-6 cap. As such, the remaining section was taken from an additional roll (G15C277060) and labeled as Panel #52 (P-52).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/6), *Trial Weld Log.*
- Upon panel installation and fusion welding, ESI conducted non-destructive seam testing in accordance with the project specs. No patch / repair work was completed, and no destructive samples were collected as work activities were completed after non-destruct testing was completed. These additional activities will be completed tomorrow (8/7/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as non-destruct testing was in conformance with the project specs and no patch / repair work, or vacuum box testing was conducted on 8/6/15.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/6/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, and 8/5/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-5. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 14+00 to Sta. 13+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/6/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 8/6/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/6/15 |
| A5 – Subgrade Approval | Sheet 10 & ESI (8/6/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Pages 2-3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/6/15. |
| A7 – Panel Placement Log | Page 11 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/6/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/6/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 11-12 | Seam Control Form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/6/15 |
| A10 – Repair Log | | N / A no repairs completed on 8/6/15 |
| A11 – Conformance COC | | N / A for 8/6/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 8/6/15 |
| A13 – Destruct. Sample Summary | | N / A no updates as no destruct samples collected |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/6/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/7/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 68/82° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1530 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #17** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #54 (P-54) installed on 8/6/15 (located at approximate Sta. 14+00) running approximately 100 ft. east to Sta. 13+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 50-54 which were placed on 8/6/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/7/15).
- A total of twenty-three repairs (RP-195 through RP-217) were observed and fixed (according to the project specifications) from Panels #50 through Panel #54 (repair / detailing work conducted on panels installed on 8/6/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- No non-conformance issues were observed as patch / repair work consisted of custom fit repairs to allow the geomembrane cap to conform to SA-6 contours.
- A total of three destruct samples were collected (DS-13, DS-14, and DSX-6). DS-13 and DS-14 (fusion) were collected from Panels 47/48 and 50/51, respectively. DSX-6 (extrusion) was collected from Panel #48 on RP-198.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for Collection Manhole #2. Note: The penetration log for Collection Manhole #2 will be completed once the boot has been sealed and covered according to the project specifications (to be completed on 8/10/15), and the final sealant is placed around top of boot.
- Langan and Entact conducted soil subgrade approval from approximate Sta. 14+00 to Sta. 13+00 while

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

patch work was being completed by ESI. Refer to *Soil Subgrade Approval* forms from 8/7/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material.Refer to Photo #6 of the daily photo log for 8/7/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 14+00 to Sta. 13+00.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 14+00 (east of P-54) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/7/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #54 (located at approximate Sta. 14+00) on 8/6/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-55, P-56, P-57, P-58, P-59, P-60) by ESI. Note:, during placement of Panel #55 and #59, the roll of geomembrane was completed, thus, Panel #56 was placed for the last 11 ft. (from roll G15C283029) to complete the southern end and Panel #60 (P-60) was placed for the last 15 ft. (from roll G15C276053) to complete the northern end of SA-6.
- During installation of the Cap, geomembrane seams were overlapped a minimum of 4-inches for fusion welding (according to project specs). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specs. A total of six 1-inch specimens were collected for peel and shear testing (3 samples/each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/7), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. Once completed, non-destructive testing on the installed panels was conducted. Non-destruct testing was conducted in accordance with the project specs and is further summarized on the *Seam Control Form (8/7/15).* After non-destructive testing the work day was terminated and no patch / repair work was completed. These activities will be completed on Monday (8/10/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 8/7/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/7/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 14+35).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-13, DS-14 and DSX-6

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, and 8/6/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-5. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 13+00 to Sta. 12+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/7/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/7/15 |
| A5 – Subgrade Approval | Sheet 11 & ESI (8/7/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/7/15. |
| A7 – Panel Placement Log | Page 12 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/7/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/7/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 12-14 | One Seam Control form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/7/15 |
| A10 – Repair Log | Pages 10-12 | One Repair Log provided by ESI and confirmed by Langan for 8/7/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/7/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected for 8/7/15 |
| A13 – Destruct. Sample Summary | | N / A no updates as no destruct samples collected on 8/7/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | One Notice of Non-Compliance form created by Langan (Sheet #26) for failed vacuum box test |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/10/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/78° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #18**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #60 (P-60) installed on 8/7/15 (located at approximate Sta. 13+00) running approximately 100 ft. east to Sta. 12+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 55-60 which were placed on 8/7/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/10/15).
- A total of thirty-one repairs (RP-218 through RP-248) were observed and fixed (according to the project specifications) from Panels #55 through Panel #60 (repair / detailing work conducted on panels installed on 8/7/15). Refer to 8/10/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for well 115-W5-SO, and completed placing the geomembrane patch around Access Manhole #2. Note: The penetration log for well 115-W5-SO will be completed once the boot has been sealed and covered according to the project specifications and the final sealant is placed around top of boot.
- Langan and Entact conducted soil subgrade approval from approximate Sta. 13+00 to Sta. 12+00 while patch work was being completed by ESI. Refer to *Soil Subgrade Approval* forms from 8/10/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #5 and #6 of the daily photo log for 8/10/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 13+00 to Sta. 12+00.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 13+00 (east of P-60) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/10/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #60 (located at approximate Sta. 13+00) on 8/7/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-61, P-62, P-63, P-64, and P-65) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/10), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. Once completed, non-destructive testing on the installed panels was conducted. Non-destruct testing was conducted in accordance with the project specs and is further summarized on the *Seam Control Form (8/10/15).* After non-destructive testing the work day was terminated and no patch / repair work was completed.
- A total of three destructive samples were collected (two fusion and one extrusion weld). Fusion weld destruct samples (DS-15, DS-16) were collected from Panel Seams 54/55 and 59/61 respectively. DSX-7 was collected along Panel 53/54 seam. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/10/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-15, DS-16, DS-17, and DSX-7

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, and 8/7/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-14, and DSX-1 through DSX-6. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 12+00 to Sta. 11+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/10/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 8/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/10/15 |
| A5 – Subgrade Approval | Sheet 12 & ESI (8/10/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/10/15. |
| A7 – Panel Placement Log | Page 13 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/10/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct samples collected on 8/10/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 12-14 | One Seam Control form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/10/15 |
| A10 – Repair Log | Pages 10-12 | One Repair Log provided by ESI and confirmed by Langan for 8/10/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/10/15 |
| A12 – Destructive Seam Field Test | Page 12 | One destruct sample information form provided by ESI and confirmed by Langan for 8/10/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with destruct sample information from 8/10/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted on 8/10/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 8/12/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 71/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #19**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT** / **ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-65) installed on 8/10/15 (located at approximate Sta. 12+00) running approximately 100 ft. east to Sta. 11+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 61-66 which were placed on 8/10/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/12/15).
- A total of four repairs (RP-249 through RP-252) were observed and fixed (according to the project specifications) from Panels #64 through Panel #66 (repair / detailing work conducted on panels installed on 8/10/15). Refer to 8/12/15 *Repair Report* for supporting information. The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed / construction penetration boots for well 115-W5-SO and gas vent #5 (GV-5). Note: These penetration logs will be completed once the final clamps and seal (butyl seal) have been completed according to the project specifications and the final sealant is placed around top of boot.
- While ESI was conducting repair / patch work, Langan and Entact conducted soil subgrade observation from approximate Sta. 12+00 to Sta. 11+00. Based on visual inspection, the soil subgrade appeared to contain areas of soft / wet subgrade due to rainstorms from 8/11/15. Based on these soft areas, soil subgrade was not approved for geomembrane placement. Entact conducted additional preparation work (i.e. drying the soil and re-grading and re-compacting) as required, to conform the subgrade to the project specifications (refer to Photo #7 of the daily photo log for 8/12/15)

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After completing patch / repair work from the panels installed on 8/10/15, ESI began to place GDL continuing east along the utility corridor. GDL was placed along the eastern slope of the utility corridor (located at approximate Sta. 16+50). Panels were oriented east to west within the utility corridor, and reverted back to the north and south orientation outside of the corridor (refer to the *8/12/15 Photo Log* for supporting photos)
- GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/12/15 Photo Log* for supporting photographs.
- No new geomembrane panels were placed as the soil subgrade for the next 100 ft. section was not approved. No destruct samples were collected, as DS-17 was collected on 8/10/15 during panel placement.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 5 ft. spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no new geomembrane panels were placed and the patch / repair work conducted on geomembrane cap was in compliance with the project specifications.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/12/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, and 8/10/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 12+00 to Sta. 11+00) east of utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/12/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/12/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/12/15 |
| A5 – Subgrade Approval | | N / A no subgrade approved due to soft / wet conditions observed from storms on 8/11/15 |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/12/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 8/12/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/12/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 14-15 | Updated with vacuum box test conducted from 8/12/15 on Panels 64/66 |
| A10 – Repair Log | Pages 11-12 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 8/12/15 |
| A11 – Conformance COC | | N / A for 8/12/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/12/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/12/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/12/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/13/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #20** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-65) installed on 8/10/15 (located at approximate Sta. 12+00) running approximately 100 ft. east to Sta. 11+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 12+00 to Sta. 11+00. Refer to *Soil Subgrade Approval* forms from 8/13/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 8/13/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 12+00 to Sta. 11+00. Note: The soft / wet areas identified on 8/12/15 were allowed to dry and were repaired for geomembrane placement.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 12+00 (east of P-65) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/13/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #65 (located at approximate Sta. 12+00) on 8/10/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

installed (P-67, P-68, P-69, P-70, and P-71) by ESI.

- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/13), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 11+00, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (8/13/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, no patch / repair work was conducted, and any associated repairs will be completed on 8/14/15.
- After completing non-destructive testing along the panels installed today (8/13/15), ESI began to place GDL continuing east from the 1st utility corridor (located at approx. Sta. 16+50). Panels were oriented from north to south (as outlined in the proposed GDL layout). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/13/15 Photo Log* for supporting photographs.
- A total of two destructive samples were collected (two fusion welds). Fusion weld destruct samples (DS-18, DS-19) were collected from Panel Seams 64/65 and 68/69, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 55-inch spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17, DS-18, and DS-19 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, and 8/12/15 as well as reviewed and approved daily ESI form submittals.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 11+00 to Sta. 10+20) to Access Manhole #3 (ESI demobilization point).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/13/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/13/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/13/15 |
| A5 – Subgrade Approval | Sheet 13 & ESI (8/13/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/13/15. |
| A7 – Panel Placement Log | Page 14 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/13/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/13/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 15-16 | Updated with vacuum box test conducted from 8/13/15 on Panels 67 through 71 |
| A10 – Repair Log | | N / A no repairs completed on 8/13/15 |
| A11 – Conformance COC | | N / A for 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/13/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/13/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 8/14/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 78/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0600 – 1430 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #21** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-71) installed on 8/13/15 (located at approximate Sta. 11+00) running approximately 80 ft. east to Sta. 10+20 (western slope of 2nd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 11+00 to Sta. 10+20. Refer to *Soil Subgrade Approval* forms from 8/14/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 11+00 to Sta. 10+20.
- Geocomposite clay liner (GCL), GVL and Cap placement began with ESI placing the GCL along the southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- In addition to the GCL (placed along the southern slope below the groundwater table), 16 oz. geotextile was placed along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 11+00 (east of P-71) moving east (for approximately 80 ft.) to Sta. 10+20. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/14/15 Photo Log* for supporting photographs.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #71 (located at approximate Sta. 11+00) on 8/13/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-72, P-73, P-74, and P-75) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/14), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 10+20, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (8/14/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. ESI conducted patch / repair work for the panels installed on 8/13/15 (Panels 66-71) and 8/14/15 (Panels 72-75). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 8/14/15 for results (extrusion testing identified as EXT. on form).
- A total of ten repairs (RP-253 through RP-262) were observed and fixed (according to the project specifications) from Panel #71 through Panel #75 (repair / detailing work conducted on panels installed on 8/13/15 & 8/14/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Upon completion of patch / repair activities, ESI began to pack and load equipment for their 2-week demob from the Site.
- A total of two destructive samples were collected (two fusion welds). Fusion weld destruct samples (DS-20, DS-21) were collected from Panel Seams 70/71 and 74/75, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 55-inch spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17, DS-18, DS-19, DS-20, and DS-21 (once received)

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, and 8/13/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South after 2-week demobilization is complete.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/13/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/14/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/13/15 |
| A5 – Subgrade Approval | Sheet 14 & ESI (8/14/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/14/15. |
| A7 – Panel Placement Log | Page 15 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/14/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 15-16 | Updated with vacuum box test conducted from 8/13/15 on Panels 67 through 71 |
| A10 – Repair Log | Page 13 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 8/14/15 |
| A11 – Conformance COC | | N / A for 8/14/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/14/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/14/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 31, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 2 |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/31/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, July 31, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Partially filled drums in the mechanics area on SA-6 South are not on spill pallets |
| 2 | IA2Q4A1AL8 | Drums and other containers in the mechanics area on SA-6 South are not properly labelled as to content. |
| 3 | IA2Q4A1AL8 | Remains of drainage pipe and other debris are present on the SA-6 South backfill area. |
| 4 | IA2Q4A1AL8 | Silt fence along the southern perimter of the Novartis stockpile area on SA-7 is not properly toed in. |
| 5 | IA2Q4A1AL8 | Sediment is present on the southern SA-7 paved access roadway by the Novartis stockpile area. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 07/31/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place all drums which are in use on or in secondary spill containment. | 8/3/15 RAD |
| 2 | Check labelling on all containers for Hazcom compliance and properly label or else remove any containers which are out of compliance. | 8/3/15 RAD |
| 3 | Place debris in rolloffs for disposal. | 8/4/15 RAD |
| 4 | Reinstall or replace silt fence as required. | 8/4/15 RAD |
| 5 | Clean up all sediment from the SA-7 access roadway | 8/5/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 08/06/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 7, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2,3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 4 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 5 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 7 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/07/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, August 07, 2015**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Discarded water bottles and other debris are present in the area of the SA-6 South cap installation. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing around the EZ to the south of the SA-6 North trash pit requires maintenance. |
| 3 | IA2Q4A1AL8 | Exclusion Zone surrounding the EA-8 excavation requires maintenance. |
| 4 | IA2Q4A1AL8 | The stockpile of relocated material in the SA-6 North Exclusion Zone requires erosion control measures. |
| 5 | IA2Q4A1AL8 | Debris is present on the ground in the EA-7/EA-8 excavation areas on SA-6 North. |
| 6 | IA2Q4A1AL8 | Silt fence along the SA-7 northern roadway requires maintenance. |
| 7 | IA2Q4A1AL8 | Debris is present on the eastern SA-7 roadway adjacent to Route 440. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 08/07/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and dispose of discarded water bottles in the SA-6 South cap area. Place garbage cans as needed for future use. | 8-11-15 RAD |
| 2 | Repair or maintain EZ fencing as required. Confirm that fencing across access points is closed at the end of every workday. | 8-11-15 RAD |
| 3 | Repair or maintain the EZ fencing as required | 8-11-15 RAD |
| 4 | Install silt control measures along the toe of the material stockpile. | 8-11-15 RAD |
| 5 | Pick up and dispose of debris. | 8-11-15 RAD |
| 6 | Repair or replace silt fence as required. | 8-11-15 RAD |
| 7 | Pick up and dispose of debris. | 8-11-15 RAD |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 08/13/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: August 14, 2015**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 1 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 6 |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 08/14/15

**SWPPP Observer:** _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, August 14, 2015

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Excluzion Zone fencing at the southeastern corner of the SA-6 South cap area is damaged |
| 2 | IA2Q4A1AL8 | Cover material is exposed on the eastern end of the SA-6 South cap area adjacent to the Hackensack River |
| 3 | IA2Q4A1AL8 | Exclusion Zone signage is not adequate on the EZ at the southeastern corner of SA-6 North. |
| 4 | IA2Q4A1AL8 | Filter fabric in the catch basins on SA-6 North by the trash pit has become blinded and requires maintenance. |
| 5 | IA2Q4A1AL8 | Sediment is present on the SA-7 access roadway. |
| 6 | IA2Q4A1AL8 | **REPEAT:** Debris is present on the eastern SA-7 roadway adjacent to Route 440 |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 08/14/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Maintain/repair the EZ fencing as required. | 8/19/15 RAD |
| 2 | Install plastic sheeting over the placed cover material. | |
| 3 | Install additional EZ signage on the EZ fenceline. | |
| 4 | Replace filter fabric in catch basins as required | |
| 5 | Clean the access roadway as required. Clean sediment from around the western cover material ramp. | |
| 6 | Pick up and dispose of debris. | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 08/20/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 21, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 4 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/21/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, August 21, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has accumulated on the north side of Kellogg Street to the west of the 60 Kellogg building and the filter fabric in the associated catch basins requires maintenance. |
| 2 | IA2Q4A1AL8 | Discarded filter fabric, old fence posts, and other debris are present on the SA-6 South backfill area adjacent to the western end of Kellogg Street. |
| 3 | IA2Q4A1AL8 | Silt fence is not properly toed in on the north side of the EA-4 excavation. |
| 4 | IA2Q4A1AL8 | Containment measures surrounding the Exclusion Zone at the southeastern corner of SA-6 North require upgrading. |
| 5 | IA2Q4A1AL8 | A catch basin on the north side of the trash pit on SA-6 North requires filter fabric replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 08/21/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove the accumulated sediment from the north side of Kellogg Street and change catch basin filter fabric as needed. | 8/27/15 RAD |
| 2 | Remove and properly dispose of all debris in this area. | |
| 3 | Toe in the silt fence. | |
| 4 | Install silt dams or other approved erosion control measures on the eastern side of the EZ between the excavated area and the sidewalk. | |
| 5 | Replace the filter fabric in the catch basin between the trash pit and the EA-4 excavation. | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 08/27/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 28, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 1 |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/28/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, August 28, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Oxygen tanks are not properly chained/stored in the mechanics area on SA-6 South |
| 2 | IA2Q4A1AL8 | Sediment is present on the road surface at the western end of Kellogg Street in the areas around the storm drain catch basins. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing is inadequate on the eastern side of the EA-5 excavation zone on SA-6 North |
| 4 | IA2Q4A1AL8 | A gap is present in the perimeter chain link fencing on SA-6 North, just to the east of the CWTP. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 08/28/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Chain or strap all compressed gas cylinders as required | 9/1/15 RAD |
| 2 | Shovel accumulated sediment from the road surface and dispose of properly. | 9/1/15 RAD |
| 3 | Install additional EZ fencing as required to close off the eastern side of EA-5 | 8/28/15 RAD |
| 4 | Repair the gap in the chain link fabric as required | 9/1/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 9/4/15

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (July 2015)

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

August 20, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the July 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 7 | 01 | 15 | 7 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,469 | 86,397 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.65 | 0.72 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.3 | <5.3 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1312 | 0.1312 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

## PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

8/18/2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 7 | 01 | 15 | 7 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,401,528 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 41,001,828 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 7/16/2015 | 8.3 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J Morris VP | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 8/18/2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | MONTH: July 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 7/1/2015 | Angel Trujillo | 38600300 | 38673403 | 73,103 | 0.073103 | 7.56 | 1.000 | | | | | | | | | 0.61 |
| 7/2/2015 | Angel Trujillo | 38673403 | 38752880 | 79,477 | 0.079477 | 7.59 | 1.000 | | | | | | | | | 0.66 |
| 7/3/2015 | Angel Trujillo | 38752880 | 38828208 | 75,328 | 0.075328 | 7.52 | 1.000 | | | | | | | | | 0.63 |
| 7/4/2015 | Angel Trujillo | 38828208 | 38907512 | 79,304 | 0.079304 | N/A | 1.000 | | | | | | | | | 0.66 |
| 7/5/2015 | Angel Trujillo | 38907512 | 38986815 | 79,303 | 0.079303 | 7.53 | 1.000 | | | | | | | | | 0.66 |
| 7/6/2015 | Angel Trujillo | 38986815 | 39056369 | 69,554 | 0.069554 | 7.55 | 1.000 | | | | | | | | | 0.58 |
| 7/7/2015 | Angel Trujillo | 39056369 | 39138805 | 82,436 | 0.082436 | 7.57 | 1.000 | | | | | | | | | 0.69 |
| 7/8/2015 | Angel Trujillo | 39138805 | 39218788 | 79,983 | 0.079983 | 6.70 | 1.000 | | | | | | | | | 0.67 |
| 7/9/2015 | Angel Trujillo | 39218788 | 39297122 | 78,334 | 0.078334 | 6.82 | 1.000 | | | | | | | | | 0.65 |
| 7/10/2015 | Angel Trujillo | 39297122 | 39371889 | 74,767 | 0.074767 | 6.83 | 1.000 | | | | | | | | | 0.62 |
| 7/11/2015 | Angel Trujillo | 39371889 | 39457013 | 85,124 | 0.085124 | 6.90 | 1.000 | | | | | | | | | 0.71 |
| 7/12/2015 | Angel Trujillo | 39457013 | 39530282 | 73,269 | 0.073269 | N/A | 1.000 | | | | | | | | | 0.61 |
| 7/13/2015 | Angel Trujillo | 39530282 | 39603551 | 73,269 | 0.073269 | 6.88 | 1.000 | | | | | | | | | 0.61 |
| 7/14/2015 | Angel Trujillo | 39603551 | 39683613 | 80,062 | 0.080062 | 6.88 | 1.000 | | | | | | | | | 0.67 |
| 7/15/2015 | Angel Trujillo | 39683613 | 39761777 | 78,164 | 0.078164 | 6.84 | 1.000 | | | | | | | | | 0.65 |
| 7/16/2015 | Angel Trujillo | 39761777 | 39839429 | 77,652 | 0.077652 | 6.86 | 1.000 | <5.3 | 8.3 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.65 |
| 7/17/2015 | Angel Trujillo | 39839429 | 39917383 | 77,954 | 0.077954 | 6.83 | 1.000 | | | | | | | | | 0.65 |
| 7/18/2015 | Angel Trujillo | 39917383 | 40000664 | 83,281 | 0.083281 | 6.82 | 1.000 | | | | | | | | | 0.69 |
| 7/19/2015 | Angel Trujillo | 40000664 | 40075996 | 75,332 | 0.075332 | N/A | 1.000 | | | | | | | | | 0.63 |
| 7/20/2015 | Angel Trujillo | 40075996 | 40151328 | 75,332 | 0.075332 | 6.81 | 1.000 | | | | | | | | | 0.63 |
| 7/21/2015 | Angel Trujillo | 40151328 | 40228223 | 76,895 | 0.076895 | 6.84 | 1.000 | | | | | | | | | 0.64 |
| 7/22/2015 | Angel Trujillo | 40228223 | 40305044 | 76,821 | 0.076821 | 6.90 | 1.000 | | | | | | | | | 0.64 |
| 7/23/2015 | Angel Trujillo | 40305044 | 40382213 | 77,169 | 0.077169 | 6.81 | 1.000 | | | | | | | | | 0.64 |
| 7/24/2015 | Angel Trujillo | 40382213 | 40459781 | 77,568 | 0.077568 | 6.82 | 1.000 | | | | | | | | | 0.65 |
| 7/25/2015 | Angel Trujillo | 40459781 | 40546178 | 86,397 | 0.086397 | 6.80 | 1.000 | | | | | | | | | 0.72 |
| 7/26/2015 | Angel Trujillo | 40546178 | 40619985 | 73,807 | 0.073807 | N/A | 1.000 | | | | | | | | | 0.62 |
| 7/27/2015 | Angel Trujillo | 40619985 | 40693793 | 73,808 | 0.0738 | 6.90 | 1.000 | | | | | | | | | 0.62 |
| 7/28/2015 | Angel Trujillo | 40693793 | 40771316 | 77,523 | 0.077523 | 6.89 | 1.000 | | | | | | | | | 0.65 |
| 7/29/2015 | Angel Trujillo | 40771316 | 40847941 | 76,625 | 0.076625 | 6.95 | 1.000 | | | | | | | | | 0.64 |
| 7/30/2015 | Angel Trujillo | 40847941 | 40924300 | 76,359 | 0.076359 | 6.90 | 1.000 | | | | | | | | | 0.64 |
| 7/31/2015 | Angel Trujillo | 40924300 | 41001828 | 77,528 | 0.077528 | 6.91 | 1.000 | | | | | | | | | 0.65 |
| TOTAL | | | | 2,401,528 | 2.401528 | | | <5.3 | 8.3 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 86,397 | | | | | | | | | | | High: | 0.72 |
| | | | Average: | 77,469 | | | | | | | | | | | Average: | 0.65 |

WW

E

TB99282

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42201.55960 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-071615 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program: 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | | | Site ID HudsonCo |
| Honeywell International<br>101 Columbia Road Morristown, NJ 07962 | Analysis Turnaround Time (TAT): Consultant: 3 CH2M | | | Lab Job # HWINJM32815 |
| Preliminary Data To | | | | Authorized User: Honeywell |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | Text & Excel File Drive / Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | Units | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | Preservative | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | | | |
| 1 | 087-WW | | | 087-WWE-071615-A | 7/16/2015 | 15:10 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | L25 |
| 2 | 087-WW | | | 087-WWE-071615-B | 7/16/2015 | 15:20 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | V6J1 |
| 3 | 087-WW | | | 087-WWI-071615 | 7/16/2015 | 15:30 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | A6 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | G43 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Relinquished by: pH = 6.86 s.u. @ 7.6° C | Company: AMEC Foster Wheeler | Received by: | Company: Accutest | Condition: 3.5 ED | Custody Seals Intact: |
| Frank Schroyer | Date/Time: 7/16/15 16:40 | | Date/Time: 7/16/15 16:40 | Cooler Temp. | |
| Relinquished by: | Company: Accutest | Received by: | Company: ALNJ | Condition: | Custody Seals Intact: |
| | Date/Time: 7/16/15 17:46 | | Date/Time: 7/16/15 1746 | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

INITIAL ASESSMENT 3B JK

LABEL VERIFICATION JK

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE JK

Accutest LabLink@866105 11:11 03-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-071615-A | | |
| **Lab Sample ID:** | JB99282-1 | **Date Sampled:** | 07/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1000 | 10 | ug/l | 1 | 07/17/15 | 07/20/15 | AP | EPA 200.7 [1] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 07/17/15 | 07/20/15 | AP | EPA 200.7 [1] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 07/17/15 | 07/20/15 | AP | EPA 200.7 [1] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 07/20/15 | 07/20/15 | MA | EPA 245.1 [2] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 07/17/15 | 07/20/15 | AP | EPA 200.7 [1] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 07/17/15 | 07/20/15 | AP | EPA 200.7 [1] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA37126
(2) Instrument QC Batch: MA37129
(3) Prep QC Batch: MP87721
(4) Prep QC Batch: MP87797

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@866105 11:11 03-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-071615-A | | |
| **Lab Sample ID:** | JB99282-1 | **Date Sampled:** | 07/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 07/19/15 | SP | SM2540 D-11 |
| pH [a] | 6.89 | | su | 1 | 07/16/15 17:59 | AL | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@866105 11:11 03-Aug-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-071615-A | | |
| **Lab Sample ID:** | JB99282-1A | **Date Sampled:** | 07/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 8.3 | 3.4 | mg/l | 1 | 07/16/15 20:37 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@866105 11:11 03-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-071615-B | | |
| **Lab Sample ID:** | JB99282-2 | **Date Sampled:** | 07/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/16/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | T209724.D | 1 | 07/21/15 | DC | n/a | n/a | VT8607 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.2 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.5 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.27 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 17.7 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.41 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.32 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 59.8 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.3 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.47 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@866105 11:11 03-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-071615-B | | |
| **Lab Sample ID:** | JB99282-2 | **Date Sampled:** | 07/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/16/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 42.5 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | 0.70 | 1.0 | 0.13 | ug/l | J |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 106% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 101% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 101% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 99% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@866105 11:11 03-Aug-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-071615-B | | |
| **Lab Sample ID:** | JB99282-2 | **Date Sampled:** | 07/16/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/16/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.3 | 5.3 | mg/l | 1 | 07/18/15 12:00 | CB | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending August 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending August 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending August 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-22** | Detail BN has been modified to extend the lIDPE up and over the SCB Wall. The prior detail showed both the GDI and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**10/15/2015**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

October 15, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-09**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from August 1 – August 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: September 2015 SA-6/7 Combined Monthly Progress Report No. 2015-09

cc: Joe Clifford - Amec Foster Wheeler (electronic copy)
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-09

**Project SA-6 & 7 Remediation**

## September 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 09/02/15 | Revised Combined Chromium Remediation Schedule<br>Study Area 6 North and South<br>Jersey City, Hudson County, NJ | Thomas Cozzi, Assistant Director<br>New Jersey Department of Environmental Protection |
| 09/10/15 | Pump Well PW-3<br>Study Area 7 Groundwater<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/11/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights<br>Report No. 2015-07 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/11/15 | Responses to Verbal Questions Posed by Dr. Rogers on August 18, 2015 Regarding SA-6 South Geomembrane Boot Installations<br>Study Area 6 North and South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/15/15 | Special Master Conference Meeting | N/A |
| 09/16/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2, Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 09/18/15 | Interface Friction Evaluation Geomembrane versus Gas Vent Layer<br>Study Area 6<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/23/15 | Design Change Bulletin: Planting Soil Specifications<br>Study Area 6 North and South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/29/15 | NJDEP Corr re SA-6NS Revised Combined Master Schedule<br>Study Area 6 North and South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/29/15 | Boot Installation for Geomembrane Penetrations<br>Study Area 6 South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 9/6/2015 | 9/13/2015 | 9/20/2015 | 9/27/2015 |
| Construction Management (AMEC) | 8 | 8 | 9 | 10 |
| Engineering (AMEC) | 1 | 1 | 1 | 1 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 35 | 40 | 42 | 43 |
| Arecon/US Ecology Subcontractors | 0 | 3 | 3 | 0 |
| Langan | 0 | 0 | 1 | 1 |
| Evoqua | 1 | 1 | 1 | 1 |
| B&B Drilling | 2 | 0 | 0 | 2 |
| **TOTAL STAFF** | **51** | **57** | **61** | **62** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected September PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- On September 27 through 29, Cornerstone personnel completed S-3 Mass Removal Injection Event No. 24 in Injection Well 088-IW-02.
- On September 17 and 18, Cornerstone conducted a round of regional quarterly groundwater level measurements.
- ERFS/Summit re-mobilized to SA-6 North, Treatment Area 10-1 on September 9 and 10 and completed the proposed injection program in accordance with the Updated Work Plan submitted to all Parties on August 21, 2015.
- Continued screening of Celgene material for use as protective cover soils above geosynthetics.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on September 10, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 9/6/2015 | 9/13/2015 | 9/20/2015 | 9/27/2015 |
| Avg. Gallons Treated & Discharged (per day) | 78,081 | 78,108 | 77,991 | 76,827 |
| Average Flow (gpm) for Operating Period | 55 | 54 | 56 | 56 |
| Avg. Hours of Plant Operation | 24 | 24 | 24 | 23 |
| GWTP Influent Tanks (gal.) | 8,208 | 4,566 | 5,253 | 4,358 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completion of the Excavation Area EA-8 excavation is pending post excavation sampling results.
- Completed installation of dewatering well points and two deep dewatering wells associated with EA-2 and EA-3.
- Completed excavation of Excavation Area EA-5. An unknown UST was encountered during excavation activities. The UST was removed from the excavation on October 1, 2015 due to slope stability concerns. The UST was staged on site for future disposal and closure reporting under the non-chromium project and LSRP.
- Continued relocating soils from Area 3S to the SA-6 North Cap Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Canada | Stablex | WWTP Filter Cake | 1 | 16.5 | 16.5 |
| **Entact/Horwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non-haz Cr | 44 | 26 | 1,153.71 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Excavation Area EA-5<br>Volume Excavated - Total for Reporting Period: 2,690.CY / Total to Date: 6,432. CY |
| **Backfill in Progress** | Celgene Screened fraction above 3/8 inch – EA-5 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 9/6/2015 | 9/13/2015 | 9/20/2015 | 9/27/2015 |
| Mt. Hope 3/8" Stone | 100.23 | 0 | 0 | 50.89 |
| Mt. Hope DGA | 0 | 0 | 397.21 | 0 |

- Screened Celgene materials greater than 3/8 inch were transferred and placed as backfill in EA-5. A total of 36 loads, totaling approximately 810 cubic yards was placed as backfill in EA-5.
- Screened Celgene material was placed as protective cover soil in the SA-6 South cap area. A total approximately 4,973 cubic yards was placed as protective cover soil during the reporting period.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Completed installation of surcharge monitoring instrumentation.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- No activity to report.

## G. CAPPING OPERATIONS

- A total of 117,022 sq. ft. of liner totaling 32% of the total cap area was deployed during the reporting period. The total liner area deployed through September 27, 2015 is 96% for the cap system at SA-6 South.

- Continued installation of geosynthetic cap components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- Continued general liner subgrade preparation in Area 3S.
- Continued cutting hydraulic barrier sheets and the SCB wall to final elevation in SA-6 South Open Space Area.
- Continued removing asphalt on top of the SCB wall and smooth coating as necessary for geosynthetics installation detail.
- Continued installation of gas vent pipe.
- Modified destructive seam testing interval from 1 test per 500 feet of seam to 1 test per 1,500 feet of seam length according to Specification 02372-3.07.A. (Samples DS-1 to DS-26 had been collected with 0 failures).
- Continued placement of protective cover soils and demarcation tape over the geocomposite drainage layer.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 | Renewal Not Needed | 6/23/2014 | 11/20/2013 |
| PVSC SUP No. 31630016 | New GWTP | Obtained 10/1/2013 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| PVSC SUP No. 31630005 | Existing GWTP/SA-7 | Obtained 1/1/2014 | Renewal Not Needed | 12/31/2018 | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15 | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete excavation of Area EA-8.
- Complete backfilling of excavation areas EA-4 and EA-5.
- Begin Trash Pit area Meadow Mat Repair.
- Complete liner subgrade and utility corridor preparation activities on SA-6 South.
- Complete installation of geosynthetic cap components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- Continue screening Celgene material for use as protective cover soils above geosyntethics.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Continue to coordinate the planned PW-3 extraction well/trench installation.
- Initiate import and placement of Horizon B/C Soils.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Repair Log
11. Capping Update
    - SA-6 South Cap Subgrade Progress Map
    - Repair Log
    - Non-conformance Log

- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports (Langan)


12. Weekly SWPPP Reports
13. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted September2015)
14. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 9/30/15

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Cleaning Barrier Wall prior to backfill former JC Properties.




**Site Photograph 2:** Completed Concrete Surface on SCB Wall.





**Site Photograph 3:** EA-4 Excavation on former JC Properties.




**Site Photograph 4:** EA-5 Backfilling on former JC Properties.




**Site Photograph 5:** Placing Orange Geotextile in Open Space.




**Site Photograph 6:** Screening Imported Soils.





**Site Photograph 7:** Unloading Clean Cover Soils.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of October 1, 2015

September 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 08/03/15 | 9:00 | 13:30 | 4:30 | 34,908.04 | 34,940.20 | 32,160 | 34,796,350 | |
| 08/04/15 | 10:30 | 21:30 | 11:00 | 34,940.20 | 35,081.91 | 141,710 | 34,938,060 | |
| 08/07/15 | 6:30 | 12:30 | 6:00 | 35,081.91 | 35,221.03 | 139,120 | 35,077,180 | PVSC Compliance Sample Collected |
| 08/10/15 | 6:15 | 12:00 | 5:45 | 35,221.03 | 35,298.93 | 77,900 | 35,155,080 | |
| 08/11/15 | 6:35 | 14:30 | 7:55 | 35,298.93 | 35,398.03 | 99,100 | 35,254,180 | |
| 08/12/15 | 6:30 | 13:30 | 7:00 | 35,398.03 | 35,457.13 | 59,100 | 35,313,280 | |
| 08/13/15 | 7:00 | 13:30 | 6:30 | 35,457.13 | 35,497.93 | 40,800 | 35,354,080 | |
| 08/14/15 | 7:00 | 13:00 | 6:00 | 34,497.93 | 35,552.43 | 54,500 | 35,408,580 | |
| 08/17/15 | 6:30 | 12:30 | 6:00 | 35,552.43 | 35,618.63 | 66,200 | 35,474,780 | |
| 08/19/15 | 8:00 | 15:00 | 7:00 | 35,618.63 | 35,662.04 | 43,410 | 35,518,190 | |
| 08/20/15 | 7:00 | 14:00 | 7:00 | 35,662.04 | 35,706.84 | 44,800 | 35,562,990 | |
| 08/21/15 | 7:00 | 13:30 | 6:30 | 35,706.84 | 35,724.91 | 18,070 | 35,581,060 | |
| 08/25/15 | 8:00 | 14:00 | 6:00 | 35,724.91 | 35,790.40 | 65,490 | 35,646,550 | |
| 08/28/15 | 7:00 | 13:00 | 6:00 | 35,790.40 | 35,841.14 | 50,740 | 35,697,290 | |
| 09/01/15 | 7:00 | 13:00 | 6:00 | 35,841.14 | 35,929.31 | 88,170 | 35,785,460 | PVSC Compliance Sample Collected |
| 09/04/15 | 7:00 | 13:00 | 6:00 | 35,929.31 | 35,970.92 | 41,610 | 35,827,070 | |
| 09/09/15 | 7:00 | 15:00 | 8:00 | 35,970.92 | 36,046.73 | 75,810 | 35,902,880 | |
| 09/11/15 | 7:00 | 14:00 | 7:00 | 36,046.73 | 36,113.32 | 66,590 | 35,969,470 | |
| 09/18/15 | 7:00 | 15:00 | 8:00 | 36,113.32 | 36,198.63 | 85,310 | 36,054,780 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

**Material Tracking and Sampling Log**
**SA-6 North and South**


| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA-8 | <20 | 087-EA8-20-a,b | 1500 | 087-EA8-20-a1 | 6/24/2015 | 7:35 | <2.3 | Yes | | |
| | | | | 087-EA8-20-a2 | 6/24/2015 | 7:40 | <2.3 | Yes | | |
| | | | | 087-EA8-20-a3 | 6/24/2015 | 7:45 | <1.9 | Yes | | |
| | | | | 087-EA8-20-a4 | 6/24/2015 | 7:50 | <1.9 | Yes | | |
| | | | | 087-EA8-20-b1 | 6/24/2015 | 7:55 | <2.1 | Yes | | |
| | | | | 087-EA8-20-b2 | 6/24/2015 | 8:00 | 0.78 | Yes | | |
| | | | | 087-EA8-20-b3 | 6/24/2015 | 8:05 | 2.10 | Yes | | |
| | | | | 087-EA8-20-b4 | 6/24/2015 | 8:10 | <2.0 | Yes | | |
| EA-8 | <20 | 087-EA8-20-c (bermed / trench material) | 250 | 087-EA8-20-c1 | 6/24/2015 | 11:40 | <1.9 | * | | |
| | | | | 087-EA8-20-c2 | 6/24/2015 | 11:45 | <2.1 | * | | |
| | | | | 087-EA8-20-c3 | 6/24/2015 | 11:50 | <2.1 | * | | |
| | | | | 087-EA8-20-c4 | 6/24/2015 | 11:55 | <1.9 | * | | |
| EA-7 | <20 | 087-EA7-20-a (bermed/trench material) | 900 | 087-EA7-20-a1 | 6/26/2015 | 13:15 | <1.8 | Yes | | |
| | | | | 087-EA7-20-a2 | 6/26/2015 | 13:20 | <1.4 | Yes | | |
| | | | | 087-EA7-20-a3 | 6/26/2015 | 13:25 | <1.4 | Yes | | |
| | | | | 087-EA7-20-a4 | 6/26/2015 | 13:30 | 5.5 | Yes | | |
| EA-7 | <20 | 087-EA7-20-b West Pile | 600 | 087-EA7-20-b1 | 7/14/2015 | 8:52 | 5.2 | Yes | | |
| | | | | 087-EA7-20-b2 | 7/14/2015 | 8:56 | 2.6 | Yes | | |
| | | | | 087-EA7-20-b3 | 7/14/2015 | 9:00 | 4.3 | Yes | | |
| | | | | 087-EA7-20-b4 | 7/14/2015 | 9:03 | 2.8 | Yes | | |
| EA-7 | <20 | 087-EA7-20-c East Pile | 200 | 087-EA7-20-c1 | 7/14/2015 | 9:06 | <.47 | Yes | | |
| | | | | 087-EA7-20-c2 | 7/14/2015 | 9:11 | <1.6 | Yes | | |
| 3S cap material | <240 | 124-3S-EX-a,b,c,d (Excess 3S material) | 3500 | 124-3S-EX-a1 | 8/10/2015 | 12:10 | 51.6 | | Yes | |
| | | | | 124-3S-EX-a2 | 8/10/2015 | 12:15 | 18.6 | * | | |
| | | | | 124-3S-EX-a3 | 8/10/2015 | 12:18 | 37.1 | | Yes | |
| | | | | 124-3S-EX-a4 | 8/10/2015 | 12:20 | 18.9 | * | | |
| | | | | 124-3S-EX-b1 | 8/10/2015 | 12:21 | 24.8 | | Yes | |
| | | | | 124-3S-EX-b2 | 8/10/2015 | 12:22 | 49.3 | | Yes | |
| | | | | 124-3S-EX-b3 | 8/10/2015 | 12:23 | 37.9 | | Yes | |
| | | | | 124-3S-EX-b4 | 8/10/2015 | 12:24 | 40.4 | | Yes | |
| | | | | 124-3S-EX-c1 | 8/10/2015 | 12:25 | 24.7 | | Yes | |
| | | | | 124-3S-EX-c2 | 8/10/2015 | 12:26 | 36.3 | | Yes | |
| | | | | 124-3S-EX-c3 | 8/10/2015 | 12:27 | 46.7 | | Yes | |
| | | | | 124-3S-EX-c4 | 8/10/2015 | 12:28 | 8.1 | * | | |
| | | | | 124-3S-EX-d1 | 8/10/2015 | 12:29 | 25.6 | | Yes | |
| | | | | 124-3S-EX-d2 | 8/10/2015 | 12:30 | 32.1 | | Yes | |
| | | | | 124-3S-EX-d3 | 8/10/2015 | 12:31 | 74.6 | | Yes | |
| | | | | 124-3S-EX-d4 | 8/10/2015 | 12:32 | 34.7 | | Yes | |
| EA-4 | <20 | 087-EA4-20-a (bermed/trench material) | 225 | 087-EA4-20-a1 | 9/11/2015 | 10:35 | 2 | Yes | | |
| | | | | 087-EA4-20-a2 | 9/11/2015 | 10:40 | <1.4 | Yes | | |
| | | | | 087-EA4-20-a3 | 9/11/2015 | 10:45 | <1.8 | Yes | | |
| | | | | 087-EA4-20-a4 | 9/11/2015 | 10:50 | 5.0 | Yes | | |
| EA-5 | <20 | 087-EA5-20-a1:b4 (stockpile of A material) | 1300 | 087-EA5-20-a1 | 9/11/2015 | 11:05 | 0.7 | * | | |
| | | | | 087-EA5-20-a2 | 9/11/2015 | 11:10 | <1.7 | * | | |
| | | | | 087-EA5-20-a3 | 9/11/2015 | 11:15 | <0.46 | * | | |
| | | | | 087-EA5-20-a4 | 9/11/2015 | 11:20 | <1.1 | * | | |
| | | | | 087-EA5-20-b1 | 9/11/2015 | 11:25 | <2.0 | * | | |
| | | | | 087-EA5-20-b2 | 9/11/2015 | 11:30 | 6.8 | * | | |
| | | | | 087-EA5-20-b3 | 9/11/2015 | 11:35 | 8.3 | * | | |
| | | | | 087-EA5-20-b4 | 9/11/2015 | 11:40 | <0.55 | * | | |

**Material Tracking and Sampling Log**
**SA-6 North and South**

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA-5 | <20 | 087-EA5-20-c1:d4 (stockpile of A material) | 2000 | 087-EA5-20-c1 | 9/11/2015 | 12:10 | <1.8 | * | | |
| | | | | 087-EA5-20-c2 | 9/11/2015 | 12:15 | <1.9 | * | | |
| | | | | 087-EA5-20-c3 | 9/11/2015 | 12:20 | <0.56 | * | | |
| | | | | 087-EA5-20-c4 | 9/11/2015 | 12:25 | <0.60 | * | | |
| | | | | 087-EA5-20-d1 | 9/11/2015 | 12:30 | <0.56 | * | | |
| | | | | 087-EA5-20-d2 | 9/11/2015 | 12:35 | <0.44 | * | | |
| | | | | 087-EA5-20-d3 | 9/11/2015 | 12:40 | <0.5 | * | | |
| | | | | 087-EA5-20-d4 | 9/11/2015 | 12:45 | 9.6 | * | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP–1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | |
| 10/14/2014 | | 4.9 | 5.5 | 5.8 | 5.8 | 2.3 | 3.0 | 5.0 | 4.6 | 6.4 | 5.9 | 5.7 | 5.2 | 5.6 | | 3.1 | 2.8 | 3.5 | 4.1 | 5.9 | 8.3 |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | 2.8 | 3.1 | 5.1 | 4.7 | 6.7 | 6.2 | 5.6 | 5.3 | 5.7 | | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | 3.8 | 5.1 | 5.0 | 4.6 | 6.5 | 6.4 | 5.6 | 5.3 | 5.7 | | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | 5.3 | 6.6 | 5.2 | 4.9 | 6.9 | 6.9 | 6.0 | 5.9 | 6.2 | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | 6.8 | 6.7 | 5.5 | 5.2 | 7.3 | 6.9 | 6.4 | 6.2 | 6.7 | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | 8.6 | 7.3 | 5.4 | 5.0 | 7.2 | 6.7 | 6.0 | 5.8 | 6.3 | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | 3.5 | 3.1 | | 5.6 | 6.6 | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, W1-SO,

# Attachment 8: Groundwater Quality Data

Honeywell

**Table 1**
Summary of Groundwater Quality Data from GWET Wells

| Parameter | 18-Dec-14 | | | 17-Mar-15 | | | 28-May-15 | | | 23-Sep-15 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 3.2 | 4.0 | ND | 3.1 | 3.9 | ND | 3.1 | 3.8 | ND | 3.8 | 3.6 | ND |
| Carbon Tetrachloride | 5.2 | 4.2 | 2.9 | 5.8 | 4.6 | 2.1 | 5.7 | 4.5 | 3.0 | 6.7 | 4.3 | 2.9 |
| Chloroform | 25.8 | 9.4 | ND | 23.1 | 7.8 | 0.21 | 23.5 | 7.8 | 0.24J | 27.4 | 6.8 | 0.27 |
| 1,1-Dichloroethene | 0.57 | ND | ND | 0.63 | ND | ND | 0.61J | ND | ND | 0.63 | ND | ND |
| cis-1,2-Dichloroethene | 112 | 8.6 | ND | 111 | 8.1 | ND | 131 | 9.6 | ND | 129 | 8.7 | 0.24 |
| trans-1,2-Dichloroethene | 3.5 | ND | ND | 3.8 | ND | ND | 3.9 | ND | ND | 3.9 | ND | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 97 | 44.4 | ND | 101 | 45.0 | ND | 94.9 | 40.7 | ND | 105.0 | 37.3 | ND |
| 1,1-Dichloroethane | 0.46 | ND | ND | 0.51 | ND | ND | 0.56J | ND | ND | 0.64 | ND | ND |
| Methylene chloride | 0.77 | 0.20 | ND | 0.71 | ND | ND | 0.73J | ND | ND | 0.71 | ND | ND |
| Vinyl chloride | 15.4 | 2.5 | ND | 16.9 | 2.5 | ND | 18.1 | 3.0 | ND | 17.4 | 2.0 | ND |
| 1,2-Dichlorobenzene | 0.66 | ND | ND | 0.70 | ND | ND | 0.67J | ND | ND | 0.61 | ND | ND |
| Chlorobenzene | 0.37 | ND | ND | 0.41 | ND | ND | 0.38J | ND | ND | 0.35 | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 35,900 | 12,200 | 15,900 | 34,700 | 13,500 | 15,100 | 36,100 | 13,500 | 16,800 | 33,900 | 7,300 | 14,700 |
| Total Chromium | 34,100 | 12,700 | 15,900 | 34,700 | 15,100 | 14,800 | 32,600 | 15,600 | 16,700 | 33,800 | 8,480 | 14,000 |


NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.


**TABLE 2**
**Quarterly Water Levels**
**September 2015**

Honeywell


| Wells<br>Date: September 18, 2015 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments<br>*GW Elevations are not corrected for tidal influence* |
|---|---|---|---|---|
| 087-MW-25D | 18.17 | NA | NA | no access |
| 087-MW-25T | 18.19 | NA | NA | no access |
| 087-MW-35 | 18.29 | NA | NA | Well abandoned |
| 087-OBS-1D | 15.13 | 13.39 | 1.74 | |
| 087-OBS-1L | 15.27 | 13.90 | 1.37 | |
| 087-OBS-1T | 15.23 | 13.62 | 1.61 | |
| 087-PW-2 | 13.02 | 28.35 | -15.33 | |
| 087-MW-08 | 12.98 | 12.16 | 0.82 | |
| 087-OBS-3L | 12.88 | 12.81 | 0.07 | |
| 087-MW-13 | 12.93 | 12.91 | 0.02 | |
| 087-OBS-5D | 12.72 | 12.04 | 0.68 | |
| 087-OBS-5T | 12.62 | 13.25 | -0.63 | |
| 087-PW-1 | 12.66 | 39.55 | -26.89 | |
| 087-MW-34 | 12.73 | 13.94 | -1.21 | |
| 087-OBS-2D | 12.68 | 15.20 | -2.52 | |
| SA6-MW-AA1D | 19.36 | 18.56 | 0.80 | |
| SA6-MW-AA1T | 15.31 | 14.42 | 0.89 | |
| SA6-MW-5BR-1 | 17.06 | 15.07 | 1.99 | |
| 087-OBS-4T | 11.60 | 11.48 | 0.12 | |
| 087-MW-O29D | 10.32 | 9.34 | 0.98 | |
| 087-MW-O29T | 9.98 | 8.58 | 1.40 | |
| 087-MW-03 | 13.77 | NA | N/A | Well not accessible |
| 087-MW-02 | 12.57 | NA | N/A | Well abandoned |
| 115-MW-203BR* | 8.70 | 7.43 | 1.27 | |
| 073-MW-1BR-1 | 7.58 | 26.28 | -18.70 | |
| 073-MW-10BR-1 | 6.67 | 7.58 | -0.91 | |
| 115-MW-215BR* | 8.82 | 12.02 | -3.20 | |

* Reference point elevation to be confirmed.




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR

# Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-43
Date Exposed: 8/26/15
Describe Damage: Epoxy removed on the edges and face of the sheet while excavator trying to remove soil from belly of the sheets.

Equipment 349E Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet

Date Repaired: 9/2/15 Partial 9/4/15 remaining
Inspected by: Ari Eslaminejad
Describe Repair: Clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: [signature]
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-42
Date Exposed: 8/26/15
Describe Damage: Epoxy removed on the edges and face of the sheet while excavator trying to remove soil from belly of the sheets

Equipment 349E Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet pile

Date Repaired: 9/2/15 Partial 9/4/15 remaining
Inspected by: Ari Eslaminejad
Describe Repair: clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: [signature]
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-41
Date Exposed: 8/26/15
Describe Damage: _____

Multiple Scrapes of epoxy coating along the length of the sheets on the edges and face.

.. Equipment 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet

Date Repaired: 9/2/15 Partial 9/4/15 remaining
Inspected by: A. Eslaminejad
Describe Repair: Clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: [signature]
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-40
Date Exposed: 8/27/15
Describe Damage: _____

Multiple Scrapes of epoxy coating along the length of the sheets on the edge and face.

Equipment 349E


Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet

Date Repaired: 9/2/15 Partial 9/4/15 Remaining
Inspected by: A. Eslaminejad
Describe Repair: clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: [signature]
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

# Attachment 11: Capping Update

- SA-6 South Cap Subgrade Progress Map
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports




LEGEND

- SUBGRADE GRADING UNDERWAY
- SUBGRADE COMPLETE AND SURVEYED
- APPROVED FOR GEOSYNTHETIC DEPLOYMENT
- LINER DEPLOYED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP SUBGRADE PROGRESS MAP
09/25/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4163 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 5989.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-274 | CF | | 73 | 23'N OF 72/73 & 15'E | P | 2 | x | 6 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-275 | CF | | 73 | FROM RP-274 TO 5'N | B | | x | | 60 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-276 | CF | | 73 | FROM RP-277 TO 12'E | B | | x | | 144 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-277 | CF | | 73 | 50'N OF 72/73 & 5'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-278 | CF | | 73 | 46'N OF 73/74 & 5'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-279 | CF | | 73 | BETWEEN RP-278 & RP-280 | B | | x | | 156 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-280 | CF | | 73 | 59'N OF 73/74 & 16'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-281 | CF | | 71 | 137'N OF 71/72 & 2'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-282 | CF | | 71 | BETWEEN RP-281 & RP-283 | B | | x | | 120 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-283 | CF | | 71 | 125'N OF 71/72 & 8'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-284 | CF | | 71 | 164'N OF 71/72 & 8'W | P | 2 | x | 4 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-285 | CF | | 71 | BETWEEN RP-284 & RP-286 | B | | x | | 132 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-286 | CF | | 71 | 142'N OF 71/72 & 3'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-287 | CF | | 71 | FROM RP-288 TO 8'N | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-288 | CF | | 71 | 137'N OF 71/72 & 9.5' W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-289 | DSX-8 | RP-284/71 | | ON RP-284/71 | P | 2 | x | 5 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-290 | WR | 68/69 | | 132'N OF SEOS | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-291 | WR | | 68 | BETWEEN RP-290 & RP-292 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-292 | WR | | 68 | 126'N OF 68/69 & 10'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-293 | SI | | 57 | 136'N OF 56/57 & 7'E | P | 2 | x | 2 | | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-294 | SJ | | | SJ 75/80/81 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4163 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 5989.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-316 | DS-23 | 88/89 | | 116'N OF SEOS | p | 2 | x | 4.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-317 | WR | | 79 | BETWEEN RP-298 & RP-318 | B | | x | | 66 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-318 | WR | | 79 | 78'E OF 79/80 & 7'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-319 | BO | 81/87 | | 8'N OF SEOS | P | 2 | x | 5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-320 | SJ | | | SJ 80/81/87 | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-321 | SJ | | | SJ 79/80/87 | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-322 | WR | 79/87 | | 6'N OF SEOS | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-323 | SJ | | | SJ 78/79/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-324 | SJ | | | SJ 77/78/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-325 | SJ | | | SJ 76/77/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-326 | CF | 89/90 | | 145'N OF SEOS | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-327 | CF | | 89 | 145'N OF 89/90 & 6'W | B | | x | | 72 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-328 | CF | 89/90 | | 81'N OF NEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-329 | CF | | 89 | 81'N OF 89/90 & 5'W | B | | x | | 60 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-330 | DSX-9 | RP-316/88 | | RP-316/88 | P | 2 | x | 4.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-331 | SI | | 83 | 9'S OF 83/84 & 8'W (END OF PANEL) | P | 2 | x | 18 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-332 | SJ | | | SJ 84/86/87 | P | 3 | x | 12 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-333 | CR | | 84/86 | EEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-334 | WR | | 84 | BETWEEN RP-315 & RP-335 | B | | x | | 12 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-335 | WR | | 84 | 7'W OF 81/84 & 3.5'S | P | 3 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-336 | SJ | | | SJ 81/84/87 | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4163 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 5989.00 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-379 | CF | | 96 | 101'S OF 96/97 & 17'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-380 | CF | | 96 | 93'S OF 96/97 & 8'W | P | 2.5 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-381 | CF | | 96 | BETWEEN RP-380 & RP-382 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-382 | CF | | 96 | 86.5'S OF 96/97 & 4'W | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-383 | BO | 103/104 | | 16'W OF EEOS | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-384 | BO | 97/103 | | 12'S OF NEOS | | | x | | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-385 | SI | | 94 | 126'N OF 94/95 & 8'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-386 | DSX-10 | RP-376/96 | | RP-376/96 (DSX-10 ) | P | 2 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-387 | SJ | | | SJ 97/103/104 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-388 | CF | | 97 | BETWEEN RP-384 & RP-389 | B | | x | | 24 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-389 | CF | | 97 | 12'S OF 97/103 & 3.5'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-390 | SJ | | | SJ 97/102/103 | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-391 | SJ | | | SJ 97/101/102 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-392 | SJ | | | SJ 97/100/101 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-393 | SJ | | | SJ 97/99/100 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-394 | SJ | | | SJ 97/98/99 | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-395 | CF | | 103 | FROM RP-383 TO 5'N | B | | x | | 60 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-396 | CF | | 103 | 4'N FROM RP-397 & 14'NW | B | | x | | 168 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-397 | SJ | | | SJ 103/104/105 | P | 2 | x | 3.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-398 | SJ | | | SJ 103/105/106 | P | 3 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-399 | CF | | 107 | 122'S OF 107/108 & 4'W | B | | x | | 192 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

## Summary of Non-Compliance & Corrective Action Forms

**SA-6 South Cap Installation**

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 1 | 7/21/2015 | Subgrade Irregularity | RP-3 | Panel #2 (P-2) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2.5 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 2 | 7/21/2015 | Subgrade Irregularity | RP-8 | Panel #2 (P-2) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2.5 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 3 | 7/22/2015 | Failed Non-Destruct Test | RP-13 | Panel #7 (P-7) & Panel #8 (P-8) seam | Based on length of failed seam (approximately 6 ft.) the entire seam was patched and repaired (approximate 2 ft. by 6 ft. patch). The patch was overlapped a minimum of 4-inches, with rounded edges, and sealed with an extrusion weld. Vacuum box testing was then conducted in accordance with Section 02372-8 to confirm the weld. |
| 4 | 7/24/2015 | Subgrade Irregularity | RP-30 | Panel #17 (P-17) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 5 | 8/7/2015 | Failed Vacuum Box Test | RP-215 | Panel #50 (P-50) | Failed extrusion weld (identified during vacuum box testing) was patched with an approximate 2 ft. by 2 ft. geomembrane patch over the extrusion weld (noted as RP-222 on Repair Log). The patch was overlapped a minimum of 4-inches beyond the edges of the failed weld, conformed so that the edges were rounded, and sealed with an extrusion weld. Vacuum box testing was conducted along the seams to confirm the seams were properly patched and repaired. |
| 6 | 9/11/2015 | Subgrade Irregularity | RP-293 | Panel #57 (P-57) | Rock was removed from underneath geomembrane and hole was then patched with approximate 1.5 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 7 | 9/16/2015 | Subgrade Irregularity - Hydrated GCL | RP-331 | Panel #83 (P-83) | Geomembrane cap was cut and GCL was exposed. Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. The cut in the geomembrane was then repaired with approximate 2 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). |
| 8 | 9/24/2015 | Subgrade Irregularity | RP-423 | Panel #111 (P-111) | Rock was removed from underneath geomembrane and hole was then patched with approximate 1.5 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |

LANGAN

# Certificate of Soil Surface

Sheet # 15

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 10+20 TO ~STA. 9+50 | | |
| QA Monitor | LANGAN | Date | 9/9/15 | | |

Description of Soil Surface to be lined: ~770 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/14/15 (P.175). SUBGRADE APPROVED THROUGH 2ND UTILITY CORRIDOR FROM APPROX. STA. 10+20 TO STA. 9+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/9/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/9/15 |
| Title | QC Manager |
| Representing: | ENTACT |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 023172-S

- SOIL APPROVED FOR GCL PLACEMENT ALONG EASTERN + WESTERN SLOPES OF UTILITY CORRIDOR + SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN END OF SA-6 AREA BELOW (TO 1FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | ~STA 10+00 | LOOKING SW | REFER TO 9/9/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | ~STA. 10+00 | LOOKING NE | REFER TO 9/9/15 PHOTO LOG (PHOTO #3) |

1. REFER TO PHOTO LOG (9/9/15) PHOTOS 2,3 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 16

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) Operations LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 9+50 TO ~STA. 8+50 |
| QA Monitor | LANGAN | Date | 9/15/15 |

Description of Soil Surface to be lined: ~100 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/9/15 (P-86). SUBGRADE APPROVED EAST OF 2ND UTILITY CORRIDOR FROM APPROX. STA. 9+50 TO ~STA. 8+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/15/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9-15-15 |
| Title | Entact QC Manager |
| Representing: | ENTACT |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8

~~THE~~ GCL PLACED ALONG SOUTHERN SLOPE OF SA-6 SOUTH (LOWER BENCH) AT AREA BELOW (TO 1FT. ABOVE) GROUNDWATER TABLE

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 9+50 | LOOKING S | REFER TO 9/15/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 9+50 | LOOKING E | REFER TO 9/15/15 PHOTO LOG |

1. REFER TO PHOTO LOG (9/15/15) PHOTOS 1,2 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 17

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 8+50 TO ~STA. 7+70 | | |
| QA Monitor | LANGAN | Date | 9/16/15 | | |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/15/15 (P-90). SUBGRADE APPROVED FROM APPROXIMATE STA. 8+50 (P-90) TO APPROX STA. 7+70. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOUCHER |
| Date: | 9/16/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/16/15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02372-8

NO GCL PLACED ALONG SA-6 AS AREAS OUTSIDE OF GROUNDWATER ZONE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #17 | ~STA 8+50 | LOOKING N/NE | REFER TO 9/16/15 PHOTO LOG (PHOTO #17) |
| | 2 | | | |

1. REFER TO PHOTO LOG (9/16/15) PHOTO #17 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 18

| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane |
| Project No. | 100530001 | General Desc. | (Subgrade) Operations LCRS |
| Owner/ Contr. | Honeywell / Arec FW | Cell No. | ~Sta. 7+70 to ~Sta. 7+00 |
| QA Monitor | Langan | Date | 9/17/15 |

Description of Soil Surface to be lined: ~70 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/16/15 (P-94). Subgrade Approved From Approximate Sta. 7+70 (P-94) to Approximate Sta. 7+00 (western slope of 3rd utility corridor). Soil Appears to be Graded, Compacted, and Free of Debris (>1½") and in conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/17/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/17/15 |
| Title | QC Manager |
| Representing: | Entek |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (1 1/2") AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED ALONG SA-6 AS NO AREAS BELOW (TO 1 FT. ABOVE) GROUNDWATER

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |
| 1. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 19

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 7+00 TO ~STA. 6+40 | | |
| QA Monitor | LANGAN | Date | 9/18/15 | | |

Description of Soil Surface to be lined: ~60 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/17/15 (P-97). SUBGRADE APPROVED THROUGH 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 7+00 TO ~STA. 6+40 (EASTERN SIDE OF 3RD UTILITY CORRIDOR). SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/18/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/18/15 |
| Title: | QC Manager |
| Representing: | Entek |
| Signature: | |

LANGAN

Notes, Observations, Comments SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 023172-8.

- GCL PLACED ALONG BOTTOM AND SIDE SLOPES (APPROX 2 FT. TO 3FT. EACH BOTTOM) OF 3RD UTILITY CORRIDOR (LOCATED AT APPROX. STA. 6+80). GCL ALSO PLACED ALONG SOUTHERN END OF CORRIDOR (LOWER BENCH) BELOW TO 1 FT. ABOVE WATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | STA. 6+80 | LOOKING S | REFER TO 9/18/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | STA. 6+86 | LOOKING N | REFER TO 9/18/15 PHOTO LOG (PHOTO #2) |
| 1 REFER TO PHOTO LOG (9/18/15) PHOTOS 1, 2 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2 |

LANGAN

# Certificate of Soil Surface

Sheet # 20

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 180530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 6+40 TO ~STA. 5+30 | | |
| QA Monitor | LANGAN | Date | 9/22/15 | | |

Description of Soil Surface to be lined: ~110 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/18/15 (P-98-103 / EAST-WEST ORIENTATION). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 6+40 TO ~STA. 5+30. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/22/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-22-15 |
| Title: | QC manager |
| Representing: | Entact |
| Signature: | Carolina Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS APPROVED SUBGRADE OUTSIDE OF WATER TABLE INFLUENCE. ONLY GVL REQUIRED

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | 25TH. 6+40 | LOOKING N | REFER TO 9/22/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | 25TH 5+90 | LOOKING S | REFER TO 9/22/15 PHOTO LOG (PHOTO #3) |
| 1 REFER TO PHOTO LOG (9/22/15) PHOTOS 1, 2, 3 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2 |

LANGAN

# Certificate of Soil Surface

Sheet # 21

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 5+30 TO ~STA. 4+50 | | |
| QA Monitor | LANGAN | Date | 9/23/15 | | |

Description of Soil Surface to be lined: ~480 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEC-MEMBRANE PANELS INSTALLED ON 9/22/15 (PANEL #110). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 5+30 TO APPROX. STA. 4+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BUSWORTH |
| Date: | 9/23/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9-23-15 |
| Title: | QC Manager |
| Representing: | Caroline Panico |
| Signature: | ENTACT |

LANGAN

Notes, Observations, Comments SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8.

- GCL PLACED ALONG NORTHERN AND SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO 1FT. ABOVE) THE GROUNDWATER TABLE AS SHOWN ON PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 4+90 | LOOKING S | REFER TO 9/23/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 4+70 | LOOKING W | REFER TO 9/23/15 PHOTO LOG (PHOTO #2) |

1 REFER TO PHOTO LOG (9/23/15) PHOTOS 1, 2 FOR SUPPORTING SUBSURFACE PHOTOS

2

LANGAN

# Certificate of Soil Surface

Sheet # 22


| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 4+50 to ~Sta. 3+80 | | |
| QA Monitor | Langan | Date | 9/24/15 | | |

Description of Soil Surface to be lined: ~480 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/23/15 (Panel N114). Subgrade Approved for Area East of 3rd Utility Corridor From Approximate Sta. 4+50 to Approx. Sta. 3+80. Soil Appears to Be Graded, Compacted, and Free of Debris (>½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bodworth |
| Date: | 9/24/15 |
| Title: | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-24-15 |
| Title: | QC Manager |
| Representing: | Entrie |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8

- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO 1FT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG BOTTOM + SLOPES OF UTILITY/DRAINAGE DITCHES RUNNING N-S THROUGH SA-6, AND AS SHOWN ON THE PROJECT DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 4+50 | LOOKING S | REFER TO 9/24/15 PHOTO LOG (PHOTO #3) |
| | 2 PHOTO #4 | ~STA. 4+50 | LOOKING E | REFER TO 9/24/15 PHOTO LOG (PHOTO #4) |

1 REFER TO PHOTO LOG (9/24/15) PHOTOS 3,4 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR PICTURES OF GCL

2

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north / northeast along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

Prepared soil subgrade through 2nd utility corridor. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking north / northeast along SA-6 Cap (from approximate Sta. 8+50).

**Description:**

ESI deploying GVL. Approved soil subgrade to the east. Soil compacted, graded, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (09/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approx. Sta. 10+00)

**Description:**

ESi deploying GCL along 2nd utility corridor. GCL placed north to south (along bottom of corridor) and east to west (along slopes of corridor).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (09/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/9/15

**Direction Taken:**

Looking east along 2nd utility corridor

**Description:**

ESi placing granular bentonite along GCL seams (overlapped a minimum of 1 ft.) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
9/15/15

**Direction Taken:**

Looking north along southern slope of SA-6

**Description:**

Stakes / staples placed along top 6-inches of GCL to secure material.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (09/16/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
9/16/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 8+20)

**Description:**

ESI deploying geomembrane panels over placed GVL (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking east along SA-6 cap (through 2nd utility corridor)

**Description:**

ESI conducting non-destructive testing as outlined in project specs. Pressure testing conducted between Panel Seams 76 / 77.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap (western slope of 2nd utility corridor).

**Description:**

ESI completed patch / repair over seam joint for non-destruct testing. Patch overlapped, sealed, and extrusion welded as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
9/14/15

**Direction Taken:**

Looking southeast along SA-6 cap (at approximate Sta. 10+20).

**Description:**

ESI installing geomembrane boot around Access Manhole #3 located along western slope of 2nd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
9/15/15

**Direction Taken:**

Looking southwest along SA-6 cap (at approximate Sta. 9+20).

**Description:**

ESI conducting fusion welding along geomembrane seams (P-87 & P-88) as per project specifications



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (09/16/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/16/15

**Direction Taken:**

Looking south along western slope of 2nd utility corridor

**Description:**

ESI conducting vacuum box testing (as per project specs) for geomembrane boot around Access Manhole #3 (RP-262).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (09/17/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/17/15

**Direction Taken:**

Looking west along SA-6 cap (at destruct sample location DS-24)

**Description:**

ESI completing patch / repair work for destruct sample DS-24 collected along Panel 91 / 92 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #13 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:** 9/17/15

**Direction Taken:**

Looking south along SA-6 (through 2nd utility corridor)

**Description:**

ESI placing GDL panels along western slope of 2nd utility corridor. Panels oriented east to west and secured with white plastic fasteners and sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #14 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:** 9/14/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Entact spreading protective cover soil over placed GDL. Warning caution tape spaced at maximum 55-inch intervals, as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #15 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking north along 3rd utility corridor (approximate Sta. 6+80)

**Description:**

ESI placing GDL panels (oriented from east to west) moving north along 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #16 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta. 3+80)

**Description:**

ESI placing GCL over soil subgrade. GCL placed at locations shown on the project drawings and according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 9/9/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 75/86° F, Clear AM, Clouds & Rain PM |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0630 – 1830 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #22**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #75 (P-75) installed on 8/14/15 (located at approximate Sta. 10+20 – western slope of utility corridor) running approximately 70 ft. east through 2nd utility corridor to approximate Sta. 9+50 (eastern slope of 2nd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 10+20 to Sta. 9+50. Refer to *Soil Subgrade Approval* forms from 9/9/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 10+20 to Sta. 9+50.
- While subgrade approval was being conducted, ESI completed patch / repair work for cap wrinkles that were observed from panel placement on 8/14/15. A total of thirty repairs (RP-263 through RP-292) were observed and fixed (according to the project specifications) from Panel #71 and Panel #73 (repair / detailing work conducted on panels installed on 8/14/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), where wrinkles were observed. These areas were subsequently patched and sealed with extrusion welds. No vacuum box testing was conducted on these repairs, and will be completed tomorrow (9/10).
- No non-conformance issues were recorded as patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GCL and Cap placement began with ESI placing the GCL along the eastern and western slopes of the utility corridor and southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #75 (located at approximate Sta. 10+20) on 8/14/15 and through the 2nd utility corridor. Panels were oriented from east to west (as proposed in the approved Panel Layout) and were placed on top of the GCL layer. A total of eleven panel lengths (panel lengths identified as the approximate 80 ft. run from east to west across the corridor, as well as geomembrane pieces which were used to complete the southern end of the corridor) were installed (P-76, P-77, P-78, P-79, P-80, P-81, P-82, P-83, P-84, P-85, and P-86) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/9), *Trial Weld Log.*
- No non-destructive testing or patch / repair work was conducted upon completion of geomembrane panel placement to approximate Sta. 9+50, as panel placement and fusion welded activities concluded the work day.
- One destructive sample was collected – DSX-8 (extrusion weld). Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact completed Site preparation activities for expectation of rainstorms tomorrow (9/10).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/9/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DSX-8 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, and 8/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/9/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 9/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/9/15 |
| A5 – Subgrade Approval | Sheet 15 & ESI (9/9/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/9/15. |
| A7 – Panel Placement Log | Page 16 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 9/9/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 9/9/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no vacuum box testing conducted on 9/9/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Page 13 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/9/15 |
| A11 – Conformance COC | | N / A for 8/14/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 9/9/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 9/9/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/9/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/11/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/77° F, Clear AM, Clouds & Rain PM |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #23** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Dave Ambrose<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from geomembrane Panel #56 (located at approximate Sta. 14+20 – location where GDL had previously been placed to along with protective cover soil) running approximately 220 ft. east to Panel #68 (approximate Sta. 12+00)..
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing for the repairs completed on 9/11/15 (as outlined in projecte specs). One vacuum box testing was complete, ESI began placing GDL from approximate Sta. 14+20 (Panel #56) to approximate Sta. 12+00 (Panel #68). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL were cut with the first wrap of geocomposite removed prior to use
    - Roll 64021010124 – 10 ft. removed
    - Roll 64021010133 – 8 ft. removed
    - Roll 64021010126 – 10 ft. removed
    - Roll 64021010116- 5 ft. removed
    - Roll 64021010112 – 10 ft. removed
        - Note: this roll was not identified during the GDL inspection, however based on damage to the protective plastic liner observed in the field, the outside layer of GDL was removed.
    - Roll 64021010119 – 10 ft. removed
- Due to the inclement weather from 9/10/15 and potential storms over the weekend, the protective plastic covering the soil subgrade to the east was not removed. As such, no soil subgrade approval was conducted and no additional geomembrane panels were placed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- One non-conformance issues was observed during placement of GDL. A rock was encountered underneath geomembrane panel #57. This non-conformance issue was recorded as RP-293 and will be patched and repaired on Monday (9/14).
- Upon completion of GDL placement to the approved panel location, a visual observation of the top of the western slope of the 2nd utility corridor was conducted by Langan and Entact. The geomembrane panels were pulled back to expose the GCL. Visual observation confirmed that the GCL was dry and no water had drained underneath the panels. The top of the slope was then sealed with a fusion weld "T-seams" along Panel #75 (oriented north to south) and Panel #76 through Panel #81 (oriented east to west).
- Geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/11), *Trial Weld Log.* Note: non-destructive testing was completed on the welded seams (to be completed Monday – 9/14/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 6 (Sheet #6) – Subgrade irregularity identified as RP-293 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #57). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 6 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/11/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 4 gas vents).
- Review laboratory results for DSX-8 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, and 8/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/11/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/11/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/11/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/11/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/11/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 9/11/15 |
| A10 – Repair Log | Page 13 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/9/15 |
| A11 – Conformance COC | | N / A for 9/11/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/11/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/11/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet #6 | One non-compliance issue identified on 9/11/15 and recorded on Sheet #6 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/14/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 58/74° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1630 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #24** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from geomembrane Panel #68 (located at approximate Sta. 12+00 – location where GDL had previously been placed to - based on approved as-built drawings) running approximately 170 ft. east to Panel #74 located at top of western slope of 2nd utility corridor (approximate Sta. 10+30).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL from approximate Sta. 12+00 (Panel #68) to approximate Sta. 10+30 (Panel #75). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.
- While GDL was being placed, ESI conducted non-destructive testing (air pressure testing) of the geomembrane panel seams installed on 9/9/15 in accordance with the project specifications. Refer to *Seam Control Form* (9/14/15) for non-destructive testing details.
- Once non-destructive testing was completed, ESI completed patch / repair along the panels previously installed, Panels 76-86 which were placed on 9/9/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/14/15).
- A total of twenty-three repairs (RP-293 through RP-315) were observed and fixed (according to the project specifications) from Panels #76 through Panel #86 (repair / detailing work conducted on panels installed on 9/11/15). Refer to 9/14/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for gas vent GV-3, and completed placing the geomembrane patch around Access Manhole #3. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.
- One destructive sample (DS-22) was collected (fusion) from Panel Seams 79/80. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/14/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-22 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, and 9/11/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/14/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 9/14/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/14/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/11/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/14/15 |
| A8 – Destruct Seam Testing COC | | Updated with destruct sample information collected on 9/14/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 17-18 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/14/15 |
| A10 – Repair Log | Pages 14-15 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/14/15 |
| A11 – Conformance COC | | N / A for 9/14/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/14/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/14/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/15/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #25** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), and continuing from eastern end of 2nd utility corridor. Material to be placed from Panels #76, 77, 78, 79, 80, 81, and 86 (panels running east to west through utility corridor) installed on 9/9/15 (located at approximate Sta. 9+50) running approximately 100 ft. east to Sta. 8+50. Panels installed today (9/15) will "T" into the panels outlined above as panels will revert back to north-south orientation outside of utility corridor (as per the approved panel layout).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 9+50 (eastern end of 2nd utility corridor) to Sta. 8+50. Refer to *Soil Subgrade Approval* forms from 9/15/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 9/15/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 9+50 to Sta. 8+50.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 9+50 (east of 2nd utility corridor) moving east (for approximately 100 ft.) to approximate Sta. 8+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/15/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panels #76-81, and #86 (running east-west through 2nd utility corridor) on 9/9/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-87, P-88, P-89, and P-90) by ESI.

- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/15), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 8+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/15/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/16/15.
- One destructive sample (DS-23) was collected (fusion) from Panel Seams 88/89. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- ESI pulled back the installed geomembrane panels along the northern and southern ends of the 2nd utility corridor to expose the underlying GCL. The GCL appeared to be hydrated (approximate 10 ft. wide section along southern end of corridor and approximate 4 ft. wide section along northern end of corridor) from rainwater infiltration that washed back underneath the cap due to the soil subgrade outside of the cap which was not yet completed to grade. These sections of GCL were cut and removed and the area was left open to dry overnight. New GCL pieces will be placed (according to the project specs) on 9/16/15.
- With cap activities complete, ESI filled sandbags for the remainder of the work day.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/15/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-23 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, and 9/14/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-22, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/15/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 9/15/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/15/15 |
| A5 – Subgrade Approval | Sheet 16 & ESI (9/15/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/15/15. |
| A7 – Panel Placement Log | Page 18 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/15/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/15/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 19-20 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/15/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | N / A no repairs completed for 9/15/15 |
| A11 – Conformance COC | | N / A for 9/15/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/15/15 |
| A13 – Destruct. Sample Summary | Page 4 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/15/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/15/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/16/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 63/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #26** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), and continuing from eastern end of 2nd utility corridor. Material to be placed from Panel #90 (P-90) installed on 9/15/15 and located at approximate Sta. 8+50 running approximately 80 ft. east to Sta. 7+70.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing on the repairs completed from 9/14/15 (through 2nd utility corridor). ESI also conducted patch / repair work for the panels installed on 9/15/15 (Panels 87-90). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 9/16/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-four repairs (RP-316 through RP-349) were observed and fixed (according to the project specifications) from Panel #87 through Panel #90 (repair / detailing work conducted on panels installed on 9/15/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Along with the repair work, ESI also placed the new pieces of GCL (refer to Photo Log) for the northern and southern areas along the 2nd utility corridor where the GCL was hydrated. One area along the southern section required the liner to be cut to pull back and expose the GCL. As such, this repair (RP-331) was identified as a non-conformance issue (subgrade irregularity) and is further defined below.
- While patch / repair work was being completed, Langan and Entact conducting soil subgrade approval from approximate Sta. 8+50 (moving east from P-90) to Sta. 7+70. Refer to *Soil Subgrade Approval* forms from 9/16/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photo #6 of the daily photo log for 9/16/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 8+50 to Sta. 7+70.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 8+50 (moving east of P-90) moving east (for approximately 80 ft.) to approximate Sta. 7+70. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/16/15 Photo Log* for supporting photographs.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, the following rolls of GVL were cut with the first wrap of geocomposite removed prior to use
    - Roll 65211010130 – 8 ft. removed
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #90 on 9/15/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-91, P-92, P-93, and P-94) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/16), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 7+70, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/16/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/17/15.
- One destructive sample (DSX-9) was collected (extrusion weld) from Panel Seams 88/89. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 7 (Sheet #7) – Subgrade irregularity identified as RP-293 on *Repair Log*
    - GCL underneath geomembrane liner along southern end of utility corridor hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final). Geomembrane liner pulled back and cut to remove and replace sections of GCL. This patch was noted as a subgrade irregularity and was patched/repaired following project specs and is further defined on *Sheet 7 Notice of Non-Compliance*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/16/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DSX-9 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, and 9/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-23, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/16/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/16/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/16/15 |
| A5 – Subgrade Approval | Sheet 17 & ESI (9/16/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A6 – Trial Weld Log | Pages 4-5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/16/15. |
| A7 – Panel Placement Log | Page 19 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/16/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/16/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 20-21 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/16/15 |
| A10 – Repair Log | Pages 16-17 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/16/15 |
| A11 – Conformance COC | | N / A for 9/16/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/16/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/16/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 7 | One non-compliance issues identified and further defined on Sheet 7 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/17/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 65/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #27** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu, Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), continuing from eastern end of 2nd utility corridor. Material to be placed from Panel #94 (P-94) installed on 9/16/15 and located at approximate Sta. 7+70 running approximately 70 ft. east to Sta. 7+00 (top western slope of 3rd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work for the panels installed on 9/16/15 (Panels 91-94). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 9/17/15 for results (extrusion testing identified as EXT. on form).
- A total of seventeen repairs (RP-350 through RP-366) were observed and fixed (according to the project specifications) from Panel #91 through Panel #94 (repair / detailing work conducted on panels installed on 9/16/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications. Additionally, custom fit repairs were conducted along the top eastern slope of the 2nd utility corridor (Panel #80) to remove observed wrinkles in the geomembrane panels. Vacuum box testing was then completed on the repairs (as per the project specifications) to confirm the integrity of the extrusion welds.
- Once the patch / repair work was completed ESI began placing GDL from approximate Sta. 10+30 (Panel #75) to approximate Sta. 9+60 (Panel #87). GDL was placed through the 2nd utility corridor with the panels oriented east to west, and was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While GDL placement was being conducted, Langan and Entact completed soil subgrade approval from approximate Sta. 7+70 (moving east from P-94) to Sta. 7+00 (top western slope of 3rd utility corridor). Refer to *Soil Subgrade Approval* forms from 9/17/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 7+70 to Sta. 7+00.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 7+70 (moving east of P-94) moving east (for approximately 70 ft.) to approximate Sta. 7+00. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/17/15 Photo Log* for supporting photographs.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove first wrap of geocomposite prior to use
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #94 on 9/16/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of three panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-95, P-96, and P-97) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/17), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 7+00, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/17/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/18/15.
- One destructive sample (DS-24) was collected (fusion weld) from Panel Seams 91/92. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/17/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-24 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, and 9/16/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-23, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 through, and east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/17/15 |
| A3 – Photo Log | Pages 1 – 3 | Total of 6 photos outlining pertinent daily observations and descriptions for 9/17/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/17/15 |
| A5 – Subgrade Approval | Sheet 18 & ESI (9/17/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/17/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A7 – Panel Placement Log | Page 20 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/17/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/17/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 21 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/17/15 |
| A10 – Repair Log | Pages 16-18 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/16/15 and 9/17/15 |
| A11 – Conformance COC | | N / A for 9/17/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/17/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/17/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/17/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/18/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #28** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu, Bills, Geoff Shallard, Dave Ambrose, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL) geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), through 3rd utility corridor (located at approximate Sta. 6+80). Material to be placed from Panel #97 (P-97) installed on 9/17/15 and located at approximate Sta. 7+00 running approximately 60 ft. east through 3rd utility corridor to Sta. 6+40 (top eastern side of 3rd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 7+00 (P-97 installed on 9/17/15) through the 3rd utility corridor to Sta. 6+40. Refer to *Soil Subgrade Approval* forms from 9/18/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 7+00 to Sta. 6+40.
- GCL and Cap placement began with ESI placing GVL along the eastern and western slopes of the 3rd utility corridor. GVL was placed at the areas above the groundwater table down the slopes of the corridor (GCL areas comprised the bottom of the utility corridor to approximately 2 ft. to 3 ft. up the side slopes). GVL was secured with white plastic fasteners spaced at a maximum of 5 ft. and was sewn along the top layer of geotextile (as outlined in the project specs).
- GCL was then placed along the bottom of the 3rd utility corridor, and along the eastern and western slopes of the utility corridor and southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite. The GVL overlapped the GCL a minimum of 1 ft. along the bottom slopes of the corridor, and the GCL was secured into the side slopes via soil stakes / staples.
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #97 (located at approximate Sta. 7+-00) on 9/17/15 and through the 3rd utility corridor. Panels

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

were oriented from east to west (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers.

- A total of nine panel lengths (panel lengths identified as the approximate 68 ft. run from east to west across the corridor, as well as geomembrane pieces which were used to complete the southern end of the corridor) were installed (P-98, P-99, P-100, P-101, P-102, P-103, P-104, P-105, and P-106) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/18), *Trial Weld Log.*
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- Upon completion of geomembrane panel placement to approximate Sta. 6+40, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/18/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/21/15.
- Two destructive samples (DS-25 and DS-26) were collected (fusion welds) from Panel Seams 94/95 and 97/97, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/18/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 6 gas vents).
- Review laboratory results for DS-25 and DS-26 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, and 9/17/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-24, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 through, and east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/18/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/18/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/18/15 |
| A5 – Subgrade Approval | Sheet 19 & ESI (9/18/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/18/15. |
| A7 – Panel Placement Log | Page 21 & 22 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/18/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/18/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 22-24 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/18/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | N / A repairs patched and leistered, however, no welding or vacuum box testing completed |
| A11 – Conformance COC | | N / A for 9/18/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/18/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/18/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/18/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/21/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1500 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #29** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Dave Ambrose, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing through 2nd utility corridor (located at approximate Sta. 10+00). Material to be placed from eastern slope of 2nd utility corridor (Panels 76-81; running east to west) located at approximate Sta. 10+30) running approximately 250 ft. east to Panel #93 (located at approximate Sta. 7+80).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL from approximate Sta. 10+30 (eastern slope of 2nd utility corridor) to approximate Sta. 7+80 (Panel #93). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.
- Once GDL was completed to the (based on the approved as-builts) , ESI completed patch / repair along the panels previously installed, Panels 95-106 which were placed on 9/17/15 and 9/18/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/21/15).
- A total of thirty-two repairs (RP-367 through RP-398) were observed and fixed (according to the project specifications) from Panels #95 through Panel #106 (repair / detailing work conducted on panels installed on 9/17/15 and 9/18/15). Refer to 9/21/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for gas vent GV-2. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- One destructive sample (DSX-10) was collected (extrusion) from RP-376. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/21/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 6 gas vents).
- Review laboratory data for destruct sample DSX-10 (extrusion) once received

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, and 9/18/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/21/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/21/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/21/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed for 9/21/15. |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/21/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/21/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/21/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 9/21/15 |
| A10 – Repair Log | Pages 18-19 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/21/15 |
| A11 – Conformance COC | | N / A for 9/18/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/21/15 |
| A13 – Destruct. Sample Summary | Page 4 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/21/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/21/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/22/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #30**
**AmecFW**: Stu Bills, Dave Ambrose, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT** / **ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), continuing past eastern side of 3rd utility corridor. Material to be placed from Panels #98, 99, 100, 101, 102, 103, and 106 (panels running east to west through 3rd utility corridor) installed on 9/18/15 (located at approximate Sta. 6+40) running approximately 110 ft. east to Sta. 5+30. Panels installed today (9/22) will "T" into the panels outlined above as panels will revert back to north-south orientation outside of utility corridor (as per the approved panel layout).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 6+40 (eastern end of 3rd utility corridor) to Sta. 5+30. Refer to *Soil Subgrade Approval* forms from 9/22/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 and #3 of the daily photo log for 9/22/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 6+40 to Sta. 5+30.
- While subgrade inspection was being conducted, ESI conducted vacuum box testing for the repairs completed on 9/21/15, and also installed the remaining panels of GDL from geomembrane Panel #93 to Panel #96.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, one roll of GDL was required to be cut to remove the first wrap of geocomposite prior to use – Roll #64021010086 (8 ft. cut).
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 6+40 (east of 3rd utility corridor) moving east (for approximately 110 ft.) to approximate Sta. 5+30. GVL was placed according to

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/22/15 Photo Log* for supporting photographs.

- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, one roll of GVL was required to be cut to remove the first wrap of geocomposite prior to use – Roll #65211010113 (8 ft. cut)
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panels #98-103, and #106 (running east-west through 3rd utility corridor) on 9/18/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-107, P-108, P-109, and P-110) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/22), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 5+30, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/22/15) for non-destructive testing details.
- Once non-destructive testing was completed, ESI conducted patch / repair along the panels installed, Panels 107-110. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/22/15).
- A total of nineteen repairs (RP-399 through RP-417) were observed and fixed (according to the project specifications) from Panels #107 through Panel #110 (repair / detailing work conducted on panels installed on 9/22/15). Refer to 9/22/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for piezometer PZ-14. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.
- No destructive samples were collected, as an RFI was submitted to AmecFW, and based on the results of the first 26 destruct samples – the sampling frequency was decreased from 500 LF to 1500 LF as samples yielded zero failures with all 26 exhibited shear and peel results greater than the minimum requirements (as per the project specs).
- During cap placement activities, Entact spread protective cover soil for the area immediately west of the 2nd utility corridor (approximate Sta. 10+20). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/15/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 4 piezometers, and 5 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, and 9/21/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/22/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/22/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/22/15 |
| A5 – Subgrade Approval | Sheet 20 & ESI (9/22/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/22/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A7 – Panel Placement Log | Page 23 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/22/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/22/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 24-25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/22/15 |
| A10 – Repair Log | Pages 19-20 | One repair log provided by ESI and confirmed by Langan for repairs completed for 9/22/15 |
| A11 – Conformance COC | | N / A for 9/22/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/22/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/22/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/22/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/23/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 58/79° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1700 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #31**<br>**AmecFW**: Stu Bills, Dave Ambrose, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing past eastern side of 3rd utility corridor. Material to be placed from Panels #110 installed on 9/22/15 (located at approximate Sta. 5+30) running approximately 80 ft. east to Sta. 4+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #96/97 (approximate Sta. 7+00) through 3rd utility corridor to approximate Sta. 5+30 (Panel #110 placed on 9/22/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL was required to be cut to remove the first wrap of geocomposite prior to use:
    - Roll #64021010103 - 5 ft. cut and removed
    - Roll #64021010105 – 8 ft. cut and removed
- Langan and Entact conducting soil subgrade approval from east of Panel #110 (located at approximate Sta. 5+30) to approximate Sta. 4+50. Refer to *Soil Subgrade Approval* forms from 9/23/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 9/23/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 5+30 to Sta. 4+50.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 5+30 (east of 3rd utility

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

corridor) moving east (for approximately 80 ft.) to approximate Sta. 4+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/23/15 Photo Log* for supporting photographs.

- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- In addition to the GVL, GCL was placed along the northern and southern edges of SA-6 at areas below (to 1 ft. above) the groundwater table (as shown on the drawings and outlined in the project specs). GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- After installation of the GVL and GCL, geomembrane cap was installed continuing east of previously installed Panel #110 on 9/22/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-111, P-112, P-113, and P-114) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, a trial weld (smooth to smooth) was conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/23), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 4+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/23/15) for non-destructive testing details.
- No patch / repair work was conducted as part of the activities on 9/23/15. Additionally, no destruct samples were collected.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and no patch / repair work was conducted.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, and 9/22/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/23/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 9/23/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/23/15 |
| A5 – Subgrade Approval | Sheet 21 & ESI (9/23/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 5-6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/23/15. |
| A7 – Panel Placement Log | Page 24 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/23/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/23/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/23/15 |
| A10 – Repair Log | | N / A no repairs completed for 9/23/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A11 – Conformance COC | | N / A for 9/23/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/23/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/23/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/23/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/24/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 59/80° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #32** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), and 60-mil geomembrane liner (Cap), continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #114 installed on 9/23/15 (located at approximate Sta. 4+50) running approximately 70 ft. east to Sta. 3+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair along the panels previously installed, Panels 111-114 which were placed on 9/23/15. Prior to repair work, a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/24/15).
- A total of seven repairs (RP-419 through RP-424) were observed and fixed (according to the project specifications) from Panels #111 through Panel #114 (repair / detailing work conducted on panels installed on 9/23/15). Refer to 9/24/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-compliance issue was observed and was noted on *Sheet #8 Notice of Non-Compliance and Corrective Action Form.* This non-compliance was also noted on the Repair Log as a subgrade irregularity and was identified as RP-423. This non-compliance issue was identified based on a rock that was observed underneath the geomembrane cap. The rock was removed from underneath the liner and the hole was patched / repaired according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – *Sheet #8* for 9/24/15.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for well 115-E1A-SO and Access Manhole #4. Note: The penetration logs for all boots to date will be completed once the boots have been sealed with butyl sealant (not yet completed).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was completing patch / repair work, Langan and Entact conducted soil subgrade approval from east of Panel #114 (located at approximate Sta. 4+50) to approximate Sta. 3+80. Refer to *Soil Subgrade Approval* forms from 9/24/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3 and #4 of the daily photo log for 9/24/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 4+50 to Sta. 3+80.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the areas within the SA-6 cap along the bottom and side slopes of the drainage/utility ditches located from approximate Sta. 4+50 to Sta. 3+80. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- After the GCL was placed, GVL was installed from approximate Sta. 4+50 (Panel #114) moving east (for approximately 70 ft.) to approximate Sta. 3+80. GVL was placed along the areas outside of the water GCL (outside of the water table influence) and according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/24/15 Photo Log* for supporting photographs. Note: The GVL was cut along the drainage / utility to expose the GCL as a minimum of 1 ft. of overlap was required along the ditches where the GVL and GCL intersected.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- After installation of the GVL and GCL, geomembrane cap was installed continuing east of previously installed Panel #114 on 9/23/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-115, P-116, P-117, and P-118) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, two trial welds (smooth to smooth and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/24), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 4+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/24/15) for non-destructive testing details.
- No patch / repair work was conducted on Panels #115 through #118 as part of the activities on 9/24/15.
- Two destructive samples were collected for laboratory testing. DS-27 (fusion) was collected from Panel Seam 110/111 and is noted as RP-422 on the *Repair Log*. Fusion weld destruct samples collected at 1500 LF intervals (as per the approved RFI to reduce the sampling frequency from 500 LF to 1500 LF). One extrusion weld sample (DSX-11) was also collected from RP-421 and is noted as RP-424 on the *Repair Log*. Extrusion weld samples collected at 500 LF intervals as per the project specs.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 8 (Sheet #8) – Subgrade irregularity identified as RP-423 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #111). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 8 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/24/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory destruct data for destruct samples DS-27 and DSX-11.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, and 9/23/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/24/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 9/24/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/24/15 |
| A5 – Subgrade Approval | Sheet 22 & ESI (9/24/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/24/15. |
| A7 – Panel Placement Log | Page 25 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/24/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information from 9/24/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25-26 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/24/15 |
| A10 – Repair Log | Pages 20-21 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/24/15 |
| A11 – Conformance COC | | N / A for 9/24/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct sample information from 9/24/15 |
| A13 – Destruct. Sample Summary | Page 3 | One destruct sample summary form provided by ESI and confirmed by Langan for 9/24/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 8 | One non-compliance issue identified on 9/24/15 and identified on Sheet #8 and the Repair Log as a subgrade irregularity. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 4, 2015

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 1 |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | | | X | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.


STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 9/4/15

SWPPP Observer: 
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, September 04, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Blue Poly drums are not properly stored |
| 2 | IA2Q4A1AL8 | Repair Exclusion Zone Fencing associated with EA4 |
| 3 | EEPSQUO2YB | Repair Silt Fence on Southern boundary of Novartis Pile |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 9/4/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place blue poly drums on spill pallets Not an issue or concern | 9/8/15 RAD |
| 2 | Reestablish exclusion zone fencing at excavation area EA4 | ↓ |
| 3 | Repair silt fence on the southern boundary of the Novartis Pile | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** Ed Shore **Date:** 9/4/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 11, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 4 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/11/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, September 11, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Secondary containment measures in the mechanic's area contain stormwater |
| 2 | IA2Q4A1AL8 | Garbage is present along the Kellogg Street jughandle and on the SA-6 cap area. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing is down or requires maintenance in the Sedimentation Basin area on SA-6 North. |
| 4 | IA2Q4A1AL8 | Stockpile containment measures are failing on the eastern side of the Novartis stockpile area on SA-7 |
| 5 | IA2Q4A1AL8 | Sediment is present on the SA-7 paved haul roadways. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/11/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Drain accumulated stormwater from the secondary containment structures. | 9-17-15 RAD |
| 2 | Pick up and dispose of garbage/debris where present. | |
| 3 | Maintain/repair Exclusion Zone fencing as required. | |
| 4 | Install additional erosion control measures on the eastern side of the Novartis stockpile area as required. | |
| 5 | Clean sediment from the SA-7 roadways as required | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date 09/17/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 18, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 09/18/15

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, September 18, 2015

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage is present along the Kellogg Street jughandle and on the north side of Kellogg Street. |
| 2 | IA2Q4A1AL8 | Windscreen on the Rt. 440 perimeter fence at the southern end of the pedestrian walkway has pulled loose from the chain-link fabric on SA-6 North. |
| 3 | IA2Q4A1AL8 | Garbage is present along the entire length of the Rt. 440 pedestrian walkway on SA-6 North. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** 09/18/15 **Date:**

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and dispose of garbage/debris where present. | 9/18/15 RAV |
| 2 | Reinstall or replace windscreen fabric as required | ↓ |
| 3 | Pick up and dispose of garbage/debris where present. | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** **Date:** 09/21/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 25, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 6,7 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/25/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, September 25, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Filter fabric in a catch basin on the north side of Kellogg Street to the west of the guard shack has accumualted a significant amount of sediment. |
| 2 | IA2Q4A1AL8 | Silt fence on along the eastern side of the SA-6 North cap area parallel to Rt. 440 has fallen down and requires maintenance. |
| 3 | IA2Q4A1AL8 | REPEAT ITEM: Windscreen material has detached from the perimeter fence at the southeastern corner of SA-6 North, by the southern end of the Rt. 440 pedestrian walkway. |
| 4 | IA2Q4A1AL8 | REPEAT ITEM: Garbage is present in the SA-6 North pedestrian walkway along Rt. 440. |
| 5 | IA2Q4A1AL8 | Filter fabric in the catch basins on the eastern SA-7 roadway is missing, damaged or blinded by sediment. |
| 6 | IA2Q4A1AL8 | Discarded plastic sheeting, broken pallets and other debris are present in the laydown area to the west of the SA-7 frac tanks. |
| 7 | IA2Q4A1AL8 | Garbage and other debris is present on SA-7 at the waterfront. |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/25/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the filter fabric in the storm water catch basin as required. | 9/28/13 RAD |
| 2 | Replace or re-install the silt fence where it has fallen down. | |
| 3 | Re-attach the windscreen fabric as required | |
| 4 | Remove all accumulated garbage from the pedestrian walkway | |
| 5 | Replace the filter fabric in the storm water catch basins as required | |
| 6 | Remove and dispose of garbage/debris as required. | |
| 7 | Remove and dispose of garbage/debris as required | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 09/29/15

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (Submitted September 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

September 16, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the August 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 8 | 01 | 15 | 8 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,942 | 83,635 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.43 | 0.46 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1384 | 0.1384 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

9/15/2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 8 | 01 | 15 | 8 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,416,202 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 43,418,030 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 8/11/2015 | 4.8 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J Morris VP | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 9/15/2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | | MONTH: August 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BODs | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 8/1/2015 | Angel Trujillo | 41001828 | 41082771 | 80,943 | 0.080943 | N/A | 0.666 | | | | | | | | | 0.45 |
| 8/2/2015 | Angel Trujillo | 41082771 | 41163715 | 80,944 | 0.080944 | 6.78 | 0.666 | | | | | | | | | 0.45 |
| 8/3/2015 | Angel Trujillo | 41163715 | 41236307 | 72,592 | 0.072592 | 6.79 | 0.666 | | | | | | | | | 0.40 |
| 8/4/2015 | Angel Trujillo | 41236307 | 41308231 | 71,924 | 0.071924 | 7.59 | 0.666 | | | | | | | | | 0.40 |
| 8/5/2015 | Angel Trujillo | 41308231 | 41389811 | 81,580 | 0.08158 | 7.56 | 0.666 | | | | | | | | | 0.45 |
| 8/6/2015 | Angel Trujillo | 41389811 | 41462921 | 73,110 | 0.07311 | 7.51 | 0.666 | | | | | | | | | 0.41 |
| 8/7/2015 | Angel Trujillo | 41462921 | 41546556 | 83,635 | 0.083635 | 7.53 | 0.666 | | | | | | | | | 0.46 |
| 8/8/2015 | Angel Trujillo | 41546556 | 41628002 | 81,446 | 0.081446 | 7.52 | 0.666 | | | | | | | | | 0.45 |
| 8/9/2015 | Angel Trujillo | 41628002 | 41703264 | 75,262 | 0.075262 | N/A | 0.666 | | | | | | | | | 0.42 |
| 8/10/2015 | Angel Trujillo | 41703264 | 41778526 | 75,262 | 0.075262 | 7.52 | 0.666 | | | | | | | | | 0.42 |
| 8/11/2015 | Angel Trujillo | 41778526 | 41857202 | 78,676 | 0.078676 | 7.02 | 0.666 | <5.0 | 4.8 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.44 |
| 8/12/2015 | Angel Trujillo | 41857202 | 41933154 | 75,952 | 0.075952 | 7.52 | 0.666 | | | | | | | | | 0.42 |
| 8/13/2015 | Angel Trujillo | 41933154 | 42010732 | 77,578 | 0.077578 | 7.57 | 0.666 | | | | | | | | | 0.43 |
| 8/14/2015 | Angel Trujillo | 42010732 | 42089330 | 78,598 | 0.078598 | 7.47 | 0.666 | | | | | | | | | 0.44 |
| 8/15/2015 | Angel Trujillo | 42089330 | 42171736 | 82,406 | 0.082406 | 7.58 | 0.666 | | | | | | | | | 0.46 |
| 8/16/2015 | Angel Trujillo | 42171736 | 42246145 | 74,409 | 0.074409 | N/A | 0.666 | | | | | | | | | 0.41 |
| 8/17/2015 | Angel Trujillo | 42246145 | 42320554 | 74,409 | 0.074409 | 7.66 | 0.666 | | | | | | | | | 0.41 |
| 8/18/2015 | Angel Trujillo | 42320554 | 42399740 | 79,186 | 0.079186 | 7.57 | 0.666 | | | | | | | | | 0.44 |
| 8/19/2015 | Angel Trujillo | 42399740 | 42477975 | 78,235 | 0.078235 | 7.54 | 0.666 | | | | | | | | | 0.43 |
| 8/20/2015 | Angel Trujillo | 42477975 | 42556035 | 78,060 | 0.07806 | 7.55 | 0.666 | | | | | | | | | 0.43 |
| 8/21/2015 | Angel Trujillo | 42556035 | 42633757 | 77,722 | 0.077722 | 7.51 | 0.666 | | | | | | | | | 0.43 |
| 8/22/2015 | Angel Trujillo | 42633757 | 42717220 | 83,463 | 0.083463 | 7.48 | 0.666 | | | | | | | | | 0.46 |
| 8/23/2015 | Angel Trujillo | 42717220 | 42792665 | 75,445 | 0.075445 | N/A | 0.666 | | | | | | | | | 0.42 |
| 8/24/2015 | Angel Trujillo | 42792665 | 42868110 | 75,445 | 0.075445 | 7.49 | 0.666 | | | | | | | | | 0.42 |
| 8/25/2015 | Angel Trujillo | 42868110 | 42948692 | 80,582 | 0.080582 | 7.52 | 0.666 | | | | | | | | | 0.45 |
| 8/26/2015 | Angel Trujillo | 42948692 | 43023842 | 75,150 | 0.07515 | 7.45 | 0.666 | | | | | | | | | 0.42 |
| 8/27/2015 | Angel Trujillo | 43023842 | 43104616 | 80,774 | 0.0808 | 7.51 | 0.666 | | | | | | | | | 0.45 |
| 8/28/2015 | Angel Trujillo | 43104616 | 43183594 | 78,978 | 0.078978 | 7.47 | 0.666 | | | | | | | | | 0.44 |
| 8/29/2015 | Angel Trujillo | 43183594 | 43266122 | 82,528 | 0.082528 | 7.55 | 0.666 | | | | | | | | | 0.46 |
| 8/30/2015 | Angel Trujillo | 43266122 | 43342076 | 75,954 | 0.075954 | N/A | 0.666 | | | | | | | | | 0.42 |
| 8/31/2015 | Angel Trujillo | 43342076 | 43418030 | 75,954 | 0.075954 | 7.66 | 0.666 | | | | | | | | | 0.42 |
| TOTAL | | | | 2,416,202 | 2.416202 | | | <5.0 | 4.8 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 83,635 | | | | | | | | | | | High: | 0.46 |
| | | | Average: | 77,942 | | | | | | | | | | | Average: | 0.43 |

Accutest LabLink@869982 11:58 26-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-081115-A | | |
| **Lab Sample ID:** | JC1207-1 | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 666 | 10 | ug/l | 1 | 08/12/15 | 08/13/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 08/12/15 | 08/13/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 08/12/15 | 08/13/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 08/13/15 | 08/13/15 | MA | EPA 245.1 [2] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 08/12/15 | 08/13/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 08/12/15 | 08/13/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA37316
(2) Instrument QC Batch: MA37317
(3) Prep QC Batch: MP88321
(4) Prep QC Batch: MP88347

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@869982 11:58 26-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-081115-A | | |
| **Lab Sample ID:** | JC1207-1 | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 08/13/15 | SP | SM2540 D-11 |
| pH [a] | 6.90 | | su | 1 | 08/11/15 16:29 | AL | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@869982 11:58 26-Aug-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-081115-A | | |
| **Lab Sample ID:** | JC1207-1A | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 4.8 | 3.4 | mg/l | 1 | 08/12/15 18:24 | LS | SM5210 B-01 |

RL = Reporting Limit

Accutest LabLink@869982 11:58 26-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-081115-B | | |
| **Lab Sample ID:** | JC1207-2 | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N247694.D | 1 | 08/12/15 | MM | n/a | n/a | VN10501 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.0 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 2.8 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.21 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 17.6 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.40 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.38 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 67.1 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.7 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.43 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@869982 11:58 26-Aug-2015

## Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-081115-B | | |
| **Lab Sample ID:** | JC1207-2 | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 42.9 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | 0.89 | 1.0 | 0.13 | ug/l | J |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 102% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 99% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 102% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 102% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@869982 11:58 26-Aug-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-081115-B | | |
| **Lab Sample ID:** | JC1207-2 | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3

4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 08/12/15 16:48 | LS | EPA 1664A |

RL = Reporting Limit

Accutest LabLink@869982 11:58 26-Aug-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWI-081115 | | |
| **Lab Sample ID:** | JC1207-3 | **Date Sampled:** | 08/11/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 08/11/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N247714.D | 1 | 08/13/15 | MM | n/a | n/a | VN10501 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA PPL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 71-43-2 | Benzene | 2.6 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 4.4 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.25 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 67-66-3 | Chloroform | 21.3 | 1.0 | 0.091 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | 0.38 | 1.0 | 0.16 | ug/l | J |
| 156-60-5 | trans-1,2-Dichloroethene | 3.1 | 1.0 | 0.14 | ug/l | |
| 542-75-6 | 1,3-Dichloropropene (total) | ND | 1.0 | 0.12 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 75-09-2 | Methylene chloride | 0.55 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 79.2 | 1.0 | 0.12 | ug/l | |
| 75-01-4 | Vinyl chloride | 12.5 | 1.0 | 0.13 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 112% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 99% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 105% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 104% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

WW

E

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42227.80965 |
|---|---|---|---|---|
| 2236 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: C9 | COC# 087-WW-091115 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | | | Site ID HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | Preservative 3 3 3 1 2 2 0 0 2 | | Lab Job # HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant CH2M | | | Authorized User: Honeywell |
| Preliminary Data To | | | | Excel & Text File Drive / Excel & Text File Order |
| Sample Receipt Acknowledgement To | Full Report TAT: 28 Days | | | JC1207 |
| Hard Copy To: Helen Fahy (Honeywell) | | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-BL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-081115-A | 8/11/2015 | 14:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | | | | | | L23 |
| 2 | 087-WW | | | 087-WWE-081115-B | 8/11/2015 | 14:10 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | | | | | | V871 |
| 3 | 087-WW | | | 087-WWI-081115 | 8/11/2015 | 14:20 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | | | | | | A37 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | G50 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: 7.02 S.U.@ | 9.6°C Company | AMEC Foster Wheeler | Received by: | Company | | Condition | Custody Seals Intact |
| Frank Schroyer | Date/Time 1454 | 8/11/15 | | Date/Time 8-11 1454 | 8/11/15 | Cooler Temp. | |
| Relinquished by: | Company | | Received by: | Company | | Condition | Custody Seals Intact |
| | Date/Time | 8-11 1710 | | Date/Time | 1710 | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

03.9 SP

INITIAL ASESSMENT 4A/ca

LABEL VERIFICATION MB

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE CL

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending September 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending September 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending September 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-22** | Detail BN has been modified to extend the lIDPE up and over the SCB Wall. The prior detail showed both the GDI and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under th | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending September 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 11 OF 25**

- **2015 Monthly Reports Part 4**

**11/13/2015**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

November 13, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-10**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from October 1 – October 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: October 2015 SA-6/7 Combined Monthly Progress Report No. 2015-10

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2015-10
### Project SA-6 & 7 Remediation

# October 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 10/01/15 | Site 163 Chromium-Impacted Soil Excavation Design Change<br>Study Area 6 South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/02/15 | Spark Testing of Pipe Penetration Boots for Geomembrane Caps | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/5/15 | Arnold & Porter E-mail Communication: Draft Form of Order - Consolidated Study Area 6 Revised Schedule | The Honorable Robert G. Torricelli - Office of the Special Master<br>Jeremy Farrell – City Hall<br>Jason Watson – City Hall<br>Agnieszka Antonian – Connell Foley LLP<br>Kevin Coakley, Esq. – Connell Foley LLP<br>Liza Walsh – Connell Foley LLP<br>Frank Borin – DeCotiis, Fitzpatrick & Cole, LLP<br>Kevin Kinsella – DeCotiis, Fitzpatrick & Cole, LLP<br>David Isabel – Golub & Isabel PC<br>Eric Tomaszewski - Golub & Isabel PC<br>Alicia Clark Alcorn – Terris, Pravlik & Millian, LLP<br>Ben Davis – Terris, Pravlik & Millian, LLP |
| 10/08/15 | Surcharge Monitoring Plan<br>Monthly Report No. 12<br>Study Area 6 South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/08/15 | Warning Tape above Root Barrier Design Change<br>Study Area 6<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/09/15 | Long Term Monitoring Plan<br>Study Area 6 North & South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/12/15 | Summary of In-Situ Treatment of Hexavalent Chromium Impacted Soils Treatment Area 10-1 Only<br>Study Area 6 North (Site 087)<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 10/15/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights<br>Report No. 2015-09 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/20/15 | Special Master Conference Call | N/A |
| 10/20/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 10/20/15 | PW-3 Capture Zone<br>Study Area 7 Groundwater<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/20/15 | New Source of Imported Clean Fill<br>Study Area 6<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 10/4/15 | 10/11/15 | 10/18/15 | 10/25/15 | 11/1/15 |
| **Construction Management (AMEC)** | 8 | 9 | 8 | 9 | 10 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 31 | 38 | 25 | 26 | 27 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 0 | 0 |
| **Langan** | 0 | 0 | 1 | 1 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 2 | 0 | 0 | 2 | 0 |
| **TOTAL STAFF** | **47** | **53** | **40** | **44** | **43** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected September PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Continued screening of Celgene material for use as protective cover soils above geosynthetics.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on October 13, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 10/4/15 | 10/11/15 | 10/18/15 | 10/25/15 | 11/1/15 |
| Avg. Gallons Treated & Discharged (per day) | 74,923 | 76,936 | 76,739 | 77,013 | 76,591 |
| Average Flow (gpm) for Operating Period | 57 | 56 | 54 | 57 | 57 |
| Avg. Hours of Plant Operation | 22 | 23 | 24 | 23 | 22 |
| GWTP Influent Tanks (gal.) | 7,488 | 4,836 | 5,381 | 4,258 | 5,498 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completion of the Excavation Area EA-8 excavation is pending post excavation sampling results.
- Began pumping/dewatering well points associated with Excavation Areas EA-2 and EA-3.
- Completed backfilling of EA-4 Excavation and began backfilling EA-5 Excavation.
- Began trash pit meadow mat repair activities as identified in the 100% Design, which consisted of the removal of concrete slabs and the excavation of historic fill. In addition, the contractor installed vinyl sheeting around the Stratum D repair area that included placement of the sand-bentonite plug.
- Began excavating surficial historic fill in N1 area. A total of 6,375 cubic yards was removed and stockpiled east of the Department of Public Works "H" building.
- Completed relocating soils from Area 3S to the SA-6 North Cap Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| No update for the reporting period | | | | | | | |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| Excavation Completed | Excavation Area N1<br>Volume Excavated - Total for Reporting Period: 6,375CY / Total to Date: 12,807CY |
| Backfill in Progress | Celgene Screened fraction above 3/8 inch – EA-5 , EA-8 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 10/4/15 | 10/11/15 | 10/18/15 | 10/25/15 | 11/1/15 |
| Liberty I-5 | 0 | 0 | 0 | 801.7 | 2,164.97 |

- Screened Celgene materials greater than 3/8 inch were transferred and placed as backfill in EA-8. A total of 25 loads, totaling approximately 563 cubic yards was placed as backfill in EA-8. In addition, 17 loads of crushed concrete totaling 383 yards were placed as backfill in EA-8.
- Screened Celgene material was placed as protective cover soil in the SA-6 South cap area. A total of approximately 5,333 cubic yards was placed as protective cover soil during the reporting period.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading not yet scheduled by contractor.
- Area 3N: Completed installation of surcharge monitoring instrumentation.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- Completed installation of temporary sheet pile along 440 to support the EA2/EA3 excavation.

## G. CAPPING OPERATIONS

- A total of 22,040 sq. ft. of liner totaling 4% of the total cap area was deployed during the reporting period.
- Completed installation of geosynthetic cap components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer for SA-6 South.
- On October 12, 2015 the results of the laboratory testing for destruct sample DSX-13 indicated 1 of 5 specimens exhibited a peel value less than the 66 lb/in minimum value. Based on this one failure anomaly, the repair associated with DSX-13 (RP-477) was covered with a new patch, welded, and vacuum box tested in accordance with the specifications. A new destruct sample DSX-15 was collected to confirm the integrity of the new welds and subsequent analysis indicated a passing result.
- Completed general liner subgrade preparation in Area 3S.
- Completed cutting hydraulic barrier sheets and the SCB wall to final elevation in SA-6 South Open Space Area.
- Completed removing asphalt on top of the SCB wall and smooth coating as necessary for geosynthetics installation detail.
- Completed installation of gas vent pipe on SA-6 South.
- Continued placement of protective cover soils and demarcation tape over the geocomposite drainage layer.
- Began fine grading of GDL cover soils to include associated compaction testing on the west side of the SA-6 South Cap area.
- Began placement of root barrier on the west side of the SA-6 South Cap.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Revision Pending | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Pending | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete excavation and backfilling of Excavation Area EA-8.
- Complete backfilling of Excavation Area EA-5.
- Complete Trash Pit area Meadow Mat Repair.
- Complete installation of sheet pile barrier wall on the interior of the trash pit.
- Complete removal of surficial historic fill in N1 area.
- Begin EA-2/EA-3 excavation activities.
- Complete screening Celgene material for use as protective cover soils above geosyntethics.
- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South.
- Begin import and placement of Horizon C soils on the SA-6 South open space area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 25 in well 088-IW-03 (completed November 4, 2015).

- Begin PW-3 extraction well/trench installation activities.
- Initiate preparation activities for planned Site 163 excavation within the residential footprint.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. *Dewatering Operations Update (not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. *Groundwater Quality Data (conducted quarterly; not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Repair Log
11. Capping Update
    - SA-6 South Cap Subgrade Progress Map
    - Repair Log
    - Non-conformance Log
    - Subgrade Approval Forms
    - QA Photo Log
    - Daily QA Reports (Langan)
12. Weekly SWPPP Reports
13. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted October 2015)
14. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 10/31/15

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Breaking up concrete at former JCIA building.



**Site Photograph 2:** Driving in vinyl sheeting near former JCIA building.




**Site Photograph 3:** Excavating near sheeting with small back hoe.




**Site Photograph 4:** Fine grading of utility corridors.



**Site Photograph 5:** Placing clean fill in utility corridor.




**Site Photograph 6:** Stockpiling of Historic Fill on former city properties.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of November 1, 2015

October 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties

Former Roosevelt Drive-In Site
(Remediation Complete)

Kellogg Street Properties

Hackensack River

Route 440

Kellogg Street

## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 08/28/15 | 7:00 | 13:00 | 6:00 | 35,790.40 | 35,841.14 | 50,740 | 35,697,290 | |
| 09/01/15 | 7:00 | 13:00 | 6:00 | 35,841.14 | 35,929.31 | 88,170 | 35,785,460 | |
| 09/04/15 | 7:00 | 13:00 | 6:00 | 35,929.31 | 35,970.92 | 41,610 | 35,827,070 | |
| 09/09/15 | 7:00 | 15:00 | 8:00 | 35,970.92 | 36,046.73 | 75,810 | 35,902,880 | |
| 09/11/15 | 7:00 | 14:00 | 7:00 | 36,046.73 | 36,113.32 | 66,590 | 35,969,470 | |
| 09/18/15 | 7:00 | 15:00 | 8:00 | 36,113.32 | 36,198.63 | 85,310 | 36,054,780 | |
| 09/28/15 | 8:00 | 11:00 | 3:00 | 36,198.63 | 36,238.88 | 40,250 | 36,095,030 | |
| 09/30/15 | 7:30 | 15:00 | 7:30 | 36,238.88 | 36,367.55 | 128,670 | 36,223,700 | |
| 10/01/15 | 7:00 | 13:30 | 6:30 | 36,367.55 | 36,413.58 | 46,030 | 36,269,730 | PVSC Compliance Sample Collected |
| 10/02/15 | 7:00 | 15:00 | 8:00 | 36,413.58 | 36,458.01 | 44,430 | 36,314,160 | |
| 10/03/15 | 8:00 | 13:00 | 5:00 | 36,458.01 | 36,558.18 | 100,170 | 36,414,330 | |
| 10/04/15 | 9:30 | 13:00 | 3:30 | 36,558.18 | 36,598.54 | 40,360 | 36,454,690 | |
| 10/05/15 | 7:30 | 12:00 | 4:30 | 36,598.54 | 36,653.18 | 54,640 | 36,509,330 | |
| 10/06/15 | 7:30 | 11:30 | 4:00 | 36,653.18 | 36,704.47 | 51,290 | 36,560,620 | |
| 10/09/15 | 7:30 | 14:00 | 6:30 | 36,704.47 | 36,777.92 | 73,450 | 36,634,070 | |
| 10/15/15 | 8:00 | 15:00 | 7:00 | 36,777.92 | 36,888.81 | 110,890 | 36,744,960 | |
| 10/21/15 | 8:00 | 15:00 | 7:00 | 36,888.81 | 36,951.56 | 62,750 | 36,807,710 | |
| 10/23/15 | 11:00 | 14:30 | 3:30 | 36,951.56 | 36,973.34 | 21,780 | 36,829,490 | |
| 10/29/15 | 9:00 | 15:00 | 6:00 | 36,973.34 | 37,092.42 | 119,080 | 36,948,570 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA-8 | <20 | 087-EA8-20-c (bermed / trench material) | 250 | 087-EA8-20-c1 | 6/24/2015 | 11:40 | <1.9 | Yes | | |
| | | | | 087-EA8-20-c2 | 6/24/2015 | 11:45 | <2.1 | Yes | | |
| | | | | 087-EA8-20-c3 | 6/24/2015 | 11:50 | <2.1 | Yes | | |
| | | | | 087-EA8-20-c4 | 6/24/2015 | 11:55 | <1.9 | Yes | | |
| 3S cap material | <240 | 124-3S-EX-a,b,c,d (Excess 3S material) | 3500 | 124-3S-EX-a1 | 8/10/2015 | 12:10 | 51.6 | | Yes | |
| | | | | 124-3S-EX-a2 | 8/10/2015 | 12:15 | 18.6 | * | | |
| | | | | 124-3S-EX-a3 | 8/10/2015 | 12:18 | 37.1 | | Yes | |
| | | | | 124-3S-EX-a4 | 8/10/2015 | 12:20 | 18.9 | * | | |
| | | | | 124-3S-EX-b1 | 8/10/2015 | 12:21 | 24.8 | | Yes | |
| | | | | 124-3S-EX-b2 | 8/10/2015 | 12:22 | 49.3 | | Yes | |
| | | | | 124-3S-EX-b3 | 8/10/2015 | 12:23 | 37.9 | | Yes | |
| | | | | 124-3S-EX-b4 | 8/10/2015 | 12:24 | 40.4 | | Yes | |
| | | | | 124-3S-EX-c1 | 8/10/2015 | 12:25 | 24.7 | | Yes | |
| | | | | 124-3S-EX-c2 | 8/10/2015 | 12:26 | 36.3 | | Yes | |
| | | | | 124-3S-EX-c3 | 8/10/2015 | 12:27 | 46.7 | | Yes | |
| | | | | 124-3S-EX-c4 | 8/10/2015 | 12:28 | 8.1 | * | | |
| | | | | 124-3S-EX-d1 | 8/10/2015 | 12:29 | 25.6 | | Yes | |
| | | | | 124-3S-EX-d2 | 8/10/2015 | 12:30 | 32.1 | | Yes | |
| | | | | 124-3S-EX-d3 | 8/10/2015 | 12:31 | 74.6 | | Yes | |
| | | | | 124-3S-EX-d4 | 8/10/2015 | 12:32 | 34.7 | | Yes | |
| EA4 | <20 | 087-EA4-20-a (bermed/trench material) | 225 | 087-EA4-20-a1 | 9/11/2015 | 10:35 | 2 | Yes | | |
| | | | | 087-EA4-20-a2 | 9/11/2015 | 10:40 | <1.4 | Yes | | |
| | | | | 087-EA4-20-a3 | 9/11/2015 | 10:45 | <1.8 | Yes | | |
| | | | | 087-EA4-20-a4 | 9/11/2015 | 10:50 | 5.0 | Yes | | |
| EA-5 | <20 | 087-EA5-20-a1:b4 (stockpile of A material) | 1300 | 087-EA5-20-a1 | 9/11/2015 | 11:05 | 0.7 | Yes | | |
| | | | | 087-EA5-20-a2 | 9/11/2015 | 11:10 | <1.7 | Yes | | |
| | | | | 087-EA5-20-a3 | 9/11/2015 | 11:15 | <0.46 | Yes | | |
| | | | | 087-EA5-20-a4 | 9/11/2015 | 11:20 | <1.1 | Yes | | |
| | | | | 087-EA5-20-b1 | 9/11/2015 | 11:25 | <2.0 | Yes | | |
| | | | | 087-EA5-20-b2 | 9/11/2015 | 11:30 | 6.8 | Yes | | |
| | | | | 087-EA5-20-b3 | 9/11/2015 | 11:35 | 8.3 | Yes | | |
| | | | | 087-EA5-20-b4 | 9/11/2015 | 11:40 | <0.55 | Yes | | |
| EA-5 | <20 | 087-EA5-20-c1:d4 (stockpile of A material) | 2000 | 087-EA5-20-c1 | 9/11/2015 | 12:10 | <1.8 | * | | |
| | | | | 087-EA5-20-c2 | 9/11/2015 | 12:15 | <1.9 | * | | |
| | | | | 087-EA5-20-c3 | 9/11/2015 | 12:20 | <0.56 | * | | |
| | | | | 087-EA5-20-c4 | 9/11/2015 | 12:25 | <0.60 | * | | |
| | | | | 087-EA5-20-d1 | 9/11/2015 | 12:30 | <0.56 | * | | |
| | | | | 087-EA5-20-d2 | 9/11/2015 | 12:35 | <0.44 | * | | |
| | | | | 087-EA5-20-d3 | 9/11/2015 | 12:40 | <0.5 | * | | |
| | | | | 087-EA5-20-d4 | 9/11/2015 | 12:45 | 9.6 | * | | |
| JCMUA Water Main Break (EA-2) | <20 | 087-EA2-waterline | 50 | 087-EA2-waterline-092815 | 9/28/2015 | NA | 13.5 | * | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'

N4 N3 N2 N1 E1 E2 S4 S3 S2 S1

NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1 117-MW-A99 117-MW-A85 117-MW-A89
115-PZ-6 115-PZ-5 115-PZ-4
073-MW-BB11 073-MW-Y10 134-MW-V09 134-MW-Q08
140-MW-06 140-MW-07 125-MW-L03
MW-124-103L MW-124-102D MW-124-103D MW-124-102T

W6-SO W1-SO W3-SO W5-SO E5-SO E4-SO E3-SO E2-SO E1-SO E1A-SO

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

STA. N11+10 STA. N6+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. F3+75 STA. F4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+58 STA. S3+85 STA. S0+50

KELLOGG STREET

ROUTE 17 NEW JERSEY STATE

## LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE
100' 50' 0 100' 200'

IN PROGRESS
06-10-2015


# STUDY AREA 7
# PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 11/3/2014 | | 4.8 | 5.6 | 5.9 | 6.0 | | 2.8 | 3.1 | 5.1 | 4.7 | 6.7 | 6.2 | 5.6 | 5.3 | 5.7 | | 4.2 | 3.8 | 3.2 | 5.8 | 4.1 | 3.6 |
| 11/17/2014 | | 4.8 | 5.5 | 6.2 | 6.0 | | 3.8 | 5.1 | 5.0 | 4.6 | 6.5 | 6.4 | 5.6 | 5.3 | 5.7 | | 5.4 | 4.9 | 3.7 | 6.6 | 5.4 | 4.9 |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | 4.9 | 6.9 | 6.9 | 6.0 | 5.9 | 6.2 | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | 5.2 | 7.3 | 6.9 | 6.4 | 6.2 | 6.7 | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | 5.0 | 7.2 | 6.7 | 6.0 | 5.8 | 6.3 | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | 5.6 | 6.6 | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-3

Date Exposed: 9/9/15

Describe Damage: Multiple Scrapes due to CAT 349E bucket along the face of the sheet

Damage Location (ft below top of sheet, inboard side outboard side): Along the Lngth of the Sheet from existing ground to BOE

Date Repaired: 9/11/15, 10/22/15, 10/27/15

Inspected by: A. Eslamiezad

Describe Repair: clean, wirebrush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-7

Date Exposed: 9/8/15

Describe Damage: Multiple Scrapes along the face of the sheet, from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE.

Date Repaired: 9/11/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-6

Date Exposed: 9/9/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/11/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-5

Date Exposed: 9/9/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/11/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-4

Date Exposed: 9/9/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/11/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-11
Date Exposed: 9/4/15
Describe Damage: Multiple Scrapes along the face of the sheet, from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE.
Date Repaired: 9/9/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-10
Date Exposed: 9/4/15
Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE
Date Repaired: 9/9/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-9
Date Exposed: 9/8/15
Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE
Date Repaired: 9/9/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-8
Date Exposed: 9/8/15
Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE
Date Repaired: 9/9/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-15

Date Exposed: 9/3/15

Describe Damage: Multiple Scrapes along the face of the sheet, from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/9/15, 10/22/15, 10/27/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-14

Date Exposed: 9/4/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/9/15, 10/22/15, 10/27/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-13

Date Exposed: 9/4/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/9/15, 10/22/15, 10/27/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-12

Date Exposed: 9/4/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/9/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-19

Date Exposed: 9/2/15

Describe Damage: Multiple Scrapes along the face of the sheet, from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE.

Date Repaired: 9/9/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-18

Date Exposed: 9/3/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/9/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-17

Date Exposed: 9/3/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/9/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-16

Date Exposed: 9/3/15

Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE

Date Repaired: 9/4/15, 10/22/15, 10/27/15

Inspected by: A. Eskaminejad

Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-23
Date Exposed: 9/2/15
Describe Damage: Multiple Scrapes along the face of the sheet, from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE.
Date Repaired: 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-22
Date Exposed: 9/2/15
Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE
Date Repaired: 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-21
Date Exposed: 9/2/15
Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE
Date Repaired: 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-20
Date Exposed: 9/2/15
Describe Damage: Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to BOE
Date Repaired: 9/4/15, 10/27/15, 10/22/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-27
Date Exposed: 9/1/15
Describe Damage:

Multiple Scrapes along the face of the sheet, from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to BOE.
Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-26
Date Exposed: 9/1/15
Describe Damage:

Multiple Scrapes along the face of the sheet from the CAT 349E bucket.

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to BOE
Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-25
Date Exposed: 9/1/15
Describe Damage:

Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to BOE
Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

125

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-24
Date Exposed: 9/1/15
Describe Damage:

Multiple Scrapes along the face of the sheet from the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to BOE
Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslaminejad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:
Entact ID: 54P-31
Date Exposed: 8/31/15
Describe Damage:

Multiple scrapes along the face of the sheetpile, from the CAT 349 E bucket

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to the ~~surface~~ BOE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamineyad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:
Entact ID: 54P-30
Date Exposed: 8/31/15
Describe Damage:

Multiple scrapes from the CAT 349 E bucket, along the face of the sheetpile.

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to the BOE.

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamineyad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:
Entact ID: 54P-29
Date Exposed: 8/31/15
Describe Damage:

Multiple Scrapes along the face of the sheet from the CAT 349 E bucket.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from existing ground to the BOE.

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamineyad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID:
Entact ID: 54P-28
Date Exposed: 9/1/15
Describe Damage:

Multiple scrapes from the bucket of the 349 E along the face of the sheetpile

Damage Location (ft below top of sheet, inboard side outboard side):
Along the length of the sheet from existing ground to BOE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamineyad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-35
Date Exposed: 8/28/15
Describe Damage:

Multiple scrapes from the CAT 349 E bucket along the face of the sheet

Damage Location (ft below top of sheet, inboard side outboard side):

Along the length of the sheet from ground surface to BOE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamingad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-34
Date Exposed: 8/28/15
Describe Damage:

Multiple scrapes along the face of the sheet with the CAT 349E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from ground surface to BOE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamingad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-33
Date Exposed: 8/28/15
Describe Damage:

Multiple scrapes along the face of the sheet by the CAT 349 E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from ground surface to the BOE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamingad
Describe Repair:

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-32
Date Exposed: 8/31/15
Describe Damage:

Multiple scrapes along the face of the sheet from the CAT 349 E bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of sheet from ground surface to the BOE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15
Inspected by: A. Eslamingad
Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature:
Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-9b39

Date Exposed: 8/27/15

Describe Damage: Multiple scrapes from the bucket of the CAT 349E. Defects are along the face of the sheet

Damage Location (ft below top of sheet, inboard side outboard side): Along the length from ground surface to BoE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15

Inspected by: A. Eslamiejad

Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-38

Date Exposed: 8/27/15

Describe Damage: Multiple scrapes from the CAT 349E bucket, along the face of the sheet.

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from ground surface to BoE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15

Inspected by: A. Eslamiejad

Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-~~38~~ 37

Date Exposed: 8/27/15

Describe Damage: Multiple scrapes from the CAT 349E bucket, along the face of the sheet

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from ground surface to BoE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15

Inspected by: A. Eslamiejad

Describe Repair: clean, wirebrush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 54P-36

Date Exposed: 8/28/15

Describe Damage: Multiple scrapes from the CAT 349E bucket, along the face of the sheet

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet from ground surface to BoE

Date Repaired: 9/2/15, 9/4/15, 10/22/15, 10/27/15

Inspected by: A. Eslamiejad

Describe Repair: clean, wire brush, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/27/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-43
Date Exposed: 8/26/15
Describe Damage: Epoxy removed on the edges and face of the sheet while excavator trying to remove soil from belly of the sheets.

Equipment 349E Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet

Date Repaired: 9/2/15 Partial 9/4/15 remaining
Inspected by: Ari Eslaminejad
Describe Repair: Clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: _____
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-42
Date Exposed: 8/26/15
Describe Damage: Epoxy removed on the edges and face of the sheet while excavator trying to remove soil from belly of the sheets

Equipment 349E Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet pile

Date Repaired: 9/2/15 Partial 9/4/15 remaining
Inspected by: Ari Eslaminejad
Describe Repair: clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: _____
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-41
Date Exposed: 8/26/15
Describe Damage: _____

Multiple Scrapes of epoxy coating along the length of the sheets on the edges and face.

Equipment 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet

Date Repaired: 9/2/15 Partial 9/4/15 remaining
Inspected by: A. Eslaminejad
Describe Repair: clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: _____
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 54P-40
Date Exposed: 8/27/15
Describe Damage: _____

Multiple Scrapes of epoxy coating along the length of the sheets on the edge and face.

Equipment 349E

Damage Location (ft below top of sheet, inboard side outboard side): Along the length of the sheet

Date Repaired: 9/2/15 Partial 9/4/15 Remaining
Inspected by: A. Eslaminejad
Describe Repair: clean & coat sheets wire brush
Repair Log Closure: AMEC Signature: _____
Date: 9/4/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 52P1-25
Date Exposed: _____
Describe Damage: Multiple scrapes caused by excavator bucket during the meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to elev +4

Date Repaired: 10/30/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 52P-24
Date Exposed: _____
Describe Damage: Multiple scrapes caused by the excavator bucket during meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15
Inspected by: A. Eslaminejad as
Describe Repair: Clean, grind, ~~repair~~ coat

Repair Log Closure: AMEC Signature: [signature]
Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 52P1-23
Date Exposed: _____
Describe Damage: Multiple scrapes along the face of the sheet during meadow mat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15
Inspected by: A. Eslaminejad
Describe Repair: ~~Cl~~ clean, grind, coat as

Repair Log Closure: AMEC Signature: [signature]
Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 52P1-22
Date Exposed: _____
Describe Damage: Multiple scrapes caused by the excavator bucket during the meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15
Inspected by: A. Eslaminejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: S2P1-21

Date Exposed: _____

Describe Damage: Multiple scrapes caused by excavator bucket in meadowmat repair.

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: S2P-20

Date Exposed: _____

Describe Damage: Multiple scrapes caused by excavator bucket in meadow mat repair.

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: S2P-19

Date Exposed: _____

Describe Damage: Multiple scrapes caused by excavator bucket in meadow mat repair

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: S2P-18

Date Exposed: _____

Describe Damage: Multiple scrape caused by excavator bucket in meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-1

Date Exposed: _____

Describe Damage: Multiple scrapes caused by excavator bucket during meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-2

Date Exposed: _____

Describe Damage: Multiple scrapes along the face caused by the excavator bucket during meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-3

Date Exposed: _____

Describe Damage: Multiple scrapes caused by excavator bucket during meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SPI-4

Date Exposed: _____

Describe Damage: Multiple scrapes caused by excavator bucket during meadowmat repair

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to ele +4

Date Repaired: 10/30/15

Inspected by: A. Eslaminejad

Describe Repair: clean, grind, coat


Repair Log Closure: AMEC Signature: _____

Date: 10/30/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

# Attachment 11: Capping Update

- SA-6 South Cap Subgrade Progress Map
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports




LEGEND

- SUBGRADE GRADING UNDERWAY
- SUBGRADE COMPLETE AND SURVEYED
- APPROVED FOR GEOSYNTHETIC DEPLOYMENT
- LINER DEPLOYED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP SUBGRADE PROGRESS MAP
10/09/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | | | | | | | 4977 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | | | | | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | | | | | | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | | | | | | | 6915.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-442 | CF | | 119 | BETWEEN RP-440 & RP-443 | B | | x | | 192 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-443 | CF | | 119 | 149'S OF 119/120 & 17.5'W | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-444 | CF | 119/120 | | BETWEEN RP-439 & RP-440 | B | | x | | 144 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-445 | AO | RP-445 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-446 | AO | RP-446 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-447 | SJ | | | RP-445/RP-446/122 | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-448 | SJ | | | RP-446/121/122 | P | 2.5 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-449 | CF | | 122 | FROM RP-448 TO 10'E | B | | x | | 120 | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-450 | BO | 122/123 | | 23'N OF SEOS | P | 2.5 | x | 4 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-451 | SJ | | | P122/123/124 | P | 1.5 | x | 2 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-452 | SJ | | | P 123/124/125 | P | 1.5 | x | 1.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-453 | CF | | 125 | FROM RP-454 TO 11'S | P | 3.5 | x | 11 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-454 | CF | 123/125 | | 18'N OF SEOS | P | 3 | x | 9.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-455 | CF | | 125 | FROM RP-454 TO 10'N | P | 3.5 | x | 10 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-456 | DS-28 | 123/125 | | 90'N OF SEOS | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-457 | PB | | 125 | 68'S OF P125/126 & 4'W (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-458 | SI | | 125 | ON RP-453 & RP-455 | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-459 | SI | 120,121,122, | &123 | BETWEEN RP-454 TO RP-473 | P | 2 | x | 91 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-460 | DSX-12 | RP-459/123 | | N.SIDE OF RP-459 ( DSX-12 ) | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-461 | SI | | 122 | BETWEEN RP-450 & RP-459 | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-462 | SI | | 122 | FROM RP-461 TO 3'NW | B | | x | | 36 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 4977 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6915.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-463 | SI | | 122 | FROM RP-459 TO 5'S | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-464 | SI | | | SJ 121/122/RP-459 | P | 2 | x | 4 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-465 | SI | | 121 | BETWEEN RP-459 & RP-468 | B | | x | | 6 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-466 | SI | 121/122 | | FROM RP-467 TO RP-465 & RP-468 | B | | x | | 108 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-467 | SI | | 121 | 9'SE OF RP-465 , RP-466 & RP-468 | P | 2 | x | 2.5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-468 | SI | | 121 | BETWEEN RP-465 & RP-469 | B | | x | | 42 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-469 | SI | | 121 | BETWEEN RP-468 & RP-470 | B | | x | | 132 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-470 | SI | | 121 | 11'SW OF RP-468 | P | 2 | x | 3 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-471 | SI | | 121 | BETWEEN RP-468 & RP-472 | B | | x | | 12 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-472 | SI | | 121 | FROM RP-471 TO SEOP | P | 2 | x | 23 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-473 | SI | 119/120 | | BETWEEN RP-439,RP-444& RP-440 | P | 2 | x | 17 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-474 | SI | 119/120 | | NEOS TO 16'S | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-475 | SI | | 117 | NEOP & 5'W OF 117/118 | P | 2 | x | 14 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-476 | PB | 128/132 | 132 | 81'N OF SEOS & 3'E (PB 4") | P | 3 | x | 6 | 36.6 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/9/15 |
| RP-477 | SI | 125/126 | 125 | 159'S OF NEOS & 13' W | P | 2 | x | 13 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-478 | SJ | | | P 127/128/129 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-479 | SJ | | | P 128/129/132 | P | 2 | x | 3 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-480 | DS-29 | 128/132 | | 25'N OF SEOS | P | 2 | x | 7 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-481 | SJ | | | P 128/131/132 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-482 | SJ | | | P 128/130/131 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-483 | DSX-13 | RP-477/125 | | N.SIDE OF RP-477 (DSX-13) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | | | | | | | 4977 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | | | | | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | | | | | | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | | | | | | | 6915.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-484 | DSX-14 | RP-480/132 | | E.SIDE OF RP-480 ( DSX-14) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-485 | SJ | | | P 132/133/143 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-486 | DSX-15 | RP-487/125 | | N.SIDE OF RP-487 (DSX-15) | P | 2 | x | 5 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-487 | FS | | 125 | DS-13 FAIL (CAP OVER RP-483) | P | 5 | x | 15 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| 488 | | | | | | | x | | | | | | | | |
| 489 | | | | | | | x | | | | | | | | |
| 490 | | | | | | | x | | | | | | | | |
| 491 | | | | | | | x | | | | | | | | |
| 492 | | | | | | | x | | | | | | | | |
| 493 | | | | | | | x | | | | | | | | |
| 494 | | | | | | | x | | | | | | | | |
| 495 | | | | | | | x | | | | | | | | |
| 496 | | | | | | | x | | | | | | | | |
| 497 | | | | | | | x | | | | | | | | |
| 498 | | | | | | | x | | | | | | | | |
| 499 | | | | | | | x | | | | | | | | |
| 500 | | | | | | | x | | | | | | | | |
| 501 | | | | | | | x | | | | | | | | |
| 502 | | | | | | | x | | | | | | | | |
| 503 | | | | | | | x | | | | | | | | |
| 504 | | | | | | | x | | | | | | | | |

**Summary of Non-Compliance & Corrective Action Forms**
**SA-6 South Cap Installation**

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 1 | 7/21/2015 | Subgrade Irregularity | RP-3 | Panel #2 (P-2) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2.5 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 2 | 7/21/2015 | Subgrade Irregularity | RP-8 | Panel #2 (P-2) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2.5 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 3 | 7/22/2015 | Failed Non-Destruct Test | RP-13 | Panel #7 (P-7) & Panel #8 (P-8) seam | Based on length of failed seam (approximately 6 ft.) the entire seam was patched and repaired (approximate 2 ft. by 6 ft. patch). The patch was overlapped a minimum of 4-inches, with rounded edges, and sealed with an extrusion weld. Vacuum box testing was then conducted in accordance with Section 02372-8 to confirm the weld. |
| 4 | 7/24/2015 | Subgrade Irregularity | RP-30 | Panel #17 (P-17) | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 5 | 8/7/2015 | Failed Vacuum Box Test | RP-215 | Panel #50 (P-50) | Failed extrusion weld (identified during vacuum box testing) was patched with an approximate 2 ft. by 2 ft. geomembrane patch over the extrusion weld (noted as RP-222 on Repair Log). The patch was overlapped a minimum of 4-inches beyond the edges of the failed weld, conformed so that the edges were rounded, and sealed with an extrusion weld. Vacuum box testing was conducted along the seams to confirm the seams were properly patched and repaired. |
| 6 | 9/11/2015 | Subgrade Irregularity | RP-293 | Panel #57 (P-57) | Rock was removed from underneath geomembrane and hole was then patched with approximate 1.5 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 7 | 9/16/2015 | Subgrade Irregularity - Hydrated GCL | RP-331 | Panel #83 (P-83) | Geomembrane cap was cut and GCL was exposed. Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. The cut in the geomembrane was then repaired with approximate 2 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). |
| 8 | 9/24/2015 | Subgrade Irregularity | RP-423 | Panel #111 (P-111) | Rock was removed from underneath geomembrane and hole was then patched with approximate 1.5 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 9 | 10/7/2015 | Subgrade Irregularity - Hydrated GCL | RP-458 through RP-473 | Panels #121-125 (P-121 to P-125) | Geomembrane cap was cut and GCL was exposed (southern swale of SA-6). Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. Various cuts in the geomembrane were then repaired with geomembrane patches. The patches were overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the cuts were properly patched (as outlined in Section 02372). |
| 10 | 10/7/2015 | Subgrade Irregulairty - Hydrated GCL | RP-474 & RP-475 | Panels #117 and Panel #119/120 | Geomembrane cap was cut and GCL was exposed (northern end of SA-6 at SCB wall). Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. Various cuts in the geomembrane were then repaired (RP-474 & RP-475) with geomembrane patches. The patches were overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the cuts were properly patched (as outlined in Section 02372). |

**Summary of Non-Compliance & Corrective Action Forms**
**SA-6 South Cap Installation**

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 11 | 10/12/2015 | Failed Destruct Sample | RP-477 | Panel #125 (P-125) | Geomembrane patch was placed over RP-477 (failed one of five specimens during destruct testing), and was overlapped a minimum of 4-inches beyond the edges of the repair, conformed so the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the patch was properly sealed (as outlined in Section 02372). Additionally, once the new patch (RP-486) was completed, an additional destruct sample (DSX-15) was collected to confirm the integrity of the new weld. Subsequent testing of DSX-15 yielded laboratory results that were in complinace with the project specs. |

LANGAN

# Certificate of Soil Surface

Sheet # 23

| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 3+80 to ~Sta. 3+30 |
| QA Monitor | Langan | Date | 9/25/15 |

Description of Soil Surface to be lined: ~ 50 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/24/15 (Panel #118). Subgrade Approved for Area East of 3rd Utility Crossing From Approximate Sta. 3+80 to Approx. Sta. 3+30. Soil Appears to Be Graded, Compacted, and Free of Debris (>½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/25/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-25-15 |
| Title | QC Manager |
| Representing: | Entuck |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8
- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AND AT AREAS BELOW (TO 1 FT. ABOVE) THE GROUNDWATER TABLE, AS DEFINED ON THE PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | ~STA. 3+50 | LOOKING E | REFER TO 9/25/15 PHOTO LOG (PHOTO #5) |
| | 2 PHOTO #6 | ~STA. 3+40 | LOOKING N | REFER TO 9/25/15 PHOTO LOG (PHOTO #6) |

1 REFER TO PHOTO LOG (9/25/15) PHOTOS 5,6 FOR SUPPORTING SUBGRADE PHOTOS (WITH GCL).

2

LANGAN

# Certificate of Soil Surface

Sheet # 24

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL |
| Project No. | 10053000 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 3+30 TO ~STA. 2+50 |
| QA Monitor | LANGAN | Date | 9/29/15 |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/25/15 (PANEL #120). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 3+30 TO APPROX. STA. 2+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name | DANIEL BOSWORTH |
| Date | 9/29/15 |
| Title | LEAD QA ENGINEER |
| Representing | LANGAN |
| Signature | |

| Geosynthetic Installer Representative | |
|---|---|
| Name | Carolina Panico |
| Date | 9-29-15 |
| Title | QC Manager |
| Representing | Entact |
| Signature | Carolina Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AS OUTLINED IN SECTION 02372-8.
- GCL PLACED ALONG NORTHERN & SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW, (TO 1 FT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG LOWER BENCH ON EASTERN END OF SA-6 AS SHOWN ON THE PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | ~STA. 3+30 | LOOKING S | REFER TO 9/29/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | ~STA. 2+90 | LOOKING E | REFER TO 9/29/15 PHOTO LOG (PHOTO #3) |

1 REFER TO PHOTO LOG (9/29/15) PHOTOS 2, 3 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR PICTURES OF GCL.

2

LANGAN

# Certificate of Soil Surface

Sheet # 25

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 2+50 TO ~STA 1+50 | | |
| QA Monitor | LANGAN | Date | 10/8/2015 | | |

Description of Soil Surface to be lined: ~100 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/29/15 (PANEL # 125). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 2+50 TO APPROX. STA. 1+50 (EASTERN END OF SA-6, ROUTE 440). SOIL APPROVED TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (1½") AND IN CONFORMANCE W/ SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 10/8/2015 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 10/8/15 |
| Title | QC Manager |
| Representing: | ENTACT |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8
- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW, (TO LFT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG LOWER BENCH ON EASTERN END OF SA-6 AS SHOWN ON PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 1+70 | LOOKING N/NW | REFER TO 10/8/15 PHOTO LOG (PHOTO #3) |
| | 2 PHOTO #4 | ~STA. 2+00 | LOOKING S | REFER TO 10/8/15 PHOTO LOG (PHOTO #4) |

1 REFER TO PHOTO LOG (10/8/15) PHOTOS 3,4 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR SUPPORTING PHOTOS OF GVL + GCL

2

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+00)

**Description:**

ESI deploying GDL over installed geomembrane panels. GDL placed according to project specs with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta.3+30)

**Description:**

Soil subgrade east of Panel #120 prepared for panel placement. Subgrade prepared according to project specs (graded, compacted, and free of debris >1/2").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 2+90)

**Description:**

GVL and GCL placed over approved subgrade prior to placement of geomembrane panels. GCL placed at areas below (to 1 ft. above) the groundwater table (as shown on project drawings) with GVL placed on the upper bench above water table areas.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/7/15

**Direction Taken:**

Looking east along SA-6 cap (Panel 123 / 125 seam

**Description:**

ESI collecting destruct sample DS-28 (fusion) along Panel 123 / 125 seam as per project specs



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (10/8/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast toward eastern end of SA-6

**Description:**

ESI deploying geomembrane panels over GVL and GCL (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (10/8/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
10/8/15

**Direction Taken:**

Looking east at eastern end of SA-6 (along Route 440).

**Description:**

ESI conducting fusion welding along Panel Seams 132/133 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (10/8/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/8/15

**Direction Taken:**

Looking northeast along SA-6

**Description:**

Pipe boot PZ-12 completed with extrusion welds and vacuum box tested to confirm integrity (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (10/9/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6 (at piezometer PZ-12)

**Description:**

ESI placing final butyl seal around piezometer PZ-12



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (10/9/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6

**Description:**

ESI placing final 1-inch band clamp around Manhole #4 with final butyl seal applied (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
10/12/15

**Direction Taken:**

Looking south along SA-6 (at RP-487)

**Description:**

ESI conducting extrusion welding (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESI conducting vacuum box testing (as per project specs) for RP-487



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESI cutting destruct sample DSX-15 from RP-487 to confirm integrity of welds.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/29/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/79° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #34**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #120 installed on 9/25/15 (located at approximate Sta. 3+30) running approximately 80 ft. east to Sta. 2+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #114 (approximate Sta. 4+50) to approximate Sta. 3+80 (Panel #118 placed on 9/24/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use:
    - Roll #64021010072 – Approximately 8 ft. removed
    - Roll #64021010064 – Roll not on inspection list. Approximately 30 ft. removed due to damage observed from forklift
- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #120 (located at approximate Sta. 3+30) to approximate Sta. 2+50. Refer to *Soil Subgrade Approval* forms from 9/29/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 and #3 of the daily photo log for 9/29/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 3+30 to Sta. 2+50.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 3+30 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- Upon placement of the GCL, GVL was placed along the upper elevations within the areas outside of the water table influence (as shown on the project drawings). GVL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals and the top layer of geotextile sewn.
- After installation of the GCL and GVL, geomembrane cap was installed continuing east of previously installed Panel #120 on 9/25/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-120, P-121, P-122, P-123, P-124, and P-125) by ESI. Note: During placement of geomembrane panel P-123, the roll of geomembrane terminated within the SA-6 approximately 20 ft. from the southern end of the cap. Thus an additional panel (P-124) was required to complete the geomembrane run from north to south.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, three trial welds (smooth to smooth, smooth to texture, and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/29), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 2+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/29/15) for non-destructive testing details. Once, non-destructive testing was completed, ESI then conducted patch/ repair work for the panels installed.
- A total of eleven repairs (RP-445 through RP-455) were observed and fixed (according to the project specifications) from Panels #121 through Panel #125 (repair / detailing work conducted on panels installed on 9/24/15). Refer to 9/29/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. No non-compliance issues were identified as patch / repair work completed was custom fit repairs to allow geomembrane to conform to SA-6 contours.
- No destructive samples were collected from 9/29/15
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of custom fit repairs to allow the geomembrane to conform to the SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/29/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, and 9/25/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/29/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 9/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/29/15 |
| A5 – Subgrade Approval | Sheet 24 & ESI (9/29/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/29/15. |
| A7 – Panel Placement Log | Page 27 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/29/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected for 9/29/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 27-28 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/29/15 |
| A10 – Repair Log | Page 22 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/29/15 |
| A11 – Conformance COC | | N / A for 9/29/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected from 9/29/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected from 9/29/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered from 9/29/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 10/07/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 60/72° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0630 – 1600 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #35** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor, and patch / repair work associated with panels placed from 9/29/15.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing patch / repair work for minor wrinkles from panels previously placed on 9/29/15 (Panels 121 – 125). During the patch / repair work it was observed that the GCL underlying the geomembrane panels was hydrated with standing water present at two areas:
    - Area 1 was comprised of the drainage / utility swale located along the southern end of SA-6 (approximate Sta. 3+50 to Sta. 2+60 ). At this area, a sump pump pit was located immediately outside of SA-6 cap to the south. During the storm events over the weekend, this pump at one point shut down thus causing a build-up (ponding) of water that extended laterally into the swale and hydrating the GCL.
    - Area 2 was located along the northern end of the cap (approximate Sta. 4+00 to Sta. 3+40) along the SCB wall. During the storm events water from the adjacent roadway (higher elevation than the SA-6 cap as final grading has not yet been completed) ran along the edges of SA-6 causing some soil washout, which allowed the water to infiltrate laterally over the SCB wall and onto the lower portion of SA-6.
- For both of these areas, the geomembrane cap was pulled back to expose the hydrated GCL. The GCL was then cut and removed to expose the underlying soil subgrade. Visual observation of the subgrade showed that the soil was in good condition (firm and unyielding) with no wet or wash out areas observed. New GCL was then placed in these areas with minimum of 1 ft. of overlap and granular bentonite placed along the seams as per project specifications. Refer to *10/7/15 Photograph Log* for supporting Site photos.
- Once the new GCL was placed, the geomembrane panels were patch / repaired (as required) over these areas.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of twenty repairs (RP-456 through RP-475) were observed and fixed (according to the project specifications) from Panels #119 through Panel #122 (repair / detailing work for replaced GCL on panels installed from 9/29/15). Refer to 10/7/15 *Repair Report.* The majority of these repairs were patch / repairs associated with the removal and replacing of the hydrated GCL. These repairs were identified as subgrade irregularities on the *Repair Report,* and were identified as non-compliance issues on *Sheet #9* and *Sheet #10 Notice of Non-Compliance* forms, respectively. Note: RP-457 which consisted of a pipe boot for GV-0 was marked in the field and noted on the Repair Report (as RP-457), however the boot and repair itself has not yet been completed.
- Two destructive samples were collected from 10/7/15. Destruct sample DS-28 (fusion) was collected from Panel #123/125, and sample DSX-12 was collected from RP-459 (Panel #123).
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 9 (Sheet #9) – Subgrade irregularity (hydrated GCL) identified as repairs RP-458 through RP-473 on *Repair Log*
    - GCL underneath geomembrane liner along southern end SA-6 (swale) hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final) and failure of sump pump in area during storm. Geomembrane liner pulled back and cut to remove and replace sections of GCL. These patches were noted as a subgrade irregularities and were completed following project specs and are further defined on *Sheet 9 Notice of Non-Compliance*
- Non-Conformance No. 10 (Sheet #10) – Subgrade irregularity (hydrated GCL) identified as RP-474 and RP-475 on *Repair Log*
    - GCL underneath geomembrane liner along northern end of SA-6 cap (along SCB wall) hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final). Geomembrane liner pulled back and cut to remove and replace sections of GCL. These patches were noted as a subgrade irregularities and were patched/repaired following project specs as further defined on *Sheet 10 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/7/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 7 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DS-28 and DSX-12.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, and 9/29/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/7/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 10/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/7/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/7/15 |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/7/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/7/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected form 10/7/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 10/7/15 |
| A10 – Repair Log | Pages 22-23 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/7/15 |
| A11 – Conformance COC | | N / A for 10/7/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct sample information from 10/7/15 |
| A13 – Destruct. Sample Summary | Page 3 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/7/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before logs can be completed |
| A16 – Notice of Non-Compliance | Sheet #9 and Sheet #10 | Two non-compliance forms completed (Sheet #9 and Sheet #10) for cutting and removal of hydrated GCL |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 10/08/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/77° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1830 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #36**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #125 installed on 9/29/15 (located at approximate Sta. 2+50) running approximately 100 ft. east to Sta. 1+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #118 (approximate Sta. 3+80) to approximate Sta. 2+50 (Panel #125). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #125 (located at approximate Sta. 2+50) to approximate Sta. 1+50. Refer to *Soil Subgrade Approval* forms from 10/08/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3 and #4 of the daily photo log for 10/08/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 2+50 to Sta. 1+50.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 2+50 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- Upon placement of the GCL, GVL was placed along the upper elevations within the areas outside of the water table influence (as shown on the project drawings). GVL was placed according to project

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals and the top layer of geotextile sewn.

- After installation of the GCL and GVL, geomembrane cap was installed continuing east of previously installed Panel #125 on 9/29/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of ten varying panel lengths were placed by ESI (Panels #126-134). Note: the dimensions of these panel lengths varied as the geomembrane panels were conformed to fit along the eastern end of the SA-6 cap.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, three trial welds (smooth to smooth, smooth to texture, and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (10/8), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 1+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (10/08/15) for non-destructive testing details. Once, non-destructive testing was completed, ESI then conducted minor patch/ repair work for the panels installed (pipe boots PZ-12).
- A total of one repair (RP-476) was completed (according to the project specifications) for Panel #132 (pipe boot PZ-12). Refer to 10/8/15 *Repair Report* for additional details on the pipe boot. Note: no non-compliance issues were observed during the geomembrane placement and testing conducted on 10/8/15.
- One destructive sample was collected from 10/8/15. Destruct sample DS-29 (fusion) was collected from Panel #128/132 seam.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of pipe boot installations around PZ-12.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/8/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 5 piezometers, and 8 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DS-29.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, and 10/07/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-28, and DSX-1 through DSX-12. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/8/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 10/8/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/8/15 |
| A5 – Subgrade Approval | Sheet 25 & ESI (10/8/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Pages 6-7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/8/15. |
| A7 – Panel Placement Log | Pages 28-29 | One panel placement log provided by ESI and confirmed by Langan for prewelds completed on 10/8/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/8/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 28-30 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 10/8/15 |
| A10 – Repair Log | Page 23 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 10/8/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/8/15 |
| A13 – Destruct. Sample Summary | Page 3 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/8/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before logs can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 10/09/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 58/75° F, Clear, Overcast, PM T'Storm |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0630 – 1730 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #37** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor, and to eastern end of SA-6, and patch / repair work associated with panels placed from 10/8/15 (Panels #126-134).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing patch / repair work for panels previously placed on 10/8/15 (Panels #126-134). A total of nine repairs (RP-477 through RP-485) were observed and fixed (according to the project specifications) from Panels #126 through Panel #134. Refer to 10/9/15 *Repair Report* for additional details. The majority of these repairs were custom fit details (allow the geomembrane to conform to the SA-6 contours) or seam joint repairs (joints where non-destructive testing was completed). Repairs were patched, sealed with an extrusion weld, and vacuum box tested (according to project specs).
- Two destructive samples were collected from 10/9/15. Destruct sample DSX-13 (extrusion) was collected from RP-477 (Panel #125) and DSX-14 (extrusion) was collected from RP-480 (Panel #132).
- Upon completion of the patch / repair work, ESI completed the final monitoring well, piezometer, and gas vent boots by placing the final butyl sealant around the top of the boot. Additionally, 1-inch pipe bands were placed around the conical Access Manholes (as per project specs).
- With the pipe boots completed, ESI deployed GDL from Panel #125 to Panel #134 (panels placed on 10/9/15). GDL was placed according to project specs with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile sewn.
- Note: As per the AmecFW GDL Cover Soil Siltation Evaluation and Mitigation Measures Memo (Memo) submitted October 2015, three areas in the field were identified where GDL was exposed and silts were deposited directly onto the GDL. In response to the protective cover soil siltation, three new pieces of GDL were placed directly over the potentially impacted areas to assist in drainage. Additional details of these areas and mitigation measures are further described in the AmecFW Memo, with supporting photographs provided.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.
- Upon completion of the daily activities, ESI demobilized from the Site, as SA-6 capping activities were completed.

***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as patch / repair work completed consisted of custom fit repairs and seam joint patches to allow the geomembrane to conform to the SA-6 contours.

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/9/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (for 3 wells, 5 piezometers, and 8 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1, and Manhole #2, Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DSX-13 and DSX-14.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, and 10/08/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-12. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue with protective cover soil placement along eastern end of SA-6.
- Ensure destruct samples are in compliance with project specs and complete associated paperwork and construction certification report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/9/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 10/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/8/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/9/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/9/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/9/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/9/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 10/9/15 |
| A10 – Repair Log | Pages 23-24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/9/15 |
| A11 – Conformance COC | | N / A for 10/9/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/9/15 |
| A13 – Destruct. Sample Summary | Page 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/9/15 |
| A14 – Penetration & Edge Form | Sheets #1-18 | Final penetration & edge forms completed for piezometers, wells, gas vents, and access manholes. |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 10/12/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 72° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 1520 – 1720 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #38**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of patch / repair work associated with a failed destruct test (DSX-13) for RP-477 located on Panel #125.
- Based on results of the laboratory destruct testing, 1 of 5 specimens exhibited a peel value less than the 66 lb/in value allotted (as per the project specs) for destruct sample DSX-13. Based on this one failure anomaly, the repair associated with DSX-13 (RP-477) was covered with a new patch, welded, and vacuum box tested (as per project specs). In addition, a new destruct sample DSX-15 was collected to confirm the integrity of the new welds associated with the new patch. Note: the average of the 5 peel specimens complied with the project specs (total of 92 lb/in).
- Site activities commenced with ESI completing patch / repair work for RP-477. A new 5 ft. by 15 ft. patch was placed over the repair, sealed with an extrusion weld, and vacuum box tested as per project specs. Once the new repair (RP-487) was complete, a new destruct sample, DSX-15, was collected to confirm the integrity of the weld.
- One destructive sample was collected from 10/12/15. Destruct sample DSX-15 (extrusion) was collected from RP-487 (placed over RP-477). Subsequent laboratory testing yielded peel and shear values that were in compliance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 11 (Sheet #11) – Failed destruct sample (DSX-13) collected from RP-477 from Panel #125 (failed one of the five specimens for peel testing)
    - Geomembrane patch was placed over RP-477, welded, and vacuum box tested (as per project specs). Additionally, a new destruct sample (DSX-15) was collected from the new patch (RP-487) to confirm the integrity of the new weld. This repair was noted as a failed destruct sample and was completed following project specs and as further defined on *Sheet 11 Notice of Non-Compliance.*

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/12/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory data for destruct samples DSX-15.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, 10/08/15, and 10/09/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-14. Laboratory results in compliance with shear and peel requirements as outlined in project specifications with the exception of DSX-13. Subsequent patch / repair work defined within this report for the failed destruct sample.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Ensure new destruct sample (DSX-15) adheres to project specifications. Subsequent review of the data yielded peel and shear values that were in compliance with the project specs.
- Complete associated paperwork and begin construction certification report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/12/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 10/12/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/12/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/12/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/12/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/12/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/12/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 10/12/15 |
| A10 – Repair Log | Page 24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/12/15 |
| A11 – Conformance COC | | N / A for 10/12/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/12/15 |
| A13 – Destruct. Sample Summary | Page 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/12/15 |
| A14 – Penetration & Edge Form | | N / A no penetration and edge forms completed for 10/12/15 |
| A16 – Notice of Non-Compliance | Sheet #11 | One non-compliance issue encountered on 10/12/15 and documented on *Sheet #11 Notice of Non-Compliance* |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: October 2, 2015

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☒ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☒ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | | X | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

NOTE: All comments are numbered for reference and included on the included comment section.

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 10/1/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, October 02, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Scrap white fabric on the ground |
| 2 | IA2Q4A1AL8 | Screenings berm requires maintenance |
| 3 | IA2Q4A1AL8 | Silt fence around EA-8 requires maintenance. Barrels and orange fencing should be secured or relocated. |
| 4 | IA2Q4A1AL8 | Sediment has accumulated on the EA-5 roadway. King berm requires maintenance or removal. Catch basin filter fabric requires replacement |
| 5 | IA2Q4A1AL8 | Silt fence is required around the EA-4 excavation. Wind screen fence posts needs to be fixed, it has been dislodged. |
| 6 | IA2Q4A1AL8 | Silt fence requires maintenance |
| 7 | IA2Q4A1AL8 | Silt fence laying on the ground |
| 8 | IA2Q4A1AL8 | Silt fence requires maintenance |
| 9 | IA2Q4A1AL8 | Silt fence requires maintenance, rolls of GDL/GVL scattered along the roadway, celgene screenings requires sediment control |
| 10 | IA2Q4A1AL8 | Silt has overtopped the berms along the eastern section of the Surcharge stockpiles on SA-7 |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 10/1/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | DONE | 10/2/15 (RA1) |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 10/08/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: October 9, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

NOTE: All comments are numbered for reference and included on the included comment section.

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 10/09/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, October 09, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Several spill pallets in the SA-6 South mechanics area have filled with storm-water. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing at on the western side of the SA-6 North trash pit is down and is not adequately marked. |
| 3 | IA2Q4A1AL8 | Orange warning fencing around the EA-5 excavation is down and requires repair |
| 4 | IA2Q4A1AL8 | Filter fabric in the catch basin to the north of the SA-6 North trash pit is blinded. |
| 5 | IA2Q4A1AL8 | Silt fence along the northern access road on SA-7 requires maintenance/repair. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 10/09/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Drain the accumulated storm-water from the spill pallets as required. | RAD 10/13/15 |
| 2 | Reinstall or repair the orange EZ fencing and install additional signage as needed. | |
| 3 | Re-establish the warning fencing around the open excavation. | |
| 4 | Replace the catch basin filter fabric as required. | |
| 5 | Repair the silt fencing as needed. | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 10/14/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: October 16, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 3 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 10/16/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, October 16, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and other debris is present along the north side of Kellogg Street and along the Kellogg Street jughandle |
| 2 | IA2Q4A1AL8 | The hazardous material pile in the SA-6 North cap area is not covered |
| 3 | IA2Q4A1AL8 | Due to sediment build-up, stormwaler in the northeast corner of the sedimentation basin Exclusion Zone no longer flows to the sump in that area. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 10/16/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up garbage/debris as required. | 10/19/15 RHS |
| 2 | Tarp the hazardous material pile as required. | ↓ |
| 3 | Re-establish a swale to direct stormwater run-off to the sump | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 10/21/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: October 23, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 10/23/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, October 23, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence surroundinng the SA-6 South cap area is down in some locations and requires maintenance or replacement. |
| 2 | IA2Q4A1AL8 | Site sediment has accumulated on the Rt. 440 sidewalk outside of SA-6 South. |
| 3 | IA2Q4A1AL8 | Silt dams in the area of SA-6 North where water main work was recently completed have been damaged and are no longer functional. |
| 4 | IA2Q4A1AL8 | Garbage is present in the Rt. 440 pedestrian walkway on SA-6 North |
| 5 | IA2Q4A1AL8 | Silt fence on the southern side of the SA-6 North cap area is down in some locations and requires maintenance or replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: 10/23/15 Signature Date:

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the silt fence as needed to restore function. | berms are present no need for silt fence RAD |
| 2 | Shovel up and remove all site-related sediment on the Rt. 440 sidewalk. | next week |
| 3 | Repair or replace the silt dams as needed to restore function. Shovel up and remove any soil material between the new silt dams and the pedestrian walkway. | RAD 10/28/15 |
| 4 | Pick up and remove accumulated refuse from the walkway | ↓ |
| 5 | Repair or replace the silt fence as needed to restore function. | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: Date: 10/29/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: October 30, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 4 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

NOTE: All comments are numbered for reference and included on the included comment section.

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 10/30/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, October 30, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fabric in a storm drain catch basin on the western end of Kellogg Street is torn. |
| 2 | IA2Q4A1AL8 | **REPEAT:** Site sediment has accumulated on the Rt. 440 sidewalk outside of SA-6 South. |
| 3 | IA2Q4A1AL8 | Silt fence along the JCMUA perimeter, due north of the EA-5 excavation, has been overtopped with historic fill material and requires maintenance or replacement. |
| 4 | IA2Q4A1AL8 | Exclusion Zone fencing is absent along the southern side of the EA-5 excavation area. |
| 5 | IA2Q4A1AL8 | Silt fence surrounding the Novartis stockpile area requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 10/30/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the filter fabric in the catch basin as required. | MM 11-9-15 |
| 2 | Shovel up and remove all site-related sediment on the Rt. 440 sidewalk. | MM 11-9-15 |
| 3 | Remove the historic fill material from the installed silt fence, repair or replace as required. | MM 11-9-15 |
| 4 | Install Exclusion Zone fencing and signage as required. | Completed 11/05/15 |
| 5 | Repair or replace the silt fence as needed to restore function. | MM 11-9-15 |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 11/09/15

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (Submitted October 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

October 20, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the September 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 9 | 01 | 15 | 9 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,610 | 85,210 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.75 | 0.82 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00021 | 0.00021 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.2 | <5.2 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.132 | 0.132 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J Morris HF

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

10/19/2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 9 | 01 | 15 | 9 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,328,298 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 45,746,328 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 9/10/2015 | 5.1 | 6.6 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris VP | John J. Morris | (973) 455-4003 |
| | | DATE 10/19/2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: September, 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 9/1/2015 | Angel Trujillo | 43418030 | 43497868 | 79,838 | 0.079838 | 7.54 | 1.160 | | | | | | | | | 0.77 |
| 9/2/2015 | Angel Trujillo | 43497868 | 43574466 | 76,598 | 0.076598 | 7.52 | 1.160 | | | | | | | | | 0.74 |
| 9/3/2015 | Angel Trujillo | 43574466 | 43650460 | 75,994 | 0.075994 | 7.20 | 1.160 | | | | | | | | | 0.74 |
| 9/4/2015 | Angel Trujillo | 43650460 | 43731984 | 81,524 | 0.081524 | 7.17 | 1.160 | | | | | | | | | 0.79 |
| 9/5/2015 | Angel Trujillo | 43731984 | 43812906 | 80,922 | 0.080922 | 7.12 | 1.160 | | | | | | | | | 0.78 |
| 9/6/2015 | Angel Trujillo | 43812906 | 43888751 | 75,845 | 0.075845 | N/A | 1.160 | | | | | | | | | 0.73 |
| 9/7/2015 | Angel Trujillo | 43888751 | 43964596 | 75,845 | 0.075845 | 7.23 | 1.160 | | | | | | | | | 0.73 |
| 9/8/2015 | Angel Trujillo | 43964596 | 44044350 | 79,754 | 0.079754 | 7.12 | 1.160 | | | | | | | | | 0.77 |
| 9/9/2015 | Angel Trujillo | 44044350 | 44122725 | 78,375 | 0.078375 | 7.17 | 1.160 | | | | | | | | | 0.76 |
| 9/10/2015 | Angel Trujillo | 44122725 | 44196996 | 74,271 | 0.074271 | 6.75 | 1.160 | <5.2 | 5.1 | | <0.010 | <0.015 | <0.010 | 0.00021 | <0.020 | 0.72 |
| 9/11/2015 | Angel Trujillo | 44196996 | 44278070 | 81,074 | 0.081074 | 7.23 | 1.160 | | | | | | | | | 0.78 |
| 9/12/2015 | Angel Trujillo | 44278070 | 44361752 | 83,682 | 0.083682 | 7.17 | 1.160 | | | | | | | | | 0.81 |
| 9/13/2015 | Angel Trujillo | 44361752 | 44436554 | 74,802 | 0.074802 | N/A | 1.160 | | | | | | | | | 0.72 |
| 9/14/2015 | Angel Trujillo | 44436554 | 44511356 | 74,802 | 0.074802 | 7.20 | 1.160 | | | | | | | | | 0.72 |
| 9/15/2015 | Angel Trujillo | 44511356 | 44588584 | 77,228 | 0.077228 | 7.12 | 1.160 | | | | | | | | | 0.75 |
| 9/16/2015 | Angel Trujillo | 44588584 | 44667980 | 79,396 | 0.079396 | 7.18 | 1.160 | | | | | | | | | 0.77 |
| 9/17/2015 | Angel Trujillo | 44667980 | 44745836 | 77,856 | 0.077856 | 7.08 | 1.160 | | | | | | | | | 0.75 |
| 9/18/2015 | Angel Trujillo | 44745836 | 44822084 | 76,248 | 0.076248 | 7.08 | 1.160 | | | | | | | | | 0.74 |
| 9/19/2015 | Angel Trujillo | 44822084 | 44907294 | 85,210 | 0.08521 | 7.10 | 1.160 | | | | | | | | | 0.82 |
| 9/20/2015 | Angel Trujillo | 44907294 | 44982294 | 75,000 | 0.075 | N/A | 1.160 | | | | | | | | | 0.73 |
| 9/21/2015 | Angel Trujillo | 44982294 | 45057294 | 75,000 | 0.075 | 7.07 | 1.160 | | | | | | | | | 0.73 |
| 9/22/2015 | Angel Trujillo | 45057294 | 45135636 | 78,342 | 0.078342 | 7.09 | 1.160 | | | | | | | | | 0.76 |
| 9/23/2015 | Angel Trujillo | 45135636 | 45212786 | 77,150 | 0.07715 | 7.15 | 1.160 | | | | | | | | | 0.75 |
| 9/24/2015 | Angel Trujillo | 45212786 | 45289888 | 77,102 | 0.077102 | 7.07 | 1.160 | | | | | | | | | 0.75 |
| 9/25/2015 | Angel Trujillo | 45289888 | 45368271 | 78,383 | 0.078383 | 7.15 | 1.160 | | | | | | | | | 0.76 |
| 9/26/2015 | Angel Trujillo | 45368271 | 45452107 | 83,836 | 0.083836 | N/A | 1.160 | | | | | | | | | 0.81 |
| 9/27/2015 | Angel Trujillo | 45452107 | 45535943 | 83,836 | 0.0838 | 6.95 | 1.160 | | | | | | | | | 0.81 |
| 9/28/2015 | Angel Trujillo | 45535943 | 45595082 | 59,139 | 0.059139 | 7.08 | 1.160 | | | | | | | | | 0.57 |
| 9/29/2015 | Angel Trujillo | 45595082 | 45673047 | 77,965 | 0.077965 | 7.05 | 1.160 | | | | | | | | | 0.75 |
| 9/30/2015 | Angel Trujillo | 45673047 | 45746328 | 73,281 | 0.073281 | 7.07 | 1.160 | | | | | | | | | 0.71 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,328,298 | 2.328298 | | | <5.2 | 5.1 | | <0.010 | <0.015 | <0.010 | 0.00021 | <0.020 | |
| | | | High: | 85,210 | | | | | | | | | | | High: | 0.82 |
| | | | Average: | 77,610 | | | | | | | | | | | Average: | 0.75 |

WW

JC3544

| Accutest Labs | | |

Accutest LabLink@873300 09:58 17-Sep-2015 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091015-A | | |
| **Lab Sample ID:** | JC3544-1 | **Date Sampled:** | 09/10/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/10/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1160 | 10 | ug/l | 1 | 09/11/15 | 09/14/15 | AP | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 09/11/15 | 09/14/15 | AP | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 09/11/15 | 09/14/15 | AP | EPA 200.7 [2] | EPA 200.7 [4] |
| Mercury | 0.21 | 0.20 | ug/l | 1 | 09/11/15 | 09/11/15 | VM | EPA 245.1 [1] | EPA 245.1 [3] |
| Nickel | < 10 | 10 | ug/l | 1 | 09/11/15 | 09/14/15 | AP | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 09/11/15 | 09/14/15 | AP | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA37530
(2) Instrument QC Batch: MA37552
(3) Prep QC Batch: MP88942
(4) Prep QC Batch: MP88958

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@873300 09:58 17-Sep-2015 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091015-A | | |
| **Lab Sample ID:** | JC3544-1 | **Date Sampled:** | 09/10/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/10/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | 6.6 | 4.0 | mg/l | 1 | 09/11/15 | KP | SM2540 D-11 |
| pH [a] | 7.00 | | su | 1 | 09/10/15 19:30 | HFM | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@873300 09:58 17-Sep-2015 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091015-A | | |
| **Lab Sample ID:** | JC3544-1A | **Date Sampled:** | 09/10/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/10/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 5.1 | 3.4 | mg/l | 1 | 09/10/15 20:50 | LS | SM5210 B-11 |

RL = Reporting Limit

Accutest LabLink@873300 09:58 17-Sep-2015 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091015-B | | |
| **Lab Sample ID:** | JC3544-2 | **Date Sampled:** | 09/10/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/10/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | T211133.D | 1 | 09/15/15 | DC | n/a | n/a | VT8660 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.0 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 2.7 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.22 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 16.9 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.44 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.36 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 63.2 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.7 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.41 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Draft: 4 of 8

Accutest LabLink@873300 09:58 17-Sep-2015 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091015-B | | |
| **Lab Sample ID:** | JC3544-2 | **Date Sampled:** | 09/10/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/10/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 42.1 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 99% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 102% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 103% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 104% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@873300 09:58 17-Sep-2015 Preliminary Data

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-091015-B | | |
| **Lab Sample ID:** | JC3544-2 | **Date Sampled:** | 09/10/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 09/10/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.2 | 5.2 | mg/l | 1 | 09/11/15 09:45 | BM | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending October 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending October 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending October 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-22** | Detail BN has been modified to extend the lIDPE up and over the SCB Wall. The prior detail showed both the GDI and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending October 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**12/11/2015**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

December 11, 2015

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-11**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from November 1 – November 30, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: November 2015 SA-6/7 Combined Monthly Progress Report No. 2015-11

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2015-11

**Project SA-6 & 7 Remediation**

## November 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 11/13/15 | Riverkeeper et al v. Honeywell International Inc. et al<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights<br>Report No. 2015-10 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/17/15 | E-mail from William Hague: S-3 Injection Event #25 Summary with Data | Ben Ross<br>Kim Hosea<br>Steve Egnaczyk |
| 11/17/15 | Special Master Meeting | N/A |
| 11/19/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 11/24/15 | Summary of Site 163, Additional Area G Sample<br>SA-6 South, Site 163<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 11/8/15 | 11/15/15 | 11/22/15 | 11/29/15 |
| **Construction Management (AMEC)** | 8 | 9 | 9 | 6 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 27 | 28 | 28 | 29 |

| | | | | |
|---|---|---|---|---|
| **Arecon/US Ecology Subcontractors** | 2 | 2 | 0 | 0 |
| **Langan** | 1 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 0 | 4 | 0 |
| **Century Electric** | 0 | 0 | 2 | 0 |
| **TOTAL STAFF** | **44** | **45** | **49** | **41** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected September PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed screening of Celgene material for use as protective cover soils above geosynthetics.
- Conducted S-3 Mass Removal Injection Event No. 25 in well 088-IW-03.
- Completed installation of PW-3 extraction well and observation well OBS-7.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on November 12, 2015.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 11/8/15 | 11/15/15 | 11/22/15 | 11/29/15 |
| Avg. Gallons Treated & Discharged (per day) | 76,371 | 76,957 | 77,338 | 77,033 |
| Average Flow (gpm) for Operating Period | 55 | 56 | 56 | 53 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 24 |
| GWTP Influent Tanks (gal.) | 4,430 | 5,186 | 4,953 | 4,856 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.

- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed cleaning and decommissioning of frac tanks, piping, and valves that were used at SA-6 South for collection and transfer of construction water to the treatment system located at SA-6 North.
- Continue pumping/dewatering of well points associated with Excavation Areas EA-2 and EA-3.
- Began excavation and backfilling of Excavation Areas EA-2 and EA-3. Contractor temporarily relocated the JCMUA water meter concrete vault within the EA-2/EA-3 excavation area. The vault was staged outside the limits of the EA-2/EA-3 excavation area.
- Completed backfilling EA-5 Excavation.
- Completed trash pit meadow mat repair activities to include installation of the sand-bentonite plug in the SA-6 North Stratum D repair area on the interior side to the vinyl sheets and placement of GCL.
- Completed excavating surficial historic fill in N1 area. A total of ~5,000 cubic yards was removed and stockpiled east of the Department of Public Works "H" building for subsequent sampling.

## 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| Horwith | Tri-axle | PA Transload | US Ecology | >240 mg/kg CrVI | 150 | 21.72 | 3,258.35 |

## 2. EXCAVATION & BACKFILL PROGRESS

| Description | Cells |
|---|---|
| **Excavation Completed** | Excavation Area N1, EA-2/EA-3<br>Volume Excavated - Total for Reporting Period: N1(4,964 CY) EA-2/EA-3(6,840 CY) /<br>Total to Date: 24,611CY |
| **Backfill in Progress** | EA-5 |

## 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 11/8/15 | 11/15/15 | 11/22/15 | 11/29/15 |
| Liberty I-5 | 1,787 | 1,399 | 71 | 504 |
| Horizon C soils | 1,600 | 1,209 | 3,501 | 0 |
| Tilcon 1.5" | 0 | 0 | 251.11 | 0 |

- Screened Celgene materials greater than 3/8 inch were transferred and placed as bridge lift in EA-2/EA-3. A total of 18 loads, totaling approximately 406 cubic yards was placed as temporary fill for bridge lift in EA-2/EA-3.

- Screened Celgene material was removed from the east side of the SA-6 South open space area during final grading of the protective cover soils. Approximately 1,530 cubic yards was removed from the cap area and transferred to the Celgene stockpile area.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Continued off-loading of remaining screened historic fill.
- Area 2N: Surcharging is 100% complete. Offloading is anticipated to be begin in December 2015.
- Area 3N: Completed installation of surcharge monitoring instrumentation.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- Begin installation of wales to the temporary sheet pile along Route 440.

## G. CAPPING OPERATIONS

- On November 4, 2014, liner crew was on site to address the remaining repair area identified near the SCB wall on the east side of the SA-6 Southopen space area.
- Completed placement of protective cover soils and demarcation tape over the geocomposite drainage layer.
- Continued fine grading of protective cover soils to include associated compaction testing on the SA-6 South open space area.
- Continued placement of root barrier and demarcation tape on the SA-6 Southopen space area.
- Began placement and grading of Horizon C soils (within future vegetated areas) and structural fill (within future roadway areas) of the SA-6 South open space area.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Pending | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete excavation and backfilling of Excavation Area EA-8.
- Complete Trash Pit Interior work activities.
- Continue EA-2/EA-3 excavation and backfilling activities.
- Begin Area 3N Surcharge material placement.
- Begin installation of the Contingent Groundwater Extraction System piping in Area 1N.

- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.
- Continue placement of Horizon C soils on the SA-6 South open space area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 26 in well 088-IW-01 (completed December 7-9, 2015).
- Complete PW-3 force main/trench installation and associated piping connections back to GWTP
- Begin dewatering and excavation activities associated with Site 163 excavation within the residential footprint.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill
   - Progression Chart
4. Dewatering Operations Update
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. *Groundwater Quality Data (conducted quarterly; not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update
    - Repair Log
11. Capping Update
    - SA-6 South Cap Subgrade Progress Map
    - Repair Log
    - QA Photo Log
    - Daily QA Reports (Langan)
12. Weekly SWPPP Reports
13. GWTP Update
    - 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted November 2015)
    - 12/2/15 PVSC Correspondence: Revisions to Sewer Use Permit #20630025
14. SA-6 North & South Design Change Tracking Log


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule

Study Areas 6 and 7 Combined Progress Report No. 2015-11
Attachment 1: Schedule – 6 Month Look Ahead

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 11/30/15

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Grading slopes in open space area.




**Site Photograph 2:** Grading utility corridor soils in open space area.




**Site Photograph 3:** Loading of material for offsite disposal.




**Site Photograph 4:** Loading of materials for onsite reuse.



**Site Photograph 5:** Placing clean fill over white root barrier.




**Site Photograph 6:** Screener removes larger stone material.



**Site Photograph 7:** Unloading clean imported soils.




**Site Photograph 8:** White geotextile placed as root barrier.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of December 1, 2015

November 2015 SA-6/7 Progress Report Attachment 3: Excavation and Backfill



# Attachment 4: Dewatering Operations Update

**STUDY AREA 6 SOUTH DEEP WELL DATA (DW-7)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/18/15 | 24 | N/A | N/A | 11,500 | 11,500 | 8.0 | Flow meter not installed, tank measured |
| 11/19/15 | 24 | N/A | N/A | 11,000 | 22,500 | 7.6 | |
| 11/20/15 | 24 | N/A | N/A | 11,000 | 33,500 | 7.6 | |
| 11/22/15 | 48 | N/A | N/A | 11,000 | 44,500 | 3.8 | |
| 11/23/15 | 24 | N/A | N/A | 11,000 | 55,500 | 7.6 | |
| 11/24/15 | 24 | N/A | N/A | 10,500 | 66,000 | 7.3 | |
| 11/25/15 | 24 | N/A | N/A | 10,500 | 76,500 | 7.3 | |
| 11/29/15 | 96 | N/A | N/A | 40,000 | 116,500 | 6.9 | |
| 11/30/15 | 24 | N/A | N/A | 10,500 | 127,000 | 7.3 | |

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 09/30/15 | 7:30 | 15:00 | 7:30 | 36,238.88 | 36,367.55 | 128,670 | 36,223,700 | |
| 10/01/15 | 7:00 | 13:30 | 6:30 | 36,367.55 | 36,413.58 | 46,030 | 36,269,730 | |
| 10/02/15 | 7:00 | 15:00 | 8:00 | 36,413.58 | 36,458.01 | 44,430 | 36,314,160 | |
| 10/03/15 | 8:00 | 13:00 | 5:00 | 36,458.01 | 36,558.18 | 100,170 | 36,414,330 | |
| 10/04/15 | 9:30 | 13:00 | 3:30 | 36,558.18 | 36,598.54 | 40,360 | 36,454,690 | |
| 10/05/15 | 7:30 | 12:00 | 4:30 | 36,598.54 | 36,653.18 | 54,640 | 36,509,330 | |
| 10/06/15 | 7:30 | 11:30 | 4:00 | 36,653.18 | 36,704.47 | 51,290 | 36,560,620 | |
| 10/09/15 | 7:30 | 14:00 | 6:30 | 36,704.47 | 36,777.92 | 73,450 | 36,634,070 | |
| 10/15/15 | 8:00 | 15:00 | 7:00 | 36,777.92 | 36,888.81 | 110,890 | 36,744,960 | |
| 10/21/15 | 8:00 | 15:00 | 7:00 | 36,888.81 | 36,951.56 | 62,750 | 36,807,710 | |
| 10/23/15 | 11:00 | 14:30 | 3:30 | 36,951.56 | 36,973.34 | 21,780 | 36,829,490 | |
| 10/29/15 | 9:00 | 15:00 | 6:00 | 36,973.34 | 37,092.42 | 119,080 | 36,948,570 | |
| 11/02/15 | 8:00 | 13:00 | 5:00 | 37,092.42 | 37,158.61 | 66,190 | 37,014,760 | PVSC Compliance Sample Collected |
| 11/04/15 | 8:30 | 14:30 | 6:00 | 37,158.61 | 37,207.47 | 48,860 | 37,063,620 | |
| 11/06/15 | 12:00 | 15:00 | 3:00 | 37,207.47 | 37,237.70 | 30,230 | 37,093,850 | |
| 11/18/15 | 8:00 | 15:00 | 7:00 | 37,237.70 | 37,375.84 | 138,140 | 37,231,990 | |
| 11/22/15 | 9:00 | 13:00 | 4:00 | 37,375.84 | 37,440.68 | 64,840 | 37,296,830 | |
| 11/23/15 | 9:30 | 14:30 | 5:00 | 37,440.68 | 37,505.15 | 64,470 | 37,361,300 | |
| 11/25/15 | 7:15 | 13:45 | 6:30 | 37,505.15 | 37,566.11 | 60,960 | 37,422,260 | |
| 11/30/15 | 7:30 | 14:30 | 7:00 | 37,566.11 | 37,667.64 | 101,530 | 37,523,790 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| 3S cap material | <240 | 124-3S-EX-a,b,c,d (Excess 3S material) | 3500 | 124-3S-EX-a1 | 8/10/2015 | 12:10 | 51.6 | | Yes | |
| | | | | 124-3S-EX-a2 | 8/10/2015 | 12:15 | 18.6 | * | | |
| | | | | 124-3S-EX-a3 | 8/10/2015 | 12:18 | 37.1 | | Yes | |
| | | | | 124-3S-EX-a4 | 8/10/2015 | 12:20 | 18.9 | * | | |
| | | | | 124-3S-EX-b1 | 8/10/2015 | 12:21 | 24.8 | | Yes | |
| | | | | 124-3S-EX-b2 | 8/10/2015 | 12:22 | 49.3 | | Yes | |
| | | | | 124-3S-EX-b3 | 8/10/2015 | 12:23 | 37.9 | | Yes | |
| | | | | 124-3S-EX-b4 | 8/10/2015 | 12:24 | 40.4 | | Yes | |
| | | | | 124-3S-EX-c1 | 8/10/2015 | 12:25 | 24.7 | | Yes | |
| | | | | 124-3S-EX-c2 | 8/10/2015 | 12:26 | 36.3 | | Yes | |
| | | | | 124-3S-EX-c3 | 8/10/2015 | 12:27 | 46.7 | | Yes | |
| | | | | 124-3S-EX-c4 | 8/10/2015 | 12:28 | 8.1 | * | | |
| | | | | 124-3S-EX-d1 | 8/10/2015 | 12:29 | 25.6 | | Yes | |
| | | | | 124-3S-EX-d2 | 8/10/2015 | 12:30 | 32.1 | | Yes | |
| | | | | 124-3S-EX-d3 | 8/10/2015 | 12:31 | 74.6 | | Yes | |
| | | | | 124-3S-EX-d4 | 8/10/2015 | 12:32 | 34.7 | | Yes | |
| EA4 | <20 | 087-EA4-20-a (bermed/trench material) | 225 | 087-EA4-20-a1 | 9/11/2015 | 10:35 | 2 | Yes | | |
| | | | | 087-EA4-20-a2 | 9/11/2015 | 10:40 | <1.4 | Yes | | |
| | | | | 087-EA4-20-a3 | 9/11/2015 | 10:45 | <1.8 | Yes | | |
| | | | | 087-EA4-20-a4 | 9/11/2015 | 10:50 | 5.0 | Yes | | |
| EA-5 | <20 | 087-EA5-20-a1:b4 (stockpile of A material) | 1300 | 087-EA5-20-a1 | 9/11/2015 | 11:05 | 0.7 | Yes | | |
| | | | | 087-EA5-20-a2 | 9/11/2015 | 11:10 | <1.7 | Yes | | |
| | | | | 087-EA5-20-a3 | 9/11/2015 | 11:15 | <0.46 | Yes | | |
| | | | | 087-EA5-20-a4 | 9/11/2015 | 11:20 | <1.1 | Yes | | |
| | | | | 087-EA5-20-b1 | 9/11/2015 | 11:25 | <2.0 | Yes | | |
| | | | | 087-EA5-20-b2 | 9/11/2015 | 11:30 | 6.8 | Yes | | |
| | | | | 087-EA5-20-b3 | 9/11/2015 | 11:35 | 8.3 | Yes | | |
| | | | | 087-EA5-20-b4 | 9/11/2015 | 11:40 | <0.55 | Yes | | |
| EA-5 | <20 | 087-EA5-20-c1:d4 (stockpile of A material) | 2000 | 087-EA5-20-c1 | 9/11/2015 | 12:10 | <1.8 | * | | |
| | | | | 087-EA5-20-c2 | 9/11/2015 | 12:15 | <1.9 | * | | |
| | | | | 087-EA5-20-c3 | 9/11/2015 | 12:20 | <0.56 | * | | |
| | | | | 087-EA5-20-c4 | 9/11/2015 | 12:25 | <0.60 | * | | |
| | | | | 087-EA5-20-d1 | 9/11/2015 | 12:30 | <0.56 | * | | |
| | | | | 087-EA5-20-d2 | 9/11/2015 | 12:35 | <0.44 | * | | |
| | | | | 087-EA5-20-d3 | 9/11/2015 | 12:40 | <0.5 | * | | |
| | | | | 087-EA5-20-d4 | 9/11/2015 | 12:45 | 9.6 | * | | |
| 3S cap material | <240 | 124-3S-EX2-a | 780 | 124-3S-EX2-a1 | 9/28/2015 | -- | 50 | | Yes | |
| | | | | 124-3S-EX2-a2 | 9/28/2015 | -- | 48.5 | | Yes | |
| | | | | 124-3S-EX2-a3 | 9/28/2015 | -- | 82.3 | | Yes | |
| | | | | 124-3S-EX2-a4 | 9/28/2015 | -- | 785 | | | Yes |
| 3S Cap Material (under asphalt roadway) | <240 | 124-3S-Roadway-a | 525 | 124-3S-Roadway-a1 | 9/28/2015 | -- | 327 | | | Yes |
| | | | | 124-3S-Roadway-a2 | 9/28/2015 | -- | 2100 | | | Yes |
| | | | | 124-3S-Roadway-a3 | 9/28/2015 | -- | 1970 | | | Yes |
| | | | | 124-3S-Roadway-a4 | 9/28/2015 | -- | 5900 | | | Yes |
| JCMUA Water Main Break (EA-2) | <20 | 087-EA2-waterline | 50 | 087-EA2-waterline-092815 | 9/28/2015 | NA | 13.5 | * | | |
| 3S cap material | <240 | 124-3S-EX3-a | 1000 | 124-3S-EX3-a1 | 10/21/2015 | -- | 3120 | | | Yes |
| | | | | 124-3S-EX3-a2 | 10/21/2015 | -- | 6820 | | | Yes |
| | | | | 124-3S-EX3-a3 | 10/21/2015 | -- | 5690 | | | Yes |
| | | | | 124-3S-EX3-a4 | 10/21/2015 | -- | 4300 | | | Yes |

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| 1N (2 foot cut material) | <20 | 087-1N-20-a, b, c | 3000 | 087-1N-20-a1 | 10/28/2015 | -- | <.5 | * | | |
| | | | | 087-1N-20-a2 | 10/28/2015 | -- | 2.1 | * | | |
| | | | | 087-1N-20-a3 | 10/28/2015 | -- | <.48 | * | | |
| | | | | 087-1N-20-a4 | 10/28/2015 | -- | 5.4 | * | | |
| | | | | 087-1N-20-b1 | 10/28/2015 | -- | 1.0 | * | | |
| | | | | 087-1N-20-b2 | 10/28/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-b3 | 10/28/2015 | -- | 0.65 | * | | |
| | | | | 087-1N-20-b4 | 10/28/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-c1 | 10/28/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-c2 | 10/28/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-c3 | 10/28/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-c4 | 10/28/2015 | -- | <.51 | * | | |
| 1 N (2 foot cut material) | <20 | 087-1N-20-d1:n4 | 11,160 | 087-1N-20-d1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-d2 | 11/17/2015 | -- | 9.5 | * | | |
| | | | | 087-1N-20-d3 | 11/17/2015 | -- | 19.9 | * | | |
| | | | | 087-1N-20-d4 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-e1 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-e2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-e3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-e4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-f1 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-f2 | 11/17/2015 | -- | <.93 | * | | |
| | | | | 087-1N-20-f3 | 11/17/2015 | -- | <.90 | * | | |
| | | | | 087-1N-20-f4 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-g1 | 11/17/2015 | -- | <.95 | * | | |
| | | | | 087-1N-20-g2 | 11/17/2015 | -- | <.86 | * | | |
| | | | | 087-1N-20-g3 | 11/17/2015 | -- | <.96 | * | | |
| | | | | 087-1N-20-g4 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-h1 | 11/17/2015 | -- | 1.9 | * | | |
| | | | | 087-1N-20-h2 | 11/17/2015 | -- | <.92 | * | | |
| | | | | 087-1N-20-h3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-h4 | 11/17/2015 | -- | <.92 | * | | |
| | | | | 087-1N-20-i1 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-i2 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-i3 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-i4 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-j1 | 11/17/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-j2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-j3 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-j4 | 11/17/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-k1 | 11/17/2015 | -- | <1.6 | * | | |

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| 1 N (2 foot cut material) | <20 | 087-1N-20-d1:n4 | 11,160 | 087-1N-20-k2 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-k3 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-k4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-l1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-l2 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-l3 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-l4 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-m1 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-m2 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-m3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-m4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n3 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-n4 | 11/17/2015 | -- | <1.5 | * | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

N4 POOL N4 ELEV.+6.5 525'
N3 POOL N3 ELEV.+7.5 343'
N2 POOL N2 ELEV.+8.0 237'
N1 POOL N1 ELEV.+10.0 660'
E1 POOL E1 ELEV.+8.0 325'
E2 POOL E2 ELEV.+8 270'
S4 POOL S4 ELEV.+6.0 419'
S3 POOL S3 ELEV.+7.0 640'
S2 POOL S2 ELEV.+7.5 622'
S1 POOL S1 ELEV.+8 338'

087-MW-Y20
087-MW-S19
087-MW-O19
087-MW-O01
088-MW-G19
090-MW-E1
117-MW-A99
117-MW-A85
117-MW-A89
115-PZ-6
115-PZ-5
115-PZ-4
073-MW-BB11
073-MW-Y10
134-MW-V09
134-MW-Q08
140-MW-06
140-MW-07
125-MW-L03
MW-124-103L
MW-124-102D
MW-124-103D
MW-124-102T

NORTH-FS-1
NORTH-FS-2
NORTH-FS-3
NORTH-FS-4
NORTH-FS-5
NORTH-FS-6
NORTH-FS-7
NORTH-FS-8
NORTH-FS-9
NORTH-FS-13
SOUTH-FS-1
SOUTH-FS-3
SOUTH-FS-4
SOUTH-FS-5
SOUTH FS-7
SOUTH-FS-6

W6-SO W1-SO W5-SO W3-SO E5-SO E4-SO E3-SO E2-SO E1-SO

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

STA. N11+10 STA. N6+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. E3+75 STA. E4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+58 STA. S3+85 STA. S0+50

KELLOGG STREET

ROUTE 3 WEST STATE HIGHWAY

**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 12/1/2014 | | 4.7 | 5.5 | 6.6 | 6.5 | | 5.3 | 6.6 | 5.2 | 4.9 | 6.9 | 6.9 | 6.0 | 5.9 | 6.2 | | 6.4 | 6.5 | 6.0 | 7.9 | | 6.5 |
| 12/15/2014 | | 5.0 | 5.8 | 7.5 | 6.9 | | 6.8 | 6.7 | 5.5 | 5.2 | 7.3 | 6.9 | 6.4 | 6.2 | 6.7 | | 7.7 | 7.6 | 2.4 | 7.4 | | 6.7 |
| 12/30/2014 | | 5.0 | 5.6 | 7.1 | 6.5 | | 8.6 | 7.3 | 5.4 | 5.0 | 7.2 | 6.7 | 6.0 | 5.8 | 6.3 | | 6.7 | 6.4 | 2.4 | 7.2 | 6.1 | 5.3 |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | 5.6 | 6.6 | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: SAP-9
Date Exposed: 11/16/15
Describe Damage:

Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: SAP-10
Date Exposed: 11/16/15
Describe Damage:

Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: SAP-11
Date Exposed: 11/16/15
Describe Damage:

Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: SAP-12
Date Exposed: 11/16/15
Describe Damage:

Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: SAP-13

Date Exposed: 11/16/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/19/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-1

Date Exposed: 11/16/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-2

Date Exposed: 11/16/15

Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-3

Date Exposed: 11/16/15

Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-4
Date Exposed: 11/16/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-5
Date Exposed: 11/16/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-6
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-7
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-8
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-9
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-10
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-11
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-12
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamingad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-13
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the Sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamingad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-14
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamingad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-15
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamingad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-16
Date Exposed: 11/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/19/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/19/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-17
Date Exposed: 11/19/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/24/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-18
Date Exposed: 11/19/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/24/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-19
Date Exposed: 11/19/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/24/15
Inspected by: A. Eslamineyad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-20

Date Exposed: 11/19/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 11/24/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-21

Date Exposed: 11/19/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/24/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-22

Date Exposed: 11/19/15

Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/24/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-23

Date Exposed: 11/19/15

Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 11/24/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat


Repair Log Closure: AMEC Signature: _____

Date: 11/24/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

# Attachment 11: Capping Update

- SA-6 South Cap Subgrade Progress Map
- Repair Log
- QA Photo Log
- Daily QA Reports




LEGEND

- GDL COVER SOIL PLACED
- GDL COVER SOIL GRADED AND APPROVED FOR HORIZON SOILS
- HORIZON C SOIL PLACED
- HORIZON C PLACED TO FINAL HORIZON C GRADE
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
12/03/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-1 | CF | 2/3 | | 98'N OF SEOS ( VALLEY DESIGN) | P | 2.5 | x | 63 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-2 | WR | 3/4 | | 94'N OF SEOS | P | 2 | x | 12 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-3 | SI | | 3 | 60'N OF 2/3 & 11'E | P | 2 | x | 2.5 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-4 | DS-1 | 3/4 | | 18'N OF SEOS | P | 2 | X | 28 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-5 | CF | | 3 | 140'N OF 2/3 & 6'E | P | 2 | x | 10 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-6 | PB | 1/2 | | 135'N OF SEOS (PB 8") | P | 5 | x | 5 | 52.5 | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-7 | PB | | 1 | 85'N OF 1/2 & 17'W (PB 4") | P | 3 | x | 4 | 36.58 | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-8 | SI | | 2 | 86'N OF 2/3 & 2'W | P | 1.5 | x | 2 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-9 | RW | 4/5 | | SEOS | P | 1.5 | x | 3 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-10 | SJ | 5/6/7 | | SJ 5/6/7 | P | 1.5 | X | 2 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-11 | RW | 5/7 | | SEOS | P | 2 | x | 4 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-12 | DS-2 | 6/7 | | 10'E OF WEOS | P | 2 | x | 5.5 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-13 | FS | 7/8 | | E.S. & COVER OVER SJ 6/7/8 | P | 2 | x | 6 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-14 | PB | | 8 | 147'N OF 6/8 & 4'E ( PB 8") | P | 5 | x | 5 | 52.5 | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-15 | BO | 9/10 | | 52'N OF SEOS | P | 2 | x | 3 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-16 | DS-3 | 11/12 | | 100'N OF SEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-17 | CF | 13/14 | | 46'S OF NEOS (VALLEY DESIGN) | P | 2 | x | 42 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-18 | DSX-1 | | 13 | ON RP-17 | P | 2 | X | 6 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-19 | DS-4 | 14/15 | | 16'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-20 | CF | 14/15 | 15 | 57'S OF NEOS | P | 2 | x | 20 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-21 | CF | 15/16 | | 37'S OF NEOS | P | 2 | x | 16 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-22 | BO | 16/17 | | 23'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | | 7/30/15 |
| RP-23 | DS-5 | 17/18 | | 75'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-24 | PB | 16 | | 80'S OF 16/17 & 13'W (MH 48") | P | 10 | x | 10 | 174.7 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-25 | CF | 15/16 | | 78'S OF NEOS | P | 2 | x | 15 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-26 | CF | | 16 | 100'S OF 16/17 & 15'W | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-27 | BO | 16/17 | | 80'S OF NEOS (PATCH)& 7'W (EXT) | P | 2 | x | 2 | 84 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-28 | BO | 16/17 | | 115'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-29 | BO | 16/17 | | 130'S OF NEOS | P | 2 | x | 8 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-30 | SI | | 17 | 110'S OF 17/18 & 4'W | P | 2 | x | 2 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-31 | BO | 17/18 | | 101'S OF NEOS | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-32 | AO | | 15 | SEOP (TRIANGLE ) | B | | x | | 324 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-33 | CF | | 16 | 134'S OF 16/17 & 6'W | P | 2 | x | 13 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-34 | DSX-2 | RP-32/15 | 15 | 10'E OF RP-32 | P | 2 | x | 4.5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-35 | WR | | 17 | 94'S OF 16/17 & 3'W | P | 2 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-36 | WR | | 17 | 88'S OF 16/17 & 3'W | P | 1.5 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-37 | WR | | 17 | 88'S OF 16/17 & 15'W | P | 2 | x | 6 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-38 | WR | | 17 | 101'S OF 16/17 & 10'W | P | 2 | x | 8 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-39 | DS-6 | 20/21 | | 155'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-40 | BO | 20/21 | | 128'S OF NEOS | P | 2 | x | 7 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-41 | WR | | 18 | 75'S OF 18/19 & 11'W | P | 2 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-42 | CR | 17/18 | | 60'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-64 | WR | | 21 | BETWEEN RP-63 & RP-65 | B | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-65 | WR | | 21 | 20'S OF 21/22 & 18'W | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-66 | WR | | 22 | 20'S OF 22/23 & 5'W | P | 1.5 | x | 12 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-67 | BO | 21/22 | | 84'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-68 | BO | 22/23 | | 76'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-69 | WR | | 22 | 130'S OF 21/22 & 6'E | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-70 | WR | | 22 | BETWEEN RP-69 & RP-71 | B | | x | | 60 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-71 | CR | 21/22 | | 137'S OF NEOS | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-72 | WR | | 21 | BETWEEN RP-71 & RP-73 | B | | x | | 24 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-73 | WR | | 21 | 130'S OF 21/22 & 4'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-74 | WR | | 21 | BETWEEN RP-73 & RP-75 | B | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-75 | WR | | 21 | 129'S OF 21/22 & 9'W | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-76 | BO | 22/23 | | 97'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-77 | WR | | 23 | 118'S OF 22/23 & 7'E | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-78 | WR | | 23 | BETWEEN RP-77 & RP-79 | B | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-79 | WR | | 23 | 124'S OF 22/23 & 7'E | P | 2 | x | 11 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-80 | WR | | 23 | BETWEEN RP-79 & RP-81 | B | | x | | 84 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-81 | WR | | 23 | 134'S 22/23 & 9'E | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-82 | DS-7 | 23/24 | | 87'S OF NEOS | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-83 | DSX-3 | RP-82/23 | | ON RP-82/83( 87'S OF NEOS) | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-84 | CR | 23/24 | | 116'S OF NEOS | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-85 | CF | | 23 | 125'S OF 23/24 & 3'W | P | 2 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-86 | CF | | 23 | BETWEEN RP-85 & RP-87 | B | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-87 | CF | | 23 | 140'S OF 23/24 & 10'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-88 | BO | 24/25 | | 127'S OF NEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-89 | WR | | 24 | BETWEEN RP-88 & RP-90 | B | | x | | 60 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-90 | WR | | 24 | 127'S OF 24/25 & 5'W | P | 2 | x | 2.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-91 | CF | | 25 | 100'N OF 25/26 & 6'W | P | 2 | x | 6 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-92 | CF | | 25 | BETWEEN RP-91 & RP-93 | B | | X | | 120 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-93 | CF | | 25 | 121'N OF 25/26 & 12'W ( T-SHAPE) | P | 2 | x | 22 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-94 | CF | | 25 | BETWEEN RP-93 & RP-95 | B | | x | | 84 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-95 | CF | 25/26 | | 110'N TO 129'N OF SEOS | P | 2 | x | 19 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-96 | DS-8 | 26/27 | | 128'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-97 | BO | 26/27 | | 71'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-98 | CF | | 27 | BETWEEN RP-97 & RP-100 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-99 | CR | 26/27 | | 38'N OF SEOS | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-100 | CF | | 27 | 55'N OF 26/27 & 13'E | P | 2 | x | 30 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-101 | CF | | 27 | BETWEEN RP-100 & RP-102 | B | | x | | 144 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-102 | CF | | 27 | 87'N OF 26/27 & 7'E | P | 2 | x | 6.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-103 | CF | 27/28 | | 117'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-104 | CF | | 28 | BETWEEN RP-103 & RP-105 | B | | x | | 156 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-105 | BO | 28/29 | | 120'N OF SEOS | P | 2 | x | 15 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-106 | CF | | 28 | BETWEEN RP-105 & RP-107 | B | | x | | 192 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-107 | CF | | 28 | 134'N OF 27/28 & 4'E | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-108 | BO | 29/30 | | 125'N OF SEOS | P | 2 | x | 10 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-109 | DS-9 | 29/30 | | 80'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-110 | CF | | 28 | 85'N OF 28/29 & 3'W | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-111 | CF | | 28 | BETWEEN RP-110 & RP-112 | B | | x | | 180 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-112 | WR | 28/29 | | 68'N OF SEOS | P | 2 | x | 8 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-113 | WR | | 28 | BETWEEN RP-112 & RP-114 | B | | x | | 36 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-114 | WS | 28/29 | | 73'N OF SEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-115 | BO | 28/29 | | 61'N OF SEOS | P | 1.5 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-116 | WR | | 28 | 29'N OF 27/28 & 1'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-117 | WR | | 28 | BETWEEN RP-116 & RP-118 | B | | x | | 72 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-118 | WR | | 28 | 29'N OF 27/28 &9'E | P | 2 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-119 | WR | | 28 | BETWEEN RP-118 & RP-120 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-120 | WR | | 28 | 29'N OF 27/28 & 13'E | P | 1 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-121 | BO | 27/28 | | 34'N OF SEOS | P | 2 | x | 7 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-122 | CF | | 27 | BETWEEN RP-121 & RP-123 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-123 | CF | | 27 | 34'N OF 27/28 & 5'W | P | 1.5 | x | 1.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-124 | CF | | 28 | 34'N OF 27/28 & 10'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-125 | CF | | 28 | BETWEEN RP-124 & RP-126 | B | | x | | 108 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-126 | CF | | 28 | 45'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-127 | CF | | 28 | BETWEEN RP-126 & RP-128 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-128 | CF | | 28 | 48'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-129 | PB | | 11 | 80'N OF 10/11 & 8'E (PB 8") | P | 3 | x | 3 | 52.5 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-130 | DS-10 | 32/33 | | 20'N OF SEOS | P | 2 | x | 5.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-131 | DSX-4 | RP-102/27 | | ON EASTSIDE OF RP-102/27 | P | 2 | x | 5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-132 | PB | | 32 | 13'N OF 31/32 & 1'E (PB 4") | P | 3 | x | 4 | 36.6 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-133 | WR | 33/34 | | SEOS TO 21'N | P | 2.5 | x | 21 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-134 | WR | | 34 | BETWEEN RP-133 & RP-135(N.SIDE) | B | | x | | 84 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-135 | WR | | 34 | 18'N OF 33/34 & 11'E | P | 3 | x | 10 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-136 | WR | | 34 | FROM RP-135 TO SEOP | B | | x | | 180 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-137 | WR | | 34 | BETWEEN RP-133 & RP-135(S.SIDE) | B | | x | | 120 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-138 | WR | | 34 | BETWEEN RP-137 & RP-139 | B | | x | | 36 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-139 | WR | | 34 | 13'N OF 33/34 & 6'E | P | 1.5 | x | 1.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-140 | WR | | 34 | BETWEEN RP-135 & RP-141 | B | | x | | 168 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-141 | WR | | 34 | 36'N OF 33/34 & 10'E | P | 1 | x | 2 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-142 | CF | | 30 | 112'N OF 29/30 & 5'E | P | 2 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-143 | CF | | 30 | BETWEEN RP-142 & RP-144 | B | | x | | 48 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-144 | CF | | 30 | 98'N OF 29/30 & 7'E | P | 1.5 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-145 | DS-11 | 36/37 | | 90'W OF EEOS & SJ 34/36/37 | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-146 | SJ | 41/44/45 | | SJ 41/44/45 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-147 | SJ | 44/45/46 | | SJ 44/45/46 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-148 | SJ | 40/41/44 | | SJ 40/41/44 | P | 2 | x | 5.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-149 | SJ | 34/40/41 | | SJ 34/40/41 | P | 3 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-150 | SJ | 34/39/40 | | SJ 34/39/40 | P | 1.5 | x | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-151 | SJ | 34/38/39 | | SJ 34/38/39 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-152 | SJ | 34/37/38 | | SJ 34/37/38 | P | 2 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-153 | BO | 35/36 | | 84'W OF EEOS | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-154 | WR | | 36 | BETWEEN RP-153 & RP-155 | B | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-155 | WR | | 36 | 84'W OF 35/36 & 5'S | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-156 | SJ | 34/35/36 | | SJ 34/35/36 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-157 | BO | 34/35 | | 10'S OF NEOS | P | 1.5 | X | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-158 | WR | | 35 | 65'W OF 35/36 & 11'N | P | 1.5 | X | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-159 | WR | | 35 | FROM RP-158 TO N.END OF P-35 | P | | x | | 144 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-160 | DS-12 | 42/43 | | 20'N OF SEOS | P | 2 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-161 | SJ | 43/44/46 | | SJ 43/44/46 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-162 | WR | 44/46 | | 5'W OF EEOS | P | 1.5 | X | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-163 | WR | | 44 | BETWEEN RP-162 & RP-164 | B | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-164 | WR | | 44 | 5'W OF 44/46 & 5'N | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-165 | WR | | 44 | BETWEEN RP-162 RP-166 | B | | x | | 216 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-166 | WR | 40/44 | | 16'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-167 | SJ | 40/42/43 | | SJ 40/42/43 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-168 | SJ | 39/40/42 | | SJ 39/40/42 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-190 | WR | | 35 | BETWEEN RP-189 & RP-191 | B | | x | | 84 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-191 | WR | | 35 | 15'W OF 35/36 & 6'N | P | 1.5 | x | 1.5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-192 | WR | | 36 | 10'W OF 36/37 & 7'N | P | 1.5 | x | 2 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-193 | WR | | 36 | BETWEEN RP-192 & RP-194 | B | | x | | 180 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-194 | WR | | 36 | 10'W OF 36/37 & 24'N | P | 2 | x | 4 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-195 | BO | 47/48 | | 106'S OF NEOS | P | 2 | x | 6.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-196 | BO | 48/49 | | 86'S OF NEOS | P | 2 | x | 4 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-197 | BO | 53/54 | | 15'S OF NEOS | P | 2 | x | 7 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-198 | WR | 48/49 | | 94'S OF NEOS | P | 2 | x | 28 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-199 | CR | 42/47 | | 50'S OF NEOS | P | 2 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-200 | CF | | 47 | 56'S OF NEOS(SURFACE DESIGN) | P | 2 | x | 38 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-201 | CF | | 47 | 38'S OF 42/47 & 8'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-202 | CF | | 47 | BETWEEN RP-201 & RP-203 | B | | x | | 240 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-203 | CF | | 47 | 59'S OF 42/47 & 18'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-204 | DS-13 | 47/48 | | 70'S OF NEOS | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-205 | CF | | 47 | FROM RP-200 TO MANHOLE | B | | x | | 216 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-206 | WR | | 48 | 46'S OF 47/48 & 4'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-207 | WR | | 48 | BETWEEN RP-206 & RP-208 | B | | x | | 180 | 8/7/15 | PEDRO S. | EXT 512 | VNOX | P | 8/7/15 |
| RP-208 | WR | | 48 | 64'S OF 48/49 & 6'W | P | 2 | x | 11 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-209 | WR | | 48 | BETWEEN RP-208 & RP-210 | B | | x | | 36 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-210 | WR | | 48 | 57'S OF 48/49 & 4'W | P | 2.5 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-211 | DSX-6 | RP-198/48 | | ON W.END OF RP-198/48 | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-212 | WR | 49/50 | | 72'S OF NEOS | P | 2 | x | 9 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-213 | WR | | 50 | 75'S OF 49/50 & 8'E | P | 2 | x | 7 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-214 | WR | | 50 | BETWEEN RP-213 & RP-215 | B | | x | | 24 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-215 | WR | | 50 | 78'S OF 49/50 & 2'E | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | F | 8/10/15 |
| RP-216 | SJ | 50/51/52 | | SJ 50/51/52 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-217 | SJ | 51/52/53 | | SJ 51/52/53 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-218 | PB | | 47 | 87'S OF 42/47 & 11'E(MH 48" ) | P | 9.5 | x | 9.5 | 175 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-219 | PB | | 38 | 3'W OF 37/38 & 3'S (PB 8") | P | 3.5 | x | 4 | 52.5 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-220 | BO | 55/57 | | 101'N OF SEOS | P | 2 | x | 2.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-221 | BO | 55/57 | | 120'N OF SEOS | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-222 | WR | | 50 | REPAIR LEAK OVER RP-215 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-223 | DS-14 | 50/51 | | 35'S OF NEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-224 | WR | 51/53 | | 20'S OF NEOS | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-225 | WR | | 53 | BETWEEN RP-224 & RP-226 | B | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-226 | WR | | 53 | 20'S OF 51/53 & 14'E | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-227 | WR | | 53 | 30'S OF 53/54 & 5'W | P | 1.5 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-228 | WR | | 53 | BETWEEN RP-227 & RP-229 | B | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-229 | WR | | 53 | 35'S OF 51/53 & 5'W | P | 2 | x | 11 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-230 | DS-15 | 54/55 | | 72'S OF NEOS | P | 2 | x | 4.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-231 | SJ | 54/55/56 | | SJ 54/55/56 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-232 | SJ | 55/56/57 | | SJ 55/56/57 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-233 | CF | | 55 | 76'N OF 55/57 & 3'W | P | 2 | X | 13 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-234 | CF | | 55 | BETWEEN RP-233 & RP-235 | B | | x | | 24 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-235 | CF | | 55 | 80'N OF 55/57 & 2'W | P | 2 | x | 3.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-236 | CF | | 58 | 128'S OF 57/58 7'E | P | 3 | x | 4 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-237 | CF | | 58 | BETWEEN RP-236 & RP-238 | B | | x | | 168 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-238 | CF | | 58 | 140'S OF 57/58 & 20'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-239 | CF | | 58 | BETWEEN RP-236 & RP-240 | B | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-240 | CF | | 58 | 125'S OF 57/58 & 17'E | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-241 | CF | | 58 | BETWEEN RP-239 & RP-242 | B | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-242 | CF | | 58 | 128'S OF 57/58 & 15'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-243 | PB | | 58 | 75'S OF 57/58 & 6'E (PB 8") | p | 4 | x | 4 | 52.5 | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-244 | SJ | 58/59/60 | | SJ 58/59/60 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-245 | DSX-7 | RP-197/53 | | ON RP-197/53 | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-246 | PB | | 62 | 135'N OF 61/62 & 2'E (PB 8") | P | 3 | x | 4 | 52.5 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-247 | SJ | 59/60/61 | | SJ 59/60/61 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-248 | DS-16 | 59/61 | | 6'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-249 | DS-17 | 62/63 | | 90'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-250 | CR | | 65 | 2'N OF 65/66 & 5'E | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-251 | SJ | 64/65/66 | | SJ 64/65/66 | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-252 | BO | 65/66 | | 8'N OF SEOS | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-253 | DS-18 | 64/65 | | 128'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-254 | DS-19 | 68/69 | | 100'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-255 | PB | | 71 | 9'N OF 71/72 & 5'W (PB 4") | P | 5 | x | 6 | 36.6 | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-256 | DS-20 | 72/73 | | 10'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-257 | PB | | 74 | 92'N OF 73/74 & 1'E (PB 8") | P | 3.5 | x | 4 | 52.5 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/14/15 |
| RP-258 | BO | 71/72 | | 57'N OF SEOS | P | 2 | x | 2 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-259 | BO | 71/72 | | 133'N OF SEOS | P | 2 | x | 2.5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-260 | BO | 74/75 | | 60'N OF SEOS | P | 2 | x | 6 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-261 | DS-21 | 74/75 | | 75'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-262 | PB | 78/79 | | WEOS (MH 48") | P | 10 | x | 11 | 175 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-263 | CF | | 73 | FROM RP-264 TO 4'N | B | | x | | 48 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-264 | CF | | 73 | 23'N OF 72/73 & 5'E | P | 2.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-265 | CF | | 73 | BETWEEN RP-264 & RP-266 | B | | x | | 84 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-266 | CF | | 73 | 14'N OF 72/73 & 7'E | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-267 | CF | | 73 | BETWEEN RP-266 & RP-272 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-268 | CF | | 73 | FROM RP-269 TO 3'W | B | | x | | 36 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-269 | CF | | 73 | 14'N OF 72/73 &18'E | P | 2 | x | 9 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-270 | CF | | 73 | BETWEEN RP-269 & RP-271 | B | | x | | 108 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-271 | CF | | 73 | 4'N OF 72/73 & 9'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-272 | CF | | 73 | 15'N OF 72/73 & 15'E | P | 2 | x | 10 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-273 | CF | | 73 | BETWEEN RP-272 & RP-274 | B | | x | | 36 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-274 | CF | | 73 | 23'N OF 72/73 & 15'E | P | 2 | x | 6 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-275 | CF | | 73 | FROM RP-274 TO 5'N | B | | x | | 60 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-276 | CF | | 73 | FROM RP-277 TO 12'E | B | | x | | 144 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-277 | CF | | 73 | 50'N OF 72/73 & 5'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-278 | CF | | 73 | 46'N OF 73/74 & 5'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-279 | CF | | 73 | BETWEEN RP-278 & RP-280 | B | | x | | 156 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-280 | CF | | 73 | 59'N OF 73/74 & 16'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-281 | CF | | 71 | 137'N OF 71/72 & 2'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-282 | CF | | 71 | BETWEEN RP-281 & RP-283 | B | | x | | 120 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-283 | CF | | 71 | 125'N OF 71/72 & 8'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-284 | CF | | 71 | 164'N OF 71/72 & 8'W | P | 2 | x | 4 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-285 | CF | | 71 | BETWEEN RP-284 & RP-286 | B | | x | | 132 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-286 | CF | | 71 | 142'N OF 71/72 & 3'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-287 | CF | | 71 | FROM RP-288 TO 8'N | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-288 | CF | | 71 | 137'N OF 71/72 & 9.5' W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-289 | DSX-8 | RP-284/71 | | ON RP-284/71 | P | 2 | x | 5 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-290 | WR | 68/69 | | 132'N OF SEOS | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-291 | WR | | 68 | BETWEEN RP-290 & RP-292 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-292 | WR | | 68 | 126'N OF 68/69 & 10'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-293 | SI | | 57 | 136'N OF 56/57 & 7'E | P | 2 | x | 2 | | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-294 | SJ | | | SJ 75/80/81 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-295 | SJ | | | SJ 75/79/80 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-296 | SJ | | | SJ 75/77/78 | P | 2 | x | 3 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-297 | SJ | | | SJ 75/76/77 | P | 1 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-298 | DS-22 | 79/80 | | 78'E OF WEOS | P | 2 | x | 4 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-299 | SJ | | | SJ 75/81/82 | P | 2.5 | x | 14 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-300 | SJ | | | SJ 81/82/83 | P | 1.5 | x | 1.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-301 | SJ | | | SJ 81/83/84 | P | 1 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-302 | SJ | | | SJ 83/84/85 | P | 2 | x | 4 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-303 | SJ | | | SJ 84/85/86 | P | 1 | x | 1 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-304 | WR | 84/85 | | 7'W OF EEOS | P | 1.5 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-305 | WR | | 84 | BETWEEN RP-304 & RP-306 | B | | x | | 204 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-306 | WR | | 84 | 7'W OF 84/85 & 17'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-307 | WR | | 84 | FROM RP-308 TO 12'SW | B | | x | | 144 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-308 | WR | | 84 | 20'E OF 81/84 & 13'S | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-309 | WR | 75/82 | | 14'N OF SEOS | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-310 | WR | | 82 | BETWEEN RP-309 & RP-311 | B | | x | | 240 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-311 | WR | 82/83 | | 15'N OF SEOS | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-312 | WR | | 82 | 6'N OF 82/83 & 6.5' W | P | 1.5 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-313 | WR | | 82 | BETWEEN RP-312 & RP-314 | B | | x | | 132 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-314 | WR | | 82 | 19'N OF 82/83 & 6'W | P | 1.5 | x | 1.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-315 | BO | 81/84 | | 24'E OF WEOS | | | x | | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-316 | DS-23 | 88/89 | | 116'N OF SEOS | p | 2 | x | 4.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-317 | WR | | 79 | BETWEEN RP-298 & RP-318 | B | | x | | 66 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-318 | WR | | 79 | 78'E OF 79/80 & 7'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-319 | BO | 81/87 | | 8'N OF SEOS | P | 2 | x | 5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-320 | SJ | | | SJ 80/81/87 | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-321 | SJ | | | SJ 79/80/87 | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-322 | WR | 79/87 | | 6'N OF SEOS | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-323 | SJ | | | SJ 78/79/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-324 | SJ | | | SJ 77/78/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-325 | SJ | | | SJ 76/77/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-326 | CF | 89/90 | | 145'N OF SEOS | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-327 | CF | | 89 | 145'N OF 89/90 & 6'W | B | | x | | 72 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-328 | CF | 89/90 | | 81'N OF NEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-329 | CF | | 89 | 81'N OF 89/90 & 5'W | B | | x | | 60 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-330 | DSX-9 | RP-316/88 | | RP-316/88 | P | 2 | x | 4.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-331 | SI | | 83 | 9'S OF 83/84 & 8'W (END OF PANEL) | P | 2 | x | 18 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-332 | SJ | | | SJ 84/86/87 | P | 3 | x | 12 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-333 | CR | | 84/86 | EEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-334 | WR | | 84 | BETWEEN RP-315 & RP-335 | B | | x | | 12 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-335 | WR | | 84 | 7'W OF 81/84 & 3.5'S | P | 3 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-336 | SJ | | | SJ 81/84/87 | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-337 | CF | 84/87 | | BETWEEN RP-332 & RP-336 | B | | x | | 216 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-338 | WR | 81/84 | | 24'E TO EEOS | B | | x | | 36 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-339 | WR | | 81 | 11'N OF 81/87 & 4'W | P | 1.5 | x | 1.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-340 | WR | | 81 | BETWEEN RP-339 & RP-341 | B | | x | | 138 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-341 | WR | | 81 | 13'W OF 81/84 & 3'N | P | 2 | x | 3.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-342 | AO | | 76 | ADD ON NORTH SIDE OF P-76 | P | 8 | x | 16 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-343 | CF | 76/77 | | 66'E OF WEOS | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-344 | CF | | 77 | BETWEEN RP-343 & RP-345 | B | | x | | 36 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-345 | CF | | 77 | 66'E OF 76/77 & 5'S | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-346 | CF | | 77 | BETWEEN RP-345 & RP-347 | B | | x | | 48 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-347 | CF | | 77 | 66'E OF 76/77 & 10'S | P | 1.5 | x | 1.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-348 | WR | | 85 | 4'W OF 84/85 & 4'S | B | | x | | 48 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-349 | WR | | 84 | 4'W OF 84/85 & 8'N | B | | x | | 96 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-350 | DS-24 | 91/92 | | 45'N OF SEOS | P | 2 | x | 5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-351 | CF | 91/92 | | 151'N OF SEOS | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-352 | CF | | 91 | BETWEEN RP-351 & RP-353 | B | | x | | 216 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-353 | CF | | 91 | 151'N OF 91/92 & 19.5'W | P | 3 | x | 3 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-354 | CF | 93/94 | | 144'N OF SEOS | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-355 | CF | | 94 | BETWEEN RP-354 & RP-356 | B | | x | | 72 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-356 | CF | | 94 | 144'N OF 93/94 & 10'E | P | 2 | x | 4.5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-357 | CF | | 90 | 29'N OF 90/91 & 4'W | P | 2 | x | 3 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-358 | CF | | 90 | BETWEEN RP-357 & RP-359 | B | | x | | 60 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-359 | CF | | 90 | 31'N OF 90/91 & 9'W | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-360 | CF | | 90 | BETWEEN RP-359 & RP-361 | B | | x | | 24 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-361 | CF | | 90 | 31'N OF 90/91 & 13'W | P | 2 | x | 2.5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-362 | WR | | 80 | 11'S OF 80/87 & 5'W | P | 1 | x | 2 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-363 | WR | | 80 | BETWEEN RP-362 & RP-365 | B | | x | | 54 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-364 | WR | 79/80 | | 8.5'W OF EEOS | P | 2 | x | 2 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-365 | WR | | 8O | 5'S OF 80/87 & 10'W | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-366 | WR | | 80 | BETWEEN RP-364 & RP-365 | B | | x | | 60 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-367 | DS-25 | 94/95 | | 100'N OF SEOS | P | 2 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-368 | CF | 94/95 | | 125'N OF SEOS | P | 2 | x | 6 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-369 | PB | | 95 | 95'N OF 94/95 & 6'E (PB 8") | P | 4 | x | 4.5 | 52.5 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-370 | CF | 94/95 | | 33'N OF SEOS | P | 2.5 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-371 | CF | | 95 | BETWEEN RP-370 & RP-372 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-372 | CF | | 95 | 33'N OF 94/95 & 6.5'E | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-373 | BO | 95/96 | | 128'S OF NEOS | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-374 | DS-26 | 96/97 | | 33'S OF NEOS | P | 2 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-375 | CF | 96/97 | | 95'S OF NEOS | P | 2 | x | 8 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-376 | CF | 96/97 | | FROM RP-377 TO 117'S | P | 2 | x | 14 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-377 | CF | | 96 | 101'S OF 96/97 TO 15'W | P | 4 | x | 15 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-378 | CF | | 96 | 105'S OF OF 96/97 & 13'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-379 | CF | | 96 | 101'S OF 96/97 & 17'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-380 | CF | | 96 | 93'S OF 96/97 & 8'W | P | 2.5 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-381 | CF | | 96 | BETWEEN RP-380 & RP-382 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-382 | CF | | 96 | 86.5'S OF 96/97 & 4'W | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-383 | BO | 103/104 | | 16'W OF EEOS | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-384 | BO | 97/103 | | 12'S OF NEOS | | | x | | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-385 | SI | | 94 | 126'N OF 94/95 & 8'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-386 | DSX-10 | RP-376/96 | | RP-376/96 (DSX-10 ) | P | 2 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-387 | SJ | | | SJ 97/103/104 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-388 | CF | | 97 | BETWEEN RP-384 & RP-389 | B | | x | | 24 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-389 | CF | | 97 | 12'S OF 97/103 & 3.5'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-390 | SJ | | | SJ 97/102/103 | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-391 | SJ | | | SJ 97/101/102 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-392 | SJ | | | SJ 97/100/101 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-393 | SJ | | | SJ 97/99/100 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-394 | SJ | | | SJ 97/98/99 | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-395 | CF | | 103 | FROM RP-383 TO 5'N | B | | x | | 60 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-396 | CF | | 103 | 4'N FROM RP-397 & 14'NW | B | | x | | 168 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-397 | SJ | | | SJ 103/104/105 | P | 2 | x | 3.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-398 | SJ | | | SJ 103/105/106 | P | 3 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-399 | CF | | 107 | 122'S OF 107/108 & 4'W | B | | x | | 192 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-400 | SJ | | | SJ 103/106/107 | P | 2 | x | 2.5 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-401 | SJ | | | SJ 102/103/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-402 | SJ | | | SJ 101/102/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-403 | SJ | | | SJ 100/101/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-404 | SJ | | | SJ 99/100/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-405 | SJ | | | SJ 98/99/107 | P | 1.5 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-406 | CF | | 98 | FROM RP-412 TO N.E. CORNER | B | | x | | 144 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-407 | CF | | 98 | FROM RP-412 TO N.W. CORNER | B | | x | | 168 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-408 | CF | | 107 | 13'S OF 107/108 & 4.5'W | P | 1.5 | x | 3 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-409 | CF | | 107 | BETWEEN RP-408 & RP-411 | B | | x | | 168 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-410 | CF | | 107 | 6'S OF 107/108 & 5'W | B | | x | | 60 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-411 | CF | | 107 | 5'S OF 98/107 & 4'E | P | 1.5 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-412 | CF | | 98 | BETWEEN RP-406 & RP-407 | P | 2 | x | 22 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-413 | CF | | 108 | 143'S OF 108/109 & 3'E | P | 1.5 | x | 1.5 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-414 | CF | | 108 | FROM RP-413 TO 17'S | B | | x | | 204 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-415 | CF | | 107 | FROM RP-416 TO 4'W | B | | x | | 48 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-416 | CF | | 107 | 154'S OF 107/108 & 6'W | P | 2 | x | 4 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-417 | CF | | 107 | FROM RP-416 TO 4'E | B | | x | | 48 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-418 | PB | | 109 | 152'S OF 108/109 & 2.5'E (PB 4") | P | 4 | x | 6 | 36.6 | 9/23/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/23/15 |
| RP-419 | PB | 111/112 | | 15'S OF NEOS (PB 8") | P | 3.5 | x | 4.5 | 52.5 | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-420 | PB | | 113 | 82'S OF 112/113 & 14' ( MH 48" ) | P | 9 | x | 11 | 175 | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-421 | BO | 113/114 | | 28'S OF NEOS | P | 2 | x | 4.5 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-422 | DS-27 | 110/111 | | 120'S OF NEOS | P | 2 | x | 5 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-423 | SI | | 111 | 15'S OF 111/112 & 6'E | P | 1.5 | x | 2 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-424 | DSX-11 | RP-421/114 | | RP-421/114 (DSX-11 ) | P | 2 | x | 6 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-425 | PB | 114/115 | | 68'S OF NEOS (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/8/15 |
| RP-426 | CF | 115/116 | | 28'S OF NEOS | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-427 | CF | 117/118 | | 121'S OF NEOS | P | 2 | x | 13 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-428 | WR | | 115 | 12'S OF 114/115 & 3'E | P | 2 | x | 3.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-429 | WR | | 115 | BETWEEN RP-428 & RP-430 | B | | x | | 120 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-430 | WR | | 115 | 12'S OF 114/115 &15.5'E | P | 2 | x | 3.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-431 | CF | | 115 | BETWEEN RP-426 & RP-432 | B | | x | | 48 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-432 | CF | | 115 | FROM RP-431 TO 15'NW | P | 2 | x | 15 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-433 | DO | | 117 | 123'S OF 117/118 & 6'E | P | 1.5 | x | 1.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-434 | CF | | 118 | BETWEEN RP-427 & RP-435 | B | | x | | 12 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-435 | CF | | 118 | FROM RP-436 TO 5'N | B | | x | | 60 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-436 | CF | | 118 | BETWEEN RP-434 & RP-435 | P | 2 | x | 14 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-437 | CF | 119/120 | | 94'S OF NEOS | P | 2 | x | 3 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-438 | CF | 119/120 | | 22'S OF NEOS | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-439 | CF | 119/120 | | 127'S OF NEOS | P | 2 | x | 9 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-440 | CF | 119/120 | | 139'S OF NEOS | P | 2.5 | x | 4 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-441 | CF | | 119 | FROM RP-437 TO 14'W | B | | x | | 168 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-442 | CF | | 119 | BETWEEN RP-440 & RP-443 | B | | x | | 192 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-443 | CF | | 119 | 149'S OF 119/120 & 17.5'W | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-444 | CF | 119/120 | | BETWEEN RP-439 & RP-440 | B | | x | | 144 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-445 | AO | RP-445 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-446 | AO | RP-446 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-447 | SJ | | | RP-445/RP-446/122 | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-448 | SJ | | | RP-446/121/122 | P | 2.5 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-449 | CF | | 122 | FROM RP-448 TO 10'E | B | | x | | 120 | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-450 | BO | 122/123 | | 23'N OF SEOS | P | 2.5 | x | 4 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-451 | SJ | | | P122/123/124 | P | 1.5 | x | 2 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-452 | SJ | | | P 123/124/125 | P | 1.5 | x | 1.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-453 | CF | | 125 | FROM RP-454 TO 11'S | P | 3.5 | x | 11 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-454 | CF | 123/125 | | 18'N OF SEOS | P | 3 | x | 9.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-455 | CF | | 125 | FROM RP-454 TO 10'N | P | 3.5 | x | 10 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-456 | DS-28 | 123/125 | | 90'N OF SEOS | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-457 | PB | | 125 | 68'S OF P125/126 & 4'W (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-458 | SI | | 125 | ON RP-453 & RP-455 | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-459 | SI | 120,121,122, | &123 | BETWEEN RP-454 TO RP-473 | P | 2 | x | 91 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-460 | DSX-12 | RP-459/123 | | N.SIDE OF RP-459 ( DSX-12 ) | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-461 | SI | | 122 | BETWEEN RP-450 & RP-459 | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-462 | SI | | 122 | FROM RP-461 TO 3'NW | B | | x | | 36 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-463 | SI | | 122 | FROM RP-459 TO 5'S | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-464 | SI | | | SJ 121/122/RP-459 | P | 2 | x | 4 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-465 | SI | | 121 | BETWEEN RP-459 & RP-468 | B | | x | | 6 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-466 | SI | 121/122 | | FROM RP-467 TO RP-465 & RP-468 | B | | x | | 108 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-467 | SI | | 121 | 9'SE OF RP-465 , RP-466 & RP-468 | P | 2 | x | 2.5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-468 | SI | | 121 | BETWEEN RP-465 & RP-469 | B | | x | | 42 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-469 | SI | | 121 | BETWEEN RP-468 & RP-470 | B | | x | | 132 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-470 | SI | | 121 | 11'SW OF RP-468 | P | 2 | x | 3 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-471 | SI | | 121 | BETWEEN RP-468 & RP-472 | B | | x | | 12 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-472 | SI | | 121 | FROM RP-471 TO SEOP | P | 2 | x | 23 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-473 | SI | 119/120 | | BETWEEN RP-439,RP-444& RP-440 | P | 2 | x | 17 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-474 | SI | 119/120 | | NEOS TO 16'S | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-475 | SI | | 117 | NEOP & 5'W OF 117/118 | P | 2 | x | 14 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-476 | PB | 128/132 | 132 | 81'N OF SEOS & 3'E (PB 4") | P | 3 | x | 6 | 36.6 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/9/15 |
| RP-477 | SI | 125/126 | 125 | 159'S OF NEOS & 13' W | P | 2 | x | 13 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-478 | SJ | | | P 127/128/129 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-479 | SJ | | | P 128/129/132 | P | 2 | x | 3 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-480 | DS-29 | 128/132 | | 25'N OF SEOS | P | 2 | x | 7 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-481 | SJ | | | P 128/131/132 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-482 | SJ | | | P 128/130/131 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-483 | DSX-13 | RP-477/125 | | N.SIDE OF RP-477 (DSX-13) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 4984.5 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-484 | DSX-14 | RP-480/132 | | E.SIDE OF RP-480 ( DSX-14) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-485 | SJ | | | P 132/133/143 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-486 | DSX-15 | RP-487/125 | | N.SIDE OF RP-487 (DSX-15) | P | 2 | x | 5 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-487 | FS | | 125 | DS-13 FAIL (CAP OVER RP-477/RP-483) | P | 5 | x | 15 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-488 | DO | | 123 | 6' S OF NEOS ON SCB WALL EDGE | P | 3 | x | 2.5 | | 11/4/15 | EDFY E. | EXT 512 | NA | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking north along northern end of SA-6 cap (SCB wall) at approximate Sta. 2+95

**Description:**

Minor puncture along SCB wall from excavator bucket. Tooth of bucket penetrated through GDL and into underlying geomembrane layer.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall

**Description:**

Area around puncture cleared to allow ESI to complete patch / repair work (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking south along SCB wall

**Description:**

ESI replacing GCL underneath puncture at SCB wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall (northern end of SA-6)

**Description:**

New geomembrane patch leistered over puncture



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
11/4/15

**Direction Taken:**

Looking east along SA-6 (at SCB wall)

**Description:**

ESI conducting extrusion welding over new patch / repair (RP-488).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall

**Description:**

Extrusion welding along patch completed (as per project specs). Vacuum box testing unable to be conducted based on the location of the patch (on edge of SCB wall). Weld visually inspected by Entact / Langan.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking east along SCB wall

**Description:**

GDL patched and repaired and covered with fabric (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 11/04/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 55 / 70° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0845 – 1215 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #39** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of patch / repair work associated with an equipment puncture that was observed along the northern end of SA-6 (at SCB wall) at approximate Sta. 2+95.
- Based on conversations with the project team, it is understood that during final grading of the area, the tooth of an excavator bucket punctured the GDL and underlying geomembrane cap. This error was attributed to malfunctioning GPS equipment, as the SCB wall (outside of the Cap) was not programmed into the GPS.
- Site activities commenced with ESI completing patch / repair work at the puncture location (along edge of SCB wall at approximate Sta. 2+95. A new piece of GCL was initially placed over the puncture area and a 2 ft. by 1.5 ft. geomembrane patch was then placed over the puncture, and sealed with an extrusion weld (as per project specs). Vacuum box testing could not be completed by ESI, as the patch / repair was located right on the edge of the SCB wall (refer to supporting photo log from 11/4/15). As such, the welds were visually observed by Langan and Entact / ESI to confirm uniformity.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 12 (Sheet #12) – Equipment puncture through geomembrane cap.
    - Geomembrane patch was placed over equipment puncture along SCB wall (at approximate Sta. 2+95) and extrusion welded (as per project specs). Prior to patch / repair work, a new piece of GCL was placed over the puncture. This repair was noted as an equipment puncture and was completed following the project specs and as further defined on *Sheet 12 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 11/04/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, 10/08/15, 10/09/15, and 10/12/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-15. Laboratory results in compliance with shear and peel requirements as outlined in project specifications with the exception of DSX-13 (details previously defined in *10/12/15 Daily Report*).

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Complete associated paperwork and begin construction certification report.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 11/04/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 7 photos outlining pertinent daily observations and descriptions for 11/04/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 11/4/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 11/4/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 11/4/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 11/4/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 11/4/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 11/4/15 |
| A10 – Repair Log | Page 24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 11/4/15 |
| A11 – Conformance COC | | N / A for 11/4/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 11/4/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 11/4/15 |
| A14 – Penetration & Edge Form | | N / A no penetration and edge forms completed for 11/4/15 |
| A16 – Notice of Non-Compliance | Sheet #12 | One non-compliance issue encountered on 11/4/15 and documented on *Sheet #12 Notice of Non-Compliance* |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 6, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

NOTE: All comments are numbered for reference and included on the included comment section.

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/09/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, November 06, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen material is pulling loose from the perimeter fence by the mechanics area on Kellogg Street on SA-6 South. |
| 2 | IA2Q4A1AL8 | Garbage and other debris is present on the grass area at the Kellogg Street jughandle on SA-6 South |
| 3 | IA2Q4A1AL8 | Erosion control measures are not in place on SA-6 North along the sidewalk where Guarini Plumbing installed the new water valves. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 11/09/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach or replace windscreen material as required. | 11-12-15 MM |
| 2 | Pick up and dispose of garbage and debris as required. | 11-12-15 MM |
| 3 | Re-install silt fence or construct silt dams along the sidewalk adjacent to the Rt. 440 pedestrian walkway. | 11-11-15 MM |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date** 11/12/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 13, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | ✓ | | | |
| River Discharge Weir | ✓ | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | ✓ | | | |
| Stockpile Tarping/Containment | ✓ | | | |
| Proper Chemical Storage | ✓ | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | ✓ | | | |
| Truck De-Con Operation | ✓ | | | |
| Flood Protection | ✓ | | | |
| Haul Road Maintenance | ✓ | | | |
| Perimeter Fencing/Windscreen | ✓ | | | |
| Storm Drain Protection | ✓ | | | |
| Ponded Storm Water | ✓ | | | |
| Housekeeping | ✓ | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | ✓ | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | ✓ | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | ✓ | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | ✓ | | | |
| Proper Chemical Storage | ✓ | | | |
| Containment Around Exclusion Zones | ✓ | | | |
| Water Truck Wet- Down Operation | ✓ | | | |
| Truck De-Con Operation | ✓ | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | ✓ | | | |
| Perimeter Fencing/Windscreen | ✓ | | | |
| Storm Drain Protection | ✓ | | | |
| Ponded Storm Water | ✓ | | | |
| Housekeeping | ✓ | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | ✓ | | | |
| River Discharge Weir | ✓ | | | |
| Swale Check Dams | ✓ | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | ✓ | | | |
| Stockpile Tarping/Containment | ✓ | | | |
| Proper Chemical Storage | ✓ | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | ✓ | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | ✓ | | | |
| Perimeter Fencing/Windscreen | ✓ | | | |
| Storm Drain Protection | ✓ | | | |
| Ponded Storm Water | ✓ | | | |
| Housekeeping | ✓ | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/12/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, November ~~13~~ 12, 2015**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
**SESCP SCD:** EEPSQUO2YB
**RFA PI ID #:**
**RFA Portal ID#:** 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Material on ramp to SA-6 North |
| 2 | IA2Q4A1AL8 | Material on on the south runway of SA-7 and at the outlet of the structural fill crossing on the west side |
| 3 | IA2Q4A1AL8 | No safety fencing along the excavation of the 2' cut in 1N. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** _____

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Scrape the ramp | 11/17/15 |
| 2 | Scrape the south run way | 11/18/15 |
| 3 | Install safety fencing along cut faces of 1N | 11/17/15 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 11/18/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 20, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 1 |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/23/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, November 20, 2015

SA-6 North & South
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

GWTP (SA-6 North)
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The tracking pad at the truck exit gate on SA-6 South is blinded with sediment. |
| 2 | IA2Q4A1AL8 | Filter fabric in the catch basins at the western end of Kellogg Street is blinded with sediment and/or perforated. |
| 3 | IA2Q4A1AL8 | The fire truck access roadway on the eastern side of the H Building on SA-6 North is blocked with historic fill material from the stockpile in that area. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 11/23/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-work the stone in the tracking pad or replace it to make it functional. | 11-25-15 MM. |
| 2 | Replace the filter fabric in the three catch basins as required. | 11-23-15 MM. |
| 3 | Remove the material which is blocking the emergency vehicle accessway between the eastern side of the H Building and the historic fill stockpile. | ONGOING MM. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 11/25/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 25, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/30/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Wednesday, November 25, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage is present along the Kellogg Street jughandle outside of the perimeter site fence. |
| 2 | IA2Q4A1AL8 | **REPEAT:** The fire truck access roadway on the eastern side of the H Building on SA-6 North is blocked with historic fill material from the stockpile in that area. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 11/30/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up garbage and other debris along the outside of the SA-6 South perimeter fence. | 12-2-15 MM |
| 2 | Remove the material which is blocking the emergency vehicle accessway between the eastern side of the H Building and the historic fill stockpile. | 12-3-15 MM |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 12/03/15

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (Submitted October 2015)
- 12/2/15 PVSC Correspondence: Revisions to Sewer Use Permit #20630025

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

November 19, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the October 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 10 | 01 | 15 | 10 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,506 | 86,317 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF SAMPLES | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | | COMP/GRAB |
| Chromium | Sample Measurement | 0.48 | 0.54 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00021 | 0.00021 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1576 | 0.1576 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

November 19, 2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North
**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)
**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305
**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 10 | 01 | 15 | 10 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,371,680 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 48,118,008 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 10/13/2015 | <33 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris HF | John J. Morris | (973) 455-4003 |
| | | DATE November 19, 2015 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | | | | | | | | MONTH: October 2015 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 10/1/2015 | Angel Trujillo | 45746328 | 45829794 | 83,466 | 0.083466 | 7.07 | 0.749 | | | | | | | | | 0.52 |
| 10/2/2015 | Angel Trujillo | 45829794 | 45905736 | 75,942 | 0.075942 | 7.44 | 0.749 | | | | | | | | | 0.47 |
| 10/3/2015 | Angel Trujillo | 45905736 | 45976242 | 70,506 | 0.070506 | N/A | 0.749 | | | | | | | | | 0.44 |
| 10/4/2015 | Angel Trujillo | 45976242 | 46046748 | 70,506 | 0.070506 | 7.51 | 0.749 | | | | | | | | | 0.44 |
| 10/5/2015 | Angel Trujillo | 46046748 | 46119544 | 72,796 | 0.072796 | 7.53 | 0.749 | | | | | | | | | 0.45 |
| 10/6/2015 | Angel Trujillo | 46119544 | 46195518 | 75,974 | 0.075974 | 7.36 | 0.749 | | | | | | | | | 0.47 |
| 10/7/2015 | Angel Trujillo | 46195518 | 46273544 | 78,026 | 0.078026 | 7.39 | 0.749 | | | | | | | | | 0.49 |
| 10/8/2015 | Angel Trujillo | 46273544 | 46350538 | 76,994 | 0.076994 | 7.47 | 0.749 | | | | | | | | | 0.48 |
| 10/9/2015 | Angel Trujillo | 46350538 | 46426069 | 75,531 | 0.075531 | 7.50 | 0.749 | | | | | | | | | 0.47 |
| 10/10/2015 | Angel Trujillo | 46426069 | 46512386 | 86,317 | 0.086317 | 7.49 | 0.749 | | | | | | | | | 0.54 |
| 10/11/2015 | Angel Trujillo | 46512386 | 46585241 | 72,855 | 0.072855 | N/A | 0.749 | | | | | | | | | 0.46 |
| 10/12/2015 | Angel Trujillo | 46585241 | 46658096 | 72,855 | 0.072855 | 7.52 | 0.749 | | | | | | | | | 0.46 |
| 10/13/2015 | Angel Trujillo | 46658096 | 46733444 | 75,348 | 0.075348 | 7.05 | 0.749 | <5.1 | <33 | | <0.010 | <0.015 | <0.010 | 0.00021 | <0.020 | 0.47 |
| 10/14/2015 | Angel Trujillo | 46733444 | 46808816 | 75,372 | 0.075372 | 7.53 | 0.749 | | | | | | | | | 0.47 |
| 10/15/2015 | Angel Trujillo | 46808816 | 46886626 | 77,810 | 0.07781 | 7.52 | 0.749 | | | | | | | | | 0.49 |
| 10/16/2015 | Angel Trujillo | 46886626 | 46964342 | 77,716 | 0.077716 | 7.49 | 0.749 | | | | | | | | | 0.49 |
| 10/17/2015 | Angel Trujillo | 46964342 | 47049248 | 84,906 | 0.084906 | 7.44 | 0.749 | | | | | | | | | 0.53 |
| 10/18/2015 | Angel Trujillo | 47049248 | 47122258 | 73,010 | 0.07301 | N/A | 0.749 | | | | | | | | | 0.46 |
| 10/19/2015 | Angel Trujillo | 47122258 | 47195268 | 73,010 | 0.07301 | 7.33 | 0.749 | | | | | | | | | 0.46 |
| 10/20/2015 | Angel Trujillo | 47195268 | 47272370 | 77,102 | 0.077102 | 7.81 | 0.749 | | | | | | | | | 0.48 |
| 10/21/2015 | Angel Trujillo | 47272370 | 47348190 | 75,820 | 0.07582 | 7.54 | 0.749 | | | | | | | | | 0.47 |
| 10/22/2015 | Angel Trujillo | 47348190 | 47425246 | 77,056 | 0.077056 | 7.40 | 0.749 | | | | | | | | | 0.48 |
| 10/23/2015 | Angel Trujillo | 47425246 | 47504328 | 79,082 | 0.079082 | 7.47 | 0.749 | | | | | | | | | 0.49 |
| 10/24/2015 | Angel Trujillo | 47504328 | 47588942 | 84,614 | 0.084614 | 7.53 | 0.749 | | | | | | | | | 0.53 |
| 10/25/2015 | Angel Trujillo | 47588942 | 47661650 | 72,708 | 0.072708 | N/A | 0.749 | | | | | | | | | 0.45 |
| 10/26/2015 | Angel Trujillo | 47661650 | 47734358 | 72,708 | 0.072708 | 7.48 | 0.749 | | | | | | | | | 0.45 |
| 10/27/2015 | Angel Trujillo | 47734358 | 47809676 | 75,318 | 0.0753 | 7.44 | 0.749 | | | | | | | | | 0.47 |
| 10/28/2015 | Angel Trujillo | 47809676 | 47887866 | 78,190 | 0.07819 | 7.53 | 0.749 | | | | | | | | | 0.49 |
| 10/29/2015 | Angel Trujillo | 47887866 | 47958382 | 70,516 | 0.070516 | 7.47 | 0.749 | | | | | | | | | 0.44 |
| 10/30/2015 | Angel Trujillo | 47958382 | 48032990 | 74,608 | 0.074608 | 7.29 | 0.749 | | | | | | | | | 0.47 |
| 10/31/2015 | Angel Trujillo | 48032990 | 48118008 | 85,018 | 0.085018 | 7.51 | 0.749 | | | | | | | | | 0.53 |
| **TOTAL** | | | | **2,371,680** | **2.37168** | | | <5.1 | <33 | | <0.010 | <0.015 | <0.010 | 0.00021 | <0.020 | |
| | | | **High:** | **86,317** | | | | | | | | | | | **High:** | **0.54** |
| | | | **Average:** | **76,506** | | | | | | | | | | | **Average:** | **0.48** |

WW

E

JC 6107

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42290.45854 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-101315 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | | | Site ID HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | | | Lab Job # HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant CH2M | | | Authorized User: Honeywell |
| Preliminary Data To | | | | Text & Excel File Drive: Excel & Text File Order |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI; Version 8.0 Unauthorized use strictly prohibited

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-101315-A | 10/13/2015 | 13:15 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | L19 |
| 2 | 087-WW | | | 087-WWE-101315-B | 10/13/2015 | 13:20 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | U448 |
| 3 | 087-WW | | | 087-WWI-101315 | 10/13/2015 | 13:25 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | A5 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | G16 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact |
|---|---|---|---|---|---|
| Frank Schroyer pH = 7.05 s.u. @ 8.8°C | AMEC Foster Wheeler | | | | |
| Date/Time 1500 10/13/15 | | Date/Time 10-13 1500 | | Cooler Temp. | |
| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact |
| Date/Time 10-13 1701 | | | Date/Time 10/13 1701 | Cooler Temp. | |

Preservatives: (Other; Specify): 1

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

03.5 SP

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE

INITIAL ASESSMENT NL38

LABEL VERIFICATION

Accutest LabLink@881656 10:36 06-Nov-2015

# Report of Analysis





**Client Sample ID:** 087-WWE-101315-A
**Lab Sample ID:** JC6107-1
**Matrix:** AQ - Water
**Project:** PESNJP: Hudson County, Jersey City, NJ

**Date Sampled:** 10/13/15
**Date Received:** 10/13/15
**Percent Solids:** n/a

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 749 | 10 | ug/l | 1 | 10/15/15 | 10/15/15 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 10/15/15 | 10/15/15 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Lead | < 15 | 15 | ug/l | 5 | 10/15/15 | 10/16/15 | GT | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | 0.21 | 0.20 | ug/l | 1 | 10/14/15 | 10/14/15 | MA | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 10/15/15 | 10/15/15 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 10/15/15 | 10/15/15 | ND | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA37773
(2) Instrument QC Batch: MA37787
(3) Instrument QC Batch: MA37798
(4) Prep QC Batch: MP89591
(5) Prep QC Batch: MP89597

RL = Reporting Limit

Accutest LabLink@881656 10:36 06-Nov-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-101315-A | | |
| **Lab Sample ID:** | JC6107-1 | **Date Sampled:** | 10/13/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 10/13/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | < 4.0 | 4.0 | mg/l | 1 | 10/15/15 | LA | SM2540 D-11 |
| pH [b] | 6.91 | | su | 1 | 10/13/15 17:10 | HL | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 520 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@881656 10:36 06-Nov-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-101315-A | | |
| **Lab Sample ID:** | JC6107-1A | **Date Sampled:** | 10/13/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 10/13/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.2 4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 33 | 33 | mg/l | 1 | 10/14/15 16:10 | LS | SM5210 B-11 |

RL = Reporting Limit

Accutest LabLink@881656 10:36 06-Nov-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-101315-B | | |
| **Lab Sample ID:** | JC6107-2 | **Date Sampled:** | 10/13/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 10/13/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | N249107.D | 1 | 10/14/15 | WO | n/a | n/a | VN10560 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 50 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.6 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.1 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.25 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 20.6 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.45 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.47 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 75.3 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.7 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.66 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@881656 10:36 06-Nov-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-101315-B | | |
| **Lab Sample ID:** | JC6107-2 | **Date Sampled:** | 10/13/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 10/13/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 49.5 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 101% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 101% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 103% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 101% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@881656 10:36 06-Nov-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-101315-B | | |
| **Lab Sample ID:** | JC6107-2 | **Date Sampled:** | 10/13/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 10/13/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 10/15/15 | LS | EPA 1664A |

RL = Reporting Limit

THOMAS TUCCI, JR.
*Chairman*

KENNETH J. LUCIANIN
*Vice Chairman*

ELIZABETH CALABRESE
DAVID S. CATUOGNO
MILDRED C. CRUMP
SCOTT M. HECK
LUIS A. QUINTANA
*Commissioners*

*"Protecting Public Health and the Environment"*
600 Wilson Avenue
Newark, New Jersey 07105
P (973) 344-1800
www.nj.gov/pvsc
Fax: (973) 344-4876

GREGORY A. TRAMONTOZZI
*Executive Director and General Counsel*

JOSEPH F. KELLY
*Acting Clerk*

December 2, 2015

**CERTIFIED RECEIPT**
**91 7190 0943 0010 0008 2910**

Maria Kaouris, Remediation Manager
Honeywell International Inc.
101 Columbia Road, Solvay#4
Morristown, NJ 07962

**RE: REVISIONS TO SEWER USE PERMIT # 20630025**

Dear Ms. Kaouris,

Enclosed is a revised Sewer Use Permit for your facility. This revised permit will replace your presently active permit. The revisions are stated on page 3 of 8, special conditions or remarks.

In addition, Section B, conditions applicable to all permits (pages1-13) was sent with your permit. This section should be attached to the final permit.

If you have any questions, please contact Laura Marchitto at (973) 817-5905.

Very truly yours,
**PASSAIC VALLEY SEWERAGE COMMISSION**

Anthony Gammaro
Assistant Manager, User Charge & Permit Management

AG/lm
Enclosure

c: Gregory A. Tramontozzi, Executive Director
Herbert Skinner, Director, Inspection & Compliance Bureau
Andrew Caltagirone, Assistant Director, Inspection & Compliance Bureau
Laura Marchitto, Operations Coordinator, User Charge and Permit Management
Rich Haytas, Senior Engineer, Jersey City Municipal Utilities Authority

Passaic Valley Sewerage Commission
600 Wilson Ave
NEWARK NJ 07105



91 7190 0943 0010 0008 2910

HONEYWELL INTERNATIONAL INC.
ATTN: MARIA KAOURIS
115 Tabor Raod ( 4D-8)
Morrris Plains NJ 07950

17966

# PASSAIC VALLEY SEWERAGE COMMISSION

## SEWER USE PERMIT

**Permit #** 20630025

(Please use the Permit Number on any correspondence with PVSC)
In compliance with the provisions of the Federal Water Pollution Control Act, its amendments, the Clean Water Act and Rules and Regulations of the Passaic Valley Sewerage Commission

HONEYWELL INTERNATIONAL INC.

BAYFRONT REDEVELOPMENT

(herein, after referred to as the Permittee)
is authorized to discharge from a facility located at

525 & 575 ROUTE 440

JERSEY CITY, NEW JERSEY 07305

to the Passaic Valley Sewerage Commission Treatment Works in accordance with discharge limitations, monitoring requirements and other conditions set forth herein.

**EFFECTIVE DATE** 10/01/2013

**EXPIRATION DATE** 09/30/2018

**PASSAIC VALLEY SEWERAGE COMMISSION**

BY Gregory A. Tramontozzi

Gregory A. Tramontozzi
Executive Director

REV: 04/2015
REV: 12/2015

## SECTION A

## CONDITION SPECIFIC TO THIS PERMIT

1. **Sampling**

1.1 Samples and measurements taken as required under this permit shall be representative of the monitored activity. All samples shall be taken at the monitoring points approved by the PVSC and specified in this permit. Unless other wise specified, all samples shall be drawn by a 24-hour composite sampler acceptable to the PVSC which shall be equipped with attachments appropriate for affixing seals. During and after collection, the sample shall be maintained between $1^0C - 4^0C$.

1.2 In addition to the other sample requirements set forth in SECTION A, PART 2 of this permit, the Permittee shall comply with the following:

(a) Samples that are taken for heavy metal analysis must be drawn by an automatic 24-hour composite sampler. A grab sample is not acceptable for metals compliance determination.

# PASSAIC VALLEY SEWERAGE COMMISSION
# 600 WILSON AVENUE
# NEWARK, NEW JERSEY 07105

## SIU FACT SHEET

Sewer Use Permit to discharge into Passaic Valley Sewerage Commission Treatment Plant

Honeywell International Incorporated has submitted a completed Contractual Indirect Discharger Application for a Sewer Use Permit Revision to discharge into the treatment works.

| NAME & ADDRESS OF APPLICANT | NAME AND ADDRESS OF FACILITY WHERE DISCHARGE OCCURS |
|---|---|
| Honeywell International Inc.<br>101 Columbia Road, Solvay 4<br>Morristown, New Jersey 07962 | Honeywell International Inc.<br>Bayfront Redevelopment<br>525 & 575 Route 440<br>Jersey City, New Jersey 07305 |

**Description of Facility Operations:** Groundwater discharger

**Million Gallons per Day (MGD) Industrial Wastewater:** Approx. - .094 MGD

**Number of Outlets: – 1:** This outlet is used for compliance

**Sample Point Location:** The Sample points for 24hr. composite & grab sampling are located within the Groundwater Treatment Plant (GWTP) Building. The sample point for 24hr. composite sampling (Metals & BOD) is located at the effluent surge tank and the sample point for the grab samples (SGT-HEM, TVOC) is located upstream of the effluent flow meter.

**Basis for Permit Conditions:** Groundwater

**Type of Pretreatment Equipment Installed:** Equalization Tank, Chemical Precipitation System and a Solids Handling System

**Duration of Sewer Use Permit:** 5 Years

**Special Conditions or Remarks:** Revision. Amended to 70gpm. This company is covered under PVSC Local Limits

REV: 04/2015
REV: 12/2015

2. **MONITORING REQUIREMENTS AND DISCHARGE LIMITATIONS**

(a) Beginning (10/01/2013) and lasting through (09/30/2018) the Permittee is authorized to discharge from outlet # (20630025-1). Such discharge shall be monitored as specified below. The table lists the limitations or procedures applicable to this outlet. The volume shall be determined from flowmeter readings. The Permittee shall submit volume in accordance with PVSC User Charge Self-Monitoring Report Form MR-2.

| EFFLUENT CHARACTERISTIC | DISCHARGE LIMITATIONS | | | MONITORING REQUIREMENTS | |
|---|---|---|---|---|---|
| PARAMETER | MONTHLY AVERAGE | DAILY MAX | MEASUREMENT FREQUENCY | SAMPLE TYPE | REPORTING PERIOD |
| Volume | XXXXX | XXXXX | XXXXX | XXXXX | Monthly |

## 2. MONITORING REQUIREMENTS AND DISCHARGE LIMITATIONS

(b) Beginning (10/01/2013) and lasting through (09/30/2018) the Permittee is authorized to discharge from outlet # (20630025-1). Such discharge shall be monitored as specified below. The table lists the limitations or procedures applicable to this outlet. The volume shall be determined from flowmeter readings. The Sample points for 24hr. composite & grab sampling are located within the Groundwater Treatment Plant (GWTP) Building. The sample point for 24hr. composite sampling (Metals & BOD) is located at the effluent surge tank and the sample point for the grab samples (SGT-HEM, TVOC) is located upstream of the effluent flow meter. The Permittee shall submit volume and analysis results in accordance with PVSC Pretreatment Discharge Monitoring Form MR-1.

| | DISCHARGE LIMITATIONS | | MONITORING REQUIREMENTS | | |
|---|---|---|---|---|---|
| PARAMETER | MONTHLY AVERAGE | DAILY MAX | MEASUREMENT FREQUENCY | SAMPLE TYPE | REPORTING PERIOD |
| SGT-HEM (Non-Polar Material) | 100 mg/l | 150 mg/l | Monthly | Grab* | Monthly |
| Chromium | XXXXX | 23 lbs/day | Monthly | 24 hr. Comp. | Monthly |
| TVOC | XXXXX | XXXXX | Monthly | Grab** | Monthly |
| BOD | XXXXX | XXXXX | Monthly | 24 hr. Comp | Monthly |
| Volume | XXXXX | XXXXX | XXXXX | XXXXX | Monthly |

* Sampling procedure must be in accordance with those specified by N.J.D.E.P.. Analysis procedure as defined by E.P.A. Method 1664A.

** Sampling procedure must be in accordance with those specified by N.J.D.E.P.. Analysis procedure as defined by E.P.A. Method 624.

REV: 04/2015

## 2. MONITORING REQUIREMENTS AND DISCHARGE LIMITATIONS

(b) Beginning (10/01/2013) and lasting through (09/30/2018) the Permittee is authorized to discharge from outlet # (20630025-1). Such discharge shall be monitored as specified below. The table lists the limitations or procedures applicable to this outlet. The volume shall be determined from flowmeter readings. The Sample points for 24hr. composite & grab sampling are located within the Groundwater Treatment Plant (GWTP) Building. The sample point for 24hr. composite sampling (Metals & BOD) is located at the effluent surge tank and the sample point for the grab samples (SGT-HEM, TVOC) is located upstream of the effluent flow meter The Permittee shall submit volume and analysis results in accordance with PVSC Pretreatment Discharge Monitoring Report Form MR-1.

| PVSC LOCAL LIMITS | DISCHARGE LIMITATIONS | | MONITORING REQUIREMENTS | | |
|---|---|---|---|---|---|
| PARAMETER | mg/l MONTHLY AVERAGE | mg/l THRESHOLD VALUE | MEASUREMENT FREQUENCY | SAMPLE TYPE | REPORTING PERIOD |
| Cu | 3.6 | 0.18 | Monthly | 24 hr. comp. | Monthly |
| Pb | 1.0 | 0.05 | Monthly | 24 hr. comp. | Monthly |
| Hg | 0.080 | 0.004 | Monthly | 24 hr. comp. | Monthly |
| Ni | 3.9 | 0.2 | Monthly | 24 hr. comp. | Monthly |
| Zn | 4.2 | 0.21 | Monthly | 24 hr. comp. | Monthly |
| Volume | XXXXX | XXXXX | XXXXX | XXXXX | Monthly |

# HONEYWELL INTERNATIONAL INC. – BAYFRONT REDEVELOPMENT - ID# 20630025

## 3. SCHEDULE OF COMPLIANCE

The Permittee is required to meet the following schedule of compliance:

A. Analysis of wastewater parameters shall be performed by a laboratory that has been certified by the State of New Jersey. Perittee is required to submit all certified analyses as an attachment to the monthly MR-1 report.

B. The Permittee is required to submit as an attachment to the MR-1 and/or MR-2 report monthly, a water balance showing meter readings used to calculate the reported volume discharged.

C. Permittee to submit a periodic compliance monitoring report MR-2 form for monthly reporting requirements within twenty-one (21) days after the end date of each preceding month.

D. Permittee to be in compliance with PVSC Local Limits.

Permittee to submit a periodic compliance monitoring report MR-1 form for monthly reporting requirements within thirty-five (35) days after the end date of each preceding month in accordance with General Pretreatment Regulations 40 CFR 403.12 section (e).

E. If the Permittee has been authorized by the PVSC to certify for non-use for one or more heavy metals, the Permittee must sample the discharge in March and September of each year in order to prove continued compliance. If any analytical results exceed the Threshold Value, but not the Local Limit, the Permittee shall analyze a sample each succeeding month until three successive monthly results are at or below the Threshold Value stated in the PVSC Rules and Regulations Section B-103.3 Table B-2.

F. Be certain that you do not surcharge any sewer lines. The rate of discharge must not exceed a maximum average daily flow rate of 70 gpm over the course of a sample date. Please note all discharges will automatically cease in the event the liquid level in the Emergency Outflow Structure Standpipe rises to a level 12 inches from the top of this pipe as detected by a float switch.

G. Permittee must operate in accordance with its 6/4/14 approved Slug Control Plan.

H. All discharge must pass through a non-resettable flow meter.

I. All discharge shall cease 5 years from the start of discharge. If additional time is needed, you must request an extension from PVSC 90 days prior to the expiration date of the Agreement and this Sewer Use Permit.

REV: 04/2015
REV: 12/2015

# HONEYWELL INTERNATIONAL INC. - BAYFRONT REDEVELOPEMENT – ID# 20630025

## SECTION A-3 SCHEDULE OF COMPLIANCE CONTINUED

J. All PVSC Rules & Regulations must be adhered to. (www.nj.gov/pvsc)

K. This Sewer Use Permit will run concurrent with a said contract executed by both Honeywell International Inc. and PVSC.

L. Honeywell International Incorporated must abide with the Memorandum of Understanding (MOU) executed both by Honeywell International Inc. and PVSC on 1/29/13.

M. PVSC reserves the right to require toxicity evaluation and/or to change the condition of this Permit, including discontinuing the discharge if it deems necessary.

N. The Permittee shall notify in writing, all agencies as directed by 40 CFR 403.12 (p) of any discharges classified hazardous waste under 40 CFR 261.

REV: 04/2015

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending November 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending November 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending November 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-22** | Detail BN has been modified to extend the lIDPE up and over the SCB Wall. The prior detail showed both the GDI and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending November 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D.<br>In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF.<br>This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 12 OF 25**

- **2016 Monthly Reports Part 1**

**1/14/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

January 14, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2015-12**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from December 1 – December 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:jtc/sgf

Attachment: December 2015 SA-6/7 Combined Monthly Progress Report No. 2015-12

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2015-12
### Project SA-6 & 7 Remediation

# December 2015

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 12/11/15 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2015-11 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 12/15/15 | Special Master Conference Call | n/a |
| 12/17/15 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, JC<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 12/23/15 | SA-6 Horizon C Cover Soils<br>Study Area 6 Chromium Remedy<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 12/6/15 | 12/13/15 | 12/20/15 | 12/27/15 |
| **Construction Management (AMEC)** | 8 | 10 | 9 | 8 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 30 | 31 | 32 | 36 |
| **Arecon/US Ecology Subcontractors** | 2 | 0 | 2 | 2 |
| **Langan** | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 1 | 2 | 2 |
| **Cornerstone** | 0 | 2 | 2 | 1 |
| **TOTAL STAFF** | **46** | **50** | **53** | **55** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected December PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Conducted S-3 Mass Removal Injection Event No. 26 in well 088-IW-01.
- Completed installation of dual walled piping and electrical conduit to PW-3 extraction well.
- Completed startup and pumping of PW-3 extraction well.
- Conducted round of quarterly groundwater level measurements.
- Conducted biennial LTMP groundwater quality sampling event.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on December 8, 2015.
- From December 23, 2015 to December 28, 2015, the GWTP was offline due to a faulty control card. Trouble shooting was attempted on December 26, 2015 which included replacement of a communication cable and the input and output boards. These actions did not restore the system. On December 28, 2015 the problem was diagnosed as being a faulty scanner and module card and cards were replaced. The system was fully restarted on December 28, 2015 at 1:25 pm.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 12/6/15 | 12/13/15 | 12/20/15 | 12/27/15 |
| Avg. Gallons Treated & Discharged (per day) | 76,813 | 67,192 | 62,438 | 61,634 |
| Average Flow (gpm) for Operating Period | 55 | 53 | 54 | 49 |
| Avg. Hours of Plant Operation | 23 | 21 | 23 | 20 |
| GWTP Influent Tanks (gal.) | 4,080 | 4,157 | 4,560 | 5,424 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continue pumping/dewatering of well points associated with Excavation Areas EA-2 and EA-3.

- Completed excavation of EA-8.
- Completed installation of shallow well points and dewatering well at Site 163.
- Began dewatering and excavation activities of Site 163. Completed installation of temporary 40 mil geomembrane liner in bermed containment areas.
- Initiated excavation of Excavation Areas EA-2 and EA-3 and placed ramp and bridge lift to protect work in the southern portion.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Horwith** | Tri-axle | PA Transload | US Ecology | >240 mg/kg CrVI | 154 | 21.56 | 3,321 |
| **Entact/Horwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non-haz Cr | 65 | 26.1 | 1,701 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | Excavation, EA-2/EA-3<br>Volume Excavated - Total for Reporting Period: EA-2/EA-3(9,945 CY) /<br>Total to Date: 34,556 CY |
| **Backfill in Progress** | EA-8, EA2/3 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 12/6/15 | 12/13/15 | 12/20/15 | 12/27/15 |
| Liberty I-5 | 940 | 2,337 | 1,427 | 0 |
| Horizon C soils | 1,133 | 0 | 0 | 0 |
| Tilcon 2.5” | 182 | 0 | 0 | 0 |

- Screened Celgene materials greater than 3/8 inch were transferred and placed as bridge lift in EA-2/EA-3.
- Screened Celgene material was removed from the east side of the SA-6 South open space area during final grading of the protective cover soils. Approximately 203 cubic yards was removed from the cap area and transferred to the Celgene stockpile area.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.

- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.
- Area 2N: Began offloading of area 2N.
- Area 3N: Began placing surcharge material, approximately 80% of the design volume to be placed is complete.
- Area 4N: Completed installation of surcharge monitoring instrumentation.

## F. SHEET PILE OPERATIONS

- Completed the installation of lagging to the EA-2/EA-3 temporary excavation support system.
- Completed installation of sheeting within the Trash Pit interior (grout sealing to concrete walls still to be completed).

## G. CAPPING OPERATIONS

- Continued fine grading of protective cover soils and associated compaction testing on the SA-6 South open space area.
- Continued placement of root barrier and demarcation tape on the SA-6 South open space area.
- Continued placement and grading of Horizon C soils (within future vegetated areas) and structural fill (within future roadway areas) of the SA-6 South open space area.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Pending | 12/2/15 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue Trash Pit Interior sheeting, grouting and backfilling activities.
- Complete EA-2/EA-3 excavation and backfilling activities.
- Complete EA-1 excavation and backfilling activities.
- Continue Site 163 dewatering and excavation activities.
- Complete Area 3N Surcharge material placement and begin to place material in Area 4N. Prepare next monthly Surcharge Monitoring Report for data collected in December 2015.
- Begin installation of the Contingent Groundwater Extraction System piping in Area 1N.
- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.
- Pending identification of new source(s), resume import and placement of Horizon C Soils on the Study Area 6 South open space area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Complete placement of asphalt associated with the PW-3 force main trench.

- Continue dewatering and excavation activities associated with Site 163 excavation within the residential footprint including installation of temporary sheeting as needed.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. *Groundwater Quality Data (not included in this reporting period)*
9. *Surcharge Monitoring Update (not included in this reporting period)*
10. Sheet Pile Update (Repair Log)
11. Capping Update (SA-6 South Cap Subgrade Progress Map)
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 12/29/15

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Continuing Excavation Areas 2 and 3.




**Site Photograph 2:** Placement of clean fill in Excavation Areas 2 and 3.




**Site Photograph 3:** Placement of surcharge soils at former city properties Area 3N.



**Site Photograph 4:** Installing root barrier in open space area utility corridor.




**Site Photograph 5:** Loading clean fill for use in utility corridor.




**Site Photograph 6:** Spreading clean fill in utility corridor.





**Site Photograph 7:** Placement of clean fill in open space area utility corridor.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of January 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2015-12
Attachment 3: Excavation and Backfill (Progression Chart)




## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

# Attachment 4: Dewatering Operations Update

**STUDY AREA 6 NORTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 10/30/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 7,750 | 2,962,922 | 5.4 | |
| 11/02/15 | 1 | 72 | 19,20 | 26 | N/A | N/A | 21,000 | 2,983,922 | 4.9 | |
| 11/03/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 7,750 | 2,991,672 | 5.4 | |
| 11/04/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 7,750 | 2,999,422 | 5.4 | |
| 11/05/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 7,750 | 3,007,172 | 5.4 | |
| 11/06/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 7,750 | 3,014,922 | 5.4 | |
| 11/09/15 | 1 | 72 | 19,20 | 26 | N/A | N/A | 20,500 | 3,035,422 | 4.7 | |
| 11/10/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 7,750 | 3,043,172 | 5.4 | |
| 11/11/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 3,500 | 3,046,672 | 2.4 | |
| 11/12/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 3,500 | 3,050,172 | 2.4 | |
| 11/13/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 3,000 | 3,053,172 | 2.1 | |
| 11/16/15 | 1 | 72 | 19,20 | 26 | N/A | N/A | 6,000 | 3,059,172 | 1.4 | |
| 11/17/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 2,200 | 3,061,372 | 1.5 | |
| 11/18/15 | 1 | 24 | 19,20 | 26 | N/A | N/A | 2,000 | 3,063,372 | 1.4 | |
| 11/19/15 | 1 | 24 | 19,20 | 22 | N/A | N/A | 2,000 | 3,065,372 | 1.4 | |
| 11/20/15 | 1 | 24 | 19,20 | 22 | N/A | N/A | 2,000 | 3,067,372 | 1.4 | |
| 11/22/15 | 1 | 48 | 19,20 | 22 | N/A | N/A | 4,000 | 3,071,372 | 1.4 | |
| 11/23/15 | 1 | 24 | 19,20 | 22 | N/A | N/A | 2,000 | 3,073,372 | 1.4 | |
| 11/24/15 | 1 | 24 | 19,21 | 23 | N/A | N/A | 2,000 | 3,075,372 | 1.4 | |
| 11/25/15 | 1 | 24 | 19,20 | 18 | N/A | N/A | 1,500 | 3,076,872 | 1.0 | |
| 11/29/15 | 1 | 96 | 19,20 | 18 | N/A | N/A | 6,000 | 3,082,872 | 1.0 | |
| 11/30/15 | 1 | 24 | 19,20 | 18 | N/A | N/A | 2,000 | 3,084,872 | 1.4 | |
| 12/01/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,086,672 | 1.3 | |
| 12/02/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,088,472 | 1.3 | |
| 12/03/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,090,272 | 1.3 | |
| 12/04/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,092,072 | 1.3 | |
| 12/06/15 | 1 | 48 | 19,20 | 14 | N/A | N/A | 3,000 | 3,095,072 | 1.0 | |
| 12/07/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,096,872 | 1.3 | |
| 12/08/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,098,672 | 1.3 | |
| 12/09/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,100,472 | 1.3 | |
| 12/10/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,102,272 | 1.3 | |
| 12/13/15 | 1 | 48 | 19,20 | 11 | N/A | N/A | 1,700 | 3,103,972 | 0.6 | |
| 12/14/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,105,672 | 1.2 | |
| 12/15/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,107,372 | 1.2 | |
| 12/16/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,109,072 | 1.2 | |
| 12/17/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,110,772 | 1.2 | |
| 12/18/15 | 1 | 24 | 19 | 10 | N/A | N/A | 1,700 | 3,112,472 | 1.2 | System Taken Offline |

Note: Previous information is trunketed. Only last month and current month information is provided.
Dewatering is associated with EA2/EA3 Excavation.

**STUDY AREA 6 NORTH DEEP WELL DATA (DW-6)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 12/06/15 | 48 | N/A | N/A | 10,000 | 10,000 | 3.5 | |
| 12/07/15 | 24 | N/A | N/A | 8,000 | 18,000 | 5.6 | |
| 12/08/15 | 24 | N/A | N/A | 8,000 | 26,000 | 5.6 | |
| 12/09/15 | 24 | N/A | N/A | 8,000 | 34,000 | 5.6 | |
| 12/10/15 | 24 | N/A | N/A | 10,000 | 44,000 | 6.9 | |
| 12/13/15 | 48 | N/A | N/A | 20,000 | 64,000 | 6.9 | |
| 12/14/15 | 24 | N/A | N/A | 10,000 | 74,000 | 6.9 | |
| 12/15/15 | 24 | N/A | N/A | 10,000 | 84,000 | 6.9 | |
| 12/16/15 | 24 | N/A | N/A | 10,000 | 94,000 | 6.9 | |
| 12/17/15 | 24 | N/A | N/A | 10,000 | 104,000 | 6.9 | |
| 12/18/15 | 24 | N/A | N/A | 10,000 | 114,000 | 6.9 | |
| 12/20/15 | 48 | N/A | N/A | 20,000 | 134,000 | 6.9 | |
| 12/21/15 | 24 | N/A | N/A | 10,000 | 144,000 | 6.9 | |
| 12/23/15 | 24 | N/A | N/A | 10,000 | 154,000 | 6.9 | |
| 12/24/15 | 24 | N/A | N/A | 10,000 | 164,000 | 6.9 | |
| 12/26/15 | 48 | N/A | N/A | 20,000 | 184,000 | 6.9 | |

**STUDY AREA 6 NORTH DEEP WELL DATA (DW-7)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/18/15 | 24 | N/A | N/A | 11,500 | 11,500 | 8.0 | Flow meter not installed, tank measured |
| 11/19/15 | 24 | N/A | N/A | 11,000 | 22,500 | 7.6 | |
| 11/20/15 | 24 | N/A | N/A | 11,000 | 33,500 | 7.6 | |
| 11/22/15 | 48 | N/A | N/A | 11,000 | 44,500 | 3.8 | |
| 11/23/15 | 24 | N/A | N/A | 11,000 | 55,500 | 7.6 | |
| 11/24/15 | 24 | N/A | N/A | 10,500 | 66,000 | 7.3 | |
| 11/25/15 | 24 | N/A | N/A | 10,500 | 76,500 | 7.3 | |
| 11/29/15 | 96 | N/A | N/A | 40,000 | 116,500 | 6.9 | |
| 11/30/15 | 24 | N/A | N/A | 10,500 | 127,000 | 7.3 | |
| 12/01/15 | 24 | N/A | N/A | 10,000 | 137,000 | 6.9 | |
| 12/02/15 | 24 | N/A | N/A | 10,000 | 147,000 | 6.9 | |
| 12/03/15 | 24 | N/A | N/A | 10,000 | 157,000 | 6.9 | |
| 12/04/15 | 24 | N/A | N/A | 12,000 | 169,000 | 8.3 | |
| 12/06/15 | 48 | N/A | N/A | 20,000 | 189,000 | 6.9 | |
| 12/07/15 | 24 | N/A | N/A | 8,000 | 197,000 | 5.6 | |
| 12/08/15 | 24 | N/A | N/A | 8,000 | 205,000 | 5.6 | |
| 12/09/15 | 24 | N/A | N/A | 8,000 | 213,000 | 5.6 | |
| 12/10/15 | 24 | N/A | N/A | 10,000 | 223,000 | 6.9 | |
| 12/13/15 | 48 | N/A | N/A | 20,000 | 243,000 | 6.9 | |
| 12/14/15 | 24 | N/A | N/A | 10,000 | 253,000 | 6.9 | |
| 12/15/15 | 24 | N/A | N/A | 10,000 | 263,000 | 6.9 | |
| 12/16/15 | 24 | N/A | N/A | 10,000 | 273,000 | 6.9 | |
| 12/17/15 | 24 | N/A | N/A | 10,000 | 283,000 | 6.9 | |
| 12/18/15 | 24 | N/A | N/A | 10,000 | 293,000 | 6.9 | |
| 12/20/15 | 48 | N/A | N/A | 20,000 | 313,000 | 6.9 | |
| 12/21/15 | 24 | N/A | N/A | 10,000 | 323,000 | 6.9 | Offline for Excavation/Backfill |

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 10/29/15 | 9:00 | 15:00 | 6:00 | 36,973.34 | 37,092.42 | 119,080 | 36,948,570 | |
| 11/02/15 | 8:00 | 13:00 | 5:00 | 37,092.42 | 37,158.61 | 66,190 | 37,014,760 | PVSC Compliance Sample Collected |
| 11/04/15 | 8:30 | 14:30 | 6:00 | 37,158.61 | 37,207.47 | 48,860 | 37,063,620 | |
| 11/06/15 | 12:00 | 15:00 | 3:00 | 37,207.47 | 37,237.70 | 30,230 | 37,093,850 | |
| 11/18/15 | 8:00 | 15:00 | 7:00 | 37,237.70 | 37,375.84 | 138,140 | 37,231,990 | |
| 11/22/15 | 9:00 | 13:00 | 4:00 | 37,375.84 | 37,440.68 | 64,840 | 37,296,830 | |
| 11/23/15 | 9:30 | 14:30 | 5:00 | 37,440.68 | 37,505.15 | 64,470 | 37,361,300 | |
| 11/25/15 | 7:15 | 13:45 | 6:30 | 37,505.15 | 37,566.11 | 60,960 | 37,422,260 | |
| 11/30/15 | 7:30 | 14:30 | 7:00 | 37,566.11 | 37,667.64 | 101,530 | 37,523,790 | |
| 12/01/15 | 8:00 | 15:15 | 7:15 | 37,667.64 | 37,743.44 | 75,800 | 37,599,590 | |
| 12/02/15 | 7:00 | 15:00 | 8:00 | 37,743.44 | 37,805.70 | 62,260 | 37,661,850 | |
| 12/03/15 | 9:00 | 15:15 | 6:15 | 37,805.70 | 37,863.53 | 57,830 | 37,719,680 | |
| 12/04/15 | 7:00 | 12:30 | 5:30 | 37,863.53 | 37,912.70 | 49,170 | 37,768,850 | |
| 12/06/15 | 12:00 | 14:00 | 2:00 | 37,912.70 | 37,958.66 | 45,960 | 37,814,810 | |
| 12/07/15 | 10:30 | 15:15 | 4:45 | 37,958.66 | 37,984.16 | 25,500 | 37,840,310 | |
| 12/08/15 | 11:00 | 14:30 | 3:30 | 37,984.16 | 38,016.05 | 31,890 | 37,872,200 | |
| 12/09/15 | 10:30 | 15:00 | 4:30 | 38,016.05 | 38,051.66 | 35,610 | 37,907,810 | |
| 12/10/15 | 8:00 | 15:15 | 7:15 | 38,051.66 | 38,176.63 | 124,970 | 38,032,780 | PVSC Compliance Sample Collected |
| 12/13/15 | 9:00 | 12:15 | 3:15 | 38,176.63 | 38,243.45 | 66,820 | 38,099,600 | |
| 12/14/15 | 13:45 | 15:30 | 1:45 | 38,243.45 | 38,278.63 | 35,180 | 38,134,780 | |
| 12/15/15 | 7:00 | 12:30 | 5:30 | 38,278.63 | 38,398.71 | 120,080 | 38,254,860 | |
| 12/16/15 | 11:30 | 15:30 | 4:00 | 38,398.71 | 38,456.74 | 58,030 | 38,312,890 | |
| 12/17/15 | 7:00 | 11:00 | 4:00 | 38,456.74 | 38,495.28 | 38,540 | 38,351,430 | |
| 12/18/15 | 8:00 | 15:15 | 7:15 | 38,495.28 | 38,587.27 | 91,990 | 38,443,420 | |
| 12/20/15 | 8:45 | 12:00 | 3:15 | 38,587.27 | 38,637.00 | 49,730 | 38,493,150 | |
| 12/21/15 | 7:30 | 13:00 | 5:30 | 38,637.00 | 38,700.54 | 63,540 | 38,556,690 | |
| 12/23/15 | 7:30 | 13:45 | 6:15 | 38,700.54 | 38,805.80 | 105,260 | 38,661,950 | |
| 12/24/15 | 8:00 | 15:00 | 7:00 | 38,805.80 | 38,835.49 | 29,690 | 38,691,640 | |
| 12/26/15 | 8:00 | 14:00 | 6:00 | 38,835.49 | 38,889.27 | 53,780 | 38,745,420 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

**MATERIAL TRACKING AND SAMPLING LOG**
**SA-6 North and South**

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| 3S cap material | <240 | 124-3S-EX-a,b,c,d (Excess 3S material) | 3500 | 124-3S-EX-a1 | 8/10/2015 | 12:10 | 51.6 | | Yes | |
| | | | | 124-3S-EX-a2 | 8/10/2015 | 12:15 | 18.6 | * | | |
| | | | | 124-3S-EX-a3 | 8/10/2015 | 12:18 | 37.1 | | Yes | |
| | | | | 124-3S-EX-a4 | 8/10/2015 | 12:20 | 18.9 | * | | |
| | | | | 124-3S-EX-b1 | 8/10/2015 | 12:21 | 24.8 | | Yes | |
| | | | | 124-3S-EX-b2 | 8/10/2015 | 12:22 | 49.3 | | Yes | |
| | | | | 124-3S-EX-b3 | 8/10/2015 | 12:23 | 37.9 | | Yes | |
| | | | | 124-3S-EX-b4 | 8/10/2015 | 12:24 | 40.4 | | Yes | |
| | | | | 124-3S-EX-c1 | 8/10/2015 | 12:25 | 24.7 | | Yes | |
| | | | | 124-3S-EX-c2 | 8/10/2015 | 12:26 | 36.3 | | Yes | |
| | | | | 124-3S-EX-c3 | 8/10/2015 | 12:27 | 46.7 | | Yes | |
| | | | | 124-3S-EX-c4 | 8/10/2015 | 12:28 | 8.1 | * | | |
| | | | | 124-3S-EX-d1 | 8/10/2015 | 12:29 | 25.6 | | Yes | |
| | | | | 124-3S-EX-d2 | 8/10/2015 | 12:30 | 32.1 | | Yes | |
| | | | | 124-3S-EX-d3 | 8/10/2015 | 12:31 | 74.6 | | Yes | |
| | | | | 124-3S-EX-d4 | 8/10/2015 | 12:32 | 34.7 | | Yes | |
| EA4 | <20 | 087-EA4-20-a (bermed/trench material) | 225 | 087-EA4-20-a1 | 9/11/2015 | 10:35 | 2 | Yes | | |
| | | | | 087-EA4-20-a2 | 9/11/2015 | 10:40 | <1.4 | Yes | | |
| | | | | 087-EA4-20-a3 | 9/11/2015 | 10:45 | <1.8 | Yes | | |
| | | | | 087-EA4-20-a4 | 9/11/2015 | 10:50 | 5.0 | Yes | | |
| EA-5 | <20 | 087-EA5-20-a1:b4 (stockpile of A material) | 1300 | 087-EA5-20-a1 | 9/11/2015 | 11:05 | 0.7 | Yes | | |
| | | | | 087-EA5-20-a2 | 9/11/2015 | 11:10 | <1.7 | Yes | | |
| | | | | 087-EA5-20-a3 | 9/11/2015 | 11:15 | <0.46 | Yes | | |
| | | | | 087-EA5-20-a4 | 9/11/2015 | 11:20 | <1.1 | Yes | | |
| | | | | 087-EA5-20-b1 | 9/11/2015 | 11:25 | <2.0 | Yes | | |
| | | | | 087-EA5-20-b2 | 9/11/2015 | 11:30 | 6.8 | Yes | | |
| | | | | 087-EA5-20-b3 | 9/11/2015 | 11:35 | 8.3 | Yes | | |
| | | | | 087-EA5-20-b4 | 9/11/2015 | 11:40 | <0.55 | Yes | | |
| EA-5 | <20 | 087-EA5-20-c1:d4 (stockpile of A material) | 2000 | 087-EA5-20-c1 | 9/11/2015 | 12:10 | <1.8 | * | | |
| | | | | 087-EA5-20-c2 | 9/11/2015 | 12:15 | <1.9 | * | | |
| | | | | 087-EA5-20-c3 | 9/11/2015 | 12:20 | <0.56 | * | | |
| | | | | 087-EA5-20-c4 | 9/11/2015 | 12:25 | <0.60 | * | | |
| | | | | 087-EA5-20-d1 | 9/11/2015 | 12:30 | <0.56 | * | | |
| | | | | 087-EA5-20-d2 | 9/11/2015 | 12:35 | <0.44 | * | | |
| | | | | 087-EA5-20-d3 | 9/11/2015 | 12:40 | <0.5 | * | | |
| | | | | 087-EA5-20-d4 | 9/11/2015 | 12:45 | 9.6 | * | | |
| 3S cap material | <240 | 124-3S-EX2-a | 780 | 124-3S-EX2-a1 | 9/28/2015 | -- | 50 | | Yes | |
| | | | | 124-3S-EX2-a2 | 9/28/2015 | -- | 48.5 | | Yes | |
| | | | | 124-3S-EX2-a3 | 9/28/2015 | -- | 82.3 | | Yes | |
| | | | | 124-3S-EX2-a4 | 9/28/2015 | -- | 785 | | | Yes |
| 3S Cap Material (under asphalt roadway) | <240 | 124-3S-Roadway-a | 525 | 124-3S-Roadway-a1 | 9/28/2015 | -- | 327 | | | Yes |
| | | | | 124-3S-Roadway-a2 | 9/28/2015 | -- | 2100 | | | Yes |
| | | | | 124-3S-Roadway-a3 | 9/28/2015 | -- | 1970 | | | Yes |
| | | | | 124-3S-Roadway-a4 | 9/28/2015 | -- | 5900 | | | Yes |
| JCMUA Water Main Break (EA-2) | <20 | 087-EA2-waterline | 50 | 087-EA2-waterline-092815 | 9/28/2015 | NA | 13.5 | * | | |
| 3S cap material | <240 | 124-3S-EX3-a | 1000 | 124-3S-EX3-a1 | 10/21/2015 | -- | 3120 | | | Yes |
| | | | | 124-3S-EX3-a2 | 10/21/2015 | -- | 6820 | | | Yes |
| | | | | 124-3S-EX3-a3 | 10/21/2015 | -- | 5690 | | | Yes |
| | | | | 124-3S-EX3-a4 | 10/21/2015 | -- | 4300 | | | Yes |

**MATERIAL TRACKING AND SAMPLING LOG**
**SA-6 North and South**


| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| 1N (2 foot cut material) | <20 | 087-1N-20-a, b, c | 3000 | 087-1N-20-a1 | 10/28/2015 | -- | <.5 | * | | |
| | | | | 087-1N-20-a2 | 10/28/2015 | -- | 2.1 | * | | |
| | | | | 087-1N-20-a3 | 10/28/2015 | -- | <.48 | * | | |
| | | | | 087-1N-20-a4 | 10/28/2015 | -- | 5.4 | * | | |
| | | | | 087-1N-20-b1 | 10/28/2015 | -- | 1.0 | * | | |
| | | | | 087-1N-20-b2 | 10/28/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-b3 | 10/28/2015 | -- | 0.65 | * | | |
| | | | | 087-1N-20-b4 | 10/28/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-c1 | 10/28/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-c2 | 10/28/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-c3 | 10/28/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-c4 | 10/28/2015 | -- | <.51 | * | | |
| 1 N (2 foot cut material) | <20 | 087-1N-20-d1:n4 | 11,160 | 087-1N-20-d1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-d2 | 11/17/2015 | -- | 9.5 | * | | |
| | | | | 087-1N-20-d3 | 11/17/2015 | -- | 19.9 | * | | |
| | | | | 087-1N-20-d4 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-e1 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-e2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-e3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-e4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-f1 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-f2 | 11/17/2015 | -- | <.93 | * | | |
| | | | | 087-1N-20-f3 | 11/17/2015 | -- | <.90 | * | | |
| | | | | 087-1N-20-f4 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-g1 | 11/17/2015 | -- | <.95 | * | | |
| | | | | 087-1N-20-g2 | 11/17/2015 | -- | <.86 | * | | |
| | | | | 087-1N-20-g3 | 11/17/2015 | -- | <.96 | * | | |
| | | | | 087-1N-20-g4 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-h1 | 11/17/2015 | -- | 1.9 | * | | |
| | | | | 087-1N-20-h2 | 11/17/2015 | -- | <.92 | * | | |
| | | | | 087-1N-20-h3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-h4 | 11/17/2015 | -- | <.92 | * | | |
| | | | | 087-1N-20-i1 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-i2 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-i3 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-i4 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-j1 | 11/17/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-j2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-j3 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-j4 | 11/17/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-k1 | 11/17/2015 | -- | <1.6 | * | | |
| 1 N (2 foot cut material) | <20 | 087-1N-20-d1:n4 | 11,160 | 087-1N-20-k2 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-k3 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-k4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-l1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-l2 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-l3 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-l4 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-m1 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-m2 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-m3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-m4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n3 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-n4 | 11/17/2015 | -- | <1.5 | * | | |

**MATERIAL TRACKING AND SAMPLING LOG**
**SA-6 North and South**

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA2/EA3 | <20 | 087-EA2-20-a (bermed/trench material) | 400 | 087-EA2-20-a1 | 12/11/2015 | -- | <1.8 | * | | |
| | | | | 087-EA2-20-a2 | 12/11/2015 | -- | 6.7 | * | | |
| | | | | 087-EA2-20-a3 | 12/11/2015 | -- | <1.9 | * | | |
| | | | | 087-EA2-20-a4 | 12/11/2015 | -- | 3.8 | * | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 1/15/2015 | | 5.0 | 5.6 | 7.0 | 5.5 | | 5.5 | 4.6 | 5.1 | 4.8 | 7.1 | 7.0 | 6.2 | 6.1 | 6.3 | | 5.2 | 5.0 | 6.4 | 5.8 | | |
| 1/30/2015 | | | 6.5 | 7.1 | 5.5 | | 3.6 | 2.4 | 5.1 | 4.8 | 6.7 | 6.5 | 6.1 | 6.0 | 6.3 | | | 3.2 | 4.9 | 4.6 | | 3.8 |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | 5.6 | 6.6 | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | | | | 4.5 | 5.0 | 3.8 | 3.5 | | | | | | |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | | | | 3.5 | 3.6 | | | | | | | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | | | | 5.2 | | | 4.6 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09

## Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-28
Date Exposed: 12/1/15
Describe Damage:

Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 12/3/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/3/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-29
Date Exposed: 12/1/15
Describe Damage:

Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/3/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/3/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-30
Date Exposed: 12/4/15
Describe Damage:

Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/11/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-31
Date Exposed: 12/4/15
Describe Damage:

Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/11/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6OP-32

Date Exposed: 12/4/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 12/11/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6OP-33

Date Exposed: 12/4/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the Sheet to the bottom of the excavation

Date Repaired: 12/11/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6OP-34

Date Exposed: 12/4/15

Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/11/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 6OP-35

Date Exposed: 12/4/15

Describe Damage: Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/11/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____

Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-36
Date Exposed: 12/14/15
Describe Damage:

Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 12/11/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/11/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-37
Date Exposed: 12/14/15
Describe Damage:

Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/17/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-38
Date Exposed: 12/14/15
Describe Damage:

Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/17/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-39
Date Exposed: 12/14/15
Describe Damage:

Epoxy scrapes along the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/17/15
Inspected by: A. Eslaminejad
Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-40
Date Exposed: 12/14/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the CAT 349 Excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/17/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-41
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the CAT 349 Excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of excavation

Date Repaired: 12/17/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-42
Date Exposed: 12/14/15
Describe Damage: Epoxy scrapes on the face of the sheet. Caused by the CAT 349 excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 12/17/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-43
Date Exposed: 12/14/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the CAT 349 Excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 12/17/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-44
Date Exposed: 12/14/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the CAT 349 Excavator bucket
Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation
Date Repaired: 12/17/15
Inspected by: A. Eslamiejad
Describe Repair: clean, grind, coat
Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-45
Date Exposed: 12/14/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the CAT 349 Excavator bucket
Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of excavation
Date Repaired: 12/17/15
Inspected by: A. Eslamiejad
Describe Repair: clean, grind, coat
Repair Log Closure: AMEC Signature: _____
Date: 12/17/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-46
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes on the face of the sheet. Caused by the CAT 349 excavator bucket
Damage Location (ft below top of sheet, inboard side outboard side): _____
Date Repaired: 12/22/15
Inspected by: A. Eslamiejad
Describe Repair: clean, grind, coat
Repair Log Closure: AMEC Signature: _____
Date: 12/22/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-47
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the CAT 349 Excavator bucket
Damage Location (ft below top of sheet, inboard side outboard side): _____
Date Repaired: 12/22/15
Inspected by: A. Eslamiejad
Describe Repair: clean, grind, coat
Repair Log Closure: AMEC Signature: _____
Date: 12/22/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-48
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the CAT 349 Excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/22/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/22/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-49
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes along the face of the sheet, caused by the CAT 349 Excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of excavation

Date Repaired: 12/22/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/22/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-50
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes on the face of the sheet. Caused by the CAT 349 excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 12/22/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/22/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____
Entact ID: 60P-51
Date Exposed: 12/17/15
Describe Damage: Epoxy scrapes on the face of the sheet, caused by the CAT 349 Excavator bucket

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: 12/22/15
Inspected by: A. Eslamnejad
Describe Repair: clean, grind, coat

Repair Log Closure: AMEC Signature: _____
Date: 12/22/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-24

Date Exposed: 12/1/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to bottom of excavation

Date Repaired: 12/3/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 12/3/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: 60P-25

Date Exposed: 12/1/15

Describe Damage: Epoxy scrapes on the face of the sheet, caused by the bucket of the 349 Excavator

Damage Location (ft below top of sheet, inboard side outboard side): Along the face of the sheet to the bottom of the excavation

Date Repaired: 12/3/15

Inspected by: A. Eslaminejad

Describe Repair: Clean, grind, coat

Repair Log Closure: AMEC Signature: [signature]

Date: 12/3/15

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____

Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

amec

SHEET PILE REPAIR LOG[1]

Sheet Number/DB ID: _____

Entact ID: _____

Date Exposed: _____

Describe Damage: _____

Damage Location (ft below top of sheet, inboard side outboard side): _____

Date Repaired: _____

Inspected by: _____

Describe Repair: _____


Repair Log Closure: AMEC Signature: _____

Date: _____

[1] A repair log is to be completed for each sheet pile section that is exposed and in need of repair.

# Attachment 11: Capping Update

- SA-6 South Cap Subgrade Progress Map




LEGEND

- GDL COVER SOIL PLACED
- GDL COVER SOIL GRADED AND APPROVED FOR HORIZON SOILS
- HORIZON C SOIL PLACED
- HORIZON C PLACED TO FINAL HORIZON C GRADE
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
12/28/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 04, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | | X | | 3 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/04/15

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
Friday, December 04, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Storm water has accumulated in the secondary containment structures in the mechanic's work area on SA-6 South. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing is inadequate at several locations around the EA-2/EA-3 excavations |
| 3 | IA2Q4A1AL8 | The Type A stockpile to the north of the EA-5 excavation area has overtopped the installed silt fencing to the north and to the west. |
| 4 | IA2Q4A1AL8 | The haul road to the north of the trash pit on SA-6 North is heavily coated with sediment and other material. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 12/04/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Drain accumulated storm water from secondary containment structures. | 12-11-15 MM |
| 2 | Maintain or replace EZ fencing as required to meet site requirements. | 12-11-15 MM |
| 3 | Re-install silt fence as required. | 12-11-15 MM |
| 4 | Clean the haul road and confirm that all catch basins in the area are properly protected from sediment run-off. | 12-7-15 MM |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 12/11/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 11, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/14/15

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, December 11, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has built up along the north side of Kellogg Street, west of the old guard shack |
| 2 | IA2Q4A1AL8 | REPEAT: The haul road to the north of the trash pit on SA-6 North is heavily coated with sediment and other material. |
| 3 | IA2Q4A1AL8 | Sediment and vehicle-tracked material has accumulated on the western SA-7 paved access roadway. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 12/14/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove accumulated sediment with flat shovels and/or brooms as required. | 12/15/15 R4D |
| 2 | Clean the haul road and confirm that all catch basins in the area are properly protected from sediment run-off. | |
| 3 | Remove accumulated sediment as required. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 12/16/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 18, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/21/15

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

Friday, December 18, 2015

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the SA-6 South perimeter fenceline is partially detached at several locations and requires maintenance. |
| 2 | IA2Q4A1AL8 | Trash and other debris has accumulated outside of the perimeter fence at the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | Some of the temporary fence panels between SA-6 North and the JCMUA property require stabilization or additional bracing. |
| 4 | IA2Q4A1AL8 | Sediment has accumulated on the SA-7 northern haul road. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 12/21/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach windscreen fabric to the perimeter fence as required | 12/23/15 RAD |
| 2 | Pick up and dispose of trash and other refuse as required. | |
| 3 | Re-enforce the temporary fence panels as required. | |
| 4 | Remove accumulated sediment as required. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 12/23/15

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 23, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/23/15

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Wednesday, December 23, 2015**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Temporary fence panels in the perimeter fenceline along the Kellogg Street jughandle are loose and require maintenance and/or reinforcement. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 12/23/15
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-secure temporary fence panels as required | 12/29/15 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 12/30/15

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted December 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

December 17, 2015

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the November 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 11 | 01 | 15 | 11 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,879 | 84,187 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYP |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAI |
| Chromium | Sample Measurement | 0.63 | 0.69 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00021 | 0.00021 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1603 | 0.1603 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

December 16, 2015

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North
**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962
**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305
**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 11 | 01 | 15 | 11 | 30 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,306,384 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 50,424,392 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 11/12/2015 | 4.9 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |

DATE December 16, 2015

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | | | | MONTH: November, 2015 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 11/1/2015 | Angel Trujillo | 48118008 | 48194250 | 76,242 | 0.076242 | 7.40 | 0.987 | | | | | | | | | 0.63 |
| 11/2/2015 | Angel Trujillo | 48194250 | 48270492 | 76,242 | 0.076242 | 7.46 | 0.987 | | | | | | | | | 0.63 |
| 11/3/2015 | Angel Trujillo | 48270492 | 48346040 | 75,548 | 0.075548 | 7.01 | 0.987 | | | | | | | | | 0.62 |
| 11/4/2015 | Angel Trujillo | 48346040 | 48422186 | 76,146 | 0.076146 | 7.02 | 0.987 | | | | | | | | | 0.63 |
| 11/5/2015 | Angel Trujillo | 48422186 | 48500024 | 77,838 | 0.077838 | 7.01 | 0.987 | | | | | | | | | 0.64 |
| 11/6/2015 | Angel Trujillo | 48500024 | 48577670 | 77,646 | 0.077646 | 7.04 | 0.987 | | | | | | | | | 0.64 |
| 11/7/2015 | Angel Trujillo | 48577670 | 48657202 | 79,532 | 0.079532 | 7.16 | 0.987 | | | | | | | | | 0.65 |
| 11/8/2015 | Angel Trujillo | 48657202 | 48731146 | 73,944 | 0.073944 | 6.95 | 0.987 | | | | | | | | | 0.61 |
| 11/9/2015 | Angel Trujillo | 48731146 | 48805090 | 73,944 | 0.073944 | 6.98 | 0.987 | | | | | | | | | 0.61 |
| 11/10/2015 | Angel Trujillo | 48805090 | 48883394 | 78,304 | 0.078304 | 6.99 | 0.987 | | | | | | | | | 0.64 |
| 11/11/2015 | Angel Trujillo | 48883394 | 48959110 | 75,716 | 0.075716 | 7.08 | 0.987 | | | | | | | | | 0.62 |
| 11/12/2015 | Angel Trujillo | 48959110 | 49034698 | 75,588 | 0.075588 | 6.70 | 0.987 | <5.0 | 4.9 | | <0.010 | <0.030 | <0.010 | 0.00021 | <0.020 | 0.62 |
| 11/13/2015 | Angel Trujillo | 49034698 | 49112107 | 77,409 | 0.077409 | 7.32 | 0.987 | | | | | | | | | 0.64 |
| 11/14/2015 | Angel Trujillo | 49112107 | 49196294 | 84,187 | 0.084187 | 7.00 | 0.987 | | | | | | | | | 0.69 |
| 11/15/2015 | Angel Trujillo | 49196294 | 49270042 | 73,748 | 0.073748 | 6.95 | 0.987 | | | | | | | | | 0.61 |
| 11/16/2015 | Angel Trujillo | 49270042 | 49343790 | 73,748 | 0.073748 | 7.04 | 0.987 | | | | | | | | | 0.61 |
| 11/17/2015 | Angel Trujillo | 49343790 | 49421208 | 77,418 | 0.077418 | 7.17 | 0.987 | | | | | | | | | 0.64 |
| 11/18/2015 | Angel Trujillo | 49421208 | 49496880 | 75,672 | 0.075672 | 7.28 | 0.987 | | | | | | | | | 0.62 |
| 11/19/2015 | Angel Trujillo | 49496880 | 49575270 | 78,390 | 0.07839 | 7.08 | 0.987 | | | | | | | | | 0.65 |
| 11/20/2015 | Angel Trujillo | 49575270 | 49652858 | 77,588 | 0.077588 | 7.06 | 0.987 | | | | | | | | | 0.64 |
| 11/21/2015 | Angel Trujillo | 49652858 | 49732407 | 79,549 | 0.079549 | 7.00 | 0.987 | | | | | | | | | 0.65 |
| 11/22/2015 | Angel Trujillo | 49732407 | 49811956 | 79,549 | 0.079549 | 7.02 | 0.987 | | | | | | | | | 0.65 |
| 11/23/2015 | Angel Trujillo | 49811956 | 49885156 | 73,200 | 0.0732 | 7.08 | 0.987 | | | | | | | | | 0.60 |
| 11/24/2015 | Angel Trujillo | 49885156 | 49959637 | 74,481 | 0.074481 | 7.09 | 0.987 | | | | | | | | | 0.61 |
| 11/25/2015 | Angel Trujillo | 49959637 | 50035893 | 76,256 | 0.076256 | 7.02 | 0.987 | | | | | | | | | 0.63 |
| 11/26/2015 | Angel Trujillo | 50035893 | 50116296 | 80,403 | 0.080403 | 6.95 | 0.987 | | | | | | | | | 0.66 |
| 11/27/2015 | Angel Trujillo | 50116296 | 50196699 | 80,403 | 0.0804 | 7.00 | 0.987 | | | | | | | | | 0.66 |
| 11/28/2015 | Angel Trujillo | 50196699 | 50277614 | 80,915 | 0.080915 | 6.97 | 0.987 | | | | | | | | | 0.67 |
| 11/29/2015 | Angel Trujillo | 50277614 | 50351003 | 73,389 | 0.073389 | 6.98 | 0.987 | | | | | | | | | 0.60 |
| 11/30/2015 | Angel Trujillo | 50351003 | 50424392 | 73,389 | 0.073389 | 6.95 | 0.987 | | | | | | | | | 0.60 |
| | | | | | | | | | | | | | | | | |
| **TOTAL** | | | | **2,306,384** | **2.306384** | | | <5.0 | 4.9 | | <0.010 | <0.030 | <0.010 | 0.00021 | <0.020 | |
| | | | **High:** | **84,187** | | | | | | | | | | | **High:** | **0.69** |
| | | | **Average:** | **76,879** | | | | | | | | | | | **Average:** | **0.63** |

Accutest LabLink@885056 10:46 01-Dec-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111215-A | | |
| **Lab Sample ID:** | JC8421-1 | **Date Sampled:** | 11/12/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 987 | 10 | ug/l | 1 | 11/13/15 | 11/15/15 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 11/13/15 | 11/15/15 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 11/13/15 | 11/16/15 | ND | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | 0.21 | 0.20 | ug/l | 1 | 11/14/15 | 11/14/15 | MA | EPA 245.1 [1] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 11/13/15 | 11/15/15 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 11/13/15 | 11/15/15 | GT | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA38049
(2) Instrument QC Batch: MA38050
(3) Instrument QC Batch: MA38068
(4) Prep QC Batch: MP90316
(5) Prep QC Batch: MP90345

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@885056 10:46 01-Dec-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111215-A | | |
| **Lab Sample ID:** | JC8421-1 | **Date Sampled:** | 11/12/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | < 4.0 | 4.0 | mg/l | 1 | 11/13/15 | LA | SM2540 D-11 |
| pH [b] | 6.82 | | su | 1 | 11/12/15 17:13 | HL | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 540 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@885056 10:46 01-Dec-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111215-A | | |
| **Lab Sample ID:** | JC8421-1A | **Date Sampled:** | 11/12/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 4.9 | 3.4 | mg/l | 1 | 11/12/15 21:27 | TT | SM5210 B-11 |

RL = Reporting Limit

Accutest LabLink@885056 10:46 01-Dec-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111215-B | | |
| **Lab Sample ID:** | JC8421-2 | **Date Sampled:** | 11/12/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | U200844.D | 1 | 11/17/15 | NH | n/a | n/a | VU9247 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.5 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.2 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.24 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 19.8 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.41 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.42 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 78.6 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 4.2 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.54 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@885056 10:46 01-Dec-2015

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111215-B | | |
| **Lab Sample ID:** | JC8421-2 | **Date Sampled:** | 11/12/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 50.4 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 97% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 99% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 102% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 99% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@885056 10:46 01-Dec-2015

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-111215-B | | |
| **Lab Sample ID:** | JC8421-2 | **Date Sampled:** | 11/12/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 11/12/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 11/16/15 17:40 | LS | EPA 1664A |

RL = Reporting Limit

WW

JC8421

# Honeywell — Chain Of Custody / Analysis Request

| Accutest Labs | | |

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending December 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending December 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |

**SA-6 North/South Field Change Log - Month Ending December 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the lIDPE up and over the SCB Wall. The prior detail showed both the GDI and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending December 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |

**SA-6 North/South Field Change Log - Month Ending December 2015**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D.<br>In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF.<br>This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals.<br>EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results.<br>Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits.<br>A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**2/9/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

February 11, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-01**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from January 1 – January 31, 2015.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: January 2015 SA-6/7 Combined Monthly Progress Report No. 2016-01

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-01

**Project SA-6 & 7 Remediation**

# January 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 01/14/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2015-12 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/14/16 | SA-6 North Chrome Remedy<br>Spark Testing of Liner Boots<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 01/19/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, JC<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 01/19/16 | Special Master Conference Call | n/a |
| 01/25/16 | Honeywell correspondence re: Surcharge Monitoring Plan – Monthly Report No. 14, Study Area 6 North and South | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/03/16 | 01/10/16 | 01/17/16 | 01/24/16 | 01/31/16 |
| **Construction Management (AMEC)** | 7 | 7 | 9 | 7 | 7 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 33 | 34 | 34 | 30 | 33 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 0 | 0 |
| **Langan** | 0 | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 | 1 |

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/03/16 | 01/10/16 | 01/17/16 | 01/24/16 | 01/31/16 |
| **B&B Drilling** | 0 | 0 | 1 | 1 | 0 |
| **Cornerstone** | 0 | 1 | 0 | 0 | 0 |
| **TOTAL STAFF** | **47** | **49** | **51** | **44** | **46** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected January PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Completed placement of asphalt associated with the PW-3 force main trench restoration.
- Completed acid cleaning of PW-3 line.
- Sampled discharge from PW-3 extraction well for analysis of selected indicator parameters (results will be reported when validated).

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on January 20, 2016. From January 24, 2016 to January 27, 2016 to, the GWTP was offline due to a faulty main service breaker. The system was fully restarted on January 27, 2016 at 3:40PM.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/03/16 | 01/10/16 | 01/17/16 | 01/24/16 | 01/31/16 |
| Avg. Gallons Treated & Discharged (per day) | 77,236 | 78,455 | 68,614 | 79,663 | 80,596 |
| Average Flow (gpm) for Operating Period | 53 | 56 | 56 | 57 | 60 |
| Avg. Hours of Plant Operation | 24 | 23 | 20 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 4,555 | 7,620 | 6,483 | 5,346 | 5,682 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.

- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued pumping/dewatering of well points associated with Excavation Areas EA-2 and EA-3.
- Continued dewatering and excavation activities of Site 163.
- Completed excavation of Excavation Areas EA-2 and EA-3.
- Continued backfilling of EA-2/EA-3 and the trash pit area.
- Began excavation of trench for installation of the Contingent Groundwater Extraction System piping in Area 1N.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Horwith** | Tri-axle | PA Transload | US Ecology | >240 mg/kg CrVI | 28 | 22.3 | 625 |
| **Entact/Horwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non-haz Cr | 59 | 25 | 1462 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | Excavation: EA-2/EA-3, Site 163<br>Volume Excavated - Total for Reporting Period (EA-2/EA-3): 3,847.5 CY/ Total to Date (SA-6 North): 38,403CY;<br>Total for Reporting period (Site 163): 4,342.5 CY/ Total to Date : 4,342.5 CY |
| **Backfill in Progress** | EA-2/EA-3 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 01/03/16 | 01/10/16 | 01/17/16 | 01/24/16 | 01/31/16 |
| Clayton Sand | 0 | 0 | 0 | 0 | 202 |
| Tilcon 2.5” | 0 | 0 | 0 | 255 | 0 |

- Screened Celgene materials greater than 3/8 inch were transferred and placed as bridge lift in EA-2/EA-3 and Site 163. In addition historic fill soils were transferred and placed as backfill in EA-2/EA-3.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.

- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.
- Area 2N: Completed offloading of area 2N.
- Area 3N: Completed placement of surcharge material.
- Area 4N: Completed placement of surcharge material.

## F. SHEET PILE OPERATIONS

- Completed installation of remaining hydraulic barrier sheeting on SA-6 North along Route 440. The subcontractor technician was on site for vibration monitoring over the sewer/water line during driving operations and no action levels were exceeded.
- Completed installation of sheeting within the former Trash Pit interior to include placement of Aqua Block bags to seal along bottom of sheeting and pit floor.
- Completed installation of grout tubes and bentonite at the connection of the former Trash Pit interior walls and the sheeting.
- Completed breaching of the pit concrete sidewalls in accordance with 100% Design.
- Completed removing temporary sheeting used along 440 and began installing these temporary sheets as needed for the Site 163 excavation.

## G. CAPPING OPERATIONS

- Continued evaluations of potential alternative fill source(s), of Horizon C Soils for the SA-6 South open space area.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete EA-2/EA-3 backfilling activities.
- Complete EA-1 excavation and backfilling activities.
- Continue dewatering and excavation activities associated with Site 163 excavation within the residential footprint including installation of temporary sheeting as needed.
- Continue installation of the Contingent Groundwater Extraction System piping in Area 1N.
- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.

- Pending identification of acceptable alternative fill source(s), resume import and placement of Horizon C Soils on the SA-6 South open space area.
- Continue routine surcharge monitoring in Areas 3N and 4N.
- Complete installation and grouting of the last special sheet pile barrier wall piece at the connection point of the SA-6 North barrier wall and the SCB wall at the southwestern portion of Area 1N.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data *(not included in this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update
11. Capping Update *(not included in this reporting period)*
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 1/31/16

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Breaking up former JCIA building pad.




**Site Photograph 2:** Excavating along Kellogg St. Site 163.



**Site Photograph 3:** Placement of bridge lift in excavation area.




**Site Photograph 4:** Removing portion of former trash pit walls.



**Site Photograph 5:** Sheet piling across former trash pit.





**Site Photograph 6:** Sheeting and Excavation along Kellogg St. Site 163.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of February 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-01
Attachment 3: Excavation and Backfill (Progression Chart)



# Attachment 4: Dewatering Operations Update

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) Daily | EXTRACTED VOLUME (Gal) Total | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 11/30/15 | 1 | 24 | 19,20 | 18 | N/A | N/A | 2,000 | 3,084,872 | 1.4 | EA-2/EA-3 Excvation |
| 12/01/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,086,672 | 1.3 | EA-2/EA-3 Excvation |
| 12/02/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,088,472 | 1.3 | EA-2/EA-3 Excvation |
| 12/03/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,090,272 | 1.3 | EA-2/EA-3 Excvation |
| 12/04/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,092,072 | 1.3 | EA-2/EA-3 Excvation |
| 12/06/15 | 1 | 48 | 19,20 | 14 | N/A | N/A | 3,000 | 3,095,072 | 1.0 | EA-2/EA-3 Excvation |
| 12/07/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,096,872 | 1.3 | EA-2/EA-3 Excvation |
| 12/08/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,098,672 | 1.3 | EA-2/EA-3 Excvation |
| 12/09/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,100,472 | 1.3 | EA-2/EA-3 Excvation |
| 12/10/15 | 1 | 24 | 19,20 | 14 | N/A | N/A | 1,800 | 3,102,272 | 1.3 | EA-2/EA-3 Excvation |
| 12/13/15 | 1 | 48 | 19,20 | 11 | N/A | N/A | 1,700 | 3,103,972 | 0.6 | EA-2/EA-3 Excvation |
| 12/14/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,105,672 | 1.2 | EA-2/EA-3 Excvation |
| 12/15/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,107,372 | 1.2 | EA-2/EA-3 Excvation |
| 12/16/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,109,072 | 1.2 | EA-2/EA-3 Excvation |
| 12/17/15 | 1 | 24 | 19,20 | 11 | N/A | N/A | 1,700 | 3,110,772 | 1.2 | EA-2/EA-3 Excvation |
| 12/18/15 | 1 | 24 | 19 | 10 | N/A | N/A | 1,700 | 3,112,472 | 1.2 | System Taken Offline |
| 01/14/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 5,000 | 3,117,472 | 3.5 | Site 163 |
| 01/15/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,122,472 | 3.5 | Site 163 |
| 01/18/16 | 1 | 72 | 22,23,24 | 23 | N/A | N/A | 15,000 | 3,137,472 | 3.5 | Site 163 |
| 01/19/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,142,472 | 3.5 | System Offline for Excavationn |

Notes: Previous information is truncated. Only last month and current month information is provided.

**STUDY AREA 6 NORTH DEEP WELL DATA (DW-6)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 12/06/15 | 48 | N/A | N/A | 10,000 | 10,000 | 3.5 | |
| 12/07/15 | 24 | N/A | N/A | 8,000 | 18,000 | 5.6 | |
| 12/08/15 | 24 | N/A | N/A | 8,000 | 26,000 | 5.6 | |
| 12/09/15 | 24 | N/A | N/A | 8,000 | 34,000 | 5.6 | |
| 12/10/15 | 24 | N/A | N/A | 10,000 | 44,000 | 6.9 | |
| 12/13/15 | 48 | N/A | N/A | 20,000 | 64,000 | 6.9 | |
| 12/14/15 | 24 | N/A | N/A | 10,000 | 74,000 | 6.9 | |
| 12/15/15 | 24 | N/A | N/A | 10,000 | 84,000 | 6.9 | |
| 12/16/15 | 24 | N/A | N/A | 10,000 | 94,000 | 6.9 | |
| 12/17/15 | 24 | N/A | N/A | 10,000 | 104,000 | 6.9 | |
| 12/18/15 | 24 | N/A | N/A | 10,000 | 114,000 | 6.9 | |
| 12/20/15 | 48 | N/A | N/A | 20,000 | 134,000 | 6.9 | |
| 12/21/15 | 24 | N/A | N/A | 10,000 | 144,000 | 6.9 | |
| 12/23/15 | 24 | N/A | N/A | 10,000 | 154,000 | 6.9 | |
| 12/24/15 | 24 | N/A | N/A | 10,000 | 164,000 | 6.9 | |
| 12/26/15 | 48 | N/A | N/A | 20,000 | 184,000 | 6.9 | |
| 12/28/15 | 48 | N/A | N/A | 20,000 | 204,000 | 6.9 | |
| 12/29/15 | 24 | N/A | N/A | 10,000 | 214,000 | 6.9 | |
| 12/30/15 | 24 | N/A | N/A | 10,000 | 224,000 | 6.9 | |
| 12/31/16 | 24 | N/A | N/A | 10,000 | 234,000 | 6.9 | |
| 01/04/16 | 96 | N/A | N/A | 40,000 | 274,000 | 6.9 | |
| 01/05/16 | 24 | N/A | N/A | 10,000 | 284,000 | 6.9 | Taken offline for excavation |

**STUDY AREA 6 NORTH DEEP WELL DATA (DW-7)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) Daily | VOLUME (Gal) Total | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 11/18/15 | 24 | N/A | N/A | 11,500 | 11,500 | 8.0 | Flow meter not installed, tank measured |
| 11/19/15 | 24 | N/A | N/A | 11,000 | 22,500 | 7.6 | |
| 11/20/15 | 24 | N/A | N/A | 11,000 | 33,500 | 7.6 | |
| 11/22/15 | 48 | N/A | N/A | 11,000 | 44,500 | 3.8 | |
| 11/23/15 | 24 | N/A | N/A | 11,000 | 55,500 | 7.6 | |
| 11/24/15 | 24 | N/A | N/A | 10,500 | 66,000 | 7.3 | |
| 11/25/15 | 24 | N/A | N/A | 10,500 | 76,500 | 7.3 | |
| 11/29/15 | 96 | N/A | N/A | 40,000 | 116,500 | 6.9 | |
| 11/30/15 | 24 | N/A | N/A | 10,500 | 127,000 | 7.3 | |
| 12/01/15 | 24 | N/A | N/A | 10,000 | 137,000 | 6.9 | |
| 12/02/15 | 24 | N/A | N/A | 10,000 | 147,000 | 6.9 | |
| 12/03/15 | 24 | N/A | N/A | 10,000 | 157,000 | 6.9 | |
| 12/04/15 | 24 | N/A | N/A | 12,000 | 169,000 | 8.3 | |
| 12/06/15 | 48 | N/A | N/A | 20,000 | 189,000 | 6.9 | |
| 12/07/15 | 24 | N/A | N/A | 8,000 | 197,000 | 5.6 | |
| 12/08/15 | 24 | N/A | N/A | 8,000 | 205,000 | 5.6 | |
| 12/09/15 | 24 | N/A | N/A | 8,000 | 213,000 | 5.6 | |
| 12/10/15 | 24 | N/A | N/A | 10,000 | 223,000 | 6.9 | |
| 12/13/15 | 48 | N/A | N/A | 20,000 | 243,000 | 6.9 | |
| 12/14/15 | 24 | N/A | N/A | 10,000 | 253,000 | 6.9 | |
| 12/15/15 | 24 | N/A | N/A | 10,000 | 263,000 | 6.9 | |
| 12/16/15 | 24 | N/A | N/A | 10,000 | 273,000 | 6.9 | |
| 12/17/15 | 24 | N/A | N/A | 10,000 | 283,000 | 6.9 | |
| 12/18/15 | 24 | N/A | N/A | 10,000 | 293,000 | 6.9 | |
| 12/20/15 | 48 | N/A | N/A | 20,000 | 313,000 | 6.9 | |
| 12/21/15 | 24 | N/A | N/A | 10,000 | 323,000 | 6.9 | Offline for Excavation/Backfill |

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 11/30/15 | 7:30 | 14:30 | 7:00 | 37,566.11 | 37,667.64 | 101,530 | 37,523,790 | |
| 12/01/15 | 8:00 | 15:15 | 7:15 | 37,667.64 | 37,743.44 | 75,800 | 37,599,590 | |
| 12/02/15 | 7:00 | 15:00 | 8:00 | 37,743.44 | 37,805.70 | 62,260 | 37,661,850 | |
| 12/03/15 | 9:00 | 15:15 | 6:15 | 37,805.70 | 37,863.53 | 57,830 | 37,719,680 | |
| 12/04/15 | 7:00 | 12:30 | 5:30 | 37,863.53 | 37,912.70 | 49,170 | 37,768,850 | |
| 12/06/15 | 12:00 | 14:00 | 2:00 | 37,912.70 | 37,958.66 | 45,960 | 37,814,810 | |
| 12/07/15 | 10:30 | 15:15 | 4:45 | 37,958.66 | 37,984.16 | 25,500 | 37,840,310 | |
| 12/08/15 | 11:00 | 14:30 | 3:30 | 37,984.16 | 38,016.05 | 31,890 | 37,872,200 | |
| 12/09/15 | 10:30 | 15:00 | 4:30 | 38,016.05 | 38,051.66 | 35,610 | 37,907,810 | |
| 12/10/15 | 8:00 | 15:15 | 7:15 | 38,051.66 | 38,176.63 | 124,970 | 38,032,780 | PVSC Compliance Sample Collected |
| 12/13/15 | 9:00 | 12:15 | 3:15 | 38,176.63 | 38,243.45 | 66,820 | 38,099,600 | |
| 12/14/15 | 13:45 | 15:30 | 1:45 | 38,243.45 | 38,278.63 | 35,180 | 38,134,780 | |
| 12/15/15 | 7:00 | 12:30 | 5:30 | 38,278.63 | 38,398.71 | 120,080 | 38,254,860 | |
| 12/16/15 | 11:30 | 15:30 | 4:00 | 38,398.71 | 38,456.74 | 58,030 | 38,312,890 | |
| 12/17/15 | 7:00 | 11:00 | 4:00 | 38,456.74 | 38,495.28 | 38,540 | 38,351,430 | |
| 12/18/15 | 8:00 | 15:15 | 7:15 | 38,495.28 | 38,587.27 | 91,990 | 38,443,420 | |
| 12/20/15 | 8:45 | 12:00 | 3:15 | 38,587.27 | 38,637.00 | 49,730 | 38,493,150 | |
| 12/21/15 | 7:30 | 13:00 | 5:30 | 38,637.00 | 38,700.54 | 63,540 | 38,556,690 | |
| 12/23/15 | 7:30 | 13:45 | 6:15 | 38,700.54 | 38,805.80 | 105,260 | 38,661,950 | |
| 12/24/15 | 8:00 | 15:00 | 7:00 | 38,805.80 | 38,835.49 | 29,690 | 38,691,640 | |
| 12/26/15 | 8:00 | 14:00 | 6:00 | 38,835.49 | 38,889.27 | 53,780 | 38,745,420 | |
| 12/28/15 | 7:00 | 15:30 | 8:30 | 38,889.27 | 39,029.27 | 140,000 | 38,885,420 | |
| 12/30/15 | 7:15 | 14:30 | 7:15 | 39,029.27 | 39,125.05 | 95,780 | 38,981,200 | |
| 12/31/16 | 7:00 | 13:45 | 6:45 | 39,125.05 | 39,167.86 | 42,810 | 39,024,010 | |
| 01/04/16 | 7:30 | 16:15 | 8:45 | 39,167.86 | 39,269.10 | 101,240 | 39,125,250 | |
| 01/07/16 | 8:00 | 16:15 | 8:15 | 39,269.10 | 39,354.16 | 85,060 | 39,210,310 | |
| 01/11/16 | 7:30 | 14:00 | 6:30 | 39,354.16 | 39,425.93 | 71,770 | 39,282,080 | |
| 01/12/16 | 8:00 | 13:00 | 5:00 | 39,425.93 | 39,510.66 | 84,730 | 39,366,810 | PVSC Compliance Sample Collected |
| 01/14/16 | 9:30 | 14:00 | 4:30 | 39,510.66 | 39,562.31 | 51,650 | 39,418,460 | |
| 02/01/16 | 7:30 | 13:15 | 5:45 | 39,562.31 | 39,632.04 | 69,730 | 39,488,190 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data


| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| 3S cap material | <240 | 124-3S-EX-a,b,c,d (Excess 3S material) | 3500 | 124-3S-EX-a1 | 8/10/2015 | 12:10 | 51.6 | | Yes | |
| | | | | 124-3S-EX-a2 | 8/10/2015 | 12:15 | 18.6 | * | | |
| | | | | 124-3S-EX-a3 | 8/10/2015 | 12:18 | 37.1 | | Yes | |
| | | | | 124-3S-EX-a4 | 8/10/2015 | 12:20 | 18.9 | * | | |
| | | | | 124-3S-EX-b1 | 8/10/2015 | 12:21 | 24.8 | | Yes | |
| | | | | 124-3S-EX-b2 | 8/10/2015 | 12:22 | 49.3 | | Yes | |
| | | | | 124-3S-EX-b3 | 8/10/2015 | 12:23 | 37.9 | | Yes | |
| | | | | 124-3S-EX-b4 | 8/10/2015 | 12:24 | 40.4 | | Yes | |
| | | | | 124-3S-EX-c1 | 8/10/2015 | 12:25 | 24.7 | | Yes | |
| | | | | 124-3S-EX-c2 | 8/10/2015 | 12:26 | 36.3 | | Yes | |
| | | | | 124-3S-EX-c3 | 8/10/2015 | 12:27 | 46.7 | | Yes | |
| | | | | 124-3S-EX-c4 | 8/10/2015 | 12:28 | 8.1 | * | | |
| | | | | 124-3S-EX-d1 | 8/10/2015 | 12:29 | 25.6 | | Yes | |
| | | | | 124-3S-EX-d2 | 8/10/2015 | 12:30 | 32.1 | | Yes | |
| | | | | 124-3S-EX-d3 | 8/10/2015 | 12:31 | 74.6 | | Yes | |
| | | | | 124-3S-EX-d4 | 8/10/2015 | 12:32 | 34.7 | | Yes | |
| EA-5 | <20 | 087-EA5-20-c1:d4 (stockpile of A material) | 2000 | 087-EA5-20-c1 | 9/11/2015 | 12:10 | <1.8 | Yes | | |
| | | | | 087-EA5-20-c2 | 9/11/2015 | 12:15 | <1.9 | Yes | | |
| | | | | 087-EA5-20-c3 | 9/11/2015 | 12:20 | <0.56 | Yes | | |
| | | | | 087-EA5-20-c4 | 9/11/2015 | 12:25 | <0.60 | Yes | | |
| | | | | 087-EA5-20-d1 | 9/11/2015 | 12:30 | <0.56 | Yes | | |
| | | | | 087-EA5-20-d2 | 9/11/2015 | 12:35 | <0.44 | Yes | | |
| | | | | 087-EA5-20-d3 | 9/11/2015 | 12:40 | <0.5 | Yes | | |
| | | | | 087-EA5-20-d4 | 9/11/2015 | 12:45 | 9.6 | Yes | | |
| JCMUA Water Main Break (EA-2) | <20 | 087-EA2-waterline | 50 | 087-EA2-waterline-092815 | 9/28/2015 | NA | 13.5 | * | | |
| 1N (2 foot cut material) | <20 | 087-1N-20-a, b, c | 3000 | 087-1N-20-a1 | 10/28/2015 | -- | <.5 | * | | |
| | | | | 087-1N-20-a2 | 10/28/2015 | -- | 2.1 | * | | |
| | | | | 087-1N-20-a3 | 10/28/2015 | -- | <.48 | * | | |
| | | | | 087-1N-20-a4 | 10/28/2015 | -- | 5.4 | * | | |
| | | | | 087-1N-20-b1 | 10/28/2015 | -- | 1.0 | * | | |
| | | | | 087-1N-20-b2 | 10/28/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-b3 | 10/28/2015 | -- | 0.65 | * | | |
| | | | | 087-1N-20-b4 | 10/28/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-c1 | 10/28/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-c2 | 10/28/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-c3 | 10/28/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-c4 | 10/28/2015 | -- | <.51 | * | | |
| 1 N (2 foot cut material) | <20 | 087-1N-20-d1:n4 | 11,160 | 087-1N-20-d1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-d2 | 11/17/2015 | -- | 9.5 | * | | |
| | | | | 087-1N-20-d3 | 11/17/2015 | -- | 19.9 | * | | |
| | | | | 087-1N-20-d4 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-e1 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-e2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-e3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-e4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-f1 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-f2 | 11/17/2015 | -- | <.93 | * | | |
| | | | | 087-1N-20-f3 | 11/17/2015 | -- | <.90 | * | | |
| | | | | 087-1N-20-f4 | 11/17/2015 | -- | <1.5 | * | | |
| | | | | 087-1N-20-g1 | 11/17/2015 | -- | <.95 | * | | |
| | | | | 087-1N-20-g2 | 11/17/2015 | -- | <.86 | * | | |
| | | | | 087-1N-20-g3 | 11/17/2015 | -- | <.96 | * | | |
| | | | | 087-1N-20-g4 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-h1 | 11/17/2015 | -- | 1.9 | * | | |

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| | | | | 087-1N-20-h2 | 11/17/2015 | -- | <.92 | * | | |
| | | | | 087-1N-20-h3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-h4 | 11/17/2015 | -- | <.92 | * | | |
| | | | | 087-1N-20-i1 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-i2 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-i3 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-i4 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-j1 | 11/17/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-j2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-j3 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-j4 | 11/17/2015 | -- | <1.8 | * | | |
| | | | | 087-1N-20-k1 | 11/17/2015 | -- | <1.6 | * | | |
| 1 N (2 foot cut material) | <20 | 087-1N-20-d1:n4 | 11,160 | 087-1N-20-k2 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-k3 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-k4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-l1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-l2 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-l3 | 11/17/2015 | -- | <2.0 | * | | |
| | | | | 087-1N-20-l4 | 11/17/2015 | -- | <2.1 | * | | |
| | | | | 087-1N-20-m1 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-m2 | 11/17/2015 | -- | <1.9 | * | | |
| | | | | 087-1N-20-m3 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-m4 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n1 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n2 | 11/17/2015 | -- | <1.4 | * | | |
| | | | | 087-1N-20-n3 | 11/17/2015 | -- | <1.3 | * | | |
| | | | | 087-1N-20-n4 | 11/17/2015 | -- | <1.5 | * | | |
| EA2/EA3 | <20 | 087-EA2-20-a (bermed/trench material) | 400 | 087-EA2-20-a1 | 12/11/2015 | -- | <1.8 | Yes | | |
| | | | | 087-EA2-20-a2 | 12/11/2015 | -- | 6.7 | Yes | | |
| | | | | 087-EA2-20-a3 | 12/11/2015 | -- | <1.9 | Yes | | |
| | | | | 087-EA2-20-a4 | 12/11/2015 | -- | 3.8 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-b1:g1 (A material) | 5200 cy | 087-EA2-20-b1 | 12/30/2015 | -- | 3.0 | Yes | | |
| | | | | 087-EA2-20-b2 | 12/30/2015 | -- | 3.0 | Yes | | |
| | | | | 087-EA2-20-b3 | 12/30/2015 | -- | 0.55 | Yes | | |
| | | | | 087-EA2-20-b4 | 12/30/2015 | -- | 0.97 | Yes | | |
| | | | | 087-EA2-20-c1 | 12/30/2015 | -- | 4.3 | Yes | | |
| | | | | 087-EA2-20-c2 | 12/30/2015 | -- | 1.5 | Yes | | |
| | | | | 087-EA2-20-c3 | 12/30/2015 | -- | 1.6 | Yes | | |
| | | | | 087-EA2-20-c4 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-d1 | 12/30/2015 | -- | 0.60 | Yes | | |
| | | | | 087-EA2-20-d2 | 12/30/2015 | -- | 15.9 | Yes | | |
| | | | | 087-EA2-20-d3 | 12/30/2015 | -- | 5.4 | Yes | | |
| | | | | 087-EA2-20-d4 | 12/30/2015 | -- | 1.7 | Yes | | |
| | | | | 087-EA2-20-e1 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-e2 | 12/30/2015 | -- | 12.3 | Yes | | |
| | | | | 087-EA2-20-e3 | 12/30/2015 | -- | 3.1 | Yes | | |
| | | | | 087-EA2-20-e4 | 12/30/2015 | -- | 0.57 | Yes | | |
| | | | | 087-EA2-20-f1 | 12/30/2015 | -- | 0.52 | Yes | | |
| | | | | 087-EA2-20-f2 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-f3 | 12/30/2015 | -- | 0.57 | Yes | | |
| | | | | 087-EA2-20-f4 | 12/30/2015 | -- | 0.54 | Yes | | |
| | | | | 087-EA2-20-g1 | 12/30/2015 | -- | 0.53 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-h1 (overburden) | 150 cy | 087-EA2-20-h1 | 12/30/2015 | -- | 0.7 | * | | |
| EA2/EA3 | <20 | 087-EA2-20-i1 (overburden) | 200 cy | 087-EA2-20-i1 | 12/30/2015 | -- | 0.54 | Yes | | |

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA2/EA3 | <20 | 087-EA2-20-h2:j3 (overburden) | 2200 cy | 087-EA2-20-h2 | 1/8/2016 | -- | 24.1 | | * | |
| | | | | 087-EA2-20-h3 | 1/8/2016 | -- | <1.4 | Yes | | |
| | | | | 087-EA2-20-h4 | 1/8/2016 | -- | 19 | Yes | | |
| | | | | 087-EA2-20-i2 | 1/8/2016 | -- | 0.66 | Yes | | |
| | | | | 087-EA2-20-i3 | 1/8/2016 | -- | <1.9 | Yes | | |
| | | | | 087-EA2-20-i4 | 1/8/2016 | -- | <1.4 | Yes | | |
| | | | | 087-EA2-20-j1 | 1/8/2016 | -- | <2.0 | Yes | | |
| | | | | 087-EA2-20-j2 | 1/8/2016 | -- | 8.9 | Yes | | |
| | | | | 087-EA2-20-j3 | 1/8/2016 | -- | <1.9 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-k1:k4 | 1000 cy | 087-EA2-20-k1 | 1/8/2016 | -- | 7 | Yes | | |
| | | | | 087-EA2-20-k2 | 1/8/2016 | -- | 10 | Yes | | |
| | | | | 087-EA2-20-k3 | 1/8/2016 | -- | 8 | Yes | | |
| | | | | 087-EA2-20-k4 | 1/8/2016 | -- | <1.9 | Yes | | |
| Site 163 | <20 | 163-20-a | 840 | 163-20-a1 | 1/19/2016 | -- | 8.1 | * | | |
| | | | | 163-20-a2 | 1/19/2016 | -- | 4.0 | * | | |
| | | | | 163-20-a3 | 1/19/2016 | -- | 1.7 | * | | |
| | | | | 163-20-a4 | 1/19/2016 | u | 5.0 | * | | |

*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


# STUDY AREA 7
# PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 2/11/2015 | 3.8 | | 6.5 | 6.7 | 6.4 | | 3.1 | 2.9 | | 4.7 | 6.8 | 6.5 | 6.1 | 6.1 | 6.2 | | 2.1 | | 4.4 | 3.9 | 3.8 | 3.7 |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | 5.6 | 6.6 | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | | | | 4.5 | 5.0 | 3.8 | 3.5 | | | | | | |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | | | | 3.5 | 3.6 | | | | | | | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | | | | 5.2 | | | 4.6 | | | | | | |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | | | | 6.0 | | | 5.6 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, E4-SO, W1-SO, North FS-6, North FS-7


# Attachment 8: Groundwater Quality Data


(not included in this reporting period)


## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update


EXISTING JCIA TRASH PIT
CONSERVATION EASEMENT
HYDRAULIC BARRIER (TYP)
STA. 0+00 TO 5+00 SEE SPECIAL INSTRUCTIONS FOR SEALING SHEETS, SEE NOTE HB19 ON SHEET GN-004
SEE NOTE HB21 ON SHEET GN-003
NEW JERSEY STATE HIGHWAY ROUTE 440
MATCH LINE, SHEET SN-202
GEOMEMBRANE GRADE CONTOURS (TYP)
HORIZONTAL SCALE
EXISTING SOIL CEMENT BENTONITE WALL
HYDRAULIC BARRIER AND SLURRY CEMENT BENTONITE WALL CONNECTION SN-201 SN-301
NOTES:
1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-005, NOTE HB17 AND DETAIL E ON SHEET GN-501 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.
HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE
NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700
STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700
NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700
NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700
STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N
NON STRUCTURAL | 8+64 | 9+85 | -8 | AZ 19-700
Corner + 1 pair
1/4/16
Special 4/29/15
5/5/15
EXISTING GRADE
JCIA BUILDING
TYPICAL UTILITY CORRIDOR/ HYDRAULIC BARRIER WALL CROSSING DETAIL
SN-201 SN-301
STA. 3+66 JCIA TRASH PIT
STA. 3+80 JCIA TRASH PIT
GEOMEMBRANE GRADE
HISTORIC FILL
SITE HISTORIC WATER TABLE (SEE NOTE 3)
STRATUM O
STRATUM D
STRATUM S1
JCIA TRASH PIT SEE NOTE JC2 ON SHEET GN-004
STA. 0+00 TO STA 5+00 SPECIAL INSTRUCTIONS FOR SEALING SHEETS SEE NOTE HB19 ON SHEET GN-004
Time frame for HB sheets driven
HORIZONTAL SCALE
VERTICAL SCALE
SCALE IN FEET
Honeywell
CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
DRAWING STATUS
100 PERCENT DESIGN DRAWINGS
HYDRAULIC BARRIER PLAN AND PROFILE
amec
VERIFY SCALE
DATE
PROJ 3480-12-0317
DWG SN-201
SHEET 54 OF 70




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/13/13 | TDD | RJR | TDD | BCO |
| 0 | 06/07/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | RJR | SGS |
| | | ISSUED FOR CONSTRUCTION | | TDD | SGS |
| | | REVISION | | BY | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N-100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | TDD | DR RJR CHK TDD | APVD | SGS |

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA27915600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Capping Update

(not included in this reporting period)

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: December 31, 2015

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 1 |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 12/7/15

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Thursday, December 31, 2015

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Secondary containment structures in the mechanic's area have accumulated stormwater. |
| 2 | IA2Q4A1AL8 | Ponded stormwater is present at several locations across SA-6 South. |
| 3 | IA2Q4A1AL8 | Ponded stormwater is present at several locations across SA-6 North. |
| 4 | IA2Q4A1AL8 | The northern SA-7 access roadway has accumulated mud and sediment from the surcharge operation. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 12/31/15

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Drain stormwater from the secondary containment structures. | |
| 2 | Pump ponded stormwater as required. | Frozen |
| 3 | Pump ponded stormwater as required. | |
| 4 | Clean the access roadway and remove all accumulated sediment. | RAD 1/6/16 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/07/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 8, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 01/11/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, January 08, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence along the northern SA-7 access roadway requires maintenance. |
| 2 | IA2Q4A1AL8 | Repeat: The northern SA-7 access roadway has accumulated mud and sediment from the surcharge operation. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 01/11/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace silt fence as required. | will be completed when ground is not frozen |
| 2 | Clean the access roadway and remove all accumulated sediment. | 1/12/16 and daily activity |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/14/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 15, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 01/15/16

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, January 15, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence on Study Area 6 South has become detached. |
| 2 | IA2Q4A1AL8 | The silt bag at the west end of Kellogg Street which filters sediment from the diesel pump has become blinded with sediment. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 01/15/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the perimeter fenceline windscreen where it has become detached from the fence. | 1/20/16 (AD) |
| 2 | Replace the silt bag on the diesel pump hose on Study Area 6 South. | 1/20/16 (AD) |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/20/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: January 22, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 01/22/16

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, January 22, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence on Study Area 6 South has become detached |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 01/22/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the perimeter fenceline windscreen where it has become detached from the fence. | 1/26/16 RAM |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 01/26/16

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted January 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

January 19, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the December 2015 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 12 | 01 | 15 | 12 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 59,770 | 78,659 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.47 | 0.61 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.00020 | <0.00020 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1486 | 0.1486 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris
Signature of Principal
Executive or Authorized Agent

John J. Morris
Remediation Portfolio Director
Type Name and Title

01/19/2016
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 12 | 01 | 15 | 12 | 31 | 15 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 1,852,869 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 52,277,261 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 12/8/2015 | <13 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE 01/19/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: December 2015 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 12/1/2015 | Angel Trujillo | 50424392 | 50500018 | 75,626 | 0.075626 | 7.02 | 0.935 | | | | | | | | | 0.59 |
| 12/2/2015 | Angel Trujillo | 50500018 | 50577106 | 77,088 | 0.077088 | 7.34 | 0.935 | | | | | | | | | 0.60 |
| 12/3/2015 | Angel Trujillo | 50577106 | 50652921 | 75,815 | 0.075815 | 7.39 | 0.935 | | | | | | | | | 0.59 |
| 12/4/2015 | Angel Trujillo | 50652921 | 50731580 | 78,659 | 0.078659 | 7.40 | 0.935 | | | | | | | | | 0.61 |
| 12/5/2015 | Angel Trujillo | 50731580 | 50809695 | 78,115 | 0.078115 | 7.30 | 0.935 | | | | | | | | | 0.61 |
| 12/6/2015 | Angel Trujillo | 50809695 | 50887810 | 78,115 | 0.078115 | 7.43 | 0.935 | | | | | | | | | 0.61 |
| 12/7/2015 | Angel Trujillo | 50887810 | 50962084 | 74,274 | 0.074274 | 7.42 | 0.935 | | | | | | | | | 0.58 |
| 12/8/2015 | Angel Trujillo | 50962084 | 51038112 | 76,028 | 0.076028 | 6.78 | 0.935 | <5.1 | <13 | | <0.010 | <0.030 | <0.010 | <0.00020 | <0.020 | 0.59 |
| 12/9/2015 | Angel Trujillo | 51038112 | 51114910 | 76,798 | 0.076798 | 7.42 | 0.935 | | | | | | | | | 0.60 |
| 12/10/2015 | Angel Trujillo | 51114910 | 51176568 | 61,658 | 0.061658 | 7.22 | 0.935 | | | | | | | | | 0.48 |
| 12/11/2015 | Angel Trujillo | 51176568 | 51231814 | 55,246 | 0.055246 | 7.41 | 0.935 | | | | | | | | | 0.43 |
| 12/12/2015 | Angel Trujillo | 51231814 | 51287230 | 55,416 | 0.055416 | 7.39 | 0.935 | | | | | | | | | 0.43 |
| 12/13/2015 | Angel Trujillo | 51287230 | 51359830 | 72,600 | 0.0726 | 7.30 | 0.935 | | | | | | | | | 0.57 |
| 12/14/2015 | Angel Trujillo | 51359830 | 51432430 | 72,600 | 0.0726 | 7.42 | 0.935 | | | | | | | | | 0.57 |
| 12/15/2015 | Angel Trujillo | 51432430 | 51466202 | 33,772 | 0.033772 | 7.64 | 0.935 | | | | | | | | | 0.26 |
| 12/16/2015 | Angel Trujillo | 51466202 | 51519186 | 52,984 | 0.052984 | 7.63 | 0.935 | | | | | | | | | 0.41 |
| 12/17/2015 | Angel Trujillo | 51519186 | 51589110 | 69,924 | 0.069924 | 7.84 | 0.935 | | | | | | | | | 0.55 |
| 12/18/2015 | Angel Trujillo | 51589110 | 51657980 | 68,870 | 0.06887 | 7.58 | 0.935 | | | | | | | | | 0.54 |
| 12/19/2015 | Angel Trujillo | 51657980 | 51730250 | 72,270 | 0.07227 | 7.61 | 0.935 | | | | | | | | | 0.56 |
| 12/20/2015 | Angel Trujillo | 51730250 | 51799873 | 69,623 | 0.069623 | 7.40 | 0.935 | | | | | | | | | 0.54 |
| 12/21/2015 | Angel Trujillo | 51799873 | 51869497 | 69,624 | 0.069624 | 7.54 | 0.935 | | | | | | | | | 0.54 |
| 12/22/2015 | Angel Trujillo | 51869497 | 51937069 | 67,572 | 0.067572 | 7.59 | 0.935 | | | | | | | | | 0.53 |
| 12/23/2015 | Angel Trujillo | 51937069 | 52013772 | 76,703 | 0.076703 | 7.57 | 0.935 | | | | | | | | | 0.60 |
| 12/24/2015 | Angel Trujillo | 52013772 | 52054400 | 40,628 | 0.040628 | 7.82 | 0.935 | | | | | | | | | 0.32 |
| 12/25/2015 | Angel Trujillo | 52054400 | 52054400 | 0 | 0 | N/A | 0.935 | | | | | | | | | 0.00 |
| 12/26/2015 | Angel Trujillo | 52054400 | 52054400 | 0 | 0 | N/A | 0.935 | | | | | | | | | 0.00 |
| 12/27/2015 | Angel Trujillo | 52054400 | 52054400 | 0 | 0 | N/A | 0.935 | | | | | | | | | 0.00 |
| 12/28/2015 | Angel Trujillo | 52054400 | 52054400 | 0 | 0 | N/A | 0.935 | | | | | | | | | 0.00 |
| 12/29/2015 | Angel Trujillo | 52054400 | 52125809 | 71,409 | 0.071409 | 7.52 | 0.935 | | | | | | | | | 0.56 |
| 12/30/2015 | Angel Trujillo | 52125809 | 52202753 | 76,944 | 0.076944 | 7.47 | 0.935 | | | | | | | | | 0.60 |
| 12/31/2015 | Angel Trujillo | 52202753 | 52277261 | 74,508 | 0.074508 | 7.56 | 0.935 | | | | | | | | | 0.58 |
| TOTAL | | | | 1,852,869 | 1.852869 | | | <5.1 | <13 | | <0.010 | <0.030 | <0.010 | <0.00020 | <0.020 | |
| | | | High: | 78,659 | | | | | | | | | | | High: | 0.61 |
| | | | Average: | 59,770 | | | | | | | | | | | Average: | 0.47 |

WW

Impulse

E

TC10089

**Accutest Labs**
2235 ROUTE 130
Dayton, NJ 8810
732-329-0200

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 42346.39172
COC#: 087-WW-120815

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Privileged & Confidential | | | Site Name: | Hudson County | Phase: | CS | Lab Proj # (SDG): |
| EDD To: | | | Location of Site: | Jersey City, NJ | Sampling Program | 087: JCIA | Lab ID: ACTD |
| Sampling Co.: MACTEC | | | | | | | Site ID: HudsonCo |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | | | | Lab Job #: HWINJM32815 |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | | | | | | Authorized User: Honeywell |
| Honeywell International | Analysis Turnaround Time (TAT): | 3 | | | | | |
| 101 Columbia Road Morristown, NJ 07962 | Consultant | CH2M | | | | | |
| Preliminary Data To | | | | | | | Text & Excel File Drive: L23 A18 V1077 G42 |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | | | | Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: | 28 Days | | | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | | | | |

Copyright AESI; Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs: see attached special list | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-120815-A | 12/8/2015 | 15:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | | -1 |
| 2 | 087-WW | | | 087-WWE-120815-B | 12/8/2015 | 15:05 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | | -2 |
| 3 | 087-WW | | | 087-WWI-120815 | 12/8/2015 | 15:15 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | | -3 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | |

INITIAL ASESSMENT SA JK

LABEL VERIFICATION JK

ALL SAMPLES RECEIVED
PRESERVED AS APPLICABLE
JK

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: pH = 6.78 s.u. @ 7.9°C | Company: AMEC Foster Wheeler | Received by: | Company: | | Condition: | | Custody Seals Intact: |
| Frank Schroyer | Date/Time: 12/8/15 | Robert Chambers | Date/Time: 12-8-15 16:26 | | Cooler Temp. | 1.5°C | |
| Relinquished by: Robert Chambers | Company: | Received by: | Company: | | Condition: | | Custody Seals Intact: |
| | Date/Time: 12-8-15 16:26 | | Date/Time: 12-8-15 | | Cooler Temp. | | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

Relinquished by LC 12.8.15 8:34 Received by Jane Yua 12/8/15 18:34

Accutest LabLink@891489 18:36 14-Jan-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120815-A | | |
| **Lab Sample ID:** | JC10089-1 | **Date Sampled:** | 12/08/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/08/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 935 | 10 | ug/l | 1 | 12/09/15 | 12/10/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 12/09/15 | 12/10/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 12/09/15 | 12/10/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 12/11/15 | 12/11/15 | MA | EPA 245.1 [2] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 12/09/15 | 12/10/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 12/09/15 | 12/10/15 | ND | EPA 200.7 [1] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA38252
(2) Instrument QC Batch: MA38262
(3) Prep QC Batch: MP90841
(4) Prep QC Batch: MP90894

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@891489 18:36 14-Jan-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120815-A | | |
| **Lab Sample ID:** | JC10089-1 | **Date Sampled:** | 12/08/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/08/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | < 4.0 | 4.0 | mg/l | 1 | 12/09/15 | LA | SM2540 D-11 |
| pH [b] | 6.92 | | su | 1 | 12/08/15 19:38 | JK | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 500 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@891489 18:36 14-Jan-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120815-A | | |
| **Lab Sample ID:** | JC10089-1A | **Date Sampled:** | 12/08/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/08/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.2
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 13 | 13 | mg/l | 1 | 12/09/15 19:54 | LS | SM5210 B-11 |

RL = Reporting Limit

Accutest LabLink@891489 18:36 14-Jan-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120815-B | | |
| **Lab Sample ID:** | JC10089-2 | **Date Sampled:** | 12/08/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/08/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | T213774.D | 1 | 12/09/15 | DC | n/a | n/a | VT8773 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.3 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.0 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.23 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 20.3 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.42 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.44 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 71.2 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.5 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.57 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@891489 18:36 14-Jan-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120815-B | | |
| **Lab Sample ID:** | JC10089-2 | **Date Sampled:** | 12/08/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/08/15 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 46.6 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 105% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 98% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 98% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 106% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@891489 18:36 14-Jan-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-120815-B | | |
| **Lab Sample ID:** | JC10089-2 | **Date Sampled:** | 12/08/15 |
| **Matrix:** | AQ - Water | **Date Received:** | 12/08/15 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 12/09/15 | JOO | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending January 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | May 6, 2014 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending January 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending January 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending January 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending January 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**3/10/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

March 10, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-02**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from February 1 – February 29, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: February 2016 SA-6/7 Combined Monthly Progress Report No. 2016-02

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2016-02
## Project SA-6 & 7 Remediation

# February 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 02/04/16 | Updated Declarations Schedule for Performance Certifications<br>Study Area 6 North and South<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/05/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, JC<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 02/11/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-01 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/16/16 | Special Master Conference Call | n/a |
| 02/22/16 | 2015 Annual Hazardous Waste Export Report For USEPA Id No.: NJD986581437<br>EPA Notice No.: 009557/4E/14 and 011562/3E/15 | US Environmental Protection Agency<br>International Compliance Assurance Division |
| 02/23/16 | PW-3 Startup Monitoring<br>Study Area 7 Groundwater<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 02/24/16 | Surcharge Monitoring Report<br>Study Area 6 North and South | Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 02/07/16 | 02/14/16 | 02/21/16 | 02/28/16 |
| **Construction Management (AMEC)** | 10 | 10 | 9 | 7 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 30 | 27 | 29 | 30 |

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 02/07/16 | 02/14/16 | 02/21/16 | 02/28/16 |
| **Arecon/US Ecology Subcontractors** | 2 | 1 | 1 | 0 |
| **Eglentowicz (Demolition)** | 0 | 0 | 1 | 1 |
| **Langan** | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 2 | 1 | 1 |
| **Cornerstone** | 0 | 1 | 0 | 0 |
| **TOTAL STAFF** | **48** | **47** | **47** | **45** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected February PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Installed 11 new shallow monitoring wells in the SA-6 South Development AOC in accordance with the 100% Design and Long Term Monitoring Plan and 1 new/replacement shallow monitoring well in a non-chromium AOC at SA-6 South in accordance with the NJDEP-approved Remedial Action Work Plan for Non-Chromium Contaminants of Concern.
- Began pre-demolition activities associated with 60/72 Kellogg to include disconnecting the water and sewer lines to 60 Kellogg, removal of the gas meters from 60 and 72 Kellogg, removal of the electric meter from 60 Kellogg, and installation of temporary construction fence.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on February 10, 2016.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 02/07/16 | 02/14/16 | 02/21/16 | 02/28/16 |
| Avg. Gallons Treated & Discharged (per day) | 79,597 | 79,365 | 78,708 | 79,077 |
| Average Flow (gpm) for Operating Period | 58 | 57 | 57 | 57 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 3,701 | 3,636 | 3,774 | 4,332 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed installation of temporary well points at Site 163.
- Continued dewatering and excavation activities of Site 163 and began placing backfill in surveyed portions of Site 163.
- Completed excavation of Excavation Areas EA-2 and EA-3.
- Continued backfilling of EA-2/EA-3 excavation area.
- Completed abandonment of the two deep wells in EA-2/EA-3 (designated DW-6 and DW-7) and 88-MW-113 near EA-5.
- Continued EA-1 excavation and backfilling activities. After completion of the original excavation to the limits identified in the approved 100% Design, a lens of anomalous material less than 10 foot in width was observed on the northern face of the excavation at ~2 to 3 feet below grade near Culver Circle. Honeywell requested that the property line limits be laid out in the field and that removal of this observed anomalous material be completed up to this property line and the excavation limits resurveyed for the asbuilt documentation.
- Continued excavation of trench for installation of the Contingent Groundwater Extraction System piping in Area 1N. A total of 578 linear feet of pipe were installed.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Horwith** | Tri-axle | PA Transload | US Ecology | >240 mg/kg CrVI | 55 | 22.3 | 1,229 |
| **Entact/Horwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non-haz Cr | 30 | 22.4 | 675 |

- See Attachment 15 for the Final February 1, 2016 truck incident report.

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | Excavation: EA-1, Site 163<br>Volume Excavated - Total for Reporting Period (EA-1): 1,040 CY/<br>Total to Date (SA-6 North): 39,443 CY;<br>Total for Reporting period (Site 163): 2,565 CY/ Total to Date: 6,907.5 CY |
| **Backfill in Progress** | EA-2/EA-3, EA-1, Site 163 |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 02/07/16 | 02/14/16 | 02/21/16 | 02/28/16 |
| Tilcon 1.5" Stone | 0 | 758.6 | 0 | 200.6 |

- Screened Celgene materials greater than 3/8 inch were transferred and placed as bridge lift in the Site 163 residential footprint excavation areas.
- Overburden historic fill soils with hexavalent chromium concentrations confirmed to be < 20 mg/kg soils were transferred and placed as backfill in Site 163.
- In addition historic fill soils previously identified to be < 20 mg/kg hexavalent chromium were transferred and placed as backfill in EA-2/EA-3.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.
- Area 2N: Surcharging and offloading of surcharge material is complete.
- Area 3N: Completed placement of surcharge material. Surcharging appears to be complete in the majority of this area and peer review of the calculations is underway by MRCE.
- Area 4N: Completed placement of surcharge material.

## F. SHEET PILE OPERATIONS

- Completed installation and grouting of the last special sheet pile barrier wall piece at the connection point of the SA-6 North barrier wall and the SA-7 SCB wall at the southwestern portion of Area 1N.
- Installed sheet pile for temporary excavation support at Site 163.

## G. CAPPING OPERATIONS

- Continued evaluations of potential alternative fill source(s), of Horizon C Soils for the SA-6 South open space area. Short list of potential Horizon B and C soil source vendors which may need relief on physical parameters (gradations, pH or organic matter content ranges in current specifications) were submitted to Dr. Jason Grabosky of Rutgers University for review.
- Continued to install additional panels of temporary plastic sheeting on the SA-6 South Cap.

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete EA-2/EA-3 backfilling activities.
- Complete EA-1 excavation and backfilling activities.
- Complete excavation and backfill activities associated with Site 163 excavation including removal of temporary sheeting.
- Continue installation of the Contingent Groundwater Extraction System piping in Area 1N.
- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.
- Pending identification of acceptable alternative fill source(s), resume import and placement of Horizon C Soils on the SA-6 South open space area.
- Continue routine surcharge monitoring in Areas 3N and 4N.
- Continue demolition of 60 and 72 Kellogg above-grade buildings to include asbestos abatement, universal waste removal, rodent abatement, and termination of the gas and electric service.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal injection event no. 27 in well 088-IW-02.
- Cornerstone will conduct round of quarterly LTMP groundwater level measurements.
- Conduct 6-month performance assessment soil sampling in the in-situ treatment area TA-10-1 in accordance with the updated Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated August 2015.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data *(not included in this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update
11. Capping Update *(not included in this reporting period)*
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log
15. Horwith Accident RollOver


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 3/01/16

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Continuing Contingent GWES Trenching in Area 1N.




**Site Photograph 2:** EA-1 Survey activities.




**Site Photograph 3:** Excavation activities at Site 163 Kellogg Street properties.




**Site Photograph 4:** Hand digging to locate utility lines at EA-1.




**Site Photograph 5:** Loading of excavated soils from EA-1.





**Site Photograph 6:** Loading of excavated soils from Site 163.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of March 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-02
Attachment 3: Excavation and Backfill (Progression Chart)




## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

# Attachment 4: Dewatering Operations Update

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 12/18/15 | 1 | 24 | 19 | 10 | N/A | N/A | 1,700 | 3,112,472 | 1.2 | System Taken Offline |
| 01/14/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 5,000 | 3,117,472 | 3.5 | |
| 01/15/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,122,472 | 3.5 | |
| 01/18/16 | 1 | 72 | 22,23,24 | 23 | N/A | N/A | 15,000 | 3,137,472 | 3.5 | |
| 01/19/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,142,472 | 3.5 | System Offline for Excavation |
| 02/05/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,147,472 | 3.5 | |
| 02/08/16 | 1 | 72 | 22,23,24 | 23 | N/A | N/A | 15,000 | 3,162,472 | 3.5 | |
| 02/09/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 5,000 | 3,167,472 | 3.5 | |
| 02/10/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 3,000 | 3,170,472 | 2.1 | |
| 02/11/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 3,000 | 3,173,472 | 2.1 | |
| 02/12/16 | 1 | 24 | 22,23,24 | 21 | N/A | N/A | 3,000 | 3,176,472 | 2.1 | |
| 02/16/16 | 1 | 96 | 22,23,24 | 21 | N/A | N/A | 2,000 | 3,178,472 | 0.3 | |
| 02/17/16 | 1 | 24 | 22,23,24 | 15 | N/A | N/A | 1,000 | 3,179,472 | 0.7 | |
| 02/18/16 | 1 | 24 | 22,23,24 | 8 | N/A | N/A | 1,000 | 3,180,472 | 0.7 | |
| 02/19/16 | 1 | 24 | 22,23,24 | 8 | N/A | N/A | 1,500 | 3,181,972 | 1.0 | |
| 02/22/16 | 1 | 72 | 22,23,24 | 3 | N/A | N/A | 4,000 | 3,185,972 | 0.9 | |
| 02/23/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,186,972 | 0.7 | |
| 02/24/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,187,972 | 0.7 | |
| 02/25/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,188,972 | 0.7 | |
| 02/26/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,189,972 | 0.7 | |

Notes: Previous information is truncated. Only last month and current month information is provided.
Dewatering is associated with EA2/EA3 Excavation.

**STUDY AREA 6 NORTH (EA2/3) DEEP WELL DATA (DW-6)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 12/06/15 | 48 | N/A | N/A | 10,000 | 10,000 | 3.5 | |
| 12/07/15 | 24 | N/A | N/A | 8,000 | 18,000 | 5.6 | |
| 12/08/15 | 24 | N/A | N/A | 8,000 | 26,000 | 5.6 | |
| 12/09/15 | 24 | N/A | N/A | 8,000 | 34,000 | 5.6 | |
| 12/10/15 | 24 | N/A | N/A | 10,000 | 44,000 | 6.9 | |
| 12/13/15 | 48 | N/A | N/A | 20,000 | 64,000 | 6.9 | |
| 12/14/15 | 24 | N/A | N/A | 10,000 | 74,000 | 6.9 | |
| 12/15/15 | 24 | N/A | N/A | 10,000 | 84,000 | 6.9 | |
| 12/16/15 | 24 | N/A | N/A | 10,000 | 94,000 | 6.9 | |
| 12/17/15 | 24 | N/A | N/A | 10,000 | 104,000 | 6.9 | |
| 12/18/15 | 24 | N/A | N/A | 10,000 | 114,000 | 6.9 | |
| 12/20/15 | 48 | N/A | N/A | 20,000 | 134,000 | 6.9 | |
| 12/21/15 | 24 | N/A | N/A | 10,000 | 144,000 | 6.9 | |
| 12/23/15 | 24 | N/A | N/A | 10,000 | 154,000 | 6.9 | |
| 12/24/15 | 24 | N/A | N/A | 10,000 | 164,000 | 6.9 | |
| 12/26/15 | 48 | N/A | N/A | 20,000 | 184,000 | 6.9 | |
| 12/28/15 | 48 | N/A | N/A | 20,000 | 204,000 | 6.9 | |
| 12/29/15 | 24 | N/A | N/A | 10,000 | 214,000 | 6.9 | |
| 12/30/15 | 24 | N/A | N/A | 10,000 | 224,000 | 6.9 | |
| 12/31/16 | 24 | N/A | N/A | 10,000 | 234,000 | 6.9 | |
| 01/04/16 | 96 | N/A | N/A | 40,000 | 274,000 | 6.9 | |
| 01/05/16 | 24 | N/A | N/A | 10,000 | 284,000 | 6.9 | Taken offline for excavation |

**STUDY AREA 6 SOUTH (SITE 163) DEEP WELL DATA (DW-8)**

| DATE | HOURS OF OPERATION | FLOW METER START (Gal) | FLOW METER FINISH (Gal) | VOLUME (Gal) DAILY | VOLUME (Gal) TOTAL | FLOW RATE (GPM) | COMMENTS |
|---|---|---|---|---|---|---|---|
| 02/09/16 | 24 | N/A | N/A | 10,000 | 10,000 | 6.9 | Flow meter not installed, tank measured |
| 02/10/16 | 24 | N/A | N/A | 8,000 | 18,000 | 5.6 | |
| 02/11/16 | 24 | N/A | N/A | 8,000 | 26,000 | 5.6 | |
| 02/12/16 | 24 | N/A | N/A | 6,000 | 32,000 | 4.2 | |
| 02/16/16 | 96 | N/A | N/A | 12,000 | 44,000 | 2.1 | |
| 02/17/16 | 24 | N/A | N/A | 6,000 | 50,000 | 4.2 | |
| 02/18/16 | 24 | N/A | N/A | 4,000 | 54,000 | 2.8 | System Taken Offline for Ecavation |

# Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 12/31/15 | 7:00 | 13:45 | 6:45 | 39,125.05 | 39,167.86 | 42,810 | 39,024,010 | |
| 01/04/16 | 7:30 | 16:15 | 8:45 | 39,167.86 | 39,269.10 | 101,240 | 39,125,250 | |
| 01/07/16 | 8:00 | 16:15 | 8:15 | 39,269.10 | 39,354.16 | 85,060 | 39,210,310 | |
| 01/11/16 | 7:30 | 14:00 | 6:30 | 39,354.16 | 39,425.93 | 71,770 | 39,282,080 | |
| 01/12/16 | 8:00 | 13:00 | 5:00 | 39,425.93 | 39,510.66 | 84,730 | 39,366,810 | PVSC Compliance Sample Collected |
| 01/14/16 | 9:30 | 14:00 | 4:30 | 39,510.66 | 39,562.31 | 51,650 | 39,418,460 | |
| 02/01/16 | 7:30 | 13:15 | 5:45 | 39,562.31 | 39,632.04 | 69,730 | 39,488,190 | |
| 02/02/16 | 7:00 | 11:30 | 4:30 | 39,632.04 | 39,691.51 | 59,470 | 39,547,660 | PVSC Compliance Sample Collected |
| 02/03/16 | 7:30 | 15:30 | 8:00 | 39,691.51 | 39,789.38 | 97,870 | 39,645,530 | |
| 02/04/16 | 8:00 | 15:30 | 7:30 | 39,789.38 | 39,869.34 | 79,960 | 39,725,490 | |
| 02/05/16 | 8:00 | 15:30 | 7:30 | 39,869.34 | 39,962.83 | 93,490 | 39,818,980 | |
| 02/06/16 | 8:00 | 14:00 | 6:00 | 39,962.83 | 40,010.68 | 47,850 | 39,866,830 | |
| 02/08/16 | 7:15 | 15:15 | 8:00 | 40,010.68 | 40,119.75 | 109,070 | 39,975,900 | |
| 02/09/16 | 8:30 | 15:30 | 7:00 | 40,119.75 | 40,195.00 | 75,250 | 40,051,150 | |
| 02/10/16 | 9:30 | 15:30 | 6:00 | 40,195.00 | 40,313.68 | 118,680 | 40,169,830 | |
| 02/11/16 | 10:30 | 15:30 | 5:00 | 40,313.68 | 40,407.45 | 93,770 | 40,263,600 | |
| 02/16/16 | 10:00 | 16:00 | 6:00 | 40,407.45 | 40,472.48 | 65,030 | 40,328,630 | |
| 02/17/16 | 7:00 | 15:30 | 8:30 | 40,472.48 | 40,635.48 | 163,000 | 40,491,630 | |
| 02/18/16 | 9:30 | 14:30 | 5:00 | 40,635.48 | 40,695.00 | 59,520 | 40,551,150 | |
| 02/22/16 | 7:30 | 13:00 | 5:30 | 40,695.00 | 40,767.90 | 72,900 | 40,624,050 | |
| 02/23/16 | 7:30 | 15:00 | 7:30 | 40,767.90 | 40,847.01 | 79,110 | 40,703,160 | |
| 02/24/16 | 8:30 | 15:00 | 6:30 | 40,847.01 | 40,947.06 | 100,050 | 40,803,210 | |
| 02/25/16 | 9:00 | 16:00 | 7:00 | 40,947.06 | 41,052.04 | 104,980 | 40,908,190 | |
| 02/26/16 | 7:30 | 15:00 | 7:30 | 41,052.04 | 41,114.52 | 62,480 | 40,970,670 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

**MATERIAL TRACKING AND SAMPLING LOG**
**SA-6 NORTH AND SOUTH**

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA2/EA3 | <20 | 087-EA2-20-a (bermed/trench material) | 400 | 087-EA2-20-a1 | 12/11/2015 | -- | <1.8 | Yes | | |
| | | | | 087-EA2-20-a2 | 12/11/2015 | -- | 6.7 | Yes | | |
| | | | | 087-EA2-20-a3 | 12/11/2015 | -- | <1.9 | Yes | | |
| | | | | 087-EA2-20-a4 | 12/11/2015 | -- | 3.8 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-b1:g1 (A material) | 5200 cy | 087-EA2-20-b1 | 12/30/2015 | -- | 3.0 | Yes | | |
| | | | | 087-EA2-20-b2 | 12/30/2015 | -- | 3.0 | Yes | | |
| | | | | 087-EA2-20-b3 | 12/30/2015 | -- | 0.55 | Yes | | |
| | | | | 087-EA2-20-b4 | 12/30/2015 | -- | 0.97 | Yes | | |
| | | | | 087-EA2-20-c1 | 12/30/2015 | -- | 4.3 | Yes | | |
| | | | | 087-EA2-20-c2 | 12/30/2015 | -- | 1.5 | Yes | | |
| | | | | 087-EA2-20-c3 | 12/30/2015 | -- | 1.6 | Yes | | |
| | | | | 087-EA2-20-c4 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-d1 | 12/30/2015 | -- | 0.60 | Yes | | |
| | | | | 087-EA2-20-d2 | 12/30/2015 | -- | 15.9 | Yes | | |
| | | | | 087-EA2-20-d3 | 12/30/2015 | -- | 5.4 | Yes | | |
| | | | | 087-EA2-20-d4 | 12/30/2015 | -- | 1.7 | Yes | | |
| | | | | 087-EA2-20-e1 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-e2 | 12/30/2015 | -- | 12.3 | Yes | | |
| | | | | 087-EA2-20-e3 | 12/30/2015 | -- | 3.1 | Yes | | |
| | | | | 087-EA2-20-e4 | 12/30/2015 | -- | 0.57 | Yes | | |
| | | | | 087-EA2-20-f1 | 12/30/2015 | -- | 0.52 | Yes | | |
| | | | | 087-EA2-20-f2 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-f3 | 12/30/2015 | -- | 0.57 | Yes | | |
| | | | | 087-EA2-20-f4 | 12/30/2015 | -- | 0.54 | Yes | | |
| | | | | 087-EA2-20-g1 | 12/30/2015 | -- | 0.53 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-h1 (overburden) | 150 cy | 087-EA2-20-h1 | 12/30/2015 | -- | 0.7 | * | | |
| EA2/EA3 | <20 | 087-EA2-20-i1 (overburden) | 200 cy | 087-EA2-20-i1 | 12/30/2015 | -- | 0.54 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-h2:j3 (overburden) | 2200 cy | 087-EA2-20-h2 | 1/8/2016 | -- | 24.1 | | * | |
| | | | | 087-EA2-20-h3 | 1/8/2016 | -- | <1.4 | Yes | | |
| | | | | 087-EA2-20-h4 | 1/8/2016 | -- | 19 | Yes | | |
| | | | | 087-EA2-20-i2 | 1/8/2016 | -- | 0.66 | Yes | | |
| | | | | 087-EA2-20-i3 | 1/8/2016 | -- | <1.9 | Yes | | |
| | | | | 087-EA2-20-i4 | 1/8/2016 | -- | <1.4 | Yes | | |
| | | | | 087-EA2-20-j1 | 1/8/2016 | -- | <2.0 | Yes | | |
| | | | | 087-EA2-20-j2 | 1/8/2016 | -- | 8.9 | Yes | | |
| | | | | 087-EA2-20-j3 | 1/8/2016 | -- | <1.9 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-k1:k4 | 1000 cy | 087-EA2-20-k1 | 1/8/2016 | -- | 7 | Yes | | |
| | | | | 087-EA2-20-k2 | 1/8/2016 | -- | 10 | Yes | | |
| | | | | 087-EA2-20-k3 | 1/8/2016 | -- | 8 | Yes | | |
| | | | | 087-EA2-20-k4 | 1/8/2016 | -- | <1.9 | Yes | | |
| Site 163 | <20 | 163-20-a | 840 | 163-20-a1 | 1/19/2016 | -- | 8.1 | * | | |
| | | | | 163-20-a2 | 1/19/2016 | -- | 4.0 | * | | |
| | | | | 163-20-a3 | 1/19/2016 | -- | 1.7 | * | | |
| | | | | 163-20-a4 | 1/19/2016 | -- | 5.0 | * | | |
| Site 163 | <20 | 163-20-a | 840 | 163-20-a5 | 2/22/2016 | -- | 2.7 | * | | |
| | | | | 163-20-a6 | 2/22/2016 | -- | 3.6 | * | | |
| | | | | 163-20-a7 | 2/22/2016 | -- | 1.0 | * | | |
| | | | | 163-20-a8 | 2/22/2016 | -- | 5.1 | * | | |

Previous information is truncated. Only last two months and current month information is provided.
*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'

N4 N3 N2 N1 E1 E2 S4 S3 S2 S1

NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1
073-MW-BB11 073-MW-Y10 134-MW-V09 134-MW-Q08 140-MW-06 140-MW-07 125-MW-L03
MW-124-103L MW-124-102D MW-124-103D MW-124-102T 117-MW-A99 117-MW-A85 117-MW-A89
115-PZ-6 115-PZ-5 115-PZ-4

W6-SO W1-SO W5-SO W3-SO E5-SO E4-SO E3-SO E2-SO E1-SO

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

KELLOGG STREET

HERSEY STATE ROUTE

**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 3/2/2015 | 3.1 | | 5.5 | 5.9 | 6.0 | | 3.0 | 3.1 | | 4.1 | 6.6 | 5.9 | 5.8 | 5.8 | 5.8 | | 2.7 | 2.9 | 4.3 | 3.5 | 3.3 | 3.0 |
| 3/17/2015 | 3.1 | 5.6 | 6.4 | 7.5 | 7.0 | | 3.5 | 3.1 | | 5.6 | 6.6 | | 6.0 | 5.9 | 6.5 | | 3.4 | | 4.3 | | 3.3 | 3.2 |
| 3/31/2015 | 3.3 | 5.5 | 6.4 | 7.2 | 6.7 | | 3.5 | 3.0 | 5.7 | 5.7 | 6.8 | | 5.7 | 5.6 | 5.3 | | 3.0 | 2.9 | 4.4 | | 3.2 | 3.1 |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | | | | 4.5 | 5.0 | 3.8 | 3.5 | | | | | | |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | | | | 3.5 | 3.6 | | | | | | | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | | | | 5.2 | | | 4.6 | | | | | | |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | | | | 6.0 | | | 5.6 | | | | | | |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | | | | 6.5 | | | 6.2 | | | | | | |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | | | | 6.0 | | | 5.7 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, E4-SO, W1-SO, North FS-6, North FS-7


# Attachment 8: Groundwater Quality Data


(not included in this reporting period)

# Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update


EXISTING JCIA TRASH PIT
CONSERVATION EASEMENT
HYDRAULIC BARRIER (TYP)
STA. 0+00 TO 5+00 SEE SPECIAL INSTRUCTIONS FOR SEALING SHEETS, SEE NOTE HB19 ON SHEET GN-004.
SEE NOTE HB21 ON SHEET GN-003
NEW JERSEY STATE HIGHWAY ROUTE 440
MATCH LINE SHEET SN-202
GEOMEMBRANE GRADE CONTOURS (TYP)
HORIZONTAL SCALE
SCALE IN FEET
EXISTING SOIL CEMENT BENTONITE WALL
HYDRAULIC BARRIER AND SLURRY CEMENT BENTONITE WALL CONNECTION SN-201 SN-301
NOTES:
1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET GN-501 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.
HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE
NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700
STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700
NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700
NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700
STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N
NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700
Corner + 1 pair
1/4/16
Special 4/29/15
5/5/15
EXISTING GRADE
JCIA BUILDING
TYPICAL UTILITY CORRIDOR/ HYDRAULIC BARRIER SN-201 SN-301 CROSSING DETAIL
STA. 3+66 JCIA TRASH PIT
STA. 3+80 JCIA TRASH PIT
GEOMEMBRANE GRADE
HISTORIC FILL
SITE HISTORIC WATER TABLE (SEE NOTE 3)
STRATUM O
STRATUM D
STRATUM S1
JCIA TRASH PIT SEE NOTE JC2 ON SHEET GN-004
STA. 0+00 TO STA. 5+00 SPECIAL INSTRUCTIONS FOR SEALING SHEETS SEE NOTE HB19 ON SHEET GN-004
HORIZONTAL SCALE
SCALE IN FEET
VERTICAL SCALE
SCALE IN FEET
Time frame for: 4 HB sheets driven
SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43527
NO. DATE DSGN CHK APVD
1 12/10/15 TDD RJR SGS
0 6/30/15 TDD RJR SGS
HB19 RE-ALIGNMENT ADJACENT TO 72-INCH RM
ISSUED FOR CONSTRUCTION
Honeywell
CHROMIUM REMEDY
STUDY AREA 6 / 7 SOUTH
JEFFREY ST. AND MAIN ST.
JERSEY CITY, NEW JERSEY
DRAWING STATUS
100 PERCENT DESIGN DRAWINGS
HYDRAULIC BARRIER
PLAN AND PROFILE
amec
VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
DATE
PROJ 3480-12-0317
DWG SN-201
SHEET 54 OF 70




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

Time frame for:
HB sheets driven

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 09/13/13 | TDD | RJR | TDD | BCO | RJR | SGS |
| 0 | 06/07/13 | | | | | TDD | SGS |

HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 587-2220
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:35 AM




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APV'D |
|---|---|---|---|---|
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | TDD | DR TDD | RJR | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTED FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2629
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 18 Oct 2013 PLOT TIME: 10:37 AM

# Attachment 11: Capping Update

(not included in this reporting period)

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: February 5, 2016**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | X | | 1 |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 02/5/16

**SWPPP Observer:** David Chase for George Pfeiffer
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, February 05, 2016**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The tracking pad at the SA-6 South truck exit has become blinded with sediment. |
| 2 | IA2Q4A1AL8 | Windscreen on the SA-6 South perimeter fenceline has become detached in several locations. |
| 3 | IA2Q4A1AL8 | Ponded storm water (snow melt) is present on puddles/ponds throughout SA-6 South. |
| 4 | IA2Q4A1AL8 | Trash and other debris is present along Rt. 440 and the Kellogg Street jughandle. |
| 5 | IA2Q4A1AL8 | **REPEAT:** The silt fence along the southern perimeter of the Novartis Stockpile Area on SA-7 requires maintenance or replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey
**SWAP Observer:** David Rose **Date:** 02/5/16

Signature for George Pfeiffer

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Stir up the stone in the tracking pad to restore function | 2-10-16 |
| 2 | Re-attach windscreen to the perimeter fenceline as required. | 2-10-16 |
| 3 | Pump ponded stormwater as required. | frozen can't do |
| 4 | Pick up and dispose of trash and other debris along the roadway | 2-11-16 |
| 5 | Repair or replace the silt fence along the southern perimeter of the Novartis Stockpile Area. | frozen can't do |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** David Rose **Date:** 02/05/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 12, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/12/16

SWPPP Observer: _____
Signature

# Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, February 12, 2016**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
RFA Portal ID#: 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
RFA Portal ID#: 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the SA-6 South perimeter fenceline has become detached in several locations. |
| 2 | IA2Q4A1AL8 | Trash and other debris is present along Rt. 440 and the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | The silt fence along the southern perimeter of the Novartis Stockpile Area on SA-7 requires maintenance or replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION


**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 02/12/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach windscreen to the perimeter fenceline as required. | 2/12/16 |
| 2 | Pick up and dispose of trash and other debris along the roadway. | |
| 3 | Repair or replace the silt fence along the southern perimeter of the Novartis Stockpile Area. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 02/12/16

for George Pfeiffer




SWPPP - 02/17/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 19, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 1 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 4 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 6 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/19/16

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, February 19, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Plastic sheeting used for erosion control on the western toe of the SA-6 South cap area adjacent to the Hackensack River has blown out of place. |
| 2 | IA2Q4A1AL8 | Windscreen on the SA-6 South perimeter fenceline is detached from the perimeter fence in the area of the 60 Kellogg building. |
| 3 | IA2Q4A1AL8 | Garbage has accumulated on the grass area along the 60 kellogg jughandle. |
| 4 | IA2Q4A1AL8 | Exclusion Zone fencing surrounding the EZ at the western end of the SA-6 North cap area requires maintenance. |
| 5 | IA2Q4A1AL8 | **Repeat:** Silt fence surrounding the Novartis Stockpile Area on SA-7 requires maintenance. |
| 6 | IA2Q4A1AL8 | Sediment has accumulated on the western SA-7 haul road. |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: 02/19/16 Date:


Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-install plastic sheeting over the western toe of the SA-6 South cap area. | 2/25/16 RAD |
| 2 | Re-attach windscreen to the perimeter fence as required. | |
| 3 | Pick up and dispose of accumulated garbage along the side of Kellogg Street. | |
| 4 | Repair or replace Exclusion Zone fencing as required. | |
| 5 | Repair or replace the silt fence surrounding the Novartis Stockpile Area as required. | |
| 6 | Clean sediment from the SA-7 roadway as required. | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: Ted Rose Date: 2/25/16

for George Pfeiffer

SWPPP - 02/19/16



STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: February 26, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 02/26/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, February 26, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608287
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Windscreen on the SA-6 South perimeter fenceline is detached from the perimeter fence in the area of the 60 Kellogg building. |
| 2 | IA2Q4A1AL8 | Ponded stormwater is present at numerous locations on SA-6 South. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing surrounding the EZ at the western end of the SA-6 North cap area requires maintenance. |
| 4 | IA2Q4A1AL8 | REPEAT: Silt fence surrounding the Novartis Stockpile Area on SA-7 requires maintenance. |
| 5 | IA2Q4A1AL8 | Sediment has accumulated on the western SA-7 haul road. |
| | | |
| | | |
| | | |
| | | |
| | | |


**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 02/26/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach or replace windscreen to the perimeter fence as required. | 2-26-16 (RAD) |
| 2 | Pump accumulated surface water to the CWTP as required. | |
| 3 | Repair or replace Exclusion Zone fencing as required. | |
| 4 | Repair or replace the silt fence surrounding the Novartis Stockpile Area as required. | |
| 5 | Clean sediment from the SA-7 roadway as required. | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 02/26/16
for George Pfeiffer




SWPPP-07/26/16

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted February 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

February 5, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the January 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 1 | 01 | 16 | 1 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 69,166 | 86,376 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.99 | 1.23 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00047 | 0.00047 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.2 | <5.2 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1437 | 0.1437 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT


Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or superv accordance with a system designed to assure that qualified personnel properly gather and evaluate the informati Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

02/04/2016

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION:** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 1 | 01 | 16 | 1 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,144,155 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 54,421,416 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 1/20/2016 | 4.2 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE 02/04/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | MONTH: January 2016 | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 1/1/2016 | Angel Trujillo | 52277261 | 52360622 | 83,361 | 0.083361 | 7.40 | 1.710 | | | | | | | | | 1.19 |
| 1/2/2016 | Angel Trujillo | 52360622 | 52443983 | 83,361 | 0.083361 | 7.51 | 1.710 | | | | | | | | | 1.19 |
| 1/3/2016 | Angel Trujillo | 52443983 | 52519517 | 75,534 | 0.075534 | 7.20 | 1.710 | | | | | | | | | 1.08 |
| 1/4/2016 | Angel Trujillo | 52519517 | 52595052 | 75,535 | 0.075535 | 7.61 | 1.710 | | | | | | | | | 1.08 |
| 1/5/2016 | Angel Trujillo | 52595052 | 52676528 | 81,476 | 0.081476 | 7.12 | 1.710 | | | | | | | | | 1.16 |
| 1/6/2016 | Angel Trujillo | 52676528 | 52754626 | 78,098 | 0.078098 | 7.10 | 1.710 | | | | | | | | | 1.11 |
| 1/7/2016 | Angel Trujillo | 52754626 | 52834124 | 79,498 | 0.079498 | 7.10 | 1.710 | | | | | | | | | 1.13 |
| 1/8/2016 | Angel Trujillo | 52834124 | 52910910 | 76,786 | 0.076786 | 7.20 | 1.710 | | | | | | | | | 1.10 |
| 1/9/2016 | Angel Trujillo | 52910910 | 52992706 | 81,796 | 0.081796 | 7.15 | 1.710 | | | | | | | | | 1.17 |
| 1/10/2016 | Angel Trujillo | 52992706 | 53068438 | 75,732 | 0.075732 | 7.00 | 1.710 | | | | | | | | | 1.08 |
| 1/11/2016 | Angel Trujillo | 53068438 | 53144170 | 75,732 | 0.075732 | 6.91 | 1.710 | | | | | | | | | 1.08 |
| 1/12/2016 | Angel Trujillo | 53144170 | 53222850 | 78,680 | 0.07868 | 7.08 | 1.710 | | | | | | | | | 1.12 |
| 1/13/2016 | Angel Trujillo | 53222850 | 53303728 | 80,878 | 0.080878 | 7.15 | 1.710 | | | | | | | | | 1.15 |
| 1/14/2016 | Angel Trujillo | 53303728 | 53316922 | 13,194 | 0.013194 | 7.12 | 1.710 | | | | | | | | | 0.19 |
| 1/15/2016 | Angel Trujillo | 53316922 | 53384990 | 68,068 | 0.068068 | 7.14 | 1.710 | | | | | | | | | 0.97 |
| 1/16/2016 | Angel Trujillo | 53384990 | 53470632 | 85,642 | 0.085642 | 7.20 | 1.710 | | | | | | | | | 1.22 |
| 1/17/2016 | Angel Trujillo | 53470632 | 53547549 | 76,917 | 0.076917 | 7.00 | 1.710 | | | | | | | | | 1.10 |
| 1/18/2016 | Angel Trujillo | 53547549 | 53624466 | 76,917 | 0.076917 | 7.07 | 1.710 | | | | | | | | | 1.10 |
| 1/19/2016 | Angel Trujillo | 53624466 | 53703794 | 79,328 | 0.079328 | 7.21 | 1.710 | | | | | | | | | 1.13 |
| 1/20/2016 | Angel Trujillo | 53703794 | 53782422 | 78,628 | 0.078628 | 6.92 | 1.710 | <5.2 | 4.2 | | <0.010 | <0.015 | <0.010 | 0.00047 | <0.020 | 1.12 |
| 1/21/2016 | Angel Trujillo | 53782422 | 53863312 | 80,890 | 0.08089 | 7.22 | 1.710 | | | | | | | | | 1.15 |
| 1/22/2016 | Angel Trujillo | 53863312 | 53943116 | 79,804 | 0.079804 | 7.19 | 1.710 | | | | | | | | | 1.14 |
| 1/23/2016 | Angel Trujillo | 53943116 | 54004535 | 61,419 | 0.061419 | 7.10 | 1.710 | | | | | | | | | 0.88 |
| 1/24/2016 | Angel Trujillo | 54004535 | 54065954 | 61,419 | 0.061419 | 7.00 | 1.710 | | | | | | | | | 0.88 |
| 1/25/2016 | Angel Trujillo | 54065954 | 54127374 | 61,420 | 0.06142 | 7.50 | 1.710 | | | | | | | | | 0.88 |
| 1/26/2016 | Angel Trujillo | 54127374 | 54127374 | 0 | 0 | N/A | 1.710 | | | | | | | | | 0.00 |
| 1/27/2016 | Angel Trujillo | 54127374 | 54127374 | 0 | 0 | N/A | 1.710 | | | | | | | | | 0.00 |
| 1/28/2016 | Angel Trujillo | 54127374 | 54176268 | 48,894 | 0.048894 | 7.14 | 1.710 | | | | | | | | | 0.70 |
| 1/29/2016 | Angel Trujillo | 54176268 | 54262644 | 86,376 | 0.086376 | 7.38 | 1.710 | | | | | | | | | 1.23 |
| 1/30/2016 | Angel Trujillo | 54262644 | 54344182 | 81,538 | 0.081538 | 7.18 | 1.710 | | | | | | | | | 1.16 |
| 1/31/2016 | Angel Trujillo | 54344182 | 54421416 | 77,234 | 0.077234 | 7.20 | 1.710 | | | | | | | | | 1.10 |
| **TOTAL** | | | | **2,144,155** | **2.144155** | | | <5.2 | 4.2 | | <0.010 | <0.015 | <0.010 | 0.00047 | <0.020 | |
| | | | **High:** | **86,376** | | | | | | | | | | | **High:** | **1.23** |
| | | | **Average:** | **69,166** | | | | | | | | | | | **Average:** | **0.99** |

WW

JC12950

E/L

**Accutest Labs**
2235 ROUTE 130
Dayton, NJ 8810
732-329-0200

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 42388.53078
COC#: 087-WW-012016

| | | |

Accutest LabLink@894420 13:44 03-Feb-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-012016-A | | |
| **Lab Sample ID:** | JC12950-1 | **Date Sampled:** | 01/20/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/20/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1710 | 10 | ug/l | 1 | 01/21/16 | 01/22/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 01/21/16 | 01/22/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 01/21/16 | 01/22/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Mercury | 0.47 | 0.20 | ug/l | 1 | 01/22/16 | 01/22/16 | VM | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 01/21/16 | 01/22/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 01/21/16 | 01/22/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA38582
(2) Instrument QC Batch: MA38588
(3) Prep QC Batch: MP91567
(4) Prep QC Batch: MP91705

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

Accutest LabLink@894420 13:44 03-Feb-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-012016-A | | |
| **Lab Sample ID:** | JC12950-1 | **Date Sampled:** | 01/20/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/20/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | < 4.0 | 4.0 | mg/l | 1 | 01/21/16 | LA | SM2540 D-11 |
| pH [b] | 6.85 | | su | 1 | 01/20/16 18:14 | HL | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 500 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

Accutest LabLink@894420 13:44 03-Feb-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-012016-A | | |
| **Lab Sample ID:** | JC12950-1A | **Date Sampled:** | 01/20/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/20/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 4.2 | 3.4 | mg/l | 1 | 01/21/16 13:10 | YR | SM5210 B-11 |

RL = Reporting Limit

Accutest LabLink@894420 13:44 03-Feb-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-012016-B | | |
| **Lab Sample ID:** | JC12950-2 | **Date Sampled:** | 01/20/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/20/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | U202808.D | 1 | 01/21/16 | NH | n/a | n/a | VU9329 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 2.3 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 4.5 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.21 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 20.5 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.41 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | ND | 1.0 | 0.12 | ug/l | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 70.8 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.9 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | ND | 1.0 | 0.22 | ug/l | |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@894420 13:44 03-Feb-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-012016-B | | |
| **Lab Sample ID:** | JC12950-2 | **Date Sampled:** | 01/20/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/20/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 41.1 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 104% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 99% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 101% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Accutest LabLink@894420 13:44 03-Feb-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-012016-B | | |
| **Lab Sample ID:** | JC12950-2 | **Date Sampled:** | 01/20/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 01/20/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.2 | 5.2 | mg/l | 1 | 01/22/16 21:45 | CB | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending February 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending February 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending February 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending February 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA 6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending February 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |
| **DC 2015-02-03** | The final grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending February 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

# Attachment 15: Horwith Accident RollOver

# TRANSPORTATION HAZARDOUS WASTE ACCIDENT W / POTENTIAL OF RELEASE

Date: February 1st, 2016

Time: 3:00 PM

Driver: Salvatore Gagliano

Truck Number: 242

Shipment Information: Manifest #000728562WAS

Pickup: 60 Kellogg Street, Jersey City NJ.
Deliver: Horwith Transload Facility, Northampton PA

## Event Details

Initial Report

Kellie Heffley received a telephone call from Fastlane Towing stating they are on the scene of a single vehicle rollover and the truck is owned by Horwith Trucks. A represented from Fastlane, "Pinky" reported unit #242 had rolled over with load on Route 33 near the 3.3 mile marker. Pinky indicated he was called to the scene by the PA State Police.

The Horwith team immediately implemented our Transporter Contingency plan. Kellie contacted the PA State Police – Belfast Barracks and informed them the shipment was being shipped on a Hazardous Waste Manifest and caution should be used when up righting the unit to ensure the commodity was not released. Initial reports indicated cargo within the enclosed IP-1 Zippered liner was not breached during the rollover.

Pete Zarayko called Dave Desiderio of HandsOn Environmental and notified him of the accident.

Initial Reports indicated there was no release of product, therefore PA DEP was not immediately notified.

## HONEYWELL SA-7 - 2/1/17 Rollover Accident Details

At approximately 3:00pm on Monday, February 1st 2016, a tri-axle dump truck driven by Salvatore Gagliano was traveling northbound on Route 33 near mile marker 3.3 in Pennsylvania. The driver was traveling in the left lane of a two lane highway at approximately 65mph. For an unknown reason the driver side tires left the roadway. The driver attempted to regain traction on the highway with all tires at which time he lost control of the vehicle. The vehicle crossed both lanes of traffic and rolled onto the driver's side and came to rest on the right side of the highway.

Various "good Samaritans" stopped to aid assistance to the driver. Mr. Gagliano was initially unconscious when the first "Samaritan" arrived. The driver regained consciousness a few minutes later and was able to exit the unit from the passenger side window. He was quickly transported to St Luke's Fountain Hill where he was treated and released.

Initially the IP-1 zippered liner stayed in the dump body. However, a portion of the liner containing the contaminated soil slide out as a result of gravity and the unit being on its side. A portion of the liner came to rest on the roadway pavement. The liner did not breach at any point during the rollover incident.

Immediately following the incident, appropriate notifications were made to the PA State Police, emergency response personnel and our customer to inform them of the accident. 911 was called by another motorist. The following agencies were present on the scene: Northampton County EMA, Lehigh County Hazmat, Penn Dot, PA State Police, Bethlehem Twp. Fire Co., Nancy Run Fire Co., Rapid Response, Fastlane Towing, and PA DEP.

Under the direction of Fastlane Towing, Horwith was asked to send two additional vehicles to the accident scene to transfer the cargo. Fastlane Towing and Rapid Response received approval from DEP to open the IP-1 Zippered liner and remediate the soil prior to up righting the unit. (See Attached DEP Report) Various safety and security measures were used to ensure the contaminated soil was not released onto the roadway or into the environment. The soil was dug out of the IP-1 zippered liner from unit #242 and immediately loaded into two lined roll off containers. The dirt was transported by Horwith personnel under the same manifest number and transport instructions as the original load. (Manifest Number 000728562WAS) The two loads were dumped at the Northampton Transloading facility on Tuesday, February 2nd 2016 and shipped via rail to the designated disposal facility.

Unit # 242 was towed from the scene by Fastlane Towing and brought to the Horwith terminal in Northampton PA.
Rapid Response concluded cleanup operations by 12:00 AM February 2nd 2016.

**Incident Follow-up as of 2/17/16**

Eight soil samples were taken following the cleanup and the written results were provided to Horwith by Rapid Response. All samples reflected that no traces of the hazardous material were present. (See Attached) These result were sent to the PADEP by Rapid Response.

The driver was interviewed by Kellie Heffley and Michael Horwith regarding the accident details. The driver indicated he has no memory of the accident. He was initially treated at the hospital and released. Horwith sent him to our approved medical provider who conducted various post accident tests including drug testing. All test results were negative and did not provide any further insight as to a possible cause of the accident.

The vehicle was not impounded by the Department of Transportation and was released back to Horwith immediately. A DOT Inspection at the scene did not reveal any mechanical deficiencies with unit #242. The ECM was downloaded post accident. The average driver speed for February 1st 2016 was 52.1mph. The exact speed at impact cannot be validated by the ECM as the tires continued to rotate once the vehicle overturned. The vehicle is currently in the process of being repaired.

A copy of the police investigation report was requested but not received as of February 17, 2016. However, our driver did inform Horwith he received three citations in the mail. The charges include: Securing Loads in Vehicle, Driving on Roadways Laned for Traffic, Unlawful Activities. (See Attached) The citations were issued directly to Mr. Gagliano and are his responsibility. He has indicated he will be taking a hearing for each. Horwith did not receive any citations regarding this accident.

**Conclusion & Action Items**

In reviewing the details available to date, the cause of the accident is deemed driver error. There is no indication of a third party event that would have lead the truck #242 leaving the roadway for any reason.

Weather – Clear & Dry – Weather did not play a factor regarding visibility.
Vehicle – No mechanical deficiencies were revealed during the post-accident investigation. Manifest verified truck was transporting within legal weight limits for highway transportation.
Medical – All medical and drug test result have been concluded and did not reveal any medical reason the driver was unconscious prior to the accident.
Driver – Driver was not able to provide any memory or reasoning why he was unable to maintain control of unit #242.

Action Items:

- Mr. Gagliano employment with Horwith Trucks has been terminated.
- Immediately following the accident, Horwith reevaluated our company speed policy. All triaxles have been reset with a maximum speed limiter of 62mph. We researched and implemented additional mechanical settings to automatically apply the Jake Break for attempted override of the speed limiter setting.
- ECM Monitoring Policy implemented. Each time a vehicle is brought into our facility for service, the truck ECM will be downloaded and reviewed to monitor aggressive driving habits. These reports are reviewed directly by top management.
- All Horwith drivers have recently attended a Smith System driver training course. This course focuses on defensive driving techniques. We have currently held two courses and will be including this training in our new driver orientation program.
- Electronic logging and driver management technology. Horwith has been meeting with various global technology providers to team up with to capture our employee logs electronically along with speed gauge and aggressive driving monitoring services.
- A final analysis of the accident will be reviewed once the police report is received.

Report Prepared by Kellie Heffley, Director of Safety & Compliance for Horwith Trucks.

# COPIES OF DRIVER CHARGES

1449 Nor-Bath Blvd, PO Box 7
Northampton, PA 18067

EALTH OF PENNSYLVANIA
District No. 03-2-03
areth Pike

ehem, PA 18020
-746-9740

CITATION NO.: T3244634-1
Docket Number Assigned by Court:
MJ-03203-TR-0000183-2016

FILED: 02/02/2016

# TRAFFIC CITATION

TR-183-16

| Defendant's First Name | Middle Name | Last Name | Suffix | Driver's Number | CDL | State | Sex |
|---|---|---|---|---|---|---|---|
| SALVATORE | J | GAGLIANO | | [redacted] | Yes | PA | M |

| Defendant's Address Street | City | State | Zip Code | D.O.B. | Primary Phone No. | 2nd Phone No. |
|---|---|---|---|---|---|---|
| 2[redacted] | H[redacted] | [redacted] | [redacted] | [redacted] | [redacted] | |

| | Veh. Reg. No. | Reg. Yr. | State | Model Yr. | Make | Model | Style | Color |
|---|---|---|---|---|---|---|---|---|
| PRIMARY VEHICLE | AF86558 | 2016 | PA | 2011 | FRHT | | Dump | Blue |
| TRAILING UNIT 1 | | | | | | | | |
| TRAILING UNIT 2 | | | | | | | | |

| Owner/Lessee or Carrier | First Name | Middle Name | Suffix |
|---|---|---|---|
| L V COMPANY | HORWITH TRUCKING, INC | | |

| Owner Street Address | City | State | Zip Code |
|---|---|---|---|
| ROUTE 329, PO BOX 7 | NORTHAMPTON | PA | 18067 |

| Charge | | |
|---|---|---|
| SECURING LOADS IN VEHICLES | | TITLE 75 |
| Nature of Offense: OPERATED A VEHICLE WITH A LOAD IMPROPERLY FASTENED | 67 PA Code | Section: 4903 / Subsection: B |
| | Ref. 49 CFR | FINE: 100.00 |

| Actual Speed | Allowed Speed | Timing Device | Fine Doubled Due To | | | | | |
|---|---|---|---|---|---|---|---|---|
| | | | | | | | E.M.S. | $ 10.00 |

| Offense Date | Time | Day | Vehicle Weight | Permitted Weight | File on Info. Rec'd | Lab Serv. Requested | | |
|---|---|---|---|---|---|---|---|---|
| 02/01/2016 | 15:00 | Monday | lbs. | 80,000.00 lbs. | No | No | SURCHARGE | $ 45.00 |

| Comm. Veh. | HazMat | Juvenile | Parents Notified | Accident Rpt. | Incident Number | Weather Conditions | | |
|---|---|---|---|---|---|---|---|---|
| Yes | Yes | No | No | Yes | M06-1625496 | No Adverse Conditions | COSTS | $ 0.00 |

| Location | | |
|---|---|---|
| ON PA-33 N AT MM 3.6 | J.C.P./A.T.J. | $ 10.00 |
| | | |

| Route | Dir. of Travel | Interstate | County | Twp-Boro-City | | |
|---|---|---|---|---|---|---|
| 0033 | N | No | NORTHAMPTON | BETHLEHEM TWP | Total Due | 165.00 |

| Speed Timing Device Operator | Miles Followed | Miles Timed | Secs. Timed | Special Activity |
|---|---|---|---|---|
| | | | | None |

| Stopped By | Observed By | Speed Detection Type | Station Equip. Tested | Date Equip. Tested | Speed Equip. Serial No. |
|---|---|---|---|---|---|
| Unmarked | Unmarked | | | | |

Remarks
-FREIGHTLINER

I verify that the facts set forth in this citation are true and correct to the best of my knowledge, information and belief. This verification is made subject to the penalties of Section4904 of the Crimes Code (18 Pa.C.S. § 4904) relating to the unsworn falsification to authorities.

| Officer | | Officer ID No. |
|---|---|---|
| PAPPAS | E-FILED | 658910 |

| THIS CITATION HAS BEEN ISSUED/FILED BY A MEMBER OF THE | | ORI Number | Phone Number |
|---|---|---|---|
| | PA STATE POLICE - BELFAST | PAPSP2100 | (610)759-6106 |

## RIGHTS AND OBLIGATIONS

**This citation will be filed with the magisterial district judge whose address appears above.**

1. Within ten (10) days of the receipt of this citation you must;
a. PLEAD NOT GUILTY by notifying the proper Magisterial District Judge in writing, signing the appropriate plea below, and by forwarding for collateral an amount equal to the Total Due plus $8.00 if the offense charged is under the Vehicle Code; or if the Total Due is not specified, by forwarding the sum of $50.00 as collateral for your appearance at trial

**OR**

b. PLEAD NOT GUILTY by appearing before the proper Magisterial District Judge and posting such collateral for your appearance as the Magisterial District Judge shall require

**OR**

c. Appear before the proper Magisterial District Judge to enter a plea if you cannot afford to pay the Total Due or the $50.00 collateral

**OR**

d. PLEAD GUILTY by notifying the proper Magisterial District Judge in writing, signing the appropriate plea below, and by forwarding an amount equal to the Total Due as specified, or by making payments online through Pennsylvania's Unified Judicial System web portal. Visit the portal at <http://ujsportal.pacourts.us> to make a payment.

**OR**

e. PLEAD GUILTY by appearing before the proper Magisterial District Judge if the Total Due is not specified or if you are required to appear because of the offense with which you are charged carries a mandatory sentence of imprisonment, for example, a violation of 75 Pa.C.S.§ 1543(b) (Driving while operating privilege is suspended or revoked.)

2. If you fail to appear for trial, the trial may be held in your absence.
3. If you have been charged with a summary offense under the Vehicle Code, failure to respond within the time specified above will result in the suspension of your driver's license, the issuance of a summons or a warrant for your arrest.
4. If you have been charged with a violation of a local ordinance or any parking offense, failure to respond within the time specified above will result in the issuance of a summons.
5. If you plead guilty or are found guilty, points may be assessed against your driver's record. An accumulation of points may result in the suspension of your driving privilege.
6. Your driving privilege WILL BE SUSPENDED if you plead guilty or are found guilty of certain offenses under the Vehicle Code, including but not limited to,75 Pa.C.S.§§ 1371, 3341, 3345, 3367, 3718, 3733, 3734, 3736, subsequent convictions of Pa.C.S.§ 3361 when occurring in an active work zone and an accident report is submitted by the police, subsequent convictions of 75 Pa. C.S.§ 1501, a violation of 75 Pa.C.S.§ 3361 when occurring in an active work zone and an accident report is submitted by the police, and a violation of 75 Pa.C.S.§ 3362 when occurring in an active work zone.
7. If you are found guilty by the Magisterial District Judge, or you plead guilty, and you wish to appeal, you have THIRTY(30) days to file an appeal for a trial in the Court of Common Pleas.
8. If you are disabled and require assistance, please contact the Magisterial District office shown above.

Explanation of Terms:
E.M.S. - Emergency Medical Service Act
SURCHARGE - Funds distributed pursuant to 75 Pa.C.S. § 6506
J.C.P./A.T.J. - Judicial Computer Project/Access to Justice

ALTH OF PENNSYLVANIA
District No. 03-2-03
reth Pike

em, PA 18020
6-9740

CITATION NO.: T3244629-3
Docket Number Assigned by Court:
MJ-03203-TR-0000182-2016

FILED: 02/02/2016

# TRAFFIC CITATION

TR-182-16

| Defendant's First Name | Middle Name | Last Name | Suffix | Driver's Number | CDL | State | Sex |
|---|---|---|---|---|---|---|---|
| LVATORE | J | GAGLIANO | | [redacted] | Yes | PA | M |

| Defendant's Address Street | City | State | Zip Code | D.O.B. | Primary Phone No. | 2nd Phone No. |
|---|---|---|---|---|---|---|
| [redacted] | [redacted]VN | [redacted] | [redacted] | [redacted] | [redacted] | |

| | Veh. Reg. No. | Reg. Yr. | State | Model Yr. | Make | Model | Style | Color |
|---|---|---|---|---|---|---|---|---|
| PRIMARY VEHICLE | AF86558 | 2016 | PA | 2011 | FRHT | | Dump | Blue |
| TRAILING UNIT 1 | | | | | | | | |
| TRAILING UNIT 2 | | | | | | | | |

| Owner/Lessee or Carrier | First Name | Middle Name | Suffix |
|---|---|---|---|
| L V COMPANY | HORWITH TRUCKING, INC | | |

| Owner Street Address | City | State | Zip Code |
|---|---|---|---|
| ROUTE 329, PO BOX 7 | NORTHAMPTON | PA | 18067 |

| Charge | |
|---|---|
| DRIVING ON ROADWAYS LANED FOR TRAFFIC | TITLE 75 |

| Nature of Offense | 67 PA Code | Section | Subsection |
|---|---|---|---|
| FAILED TO DRIVE WITHIN A SINGLE LANE AND OR MOVEMENT FROM LANE WAS NOT MADE SAFELY | | 3309 | 1 |
| | Ref. 49 CFR | FINE | $ 25.00 |
| | | E.M.S. | $ 10.00 |
| | | SURCHARGE | $ 45.00 |
| | | COSTS | $ 45.50 |
| | | J.C.P./A.T.J. | $ 10.00 |
| | | Total Due | $ 135.50 |

| Actual Speed | Allowed Speed | Timing Device | Fine Doubled Due To |
|---|---|---|---|
| | | | |

| Offense Date | Time | Day | Vehicle Weight | Permitted Weight | File on Info. Rec'd | Lab Serv. Requested |
|---|---|---|---|---|---|---|
| 02/01/2016 | 15:00 | Monday | lbs. | 80,000.00 lbs. | No | No |

| Comm. Veh. | HazMat | Juvenile | Parents Notified | Accident Rpt. | Incident Number | Weather Conditions |
|---|---|---|---|---|---|---|
| Yes | Yes | No | No | Yes | M06-1625496 | No Adverse Conditions |

| Location |
|---|
| ON PA-33 N AT MM 3.6 |

| Route | Dir. of Travel | Interstate | County | Twp-Boro-City |
|---|---|---|---|---|
| 0033 | N | No | NORTHAMPTON | BETHLEHEM TWP |

| Speed Timing Device Operator | Miles Followed | Miles Timed | Secs. Timed | Special Activity |
|---|---|---|---|---|
| | | | | None |

| Stopped By | Observed By | Speed Detection Type | Station Equip. Tested | Date Equip. Tested | Speed Equip. Serial No. |
|---|---|---|---|---|---|
| Unmarked | Unmarked | | | | |

Remarks
-FREIGHTLINER

I verify that the facts set forth in this citation are true and correct to the best of my knowledge, information and belief. This verification is made subject to the penalties of Section4904 of the Crimes Code (18 Pa.C.S. § 4904) relating to the unsworn falsification to authorities.

| Officer | | Officer ID No. |
|---|---|---|
| PAPPAS | E-FILED | 658910 |

| THIS CITATION HAS BEEN ISSUED/FILED BY A MEMBER OF THE | | ORI Number | Phone Number |
|---|---|---|---|
| | PA STATE POLICE - BELFAST | PAPSP2100 | (610)759-6106 |

## RIGHTS AND OBLIGATIONS

**This citation will be filed with the magisterial district judge whose address appears above.**

1. Within ten (10) days of the receipt of this citation you must:

a. PLEAD NOT GUILTY by notifying the proper Magisterial District Judge in writing, signing the appropriate plea below, and by forwarding for collateral an amount equal to the Total Due plus $8.00 if the offense charged is under the Vehicle Code; or if the Total Due is not specified, by forwarding the sum of $50.00 as collateral for your appearance at trial.

**OR**

b. PLEAD NOT GUILTY by appearing before the proper Magisterial District Judge and posting such collateral for your appearance as the Magisterial District Judge shall require.

**OR**

c. Appear before the proper Magisterial District Judge to enter a plea if you cannot afford to pay the Total Due or the $50.00 collateral.

**OR**

d. PLEAD GUILTY by notifying the proper Magisterial District Judge in writing, signing the appropriate plea below, and by forwarding an amount equal to the Total Due as specified, or by making payments online through Pennsylvania's Unified Judicial System web portal. Visit the portal at <http://ujsportal.pacourts.us> to make a payment.

**OR**

e. PLEAD GUILTY by appearing before the proper Magisterial District Judge if the Total Due is not specified or if you are required to appear because of the offense with which you are charged carries a mandatory sentence of imprisonment, for example, a violation of 75 Pa.C.S.§ 1543(b) (Driving while operating privilege is suspended or revoked.)

2. If you fail to appear for trial, the trial may be held in your absence.

3. If you have been charged with a summary offense under the Vehicle Code, failure to respond within the time specified above will result in the suspension of your driver's license, the issuance of a summons or a warrant for your arrest.

4. If you have been charged with a violation of a local ordinance or any parking offense, failure to respond within the time specified above will result in the issuance of a summons.

5. If you plead guilty or are found guilty, points may be assessed against your driver's record. An accumulation of points may result in the suspension of your driving privilege.

6. Your driving privilege WILL BE SUSPENDED if you plead guilty or are found guilty of certain offenses under the Vehicle Code, including but not limited to,75 Pa.C.S.§§ 1371, 3341, 3345, 3367, 3718, 3733, 3734, 3736, subsequent convictions of Pa.C.S.§ 3361when occurring in an active work zone and an accident report is submitted by the police, subsequent convictions of 75 Pa. C.S.§ 1501, a violation of 75 Pa.C.S.§ 3361when occurring in an active work zone and an accident report is submitted by the police, and a violation of 75 Pa.C.S.§ 3362 when occurring in an active work zone.

7. If you are found guilty by the Magisterial District Judge, or you plead guilty, and you wish to appeal, you have THIRTY(30) days to file an appeal for a trial in the Court of Common Pleas.

8. If you are disabled and require assistance, please contact the Magisterial District office shown above.

Explanation of Terms:
E.M.S. - Emergency Medical Service Act
SURCHARGE - Funds distributed pursuant to 75 Pa.C.S. § 6506
J.C.P./A.T.J. - Judicial Computer Project/Access to Justice

OF PENNSYLVANIA
t No. 03-2-03
Pike

PA 18020
9740

CITATION NO.: T3244686-4
Docket Number Assigned by Court:
MJ-03203-TR-0000184-2016

FILED: 02/02/2016

# TRAFFIC CITATION

72-184-16

| Defendant's First Name | Middle Name | Last Name | Suffix | Driver's Number | CDL | State | Sex |
|---|---|---|---|---|---|---|---|
| VATORE | J | GAGLIANO | | [redacted] | Yes | PA | M |

| Defendant's Address Street | City | State | Zip Code | D.O.B. | Primary Phone No. | 2nd Phone No. |
|---|---|---|---|---|---|---|
| [redacted] | [redacted] | [redacted] | [redacted] | [redacted] | [redacted] | |

| | Veh. Reg. No. | Reg. Yr. | State | Model Yr. | Make | Model | Style | Color |
|---|---|---|---|---|---|---|---|---|
| PRIMARY VEHICLE | AF86558 | 2016 | PA | 2011 | FRHT | | Dump | Blue |
| TRAILING UNIT 1 | | | | | | | | |
| TRAILING UNIT 2 | | | | | | | | |

| Owner/Lessee or Carrier | First Name | Middle Name | Suffix |
|---|---|---|---|
| L V COMPANY | HORWITH TRUCKING, INC | | |

| Owner Street Address | City | State | Zip Code |
|---|---|---|---|
| ROUTE 329, PO BOX 7 | NORTHAMPTON | PA | 18067 |

Charge: **UNLAWFUL ACTIVITIES** — TITLE 75

Nature of Offense: **OPERATED OR PERMITTED TO OPERATE A VEHICLE NOT EQUIPPED AS REQUIRED**

| 67 PA Code | Section | Subsection |
|---|---|---|
| 229.14 | 4107 | B2 |
| Ref. 49 CFR 392.16 | FINE | $ 25.00 |
| | E.M.S. | $ 10.00 |
| | SURCHARGE | $ 45.00 |
| | COSTS | $ 0.00 |
| | J.C.P./A.T.J. | $ 10.00 |
| | Total Due | $ 90.00 |

| Actual Speed | Allowed Speed | Timing Device | Fine Doubled Due To |
|---|---|---|---|
| | | | |

| Offense Date | Time | Day | Vehicle Weight | Permitted Weight | File on Info. Rec'd | Lab Serv. Requested |
|---|---|---|---|---|---|---|
| 02/01/2016 | 15:00 | Monday | lbs. | 80,000.00 lbs. | No | No |

| Comm. Veh. | HazMat | Juvenile | Parents Notified | Accident Rpt. | Incident Number | Weather Conditions |
|---|---|---|---|---|---|---|
| Yes | Yes | No | No | Yes | M06-1625496 | No Adverse Conditions |

Location: **ON PA-33 N AT MM 3.6**

| Route | Dir. of Travel | Interstate | County | Twp-Boro-City |
|---|---|---|---|---|
| 0033 | N | No | NORTHAMPTON | BETHLEHEM TWP |

| Speed Timing Device Operator | Miles Followed | Miles Timed | Secs. Timed | Special Activity |
|---|---|---|---|---|
| | | | | None |

| Stopped By | Observed By | Speed Detection Type | Station Equip. Tested | Date Equip. Tested | Speed Equip. Serial No. |
|---|---|---|---|---|---|
| Unmarked | Unmarked | | | | |

Remarks: **-FREIGHTLINER**

I verify that the facts set forth in this citation are true and correct to the best of my knowledge, information and belief. This verification is made subject to the penalties of Section4904 of the Crimes Code (18 Pa.C.S. § 4904) relating to the unsworn falsification to authorities.

| Officer | | Officer ID No. |
|---|---|---|
| PAPPAS | E-FILED | 658910 |

| THIS CITATION HAS BEEN ISSUED/FILED BY A MEMBER OF THE | | ORI Number | Phone Number |
|---|---|---|---|
| | PA STATE POLICE - BELFAST | PAPSP2100 | (610)759-6106 |

## RIGHTS AND OBLIGATIONS

**This citation will be filed with the magisterial district judge whose address appears above.**

1. Within ten (10) days of the receipt of this citation you must;
a. PLEAD NOT GUILTY by notifying the proper Magisterial District Judge in writing, signing the appropriate plea below, and by forwarding for collateral an amount equal to the Total Due plus $8.00 if the offense charged is under the Vehicle Code; or if the Total Due is not specified, by forwarding the sum of $50.00 as collateral for your appearance at trial

**OR**

b. PLEAD NOT GUILTY by appearing before the proper Magisterial District Judge and posting such collateral for your appearance as the Magisterial District Judge shall require.

**OR**

c. Appear before the proper Magisterial District Judge to enter a plea if you cannot afford to pay the Total Due or the $50.00 collateral

**OR**

d. PLEAD GUILTY by notifying the proper Magisterial District Judge in writing, signing the appropriate plea below, and by forwarding an amount equal to the Total Due as specified, or by making payments online through Pennsylvania's Unified Judicial System web portal. Visit the portal at <http://ujsportal.pacourts.us> to make a payment.

**OR**

e. PLEAD GUILTY by appearing before the proper Magisterial District Judge if the Total Due is not specified or if you are required to appear because of the offense with which you are charged carries a mandatory sentence of imprisonment, for example, a violation of 75 Pa.C.S.§ 1543(b) (Driving while operating privilege is suspended or revoked.)

2. If you fail to appear for trial, the trial may be held in your absence.
3. If you have been charged with a summary offense under the Vehicle Code, failure to respond within the time specified above will result in the suspension of your driver's license, the issuance of a summons or a warrant for your arrest.
4. If you have been charged with a violation of a local ordinance or any parking offense, failure to respond within the time specified above will result in the issuance of a summons.
5. If you plead guilty or are found guilty, points may be assessed against your driver's record. An accumulation of points may result in the suspension of your driving privilege.
6. Your driving privilege WILL BE SUSPENDED if you plead guilty or are found guilty of certain offenses under the Vehicle Code, including but not limited to,75 Pa.C.S.§§ 1371, 3341, 3345, 3367, 3718, 3733, 3734, 3736, subsequent convictions of Pa.C.S.§ 3361when occurring in an active work zone and an accident report is submitted by the police, subsequent convictions of 75 Pa. C.S.§ 1501, a violation of 75 Pa.C.S.§ 3361when occurring in an active work zone and an accident report is submitted by the police, and a violation of 75 Pa.C.S.§ 3362 when occurring in an active work zone.
7. If you are found guilty by the Magisterial District Judge, or you plead guilty, and you wish to appeal, you have THIRTY(30) days to file an appeal for a trial in the Court of Common Pleas.
8. If you are disabled and require assistance, please contact the Magisterial District office shown above.

Explanation of Terms:
E.M.S. - Emergency Medical Service Act
SURCHARGE - Funds distributed pursuant to 75 Pa.C.S. § 6506
J.C.P./A.T.J. - Judicial Computer Project/Access to Justice

# COPIES OF ANALYTICAL RESULTS

1449 Nor-Bath Blvd, PO Box 7
Northampton, PA 18067

# Sample Summary

Environmental Waste Minimization, Inc.

Job No: JC13588

City Line, 6 Horwith Drive, Northampton, PA
Project No: 04-1944

| Sample Number | Collected Date | Time | By | Received | Matrix Code | Matrix Type | Client Sample ID |
|---|---|---|---|---|---|---|---|
| JC13588-1 | 02/02/16 | 11:33 | SS | 02/03/16 | SO | Soil | #1 |
| JC13588-2 | 02/02/16 | 11:36 | SS | 02/03/16 | SO | Soil | #2 |
| JC13588-3 | 02/02/16 | 11:40 | SS | 02/03/16 | SO | Soil | #3 |
| JC13588-4 | 02/02/16 | 11:43 | SS | 02/03/16 | SO | Soil | #4 |
| JC13588-5 | 02/02/16 | 11:46 | SS | 02/03/16 | SO | Soil | #5 |
| JC13588-6 | 02/02/16 | 11:50 | SS | 02/03/16 | SO | Soil | #6 |
| JC13588-7 | 02/02/16 | 11:53 | SS | 02/03/16 | SO | Soil | #7 |
| JC13588-8 | 02/02/16 | 11:56 | SS | 02/03/16 | SO | Soil | #8 |

Soil samples reported on a dry weight basis unless otherwise indicated on result page.

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #1 | | |
| **Lab Sample ID:** | JC13588-1 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 79.9 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | 1.0 | 0.50 | mg/kg | 1 | 02/04/16 10:12 | RP | SW846 3060A/7196A |
| Solids, Percent | 79.9 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #2 | | |
| **Lab Sample ID:** | JC13588-2 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 85.4 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | 0.85 | 0.47 | mg/kg | 1 | 02/04/16 10:12 | RP | SW846 3060A/7196A |
| Solids, Percent | 85.4 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #3 | | |
| **Lab Sample ID:** | JC13588-3 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 94.4 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | 7.4 | 0.42 | mg/kg | 1 | 02/04/16 10:06 | RP | SW846 3060A/7196A |
| Solids, Percent | 94.4 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #4 | | |
| **Lab Sample ID:** | JC13588-4 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 81.8 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | 1.0 | 0.49 | mg/kg | 1 | 02/04/16 10:12 | RP | SW846 3060A/7196A |
| Solids, Percent | 81.8 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #5 | | |
| **Lab Sample ID:** | JC13588-5 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 86.0 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | 11.0 | 0.47 | mg/kg | 1 | 02/04/16 10:12 | RP | SW846 3060A/7196A |
| Solids, Percent | 86 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #6 | | |
| **Lab Sample ID:** | JC13588-6 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 79.7 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | < 0.50 | 0.50 | mg/kg | 1 | 02/04/16 10:12 | RP | SW846 3060A/7196A |
| Solids, Percent | 79.7 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #7 | | |
| **Lab Sample ID:** | JC13588-7 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 73.5 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Oil and Grease | < 640 | 640 | mg/kg | 1 | 02/03/16 20:15 | LS | SW846 9071B |
| Solids, Percent | 73.5 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | #8 | | |
| **Lab Sample ID:** | JC13588-8 | **Date Sampled:** | 02/02/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 02/03/16 |
| | | **Percent Solids:** | 74.3 |
| **Project:** | City Line, 6 Horwith Drive, Northampton, PA | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Oil and Grease | < 670 | 670 | mg/kg | 1 | 02/03/16 20:15 | LS | SW846 9071B |
| Solids, Percent | 74.3 | | % | 1 | 02/03/16 17:00 | KP | SM2540 G-97 |

RL = Reporting Limit

ACCUTEST LABORATORIES

So

# CHAIN OF CUSTODY

PAGE ___ OF ___

2235 Route 130, Dayton, NJ 08810
TEL: 732-329-0200 FAX: 732-329-3499/3480
www.accutest.com

FED-EX Tracking #: | Bottle Order Control #:
Accutest Quote #: | Accutest Job #: JC13588

**Client / Reporting Information**

Company Name: EWMI (RAPID RESPONSE)
Street Address: 14 Brick Kiln CT
City / State / Zip: Northampton, PA 18067
Project Contact / E-mail: Scott Soden SSODEN@EWMI.com
Phone # / Fax #: 484-275-6945
Sampler(s) Name(s) / Phone #: Scott Soden 484-275-6945

**Project Information**

Project Name: Hornwith Trucks RT 33
Street:
City / State:
Project #: 1944
Client Purchase Order #: 04-1944
Project Manager: Scott Soden

Billing Information (if different from Report to)
Company Name:
Street Address:
City / State / Zip:
Attention:

**Requested Analysis (see TEST CODE sheet)**

Hexavalent Chrome
Oil & Grease

**Matrix Codes**

DW - Drinking Water
GW - Ground Water
WW - Water
SW - Surface Water
SO - Soil
SL - Sludge
SED - Sediment
OI - Oil
LIQ - Other Liquid
AIR - Air
SOL - Other Solid
WP - Wipe
FB - Field Blank
EB - Equipment Blank
RB - Rinse Blank
TB - Trip Blank

| Accutest Sample # | Field ID / Point of Collection | MEOH/DI Vial # | Collection Date | Collection Time | Sampled by | Matrix | # of bottles | Number of preserved Bottles: HCl | MeOH | HNO3 | H2SO4 | NaOH | Zn Acetate | DI Water | MeOH | EnCore | Hexavalent Chrome | Oil & Grease | LAB USE ONLY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | #1 | | 2/2/16 | 8133 | | Soil | 1 | | | | X | | | | | | X | -1 | DL3 |
| | #2 | | 2/2/16 | 1136 | | Soil | 1 | | | | X | | | | | | X | -2 | |
| | #3 | | 2/2/16 | 1145 | | Soil | 1 | | | | X | | | | | | X | -3 | |
| | #4 | | 2/2/16 | 1143 | | Soil | 1 | | | | X | | | | | | X | -4 | |
| | #5 | | 2/2/16 | 1146 | | Soil | 1 | | | | X | | | | | | X | -5 | |
| | #6 | | 2/2/16 | 1150 | | Soil | 1 | | | | X | | | | | | X | -6 | |
| | #7 | | 2/2/16 | 1153 | | Soil | 1 | | | | X | | | | | | | X | -7 |
| | #8 | | 2/2/16 | 1156 | | Soil | 1 | | | | X | | | | | | | X | -8 |

**Turnaround Time (Business days)**

Approved By (Accutest PM): / Date:

- ☐ Std. 10 Business Days
- ☐ 5 Day RUSH
- ☐ 3 Day EMERGENCY
- ☐ 2 Day EMERGENCY
- ☒ 1 Day EMERGENCY
- ☐ other

Emergency & Rush T/A data available VIA Labtrak

**Data Deliverable Information**

- ☐ Commercial "A" (Level 1)
- ☐ Commercial "B" (Level 2)
- ☐ FULLT1 (Level 3+4)
- ☐ NJ Reduced
- ☐ Commercial "C"
- ☐ NYASP Category A
- ☐ NYASP Category B
- ☐ State Forms
- ☐ EDD Format
- ☐ Other

Commercial "A" = Results Only
Commercial "B" = Results + QC Summary
NJ Reduced = Results + QC Summary + Partial Raw data

**Comments / Special Instructions**

INITIAL ASSESSMENT Am 2/8
LABEL VERIFICATION Am

**Sample Custody must be documented below each time samples change possession, including courier delivery.**

11:03

| Relinquished by Sampler: | Date Time: | Received By: | Relinquished By: | Date Time: | Received By: |
|---|---|---|---|---|---|
| 1 | 2/2/16 1315 | 1 Robert Chambers | 2 Robert Chambers | 2-3-16 | 2 |
| Relinquished by Sampler: | Date Time: | Received By: | Relinquished By: | Date Time: | Received By: |
| 3 | | 3 | 4 | | 4 |
| Relinquished by: | Date Time: | Received By: | Custody Seals: ☐ Intact ☐ Not Intact | Preserved where applicable ☐ | On Ice ☒ Cooler Temp. 2.6°c/IP |
| 5 | | 5 | | | |

**JC13588: Chain of Custody**
**Page 1 of 2**

ACCUTEST LABORATORIES

# Accutest Laboratories Sample Receipt Summary

**Accutest Job Number:** JC13588 **Client:** **Project:**

**Date / Time Received:** 2/3/2016 11:03:00 AM **Delivery Method:** **Airbill #'s:**

Cooler Temps (Raw Measured) °C: Cooler 1: (2.6);

Cooler Temps (Corrected) °C: Cooler 1: (3.0);

| Cooler Security | Y or N | | Y or N |
|---|---|---|---|
| 1. Custody Seals Present: | ☑ ☐ | 3. COC Present: | ☑ ☐ |
| 2. Custody Seals Intact: | ☑ ☐ | 4. Smpl Dates/Time OK | ☑ ☐ |

| Cooler Temperature | Y or N |
|---|---|
| 1. Temp criteria achieved: | ☑ ☐ |
| 2. Cooler temp verification: | IR Gun |
| 3. Cooler media: | Ice (Bag) |
| 4. No. Coolers: | 1 |

| Quality Control Preservation | Y or N | N/A |
|---|---|---|
| 1. Trip Blank present / cooler: | ☐ ☐ | ☑ |
| 2. Trip Blank listed on COC: | ☐ ☐ | ☑ |
| 3. Samples preserved properly: | ☑ ☐ | |
| 4. VOCs headspace free: | ☐ ☐ | ☑ |

| Sample Integrity - Documentation | Y or N |
|---|---|
| 1. Sample labels present on bottles: | ☑ ☐ |
| 2. Container labeling complete: | ☑ ☐ |
| 3. Sample container label / COC agree: | ☑ ☐ |


| Sample Integrity - Condition | Y or N |
|---|---|
| 1. Sample recvd within HT: | ☑ ☐ |
| 2. All containers accounted for: | ☑ ☐ |
| 3. Condition of sample: | Intact |

| Sample Integrity - Instructions | Y or N | N/A |
|---|---|---|
| 1. Analysis requested is clear: | ☑ ☐ | |
| 2. Bottles received for unspecified tests | ☐ ☑ | |
| 3. Sufficient volume recvd for analysis: | ☑ ☐ | |
| 4. Compositing instructions clear: | ☐ ☐ | ☑ |
| 5. Filtering instructions clear: | ☐ ☐ | ☑ |

Comments



**JC13588: Chain of Custody**
**Page 2 of 2**


NOT TO SCALE
SAMPLES TAKEN AT THE EDGE of THE HARD shoulder
APPROX 15 FT APART
RT33 N.B
CENTER SHOULDER
#1 LANE
#2 LANE
RIGHT SHOULDER
6
5
4
3
2
1
WHERE TRUCK WAS RESTING
6 SAMPLES
36
MILEMARKER

# DEP RESPONSE REPORT

1449 Nor-Bath Blvd, PO Box 7
Northampton, PA 18067

# DEPARTMENT OF ENVIRONMENTAL PROTECTION
# EMERGENCY RESPONSE FIELD INSPECTION REPORT

| | |
|---|---|
| **Type of incident:** Truck overturned on Route 33 North hauling hazardous waste, hexavalent chromium contaminated soil | **Date:** Mon. 2/1/2016 |
| **Facility or Location: Rte 33 North at Milemarker 3.6** | |
| **Municipality:** Bethlehem Twp. | **County:** Northampton |
| **Latitude:** 40° 40' 33.9" | **Longitude:** 75° 17' 27.2" |
| **Call Out Time:** 1600hrs | **Return Time:** 2358hrs |
| **Site Arrival Time:** 1630hrs | **Site Departure Time:** 2310hrs |
| **Beginning Mileage:** | **Ending Mileage:** |
| **Complainant Name and Address: N/A** | |
| **Telephone Number (  )** | |
| **Responsible Party Name and Address:** Truck owner/Hazardous waste transporter – Horwith Trucking, Inc., Route 329, P.O. Box 7, Northampton, PA 18067; Hazardous waste generator – Honeywell, Inc., 115 Tabor Rd., Morris Plains, NJ 07950-4262 | |
| **Telephone Number** (610) 261-2220 Horwith Trucks; 973-455-4252 – Honeywell, John Mojka (Contact on Manifest) | |
| **Weather Conditions:** Clear, Temp 40s | |

**Remarks:** 1600hrs – Call from Kevin Augustine, ER Mgr., to respond to the truck accident on Rte. 33 North involving hexavalent chromium-contaminated soil. Accident occurred about 1500hrs.

Called Jeff Stire, Northampton County EMA, to confirm location and directions into the scene. 1630hrs – Arrived at the accident scene – Northampton County EMA, Lehigh County Hazmat, PennDOT, PSP, and Bethlehem Twp and Nancy Run Fire Co., Rapid Response, Fast Lane Towing and Transport, on-scene; Horwith Tri-axle truck was overturned on the northbound shoulder of Rte. 33 N. at milemarker 3.6. Truck was hauling the soil from a Honeywell Site located at 60 Kellogg St., Jersey City, NJ to the Horwith Trucking yard in Northampton to be loaded into Norfolk So. Rail cars for transport to Heritage Environmental Services facility in Indianapolis, IN via a CSX rail siding and Heritage trucks into the TSD. The manifest listed an estimated quantity of the hazardous waste (D007-TCLP hazardous for Cr) at 47,520 lbs. and listed a concentration range of 240- <1000ppm Hexavalent Cr. The truck was overturned, but the white sack/containment bladder appeared to be intact and for the most part still lying within the side of the bed on the truck. Work crews from Fast Lane Towing and Transport and Rapid Response performed the waste removal in Level C PPE and off-loaded the soils into two rolloff containers for transportation to the Horwith facility. Plastic was laid in front of the waste bladder and underneath the portion hanging out of the truck before the bladder was cut open and the waste soils were off-loaded. The soils appeared to be moist and no dust was observed during the transfer of the soils into the rolloffs. The backhoe and truck were deconned after the soils were removed. After the soil was removed, the truck was righted to be towed away and the truck and the area where the truck laid were examined. There did not appear to be a diesel fuel spill, but a small puddle of motor oil was observed, which the Rapid Response crew soaked up with pads and then scraped out the area with a backhoe. I left the Site after the truck was righted, the shoulder inspected, and the crews were finishing up the cleanup.

| | | |
|---|---|---|
| **Materials Used:** N/A | | |
| **Sample Collected?** N/A | **Sample Numbers:** | **Analysis?** |
| **Investigated By: J. Kunkle (ER-JK-02012016)** | **PADEP** | **Northeast Regional Office** |

**4/13/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

April 13, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-03**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from March 1 – March 31, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: March 2016 SA-6/7 Combined Monthly Progress Report No. 2016-03

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2016-03
### Project SA-6 & 7 Remediation

# March 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/10/16 | Combined Monthly Progress/Highlights Report No. 2016-02<br>Study Areas 6 and 7<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/11/16 | Spark Testing of Liner Boots RTC<br>Study Area 6 North Chromium Remedy<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/15/16 | Special Master Meeting | n/a |
| 03/16/16 | BEP -- USACE Additional Information Request and Response<br>Study Area 7 Sediment<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/16/15 | NMFS E-mail: BEP - Pre-Construction Notice for NWP No 27<br>Study Area 7 Sediment<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/16/16 | Declaration<br>Study Area 6 South Chromium Remedy<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/17/16 | Evaluation of Depressurization Pumping<br>Study Area 6 Groundwater<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/18/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 03/21/16 | Request for Initial Consultation<br>Pedestrian Bridge<br>Study Area 7 Sediment<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 03/22/16 | Design Change Bulletin: Horizon B and Horizon C Planting Soils<br>New Sources of Imported Fill Identification<br>Study Area 6<br>Jersey City, New Jersey<br>*(One DCB was specific to Nature's Choice Horizon C Soils, One DCB was related to Horizon B Soils and Alternative Horizon C Soils)* | The Honorable Robert G. Torricelli<br>Office of the Special Master |

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 03/30/16 | Groundwater Sampling<br>Study Area 6 South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## B. SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 03/06/16 | 03/13/16 | 03/20/16 | 03/27/16 |
| **Construction Management (AMEC)** | 7 | 8 | 8 | 8 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 29 | 25 | 26 | 26 |
| **Arecon/US Ecology Subcontractors** | 1 | 2 | 0 | 0 |
| **Eglentowicz (Demolition)** | 6 | 1 | 0 | 3 |
| **Langan** | 0 | 0 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 0 | 1 | 1 |
| **Cornerstone** | 0 | 0 | 0 | 0 |
| **TOTAL STAFF** | **49** | **42** | **41** | **44** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected March PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Conducted 6-month performance assessment soil sampling from the in-situ treatment area TA-10-1 in accordance with the updated Work Plan, dated August 2015 for the in-situ treatment of hexavalent chromium (Cr(VI)) impacted soils (results pending).
- Continued pre-demolition activities associated with 60/72 Kellogg to include terminating the gas and electric service, and completing the asbestos, rodent and universal waste abatement activities.
- Conducted quarterly regional LTMP groundwater level monitoring event.
- Completed S-3 Mass Removal Injection Event No. 27 in well 088-IW-02.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on March 15, 2016.
- Initiated piping layout plans for routing the Contingent Groundwater Extraction System force mains from SA-6 North and South to the existing GWTP Neutralization Tank.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 03/06/16 | 03/13/16 | 03/20/16 | 03/27/16 |
| Avg. Gallons Treated & Discharged (per day) | 78,884 | 79,334 | 78,927 | 79,097 |
| Average Flow (gpm) for Operating Period | 55 | 57 | 57 | 57 |
| Avg. Hours of Plant Operation | 24 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 4,370 | 5,300 | 5,771 | 4,318 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed dewatering and excavation activities of Site 163.
- Completed abandonment of the temporary Deep Extraction Well, DW8.
- Completed placement of backfill in Site 163 excavations in residential footprint.
- Continued backfilling of EA-2/EA-3 excavation area.
- Completed backfilling and restoration of EA-8.
- Completed excavation and backfilling of the anomalous material area observed within the northern portion of EA-1 up to the property line at Culver Circle.
- Completed trenching for installation of the Contingent Groundwater Extraction System piping on SA-6 North. A total of 260 linear feet of collection pipe was installed.
- Began backfilling the SA-6 North CGWES pipeline and installed the risers on manholes.
- On March 22, Amec sampled the proposed Nature's Choice Horizon C stockpiled soils for the additional hexavalent chromium analysis agreed upon with the parties. Results will be submitted when final.

## 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 1 | 14 | 14 |
| **Horwith** | Tri-axle | PA Transload | US Ecology | >240 mg/kg CrVI | 25 | 21.39 | 534.91 |
| **Entact/Horwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non-haz "C" | 9 | 21.8 | 197 |
| **Entact/Hortwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non Haz Petroleum | 85 | 23.63 | 2009 |
| **Entact/Horwith** | Tri-axle Dump | Middlesex County Landfill, NJ | MCUA | Non-haz "B" | 19 | 23 | 437 |
| **Common Carrier** | Roll-off | Tullytown, Pa | Waste Management | Non Friable ACM | 1 | 30 cyds. | 30 cyds. |

## 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | Excavation Site 163 Complete - Total for Reporting Period (Site 163): 225 CY/ Total: 7,132.5 CY<br>Excavation SA-6 North Complete - Total to Date (SA-6 North): 39,443 CY |
| **Backfill in Progress** | EA-2/EA-3, Site 163, SA-6 South Utility Corridor (C Street), EA-1 Completed in March |

## 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 03/06/16 | 03/13/16 | 03/20/16 | 03/27/16 |
| Tilcon 1.5" Stone | 350.86 | 0 | 0 | 0 |
| Tilcon Mount Hope I-8 | 0 | 0 | 987.97 | 0 |
| Natures Choice Topsoil | 150.83 | 65.54 | 0 | 0 |

- Screened Celgene material was placed as protective cover soil in the SA-6 South cap area along edges which were disturbed during the temporary plastic cover installation.
- Overburden historic fill soils with hexavalent chromium concentrations confirmed to be < 20 mg/kg soils were placed as backfill in Site 163.
- Historic fill soils identified to be < 20 mg/kg hexavalent chromium were placed as backfill in EA-2/EA-3.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.
- Area 2N: Surcharging and offloading of surcharge material is complete.
- Area 3N: Surcharge complete. Began offloading of Area 3N.
- Area 4N: Surcharge complete. Began offloading of Area 4N.

## F. SHEET PILE OPERATIONS

- Completed installation of sheet pile for temporary excavation support at Site 163.
- Begin grouting Hydraulic Barrier Wall interlocks on SA-6 North.

## G. CAPPING OPERATIONS

- Completed evaluations of potential alternative fill source(s), of both Horizon B and C Soils for the SA-6 South open space area. Conditions for acceptability of Nature's Choice Horizon C soils were agreed upon. A separate short list of potential Horizon B and C soil source vendors and the Dr. Jason Grabosky of Rutgers University recommendations were submitted to all parties for review as part of DCB 2016-03-18.
- Completed installation of additional panels of temporary plastic sheeting on the SA-6 South Cap.
- Continued placement of Structural Fill Material in the SA-6 South Cap Area corridor (C Street).

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 | Not Specified, Est. 3/31/2016 | 6/30/2016 | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete EA-2/EA-3 backfilling activities.
- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.
- Resume import and placement of Horizon C Soils from Nature's Choice on the SA-6 South open space area. Pending approval of Horizon B and alternative Horizon C sources, we will import as soon as possible.
- Complete grouting of Hydraulic Barrier Wall interlocks.
- Begin demolition of 60 and 72 Kellogg Street above-grade structures.

- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal injection event no. 28 in well 088-IW-03.
- Continue to develop CGWES piping layout plans for connection to GWTP Neutralization Tank.


**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data *(not included in this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update *(not included in this reporting period)*
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 3/31/16

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Area C Dozer Spreading Backfill at Site 163.




**Site Photograph 2:** Area C Excavation at Site 163.



**Site Photograph 3:** Area EA-8 Restoration at JC Properties.



**Site Photograph 4:** Grading Structural Fill in future utility corridor.




**Site Photograph 5:** Loading concrete debris from Site 163.




**Site Photograph 6:** Removing temporary sheet pile at Area C Site 163.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
## Progress as of April 1, 2016




**Legend**

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

# Attachment 4: Dewatering Operations Update

**STUDY AREA 6 SOUTH DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 12/18/15 | 1 | 24 | 19 | 10 | N/A | N/A | 1,700 | 3,112,472 | 1.2 | System Taken Offline |
| 01/14/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 5,000 | 3,117,472 | 3.5 | |
| 01/15/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,122,472 | 3.5 | |
| 01/18/16 | 1 | 72 | 22,23,24 | 23 | N/A | N/A | 15,000 | 3,137,472 | 3.5 | |
| 01/19/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,142,472 | 3.5 | System Offline for Excavation |
| 02/05/16 | 1 | 24 | 22,23,24 | 23 | N/A | N/A | 5,000 | 3,147,472 | 3.5 | |
| 02/08/16 | 1 | 72 | 22,23,24 | 23 | N/A | N/A | 15,000 | 3,162,472 | 3.5 | |
| 02/09/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 5,000 | 3,167,472 | 3.5 | |
| 02/10/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 3,000 | 3,170,472 | 2.1 | |
| 02/11/16 | 1 | 24 | 22,23,24 | 27 | N/A | N/A | 3,000 | 3,173,472 | 2.1 | |
| 02/12/16 | 1 | 24 | 22,23,24 | 21 | N/A | N/A | 3,000 | 3,176,472 | 2.1 | |
| 02/16/16 | 1 | 96 | 22,23,24 | 21 | N/A | N/A | 2,000 | 3,178,472 | 0.3 | |
| 02/17/16 | 1 | 24 | 22,23,24 | 15 | N/A | N/A | 1,000 | 3,179,472 | 0.7 | |
| 02/18/16 | 1 | 24 | 22,23,24 | 8 | N/A | N/A | 1,000 | 3,180,472 | 0.7 | |
| 02/19/16 | 1 | 24 | 22,23,24 | 8 | N/A | N/A | 1,500 | 3,181,972 | 1.0 | |
| 02/22/16 | 1 | 72 | 22,23,24 | 3 | N/A | N/A | 4,000 | 3,185,972 | 0.9 | |
| 02/23/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,186,972 | 0.7 | |
| 02/24/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,187,972 | 0.7 | |
| 02/25/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,188,972 | 0.7 | |
| 02/26/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,189,972 | 0.7 | |
| 02/27/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 500 | 3,190,472 | 0.3 | |
| 02/28/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 500 | 3,190,972 | 0.3 | |
| 02/29/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 500 | 3,191,472 | 0.3 | |
| 03/01/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 500 | 3,191,972 | 0.3 | |
| 03/02/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,192,972 | 0.7 | |
| 03/03/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,193,972 | 0.7 | System Offline for Excavation |

Notes: Previous information is truncated. Only last month and current month information is provided.
Site 163 Excavation was completed and the system was turned off.

# Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 01/14/16 | 9:30 | 14:00 | 4:30 | 39,510.66 | 39,562.31 | 51,650 | 39,418,460 | |
| 02/01/16 | 7:30 | 13:15 | 5:45 | 39,562.31 | 39,632.04 | 69,730 | 39,488,190 | |
| 02/02/16 | 7:00 | 11:30 | 4:30 | 39,632.04 | 39,691.51 | 59,470 | 39,547,660 | PVSC Compliance Sample Collected |
| 02/03/16 | 7:30 | 15:30 | 8:00 | 39,691.51 | 39,789.38 | 97,870 | 39,645,530 | |
| 02/04/16 | 8:00 | 15:30 | 7:30 | 39,789.38 | 39,869.34 | 79,960 | 39,725,490 | |
| 02/05/16 | 8:00 | 15:30 | 7:30 | 39,869.34 | 39,962.83 | 93,490 | 39,818,980 | |
| 02/06/16 | 8:00 | 14:00 | 6:00 | 39,962.83 | 40,010.68 | 47,850 | 39,866,830 | |
| 02/08/16 | 7:15 | 15:15 | 8:00 | 40,010.68 | 40,119.75 | 109,070 | 39,975,900 | |
| 02/09/16 | 8:30 | 15:30 | 7:00 | 40,119.75 | 40,195.00 | 75,250 | 40,051,150 | |
| 02/10/16 | 9:30 | 15:30 | 6:00 | 40,195.00 | 40,313.68 | 118,680 | 40,169,830 | |
| 02/11/16 | 10:30 | 15:30 | 5:00 | 40,313.68 | 40,407.45 | 93,770 | 40,263,600 | |
| 02/16/16 | 10:00 | 16:00 | 6:00 | 40,407.45 | 40,472.48 | 65,030 | 40,328,630 | |
| 02/17/16 | 7:00 | 15:30 | 8:30 | 40,472.48 | 40,635.48 | 163,000 | 40,491,630 | |
| 02/18/16 | 9:30 | 14:30 | 5:00 | 40,635.48 | 40,695.00 | 59,520 | 40,551,150 | |
| 02/22/16 | 7:30 | 13:00 | 5:30 | 40,695.00 | 40,767.90 | 72,900 | 40,624,050 | |
| 02/23/16 | 7:30 | 15:00 | 7:30 | 40,767.90 | 40,847.01 | 79,110 | 40,703,160 | |
| 02/24/16 | 8:30 | 15:00 | 6:30 | 40,847.01 | 40,947.06 | 100,050 | 40,803,210 | |
| 02/25/16 | 9:00 | 16:00 | 7:00 | 40,947.06 | 41,052.04 | 104,980 | 40,908,190 | |
| 02/26/16 | 7:30 | 15:00 | 7:30 | 41,052.04 | 41,114.52 | 62,480 | 40,970,670 | |
| 02/27/16 | 9:00 | 12:30 | 3:30 | 41,114.52 | 41,172.24 | 57,720 | 41,028,390 | |
| 02/28/16 | 8:00 | 13:00 | 5:00 | 41,172.24 | 41,227.51 | 55,270 | 41,083,660 | |
| 02/29/16 | 6:30 | 15:15 | 8:45 | 41,227.51 | 41,400.89 | 173,380 | 41,257,040 | |
| 03/01/16 | 7:00 | 15:30 | 8:30 | 41,400.89 | 41,493.59 | 92,700 | 41,349,740 | |
| 03/02/16 | 7:00 | 14:00 | 7:00 | 41,493.59 | 41,607.89 | 114,300 | 41,464,040 | |
| 03/03/16 | 7:30 | 12:15 | 4:45 | 41,607.89 | 41,671.38 | 63,490 | 41,527,530 | |
| 03/04/16 | 7:30 | 15:00 | 7:30 | 41,671.38 | 41,722.53 | 51,150 | 41,578,680 | |
| 03/05/16 | 9:00 | 15:00 | 6:00 | 41,722.53 | 41,782.88 | 60,350 | 41,639,030 | |
| 03/07/16 | 8:30 | 15:30 | 7:00 | 41,782.88 | 41,826.70 | 43,820 | 41,682,850 | |
| 03/10/16 | 9:00 | 15:00 | 6:00 | 41,826.70 | 41,955.66 | 128,960 | 41,811,810 | PVSC Compliance Sample Collected |
| 03/11/16 | 9:00 | 14:45 | 5:45 | 41,955.66 | 42,015.16 | 59,500 | 41,871,310 | |
| 03/15/16 | 8:00 | 16:00 | 8:00 | 42,015.16 | 42,113.22 | 98,060 | 41,969,370 | |
| 03/16/16 | 10:15 | 13:15 | 3:00 | 42,113.22 | 42,181.63 | 68,410 | 42,037,780 | |
| 03/17/16 | 7:30 | 15:00 | 7:30 | 42,181.63 | 42,268.80 | 87,170 | 42,124,950 | |
| 03/18/16 | 8:00 | 12:30 | 4:30 | 42,268.80 | 42,308.01 | 39,210 | 42,164,160 | |
| 03/21/16 | 7:30 | 13:00 | 5:30 | 42,308.01 | 42,352.43 | 44,420 | 42,208,580 | |
| 03/22/16 | 7:30 | 14:00 | 6:30 | 42,352.43 | 42,406.76 | 54,330 | 42,262,910 | |
| 03/23/16 | 12:00 | 15:15 | 3:15 | 42,406.76 | 42,437.75 | 30,990 | 42,293,900 | |
| 03/24/16 | 7:30 | 13:00 | 5:30 | 42,437.75 | 42,475.64 | 37,890 | 42,331,790 | |
| 03/28/16 | 7:30 | 15:30 | 8:00 | 42,475.64 | 42,517.63 | 41,990 | 42,373,780 | |


Notes: Previous information is truncated. Only last month and current month information is provided

# Attachment 6: Backfill Analytical Data

| Excavated Material Location (Grid No.) | Material Designation (<20 or >240) | Stockpile ID | Estimated Stockpile Volume (CY) | Sample ID | Sample Date | Sample Time | Hex Cr Result (mg/kg) | FINAL PLACEMENT OF MATERIAL | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | <20 Backfill in Excavation (Excavation Cell) | >20 - <240 Placed Under Cap | >240 Shipped Off Site as Haz |
| EA2/EA3 | <20 | 087-EA2-20-a (bermed/trench material) | 400 | 087-EA2-20-a1 | 12/11/2015 | -- | <1.8 | Yes | | |
| | | | | 087-EA2-20-a2 | 12/11/2015 | -- | 6.7 | Yes | | |
| | | | | 087-EA2-20-a3 | 12/11/2015 | -- | <1.9 | Yes | | |
| | | | | 087-EA2-20-a4 | 12/11/2015 | -- | 3.8 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-b1:g1 (A material) | 5200 cy | 087-EA2-20-b1 | 12/30/2015 | -- | 3.0 | Yes | | |
| | | | | 087-EA2-20-b2 | 12/30/2015 | -- | 3.0 | Yes | | |
| | | | | 087-EA2-20-b3 | 12/30/2015 | -- | 0.55 | Yes | | |
| | | | | 087-EA2-20-b4 | 12/30/2015 | -- | 0.97 | Yes | | |
| | | | | 087-EA2-20-c1 | 12/30/2015 | -- | 4.3 | Yes | | |
| | | | | 087-EA2-20-c2 | 12/30/2015 | -- | 1.5 | Yes | | |
| | | | | 087-EA2-20-c3 | 12/30/2015 | -- | 1.6 | Yes | | |
| | | | | 087-EA2-20-c4 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-d1 | 12/30/2015 | -- | 0.60 | Yes | | |
| | | | | 087-EA2-20-d2 | 12/30/2015 | -- | 15.9 | Yes | | |
| | | | | 087-EA2-20-d3 | 12/30/2015 | -- | 5.4 | Yes | | |
| | | | | 087-EA2-20-d4 | 12/30/2015 | -- | 1.7 | Yes | | |
| | | | | 087-EA2-20-e1 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-e2 | 12/30/2015 | -- | 12.3 | Yes | | |
| | | | | 087-EA2-20-e3 | 12/30/2015 | -- | 3.1 | Yes | | |
| | | | | 087-EA2-20-e4 | 12/30/2015 | -- | 0.57 | Yes | | |
| | | | | 087-EA2-20-f1 | 12/30/2015 | -- | 0.52 | Yes | | |
| | | | | 087-EA2-20-f2 | 12/30/2015 | -- | 0.53 | Yes | | |
| | | | | 087-EA2-20-f3 | 12/30/2015 | -- | 0.57 | Yes | | |
| | | | | 087-EA2-20-f4 | 12/30/2015 | -- | 0.54 | Yes | | |
| | | | | 087-EA2-20-g1 | 12/30/2015 | -- | 0.53 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-h1 (overburden) | 150 cy | 087-EA2-20-h1 | 12/30/2015 | -- | 0.7 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-i1 (overburden) | 200 cy | 087-EA2-20-i1 | 12/30/2015 | -- | 0.54 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-h2:j3 (overburden) | 2200 cy | 087-EA2-20-h2 | 1/8/2016 | -- | 24.1 | | Yes | |
| | | | | 087-EA2-20-h3 | 1/8/2016 | -- | <1.4 | Yes | | |
| | | | | 087-EA2-20-h4 | 1/8/2016 | -- | 19 | Yes | | |
| | | | | 087-EA2-20-i2 | 1/8/2016 | -- | 0.66 | Yes | | |
| | | | | 087-EA2-20-i3 | 1/8/2016 | -- | <1.9 | Yes | | |
| | | | | 087-EA2-20-i4 | 1/8/2016 | -- | <1.4 | Yes | | |
| | | | | 087-EA2-20-j1 | 1/8/2016 | -- | <2.0 | Yes | | |
| | | | | 087-EA2-20-j2 | 1/8/2016 | -- | 8.9 | Yes | | |
| | | | | 087-EA2-20-j3 | 1/8/2016 | -- | <1.9 | Yes | | |
| EA2/EA3 | <20 | 087-EA2-20-k1:k4 | 1000 cy | 087-EA2-20-k1 | 1/8/2016 | -- | 7 | Yes | | |
| | | | | 087-EA2-20-k2 | 1/8/2016 | -- | 10 | Yes | | |
| | | | | 087-EA2-20-k3 | 1/8/2016 | -- | 8 | Yes | | |
| | | | | 087-EA2-20-k4 | 1/8/2016 | -- | <1.9 | Yes | | |
| Site 163 | <20 | 163-20-a | 840 | 163-20-a1 | 1/19/2016 | -- | 8.1 | Yes | | |
| | | | | 163-20-a2 | 1/19/2016 | -- | 4.0 | Yes | | |
| | | | | 163-20-a3 | 1/19/2016 | -- | 1.7 | Yes | | |
| | | | | 163-20-a4 | 1/19/2016 | -- | 5.0 | Yes | | |
| Site 163 | <20 | 163-20-a | 840 | 163-20-a5 | 2/22/2016 | -- | 2.7 | Yes | | |
| | | | | 163-20-a6 | 2/22/2016 | -- | 3.6 | Yes | | |
| | | | | 163-20-a7 | 2/22/2016 | -- | 1.0 | Yes | | |
| | | | | 163-20-a8 | 2/22/2016 | -- | 5.1 | Yes | | |
| EA1 | <20 | 087-EA1-20 | 210 | 087-EA1-20-A1 | 2/29/2016 | -- | 0.9 | Yes | | |
| | | | | 087-EA1-20-A2 | 2/29/2016 | -- | 3.2 | Yes | | |
| | | | | 087-EA1-20-A3 | 2/29/2016 | -- | 29.0 | | Yes | |
| | | | | 087-EA1-20-A4 | 2/29/2016 | -- | 2.3 | Yes | | |

Previous information is truncated. Only last two months and current month information is provided.
*Material currently stockpiled. Pending final placement.
**Waiting on final results from the laboratory.

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015

**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 4/16/2015 | 3.1 | 5.2 | 6.0 | 6.5 | 6.1 | | 2.8 | 2.1 | 5.4 | 5.5 | 6.8 | 6.2 | 5.1 | 5.2 | 5.9 | | 2.1 | 2.2 | 3.8 | 3.0 | 3.2 | 2.8 |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | | | | 4.5 | 5.0 | 3.8 | 3.5 | | | | | | |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | | | | 3.5 | 3.6 | | | | | | | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | | | | 5.2 | | | 4.6 | | | | | | |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | | | | 6.0 | | | 5.6 | | | | | | |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | | | | 6.5 | | | 6.2 | | | | | | |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | | | | 6.0 | | | 5.7 | | | | | | |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | | | | 5.6 | | | 5.0 | | | | | | |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | | | | 2.7 | | | 3.6 | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, E4-SO, W1-SO, North FS-6, North FS-7

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)

# Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

(not included in this reporting period)

# Attachment 11: Capping Update

(not included in this reporting period)

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: ~~March 4, 2016~~ March 3, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | ✓ | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | ✓ | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | ✓ | | | |
| Stockpile Tarping/Containment | ✓ | | | |
| Proper Chemical Storage | ✓ | | | |
| Containment Around Exclusion Zones | ✓ | | | |
| Water Truck Wet- Down Operation | ✓ | | | |
| Truck De-Con Operation | ✓ | | | |
| Flood Protection | ✓ | | | |
| Haul Road Maintenance | ✓ | | | |
| Perimeter Fencing/Windscreen | ✓ | | | |
| Storm Drain Protection | ✓ | | | |
| Ponded Storm Water | ✓ | | | |
| Housekeeping | ✓ | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | ✓ | | | |
| River Discharge Weir | ✓ | | X | |
| Swale Check Dams | | ✓ | X | |
| Exclusion Zone Fencing | ✓ | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | ✓ | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | / | | | |
| Proper Chemical Storage | / | | | |
| Containment Around Exclusion Zones | / | | | |
| Water Truck Wet- Down Operation | / | | | |
| Truck De-Con Operation | / | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | / | | | |
| Perimeter Fencing/Windscreen | / | | | |
| Storm Drain Protection | / | | | |
| Ponded Storm Water | / | | | |
| Housekeeping | / | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | / | | | |
| River Discharge Weir | / | | | |
| Swale Check Dams | / | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | / | | | |
| Stockpile Tarping/Containment | / | | | |
| Proper Chemical Storage | / | | | |
| Containment Around Exclusion Zones | / | | X | |
| Water Truck Wet- Down Operation | / | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | / | | X | |
| Haul Road Maintenance | / | | | |
| Perimeter Fencing/Windscreen | / | | | |
| Storm Drain Protection | / | | | |
| Ponded Storm Water | / | | | |
| Housekeeping | / | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 3/3/16

SWPPP Observer: _____
Signature

Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE

**Thursday, March 03, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | **REPEAT**: Windscreen on the SA-6 South perimeter fenceline is detached from the perimeter fence in the area of the 60 Kellogg building. |
| 2 | " | Sediment from SA-7 roadway |
| 3 | " | Trash pile outside of EA-8 |
| 4 | " | Trash on kellogg jug handle |
| 5 | " | Exclusion zone fencing is down on the west side of 1N |
| 6 | " | Bayfront banner on 440 is starting to detach |
| 7 | " | Filter fabric under storm drains is blinded, north of the trash pit |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ (Signature) **Date:** 3/3/16

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach or replace windscreen to the perimeter fence as required. | 3/10/16 RAD |
| 2 | Clean up sediment from SA-7 roadway | |
| 3 | Clean up trash pile outside of EA-8 | |
| 4 | Clean up trash on kellogg jug handle | |
| 5 | Repair exclusion zone fencing on the west side of 1N | |
| 6 | Reinforce Bayfront banner on 440 | |
| 7 | Replace filter fabric under storm drains north of the trash pit | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 03/10/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 11, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | X | | | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 4 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/11/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, March 11, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence inside of the perimeter fence line along the western end of Kellogg Street requires maintenance. |
| 2 | IA2Q4A1AL8 | Windscreen on the perimeter fence at the western end of Kellogg Street has become detached. |
| 3 | IA2Q4A1AL8 | Garbage and other debris is present along the Kellogg Street jughandle. |
| 4 | IA2Q4A1AL8 | Two catch basins in the former JCIA area to the north of the sedimentation basin require silt protection. |
| 5 | IA2Q4A1AL8 | Silt fence along the southern perimeter of the N-1 stockpile area on SA-7 requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 03/11/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace the silt fence along the Kellogg Street fenceline as required. | 3-17-16 RAD |
| 2 | Re-attach or replace windscreen on the perimeter fence as required. | ↓ |
| 3 | Pick up and discard the garbage and debris along the roadside. | |
| 4 | Install filter fabric or sediment baskets in the two catch basins as required. | |
| 5 | Repair or replace the silt fence along the northern SA-7 roadway as required. | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 03/17/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 18, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2,3 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 4 |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 5 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 6 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/21/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, March 18, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and other debris is present along the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Exclusion Zone fencing at the western end of surcharge area 1-N is down and requires maintenance. |
| 3 | IA2Q4A1AL8 | Exclusion Zone fencing along the sheetpile in the sedimentation basin area requires maintenance. |
| 4 | IA2Q4A1AL8 | There are 55 gallon drums of lubricant in the mechanics area which are not on spill pallets. |
| 5 | IA2Q4A1AL8 | Silt fencing surrounding the Novartis Stockpile area requires maintenance. |
| 6 | IA2Q4A1AL8 | Sediment has accumulated on the western haul road on SA-7. |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 03/21/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and discard the garbage and debris along the roadside. | 3/24/16 KAD |
| 2 | Repair or replace EZ fencing and signage as required. | |
| 3 | Repair or replace EZ fencing and signage as required. | |
| 4 | Place all "in-use" drums on spill pallets. | |
| 5 | Repair or replace the silt fence surrounding the Novartis Stockpile Area as required. | |
| 6 | Clean sediment from the western SA-7 haul road as required. | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 03/24/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: March 25, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 03/25/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, March 25, 2016**

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and other debris is present along the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Silt fencing along the southern toe of the 1-N surcharge area requires maintenance. |
| 3 | IA2Q4A1AL8 | Sediment fabric in a stormwater catch basin on the eastern SA-7 roadway has fallen through and requires replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 03/25/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and discard the garbage and debris along the roadside. | 3/31/16 RAD |
| 2 | Repair or replace silt fence along the southern toe of the 1-N surcharge area as required | |
| 3 | Replace the filter fabric in the eastern SA-7 roadway catch basin as required | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 03/31/16

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted March 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

March 18, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the February 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 2 | 01 | 16 | 2 | 29 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 79,211 | 84,960 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.75 | 0.80 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00021 | 0.00021 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1689 | 0.1689 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 2 | 01 | 16 | 2 | 29 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,297,112 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 56,718,528 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 2/10/2016 | <3.4 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris IHE | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 3/16/2016 |

**PVSC FORM MR-2 REV.3 6/93**

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

3/16/2016

Date

PVSC FORM MR-1 REV: 5 3/91 P2

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: February 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 2/1/2016 | Angel Trujillo | 54421416 | 54498650 | 77,234 | 0.077234 | 7.18 | 1.130 | | | | | | | | | 0.73 |
| 2/2/2016 | Angel Trujillo | 54498650 | 54577458 | 78,808 | 0.078808 | 7.78 | 1.130 | | | | | | | | | 0.74 |
| 2/3/2016 | Angel Trujillo | 54577458 | 54656198 | 78,740 | 0.07874 | 7.60 | 1.130 | | | | | | | | | 0.74 |
| 2/4/2016 | Angel Trujillo | 54656198 | 54736172 | 79,974 | 0.079974 | 7.78 | 1.130 | | | | | | | | | 0.75 |
| 2/5/2016 | Angel Trujillo | 54736172 | 54816320 | 80,148 | 0.080148 | 7.63 | 1.130 | | | | | | | | | 0.76 |
| 2/6/2016 | Angel Trujillo | 54816320 | 54900072 | 83,752 | 0.083752 | 7.68 | 1.130 | | | | | | | | | 0.79 |
| 2/7/2016 | Angel Trujillo | 54900072 | 54977848 | 77,776 | 0.077776 | 7.70 | 1.130 | | | | | | | | | 0.73 |
| 2/8/2016 | Angel Trujillo | 54977848 | 55055624 | 77,776 | 0.077776 | 7.74 | 1.130 | | | | | | | | | 0.73 |
| 2/9/2016 | Angel Trujillo | 55055624 | 55134636 | 79,012 | 0.079012 | 7.67 | 1.130 | | | | | | | | | 0.74 |
| 2/10/2016 | Angel Trujillo | 55134636 | 55216114 | 81,478 | 0.081478 | 6.85 | 1.130 | <5.1 | <3.4 | | <0.010 | <0.030 | <0.010 | 0.00021 | <0.020 | 0.77 |
| 2/11/2016 | Angel Trujillo | 55216114 | 55294078 | 77,964 | 0.077964 | 7.81 | 1.130 | | | | | | | | | 0.73 |
| 2/12/2016 | Angel Trujillo | 55294078 | 55374112 | 80,034 | 0.080034 | 7.79 | 1.130 | | | | | | | | | 0.75 |
| 2/13/2016 | Angel Trujillo | 55374112 | 55456622 | 82,510 | 0.08251 | 7.09 | 1.130 | | | | | | | | | 0.78 |
| 2/14/2016 | Angel Trujillo | 55456622 | 55533901 | 77,279 | 0.077279 | 7.70 | 1.130 | | | | | | | | | 0.73 |
| 2/15/2016 | Angel Trujillo | 55533901 | 55611180 | 77,279 | 0.077279 | 7.60 | 1.130 | | | | | | | | | 0.73 |
| 2/16/2016 | Angel Trujillo | 55611180 | 55688012 | 76,832 | 0.076832 | 7.76 | 1.130 | | | | | | | | | 0.72 |
| 2/17/2016 | Angel Trujillo | 55688012 | 55768112 | 80,100 | 0.0801 | 7.46 | 1.130 | | | | | | | | | 0.75 |
| 2/18/2016 | Angel Trujillo | 55768112 | 55846367 | 78,255 | 0.078255 | 7.81 | 1.130 | | | | | | | | | 0.74 |
| 2/19/2016 | Angel Trujillo | 55846367 | 55927468 | 81,101 | 0.081101 | 7.75 | 1.130 | | | | | | | | | 0.76 |
| 2/20/2016 | Angel Trujillo | 55927468 | 56012428 | 84,960 | 0.08496 | 7.56 | 1.130 | | | | | | | | | 0.80 |
| 2/21/2016 | Angel Trujillo | 56012428 | 56088708 | 76,280 | 0.07628 | 7.70 | 1.130 | | | | | | | | | 0.72 |
| 2/22/2016 | Angel Trujillo | 56088708 | 56164988 | 76,280 | 0.07628 | 7.90 | 1.130 | | | | | | | | | 0.72 |
| 2/23/2016 | Angel Trujillo | 56164988 | 56244394 | 79,406 | 0.079406 | 7.80 | 1.130 | | | | | | | | | 0.75 |
| 2/24/2016 | Angel Trujillo | 56244394 | 56321732 | 77,338 | 0.077338 | 7.74 | 1.130 | | | | | | | | | 0.73 |
| 2/25/2016 | Angel Trujillo | 56321732 | 56402166 | 80,434 | 0.080434 | 7.71 | 1.130 | | | | | | | | | 0.76 |
| 2/26/2016 | Angel Trujillo | 56402166 | 56481148 | 78,982 | 0.078982 | 7.57 | 1.130 | | | | | | | | | 0.74 |
| 2/27/2016 | Angel Trujillo | 56481148 | 56564090 | 82,942 | 0.082942 | 7.81 | 1.130 | | | | | | | | | 0.78 |
| 2/28/2016 | Angel Trujillo | 56564090 | 56641309 | 77,219 | 0.077219 | 7.80 | 1.130 | | | | | | | | | 0.73 |
| 2/29/2016 | Angel Trujillo | 56641309 | 56718528 | 77,219 | 0.077219 | 7.76 | 1.130 | | | | | | | | | 0.73 |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,297,112 | 2.297112 | | | <5.1 | <3.4 | | <0.010 | <0.030 | <0.010 | 0.00021 | <0.020 | |
| | | | High: | 84,960 | | | | | | | | | | | High: | 0.80 |
| | | | Average: | 79,211 | | | | | | | | | | | Average: | 0.75 |

WW

JC14033

PN

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42410.53492 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County / Phase: CS | COC# | 087-WW-021016 |
| | | Location of Site: Jersey City, NJ / Sampling Program: 097: JCIA | Lab Proj # (SDG): | |
| Sampling Co.: MACTEC | EDD To: | | Lab ID | ACTD |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | Site ID | HudsonCo |
| Helen Fahy P: (973) 455-2689 E: helen.fahy@honeywell.com | PO # | Preservative: 3 / 3 / 3 / 1 / 2 / 2 / 0 / 0 / 2 | Lab Job # | HWNJM32915 |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | | Authorized User: | Honeywell |
| 101 Columbia Road Morristown, NJ 07962 | Consultant: CH2M | | | |
| Preliminary Data To | | | Text & Excel File Drive | Excel & Text File Order |
| Sample Receipt Acknowledgement To | | | | |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs: see attached special list | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-021016-A | 2/10/2016 | 14:00 | WW | WATER | REG | 3 | comp | N | X | X | X | X | | | X | X | | | | -1 | | |
| 2 | 087-WW | | | 087-WWE-021016-B | 2/10/2016 | 14:05 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | | | -2 | | |
| 3 | 087-WW | | | 087-WWI-021016 @ | 2/10/2016 | 14:15 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | | | -3 | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

L26
V451
AYJ
G58

| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact |
|---|---|---|---|---|---|
| 685eu@ 7.9°C | AMEC Foster Wheeler | | | | |
| Frank Schroyer | Date/Time 2/10/16 | Robert Chambers | Date/Time 2-10-16 17:19 | Cooler Temp. | |
| Relinquished by | Company | Received by | Company | Condition | Custody Seals Intact |
| Robert Chambers | Date/Time 2-10-16 17:19 | DI | Date/Time 2/10/16 1715 | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

03 • VOA QC VIAL

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE 03

INITIAL ASESSMENT 2A-03

LABEL VERIFICATION NL

I.G 5.0°C

SGS Accutest LabLink@898999 11:34 08-Mar-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-021016-A | | |
| Lab Sample ID: | JC14033-1 | Date Sampled: | 02/10/16 |
| Matrix: | AQ - Water | Date Received: | 02/10/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.1
4

Total Metals Analysis

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1130 | 10 | ug/l | 1 | 02/11/16 | 02/12/16 | MS | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 02/11/16 | 02/12/16 | MS | EPA 200.7 [2] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 02/11/16 | 02/13/16 | MS | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | 0.21 | 0.20 | ug/l | 1 | 02/11/16 | 02/11/16 | VM | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 02/11/16 | 02/12/16 | MS | EPA 200.7 [2] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 02/11/16 | 02/12/16 | MS | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA38713
(2) Instrument QC Batch: MA38723
(3) Instrument QC Batch: MA38728
(4) Prep QC Batch: MP91970
(5) Prep QC Batch: MP91973

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@898871 16:38 07-Mar-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021016-A | | |
| **Lab Sample ID:** | JC14033-1 | **Date Sampled:** | 02/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | < 4.0 | 4.0 | mg/l | 1 | 02/11/16 | LA | SM2540 D-11 |
| pH [b] | 6.97 | | su | 1 | 02/10/16 17:36 | SUB | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 550 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@898871 16:38 07-Mar-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021016-A | | |
| **Lab Sample ID:** | JC14033-1A | **Date Sampled:** | 02/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.2
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 3.4 | 3.4 | mg/l | 1 | 02/10/16 19:55 | LA | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@898999 11:34 08-Mar-2016

# Report of Analysis



4.3
4

| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-021016-B | | |
| Lab Sample ID: | JC14033-2 | Date Sampled: | 02/10/16 |
| Matrix: | AQ - Water | Date Received: | 02/10/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | T215436.D | 1 | 02/12/16 | DC | n/a | n/a | VT8851 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 3.7 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 5.4 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | ND | 1.0 | 0.093 | ug/l | |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 29.8 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.37 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.40 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 65.6 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.5 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.94 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@898999 11:34 08-Mar-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-021016-B | | |
| Lab Sample ID: | JC14033-2 | Date Sampled: | 02/10/16 |
| Matrix: | AQ - Water | Date Received: | 02/10/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 59.2 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 93% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 98% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 107% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 103% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@898871 16:38 07-Mar-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-021016-B | | |
| **Lab Sample ID:** | JC14033-2 | **Date Sampled:** | 02/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 02/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 02/11/16 10:00 | JOO | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending March 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending March 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Contractor only. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groudnwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |

**SA-6 North/South Field Change Log - Month Ending March 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending March 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |

**SA-6 North/South Field Change Log - Month Ending March 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |
| **DC 2016-02-03** | The final grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Contractor only. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Contractor only. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 13 OF 25**

- **2016 Monthly Reports Part 2**

**5/12/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

May 12, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-04**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from April 1 – April 30, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: April 2016 SA-6/7 Combined Monthly Progress Report No. 2016-04

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC (electronic copy)
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-04

**Project SA-6 & 7 Remediation**

# April 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 04/12/16 | Design Change Bulletin: Horizon B and Horizon C Planting Soils<br>Study Area 6<br>Jersey City, NJ | Alicia Alcorn<br>Terris, Pravlik & Millian |
| 04/13/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-03 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/18/16 | Request for Recertification for Soil Erosion and Sediment Control Plan Certification<br>Imported Novartis Fill Stockpile – Study Area 6<br>Block 21901 Lot 6, 7, and 8<br>Jersey City, NJ | Mr. Glen Van Olden<br>Hudson-Essex-Passaic Soil Conservation District (HEPSCD) |
| 04/18/16 | Spark Testing of Liner Boots Response to Comments<br>Study Area 6 North<br>Jersey City, NJ | Alicia Alcorn<br>Terris, Pravlik & Millian |
| 4/19/2016 | Surcharge Monitoring Plan – Monthly Report No. 16<br>Study Area 6 North and South<br>Jersey City, NJ | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 04/19/16 | Special Master Conference Call | N/A |
| 04/20/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440<br>Jersey City, NJ | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 04/21/16 | Design Change Bulletin: Horizon B and Horizon C Planting Soils<br>New Sources of Imported Fill Identification<br>Study Area 6<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |

# B. SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 4/3/16 | 4/10/16 | 4/17/16 | 4/24/16 | 5/1/16 |
| Construction Management (AMEC) | 9 | 9 | 8 | 8 | 7 |
| Engineering (AMEC) | 1 | 1 | 1 | 1 | 1 |
| Air Monitoring (Emilcott) | 1 | 1 | 1 | 1 | 1 |
| Security (Securitas) | 3 | 3 | 3 | 3 | 3 |
| Entact/Subcontractors | 26 | 26 | 27 | 25 | 25 |
| Arecon/US Ecology Subcontractors | 0 | 2 | 0 | 0 | 0 |
| Eglentowicz (Demolition) | 0 | 1 | 0 | 5 | 5 |
| Century | 0 | 1 | 1 | 0 | 0 |
| Evoqua | 1 | 1 | 1 | 1 | 1 |
| B&B Drilling | 0 | 0 | 0 | 1 | 1 |
| Cornerstone | 0 | 0 | 0 | 0 | 0 |
| **TOTAL STAFF** | **41** | **45** | **42** | **45** | **44** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected April PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Conducted 6-month performance assessment soil sampling from the in-situ treatment area TA-10-1 in accordance with the updated Work Plan, dated August 2015 for the in-situ treatment of hexavalent chromium (Cr(VI)) impacted soils. Results submitted to all Parties on May 5, 2016.
- Completed demolition activities associated with 60/72 Kellogg to include demolition, loadout of demolition debris, and demolition of the above grade slab. Restoration of the site is pending evaluation of the analytical results of a sample of suspect material observed at one timber pile location below the former building slab.
- Reinstalled JCMUA water main vault and completed valve connection associated with the JCMUA water line.
- Completed S-3 Mass Removal Injection Event No. 28 in well 088-IW-03.

## C. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned upstream process (tank 201 and tank 202) pH probes, and tank 201.
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on April 12, 2016.
- Continued piping layout plans for routing the Contingent Groundwater Extraction System force mains from SA-6 North and South to the existing GWTP Neutralization Tank.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 4/3/16 | 4/10/16 | 4/17/16 | 4/24/16 | 5/1/16 |
| Avg. Gallons Treated & Discharged (per day) | 78,240 | 79,310 | 79,016 | 77,790 | 78,493 |
| Average Flow (gpm) for Operating Period | 57 | 57 | 57 | 58 | 56 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 4,322 | 3,806 | 4,492 | 3,816 | 5,500 |

## D. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Contractor completed abandonment of 3 monitoring wells (087-MW-14, 087-MW-130T, and 087-MW-OBS-6D).
- Completed backfilling of EA-2/EA-3 excavation area.
- Placed flowable concrete within the vault on the north side of the JCIA trash pit to an elevation of approximately +5.0 msl.
- Continued backfilling the SA-6 North CGWES pipeline and installed the risers on manholes.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 0 | 0 | 0 |
| **Eglentowicz/F Rover & Sons** | Roll-off | Harrison, NJ | Rover & Sons Recycling Yard | Metal | 4 | 6.9 | 27.63 |
| **Eglentowicz/ Evergreen Recycling** | Roll-off | Newark, NJ | Evergreen Recycling Solutions | Concrete | 21 | 19.45 | 408.55 |
| **Eglentowicz/ Evergreen Recycling** | Roll-off | Newark, NJ | Evergreen Recycling Solutions | C&D Debris | 8 | 16 | 127 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | Excavation Site 163 Complete - Total for Reporting Period (Site 163): 225 CY/ Total: 7,132.5 CY<br>Excavation SA-6 North Complete - Total to Date (SA-6 North): 39,443 CY |
| **Backfill in Progress** | EA-2/EA-3, SA-6 South Utility Corridor (B Street) |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 4/3/16 | 4/10/16 | 4/17/16 | 4/24/16 | 5/1/16 |
| Natures Choice Horizon C | 0 | 0 | 01,141.83 | 1,381.44 | 3,322.93 |
| Tilcon Mount Hope I-8 | 0 | 0 | 0 | 1,838 | 2,633.5 |
| Natures Choice Topsoil | 0 | 0 | 00 | 0 | 271.4 |

- Historic fill soils identified to be < 20 mg/kg hexavalent chromium were placed as backfill in EA-2/EA-3.
- Screened Celgene material was removed from the SA6-South open space area during grading of the protective cover soils. Approximately 160 cubic yard was removed from the cap area and transferred to the Celgene stockpile area.

## E. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.

- Area 2N: Surcharging and offloading of surcharge material is complete.
- Area 3N: Surcharging and offloading of surcharge material is complete.
- Area 4N: Surcharging and offloading of surcharge material is complete.

## F. SHEET PILE OPERATIONS

- Completed grouting Hydraulic Barrier Wall interlocks on SA-6 North.

## G. CAPPING OPERATIONS

- Completed repairs to exposed GDL on west side of the SA-6 South Cap.
- Regraded the GDL cover soil in GDL repair areas on the west side of the SA-6 South cap to include associated compaction testing. In addition, the underlying exposed root barrier on the west side of the cap was replaced.
- Began importing and placing Horizon C soils to include associated compaction testing and placement of underlying root barrier and demarcation tape.
- Began SA-6 North cap subgrade construction activities.
- Continued placement of Structural Fill Material in the SA-6 South Cap Area corridor (B Street).

## H. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 | Renewal Not Needed | 2/21/2016 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## I. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.
- Continue placement of Horizon C and begin importing and placing Horizon B soils.
- Continue SA-6 North cap subgrade construction activities.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Continue to develop CGWES piping layout plans for connection to GWTP Neutralization Tank.

**ATTACHMENTS:**

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data *(not included in this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead


Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



amec foster wheeler

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 5/03/16

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Delivery of Horizon C Material at SA-6 South.




**Site Photograph 2:** Demolition of 60 Kellogg Building SA-6 South.




**Site Photograph 3:** Grading Cover Soils on SA-6 South Cap.




**Site Photograph 4:** Reinstallation of the JCMUA Water Meter Valve Box.




**Site Photograph 5:** Removal of Surcharge Material at JC Properties.





**Site Photograph 6:** Restoration of EA-3 at JC Properties.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of May 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-04
Attachment 3: Excavation and Backfill




## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

# Attachment 4: Dewatering Operations Update

**STUDY AREA 6 DEWATERING DATA (HEADERS)**

| DATE | VAC PLANT NUMBER | HOURS OF OPERATION | ACTIVE HEADERS* | # OF ACTIVE WELLPOINTS | VAC PLANT FLOW METER START (Gal) | VAC PLANT FLOW METER FINISH (Gal) | EXTRACTED VOLUME (Gal) DAILY | EXTRACTED VOLUME (Gal) TOTAL | AVERAGE FLOW RATE (gpm) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|
| 03/01/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 500 | 3,191,972 | 0.3 | |
| 03/02/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,192,972 | 0.7 | |
| 03/03/16 | 1 | 24 | 22,23,24 | 3 | N/A | N/A | 1,000 | 3,193,972 | 0.7 | System Offline for Excavation |

Notes: Site 163 Excavation was completed and the system was turned off.
The information of the final month of operation is provided.

# Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 02/29/16 | 6:30 | 15:15 | 8:45 | 41,227.51 | 41,400.89 | 173,380 | 41,257,040 | |
| 03/01/16 | 7:00 | 15:30 | 8:30 | 41,400.89 | 41,493.59 | 92,700 | 41,349,740 | |
| 03/02/16 | 7:00 | 14:00 | 7:00 | 41,493.59 | 41,607.89 | 114,300 | 41,464,040 | |
| 03/03/16 | 7:30 | 12:15 | 4:45 | 41,607.89 | 41,671.38 | 63,490 | 41,527,530 | |
| 03/04/16 | 7:30 | 15:00 | 7:30 | 41,671.38 | 41,722.53 | 51,150 | 41,578,680 | |
| 03/05/16 | 9:00 | 15:00 | 6:00 | 41,722.53 | 41,782.88 | 60,350 | 41,639,030 | |
| 03/07/16 | 8:30 | 15:30 | 7:00 | 41,782.88 | 41,826.70 | 43,820 | 41,682,850 | |
| 03/10/16 | 9:00 | 15:00 | 6:00 | 41,826.70 | 41,955.66 | 128,960 | 41,811,810 | PVSC Compliance Sample Collected |
| 03/11/16 | 9:00 | 14:45 | 5:45 | 41,955.66 | 42,015.16 | 59,500 | 41,871,310 | |
| 03/15/16 | 8:00 | 16:00 | 8:00 | 42,015.16 | 42,113.22 | 98,060 | 41,969,370 | |
| 03/16/16 | 10:15 | 13:15 | 3:00 | 42,113.22 | 42,181.63 | 68,410 | 42,037,780 | |
| 03/17/16 | 7:30 | 15:00 | 7:30 | 42,181.63 | 42,268.80 | 87,170 | 42,124,950 | |
| 03/18/16 | 8:00 | 12:30 | 4:30 | 42,268.80 | 42,308.01 | 39,210 | 42,164,160 | |
| 03/21/16 | 7:30 | 13:00 | 5:30 | 42,308.01 | 42,352.43 | 44,420 | 42,208,580 | |
| 03/22/16 | 7:30 | 14:00 | 6:30 | 42,352.43 | 42,406.76 | 54,330 | 42,262,910 | |
| 03/23/16 | 12:00 | 15:15 | 3:15 | 42,406.76 | 42,437.75 | 30,990 | 42,293,900 | |
| 03/24/16 | 7:30 | 13:00 | 5:30 | 42,437.75 | 42,475.64 | 37,890 | 42,331,790 | |
| 03/28/16 | 7:30 | 15:30 | 8:00 | 42,475.64 | 42,517.63 | 41,990 | 42,373,780 | |
| 03/30/16 | 7:30 | 14:00 | 6:30 | 42,517.63 | 42,566.76 | 49,130 | 42,422,910 | |
| 03/31/16 | 10:00 | 13:30 | 3:30 | 42,566.76 | 42,598.54 | 31,780 | 42,454,690 | |
| 04/01/16 | 10:00 | 14:00 | 4:00 | 42,598.54 | 42,638.28 | 39,740 | 42,494,430 | |
| 04/08/16 | 8:00 | 12:00 | 4:00 | 42,638.28 | 42,688.87 | 50,590 | 42,545,020 | PVSC Compliance Sample Collected |
| 04/13/16 | 12:00 | 15:00 | 3:00 | 42,688.87 | 42,734.89 | 46,020 | 42,591,040 | |
| 04/19/16 | 8:00 | 13:00 | 5:00 | 42,734.89 | 42,802.71 | 67,820 | 42,658,860 | |
| 04/22/16 | 11:00 | 15:00 | 4:00 | 42,802.71 | 42,847.64 | 44,930 | 42,703,790 | |
| 04/29/16 | 10:00 | 14:15 | 4:15 | 42,847.64 | 42,912.90 | 65,260 | 42,769,050 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

(not included in this reporting period)

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

N4 POOL N4 ELEV.+6.5 525'
N3 POOL N3 ELEV.+7.5 343'
N2 POOL N2 ELEV.+8.0 237'
N1 POOL N1 ELEV.+10.0 660'
E1 POOL E1 ELEV.+8.0 325'
E2 POOL E2 ELEV.+8 270'
S4 POOL S4 ELEV.+6.0 419'
S3 POOL S3 ELEV.+7.0 640'
S2 POOL S2 ELEV.+7.5 622'
S1 POOL S1 ELEV.+8 338'

087-MW-Y20
087-MW-S19
087-MW-O19
087-MW-O01
088-MW-G19
090-MW-E1
117-MW-A99
117-MW-A85
117-MW-A89
115-PZ-6
115-PZ-5
115-PZ-4
073-MW-BB11
073-MW-Y10
134-MW-V09
134-MW-Q08
140-MW-06
140-MW-07
125-MW-L03
MW-124-103L
MW-124-102D
MW-124-103D
MW-124-102T

NORTH-FS-1
NORTH-FS-2
NORTH-FS-3
NORTH-FS-4
NORTH-FS-5
NORTH-FS-6
NORTH-FS-7
NORTH-FS-8
NORTH-FS-9
NORTH-FS-13
SOUTH-FS-1
SOUTH-FS-3
SOUTH-FS-4
SOUTH-FS-5
SOUTH FS-7
SOUTH-FS-6

W6-SO W1-SO W5-SO W3-SO E5-SO E4-SO E3-SO E2-SO E1-SO

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

KELLOGG STREET

STATE ROUTE 139

STA. N1+10 STA. N6+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. F3+75 STA. F4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+58 STA. S3+86 STA. S0+50

## LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

## GRAPHIC SCALE

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015

# STUDY AREA 7
# PERIMETER POOL DESIGN ELEVATIONS


NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET


FILE NO. 10210
DRAWING NO. PP-1




Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 5/1/2015 | 3.5 | 5.2 | 5.9 | 5.1 | 6.0 | | 3.3 | 2.7 | 5.7 | 5.6 | 6.8 | 6.2 | 5.3 | 5.2 | 5.7 | 6.3 | 2.8 | 2.9 | 4.0 | | 4.0 | 3.0 |
| 5/14/2015 | 2.9 | 5.1 | 5.7 | 6.6 | 5.5 | | 3.0 | 2.2 | 5.4 | 5.4 | 6.2 | 5.8 | 4.9 | 4.9 | 5.2 | 6.3 | | | | 2.8 | 3.5 | 2.8 |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | | | | 4.5 | 5.0 | 3.8 | 3.5 | | | | | | |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | | | | 3.5 | 3.6 | | | | | | | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | | | | 5.2 | | | 4.6 | | | | | | |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | | | | 6.0 | | | 5.6 | | | | | | |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | | | | 6.5 | | | 6.2 | | | | | | |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | | | | 6.0 | | | 5.7 | | | | | | |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | | | | 5.6 | | | 5.0 | | | | | | |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | | | | 2.7 | | | 3.6 | | | | | | |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | | | | 2.1 | | | | | | | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | | | | 1.8 | | | | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09, E4-SO, W1-SO, North FS-6, North FS-7

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)


## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

(not included in this reporting period)

# Attachment 11: Capping Update




LEGEND

- GDL COVER SOIL PLACED
- GDL COVER SOIL GRADED AND APPROVED FOR HORIZON SOILS
- HORIZON C SOIL PLACED
- HORIZON C PLACED TO FINAL HORIZON C GRADE
- HORIZON C PLACED AND PREPARED FOR HORIZON B
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
05/04/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: April 1, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 04/01/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, April 01, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence along the western end of Kellogg Street requires maintenance or replacement. |
| 2 | IA2Q4A1AL8 | Windscreen on the perimeter fence in the vicinity of the 60 Kellogg building requires maintenance or replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 04/01/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace silt fence along the north side of the western end of Kellogg Street as required. | 4/7/16 TAD |
| 2 | Repair or replace the windscreen on the perimeter fence by the 60 Kellogg building as required. | tape w/ yellow Safety Hazard |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 04/07/16

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: April 8, 2016**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 04/08/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, April 08, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Filter fabric is missing from a catch basin at the western end of Kellogg Street. |
| 2 | IA2Q4A1AL8 | Windscreen on the perimeter fence bordering the JCMUA complex requires maintenance or replacement. |
| 3 | IA2Q4A1AL8 | Trash and debris are present in the Rt. 440 pedestrian walkway on the east side of SA-6 North. |
| 4 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern SA-7 paved haul road |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 04/08/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the filter fabric as required. | 4/11/16 RAD |
| 2 | Repair or replace the windscreen on the perimeter fence as required. | |
| 3 | Remove trash and debris as required. | |
| 4 | Clean the northern SA-7 haul road and install stone tracking pads where needed to reduce the tracking of material by end dumps working in the area. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 04/13/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: April 15, 2016**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2,3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 04/18/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
**Friday, April 15, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Trash and debris are present along the outside of the perimeter fence on Kellogg Street and on the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Silt fence material is not properly toed in along the southern perimeter of the 1-N surcharge area. This silt fence is located on SA-7. |
| 3 | EEPSQUO2YB | Silt fence surrounding the Novartis Stockpile Area requires maintenance. |
| 4 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern and southern SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 04/18/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove and dispose of accumulated trash and debris. | CAD 4/21/16 |
| 2 | Toe in or replace silt the silt fence along the south side of the 1-N Surcharge Area as required. | |
| 3 | Repair or replace the existing silt fence surrounding the Novartis Stockpile Area as required. | |
| 4 | Clean the northern and southern SA-7 haul roads and install stone tracking pads where needed to reduce the tracking of material by end dumps working in the area. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 04/21/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: April 22, 2016**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 North & GWTP** | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| **SA-7 & Novartis Stockpile** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 04/22/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, April 22, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Trash and debris are present along the outside of the perimeter fence on Kellogg Street and on the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Windscreen fabric has become detached from the perimeter fence which borders the MUA complex on SA-6 North. |
| 3 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern and southern SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** 04/22/16 **Date:**

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove and dispose of accumulated trash and debris. | 4/28/16 (RAD) |
| 2 | Reattach or replace the windscreen on the fenceline between SA-6 North and the JCMUA parking lot. | |
| 3 | Clean the northern and southern SA-7 haul roads and install stone tracking pads where needed to reduce the tracking of material by end dumps working in the area. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** **Date:** 04/28/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: April 28, 2016**

**Type of Inspection:** ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 04/28/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
Thursday, April 28, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Silt fence on SA-6 South along Kellogg Steet (to the west of the old guard house) requires maintenance or replacement. |
| 2 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern and southern SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION
Facility Location: Jersey City, New Jersey
SWAP Observer: _____ Date: 04/28/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace silt fence as required. Toe in the silt fence properly. | 5/6/16 RAD |
| 2 | Clean the northern and southern SA-7 haul roads and install stone tracking pads where needed to reduce the tracking of material by end dumps working in the area | V |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 05/04/16

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted April 2015)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

April 20, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the March 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 3 | 01 | 16 | 3 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 78,969 | 86,966 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.51 | 0.56 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00032 | 0.00032 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1750 | 0.1750 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

## PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

04/19/2016

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 3 | 01 | 16 | 3 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,448,028 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 59,166,556 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 3/15/2016 | <10 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J Morris MC | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 04/19/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | MONTH: March 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 3/1/2016 | Angel Trujillo | 56718528 | 56794115 | 75,587 | 0.075587 | 7.79 | 0.773 | | | | | | | | | 0.49 |
| 3/2/2016 | Angel Trujillo | 56794115 | 56874850 | 80,735 | 0.080735 | 7.13 | 0.773 | | | | | | | | | 0.52 |
| 3/3/2016 | Angel Trujillo | 56874850 | 56957046 | 82,196 | 0.082196 | 7.35 | 0.773 | | | | | | | | | 0.53 |
| 3/4/2016 | Angel Trujillo | 56957046 | 57034950 | 77,904 | 0.077904 | 7.28 | 0.773 | | | | | | | | | 0.50 |
| 3/5/2016 | Angel Trujillo | 57034950 | 57121916 | 86,966 | 0.086966 | 7.51 | 0.773 | | | | | | | | | 0.56 |
| 3/6/2016 | Angel Trujillo | 57121916 | 57196317 | 74,401 | 0.074401 | 7.20 | 0.773 | | | | | | | | | 0.48 |
| 3/7/2016 | Angel Trujillo | 57196317 | 57270718 | 74,401 | 0.074401 | 7.34 | 0.773 | | | | | | | | | 0.48 |
| 3/8/2016 | Angel Trujillo | 57270718 | 57351070 | 80,352 | 0.080352 | 7.25 | 0.773 | | | | | | | | | 0.52 |
| 3/9/2016 | Angel Trujillo | 57351070 | 57428662 | 77,592 | 0.077592 | 7.16 | 0.773 | | | | | | | | | 0.50 |
| 3/10/2016 | Angel Trujillo | 57428662 | 57511584 | 82,922 | 0.082922 | 7.15 | 0.773 | | | | | | | | | 0.53 |
| 3/11/2016 | Angel Trujillo | 57511584 | 57590534 | 78,950 | 0.07895 | 7.20 | 0.773 | | | | | | | | | 0.51 |
| 3/12/2016 | Angel Trujillo | 57590534 | 57670542 | 80,008 | 0.080008 | 7.10 | 0.773 | | | | | | | | | 0.52 |
| 3/13/2016 | Angel Trujillo | 57670542 | 57750550 | 80,008 | 0.080008 | 7.02 | 0.773 | | | | | | | | | 0.52 |
| 3/14/2016 | Angel Trujillo | 57750550 | 57826060 | 75,510 | 0.07551 | 7.47 | 0.773 | | | | | | | | | 0.49 |
| 3/15/2016 | Angel Trujillo | 57826060 | 57902698 | 76,638 | 0.076638 | 6.94 | 0.773 | <5.0 | <10 | | <0.010 | <0.030 | <0.010 | 0.00032 | <0.020 | 0.49 |
| 3/16/2016 | Angel Trujillo | 57902698 | 57984118 | 81,420 | 0.08142 | 7.05 | 0.773 | | | | | | | | | 0.52 |
| 3/17/2016 | Angel Trujillo | 57984118 | 58064512 | 80,394 | 0.080394 | 7.07 | 0.773 | | | | | | | | | 0.52 |
| 3/18/2016 | Angel Trujillo | 58064512 | 58141676 | 77,164 | 0.077164 | 7.04 | 0.773 | | | | | | | | | 0.50 |
| 3/19/2016 | Angel Trujillo | 58141676 | 58224948 | 83,272 | 0.083272 | 7.21 | 0.773 | | | | | | | | | 0.54 |
| 3/20/2016 | Angel Trujillo | 58224948 | 58301750 | 76,802 | 0.076802 | 7.00 | 0.773 | | | | | | | | | 0.50 |
| 3/21/2016 | Angel Trujillo | 58301750 | 58378552 | 76,802 | 0.076802 | 7.06 | 0.773 | | | | | | | | | 0.50 |
| 3/22/2016 | Angel Trujillo | 58378552 | 58457708 | 79,156 | 0.079156 | 7.18 | 0.773 | | | | | | | | | 0.51 |
| 3/23/2016 | Angel Trujillo | 58457708 | 58536570 | 78,862 | 0.078862 | 7.05 | 0.773 | | | | | | | | | 0.51 |
| 3/24/2016 | Angel Trujillo | 58536570 | 58617316 | 80,746 | 0.080746 | 7.20 | 0.773 | | | | | | | | | 0.52 |
| 3/25/2016 | Angel Trujillo | 58617316 | 58694426 | 77,110 | 0.07711 | 7.10 | 0.773 | | | | | | | | | 0.50 |
| 3/26/2016 | Angel Trujillo | 58694426 | 58776932 | 82,506 | 0.082506 | 7.22 | 0.773 | | | | | | | | | 0.53 |
| 3/27/2016 | Angel Trujillo | 58776932 | 58854584 | 77,652 | 0.077652 | 7.10 | 0.773 | | | | | | | | | 0.50 |
| 3/28/2016 | Angel Trujillo | 58854584 | 58932236 | 77,652 | 0.077652 | 7.01 | 0.773 | | | | | | | | | 0.50 |
| 3/29/2016 | Angel Trujillo | 58932236 | 59010326 | 78,090 | 0.07809 | 7.04 | 0.773 | | | | | | | | | 0.50 |
| 3/30/2016 | Angel Trujillo | 59010326 | 59088498 | 78,172 | 0.078172 | 7.08 | 0.773 | | | | | | | | | 0.50 |
| 3/31/2016 | Angel Trujillo | 59088498 | 59166556 | 78,058 | 0.078058 | 7.05 | 0.773 | | | | | | | | | 0.50 |
| TOTAL | | | | 2,448,028 | 2.448028 | | | <5.0 | <10 | | <0.010 | <0.030 | <0.010 | 0.00032 | <0.020 | |
| | | | High: | 86,966 | | | | | | | | | | | High: | 0.56 |
| | | | Average: | 78,969 | | | | | | | | | | | Average: | 0.51 |

WW

E

JC16234

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42444.60016 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-031516 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTG |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | Preservative | 3 3 3 1 2 2 0 0 2 | Site ID HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | | | Lab Job # HWINJM32815 |
| 101 Columbia Road Morristown, NJ 07962 | Consultant CH2M | | | Authorized User: Honeywell |
| Preliminary Data To | | | | |
| Sample Receipt Acknowledgement To | | | Test & Report File Name | Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

2

| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 160.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | Units | | | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-031516-A | 3/15/2016 | 14:20 | WW | WATER | REG | 5 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | | |
| 2 | 087-WW | | | 087-WWE-031516-B | 3/15/2016 | 14:25 | WW | WATER | REG | 6 | grab | N | | | | | X | X | | | | 2 | | | | | | | C38 |
| 3 | 087-WW | | | 087-WWI-031516 | 3/15/2016 | 14:35 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | | U748 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | A27 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | M15 |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: Frank Schroyer | 6.94 s.u. @ 7.2°C | Company: AMEC Foster Wheeler | Received by: | Company: | | Condition: | Custody Seals Intact: |
| | Date/Time: 3/15/16 1500 | | | Date/Time: 3.15 1500 | | Cooler Temp. | |
| Relinquished by: | | Company: | Received by: | Company: | AcWEST | Condition: | Custody Seals Intact: |
| | Date/Time: 3-15 1740 | | | Date/Time: 3/15/16 1740 | | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

INITIAL ASESSMENT 3B 03

LABEL VERIFICATION JK

04.5 EJO

SGS Accutest LabLink@903397 10:39 05-Apr-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031516-A | | |
| **Lab Sample ID:** | JC16234-1 | **Date Sampled:** | 03/15/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/15/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.1
4

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 773 | 10 | ug/l | 1 | 03/16/16 | 03/18/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 03/16/16 | 03/18/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead | < 30 | 30 | ug/l | 10 | 03/16/16 | 03/18/16 | GT | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | 0.32 | 0.20 | ug/l | 1 | 03/18/16 | 03/18/16 | MS | EPA 245.1 [1] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 03/16/16 | 03/18/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 03/16/16 | 03/18/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA38951
(2) Instrument QC Batch: MA38954
(3) Instrument QC Batch: MA38958
(4) Prep QC Batch: MP92578
(5) Prep QC Batch: MP92639

RL = Reporting Limit

SGS Accutest LabLink@903397 10:39 05-Apr-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031516-A | | |
| **Lab Sample ID:** | JC16234-1 | **Date Sampled:** | 03/15/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/15/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.1
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 03/16/16 | LA | SM2540 D-11 |
| pH [a] | 6.93 | | su | 1 | 03/15/16 19:11 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@903397 10:39 05-Apr-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031516-A | | |
| **Lab Sample ID:** | JC16234-1A | **Date Sampled:** | 03/15/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/15/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.2
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 10 | 10 | mg/l | 1 | 03/16/16 18:21 | LS | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@903397 10:39 05-Apr-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031516-B | | |
| **Lab Sample ID:** | JC16234-2 | **Date Sampled:** | 03/15/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/15/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | T216146.D | 1 | 03/17/16 | DC | n/a | n/a | VT8881 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.6 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 2.6 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 4.7 | 1.0 | 0.10 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.10 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.17 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.57 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 4.6 | 1.0 | 0.096 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.24 | 1.0 | 0.093 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.21 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.50 | ug/l | |
| 67-66-3 | Chloroform | 31.5 | 1.0 | 0.091 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.11 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.15 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.11 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.37 | 1.0 | 0.19 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.19 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.11 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.29 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.39 | 1.0 | 0.12 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.090 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.16 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 62.5 | 1.0 | 0.12 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.2 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.11 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.12 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.15 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 20 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.22 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.97 | 1.0 | 0.22 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.12 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@903397 10:39 05-Apr-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031516-B | | |
| **Lab Sample ID:** | JC16234-2 | **Date Sampled:** | 03/15/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/15/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.14 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.25 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.086 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.13 | ug/l | |
| 79-01-6 | Trichloroethene | 66.5 | 1.0 | 0.12 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.20 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.13 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.22 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 87% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 97% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 99% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 98% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@903397 10:39 05-Apr-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-031516-B | | |
| **Lab Sample ID:** | JC16234-2 | **Date Sampled:** | 03/15/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 03/15/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 03/17/16 13:50 | JOO | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending April 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending April 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |

**SA-6 North/South Field Change Log - Month Ending April 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending April 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending April 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |
| **DC 2016-02-03** | The final grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Contractor only. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Contractor only. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Contractor only. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |

**SA-6 North/South Field Change Log - Month Ending April 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**6/10/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

June 10, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-05**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from May 1 – May 31, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: May 2016 SA-6/7 Combined Monthly Progress Report No. 2016-05

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP (electronic copy)
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-05

**Project SA-6 & 7 Remediation**

# May 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 05/04/16 | BEP - Environmental Project - USACE Permit<br>SA-7 Sediment | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/05/16 | Summary of 6-Month Performance Assessment<br>Sampling Post In-Situ Treatment of Hexavalent<br>Chromium Impacted Soils<br>Treatment Area 10-1 Only<br>Study Area 6 (SA-6) North (Site 087)<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/12/16 | Study Areas 6 and 7 Combined Monthly<br>Progress/Highlights Report No. 2016-04 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/16/16 | Groundwater Sampling Results<br>Study Area 6 (SA-6) South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/17/16 | Observance of Suspect Material at the<br>60 Kellogg Street Building<br>Study Area 6 (SA-6) South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 05/17/16 | Special Master All Hands Meeting | n/a |
| 05/19/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy<br>Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage<br>Commission |

## SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | 05/08/16 | 05/15/16 | 05/22/16 | 05/29/16 |
|---|---|---|---|---|
| **Construction Management (AMEC)** | 7 | 9 | 9 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |

| Team | 05/08/16 | 05/15/16 | 05/22/16 | 05/29/16 |
|---|---|---|---|---|
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 28 | 30 | 31 | 32 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 1 |
| **Eglentowicz (Demolition)** | 0 | 0 | 0 | 0 |
| **Century** | 0 | 2 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 2 | 1 | 0 |
| **Cornerstone** | 0 | 0 | 0 | 0 |
| **TOTAL STAFF** | **41** | **49** | **47** | **48** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Collected May PVSC compliance sample from the Construction Water Treatment Plant (CWTP).

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on May 6, 2016.
- Completed piping layout plans for routing the Contingent Groundwater Extraction System force mains from SA-6 North and South to the existing GWTP Neutralization Tank.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 05/08/16 | 05/15/16 | 05/22/16 | 05/29/16 |
| Avg. Gallons Treated & Discharged (per day) | 77,947 | 78,345 | 77,444 | 78,840 |
| Average Flow (gpm) for Operating Period | 56 | 56 | 54 | 57 |
| Avg. Hours of Plant Operation | 23 | 23 | 24 | 23 |
| GWTP Influent Tanks (gal.) | 4,400 | 3,026 | 4,109 | 5,352 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 0 | 0 | 0 |
| **Bayshore** | Tri-Axle | Keasbey, NJ | Bayshore Recycling | Non-Haz Petroleum Soil | 30 | 24 | 720 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | No chromium soil excavation performed. |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 05/08/16 | 05/15/16 | 05/22/16 | 5/29/16 |
| Natures Choice Horizon C | 1,867.67 | 1,826.85 | 2,461.46 | 4,442.30 |
| Cedar Hill Horizon B | 2,093.69 | 1,206.67 | 1,917.90 | 2,347.65 |
| Tilcon Mount Hope I-8 | 1,320.32 | 817.21 | 304.28 | 308.73 |
| Natures Choice Topsoil | 0 | 786.37 | 740.25 | 0 |
| Weldon Screenings | 0 | 1,806.60 | 1,649.19 | 2,154.68 |

## D. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.
- Area 2N: Surcharging and offloading of surcharge material is complete.
- Area 3N: Surcharging and offloading of surcharge material is complete.

- Area 4N: Surcharging and offloading of surcharge material is complete.

## E. SHEET PILE OPERATIONS

- Grouting of Hydraulic Barrier Wall on SA-6 North interlocks is complete.

## F. CAPPING OPERATIONS

- Continued re-grading the GDL cover soil in GDL repair areas on the west side of the SA-6 South cap to include associated compaction testing.
- Continued placement of root barrier and demarcation tape and importing and placing Horizon C soils to include associated compaction testing on the SA-6 South open space area.
- Began importing and placing Horizon B soils atop Horizon C soils on SA-6 South.
- Continued importing and stockpiling Horizon A Topsoil.
- Continued SA-6 North liner subgrade grading activities within the open space area.
- Continued placement of Structural Fill Material in the future utility corridors crossing the SA-6 South open space area.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete final grading of GDL cover soils to include associated compaction testing and installation of root barrier on SA-6 South open space area.
- Continue placement of Horizon C and Horizon B soils on SA-6 South open space area.
- Continue importing Horizon A Topsoil and begin placement on the SA-6 South Cap Area.
- Continue SA-6 North liner subgrade grading activities.
- Begin cutting SA-6 North Hydraulic Barrier Wall and Soil-Cement Bentonite Wall to liner grade.
- Prepare SA-6 North subgrade for initial geomembrane liner installation.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Continue to coordinate the CGWES piping layout with selected contractor for connection to GWTP Neutralization Tank.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 29 in well 088-IW-01 (completed June 5$^{th}$ through 7$^{th}$, 2016).
- Conduct second quarterly LTMP regional groundwater level measurement round.
- Complete excavation and post-excavation sampling of small area of observed chromium impacted soils under the former 60 Kellogg St. building.
- Coordinate follow-up injections in Treatment Area TA 10-1.

## ATTACHMENTS:


1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data *(not included in this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log

# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration | Start | Finish |
|---|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **1/4/08** | **6/1/15** |
| **2** | **Remedial Action Work Plan** | **33 days** | **1/4/08** | **2/19/08** |
| **5** | **Remedial Action Design** | **1522 days** | **2/20/08** | **12/13/13** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **8/11/08** | **6/1/15** |
| 19 | Develop Site Relocation Master Plan | 38 days | 8/11/08 | 10/1/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | 10/1/08 | 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | 6/2/09 | 6/2/14 |
| 22 | Relocation Contractor Procurement | 392 days | 4/15/10 | 10/13/11 |
| 23 | JCIA and JCDPW Relocation | 949 days | 10/17/11 | 6/1/15 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | 12/12/11 | 4/30/12 |
| 24a | Demolition of JCIA Structures | 146 days | 9/1/14 | 3/23/15 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **7/11/08** | **4/30/14** |
| **26** | **Remedial Action Work Plan** | **187 days** | **7/11/08** | **3/30/09** |
| **32** | **Remedial Action Design** | **1161 days** | **2/2/09** | **7/9/13** |
| **57** | **SA-6 South Relocation** | **616 days** | **12/26/11** | **4/30/14** |
| 58 | New GWTP Construction Completion | 502 days | 3/5/12 | 1/30/14 |
| 59 | Demolition of 80 Kellogg | 857 days | 12/26/11 | 4/30/14 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **3/1/13** | **8/1/16** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | 6/17/13 | 12/31/15 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | 11/15/13 | 12/31/15 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **3/1/13** | **6/28/13** |
| 61a | Mobilization | 87 days | 3/1/13 | 6/28/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **6/17/13** | **2/29/16** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | 6/17/13 | 12/31/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | 4/8/14 | 2/13/15 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | 6/30/15 | 2/29/16 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | 6/16/14 | 2/23/15 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | 10/6/14 | 5/8/15 |
| **63** | **Barrier Wall Install** | **569 days** | **8/12/13** | **10/15/15** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | 3/9/15 | 10/15/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | 8/12/13 | 5/30/14 |
| **64** | **Excavation** | **507 days** | **10/22/13** | **9/30/15** |
| 64a | SA 6N Excavation | 218 days | 12/1/14 | 9/30/15 |
| 64b | SA 6S Excavation | 295 days | 10/22/13 | 12/8/14 |
| **65** | **Backfill** | **558 days** | **11/11/13** | **12/30/15** |
| 65a | SA 6N Backfill | 283 days | 12/1/14 | 12/30/15 |
| 65b | SA 6S Backfill | 384 days | 11/11/13 | 4/30/15 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **12/1/14** | **7/15/16** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | 3/24/16 | 7/15/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | 12/1/14 | 12/30/15 |
| **67** | **Restoration** | **234 days** | **9/1/15** | **7/21/16** |
| 67a | Restoration | 234 days | 9/1/15 | 7/21/16 |
| **68** | **Demobilization** | **22 days** | **7/1/16** | **8/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | | | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | | | |
| **69** | **SA-6 North Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **10/1/15** | **12/7/16** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **10/1/08** | **10/1/15** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **6/5/08** | **3/31/18** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 5/31/16

Task  Milestone  Summary  Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Compacting historical fill subgrade within open space area.




**Site Photograph 2:** Compacting structural fill in future utility corridor.




**Site Photograph 3:** Grading and compacting cover soils along open space area slope.




**Site Photograph 4:** Loading imported cover soils for placement in open space area.




**Site Photograph 5:** Spreading cover soils - survey control in background.




**Site Photograph 6:** Unloading imported cover soils for placement in open space area.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of June 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-05
Attachment 3: Excavation and Backfill (Progression Chart)

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties

Former Roosevelt Drive-In Site
(Remediation Complete)

Kellogg Street Properties

Added Excavation Area
(complete)

Hackensack River

Route 440

Kellogg Street

# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 04/01/16 | 10:00 | 14:00 | 4:00 | 42,598.54 | 42,638.28 | 39,740 | 42,637,830 | |
| 04/08/16 | 8:00 | 12:00 | 4:00 | 42,638.28 | 42,688.87 | 50,590 | 42,688,420 | PVSC Compliance Sample Collected |
| 04/13/16 | 12:00 | 15:00 | 3:00 | 42,688.87 | 42,734.89 | 46,020 | 42,734,440 | |
| 04/19/16 | 8:00 | 13:00 | 5:00 | 42,734.89 | 42,802.71 | 67,820 | 42,802,260 | |
| 04/22/16 | 11:00 | 15:00 | 4:00 | 42,802.71 | 42,847.64 | 44,930 | 42,847,190 | |
| 04/29/16 | 10:00 | 14:15 | 4:15 | 42,847.64 | 42,912.90 | 65,260 | 42,912,450 | |
| 05/06/16 | 10:00 | 15:00 | 5:00 | 42,912.90 | 42,965.49 | 52,590 | 42,965,040 | PVSC Compliance Sample Collected |
| 05/13/16 | 11:00 | 15:00 | 4:00 | 42,965.49 | 43,019.78 | 54,290 | 43,019,330 | |
| 05/20/16 | 11:00 | 15:00 | 4:00 | 43,019.78 | 43,071.32 | 51,540 | 43,070,870 | |
| 05/27/16 | 10:00 | 14:00 | 4:00 | 43,071.32 | 43,130.78 | 59,460 | 43,130,330 | |
| 05/31/16 | 11:00 | 14:30 | 3:30 | 43,130.78 | 43,178.93 | 48,150 | 43,178,480 | |
| 06/01/16 | 6:30 | 13:30 | 7:00 | 43,178.93 | 43,268.97 | 90,040 | 43,268,520 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

(not included in this reporting period)

# Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

N4 POOL N4 ELEV.+6.5 525'
N3 POOL N3 ELEV.+7.5 343'
N2 POOL N2 ELEV.+8.0 237'
N1 POOL N1 ELEV.+10.0 660'
S4 POOL S4 ELEV.+6.0 419'
S3 POOL S3 ELEV.+7.0 640'
S2 POOL S2 ELEV.+7.5 622'
S1 POOL S1 ELEV.+8 338'
E1 POOL E1 ELEV.+8.0 325'
E2 POOL E2 ELEV.+8 270'

087-MW-Y20
087-MW-S19
087-MW-O19
087-MW-O01
088-MW-G19
090-MW-E1
117-MW-A99
117-MW-A85
117-MW-A89
115-PZ-6
115-PZ-5
115-PZ-4
073-MW-BB11
073-MW-Y10
134-MW-V09
134-MW-Q08
140-MW-06
140-MW-07
125-MW-L03
MW-124-103L
MW-124-102D
MW-124-103D
MW-124-102T

NORTH-FS-1
NORTH-FS-2
NORTH-FS-3
NORTH-FS-4
NORTH-FS-5
NORTH-FS-6
NORTH-FS-7
NORTH-FS-8
NORTH-FS-9
NORTH-FS-13
SOUTH-FS-1
SOUTH-FS-3
SOUTH-FS-4
SOUTH-FS-5
SOUTH FS-7
SOUTH-FS-6

W6-SO W1-SO W3-SO W5-SO E5-SO E4-SO E3-SO E2-SO E1-SO

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

KELLOGG STREET

STATE ROUTE 139

STA. N1+10 STA. N6+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. F3+75 STA. F4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+58 STA. S3+86 STA. S0+50

## LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE
100' 50' 0 100' 200'

IN PROGRESS
06-10-2015


# STUDY AREA 7
# PERIMETER POOL DESIGN ELEVATIONS

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | | | | | South | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-1 | FS-2 | FS-3 | FS-5 | FS-6 | FS-7 | FS-13 | FS-1 | FS-3 | FS-4 | FS-5 | FS-6 | FS-7 |
| Date | | | | | | | | | | | | | | | | | | | | | | |
| 6/1/2015 | 6.0 | 5.1 | 5.6 | 4.4 | 4.2 | | 4.7 | 4.0 | 7.0 | 6.2 | 6.5 | 6.1 | 4.6 | 4.5 | 4.2 | 5.3 | | | | | 3.9 | |
| 6/15/2015 | 5.6 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 5.0 | 6.6 | | | | 4.8 | 4.8 | 4.2 | 4.3 | | | | | | |
| 6/30/2015 | 4.2 | 5.2 | 5.7 | 4.2 | 4.4 | | 5.1 | 4.2 | 6.7 | | | | 4.8 | 4.7 | 4.2 | 4.5 | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | | | | 4.8 | 4.7 | 3.9 | 4.1 | | | | | | |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | | | | 4.6 | 4.5 | 3.7 | 3.3 | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | | | | 4.6 | 4.5 | 3.9 | 4.0 | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | | | | 4.5 | 4.5 | 3.6 | | | | | | | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | | | | 4.4 | 4.3 | 3.5 | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | | | | 4.4 | 4.4 | 3.5 | | | | | | | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 4.0 | 4.0 | | | | | | |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | | | | 4.7 | 4.6 | 3.9 | 3.8 | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | | | | 4.6 | 4.6 | 3.7 | 3.4 | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | | | | 4.5 | 5.0 | 3.8 | 3.5 | | | | | | |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | | | | 3.5 | 3.6 | | | | | | | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | | | | 5.2 | | | 4.6 | | | | | | |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | | | | 6.0 | | | 5.6 | | | | | | |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | | | | 6.5 | | | 6.2 | | | | | | |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | | | | 6.0 | | | 5.7 | | | | | | |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | | | | 5.6 | | | 5.0 | | | | | | |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | | | | 2.7 | | | 3.6 | | | | | | |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | | | | 2.1 | | | | | | | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | | | | 1.8 | | | | | | | | | |
| 5/2/2016 | 3.1 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | | | | 1.6 | | | | | | | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | | | | | | | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)


## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

# Attachment 10: Sheet Pile Update

(not included in this reporting period)

# Attachment 11: Capping Update




LEGEND

- HORIZON C SOIL PLACED
- HORIZON C PLACED AND READY FOR TOPSOIL
- HORIZON C PLACED AND PREPARED FOR HORIZON B
- HORIZON B PLACED
- HORIZON B PLACED AND READY FOR TOPSOIL
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
06/03/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: May 6, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 05/06/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 06, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence at the Kellogg Street jughandle has become detached. |
| 2 | IA2Q4A1AL8 | Garbage has accumulated on the grass outside of the perimeter fence along Kellogg Street. |
| 3 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern and southern SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 05/06/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen as required. | RAD 5/11/16 |
| 2 | Pick up and dispose of accumulated garbage. | |
| 3 | Clean the northern and southern SA-7 haul roads and install stone tracking pads where needed to reduce the tracking of material by end dumps working in the area. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 05/12/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: May 13, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 05/16/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 13, 2016**

**SA-6 North & South**
**SESCP SCD:** IA2Q4A1AL8
**RFA PI ID #:** 608267
**RFA Portal ID#:** 304689
**RFA NJPDES #:** NJG0216771

**GWTP (SA-6 North)**
**SESCP SCD:** EHWG3RTMXR
**RFA PI ID #:** 587787
**RFA Portal ID#:** 219047
**RFA NJPDES #:** NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
**RFA PI ID #:**
RFA Portal ID#: 217517
**RFA NJPDES #:**

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence at the Kellogg Street jughandle has become detached. |
| 2 | IA2Q4A1AL8 | Garbage has accumulated on the grass outside of the perimeter fence along Kellogg Street. |
| 3 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern and southern SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 05/16/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen as required | 5-19-16 RAD |
| 2 | Pick up and dispose of accumulated garbage. | 1 |
| 3 | Clean the northern and southern SA-7 haul roads and install stone tracking pads where needed to reduce the tracking of material by end dumps working in the area. | 1 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 05/19/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: May 20, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 5 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 05/23/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 20, 2016**

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Erosion protection measures are not present on the western end of the south cap area adjacent to the Hackensack River bulkhead. |
| 2 | IA2Q4A1AL8 | Windscreen fabric on the perimeter fence at the Kellogg Street jughandle has become detached along the top. |
| 3 | IA2Q4A1AL8 | Garbage has accumulated on the grass outside of the perimeter fence along Kellogg Street and the grass requires cutting. |
| 4 | IA2Q4A1AL8 | Erosion protection measures are not present in the north cap area at the western side of the sedimentation basin (just south of the CWTP). |
| 5 | IA2Q4A1AL8 | Mud and sediment have accumulated on the northern, southern and western SA-7 paved haul roads. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 05/23/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install erosion control measures on the western end of the south cap adjacent to the river bulkhead. | 5/26/16 (AM) |
| 2 | Re-attach the windscreen as required. | |
| 3 | Pick up and dispose of accumulated garbage, cut the grass. | |
| 4 | Install erosion control measures on the north cap at the western end of the sedimentation basin where cap material overtops the sheetpile. | |
| 5 | Clean the northern, southern and western SA-7 haul roads. | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date** 05/26/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: May 27, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 2 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 05/27/16.

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, May 27, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has accumulated on the western end of Kellogg Street. |
| 2 | IA2Q4A1AL8 | Entrances/exits to the SA-6 north cap area exclusion zone are being left open when unattended. |
| 3 | IA2Q4A1AL8 | Garbage and other debris is present in the SA-6 North pedestrian walkway adjacent to Rte. 440. |
| 4 | IA2Q4A1AL8 | Silt fence along the western end of the northern SA-7 roadway has become detached from the upright wooden stakes. |
| 5 | IA2Q4A1AL8 | Filter fabric in two catch basins on the eastern SA-7 roadway has become blinded with sediment. |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 05/27/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Clean up all accumulated sediment on the western end of Kellogg Street, adjacent to the truck entrance gate. | CHD 6/2/16 |
| 2 | Pull orange fencing across EZ entrances/exits when they are not being used. | / |
| 3 | Remove and dispose of accumulated garbage in the pedestrian walkway. | / |
| 4 | Maintain or replace the silt fence as required | / |
| 5 | Replace the filter fabric as needed to restore function. | / |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 06/02/16

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted May 2016)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

May 18, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the April 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 4 | 01 | 16 | 4 | 30 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 78,700 | 87,494 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.72 | 0.80 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00026 | 0.00026 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.17461 | 0.17461 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

**PRETREATMENT MONITORING REPORT**

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

May 18, 2016

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 4 | 01 | 16 | 4 | 30 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,360,988 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 61,527,544 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 4/12/2016 | 11.0 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris VP | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE May 18, 2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | | | | | MONTH: April, 2016 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 4/1/2016 | Angel Trujillo | 59166556 | 59244612 | 78,056 | 0.078056 | 7.15 | 1.090 | | | | | | | | | 0.71 |
| 4/2/2016 | Angel Trujillo | 59244612 | 59308878 | 64,266 | 0.064266 | 7.11 | 1.090 | | | | | | | | | 0.58 |
| 4/3/2016 | Angel Trujillo | 59308878 | 59394398 | 85,520 | 0.08552 | 7.80 | 1.090 | | | | | | | | | 0.78 |
| 4/4/2016 | Angel Trujillo | 59394398 | 59479918 | 85,520 | 0.08552 | 7.20 | 1.090 | | | | | | | | | 0.78 |
| 4/5/2016 | Angel Trujillo | 59479918 | 59561506 | 81,588 | 0.081588 | 7.61 | 1.090 | | | | | | | | | 0.74 |
| 4/6/2016 | Angel Trujillo | 59561506 | 59637952 | 76,446 | 0.076446 | 7.73 | 1.090 | | | | | | | | | 0.69 |
| 4/7/2016 | Angel Trujillo | 59637952 | 59719498 | 81,546 | 0.081546 | 7.65 | 1.090 | | | | | | | | | 0.74 |
| 4/8/2016 | Angel Trujillo | 59719498 | 59799370 | 79,872 | 0.079872 | 7.76 | 1.090 | | | | | | | | | 0.73 |
| 4/9/2016 | Angel Trujillo | 59799370 | 59881000 | 81,630 | 0.08163 | 7.45 | 1.090 | | | | | | | | | 0.74 |
| 4/10/2016 | Angel Trujillo | 59881000 | 59962630 | 81,630 | 0.08163 | 7.75 | 1.090 | | | | | | | | | 0.74 |
| 4/11/2016 | Angel Trujillo | 59962630 | 60035090 | 72,460 | 0.07246 | 7.64 | 1.090 | | | | | | | | | 0.66 |
| 4/12/2016 | Angel Trujillo | 60035090 | 60113084 | 77,994 | 0.077994 | 6.94 | 1.090 | <5.0 | 11.0 | | <0.010 | <0.030 | <0.010 | 0.00026 | <0.020 | 0.71 |
| 4/13/2016 | Angel Trujillo | 60113084 | 60191378 | 78,294 | 0.078294 | 7.67 | 1.090 | | | | | | | | | 0.71 |
| 4/14/2016 | Angel Trujillo | 60191378 | 60270082 | 78,704 | 0.078704 | 7.53 | 1.090 | | | | | | | | | 0.72 |
| 4/15/2016 | Angel Trujillo | 60270082 | 60349094 | 79,012 | 0.079012 | 7.59 | 1.090 | | | | | | | | | 0.72 |
| 4/16/2016 | Angel Trujillo | 60349094 | 60431159 | 82,065 | 0.082065 | 7.90 | 1.090 | | | | | | | | | 0.75 |
| 4/17/2016 | Angel Trujillo | 60431159 | 60513224 | 82,065 | 0.082065 | 7.60 | 1.090 | | | | | | | | | 0.75 |
| 4/18/2016 | Angel Trujillo | 60513224 | 60588200 | 74,976 | 0.074976 | 7.62 | 1.090 | | | | | | | | | 0.68 |
| 4/19/2016 | Angel Trujillo | 60588200 | 60667406 | 79,206 | 0.079206 | 7.61 | 1.090 | | | | | | | | | 0.72 |
| 4/20/2016 | Angel Trujillo | 60667406 | 60743746 | 76,340 | 0.07634 | 7.84 | 1.090 | | | | | | | | | 0.69 |
| 4/21/2016 | Angel Trujillo | 60743746 | 60831240 | 87,494 | 0.087494 | 7.72 | 1.090 | | | | | | | | | 0.80 |
| 4/22/2016 | Angel Trujillo | 60831240 | 60907212 | 75,972 | 0.075972 | 7.60 | 1.090 | | | | | | | | | 0.69 |
| 4/23/2016 | Angel Trujillo | 60907212 | 60990318 | 83,106 | 0.083106 | 7.60 | 1.090 | | | | | | | | | 0.76 |
| 4/24/2016 | Angel Trujillo | 60990318 | 61055402 | 65,084 | 0.065084 | 7.68 | 1.090 | | | | | | | | | 0.59 |
| 4/25/2016 | Angel Trujillo | 61055402 | 61132730 | 77,328 | 0.077328 | 7.82 | 1.090 | | | | | | | | | 0.70 |
| 4/26/2016 | Angel Trujillo | 61132730 | 61212418 | 79,688 | 0.079688 | 7.65 | 1.090 | | | | | | | | | 0.72 |
| 4/27/2016 | Angel Trujillo | 61212418 | 61288291 | 75,873 | 0.0759 | 7.62 | 1.090 | | | | | | | | | 0.69 |
| 4/28/2016 | Angel Trujillo | 61288291 | 61365913 | 77,622 | 0.077622 | 7.82 | 1.090 | | | | | | | | | 0.71 |
| 4/29/2016 | Angel Trujillo | 61365913 | 61449220 | 83,307 | 0.083307 | 7.69 | 1.090 | | | | | | | | | 0.76 |
| 4/30/2016 | Angel Trujillo | 61449220 | 61527544 | 78,324 | 0.078324 | 7.80 | 1.090 | | | | | | | | | 0.71 |
| | | | | | | | | | | | | | | | | |
| **TOTAL** | | | | **2,360,988** | **2.360988** | | | <5.0 | 11.0 | | <0.010 | <0.030 | <0.010 | 0.00026 | <0.020 | |
| | | | **High:** | **87,494** | | | | | | | | | | | **High:** | **0.80** |
| | | | **Average:** | **78,700** | | | | | | | | | | | **Average:** | **0.72** |

WW

E

JC18132

**Accutest Labs**
2235 ROUTE 130
Dayton, NJ 8810
732-329-0200

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 42472.64667
COC# 087-WW-041216

| | | |

SGS Accutest LabLink@909884 14:18 12-May-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-041216-A | | |
| **Lab Sample ID:** | JC18132-1 | **Date Sampled:** | 04/12/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/12/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1090 | 10 | ug/l | 1 | 04/13/16 | 04/14/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 04/13/16 | 04/14/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 04/13/16 | 04/15/16 | GT | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | 0.26 | 0.20 | ug/l | 1 | 04/13/16 | 04/13/16 | JPM | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 04/13/16 | 04/14/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 04/13/16 | 04/14/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA39168
(2) Instrument QC Batch: MA39183
(3) Instrument QC Batch: MA39193
(4) Prep QC Batch: MP93115
(5) Prep QC Batch: MP93118

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@909884 14:18 12-May-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-041216-A | | |
| **Lab Sample ID:** | JC18132-1 | **Date Sampled:** | 04/12/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/12/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | < 4.0 | 4.0 | mg/l | 1 | 04/13/16 | LA | SM2540 D-11 |
| pH [b] | 6.99 | | su | 1 | 04/12/16 18:21 | JK | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 500 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@909884 14:18 12-May-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-041216-A | | |
| **Lab Sample ID:** | JC18132-1A | **Date Sampled:** | 04/12/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/12/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 11.0 | 3.4 | mg/l | 1 | 04/13/16 18:20 | LA | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@909884 14:18 12-May-2016

# Report of Analysis



4.3
4

| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-041216-B | | |
| **Lab Sample ID:** | JC18132-2 | **Date Sampled:** | 04/12/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/12/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | N254162.D | 1 | 04/14/16 | WO | n/a | n/a | VN10745 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 4.5 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 4.0 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.23 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 26.7 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.31 | 1.0 | 0.15 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.34 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 62.6 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 2.4 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.83 | 1.0 | 0.16 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS ACCUTEST

SGS Accutest LabLink@909884 14:18 12-May-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-041216-B | | |
| **Lab Sample ID:** | JC18132-2 | **Date Sampled:** | 04/12/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/12/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 72.7 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 93% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 96% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 94% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 97% | | 79-120% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@909884 14:18 12-May-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-041216-B | | |
| **Lab Sample ID:** | JC18132-2 | **Date Sampled:** | 04/12/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 04/12/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 04/13/16 18:30 | LS | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending May 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized in supplemental DCBs based field obersvations and constructability review. | Submitted to Contractor only. |
| **DC 2014-11-20** | DC 2014-11-20 supplements DC 2014-06-10 and includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Contractor only. |
| **DC 2015-2-12** | DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Contractor only. |
| **DC 2014-2-24** | DC 2016-5-24 was issued to document the changes in the SA-6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Contractor only. |
| **DC 2015-9-03** | DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Contractor only. |
| **DC 2016-5-24** | DC 2016-5-24 was issued to address the elimination of a drop structure, the elmination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending May 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |

**SA-6 North/South Field Change Log - Month Ending May 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |

**SA-6 North/South Field Change Log - Month Ending May 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |

**SA-6 North/South Field Change Log - Month Ending May 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |
| **DC 2016-02-03** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending May 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location. In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Contractor only. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Contractor only. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-5-11** | Consistent with minor Bayfront final grading changes, Amec adjusted the interim grade in the SA-6 North landscape area by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | Submitted to Contractor only. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane liner elevations proximate to Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**7/14/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

July 14, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-06**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from June 1 – June 30, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: June 2016 SA-6/7 Combined Monthly Progress Report No. 2016-06

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP (electroni copy)

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-06

**Project SA-6 & 7 Remediation**

## June 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 06/10/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-05 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/16/16 | 3 Year Sampling At TA-7 & TA-8<br>Study Area 6 North<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/20/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 06/21/16 | Special Master All Hands Conference Call | n/a |
| 06/30/16 | Design Change Bulletin: Temporary Construction Road in SA-6 South Cap<br>Study Area 6 (SA-6) South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 06/30/16 | Integrated Annual Groundwater Performance Report for 2015<br>Study Areas 5, 6, and 7<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |

## SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 06/05/16 | 06/12/16 | 06/19/16 | 06/26/16 |
| **Construction Management (AMEC)** | 9 | 9 | 9 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 06/05/16 | 06/12/16 | 06/19/16 | 06/26/16 |
| **Entact/Subcontractors** | 32 | 33 | 32 | 32 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 1 | 1 |
| **ESI** | 0 | 0 | 0 | 13 |
| **Lagan** | 0 | 0 | 0 | 1 |
| **Century** | 0 | 0 | 0 | 1 |
| **Evoqua** | 1 | 1 | 1 | 2 |
| **B&B Drilling** | 0 | 1 | 2 | 2 |
| **Cornerstone** | 1 | 1 | 0 | 3 |
| **TOTAL STAFF** | **49** | **51** | **50** | **69** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Conducted second round of quarterly regional groundwater level measurements.
- Conducted S-3 Mass Removal Injection Event No. 29 in injection well 088-IW-01 and related semi-annual groundwater quality sampling.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 South and SA-6 North.
- Completed installation of piezometer pairs associated with SA-6 North Open Space Area.
- Completed reinstallation of electrical service on the northeast corner of SA-7.
- PVSC completed yearly inspection of the GWTP and the CWTP on June 2, 2016.
- Collected June PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Collected 3-Year Performance Assessment soil samples from in-situ treatment areas TA-7 and TA-8 in accordance with the Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil (dated February 2013) on June 27, 2016.

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on June 9, 2016.
- Completed replacement of Groundwater Treatment Plant breaker and electrical panel.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 06/05/16 | 06/12/16 | 06/19/16 | 06/26/16 |
| Avg. Gallons Treated & Discharged (per day) | 76,848 | 78,192 | 77,202 | 74,270 |
| Average Flow (gpm) for Operating Period | 57 | 56 | 56 | 55 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 3,331 | 3,816 | 2,512 | 3,619 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed excavation and post-excavation sampling of small area of observed chromium impacted soils under the former 60 Kellogg St. building. Post excavation sampling indicates that results were <20ppm.
- Completed cutting of pilings within the 60 Kellogg footprint and completed backfilling of the 60 Kellogg excavation.
- Completed disassembly of SA-6 South Soil Containment area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 1 | 17.6 | 17.6 |
| **Bayshore** | Tri-Axle | Keasbey, NJ | Bayshore Recycling | Non-Haz Petroleum Soil | 84 | 24 | 2,016 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Excavation Completed** | Excavation Area 60 Kellogg Footprint<br>Volume Excavated - Total for Reporting Period: 60 Kellogg (30 CY) |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 06/05/16 | 06/12/16 | 06/19/16 | 06/26/16 |
| Natures Choice Horizon C | 1,020 | 0 | 0 | 0 |
| Cedar Hill Horizon B | 3,929.39 | 2,545.57 | 4,185.73 | 848.7 |
| Tilcon Mount Hope I-8 | 630.20 | 179.47 | 301.45 | 0 |
| Natures Choice Topsoil | 0 | 0 | 1,678.96 | 0 |
| Tilcon 3/8" Stone | 0 | 102.64 | 0 | 51.41 |
| Weldon Screenings | 2,977.8 | 2,543.6 | 1,870.25 | 358.04 |

- Overburden historic fill soils with hexavalent chromium concentrations confirmed to be < 20 mg/kg soils were transferred and placed as backfill in Site 140.
- Continued to screen Celgene material for use as protective cover soils on the SA-6 North Open Space Area.

## D. SURCHARGE OPERATIONS

- Area 1S: Surcharging and offloading of surcharge material is complete.
- Area 2S: Surcharging and offloading of surcharge material is complete.
- Area 3S: Surcharging and offloading of surcharge material is complete.
- Area 1N: Surcharging and offloading of surcharge material is complete.
- Area 2N: Surcharging and offloading of surcharge material is complete.
- Area 3N: Surcharging and offloading of surcharge material is complete.
- Area 4N: Surcharging and offloading of surcharge material is complete.

## E. SHEET PILE OPERATIONS

- Continued cutting hydraulic barrier sheets to final elevation in SA-6 North Open Space Area.

## F. CAPPING OPERATIONS

- Completed placement of root barrier and demarcation tape and importing and placing Horizon C soils to include associated compaction testing on the SA-6 South Open Space Area.
- Completed importing and placing Horizon B soils atop Horizon C soils on SA-6 South Open Space Area.

- Continued importing and placing Horizon A Topsoil.
- Applied lime on western portion of the SA-6 South Open Space Area topsoil in preparation for hydro-seeding.
- Continued placement of Structural Fill Material in the future utility corridors crossing the SA-6 South open space area to include associated compaction testing on the SA-6 South Open Space Area.
- Continued SA-6 North geomembrane liner subgrade grading activities within the Open Space Area.
- Began installation of geosynthetic components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- A total of 57,807 sq. ft. of geomembrane liner totaling 13% of the total cap area was deployed during the reporting period.
- Completed spark testing on three initial boot welds.
- Continued cutting hydraulic barrier sheets and finishing the SCB wall to final elevation in SA-6 North Open Space Area.
- Continued installation of Gas Vent Pipe within the SA-6 North Open Space Area.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue importing and placement of Horizon A Topsoil and on the SA-6 South Open Space Area.
- Begin Hydro-seeding of SA-6 South Open Space Area.
- Continue screening of Celgene soils for protective cover soils.
- Continue cutting SA-6 North Hydraulic Barrier Wall and Soil-Cement Bentonite Wall to geomembrane liner grade.
- Continue preparation of the SA-6 North subgrade for geomembrane liner installation.
- Continue installation of geosynthetic components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- Begin placement of GDL cover soils within the SA-6 North Open Space Area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Continue installation CGWES Components.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 30 in well 088-IW-02.
- Conduct second quarterly LTMP regional groundwater level measurement round.
- Prepare and submit the NJDEP – Discharge to Groundwater Permit by Rule for Treatment Area 10-1 injections.

## ATTACHMENTS:

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data *(sampled June 30; data not available for this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update
    - SA-6 Cap Subgrade Progress Maps
    - Repair Log
    - Non-conformance Log
    - Subgrade Approval Form
    - QA Photo Log
    - Daily QA Reports (Langan)
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log


# Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule

amec foster wheeler

| ID | Task Name | Duration |
|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** |
| **2** | **Remedial Action Work Plan** | **33 days** |
| **5** | **Remedial Action Design** | **1522 days** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** |
| 19 | Develop Site Relocation Master Plan | 38 days |
| 20 | Submit Site Relocation Master Plan | 0 days |
| 21 | JC Construction of New Facilities | 1309 days |
| 22 | Relocation Contractor Procurement | 392 days |
| 23 | JCIA and JCDPW Relocation | 949 days |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days |
| 24a | Demolition of JCIA Structures | 146 days |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** |
| **26** | **Remedial Action Work Plan** | **187 days** |
| **32** | **Remedial Action Design** | **1161 days** |
| **57** | **SA-6 South Relocation** | **616 days** |
| 58 | New GWTP Construction Completion | 502 days |
| 59 | Demolition of 80 Kellogg | 857 days |
| **60** | **SA-6 North/South Field Implementation** | **894 days** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** |
| 61a | Mobilization | 87 days |
| **62** | **Surcharge Install/Instrumentation** | **706 days** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days |
| **63** | **Barrier Wall Install** | **569 days** |
| 63a | SA 6N Installation of Barrier Wall | 159 days |
| 63b | SA 6S Installation of Barrier Wall | 210 days |
| **64** | **Excavation** | **507 days** |
| 64a | SA 6N Excavation | 218 days |
| 64b | SA 6S Excavation | 295 days |
| **65** | **Backfill** | **558 days** |
| 65a | SA 6N Backfill | 283 days |
| 65b | SA 6S Backfill | 384 days |
| **66** | **Capping and Cover Soil Placement** | **426 days** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days |
| **67** | **Restoration** | **234 days** |
| 67a | Restoration | 234 days |
| **68** | **Demobilization** | **22 days** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | |
| **69** | **SA-6 North Project Closeout** | **311 days** |
| **75** | **SA-6 South Project Closeout** | **311 days** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** |




Current field implementation schedule shows capping complete in September 2016 and restoration in October 2016.

Project: SA-6 Remediation Schedule
Revision 4
Date: 6/22/15

Task Milestone Summary Critical

# Attachment 2: Site Photographs




**Site Photograph 1:** Grading clean imported cover soils in Open Space Area.




**Site Photograph 2:** Installing monitoring wells former Jersey City properties.




**Site Photograph 3:** Loading clean imported cover soils for placement in Open Space Areas.




**Site Photograph 4:** Placement of Venting Layer in Open Space Area.




**Site Photograph 5:** Placing clean imported topsoil in Open Space Area Kellogg St properties.




**Site Photograph 6:** Removing trimmed sections of sheet pile barrier wall.





**Site Photograph 7:** Unloading clean imported stone screenings in utility corridor.

# Attachment 3: Excavation and Backfill

- Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of July 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-06
Attachment 3: Excavation and Backfill (Progression Chart)




## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

# Attachment 4: Dewatering Operations Update

(not included in this reporting period)

# Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)


| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 04/29/16 | 10:00 | 14:15 | 4:15 | 42,847.64 | 42,912.90 | 65,260 | 42,912,450 | |
| 05/06/16 | 10:00 | 15:00 | 5:00 | 42,912.90 | 42,965.49 | 52,590 | 42,965,040 | PVSC Compliance Sample Collected |
| 05/13/16 | 11:00 | 15:00 | 4:00 | 42,965.49 | 43,019.78 | 54,290 | 43,019,330 | |
| 05/20/16 | 11:00 | 15:00 | 4:00 | 43,019.78 | 43,071.32 | 51,540 | 43,070,870 | |
| 05/27/16 | 10:00 | 14:00 | 4:00 | 43,071.32 | 43,130.78 | 59,460 | 43,130,330 | |
| 05/31/16 | 11:00 | 14:30 | 3:30 | 43,130.78 | 43,178.93 | 48,150 | 43,178,480 | |
| 06/01/16 | 6:30 | 13:30 | 7:00 | 43,178.93 | 43,268.97 | 90,040 | 43,268,520 | |
| 06/06/16 | 7:30 | 13:30 | 6:00 | 43,268.97 | 43,338.94 | 69,970 | 43,338,490 | |
| 06/08/16 | 7:30 | 12:00 | 4:30 | 43,338.94 | 43,402.10 | 63,160 | 43,401,650 | PVSC Compliance Sample Collected |
| 06/13/16 | 9:00 | 13:00 | 4:00 | 43,402.10 | 43,464.75 | 62,650 | 43,464,300 | |
| 06/21/16 | 8:00 | 14:00 | 6:00 | 43,464.75 | 43,543.94 | 79,190 | 43,543,490 | |
| 06/24/16 | 9:00 | 14:00 | 5:00 | 43,543.94 | 43,596.37 | 52,430 | 43,595,920 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

# Attachment 6: Backfill Analytical Data

(not included in this reporting period)

# Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-5 | FS-6 | FS-7 | FS-13 |
| Date | | | | | | | | | | | | | |
| 7/16/2015 | 2.8 | 5.0 | 5.7 | 3.6 | 4.1 | | 3.2 | 2.6 | 6.2 | 4.8 | 4.7 | 3.9 | 4.1 |
| 7/31/2015 | 2.8 | 5.0 | 5.5 | 3.2 | 3.8 | | 2.3 | 2.0 | 6.0 | 4.6 | 4.5 | 3.7 | 3.3 |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | 4.6 | 4.5 | 3.9 | 4.0 |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | 4.5 | 4.5 | 3.6 | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | 4.4 | 4.3 | 3.5 | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | 4.4 | 4.4 | 3.5 | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | 4.7 | 4.6 | 4.0 | 4.0 |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | 4.7 | 4.6 | 3.9 | 3.8 |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | 4.6 | 4.6 | 3.7 | 3.4 |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | 4.5 | 5.0 | 3.8 | 3.5 |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | 3.5 | 3.6 | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | 5.2 | | | 4.6 |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | 6.0 | | | 5.6 |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | 6.5 | | | 6.2 |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | 6.0 | | | 5.7 |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | 5.6 | | | 5.0 |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | 2.7 | | | 3.6 |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | 2.1 | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | 1.8 | | | |
| 5/2/2016 | 3.1 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | 1.6 | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | |
| 6/1/2016 | 2.7 | 5.2 | 5.5 | 2.5 | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/16/2016 | 2.7 | 5.2 | 5.6 | | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/28/2016 | 3.2 | 5.3 | 5.5 | 2.4 | 3.2 | 2.4 | 3.1 | 3.2 | 1.7 | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

# Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update


(not included in this reporting period)

# Attachment 10: Sheet Pile Update

(not included in this reporting period)

## Attachment 11: Capping Update

- SA-6 Cap Subgrade Progress Maps
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports (Langan)




LEGEND

- SUBGRADE GRADING UNDERWAY
- SUBGRADE COMPLETE AND SURVEYED
- APPROVED FOR GEOSYNTHETIC DEPLOYMENT
- LINER DEPLOYED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP SUBGRADE PROGRESS MAP
06/24/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LEGEND

- HORIZON B PLACED AND READY FOR TOPSOIL
- HORIZON C PLACED AND READY FOR TOPSOIL
- TOPSOIL PLACED
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
06/30/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 954 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 1034.67 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | PB | 1/2 | P-1 | 35' N OF SEOS & 8'W | P | 3 | x | 11 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 2 | BO | 3/5 | | 2' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 3 | SJ | 3/4/5 | | 69' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 4 | CF | 4/6 | | 5' S OF NEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 5 | CF | 4/6 | | 77' N OF SEOS | P | 5 | x | 12 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 6 | SJ | 4/5/6 | | 69' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 7 | PB | 5/6 | | 15' N OF S EOS (PB 6") | P | 3 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 8 | WR | 6/7 | P-6 | 63' N OF SEOS & 5'W | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 9 | BO | 6/7 | | 66' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 10 | SI | 6/7 | P-6 | 80' N OF SEOS & 5'W | P | 3 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 11 | DS-2 | 6/7 | | 16' N OF SEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 12 | WR | 7/9 | | 41' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 13 | CF | 7/9 | P-9 | 45' N OF SEOS & 10'E | P | 6 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 14 | DS-1 | 1/2 | | 15' N OF SEOS | P | 2 | x | 7 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 15 | DSX-1 | | P1/R15 | 34'N OF SEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 16 | CF | | P9 | BETWEEN R12 & R13 | B | | x | | 60 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 17 | WR | 7/9 | | 71' N OF SEOS | B | 3 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 18 | CF | | P9 | BETWEEN R17 & R19 | B | | x | | 168 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 19 | CF | 7/9 | P9 | 59' N OF SEOS & 12'E | P | 4 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 20 | CF | | P6 | BETWEEN R22 & R9 | B | | x | | 36 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 21 | CF | | P6 | BETWEEN R22 & R8 | B | | x | | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 954 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 1034.67 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 22 | CF | | P6 | 68' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 23 | SJ | 7/8/9 | | 103' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 24 | CF | 8/10 | | 11' S OF NEOS | P | 2 | x | 20 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 25 | SJ | 8/9/10 | | 103' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 26 | DO | 10/11 | P-10 | 27' N OF S EOS & 4'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 27 | CF | 10/11 | P10 | BETWEEN R-35 & R-28 | B | | x | | 156 | 6/26/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 28 | CF | 10/11 | P10 | 64' N OF SEOS & 15' W | P | 4 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 29 | PB | 10/11 | P10 | 93' S OF NEOS & 4'W (48" MH ) | P | 6 | x | 10 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 30 | CF | | P10 | BETWEEN R29 & R31 | B | | x | | 240 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 31 | CF | 10/11 | P10 | 68' S OF NEOS & 2' W | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 32 | CF | 10/11 | P10 | 76' N OF SEOS & 7' W | P | 2 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 33 | CF | | P10 | BETWEEN R-32 & R-34 | B | | x | | 60 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 34 | CF | 10/11 | | 78' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 35 | CF | 10/11 | | 69' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 36 | CF | 10/11 | | 49' N OF SEOS | P | 5 | x | 15 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 37 | CF | | P11 | 50' N OF SEOS | B | | x | | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 38 | PB | | 11 | 83' N OF SEOS (8" PIPE ) | P | 4 | x | 5 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 39 | DS-3 | 10/11 | | 25' S OF NEOS | P | 2 | x | 6 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 40 | AO | 10/11 | | 3' S OF NEOS | P | 12 | x | 12 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 41 | SJ | 11/12/13 | | 22' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 42 | SJ | 12/13/14 | | 24' S OF NEOS | P | 2 | x | 6 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 954 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 1034.67 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 64 | CF | 18/19 | | BETWEEN R-63 & R-65 | B | | x | | 12 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 65 | CF | | P19 | 30' N OF SEOS | P | 2 | x | 9 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 66 | CF | | P19 | BETWEEN R-65 & R-67 | B | | x | | 108 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 67 | CF | | P19 | 42' N OF SEOS | P | 3 | x | 7 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 68 | CF | 18/19 | | 46' N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 69 | CF | | P19 | BETWEEN R-68 & R-70 | B | | x | | 72 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 70 | CF | | P19 | 49' N OF SEOS | P | 3 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 71 | BO | 18/19 | | 115' N OF SEOS | P | 3 | x | 4 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 72 | BO | 18/19 | | 118' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 73 | DSX-2 | | P10/R30 | 106' N OF SEOS | P | 2 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 74 | | | | | | | x | | | | | | | | |
| 75 | | | | | | | x | | | | | | | | |
| 76 | | | | | | | x | | | | | | | | |
| 77 | | | | | | | x | | | | | | | | |
| 78 | | | | | | | x | | | | | | | | |
| 79 | | | | | | | x | | | | | | | | |
| 80 | | | | | | | x | | | | | | | | |
| 81 | | | | | | | x | | | | | | | | |
| 82 | | | | | | | x | | | | | | | | |
| 83 | | | | | | | x | | | | | | | | |
| 84 | | | | | | | x | | | | | | | | |

**Summary of Non-Compliance & Corrective Action Forms**
**SA-6 North Cap Installation**

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 1 | 6/23/2016 | Subgrade Irregularity | R-10 | Panel P6 | Rock was removed from underneath geomembrane and hole was then patched with approximate 3 ft. by 3 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 2 | 6/29/2016 | Subgrade Irregularity | R-98 | Panel P26 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |

**LANGAN**

# Certificate of Soil Surface

Sheet # 1

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 319+00 + ~STA 317+75 | | |
| QA Monitor | LANGAN | Date | 6/22/16 | | |

Description of Soil Surface to be lined: WESTERN END OF SA-6 NORTH (~STA 319+00) APPROX. 125 FT. EAST (STA. 317+75). SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS. NOTE: MINOR CHANGES IN SUBGRADE ELEVATION IN SELECT AREAS TO ALLOW POSITIVE DRAINAGE

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 6/22/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 6/22/16 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AS OUTLINED IN SECTION 02372-8.
MINOR CHANGES IN SUBGRADE ELEVATION IN SELECT AREAS OF CAP (COMPLETED BY ENTACT)
- NO GCL TO BE PLACED ALONG WESTERN END OF SA-6 NORTH

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | STA 319+00 | LOOKING N | REFER TO PHOTO #1 (PHOTO LOG 6/22/16) |
| | 2 PHOTO #2 | STA 318+50 | LOOKING N | REFER TO PHOTO #2 (PHOTO LOG 6/22/16) |
| 1. REFER TO 6/22/16 PHOTOGRAPH LOG PHOTOS 1 TO 4 FOR SUPPORTING INFORMATION. | | | | 2. |

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (06/22/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/22/16

**Direction Taken:**

Looking North along SA-6 North (western end of cap) near Sta. 319+00.

**Description:**

Soil subgrade prepared by Entact. Soil firm and unyielding, and graded, compacted and free of debris (> ½").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (06/22/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/22/16

**Direction Taken:**

Looking southeast along western end of SA-6 North.

**Description:**

Soil subgrade prepared by Entact. Soil firm and underlying, and graded, compacted and free of debris (>1/2")



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (06/22/2016)

| **Project:** Honeywell SA-6 North Capping | **Location:** SA-6 North (North of SA-7) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
6/22/16

**Direction Taken:**

Looking north along western end of SA-6 N (approximately Sta. 319+00)

**Description:**

ESI deploying 16oz. geotextile along western end of SA-6 North. Geotextile overlapped minimum of 1 ft. over the edges of the cap (remaining roll width inside)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (06/22/2016)

| **Project:** Honeywell SA-6 North Capping | **Location:** SA-6 North (North of SA-7) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
6/22/16

**Direction Taken:**

Looking south along SA-6 North (approximate Sta. 318+25).

**Description:**

ESI placing white plastic fasteners at maximum 5 ft. spacing along adjacent GVL panels. Top layer geotextile then sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (06/22/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
6/22/16

**Direction Taken:**

Looking north along western end of SA-6 North

**Description:**

ESI deploying LLDPE along western end of SA-6 North (approximate Sta. 319+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (06/22/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
6/22/16

**Direction Taken:**

Looking south / southeast along SA-6 North

**Description:**

LLDPE deployed across SA-6 North from approximate Sta. 319+00 to Sta. 317+75.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (06/24/2016)

| **Project:** Honeywell SA-6 North Capping | **Location:** SA-6 North (North of SA-7) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:** 6/24/16

**Direction Taken:**

Looking east / southeast along SA-6 North (from approximately Sta.316+50).

**Description:**

Soil subgrade prepared by Entact. Soil firm and unyielding, and graded, compacted and free of debris (> ½").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (06/24/2016)

| **Project:** Honeywell SA-6 North Capping | **Location:** SA-6 North (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:** 06/24/16

**Direction Taken:**

Looking north / northwest at Well 115-W6-SO

**Description:**

Amec conducting methane testing for Well 115-W6-SO pipe boot. Methane at concentration of 1.4% measured. No spark testing conducted on well pipe boot.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (06/24/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
6/24/16

**Direction Taken:**

SA-6 North – Gas Vent GV-6

**Description:**

ESI conducting spark testing for Gas Vent GV-6 pipe boot. Methane testing yielded results of 0.0% (below 1%), thus spark testing was conducted. No sparks identified during test. Spark test passed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (06/24/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
06/24/16

**Direction Taken:**

Looking south / southeast along SA-6 North (Panel P13 / P14).

**Description:**

ESI conducting fusion welding along Panel P13 / P 14 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (06/24/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/24/16

**Direction Taken:**

SA-6 North, Panel P12 / P13

**Description:**

ESI conducting non-destructive testing (i.e. pressure testing) for Panel seam P12 / P13 / P14. Seam pressurized to 30 psi and held for 5 minutes with <4 psi loss (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (06/24/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/24/16

**Direction Taken:**

SA-6 North Panel P10

**Description:**

ESI conducting vacuum box testing for R-31 (Panel P10).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 6/21/2015 |
| **PROJECT:** | SA-6 Capping | | | **WEATHER:** | 80/92° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Soil Subgrade Inspection | | **TIME:** | 0745 – 1215 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #1** |
|---|---|
| **Entact & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Philemon<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite to conduct soil subgrade inspection along the west end of SA-6 North. A preliminary kickoff meeting was conducted between AmecFW, Langan, and Entact to discuss the QA / QC activities, along with the strategy and implementation plan for the proposed capping of SA-6 North.
- Following the meeting, Langan and AmecFW conducted a visual observation of the prepared soil subgrade along the western end of SA-6 North. This area included the furthest western part of the cap (approximately 100 ft. from the western end moving east).
- In general, the following soil subgrade properties were observed:
  - Various debris including broken glass, wood fragments, small rocks, etc. were observed along the western end of SA-6 North (specifically along the slopes and elevation changes at the northern end of the cap). It is recommended that this debris addressed so that no objects are penetrating / extruding from the surface, and the overall subgrade is flat and even. Additionally, Entact should provide laborers with a wheelbarrow and equipment to collect various debris as it is encountered.
  - Some slight changes in elevation were observed in areas along the western end of the cap where one area appeared higher than the other. The variations in cap subgrade elevation could potentially result in the ponding of water. Additionally, the mouths along the tree bulb swales appeared to be higher than the swale itself, thus causing water to pond in the swales instead of flowing out and down the sides of the cap. AmecFW to review the survey data and confirm existing grades.
  - Additional details regarding the subgrade are outlined in the 6/21/16 Photograph Log attached as part of this report.
- AmecFW to address the issues outlined above, with follow up subgrade inspection to be completed on 6/22/16 by Langan (prior to deployment of GVL).

## ***Observations Requiring Contractor / QA Engineer Review***

- Based on the soil subgrade observation, the soil has not yet been approved for liner installation activities based on the debris / penetrations outlined in this report. It is recommended that the Entact provide the necessary labor to remove the various debris and provide a flat, even surface with no penetrations or extrusions through the subgrade.

Cc Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items Pending***

- QA Engineer - Review SA-6 North capping specifications and drawings. Review product submittals (as provided) and ensure that all data, drawings, and pertinent documents are ready for liner installation kickoff (planned to commence on 6/22/16).

***Action Items – Weekly Completions***

- None to Date

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- SA-6 North capping to commence on 6/22/16 (pending soil subgrade approval).

Cc: Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Photograph Log***



Photo 1: Wood and various debris observed along northern end of SA-6 North.



Photo 2: Looking south along western end of SA-6 North. Misc. trash and debris to be removed by Entact.

***Photograph Log (continued)***



Photo 3: Prepared subgrade along western end of SA-6 North. AmecFW to confirm and verify surveyed grades.



Photo 4: Soil subgrade along western end of SA-6 North. Entact to remove debris / penetrations. AmecFW to verify and confirm surveyed grades.

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 6/22/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/92° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0745 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #2**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Philemon<br>**Langan:** Dan Bosworth<br>**ENTACT**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) starting at the western end of SA-6 North. Material to be placed starting from the western end (approximate Sta. 319+00) of SA-6 North for approximately 125 ft. east. (to approximate Sta. 317+75).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area).
- Prior to placement of geosynthetic material, soil subgrade observation was conducted by Langan and Entact for the area outlined above. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1, 2, 3, and 4 of the daily photo log for 6/22/2016, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications as verified by AmecFW. Additionally, minor modifications to the subgrade elevations were completed by Entact to facilitate positive drainage flow away from the tree bulb swales (located at approximate Sta. 317+75).
- Following soil subgrade approval, ESI began by placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed on the western end of the Site (approximate Sta. 319+00) moving east (to approximate Sta. 317+75). GVL was placed according to the project specifications with white plastic fasteners spaced at a minimum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 6/22/16 Photo Log for supporting photographs.
- After installation of GVL, geomembrane liner was installed beginning at the western end of SA-6 North and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 319+00 to approximate Sta. 317+75. A total of seven panels were installed (P1, P2, P3, P4, P5, P6, and P7). Note: P1 consisted of an approximate 50 ft. by 18 ft. piece of LLDPE installed along the western end of SA-6 North. During placement of panel P4, the roll of LLDPE terminated at the approximate center of the cap, thus the remaining run of LLDPE was installed as P5. P2, P3, P6, and P7 ran the entire width of SA-6 North (approximately 162 ft.) from north to south.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Adjacent panel seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing. The results of the pre-trial weld are provided in the 6/22/16 *Trial Weld Log.*
- Non-destructive testing was then conducted (pressure testing) for the fusion welded seams. 30 psi was applied to the seams and held for 5-minute increments with no more than 4 psi loss measured over the 5-minute interval. The results of the non-destructive tests are outlined in the *Seam Control Form.*
- Destruct test samples and extrusion weld detailing to be completed on 6/23/15.

***Non-Conformance Items / Corrective Actions***

- None Encountered.

***Action Items – Pending***

- Complete Daily Report and Photo Log. Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, etc.)

***Action Items – Weekly Completions***

- None to Date

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 317+75 to Sta. 316+75).
- Continue with 16 oz. geotextile, GVL, and LLDPE placement moving east along SA-6 North.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be certified upon completion of SA-6 North |
| A2 – Receiving and Inspection | | NA - No material delivered to the site on 6/22/16 |
| A3 – Photo Log | Pages 1 - 8 | Total of 16 photos outlining pertinent daily observations and descriptions for activities completed on 6/22/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date, no updates from 6/22/15 |
| A5 – Subgrade Approval | Sheet 1 & ESI (6/22/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 1 | One trial weld log provided by ESI and confirmed by Langan for trial welds completed on 6/22/16 |
| A7 – Panel Placement Log | Sheet 1 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 6/22/16. |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 6/22/16 |
| A9 – Seam/Non-Destruct. Test Log | Sheet 1 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/24/15 |
| A10 – Repair Log | | NA – no repairs or extrusion welds completed on 6/22/16. |
| A11 – Conformance COC | | NA – for 6/22/16. |
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 6/22/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 6/22/16 |
| A14 – Penetration & Edge Form | | NA – no penetrations / boots completed on 6/22/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 6/22/16 |
| A17 – Spark Test Form | | NA – no spark testing conducted on 6/22/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 6/23/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/90° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0650 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Lull, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #3**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) continuing east from panel P7 installed on 6/22/16 (approximate Sta. 317+75). Material to be placed from Panel P7 running approximately 125 ft. east to approximate Sta. 316+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 317+75 (Panel P7 installed on 6/22/16) to approximate Sta. 316+50. Refer to *Soil Subgrade Approval* forms from 6/23/15 for additional details. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos 1 to 4 of the daily photo log for 6/23/2016, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications as verified by AmecFW
- GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 317+75 (east Panel P7) moving east to approximate Sta. 316+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a minimum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/23/16 Photo Log for supporting photographs.
- While GVL was being deployed, ESI also conducted patch / repair work along the panels installed on 6/22/16 (Panels P1 to P7). Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (6/23/16).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of eleven repairs (R-1 through R-11) were observed and fixed (according to the project specifications) from Panels P1 through P7. Refer to 6/23/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane (installed on 6/22/16) was being patched / repaired, ESI also began to prepare penetration boots for Piezometer PZ10 and Well 115-W6-SO. Note: The boot and boot skirts were completed, however, the vertical welds along the boot have not yet been completed as methane testing / spark testing are to be completed prior to finalizing the boot details.
- During repair activities / extrusion welding one non-conformance issue was observed and was documented on Sheet #1 as non-compliance. The non-compliance issue encountered was identified based on debris / rock that was observed underneath the LLDPE geomembrane. The rock was subsequently removed and the hole was patched / repaired according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – *Sheet #1* for 6/23/16. The non-compliance issue was also recorded within the *Repair Log* as a subgrade irregularity and is identified as R-10.
- After placement of GVL, geomembrane liner was installed beginning at the western end of SA-6 North (from Panel P7) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 317+75 (Panel P7) to approximate Sta. 316+50. A total of six panels were installed (P8, P9, P10, P11, P12, and P13). Note: During placement of panel P8, the roll of LLDPE terminated approx.. 2/3 from the north of the cap, thus the remaining run of LLDPE was installed as P9. Similarily, during placement of Panel P12, the roll terminated along the northern end of SA-6 North, thus the remaining run of LLDPE was labeled as P13. Panels P10 and P11 ran the entire width of SA-6 North (approximately 162 ft.) from north to south.
- Adjacent geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 6/23/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 316+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 6/23/16 *Seam Control Form* for non-destructive testing details. Additionally, repair and extrusion weld activities were also conducted for Panels P8 through P13. A total of 32 additional repairs (RP-11 through RP-43) were observed and fixed according to the project specifications. Additional details are also outlined on the 6/23/16 *Repair Log.*
- A total of four destruct samples were collected for laboratory sampling by Entact / ESI. Three fusion weld destruct samples DS-1 (Panel P1 / P2 seam), DS-2 (Panel P6 / P7 seam), and DS-3 (Panel P10 / P11 seam) were collected for laboratory analysis. Additionally, one extrusion weld sample DSX-1 (Panel P1) was also collected for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 1 (Sheet #1) – Subgrade irregularity identified as R-10 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P6. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 1 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 6/23/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16. ESI Daily Form Submittals still to be reviewed.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/23/16 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 6/23/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/23/16 |
| A5 – Subgrade Approval | Sheet 2 & ESI (6/23/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/23/16 |
| A7 – Panel Placement Log | Page 2 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 6/23/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/23/16 |
| A9 – Seam/Non-Destruct. Test Log | Page 1 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 6/23/16 |
| A10 – Repair Log | Pages 1,2,3 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/23/16 |
| A11 – Conformance COC | | NA for 6/23/16 |
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 6/23/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 6/23/16 |
| A14 – Penetration & Edge Form | | NA – Pipe boot skirts completed, methane testing to be completed before finalizing welds and conducting spark testing. |
| A16 – Notice of Non-Compliance | Sheet 1 | One non-compliance issue identified on 6/23/16 and summarized on Sheet 1. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 6/24/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1545 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #4**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) continuing east from Panel P12 / P13 installed on 6/23/16 (approximate Sta. 316+50). Material to be placed from Panel P12 / P13 running approximately 75 ft. east to approximate Sta. 315+75.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 316+50 (Panel P12 / P13 installed on 6/23/16) to approximate Sta. 315+75. Refer to *Soil Subgrade Approval* forms from 6/24/15 for additional details. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos 1 to 3 of the daily photo log for 6/24/2016, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications as verified by AmecFW
- GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 316+50 (east of Panel P12 / P13) moving east to approximate Sta. 315+75. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/24/16 Photo Log for supporting photographs.
- While GVL was being deployed, ESI also continued patch / repair work for the panels installed on 6/23/16 (Panels P8 to P13). Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (6/24/16).
- In addition, methane / spark testing was conducted for the pipe boots completed for Well 115-W6-SO,

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Piezometer PZ10, and Gas Vent GV-6. Prior to spark testing, methane testing was conducted to measure the concentration of methane present below the LLDPE geomembrane. During methane testing of Well 115-W6-SO, a concentration of 1.4% (greater than 1%) was measured. No spark testing was conducted on Well 115-W6-SO due to the measured methane concentration. Instead, the weld was visually observed for deficiencies and none were noted.

- Methane testing for PZ10 and Gas Vent GV-6 yielded methane concentrations of 0.8% and 0.0%, respectively (<1%). Following the methane testing, spark testing was conducted by ESI for the vertical weld and pipe boot weld at the base of the penetration (i.e. welds not accessible for vacuum box testing). No sparks were observed during the test, and both boots passed. Additional details are outlined in the *Spark Testing QA Form Sheets #1-3.*
- After placement of GVL, LLDPE geomembrane was installed continuing from Panel P12 / P13 (installed on 6/23/16) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 316+50 (Panel P12 / P13) to approximate Sta. 315+75. A total of six panels were installed (P14, P15, P16, P17, P18, and P19). Note: During placement of panel P15, the roll of LLDPE terminated approx. 2/3 from the north of the cap, thus the remaining run of LLDPE was installed as P16. Panels P14, P17, P18, and P19 ran the entire width of SA-6 North (approximately 192 ft.) from north to south.
- Adjacent geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 6/24/16 *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 315+75, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 6/24/16 *Seam Control Form* for non-destructive testing details. Additionally, repair and extrusion weld activities were also conducted for Panels P14 through P19. Additional details are also outlined on the 6/24/16 *Repair Log.*
- A total of thirty repairs (RP-44 through RP-73) were observed and fixed (according to the project specifications) from Panels P14 through P19. Refer to 6/24/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Note: vacuum box testing not completed for all welds. To be continued on 6/27/16.
- A total of two destruct samples were collected for laboratory analysis by Entact / ESI. One fusion weld destruct sample DS-4 (Panel P15 / P17 seam) was collected for laboratory analysis. Additionally, one extrusion weld sample DSX-2 (Panel P10) was also collected for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 6/24/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample data (once received from laboratory).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16 and 6/23/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1, DS-2, and DS-3. Reviewed laboratory data for extrusion weld destruct sample DSX-1.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/24/16 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 6/24/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/24/16 |
| A5 – Subgrade Approval | Sheet 3 & ESI (6/24/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/24/16 |
| A7 – Panel Placement Log | Pages 2&3 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 6/24/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/24/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 4 to 6 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 6/24/16 |
| A10 – Repair Log | Pages 2 to 3 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/24/16 |
| A11 – Conformance COC | | NA for 6/24/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 6/24/16 |
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 6/24/16 |
| A14 – Penetration & Edge Form | Sheets 1 to 3 | Pipe boot skirts completed, methane / spark testing completed for Piezometer PZ10, Well 115-W6-SO and Gas Vent GV-6 as outlined on the Sheets 1 to 3. |
| A16 – Notice of Non-Compliance | | NA - no non-compliance issues identified on 6/24/16. |
| A17 – Methane / Spark Testing Log | Sheets 1 to 3 | Methane / spark testing completed for Piezometer PZ10, Well 115-W6-SO, and Gas Vent GV-6. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 6/29/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 78/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0650 – 1530 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #6** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for LLDPE repair activities to be completed on LLDPE geomembrane installed on 6/27/16. Note: No capping activities conducted on 6/28/16 due to inclement weather, and no new LLDPE was placed on 6/29/16 as soil subgrade was not approved.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI continuing with non-destructive testing (pressure testing) and repair activities for geomembrane panels P19 through P27 (installed on 6/27/16). Non-destructive testing was conducted on the remaining panel seams and the seams were pressurized to 30 psi and held for 5 minutes with less than 4 psi loss. Refer to *6/29/16 Seam Control Form* for additional details.
- A total of twenty-two repairs (R-82 through RP-103) were observed and fixed (according to the project specifications) from Panels P19 through P27. Refer to 6/29/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of two destruct samples were collected for laboratory analysis. Two fusion weld destruct samples, DS-5 and DS-6, were collected from Panel Seam P19 / P20 and Panel Seam P23 / P24, respectively. Additional details are outlined in the *Trial Weld Log* dated 6/29/16.
- The LLDPE pipe boot penetration for Gas Vent GV-5 was completed and extrusion welded. Note: no methane testing / spark testing completed. Methane / spark testing to be completed week of July 5, 2016.
- While ESI was conducting repairs, small areas of standing water were observed on the soil subgrade from Sta. 314+25 to approximate Sta. 313+75. Entact solidified the subgrade by adding calcium cement to the soils so that the wet areas were absorbed / removed. Additionally, minor modifications to the subgrade were completed to facilitate positive drainage off of SA-6 North.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 2 (Sheet #2) – Subgrade irregularity identified as R-98 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P26. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 2 Notice of Non-Compliance.*

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 6/29/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct samples results for DS-5 and DS-6.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, and 6/27/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1, DS-2, DS-3, and DS-4. Reviewed laboratory data for extrusion weld destruct sample DSX-1 and DSX-2. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/29/16 |
| A3 – Photo Log | Pages 1 – 4 | Total of 7 photos outlining pertinent daily observations and descriptions for 6/29/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/29/16 |
| A5 – Subgrade Approval | | NA - no subgrade approval for 6/29/16 |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/29/16 |
| A7 – Panel Placement Log | | NA – no LLDPE panels placed on 6/29/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/29/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 6-7 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 6/29/16 |
| A10 – Repair Log | Pages 4-5 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/29/16 |
| A11 – Conformance COC | | NA for 6/29/16 |
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 6/29/16 |
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 6/29/16 |
| A14 – Penetration & Edge Form | 6/29/16 Form | LLDPE pipe boot penetration form completed for Gas Vent GV-5. Note: methane / spark testing not completed (to be completed week of June 5, 2016). |
| A16 – Notice of Non-Compliance | Sheet 2 | One non-compliance issue identified on 6/29/16 and summarized on Sheet 2. |
| A17 – Spark Testing Form | | NA – no methane / spark testing completed on 6/29/16 for Gas Vent GV-5. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

# Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 3, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | X | | 3 |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/06/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, June 03, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The silt fabric in the catch basin at the western end of Kellogg Street requires maintenance or replacement. |
| 2 | IA2Q4A1AL8 | REPEAT: Sediment has accumulated on the western end of Kellogg Street. |
| 3 | IA2Q4A1AL8 | Drums in active use in the mechanics area on SA-6 North are not on spill pallets. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 06/06/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the filter fabric in the catch basin as required. | 6/9/16 (AD) |
| 2 | REPEAT: Clean the sediment from the western end of Kellogg Street by the current truck entrance/exit gate. | |
| 3 | Place all drums which are in use on spill pallets. | ✓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 06/09/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 10, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/13/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, June 10, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The tracking pad at the western Kellogg Street gate is blinded with sediment and not functioning. |
| 2 | IA2Q4A1AL8 | Windscreen material is missing from the newly-installed fence panels by the 60 Kellogg excavation area. |
| 3 | IA2Q4A1AL8 | Garbage has accumulated on the grass by the Kellogg Street jughandle. |
| 4 | IA2Q4A1AL8 | Windscreen material on the perimeter fence by the JCMUA parking lot has partially detached from the fence and requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 06/10/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Clean or replace the tracking pad stone to restore function | 6-15-16 RAD |
| 2 | Install windscreen fabric on the Kellogg Street perimeter fence as needed. | / |
| 3 | Pick up and discard accumulated garbage/rubbish as required. | / |
| 4 | Re-attach windscreen material on the perimeter fenceline by the JCMUA front parking lot as required. | / |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date** 06/16/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 17, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/20/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, June 17, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: The tracking pad at the western Kellogg Street gate is blinded with sediment and not functioning. |
| 2 | IA2Q4A1AL8 | Sediment has accumulated on the western end of Kellogg Street by the truck entrance. |
| 3 | IA2Q4A1AL8 | Silt bags in two catch basins on the southern side of the H-Building on SA-6 North require maintenance. |
| 4 | IA2Q4A1AL8 | Sediment has accumulated on the western haul road on SA-7 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 06/20/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | REPEAT: Clean or replace the tracking pad stone to restore function. | 6-22-16 (2nd) |
| 2 | Remove accumulated sediment from the western end of Kellogg Street. | |
| 3 | Replace filter fabric in the two catch basins on the southern side of the H-Building. | |
| 4 | Remove accumulated sediment from the western SA-7 haul road. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 06/23/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: June 24, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 06/27/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, June 24, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and debris has accumulated on the grass area at the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | REPEAT: Sediment has accumulated on the western haul road on SA-7. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 06/27/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and dispose of accumulated litter at the Kellogg Street jughandle. | 6/30/16 RAD |
| 2 | REPEAT: Remove accumulated sediment from the western SA-7 haul road. | √ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 06/30/16

# Attachment 13: GWTP Update

- 525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted June 2016)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

June 20, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the May 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy/SGF

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 5 | 01 | 16 | 5 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,941 | 92,574 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.51 | 0.61 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.00020 | <0.00020 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1864 | 0.1864 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | ~~Sample Measurement~~ | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT


Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**



Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director

Type Name and Title

06/16/2016

Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 5 | 01 | 16 | 5 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,416,174 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 63,943,718 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 5/10/2016 | <4.4 | 6.6 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 06/16/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: May 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 5/1/2016 | Angel Trujillo | 61527544 | 61604864 | 77,320 | 0.07732 | 7.70 | 0.785 | | | | | | | | | 0.51 |
| 5/2/2016 | Angel Trujillo | 61604864 | 61682184 | 77,320 | 0.07732 | 7.56 | 0.785 | | | | | | | | | 0.51 |
| 5/3/2016 | Angel Trujillo | 61682184 | 61758654 | 76,470 | 0.07647 | 7.16 | 0.785 | | | | | | | | | 0.50 |
| 5/4/2016 | Angel Trujillo | 61758654 | 61834632 | 75,978 | 0.075978 | 7.20 | 0.785 | | | | | | | | | 0.50 |
| 5/5/2016 | Angel Trujillo | 61834632 | 61912810 | 78,178 | 0.078178 | 7.18 | 0.785 | | | | | | | | | 0.51 |
| 5/6/2016 | Angel Trujillo | 61912810 | 61991222 | 78,412 | 0.078412 | 7.13 | 0.785 | | | | | | | | | 0.51 |
| 5/7/2016 | Angel Trujillo | 61991222 | 62072706 | 81,484 | 0.081484 | 7.11 | 0.785 | | | | | | | | | 0.53 |
| 5/8/2016 | Angel Trujillo | 62072706 | 62150261 | 77,555 | 0.077555 | 7.05 | 0.785 | | | | | | | | | 0.51 |
| 5/9/2016 | Angel Trujillo | 62150261 | 62227816 | 77,555 | 0.077555 | 7.08 | 0.785 | | | | | | | | | 0.51 |
| 5/10/2016 | Angel Trujillo | 62227816 | 62305770 | 77,954 | 0.077954 | 6.96 | 0.785 | <5.1 | <4.4 | | <0.010 | <0.030 | <0.010 | <0.00020 | <0.020 | 0.51 |
| 5/11/2016 | Angel Trujillo | 62305770 | 62384068 | 78,298 | 0.078298 | 7.05 | 0.785 | | | | | | | | | 0.51 |
| 5/12/2016 | Angel Trujillo | 62384068 | 62458920 | 74,852 | 0.074852 | 7.01 | 0.785 | | | | | | | | | 0.49 |
| 5/13/2016 | Angel Trujillo | 62458920 | 62537830 | 78,910 | 0.07891 | 7.13 | 0.785 | | | | | | | | | 0.52 |
| 5/14/2016 | Angel Trujillo | 62537830 | 62621880 | 84,050 | 0.08405 | 7.03 | 0.785 | | | | | | | | | 0.55 |
| 5/15/2016 | Angel Trujillo | 62621880 | 62699054 | 77,174 | 0.077174 | 7.05 | 0.785 | | | | | | | | | 0.51 |
| 5/16/2016 | Angel Trujillo | 62699054 | 62776228 | 77,174 | 0.077174 | 7.05 | 0.785 | | | | | | | | | 0.51 |
| 5/17/2016 | Angel Trujillo | 62776228 | 62851520 | 75,292 | 0.075292 | 7.49 | 0.785 | | | | | | | | | 0.49 |
| 5/18/2016 | Angel Trujillo | 62851520 | 62928746 | 77,226 | 0.077226 | 7.05 | 0.785 | | | | | | | | | 0.51 |
| 5/19/2016 | Angel Trujillo | 62928746 | 63006510 | 77,764 | 0.077764 | 7.10 | 0.785 | | | | | | | | | 0.51 |
| 5/20/2016 | Angel Trujillo | 63006510 | 63084574 | 78,064 | 0.078064 | 6.91 | 0.785 | | | | | | | | | 0.51 |
| 5/21/2016 | Angel Trujillo | 63084574 | 63177148 | 92,574 | 0.092574 | 7.22 | 0.785 | | | | | | | | | 0.61 |
| 5/22/2016 | Angel Trujillo | 63177148 | 63247742 | 70,594 | 0.070594 | 7.00 | 0.785 | | | | | | | | | 0.46 |
| 5/23/2016 | Angel Trujillo | 63247742 | 63318336 | 70,594 | 0.070594 | 7.15 | 0.785 | | | | | | | | | 0.46 |
| 5/24/2016 | Angel Trujillo | 63318336 | 63396035 | 77,699 | 0.077699 | 7.23 | 0.785 | | | | | | | | | 0.51 |
| 5/25/2016 | Angel Trujillo | 63396035 | 63480024 | 83,989 | 0.083989 | 7.11 | 0.785 | | | | | | | | | 0.55 |
| 5/26/2016 | Angel Trujillo | 63480024 | 63554444 | 74,420 | 0.07442 | 7.07 | 0.785 | | | | | | | | | 0.49 |
| 5/27/2016 | Angel Trujillo | 63554444 | 63632586 | 78,142 | 0.078142 | 7.12 | 0.785 | | | | | | | | | 0.51 |
| 5/28/2016 | Angel Trujillo | 63632586 | 63717776 | 85,190 | 0.08519 | 7.01 | 0.785 | | | | | | | | | 0.56 |
| 5/29/2016 | Angel Trujillo | 63717776 | 63793997 | 76,221 | 0.076221 | 7.10 | 0.785 | | | | | | | | | 0.50 |
| 5/30/2016 | Angel Trujillo | 63793997 | 63870218 | 76,221 | 0.076221 | 7.05 | 0.785 | | | | | | | | | 0.50 |
| 5/31/2016 | Angel Trujillo | 63870218 | 63943718 | 73,500 | 0.0735 | 7.10 | 0.785 | | | | | | | | | 0.48 |
| TOTAL | | | | 2,416,174 | 2.416174 | | | <5.1 | <4.4 | | <0.010 | <0.030 | <0.010 | <0.00020 | <0.020 | |
| | | | High: | 92,574 | | | | | | | | | | | High: | 0.61 |
| | | | Average: | 77,941 | | | | | | | | | | | Average: | 0.51 |

WW

6

| Accutest Labs | | | Honeywell | Chain Of Custody / Analysis Request | JC19960 | AESI Ref: | 42500.48434 |
|---|---|---|---|---|---|---|---|
| 2235 ROUTE 130 | | | | | | COC# | 087-WW-051016 |
| Dayton, NJ 8810 | | | | | | | |
| 732-329-0200 | | | Privileged & Confidential | Site Name: Hudson County | Phase: CS | Lab Proj # (SDG): | |
| Sampling Co.: | MACTEC | | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab ID | ACTD |
| Client Contact: (name, co., address) | | | Sampler: Frank Schroyer | | | Site ID | HudsonCo |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | | | PO # | | | Lab Job # | HWINJM32815 |
| Honeywell International | | | Analysis Turnaround Time (TAT): 3 | | | Authorized User: | Honeywell |
| 101 Columbia Road Morristown, NJ 07962 | | | Consultant CH2M | | | | |
| Preliminary Data To | | | | | | Text & Excel File Drive | Excel & Text File Order |
| Sample Receipt Acknowledgement To | | | | | | | |
| Hard Copy To | Helen Fahy (Honeywell) | | Full Report TAT: 28 Days | | | | |
| Invoice To: | Helen Fahy (Honeywell) | | | | | | |

Copyright AESI Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | | |
| Preservative | | | | | | | | | | | | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | | | | |
| 1 | 087-WW | | | 087-WWE-051016-A | 5/10/2016 | 14:20 | WW | WATER | REG | 5 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | | |
| 2 | 087-WW | | | 087-WWE-051016-B | 5/10/2016 | 14:25 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | | L19 |
| 3 | 087-WW | | | 087-WWI-051016 | 5/10/2016 | 14:35 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | | V37 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | C155 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

INITIAL ASESSMENT 28/16

LABEL VERIFICATION

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by | 6,96 S.U. @ 7.5°C | Company | AMEC Foster Wheeler | Received by | Accutest | Condition | Custody Seals Intact |
| Frank Schroyer | 5/10/16 | Date/Time | | | 5/10/16 1711 | Cooler Temp 2.1°C | |
| Relinquished by | Accutest | Company | | Received by | Company SC, S | Condition | Custody Seals Intact |
| | 5/10/16 1800 | Date/Time | | | Date/Time 5/10 1805 | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE

C5475 Accutest

SGS Accutest LabLink@911448 12:58 24-May-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051016-A | | |
| **Lab Sample ID:** | JC19960-1 | **Date Sampled:** | 05/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.1
4

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 785 | 10 | ug/l | 1 | 05/11/16 | 05/12/16 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 05/11/16 | 05/12/16 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 05/11/16 | 05/12/16 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 05/11/16 | 05/11/16 | JPM | SW846 7470A [1] | SW846 7470A [3] |
| Nickel | < 10 | 10 | ug/l | 1 | 05/11/16 | 05/12/16 | ND | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 05/11/16 | 05/12/16 | ND | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA39380
(2) Instrument QC Batch: MA39389
(3) Prep QC Batch: MP93649
(4) Prep QC Batch: MP93653

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@911448 12:58 24-May-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051016-A | | |
| **Lab Sample ID:** | JC19960-1 | **Date Sampled:** | 05/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |



**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended [a] | 6.6 | 4.0 | mg/l | 1 | 05/11/16 14:00 | SP | SM2540 D-11 |
| pH [b] | 6.94 | | su | 1 | 05/10/16 18:45 | AL | SM4500H+ B-11 |

(a) Reported sample aliquot obtained from filtration of 320 mL of sample. Sample did not meet method requirement of 2.5 mg of solids on the filter with this volume filtered.
(b) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@911448 12:58 24-May-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051016-A | | |
| **Lab Sample ID:** | JC19960-1A | **Date Sampled:** | 05/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.2
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 4.4 | 4.4 | mg/l | 1 | 05/11/16 18:30 | LS | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@911448 12:58 24-May-2016

# Report of Analysis



4.3 4

| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051016-B | | |
| **Lab Sample ID:** | JC19960-2 | **Date Sampled:** | 05/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/10/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | N254847.D | 1 | 05/11/16 | BM | n/a | n/a | VN10771 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 4.8 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 4.7 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.22 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 30.4 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.39 | 1.0 | 0.15 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.39 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 71.4 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.5 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 1.1 | 1.0 | 0.16 | ug/l | |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@911448 12:58 24-May-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051016-B | | |
| **Lab Sample ID:** | JC19960-2 | **Date Sampled:** | 05/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/10/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 69.5 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 100% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 105% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 99% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 105% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@911448 12:58 24-May-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-051016-B | | |
| **Lab Sample ID:** | JC19960-2 | **Date Sampled:** | 05/10/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 05/10/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 05/12/16 13:00 | JOO | EPA 1664A |

RL = Reporting Limit

# Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized based field obersvations and constructability review. | Submitted to Contractor only. |
| **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Contractor only. |
| **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Contractor only. |
| **DC 2014-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA 6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Contractor only. |
| **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to address the elimination of a drop structure, the elmination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Contractor only. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |
| **DC 2016-02-03** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Contractor only. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Contractor only. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Contractor only. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |

**SA-6 North/South Field Change Log - Month Ending June 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. |
| **DC 2016-05-31** | This DCB documents the vault sketch Drawing C-310 (Rev 5, 5/31/16) | Submitted to Contractor only. |
| **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | Submitted to Contractor only. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Contractor only. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 14 OF 25**

- **2016 Monthly Reports Part 3**

**8/8/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

August 8, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-07**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from July 1 – July 31, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: July 2016 SA-6/7 Combined Monthly Progress Report No. 2016-07

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP (electroni copy)

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-07

**Project SA-6 & 7 Remediation**

## July 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 07/11/16 | Sediment Remedy Long Term Monitoring Program Year 2 Implementation Report<br>Study Area 7<br>Jersey City, NJ | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/11/16 | Proposed Additional In-Situ Injection of Calcium Polysulfide for Treatment of Hexavalent Chromium Impacted Soils<br>Treatment Area 10-1<br>Study Area 6 (SA-6) North (Site 087)<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/14/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-05 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 07/19/16 | SA-6 South Declaration No. 2 | Terris, Pravlik & Millian |
| 07/19/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 7/19/16 | Special Master Conference Call | n/a |
| 07/28/16 | Discharge to Groundwater Permit-by-Rule Authorization Request<br>Study Area 6 North, Site 087<br>Jersey City, New Jersey | NJ Department of Environmental Protection |

## SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 07/03/16 | 07/10/16 | 07/17/16 | 07/24/16 | 07/31/16 |
| **Construction Management (AMEC)** | 9 | 10 | 11 | 8 | 9 |

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 07/03/16 | 07/10/16 | 07/17/16 | 07/24/16 | 07/31/16 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 2 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 37 | 37 | 37 | 37 | 36 |
| **Arecon/US Ecology Subcontractors** | 1 | 1 | 0 | 1 | 0 |
| **ESI** | 12 | 13 | 13 | 13 | 13 |
| **Lagan** | 1 | 1 | 2 | 1 | 1 |
| **Century** | 0 | 0 | 0 | 0 | 0 |
| **Evoqua** | 2 | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 1 | 0 | 1 | 2 | 0 |
| **Cornerstone** | 1 | 1 | 2 | 0 | 0 |
| **TOTAL STAFF** | **70** | **69** | **72** | **68** | **65** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Conducted S-3 Mass Removal Injection Event No. 30 in injection well 088-IW-02.
- Replaced the submersible pump in GWET extraction well PW-3 with spare.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Continued perimeter air monitoring activities on SA-6 North. On SA-6 South, all intrusive activities are complete. As only site grading and restoration activities remain, air monitoring will be completed using hand-held portable devices for nuisance dust.
- Prepared and submitted the NJDEP – Discharge to Groundwater Permit by Rule for the planned Treatment Area 10-1 second injection event.
- Collected July PVSC compliance sample from the Construction Water Treatment Plant (CWTP).

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on July 7, 2016.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 07/03/16 | 07/10/16 | 07/17/16 | 07/24/16 | 07/31/16 |
| Avg. Gallons Treated & Discharged (per day) | 78,968 | 77,153 | 76,395 | 77,536 | 76,878 |
| Average Flow (gpm) for Operating Period | 56 | 56 | 55 | 56 | 56 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 5,100 | 5,436 | 3,360 | 3,294 | 2,761 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Began backfilling as part of site restoration in the SA-6 South Development Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 0 | 0 | 0 |
| **Entact/FCI** | Roll-off | Kearny, NJ | Clean Earth | Soil >1000ppm Cr | 3 | 18.0 | 54.2 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Backfill in Progress** | Historic Fill Soils – SA-6 South Development Area |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 07/03/16 | 07/10/16 | 07/17/16 | 07/24/16 | 07/31/16 |
| Natures Choice Horizon C | 0 | 0 | 0 | 9,523.88 | 0 |
| Cedar Hill Horizon B | 125.95 | 0 | 0 | 45.49 | 111.16 |
| Tilcon Mount Hope I-8 | 0 | 0 | 982.78 | 1994.48 | 533.16 |
| Natures Choice Topsoil | 0 | 0 | 0 | 0 | 0 |
| Tilcon 3/8” Stone | 51.11 | 127.94 | 0 | 0 | 77.08 |
| Weldon Screenings | 182.7 | 0 | 0 | 0 | 0 |

- Overburden historic fill soils with hexavalent chromium concentrations confirmed to be < 20 mg/kg soils were transferred and placed as backfill the SA-6 South development area.
- Screened Celgene material was placed as protective cover soil in the SA-6 North open space area. Approximately 6,848 cubic yards was placed as protective cover soil during the reporting period.
- Continued to screen Celgene material for use as protective cover soils on the SA-6 North Open Space Area.
- Completed the frequency sampling of stockpiled Horizon C soils at the Nature's Choice facility remaining to be imported for use at SA-6 North. Results provided in Attachment 6.

## D. SURCHARGE OPERATIONS

- All surcharging activities are completed.

## E. SHEET PILE OPERATIONS

- Continued cutting hydraulic barrier sheets to final elevation in SA-6 North Open Space Area.

## F. CAPPING OPERATIONS

- Completed importing and placing Horizon B soils atop Horizon C soils on SA-6 South Open Space Area Completed hydro-seeding of western portion of the SA-6 South Open Space. Approximately 2.1 acres of hydro-seeding was completed.
- Continued placement of Structural Fill Material in the future utility corridors crossing the SA-6 South open space area.
- Began placement of GDL cover soils and demarcation tape to include associated compaction testing on the SA-6 North Open Space Area.
- Began placement structural fill, root barrier, and Horizon C to include associated compaction testing on the SA-6 North Open Space Area.
- Continued SA-6 North geomembrane liner subgrade grading activities within the Open Space Area.
- Continued installation of geosynthetic components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- A total of 288,543 sq. ft. of geomembrane liner (65% of the total cap area) was deployed during the reporting period.
- Completed spark testing on ten boot welds during the reporting period. Please see the email summary in Attachment 11 for clarifications of the spark test reporting.
- Continued cutting hydraulic barrier sheets and finishing the SCB wall to final elevation in SA-6 North Open Space Area.

- Continued installation of Gas Vent Pipe within the SA-6 North Open Space Area.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Continue importing and placement of Horizon A Topsoil on the SA-6 South Open Space Area.
- Continue development area regrading on SA6 South.
- Continue hydro-seeding of SA-6 South Open Space Area.
- Continue screening of Celgene soils for protective cover soils.
- Continue cutting SA-6 North Hydraulic Barrier Wall and Soil-Cement Bentonite Wall to geomembrane liner grade.

- Continue preparation of the SA-6 North subgrade for geomembrane liner installation.
- Continue installation of geosynthetic components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, and geocomposite drainage layer.
- Continue placement of GDL cover soils within the SA-6 North Open Space Area.
- Continue placement structural fill, root barrier, and Horizon C soils to include associated compaction testing on the SA-6 North Open Space Area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Continue installation CGWES Components.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 31 in well 088-IW-03.
- Conduct second injection event for Treatment Area 10-1.

## ATTACHMENTS:

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data
7. Perimeter Pools Update
8. Groundwater Quality Data
    - Table 1: Summary of Groundwater Quality Data
    - Table 2: Second Quarter 2016
    - Graphs: Trichloroethene/ Chloroform/ Hexavalent Chromium in GWET Wells
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update
    - SA-6 Cap Subgrade Progress Maps
    - Repair Log
    - Non-conformance Log
    - Subgrade Approval Form
    - QA Photo Log
    - Daily QA Reports (Langan)
    - August 5, 2016 Honeywell e-mail: 080116 June 2016 SA-6 and SA-7 Combined Progress Report 21319 (pertaining to boot testing information provided in the June 2016 Combined Progress Report)
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log
    - SA-6 North & South Design Change Tracking Log
    - Design Change Bulleting 2016-07-12: SA-6 North Clarify location of Sand Bentonite Plug

## Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule

| ID | Task Name | Duration |
|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** |
| **2** | **Remedial Action Work Plan** | **33 days** |
| **5** | **Remedial Action Design** | **1522 days** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** |
| 19 | Develop Site Relocation Master Plan | 38 days |
| 20 | Submit Site Relocation Master Plan | 0 days |
| 21 | JC Construction of New Facilities | 1309 days |
| 22 | Relocation Contractor Procurement | 392 days |
| 23 | JCIA and JCDPW Relocation | 949 days |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days |
| 24a | Demolition of JCIA Structures | 146 days |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** |
| **26** | **Remedial Action Work Plan** | **187 days** |
| **32** | **Remedial Action Design** | **1161 days** |
| **57** | **SA-6 South Relocation** | **616 days** |
| 58 | New GWTP Construction Completion | 502 days |
| 59 | Demolition of 80 Kellogg | 857 days |
| **60** | **SA-6 North/South Field Implementation** | **894 days** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** |
| 61a | Mobilization | 87 days |
| **62** | **Surcharge Install/Instrumentation** | **706 days** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days |
| **63** | **Barrier Wall Install** | **569 days** |
| 63a | SA 6N Installation of Barrier Wall | 159 days |
| 63b | SA 6S Installation of Barrier Wall | 210 days |
| **64** | **Excavation** | **507 days** |
| 64a | SA 6N Excavation | 218 days |
| 64b | SA 6S Excavation | 295 days |
| **65** | **Backfill** | **558 days** |
| 65a | SA 6N Backfill | 283 days |
| 65b | SA 6S Backfill | 384 days |
| **66** | **Capping and Cover Soil Placement** | **426 days** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days |
| **67** | **Restoration** | **234 days** |
| 67a | Restoration | 234 days |
| **68** | **Demobilization** | **22 days** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | |
| **69** | **SA-6 North Project Closeout** | **311 days** |
| **75** | **SA-6 South Project Closeout** | **311 days** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/2/2016

Task  Milestone  Summary  Critical

Note: Current field implementation schedule shows capping complete in September 2016 and restoration in October 2016.

## Attachment 2: Site Photographs




**Site Photograph 1:** Compacting clean imported stone in utility corridor SA6 North open space area.



**Site Photograph 2:** Contractor deploying liner panel on the SA-6 North open space area.




**Site Photograph 3:** Contractor grading protective cover soils on the SA-6 North open space area.




**Site Photograph 4:** Contractor placing geocomposite drainage layer panel SA-6 North open space area.




**Site Photograph 5:** Contractor screens clean protective cover soils.




**Site Photograph 6:** Geosynthetic Cap construction activities SA-6 North open space area.

## Attachment 3: Excavation and Backfill Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of August 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-07
Attachment 3: Excavation and Backfill (Progression Chart)

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties

Hackensack River

Former Roosevelt Drive-In Site
(Remediation Complete)

Route 440

Kellogg Street Properties

Kellogg Street

Added Excavation Area
(complete)

## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

## Attachment 5: Weekly Dewatering Discharge to PVSC

**STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)**

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 05/31/16 | 11:00 | 14:30 | 3:30 | 43,130.78 | 43,178.93 | 48,150 | 43,178,480 | |
| 06/01/16 | 6:30 | 13:30 | 7:00 | 43,178.93 | 43,268.97 | 90,040 | 43,268,520 | |
| 06/06/16 | 7:30 | 13:30 | 6:00 | 43,268.97 | 43,338.94 | 69,970 | 43,338,490 | |
| 06/08/16 | 7:30 | 12:00 | 4:30 | 43,338.94 | 43,402.10 | 63,160 | 43,401,650 | PVSC Compliance Sample Collected |
| 06/13/16 | 9:00 | 13:00 | 4:00 | 43,402.10 | 43,464.75 | 62,650 | 43,464,300 | |
| 06/21/16 | 8:00 | 14:00 | 6:00 | 43,464.75 | 43,543.94 | 79,190 | 43,543,490 | |
| 06/24/16 | 9:00 | 14:00 | 5:00 | 43,543.94 | 43,596.37 | 52,430 | 43,595,920 | |
| 07/07/16 | 7:30 | 12:00 | 4:30 | 43,596.37 | 43,642.93 | 46,560 | 43,642,480 | PVSC Compliance Sample Collected |
| 07/15/16 | 10:00 | 14:00 | 4:00 | 43,642.93 | 43,692.98 | 50,050 | 43,692,530 | |
| 07/26/16 | 9:00 | 14:00 | 5:00 | 43,692.98 | 43,794.27 | 101,290 | 43,793,820 | |
| 07/27/16 | 7:00 | 15:00 | 8:00 | 43,794.27 | 43,826.36 | 32,090 | 43,825,910 | |
| 07/28/16 | 9:00 | 15:00 | 6:00 | 43,826.36 | 43,860.98 | 34,620 | 43,860,530 | |
| 08/01/16 | 9:00 | 15:00 | 6:00 | 43,860.98 | 43,896.38 | 35,400 | 43,895,930 | |

Notes: Previous information is truncated. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data

Nature's Choice: Horizon C
Average

| Vendor | Source Location | Sample ID | Hex Chrome mg/kg |
|---|---|---|---|
| Nature's Choice | South Brunswick, NJ | NC-HC1-002 Submittal 118A | 0.67 |
| Nature's Choice | South Brunswick, NJ | NC-003 Submittal 121 | 0.97 |
| Nature's Choice | South Brunswick, NJ | NC-HC-004 Solid | 1.1 |
| Nature's Choice | South Brunswick, NJ | NC-HC-004A Solid | 0.96 |
| Nature's Choice | South Brunswick, NJ | NC-HC-004B Solid | 1 |
| Nature's Choice | South Brunswick, NJ | NC-HC-004C Solid | 1.2 |
| Nature's Choice | South Brunswick, NJ | NC-HC-005 Solid | 0.97 |
| Nature's Choice | South Brunswick, NJ | NC-HC-006 Solid | 1 |
| Nature's Choice | South Brunswick, NJ | NC-HC1 Solid | 1.6 |
| Nature's Choice | South Brunswick, NJ | NC-HC2 Solid | 1.4 |
| Nature's Choice | South Brunswick, NJ | NC-HC3 Solid | 1.2 |
| Nature's Choice | South Brunswick, NJ | NC-HC4 Solid | 1 |
| Nature's Choice | South Brunswick, NJ | NC-HC5 Solid | 1.3 |
| Nature's Choice | South Brunswick, NJ | NC-HC6 Solid | 1.2 |
| Nature's Choice | South Brunswick, NJ | NC-HC7 Solid | 1 |
| Nature's Choice | South Brunswick, NJ | NC-HC8 Solid | 1.7 |
| Nature's Choice | South Brunswick, NJ | NC-010 | 0.78 |
| Nature's Choice | South Brunswick, NJ | NC-011 | 1 |
| Nature's Choice | South Brunswick, NJ | NC-012 | 1.5 |
| Nature's Choice | South Brunswick, NJ | NC-013 | 0.63 |
| Nature's Choice | South Brunswick, NJ | NC-014 | 0.43 |
| Nature's Choice | South Brunswick, NJ | NC-015 | 1.1 |

Nature's Choice: Horizon C
Average

| Vendor | Source Location | Sample ID | Hex Chrome mg/kg |
|---|---|---|---|
| Nature's Choice | South Brunswick, NJ | NC-016 | 1.4 |
| Nature's Choice | South Brunswick, NJ | NC-017 | 1 |
| Nature's Choice | South Brunswick, NJ | NC-018 | 1.1 |
| Nature's Choice | South Brunswick, NJ | NC-019 | 1.2 |
| Nature's Choice | South Brunswick, NJ | NC-020 | 0.87 |
| Nature's Choice | South Brunswick, NJ | NC-021 | 0.55 |
| Nature's Choice | South Brunswick, NJ | NC-022-CLAY | 1.5 |
| Nature's Choice | South Brunswick, NJ | NC-023-HORC* | 1.4 |
| Nature's Choice | South Brunswick, NJ | NC-024-HORC* | 0.86 |
| Nature's Choice | South Brunswick, NJ | NC-HC-007-CR6* | 1.30 |
| Nature's Choice | South Brunswick, NJ | NC-HC-008* | 0.63 |
| Nature's Choice | South Brunswick, NJ | NC-HC-009* | 1.50 |
| Nature's Choice | South Brunswick, NJ | NC-HC-010* | 0.71 |
| Nature's Choice | South Brunswick, NJ | NC-HC-011* | 0.61 |

SUMMARY OF STATISTICS

| | |
|---|---|
| Total Number of Observations | 36 |
| Arithmetic Mean | 1.065 |
| Minimum | 0.43 |
| Maximum | 1.7 |
| Standard Deviation | 0.318 |
| 95% UCL | 1.17 |

*Represents a 10 point composite sample (per DC 2016-3-21).

## Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL E1 ELEV.+8.0 325'
POOL E2 ELEV.+8 270'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'

N4 N3 N2 N1 E1 E2 S4 S3 S2 S1

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1 117-MW-A99 117-MW-A85 117-MW-A89
115-PZ-6 115-PZ-5 115-PZ-4
073-MW-BB11 073-MW-Y10 134-MW-V09 134-MW-Q08 140-MW-06 140-MW-07 125-MW-L03
MW-124-103L MW-124-102D MW-124-103D MW-124-102T

NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6

W6-SO W1-SO W5-SO W3-SO E5-SO E4-SO E3-SO E2-SO E1-SO

S-C-B BARRIER (TYP.)

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

KELLOGG STREET

STATE ROUTE 139

STA. N1+10 STA. N6+35 STA. N6+80 STA. N10+23 STA. N10+73 STA. N13+10 STA. N13+60 STA. N20+25 STA. E0+50 STA. F3+75 STA. F4+50 STA. E7+25 STA. S22+05 STA. S17+86 STA. S17+50 STA. S11+10 STA. S10+60 STA. S4+58 STA. S3+86 STA. S0+50

**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-5 | FS-6 | FS-7 | FS-13 |
| Date | | | | | | | | | | | | | |
| 8/14/2015 | 1.8 | 4.9 | 5.4 | 3.8 | 4.1 | | 1.7 | 1.8 | 6.1 | 4.6 | 4.5 | 3.9 | 4.0 |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | 4.5 | 4.5 | 3.6 | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | 4.4 | 4.3 | 3.5 | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | 4.4 | 4.4 | 3.5 | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | 4.7 | 4.6 | 4.0 | 4.0 |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | 4.7 | 4.6 | 3.9 | 3.8 |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | 4.6 | 4.6 | 3.7 | 3.4 |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | 4.5 | 5.0 | 3.8 | 3.5 |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | 3.5 | 3.6 | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | 5.2 | | | 4.6 |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | 6.0 | | | 5.6 |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | 6.5 | | | 6.2 |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | 6.0 | | | 5.7 |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | 5.6 | | | 5.0 |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | 2.7 | | | 3.6 |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | 2.1 | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | 1.8 | | | |
| 5/2/2016 | 3.1 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | 1.6 | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | |
| 6/1/2016 | 2.7 | 5.2 | 5.5 | 2.5 | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/16/2016 | 2.7 | 5.2 | 5.6 | | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/28/2016 | 3.2 | 5.3 | 5.5 | 2.4 | 3.2 | 2.4 | 3.1 | 3.2 | 1.7 | | | | |
| 7/15/2016 | 3.2 | 5.3 | 5.6 | 2.5 | 3.3 | 2.4 | 3.1 | 3.2 | 1.8 | | | | |
| 7/27/2016 | 3.1 | 5.3 | 5.4 | 2.6 | 3.2 | 2.3 | 3.1 | 3.2 | 2.0 | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

## Attachment 8: Groundwater Quality Data

- Table 1: Summary of Groundwater Quality Data
- Table 2: Second Quarter 2016
- Trichloroethene in GWET Wells
- Chloroform in GWET Wells
- Hexavalent Chromium in GWET Wells

**Table 1: Summary of Groundwater Quality Data**
*(Attachment 8: Groundwater Quality Data)*

**Table 1**
Summary of Groundwater Quality Data from GWET Wells

| Parameter | 23-Sep-15 | | | 4-Dec-15 | | | 16-Mar-16 | | | 30-Jun-16 | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-2 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-3 (ug/L) | 115-MW-215BR (ug/L) | PW-1 (ug/L) | PW-3 (ug/L) | 115-MW-215BR (ug/L) |
| Benzene | 3.8 | 3.6 | ND | 3.2 | 2.2 | ND | 2.7 | 24.9 | ND | 2.7 | 27.3 | ND |
| Carbon Tetrachloride | 6.7 | 4.3 | 2.9 | 3.7 | 2.9 | 2.5 | 4.5 | 18.9 | 2.7 | 4.1 | 14.6 | 2.1 |
| Chloroform | 27.4 | 6.8 | 0.27 | 24.4 | 4.8 | ND | 21.0 | 121 | 0.23 | 24.2 | 111 | 0.25 |
| 1,1-Dichloroethene | 0.63 | ND | ND | 0.43 | ND | ND | 0.44 | 0.32 | ND | 0.55 | 0.34 | ND |
| cis-1,2-Dichloroethene | 129 | 8.7 | 0.24 | 104 | 5.3 | ND | 104 | 48.9 | ND | 125 | 59.9 | ND |
| trans-1,2-Dichloroethene | 3.9 | ND | ND | 3.2 | ND | ND | 2.9 | 0.37 | ND | 3.5 | 0.44 | ND |
| Toluene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 105.0 | 37.3 | ND | 86.8 | 24.5 | ND | 84.3 | 358 | ND | 86.8 | 347 | ND |
| 1,1-Dichloroethane | 0.64 | ND | ND | 0.51 | ND | ND | 0.49 | ND | ND | 0.65 | 0.25 | ND |
| Methylene chloride | 0.71 | ND | ND | ND | ND | ND | ND | 4.0 | ND | 0.75 | 3.7 | ND |
| Vinyl chloride | 17.4 | 2.0 | ND | 11.3 | 1.4 | ND | 14.0 | 14.2 | ND | 17.0 | 15.2 | ND |
| 1,2-Dichlorobenzene | 0.61 | ND | ND | 0.55 | ND | ND | 0.54 | ND | ND | 0.54 | 0.19 | ND |
| Chlorobenzene | 0.35 | ND | ND | 0.29 | ND | ND | 0.31 | ND | ND | 0.35 | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | 0.28 | ND |
| Xylenes (total) | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | 0.44 | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 33,900 | 7,300 | 14,700 | 34,200 | 5,900 | 16,700 | 29,600 | 91,700 | 15,200 | 31,300 | 68,800 | 14,400 |
| Total Chromium | 33,800 | 8,480 | 14,000 | 34,200 | 8,430 | 16,600 | 30,400 | 84,300 | 14,800 | 31,700 | 37,100 | 12,900 |

NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.

**Table 2: Second Quarter 2016**
*(Attachment 8: Groundwater Quality Data)*


**TABLE 2**
**Second Quarter 2016**


Honeywell

| Wells<br>Date: June 22, 2016 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments<br>*GW Elevations are not corrected for tidal influence* |
|---|---|---|---|---|
| 087-MW-25D | NA | 8.22 | NA | casing extended |
| 087-MW-25T | NA | 8.10 | NA | casing extended |
| 087-MW-35 | 18.29 | NA | NA | Well abandoned |
| 087-OBS-1D | 15.13 | 12.88 | 2.25 | |
| 087-OBS-1L | 15.27 | 13.54 | 1.73 | |
| 087-OBS-1T | 15.23 | 12.67 | 2.56 | |
| 087-PW-2 | 13.02 | 11.46 | 1.56 | not pumping - obs well only |
| 087-PW-3* | 13.00 | 11.24 | 1.76 | not pumping - TP down for service |
| 087-OBS-7* | 13.00 | 11.76 | 1.24 | |
| 087-MW-08 | 12.98 | 11.40 | 1.58 | |
| 087-OBS-3L | 12.88 | 12.19 | 0.69 | |
| 087-MW-13 | 12.93 | 11.95 | 0.98 | |
| 087-OBS-5D | 12.72 | 11.71 | 1.01 | |
| 087-OBS-5T | 12.62 | 11.06 | 1.56 | |
| 087-PW-1 | 12.66 | 11.28 | 1.38 | not pumping - TP down for service |
| 087-MW-34 | 12.73 | 11.21 | 1.52 | |
| 087-OBS-2D | 12.68 | 11.31 | 1.37 | |
| SA6-MW-AA1D | 19.36 | 17.93 | 1.43 | |
| SA6-MW-AA1T | 15.31 | 13.97 | 1.34 | |
| SA6-MW-5BR-1 | 17.06 | 14.59 | 2.47 | |
| 087-OBS-4T | 11.60 | 10.05 | 1.55 | |
| 087-MW-O29D | 10.32 | 8.81 | 1.51 | |
| 087-MW-O29T | 9.98 | NA | N/A | Well abandoned |
| 087-MW-03 | 13.77 | NA | N/A | Well abandoned |
| 087-MW-02 | 12.57 | NA | N/A | Well abandoned |
| 115-MW-203BR | 8.70 | NA | N/A | Well not accessible |
| 073-MW-1 | 25.25 | 25.70 | -0.45 | retro-fitted as top-of-rock well |
| 073-MW-10BR-1 | 6.67 | NA | N/A | Flute does not purge |
| 115-MW-215BR* | 8.82 | 11.71 | -2.89 | |


* Reference point elevation to be confirmed.

**Graphs: Trichloroethene/ Chloroform/ Hexavalent Chromium in GWET Wells**
*(Attachment 8: Groundwater Quality Data)*




Note:
Well 115-MW-203BR has been replaced with well 115-MW-215BR




Notes:
Well 115-MW-203BR was replaced with 115-MW-215BR on 3/3/14.
Well 087-PW-2 was replaced with well 087-PW-3 on 12/2215.

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)


## Attachment 10: Sheet Pile Update

(not included in this reporting period)

## Attachment 11: Capping Update

- SA-6 Cap Subgrade Progress Maps
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports (Langan)
- August 5, 2016 Honeywell e-mail: 080116 June 2016 SA-6 and SA-7 Combined Progress Report 21319 (pertaining to boot testing information provided in the June 2016 Combined Progress Report)


**SA-6 Cap Subgrade Progress Maps**
*(Attachment 11: Capping Update)*




ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP SUBGRADE PROGRESS MAP
07/29/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LEGEND

- HORIZON B PLACED AND READY FOR TOPSOIL
- HORIZON C PLACED AND READY FOR TOPSOIL
- TOPSOIL PLACED
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
06/30/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**Repair Log**
*(Attachment 11:  Capping Update)*

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | PB | 1/2 | P-1 | 35' N OF SEOS & 8'W | P | 3 | x | 11 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 2 | BO | 3/5 | | 2' N OF S EOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 3 | SJ | 3/4/5 | | 69' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 4 | CF | 4/6 | | 5' S OF NEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 5 | CF | 4/6 | | 77' N OF SEOS | P | 5 | x | 12 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 6 | SJ | 4/5/6 | | 69' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 7 | PB | 5/6 | | 15' N OF S EOS (PB 6") | P | 3 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 8 | WR | 6/7 | P-6 | 63' N OF S EOS & 5'W | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 9 | BO | 6/7 | | 66' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 10 | SI | 6/7 | P-6 | 80' N OF SEOS & 5'W | P | 3 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 11 | DS-2 | 6/7 | | 16' N OF SEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 12 | WR | 7/9 | | 41' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 13 | CF | 7/9 | P-9 | 45' N OF SEOS & 10'E | P | 6 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 14 | DS-1 | 1/2 | | 15' N OF SEOS | P | 2 | x | 7 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 15 | DSX-1 | | P1/R15 | 34'N OF SEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 16 | CF | | P9 | BETWEEN R12 & R13 | B | | x | | 60 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 17 | WR | 7/9 | | 71' N OF S EOS | B | 3 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 18 | CF | | P9 | BETWEEN R17 & R19 | B | | x | | 168 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 19 | CF | 7/9 | P9 | 59' N OF SEOS & 12'E | P | 4 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 20 | CF | | P6 | BETWEEN R22 & R9 | B | | x | | 36 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 21 | CF | | P6 | BETWEEN R22 & R8 | B | | x | | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 22 | CF | 6/7 | P6 | 68' N OF SEOS & 6'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 23 | SJ | 7/8/9 | | 103' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 24 | CF | 8/10 | | 11' S OF NEOS | P | 2 | x | 20 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 25 | SJ | 8/9/10 | | 103' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 26 | DO | 10/11 | P10 | 27' N OF SEOS 4'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 27 | CF | 10/11 | P10 | BETWEEN R35 & R28 | B | | x | | 156 | 6/26/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 28 | CF | 10/11 | P10 | 64'N OF SEOS & 15' W | P | 4 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 29 | PB | 10/11 | P10 | 93' S OF NEOS 4' E (48" MH ) | P | 6 | x | 10 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 30 | CF | | P10 | BETWEEN R29 & R31 | B | | x | | 240 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 31 | CF | 10/11 | P10 | 68' S OF NEOS & 2'W | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 32 | CF | 10/11 | P10 | 78' N OF SEOS & 7'W | P | 2 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 33 | CF | | P10 | BETWEEN R32 & R34 | B | | x | | 60 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 34 | CF | 10/11 | | 78' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 35 | CF | 10/11 | | 69' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 36 | CF | 10/11 | | 49' N OF SEOS | P | 5 | x | 15 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 37 | CF | | P11 | 50' N OF SEOS & 3'E | B | | x | | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 38 | PB | 10/11 | 11 | 83' N OF SEOS & 3' E (8" PIPE ) | P | 4 | x | 5 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 39 | DS-3 | 10/11 | | 25' S OF NEOS | P | 2 | x | 6 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 40 | AO | 10/11 | | 3' S OF NEOS | P | 12 | x | 12 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 41 | SJ | 11/12/13 | | 22' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 42 | SJ | 12/13/14 | | 24' S OF NEOS | P | 2 | x | 6 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 43 | DO | 4/6 | P4 | 6' S OF NEOS & 4'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 44 | B O | 13/14 | | 65' N OF SEOS | P | 2 | x | 5 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 45 | BO | 13/14 | | 79' N OF SEOS | P | 2 | x | 5 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 46 | BO | 13/14 | | 163' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 47 | CF | 13/14 | | BETWEEN R46 & 42 | B | | x | | 12 | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 48 | SJ | 12/14/14A | | 4' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 49 | SJ | 14A/14/15 | | 4' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 50 | SJ | 14/15/16 | | 78' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 51 | BO | 14/16 | | 2'N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 52 | SJ | 15/16/17 | | 78' N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 53 | DS-4 | 15/17 | | 87' N OF SEOS | P | 2 | x | 6 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 54 | CF | 17/18 | | 53' S OF NEOS | P | 3 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 55 | CF | | P17 | 56' S OF NEOS | B | | x | | 24 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 56 | CF | 17/18 | P18 | 74' S OF NEOS | P | 3 | x | 9 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 57 | CF | 17/18 | | 83' S OF NEOS | P | 2 | x | 4 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 58 | CF | 17/18 | P18 | 84' S OF NEOS 4' E OF R-57 | B | | x | | 120 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 59 | BO | 17/18 | | 153' S OF NEOS | P | 2 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 60 | CF | | P18 | BETWEEN R-59 & R-62 | B | | x | | 140 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 61 | BO | 17/18 | | 182' S OF NEOS | P | 2 | x | 6 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 62 | CF | | P18 | 29' N OF SEOS | P | 2 | x | 13 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 63 | BO | 18/19 | | 24' N OF SEOS | P | 2 | x | 6 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 64 | CF | 18/19 | | BETWEEN R-63 & R-65 | B | | x | | 12 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 65 | CF | 18/19 | P19 | 30' N OF SEOS & 3'E | P | 2 | x | 9 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 66 | CF | | P19 | BETWEEN R-65 & R-67 | B | | x | | 108 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 67 | CF | 19/20 | P19 | 42' N OF SEOS & 5'W | P | 3 | x | 7 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 68 | CF | 18/19 | | 46' N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 69 | CF | | P19 | BETWEEN R-68 & R-70 | B | | x | | 72 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 70 | DO | 18/19 | P19 | 49' N OF SEOS & 7'E | P | 3 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 71 | BO | 18/19 | | 113' N OF SEOS | P | 3 | x | 4 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 72 | BO | 18/19 | | 130' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 73 | DSX-2 | 10/11 | P10/R30 | 106' N OF SEOS & 6'W | P | 2 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 74 | DS-5 | 19/20 | | 16' N OF SEOS | P | 2 | x | 5 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 75 | CF | 19/20 | | 164' N OF SEOS | P | 2 | x | 20 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 76 | AO | 19/R76/20 | | 180' N OF SEOS | P | 1 | x | 21 | | 6/27/16 | SU | EXT-74 | Air Pressure | Pass | 6/27/16 |
| 77 | SJ | 20/21/22 | | 99' N OF SEOS | P | 2 | x | 2 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 78 | CF | 20/21 | | 122' N OF SEOS | P | 4 | x | 4 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 79 | CF | | P21 | BETWEEN R-78 & R-80 | B | | x | | 156 | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 80 | CF | 21/23 | P21 | 128' N OF SEOS & 11' W | P | 1 | x | 1 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 81 | PB | 20/21 | P21 | 171' N OF SEOS & 3' E (PB 4") | P | 3 | x | 5 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 82 | BO | 22/23 | | 54' N OF SEOS | P | 2 | x | 4 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 83 | SJ | 21/22/23 | | 99' N OF SEOS | P | 6 | x | 14 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 84 | SJ | 23/24/25 | | 17' N OF SEOS | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 85 | BO | 23/24 | | 40' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 86 | CF | 23/24 | P23 | BETWEEN R-85 & 87 | B | | x | | 72 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 87 | CF | 23/24 | P23 | 48' N OF SEOS & 11' W | P | 2 | x | 9 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 88 | CF | 22/23 | P23 | 51' N OF SEOS & 8' E | P | 3 | x | 5 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 89 | CF | 23/24 | | 74' N OF SEOS | P | 2 | x | 6 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 90 | CF | 23/24 | | 79' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 91 | DS-6 | 23/24 | | 105' N OF SEOS | P | 2 | x | 6 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 92 | SJ | 24/25/26 | | 17' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 93 | CF | 24/26 | | 140' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 94 | CF | 24/26 | P26 | BETWEEN R-93 & 95 | B | | x | | 72 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 95 | CF | 24/26 | P26 | 139' N OF SEOS & 8' E | P | 2 | x | 4 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 96 | CF | 24/26 | P26 | 120' N OF SEOS & 2' E | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 97 | CF | 24/26 | P26 | 126' N OF SEOS & 6'E FROM R-96 | B | | x | | 132 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 98 | SI | 24/26 | P26 | 150' N OF SEOS & 8' E | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 99 | DO | 26/27 | P26 | 149' N OF SEOS & 10' W | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 100 | BO | 26/27 | | 26' N OF SEOS | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 101 | CF | 26/27 | | 55' N OF SEOS | P | 3 | x | 8 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 102 | PB | 26/27 | P27 | 124' N OF SEOS & 3' E (PB 8") | P | 4 | x | 5 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 103 | CF | 26/27 | P26 | 170' N OF SEOS & 12' E | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 104 | AO | 19/20 | | 196' N OF SEOS | P | 5 | x | 23 | | 6/30/16 | BS | W-4131 | Air Pressure | Pass | 6/30/16 |
| 105 | AO | 18/19 | | 196' N OF SEOS | P | 5 | x | 23 | | 6/30/16 | BS | W-4131 | Air Pressure | Pass | 6/30/16 |
| 106 | AO | 17/18 | | 196' N OF SEOS | P | 5 | x | 8 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 107 | CF | 19/20/R26 | | 194' N OF SEOS | P | 3 | x | 5 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 108 | CF | 18/19 | | 194' N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 109 | CF | 17/18 | | 194' N OF SEOS & 4' E | P | 2 | x | 2 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 110 | CF | 19/20 | P19 | 126' N OF SEOS & 8' W | P | 2 | x | 4 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 111 | CF | 19/20 | P19 | BETWEEN R-110 & R-112 | B | | x | | 120 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 112 | CF | 19/20 | P19 | 136' N OF SEOS & 2' W | P | 2 | x | 2 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 113 | DS-7 | 13/14 | | 91' N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 114 | DS-8 | R-105 | P18 | 195' N OF SEOS & 9' W | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 115 | DSX-3 | R-179 | P21 | BETWEEN R-78 & R-80 | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 116 | DS-9 | 18/19 | | 101' N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 117 | CF | 26/27 | | 180' N OF SEOS | P | 6 | x | 11 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 118 | CF | 26/27 | P-27 | 179' N OF SEOS 2'E | P | 4 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 119 | CF | 26/27 | P-27 | 179' N OF SEOS 4'E | P | 5 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 120 | CF | 26/27 | P-27 | 179' N OF SEOS 6'E | P | 3 | x | 7 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 121 | CF | 27/28 | P-27 | 179' N OF SEOS & 14'W | P | 3 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 122 | CF | 27/28 | P-27 | BETWEEN R-121 & R-123 | B | | x | | 108 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 123 | CF | 27/28 | | 173'N OF SEOS | P | 3 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 124 | BO | 27/28 | | 177' N OF SEOS | P | 2 | x | 5 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 125 | SJ | P27/P28 | | 129' N OF SEOS | P | 2 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 126 | SJ | P27/P28 | P28 | 129'N OF SEOS & 3' E | P | 2 | x | 2 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 127 | CF | 26/27 | | 208'N OF SEOS | P | 5 | x | 8 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 128 | CF | 26/27 | P-26 | 216'N OF SEOS FROM R-127 | B | | x | | 108 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 129 | CF | 27/129 | P-26 | 205'N OF SEOS FROM R-127 | B | | x | | 108 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 130 | AO | 27/28 | | 132'N OF SEOS | P | 6 | x | 18 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 131 | AO | 27/28 | | 200'N OF SEOS | P | 5 | x | 20 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 132 | CF | 27/28 | | 133'N OF SEOS | P | 5 | x | 8 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 133 | DS-10 | 27/28 | | 155'N OF SEOS | P | 2 | x | 5 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 134 | CF | 27/28 | | BETWEEN R133 & R154 | B | | x | | 72 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 135 | CF | 19/20 | P20 | 120' N OF SEOS & 6'E | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 136 | CF | 19/20 | P-20 | BETWEEN R-135 & R-137 | B | | x | | 60 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 137 | CF | 19/20 | P-20 | 105'N OF SEOS & 3'E | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 138 | BO | 29/31 | | 11'N OF SEOS | P | 2 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 139 | CF | 29/31 | P-29 | BETWEEN R-140 & R-141 | B | | x | | 108 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 140 | CF | 29/31 | P-29 | 54'N OFSEOS 10'W | P | 1 | x | 1 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 141 | CF | 29/31 | P-29 | 54' N OF SEOS | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 142 | SJ | 29/30/31 | | 159' N OF SEOS | P | 3 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 143 | BO | 29/30 | | 169' N OF SEOS | P | 2 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 144 | CF | 29/30 | P-29 | BETWEEN R-145 & R-146 | B | | x | | 96 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 145 | CF | 29/30 | P29 | 175' N OF SEOS & 10'W | P | 3 | x | 7 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 146 | CF | 29/30 | P-29 | 170' N OF SEOS & 2'W | P | 2 | x | 2 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 147 | DSX-4 | R-148/P32 | | 96'N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 148 | DS-11 | 31/32 | | 96' N OF SEOS | P | 4 | x | 7 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 149 | CF | 31/32 | | 65' N OF SEOS & 4'E | P | 3 | x | 12 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 150 | CF | 32/34 | P-32 | 70' N OF SEOS 12' W | B | | x | | 108 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 151 | CF | 32/34 | P32 | 73' N OF SEOS 13' W | P | 1 | x | 1 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 152 | SJ | 30/31/32 | | 158' N OF SEOS | P | 2 | x | 13 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 153 | SJ | 32/33/34 | | 130'N OF SEOS | P | 2 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 154 | CF | 27/28 | | 115' N OF SEOS | P | 8 | x | 10 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 155 | BO | 27/28 | | 102' N OF SEOS | P | 3 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 156 | PB | 28/29 | | 15' N OF SEOS (8"PB) | P | 4 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 157 | SJ | 33/34/35 | | 130' N OF SEOS | P | 2 | x | 2 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 158 | DS-12 | 34/35 | | 21' N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 159 | SJ | 35/36/37 | | 82' N OF SEOS | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 160 | SJ | 36/37/38 | | 82' N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 161 | DS-13 | 36/38 | | 127' N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 162 | CF | 36/38 | P-38 | BETWEEN R-161 & R-163 | B | | x | | 96 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 163 | CF | 36/38 | P-38 | 126' N OF SEOS & 10'W | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 164 | CF | 35/37 | P-37 | 3'N OF SEOS 9' W | B | | x | | 72 | 7/ | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 165 | CF | 35/37 | P-37 | 6'N OF SEOS 10' W | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 166 | CF | 37/38 | | 3'N OF SEOS | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 167 | SJ | 38/39/40 | | 35' N OF SEOS | P | 3 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 168 | CF | 38/39 | | 74' N OF SEOS | P | 3 | x | 5 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 169 | BO | 38/39 | | 178' N OF SEOS | P | 3 | x | 5 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 170 | SI | 38/39 | P38 | 127' N OF SEOS 7' W | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 171 | AO | | 40/39 | BETWEEN R-167 & R-172 | C | 2 | x | 23 | | 7/7/16 | BS | 4131 | Air Pressure | Pass | 7/7/16 |
| 172 | SJ | 39/40/41 | | 35'N OF SEOS | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 173 | CF | 39/41 | P-41 | 132' N OFSEOS 5'E | P | 4 | x | 13 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 174 | CF | 39/41 | P-39 | 142' N OF SEOS 4' W | P | 3 | x | 10 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 175 | CF | 39/41 | | 162' N OF SEOS | P | 2 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 176 | BO | 39/41 | | 173' N OF SEOS | P | 2 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 177 | CF | 41/42 | | 70' N OF SEOS | P | 5 | x | 20 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 178 | CF | 41/42 | P-41 | 92' N OF SEOS | P | 3 | x | 6 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 179 | CF | 41/42 | | 105' N OF SEOS | P | 3 | x | 30 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 180 | CF | 41/42 | P-42 | 156' N OF SEOS | P | 6 | x | 17 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 181 | CF | 41/42 | P-42 | BETWEEN R-180 & R-187 | B | | x | | 120 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 182 | CF | 39/41 | P-41 | 159' N OF SEOS 4' E | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 183 | CF | 39/41 | P-41 | BETWEEN R-182 & R-175 | B | | x | | 48 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 184 | DS-14 | 41/42 | | 139' N OF SEOS | P | 2 | x | 6 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 185 | DSX-5 | R-179/42 | | 100' N OF SEOS 3' E | P | 2 | x | 6 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 186 | CF | 41/42 | P-42 | 157' N OF SEOS & 10' E | P | 4 | x | 8 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 187 | CF | 41/42 | P-42 | 162' N OF SEOS | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 188 | CF | 41/42 | P-42 | 138' N OF SEOS & 10'E | P | 4 | x | 10 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 189 | PB | 42/43 | | 136' N OF SEOS (48" MH ) | P | 7 | x | 9 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 190 | CF | 42/43 | P-43 | 127' N OF SEOS & 2' E | P | 5 | x | 13 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 191 | CF | 42/43 | P-43 | 202' N OF SEOS & 10' E | P | 2 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 192 | CF | 42/43 | P-43 | BETWEEN R-191 & R-193 | B | | x | | 120 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 193 | CF | 42/43 | | 210' N 0F SEOS | P | 3 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 194 | CF | 42/43 | | BETWEEN R-193 & R-195 | B | | x | | 36 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 195 | CF | 42/43 | | 215' N OF SEOS | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 196 | CF | 42/43 | P-42 | 215'N OF SEOS (BETWEEN R-195/197 | B | | x | | 60 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 197 | CF | 42/43 | P-42 | 114' N OF SEOS( BETWEEN R-196/198 | B | | x | | 48 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 198 | CF | 42/43 | P-42 | 210' N 0F SEOS 7'W | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 199 | CF | 42/43 | P42 | 215' OFSEOS 7'W | P | 3 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 200 | CF | 42/43 | P42 | 114'N OF SEOS 11'W | P | 3 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 201 | CF | 42/43 | P-42 | 122'N OFSEOS 11'W | B | | x | | 18 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 202 | CF | 42/43 | P-42 | 132'N OF SEOS 10'W | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 203 | CF | 42/43 | P-43 | 91' N OF SEOS 10'E | P | 4 | x | 10 | | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 204 | CF | 42/43 | P-43 | 91'N OF SEOS 19'E | B | | x | | 120 | | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 205 | CF | 42/43 | P-43 | 106'N OF SEOS 20'E | B | | x | | 108 | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 206 | CF | 42/43 | P-43 | 103' N OFSEOS 20'E | P | 2 | x | 5 | | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 207 | CF | 42/43 | P-43 | 103' N OF SEOS 9'E | P | 3 | x | 13 | | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 208 | CF | 43/44 | P-43 | 107'N OF SEOS 13'W | P | 5 | x | 17 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 209 | CF | 43/44 | P-43 | 180' N OF SEOS 10'W | P | 6 | x | 22 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 210 | CF | 42/43 | P-43 | 187' N OF SEOS 8' W | B | | x | 72 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 211 | CF | 42/43 | P-43 | 190'N OF SEOS 8' E | P | 3 | x | 7 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 212 | DSX-6 | R180/42 | P-42 | 53'N SEOS 5'E | P | 3 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 213 | SJ | 43/44/45 | | 36'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 214 | CF | 43/44 | | 46'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 215 | CF | 43/44 | | 72'N OF SEOS | P | 2 | x | 4 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 216 | BO | 43/44 | | 98'N OF SEOS | P | 2 | x | 4 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 217 | CF | 43/44 | | 143'N OF SEOS | P | 2 | x | 4 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 218 | CF | 43/44 | | 150'N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 219 | CF | 43/44 | | 146'N OF SEOS 28'W | B | | x | | 60 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 220 | SJ | 43/44/44A | | 196'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 221 | SJ | 44/44A/43 | | 220' N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 222 | SI | 45/46 | | 11'N OF 4'W | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 223 | SJ | 44/45/46 | | 35'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 224 | DSX-7 | 43/44 | P-43 | 45'N OF SES 4'W | P | 4 | x | 2 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 225 | CF | 44/46 | P-44 | 180'N SEOS | P | 10 | x | 16 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 226 | DS15 | 43/44 | | 187'N OF SEOS | P | 2 | x | 4 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 227 | CF | 43./44 | P-44 | 181'N OF SEOS 5'E | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 228 | CF | 43/44 | P-44 | 181' N OF SEOS 7' E | B | | x | | 24 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 229 | CF | 43/44 | P-44 | 181'N OF SEOS 9'E | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 230 | DS-17 | 45/46 | | 24'N OF SEOS | P | 2 | x | 4 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 231 | DS-16 | 46/47 | | 146'N OF SEOS | P | 2 | x | 4 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 232 | SJ | 46/47/48 | | 115'N OF SEOS | P | 2 | x | 7 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 233 | SJ | 47/48/49 | | 116'N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 234 | CF | 47/49 | | 164' N OF SEOS | P | 3 | x | 8 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 235 | BO | 46/47 | | 258'N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 236 | CF | 46/47 | | 266'N OF SEOS | P | 5 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 237 | PB | 44/46 | P-46 | 112'N OF SEOS 8'E(8"PB) | P | 4 | x | 5 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 238 | AO | 46/47 | | 19'N OF SEOS (CAP 19') | P | 2 | x | 19 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 239 | CF | 44/46 | P-44 | 195'N OF SEOS 7'W | P | 2 | x | 2 | | 7/11/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 240 | CF | 44/46 | P-44 | 203'N OF SEOS 7'W | B | | x | 9 | | 7/11/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 241 | CF | 44/46 | P-44 | 206'N SEOS 7'W | P | 2 | x | 2 | 108 | 7/11/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 242 | SI | 49/50 | | 3'N OF SEOS | B | | x | | 60 | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 243 | BO | 49/50 | | 6'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 244 | DS-18 | 49/50 | | 251' N OF SEOS | P | 2 | x | 5 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 245 | BO | 49/50 | | 271'N OF SEOS | P | 2 | x | 4 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 246 | SJ | 50/52/53 | | 20'N OF SEOS | P | 2 | x | 3 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/1/16 |
| 247 | CF | 50/52 | P-50 | 73'N OF SEOS 2'W | P | 2 | x | 2 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/11/16 |
| 248 | CF | 50/52 | P-50 | 85'N OF SEOS 10'W | P | 3 | x | 5 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 249 | CF | 50/52 | P-50 | BETWEEN R-247 & R-248 | B | | x | | 108 | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 250 | SJ | 50/51/52 | | 74'N OF SEOS | P | 3 | x | 4 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 251 | CF | 50/51 | | 111'N OF SEOS | P | 3 | x | 5 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 252 | CF | 50/51 | P-50 | 102N OF SEOS 8'W | P | 2 | x | 8 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 253 | CF | 50/51 | P-50 | 106N OF SEOS 5'W | B | | x | | 72 | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 254 | CF | 50/51 | | 214N OF SEOS | P | 3 | x | 10 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 255 | CF | 50/51 | | 274'N OF SEOS | P | 3 | x | 3 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 256 | DS19/SJ | 52/53/54 | | 20' NSEOS | P | 3 | x | 8 | | 7/12/16 | SU | Extr #249 | Vacuum | Pass | 7/13/16 |
| 257 | SJ | 51/54/52 | | 74'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 258 | SJ | 54/56/57 | | 30'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 259 | SJ | 54/55/56 | | 103'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 260 | DS-20 | 54/55/56 | 55/56 | BETWEEN R-259 & R-263 | P | 2 | x | 6 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CR | --Crease | FS | --Failed Seam | MatD | --Material Defect | LL | --Lost Lap | CF | --Custom Fit |
| DS | --Destruct Sample | WR | --Wrinkle | WS | --Welder Restart | MD | --Mechanical Damage | PB | --Pipe Boot |
| SI | --Subgrade Irregularity | AV | --Airvent | RW | --Roller Wrinkle | DO | --Damage By Others | BO | --Burn Out |
| SJ | --Seam Joint | AO | --Add On | CS | --Concrete Structure | | | AT | -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 6489 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 261 | PB | 54/55 | P-55 | 285'N OF SEOS 20'E (4" PB) | P | 4 | x | 4 | | 7/12/16 | SU | EXTR #74 | Vacuum | Pass | 7/13/16 |
| 262 | SJ | 56/57/58 | | 30'N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 263 | SJ | 55/56/58 | | 103'N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 264 | BO | 55/58 | | 273' N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 265 | BO | 55/58 | | 285'N OF SEOS | P | 2 | x | 4 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 266 | CF | 55/58 | | 289'N OF SEOS | B | | x | | 72 | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 267 | SJ | 58/59/60 | | 94'N OF SEOS | P | 3 | x | 3 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 268 | SJ | 59/60/61 | | 94'N OF SEOS | P | 3 | x | 3 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 269 | BO | 59/61 | | 278'N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 270 | SJ | 61/62/63 | | 194'N OF SEOS | P | 2 | x | 6 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 271 | DS-21 | 58/59 | | 266'N OF SEOS | P | 2 | x | 4 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 272 | DS-22 | 61/63 | | 137' N OF SEOS | P | 2 | x | 5 | | 7/13/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 273 | WR | 50/51 | | 165'N OF SEOS | P | 3 | x | 10 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 274 | WR | 50/51 | 51 | 170'N OF SEOS 5'E | P | 3 | x | 10 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 275 | CF | 50/51 | 51 | BETWEEN R-274 & R-276 | B | | x | | 60 | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 276 | BO | 50/51 | | 158'N OF SEOS | P | 3 | x | 4 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 277 | SJ | 62/63/64 | | 193'N OF SEOS | P | 2 | x | 3 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 278 | CF | 64/65 | | 187'N OF SEOS | P | 2 | x | 3 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 279 | CF | 64/65 | | 216'N OF SEOS | P | 2 | x | 3 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 280 | CF | 64/65 | | 115'N OF SEOS | P | 5 | x | 10 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 281 | SJ | 65/66/67 | | 116'N OF SEOS | P | 2 | x | 2 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 282 | CF | 64/65 | 65 | BETWEEN R-278 & R-283 | B | | x | | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 283 | CF | 64/65 | 65 | 193'N OF SEOS & 12'E | P | 2 | x | 4 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 284 | CF | 64/65 | 65 | 215'N OF SEOS & 11'E | P | 2 | x | 9 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 285 | CF | 64/65 | 65 | BETWEEN R-279 & R-284 | B | | x | | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 286 | DSX-8 | R-270/61 | | 193'N OF SEOS | P | 2 | x | 6 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 287 | DS-23 | 64/65 | | 17'N OF SEOS | P | 2 | x | 6 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 288 | PB | 65/66 | 65 | 90'N OF SEOS & 7'W (8") | P | 2 | x | 5 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 289 | SJ | 66/67/68 | | 115' OF SEOS | P | 2 | x | 2 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 290 | CF | 66/68 | | 167'N OF SEOS | P | 6 | x | 10 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 291 | DS-24 | 66/68 | 66 | 148'N OF SEOS | P | 2 | x | 4 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 292 | PB | 66/68 | 66 | 148'N OF SEOS & 3'W (8") | P | 6 | x | 8 | | 7/14/16 | SU | EXTR #74 | Vacuum | Pass | 7/14/16 |
| 293 | BO | 68/71 | | 99' N OF SEOS | P | 3 | x | 5 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 294 | SJ | 68/70/71 | | 147' N OF SEOS | P | 5 | x | 3 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 295 | SJ | 68/69/70 | | 216' N OF SEOS | P | 2 | x | 2 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 296 | DS-25 | 68/69 | | 250' N OF SEOS | P | 3 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 297 | CF | 68/70 | P70 | 155'N OF SEOS & 12' E | P | 4 | x | 4 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 298 | CF | 70/72 | P70 | BETWEEN R-297 & R-299 | B | | x | | 109 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 299 | SJ | 71/70/72 | | 155'N OF SEOS | P | 2 | x | 16 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 300 | DSX-9 | 72/R299 | | 153'N OF SEOS | P | 2 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 301 | CF | 70/72 | | 200'N OF SEOS | P | 5 | x | 8 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 302 | SJ | 69/70/72 | | 217'N OF SEOS | P | 2 | x | 2 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 303 | CF | 72/74 | | 54'N OF SEOS | P | 3 | x | 9 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 304 | CF | 72/74 | P-72 | 60'N OF SEOS & 7' W | B | | x | | 109 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 305 | CF | 72/74 | P-72 | BETWEEN R-306 & R-317 | B | | x | | 109 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 306 | CF | 72/74 | | 104'N OF SEOS | P | 2 | x | 3 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 307 | CF | 72/74 | | 114'N OF SEOS | P | 2 | x | 3 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 308 | CF | 72/74 | P-74 | BETWEEN R-307 & R-308 | B | | x | | 84 | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 309 | CF | 74/74 | | 164'N OF SEOS | P | 4 | x | 9 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 310 | CF | 72/74 | | 172'N OF SEOS | P | 4 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 311 | SJ | 72/73/74 | | 220'N OF SEOS | P | 3 | x | 4 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 312 | DS-26 | 72/74 | | 145'N OF SEOS | P | 2 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 313 | PB | 72/74 | | 158'N OFSEOS & 6'W (8" BOOT) | P | 2 | x | 2 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 314 | CF | 74/75 | | 76'N OF SEOS | P | 3 | x | 7 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 315 | CF | 74/75 | | 209'N OF SEOS | P | 5 | x | 7 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 316 | SJ | 74/73/75 | | 218'N OF SEOS | P | 2 | x | 3 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 317 | CF | 72/74 | | 109'N OF SEOS & 7' W | P | 1 | x | 1 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 318 | CF | 72/74 | | 114'N OF SEOS & 9'E | P | 2 | x | 2 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 319 | CF | 74/75 | P-75 | 95'N OF SEOS & 10'W | P | 3 | x | 5 | | 7/27/16 | SU | EXT-75 | Vacuum | Pass | 7/27/16 |
| 320 | CF | 74/75 | P-75 | BETWEEN R-319&R-333 (DSX-10) | B | | x | | 108 | 7/27/16 | SU | EXT-75 | Vacuum | Pass | 7/27/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 321 | CF | 72/74 | P-74 | 48'N OF SEOS 2' E | P | 2 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 322 | CF | 72/74 | P-72 | 62'N OF SEOS 8' W | P | 1 | x | 2 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 323 | CF | 74/75 | P-75 | 35'N OF SEOS 10' E | P | 2 | x | 2 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 324 | CF | 74/75 | P-75 | BETWEEN R-323 AND R-325 | B | | x | | 144 | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 325 | CF | 74/75 | P-75 | 50'N OF SEOS 10' E | P | 1 | x | 1 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 326 | CF | 74/75 | P-75 | 157'N OF SEOS 12' E | P | 2 | x | 2 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 327 | CF | 74/75 | P-75 | BETWEEN R-326 AND R-334 | B | | x | | 144 | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 328 | SI | 71/72 | P-72 | 77'N OF SEOS 7' E | P | 2 | x | 2 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 329 | CF | 74/75 | P-75 | 164'N OF SEOS 7'E | P | 2 | x | 3 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 330 | CF | 74/75 | P-75 | BETWEEN R-329 AND R-331 | B | | x | | 84 | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 331 | CF | 74/75 | P-75 | 173'N OF SEOS 7'E | P | 3 | x | 3 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 7/27/16 |
| 332 | CF | 75/76 | | 8'N OF SEOS | P | 2 | x | 7 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 333 | CF | 75/76 | | 81'N OF SEOS | P | 3 | x | 3 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 334 | CF | 75/76 | | 151'N OF SEOS | P | 2 | x | 3 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 335 | BO | 75/76 | | 234'N OF SEOS | P | 2 | x | 4 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 336 | SI | 75/76 | | 254'N OF SEOS | P | 4 | x | 14 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 337 | DS-27 | 75/76 | | 24'N OF SEOS | P | 2 | x | 5 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 338 | DSX-10 | 75/76 | P-75 | 82'N OF SEOS 5'W | P | 2 | x | 5 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 339 | CF | 76/78 | | 4'N OF SEOS | P | 3 | x | 7 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 340 | SJ | 76/77/78 | | 40'N OF SEOS | P | 3 | x | 6 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 341 | CF | 78/79 | P-78 | 15'N OF SEOS | P | 2 | x | 9 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 342 | CF | 76/78 | | 15'N OF SEOS | P | 2 | x | 5 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 343 | PB | 78/79 | P-78 | 15'N OF SEOS 9'W (6"PB) | P | 2 | x | 4 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 344 | SJ | 77/78/79 | | 40'N OF SEOS | P | 3 | x | 3 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 345 | CF | 77/79 | P-79 | 138'N OF SEOS | P | 2 | x | 15 | | 7/27/16 | SU | EXTR #74 | Vacuum | Pass | 8/2/16 |
| 346 | CF | 77/79 | P-77 | 144'N OF SEOS 3'E | P | 6 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 347 | CF | 76/78 | | 25'N OF SEOS | P | 2 | x | 3 | | 7/27/16 | SU | EXT-75 | Vacuum | Pass | 8/2/16 |
| 348 | CF | 79/80 | P-79 | 133'N OF SEOS | P | 5 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 349 | CF | 79/80 | P-79 | 129'N OF SEOS 9' W | P | 2 | x | 3 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 350 | CF | 79/80 | P-79 | 131'N OFSEOS 10' W | P | 2 | x | 2 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 351 | CF | 79/80 | P-79 | BETWEEN R-348 AND R-349 | B | | x | | 36 | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 352 | CF | 79/80 | P-79 | BETWENN R-348 AND R-353 | B | | x | | 36 | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 353 | CF | 79/80 | P-79 | 138'N OF SEOS 2'W | P | 2 | x | 3 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 354 | CF | 79/80 | P-79 | 134'N OF SEOS 3'W (ON R-348) | P | 3 | x | 3 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 355 | CF | 79/80 | | 167'N OF SEOS | P | 5 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 356 | SI | 79/80 | P-79 | 106'N OF SEOS 4'W | P | 3 | x | 6 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 357 | CF | 79/80 | P-80 | 140' N OF SEOS 1'E (48" MH) | P | 6 | x | 6 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 358 | CF | 79/80 | P-79 | 207'N OF SEOS 6'W | P | 4 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 359 | CF | 79/80 | P-79 | 208'N OF SEOS 10'W | P | 3 | x | 7 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 360 | CF | 77/79 | P-79 | 148'N OF SEOS (ON R-346) | P | 2 | x | 2 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 361 | CF | 77/79 | P-77 | 137'N OF SEOS 6'W | P | 1 | x | 2 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 362 | CF | 80/82 | | 6'N OF SEOS | P | 2 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 363 | SJ | 80/81/82 | | 25'N OF SEOS | P | 2 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 364 | CF | 80/81 | | 130'N OF SEOS | P | 3 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 365 | CF | 80/81 | | 140'N OF SEOS | P | 3 | x | 15 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 366 | CF | 80/81 | P-80 | BETWEEN R-364 AND R-365 | B | | x | | 36 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 367 | CF | 80/81 | P-80 | 140'NOF SEOS | P | 3 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 368 | CF | 80/81 | | 150'N OF SEOS | P | 4 | x | 6 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 369 | CF | 80/81 | | 264'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 370 | SJ | 81/82/83 | | 25'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 371 | CF | 81/83 | | 31'N OF SEOS | P | 2 | x | 6 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 372 | BO | 81/83 | | 145'N OF SEOS | P | 2 | x | 5 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 373 | CF | 81/83 | | 216'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 374 | SJ | 83/84/85 | | 52'N OF SEOS | P | 3 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 375 | CF | 83/84 | | 202'N OF SEOS | P | 3 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 376 | SJ | 84/85/86 | | 52'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 377 | CF | 84/86 | | 198'N OF SEOS | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 378 | SJ | 86/87/88 | | 96'N OF SEOS | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 379 | CF | 86/87 | P-86 | 205' N OF SEOS | P | 4 | x | 11 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 380 | PB | 76/78 | P-76 | 6'N OF SEOS 4'W | P | 5 | x | 6 | | 7/28/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 381 | CF | 86/88 | | 40'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 382 | CF | 83/84 | 83 | 197'N OF SEOS 10'W | P | 3 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 383 | CF | 83/84 | 83 | BETWEEN R-382 AND R-375 | B | | x | | 120 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 384 | PB | 81/83 | 81 | 32'N OF SEOS 7'W (8" PB) | P | 2 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 385 | CF | 80/82 | 80 | BETWEEN R-362 AND R-386 | B | | x | | 120 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 386 | CF | 80/82 | 80 | 10'N OF SEOS 10W | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 387 | CF | 84/86 | 86 | BETWEEN R-377 AND R-379 | B | | x | | 86 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 388 | CF | 86/87 | 87 | 250'N OF SEOS 19'E | P | 3 | x | 12 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 389 | CF | 86/88 | 86 | BETWEEN R-381 AND R-390 | B | | x | | 10 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 390 | CF | 86/88 | 86 | 42'N OF SEOS & 9'E | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 391 | DS-26 B | 72/74 | | 154'N OF SEOS | P | 2 | x | 11 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 392 | DS-26 A | 72/74 | | 128'N OFSEOS | P | 2 | x | 11 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 393 | DS-28 | 81/83 | | 177'N OF SEOS | P | 2 | x | 5 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 394 | DSX-11 | 83/81 | 81 | 144'N OF SEOS 12'W | P | 2 | x | 5 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 395 | DSX-12 | 84/86 | 86 | 199'N OF SEOS 4'E | P | 2 | x | 5 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 396 | CF | 86/87 | | 210'N OF SEOS | P | 4 | x | 14 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 397 | CF | 86/87 | 86 | 210'N OF SEOS 7'W | P | 3 | x | 4 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 398 | CF | 86/87 | 86 | 208'N OF SEOS 10'W | P | 3 | x | 15 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 399 | CF | 86/87 | 87 | 200'N OF SEOS 9'E | P | 4 | x | 20 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 400 | CF | 87/90 | | 115'N OF SEOS | P | 2 | x | 5 | | 8/3/16 | SU | EXT-74 | Vacuum | | |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 6489 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 6528.42 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 401 | CF | 87/90 | 90 | BETWEEN R-400 AND R-402 | B | | x | | 120 | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 402 | CF | 87/90 | 90 | 115'N OF SEOS 13'E | P | 2 | x | 3 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 403 | BO | 87/90 | | 130'N OF SEOS | P | 2 | x | 5 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 404 | BO | 87/89/90 | | 150'N OF SEOS | P | 2 | x | 3 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 405 | SJ | 88/87/90 | | 97'N OF SEOS | P | 2 | x | 3 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 406 | CF | 90/91 | 90 | 50'N OF SEOS 3'W | P | 3 | x | 6 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 407 | CF | 90/91 | 90 | 49'N OF SEOS 7'W | P | 3 | x | 9 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 408 | PB | 90/91 | 91 | 238'N OF SEOS 7'W (4" PB) | P | 4 | x | 10 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 409 | PB | 90/91 | 91 | 107'N OF SEOS 5'E (8" PB) | P | 4 | x | 4 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 410 | CF | 91/92 | | 160' N OF SEOS | P | 6 | x | 17 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 411 | CF | 91/92 | | 180'N SEOS | P | 4 | x | 6 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 412 | CF | 92/93 | | 100'N OF SEOS | P | 3 | x | 5 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 413 | CF | 92/93 | 92 | BETWEEN R-412 AND R-414 | B | | x | | 84 | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 414 | CF | 92/93 | 92 | 115'N OF SEOS 11'W | P | 4 | x | 6 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 415 | CF | 87/89 | 87 | 246' N OF SEOS 4'W | P | 3 | x | 8 | | 8/3/16 | SU | EXT-74 | Vacuum | | |
| 416 | | | | | | | x | | | | | | | | |
| 417 | | | | | | | x | | | | | | | | |
| 418 | | | | | | | x | | | | | | | | |
| 419 | | | | | | | x | | | | | | | | |
| 420 | | | | | | | x | | | | | | | | |

**Non-conformance Log**
*(Attachment 11:  Capping Update)*

## Summary of Non-Compliance & Corrective Action Forms

***SA-6 North Cap Installation***

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 1 | 6/23/2016 | Subgrade Irregularity | R-10 | Panel P6 | Rock was removed from underneath geomembrane and hole was then patched with approximate 3 ft. by 3 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 2 | 6/29/2016 | Subgrade Irregularity | R-98 | Panel P26 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 3 | 7/6/2016 | Failed Spark Test | Gas Vent GV-5 | Gas Vent GV-5 | Spark identified during spark testing of vertical boot weld on Gas Vent GV-5 boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed duriing the test |
| 4 | 7/6/2016 | Failed Spark Test | Well 115-W1-SO | Well 115-W1-SO | Spark identified during spark testing of vertical boot weld on Well 115-W1-SO boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed duriing the test |
| 5 | 7/7/2016 | Subgrade Irregularity | R-170 | Panel P38 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 6 | 7/8/2016 | Subgrade Irregularity | R-222 | Panel P45 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 3 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 7 | 7/12/2016 | Subgrade Irregularity | R-242 | Panel P49 / P50 | Rock was removed from underneath LLDPE geomembrane along the southern edge of SA-6 North (approximately 3 ft. from the edge of the cap. As such, the edge of the LLDPE was cut to remove the stone. This cut was then repaired with an extrusion weld bead. Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the cut / bead was properly sealed (as outlined in Section 02372). |
| 8 | 7/27/2016 | Subgrade Irregularity | R-328 | Panel P72 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs) |
| 9 | 7/28/2016 | Failed Destruct Sample | DS-26 | Panel P72 / P74 (Repair R-312) | Destruct sample DS-26 reported two coupons as EPA Break Classification Code "AD BRK". Although the peel and shear strength requirments were met, since the coupons broke at the weld and were not conisdering a Film Tearing Bond, the sample was reported as a failed sample. Two field samples (DS-26A and DS-26B) were cut 10 ft. from each side of DS-26 and field tested. Peel and shear field tests met the strength requirments and sample DS-26B (lesser strength values of both samples) was sent for laboratory analysis (results pending). |

**Subgrade Approval Forms**
*(Attachment 11: Capping Update)*

LANGAN

# Certificate of Soil Surface

Sheet # 4

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 315+75 TO ~STA. 314+25 | | |
| QA Monitor | LANGAN | Date | 6/27/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P19 (INSTALLED ON 6/24/16). FROM APPROX. STA. 315+75 TO APPROX STA. 314+25. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 6/27/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 6/29/16 |
| Title | QC Manager |
| Representing: | Entrust |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½")
AS OUTLINED IN SECTION 02372-8.
- NO GCL TO BE PLACED ALONG WESTERN END OF SA-6 NORTH.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | STA. 315+75 | LOOKING E | REFER TO PHOTO #1 (PHOTO LOG 6/27/16) |
| | 2 PHOTO #2 | STA. 315+00 | LOOKING S | REFER TO PHOTO #2 (PHOTO LOG 6/27/16) |
| 1. REFER TO 6/27/16 PHOTOGRAPH LOG PHOTOS 1 TO 3 FOR SUPPORTING INFORMATION | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 5

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA 6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 314.25 TO ~STA. 313+25 | | |
| QA Monitor | LANGAN | Date | 6/30/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P27 (INSTALLED ON 6/27/16) FROM APPROX. STA. 314+25 TO APPROX. STA. 313+25. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 6/30/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Ibarra |
| Date: | 7/1/16 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Carolina Ibarra |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8

-NO GCL TO BE PLACED ALONG WESTERN END OF SA-6 NORTH

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | | | REFER TO PHOTO #1 (PHOTO LOG 6/30/16) |
| | 2 PHOTO #2 | | | REFER TO PHOTO #2 (PHOTO LOG 6/30/16) |
| 1. REFER TO 6/30/16 PHOTOGRAPH LOG PHOTOS 1 TO 3 FOR SUPPORTING INFORMATION. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 6

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 313+25 TO ~STA. 312+60 | | |
| QA Monitor | LANGAN | Date | 7/1/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P32 (INSTALLED ON 6/30/16) FROM APPROX STA. 313+25 TO APPROX STA. 312+60. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/1/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolyn Panico |
| Date: | 7/1/16 |
| Title | QC Manager |
| Representing: | Entek |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8.

- NO GCL TO BE PLACED FROM ~STA. 313+25 TO ~STA. 312+60

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 313+25 | LOOKING N | REFER TO PHOTO #1 (PHOTO LOG 7/1/16) |
| | 2 PHOTO #2 | ~STA. 313+25 | LOOKING S | REFER TO PHOTO #2 (PHOTO LOG 7/1/16) |
| 1. REFER TO 7/1/16 PHOTOGRAPH LOG PHOTOS 1 TO 3 FOR SUPPORTING INFO. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 7

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 312+60 TO ~STA. 311+75 |
| QA Monitor | LANGAN | Date | 7/6/16 |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P38 (INSTALLED ON 7/1/16) FROM APPROX. STA. 312+60 TO APPROX. STA. 311+75. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/6/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/8/16 |
| Title | QC Mgr |
| Representing: | Layfield |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT. x 8 FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (i.e. >½'). NO GCL TO BE PLACED FROM ~STA. 312+60 TO ~STA. 311+75

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA 312+25 | LOOKING S/SE | REFER TO PHOTO #3 (PHOTO LOG 7/6/16) |
| | 2 PHOTO #4 | ~STA 312+27 | LOOKING E | REFER TO PHOTO #4 (PHOTO LOG 7/6/16) |
| 1. REFER TO 7/6/16 PHOTOGRAPH LOG PHOTOS 3 TO 5 FOR SUPPORTING PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 8

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 311+75 TO ~STA. 311+55 | | |
| QA Monitor | LANGAN | Date | 7/7/16 | | |

Description of Soil Surface to be lined: ~20 FT. AREA IMMEDIATELY EAST OF PANEL P42 (INSTALLED ON 7/6/16) FROM APPROX. STA. 311+75 TO APPROX. STA. 311+55. APPROVED SOIL FOR PLACEMENT OF ONE PANEL SO INSTALLED LLDPE TERMINATES OUTSIDE OF BOTTOM OF SWALES + GRADES TO CONTOURS TO PROMOTE + DRAINAGE (PM RAINSTORMS FORECASTED).

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/7/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/8/16 |
| Title | QC Mgr |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8.
-SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT. × 8 FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>½"). NO GEL TO BE PLACED FROM ~STA. 311+75 TO ~STA. 311+55'.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | ~STA 311+85 | LOOKING N | REFER TO PHOTO #9 (PHOTO LOG 7/7/16) |
| | 2 | | | |
| 1. REFER TO 7/7/16 PHOTO LOG PHOTO 9 (N ALONG ~STA 311+75) | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 9

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 311+55 TO ~STA. 310+80 | | |
| QA Monitor | LANGAN | Date | 7/8/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P43 (INSTALLED ON 7/7/16) FROM APPROX. STA. 311+55 TO ~STA. 310+80. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BUDWORTH |
| Date: | 7/8/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/8/16 |
| Title | QC Mgr |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (>1/2")
As outlined In Section 02372-8.
- Subgrade Observed By Field Engineer Who Walked The Placement Area In Approx. 200 ft. x 8ft. Transects To Observe Soil Compaction As well As Items Requiring Removal Prior to Panel Placement (>1/2"). No GCL to Be Placed From ~Sta. 311+55 To ~Sta. 310+80.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #1 | ~Sta. 311+55 | Looking S/SE | Refer to Photo #1 (7/8/16) |
| | 2 Photo #2 | ~Sta. 311+55 | Looking S | Refer to Photo #2 (7/8/16) |
| 1. Refer to 7/8/16 Photo Log Photos 1+2 for Supporting Subgrade Photos | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 10

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 310+80 TO ~STA. 309+75 | | |
| QA Monitor | LANGAN | Date | 7/12/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P49 (INSTALLED ON 7/8/16) APPROX. 105 FT. FROM APPROX STA. 310+80 TO ~STA 309+75. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/12/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 7/15/16 |
| Title | QC Mgr |
| Representing: | Layfield |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT. x 8 FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>½"). NO GCL TO BE PLACED FROM ~STA. 310+80 TO ~STA. 309+75.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #7 | ~STA. 310+80 | LOOKING N | REFER TO PHOTO #7 (7/12/16) |
| | 2 PHOTO #8 | ~STA. 310+80 | LOOKING E | REFER TO PHOTO #8 (7/12/16) |

1. REFER TO 7/12/16 PHOTO LOG PHOTOS 7 TO 9 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 11

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 309+75 | TO ~STA. 309+00 | |
| QA Monitor | LANGAN | Date | 7/13/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P55/P56/P57 (INSTALLED ON 7/12/16) APPROX 175 FT. FROM APPROX. STA. 309+75 TO ~STA. 309+00. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/13/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 7/15/16 |
| Title | QC Mgr |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (≥ ½") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT BY 8FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (7½"). NO GCL TO BE PLACED FROM ~STA 309+75 TO ~STA. 309+00.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 309+75 | LOOKING S | REFER TO PHOTO #3 (7/13/16) |
| | 2 PHOTO #4 | ~STA. 309+75 | LOOKING E | REFER TO PHOTO #4 (7/13/16) |
| 1. REFER TO 7/13/16 PHOTO LOG PHOTOS 3 TO 5 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 12

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 309+00 TO ~STA. 308+20 | | |
| QA Monitor | LANGAN | Date | 7/14/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P62/P63 (INSTALLED ON 7/13/16) APPROX 85 FT FROM APPROX STA. 309+00 TO ~STA. 308+20 SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/14/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/15/16 |
| Title | QC Mgr |
| Representing: | Environet |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT. BY 8 FT. TRANSECTS TO OBSERVE SOIL CONDITION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>½"). NO GCL TO BE PLACED FROM APPROX STA. 309+00 TO ± STA. 308+20.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 309+00 | LOOKING E | REFER TO PHOTO #1 (7/14/16) |
| | 2 PHOTO #2 | ~STA 309+00 | LOOKING N | REFER TO PHOTO #2 (7/14/16) |
| 1. REFER TO 7/14/16 PHOTOGRAPH LOG, PHOTOS 1 TO 3 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 13

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 North | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec F&W | Cell No. | ~Sta. 308+20 to ~Sta. 307+20 | | |
| QA Monitor | Langan | Date | 7/25/16 | | |

Description of Soil Surface to be lined: Area immediately East of Panel 768 (installed on 7/14/16) approx 100 ft. from approx ~Sta. 308+20 to ~Sta. 307+20 Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/25/16 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/25/16 |
| Title | QC Mgr |
| Representing: | Entrel |
| Signature: | |

LANGAN

Notes, Observations, Comments: Soil Graded, compacted, And Free of Debris (>1/2")
As outlined In Section 023172-8.
*Subgrade Observed By Field Engineer Who Walked The Placement Area In Approx 200 FT x 8 ft. Transects To Observe Soil Compaction As well As Items Requiring Removal Prior to Panel Placement (>1/2"). No GCL to Be Placed From ~ Sta. 308+20 to ~ Sta. 307+20

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #1 | ~Sta. 308+15 | Looking S | Refer to Photo #1 (11/25/16) |
| | 2 Photo #2 | ~Sta 308+15 | Looking E | Refer to Photo #2 (11/25/16) |
| 1. Refer to 11/25/16 Photograph Log Photos 1 to 3 for supporting Subgrade Photos | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 14

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 307+20 TO ~STA. 306+40 | | |
| QA Monitor | LANGAN | Date | 7/27/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P175 (INSTALLED ON 7/25/16) APPROX 80 FT. FROM ~STA. 307+20 TO ~STA. 306+40. SOIL ADDITIONS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/27/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | CAROLINA PANICO |
| Date: | 7/27/16 |
| Title | QC |
| Representing: | Entrak |
| Signature: | |

LANGAN

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (>1/2")
As outlined in Section 02372-8.
- Subgrade Observed By Field Engineer Who Walked The Placement Area In Approx. 200 ft. x 8ft Transects to observe Soil Compaction As well As Items Requiring Removal Prior to Panel Placement (>1/2"). No GCL to Be Placed From ~Sta. 307+20 to ~Sta. 306+40.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #1 | ~Sta. 307+00 | Looking S | Refer to Photo #1 (11/27/16) |
| | 2 Photo #2 | ~Sta. 307+20 | Looking S | Refer to Photo #2 (11/27/16) |
| 1. Refer to 11/27/16 Photograph Log Photos 1 to 4 for Supporting Subgrade Photos | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 15

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 306+40 TO ~STA. 305+40 | | |
| QA Monitor | LANGAN | Date | 7/28/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P&C (INSTALLED ON 7/27/16) APPROX 100 FT. EAST FROM ~STA. 306+40 TO ~STA. 305+40 SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/28/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/28/16 |
| Title | QC |
| Representing: | Entrust |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02317-8.

- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT. x 8 FT. TRANSECTS TO OBSERVE SOIL CONDITION AS WELL AS ITEMS REQUIRING REMOVAL TO PANEL PLACEMENT (>½"). NO GCL TO BE PLACED FROM APPROX. STA. 306+40 TO ~ STA. 305+40

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | STA. 306+40 | LOOKING N | REFER TO PHOTO #1 (7/28/16) |
| | 2 PHOTO #2 | STA. 306+40 | LOOKING S | REFER TO PHOTO #2 (7/28/16) |

1. REFER TO 7/28/16 PHOTOGRAPHIC LOG PHOTOS 1 TO 3 FOR SUPPORTING SUBGRADE PHOTOS.

2.

**QA Photo Log**
*(Attachment 11:  Capping Update)*

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (06/27/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/27/16

**Direction Taken:**

Looking west/ southwest along SA-6 North (at approximate Sta. 319+00).

**Description:**

ESI preparing to deploy GDL over Panel P1 and P2 (at approximate Sta. 319+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (06/27/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |


**Date:**
6/27/16

**Direction Taken:**

Looking north along SA-6 North at Panel P20 / P21 seam

**Description:**

ESI conducting fusion welding along Panel P20 / P21 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (06/29/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/29/16

**Direction Taken:**

Looking south along SA-6 North along southern end of cap.

**Description:**

ESI continuing patch / repair activities for LLDPE geomembrane panels P19 Through P27 (installed on 6/27/16).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (06/29/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
6/29/16

**Direction Taken:**

Looking south / southwest across SA-6 North (approximate Sta. 317+00).

**Description:**

Entact placing protective cover soil over GDL Panels 1 to 11 (GDL placed on 6/27/16).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (06/30/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
6/30/16

**Direction Taken:**

Looking south along southern end of SA6 North (approximate Sta. 314+00).

**Description:**

ESI deploying GVL with white plastic fasteners spaced at a maximum of 5 ft. along geonet. Top layer of geotextile also sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (06/30/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
6/30/16

**Direction Taken:**

SA-6 North Panel P27 / P28 seam

**Description:**

ESI conducting non-destructive testing (air pressure testing) for Panel P27 / P28 seam. Seam pressurized to 30 psi and held for 5 minutes with less than 4 psi loss.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (07/01/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
07/01/16

**Direction Taken:**

Looking north along northern end of SA-6 North (from approximate Sta. 313+25).

**Description:**

Soil subgrade prepared by Entact. Soil firm and unyielding, and graded, compacted and free of debris (>1/2").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (07/01/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
07/01/16

**Direction Taken:**

Looking north along SA-6 North (approximate Sta. 313+00).

**Description:**

ESI deploying GVL across approved subgrade for SA-6 North. White plastic fasteners spaced at 5 ft. maximum across geonet with top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (7/14/2016)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
7/14/16

**Direction Taken:**

SA-6 North – Destruct Sample DS-23

**Description:**

ESI completing patch / repair activities for Destruct Sample DS-23 located on Panel P64 / P65 seam (Repair R-287).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (07/27/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
07/27/16

**Direction Taken:**

SA-6 North – Piezometer PZ6

**Description:**

Entact conducting methane testing for LLDPE boot for Piezometer PZ6. Concentration of 0.0% methane measured. As such, spark testing was subsequently completed and no sparks were observed during the test (test passed).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (07/27/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |


**Date:**
7/27/16

**Direction Taken:**

SA-6 North – Piezometer PZ6

**Description:**

ESI conducting spark testing along vertical weld and base of boot for Piezometer PZ6. No sparks were observed (i.e. spark test passed).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (07/28/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/16

**Direction Taken:**
Looking north along SA-6 North from approximate center of cap (approximate Sta. 305+90).

**Description:**

ESI deploying LLDPE geomembrane over GVL across SA-6 North.



**Daily QA Reports (Langan)**
*(Attachment 11:  Capping Update)*

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 6/27/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 70/85° F, Sunny (AM), PM Showers |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0650 – 1930 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #5** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) continuing east from Panel P19 installed on 6/24/16 (approximate Sta. 315+75). Material to be placed from Panel P19 running approximately 150 ft. east to approximate Sta. 314+25.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 315+75 (Panel P19 installed on 6/24/16) to approximate Sta. 314+25. Refer to *Soil Subgrade Approval* forms from 6/27/15 for additional details. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos 1 to 3 of the daily photo log for 6/27/2016, for supporting subgrade photos. During subgrade observation, AmecFW was also completing surveying to verify the subgrade elevations. The area was subsequently approved by AmecFW following review of the survey data.
- While the subgrade was being surveyed, ESI deployed the orange geocomposite drainage layer (GDL), over the installed LLDPE geomembrane. GDL was placed from Panel P1 (approximate Sta. 319+00), to Panel P11 (approximate Sta. 316+25). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/27/16 Photo Log for supporting photographs.
- While GDL was being deployed, ESI also conducted, methane / spark testing for the pipe boot completed for Access Manhole #1 (Panel P10). Prior to spark testing, methane testing was conducted to measure the concentration of methane present below the LLDPE geomembrane. During methane testing of Manhole #1, a concentration of 0.1% (less than 1%) was measured. Following the methane testing, spark testing was conducted by ESI for the vertical weld and pipe boot weld at the base of the penetration (i.e. welds not accessible for vacuum box testing). No sparks were observed during the test, and Manhole #1 boot passed. Additional details are outlined in the *Spark Testing QA Form Sheet #4.*

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Following the placement of GDL, and subsequent to AmecFW completing the survey requirements for the soil subgrade, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 315+75 (east of Panel P19) moving east to approximate Sta. 314+25. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/27/16 Photo Log for supporting photographs.
- After placement of GVL, LLDPE geomembrane was installed continuing from Panel P19 (installed on 6/24/16) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 315+75 (Panel P19) to approximate Sta. 314+25. A total of eight panels were installed (P20, P21, P22, P23, P24, P25, P26, and P27). Note: During placement of panel P21, the roll of LLDPE terminated at the approximate center of the cap, thus the remaining run of LLDPE was installed as P22. Similarly, during placement of Panel P24, the roll of LLDPE terminated along the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P25. Panels P20, P23, P26, and P27 ran the entire width of SA-6 North (approximately 200 ft.) from north to south.
- Adjacent geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 6/27/16 *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 314+25, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 6/27/16 *Seam Control Form* for non-destructive testing details. Additionally, repair and extrusion weld activities were also conducted for Panels P19 through P27 to attempt to patch / cover the LLDPE before inclement weather. Additional details are outlined on the 6/27/16 *Repair Log.*
- A total of seven repairs (R-75 through R-81) were observed and fixed (according to the project specifications) from Panels P20 through P21. Refer to 6/27/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Note: not all repairs completed, repairs conducted to cover and seal cap before inclemente weather. Vacuum box testing not completed. Activities to be continued on 6/28/16. No destruct samples were collected, as destruct samples to be cut on 6/28/16 (Note: Repair R-74 destruct sample to be cut on 6/28/16).

## ***Non-Conformance Items / Corrective Actions***

- None Encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 6/27/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete pipe boot penetration log for Piezometer PZ-8 (Panel P21).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, and 6/24/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1, DS-2, DS-3, and DS-4. Reviewed laboratory data for extrusion weld destruct sample DSX-1 and DSX-2. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/27/16 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 6/27/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/27/16 |
| A5 – Subgrade Approval | Sheet 4 & ESI (6/27/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/27/16 |
| A7 – Panel Placement Log | Pages 3-4 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 6/27/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/27/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 5-7 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 6/27/16 |
| A10 – Repair Log | Page 4 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/27/16 |
| A11 – Conformance COC | | NA for 6/27/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 6/27/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 6/27/16 |
| A14 – Penetration & Edge Form | 6/27/16 Form | One boot penetration form completed for Piezometer PZ8. Note: no methane / spark testing conducted. |
| A16 – Notice of Non-Compliance | | NA - no non-compliance issues identified on 6/27/16 |
| A17 – Spark Testing Form | | NA – no spark testing completed on 6/27/16. Boot for Piezometer PZ8 completed. Methane / spark testing to be completed week of July 5, 2016. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 6/29/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0650 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #6**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for LLDPE repair activities to be completed on LLDPE geomembrane installed on 6/27/16. Note: No capping activities conducted on 6/28/16 due to inclement weather, and no new LLDPE was placed on 6/29/16 as soil subgrade was not approved.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI continuing with non-destructive testing (pressure testing) and repair activities for geomembrane panels P19 through P27 (installed on 6/27/16). Non-destructive testing was conducted on the remaining panel seams and the seams were pressurized to 30 psi and held for 5 minutes with less than 4 psi loss. Refer to *6/29/16 Seam Control Form* for additional details.
- A total of twenty-two repairs (R-82 through RP-103) were observed and fixed (according to the project specifications) from Panels P19 through P27. Refer to 6/29/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of two destruct samples were collected for laboratory analysis. Two fusion weld destruct samples, DS-5 and DS-6, were collected from Panel Seam P19 / P20 and Panel Seam P23 / P24, respectively. Additional details are outlined in the *Trial Weld Log* dated 6/29/16.
- The LLDPE pipe boot penetration for Gas Vent GV-5 was completed and extrusion welded. Note: no methane testing / spark testing completed. Methane / spark testing to be completed week of July 5, 2016.
- While ESI was conducting repairs, small areas of standing water were observed on the soil subgrade from Sta. 314+25 to approximate Sta. 313+75. Entact solidified the subgrade by adding calcium cement to the soils so that the wet areas were absorbed / removed. Additionally, minor modifications to the subgrade were completed to facilitate positive drainage off of SA-6 North.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 2 (Sheet #2) – Subgrade irregularity identified as R-98 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P26. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 2 Notice of Non-Compliance.*

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 6/29/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct samples results for DS-5 and DS-6.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, and 6/27/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1, DS-2, DS-3, and DS-4. Reviewed laboratory data for extrusion weld destruct sample DSX-1 and DSX-2. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/29/16 |
| A3 – Photo Log | Pages 1 – 4 | Total of 7 photos outlining pertinent daily observations and descriptions for 6/29/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/29/16 |
| A5 – Subgrade Approval | | NA - no subgrade approval for 6/29/16 |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/29/16 |
| A7 – Panel Placement Log | | NA – no LLDPE panels placed on 6/29/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/29/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 6-7 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 6/29/16 |
| A10 – Repair Log | Pages 4-5 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/29/16 |
| A11 – Conformance COC | | NA for 6/29/16 |
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 6/29/16 |
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 6/29/16 |
| A14 – Penetration & Edge Form | 6/29/16 Form | LLDPE pipe boot penetration form completed for Gas Vent GV-5. Note: methane / spark testing not completed (to be completed week of June 5, 2016). |
| A16 – Notice of Non-Compliance | Sheet 2 | One non-compliance issue identified on 6/29/16 and summarized on Sheet 2. |
| A17 – Spark Testing Form | | NA – no methane / spark testing completed on 6/29/16 for Gas Vent GV-5. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 6/30/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 78/95° F, Sunny, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1615 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #7**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) continuing east from Panel P27 installed on 6/27/16 (approximate Sta. 314+25). Material to be placed from Panel P27 running approximately 100 ft. east to approximate Sta. 313+25.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 314+25 (Panel P27 installed on 6/27/16) to approximate Sta. 313+25. Refer to *Soil Subgrade Approval* forms from 6/30/16 for additional details. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos 1 to 3 of the daily photo log for 6/30/2016, for supporting subgrade photos. During subgrade observation, AmecFW was also completing surveying to verify the subgrade elevations. The area was subsequently approved by AmecFW following review of the survey data.
- Following subgrade approval (including AmecFW completing the survey requirements for the soil subgrade), GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 314+25 (east of Panel P27) moving east to approximate Sta. 313+25. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/30/16 Photo Log for supporting photographs.
- After placement of GVL, LLDPE geomembrane was installed continuing from Panel P27 (installed on 6/27/16) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 314+25 (Panel P27) to approximate Sta. 313+25. A total of five panels were installed (P28, P29, P30, P31, P32. Note: During placement of Panel P30, the

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

roll of LLDPE terminated near the north end of SA-6 North, thus the remaining run of LLDPE was installed as P31. Panels P28, P29, and P31 ran the entire width of SA-6 North (approximately 215 ft.) from north to south.

- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 6/30/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 314+25, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 6/30/16 *Seam Control Form* for non-destructive testing details. Additionally, repair and extrusion weld activities were also conducted for Panels P27 through P32. Additional details are outlined on the 6/30/16 *Repair Log.*
- A total of thirty-one repairs (R-104 through R-134) were observed and fixed (according to the project specifications) from Panels P19 through P27. Refer to 6/30/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Note: Add on (AO) repairs completed for Panels P17, P18, and P19, as LLDPE length had to be increased along edges of SA-6 North.
- Following the placement of LLDPE geomembrane, ESI deployed the orange geocomposite drainage layer (GDL), over the installed LLDPE geomembrane. GDL was placed from Panel P11 (approximate Sta. 316+25), to east of Panel P19 (approximate Sta. 315+50). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/30/16 Photo Log for supporting photographs
- A total of four destruct samples were collected on 6/30/16. Three fusion weld destruct samples DS-7, DS-8, and DS-9 were collected from panel seams P13 / P14, P18 / R-105, and 18 / 19, respectively. One extrusion weld destruct sample, DSX-3, was collected from Panel P21 (R-79).

## ***Non-Conformance Items / Corrective Actions***

- None Encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log for 6/30/16. Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample results for DS-7, DS-8, DS-9, and DSX-3.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, and 6/29/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-6. Reviewed laboratory data for extrusion weld destruct sample DSX-1 and DSX-2. Laboratory results in compliance with project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/30/16 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 6/30/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/30/16 |
| A5 – Subgrade Approval | Sheet 5 & ESI (6/30/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 2-3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/30/16 |
| A7 – Panel Placement Log | Pages 4-5 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 6/30/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/30/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 7-8 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 630/16 |
| A10 – Repair Log | Pages 6-7 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/30/16 |
| A11 – Conformance COC | | NA for 6/30/16 |
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 6/30/16 |
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 6/30/16 |
| A14 – Penetration & Edge Form | | NA – no pipe boot penetrations completed on 6/30/16. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A16 – Notice of Non-Compliance | | NA - no non-compliance issues identified on 6/30/16 |
| A17 – Spark Test Form | | NA – no methane / spark testing completed on 6/30/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/1/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 78/95° F, Sunny, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1315 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #8** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) continuing east from Panel P32 installed on 6/30/16 (approximate Sta. 313+25). Material to be placed from Panel P32 running approximately 65 ft. east to approximate Sta. 312+60.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 313+25 (Panel P32 installed on 6/30/16) to approximate Sta. 312+60. Refer to *Soil Subgrade Approval* forms from 7/1/16 for additional details. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos 1 to 3 of the daily photo log for 7/1/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 313+25 (east of Panel P32) moving east to approximate Sta. 312+60. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/1/16 Photo Log for supporting photographs.
- After placement of GVL, LLDPE geomembrane was installed continuing from Panel P32 (installed on 6/30/16) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 313+25 (Panel P32) to approximate Sta. 312+60. A total of seven panels were installed (P33, P34, P35, P36, P37, and P38). Note: During placement of Panel P33 the roll of LLDPE terminated near the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P34. Similarly, during placement of Panel 36, the roll of LLDPE terminated

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

approximately 2/3 from the north end of SA-6 North, thus the remaining run of LLDPE was installed as P37. Panels P32, P35, and P38 ran the entire width of SA-6 North (approximately 220 ft.) from north to south.

- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/1/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 312+60, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/1/16 *Seam Control Form* for non-destructive testing details. Additionally, repair and extrusion weld activities were also conducted for Panel P29 (installed on 6/30/16) and Panels P33 to P38 (installed on 7/1/16). Additional details are outlined on the 7/1/16 *Repair Log.*
- A total of twenty-eight repairs (R-135 through R-162) were observed and fixed (according to the project specifications) from Panels P19 through P27. Refer to 7/1/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- ESI also completed a pipe boot for Well 115-S1-SO located on the Panel P28 / P29 seam. Additional details are provided in the pipe boot penetration form for 7/1/16. No methane / spark testing was conducted on the boot (to be completed on 7/6/16).
- Following the placement of LLDPE geomembrane, ESI deployed the orange geocomposite drainage layer (GDL), over the installed LLDPE geomembrane. GDL was placed from Panel P11 (approximate Sta. 316+25), to east of Panel P19 (approximate Sta. 315+50). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/30/16 Photo Log for supporting photographs
- A total of four destruct samples were collected on 7/1/16. Three (3) fusion weld destruct samples were collected – DS-11, DS-12, and DS-13 from Panel Seams P31 / P32, P34 / P35, and P36 / P38, respectively. One extrusion weld destruct sample – DSX-4 was collected from Panel P32 (Repair R-148).

## ***Non-Conformance Items / Corrective Actions***

- None Encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/1/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory data for destruct samples DS-11, DS-12, DS-13, and DSX-4.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, and 6/30/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-10. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-3. Laboratory results in compliance with project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 7/1/16 |
| A3 – Photo Log | Pages 1 – 6 | Total of 11 photos outlining pertinent daily observations and descriptions for 7/1/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/23/16 |
| A5 – Subgrade Approval | Sheet 6 & ESI (7/1/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/1/16 |
| A7 – Panel Placement Log | Page 5 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/1/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 7/1/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 12-13 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/1/16 |
| A10 – Repair Log | Pages 7-9 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/1/16 |
| A11 – Conformance COC | | NA for 7/1/16 |
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 7/1/16 |
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 7/1/16 |
| A14 – Penetration & Edge Form | 7/1/16 Form | Pipe boot completed for Well 115-W1-SO located along Panel P28 / P29. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues identified on 7/1/16 |
| A17 – Spark Testing Form | | NA – no spark testing completed on 7/1/16. Boot for Well 115-W1-SO completed. Methane / spark testing to be completed week of July 5, 2016. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/6/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 82/98° F, Sunny, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0655 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #9**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), 60-mil geomembrane liner (LLDPE) continuing east from Panel P38 installed on 7/1/16 (approximate Sta. 312+60). Material to be placed from Panel P38 running approximately 85 ft. east to approximate Sta. 311+75.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from Panel P19 (approximate Sta. 315+50), moving east up to Panel P27 (approximate Sta. 314+60). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/6/16 Photo Log for supporting photographs
- While ESI was deploying GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 312+60 (Panel P38 installed on 7/1/16) to approximate Sta. 311+75. Refer to *Soil Subgrade Approval* forms from 7/6/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 3 to 5 of the daily photo log for 7/6/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 312+60 (east of Panel P38) moving east to approximate Sta. 311+75. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

layer of geotextile was sewn along the seams (according to the project specifications). Refer to 7/6/16 Photo Log for supporting photographs.

- During deployment of GVL, the potential for rocks or other debris to become dislodged in the soil subgrade were observed. Additional walkover and observation activities were conducted along the GVL to attempt to identify any rocks or debris (>1/2") that may have been dislodged.
- After placement of GVL, LLDPE geomembrane was installed continuing from Panel P38 (installed on 7/1/16) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 312+60 (Panel P38) to approximate Sta. 311+75. A total of four panels were installed (P39, P40, P41, and P42). Note: During placement of Panel P39 the roll of LLDPE terminated near the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P40. Panels P41 and P42 ran the entire width of SA-6 North (approximately 220 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/6/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 311+75, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/6/16 *Seam Control Form* for non-destructive testing details. ESI completed a temporary pipe boot for Extraction Pump Station #1 and completed leistering of temporary patches to cover the LLDPE geomembrane. Repair (detailing) activities to be completed on 7/7/16.
- While GDL was being deployed, ESI also conducted, methane / spark testing for the pipe boots completed for Piezometer PZ8, Gas Vent GV-5, and Well 115-W1-SO. Prior to spark testing, methane testing was conducted to measure the concentration of methane present below the LLDPE geomembrane. During methane testing, a concentration of 0.0% (<1%) was measured for each of the pipe boots. Following the methane testing, spark testing was conducted by ESI for the vertical weld and pipe boot weld at the base of the penetration (i.e. welds not accessible for vacuum box testing).
- During the spark testing for Piezometer PZ8 a spark was observed at the top of the boot (outside of the 2 ft. boot requirement). Since this spark was outside of the required boot construction, the boot was subsequently cut at 2 ft. (thus removing the failed weld), and the remaining boot was retested with no sparks observed.
- During spark testing of Gas Vent GV-5 and Well 115-W1-SO, a spark was observed while testing the vertical weld and a small pinhole deficiency was observed in the weld. These areas will be grinded, rewelded, and retested on 7/7/16. Additional details are outlined in the *Spark Testing QA Forms* dated 7/6/16.
- No destruct samples collected on 7/6/16. Destruct samples to be cut on 7/7/16.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 3 (Sheet #3) – Failed spark test along vertical weld of Gas Vent GV-5
  - Failed spark test identified during spark testing of Gas Vent GV-5. Small pinhole deficiency identified in vertical weld. Weld to be grinded, re-welded, and re-tested on 7/7/16.
- Non-Conformance No. 4 (Sheet #4) – Failed spark test along vertical weld of Well 115-W1-SO
  - Failed spark test identified during spark testing of Well 115-W1-SO. Small pinhole deficiency identified in vertical weld. Weld to be grinded, re-welded, and re-tested on 7/7/16.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/6/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, and 7/1/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-13. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-4. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 7/6/16 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 7/6/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/6/16 |
| A5 – Subgrade Approval | Sheet 7 & ESI (7/6/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/6/16 |
| A7 – Panel Placement Log | Pages 5-6 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/6/16 |
| A8 – Destruct Seam Testing COC | | NA - no destruct samples collected on 7/6/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 14-16 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/6/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | NA – no repair activities conducted on 7/6/16 |
| A11 – Conformance COC | | NA for 7/6/16 |
| A12 – Destructive Seam Field Test | | NA - no destruct samples collected on 7/6/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 7/6/16 |
| A14 – Penetration & Edge Form | | NA – no pipe boots / penetrations completed on 7/6/16 |
| A16 – Notice of Non-Compliance | Sheets 3 & 4 | Two non-compliance issues identified on 7/6/16 during spark testing of pipe boots and summarized on Sheets 3 & 4 (7/6/16 Non-Compliance Forms). |
| A17 – Spark Test Log | 7/616 Spark Test Logs | Spark tests completed for Piezometer PZ8, Gas Vent GV-5, and Well 115-W1-SO. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/7/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 82/98° F, Overcast, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #10**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), 60-mil geomembrane liner (LLDPE), continuing east from Panel P42 installed on 7/6/16 (approximate Sta. 311+75). Material to be placed from Panel P42 running approximately 20 ft. east to approximate Sta. 311+55. Note: based on available prepared subgrade and inclement weather scheduled in the afternoon, ESI deployed one panel of GVL and one panel of LLDPE geomembrane so that the installed LLDPE was outside of the slope swales and depressed contours thus promoting positive drainage away from the installed material.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from Panel P27 (approximate Sta. 314+60), moving east up to Panel P36 / P37 (approximate Sta. 313+25). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/7/16 Photo Log for supporting photographs
- While GDL was being deployed, ESI also completed repair activities for Panels P39 to P42 (installed on 7/6/16). A total of thirty-seven repairs (R-163 through R-199) were observed and fixed (according to the project specifications) from Panels P39 through P42. Refer to 7/7/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of two (2) destruct samples were collected. One fusion weld destruct sample (DS-14) was collected from Panel P41 / P42 seam, and one extrusion weld sample (DSX-5) was collected from Panel P42, Repair R-179 for laboratory analysis.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While GDL and repair activities were being completed, ESI also conducted, methane / spark testing for the pipe boots repairs for Gas Vent GV-5, and Well 115-W1-SO. Based on the sparks observed during spark testing on 7/6/16, the areas were subsequently grinded, re-welded, and re-tested. Refer to 7/7/16 Photograph Log for supporting photos. Prior to spark testing, methane testing was conducted by AmecFW to measure the concentration of methane present below the LLDPE geomembrane. During methane testing, a concentration of 0.0% (<1%) was measured for each of the boots. Following the methane testing, spark testing was conducted by ESI for the vertical weld areas that were re-welded. During the re-test no sparks were observed and the retest spark test passed. Additional details are outlined in the *Spark Testing QA Forms* dated 7/6/16.
- Following the LLDPE repair activities, and deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 311+75 (Panel P42 installed on 7/6/16) to approximate Sta. 311+55. Refer to *Soil Subgrade Approval* forms from 7/7/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photo 9 of the daily photo log for 7/7/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement. Note: the approximate 20 ft. area of soil was approved so that an additional panel of LLDPE geomembrane could be deployed to allow the edges of the liner to be outside of the depressed contours in the event of afternoon rainstorms (positive drainage away from the installed LLDPE geomembrane).
- Following subgrade approval, one panel of GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications).
- After placement of GVL, one panel of LLDPE geomembrane was installed continuing from Panel P42 (installed on 7/6/16) and moving east. The panel was oriented from north to south (as proposed in the approved Panel Layout) and was installed from approximate Sta. 311+75 (Panel P42) to approximate Sta. 311+55. A total of one panel was installed (P43). Panel P43 ran the entire width of SA-6 North (approximately 230 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/7/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 312+60, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/7/16 *Seam Control Form* for non-destructive testing details. Additionally, repairs were marked and temporary patches were leistered in place for repair activities (i.e. detailing) to be completed on 7/8/16.
- ESI completed the boot / penetration construction for Extraction Pump Station #1 manhole and welded (detailed) the repairs. Note: Extraction Pump Station #1 manhole was located in a recessed contour of SA-6 North and repair activities were conducted to seal the LLDPE geomembrane as rainstorms were forecasted for the afternoon.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 5 (Sheet #5) – Subgrade irregularity identified as R-170 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P38. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 5 Notice of Non-Compliance.*
- Note: Failed spark test non-conformance details are outlined in the 7/6/16 Daily Report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/6/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory results for destruct samples DS-14 and DSX-5.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, and 7/6/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-13. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-4. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/7/16 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 7/7/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/7/16 |
| A5 – Subgrade Approval | Sheet 8 & ESI (7/7/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 3-4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/7/16 |
| A7 – Panel Placement Log | Page 6 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/7/16 |
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/7/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A9 – Seam/Non-Destruct. Test Log | Pages 16-17 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/7/16 |
| A10 – Repair Log | Pages 9-10 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/7/16 |
| A11 – Conformance COC | | NA for 7/7/16 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/7/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/7/16 |
| A14 – Penetration & Edge Form | | NA – Pipe boot for Access Manhole #2 to be completed on 7/8/16. |
| A16 – Notice of Non-Compliance | Sheet 5 | One non-compliance issue identified as subgrade irregularity on 7/7/16 and summarized on Sheet 5. |
| A17 – Spark Test Log | 7/6/16 Spark Test Logs | Spark tests logs for Gas Vent GV-5 and Well 115-W1-SO dated 7/6/16 updated for spark retests completed on 7/7/16. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/8/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 82/98° F, Overcast, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #11**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P43 installed on 7/7/16 (approximate Sta. 311+55). Material to be placed from Panel P43 running approximately 75 ft. east to approximate Sta. 310+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing repair activities for Panels P42 and P43 (Panel P43 installed on 7/7/16). A total of twelve repairs (R-200 through R-211) were observed and fixed (according to the project specifications) from the two panels. Refer to 7/8/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While LLDPE repair activities were being conducted, Langan and Entact conducted soil subgrade approval from approximate Sta. 311+55 (Panel P43 installed on 7/7/16) to approximate Sta. 310+80. Refer to *Soil Subgrade Approval* forms from 7/8/16 for additional details. During subgrade observation, the subgrade area was transversed in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 1 and 2 of the daily photo log for 7/8/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 311+55 (east of Panel P43) moving east to approximate Sta. 310+80.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 7/8/16 Photo Log for supporting photographs.
- During deployment of GVL, the potential for rocks or other debris to become dislodged in the soil subgrade were observed. Additional walkover and observation activities were conducted along the GVL to attempt to identify any rocks or debris (>1/2") that may have been dislodged.
- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P43 (installed on 7/7/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 311+55 (Panel P43) to approximate Sta. 310+80. A total of eight panels were installed (P44, P44A, P44B, P45, P46, P47, P48, and P49). Note: During placement of Panel P44 the roll of LLDPE terminated near the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P45. Similarly, during placement of Panel P47, the roll of LLDPE terminated near the center of SA-6 North, thus the remaining run of LLDPE was installed as P48. Panels P46 and P49 ran the entire width of SA-6 North (approximately 290 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/8/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 310+80, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/8/16 *Seam Control Form* for non-destructive testing details. Additionally, repairs activities were conducted for Panels P44 through P49 (installed on 7/8/16). These repair activities were conducted in addition to the repairs completed in the morning for Panels P42 and P43 (installed on 7/7/16).
- A total of twenty additional repairs (R-212 through R-223, R-225, R-227, R-228, R-229, and R-233 to R-236) were observed and fixed (according to the project specifications) from Panels P44 to P49. Refer to 7/8/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of one (1) destruct samples was collected. One extrusion weld sample (DSX-6) was collected from Panel P42, Repair R-180 for laboratory analysis. Additional destruct samples to be cut and collected on 7/11/16.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 6 (Sheet #6) – Subgrade irregularity identified as R-222 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P45. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 6 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/13/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory results for destruct sample DSX-6.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, and 7/7/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-13. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-5. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 7/8/16 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 7/8/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/8/16 |
| A5 – Subgrade Approval | Sheet 9 & ESI (7/8/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/8/16 |
| A7 – Panel Placement Log | Page 6-7 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/8/16 |
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/8/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 16-18 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/8/16 |
| A10 – Repair Log | Pages 10-12 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/8/16 |
| A11 – Conformance COC | | NA for 7/8/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/8/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/8/16 |
| A14 – Penetration & Edge Form | | NA – Pipe boot skirts completed, methane testing to be completed before finalizing welds and conducting spark testing. |
| A16 – Notice of Non-Compliance | Sheet 6 | One non-compliance issue (subgrade irregularity) identified on 7/8/16 and summarized on Sheet 6. |
| A17 – Spark Test Log | | NA – no spark test activities conducted on 7/8/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/11/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 72/80° F, Sunny, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** LLDPE Repair Activities & Destruct Samples | **TIME:** | 0645 – 0845 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #12** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of LLDPE repair activities (from Panels P44 to P49 installed on 7/8/16). Note: soil subgrade not approved for LLDPE placement as standing water / wet areas observed along subgrade from rainstorms over the weekend. Entact to solidify, rework, and re-compact soils for subgrade approval to be completed on 7/12/16. Note: the edge of the LLDPE geomembrane placed on 7/8/16 was pulled back until dry soil subgrade from below the liner was exposed (as shown in the 7/11/16 Photo Log). Soil to be dried, solidified, reworked, and re-compacted by Entact for approval on 7/12/16.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting repair activities for Panels P44 through P49 (panels installed on 7/8/16). A total of eight repairs (R-224, R-226, R-230, R-231, R-232, R-239, R-240, and R-241) were observed and fixed (according to the project specifications) from the two panels. Refer to 7/11/16 *Repair Report* for additional details. In general, the majority of the repairs were destruct samples that were collected for laboratory analysis and cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of four (4) destruct samples were collected from panels installed on 7/8/16. Three fusion weld destruct samples – DS-15, DS-16, and DS-17 were collected from Panel Seam P43 / P44, P46 / P47, and P45 / 46, respectively. Additionally, one extrusion weld destruct sample - DSX-7 was collected from Panel P44, Repair R-179 for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/11/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct results for DS-15, DS-16, DS-17, and DSX-7.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, and 7/8/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-14. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-6. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 7/11/16 |
| A3 – Photo Log | Pages 1 – 2 | Total of 4 photos outlining pertinent daily observations and descriptions for 7/11/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/11/16 |
| A5 – Subgrade Approval | | NA – no subgrade approved for LLDPE placement on 7/11/16 |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/11/16 |
| A7 – Panel Placement Log | | NA – no panels placed on 7/11/16 as no soil subgrade was not approved. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/11/16 |
| A9 – Seam/Non-Destruct. Test Log | | NA – no pressure testing conducted on 7/11/16 |
| A10 – Repair Log | Pages 12-13 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/11/16 |
| A11 – Conformance COC | | NA for 7/11/16 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/11/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/11/16 |
| A14 – Penetration & Edge Form | | NA – no boots / penetrations completed on 7/11/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues identified on 7/11/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 7/11/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/12/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 72/85° F, Sunny, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1500 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #13** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P49 installed on 7/8/16 (approximate Sta. 310+80). Material to be placed from Panel P49 running approximately 100 ft. east to approximate Sta. 309+75.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from Panel P36 / P37 (approximate Sta. 313+25), moving east up to Panel P42 (approximate Sta. 312+25). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/12/16 Photo Log for supporting photographs.
- While GDL was being deployed, ESI also completed the LLDPE pipe boot for Gas Vent GV-4. The boot was patched and welded (to be methane / spark tested later in the morning). Additional details are outlined in the Gas Vent GV-4 penetration log dated 7/12/16.
- ESI completed methane / spark testing for the LLDPE pipe boot for Pump Station #1 and Gas Vent GV-4. Prior to spark testing, Entact conducted methane testing to measure the concentration of methane present underneath the LLDPE geomembrane. A concentration of 0.0% (>1%) was measured for both boots. As such, ESI conducted spark testing along the base of the boot and the vertical weld. No sparks were observed during the spark test and both boots passed. Additional details are outlined in the *Spark Testing QA Forms* dated 7/12/16.
- Following the deployment of GDL and spark testing activities, Langan and Entact conducted soil subgrade approval from approximate Sta. 310+80 (Panel P49 installed on 7/8/16) to approximate Sta. 309+75. Refer to *Soil Subgrade Approval* forms from 7/12/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

generally free of any loose material greater than ½". Refer to Photos 7 to 9 of the daily photo log for 7/12/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement. Note: the approximate 20 ft. area of soil was approved so that an additional panel of LLDPE geomembrane could be deployed to allow the edges of the liner to be outside of the depressed contours in the event of afternoon rainstorms (positive drainage away from the installed LLDPE geomembrane).

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 310+80 (east of Panel P49) moving east to approximate Sta. 309+75. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 7/12/16 Photo Log for supporting photographs.
- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P49 (installed on 7/8/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 310+80 (Panel P49) to approximate Sta. 309+75. A total of eight panels were installed (P50, P51, P52, P53, P54, P55, P56, and P7). Note: During placement of Panel P51 the roll of LLDPE terminated near the approximate center of SA-6 North, thus the remaining run of LLDPE was installed as P52 and P53 (P52 and P53 remaining pieces of LLDPE from rolls previously used). Similarly, during placement of Panel P55, the roll of LLDPE terminated near the center of SA-6 North, thus the remaining run of LLDPE was installed as P56 & P57 (Panels P56 and P57 installed as remaining pieces of previously used LLDPE rolls). Panels P50 and P54 ran the entire width of SA-6 North (approximately 288 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/12/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 309+75, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/12/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P50 through P57 (installed on 7/12/16).
- ESI conducted repair activities for Panels P50 to P57 (installed on 7/12/16). A total of twenty-two repairs (R-237, R-238 and R-242 through R-261) were observed and fixed (according to the project specifications) from Panels P50 through P57. Refer to 7/12/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of three (3) destruct samples were collected. Three fusion weld destruct samples - DS-18, DS-19, DS-20 were collected from Panel Seams P49 / P50, P53 / P54, and P55 / P56 for laboratory analysis

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 7 (Sheet #7) – Subgrade irregularity identified as R-242 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P49 / P50. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 7 Notice of Non-Compliance.*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/12/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory results for destruct samples DS-18, DS-19, and DS-20.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, and 7/11/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-17. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-7. Laboratory results in compliance with project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/12/16 |
| A3 – Photo Log | Pages 1 – 8 | Total of 15 photos outlining pertinent daily observations and descriptions for 7/12/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/12/16 |
| A5 – Subgrade Approval | Sheet 10 & ESI (7/12/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/12/16 |
| A7 – Panel Placement Log | Pages 8-9 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/12/16 |
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/12/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A9 – Seam/Non-Destruct. Test Log | Pages 19-22 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/12/16 |
| A10 – Repair Log | Pages 13-14 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/12/16 |
| A11 – Conformance COC | | NA for 7/12/16 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/12/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/12/16 |
| A14 – Penetration & Edge Form | 7/12/16 Boot Form | Pipe boot for Gas Vent GV-4 and Piezometer PZ6 completed on 7/12/16. |
| A16 – Notice of Non-Compliance | Sheet 7 | One non-compliance issue identified as subgrade irregularity on 7/12/16 and summarized on Sheet 7. |
| A17 – Spark Test Log | 7/12/16 Spark Test Logs | Spark tests logs for Gas Vent GV-4 and Extraction Pump Station #1 dated 7/12/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/13/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 72/85° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #14**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth, Kale<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P55 / P56 / P57 installed on 7/12/16 (approximate Sta. 309+75). Material to be placed from Panel P55 / P56 / P57 running approximately 75 ft. east to approximate Sta. 309+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from Panel P42 (approximate Sta. 312+25), moving east through Panel P47 / P48 (approximate Sta. 311+10). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/13/16 Photo Log for supporting photographs.
- Following the deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 309+75 (Panel P55 / P56 / P57 installed on 7/12/16) to approximate Sta. 309+00. Refer to *Soil Subgrade Approval* forms from 7/13/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 3,4, and 5 of the daily photo log for 7/13/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 309+75 (east of Panel P55 / P56 / P57) moving east to approximate Sta. 309+00. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 7/13/16 Photo Log for supporting photographs.

- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P55 / P56 / P57 (installed on 7/12/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 309+75 (Panel P55 / P56 / P57) to approximate Sta. 309+00. A total of six panels were installed (P58, P59, P60, P61, P62, and P63). Note: During placement of Panel P59 the roll of LLDPE terminated near the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P60. Similarly, during placement of Panel P62, the roll of LLDPE terminated near the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P63. Panels P58 and P61 ran the entire width of SA-6 North (approximately 295 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/13/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 309+00, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/13/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P58 to P63 (installed on 7/13/16)
- ESI conducted repair activities for Panels 58 to P63 (installed on 7/13/16). A total of eleven repairs (R-262 through R-272) were observed and fixed (according to the project specifications) from Panels P58 through P63. Refer to 7/13/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of two (2) destruct samples were collected. Two fusion weld destruct samples - DS-21 and DS-22 were collected from Panel Seams P58 / P59 and P61 / P63, respectively, for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/13/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory results for destruct samples DS-21 and DS-22.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, and 7/12/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-20. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-7. Laboratory results in compliance with project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/13/16 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 7/13/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/13/16 |
| A5 – Subgrade Approval | Sheet 11 & ESI (7/13/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 4-5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/13/16 |
| A7 – Panel Placement Log | Pages 9-10 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/13/16 |
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/13/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 22-24 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/13/16 |
| A10 – Repair Log | Page 14 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/13/16 |
| A11 – Conformance COC | | NA for 7/13/16 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/13/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/13/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A14 – Penetration & Edge Form | | NA – No pipe boots / penetrations completed on 7/13/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 7/13/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 7/13/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/14/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 75/85° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1500 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #15**<br>**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth, Kale<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P62 / P63 installed on 7/13/16 (approximate Sta. 309+00). Material to be placed from Panel P62 / P63 running approximately 80 ft. east to approximate Sta. 308+20.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting repair activities for a wrinkle observed on Panel P50 / P51. A total of four repairs (R-273 through R-276) were observed and fixed (according to the project specifications) from Panels P50 and P51. Refer to 7/14/16 *Repair Report* for additional details. The observed wrinkles were cut to allow the geomembrane to conform to the subgrade, and the cut areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While repair activities were being conducted, Langan and Entact conducted soil subgrade approval from approximate Sta. 309+00 (Panel P62 / P63 installed on 7/13/16) to approximate Sta. 308+20. Refer to *Soil Subgrade Approval* forms from 7/14/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 1, 2, and 3 of the daily photo log for 7/14/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta.309+00 (east of Panel P62 / P63) moving east to approximate Sta. 308+20. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 7/14/16 Photo Log for supporting photographs.

- During deployment of GVL, the potential for rocks or other debris to become dislodged in the soil subgrade were observed. Additional walkover and observation activities were conducted along the GVL to attempt to identify any rocks or debris (>1/2") that may have been dislodged.
- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P62 / P63 (installed on 7/13/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 309+00 (Panel P62 / P63) to approximate Sta. 308+20. A total of five panels were installed (P64, P65, P66, P67, and P68). Note: During placement of Panel P66 the roll of LLDPE terminated approximately 2/3 from the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P67. Panels P64, P65, and P68 ran the entire width of SA-6 North (approximately 299 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/14/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 308+20, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/14/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P64 to P68 (installed on 7/14/16).
- ESI conducted repair activities for Panels P64 to P68 (installed on 7/14/16) in addition to the wrinkle repairs completed in the morning on Panels P50 / P51. A total of sixteen repairs (R-277 through R-292) were observed and fixed (according to the project specifications) from Panels P64 through P68. Refer to 7/14/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- ESI also completed the boot / penetration construction for Gas Vent GV-3 and Extraction Pump Cleanout 1. The boots were welded and sealed with methane / spark testing to be conducted at a later date.
- A total of three (3) destruct samples were collected. Two fusion weld destruct samples - DS-23 and DS-24 were collected from Panel Seams P64 / P65 and P66 / P68, respectively, for laboratory analysis. In addition, one extrusion weld destruct sample – DSX-8 was collected from Panel P61 (Repair R-270) for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/14/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory results for destruct samples DS-23, DS-24, and DSX-8.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, and 7/13/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-22. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-7. Laboratory results in compliance with project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/14/16 |
| A3 – Photo Log | Pages 1 – 6 | Total of 11 photos outlining pertinent daily observations and descriptions for 7/14/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/14/16 |
| A5 – Subgrade Approval | Sheet 12 & ESI (7/14/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/14/16 |
| A7 – Panel Placement Log | Page 10 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/14/16 |
| A8 – Destruct Seam Testing COC | Sheet 3 | Updated for destruct samples collected on 7/14/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 24-25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/14/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Pages 14-15 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/14/16 |
| A11 – Conformance COC | | NA for 7/14/16 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct samples collected on 7/14/16 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct sample summary updated with samples collected on 7/14/16 |
| A14 – Penetration & Edge Form | 7/14/16 Boot Forms | Pipe boot / penetrations completed for Gas Vent GV-3 and Extraction Pump Cleanout 1. To be methane / spark tested at later date. |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 7/14/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 7/14/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 7/15/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 80/95° F, Partly Cloudy, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite Drainage Layer (GDL) | **TIME:** | 0645 – 1630 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #16** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth, Kale Novalis<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainager layer (GDL) over approved LLDPE geomembrane. Note: no soil subgrade approved and no LLDPE geomembrane installed on 7/15/16. Next area of subgrade still being prepared, graded, and compacted by Entact (to be surveyed by Maser).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from Panel P47 / P48 (approximate Sta. 311+10) to Panel P66 (approximate Sta. 308+35) along northern end of cap. Note: GDL rolls were approximately 200 ft. in length and covered approximately 2/3 of the cap (north to south). As such, GDL was deployed along the northern half to Panel P66. The southern end of the cap was covered to Panel P63 (approximate Sta. 309+00). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/15/16 Photo Log for supporting photographs.

## ***Non-Conformance Items / Corrective Actions***

- None encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/15/16). No LLDPE paperwork to be completed as no subgrade was approved and no LLDPE geomembrane was installed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, and 7/14/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-24. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-8. Laboratory results in compliance with project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/15/16 |
| A3 – Photo Log | Pages 1 – 2 | Total of 3 photos outlining pertinent daily observations and descriptions for 7/15/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/15/16 |
| A5 – Subgrade Approval | | NA – no subgrade approved for LLDPE placement on 7/15/16 |
| A6 – Trial Weld Log | | NA – no trial welds completed on 7/15/16 |
| A7 – Panel Placement Log | | NA – no LLDPE panels placed on 7/15/16 |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 7/15/16 |
| A9 – Seam/Non-Destruct. Test Log | | NA – no non-destructive testing conducted on 7/15/16 |
| A10 – Repair Log | | NA – no LLDPE repair activities conducted on 7/15/16 |
| A11 – Conformance COC | | NA for 7/15/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 7/15/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 7/15/16 |
| A14 – Penetration & Edge Form | | NA – no penetration / pipe boots completed on 7/15/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 7/15/16 |
| A17 – Spark Test Log | | NA – no spark testing completed on 7/15/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/18/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 78/85° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 0845 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #17** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth, Kale<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainager layer (GDL) over approved LLDPE geomembrane. Note: no soil subgrade approved and no LLDPE geomembrane installed on 7/18/16. Next area of subgrade still being prepared, graded, and compacted by Entact (to be surveyed by Maser).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed along the southern end of SA-6 North from Panel P63 (approximate Sta. 309+00) to Panel P66 (approximate Sta. 308+35) along southern end of cap. Note: GDL rolls were approximately 200 ft. in length and covered approximately 2/3 of the cap (north to south). As such, GDL was deployed along the southern half to Panel P66 (northern half previously covered with GDL on 7/15/16). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/18/16 Photo Log for supporting photographs.

## ***Non-Conformance Items / Corrective Actions***

- None encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/18/16). No LLDPE paperwork to be completed as no subgrade was approved and no LLDPE geomembrane was installed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, and 7/15/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-24. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-8. Laboratory results in compliance with project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/18/16 |
| A3 – Photo Log | Page 1 | Total of 2 photos outlining pertinent daily observations and descriptions for 7/18/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/18/16 |
| A5 – Subgrade Approval | | NA – no subgrade approved for LLDPE placement on 7/18/16 |
| A6 – Trial Weld Log | | NA – no trial welds completed on 7/18/16 |
| A7 – Panel Placement Log | | NA – no LLDPE panels placed on 7/18/16 |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 7/18/16 |
| A9 – Seam/Non-Destruct. Test Log | | NA – no non-destructive testing conducted on 7/18/16 |
| A10 – Repair Log | | NA – no LLDPE repair activities conducted on 7/18/16 |
| A11 – Conformance COC | | NA for 7/18/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 7/18/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 7/18/16 |
| A14 – Penetration & Edge Form | | NA – no penetration / pipe boots completed on 7/18/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 7/18/16 |
| A17 – Spark Test Log | | NA – no spark testing completed on 7/18/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/25/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 85/93° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #18**<br>**AmecFW**: Dave Ambrose, Josh Boynton<br>**Langan:** Dan Bosworth, Kale Novalis<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P68 installed on 7/14/16 (approximate Sta. 308+15). Material to be placed from Panel P68 running approximately 95 ft. east to approximate Sta. 307+20.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 308+15 (Panel P68 installed on 7/14/16) to approximate Sta. 307+20. Refer to *Soil Subgrade Approval* forms from 7/25/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 1, 2, and 3 of the daily photo log on 7/25/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 308+15 (east of Panel P68) moving east to approximate Sta. 307+20. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 7/25/16 Photo Log for supporting photographs.
- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P68 (installed on 7/14/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 308+15 (Panel P68) to approximate Sta. 307+20. A total of seven panels were installed (P69, P70, P71, P72, P73, P74 and P75).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Note: During placement of Panel P69 the roll of LLDPE terminated near the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P70 and P71 (P70 and P71 remaining pieces of LLDPE from rolls previously used). Similarly, during placement of Panel P73, the roll of LLDPE terminated near the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P74. Panels P72 and P75 ran the entire width of SA-6 North (approximately 280 ft.) from north to south.

- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/25/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 307+20, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 7/25/16 *Seam Control Form* for non-destructive testing details.
- ESI conducted repair activities for Panels 68 to P75 (installed on 7/25/16). A total of twenty-six repairs (R-293 through R-318) were observed and fixed (according to the project specifications) from Panels P68 through P75. Refer to 7/25/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications (Note: vacuum box testing not completed for all repairs. To be finished on 7/26/16).
- ESI also completed the pipe boot construction for Extraction Pump Cleanout Well 2.
- A total of two (3) destruct samples were collected. Two fusion weld destruct samples were collected – DS-25 and DS-26 were collected from Panel Seams P69 / P69 and P72 / P74, respectively. One extrusion weld destruct sample – DSX-9 was also collected from patch repair R29 (Panel P72) for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/25/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete boot penetration log for Extraction Pump Cleanout, Well 2
- Review laboratory results for destruct samples DS-25, DS-26, and DSX-9.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, and 7/18/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-24. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-8. Laboratory results in compliance with project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/25/16 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 7/25/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/25/16 |
| A5 – Subgrade Approval | Sheet 13 & ESI (7/25/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/25/16 |
| A7 – Panel Placement Log | Pages 10-11 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/25/16 |
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/25/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25-28 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/25/16 |
| A10 – Repair Log | Pages 15-16 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/25/16 |
| A11 – Conformance COC | | NA for 7/25/16 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/25/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/25/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A14 – Penetration & Edge Form | 7/25/16 Boots | Pipe boot penetration log completed for Extraction Pump Cleanout Well 2 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 7/25/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 7/25/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/27/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/98° F, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1615 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #19**<br>**AmecFW**: Dave Ambrose, Josh Boynton<br>**Langan:** Dan Bosworth<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P75 installed on 7/25/16 (approximate Sta. 307+20). Material to be placed from Panel P75 running approximately 80 ft. east to approximate Sta. 306+40.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 307+20 (Panel P75 installed on 7/25/16) to approximate Sta. 306+40. Refer to *Soil Subgrade Approval* forms from 7/27/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and one wet / soft area was identified at the top of the western slope of the utility corridor. The wet area was identified underneath the edge of the GVL panel (previously installed on 7/25/16). The GVL was pulled back and the soil subgrade was exposed. The wet area was re-worked by Entact and calcium cement was added to solidify the soil. Based on visual observation, the remaining soil subgrade (along with the re-worked wet area) appeared to be firm and unyielding with no other soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 1 to 4 of the daily photo log for 7/27/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 307+20 (east of Panel P75) moving east to approximate Sta. 306+40. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to the 7/27/16 Photo Log for supporting photographs.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P75 (installed on 7/25/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 307+20 (Panel P75) to approximate Sta. 306+40. A total of five panels were installed (P76, P77, P78, P79, and P80). Note: During placement of Panel P77 the roll of LLDPE terminated near the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P78. Panels P76, P79, and P80 ran the entire width of SA-6 North (approximately 270 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/27/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 306+40, ESI began to conduct non-destructive testing (pressure testing) in accordance with the project specifications. Seams were pressurized to 30 psi and held for 5 minutes with less than 5 psi loss. Refer to the 7/27/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P75 to P80 (installed on 7/25/16 and 7/27/16)
- ESI conducted repair activities for Panel P75 (installed on 7/25/16), and Panels P76 through P80 (installed on 7/27/16). A total of forty-three repairs (R-319 through R-361) were observed and fixed (according to the project specifications) from Panels P75 through P80. Refer to 7/27/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While repair activities were being conducted, ESI also completed methane / spark testing for Piezometer PZ6 and Extraction Well 1. Prior to spark testing methane testing was conducted at each location and 0.0% methane was recorded. As such, spark testing was then conducted and no sparks were observed along the base of the boot or vertical weld for both boots. Refer to the *Spark Testing Forms* from 7/27/16 for additional details.
- A total of two (2) destruct samples were collected on 7/27/16. One fusion weld destruct samples - DS-27 was collected from Panel Seams P75 / P76, for laboratory analysis. Additionally, one extrusion weld sample – DSX-10 was collected from Panel P75 Repair R-320.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 8 (Sheet #8) – Subgrade irregularity identified as R-328 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P71 / P72. Stone was subsequently removed, and hole was patched/repaired following project specs as further described in *Sheet 8 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/27/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory results for destruct samples DS-27 and DSX-10.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, and 7/25/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-24. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-8. Laboratory samples DS-25, DS-26, and DSX-9 still pending.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/27/16 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 7/27/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/27/16 |
| A5 – Subgrade Approval | Sheet 14 & ESI (7/27/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 5-6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/27/16 |
| A7 – Panel Placement Log | Pages 11-12 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/27/16 |
| A8 – Destruct Seam Testing COC | Sheet 2 | Updated for destruct samples collected on 7/27/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 28-30 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/27/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Pages 16-19 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/27/16 |
| A11 – Conformance COC | | NA for 7/27/16 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct samples collected on 7/27/16 |
| A13 – Destruct. Sample Summary | Page 2 | Destruct sample summary updated with samples collected on 7/27/16 |
| A14 – Penetration & Edge Form | 7/27/16 Pipe Boot Forms | One pipe boot / penetration completed for Well 115-E5-S0 |
| A16 – Notice of Non-Compliance | Sheet 8 | One subgrade irregularity identified and recorded on Sheet 8 Notice of Non-Compliance |
| A17 – Spark Test Log | 7/27/16 Spark Test Logs | Two spark tests completed for pipe boots Piezometer PZ6 and Extraction Pumpout Well 1 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/28/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 78/95° F, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1745 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #20** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Dave Ambrose, Josh Boynton<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT** / **ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P80 installed on 7/27/16 (approximate Sta. 306+40). Material to be placed from Panel P80 running approximately 100 ft. east to approximate Sta. 305+40.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 306+40 (Panel P80 installed on 7/27/16) to approximate Sta. 305+40. Refer to *Soil Subgrade Approval* forms from 7/28/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 1, 2, and 3 of the daily photo log for 7/28/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 306+40 (east of Panel P80) moving east to approximate Sta. 305+40. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to the 7/28/16 Photo Log for supporting photographs.
- While GVL was being installed, Entact and ESI conducted spark testing for Gas Vent GV-3, and Extraction Pumpout Well #2. Prior to spark testing, methane testing was conducted by Entact and a concentration of 0.0% was measured at each boot. As such, spark testing was subsequently completed, and no sparks were observed during the test (i.e. spark test passed). Additional details regarding the

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

methane / spark testing are provided in the 7/28/16 *Spark Test Logs*.

- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P80 (installed on 7/27/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 306+40 (Panel P80) to approximate Sta. 305+40. A total of eight panels were installed (P81, P82, P83, P84, P85, P86, P87, and P88). Note: During placement of Panel P81 the roll of LLDPE terminated near the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P82. Similarly, during placement of Panel P84 the roll of LLDPE terminated near the southern end of SA-6, thus the remaining run of LLDPE was installed as Panel P85. Panel P87 also terminated near the approximate center of SA-6 North, thus the remaining LLDPE run was installed as Panel P88. Panels P83 and P86 ran the entire width of SA-6 North (approximately 260 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 7/28/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 305+40, ESI began to conduct non-destructive testing (pressure testing) in accordance with the project specifications. Seams were pressurized to 30 psi and held for 5 minutes with less than 5 psi loss. Refer to the 7/28/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P80 to P88 (installed on 7/27/16 and 7/28/16)
- ESI conducted repair activities for Panel P80 (installed on 7/27/16), and Panels P81 through P88 (installed on 7/28/16). A total of twenty-nine repairs (R-362 through R-390) were observed and fixed (according to the project specifications) from Panels P80 through P88. Refer to 7/27/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- Laboratory results for destruct sample DS-26 were received and two of the coupons were reported as EPA Break Classificaion Code “AD BRK”. Although the coupons met the peel strength requirements, since the break was reported at the weld and not considered a film tearing bond (FTB), the sample was considered a failed sample and reported as a non-conformance item.
- No destruct samples were collected due to the forecasted storms at the end of the day. Destruct samples to be cut on 8/1/16 (rain forecast for 7/29/16 – no LLDPE activities anticipated).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 9 (Sheet #9) – Failed destruct sample DS-26 collected from Panel P72 / P74
    - Destruct sample DS-26 failed 2/5 coupons as the weld breaks were reported as “AD BRK” under the EPA Break Classification Code. Although the coupons achieved the required peel / shear strength parameters, since the break occurred at the weld and was not considered an FTB, the sample failed.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/28/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, and 7/27/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-27. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-10. Laboratory results in compliance with project specifications with the exception of destruct sample DS-26 (recorded as Non-Conformance #9).

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 7/28/16 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 7/28/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/28/16 |
| A5 – Subgrade Approval | Sheet 15 & ESI (7/28/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/28/16 |
| A7 – Panel Placement Log | Pages 12-13 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 7/28/16 |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 7/28/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 31-33 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 7/28/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Pages 19-20 | One repair log provided by ESI and confirmed by Langan for repairs completed for 7/28/16 |
| A11 – Conformance COC | | NA for 7/28/16 |
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 7/28/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 7/28/16 |
| A14 – Penetration & Edge Form | 7/28/16 Pipe Boot Form | Two pipe boot / penetrations completed for Utility Corridor Drainage Pipe and Extraction Pump Station Manhole #2 |
| A16 – Notice of Non-Compliance | Sheet 9 | One failed destruct sample: DS-26 recorded on 7/28/16. Additional details provided in Non-Conformance Log Sheet #9 |
| A17 – Spark Test Log | 7/28/16 Spark Test Logs | Spark testing completed on 7/28/16 for Gas Vent GV-3 and Extraction Pumpout Well #2 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

**Site Observation Report Day #20 (7/28/16) Attachment:**

*Response to E-mail dated August 3, 2016, transmitting amended/clarified pages of June Monthly Progress Report*

## Graham, Stephanie

**From:** Clifford, Joseph T <joseph.clifford@amecfw.com>
**Sent:** Friday, August 05, 2016 2:02 PM
**To:** Graham, Stephanie; Ambrose, David M
**Subject:** FW: Resolution of the SA-6 North Anomalous Destruct Sample

**From:** Clifford, Joseph T
**Sent:** Wednesday, August 03, 2016 4:51 PM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>; Kim Bell Hosea (k.bell@cea-enviro.com) <k.bell@cea-enviro.com>
**Cc:** Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>
**Subject:** Resolution of the SA-6 North Anomalous Destruct Sample

Steve/Kim,

I am sending this email on behalf of Honeywell and in response to the technical question raised during our biweekly technical call on Tue Aug 2.

Specifically, it was asked that Honeywell provide an update to a reported geomembrane destruct sample failure on a fusion weld that was identified by Langan as part of their standard 3rd party Quality Assurance (QA) testing procedures. It is noted that the failed sample met the strength requirement but the "inside" weld failed in such a manner as to be classified as a failure by the geotechnical testing lab.

The approved 100% Design Specifications and the QA Plan describe the procedures to be followed in the event of a failed destruct sample. Langan and the Amec EOR instructed the contractor to collect and run additional destruct samples 10 feet either side of the failed test. In addition an additional sample was collected from the sample for offsite testing from the location that yielded the lower field strength.

Both field tests and the supplemental offsite laboratory test passed. The contractor subsequently placed a single patch that encompasses all three destruct sample locations in accordance with the approved 100% Design. Langan observed the repair and the passing vacuum testing of the patch.

Lastly, we want to emphasize that this entire approach is not only consistent with the 100% Design, but is also industry practice, and considered a routine item when dealing with geomembrane liner installations of this scale.

Both the Langan QA manager and Amec EOR consider that the geomembrane in this location meets the specified requirements. The results will be reported and documented as part of the routine repair log as well as the next monthly progress report and final RAR documentation.

Please let us know if you have any other questions on this item.

Thank you. -Joe




This message is the property of Amec Foster Wheeler plc and/or its subsidiaries and/or affiliates and is intended only for the named recipient(s). Its contents (including any attachments) may be confidential, legally privileged or otherwise protected from disclosure by law. Unauthorised use, copying, distribution or disclosure of any of it may be unlawful and is strictly prohibited. We assume no responsibility to persons other than the intended named recipient(s) and do not accept liability for any errors or omissions which are a result of email transmission. If you have received this message in error, please notify us immediately by reply email to the sender and confirm that the original message and any attachments and copies have been destroyed and deleted from your system. This disclaimer applies to any and all messages originating from us and set out above. If you do not wish to receive future unsolicited commercial electronic messages from us, **please forward this email to: unsubscribe@amecfw.com and include "Unsubscribe" in the subject line**. If applicable, you will continue to receive invoices, project communications and similar factual, non-commercial electronic communications.

Please click http://amecfw.com/email-disclaimer for notices and company information in relation to emails originating in the UK, Italy or France.

**August 5, 2016 Honeywell e-mail:**
**080116 June 2016 SA-6 and SA-7 Combined Progress Report 21319**
*(Attachment 11: Capping Update)*

## Graham, Stephanie

**From:** Hague, William
**Sent:** Friday, August 05, 2016 11:20 AM
**To:** Graham, Stephanie
**Subject:** FW: 080116 June 2016 SA-6 and SA-7 Combined Progress Report 21319
**Attachments:** Well 115-W6-SO Spark Test Log.pdf; Gas Vent GV-6 Spark Test Log.pdf; DRAFT DR_LLDPE Day#4_062416_RL Rev.docx; Piezometer PZ10 Spark Test Log.pdf

**From:** Hague, William
**Sent:** Friday, August 05, 2016 9:57 AM
**To:** 'Kim Hosea'; RGTSpecialMaster@aol.com
**Cc:** joseph.clifford@amecfw.com; Michael.Daneker@APORTER.COM; Jeremy.Karpatkin@aporter.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom; Kaouris, Maria; Morris, John; AAlcorn@tpmlaw.com; KMillian@tpmlaw.com; CPravlik@tpmlaw.com; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mhogan@thewalshfirm.com; HRuiz@TheWalshFirm.com; lwalsh@thewalshfirm.com; Mojka, John; mmcwatters@louisberger.com; bdavis@tpmlaw.com
**Subject:** RE: 080116 June 2016 SA-6 and SA-7 Combined Progress Report 21319

Kim,

In response to your questions on the boot testing information provided in the June 2016 Study Areas 6 and7 Combined Monthly Progress Report, please see the following clarifications:

.

- Langan has clarified the dates of methane testing and spark testing. Langan Site Observation Report dated 6/24/16 (4 pages is attached with redline/strikeout).
- The three individual BOOT LOG QA forms (R-1/R-7/R-38) for the first three boots completed by Langan are attached.
- Regarding the question on the explanation of abbreviations.

    - **“SEOS”** represents the **South End of Seam** which refers to the southern edge of the SA-6 North Cap. The edge of the cap is used as a reference point to record and document the repair distances, panel lengths, etc. For example, if a repair was completed 10 ft. from the south edge of the cap, it is recorded on the repair report as 10 ft. north of SEOS.

    - Similarly, **“NEOS”** represents the **North End of Seam**, or northern edge of SA-6 North.

- Langan and AmecFW both disagree with the Plaintiffs request that the boot on Well-W6-S0 should be classified as a “Non Compliance” based on not performing the spark test. Specification 02372 was amended to include the spark testing. The amended specification provides for visual inspection of an extrusion weld if spark testing is not feasible due to the methane readings consistent with standard

industry practice. The specification was followed and both the methane reading and visual observation are noted on the Boot Log QA form R-7.

- Amec/Langan confirm that Plaintiffs understanding of the pipe boot penetrations on the daily reports is correct.

- The Amec portion of the Combined Report-Section F, 9th bullet will be amended to indicate that **"Spark testing was conducted on two boots that had methane reading of <1%. Visual inspection of the extrusion weld was performed on Well 115-W6-SO boot due to methane > 1%."**

Honeywell will issue an this email as an attachment to the next Study Areas 6 and 7 Combined Monthly Progress/Highlights Report to document these clarifications.

Let us know if you have any other questions on this item.

Regards,

Bill

**William J. Hague P.E.**

Honeywell
Director - Remediation Design & Construction
Corporate HSE&R
115 Tabor Road
Morris Plains, NJ 07950
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

---

**From:** Kim Hosea [mailto:k.hosea@cea-enviro.com]
**Sent:** Monday, August 01, 2016 3:01 PM
**To:** RGTSpecialMaster@aol.com
**Cc:** joseph.clifford@amecfw.com; Michael.Daneker@APORTER.COM; Jeremy.Karpatkin@aporter.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom; Hague, William; Kaouris, Maria; Morris, John; AAlcorn@tpmlaw.com; KMillian@tpmlaw.com; CPravlik@tpmlaw.com; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mhogan@thewalshfirm.com; HRuiz@TheWalshFirm.com; lwalsh@thewalshfirm.com; Mojka, John; mmcwatters@louisberger.com; bdavis@tpmlaw.com
**Subject:** 080116 June 2016 SA-6 and SA-7 Combined Progress Report 21319

We have reviewed the Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-06 and have the following comments and requests for additional information.

Section F, Capping Operations, states that three sparks tests of initial boot welds were conducted in June. The documentation provided in Attachment 11 – Capping Update does not support this statement. The Repair Report includes entries regarding three pipe boot penetrations:

- Repair No. 1 – Panel Number P-1, 35'North of SEOS & 8'W
- Repair No. 7 – 15'N of S EOS (PB 6")
- Repair No. 38 – Panel Number 11, 83' N of SEOS (8" Pipe)

We understand that the locations as shown on the Repair Report correspond to the pipe boot penetrations described in the Daily Reports. If our understanding is incorrect, please provide a drawing showing the panel layout and a description of the terms "SEOS" and "EOS."

While Section F, Capping Operations, states that three sparks tests of initial boot welds were conducted in June, the June 24, 2016, Site Observation Report, included in Attachment 11, indicates that only 2 of the 3 installed boots were spark tested. The Site Observation Report states that methane testing was conducted at Well 115-W6-SO, GV-6, and Piezometer PZ-10. Per the specifications, due to methane concentrations of >1.0%, no spark testing was conducted of the Well 115-W6-SO boot. Spark tests were conducted at GV-6 and PZ10 (methane <1%) and passed. Thus, based on Langan's Site Observation Report, only two spark tests were conducted in June. Section F should accurately reflect the testing that was conducted and the results.

The Repair Report, included in Attachment 11, contains entries regarding vacuum testing, but does not contain any entries for spark testing. Completed spark tests should be documented on the Repair Report and, in the event that methane concentrations are detected >1%, the lack of spark testing should be documented on the Summary of Non-Compliance & Corrective Action Forms. In addition, the QA/QC logs for the spark testing should be included in Attachment 11.

Please let me know if you have any questions or require additional information.

Thank you –

Kim Bell Hosea
President
Carpenter Environmental Associates, Inc.
610 County Route 1, Unit 2F
Pine Island, New York 10969

k.hosea@cea-enviro.com
(O) 845-781-4844 ext. 309
(F) 845-782-5591
(M) 862-812-3397

---

**From:** Graham, Stephanie [mailto:Stephanie.Graham@honeywell.com]
**Sent:** Thursday, July 14, 2016 4:27 PM
**To:** RGTSpecialMaster@aol.com
**Cc:** joseph.clifford@amecfw.com; Michael.Daneker@APORTER.COM; Jeremy.Karpatkin@aporter.com; Kim Hosea <k.hosea@cea-enviro.com>; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom <tom.byrne@honeywell.com>; Hague, William <william.hague@honeywell.com>; Kaouris, Maria <Maria.Kaouris@Honeywell.com>; Morris, John

<John.Morris@honeywell.com>; AAlcorn@tpmlaw.com; KMillian@tpmlaw.com; CPravlik@tpmlaw.com; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mhogan@thewalshfirm.com; HRuiz@TheWalshFirm.com; lwalsh@thewalshfirm.com; Mojka, John <John.Mojka@Honeywell.com>; mmcwatters@louisberger.com; bdavis@tpmlaw.com
**Subject:** June 2016 SA-6 and SA-7 Combined Progress Report

Attached please find the **June 2016 SA-6 and SA-7 Combined Progress Report.**

Please note that these files have also been made available for download on the Louis Berger SharePoint Site.

Thank you,

Stephanie Graham

**Amec Foster Wheeler**
c/o Honeywell
115 Tabor Road
Morris Plains, New Jersey 07950
Phone: 973-455-4209

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

**SITE OBSERVATION REPORT**

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 6/24/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1545 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #4**
**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) continuing east from Panel P12 / P13 installed on 6/23/16 (approximate Sta. 316+50). Material to be placed from Panel P12 / P13 running approximately 75 ft. east to approximate Sta. 315+75.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 316+50 (Panel P12 / P13 installed on 6/23/16) to approximate Sta. 315+75. Refer to *Soil Subgrade Approval* forms from 6/24/15 for additional details. Based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos 1 to 3 of the daily photo log for 6/24/2016, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications as verified by AmecFW
- GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 316+50 (east of Panel P12 / P13) moving east to approximate Sta. 315+75. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 6/24/16 Photo Log for supporting photographs.
- While GVL was being deployed, ESI also continued patch / repair work for the panels installed on 6/23/16 (Panels P8 to P13). Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (6/24/16).
- In addition, methane testing was conducted for the pipe boots completed for Well 115-W6-SO,

Deleted: / spark

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Piezometer PZ10, and Gas Vent GV-6. Methane testing was conducted by AmecFW to measure the concentration of methane present below the LLDPE geomembrane. During methane testing of Well 115-W6-SO, a concentration of 1.4% (greater than 1%) was measured. No spark testing was conducted on Well 115-W6-SO due to the measured methane concentration. Instead, the weld was visually observed for deficiencies and none were noted.

Deleted: Prior to spark testing, m

- Methane testing for PZ10 and Gas Vent GV-6 yielded methane concentrations of 0.8% and 0.0%, respectively (<1%). Following the methane testing, spark testing was conducted by ESI for the vertical weld and pipe boot weld at the base of the penetration (i.e. welds not accessible for vacuum box testing). No sparks were observed during the test, and both boots passed. Additional details are outlined in the *Spark Testing QA Form Sheets #1-3*.
- After placement of GVL, LLDPE geomembrane was installed continuing from Panel P12 / P13 (installed on 6/23/16) and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 316+50 (Panel P12 / P13) to approximate Sta. 315+75. A total of six panels were installed (P14, P15, P16, P17, P18, and P19). Note: During placement of panel P15, the roll of LLDPE terminated approx. 2/3 from the north of the cap, thus the remaining run of LLDPE was installed as P16. Panels P14, P17, P18, and P19 ran the entire width of SA-6 North (approximately 192 ft.) from north to south.
- Adjacent geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 6/24/16 *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 315+75, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 6/24/16 *Seam Control Form* for non-destructive testing details. Additionally, repair and extrusion weld activities were also conducted for Panels P14 through P19. Additional details are also outlined on the 6/24/16 *Repair Log*.
- A total of thirty repairs (RP-44 through RP-73) were observed and fixed (according to the project specifications) from Panels P14 through P19. Refer to 6/24/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Note: vacuum box testing not completed for all welds. To be continued on 6/27/16.
- A total of two destruct samples were collected for laboratory analysis by Entact / ESI. One fusion weld destruct sample DS-4 (Panel P15 / P17 seam) was collected for laboratory analysis. Additionally, one extrusion weld sample DSX-2 (Panel P10) was also collected for laboratory analysis.

***Non-Conformance Items / Corrective Actions***

- None Encountered

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 6/24/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample data (once received from laboratory).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16 and 6/23/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1, DS-2, and DS-3. Reviewed laboratory data for extrusion weld destruct sample DSX-1.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no material delivered on 6/24/16 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 6/24/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 6/24/16 |
| A5 – Subgrade Approval | Sheet 3 & ESI (6/24/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 6/24/16 |
| A7 – Panel Placement Log | Pages 2&3 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 6/24/16 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated for destruct samples collected on 6/24/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 4 to 6 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 6/24/16 |
| A10 – Repair Log | Pages 2 to 3 | One repair log provided by ESI and confirmed by Langan for repairs completed for 6/24/16 |
| A11 – Conformance COC | | NA for 6/24/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 1 | Updated with destruct samples collected on 6/24/16 |
| A13 – Destruct. Sample Summary | Page 1 | Destruct sample summary updated with samples collected on 6/24/16 |
| A14 – Penetration & Edge Form | Sheets 1 to 3 | Pipe boot skirts completed, methane testing completed for Piezometer PZ10, Well 115-W6-SO and Gas Vent GV-6 as outlined on the Sheets 1 to 3. |
| A16 – Notice of Non-Compliance | | NA - no non-compliance issues identified on 6/24/16. |
| A17 – Methane / Spark Testing Log | Sheets 1 to 3 | Methane testing completed for Piezometer PZ10, Well 115-W6-SO, and Gas Vent GV-6. Spark testing completed for Piezometer PZ10 and Gas Vent GV-6 |

**Deleted:** / spark

**Deleted:** / spark

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Honeywell

# STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Piezometer PZ10 located at approximate center of SA-6 North Cap on Panel P1 (approximately 35 ft. north of Panel P1 / P2 seam and 8 ft. west). Identified as R-1 on *As Built* and *Repair Report*.

**Date:** 6/24/16 **Repair Number:** R-1

**Boot Log QA Form (cross-reference):** 6/23/16 Piezometer PZ10 Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0925

*% Methane* 0.8%

☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**: ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 6/23/16. Methane / spark testing completed on 6/24/16 by ESI. Methane testing yielded concentration of 0.8%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:**

Honeywell

# STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Well 115-W6-SO located near southern end of SA-6 North Cap on Panel P5 / P6 seam (approximately 15 ft. north of southern end of cap). Identified as R-7 on *As Built* and *Repair Report*.

**Date:** 6/24/16 **Repair Number:** R-7

**Boot Log QA Form (cross-reference):** 6/23/16 Well 115-W6-SO Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0910

*% Methane* 1.4%

☐Methane < 1%; Proceed with spark testing

☒Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**:

☐Vacuum Box Tested

☐Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | | | | | | | | | | |
| Vertical weld | | | | | | | | | | |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 6/23/16. Methane completed on 6/24/16 by ESI. Methane testing yielded concentration of 1.4%. (>1%). As such, no spark testing was completed. The vertical weld and the weld at the base of the boot were visually observed and no deficiencies were noted.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:**

Honeywell


## STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 North
**Location:** Gas Vent GV-6 located near approximate center of SA-6 North Cap on Panel P11 (approximately 83 ft. north of southern end of cap). Identified as R-38 on *As Built* and *Repair Report.*

**Date:** 6/24/16 **Repair Number:** R-38
**Boot Log QA Form (cross-reference):** 6/23/16 Gas Vent GV-6 Form

### QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0915

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**: ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 6/23/16. Methane / spark testing completed on 6/24/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:** **Independent CQA Monitor Signature:**

## Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 1, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/05/16

SWPPP Observer: _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, July 01, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJPDES #:

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has accumulated on Kellogg Street, just outside of the SA-6 South truck entrance/exit gate. |
| 2 | IA2Q4A1AL8 | Filter fabric in the catch basins on the eastern SA-7 haul road has become blinded with sediment and/or damaged. |
| 3 | IA2Q4A1AL8 | Garbage and refuse is present on SA-7 between the western haul road and the Hackensack River bulkhead. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 07/05/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Clean/shovel sediment from the western end of Kellogg Street, particularly along the perimeter fenceline. | 7-7-16, RAV |
| 2 | Replace filter fabric in the catch basins as needed. | |
| 3 | Pick up and dispose of garbage/debris on western SA-7 | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 07/07/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 8, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | X | | 2 |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | X | | 3 |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/11/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, July 08, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and refuse are present along the outside of the perimeter fence on Kellogg Street and along the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | The top of sheetpile in the area of the JCIA trash pit is approximately at currently-existing grade and stormwater can accumulate and flow into the northern cap area. |
| 3 | IA2Q4A1AL8 | An O2 tank by the c-boxes on the SA-7 northern access roadway is missing its protective valve cap. |
| 4 | IA2Q4A1AL8 | Garbage and other debris is present in the Rt. 440 pedestrian walkway to the east of SA-6 North. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 07/11/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and dispose of garbage/debris located along the outside of the Kellogg Street fenceline | 7/11/16 RAD |
| 2 | Construct a berm along the top if the sheetpile in the vicinity of the old JCIA trash pit to prevent stormwater from running into the cap area. | 7/11/16 RAD |
| 3 | Replace the missing cap on the O2 bottle by the c-boxes on SA-7 | cap RMS 7/11/16 |
| 4 | Pick up and dispose of garbage/debris located in the eastern SA-6 North pedestrian walkway. | 7/11/16 RAD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 07/13/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 15, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 2 |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 07/18/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, July 15, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | The sediment bag in the stormwater catch basin at the western end of Kellogg Street (next to the truck entrance gate) requires maintenance. |
| 2 | IA2Q4A1AL8 | The N-2 perimeter pool riser on the north side of SA-7 is being impacted by stormwater during rain events. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 07/18/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the sediment bag in the catch basin. | 7-21-16 RAS |
| 2 | Construct a berm around the perimeter pool N-2 grate out of sandbags or other appropriate material to prevent stormwater run-off from entering the riser. | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date 07/21/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 22, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 07/25/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, July 22, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence by the Kellogg Street jughandle requires maintenance. |
| 2 | IA2Q4A1AL8 | The sediment bag in the stormwater catch basin on the southern side of the Groundwater Treatment Plant on SA-6 North requires maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 07/25/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Repair or replace windscreen fabric as required. | 7/28/16 RAD |
| 2 | Replace the filter fabric in the catch basin to the south of the GWTP | V |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 07/28/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: July 29, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☑ Cloudy ☐ Other _____
☑ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 2 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | | X | | 3 |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | X | | 4 |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 5 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 08/01/16

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWAP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, July 29, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has accumulated against the silt fence on the western end of the south cap and some of the silt fence is not properly toed in. |
| 2 | IA2Q4A1AL8 | Sediment has accumulated on the western end of Kellogg Street, particularly where it is piled up against the western curb at the end of the street and also along the northern edge. |
| 3 | IA2Q4A1AL8 | Stormwater has ponded at several locations on the south side of the SA-6 South cap area |
| 4 | IA2Q4A1AL8 | Additional Exclusion Zone signage is needed along the south side of the SA-6 North EZ and a CRZ must be properly delineated/identified. |
| 5 | EEPSQUO2YB | Silt fence and erosion control measures around the Novartis stockpile area require maintenance. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 08/01/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove sediment which has accumulated more than half-way up the fabric and toe in silt fence where required. | 8/4/16 RAD |
| 2 | Remove accumulated sediment from the roadway. | |
| 3 | Pump ponded stormwater as required. | |
| 4 | Place additional EZ signs on the southern edge of the Exclusion Zone and label the CRZ area | |
| 5 | Repair or replace erosion control measures around the Novartis stockpile area as required. | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 08/04/16

## Attachment 13: GWTP Update (525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted June 2016)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

July 19, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the June 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 6 | 01 | 16 | 6 | 30 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 76,973 | 83,596 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.67 | 0.73 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.17937 | 0.17937 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris VP
Signature of Principal
Executive or Authorized Agent

John J. Morris
Remediation Portfolio Director
Type Name and Title

7/19/2016
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 6 | 01 | 16 | 6 | 30 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,309,202 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 66,252,920 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 6/9/2016 | <5.0 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | DATE 7/19/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: June, 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 6/1/2016 | Angel Trujillo | 63943718 | 64021930 | 78,212 | 0.078212 | 7.01 | 1.040 | | | | | | | | | 0.68 |
| 6/2/2016 | Angel Trujillo | 64021930 | 64099220 | 77,290 | 0.07729 | 7.08 | 1.040 | | | | | | | | | 0.67 |
| 6/3/2016 | Angel Trujillo | 64099220 | 64174820 | 75,600 | 0.0756 | 7.98 | 1.040 | | | | | | | | | 0.66 |
| 6/4/2016 | Angel Trujillo | 64174820 | 64256270 | 81,450 | 0.08145 | 7.92 | 1.040 | | | | | | | | | 0.71 |
| 6/5/2016 | Angel Trujillo | 64256270 | 64332213 | 75,943 | 0.075943 | 8.10 | 1.040 | | | | | | | | | 0.66 |
| 6/6/2016 | Angel Trujillo | 64332213 | 64408156 | 75,943 | 0.075943 | 7.95 | 1.040 | | | | | | | | | 0.66 |
| 6/7/2016 | Angel Trujillo | 64408156 | 64487026 | 78,870 | 0.07887 | 8.09 | 1.040 | | | | | | | | | 0.68 |
| 6/8/2016 | Angel Trujillo | 64487026 | 64564698 | 77,672 | 0.077672 | 7.97 | 1.040 | | | | | | | | | 0.67 |
| 6/9/2016 | Angel Trujillo | 64564698 | 64644458 | 79,760 | 0.07976 | 6.95 | 1.040 | <5.1 | <5.0 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.69 |
| 6/10/2016 | Angel Trujillo | 64644458 | 64720510 | 76,052 | 0.076052 | 8.11 | 1.040 | | | | | | | | | 0.66 |
| 6/11/2016 | Angel Trujillo | 64720510 | 64799545 | 79,035 | 0.079035 | 7.90 | 1.040 | | | | | | | | | 0.69 |
| 6/12/2016 | Angel Trujillo | 64799545 | 64878580 | 79,035 | 0.079035 | 7.99 | 1.040 | | | | | | | | | 0.69 |
| 6/13/2016 | Angel Trujillo | 64878580 | 64955502 | 76,922 | 0.076922 | 7.85 | 1.040 | | | | | | | | | 0.67 |
| 6/14/2016 | Angel Trujillo | 64955502 | 65036750 | 81,248 | 0.081248 | 8.01 | 1.040 | | | | | | | | | 0.70 |
| 6/15/2016 | Angel Trujillo | 65036750 | 65109326 | 72,576 | 0.072576 | 7.00 | 1.040 | | | | | | | | | 0.63 |
| 6/16/2016 | Angel Trujillo | 65109326 | 65189252 | 79,926 | 0.079926 | 8.23 | 1.040 | | | | | | | | | 0.69 |
| 6/17/2016 | Angel Trujillo | 65189252 | 65266398 | 77,146 | 0.077146 | 8.05 | 1.040 | | | | | | | | | 0.67 |
| 6/18/2016 | Angel Trujillo | 65266398 | 65342976 | 76,578 | 0.076578 | 7.77 | 1.040 | | | | | | | | | 0.66 |
| 6/19/2016 | Angel Trujillo | 65342976 | 65419446 | 76,470 | 0.07647 | 7.80 | 1.040 | | | | | | | | | 0.66 |
| 6/20/2016 | Angel Trujillo | 65419446 | 65495916 | 76,470 | 0.07647 | 7.91 | 1.040 | | | | | | | | | 0.66 |
| 6/21/2016 | Angel Trujillo | 65495916 | 65573388 | 77,472 | 0.077472 | 8.14 | 1.040 | | | | | | | | | 0.67 |
| 6/22/2016 | Angel Trujillo | 65573388 | 65651421 | 78,033 | 0.078033 | 7.79 | 1.040 | | | | | | | | | 0.68 |
| 6/23/2016 | Angel Trujillo | 65651421 | 65706685 | 55,264 | 0.055264 | 7.74 | 1.040 | | | | | | | | | 0.48 |
| 6/24/2016 | Angel Trujillo | 65706685 | 65790281 | 83,596 | 0.083596 | 7.78 | 1.040 | | | | | | | | | 0.73 |
| 6/25/2016 | Angel Trujillo | 65790281 | 65867596 | 77,315 | 0.077315 | 7.86 | 1.040 | | | | | | | | | 0.67 |
| 6/26/2016 | Angel Trujillo | 65867596 | 65941703 | 74,107 | 0.074107 | 7.80 | 1.040 | | | | | | | | | 0.64 |
| 6/27/2016 | Angel Trujillo | 65941703 | 66015810 | 74,107 | 0.0741 | 7.77 | 1.040 | | | | | | | | | 0.64 |
| 6/28/2016 | Angel Trujillo | 66015810 | 66097814 | 82,004 | 0.082004 | 7.72 | 1.040 | | | | | | | | | 0.71 |
| 6/29/2016 | Angel Trujillo | 66097814 | 66173494 | 75,680 | 0.07568 | 7.86 | 1.040 | | | | | | | | | 0.66 |
| 6/30/2016 | Angel Trujillo | 66173494 | 66252920 | 79,426 | 0.079426 | 7.84 | 1.040 | | | | | | | | | 0.69 |
| | | | | | | | | | | | | | | | | |
| **TOTAL** | | | | **2,309,202** | **2.309202** | | | <5.1 | <5.0 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | **High:** | **83,596** | | | | | | | | | | | **High:** | **0.73** |
| | | | **Average:** | **76,973** | | | | | | | | | | | **Average:** | **0.67** |

WW

JC21877

# Honeywell — Chain Of Custody / Analysis Request

| | | | |
|---|---|---|---|
| Accutest Labs<br>2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program: 087: JCIA |
| Client Contact: (name, co., address)<br>Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | Sampler: Frank Schroyer<br>PO # | | |
| Honeywell International<br>101 Columbia Road Morristown, NJ 07962 | Analysis Turnaround Time (TAT): Consultant: 3 CH2M | | |
| Preliminary Data To<br>Sample Receipt Acknowledgement To: Frank Schroyer | | | |
| Hard Copy To: Helen Fahy (Honeywell)<br>Invoice To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | |

| | |
|---|---|
| AESI Ref: | 42530.51426 |
| COC# | 087-WW-060916 |
| Lab Proj # (SDG): | |
| Lab ID | ACTD |
| Site ID | HudsonCo |
| Lab Job # | HWINJM32815 |
| Authorized User: | Honeywell |
| Text & Excel File Drive | Excel & Text File Order |

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample ? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Preservative | | | | | | | | | | | | 3 | 3 | 3 | 1 | 2 | 2 | 0 | 0 | 2 | | | | | | | |
| | Units | | | | | | | | | | comp | N | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-060916-A | 6/9/2016 | 14:25 | WW | WATER | REG | 5 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | |
| 2 | 087-WW | | | 087-WWE-060916-B | 6/9/2016 | 14:30 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | L26 |
| 3 | 087-WW | | | 087-WWI-060916 | 6/9/2016 | 14:40 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | V338<br>A15<br>G23 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

3A Dom

INITIAL ASESSMENT

LABEL VERIFICATION JV

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: 6.95 s.u. @ 8.3°C | Company: AMEC Foster Wheeler | Received by: TC Temp | Company: | | Condition: | | Custody Seals Intact: |
| Frank Schroyer | Date/Time: 6/9/16 | | Date/Time: 6-9-16 1540 | | Cooler Temp. | | |
| Relinquished by: K Temp | Company: | Received by: | Company: | | Condition: | | Custody Seals Intact: |
| | Date/Time: 6-9-16 1740 | | Date/Time: 6-9 1740 | | Cooler Temp: 5.1°C BP | | 250 |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

ALL SAMP PRESERVE ESER VED E

SGS Accutest LabLink@917142 13:11 06-Jul-2016

# Report of Analysis





**Client Sample ID:** 087-WWE-060916-A
**Lab Sample ID:** JC21877-1
**Matrix:** AQ - Water
**Project:** PESNJP: Hudson County, Jersey City, NJ

**Date Sampled:** 06/09/16
**Date Received:** 06/09/16
**Percent Solids:** n/a

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1040 | 10 | ug/l | 1 | 06/11/16 | 06/13/16 | AB | EPA 200.7 [2] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 06/11/16 | 06/13/16 | AB | EPA 200.7 [2] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 06/11/16 | 06/13/16 | AB | EPA 200.7 [2] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 06/13/16 | 06/13/16 | JPM | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 06/11/16 | 06/13/16 | AB | EPA 200.7 [2] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 06/11/16 | 06/13/16 | AB | EPA 200.7 [2] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA39615
(2) Instrument QC Batch: MA39617
(3) Prep QC Batch: MP94237
(4) Prep QC Batch: MP94261

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@917142 13:11 06-Jul-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-060916-A | | |
| **Lab Sample ID:** | JC21877-1 | **Date Sampled:** | 06/09/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/09/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 06/11/16 08:00 | SP | SM2540 D-11 |
| pH [a] | 6.94 | | su | 1 | 06/09/16 19:10 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@917142 13:11 06-Jul-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-060916-A | | |
| **Lab Sample ID:** | JC21877-1A | **Date Sampled:** | 06/09/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/09/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 5.0 | 5.0 | mg/l | 1 | 06/09/16 21:25 | LS | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@917142 13:11 06-Jul-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-060916-B | | |
| **Lab Sample ID:** | JC21877-2 | **Date Sampled:** | 06/09/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/09/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | N255408.D | 1 | 06/10/16 | BM | n/a | n/a | VN10794 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 4.4 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.9 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.24 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 27.7 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.34 | 1.0 | 0.15 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.36 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 69.4 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.0 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.93 | 1.0 | 0.16 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS ACCUTEST

SGS Accutest LabLink@917142 13:11 06-Jul-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-060916-B | | |
| **Lab Sample ID:** | JC21877-2 | **Date Sampled:** | 06/09/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/09/16 |
| **Method:** | EPA 624 | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 67.6 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | 1.5 | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 110% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 101% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 105% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 103% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@917142 13:11 06-Jul-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-060916-B | | |
| **Lab Sample ID:** | JC21877-2 | **Date Sampled:** | 06/09/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 06/09/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 06/10/16 21:20 | CB | EPA 1664A |

RL = Reporting Limit

## Attachment 14: SA-6 North & South Design Change Tracking Log

- SA-6 North & South Design Change Tracking Log
- Design Change Bulleting 2016-07-12: SA-6 North Clarify location of Sand Bentonite Plug

**SA-6 North & South Design Change Tracking Log**
*(Attachment 14:  SA-6 North & South Design Change Tracking Log)*

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized based field obersvations and constructability review. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Contractor only. |
| **DC 2016-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2014-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA 6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to address the elimination of a drop structure, the elmination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead. | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Contractor only. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Contractor only. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Submitted to Contractor only. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | Submitted to Contractor only. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Contractor only. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Contractor only. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-12-01** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Contractor only. |
| **DC 2016-02-03** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Contractor only. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Contractor only. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Contractor only. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. |
| **DC 2016-05-31** | This DCB documents the vault sketch Drawing C-310 (Rev 5, 5/31/16) | Submitted to Contractor only. |

**SA-6 North/South Field Change Log - Month Ending July 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | Submitted to Contractor only. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. |
| **DC 2016-7-12** | DC 2016-7-12 clarifies the limit of GCL deployment and the location of the sand bentonite plug in the SA-6 North cap. | Included as an attachment to this log. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**Design Change Bulleting 2016-07-12: SA-6 North Clarify location of Sand Bentonite Plug**
*(Attachment 14: SA-6 North & South Design Change Tracking Log)*

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6 Jersey City, NJ | **DCB No.:** **Type:** Minor(a)<br>**Effective Date:** 7/12/16 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** Clarify location of Sand Bentonite Plug | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**


Drawing CN-516 indicates the limit of the GCL deployment. Where the top of the Barrier Wall is below elevation 7.0, a sand bentonite plug will be installed as shown on Section C-C. The intent of the plug is to provide a connection between the GCL and Barrier wall in locations where the cap may be below the groundwater. The plug is isolated to two utility corridors. The plug limits are noted on Section C-C.


In the remainder of the areas where the Barrier Wall is at or above elevation 7.0, the GCL will be carried over the wall as shown in Section D-D. The GCL should be in intimate contact with the top of the Barrier Wall.


| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>Clarification of drawing CN-516, incorporated into DC 2016-2-25 in an e-mail to ENTACT dated 5/4/16 |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>CN-516 |

| | | | |
|---|---|---|---|
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** |
| **(Name / Signature):** | | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** | |
| **Distribution:** | | | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.








SECTION A-A
NTS




SECTION B-B
NTS




## GEOFOAM BLOCK SUMMARY


| NUMBER | LENGTH |
|---|---|
| 1 | 40' |
| 2 | 24' |
| 3 | 11' |
| 4 | 10' |
| 5 | 10' |
| 6 | 24' |
| 7 | 10' |
| 8 | 15' |
| 9 | 21' |
| 10 | 13' |
| 11 | 25' |
| 12 | 17' |

GEOFOAM BLOCKS EPS 19 4' WIDE x 1' THICK LENGTH VARIES


## NOTES:

1. PERFORATED PIPE TO BE CORRUGATED SLOTTED PE PIPE.
2. SPACERS MAY BE PREFABRICATED AS PART OF THE 4.5" DIA VENT PIPE.

GAS VENT DETAIL
NTS
AN
CN-516 CN-516




SECTION D-D
(NO SAND BENTONITE PLUG)
NTS




STA. 2+92 TO STA. 3+26
STA. 5+60 TO STA. 5+90

SECTION C-C
(SAND BENTONITE PLUG)
NTS

NOTES:

1. HORIZONTAL GAS VENTING PIPE SHALL BE 8" ADS SINGLE WALL HEAVY DUTY PERPETRATED PIPE WITH ANNULAR INTERIOR AND EXTERIOR CORRUGATIONS OR APPROVED EQUAL.
2. PIPING JOINTS SHALL BE MADE WITH SPLIT OR SNAP COUPLINGS. STANDARD CONNECTIONS SHALL MEET THE REQUIREMENTS OF THE ASTM F405 OR ASTM F667. GASKETED CONNECTIONS SHALL INCORPORATE A CLOSED-CELL SYNTHETIC EXPANDED RUBBER GASKET MEETING THE REQUIREMENTS OF ASTM D1056 GRADE 2A2.
3. ALL PIPE FITTINGS SHALL CONFORM TO ASTM F405 OR ASTM F667.
4. PIPE AND FITTING MATERIAL SHALL BE HIGH DENSITY POLYETHYLENE CONFORMING WITH THE MINIMUM REQUIREMENTS OF CELL CLASSIFICATION 423410C AS DEFINED AND DESCRIBED IN THE LATEST VERSION OF ASTM D3350; OR ASTM D1248 TYPE III, CLASS C, CATEGORY 4, GRADE P33.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 4 | 07/12/16 | DCB 062 SAND BENTONITE PLUG CLAIRIFICATION | TDD | SGS |
| 3 | 02/01/16 | DCB 054 INCREASED LANDSCAPE GRADE 0.25 FEET | TDD | SGS |
| 2 | 08/12/14 | DCB 13 BARRIER WALL REALIGNMENT | RJR | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |

DSGN TDD | DR | CHK RJR | APVD TDD

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

GAS VENTING SYSTEM AND DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619 (609) 890-2929
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-12-0317
DWG CN-516
SHEET 52 OF 70

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR52-C-516 GAS VENTING.dwg PLOT DATE: Tue, 12 Jul 2016 PLOT TIME: 12:32 PM

**9/12/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

September 12, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-08**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from August 1 – August 31, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: August 2016 SA-6/7 Combined Monthly Progress Report No. 2016-08

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP (electroni copy)

Honeywell

# STUDY AREAS 6 AND 7 COMBINED
# MONTHLY PROGRESS/HIGHLIGHTS
# REPORT NO. 2016-08
## Project SA-6 & 7 Remediation

# August 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 08/08/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-05 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/08/16 | Response to Comments<br>Temporary Construction Road – Design Change Bulletin<br>SA-6 South Chrome Remedy<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/09/16 | Special Master Conference Call | n/a |
| 08/10/16 | 3 Year Sampling Results<br>Treatment Areas 7 and 8<br>SA-6 North (Site 087)<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/10/16 | NJDEP approved DGW permit for the continued treatment works<br>SA-6 North<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/10/16 | Honeywell - Culver Circle, Jersey City Notification to NJDOT<br>SA-6 North<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 08/11/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 08/16/16 | Evaluation of Options for Treatment Area 7<br>SA-6 North (Site 087)<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |

# SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 08/07/26 | 08/14/16 | 08/21/16 | 08/28/16 |
| **Construction Management (AMEC)** | 10 | 9 | 10 | 12 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 37 | 36 | 33 | 31 |
| **Arecon/US Ecology Subcontractors** | 0 | 1 | 0 | 0 |
| **ESI** | 12 | 12 | 3 | 0 |
| **Lagan** | 1 | 1 | 1 | 1 |
| **ERFS** | 0 | 0 | 0 | 1 |
| **Evoqua** | 2 | 1 | 1 | 1 |
| **B&B Drilling** | 1 | 1 | 0 | 1 |
| **Cornerstone** | 1 | 2 | 0 | 0 |
| **TOTAL STAFF** | **69** | **68** | **53** | **52** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Conducted S-3 Mass Removal Injection Event No. 31 in injection well 088-IW-03.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Raised the PW-3 Pump elevation to the top of screen.
- Completed perimeter air monitoring activities on SA-6 North. As of July 1, 2016, all intrusive activities are complete. As only site grading and restoration activities remain, air monitoring will be completed using hand-held portable devices for nuisance dust.
- PVSC personnel removed the spare 72” force main repair components stored on SA-7 on August 18, 2016.
- Obtained a Discharge to Groundwater-Permit by Rule from NJDEP for additional injections in treatment area 10-1.
- ERFS installed a total of 10 injection wells in Treatment Area 10-1. On August 4, 2016, received the NJDEP – Discharge to Groundwater Permit authorization for the additional in-situ treatment injections at this location.
- Began installation of CGWES components within the SA-6 South Open Space and the SA-6 North Open Space Areas to include installation of the valve vaults and link seals.
- Completed resampling of 124-MW-106T (results pending, will be provided when available.)

- Collected August PVSC compliance sample from the Construction Water Treatment Plant (CWTP).

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on August 9, 2016.
- Contracted with mechanical contractor, Brownfield Science & Technology, Inc. (BTSI), to complete piping installation from the CGWTS force mains to the neutralization tank in accordance with the PVSC permit.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 08/07/26 | 08/14/16 | 08/21/16 | 08/28/16 |
| Avg. Gallons Treated & Discharged (per day) | 76,768 | 77,362 | 77,405 | 77,197 |
| Average Flow (gpm) for Operating Period | 55 | 56 | 55 | 55 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 3,540 | 4,560 | 2,880 | 3,648 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Continued placing backfill as part of site restoration in the SA-6 South Development Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 1 | 18.4 | 18.4 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Backfill in Progress** | Historic Fill Soils – SA-6 South Development Area |

### 3. BACKFILL MATERIALS USED

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 08/07/16 | 08/14/16 | 08/21/16 | 08/28/16 |
| Natures Choice Horizon C | 0 | 0 | 0 | 6,113.75 |
| Tilcon Mt. Hope DGA | 0 | 0 | 0 | 176.57 |
| Tilcon Mount Hope I-8 | 886 | 1,263 | 504 | 1661 |
| Natures Choice Topsoil | 0 | 539 | 1,138 | 875 |
| Tilcon 3/8" Stone | 51.76 | 0 | 26.53 | 0 |
| Weldon Screenings | 0 | 377.68 | 0 | 0 |

- Overburden historic fill soils with hexavalent chromium concentrations confirmed to be < 20 mg/kg soils were transferred and placed as backfill the SA-6 South Development Area.
- Screened Celgene material was placed as protective cover soil in the SA-6 North Open Space Area. Approximately 9,984 cubic yards was placed as protective cover soil during the reporting period.
- Approximately 272 cubic yards of Celgene screening operations were placed as backfill on the south slope of the SA-6 North Open Space Area.

## D. SURCHARGE OPERATIONS

- All surcharging activities are completed.

## E. SHEET PILE OPERATIONS

- Completed cutting hydraulic barrier sheets to final elevation in SA-6 North Open Space Area.

## F. CAPPING OPERATIONS

- Continued importing and placing Horizon A soils on SA-6 South Open Space Area.
- Continued placement of GDL cover soils and demarcation tape to include associated compaction testing on the SA-6 North Open Space Area.
- Continued placement structural fill, root barrier, and Horizon C soils to include associated compaction testing on the SA-6 North Open Space Area.
- Completed SA-6 North geomembrane liner subgrade grading activities within the Open Space Area.
- Completed installation of geosynthetic components to include placement of the geocomposite gas venting layer, 60 mil geomembrane liner, geosynthetic clay layer, and geocomposite drainage layer.
- A total of 92,588sq. ft. of geomembrane liner (21% of the total cap area) was deployed during the

reporting period.

- Completed spark testing on twelve boot welds during the reporting period. Please see **Attachment 11** for the spark test logs.
- Completed cutting hydraulic barrier sheets and finishing the SCB wall to final elevation in SA-6 North Open Space Area.
- Completed installation of Gas Vent Pipe within the SA-6 North Open Space Area.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 08/04/2016 | Not Specified | Not Specified | 9/12/16 |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete importing and placement of Horizon A Topsoil on the SA-6 South Open Space Area.
- Complete redevelopment area regrading and site restoration on SA-6 South.
- Complete hydro-seeding of SA-6 South Open Space Area.
- Complete placement of historic fill cap to include geotextile and 6-inches of stone in the SA-6 South Development Area.
- Continue installation of the Contingent Groundwater Extraction System Components including the mechanical piping and conduit within the GWTP.
- Complete placement of GDL cover soils within the SA-6 North Open Space Area.
- Continue placement structural fill, root barrier, and Horizon C soils to include associated compaction testing on the SA-6 North Open Space Area.
- Begin placement of Horizon A Topsoil on the SA-6 North Open Space Area.
- Begin hydro-seeding of SA-6 North Cap Area.
- Continue dewatering and storm-water management activities.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 32 in well 088-IW-01.
- Conduct third quarter regional groundwater level measurement round.
- Start injections in Treatment Area 10-1 in accordance with NJDEP-DGW permit.

## ATTACHMENTS:

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data *(reported quarterly – not included in this report)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update
    - SA-6 Cap Subgrade Progress Maps
    - Repair Log
    - Non-conformance Log
    - Subgrade Approval Form
    - QA Photo Log
    - Daily QA Reports (Langan)
    - Spark Test Logs
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log
15. Issued Permit: NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils


## Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration |
|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** |
| **2** | **Remedial Action Work Plan** | **33 days** |
| **5** | **Remedial Action Design** | **1522 days** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** |
| 19 | Develop Site Relocation Master Plan | 38 days |
| 20 | Submit Site Relocation Master Plan | 0 days |
| 21 | JC Construction of New Facilities | 1309 days |
| 22 | Relocation Contractor Procurement | 392 days |
| 23 | JCIA and JCDPW Relocation | 949 days |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days |
| 24a | Demolition of JCIA Structures | 146 days |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** |
| **26** | **Remedial Action Work Plan** | **187 days** |
| **32** | **Remedial Action Design** | **1161 days** |
| **57** | **SA-6 South Relocation** | **616 days** |
| 58 | New GWTP Construction Completion | 502 days |
| 59 | Demolition of 80 Kellogg | 857 days |
| **60** | **SA-6 North/South Field Implementation** | **894 days** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** |
| 61a | Mobilization | 87 days |
| **62** | **Surcharge Install/Instrumentation** | **706 days** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days |
| **63** | **Barrier Wall Install** | **569 days** |
| 63a | SA 6N Installation of Barrier Wall | 159 days |
| 63b | SA 6S Installation of Barrier Wall | 210 days |
| **64** | **Excavation** | **507 days** |
| 64a | SA 6N Excavation | 218 days |
| 64b | SA 6S Excavation | 295 days |
| **65** | **Backfill** | **558 days** |
| 65a | SA 6N Backfill | 283 days |
| 65b | SA 6S Backfill | 384 days |
| **66** | **Capping and Cover Soil Placement** | **426 days** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days |
| **67** | **Restoration** | **234 days** |
| 67a | Restoration | 234 days |
| **68** | **Demobilization** | **22 days** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | |
| **69** | **SA-6 North Project Closeout** | **311 days** |
| **75** | **SA-6 South Project Closeout** | **311 days** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/2/2016

Task  Milestone  Summary  Critical

Note: Current field implementation schedule shows capping complete in September 2016 and restoration in October 2016.

## Attachment 2: Site Photographs




**Site Photograph 1:** Contractor fine grading cover soils on the SA-6N Open Space Area.




**Site Photograph 2:** Contractor placing cover soils on the SA-6N Open Space Area.




**Site Photograph 3:** Contractor grading protective cover soils on the SA-6N open space area.




**Site Photograph 4:** Dust suppression activities SA-6N.




**Site Photograph 5:** Installation of root barrier SA-6N Open Space Area.




**Site Photograph 6:** Overall view of warning layer and cover soils SA-6N Open Space Area.

## Attachment 3: Excavation and Backfill Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of September 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-08
Attachment 3: Excavation and Backfill (Progression Chart)

## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

City Properties

Hackensack River

Route 440

Former Roosevelt Drive-In Site
(Remediation Complete)

Kellogg Street Properties

Kellogg Street

Added Excavation Area
(complete)

## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)


| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 06/24/16 | 9:00 | 14:00 | 5:00 | 43,543.94 | 43,596.37 | 52,430 | 43,595,920 | |
| 07/07/16 | 7:30 | 12:00 | 4:30 | 43,596.37 | 43,642.93 | 46,560 | 43,642,480 | PVSC Compliance Sample Collected |
| 07/15/16 | 10:00 | 14:00 | 4:00 | 43,642.93 | 43,692.98 | 50,050 | 43,692,530 | |
| 07/26/16 | 9:00 | 14:00 | 5:00 | 43,692.98 | 43,794.27 | 101,290 | 43,793,820 | |
| 07/27/16 | 7:00 | 15:00 | 8:00 | 43,794.27 | 43,826.36 | 32,090 | 43,825,910 | |
| 07/28/16 | 9:00 | 15:00 | 6:00 | 43,826.36 | 43,860.98 | 34,620 | 43,860,530 | |
| 08/01/16 | 9:00 | 15:00 | 6:00 | 43,860.98 | 43,896.38 | 35,400 | 43,895,930 | PVSC Compliance Sample Collected |
| 08/11/16 | 9:00 | 16:00 | 7:00 | 43,896.38 | 43,958.93 | 62,550 | 43,958,480 | |
| 08/12/16 | 9:30 | 13:45 | 4:15 | 43,958.93 | 43,998.63 | 39,700 | 43,998,180 | |
| 08/19/16 | 8:00 | 13:30 | 5:30 | 43,998.63 | 44,062.58 | 63,950 | 44,062,130 | |


Notes: Previous information is truncated. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data


(not included in this reporting period)

## Attachment 7: Perimeter Pools Update



HACKENSACK RIVER
N4
N3
N2
N1
S4
S3
S2
S1
E1
E2
POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'
POOL E1 ELEV.+9.0 325'
POOL E2 ELEV.+8 270'
INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0
INTERIOR POOL ELEV. +4.0
COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)
COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)
S-C-B BARRIER (TYP.)
KELLOGG STREET
LEGEND
FILL TYPE A CLAY
FILL TYPE B GRANULAR FILL
SHALLOW WELL INSTALLED BY OTHERS
SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
GRAPHIC SCALE
100' 50' 0 100' 200'
IN PROGRESS
06-10-2015
STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS
NEW JERSEY
MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET
FILE NO. 10210
DRAWING NO. PP-1





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10) **Note:** Honeywell is evaluating if another flushing event is needed.





**Perimeter Pool N3** (Sta. N6+80 to N10+23) **Note:** Honeywell is evaluating if another flushing event is needed.





**Perimeter Pool N4** (Sta. N6+80 to N10+23) **Note:** Honeywell is evaluating if another flushing event is needed.





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-5 | FS-6 | FS-7 | FS-13 |
| Date | | | | | | | | | | | | | |
| 9/1/2015 | | 4.5 | 5.3 | 3.2 | 3.7 | | 1.6 | 1.6 | 5.8 | 4.5 | 4.5 | 3.6 | |
| 9/15/2015 | 0.9 | 4.6 | 5.3 | 3.1 | 3.6 | | 1.3 | 1.6 | 5.6 | 4.4 | 4.3 | 3.5 | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | 4.4 | 4.4 | 3.5 | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | 4.7 | 4.6 | 4.0 | 4.0 |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | 4.7 | 4.6 | 3.9 | 3.8 |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | 4.6 | 4.6 | 3.7 | 3.4 |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | 4.5 | 5.0 | 3.8 | 3.5 |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | 3.5 | 3.6 | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | 5.2 | | | 4.6 |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | 6.0 | | | 5.6 |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | 6.5 | | | 6.2 |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | 6.0 | | | 5.7 |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | 5.6 | | | 5.0 |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | 2.7 | | | 3.6 |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | 2.1 | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | 1.8 | | | |
| 5/2/2016 | 3.1 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | 1.6 | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | |
| 6/1/2016 | 2.7 | 5.2 | 5.5 | 2.5 | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/16/2016 | 2.7 | 5.2 | 5.6 | | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/28/2016 | 3.2 | 5.2 | 5.6 | 2.4 | 3.2 | 2.3 | 3.1 | 3.1 | 1.8 | | | | |
| 7/15/2016 | 3.2 | 5.3 | 5.6 | 2.5 | 3.3 | 2.4 | 3.1 | 3.2 | 1.8 | | | | |
| 7/27/2016 | 3.1 | 5.3 | 5.4 | 2.6 | 3.2 | 2.3 | 3.1 | 3.2 | 2.0 | | | | |
| 8/12/2016 | 3.4 | 5.3 | 5.6 | 3.2 | 2.6 | 2.8 | 3.3 | 3.4 | 2.5 | | | | |
| 8/29/2016 | 3.5 | 5.1 | 5.4 | 3.2 | 2.6 | 2.8 | 3.4 | 3.4 | 2.7 | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

## Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)


## Attachment 10: Sheet Pile Update

(not included in this reporting period)

## Attachment 11: Capping Update

- SA-6 Cap Subgrade Progress Maps
- Repair Log
- Non-conformance Log
- Subgrade Approval Forms
- QA Photo Log
- Daily QA Reports (Langan)
- Spark Test Logs

**SA-6 Cap Subgrade Progress Maps**
*(Attachment 11:  Capping Update)*




LEGEND

- GDL COVER SOIL PLACED
- GDL COVER SOIL GRADED AND APPROVED FOR HORIZON SOILS
- HORIZON C SOIL PLACED
- STRUCTURAL FILL PLACED
- GEOCOMPOSITE DRAINAGE LAYER FABRIC
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP COVER SOILS PROGRESS MAP
08/31/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LEGEND

- HORIZON B PLACED AND READY FOR TOPSOIL
- HORIZON C PLACED AND READY FOR TOPSOIL
- TOPSOIL PLACED
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
08/31/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | PB | 1/2 | P-1 | 35' N OF SEOS & 8'W PB 6") | P | 3 | x | 11 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 2 | BO | 3/5 | | 2' N OF S EOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 3 | SJ | 3/4/5 | | 69' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 4 | CF | 4/6 | | 5' S OF NEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 5 | CF | 4/6 | P-6 | 77' N OF SEOS & 2'E | P | 5 | x | 12 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 6 | SJ | 4/5/6 | | 69' N OF SEOS | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 7 | PB | 5/6 | | 15' N OF SEOS (PB 6") | P | 3 | x | 6 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 8 | WR | 6/7 | P-6 | 63' N OF S EOS & 5'W | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 9 | BO | 6/7 | | 66' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 10 | SI | 6/7 | P-6 | 80' N OF SEOS & 5'W | P | 3 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 11 | DS-2 | 6/7 | | 16' N OF SEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 12 | WR | 7/9 | | 41' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 13 | CF | 7/9 | P-9 | 45' N OF SEOS & 10'E | P | 6 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 14 | DS-1 | 1/2 | | 15' N OF SEOS | P | 2 | x | 7 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 15 | DSX-1 | R-15 | P-1 | 34'N OF SEOS & 10'W | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 16 | CF | | P-9 | BETWEEN R-12 & R-13 | B | | x | | 60 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 17 | WR | 7/9 | | 71' N OF SEOS | P | 3 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 18 | CF | | P-9 | BETWEEN R17 & R19 | B | | x | | 168 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 19 | CF | 7/9 | P-9 | 59' N OF SEOS & 12'E | P | 4 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 20 | CF | | P-6 | BETWEEN R-22 & R-9 | B | | x | | 36 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 21 | CF | | P-6 | BETWEEN R-22 & R-8 | B | | x | | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 22 | CF | 6/7 | P-6 | 68' N OF SEOS & 6'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 23 | SJ | 7/8/9 | | 103' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 24 | CF | 8/10 | | 11' S OF NEOS | P | 2 | x | 20 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 25 | SJ | 8/9/10 | | 103' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 26 | DO | 10/11 | P-10 | 27' N OF SEOS & 4'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 27 | CF | 10/11 | P-10 | BETWEEN R-35 & R-28 | B | | x | | 156 | 6/26/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 28 | CF | 10/11 | P-10 | 64'N OF SEOS & 15' W | P | 4 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 29 | PB | 10/11 | P-10 | 93' S OF NEOS 4' E (48" MH ) | P | 6 | x | 10 | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 30 | CF | | P-10 | BETWEEN R-29 & R-31 | B | | x | | 240 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 31 | CF | 10/11 | P-10 | 68' S OF NEOS & 2'W | P | 2 | x | 2 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 32 | CF | 10/11 | P-10 | 78' N OF SEOS & 7'W | P | 2 | x | 4 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 33 | CF | | P-10 | BETWEEN R-32 & R-34 | B | | x | | 60 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 34 | CF | 10/11 | | 80' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 35 | CF | 10/11 | | 69' N OF SEOS | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 36 | CF | 10/11 | P-11 | 49' N OF SEOS & 5'E | P | 5 | x | 15 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 37 | CF | | P-11 | 50' N OF SEOS & 3'E | B | | x | | 48 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 38 | PB | 10/11 | P-11 | 105' N OF SEOS & 3' E (8" PIPE ) | P | 4 | x | 5 | 24 | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 39 | DS-3 | 10/11 | | 25' S OF NEOS | P | 2 | x | 6 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 40 | AO | 10/11 | | 3' S OF NEOS | P | 12 | x | 12 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 41 | SJ | 11/12/13 | | 22' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 42 | SJ | 12/13/14 | | 24' S OF NEOS | P | 2 | x | 6 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 43 | DO | 4/6 | P-4 | 6' S OF NEOS & 4'W | P | 2 | x | 3 | | 6/23/16 | SU | EXT-74 | Vacuum | Pass | 6/23/16 |
| 44 | BO | 13/14 | | 65' N OF SEOS | P | 2 | x | 5 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 45 | BO | 13/14 | | 79' N OF SEOS | P | 2 | x | 5 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 46 | BO | 13/14 | | 163' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 47 | CF | 13/14 | | BETWEEN R-46 & R-42 | B | | x | | 12 | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 48 | SJ | 12/14/14A | | 4' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 49 | SJ | 14A/14/15 | | 4' S OF NEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 50 | SJ | 14/15/16 | | 78' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | SU | EXT-74 | Vacuum | Pass | 6/24/16 |
| 51 | BO | 14/16 | | 2'N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 52 | SJ | 15/16/17 | | 78' N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 53 | DS-4 | 15/17 | | 87' N OF SEOS | P | 2 | x | 6 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 54 | CF | 17/18 | | 53' S OF NEOS | P | 3 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 55 | CF | 17/18 | P-17 | 56' S OF NEOS & 3'W | B | | x | | 24 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 56 | CF | 17/18 | P-18 | 74' S OF NEOS &3'E | P | 3 | x | 9 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 57 | CF | 17/18 | | 83' S OF NEOS | P | 2 | x | 4 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 58 | CF | 17/18 | P-18 | 84' S OF NEOS & 4' E OF R-57 | B | | x | | 120 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 59 | BO | 17/18 | | 153' S OF NEOS | P | 2 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 60 | CF | | P-18 | BETWEEN R-59 & R-62 | B | | x | | 140 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 61 | BO | 17/18 | | 182' S OF NEOS | P | 2 | x | 6 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 62 | CF | 18/19 | P-18 | 29' N OF SEOS & 7'W | P | 2 | x | 13 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 63 | BO | 18/19 | | 24' N OF SEOS | P | 2 | x | 6 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 64 | CF | 18/19 | | BETWEEN R-63 & R-65 | B | | x | | 12 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 65 | CF | 18/19 | P-19 | 30' N OF SEOS & 3'E | P | 2 | x | 9 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 66 | CF | | P-19 | BETWEEN R-65 & R-67 | B | | x | | 108 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 67 | CF | 19/20 | P-19 | 42' N OF SEOS & 5'W | P | 3 | x | 7 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 68 | CF | 18/19 | | 46' N OF SEOS | P | 2 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 69 | CF | | P-19 | BETWEEN R-68 & R-70 | B | | x | | 72 | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 70 | CF | 18/19 | P-19 | 49' N OF SEOS & 7'E | P | 3 | x | 3 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/29/16 |
| 71 | BO | 18/19 | | 113' N OF SEOS | P | 3 | x | 4 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 72 | BO | 18/19 | | 130' N OF SEOS | P | 2 | x | 2 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 73 | DSX-2 | R-30 | P-10 | 106' N OF SEOS & 6'W | P | 2 | x | 5 | | 6/24/16 | MA | EXT-75 | Vacuum | Pass | 6/24/16 |
| 74 | DS-5 | 19/20 | | 16' N OF SEOS | P | 2 | x | 5 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 75 | CF | 19/20 | | 164' N OF SEOS | P | 2 | x | 20 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 76 | AO | 19/R76/20 | | 180' N OF SEOS | P | 1 | x | 21 | | 6/27/16 | SU | EXT-74 | Air Pressure | Pass | 6/27/16 |
| 77 | SJ | 20/21/22 | | 99' N OF SEOS | P | 2 | x | 2 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 78 | CF | 20/21 | | 122' N OF SEOS | P | 4 | x | 4 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 79 | CF | | P-21 | BETWEEN R-78 & R-80 | B | | x | | 156 | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 80 | CF | 21/23 | P-21 | 128' N OF SEOS & 11' W | P | 1 | x | 1 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 81 | PB | 20/21 | P-21 | 171' N OF SEOS & 3' E (PB 4") | P | 3 | x | 5 | | 6/27/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 82 | BO | 22/23 | | 54' N OF SEOS | P | 2 | x | 4 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 83 | SJ | 21/22/23 | | 99' N OF SEOS | P | 6 | x | 14 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 84 | SJ | 23/24/25 | | 17' N OF SEOS | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 85 | BO | 23/24 | | 40' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 86 | CF | 23/24 | P-23 | BETWEEN R-85 & R-87 | B | | x | | 72 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 87 | CF | 23/24 | P-23 | 48' N OF SEOS & 11' W | P | 2 | x | 9 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 88 | CF | 22/23 | P-23 | 51' N OF SEOS & 8' E | P | 3 | x | 5 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 89 | CF | 23/24 | | 74' N OF SEOS | P | 2 | x | 6 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 90 | CF | 23/24 | | 79' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 91 | DS-6 | 23/24 | | 105' N OF SEOS | P | 2 | x | 6 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 92 | SJ | 24/25/26 | | 17' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 93 | CF | 24/26 | | 157' N OF SEOS | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 94 | CF | 24/26 | P-26 | BETWEEN R-93 & R-95 | B | | x | | 72 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 95 | CF | 24/26 | P-26 | 156' N OF SEOS & 8' E | P | 2 | x | 4 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 96 | CF | 24/26 | P-26 | 137' N OF SEOS & 2' E | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 97 | CF | 24/26 | P-26 | 143' N OF SEOS & 6'E FROM R-96 | B | | x | | 132 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 98 | SI | 24/26 | P-26 | 167' N OF SEOS & 8' E | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 99 | DO | 26/27 | P-26 | 166' N OF SEOS & 10' W | P | 2 | x | 3 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 100 | BO | 26/27 | | 26' N OF SEOS | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 101 | CF | 26/27 | | 55' N OF SEOS | P | 3 | x | 8 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 102 | PB | 26/27 | P-27 | 124' N OF SEOS & 3' E (PB 8") | P | 4 | x | 5 | 24 | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 103 | CF | 26/27 | P-26 | 185' N OF SEOS & 12' W | P | 2 | x | 2 | | 6/29/16 | SU | EXT-74 | Vacuum | Pass | 6/29/16 |
| 104 | AO | 19/20 | | 196' N OF SEOS | P | 5 | x | 23 | | 6/30/16 | BS | W-4131 | Air Pressure | Pass | 6/30/16 |
| 105 | AO | 18/19 | | 196' N OF SEOS | P | 5 | x | 23 | | 6/30/16 | BS | W-4131 | Air Pressure | Pass | 6/30/16 |
| 106 | AO | 17/18 | | 196' N OF SEOS | P | 5 | x | 8 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 107 | CF | 19/20/R-26 | | 194' N OF SEOS | P | 3 | x | 5 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 108 | CF | 18/19 | | 194' N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 109 | CF | 17/18 | P-18 | 194' N OF SEOS & 4' E | P | 2 | x | 2 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 110 | CF | 19/20 | P-19 | 126' N OF SEOS & 8' W | P | 2 | x | 4 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 111 | CF | 19/20 | P-19 | BETWEEN R-110 & R-112 | B | | x | | 120 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 112 | CF | 19/20 | P-19 | 136' N OF SEOS & 2' W | P | 2 | x | 2 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 113 | DS-7 | 13/14 | | 91' N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 114 | DS-8 | R-105/18 | P-18 | 195' N OF SEOS & 9' W | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 115 | DSX-3 | R-79 | P-21 | 125'N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 116 | DS-9 | 18/19 | | 101' N OF SEOS | P | 3 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 117 | CF | 26/27 | | 180' N OF SEOS | P | 6 | x | 11 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 118 | CF | 26/27 | P-27 | 179' N OF SEOS 2'E | P | 4 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 119 | CF | 26/27 | P-27 | 179' N OF SEOS 4'E | P | 5 | x | 6 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 120 | CF | 26/27 | P-27 | 179' N OF SEOS 6'E | P | 3 | x | 7 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 121 | CF | 27/28 | P-27 | 179' N OF SEOS & 14'W | P | 3 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 122 | CF | 27/28 | P-27 | BETWEEN R-121 & R-123 | B | | x | | 108 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 123 | CF | 27/28 | | 173'N OF SEOS | P | 3 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 124 | BO | 27/28 | | 177' N OF SEOS | P | 2 | x | 5 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 125 | SJ | 27/28/R-30 | | 129' N OF SEOS | P | 2 | x | 3 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 126 | SJ | 27/28/R-30 | P-28 | 129'N OF SEOS & 3' E | P | 2 | x | 2 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 127 | CF | 26/27 | P-27 | 208'N OF SEOS & 2'E | P | 5 | x | 8 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 128 | CF | 26/27 | P-26 | 216'N OF SEOS (FROM R-127) | B | | x | | 108 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 129 | CF | 27/R-127 | P-26 | 205'N OF SEOS(FROM R-127) | B | | x | | 108 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 6/30/16 |
| 130 | AO | 27/28 | | 175'N OF SEOS | P | 6 | x | 18 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 131 | AO | 27/28 | | 200'N OF SEOS | P | 5 | x | 20 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 132 | CF | 27/28 | | 133'N OF SEOS | P | 5 | x | 8 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 133 | DS-10 | 27/28 | | 155'N OF SEOS | P | 2 | x | 5 | | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 134 | CF | 27/28 | | BETWEEN R-132 & R-154 | B | | x | | 72 | 6/30/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 135 | CF | 19/20 | P-20 | 115' N OF SEOS & 6'E | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 136 | CF | 19/20 | P-20 | BETWEEN R-135 & R-137 | B | | x | | 60 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 137 | CF | 19/20 | P-20 | 115'N OF SEOS & 3'E | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 138 | BO | 29/31 | | 11'N OF SEOS | P | 2 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 139 | CF | 29/31 | P-29 | BETWEEN R-140 & R-141 | B | | x | | 108 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 140 | CF | 29/31 | P-29 | 54'N OFSEOS 10'W | P | 1 | x | 1 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 141 | CF | 29/31 | | 54' N OF SEOS | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 142 | SJ | 29/30/31 | | 159' N OF SEOS | P | 3 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 143 | BO | 29/30 | | 169' N OF SEOS | P | 2 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 144 | CF | 29/30 | P-29 | BETWEEN R-145 & R-146 | B | | x | | 96 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 145 | CF | 29/30 | P-29 | 175' N OF SEOS & 10'W | P | 3 | x | 7 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 146 | CF | 29/30 | P-29 | 180' N OF SEOS & 2'W | P | 2 | x | 2 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 147 | DSX-4 | R-148 | P-32 | 96'N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 148 | DS-11 | 31/32 | | 96' N OF SEOS | P | 4 | x | 7 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 149 | CF | 31/32 | P-32 | 65' N OF SEOS & 4'E | P | 3 | x | 12 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 150 | CF | 32/34 | P-32 | BETWEEN R-149 & R-150 | B | | x | | 108 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 151 | CF | 32/34 | P-32 | 73' N OF SEOS 13' W | P | 1 | x | 1 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 152 | SJ | 30/31/32 | | 158' N OF SEOS | P | 2 | x | 13 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 153 | SJ | 32/33/34 | | 130'N OF SEOS | P | 2 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 154 | CF | 27/28 | | 115' N OF SEOS | P | 8 | x | 10 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 155 | BO | 27/28 | | 102' N OF SEOS | P | 3 | x | 4 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 156 | PB | 28/29 | | 15' N OF SEOS (8"PB) | P | 4 | x | 5 | 24 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 157 | SJ | 33/34/35 | | 130' N OF SEOS | P | 2 | x | 2 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 158 | DS-12 | 34/35 | | 21' N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 159 | SJ | 35/36/37 | | 82' N OF SEOS | P | 2 | x | 3 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 160 | SJ | 36/37/38 | | 82' N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 161 | DS-13 | 36/38 | | 215' N OF SEOS | P | 2 | x | 5 | | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 162 | CF | 36/38 | P-38 | BETWEEN R-161 & R-163 | B | | x | | 96 | 7/1/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 163 | CF | 36/38 | P-38 | 205' N OF SEOS & 10'E | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 164 | CF | 37/38 | P-37 | 3'N OF SEOS & 9' W | B | | x | | 72 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 165 | CF | 37/38 | P-37 | 6'N OF SEOS & 10' W | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 166 | CF | 37/38 | | 3'N OF SEOS | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 167 | SJ | 38/39/40 | | 35' N OF SEOS | P | 3 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 168 | CF | 38/39 | | 109' N OF SEOS | P | 3 | x | 5 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 169 | BO | 38/39 | | 213' N OF SEOS | P | 3 | x | 5 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 170 | SI | 38/39 | P-38 | 162' N OF SEOS 7' W | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 171 | AO | 40/39 | | BETWEEN R-167 & R-172 | C | 2 | x | 23 | | 7/7/16 | BS | W-4131 | Air Pressure | Pass | 7/7/16 |
| 172 | SJ | 39/40/41 | | 35'N OF SEOS | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 173 | CF | 39/41 | P-41 | 167' N OFSEOS 5'E | P | 4 | x | 13 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 174 | CF | 39/41 | P-39 | 177' N OF SEOS 4' W | P | 3 | x | 10 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 175 | CF | 39/41 | | 197' N OF SEOS | P | 2 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 176 | BO | 39/41 | | 208' N OF SEOS | P | 2 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 177 | CF | 41/42 | | 70' N OF SEOS | P | 5 | x | 20 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 178 | CF | 41/42 | P-41 | 92' N OF SEOS & 5'W | P | 3 | x | 6 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 179 | CF | 41/42 | | 105' N OF SEOS | P | 3 | x | 30 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 180 | CF | 41/42 | P-42 | 156' N OF SEOS & 5'E | P | 6 | x | 17 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 181 | CF | 41/42 | P-42 | BETWEEN R-180 & R-187 | B | | x | | 120 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 182 | CF | 39/41 | P-41 | 193' N OF SEOS & 4' E | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 183 | CF | 39/41 | P-41 | BETWEEN R-182 & R-175 | B | | x | | 48 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 184 | DS-14 | 41/42 | | 139' N OF SEOS | P | 2 | x | 6 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 185 | DSX-5 | R-179 | P-42 | 100' N OF SEOS & 3' E | P | 2 | x | 6 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 186 | CF | 41/42 | P-42 | 157' N OF SEOS & 10' E | P | 4 | x | 8 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 187 | CF | 41/42 | P-42 | 162' N OF SEOS & 8'E | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 188 | CF | 41/42 | P-42 | 138' N OF SEOS & 10'E | P | 4 | x | 10 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 189 | PB | 42/43 | | 136' N OF SEOS (48" MH ) | P | 7 | x | 9 | 48 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 190 | CF | 42/43 | P-43 | 127' N OF SEOS & 5' E | P | 5 | x | 13 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 191 | CF | 42/43 | P-43 | 202' N OF SEOS & 10' E | P | 2 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 192 | CF | 42/43 | P-43 | BETWEEN R-191 & R-193 | B | | x | | 120 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 193 | CF | 42/43 | | 210' N 0F SEOS | P | 6 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 194 | CF | 43/44 | P-43 | 175' N OF SEOS & 5'W | P | 2 | x | 2 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 195 | CF | 43/44 | P-43 | BETWEEN R-194 & R-219 | B | | x | | 24 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 196 | CF | 42/43 | P-42 | BETWEEN R-199 & R-193 | B | | x | | 48 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 197 | CF | 42/43 | P-42 | BETWEEN R-198 & R-193 | B | | x | | 60 | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/8/16 |
| 198 | CF | 42/43 | P-42 | 210' N 0F SEOS & 7'W | P | 3 | x | 4 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/7/16 |
| 199 | CF | 42/43 | P-42 | 215' N OF SEOS & 7'W | P | 3 | x | 3 | | 7/7/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 200 | CF | 42/43 | P-42 | 114'N OF SEOS & 11'W | P | 3 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 201 | CF | 42/43 | P-42 | BETWEEN R-200 & R-202 | B | | x | | 168 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 202 | CF | 42/43 | P-42 | 128'N OF SEOS & 10'W | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 203 | CF | 42/43 | P-43 | 91' N OF SEOS & 10'E | P | 4 | x | 10 | | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 204 | CF | 42/43 | P-43 | BETWEEN R-203 & R-214 | B | | x | | 120 | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 205 | CF | 42/43 | P-43 | BETWEEN R-206 & R-215 | B | | x | | 108 | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 206 | CF | 42/43 | P-43 | 103' N OF SEOS & 20'E | P | 2 | x | 5 | | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |
| 207 | CF | 42/43 | P-43 | 103' N OF SEOS & 9'E | P | 3 | x | 13 | | 7/8/16 | PHOU | EXT-75 | Vacuum | Pass | 7/9/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 208 | CF | 43/44 | P-43 | 160' N OF SEOS & 13'W | P | 5 | x | 17 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 209 | CF | 43/44 | P-43 | 180' N OF SEOS & 10'W | P | 6 | x | 22 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 210 | CF | 42/43 | P-43 | BETWEEN R-211 & R-209 | B | | x | | 72 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 211 | CF | 42/43 | P-43 | 190'N OF SEOS & 8' E | P | 8 | x | 12 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 212 | DSX-6 | R-180 | P-42 | 153'N SEOS & 5'E | P | 3 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 213 | SJ | 43/44/45 | | 36'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 214 | CF | 43/44 | | 81'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 215 | CF | 43/44 | | 107'N OF SEOS | P | 2 | x | 4 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 216 | BO | 43/44 | | 133'N OF SEOS | P | 2 | x | 4 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 217 | CF | 43/44 | | 178'N OF SEOS | P | 2 | x | 4 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 218 | CF | 43/44 | | 185'N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 219 | CF | 43/44 | | BETWEEN R-218 & R-217 | B | | x | | 60 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 220 | SJ | 43/44/44A | | 231'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 221 | SJ | 44/44A/43 | | 250' N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 222 | SI | 45/46 | P-45 | 11'N OF 4'W | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 223 | SJ | 44/45/46 | | 35'N OF SEOS | P | 2 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 224 | DSX-7 | R-204 | P-43 | 80'N OF SEOS 4'W | P | 4 | x | 2 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 225 | CF | 44/46 | P-44 | 215'N SEOS & 12'E | P | 10 | x | 16 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/9/16 |
| 226 | DS-15 | 43/44 | | 222'N OF SEOS | P | 2 | x | 4 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 227 | CF | 43./44 | P-44 | 216'N OF SEOS 5'E | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 228 | CF | 43/44 | P-44 | BETWEEN R-227 & R-229 | B | | x | | 24 | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 229 | CF | 43/44 | P-44 | 216'N OF SEOS 7'E | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 230 | DS-17 | 45/46 | | 24'N OF SEOS | P | 2 | x | 4 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 231 | DS-16 | 46/47 | | 146'N OF SEOS | P | 2 | x | 4 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 232 | SJ | 46/47/48 | | 115'N OF SEOS | P | 2 | x | 7 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 233 | SJ | 47/48/49 | | 116'N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 234 | CF | 47/49 | P-47 | 164' N OF SEOS & 2'W | P | 3 | x | 8 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 235 | BO | 46/47 | | 258'N OF SEOS | P | 2 | x | 2 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 236 | CF | 46/47 | | 266'N OF SEOS | P | 5 | x | 3 | | 7/8/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 237 | PB | 44/46 | P-46 | 147'N OF SEOS 8'E(8"PB) | P | 4 | x | 5 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 238 | AO | 46/47 | | 19'S OF NEOS (CAP 19') | P | 2 | x | 19 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 239 | CF | 44/46 | P-44 | 230'N OF SEOS 7'W | P | 2 | x | 2 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 240 | CF | 44/46 | P-44 | BETWEEN R-239 & R-241 | B | | x | | 108 | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 241 | CF | 44/46 | P-44 | 241'N SEOS 7'W | P | 2 | x | 2 | | 7/11/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 242 | SI | 49/50 | | 3'N OF SEOS | B | | x | | 60 | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 243 | BO | 49/50 | | 6'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 244 | DS-18 | 49/50 | | 251' N OF SEOS | P | 2 | x | 5 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 245 | BO | 49/50 | | 271'N OF SEOS | P | 2 | x | 4 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 246 | SJ | 50/52/53 | | 20'N OF SEOS | P | 2 | x | 3 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/1/16 |
| 247 | CF | 50/52 | P-50 | 53'N OF SEOS 2'W | P | 2 | x | 2 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/11/16 |
| 248 | CF | 50/52 | P-50 | 65'N OF SEOS 10'W | P | 3 | x | 5 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 249 | CF | 50/52 | P-50 | BETWEEN R-247 & R-248 | B | | x | | 108 | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 250 | SJ | 50/51/52 | | 74'N OF SEOS | P | 3 | x | 4 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 251 | CF | 50/51 | P-50 | 111'N OF SEOS & 2'W | P | 3 | x | 5 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 252 | CF | 50/51 | P-50 | 102N OF SEOS 8'W | P | 2 | x | 8 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 253 | CF | 50/51 | P-50 | BETWEEN R-251 & R-252 | B | | x | | 72 | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 254 | CF | 50/51 | | 214N OF SEOS | P | 3 | x | 10 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 255 | CF | 50/51 | | 274'N OF SEOS | P | 3 | x | 3 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 256 | DS-19 | 53/54 | | 20' N OF SEOS (AT SJ FOR 52/53/54) | P | 3 | x | 8 | | 7/12/16 | SU | EXT-249 | Vacuum | Pass | 7/13/16 |
| 257 | SJ | 51/54/52 | | 74'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 258 | SJ | 54/56/57 | | 30'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 259 | SJ | 54/55/56 | | 103'N OF SEOS | P | 2 | x | 2 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 260 | DS-20 | 55/56 | | 103'N OF SEOS ON P55/P56 | P | 2 | x | 6 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 261 | PB | 54/55 | P-55 | 285'N OF SEOS 20'E (4" PB) | P | 4 | x | 4 | | 7/12/16 | SU | EXT-74 | Vacuum | Pass | 7/13/16 |
| 262 | SJ | 56/57/58 | | 30'N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 263 | SJ | 55/56/58 | | 103'N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 264 | BO | 55/58 | | 273' N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 265 | BO | 55/58 | | 285'N OF SEOS | P | 2 | x | 4 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 266 | CF | 55/58 | | 289'N OF SEOS | B | | x | | 72 | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 267 | SJ | 58/59/60 | | 94'N OF SEOS | P | 3 | x | 3 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 268 | SJ | 59/60/61 | | 94'N OF SEOS | P | 3 | x | 3 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 269 | BO | 59/61 | | 278'N OF SEOS | P | 2 | x | 3 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 270 | SJ | 61/62/63 | | 194'N OF SEOS | P | 2 | x | 6 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 271 | DS-21 | 58/59 | | 266'N OF SEOS | P | 2 | x | 4 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 272 | DS-22 | 61/63 | | 137' N OF SEOS | P | 2 | x | 5 | | 7/13/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 273 | WR | 50/51 | | 165'N OF SEOS | P | 3 | x | 10 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 274 | WR | 50/51 | P-51 | 170'N OF SEOS 5'E | P | 3 | x | 10 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 275 | CF | 50/51 | P-51 | BETWEEN R-273 & R-276 | B | | x | | 60 | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 276 | BO | 50/51 | | 158'N OF SEOS | P | 3 | x | 4 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 277 | SJ | 62/63/64 | | 193'N OF SEOS | P | 2 | x | 3 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 278 | CF | 64/65 | | 187'N OF SEOS | P | 2 | x | 3 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 279 | CF | 64/65 | | 216'N OF SEOS | P | 2 | x | 3 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 280 | CF | 64/65 | | 115'N OF SEOS | P | 5 | x | 10 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 281 | SJ | 65/66/67 | | 116'N OF SEOS | P | 2 | x | 2 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 282 | CF | 64/65 | P-65 | BETWEEN R-278 & R-283 | B | | x | | 120 | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 283 | CF | 64/65 | P-65 | 193'N OF SEOS & 12'E | P | 2 | x | 4 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 284 | CF | 64/65 | P-65 | 215'N OF SEOS & 11'E | P | 2 | x | 9 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 285 | CF | 64/65 | P-65 | BETWEEN R-279 & R-284 | B | | x | | 60 | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 286 | DSX-8 | R-270 | P-61 | 193'N OF SEOS | P | 2 | x | 6 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 287 | DS-23 | 64/65 | | 17'N OF SEOS | P | 2 | x | 6 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 288 | PB | 65/67 | P-65 | 90'N OF SEOS & 7'W (8") | P | 2 | x | 5 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 289 | SJ | 66/67/68 | | 115' OF SEOS | P | 2 | x | 2 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 290 | CF | 66/68 | P-66 | 167'N OF SEOS & 4'W | P | 6 | x | 10 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 291 | DS-24 | 66/68 | | 148'N OF SEOS | P | 2 | x | 4 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 292 | PB | 66/68 | P-66 | 148'N OF SEOS & 3'W (8") | P | 6 | x | 8 | | 7/14/16 | SU | EXT-74 | Vacuum | Pass | 7/14/16 |
| 293 | BO | 68/71 | | 99' N OF SEOS | P | 3 | x | 5 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 294 | SJ | 68/70/71 | | 147' N OF SEOS | P | 5 | x | 3 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 295 | SJ | 68/69/70 | | 216' N OF SEOS | P | 2 | x | 2 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 296 | DS-25 | 68/69 | | 250' N OF SEOS | P | 3 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 297 | CF | 68/70 | P-70 | 155'N OF SEOS & 12' E | P | 4 | x | 4 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 298 | CF | 70/72 | P-70 | BETWEEN R-297 & R-299 | B | | x | | 109 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 299 | SJ | 71/70/72 | | 155'N OF SEOS | P | 2 | x | 16 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 300 | DSX-9 | R-299 | P-72 | 153'N OF SEOS | P | 2 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 301 | CF | 70/72 | | 200'N OF SEOS | P | 5 | x | 8 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 302 | SJ | 69/70/72 | | 217'N OF SEOS | P | 2 | x | 2 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 303 | CF | 72/74 | P-72 | 54'N OF SEOS & 4'W | P | 3 | x | 9 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 304 | CF | 72/74 | P-72 | BETWEEN R-303 & R-322 | B | | x | | 109 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 305 | CF | 72/74 | P-72 | BETWEEN R-306 & R-317 | B | | x | | 109 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 306 | CF | 72/74 | | 104'N OF SEOS | P | 2 | x | 3 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 307 | CF | 72/74 | | 114'N OF SEOS | P | 2 | x | 3 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 308 | CF | 72/74 | P-74 | BETWEEN R-307 & R-318 | B | | x | | 84 | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 309 | CF | 74/74 | | 164'N OF SEOS | P | 4 | x | 9 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 310 | CF | 72/74 | | 172'N OF SEOS | P | 4 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 311 | SJ | 72/73/74 | | 220'N OF SEOS | P | 3 | x | 4 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 312 | DS-26 | 72/74 | | 145'N OF SEOS | P | 2 | x | 6 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 313 | PB | 72/74 | P-72 | 158'N OFSEOS & 6'W (8" PB) | P | 2 | x | 2 | 24 | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 314 | CF | 74/75 | | 76'N OF SEOS | P | 3 | x | 7 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 315 | CF | 74/75 | | 209'N OF SEOS | P | 5 | x | 7 | | 7/25/16 | SU | EXT-74 | Vacuum | Pass | 7/25/16 |
| 316 | SJ | 74/73/75 | | 218'N OF SEOS | P | 2 | x | 3 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 317 | CF | 72/74 | P-72 | 109'N OF SEOS & 7' W | P | 1 | x | 1 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 318 | CF | 72/74 | P-74 | 114'N OF SEOS & 9'E | P | 2 | x | 2 | | 7/25/16 | DM | EXT-75 | Vacuum | Pass | 7/25/16 |
| 319 | CF | 74/75 | P-75 | 95'N OF SEOS & 10'E | P | 3 | x | 5 | | 7/27/16 | SU | EXT-75 | Vacuum | Pass | 7/27/16 |
| 320 | CF | 74/75 | P-75 | BETWEEN R-319 & R-333 | B | | x | | 108 | 7/27/16 | SU | EXT-75 | Vacuum | Pass | 7/27/16 |
| 321 | CF | 72/74 | P-74 | 48'N OF SEOS & 2' E | P | 2 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 322 | CF | 72/74 | P-72 | 62'N OF SEOS & 8' W | P | 1 | x | 2 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 323 | CF | 74/75 | P-75 | 35'N OF SEOS &10' E | P | 2 | x | 2 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 324 | CF | 74/75 | P-75 | BETWEEN R-323 AND R-325 | B | | x | | 144 | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 325 | CF | 74/75 | P-75 | 50'N OF SEOS & 10' E | P | 1 | x | 1 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 326 | CF | 74/75 | P-75 | 157'N OF SEOS & 12' E | P | 2 | x | 2 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 327 | CF | 74/75 | P-75 | BETWEEN R-326 AND R-334 | B | | x | | 144 | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 328 | SI | 71/72 | P-72 | 77'N OF SEOS & 7' E | P | 2 | x | 2 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 329 | CF | 74/75 | P-75 | 164'N OF SEOS & 7'E | P | 2 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 330 | CF | 74/75 | P-75 | BETWEEN R-329 AND R-331 | B | | x | | 84 | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 331 | CF | 74/75 | P-75 | 173'N OF SEOS & 7'E | P | 3 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 7/27/16 |
| 332 | CF | 75/76 | | 8'N OF SEOS | P | 2 | x | 7 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 333 | CF | 75/76 | | 81'N OF SEOS | P | 3 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 334 | CF | 75/76 | | 151'N OF SEOS | P | 2 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 335 | BO | 75/76 | | 234'N OF SEOS | P | 2 | x | 4 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 336 | CF | 75/76 | | 254'N OF SEOS | P | 4 | x | 14 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 337 | DS-27 | 75/76 | | 24'N OF SEOS | P | 2 | x | 5 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 338 | DSX-10 | R-320 | P-75 | 82'N OF SEOS & 5'W | P | 2 | x | 5 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 339 | CF | 76/78 | | 4'N OF SEOS | P | 3 | x | 7 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 340 | SJ | 76/77/78 | | 40'N OF SEOS | P | 3 | x | 6 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 341 | CF | 78/79 | P-78 | 15'N OF SEOS & 4'W | P | 2 | x | 9 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 342 | CF | 76/78 | | 15'N OF SEOS | P | 2 | x | 5 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 343 | PB | 78/79 | P-78 | 15'N OF SEOS & 9'W (6"PB) | P | 2 | x | 4 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 344 | SJ | 77/78/79 | | 40'N OF SEOS | P | 3 | x | 3 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 345 | CF | 77/79 | P-79 | 138'N OF SEOS & 7'E | P | 2 | x | 15 | | 7/27/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 346 | CF | 77/79 | P-77 | 144'N OF SEOS 3'W | P | 6 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 347 | CF | 76/78 | | 25'N OF SEOS | P | 2 | x | 3 | | 7/27/16 | SU | EXT-75 | Vacuum | Pass | 8/2/16 |
| 348 | CF | 79/80 | P-79 | 133'N OF SEOS & 4'W | P | 5 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 349 | CF | 79/80 | P-79 | 129'N OF SEOS & 9' W | P | 2 | x | 3 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 350 | CF | 79/80 | P-79 | 131'N OFSEOS & 10' W | P | 2 | x | 2 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 351 | CF | 79/80 | P-79 | BETWEEN R-348 AND R-349 | B | | x | | 36 | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 352 | CF | 79/80 | P-79 | BETWEEN R-348 & R-353 | B | | x | | 36 | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 353 | CF | 79/80 | P-79 | 138'N OF SEOS & 2'W | P | 2 | x | 3 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 354 | CF | 79/80 | P-79 | 134'N OF SEOS & 3'W (ON R-348) | P | 3 | x | 3 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 355 | CF | 79/80 | | 167'N OF SEOS | P | 5 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 356 | CF | 79/80 | P-79 | 106'N OF SEOS & 4'W | P | 3 | x | 6 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 357 | PB | 80/81 | P-80 | 140' N OF SEOS & 1'W (48" MH) | P | 6 | x | 6 | 60 | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 358 | CF | 79/80 | P-79 | 207'N OF SEOS & 6'W | P | 4 | x | 10 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 359 | CF | 79/80 | P-79 | 208'N OF SEOS & 10'W | P | 3 | x | 7 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 360 | CF | 77/79 | P-79 | 148'N OF SEOS (ON R-346) | P | 2 | x | 2 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 361 | CF | 77/79 | P-77 | 137'N OF SEOS & 6'W | P | 1 | x | 2 | | 7/27/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 362 | CF | 80/82 | | 6'N OF SEOS | P | 2 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 363 | SJ | 80/81/82 | | 25'N OF SEOS | P | 2 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 364 | CF | 80/81 | | 130'N OF SEOS | P | 3 | x | 4 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 365 | CF | 80/81 | | 140'N OF SEOS | P | 3 | x | 15 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 366 | CF | 80/81 | P-80 | BETWEEN R-364 & R-365 | B | | x | | 36 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 367 | CF | 80/81 | P-80 | 140'NOF SEOS & 4'W | P | 3 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 368 | CF | 80/81 | | 150'N OF SEOS | P | 4 | x | 6 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 369 | CF | 80/81 | | 264'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 370 | SJ | 81/82/83 | | 25'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 371 | CF | 81/83 | P-81 | 31'N OF SEOS & 3'W | P | 2 | x | 6 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 372 | BO | 81/83 | | 145'N OF SEOS | P | 2 | x | 5 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 373 | CF | 81/83 | | 216'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 374 | SJ | 83/84/85 | | 52'N OF SEOS | P | 3 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 375 | CF | 83/84 | | 202'N OF SEOS | P | 3 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 376 | SJ | 84/85/86 | | 52'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 377 | CF | 84/86 | | 198'N OF SEOS | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 378 | SJ | 86/87/88 | | 96'N OF SEOS | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 379 | CF | 86/87 | P-86 | 205' N OF SEOS | P | 4 | x | 11 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 380 | PB | 76/78 | P-76 | 6'N OF SEOS & 4'W (8" PB) | P | 5 | x | 6 | 24 | 7/28/16 | DM | EXT-75 | Vacuum | Pass | 8/2/16 |
| 381 | CF | 86/88 | | 40'N OF SEOS | P | 2 | x | 2 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 382 | CF | 83/84 | P-83 | 197'N OF SEOS & 10'W | P | 3 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 383 | CF | 83/84 | P-83 | BETWEEN R-382 & R-375 | B | | x | | 120 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 384 | PB | 81/83 | P-81 | 32'N OF SEOS & 7'W (8" PB) | P | 2 | x | 4 | 24 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 385 | CF | 80/82 | P-80 | BETWEEN R-362 & R-386 | B | | x | | 120 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 386 | CF | 80/82 | P-80 | 10'N OF SEOS & 10W | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 387 | CF | 84/86 | P-86 | BETWEEN R-377 & R-379 | B | | x | | 86 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 388 | CF | 86/87 | P-87 | 250'N OF SEOS & 19'E | P | 3 | x | 12 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 389 | CF | 86/88 | P-86 | BETWEEN R-381 & R-390 | B | | x | | 120 | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 390 | CF | 86/88 | P-86 | 42'N OF SEOS & 9'W | P | 2 | x | 3 | | 7/28/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 391 | DS-26 B | 72/74 | | 154'N OF SEOS | P | 2 | x | 11 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 392 | DS-26 A | 72/74 | | 135'N OFSEOS | P | 2 | x | 11 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 393 | DS-28 | 81/83 | | 177'N OF SEOS | P | 2 | x | 5 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 394 | DSX-11 | R-365 | P-81 | 144'N OF SEOS &12'W | P | 2 | x | 5 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 395 | DSX-12 | R-387 | P-86 | 199'N OF SEOS & 4'E | P | 2 | x | 5 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 396 | CF | 86/87 | | 210'N OF SEOS | P | 4 | x | 14 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 397 | CF | 86/87 | P-86 | 210'N OF SEOS 7'W | P | 3 | x | 4 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 398 | CF | 86/87 | P-86 | 208'N OF SEOS 10'W | P | 3 | x | 15 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 399 | CF | 86/87 | P-87 | 200'N OF SEOS 9'E | P | 4 | x | 20 | | 8/2/16 | SU | EXT-74 | Vacuum | Pass | 8/2/16 |
| 400 | CF | 87/90 | | 115'N OF SEOS | P | 2 | x | 5 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 401 | CF | 87/90 | P-90 | BETWEEN R-400 & R-402 | B | | x | | 120 | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 402 | CF | 87/90 | P-90 | 115'N OF SEOS 13'E | P | 2 | x | 3 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 403 | BO | 87/90 | | 130'N OF SEOS | P | 2 | x | 5 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 404 | BO | 87/89/90 | | 150'N OF SEOS | P | 2 | x | 3 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 405 | SJ | 88/87/90 | | 97'N OF SEOS | P | 2 | x | 3 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 406 | CF | 90/91 | P-90 | 50'N OF SEOS 3'W | P | 3 | x | 6 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 407 | CF | 90/91 | P-90 | 49'N OF SEOS 7'W | P | 3 | x | 9 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 408 | PB | 90/91 | P-90 | 238'N OF SEOS 7'W (4" PB) | P | 4 | x | 10 | 24 | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 409 | PB | 90/91 | P-91 | 107'N OF SEOS 5'E (8" PB) | P | 4 | x | 4 | 24 | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 410 | CF | 91/92 | | 160' N OF SEOS | P | 6 | x | 17 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 411 | CF | 91/92 | | 180'N SEOS | P | 4 | x | 6 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 412 | CF | 92/93 | | 110'N OF SEOS | P | 3 | x | 5 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 413 | CF | 92/93 | P-92 | BETWEEN R-412 & R-414 | B | | x | | 84 | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 414 | CF | 92/93 | P-92 | 115'N OF SEOS & 11'W | P | 4 | x | 6 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 415 | CF | 87/89 | P-87 | 246' N OF SEOS & 4'W | P | 3 | x | 8 | | 8/3/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 416 | DS-29 | 90/91 | | 26'N OF SEOS | P | 2 | x | 5 | | 8/4/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 417 | DSX-13 | R-401 | P-90 | 116'N OF SEOS &7'E | P | 2 | x | 7 | | 8/4/16 | SU | EXT-74 | Vacuum | Pass | 8/4/16 |
| 418 | DO | 36/38 | P-36 | 212' N OF SEOS & 6'W | P | 2 | x | 2 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/5/16 |
| 419 | CF | 94/95 | | 45'N OF SEOS | P | 2 | x | 3 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/5/16 |
| 420 | CF | 94/95 | P-94 | BETWEEN R-419 & R-420 | B | | x | | 86 | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/5/16 |
| 421 | CF | 94/95 | P-94 | 45'N OF SEOS & 12'W | P | 4 | x | 6 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 422 | CF | 94/95 | P-94 | 149'N OF SEOS | P | 2 | x | 3 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 423 | CF | 94/95 | P-94 | BETWEEN R-422 & R-424 | B | | x | | 84 | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 424 | CF | 94/95 | P-94 | 149'N OF SEOS & 11'W | P | 4 | x | 6 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 425 | CF | 94/95 | P-94 | 186'N OF SEOS & 2'W | P | 2 | x | 2 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 426 | CF | 94/95 | P-94 | BETWEEN R-425 & R-427 | B | | x | | 132 | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 427 | CF | 94/95 | P-94 | 176'N OF SEOS & 12'W | P | 3 | x | 4 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 428 | SJ | 95/96/97 | | 14'N OF SEOS | P | 2 | x | 3 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 429 | SJ | 96/97/98 | | 14'N OF SEOS | P | 2 | x | 2 | | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 430 | PB | 97/98 | P-97 | 109'N OF SEOS 2'W (8"PB) | P | 2 | x | 4 | 24 | 8/5/16 | SU | EXT-74 | Vacuum | Pass | 8/8/16 |
| 431 | DS-30 | 97/98 | | 120'N OF SEOS | P | 2 | x | 5 | | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 432 | DSX-14 | R-430 | P-98 | 110'N OF SEOS | P | 2 | x | 5 | | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 433 | CF | 99/100 | P-100 | 92'N OF SEOS & 6'E | P | 3 | x | 7 | | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 434 | CF | 99/100 | | 97'N OF SEOS | P | 3 | x | 11 | | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 435 | CF | 99/100 | | 132'N OF SEOS | P | 2 | x | 3 | | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 436 | CF | 99/100 | P-100 | BETWEEN R-435 & R-437 | B | | x | | 108 | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 437 | CF | 99/100 | P-100 | 128'N OFSEOS & 8'E | P | 2 | x | 2 | | 8/8/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 438 | DS-31 | 79/80 | | 200'N OF SEOS | P | 2 | x | 5 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 439 | DS-32 | 86/87 | | 178'N OF SEOS | P | 2 | x | 5 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 440 | SJ | 100/101/102 | | 20'N OF SEOS | P | 3 | x | 5 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 441 | SJ | 101/102/103 | | 22'N OF SEOS | P | 2 | x | 4 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 442 | CF | 103/104 | | 40'N OF SEOS | P | 4 | x | 8 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 443 | SJ | 103/104/105 | | 188'N OF SEOS | P | 2 | x | 3 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 444 | BO | 103/105 | | 218'N OF SEOS | P | 2 | x | 4 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 445 | BO | 104/106 | | 62'N OF SEOS | P | 3 | x | 8 | | 8/9/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 446 | SJ | 104/105/106 | | 190'N OF SEOS | P | 2 | x | 3 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/11/16 |
| 447 | CF | 104/106 | P-106 | 150'N OF SEOS 13'E | P | 2 | x | 7 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 448 | CF | 104/106 | P-106 | BETWEEN R-447 & R-477 | B | | x | | 108 | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 449 | PB | 102/103 | P-103 | 113'N OF SEOS 13'E (8" PB) | P | 2 | x | 4 | 24 | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 450 | PB | 103/104 | P-104 | 6'N OF SEOS 5'E (6" PB) | P | 3 | x | 4 | 24 | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 451 | DS-33 | 104/106 | | 23'N OF SEOS | P | 2 | x | 6 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 452 | DSX-15 | R-445 | P-106 | 62'N OF SEOS | P | 2 | x | 6 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 453 | BO | 93/107 | | 3'N OF SEOS | P | 2 | x | 5 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 454 | BO | 93/107 | | 45'N OF SEOS | P | 3 | x | 6 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 455 | CF | 108/110 | P-108 | 115'N OF SEOS & 2'W | P | 5 | x | 15 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 456 | SJ | 108/109/110 | | 188'N OF SEOS | P | 2 | x | 3 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 457 | SI | 107/108 | | 2'N OF SEOS | P | 2 | x | 3 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 458 | CF | 94/110 | P-110 | 103'N OF SEOS & 9'W | P | 2 | x | 4 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 459 | CF | 94/110 | | BETWEEN R-458 & R-460 | B | | x | | 120 | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 460 | SJ | R-461/94 | | 110'N OF SEOS | P | 2 | x | 4 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 461 | AO | | P-110 | 110'N OF SEOS (BTWN R-460/R-455) | C | 2 | x | 22 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 462 | CF | 110/94 | | 115'N OF SEOS & 13'W | P | 3 | x | 8 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 463 | CF | 110/94 | P-110 | 132'N OF SEOS & 2'W | P | 4 | x | 5 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 464 | CF | 110/94 | P-110 | 136'N OF SEOS & 10'W | P | 4 | x | 12 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 465 | SJ | 94/110/109 | | 188'N OF SEOS | P | 2 | x | 3 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 466 | CF | 108/110 | P-108 | 110'N OF SEOS & 5'W | P | 3 | x | 11 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 467 | DS-34 | 94/110 | | 62'N OF SEOS | P | 2 | x | 5 | | 8/10/16 | SU | EXT-74 | Vacuum | Pass | 8/10/16 |
| 468 | AO | 94/110 | | 4' N OF SEOS (ON R-469) | P | 2 | x | 2 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/11/16 |
| 469 | AO | R-470 | P-94/P-95 | 4'N OF SEOS | P | 2 | x | 45 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/11/16 |
| 470 | AO | R-469 | P-94/P-95/P-96 | 2'N OF SEOS | P | 2 | x | 55 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/11/16 |
| 471 | AO | R-470/R-472 | P-96/P-98/P-99 | 2'N OF SEOS | P | 2 | x | 45 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/11/16 |
| 472 | AO | R-473/R-474 | P-100/P-101 | 2'N OF SEOS | P | 2 | x | 56 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/11/16 |
| 473 | AO | R-472/R-475 | 103/P-104/P-1 | 2'N OF SEOS | P | 3 | x | 25 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 474 | AO | R-472 | P-99/P-100 | 4'N OF SEOS | P | 3 | x | 3 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 475 | AO | R-473 | P-104/P-106 | 3'N OF SEOS | P | 2 | x | 3 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 476 | AO | R-469/R-470 | P-94/P-95 | 2'N OF SEOS | B | | x | | 276 | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 477 | CF | 106/111 | | 161'N OF SEOS | P | 2 | x | 3 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 478 | CF | 111/112 | P-112 | 46'N OF SEOS & 4'E | P | 4 | x | 10 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 479 | CF | 111/112 | P-111 | 74'N OF SEOS & 2'W | P | 3 | x | 7 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 480 | DO | 111/112 | P-111 | 236'N OF SEOS & 11'W | P | 2 | x | 3 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 481 | CF | 111/112 | P-111 | 140'N OF SEOS & 4'W | P | 3 | x | 9 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 482 | CF | 111/112 | P-111 | 142'N OF SEOS &14'W | P | 4 | x | 12 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 483 | CF | 111/112 | P-112 | 46' N OF SEOS &15'E | P | 2 | x | 7 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |

## *Environmental Specialties International Inc.*
## Repair Report

**Project Name** HONEYWELL SA6 NORTH CAP **Job # :** 12-11-1399 **Superintendent:** TONY UNG

**Material Type:** 60 MIL LLDP MICROSPIKE LINER **Primary** X **Pond**

**Job Description:** **Secondary** **Cell**

**Reported by :** KHAI S. SOK **Cap** X

**Other:**

| Damage Codes | | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | | LF Welded | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 484 | CF | 111/112 | P-112 | BETWEEN R-483 & R-487 | B | | x | | 96 | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 485 | CF | 111/112 | P-112 | 46'N OF SEOS & 11' E | B | | x | | 36 | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 486 | DO | 103/105 | P-103 | 236'N OF SEOS & 12'W | P | 2 | x | 3 | | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/12/16 |
| 487 | CF | 112/113 | | 46'N OF SEOS | P | 2 | x | 10 | | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 488 | BO | 112/113 | | 163'N OFSEOS | P | 3 | x | 3 | | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 489 | BO | 113/114 | | 66'N OF SEOS | P | 2 | x | 3 | | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 490 | DSX-16 | R-478 | P-112 | 47'N OF SEOS | P | 2 | x | 6 | | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 491 | DS-35 | 112/113 | | 114'N OF SEOS | P | 2 | x | 6 | | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 492 | PB | 112/113 | P-113 | 110'N OF SEOS & 10'E (48" MH) | P | 7 | x | 6 | 60 | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 493 | PB | 113/114 | P-114 | 206'N SEOS & 13'E (6" PB) | P | 2 | x | 7 | 24 | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 494 | CF | 113/114 | P-114 | 206'N OF SEOS &16'E | P | 2 | x | 10 | | 8/12/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 495 | CF | 111/106 | P-106 | 161'N OF SEOS & 9'W | P | 1 | x | 1 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 496 | CF | 111/106 | P-106 | BETWEEN R-495 & R-497 | B | | x | | 120 | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 497 | CF | 111/106 | P-106 | 172'N OF SEOS & 3'W | P | 2 | x | 2 | | 8/11/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 498 | CF | 112/113 | P-113 | 38'N OF SEOS & 7'E | P | 3 | x | 7 | | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 499 | CF | 113/114 | P-114 | 46'N OF SEOS & 7'E | P | 3 | x | 10 | | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 500 | CF | 113/114 | P-114 | BETWEEN R-499 & R-503 | B | | x | | 120 | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 501 | CF | 111/112 | P-111 | 115'N OF SEOS & 6' W | P | 2 | x | 14 | | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 502 | CF | 112/113 | P-113 | 152'N OF SEOS & 11' E | P | 2 | x | 15 | | 8/13/16 | SU | EXT-74 | Vacuum | Pass | 8/13/16 |
| 503 | CF | 114/115 | | 39'N OF SEOS | P | 2 | x | 3 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 504 | CF | 114/115 | | 205'N OF SEOS | P | 2 | x | 5 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 505 | SJ | 115/119/118 | | 106'N OF SEOS | P | 4 | x | 12 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 506 | BO | 116/115 | | 244'N OF SEOS | P | 3 | x | 3 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |

## *Environmental Specialties International Inc.*
## Repair Report

| | | | | | |
|---|---|---|---|---|---|
| **Project Name** | HONEYWELL SA6 NORTH CAP | **Job # :** | 12-11-1399 | **Superintendent:** | TONY UNG |
| **Material Type:** | 60 MIL LLDP MICROSPIKE LINER | **Primary** | X | **Pond** | |
| **Job Description:** | | **Secondary** | | **Cell** | |
| **Reported by :** | KHAI S. SOK | | | **Cap** | X |
| **Other:** | | | | | |

| Damage Codes | | | | | SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | 8356 | Vacuum | *S=South | C--Cap Strip |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | | Air Pressure | *N=North | P--Patch |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | 8434.25 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 507 | SJ | 118/116/117 | | 171'N OF SEOS | P | 2 | x | 3 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 508 | BO | 117/118 | | 171'N OF SEOS & 10'E | P | 4 | x | 5 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 509 | PB | 116/118 | P-116 | 176'N OF SEOS & 13'E (4" PB) | P | 4 | x | 4 | 24 | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 510 | CF | 118/116 | P-116 | BETWEEN R-509 & R-511 | B | | x | | 60 | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 511 | CF | 117/116 | P-116 | 171'N OF SEOS & 16'E | P | 2 | x | 5 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 512 | SJ | 115/116/118 | | 225'N OF SEOS | P | 3 | x | 6 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 513 | DS-36 | 118/117 | | 40'N OF SEOS | P | 2 | x | 6 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |
| 514 | DSX-17 | R-505 | P-118 | 106' N OF SEOS | P | 3 | x | 6 | | 8/15/16 | SU | EXT-74 | Vacuum | Pass | 8/15/16 |

**Repair Log**
*(Attachment 11:  Capping Update)*

**Non-conformance Log**
*(Attachment 11:  Capping Update)*

## Summary of Non-Compliance & Corrective Action Forms

***SA-6 North Cap Installation***

| Notice of Non-Compliance & Corrective Action Sheet Number | Date | Item | Associated Repair Number | Approx. Location | Follow Up Action Taken |
|---|---|---|---|---|---|
| 1 | 6/23/2016 | Subgrade Irregularity | R-10 | Panel P6 | Rock was removed from underneath geomembrane and hole was then patched with approximate 3 ft. by 3 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 2 | 6/29/2016 | Subgrade Irregularity | R-98 | Panel P26 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 3 | 7/6/2016 | Failed Spark Test | Gas Vent GV-5 | Gas Vent GV-5 | Spark identified during spark testing of vertical boot weld on Gas Vent GV-5 boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed duriing the test. |
| 4 | 7/6/2016 | Failed Spark Test | Well 115-W1-SO | Well 115-W1-SO | Spark identified during spark testing of vertical boot weld on Well 115-W1-SO boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed duriing the test. |
| 5 | 7/7/2016 | Subgrade Irregularity | R-170 | Panel P38 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 6 | 7/8/2016 | Subgrade Irregularity | R-222 | Panel P45 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 3 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 7 | 7/12/2016 | Subgrade Irregularity | R-242 | Panel P49 / P50 | Rock was removed from underneath LLDPE geomembrane along the southern edge of SA-6 North (approximately 3 ft. from the edge of the cap. As such, the edge of the LLDPE was cut to remove the stone. This cut was then repaired with an extrusion weld bead. Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the cut / bead was properly sealed (as outlined in Section 02372). |
| 8 | 7/27/2016 | Subgrade Irregularity | R-328 | Panel P72 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 2 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 9 | 7/28/2016 | Failed Destruct Sample | DS-26 | Panel P72 / P74 (Repair R-312) | Destruct sample DS-26 reported two coupons as EPA Break Classification Code "AD BRK". Although the peel and shear strength requirments were met, since the coupons broke at the weld and were not conisdering a Film Tearing Bond, the sample was reported as a failed sample. Two field samples (DS-26A and DS-26B) were cut 10 ft. from each side of DS-26 and field tested. Peel and shear field tests met the strength requirments and sample DS-26B (lesser strength values of both samples) was sent for laboratory analysis (results pending). |
| 10 | 8/5/2016 | Equipment Puncture | R-418 | Panel P36 | Equipment puncture through SA-6 North on Panel P36 (north end) as grounding rod was driven through liner. The puncture was exposed and a geomembrane patch was placed over the area and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut. Repairs were confirmed with vacuum box testing (vacuum box test passed), as per project specs. |
| 11 | 8/9/2016 | Failed Spark Test | Piezometer PZ4 | Piezometer PZ4 | Spark identified during spark testing of vertical boot weld on Piezometer PZ4 boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed during the test. |
| 12 | 8/9/2016 | Failed Spark Test | Well 115-E5-WO | Well 115-E5-SO | Spark identified during spark testing of vertical boot weld on Well 115-E5-SO boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed during the test. |
| 13 | 8/10/2016 | Subgrade Irregularity | R-457 | Panel P107 / P108 | Rock was removed from underneath geomembrane and hole was then patched with approximate 2 ft. by 3 ft. geomembrane patch and sealed with an extrusion weld with minimum of 4-inches beyond edges of cut, and confirmed with vacuum box testing (as per project specs). |
| 14 | 8/12/2016 | Failed Spark Test | Well 115-E4-SO | Well 115-E4-SO | Spark identified during spark testing of vertical boot weld on Well 115-E4-SO boot. Area of weld was grinded, rewelded, and re-tested. Spark retest passed as no sparks were observed during the test. |

**Subgrade Approval Forms**
*(Attachment 11: Capping Update)*

LANGAN

# Certificate of Soil Surface

Sheet # 16

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 305+40 TO ~STA. 304+60 | | |
| QA Monitor | LANGAN | Date | 8/3/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P88 (INSTALLED ON 7/28/16) APPROX 80 FT EAST FROM ~STA. 305+40 TO ~STA. 304+60. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/3/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | CAROLINE PARRIS |
| Date: | 8/3/16 |
| Title | QC MGR |
| Representing: | ANTAEUS |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8.
-SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT BY 8 FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>½"). NO GCL TO BE INSTALLED FROM APPROX. STA. 805+40 TO ± STA. 804+60

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 805+40 | LOOKING S | REFER TO PHOTO #3 (8/3/16) |
| | 2 PHOTO #4 | ~STA. 805+40 | LOOKING E | REFER TO PHOTO #4 (8/3/16) |
| 1. REFER TO 8/3/16 PHOTOGRAPH LOG PHOTOS 3 TO 5 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 17

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 304+60 TO ~STA. 303+75 | | |
| QA Monitor | LANGAN | Date | 8/4/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P93 (INSTALLED ON 8/3/16) APPROX. 85 FT. EAST FROM ~STA. 304+60 TO ~STA. 303+75. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS. GCL PLACED ALONG NORTH END OF CAP (~STA. 303+75) FOR AREA BELOW, TO 1FT. ABOVE SITE WATER TABLE

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/4/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | CAROLINE PANICO |
| Date: | 8/4/16 |
| Title | QC MGR |
| Representing: | ENTRADA |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT BY 8 FT. TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>1/2"). GCL PANELS ALONG NORTHERN EDGE OF CAP AT APPROX STA. 303+75 FOR AREAS BELOW (TO LFT ABOVE SITE CONTROL DATUM TABLE) @ APPROX EL. 7

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ± STA. 304+60 | LOOKING E | REFER TO PHOTO #3 (8/4/16) |
| | 2 PHOTO #4 | ± STA. 304+60 | LOOKING S | REFER TO PHOTO #4 (8/4/16) |
| 1. REFER TO 8/4/16 PHOTOGRAPH LOG PHOTOS 3 TO 5 FOR SUPPORTING SUBGRADE PHOTOS. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 18

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 303+75 TO ~STA. 303+15 | | |
| QA Monitor | LANGAN | Date | 8/5/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF TEMPORARY PANEL 3 (INSTALLED ON 8/4/16) APPROX 60 FT EAST FROM ~STA. 303+75 TO ~STA. 303+15. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS. GCL PLACED ALONG N END OF CAP FOR AREA BELOW (TO 1 FT. ABOVE) SITE WATER TABLE AS INDICATED ON DESIGN DRAWINGS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/5/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Gepsynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/5/16 |
| Title | QC Mgr |
| Representing: | Entact |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX 200 FT BY 8 FT. TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>1½"). GCL PLACED ALONG NORTHERN END OF CAP FROM ~STA. 303+75 TO ~STA 303+15. FOR AREAS BELOW (TO 1ST. ABOVE) SITE WATER TABLE @ APPROX EL. 7 AS SHOWN ON DESIGN DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | ~STA. 303+75 | LOOKING S | REFER TO PHOTO #5 (8/5/16) |
| | 2 PHOTO #6 | ~STA. 303+75 | LOOKING E | REFER TO PHOTO #6 (8/5/16) |
| 1. REFER TO 8/5/16 PHOTOGRAPH LOG PHOTOS 5 TO 8 FOR SUPPORTING SUBGRADE PHOTOS + GCL PLACEMENT | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 19


| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 North | Material Desc. | Geomembrane |
| Project No. | 100530001 | General Desc. | (Subgrade) Operations LCRS |
| Owner/ Contr. | Honeywell / AMEC FW | Cell No. | ~Sta. 303+15 to ~Sta. 302+70 |
| QA Monitor | Langan | Date | 8/8/16 |

Description of Soil Surface to be lined: Area immediately East of Panel P98 (Installed on 8/5/16) Approx 45 ft East from Approx ~Sta. 303+15 to ~Sta. 302+70. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with Project Specs. GCL placed along N end of Cap for Areas Below (to left Above) Site Water Table as shown on Design Drawings

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/8/16 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/8/16 |
| Title | QC Manager |
| Representing: | Anchor |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX ~200 FT BY 8 FT. TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT. ALL PLACED ALONG N END OF CAP FROM APPROX ~STA. 303+15 TO ~STA. 902+70. FOR AREAS BELOW (TO LEFT ABOVE) SITE WATER TABLE @ ~EL. 7 AS SHOWN ON DESIGN DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |

1.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 20

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE |
| Project No. | 100530001 | General Desc. | (Subgrade) Operations LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 302+70 TO ~STA. 301+70 |
| QA Monitor | LANGAN | Date | 8/9/16 |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF P100 (INSTALLED ON 8/8/16) APPROX 100 FT EAST FROM APPROX ~STA. 302+70 TO ~STA. 301+70. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS. GCL PLACED ALONG N END OF CAP FOR AREAS BELOW (TO 1FT. ABOVE) SITE WATER TABLE AS SHOWN ON DESIGN DRAWINGS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSHOUWER |
| Date: | 8/9/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/9/16 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02371-8
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WITNESS THE PLACEMENT AREA IN ARMOR 1200 FT BY SET TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT (>½"). GCL PLACED ALONG N END OF CAP FROM ARMOR ~STA. 302+70 TO ~STA. 301+70 FOR AREAS BELOW (TO 1FT. ABOVE) SITE WATER TABLE @ APPROX EL. 7 AS SHOWN ON DESIGN DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | ~STA 302+70 | LOOKING E | REFER TO PHOTO #9 (8/9/16) |
| | 2 PHOTO #10 | ~STA. 302+70 | LOOKING S | REFER TO PHOTO #10 (8/9/16) |
| 1. REFER TO 8/9/16 PHOTOGRAPH LOG PHOTOS 9 TO 12 FOR SUPPORTING SUBGRADE PHOTOS + GCL PLACEMENT | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 21

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 301+70 TO ~STA. 301+25 | | |
| QA Monitor | LANGAN | Date | 8/11/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P106 (INSTALLED ON 8/9/16) APPROX 45 FT. EAST FROM APPROX ~STA. 301+70 TO ~STA. 301+25. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS. GCL PLACED ALONG N END OF CAP FOR AREAS BELOW (TO 1FT ABOVE) SITE WATER TABLE AS SHOWN ON DESIGN DRAWINGS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DAN BOSWORTH |
| Date: | 8/11/16 |
| Title | LEAD GM ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/11/16 |
| Title | QC Manager |
| Representing: | Entrak |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX ~200 FT BY 8 FT TRANSECTS TO OBSERVE SOIL CONDITIONS AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO GCL PLACEMENT (>½"). GCL PLACED ALONG N END OF CAP FROM ~STA. 301+70 TO ~STA. 301+25 FOR AREAS BELOW (TO LFT. ABOVE) SITE WATER TABLE @ APPROX EL. 7 AS SHOWN ON DESIGN DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | ~STA. 301+70 | LOOKING S | REFER TO PHOTO #9 (8/11/16) |
| | 2 PHOTO #10 | ~STA. 301+70 | LOOKING S | REFER TO PHOTO #10 (8/11/16) |

1. REFER TO 8/11/16 PHOTOGRAPH LOG PHOTOS 9 TO 12 FOR SUPPORTING SUBGRADE PHOTOS + GCL PLACEMENT

2.

LANGAN

# Certificate of Soil Surface

Sheet # 22

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 301+25 TO ~STA. 300+80 | | |
| QA Monitor | LANGAN | Date | 8/12/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P112 (INSTALLED ON 8/11/16) APPROX 45 FT. EAST FROM ~STA. 301+25 TO ~STA. 300+80. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AND IN CONFORMANCE WITH PROJECT SPECS. GCL PLACED ALONG N END OF CAP FOR AREAS BELOW (TO LEFT ABOVE) SITE WATER TABLE AT ~340' ON DESIGN DRAWINGS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DAN BOSLOUGH |
| Date: | 8/12/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/12/16 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8.
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX. 200 FT BY 8FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT
GCL PLACED ALONG N END OF CAP FROM APPROX ~STA. 301+25 TO ~STA. 300+80 FOR AREAS BELOW (TO LFT. ABOVE) SITE WATER TABLE & APPROX. EL. 17 AS SHOWN ON DESIGN DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | ~STA. 301+25 | LOOKING N | REFER TO PHOTO #9 (8/12/16) |
| | 2 PHOTO #10 | ~STA. 301+25 | LOOKING S | REFER TO PHOTO #10 (8/12/16) |

1. REFER TO 8/12/16 PHOTOGRAPH LOG PHOTOS 9 TO 12 FOR SUPPORTING SUBGRADE PHOTOS + GCL PLACEMENT

2.

LANGAN

# Certificate of Soil Surface

Sheet # 23

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 NORTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 300+80 TO ~STA. 300+00 (EEO5) | | |
| QA Monitor | LANGAN | Date | 8/13/16 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST OF PANEL P114 (INSTALLED ON 8/12/16) APPROX 80 FT. EAST FROM ~STA. 300+80 TO ~STA. 300+00 (EEO5). SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (≥½") AND IN CONFORMANCE WITH PROJECT SPECS. GCL PLACED ALONG N AND E END OF CAP FOR AREAS BELOW (TO BE ABOVE) SITE WATER TABLE. AS SHOWN ON DESIGN DRAWINGS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DAN BOSWORTH |
| Date: | 8/13/16 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/13/16 |
| Title | QC Manager |
| Representing: | Anteon |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (≤ ½") AS OUTLINED IN SECTION 02372-8
- SUBGRADE OBSERVED BY FIELD ENGINEER WHO WALKED THE PLACEMENT AREA IN APPROX ≤200FT BY 50FT TRANSECTS TO OBSERVE SOIL COMPACTION AS WELL AS ITEMS REQUIRING REMOVAL PRIOR TO PANEL PLACEMENT. GCL PLACED ALONG NORTH + EAST END OF CAP FROM APPROX STA. 300+80 TO ~STA 300+00 (EDGE OF (AND) FOR AREAS BELOW TO LFT. ABOVE SITE WATER TABLE @ APPROX EL. 7 AS SHOWN ON DESIGN DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #8 | ~STA. 300+40 | LOOKING N | REFER TO PHOTO #8 (8/13/16) |
| | 2 PHOTO #9 | ~STA. 300+80 | LOOKING N | REFER TO PHOTO #9 (8/13/16) |
| 1. REFER TO 8/13/16 PHOTOGRAPH LOG PHOTOS 8 TO 11 FOR SUPPORTING SUBGRADE PHOTOS + GCL PLACEMENT | | | | 2. |

**QA Photo Log**
*(Attachment 11:  Capping Update)*

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (08/02/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
8/2/16

**Direction Taken:**

Looking south along SA-6 North Panel P66/ P67 (approximate Sta. 308+35).

**Description:**

ESI deploying GDL over approved LLDPE geomembrane (Panels P66 / P67 and P68). GDL secured with white plastic fasteners spaced at a maximum of 5 ft. with the top layer of geotextile sewn.

.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (08/02/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |


**Date:**
8/2/16

**Direction Taken:**

SA-6 North – Panel Seam P72 / P74 (Repair R-391)

**Description:**

ESI conducting vacuum box activities for extrusion weld patch R-391. Two additional samples were cut Approximately 10 ft. from each side of DS-26, patched, sealed with an extrusion weld, and vacuum box tested.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (08/03/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
8/3/16

**Direction Taken:**

Looking north / northeast along SA-6 North (from approximate Sta. 304+80).

**Description:**

GVL deployed along approved soil subgrade up to approximate Sta. 304+60. GVL secured with white plastic fasteners spaced at maximum of 5 ft. and top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (08/03/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
8/3/16

**Direction Taken:**

Looking south / southeast along SA-6 North (approximate Sta. 305+40).

**Description:**

ESI conducting fusion welding along LLDPE geomembrane Panel Seam P88 and P90.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (08/04/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
8/4/16

**Direction Taken:**

Looking north along northern end of SA-6 North (approximate Sta. 303+75).

**Description:**

GCL placed along areas below (to 1 ft. above) the site water table. GCL seams sealed with bentonite and leistered in place.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (08/05/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |


**Date:**
8/5/16

**Direction Taken:**

SA-6 North – Panel P94 / P95 seam

**Description:**

ESI conducting non-destructive testing (pressure testing) along Panel P94 / P95 seam. Seam pressurized to 30 psi and held for 5 minutes with less than 4 psi loss.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (08/05/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/16

**Direction Taken:**

SA-6 North – Injection Well 088-IW-02

**Description:**

ESI completing boot penetration for Injection Well 088-IW-02 located on Panel P97.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (08/08/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/8/16

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 304+60).

**Description:**

ESI deploying two panels of orange GDL over approved LLDPE geomembrane. GDL placed up to temporary panels installed 8/4/16. GDL secured with white plastic fasteners spaced at a maximum of 5 ft. with top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (08/09/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
8/9/16

**Direction Taken:**

SA-6 North – Gas Vent GV-2

**Description:**

ESI conducting spark testing for Gas Vent GV-2. Prior to spark testing, methane testing was conducted and yielded a concentration of 0.0%, thus spark testing was conducted and no sparks were observed (spark test passed).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (08/10/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | **100530001** |

**Date:**
8/10/16

**Direction Taken:**

SA-6 North – Panel Seam P102 / P103 / P104

**Description:**

ESI conducting repair activities for seam joint at Panel P102 / P103 / P104 (panels installed on 8/9/16).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (08/10/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
8/.10/16

**Direction Taken:**

SA-6 North – Panel P110

**Description:**

ESI conducting custom fit repairs along Panel P110.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (08/13/16)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 North Capping | SA-6 North (North of SA-7) Jersey City, New Jersey | 100530001 |

**Date:**
8/13/16

**Direction Taken:**

Looking north along SA-6 North (approximate Sta. 300+60)

**Description:**

LLDPE geomembrane installed over GVL and GCL to east end of cap (approximate Sta. 300+00)



**Daily QA Reports (Langan)**
*(Attachment 11:  Capping Update)*

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/2/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 78/85° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #21**
**AmecFW**: Stu Bills, Dave Ambrose, Josh Boynton
**Langan:** Dan Bosworth, Vikki Hon
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) over approved LLDPE geomembrane. Note: no soil subgrade approved and no LLDPE geomembrane installed on 8/2/16. Next area of subgrade still being prepared, graded, and compacted by Entact (to be surveyed by Maser).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was first placed along the northern end of SA-6 North from Panel P66 / P67 (approximate Sta. 308+35) to the approximate center of the Utility Corridor (approximate Sta. 306+80) Note: The GDL panel orientation changed to east to west through the utility corridor so that the GDL followed the same contours as the utility corridor slopes. GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/2/16 Photo Log for supporting photographs.
- While GDL was being deployed ESI also conducted vacuum box testing and minor repair activities for Panels P86 and P87 (installed on 7/28/16). Additional details are provided in the 8/2/16 Repair Report.
- A total of three (3) destruct samples were collected. One fusion weld sample – DS-28 was collected from Panel Seam P81 / P83. Two extrusion weld destruct samples – DSX-11 and DSX-12 were collected from Repair R-365 (Panel 81) and Repair R-387 (Panel 86), respectively.
- ESI also completed repair activities for fusion weld destruct sample DS-26 (Panel P72 / P74 seam). DS-26 failed laboratory testing as two specimens were reported as EPA Break Code “AD-BRK” outlining a break in the weld and not the film tear break (FTB). Although the minimum peel requirements were met, since the break code was not an FTB, the test was reported as a failed test.
- To address the failed destruct sample, two field specimens (DS-26A & DS-26B) were cut approximately 10 ft. on each side of DS-26. Both samples were field tested and peel and shear strength requirements were met. Sample DS-26B which exhibited peel and shear breaks slightly less than DS-26A was sent for laboratory analysis.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Non-Conformance Items / Corrective Actions***

- None Encountered - Failed destruct sample DS-26 was previously outlined on the 7/28/16 Daily Report

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/2/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct results for DS-28, DSX-11, DSX-12, and DS-26B.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/27/16, and 7/28/16. ESI Daily Form Submittals still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-27. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-10. Laboratory results generally in compliance with project specifications with the exception of DS-26.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/2/16 |
| A3 – Photo Log | Pages 1-3 | Total of 6 photos outlining pertinent daily observations and descriptions for 8/2/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/2/16 |
| A5 – Subgrade Approval | | NA – no subgrade approved for LLDPE placement on 8/2/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI for prewelds completed on 8/2/16 |
| A7 – Panel Placement Log | | NA – no LLDPE panels placed on 8/2/16 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct samples collected on 8/2/16 |
| A9 – Seam/Non-Destruct. Test Log | | NA – no non-destructive testing conducted on 8/2/16 |
| A10 – Repair Log | Page 20 | Repair log provided by ESI for LLDPE repair activities completed on 8/2/16 |
| A11 – Conformance COC | | NA for 8/2/16 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct samples collected on 8/2/16 |
| A13 – Destruct. Sample Summary | Page 3 | Updated with destruct samples collected on 8/2/16 |
| A14 – Penetration & Edge Form | | NA – no penetration / pipe boots completed on 8/2/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 8/2/16 |
| A17 – Spark Test Log | | NA – no spark testing completed on 8/2/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/3/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 80/85° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #22**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth, Kale Novalis
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P87 / P88 installed on 7/28/16 (approximate Sta. 305+40). Material to be placed from Panel P87 / P88 running approximately 80 ft. east to approximate Sta. 304+60.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from the approximate center of the Utility Corridor (approximate Sta. 306+80), moving east through Panel P81 (approximate Sta. 306+20). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/3/16 Photo Log for supporting photographs.
- Following the deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 305+40 (Panel P87 / P88 installed on 7/28/16) to approximate Sta. 304+60. Refer to *Soil Subgrade Approval* forms from 8/3/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 3 to 5 of the daily photo log for 8/3/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 305+40 (east of Panel P87 / P88) moving east to approximate Sta. 304+60. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/3/16 Photo Log for supporting photographs.

- After placement of GVL, LLDPE geomembrane was installed continuing east from Panel P87 / P88 (installed on 7/28/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 305+40 (Panel P87 / P88) to approximate Sta. 304+60. A total of five panels were installed (P89, P90, P91, P92, and P93). Note: During placement of Panel P89 a piece of LLDPE was used to realign the panel placement arrangement. Panels P90, P91, P92, and P93 ran the entire width of SA-6 North (approximately 245 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 8/3/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 304+60, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 8/3/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P89 to P93 (installed on 8/3/16)
- ESI conducted repair activities for Panels 89 to P93 (installed on 8/13/16). A total of sixteen repairs (R-400 through R-415) were observed and fixed (according to the project specifications) from Panels P89 through P93. Refer to 8/3/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Additionally, ESI completed boot construction activities for Gas Vent GV-2 and Piezometer PZ4.
- No destruct samples were collected on 8/3/16. Samples to be cut for laboratory analysis on 8/4/16.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/3/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 and 8/2/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-28. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-12. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/3/16 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 8/3/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/3/16 |
| A5 – Subgrade Approval | Sheet 16 & ESI (8/3/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 6-7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/3/16 |
| A7 – Panel Placement Log | Page 13 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/3/16 |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 8/3/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 33-35 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 8/3/16 |
| A10 – Repair Log | Pages 20-21 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/3/16 |
| A11 – Conformance COC | | NA for 8/3/16 |
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 8/3/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 8/3/16 |
| A14 – Penetration & Edge Form | 8/3/16 Pipe Boot Forms | Pipe boot / penetration forms completed for Piezometer PZ4 and Gas Vent GV-2 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 8/3/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 8/3/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/4/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 72/85° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #23**
**AmecFW**: Stu Bills, Dave Ambrose, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and temporary liner, continuing east from Panel P93 installed on 8/3/16 (approximate Sta. 304+60). Material to be placed from Panel P93 running approximately 85 ft. east to approximate Sta. 303+75.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box and repair activities for LLDPE previously installed on 8/3/16. In addition, two destruct samples were collected for laboratory analysis. One fusion weld destruct sample – DS-29 was collected from Panel P90 / P91. One extrusion weld destruct sample was also collected – DSX-13 from Panel P90 Repair R-401.
- While repair / vacuum box activities were being conducted ESI deployed the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed moving east through Panel P81 (approximate Sta. 306+20) up to Panel P86 (approximate Sta. 305+80). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/4/16 Photo Log for supporting photographs.
- Following the deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 304+60 (Panel P93 installed on 8/3/16) to approximate Sta. 303+75. Refer to *Soil Subgrade Approval* forms from 8/4/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 3,4, and 5 of the daily photo log for 8/4/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 304+60 (east of Panel P93) moving east to approximate Sta. 303+75. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/4/16 Photo Log for supporting photographs.
- Additionally, GCL was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included a small area along the northern edge of SA-6 North east of Sta. 303+75. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/4/16 *Photograph Log*.
- Based on an LLDPE inventory completed by Entact, it was determined that approximately two additional rolls of 60-mil LLDPE would be required to complete the remaining area of SA-6 North. As such, three temporary panels were installed (to be replaced once new LLDPE rolls were received) from approximate Sta. 304+60 to approximate Sta. 303+75 (area of SA-6 North at upper elevation above the water table).
- After placement of GVL, three temporary panels were installed east of Panel P93 (installed on 8/3/16) and moving east. The three temporary panels were installed up to approximate Sta. 303+75 (did not cover the GCL or remaining area of subgrade to the east as permanent 60-mil panels will be installed continuing east from the temporary panel on 8/5/16.
- Note: since no permanent LLDPE was installed, and only temporary panels were placed, no repairs or non-destructive testing was conducted on the temporary panels.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/4/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct results for samples DS-29 and DSX-13.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, and 8/3/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-28. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-12. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/4/16 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/4/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/4/16 |
| A5 – Subgrade Approval | Sheet 17 & ESI (8/4/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | | NA – no trial welds completed on 8/4/16 |
| A7 – Panel Placement Log | | NA – no permanent LLDPE panels on 8/4/16 |
| A8 – Destruct Seam Testing COC | Sheet 3 | Updated for destruct samples collected on 8/4/16 |
| A9 – Seam/Non-Destruct. Test Log | | NA – no non-destructive testing conducted as no permanent LLDPE panels were installed |
| A10 – Repair Log | Page 21 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/4/16 |
| A11 – Conformance COC | | NA for 8/4/16 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct samples collected on 8/4/16 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct sample summary updated with samples collected on 8/4/16 |
| A14 – Penetration & Edge Form | | NA – No pipe boots / penetrations completed on 8/4/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 8/4/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 8/4/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/5/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 75/85° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1745 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #24**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from the third temporary panel installed on 8/4/16 (approximate Sta. 303+75). Material to be placed from Temp Panel 3 running approximately 60 ft. east to approximate Sta. 303+15.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed moving east through Panel P86 (approximate Sta. 305+80) up to Panel P93 (approximate Sta. 304+60). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/5/16 Photo Log for supporting photographs.
- While GDL was being deployed, a puncture / penetration through the liner was fixed at Panel P36. The penetration was due to work activities outside of SA-6 North, as a grounding rod was driven through the liner. This penetration was recorded as a non-conformance issue, and is identified as Repair R-418 on the *Repair Report.*
- Following the deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 303+75 (east of temporary panels installed on 8/4/16) to approximate Sta. 303+15. Refer to *Soil Subgrade Approval* forms from 8/5/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 5 to 8 of the daily photo log for 8/5/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 303+75 (east of temporary panels) moving east to approximate Sta. 303+15. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/5/16 Photo Log for supporting photographs. Note: GVL was placed along the southern end of SA-6 North at areas above the site water table (areas not covered by GCL).
- Additionally, GCL was placed along the northern end of SA-6 North at areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included an area along the northern edge of SA-6 North from Sta. 303+75 to Sta. 303+15. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/5/16 *Photograph Log*.
- After placement of GVL and GCL, LLDPE geomembrane was installed continuing east of the temporary panels (installed on 8/4/16). The LLDPE panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 303+75 (east of temporary panels) to approximate Sta. 303+15. A total of five panels were installed (P94, P95, P96, P97, and P98). Note: During placement of Panel P96 the LLDPE panel terminated along the southern end of SA-6 North, thus the remaining run of LLDPE was installed as Panel P97. Panels P94, P95, and P98 ran the entire width of SA-6 North (north to south) spanning approximately 235 ft.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 8/5/16 *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 303+15, ESI began to conduct non-destructive testing in accordance with the project specifications. Refer to the 8/5/16 *Seam Control Form* for non-destructive testing details.
- ESI conducted repair activities for Panels P94 to P98 (installed on 8/5/16). A total of thirteen repairs (R-418 through R-430) were observed and fixed (according to the project specifications) from Panels P94 through P98. Refer to 8/5/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- ESI also completed the pipe boot construction for Injection Well 088-IW-02.
- No destruct samples were collected on 8/5/16.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 10 (Sheet #10) – Penetration / puncture through LLDPE geomembrane
    - Penetration / puncture through LLDPE geomembrane from work activities outside of geosynthetic installation. Grounding rod driven through liner. Puncture exposed, and hole patched / repaired as per project specifications and outlined in the non-conformance log.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/5/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, and 8/4/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-29. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-13. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/5/16 |
| A3 – Photo Log | Pages 1 – 8 | Total of 15 photos outlining pertinent daily observations and descriptions for 8/5/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/5/16 |
| A5 – Subgrade Approval | Sheet 18 & ESI (8/5/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/5/16 |
| A7 – Panel Placement Log | Page 14 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/5/16 |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 8/5/16 |
| A9 – Seam/Non-Destruct. Test Log | Page 36 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 8/5/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Pages 21-22 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/5/16 |
| A11 – Conformance COC | | NA for 8/5/16 |
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 8/5/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 8/5/16 |
| A14 – Penetration & Edge Form | 8/15/16 Pipe Boot Form | Pipe boot / penetration form completed for Injection Well 088-IW-02 |
| A16 – Notice of Non-Compliance | 8/15/16 Sheet #10 | One non-compliance issue identified as “Damage by Others” on Panel P36 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 8/5/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/8/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 85/95° F, Sunny, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1215 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #25**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P98 installed on 8/5/16 (approximate Sta. 303+15). Material to be placed from Panel P98 running approximately 45 ft. east to approximate Sta. 302+70.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing vacuum box testing for repairs from Panels P94 to P98 (installed on 8/5/16). Additionally, two destruct samples were collected. One fusion weld destruct sample – DS-30 was collected from Panel P97 / P98, and one extrusion weld sample DSX-14 was collected from Panel P98 (Repair R-430).
- ESI deployed the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed moving east through Panel P93 and up to the temporary panels (installed on 8/4/16). Approximately 2 rolls of GDL were placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/8/16 Photo Log for supporting photographs.
- Following the deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 303+15 (east of Panel P98 installed on 8/5/16) to approximate Sta. 302+70. Refer to *Soil Subgrade Approval* forms from 8/8/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.
- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 303+15 (east of Panel P98) moving east to approximate Sta. 302+70. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/8/16 Photo Log for supporting photographs. Note: GVL was placed along the southern end of SA-6 North at areas above the site water table (areas not covered by GCL).

- Additionally, GCL was placed along the northern end of SA-6 North at areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included an area along the northern edge of SA-6 North from approximate Sta. 303+15 to Sta. 302+70. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/8/16 *Photograph Log*.
- After placement of GVL and GCL, LLDPE geomembrane was installed continuing east Panel P98 (installed on 8/5/16). The LLDPE panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 303+15 (east of Panel P98) to approximate Sta. 302+70. A total of two panels were installed (P99 and P100). Panels P99 and P100 ran the entire width of SA-6 North (north to south) spanning approximately 238 ft.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 8/8/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 302+70, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 8/8/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P99 and P100 (installed on 8/8/16) as outlined below.
- ESI conducted repair activities for Panels P99 and P100 (installed on 8/8/16). A total of seven repairs (R-431 through R-437) were observed and fixed (according to the project specifications) from Panels P99 to P100. Refer to 8/8/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/8/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample results for DS-30 and DSX-14.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, and 8/5/16. ESI Forms still to be reviewed.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-29. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-13. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/8/16 |
| A3 – Photo Log | Pages 1 – 3 | Total of 5 photos outlining pertinent daily observations and descriptions for 8/8/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/8/16 |
| A5 – Subgrade Approval | Sheet 19 & ESI (8/8/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/8/16 |
| A7 – Panel Placement Log | Page 14 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/8/16 |
| A8 – Destruct Seam Testing COC | Sheet 3 | Updated for destruct samples collected on 8/8/16 |
| A9 – Seam/Non-Destruct. Test Log | Page 37 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 8/8/16 |
| A10 – Repair Log | Page 22 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/8/16 |
| A11 – Conformance COC | | NA for 8/8/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct samples collected on 8/8/16 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct sample summary updated with samples collected on 8/8/16 |
| A14 – Penetration & Edge Form | | NA – no penetrations / pipe boots completed on 8/8/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues encountered on 8/8/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 8/8/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/9/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 85/90° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1800 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #26**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth, Kale Novalis
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## *Site Activities*

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P100 installed on 8/8/16 (approximate Sta. 302+70). Material to be placed from Panel P100 running approximately 100 ft. east to approximate Sta. 301+70.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane. GDL was placed from Panel P94 (approximate Sta. 303+75), moving east through Panel P97 (approximate Sta. 303+15). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/9/16 Photo Log for supporting photographs.
- While GDL was being deployed, ESI also collected two destruct samples for laboratory analysis. Two fusion weld destruct samples – DS-31 was collected from Panel P79 / P80 and DS-32 was collected from Panel P86 / P87. These additional samples were collected to supplement the destruct sample data previously collected beyond failed destruct sample DS-26. DS-31 and DS-32 were collected between the destruct samples collected at 1,500 LF to provide additional sample information.
- Following the deployment of GDL, Langan and Entact conducted soil subgrade approval from approximate Sta. 302+70 (Panel P100 installed on 8/8/16) to approximate Sta. 301+70. Refer to *Soil Subgrade Approval* forms from 8/9/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". Refer to Photos 9 to 12 of the daily photo log for 8/9/2016, for supporting subgrade photos. The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 302+70 (east of Panel P100) moving east to approximate Sta. 301+70. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/9/16 Photo Log for supporting photographs.
- Additionally, GCL was placed along the northern end of SA-6 North at areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs), which included an area along the northern edge of SA-6 North from approximate Sta. 302+70 to Sta. 301+70. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/9/16 *Photograph Log*.
- After placement of GVL and GCL, LLDPE geomembrane was installed continuing east from Panel P100 (installed on 8/8/16) and moving east. The panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 302+70 (Panel P100) to approximate Sta. 301+70. A total of six panels were installed (P101, P102, P103, P104, P105, and P106). Note: During placement of Panel P101 the roll of LLDPE terminated near the southern end of SA-6 North, thus the remaining run of LLDPE was installed as P102. Similarly, during placement of Panel P104, the roll of LLDPE terminated near the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P105. Panels P103 and P106 ran the entire width of SA-6 North (approximately 235 ft.) from north to south.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. At least six 1-inch specimens were collected for peel and shear testing (3 samples for each test) for each weld. The results of the pre-trial weld are provided in the 8/9/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 301+70, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 8/9/16 *Seam Control Form* for pressure testing details. Additionally, repair activities were conducted for Panels P100 to P106 (installed on 8/9/16)
- ESI conducted repair activities for Panels P100 to P106 (installed on 8/9/16). A total of eight repairs (R-438 through R-445) were observed and fixed (according to the project specifications) from Panels P100 through P106. Refer to 8/9/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds. Repair activities for Panels P100 to P106 to be completed on 8/10/16.
- ESI also conducted spark testing for seven pipe boots / penetrations total. Prior to spark testing, Entact conducted methane testing prior to spark testing and a concentration of 0.0% was measured at each location. Spark testing was completed for Extraction Pump Sta. 2, Gas Vent GV-2, Utility Corridor Drain Pipe, Injection Well 088-IW-02, and Injection Well 088-IW-03. The vertical weld and base of the boot was tested and no sparks were observed (thus the spark test passed). During spark testing of Piezometer PZ4 and Well 115-E5-SO,a spark was observed during testing as the spark was able to arc to the wire through a section of vertical weld. Area to be re-grinded, rewelded, and retested on 8/9/16.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 11 (Sheet #11) – Failed spark test along vertical weld of Piezometer PZ4
  - Failed spark test identified during spark testing of Piezometer PZ4. Spark able to arc to wire through section of vertical weld (thin weld). Weld to be grinded, re-welded, and re-tested on 8/9.
  -

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Non-Conformance Items / Corrective Actions (continued)***

- Non-Conformance No. 12 (Sheet #12) – Failed spark test along vertical weld of Well 115-E5-SO
  - Failed spark test identified during spark testing of Well 115-E5-SO. Spark able to arc to wire through section of vertical weld (thin weld). Weld to be grinded, re-welded, and re-tested on 8/9.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/9/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample results for DS-31 and DS-32.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, 8/5/16, and 8/8/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-30. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-14. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/9/16 |
| A3 – Photo Log | Pages 1 – 9 | Total of 17 photos outlining pertinent daily observations and descriptions for 8/9/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/9/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A5 – Subgrade Approval | Sheet 20 & ESI (8/9/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 7-8 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/9/16 |
| A7 – Panel Placement Log | Pages 14-15 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/9/16 |
| A8 – Destruct Seam Testing COC | Sheet 4 | Updated for destruct samples collected on 8/9/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 37-38 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 8/9/16 |
| A10 – Repair Log | Pages 22-23 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/9/16 |
| A11 – Conformance COC | | NA for 8/9/16 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct samples collected on 8/9/16 |
| A13 – Destruct. Sample Summary | Page 4 | Destruct sample summary updated with samples collected on 8/9/16 |
| A14 – Penetration & Edge Form | | NA – No pipe boots / penetrations completed on 8/9/16 |
| A16 – Notice of Non-Compliance | Sheet 11 & 12 (8/9/16) | Two non-compliance issues identified for failed spark tests on 8/9/16 |
| A17 – Spark Test Log | 8/9/16 Spark Test Logs | Seven spark test logs conducted for Extraction Pump Sta. 2 Manhole, Gas Vent GV-2, Piezometer PZ4, Utility Corridor Drain Pipe, Injection Well 088-IW-02, Injection Well 088-IW-03, and Well 115-E5-SO |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/10/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 82/88° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1315 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #27**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE) for area previously covered by temporary panels (area east of Panel P93). Temporary panels were removed, and new LLDPE was placed from Panel P93 (approximate Sta. 304+60) running approximately 85 ft. east to approximate Sta. 303+75 (subgrade previously approved on 8/4/16).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI continuing with repair activities for Panels P100 to P106 (installed on 8/9/16). The repairs were patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Additional details are outlined on the 8/10/16 *Repair Report.*
- ESI also collected two destruct samples from Panels P100 to P106 (installed on 8/9/16) for laboratory analysis. One fusion weld destruct samples – DS-33 was collected from Panel P104 / P106 and one extrusion weld destruct sample – DSX-15 was collected from Repair R-445 (Panel P104 / P106).
- While repair / vacuum box activities were being conducted ESI removed the temporary panels from approximate Sta. 304+60 to approximate Sta. 303+75 which were previously installed on 8/4/16. Note: soil subgrade approval for this area was also completed on 8/4/16 prior to the temporary panel placement. 16 oz. geotextile and GVL were also placed on 8/4/16 following subgrade approval.
- LLDPE geomembrane was installed continuing east from Panel P93 (installed on 8/4/16) up to Panel P94 (installed on 8/5/16). The new LLDPE panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 304+60 (east of Panel P93) to approximate Sta.303+75 (Panel P94) . A total of four panels were installed (P107, P108, P109, and P110). Note: During placement of Panel P109 the roll of LLDPE terminated near the northern end of SA-6 North, thus the remaining run of LLDPE was installed as P110. Panels P107 and P108 ran the entire width of SA-6 North (approximately 233 ft.) from north to south.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, smooth to texture) were conducted to confirm that the equipment met the required specifications. At least six 1-inch specimens were collected for peel and shear testing for each weld (3 samples for each test). The results of the pre-trial weld are provided in the 8/10/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 303+75, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 8/10/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P107 to P110 (installed on 8/10/16)
- ESI conducted repair activities for Panels P107 to P110 (installed on 8/10/16), along with the repair activities for Panels P100 to P106 (installed on 8/9/16). A total of twenty-two repairs (R-446 through R-467) were observed and fixed (according to the project specifications). Refer to 8/10/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- ESI also completed pipe boot / penetrations for Gas Vent GV-1 and Well 115-E4-SO. Additional details are provided in the 8/10/16 Pipe Boot Construction Logs.
- One fusion weld sample – DS-34 was also collected from Panels P107 to P110 (installed on 8/11/16) from Panel P94 / P110 seam for laboratory analysis.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 13 (Sheet #13) – Subgrade irregularity identified as R-457 on *Repair Log*
    - Stone identified underneath LLDPE geomembrane located on Panel P107 / P108. Stone was subsequently removed, and hole was patched / repaired following project specs as further described in *Sheet 13 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/10/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample results for DS-33, DS-34, and DSX-15.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, 8/5/16, 8/8/16, and 8/9/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-32. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-14. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/10/16 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/10/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/10/16 |
| A5 – Subgrade Approval | | NA – no subgrade approval for 8/10/16. Subgrade previously approved on 8/4/16 prior to temp panel placement |
| A6 – Trial Weld Log | Page 8 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/10/16 |
| A7 – Panel Placement Log | Pages 15-16 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/10/16 |
| A8 – Destruct Seam Testing COC | Sheet 4 | Updated for destruct samples collected on 8/10/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 39-40 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 8/10/16 |
| A10 – Repair Log | Pages 23-24 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/10/16 |
| A11 – Conformance COC | | NA for 8/10/16 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct samples collected on 8/10/16 |
| A13 – Destruct. Sample Summary | Page 4 | Destruct sample summary updated with samples collected on 8/10/16 |
| A14 – Penetration & Edge Form | 8/10/16 Pipe Boot Forms | Pipe boots for Gas Vent GV-1 and Well 115-E4-SO completed on 8/10/16 |
| A16 – Notice of Non-Compliance | Sheet 13 | Subgrade irregularity identified as non-compliance issue on 8/10/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 8/10/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 8/11/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 85/90° F, Overcast, Humid, Iso. Storms |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1715 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #28**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P106 installed on 8/9/16 (approximate Sta. 301+70). Material to be placed from Panel P106 running approximately 45 ft. east to approximate Sta. 301+25.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing and "Add On" repair activities for Panels P94 to P104. ESI completed Add On repairs along the southern end of SA-6 North. Additional LLDPE was installed so that the cap extended a minimum of 1 ft. beyond the edges of the SCB wall. These repairs were recorded and documented on the 8/11/16 *Repair Report.*
- Following repair activities, ESI placed geocomposite drainage layer (GDL) continuing east of Panel P93. GDL was placed over Panels P107 to P110 (installed on 8/10/16) from approximate Sta. 304+60 to approximate Sta. 303+75. GDL was placed according to the project specs with white plastic fasteners spaced at a maximum of 5 ft. with the top layer of geotextile sewn.
- Prior to soil subgrade approval, the edge of Panel P106 (installed on 8/9/16) was pulled back to expose the underlying GCL layer. A small portion of the GCL had become saturated due to overnight storms. The saturated GCL was cut and exposed to dry the GCL and soil subgrade. A new piece of GCL was then installed over the saturated GCL, secured with bentonite, and leistered in place. See Photos 6 & 7 in 8/11/6 *Photograph Log.*
- Following the GCL activities, Langan and Entact conducted soil subgrade approval from approximate Sta. 301+70 (east of Panel P106 installed on 8/9/16) to approximate Sta. 301+25. Refer to *Soil Subgrade Approval* forms from 8/11/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 301+75 (east of Panel P106) moving east to approximate Sta. 301+25. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/11/16 Photo Log for supporting photographs. Note: GVL was placed along the southern end of SA-6 North at areas above the site water table (areas not covered by GCL).
- Additionally, GCL was placed along the northern end of SA-6 North at areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included an area along the northern edge of SA-6 North from approximate Sta. 301+75 to Sta. 301+25. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/11/16 *Photograph Log*.
- After placement of GVL and GCL, LLDPE geomembrane was installed continuing east Panel P106 (installed on 8/9/16). The LLDPE panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 301+75 (east of Panel P106) to approximate Sta. 301+25. A total of two panels were installed (P111 and P112). Panels P111 and P112 ran the entire width of SA-6 North (north to south) spanning approximately 237 ft.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. At least six 1-inch specimens were collected to conduct peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 8/11/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 301+25, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 8/11/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P111 and P112 (installed on 8/11/16)
- ESI completed repair activities for Panels P94 to P104 (Add On repairs along southern end of the cap) and Panels P111 & P112 (installed on 8/11/16). A total of twenty-one repairs (R-468 through R-485 and R-495 to R-497) were observed and fixed (according to the project specifications). Refer to the 8/11/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- No destruct samples collected on 8/11/16.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/11/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, 8/5/16, 8/8/16, 8/9/16, and 8/10/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-34. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-15. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/11/16 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 8/11/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/11/16 |
| A5 – Subgrade Approval | Sheet 21 & ESI (8/11/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 8 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/11/16 |
| A7 – Panel Placement Log | Page 16 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/11/16 |
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 8/11/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 40-42 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 8/11/16 |
| A10 – Repair Log | Pages 24-25 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/11/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A11 – Conformance COC | | NA for 8/11/16 |
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 8/11/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 8/11/16 |
| A14 – Penetration & Edge Form | | NA – No pipe boots / penetrations completed on 8/11/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 8/11/16 |
| A17 – Spark Test Log | | NA – no spark testing conducted on 8/11/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/12/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 85/98° F, Sunny, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1730 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #29**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P112 installed on 8/11/16 (approximate Sta. 301+25). Material to be placed from Panel P112 running approximately 45 ft. east to approximate Sta. 300+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying orange geocomposite drainage layer (GDL) continuing east from Panel P98. GDL was placed over Panels P99 to P106 (installed on 8/8/16 and 8/9/16) from approximate Sta. 303+15 (Panel P99) to approximate Sta. 301+70 (Panel P106). GDL was placed according to the project specs with white plastic fasteners spaced at a maximum of 5 ft. with the top layer of geotextile sewn.
- While GDL was being deployed ESI also conducted vacuum box testing and minor repairs for Panels P111 and P112 (installed on 8/11/16). Additional details are provided in the 8/12/16 *Repair Report.*
- ESI also completed spark testing for Gas Vent GV-1 and Well 115-E4-SO. Prior to spark testing, methane testing was completed by AmecFW and a concentration of 0.0% was measured for both boots. Spark testing was then completed for Gas Vent GV-1 along the base of the boot and vertical weld and no sparks were observed (spark test passed). During spark testing of Well 115-E4-SO a spark was observed along the edge of the vertical weld as the extrusion weld was not centered over the copper wire. This area was marked by ESI, grinded, re-welded, and retested. No sparks were observed during the spark retest thus the retest passed.
- Prior to soil subgrade approval, the edge of Panel P112 (installed on 8/11/16) was pulled back to expose the underlying GCL layer. A small portion of the GCL had become saturated due to overnight storms. The saturated GCL was cut and exposed to dry the GCL and soil subgrade. A new piece of GCL was then installed over the saturated GCL, secured with bentonite, and leistered in place.
- Following the GCL activities, Langan and Entact conducted soil subgrade approval from approximate Sta. 301+25 (east of Panel P112 installed on 8/11/16) to approximate Sta. 300+80. Refer to *Soil Subgrade Approval* forms from 8/12/16 for additional details.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any loose material greater than ½". The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 301+25 (east of Panel P112) moving east to approximate Sta. 300+80. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/12/16 Photo Log for supporting photographs. Note: GVL was placed along the southern end of SA-6 North at areas above the site water table (areas not covered by GCL).
- Additionally, GCL was placed along the northern end of SA-6 North at areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included an area along the northern edge of SA-6 North from approximate Sta. 301+25 to approximate Sta. 300+80. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/12/16 *Photograph Log*.
- After placement of GVL and GCL, LLDPE geomembrane was installed continuing east of Panel P112 (installed on 8/12/16). The LLDPE panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 301+25 (east of Panel P112) to approximate Sta. 300+80. A total of two panels were installed (P113 and P114). Panels P113 and P114 ran the entire width of SA-6 North (north to south) spanning approximately 233 ft.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. At least six 1-inch specimens were collected for peel and shear testing (3 samples for each weld). The results of the pre-trial weld are provided in the 8/12/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 300+80, ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 8/12/16 *Seam Control Form* for non-destructive testing details. Additionally, repair activities were conducted for Panels P113 and P114 (installed on 8/12/16)
- ESI completed repair activities for Panels P113 to P114 (installed on 8/12/16). A total of seven repairs (R-486 through R-489 and R-492, R-493, and R-494) were observed and fixed (according to the project specifications). Refer to the 8/12/16 *Repair Report* for additional details. Repairs were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- ESI also completed pipe boot / penetrations for Access Manhole Sta. 18+00 and Injection Well 088-IW-01. Additional details are provided in the 8/12/16 Pipe Boot Construction Logs.
- No destruct samples collected on 8/12/16.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 14 (Sheet #14) – Failed spark test along vertical weld of Well 115-E4-SO
  - Failed spark test identified during spark testing of Well 115-E4-SO. Spark observed along edge of extrusion weld (weld not centered over wire). Area was grinded, rewelded, and retested and no sparks were observed during spark retest (spark retest passed).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/12/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, 8/5/16, 8/8/16, 8/9/16, 8/10/16, and 8/11/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-34. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-15. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/12/16 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 8/12/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/12/16 |
| A5 – Subgrade Approval | Sheet 22 & ESI (8/12/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 8-9 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/12/16 |
| A7 – Panel Placement Log | Page 16 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/12/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A8 – Destruct Seam Testing COC | | NA – no destruct samples collected on 8/12/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 42-43 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 8/12/16 |
| A10 – Repair Log | Page 25 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/12/16 |
| A11 – Conformance COC | | NA for 8/12/16 |
| A12 – Destructive Seam Field Test | | NA – no destruct samples collected on 8/12/16 |
| A13 – Destruct. Sample Summary | | NA – no destruct samples collected on 8/12/16 |
| A14 – Penetration & Edge Form | 8/12/16 Pipe Boot Forms | Pipe boots / penetrations completed for Access Manhole Sta. 18+00 and Injection Well 088-IW-01 |
| A16 – Notice of Non-Compliance | Sheet 14 | One failed spark test for Well 115-E4-SO identified on 8/12/16 |
| A17 – Spark Test Log | 8/12/16 Spark Test Logs | Spark testing for Gas Vent GV-1 and Well 115-E4-SO completed on 8/12/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/13/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 85/98° F, Sunny, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | | **TIME:** | 0645 – 1800 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #30**
**AmecFW**: Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of 16 oz. geotextile, geocomposite venting layer (GVL), and 60-mil geomembrane liner (LLDPE), continuing east from Panel P114 installed on 8/12/16 (approximate Sta. 300+80). Material to be placed from Panel P114 running approximately 80 ft. east to approximate Sta. 300+00 (east end of SA-6 North).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing and minor repair activities for Panels P113 / P114 (installed on 8/12/16). Repairs were patched, extrusion welded, and vacuum box tested as per project specifications. Additional details are outlined on the 8/13/16 *Repair Report*. Additionally, two destruct samples were collected. One fusion weld destruct sample DS-35 was collected from Panel P112 / P113, and one extrusion weld destruct sample – DSX-16 was collected from Panel P112 (Repair R-478)
- While repair activities were being completed ESI deployed orange geocomposite drainage layer (GDL) continuing east from Panel P106. GDL was placed over Panels P106 (approximate Sta. 301+70) to approximate Sta. 300+80 (Panel P114). GDL was placed according to the project specs with white plastic fasteners spaced at a maximum of 5 ft. with the top layer of geotextile sewn. Note: repairs were completed for Panels P113 / P114 in the early morning and were surveyed and verified before GDL was deployed over the panels later in the morning.
- ESI also completed spark testing for Access Manhole Sta. 18+00 and Injection Well 088-IW-01. Prior to spark testing, methane testing was completed by AmecFW and a concentration of 0.0% was measured for both boots. Spark testing was then completed along the base of the boot and vertical weld for both locations. No sparks were observed during either test (spark tests passed).
- Following the GDL activities, Langan and Entact conducted soil subgrade approval from approximate Sta. 300+80 (east of Panel P114 installed on 8/12/16) to approximate Sta. 300+00 (east end of cap). Refer to *Soil Subgrade Approval* forms from 8/13/16 for additional details. During subgrade observation, the subgrade area was transected in approximate 200 ft. by 8 ft. sections and based on visual observation, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was generally free of any

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

loose material greater than ½". The area was also previously surveyed and subsequently approved by AmecFW prior to LLDPE placement.

- Following subgrade approval, GVL and LLDPE placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 North Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 1 ft. outside of the cap (remaining roll width inside), as outlined in the project specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 300+80 (east of Panel P114) moving east to approximate Sta. 300+00 (east end of cap). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top layer of geotextile was sewn along the seams (according to the project specifications). Refer to 8/13/16 Photo Log for supporting photographs. Note: GVL was placed along the southern end of SA-6 North at areas above the site water table (areas not covered by GCL).
- Additionally, GCL was placed along the northern and eastern end of SA-6 North at areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included an area along the northern edge of SA-6 North from approximate Sta. 300+80 to approximate Sta. 300+00 (east end of cap). GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges. Supporting photos are provided in the 8/13/16 *Photograph Log*.
- After placement of GVL and GCL, LLDPE geomembrane was installed continuing east of Panel P114 (installed on 8/12/16). The LLDPE panels were generally oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 300+80 (east of Panel P114) to approximate Sta. 300+00. A total of five panels were installed (P115, P116, P117, P118, and P119). Panels P116, P117, P118, and P119 were oriented northwest/southeast and were placed to fill in the triangle area along the southeast portion of the cap. Panel P115 ran the entire width of SA-6 North (north to south) spanning approximately 235 ft.
- Adjacent LLDPE geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture) were conducted to confirm that the equipment met the required specifications. At least six 1-inch specimens were collected for several welds for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the 8/13/16 *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 300+00 (east end of cap), ESI conducted non-destructive testing in accordance with the project specifications. Refer to the 8/13/16 *Seam Control Form* for non-destructive testing details.
- Temporary patches were leistered in place for Panels P115 to P119, but no repair activities (extrusion welding) were completed on 8/13/16 (to be finished Monday – 8/15/16). ESI completed repair activities for Panels P113 to P114 (installed on 8/12/16). A total of seven repairs (R-490, R-491, R-498 to R-502) were observed and fixed (according to the project specifications). Refer to the 8/13/16 *Repair Report* for additional details. Repairs were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample results for DSX-16 and DS-35.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, 8/5/16, 8/8/16, 8/9/16, 8/10/16, 8/11/16, and 8/12/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-34. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-15. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/13/16 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 8/13/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/13/16 |
| A5 – Subgrade Approval | Sheet 23 & ESI (8/13/16) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 9 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/13/16 |
| A7 – Panel Placement Log | Pages 16-17 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 8/13/16 |
| A8 – Destruct Seam Testing COC | Page 4 | Updated with destruct samples collected on 8/13/16 |
| A9 – Seam/Non-Destruct. Test Log | Pages 43-44 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 8/13/16 |
| A10 – Repair Log | Pages 25-26 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/13/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A11 – Conformance COC | | NA for 8/13/16 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct samples collected on 8/13/16 |
| A13 – Destruct. Sample Summary | Page 4 | Destruct sample summary updated with samples collected on 8/13/16 |
| A14 – Penetration & Edge Form | | NA – no boots / penetrations completed on 8/13/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 8/13/16 |
| A17 – Spark Test Log | 8/13/16 Spark Test Forms | Spark testing completed for Access Manhole Sta. 18+00 and Injection Well 088-IW-01 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/15/2016 |
| **PROJECT:** | SA-6 North Capping | | **WEATHER:** | 82/92° F, Sunny, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & LLDPE Placement | **TIME:** | 0645 – 1500 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #31**
**AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) over approved LLDPE geomembrane (Panel P115 to P119). Note: LLDPE geomembrane installation complete up to east end of cap (Panels P115 to P119).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing repair activities and vacuum box testing for Panels P115 to P119 (installed on 8/13/16). A total of twelve repairs were (R-503 to R-514) observed and fixed according to the project specifications. Refer to the 8/15/16 *Repair Report* for additional details. In general, the majority of the repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 North grade (custom fit repairs), as well as seam joint patches. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- A total of two destruct samples were collected. One destruct sample DS-36 was collected from Panel P117 / P118 seam and one extrusion weld destruct sample – DSX-17 was collected from Panel P118 (Repair R-505) for laboratory analysis.
- ESI also completed the boot construction for Piezometer PZ2. Following the boot completion, methane / spark testing for Piezometer PZ2 was completed. Methane testing was conducted prior to spark testing and a concentration of 0.0% was measured. Spark testing was then conducted along the base of the boot and vertical weld and no sparks were observed (spark test passed). Additional details are provided in the Piezometer PZ2 boot construction log and the 8/15 *Spark Test Log.*
- After repair activities were completed, the as-built information including repair locations, distances, etc. was verified and ESI deployed the orange geocomposite drainage layer (GDL), over the previously installed LLDPE geomembrane (Panels P115 to P119). GDL was placed from approximate Sta. 300+80 to the east end of SA-6 North (approximate Sta. 300+00). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 8/15/16 Photo Log for supporting photographs.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/15/16). Review and confirm supporting QA paperwork (soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory destruct sample results for DSX-17 and DS-36.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 6/22/16, 6/23/16, 6/24/16, 6/27/16, 6/29/16, 6/30/16, 7/1/16, 7/6/16, 7/7/16, 7/8/16, 7/11/16, 7/12/16, 7/13/16, 7/14/16, 7/15/16, 7/18/16, 7/25/16, 7/28/16 8/2/16, 8/3/16, 8/4/16, 8/5/16, 8/8/16, 8/9/16, 8/10/16, 8/11/16, 8/12/16, and 8/13/16. ESI Forms still to be reviewed.
- Reviewed laboratory data for fusion weld destruct samples DS-1 through DS-35. Reviewed laboratory data for extrusion weld destruct sample DSX-1 through DSX-16. Laboratory results generally in compliance with project specifications with the exception of DS-26. Destruct sample DS-26B passed for peel and shear.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 North continuing east. Continue with subgrade observation to confirm if subgrade is graded, compacted, and free of debris, as well as surveyed (to be completed by AmecFW / Maser) to specifications.
- Continue with GVL and LLDPE geomembrane placement moving east along SA-6 North.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | NA – no new material delivered on 8/15/16 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/15/16 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/15/16 |
| A5 – Subgrade Approval | | NA – no subgrade approval completed on 8/15/16 |
| A6 – Trial Weld Log | Page 9 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/13/16 |
| A7 – Panel Placement Log | | NA – no new LLDPE geomembrane panels placed on 8/15/16 |
| A8 – Destruct Seam Testing COC | Page 4 | Updated with destruct samples collected on 8/15/16 |
| A9 – Seam/Non-Destruct. Test Log | | NA – no pressure testing completed on 8/15/16 |
| A10 – Repair Log | Page 26 | One repair log provided by ESI and confirmed by Langan for repairs completed for 8/15/16 |
| A11 – Conformance COC | | NA for 8/15/16 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct samples collected on 8/15/16 |
| A13 – Destruct. Sample Summary | Page 4 | Destruct sample summary updated with samples collected on 8/15/16 |
| A14 – Penetration & Edge Form | 8/15/16 Boot Form | LLDPE geomembrane boot for Piezometer PZ2 completed on 8/15/16 |
| A16 – Notice of Non-Compliance | | NA – no non-compliance issues observed on 8/15/16 |
| A17 – Spark Test Log | 8/15/16 Spark Test Logs | Spark testing for Piezometer PZ2 completed on 8/15/16 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/17/2016 |
| **PROJECT:** | SA-6 North Capping | | | **WEATHER:** | 82/92° F, Sunny, Humid |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Final Site Walk / Observation | | **TIME:** | 0745 – 1015 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #32** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose, Philemon Onyango, Josh Boynton<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan (Dan Bosworth and Jeff Stoicescu) onsite for final site walk of SA-6 North to observe completed geosynthetic components of SA-6 North capping activities.
- Langan conducted a site walk of the completed SA-6 North cap spanning from the west end (approximate. Sta. 319+00) to the east end (approximate Sta. 300+00). During the site walk, the following conditions were observed (in relation to the geosynthetic components of the cap installation):
  - Condition 1: The final GDL geotextile wrap around Gas Vent GV-2 was cut and gas vent was exposed.
  - Action Item: Based on discussions with Entact, the GDL was cut so that the construction of the gas vent could be completed. Entact plans to conduct leistering activities to reseal the geotextile wrap and secure the GDL.
  - Condition 2: Wrinkles were observed along the east end of the cap (approximate Sta. 300+00) due to the spreading of cover soils over the GDL.
  - Action Item: Entact to attempt to work out wrinkles to the east end of the cap. If wrinkles cannot be removed, ESI will return to the site to cut the geomembrane and complete patch / repair activities.
  - Condition 3: LLDPE was pulled taught along the slopes / contour changes along SA-6 North for areas where cover soil was being placed. During placement of cover soil, sand bags were removed from the cap so that the cover soil could be placed over the GDL. However, for areas where cover soil was not completed by the end of the day, the sand bags were not returned and the geosynthetic material was left un-weighted, thus causing the LLDPE to trampoline.
  - Action Item: Entact to ensure that areas not covered with cover soil at the end of the day will be secured with sand bags.
- Above items shall be reviewed on Friday (8/19).
- Additional details are outlined in the 8/17/16 *Photograph Log.*

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

**Spark Test Logs**
*(Attachment 11:  Capping Update)*

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North

**Location:** Extraction Pump Station #2 located near approx center of SA-6 North Cap on Panel P80 (approx 140 ft. N of southern end of cap and 5 ft. W of Panel P79/P80 seam). Identified as R-357 on *As Built* and *Repair Report*.

**Date:** 8/9/16 **Repair Number:** R-357

**Boot Log QA Form (cross-reference):** 7/27/16 Extraction Pump Station #2 Form

### QA – Spark Test Log – Manhole




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0910

*% Methane* 0.0%

☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Panel Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| Item Tested | Thickness | Operator Initials | Voltage (kV) | AC / DC | Brush Probe | Point Probe | QCR I.D.* | Pass / Fail | Retest Pass /Fail | QCR I.D.* |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication completed on 7/27/16. Spark / methane testing conducted on 8/9/16. Concentration of 0.0% methane measured prior to spark testing. As such, spark testing was conducted along the base of the boot and the vertical weld and no sparks were observed (spark test passed).

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** LANGAN

Honeywell

# STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Gas Vent GV-2 located at the approximate center of SA-6 North Cap on Panel P91 (approximately 107 ft. north of southern end of cap and 5 ft. east from Panel P90/P91 seam). Identified as R-409 on *As Built* and *Repair Report*.

**Date:** 8/9/16 **Repair Number:** R-409

**Boot Log QA Form (cross-reference):** 8/3/16 Gas Vent GV-2 Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0900

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/3/16. Methane / spark testing completed on 8/9/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:**

Honeywell

STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Injection Well 088-IW-02 located at the approx. center of SA-6 North Cap on Panel P97 (approximately 109 ft. north of southern end of cap and 2 ft. west from Panel P97/P98 seam). Identified as R-430 on *As Built* and *Repair Report*.

**Date:** 8/9/16 **Repair Number:** R-430

**Boot Log QA Form (cross-reference):** 8/5/16 Injection Well 088-IW-02 Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0840

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**: ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/5/16. Methane completed on 8/9/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** LANGAN

Honeywell

# STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Injection Well 088-IW-03 located near southern end of SA-6 North Cap on Panel P81 (approximately 32 ft. north of southern end of cap and 7 ft. west from Panel P81/P83 seam). Identified as R-384 on *As Built* and *Repair Report*.

**Date:** 8/9/16 **Repair Number:** R-384

**Boot Log QA Form (cross-reference):** 7/28/16 Injection Well 088-IW-03 Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 1220

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 7/28/16. Methane / spark testing completed on 8/9/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** -LANGAN

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Monitoring well 115-E5-SO located along southern end of SA-6 North Cap on Panel P78 (approximately 15 ft. north of southern end of cap and 9 ft. west from Panel P78/P79 seam). Identified as R-343 on *As Built* and *Repair Report*.

**Date:** 8/9/16 **Repair Number:** R-343

**Boot Log QA Form (cross-reference):** 7/27/16 Well 115-E5-SO Form

### QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0930

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Fail | Pass | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 7/27/16. Methane completed on 8/9/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. A spark was observed along the vertical weld as the weld over the wire was too thin thus causing the spark to arc. The area was grinded, rewelded, and retested on 8/9/16 and the spark retest passed as no sparks were observed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** - LANGAN

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Utility corridor horizontal drain pipe located along southern end of SA-6 North Cap on Panel P76 (approx. 6 ft. north of southern end of cap and 4 ft. west from Panel P76/P78 seam). Identified as R-380 on *As Built* and *Repair Report.*

**Date:** 8/9/16 **Repair Number:** R-380

**Boot Log QA Form (cross-reference):** 7/28/16 Utility Corridor Drain Pipe Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0935

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

Spark Test Information

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 7/28/16. Methane completed on 8/9/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** LANGAN

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Piezometer PZ4 located along northern end of SA-6 North Cap on Panel P90 (approximately 238 ft. north of southern end of cap and 7 ft. west from Panel P90/P91 seam). Identified as R-408 on *As Built* and *Repair Report*.

**Date:** 8/9/16 **Repair Number:** R-408

**Boot Log QA Form (cross-reference):** 8/3/16 Piezometer PZ4 Form

### QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0855

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**: ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Fail | Pass | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Fail | Pass | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/3/16. Methane / spark testing completed on 8/9/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld and a spark was observed as the weld over the wire was too thin thus causing the spark to arc. The area was grinded, re-welded and retested on 8/9/16 and the subsequent spark re-test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** – LANGAN

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Gas Vent GV-1 located at the approximate center of SA-6 North Cap on Panel P103 (approximately 113 ft. north of southern end of cap and 13 ft. east from Panel P102/P103 seam). Identified as R-449 on *As Built* and *Repair Report*.

**Date:** 8/12/16 **Repair Number:** R-449

**Boot Log QA Form (cross-reference):** 8/10/16 Gas Vent GV-1 Form

### QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0800

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| Item Tested | Thickness | Operator Initials | Voltage (Volts) | AC / DC | Brush Probe | Point Probe | QCR I.D* | Pass / Fail | Retest Pass /Fail | QCR I.D* |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/10/16. Methane / spark testing completed on 8/12/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** -LANGAN

Honeywell

# STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Monitoring Well 115-E4-SO located along the southern end of SA-6 North on Panel P104 (approx. 6 ft. north of southern end of cap and 5 ft. east from Panel P103/P104 seam). Identified as R-450 on *As Built* and *Repair Report*.

**Date:** 8/12/16 **Repair Number:** R-450

**Boot Log QA Form (cross-reference):** 8/10/16 Monitoring Well 115-E4-SO Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0810

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Fail | Pass | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/10/16. Methane / spark testing completed on 8/12/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing of the base of the boot, thus the spark test passed. During spark testing of the vertical weld a spark was observed along the edge of the weld (weld not centered over wire) thus the test failed. The area was grinded, rewelded, and retested on 8/12/16 and no sparks were observed (spark retest passed).

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** -LANGAN

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North

**Location:** Access Manhole Sta. 18+00 located near approximate center of SA-6 North Cap on Panel P113 (approximately 110 ft. north of southern end of cap and 10 ft. east of Panel P112/P113 seam). Identified as R-492 on *As Built* and *Repair Report*.

**Date:** 8/13/16 **Repair Number:** R-492

**Boot Log QA Form (cross-reference):** 8/12/16 Access Manhole Sta. 18+00 Form

### QA – Spark Test Log – Manhole




LINER ANCHOR TO CONCRETE STRUCTURE
NTS

CE TYP C-304

**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0910

*% Methane* 0.0%

☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Panel Extrusion Weld:** ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (kV)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication completed on 8/12/16. Spark / methane testing conducted on 8/13/16. Concentration of 0.0% methane measured prior to spark testing. As such, spark testing was conducted along the base of the boot and the vertical weld and no sparks were observed (spark test passed). Additionally, vacuum box testing was conducted along vertical and horizontal extrusion welds completed for the boot construction.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** -LANGAN

Honeywell

# STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Injection Well 088-IW-01 located along N end of SA-6 North Cap on Panel P113 / P114 seam (approx 206 ft. north of southern end of cap and 13 ft. east from Panel P113/P114 seam). Identified as R-493 on *As Built* and *Repair Report*.

**Date:** 8/13/16 **Repair Number:** R-493

**Boot Log QA Form (cross-reference):** 8/12/16 Injection Well 088-IW-01 Form

## QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0800

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**: ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/12/16. Methane / spark testing completed on 8/13/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** LANGAN

Honeywell

## STUDY AREA 6 - CAP INSTALLATION

LANGAN


**Project:** Study Area 6 North


**Location:** Piezometer PZ2 located along northern end of SA-6 North Cap on Panel P116 seam (approximately 188 ft. north of southern end of cap and 13 ft. east from Panel P116/P118 seam). Identified as R-509 on *As Built* and *Repair Report*.

**Date:** 8/15/16 **Repair Number:** R-509

**Boot Log QA Form (cross-reference):** 8/15/16 Piezometer PZ2 Form

### QA – SPARK TEST LOG (circle type of boot)




**Methane Testing:** *Instrument:* Landtec GEM 5000 *Time:* 0800

*% Methane* 0.0% ☒Methane < 1%; Proceed with spark testing ☐Methane > 1%; Visual observation of welds

**Skirt to Boot Extrusion Weld**: ☐Vacuum Box Tested ☒Spark Tested (as outlined below)

**Spark Test Information**

| *Item Tested* | *Thickness* | *Operator Initials* | *Voltage (Volts)* | *AC / DC* | *Brush Probe* | *Point Probe* | *QCR I.D** | *Pass / Fail* | *Retest Pass /Fail* | *QCR I.D** |
|---|---|---|---|---|---|---|---|---|---|---|
| Base of boot | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |
| Vertical weld | ~20 Gauge Copper | TU | 20,000 – 45,000 | AC | | Model BD-10A | CP | Pass | | CP |

*QCR represents the designated Quality Control representative determined by the Geosynthetic Installer

**Comments:** Boot fabrication and construction completed on 8/15/16. Methane / spark testing completed on 8/15/16 by ESI. Methane testing yielded concentration of 0.0%. As such, spark testing was conducted at the base of boot and along the vertical weld. No sparks were observed during testing, thus the spark test passed.

**AmecFW QA Signature:**

**Independent CQA Monitor Signature:** LANGAN

## Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 5, 2016

Type of Inspection: ☑ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☑ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 4 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/05/16

SWPPP Observer: _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, August 05, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence by the Kellogg Street jughandle has become detached |
| 2 | IA2Q4A1AL8 | Filter fabric in the catch basins to the north of the old JCIA trashpit has become blinded with accumulated sediment. |
| 3 | IA2Q4A1AL8 | Silt fence along the western end of the northern SA-7 raceway is damaged or missing in several locations. |
| 4 | IA2Q4A1AL8 | Sediment has accumulated to several inches deep on the SA-7 western raceway. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: George Pfeiff Date: 08/05/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen material as required. | 8/11/16 RAD |
| 2 | Replace the filter fabric in the three catch basins as required. | |
| 3 | Repair or replace the silt fence in this area as needed to comply with the SWPPP | |
| 4 | Remove the accumulated sediment from the western SA-7 roadway. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: Date: 08/11/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 12, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/12/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, August 12, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has accumulated along the SA-7 paved perimeter road on the south side. |
| 2 | IA2Q4A1AL8 | Trash and debris has accumulated along the North side of SA-7 |
| 3 | IA2Q4A1AL8 | Several panels of windscreen are in need of attention along the south side of SA-6 South. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 08/12/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Remove accumulated sediment from roadway. | 8/15/16 (2nd) |
| 2 | Remove accumulated debris/trash | |
| 3 | Repaid windscreen as needed along SA-6 South perimeter fencing. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 08/16/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 19, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | X | | | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/22/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, August 19, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen has become detached from the perimeter fence next to the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Garbage and other debris has accumulated on the grass at the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | The filter fabric in the stormwater catch basin immediately south of the Groundwater Treatment Plant on SA-6 North is blinded with sediment and driveway stone. |
| 4 | IA2Q4A1AL8 | There are discarded scraps of liner and other associated materials on the eastern end of the SA-6 North cap area. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 08/22/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen fabric to the perimeter chain-link fence as required. | 8/24/16 RAD |
| 2 | Pick up and dispose of garbage and other accumulated debris. | |
| 3 | Replace the filter fabric in the catch basin as required. | |
| 4 | Pick up and dispose of all liner installation-related debris from around and in the northern cap area. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 08/25/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: August 26, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 08/29/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, August 26, 2016**

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Sediment has accumulated on the western end of Kellogg street, particularly at the very end. |
| 2 | IA2Q4A1AL8 | Windscreen material is missing from the perimeter fence at the southern JCMUA driveway. |
| 3 | IA2Q4A1AL8 | Grass in the fenced-in area in front of the JCMUA building (by Rt. 440) has grown tall and need to be cut. |
| 4 | IA2Q4A1AL8 | The silt fence is down on the western and southern sides of the Novartis stockpile area on SA-7. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 08/29/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Clean up accumulated sediment from the public roadway. | 9/1/16 (CAD) |
| 2 | Replace windscreen material on the fence panels as required. | |
| 3 | Mow the grass in the area between the MUA wrought-iron fence and the temporary work zone fence along Rt. 440. | |
| 4 | Repair or replace the silt fence as required. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 09/01/16

## Attachment 13: GWTP Update (525/575 Route 440 GWTP PVSC Discharge Monitoring Report (submitted June 2016)

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

August 11, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the July 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 7 | 01 | 16 | 7 | 31 | 16 |
| \ | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,410 | 84,811 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.58 | 0.64 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | 0.00024 | 0.00024 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1737 | 0.1737 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

DocuSigned by:
John J. Morris
E0[illegible]

Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director
Type Name and Title

08/10/2016
Date

PVSC FORM MR-1 REV: 5 3/91 P2

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North
**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)
**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305
**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 7 | 01 | 16 | 7 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,399,724 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 68,652,644 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 7/7/2016 | 42.7 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| DocuSigned by: John J. Morris E013C567A19144E... | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 08/10/2016 |

**PVSC FORM MR-2 REV.3 6/93**

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | MONTH: July 2016 | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 7/1/2016 | Angel Trujillo | 66252920 | 66331772 | 78,852 | 0.078852 | 7.81 | 0.901 | | | | | | | | | 0.59 |
| 7/2/2016 | Angel Trujillo | 66331772 | 66410384 | 78,612 | 0.078612 | 7.60 | 0.901 | | | | | | | | | 0.59 |
| 7/3/2016 | Angel Trujillo | 66410384 | 66488997 | 78,613 | 0.078613 | 7.64 | 0.901 | | | | | | | | | 0.59 |
| 7/4/2016 | Angel Trujillo | 66488997 | 66568587 | 79,590 | 0.07959 | 7.59 | 0.901 | | | | | | | | | 0.60 |
| 7/5/2016 | Angel Trujillo | 66568587 | 66645834 | 77,247 | 0.077247 | 7.06 | 0.901 | | | | | | | | | 0.58 |
| 7/6/2016 | Angel Trujillo | 66645834 | 66723450 | 77,616 | 0.077616 | 7.01 | 0.901 | | | | | | | | | 0.58 |
| 7/7/2016 | Angel Trujillo | 66723450 | 66804476 | 81,026 | 0.081026 | 6.79 | 0.901 | <5.1 | 42.7 | | <0.010 | <0.030 | <0.010 | 0.00024 | <0.020 | 0.61 |
| 7/8/2016 | Angel Trujillo | 66804476 | 66877058 | 72,582 | 0.072582 | 7.04 | 0.901 | | | | | | | | | 0.55 |
| 7/9/2016 | Angel Trujillo | 66877058 | 66960358 | 83,300 | 0.0833 | 7.25 | 0.901 | | | | | | | | | 0.63 |
| 7/10/2016 | Angel Trujillo | 66960358 | 67034509 | 74,151 | 0.074151 | 7.00 | 0.901 | | | | | | | | | 0.56 |
| 7/11/2016 | Angel Trujillo | 67034509 | 67108660 | 74,151 | 0.074151 | 7.02 | 0.901 | | | | | | | | | 0.56 |
| 7/12/2016 | Angel Trujillo | 67108660 | 67186214 | 77,554 | 0.077554 | 7.00 | 0.901 | | | | | | | | | 0.58 |
| 7/13/2016 | Angel Trujillo | 67186214 | 67262708 | 76,494 | 0.076494 | 7.16 | 0.901 | | | | | | | | | 0.57 |
| 7/14/2016 | Angel Trujillo | 67262708 | 67343708 | 81,000 | 0.081 | 7.15 | 0.901 | | | | | | | | | 0.61 |
| 7/15/2016 | Angel Trujillo | 67343708 | 67416552 | 72,844 | 0.072844 | 7.09 | 0.901 | | | | | | | | | 0.55 |
| 7/16/2016 | Angel Trujillo | 67416552 | 67491180 | 74,628 | 0.074628 | 6.99 | 0.901 | | | | | | | | | 0.56 |
| 7/17/2016 | Angel Trujillo | 67491180 | 67567304 | 76,124 | 0.076124 | 7.20 | 0.901 | | | | | | | | | 0.57 |
| 7/18/2016 | Angel Trujillo | 67567304 | 67643428 | 76,124 | 0.076124 | 7.12 | 0.901 | | | | | | | | | 0.57 |
| 7/19/2016 | Angel Trujillo | 67643428 | 67723020 | 79,592 | 0.079592 | 7.11 | 0.901 | | | | | | | | | 0.60 |
| 7/20/2016 | Angel Trujillo | 67723020 | 67796418 | 73,398 | 0.073398 | 6.98 | 0.901 | | | | | | | | | 0.55 |
| 7/21/2016 | Angel Trujillo | 67796418 | 67877736 | 81,318 | 0.081318 | 7.06 | 0.901 | | | | | | | | | 0.61 |
| 7/22/2016 | Angel Trujillo | 67877736 | 67955362 | 77,626 | 0.077626 | 7.04 | 0.901 | | | | | | | | | 0.58 |
| 7/23/2016 | Angel Trujillo | 67955362 | 68040173 | 84,811 | 0.084811 | 7.00 | 0.901 | | | | | | | | | 0.64 |
| 7/24/2016 | Angel Trujillo | 68040173 | 68124984 | 84,811 | 0.084811 | 7.12 | 0.901 | | | | | | | | | 0.64 |
| 7/25/2016 | Angel Trujillo | 68124984 | 68186182 | 61,198 | 0.061198 | 6.93 | 0.901 | | | | | | | | | 0.46 |
| 7/26/2016 | Angel Trujillo | 68186182 | 68264614 | 78,432 | 0.078432 | 7.01 | 0.901 | | | | | | | | | 0.59 |
| 7/27/2016 | Angel Trujillo | 68264614 | 68339918 | 75,304 | 0.075304 | 6.98 | 0.901 | | | | | | | | | 0.57 |
| 7/28/2016 | Angel Trujillo | 68339918 | 68419386 | 79,468 | 0.079468 | 7.01 | 0.901 | | | | | | | | | 0.60 |
| 7/29/2016 | Angel Trujillo | 68419386 | 68496866 | 77,480 | 0.07748 | 7.23 | 0.901 | | | | | | | | | 0.58 |
| 7/30/2016 | Angel Trujillo | 68496866 | 68576958 | 80,092 | 0.080092 | 7.08 | 0.901 | | | | | | | | | 0.60 |
| 7/31/2016 | Angel Trujillo | 68576958 | 68652844 | 75,886 | 0.075886 | 7.20 | 0.901 | | | | | | | | | 0.57 |
| TOTAL | | | | 2,399,724 | 2.399724 | | | <5.1 | 42.7 | | <0.010 | <0.030 | <0.010 | 0.00024 | <0.020 | |
| | | | High: | 84,811 | | | | | | | | | | | High: | 0.64 |
| | | | Average: | 77,410 | | | | | | | | | | | Average: | 0.58 |

WW

E

JC23592

Accutest Labs
2235 ROUTE 130
Dayton, 8810
732-329-0200

# Honeywell — Chain Of Custody / Analysis Request

AESI Ref: 42558.46959

| | | | |
|---|---|---|---|
| Sampling Co.: | MACTEC | EDD To: | |
| Client Contact: (name, co., address) | | Sampler: | Frank Schroyer |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | | PO # | |
| Honeywell International | | Analysis Turnaround Time (TAT): | 3 |
| 101 Columbia Road Morristown, NJ 07962 | | Consultant | CH2M |
| Hard Copy To | Helen Fahy (Honeywell) | Full Report TAT: | 28 Days |
| Invoice To: | Helen Fahy (Honeywell) | | |

| | | | |
|---|---|---|---|
| COC# | 087-WW-070716 | | |
| Lab Proj # (SDG): | | | |
| Lab ID | ACTD | Site Name: | Hudson County |
| Site ID | HudsonCo | Location of Site: | Jersey City, NJ |
| Lab Job # | HWINJM32815 | Phase: | CS |
| Authorized User: | Honeywell | Sampling Program | 087: JCIA |

Text A Excel File Only | Excel & Text File Only

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite (Grab) | Excel Required? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-070716-A | 7/7/2016 | 14:55 | WW | WATER | REG | 5 | comp | N | X | X | X | X | | | X | X | | 1 | | | | L28 |
| 2 | 087-WW | | | 087-WWE-070716-B | 7/7/2016 | 15:00 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | V626 |
| 3 | 087-WW | | | 087-WWI-070716 | 7/7/2016 | 15:10 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | A5 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | G27 |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by | 6.79 S.U. | @ 9.0°C Company | AMEC Foster Wheeler | Received by | | Condition | Custody Seals Intact 232 |
| Frank Schroyer | | Date/Time 7/7/16 16:00 | | | Date/Time 7/7/16 16:00 | Cooler Temp. | |
| Relinquished by | | Company | | Received by | Company | Condition | Custody Seals Intact |
| | | Date/Time 7/7/16 17:25 | | | Date/Time 7/7/16 17:25 | Cooler Temp. 3.8°C | IP |
| Preservatives: (Other; Specify): | | | 0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2SO3); 13 (Zn Acetate); sp (special instructions) | | | |

INITIAL ASESSMENT JBJK

LABEL VERIFICATION JK

ALL SAMPLES RECEIVED PRESERVED AS APPLICABLE JK

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

SGS Accutest LabLink@922099 14:06 08-Aug-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-070716-A | | |
| Lab Sample ID: | JC23592-1 | Date Sampled: | 07/07/16 |
| Matrix: | AQ - Water | Date Received: | 07/07/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



Total Metals Analysis

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 901 | 10 | ug/l | 1 | 07/08/16 | 07/09/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Copper | < 10 | 10 | ug/l | 1 | 07/08/16 | 07/09/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 07/08/16 | 07/12/16 | ND | EPA 200.7 [3] | EPA 200.7 [5] |
| Mercury | 0.24 | 0.20 | ug/l | 1 | 07/08/16 | 07/08/16 | MS | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 07/08/16 | 07/09/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |
| Zinc | < 20 | 20 | ug/l | 1 | 07/08/16 | 07/09/16 | ND | EPA 200.7 [2] | EPA 200.7 [5] |

(1) Instrument QC Batch: MA39818
(2) Instrument QC Batch: MA39826
(3) Instrument QC Batch: MA39842
(4) Prep QC Batch: MP94800
(5) Prep QC Batch: MP94810

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

SGS Accutest LabLink@922099 14:06 08-Aug-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-070716-A | | |
| **Lab Sample ID:** | JC23592-1 | **Date Sampled:** | 07/07/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/07/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.1
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 07/08/16 | KP | SM2540 D-11 |
| pH [a] | 6.87 | | su | 1 | 07/07/16 17:47 | SUB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

SGS Accutest LabLink@922099 14:06 08-Aug-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-070716-A | | |
| Lab Sample ID: | JC23592-1A | Date Sampled: | 07/07/16 |
| Matrix: | AQ - Water | Date Received: | 07/07/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 42.7 | 10 | mg/l | 1 | 07/07/16 19:22 | LS | SM5210 B-11 |

RL = Reporting Limit

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

SGS Accutest LabLink@922099 14:06 08-Aug-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-070716-B | | |
| Lab Sample ID: | JC23592-2 | Date Sampled: | 07/07/16 |
| Matrix: | AQ - Water | Date Received: | 07/07/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | T218721.D | 1 | 07/08/16 | BK | n/a | n/a | VT8985 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 4.6 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.3 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.24 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 27.3 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.36 | 1.0 | 0.15 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.32 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 62.9 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 2.0 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.80 | 1.0 | 0.16 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

SGS Accutest LabLink@922099 14:06 08-Aug-2016

## Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-070716-B | | |
| Lab Sample ID: | JC23592-2 | Date Sampled: | 07/07/16 |
| Matrix: | AQ - Water | Date Received: | 07/07/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**VOA TVO List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 71.9 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 86% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 94% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 107% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 95% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

DocuSign Envelope ID: 59E15354-CA31-421C-9315-7024D0CBD141

SGS Accutest LabLink@922099 14:06 08-Aug-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| **Client Sample ID:** | 087-WWE-070716-B | | |
| **Lab Sample ID:** | JC23592-2 | **Date Sampled:** | 07/07/16 |
| **Matrix:** | AQ - Water | **Date Received:** | 07/07/16 |
| | | **Percent Solids:** | n/a |
| **Project:** | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 07/08/16 11:00 | TT | EPA 1664A |

**RL = Reporting Limit**

## Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized based field obersvations and constructability review. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2016-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2014-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA 6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to address the elimination of a drop structure, the elmination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead. | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | To be submitted to Parties as Attachment to Declaration 005. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | To be submitted to Parties as Attachment to Declaration 005. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | To be submitted to Parties as Attachment to Declaration 004. |

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-30** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2016-02-03** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. |
| **DC 2016-05-31** | This DCB documents the vault sketch Drawing C-310 (Rev 5, 5/31/16) | Submitted to Contractor only as clarification or response to RFI. All DCBs will be included in final Remedial Action Report. |

**SA-6 North/South Field Change Log - Month Ending August 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. |
| **DC 2016-7-12** | DC 2016-7-12 clarifies the limit of GCL deployment and the location of the sand bentonite plug in the SA-6 North cap. | Included as an attachment to July 2016 Monthly Progress Report. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

## Attachment 15: Issued Permit: NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils

State of New Jersey

DEPARTMENT OF ENVIRONMENTAL PROTECTION
SITE REMEDIATION PROGRAM
Mail Code 401-06
P.O. Box 420
Trenton, NJ 08625-0420

CHRIS CHRISTIE
Governor

KIM GUADAGNO
Lt. Governor

BOB MARTIN
Commissioner

August 4, 2016

William Hague, Director
Remediation Engineering and Construction
Honeywell International, Inc.
115 Tabor Road
Morris Plains, New Jersey 07950

Re: Permit-by-Rule Discharge Authorization
In-Situ Treatment of Chromium Impacted Soils
Study Area 6 – North
Hudson County Chromate Site 087
Jersey City, Hudson County
NJDEP PI # G000008710

Dear Mr. Hague:

This New Jersey Pollutant Discharge Elimination System/Discharge to Ground Water (NJPDES/DGW) authorization is hereby issued under the authority of the New Jersey Water Pollution Control Act, N.J.S.A. 58:10A-1 et seq. and the implementing regulations, N.J.A.C. 7:14A-1 et seq. N.J.A.C. 7:14A-7.5 authorizes this discharge of calcium polysulfide ($CaS_x$) to the ground waters of the State for the purpose of remediating chromium impacted soil at the above referenced site. Pursuant to N.J.A.C. 7:14A-22.4(b)5, a Treatment Works Approval is not required for discharges to ground water authorized pursuant to N.J.A.C. 7:14A-7.5 or 8.5. The discharge approved through this DGW Permit is to injection wells, and must be conducted in conformance with the "Proposed In-Situ Treatment Event for Remaining Hexavalent Chromium Impacted Soils, Treatment Area 10-1, SA-6 North, Site 087" (July 8, 2016) prepared by Amec Foster Wheeler E&I, Inc. for the subject site.

Honeywell is authorized to discharge fluids to the ground waters of the state from injection wells related to in-situ soil treatment where the discharge will not last more than 180 days from the first date of discharge. This NJPDES/DGW permit authorization is issued in order to facilitate the remedial activities conducted with oversight from the NJDEP. Specifically, the Administrative Consent Order executed between the NJDEP and AlliedSignal on June 17, 1993, pursuant to N.J.A.C. 7:26C, is the oversight document for remedial activities conducted at the site. In addition, remedial activities are being conducted in accordance with the Consent Decree Regarding Remediation and Redevelopment of Study Area 6 North entered by the Federal Court in JCMUA v. Honeywell Civ. No. 05-5955 on April 21, 2008. Termination of the oversight document by the

Department or Honeywell will revoke the permit-by-rule authorization to discharge to the ground waters of the State.

## I. DISCHARGE DESCRIPTION AND AREA RECEPTORS

### Site Description

The location of the permit-by-rule is Jersey City, Hudson County (west of Route 440, within Block 21901, Lot 9). The site has areas of soil contaminated with hexavalent chromium (Cr(VI)). The area targeted for in-situ treatment is Treatment Area 10-1. Area 10-1 is an 800 square foot area proximate to a 72 inch force main, with impacted soils located at 10 to 16 feet below grade. The impacted soils are contaminated with Cr(VI) at levels above 20 mg/kg and up to 39 mg/kg.

An initial in-situ treatment event with Calcium Polysulfide occurred at Area 10-1 between August and September 2015, in accordance with a Permit-By-Rule dated July 14, 2015. Post in-situ analytical results showed that Cr(VI) samples in the majority of areas treated are now below the 20 mg/kg clean up criteria. However, 5 out of 20 sample points contained soil which will require additional treatment. Calcium Polysulfide will be re-injected within all five original treatment points, not just the remaining areas of soil exceedances.

### Proposed Remedy

The proposed discharge is comprised of a Calcium Polysulfide ($CaS_x$) solution, which is to be injected into at least 10 temporary injection points within the targeted areas to convert hexavalent chromium (CrVI) to trivalent chromium (CrIII). Ten (10) 1-inch diameter PVC injection wells (IWs) will be drilled and installed within subarea TA-10-1, grouped in 5 nested pairs spaced approximately 15 feet apart, in the same general location as the previous 5 injection points. Wells within each pair will be screened at 3-foot intervals, one from 10 to 13 feet below ground surface and one from 13 to 16 feet below ground surface, to increase the vertical distribution of $CaS_x$. A total of 825 gallons of 29% $CaS_x$ will be mixed with approximately 2,425 gallons of potable water to produce 3,250 gallons of a 7% $CaS_x$ solution. Stoichiometric chemical dose is estimated to be 2.5X. The discharge will be within soils contaminated with hexavalent chromium between the depths of 10 to 16 feet, but will not be contained by recovery wells. The CaSx will be gravity fed from tanker trucks into the injection wells. Injections will occur over an estimated 5 weekly dosages of 650 gallons each. Each IW will receive 65 gallons of solution during each event.

The proposed area for the $CaS_x$ treatment in Area 10-1 is approximately 20 feet north of the force main location. As a contingency, Honeywell proposes that if the sulfate concentrations in either one or both of 087-MW-133 and 087-MW-134 reach 150 mg/L, clean potable water will be injected into both wells to dilute the sulfate concentrations in the shallow ground water adjacent to the force main.

**Site Monitoring Requirements**

Site monitoring will be scheduled as follows:

- **Baseline Monitoring**

Ten (10) injection wells (IWs) will be installed around the perimeter of the injection areas. The breathing zones at drilling locations will be monitored for volatile organic compounds (VOCs) and $H_2S$. Ground water monitoring wells 087-MW-132, 087-MW-133, and 087-MW-134 installed between subarea TA-10-1 and the adjacent force main (FM) for the 2015 injection event have been maintained in the area. The following measurements will be taken and recorded in the ten newly installed IWs and existing monitoring wells prior to the start of injections (baseline): depth to ground water; ground water quality parameters, including pH, oxidation/reduction potential (ORP), specific conductivity (SC), and total dissolved solids (TDS); hydrogen sulfide ($H_2S$) and volatile organic compounds (VOCs) in the headspace of the PVC riser pipe; and ground water color and/or odor. Ground water samples will be collected from the monitoring wells for analysis of sulfate and sulfide prior to the start of injections. Additionally, the five temporary well points (TWPs) 087-TWP-37 through 087-TWP-41 installed for the 2015 injection event have been maintained in the area and will also be monitored for sulfate and sulfide.

- **Injection Performance Monitoring**

During the course of injections, IWs and permanent monitoring wells will be sampled to monitor changes in water levels during injection, and to monitor distribution of reductant (changes in redox and conductivity as well as sulfate and sulfide concentration), and sampled for ground water quality parameters, including pH, ORP, SC, and TDS; $H_2S$ and VOCs in the headspace of the PVC riser pipe and ground water color and/or odor. The breathing zones at storage, mixing, and injection areas will be monitored for hydrogen sulfide (H2S). Ground water samples will be collected from the TWPs and monitoring wells within the vicinity of the treatment area for analysis of sulfate and sulfide each week between dosages.

- **Post-Injection Sampling**

Subsequent to the completion of the injection program, IWs and permanent monitoring wells will be sampled for ground water quality parameters, including pH, ORP, SC, and TDS; $H_2S$ and VOCs in the headspace of the PVC riser pipe and ground water color and/or odor. Also, at a minimum, samples will be collected from the TWPs and monitoring wells for analysis of sulfate and sulfide each week between dosages and for several weeks after the last dosage. Additional sampling may be implemented if conditions warrant.

The treatment remedy is being performed with a goal of long-term protectiveness. Approximately six months after the final (fifth) weekly injection dosage in subarea TA-10-1 (weather permitting), Honeywell will collect and analyze ten (10) soil samples to evaluate the effectiveness of the in-situ treatment. A second round of soil sampling will be conducted 3 years after completion of the field program. Honeywell may seek to conduct the final sampling event sooner than 3 years after the completion of the TA-10-1 injection program. Soil samples will be analyzed for Cr(VI) (3060A/7199).

All sampling and monitoring will be performed according to the methodology specified in the most current edition of the Department's Field Sampling Procedures Manual. All samples are to be analyzed by a New Jersey Certified Laboratory except those field-determined parameters specified in the monitoring program.

## II. CONSTRUCTION REQUIREMENTS

Ten (10) 1-inch diameter PVC injection wells (IWs) will be drilled and installed within subarea TA-10-1, grouped in 5 nested pairs. Wells within each pair will be screened at 3-foot intervals, one from 10 to 13 feet below ground surface and one from 13 to 16 feet below ground surface.

All design plans and specifications for the injection wells shall be retained and made available to the Department upon request. UIC Class V injection wells shall be operated and maintained pursuant to N.J.A.C. 7:14A-8.16 (c)1. Upon termination of injection well operations, the UIC-Class V injection wells will be properly closed and abandoned in accordance with N.J.A.C. 7:14A-8.16(d).

## III. SYSTEM OPERATION AND CLOSURE

The injection wells shall be inspected during injection activities for evidence of malfunction. Said evidence shall include, but not be limited to: breakout, wet areas, ponding, or odors. Discharge of water via any discharge to ground water unit shall not create an unpermitted discharge to any surface water of the State, create a persistent standing, ponded or surface-flowing fluid condition. Honeywell shall conduct periodic inspections of the treatment area throughout the injection.

Upon termination of the discharge, any discharge to ground water units will be properly closed and abandoned. Any temporary UIC-Class V injection wells shall be properly abandoned in accordance with N.J.A.C. 7:14A-8.16(d).

## IV. REPORTING REQUIREMENTS AND INFORMATION SUBMITTALS:

Honeywell, AMEC or a subcontractor will submit the Remedial Action Report, and any other information identified above which is required to be delivered to the Department, to:

Thomas J. Cozzi, Assistant Director
New Jersey Department of Environmental Protection
Site Remediation Program
Mail Code 401-06
P.O. Box 420
Trenton, NJ 08625-0420

The Department contact for this Permit-by-Rule Authorization is:

Attention: David Van Eck
New Jersey Department of Environmental Protection
Bureau of Ground Water Pollution Abatement
Mail Code 401-05V
P.O. Box 420
Trenton, NJ 08625-0420
Phone: (609) 633-2427

If you have any questions, please contact Thomas J. Cozzi of the Site Remediation Program at (609) 984-2905.

Sincerely,

Thomas J. Cozzi, Assistant Director
NJDEP Site Remediation

c: David Doyle, NJDEP
David Van Eck, NJDEP
Maria Kaouris, Honeywell
Dennis Nagg, Amec Foster Wheeler E & I

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 15 OF 25**

- **2016 Monthly Reports Part 4**

**10/12/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

October 12, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-09**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from September 1 – September 30, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: September 2016 SA-6/7 Combined Monthly Progress Report No. 2016-09

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP (electroni copy)

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-09

**Project SA-6 & 7 Remediation**

## September 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 09/01/16 | Groundwater Sampling Results<br>Study Area 6 South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/01/16 | LTMP Response to Comments (transmitted by Arnold & Porter) | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/08/16 | Response to Comments<br>Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-07 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/12/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-08 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/13/16 | Special Master Meeting | N/A |
| 09/19/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 09/19/16 | Shallow Limited Excavation at Treatment Area 7<br>Study Area 6 North<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/23/16 | Response to Comments<br>Integrated Annual Groundwater Performance Report for 2015<br>Study Areas 5, 6, and 7<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/26/16 | SA-6 Declaration 02<br>Study Area 6 South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 09/30/16 | SA-6 Declaration 3<br>Study Area 6 North<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

# SITE OPERATIONS

## 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | | |
|---|---|---|---|---|---|
| | 9/4/16 | 9/11/16 | 9/18/16 | 9/25/16 | 10/2/16 |
| **Construction Management (AMEC)** | 10 | 8 | 9 | 8 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 30 | 29 | 28 | 27 | 24 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 1 | 0 |
| **E&V Dirt Works** | 2 | 0 | 0 | 0 | 0 |
| **Lagan** | 0 | 0 | 0 | 0 | 0 |
| **ERFS** | 1 | 1 | 1 | 0 | 0 |
| **Evoqua** | 1 | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 2 | 0 | 1 | 0 | 0 |
| **Cornerstone** | 0 | 0 | 0 | 1 | 2 |
| **TOTAL STAFF** | **51** | **44** | **45** | **43** | **41** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Conducted perimeter air monitoring activities using hand-held portable devices for nuisance dust.
- Continued installation of CGWES components within the SA-6 South and the SA-6 North Open Space Areas to include installation of the valve vaults and link seals.
- ERFS Continued injections in Treatment Area 10-1 in accordance with NJDEP-DGW permit.
- Implemented post-injection groundwater sampling and monitoring in Treatment Area 10-1 in accordance with the NJDEP – Discharge to Groundwater Permit.
- Collected groundwater samples for chromium and hexavalent chromium analysis of filtered and unfiltered from the interior piezometers at both SA-6 North and South Open Space Areas.
- Completed third round of quarterly regional groundwater level measurements.
- Collected September PVSC compliance sample from the Construction Water Treatment Plant (CWTP).

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on September 13, 2016.
- Reviewed submittals from the mechanical contractor, Brownfield Science & Technology, Inc. (BTSI), associated with piping installation from the CGWTS force mains to the neutralization tank in accordance with the PVSC permit.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | | |
|---|---|---|---|---|---|
| | 9/4/16 | 9/11/16 | 9/18/16 | 9/25/16 | 10/2/16 |
| Avg. Gallons Treated & Discharged (per day) | 78,586 | 76,458 | 77,623 | 77,940 | 78,057 |
| Average Flow (gpm) for Operating Period | 56 | 54 | 55 | 56 | 56 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 3,989 | 3,780 | 3,312 | 3,264 | 2,928 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Continued routine dewatering activities and associated discharge to the construction water treatment facility.
- Completed placing backfill as part of site restoration in the SA-6 South Development Area.
- Continued placement of historic fill cap to include geotextile and 6-inches of stone in the SA-6 South Development Area.
- Completed placement of asphalt to restore the JCMUA driveway.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 0 | 0 | 0 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Backfill in Progress** | 3/4" stone Historic Fill Cap – SA-6 South Development Area |

### 3. BACKFILL MATERIALS USED (TONS)

| Source | Week Ending | | | | |
|---|---|---|---|---|---|
| | 9/4/16 | 9/11/16 | 9/18/16 | 9/25/16 | 10/2/16 |
| Natures Choice Topsoil | 376 | 454 | 1,125 | 1,569 | 898 |
| Tilcon Mt. Hope DGA | 0 | 0 | 1,654 | 0 | 0 |
| Tilcon Mount Hope I-8 | 4,458 | 4,148 | 4,248 | 4,604 | 2,738 |
| Natures Choice Horizon C | 1,350 | 0 | 6,116 | 726 | 308 |
| Tilcon 3/8" Stone | 0 | 51.51 | 51 | 51 | 76.23 |
| Tilcon Mt. Hope 1.5" | 0 | 0 | 0 | 0 | 250 |
| Tilcon Mt. Hope #57 | 629 | 2,606 | 3,742 | 3,473 | 1,348 |
| Weldon Screenings | 0 | 0 | 0 | 0 | 1,086 |

- Screened Celgene material was placed as protective cover soil in the SA-6 North Open Space Area. Approximately 464 cubic yards were placed as protective cover soil during the reporting period.

## D. SURCHARGE OPERATIONS

- All surcharging activities are completed.

## E. SHEET PILE OPERATIONS

- All sheet pile operations are complete.

## F. CAPPING OPERATIONS

- Continued importing and placing Horizon A soils on SA-6 South Open Space Area.
- Begin construction of the SA-6 South Temporary Access Road in utility corridor B.
- Begin installation of toe drain on the north site of the SA6 South Open Space Area.
- Completed placement of GDL cover soils and demarcation tape to include associated compaction testing on the SA-6 North Open Space Area.
- Continued placement structural fill to included compaction.
- Completed placement of root barrier, and Horizon C soils to include associated compaction testing on the SA-6 North Open Space Area.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 08/04/2016 | Not Specified | Not Specified | 9/12/16 |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete importing and placement of Horizon A Topsoil on the SA-6 South Open Space Area.
- Complete hydro-seeding of SA-6 South Open Space Area.
- Complete placement of historic fill cap to include geotextile and 6-inches of stone in the SA-6 South Development Area.
- Complete installation of the Contingent Groundwater Extraction System Components including the mechanical piping and conduit within the GWTP.
- Complete placement structural fill, root barrier, and Horizon C soils to include associated compaction testing on the SA-6 North Open Space Area.
- Begin placement of Horizon A Topsoil on the SA-6 North Open Space Area.
- Begin hydro-seeding of SA-6 North Cap Area.
- Continue storm-water management activities.
- Begin cleaning and demobilization of temporary CWTS.
- Continue SWPPP inspections.
- Complete PVSC Monthly compliance sampling.
- Conduct S-3 Mass Removal Injection Event No. 32 in well 088-IW-01 (completed October 3, 2016).
- Conduct S-3 Mass Removal Injection Event No. 33 in well 088-IW-02.
- Complete injections in Treatment Area 10-1 in accordance with NJDEP-DGW permit.

## ATTACHMENTS:

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data *(reported quarterly – not included in this report)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update (SA-6 Cap Subgrade Progress Maps)
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log


## Attachment 1:  Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **Fri 1/4/08** |
| **2** | **Remedial Action Work Plan** | **33 days** | **Fri 1/4/08** |
| **5** | **Remedial Action Design** | **1522 days** | **Wed 2/20/08** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 949 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 146 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **26** | **Remedial Action Work Plan** | **187 days** | **Fri 7/11/08** |
| **32** | **Remedial Action Design** | **1161 days** | **Mon 2/2/09** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | Fri 11/15/13 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | Tue 4/8/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Tue 6/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | Mon 6/16/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | Mon 10/6/14 |
| **63** | **Barrier Wall Install** | **569 days** | **Mon 8/12/13** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | Mon 3/9/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | Mon 8/12/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| 64b | SA 6S Excavation | 295 days | Tue 10/22/13 |
| **65** | **Backfill** | **558 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 283 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 384 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | Thu 3/24/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **234 days** | **Tue 9/1/15** |
| 67a | Restoration | 234 days | Tue 9/1/15 |
| **68** | **Demobilization** | **22 days** | **Fri 7/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | 1 day | Fri 3/1/13 |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | 1 day | Fri 3/1/13 |
| **69** | **SA-6 North Project Closeout** | **311 days** | **Thu 10/1/15** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **Thu 10/1/15** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **Wed 10/1/08** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **Thu 6/5/08** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/2/2016

Task | Milestone | Summary | Critical


Note: Current field implementation schedule shows capping complete in September 2016 and restoration in October 2016.

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **Fri 1/4/08** |
| **2** | **Remedial Action Work Plan** | **33 days** | **Fri 1/4/08** |
| **5** | **Remedial Action Design** | **1522 days** | **Wed 2/20/08** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 949 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 146 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **26** | **Remedial Action Work Plan** | **187 days** | **Fri 7/11/08** |
| **32** | **Remedial Action Design** | **1161 days** | **Mon 2/2/09** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | Fri 11/15/13 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | Tue 4/8/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Tue 6/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | Mon 6/16/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | Mon 10/6/14 |
| **63** | **Barrier Wall Install** | **569 days** | **Mon 8/12/13** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | Mon 3/9/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | Mon 8/12/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| 64b | SA 6S Excavation | 295 days | Tue 10/22/13 |
| **65** | **Backfill** | **558 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 283 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 384 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | Thu 3/24/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **234 days** | **Tue 9/1/15** |
| 67a | Restoration | 234 days | Tue 9/1/15 |
| **68** | **Demobilization** | **22 days** | **Fri 7/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | 1 day | Fri 3/1/13 |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | 1 day | Fri 3/1/13 |
| **69** | **SA-6 North Project Closeout** | **311 days** | **Thu 10/1/15** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **Thu 10/1/15** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **Wed 10/1/08** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **Thu 6/5/08** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/2/2016

Task | Milestone | Summary | Critical

Note: Current field implementation schedule shows capping complete in September 2016 and restoration in October 2016.

## Attachment 2: Site Photographs




**Site Photograph 1:** Compacting clean fill on Open Space Area.




**Site Photograph 2:** Delivering clean stone to Kellogg St Properties.




**Site Photograph 3:** Delivering clean top soil for SA6 South Open Space Area.




**Site Photograph 4:** Grading structural fill along SA6 North Open Space Area.




**Site Photograph 5:** Grading topsoil at SA6 South Open Space Area.





**Site Photograph 6:** Placement of asphalt for the JCMUA south entrance.

## Attachment 3: Excavation and Backfill Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of October 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-09
Attachment 3: Excavation and Backfill



## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)

| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 07/07/16 | 7:30 | 12:00 | 4:30 | 43,596.37 | 43,642.93 | 46,560 | 43,642,480 | PVSC Compliance Sample Collected |
| 07/15/16 | 10:00 | 14:00 | 4:00 | 43,642.93 | 43,692.98 | 50,050 | 43,692,530 | |
| 07/26/16 | 9:00 | 14:00 | 5:00 | 43,692.98 | 43,794.27 | 101,290 | 43,793,820 | |
| 07/27/16 | 7:00 | 15:00 | 8:00 | 43,794.27 | 43,826.36 | 32,090 | 43,825,910 | |
| 07/28/16 | 9:00 | 15:00 | 6:00 | 43,826.36 | 43,860.98 | 34,620 | 43,860,530 | |
| 08/01/16 | 9:00 | 15:00 | 6:00 | 43,860.98 | 43,896.38 | 35,400 | 43,895,930 | PVSC Compliance Sample Collected |
| 08/11/16 | 9:00 | 16:00 | 7:00 | 43,896.38 | 43,958.93 | 62,550 | 43,958,480 | |
| 08/12/16 | 9:30 | 13:45 | 4:15 | 43,958.93 | 43,998.63 | 39,700 | 43,998,180 | |
| 08/19/16 | 8:00 | 13:30 | 5:30 | 43,998.63 | 44,062.58 | 63,950 | 44,062,130 | |
| 09/08/16 | 7:00 | 13:00 | 6:00 | 44,062.58 | 44,120.80 | 58,220 | 44,120,350 | PVSC Compliance Sample Collected |

Notes: Previous information is truncated. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data

(not included in this reporting period)

## Attachment 7: Perimeter Pools Update

HACKENSACK RIVER

POOL N4 ELEV.+6.5 525'
POOL N3 ELEV.+7.5 343'
POOL N2 ELEV.+8.0 237'
POOL N1 ELEV.+10.0 660'
POOL E1 ELEV.+9.0 325'
POOL E2 ELEV.+8 270'
POOL S4 ELEV.+6.0 419'
POOL S3 ELEV.+7.0 640'
POOL S2 ELEV.+7.5 622'
POOL S1 ELEV.+8 338'

N4 N3 N2 N1 E1 E2 S4 S3 S2 S1

INTERIOR POOL ELEVATION CONTROLLED BY WEST BARRIER CUTOFF ELEV. +4.0

INTERIOR POOL ELEV. +4.0

COMPACTED CLAY DAM SEPARATING PERIMETER POOLS (TYP.)

COMPACTED CLAY LEVEE SEPARATING PERIMETER POOL FROM INTERIOR POOL (TYP.)

S-C-B BARRIER (TYP.)

087-MW-Y20 087-MW-S19 087-MW-O19 087-MW-O01 088-MW-G19 090-MW-E1
115-PZ-6 115-PZ-5 115-PZ-4
117-MW-A99 117-MW-A85 117-MW-A89
073-MW-BB11 073-MW-Y10
134-MW-V09 134-MW-Q08
140-MW-06 140-MW-07
125-MW-L03
MW-124-103L MW-124-102D MW-124-103D MW-124-102T

NORTH-FS-1 NORTH-FS-2 NORTH-FS-3 NORTH-FS-4 NORTH-FS-5 NORTH-FS-6 NORTH-FS-7 NORTH-FS-8 NORTH-FS-9 NORTH-FS-13
SOUTH-FS-1 SOUTH-FS-3 SOUTH-FS-4 SOUTH-FS-5 SOUTH FS-7 SOUTH-FS-6

W6-S0 W1-S0 W5-S0 W3-S0 E5-S0 E4-S0 E3-S0 E2-S0 E1-S0 E1A-S0

STA N1+10 STA N6+35 STA N6+80 STA N10+23 STA N10+73 STA N13+10 STA N13+60 STA N20+25 STA E0+50 STA E3+75 STA E4+50 STA E7+25 STA S0+50 STA S3+38 STA S4+38 STA S10+60 STA S11+10 STA S17+50 STA S17+86 STA S22+06

KELLOGG STREET

LEGEND

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

GRAPHIC SCALE
100' 50' 0 100' 200'


IN PROGRESS
06-10-2015

STUDY AREA 7
PERIMETER POOL DESIGN ELEVATIONS
NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1

Jul 09, 2015 at 3:14pm
C:\DWGS\102\10210\Dewatering\PP-1.dwg
bbascaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)


Honeywell is evaluating if additional flushing of the perimeter pool line is needed.





**Perimeter Pool N3** (Sta. N6+80 to N10+23) Honeywell is evaluating if additional flushing of the perimeter pool line is needed.





**Perimeter Pool N4** (Sta. N6+80 to N10+23) Honeywell is evaluating if additional flushing of the perimeter pool line is needed.





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

# Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-5 | FS-6 | FS-7 | FS-13 |
| Date | | | | | | | | | | | | | |
| 10/1/2015 | 1.8 | 4.5 | 5.2 | 3.2 | 3.7 | | 1.2 | 1.6 | 5.8 | 4.4 | 4.4 | 3.5 | |
| 10/15/2015 | 1.8 | 4.5 | 5.1 | 4.1 | 4.2 | | 1.1 | 1.5 | 6.1 | 4.7 | 4.6 | 4.0 | 4.0 |
| 10/28/2015 | 1.9 | 4.6 | 4.9 | 3.9 | 4.1 | 6.9 | 1.3 | 1.5 | 6.1 | 4.7 | 4.6 | 3.9 | 3.8 |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | 4.6 | 4.6 | 3.7 | 3.4 |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | 4.5 | 5.0 | 3.8 | 3.5 |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | 3.5 | 3.6 | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | 5.2 | | | 4.6 |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | 6.0 | | | 5.6 |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | 6.5 | | | 6.2 |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | 6.0 | | | 5.7 |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | 5.6 | | | 5.0 |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | 2.7 | | | 3.6 |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | 2.1 | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | 1.8 | | | |
| 5/2/2016 | 3.0 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | 1.6 | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | |
| 6/1/2016 | 2.7 | 5.2 | 5.5 | 2.5 | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/16/2016 | 2.7 | 5.2 | 5.6 | | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/28/2016 | 3.2 | 5.2 | 5.6 | 2.4 | 3.2 | 2.3 | 3.1 | 3.1 | 1.8 | | | | |
| 7/15/2016 | 3.2 | 5.3 | 5.6 | 2.5 | 3.3 | 2.4 | 3.1 | 3.2 | 1.8 | | | | |
| 7/27/2016 | 3.1 | 5.3 | 5.4 | 2.6 | 3.2 | 2.3 | 3.1 | 3.2 | 2.0 | | | | |
| 8/12/2016 | 3.4 | 5.3 | 5.6 | 3.2 | 2.6 | 2.8 | 3.3 | 3.4 | 2.5 | | | | |
| 8/29/2016 | 3.5 | 5.1 | 5.4 | 3.1 | 2.6 | 2.8 | 3.4 | 3.4 | 2.7 | | | | |
| 9/9/2016 | 3.5 | 5.0 | 5.4 | 3.2 | 3.4 | 2.6 | 3.4 | 3.5 | 2.3 | | | | |
| 9/29/2016 | 3.5 | 4.8 | 5.2 | 3.2 | 3.3 | 3.1 | 3.5 | 3.5 | 1.7 | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

## Attachment 8: Groundwater Quality Data

(not included in this reporting period)


## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

## Attachment 10: Sheet Pile Update

(not included in this reporting period)

**Attachment 11: Capping Update** (SA-6 Cap Subgrade Progress Maps)



LEGEND

HORIZON C SOIL PLACED

STRUCTURAL FILL PLACED


SCB WALL

HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP COVER SOILS PROGRESS MAP
10/03/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LEGEND

- HORIZON B PLACED AND READY FOR TOPSOIL
- HORIZON C PLACED AND READY FOR TOPSOIL
- TOPSOIL PLACED
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
10/03/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 2, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1,2 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/06/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, September 02, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | No sediment controls are currently in place for the newly-installed historic fill lifts along Droyer's Cove on SA-6 South. |
| 2 | IA2Q4A1AL8 | Additional sandbags are needed in the low areas along the eastern edge of the south cap to prevent Horizon A soils from eroding off site during storm events. |
| 3 | IA2Q4A1AL8 | The filter fabric in the catch basins along the north side of Kellogg Street is blinded with sediment. |
| 4 | IA2Q4A1AL8 | Garbage has accumulated on the grass area by the Kellogg Street jughandle |
| 5 | IA2Q4A1AL8 | The filter fabric in the catch basins by the former JCIA garbage pit on SA-6 North is blinded with sediment. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/08/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt fence or else geotextile with stone cover along the edge of Droyer's Cove on the southern development area. | 9/8/16 RAD |
| 2 | Place additional sandbags along the low areas on the eastern end of the south cap area. | |
| 3 | Replace the filter fabric in the five catch basins along the north side of Kellogg Street, starting at the truck entrance and going westward to the end of the street. | |
| 4 | Pick up and dispose of the accumulated garbage/debris. | |
| 5 | Replace the filter fabric in the catch basins to the north of the former JCIA trash pit. | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 09/08/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 9, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 1 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 4 |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/12/16

SWPPP Observer: _____
Signature

Honeywell

# STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE

Friday, September 09, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: No sediment controls are currently in place for the newly-installed historic fill lifts along Droyer's Cove on SA-6 South. |
| 2 | IA2Q4A1AL8 | REPEAT: The filter fabric in the catch basins along the north side of Kellogg Street is blinded with sediment. |
| 3 | IA2Q4A1AL8 | REPEAT: Garbage has accumulated on the grass area by the Kellogg Street jughandle |
| 4 | IA2Q4A1AL8 | No erosion control measures are in place between the MUA South Driveway work area and the public sidewalk on Rt. 440. |
| 5 | IA2Q4A1AL8 | REPEAT: The filter fabric in the catch basins by the former JCIA garbage pit on SA-6 North is blinded with sediment. |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/12/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Install silt fence or else geotextile with #57 stone cover along the edge of Droyer's Cove on the southern development area. | 9-15-16 RM |
| 2 | Replace the filter fabric in the five catch basins along the north side of Kellogg Street, starting at the truck entrance and going westward to the end of the street. | |
| 3 | Pick up and dispose of the accumulated garbage/debris. | |
| 4 | Install erosion control measures in this area. | |
| 5 | Replace the filter fabric in the catch basins to the north of the former JCIA trash pit. | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 09/15/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 16, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/19/16

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE

**Friday, September 16, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Additional sandbags are needed at the eastern end of the SA-6 South cap where it abutts the Rt. 440 sidewalk. |
| 2 | IA2Q4A1AL8 | Garbage and other debris is present in the Rt. 440 pedestrian walkway at the eastern end of SA-6 North. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/19/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Place additional sandbags on top of the existing ones (where needed) to prevent stormwater runoff from carrying sediment to the Rt. 440 sidewalk and catch basins. | 9-19-16 RAD |
| 2 | Pick up and dispose of accumulated litter and garbage in the SA-6 North pedestrian walkway. | ✓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 09/19/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 23, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/26/16

SWPPP Observer: _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, September 23, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen on the perimeter fence by the MUA administrative building is detached or missing in two areas. |
| 2 | IA2Q4A1AL8 | Sediment has accumulated on the filter fabric in the catch basin near the eastern side of the sedimentation basin. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 09/26/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach or replace windscreen fabric on the perimeter fence adjacent to the MUA admin building as needed. | 9/26/16 RPD |
| 2 | Replace the filter fabric in the catch basin. | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 09/29/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: September 30, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 2 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 09/30/16

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE

**Friday, September 30, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and debris has accumulated on the grassy area by the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | REPEAT: Windscreen on the perimeter fence by the MUA administrative building is detached or missing in two areas. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 09/30/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and dispose of accumulated garbage along the Kellogg Street jughandle and along Kellogg Street. | 10/5/16 RAD |
| 2 | Re-attach or replace windscreen fabric on the perimeter fence adjacent to the MUA admin building as needed. | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 10/05/16

## Attachment 13: GWTP Update (525/575 Route 440 GWTP PVSC Discharge Monitoring Report - submitted August 2016)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

September 19, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the August 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy /sgf

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 8 | 01 | 16 | 8 | 31 | 16 |
| \ | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,329 | 82,476 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.72 | 0.77 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1595 | 0.1595 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J Morris VP
Signature of Principal
Executive or Authorized Agent

John J. Morris
Remediation Portfolio Director
Type Name and Title

09/16/2016
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 8 | 01 | 16 | 8 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD | |
|---|---|
| 2,397,212 | GALS |
| CU. FT X 7.48 - GALLONS | |
| | |
| EFFLUENT METER READING LAST DAY THIS PERIOD | 71,049,856 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 8/9/2016 | <5.0 | 4.2 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 09/15/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: August 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | $BOD_5$ | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 8/1/2016 | Angel Trujillo | 68652644 | 68728330 | 75,686 | 0.075686 | 7.22 | 1.120 | | | | | | | | | 0.71 |
| 8/2/2016 | Angel Trujillo | 68728330 | 68804226 | 75,896 | 0.075896 | 7.96 | 1.120 | | | | | | | | | 0.71 |
| 8/3/2016 | Angel Trujillo | 68804226 | 68881512 | 77,286 | 0.077286 | 8.17 | 1.120 | | | | | | | | | 0.72 |
| 8/4/2016 | Angel Trujillo | 68881512 | 68958126 | 76,614 | 0.076614 | 7.86 | 1.120 | | | | | | | | | 0.72 |
| 8/5/2016 | Angel Trujillo | 68958126 | 69036568 | 78,442 | 0.078442 | 8.03 | 1.120 | | | | | | | | | 0.73 |
| 8/6/2016 | Angel Trujillo | 69036568 | 69118306 | 81,738 | 0.081738 | 8.13 | 1.120 | | | | | | | | | 0.76 |
| 8/7/2016 | Angel Trujillo | 69118306 | 69192009 | 73,703 | 0.073703 | 8.10 | 1.120 | | | | | | | | | 0.69 |
| 8/8/2016 | Angel Trujillo | 69192009 | 69265712 | 73,703 | 0.073703 | 7.97 | 1.120 | | | | | | | | | 0.69 |
| 8/9/2016 | Angel Trujillo | 69265712 | 69348188 | 82,476 | 0.082476 | 7.12 | 1.120 | <5.1 | <5.0 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | 0.77 |
| 8/10/2016 | Angel Trujillo | 69348188 | 69422849 | 74,661 | 0.074661 | 8.05 | 1.120 | | | | | | | | | 0.70 |
| 8/11/2016 | Angel Trujillo | 69422849 | 69500076 | 77,227 | 0.077227 | 8.15 | 1.120 | | | | | | | | | 0.72 |
| 8/12/2016 | Angel Trujillo | 69500076 | 69579008 | 78,932 | 0.078932 | 8.15 | 1.120 | | | | | | | | | 0.74 |
| 8/13/2016 | Angel Trujillo | 69579008 | 69658212 | 79,204 | 0.079204 | 8.19 | 1.120 | | | | | | | | | 0.74 |
| 8/14/2016 | Angel Trujillo | 69658212 | 69733571 | 75,359 | 0.075359 | 8.10 | 1.120 | | | | | | | | | 0.70 |
| 8/15/2016 | Angel Trujillo | 69733571 | 69808930 | 75,359 | 0.075359 | 8.11 | 1.120 | | | | | | | | | 0.70 |
| 8/16/2016 | Angel Trujillo | 69808930 | 69886178 | 77,248 | 0.077248 | 8.09 | 1.120 | | | | | | | | | 0.72 |
| 8/17/2016 | Angel Trujillo | 69886178 | 69963024 | 76,846 | 0.076846 | 8.10 | 1.120 | | | | | | | | | 0.72 |
| 8/18/2016 | Angel Trujillo | 69963024 | 70038618 | 75,594 | 0.075594 | 8.25 | 1.120 | | | | | | | | | 0.71 |
| 8/19/2016 | Angel Trujillo | 70038618 | 70117954 | 79,336 | 0.079336 | 8.12 | 1.120 | | | | | | | | | 0.74 |
| 8/20/2016 | Angel Trujillo | 70117954 | 70196154 | 78,200 | 0.0782 | 7.99 | 1.120 | | | | | | | | | 0.73 |
| 8/21/2016 | Angel Trujillo | 70196154 | 70273460 | 77,306 | 0.077306 | 8.20 | 1.120 | | | | | | | | | 0.72 |
| 8/22/2016 | Angel Trujillo | 70273460 | 70350766 | 77,306 | 0.077306 | 8.18 | 1.120 | | | | | | | | | 0.72 |
| 8/23/2016 | Angel Trujillo | 70350766 | 70424330 | 73,564 | 0.073564 | 8.20 | 1.120 | | | | | | | | | 0.69 |
| 8/24/2016 | Angel Trujillo | 70424330 | 70503620 | 79,290 | 0.07929 | 8.21 | 1.120 | | | | | | | | | 0.74 |
| 8/25/2016 | Angel Trujillo | 70503620 | 70581100 | 77,480 | 0.07748 | 8.27 | 1.120 | | | | | | | | | 0.72 |
| 8/26/2016 | Angel Trujillo | 70581100 | 70658594 | 77,494 | 0.077494 | 8.12 | 1.120 | | | | | | | | | 0.72 |
| 8/27/2016 | Angel Trujillo | 70658594 | 70739518 | 80,924 | 0.080924 | 8.23 | 1.120 | | | | | | | | | 0.76 |
| 8/28/2016 | Angel Trujillo | 70739518 | 70815334 | 75,816 | 0.075816 | 7.10 | 1.120 | | | | | | | | | 0.71 |
| 8/29/2016 | Angel Trujillo | 70815334 | 70891150 | 75,816 | 0.075816 | 7.95 | 1.120 | | | | | | | | | 0.71 |
| 8/30/2016 | Angel Trujillo | 70891150 | 70968302 | 77,152 | 0.077152 | 8.16 | 1.120 | | | | | | | | | 0.72 |
| 8/31/2016 | Angel Trujillo | 70968302 | 71049856 | 81,554 | 0.081554 | 8.25 | 1.120 | | | | | | | | | 0.76 |
| TOTAL | | | | 2,397,212 | 2.397212 | | | <5.1 | <5.0 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 82,476 | | | | | | | | | | | High: | 0.77 |
| | | | Average: | 77,329 | | | | | | | | | | | Average: | 0.72 |

WW

E

JC25469

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42591.41809 |
|---|---|---|---|---|
| 2235 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County | Phase: CS | COC# 087-WW-080916 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ | Sampling Program 087: JCIA | Lab Proj # (SDG): |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | | Lab ID ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | Preservative 3 | 3 3 1 2 2 0 0 2 | Site ID HudsonCo |
| Honeywell International<br>101 Columbia Road Morristown, NJ 07962 | Analysis Turnaround Time (TAT): 3<br>Consultant CH2M | | | Lab Job # HWINJM32815 |
| Preliminary Data To | | | | Authorized User: Honeywell |
| Sample Receipt Acknowledgement To: Frank Schroyer | | | | Text & Excel File Order: Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | Copyright AESI: Version 8.0 Unauthorized use strictly prohibited. |

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cu, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-080916-A | 8/9/2016 | 14:50 | WW | WATER | REG | 5 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | |
| 2 | 087-WW | | | 087-WWE-080916-B | 8/9/2016 | 14:55 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | A7 |
| 3 | 087-WW | | | 087-WWI-080916 | 8/9/2016 | 15:00 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | G2 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | L23 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | V862 |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: 7.12 S.U. @7.5°C | Company: AMEC Foster Wheeler | Received by: | Company: | | Condition: | | Custody Seals Intact: | |
| Frank Schroyer | Date/Time: 8/9/16 1505 | | Date/Time: 8-9 1505 | | Cooler Temp. | | | |
| Relinquished by: | Company: | Received by: | Company: SGS | | Condition: | | Custody Seals Intact: | |
| 8-9 1630 | Date/Time: | | Date/Time: 8/9/16 1630 | | Cooler Temp. | | | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

INITIAL ASESSMENT 2A-OB 04.5 SB

LABEL VERIFICATION_____

SGS Accutest LabLink@926159 15:42 09-Sep-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-080916-A | | |
| Lab Sample ID: | JC25469-1 | Date Sampled: | 08/09/16 |
| Matrix: | AQ - Water | Date Received: | 08/09/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

**Total Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1120 | 10 | ug/l | 1 | 08/10/16 | 08/11/16 | KS | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 08/10/16 | 08/11/16 | KS | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 08/10/16 | 08/12/16 | ND | EPA 200.7 [3] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 08/11/16 | 08/11/16 | MS | EPA 245.1 [1] | EPA 245.1 [5] |
| Nickel | < 10 | 10 | ug/l | 1 | 08/10/16 | 08/11/16 | KS | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 08/10/16 | 08/11/16 | KS | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA40059
(2) Instrument QC Batch: MA40065
(3) Instrument QC Batch: MA40073
(4) Prep QC Batch: MP95353
(5) Prep QC Batch: MP95382

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@926159 15:42 09-Sep-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-080916-A | | |
| Lab Sample ID: | JC25469-1 | Date Sampled: | 08/09/16 |
| Matrix: | AQ - Water | Date Received: | 08/09/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | 4.2 | 4.0 | mg/l | 1 | 08/11/16 11:00 | AT | SM2540 D-11 |
| pH [a] | 6.93 | | su | 1 | 08/09/16 16:33 | OB | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@926159 15:42 09-Sep-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-080916-A | | |
| Lab Sample ID: | JC25469-1A | Date Sampled: | 08/09/16 |
| Matrix: | AQ - Water | Date Received: | 08/09/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 5.0 | 5.0 | mg/l | 1 | 08/10/16 19:16 | LS | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@926159 15:42 09-Sep-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-080916-B | | |
| Lab Sample ID: | JC25469-2 | Date Sampled: | 08/09/16 |
| Matrix: | AQ - Water | Date Received: | 08/09/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | N256771.D | 1 | 08/10/16 | BM | n/a | n/a | VN10847 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 3.7 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.5 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.21 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 23.1 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.33 | 1.0 | 0.15 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.37 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 62.8 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 2.5 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.81 | 1.0 | 0.16 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@926159 15:42 09-Sep-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-080916-B | | |
| Lab Sample ID: | JC25469-2 | Date Sampled: | 08/09/16 |
| Matrix: | AQ - Water | Date Received: | 08/09/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 62.2 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 95% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 97% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 100% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 100% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@926159 15:42 09-Sep-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-080916-B | | |
| Lab Sample ID: | JC25469-2 | Date Sampled: | 08/09/16 |
| Matrix: | AQ - Water | Date Received: | 08/09/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 08/11/16 11:30 | TT | EPA 1664A |

RL = Reporting Limit

## Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized based field obersvations and constructability review. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2016-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2015-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA 6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to address the elimination of a drop structure, the elmination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead. | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | To be submitted to Parties as Attachment to Declaration 005. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | To be submitted to Parties as Attachment to Declaration 005. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | To be submitted to Parties as Attachment to Declaration 004. |

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-30** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2016-02-03** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. |
| **DC 2016-05-31** | This DCB documents the vault sketch Drawing C-310 (Rev 5, 5/31/16) | Submitted to Contractor only as clarification or response to RFI. |

**SA-6 North/South Field Change Log - Month Ending September 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. |
| **DC 2016-7-12** | DC 2016-7-12 clarifies the limit of GCL deployment and the location of the sand bentonite plug in the SA-6 North cap. | Included as an attachment to July 2016 Monthly Progress Report. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**11/14/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

November 14, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-10**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from October 1 – October 31, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: October 2016 SA-6/7 Combined Monthly Progress Report No. 2016-10

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP (electroni copy)

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-10

**Project SA-6 & 7 Remediation**

# October 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 10/11/16 | Special Master All Parties Conference Call | n/a |
| 10/12/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-09 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/13/16 | New Source of Horizon A Topsoil<br>Study Area 6 (SA-6)<br>Jersey City, New Jersey | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/17/16 | SA-5-7 Financial Assurances (Arnold & Porter correspondence) | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 10/19/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Passaic Valley Sewerage Commission |
| 10/20/16 | ICO v. Honeywell<br>Response to Plaintiffs' Comments of August 29, 2016 Regarding the SA-7 Sediment Remedy Long-Term Monitoring Program – Year 2 Report | Honorable Robert G. Torricelli<br>Office of the Special Master |

## SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 10/9/16 | 10/16/16 | 10/23/16 | 10/30/16 |
| **Construction Management (AMEC)** | 9 | 8 | 8 | 9 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 24 | 25 | 24 | 17 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 0 |

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 10/9/16 | 10/16/16 | 10/23/16 | 10/30/16 |
| **E&V Dirt Works** | 0 | 0 | 0 | 0 |
| **Langan** | 0 | 0 | 0 | 0 |
| **ERFS** | 1 | 1 | 0 | 1 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 1 | 0 | 0 |
| **Cornerstone** | 2 | 1 | 1 | 2 |
| **TOTAL STAFF** | **42** | **42** | **39** | **35** |

### 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Conducted perimeter air monitoring activities using hand-held portable devices for nuisance dust.
- Continued installation of CGWES components within the SA-6 North Open Space Areas to include installation of spare conduit pipe for future piezometer instrumentation on the north side of the SA-6 North Open Space Area.
- Completed installation of the CGWES dual wall force main pipe on the north side of the SA-6 North Open Space Area to approximately 8 feet outside of the GWTP.
- ERFS completed injections in Treatment Area 10-1 in accordance with NJDEP-DGW permit.
- Continued post-injection groundwater sampling and monitoring in Treatment Area 10-1 in accordance with the NJDEP – Discharge to Groundwater Permit.
- An inspector from the Hudson Essex Passaic Soil Conservation District was on site on October 25, 2016 for an inspection of the current erosion and sediment controls. There were no findings and all items were in compliance.
- Conducted S-3 Mass Removal Injection Event No. 32 in injection well 088-IW-01.
- Conducted S-3 Mass Removal Injection Event No. 33 in injection well 088-IW-02.
- Collected October PVSC compliance sample from the Construction Water Treatment Plant (CWTP).
- Obtained NJDOT Permit for Restoration of Sidewalks within work limits along Rt. 440.

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on October 11, 2016.

- Reviewed submittals from the mechanical contractor, Brownfield Science & Technology, Inc. (BTSI), associated with piping installation from the CGWTS force mains to the neutralization tank.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 10/9/16 | 10/16/16 | 10/23/16 | 10/30/16 |
| Avg. Gallons Treated & Discharged (per day) | 78,882 | 77,380 | 78,011 | 78,861 |
| Average Flow (gpm) for Operating Period | 56 | 55 | 56 | 56 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 23 |
| GWTP Influent Tanks (gal.) | 5,784 | 4,266 | 3,669 | 2,431 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Completed routine dewatering activities and associated discharge to the construction water treatment facility.
- Initiated cleaning and demobilization of temporary Construction Water Treatment Plant.
- Completed cutting of temporary sheetpile along the SA-6 South Kellogg Street Jug handle.
- Completed placement of historic fill cap to include geotextile and 6-inches of stone in the SA-6 South Development Area.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 0 | 0 | 0 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Backfill in Progress** | 3/8” stone Historic Fill Cap – SA-6 South Development Area |

### 3. BACKFILL MATERIALS USED (TONS)

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 10/9/16 | 10/16/16 | 10/23/16 | 10/30/16 |
| Natures Choice Topsoil | 0 | 0 | 0 | 994 |
| EME Topsoil | 0 | 0 | 0 | 294.53 |
| Tilcon Mount Hope I-8 | 203 | 256 | 203 | 868 |
| Natures Choice Horizon C | 0 | 0 | 0 | 0 |
| Tilcon 3/8" Stone | 53 | 51 | 52 | 0 |
| Tilcon Mt. Hope 1.5" | 316 | 153 | 154 | 105 |
| Tilcon Mt. Hope #57 | 0 | 676 | 356 | 0 |
| Weldon Screenings | 0 | 0 | 0 | 290.32 |

- A total of 37 loads totaling approximately 834 cubic yards on crushed concrete were relocated from the SA-6 North former JCIA area to the south of the former JCDPW "H" building. This concrete stockpile will be sampled and managed in accordance with the approved materials management plan by the non-chromium contractor.

## D. SURCHARGE OPERATIONS

- All surcharging activities are completed.

## E. SHEET PILE OPERATIONS

- All sheet pile operations are complete.

## F. CAPPING OPERATIONS

- Continued importing and placing Horizon A soils on SA-6 South Open Space Area.
- Completed construction of the SA-6 South Temporary Access Road in utility corridor B.
- Completed installation of toe drain on the north site of the SA-6 South Open Space Area.
- Performed hydro-seeding of SA-6 South Open Space Area to include placement of erosion control matting. Approximately 5 acres were hydro-seeded.
- Initiated installation of toe drain on the south side slope of the SA-6 North Open Space Area.
- Completed placement structural fill to included compaction on the SA-6 North Open Space Area.
- Initiated importing and placing Horizon A soils on SA-6 North Open Space Area.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 08/04/2016 | Not Specified | Not Specified | 9/12/16 |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete importing and placement of Horizon A Topsoil on the SA-6 South Open Space Area.
- Complete hydro-seeding of SA-6 South Open Space Area.
- Initiate installation of the Contingent Groundwater Extraction System Components within the GWTP including the mechanical piping and conduit.
- Complete importing and placement of Horizon A Topsoil on the SA-6 North Open Space Area.
- Complete hydro-seeding of SA-6 North Open Space Area.
- Complete storm-water management activities associated with construction.
- Complete cleaning and demobilization of temporary CWTS.
- Complete NJDOT sidewalk restoration and removal of Highway Occupancy Permit traffic control devices.
- Complete SWPPP inspections associated with construction.
- Conduct S-3 Mass Removal Injection Event No. 34 in well 088-IW-03.
- Initiate periodic groundwater level monitoring in accordance with Draft Long-Term Monitoring Plan at SA-6 South and perimeter pools.
- Demobilize Entact office trailers and equipment.

## ATTACHMENTS:

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update (SA-6 Cap Subgrade Progress Maps)
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log


## Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **Fri 1/4/08** |
| **2** | **Remedial Action Work Plan** | **33 days** | **Fri 1/4/08** |
| **5** | **Remedial Action Design** | **1522 days** | **Wed 2/20/08** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 949 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 146 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **26** | **Remedial Action Work Plan** | **187 days** | **Fri 7/11/08** |
| **32** | **Remedial Action Design** | **1161 days** | **Mon 2/2/09** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | Fri 11/15/13 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | Tue 4/8/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Tue 6/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | Mon 6/16/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | Mon 10/6/14 |
| **63** | **Barrier Wall Install** | **569 days** | **Mon 8/12/13** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | Mon 3/9/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | Mon 8/12/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| 64b | SA 6S Excavation | 295 days | Tue 10/22/13 |
| **65** | **Backfill** | **558 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 283 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 384 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | Thu 3/24/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **234 days** | **Tue 9/1/15** |
| 67a | Restoration | 234 days | Tue 9/1/15 |
| **68** | **Demobilization** | **22 days** | **Fri 7/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | 1 day | Fri 3/1/13 |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | 1 day | Fri 3/1/13 |
| **69** | **SA-6 North Project Closeout** | **311 days** | **Thu 10/1/15** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **Thu 10/1/15** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **Wed 10/1/08** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **Thu 6/5/08** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/2/2016

Task | Milestone ◆ | Summary | Critical

Note: Current field implementation schedule shows restoration in November 2016.

## Attachment 2: Site Photographs




**Site Photograph 1:** Dust suppression activities SA-6S Open Space Area.




**Site Photograph 2:** Grading imported Horizon C clean fill on SA-6N Open Space Area.




**Site Photograph 3:** Grading imported stone in the SA-6S Restoration Areas.



**Site Photograph 4:** Hydroseeding along the eastern portion SA-6S Open Space Area.



**Site Photograph 5:** Installing Erosion Control Matting on the north slope of the SA-6S Open Space Area.



**Site Photograph 6:** Placement of Contingent Groundwater System cleanout station.




**Site Photograph 7:** Toe drain construction north side of SA-6S Open Space Area.





**Site Photograph 8:** View of SA-6S Kellogg St Properties Final Restoration.

## Attachment 3: Excavation and Backfill Progression Chart

# Jersey City & Kellogg Street Properties Remedies Progress as of November 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-10
Attachment 3: Excavation and Backfill (Progression Chart)



## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)


| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 07/07/16 | 7:30 | 12:00 | 4:30 | 43,596.37 | 43,642.93 | 46,560 | 43,642,480 | PVSC Compliance Sample Collected |
| 07/15/16 | 10:00 | 14:00 | 4:00 | 43,642.93 | 43,692.98 | 50,050 | 43,692,530 | |
| 07/26/16 | 9:00 | 14:00 | 5:00 | 43,692.98 | 43,794.27 | 101,290 | 43,793,820 | |
| 07/27/16 | 7:00 | 15:00 | 8:00 | 43,794.27 | 43,826.36 | 32,090 | 43,825,910 | |
| 07/28/16 | 9:00 | 15:00 | 6:00 | 43,826.36 | 43,860.98 | 34,620 | 43,860,530 | |
| 08/01/16 | 9:00 | 15:00 | 6:00 | 43,860.98 | 43,896.38 | 35,400 | 43,895,930 | PVSC Compliance Sample Collected |
| 08/11/16 | 9:00 | 16:00 | 7:00 | 43,896.38 | 43,958.93 | 62,550 | 43,958,480 | |
| 08/12/16 | 9:30 | 13:45 | 4:15 | 43,958.93 | 43,998.63 | 39,700 | 43,998,180 | |
| 08/19/16 | 8:00 | 13:30 | 5:30 | 43,998.63 | 44,062.58 | 63,950 | 44,062,130 | |
| 09/08/16 | 7:00 | 13:00 | 6:00 | 44,062.58 | 44,120.80 | 58,220 | 44,120,350 | PVSC Compliance Sample Collected |
| 10/05/16 | 8:00 | 11:00 | 3:00 | 44,120.80 | 44,158.46 | 37,660 | 44,158 | PVSC Compliance Sample Collected |
| 11/01/16 | 8:00 | 10:00 | 2:00 | 44,158.46 | 44,204.91 | 46,450 | 44,205 | Final reading; system disassembled 11/1/16 |

Notes: Previous information is truncated. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data

(not included in this reporting period)

## Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-5 | FS-6 | FS-7 | FS-13 |
| Date | | | | | | | | | | | | | |
| 11/13/2015 | 1.8 | 4.4 | 4.9 | 3.5 | 3.9 | 6.4 | 1.5 | 1.5 | 5.8 | 4.6 | 4.6 | 3.7 | 3.4 |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | 4.5 | 5.0 | 3.8 | 3.5 |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | 3.5 | 3.6 | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | 5.2 | | | 4.6 |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | 6.0 | | | 5.6 |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | 6.5 | | | 6.2 |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | 6.0 | | | 5.7 |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | 5.6 | | | 5.0 |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | 2.7 | | | 3.6 |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | 2.1 | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | 1.8 | | | |
| 5/2/2016 | 3.0 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | 1.6 | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | |
| 6/1/2016 | 2.7 | 5.2 | 5.5 | 2.5 | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/16/2016 | 2.7 | 5.2 | 5.6 | | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/28/2016 | 3.2 | 5.2 | 5.6 | 2.4 | 3.2 | 2.3 | 3.1 | 3.1 | 1.8 | | | | |
| 7/15/2016 | 3.2 | 5.3 | 5.6 | 2.5 | 3.3 | 2.4 | 3.1 | 3.2 | 1.8 | | | | |
| 7/27/2016 | 3.1 | 5.3 | 5.4 | 2.6 | 3.2 | 2.3 | 3.1 | 3.2 | 2.0 | | | | |
| 8/12/2016 | 3.4 | 5.3 | 5.6 | 3.2 | 2.6 | 2.8 | 3.3 | 3.4 | 2.5 | | | | |
| 8/29/2016 | 3.5 | 5.1 | 5.4 | 3.1 | 2.6 | 2.8 | 3.4 | 3.4 | 2.7 | | | | |
| 9/9/2016 | 3.5 | 5.0 | 5.4 | 3.2 | 3.4 | 2.6 | 3.4 | 3.5 | 2.3 | | | | |
| 9/29/2016 | 3.5 | 4.8 | 5.2 | 3.2 | 3.3 | 3.1 | 3.5 | 3.5 | 1.7 | | | | |
| 10/17/2016 | 3.6 | 4.7 | 5.2 | 3.3 | 3.5 | 2.3 | 3.6 | 3.5 | 2.2 | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

## Attachment 8: Groundwater Quality Data

**Table 1: Summary of Groundwater Quality Data**
*(Attachment 8: Groundwater Quality Data)*

Honeywell

**Table 1**
Summary of Groundwater Quality Data from GWET Wells

| Parameter | 30-Jun-16 | | | 19-Oct-16 | | |
|---|---|---|---|---|---|---|
| | **PW-1** (ug/L) | **PW-3** (ug/L) | **115-MW-215BR** (ug/L) | **PW-1** (ug/L) | **PW-3** (ug/L) | **115-MW-215BR** (ug/L) |
| Benzene | 2.7 | 27.3 | ND | 2.5 | 17.4 | ND |
| Carbon Tetrachloride | 4.1 | 14.6 | 2.1 | 4.6 | 8.2 | 3.0 |
| Chloroform | 24.2 | 111 | 0.25 | 21.9 | 77.3 | 0.29 |
| 1,1-Dichloroethene | 0.55 | 0.34 | ND | 0.49 | ND | ND |
| cis-1,2-Dichloroethene | 125 | 59.9 | ND | 100 | 46.8 | ND |
| trans-1,2-Dichloroethene | 3.5 | 0.44 | ND | 3.4 | 0.32 | ND |
| Toluene | ND | ND | ND | ND | ND | ND |
| Trichloroethene | 86.8 | 347 | ND | 80.7 | 205 | ND |
| 1,1-Dichloroethane | 0.65 | 0.25 | ND | 0.65 | ND | ND |
| Methylene chloride | 0.75 | 3.7 | ND | 0.58 | 2.2 | ND |
| Vinyl chloride | 17.0 | 15.2 | ND | 13.2 | 6.9 | ND |
| 1,2-Dichlorobenzene | 0.54 | 0.19 | ND | 0.52 | ND | ND |
| Chlorobenzene | 0.35 | ND | ND | 0.33 | ND | ND |
| Ethylbenzene | ND | 0.28 | ND | ND | ND | ND |
| Xylenes (total) | ND | 0.44 | ND | ND | ND | ND |
| Bromodichloromethane | ND | ND | ND | ND | ND | ND |
| Hexavalent Chromium | 31,300 | 68,800 | 14,400 | 31,000 | 56,300 | 19,200 |
| Total Chromium | 31,700 | 37,100 | 12,900 | 30,200 | 58,500 | 17,800 |

NA = Not Available for Testing due to COPR excavation activities.
NT = Not Tested
ND = Not detected above reporting limit.

**Table 2: Third Quarter 2016**
*(Attachment 8: Groundwater Quality Data)*


**TABLE 2**
**Third Quarter 2016**


Honeywell

| Wells<br>Date: September 27, 2016 | Top of Casing Elevation (ft. msl) | Depth to Water (ft., btoc) | Groundwater Elevation (ft., msl) | Comments<br>*GW Elevations are not corrected for tidal influence* |
|---|---|---|---|---|
| 087-MW-25D* | NA | 8.71 | NA | casing extended |
| 087-MW-25T* | NA | 8.73 | NA | casing extended |
| 087-MW-35 | 18.29 | NA | NA | Well abandoned |
| 087-OBS-1D | 15.13 | 12.07 | 3.06 | |
| 087-OBS-1L | 15.27 | 12.65 | 2.62 | |
| 087-OBS-1T | 15.23 | 13.65 | 1.58 | |
| 087-PW-2 | 13.02 | 10.93 | 2.09 | Inactive, use as obs well only |
| 087-PW-3* | 13.00 | 17.08 | -4.08 | |
| 087-OBS-7* | 13.00 | 13.66 | -0.66 | |
| 087-MW-08 | 12.98 | 11.46 | 1.52 | |
| 087-OBS-3L | 12.88 | 11.39 | 1.49 | |
| 087-MW-13 | 12.93 | 11.47 | 1.46 | |
| 087-OBS-5D | 12.72 | 11.95 | 0.77 | |
| 087-OBS-5T | 12.62 | 12.30 | 0.32 | |
| 087-PW-1 | 12.66 | 39.75 | -27.09 | |
| 087-MW-34 | 12.73 | 12.88 | -0.15 | |
| 087-OBS-2D | 12.68 | 14.07 | -1.39 | |
| SA6-MW-AA1D | 19.36 | 17.56 | 1.80 | |
| SA6-MW-AA1T | 15.31 | 13.78 | 1.53 | |
| SA6-MW-5BR-1 | 17.06 | 14.59 | 2.47 | |
| 087-OBS-4T | 11.60 | 10.52 | 1.08 | |
| 087-MW-O29D | 10.32 | 8.67 | 1.65 | |
| 087-MW-O29T | 9.98 | NA | N/A | Well abandoned |
| 115-MW-203BR* | 8.70 | 7.13 | N/A | casing extended |
| 073-MW-1 | 25.25 | 25.70 | -0.45 | retro-fitted as top-of-rock well |
| 073-MW-10BR-1 | 6.67 | NA | NA | Flute does not purge |
| 115-MW-215BR | 8.82 | 11.71 | -2.89 | |

* Reference point elevation to be confirmed.


**Graphs: Trichloroethene/ Chloroform/ Hexavalent Chromium/ Carbon Tetrachloride in GWET Wells**
*(Attachment 8: Groundwater Quality Data)*





Note:

Notes:
Well 115-MW-203BR was replaced with 115-MW-215BR on 3/3/14.
Well 087-PW-2 was replaced with well 087-PW-3 on 12/2215.




Notes:
Well 115-MW-203BR was replaced with 115-MW-215BR on 3/3/14.
Well 087-PW-2 was replaced with well 087-PW-3 on 12/2215.


## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

## Attachment 10: Sheet Pile Update

(not included in this reporting period)

**Attachment 11: Capping Update** (SA-6 Cap Subgrade Progress Maps)




LEGEND

- HORIZON C SOIL PLACED
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL
- TOPSOIL PLACED

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP COVER SOILS PROGRESS MAP
11/04/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LEGEND

TOPSOIL PLACED

SCB WALL

HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
11/04/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 12: Weekly SWPPP Reports

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 7, 2016**

**Type of Inspection:** ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 1 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/07/16

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, October 07, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Filter fabric in the stormwater catch basins at the western end of Kellogg Street has become blinded. |
| 2 | IA2Q4A1AL8 | Garbage and debris has accumulated on the grassy area by the Kellogg Street jughandle |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 10/07/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Replace the catch basin filter fabric as required. | 10/12/16 RAD |
| 2 | Pick up and dispose of accumulated garbage along the Kellogg Street jughandle and along Kellogg Street. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 10/13/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 14, 2016**

**Type of Inspection:** ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 1 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | X | | | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | X | | | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 4 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/14/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, October 14, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Mud and other sediment is present on the western end of Kellogg Street by the truck entrance gate. |
| 2 | IA2Q4A1AL8 | Garbage and debris is present on the grass by the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | Garbage and debris is present in the SA-6 North, Rt. 440 pedestrian walkway. |
| 4 | IA2Q4A1AL8 | The silt fence surrounding the Novartis stockpile area on Study Area 7 requires maintenance or replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 10/14/16

Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Clean up and remove mud and sediment from the road surface and from the strip along the perimeter fence jersey barriers. | 10/20/16 RAD |
| 2 | Pick up and dispose of the accumulated garbage and debris. | |
| 3 | Pick up and dispose of the accumulated garbage and debris. | |
| 4 | Repair or replace the erosion control measures as required. | in progress |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 10/20/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 21, 2016**

**Type of Inspection:** ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☐ Fair ☐ Cloudy ☐ Other _____
☒ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 1 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | | X | | 2 |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | | X | | 3 |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/21/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, October 21, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Garbage and debris is present on the grass by the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | The silt fence surrounding the Novartis stockpile area on Study Area 7 requires maintenance or replacement. |
| 3 | IA2Q4A1AL8 | Sediment is present on the Study Area 7 north roadway where the berm material was recently removed |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 10/21/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Pick up and dispose of the accumulated garbage and debris. | 10/27/16 (12:41) |
| 2 | Repair or replace the erosion control measures as required. | |
| 3 | Clean the paved haul road on SA-7 as required. | ↓ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 10/27/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Date of Inspection: October 28, 2016**

**Type of Inspection:** ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☐ Fair ☐ Cloudy ☐ Other _____
☒ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 2 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 3 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 10/28/16

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, October 28, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710
PERMIT CLOSED

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen material has become detached from the perimeter fence on SA-6 North by the Rt. 440 pedestrican walkway. |
| 2 | IA2Q4A1AL8 | The silt fence surrounding the Novartis stockpile area on Study Area 7 requires maintenance or replacement. |
| 3 | IA2Q4A1AL8 | The filter fabric in the stormwater catch basin at the Northeast corner of SA-7 is blinded with sediment and requires replacement. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 10/28/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen fabric to the perimeter fence as required. | 11/3/16 RAD |
| 2 | Repair or replace the erosion control measures as required. | |
| 3 | Replace the filter fabric in the catch basin. | 1/ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 11/03/16

## Attachment 13: GWTP Update (525/575 Route 440 GWTP PVSC Discharge Monitoring Report - submitted September 2016)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

October 19, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the September 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 9 | 01 | 16 | 9 | 30 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 77,623 | 81,075 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.66 | 0.69 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.015 | <0.015 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.0 | <5.0 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1516 | 0.1516 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

**PRETREATMENT MONITORING REPORT**

Certification of Non-Use if applicable (use additional sheets):

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used:

All analytes are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3.

SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler.

All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris VP
Signature of Principal
Executive or Authorized Agent

John J. Morris

Remediation Portfolio Director
Type Name and Title

Oct 18, 2016
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 101 Columbia Rd, (Attn: Maria Kaouris (SOL-4)) Morristown, NJ 07962

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 9 | 01 | 16 | 9 | 30 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,328,702 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 73,378,558 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 9/13/2016 | <5.0 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris VP | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE Oct 18, 2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | MONTH: September, 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 9/1/2016 | Angel Trujillo | 71049856 | 71125968 | 76,112 | 0.076112 | 8.29 | 1.020 | | | | | | | | | 0.65 |
| 9/2/2016 | Angel Trujillo | 71125968 | 71205920 | 79,952 | 0.079952 | 7.01 | 1.020 | | | | | | | | | 0.68 |
| 9/3/2016 | Angel Trujillo | 71205920 | 71285772 | 79,852 | 0.079852 | 7.02 | 1.020 | | | | | | | | | 0.68 |
| 9/4/2016 | Angel Trujillo | 71285772 | 71363511 | 77,739 | 0.077739 | 7.10 | 1.020 | | | | | | | | | 0.66 |
| 9/5/2016 | Angel Trujillo | 71363511 | 71441250 | 77,739 | 0.077739 | 7.09 | 1.020 | | | | | | | | | 0.66 |
| 9/6/2016 | Angel Trujillo | 71441250 | 71515976 | 74,726 | 0.074726 | 7.01 | 1.020 | | | | | | | | | 0.64 |
| 9/7/2016 | Angel Trujillo | 71515976 | 71592442 | 76,466 | 0.076466 | 7.16 | 1.020 | | | | | | | | | 0.65 |
| 9/8/2016 | Angel Trujillo | 71592442 | 71669950 | 77,508 | 0.077508 | 7.16 | 1.020 | | | | | | | | | 0.66 |
| 9/9/2016 | Angel Trujillo | 71669950 | 71748819 | 78,869 | 0.078869 | 6.95 | 1.020 | | | | | | | | | 0.67 |
| 9/10/2016 | Angel Trujillo | 71748819 | 71828328 | 79,509 | 0.079509 | 7.23 | 1.020 | | | | | | | | | 0.68 |
| 9/11/2016 | Angel Trujillo | 71828328 | 71902394 | 74,066 | 0.074066 | 7.10 | 1.020 | | | | | | | | | 0.63 |
| 9/12/2016 | Angel Trujillo | 71902394 | 71976460 | 74,066 | 0.074066 | 7.11 | 1.020 | | | | | | | | | 0.63 |
| 9/13/2016 | Angel Trujillo | 71976460 | 72056256 | 79,796 | 0.079796 | 6.83 | 1.020 | <5.0 | <5.0 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | 0.68 |
| 9/14/2016 | Angel Trujillo | 72056256 | 72132192 | 75,936 | 0.075936 | 7.09 | 1.020 | | | | | | | | | 0.65 |
| 9/15/2016 | Angel Trujillo | 72132192 | 72210400 | 78,208 | 0.078208 | 7.80 | 1.020 | | | | | | | | | 0.67 |
| 9/16/2016 | Angel Trujillo | 72210400 | 72288135 | 77,735 | 0.077735 | 7.05 | 1.020 | | | | | | | | | 0.66 |
| 9/17/2016 | Angel Trujillo | 72288135 | 72369210 | 81,075 | 0.081075 | 7.13 | 1.020 | | | | | | | | | 0.69 |
| 9/18/2016 | Angel Trujillo | 72369210 | 72444517 | 75,307 | 0.075307 | 7.20 | 1.020 | | | | | | | | | 0.64 |
| 9/19/2016 | Angel Trujillo | 72444517 | 72519824 | 75,307 | 0.075307 | 7.30 | 1.020 | | | | | | | | | 0.64 |
| 9/20/2016 | Angel Trujillo | 72519824 | 72596090 | 76,266 | 0.076266 | 7.28 | 1.020 | | | | | | | | | 0.65 |
| 9/21/2016 | Angel Trujillo | 72596090 | 72672621 | 76,531 | 0.076531 | 7.14 | 1.020 | | | | | | | | | 0.65 |
| 9/22/2016 | Angel Trujillo | 72672621 | 72753213 | 80,592 | 0.080592 | 7.22 | 1.020 | | | | | | | | | 0.69 |
| 9/23/2016 | Angel Trujillo | 72753213 | 72829818 | 76,605 | 0.076605 | 7.19 | 1.020 | | | | | | | | | 0.65 |
| 9/24/2016 | Angel Trujillo | 72829818 | 72908564 | 78,746 | 0.078746 | 7.24 | 1.020 | | | | | | | | | 0.67 |
| 9/25/2016 | Angel Trujillo | 72908564 | 72986986 | 78,422 | 0.078422 | 7.30 | 1.020 | | | | | | | | | 0.67 |
| 9/26/2016 | Angel Trujillo | 72986986 | 73065408 | 78,422 | 0.078422 | 7.21 | 1.020 | | | | | | | | | 0.67 |
| 9/27/2016 | Angel Trujillo | 73065408 | 73144654 | 79,246 | 0.0792 | 7.33 | 1.020 | | | | | | | | | 0.67 |
| 9/28/2016 | Angel Trujillo | 73144654 | 73221560 | 76,906 | 0.076906 | 7.35 | 1.020 | | | | | | | | | 0.65 |
| 9/29/2016 | Angel Trujillo | 73221560 | 73300054 | 78,494 | 0.078494 | 7.15 | 1.020 | | | | | | | | | 0.67 |
| 9/30/2016 | Angel Trujillo | 73300054 | 73378558 | 78,504 | 0.078504 | 7.18 | 1.020 | | | | | | | | | 0.67 |
| | | | | | | | | | | | | | | | | |
| TOTAL | | | | 2,328,702 | 2.328702 | | | <5.0 | <5.0 | | <0.010 | <0.015 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 81,075 | | | | | | | | | | | High: | 0.69 |
| | | | Average: | 77,623 | | | | | | | | | | | Average: | 0.66 |

WW

E

JC 27484

| Accutest Labs | Honeywell | Chain Of Custody / Analysis Request | AESI Ref: | 42626.48208 |
|---|---|---|---|---|
| 2236 ROUTE 130<br>Dayton, NJ 8810<br>732-329-0200 | Privileged & Confidential | Site Name: Hudson County / Phase: CS | COC# | 087-WW-091316 |
| Sampling Co.: MACTEC | EDD To: | Location of Site: Jersey City, NJ / Sampling Program: 087: JCIA | Lab Proj # (SDG): | |
| Client Contact: (name, co., address) | Sampler: Frank Schroyer | | Lab ID | ACTD |
| Helen Fahy P: (973) 455-2989 E: helen.fahy@honeywell.com | PO # | | Site ID | HudsonCo |
| Honeywell International | Analysis Turnaround Time (TAT): 3 | Preservative: 3 3 3 1 2 2 0 0 2 | Lab Job # | HWINJM32815 |
| 115 Tabor Road, Morris Plains, NJ 07950 | Consultant: CH2M | | Authorized User: | Honeywell |
| Preliminary Data To | | | | |
| Sample Receipt Acknowledgement To | | | Text & Excel File Drive | Excel & Text File Order |
| Hard Copy To: Helen Fahy (Honeywell) | Full Report TAT: 28 Days | | | |
| Invoice To: Helen Fahy (Honeywell) | | | | |

Copyright AESI: Version 8.0 Unauthorized use strictly prohibited.

| | Sample Identification | | | | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Composite/Grab | Field Filtered Sample? | Total CHROMIUM (EPA 200.7) | EPA 200.7 Cd, Pb, Zn, Ni | E245.1 Hg | E405.1 Biological Oxygen Demand | EPA 624 TVOC | E1664A SGT-HEM | EPA 150.1 PH | E160.2 Total Suspended Solids | EPA V624-SL VOCs; see attached special list | | | | | | | Sampling Method (code) | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | | | | | | | Units | | | | | | | | | | | | | | | | | | |
| 1 | 087-WW | | | 087-WWE-091316-A | 9/13/2016 | 14:20 | WW | WATER | REG | 5 | comp | N | X | X | X | X | | | X | X | | 1 | | | | | | | |
| 2 | 087-WW | | | 087-WWE-091316-B | 9/13/2016 | 14:25 | WW | WATER | REG | 5 | grab | N | | | | | X | X | | | | 2 | | | | | | | A29 |
| 3 | 087-WW | | | 087-WWI-091316 | 9/13/2016 | 14:30 | WW | WATER | REG | 3 | grab | N | | | | | | | | | X | 3 | | | | | | | G56 |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | L29 |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | V1125 |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Relinquished by: Frank Schroyer | 6.83 5.4 @ 9.5°C / 9/13/16 Date/Time 1515 | Company: AMEC Foster Wheeler | Received by | Company | | Condition | Custody Seals Intact |
| | | | | 9-13-16 Date/Time 1515 | | Cooler Temp. | |
| Relinquished by | 9-13-16 Date/Time 1650 | Company | Received by | Company: SAS | | Condition | Custody Seals Intact |
| | | | | Date/Time: 9-13-16 1650 | | Cooler Temp. | |

Preservatives: (Other; Specify):

0 (none); 1 (4 Deg C); 2 (HCl pH<2); 3 (HNO3 pH<2); 4 (H2SO4 pH<2); 5 (NaOH pH>12); 6 (NaOH, Zn Acetate); 7 (H2SO4 (pH<2), 4 Deg C)); 8 (HCl pH<2); 9 (HCl 4 Deg C); 10 (HNO3 (pH<2), 4Deg C); 11 (4C NaOH (pH>12) & Ascorbic Acid); 12 (4C H2SO4 (pH<2) & Na2S2O3); 13 (Zn Acetate); sp (special instructions)

INITIAL ASESSMENT BBM

LABEL VERIFICATION

049

SGS Accutest LabLink@929339 14:20 05-Oct-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091316-A | | |
| Lab Sample ID: | JC27484-1 | Date Sampled: | 09/13/16 |
| Matrix: | AQ - Water | Date Received: | 09/13/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



Total Metals Analysis

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1020 | 10 | ug/l | 1 | 09/16/16 | 09/17/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Copper | < 10 | 10 | ug/l | 1 | 09/16/16 | 09/17/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Lead [a] | < 15 | 15 | ug/l | 5 | 09/16/16 | 09/17/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 09/14/16 | 09/14/16 | JPM | EPA 245.1 [1] | EPA 245.1 [3] |
| Nickel | < 10 | 10 | ug/l | 1 | 09/16/16 | 09/17/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |
| Zinc | < 20 | 20 | ug/l | 1 | 09/16/16 | 09/17/16 | GT | EPA 200.7 [2] | EPA 200.7 [4] |

(1) Instrument QC Batch: MA40293
(2) Instrument QC Batch: MA40321
(3) Prep QC Batch: MP95994
(4) Prep QC Batch: MP96034

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@929339 14:20 05-Oct-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091316-A | | |
| Lab Sample ID: | JC27484-1 | Date Sampled: | 09/13/16 |
| Matrix: | AQ - Water | Date Received: | 09/13/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.1
4

## General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 09/14/16 11:15 | AT | SM2540 D-11 |
| pH [a] | 6.82 | | su | 1 | 09/13/16 17:46 | HFM | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@929339 14:20 05-Oct-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091316-A | | |
| Lab Sample ID: | JC27484-1A | Date Sampled: | 09/13/16 |
| Matrix: | AQ - Water | Date Received: | 09/13/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | < 5.0 | 5.0 | mg/l | 1 | 09/14/16 17:02 | DM | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@929339 14:20 05-Oct-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091316-B | | |
| Lab Sample ID: | JC27484-2 | Date Sampled: | 09/13/16 |
| Matrix: | AQ - Water | Date Received: | 09/13/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | N257494.D | 1 | 09/15/16 | SC | n/a | n/a | VN10876 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 3.7 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.7 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | ND | 1.0 | 0.12 | ug/l | |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 23.6 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.43 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 60.6 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.6 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.81 | 1.0 | 0.16 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@929339 14:20 05-Oct-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091316-B | | |
| Lab Sample ID: | JC27484-2 | Date Sampled: | 09/13/16 |
| Matrix: | AQ - Water | Date Received: | 09/13/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

4.3
4

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene [b] | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 55.2 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 102% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 100% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 97% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 103% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.
(b) This compound in BS is outside in house QC limits bias high.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@929339 14:20 05-Oct-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-091316-B | | |
| Lab Sample ID: | JC27484-2 | Date Sampled: | 09/13/16 |
| Matrix: | AQ - Water | Date Received: | 09/13/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.0 | 5.0 | mg/l | 1 | 09/14/16 17:20 | LS | EPA 1664A |

RL = Reporting Limit

## Attachment 14: SA-6 North & South Design Change Tracking Log

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentaion Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-8-14** | The area indicated on sheets S-201 to S-203 from Station 0+00 to 17+80 will be sealed with a cement bentonite grout in lieu of hydraulic sealant. This area will include a grouted angle. | Contingency to Expand Use of Grouted Joint Called out in 100% Design. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2013-9-12** | Hydraulic barrier alignment for SA-6 South between 21+00 and 22+00 to be straightened. Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall. | Minor alignment adjustment now that Boatyard Property transaction to Bayfront completed. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2013-12-12** | The proposed bottom of excavation elevations may be deepened as required to expose Post-Excavation Samples as reported on the revised PDI summary tables which were submitted to Parties in HON/Amec Response to Comments dated 02/06/14. | In addition to the periodic notice of excavation complete emails to the Parties, Honeywell submitted the following documents that further defined excavation extents, updated PDI Tables (converted to elevations), Colorized Area Excavation Depth Drawing, and procedures to certify those extents:<br>1) 2/6/14 RTC letter on 1/28/14 & 1/31/14 Plaintiff comment letters Re: Cells 17 - 29.<br>2) 3/3/14 SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits.<br>3) 4/17/14 RTC letter on 4/11/14 Plaintiff comment letters Re: Cells 44 - 52.<br>4) 4/24/14 Revised SA-6 South Standard Operating Procedure, Confirmation of Excavation Limits. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-6-10 includes the french drain installation, as well as pump and access station manholes for SA-6 South. Some design details, including the electrical design, will be finalized based field obersvations and constructability review. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2016-6-10** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2015-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA 6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to address the elimination of a drop structure, the elmination of a flow meter, conduit sizing changes, and to clarify Entact's scope. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2013-8-14** | Modify surcharge pile toe of slope to reduce load on the bulkhead. | Submitted to all Parties on July 10, 2014. |
| **DC 2014-5-6** | Excavate down to 4 ft bgs (instead of 3 ft bgs) in a portion of the Site 163 excavation area. | 5/6/14 letter from Honeywell summarizing the ERFS SiteVision field testing program indicated that this portion of Site 163 would be excavated instead of treated in-situ. |
| **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-10-28** | Direction on the handling of petroleum soils under the cap. | Submitted to all Parties on November 19, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2014-12-01** | The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-01-22** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on 5/27/15. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on 5/27/15. |

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-03-04** | The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge. | Submitted to Parties on July 2, 2015. |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-04-30** | A concrete protuberence was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2015-06-18** | Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor).<br>In addition, it was identified that minor increases in the Bayfront final grades of up to 0.25 feet may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design. | Submitted to all Parties on June 18, 2015. |
| **DC 2015-05-29** | Details were revised in order to clarify cap termination beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner. | Submitted to Parties on August 27, 2015. |
| **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | To be submitted to Parties as Attachment to Declaration 005. |
| **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | To be submitted to Parties as Attachment to Declaration 005. |
| **DC 2015-06-18 (South)** | Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated September 2012. | Submitted to all Parties on 6/22/15. |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. |

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-06-15** | A Construction Control Grid for the SA-6 cap subgrade was developed in CAD as a Triangular Irregular Network for construction control and verification of compliance with cover thickness requirements in the Consent Decree and Open Space Design Standards. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-16** | The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-18** | The Design detail (Drawing C-121, Detail AN) assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | Submitted to Parties on August 27, 2015. |
| **DC 2015-10-06** | GCL is required to be installed over the SCB wall and Barrier Wall at the locations shown in the annotated PDF of C-121 (rev 4, 8/13/15). | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-07-22** | Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall. | Submitted to Parties on August 27, 2015. |
| **DC 2015-07-28** | Drawing 304, Detail CE and associated notes regarding the "Liner Anchor to Concrete Structure" have been modified. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-08-07** | AmecFW has conducted further review of the "Liner to Concrete Structure Detail" (Drawing C-304, Detail CE) with Entact/ESI, including field review, to improve constructability. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-07-30** | Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. AmecFW reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development. The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longe required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-20** | The most easterly utility corridor was eliminated from the Development Plan, allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall (revised Drawing S-201). Addendum: The top of the SCB wall will also be revised to reflect the elimination of the utility corridor (revised Drawing S-204). | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | To be submitted to Parties as Attachment to Declaration 004. |

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. |
| **DC 2015-12-21** | Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance withASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2015-11-30** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | To be submitted to Parties as Attachment to Declaration 003. |
| **DC 2016-02-03** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. |
| **DC 2016-05-31** | This DCB documents the vault sketch Drawing C-310 (Rev 5, 5/31/16) | Submitted to Contractor only as clarification or response to RFI. |

**SA-6 North/South Field Change Log - Month Ending October 2016**

| Changed Item Identifier | Description of Change | Comments |
|---|---|---|
| **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | To be submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. |
| **DC 2016-7-12** | DC 2016-7-12 clarifies the limit of GCL deployment and the location of the sand bentonite plug in the SA-6 North cap. | Included as an attachment to July 2016 Monthly Progress Report. |
| **DC 2016-10-21** | Amee Foster Wheeler has consulted with Dr. James Murphy of the Rutgers Cooperative Extension regarding seed mixes that are suitable for use at this time of year. Based on the Rutgers' recommendations either one of the two seed mixes noted below is considered acceptable.<br>Seed Mix 1:<br>• 80% tall fescue<br>• 20% perennial ryegrass<br>• seeded at 360 pounds per acre<br>Seed Mix 2:<br>• 70% ta ll fescue<br>• 10% Kentucky bluegrass<br>• 20% perennial ryegrass<br>• seeded at 360 pounds per acre | Included as an attachment to October 2016 Monthly Progress Report. |

**Notes:** All tracked changes will be reflected in the as-built drawings and Final Record Documents as agreed to with the Parties.

**12/13/2016**
**MONTHLY REPORT**

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

December 13, 2016

Honorable Robert G. Torricelli
Office of the Special Master
c/o Sean Jackson
7 So. Lanning Ave.
Hopewell, NJ 08525

**Re: Riverkeeper et al v. Honeywell International Inc. et al**
**Study Areas 6 and 7 Combined Monthly Progress/Highlights**
**Report No. 2016-11**

Dear Senator Torricelli:

Attached is the combined Chromium Remedy Monthly Progress Report for Study Areas 6 and 7, for activities conducted by Honeywell during the period from November 1 – November 30, 2016.

If you have any questions concerning the content of the report, please feel free to contact the undersigned.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:jtc/sgf

Attachment: Novembefr 2016 SA-6/7 Combined Monthly Progress Report No. 2016-11

cc: Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP (electronic copy)
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall (electronic copy)
Jason Watson – City Hall (electronic copy)
Agnieszka Antonian - Connell Foley LLP (electronic copy)
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP (electronic copy)
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell (electronic copy)
Maria Kaouris - Honeywell (electronic copy)
John Morris - Honeywell (electronic copy)
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP (electronic copy)
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP (electronic copy)
Steve Egnaczyk - The Louis Berger Group, Inc. (electronic copy)
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP (electronic copy)
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP (electroni copy)

Honeywell

# STUDY AREAS 6 AND 7 COMBINED MONTHLY PROGRESS/HIGHLIGHTS REPORT NO. 2016-11

**Project SA-6 & 7 Remediation**

# November 2016

## A. SUBMITTALS AND MEETINGS

| Date | Submittal/Meeting | Recipient |
|---|---|---|
| 11/07/16 | Initiation of Long Term Groundwater Monitoring<br>Study Area 6 (SA-6) South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/09/16 | SA-6 South Declaration No. 2 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/14/16 | Study Areas 6 and 7 Combined Monthly Progress/Highlights Report No. 2016-10 | Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/17/16 | SA-6 South 12-month transition period groundwater elevation data (Presentation Slides) | *Upload to Louis Berger SharePoint Site* |
| 11/15/16 | Special Master All Parties Meeting | n/a |
| 11/21/16 | Study Area 6 Chromium Remediation – PVSC Connection Fee<br>Jersey City, NJ<br>Connection File # 15830 | Frank Grant<br>Passaic Valley Sewerage Commission |
| 11/21/16 | Honeywell International Inc.<br>Court Ordered Regional Groundwater Remedy Treatment Plant<br>Located at 525 & 575 Route 440, Jersey City<br>MR 1 and MR 2<br>Permit ID# 20630025 | Andy Caltagirone<br>Manager of Industrial & Pollution Control<br>Passaic Valley Sewerage Commission |
| 11/30/16 | SA-6 North Declaration No. 4 | The Honorable Robert G. Torricelli<br>Office of the Special Master |
| 11/30/16 | Groundwater Sampling Results<br>Study Area 6 (SA-6) South<br>Jersey City, New Jersey | The Honorable Robert G. Torricelli<br>Office of the Special Master |

## SITE OPERATIONS

### 1. AVERAGE WEEKLY SITE RESOURCES

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 11/6/16 | 11/13/16 | 11/20/16 | 11/27/16 |
| **Construction Management (AMEC)** | 9 | 8 | 10 | 7 |
| **Engineering (AMEC)** | 1 | 1 | 1 | 1 |

| Team | Week Ending | | | |
|---|---|---|---|---|
| | 11/6/16 | 11/13/16 | 11/20/16 | 11/27/16 |
| **Air Monitoring (Emilcott)** | 1 | 1 | 1 | 1 |
| **Security (Securitas)** | 3 | 3 | 3 | 3 |
| **Entact/Subcontractors** | 19 | 20 | 22 | 16 |
| **Arecon/US Ecology Subcontractors** | 0 | 0 | 0 | 1 |
| **Maser** | 1 | 0 | 1 | 1 |
| **Langan** | 0 | 0 | 0 | 0 |
| **ERFS** | 0 | 0 | 0 | 1 |
| **Evoqua** | 1 | 1 | 1 | 1 |
| **B&B Drilling** | 0 | 0 | 1 | 0 |
| **Cornerstone** | 0 | 0 | 1 | 2 |
| **TOTAL STAFF** | **35** | **34** | **41** | **34** |

## 2. SITE HIGHLIGHTS (GENERAL)

- Performed routine groundwater monitoring and GWET inspections.
- Continued Ground Water Treatment Plant (GWTP) processing activities.
- Conducted perimeter air monitoring activities using hand-held portable devices for nuisance dust.
- Completed installation of CGWES components within the SA-6 North Open Space Areas to include installation of spare conduit pipe for future piezometer instrumentation on the north side of the SA-6 North Open Space Area.
- Initiated long-term groundwater monitoring activities at SA-6 South in accordance with the correspondence submitted by Honeywell to All Parties, dated November 7, 2016. This correspondence also transmitted results of samples collected from piezometers located on the interior of both SA-6 North and SA-6 South Open Areas.
- Completed post-injection groundwater sampling and monitoring in Treatment Area 10-1 in accordance with the NJDEP – Discharge to Groundwater Permit.
- On December 5, 2016, collected post-injection soil samples for total and hexavalent chromium and sulfide from the TA-10-1 area in accordance with the Amec Foster Wheeler memo entitled, "Proposed In-Situ-Treatment Event for Remaining Hexavalent Chromium Impacted Soils – Treatment Area 10-1", dated July 11, 2016.
- Conducted S-3 Mass Removal Injection Event No. 34 in injection well 088-IW-03.
- Completed sidewalk restoration activities within the work limits along Route 440.
- Removed Highway Occupancy Permit Fence and barricades along Route 440.

## B. SA-6N GROUND WATER TREATMENT PLANT

- Cleaned all process vessel pH and ORP probes, and mixed/refilled the polymer.
- Cleaned downstream process tanks T-300 (neutralization tank) and T-400 (effluent tank).
- Received monthly lab results for the GWTP effluent PVSC sampling conducted on November 15, 2016.

### 1. WEEKLY SUMMARY

| 80 Kellogg GWTP Data | Week Ending | | | |
|---|---|---|---|---|
| | 11/06/16 | 11/13/16 | 11/20/16 | 11/27/16 |
| Avg. Gallons Treated & Discharged (per day) | 77,961 | 77,307 | 78,910 | 74,929 |
| Average Flow (gpm) for Operating Period | 55 | 55 | 56 | 58 |
| Avg. Hours of Plant Operation | 23 | 23 | 23 | 22 |
| GWTP Influent Tanks (gal.) | 3,246 | 2,844 | 4,300 | 3,463 |

## C. EXCAVATION AND BACKFILL *(see **Attachment 3** for Progression Chart)*

- Continued storm-water management activities.
- Completed cleaning and demobilization of temporary Construction Water Treatment Plant.
- Initiated placement of geotextile and 6 inches of #57 Stone in the SA-6 North in the area just north of the Open Space Area and south of the JCMUA property. The restoration serves as both final restoration of disturbed areas and also as historic fill cap.

### 1. OFF-SITE DISPOSAL MONTHLY WASTE MATERIALS SUMMARY

| Contractor/ Transporter | Truck Type | Destination | TSDF | Material | Truck Loads | Avg. T/ Truck | Tons Shipped |
|---|---|---|---|---|---|---|---|
| **Siemens/FCI** | Roll-off | Sarnia, Ontario Canada | Stablex | WWTP Filer Cake | 1 | 17 | 17 |
| **Montecalvo** | Tri-axle | Keasby, NJ | Bay shore Recycling | Non Haz Cr | 4 | 24 | 96 |

### 2. EXCAVATION & BACKFILL PROGRESS

| Description | Areas |
|---|---|
| **Backfill in Progress** | #57 Stone Historic Fill Cap – SA6 N Restoration Area |

### 3. BACKFILL MATERIALS USED (TONS)

| Source | Week Ending | | | |
|---|---|---|---|---|
| | 11/06/16 | 11/13/16 | 11/20/16 | 11/27/16 |
| Natures Choice Topsoil | 801 | 0 | 1,241 | 287 |
| EME Topsoil | 4,640 | 5,090 | 3,566 | 1,524 |
| Tilcon Mount Hope I-8 | 104 | 0 | 52 | 0 |
| Natures Choice Horizon C | 203 | 0 | 0 | 108 |
| Tilcon DGA | 0 | 0 | 0 | 100 |
| Tilcon Mt. Hope 1.5" | 0 | 52 | 51 | 77 |
| Tilcon Mt. Hope #57 | 0 | 513 | 1,427 | 1,189 |
| Weldon Screenings | 277 | 139 | 0 | 0 |

- The EME Horizon A clean fill new source information dated October 13, 2016 is included in Attachment 15.
- This new source transmittal includes the EME certification that materials from their identified quarries being used for the Horizon A Topsoil are both virgin and not commingled. In addition, this transmittal includes all initial analytical and geotechnical data that supported the material meets the SA-6 100% Design and DCB adjusted specifications for Horizon A topsoil.
- In response to Plaintiffs' initial questions, we are also attaching the October 19, 2016 e-mail transmittal which confirmed earlier discussions (among Amec Foster Wheeler and the Parties during a conference call on October 4, 2016) which identified that the EME facility needed to increase the organic content via blending of an amendment to meet SA-6 100% Design and DCB adjusted specifications.
- The October 19, 2016 transmittal also clarifies that a natural Peat material was the organic amendment being used in the blending process at the EME facility. Honeywell further provided a separate clean fill certification from the Peat organic amendment supplier.
- Lastly, the October 19, 2016 response by Honeywell includes a clarification statement that Amec Foster Wheeler obtained the analytical and geotechnical samples on the blended Horizon A Topsoil product to be imported to SA-6.

## D. SURCHARGE OPERATIONS

- All surcharging activities are completed.

## E. SHEET PILE OPERATIONS

- All sheet pile operations are complete.

## F. CAPPING OPERATIONS

- Completed importing and placing Horizon A soils on SA-6 South Open Space Area.

- Completed hydro-seeding of SA-6 South Open Space Area and placement of erosion control matting.
- Completed installation of toe drain on the south side slope of the SA-6 North Open Space Area.
- Performed hydro-seeding of the SA-6 North Open Space Area and placement of erosion control matting.
- Completed importing and placing Horizon A soils on SA-6 North Open Space Area.
- Stockpiled a small quantity of Horizon A & C soils within SA-7 for potential future repairs of the SA-6 South and SA-6 North Open Space Areas.

## G. PERMIT STATUS

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Waterfront Development | SA-6 North Only | Obtained 6/23/2010 | Not Specified, Est. 3/31/2015 | 6/23/2015 | - |
| NJDEP CAFRA/FHA | SA-6 South Only | Obtained 9/26/2012 | Renewal Not Needed | 9/25/2017 | 10/09/2012 |
| HEPSCD SESCP | Novartis Soil Pile/SA-7 | Obtained 8/21/2012 Extension Obtained 5/17/2015 | Renewal Not Needed | 10/04/2019 | - |
| NJDEP RFA | Novartis Soil Pile/SA-7 | Obtained 9/7/2012 | Renewal Not Needed | Not Specified | - |
| PVSC SUP No. 31630019 | SA-6 Chromium Remedy | Obtained 3/26/2014 Final Revision 5/23/14 | Renewal Not Needed | 8/31/2018 | 04/19/2014 |
| SESCP | SA-6 Chromium Remedy | Obtained 5/16/2013 | Renewal Not Needed | 11/16/2016 | - |
| RFA | SA-6 Chromium Remedy | Obtained 5/29/2013 | Not Specified | Not Specified | - |
| NJDEP - Water Allocation | SA-6 Chromium Remedy | Obtained 6/19/2013 | Renewal Not Needed | 5/31/2018 | - |
| NJDEP – Treatment Works Approval | SA-6 Chromium Remedy | Obtained 7/8/2013 Extension Obtained 3/16/2015 | Not Specified, Est. 3/31/2016 | 6/30/2016* | - |
| NJDOT - Highway Occupancy Permit | SA-6 Chromium Remedy | Obtained 9/11/2013 Extension Obtained 10/14/2015 | Not Specified | 6/30/2016 | - |
| NJDEP CAFRA/WFD/FHA GWTP Force Mains | GWTP | Obtained 4/22/2008 | Renewal Not Needed | 4/22/2013 | - |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| HEPSCD SESCP | GWTP | Obtained 8/27/2012 | Renewal Not Needed | 2/27/2016 | - |
| NJDEP CAFRA/WFD/FHA | GWTP | Obtained 11/16/2012 | Renewal Not Needed | 6/23/2015 | - |
| NJDEP Treatment Works Approval | GWTP | Obtained 4/11/2013 | Renewal Not Needed | 4/10/2015 | 4/23/2013 |
| NJDEP Air Pollution Control Preconstruction Permit | Existing GWTP | Obtained 9/24/2013 Automatically Renewed for 5 years | Not Specified, Est. 3/23/2019 | 6/23/2019 | 11/20/2013 |
| PVSC SUP No. 20630025 | Existing GWTP | Obtained 10/1/2013 Final Revision Received 12/02/2015 | 6/30/2018 | 9/30/2018 | 10/29/2013 |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 4/30/2012 Revised 07/14/2015 | Not Specified | Not Specified | 5/10/2012 |
| NJDEP DGW for In-Situ Treatment of Chromium Impacted Soils | SA-6 South Only | Obtained 1/3/2013 | Not Specified | Not Specified | - |
| NJDEP Discharge to Groundwater (DGW) for In-Situ Treatment of Chromium Impacted Soils | SA-6 North Only | Obtained 08/04/2016 | Not Specified | Not Specified | 9/12/16 |
| NJPDES Permit | SA-7 | Renewed: Effective 12/01/2012 | Renewal Not Needed | 6/30/2015 | 1/11/2013 |
| Subchapter 8 Air Permit Application for the Waste Water Treatment Plant | SA-7 | Issued: 06/24/2009 | Renewal Not Needed | 6/23/2014 | 7/15/2009 |
| Individual Waterfront Development Permit and Water Quality Certificate for Sediment Remedy | SA-7 | Issued: 05/27/2011 Modified: 07/02/2012 | N/A | 5/26/2016 | 5/27/2011, 7/5/2012 |
| Tidelands Licenses for Sediment Remedy | SA-7 | Re-Issuance of Final Tidelands License is pending and will be effective 7/21/2013 | N/A | 7/21/2014 | 7/19/2012 |
| Pre-Construction Notice – Nationwide Permit #38 for Sediment Remedy | SA-7 | Issued: 3/21/2013 | N/A | 3/18/2015 | 3/25/2013 |

| Permit | Site | Status | Renewal Application Due Date | Expiration Date | Date Transmitted to the Louis Berger Group |
|---|---|---|---|---|---|
| NJDEP Individual Upland Waterfront Development Permit and Water Quality Certificate for Bulkhead Expansion Project | SA-7 | Issued: 5/10/2016 | TBD | 5/9/2021 | - |
| NJDOT – Application for Drainage Connection, Post Remediation Grading and Drainage | SA-6 Chromium Remedy | Application Submitted 8/19/14 Permit Application Rescinded 12/1/14 & Approved by DOT on 12/18/14 | N/A | N/A | N/A |
| NJDOT – Highway Occupancy Permit – Installation of Sheet Piling and Excavation Adjacent to Rte 440 ROW | SA-6 Chromium Remedy | Application Submitted 9/8/14 Final Executed Permit Issued 12/2/14 | 11/2/15, 1-yr Extension Obtained 12/24/15 | 12/03/16 | Pending |
| USACE Nationwide Permit No. 27 for Droyers Cove Beneficial Environmental Project | Bayfront | Issued: 4/15/2016 | TBD | 3/18/2017 | 5/4/16 |
| NJDEP Coastal General Permit 24 for the living shoreline | Bayfront | Issued: 10/15/2015 | TBD | 10/14/2020 | 5/4/16 |

** Amec Foster Wheeler reviewed the expiration of this TWA with NJDEP, Division of Water Quality and no extension is necessary.*

## H. PLANNED HIGHLIGHTS FOR NEXT MONTH

- Complete installation of the Contingent Groundwater Extraction System Components final connections within the GWTP including the mechanical piping and conduit.
- Complete hydro-seeding of SA-6 North Open Space Area.
- Complete storm-water management activities associated with construction.
- Complete placement of geotextile and 6 inches of #57 Stone in the SA-6 North Restoration Area.
- Complete SWPPP inspections associated with construction.
- Conduct fourth quarter regional groundwater level monitoring event.
- Complete demobilization of Entact crew, office trailers and equipment.

## ATTACHMENTS:

1. Schedule – 6 Month Look Ahead
2. Site Photographs
3. Excavation and Backfill (Progression Chart)
4. Dewatering Operations Update *(not included in this reporting period)*
5. SA-6 Construction Water Discharge Data (To PVSC)
6. Backfill Analytical Data *(not included in this reporting period)*
7. Perimeter Pools Update
8. Groundwater Quality Data *(provided quarterly, not included in this reporting period)*
9. Surcharge Monitoring Update *(not included in this reporting period)*
10. Sheet Pile Update *(not included in this reporting period)*
11. Capping Update (SA-6 Cap Subgrade Progress Maps)
12. Weekly SWPPP Reports
13. GWTP Update
14. SA-6 North & South Design Change Tracking Log
    - DCB 2016-7-14: Design change documenting minor grading adjustments to improvements to drainage off of the SA-6N Open Space Area
15. EME Soils
    - 10/13/16 – Transmittal: SA-6 New Source of Topsoil
    - 10/19/16 – E-mail Transmittal: Response to Email -- 101716 Horizon A Analytical Results 21319

## Attachment 1: Schedule – 6 Month Look Ahead

Honeywell

# SA-6 North/South Combined Chromium Remediation Schedule



| ID | Task Name | Duration | Start |
|---|---|---|---|
| **1** | **SA-6 North Chromium Remedy Preparation (Sites 087 and 088)** | **1936 days** | **Fri 1/4/08** |
| **2** | **Remedial Action Work Plan** | **33 days** | **Fri 1/4/08** |
| **5** | **Remedial Action Design** | **1522 days** | **Wed 2/20/08** |
| **18** | **JCIA/JCDPW Relocation** | **1780 days** | **Mon 8/11/08** |
| 19 | Develop Site Relocation Master Plan | 38 days | Mon 8/11/08 |
| 20 | Submit Site Relocation Master Plan | 0 days | Wed 10/1/08 |
| 21 | JC Construction of New Facilities | 1309 days | Tue 6/2/09 |
| 22 | Relocation Contractor Procurement | 392 days | Thu 4/15/10 |
| 23 | JCIA and JCDPW Relocation | 949 days | Mon 10/17/11 |
| 24 | Demolition of Existing JCIA Facilities - Sedimentation Basin | 101 days | Mon 12/12/11 |
| 24a | Demolition of JCIA Structures | 146 days | Mon 9/1/14 |
| **25** | **SA-6 South Chromium Remedy Preparation (Sites 073, 124, 125, 134, 140 and 163)** | **1518 days** | **Fri 7/11/08** |
| **26** | **Remedial Action Work Plan** | **187 days** | **Fri 7/11/08** |
| **32** | **Remedial Action Design** | **1161 days** | **Mon 2/2/09** |
| **57** | **SA-6 South Relocation** | **616 days** | **Mon 12/26/11** |
| 58 | New GWTP Construction Completion | 502 days | Mon 3/5/12 |
| 59 | Demolition of 80 Kellogg | 857 days | Mon 12/26/11 |
| **60** | **SA-6 North/South Field Implementation** | **894 days** | **Fri 3/1/13** |
| 60a | SA-6N In-Situ Treatment Areas 7, 8 and 10 | 664 days | Mon 6/17/13 |
| 60b | SA-6S (Site 163) In-Situ Treatment | 555 days | Fri 11/15/13 |
| **61** | **Mobilization (Includees new GWTP, In-situ Treatment & Main Remedy)** | **87 days** | **Fri 3/1/13** |
| 61a | Mobilization | 87 days | Fri 3/1/13 |
| **62** | **Surcharge Install/Instrumentation** | **706 days** | **Mon 6/17/13** |
| 62a | Prepare Open Space Areas for Surcharge/Install Instumentation | 142 days | Mon 6/17/13 |
| 62b | Place Stockpile Surcharge SA6N Western Areas | 185 days | Tue 4/8/14 |
| 62c | Place Stockpile Surcharge SA6N Eastern Areas | 175 days | Tue 6/30/15 |
| 62d | Place Stockpile Surcharge SA6S Western Areas | 91 days | Mon 6/16/14 |
| 62e | Place Stockpile Surcharge SA6S Eastern Areas | 155 days | Mon 10/6/14 |
| **63** | **Barrier Wall Install** | **569 days** | **Mon 8/12/13** |
| 63a | SA 6N Installation of Barrier Wall | 159 days | Mon 3/9/15 |
| 63b | SA 6S Installation of Barrier Wall | 210 days | Mon 8/12/13 |
| **64** | **Excavation** | **507 days** | **Tue 10/22/13** |
| 64a | SA 6N Excavation | 218 days | Mon 12/1/14 |
| 64b | SA 6S Excavation | 295 days | Tue 10/22/13 |
| **65** | **Backfill** | **558 days** | **Mon 11/11/13** |
| 65a | SA 6N Backfill | 283 days | Mon 12/1/14 |
| 65b | SA 6S Backfill | 384 days | Mon 11/11/13 |
| **66** | **Capping and Cover Soil Placement** | **426 days** | **Mon 12/1/14** |
| 66a | SA 6N Capping and Cover Soil Placement | 83 days | Thu 3/24/16 |
| 66b | SA 6S Capping and Cover Soil Placement | 283 days | Mon 12/1/14 |
| **67** | **Restoration** | **234 days** | **Tue 9/1/15** |
| 67a | Restoration | 234 days | Tue 9/1/15 |
| **68** | **Demobilization** | **22 days** | **Fri 7/1/16** |
| 68a | Deferred Remediation of SA-6 South Along Bulkhead | 1 day | Fri 3/1/13 |
| 68b | Deferred Remediation of SA-6 North/South Along PSEG Gas Line | 1 day | Fri 3/1/13 |
| **69** | **SA-6 North Project Closeout** | **311 days** | **Thu 10/1/15** |
| **75** | **SA-6 South Project Closeout** | **311 days** | **Thu 10/1/15** |
| **81** | **SA-6 North Long Term Protections** | **1830 days** | **Wed 10/1/08** |
| **92** | **SA-6 South Long Term Protections** | **2569 days** | **Thu 6/5/08** |




Project: SA-6 Remediation Schedule
Revision 4
Date: 8/2/2016

Task | Milestone | Summary | Critical

Note: Current field implementation schedule shows final restoration activities and demobilization in December 2016.

## Attachment 2: Site Photographs




**Site Photograph 1:** Finishing toe drain at SA-6S Open Space Area.




**Site Photograph 2:** Grading topsoil along north slope of the SA-6N Open Space Area.




**Site Photograph 3:** Hydroseeding the top of SA-6S Open Space Area.




**Site Photograph 4:** Restoring curb and sidewalk along Route 440.




**Site Photograph 5:** Securing straw matting on SA-6S Open Space Area.





**Site Photograph 6:** Watering the SA-6S Open Space Area.

## Attachment 3: Excavation and Backfill Progression Chart

# Jersey City & Kellogg Street Properties Remedies
# Progress as of December 1, 2016

Study Areas 6 and 7 Combined Progress Report No. 2016-11
Attachment 3: Excavation and Backfill (Progression Chart)




## Legend

- Property Line
- 72” PVSC Sewer Force Main
- Temporary Sheeting to Support Excavation

**Underground Barrier Wall**
- Planned
- Complete

**Excavation**
- Planned
- Complete

**Soil Compaction**
- In Progress
- Complete

**Open Space Containment**
- In Progress
- Complete

## Attachment 4: Dewatering Operations Update

(not included in this reporting period)

## Attachment 5: Weekly Dewatering Discharge to PVSC

## STUDY AREA 6 CONSTRUCTION WATER DISCHARGE DATA (TO PVSC)


| DATE | SHIFT START TIME | SHIFT END TIME | HOURS OF OPERATION | DISCHARGE FLOW METER SHIFT START (KGal) | DISCHARGE FLOW METER SHIFT END (KGal) | DISCHARGED VOLUME (Gal) PUMPING DURATION | DISCHARGED VOLUME (Gal) TOTAL | COMMENTS |
|---|---|---|---|---|---|---|---|---|
| 07/07/16 | 7:30 | 12:00 | 4:30 | 43,596.37 | 43,642.93 | 46,560 | 43,642,480 | PVSC Compliance Sample Collected |
| 07/15/16 | 10:00 | 14:00 | 4:00 | 43,642.93 | 43,692.98 | 50,050 | 43,692,530 | |
| 07/26/16 | 9:00 | 14:00 | 5:00 | 43,692.98 | 43,794.27 | 101,290 | 43,793,820 | |
| 07/27/16 | 7:00 | 15:00 | 8:00 | 43,794.27 | 43,826.36 | 32,090 | 43,825,910 | |
| 07/28/16 | 9:00 | 15:00 | 6:00 | 43,826.36 | 43,860.98 | 34,620 | 43,860,530 | |
| 08/01/16 | 9:00 | 15:00 | 6:00 | 43,860.98 | 43,896.38 | 35,400 | 43,895,930 | PVSC Compliance Sample Collected |
| 08/11/16 | 9:00 | 16:00 | 7:00 | 43,896.38 | 43,958.93 | 62,550 | 43,958,480 | |
| 08/12/16 | 9:30 | 13:45 | 4:15 | 43,958.93 | 43,998.63 | 39,700 | 43,998,180 | |
| 08/19/16 | 8:00 | 13:30 | 5:30 | 43,998.63 | 44,062.58 | 63,950 | 44,062,130 | |
| 09/08/16 | 7:00 | 13:00 | 6:00 | 44,062.58 | 44,120.80 | 58,220 | 44,120,350 | PVSC Compliance Sample Collected |
| 10/05/16 | 8:00 | 11:00 | 3:00 | 44,120.80 | 44,158.46 | 37,660 | 44,158 | PVSC Compliance Sample Collected |
| 11/01/16 | 8:00 | 10:00 | 2:00 | 44,158.46 | 44,204.91 | 46,450 | 44,205 | Final reading; system disassembled 11/1/16 |

Notes: Previous information is truncated. Only last month and current month information is provided.

## Attachment 6: Backfill Analytical Data

(not included in this reporting period)

## Attachment 7: Perimeter Pools Update




**LEGEND**

- FILL TYPE A CLAY
- FILL TYPE B GRANULAR FILL
- SHALLOW WELL INSTALLED BY OTHERS
- SHALLOW WELL ABANDONED IN 2014 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN
- SHALLOW WELL INSTALLED FOR STUDY AREA 7 REMEDIATION
- SURCHARGE MONITORING STANDPIPE INSTALLED IN 2014 OR 2015 IN ACCORDANCE WITH STUDY AREA 6 100% DESIGN

**GRAPHIC SCALE**

100' 50' 0 100' 200'

**IN PROGRESS**
06-10-2015


**STUDY AREA 7**
**PERIMETER POOL DESIGN ELEVATIONS**

NEW JERSEY


MUESER RUTLEDGE CONSULTING ENGINEERS
14 PENN PLAZA – 225 WEST 34th STREET

FILE NO. 10210
DRAWING NO. PP-1


Jul 09, 2015 at 3:14pm
G:\DWGS\102\10210\Dewatering\PP-1.dwg
bboscaino





**Perimeter Pool N1** (Sta. N13+60 to N20+25)





**Perimeter Pool N2** (Sta. N10+73 to N13+10)





**Perimeter Pool N3** (Sta. N6+80 to N10+23)





**Perimeter Pool N4** (Sta. N6+80 to N10+23)





**Perimeter Pool E1** (Sta. E0+50 to E3+75)





**Perimeter Pool E2** (Sta. E4+50 to E7+25)





**Perimeter Pool S1** (Sta. S0+50 to S3+88)




**Perimeter Pool S2** (Sta. S4+38 to S10+60)




**Perimeter Pool S3** (Sta. S11+10 to S17+50)




**Perimeter Pool S4** (Sta. S17+86 to S22+05)

## Table 1

Shallow Groundwater Data

| | | | | | | | | | | North | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E1A-SO | E2-SO | E3-SO | E4-SO | E5-SO | W1-SO | W3-SO | W5-SO | W6-SO | FS-5 | FS-6 | FS-7 | FS-13 |
| Date | | | | | | | | | | | | | |
| 12/1/2015 | 1.7 | 4.2 | 4.8 | 3.6 | 3.9 | 6.2 | 1.7 | 1.6 | 5.6 | 4.5 | 5.0 | 3.8 | 3.5 |
| 12/14/2015 | 1.7 | 4.3 | 4.7 | 3.3 | 3.8 | 6.2 | 1.9 | 1.8 | 5.8 | | 3.5 | 3.6 | |
| 12/30/2015 | 1.8 | 4.1 | 4.8 | 4.9 | 4.8 | 7.5 | 1.9 | 1.9 | 6.9 | 5.2 | | | 4.6 |
| 1/15/2016 | 1.8 | 4.4 | 4.8 | | | 7.9 | 2.0 | 2.0 | 7.4 | 6.0 | | | 5.6 |
| 2/1/2016 | 2.1 | 4.3 | 6.0 | 5.1 | | 7.7 | 2.2 | 2.1 | 7.6 | 6.5 | | | 6.2 |
| 2/16/2016 | 2.4 | 4.5 | 5.3 | 5.6 | 5.4 | 6.7 | 2.4 | 2.4 | 5.5 | 6.0 | | | 5.7 |
| 3/1/2016 | 2.5 | 5.1 | 6.2 | 4.9 | 5.4 | 5.1 | 2.3 | 2.5 | 4.0 | 5.6 | | | 5.0 |
| 3/16/2016 | 2.7 | 5.5 | 6.1 | 3.3 | 4.0 | 4.2 | 2.6 | 2.6 | 3.1 | 2.7 | | | 3.6 |
| 4/1/2016 | 2.7 | 5.6 | 5.9 | 2.7 | 4.3 | 3.5 | 2.6 | 2.7 | 2.6 | 2.1 | | | |
| 4/15/2016 | 2.7 | 5.5 | 5.8 | 2.5 | 4.0 | 2.9 | 2.6 | 2.7 | 2.1 | 1.8 | | | |
| 5/2/2016 | 3.0 | 5.5 | 5.8 | 2.6 | 4.1 | | 2.7 | 2.8 | 2.2 | 1.6 | | | |
| 5/16/2016 | 2.8 | 5.5 | 5.9 | 2.4 | 2.9 | 2.4 | 2.9 | 2.9 | 1.6 | | | | |
| 6/1/2016 | 2.7 | 5.2 | 5.5 | 2.5 | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/16/2016 | 2.7 | 5.2 | 5.6 | | 3.0 | 2.5 | 2.9 | 3.0 | 1.7 | | | | |
| 6/28/2016 | 3.2 | 5.2 | 5.6 | 2.4 | 3.2 | 2.3 | 3.1 | 3.1 | 1.8 | | | | |
| 7/15/2016 | 3.2 | 5.3 | 5.6 | 2.5 | 3.3 | 2.4 | 3.1 | 3.2 | 1.8 | | | | |
| 7/27/2016 | 3.1 | 5.3 | 5.4 | 2.6 | 3.2 | 2.3 | 3.1 | 3.2 | 2.0 | | | | |
| 8/12/2016 | 3.4 | 5.3 | 5.6 | 3.2 | 2.6 | 2.8 | 3.3 | 3.4 | 2.5 | | | | |
| 8/29/2016 | 3.5 | 5.1 | 5.4 | 3.1 | 2.6 | 2.8 | 3.4 | 3.4 | 2.7 | | | | |
| 9/9/2016 | 3.5 | 5.0 | 5.4 | 3.2 | 3.4 | 2.6 | 3.4 | 3.5 | 2.3 | | | | |
| 9/29/2016 | 3.5 | 4.8 | 5.2 | 3.2 | 3.3 | 3.1 | 3.5 | 3.5 | 1.7 | | | | |
| 10/17/2016 | 3.6 | 4.7 | 5.2 | 3.3 | 3.5 | 2.3 | 3.6 | 3.5 | 2.2 | | | | |
| 11/4/2016 | 3.6 | 4.6 | 4.9 | 3.3 | 3.9 | 2.5 | 3.6 | 3.5 | 2.5 | | | | |
| 11/16/2016 | 3.6 | 4.6 | 4.9 | 3.6 | 4.1 | 2.7 | 3.7 | 3.6 | 2.7 | | | | |

The following wells have been abandoned in accordance with the SA-6 100% Design:
134-W4-DO, 087-MW-001, 087-MW-019, 087-MW-Y20, 115-E1-DO, 115-E1-SO, 125-MW-01, 073-MW-BB-11, 073-MW-Y10, 134-MW-Q08.

The following wells have been abandoned:
North FS-1, FS-2, FS-3, FS-4, FS-5, FS-6, FS-7, FS-13
South FS-1, FS-3, FS-4, FS-5, FS-6, FS-7

The following wells are temporarily inaccessible:
134-MW-V09,

## Attachment 8: Groundwater Quality Data

(not included in this reporting period)

## Attachment 9: Surcharge Monitoring Update

(not included in this reporting period)

## Attachment 10: Sheet Pile Update

(not included in this reporting period)

**Attachment 11: Capping Update** (SA-6 Cap Subgrade Progress Maps)




LEGEND

- HORIZON C SOIL PLACED
- STRUCTURAL FILL PLACED
- SCB WALL
- HB WALL
- TOPSOIL PLACED

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP COVER SOILS PROGRESS MAP
12/05/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




LEGEND

TOPSOIL PLACED

SCB WALL

HB WALL

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP COVER SOILS PROGRESS MAP
11/04/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

## Attachment 12: Weekly SWPPP Reports

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 4, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☐ Fair ☐ Cloudy ☐ Other _____
☒ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 2 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 3 |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 4 |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

NOTE: All comments are numbered for reference and included on the included comment section.

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Project Name: SA-6&7 COURT ORDERED REMIDIATION ACTION

Facility Location: Jersey City, NJ

Date: 11/07/16

SWPPP Observer: _____
Signature

# Honeywell

## STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
## 60 KELLOGG STREET; JERSEY CITY, NJ
## WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE

**Friday, November 04, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710
PERMIT CLOSED

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | Windscreen material has become detached from the perimeter fence on SA-6 South along Kellogg Street and by the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Garbage has accumulated on the grassy area by the Kellogg Street jughandle. |
| 3 | IA2Q4A1AL8 | Windscreen material has become detached from the perimeter fence on SA-6 north adjacent to the JCMUA property. |
| 4 | IA2Q4A1AL8 | Garbage has accumulated in the SA-6 North pedestrican walkway along Rte. 440. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ Signature **Date:** 11/07/16

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen fabric to the perimeter fence as required. | RLAD 11/10/16 |
| 2 | Pick up and dispose of accumulated garbage/refuse. | |
| 3 | Re-attach the windscreen fabric to the perimeter fence as required. | |
| 4 | Pick up and dispose of accumulated garbage/refuse. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 11/10/16

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Date of Inspection: November 11, 2016**

**Type of Inspection:** ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

**Weather Conditions:** ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| **SA-6 South** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| **SA-6 North & GWTP** | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | | X | | 7 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 11/14/16

**SWPPP Observer:** _____
Signature

# Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Friday, November 11, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710
PERMIT CLOSED

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Windscreen material has become detached from the perimeter fence on SA-6 South along Kellogg Street and by the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | Filter fabric in all catch basins on SA-6 South must be replaced prior to demobilization. |
| 3 | IA2Q4A1AL8 | REPEAT: Garbage has accumulated on the grassy area by the Kellogg Street jughandle. |
| 4 | IA2Q4A1AL8 | Windscreen material has become detached from the perimeter fence along the JCMUA parking lot. |
| 5 | IA2Q4A1AL8 | Filter fabric in all catch basins on SA-6 North must be replaced prior to demobilization. |
| 6 | EEPSQU02YB | Sediment control measures (silt fence or hay bales) are missing in several areas surrounding the Novartis material stockpile area on SA-7. |
| 7 | IA2Q4A1AL8 | Filter fabric in all catch basins on SA-7 must be replaced prior to demobilization. |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 11/14/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen fabric to the perimeter fence as required. | All will |
| 2 | Replace filter fabric in all catch basins on SA-6 South and on Kellogg Street. | be done |
| 3 | Pick up and dispose of accumulated garbage/refuse. | prior to |
| 4 | Re-attach the windscreen fabric to the perimeter fence as required. | demob. |
| 5 | Replace filter fabric in all catch basins on SA-6 North. | R&D |
| 6 | Complete the installation of sediment control measures around the Novartis stockpile area on SA-7. | |
| 7 | Replace filter fabric in all catch basins on SA-7 | 11-17-16 |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 11/17/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 18, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | X | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | | X | | 3 |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 4 |
| Storm Drain Protection | | X | | 5 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 6 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 11/21/16

**SWPPP Observer:** _____
Signature

Honeywell

STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET; JERSEY CITY, NJ
WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE
Friday, November 18, 2016

SA-6 North & South
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

GWTP (SA-6 North)
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710
PERMIT CLOSED

Novartis Soil Pile
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJIf

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | **REPEAT:** Windscreen material has become detached from the perimeter fence on SA-6 South along Kellogg Street and by the Kellogg Street jughandle. |
| 2 | IA2Q4A1AL8 | **REPEAT:** Filter fabric in all catch basins on SA-6 South must be replaced prior to demobilization. |
| 3 | IA2Q4A1AL8 | **REPEAT:** Garbage has accumulated on the grassy area by the Kellogg Street jughandle. |
| 4 | IA2Q4A1AL8 | **REPEAT:** Windscreen material has become detached from the perimeter fence along the JCMUA parking lot. |
| 5 | IA2Q4A1AL8 | **REPEAT:** Filter fabric in all catch basins on SA-6 North must be replaced prior to demobilization. |
| 6 | EEPSQU02YB | **REPEAT:** Sediment control measures (silt fence or hay bales) are missing in several areas surrounding the Novartis material stockpile area on SA-7. |
| | | |
| | | |
| | | |
| | | |

**Project Name:** SA-6 COURT ORDERED REMEDIATION ACTION

**Facility Location:** Jersey City, New Jersey

**SWAP Observer:** _____ **Date:** 11/21/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen fabric to the perimeter fence as required. | 11/23/16 RAD |
| 2 | Replace filter fabric in all catch basins on SA-6 South and on Kellogg Street. | |
| 3 | Pick up and dispose of accumulated garbage/refuse. | |
| 4 | Re-attach the windscreen fabric to the perimeter fence as required. | |
| 5 | Replace filter fabric in all catch basins on SA-6 North. | |
| 6 | Complete the installation of sediment control measures around the Novartis stockpile area on SA-7. | |
| | | |
| | | |
| | | |
| | | |

**Construction Manager:** _____ **Date:** 11/23/16

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

Date of Inspection: November 23, 2016

Type of Inspection: ☒ Regular ☐ During Storm ☐ Annual
☐ Pre-Storm ☐ Post Storm

Weather Conditions: ☒ Fair ☐ Cloudy ☐ Other _____
☐ Rain ☐ Snow

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 South | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | | | X | |
| Stockpile Tarping/Containment | | | X | |
| Proper Chemical Storage | | | X | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-6 North & GWTP | | | | |
| Hay Bales/Silt Fence Present and Intact | X | | | |
| River Discharge Weir | | | X | |
| Swale Check Dams | | | X | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |

STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION
60 KELLOGG STREET
JERSEY CITY, NJ 07305
PHONE: 201-413-5160
FAX: 201-413-5161

# Weekly SWPPP Compliance Checklist

| Description | Satisfactory | Needs Work | Not Applicable | Comment Number |
|---|---|---|---|---|
| SA-6 North & GWTP | | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | | X | | 1 |
| Storm Drain Protection | | X | | 2 |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |
| SA-7 & Novartis Stockpile | | | | |
| Hay Bales/Silt Fence Present and Intact | | X | | 3 |
| River Discharge Weir | X | | | |
| Swale Check Dams | X | | | |
| Exclusion Zone Fencing | | | X | |
| Misc. Spill Control (Fuels, Lubricants, Etc.) | X | | | |
| Stockpile Tarping/Containment | X | | | |
| Proper Chemical Storage | X | | | |
| Containment Around Exclusion Zones | | | X | |
| Water Truck Wet- Down Operation | X | | | |
| Truck De-Con Operation | | | X | |
| Flood Protection | | | X | |
| Haul Road Maintenance | X | | | |
| Perimeter Fencing/Windscreen | X | | | |
| Storm Drain Protection | X | | | |
| Ponded Storm Water | X | | | |
| Housekeeping | X | | | |

**NOTE: All comments are numbered for reference and included on the included comment section.**

**STUDY AREAS 6&7- COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET**
**JERSEY CITY, NJ 07305**
**PHONE: 201-413-5160**
**FAX: 201-413-5161**

# Weekly SWPPP Compliance Checklist

**Project Name:** SA-6&7 COURT ORDERED REMIDIATION ACTION

**Facility Location:** Jersey City, NJ

**Date:** 11/23/16

**SWPPP Observer:** _____
Signature

Honeywell

**STUDY AREAS 6&7 - COURT ORDERED REMEDIAL ACTION**
**60 KELLOGG STREET; JERSEY CITY, NJ**
**WEEKLY SWPPP COMPLIANCE CHECKLIST COMMENT PAGE**
**Wednesday, November 23, 2016**

**SA-6 North & South**
SESCP SCD: IA2Q4A1AL8
RFA PI ID #: 608267
RFA Portal ID#: 304689
RFA NJPDES #: NJG0216771

**GWTP (SA-6 North)**
SESCP SCD: EHWG3RTMXR
RFA PI ID #: 587787
RFA Portal ID#: 219047
RFA NJPDES #: NJG0208710
PERMIT CLOSED

**Novartis Soil Pile**
SESCP SCD: EEPSQUO2YB
RFA PI ID #:
RFA Portal ID#: 217517
RFA NJI f

| Comment Number | Permit Number | SWAP Observer's Comments |
|---|---|---|
| 1 | IA2Q4A1AL8 | REPEAT: Windscreen material has become detached from the perimeter fence along the JCMUA parking lot. |
| 2 | IA2Q4A1AL8 | REPEAT: Filter fabric in all catch basins on SA-6 North must be replaced prior to demobilization. |
| 3 | EEPSQU02YB | REPEAT: Sediment control measures (silt fence or hay bales) are missing in several areas surrounding the Novartis material stockpile area on SA-7. |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Project Name: SA-6 COURT ORDERED REMEDIATION ACTION

Facility Location: Jersey City, New Jersey

SWAP Observer: _____ Date: 11/23/16
Signature

| Comment | Construction Manager's Comments to Contractor | Date Completed |
|---|---|---|
| 1 | Re-attach the windscreen fabric to the perimeter fence as required. | 12/1/16 RMD |
| 2 | Replace filter fabric in all catch basins on SA-6 North. | |
| 3 | Complete the installation of sediment control measures around the Novartis stockpile area on SA-7. | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Construction Manager: _____ Date: 12/01/16

## Attachment 13: GWTP Update (525/575 Route 440 GWTP PVSC Discharge Monitoring Report - submitted October 2016)

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

November 21, 2016

Andy Caltagirone
Manager of Industrial & Pollution Control
Passaic Valley Sewerage Commission
600 Wilson Avenue
Newark, NJ 07105

**Re: Honeywell International Inc.**
**Court Ordered Regional Groundwater Remedy Treatment Plant**
**Located at 525 & 575 Route 440, Jersey City**
**MR 1 and MR 2**
**Permit ID# 20630025**

Dear Mr. Caltagirone:

Honeywell is submitting the October 2016 discharge monitoring reports, MR 1 and MR 2, for the Court Ordered Regional Groundwater Remedy treatment plant located at 525 & 575 Route 440 in Jersey City. Our discharge is in compliance with the limits.

Please contact me at 973-455-2989 if you need further clarification or have questions.

On Behalf of Honeywell
Sincerely,

Helen Fahy
Remediation Manager
Fahy Associates

cc: (electronic copy)
Frank Schroyer – Amec Foster Wheeler
Angle Trujillo - Evoqua
Maria Kaouris - Honeywell
Dave Wissen - JCMUA

# PRETREATMENT MONITORING REPORT

NAME: Honeywell International Inc.; Jersey City GWTP; SA-6 North

MAILING ADDRESS: 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

FACILITY LOCATION: 525 Route 440, Jersey City, NJ 07305

CATEGORY & SUBPART: Not Applicable OUTLET #: 1

CONTACT OFFICIAL: Maria Kaouris TELEPHONE: 973-455-3302

NEW CUSTOMER ID / OUTLET ID: 20630025 OLD OUTLET DESIGNATION: 31630016

MONITORING PERIOD

| Start | | | End | | |
|---|---|---|---|---|---|
| 10 | 01 | 16 | 10 | 31 | 16 |
| \ | DAY | YR | MO | DAY | YR |

| | Average | Maximum |
|---|---|---|
| ~~Regulated Flow-gal/day~~ | | |
| Total Flow-gal/day | 78,106 | 84,582 (see attached) |

Method Used: Honeywell VersaFlow Mag 100 1-1/2" Flowmeter #FE/FIT-41001 w/ #TWM9000 WCG30011100 Non-Resettable Remote Totalizer Readout.

Production Rate (if applicable)

| PARAMETER | | MASS OR CONCENTRATION | | | # OF | SAMPLE TYPE |
|---|---|---|---|---|---|---|
| | | MON AVG | MAXIMUM | UNITS | SAMPLES | COMP/GRAB |
| Chromium | Sample Measurement | 0.96 | 1.04 | lb/day | 1 | COMP |
| | Permit Requirement | | **23** | lb/day | | |
| | | | | | | |
| | | | | | | |
| Copper | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.6** | | mg/l | | |
| Lead | Sample Measurement | <0.030 | <0.030 | mg/l | 1 | COMP |
| | Permit Requirement | **1.0** | | mg/l | | |
| Nickel | Sample Measurement | <0.010 | <0.010 | mg/l | 1 | COMP |
| | Permit Requirement | **3.9** | | mg/l | | |
| Mercury | Sample Measurement | <0.0002 | <0.0002 | mg/l | 1 | COMP |
| | Permit Requirement | **0.08** | | mg/l | | |
| Zinc | Sample Measurement | <0.020 | <0.020 | mg/l | 1 | COMP |
| | Permit Requirement | **4.2** | | mg/l | | |
| SGT-HEM; Non-Polar Material | Sample Measurement | <5.1 | <5.1 | mg/l | 1 | GRAB |
| | Permit Requirement | **100** | **150** | mg/l | | |
| TVOC | Sample Measurement | 0.1699 | 0.1699 | mg/l | 1 | GRAB |
| | Permit Requirement | N.A. | N.A. | mg/l | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |
| | Sample Measurement | | | | | |
| | Permit Requirement | | | | | |

PVSC FORM MR-1 REV: 4 6/87 P1

# PRETREATMENT MONITORING REPORT

Certification of Non-Use if applicable (use additional sheets): _____

Compliance or non compliance statement with compliance schedule (use additional sheets if necessary) for every parameter used: All analyte results are compliant (see attached report).

Explain Method for preserving samples: Monthly metals are preserved with HNO3. SGT-HEM & TVOC samples are preserved using HCl. BOD samples are collected in a refrigerated sampler. All samples are iced in a cooler during transport to the lab.

**I certify under penalty of law that this document and attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

**403.6(a)(2)(ii) revised by 53 FR 40610, October 17, 1988**

John J. Morris IV
Signature of Principal
Executive or Authorized Agent

John J. Morris
Remediation Portfolio Director
Type Name and Title

11/17/2016
Date

PVSC FORM MR-1 REV: 5 3/91 P2

# USER CHARGE SELF MONITORING REPORT

**NAME:** Honeywell International Inc.; Jersey City GWTP; SA-6 North

**ADDRESS:** 115 Tabor Avenue, Morris Plains, NJ 07950 (Attn: Maria Kaouris)

**FACILITY LOCATION:** 525 Route 440, Jersey City, NJ 07305

**NEW CUSTOMER ID / OUTLET ID:** 20630025 **OLD OUTLET DESIGNATION** 31630016

**MONITORING PERIOD**

| Start | | | End | | |
|---|---|---|---|---|---|
| 10 | 01 | 16 | 10 | 31 | 16 |
| MO | DAY | YR | MO | DAY | YR |

| VOL DISCHARGE THIS PERIOD |
|---|
| 2,421,276 GALS |
| CU. FT X 7.48 - GALLONS |
| |
| EFFLUENT METER READING LAST DAY THIS PERIOD 75,799,834 |

| DATE | BOD (mg/l) | TSS (mg/l) |
|---|---|---|
| 10/11/2016 | 5.9 | <4.0 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| DATE | BOD | TSS |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.**

| SIGNATURE OF PRINCIPAL OR | TYPE NAME AND TITLE | TELEPHONE NUMBER |
|---|---|---|
| John J. Morris | John J. Morris | (973) 455-4003 |
| | | |
| | | DATE 11/17/2016 |

**PVSC FORM MR-2 REV.3 6/93**

| PVSC DAILY OPERATING LOG | | | | Honeywell Jersey City GWTP; SA-6 North (Permit #20630025) | | | | | | | MONTH: October 2016 | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DATE | OPERATOR | PREVIOUS TOT. | CURRENT TOT. | DAILY FLOW | MGD | pH | TOTAL CR | SGT-HEM | BOD5 | | CU | PB | NI | HG | ZINC | CR LBS/DAY |
| | | | | Permit Limits | 0.2376 | 5-10.5 | | 100 mg/l max | | | 3.6 mg/l | 1.0 mg/l | 3.9 mg/l | 0.08 mg/l | 4.2 mg/l | 23 #/day |
| | | | | gallons/day | | pH Units | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | mg/l | lbs/day |
| 10/1/2016 | Angel Trujillo | 73378558 | 73460508 | 81,950 | 0.08195 | 7.23 | 1.480 | | | | | | | | | 1.01 |
| 10/2/2016 | Angel Trujillo | 73460508 | 73536160 | 75,652 | 0.075652 | 7.40 | 1.480 | | | | | | | | | 0.93 |
| 10/3/2016 | Angel Trujillo | 73536160 | 73611812 | 75,652 | 0.075652 | 7.29 | 1.480 | | | | | | | | | 0.93 |
| 10/4/2016 | Angel Trujillo | 73611812 | 73689504 | 77,692 | 0.077692 | 7.31 | 1.480 | | | | | | | | | 0.96 |
| 10/5/2016 | Angel Trujillo | 73689504 | 73766524 | 77,020 | 0.07702 | 7.36 | 1.480 | | | | | | | | | 0.95 |
| 10/6/2016 | Angel Trujillo | 73766524 | 73849214 | 82,690 | 0.08269 | 7.46 | 1.480 | | | | | | | | | 1.02 |
| 10/7/2016 | Angel Trujillo | 73849214 | 73925458 | 76,244 | 0.076244 | 7.40 | 1.480 | | | | | | | | | 0.94 |
| 10/8/2016 | Angel Trujillo | 73925458 | 74007834 | 82,376 | 0.082376 | 7.35 | 1.480 | | | | | | | | | 1.02 |
| 10/9/2016 | Angel Trujillo | 74007834 | 74085721 | 77,887 | 0.077887 | 7.40 | 1.480 | | | | | | | | | 0.96 |
| 10/10/2016 | Angel Trujillo | 74085721 | 74163608 | 77,887 | 0.077887 | 7.79 | 1.480 | | | | | | | | | 0.96 |
| 10/11/2016 | Angel Trujillo | 74163608 | 74241954 | 78,346 | 0.078346 | 7.33 | 1.480 | <5.1 | 5.9 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | 0.97 |
| 10/12/2016 | Angel Trujillo | 74241954 | 74317348 | 75,394 | 0.075394 | 7.51 | 1.480 | | | | | | | | | 0.93 |
| 10/13/2016 | Angel Trujillo | 74317348 | 74394862 | 77,514 | 0.077514 | 7.51 | 1.480 | | | | | | | | | 0.96 |
| 10/14/2016 | Angel Trujillo | 74394862 | 74470970 | 76,108 | 0.076108 | 7.44 | 1.480 | | | | | | | | | 0.94 |
| 10/15/2016 | Angel Trujillo | 74470970 | 74555552 | 84,582 | 0.084582 | 7.41 | 1.480 | | | | | | | | | 1.04 |
| 10/16/2016 | Angel Trujillo | 74555552 | 74630410 | 74,858 | 0.074858 | 7.40 | 1.480 | | | | | | | | | 0.92 |
| 10/17/2016 | Angel Trujillo | 74630410 | 74705268 | 74,858 | 0.074858 | 7.41 | 1.480 | | | | | | | | | 0.92 |
| 10/18/2016 | Angel Trujillo | 74705268 | 74780890 | 75,622 | 0.075622 | 7.46 | 1.480 | | | | | | | | | 0.93 |
| 10/19/2016 | Angel Trujillo | 74780890 | 74858587 | 77,697 | 0.077697 | 7.47 | 1.480 | | | | | | | | | 0.96 |
| 10/20/2016 | Angel Trujillo | 74858587 | 74937348 | 78,761 | 0.078761 | 7.51 | 1.480 | | | | | | | | | 0.97 |
| 10/21/2016 | Angel Trujillo | 74937348 | 75014720 | 77,372 | 0.077372 | 7.37 | 1.480 | | | | | | | | | 0.96 |
| 10/22/2016 | Angel Trujillo | 75014720 | 75098742 | 84,022 | 0.084022 | 7.55 | 1.480 | | | | | | | | | 1.04 |
| 10/23/2016 | Angel Trujillo | 75098742 | 75175023 | 76,281 | 0.076281 | 7.30 | 1.480 | | | | | | | | | 0.94 |
| 10/24/2016 | Angel Trujillo | 75175023 | 75251304 | 76,281 | 0.076281 | 7.43 | 1.480 | | | | | | | | | 0.94 |
| 10/25/2016 | Angel Trujillo | 75251304 | 75329662 | 78,358 | 0.078358 | 7.49 | 1.480 | | | | | | | | | 0.97 |
| 10/26/2016 | Angel Trujillo | 75329662 | 75407004 | 77,342 | 0.077342 | 7.44 | 1.480 | | | | | | | | | 0.95 |
| 10/27/2016 | Angel Trujillo | 75407004 | 75484996 | 77,992 | 0.077992 | 7.40 | 1.480 | | | | | | | | | 0.96 |
| 10/28/2016 | Angel Trujillo | 75484996 | 75564766 | 79,770 | 0.07977 | 7.52 | 1.480 | | | | | | | | | 0.98 |
| 10/29/2016 | Angel Trujillo | 75564766 | 75646364 | 81,598 | 0.081598 | 7.51 | 1.480 | | | | | | | | | 1.01 |
| 10/30/2016 | Angel Trujillo | 75646364 | 75723099 | 76,735 | 0.076735 | 7.30 | 1.480 | | | | | | | | | 0.95 |
| 10/31/2016 | Angel Trujillo | 75723099 | 75799834 | 76,735 | 0.076735 | 7.39 | 1.480 | | | | | | | | | 0.95 |
| TOTAL | | | | 2,421,276 | 2.421276 | | | <5.1 | 5.9 | | <0.010 | <0.030 | <0.010 | <0.0002 | <0.020 | |
| | | | High: | 84,582 | | | | | | | | | | | High: | 1.04 |
| | | | Average: | 78,106 | | | | | | | | | | | Average: | 0.96 |

WW

E

JC 29431

| Accutest Labs | | |

SGS Accutest LabLink@934243 14:51 09-Nov-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101116-A | | |
| Lab Sample ID: | JC29431-1 | Date Sampled: | 10/11/16 |
| Matrix: | AQ - Water | Date Received: | 10/11/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

Total Metals Analysis

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Chromium | 1480 | 10 | ug/l | 1 | 10/12/16 | 10/13/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Copper | < 10 | 10 | ug/l | 1 | 10/12/16 | 10/13/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Lead [a] | < 30 | 30 | ug/l | 10 | 10/12/16 | 10/13/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Mercury | < 0.20 | 0.20 | ug/l | 1 | 10/13/16 | 10/13/16 | JPM | EPA 245.1 [1] | EPA 245.1 [4] |
| Nickel | < 10 | 10 | ug/l | 1 | 10/12/16 | 10/13/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |
| Zinc | < 20 | 20 | ug/l | 1 | 10/12/16 | 10/13/16 | ND | EPA 200.7 [2] | EPA 200.7 [3] |

(1) Instrument QC Batch: MA40513
(2) Instrument QC Batch: MA40520
(3) Prep QC Batch: MP96496
(4) Prep QC Batch: MP96513

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

SGS Accutest LabLink@934243 14:51 09-Nov-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101116-A | | |
| Lab Sample ID: | JC29431-1 | Date Sampled: | 10/11/16 |
| Matrix: | AQ - Water | Date Received: | 10/11/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Solids, Total Suspended | < 4.0 | 4.0 | mg/l | 1 | 10/13/16 12:45 | RI | SM2540 D-11 |
| pH [a] | 6.94 | | su | 1 | 10/11/16 18:24 | JM | SM4500H+ B-11 |

(a) Sample received out of holding time for pH analysis.

RL = Reporting Limit

SGS Accutest LabLink@934243 14:51 09-Nov-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101116-A | | |
| Lab Sample ID: | JC29431-1A | Date Sampled: | 10/11/16 |
| Matrix: | AQ - Water | Date Received: | 10/11/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| BOD, 5 Day | 5.9 | 5.0 | mg/l | 1 | 10/11/16 20:58 | LS | SM5210 B-11 |

RL = Reporting Limit

SGS Accutest LabLink@934243 14:51 09-Nov-2016

# Report of Analysis





| | | | | |
|---|---|---|---|---|
| Client Sample ID: | 087-WWE-101116-B | | | |
| Lab Sample ID: | JC29431-2 | | Date Sampled: | 10/11/16 |
| Matrix: | AQ - Water | | Date Received: | 10/11/16 |
| Method: | EPA 624 | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | | |

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 [a] | T220132.D | 1 | 10/12/16 | BK | n/a | n/a | VT9043 |
| Run #2 | | | | | | | |

| | Purge Volume |
|---|---|
| Run #1 | 5.0 ml |
| Run #2 | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 107-02-8 | Acrolein | ND | 10 | 1.3 | ug/l | |
| 107-13-1 | Acrylonitrile | ND | 10 | 1.2 | ug/l | |
| 542-88-1 | Bis(chloromethyl)ether | IND | | | ug/l | |
| 71-43-2 | Benzene | 4.2 | 1.0 | 0.11 | ug/l | |
| 75-27-4 | Bromodichloromethane | ND | 1.0 | 0.14 | ug/l | |
| 75-25-2 | Bromoform | ND | 1.0 | 0.15 | ug/l | |
| 74-83-9 | Bromomethane | ND | 1.0 | 0.20 | ug/l | |
| 56-23-5 | Carbon tetrachloride | 3.9 | 1.0 | 0.19 | ug/l | |
| 108-90-7 | Chlorobenzene | 0.23 | 1.0 | 0.12 | ug/l | J |
| 75-00-3 | Chloroethane | ND | 1.0 | 0.19 | ug/l | |
| 110-75-8 | 2-Chloroethyl vinyl ether | ND | 5.0 | 0.73 | ug/l | |
| 67-66-3 | Chloroform | 26.5 | 1.0 | 0.11 | ug/l | |
| 74-87-3 | Chloromethane | ND | 1.0 | 0.22 | ug/l | |
| 124-48-1 | Dibromochloromethane | ND | 1.0 | 0.22 | ug/l | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.19 | ug/l | |
| 95-50-1 | 1,2-Dichlorobenzene | 0.35 | 1.0 | 0.15 | ug/l | J |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.15 | ug/l | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.13 | ug/l | |
| 75-71-8 | Dichlorodifluoromethane | ND | 2.0 | 0.54 | ug/l | |
| 75-34-3 | 1,1-Dichloroethane | 0.46 | 1.0 | 0.16 | ug/l | J |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.21 | ug/l | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.22 | ug/l | |
| 156-59-2 | cis-1,2-Dichloroethene | 67.5 | 1.0 | 0.30 | ug/l | |
| 156-60-5 | trans-1,2-Dichloroethene | 3.1 | 1.0 | 0.14 | ug/l | |
| 78-87-5 | 1,2-Dichloropropane | ND | 1.0 | 0.17 | ug/l | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 1.0 | 0.16 | ug/l | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 1.0 | 0.17 | ug/l | |
| 123-91-1 | 1,4-Dioxane | ND | 130 | 27 | ug/l | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.11 | ug/l | |
| 151-56-4 | Ethylenimine | IND | | | ug/l | |
| 75-09-2 | Methylene chloride | 0.80 | 1.0 | 0.16 | ug/l | J |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 1.0 | 0.18 | ug/l | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@934243 14:51 09-Nov-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101116-B | | |
| Lab Sample ID: | JC29431-2 | Date Sampled: | 10/11/16 |
| Matrix: | AQ - Water | Date Received: | 10/11/16 |
| Method: | EPA 624 | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |

VOA TVO List

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 127-18-4 | Tetrachloroethene | ND | 1.0 | 0.17 | ug/l | |
| 108-88-3 | Toluene | ND | 1.0 | 0.12 | ug/l | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 1.0 | 0.17 | ug/l | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 1.0 | 0.18 | ug/l | |
| 79-01-6 | Trichloroethene | 62.9 | 1.0 | 0.16 | ug/l | |
| 75-69-4 | Trichlorofluoromethane | ND | 2.0 | 0.55 | ug/l | |
| 75-01-4 | Vinyl chloride | ND | 1.0 | 0.19 | ug/l | |
| 1330-20-7 | Xylenes (total) | ND | 1.0 | 0.24 | ug/l | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 17060-07-0 | 1,2-Dichloroethane-D4 (SUR) | 99% | | 72-125% |
| 2037-26-5 | Toluene-D8 (SUR) | 99% | | 78-119% |
| 460-00-4 | 4-Bromofluorobenzene (SUR) | 102% | | 74-115% |
| 1868-53-7 | Dibromofluoromethane (S) | 100% | | 79-120% |

(a) Results reported from the HCl preserved sample. This reported result can only be used for screening purposes for acrolein and acrylonitrile.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@934243 14:51 09-Nov-2016

# Report of Analysis



| | | | |
|---|---|---|---|
| Client Sample ID: | 087-WWE-101116-B | | |
| Lab Sample ID: | JC29431-2 | Date Sampled: | 10/11/16 |
| Matrix: | AQ - Water | Date Received: | 10/11/16 |
| | | Percent Solids: | n/a |
| Project: | PESNJP: Hudson County, Jersey City, NJ | | |



General Chemistry

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| HEM Petroleum Hydrocarbons | < 5.1 | 5.1 | mg/l | 1 | 10/13/16 14:25 | TT | EPA 1664A |

RL = Reporting Limit

## Attachment 14: SA-6 North & South Design Change Tracking Log

| SA-6 North/South Field Change Log | | |
|---|---|---|
| **Changed Item Identifier** | **Description of Change** | **Comments** |
| **DC 2013-7-29** | Surcharge Monitoring Plan modifications to match changes associated with relocation of the hydraulic barrier wall near the 72" force main. 72-Inch Force Main Monitoring Layout Plan, Details, and Notes developed. Surcharge pile layout redesign and instrumentation adjustments. The format of the Daily Report, Instrumentation Installation Forms, and Monitoring Data Forms has been modified to allow for generation using a "tablet application". | Submitted to all Parties on March 12, 2014. |
| **DC 2013-8-14** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. |
| **DC 2013-9-24** | Testing frequency for analytic parameters for imported borrow material is to be modified to 1 test/5,000 CY of borrow. | Honeywell directive to be more conservative than 100% Design. Submitted to Contractor only as clarification or response to RFI. |
| **DC 2014-3-25** | Change Contingent GW system from wells to trench on both SA-6 S and SA-6N. | Submitted to all Parties on March 25, 2014 and April 23, 2014. |
| **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. |
| **DC 2016-6-6** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 004. (Design Change ID changed from DC 2016-6-10 to DC 2016-6-6 to reflect actual date on Design Change form). |
| **DC 2015-2-24** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-5-24 was issued to document the changes in the SA-6 North and South cap subgrades that resulted from the change to a trench system. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. |
| **DC 2014-8-13** | Revised hydraulic barrier wall alignment through the sedimentation basin to reduce potential conflict with existing timber piles. | Submitted to all Parties on August 19, 2014. |
| **DC 2014-9-2** | Revised hydraulic barrier wall alignment adjacent the 72" force main in order to provide a clearance of 25 ft. between the centerline of the 72" force main and the barrier wall as previously agreed with PVSC. | Submitted to all Parties on September 4, 2014. |
| **DC 2014-10-31** | Revised Soil Management Plan (Appendix G - SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused as backfill or placed underneath the cap.<br>Contractor directed to consolidate arsenic-impacted asphalt in Cap Areas in a footprint that does not exceed 44,000 SF and to cover the asphalt with chromium-impacted soil. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-01-22** | In accordance with the 100% Design, the Contractor is directed to remove 0-2 feet of <20 mg/kg overburden historic fill soils from selected locations throughout the SA-6 North Open Space Area. This will create a nominal 10,000 to 12,000 cubic yards (CY) additional capacity under the SA-6 North liner without affecting final grades for the liner or cover soils. The SMP allows such soils that are confirmed to be below 20 mg/kg for hexavalent chromium, to be used as temporary surcharge in the cap areas, backfill for excavations, or to raise the grades for the Redevelopment Project outside of the cap areas. In the space created by this removal of the 0-2 feet of historic fill soils from selected locations throughout the SA-6 North Open Space Area, the Contractor will relocate an additional estimated 10,000 to 12,000 CY worth of 20-240 mg/kg hexavalent chromium soils currently staged at SA-6 South. | Submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-03-03** | Mueser Rutledge Consulting Engineers (MRCE) have revised the design for temporary excavation support in SA-6 North along Route 440. Revised drawings SN-501, SN-502, SN-503, SN-504, and SN-505 are included in this Design Change Bulletin. | Submitted to Contractor and BMUA/JCMUA. Submitted to all Parties on May 27, 2015. |
| **DC 2015-03-30** | A pile cap was encountered during pre-trenching at the general location of the demolished Waste Management Garage. An alternatives evaluation was conducted and it was concluded that the least risk option was to re-align the wall to the south effectively resulting in a decrease in the cap area and an increase in the EA-5 Excavation. | Submitted to all Parties on May 27, 2015. |

| SA-6 North/South Field Change Log | | |
|---|---|---|
| **Changed Item Identifier** | **Description of Change** | **Comments** |
| **DC 2015-03-09** | The utility pole relocations along Route 440 require the installation of new poles in the DOT Right of Way along Route 440. The DCB includes the pole sleeve construction details and locations. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-04-30** | A concrete protuberance was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-05-19** | Supply and installation of specific components related to the contingent groundwater system will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6 North and SA-6 South. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 |
| **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on June 22, 2015. |
| **DC 2015-07-31** | The sheet pile pair is located at Sta. 0+50. Driving was stopped with a top elevation of +12.8 and a tip of -2.2. The top of meadow mat is at elevation +0.5. In accordance with the 100% Design Report (10.1.3 Bottom Key), the tip of the sheet shall be embedded a minimum of 2' into the Stratum D. The tip of the sheet is embedded 2.7 ft. and therefore meets the design criteria which was established in accordance with the requirements of the Consent Decree. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-08-19** | Entact notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring). As an option Entact proposed installing a standard direct burial utility marking tape. AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. | Submitted to Parties on August 27, 2015. |
| **DC 2015-08-21** | The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longer required and therefore the following is deleted in its entirety. | Submitted to Parties on August 27, 2015. |
| **DC 2015-9-02** | As identified in the 100% Design, ENTACT should now remove approximately 2 ft. of historic fill from the post surcharge removal surface of Area 1N to create capacity for 20-240 mg/kg chromium impacted soils. Excavated Soils will be sampled and analyzed according to the Soil Management Plan. Should any excavated historic fill exceed the 20 mg/kg criteria, it will be placed under the cap. | Submitted to Parties as Attachment to Declaration 004. |
| **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. |
| **DC 2015-9-04** | EA-8 boundaries have been revised to reflect additional sampling following initial excavation as defined in the 100% Design. The internal boundaries delineating the different soil disposition based on hexavalent chromium content have been revised. The revisions are minor in nature and are based on using a means of interpolation between sample points that is consistent with that used on SA-6S. | Submitted to Parties as Attachment to Declaration 003. |

| SA-6 North/South Field Change Log | | |
|---|---|---|
| **Changed Item Identifier** | **Description of Change** | **Comments** |
| **DC 2015-11-18** | Drawing CN-118 has been revised to show additional excavation in EA-8 as outlined in DC 2015-09-04. In addition, review of DC 2015-09-04 indicated a small area where the 20 - 240 ppm hatch had not been carried to the outer limit of excavation. The hatch mark has been corrected in CN-118 revision 2. | Submitted to Parties as Attachment to Declaration 003. |
| **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. |
| **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only as clarification or response to RFI. |
| **DC 2015-12-14** | Specification 02372, Sections 3.03 – Geomembrane Placement, C. Liner Boots and 3.06 – Field Quality Control, B. Nondestructive Seam Testing have been amended to include spark testing of extrusion welds that cannot be tested by other means. Spark testing will be performed in accordance with ASTM D6365 - Standard Practice for the Non Destructive Testing of Geomembrane Seams using the Spark Test. In addition, GRI-19 - Specification Seam Strength & Related Properties of Thermally Bonded Polyolefin Geomembrane was added as a reference document. The Specification also requires preparation of a Spark Testing form for each location that Spark Testing is used, to be signed by the Independent Geosynthetics QA representative.<br>Agreement was reached between Honeywell and the Plaintiffs to implement Spark Testing on SA-6N. Specification 02372 has been revised accordingly. | Submitted to Parties on January 14, 2016. |
| **DC 2015-11-30** | EA 2&3 external boundaries remain consistent with the Issued for Construction Design. Internal waste classification boundaries required adjustment to clarify the limits in three small triangular areas within the main excavation. A complete set of EA 2&3 Drawings and AutoCAD Files have been included showing all intervals. EA-8 Issued for Construction defined excavation limits from the surface to elevation 7. Upon reaching elevation 7 supplemental sampling was conducted and excavation conducted based on those results. Observation of excavation faces revealed a suspect area that subsequent testing verified required removal. A further round of supplemental sampling established new excavation limits. A detail is shown on the Interval 6 drawing showing the extent of extra excavation required. | Submitted to Parties as Attachment to Declaration 003. |
| **DC 2016-02-02** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Parties as Attachment to Declaration 004. (Design Change ID changed from DC 2016-02-03 to DC 2016-02-02 to reflect actual date on Design Change form). |
| **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only as clarification or response to RFI. |

| SA-6 North/South Field Change Log | | |
|---|---|---|
| **Changed Item Identifier** | **Description of Change** | **Comments** |
| **DC 2016-03-18** | This DC 2016-03-18 documents the revised acceptable ranges of physical parameters and provides an updated specification made in consultation with Dr. Grabosky of Rutgers University. Dr. Grabosky provided his recommendations in correspondence dated 3/17/2016. | Submitted to Parties on March 22, 2016. Plaintiffs responded in a letter dated April 15, 2016. Plaintiffs and Honeywell subsequently held discussions and DCB 2016-04-20 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. |
| **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. |
| **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. |
| **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | Submitted to Parties as Attachment to Declaration 004. |
| **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. |
| **DC 2016-7-14** | Design change documenting minor grading adjustments to improvements to drainage off of the SA6N Open Space Area. | DCB will be provided to Parties in the November 2016 monthly progress report and included in the finalized Declaration No. 4. |
| **DC 2016-7-12** | DC 2016-7-12 clarifies the limit of GCL deployment and the location of the sand bentonite plug in the SA-6 North cap. | Included as an attachment to July 2016 Monthly Progress Report. |

**DCB-2016-7-14: North Cap – Field Engineered Subgrade Adjustments**
*(Attachment 14: SA-6 North & South Design Change Tracking Log)*

Honeywell RES

Honeywell.com

PDESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** **Type:** Minor(a)<br>**Effective Date:** 7/14/16 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** North Cap - Field Engineered Subgrade Adjustments | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description.**

During the course of subgrade construction two field conditions were identified that resulted in the need for minor adjustments to several small localized areas of the subgrade to achieve positive drainage. In one area these field developed changes resulted in a change in elevation of the Construction Control Grid subgrade elevation.

In addition there were several minor changes in the top elevation of the Hydraulic Barrier wall. These changes were made to avoid major changes to the Construction Water Treatment forcemain and to address several locations where the final top elevations of driven sheets were slightly below the design levels. These changes did result in a very small reduction in capacity under the cap and had no impact on the containment and hydraulic requirements of the wall. The changes are so minor they are not readily visible on the hard copy drawings. Revisions were issued to Entact in electronic format and will be incorporated in As Built documentation.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Construction Control Grid<br>Top of Barrier Wall and Subgrade |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 12/12/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




153 16.66 GRID POINT
2054 17.00 BREAK POINT
1157 12.31 BOUND POINT

NOTE: REFER TO FIGURE 1.3 FOR REVISED GRID POINT ELEVATION SUMMARY TABLE.

0 10 20 40
SCALE IN FEET

DCB 054.5 – REVISED CONTROL GRID ELEVATIONS 12/12/16

Prepared/Date: RJR 05/12/16
Checked/Date: TDD 05/12/16

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 NORTH<br>JERSEY CITY, NEW JERSEY<br>HONEYWELL SITE ID - 37472 | amec foster wheeler<br>Environment & Infrastructure, Inc.<br>200 American Metro Blvd, Suite 113<br>Hamilton, NJ, 08619, (609) 689 - 2829<br>NJ Certificate of Authorization Number 24GA28019300 | SA-6 NORTH CONSTRUCTION CONTROL GRID<br>FIGURE 1 OF 3<br>Project 3480-13-0377<br>Figure 1.1 |

C:\Donovan\SA- 6 North\2013 Excavation Surfaces\SA- 6 North Cap Surveys\Figure - Survey Control Grid.dwg Mon, 12 Dec 2016 - 12:46pm tony.donovan

NOTE: REFER TO FIGURE 1.3 FOR REVISED GRID POINT ELEVATION SUMMARY TABLE.

153 16.66 GRID POINT

2054 17.00 BREAK POINT

1157 12.31 BOUND POINT

0 10 20 40
SCALE IN FEET

DCB 054.5 – REVISED CONTROL GRID ELEVATIONS 12/12/16

Prepared/Date: RJR 05/12/16
Checked/Date: TDD 05/12/16

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019600

SA-6 NORTH CONSTRUCTION CONTROL GRID
FIGURE 2 OF 3
Project 3480-13-0377
Figure 1.2

C:\Donovan\SA-6 North\2013 Excavation Surfaces\SA-6 North Cap Surveys\Figure - Survey Control Grid.dwg Mon, 12 Dec 2016 - 12:45pm tony.donovan

**DCB 054.5 - REVISED SUBGRADE ELEVATION SUMMARY**

| CONTROL GRID POINT ID | DESCRIPTION | SUBGRADE DESIGN ELEV (FT) | REVISED SUBGRADE DESIGN ELEV (FT) |
|---|---|---|---|
| 160 | GRID | 17.62 | 17.44 |
| 161 | GRID | 17.65 | 17.39 |
| 533 | GRID | 10.17 | 10.88 |
| 1044 | BNDY | 18.03 | 16.59 |
| 1055 | BNDY | 11.84 | 11.43 |
| 1070 | BNDY | 14.78 | 13.85 |
| 1071 | BNDY | 14.27 | 14.01 |
| 1107 | BNDY | 8.55 | 10.75 |
| 1108 | BNDY | 8.50 | 10.75 |
| 1109 | BNDY | 8.86 | 10.75 |
| 1110 | BNDY | 9.63 | 10.75 |
| 1111 | BNDY | 9.76 | 10.75 |
| 1112 | BNDY | 9.94 | 10.75 |
| 1113 | BNDY | 10.18 | 10.75 |
| 1114 | BNDY | 10.43 | 10.75 |
| 1115 | BNDY | 10.68 | 10.75 |
| 1136 | BNDY | 8.98 | 9.65 |
| 1184 | BNDY | 8.50 | 10.75 |

153 16.66 GRID POINT
2054 17.00 BREAK POINT
1157 12.31 BOUND POINT

0 10 20 40
SCALE IN FEET

DCB 054.5 – REVISED CONTROL GRID ELEVATIONS 12/12/16

Prepared/Date: RJR 05/12/16
Checked/Date: TDD 05/12/16

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

SA-6 NORTH CONSTRUCTION CONTROL GRID
FIGURE 3 OF 3
Project 3480-13-0377
Figure 1.3

O:\Donovan\SA-6 North\2013 Excavation Surfaces\SA-6 North Cap Surveys\Figure - Survey Control Grid.dwg Mon, 12 Dec 2016 - 12:43pm tony.donovan

## Attachment 15: EME Soils

**10/13/16 Honeywell Corr: New Source of Horizon A Topsoil - SA-6**
*(Attachment 15: EME Soils)*
*Included in electronic copy only*

Honeywell
115 Tabor Road
Morris Plains, NJ 07950

October 13, 2016 ***via Electronic Mail***

The Honorable Robert G. Torricelli
Office of the Special Master
*RGTSpecialMaster@aol.com*

**Re: New Source of Horizon A Topsoil**
**Study Area 6 (SA-6)**
**Jersey City, New Jersey**

Dear Senator Torricelli:

Honeywell is preparing this letter to advise the parties that we have identified a new fill material from the Excavating Materials & Equipment, Inc. quarry in New Egypt, NJ, which can be used at SA-6 for Horizon A topsoil needs. A clean fill certification and mine registration certificate are provided in Attachment A.

Although the fill material is certified by the quarry, an analytical sample was collected and compared to the NJDEP Residential Soil Remediation Standards. The soil sample was analyzed for VOCs, SVOCs, PCBs, pesticides, metals, cyanide, and hexavalent Cr.

All the data was found to meet NJDEP unrestricted use criteria and the hexavalent Cr was found to be < 1 mg/kg. Consistent with our prior practice, we are providing the parties with a copy of the final laboratory data package, which includes the Horizon A topsoil sample collected by Amec Foster Wheeler, WOOLSTON-TS-002.

In addition, Amec Foster Wheeler collected a geotechnical sample to confirm that the material meets the topsoil specifications in the approved 100% Design and DC 2015-09-17 (provided to Parties in a letter dated September 23, 2015). Amec Foster Wheeler found that the materials meet the topsoil specifications. A copy of the geotechnical data is also attached to this letter (Attachment B).

Should you have any questions please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Global Director, Remediation
Design and Construction

WJH:egc/sgf

Encl.: Attachment A: Clean Fill Certification/ Mine Registration Certificate/
WOOLSTON-TS-002 Sample Results
Attachment B: Geotechnical Results - Rutgers Soil Testing Laboratory

cc: (electronic copy only)
Joe Clifford - Amec Foster Wheeler
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
Tom Byrne - Honeywell
Maria Kaouris - Honeywell
John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.
Mary Hogan - Walsh Pizzi O'Reilly Falanga LLP
Hector Ruiz - Walsh Pizzi O'Reilly Falanga LLP
Liza Walsh - Walsh Pizzi O'Reilly Falanga LLP

# ATTACHMENT A

# CLEAN FILL CERTIFICATION/ MINE REGISTRATION CERTIFICATE/ WOOLSTON-TS-002 LAB RESULTS

EXCAVATING MATERIALS & EQUIPMENT, INC.
849 ROUTE 539 • NEW EGYPT, NJ 08533 • 609.758.3400 • FAX: 609.758.5545

10-12-16

**GENERAL CONTRACTOR : Entach Corp**

**CERTIFICATION:** Clean Fill Certification

**PROJECT: Honeywell Jersey City NJ.**

Please accept this letter as our certification that the Clean Fill to be supplied to you through EME for the above referenced project is produced at our Plumsted Township Plant located at 849 Route 539, New Egypt, NJ 08533. Block 80 lot 4.

The material provided from our pit is:
Excavated from undisturbed geologic formations;
Obtained from a licensed quarry/mine;
Not been subject to a discharged hazardous substance at any time;
Not located on or impacted by other contaminant sources;
Not comingled with any other materials;
Not known or suspected of being contaminated.
Not adversely impacted by discharges of hazardous materials or chemical applications;
Not affected by conditions or processes that would result in the introduction of contaminates into the licensed quarry/mine material in concentrations above regulatory concern; and
Not affected by conditions or processes that would increase the concentrations of contaminants already present in the licensed quarry/mine to concentrations above regulatory concern.
Also please find a copy of our state mine registration.

If you need any further assistance, please feel free to contact me.

Sincerely,

Keith Prince
Vice President

State of New Jersey
Department of Labor and Workforce Development

Certificate No. 004218
Expiration Date 3/31/2017

# MINE REGISTRATION CERTIFICATE

ISSUED TO: EME Inc

LOCATION: 849 Route 539
New Egypt, NJ

BLK NO(S): 80
LOT NO(S): 4
COUNTY: Ocean

Issued pursuant to the provisions of N.J.S.A. 34:6-98.1 et. seq. Failure to comply with the provisions of the Act, and the Rules promulgated thereunder, shall be good cause for the revocation of this Certificate.

Harold J. Wirths
Commissioner

THIS CERTIFICATE MUST BE POSTED AT ALL TIMES

ES 140 (R-1-05)

| SGS Accutest New Jersey | | | | | 10/12/2016 7:08 |
|---|---|---|---|---|---|
| Job Number: | JC28902 | | | | |
| Account: | Honeywell International Inc. | | | | |
| Project: | HLANJPR: Study Area 6 Chrome Remedy | | | | |
| Project Number: | | | | | |
| Results flagged as "Exceed" if any of the selected criteria exceeded (most stringent). | | | Legend: | Hit | Exceed |
| Client Sample ID: | | NJ Residential Direct Contact Soil (NJAC 7: 26D 5/12)[1] | NJ Default Impact to Groundwater Soil Screening (NJAC 7:26D 11/13) | WOOLSTON-TS-002 | WOOLSTON-TS-002 |
| Lab Sample ID: | | | | JC28902-1 | JC28902-1R |
| Date Sampled: | | | | 10/4/2016 | 10/4/2016 |
| Matrix: | | | | Soil | Soil |
| **GC/MS Volatiles (SW846 8260C)** | | | | | |
| Acetone | ug/kg | 70000000 | 19000 | ND (9.6) | - |
| Benzene | ug/kg | 2000 | 5 | ND (0.23) | - |
| Bromochloromethane | ug/kg | - | - | ND (0.61) | - |
| Bromodichloromethane | ug/kg | 1000 | 5 | ND (0.29) | - |
| Bromoform | ug/kg | 81000 | 30 | ND (0.51) | - |
| Bromomethane | ug/kg | 25000 | 40 | ND (0.93) | - |
| 2-Butanone (MEK) | ug/kg | 3100000 | 900 | ND (3.4) | - |
| Carbon disulfide | ug/kg | 7800000 | 6000 | ND (0.33) | - |
| Carbon tetrachloride | ug/kg | 600 | 5 | ND (0.32) | - |
| Chlorobenzene | ug/kg | 510000 | 600 | ND (0.31) | - |
| Chloroethane | ug/kg | 220000 | NA | ND (0.83) | - |
| Chloroform | ug/kg | 600 | 400 | ND (0.46) | - |
| Chloromethane | ug/kg | 4000 | NA | ND (0.41) | - |
| Cyclohexane | ug/kg | - | - | ND (1.1) | - |
| 1,2-Dibromo-3-chloropropane | ug/kg | 80 | 5 | ND (0.93) | - |
| Dibromochloromethane | ug/kg | 3000 | 5 | ND (0.29) | - |
| 1,2-Dibromoethane | ug/kg | 8 | 5 | ND (0.47) | - |
| 1,2-Dichlorobenzene | ug/kg | 5300000 | 17000 | ND (0.33) | - |
| 1,3-Dichlorobenzene | ug/kg | 5300000 | 19000 | ND (0.26) | - |
| 1,4-Dichlorobenzene | ug/kg | 5000 | 2000 | ND (0.29) | - |
| Dichlorodifluoromethane | ug/kg | 490000 | 39000 | ND (1.1) | - |
| 1,1-Dichloroethane | ug/kg | 8000 | 200 | ND (0.36) | - |
| 1,2-Dichloroethane | ug/kg | 900 | 5 | ND (0.33) | - |
| 1,1-Dichloroethene | ug/kg | 11000 | 8 | ND (0.29) | - |
| cis-1,2-Dichloroethene | ug/kg | 230000 | 300 | ND (0.84) | - |
| trans-1,2-Dichloroethene | ug/kg | 300000 | 600 | ND (0.30) | - |
| 1,2-Dichloropropane | ug/kg | 2000 | 5 | ND (0.60) | - |
| cis-1,3-Dichloropropene | ug/kg | 2000 | 5 | ND (0.38) | - |
| trans-1,3-Dichloropropene | ug/kg | 2000 | 5 | ND (0.43) | - |
| Ethylbenzene | ug/kg | 7800000 | 13000 | ND (0.29) | - |
| Freon 113 | ug/kg | - | - | ND (0.93) | - |
| 2-Hexanone | ug/kg | - | - | ND (2.7) | - |
| Isopropylbenzene | ug/kg | - | - | ND (0.30) | - |
| Methyl Acetate | ug/kg | 78000000 | 22000 | ND (3.9) | - |
| Methylcyclohexane | ug/kg | - | - | ND (0.97) | - |
| Methyl Tert Butyl Ether | ug/kg | 110000 | 200 | ND (0.51) | - |
| 4-Methyl-2-pentanone(MIBK) | ug/kg | - | - | ND (1.6) | - |
| Methylene chloride | ug/kg | 34000 | 10 | ND (1.9) | - |
| Styrene | ug/kg | 90000 | 3000 | ND (0.28) | - |
| 1,1,2,2-Tetrachloroethane | ug/kg | 1000 | 7 | ND (0.46) | - |
| Tetrachloroethene | ug/kg | 2000 | 5 | ND (0.54) | - |
| Toluene | ug/kg | 6300000 | 7000 | ND (0.24) | - |
| 1,2,3-Trichlorobenzene | ug/kg | - | - | ND (0.44) | - |
| 1,2,4-Trichlorobenzene | ug/kg | 73000 | 700 | ND (0.35) | - |
| 1,1,1-Trichloroethane | ug/kg | 290000 | 300 | ND (0.32) | - |
| 1,1,2-Trichloroethane | ug/kg | 2000 | 20 | ND (0.62) | - |
| Trichloroethene | ug/kg | 7000 | 10 | ND (0.37) | - |
| Trichlorofluoromethane | ug/kg | 23000000 | 34000 | ND (1.2) | - |
| Vinyl chloride | ug/kg | 700 | 5 | ND (0.39) | - |
| m,p-Xylene | ug/kg | 12000000 | 19000 | ND (0.42) | - |
| o-Xylene | ug/kg | 12000000 | 19000 | ND (0.39) | - |
| Xylene (total) | ug/kg | 12000000 | 19000 | ND (0.39) | - |
| **GC/MS Volatile TIC** | | | | | |
| Total TIC, Volatile | ug/kg | - | - | 0 | - |
| Total Alkanes | ug/kg | - | - | 0 | - |
| **GC/MS Semi-volatiles (SW846 8270D)** | | | | | |
| 2-Chlorophenol | ug/kg | 310000 | 800 | ND (19) | - |
| 4-Chloro-3-methyl phenol | ug/kg | - | - | ND (23) | - |
| 2,4-Dichlorophenol | ug/kg | 180000 | 200 | ND (32) | - |
| 2,4-Dimethylphenol | ug/kg | 1200000 | 1000 | ND (68) | - |
| 2,4-Dinitrophenol | ug/kg | 120000 | 300 | ND (140) | - |
| 4,6-Dinitro-o-cresol | ug/kg | 6000 | 300 | ND (41) | - |
| 2-Methylphenol | ug/kg | 310000 | NA | ND (24) | - |
| 3&4-Methylphenol | ug/kg | - | - | ND (31) | - |
| 2-Nitrophenol | ug/kg | - | - | ND (25) | - |
| 4-Nitrophenol | ug/kg | - | - | ND (100) | - |
| Pentachlorophenol | ug/kg | 3000 | 300 | ND (36) | - |
| Phenol | ug/kg | 18000000 | 8000 | ND (20) | - |
| 2,3,4,6-Tetrachlorophenol | ug/kg | - | - | ND (25) | - |
| 2,4,5-Trichlorophenol | ug/kg | 6100000 | 68000 | ND (28) | - |
| 2,4,6-Trichlorophenol | ug/kg | 19000 | 200 | ND (23) | - |
| Acenaphthene | ug/kg | 3400000 | 110000 | ND (13) | - |
| Acenaphthylene | ug/kg | NA | NA | ND (19) | - |

| SGS Accutest New Jersey | | | | | 10/12/2016 7:08 |
|---|---|---|---|---|---|
| Job Number: | JC28902 | | | | |
| Account: | Honeywell International Inc. | | | | |
| Project: | HLANJPR: Study Area 6 Chrome Remedy | | | | |
| Project Number: | | | | | |
| Results flagged as "Exceed" if any of the selected criteria exceeded (most stringent). | | | Legend: | Hit | Exceed |
| Client Sample ID: | | NJ Residential Direct Contact Soil (NJAC 7: | NJ Default Impact to Groundwater | WOOLSTON-TS-002 | WOOLSTON-TS-002 |
| Lab Sample ID: | | 26D 5/12)[1] | Soil Screening | JC28902-1 | JC28902-1R |
| Date Sampled: | | | (NJAC 7:26D | 10/4/2016 | 10/4/2016 |
| Matrix: | | | 11/13) | Soil | Soil |
| Acetophenone | ug/kg | 2000 | 3000 | 15.8 J | - |
| Anthracene | ug/kg | 17000000 | 2400000 | ND (23) | - |
| Atrazine | ug/kg | 210000 | 200 | ND (16) | - |
| Benzo(a)anthracene | ug/kg | 600 | 800 | ND (11) | - |
| Benzo(a)pyrene | ug/kg | 200 | 200 | ND (17) | - |
| Benzo(b)fluoranthene | ug/kg | 600 | 2000 | ND (17) | - |
| Benzo(g,h,i)perylene | ug/kg | 380000000 | NA | ND (19) | - |
| Benzo(k)fluoranthene | ug/kg | 6000 | 25000 | ND (18) | - |
| 4-Bromophenyl phenyl ether | ug/kg | - | - | ND (15) | - |
| Butyl benzyl phthalate | ug/kg | 1200000 | 230000 | ND (9.3) | - |
| 1,1'-Biphenyl | ug/kg | 3100000 | 140000 | ND (5.2) | - |
| Benzaldehyde | ug/kg | 6100000 | NA | 11.3 J | - |
| 2-Chloronaphthalene | ug/kg | - | - | ND (9.1) | - |
| 4-Chloroaniline | ug/kg | - | - | ND (14) | - |
| Carbazole | ug/kg | 24000 | NA | ND (5.5) | - |
| Caprolactam | ug/kg | 31000000 | 12000 | ND (15) | - |
| Chrysene | ug/kg | 62000 | 80000 | ND (12) | - |
| bis(2-Chloroethoxy)methane | ug/kg | - | - | ND (8.1) | - |
| bis(2-Chloroethyl)ether | ug/kg | 400 | 200 | ND (16) | - |
| bis(2-Chloroisopropyl)ether | ug/kg | 23000 | 5000 | ND (14) | - |
| 4-Chlorophenyl phenyl ether | ug/kg | - | - | ND (12) | - |
| 2,4-Dinitrotoluene | ug/kg | 700 | NA | ND (12) | - |
| 2,6-Dinitrotoluene | ug/kg | 700 | NA | ND (19) | - |
| 3,3'-Dichlorobenzidine | ug/kg | 1000 | 200 | ND (32) | - |
| 1,4-Dioxane | ug/kg | - | - | ND (25) | - |
| Dibenzo(a,h)anthracene | ug/kg | 200 | 800 | ND (17) | - |
| Dibenzofuran | ug/kg | - | - | ND (15) | - |
| Di-n-butyl phthalate | ug/kg | 6100000 | 760000 | ND (6.2) | - |
| Di-n-octyl phthalate | ug/kg | 2400000 | 3300000 | ND (9.5) | - |
| Diethyl phthalate | ug/kg | 49000000 | 88000 | ND (8.1) | - |
| Dimethyl phthalate | ug/kg | - | - | ND (6.8) | - |
| bis(2-Ethylhexyl)phthalate | ug/kg | 35000 | 1200000 | ND (8.9) | - |
| Fluoranthene | ug/kg | 2300000 | 1300000 | ND (17) | - |
| Fluorene | ug/kg | 2300000 | 170000 | ND (17) | - |
| Hexachlorobenzene | ug/kg | 300 | 200 | ND (9.6) | - |
| Hexachlorobutadiene | ug/kg | 6000 | 900 | ND (15) | - |
| Hexachlorocyclopentadiene | ug/kg | 45000 | 320000 | ND (15) | - |
| Hexachloroethane | ug/kg | 35000 | 200 | ND (19) | - |
| Indeno(1,2,3-cd)pyrene | ug/kg | 600 | 7000 | ND (18) | - |
| Isophorone | ug/kg | 510000 | 200 | ND (8.1) | - |
| 2-Methylnaphthalene | ug/kg | 230000 | 8000 | ND (8.6) | - |
| 2-Nitroaniline | ug/kg | 39000 | NA | ND (9.0) | - |
| 3-Nitroaniline | ug/kg | - | - | ND (9.5) | - |
| 4-Nitroaniline | ug/kg | - | - | ND (9.8) | - |
| Naphthalene | ug/kg | 6000 | 25000 | ND (11) | - |
| Nitrobenzene | ug/kg | 31000 | 200 | ND (15) | - |
| N-Nitroso-di-n-propylamine | ug/kg | 200 | 200 | ND (11) | - |
| N-Nitrosodiphenylamine | ug/kg | 99000 | 400 | ND (14) | - |
| Phenanthrene | ug/kg | NA | NA | ND (13) | - |
| Pyrene | ug/kg | 1700000 | 840000 | ND (12) | - |
| 1,2,4,5-Tetrachlorobenzene | ug/kg | - | - | ND (9.7) | - |
| **GC/MS Semi-volatile TIC** | | | | | |
| Total TIC, Semi-Volatile | ug/kg | - | - | 41160 J | - |
| Total Alkanes | ug/kg | - | - | 600 J | - |
| **GC Semi-volatiles (NJDEP EPH)** | | | | | |
| EPH (C9-C28) | mg/kg | - | - | 88.4 | - |
| EPH (>C28-C40) | mg/kg | - | - | 358 | - |
| Total EPH (C9-C40) | mg/kg | - | - | 447 | - |
| **GC Semi-volatiles (SW846 8081B)** | | | | | |
| Aldrin | ug/kg | 40 | 200 | ND (1.2) | - |
| alpha-BHC | ug/kg | 100 | 2 | ND (1.3) | - |
| beta-BHC | ug/kg | 400 | 2 | ND (1.5) | - |
| delta-BHC | ug/kg | - | - | ND (1.1) | - |
| gamma-BHC (Lindane) | ug/kg | 400 | 2 | ND (1.1) | - |
| alpha-Chlordane | ug/kg | 200 | 50 | ND (1.2) | - |
| gamma-Chlordane | ug/kg | 200 | 50 | ND (1.1) | - |
| Chlordane (alpha and gamma) | ug/kg | 200 | 50 | ND (1.1) | - |
| Dieldrin | ug/kg | 40 | 3 | ND (1.2) | - |
| 4,4'-DDD | ug/kg | 3000 | 4000 | ND (1.6) | - |
| 4,4'-DDE | ug/kg | 2000 | 18000 | ND (1.3) | - |
| 4,4'-DDT | ug/kg | 2000 | 11000 | ND (1.5) | - |
| Endrin | ug/kg | 23000 | 1000 | ND (1.2) | - |
| Endosulfan sulfate | ug/kg | 470000 | 2000 | ND (0.99) | - |

| SGS Accutest New Jersey | | | | | 10/12/2016 7:08 |
|---|---|---|---|---|---|
| Job Number: | JC28902 | | | | |
| Account: | Honeywell International Inc. | | | | |
| Project: | HLANJPR: Study Area 6 Chrome Remedy | | | | |
| Project Number: | | | | | |
| Results flagged as "Exceed" if any of the selected criteria exceeded (most stringent). | | | Legend: | Hit | Exceed |
| Client Sample ID: | | NJ Residential Direct Contact Soil (NJAC 7: | NJ Default Impact to Groundwater | WOOLSTON-TS-002 | WOOLSTON-TS-002 |
| Lab Sample ID: | | 26D 5/12)[1] | Soil Screening | JC28902-1 | JC28902-1R |
| Date Sampled: | | | (NJAC 7:26D | 10/4/2016 | 10/4/2016 |
| Matrix: | | | 11/13) | Soil | Soil |
| Endrin aldehyde | ug/kg | - | - | ND (1.5) | - |
| Endosulfan-I | ug/kg | 470000 | 4000 | ND (1.3) | - |
| Endosulfan-II | ug/kg | 470000 | 4000 | ND (1.3) | - |
| Heptachlor | ug/kg | 100 | 500 | ND (1.2) | - |
| Heptachlor epoxide | ug/kg | 70 | 10 | ND (1.3) | - |
| Methoxychlor | ug/kg | 390000 | 160000 | ND (1.2) | - |
| Endrin ketone | ug/kg | - | - | ND (1.9) | - |
| Toxaphene | ug/kg | 600 | 300 | ND (26) | - |
| **GC Semi-volatiles (SW846 8082A)** | | | | | |
| Aroclor 1016 | ug/kg | 200 | 200 | ND (29) | - |
| Aroclor 1221 | ug/kg | 200 | 200 | ND (29) | - |
| Aroclor 1232 | ug/kg | 200 | 200 | ND (23) | - |
| Aroclor 1242 | ug/kg | 200 | 200 | ND (21) | - |
| Aroclor 1248 | ug/kg | 200 | 200 | ND (38) | - |
| Aroclor 1254 | ug/kg | 200 | 200 | ND (30) | - |
| Aroclor 1260 | ug/kg | 200 | 200 | ND (25) | - |
| Aroclor 1268 | ug/kg | 200 | 200 | ND (21) | - |
| Aroclor 1262 | ug/kg | 200 | 200 | ND (40) | - |
| **GC Semi-volatiles (SW846 8151)** | | | | | |
| 2,4-D | ug/kg | - | - | ND (17) | - |
| 2,4,5-TP (Silvex) | ug/kg | - | - | ND (2.7) | - |
| 2,4,5-T | ug/kg | - | - | ND (2.9) | - |
| Dalapon | ug/kg | - | - | ND (5.1) | - |
| Dicamba | ug/kg | - | - | ND (3.8) | - |
| Dichloroprop | ug/kg | - | - | ND (11) | - |
| Dinoseb | ug/kg | - | - | ND (25) | - |
| MCPA | ug/kg | - | - | ND (860) | - |
| MCPP | ug/kg | - | - | ND (820) | - |
| Pentachlorophenol | ug/kg | 3000 | 300 | ND (3.3) | - |
| 2,4-DB | ug/kg | - | - | ND (12) | - |
| **Metals Analysis** | | | | | |
| Aluminum | mg/kg | 78000 | 6000 | 3160 | - |
| Antimony | mg/kg | 31 | 6 | <2.3 | - |
| Arsenic | mg/kg | 19 | 19 | 5.4 | - |
| Barium | mg/kg | 16000 | 2100 | <23 | - |
| Beryllium | mg/kg | 16 | 0.7 | <0.23 | - |
| Cadmium | mg/kg | 78 | 2 | <0.58 | - |
| Calcium | mg/kg | - | - | 1380 | - |
| Chromium | mg/kg | - | - | 7.2 | - |
| Cobalt | mg/kg | 1600 | 90 | <5.8 | - |
| Copper | mg/kg | 3100 | 11000 | 3.5 | - |
| Iron | mg/kg | - | - | 7460 | - |
| Lead | mg/kg | 400 | 90 | 4.3 | - |
| Magnesium | mg/kg | - | - | 637 | - |
| Manganese | mg/kg | 11000 | 65 | 12.7 | - |
| Mercury | mg/kg | 23 | 0.1 | <0.038 | - |
| Nickel | mg/kg | 1600 | 48 | <4.6 | - |
| Potassium | mg/kg | - | - | <1200 | - |
| Selenium | mg/kg | 390 | 11 | <2.3 | - |
| Silver | mg/kg | 390 | 1 | <0.58 | - |
| Sodium | mg/kg | - | - | <1200 | - |
| Thallium | mg/kg | 5 | 3 | <1.2 | - |
| Vanadium | mg/kg | 78 | NA | 9.1 | - |
| Zinc | mg/kg | 23000 | 930 | <5.8 | - |
| **General Chemistry** | | | | | |
| Chromium, Hexavalent | mg/kg | - | - | <0.45 | <0.46 |
| Cyanide | mg/kg | 1600 | 20 | <0.23 | - |
| Redox Potential Vs H2 | mv | - | - | 302 | - |
| Solids, Percent | % | - | - | 86.5 | - |
| pH | su | - | - | 5.55 | - |

Regulatory limits listed in this document have been obtained from the latest version of the regulations cited and are used for advisory purposes only. SGS Accutest assumes no responsibility for errors in regulatory documents or changes to criteria detailed in later versions of the referenced regulation. It is the responsibility of the user to verify these limits before using or reporting any data.

No results exceeded regulatory criteria.

[1] NOTE: Soil Remediation Standards from June 2008 were incorporated in the May 2012 rule without change.

SGS ACCUTEST
New Jersey

10/12/16

SGS ACCUTEST IS PART OF SGS, THE WORLD'S LEADING INSPECTION, VERIFICATION, TESTING AND CERTIFICATION COMPANY.

*e-Hardcopy 2.0*
*Automated Report*



## Technical Report for

Honeywell International Inc.

HLANJPR: Study Area 6 Chrome Remedy

SGS Accutest Job Number: JC28902

Sampling Date: 10/04/16

Report to:

AMEC Environment & Infrastructure, Inc.

jenna.desiderio@amecfw.com

ATTN: Jenna Desiderio

Total number of pages in report: 349

NELAP ACCREDITED TNI LABORATORY

Test results contained within this data package meet the requirements of the National Environmental Laboratory Accreditation Program and/or state specific certification programs as applicable.

Nancy Cole
Laboratory Director

Client Service contact: Marty Vitanza 732-329-0200

Certifications: NJ(12129), NY(10983), CA, CT, FL, IL, IN, KS, KY, LA, MA, MD, ME, MN, NC, OH VAP (CL0056), AK (UST-103), AZ (AZ0786), PA, RI, SC, TX, UT, VA, WV, DoD ELAP (L-A-B L2248)

This report shall not be reproduced, except in its entirety, without the written approval of SGS Accutest.
Test results relate only to samples analyzed.



SGS Accutest is the sole authority for authorizing edits or modifications to this document.
Unauthorized modification of this report is strictly prohibited.

Sections: 1 2 3 4 5 6 7 8 9 10

# Table of Contents

-1-

**Section 1: Sample Summary** ..... **4**
**Section 2: Case Narrative/Conformance Summary** ..... **5**
**Section 3: Summary of Hits** ..... **9**
**Section 4: Sample Results** ..... **10**
**4.1:** JC28902-1: WOOLSTON-TS-002 ..... 11
**4.2:** JC28902-1R: WOOLSTON-TS-002 ..... 22
**Section 5: Misc. Forms** ..... **23**
**5.1:** Certification Exceptions ..... 24
**5.2:** Chain of Custody ..... 25
**5.3:** Sample Tracking Chronicle ..... 28
**5.4:** Internal Chain of Custody ..... 29
**Section 6: GC/MS Volatiles - QC Data Summaries** ..... **31**
**6.1:** Method Blank Summary ..... 32
**6.2:** Blank Spike Summary ..... 34
**6.3:** Matrix Spike Summary ..... 36
**6.4:** Duplicate Summary ..... 38
**6.5:** Instrument Performance Checks (BFB) ..... 40
**6.6:** Internal Standard Area Summaries ..... 42
**6.7:** Surrogate Recovery Summaries ..... 43
**6.8:** Initial and Continuing Calibration Summaries ..... 44
**Section 7: GC/MS Semi-volatiles - QC Data Summaries** ..... **55**
**7.1:** Method Blank Summary ..... 56
**7.2:** Blank Spike Summary ..... 65
**7.3:** Matrix Spike/Matrix Spike Duplicate Summary ..... 68
**7.4:** Instrument Performance Checks (DFTPP) ..... 71
**7.5:** Internal Standard Area Summaries ..... 83
**7.6:** Surrogate Recovery Summaries ..... 86
**7.7:** Initial and Continuing Calibration Summaries ..... 87
**Section 8: GC Semi-volatiles - QC Data Summaries** ..... **143**
**8.1:** Method Blank Summary ..... 144
**8.2:** Blank Spike Summary ..... 149
**8.3:** Matrix Spike/Matrix Spike Duplicate Summary ..... 153
**8.4:** Duplicate Summary ..... 157
**8.5:** Internal Standard Area Summaries ..... 158
**8.6:** DDT/Endrin Breakdown Checks ..... 160
**8.7:** GC Identification Summaries (Hits) ..... 163
**8.8:** Surrogate Recovery Summaries ..... 175
**8.9:** GC Surrogate Retention Time Summaries ..... 179
**8.10:** Initial and Continuing Calibration Summaries ..... 188
**Section 9: Metals Analysis - QC Data Summaries** ..... **235**
**9.1:** Inst QC MA40457: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na, Tl,V,Zn ..... 236

# Table of Contents



**9.2:** Inst QC MA40466: Hg ..... 264
**9.3:** Inst QC MA40471: Zn ..... 269
**9.4:** Prep QC MP96373: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na, Tl,V,Zn ..... 315
**9.5:** Prep QC MP96393: Hg ..... 325
**9.6:** IDL and Linear Range Summaries ..... 329
**Section 10: General Chemistry - QC Data Summaries ..... 335**
**10.1:** Method Blank and Spike Results Summary ..... 336
**10.2:** Duplicate Results Summary ..... 337
**10.3:** Matrix Spike Results Summary ..... 338
**10.4:** Inst QC GN53097: Chromium, Hexavalent ..... 339
**10.5:** Inst QC GN53120: Cyanide ..... 342
**10.6:** Inst QC GN53231: Chromium, Hexavalent ..... 347
**10.7:** Percent Solids Raw Data Summary ..... 349

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Sample Summary

Honeywell International Inc.

**Job No:** JC28902

HLANJPR: Study Area 6 Chrome Remedy

| Sample Number | Collected Date | Time | By | Received | Matrix Code | Type | Client Sample ID |
|---|---|---|---|---|---|---|---|
| JC28902-1 | 10/04/16 | 08:30 | JD | 10/04/16 | SO | Soil | WOOLSTON-TS-002 |
| JC28902-1R | 10/04/16 | 08:30 | JD | 10/04/16 | SO | Soil | WOOLSTON-TS-002 |

Soil samples reported on a dry weight basis unless otherwise indicated on result page.

2

# CASE NARRATIVE / CONFORMANCE SUMMARY

| | | | |
|---|---|---|---|
| **Client:** | Honeywell International Inc. | **Job No** | JC28902 |
| **Site:** | HLANJPR: Study Area 6 Chrome Remedy | **Report Date** | 10/11/2016 5:29:27 P |

On 10/04/2016, 1 Sample(s), 0 Trip Blank(s) and 0 Field Blank(s) were received at SGS Accutest at a maximum corrected temperature of 5.2 C. Samples were intact and chemically preserved, unless noted below. A SGS Accutest Job Number of JC28902 was assigned to the project. Laboratory sample ID, client sample ID and dates of sample collection are detailed in the report's Results Summary Section. Specified quality control criteria were achieved for this job except as noted below. For more information, please refer to the analytical results and QC summary pages.

Please refer to certification exceptions summary for additional certification information.

Compounds qualified as out of range in the continuing calibration summary report are acceptable as per method requirements when there is a high bias but the sample result is non-detect.

## Volatiles by GCMS By Method SW846 8260C

**Matrix:** SO **Batch ID:** VY7259

- All samples were analyzed within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28964-1DUP, JC28964-2MS, JC28964-1DUP were used as the QC samples indicated.
- RPD(s) for Duplicate for 2-Butanone (MEK), Acetone, Benzene, Carbon disulfide, Chloroform, Cyclohexane, Ethylbenzene, Isopropylbenzene, m,p-Xylene, Methylcyclohexane, o-Xylene, Toluene, Xylene (total) are outside control limits for sample JC28964-1DUP. Outside control limits due to different encores.

## Extractables by GCMS By Method SW846 8270D

**Matrix:** SO **Batch ID:** OP97539

- All samples were extracted within the recommended method holding time.
- Sample(s) JC28910-1MS, JC28910-1MSD were used as the QC samples indicated.
- All method blanks for this batch meet method specific criteria.
- JC28902-1: Confirmation run.
- JC28902-1 for 2-Fluorobiphenyl: Outside control limits due to matrix interference.

## Extractables by GC By Method NJDEP EPH

**Matrix:** SO **Batch ID:** OP97541

- All samples were extracted within the recommended method holding time.
- Sample(s) JC28906-2MS, JC28906-2MSD, JC28910-2DUP were used as the QC samples indicated.
- All method blanks for this batch meet method specific criteria.
- Matrix Spike Recovery(s) for EPH (>C28-C40) are outside control limits. Outside control limits due to high level in sample relative to spike amount.
- Matrix Spike / Matrix Spike Duplicate Recovery(s) for EPH (C9-C28), Total EPH (C9-C40) are outside control limits. Outside control limits due to high level in sample relative to spike amount.

## Extractables by GC By Method SW846 8081B

**Matrix:** SO **Batch ID:** OP97536

- All samples were extracted within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28906-1MS, JC28906-1MSD, OP97536-MSMSD were used as the QC samples indicated.

## Extractables by GC By Method SW846 8082A

**Matrix:** SO **Batch ID:** OP97535

- All samples were extracted within the recommended method holding time.
- Sample(s) JC28902-1MS, JC28902-1MSD, OP97535-MSMSD were used as the QC samples indicated.
- All method blanks for this batch meet method specific criteria.
- OP97535-BS1 for Aroclor 1260: Reported from 2nd signal. %D of check calibration on 1st signal exceed method criteria (20%) so using for confirmation only.

## Extractables by GC By Method SW846 8151

**Matrix:** SO **Batch ID:** OP97538

- All samples were extracted within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28904-1AMS, JC28904-1AMSD were used as the QC samples indicated.
- Matrix Spike Recovery(s) for 2,4-DB, Dinoseb, MCPA, MCPP are outside control limits. Outside control limits due to matrix interference.
- Matrix Spike Duplicate Recovery(s) for Dinoseb, MCPA, MCPP are outside control limits. Outside control limits due to matrix interference.
- RPD(s) for MSD for 2,4,5-T, 2,4,5-TP (Silvex), 2,4-DB, Dalapon, Dicamba, Dichloroprop, Pentachlorophenol are outside control limits for sample OP97538-MSD.
- OP97538-MSD for 2,4-DB: Outside the QC limits.

## Metals By Method SW846 6010C

**Matrix:** SO **Batch ID:** MP96373

- All samples were digested within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28910-1MS, JC28910-1MSD, JC28910-1SDL were used as the QC samples for metals.
- RPD(s) for Serial Dilution for Antimony, Arsenic, Barium, Cadmium, Calcium, Chromium, Cobalt, Copper, Lead, Nickel, Potassium, Sodium, Vanadium are outside control limits for sample MP96373-SD1. Percent difference acceptable due to low initial sample concentration (< 50 times IDL).
- MP96373-SD1 for Zinc: Serial dilution indicates possible matrix interference.
- MP96373-MB1 for Zinc: All reported results >10x MB value or with RL> 2X of this value.

## Metals By Method SW846 7471B

**Matrix:** SO **Batch ID:** MP96393

- All samples were digested within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28910-1MS, JC28910-1MSD were used as the QC samples for metals.

## Wet Chemistry By Method ASTM D1498-76M

**Matrix:** SO **Batch ID:** GN52967

- Sample(s) JC28819-1DUP were used as the QC samples for Redox Potential Vs H2.

## Wet Chemistry By Method SM2540 G-97

**Matrix:** SO **Batch ID:** GN52970

- The data for SM2540 G-97 meets quality control requirements.

## Wet Chemistry By Method SW846 3060A/7199

**Matrix:** SO **Batch ID:** GP574

- All samples were prepared within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28902-1PS, JC28902-1MS, JC28902-1DUP were used as the QC samples for Chromium, Hexavalent.
- Matrix Spike Recovery(s) for Chromium, Hexavalent are outside control limits. Insoluble XCR matrix spike recovery indicates possible matrix interference. See additional comments on soluble matrix spike recovery.
- RPD(s) for Duplicate for Chromium, Hexavalent are outside control limits for sample GP574-D1. RPD acceptable due to low duplicate and sample concentrations.
- GP574-S1 for Chromium, Hexavalent: Soluble XCR matrix spike recovery indicates possible matrix interference. Good post spike recovery (102%) on this sample.

**Matrix:** SO **Batch ID:** GP648

- All samples were prepared within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28902-1RPS, JC28902-1RMS, JC28902-1RDUP were used as the QC samples for Chromium, Hexavalent.
- Matrix Spike Recovery(s) for Chromium, Hexavalent are outside control limits. Insoluble XCR matrix spike recovery indicates possible matrix interference. See additional comments on soluble matrix spike recovery.
- RPD(s) for Duplicate for Chromium, Hexavalent are outside control limits for sample GP648-D1. RPD acceptable due to low duplicate and sample concentrations.
- GP648-S1 for Chromium, Hexavalent: Soluble XCR matrix spike recovery indicates possible matrix interference. Good post spike recovery (97.2%) on this sample.

## Wet Chemistry By Method SW846 9012B/LACHAT

**Matrix:** SO **Batch ID:** GP585

- All samples were prepared within the recommended method holding time.
- All method blanks for this batch meet method specific criteria.
- Sample(s) JC28906-1DUP, JC28906-1MS were used as the QC samples for Cyanide.
- Matrix Spike Recovery(s) for Cyanide are outside control limits. Spike recovery indicates possible matrix interference.

## Wet Chemistry By Method SW846 9045D

**Matrix:** SO **Batch ID:** GN52968

- Sample(s) JC28819-1DUP were used as the QC samples for pH.

SGS Accutest certifies that data reported for samples received, listed on the associated custody chain or analytical task order, were produced to specifications meeting the Quality System precision, accuracy and completeness objectives except as noted.

Estimated non-standard method measurement uncertainty data is available on request, based on quality control bias and implicit for standard methods. Acceptable uncertainty requires tested parameter quality control data to meet method criteria.

SGS Accutest is not responsible for data quality assumptions if partial reports are used and recommends that this report be used in its entirety. Data release is authorized by SGS Accutest indicated via signature on the report cover

# Summary of Hits



**Job Number:** JC28902
**Account:** Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Collected:** 10/04/16



| Lab Sample ID / Analyte | Client Sample ID | Result/ Qual | RL | MDL | Units | Method |
|---|---|---|---|---|---|---|
| **JC28902-1** | **WOOLSTON-TS-002** | | | | | |
| Acetophenone | | 15.8 J | 190 | 8.2 | ug/kg | SW846 8270D |
| Benzaldehyde | | 11.3 J | 190 | 9.4 | ug/kg | SW846 8270D |
| Total TIC, Semi-Volatile | | 41160 J | | | ug/kg | |
| Total Alkanes | | 600 J | | | ug/kg | |
| EPH (C9-C28) | | 88.4 | 7.0 | 3.6 | mg/kg | NJDEP EPH |
| EPH (> C28-C40) | | 358 | 7.0 | 3.6 | mg/kg | NJDEP EPH |
| Total EPH (C9-C40) | | 447 | 7.0 | 3.6 | mg/kg | NJDEP EPH |
| Aluminum | | 3160 | 58 | | mg/kg | SW846 6010C |
| Arsenic | | 5.4 | 2.3 | | mg/kg | SW846 6010C |
| Calcium | | 1380 | 580 | | mg/kg | SW846 6010C |
| Chromium | | 7.2 | 1.2 | | mg/kg | SW846 6010C |
| Copper | | 3.5 | 2.9 | | mg/kg | SW846 6010C |
| Iron | | 7460 | 58 | | mg/kg | SW846 6010C |
| Lead | | 4.3 | 2.3 | | mg/kg | SW846 6010C |
| Magnesium | | 637 | 580 | | mg/kg | SW846 6010C |
| Manganese | | 12.7 | 1.7 | | mg/kg | SW846 6010C |
| Vanadium | | 9.1 | 5.8 | | mg/kg | SW846 6010C |
| Redox Potential Vs H2 | | 302 | | | mv | ASTM D1498-76M |
| pH | | 5.55 | | | su | SW846 9045D |
| **JC28902-1R** | **WOOLSTON-TS-002** | | | | | |

No hits reported in this sample.

SGS ACCUTEST New Jersey

Section 4

4

## Sample Results

Report of Analysis

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8260C SW846 5035
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | Y166776.D | 1 | 10/06/16 | PS | 10/05/16 10:00 | n/a | VY7259 |
| Run #2 | | | | | | | |

| | Initial Weight |
|---|---|
| Run #1 | 3.0 g |
| Run #2 | |

**VOA TCL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 67-64-1 | Acetone | ND | 19 | 9.6 | ug/kg | |
| 71-43-2 | Benzene | ND | 0.96 | 0.23 | ug/kg | |
| 74-97-5 | Bromochloromethane | ND | 9.6 | 0.61 | ug/kg | |
| 75-27-4 | Bromodichloromethane | ND | 3.9 | 0.29 | ug/kg | |
| 75-25-2 | Bromoform | ND | 9.6 | 0.51 | ug/kg | |
| 74-83-9 | Bromomethane | ND | 9.6 | 0.93 | ug/kg | |
| 78-93-3 | 2-Butanone (MEK) | ND | 19 | 3.4 | ug/kg | |
| 75-15-0 | Carbon disulfide | ND | 3.9 | 0.33 | ug/kg | |
| 56-23-5 | Carbon tetrachloride | ND | 3.9 | 0.32 | ug/kg | |
| 108-90-7 | Chlorobenzene | ND | 3.9 | 0.31 | ug/kg | |
| 75-00-3 | Chloroethane | ND | 9.6 | 0.83 | ug/kg | |
| 67-66-3 | Chloroform | ND | 3.9 | 0.46 | ug/kg | |
| 74-87-3 | Chloromethane | ND | 9.6 | 0.41 | ug/kg | |
| 110-82-7 | Cyclohexane | ND | 3.9 | 1.1 | ug/kg | |
| 96-12-8 | 1,2-Dibromo-3-chloropropane | ND | 3.9 | 0.93 | ug/kg | |
| 124-48-1 | Dibromochloromethane | ND | 3.9 | 0.29 | ug/kg | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.9 | 0.47 | ug/kg | |
| 95-50-1 | 1,2-Dichlorobenzene | ND | 1.9 | 0.33 | ug/kg | |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.9 | 0.26 | ug/kg | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.9 | 0.29 | ug/kg | |
| 75-71-8 | Dichlorodifluoromethane | ND | 9.6 | 1.1 | ug/kg | |
| 75-34-3 | 1,1-Dichloroethane | ND | 1.9 | 0.36 | ug/kg | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.9 | 0.33 | ug/kg | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.9 | 0.29 | ug/kg | |
| 156-59-2 | cis-1,2-Dichloroethene | ND | 1.9 | 0.84 | ug/kg | |
| 156-60-5 | trans-1,2-Dichloroethene | ND | 1.9 | 0.30 | ug/kg | |
| 78-87-5 | 1,2-Dichloropropane | ND | 3.9 | 0.60 | ug/kg | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 3.9 | 0.38 | ug/kg | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 3.9 | 0.43 | ug/kg | |
| 100-41-4 | Ethylbenzene | ND | 1.9 | 0.29 | ug/kg | |
| 76-13-1 | Freon 113 | ND | 9.6 | 0.93 | ug/kg | |
| 591-78-6 | 2-Hexanone | ND | 9.6 | 2.7 | ug/kg | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8260C SW846 5035
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

**VOA TCL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 98-82-8 | Isopropylbenzene | ND | 3.9 | 0.30 | ug/kg | |
| 79-20-9 | Methyl Acetate | ND | 9.6 | 3.9 | ug/kg | |
| 108-87-2 | Methylcyclohexane | ND | 3.9 | 0.97 | ug/kg | |
| 1634-04-4 | Methyl Tert Butyl Ether | ND | 1.9 | 0.51 | ug/kg | |
| 108-10-1 | 4-Methyl-2-pentanone(MIBK) | ND | 9.6 | 1.6 | ug/kg | |
| 75-09-2 | Methylene chloride | ND | 9.6 | 1.9 | ug/kg | |
| 100-42-5 | Styrene | ND | 3.9 | 0.28 | ug/kg | |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 3.9 | 0.46 | ug/kg | |
| 127-18-4 | Tetrachloroethene | ND | 3.9 | 0.54 | ug/kg | |
| 108-88-3 | Toluene | ND | 1.9 | 0.24 | ug/kg | |
| 87-61-6 | 1,2,3-Trichlorobenzene | ND | 9.6 | 0.44 | ug/kg | |
| 120-82-1 | 1,2,4-Trichlorobenzene | ND | 9.6 | 0.35 | ug/kg | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 3.9 | 0.32 | ug/kg | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 3.9 | 0.62 | ug/kg | |
| 79-01-6 | Trichloroethene | ND | 1.9 | 0.37 | ug/kg | |
| 75-69-4 | Trichlorofluoromethane | ND | 9.6 | 1.2 | ug/kg | |
| 75-01-4 | Vinyl chloride | ND | 3.9 | 0.39 | ug/kg | |
| | m,p-Xylene | ND | 1.9 | 0.42 | ug/kg | |
| 95-47-6 | o-Xylene | ND | 1.9 | 0.39 | ug/kg | |
| 1330-20-7 | Xylene (total) | ND | 1.9 | 0.39 | ug/kg | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 1868-53-7 | Dibromofluoromethane | 105% | | 70-122% |
| 17060-07-0 | 1,2-Dichloroethane-D4 | 109% | | 68-124% |
| 2037-26-5 | Toluene-D8 | 100% | | 77-125% |
| 460-00-4 | 4-Bromofluorobenzene | 121% | | 72-130% |

| CAS No. | Tentatively Identified Compounds | R.T. | Est. Conc. | Units | Q |
|---|---|---|---|---|---|
| | Total TIC, Volatile | | 0 | ug/kg | |
| | Total Alkanes | | 0 | ug/kg | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8270D SW846 3546
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | M128187.D | 1 | 10/07/16 | CS | 10/06/16 | OP97539 | EM5462 |
| Run #2 [a] | M128186.D | 1 | 10/07/16 | CS | 10/06/16 | OP97539 | EM5462 |

| | Initial Weight | Final Volume |
|---|---|---|
| Run #1 | 30.4 g | 1.0 ml |
| Run #2 | 6.5 g | 1.0 ml |

**ABN TCL List (SOM0 2.0)**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 95-57-8 | 2-Chlorophenol | ND | 76 | 19 | ug/kg | |
| 59-50-7 | 4-Chloro-3-methyl phenol | ND | 190 | 23 | ug/kg | |
| 120-83-2 | 2,4-Dichlorophenol | ND | 190 | 32 | ug/kg | |
| 105-67-9 | 2,4-Dimethylphenol | ND | 190 | 68 | ug/kg | |
| 51-28-5 | 2,4-Dinitrophenol | ND | 190 | 140 | ug/kg | |
| 534-52-1 | 4,6-Dinitro-o-cresol | ND | 190 | 41 | ug/kg | |
| 95-48-7 | 2-Methylphenol | ND | 76 | 24 | ug/kg | |
| | 3&4-Methylphenol | ND | 76 | 31 | ug/kg | |
| 88-75-5 | 2-Nitrophenol | ND | 190 | 25 | ug/kg | |
| 100-02-7 | 4-Nitrophenol | ND | 380 | 100 | ug/kg | |
| 87-86-5 | Pentachlorophenol | ND | 150 | 36 | ug/kg | |
| 108-95-2 | Phenol | ND | 76 | 20 | ug/kg | |
| 58-90-2 | 2,3,4,6-Tetrachlorophenol | ND | 190 | 25 | ug/kg | |
| 95-95-4 | 2,4,5-Trichlorophenol | ND | 190 | 28 | ug/kg | |
| 88-06-2 | 2,4,6-Trichlorophenol | ND | 190 | 23 | ug/kg | |
| 83-32-9 | Acenaphthene | ND | 38 | 13 | ug/kg | |
| 208-96-8 | Acenaphthylene | ND | 38 | 19 | ug/kg | |
| 98-86-2 | Acetophenone | 15.8 | 190 | 8.2 | ug/kg | J |
| 120-12-7 | Anthracene | ND | 38 | 23 | ug/kg | |
| 1912-24-9 | Atrazine | ND | 76 | 16 | ug/kg | |
| 56-55-3 | Benzo(a)anthracene | ND | 38 | 11 | ug/kg | |
| 50-32-8 | Benzo(a)pyrene | ND | 38 | 17 | ug/kg | |
| 205-99-2 | Benzo(b)fluoranthene | ND | 38 | 17 | ug/kg | |
| 191-24-2 | Benzo(g,h,i)perylene | ND | 38 | 19 | ug/kg | |
| 207-08-9 | Benzo(k)fluoranthene | ND | 38 | 18 | ug/kg | |
| 101-55-3 | 4-Bromophenyl phenyl ether | ND | 76 | 15 | ug/kg | |
| 85-68-7 | Butyl benzyl phthalate | ND | 76 | 9.3 | ug/kg | |
| 92-52-4 | 1,1'-Biphenyl | ND | 76 | 5.2 | ug/kg | |
| 100-52-7 | Benzaldehyde | 11.3 | 190 | 9.4 | ug/kg | J |
| 91-58-7 | 2-Chloronaphthalene | ND | 76 | 9.1 | ug/kg | |
| 106-47-8 | 4-Chloroaniline | ND | 190 | 14 | ug/kg | |
| 86-74-8 | Carbazole | ND | 76 | 5.5 | ug/kg | |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8270D SW846 3546
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

**ABN TCL List (SOM0 2.0)**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 105-60-2 | Caprolactam | ND | 76 | 15 | ug/kg | |
| 218-01-9 | Chrysene | ND | 38 | 12 | ug/kg | |
| 111-91-1 | bis(2-Chloroethoxy)methane | ND | 76 | 8.1 | ug/kg | |
| 111-44-4 | bis(2-Chloroethyl)ether | ND | 76 | 16 | ug/kg | |
| 108-60-1 | bis(2-Chloroisopropyl)ether | ND | 76 | 14 | ug/kg | |
| 7005-72-3 | 4-Chlorophenyl phenyl ether | ND | 76 | 12 | ug/kg | |
| 121-14-2 | 2,4-Dinitrotoluene | ND | 38 | 12 | ug/kg | |
| 606-20-2 | 2,6-Dinitrotoluene | ND | 38 | 19 | ug/kg | |
| 91-94-1 | 3,3'-Dichlorobenzidine | ND | 76 | 32 | ug/kg | |
| 123-91-1 | 1,4-Dioxane | ND | 38 | 25 | ug/kg | |
| 53-70-3 | Dibenzo(a,h)anthracene | ND | 38 | 17 | ug/kg | |
| 132-64-9 | Dibenzofuran | ND | 76 | 15 | ug/kg | |
| 84-74-2 | Di-n-butyl phthalate | ND | 76 | 6.2 | ug/kg | |
| 117-84-0 | Di-n-octyl phthalate | ND | 76 | 9.5 | ug/kg | |
| 84-66-2 | Diethyl phthalate | ND | 76 | 8.1 | ug/kg | |
| 131-11-3 | Dimethyl phthalate | ND | 76 | 6.8 | ug/kg | |
| 117-81-7 | bis(2-Ethylhexyl)phthalate | ND | 76 | 8.9 | ug/kg | |
| 206-44-0 | Fluoranthene | ND | 38 | 17 | ug/kg | |
| 86-73-7 | Fluorene | ND | 38 | 17 | ug/kg | |
| 118-74-1 | Hexachlorobenzene | ND | 76 | 9.6 | ug/kg | |
| 87-68-3 | Hexachlorobutadiene | ND | 38 | 15 | ug/kg | |
| 77-47-4 | Hexachlorocyclopentadiene | ND | 380 | 15 | ug/kg | |
| 67-72-1 | Hexachloroethane | ND | 190 | 19 | ug/kg | |
| 193-39-5 | Indeno(1,2,3-cd)pyrene | ND | 38 | 18 | ug/kg | |
| 78-59-1 | Isophorone | ND | 76 | 8.1 | ug/kg | |
| 91-57-6 | 2-Methylnaphthalene | ND | 76 | 8.6 | ug/kg | |
| 88-74-4 | 2-Nitroaniline | ND | 190 | 9.0 | ug/kg | |
| 99-09-2 | 3-Nitroaniline | ND | 190 | 9.5 | ug/kg | |
| 100-01-6 | 4-Nitroaniline | ND | 190 | 9.8 | ug/kg | |
| 91-20-3 | Naphthalene | ND | 38 | 11 | ug/kg | |
| 98-95-3 | Nitrobenzene | ND | 76 | 15 | ug/kg | |
| 621-64-7 | N-Nitroso-di-n-propylamine | ND | 76 | 11 | ug/kg | |
| 86-30-6 | N-Nitrosodiphenylamine | ND | 190 | 14 | ug/kg | |
| 85-01-8 | Phenanthrene | ND | 38 | 13 | ug/kg | |
| 129-00-0 | Pyrene | ND | 38 | 12 | ug/kg | |
| 95-94-3 | 1,2,4,5-Tetrachlorobenzene | ND | 190 | 9.7 | ug/kg | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 367-12-4 | 2-Fluorophenol | 32% | 53% | 30-106% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8270D SW846 3546
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

**ABN TCL List (SOM0 2.0)**

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 4165-62-2 | Phenol-d5 | 31% | 53% | 30-106% |
| 118-79-6 | 2,4,6-Tribromophenol | 40% | 72% | 24-140% |
| 4165-60-0 | Nitrobenzene-d5 | 31% | 62% | 26-122% |
| 321-60-8 | 2-Fluorobiphenyl | 35% [b] | 56% | 36-112% |
| 1718-51-0 | Terphenyl-d14 | 36% | 59% | 36-132% |

| CAS No. | Tentatively Identified Compounds | R.T. | Est. Conc. | Units | Q |
|---|---|---|---|---|---|
| | system artifact | 3.20 | 1500 | ug/kg | J |
| | system artifact | 3.53 | 2100 | ug/kg | J |
| | system artifact/aldol-condensation | 3.59 | 4600 | ug/kg | J |
| | unknown | 5.39 | 1100 | ug/kg | J |
| 1470-50-4 | 2-Octenoic acid | 6.05 | 600 | ug/kg | JN |
| 67-47-0 | 2-Furancarboxaldehyde, 5-(hydroxymethyl) | 6.20 | 980 | ug/kg | JN |
| | unknown | 10.48 | 530 | ug/kg | J |
| | alkene | 16.02 | 1200 | ug/kg | J |
| | unknown | 17.30 | 670 | ug/kg | J |
| | unknown | 18.11 | 730 | ug/kg | J |
| | unknown | 18.56 | 1300 | ug/kg | J |
| | unknown | 18.91 | 5300 | ug/kg | J |
| | unknown | 19.23 | 1400 | ug/kg | J |
| | Tocopherol | 19.37 | 680 | ug/kg | J |
| | unknown | 19.48 | 2200 | ug/kg | J |
| | unknown | 19.58 | 1300 | ug/kg | J |
| | unknown | 19.65 | 1100 | ug/kg | J |
| | Tocopherol | 19.79 | 900 | ug/kg | J |
| | unknown | 20.39 | 960 | ug/kg | J |
| | unknown | 20.44 | 1700 | ug/kg | J |
| | unknown | 20.78 | 990 | ug/kg | J |
| | unknown | 21.03 | 4600 | ug/kg | J |
| | unknown | 21.18 | 6100 | ug/kg | J |
| | unknown | 21.32 | 610 | ug/kg | J |
| | unknown | 21.45 | 2900 | ug/kg | J |
| | unknown | 21.55 | 810 | ug/kg | J |
| | unknown | 21.71 | 2500 | ug/kg | J |
| | Total TIC, Semi-Volatile | | 41160 | ug/kg | J |
| | Total Alkanes | | 600 | ug/kg | J |

(a) Confirmation run.
(b) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range

J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8151 SW846 8151/3550C
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | OA120273.D | 2 | 10/07/16 | VDT | 10/06/16 | OP97538 | GOA4139 |
| Run #2 | | | | | | | |

| | Initial Weight | Final Volume |
|---|---|---|
| Run #1 | 15.4 g | 5.0 ml |
| Run #2 | | |

**Herbicide List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 94-75-7 | 2,4-D | ND | 38 | 17 | ug/kg | |
| 93-72-1 | 2,4,5-TP (Silvex) | ND | 7.5 | 2.7 | ug/kg | |
| 93-76-5 | 2,4,5-T | ND | 7.5 | 2.9 | ug/kg | |
| 75-99-0 | Dalapon | ND | 7.5 | 5.1 | ug/kg | |
| 1918-00-9 | Dicamba | ND | 7.5 | 3.8 | ug/kg | |
| 120-36-5 | Dichloroprop | ND | 38 | 11 | ug/kg | |
| 88-85-7 | Dinoseb | ND | 38 | 25 | ug/kg | |
| 94-74-6 | MCPA | ND | 3800 | 860 | ug/kg | |
| 93-65-2 | MCPP | ND | 3800 | 820 | ug/kg | |
| 87-86-5 | Pentachlorophenol | ND | 3.8 | 3.3 | ug/kg | |
| 94-82-6 | 2,4-DB | ND | 38 | 12 | ug/kg | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 19719-28-9 | 2,4-DCAA | 94% | | 10-156% |
| 19719-28-9 | 2,4-DCAA | 101% | | 10-156% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8081B SW846 3546
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | 4G73355.D | 1 | 10/06/16 | DS | 10/06/16 | OP97536 | G4G1919 |
| Run #2 | | | | | | | |

| | Initial Weight | Final Volume |
|---|---|---|
| Run #1 | 4.7 g | 10.0 ml |
| Run #2 | | |

**Pesticide TCL List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 309-00-2 | Aldrin | ND | 2.5 | 1.2 | ug/kg | |
| 319-84-6 | alpha-BHC | ND | 2.5 | 1.3 | ug/kg | |
| 319-85-7 | beta-BHC | ND | 2.5 | 1.5 | ug/kg | |
| 319-86-8 | delta-BHC | ND | 2.5 | 1.1 | ug/kg | |
| 58-89-9 | gamma-BHC (Lindane) | ND | 2.5 | 1.1 | ug/kg | |
| 5103-71-9 | alpha-Chlordane | ND | 2.5 | 1.2 | ug/kg | |
| 5103-74-2 | gamma-Chlordane | ND | 2.5 | 1.1 | ug/kg | |
| 57-74-9 | Chlordane (alpha and gamma) | ND | 2.5 | 1.1 | ug/kg | |
| 60-57-1 | Dieldrin | ND | 2.5 | 1.2 | ug/kg | |
| 72-54-8 | 4,4'-DDD | ND | 2.5 | 1.6 | ug/kg | |
| 72-55-9 | 4,4'-DDE | ND | 2.5 | 1.3 | ug/kg | |
| 50-29-3 | 4,4'-DDT | ND | 2.5 | 1.5 | ug/kg | |
| 72-20-8 | Endrin | ND | 2.5 | 1.2 | ug/kg | |
| 1031-07-8 | Endosulfan sulfate | ND | 2.5 | 0.99 | ug/kg | |
| 7421-93-4 | Endrin aldehyde | ND | 2.5 | 1.5 | ug/kg | |
| 959-98-8 | Endosulfan-I | ND | 2.5 | 1.3 | ug/kg | |
| 33213-65-9 | Endosulfan-II | ND | 2.5 | 1.3 | ug/kg | |
| 76-44-8 | Heptachlor | ND | 2.5 | 1.2 | ug/kg | |
| 1024-57-3 | Heptachlor epoxide | ND | 2.5 | 1.3 | ug/kg | |
| 72-43-5 | Methoxychlor | ND | 4.9 | 1.2 | ug/kg | |
| 53494-70-5 | Endrin ketone | ND | 2.5 | 1.9 | ug/kg | |
| 8001-35-2 | Toxaphene | ND | 61 | 26 | ug/kg | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 77% | | 24-136% |
| 877-09-8 | Tetrachloro-m-xylene | 74% | | 24-136% |
| 2051-24-3 | Decachlorobiphenyl | 65% | | 10-153% |
| 2051-24-3 | Decachlorobiphenyl | 78% | | 10-153% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** SW846 8082A SW846 3546
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | XX198049.D | 1 | 10/06/16 | HB | 10/06/16 | OP97535 | GXX5823 |
| Run #2 | | | | | | | |

| | Initial Weight | Final Volume |
|---|---|---|
| Run #1 | 9.7 g | 10.0 ml |
| Run #2 | | |

**PCB List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 12674-11-2 | Aroclor 1016 | ND | 60 | 29 | ug/kg | |
| 11104-28-2 | Aroclor 1221 | ND | 60 | 29 | ug/kg | |
| 11141-16-5 | Aroclor 1232 | ND | 60 | 23 | ug/kg | |
| 53469-21-9 | Aroclor 1242 | ND | 60 | 21 | ug/kg | |
| 12672-29-6 | Aroclor 1248 | ND | 60 | 38 | ug/kg | |
| 11097-69-1 | Aroclor 1254 | ND | 60 | 30 | ug/kg | |
| 11096-82-5 | Aroclor 1260 | ND | 60 | 25 | ug/kg | |
| 11100-14-4 | Aroclor 1268 | ND | 60 | 21 | ug/kg | |
| 37324-23-5 | Aroclor 1262 | ND | 60 | 40 | ug/kg | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 89% | | 20-152% |
| 877-09-8 | Tetrachloro-m-xylene | 88% | | 20-152% |
| 2051-24-3 | Decachlorobiphenyl | 83% | | 12-157% |
| 2051-24-3 | Decachlorobiphenyl | 80% | | 12-157% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Method:** NJDEP EPH SW846 3546
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

| | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| Run #1 | 5Y36634.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Y1211 |
| Run #2 | | | | | | | |

| | Initial Weight | Final Volume |
|---|---|---|
| Run #1 | 16.6 g | 2.0 ml |
| Run #2 | | |

**NJDEP EPH List**

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| | EPH (C9-C28) | 88.4 | 7.0 | 3.6 | mg/kg | |
| | EPH (> C28-C40) | 358 | 7.0 | 3.6 | mg/kg | |
| | Total EPH (C9-C40) | 447 | 7.0 | 3.6 | mg/kg | |

| CAS No. | Surrogate Recoveries | Run# 1 | Run# 2 | Limits |
|---|---|---|---|---|
| 84-15-1 | o-Terphenyl | 63% | | 40-140% |
| 3386-33-2 | 1-Chlorooctadecane | 69% | | 40-140% |

ND = Not detected MDL = Method Detection Limit
RL = Reporting Limit
E = Indicates value exceeds calibration range
J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

**Metals Analysis**

| Analyte | Result | RL | Units | DF | Prep | Analyzed | By | Method | Prep Method |
|---|---|---|---|---|---|---|---|---|---|
| Aluminum | 3160 | 58 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Antimony | < 2.3 | 2.3 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Arsenic | 5.4 | 2.3 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Barium | < 23 | 23 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Beryllium | < 0.23 | 0.23 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Cadmium | < 0.58 | 0.58 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Calcium | 1380 | 580 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Chromium | 7.2 | 1.2 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Cobalt | < 5.8 | 5.8 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Copper | 3.5 | 2.9 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Iron | 7460 | 58 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Lead | 4.3 | 2.3 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Magnesium | 637 | 580 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Manganese | 12.7 | 1.7 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Mercury | < 0.038 | 0.038 | mg/kg | 1 | 10/06/16 | 10/06/16 | JPM | SW846 7471B [2] | SW846 7471B [4] |
| Nickel | < 4.6 | 4.6 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Potassium | < 1200 | 1200 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Selenium | < 2.3 | 2.3 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Silver | < 0.58 | 0.58 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Sodium | < 1200 | 1200 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Thallium | < 1.2 | 1.2 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Vanadium | 9.1 | 5.8 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |
| Zinc | < 5.8 | 5.8 | mg/kg | 1 | 10/05/16 | 10/05/16 | ND | SW846 6010C [1] | SW846 3050B [3] |

(1) Instrument QC Batch: MA40457
(2) Instrument QC Batch: MA40466
(3) Prep QC Batch: MP96373
(4) Prep QC Batch: MP96393

RL = Reporting Limit

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





**Client Sample ID:** WOOLSTON-TS-002
**Lab Sample ID:** JC28902-1
**Matrix:** SO - Soil
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Date Sampled:** 10/04/16
**Date Received:** 10/04/16
**Percent Solids:** 86.5

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | < 0.45 | 0.45 | mg/kg | 1 | 10/07/16 11:04 | TT | SW846 3060A/7199 |
| Cyanide | < 0.23 | 0.23 | mg/kg | 1 | 10/07/16 10:09 | YZ | SW846 9012B/LACHAT |
| Redox Potential Vs H2 | 302 | | mv | 1 | 10/05/16 14:10 | AC | ASTM D1498-76M |
| Solids, Percent | 86.5 | | % | 1 | 10/05/16 14:00 | AT | SM2540 G-97 |
| pH | 5.55 | | su | 1 | 10/05/16 13:45 | AC | SW846 9045D |

RL = Reporting Limit

SGS Accutest LabLink@930131 07:10 12-Oct-2016

# Report of Analysis





| | | | |
|---|---|---|---|
| **Client Sample ID:** | WOOLSTON-TS-002 | | |
| **Lab Sample ID:** | JC28902-1R | **Date Sampled:** | 10/04/16 |
| **Matrix:** | SO - Soil | **Date Received:** | 10/04/16 |
| | | **Percent Solids:** | 86.5 |
| **Project:** | HLANJPR: Study Area 6 Chrome Remedy | | |

**General Chemistry**

| Analyte | Result | RL | Units | DF | Analyzed | By | Method |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | < 0.46 | 0.46 | mg/kg | 1 | 10/10/16 19:47 | AT | SW846 3060A/7199 |

RL = Reporting Limit

SGS ACCUTEST New Jersey

Section 5

5

## Misc. Forms

### Custody Documents and Other Forms

Includes the following where applicable:

- Certification Exceptions
- Chain of Custody
- Sample Tracking Chronicle
- Internal Chain of Custody

# Parameter Certification Exceptions



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

The following parameters included in this report are exceptions to NELAC certification.
The certification status of each is indicated below.

| Parameter | CAS# | Method | Mat | Certification Status |
|---|---|---|---|---|
| Redox Potential Vs H2 | | **ASTM D1498-76M** | SO | Accutest is not certified for this parameter.[a] |

(a) Lab cert for analyte not supported by NJDEP, OQA. Only methods/analytes required for reporting by the State of NJ can be certified in NJ. Use of this analyte for compliance must be verified through the appropriate regulatory office.

Certification exceptions shown are based on the New Jersey DEP certifications. Applicability in other states may vary. Please contact your laboratory representative if additional information is required for a specific regulatory program.

SLL

**ACCUTEST**
Fresh Ponds Corporate Village, Building B
2235 Route 130,Dayton, New Jersey 08810
732-329-0200 Phone, 732-329-3499 Fax

**Honeywell** **Chain Of Custody / Analysis Request**

AESI Ref: 38439.43925
COC # : 37394-092716
Lab Use Only
Lab Proj # HWINJM 45341
Lab ID ACTD
PAGE 1 of 1
Job No. JC28902

Privileged & Confidential: Y
EDD To: Andrew Shust (AMEC)
Sampler: Jenna Desiderio
P O #
Analysis Turnaround Time: 3 day TAT
Standard -
Rush Charges Authorized for - Y
2 weeks -
1 week -
48 Hours -

Site Name: HUDSONCO
Location of Site: SA-6 Cr Remedy

Client Contact: (name, co., address)
Andrew Shust, AMEC Hamilton, NJ
200 American Metro Blvd., Suite 113
Hamilton, NJ 08619

Hardcopy Report To: See above
Invoice To: Maria Kaouris - Honeywell PM 101 Columbia Rd. Morristown, NJ 07962

What is in the Text File? Mouse over here.
Written and maintained by AESI (Ver 3_7) 02-01-05 renesurgi@aol.com

| | Sample Identification: Location ID | Start Depth (ft) | End Depth (ft) | Field Sample ID | Sample Date | Sample Time | Sample Type | Sample Matrix | Sample Purpose | # of Cont. | Grab/Composite | Field Filtered Sample ? | Preservative | EPA 7199 Hexavalent Chromium | TAL Metals 6010B | TCL VOC 8260B | TCL SVOCs 8270C | Non- fractionated EPH | PCB | SW846 9012A | Pesticides 8081A | SW8151 Total Herb | | | | Lab Sample Numbers |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | | |
| | | | | | | | | | | | | | Units | mg/kg | mg/kg | mg/kg | mg/kg | mg/kg | mg/kg | mg/kg | mg/kg | mg/kg | | | | |
| 1 | WOOLSTON-TS | | | WOOLSTON-TS-002 * | 10/4/2016 | 8:30 | SOIL | Soil | REG | 4 | grab | N | | X | X | X | X | X | X | X | X | X | | | | 1 |
| 2 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | | | | | | | | | | | |

Lab Sample Numbers: D10 P1 1403 4013

INITIAL ASSESSMENT AM 10
LABEL VERIFICATION Am

**3 day TAT** * 3X5 & ENC 10/4/16 1m

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Relinquished by | Company | AMEC | Received by | Company | ACTD | Condition | | Custody Seals Intact | |
| | Date/Time | 10/4/16 8:40 | | Date/Time 10-4-16 1500 | | Cooler Temp. | | | |
| Relinquished by | Company | | Received by | Company | | Condition | | Custody Seals Intact | |
| | Date/Time 10-4-16 1652 | | | Date/Time 10/4/16 1738 | | Cooler Temp. | | | |

Preservatives: 0 = None; [1 = HCL]; [2 = HNO3]; [3 = H2SO4]; [4 = NaOH]; [5 = Zn. Acetate]; [6 = MeOH]; [7 = NaHSO4]; 8 = Other (specify):

04.1 SEP

**JC28902: Chain of Custody**
**Page 1 of 3**

## SGS Accutest Sample Receipt Summary

**Job Number:** JC28902 **Client:** **Project:**

**Date / Time Received:** 10/4/2016 4:52:00 PM **Delivery Method:** **Airbill #'s:**

**Cooler Temps (Raw Measured) °C:** Cooler 1: (4.1);

**Cooler Temps (Corrected) °C:** Cooler 1: (5.0);

| Cooler Security | Y | or | N | | Y | or | N |
|---|---|---|---|---|---|---|---|
| 1. Custody Seals Present: | ☑ | | ☐ | 3. COC Present: | ☑ | | ☐ |
| 2. Custody Seals Intact: | ☑ | | ☐ | 4. Smpl Dates/Time OK | ☑ | | ☐ |

| Cooler Temperature | Y | or | N |
|---|---|---|---|
| 1. Temp criteria achieved: | ☑ | | ☐ |
| 2. Cooler temp verification: | IR Gun | | |
| 3. Cooler media: | Ice (Bag) | | |
| 4. No. Coolers: | 1 | | |

| Quality Control _Preservation | Y | or | N | N/A |
|---|---|---|---|---|
| 1. Trip Blank present / cooler: | ☐ | | ☑ | ☐ |
| 2. Trip Blank listed on COC: | ☐ | | ☑ | ☐ |
| 3. Samples preserved properly: | ☑ | | ☐ | |
| 4. VOCs headspace free: | ☐ | | ☐ | ☑ |

| Sample Integrity - Documentation | Y | or | N |
|---|---|---|---|
| 1. Sample labels present on bottles: | ☑ | | ☐ |
| 2. Container labeling complete: | ☑ | | ☐ |
| 3. Sample container label / COC agree: | ☑ | | ☐ |

| Sample Integrity - Condition | Y | or | N |
|---|---|---|---|
| 1. Sample recvd within HT: | ☑ | | ☐ |
| 2. All containers accounted for: | ☑ | | ☐ |
| 3. Condition of sample: | Intact | | |

| Sample Integrity - Instructions | Y | or | N | N/A |
|---|---|---|---|---|
| 1. Analysis requested is clear: | ☑ | | ☐ | |
| 2. Bottles received for unspecified tests | ☐ | | ☑ | |
| 3. Sufficient volume recvd for analysis: | ☑ | | ☐ | |
| 4. Compositing instructions clear: | ☐ | | ☐ | ☑ |
| 5. Filtering instructions clear: | ☐ | | ☐ | ☑ |

Comments

**JC28902: Chain of Custody**
**Page 2 of 3**

## Job Change Order: JC28902

| | | | |
|---|---|---|---|
| **Requested Date:** | 10/7/2016 | **Received Date:** | 10/4/2016 |
| **Account Name:** | Honeywell International Inc. | **Due Date:** | 10/20/2016 |
| **Project Description:** | HLANJPR: Study Area 6 Chrome Remedy | **Deliverable:** | FULT1 |
| **CSR:** | mayurp | **TAT (Days):** | 3 |

==========

**Sample #:** JC28902-1

**Dept:**

**TAT:** 3

WOOLSTON-TS-002

**Change:**
Relog the sample for XXCRA7199R, HOMOGENIZE
move HWSHEET to relogged email

==========

**Above Changes Per:**

**Date/Time:** 10/7/2016 3:38:35 PM

To Client: This Change Order is confirmation of the revisions, previously discussed with the SGS Accutest Client Service Representative.

Page 1 of 1

5.2 5

**JC28902: Chain of Custody**
**Page 3 of 3**

SGS Accutest

# Internal Sample Tracking Chronicle

Honeywell International Inc.

**Job No:** JC28902

HLANJPR: Study Area 6 Chrome Remedy

| Sample Number | Method | Analyzed | By | Prepped | By | Test Codes |
|---|---|---|---|---|---|---|
| JC28902-1 | Collected: 04-OCT-16 08:30 By: JD | | Received: 04-OCT-16 By: JK | | | |
| WOOLSTON-TS-002 | | | | | | |
| JC28902-1 | SW846 9045D | 05-OCT-16 13:45 | AC | | | PH |
| JC28902-1 | SM2540 G-97 | 05-OCT-16 14:00 | AT | | | SOL104 |
| JC28902-1 | ASTM D1498-76M | 05-OCT-16 14:10 | AC | | | EH |
| JC28902-1 | SW846 6010C | 05-OCT-16 23:30 | ND | 05-OCT-16 | DM | AG,AL,AS,BA,BE,CA,CD,CO,CR,CU,FE,K,MG,MN,NA,NI,PB,SB,SE,TL,V,ZN |
| JC28902-1 | SW846 7471B | 06-OCT-16 11:51 | JPM | 06-OCT-16 | JPM | HG |
| JC28902-1 | NJDEP EPH | 06-OCT-16 16:01 | SP | 06-OCT-16 | SZ | BNJEPHCAT2NF |
| JC28902-1 | SW846 8082A | 06-OCT-16 17:57 | HB | 06-OCT-16 | SZ | P8082PCB11AO |
| JC28902-1 | SW846 8081B | 06-OCT-16 18:11 | DS | 06-OCT-16 | SZ | P8081PESTTCL |
| JC28902-1 | SW846 8260C | 06-OCT-16 21:54 | PS | | | V8260TCL20+ |
| JC28902-1 | SW846 9012B/LACHAT | 07-OCT-16 10:09 | YZ | 06-OCT-16 | HS | CN |
| JC28902-1 | SW846 3060A/7199 | 07-OCT-16 11:04 | TT | 06-OCT-16 | MP | XCRA7199 |
| JC28902-1 | SW846 8151 | 07-OCT-16 12:09 | VDT | 06-OCT-16 | RG | H8151FL |
| JC28902-1 | SW846 8270D | 07-OCT-16 14:49 | CS | 06-OCT-16 | FN | AB8270TCL20+ |
| JC28902-1 | SW846 8270D | 07-OCT-16 15:17 | CS | 06-OCT-16 | FN | AB8270TCL20+ |
| JC28902-1R | Collected: 04-OCT-16 08:30 By: JD | | Received: 04-OCT-16 By: JK | | | |
| WOOLSTON-TS-002 | | | | | | |
| JC28902-1R | SW846 3060A/7199 | 10-OCT-16 19:47 | AT | 10-OCT-16 | AP | XCRA7199 |

# SGS Accutest Internal Chain of Custody



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Received:** 10/04/16

| Sample.Bottle Number | Transfer FROM | Transfer TO | Date/Time | Reason |
|---|---|---|---|---|
| JC28902-1.1 | Secured Storage | Alfredo Crespo | 10/05/16 08:10 | Retrieve from Storage |
| JC28902-1.1 | Alfredo Crespo | Secured Staging Area | 10/05/16 08:10 | Return to Storage |
| JC28902-1.1 | Secured Staging Area | Diana Mathes | 10/05/16 10:02 | Retrieve from Storage |
| JC28902-1.1 | Diana Mathes | Andrew Csimbok | 10/05/16 10:17 | Custody Transfer |
| JC28902-1.1 | Andrew Csimbok | Secured Storage | 10/05/16 17:16 | Return to Storage |
| JC28902-1.1 | Secured Storage | Steven Zarchy | 10/06/16 06:38 | Retrieve from Storage |
| JC28902-1.1 | Steven Zarchy | Deanna Hornig | 10/06/16 07:37 | Custody Transfer |
| JC28902-1.1 | Deanna Hornig | Secured Storage | 10/06/16 09:34 | Return to Storage |
| JC28902-1.1 | Secured Storage | Todd Shoemaker | 10/06/16 15:27 | Retrieve from Storage |
| JC28902-1.1 | Todd Shoemaker | Secured Staging Area | 10/06/16 15:27 | Return to Storage |
| JC28902-1.1 | Secured Staging Area | Hans Seignon | 10/06/16 16:49 | Retrieve from Storage |
| JC28902-1.1 | Hans Seignon | Secured Storage | 10/07/16 00:21 | Return to Storage |
| JC28902-1.1 | Secured Storage | Alfredo Crespo | 10/10/16 07:27 | Retrieve from Storage |
| JC28902-1.1 | Alfredo Crespo | Secured Staging Area | 10/10/16 07:27 | Return to Storage |
| JC28902-1.1 | Secured Staging Area | Aesha Patel | 10/10/16 09:15 | Retrieve from Storage |
| JC28902-1.1 | Lisa Brassell | | 10/10/16 11:17 | Depleted |
| Bottle was returned to secure storage, but inadvertently not scanned. | | | | |
| JC28902-1.1.1 | Diana Mathes | Metals Digestion | 10/05/16 10:14 | Digestate from JC28902-1.1 |
| JC28902-1.1.1 | Metals Digestion | Diana Mathes | 10/05/16 10:14 | Digestate from JC28902-1.1 |
| JC28902-1.1.1 | Diana Mathes | Metals Digestate Storage | 10/05/16 10:14 | Return to Storage |
| JC28902-1.1.2 | Steven Zarchy | Organics Prep | 10/06/16 06:39 | Extract from JC28902-1.1 |
| JC28902-1.1.2 | Organics Prep | Steven Zarchy | 10/06/16 11:54 | Extract from JC28902-1.1 |
| JC28902-1.1.2 | Steven Zarchy | Extract Storage | 10/06/16 11:54 | Return to Storage |
| JC28902-1.1.2 | Extract Storage | Sarah Patterson | 10/06/16 16:06 | Retrieve from Storage |
| JC28902-1.1.2 | Sarah Patterson | GC5Y | 10/06/16 16:06 | Load on Instrument |
| JC28902-1.1.2 | GC5Y | Sarah Patterson | 10/07/16 16:10 | Unload from Instrument |
| JC28902-1.1.2 | Sarah Patterson | Extract Freezer | 10/07/16 16:10 | Return to Storage |
| JC28902-1.1.3 | Steven Zarchy | Organics Prep | 10/06/16 06:41 | Extract from JC28902-1.1 |
| JC28902-1.1.3 | Organics Prep | Steven Zarchy | 10/06/16 13:15 | Extract from JC28902-1.1 |
| JC28902-1.1.3 | Steven Zarchy | Extract Storage | 10/06/16 13:15 | Return to Storage |
| JC28902-1.1.3 | Extract Storage | Humarah Bano | 10/06/16 17:33 | Retrieve from Storage |
| JC28902-1.1.3 | Humarah Bano | GCXX | 10/06/16 17:33 | Load on Instrument |
| JC28902-1.1.4 | Steven Zarchy | Organics Prep | 10/06/16 06:42 | Extract from JC28902-1.1 |
| JC28902-1.1.4 | Organics Prep | Steven Zarchy | 10/06/16 13:15 | Extract from JC28902-1.1 |
| JC28902-1.1.4 | Steven Zarchy | Extract Storage | 10/06/16 13:15 | Return to Storage |
| JC28902-1.1.4 | Extract Storage | Kristen Drake | 10/06/16 16:35 | Retrieve from Storage |
| JC28902-1.1.4 | Kristen Drake | GC4G | 10/06/16 16:35 | Load on Instrument |
| JC28902-1.1.4 | GC4G | Dhara Saparia | 10/10/16 09:44 | Unload from Instrument |
| JC28902-1.1.4 | Dhara Saparia | Extract Freezer | 10/10/16 09:45 | Return to Storage |

# SGS Accutest Internal Chain of Custody



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Received:** 10/04/16

| Sample.Bottle Number | Transfer FROM | Transfer TO | Date/Time | Reason |
|---|---|---|---|---|
| JC28902-1.1.5 | Deanna Hornig | Organics Prep | 10/06/16 07:40 | Extract from JC28902-1.1 |
| JC28902-1.1.5 | Organics Prep | Finley Nyaata | 10/06/16 17:34 | Extract from JC28902-1.1 |
| JC28902-1.1.5 | Finley Nyaata | Extract Storage | 10/06/16 17:34 | Return to Storage |
| JC28902-1.1.5 | Extract Storage | Ashley Noble | 10/07/16 13:20 | Retrieve from Storage |
| JC28902-1.1.5 | Ashley Noble | GCMS6P | 10/07/16 13:20 | Load on Instrument |
| JC28902-1.1.5 | Arielle Cocozza | Extract Freezer | 10/08/16 12:06 | Return to Storage |
| JC28902-1.1.5 | GCMS6P | Arielle Cocozza | 10/08/16 12:06 | Unload from Instrument |
| JC28902-1.1.6 | Deanna Hornig | Organics Prep | 10/06/16 07:42 | Extract from JC28902-1.1 |
| JC28902-1.1.6 | Organics Prep | Rebecca Gluckman | 10/06/16 17:46 | Extract from JC28902-1.1 |
| JC28902-1.1.6 | Rebecca Gluckman | Extract Storage | 10/06/16 17:46 | Return to Storage |
| JC28902-1.1.6 | Extract Storage | Vincent Drago | 10/07/16 09:44 | Retrieve from Storage |
| JC28902-1.1.6 | Vincent Drago | GCOA | 10/07/16 09:44 | Load on Instrument |
| JC28902-1.1.6 | GCOA | Vincent Drago | 10/10/16 09:37 | Unload from Instrument |
| JC28902-1.1.6 | Vincent Drago | Extract Freezer | 10/10/16 09:37 | Return to Storage |
| JC28902-1.1.7 | Deanna Hornig | Miti Patel | 10/06/16 08:23 | Aliquot from JC28902-1.1 |
| JC28902-1.1.7 | Miti Patel | | 10/06/16 11:53 | Depleted |
| JC28902-1.2 | Secured Storage | Todd Shoemaker | 10/05/16 08:49 | Retrieve from Storage |
| JC28902-1.2 | Todd Shoemaker | Secured Staging Area | 10/05/16 08:49 | Return to Storage |
| JC28902-1.2 | Secured Staging Area | Amir Takla | 10/05/16 08:52 | Retrieve from Storage |
| JC28902-1.2 | Amir Takla | Secured Storage | 10/05/16 17:18 | Return to Storage |
| JC28902-1.2 | Secured Storage | Alfredo Crespo | 10/06/16 07:49 | Retrieve from Storage |
| JC28902-1.2 | Alfredo Crespo | Secured Staging Area | 10/06/16 07:49 | Return to Storage |
| JC28902-1.2 | Secured Staging Area | James Patrick McIlvaine | 10/06/16 08:47 | Retrieve from Storage |
| JC28902-1.2 | Secured Storage | Alfredo Crespo | 10/06/16 09:12 | Retrieve from Storage |
| Bottle was returned to secure storage, but inadvertently not scanned. | | | | |
| JC28902-1.2 | Alfredo Crespo | Secured Staging Area | 10/06/16 09:12 | Return to Storage |
| JC28902-1.2 | Deanna Hornig | | 10/06/16 09:34 | Depleted |
| Analyst unavailable for custody transfer. | | | | |
| JC28902-1.4 | Secured Storage | Jayna Patel | 10/05/16 10:15 | Retrieve from Storage |
| JC28902-1.4 | Jayna Patel | Secured Storage | 10/05/16 10:15 | Return to Storage |
| JC28902-1.5 | Secured Storage | Jayna Patel | 10/05/16 10:15 | Retrieve from Storage |
| JC28902-1.5 | Jayna Patel | Secured Storage | 10/05/16 10:15 | Return to Storage |
| JC28902-1.5 | Secured Storage | Prashant Shukla | 10/06/16 15:59 | Retrieve from Storage |
| JC28902-1.5 | Prashant Shukla | GCMSY | 10/06/16 15:59 | Load on Instrument |
| JC28902-1.5 | GCMSY | Prashant Shukla | 10/08/16 09:37 | Unload from Instrument |
| JC28902-1.5 | Prashant Shukla | | 10/08/16 09:37 | Depleted |
| JC28902-1.6 | Secured Storage | Jayna Patel | 10/05/16 10:15 | Retrieve from Storage |
| JC28902-1.6 | Jayna Patel | Secured Storage | 10/05/16 10:15 | Return to Storage |

SGS ACCUTEST New Jersey

Section 6

## GC/MS Volatiles

6

### QC Data Summaries

Includes the following where applicable:

- Method Blank Summaries
- Blank Spike Summaries
- Matrix Spike and Duplicate Summaries
- Instrument Performance Checks (BFB)
- Internal Standard Area Summaries
- Surrogate Recovery Summaries
- Initial and Continuing Calibration Summaries

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| VY7259-MB | Y166756.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 67-64-1 | Acetone | ND | 10 | 5.0 | ug/kg | |
| 71-43-2 | Benzene | ND | 0.50 | 0.12 | ug/kg | |
| 74-97-5 | Bromochloromethane | ND | 5.0 | 0.32 | ug/kg | |
| 75-27-4 | Bromodichloromethane | ND | 2.0 | 0.15 | ug/kg | |
| 75-25-2 | Bromoform | ND | 5.0 | 0.27 | ug/kg | |
| 74-83-9 | Bromomethane | ND | 5.0 | 0.49 | ug/kg | |
| 78-93-3 | 2-Butanone (MEK) | ND | 10 | 1.8 | ug/kg | |
| 75-15-0 | Carbon disulfide | ND | 2.0 | 0.17 | ug/kg | |
| 56-23-5 | Carbon tetrachloride | ND | 2.0 | 0.17 | ug/kg | |
| 108-90-7 | Chlorobenzene | ND | 2.0 | 0.16 | ug/kg | |
| 75-00-3 | Chloroethane | ND | 5.0 | 0.43 | ug/kg | |
| 67-66-3 | Chloroform | ND | 2.0 | 0.24 | ug/kg | |
| 74-87-3 | Chloromethane | ND | 5.0 | 0.21 | ug/kg | |
| 110-82-7 | Cyclohexane | ND | 2.0 | 0.55 | ug/kg | |
| 96-12-8 | 1,2-Dibromo-3-chloropropane | ND | 2.0 | 0.48 | ug/kg | |
| 124-48-1 | Dibromochloromethane | ND | 2.0 | 0.15 | ug/kg | |
| 106-93-4 | 1,2-Dibromoethane | ND | 1.0 | 0.24 | ug/kg | |
| 95-50-1 | 1,2-Dichlorobenzene | ND | 1.0 | 0.17 | ug/kg | |
| 541-73-1 | 1,3-Dichlorobenzene | ND | 1.0 | 0.14 | ug/kg | |
| 106-46-7 | 1,4-Dichlorobenzene | ND | 1.0 | 0.15 | ug/kg | |
| 75-71-8 | Dichlorodifluoromethane | ND | 5.0 | 0.55 | ug/kg | |
| 75-34-3 | 1,1-Dichloroethane | ND | 1.0 | 0.19 | ug/kg | |
| 107-06-2 | 1,2-Dichloroethane | ND | 1.0 | 0.17 | ug/kg | |
| 75-35-4 | 1,1-Dichloroethene | ND | 1.0 | 0.15 | ug/kg | |
| 156-59-2 | cis-1,2-Dichloroethene | ND | 1.0 | 0.44 | ug/kg | |
| 156-60-5 | trans-1,2-Dichloroethene | ND | 1.0 | 0.16 | ug/kg | |
| 78-87-5 | 1,2-Dichloropropane | ND | 2.0 | 0.31 | ug/kg | |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | 2.0 | 0.20 | ug/kg | |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | 2.0 | 0.22 | ug/kg | |
| 100-41-4 | Ethylbenzene | ND | 1.0 | 0.15 | ug/kg | |
| 76-13-1 | Freon 113 | ND | 5.0 | 0.48 | ug/kg | |
| 591-78-6 | 2-Hexanone | ND | 5.0 | 1.4 | ug/kg | |
| 98-82-8 | Isopropylbenzene | ND | 2.0 | 0.15 | ug/kg | |
| 79-20-9 | Methyl Acetate | ND | 5.0 | 2.0 | ug/kg | |
| 108-87-2 | Methylcyclohexane | ND | 2.0 | 0.51 | ug/kg | |
| 1634-04-4 | Methyl Tert Butyl Ether | ND | 1.0 | 0.27 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| VY7259-MB | Y166756.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 108-10-1 | 4-Methyl-2-pentanone(MIBK) | ND | 5.0 | 0.85 | ug/kg | |
| 75-09-2 | Methylene chloride | ND | 5.0 | 1.0 | ug/kg | |
| 100-42-5 | Styrene | ND | 2.0 | 0.15 | ug/kg | |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | 2.0 | 0.24 | ug/kg | |
| 127-18-4 | Tetrachloroethene | ND | 2.0 | 0.28 | ug/kg | |
| 108-88-3 | Toluene | ND | 1.0 | 0.13 | ug/kg | |
| 87-61-6 | 1,2,3-Trichlorobenzene | ND | 5.0 | 0.23 | ug/kg | |
| 120-82-1 | 1,2,4-Trichlorobenzene | ND | 5.0 | 0.18 | ug/kg | |
| 71-55-6 | 1,1,1-Trichloroethane | ND | 2.0 | 0.17 | ug/kg | |
| 79-00-5 | 1,1,2-Trichloroethane | ND | 2.0 | 0.32 | ug/kg | |
| 79-01-6 | Trichloroethene | ND | 1.0 | 0.19 | ug/kg | |
| 75-69-4 | Trichlorofluoromethane | ND | 5.0 | 0.63 | ug/kg | |
| 75-01-4 | Vinyl chloride | ND | 2.0 | 0.20 | ug/kg | |
| | m,p-Xylene | ND | 1.0 | 0.22 | ug/kg | |
| 95-47-6 | o-Xylene | ND | 1.0 | 0.20 | ug/kg | |
| 1330-20-7 | Xylene (total) | ND | 1.0 | 0.20 | ug/kg | |

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 1868-53-7 | Dibromofluoromethane | 99% | 70-122% |
| 17060-07-0 | 1,2-Dichloroethane-D4 | 99% | 68-124% |
| 2037-26-5 | Toluene-D8 | 100% | 77-125% |
| 460-00-4 | 4-Bromofluorobenzene | 105% | 72-130% |

| CAS No. | Tentatively Identified Compounds | R.T. | Est. Conc. | Units | Q |
|---|---|---|---|---|---|
| | Total TIC, Volatile | | 0 | ug/kg | |

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| VY7259-BS | Y166757.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 67-64-1 | Acetone | 50 | 53.1 | 106 | 30-150 |
| 71-43-2 | Benzene | 50 | 46.7 | 93 | 77-122 |
| 74-97-5 | Bromochloromethane | 50 | 49.1 | 98 | 81-126 |
| 75-27-4 | Bromodichloromethane | 50 | 48.7 | 97 | 82-130 |
| 75-25-2 | Bromoform | 50 | 49.7 | 99 | 78-134 |
| 74-83-9 | Bromomethane | 50 | 48.9 | 98 | 56-141 |
| 78-93-3 | 2-Butanone (MEK) | 50 | 53.1 | 106 | 61-139 |
| 75-15-0 | Carbon disulfide | 50 | 46.6 | 93 | 68-131 |
| 56-23-5 | Carbon tetrachloride | 50 | 51.2 | 102 | 73-139 |
| 108-90-7 | Chlorobenzene | 50 | 49.8 | 100 | 79-120 |
| 75-00-3 | Chloroethane | 50 | 54.2 | 108 | 64-150 |
| 67-66-3 | Chloroform | 50 | 51.4 | 103 | 77-123 |
| 74-87-3 | Chloromethane | 50 | 49.1 | 98 | 50-140 |
| 110-82-7 | Cyclohexane | 50 | 54.3 | 109 | 66-131 |
| 96-12-8 | 1,2-Dibromo-3-chloropropane | 50 | 50.8 | 102 | 70-128 |
| 124-48-1 | Dibromochloromethane | 50 | 49.6 | 99 | 82-129 |
| 106-93-4 | 1,2-Dibromoethane | 50 | 49.2 | 98 | 83-125 |
| 95-50-1 | 1,2-Dichlorobenzene | 50 | 49.8 | 100 | 79-118 |
| 541-73-1 | 1,3-Dichlorobenzene | 50 | 48.7 | 97 | 76-119 |
| 106-46-7 | 1,4-Dichlorobenzene | 50 | 49.0 | 98 | 75-118 |
| 75-71-8 | Dichlorodifluoromethane | 50 | 54.4 | 109 | 31-170 |
| 75-34-3 | 1,1-Dichloroethane | 50 | 48.0 | 96 | 78-129 |
| 107-06-2 | 1,2-Dichloroethane | 50 | 50.1 | 100 | 77-140 |
| 75-35-4 | 1,1-Dichloroethene | 50 | 49.2 | 98 | 71-128 |
| 156-59-2 | cis-1,2-Dichloroethene | 50 | 50.0 | 100 | 73-123 |
| 156-60-5 | trans-1,2-Dichloroethene | 50 | 46.7 | 93 | 72-122 |
| 78-87-5 | 1,2-Dichloropropane | 50 | 49.2 | 98 | 80-129 |
| 10061-01-5 | cis-1,3-Dichloropropene | 50 | 49.7 | 99 | 75-124 |
| 10061-02-6 | trans-1,3-Dichloropropene | 50 | 49.2 | 98 | 75-129 |
| 100-41-4 | Ethylbenzene | 50 | 48.7 | 97 | 75-121 |
| 76-13-1 | Freon 113 | 50 | 54.2 | 108 | 67-136 |
| 591-78-6 | 2-Hexanone | 50 | 52.9 | 106 | 63-140 |
| 98-82-8 | Isopropylbenzene | 50 | 50.1 | 100 | 70-126 |
| 79-20-9 | Methyl Acetate | 50 | 51.7 | 103 | 59-131 |
| 108-87-2 | Methylcyclohexane | 50 | 46.9 | 94 | 62-131 |
| 1634-04-4 | Methyl Tert Butyl Ether | 100 | 99.5 | 100 | 77-121 |

* = Outside of Control Limits.

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| VY7259-BS | Y166757.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 108-10-1 | 4-Methyl-2-pentanone(MIBK) | 50 | 51.8 | 104 | 73-141 |
| 75-09-2 | Methylene chloride | 50 | 50.8 | 102 | 71-124 |
| 100-42-5 | Styrene | 50 | 51.2 | 102 | 79-125 |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | 50 | 48.7 | 97 | 72-121 |
| 127-18-4 | Tetrachloroethene | 50 | 49.2 | 98 | 70-135 |
| 108-88-3 | Toluene | 50 | 48.4 | 97 | 75-123 |
| 87-61-6 | 1,2,3-Trichlorobenzene | 50 | 56.1 | 112 | 76-128 |
| 120-82-1 | 1,2,4-Trichlorobenzene | 50 | 58.3 | 117 | 74-129 |
| 71-55-6 | 1,1,1-Trichloroethane | 50 | 53.0 | 106 | 75-134 |
| 79-00-5 | 1,1,2-Trichloroethane | 50 | 50.7 | 101 | 78-130 |
| 79-01-6 | Trichloroethene | 50 | 50.1 | 100 | 79-127 |
| 75-69-4 | Trichlorofluoromethane | 50 | 50.4 | 101 | 64-141 |
| 75-01-4 | Vinyl chloride | 50 | 50.3 | 101 | 57-136 |
| | m,p-Xylene | 100 | 95.1 | 95 | 75-122 |
| 95-47-6 | o-Xylene | 50 | 50.0 | 100 | 76-121 |
| 1330-20-7 | Xylene (total) | 150 | 145 | 97 | 76-121 |

| CAS No. | Surrogate Recoveries | BSP | Limits |
|---|---|---|---|
| 1868-53-7 | Dibromofluoromethane | 103% | 70-122% |
| 17060-07-0 | 1,2-Dichloroethane-D4 | 102% | 68-124% |
| 2037-26-5 | Toluene-D8 | 101% | 77-125% |
| 460-00-4 | 4-Bromofluorobenzene | 98% | 72-130% |

* = Outside of Control Limits.

# Matrix Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| JC28964-2MS | Y166764.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |
| JC28964-2 | Y166760.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | JC28964-2 ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Limits |
|---|---|---|---|---|---|---|---|
| 67-64-1 | Acetone | ND | | 61.2 | 36.8 | 60 | 10-180 |
| 71-43-2 | Benzene | ND | | 61.2 | 53.5 | 87 | 48-136 |
| 74-97-5 | Bromochloromethane | ND | | 61.2 | 51.6 | 84 | 53-137 |
| 75-27-4 | Bromodichloromethane | ND | | 61.2 | 51.7 | 85 | 50-145 |
| 75-25-2 | Bromoform | ND | | 61.2 | 47.7 | 78 | 39-148 |
| 74-83-9 | Bromomethane | ND | | 61.2 | 56.1 | 92 | 12-156 |
| 78-93-3 | 2-Butanone (MEK) | ND | | 61.2 | 41.7 | 68 | 26-164 |
| 75-15-0 | Carbon disulfide | ND | | 61.2 | 59.2 | 97 | 34-146 |
| 56-23-5 | Carbon tetrachloride | ND | | 61.2 | 58.8 | 96 | 43-152 |
| 108-90-7 | Chlorobenzene | ND | | 61.2 | 56.3 | 92 | 38-144 |
| 75-00-3 | Chloroethane | ND | | 61.2 | 60.6 | 99 | 26-154 |
| 67-66-3 | Chloroform | ND | | 61.2 | 58.6 | 96 | 52-134 |
| 74-87-3 | Chloromethane | ND | | 61.2 | 55.3 | 90 | 41-142 |
| 110-82-7 | Cyclohexane | ND | | 61.2 | 60.7 | 99 | 22-154 |
| 96-12-8 | 1,2-Dibromo-3-chloropropane | ND | | 61.2 | 46.0 | 75 | 29-145 |
| 124-48-1 | Dibromochloromethane | ND | | 61.2 | 51.3 | 84 | 49-142 |
| 106-93-4 | 1,2-Dibromoethane | ND | | 61.2 | 49.0 | 80 | 46-139 |
| 95-50-1 | 1,2-Dichlorobenzene | ND | | 61.2 | 53.8 | 88 | 30-144 |
| 541-73-1 | 1,3-Dichlorobenzene | ND | | 61.2 | 54.0 | 88 | 28-148 |
| 106-46-7 | 1,4-Dichlorobenzene | ND | | 61.2 | 53.4 | 87 | 30-142 |
| 75-71-8 | Dichlorodifluoromethane | ND | | 61.2 | 63.4 | 104 | 31-161 |
| 75-34-3 | 1,1-Dichloroethane | ND | | 61.2 | 55.8 | 91 | 54-137 |
| 107-06-2 | 1,2-Dichloroethane | ND | | 61.2 | 51.7 | 85 | 56-140 |
| 75-35-4 | 1,1-Dichloroethene | ND | | 61.2 | 60.2 | 98 | 41-143 |
| 156-59-2 | cis-1,2-Dichloroethene | ND | | 61.2 | 56.7 | 93 | 45-137 |
| 156-60-5 | trans-1,2-Dichloroethene | ND | | 61.2 | 55.4 | 91 | 42-141 |
| 78-87-5 | 1,2-Dichloropropane | ND | | 61.2 | 54.6 | 89 | 53-139 |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | | 61.2 | 51.1 | 84 | 41-144 |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | | 61.2 | 49.1 | 80 | 36-148 |
| 100-41-4 | Ethylbenzene | ND | | 61.2 | 56.1 | 92 | 34-145 |
| 76-13-1 | Freon 113 | ND | | 61.2 | 59.0 | 96 | 30-152 |
| 591-78-6 | 2-Hexanone | ND | | 61.2 | 45.1 | 74 | 16-176 |
| 98-82-8 | Isopropylbenzene | ND | | 61.2 | 58.2 | 95 | 36-145 |
| 79-20-9 | Methyl Acetate | ND | | 61.2 | 47.0 | 77 | 26-176 |
| 108-87-2 | Methylcyclohexane | ND | | 61.2 | 50.1 | 82 | 14-153 |
| 1634-04-4 | Methyl Tert Butyl Ether | ND | | 122 | 99.3 | 81 | 54-129 |

* = Outside of Control Limits.

# Matrix Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| JC28964-2MS | Y166764.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |
| JC28964-2 | Y166760.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | JC28964-2 ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Limits |
|---|---|---|---|---|---|---|---|
| 108-10-1 | 4-Methyl-2-pentanone(MIBK) | ND | | 61.2 | 47.3 | 77 | 33-154 |
| 75-09-2 | Methylene chloride | ND | | 61.2 | 55.6 | 91 | 47-133 |
| 100-42-5 | Styrene | ND | | 61.2 | 56.4 | 92 | 32-156 |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | | 61.2 | 47.7 | 78 | 31-149 |
| 127-18-4 | Tetrachloroethene | ND | | 61.2 | 56.5 | 92 | 34-163 |
| 108-88-3 | Toluene | ND | | 61.2 | 55.0 | 90 | 40-141 |
| 87-61-6 | 1,2,3-Trichlorobenzene | ND | | 61.2 | 54.2 | 89 | 14-153 |
| 120-82-1 | 1,2,4-Trichlorobenzene | ND | | 61.2 | 57.7 | 94 | 14-156 |
| 71-55-6 | 1,1,1-Trichloroethane | ND | | 61.2 | 61.7 | 101 | 48-144 |
| 79-00-5 | 1,1,2-Trichloroethane | ND | | 61.2 | 50.9 | 83 | 43-146 |
| 79-01-6 | Trichloroethene | ND | | 61.2 | 57.2 | 94 | 42-152 |
| 75-69-4 | Trichlorofluoromethane | ND | | 61.2 | 55.9 | 91 | 39-153 |
| 75-01-4 | Vinyl chloride | ND | | 61.2 | 57.6 | 94 | 38-149 |
| | m,p-Xylene | ND | | 122 | 107 | 87 | 32-148 |
| 95-47-6 | o-Xylene | ND | | 61.2 | 55.7 | 91 | 36-145 |
| 1330-20-7 | Xylene (total) | ND | | 184 | 163 | 89 | 34-146 |

| CAS No. | Surrogate Recoveries | MS | JC28964-2 | Limits |
|---|---|---|---|---|
| 1868-53-7 | Dibromofluoromethane | 99% | 102% | 70-122% |
| 17060-07-0 | 1,2-Dichloroethane-D4 | 93% | 104% | 68-124% |
| 2037-26-5 | Toluene-D8 | 100% | 101% | 77-125% |
| 460-00-4 | 4-Bromofluorobenzene | 100% | 104% | 72-130% |

* = Outside of Control Limits.

# Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| JC28964-1DUP | Y166759.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |
| JC28964-1 | Y166763.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | JC28964-1 ug/kg | Q | DUP ug/kg | Q | RPD | Limits |
|---|---|---|---|---|---|---|---|
| 67-64-1 | Acetone | 35.3 | | ND | | 200* [a] | 35 |
| 71-43-2 | Benzene | 0.26 | J | ND | | 200* [a] | 17 |
| 74-97-5 | Bromochloromethane | ND | | ND | | nc | 30 |
| 75-27-4 | Bromodichloromethane | ND | | ND | | nc | 30 |
| 75-25-2 | Bromoform | ND | | ND | | nc | 30 |
| 74-83-9 | Bromomethane | ND | | ND | | nc | 30 |
| 78-93-3 | 2-Butanone (MEK) | 5.2 | J | ND | | 200* [a] | 30 |
| 75-15-0 | Carbon disulfide | 0.81 | J | ND | | 200* [a] | 20 |
| 56-23-5 | Carbon tetrachloride | ND | | ND | | nc | 30 |
| 108-90-7 | Chlorobenzene | ND | | ND | | nc | 30 |
| 75-00-3 | Chloroethane | ND | | ND | | nc | 30 |
| 67-66-3 | Chloroform | ND | | 0.40 | J | 200* [a] | 30 |
| 74-87-3 | Chloromethane | ND | | ND | | nc | 30 |
| 110-82-7 | Cyclohexane | 2.4 | | ND | | 200* [a] | 30 |
| 96-12-8 | 1,2-Dibromo-3-chloropropane | ND | | ND | | nc | 30 |
| 124-48-1 | Dibromochloromethane | ND | | ND | | nc | 30 |
| 106-93-4 | 1,2-Dibromoethane | ND | | ND | | nc | 30 |
| 95-50-1 | 1,2-Dichlorobenzene | ND | | ND | | nc | 30 |
| 541-73-1 | 1,3-Dichlorobenzene | ND | | ND | | nc | 30 |
| 106-46-7 | 1,4-Dichlorobenzene | ND | | ND | | nc | 30 |
| 75-71-8 | Dichlorodifluoromethane | ND | | ND | | nc | 30 |
| 75-34-3 | 1,1-Dichloroethane | ND | | ND | | nc | 30 |
| 107-06-2 | 1,2-Dichloroethane | ND | | ND | | nc | 30 |
| 75-35-4 | 1,1-Dichloroethene | ND | | ND | | nc | 30 |
| 156-59-2 | cis-1,2-Dichloroethene | ND | | ND | | nc | 30 |
| 156-60-5 | trans-1,2-Dichloroethene | ND | | ND | | nc | 30 |
| 78-87-5 | 1,2-Dichloropropane | ND | | ND | | nc | 30 |
| 10061-01-5 | cis-1,3-Dichloropropene | ND | | ND | | nc | 30 |
| 10061-02-6 | trans-1,3-Dichloropropene | ND | | ND | | nc | 30 |
| 100-41-4 | Ethylbenzene | 0.27 | J | ND | | 200* [a] | 23 |
| 76-13-1 | Freon 113 | ND | | ND | | nc | 30 |
| 591-78-6 | 2-Hexanone | ND | | ND | | nc | 30 |
| 98-82-8 | Isopropylbenzene | 0.31 | J | ND | | 200* [a] | 22 |
| 79-20-9 | Methyl Acetate | ND | | ND | | nc | 30 |
| 108-87-2 | Methylcyclohexane | 23.6 | | ND | | 200* [a] | 18 |
| 1634-04-4 | Methyl Tert Butyl Ether | ND | | ND | | nc | 30 |

* = Outside of Control Limits.

# Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| JC28964-1DUP | Y166759.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |
| JC28964-1 | Y166763.D | 1 | 10/06/16 | PS | n/a | n/a | VY7259 |

**The QC reported here applies to the following samples:** **Method:** SW846 8260C

JC28902-1

| CAS No. | Compound | JC28964-1 ug/kg | Q | DUP ug/kg | Q | RPD | Limits |
|---|---|---|---|---|---|---|---|
| 108-10-1 | 4-Methyl-2-pentanone(MIBK) | ND | | ND | | nc | 30 |
| 75-09-2 | Methylene chloride | ND | | ND | | nc | 37 |
| 100-42-5 | Styrene | ND | | ND | | nc | 30 |
| 79-34-5 | 1,1,2,2-Tetrachloroethane | ND | | ND | | nc | 30 |
| 127-18-4 | Tetrachloroethene | ND | | ND | | nc | 30 |
| 108-88-3 | Toluene | 0.24 | J | ND | | 200* [a] | 22 |
| 87-61-6 | 1,2,3-Trichlorobenzene | ND | | ND | | nc | 30 |
| 120-82-1 | 1,2,4-Trichlorobenzene | ND | | ND | | nc | 30 |
| 71-55-6 | 1,1,1-Trichloroethane | ND | | ND | | nc | 30 |
| 79-00-5 | 1,1,2-Trichloroethane | ND | | ND | | nc | 30 |
| 79-01-6 | Trichloroethene | ND | | ND | | nc | 17 |
| 75-69-4 | Trichlorofluoromethane | ND | | ND | | nc | 30 |
| 75-01-4 | Vinyl chloride | ND | | ND | | nc | 30 |
| | m,p-Xylene | 0.51 | J | ND | | 200* [a] | 20 |
| 95-47-6 | o-Xylene | 0.86 | J | ND | | 200* [a] | 19 |
| 1330-20-7 | Xylene (total) | 1.4 | | ND | | 200* [a] | 21 |

| CAS No. | Surrogate Recoveries | DUP | JC28964-1 | Limits |
|---|---|---|---|---|
| 1868-53-7 | Dibromofluoromethane | 101% | 103% | 70-122% |
| 17060-07-0 | 1,2-Dichloroethane-D4 | 103% | 105% | 68-124% |
| 2037-26-5 | Toluene-D8 | 101% | 104% | 77-125% |
| 460-00-4 | 4-Bromofluorobenzene | 105% | 109% | 72-130% |

(a) Outside control limits due to different encores.

* = Outside of Control Limits.

# Instrument Performance Check (BFB)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** VY7258-BFB
**Lab File ID:** Y166738.D
**Instrument ID:** GCMSY
**Injection Date:** 10/05/16
**Injection Time:** 12:58

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 50 | 15.0 - 40.0% of mass 95 | 29648 | 21.1 | | Pass |
| 75 | 30.0 - 60.0% of mass 95 | 69402 | 49.4 | | Pass |
| 95 | Base peak, 100% relative abundance | 140400 | 100.0 | | Pass |
| 96 | 5.0 - 9.0% of mass 95 | 9399 | 6.69 | | Pass |
| 173 | Less than 2.0% of mass 174 | 0 | 0.00 | (0.00) [a] | Pass |
| 174 | 50.0 - 120.0% of mass 95 | 110045 | 78.4 | | Pass |
| 175 | 5.0 - 9.0% of mass 174 | 8437 | 6.01 | (7.67) [a] | Pass |
| 176 | 95.0 - 101.0% of mass 174 | 107696 | 76.7 | (97.9) [a] | Pass |
| 177 | 5.0 - 9.0% of mass 176 | 7186 | 5.12 | (6.67) [b] | Pass |

(a) Value is % of mass 174
(b) Value is % of mass 176

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| VY7258-IC7258 | Y166739.D | 10/05/16 | 13:36 | 00:38 | Initial cal 0.2 |
| VY7258-IC7258 | Y166740.D | 10/05/16 | 14:04 | 01:06 | Initial cal 0.5 |
| VY7258-IC7258 | Y166741.D | 10/05/16 | 14:32 | 01:34 | Initial cal 1 |
| VY7258-IC7258 | Y166742.D | 10/05/16 | 15:00 | 02:02 | Initial cal 2 |
| VY7258-IC7258 | Y166743.D | 10/05/16 | 15:28 | 02:30 | Initial cal 4 |
| VY7258-IC7258 | Y166744.D | 10/05/16 | 15:56 | 02:58 | Initial cal 8 |
| VY7258-IC7258 | Y166745.D | 10/05/16 | 16:24 | 03:26 | Initial cal 20 |
| VY7258-ICC7258 | Y166746.D | 10/05/16 | 16:53 | 03:55 | Initial cal 50 |
| VY7258-IC7258 | Y166747.D | 10/05/16 | 17:21 | 04:23 | Initial cal 100 |
| VY7258-IC7258 | Y166748.D | 10/05/16 | 17:49 | 04:51 | Initial cal 200 |
| VY7258-ICV7258 | Y166751.D | 10/05/16 | 19:14 | 06:16 | Initial cal verification 50 |

# Instrument Performance Check (BFB)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** VY7259-BFB
**Lab File ID:** Y166753.D
**Instrument ID:** GCMSY
**Injection Date:** 10/06/16
**Injection Time:** 10:47

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 50 | 15.0 - 40.0% of mass 95 | 30877 | 21.8 | | Pass |
| 75 | 30.0 - 60.0% of mass 95 | 71696 | 50.6 | | Pass |
| 95 | Base peak, 100% relative abundance | 141672 | 100.0 | | Pass |
| 96 | 5.0 - 9.0% of mass 95 | 9423 | 6.65 | | Pass |
| 173 | Less than 2.0% of mass 174 | 0 | 0.00 | (0.00) [a] | Pass |
| 174 | 50.0 - 120.0% of mass 95 | 109643 | 77.4 | | Pass |
| 175 | 5.0 - 9.0% of mass 174 | 8398 | 5.93 | (7.66) [a] | Pass |
| 176 | 95.0 - 101.0% of mass 174 | 107021 | 75.5 | (97.6) [a] | Pass |
| 177 | 5.0 - 9.0% of mass 176 | 7348 | 5.19 | (6.87) [b] | Pass |

(a) Value is % of mass 174
(b) Value is % of mass 176

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| VY7259-CC7258 | Y166754.D | 10/06/16 | 11:20 | 00:33 | Continuing cal 20 |
| VY7259-MB | Y166756.D | 10/06/16 | 12:24 | 01:37 | Method Blank |
| VY7259-BS | Y166757.D | 10/06/16 | 13:00 | 02:13 | Blank Spike |
| JC28964-1DUP | Y166759.D | 10/06/16 | 13:56 | 03:09 | Duplicate |
| JC28964-2 | Y166760.D | 10/06/16 | 14:24 | 03:37 | (used for QC only; not part of job JC28902) |
| JC28964-3 | Y166761.D | 10/06/16 | 14:52 | 04:05 | (used for QC only; not part of job JC28902) |
| ZZZZZZ | Y166762.D | 10/06/16 | 15:20 | 04:33 | (unrelated sample) |
| JC28964-1 | Y166763.D | 10/06/16 | 15:48 | 05:01 | (used for QC only; not part of job JC28902) |
| JC28964-2MS | Y166764.D | 10/06/16 | 16:16 | 05:29 | Matrix Spike |
| ZZZZZZ | Y166766.D | 10/06/16 | 17:13 | 06:26 | (unrelated sample) |
| ZZZZZZ | Y166767.D | 10/06/16 | 17:41 | 06:54 | (unrelated sample) |
| ZZZZZZ | Y166768.D | 10/06/16 | 18:09 | 07:22 | (unrelated sample) |
| ZZZZZZ | Y166769.D | 10/06/16 | 18:37 | 07:50 | (unrelated sample) |
| ZZZZZZ | Y166770.D | 10/06/16 | 19:06 | 08:19 | (unrelated sample) |
| ZZZZZZ | Y166771.D | 10/06/16 | 19:34 | 08:47 | (unrelated sample) |
| ZZZZZZ | Y166772.D | 10/06/16 | 20:02 | 09:15 | (unrelated sample) |
| ZZZZZZ | Y166773.D | 10/06/16 | 20:30 | 09:43 | (unrelated sample) |
| ZZZZZZ | Y166774.D | 10/06/16 | 20:58 | 10:11 | (unrelated sample) |
| JC28964-3DUP | Y166775.D | 10/06/16 | 21:26 | 10:39 | Duplicate |
| JC28902-1 | Y166776.D | 10/06/16 | 21:54 | 11:07 | WOOLSTON-TS-002 |
| ZZZZZZ | Y166777.D | 10/06/16 | 22:23 | 11:36 | (unrelated sample) |

# Volatile Internal Standard Area Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | VY7259-CC7258 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | Y166754.D | **Injection Time:** | 11:20 |
| **Instrument ID:** | GCMSY | **Method:** | SW846 8260C |

| | IS 1 AREA | RT | IS 2 AREA | RT | IS 3 AREA | RT | IS 4 AREA | RT | IS 5 AREA | RT |
|---|---|---|---|---|---|---|---|---|---|---|
| Check Std | 207250 | 7.12 | 438461 | 9.34 | 702778 | 10.25 | 494671 | 13.40 | 233044 | 15.71 |
| Upper Limit [a] | 414500 | 7.62 | 876922 | 9.84 | 1405556 | 10.75 | 989342 | 13.90 | 466088 | 16.21 |
| Lower Limit [b] | 103625 | 6.62 | 219231 | 8.84 | 351389 | 9.75 | 247336 | 12.90 | 116522 | 15.21 |

| Lab Sample ID | IS 1 AREA | RT | IS 2 AREA | RT | IS 3 AREA | RT | IS 4 AREA | RT | IS 5 AREA | RT |
|---|---|---|---|---|---|---|---|---|---|---|
| VY7259-MB | 189890 | 7.11 | 450817 | 9.33 | 726112 | 10.24 | 519035 | 13.40 | 224416 | 15.71 |
| VY7259-BS | 211182 | 7.12 | 438407 | 9.33 | 712045 | 10.25 | 499349 | 13.40 | 236255 | 15.71 |
| JC28964-1DUP | 225773 | 7.12 | 471009 | 9.33 | 765539 | 10.24 | 553047 | 13.40 | 239877 | 15.71 |
| JC28964-2 | 228305 | 7.12 | 462441 | 9.33 | 746100 | 10.24 | 544205 | 13.40 | 237964 | 15.71 |
| JC28964-3 | 220112 | 7.12 | 475491 | 9.33 | 773150 | 10.24 | 560467 | 13.40 | 241667 | 15.71 |
| ZZZZZZ | 221345 | 7.11 | 457506 | 9.33 | 742458 | 10.24 | 532212 | 13.40 | 235600 | 15.71 |
| JC28964-1 | 235825 | 7.12 | 477465 | 9.33 | 784176 | 10.24 | 560475 | 13.40 | 240827 | 15.71 |
| JC28964-2MS | 172075 | 7.11 | 477485 | 9.33 | 780754 | 10.24 | 536100 | 13.40 | 245738 | 15.71 |
| ZZZZZZ | 224967 | 7.11 | 471990 | 9.33 | 772252 | 10.24 | 551240 | 13.40 | 227284 | 15.71 |
| ZZZZZZ | 236455 | 7.11 | 460548 | 9.33 | 754302 | 10.24 | 549486 | 13.40 | 234477 | 15.71 |
| ZZZZZZ | 238555 | 7.12 | 475717 | 9.33 | 778798 | 10.24 | 559392 | 13.40 | 239460 | 15.71 |
| ZZZZZZ | 254139 | 7.12 | 461856 | 9.33 | 767808 | 10.24 | 561452 | 13.40 | 247073 | 15.71 |
| ZZZZZZ | 239023 | 7.11 | 456330 | 9.33 | 749096 | 10.24 | 542088 | 13.40 | 237096 | 15.71 |
| ZZZZZZ | 266193 | 7.12 | 465247 | 9.33 | 767579 | 10.24 | 557811 | 13.40 | 239885 | 15.71 |
| ZZZZZZ | 210513 | 7.11 | 469800 | 9.33 | 768831 | 10.24 | 559250 | 13.40 | 238827 | 15.71 |
| ZZZZZZ | 199302 | 7.11 | 444538 | 9.33 | 729759 | 10.24 | 522204 | 13.40 | 224150 | 15.71 |
| ZZZZZZ | 209506 | 7.11 | 465690 | 9.33 | 765480 | 10.24 | 544409 | 13.40 | 230564 | 15.71 |
| JC28964-3DUP | 226008 | 7.11 | 435516 | 9.33 | 729365 | 10.24 | 535178 | 13.40 | 229919 | 15.71 |
| JC28902-1 | 154672 | 7.11 | 443977 | 9.33 | 722047 | 10.24 | 488363 | 13.40 | 169486 | 15.71 |
| ZZZZZZ | 225252 | 7.12 | 455552 | 9.33 | 756181 | 10.24 | 548333 | 13.40 | 232113 | 15.71 |

**IS 1** = Tert Butyl Alcohol-D9
**IS 2** = Pentafluorobenzene
**IS 3** = 1,4-Difluorobenzene
**IS 4** = Chlorobenzene-D5
**IS 5** = 1,4-Dichlorobenzene-d4

(a) Upper Limit = + 100% of check standard area; Retention time + 0.5 minutes.
(b) Lower Limit = -50% of check standard area; Retention time -0.5 minutes.

# Volatile Surrogate Recovery Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Method:** SW846 8260C **Matrix:** SO

**Samples and QC shown here apply to the above method**

| Lab Sample ID | Lab File ID | S1 | S2 | S3 | S4 |
|---|---|---|---|---|---|
| JC28902-1 | Y166776.D | 105 | 109 | 100 | 121 |
| JC28964-1DUP | Y166759.D | 101 | 103 | 101 | 105 |
| JC28964-2MS | Y166764.D | 99 | 93 | 100 | 100 |
| VY7259-BS | Y166757.D | 103 | 102 | 101 | 98 |
| VY7259-MB | Y166756.D | 99 | 99 | 100 | 105 |

| Surrogate Compounds | Recovery Limits |
|---|---|
| **S1** = Dibromofluoromethane | 70-122% |
| **S2** = 1,2-Dichloroethane-D4 | 68-124% |
| **S3** = Toluene-D8 | 77-125% |
| **S4** = 4-Bromofluorobenzene | 72-130% |

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** VY7258-ICC7258
**Lab FileID:** Y166746.D

Response Factor Report MSY

Method : C:\MSDCHEM\1\METHODS\MYS7258.M (RTE Integrator)
Title : Method SW846 8260C, ZB624 60m x 0.25mm x 1.4um
Last Update : Fri Oct 07 09:37:12 2016
Response via : Initial Calibration

Calibration Files
4 =Y166743.D 8 =Y166744.D 0.5 =Y166740.D 50 =Y166746.D
100 =Y166747.D 1 =Y166741.D 200 =Y166748.D 20 =Y166745.D
2 =Y166742.D 0.2 =Y166739.D = =

| Compound | 4 | 8 | 0.5 | 50 | 100 | 1 | 200 | 20 | 2 | 0.2 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) I Tert Butyl Alcohol-d9 | ----------ISTD---------- | | | | | | | | | | | |
| 2) 1,4-dioxane | 0.105 | 0.121 | | 0.119 | 0.114 | | 0.125 | 0.123 | | | 0.118 | 6.23 |
| 3) tertiary butyl alcohol | 1.483 | 1.471 | | 1.428 | 1.374 | | 1.518 | 1.469 | 1.466 | | 1.458 | 3.12 |
| 4) I pentafluorobenzene | ----------ISTD---------- | | | | | | | | | | | |
| 5) propene | | | | | | | | | | | 0.000 | -1.00 |
| 6) chlorodifluoromethane | 0.830 | 0.824 | | 0.800 | 0.761 | | 0.760 | 0.833 | 0.854 | | 0.809 | 4.54 |
| 7) dichlorodifluoromethane | 0.753 | 0.699 | | 0.686 | 0.646 | 0.664 | 0.655 | 0.699 | 0.658 | | 0.683 | 5.12 |
| 8) chloromethane | 1.268 | 0.971 | | 0.877 | 0.855 | | 0.875 | 0.898 | | | 0.957 | 16.43 |
| 9) vinyl chloride | 0.959 | 0.889 | | 0.829 | 0.792 | 0.910 | 0.793 | 0.844 | 0.846 | | 0.858 | 6.77 |
| 10) 1,3-butadiene | | | | | | | | | | | 0.000 | -1.00 |
| 11) bromomethane | 0.610 | 0.494 | | 0.436 | 0.360 | | 0.466 | | | | 0.473 | 19.27 |
| 12) chloroethane | 0.479 | 0.439 | | 0.401 | 0.365 | 0.441 | 0.332 | 0.423 | 0.416 | | 0.412 | 11.23 |
| 13) Vinyl Bromide | 0.758 | 0.697 | 0.740 | 0.656 | 0.619 | 0.658 | 0.624 | 0.673 | 0.651 | | 0.675 | 7.16 |
| 14) trichlorofluoromethane | 0.875 | 0.777 | | 0.747 | 0.717 | | 0.734 | 0.759 | | | 0.768 | 7.33 |
| 15) ethyl ether | 0.356 | 0.319 | | 0.312 | 0.308 | 0.320 | 0.314 | 0.323 | 0.350 | | 0.325 | 5.47 |
| 16) 2-chloropropane | | | | | | | | | | | 0.000 | -1.00 |
| 17) acrolein | 0.105 | 0.101 | | 0.098 | 0.091 | | 0.092 | 0.100 | 0.104 | | 0.099 | 5.35 |
| 18) 1,1-dichloroethene | 1.008 | 0.978 | | 0.900 | 0.882 | 0.852 | 0.895 | 0.957 | 1.045 | | 0.940 | 7.22 |
| 19) acetone | | 0.268 | | 0.170 | 0.188 | | 0.205 | 0.237 | | | 0.213 | 18.34 |
| 20) allyl chloride | 0.392 | 0.361 | | 0.367 | 0.351 | | 0.357 | 0.390 | 0.434 | | 0.379 | 7.63 |
| 21) acetonitrile | 0.055 | 0.054 | | 0.051 | 0.047 | | 0.049 | 0.051 | | | 0.051 | 5.69 |
| 22) iodomethane | 1.082 | 1.008 | | 0.937 | 0.932 | 0.829 | 0.960 | 0.996 | 1.019 | | 0.970 | 7.75 |
| 23) carbon disulfide | | | | | | | | | | | | |

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** VY7258-ICC7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166746.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

```
      2.274 2.164       1.966 1.911 1.928 1.959 2.062 2.237        2.063    7.02
24)  1-chloropropane
                                                                   0.000   -1.00
25)  methylene chloride
      1.016 0.769       0.646 0.623       0.627 0.691              0.729   20.74
            ----- Linear regression -----  Coefficient =  0.9998
              Response Ratio = 0.02952 + 0.61555 *A

26)  methyl acetate
      0.440 0.378       0.392 0.370       0.381 0.398              0.393    6.35
27)  methyl tert butyl ether
      1.864 1.729       1.667 1.637 1.618 1.677 1.714 1.938        1.730    6.54
28)  trans-1,2-dichloroethene
      1.057 1.007 1.155 0.933 0.915 0.935 0.927 0.988 1.049 1.059  1.002    7.76
29)  di-isopropyl ether
      2.494 2.573 2.197 2.345 2.290 2.254 2.328 2.415 2.463        2.373    5.15
30)  ethyl tert-butyl ether
      2.139 2.191 1.935 2.063 2.030 1.997 2.086 2.093 2.085        2.069    3.65
31)  2-butanone
      0.057 0.062       0.056 0.058       0.063 0.063              0.060    5.02
32)  1,1-dichloroethane
      1.323 1.230 1.470 1.122 1.103 1.063 1.109 1.203 1.280 1.300  1.220   10.35
33)  chloroprene
      0.945 0.997 0.860 0.913 0.894 0.882 0.921 0.944 0.970        0.925    4.71
34)  acrylonitrile
      0.199 0.178       0.180 0.173 0.162 0.178 0.189 0.187        0.181    6.10
35)  vinyl acetate
      0.065 0.078       0.085 0.082       0.084 0.086              0.080    9.68
36)  ethyl acetate
      0.109 0.089       0.079 0.075       0.075 0.086              0.086   14.98
37)  2,2-dichloropropane
      1.019 0.959       0.871 0.854 0.956 0.866 0.922 1.087        0.942    8.66
38)  cis-1,2-dichloroethene
      0.734 0.649       0.620 0.609 0.556 0.609 0.658 0.696        0.641    8.71
39)  propionitrile
      0.074 0.067       0.068 0.065       0.066 0.070              0.068    4.68
40)  bromochloromethane
      0.391 0.369 0.402 0.360 0.355 0.317 0.360 0.371 0.399        0.369    7.13
41)  tetrahydrofuran
            0.076       0.066 0.063       0.064 0.070              0.068    8.02
42)  chloroform
      1.172 1.087       1.018 1.015 1.017 1.043 1.067 1.184        1.075    6.36
43)  tert-Butyl Formate
      0.589 0.592       0.571 0.558 0.528 0.574 0.566 0.556        0.567    3.62
44)  isobutyl alcohol
                                                                   0.000   -1.00
45)  dibromofluoromethane (s)
      0.528 0.522 0.523 0.524 0.522 0.530 0.513 0.522 0.533 0.536  0.525    1.26
46)  1,2-dichloroethane-d4 (s)
      0.566 0.543 0.556 0.552 0.545 0.558 0.536 0.547 0.565 0.563  0.553    1.86
47)  freon 113
      0.399 0.421       0.375 0.362       0.351 0.391 0.400        0.385    6.32
48)  methacrylonitrile
      0.207 0.183       0.192 0.189       0.197 0.198 0.168        0.191    6.65
49)  1,1,1-trichloroethane
      0.919 0.848       0.804 0.808 0.756 0.832 0.840 0.913        0.840    6.56
50)  Cyclohexane
      0.871 0.868 0.750 0.786 0.751 0.769 0.751 0.825 0.906        0.808    7.50
51)  2,2,4-trimethylpentane
      2.596 2.664 2.440 2.554 2.422 2.295 2.366 2.549 2.602 2.490  2.498    4.65
```

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** VY7258-ICC7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166746.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

```
52)  tert-amyl methyl ether
      1.862 1.915       1.801 1.756 1.845 1.789 1.829 1.843        1.830    2.66

53) I   1,4-difluorobenzene   ----------------ISTD---------------------
54)  epichlorohydrin
      0.030 0.030       0.028 0.027       0.028 0.029 0.025        0.028    6.12
55)  n-butyl alcohol
      0.009 0.009       0.010 0.010       0.010 0.010 0.007        0.009   12.32
56)  carbon tetrachloride
      0.501 0.483       0.444 0.445 0.432 0.459 0.478 0.520        0.470    6.51
57)  1,1-dichloropropene
      0.502 0.496       0.455 0.451 0.432 0.460 0.493 0.530        0.477    6.89
58)  hexane   **This compound does not meet IC QC criteria**
      0.568 0.582       0.528 0.500 0.577 0.493 0.551 0.595        0.549    6.99
59)  Tert Amyl Alcohol
                                                                   0.000   -1.00
60)  benzene
      1.636 1.544 1.977 1.391 1.375 1.491 1.381 1.496 1.641        1.548   12.28
61)  heptane
      0.316 0.319 0.313 0.295 0.282 0.279 0.283 0.304 0.313        0.300    5.35
62)  isopropyl acetate
      0.046 0.055       0.053 0.053       0.054 0.057 0.050        0.053    6.42
63)  1,2-dichloroethane
      0.529 0.487       0.463 0.459 0.446 0.476 0.491 0.515        0.483    5.85
64)  trichloroethene
      0.376 0.366       0.334 0.335 0.318 0.341 0.357 0.381        0.351    6.43
65)  ethyl acrylate
      0.339 0.314       0.321 0.318       0.333 0.334 0.304        0.323    3.91
66)  2-nitropropane **This compound does not meet IC QC criteria**
      0.122 0.109       0.094 0.093       0.098 0.097              0.102   10.91
67)  2-chloroethyl vinyl ether
      0.078 0.081       0.079 0.077 0.068 0.081 0.078 0.070        0.076    6.37
68)  methyl methacrylate
      0.055 0.055       0.060 0.059       0.061 0.063 0.053        0.058    6.60
69)  1,2-dichloropropane
      0.436 0.421       0.380 0.379 0.361 0.375 0.416 0.437        0.401    7.50
70)  methylcyclohexane
      0.718 0.744 0.666 0.680 0.640 0.664 0.608 0.708 0.733 0.682  0.684    6.21
71)  Tert-amyl ethyl ether
                                                                   0.000   -1.00
72)  dibromomethane
      0.221 0.208 0.213 0.199 0.193 0.190 0.197 0.211 0.213        0.205    5.15
73)  bromodichloromethane
      0.528 0.493 0.540 0.475 0.481 0.432 0.496 0.503 0.507        0.495    6.36
74)  cis-1,3-dichloropropene
      0.614 0.578 0.614 0.551 0.547 0.506 0.563 0.584 0.614 0.606  0.578    6.29
75)  toluene-d8 (s)
      1.104 1.101 1.093 1.088 1.086 1.094 1.074 1.107 1.101 1.113  1.096    1.06
76)  4-methyl-2-pentanone
      0.118 0.108       0.112 0.108       0.110 0.116 0.101        0.111    5.05
77)  toluene
      1.407 1.349       1.211 1.207 1.281 1.208 1.308 1.419        1.299    6.71
78)  3-methyl-1-butanol
      0.007 0.007       0.008 0.007       0.008 0.008 0.006        0.007    9.71
79)  trans-1,3-dichloropropene
      0.531 0.491       0.463 0.454 0.449 0.450 0.493 0.535        0.483    7.25
80)  ethyl methacrylate
      0.349 0.326       0.335 0.329 0.274 0.328 0.348 0.325        0.327    7.09
81)  1,1,2-trichloroethane
      0.233 0.219 0.228 0.211 0.203 0.189 0.200 0.223 0.233 0.180  0.212    8.71
```

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** VY7258-ICC7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166746.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

82) 2-hexanone
0.099 0.088 0.089 0.087 0.088 0.094 0.091 0.091 4.55

83) I chlorobenzene-d5 ----------ISTD----------
84) tetrachloroethene
0.425 0.421 0.399 0.399 0.365 0.433 0.431 0.438 0.414 6.00
85) 1,3-dichloropropane
0.656 0.608 0.658 0.583 0.566 0.538 0.574 0.618 0.627 0.603 6.79
86) butyl acetate
0.244 0.243 0.252 0.243 0.248 0.258 0.248 2.51
87) dibromochloromethane
0.456 0.422 0.432 0.424 0.430 0.353 0.445 0.430 0.445 0.426 6.92
88) 1,2-dibromoethane
0.371 0.349 0.341 0.343 0.338 0.300 0.347 0.355 0.352 0.344 5.59
89) 3,3-Dimethyl-1-Butanol
0.043 0.039 0.043 0.041 0.039 0.044 0.043 0.041 0.041 4.54
90) n-butyl ether
2.029 1.946 1.858 1.836 1.873 1.932 1.985 1.923 3.67
91) chlorobenzene
1.141 1.097 1.020 1.018 0.924 1.066 1.071 1.131 1.058 6.68
92) 1,1,1,2-tetrachloroethane
0.462 0.435 0.475 0.408 0.413 0.386 0.426 0.430 0.447 0.431 6.40
93) ethylbenzene
2.052 1.942 1.762 1.761 1.796 1.784 1.893 2.071 1.883 6.80
94) m,p-xylene
0.765 0.718 0.900 0.657 0.649 0.675 0.655 0.698 0.758 0.719 11.17
95) o-xylene
1.709 1.616 1.495 1.484 1.491 1.497 1.587 1.713 1.574 6.20
96) styrene
1.146 1.103 1.076 1.072 0.962 1.094 1.114 1.145 1.089 5.36
97) bromoform
0.259 0.244 0.270 0.247 0.249 0.213 0.266 0.252 0.262 0.251 6.66
98) butyl acrylate
0.000 -1.00

99) I 1,4-dichlorobenzene-d ----------ISTD----------
100) isopropylbenzene
4.067 3.956 3.654 3.600 3.616 3.699 3.912 4.132 3.830 5.56
101) 4-bromofluorobenzene (s)
1.091 1.097 1.112 1.065 1.063 1.136 1.061 1.086 1.103 1.110 1.092 2.22
102) cis-1,4-dichloro-2-butene
0.000 -1.00
103) bromobenzene
1.078 0.990 0.905 0.885 0.912 0.919 0.967 1.059 0.964 7.56
104) cyclohexanone
0.157 0.170 0.129 0.140 0.153 0.155 0.176 0.166 0.156 9.88
105) 1,1,2,2-tetrachloroethane
1.021 0.932 0.888 0.844 0.876 0.860 0.959 0.982 0.920 6.88
106) trans-1,4-dichloro-2-butene
0.272 0.252 0.243 0.237 0.206 0.252 0.254 0.233 0.244 7.90
107) 1,2,3-trichloropropane
0.229 0.205 0.198 0.187 0.192 0.209 0.203 7.33
108) n-propylbenzene
4.904 4.771 4.276 4.162 4.373 4.238 4.612 4.752 4.511 6.28
109) 4-Ethyltoluene
0.000 -1.00
110) 2-chlorotoluene
1.005 0.963 0.890 0.856 0.834 0.865 0.950 1.056 0.927 8.49
111) 4-chlorotoluene
3.233 3.016 2.758 2.709 2.874 2.820 2.940 3.293 2.955 7.23

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** VY7258-ICC7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166746.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

```
112)  1,3,5-trimethylbenzene
       3.586 3.452       3.183 3.113 3.090 3.149 3.443 3.543        3.320    6.20
113)  tert-butylbenzene
       0.582 0.550       0.532 0.539 0.515 0.560 0.578 0.559        0.552    4.16
114)  pentachloroethane
       0.671 0.619 0.694 0.618 0.606 0.595 0.624 0.625 0.631        0.632    4.98
115)  1,2,4-trimethylbenzene
       3.643 3.453       3.225 3.176 3.188 3.266 3.436 3.652        3.380    5.78
116)  sec-butylbenzene
       4.363 4.235 4.902 3.975 3.905 3.653 4.033 4.211 4.392 4.450  4.212    8.24
117)  1,3-dichlorobenzene
       2.008 1.856       1.751 1.716 1.668 1.807 1.861 1.923        1.824    6.14
118)  p-isopropyltoluene
       3.576 3.483       3.314 3.271 3.025 3.376 3.495 3.728        3.408    6.26
119)  1,4-dichlorobenzene
       1.938 1.818       1.704 1.680 1.626 1.778 1.820 1.931        1.787    6.33
120)  1,2-dichlorobenzene
       1.843 1.743       1.671 1.625 1.534 1.712 1.766 1.812        1.713    5.93
121)  n-butylbenzene
       1.944 1.893 2.074 1.834 1.766 1.540 1.814 1.917 1.895        1.853    7.91
122)  p-Diethylbenzene
                                                                    0.000   -1.00
123)  1,2-dibromo-3-chloropropane
       0.166 0.148       0.159 0.154       0.165 0.161 0.161        0.159    3.93
124)  1,3,5-Trichlorobenzene
       1.480 1.444 1.516 1.455 1.392 1.149 1.500 1.473 1.419 1.553  1.438    7.78
125)  1,2,4-trichlorobenzene
       1.036 1.049       1.227 1.196       1.313 1.181 0.912        1.131   12.13
126)  1,2,4,5-tetramethylbenzene
                                                                    0.000   -1.00
127)  hexachlorobutadiene
       0.929 0.884       0.860 0.832 0.773 0.876 0.910 0.910        0.872    5.79
128)  naphthalene
       1.683 1.699       2.084 2.107       2.299 1.974              1.974   12.31
129)  1,2,3-trichlorobenzene
       0.927 0.902       1.071 1.063       1.156 1.039 0.825        0.998   11.62
130)  hexachloroethane
       0.626 0.604       0.596 0.611 0.523 0.657 0.617 0.626        0.607    6.41
131)  Benzyl chloride
       1.584 1.704       1.592 1.510 1.748 1.581 1.645 1.654        1.627    4.68
132)  2-ethylhexyl acrylate
                                                                    0.000   -1.00
 ------------------------------------------------------------------------------
 (#) = Out of Range  ###  Number of calibration levels exceeded format  ###

           MYS7258.M         Fri Oct 07 11:26:07 2016   RPT1
```

# Initial Calibration Verification



**Job Number:** JC28902 **Sample:** VY7258-ICV7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166751.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\Y166751.D Vial: 14
Acq On : 5 Oct 2016 7:14 pm Operator: prashans
Sample : ICV7258-50 Inst : MSY
Misc : MS7637,VY7258,5.0,,,,1 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MYS7258.M (RTE Integrator)
Title : Method SW846 8260C, ZB624 60m x 0.25mm x 1.4um
Last Update : Fri Oct 07 09:37:12 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | Tert Butyl Alcohol-d9 | 1.000 | 1.000 | 0.0 | 100 | 0.00 | 7.12 |
| 2 | | 1,4-dioxane | 0.118 | 0.112 | 5.1 | 94 | 0.00 | 10.96 |
| 3 | | tertiary butyl alcohol | 1.458 | 1.445 | 0.9 | 102 | 0.00 | 7.23 |
| 4 | I | pentafluorobenzene | 1.000 | 1.000 | 0.0 | 102 | 0.00 | 9.33 |
| 5 | | propene | | ----------NA---------- | | | | |
| 6 | | chlorodifluoromethane | 0.809 | 0.725 | 10.4 | 92 | 0.00 | 3.90 |
| 7 | | dichlorodifluoromethane | 0.683 | 0.586 | 14.2 | 87 | 0.00 | 3.89 |
| 8 | | chloromethane | 0.957 | 0.800 | 16.4 | 93 | 0.00 | 4.19 |
| 9 | | vinyl chloride | 0.858 | 0.727 | 15.3 | 89 | 0.00 | 4.45 |
| 10 | | 1,3-butadiene | | ----------NA---------- | | | | |
| 11 | | bromomethane | 0.473 | 0.412 | 12.9 | 96 | 0.00 | 5.06 |
| 12 | | chloroethane | 0.412 | 0.378 | 8.3 | 96 | 0.00 | 5.21 |
| 13 | | Vinyl Bromide | 0.675 | 0.638 | 5.5 | 99 | 0.00 | 5.56 |
| 14 | | trichlorofluoromethane | 0.768 | 0.659 | 14.2 | 90 | 0.00 | 5.68 |
| 15 | | ethyl ether | 0.325 | 0.319 | 1.8 | 104 | 0.00 | 6.06 |
| 16 | | 2-chloropropane | | ----------NA---------- | | | | |
| 17 | | acrolein | 0.099 | 0.110 | -11.1 | 114 | -0.01 | 6.28 |
| 18 | | 1,1-dichloroethene | 0.940 | 0.868 | 7.7 | 98 | 0.00 | 6.47 |
| 19 | | acetone | 0.213 | 0.173 | 18.8 | 104 | 0.00 | 6.49 |
| 20 | | allyl chloride | 0.379 | 0.353 | 6.9 | 98 | 0.00 | 6.97 |
| 21 | | acetonitrile | 0.051 | 0.048 | 5.9 | 97 | -0.01 | 6.90 |
| 22 | | iodomethane | 0.970 | 0.897 | 7.5 | 97 | 0.00 | 6.74 |
| 23 | | carbon disulfide | 2.063 | 1.868 | 9.5 | 97 | 0.00 | 6.88 |
| 24 | | 1-chloropropane | | ----------NA---------- | | | | |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 25 | | methylene chloride | 50.000 | 49.617 | 0.8 | 101 | 0.00 | 7.15 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 26 | | methyl acetate | 0.393 | 0.395 | -0.5 | 102 | 0.00 | 6.96 |
| 27 | | methyl tert butyl ether | 1.730 | 1.678 | 3.0 | 102 | 0.00 | 7.49 |
| 28 | | trans-1,2-dichloroethene | 1.002 | 0.895 | 10.7 | 97 | 0.00 | 7.54 |
| 29 | | di-isopropyl ether | 2.373 | 2.418 | -1.9 | 105 | 0.00 | 8.09 |
| 30 | | ethyl tert-butyl ether | 2.069 | 2.164 | -4.6 | 107 | 0.00 | 8.55 |
| 31 | | 2-butanone | 0.060 | 0.056 | 6.7 | 101 | 0.00 | 8.76 |
| 32 | | 1,1-dichloroethane | 1.220 | 1.115 | 8.6 | 101 | 0.00 | 8.09 |
| 33 | | chloroprene | 0.925 | 0.892 | 3.6 | 99 | 0.00 | 8.20 |
| 34 | | acrylonitrile | 0.181 | 0.186 | -2.8 | 105 | 0.00 | 7.45 |
| 35 | | vinyl acetate | 0.080 | 0.088 | -10.0 | 104 | 0.00 | 8.07 |
| 36 | | ethyl acetate | 0.086 | 0.081 | 5.8 | 104 | 0.00 | 8.80 |
| 37 | | 2,2-dichloropropane | 0.942 | 0.838 | 11.0 | 98 | 0.00 | 8.83 |

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** VY7258-ICV7258
**Lab FileID:** Y166751.D

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 38 | | cis-1,2-dichloroethene | 0.641 | 0.616 | 3.9 | 101 | 0.00 | 8.81 |
| 39 | | propionitrile | 0.068 | 0.069 | -1.5 | 103 | 0.00 | 8.84 |
| 40 | | bromochloromethane | 0.369 | 0.359 | 2.7 | 101 | 0.00 | 9.12 |
| 41 | | tetrahydrofuran | 0.068 | 0.068 | 0.0 | 105 | 0.00 | 9.16 |
| 42 | | chloroform | 1.075 | 1.068 | 0.7 | 107 | 0.00 | 9.17 |
| 43 | | tert-Butyl Formate | 0.567 | 0.437 | 22.9 | 78 | 0.00 | 9.22 |
| 44 | | isobutyl alcohol | | ----------NA---------- | | | | |
| 45 | S | dibromofluoromethane (s) | 0.525 | 0.532 | -1.3 | 103 | 0.00 | 9.37 |
| 46 | S | 1,2-dichloroethane-d4 (s) | 0.553 | 0.558 | -0.9 | 103 | 0.00 | 9.79 |
| 47 | | freon 113 | 0.385 | 0.373 | 3.1 | 101 | 0.00 | 6.46 |
| 48 | | methacrylonitrile | 0.191 | 0.186 | 2.6 | 98 | 0.00 | 9.03 |
| 49 | | 1,1,1-trichloroethane | 0.840 | 0.813 | 3.2 | 103 | 0.00 | 9.45 |
| 50 | | Cyclohexane | 0.808 | 0.764 | 5.4 | 99 | 0.00 | 9.54 |
| 51 | | 2,2,4-trimethylpentane | 2.498 | 2.429 | 2.8 | 97 | 0.00 | 9.91 |
| 52 | | tert-amyl methyl ether | 1.830 | 1.822 | 0.4 | 103 | 0.00 | 9.92 |
| 53 | I | 1,4-difluorobenzene | 1.000 | 1.000 | 0.0 | 101 | 0.00 | 10.24 |
| 54 | | epichlorohydrin | 0.028 | 0.028 | 0.0 | 103 | 0.00 | 11.48 |
| 55 | | n-butyl alcohol | 0.009 | 0.010 | -11.1 | 96 | 0.00 | 10.35 |
| 56 | | carbon tetrachloride | 0.470 | 0.433 | 7.9 | 99 | 0.00 | 9.65 |
| 57 | | 1,1-dichloropropene | 0.477 | 0.449 | 5.9 | 100 | 0.00 | 9.62 |
| 58 | | hexane | 0.549 | 0.336 | 38.8# | 65 | 0.00 | 7.86 |
| 59 | | Tert Amyl Alcohol | | ----------NA---------- | | | | |
| 60 | | benzene | 1.548 | 1.377 | 11.0 | 100 | 0.00 | 9.88 |
| 61 | | heptane | 0.300 | 0.281 | 6.3 | 97 | 0.00 | 10.08 |
| 62 | | isopropyl acetate | 0.053 | 0.054 | -1.9 | 104 | 0.00 | 9.79 |
| 63 | | 1,2-dichloroethane | 0.483 | 0.474 | 1.9 | 104 | 0.00 | 9.87 |
| 64 | | trichloroethene | 0.351 | 0.330 | 6.0 | 100 | 0.00 | 10.60 |
| 65 | | ethyl acrylate | 0.323 | 0.333 | -3.1 | 105 | 0.00 | 10.59 |
| 66 | | 2-nitropropane | 0.102 | 0.094 | 7.8 | 102 | 0.00 | 11.33 |
| 67 | | 2-chloroethyl vinyl ether | 0.076 | 0.081 | -6.6 | 105 | 0.00 | 11.38 |
| 68 | | methyl methacrylate | 0.058 | 0.060 | -3.4 | 101 | 0.00 | 10.86 |
| 69 | | 1,2-dichloropropane | 0.401 | 0.382 | 4.7 | 102 | 0.00 | 10.84 |
| 70 | | methylcyclohexane | 0.684 | 0.564 | 17.5 | 84 | 0.00 | 10.84 |
| 71 | | Tert-amyl ethyl ether | | ----------NA---------- | | | | |
| 72 | | dibromomethane | 0.205 | 0.201 | 2.0 | 103 | 0.00 | 11.00 |
| 73 | | bromodichloromethane | 0.495 | 0.468 | 5.5 | 100 | 0.00 | 11.13 |
| 74 | | cis-1,3-dichloropropene | 0.578 | 0.556 | 3.8 | 102 | 0.00 | 11.60 |
| 75 | S | toluene-d8 (s) | 1.096 | 1.088 | 0.7 | 101 | 0.00 | 11.90 |
| 76 | | 4-methyl-2-pentanone | 0.111 | 0.109 | 1.8 | 99 | 0.00 | 11.69 |
| 77 | | toluene | 1.299 | 1.195 | 8.0 | 100 | 0.00 | 11.97 |
| 78 | | 3-methyl-1-butanol | 0.007 | 0.008 | -14.3 | 99 | 0.00 | 11.70 |
| 79 | | trans-1,3-dichloropropene | 0.483 | 0.462 | 4.3 | 101 | 0.00 | 12.15 |
| 80 | | ethyl methacrylate | 0.327 | 0.330 | -0.9 | 100 | 0.00 | 12.16 |
| 81 | | 1,1,2-trichloroethane | 0.212 | 0.208 | 1.9 | 100 | 0.00 | 12.36 |
| 82 | | 2-hexanone | 0.091 | 0.087 | 4.4 | 99 | 0.00 | 12.54 |
| 83 | I | chlorobenzene-d5 | 1.000 | 1.000 | 0.0 | 101 | 0.00 | 13.40 |
| 84 | | tetrachloroethene | 0.414 | 0.388 | 6.3 | 98 | 0.00 | 12.56 |
| 85 | | 1,3-dichloropropane | 0.603 | 0.584 | 3.2 | 101 | 0.00 | 12.55 |
| 86 | | butyl acetate | 0.248 | 0.257 | -3.6 | 103 | 0.00 | 12.63 |
| 87 | | dibromochloromethane | 0.426 | 0.420 | 1.4 | 100 | 0.00 | 12.81 |
| 88 | | 1,2-dibromoethane | 0.344 | 0.337 | 2.0 | 99 | 0.00 | 12.96 |
| 89 | | 3,3-Dimethyl-1-Butanol | 0.041 | 0.042 | -2.4 | 99 | 0.00 | 12.71 |
| 90 | | n-butyl ether | 1.923 | 2.195 | -14.1 | 119 | 0.00 | 13.37 |
| 91 | | chlorobenzene | 1.058 | 1.025 | 3.1 | 101 | 0.00 | 13.43 |
| 92 | | 1,1,1,2-tetrachloroethane | 0.431 | 0.406 | 5.8 | 100 | 0.00 | 13.49 |
| 93 | | ethylbenzene | 1.883 | 1.747 | 7.2 | 100 | 0.00 | 13.49 |
| 94 | | m,p-xylene | 0.719 | 0.646 | 10.2 | 99 | 0.00 | 13.60 |
| 95 | | o-xylene | 1.574 | 1.490 | 5.3 | 101 | 0.00 | 14.01 |

# Initial Calibration Verification



**Job Number:** JC28902 **Sample:** VY7258-ICV7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166751.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 96 | | styrene | 1.089 | 1.080 | 0.8 | 101 | 0.00 | 14.02 |
| 97 | | bromoform | 0.251 | 0.245 | 2.4 | 100 | 0.00 | 14.27 |
| 98 | | butyl acrylate | | ----------NA---------- | | | | |
| 99 | I | 1,4-dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 103 | 0.00 | 15.71 |
| 100 | | isopropylbenzene | 3.830 | 3.475 | 9.3 | 98 | 0.00 | 14.35 |
| 101 | S | 4-bromofluorobenzene (s) | 1.092 | 1.064 | 2.6 | 103 | 0.00 | 14.54 |
| 102 | | cis-1,4-dichloro-2-butene | | ----------NA---------- | | | | |
| 103 | | bromobenzene | 0.964 | 0.887 | 8.0 | 101 | 0.00 | 14.74 |
| 104 | | cyclohexanone | 0.156 | 0.112 | 28.2 | 89 | 0.00 | 14.49 |
| 105 | | 1,1,2,2-tetrachloroethane | 0.920 | 0.849 | 7.7 | 98 | 0.00 | 14.63 |
| 106 | | trans-1,4-dichloro-2-bute | 0.244 | 0.247 | -1.2 | 104 | 0.00 | 14.68 |
| 107 | | 1,2,3-trichloropropane | 0.203 | 0.189 | 6.9 | 98 | 0.00 | 14.71 |
| 108 | | n-propylbenzene | 4.511 | 4.190 | 7.1 | 101 | 0.00 | 14.76 |
| 109 | | 4-Ethyltoluene | | ----------NA---------- | | | | |
| 110 | | 2-chlorotoluene | 0.927 | 0.844 | 9.0 | 97 | 0.00 | 14.90 |
| 111 | | 4-chlorotoluene | 2.955 | 2.662 | 9.9 | 99 | 0.00 | 14.99 |
| 112 | | 1,3,5-trimethylbenzene | 3.320 | 3.030 | 8.7 | 98 | 0.00 | 14.91 |
| 113 | | tert-butylbenzene | 0.552 | 0.524 | 5.1 | 101 | 0.00 | 15.26 |
| 114 | | pentachloroethane | 0.632 | 0.608 | 3.8 | 101 | 0.00 | 15.33 |
| 115 | | 1,2,4-trimethylbenzene | 3.380 | 3.165 | 6.4 | 101 | 0.00 | 15.30 |
| 116 | | sec-butylbenzene | 4.212 | 3.765 | 10.6 | 97 | 0.00 | 15.47 |
| 117 | | 1,3-dichlorobenzene | 1.824 | 1.671 | 8.4 | 98 | 0.00 | 15.65 |
| 118 | | p-isopropyltoluene | 3.408 | 3.167 | 7.1 | 98 | 0.00 | 15.59 |
| 119 | | 1,4-dichlorobenzene | 1.787 | 1.640 | 8.2 | 99 | 0.00 | 15.73 |
| 120 | | 1,2-dichlorobenzene | 1.713 | 1.614 | 5.8 | 99 | 0.00 | 16.12 |
| 121 | | n-butylbenzene | 1.853 | 1.689 | 8.9 | 95 | 0.00 | 16.00 |
| 122 | | p-Diethylbenzene | | ----------NA---------- | | | | |
| 123 | | 1,2-dibromo-3-chloropropa | 0.159 | 0.151 | 5.0 | 97 | 0.00 | 16.87 |
| 124 | | 1,3,5-Trichlorobenzene | 1.438 | 1.442 | -0.3 | 102 | 0.00 | 17.08 |
| 125 | | 1,2,4-trichlorobenzene | 1.131 | 1.143 | -1.1 | 96 | 0.00 | 17.70 |
| 126 | | 1,2,4,5-tetramethylbenzen | | ----------NA---------- | | | | |
| 127 | | hexachlorobutadiene | 0.872 | 0.818 | 6.2 | 98 | 0.00 | 17.83 |
| 128 | | naphthalene | 1.974 | 1.975 | -0.1 | 97 | 0.00 | 17.97 |
| 129 | | 1,2,3-trichlorobenzene | 0.998 | 0.997 | 0.1 | 96 | 0.00 | 18.22 |
| 130 | | hexachloroethane | 0.607 | 0.586 | 3.5 | 101 | 0.00 | 16.39 |
| 131 | | Benzyl chloride | 1.627 | 1.451 | 10.8 | 94 | 0.00 | 15.84 |
| 132 | | 2-ethylhexyl acrylate | | ----------NA---------- | | | | |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Y166746.D MYS7258.M Fri Oct 07 11:26:29 2016 RPT1

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** VY7259-CC7258
**Lab FileID:** Y166754.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\Y\...7260\vy7259\Y166754.D Vial: 2
Acq On : 6 Oct 2016 11:20 am Operator: prashans
Sample : CC7258-20 Inst : MSY
Misc : MS7637,VY7259,5.0,,,,1 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MYS7258.M (RTE Integrator)
Title : Method SW846 8260C, ZB624 60m x 0.25mm x 1.4um
Last Update : Mon Sep 13 11:48:20 2010
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | Tert Butyl Alcohol-d9 | 1.000 | 1.000 | 0.0 | 99 | 0.00 | 7.12 |
| 2 | | 1,4-dioxane | 0.118 | 0.112 | 5.1 | 90 | 0.01 | 10.97 |
| 3 | | tertiary butyl alcohol | 1.458 | 1.369 | 6.1 | 92 | 0.02 | 7.24 |
| 4 | I | pentafluorobenzene | 1.000 | 1.000 | 0.0 | 94 | 0.00 | 9.34 |
| 5 | | propene | | ----------NA---------- | | | | |
| 6 | | chlorodifluoromethane | 0.809 | 1.013 | -25.2# | 115 | 0.00 | 3.90 |
| 7 | | dichlorodifluoromethane | 0.683 | 0.820 | -20.1# | 110 | 0.01 | 3.90 |
| 8 | | chloromethane | 0.957 | 1.048 | -9.5 | 110 | -0.02 | 4.17 |
| 9 | | vinyl chloride | 0.858 | 0.998 | -16.3 | 111 | 0.00 | 4.44 |
| 10 | | 1,3-butadiene | | ----------NA---------- | | | | |
| 11 | | bromomethane | 0.473 | 0.535 | -13.1 | 108 | 0.00 | 5.05 |
| 12 | | chloroethane | 0.412 | 0.489 | -18.7 | 109 | 0.01 | 5.22 |
| 13 | | Vinyl Bromide | 0.675 | 0.788 | -16.7 | 110 | 0.00 | 5.56 |
| 14 | | trichlorofluoromethane | 0.768 | 0.905 | -17.8 | 112 | 0.00 | 5.68 |
| 15 | | ethyl ether | 0.325 | 0.337 | -3.7 | 98 | 0.00 | 6.06 |
| 16 | | 2-chloropropane | | ----------NA---------- | | | | |
| 17 | | acrolein | 0.099 | 0.104 | -5.1 | 97 | 0.00 | 6.28 |
| 18 | | 1,1-dichloroethene | 0.940 | 1.100 | -17.0 | 108 | 0.00 | 6.47 |
| 19 | | acetone | 0.213 | 0.192 | 9.9 | 76 | 0.00 | 6.49 |
| 20 | | allyl chloride | 0.379 | 0.408 | -7.7 | 99 | 0.00 | 6.98 |
| 21 | | acetonitrile | 0.051 | 0.056 | -9.8 | 103 | 0.00 | 6.91 |
| 22 | | iodomethane | 0.970 | 1.100 | -13.4 | 104 | 0.00 | 6.74 |
| 23 | | carbon disulfide | 2.063 | 2.375 | -15.1 | 108 | 0.00 | 6.88 |
| 24 | | 1-chloropropane | | ----------NA---------- | | | | |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 25 | | methylene chloride | 20.000 | 21.755 | -8.8 | 101 | 0.00 | 7.16 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 26 | | methyl acetate | 0.393 | 0.410 | -4.3 | 97 | 0.00 | 6.96 |
| 27 | | methyl tert butyl ether | 1.730 | 1.813 | -4.8 | 100 | 0.00 | 7.50 |
| 28 | | trans-1,2-dichloroethene | 1.002 | 1.105 | -10.3 | 105 | 0.00 | 7.54 |
| 29 | | di-isopropyl ether | 2.373 | 2.585 | -8.9 | 101 | 0.00 | 8.09 |
| 30 | | ethyl tert-butyl ether | 2.069 | 2.211 | -6.9 | 99 | 0.00 | 8.56 |
| 31 | | 2-butanone | 0.060 | 0.059 | 1.7 | 88 | 0.00 | 8.77 |
| 32 | | 1,1-dichloroethane | 1.220 | 1.301 | -6.6 | 102 | 0.00 | 8.09 |
| 33 | | chloroprene | 0.925 | 1.065 | -15.1 | 106 | 0.00 | 8.21 |
| 34 | | acrylonitrile | 0.181 | 0.192 | -6.1 | 96 | 0.00 | 7.46 |
| 35 | | vinyl acetate | 0.080 | 0.083 | -3.8 | 91 | 0.00 | 8.07 |
| 36 | | ethyl acetate | 0.086 | 0.080 | 7.0 | 88 | 0.00 | 8.80 |
| 37 | | 2,2-dichloropropane | 0.942 | 1.055 | -12.0 | 108 | 0.00 | 8.83 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** VY7259-CC7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166754.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 38 | | cis-1,2-dichloroethene | 0.641 | 0.702 | -9.5 | 100 | 0.00 | 8.82 |
| 39 | | propionitrile | 0.068 | 0.070 | -2.9 | 94 | 0.00 | 8.85 |
| 40 | | bromochloromethane | 0.369 | 0.394 | -6.8 | 100 | 0.00 | 9.12 |
| 41 | | tetrahydrofuran | 0.068 | 0.070 | -2.9 | 94 | 0.00 | 9.17 |
| 42 | | chloroform | 1.075 | 1.152 | -7.2 | 102 | 0.00 | 9.18 |
| 43 | | tert-Butyl Formate | 0.567 | 0.593 | -4.6 | 99 | 0.00 | 9.22 |
| 44 | | isobutyl alcohol | | ----------NA---------- | | | | |
| 45 | S | dibromofluoromethane (s) | 0.525 | 0.533 | -1.5 | 96 | 0.00 | 9.37 |
| 46 | S | 1,2-dichloroethane-d4 (s) | 0.553 | 0.556 | -0.5 | 96 | 0.00 | 9.79 |
| 47 | | freon 113 | 0.385 | 0.451 | -17.1 | 109 | 0.00 | 6.46 |
| 48 | | methacrylonitrile | 0.191 | 0.185 | 3.1 | 88 | 0.00 | 9.04 |
| 49 | | 1,1,1-trichloroethane | 0.840 | 0.957 | -13.9 | 107 | 0.00 | 9.45 |
| 50 | | Cyclohexane | 0.808 | 0.961 | -18.9 | 110 | 0.00 | 9.54 |
| 51 | | 2,2,4-trimethylpentane | 2.498 | 2.764 | -10.6 | 102 | 0.00 | 9.91 |
| 52 | | tert-amyl methyl ether | 1.830 | 1.906 | -4.2 | 98 | 0.00 | 9.93 |
| 53 | I | 1,4-difluorobenzene | 1.000 | 1.000 | 0.0 | 95 | 0.00 | 10.25 |
| 54 | | epichlorohydrin | 0.028 | 0.029 | -3.6 | 93 | 0.00 | 11.48 |
| 55 | | n-butyl alcohol | 0.009 | 0.010 | -11.1 | 90 | 0.00 | 10.36 |
| 56 | | carbon tetrachloride | 0.470 | 0.542 | -15.3 | 107 | 0.00 | 9.66 |
| 57 | | 1,1-dichloropropene | 0.477 | 0.545 | -14.3 | 105 | 0.00 | 9.62 |
| 58 | | hexane | 0.549 | 0.583 | -6.2 | 100 | 0.00 | 7.86 |
| 59 | | Tert Amyl Alcohol | | ----------NA---------- | | | | |
| 60 | | benzene | 1.548 | 1.610 | -4.0 | 102 | 0.00 | 9.88 |
| 61 | | heptane | 0.300 | 0.301 | -0.3 | 94 | 0.00 | 10.08 |
| 62 | | isopropyl acetate | 0.053 | 0.053 | 0.0 | 89 | 0.00 | 9.80 |
| 63 | | 1,2-dichloroethane | 0.483 | 0.505 | -4.6 | 97 | 0.00 | 9.87 |
| 64 | | trichloroethene | 0.351 | 0.382 | -8.8 | 101 | 0.00 | 10.60 |
| 65 | | ethyl acrylate | 0.323 | 0.331 | -2.5 | 94 | 0.00 | 10.59 |
| 66 | | 2-nitropropane | 0.102 | 0.103 | -1.0 | 100 | 0.00 | 11.33 |
| 67 | | 2-chloroethyl vinyl ether | 0.076 | 0.078 | -2.6 | 94 | 0.00 | 11.38 |
| 68 | | methyl methacrylate | 0.058 | 0.061 | -5.2 | 92 | 0.00 | 10.86 |
| 69 | | 1,2-dichloropropane | 0.401 | 0.428 | -6.7 | 97 | 0.00 | 10.85 |
| 70 | | methylcyclohexane | 0.684 | 0.801 | -17.1 | 107 | 0.00 | 10.84 |
| 71 | | Tert-amyl ethyl ether | | ----------NA---------- | | | | |
| 72 | | dibromomethane | 0.205 | 0.213 | -3.9 | 95 | 0.00 | 11.00 |
| 73 | | bromodichloromethane | 0.495 | 0.513 | -3.6 | 96 | 0.00 | 11.13 |
| 74 | | cis-1,3-dichloropropene | 0.578 | 0.590 | -2.1 | 95 | 0.00 | 11.59 |
| 75 | S | toluene-d8 (s) | 1.096 | 1.094 | 0.2 | 93 | 0.00 | 11.90 |
| 76 | | 4-methyl-2-pentanone | 0.111 | 0.115 | -3.6 | 94 | 0.00 | 11.69 |
| 77 | | toluene | 1.299 | 1.377 | -6.0 | 100 | 0.00 | 11.97 |
| 78 | | 3-methyl-1-butanol | 0.007 | 0.008 | -14.3 | 92 | 0.00 | 11.70 |
| 79 | | trans-1,3-dichloropropene | 0.483 | 0.494 | -2.3 | 95 | 0.00 | 12.15 |
| 80 | | ethyl methacrylate | 0.327 | 0.342 | -4.6 | 93 | 0.00 | 12.16 |
| 81 | | 1,1,2-trichloroethane | 0.212 | 0.221 | -4.2 | 94 | 0.00 | 12.37 |
| 82 | | 2-hexanone | 0.091 | 0.088 | 3.3 | 89 | 0.00 | 12.55 |
| 83 | I | chlorobenzene-d5 | 1.000 | 1.000 | 0.0 | 94 | 0.00 | 13.40 |
| 84 | | tetrachloroethene | 0.414 | 0.451 | -8.9 | 99 | 0.00 | 12.57 |
| 85 | | 1,3-dichloropropane | 0.603 | 0.614 | -1.8 | 94 | 0.00 | 12.55 |
| 86 | | butyl acetate | 0.248 | 0.246 | 0.8 | 90 | 0.00 | 12.63 |
| 87 | | dibromochloromethane | 0.426 | 0.426 | 0.0 | 94 | 0.00 | 12.81 |
| 88 | | 1,2-dibromoethane | 0.344 | 0.350 | -1.7 | 93 | 0.00 | 12.96 |
| 89 | | 3,3-Dimethyl-1-Butanol | 0.041 | 0.041 | 0.0 | 90 | 0.00 | 12.71 |
| 90 | | n-butyl ether | 1.923 | 2.133 | -10.9 | 104 | 0.00 | 13.37 |
| 91 | | chlorobenzene | 1.058 | 1.122 | -6.0 | 99 | 0.00 | 13.43 |
| 92 | | 1,1,1,2-tetrachloroethane | 0.431 | 0.457 | -6.0 | 100 | 0.00 | 13.49 |
| 93 | | ethylbenzene | 1.883 | 2.016 | -7.1 | 100 | 0.00 | 13.49 |
| 94 | | m,p-xylene | 0.719 | 0.742 | -3.2 | 100 | 0.00 | 13.60 |
| 95 | | o-xylene | 1.574 | 1.690 | -7.4 | 100 | 0.00 | 14.01 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** VY7259-CC7258
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Y166754.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 96 | | styrene | 1.089 | 1.167 | -7.2 | 99 | 0.00 | 14.02 |
| 97 | | bromoform | 0.251 | 0.247 | 1.6 | 93 | 0.00 | 14.27 |
| 98 | | butyl acrylate | | ----------NA---------- | | | | |
| 99 | I | 1,4-dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 15.71 |
| 100 | | isopropylbenzene | 3.830 | 4.162 | -8.7 | 103 | 0.00 | 14.36 |
| 101 | S | 4-bromofluorobenzene (s) | 1.092 | 1.065 | 2.5 | 95 | 0.00 | 14.55 |
| 102 | | cis-1,4-dichloro-2-butene | | ----------NA---------- | | | | |
| 103 | | bromobenzene | 0.964 | 0.983 | -2.0 | 99 | 0.00 | 14.74 |
| 104 | | cyclohexanone | 0.156 | 0.124 | 20.5# | 68 | 0.00 | 14.49 |
| 105 | | 1,1,2,2-tetrachloroethane | 0.920 | 0.921 | -0.1 | 93 | 0.00 | 14.64 |
| 106 | | trans-1,4-dichloro-2-bute | 0.244 | 0.255 | -4.5 | 97 | 0.00 | 14.68 |
| 107 | | 1,2,3-trichloropropane | 0.203 | 0.208 | -2.5 | 97 | 0.00 | 14.71 |
| 108 | | n-propylbenzene | 4.511 | 4.896 | -8.5 | 103 | 0.00 | 14.76 |
| 109 | | 4-Ethyltoluene | | ----------NA---------- | | | | |
| 110 | | 2-chlorotoluene | 0.927 | 0.996 | -7.4 | 102 | 0.00 | 14.90 |
| 111 | | 4-chlorotoluene | 2.955 | 3.018 | -2.1 | 100 | 0.00 | 15.00 |
| 112 | | 1,3,5-trimethylbenzene | 3.320 | 3.597 | -8.3 | 101 | 0.00 | 14.92 |
| 113 | | tert-butylbenzene | 0.552 | 0.599 | -8.5 | 101 | 0.00 | 15.26 |
| 114 | | pentachloroethane | 0.632 | 0.647 | -2.4 | 100 | 0.00 | 15.33 |
| 115 | | 1,2,4-trimethylbenzene | 3.380 | 3.636 | -7.6 | 103 | 0.00 | 15.30 |
| 116 | | sec-butylbenzene | 4.212 | 4.568 | -8.5 | 105 | 0.00 | 15.47 |
| 117 | | 1,3-dichlorobenzene | 1.824 | 1.901 | -4.2 | 99 | 0.00 | 15.65 |
| 118 | | p-isopropyltoluene | 3.408 | 3.747 | -9.9 | 104 | 0.00 | 15.59 |
| 119 | | 1,4-dichlorobenzene | 1.787 | 1.827 | -2.2 | 97 | 0.00 | 15.73 |
| 120 | | 1,2-dichlorobenzene | 1.713 | 1.774 | -3.6 | 98 | 0.00 | 16.12 |
| 121 | | n-butylbenzene | 1.853 | 2.029 | -9.5 | 103 | 0.00 | 16.00 |
| 122 | | p-Diethylbenzene | | ----------NA---------- | | | | |
| 123 | | 1,2-dibromo-3-chloropropa | 0.159 | 0.152 | 4.4 | 92 | 0.00 | 16.88 |
| 124 | | 1,3,5-Trichlorobenzene | 1.438 | 1.575 | -9.5 | 104 | 0.00 | 17.08 |
| 125 | | 1,2,4-trichlorobenzene | 1.131 | 1.243 | -9.9 | 102 | 0.00 | 17.71 |
| 126 | | 1,2,4,5-tetramethylbenzen | | ----------NA---------- | | | | |
| 127 | | hexachlorobutadiene | 0.872 | 0.957 | -9.7 | 102 | 0.00 | 17.83 |
| 128 | | naphthalene | 1.974 | 1.985 | -0.6 | 98 | 0.00 | 17.98 |
| 129 | | 1,2,3-trichlorobenzene | 0.998 | 1.065 | -6.7 | 99 | 0.00 | 18.22 |
| 130 | | hexachloroethane | 0.607 | 0.648 | -6.8 | 102 | 0.00 | 16.39 |
| 131 | | Benzyl chloride | 1.627 | 1.592 | 2.2 | 94 | 0.00 | 15.84 |
| 132 | | 2-ethylhexyl acrylate | | ----------NA---------- | | | | |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Y166745.D MYS7258.M Fri Oct 07 12:37:30 2016 ACC-VOA-DP

SGS ACCUTEST New Jersey

Section 7

## GC/MS Semi-volatiles

### QC Data Summaries

Includes the following where applicable:

- Method Blank Summaries
- Blank Spike Summaries
- Matrix Spike and Duplicate Summaries
- Instrument Performance Checks (DFTPP)
- Internal Standard Area Summaries
- Surrogate Recovery Summaries
- Initial and Continuing Calibration Summaries

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | P107983.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 95-57-8 | 2-Chlorophenol | ND | 67 | 16 | ug/kg | |
| 59-50-7 | 4-Chloro-3-methyl phenol | ND | 170 | 20 | ug/kg | |
| 120-83-2 | 2,4-Dichlorophenol | ND | 170 | 28 | ug/kg | |
| 105-67-9 | 2,4-Dimethylphenol | ND | 170 | 59 | ug/kg | |
| 51-28-5 | 2,4-Dinitrophenol | ND | 170 | 130 | ug/kg | |
| 534-52-1 | 4,6-Dinitro-o-cresol | ND | 170 | 36 | ug/kg | |
| 95-48-7 | 2-Methylphenol | ND | 67 | 21 | ug/kg | |
| | 3&4-Methylphenol | ND | 67 | 27 | ug/kg | |
| 88-75-5 | 2-Nitrophenol | ND | 170 | 22 | ug/kg | |
| 100-02-7 | 4-Nitrophenol | ND | 330 | 89 | ug/kg | |
| 87-86-5 | Pentachlorophenol | ND | 130 | 31 | ug/kg | |
| 108-95-2 | Phenol | ND | 67 | 17 | ug/kg | |
| 58-90-2 | 2,3,4,6-Tetrachlorophenol | ND | 170 | 22 | ug/kg | |
| 95-95-4 | 2,4,5-Trichlorophenol | ND | 170 | 25 | ug/kg | |
| 88-06-2 | 2,4,6-Trichlorophenol | ND | 170 | 20 | ug/kg | |
| 83-32-9 | Acenaphthene | ND | 33 | 11 | ug/kg | |
| 208-96-8 | Acenaphthylene | ND | 33 | 17 | ug/kg | |
| 98-86-2 | Acetophenone | ND | 170 | 7.2 | ug/kg | |
| 120-12-7 | Anthracene | ND | 33 | 20 | ug/kg | |
| 1912-24-9 | Atrazine | ND | 67 | 14 | ug/kg | |
| 56-55-3 | Benzo(a)anthracene | ND | 33 | 9.4 | ug/kg | |
| 50-32-8 | Benzo(a)pyrene | ND | 33 | 15 | ug/kg | |
| 205-99-2 | Benzo(b)fluoranthene | ND | 33 | 15 | ug/kg | |
| 191-24-2 | Benzo(g,h,i)perylene | ND | 33 | 17 | ug/kg | |
| 207-08-9 | Benzo(k)fluoranthene | ND | 33 | 16 | ug/kg | |
| 101-55-3 | 4-Bromophenyl phenyl ether | ND | 67 | 13 | ug/kg | |
| 85-68-7 | Butyl benzyl phthalate | ND | 67 | 8.1 | ug/kg | |
| 92-52-4 | 1,1'-Biphenyl | ND | 67 | 4.6 | ug/kg | |
| 100-52-7 | Benzaldehyde | ND | 170 | 8.3 | ug/kg | |
| 91-58-7 | 2-Chloronaphthalene | ND | 67 | 7.9 | ug/kg | |
| 106-47-8 | 4-Chloroaniline | ND | 170 | 12 | ug/kg | |
| 86-74-8 | Carbazole | ND | 67 | 4.8 | ug/kg | |
| 105-60-2 | Caprolactam | ND | 67 | 13 | ug/kg | |
| 218-01-9 | Chrysene | ND | 33 | 10 | ug/kg | |
| 111-91-1 | bis(2-Chloroethoxy)methane | ND | 67 | 7.1 | ug/kg | |
| 111-44-4 | bis(2-Chloroethyl)ether | ND | 67 | 14 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | P107983.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 108-60-1 | bis(2-Chloroisopropyl)ether | ND | 67 | 12 | ug/kg | |
| 7005-72-3 | 4-Chlorophenyl phenyl ether | ND | 67 | 11 | ug/kg | |
| 121-14-2 | 2,4-Dinitrotoluene | ND | 33 | 10 | ug/kg | |
| 606-20-2 | 2,6-Dinitrotoluene | ND | 33 | 17 | ug/kg | |
| 91-94-1 | 3,3'-Dichlorobenzidine | ND | 67 | 28 | ug/kg | |
| 123-91-1 | 1,4-Dioxane | ND | 33 | 22 | ug/kg | |
| 53-70-3 | Dibenzo(a,h)anthracene | ND | 33 | 15 | ug/kg | |
| 132-64-9 | Dibenzofuran | ND | 67 | 14 | ug/kg | |
| 84-74-2 | Di-n-butyl phthalate | ND | 67 | 5.4 | ug/kg | |
| 117-84-0 | Di-n-octyl phthalate | ND | 67 | 8.3 | ug/kg | |
| 84-66-2 | Diethyl phthalate | ND | 67 | 7.1 | ug/kg | |
| 131-11-3 | Dimethyl phthalate | ND | 67 | 5.9 | ug/kg | |
| 117-81-7 | bis(2-Ethylhexyl)phthalate | ND | 67 | 7.8 | ug/kg | |
| 206-44-0 | Fluoranthene | ND | 33 | 15 | ug/kg | |
| 86-73-7 | Fluorene | ND | 33 | 15 | ug/kg | |
| 118-74-1 | Hexachlorobenzene | ND | 67 | 8.4 | ug/kg | |
| 87-68-3 | Hexachlorobutadiene | ND | 33 | 13 | ug/kg | |
| 77-47-4 | Hexachlorocyclopentadiene | ND | 330 | 13 | ug/kg | |
| 67-72-1 | Hexachloroethane | ND | 170 | 16 | ug/kg | |
| 193-39-5 | Indeno(1,2,3-cd)pyrene | ND | 33 | 16 | ug/kg | |
| 78-59-1 | Isophorone | ND | 67 | 7.1 | ug/kg | |
| 91-57-6 | 2-Methylnaphthalene | ND | 67 | 7.5 | ug/kg | |
| 88-74-4 | 2-Nitroaniline | ND | 170 | 7.9 | ug/kg | |
| 99-09-2 | 3-Nitroaniline | ND | 170 | 8.3 | ug/kg | |
| 100-01-6 | 4-Nitroaniline | ND | 170 | 8.6 | ug/kg | |
| 91-20-3 | Naphthalene | ND | 33 | 9.4 | ug/kg | |
| 98-95-3 | Nitrobenzene | ND | 67 | 13 | ug/kg | |
| 621-64-7 | N-Nitroso-di-n-propylamine | ND | 67 | 9.6 | ug/kg | |
| 86-30-6 | N-Nitrosodiphenylamine | ND | 170 | 12 | ug/kg | |
| 85-01-8 | Phenanthrene | ND | 33 | 11 | ug/kg | |
| 129-00-0 | Pyrene | ND | 33 | 11 | ug/kg | |
| 95-94-3 | 1,2,4,5-Tetrachlorobenzene | ND | 170 | 8.5 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | P107983.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 367-12-4 | 2-Fluorophenol | 74% | 30-106% |
| 4165-62-2 | Phenol-d5 | 76% | 30-106% |
| 118-79-6 | 2,4,6-Tribromophenol | 83% | 24-140% |
| 4165-60-0 | Nitrobenzene-d5 | 87% | 26-122% |
| 321-60-8 | 2-Fluorobiphenyl | 88% | 36-112% |
| 1718-51-0 | Terphenyl-d14 | 90% | 36-132% |

| CAS No. | Tentatively Identified Compounds | R.T. | Est. Conc. | Units | Q |
|---|---|---|---|---|---|
| | system artifact | 2.83 | 400 | ug/kg | J |
| | system artifact | 3.15 | 290 | ug/kg | J |
| | system artifact/aldol-condensation | 3.22 | 410 | ug/kg | J |
| | Total TIC, Semi-Volatile | | 0 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | Z114917.D | 1 | 10/07/16 | AD | 10/06/16 | OP97539 | EZ5729 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 95-57-8 | 2-Chlorophenol | ND | 67 | 16 | ug/kg | |
| 59-50-7 | 4-Chloro-3-methyl phenol | ND | 170 | 20 | ug/kg | |
| 120-83-2 | 2,4-Dichlorophenol | ND | 170 | 28 | ug/kg | |
| 105-67-9 | 2,4-Dimethylphenol | ND | 170 | 59 | ug/kg | |
| 51-28-5 | 2,4-Dinitrophenol | ND | 170 | 130 | ug/kg | |
| 534-52-1 | 4,6-Dinitro-o-cresol | ND | 170 | 36 | ug/kg | |
| 95-48-7 | 2-Methylphenol | ND | 67 | 21 | ug/kg | |
| | 3&4-Methylphenol | ND | 67 | 27 | ug/kg | |
| 88-75-5 | 2-Nitrophenol | ND | 170 | 22 | ug/kg | |
| 100-02-7 | 4-Nitrophenol | ND | 330 | 89 | ug/kg | |
| 87-86-5 | Pentachlorophenol | ND | 130 | 31 | ug/kg | |
| 108-95-2 | Phenol | ND | 67 | 17 | ug/kg | |
| 58-90-2 | 2,3,4,6-Tetrachlorophenol | ND | 170 | 22 | ug/kg | |
| 95-95-4 | 2,4,5-Trichlorophenol | ND | 170 | 25 | ug/kg | |
| 88-06-2 | 2,4,6-Trichlorophenol | ND | 170 | 20 | ug/kg | |
| 83-32-9 | Acenaphthene | ND | 33 | 11 | ug/kg | |
| 208-96-8 | Acenaphthylene | ND | 33 | 17 | ug/kg | |
| 98-86-2 | Acetophenone | ND | 170 | 7.2 | ug/kg | |
| 120-12-7 | Anthracene | ND | 33 | 20 | ug/kg | |
| 1912-24-9 | Atrazine | ND | 67 | 14 | ug/kg | |
| 56-55-3 | Benzo(a)anthracene | ND | 33 | 9.4 | ug/kg | |
| 50-32-8 | Benzo(a)pyrene | ND | 33 | 15 | ug/kg | |
| 205-99-2 | Benzo(b)fluoranthene | ND | 33 | 15 | ug/kg | |
| 191-24-2 | Benzo(g,h,i)perylene | ND | 33 | 17 | ug/kg | |
| 207-08-9 | Benzo(k)fluoranthene | ND | 33 | 16 | ug/kg | |
| 101-55-3 | 4-Bromophenyl phenyl ether | ND | 67 | 13 | ug/kg | |
| 85-68-7 | Butyl benzyl phthalate | ND | 67 | 8.1 | ug/kg | |
| 92-52-4 | 1,1'-Biphenyl | ND | 67 | 4.6 | ug/kg | |
| 100-52-7 | Benzaldehyde | ND | 170 | 8.3 | ug/kg | |
| 91-58-7 | 2-Chloronaphthalene | ND | 67 | 7.9 | ug/kg | |
| 106-47-8 | 4-Chloroaniline | ND | 170 | 12 | ug/kg | |
| 86-74-8 | Carbazole | ND | 67 | 4.8 | ug/kg | |
| 105-60-2 | Caprolactam | ND | 67 | 13 | ug/kg | |
| 218-01-9 | Chrysene | ND | 33 | 10 | ug/kg | |
| 111-91-1 | bis(2-Chloroethoxy)methane | ND | 67 | 7.1 | ug/kg | |
| 111-44-4 | bis(2-Chloroethyl)ether | ND | 67 | 14 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | Z114917.D | 1 | 10/07/16 | AD | 10/06/16 | OP97539 | EZ5729 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 108-60-1 | bis(2-Chloroisopropyl)ether | ND | 67 | 12 | ug/kg | |
| 7005-72-3 | 4-Chlorophenyl phenyl ether | ND | 67 | 11 | ug/kg | |
| 121-14-2 | 2,4-Dinitrotoluene | ND | 33 | 10 | ug/kg | |
| 606-20-2 | 2,6-Dinitrotoluene | ND | 33 | 17 | ug/kg | |
| 91-94-1 | 3,3'-Dichlorobenzidine | ND | 67 | 28 | ug/kg | |
| 123-91-1 | 1,4-Dioxane | ND | 33 | 22 | ug/kg | |
| 53-70-3 | Dibenzo(a,h)anthracene | ND | 33 | 15 | ug/kg | |
| 132-64-9 | Dibenzofuran | ND | 67 | 14 | ug/kg | |
| 84-74-2 | Di-n-butyl phthalate | ND | 67 | 5.4 | ug/kg | |
| 117-84-0 | Di-n-octyl phthalate | ND | 67 | 8.3 | ug/kg | |
| 84-66-2 | Diethyl phthalate | ND | 67 | 7.1 | ug/kg | |
| 131-11-3 | Dimethyl phthalate | ND | 67 | 5.9 | ug/kg | |
| 117-81-7 | bis(2-Ethylhexyl)phthalate | ND | 67 | 7.8 | ug/kg | |
| 206-44-0 | Fluoranthene | ND | 33 | 15 | ug/kg | |
| 86-73-7 | Fluorene | ND | 33 | 15 | ug/kg | |
| 118-74-1 | Hexachlorobenzene | ND | 67 | 8.4 | ug/kg | |
| 87-68-3 | Hexachlorobutadiene | ND | 33 | 13 | ug/kg | |
| 77-47-4 | Hexachlorocyclopentadiene | ND | 330 | 13 | ug/kg | |
| 67-72-1 | Hexachloroethane | ND | 170 | 16 | ug/kg | |
| 193-39-5 | Indeno(1,2,3-cd)pyrene | ND | 33 | 16 | ug/kg | |
| 78-59-1 | Isophorone | ND | 67 | 7.1 | ug/kg | |
| 91-57-6 | 2-Methylnaphthalene | ND | 67 | 7.5 | ug/kg | |
| 88-74-4 | 2-Nitroaniline | ND | 170 | 7.9 | ug/kg | |
| 99-09-2 | 3-Nitroaniline | ND | 170 | 8.3 | ug/kg | |
| 100-01-6 | 4-Nitroaniline | ND | 170 | 8.6 | ug/kg | |
| 91-20-3 | Naphthalene | ND | 33 | 9.4 | ug/kg | |
| 98-95-3 | Nitrobenzene | ND | 67 | 13 | ug/kg | |
| 621-64-7 | N-Nitroso-di-n-propylamine | ND | 67 | 9.6 | ug/kg | |
| 86-30-6 | N-Nitrosodiphenylamine | ND | 170 | 12 | ug/kg | |
| 85-01-8 | Phenanthrene | ND | 33 | 11 | ug/kg | |
| 129-00-0 | Pyrene | ND | 33 | 11 | ug/kg | |
| 95-94-3 | 1,2,4,5-Tetrachlorobenzene | ND | 170 | 8.5 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | Z114917.D | 1 | 10/07/16 | AD | 10/06/16 | OP97539 | EZ5729 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 367-12-4 | 2-Fluorophenol | 70% | 30-106% |
| 4165-62-2 | Phenol-d5 | 73% | 30-106% |
| 118-79-6 | 2,4,6-Tribromophenol | 84% | 24-140% |
| 4165-60-0 | Nitrobenzene-d5 | 83% | 26-122% |
| 321-60-8 | 2-Fluorobiphenyl | 93% | 36-112% |
| 1718-51-0 | Terphenyl-d14 | 88% | 36-132% |

| CAS No. | Tentatively Identified Compounds | R.T. | Est. Conc. | Units | Q |
|---|---|---|---|---|---|
| | system artifact | 2.72 | 360 | ug/kg | J |
| | system artifact | 3.05 | 320 | ug/kg | J |
| | system artifact/aldol-condensation | 3.12 | 500 | ug/kg | J |
| | Total TIC, Semi-Volatile | | 0 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | M128185.D | 1 | 10/07/16 | CS | 10/06/16 | OP97539 | EM5462 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 95-57-8 | 2-Chlorophenol | ND | 67 | 16 | ug/kg | |
| 59-50-7 | 4-Chloro-3-methyl phenol | ND | 170 | 20 | ug/kg | |
| 120-83-2 | 2,4-Dichlorophenol | ND | 170 | 28 | ug/kg | |
| 105-67-9 | 2,4-Dimethylphenol | ND | 170 | 59 | ug/kg | |
| 51-28-5 | 2,4-Dinitrophenol | ND | 170 | 130 | ug/kg | |
| 534-52-1 | 4,6-Dinitro-o-cresol | ND | 170 | 36 | ug/kg | |
| 95-48-7 | 2-Methylphenol | ND | 67 | 21 | ug/kg | |
| | 3&4-Methylphenol | ND | 67 | 27 | ug/kg | |
| 88-75-5 | 2-Nitrophenol | ND | 170 | 22 | ug/kg | |
| 100-02-7 | 4-Nitrophenol | ND | 330 | 89 | ug/kg | |
| 87-86-5 | Pentachlorophenol | ND | 130 | 31 | ug/kg | |
| 108-95-2 | Phenol | ND | 67 | 17 | ug/kg | |
| 58-90-2 | 2,3,4,6-Tetrachlorophenol | ND | 170 | 22 | ug/kg | |
| 95-95-4 | 2,4,5-Trichlorophenol | ND | 170 | 25 | ug/kg | |
| 88-06-2 | 2,4,6-Trichlorophenol | ND | 170 | 20 | ug/kg | |
| 83-32-9 | Acenaphthene | ND | 33 | 11 | ug/kg | |
| 208-96-8 | Acenaphthylene | ND | 33 | 17 | ug/kg | |
| 98-86-2 | Acetophenone | ND | 170 | 7.2 | ug/kg | |
| 120-12-7 | Anthracene | ND | 33 | 20 | ug/kg | |
| 1912-24-9 | Atrazine | ND | 67 | 14 | ug/kg | |
| 56-55-3 | Benzo(a)anthracene | ND | 33 | 9.4 | ug/kg | |
| 50-32-8 | Benzo(a)pyrene | ND | 33 | 15 | ug/kg | |
| 205-99-2 | Benzo(b)fluoranthene | ND | 33 | 15 | ug/kg | |
| 191-24-2 | Benzo(g,h,i)perylene | ND | 33 | 17 | ug/kg | |
| 207-08-9 | Benzo(k)fluoranthene | ND | 33 | 16 | ug/kg | |
| 101-55-3 | 4-Bromophenyl phenyl ether | ND | 67 | 13 | ug/kg | |
| 85-68-7 | Butyl benzyl phthalate | ND | 67 | 8.1 | ug/kg | |
| 92-52-4 | 1,1'-Biphenyl | ND | 67 | 4.6 | ug/kg | |
| 100-52-7 | Benzaldehyde | ND | 170 | 8.3 | ug/kg | |
| 91-58-7 | 2-Chloronaphthalene | ND | 67 | 7.9 | ug/kg | |
| 106-47-8 | 4-Chloroaniline | ND | 170 | 12 | ug/kg | |
| 86-74-8 | Carbazole | ND | 67 | 4.8 | ug/kg | |
| 105-60-2 | Caprolactam | ND | 67 | 13 | ug/kg | |
| 218-01-9 | Chrysene | ND | 33 | 10 | ug/kg | |
| 111-91-1 | bis(2-Chloroethoxy)methane | ND | 67 | 7.1 | ug/kg | |
| 111-44-4 | bis(2-Chloroethyl)ether | ND | 67 | 14 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | M128185.D | 1 | 10/07/16 | CS | 10/06/16 | OP97539 | EM5462 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 108-60-1 | bis(2-Chloroisopropyl)ether | ND | 67 | 12 | ug/kg | |
| 7005-72-3 | 4-Chlorophenyl phenyl ether | ND | 67 | 11 | ug/kg | |
| 121-14-2 | 2,4-Dinitrotoluene | ND | 33 | 10 | ug/kg | |
| 606-20-2 | 2,6-Dinitrotoluene | ND | 33 | 17 | ug/kg | |
| 91-94-1 | 3,3'-Dichlorobenzidine | ND | 67 | 28 | ug/kg | |
| 123-91-1 | 1,4-Dioxane | ND | 33 | 22 | ug/kg | |
| 53-70-3 | Dibenzo(a,h)anthracene | ND | 33 | 15 | ug/kg | |
| 132-64-9 | Dibenzofuran | ND | 67 | 14 | ug/kg | |
| 84-74-2 | Di-n-butyl phthalate | ND | 67 | 5.4 | ug/kg | |
| 117-84-0 | Di-n-octyl phthalate | ND | 67 | 8.3 | ug/kg | |
| 84-66-2 | Diethyl phthalate | ND | 67 | 7.1 | ug/kg | |
| 131-11-3 | Dimethyl phthalate | ND | 67 | 5.9 | ug/kg | |
| 117-81-7 | bis(2-Ethylhexyl)phthalate | ND | 67 | 7.8 | ug/kg | |
| 206-44-0 | Fluoranthene | ND | 33 | 15 | ug/kg | |
| 86-73-7 | Fluorene | ND | 33 | 15 | ug/kg | |
| 118-74-1 | Hexachlorobenzene | ND | 67 | 8.4 | ug/kg | |
| 87-68-3 | Hexachlorobutadiene | ND | 33 | 13 | ug/kg | |
| 77-47-4 | Hexachlorocyclopentadiene | ND | 330 | 13 | ug/kg | |
| 67-72-1 | Hexachloroethane | ND | 170 | 16 | ug/kg | |
| 193-39-5 | Indeno(1,2,3-cd)pyrene | ND | 33 | 16 | ug/kg | |
| 78-59-1 | Isophorone | ND | 67 | 7.1 | ug/kg | |
| 91-57-6 | 2-Methylnaphthalene | ND | 67 | 7.5 | ug/kg | |
| 88-74-4 | 2-Nitroaniline | ND | 170 | 7.9 | ug/kg | |
| 99-09-2 | 3-Nitroaniline | ND | 170 | 8.3 | ug/kg | |
| 100-01-6 | 4-Nitroaniline | ND | 170 | 8.6 | ug/kg | |
| 91-20-3 | Naphthalene | ND | 33 | 9.4 | ug/kg | |
| 98-95-3 | Nitrobenzene | ND | 67 | 13 | ug/kg | |
| 621-64-7 | N-Nitroso-di-n-propylamine | ND | 67 | 9.6 | ug/kg | |
| 86-30-6 | N-Nitrosodiphenylamine | ND | 170 | 12 | ug/kg | |
| 85-01-8 | Phenanthrene | ND | 33 | 11 | ug/kg | |
| 129-00-0 | Pyrene | ND | 33 | 11 | ug/kg | |
| 95-94-3 | 1,2,4,5-Tetrachlorobenzene | ND | 170 | 8.5 | ug/kg | |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MB1 | M128185.D | 1 | 10/07/16 | CS | 10/06/16 | OP97539 | EM5462 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 367-12-4 | 2-Fluorophenol | 81% | 30-106% |
| 4165-62-2 | Phenol-d5 | 84% | 30-106% |
| 118-79-6 | 2,4,6-Tribromophenol | 108% | 24-140% |
| 4165-60-0 | Nitrobenzene-d5 | 90% | 26-122% |
| 321-60-8 | 2-Fluorobiphenyl | 82% | 36-112% |
| 1718-51-0 | Terphenyl-d14 | 85% | 36-132% |

| CAS No. | Tentatively Identified Compounds | R.T. | Est. Conc. | Units | Q |
|---|---|---|---|---|---|
| | system artifact | 1.78 | 1600 | ug/kg | J |
| | system artifact | 2.19 | 220 | ug/kg | J |
| | system artifact | 3.21 | 310 | ug/kg | J |
| | system artifact | 3.48 | 210 | ug/kg | J |
| | system artifact/aldol-condensation | 3.59 | 350 | ug/kg | J |
| | Total TIC, Semi-Volatile | | 0 | ug/kg | |

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-BS1 | P107984.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 95-57-8 | 2-Chlorophenol | 1670 | 1410 | 85 | 54-98 |
| 59-50-7 | 4-Chloro-3-methyl phenol | 1670 | 1570 | 94 | 52-107 |
| 120-83-2 | 2,4-Dichlorophenol | 1670 | 1540 | 92 | 53-105 |
| 105-67-9 | 2,4-Dimethylphenol | 1670 | 1470 | 88 | 49-115 |
| 51-28-5 | 2,4-Dinitrophenol | 3330 | 2740 | 82 | 30-127 |
| 534-52-1 | 4,6-Dinitro-o-cresol | 1670 | 1500 | 90 | 41-114 |
| 95-48-7 | 2-Methylphenol | 1670 | 1430 | 86 | 53-103 |
| | 3&4-Methylphenol | 1670 | 1370 | 82 | 53-102 |
| 88-75-5 | 2-Nitrophenol | 1670 | 1530 | 92 | 52-104 |
| 100-02-7 | 4-Nitrophenol | 1670 | 1320 | 79 | 36-143 |
| 87-86-5 | Pentachlorophenol | 1670 | 1110 | 67 | 29-128 |
| 108-95-2 | Phenol | 1670 | 1240 | 74 | 45-106 |
| 58-90-2 | 2,3,4,6-Tetrachlorophenol | 1670 | 1420 | 85 | 47-113 |
| 95-95-4 | 2,4,5-Trichlorophenol | 1670 | 1450 | 87 | 55-112 |
| 88-06-2 | 2,4,6-Trichlorophenol | 1670 | 1610 | 97 | 57-108 |
| 83-32-9 | Acenaphthene | 1670 | 1470 | 88 | 60-108 |
| 208-96-8 | Acenaphthylene | 1670 | 1390 | 83 | 54-94 |
| 98-86-2 | Acetophenone | 1670 | 1360 | 82 | 53-110 |
| 120-12-7 | Anthracene | 1670 | 1450 | 87 | 59-109 |
| 1912-24-9 | Atrazine | 1670 | 1500 | 90 | 59-126 |
| 56-55-3 | Benzo(a)anthracene | 1670 | 1520 | 91 | 52-113 |
| 50-32-8 | Benzo(a)pyrene | 1670 | 1500 | 90 | 56-122 |
| 205-99-2 | Benzo(b)fluoranthene | 1670 | 1440 | 86 | 53-119 |
| 191-24-2 | Benzo(g,h,i)perylene | 1670 | 1440 | 86 | 48-117 |
| 207-08-9 | Benzo(k)fluoranthene | 1670 | 1460 | 88 | 52-115 |
| 101-55-3 | 4-Bromophenyl phenyl ether | 1670 | 1530 | 92 | 58-114 |
| 85-68-7 | Butyl benzyl phthalate | 1670 | 1680 | 101 | 44-132 |
| 92-52-4 | 1,1'-Biphenyl | 1670 | 1440 | 86 | 54-101 |
| 100-52-7 | Benzaldehyde | 1670 | 1460 | 88 | 39-117 |
| 91-58-7 | 2-Chloronaphthalene | 1670 | 1400 | 84 | 54-103 |
| 106-47-8 | 4-Chloroaniline | 1670 | 1020 | 61 | 10-110 |
| 86-74-8 | Carbazole | 1670 | 1520 | 91 | 55-105 |
| 105-60-2 | Caprolactam | 1670 | 1080 | 65 | 42-111 |
| 218-01-9 | Chrysene | 1670 | 1410 | 85 | 51-119 |
| 111-91-1 | bis(2-Chloroethoxy)methane | 1670 | 1380 | 83 | 51-106 |
| 111-44-4 | bis(2-Chloroethyl)ether | 1670 | 1440 | 86 | 48-107 |

* = Outside of Control Limits.

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-BS1 | P107984.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 108-60-1 | bis(2-Chloroisopropyl)ether | 1670 | 1270 | 76 | 46-103 |
| 7005-72-3 | 4-Chlorophenyl phenyl ether | 1670 | 1450 | 87 | 54-112 |
| 121-14-2 | 2,4-Dinitrotoluene | 1670 | 1600 | 96 | 56-116 |
| 606-20-2 | 2,6-Dinitrotoluene | 1670 | 1550 | 93 | 56-115 |
| 91-94-1 | 3,3'-Dichlorobenzidine | 3330 | 2040 | 61 | 22-103 |
| 123-91-1 | 1,4-Dioxane | 1670 | 813 | 49 | 14-110 |
| 53-70-3 | Dibenzo(a,h)anthracene | 1670 | 1500 | 90 | 49-118 |
| 132-64-9 | Dibenzofuran | 1670 | 1540 | 92 | 55-103 |
| 84-74-2 | Di-n-butyl phthalate | 1670 | 1610 | 97 | 56-117 |
| 117-84-0 | Di-n-octyl phthalate | 1670 | 1720 | 103 | 47-137 |
| 84-66-2 | Diethyl phthalate | 1670 | 1470 | 88 | 54-112 |
| 131-11-3 | Dimethyl phthalate | 1670 | 1440 | 86 | 56-108 |
| 117-81-7 | bis(2-Ethylhexyl)phthalate | 1670 | 1630 | 98 | 45-130 |
| 206-44-0 | Fluoranthene | 1670 | 1490 | 89 | 58-110 |
| 86-73-7 | Fluorene | 1670 | 1450 | 87 | 59-108 |
| 118-74-1 | Hexachlorobenzene | 1670 | 1420 | 85 | 55-114 |
| 87-68-3 | Hexachlorobutadiene | 1670 | 1380 | 83 | 44-118 |
| 77-47-4 | Hexachlorocyclopentadiene | 3330 | 2180 | 65 | 41-137 |
| 67-72-1 | Hexachloroethane | 1670 | 1400 | 84 | 50-107 |
| 193-39-5 | Indeno(1,2,3-cd)pyrene | 1670 | 1450 | 87 | 48-120 |
| 78-59-1 | Isophorone | 1670 | 1350 | 81 | 54-109 |
| 91-57-6 | 2-Methylnaphthalene | 1670 | 1400 | 84 | 48-104 |
| 88-74-4 | 2-Nitroaniline | 1670 | 1530 | 92 | 49-124 |
| 99-09-2 | 3-Nitroaniline | 1670 | 1140 | 68 | 22-110 |
| 100-01-6 | 4-Nitroaniline | 1670 | 1540 | 92 | 50-107 |
| 91-20-3 | Naphthalene | 1670 | 1360 | 82 | 49-100 |
| 98-95-3 | Nitrobenzene | 1670 | 1390 | 83 | 47-108 |
| 621-64-7 | N-Nitroso-di-n-propylamine | 1670 | 1290 | 77 | 49-106 |
| 86-30-6 | N-Nitrosodiphenylamine | 1670 | 1440 | 86 | 53-112 |
| 85-01-8 | Phenanthrene | 1670 | 1470 | 88 | 57-105 |
| 129-00-0 | Pyrene | 1670 | 1520 | 91 | 50-117 |
| 95-94-3 | 1,2,4,5-Tetrachlorobenzene | 1670 | 1350 | 81 | 52-109 |

* = Outside of Control Limits.

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-BS1 | P107984.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Surrogate Recoveries | BSP | Limits |
|---|---|---|---|
| 367-12-4 | 2-Fluorophenol | 83% | 30-106% |
| 4165-62-2 | Phenol-d5 | 77% | 30-106% |
| 118-79-6 | 2,4,6-Tribromophenol | 85% | 24-140% |
| 4165-60-0 | Nitrobenzene-d5 | 91% | 26-122% |
| 321-60-8 | 2-Fluorobiphenyl | 93% | 36-112% |
| 1718-51-0 | Terphenyl-d14 | 96% | 36-132% |

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MS | P107985.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |
| OP97539-MSD | P107986.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |
| JC28910-1 | P107987.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | JC28910-1 ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Spike ug/kg | MSD ug/kg | MSD % | RPD | Limits Rec/RPD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 95-57-8 | 2-Chlorophenol | ND | | 1680 | 1310 | 78 | 1670 | 1260 | 75 | 4 | 33-106/35 |
| 59-50-7 | 4-Chloro-3-methyl phenol | ND | | 1680 | 1540 | 92 | 1670 | 1500 | 90 | 3 | 27-124/34 |
| 120-83-2 | 2,4-Dichlorophenol | ND | | 1680 | 1490 | 89 | 1670 | 1470 | 88 | 1 | 25-122/34 |
| 105-67-9 | 2,4-Dimethylphenol | ND | | 1680 | 1580 | 94 | 1670 | 1550 | 93 | 2 | 23-133/34 |
| 51-28-5 | 2,4-Dinitrophenol | ND | | 3360 | 2560 | 76 | 3340 | 2420 | 72 | 6 | 10-110/51 |
| 534-52-1 | 4,6-Dinitro-o-cresol | ND | | 1680 | 1490 | 89 | 1670 | 1380 | 83 | 8 | 10-113/49 |
| 95-48-7 | 2-Methylphenol | ND | | 1680 | 1430 | 85 | 1670 | 1330 | 80 | 7 | 32-111/34 |
| | 3&4-Methylphenol | ND | | 1680 | 1400 | 83 | 1670 | 1290 | 77 | 8 | 32-113/34 |
| 88-75-5 | 2-Nitrophenol | ND | | 1680 | 1490 | 89 | 1670 | 1470 | 88 | 1 | 17-118/37 |
| 100-02-7 | 4-Nitrophenol | ND | | 1680 | 1370 | 82 | 1670 | 1300 | 78 | 5 | 14-154/39 |
| 87-86-5 | Pentachlorophenol | ND | | 1680 | 1070 | 64 | 1670 | 939 | 56 | 13 | 10-131/43 |
| 108-95-2 | Phenol | ND | | 1680 | 1190 | 71 | 1670 | 1110 | 66 | 7 | 25-112/33 |
| 58-90-2 | 2,3,4,6-Tetrachlorophenol | ND | | 1680 | 1400 | 83 | 1670 | 1340 | 80 | 4 | 19-125/37 |
| 95-95-4 | 2,4,5-Trichlorophenol | ND | | 1680 | 1420 | 84 | 1670 | 1380 | 83 | 3 | 30-125/35 |
| 88-06-2 | 2,4,6-Trichlorophenol | ND | | 1680 | 1490 | 89 | 1670 | 1540 | 92 | 3 | 26-126/35 |
| 83-32-9 | Acenaphthene | ND | | 1680 | 1410 | 84 | 1670 | 1390 | 83 | 1 | 34-125/36 |
| 208-96-8 | Acenaphthylene | ND | | 1680 | 1350 | 80 | 1670 | 1340 | 80 | 1 | 28-113/34 |
| 98-86-2 | Acetophenone | ND | | 1680 | 1340 | 80 | 1670 | 1200 | 72 | 11 | 26-120/34 |
| 120-12-7 | Anthracene | ND | | 1680 | 1430 | 85 | 1670 | 1390 | 83 | 3 | 31-131/41 |
| 1912-24-9 | Atrazine | ND | | 1680 | 1470 | 87 | 1670 | 1420 | 85 | 3 | 34-138/36 |
| 56-55-3 | Benzo(a)anthracene | ND | | 1680 | 1490 | 89 | 1670 | 1420 | 85 | 5 | 23-136/43 |
| 50-32-8 | Benzo(a)pyrene | ND | | 1680 | 1530 | 91 | 1670 | 1440 | 86 | 6 | 22-144/42 |
| 205-99-2 | Benzo(b)fluoranthene | ND | | 1680 | 1450 | 86 | 1670 | 1370 | 82 | 6 | 18-145/43 |
| 191-24-2 | Benzo(g,h,i)perylene | ND | | 1680 | 1520 | 90 | 1670 | 1360 | 81 | 11 | 20-138/43 |
| 207-08-9 | Benzo(k)fluoranthene | ND | | 1680 | 1480 | 88 | 1670 | 1370 | 82 | 8 | 27-129/43 |
| 101-55-3 | 4-Bromophenyl phenyl ether | ND | | 1680 | 1450 | 86 | 1670 | 1430 | 86 | 1 | 39-124/33 |
| 85-68-7 | Butyl benzyl phthalate | ND | | 1680 | 1650 | 98 | 1670 | 1540 | 92 | 7 | 27-143/35 |
| 92-52-4 | 1,1'-Biphenyl | ND | | 1680 | 1370 | 82 | 1670 | 1340 | 80 | 2 | 33-116/32 |
| 100-52-7 | Benzaldehyde | ND | | 1680 | 1320 | 79 | 1670 | 1230 | 74 | 7 | 20-129/34 |
| 91-58-7 | 2-Chloronaphthalene | ND | | 1680 | 1370 | 82 | 1670 | 1370 | 82 | 0 | 38-110/32 |
| 106-47-8 | 4-Chloroaniline | ND | | 1680 | 1130 | 67 | 1670 | 1070 | 64 | 5 | 10-110/49 |
| 86-74-8 | Carbazole | ND | | 1680 | 1480 | 88 | 1670 | 1420 | 85 | 4 | 27-129/38 |
| 105-60-2 | Caprolactam | ND | | 1680 | 1060 | 63 | 1670 | 1030 | 62 | 3 | 18-127/35 |
| 218-01-9 | Chrysene | ND | | 1680 | 1380 | 82 | 1670 | 1330 | 80 | 4 | 21-142/43 |
| 111-91-1 | bis(2-Chloroethoxy)methane | ND | | 1680 | 1350 | 80 | 1670 | 1280 | 77 | 5 | 32-116/33 |
| 111-44-4 | bis(2-Chloroethyl)ether | ND | | 1680 | 1620 | 96 | 1670 | 1290 | 77 | 23 | 30-113/37 |

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MS | P107985.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |
| OP97539-MSD | P107986.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |
| JC28910-1 | P107987.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Compound | JC28910-1 ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Spike ug/kg | MSD ug/kg | MSD % | RPD | Limits Rec/RPD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 108-60-1 | bis(2-Chloroisopropyl)ether | ND | | 1680 | 1290 | 77 | 1670 | 1170 | 70 | 10 | 28-110/33 |
| 7005-72-3 | 4-Chlorophenyl phenyl ether | ND | | 1680 | 1400 | 83 | 1670 | 1400 | 84 | 0 | 38-119/33 |
| 121-14-2 | 2,4-Dinitrotoluene | ND | | 1680 | 1580 | 94 | 1670 | 1540 | 92 | 3 | 28-126/36 |
| 606-20-2 | 2,6-Dinitrotoluene | ND | | 1680 | 1480 | 88 | 1670 | 1460 | 87 | 1 | 31-126/34 |
| 91-94-1 | 3,3'-Dichlorobenzidine | ND | | 3360 | 2450 | 73 | 3340 | 2160 | 65 | 13 | 10-115/44 |
| 123-91-1 | 1,4-Dioxane | ND | | 1680 | 740 | 44 | 1670 | 691 | 41 | 7 | 10-110/38 |
| 53-70-3 | Dibenzo(a,h)anthracene | ND | | 1680 | 1540 | 92 | 1670 | 1430 | 86 | 7 | 25-135/41 |
| 132-64-9 | Dibenzofuran | ND | | 1680 | 1470 | 87 | 1670 | 1470 | 88 | 0 | 30-125/35 |
| 84-74-2 | Di-n-butyl phthalate | ND | | 1680 | 1580 | 94 | 1670 | 1510 | 90 | 5 | 32-131/34 |
| 117-84-0 | Di-n-octyl phthalate | ND | | 1680 | 1700 | 101 | 1670 | 1620 | 97 | 5 | 28-144/35 |
| 84-66-2 | Diethyl phthalate | ND | | 1680 | 1450 | 86 | 1670 | 1390 | 83 | 4 | 35-124/32 |
| 131-11-3 | Dimethyl phthalate | ND | | 1680 | 1410 | 84 | 1670 | 1390 | 83 | 1 | 36-121/33 |
| 117-81-7 | bis(2-Ethylhexyl)phthalate | ND | | 1680 | 1610 | 96 | 1670 | 1490 | 89 | 8 | 25-146/35 |
| 206-44-0 | Fluoranthene | ND | | 1680 | 1500 | 89 | 1670 | 1430 | 86 | 5 | 15-143/46 |
| 86-73-7 | Fluorene | ND | | 1680 | 1420 | 84 | 1670 | 1400 | 84 | 1 | 30-129/37 |
| 118-74-1 | Hexachlorobenzene | ND | | 1680 | 1430 | 85 | 1670 | 1340 | 80 | 6 | 34-125/34 |
| 87-68-3 | Hexachlorobutadiene | ND | | 1680 | 1370 | 82 | 1670 | 1280 | 77 | 7 | 29-120/34 |
| 77-47-4 | Hexachlorocyclopentadiene | ND | | 3360 | 2060 | 61 | 3340 | 1970 | 59 | 4 | 10-127/46 |
| 67-72-1 | Hexachloroethane | ND | | 1680 | 1420 | 84 | 1670 | 1210 | 72 | 16 | 21-109/38 |
| 193-39-5 | Indeno(1,2,3-cd)pyrene | ND | | 1680 | 1480 | 88 | 1670 | 1390 | 83 | 6 | 23-141/44 |
| 78-59-1 | Isophorone | ND | | 1680 | 1330 | 79 | 1670 | 1270 | 76 | 5 | 31-124/32 |
| 91-57-6 | 2-Methylnaphthalene | ND | | 1680 | 1360 | 81 | 1670 | 1290 | 77 | 5 | 21-125/33 |
| 88-74-4 | 2-Nitroaniline | ND | | 1680 | 1440 | 86 | 1670 | 1450 | 87 | 1 | 29-138/33 |
| 99-09-2 | 3-Nitroaniline | ND | | 1680 | 1200 | 71 | 1670 | 1160 | 69 | 3 | 12-112/38 |
| 100-01-6 | 4-Nitroaniline | ND | | 1680 | 1450 | 86 | 1670 | 1470 | 88 | 1 | 21-117/38 |
| 91-20-3 | Naphthalene | ND | | 1680 | 1360 | 81 | 1670 | 1270 | 76 | 7 | 24-118/35 |
| 98-95-3 | Nitrobenzene | ND | | 1680 | 1360 | 81 | 1670 | 1260 | 75 | 8 | 28-118/32 |
| 621-64-7 | N-Nitroso-di-n-propylamine | ND | | 1680 | 1280 | 76 | 1670 | 1140 | 68 | 12 | 26-121/34 |
| 86-30-6 | N-Nitrosodiphenylamine | ND | | 1680 | 1430 | 85 | 1670 | 1380 | 83 | 4 | 24-142/35 |
| 85-01-8 | Phenanthrene | ND | | 1680 | 1460 | 87 | 1670 | 1390 | 83 | 5 | 14-144/44 |
| 129-00-0 | Pyrene | ND | | 1680 | 1490 | 89 | 1670 | 1410 | 84 | 6 | 16-147/46 |
| 95-94-3 | 1,2,4,5-Tetrachlorobenzene | ND | | 1680 | 1320 | 79 | 1670 | 1300 | 78 | 2 | 37-115/32 |

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97539-MS | P107985.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |
| OP97539-MSD | P107986.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |
| JC28910-1 | P107987.D | 1 | 10/06/16 | RL | 10/06/16 | OP97539 | EP4787 |

**The QC reported here applies to the following samples:** **Method:** SW846 8270D

JC28902-1

| CAS No. | Surrogate Recoveries | MS | MSD | JC28910-1 | Limits |
|---|---|---|---|---|---|
| 367-12-4 | 2-Fluorophenol | 70% | 74% | 72% | 30-106% |
| 4165-62-2 | Phenol-d5 | 84% | 70% | 75% | 30-106% |
| 118-79-6 | 2,4,6-Tribromophenol | 87% | 83% | 79% | 24-140% |
| 4165-60-0 | Nitrobenzene-d5 | 89% | 86% | 89% | 26-122% |
| 321-60-8 | 2-Fluorobiphenyl | 88% | 90% | 91% | 36-112% |
| 1718-51-0 | Terphenyl-d14 | 94% | 92% | 88% | 36-132% |

* = Outside of Control Limits.

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5442-DFTPP
**Lab File ID:** M127785.D
**Instrument ID:** GCMSM
**Injection Date:** 09/24/16
**Injection Time:** 08:54

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 105373 | 35.1 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 149572 | 49.9 | | Pass |
| 70 | Less than 2.0% of mass 69 | 724 | 0.24 | (0.48) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 166918 | 55.6 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 299946 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 21993 | 7.33 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 65058 | 21.7 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 7342 | 2.45 | | Pass |
| 441 | Present, but less than mass 443 | 35006 | 11.7 | (78.7) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 230498 | 76.8 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 44478 | 14.8 | (19.3) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EM5442-IC5442 | M127786.D | 09/24/16 | 09:06 | 00:12 | Initial cal 2 |
| EM5442-IC5442 | M127787.D | 09/24/16 | 09:34 | 00:40 | Initial cal 1 |
| EM5442-IC5442 | M127788.D | 09/24/16 | 10:03 | 01:09 | Initial cal 100 |
| EM5442-ICC5442 | M127789.D | 09/24/16 | 10:31 | 01:37 | Initial cal 50 |
| EM5442-IC5442 | M127790.D | 09/24/16 | 10:59 | 02:05 | Initial cal 5 |
| EM5442-IC5442 | M127791.D | 09/24/16 | 11:27 | 02:33 | Initial cal 10 |
| EM5442-IC5442 | M127792.D | 09/24/16 | 11:56 | 03:02 | Initial cal 25 |
| EM5442-IC5442 | M127793.D | 09/24/16 | 12:24 | 03:30 | Initial cal 80 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5443-DFTPP
**Lab File ID:** M127794.D
**Instrument ID:** GCMSM
**Injection Date:** 09/24/16
**Injection Time:** 12:54

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 104664 | 35.3 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 160739 | 54.2 | | Pass |
| 70 | Less than 2.0% of mass 69 | 480 | 0.16 | (0.30) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 177138 | 59.7 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 296520 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 21189 | 7.15 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 69023 | 23.3 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 11253 | 3.80 | | Pass |
| 441 | Present, but less than mass 443 | 42406 | 14.3 | (87.1) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 262675 | 88.6 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 48678 | 16.4 | (18.5) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EM5443-IC5443 | M127795.D | 09/24/16 | 13:05 | 00:11 | Initial cal 100 |
| EM5443-IC5443 | M127796.D | 09/24/16 | 13:34 | 00:40 | Initial cal 80 |
| EM5443-IC5443 | M127797.D | 09/24/16 | 14:02 | 01:08 | Initial cal 25 |
| EM5443-IC5443 | M127798.D | 09/24/16 | 14:30 | 01:36 | Initial cal 10 |
| EM5443-IC5443 | M127799.D | 09/24/16 | 14:58 | 02:04 | Initial cal 5 |
| EM5443-IC5443 | M127800.D | 09/24/16 | 15:27 | 02:33 | Initial cal 2 |
| EM5443-IC5443 | M127801.D | 09/24/16 | 15:55 | 03:01 | Initial cal 1 |
| EM5443-ICC5443 | M127802.D | 09/24/16 | 16:23 | 03:29 | Initial cal 50 |
| EM5443-ICV5442 | M127803.D | 09/24/16 | 16:52 | 03:58 | Initial cal verification 50 |
| EM5443-ICV5442 | M127804.D | 09/24/16 | 17:20 | 04:26 | Initial cal verification 50 |
| EM5443-ICV5442 | M127805.D | 09/24/16 | 17:48 | 04:54 | Initial cal verification 50 |
| EM5443-ICV5443 | M127806A.D | 09/24/16 | 18:16 | 05:22 | Initial cal verification 50 |
| EM5443-ICV5442 | M127806.D | 09/24/16 | 18:16 | 05:22 | Initial cal verification 50 |
| EM5443-ICV5442 | M127808.D | 09/24/16 | 19:13 | 06:19 | Initial cal verification 50 |
| EM5443-ICV5443 | M127808A.D | 09/24/16 | 19:13 | 06:19 | Initial cal verification 50 |
| EM5443-ICV5443 | M127809.D | 09/24/16 | 19:41 | 06:47 | Initial cal verification 50 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5444-DFTPP
**Lab File ID:** M127815.D
**Instrument ID:** GCMSM
**Injection Date:** 09/26/16
**Injection Time:** 13:01

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 113048 | 30.4 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 164640 | 44.3 | | Pass |
| 70 | Less than 2.0% of mass 69 | 1333 | 0.36 | (0.81) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 203253 | 54.7 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 371328 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 24176 | 6.51 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 86575 | 23.3 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 11199 | 3.02 | | Pass |
| 441 | Present, but less than mass 443 | 49731 | 13.4 | (88.0) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 314922 | 84.8 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 56522 | 15.2 | (17.9) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EM5444-ICV5443 | M127816A.D | 09/26/16 | 13:14 | 00:13 | Initial cal verification 50 |
| EM5444-ICV5442 | M127816.D | 09/26/16 | 13:14 | 00:13 | Initial cal verification 50 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5462-DFTPP
**Lab File ID:** M128174.D
**Instrument ID:** GCMSM
**Injection Date:** 10/07/16
**Injection Time:** 09:03

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 100448 | 31.7 | | Pass |
| 68 | Less than 2.0% of mass 69 | 963 | 0.30 | (0.67) [a] | Pass |
| 69 | Mass 69 relative abundance | 143925 | 45.4 | | Pass |
| 70 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 172026 | 54.2 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 317319 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 22762 | 7.17 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 81666 | 25.7 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 12639 | 3.98 | | Pass |
| 441 | Present, but less than mass 443 | 45802 | 14.4 | (76.7) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 314111 | 99.0 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 59677 | 18.8 | (19.0) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EM5462-CC5442 | M128175.D | 10/07/16 | 09:15 | 00:12 | Continuing cal 25 |
| EM5462-CC5443 | M128178.D | 10/07/16 | 10:49 | 01:46 | Continuing cal 25 |
| OP97337A-MB1 | M128180.D | 10/07/16 | 12:27 | 03:24 | Method Blank |
| OP97337A-BS1 | M128181.D | 10/07/16 | 12:55 | 03:52 | Blank Spike |
| OP97337A-BSD | M128182.D | 10/07/16 | 13:24 | 04:21 | Blank Spike Duplicate |
| ZZZZZZ | M128183.D | 10/07/16 | 13:52 | 04:49 | (unrelated sample) |
| OP97539-MB1 | M128185.D | 10/07/16 | 14:20 | 05:17 | Method Blank |
| JC28902-1 | M128186.D | 10/07/16 | 14:49 | 05:46 | WOOLSTON-TS-002 |
| JC28902-1 | M128187.D | 10/07/16 | 15:17 | 06:14 | WOOLSTON-TS-002 |
| ZZZZZZ | M128184.D | 10/07/16 | 15:46 | 06:43 | (unrelated sample) |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4769-DFTPP
**Lab File ID:** P107661A.D
**Instrument ID:** GCMSP
**Injection Date:** 09/21/16
**Injection Time:** 15:01

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 18792 | 37.0 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 25458 | 50.1 | | Pass |
| 70 | Less than 2.0% of mass 69 | 73 | 0.14 | (0.29) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 23152 | 45.6 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 50773 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 3727 | 7.34 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 13590 | 26.8 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 1408 | 2.77 | | Pass |
| 441 | Present, but less than mass 443 | 5138 | 10.1 | (83.1) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 32706 | 64.4 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 6186 | 12.2 | (18.9) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EP4769-IC4769 | P107662.D | 09/21/16 | 15:24 | 00:23 | Initial cal 100 |
| EP4769-IC4769 | P107663.D | 09/21/16 | 15:52 | 00:51 | Initial cal 1 |
| EP4769-ICC4769 | P107664.D | 09/21/16 | 16:25 | 01:24 | Initial cal 50 |
| EP4769-IC4769 | P107665.D | 09/21/16 | 16:53 | 01:52 | Initial cal 2 |
| EP4769-IC4769 | P107666.D | 09/21/16 | 17:21 | 02:20 | Initial cal 5 |
| EP4769-IC4769 | P107667.D | 09/21/16 | 17:49 | 02:48 | Initial cal 10 |
| EP4769-IC4769 | P107668.D | 09/21/16 | 18:17 | 03:16 | Initial cal 25 |
| EP4769-IC4769 | P107669.D | 09/21/16 | 18:45 | 03:44 | Initial cal 80 |
| EP4769-ICV4769 | P107670.D | 09/21/16 | 19:14 | 04:13 | Initial cal verification 50 |
| EP4769-ICV4769 | P107672.D | 09/21/16 | 20:11 | 05:10 | Initial cal verification 50 |
| EP4769-ICV4769 | P107673.D | 09/21/16 | 20:39 | 05:38 | Initial cal verification 50 |
| EP4769-ICV4769 | P107674.D | 09/21/16 | 21:07 | 06:06 | Initial cal verification 50 |
| EP4769-ICV4769 | P107675.D | 09/21/16 | 21:34 | 06:33 | Initial cal verification 50 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4770-DFTPP
**Lab File ID:** P107676.D
**Instrument ID:** GCMSP
**Injection Date:** 09/22/16
**Injection Time:** 08:26

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 20850 | 37.5 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 27904 | 50.2 | | Pass |
| 70 | Less than 2.0% of mass 69 | 63 | 0.11 | (0.23) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 25264 | 45.5 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 55546 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 3673 | 6.61 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 14326 | 25.8 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 1638 | 2.95 | | Pass |
| 441 | Present, but less than mass 443 | 5853 | 10.5 | (83.3) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 35394 | 63.7 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 7029 | 12.7 | (19.9) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EP4770-IC4770 | P107677.D | 09/22/16 | 08:42 | 00:16 | Initial cal 100 |
| EP4770-IC4770 | P107678.D | 09/22/16 | 09:10 | 00:44 | Initial cal 80 |
| EP4770-ICC4770 | P107679.D | 09/22/16 | 09:38 | 01:12 | Initial cal 50 |
| EP4770-IC4770 | P107680.D | 09/22/16 | 10:06 | 01:40 | Initial cal 25 |
| EP4770-IC4770 | P107681.D | 09/22/16 | 10:34 | 02:08 | Initial cal 10 |
| EP4770-IC4770 | P107682.D | 09/22/16 | 11:02 | 02:36 | Initial cal 5 |
| EP4770-IC4770 | P107683.D | 09/22/16 | 11:30 | 03:04 | Initial cal 2 |
| EP4770-IC4770 | P107684.D | 09/22/16 | 11:57 | 03:31 | Initial cal 1 |
| EP4770-ICV4770 | P107685.D | 09/22/16 | 12:25 | 03:59 | Initial cal verification 50 |
| EP4770-ICV4770 | P107686.D | 09/22/16 | 12:53 | 04:27 | Initial cal verification 51 |
| EP4770-ICV4770 | P107687.D | 09/22/16 | 13:21 | 04:55 | Initial cal verification 50 |
| EP4770-ICV4770 | P107688.D | 09/22/16 | 13:50 | 05:24 | Initial cal verification 50 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4771-DFTPP
**Lab File ID:** P107689.D
**Instrument ID:** GCMSP
**Injection Date:** 09/22/16
**Injection Time:** 14:47

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 14988 | 30.3 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 22418 | 45.4 | | Pass |
| 70 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 21310 | 43.1 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 49426 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 3344 | 6.77 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 13218 | 26.7 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 1379 | 2.79 | | Pass |
| 441 | Present, but less than mass 443 | 5951 | 12.0 | (84.7) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 37178 | 75.2 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 7026 | 14.2 | (18.9) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EP4771-ICV4769 | P107690.D | 09/22/16 | 15:22 | 00:35 | Initial cal verification 50 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4787-DFTPP
**Lab File ID:** P107973.D
**Instrument ID:** GCMSP
**Injection Date:** 10/06/16
**Injection Time:** 09:57

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 16322 | 34.4 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 21158 | 44.6 | | Pass |
| 70 | Less than 2.0% of mass 69 | 157 | 0.33 | (0.74) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 21293 | 44.9 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 47453 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 3321 | 7.00 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 12276 | 25.9 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 1559 | 3.29 | | Pass |
| 441 | Present, but less than mass 443 | 5311 | 11.2 | (82.5) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 32325 | 68.1 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 6440 | 13.6 | (19.9) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EP4787-CC4769 | P107974.D | 10/06/16 | 10:09 | 00:12 | Continuing cal 25 |
| EP4787-CC4770 | P107975.D | 10/06/16 | 10:36 | 00:39 | Continuing cal 25 |
| OP95519-MB1 | P107978.D | 10/06/16 | 12:18 | 02:21 | Method Blank |
| OP97539-MB1 | P107983.D | 10/06/16 | 14:37 | 04:40 | Method Blank |
| OP97539-BS1 | P107984.D | 10/06/16 | 15:05 | 05:08 | Blank Spike |
| JC28910-1 | P107987.D | 10/06/16 | 15:33 | 05:36 | (used for QC only; not part of job JC28902) |
| ZZZZZZ | P107988.D | 10/06/16 | 16:01 | 06:04 | (unrelated sample) |
| OP97539-MS | P107985.D | 10/06/16 | 16:29 | 06:32 | Matrix Spike |
| OP97539-MSD | P107986.D | 10/06/16 | 16:57 | 07:00 | Matrix Spike Duplicate |
| ZZZZZZ | P107989.D | 10/06/16 | 17:25 | 07:28 | (unrelated sample) |
| ZZZZZZ | P107990.D | 10/06/16 | 17:53 | 07:56 | (unrelated sample) |
| ZZZZZZ | P107991.D | 10/06/16 | 18:21 | 08:24 | (unrelated sample) |
| ZZZZZZ | P107992.D | 10/06/16 | 18:48 | 08:51 | (unrelated sample) |
| ZZZZZZ | P107993.D | 10/06/16 | 19:16 | 09:19 | (unrelated sample) |
| ZZZZZZ | P107994.D | 10/06/16 | 19:44 | 09:47 | (unrelated sample) |
| ZZZZZZ | P107995.D | 10/06/16 | 20:12 | 10:15 | (unrelated sample) |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5695-DFTPP
**Lab File ID:** Z114090.D
**Instrument ID:** GCMSZ
**Injection Date:** 09/14/16
**Injection Time:** 14:10

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 57762 | 30.1 | | Pass |
| 68 | Less than 2.0% of mass 69 | 490 | 0.26 | (0.61) [a] | Pass |
| 69 | Mass 69 relative abundance | 79784 | 41.6 | | Pass |
| 70 | Less than 2.0% of mass 69 | 416 | 0.22 | (0.52) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 95874 | 50.0 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 191730 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 13255 | 6.91 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 44994 | 23.5 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 5571 | 2.91 | | Pass |
| 441 | Present, but less than mass 443 | 17773 | 9.27 | (76.3) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 123016 | 64.2 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 23306 | 12.2 | (18.9) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EZ5695-IC5695 | Z114092A.D | 09/14/16 | 14:38 | 00:28 | Initial cal 2 |
| EZ5695-IC5695 | Z114093.D | 09/14/16 | 15:05 | 00:55 | Initial cal 1 |
| EZ5695-IC5695 | Z114094.D | 09/14/16 | 15:33 | 01:23 | Initial cal 100 |
| EZ5695-ICC5695 | Z114095.D | 09/14/16 | 16:01 | 01:51 | Initial cal 50 |
| EZ5695-IC5695 | Z114096.D | 09/14/16 | 16:28 | 02:18 | Initial cal 80 |
| EZ5695-IC5695 | Z114097.D | 09/14/16 | 16:55 | 02:45 | Initial cal 25 |
| EZ5695-IC5695 | Z114098.D | 09/14/16 | 17:23 | 03:13 | Initial cal 10 |
| EZ5695-IC5695 | Z114099.D | 09/14/16 | 17:49 | 03:39 | Initial cal 5 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5696-DFTPP
**Lab File ID:** Z114103.D
**Instrument ID:** GCMSZ
**Injection Date:** 09/15/16
**Injection Time:** 07:35

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 47954 | 30.4 | | Pass |
| 68 | Less than 2.0% of mass 69 | 1125 | 0.71 | (1.75) [a] | Pass |
| 69 | Mass 69 relative abundance | 64142 | 40.6 | | Pass |
| 70 | Less than 2.0% of mass 69 | 591 | 0.37 | (0.92) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 76333 | 48.3 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 157941 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 10519 | 6.66 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 36816 | 23.3 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 4277 | 2.71 | | Pass |
| 441 | Present, but less than mass 443 | 14771 | 9.35 | (74.1) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 102917 | 65.2 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 19940 | 12.6 | (19.4) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EZ5696-IC5696 | Z114104.D | 09/15/16 | 07:50 | 00:15 | Initial cal 100 |
| EZ5696-IC5696 | Z114105.D | 09/15/16 | 08:17 | 00:42 | Initial cal 2 |
| EZ5696-IC5696 | Z114106.D | 09/15/16 | 08:43 | 01:08 | Initial cal 80 |
| EZ5696-ICC5696 | Z114107.D | 09/15/16 | 09:09 | 01:34 | Initial cal 50 |
| EZ5696-IC5696 | Z114108.D | 09/15/16 | 09:35 | 02:00 | Initial cal 25 |
| EZ5696-IC5696 | Z114109.D | 09/15/16 | 10:01 | 02:26 | Initial cal 10 |
| EZ5696-IC5696 | Z114110.D | 09/15/16 | 10:26 | 02:51 | Initial cal 5 |
| EZ5696-IC5696 | Z114111.D | 09/15/16 | 10:52 | 03:17 | Initial cal 1 |
| EZ5696-ICV5695 | Z114112.D | 09/15/16 | 11:18 | 03:43 | Initial cal verification 50 |
| EZ5696-ICV5695 | Z114113.D | 09/15/16 | 11:43 | 04:08 | Initial cal verification 50 |
| EZ5696-ICV5695 | Z114114.D | 09/15/16 | 12:09 | 04:34 | Initial cal verification 50 |
| EZ5696-ICV5695 | Z114115.D | 09/15/16 | 12:35 | 05:00 | Initial cal verification 50 |
| EZ5696-ICV5696 | Z114115A.D | 09/15/16 | 12:35 | 05:00 | Initial cal verification 50 |
| EZ5696-ICV5695 | Z114116.D | 09/15/16 | 13:01 | 05:26 | Initial cal verification 50 |
| EZ5696-ICV5696 | Z114116A.D | 09/15/16 | 13:01 | 05:26 | Initial cal verification 50 |
| EZ5696-ICV5695 | Z114117.D | 09/15/16 | 13:26 | 05:51 | Initial cal verification 50 |
| EZ5696-ICV5696 | Z114118.D | 09/15/16 | 13:52 | 06:17 | Initial cal verification 50 |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5729-DFTPP
**Lab File ID:** Z114913.D
**Instrument ID:** GCMSZ
**Injection Date:** 10/07/16
**Injection Time:** 09:43

| m/e | Ion Abundance Criteria | Raw Abundance | % Relative Abundance | | Pass/Fail |
|---|---|---|---|---|---|
| 51 | 30.0 - 60.0% of mass 198 | 30500 | 39.2 | | Pass |
| 68 | Less than 2.0% of mass 69 | 0 | 0.00 | (0.00) [a] | Pass |
| 69 | Mass 69 relative abundance | 35041 | 45.0 | | Pass |
| 70 | Less than 2.0% of mass 69 | 185 | 0.24 | (0.53) [a] | Pass |
| 127 | 40.0 - 60.0% of mass 198 | 40669 | 52.3 | | Pass |
| 197 | Less than 1.0% of mass 198 | 0 | 0.00 | | Pass |
| 198 | Base peak, 100% relative abundance | 77808 | 100.0 | | Pass |
| 199 | 5.0 - 9.0% of mass 198 | 5292 | 6.80 | | Pass |
| 275 | 10.0 - 30.0% of mass 198 | 21245 | 27.3 | | Pass |
| 365 | 1.0 - 100.0% of mass 198 | 2872 | 3.69 | | Pass |
| 441 | Present, but less than mass 443 | 9795 | 12.6 | (75.0) [b] | Pass |
| 442 | 40.0 - 100.0% of mass 198 | 65941 | 84.7 | | Pass |
| 443 | 17.0 - 23.0% of mass 442 | 13063 | 16.8 | (19.8) [c] | Pass |

(a) Value is % of mass 69
(b) Value is % of mass 443
(c) Value is % of mass 442

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| EZ5729-CC5695 | Z114914.D | 10/07/16 | 10:11 | 00:28 | Continuing cal 50 |
| EZ5729-CC5696 | Z114915.D | 10/07/16 | 10:38 | 00:55 | Continuing cal 25 |
| OP97539-MB1 | Z114917.D | 10/07/16 | 11:56 | 02:13 | Method Blank |
| ZZZZZZ | Z114918.D | 10/07/16 | 12:22 | 02:39 | (unrelated sample) |
| ZZZZZZ | Z114919.D | 10/07/16 | 12:48 | 03:05 | (unrelated sample) |
| ZZZZZZ | Z114920.D | 10/07/16 | 13:13 | 03:30 | (unrelated sample) |
| OP97072-MB1 | Z114923.D | 10/07/16 | 14:44 | 05:01 | Method Blank |
| ZZZZZZ | Z114924.D | 10/07/16 | 15:10 | 05:27 | (unrelated sample) |
| OP97582-MB1 | Z114925.D | 10/07/16 | 15:35 | 05:52 | Method Blank |
| OP97582-BS1 | Z114926.D | 10/07/16 | 16:01 | 06:18 | Blank Spike |
| ZZZZZZ | Z114927.D | 10/07/16 | 16:27 | 06:44 | (unrelated sample) |
| ZZZZZZ | Z114929.D | 10/07/16 | 17:19 | 07:36 | (unrelated sample) |
| ZZZZZZ | Z114930.D | 10/07/16 | 17:45 | 08:02 | (unrelated sample) |
| ZZZZZZ | Z114931.D | 10/07/16 | 18:11 | 08:28 | (unrelated sample) |
| JC29041-1 | Z114932.D | 10/07/16 | 18:37 | 08:54 | (used for QC only; not part of job JC28902) |
| OP97582-MS | Z114933.D | 10/07/16 | 19:02 | 09:19 | Matrix Spike |
| OP97582-MSD | Z114934.D | 10/07/16 | 19:28 | 09:45 | Matrix Spike Duplicate |
| ZZZZZZ | Z114935.D | 10/07/16 | 19:54 | 10:11 | (unrelated sample) |
| ZZZZZZ | Z114936.D | 10/07/16 | 20:20 | 10:37 | (unrelated sample) |

# Instrument Performance Check (DFTPP)



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Sample:** | EZ5729-DFTPP | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | Z114913.D | **Injection Time:** | 09:43 |
| **Instrument ID:** | GCMSZ | | |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| ZZZZZZ | Z114937.D | 10/07/16 | 20:46 | 11:03 | (unrelated sample) |
| ZZZZZZ | Z114938.D | 10/07/16 | 21:12 | 11:29 | (unrelated sample) |
| ZZZZZZ | Z114939.D | 10/07/16 | 21:37 | 11:54 | (unrelated sample) |

# Semivolatile Internal Standard Area Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Check Std:** EM5462-CC5442 **Injection Date:** 10/07/16
**Lab File ID:** M128175.D **Injection Time:** 09:15
**Instrument ID:** GCMSM **Method:** SW846 8270D

| | IS 1 AREA | RT | IS 2 AREA | RT | IS 3 AREA | RT | IS 4 AREA | RT | IS 5 AREA | RT | IS 6 AREA | RT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Check Std | 1564755 | 4.81 | 6266363 | 5.97 | 4409431 | 8.33 | 8338826 | 10.96 | 9356188 | 16.12 | 9550995 | 18.75 |
| Upper Limit [a] | 3129510 | 5.31 | 12532726 | 6.47 | 8818862 | 8.83 | 16677652 | 11.46 | 18712376 | 16.62 | 19101990 | 19.25 |
| Lower Limit [b] | 782378 | 4.31 | 3133182 | 5.47 | 2204716 | 7.83 | 4169413 | 10.46 | 4678094 | 15.62 | 4775498 | 18.25 |
| **Lab Sample ID** | **IS 1 AREA** | **RT** | **IS 2 AREA** | **RT** | **IS 3 AREA** | **RT** | **IS 4 AREA** | **RT** | **IS 5 AREA** | **RT** | **IS 6 AREA** | **RT** |
| OP97337A-MB1 | 1443873 | 4.82 | 5498150 | 5.97 | 4067136 | 8.33 | 8184417 | 10.96 | 10374822 | 16.12 | 10489244 | 18.74 |
| OP97337A-BS1 | 1345553 | 4.81 | 5109687 | 5.97 | 3903056 | 8.33 | 7564553 | 10.96 | 9242235 | 16.12 | 9553446 | 18.75 |
| OP97337A-BSD | 1206467 | 4.82 | 4550809 | 5.97 | 3442851 | 8.33 | 6630668 | 10.96 | 8032963 | 16.12 | 8203376 | 18.74 |
| ZZZZZZ | 1339665 | 4.81 | 5221911 | 5.97 | 3761953 | 8.33 | 6801974 | 10.96 | 7987181 | 16.12 | 7785895 | 18.75 |
| OP97539-MB1 | 1069851 | 4.81 | 4338474 | 5.97 | 3161657 | 8.33 | 6311133 | 10.96 | 7825280 | 16.11 | 7732888 | 18.74 |
| JC28902-1 [c] | 1266058 | 4.82 | 4992434 | 5.97 | 3504143 | 8.33 | 6695282 | 10.96 | 7324592 | 16.12 | 6956599 | 18.74 |
| JC28902-1 | 1511417 | 4.81 | 5744728 | 5.97 | 3994359 | 8.33 | 7055287 | 10.96 | 6529861 | 16.12 | 6342825 | 18.75 |
| ZZZZZZ | 1123328 | 4.82 | 4350213 | 5.98 | 2927301 | 8.34 | 4867320 | 10.97 | 4606748* | 16.15 | 3988049* | 18.78 |

**IS 1** = 1,4-Dichlorobenzene-d4
**IS 2** = Naphthalene-d8
**IS 3** = Acenaphthene-D10
**IS 4** = Phenanthrene-d10
**IS 5** = Chrysene-d12
**IS 6** = Perylene-d12

(a) Upper Limit = + 100% of check standard area; Retention time + 0.5 minutes.
(b) Lower Limit = -50% of check standard area; Retention time -0.5 minutes.
(c) Confirmation run.

# Semivolatile Internal Standard Area Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Check Std:** EP4787-CC4769 **Injection Date:** 10/06/16
**Lab File ID:** P107974.D **Injection Time:** 10:09
**Instrument ID:** GCMSP **Method:** SW846 8270D

| | IS 1 AREA | RT | IS 2 AREA | RT | IS 3 AREA | RT | IS 4 AREA | RT | IS 5 AREA | RT | IS 6 AREA | RT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Check Std | 71259 | 4.46 | 257092 | 5.37 | 166163 | 6.71 | 303426 | 8.47 | 302776 | 13.61 | 283483 | 16.63 |
| Upper Limit [a] | 142518 | 4.96 | 514184 | 5.87 | 332326 | 7.21 | 606852 | 8.97 | 605552 | 14.11 | 566966 | 17.13 |
| Lower Limit [b] | 35630 | 3.96 | 128546 | 4.87 | 83082 | 6.21 | 151713 | 7.97 | 151388 | 13.11 | 141742 | 16.13 |
| **Lab Sample ID** | **IS 1 AREA** | **RT** | **IS 2 AREA** | **RT** | **IS 3 AREA** | **RT** | **IS 4 AREA** | **RT** | **IS 5 AREA** | **RT** | **IS 6 AREA** | **RT** |
| OP95519-MB1 | 76414 | 4.46 | 280288 | 5.37 | 168797 | 6.71 | 291849 | 8.47 | 276157 | 13.60 | 240391 | 16.63 |
| OP97539-MB1 | 60226 | 4.46 | 220032 | 5.37 | 135194 | 6.71 | 232261 | 8.47 | 225935 | 13.59 | 198577 | 16.62 |
| OP97539-BS1 | 54326 | 4.46 | 195164 | 5.37 | 124084 | 6.71 | 215327 | 8.47 | 205213 | 13.60 | 189146 | 16.63 |
| JC28910-1 | 59192 | 4.46 | 212254 | 5.37 | 130260 | 6.71 | 224493 | 8.47 | 214462 | 13.59 | 188062 | 16.62 |
| ZZZZZZ | 51850 | 4.46 | 195309 | 5.37 | 118936 | 6.71 | 207619 | 8.47 | 204760 | 13.59 | 178909 | 16.62 |
| OP97539-MS | 51844 | 4.46 | 188812 | 5.37 | 121906 | 6.71 | 209623 | 8.47 | 203761 | 13.60 | 185366 | 16.63 |
| OP97539-MSD | 55309 | 4.46 | 191919 | 5.37 | 121660 | 6.71 | 212805 | 8.47 | 207278 | 13.60 | 189179 | 16.63 |
| ZZZZZZ | 63770 | 4.45 | 226926 | 5.37 | 138117 | 6.71 | 238349 | 8.47 | 229133 | 13.59 | 202599 | 16.63 |
| ZZZZZZ | 58559 | 4.46 | 214602 | 5.37 | 132321 | 6.71 | 223664 | 8.47 | 218082 | 13.59 | 190491 | 16.62 |
| ZZZZZZ | 57175 | 4.45 | 209081 | 5.37 | 125888 | 6.71 | 212740 | 8.47 | 215167 | 13.59 | 186251 | 16.62 |
| ZZZZZZ | 57166 | 4.46 | 191618 | 5.37 | 129133 | 6.71 | 231521 | 8.48 | 251796 | 13.63 | 238740 | 16.68 |
| ZZZZZZ | 58093 | 4.46 | 203400 | 5.38 | 142093 | 6.72 | 239854 | 8.49 | 256783 | 13.67 | 241391 | 16.73 |
| ZZZZZZ | 68126 | 4.46 | 225395 | 5.38 | 138085 | 6.72 | 241402 | 8.49 | 250469 | 13.64 | 235910 | 16.69 |
| ZZZZZZ | 64550 | 4.46 | 224029 | 5.38 | 138304 | 6.71 | 225185 | 8.48 | 212555 | 13.63 | 199804 | 16.67 |

**IS 1** = 1,4-Dichlorobenzene-d4
**IS 2** = Naphthalene-d8
**IS 3** = Acenaphthene-D10
**IS 4** = Phenanthrene-d10
**IS 5** = Chrysene-d12
**IS 6** = Perylene-d12

(a) Upper Limit = + 100% of check standard area; Retention time + 0.5 minutes.
(b) Lower Limit = -50% of check standard area; Retention time -0.5 minutes.

# Semivolatile Internal Standard Area Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Check Std:** EZ5729-CC5695 **Injection Date:** 10/07/16
**Lab File ID:** Z114914.D **Injection Time:** 10:11
**Instrument ID:** GCMSZ **Method:** SW846 8270D

| | IS 1 AREA | RT | IS 2 AREA | RT | IS 3 AREA | RT | IS 4 AREA | RT | IS 5 AREA | RT | IS 6 AREA | RT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Check Std | 149398 | 4.38 | 601366 | 5.31 | 362486 | 6.60 | 647623 | 8.11 | 607929 | 11.84 | 623634 | 13.91 |
| Upper Limit [a] | 298796 | 4.88 | 1202732 | 5.81 | 724972 | 7.10 | 1295246 | 8.61 | 1215858 | 12.34 | 1247268 | 14.41 |
| Lower Limit [b] | 74699 | 3.88 | 300683 | 4.81 | 181243 | 6.10 | 323812 | 7.61 | 303965 | 11.34 | 311817 | 13.41 |

| Lab Sample ID | IS 1 AREA | RT | IS 2 AREA | RT | IS 3 AREA | RT | IS 4 AREA | RT | IS 5 AREA | RT | IS 6 AREA | RT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| OP97539-MB1 | 138512 | 4.38 | 581118 | 5.30 | 341107 | 6.60 | 565828 | 8.11 | 551004 | 11.83 | 530923 | 13.91 |
| ZZZZZZ | 155463 | 4.38 | 608829 | 5.30 | 358788 | 6.60 | 615167 | 8.10 | 590480 | 11.83 | 572563 | 13.91 |
| ZZZZZZ | 163845 | 4.38 | 654866 | 5.30 | 363793 | 6.60 | 609109 | 8.11 | 550235 | 11.83 | 514601 | 13.91 |
| ZZZZZZ | 139743 | 4.38 | 565459 | 5.30 | 315416 | 6.60 | 526461 | 8.11 | 486996 | 11.83 | 452345 | 13.91 |
| OP97072-MB1 | 107724 | 4.38 | 431814 | 5.30 | 249368 | 6.60 | 435183 | 8.11 | 405529 | 11.83 | 389973 | 13.91 |
| ZZZZZZ | 110121 | 4.38 | 454910 | 5.30 | 260870 | 6.60 | 452202 | 8.11 | 434611 | 11.83 | 421621 | 13.91 |
| OP97582-MB1 | 135422 | 4.38 | 557129 | 5.30 | 311685 | 6.60 | 523878 | 8.11 | 508122 | 11.83 | 486665 | 13.91 |
| OP97582-BS1 | 123265 | 4.38 | 486608 | 5.31 | 289308 | 6.60 | 500480 | 8.11 | 476904 | 11.84 | 500999 | 13.91 |
| ZZZZZZ | 124285 | 4.38 | 485273 | 5.30 | 255434 | 6.60 | 450808 | 8.11 | 458885 | 11.84 | 448402 | 13.92 |
| ZZZZZZ | 120214 | 4.38 | 415100 | 5.31 | 287075 | 6.63 | 518536 | 8.14 | 596638 | 11.84 | 569743 | 13.91 |
| ZZZZZZ | 150509 | 4.38 | 574839 | 5.30 | 293743 | 6.61 | 514540 | 8.12 | 550644 | 11.84 | 518092 | 13.91 |
| ZZZZZZ | 115829 | 4.39 | 388351 | 5.31 | 268845 | 6.64 | 530225 | 8.16 | 618022 | 11.86 | 597836 | 13.92 |
| JC29041-1 | 138087 | 4.38 | 442350 | 5.31 | 266919 | 6.63 | 520247 | 8.15 | 582900 | 11.86 | 558949 | 13.91 |
| OP97582-MS | 142343 | 4.38 | 473051 | 5.31 | 284591 | 6.64 | 552399 | 8.16 | 622142 | 11.86 | 613345 | 13.92 |
| OP97582-MSD | 137481 | 4.38 | 444968 | 5.31 | 270810 | 6.63 | 506060 | 8.15 | 551784 | 11.86 | 553747 | 13.92 |
| ZZZZZZ | 170595 | 4.38 | 661122 | 5.30 | 375612 | 6.60 | 630256 | 8.11 | 594861 | 11.85 | 579792 | 13.92 |
| ZZZZZZ | 176107 | 4.38 | 664746 | 5.30 | 384115 | 6.60 | 646129 | 8.11 | 602690 | 11.84 | 578549 | 13.92 |
| ZZZZZZ | 138501 | 4.38 | 534640 | 5.30 | 312408 | 6.61 | 508770 | 8.11 | 468210 | 11.86 | 462808 | 13.93 |
| ZZZZZZ | 157213 | 4.38 | 619851 | 5.31 | 366827 | 6.61 | 628365 | 8.12 | 562592 | 11.86 | 537657 | 13.93 |
| ZZZZZZ | 190302 | 4.38 | 737277 | 5.31 | 417548 | 6.61 | 696231 | 8.12 | 625443 | 11.85 | 591876 | 13.93 |

**IS 1** = 1,4-Dichlorobenzene-d4
**IS 2** = Naphthalene-d8
**IS 3** = Acenaphthene-D10
**IS 4** = Phenanthrene-d10
**IS 5** = Chrysene-d12
**IS 6** = Perylene-d12

(a) Upper Limit = + 100% of check standard area; Retention time + 0.5 minutes.
(b) Lower Limit = -50% of check standard area; Retention time -0.5 minutes.

# Semivolatile Surrogate Recovery Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Method:** SW846 8270D **Matrix:** SO

**Samples and QC shown here apply to the above method**

| Lab Sample ID | Lab File ID | S1 | S2 | S3 | S4 | S5 | S6 |
|---|---|---|---|---|---|---|---|
| JC28902-1 | M128187.D | 32 | 31 | 40 | 31 | 35* [a] | 36 |
| JC28902-1 | M128186.D | 53 | 53 | 72 | 62 | 56 | 59 |
| OP97539-BS1 | P107984.D | 83 | 77 | 85 | 91 | 93 | 96 |
| OP97539-MB1 | P107983.D | 74 | 76 | 83 | 87 | 88 | 90 |
| OP97539-MB1 | Z114917.D | 70 | 73 | 84 | 83 | 93 | 88 |
| OP97539-MB1 | M128185.D | 81 | 84 | 108 | 90 | 82 | 85 |
| OP97539-MS | P107985.D | 70 | 84 | 87 | 89 | 88 | 94 |
| OP97539-MSD | P107986.D | 74 | 70 | 83 | 86 | 90 | 92 |

| Surrogate Compounds | Recovery Limits |
|---|---|
| **S1** = 2-Fluorophenol | 30-106% |
| **S2** = Phenol-d5 | 30-106% |
| **S3** = 2,4,6-Tribromophenol | 24-140% |
| **S4** = Nitrobenzene-d5 | 26-122% |
| **S5** = 2-Fluorobiphenyl | 36-112% |
| **S6** = Terphenyl-d14 | 36-132% |

(a) Outside control limits due to matrix interference.

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5442-ICC5442
**Lab FileID:** M127789.D

Response Factor Report Instrument #1

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Tue Sep 27 14:20:13 2016
Response via : Initial Calibration

Calibration Files
2 =M127786.D 5 =M127790.D 100 =M127788.D 50 =M127789.D
1 =M127787.D 10 =M127791.D 80 =M127793.D 25 =M127792.D

| Compound | 2 | 5 | 100 | 50 | 1 | 10 | 80 | 25 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 1) I 1,4-Dichlorobenzene-d | ISTD | | | | | | | | | |
| 2) 1,4-Dioxane | 0.490 | 0.519 | 0.512 | 0.512 | 0.601 | 0.549 | 0.526 | 0.519 | 0.528 | 6.38 |
| 3) Pyridine | 1.095 | 1.177 | 1.218 | 1.182 | 0.958 | 1.238 | 1.224 | 1.272 | 1.170 | 8.61 |
| 4) N-Nitrosodim | 0.428 | 0.412 | 0.417 | 0.423 | 0.475 | 0.444 | 0.423 | 0.443 | 0.433 | 4.71 |
| 5) 2-Fluorophen | 1.139 | 1.264 | 1.218 | 1.291 | 1.212 | 1.354 | 1.277 | 1.330 | 1.261 | 5.51 |
| 6) Indene | 2.295 | 2.342 | 1.811 | 2.083 | 2.321 | 2.478 | 1.907 | 2.231 | 2.183 | 10.54 |
| 7) Cumene | 3.051 | 3.296 | 2.406 | 2.819 | 3.170 | 3.334 | 2.522 | 3.043 | 2.955 | 11.66 |
| 8) Phenol-d5 | 1.444 | 1.569 | 1.354 | 1.509 | 1.381 | 1.683 | 1.420 | 1.584 | 1.493 | 7.60 |
| 9) Phenol | 1.720 | 1.835 | 1.387 | 1.579 | 1.427 | 1.867 | 1.451 | 1.681 | 1.619 | 11.50 |
| 10) Aniline | 1.968 | 1.947 | | 1.405 | 1.856 | 1.913 | 1.181 | 1.597 | 1.695 | 18.18 |
| 11) bis(2-Chloro | 1.018 | 1.242 | 0.954 | 1.093 | 1.162 | 1.232 | 1.104 | 1.146 | 1.119 | 8.85 |
| 12) 2-Chlorophen | 1.376 | 1.395 | 1.140 | 1.260 | 1.391 | 1.429 | 1.202 | 1.323 | 1.314 | 7.87 |
| 13) Decane | 0.948 | 0.944 | 0.630 | 0.729 | 0.976 | 0.924 | 0.671 | 0.797 | 0.827 | 16.70 |
| 14) 1,3-Dichloro | 1.621 | 1.633 | 1.316 | 1.476 | 1.686 | 1.729 | 1.374 | 1.574 | 1.551 | 9.57 |
| 15) 1,4-Dichloro | 1.448 | 1.523 | 1.266 | 1.403 | 1.506 | 1.525 | 1.315 | 1.469 | 1.432 | 6.79 |
| 16) Benzyl alcoh | 0.626 | 0.697 | 0.706 | 0.777 | 0.574 | 0.799 | 0.747 | 0.792 | 0.715 | 11.35 |
| 17) 1,2-Dichloro | 1.551 | 1.581 | 1.192 | 1.356 | 1.658 | 1.653 | 1.254 | 1.464 | 1.464 | 12.22 |
| 18) Acetophenone | 1.757 | 1.816 | 1.419 | 1.589 | 1.704 | 1.878 | 1.494 | 1.728 | 1.673 | 9.50 |
| 19) 2-Methylphen | 1.119 | 1.256 | 1.037 | 1.125 | 1.196 | 1.267 | 1.097 | 1.195 | 1.161 | 6.92 |
| 20) 2,2'-oxybis( | 0.470 | 0.460 | 0.399 | 0.431 | 0.494 | 0.492 | 0.415 | 0.458 | 0.452 | 7.67 |
| 21) 3&4-Methylph | 1.205 | 1.299 | 1.131 | 1.207 | 1.153 | 1.325 | 1.193 | 1.241 | 1.219 | 5.48 |
| 22) n-Nitroso-di | 0.719 | 0.809 | 0.696 | 0.796 | 0.705 | 0.924 | 0.745 | 0.860 | 0.782 | 10.35 |
| 23) Hexachloroet | 0.491 | 0.503 | 0.438 | 0.471 | 0.489 | 0.508 | 0.449 | 0.493 | 0.480 | 5.25 |
| 24) I Naphthalene-d8 | ISTD | | | | | | | | | |
| 25) Nitrobenzene | 0.284 | 0.320 | 0.290 | 0.316 | 0.266 | 0.356 | 0.305 | 0.329 | 0.308 | 9.18 |
| 26) Nitrobenzene | 0.307 | 0.336 | 0.273 | 0.304 | 0.315 | 0.368 | 0.289 | 0.318 | 0.314 | 9.19 |
| 27) Quinoline | 0.732 | 0.806 | 0.707 | 0.765 | 0.711 | 0.885 | 0.740 | 0.811 | 0.770 | 7.93 |
| 28) Isophorone | 0.542 | 0.621 | 0.531 | 0.601 | 0.480 | 0.690 | 0.565 | 0.640 | 0.584 | 11.54 |
| 29) 2-Nitropheno | 0.151 | 0.164 | 0.173 | 0.186 | 0.134 | 0.201 | 0.182 | 0.194 | 0.173 | 12.93 |
| 30) 2,4-Dimethyl | 0.289 | 0.295 | 0.272 | 0.294 | 0.272 | 0.310 | 0.284 | 0.291 | 0.288 | 4.38 |
| 31) Benzoic acid | | 0.067 | 0.252 | 0.229 | | 0.120 | 0.253 | 0.185 | 0.184 | 41.35 |
| ---- Quadratic regression ---- Coefficient = 0.9990 | | | | | | | | | | |
| Response Ratio = -0.02898 + 0.24000 *A + 0.01062 *A^2 | | | | | | | | | | |
| 32) bis(2-Chloro | 0.353 | 0.382 | 0.309 | 0.349 | 0.361 | 0.411 | 0.334 | 0.372 | 0.359 | 8.58 |
| 33) 2,4-Dichloro | 0.300 | 0.312 | 0.275 | 0.309 | 0.289 | 0.355 | 0.290 | 0.331 | 0.308 | 8.29 |
| 34) 2,6-Dichloro | 0.286 | 0.296 | 0.262 | 0.289 | 0.284 | 0.333 | 0.273 | 0.300 | 0.290 | 7.30 |
| 35) 1,3,5-Trichl | 0.408 | 0.381 | 0.281 | 0.324 | 0.388 | 0.398 | 0.297 | 0.351 | 0.354 | 13.63 |
| 36) 1,2,4-Trichl | 0.364 | 0.359 | 0.281 | 0.314 | 0.359 | 0.374 | 0.292 | 0.334 | 0.334 | 10.60 |
| 37) 1,2,3-Trichl | 0.330 | 0.352 | 0.277 | 0.309 | 0.337 | 0.368 | 0.289 | 0.329 | 0.324 | 9.53 |
| 38) Naphthalene | 1.056 | 1.099 | 0.824 | 0.986 | 1.052 | 1.176 | 0.864 | 1.059 | 1.014 | 11.68 |
| 39) 4-Chloroanil | 0.423 | 0.485 | 0.331 | 0.397 | 0.458 | 0.507 | 0.351 | 0.448 | 0.425 | 14.66 |
| 40) 2,3-Dichloro | 0.400 | 0.411 | 0.310 | 0.352 | 0.369 | 0.440 | 0.325 | 0.383 | 0.374 | 11.73 |
| 41) Caprolactam | 0.088 | 0.108 | 0.121 | 0.126 | | 0.131 | 0.126 | 0.127 | 0.118 | 12.75 |
| 42) Hexachlorobu | 0.174 | 0.170 | 0.142 | 0.156 | 0.156 | 0.180 | 0.147 | 0.168 | 0.162 | 8.39 |

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** EM5442-ICC5442
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** M127789.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 43) | 4-Chloro-3-m | 0.287 | 0.288 | 0.271 | 0.294 | 0.246 | 0.327 | 0.282 | 0.308 | 0.288 | 8.33 |
| 44) | 2-Methylnaph | 0.740 | 0.722 | 0.541 | 0.619 | 0.682 | 0.769 | 0.566 | 0.676 | 0.664 | 12.37 |
| 45) | 1-Methylnaph | 0.835 | 0.835 | 0.654 | 0.747 | 0.816 | 0.902 | 0.676 | 0.791 | 0.782 | 10.79 |
| 46) | Dimethylnaph | 0.726 | 0.750 | 0.582 | 0.655 | 0.704 | 0.804 | 0.606 | 0.712 | 0.692 | 10.72 |
| 47) | I Acenaphthene-d10 | ---------- | ISTD | ---------- | | | | | | | |
| 48) | Hexachlorocy | 0.242 | 0.252 | 0.247 | 0.278 | 0.206 | 0.293 | 0.256 | 0.283 | 0.257 | 10.78 |
| 49) | 2,4,6-Trichl | 0.317 | 0.346 | 0.302 | 0.336 | 0.275 | 0.388 | 0.316 | 0.357 | 0.330 | 10.69 |
| 50) | 2,4,5-Trichl | 0.369 | 0.379 | 0.351 | 0.372 | 0.388 | 0.410 | 0.363 | 0.389 | 0.378 | 4.83 |
| 51) | 2-Fluorobiph | 1.461 | 1.470 | 1.085 | 1.255 | 1.420 | 1.508 | 1.161 | 1.352 | 1.339 | 11.67 |
| 52) | 2-Chloronaph | 1.196 | 1.216 | 0.905 | 1.033 | 1.252 | 1.211 | 0.956 | 1.110 | 1.110 | 11.83 |
| 53) | Biphenyl | 1.663 | 1.648 | 1.224 | 1.444 | 1.575 | 1.728 | 1.309 | 1.574 | 1.521 | 11.75 |
| 54) | 2-Nitroanili | 0.181 | 0.228 | 0.220 | 0.238 | 0.179 | 0.257 | 0.232 | 0.244 | 0.222 | 12.84 |
| 55) | Dimethylphth | 1.280 | 1.299 | 1.112 | 1.232 | 1.135 | 1.377 | 1.173 | 1.319 | 1.241 | 7.59 |
| 56) | Acenaphthyle | 1.778 | 1.982 | 1.505 | 1.764 | 1.704 | 2.088 | 1.587 | 1.921 | 1.791 | 11.04 |
| 57) | 2,6-Dinitrot | 0.183 | 0.236 | 0.276 | 0.298 | 0.171 | 0.302 | 0.294 | 0.298 | 0.257 | 20.95 |
| | ---- Quadratic regression ---- Coefficient = 0.9995 | | | | | | | | | | |
| | Response Ratio = -0.00842 + 0.33313 *A + -0.02048 *A^2 | | | | | | | | | | |
| 58) | 3-Nitroanili | 0.179 | 0.264 | 0.310 | 0.315 | | 0.302 | 0.324 | 0.311 | 0.287 | 17.86 |
| 59) | Acenaphthene | 1.219 | 1.245 | 0.975 | 1.119 | 1.235 | 1.334 | 1.030 | 1.203 | 1.170 | 10.24 |
| 60) | 2,4-Dinitrop | 0.059 | 0.076 | 0.184 | 0.180 | | 0.133 | 0.185 | 0.165 | 0.140 | 37.97 |
| | ---- Quadratic regression ---- Coefficient = 0.9997 | | | | | | | | | | |
| | Response Ratio = -0.02345 + 0.18780 *A + 0.00040 *A^2 | | | | | | | | | | |
| 61) | 4-Nitropheno | 0.098 | 0.104 | 0.136 | 0.135 | | 0.133 | 0.136 | 0.132 | 0.125 | 13.15 |
| 62) | Dibenzofuran | 1.720 | 1.773 | 1.301 | 1.504 | 1.687 | 1.840 | 1.359 | 1.636 | 1.602 | 12.20 |
| 63) | 2,4-Dinitrot | 0.237 | 0.314 | 0.343 | 0.361 | 0.188 | 0.375 | 0.358 | 0.366 | 0.318 | 21.58 |
| | ---- Quadratic regression ---- Coefficient = 0.9998 | | | | | | | | | | |
| | Response Ratio = -0.00735 + 0.39457 *A + -0.01885 *A^2 | | | | | | | | | | |
| 64) | 2,3,4,6-Tetr | 0.246 | 0.268 | 0.276 | 0.297 | 0.216 | 0.293 | 0.284 | 0.297 | 0.272 | 10.44 |
| 65) | Diethylphtha | 1.123 | 1.297 | 1.047 | 1.179 | 1.078 | 1.396 | 1.103 | 1.278 | 1.188 | 10.39 |
| 66) | Fluorene | 1.427 | 1.455 | 1.103 | 1.256 | 1.425 | 1.522 | 1.159 | 1.354 | 1.338 | 11.21 |
| 67) | 4-Chlorophen | 0.671 | 0.662 | 0.499 | 0.560 | 0.674 | 0.659 | 0.517 | 0.582 | 0.603 | 12.05 |
| 68) | 4-Nitroanili | 0.212 | 0.304 | 0.322 | 0.342 | | 0.372 | 0.332 | 0.357 | 0.320 | 16.37 |
| 69) | I Phenanthrene-d10 | ---------- | ISTD | ---------- | | | | | | | |
| 70) | 4,6-Dinitro- | 0.045 | 0.063 | 0.139 | 0.135 | | 0.106 | 0.142 | 0.126 | 0.108 | 36.34 |
| | ---- Quadratic regression ---- Coefficient = 0.9995 | | | | | | | | | | |
| | Response Ratio = -0.00853 + 0.14351 *A + -0.00006 *A^2 | | | | | | | | | | |
| 71) | n-Nitrosodip | 0.555 | 0.585 | 0.487 | 0.551 | 0.520 | 0.647 | 0.511 | 0.590 | 0.556 | 9.24 |
| 72) | 1,2-Diphenyl | 0.515 | 0.613 | 0.494 | 0.561 | 0.485 | 0.666 | 0.527 | 0.608 | 0.559 | 11.60 |
| 73) | 2,4,6-Tribro | 0.093 | 0.095 | 0.114 | 0.123 | 0.088 | 0.121 | 0.117 | 0.123 | 0.109 | 13.44 |
| 74) | 4-Bromopheny | 0.217 | 0.227 | 0.190 | 0.215 | 0.237 | 0.251 | 0.198 | 0.228 | 0.220 | 9.13 |
| 75) | Hexachlorobe | 0.264 | 0.266 | 0.210 | 0.236 | 0.271 | 0.275 | 0.218 | 0.249 | 0.248 | 10.01 |
| 76) | Pentachlorop | 0.091 | 0.089 | 0.130 | 0.139 | | 0.129 | 0.133 | 0.138 | 0.121 | 17.81 |
| 77) | Phenanthrene | 1.168 | 1.198 | 0.888 | 1.042 | 1.166 | 1.243 | 0.935 | 1.118 | 1.095 | 11.69 |
| 78) | Anthracene | 1.086 | 1.171 | 0.918 | 1.082 | 0.974 | 1.298 | 0.965 | 1.171 | 1.083 | 11.82 |
| 79) | Carbazole | 1.095 | 1.227 | 0.952 | 1.108 | 1.025 | 1.316 | 1.007 | 1.195 | 1.116 | 11.04 |
| 80) | Di-n-butylph | 0.842 | 1.160 | 1.008 | 1.227 | | 1.399 | 1.085 | 1.318 | 1.148 | 16.49 |
| 81) | Fluoranthene | 1.186 | 1.324 | 1.017 | 1.184 | 1.139 | 1.418 | 1.062 | 1.260 | 1.199 | 11.08 |
| 82) | Octadecane | 0.313 | 0.373 | 0.285 | 0.336 | 0.311 | 0.408 | 0.309 | 0.364 | 0.337 | 12.21 |
| 83) | I Chrysene-d12 | ---------- | ISTD | ---------- | | | | | | | |
| 84) | Pyrene | 1.265 | 1.364 | 1.079 | 1.241 | 1.176 | 1.451 | 1.160 | 1.328 | 1.258 | 9.61 |
| 85) | Terphenyl-d1 | 0.862 | 0.877 | 0.759 | 0.856 | 0.792 | 0.972 | 0.823 | 0.911 | 0.857 | 7.84 |
| 86) | Butylbenzylp | 0.287 | 0.421 | 0.539 | 0.581 | 0.248 | 0.570 | 0.580 | 0.592 | 0.477 | 29.51 |
| | ---- Quadratic regression ---- Coefficient = 0.9993 | | | | | | | | | | |

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** EM5442-ICC5442
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** M127789.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

```
              Response Ratio = -0.02107 + 0.66311 *A + -0.04377 *A^2

 87) Benzo[a]anth 0.966 1.074 1.006 1.111 0.978 1.194 1.068 1.152 1.069   7.68
 88) 3,3'-Dichlor 0.279 0.358 0.407 0.433 0.257 0.417 0.423 0.425 0.375  18.67
 89) Chrysene     1.142 1.159 0.938 1.059 1.097 1.215 0.998 1.127 1.092   8.26
 90) bis(2-Ethylh 0.367 0.589 0.708 0.786 0.309 0.778 0.763 0.795 0.637  30.88
            ---- Quadratic regression ----  Coefficient =  0.9995
              Response Ratio = -0.02900 + 0.90693 *A + -0.07233 *A^2


 91) I   Perylene-d12          -----------------ISTD----------------------
 92) Di-n-octylph 0.583 0.952 1.039 1.274 0.516 1.314 1.148 1.324 1.019  31.26
            ---- Quadratic regression ----  Coefficient =  0.9997
              Response Ratio = -0.05099 + 1.55963 *A + -0.19828 *A^2

 93) Benzo[b]fluo 1.164 1.252 1.010 1.099 1.126 1.308 1.064 1.188 1.151   8.52
 94) Benzo[k]fluo 1.143 1.179 0.905 1.101 1.126 1.274 0.960 1.182 1.109  10.91
 95) Benzo[a]pyre 0.901 1.068 0.918 1.041 0.849 1.179 0.966 1.095 1.002  11.19
 96) Indeno[1,2,3 0.958 1.105 1.080 1.163 0.895 1.229 1.107 1.150 1.086  10.09
 97) Dibenz(a,h)a 0.824 0.974 0.926 1.011 0.805 1.077 0.957 1.034 0.951  10.15
 98) Dibenz[a,h]a 1.073 1.192 1.033 1.165 1.094 1.273 1.072 1.190 1.137   7.13
 99) 7,12-Dimethy 0.418 0.487 0.466 0.519 0.381 0.548 0.485 0.532 0.479  11.88
100) Benzo[g,h,i] 1.094 1.172 1.082 1.160 1.045 1.269 1.101 1.180 1.138   6.26

 (#) = Out of Range  ###  Number of calibration levels exceeded format  ###

          MM5442.M          Tue Sep 27 14:20:44 2016   MSM
```

7.1.1

7

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICC5443
**Lab FileID:** M127802.D

Response Factor Report Instrument #1

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Tue Sep 27 14:28:37 2016
Response via : Initial Calibration

Calibration Files
2 =Copy of M127800.D 5 =M127799.D 100 =M127795.D 50 =M127802.D
1 =Copy of M127801.D 10 =M127798.D 80 =M127796.D 25 =M127797.D

| Compound | 2 | 5 | 100 | 50 | 1 | 10 | 80 | 25 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 101) I 1,4-Dichlorobenzene-d | ISTD | | | | | | | | | |
| 102) Benzaldehyde | 1.158 | 1.226 | 0.666 | 0.765 | 1.222 | 1.139 | 0.716 | 1.033 | 0.991 | 23.90 |
| ---- Quadratic regression ---- Coefficient = 0.9959 | | | | | | | | | | |
| Response Ratio = 0.03626 + 0.92101 *A + -0.10988 *A^2 | | | | | | | | | | |
| 103) I Acenaphthene-d10a | ISTD | | | | | | | | | |
| 104) 1,2,4,5-Tetr | 0.679 | 0.671 | 0.468 | 0.472 | 0.681 | 0.585 | 0.479 | 0.544 | 0.572 | 16.67 |
| 105) Atrazine | 0.142 | 0.196 | 0.187 | 0.170 | 0.129 | 0.197 | 0.189 | 0.199 | 0.176 | 15.28 |
| 106) I Chrysene-d12a | ISTD | | | | | | | | | |
| 107) Benzidine | 0.653 | 0.497 | 0.575 | | 0.765 | 0.472 | 0.700 | 0.610 | | 19.01 |
| 108) 1-chloroocta | 0.237 | 0.284 | 0.220 | 0.235 | 0.210 | 0.278 | 0.222 | 0.257 | 0.243 | 11.28 |
| 109) I Phenanthrene-d10a | ISTD | | | | | | | | | |
| 110) o-terphenyl | 0.723 | 0.727 | 0.505 | 0.523 | 0.718 | 0.665 | 0.522 | 0.600 | 0.623 | 15.62 |
| 111) I Naphthalene-d8a | ISTD | | | | | | | | | |
| 112) Hydroquinone | 0.241 | 0.312 | 0.359 | 0.326 | | 0.359 | 0.355 | 0.353 | 0.329 | 13.00 |

(#) = Out of Range ### Number of calibration levels exceeded format ###

MM5442.M Tue Sep 27 14:29:38 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5442
**Lab FileID:** M127803.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127803.D Vial: 10
Acq On : 24 Sep 2016 4:52 pm Operator: ariellec
Sample : icv5442-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Tue Sep 27 14:34:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 118 | 0.00 | 4.92 |
| 9 | t | Phenol | 1.619 | 1.518 | 6.2 | 113 | 0.00 | 4.69 |
| 12 | t | 2-Chlorophenol | 1.314 | 1.315 | -0.1 | 123 | 0.00 | 4.78 |
| 19 | t | 2-Methylphenol | 1.161 | 1.148 | 1.1 | 120 | 0.00 | 5.15 |
| 21 | t | 3&4-Methylphenol | 1.219 | 1.188 | 2.5 | 116 | 0.00 | 5.28 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 111 | 0.00 | 6.10 |
| 29 | t | 2-Nitrophenol | 0.173 | 0.206 | -19.1 | 123 | 0.00 | 5.71 |
| 30 | t | 2,4-Dimethylphenol | 0.288 | 0.306 | -6.3 | 116 | 0.00 | 5.76 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 31 | t | Benzoic acid | 50.000 | 40.264 | 19.5 | 87 | 0.02 | 5.90 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 33 | t | 2,4-Dichlorophenol | 0.308 | 0.312 | -1.3 | 112 | 0.00 | 5.96 |
| 34 | t | 2,6-Dichlorophenol | 0.290 | 0.303 | -4.5 | 117 | 0.00 | 6.20 |
| 43 | t | 4-Chloro-3-methylphenol | 0.288 | 0.277 | 3.8 | 104 | 0.00 | 6.80 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 108 | 0.00 | 8.48 |
| 49 | t | 2,4,6-Trichlorophenol | 0.330 | 0.367 | -11.2 | 118 | 0.00 | 7.35 |
| 50 | t | 2,4,5-Trichlorophenol | 0.378 | 0.367 | 2.9 | 107 | 0.00 | 7.41 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 60 | t | 2,4-Dinitrophenol | 100.000 | 41.818 | 16.4 | 94 | 0.00 | 8.63 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 61 | t | 4-Nitrophenol | 0.125 | 0.135 | -8.0 | 108 | 0.00 | 8.87 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 64 | t | 2,3,4,6-Tetrachlorophenol | 0.272 | 0.288 | -5.9 | 105 | 0.00 | 9.07 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 104 | 0.00 | 11.12 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 70 | t | 4,6-Dinitro-2-methylpheno | 50.000 | 46.919 | 6.2 | 98 | 0.00 | 9.55 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 76 | t | Pentachlorophenol | 0.121 | 0.136 | -12.4 | 100 | 0.00 | 10.82 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Tue Sep 27 14:38:22 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5442
**Lab FileID:** M127804.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127804.D Vial: 11
Acq On : 24 Sep 2016 5:20 pm Operator: ariellec
Sample : icv5442-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Tue Sep 27 14:34:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 96 | 0.00 | 4.92 |
| 3 | t | Pyridine | 1.170 | 1.171 | -0.1 | 95 | 0.05 | 2.95 |
| 10 | t | Aniline | 1.695 | 1.728 | -1.9 | 118 | 0.00 | 4.69 |
| 16 | t | Benzyl alcohol | 0.715 | 0.829 | -15.9 | 102 | 0.00 | 5.05 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 103 | 0.00 | 6.10 |
| 39 | t | 4-Chloroaniline | 0.425 | 0.349 | 17.9 | 90 | 0.00 | 6.20 |
| 44 | t | 2-Methylnaphthalene | 0.664 | 0.560 | 15.7 | 93 | 0.00 | 6.94 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 100 | 0.00 | 8.48 |
| 54 | t | 2-Nitroaniline | 0.222 | 0.232 | -4.5 | 97 | 0.00 | 7.83 |
| 58 | t | 3-Nitroaniline | 0.287 | 0.272 | 5.2 | 86 | 0.00 | 8.49 |
| 62 | t | Dibenzofuran | 1.602 | 1.539 | 3.9 | 102 | 0.00 | 8.83 |
| 68 | t | 4-Nitroaniline | 0.320 | 0.336 | -5.0 | 98 | 0.00 | 9.56 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 103 | 0.00 | 11.12 |
| 79 | t | Carbazole | 1.116 | 1.031 | 7.6 | 96 | 0.00 | 11.64 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Tue Sep 27 14:41:12 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5442
**Lab FileID:** M127805.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127805.D Vial: 12
Acq On : 24 Sep 2016 5:48 pm Operator: ariellec
Sample : icv5442-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 125 | 0.00 | 4.92 |
| 5 | S | 2-Fluorophenol | 1.261 | 1.038 | 17.7 | 101 | 0.00 | 3.97 |
| 8 | S | Phenol-d5 | 1.493 | 1.240 | 16.9 | 103 | 0.00 | 4.68 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 121 | 0.00 | 6.10 |
| 25 | S | Nitrobenzene-d5 | 0.308 | 0.281 | 8.8 | 108 | 0.00 | 5.40 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 115 | 0.00 | 8.48 |
| 51 | S | 2-Fluorobiphenyl | 1.339 | 1.197 | 10.6 | 110 | 0.00 | 7.45 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 113 | -0.01 | 11.12 |
| 73 | S | 2,4,6-Tribromophenol | 0.109 | 0.101 | 7.3 | 93 | -0.01 | 9.85 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 113 | -0.02 | 16.28 |
| 85 | S | Terphenyl-d14 | 0.857 | 0.768 | 10.4 | 101 | -0.01 | 14.27 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Mon Sep 26 11:14:45 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5442
**Lab FileID:** M127806.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127806.D Vial: 13
Acq On : 24 Sep 2016 6:16 pm Operator: ariellec
Sample : icv5442-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 99 | 0.00 | 4.92 |
| 4 | t | N-Nitrosodimethylamine | 0.433 | 0.386 | 10.9 | 91 | 0.00 | 2.84 |
| 11 | t | bis(2-Chloroethyl)ether | 1.119 | 1.160 | -3.7 | 105 | 0.00 | 4.71 |
| 14 | t | 1,3-Dichlorobenzene | 1.551 | 1.498 | 3.4 | 101 | 0.00 | 4.87 |
| 15 | t | 1,4-Dichlorobenzene | 1.432 | 1.381 | 3.6 | 98 | 0.00 | 4.93 |
| 17 | t | 1,2-Dichlorobenzene | 1.464 | 1.423 | 2.8 | 104 | 0.00 | 5.07 |
| 20 | t | 2,2'-oxybis(1-Chloropropa | 0.452 | 0.427 | 5.5 | 98 | 0.00 | 5.13 |
| 22 | t | n-Nitroso-di-n-propylamin | 0.782 | 0.743 | 5.0 | 93 | -0.01 | 5.25 |
| 23 | t | Hexachloroethane | 0.480 | 0.478 | 0.4 | 101 | 0.00 | 5.35 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 6.10 |
| 26 | t | Nitrobenzene | 0.314 | 0.298 | 5.1 | 95 | 0.00 | 5.42 |
| 28 | t | Isophorone | 0.584 | 0.542 | 7.2 | 87 | -0.02 | 5.62 |
| 32 | t | bis(2-Chloroethoxy)methan | 0.359 | 0.357 | 0.6 | 99 | 0.00 | 5.83 |
| 36 | t | 1,2,4-Trichlorobenzene | 0.334 | 0.329 | 1.5 | 101 | 0.00 | 6.03 |
| 38 | t | Naphthalene | 1.014 | 0.935 | 7.8 | 92 | 0.00 | 6.12 |
| 42 | t | Hexachlorobutadiene | 0.162 | 0.165 | -1.9 | 103 | 0.00 | 6.25 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 95 | 0.00 | 8.48 |
| 48 | t | Hexachlorocyclopentadiene | 0.257 | 0.270 | -5.1 | 92 | 0.00 | 7.16 |
| 52 | t | 2-Chloronaphthalene | 1.110 | 1.109 | 0.1 | 102 | -0.01 | 7.62 |
| 55 | t | Dimethylphthalate | 1.241 | 1.191 | 4.0 | 91 | -0.01 | 8.09 |
| 56 | t | Acenaphthylene | 1.791 | 1.621 | 9.5 | 87 | -0.01 | 8.25 |
| | | ---------- | True | Calc. | % Drift | | ---------- | |
| 57 | t | 2,6-Dinitrotoluene | 50.000 | 43.780 | 12.4 | 84 | -0.01 | 8.19 |
| | | ---------- | AvgRF | CCRF | % Dev | | ---------- | |
| 59 | t | Acenaphthene | 1.170 | 1.065 | 9.0 | 90 | 0.00 | 8.54 |
| | | ---------- | True | Calc. | % Drift | | ---------- | |
| 63 | t | 2,4-Dinitrotoluene | 50.000 | 47.402 | 5.2 | 91 | -0.01 | 8.85 |
| | | ---------- | AvgRF | CCRF | % Dev | | ---------- | |
| 65 | t | Diethylphthalate | 1.188 | 1.120 | 5.7 | 90 | -0.01 | 9.28 |
| 66 | t | Fluorene | 1.338 | 1.213 | 9.3 | 91 | 0.00 | 9.41 |
| 67 | t | 4-Chlorophenyl-phenylethe | 0.603 | 0.556 | 7.8 | 94 | 0.00 | 9.44 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 95 | -0.01 | 11.12 |
| 71 | t | n-Nitrosodiphenylamine | 0.556 | 0.502 | 9.7 | 87 | -0.02 | 9.66 |
| 72 | t | 1,2-Diphenylhydrazine | 0.559 | 0.523 | 6.4 | 89 | 0.00 | 9.72 |
| 74 | t | 4-Bromophenyl-phenylether | 0.220 | 0.210 | 4.5 | 94 | -0.01 | 10.31 |

# Initial Calibration Verification



**Job Number:** JC28902 **Sample:** EM5443-ICV5442
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** M127806.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 75 | t | Hexachlorobenzene | 0.248 | 0.235 | 5.2 | 95 | 0.00 | 10.40 |
| 77 | t | Phenanthrene | 1.095 | 0.984 | 10.1 | 90 | -0.01 | 11.17 |
| 78 | t | Anthracene | 1.083 | 0.987 | 8.9 | 87 | -0.01 | 11.26 |
| 80 | t | Di-n-butylphthalate | 1.148 | 1.091 | 5.0 | 85 | 0.00 | 12.36 |
| 81 | t | Fluoranthene | 1.199 | 1.084 | 9.6 | 87 | -0.01 | 13.45 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 91 | -0.01 | 16.28 |
| 84 | t | Pyrene | 1.258 | 1.196 | 4.9 | 87 | -0.01 | 13.89 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 86 | t | Butylbenzylphthalate | 50.000 | 44.631 | 10.7 | 83 | 0.00 | 15.31 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 87 | t | Benzo[a]anthracene | 1.069 | 1.040 | 2.7 | 85 | 0.00 | 16.26 |
| 89 | t | Chrysene | 1.092 | 0.958 | 12.3 | 82 | -0.01 | 16.34 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 90 | t | bis(2-Ethylhexyl)phthalat | 50.000 | 43.409 | 13.2 | 80 | 0.00 | 16.47 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 89 | -0.01 | 18.90 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 92 | t | Di-n-octylphthalate | 50.000 | 44.959 | 10.1 | 81 | 0.00 | 17.68 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 93 | t | Benzo[b]fluoranthene | 1.151 | 1.067 | 7.3 | 87 | -0.01 | 18.26 |
| 94 | t | Benzo[k]fluoranthene | 1.109 | 1.064 | 4.1 | 86 | -0.02 | 18.30 |
| 95 | t | Benzo[a]pyrene | 1.002 | 1.013 | -1.1 | 87 | -0.02 | 18.80 |
| 96 | t | Indeno[1,2,3-cd]pyrene | 1.086 | 1.042 | 4.1 | 80 | -0.02 | 20.67 |
| 98 | t | Dibenz[a,h]anthracene | 1.137 | 1.087 | 4.4 | 83 | -0.02 | 20.71 |
| 100 | t | Benzo[g,h,i]perylene | 1.138 | 1.094 | 3.9 | 84 | -0.03 | 21.17 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Mon Sep 26 11:14:47 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5443
**Lab FileID:** M127806A.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127806a.D Vial: 13
Acq On : 24 Sep 2016 6:16 pm Operator: ariellec
Sample : icv5443-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| | | AvgRF | CCRF | % Dev | | | |
| 103 I | Acenaphthene-d10a | 1.000 | 1.000 | 0.0 | 85 | 0.00 | 8.48 |
| 104 I | 1,2,4,5-Tetrachlorobenzen | 0.572 | 0.518 | 9.4 | 94 | 0.00 | 7.16 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Mon Sep 26 11:14:49 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5442
**Lab FileID:** M127808.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127808.D Vial: 15
Acq On : 24 Sep 2016 7:13 pm Operator: ariellec
Sample : icv5442-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 105 | -0.02 | 16.28 |
| 88 | t | 3,3'-Dichlorobenzidine | 0.375 | 0.394 | -5.1 | 95 | 0.00 | 16.32 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Mon Sep 26 11:19:00 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5443-ICV5443
**Lab FileID:** M127808A.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127808a.D Vial: 15
Acq On : 24 Sep 2016 7:13 pm Operator: ariellec
Sample : icv5443-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Tue Sep 27 14:28:37 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 106 I | Chrysene-d12a | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 16.28 |
| 107 t | Benzidine | 0.610 | 0.785 | -28.7 | 133 | 0.00 | 13.83 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Tue Sep 27 14:33:41 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5443-ICV5443
**Lab FileID:** M127809.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\em5443\M127809.D Vial: 16
Acq On : 24 Sep 2016 7:41 pm Operator: ariellec
Sample : icv5443-50 Inst : Instrument #1
Misc : op96678,em5443 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 111 I | Naphthalene-d8a | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 6.09 |
| 112 | Hydroquinone | 0.329 | 0.370 | -12.5 | 111 | 0.00 | 6.63 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Mon Sep 26 11:14:53 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5444-ICV5442
**Lab FileID:** M127816.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\EM5444\M127816.D Vial: 2
Acq On : 26 Sep 2016 1:14 pm Operator: chriss2
Sample : icv5442-50 Inst : Instrument #1
Misc : op96678,em5444 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 121 | -0.02 | 4.90 |
| 2 | t | 1,4-Dioxane | 0.528 | 0.373 | 29.4 | 88 | -0.02 | 2.51 |
| 6 | t | Indene | 2.183 | 1.843 | 15.6 | 107 | -0.03 | 5.11 |
| 7 | t | Cumene | 2.955 | 2.164 | 26.8 | 93 | -0.02 | 4.28 |
| 13 | t | Decane | 0.827 | 0.599 | 27.6 | 99 | -0.02 | 4.74 |
| 18 | t | Acetophenone | 1.673 | 1.335 | 20.2 | 101 | -0.03 | 5.23 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 127 | -0.03 | 6.07 |
| 27 | t | Quinoline | 0.770 | 0.569 | 26.1 | 94 | -0.06 | 6.48 |
| 40 | t | 2,3-Dichloroaniline | 0.374 | 0.305 | 18.4 | 110 | -0.03 | 7.33 |
| 41 | t | Caprolactam | 0.118 | 0.085 | 28.0 | 85 | -0.08 | 6.57 |
| 45 | t | 1-Methylnaphthalene | 0.782 | 0.553 | 29.3 | 94 | -0.03 | 7.05 |
| 46 | t | Dimethylnaphthalene | 0.692 | 0.550 | 20.5 | 107 | -0.03 | 7.79 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 119 | -0.03 | 8.45 |
| 53 | t | Biphenyl | 1.521 | 1.275 | 16.2 | 105 | -0.04 | 7.56 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 121 | -0.04 | 11.09 |
| 82 | t | Octadecane | 0.337 | 0.257 | 23.7 | 93 | -0.03 | 10.97 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 117 | -0.04 | 18.87 |
| 99 | t | 7,12-Dimethylbenz(a)anthr | 0.479 | 0.411 | 14.2 | 93 | -0.06 | 18.22 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Tue Sep 27 09:34:14 2016 MSM

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EM5444-ICV5443
**Lab FileID:** M127816A.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\EM5444\M127816a.D Vial: 2
Acq On : 26 Sep 2016 1:14 pm Operator: chriss2
Sample : icv5443-50 Inst : Instrument #1
Misc : op96678,em5444 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Mon Sep 26 10:51:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 101 I | 1,4-Dichlorobenzene-d4a | 1.000 | 1.000 | 0.0 | 105 | -0.02 | 4.90 |
| | ---------- True | Calc. | % Drift | ---------- | | | |
| 102 t | Benzaldehyde | 50.000 | 44.863 | 10.3 | 102 | -0.02 | 4.57 |
| | ---------- AvgRF | CCRF | % Dev | ---------- | | | |
| 103 I | Acenaphthene-d10a | 1.000 | 1.000 | 0.0 | 108 | -0.03 | 8.45 |
| 105 t | Atrazine | 0.176 | 0.189 | -7.4 | 120 | -0.03 | 10.68 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127802.D MM5442.M Tue Sep 27 09:34:16 2016 MSM

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5462-CC5442
**Lab FileID:** M128175.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\EM5462\M128175.D Vial: 2
Acq On : 7 Oct 2016 9:15 am Operator: chriss2
Sample : cc5442-25 Inst : Instrument #1
Misc : op96678,em5462 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Fri Oct 07 09:45:00 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 89 | 0.00 | 4.81 |
| 2 | t | 1,4-Dioxane | 0.528 | 0.414 | 21.6# | 71 | 0.02 | 2.42 |
| 3 | t | Pyridine | 1.170 | 1.085 | 7.3 | 76 | 0.00 | 2.78 |
| 4 | t | N-Nitrosodimethylamine | 0.433 | 0.458 | -5.8 | 92 | 0.02 | 2.73 |
| 5 | S | 2-Fluorophenol | 1.261 | 1.139 | 9.7 | 76 | 0.01 | 3.90 |
| 6 | t | Indene | 2.183 | 2.132 | 2.3 | 85 | 0.00 | 5.02 |
| 7 | t | Cumene | 2.955 | 2.669 | 9.7 | 78 | 0.00 | 4.21 |
| 8 | S | Phenol-d5 | 1.493 | 1.407 | 5.8 | 79 | 0.01 | 4.61 |
| 9 | t | Phenol | 1.619 | 1.597 | 1.4 | 85 | 0.02 | 4.62 |
| 10 | t | Aniline | 1.695 | 1.347 | 20.5# | 75 | 0.00 | 4.59 |
| 11 | t | bis(2-Chloroethyl)ether | 1.119 | 1.203 | -7.5 | 93 | 0.00 | 4.61 |
| 12 | t | 2-Chlorophenol | 1.314 | 1.332 | -1.4 | 90 | 0.01 | 4.69 |
| 13 | t | Decane | 0.827 | 0.790 | 4.5 | 88 | 0.00 | 4.66 |
| 14 | t | 1,3-Dichlorobenzene | 1.551 | 1.439 | 7.2 | 81 | 0.00 | 4.77 |
| 15 | t | 1,4-Dichlorobenzene | 1.432 | 1.375 | 4.0 | 83 | 0.00 | 4.83 |
| 16 | t | Benzyl alcohol | 0.715 | 0.808 | -13.0 | 91 | 0.00 | 4.95 |
| 17 | t | 1,2-Dichlorobenzene | 1.464 | 1.430 | 2.3 | 87 | 0.00 | 4.96 |
| 18 | t | Acetophenone | 1.673 | 1.726 | -3.2 | 89 | 0.00 | 5.15 |
| 19 | t | 2-Methylphenol | 1.161 | 1.170 | -0.8 | 87 | 0.03 | 5.07 |
| 20 | t | 2,2'-oxybis(1-Chloropropa | 0.452 | 0.449 | 0.7 | 87 | 0.00 | 5.03 |
| 21 | t | 3&4-Methylphenol | 1.219 | 1.273 | -4.4 | 91 | 0.03 | 5.20 |
| 22 | t | n-Nitroso-di-n-propylamin | 0.782 | 0.877 | -12.1 | 91 | 0.00 | 5.14 |
| 23 | t | Hexachloroethane | 0.480 | 0.492 | -2.5 | 89 | 0.00 | 5.24 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 5.97 |
| 25 | S | Nitrobenzene-d5 | 0.308 | 0.306 | 0.6 | 91 | 0.00 | 5.29 |
| 26 | t | Nitrobenzene | 0.314 | 0.308 | 1.9 | 94 | 0.00 | 5.31 |
| 27 | t | Quinoline | 0.770 | 0.806 | -4.7 | 97 | 0.02 | 6.38 |
| 28 | t | Isophorone | 0.584 | 0.615 | -5.3 | 93 | 0.00 | 5.51 |
| 29 | t | 2-Nitrophenol | 0.173 | 0.202 | -16.8 | 101 | 0.00 | 5.60 |
| 30 | t | 2,4-Dimethylphenol | 0.288 | 0.273 | 5.2 | 91 | 0.01 | 5.66 |
| | | | True | Calc. | % Drift | | | |
| 31 | t | Benzoic acid | 25.000 | 27.437 | -9.7 | 118 | 0.03 | 5.80 |
| | | | AvgRF | CCRF | % Dev | | | |
| 32 | t | bis(2-Chloroethoxy)methan | 0.359 | 0.356 | 0.8 | 93 | 0.00 | 5.71 |
| 33 | t | 2,4-Dichlorophenol | 0.308 | 0.314 | -1.9 | 92 | 0.02 | 5.86 |
| 34 | t | 2,6-Dichlorophenol | 0.290 | 0.301 | -3.8 | 97 | 0.00 | 6.09 |
| 35 | t | 1,3,5-Trichlorobenzene | 0.354 | 0.339 | 4.2 | 94 | 0.00 | 5.59 |
| 36 | t | 1,2,4-Trichlorobenzene | 0.334 | 0.321 | 3.9 | 93 | 0.00 | 5.91 |
| 37 | t | 1,2,3-Trichlorobenzene | 0.324 | 0.327 | -0.9 | 97 | 0.00 | 6.16 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EM5462-CC5442
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** M128175.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 38 | t | Naphthalene | 1.014 | 0.980 | 3.4 | 90 | 0.00 | 6.00 |
| 39 | t | 4-Chloroaniline | 0.425 | 0.423 | 0.5 | 92 | 0.00 | 6.08 |
| 40 | t | 2,3-Dichloroaniline | 0.374 | 0.412 | -10.2 | 105 | 0.00 | 7.22 |
| 41 | t | Caprolactam | 0.118 | 0.146 | -23.7# | 111 | 0.02 | 6.50 |
| 42 | t | Hexachlorobutadiene | 0.162 | 0.171 | -5.6 | 99 | 0.00 | 6.12 |
| 43 | t | 4-Chloro-3-methylphenol | 0.288 | 0.312 | -8.3 | 98 | 0.05 | 6.71 |
| 44 | t | 2-Methylnaphthalene | 0.664 | 0.634 | 4.5 | 91 | 0.00 | 6.80 |
| 45 | t | 1-Methylnaphthalene | 0.782 | 0.767 | 1.9 | 94 | 0.00 | 6.94 |
| 46 | t | Dimethylnaphthalene | 0.692 | 0.734 | -6.1 | 100 | 0.00 | 7.67 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 111 | 0.00 | 8.33 |
| 48 | t | Hexachlorocyclopentadiene | 0.257 | 0.215 | 16.3 | 84 | -0.01 | 7.02 |
| 49 | t | 2,4,6-Trichlorophenol | 0.330 | 0.344 | -4.2 | 107 | 0.00 | 7.22 |
| 50 | t | 2,4,5-Trichlorophenol | 0.378 | 0.379 | -0.3 | 108 | 0.03 | 7.31 |
| 51 | S | 2-Fluorobiphenyl | 1.339 | 1.171 | 12.5 | 96 | 0.00 | 7.31 |
| 52 | t | 2-Chloronaphthalene | 1.110 | 1.008 | 9.2 | 101 | 0.00 | 7.47 |
| 53 | t | Biphenyl | 1.521 | 1.359 | 10.7 | 96 | 0.00 | 7.45 |
| 54 | t | 2-Nitroaniline | 0.222 | 0.258 | -16.2 | 117 | 0.00 | 7.69 |
| 55 | t | Dimethylphthalate | 1.241 | 1.317 | -6.1 | 111 | 0.00 | 7.95 |
| 56 | t | Acenaphthylene | 1.791 | 1.753 | 2.1 | 101 | 0.00 | 8.11 |
| | | | True | Calc. | % Drift | | | |
| 57 | t | 2,6-Dinitrotoluene | 25.000 | 25.682 | -2.7 | 117 | 0.00 | 8.04 |
| | | | AvgRF | CCRF | % Dev | | | |
| 58 | t | 3-Nitroaniline | 0.287 | 0.328 | -14.3 | 117 | 0.02 | 8.35 |
| 59 | t | Acenaphthene | 1.170 | 1.086 | 7.2 | 100 | 0.00 | 8.38 |
| | | | True | Calc. | % Drift | | | |
| 60 | t | 2,4-Dinitrophenol | 50.000 | 57.302 | -14.6 | 132 | 0.03 | 8.50 |
| | | | AvgRF | CCRF | % Dev | | | |
| 61 | t | 4-Nitrophenol | 0.125 | 0.121 | 3.2 | 101 | 0.05 | 8.82 |
| 62 | t | Dibenzofuran | 1.602 | 1.575 | 1.7 | 107 | 0.00 | 8.67 |
| | | | True | Calc. | % Drift | | | |
| 63 | t | 2,4-Dinitrotoluene | 25.000 | 28.539 | -14.2 | 128 | 0.02 | 8.71 |
| | | | AvgRF | CCRF | % Dev | | | |
| 64 | t | 2,3,4,6-Tetrachlorophenol | 0.272 | 0.312 | -14.7 | 116 | 0.03 | 8.94 |
| 65 | t | Diethylphthalate | 1.188 | 1.301 | -9.5 | 113 | 0.01 | 9.13 |
| 66 | t | Fluorene | 1.338 | 1.345 | -0.5 | 110 | 0.01 | 9.25 |
| 67 | t | 4-Chlorophenyl-phenylethe | 0.603 | 0.639 | -6.0 | 122 | 0.01 | 9.28 |
| 68 | t | 4-Nitroaniline | 0.320 | 0.373 | -16.6 | 116 | 0.03 | 9.42 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 126 | 0.00 | 10.96 |
| | | | True | Calc. | % Drift | | | |
| 70 | t | 4,6-Dinitro-2-methylpheno | 25.000 | 28.359 | -13.4 | 149 | 0.00 | 9.41 |
| | | | AvgRF | CCRF | % Dev | | | |
| 71 | t | n-Nitrosodiphenylamine | 0.556 | 0.534 | 4.0 | 114 | -0.01 | 9.51 |
| 72 | t | 1,2-Diphenylhydrazine | 0.559 | 0.521 | 6.8 | 108 | -0.02 | 9.56 |
| 73 | S | 2,4,6-Tribromophenol | 0.109 | 0.138 | -26.6# | 140 | 0.00 | 9.70 |
| 74 | t | 4-Bromophenyl-phenylether | 0.220 | 0.233 | -5.9 | 128 | 0.00 | 10.15 |
| 75 | t | Hexachlorobenzene | 0.248 | 0.268 | -8.1 | 135 | 0.00 | 10.24 |
| 76 | t | Pentachlorophenol | 0.121 | 0.128 | -5.8 | 117 | 0.02 | 10.69 |
| 77 | t | Phenanthrene | 1.095 | 1.052 | 3.9 | 118 | 0.00 | 11.00 |
| 78 | t | Anthracene | 1.083 | 1.092 | -0.8 | 117 | 0.00 | 11.10 |
| 79 | t | Carbazole | 1.116 | 1.107 | 0.8 | 117 | 0.02 | 11.48 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EM5462-CC5442
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** M128175.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 80 | t | Di-n-butylphthalate | 1.148 | 1.262 | -9.9 | 121 | 0.02 | 12.20 |
| 81 | t | Fluoranthene | 1.199 | 1.276 | -6.4 | 127 | 0.03 | 13.29 |
| 82 | t | Octadecane | 0.337 | 0.310 | 8.0 | 107 | 0.00 | 10.84 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 144 | 0.00 | 16.12 |
| 84 | t | Pyrene | 1.258 | 1.177 | 6.4 | 128 | 0.02 | 13.72 |
| 85 | S | Terphenyl-d14 | 0.857 | 0.894 | -4.3 | 142 | -0.03 | 14.10 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 86 | t | Butylbenzylphthalate | 25.000 | 22.322 | 10.7 | 131 | -0.02 | 15.14 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 87 | t | Benzo[a]anthracene | 1.069 | 1.123 | -5.1 | 141 | 0.00 | 16.10 |
| 88 | t | 3,3'-Dichlorobenzidine | 0.375 | 0.460 | -22.7# | 156 | 0.00 | 16.15 |
| 89 | t | Chrysene | 1.092 | 1.099 | -0.6 | 141 | 0.00 | 16.17 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 90 | t | bis(2-Ethylhexyl)phthalat | 25.000 | 22.795 | 8.8 | 135 | 0.00 | 16.29 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 145 | 0.00 | 18.75 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 92 | t | Di-n-octylphthalate | 25.000 | 22.436 | 10.3 | 133 | -0.03 | 17.50 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 93 | t | Benzo[b]fluoranthene | 1.151 | 1.221 | -6.1 | 149 | 0.00 | 18.10 |
| 94 | t | Benzo[k]fluoranthene | 1.109 | 1.140 | -2.8 | 139 | 0.00 | 18.14 |
| 95 | t | Benzo[a]pyrene | 1.002 | 1.088 | -8.6 | 144 | 0.00 | 18.64 |
| 96 | t | Indeno[1,2,3-cd]pyrene | 1.086 | 1.195 | -10.0 | 150 | 0.01 | 20.48 |
| 97 | t | Dibenz(a,h)acridine | 0.951 | 1.057 | -11.1 | 148 | 0.00 | 20.09 |
| 98 | t | Dibenz[a,h]anthracene | 1.137 | 1.219 | -7.2 | 148 | 0.00 | 20.52 |
| 99 | t | 7,12-Dimethylbenz(a)anthr | 0.479 | 0.515 | -7.5 | 140 | -0.02 | 18.09 |
| 100 | t | Benzo[g,h,i]perylene | 1.138 | 1.184 | -4.0 | 145 | 0.02 | 20.96 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127797.D MM5442.M Fri Oct 07 16:16:41 2016 MSM

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EM5462-CC5443
**Lab FileID:** M128178.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\EM5462\M128178.D Vial: 3
Acq On : 7 Oct 2016 10:49 am Operator: chriss2
Sample : cc5443-25 Inst : Instrument #1
Misc : op96678,em5462 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MM5442.M (RTE Integrator)
Title : Semi Volatile GC/MS, rtx-5ms 30mx0.25mmx0.25um
Last Update : Fri Oct 07 09:45:00 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 101 | I | 1,4-Dichlorobenzene-d4a | 1.000 | 1.000 | 0.0 | 79 | 0.00 | 4.82 |
| | | | True | Calc. | % Drift | | | |
| 102 | t | Benzaldehyde | 25.000 | 25.766 | -3.1 | 71 | 0.00 | 4.50 |
| | | | AvgRF | CCRF | % Dev | | | |
| 103 | I | Acenaphthene-d10a | 1.000 | 1.000 | 0.0 | 104 | 0.00 | 8.33 |
| 104 | I | 1,2,4,5-Tetrachlorobenzen | 0.572 | 0.454 | 20.6# | 86 | -0.01 | 7.03 |
| 105 | t | Atrazine | 0.176 | 0.239 | -35.8# | 125 | 0.02 | 10.55 |
| 106 | I | Chrysene-d12a | 1.000 | 1.000 | 0.0 | 148 | -0.01 | 16.11 |
| 107 | t | Benzidine | 0.610 | 0.552 | 9.5 | 117 | 0.02 | 13.67 |
| 108 | s | 1-chlorooctadecane | 0.243 | 0.190 | 21.8# | 110 | -0.02 | 13.17 |
| 109 | I | Phenanthrene-d10a | 1.000 | 1.000 | 0.0 | 120 | 0.00 | 10.96 |
| 110 | s | o-terphenyl | 0.623 | 0.595 | 4.5 | 119 | 0.00 | 11.74 |
| 111 | I | Naphthalene-d8a | 1.000 | 1.000 | 0.0 | 85 | 0.00 | 5.97 |
| 112 | | Hydroquinone | 0.329 | 0.374 | -13.7 | 90 | 0.00 | 6.55 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of M127797.D MM5442.M Fri Oct 07 16:16:44 2016 MSM

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICC4769
**Lab FileID:** P107664.D

Response Factor Report MSP

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 16:22:13 2016
Response via : Initial Calibration

Calibration Files
2 =P107665.D 5 =P107666.D 25 =P107668.D 80 =P107669.D
100 =P107662.D 50 =P107664.D 10 =P107667.D 1 =P107663.D

| Compound | 2 | 5 | 25 | 80 | 100 | 50 | 10 | 1 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 1) I 1,4-Dichlorobenzene-d | ISTD | | | | | | | | | |
| 2) 1,4-Dioxane | 0.665 | 0.693 | 0.771 | 0.763 | 0.744 | 0.791 | 0.789 | 0.787 | 0.751 | 6.30 |
| 3) Pyridine | 1.552 | 1.578 | 1.967 | 1.833 | 1.779 | 1.840 | 1.996 | 1.474 | 1.752 | 11.17 |
| 4) N-Nitrosodim | 0.791 | 0.791 | 0.882 | 0.820 | 0.800 | 0.861 | 0.911 | 0.865 | 0.840 | 5.45 |
| 5) 2-Fluorophen | 1.228 | 1.423 | 1.569 | 1.482 | 1.443 | 1.555 | 1.552 | 1.285 | 1.442 | 8.83 |
| 6) Indene | 2.427 | 2.511 | 2.425 | 2.227 | 2.099 | 2.374 | 2.567 | 2.516 | 2.393 | 6.63 |
| 7) Cumene | 3.740 | 3.891 | 3.824 | 3.211 | 3.025 | 3.547 | 4.211 | 3.731 | 3.647 | 10.42 |
| 8) Phenol-d5 | 1.976 | 2.046 | 1.993 | 1.777 | 1.683 | 1.898 | 2.073 | 1.802 | 1.906 | 7.35 |
| 9) Phenol | 2.191 | 2.281 | 2.247 | 1.944 | 1.836 | 2.089 | 2.400 | 2.324 | 2.164 | 8.97 |
| 10) Aniline | 2.386 | 2.545 | 2.290 | 1.906 | 1.835 | 2.177 | 2.573 | 2.547 | 2.282 | 12.69 |
| 11) bis(2-Chloro | 1.473 | 1.473 | 1.400 | 1.235 | 1.197 | 1.308 | 1.513 | 1.493 | 1.386 | 8.95 |
| 12) 2-Chlorophen | 1.534 | 1.465 | 1.438 | 1.291 | 1.225 | 1.370 | 1.540 | 1.391 | 1.407 | 7.90 |
| 13) Decane | 1.493 | 1.426 | 1.315 | 1.140 | 1.110 | 1.268 | 1.420 | 1.530 | 1.338 | 11.71 |
| 14) 1,3-Dichloro | 1.577 | 1.611 | 1.560 | 1.419 | 1.358 | 1.519 | 1.671 | 1.565 | 1.535 | 6.63 |
| 15) 1,4-Dichloro | 1.577 | 1.502 | 1.511 | 1.383 | 1.328 | 1.467 | 1.589 | 1.532 | 1.486 | 6.12 |
| 16) Benzyl alcoh | 0.802 | 0.851 | 0.951 | 0.929 | 0.893 | 0.946 | 0.993 | 0.679 | 0.880 | 11.54 |
| 17) 1,2-Dichloro | 1.472 | 1.458 | 1.490 | 1.323 | 1.262 | 1.404 | 1.562 | 1.465 | 1.430 | 6.75 |
| 18) Acetophenone | 2.084 | 2.021 | 2.023 | 1.927 | 1.837 | 1.984 | 2.157 | 2.035 | 2.008 | 4.82 |
| 19) 2-Methylphen | 1.335 | 1.380 | 1.337 | 1.270 | 1.214 | 1.306 | 1.414 | 1.333 | 1.324 | 4.70 |
| 20) 2,2'-oxybis( | 0.406 | 0.466 | 0.436 | 0.421 | 0.398 | 0.414 | 0.463 | 0.457 | 0.433 | 6.20 |
| 21) 3&4-Methylph | 1.438 | 1.462 | 1.458 | 1.372 | 1.336 | 1.416 | 1.571 | 1.392 | 1.431 | 4.98 |
| 22) n-Nitroso-di | 1.186 | 1.184 | 1.177 | 1.068 | 1.037 | 1.123 | 1.277 | 1.262 | 1.164 | 7.30 |
| 23) Hexachloroet | 0.563 | 0.558 | 0.585 | 0.565 | 0.547 | 0.579 | 0.597 | 0.573 | 0.571 | 2.82 |
| 24) I Naphthalene-d8 | ISTD | | | | | | | | | |
| 25) Nitrobenzene | 0.466 | 0.489 | 0.490 | 0.446 | 0.423 | 0.467 | 0.529 | 0.466 | 0.472 | 6.72 |
| 26) Nitrobenzene | 0.495 | 0.480 | 0.464 | 0.413 | 0.393 | 0.440 | 0.520 | 0.461 | 0.458 | 9.14 |
| 27) Quinoline | 0.741 | 0.803 | 0.805 | 0.780 | 0.746 | 0.795 | 0.858 | 0.715 | 0.780 | 5.77 |
| 28) Isophorone | 0.828 | 0.914 | 0.871 | 0.769 | 0.733 | 0.824 | 0.954 | 0.825 | 0.840 | 8.61 |
| 29) 2-Nitropheno | 0.189 | 0.200 | 0.213 | 0.195 | 0.187 | 0.210 | 0.229 | 0.188 | 0.201 | 7.41 |
| 30) 2,4-Dimethyl | 0.386 | 0.397 | 0.377 | 0.366 | 0.349 | 0.380 | 0.409 | 0.368 | 0.379 | 5.00 |
| 31) Benzoic acid | | | 0.275 | 0.313 | 0.305 | 0.297 | 0.241 | | 0.286 | 10.12 |
| 32) bis(2-Chloro | 0.467 | 0.482 | 0.478 | 0.428 | 0.405 | 0.449 | 0.514 | 0.446 | 0.459 | 7.47 |
| 33) 2,4-Dichloro | 0.295 | 0.341 | 0.335 | 0.305 | 0.287 | 0.326 | 0.359 | 0.281 | 0.316 | 8.86 |
| 34) 2,6-Dichloro | 0.291 | 0.311 | 0.313 | 0.285 | 0.270 | 0.302 | 0.337 | 0.288 | 0.300 | 6.93 |
| 35) 1,3,5-Trichl | 0.376 | 0.404 | 0.384 | 0.331 | 0.314 | 0.352 | 0.422 | 0.397 | 0.372 | 10.02 |
| 36) 1,2,4-Trichl | 0.353 | 0.398 | 0.371 | 0.327 | 0.309 | 0.348 | 0.394 | 0.363 | 0.358 | 8.58 |
| 37) 1,2,3-Trichl | 0.357 | 0.367 | 0.358 | 0.322 | 0.306 | 0.343 | 0.387 | 0.350 | 0.349 | 7.29 |
| 38) Naphthalene | 1.129 | 1.125 | 1.061 | 0.908 | 0.840 | 1.004 | 1.170 | 1.079 | 1.039 | 11.07 |
| 39) 4-Chloroanil | 0.444 | 0.489 | 0.469 | 0.411 | 0.393 | 0.449 | 0.519 | 0.449 | 0.453 | 8.93 |
| 40) 2,3-Dichloro | 0.382 | 0.428 | 0.412 | 0.388 | 0.367 | 0.399 | 0.452 | 0.416 | 0.405 | 6.68 |
| 41) Caprolactam | 0.147 | 0.168 | 0.182 | 0.178 | 0.176 | 0.179 | 0.188 | 0.194 | 0.176 | 8.05 |
| 42) Hexachlorobu | 0.223 | 0.235 | 0.229 | 0.210 | 0.196 | 0.220 | 0.237 | 0.218 | 0.221 | 6.07 |
| 43) 4-Chloro-3-m | 0.322 | 0.379 | 0.406 | 0.368 | 0.350 | 0.378 | 0.412 | 0.348 | 0.370 | 8.12 |
| 44) 2-Methylnaph | 0.671 | 0.657 | 0.647 | 0.559 | 0.521 | 0.607 | 0.699 | 0.647 | 0.626 | 9.55 |
| 45) 1-Methylnaph | 0.802 | 0.840 | 0.813 | 0.696 | 0.653 | 0.757 | 0.886 | 0.808 | 0.782 | 9.78 |

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICC4769
**Lab FileID:** P107664.D

```
46) Dimethylnaph 0.701 0.765 0.732 0.649 0.615 0.703 0.807 0.714 0.711   8.56

47) I   Acenaphthene-d10      ----------------ISTD--------------------
48) Hexachlorocy 0.037 0.082 0.209 0.242 0.233 0.232 0.167       0.172  47.50
         ----- Quadratic regression -----                 Coefficient =  0.9990
              Response Ratio = -0.03821 + 0.25346 *A + -0.00199 *A^2

49) 2,4,6-Trichl 0.336 0.368 0.361 0.326 0.314 0.346 0.391 0.348 0.349   7.02
50) 2,4,5-Trichl 0.374 0.401 0.380 0.357 0.342 0.384 0.426 0.339 0.375   7.83
51) 2-Fluorobiph 1.422 1.406 1.260 1.035       1.158 1.424 1.412 1.302  11.97
52) 2-Chloronaph 1.172 1.120 1.039 0.898 0.848 0.962 1.161 1.136 1.042  12.07
53) Biphenyl     1.521 1.580 1.442 1.229 1.151 1.359 1.628 1.581 1.436  12.23
54) 2-Nitroanili 0.375 0.436 0.422 0.384 0.369 0.405 0.471 0.380 0.405   8.74
55) Dimethylphth 1.309 1.265 1.250 1.124 1.063 1.161 1.263 1.302 1.217   7.41
56) Acenaphthyle 1.795 1.826 1.738 1.479 1.413 1.675 1.902 1.822 1.706  10.24
57) 2,6-Dinitrot 0.272 0.297 0.304 0.298 0.289 0.306 0.305 0.247 0.290   7.13
58) 3-Nitroanili 0.277 0.330 0.336 0.332 0.326 0.342 0.346 0.274 0.320   8.90
59) Acenaphthene 1.117 1.169 1.137 0.982 0.940 1.077 1.243 1.147 1.101   9.02
60) 2,4-Dinitrop 0.003 0.026 0.125 0.174 0.172 0.151 0.088       0.106  65.54
         ----- Quadratic regression -----                 Coefficient =  0.9982
              Response Ratio = -0.02875 + 0.15053 *A + 0.00596 *A^2

61) 4-Nitropheno 0.111 0.144 0.185 0.179 0.174 0.186 0.176       0.165  16.89
         ----- Quadratic regression -----                 Coefficient =  1.0000
              Response Ratio = -0.00589 + 0.20233 *A + -0.01028 *A^2

62) Dibenzofuran 1.620 1.704 1.569 1.315 1.234 1.466 1.802 1.705 1.552  12.85
63) 2,4-Dinitrot 0.311 0.387 0.402 0.348 0.332 0.381 0.435 0.279 0.359  14.26
64) 2,3,4,6-Tetr 0.265 0.309 0.341 0.346 0.339 0.353 0.346 0.282 0.323  10.40
65) Diethylphtha 1.221 1.313 1.263 1.110 1.053 1.210 1.397 1.285 1.232   8.96
66) Fluorene     1.378 1.442 1.331 1.119 1.054 1.226 1.449 1.364 1.295  11.38
67) 4-Chlorophen 0.696 0.714 0.677 0.595 0.566 0.638 0.742 0.698 0.666   9.15
68) 4-Nitroanili 0.237 0.277 0.328 0.323 0.321 0.333 0.338 0.264 0.303  12.53

69) I   Phenanthrene-d10      ----------------ISTD--------------------
70) 4,6-Dinitro- 0.025 0.064 0.135 0.150 0.146 0.143 0.112       0.111  43.49
         ----- Quadratic regression -----                 Coefficient =  0.9995
              Response Ratio = -0.00995 + 0.15536 *A + -0.00185 *A^2

71) n-Nitrosodip 0.561 0.578 0.559 0.494 0.466 0.537 0.613 0.519 0.541   8.75
72) 1,2-Diphenyl 0.784 0.853 0.794 0.675 0.627 0.744 0.860 0.774 0.764  10.59
73) 2,4,6-Tribro 0.081 0.090 0.101 0.100 0.096 0.102 0.103       0.096   8.34
74) 4-Bromopheny 0.225 0.233 0.239 0.223 0.211 0.237 0.258 0.216 0.230   6.55
75) Hexachlorobe 0.235 0.237 0.232 0.208 0.203 0.222 0.250 0.272 0.232   9.59
76) Pentachlorop 0.043 0.077 0.116 0.120 0.119 0.119 0.096       0.099  29.63
         ----- Quadratic regression -----                 Coefficient =  0.9999
              Response Ratio = -0.01153 + 0.12621 *A + -0.00091 *A^2

77) Phenanthrene 1.112 1.116 1.078 0.942 0.883 1.027 1.172 1.129 1.057   9.44
78) Anthracene   1.132 1.168 1.125 0.967 0.904 1.073 1.224 1.140 1.092   9.78
79) Carbazole    1.065 1.098 1.092 0.957 0.910 1.045 1.199 1.065 1.054   8.40
80) Di-n-butylph 1.045 1.214 1.251 1.092 1.017 1.192 1.298 1.011 1.140   9.88
81) Fluoranthene 1.247 1.322 1.321 1.130 1.066 1.236 1.374 1.221 1.240   8.31
82) Octadecane   0.444 0.497 0.468 0.404 0.380 0.441 0.491 0.442 0.446   8.99

83) I   Chrysene-d12          ----------------ISTD--------------------
84) Pyrene       1.284 1.346 1.348 1.217 1.179 1.275 1.444 1.298 1.299   6.33
85) Terphenyl-d1 0.829 0.868 0.895 0.859 0.823 0.870 0.915 0.847 0.863   3.61
86) Butylbenzylp 0.418 0.500 0.553 0.544 0.534 0.554 0.534 0.416 0.507  11.38
87) Benzo[a]anth 1.116 1.179 1.209 1.169 1.141 1.202 1.246 1.223 1.186   3.63
```

# Initial Calibration Summary



**Job Number:** JC28902 **Sample:** EP4769-ICC4769
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** P107664.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 88) | 3,3'-Dichlor | 0.328 | 0.381 | 0.414 | 0.426 | 0.422 | 0.429 | 0.414 | 0.349 | 0.395 | 9.71 |
| 89) | Chrysene | 1.118 | 1.148 | 1.142 | 1.073 | 1.069 | 1.122 | 1.198 | 1.103 | 1.122 | 3.76 |
| 90) | bis(2-Ethylh | 0.511 | 0.603 | 0.731 | 0.716 | 0.699 | 0.735 | 0.729 | | 0.675 | 12.69 |
| 91) | I Perylene-d12 | ISTD | | | | | | | | | |
| 92) | Di-n-octylph | 0.910 | 1.111 | 1.336 | 1.253 | 1.156 | 1.340 | 1.314 | | 1.203 | 13.05 |
| 93) | Benzo[b]fluo | 1.169 | 1.307 | 1.304 | 1.228 | 1.181 | 1.259 | 1.415 | 1.313 | 1.272 | 6.33 |
| 94) | Benzo[k]fluo | 1.236 | 1.274 | 1.211 | 1.092 | 0.993 | 1.187 | 1.310 | 1.221 | 1.191 | 8.59 |
| 95) | Benzo[a]pyre | 1.064 | 1.128 | 1.176 | 1.108 | 1.038 | 1.156 | 1.215 | 1.173 | 1.132 | 5.30 |
| 96) | Indeno[1,2,3 | 0.899 | 1.013 | 1.079 | 1.051 | 0.988 | 1.063 | 1.124 | 0.930 | 1.018 | 7.49 |
| 97) | Dibenz(a,h)a | 0.812 | 0.891 | 0.982 | 0.936 | 0.865 | 0.966 | 1.004 | 0.860 | 0.914 | 7.43 |
| 98) | Dibenz[a,h]a | 0.965 | 1.008 | 1.013 | 1.014 | 0.955 | 1.048 | 1.113 | 0.935 | 1.006 | 5.65 |
| 99) | 7,12-Dimethy | 0.476 | 0.532 | 0.578 | 0.558 | 0.541 | 0.586 | 0.596 | 0.478 | 0.543 | 8.50 |
| 100) | Benzo[g,h,i] | 1.100 | 1.091 | 1.154 | 1.093 | 1.030 | 1.129 | 1.223 | 1.048 | 1.108 | 5.49 |

(#) = Out of Range ### Number of calibration levels exceeded format ###

MP4769.M Thu Sep 22 16:22:41 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICV4769
**Lab FileID:** P107670.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4769\P107670.D Vial: 10
Acq On : 21 Sep 2016 7:14 pm Operator: robertl1
Sample : ICV4769-50 Inst : MSP
Misc : OP97024,EP4769 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 11:48:02 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 124 | 0.00 | 4.50 |
| 4 | t | N-Nitrosodimethylamine | 0.840 | 0.731 | 13.0 | 105 | 0.02 | 2.33 |
| 11 | t | bis(2-Chloroethyl)ether | 1.386 | 1.484 | -7.1 | 141 | 0.00 | 4.30 |
| 14 | t | 1,3-Dichlorobenzene | 1.535 | 1.550 | -1.0 | 126 | 0.00 | 4.46 |
| 15 | t | 1,4-Dichlorobenzene | 1.486 | 1.398 | 5.9 | 118 | 0.00 | 4.51 |
| 17 | t | 1,2-Dichlorobenzene | 1.430 | 1.396 | 2.4 | 123 | 0.00 | 4.62 |
| 20 | t | 2,2'-oxybis(1-Chloropropa | 0.433 | 0.414 | 4.4 | 124 | 0.00 | 4.70 |
| 22 | | n-Nitroso-di-n-propylamin | 1.164 | 1.086 | 6.7 | 120 | 0.00 | 4.79 |
| 23 | t | Hexachloroethane | 0.571 | 0.550 | 3.7 | 117 | 0.00 | 4.87 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 114 | 0.00 | 5.42 |
| 26 | t | Nitrobenzene | 0.458 | 0.437 | 4.6 | 113 | 0.00 | 4.91 |
| 28 | t | Isophorone | 0.840 | 0.759 | 9.6 | 105 | 0.00 | 5.08 |
| 32 | t | bis(2-Chloroethoxy)methan | 0.459 | 0.470 | -2.4 | 119 | 0.00 | 5.24 |
| 36 | t | 1,2,4-Trichlorobenzene | 0.358 | 0.357 | 0.3 | 117 | 0.00 | 5.38 |
| 38 | t | Naphthalene | 1.039 | 0.958 | 7.8 | 109 | 0.00 | 5.43 |
| 42 | t | Hexachlorobutadiene | 0.221 | 0.221 | 0.0 | 115 | 0.00 | 5.52 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 106 | 0.00 | 6.77 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 48 | t | Hexachlorocyclopentadiene | 50.000 | 47.891 | 4.2 | 96 | 0.00 | 6.04 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 52 | t | 2-Chloronaphthalene | 1.042 | 1.028 | 1.3 | 113 | 0.00 | 6.29 |
| 55 | t | Dimethylphthalate | 1.217 | 1.129 | 7.2 | 103 | 0.00 | 6.52 |
| 56 | t | Acenaphthylene | 1.706 | 1.489 | 12.7 | 94 | 0.00 | 6.64 |
| 57 | t | 2,6-Dinitrotoluene | 0.290 | 0.275 | 5.2 | 96 | 0.00 | 6.58 |
| 59 | t | Acenaphthene | 1.101 | 1.006 | 8.6 | 99 | 0.00 | 6.80 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 63 | t | 2,4-Dinitrotoluene | 0.359 | 0.354 | 1.4 | 99 | 0.00 | 6.96 |
| 65 | t | Diethylphthalate | 1.232 | 1.104 | 10.4 | 97 | 0.00 | 7.20 |
| 66 | t | Fluorene | 1.295 | 1.116 | 13.8 | 97 | 0.00 | 7.33 |
| 67 | t | 4-Chlorophenyl-phenylethe | 0.666 | 0.593 | 11.0 | 99 | 0.00 | 7.32 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 100 | 0.00 | 8.55 |
| 71 | t | n-Nitrosodiphenylamine | 0.541 | 0.485 | 10.4 | 90 | 0.00 | 7.47 |
| 72 | t | 1,2-Diphenylhydrazine | 0.764 | 0.718 | 6.0 | 97 | 0.00 | 7.51 |
| 74 | t | 4-Bromophenyl-phenylether | 0.230 | 0.222 | 3.5 | 94 | 0.00 | 7.92 |

# Initial Calibration Verification



**Job Number:** JC28902 **Sample:** EP4769-ICV4769
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** P107670.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 75 | t | Hexachlorobenzene | 0.232 | 0.211 | 9.1 | 95 | 0.00 | 8.02 |
| 77 | t | Phenanthrene | 1.057 | 0.958 | 9.4 | 93 | 0.00 | 8.59 |
| 78 | t | Anthracene | 1.092 | 0.955 | 12.5 | 89 | 0.00 | 8.66 |
| 80 | t | Di-n-butylphthalate | 1.140 | 1.077 | 5.5 | 90 | 0.00 | 9.60 |
| 81 | t | Fluoranthene | 1.240 | 1.090 | 12.1 | 88 | 0.00 | 10.66 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 85 | 0.00 | 13.71 |
| 84 | t | Pyrene | 1.299 | 1.307 | -0.6 | 87 | 0.00 | 11.10 |
| 86 | t | Butylbenzylphthalate | 0.507 | 0.552 | -8.9 | 85 | 0.00 | 12.67 |
| 87 | t | Benzo[a]anthracene | 1.186 | 1.130 | 4.7 | 80 | 0.00 | 13.69 |
| 89 | t | Chrysene | 1.122 | 1.027 | 8.5 | 78 | 0.00 | 13.77 |
| 90 | t | bis(2-Ethylhexyl)phthalat | 0.675 | 0.694 | -2.8 | 80 | 0.00 | 14.07 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 81 | 0.00 | 16.74 |
| 92 | t | Di-n-octylphthalate | 1.203 | 1.323 | -10.0 | 80 | 0.00 | 15.50 |
| 93 | t | Benzo[b]fluoranthene | 1.272 | 1.174 | 7.7 | 76 | 0.00 | 15.99 |
| 94 | t | Benzo[k]fluoranthene | 1.191 | 1.149 | 3.5 | 79 | 0.00 | 16.05 |
| 95 | t | Benzo[a]pyrene | 1.132 | 1.108 | 2.1 | 78 | 0.00 | 16.62 |
| 96 | t | Indeno[1,2,3-cd]pyrene | 1.018 | 0.929 | 8.7 | 71 | 0.00 | 18.69 |
| 98 | t | Dibenz[a,h]anthracene | 1.006 | 0.933 | 7.3 | 73 | 0.00 | 18.74 |
| 100 | t | Benzo[g,h,i]perylene | 1.108 | 1.034 | 6.7 | 75 | 0.00 | 19.11 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 11:56:07 2016

7.7.16

7

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICV4769
**Lab FileID:** P107672.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4769\P107672.D Vial: 12
Acq On : 21 Sep 2016 8:11 pm Operator: robertl1
Sample : ICV4769-50 Inst : MSP
Misc : OP97024,EP4769 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 12:40:53 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 127 | 0.00 | 4.50 |
| 9 | t | Phenol | 2.164 | 2.012 | 7.0 | 123 | 0.00 | 4.28 |
| 12 | t | 2-Chlorophenol | 1.407 | 1.443 | -2.6 | 134 | 0.00 | 4.36 |
| 19 | t | 2-Methylphenol | 1.324 | 1.350 | -2.0 | 132 | 0.00 | 4.70 |
| 21 | t | 3&4-Methylphenol | 1.431 | 1.410 | 1.5 | 127 | 0.00 | 4.82 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 116 | 0.00 | 5.42 |
| 29 | t | 2-Nitrophenol | 0.201 | 0.223 | -10.9 | 123 | 0.00 | 5.15 |
| 30 | t | 2,4-Dimethylphenol | 0.379 | 0.416 | -9.8 | 127 | 0.00 | 5.19 |
| 31 | t | Benzoic acid | 0.286 | 0.270 | 5.6 | 106 | 0.02 | 5.30 |
| 33 | t | 2,4-Dichlorophenol | 0.316 | 0.322 | -1.9 | 115 | 0.00 | 5.33 |
| 34 | | 2,6-Dichlorophenol | 0.300 | 0.317 | -5.7 | 122 | 0.00 | 5.48 |
| 43 | t | 4-Chloro-3-methylphenol | 0.370 | 0.359 | 3.0 | 111 | 0.00 | 5.83 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 113 | 0.00 | 6.77 |
| 49 | t | 2,4,6-Trichlorophenol | 0.349 | 0.382 | -9.5 | 125 | 0.00 | 6.14 |
| 50 | t | 2,4,5-Trichlorophenol | 0.375 | 0.370 | 1.3 | 108 | -0.01 | 6.17 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 60 | t | 2,4-Dinitrophenol | 50.000 | 44.533 | 10.9 | 88 | -0.06 | 6.84 |
| 61 | t | 4-Nitrophenol | 50.000 | 47.370 | 5.3 | 107 | 0.00 | 6.94 |
| | | ---------- | AvgRF | CCRF | % Dev | ---------- | | |
| 64 | | 2,3,4,6-Tetrachlorophenol | 0.323 | 0.336 | -4.0 | 107 | 0.00 | 7.10 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 102 | 0.00 | 8.55 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 70 | t | 4,6-Dinitro-2-methylpheno | 50.000 | 47.344 | 5.3 | 98 | 0.00 | 7.40 |
| | | ---------- | True | Calc. | % Drift | ---------- | | |
| 76 | t | Pentachlorophenol | 50.000 | 51.745 | -3.5 | 104 | 0.00 | 8.30 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 12:43:47 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICV4769
**Lab FileID:** P107673.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4769\P107673.D Vial: 13
Acq On : 21 Sep 2016 8:39 pm Operator: robertl1
Sample : ICV4769-50 Inst : MSP
Misc : OP97024,EP4769 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 11:48:02 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 100 | 0.00 | 4.50 |
| 3 | t | Pyridine | 1.752 | 1.885 | -7.6 | 103 | 0.11 | 2.45 |
| 10 | t | Aniline | 2.282 | 2.621 | -14.9 | 121 | 0.01 | 4.27 |
| 16 | t | Benzyl alcohol | 0.880 | 1.017 | -15.6 | 108 | 0.00 | 4.61 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 108 | 0.00 | 5.42 |
| 39 | t | 4-Chloroaniline | 0.453 | 0.427 | 5.7 | 103 | 0.00 | 5.47 |
| 44 | t | 2-Methylnaphthalene | 0.626 | 0.540 | 13.7 | 96 | 0.00 | 5.92 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 6.77 |
| 54 | t | 2-Nitroaniline | 0.405 | 0.406 | -0.2 | 97 | 0.00 | 6.38 |
| 58 | t | 3-Nitroaniline | 0.320 | 0.323 | -0.9 | 92 | 0.00 | 6.74 |
| 62 | t | Dibenzofuran | 1.552 | 1.539 | 0.8 | 102 | 0.00 | 6.96 |
| 68 | t | 4-Nitroaniline | 0.303 | 0.320 | -5.6 | 93 | 0.00 | 7.37 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 103 | 0.00 | 8.55 |
| 79 | t | Carbazole | 1.054 | 0.930 | 11.8 | 92 | 0.00 | 8.94 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 11:56:09 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICV4769
**Lab FileID:** P107674.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4769\P107674.D Vial: 14
Acq On : 21 Sep 2016 9:07 pm Operator: robertl1
Sample : ICV4769-50 Inst : MSP
Misc : OP97024,EP4769 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 11:48:02 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 83 I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 13.71 |
| 88 t | 3,3'-Dichlorobenzidine | 0.395 | 0.397 | -0.5 | 90 | 0.00 | 13.73 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 11:56:10 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4769-ICV4769
**Lab FileID:** P107675.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4769\P107675.D Vial: 15
Acq On : 21 Sep 2016 9:34 pm Operator: robertl1
Sample : ICV4769-50 Inst : MSP
Misc : OP97024,EP4769 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 11:48:02 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 129 | 0.00 | 4.50 |
| 5 | S | 2-Fluorophenol | 1.442 | 1.452 | -0.7 | 121 | 0.00 | 3.55 |
| 8 | S | Phenol-d5 | 1.906 | 1.851 | 2.9 | 126 | 0.00 | 4.27 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 122 | 0.00 | 5.42 |
| 25 | S | Nitrobenzene-d5 | 0.472 | 0.445 | 5.7 | 116 | 0.00 | 4.90 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 109 | 0.00 | 6.77 |
| 51 | S | 2-Fluorobiphenyl | 1.302 | 1.186 | 8.9 | 112 | 0.00 | 6.19 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 102 | 0.00 | 8.55 |
| 73 | S | 2,4,6-Tribromophenol | 0.096 | 0.101 | -5.2 | 102 | 0.00 | 7.61 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 96 | 0.00 | 13.71 |
| 85 | S | Terphenyl-d14 | 0.863 | 0.831 | 3.7 | 91 | 0.00 | 11.52 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 11:56:11 2016

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4770-ICC4770
**Lab FileID:** P107679.D

Response Factor Report MSP

Method : C:\MSDCHEM\1\METHODS\MP4770.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 15:52:56 2016
Response via : Initial Calibration

Calibration Files
2 =P107683.D 5 =P107682.D 25 =P107680.D 80 =P107678.D
100 =P107677.D 50 =P107679.D 10 =P107681.D 1 =P107684.D

| Compound | 2 | 5 | 25 | 80 | 100 | 50 | 10 | 1 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 158) I 1,4-Dichlorobenzene-d | ISTD | | | | | | | | | |
| 159) Benzaldehyde | 1.387 | 1.407 | 1.195 | 0.831 | 0.708 | 0.931 | 1.311 | 1.503 | 1.159 | 25.65 |
| ----- Quadratic regression ----- Coefficient = 0.9980 | | | | | | | | | | |
| Response Ratio = 0.02275 + 1.21397 *A + -0.20464 *A^2 | | | | | | | | | | |
| 160) I Phenanthrene-d10b | ISTD | | | | | | | | | |
| 161) Atrazine | 0.232 | 0.270 | 0.248 | 0.236 | 0.234 | 0.244 | 0.254 | 0.206 | 0.241 | 7.73 |
| 162) I Chrysene-d12b | ISTD | | | | | | | | | |
| 163) Benzidine | | 0.604 | 0.658 | 0.395 | | 0.509 | 0.688 | | 0.571 | 20.95 |
| 164) I Naphthalene-d8b | ISTD | | | | | | | | | |
| 165) Hydroquinone | 0.250 | 0.341 | 0.385 | 0.395 | 0.377 | 0.397 | 0.352 | | 0.357 | 14.46 |
| 166) I Acenaphthene-d10b | ISTD | | | | | | | | | |
| 167) 1,2,4,5-Tetr | 0.742 | 0.750 | 0.637 | 0.574 | 0.563 | 0.593 | 0.671 | 0.750 | 0.660 | 12.09 |

(#) = Out of Range ### Number of calibration levels exceeded format ###

MP4769.M Thu Sep 22 15:53:27 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4770-ICV4770
**Lab FileID:** P107685.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4770\P107685.D Vial: 10
Acq On : 22 Sep 2016 12:25 pm Operator: robertl1
Sample : ICV4770-50 Inst : MSP
Misc : OP97024,EP4770 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 16:22:13 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 166 I | Acenaphthene-d10b | 1.000 | 1.000 | 0.0 | 83 | 0.00 | 6.77 |
| 167 | 1,2,4,5-Tetrachlorobenzen | 0.660 | 0.634 | 3.9 | 88 | 0.00 | 6.05 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 16:30:45 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4770-ICV4770
**Lab FileID:** P107686.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4770\P107686.D Vial: 11
Acq On : 22 Sep 2016 12:53 pm Operator: robertl1
Sample : ICV4770-51 Inst : MSP
Misc : OP97024,EP4770 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 12:51:15 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 158 I | 1,4-Dichlorobenzene-d4b | 1.000 | 1.000 | 0.0 | 83 | 0.00 | 4.50 |
| | | True | Calc. | % Drift | | | |
| 159 | Benzaldehyde | 50.000 | 54.386 | -8.8 | 92 | 0.00 | 4.18 |
| | | AvgRF | CCRF | % Dev | | | |
| 160 I | Phenanthrene-d10b | 1.000 | 1.000 | 0.0 | 80 | 0.00 | 8.55 |
| 161 | Atrazine | 0.241 | 0.233 | 3.3 | 76 | 0.00 | 8.18 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 15:51:09 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4770-ICV4770
**Lab FileID:** P107687.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4770\P107687.D Vial: 12
Acq On : 22 Sep 2016 1:21 pm Operator: robertl1
Sample : ICV4770-50 Inst : MSP
Misc : OP97024,EP4770 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 15:52:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 162 I | Chrysene-d12b | 1.000 | 1.000 | 0.0 | 86 | 0.00 | 13.70 |
| 163 | Benzidine | 0.571 | 0.772 | -35.2# | 131 | 0.00 | 11.00 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 15:58:34 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4770-ICV4770
**Lab FileID:** P107688.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4770\P107688.D Vial: 13
Acq On : 22 Sep 2016 1:50 pm Operator: robertl1
Sample : ICV4770-50 Inst : MSP
Misc : OP97024,EP4770 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 12:51:15 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 164 I | Naphthalene-d8b | 1.000 | 1.000 | 0.0 | 87 | 0.00 | 5.42 |
| 165 | Hydroquinone | 0.357 | 0.414 | -16.0 | 91 | -0.01 | 5.74 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 15:51:10 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EP4771-ICV4769
**Lab FileID:** P107690.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4771\P107690.D Vial: 2
Acq On : 22 Sep 2016 3:22 pm Operator: ashleyd
Sample : icv4769-50 Inst : MSP
Misc : OP97024,EP4771 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Sep 22 15:52:56 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 134 | 0.00 | 4.49 |
| 2 | t | 1,4-Dioxane | 0.751 | 0.591 | 21.3 | 100 | 0.01 | 2.01 |
| 6 | t | Indene | 2.393 | 2.242 | 6.3 | 126 | 0.00 | 4.68 |
| 7 | t | Cumene | 3.647 | 2.965 | 18.7 | 112 | 0.00 | 3.90 |
| 13 | t | Decane | 1.338 | 1.089 | 18.6 | 115 | -0.01 | 4.37 |
| 18 | t | Acetophenone | 2.008 | 1.774 | 11.7 | 119 | 0.00 | 4.78 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 129 | -0.01 | 5.40 |
| 26 | t | Nitrobenzene | 0.458 | 0.443 | 3.3 | 130 | -0.14 | 4.78 |
| 27 | t | Quinoline | 0.780 | 0.662 | 15.1 | 107 | -0.01 | 5.66 |
| 40 | t | 2,3-Dichloroaniline | 0.405 | 0.325 | 19.8 | 105 | 0.00 | 6.13 |
| 41 | t | Caprolactam | 0.176 | 0.127 | 27.8 | 91 | -0.02 | 5.70 |
| 45 | t | 1-Methylnaphthalene | 0.782 | 0.622 | 20.5 | 106 | 0.00 | 5.99 |
| 46 | t | Dimethylnaphthalene | 0.711 | 0.599 | 15.8 | 110 | 0.00 | 6.39 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 121 | -0.01 | 6.76 |
| 53 | t | Biphenyl | 1.436 | 1.232 | 14.2 | 110 | 0.00 | 6.26 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 109 | -0.02 | 8.54 |
| 82 | t | Octadecane | 0.446 | 0.417 | 6.5 | 103 | -0.01 | 8.44 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 96 | -0.02 | 16.72 |
| 99 | t | 7,12-Dimethylbenz(a)anthr | 0.543 | 0.455 | 16.2 | 75 | -0.02 | 15.98 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107679a.D MP4769.M Thu Sep 22 16:05:15 2016

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EP4787-CC4769
**Lab FileID:** P107974.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4787\P107974.D Vial: 2
Acq On : 6 Oct 2016 10:09 am Operator: robertl1
Sample : CC4769-25 Inst : MSP
Misc : OP97024,EP4787 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Oct 06 14:50:26 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 66 | -0.02 | 4.46 |
| 2 | t | 1,4-Dioxane | 0.751 | 0.689 | 8.3 | 59 | 0.00 | 1.98 |
| 3 | t | Pyridine | 1.752 | 1.643 | 6.2 | 55 | 0.01 | 2.33 |
| 4 | t | N-Nitrosodimethylamine | 0.840 | 0.831 | 1.1 | 62 | 0.01 | 2.31 |
| 5 | S | 2-Fluorophenol | 1.442 | 1.494 | -3.6 | 63 | 0.05 | 3.58 |
| 6 | t | Indene | 2.393 | 2.417 | -1.0 | 66 | -0.02 | 4.65 |
| 7 | t | Cumene | 3.647 | 3.866 | -6.0 | 67 | -0.02 | 3.86 |
| 8 | S | Phenol-d5 | 1.906 | 1.845 | 3.2 | 61 | 0.04 | 4.29 |
| 9 | t | Phenol | 2.164 | 1.886 | 12.8 | 55 | 0.05 | 4.30 |
| 10 | t | Aniline | 2.282 | 2.304 | -1.0 | 66 | 0.00 | 4.23 |
| 11 | t | bis(2-Chloroethyl)ether | 1.386 | 1.502 | -8.4 | 71 | -0.01 | 4.27 |
| 12 | t | 2-Chlorophenol | 1.407 | 1.407 | 0.0 | 64 | 0.01 | 4.35 |
| 13 | t | Decane | 1.338 | 1.353 | -1.1 | 68 | -0.02 | 4.34 |
| 14 | t | 1,3-Dichlorobenzene | 1.535 | 1.553 | -1.2 | 66 | -0.02 | 4.42 |
| 15 | t | 1,4-Dichlorobenzene | 1.486 | 1.524 | -2.6 | 67 | -0.02 | 4.47 |
| 16 | t | Benzyl alcohol | 0.880 | 0.896 | -1.8 | 62 | 0.00 | 4.59 |
| 17 | t | 1,2-Dichlorobenzene | 1.430 | 1.512 | -5.7 | 67 | -0.02 | 4.58 |
| 18 | t | Acetophenone | 2.008 | 2.060 | -2.6 | 67 | -0.03 | 4.76 |
| 19 | t | 2-Methylphenol | 1.324 | 1.402 | -5.9 | 69 | -0.07 | 4.71 |
| 20 | t | 2,2'-oxybis(1-Chloropropa | 0.433 | 0.436 | -0.7 | 66 | -0.03 | 4.66 |
| 21 | t | 3&4-Methylphenol | 1.431 | 1.435 | -0.3 | 65 | -0.07 | 4.82 |
| 22 | | n-Nitroso-di-n-propylamin | 1.164 | 1.148 | 1.4 | 64 | -0.01 | 4.76 |
| 23 | t | Hexachloroethane | 0.571 | 0.587 | -2.8 | 66 | -0.01 | 4.82 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 65 | -0.02 | 5.37 |
| 25 | S | Nitrobenzene-d5 | 0.472 | 0.487 | -3.2 | 64 | -0.01 | 4.87 |
| 26 | t | Nitrobenzene | 0.458 | 0.473 | -3.3 | 66 | -0.01 | 4.88 |
| 27 | t | Quinoline | 0.780 | 0.791 | -1.4 | 64 | -0.02 | 5.63 |
| 28 | t | Isophorone | 0.840 | 0.858 | -2.1 | 64 | -0.02 | 5.05 |
| 29 | t | 2-Nitrophenol | 0.201 | 0.215 | -7.0 | 65 | -0.01 | 5.11 |
| 30 | t | 2,4-Dimethylphenol | 0.379 | 0.425 | -12.1 | 73 | 0.00 | 5.17 |
| 31 | t | Benzoic acid | 0.286 | 0.242 | 15.4 | 57 | 0.01 | 5.29 |
| 32 | t | bis(2-Chloroethoxy)methan | 0.459 | 0.459 | 0.0 | 62 | -0.02 | 5.20 |
| 33 | t | 2,4-Dichlorophenol | 0.316 | 0.331 | -4.7 | 64 | 0.01 | 5.32 |
| 34 | | 2,6-Dichlorophenol | 0.300 | 0.317 | -5.7 | 66 | 0.00 | 5.45 |
| 35 | | 1,3,5-Trichlorobenzene | 0.372 | 0.397 | -6.7 | 67 | -0.02 | 5.11 |
| 36 | t | 1,2,4-Trichlorobenzene | 0.358 | 0.359 | -0.3 | 63 | -0.02 | 5.34 |
| 37 | | 1,2,3-Trichlorobenzene | 0.349 | 0.350 | -0.3 | 63 | -0.02 | 5.50 |
| 38 | t | Naphthalene | 1.039 | 1.069 | -2.9 | 65 | -0.02 | 5.39 |
| 39 | t | 4-Chloroaniline | 0.453 | 0.471 | -4.0 | 65 | -0.01 | 5.44 |
| 40 | t | 2,3-Dichloroaniline | 0.405 | 0.405 | 0.0 | 64 | -0.01 | 6.09 |
| 41 | t | Caprolactam | 0.176 | 0.171 | 2.8 | 61 | 0.00 | 5.70 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EP4787-CC4769
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** P107974.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 42 | t | Hexachlorobutadiene | 0.221 | 0.221 | 0.0 | 63 | -0.02 | 5.47 |
| 43 | t | 4-Chloro-3-methylphenol | 0.370 | 0.389 | -5.1 | 62 | 0.02 | 5.83 |
| 44 | t | 2-Methylnaphthalene | 0.626 | 0.637 | -1.8 | 64 | -0.02 | 5.88 |
| 45 | t | 1-Methylnaphthalene | 0.782 | 0.782 | 0.0 | 62 | -0.02 | 5.95 |
| 46 | t | Dimethylnaphthalene | 0.711 | 0.729 | -2.5 | 65 | -0.02 | 6.35 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 62 | -0.03 | 6.71 |
| | | | True | Calc. | % Drift | | | |
| 48 | t | Hexachlorocyclopentadiene | 50.000 | 37.390 | 25.2# | 47 | -0.03 | 5.99 |
| | | | AvgRF | CCRF | % Dev | | | |
| 49 | t | 2,4,6-Trichlorophenol | 0.349 | 0.374 | -7.2 | 64 | -0.04 | 6.11 |
| 50 | t | 2,4,5-Trichlorophenol | 0.375 | 0.375 | 0.0 | 61 | -0.01 | 6.17 |
| 51 | S | 2-Fluorobiphenyl | 1.302 | 1.329 | -2.1 | 65 | -0.02 | 6.14 |
| 52 | t | 2-Chloronaphthalene | 1.042 | 1.081 | -3.7 | 64 | -0.02 | 6.24 |
| 53 | t | Biphenyl | 1.436 | 1.486 | -3.5 | 64 | -0.02 | 6.22 |
| 54 | t | 2-Nitroaniline | 0.405 | 0.426 | -5.2 | 62 | 0.00 | 6.35 |
| 55 | t | Dimethylphthalate | 1.217 | 1.278 | -5.0 | 63 | -0.02 | 6.47 |
| 56 | t | Acenaphthylene | 1.706 | 1.772 | -3.9 | 63 | -0.02 | 6.59 |
| 57 | t | 2,6-Dinitrotoluene | 0.290 | 0.309 | -6.6 | 63 | -0.02 | 6.53 |
| 58 | t | 3-Nitroaniline | 0.320 | 0.331 | -3.4 | 61 | 0.00 | 6.70 |
| 59 | t | Acenaphthene | 1.101 | 1.151 | -4.5 | 63 | -0.03 | 6.74 |
| | | | True | Calc. | % Drift | | | |
| 60 | t | 2,4-Dinitrophenol | 50.000 | 44.315 | 11.4 | 57 | 0.00 | 6.80 |
| 61 | t | 4-Nitrophenol | 25.000 | 22.779 | 8.9 | 57 | 0.08 | 6.99 |
| | | | AvgRF | CCRF | % Dev | | | |
| 62 | t | Dibenzofuran | 1.552 | 1.669 | -7.5 | 66 | -0.03 | 6.91 |
| 63 | t | 2,4-Dinitrotoluene | 0.359 | 0.413 | -15.0 | 64 | -0.02 | 6.92 |
| 64 | | 2,3,4,6-Tetrachlorophenol | 0.323 | 0.305 | 5.6 | 55 | 0.00 | 7.06 |
| 65 | t | Diethylphthalate | 1.232 | 1.318 | -7.0 | 64 | -0.03 | 7.14 |
| 66 | t | Fluorene | 1.295 | 1.371 | -5.9 | 64 | -0.03 | 7.26 |
| 67 | t | 4-Chlorophenyl-phenylethe | 0.666 | 0.692 | -3.9 | 63 | -0.03 | 7.26 |
| 68 | t | 4-Nitroaniline | 0.303 | 0.335 | -10.6 | 63 | 0.00 | 7.33 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 63 | -0.04 | 8.47 |
| | | | True | Calc. | % Drift | | | |
| 70 | t | 4,6-Dinitro-2-methylpheno | 25.000 | 23.151 | 7.4 | 59 | -0.02 | 7.35 |
| | | | AvgRF | CCRF | % Dev | | | |
| 71 | t | n-Nitrosodiphenylamine | 0.541 | 0.536 | 0.9 | 60 | -0.03 | 7.40 |
| 72 | t | 1,2-Diphenylhydrazine | 0.764 | 0.779 | -2.0 | 62 | -0.04 | 7.44 |
| 73 | S | 2,4,6-Tribromophenol | 0.096 | 0.096 | 0.0 | 60 | -0.03 | 7.55 |
| 74 | t | 4-Bromophenyl-phenylether | 0.230 | 0.235 | -2.2 | 62 | -0.04 | 7.85 |
| 75 | t | Hexachlorobenzene | 0.232 | 0.221 | 4.7 | 60 | -0.04 | 7.94 |
| | | | True | Calc. | % Drift | | | |
| 76 | t | Pentachlorophenol | 50.000 | 39.427 | 21.1# | 48 | -0.02 | 8.25 |
| | | | AvgRF | CCRF | % Dev | | | |
| 77 | t | Phenanthrene | 1.057 | 1.065 | -0.8 | 62 | -0.04 | 8.50 |
| 78 | t | Anthracene | 1.092 | 1.101 | -0.8 | 61 | -0.04 | 8.58 |
| 79 | t | Carbazole | 1.054 | 1.087 | -3.1 | 62 | -0.02 | 8.88 |
| 80 | t | Di-n-butylphthalate | 1.140 | 1.282 | -12.5 | 64 | -0.06 | 9.50 |
| 81 | t | Fluoranthene | 1.240 | 1.292 | -4.2 | 61 | -0.05 | 10.57 |
| 82 | t | Octadecane | 0.446 | 0.458 | -2.7 | 61 | -0.06 | 8.35 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EP4787-CC4769
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** P107974.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 62 | -0.04 | 13.61 |
| 84 | t | Pyrene | 1.299 | 1.313 | -1.1 | 61 | -0.04 | 11.00 |
| 85 | S | Terphenyl-d14 | 0.863 | 0.885 | -2.5 | 62 | -0.05 | 11.40 |
| 86 | t | Butylbenzylphthalate | 0.507 | 0.566 | -11.6 | 64 | -0.05 | 12.55 |
| 87 | t | Benzo[a]anthracene | 1.186 | 1.199 | -1.1 | 62 | -0.04 | 13.58 |
| 88 | t | 3,3'-Dichlorobenzidine | 0.395 | 0.395 | 0.0 | 59 | -0.03 | 13.64 |
| 89 | t | Chrysene | 1.122 | 1.092 | 2.7 | 60 | -0.04 | 13.66 |
| 90 | t | bis(2-Ethylhexyl)phthalat | 0.675 | 0.755 | -11.9 | 64 | -0.06 | 13.94 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 63 | -0.05 | 16.63 |
| 92 | t | Di-n-octylphthalate | 1.203 | 1.379 | -14.6 | 65 | -0.02 | 15.36 |
| 93 | t | Benzo[b]fluoranthene | 1.272 | 1.220 | 4.1 | 59 | -0.05 | 15.89 |
| 94 | t | Benzo[k]fluoranthene | 1.191 | 1.145 | 3.9 | 59 | -0.07 | 15.94 |
| 95 | t | Benzo[a]pyrene | 1.132 | 1.118 | 1.2 | 60 | -0.05 | 16.52 |
| 96 | t | Indeno[1,2,3-cd]pyrene | 1.018 | 1.063 | -4.4 | 62 | -0.05 | 18.58 |
| 97 | t | Dibenz(a,h)acridine | 0.914 | 0.938 | -2.6 | 60 | -0.06 | 18.21 |
| 98 | t | Dibenz[a,h]anthracene | 1.006 | 1.025 | -1.9 | 63 | -0.05 | 18.63 |
| 99 | t | 7,12-Dimethylbenz(a)anthr | 0.543 | 0.583 | -7.4 | 63 | -0.08 | 15.88 |
| 100 | t | Benzo[g,h,i]perylene | 1.108 | 1.071 | 3.3 | 58 | -0.05 | 19.01 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107680a.D MP4769.M Thu Oct 06 15:50:36 2016

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EP4787-CC4770
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** P107975.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\EP4787\P107975.D Vial: 3
Acq On : 6 Oct 2016 10:36 am Operator: robertl1
Sample : CC4770-25 Inst : MSP
Misc : OP97024,EP4787 Multiplr: 1.00
MS Integration Params: rteint.p

Method : C:\MSDCHEM\1\METHODS\MP4769.M (RTE Integrator)
Title : Semi Volatile Extractables by GC/MS
Last Update : Thu Oct 06 14:50:26 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 48% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 101 I | 1,4-Dichlorobenzene-d4b | 1.000 | 1.000 | 0.0 | 71 | -0.02 | 4.46 |
| | | True | Calc. | % Drift | | | |
| 102 | Benzaldehyde | 25.000 | 27.059 | -8.2 | 71 | 0.03 | 4.14 |
| | | AvgRF | CCRF | % Dev | | | |
| 103 I | Phenanthrene-d10b | 1.000 | 1.000 | 0.0 | 69 | -0.04 | 8.47 |
| 104 | Atrazine | 0.241 | 0.260 | -7.9 | 72 | 0.04 | 8.10 |
| 105 I | Chrysene-d12b | 1.000 | 1.000 | 0.0 | 69 | -0.05 | 13.60 |
| 106 | Benzidine | 0.571 | 0.540 | 5.4 | 57 | 0.06 | 10.92 |
| 107 I | Naphthalene-d8b | 1.000 | 1.000 | 0.0 | 70 | -0.02 | 5.37 |
| 108 | Hydroquinone | 0.357 | 0.423 | -18.5 | 77 | 0.04 | 5.74 |
| 109 I | Acenaphthene-d10b | 1.000 | 1.000 | 0.0 | 70 | -0.03 | 6.71 |
| 110 | 1,2,4,5-Tetrachlorobenzen | 0.660 | 0.659 | 0.2 | 73 | 0.03 | 6.00 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
P107680a.D MP4769.M Thu Oct 06 15:50:37 2016

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5695-ICC5695
**Lab FileID:** Z114095.D

Response Factor Report MSZ

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 07:33:53 2016
Response via : Initial Calibration

Calibration Files
100 =z114094.D 80 =z114096.D 50 =z114095.D 25 =z114097.D
10 =z114098.D 5 =z114099.D 2 =z114092a.D 1 =z114093.D

| Compound | 100 | 80 | 50 | 25 | 10 | 5 | 2 | 1 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 1) I 1,4-Dichlorobenzene-d | ISTD | | | | | | | | | |
| 2) 1,4-Dioxane | 0.648 | 0.640 | 0.689 | 0.639 | 0.650 | 0.692 | 0.771 | 0.676 | 0.676 | 6.53 |
| 3) Pyridine | 1.604 | 1.658 | 1.794 | 1.631 | 1.583 | 1.952 | 1.817 | 1.770 | 1.726 | 7.43 |
| 4) N-Nitrosodim | 0.964 | 0.955 | 1.035 | 0.980 | 0.990 | 1.094 | 0.994 | 0.968 | 0.997 | 4.62 |
| 5) 2-Fluorophen | 1.371 | 1.385 | 1.501 | 1.444 | 1.424 | 1.566 | 1.441 | 1.422 | 1.444 | 4.36 |
| 6) Indene | 1.760 | 1.867 | 2.155 | 2.213 | 2.391 | 2.777 | 2.523 | 2.565 | 2.281 | 15.37 |
| 7) Cumene | 2.896 | 3.083 | 3.490 | 3.412 | 3.540 | 3.943 | 3.598 | 3.551 | 3.439 | 9.37 |
| 8) Phenol-d5 | 1.677 | 1.715 | 1.914 | 1.850 | 1.875 | 2.113 | 1.906 | 1.936 | 1.873 | 7.23 |
| 9) Phenol | 1.594 | 1.716 | 1.984 | 2.004 | 2.092 | 2.382 | 2.157 | 2.203 | 2.017 | 12.76 |
| 10) Aniline | | 1.557 | 1.641 | 1.940 | 2.155 | 2.563 | 2.455 | 2.384 | 2.099 | 19.01 |
| 11) bis(2-Chloro | 1.152 | 1.179 | 1.317 | 1.296 | 1.330 | 1.526 | 1.413 | 1.421 | 1.329 | 9.41 |
| 12) 2-Chlorophen | 1.189 | 1.233 | 1.395 | 1.391 | 1.475 | 1.638 | 1.543 | 1.537 | 1.425 | 10.90 |
| 13) Decane | 0.754 | 0.801 | 0.912 | 0.925 | 0.999 | 1.139 | 1.186 | 1.148 | 0.983 | 16.63 |
| 14) 1,3-Dichloro | 1.249 | 1.300 | 1.471 | 1.446 | 1.571 | 1.743 | 1.652 | 1.620 | 1.506 | 11.44 |
| 15) 1,4-Dichloro | 1.206 | 1.247 | 1.418 | 1.395 | 1.495 | 1.648 | 1.598 | 1.579 | 1.448 | 11.21 |
| 16) Benzyl alcoh | 0.833 | 0.855 | 0.931 | 0.900 | 0.950 | 1.049 | 0.955 | 0.951 | 0.928 | 7.23 |
| 17) 1,2-Dichloro | 1.150 | 1.207 | 1.374 | 1.377 | 1.468 | 1.646 | 1.566 | 1.542 | 1.416 | 12.28 |
| 18) Acetophenone | 1.481 | 1.528 | 1.779 | 1.799 | 2.002 | 2.270 | 2.090 | 2.186 | 1.892 | 15.52 |
| 19) 2-Methylphen | 0.941 | 1.000 | 1.161 | 1.208 | 1.316 | 1.457 | 1.359 | 1.397 | 1.230 | 15.23 |
| 20) 2,2'-oxybis( | 0.346 | 0.359 | 0.394 | 0.399 | 0.431 | 0.484 | 0.427 | 0.429 | 0.409 | 10.78 |
| 21) 3&4-Methylph | 0.986 | 1.049 | 1.217 | 1.237 | 1.358 | 1.570 | 1.430 | 1.460 | 1.288 | 15.79 |
| 22) n-Nitroso-di | 0.722 | 0.751 | 0.876 | 0.907 | 1.012 | 1.225 | 1.126 | 1.176 | 0.974 | 19.62 |
| 23) Hexachloroet | 0.429 | 0.443 | 0.506 | 0.486 | 0.508 | 0.578 | 0.511 | 0.532 | 0.499 | 9.52 |
| 24) I Naphthalene-d8 | ISTD | | | | | | | | | |
| 25) Nitrobenzene | 0.341 | 0.345 | 0.389 | 0.370 | 0.392 | 0.435 | 0.412 | 0.421 | 0.388 | 8.87 |
| 26) Nitrobenzene | 0.330 | 0.333 | 0.386 | 0.377 | 0.399 | 0.447 | 0.429 | 0.429 | 0.391 | 11.16 |
| 27) Quinoline | 0.669 | 0.666 | 0.747 | 0.708 | 0.736 | 0.851 | 0.768 | 0.798 | 0.743 | 8.52 |
| 28) Isophorone | 0.631 | 0.640 | 0.715 | 0.710 | 0.735 | 0.855 | 0.796 | 0.813 | 0.737 | 10.89 |
| 29) 2-Nitropheno | 0.173 | 0.178 | 0.202 | 0.193 | 0.189 | 0.214 | 0.187 | 0.180 | 0.189 | 7.09 |
| 30) 2,4-Dimethyl | 0.298 | 0.306 | 0.331 | 0.308 | 0.327 | 0.364 | 0.333 | 0.359 | 0.328 | 7.38 |
| 31) Benzoic Acid | 0.293 | 0.289 | 0.314 | 0.261 | 0.226 | 0.236 | 0.173 | | 0.256 | 18.87 |
| 32) bis(2-Chloro | 0.355 | 0.361 | 0.410 | 0.393 | 0.422 | 0.483 | 0.458 | 0.459 | 0.418 | 11.25 |
| 33) 2,4-Dichloro | 0.248 | 0.255 | 0.293 | 0.285 | 0.302 | 0.337 | 0.312 | 0.303 | 0.292 | 10.04 |
| 34) 2,6-Dichloro | 0.225 | 0.229 | 0.268 | 0.263 | 0.285 | 0.315 | 0.297 | 0.306 | 0.273 | 12.36 |
| 35) 1,3,5-Trichl | 0.259 | 0.273 | 0.316 | 0.314 | 0.338 | 0.402 | 0.351 | 0.364 | 0.327 | 14.38 |
| 36) 1,2,4-Trichl | 0.262 | 0.266 | 0.308 | 0.303 | 0.317 | 0.372 | 0.345 | 0.350 | 0.315 | 12.39 |
| 37) 1,2,3-Trichl | 0.243 | 0.250 | 0.294 | 0.291 | 0.310 | 0.366 | 0.340 | 0.336 | 0.304 | 14.29 |
| 38) Naphthalene | 0.817 | 0.848 | 0.978 | 0.956 | 1.028 | 1.191 | 1.102 | 1.140 | 1.008 | 13.30 |
| 39) 4-Chloroanil | 0.338 | 0.352 | 0.403 | 0.408 | 0.446 | 0.516 | 0.469 | 0.484 | 0.427 | 14.72 |
| 40) 2,3-Dichloro | 0.285 | 0.291 | 0.341 | 0.338 | 0.360 | 0.424 | 0.388 | 0.407 | 0.354 | 14.31 |
| 41) Caprolactam | 0.131 | 0.130 | 0.136 | 0.129 | 0.136 | 0.153 | 0.149 | 0.164 | 0.141 | 9.11 |
| 42) Hexachlorobu | 0.138 | 0.142 | 0.168 | 0.161 | 0.170 | 0.200 | 0.172 | 0.188 | 0.167 | 12.39 |
| 43) 4-Chloro-3-m | 0.284 | 0.291 | 0.336 | 0.318 | 0.320 | 0.378 | 0.320 | 0.355 | 0.325 | 9.54 |
| 44) 2-Methylnaph | 0.449 | 0.467 | 0.549 | 0.541 | 0.560 | 0.656 | 0.597 | 0.590 | 0.551 | 12.33 |
| 45) 1-Methylnaph | 0.462 | 0.486 | 0.562 | 0.561 | 0.586 | 0.696 | 0.633 | 0.644 | 0.579 | 13.72 |

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5695-ICC5695
**Lab FileID:** Z114095.D

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 46) | Dimethylnaph | 0.474 | 0.494 | 0.565 | 0.566 | 0.601 | 0.705 | 0.634 | 0.649 | 0.586 | 13.32 |
| 47) | I Acenaphthene-d10 | ISTD | | | | | | | | | |
| 48) | Hexachlorocy | 0.238 | 0.248 | 0.291 | 0.289 | 0.312 | 0.342 | 0.293 | 0.285 | 0.287 | 11.52 |
| 49) | 2,4,6-Trichl | 0.260 | 0.270 | 0.318 | 0.315 | 0.348 | 0.409 | 0.362 | 0.350 | 0.329 | 14.97 |
| 50) | 2,4,5-Trichl | 0.313 | 0.316 | 0.359 | 0.350 | 0.369 | 0.431 | 0.386 | 0.363 | 0.361 | 10.54 |
| 51) | 2-Fluorobiph | 0.911 | 0.954 | 1.138 | 1.121 | 1.238 | 1.458 | 1.355 | 1.338 | 1.189 | 16.34 |
| 52) | 2-Chloronaph | 0.796 | 0.820 | 0.968 | 0.954 | 1.052 | 1.253 | 1.135 | 1.169 | 1.019 | 16.08 |
| 53) | Biphenyl | 1.049 | 1.092 | 1.314 | 1.290 | 1.411 | 1.653 | 1.534 | 1.562 | 1.363 | 16.05 |
| 54) | 2-Nitroanili | 0.283 | 0.286 | 0.325 | 0.307 | 0.318 | 0.353 | 0.324 | 0.306 | 0.313 | 7.27 |
| 55) | Dimethylphth | 1.013 | 1.047 | 1.216 | 1.162 | 1.229 | 1.460 | 1.334 | 1.286 | 1.219 | 12.05 |
| 56) | Acenaphthyle | 1.392 | 1.464 | 1.731 | 1.699 | 1.823 | 2.147 | 1.949 | 1.930 | 1.767 | 14.28 |
| 57) | 2,6-Dinitrot | 0.237 | 0.244 | 0.278 | 0.251 | 0.254 | 0.289 | 0.250 | 0.204 | 0.251 | 10.24 |
| 58) | 3-Nitroanili | 0.302 | 0.306 | 0.343 | 0.324 | 0.330 | 0.367 | 0.312 | 0.301 | 0.323 | 7.13 |
| 59) | Acenaphthene | 0.816 | 0.850 | 1.004 | 0.970 | 1.052 | 1.251 | 1.132 | 1.149 | 1.028 | 14.52 |
| 60) | 2,4-Dinitrop | 0.150 | 0.152 | 0.162 | 0.142 | 0.115 | 0.106 | 0.044 | | 0.125 | 32.70 |
| | ---- Quadratic regression ---- Coefficient = 0.9990 | | | | | | | | | | |
| | Response Ratio = -0.02041 + 0.17438 *A + -0.00409 *A^2 | | | | | | | | | | |
| 61) | 4-Nitropheno | 0.164 | 0.165 | 0.185 | 0.170 | 0.170 | 0.190 | 0.147 | 0.146 | 0.167 | 9.43 |
| 62) | Dibenzofuran | 1.140 | 1.199 | 1.428 | 1.415 | 1.535 | 1.808 | 1.623 | 1.668 | 1.477 | 15.52 |
| 63) | 2,4-Dinitrot | 0.314 | 0.328 | 0.377 | 0.352 | 0.351 | 0.395 | 0.317 | 0.252 | 0.336 | 13.09 |
| 64) | 2,3,4,6-Tetr | 0.258 | 0.260 | 0.300 | 0.285 | 0.296 | 0.331 | 0.278 | 0.274 | 0.285 | 8.39 |
| 65) | Diethylphtha | 1.047 | 1.078 | 1.251 | 1.204 | 1.269 | 1.494 | 1.284 | 1.295 | 1.240 | 11.21 |
| 66) | Fluorene | 0.878 | 0.936 | 1.126 | 1.111 | 1.253 | 1.505 | 1.326 | 1.316 | 1.182 | 17.79 |
| 67) | 4-Chlorophen | 0.405 | 0.430 | 0.508 | 0.505 | 0.561 | 0.668 | 0.588 | 0.576 | 0.530 | 16.30 |
| 68) | 4-Nitroanili | 0.291 | 0.311 | 0.345 | 0.329 | 0.335 | 0.391 | 0.332 | 0.308 | 0.330 | 9.14 |
| 69) | I Phenanthrene-d10 | ISTD | | | | | | | | | |
| 70) | 4,6-Dinitro- | 0.120 | 0.122 | 0.133 | 0.119 | 0.103 | 0.101 | | | 0.116 | 10.61 |
| 71) | n-Nitrosodip | 0.417 | 0.432 | 0.506 | 0.478 | 0.516 | 0.598 | 0.550 | 0.569 | 0.508 | 12.58 |
| 72) | 1,2-Diphenyl | 0.608 | 0.631 | 0.750 | 0.719 | 0.775 | 0.885 | 0.832 | 0.858 | 0.757 | 13.39 |
| 73) | 2,4,6-Tribro | 0.096 | 0.097 | 0.110 | 0.104 | 0.104 | 0.116 | 0.102 | 0.095 | 0.103 | 7.18 |
| 74) | 4-Bromopheny | 0.166 | 0.169 | 0.197 | 0.184 | 0.199 | 0.219 | 0.195 | 0.196 | 0.191 | 9.03 |
| 75) | Hexachlorobe | 0.179 | 0.183 | 0.212 | 0.200 | 0.217 | 0.248 | 0.222 | 0.229 | 0.211 | 11.05 |
| 76) | Pentachlorop | 0.122 | 0.127 | 0.145 | 0.136 | 0.140 | 0.149 | 0.125 | 0.096 | 0.130 | 12.96 |
| 77) | Phenanthrene | 0.793 | 0.824 | 0.981 | 0.920 | 1.001 | 1.172 | 1.062 | 1.079 | 0.979 | 13.19 |
| 78) | Anthracene | 0.806 | 0.841 | 0.986 | 0.957 | 1.029 | 1.220 | 1.091 | 1.107 | 1.005 | 13.79 |
| 79) | Carbazole | 0.842 | 0.881 | 1.018 | 0.973 | 1.056 | 1.218 | 1.094 | 1.117 | 1.025 | 12.16 |
| 80) | Di-n-butylph | 1.075 | 1.121 | 1.311 | 1.237 | 1.281 | 1.448 | 1.294 | 1.290 | 1.257 | 9.24 |
| 81) | Fluoranthene | 0.936 | 0.982 | 1.153 | 1.101 | 1.177 | 1.348 | 1.186 | 1.203 | 1.136 | 11.47 |
| 82) | Octadecane | 0.298 | 0.312 | 0.371 | 0.357 | 0.388 | 0.443 | 0.411 | 0.421 | 0.375 | 13.63 |
| 83) | I Chrysene-d12 | ISTD | | | | | | | | | |
| 84) | Pyrene | 1.264 | 1.258 | 1.389 | 1.320 | 1.374 | 1.556 | 1.458 | 1.478 | 1.387 | 7.61 |
| 85) | Terphenyl-d1 | 0.799 | 0.802 | 0.855 | 0.808 | 0.825 | 0.937 | 0.890 | 0.916 | 0.854 | 6.39 |
| 86) | Butylbenzylp | 0.661 | 0.660 | 0.712 | 0.651 | 0.640 | 0.718 | 0.662 | 0.644 | 0.668 | 4.46 |
| 87) | Benzo[a]anth | 1.085 | 1.094 | 1.174 | 1.122 | 1.152 | 1.344 | 1.264 | 1.303 | 1.192 | 8.28 |
| 88) | 3,3'-Dichlor | 0.386 | 0.391 | 0.428 | 0.414 | 0.415 | 0.464 | 0.420 | 0.423 | 0.418 | 5.73 |
| 89) | Chrysene | 1.028 | 1.024 | 1.108 | 1.056 | 1.113 | 1.280 | 1.170 | 1.146 | 1.116 | 7.63 |
| 90) | bis(2-Ethylh | 0.862 | 0.860 | 0.929 | 0.856 | 0.861 | 0.960 | 0.952 | 0.928 | 0.901 | 5.03 |
| 91) | I Perylene-d12 | ISTD | | | | | | | | | |
| 92) | Di-n-octylph | 1.335 | 1.392 | 1.554 | 1.522 | 1.530 | 1.723 | 1.658 | 1.734 | 1.556 | 9.35 |
| 93) | Benzo[b]fluo | 1.075 | 0.999 | 1.137 | 1.112 | 1.226 | 1.390 | 1.262 | 1.247 | 1.181 | 10.50 |
| 94) | Benzo[k]fluo | 0.758 | 0.899 | 1.001 | 1.010 | 1.118 | 1.312 | 1.193 | 1.254 | 1.068 | 17.51 |
| 95) | Benzo[a]pyre | 0.876 | 0.898 | 1.004 | 1.005 | 1.082 | 1.236 | 1.137 | 1.171 | 1.051 | 12.21 |
| 96) | Indeno[1,2,3 | 0.889 | 0.886 | 1.009 | 0.971 | 1.032 | 1.171 | 1.094 | 1.134 | 1.023 | 10.39 |
| 97) | Dibenz(a,h)a | 0.773 | 0.786 | 0.877 | 0.876 | 0.915 | 1.043 | 1.000 | 1.031 | 0.913 | 11.46 |
| 98) | Dibenz[a,h]a | 0.865 | 0.870 | 0.985 | 0.970 | 1.046 | 1.153 | 1.036 | 1.104 | 1.004 | 10.22 |

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5695-ICC5695
**Lab FileID:** Z114095.D

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| 99) | 7,12-Dimethy | 0.427 | 0.430 | 0.472 | 0.471 | 0.479 | 0.510 | 0.460 | 0.459 | 0.463 | 5.81 |
| 100) | Benzo[g,h,i] | 0.886 | 0.898 | 1.007 | 0.984 | 1.061 | 1.222 | 1.128 | 1.185 | 1.046 | 11.98 |

---

(#) = Out of Range ### Number of calibration levels exceeded format ###

MZ5695.M Thu Sep 15 07:39:20 2016 RTE

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5696-ICC5696
**Lab FileID:** Z114107.D

Response Factor Report MSZ

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 13:44:08 2016
Response via : Initial Calibration

Calibration Files
100 =z114104.D 80 =z114106.D 50 =z114107.D 25 =z114108.D
10 =z114109.D 5 =z114110.D 2 =z114105.D 1 =z114111.D

| Compound | 100 | 80 | 50 | 25 | 10 | 5 | 2 | 1 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 101) 1,4-Dichlorobenzene-d | ISTD | | | | | | | | | |
| 102) Benzaldehyde | 0.835 | 0.861 | 0.929 | 1.216 | 1.336 | 1.426 | 1.440 | | 1.149 | 23.32 |
| ---- Quadratic regression ---- Coefficient = 0.9963 | | | | | | | | | | |
| Response Ratio = 0.06284 + 1.03330 *A + -0.09365 *A^2 | | | | | | | | | | |
| 103) Phenanthrene-d10a | ISTD | | | | | | | | | |
| 104) 1-chloroocta | 0.268 | 0.267 | 0.266 | 0.297 | 0.309 | 0.333 | 0.328 | 0.303 | 0.296 | 9.13 |
| 105) o-terphenyl | 0.498 | 0.505 | 0.494 | 0.556 | 0.593 | 0.661 | 0.653 | 0.655 | 0.577 | 12.75 |
| 106) Atrazine | 0.106 | 0.105 | 0.103 | 0.112 | 0.117 | 0.125 | 0.125 | 0.110 | 0.113 | 7.81 |
| 107) Chrysene-d12a | ISTD | | | | | | | | | |
| 108) Benzidine | 0.379 | 0.511 | 0.715 | 0.695 | 0.586 | 0.437 | | | 0.554 | 24.65 |
| 109) Acenaphthene-d10a | ISTD | | | | | | | | | |
| 110) 1,2,4,5-Tetr | 0.478 | 0.490 | 0.487 | 0.550 | 0.600 | 0.671 | 0.657 | 0.655 | 0.573 | 14.47 |
| 111) I Naphthalene-d8a | ISTD | | | | | | | | | |
| 112) Hydroquinone | 0.415 | 0.416 | 0.395 | 0.417 | 0.403 | 0.378 | 0.373 | 0.283 | 0.385 | 11.57 |

(#) = Out of Range ### Number of calibration levels exceeded format ###

MZ5695.M Thu Sep 15 13:44:26 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5696-ICV5695
**Lab FileID:** Z114112.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114112.D Vial: 10
Acq On : 15 Sep 2016 11:18 am Operator: ariellec
Sample : icv5695-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 11:21:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 114 | 0.00 | 4.55 |
| 9 | t | Phenol | 2.017 | 1.948 | 3.4 | 112 | 0.00 | 4.29 |
| 12 | t | 2-Chlorophenol | 1.425 | 1.494 | -4.8 | 122 | 0.00 | 4.40 |
| 19 | t | 2-Methylphenol | 1.230 | 1.350 | -9.8 | 133 | 0.00 | 4.74 |
| 21 | t | 3&4-Methylphenol | 1.288 | 1.387 | -7.7 | 130 | 0.00 | 4.84 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 110 | 0.00 | 5.47 |
| 29 | t | 2-Nitrophenol | 0.189 | 0.204 | -7.9 | 111 | 0.00 | 5.20 |
| 30 | t | 2,4-Dimethylphenol | 0.328 | 0.388 | -18.3 | 129 | 0.00 | 5.23 |
| 31 | | Benzoic Acid | 0.256 | 0.249 | 2.7 | 87 | 0.05 | 5.32 |
| 33 | t | 2,4-Dichlorophenol | 0.292 | 0.298 | -2.1 | 112 | 0.00 | 5.37 |
| 34 | | 2,6-Dichlorophenol | 0.273 | 0.289 | -5.9 | 119 | 0.00 | 5.53 |
| 43 | t | 4-Chloro-3-methylphenol | 0.325 | 0.336 | -3.4 | 110 | 0.00 | 5.86 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 109 | 0.00 | 6.81 |
| 49 | t | 2,4,6-Trichlorophenol | 0.329 | 0.371 | -12.8 | 127 | 0.00 | 6.19 |
| 50 | t | 2,4,5-Trichlorophenol | 0.361 | 0.340 | 5.8 | 103 | 0.00 | 6.21 |
| | | | True | Calc. | % Drift | | | |
| 60 | t | 2,4-Dinitrophenol | 100.000 | 80.740 | 19.2 | 82 | 0.00 | 6.85 |
| | | | AvgRF | CCRF | % Dev | | | |
| 61 | t | 4-Nitrophenol | 0.167 | 0.181 | -8.4 | 106 | 0.00 | 6.91 |
| 64 | | 2,3,4,6-Tetrachlorophenol | 0.285 | 0.293 | -2.8 | 107 | 0.00 | 7.11 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 104 | 0.00 | 8.36 |
| 70 | t | 4,6-Dinitro-2-methylpheno | 0.116 | 0.130 | -12.1 | 102 | 0.00 | 7.37 |
| 76 | t | Pentachlorophenol | 0.130 | 0.158 | -21.5 | 112 | 0.00 | 8.14 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 11:37:43 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5696-ICV5695
**Lab FileID:** Z114113.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114113.D Vial: 11
Acq On : 15 Sep 2016 11:43 am Operator: ariellec
Sample : icv5695-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 11:21:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 90 | 0.00 | 4.56 |
| 3 | t | Pyridine | 1.726 | 1.782 | -3.2 | 89 | 0.09 | 2.48 |
| 10 | t | Aniline | 2.099 | 2.362 | -12.5 | 130 | 0.00 | 4.31 |
| 16 | t | Benzyl alcohol | 0.928 | 0.975 | -5.1 | 94 | 0.00 | 4.66 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 91 | 0.00 | 5.47 |
| 39 | t | 4-Chloroaniline | 0.427 | 0.448 | -4.9 | 101 | 0.00 | 5.52 |
| 44 | t | 2-Methylnaphthalene | 0.551 | 0.530 | 3.8 | 88 | 0.00 | 5.98 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 87 | 0.00 | 6.81 |
| 54 | t | 2-Nitroaniline | 0.313 | 0.323 | -3.2 | 87 | 0.00 | 6.42 |
| 58 | t | 3-Nitroaniline | 0.323 | 0.333 | -3.1 | 85 | 0.00 | 6.76 |
| 62 | t | Dibenzofuran | 1.477 | 1.495 | -1.2 | 91 | 0.00 | 6.99 |
| 68 | t | 4-Nitroaniline | 0.330 | 0.338 | -2.4 | 85 | 0.00 | 7.33 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 89 | 0.00 | 8.35 |
| 79 | t | Carbazole | 1.025 | 0.974 | 5.0 | 86 | 0.00 | 8.65 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 12:02:15 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5696-ICV5695
**Lab FileID:** Z114114.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114114.D Vial: 12
Acq On : 15 Sep 2016 12:09 pm Operator: ariellec
Sample : icv5695-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 11:21:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 125 | 0.00 | 4.55 |
| 5 | S | 2-Fluorophenol | 1.444 | 1.318 | 8.7 | 110 | 0.00 | 3.57 |
| 8 | S | Phenol-d5 | 1.873 | 1.669 | 10.9 | 109 | 0.00 | 4.28 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 125 | 0.00 | 5.47 |
| 25 | S | Nitrobenzene-d5 | 0.388 | 0.383 | 1.3 | 123 | 0.00 | 4.95 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 116 | 0.00 | 6.81 |
| 51 | S | 2-Fluorobiphenyl | 1.189 | 1.168 | 1.8 | 119 | 0.00 | 6.25 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 113 | 0.00 | 8.35 |
| 73 | S | 2,4,6-Tribromophenol | 0.103 | 0.095 | 7.8 | 98 | 0.00 | 7.56 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 123 | 0.00 | 12.13 |
| 85 | S | Terphenyl-d14 | 0.854 | 0.723 | 15.3 | 104 | 0.00 | 10.58 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 12:29:12 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5696-ICV5696
**Lab FileID:** Z114115A.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114115a.D Vial: 13
Acq On : 15 Sep 2016 12:35 pm Operator: ariellec
Sample : icv5696-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 13:44:08 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 107 | Chrysene-d12a | 1.000 | 1.000 | 0.0 | 88 | 0.00 | 12.13 |
| 108 | Benzidine | 0.554 | 0.391 | 29.4 | 135 | 0.00 | 10.20 |
| 109 | Acenaphthene-d10a | 1.000 | 1.000 | 0.0 | 96 | 0.00 | 6.81 |
| 110 | 1,2,4,5-Tetrachlorobenzen | 0.573 | 0.502 | 12.4 | 99 | 0.00 | 6.11 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 13:53:58 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5696-ICV5695
**Lab FileID:** Z114115.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114115.D Vial: 13
Acq On : 15 Sep 2016 12:35 pm Operator: ariellec
Sample : icv5695-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 13:44:08 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 112 | 0.00 | 4.55 |
| 4 | t | N-Nitrosodimethylamine | 0.997 | 0.944 | 5.3 | 102 | 0.00 | 2.36 |
| 11 | t | bis(2-Chloroethyl)ether | 1.329 | 1.496 | -12.6 | 128 | 0.00 | 4.36 |
| 14 | t | 1,3-Dichlorobenzene | 1.506 | 1.555 | -3.3 | 119 | 0.00 | 4.51 |
| 15 | t | 1,4-Dichlorobenzene | 1.448 | 1.452 | -0.3 | 115 | 0.00 | 4.57 |
| 17 | t | 1,2-Dichlorobenzene | 1.416 | 1.429 | -0.9 | 117 | 0.00 | 4.67 |
| 20 | t | 2,2'-oxybis(1-Chloropropa | 0.409 | 0.426 | -4.2 | 121 | 0.00 | 4.75 |
| 22 | t | n-Nitroso-di-n-propylamin | 0.974 | 0.956 | 1.8 | 123 | 0.00 | 4.84 |
| 23 | t | Hexachloroethane | 0.499 | 0.508 | -1.8 | 113 | 0.00 | 4.92 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 108 | 0.00 | 5.47 |
| 26 | t | Nitrobenzene | 0.391 | 0.383 | 2.0 | 107 | 0.00 | 4.97 |
| 28 | t | Isophorone | 0.737 | 0.709 | 3.8 | 107 | 0.00 | 5.14 |
| 32 | t | bis(2-Chloroethoxy)methan | 0.418 | 0.461 | -10.3 | 122 | 0.00 | 5.29 |
| 36 | t | 1,2,4-Trichlorobenzene | 0.315 | 0.318 | -1.0 | 112 | 0.00 | 5.43 |
| 38 | t | Naphthalene | 1.008 | 0.935 | 7.2 | 103 | 0.00 | 5.49 |
| 42 | t | Hexachlorobutadiene | 0.167 | 0.175 | -4.8 | 113 | 0.00 | 5.58 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 105 | 0.00 | 6.81 |
| 52 | t | 2-Chloronaphthalene | 1.019 | 1.100 | -7.9 | 119 | 0.00 | 6.35 |
| 55 | t | Dimethylphthalate | 1.219 | 1.175 | 3.6 | 101 | 0.00 | 6.58 |
| 56 | t | Acenaphthylene | 1.767 | 1.661 | 6.0 | 101 | 0.00 | 6.68 |
| 57 | t | 2,6-Dinitrotoluene | 0.251 | 0.253 | -0.8 | 96 | 0.00 | 6.62 |
| 59 | t | Acenaphthene | 1.028 | 0.977 | 5.0 | 102 | 0.00 | 6.84 |
| 63 | t | 2,4-Dinitrotoluene | 0.336 | 0.313 | 6.8 | 87 | 0.00 | 6.98 |
| 65 | t | Diethylphthalate | 1.240 | 1.169 | 5.7 | 98 | 0.00 | 7.21 |
| 66 | t | Fluorene | 1.182 | 1.038 | 12.2 | 97 | 0.00 | 7.32 |
| 67 | t | 4-Chlorophenyl-phenylethe | 0.530 | 0.499 | 5.8 | 103 | 0.00 | 7.32 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 105 | 0.00 | 8.36 |
| 71 | t | n-Nitrosodiphenylamine | 0.508 | 0.447 | 12.0 | 93 | 0.00 | 7.44 |
| 72 | t | 1,2-Diphenylhydrazine | 0.757 | 0.691 | 8.7 | 97 | 0.00 | 7.48 |
| 74 | t | 4-Bromophenyl-phenylether | 0.191 | 0.189 | 1.0 | 101 | 0.00 | 7.84 |
| 75 | t | Hexachlorobenzene | 0.211 | 0.204 | 3.3 | 101 | 0.00 | 7.92 |
| 77 | t | Phenanthrene | 0.979 | 0.893 | 8.8 | 96 | 0.00 | 8.39 |
| 78 | t | Anthracene | 1.005 | 0.898 | 10.6 | 96 | 0.00 | 8.45 |
| 80 | t | Di-n-butylphthalate | 1.257 | 1.172 | 6.8 | 94 | 0.00 | 9.17 |
| 81 | t | Fluoranthene | 1.136 | 1.014 | 10.7 | 93 | 0.00 | 9.97 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 12.13 |
| 84 | t | Pyrene | 1.387 | 1.301 | 6.2 | 91 | 0.00 | 10.29 |
| 86 | t | Butylbenzylphthalate | 0.668 | 0.660 | 1.2 | 90 | 0.00 | 11.37 |

# Initial Calibration Verification



**Job Number:** JC28902 **Sample:** EZ5696-ICV5695
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Z114115.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 87 | t | Benzo[a]anthracene | 1.192 | 1.080 | 9.4 | 89 | 0.00 | 12.12 |
| 89 | t | Chrysene | 1.116 | 1.000 | 10.4 | 87 | 0.00 | 12.17 |
| 90 | t | bis(2-Ethylhexyl)phthalat | 0.901 | 0.849 | 5.8 | 88 | 0.00 | 12.32 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 94 | 0.00 | 14.20 |
| 92 | t | Di-n-octylphthalate | 1.556 | 1.502 | 3.5 | 91 | 0.00 | 13.29 |
| 93 | t | Benzo[b]fluoranthene | 1.181 | 1.021 | 13.5 | 85 | 0.01 | 13.69 |
| 94 | t | Benzo[k]fluoranthene | 1.068 | 0.975 | 8.7 | 92 | 0.01 | 13.73 |
| 95 | t | Benzo[a]pyrene | 1.051 | 0.975 | 7.2 | 92 | 0.00 | 14.12 |
| 96 | t | Indeno[1,2,3-cd]pyrene | 1.023 | 0.970 | 5.2 | 91 | 0.01 | 15.52 |
| 98 | t | Dibenz[a,h]anthracene | 1.004 | 0.900 | 10.4 | 86 | 0.01 | 15.55 |
| 100 | t | Benzo[g,h,i]perylene | 1.046 | 0.939 | 10.2 | 88 | 0.02 | 15.84 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 13:49:24 2016 RTE

7.7.35

7

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5696-ICV5695
**Lab FileID:** Z114116.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114116.D Vial: 14
Acq On : 15 Sep 2016 1:01 pm Operator: ariellec
Sample : icv5695-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 11:21:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 113 | 0.00 | 4.55 |
| 2 | | 1,4-Dioxane | 0.676 | 0.594 | 12.1 | 97 | 0.00 | 2.07 |
| 6 | t | Indene | 2.281 | 2.370 | -3.9 | 124 | 0.00 | 4.74 |
| 7 | t | Cumene | 3.439 | 3.196 | 7.1 | 103 | 0.00 | 3.96 |
| 13 | t | Decane | 0.983 | 0.859 | 12.6 | 106 | 0.00 | 4.44 |
| 18 | t | Acetophenone | 1.892 | 1.907 | -0.8 | 121 | 0.00 | 4.84 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 114 | 0.00 | 5.47 |
| 27 | t | Quinoline | 0.743 | 0.677 | 8.9 | 104 | 0.00 | 5.72 |
| 40 | t | 2,3-Dichloroaniline | 0.354 | 0.311 | 12.1 | 104 | 0.00 | 6.19 |
| 41 | t | Caprolactam | 0.141 | 0.109 | 22.7 | 92 | 0.01 | 5.76 |
| 45 | t | 1-Methylnaphthalene | 0.579 | 0.510 | 11.9 | 104 | 0.00 | 6.05 |
| 46 | t | Dimethylnaphthalene | 0.586 | 0.546 | 6.8 | 110 | 0.00 | 6.45 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 107 | 0.00 | 6.81 |
| 48 | t | Hexachlorocyclopentadiene | 0.287 | 0.306 | -6.6 | 112 | 0.00 | 6.10 |
| 53 | t | Biphenyl | 1.363 | 1.338 | 1.8 | 108 | 0.00 | 6.32 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 100 | 0.00 | 8.35 |
| 82 | t | Octadecane | 0.375 | 0.394 | -5.1 | 106 | 0.00 | 8.27 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 99 | 0.00 | 14.19 |
| 99 | t | 7,12-Dimethylbenz(a)anthr | 0.463 | 0.470 | -1.5 | 98 | 0.00 | 13.69 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 13:39:37 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5696-ICV5696
**Lab FileID:** Z114116A.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114116a.D Vial: 14
Acq On : 15 Sep 2016 1:01 pm Operator: ariellec
Sample : icv5696-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 11:21:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 101 | 1,4-Dichlorobenzene-d4a | 1.000 | 1.000 | 0.0 | 97 | 0.00 | 4.55 |
| | | True | Calc. | % Drift | | | |
| 102 | Benzaldehyde | 50.000 | 57.642 | -15.3 | 113 | 0.00 | 4.22 |
| | | AvgRF | CCRF | % Dev | | | |
| 103 | Phenanthrene-d10a | 1.000 | 1.000 | 0.0 | 93 | 0.00 | 8.35 |
| 106 | Atrazine | 0.113 | 0.111 | 1.8 | 101 | 0.02 | 8.04 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 13:39:39 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5696-ICV5695
**Lab FileID:** Z114117.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114117.D Vial: 15
Acq On : 15 Sep 2016 1:26 pm Operator: ariellec
Sample : icv5695-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 13:44:08 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 83 I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 12.12 |
| 88 t | 3,3'-Dichlorobenzidine | 0.418 | 0.428 | -2.4 | 98 | 0.00 | 12.12 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 13:52:10 2016 RTE

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5696-ICV5696
**Lab FileID:** Z114118.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\ez5696\z114118.D Vial: 16
Acq On : 15 Sep 2016 1:52 pm Operator: ariellec
Sample : icv5696-50 Inst : MSZ
Misc : op96490,ez5696 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Sep 15 13:44:08 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 111 I | Naphthalene-d8a | 1.000 | 1.000 | 0.0 | 95 | 0.00 | 5.47 |
| 112 | Hydroquinone | 0.385 | 0.449 | -16.6 | 108 | 0.02 | 5.76 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Thu Sep 15 14:21:19 2016 RTE

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** EZ5729-CC5695
**Lab FileID:** Z114914.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\EZ5729\z114914.D Vial: 2
Acq On : 7 Oct 2016 10:11 am Operator: ashleyd
Sample : cc5695-50 Inst : MSZ
Misc : op97372,ez5729 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Oct 06 13:37:48 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1,4-Dichlorobenzene-d4 | 1.000 | 1.000 | 0.0 | 75 | -0.02 | 4.38 |
| 2 | | 1,4-Dioxane | 0.676 | 0.632 | 6.5 | 69 | -0.18 | 1.82 |
| 3 | t | Pyridine | 1.726 | 1.288 | 25.4# | 54 | 0.06 | 2.17 |
| 4 | t | N-Nitrosodimethylamine | 0.997 | 0.859 | 13.8 | 62 | -0.08 | 2.14 |
| 5 | S | 2-Fluorophenol | 1.444 | 1.300 | 10.0 | 65 | -0.03 | 3.45 |
| 6 | t | Indene | 2.281 | 2.355 | -3.2 | 82 | -0.01 | 4.57 |
| 7 | t | Cumene | 3.439 | 3.243 | 5.7 | 70 | -0.05 | 3.78 |
| 8 | S | Phenol-d5 | 1.873 | 1.676 | 10.5 | 66 | -0.04 | 4.18 |
| 9 | t | Phenol | 2.017 | 1.749 | 13.3 | 66 | 0.04 | 4.19 |
| 10 | t | Aniline | 2.099 | 1.458 | 30.5# | 67 | -0.01 | 4.15 |
| 11 | t | bis(2-Chloroethyl)ether | 1.329 | 1.259 | 5.3 | 72 | -0.02 | 4.19 |
| 12 | t | 2-Chlorophenol | 1.425 | 1.401 | 1.7 | 75 | 0.00 | 4.25 |
| 13 | t | Decane | 0.983 | 1.240 | -26.1# | 102 | -0.03 | 4.27 |
| 14 | t | 1,3-Dichlorobenzene | 1.506 | 1.457 | 3.3 | 74 | -0.02 | 4.34 |
| 15 | t | 1,4-Dichlorobenzene | 1.448 | 1.450 | -0.1 | 77 | -0.02 | 4.40 |
| 16 | t | Benzyl alcohol | 0.928 | 0.787 | 15.2 | 63 | 0.00 | 4.51 |
| 17 | t | 1,2-Dichlorobenzene | 1.416 | 1.413 | 0.2 | 77 | -0.01 | 4.51 |
| 18 | t | Acetophenone | 1.892 | 1.861 | 1.6 | 78 | 0.00 | 4.68 |
| 19 | t | 2-Methylphenol | 1.230 | 1.178 | 4.2 | 76 | -0.10 | 4.62 |
| 20 | t | 2,2'-oxybis(1-Chloropropa | 0.409 | 0.401 | 2.0 | 76 | 0.00 | 4.59 |
| 21 | t | 3&4-Methylphenol | 1.288 | 1.331 | -3.3 | 82 | 0.00 | 4.73 |
| 22 | t | n-Nitroso-di-n-propylamin | 0.974 | 0.973 | 0.1 | 83 | 0.00 | 4.69 |
| 23 | t | Hexachloroethane | 0.499 | 0.490 | 1.8 | 73 | -0.02 | 4.74 |
| 24 | I | Naphthalene-d8 | 1.000 | 1.000 | 0.0 | 81 | -0.02 | 5.31 |
| 25 | S | Nitrobenzene-d5 | 0.388 | 0.338 | 12.9 | 70 | -0.02 | 4.79 |
| 26 | t | Nitrobenzene | 0.391 | 0.329 | 15.9 | 69 | -0.02 | 4.81 |
| 27 | t | Quinoline | 0.743 | 0.739 | 0.5 | 80 | -0.06 | 5.57 |
| 28 | t | Isophorone | 0.737 | 0.632 | 14.2 | 71 | -0.03 | 4.97 |
| 29 | t | 2-Nitrophenol | 0.189 | 0.203 | -7.4 | 81 | -0.02 | 5.04 |
| 30 | t | 2,4-Dimethylphenol | 0.328 | 0.325 | 0.9 | 79 | -0.02 | 5.10 |
| 31 | | Benzoic Acid | 0.256 | 0.281 | -9.8 | 72 | 0.09 | 5.22 |
| 32 | t | bis(2-Chloroethoxy)methan | 0.418 | 0.366 | 12.4 | 72 | -0.02 | 5.13 |
| 33 | t | 2,4-Dichlorophenol | 0.292 | 0.281 | 3.8 | 77 | 0.01 | 5.24 |
| 34 | | 2,6-Dichlorophenol | 0.273 | 0.264 | 3.3 | 80 | 0.00 | 5.38 |
| 35 | t | 1,3,5-Trichlorobenzene | 0.327 | 0.311 | 4.9 | 80 | -0.03 | 5.04 |
| 36 | t | 1,2,4-Trichlorobenzene | 0.315 | 0.296 | 6.0 | 78 | -0.02 | 5.27 |
| 37 | t | 1,2,3-Trichlorobenzene | 0.304 | 0.289 | 4.9 | 80 | -0.01 | 5.42 |
| 38 | t | Naphthalene | 1.008 | 0.965 | 4.3 | 80 | -0.02 | 5.32 |
| 39 | t | 4-Chloroaniline | 0.427 | 0.377 | 11.7 | 75 | 0.00 | 5.38 |
| 40 | t | 2,3-Dichloroaniline | 0.354 | 0.356 | -0.6 | 84 | 0.00 | 6.02 |
| 41 | t | Caprolactam | 0.141 | 0.154 | -9.2 | 91 | 0.03 | 5.63 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EZ5729-CC5695
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Z114914.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 42 | t | Hexachlorobutadiene | 0.167 | 0.159 | 4.8 | 76 | -0.02 | 5.41 |
| 43 | t | 4-Chloro-3-methylphenol | 0.325 | 0.334 | -2.8 | 80 | 0.04 | 5.75 |
| 44 | t | 2-Methylnaphthalene | 0.551 | 0.578 | -4.9 | 85 | 0.00 | 5.81 |
| 45 | t | 1-Methylnaphthalene | 0.579 | 0.599 | -3.5 | 86 | 0.00 | 5.88 |
| 46 | t | Dimethylnaphthalene | 0.586 | 0.592 | -1.0 | 85 | -0.01 | 6.27 |
| 47 | I | Acenaphthene-d10 | 1.000 | 1.000 | 0.0 | 80 | -0.03 | 6.60 |
| 48 | t | Hexachlorocyclopentadiene | 0.287 | 0.227 | 20.9# | 63 | -0.02 | 5.92 |
| 49 | t | 2,4,6-Trichlorophenol | 0.329 | 0.328 | 0.3 | 83 | -0.02 | 6.03 |
| 50 | t | 2,4,5-Trichlorophenol | 0.361 | 0.349 | 3.3 | 78 | -0.02 | 6.08 |
| 51 | S | 2-Fluorobiphenyl | 1.189 | 1.164 | 2.1 | 82 | 0.00 | 6.08 |
| 52 | t | 2-Chloronaphthalene | 1.019 | 0.982 | 3.6 | 81 | 0.00 | 6.17 |
| 53 | t | Biphenyl | 1.363 | 1.363 | 0.0 | 83 | 0.00 | 6.15 |
| 54 | t | 2-Nitroaniline | 0.313 | 0.343 | -9.6 | 85 | 0.00 | 6.26 |
| 55 | t | Dimethylphthalate | 1.219 | 1.240 | -1.7 | 82 | -0.01 | 6.38 |
| 56 | t | Acenaphthylene | 1.767 | 1.740 | 1.5 | 81 | -0.01 | 6.49 |
| 57 | t | 2,6-Dinitrotoluene | 0.251 | 0.289 | -15.1 | 83 | 0.00 | 6.44 |
| 58 | t | 3-Nitroaniline | 0.323 | 0.333 | -3.1 | 78 | 0.00 | 6.59 |
| 59 | t | Acenaphthene | 1.028 | 1.087 | -5.7 | 87 | -0.02 | 6.64 |
| | | | True | Calc. | % Drift | | | |
| 60 | t | 2,4-Dinitrophenol | 100.000 | 116.299 | -16.3 | 90 | 0.02 | 6.69 |
| | | | AvgRF | CCRF | % Dev | | | |
| 61 | t | 4-Nitrophenol | 0.167 | 0.124 | 25.7# | 54 | -0.03 | 6.80 |
| 62 | t | Dibenzofuran | 1.477 | 1.502 | -1.7 | 84 | -0.02 | 6.79 |
| 63 | t | 2,4-Dinitrotoluene | 0.336 | 0.378 | -12.5 | 80 | -0.03 | 6.79 |
| 64 | | 2,3,4,6-Tetrachlorophenol | 0.285 | 0.280 | 1.8 | 75 | 0.00 | 6.92 |
| 65 | t | Diethylphthalate | 1.240 | 1.231 | 0.7 | 79 | -0.02 | 7.00 |
| 66 | t | Fluorene | 1.182 | 1.214 | -2.7 | 86 | -0.02 | 7.10 |
| 67 | t | 4-Chlorophenyl-phenylethe | 0.530 | 0.570 | -7.5 | 90 | -0.02 | 7.10 |
| 68 | t | 4-Nitroaniline | 0.330 | 0.329 | 0.3 | 76 | 0.02 | 7.16 |
| 69 | I | Phenanthrene-d10 | 1.000 | 1.000 | 0.0 | 83 | -0.03 | 8.11 |
| 70 | t | 4,6-Dinitro-2-methylpheno | 0.116 | 0.133 | -14.7 | 83 | 0.02 | 7.19 |
| 71 | t | n-Nitrosodiphenylamine | 0.508 | 0.505 | 0.6 | 83 | -0.01 | 7.22 |
| 72 | t | 1,2-Diphenylhydrazine | 0.757 | 0.603 | 20.3# | 67 | -0.03 | 7.26 |
| 73 | S | 2,4,6-Tribromophenol | 0.103 | 0.110 | -6.8 | 83 | -0.02 | 7.35 |
| 74 | t | 4-Bromophenyl-phenylether | 0.191 | 0.206 | -7.9 | 87 | -0.03 | 7.60 |
| 75 | t | Hexachlorobenzene | 0.211 | 0.227 | -7.6 | 89 | -0.02 | 7.68 |
| 76 | t | Pentachlorophenol | 0.130 | 0.116 | 10.8 | 67 | 0.00 | 7.92 |
| 77 | t | Phenanthrene | 0.979 | 0.988 | -0.9 | 84 | -0.01 | 8.14 |
| 78 | t | Anthracene | 1.005 | 1.012 | -0.7 | 85 | 0.00 | 8.20 |
| 79 | t | Carbazole | 1.025 | 1.011 | 1.4 | 83 | -0.03 | 8.42 |
| 80 | t | Di-n-butylphthalate | 1.257 | 1.267 | -0.8 | 80 | -0.03 | 8.89 |
| 81 | t | Fluoranthene | 1.136 | 1.172 | -3.2 | 85 | 0.00 | 9.70 |
| 82 | t | Octadecane | 0.375 | 0.446 | -18.9 | 100 | -0.04 | 8.01 |
| 83 | I | Chrysene-d12 | 1.000 | 1.000 | 0.0 | 92 | -0.02 | 11.84 |
| 84 | t | Pyrene | 1.387 | 1.273 | 8.2 | 85 | -0.03 | 10.02 |
| 85 | S | Terphenyl-d14 | 0.854 | 0.873 | -2.2 | 94 | -0.01 | 10.29 |
| 86 | t | Butylbenzylphthalate | 0.668 | 0.617 | 7.6 | 80 | -0.05 | 11.07 |
| 87 | t | Benzo[a]anthracene | 1.192 | 1.169 | 1.9 | 92 | -0.03 | 11.82 |
| 88 | t | 3,3'-Dichlorobenzidine | 0.418 | 0.429 | -2.6 | 92 | -0.02 | 11.84 |
| 89 | t | Chrysene | 1.116 | 1.064 | 4.7 | 89 | -0.02 | 11.88 |
| 90 | t | bis(2-Ethylhexyl)phthalat | 0.901 | 0.818 | 9.2 | 81 | -0.05 | 12.00 |
| 91 | I | Perylene-d12 | 1.000 | 1.000 | 0.0 | 90 | -0.03 | 13.91 |
| 92 | t | Di-n-octylphthalate | 1.556 | 1.450 | 6.8 | 84 | -0.04 | 12.98 |
| 93 | t | Benzo[b]fluoranthene | 1.181 | 1.157 | 2.0 | 92 | -0.02 | 13.40 |

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** EZ5729-CC5695
**Lab FileID:** Z114914.D

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 94 | t | Benzo[k]fluoranthene | 1.068 | 1.084 | -1.5 | 97 | -0.02 | 13.44 |
| 95 | t | Benzo[a]pyrene | 1.051 | 1.050 | 0.1 | 94 | -0.02 | 13.84 |
| 96 | t | Indeno[1,2,3-cd]pyrene | 1.023 | 1.104 | -7.9 | 98 | 0.00 | 15.23 |
| 97 | t | Dibenz(a,h)acridine | 0.913 | 0.993 | -8.8 | 102 | 0.00 | 14.97 |
| 98 | t | Dibenz[a,h]anthracene | 1.004 | 1.098 | -9.4 | 100 | 0.00 | 15.25 |
| 99 | t | 7,12-Dimethylbenz(a)anthr | 0.463 | 0.544 | -17.5 | 104 | -0.04 | 13.40 |
| 100 | t | Benzo[g,h,i]perylene | 1.046 | 1.090 | -4.2 | 97 | -0.07 | 15.54 |

---

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114107.D MZ5695.M Fri Oct 07 14:23:29 2016 RTE

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** EZ5729-CC5696
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** Z114915.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\EZ5729\z114915.D Vial: 3
Acq On : 7 Oct 2016 10:38 am Operator: ashleyd
Sample : cc5696-25 Inst : MSZ
Misc : op97372,ez5729 Multiplr: 1.00
MS Integration Params: RTEINT.P

Method : C:\MSDCHEM\1\METHODS\MZ5695.M (RTE Integrator)
Title : Semi Volatile GC/MS, ZB-5MS 15m x .25mm x .25um
Last Update : Thu Oct 06 13:37:48 2016
Response via : Multiple Level Calibration

Min. RRF : 0.050 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | R.T. |
|---|---|---|---|---|---|---|---|
| 101 | 1,4-Dichlorobenzene-d4a | 1.000 | 1.000 | 0.0 | 65 | -0.02 | 4.38 |
| | | True | Calc. | % Drift | | | |
| 102 | Benzaldehyde | 25.000 | 19.763 | 20.9# | 47 | -0.03 | 4.06 |
| | | AvgRF | CCRF | % Dev | | | |
| 103 | Phenanthrene-d10a | 1.000 | 1.000 | 0.0 | 74 | -0.03 | 8.10 |
| 104 | Atrazine | 0.113 | 0.119 | -5.3 | 79 | -0.01 | 7.81 |
| 105 | Chrysene-d12a | 1.000 | 1.000 | 0.0 | 81 | -0.03 | 11.83 |
| 106 | Benzidine | 0.554 | 0.577 | -4.2 | 66 | -0.04 | 9.93 |
| 107 | Acenaphthene-d10a | 1.000 | 1.000 | 0.0 | 74 | -0.03 | 6.60 |
| 108 | 1,2,4,5-Tetrachlorobenzen | 0.573 | 0.543 | 5.2 | 73 | -0.01 | 5.93 |
| 109 I | Naphthalene-d8a | 1.000 | 1.000 | 0.0 | 72 | -0.02 | 5.30 |
| 110 | Hydroquinone | 0.385 | 0.301 | 21.8# | 52 | 0.07 | 5.66 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
Copy of z114108.D MZ5695.M Fri Oct 07 14:23:17 2016 RTE

SGS ACCUTEST New Jersey

Section 8

## GC Semi-volatiles

### QC Data Summaries

8

Includes the following where applicable:

- Method Blank Summaries
- Blank Spike Summaries
- Matrix Spike and Duplicate Summaries
- Internal Standard Area Summaries
- DDT/Endrin Breakdown Checks
- GC Identification Summaries (Hits)
- Surrogate Recovery Summaries
- GC Surrogate Retention Time Summaries
- Initial and Continuing Calibration Summaries

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97541-MB1 | 5Y36627.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Y1211 |

**The QC reported here applies to the following samples:** **Method:** NJDEP EPH

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| | EPH (C9-C28) | ND | 6.7 | 3.5 | mg/kg | |
| | EPH (> C28-C40) | ND | 6.7 | 3.5 | mg/kg | |
| | Total EPH (C9-C40) | ND | 6.7 | 3.5 | mg/kg | |

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 84-15-1 | o-Terphenyl | 68% | 40-140% |
| 3386-33-2 | 1-Chlorooctadecane | 72% | 40-140% |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97541-MB1 | 5Z30028.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Z1032 |

**The QC reported here applies to the following samples:** **Method:** NJDEP EPH

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| | EPH (C9-C28) | ND | 6.7 | 3.5 | mg/kg | |
| | EPH (> C28-C40) | ND | 6.7 | 3.5 | mg/kg | |
| | Total EPH (C9-C40) | ND | 6.7 | 3.5 | mg/kg | |

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 84-15-1 | o-Terphenyl | 84% | 40-140% |
| 3386-33-2 | 1-Chlorooctadecane | 97% | 40-140% |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97538-MB1 | OA120269.D | 1 | 10/07/16 | VDT | 10/06/16 | OP97538 | GOA4139 |

**The QC reported here applies to the following samples:** **Method:** SW846 8151

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 94-75-7 | 2,4-D | ND | 17 | 7.5 | ug/kg | |
| 93-72-1 | 2,4,5-TP (Silvex) | ND | 3.3 | 1.2 | ug/kg | |
| 93-76-5 | 2,4,5-T | ND | 3.3 | 1.3 | ug/kg | |
| 75-99-0 | Dalapon | ND | 3.3 | 2.2 | ug/kg | |
| 1918-00-9 | Dicamba | ND | 3.3 | 1.7 | ug/kg | |
| 120-36-5 | Dichloroprop | ND | 17 | 4.7 | ug/kg | |
| 88-85-7 | Dinoseb | ND | 17 | 11 | ug/kg | |
| 94-74-6 | MCPA | ND | 1700 | 380 | ug/kg | |
| 93-65-2 | MCPP | ND | 1700 | 360 | ug/kg | |
| 87-86-5 | Pentachlorophenol | ND | 1.7 | 1.5 | ug/kg | |
| 94-82-6 | 2,4-DB | ND | 17 | 5.4 | ug/kg | |

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 19719-28-9 | 2,4-DCAA | 110% | 10-156% |
| 19719-28-9 | 2,4-DCAA | 114% | 10-156% |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97536-MB1 | 4G73353.D | 1 | 10/06/16 | DS | 10/06/16 | OP97536 | G4G1919 |

**The QC reported here applies to the following samples:** **Method:** SW846 8081B

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 309-00-2 | Aldrin | ND | 0.67 | 0.32 | ug/kg | |
| 319-84-6 | alpha-BHC | ND | 0.67 | 0.36 | ug/kg | |
| 319-85-7 | beta-BHC | ND | 0.67 | 0.42 | ug/kg | |
| 319-86-8 | delta-BHC | ND | 0.67 | 0.30 | ug/kg | |
| 58-89-9 | gamma-BHC (Lindane) | ND | 0.67 | 0.29 | ug/kg | |
| 5103-71-9 | alpha-Chlordane | ND | 0.67 | 0.32 | ug/kg | |
| 5103-74-2 | gamma-Chlordane | ND | 0.67 | 0.29 | ug/kg | |
| 57-74-9 | Chlordane (alpha and gamma) | ND | 0.67 | 0.29 | ug/kg | |
| 60-57-1 | Dieldrin | ND | 0.67 | 0.33 | ug/kg | |
| 72-54-8 | 4,4'-DDD | ND | 0.67 | 0.43 | ug/kg | |
| 72-55-9 | 4,4'-DDE | ND | 0.67 | 0.35 | ug/kg | |
| 50-29-3 | 4,4'-DDT | ND | 0.67 | 0.40 | ug/kg | |
| 72-20-8 | Endrin | ND | 0.67 | 0.31 | ug/kg | |
| 1031-07-8 | Endosulfan sulfate | ND | 0.67 | 0.27 | ug/kg | |
| 7421-93-4 | Endrin aldehyde | ND | 0.67 | 0.40 | ug/kg | |
| 959-98-8 | Endosulfan-I | ND | 0.67 | 0.35 | ug/kg | |
| 33213-65-9 | Endosulfan-II | ND | 0.67 | 0.35 | ug/kg | |
| 76-44-8 | Heptachlor | ND | 0.67 | 0.33 | ug/kg | |
| 1024-57-3 | Heptachlor epoxide | ND | 0.67 | 0.36 | ug/kg | |
| 72-43-5 | Methoxychlor | ND | 1.3 | 0.33 | ug/kg | |
| 53494-70-5 | Endrin ketone | ND | 0.67 | 0.51 | ug/kg | |
| 8001-35-2 | Toxaphene | ND | 17 | 6.9 | ug/kg | |

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 92% | 24-136% |
| 877-09-8 | Tetrachloro-m-xylene | 90% | 24-136% |
| 2051-24-3 | Decachlorobiphenyl | 89% | 10-153% |
| 2051-24-3 | Decachlorobiphenyl | 107% | 10-153% |

# Method Blank Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97535-MB1 | XX198040.D | 1 | 10/06/16 | HB | 10/06/16 | OP97535 | GXX5823 |

**The QC reported here applies to the following samples:** **Method:** SW846 8082A

JC28902-1

| CAS No. | Compound | Result | RL | MDL | Units | Q |
|---|---|---|---|---|---|---|
| 12674-11-2 | Aroclor 1016 | ND | 33 | 16 | ug/kg | |
| 11104-28-2 | Aroclor 1221 | ND | 33 | 16 | ug/kg | |
| 11141-16-5 | Aroclor 1232 | ND | 33 | 13 | ug/kg | |
| 53469-21-9 | Aroclor 1242 | ND | 33 | 12 | ug/kg | |
| 12672-29-6 | Aroclor 1248 | ND | 33 | 21 | ug/kg | |
| 11097-69-1 | Aroclor 1254 | ND | 33 | 17 | ug/kg | |
| 11096-82-5 | Aroclor 1260 | ND | 33 | 14 | ug/kg | |
| 11100-14-4 | Aroclor 1268 | ND | 33 | 12 | ug/kg | |
| 37324-23-5 | Aroclor 1262 | ND | 33 | 23 | ug/kg | |

| CAS No. | Surrogate Recoveries | | Limits |
|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 101% | 20-152% |
| 877-09-8 | Tetrachloro-m-xylene | 95% | 20-152% |
| 2051-24-3 | Decachlorobiphenyl | 114% | 12-157% |
| 2051-24-3 | Decachlorobiphenyl | 96% | 12-157% |

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97541-BS11 | 5Z30027.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Z1032 |

**The QC reported here applies to the following samples:** **Method:** NJDEP EPH

JC28902-1

| CAS No. | Compound | Spike mg/kg | BSP mg/kg | BSP % | Limits |
|---|---|---|---|---|---|
| | EPH (C9-C28) | 33.3 | 25.3 | 76 | 40-140 |
| | Total EPH (C9-C40) | 33.3 | 25.3 | 76 | 40-140 |

| CAS No. | Surrogate Recoveries | BSP | Limits |
|---|---|---|---|
| 84-15-1 | o-Terphenyl | 90% | 40-140% |
| 3386-33-2 | 1-Chlorooctadecane | 107% | 40-140% |

* = Outside of Control Limits.

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97538-BS1 | OA120270.D | 1 | 10/07/16 | VDT | 10/06/16 | OP97538 | GOA4139 |

**The QC reported here applies to the following samples:** **Method:** SW846 8151

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 94-75-7 | 2,4-D | 133 | 131 | 98 | 63-160 |
| 93-72-1 | 2,4,5-TP (Silvex) | 26.7 | 25.6 | 96 | 53-132 |
| 93-76-5 | 2,4,5-T | 26.7 | 26.0 | 98 | 41-139 |
| 75-99-0 | Dalapon | 26.7 | 29.3 | 110 | 24-160 |
| 1918-00-9 | Dicamba | 26.7 | 24.2 | 91 | 52-144 |
| 120-36-5 | Dichloroprop | 133 | 143 | 107 | 66-141 |
| 88-85-7 | Dinoseb | 133 | 58.9 | 44 | 10-182 |
| 94-74-6 | MCPA | 6670 | 6340 | 95 | 48-147 |
| 93-65-2 | MCPP | 6670 | 7480 | 112 | 42-160 |
| 87-86-5 | Pentachlorophenol | 13.3 | 9.0 | 68 | 47-150 |
| 94-82-6 | 2,4-DB | 133 | 128 | 96 | 35-143 |

| CAS No. | Surrogate Recoveries | BSP | Limits |
|---|---|---|---|
| 19719-28-9 | 2,4-DCAA | 106% | 10-156% |
| 19719-28-9 | 2,4-DCAA | 109% | 10-156% |

* = Outside of Control Limits.

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97536-BS1 | 4G73354.D | 1 | 10/06/16 | DS | 10/06/16 | OP97536 | G4G1919 |

**The QC reported here applies to the following samples:** **Method:** SW846 8081B

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 309-00-2 | Aldrin | 16.7 | 12.8 | 77 | 40-135 |
| 319-84-6 | alpha-BHC | 16.7 | 12.8 | 77 | 37-134 |
| 319-85-7 | beta-BHC | 16.7 | 13.3 | 80 | 37-131 |
| 319-86-8 | delta-BHC | 16.7 | 13.1 | 79 | 34-132 |
| 58-89-9 | gamma-BHC (Lindane) | 16.7 | 12.7 | 76 | 36-128 |
| 5103-71-9 | alpha-Chlordane | 16.7 | 13.0 | 78 | 40-131 |
| 5103-74-2 | gamma-Chlordane | 16.7 | 12.0 | 72 | 41-133 |
| 57-74-9 | Chlordane (alpha and gamma) | 33.3 | 25.0 | 75 | 41-132 |
| 60-57-1 | Dieldrin | 16.7 | 13.4 | 80 | 33-133 |
| 72-54-8 | 4,4'-DDD | 16.7 | 13.4 | 80 | 37-132 |
| 72-55-9 | 4,4'-DDE | 16.7 | 13.2 | 79 | 39-133 |
| 50-29-3 | 4,4'-DDT | 16.7 | 15.1 | 91 | 26-150 |
| 72-20-8 | Endrin | 16.7 | 17.9 | 107 | 41-134 |
| 1031-07-8 | Endosulfan sulfate | 16.7 | 14.6 | 88 | 38-138 |
| 7421-93-4 | Endrin aldehyde | 16.7 | 12.7 | 76 | 37-129 |
| 959-98-8 | Endosulfan-I | 16.7 | 12.8 | 77 | 39-130 |
| 33213-65-9 | Endosulfan-II | 16.7 | 13.0 | 78 | 40-134 |
| 76-44-8 | Heptachlor | 16.7 | 12.4 | 74 | 36-132 |
| 1024-57-3 | Heptachlor epoxide | 16.7 | 13.5 | 81 | 39-131 |
| 72-43-5 | Methoxychlor | 16.7 | 15.8 | 95 | 28-149 |
| 53494-70-5 | Endrin ketone | 16.7 | 14.0 | 84 | 31-138 |

| CAS No. | Surrogate Recoveries | BSP | Limits |
|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 81% | 24-136% |
| 877-09-8 | Tetrachloro-m-xylene | 78% | 24-136% |
| 2051-24-3 | Decachlorobiphenyl | 79% | 10-153% |
| 2051-24-3 | Decachlorobiphenyl | 97% | 10-153% |

* = Outside of Control Limits.

# Blank Spike Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97535-BS1 | XX198041.D | 1 | 10/06/16 | HB | 10/06/16 | OP97535 | GXX5823 |

**The QC reported here applies to the following samples:** **Method:** SW846 8082A

JC28902-1

| CAS No. | Compound | Spike ug/kg | BSP ug/kg | BSP % | Limits |
|---|---|---|---|---|---|
| 12674-11-2 | Aroclor 1016 | 133 | 120 | 90 | 48-167 |
| 11104-28-2 | Aroclor 1221 | | ND | | 70-130 |
| 11141-16-5 | Aroclor 1232 | | ND | | 70-130 |
| 53469-21-9 | Aroclor 1242 | | ND | | 70-130 |
| 12672-29-6 | Aroclor 1248 | | ND | | 70-130 |
| 11097-69-1 | Aroclor 1254 | | ND | | 70-130 |
| 11096-82-5 | Aroclor 1260 | 133 | 116 | 87 [a] | 44-162 |
| 11100-14-4 | Aroclor 1268 | | ND | | 50-150 [b] |
| 37324-23-5 | Aroclor 1262 | | ND | | 50-150 [b] |

| CAS No. | Surrogate Recoveries | BSP | Limits |
|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 97% | 20-152% |
| 877-09-8 | Tetrachloro-m-xylene | 91% | 20-152% |
| 2051-24-3 | Decachlorobiphenyl | 103% | 12-157% |
| 2051-24-3 | Decachlorobiphenyl | 89% | 12-157% |

(a) Reported from 2nd signal. %D of check calibration on 1st signal exceed method criteria (20%) so using for confirmation only.
(b) Advisory control limits.

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97541-MS | 5Z30030.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Z1032 |
| OP97541-MSD | 5Z30031.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Z1032 |
| JC28906-2 | 5Z30029.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Z1032 |
| JC28906-2 | 5Z30044.D | 5 | 10/07/16 | SP | 10/06/16 | OP97541 | G5Z1033 |

**The QC reported here applies to the following samples:** **Method:** NJDEP EPH

JC28902-1

| CAS No. | Compound | JC28906-2 mg/kg | Q | Spike mg/kg | MS mg/kg | MS % | Spike mg/kg | MSD mg/kg | MSD % | RPD | Limits Rec/RPD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | EPH (C9-C28) | 3520 [b] | | 178 | 4790 | 584* [a] | 178 | 4310 | 315* [a] | 11 | 40-140/50 |
| | EPH (> C28-C40) | 162 [b] | | 89 | 310 | 148* [a] | 89 | 258 | 90 | 18 | 40-140/50 |
| | Total EPH (C9-C40) | 3680 [b] | | 267 | 5100 | 438* [a] | 267 | 4570 | 240* [a] | 11 | 40-140/50 |

| CAS No. | Surrogate Recoveries | MS | MSD | JC28906-2 | JC28906-2 | Limits |
|---|---|---|---|---|---|---|
| 84-15-1 | o-Terphenyl | 105% | 103% | 100% | 102% | 40-140% |
| 3386-33-2 | 1-Chlorooctadecane | 85% | 84% | 76% | 81% | 40-140% |

(a) Outside control limits due to high level in sample relative to spike amount.
(b) Result is from Run #2.

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97538-MS | 3G103397.D | 2 | 10/07/16 | VDT | 10/06/16 | OP97538 | G3G3614 |
| OP97538-MSD | 3G103398.D | 2 | 10/07/16 | VDT | 10/06/16 | OP97538 | G3G3614 |
| JC28904-1A | 3G103396.D | 2 | 10/07/16 | VDT | 10/06/16 | OP97538 | G3G3614 |

**The QC reported here applies to the following samples:** **Method:** SW846 8151

JC28902-1

| CAS No. | Compound | JC28904-1A ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Spike ug/kg | MSD ug/kg | MSD % | RPD | Limits Rec/RPD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 94-75-7 | 2,4-D | ND | | 144 | 74.4 | 52 | 146 | 132 | 90 | 56 | 10-176/56 |
| 93-72-1 | 2,4,5-TP (Silvex) | ND | | 28.9 | 7.5 | 26 | 29.3 | 30.9 | 106 | 122* [a] | 10-146/52 |
| 93-76-5 | 2,4,5-T | ND | | 28.9 | 5.5 | 19 | 29.3 | 22.5 | 77 | 121* [a] | 10-145/56 |
| 75-99-0 | Dalapon | ND | | 28.9 | 13.9 | 48 | 29.3 | 42.8 | 146 | 102* [a] | 10-203/60 |
| 1918-00-9 | Dicamba | ND | | 28.9 | 8.4 | 29 | 29.3 | 26.7 | 91 | 104* [a] | 10-162/53 |
| 120-36-5 | Dichloroprop | ND | | 144 | 35.2 | 24 | 146 | 76.5 | 52 | 74* [a] | 10-169/50 |
| 88-85-7 | Dinoseb | ND | | 144 | ND | 0* [b] | 146 | ND | 0* [b] | nc | 10-193/48 |
| 94-74-6 | MCPA | ND | | 7220 | ND | 0* [b] | 7320 | ND | 0* [b] | nc | 10-153/51 |
| 93-65-2 | MCPP | ND | | 7220 | ND | 0* [b] | 7320 | ND | 0* [b] | nc | 10-184/51 |
| 87-86-5 | Pentachlorophenol | ND | | 14.4 | 4.7 | 33 | 14.6 | 13.6 | 93 | 97* [a] | 10-178/48 |
| 94-82-6 | 2,4-DB | ND | | 144 | ND | 0* [b] | 146 | 271 | 185* [a] | 200* [a] | 10-164/49 |

| CAS No. | Surrogate Recoveries | MS | MSD | JC28904-1A | Limits |
|---|---|---|---|---|---|
| 19719-28-9 | 2,4-DCAA | 14% | 73% | 34% | 10-156% |
| 19719-28-9 | 2,4-DCAA | 18% | 113% | 71% | 10-156% |

(a) Outside the QC limits.
(b) Outside control limits due to matrix interference.

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97536-MS | 4G73391.D | 1 | 10/07/16 | RK | 10/06/16 | OP97536 | G4G1920 |
| OP97536-MSD | 4G73392.D | 1 | 10/07/16 | RK | 10/06/16 | OP97536 | G4G1920 |
| JC28906-1 | 4G73390.D | 1 | 10/07/16 | RK | 10/06/16 | OP97536 | G4G1920 |

**The QC reported here applies to the following samples:** **Method:** SW846 8081B

JC28902-1

| CAS No. | Compound | JC28906-1 ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Spike ug/kg | MSD ug/kg | MSD % | RPD | Limits Rec/RPD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 309-00-2 | Aldrin | ND | | 17.8 | 10.9 | 61 | 17.8 | 13.8 | 78 | 23 | 19-147/48 |
| 319-84-6 | alpha-BHC | 6.7 | | 17.8 | 16.6 | 56 | 17.8 | 20.2 | 76 | 20 | 13-155/50 |
| 319-85-7 | beta-BHC | ND | | 17.8 | 10.3 | 58 | 17.8 | 12.7 | 72 | 21 | 10-145/53 |
| 319-86-8 | delta-BHC | ND | | 17.8 | 12.8 | 72 | 17.8 | 15.1 | 85 | 16 | 11-148/51 |
| 58-89-9 | gamma-BHC (Lindane) | ND | | 17.8 | 10.4 | 59 | 17.8 | 13.1 | 74 | 23 | 16-143/47 |
| 5103-71-9 | alpha-Chlordane | 0.67 | J | 17.8 | 11.4 | 60 | 17.8 | 13.7 | 73 | 18 | 15-151/50 |
| 5103-74-2 | gamma-Chlordane | 1.8 | | 17.8 | 12.1 | 58 | 17.8 | 14.0 | 69 | 15 | 13-151/50 |
| 57-74-9 | Chlordane (alpha and gamma) | 2.5 | | 35.5 | 23.4 | 59 | 35.5 | 27.2 | 70 | 15 | 22-136/52 |
| 60-57-1 | Dieldrin | 1.1 | | 17.8 | 13.1 | 68 | 17.8 | 14.9 | 78 | 13 | 10-157/54 |
| 72-54-8 | 4,4'-DDD | ND | | 17.8 | 11.9 | 67 | 17.8 | 14.9 | 84 | 22 | 10-157/52 |
| 72-55-9 | 4,4'-DDE | ND | | 17.8 | 13.0 | 73 | 17.8 | 17.5 | 99 | 30 | 10-155/49 |
| 50-29-3 | 4,4'-DDT | 3.4 | | 17.8 | 13.8 | 59 | 17.8 | 18.3 | 84 | 28 | 10-187/49 |
| 72-20-8 | Endrin | ND | | 17.8 | 16.3 | 92 | 17.8 | 19.9 | 112 | 20 | 14-154/53 |
| 1031-07-8 | Endosulfan sulfate | ND | | 17.8 | 10.3 | 58 | 17.8 | 14.0 | 79 | 30 | 16-140/55 |
| 7421-93-4 | Endrin aldehyde | ND | | 17.8 | 3.8 | 21 | 17.8 | 5.5 | 31 | 37 | 10-156/51 |
| 959-98-8 | Endosulfan-I | ND | | 17.8 | 10.3 | 58 | 17.8 | 12.7 | 72 | 21 | 12-142/47 |
| 33213-65-9 | Endosulfan-II | ND | | 17.8 | 9.2 | 52 | 17.8 | 11.4 | 64 | 21 | 10-150/52 |
| 76-44-8 | Heptachlor | ND | | 17.8 | 12.3 | 69 | 17.8 | 14.7 | 83 | 18 | 10-159/49 |
| 1024-57-3 | Heptachlor epoxide | 0.43 | J | 17.8 | 11.5 | 62 | 17.8 | 14.3 | 78 | 22 | 16-150/51 |
| 72-43-5 | Methoxychlor | ND | | 17.8 | 12.3 | 69 | 17.8 | 14.7 | 83 | 18 | 10-166/52 |
| 53494-70-5 | Endrin ketone | ND | | 17.8 | 15.4 | 87 | 17.8 | 19.1 | 108 | 21 | 10-171/52 |
| 8001-35-2 | Toxaphene | ND | | | ND | | | ND | | nc | 50-150/30 |

| CAS No. | Surrogate Recoveries | MS | MSD | JC28906-1 | Limits |
|---|---|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 84% | 105% | 85% | 24-136% |
| 877-09-8 | Tetrachloro-m-xylene | 62% | 77% | 67% | 24-136% |
| 2051-24-3 | Decachlorobiphenyl | 58% | 70% | 52% | 10-153% |
| 2051-24-3 | Decachlorobiphenyl | 68% | 84% | 77% | 10-153% |

* = Outside of Control Limits.

# Matrix Spike/Matrix Spike Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97535-MS | XX198050.D | 1 | 10/06/16 | HB | 10/06/16 | OP97535 | GXX5823 |
| OP97535-MSD | XX198051.D | 1 | 10/06/16 | HB | 10/06/16 | OP97535 | GXX5823 |
| JC28902-1 | XX198049.D | 1 | 10/06/16 | HB | 10/06/16 | OP97535 | GXX5823 |

**The QC reported here applies to the following samples:** **Method:** SW846 8082A

JC28902-1

| CAS No. | Compound | JC28902-1 ug/kg | Q | Spike ug/kg | MS ug/kg | MS % | Spike ug/kg | MSD ug/kg | MSD % | RPD | Limits Rec/RPD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 12674-11-2 | Aroclor 1016 | ND | | 149 | 116 | 78 | 149 | 102 | 68 | 13 | 32-176/47 |
| 11104-28-2 | Aroclor 1221 | ND | | | ND | | | ND | | nc | 70-130/30 |
| 11141-16-5 | Aroclor 1232 | ND | | | ND | | | ND | | nc | 70-130/30 |
| 53469-21-9 | Aroclor 1242 | ND | | | ND | | | ND | | nc | 70-130/30 |
| 12672-29-6 | Aroclor 1248 | ND | | | ND | | | ND | | nc | 70-130/30 |
| 11097-69-1 | Aroclor 1254 | ND | | | ND | | | ND | | nc | 70-130/30 |
| 11096-82-5 | Aroclor 1260 | ND | | 149 | 102 | 68 | 149 | 97.6 | 65 | 4 | 19-180/49 |
| 11100-14-4 | Aroclor 1268 | ND | | | ND | | | ND | | nc | -/30 |
| 37324-23-5 | Aroclor 1262 | ND | | | ND | | | ND | | nc | -/30 |

| CAS No. | Surrogate Recoveries | MS | MSD | JC28902-1 | Limits |
|---|---|---|---|---|---|
| 877-09-8 | Tetrachloro-m-xylene | 83% | 65% | 89% | 20-152% |
| 877-09-8 | Tetrachloro-m-xylene | 86% | 68% | 88% | 20-152% |
| 2051-24-3 | Decachlorobiphenyl | 77% | 69% | 83% | 12-157% |
| 2051-24-3 | Decachlorobiphenyl | 78% | 74% | 80% | 12-157% |

* = Outside of Control Limits.

# Duplicate Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| Sample | File ID | DF | Analyzed | By | Prep Date | Prep Batch | Analytical Batch |
|---|---|---|---|---|---|---|---|
| OP97541-DUP | 5Y36630.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Y1211 |
| JC28910-2 | 5Y36629.D | 1 | 10/06/16 | SP | 10/06/16 | OP97541 | G5Y1211 |

**The QC reported here applies to the following samples:** **Method:** NJDEP EPH

JC28902-1

| CAS No. | Compound | JC28910-2 mg/kg | Q | DUP mg/kg | Q | RPD | Limits |
|---|---|---|---|---|---|---|---|
| | EPH (C9-C28) | ND | | ND | | nc | 50 |
| | EPH (> C28-C40) | ND | | ND | | nc | 50 |
| | Total EPH (C9-C40) | ND | | ND | | nc | 50 |

| CAS No. | Surrogate Recoveries | DUP | JC28910-2 | Limits |
|---|---|---|---|---|
| 84-15-1 | o-Terphenyl | 68% | 70% | 40-140% |
| 3386-33-2 | 1-Chlorooctadecane | 74% | 76% | 40-140% |

* = Outside of Control Limits.

# Semivolatile Internal Standard Area Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1919-CC1911 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73351.D | **Injection Time:** | 17:13 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | IS 1 AREA | RT | IS 2 AREA | RT |
|---|---|---|---|---|
| Check Std | 313852376 | 1.33 | 433214677 | 1.54 |
| Upper Limit [a] | 627704752 | 1.83 | 866429354 | 2.04 |
| Lower Limit [b] | 156926188 | 0.83 | 216607339 | 1.04 |

| Lab Sample ID | IS 1 AREA | RT | IS 2 AREA | RT |
|---|---|---|---|---|
| OP97536-MB1 | 267521183 | 1.33 | 367619848 | 1.54 |
| OP97536-BS1 | 280482044 | 1.33 | 392329723 | 1.54 |
| JC28902-1 | 285220657 | 1.33 | 379496517 | 1.54 |
| ZZZZZZ | 204412703 | 1.33 | 263668459 | 1.54 |
| ZZZZZZ | 282690633 | 1.33 | 387242090 | 1.54 |
| ZZZZZZ | 296271135 | 1.33 | 418448094 | 1.54 |
| ZZZZZZ | 213657532 | 1.33 | 271399774 | 1.54 |

**IS 1** = 1-Bromo-2-nitrobenzene (Signal #2)
**IS 2** = 1-Bromo-2-nitrobenzene (Signal #1)

(a) Upper Limit = + 100% of check standard area; Retention time + 0.5 minutes.
(b) Lower Limit = -50% of check standard area; Retention time -0.5 minutes.

# Semivolatile Internal Standard Area Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1920-CC1911 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73382.D | **Injection Time:** | 09:09 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | IS 1 AREA | RT | IS 2 AREA | RT |
|---|---|---|---|---|
| Check Std | 346598203 | 1.32 | 483445268 | 1.53 |
| Upper Limit [a] | 693196406 | 1.82 | 966890536 | 2.03 |
| Lower Limit [b] | 173299102 | 0.82 | 241722634 | 1.03 |

| Lab Sample ID | IS 1 AREA | RT | IS 2 AREA | RT |
|---|---|---|---|---|
| OP97573-MB1 | 252307651 | 1.32 | 339570631 | 1.54 |
| OP97573-BS1 | 286580679 | 1.32 | 399664794 | 1.54 |
| ZZZZZZ | 258504359 | 1.32 | 342478265 | 1.53 |
| ZZZZZZ | 274453871 | 1.32 | 366781109 | 1.54 |
| JC28906-1 | 199891166 | 1.33 | 242933370 | 1.54 |
| OP97536-MS | 210790555 | 1.33 | 256735275 | 1.54 |
| OP97536-MSD | 211667972 | 1.33 | 256610267 | 1.54 |
| ZZZZZZ | 210803696 | 1.33 | 268376486 | 1.54 |
| ZZZZZZ | 284030853 | 1.33 | 364314186 | 1.54 |
| ZZZZZZ | 285695462 | 1.33 | 374546949 | 1.54 |
| ZZZZZZ | 284146781 | 1.32 | 410550818 | 1.54 |
| ZZZZZZ | 264437338 | 1.33 | 377972145 | 1.54 |
| JC28920-6A | 279854987 | 1.33 | 392582877 | 1.54 |
| OP97573-LS12 | 268524908 | 1.33 | 376179941 | 1.54 |
| OP97573-MS | 268524908 | 1.33 | 376179941 | 1.54 |
| OP97573-MSD | 277451975 | 1.33 | 383219357 | 1.54 |
| OP97573-LB31 | 274105568 | 1.33 | 384763465 | 1.54 |

**IS 1** = 1-Bromo-2-nitrobenzene (Signal #2)
**IS 2** = 1-Bromo-2-nitrobenzene (Signal #1)

(a) Upper Limit = + 100% of check standard area; Retention time + 0.5 minutes.
(b) Lower Limit = -50% of check standard area; Retention time -0.5 minutes.

# DDT/Endrin Breakdown Check



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Sample:** | G4G1911-DDT | **Injection Date:** | 09/28/16 |
| **Lab File ID:** | 4G72942.D | **Injection Time:** | 18:11 |
| **Instrument ID:** | GC4G | | |

| Compound | Response Signal 1 | Response Signal 2 |
|---|---|---|
| 4,4'-DDD | 21567067 | 19693440 |
| 4,4'-DDE | 12804498 | 8741360 |
| 4,4'-DDT | 827661617 | 478047746 |
| DDT Breakdown [a] | 4 % | 5.6 % |
| Endrin aldehyde | 19289512 | 16710867 |
| Endrin ketone | 43465767 | 27626447 |
| Endrin | 384878674 | 278309171 |
| Endrin Breakdown [b] | 14 % | 13.7 % |

(a) Calculated as: (DDD + DDE) / (DDD + DDE + DDT) x 100
(b) Calculated as: (Endrin Aldehyde + Endrin Ketone) / (Endrin Aldehyde + Endrin Ketone + Endrin) x 100

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| G4G1911-IC1911 | 4G72944.D | 09/28/16 | 18:40 | 00:29 | Initial cal 1 |
| G4G1911-IC1911 | 4G72945.D | 09/28/16 | 18:55 | 00:44 | Initial cal 2 |
| G4G1911-IC1911 | 4G72946.D | 09/28/16 | 19:09 | 00:58 | Initial cal 5 |
| G4G1911-IC1911 | 4G72947.D | 09/28/16 | 19:24 | 01:13 | Initial cal 10 |
| G4G1911-ICC1911 | 4G72948.D | 09/28/16 | 19:38 | 01:27 | Initial cal 25 |
| G4G1911-IC1911 | 4G72949.D | 09/28/16 | 19:53 | 01:42 | Initial cal 50 |
| G4G1911-IC1911 | 4G72950.D | 09/28/16 | 20:07 | 01:56 | Initial cal 75 |
| G4G1911-IC1911 | 4G72951.D | 09/28/16 | 20:22 | 02:11 | Initial cal 100 |
| G4G1911-IC1911 | 4G72952.D | 09/28/16 | 20:36 | 02:25 | Initial cal 500 |
| G4G1911-IC1911 | 4G72953.D | 09/28/16 | 20:51 | 02:40 | Initial cal 500 |
| G4G1911-ICV1911 | 4G72954.D | 09/28/16 | 21:05 | 02:54 | Initial cal verification 25 |
| G4G1911-ICV1911 | 4G72955.D | 09/28/16 | 21:20 | 03:09 | Initial cal verification 25 |
| G4G1911-ICV1911 | 4G72956.D | 09/28/16 | 21:34 | 03:23 | Initial cal verification 500 |
| G4G1911-ICV1911 | 4G72957.D | 09/28/16 | 21:49 | 03:38 | Initial cal verification 500 |

# DDT/Endrin Breakdown Check



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Sample:** | G4G1919-DDT | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73350.D | **Injection Time:** | 16:59 |
| **Instrument ID:** | GC4G | | |

| Compound | Response Signal 1 | Response Signal 2 |
|---|---|---|
| 4,4'-DDD | 9719194 | 9227782 |
| 4,4'-DDE | 12667378 | 5921347 |
| 4,4'-DDT | 1047090615 | 605414779 |
| DDT Breakdown [a] | 2.1 % | 2.4 % |
| Endrin aldehyde | 6356626 | 4711502 |
| Endrin ketone | 23269961 | 19729894 |
| Endrin | 536086930 | 387188115 |
| Endrin Breakdown [b] | 5.2 % | 5.9 % |

(a) Calculated as: (DDD + DDE) / (DDD + DDE + DDT) x 100
(b) Calculated as: (Endrin Aldehyde + Endrin Ketone) / (Endrin Aldehyde + Endrin Ketone + Endrin) x 100

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| G4G1919-CC1911 | 4G73351.D | 10/06/16 | 17:13 | 00:14 | Continuing cal 25 |
| OP97536-MB1 | 4G73353.D | 10/06/16 | 17:42 | 00:43 | Method Blank |
| OP97536-BS1 | 4G73354.D | 10/06/16 | 17:56 | 00:57 | Blank Spike |
| JC28902-1 | 4G73355.D | 10/06/16 | 18:11 | 01:12 | WOOLSTON-TS-002 |
| ZZZZZZ | 4G73360.D | 10/06/16 | 19:23 | 02:24 | (unrelated sample) |
| ZZZZZZ | 4G73362.D | 10/06/16 | 19:52 | 02:53 | (unrelated sample) |
| ZZZZZZ | 4G73363.D | 10/06/16 | 20:06 | 03:07 | (unrelated sample) |
| ZZZZZZ | 4G73366.D | 10/06/16 | 20:49 | 03:50 | (unrelated sample) |

# DDT/Endrin Breakdown Check



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Sample:** | G4G1920-DDT | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73381.D | **Injection Time:** | 08:54 |
| **Instrument ID:** | GC4G | | |

| Compound | Response Signal 1 | Response Signal 2 |
|---|---|---|
| 4,4'-DDD | 29741342 | 23736858 |
| 4,4'-DDE | 13246422 | 10842480 |
| 4,4'-DDT | 1157608144 | 705845177 |
| DDT Breakdown [a] | 3.6 % | 4.7 % |
| Endrin aldehyde | 8251616 | 9089682 |
| Endrin ketone | 28637204 | 23153861 |
| Endrin | 625394352 | 446375802 |
| Endrin Breakdown [b] | 5.6 % | 6.7 % |

(a) Calculated as: (DDD + DDE) / (DDD + DDE + DDT) x 100
(b) Calculated as: (Endrin Aldehyde + Endrin Ketone) / (Endrin Aldehyde + Endrin Ketone + Endrin) x 100

**This check applies to the following Samples, MS, MSD, Blanks, and Standards:**

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | Hours Lapsed | Client Sample ID |
|---|---|---|---|---|---|
| G4G1920-CC1911 | 4G73382.D | 10/07/16 | 09:09 | 00:15 | Continuing cal 50 |
| OP97573-MB1 | 4G73384.D | 10/07/16 | 09:54 | 01:00 | Method Blank |
| OP97573-BS1 | 4G73385.D | 10/07/16 | 10:08 | 01:14 | Blank Spike |
| ZZZZZZ | 4G73386.D | 10/07/16 | 10:23 | 01:29 | (unrelated sample) |
| ZZZZZZ | 4G73389.D | 10/07/16 | 11:06 | 02:12 | (unrelated sample) |
| JC28906-1 | 4G73390.D | 10/07/16 | 11:21 | 02:27 | (used for QC only; not part of job JC28902) |
| OP97536-MS | 4G73391.D | 10/07/16 | 11:35 | 02:41 | Matrix Spike |
| OP97536-MSD | 4G73392.D | 10/07/16 | 11:49 | 02:55 | Matrix Spike Duplicate |
| ZZZZZZ | 4G73393.D | 10/07/16 | 12:04 | 03:10 | (unrelated sample) |
| ZZZZZZ | 4G73394.D | 10/07/16 | 12:18 | 03:24 | (unrelated sample) |
| ZZZZZZ | 4G73395.D | 10/07/16 | 12:33 | 03:39 | (unrelated sample) |
| ZZZZZZ | 4G73396.D | 10/07/16 | 12:47 | 03:53 | (unrelated sample) |
| ZZZZZZ | 4G73397.D | 10/07/16 | 13:01 | 04:07 | (unrelated sample) |
| JC28920-6A | 4G73398.D | 10/07/16 | 13:16 | 04:22 | (used for QC only; not part of job JC28902) |
| OP97573-LS12 | 4G73399.D | 10/07/16 | 13:30 | 04:36 | Leachate Spike |
| OP97573-MS | 4G73399.D | 10/07/16 | 13:30 | 04:36 | Matrix Spike |
| OP97573-MSD | 4G73400.D | 10/07/16 | 13:45 | 04:51 | Matrix Spike Duplicate |
| OP97573-LB31 | 4G73401.D | 10/07/16 | 13:59 | 05:05 | Leachate Blank |

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GOA4139-CC4125 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | OA120267.D | **Injection Time:** | 09:18 |
| **Instrument ID:** | GCOA | **Method:** | SW846 8151 |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97538-BS1 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | OA120270.D | **Injection Time:** | 10:44 |
| **Client ID:** | Blank Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| 2,4-D | 1 | 8.50 | 8.51 | 137 | | ug/kg | 4.5 |
| 2,4-D | 2 [a] | 9.62 | 9.62 | 131 | | ug/kg | |
| 2,4,5-TP (Silvex) | 1 | 9.54 | 9.55 | 28.2 | | ug/kg | 9.7 |
| 2,4,5-TP (Silvex) | 2 [a] | 10.73 | 10.74 | 25.6 | | ug/kg | |
| 2,4,5-T | 1 | 9.89 | 9.91 | 27.9 | | ug/kg | 7.1 |
| 2,4,5-T | 2 [a] | 11.28 | 11.28 | 26.0 | | ug/kg | |
| Dalapon | 1 | 2.32 | 2.32 | 30.4 | E | ug/kg | 3.7 |
| Dalapon | 2 [a] | 2.50 | 2.51 | 29.3 | | ug/kg | |
| Dicamba | 1 | 7.38 | 7.38 | 25.7 | | ug/kg | 6.0 |
| Dicamba | 2 [a] | 8.28 | 8.28 | 24.2 | | ug/kg | |
| Dichloroprop | 1 | 8.23 | 8.23 | 145 | | ug/kg | 1.4 |
| Dichloroprop | 2 [a] | 9.19 | 9.20 | 143 | | ug/kg | |
| Dinoseb | 1 | 12.02 | 12.03 | 89.0 | | ug/kg | 40.7 |
| Dinoseb | 2 [a] | 12.40 | 12.41 | 58.9 | | ug/kg | |
| MCPA | 1 | 7.79 | 7.80 | 11200 | E | ug/kg | 55.4 |
| MCPA | 2 [a] | 8.74 | 8.75 | 6340 | | ug/kg | |
| MCPP | 1 | 7.62 | 7.63 | 8830 | E | ug/kg | 16.6 |
| MCPP | 2 [a] | 8.43 | 8.44 | 7480 | | ug/kg | |
| Pentachlorophenol | 1 [a] | 8.72 | 8.73 | 9.0 | | ug/kg | 18.2 |
| Pentachlorophenol | 2 | 10.12 | 10.12 | 10.8 | | ug/kg | |
| 2,4-DB | 1 | 10.60 | 10.62 | 141 | | ug/kg | 9.7 |
| 2,4-DB | 2 [a] | 12.00 | 12.01 | 128 | | ug/kg | |

(a) QC results reported from this column.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G3G3614-CC3591 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 3G103394.D | **Injection Time:** | 09:07 |
| **Instrument ID:** | GC3G | **Method:** | SW846 8151 |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97538-MS | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 3G103397.D | **Injection Time:** | 10:39 |
| **Client ID:** | Matrix Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| 2,4-D | 1 [a] | 8.52 | 8.53 | 74.4 | | ug/kg | 58.1 |
| 2,4-D | 2 | 9.68 | 9.69 | 40.9 | | ug/kg | |
| 2,4,5-TP (Silvex) | 1 [a] | 9.55 | 9.57 | 7.5 | | ug/kg | 6.9 |
| 2,4,5-TP (Silvex) | 2 | 10.78 | 10.79 | 7.0 | J | ug/kg | |
| 2,4,5-T | 1 [a] | 9.91 | 9.93 | 5.5 | J | ug/kg | 0.0 |
| 2,4,5-T | 2 | 11.33 | 11.36 | 5.5 | J | ug/kg | |
| Dalapon | 1 [a] | 2.33 | 2.33 | 13.9 | | ug/kg | 39.3 |
| Dalapon | 2 | 2.54 | 2.53 | 20.7 | | ug/kg | |
| Dicamba | 1 [a] | 7.39 | 7.40 | 8.4 | | ug/kg | 192.6 |
| Dicamba | 2 | 8.33 | 8.32 | 447 | E | ug/kg | |
| Dichloroprop | 1 [a] | 8.25 | 8.25 | 35.2 | J | ug/kg | 74.6 |
| Dichloroprop | 2 | 9.24 | 9.25 | 77.1 | | ug/kg | |
| Pentachlorophenol | 1 [a] | 8.75 | 8.75 | 4.7 | | ug/kg | 12.0 |
| Pentachlorophenol | 2 | 10.17 | 10.17 | 5.3 | | ug/kg | |

(a) QC results reported from this column.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G3G3614-CC3591 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 3G103394.D | **Injection Time:** | 09:07 |
| **Instrument ID:** | GC3G | **Method:** | SW846 8151 |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97538-MSD | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 3G103398.D | **Injection Time:** | 11:09 |
| **Client ID:** | Matrix Spike Duplicate | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| 2,4-D | 1 [a] | 8.51 | 8.53 | 132 | | ug/kg | 7.1 |
| 2,4-D | 2 | 9.67 | 9.69 | 123 | | ug/kg | |
| 2,4,5-TP (Silvex) | 1 [a] | 9.56 | 9.57 | 30.9 | | ug/kg | 109.7 |
| 2,4,5-TP (Silvex) | 2 | 10.77 | 10.79 | 106 | E | ug/kg | |
| 2,4,5-T | 1 [a] | 9.91 | 9.93 | 22.5 | | ug/kg | 53.4 |
| 2,4,5-T | 2 | 11.33 | 11.36 | 38.9 | | ug/kg | |
| Dalapon | 1 [a] | 2.33 | 2.33 | 42.8 | | ug/kg | 40.9 |
| Dalapon | 2 | 2.53 | 2.53 | 64.8 | | ug/kg | |
| Dicamba | 1 [a] | 7.39 | 7.40 | 26.7 | | ug/kg | 118.3 |
| Dicamba | 2 | 8.30 | 8.32 | 104 | E | ug/kg | |
| Dichloroprop | 1 [a] | 8.24 | 8.25 | 76.5 | | ug/kg | 171.4 |
| Dichloroprop | 2 | 9.27 | 9.25 | 994 | E | ug/kg | |
| Pentachlorophenol | 1 [a] | 8.75 | 8.75 | 13.6 | | ug/kg | 39.5 |
| Pentachlorophenol | 2 | 10.18 | 10.17 | 20.3 | | ug/kg | |
| 2,4-DB | 1 [a] | 10.62 | 10.63 | 271 | | ug/kg | 1.1 |
| 2,4-DB | 2 | 12.07 | 12.08 | 274 | | ug/kg | |

(a) QC results reported from this column.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1919-CC1911 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73351.D | **Injection Time:** | 17:13 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97536-BS1 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73354.D | **Injection Time:** | 17:56 |
| **Client ID:** | Blank Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| Aldrin | 1 [a] | 3.37 | 3.37 | 12.8 | | ug/kg | 4.6 |
| Aldrin | 2 | 3.47 | 3.47 | 13.4 | | ug/kg | |
| alpha-BHC | 1 [a] | 2.39 | 2.39 | 12.8 | | ug/kg | 6.8 |
| alpha-BHC | 2 | 2.36 | 2.36 | 13.7 | | ug/kg | |
| beta-BHC | 1 | 2.71 | 2.71 | 13.9 | | ug/kg | 4.4 |
| beta-BHC | 2 [a] | 2.76 | 2.76 | 13.3 | | ug/kg | |
| delta-BHC | 1 [a] | 2.87 | 2.87 | 13.1 | | ug/kg | 12.9 |
| delta-BHC | 2 | 3.06 | 3.06 | 14.9 | | ug/kg | |
| gamma-BHC (Lindane) | 1 [a] | 2.64 | 2.64 | 12.7 | | ug/kg | 6.1 |
| gamma-BHC (Lindane) | 2 | 2.68 | 2.68 | 13.5 | | ug/kg | |
| alpha-Chlordane | 1 [a] | 4.34 | 4.34 | 13.0 | | ug/kg | 4.5 |
| alpha-Chlordane | 2 | 4.59 | 4.59 | 13.6 | | ug/kg | |
| gamma-Chlordane | 1 [a] | 4.18 | 4.18 | 12.0 | | ug/kg | 12.5 |
| gamma-Chlordane | 2 | 4.40 | 4.40 | 13.6 | | ug/kg | |
| Chlordane (alpha and gamma) | n/a [b] | | | 25.0 | | ug/kg | |
| Dieldrin | 1 [a] | 4.81 | 4.81 | 13.4 | | ug/kg | 8.6 |
| Dieldrin | 2 | 5.04 | 5.04 | 14.6 | | ug/kg | |
| 4,4'-DDD | 1 [a] | 5.25 | 5.25 | 13.4 | | ug/kg | 9.3 |
| 4,4'-DDD | 2 | 5.71 | 5.71 | 14.7 | | ug/kg | |
| 4,4'-DDE | 1 [a] | 4.45 | 4.45 | 13.2 | | ug/kg | 7.3 |
| 4,4'-DDE | 2 | 4.86 | 4.86 | 14.2 | | ug/kg | |
| 4,4'-DDT | 1 | 5.64 | 5.64 | 15.7 | | ug/kg | 3.9 |
| 4,4'-DDT | 2 [a] | 6.19 | 6.19 | 15.1 | | ug/kg | |
| Endrin | 1 | 5.12 | 5.12 | 18.4 | | ug/kg | 2.8 |
| Endrin | 2 [a] | 5.48 | 5.48 | 17.9 | | ug/kg | |
| Endosulfan sulfate | 1 [a] | 6.71 | 6.71 | 14.6 | | ug/kg | 10.4 |
| Endosulfan sulfate | 2 | 6.77 | 6.77 | 16.2 | | ug/kg | |
| Endrin aldehyde | 1 [a] | 6.04 | 6.04 | 12.7 | | ug/kg | 6.8 |
| Endrin aldehyde | 2 | 6.34 | 6.34 | 13.6 | | ug/kg | |
| Endosulfan-I | 1 [a] | 4.51 | 4.51 | 12.8 | | ug/kg | 4.6 |
| Endosulfan-I | 2 | 4.66 | 4.66 | 13.4 | | ug/kg | |
| Endosulfan-II | 1 [a] | 5.43 | 5.43 | 13.0 | | ug/kg | 8.1 |
| Endosulfan-II | 2 | 5.81 | 5.81 | 14.1 | | ug/kg | |
| Heptachlor | 1 | 3.07 | 3.07 | 13.8 | | ug/kg | 10.7 |
| Heptachlor | 2 [a] | 3.12 | 3.12 | 12.4 | | ug/kg | |
| Heptachlor epoxide | 1 | 4.03 | 4.03 | 13.6 | | ug/kg | 0.7 |
| Heptachlor epoxide | 2 [a] | 4.15 | 4.15 | 13.5 | | ug/kg | |
| Methoxychlor | 1 | 6.42 | 6.42 | 17.8 | | ug/kg | 11.9 |
| Methoxychlor | 2 [a] | 7.38 | 7.38 | 15.8 | | ug/kg | |
| Endrin ketone | 1 [a] | 7.12 | 7.12 | 14.0 | | ug/kg | 7.6 |
| Endrin ketone | 2 | 7.65 | 7.65 | 15.1 | | ug/kg | |

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1919-CC1911 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73351.D | **Injection Time:** | 17:13 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97536-BS1 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73354.D | **Injection Time:** | 17:56 |
| **Client ID:** | Blank Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|

(a) QC results reported from this column.
(b) Final reported result.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1920-CC1911 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73382.D | **Injection Time:** | 09:09 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97536-MS | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73391.D | **Injection Time:** | 11:35 |
| **Client ID:** | Matrix Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| Aldrin | 1 [a] | 3.38 | 3.37 | 10.9 | | ug/kg | 7.1 |
| Aldrin | 2 | 3.47 | 3.47 | 11.7 | | ug/kg | |
| alpha-BHC | 1 | 2.39 | 2.39 | 20.6 | | ug/kg | 21.5 |
| alpha-BHC | 2 [a] | 2.36 | 2.36 | 16.6 | | ug/kg | |
| beta-BHC | 1 [a] | 2.72 | 2.71 | 10.3 | | ug/kg | 22.4 |
| beta-BHC | 2 | 2.76 | 2.75 | 12.9 | | ug/kg | |
| delta-BHC | 1 [a] | 2.88 | 2.87 | 12.8 | | ug/kg | 9.8 |
| delta-BHC | 2 | 3.06 | 3.06 | 11.6 | | ug/kg | |
| gamma-BHC (Lindane) | 1 [a] | 2.65 | 2.64 | 10.4 | | ug/kg | 65.4 |
| gamma-BHC (Lindane) | 2 | 2.68 | 2.68 | 20.5 | | ug/kg | |
| alpha-Chlordane | 1 | 4.34 | 4.34 | 12.5 | | ug/kg | 9.2 |
| alpha-Chlordane | 2 [a] | 4.59 | 4.59 | 11.4 | | ug/kg | |
| gamma-Chlordane | 1 | 4.18 | 4.18 | 13.8 | | ug/kg | 13.1 |
| gamma-Chlordane | 2 [a] | 4.40 | 4.40 | 12.1 | | ug/kg | |
| Chlordane (alpha and gamma) | n/a [b] | | | 23.4 | | ug/kg | |
| Dieldrin | 1 | 4.81 | 4.81 | 11.5 | | ug/kg | 13.0 |
| Dieldrin | 2 [a] | 5.04 | 5.04 | 13.1 | | ug/kg | |
| 4,4'-DDD | 1 [a] | 5.25 | 5.24 | 11.9 | | ug/kg | 14.1 |
| 4,4'-DDD | 2 | 5.70 | 5.71 | 13.7 | | ug/kg | |
| 4,4'-DDE | 1 [a] | 4.45 | 4.45 | 13.0 | | ug/kg | 11.4 |
| 4,4'-DDE | 2 | 4.85 | 4.85 | 11.6 | | ug/kg | |
| 4,4'-DDT | 1 | 5.64 | 5.64 | 14.5 | | ug/kg | 4.9 |
| 4,4'-DDT | 2 [a] | 6.18 | 6.18 | 13.8 | | ug/kg | |
| Endrin | 1 [a] | 5.12 | 5.11 | 16.3 | | ug/kg | 17.3 |
| Endrin | 2 | 5.48 | 5.48 | 13.7 | | ug/kg | |
| Endosulfan sulfate | 1 [a] | 6.71 | 6.71 | 10.3 | | ug/kg | 42.7 |
| Endosulfan sulfate | 2 | 6.77 | 6.77 | 15.9 | | ug/kg | |
| Endrin aldehyde | 1 [a] | 6.01 | 6.04 | 3.8 | | ug/kg | 11.1 |
| Endrin aldehyde | 2 | 6.34 | 6.34 | 3.4 | | ug/kg | |
| Endosulfan-I | 1 [a] | 4.51 | 4.51 | 10.3 | | ug/kg | 0.0 |
| Endosulfan-I | 2 | 4.66 | 4.66 | 10.3 | | ug/kg | |
| Endosulfan-II | 1 [a] | 5.43 | 5.43 | 9.2 | | ug/kg | 11.3 |
| Endosulfan-II | 2 | 5.81 | 5.81 | 10.3 | | ug/kg | |
| Heptachlor | 1 [a] | 3.08 | 3.07 | 12.3 | | ug/kg | 25.7 |
| Heptachlor | 2 | 3.12 | 3.12 | 9.5 | | ug/kg | |
| Heptachlor epoxide | 1 [a] | 4.04 | 4.03 | 11.5 | | ug/kg | 7.5 |
| Heptachlor epoxide | 2 | 4.16 | 4.15 | 12.4 | | ug/kg | |
| Methoxychlor | 1 [a] | 6.41 | 6.41 | 12.3 | | ug/kg | 0.8 |
| Methoxychlor | 2 | 7.38 | 7.38 | 12.4 | | ug/kg | |
| Endrin ketone | 1 [a] | 7.12 | 7.12 | 15.4 | | ug/kg | 22.4 |
| Endrin ketone | 2 | 7.64 | 7.64 | 12.3 | | ug/kg | |

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1920-CC1911 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73382.D | **Injection Time:** | 09:09 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97536-MS | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73391.D | **Injection Time:** | 11:35 |
| **Client ID:** | Matrix Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|

(a) QC results reported from this column.
(b) Final reported result.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1920-CC1911 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73382.D | **Injection Time:** | 09:09 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97536-MSD | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73392.D | **Injection Time:** | 11:49 |
| **Client ID:** | Matrix Spike Duplicate | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| Aldrin | 1 [a] | 3.38 | 3.37 | 13.8 | | ug/kg | 4.9 |
| Aldrin | 2 | 3.47 | 3.47 | 14.5 | | ug/kg | |
| alpha-BHC | 1 | 2.40 | 2.39 | 24.7 | | ug/kg | 20.0 |
| alpha-BHC | 2 [a] | 2.36 | 2.36 | 20.2 | | ug/kg | |
| beta-BHC | 1 [a] | 2.72 | 2.71 | 12.7 | | ug/kg | 20.5 |
| beta-BHC | 2 | 2.76 | 2.75 | 15.6 | | ug/kg | |
| delta-BHC | 1 [a] | 2.88 | 2.87 | 15.1 | | ug/kg | 6.1 |
| delta-BHC | 2 | 3.06 | 3.06 | 14.2 | | ug/kg | |
| gamma-BHC (Lindane) | 1 [a] | 2.65 | 2.64 | 13.1 | | ug/kg | 62.8 |
| gamma-BHC (Lindane) | 2 | 2.68 | 2.68 | 25.1 | | ug/kg | |
| alpha-Chlordane | 1 | 4.34 | 4.34 | 14.9 | | ug/kg | 8.4 |
| alpha-Chlordane | 2 [a] | 4.59 | 4.59 | 13.7 | | ug/kg | |
| gamma-Chlordane | 1 | 4.18 | 4.18 | 13.6 | | ug/kg | 2.9 |
| gamma-Chlordane | 2 [a] | 4.40 | 4.40 | 14.0 | | ug/kg | |
| Chlordane (alpha and gamma) | n/a [b] | | | 27.2 | | ug/kg | |
| Dieldrin | 1 | 4.81 | 4.81 | 13.8 | | ug/kg | 7.7 |
| Dieldrin | 2 [a] | 5.04 | 5.04 | 14.9 | | ug/kg | |
| 4,4'-DDD | 1 [a] | 5.25 | 5.24 | 14.9 | | ug/kg | 16.6 |
| 4,4'-DDD | 2 | 5.71 | 5.71 | 17.6 | | ug/kg | |
| 4,4'-DDE | 1 [a] | 4.45 | 4.45 | 17.5 | | ug/kg | 20.8 |
| 4,4'-DDE | 2 | 4.85 | 4.85 | 14.2 | | ug/kg | |
| 4,4'-DDT | 1 | 5.64 | 5.64 | 16.3 | | ug/kg | 11.6 |
| 4,4'-DDT | 2 [a] | 6.18 | 6.18 | 18.3 | | ug/kg | |
| Endrin | 1 [a] | 5.12 | 5.11 | 19.9 | | ug/kg | 20.5 |
| Endrin | 2 | 5.48 | 5.48 | 16.2 | | ug/kg | |
| Endosulfan sulfate | 1 [a] | 6.71 | 6.71 | 14.0 | | ug/kg | 27.7 |
| Endosulfan sulfate | 2 | 6.77 | 6.77 | 18.5 | | ug/kg | |
| Endrin aldehyde | 1 [a] | 6.03 | 6.04 | 5.5 | | ug/kg | 13.6 |
| Endrin aldehyde | 2 | 6.34 | 6.34 | 4.8 | | ug/kg | |
| Endosulfan-I | 1 [a] | 4.51 | 4.51 | 12.7 | | ug/kg | 0.8 |
| Endosulfan-I | 2 | 4.67 | 4.66 | 12.6 | | ug/kg | |
| Endosulfan-II | 1 [a] | 5.43 | 5.43 | 11.4 | | ug/kg | 11.6 |
| Endosulfan-II | 2 | 5.81 | 5.81 | 12.8 | | ug/kg | |
| Heptachlor | 1 [a] | 3.08 | 3.07 | 14.7 | | ug/kg | 23.6 |
| Heptachlor | 2 | 3.12 | 3.12 | 11.6 | | ug/kg | |
| Heptachlor epoxide | 1 [a] | 4.04 | 4.03 | 14.3 | | ug/kg | 2.8 |
| Heptachlor epoxide | 2 | 4.16 | 4.15 | 13.9 | | ug/kg | |
| Methoxychlor | 1 [a] | 6.41 | 6.41 | 14.7 | | ug/kg | 2.8 |
| Methoxychlor | 2 | 7.38 | 7.38 | 14.3 | | ug/kg | |
| Endrin ketone | 1 [a] | 7.12 | 7.12 | 19.1 | | ug/kg | 24.0 |
| Endrin ketone | 2 | 7.64 | 7.64 | 15.0 | | ug/kg | |

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1920-CC1911 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73382.D | **Injection Time:** | 09:09 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97536-MSD | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73392.D | **Injection Time:** | 11:49 |
| **Client ID:** | Matrix Spike Duplicate | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|

(a) QC results reported from this column.
(b) Final reported result.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GXX5823-CC5786 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198038.D | **Injection Time:** | 14:28 |
| **Instrument ID:** | GCXX | **Method:** | SW846 8082A |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97535-BS1 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198041.D | **Injection Time:** | 15:19 |
| **Client ID:** | Blank Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| Aroclor 1016 | 1 | | | 124 | | ug/kg | 3.3 |
| Aroclor 1016 | 2 [a] | | | 120 | | ug/kg | |
| AR1016-A | 1 | 3.19 | 3.19 | 126 | | ug/kg | |
| AR1016-A | 2 | 3.98 | 3.98 | 119 | | ug/kg | |
| AR1016-B | 1 | 3.58 | 3.58 | 127 | | ug/kg | |
| AR1016-B | 2 | 4.52 | 4.52 | 123 | | ug/kg | |
| AR1016-C | 1 | 4.15 | 4.15 | 110 | | ug/kg | |
| AR1016-C | 2 | 5.16 | 5.16 | 116 | | ug/kg | |
| AR1016-D | 1 | 4.31 | 4.31 | 127 | | ug/kg | |
| AR1016-D | 2 | 5.34 | 5.34 | 126 | | ug/kg | |
| AR1016-E | 1 | 4.81 | 4.81 | 132 | | ug/kg | |
| AR1016-E | 2 | 5.99 | 6.00 | 118 | | ug/kg | |
| Aroclor 1260 | 1 | | | 115 | | ug/kg | 0.9 |
| Aroclor 1260 [b] | 2 [a] | | | 116 | | ug/kg | |
| AR1260-A | 1 | 7.21 | 7.21 | 88.0 | | ug/kg | |
| AR1260-A | 2 | 8.61 | 8.60 | 96.9 | | ug/kg | |
| AR1260-B | 1 | 7.34 | 7.33 | 139 | | ug/kg | |
| AR1260-B | 2 | 8.72 | 8.72 | 131 | | ug/kg | |
| AR1260-C | 1 | 7.68 | 7.67 | 118 | | ug/kg | |
| AR1260-C | 2 | 9.15 | 9.15 | 119 | | ug/kg | |
| AR1260-D | 1 | 8.13 | 8.13 | 134 | | ug/kg | |
| AR1260-D | 2 | 9.51 | 9.51 | 122 | | ug/kg | |
| AR1260-E | 1 | 8.55 | 8.55 | 96.5 | | ug/kg | |
| AR1260-E | 2 | 10.05 | 10.05 | 112 | | ug/kg | |

(a) QC results reported from this column.
(b) Reported from 2nd signal. %D of check calibration on 1st signal exceed method criteria (20%) so using for confirmation only.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GXX5823-CC5786 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198044.D | **Injection Time:** | 16:24 |
| **Instrument ID:** | GCXX | **Method:** | SW846 8082A |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97535-MS | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198050.D | **Injection Time:** | 18:13 |
| **Client ID:** | Matrix Spike | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| Aroclor 1016 | 1 [a] | | | 116 | | ug/kg | 5.0 |
| Aroclor 1016 | 2 | | | 122 | | ug/kg | |
| AR1016-A | 1 | 3.19 | 3.19 | 122 | | ug/kg | |
| AR1016-A | 2 | 3.98 | 3.98 | 117 | | ug/kg | |
| AR1016-B | 1 | 3.58 | 3.58 | 126 | | ug/kg | |
| AR1016-B | 2 | 4.52 | 4.53 | 113 | | ug/kg | |
| AR1016-C | 1 | 4.15 | 4.15 | 121 | | ug/kg | |
| AR1016-C | 2 | 5.16 | 5.16 | 114 | | ug/kg | |
| AR1016-D | 1 | 4.31 | 4.31 | 95.5 | | ug/kg | |
| AR1016-D | 2 | 5.34 | 5.34 | 150 | | ug/kg | |
| AR1016-E | 1 | 4.81 | 4.81 | 113 | | ug/kg | |
| AR1016-E | 2 | 5.99 | 5.99 | 116 | | ug/kg | |
| Aroclor 1260 | 1 [a] | | | 102 | | ug/kg | 18.7 |
| Aroclor 1260 | 2 | | | 123 | | ug/kg | |
| AR1260-A | 1 | 7.18 | 7.21 | 85.5 | | ug/kg | |
| AR1260-A | 2 | 8.60 | 8.60 | 87.6 | | ug/kg | |
| AR1260-B | 1 | 7.33 | 7.33 | 112 | | ug/kg | |
| AR1260-B | 2 | 8.71 | 8.72 | 136 | | ug/kg | |
| AR1260-C | 1 | 7.67 | 7.67 | 95.8 | | ug/kg | |
| AR1260-C | 2 | 9.14 | 9.15 | 155 | | ug/kg | |
| AR1260-D | 1 | 8.10 | 8.13 | 96.8 | | ug/kg | |
| AR1260-D | 2 | 9.50 | 9.51 | 128 | | ug/kg | |
| AR1260-E | 1 | 8.50 | 8.55 | 120 | | ug/kg | |
| AR1260-E | 2 | 10.04 | 10.05 | 111 | | ug/kg | |

(a) QC results reported from this column.

# GC Identification Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GXX5823-CC5786 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198044.D | **Injection Time:** | 16:24 |
| **Instrument ID:** | GCXX | **Method:** | SW846 8082A |

| | | | |
|---|---|---|---|
| **Sample ID:** | OP97535-MSD | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198051.D | **Injection Time:** | 18:30 |
| **Client ID:** | Matrix Spike Duplicate | | |

| Compound | Column | RT | StdRT | Conc | Q | Units | RPD Conc |
|---|---|---|---|---|---|---|---|
| Aroclor 1016 | 1 [a] | | | 102 | | ug/kg | 10.2 |
| Aroclor 1016 | 2 | | | 113 | | ug/kg | |
| AR1016-A | 1 | 3.19 | 3.19 | 83.2 | | ug/kg | |
| AR1016-A | 2 | 3.98 | 3.98 | 106 | | ug/kg | |
| AR1016-B | 1 | 3.58 | 3.58 | 118 | | ug/kg | |
| AR1016-B | 2 | 4.52 | 4.53 | 108 | | ug/kg | |
| AR1016-C | 1 | 4.15 | 4.15 | 113 | | ug/kg | |
| AR1016-C | 2 | 5.16 | 5.16 | 116 | | ug/kg | |
| AR1016-D | 1 | 4.31 | 4.31 | 91.5 | | ug/kg | |
| AR1016-D | 2 | 5.34 | 5.34 | 127 | | ug/kg | |
| AR1016-E | 1 | 4.81 | 4.81 | 106 | | ug/kg | |
| AR1016-E | 2 | 5.99 | 5.99 | 107 | | ug/kg | |
| Aroclor 1260 | 1 [a] | | | 97.6 | | ug/kg | 18.9 |
| Aroclor 1260 | 2 | | | 118 | | ug/kg | |
| AR1260-A | 1 | 7.18 | 7.21 | 87.9 | | ug/kg | |
| AR1260-A | 2 | 8.59 | 8.60 | 88.6 | | ug/kg | |
| AR1260-B | 1 | 7.33 | 7.33 | 95.9 | | ug/kg | |
| AR1260-B | 2 | 8.71 | 8.72 | 133 | | ug/kg | |
| AR1260-C | 1 | 7.67 | 7.67 | 88.3 | | ug/kg | |
| AR1260-C | 2 | 9.14 | 9.15 | 147 | | ug/kg | |
| AR1260-D | 1 | 8.11 | 8.13 | 92.7 | | ug/kg | |
| AR1260-D | 2 | 9.50 | 9.51 | 118 | | ug/kg | |
| AR1260-E | 1 | 8.50 | 8.55 | 123 | | ug/kg | |
| AR1260-E | 2 | 10.04 | 10.05 | 102 | | ug/kg | |

(a) QC results reported from this column.

# Semivolatile Surrogate Recovery Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Method:** SW846 8151 **Matrix:** SO

**Samples and QC shown here apply to the above method**

| Lab Sample ID | Lab File ID | S1 [a] | S1 [b] |
|---|---|---|---|
| JC28902-1 | OA120273.D | 94 | 101 |
| OP97538-BS1 | OA120270.D | 106 | 109 |
| OP97538-MB1 | OA120269.D | 110 | 114 |
| OP97538-MS | 3G103397.D | 14 | 18 |
| OP97538-MSD | 3G103398.D | 73 | 113 |

| Surrogate Compounds | Recovery Limits |
|---|---|
| **S1** = 2,4-DCAA | 10-156% |

(a) Recovery from GC signal #2
(b) Recovery from GC signal #1

# Semivolatile Surrogate Recovery Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Method:** SW846 8081B **Matrix:** SO

**Samples and QC shown here apply to the above method**

| Lab Sample ID | Lab File ID | S1 [a] | S1 [b] | S2 [a] | S2 [b] |
|---|---|---|---|---|---|
| JC28902-1 | 4G73355.D | 77 | 74 | 65 | 78 |
| OP97536-BS1 | 4G73354.D | 81 | 78 | 79 | 97 |
| OP97536-MB1 | 4G73353.D | 92 | 90 | 89 | 107 |
| OP97536-MS | 4G73391.D | 84 | 62 | 58 | 68 |
| OP97536-MSD | 4G73392.D | 105 | 77 | 70 | 84 |

| Surrogate Compounds | Recovery Limits |
|---|---|
| **S1** = Tetrachloro-m-xylene | 24-136% |
| **S2** = Decachlorobiphenyl | 10-153% |

(a) Recovery from GC signal #1
(b) Recovery from GC signal #2

# Semivolatile Surrogate Recovery Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Method:** SW846 8082A **Matrix:** SO

**Samples and QC shown here apply to the above method**

| Lab Sample ID | Lab File ID | S1 [a] | S1 [b] | S2 [a] | S2 [b] |
|---|---|---|---|---|---|
| JC28902-1 | XX198049.D | 89 | 88 | 83 | 80 |
| OP97535-BS1 | XX198041.D | 97 | 91 | 103 | 89 |
| OP97535-MB1 | XX198040.D | 101 | 95 | 114 | 96 |
| OP97535-MS | XX198050.D | 83 | 86 | 77 | 78 |
| OP97535-MSD | XX198051.D | 65 | 68 | 69 | 74 |

| Surrogate Compounds | Recovery Limits |
|---|---|
| **S1** = Tetrachloro-m-xylene | 20-152% |
| **S2** = Decachlorobiphenyl | 12-157% |

(a) Recovery from GC signal #1
(b) Recovery from GC signal #2

# Semivolatile Surrogate Recovery Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Method:** NJDEP EPH **Matrix:** SO

**Samples and QC shown here apply to the above method**

| Lab Sample ID | Lab File ID | S1 [a] | S2 [a] |
|---|---|---|---|
| JC28902-1 | 5Y36634.D | 63 | 69 |
| OP97541-BS11 | 5Z30027.D | 90 | 107 |
| OP97541-DUP | 5Y36630.D | 68 | 74 |
| OP97541-MB1 | 5Y36627.D | 68 | 72 |
| OP97541-MB1 | 5Z30028.D | 84 | 97 |
| OP97541-MS | 5Z30030.D | 105 | 85 |
| OP97541-MSD | 5Z30031.D | 103 | 84 |

| Surrogate Compounds | Recovery Limits |
|---|---|
| **S1** = o-Terphenyl | 40-140% |
| **S2** = 1-Chlorooctadecane | 40-140% |

(a) Recovery from GC signal #1

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G5Y1211-CC1190 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 5Y36625.D | **Injection Time:** | 10:21 |
| **Instrument ID:** | GC5Y | **Method:** | NJDEP EPH |

| | S1 [a] RT | S2 [a] RT |
|---|---|---|
| Check Std | 11.97 | 13.28 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S2 [a] RT |
|---|---|---|---|---|---|
| OP97541-MB1 | 5Y36627.D | 10/06/16 | 12:05 | 11.96 | 13.28 |
| ZZZZZZ | 5Y36628.D | 10/06/16 | 12:36 | 11.96 | 13.27 |
| JC28910-2 | 5Y36629.D | 10/06/16 | 13:07 | 11.96 | 13.27 |
| OP97541-DUP | 5Y36630.D | 10/06/16 | 13:38 | 11.96 | 13.28 |

**Surrogate Compounds**

**S1** = o-Terphenyl
**S2** = 1-Chlorooctadecane

(a) Retention time from GC signal #1

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G5Y1211-CC1190 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 5Y36632.D | **Injection Time:** | 14:41 |
| **Instrument ID:** | GC5Y | **Method:** | NJDEP EPH |

| | S1 [a] RT | S2 [a] RT |
|---|---|---|
| Check Std | 11.96 | 13.27 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S2 [a] RT |
|---|---|---|---|---|---|
| JC28902-1 | 5Y36634.D | 10/06/16 | 16:01 | 11.96 | 13.28 |
| ZZZZZZ | 5Y36635.D | 10/06/16 | 16:32 | 11.97 | 13.28 |

**Surrogate Compounds**

**S1** = o-Terphenyl
**S2** = 1-Chlorooctadecane

(a) Retention time from GC signal #1

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G5Z1032-CC1024 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 5Z30025.D | **Injection Time:** | 10:21 |
| **Instrument ID:** | GC5Z | **Method:** | NJDEP EPH |

| | S1 [a] RT | S2 [a] RT |
|---|---|---|
| Check Std | 11.67 | 12.97 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S2 [a] RT |
|---|---|---|---|---|---|
| OP97541-BS11 | 5Z30027.D | 10/06/16 | 12:05 | 11.67 | 12.97 |
| OP97541-MB1 | 5Z30028.D | 10/06/16 | 12:36 | 11.67 | 12.97 |
| JC28906-2 | 5Z30029.D | 10/06/16 | 13:07 | 11.69 | 12.98 |
| OP97541-MS | 5Z30030.D | 10/06/16 | 13:38 | 11.70 | 12.99 |
| OP97541-MSD | 5Z30031.D | 10/06/16 | 14:09 | 11.70 | 12.98 |

**Surrogate Compounds**

**S1** = o-Terphenyl
**S2** = 1-Chlorooctadecane

(a) Retention time from GC signal #1

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G3G3614-CC3591 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 3G103394.D | **Injection Time:** | 09:07 |
| **Instrument ID:** | GC3G | **Method:** | SW846 8151 |

| | S1 [a] RT | S1 [b] RT |
|---|---|---|
| Check Std | 8.10 | 7.20 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S1 [b] RT |
|---|---|---|---|---|---|
| JC28904-1A | 3G103396.D | 10/07/16 | 10:08 | 8.09 | 7.18 |
| OP97538-MS | 3G103397.D | 10/07/16 | 10:39 | 8.10 | 7.21 |
| OP97538-MSD | 3G103398.D | 10/07/16 | 11:09 | 8.09 | 7.20 |
| OP97571-MB1 | 3G103399.D | 10/07/16 | 11:39 | 8.10 | 7.20 |
| OP97571-BS1 | 3G103400.D | 10/07/16 | 12:10 | 8.09 | 7.20 |
| ZZZZZZ | 3G103401.D | 10/07/16 | 12:40 | 8.10 | 7.20 |
| ZZZZZZ | 3G103402.D | 10/07/16 | 13:11 | 8.10 | 7.20 |
| ZZZZZZ | 3G103403.D | 10/07/16 | 13:41 | 8.10 | 7.20 |

**Surrogate Compounds**

**S1** = 2,4-DCAA

(a) Retention time from GC signal #2
(b) Retention time from GC signal #1

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GOA4139-CC4125 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | OA120267.D | **Injection Time:** | 09:18 |
| **Instrument ID:** | GCOA | **Method:** | SW846 8151 |

| | S1 [a] RT | S1 [b] RT |
|---|---|---|
| Check Std | 8.05 | 7.19 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S1 [b] RT |
|---|---|---|---|---|---|
| OP97538-MB1 | OA120269.D | 10/07/16 | 10:16 | 8.05 | 7.19 |
| OP97538-BS1 | OA120270.D | 10/07/16 | 10:44 | 8.05 | 7.18 |
| ZZZZZZ | OA120271.D | 10/07/16 | 11:12 | 8.05 | 7.18 |
| ZZZZZZ | OA120272.D | 10/07/16 | 11:41 | 8.05 | 7.18 |
| JC28902-1 | OA120273.D | 10/07/16 | 12:09 | 8.05 | 7.19 |
| ZZZZZZ | OA120274.D | 10/07/16 | 12:37 | 0.00 | 0.00 |

**Surrogate Compounds**

**S1** = 2,4-DCAA

(a) Retention time from GC signal #2
(b) Retention time from GC signal #1

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GXX5823-CC5786 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198038.D | **Injection Time:** | 14:28 |
| **Instrument ID:** | GCXX | **Method:** | SW846 8082A |

| | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|
| Check Std | 2.80 | 3.34 | 10.03 | 11.71 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|---|---|---|
| OP97535-MB1 | XX198040.D | 10/06/16 | 15:02 | 2.80 | 3.34 | 10.03 | 11.71 |
| OP97535-BS1 | XX198041.D | 10/06/16 | 15:19 | 2.81 | 3.34 | 10.03 | 11.71 |
| ZZZZZZ | XX198042.D | 10/06/16 | 15:35 | 2.81 | 3.34 | 10.03 | 11.71 |
| ZZZZZZ | XX198043.D | 10/06/16 | 15:52 | 2.81 | 3.34 | 10.03 | 11.71 |

**Surrogate Compounds**

**S1** = Tetrachloro-m-xylene
**S2** = Decachlorobiphenyl

(a) Retention time from GC signal #1
(b) Retention time from GC signal #2

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1919-CC1911 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | 4G73351.D | **Injection Time:** | 17:13 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|
| Check Std | 1.99 | 1.88 | 8.88 | 9.83 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|---|---|---|
| OP97536-MB1 | 4G73353.D | 10/06/16 | 17:42 | 1.99 | 1.88 | 8.88 | 9.83 |
| OP97536-BS1 | 4G73354.D | 10/06/16 | 17:56 | 1.99 | 1.88 | 8.88 | 9.83 |
| JC28902-1 | 4G73355.D | 10/06/16 | 18:11 | 1.99 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73360.D | 10/06/16 | 19:23 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73362.D | 10/06/16 | 19:52 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73363.D | 10/06/16 | 20:06 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73366.D | 10/06/16 | 20:49 | 2.00 | 1.89 | 8.88 | 9.83 |

**Surrogate Compounds**

**S1** = Tetrachloro-m-xylene
**S2** = Decachlorobiphenyl

(a) Retention time from GC signal #1
(b) Retention time from GC signal #2

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | G4G1920-CC1911 | **Injection Date:** | 10/07/16 |
| **Lab File ID:** | 4G73382.D | **Injection Time:** | 09:09 |
| **Instrument ID:** | GC4G | **Method:** | SW846 8081B |

| | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|
| Check Std | 1.99 | 1.88 | 8.88 | 9.83 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|---|---|---|
| OP97573-MB1 | 4G73384.D | 10/07/16 | 09:54 | 1.99 | 1.87 | 8.89 | 9.83 |
| OP97573-BS1 | 4G73385.D | 10/07/16 | 10:08 | 1.99 | 1.88 | 8.88 | 9.83 |
| ZZZZZZ | 4G73386.D | 10/07/16 | 10:23 | 1.99 | 1.88 | 8.88 | 9.83 |
| ZZZZZZ | 4G73389.D | 10/07/16 | 11:06 | 1.99 | 1.88 | 8.88 | 9.83 |
| JC28906-1 | 4G73390.D | 10/07/16 | 11:21 | 2.00 | 1.89 | 8.88 | 9.83 |
| OP97536-MS | 4G73391.D | 10/07/16 | 11:35 | 2.00 | 1.89 | 8.88 | 9.83 |
| OP97536-MSD | 4G73392.D | 10/07/16 | 11:49 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73393.D | 10/07/16 | 12:04 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73394.D | 10/07/16 | 12:18 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73395.D | 10/07/16 | 12:33 | 2.00 | 1.89 | 8.88 | 9.83 |
| ZZZZZZ | 4G73396.D | 10/07/16 | 12:47 | 1.99 | 1.88 | 8.88 | 9.83 |
| ZZZZZZ | 4G73397.D | 10/07/16 | 13:01 | 1.99 | 1.89 | 8.88 | 9.83 |
| JC28920-6A | 4G73398.D | 10/07/16 | 13:16 | 1.99 | 1.89 | 8.88 | 9.83 |
| OP97573-LS12 | 4G73399.D | 10/07/16 | 13:30 | 1.99 | 1.88 | 8.88 | 9.83 |
| OP97573-MS | 4G73399.D | 10/07/16 | 13:30 | 1.99 | 1.88 | 8.88 | 9.83 |
| OP97573-MSD | 4G73400.D | 10/07/16 | 13:45 | 2.00 | 1.89 | 8.88 | 9.83 |
| OP97573-LB31 | 4G73401.D | 10/07/16 | 13:59 | 2.00 | 1.89 | 8.88 | 9.83 |

**Surrogate Compounds**

**S1** = Tetrachloro-m-xylene
**S2** = Decachlorobiphenyl

(a) Retention time from GC signal #1
(b) Retention time from GC signal #2

# GC Surrogate Retention Time Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | |
|---|---|---|---|
| **Check Std:** | GXX5823-CC5786 | **Injection Date:** | 10/06/16 |
| **Lab File ID:** | XX198044.D | **Injection Time:** | 16:24 |
| **Instrument ID:** | GCXX | **Method:** | SW846 8082A |

| | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|
| Check Std | 2.80 | 3.34 | 10.03 | 11.71 |

| Lab Sample ID | Lab File ID | Date Analyzed | Time Analyzed | S1 [a] RT | S1 [b] RT | S2 [a] RT | S2 [b] RT |
|---|---|---|---|---|---|---|---|
| ZZZZZZ | XX198046.D | 10/06/16 | 17:06 | 2.80 | 3.34 | 10.03 | 11.71 |
| ZZZZZZ | XX198047.D | 10/06/16 | 17:23 | 2.80 | 3.34 | 10.02 | 11.70 |
| ZZZZZZ | XX198048.D | 10/06/16 | 17:40 | 2.81 | 3.34 | 10.02 | 11.70 |
| JC28902-1 | XX198049.D | 10/06/16 | 17:57 | 2.81 | 3.34 | 10.02 | 11.71 |
| OP97535-MS | XX198050.D | 10/06/16 | 18:13 | 2.81 | 3.34 | 10.02 | 11.71 |
| OP97535-MSD | XX198051.D | 10/06/16 | 18:30 | 2.80 | 3.34 | 10.02 | 11.71 |
| ZZZZZZ | XX198052.D | 10/06/16 | 18:47 | 2.80 | 3.34 | 10.02 | 11.71 |

**Surrogate Compounds**

**S1** = Tetrachloro-m-xylene
**S2** = Decachlorobiphenyl

(a) Retention time from GC signal #1
(b) Retention time from GC signal #2

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G3G3591-ICC3591
**Lab FileID:** 3G102648.D

Response Factor Report GC3G

Method : C:\MSDCHEM\1\METHODS\3H3591.M (Chemstation Integrator)
Title : HERB
Last Update : Thu Sep 08 16:38:34 2016
Response via : Initial Calibration

Calibration Files
500 =3G102650.D 400 =3G102649.D 300 =3G102648.D 200 =3G102647.D
100 =3G102646.D 50 =3G102645.D

| | | Compound | 500 | 400 | 300 | 200 | 100 | 50 | Avg | | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) | | Dalapon | 7.441 | 7.576 | 7.657 | 8.096 | 8.746 | 8.717 | 8.039 | E6 | 7.21 |
| 2) | S | 2,4-DCAA | 4.488 | 4.601 | 4.685 | 5.000 | 5.590 | 6.096 | 5.077 | E6 | 12.57 |
| 3) | | Dicamba | 2.136 | 2.196 | 2.221 | 2.343 | 2.612 | 2.805 | 2.386 | E7 | 11.16 |
| 4) | | MCPP | 1.341 | 1.382 | 1.409 | 1.489 | 1.684 | | 1.461 | E4 | 9.30 |
| 5) | | MCPA | 2.015 | 2.098 | 2.158 | 2.341 | 2.909 | | 2.304 | E4 | 15.58 |
| 6) | | Dichloroprop | 4.947 | 5.121 | 5.749 | 5.794 | 6.542 | 7.249 | 5.900 | E6 | 14.74 |
| 7) | | 2,4-D | 6.369 | 6.539 | 7.146 | 7.245 | 7.648 | 7.771 | 7.120 | E6 | 8.00 |
| 8) | | Pentachlorophenol | 1.188 | 1.207 | 1.243 | 1.265 | 1.294 | 1.320 | 1.253 | E8 | 4.04 |
| 9) | | 2,4,5-TP | 3.651 | 3.746 | 3.825 | 3.968 | 4.021 | 3.630 | 3.807 | E7 | 4.26 |
| 10) | | 2,4,5-T | 3.713 | 3.741 | 3.766 | 3.896 | 3.904 | 4.031 | 3.842 | E7 | 3.19 |
| 11) | | 2,4-DB | 3.415 | 3.457 | 3.642 | 4.134 | 4.017 | 4.635 | 3.884 | E6 | 12.11 |
| 12) | | Dinoseb | 1.850 | 1.911 | 1.944 | 2.140 | 2.334 | 2.810 | 2.165 | E7 | 16.76 |
| 13) | | Picloram | 3.454 | 3.522 | 3.529 | 3.655 | 3.730 | 3.777 | 3.611 | E7 | 3.57 |

Signal #2

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) | | Dalapon | 1.426 | 1.458 | 1.477 | 1.542 | 1.615 | 1.731 | 1.541 | E7 | 7.43 |
| 2) | S | 2,4-DCAA | 5.027 | 5.152 | 5.310 | 5.679 | 6.571 | 7.517 | 5.876 | E6 | 16.64 |
| 3) | | Dicamba | 3.509 | 3.609 | 3.701 | 3.783 | 4.115 | 4.473 | 3.865 | E7 | 9.38 |
| 4) | | MCPP | 8.629 | 8.397 | 7.687 | 6.670 | 5.076 | | 7.292 | E3 | 19.95 |
| 5) | | MCPA | 1.369 | 1.322 | 1.239 | 1.091 | 0.856 | | 1.175 | E4 | 17.64 |
| 6) | | Dichloroprop | 0.738 | 0.756 | 0.807 | 0.839 | 0.980 | 1.032 | 0.859 | E7 | 14.07 |
| 7) | | 2,4-D | 0.841 | 0.977 | 0.938 | 1.050 | 1.215 | 1.179 | 1.033 | E7 | 13.92 |
| 8) | | Pentachlorophenol | 2.637 | 2.682 | 2.602 | 2.648 | 2.684 | 2.732 | 2.664 | E8 | 1.70 |
| 9) | | 2,4,5-TP | 7.944 | 8.044 | 8.225 | 8.278 | 8.589 | 8.636 | 8.286 | E7 | 3.39 |
| 10) | | 2,4,5-T | 7.661 | 7.552 | 7.701 | 7.682 | 8.169 | 8.303 | 7.845 | E7 | 3.96 |
| 11) | | 2,4-DB | 5.219 | 5.231 | 5.299 | 5.455 | 5.522 | 4.760 | 5.248 | E6 | 5.11 |
| 12) | | Dinoseb | 3.428 | 3.528 | 3.636 | 3.861 | 4.183 | 4.791 | 3.904 | E7 | 13.09 |
| 13) | | Picloram | 1.054 | 1.090 | 1.098 | 1.114 | 1.164 | 1.082 | 1.100 | E8 | 3.35 |

(#) = Out of Range

3H3591.M Thu Sep 08 16:40:51 2016 GC3G

8.10.1

8

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G3G3591-ICV3591
**Lab FileID:** 3G102651.D

Evaluate Continuing Calibration Report

Signal #1 : C:\MSDCHEM\1\DATA\3G3591\3G102651.D\ECD1A.CH Vial: 42
Signal #2 : C:\MSDCHEM\1\DATA\3G3591\3G102651.D\ECD2B.CH
Acq On : 9-8-2016 04:03:33 PM Operator: josephr
Sample : icv3591-300 Inst : GC3G
Misc : op96824,g3g3591,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\3H3591.M (Chemstation Integrator)
Title : HERB
Last Update : Thu Sep 08 16:38:34 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | Dalapon | 8.039 | 8.262 | E6 | -2.8 | 108 | 0.00 | 2.32- 2.38 |
| 2 | S | 2,4-DCAA | 5.077 | 4.901 | E6 | 3.5 | 105 | 0.00 | 7.19- 7.25 |
| 3 | | Dicamba | 23.856 | 23.451 | E6 | 1.7 | 106 | 0.00 | 7.39- 7.45 |
| 4 | | MCPP | 14.612 | 14.352 | E3 | 1.8 | 102 | 0.00 | 7.63- 7.69 |
| 5 | | MCPA | 23.041 | 21.441 | E3 | 6.9 | 99 | 0.00 | 7.80- 7.86 |
| 6 | | Dichloroprop | 5.900 | 5.200 | E6 | 11.9 | 90 | 0.00 | 8.24- 8.30 |
| 7 | | 2,4-D | 7.120 | 7.427 | E6 | -4.3 | 104 | 0.00 | 8.52- 8.59 |
| 8 | | Pentachlorophenol | 125.289 | 106.292 | E6 | 15.2 | 86 | 0.00 | 8.75- 8.81 |
| 9 | | 2,4,5-TP | 38.069 | 40.238 | E6 | -5.7 | 105 | 0.00 | 9.56- 9.62 |
| 10 | | 2,4,5-T | 38.419 | 41.865 | E6 | -9.0 | 111 | 0.00 | 9.92- 9.99 |
| 11 | | 2,4-DB | 3.884 | 3.934 | E6 | -1.3 | 108 | 0.00 | 10.61-10.71 |
| 12 | | Dinoseb | 21.651 | 24.001 | E6 | -10.9 | 123 | 0.00 | 12.02-12.08 |
| 13 | | Picloram | 36.110 | 32.478 | E6 | 10.1 | 92 | 0.00 | 11.80-11.86 |

***** Signal #2 *****

| | | Compound | AvgRF | CCRF | | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | Dalapon | 15.415 | 14.532 | E6 | 5.7 | 98 | 0.00 | 2.51- 2.57 |
| 2 | S | 2,4-DCAA | 5.876 | 5.418 | E6 | 7.8 | 102 | 0.00 | 8.07- 8.13 |
| 3 | | Dicamba | 38.652 | 38.721 | E6 | -0.2 | 105 | 0.00 | 8.30- 8.36 |
| 4 | | MCPP | 7.292 | 8.131 | E3 | -11.5 | 106 | 0.00 | 8.45- 8.51 |
| 5 | | MCPA | 11.752 | 11.916 | E3 | -1.4 | 96 | 0.00 | 8.77- 8.83 |
| 6 | | Dichloroprop | 8.587 | 7.591 | E6 | 11.6 | 94 | 0.00 | 9.22- 9.28 |
| 7 | | 2,4-D | 10.335 | 9.802 | E6 | 5.2 | 104 | 0.00 | 9.66- 9.72 |
| 8 | | Pentachlorophenol | 266.397 | 225.381 | E6 | 15.4 | 87 | 0.00 | 10.16-10.22 |
| 9 | | 2,4,5-TP | 82.859 | 86.037 | E6 | -3.8 | 105 | 0.00 | 10.77-10.83 |
| 10 | | 2,4,5-T | 78.445 | 81.729 | E6 | -4.2 | 106 | 0.00 | 11.30-11.42 |
| 11 | | 2,4-DB | 5.248 | 5.503 | E6 | -4.9 | 104 | 0.00 | 12.03-12.13 |
| 12 | | Dinoseb | 39.044 | 44.833 | E6 | -14.8 | 123 | 0.00 | 12.44-12.51 |
| 13 | | Picloram | 110.022 | 97.680 | E6 | 11.2 | 89 | 0.00 | 13.92-13.98 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
3G102648.D 3H3591.M Thu Sep 08 16:41:05 2016 GC3G

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G3G3614-CC3591
**Lab FileID:** 3G103394.D

Evaluate Continuing Calibration Report

Signal #1 : C:\MSDCHEM\1\DATA\3G3614\3G103394.D\ECD1A.CH Vial: 2
Signal #2 : C:\MSDCHEM\1\DATA\3G3614\3G103394.D\ECD2B.CH
Acq On : 10-7-2016 09:07:41 AM Operator: vinced
Sample : cc3591-200 Inst : GC3G
Misc : op97545,g3g3614,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\3H3591.M (Chemstation Integrator)
Title : HERB
Last Update : Fri Oct 07 15:00:12 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 1 | Dalapon | 8.039 | 7.187 E6 | 10.6 | 89 | 0.00 | 2.30- 2.36 |
| 2 S | 2,4-DCAA | 5.077 | 5.089 E6 | -0.2 | 102 | 0.00 | 7.17- 7.23 |
| 3 | Dicamba | 23.856 | 22.810 E6 | 4.4 | 97 | 0.00 | 7.37- 7.43 |
| 4 | MCPP | 14.612 | 17.805 E3 | -21.9# | 120 | 0.00 | 7.61- 7.67 |
| 5 | MCPA | 23.041 | 28.445 E3 | -23.5# | 122 | 0.00 | 7.78- 7.84 |
| 6 | Dichloroprop | 5.900 | 6.108 E6 | -3.5 | 105 | 0.00 | 8.22- 8.28 |
| 7 | 2,4-D | 7.120 | 7.739 E6 | -8.7 | 107 | 0.00 | 8.50- 8.57 |
| 8 | Pentachlorophenol | 125.289 | 131.244 E6 | -4.8 | 104 | 0.00 | 8.72- 8.78 |
| 9 | 2,4,5-TP | 38.069 | 40.968 E6 | -7.6 | 103 | 0.00 | 9.54- 9.60 |
| 10 | 2,4,5-T | 38.419 | 40.220 E6 | -4.7 | 103 | 0.00 | 9.90- 9.97 |
| 11 | 2,4-DB | 3.884 | 4.086 E6 | -5.2 | 99 | 0.00 | 10.59-10.68 |
| 12 | Dinoseb | 21.651 | 24.967 E6 | -15.3 | 117 | 0.00 | 11.98-12.04 |
| 13 | Picloram | 36.110 | 40.249 E6 | -11.5 | 110 | 0.00 | 11.77-11.83 |

***** Signal #2 *****

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 1 | Dalapon | 15.415 | 15.425 E6 | -0.1 | 100 | 0.00 | 2.50- 2.56 |
| 2 S | 2,4-DCAA | 5.876 | 5.878 E6 | -0.0 | 103 | 0.00 | 8.07- 8.13 |
| 3 | Dicamba | 38.652 | 40.496 E6 | -4.8 | 107 | 0.00 | 8.29- 8.35 |
| 4 | MCPP | 7.292 | 6.753 E3 | 7.4 | 101 | 0.00 | 8.45- 8.51 |
| 5 | MCPA | 11.752 | 10.713 E3 | 8.8 | 98 | 0.00 | 8.76- 8.82 |
| 6 | Dichloroprop | 8.587 | 8.727 E6 | -1.6 | 104 | 0.00 | 9.22- 9.28 |
| 7 | 2,4-D | 10.335 | 10.761 E6 | -4.1 | 102 | 0.00 | 9.66- 9.72 |
| 8 | Pentachlorophenol | 266.397 | 284.104 E6 | -6.6 | 107 | 0.00 | 10.14-10.20 |
| 9 | 2,4,5-TP | 82.859 | 88.805 E6 | -7.2 | 107 | 0.00 | 10.76-10.82 |
| 10 | 2,4,5-T | 78.445 | 83.934 E6 | -7.0 | 109 | 0.00 | 11.30-11.42 |
| 11 | 2,4-DB | 5.248 | 4.616 E6 | 12.0 | 85 | 0.00 | 12.03-12.12 |
| 12 | Dinoseb | 39.044 | 45.888 E6 | -17.5 | 119 | 0.00 | 12.43-12.50 |
| 13 | Picloram | 110.022 | 120.574 E6 | -9.6 | 108 | 0.00 | 13.91-13.97 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
3G102647.D 3H3591.M Fri Oct 07 15:00:21 2016 GC3G

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G3G3614-CC3591
**Lab FileID:** 3G103404.D

Evaluate Continuing Calibration Report

Signal #1 : C:\MSDCHEM\1\DATA\3G3614\3G103404.D\ECD1A.CH Vial: 3
Signal #2 : C:\MSDCHEM\1\DATA\3G3614\3G103404.D\ECD2B.CH
Acq On : 10-7-2016 02:12:11 PM Operator: vinced
Sample : cc3591-300 Inst : GC3G
Misc : op97571,g3g3614,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\3H3591.M (Chemstation Integrator)
Title : HERB
Last Update : Fri Oct 07 15:00:12 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | Dalapon | 8.039 | 6.965 | E6 | 13.4 | 91 | 0.00 | 2.30- 2.36 |
| 2 S | 2,4-DCAA | 5.077 | 4.812 | E6 | 5.2 | 103 | 0.00 | 7.17- 7.23 |
| 3 | Dicamba | 23.856 | 21.956 | E6 | 8.0 | 99 | 0.00 | 7.36- 7.42 |
| 4 | MCPP | 14.612 | 17.344 | E3 | -18.7 | 123 | 0.00 | 7.61- 7.67 |
| 5 | MCPA | 23.041 | 28.003 | E3 | -21.5# | 130 | 0.00 | 7.78- 7.84 |
| 6 | Dichloroprop | 5.900 | 5.654 | E6 | 4.2 | 98 | 0.00 | 8.21- 8.27 |
| 7 | 2,4-D | 7.120 | 7.272 | E6 | -2.1 | 102 | 0.00 | 8.49- 8.56 |
| 8 | Pentachlorophenol | 125.289 | 126.431 | E6 | -0.9 | 102 | 0.00 | 8.72- 8.78 |
| 9 | 2,4,5-TP | 38.069 | 40.372 | E6 | -6.0 | 106 | 0.00 | 9.53- 9.59 |
| 10 | 2,4,5-T | 38.419 | 40.130 | E6 | -4.5 | 107 | 0.00 | 9.89- 9.96 |
| 11 | 2,4-DB | 3.884 | 3.851 | E6 | 0.8 | 106 | 0.00 | 10.58-10.68 |
| 12 | Dinoseb | 21.651 | 21.023 | E6 | 2.9 | 108 | 0.00 | 11.98-12.04 |
| 13 | Picloram | 36.110 | 35.826 | E6 | 0.8 | 102 | 0.00 | 11.77-11.83 |

***** Signal #2 *****

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 | Dalapon | 15.415 | 14.945 | E6 | 3.0 | 101 | 0.00 | 2.50- 2.56 |
| 2 S | 2,4-DCAA | 5.876 | 5.548 | E6 | 5.6 | 104 | 0.00 | 8.07- 8.13 |
| 3 | Dicamba | 38.652 | 39.679 | E6 | -2.7 | 107 | 0.00 | 8.29- 8.35 |
| 4 | MCPP | 7.292 | 7.874 | E3 | -8.0 | 102 | 0.00 | 8.45- 8.51 |
| 5 | MCPA | 11.752 | 12.414 | E3 | -5.6 | 100 | 0.00 | 8.76- 8.82 |
| 6 | Dichloroprop | 8.587 | 8.350 | E6 | 2.8 | 104 | 0.00 | 9.21- 9.27 |
| 7 | 2,4-D | 10.335 | 10.359 | E6 | -0.2 | 110 | 0.00 | 9.66- 9.72 |
| 8 | Pentachlorophenol | 266.397 | 280.898 | E6 | -5.4 | 108 | 0.00 | 10.14-10.20 |
| 9 | 2,4,5-TP | 82.859 | 86.124 | E6 | -3.9 | 105 | 0.00 | 10.76-10.82 |
| 10 | 2,4,5-T | 78.445 | 82.053 | E6 | -4.6 | 107 | 0.00 | 11.29-11.41 |
| 11 | 2,4-DB | 5.248 | 5.822 | E6 | -10.9 | 110 | 0.00 | 12.03-12.12 |
| 12 | Dinoseb | 39.044 | 37.336 | E6 | 4.4 | 103 | 0.00 | 12.43-12.50 |
| 13 | Picloram | 110.022 | 117.539 | E6 | -6.8 | 107 | 0.00 | 13.91-13.97 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
3G102648.D 3H3591.M Fri Oct 07 15:00:39 2016 GC3G

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G4G1911-ICC1911
**Lab FileID:** 4G72948.D

Response Factor Report GC4G

Method : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title : PEST/PCB
Last Update : Thu Sep 29 09:14:27 2016
Response via : Initial Calibration

Calibration Files
2 =4g72945.D 5 =4g72946.D 10 =4g72947.D 25 =4g72948.D
50 =4g72949.D 100 =4g72951.D 1 =4g72944.D 75 =4g72950.D

| Compound | 2 | 5 | 10 | 25 | 50 | 100 | 1 | 75 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 1) I 1-bromo-2-nitrobenzen | ISTD | | | | | | | | | |
| 2) Tetrachloro- | 0.750 | 0.863 | 0.865 | 0.870 | 0.876 | 0.916 | | 0.891 | 0.861 | 6.09 |
| 3) alpha-BHC | 1.131 | 1.103 | 1.114 | 1.159 | 1.225 | 1.393 | 1.290 | 1.293 | 1.214 | 8.62 |
| 4) gamma-BHC | 1.166 | 1.069 | 1.105 | 1.065 | 1.121 | 1.267 | 1.254 | 1.175 | 1.153 | 6.72 |
| 5) Heptachlor | 1.077 | 1.002 | 0.995 | 0.989 | 1.023 | 1.141 | 1.161 | 1.070 | 1.057 | 6.31 |
| 6) beta-BHC | 0.588 | 0.494 | 0.505 | 0.478 | 0.484 | 0.520 | 0.495 | 0.502 | 0.508 | 6.82 |
| 7) delta-BHC | 0.933 | 0.906 | 0.935 | 0.924 | 1.012 | 1.121 | 1.092 | 1.081 | 1.001 | 8.69 |
| 8) Aldrin | 1.041 | 0.999 | 0.976 | 0.997 | 1.047 | 1.178 | 1.161 | 1.087 | 1.061 | 7.14 |
| 9) Heptachlor E | 0.943 | 0.939 | 0.936 | 0.934 | 0.957 | 1.023 | 0.990 | 0.976 | 0.962 | 3.29 |
| 10) gamma-Chlord | 1.128 | 1.006 | 0.974 | 0.958 | 0.983 | 1.089 | 1.513 | 1.014 | 1.083 | 16.90 |
| 11) alpha-Chlord | 1.022 | 0.953 | 0.950 | 0.936 | 0.964 | 1.068 | 1.146 | 0.994 | 1.004 | 7.17 |
| 12) Endosulfan I | 0.974 | 0.929 | 0.924 | 0.916 | 0.939 | 1.032 | 1.124 | 0.965 | 0.975 | 7.26 |
| 13) 4,4'-DDE | 0.953 | 0.917 | 0.924 | 0.927 | 0.963 | 1.079 | 1.215 | 0.999 | 0.997 | 10.32 |
| 14) Dieldrin | 0.981 | 0.954 | 0.940 | 0.953 | 0.990 | 1.103 | 1.149 | 1.027 | 1.012 | 7.51 |
| 15) Endrin | 0.746 | 0.692 | 0.676 | 0.670 | 0.691 | 0.756 | 0.915 | 0.709 | 0.732 | 10.98 |
| 16) 4,4'-DDD | 0.785 | 0.761 | 0.763 | 0.772 | 0.804 | 0.906 | 0.851 | 0.838 | 0.810 | 6.32 |
| 17) Endosulfan I | 0.931 | 0.883 | 0.861 | 0.853 | 0.872 | 0.951 | 1.119 | 0.908 | 0.922 | 9.37 |
| 18) 4,4'-DDT | 0.708 | 0.645 | 0.648 | 0.661 | 0.707 | 0.809 | 0.934 | 0.749 | 0.733 | 13.43 |
| 19) Endrin Aldeh | 0.734 | 0.731 | 0.727 | 0.730 | 0.740 | 0.812 | 0.902 | 0.776 | 0.769 | 7.97 |
| 20) Endosulfan S | 0.707 | 0.673 | 0.695 | 0.674 | 0.699 | 0.744 | 0.863 | 0.719 | 0.722 | 8.54 |
| 21) Methoxychlor | 0.338 | 0.330 | 0.342 | 0.341 | 0.357 | 0.387 | 0.435 | 0.366 | 0.362 | 9.61 |
| 22) Mirex | 0.862 | 0.772 | 0.768 | 0.741 | 0.738 | 0.782 | 0.983 | 0.744 | 0.799 | 10.56 |
| 23) Endrin Keton | 0.888 | 0.851 | 0.883 | 0.861 | 0.891 | 0.982 | 1.069 | 0.929 | 0.919 | 7.97 |
| 24) Decachlorobi | 1.082 | 0.917 | 0.880 | 0.863 | 0.859 | 0.916 | 1.168 | 0.872 | 0.945 | 12.26 |
| 25) I 1-bromo-2-nitrobenzen | ISTD | | | | | | | | | |
| 26) Toxaphene{A} | | | | 0.014 | | | | | 0.014 | 0.00 |
| 27) Toxaphene{B} | | | | 0.030 | | | | | 0.030 | 0.00 |
| 28) Toxaphene{C} | | | | 0.029 | | | | | 0.029 | 0.00 |
| 29) Toxaphene{D} | | | | 0.028 | | | | | 0.028 | 0.00 |
| 30) Toxaphene{E} | | | | 0.026 | | | | | 0.026 | 0.00 |
| 31) I 1-bromo-2-nitrobenzen | ISTD | | | | | | | | | |
| 32) Chlordane {A | | | | 0.048 | | | | | 0.048 | 0.00 |
| 33) Chlordane {B | | | | 0.044 | | | | | 0.044 | 0.00 |
| 34) Chlordane {C | | | | 0.131 | | | | | 0.131 | 0.00 |
| 35) Chlordane {D | | | | 0.207 | | | | | 0.207 | 0.00 |
| 36) Chlordane {E | | | | 0.035 | | | | | 0.035 | 0.00 |

Signal #2

| Compound | 2 | 5 | 10 | 25 | 50 | 100 | 1 | 75 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|
| 1) I 1-bromo-2-nitrobenzen | ISTD | | | | | | | | | |
| 2) Tetrachloro- | 0.914 | 0.882 | 0.882 | 0.847 | 0.870 | 0.887 | 0.956 | 0.875 | 0.889 | 3.68 |
| 3) alpha-BHC | 1.076 | 1.099 | 1.094 | 1.136 | 1.238 | 1.320 | 1.091 | 1.262 | 1.165 | 8.11 |
| 4) gamma-BHC | 1.013 | 1.015 | 1.003 | 1.041 | 1.104 | 1.176 | 0.993 | 1.134 | 1.060 | 6.49 |

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G4G1911-ICC1911
**Lab FileID:** 4G72948.D

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 5) | Heptachlor | 1.118 | 1.083 | 1.023 | 1.021 | 1.058 | 1.089 | 1.220 | 1.072 | 1.086 | 5.84 |
| 6) | beta-BHC | 0.530 | 0.532 | 0.503 | 0.478 | 0.496 | 0.496 | 0.480 | 0.488 | 0.500 | 4.12 |
| 7) | delta-BHC | 0.734 | 0.770 | 0.771 | 0.823 | 0.913 | 0.969 | 0.764 | 0.964 | 0.838 | 11.44 |
| 8) | Aldrin | 1.033 | 1.004 | 0.979 | 1.003 | 1.052 | 1.106 | 1.065 | 1.070 | 1.039 | 4.07 |
| 9) | Heptachlor E | 0.995 | 0.963 | 0.931 | 0.927 | 0.950 | 0.984 | 0.993 | 0.962 | 0.963 | 2.73 |
| 10) | gamma-Chlord | 0.982 | 0.972 | 0.928 | 0.927 | 0.958 | 1.006 | 1.037 | 0.976 | 0.973 | 3.79 |
| 11) | alpha-Chlord | 0.971 | 0.959 | 0.905 | 0.902 | 0.931 | 0.968 | 1.081 | 0.942 | 0.957 | 5.89 |
| 12) | Endosulfan I | 0.953 | 0.943 | 0.891 | 0.889 | 0.911 | 0.942 | 1.057 | 0.921 | 0.938 | 5.72 |
| 13) | 4,4'-DDE | 0.934 | 0.930 | 0.879 | 0.888 | 0.927 | 0.979 | 0.952 | 0.943 | 0.929 | 3.49 |
| 14) | Dieldrin | 0.931 | 0.955 | 0.924 | 0.925 | 0.968 | 1.016 | 1.036 | 0.984 | 0.967 | 4.36 |
| 15) | Endrin | 0.750 | 0.714 | 0.690 | 0.692 | 0.721 | 0.743 | 0.792 | 0.729 | 0.729 | 4.59 |
| 16) | 4,4'-DDD | 0.676 | 0.714 | 0.678 | 0.700 | 0.729 | 0.767 | 0.816 | 0.745 | 0.728 | 6.51 |
| 17) | Endosulfan I | 0.870 | 0.922 | 0.864 | 0.869 | 0.884 | 0.904 | 0.960 | 0.891 | 0.895 | 3.64 |
| 18) | 4,4'-DDT | 0.399 | 0.441 | 0.470 | 0.500 | 0.563 | 0.622 | 0.428 | 0.594 | 0.502 | 16.35 |
| 19) | Endrin Aldeh | 0.728 | 0.702 | 0.692 | 0.678 | 0.697 | 0.707 | 0.689 | 0.708 | 0.700 | 2.14 |
| 20) | Endosulfan S | 0.649 | 0.621 | 0.625 | 0.612 | 0.639 | 0.648 | 0.603 | 0.659 | 0.632 | 3.10 |
| 21) | Methoxychlor | 0.255 | 0.246 | 0.255 | 0.283 | 0.299 | 0.308 | 0.370 | 0.306 | 0.290 | 14.02 |
| 22) | Mirex | 0.816 | 0.746 | 0.691 | 0.675 | 0.665 | 0.654 | 0.818 | 0.654 | 0.715 | 9.73 |
| 23) | Endrin Keton | 0.805 | 0.780 | 0.747 | 0.773 | 0.798 | 0.822 | 0.854 | 0.816 | 0.799 | 4.10 |
| 24) | Decachlorobi | 0.837 | 0.788 | 0.757 | 0.723 | 0.721 | 0.714 | 0.726 | 0.710 | 0.747 | 6.00 |

| | | | | | |
|---|---|---|---|---|---|
| 25) | I 1-bromo-2-nitrobenzen | ----------ISTD---------- | | | |
| 26) | Toxaphene{A} | | 0.020 | 0.020 | 0.00 |
| 27) | Toxaphene{B} | | 0.024 | 0.024 | 0.00 |
| 28) | Toxaphene{C} | | 0.035 | 0.035 | 0.00 |
| 29) | Toxaphene{D} | | 0.022 | 0.022 | 0.00 |
| 30) | Toxaphene{E} | | 0.022 | 0.022 | 0.00 |

| | | | | | |
|---|---|---|---|---|---|
| 31) | I 1-bromo-2-nitrobenzen | ----------ISTD---------- | | | |
| 32) | Chlordane {A | | 0.045 | 0.045 | 0.00 |
| 33) | Chlordane {B | | 0.039 | 0.039 | 0.00 |
| 34) | Chlordane {C | | 0.121 | 0.121 | 0.00 |
| 35) | Chlordane {D | | 0.195 | 0.195 | 0.00 |
| 36) | Chlordane {E | | 0.029 | 0.029 | 0.00 |

(#) = Out of Range ### Number of calibration levels exceeded format ###

4PST1911.M Thu Sep 29 09:23:05 2016 RPT1

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1911-ICV1911
**Lab FileID:** 4G72954.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\4G1911\4g72954.D\ECD1A.ch Vial: 13
Signal #2 : C:\msdchem\1\DATA\4G1911\4g72954.D\ECD2B.ch
Acq On : 28 Sep 2016 9:05 pm Operator: rebeccak
Sample : icv1911-25 Inst : GC4G
Misc : op97218,g4g1911,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title : PEST/PCB
Last Update : Thu Sep 29 09:14:27 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 101 | 0.00 | 1.51- 1.57 |
| 2 | SAB | Tetrachloro-m-xylene | 0.861 | 0.774 | 10.1 | 90 | 0.00 | 1.97- 2.03 |
| 3 | A | alpha-BHC | 1.214 | 1.110 | 8.6 | 96 | 0.00 | 2.37- 2.43 |
| 4 | MA | gamma-BHC | 1.153 | 1.026 | 11.0 | 97 | 0.00 | 2.62- 2.68 |
| 5 | MA | Heptachlor | 1.057 | 0.939 | 11.2 | 96 | 0.00 | 3.05- 3.11 |
| 6 | B | beta-BHC | 0.508 | 0.460 | 9.4 | 97 | 0.00 | 2.69- 2.75 |
| 7 | B | delta-BHC | 1.001 | 0.929 | 7.2 | 101 | 0.00 | 2.85- 2.91 |
| 8 | MB | Aldrin | 1.061 | 0.969 | 8.7 | 98 | 0.00 | 3.35- 3.41 |
| 9 | B | Heptachlor Epoxide | 0.962 | 0.909 | 5.5 | 98 | 0.00 | 4.01- 4.07 |
| 10 | B | gamma-Chlordane | 1.083 | 0.928 | 14.3 | 98 | 0.00 | 4.16- 4.22 |
| 11 | B | alpha-Chlordane | 1.004 | 0.904 | 10.0 | 97 | 0.00 | 4.32- 4.38 |
| 12 | A | Endosulfan I | 0.975 | 0.879 | 9.8 | 97 | 0.00 | 4.49- 4.55 |
| 13 | B | 4,4'-DDE | 0.997 | 0.890 | 10.7 | 97 | 0.00 | 4.43- 4.49 |
| 14 | MA | Dieldrin | 1.012 | 0.922 | 8.9 | 97 | 0.00 | 4.79- 4.85 |
| 15 | MA | Endrin | 0.732 | 0.679 | 7.2 | 102 | 0.00 | 5.10- 5.16 |
| 16 | A | 4,4'-DDD | 0.810 | 0.735 | 9.3 | 96 | 0.00 | 5.23- 5.29 |
| 17 | B | Endosulfan II | 0.922 | 0.809 | 12.3 | 95 | 0.00 | 5.41- 5.47 |
| 18 | MA | 4,4'-DDT | 0.733 | 0.629 | 14.2 | 96 | 0.00 | 5.62- 5.68 |
| 19 | B | Endrin Aldehyde | 0.769 | 0.727 | 5.5 | 100 | 0.00 | 6.02- 6.08 |
| 20 | B | Endosulfan Sulfate | 0.722 | 0.644 | 10.8 | 96 | 0.00 | 6.69- 6.75 |
| 21 | A | Methoxychlor | 0.362 | 0.322 | 11.0 | 95 | 0.00 | 6.40- 6.46 |
| 23 | B | Endrin Ketone | 0.919 | 0.842 | 8.4 | 98 | 0.00 | 7.11- 7.17 |
| 24 | SA | Decachlorobiphenyl | 0.945 | 0.840 | 11.1 | 98 | 0.00 | 8.86- 8.92 |

***** Signal #2 *****

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 104 | 0.00 | 1.31- 1.37 |
| 2 | SAB | Tetrachloro-m-xylene | 0.889 | 0.762 | 14.3 | 94 | 0.00 | 1.87- 1.93 |
| 3 | A | alpha-BHC | 1.165 | 1.089 | 6.5 | 100 | 0.00 | 2.34- 2.40 |
| 4 | MA | gamma-BHC | 1.060 | 0.972 | 8.3 | 97 | 0.00 | 2.67- 2.73 |
| 5 | MA | Heptachlor | 1.086 | 0.976 | 10.1 | 99 | 0.00 | 3.10- 3.16 |
| 6 | B | beta-BHC | 0.500 | 0.474 | 5.2 | 103 | 0.00 | 2.75- 2.81 |
| 7 | B | delta-BHC | 0.838 | 0.777 | 7.3 | 98 | 0.00 | 3.05- 3.11 |
| 8 | MB | Aldrin | 1.039 | 0.937 | 9.8 | 97 | 0.00 | 3.46- 3.52 |
| 9 | B | Heptachlor Epoxide | 0.963 | 0.881 | 8.5 | 99 | 0.00 | 4.15- 4.21 |
| 10 | B | gamma-Chlordane | 0.973 | 0.877 | 9.9 | 98 | 0.00 | 4.39- 4.45 |
| 11 | B | alpha-Chlordane | 0.957 | 0.850 | 11.2 | 98 | 0.00 | 4.59- 4.65 |
| 12 | A | Endosulfan I | 0.938 | 0.829 | 11.6 | 97 | 0.00 | 4.66- 4.72 |

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1911-ICV1911
**Lab FileID:** 4G72954.D

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 13 | B | 4,4'-DDE | 0.929 | 0.843 | 9.3 | 99 | 0.00 | 4.86- 4.92 |
| 14 | MA | Dieldrin | 0.967 | 0.887 | 8.3 | 100 | 0.00 | 5.04- 5.10 |
| 15 | MA | Endrin | 0.729 | 0.687 | 5.8 | 103 | 0.00 | 5.48- 5.54 |
| 16 | A | 4,4'-DDD | 0.728 | 0.650 | 10.7 | 97 | 0.00 | 5.72- 5.78 |
| 17 | B | Endosulfan II | 0.895 | 0.817 | 8.7 | 98 | 0.00 | 5.81- 5.87 |
| 18 | MA | 4,4'-DDT | 0.502 | 0.464 | 7.6 | 96 | 0.00 | 6.19- 6.25 |
| 19 | B | Endrin Aldehyde | 0.700 | 0.662 | 5.4 | 102 | 0.00 | 6.34- 6.40 |
| 20 | B | Endosulfan Sulfate | 0.632 | 0.591 | 6.5 | 100 | 0.00 | 6.77- 6.83 |
| 21 | A | Methoxychlor | 0.290 | 0.268 | 7.6 | 99 | 0.00 | 7.39- 7.45 |
| 23 | B | Endrin Ketone | 0.799 | 0.729 | 8.8 | 98 | 0.00 | 7.65- 7.71 |
| 24 | SA | Decachlorobiphenyl | 0.747 | 0.712 | 4.7 | 102 | 0.00 | 9.83- 9.89 |

---

(#) = Out of Range SPCC's out = 0 CCC's out = 0
4g72948.D 4PST1911.M Thu Sep 29 09:21:09 2016 RPT1

8.10.6
8

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1911-ICV1911
**Lab FileID:** 4G72955.D

Evaluate Continuing Calibration Report

```
 Signal #1 : C:\msdchem\1\DATA\4G1911\4g72955.D\ECD1A.ch  Vial: 14
 Signal #2 : C:\msdchem\1\DATA\4G1911\4g72955.D\ECD2B.ch
 Acq On    : 28 Sep 2016   9:20 pm                    Operator: rebeccak
 Sample    : icv1911-25                               Inst    : GC4G
 Misc      : op97218,g4g1911,100,,,10,1               Multiplr: 1.00
 IntFile Signal #1: autoint1.e   IntFile Signal #2: autoint2.e

 Method       : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
 Title        : PEST/PCB
 Last Update  : Thu Sep 29 09:14:27 2016
 Response via : Multiple Level Calibration

 Min. RRF     :   0.000  Min. Rel. Area :  50%  Max. R.T. Dev  0.10min
 Max. RRF Dev :  20%     Max. Rel. Area : 200%
```

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 1 I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 96 | 0.00 | 1.52- 1.58 |
| 22 | Mirex | 0.799 | 0.738 | 7.6 | 96 | 0.00 | 6.48- 6.54 |
| ***** | Signal #2 ***** | | | | | | |
| 1 I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 102 | 0.00 | 1.31- 1.37 |
| 22 | Mirex | 0.715 | 0.642 | 10.2 | 97 | 0.00 | 7.55- 7.61 |

```
(#) = Out of Range              SPCC's out = 0  CCC's out = 0
 4g72948.D  4PST1911.M       Thu Sep 29 09:21:11 2016   RPT1
```

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1911-ICV1911
**Lab FileID:** 4G72956.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\4G1911\4g72956.D\ECD1A.ch Vial: 15
Signal #2 : C:\msdchem\1\DATA\4G1911\4g72956.D\ECD2B.ch
Acq On : 28 Sep 2016 9:34 pm Operator: rebeccak
Sample : icv1911-500 Inst : GC4G
Misc : op97218,g4g1911,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title : PEST/PCB
Last Update : Thu Sep 29 09:14:27 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 1.52- 1.58 |
| 2 | SAB | Tetrachloro-m-xylene | 0.861 | 0.785 | 8.8 | 88 | 0.00 | 1.97- 2.03 |
| 24 | SA | Decachlorobiphenyl | 0.945 | 0.816 | 13.7 | 93 | 0.00 | 8.86- 8.92 |
| 31 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 1.45- 1.65 |
| 32 | | Chlordane {A} | 0.048 | 0.047 | 2.1 | 95 | 0.00 | 2.98- 3.18 |
| 33 | | Chlordane {B} | 0.044 | 0.038 | 13.6 | 86 | 0.00 | 3.42- 3.62 |
| 34 | | Chlordane {C} | 0.131 | 0.124 | 5.3 | 93 | 0.00 | 4.09- 4.29 |
| 35 | | Chlordane {D} | 0.207 | 0.199 | 3.9 | 94 | 0.00 | 4.24- 4.44 |
| 36 | | Chlordane {E} | 0.035 | 0.032 | 8.6 | 90 | 0.00 | 5.24- 5.44 |

***** Signal #2 *****

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 99 | 0.00 | 1.31- 1.37 |
| 2 | SAB | Tetrachloro-m-xylene | 0.889 | 0.793 | 10.8 | 90 | 0.00 | 1.87- 1.93 |
| 24 | SA | Decachlorobiphenyl | 0.747 | 0.708 | 5.2 | 97 | 0.00 | 9.83- 9.89 |
| 31 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 96 | 0.00 | 1.24- 1.44 |
| 32 | | Chlordane {A} | 0.045 | 0.048 | -6.7 | 102 | 0.00 | 3.03- 3.23 |
| 33 | | Chlordane {B} | 0.039 | 0.036 | 7.7 | 90 | 0.00 | 3.56- 3.76 |
| 34 | | Chlordane {C} | 0.121 | 0.120 | 0.8 | 95 | 0.00 | 4.32- 4.52 |
| 35 | | Chlordane {D} | 0.195 | 0.190 | 2.6 | 93 | 0.00 | 4.51- 4.71 |
| 36 | | Chlordane {E} | 0.029 | 0.026 | 10.3 | 86 | 0.00 | 5.80- 6.00 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
4g72949.D 4PST1911.M Thu Sep 29 09:21:25 2016 RPT1

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1911-ICV1911
**Lab FileID:** 4G72957.D

Evaluate Continuing Calibration Report

```
Signal #1 : C:\msdchem\1\DATA\4G1911\4g72957.D\ECD1A.ch  Vial: 16
Signal #2 : C:\msdchem\1\DATA\4G1911\4g72957.D\ECD2B.ch
Acq On    : 28 Sep 2016   9:49 pm                    Operator: rebeccak
Sample    : icv1911-500                              Inst    : GC4G
Misc      : op97218,g4g1911,100,,,10,1               Multiplr: 1.00
IntFile Signal #1: autoint1.e   IntFile Signal #2: autoint2.e

Method       : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title        : PEST/PCB
Last Update  : Thu Sep 29 09:14:27 2016
Response via : Multiple Level Calibration

Min. RRF     :   0.000  Min. Rel. Area :  50%  Max. R.T. Dev  0.10min
Max. RRF Dev :  20%     Max. Rel. Area : 200%
```

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 96 | 0.00 | 1.51- 1.57 |
| 2 | SAB | Tetrachloro-m-xylene | 0.861 | 0.788 | 8.5 | 86 | 0.00 | 1.97- 2.03 |
| 24 | SA | Decachlorobiphenyl | 0.945 | 0.886 | 6.2 | 99 | 0.00 | 8.86- 8.92 |
| 25 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 1.44- 1.64 |
| 26 | L8 | Toxaphene{A} | 0.014 | 0.015 | -7.1 | 108 | 0.00 | 4.73- 4.93 |
| 27 | L8 | Toxaphene{B} | 0.030 | 0.031 | -3.3 | 103 | 0.00 | 5.33- 5.53 |
| 28 | L8 | Toxaphene{C} | 0.029 | 0.031 | -6.9 | 104 | 0.00 | 5.49- 5.69 |
| 29 | L8 | Toxaphene{D} | 0.028 | 0.028 | 0.0 | 99 | 0.00 | 5.82- 6.02 |
| 30 | L8 | Toxaphene{E} | 0.026 | 0.027 | -3.8 | 102 | 0.00 | 6.44- 6.64 |

***** Signal #2 *****

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 102 | 0.00 | 1.31- 1.37 |
| 2 | SAB | Tetrachloro-m-xylene | 0.889 | 0.778 | 12.5 | 91 | 0.00 | 1.87- 1.93 |
| 24 | SA | Decachlorobiphenyl | 0.747 | 0.701 | 6.2 | 99 | 0.00 | 9.83- 9.89 |
| 25 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 101 | 0.00 | 1.24- 1.44 |
| 26 | L8 | Toxaphene{A} | 0.020 | 0.020 | 0.0 | 104 | 0.00 | 4.93- 5.13 |
| 27 | L8 | Toxaphene{B} | 0.024 | 0.024 | 0.0 | 103 | 0.00 | 5.71- 5.91 |
| 28 | L8 | Toxaphene{C} | 0.035 | 0.036 | -2.9 | 103 | 0.00 | 5.86- 6.06 |
| 29 | L8 | Toxaphene{D} | 0.022 | 0.023 | -4.5 | 103 | 0.00 | 6.27- 6.47 |
| 30 | L8 | Toxaphene{E} | 0.022 | 0.022 | 0.0 | 103 | 0.00 | 7.09- 7.29 |

```
(#) = Out of Range              SPCC's out = 0  CCC's out = 0
 4g72949.D  4PST1911.M      Thu Sep 29 09:21:27 2016   RPT1
```

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1919-CC1911
**Lab FileID:** 4G73351.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\4G1919\4g73351.D\ECD1A.ch Vial: 2
Signal #2 : C:\msdchem\1\DATA\4G1919\4g73351.D\ECD2B.ch
Acq On : 6 Oct 2016 5:13 pm Operator: kristend
Sample : cc1911-25 Inst : GC4G
Misc : op97520,g4g1919,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title : PEST/PCB
Last Update : Thu Oct 06 11:37:41 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 95 | 0.00 | 1.51- 1.57 |
| 2 | SAB | Tetrachloro-m-xylene | 0.861 | 0.841 | 2.3 | 92 | 0.00 | 1.96- 2.02 |
| 3 | A | alpha-BHC | 1.214 | 1.137 | 6.3 | 93 | 0.00 | 2.36- 2.42 |
| 4 | MA | gamma-BHC | 1.153 | 1.021 | 11.4 | 91 | 0.00 | 2.61- 2.67 |
| 5 | MA | Heptachlor | 1.057 | 1.009 | 4.5 | 97 | 0.00 | 3.04- 3.10 |
| 6 | B | beta-BHC | 0.508 | 0.446 | 12.2 | 89 | 0.00 | 2.68- 2.74 |
| 7 | B | delta-BHC | 1.001 | 0.887 | 11.4 | 91 | 0.00 | 2.84- 2.90 |
| 8 | MB | Aldrin | 1.061 | 0.937 | 11.7 | 89 | 0.00 | 3.34- 3.40 |
| 9 | B | Heptachlor Epoxide | 0.962 | 0.795 | 17.4 | 81 | 0.00 | 4.00- 4.06 |
| 10 | B | gamma-Chlordane | 1.083 | 0.903 | 16.6 | 89 | 0.00 | 4.15- 4.21 |
| 11 | B | alpha-Chlordane | 1.004 | 0.849 | 15.4 | 86 | 0.00 | 4.31- 4.37 |
| 12 | A | Endosulfan I | 0.975 | 0.844 | 13.4 | 87 | 0.00 | 4.48- 4.54 |
| 13 | B | 4,4'-DDE | 0.997 | 0.868 | 12.9 | 89 | 0.00 | 4.42- 4.48 |
| 14 | MA | Dieldrin | 1.012 | 0.886 | 12.5 | 88 | 0.00 | 4.78- 4.84 |
| 15 | MA | Endrin | 0.732 | 0.846 | -15.6 | 120 | 0.00 | 5.09- 5.15 |
| 16 | A | 4,4'-DDD | 0.810 | 0.711 | 12.2 | 87 | 0.00 | 5.22- 5.28 |
| 17 | B | Endosulfan II | 0.922 | 0.807 | 12.5 | 90 | 0.00 | 5.40- 5.46 |
| 18 | MA | 4,4'-DDT | 0.733 | 0.742 | -1.2 | 107 | 0.00 | 5.61- 5.67 |
| 19 | B | Endrin Aldehyde | 0.769 | 0.642 | 16.5 | 83 | 0.00 | 6.01- 6.07 |
| 20 | B | Endosulfan Sulfate | 0.722 | 0.691 | 4.3 | 97 | 0.00 | 6.68- 6.74 |
| 21 | A | Methoxychlor | 0.362 | 0.421 | -16.3 | 117 | 0.00 | 6.39- 6.45 |
| 22 | | Mirex | 0.799 | 0.690 | 13.6 | 88 | 0.00 | 6.47- 6.53 |
| 23 | B | Endrin Ketone | 0.919 | 0.833 | 9.4 | 92 | 0.00 | 7.09- 7.15 |
| 24 | SA | Decachlorobiphenyl | 0.945 | 0.813 | 14.0 | 89 | 0.00 | 8.85- 8.91 |

***** Signal #2 *****

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 98 | 0.00 | 1.30- 1.36 |
| 2 | SAB | Tetrachloro-m-xylene | 0.889 | 0.833 | 6.3 | 96 | 0.00 | 1.85- 1.91 |
| 3 | A | alpha-BHC | 1.165 | 1.141 | 2.1 | 98 | 0.00 | 2.33- 2.39 |
| 4 | MA | gamma-BHC | 1.060 | 0.988 | 6.8 | 93 | 0.00 | 2.65- 2.71 |
| 5 | MA | Heptachlor | 1.086 | 0.869 | 20.0 | 83 | 0.00 | 3.09- 3.15 |
| 6 | B | beta-BHC | 0.500 | 0.451 | 9.8 | 92 | 0.00 | 2.73- 2.79 |
| 7 | B | delta-BHC | 0.838 | 0.857 | -2.3 | 102 | 0.00 | 3.03- 3.09 |
| 8 | MB | Aldrin | 1.039 | 0.945 | 9.0 | 92 | 0.00 | 3.44- 3.50 |
| 9 | B | Heptachlor Epoxide | 0.963 | 0.849 | 11.8 | 90 | 0.00 | 4.12- 4.18 |
| 10 | B | gamma-Chlordane | 0.973 | 0.847 | 12.9 | 89 | 0.00 | 4.37- 4.43 |
| 11 | B | alpha-Chlordane | 0.957 | 0.834 | 12.9 | 90 | 0.00 | 4.56- 4.62 |
| 12 | A | Endosulfan I | 0.938 | 0.814 | 13.2 | 90 | 0.00 | 4.63- 4.69 |
| 13 | B | 4,4'-DDE | 0.929 | 0.851 | 8.4 | 94 | 0.00 | 4.83- 4.89 |

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G4G1919-CC1911
**Lab FileID:** 4G73351.D

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 14 | MA | Dieldrin | 0.967 | 0.883 | 8.7 | 93 | 0.00 | 5.01- 5.07 |
| 15 | MA | Endrin | 0.729 | 0.817 | -12.1 | 115 | 0.00 | 5.45- 5.51 |
| 16 | A | 4,4'-DDD | 0.728 | 0.696 | 4.4 | 97 | 0.00 | 5.68- 5.74 |
| 17 | B | Endosulfan II | 0.895 | 0.811 | 9.4 | 91 | 0.00 | 5.78- 5.84 |
| 18 | MA | 4,4'-DDT | 0.502 | 0.477 | 5.0 | 93 | 0.00 | 6.16- 6.22 |
| 19 | B | Endrin Aldehyde | 0.700 | 0.617 | 11.9 | 89 | 0.00 | 6.31- 6.37 |
| 20 | B | Endosulfan Sulfate | 0.632 | 0.675 | -6.8 | 108 | 0.00 | 6.74- 6.80 |
| 21 | A | Methoxychlor | 0.290 | 0.291 | -0.3 | 101 | 0.00 | 7.35- 7.41 |
| 22 | | Mirex | 0.715 | 0.656 | 8.3 | 95 | 0.00 | 7.51- 7.57 |
| 23 | B | Endrin Ketone | 0.799 | 0.796 | 0.4 | 101 | 0.00 | 7.62- 7.68 |
| 24 | SA | Decachlorobiphenyl | 0.747 | 0.779 | -4.3 | 105 | 0.00 | 9.80- 9.86 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
4g72948.D 4PST1911.M Fri Oct 07 08:32:46 2016 RPT1

8.10.10
8

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** G4G1920-CC1911
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** 4G73382.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\4G1920\4g73382.D\ECD1A.ch Vial: 4
Signal #2 : C:\msdchem\1\DATA\4G1920\4g73382.D\ECD2B.ch
Acq On : 7 Oct 2016 9:09 am Operator: rebeccak
Sample : cc1911-50 Inst : GC4G
Misc : op97536,g4g1920,15.3,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title : PEST/PCB
Last Update : Thu Oct 06 11:37:41 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 106 | 0.00 | 1.50- 1.56 |
| 2 | SAB | Tetrachloro-m-xylene | 0.861 | 0.860 | 0.1 | 104 | 0.00 | 1.96- 2.02 |
| 3 | A | alpha-BHC | 1.214 | 1.215 | -0.1 | 106 | 0.00 | 2.36- 2.42 |
| 4 | MA | gamma-BHC | 1.153 | 1.079 | 6.4 | 102 | 0.00 | 2.61- 2.67 |
| 5 | MA | Heptachlor | 1.057 | 1.053 | 0.4 | 109 | 0.00 | 3.04- 3.10 |
| 6 | B | beta-BHC | 0.508 | 0.456 | 10.2 | 100 | 0.00 | 2.68- 2.74 |
| 7 | B | delta-BHC | 1.001 | 0.970 | 3.1 | 102 | 0.00 | 2.84- 2.90 |
| 8 | MB | Aldrin | 1.061 | 0.993 | 6.4 | 101 | 0.00 | 3.34- 3.40 |
| 9 | B | Heptachlor Epoxide | 0.962 | 0.851 | 11.5 | 95 | 0.00 | 4.00- 4.06 |
| 10 | B | gamma-Chlordane | 1.083 | 0.891 | 17.7 | 96 | 0.00 | 4.15- 4.21 |
| 11 | B | alpha-Chlordane | 1.004 | 0.867 | 13.6 | 96 | 0.00 | 4.31- 4.37 |
| 12 | A | Endosulfan I | 0.975 | 0.862 | 11.6 | 98 | 0.00 | 4.48- 4.54 |
| 13 | B | 4,4'-DDE | 0.997 | 0.895 | 10.2 | 99 | 0.00 | 4.42- 4.48 |
| 14 | MA | Dieldrin | 1.012 | 0.928 | 8.3 | 100 | 0.00 | 4.78- 4.84 |
| 15 | MA | Endrin | 0.732 | 0.868 | -18.6 | 134 | 0.00 | 5.08- 5.14 |
| 16 | A | 4,4'-DDD | 0.810 | 0.751 | 7.3 | 99 | 0.00 | 5.21- 5.27 |
| 17 | B | Endosulfan II | 0.922 | 0.822 | 10.8 | 100 | 0.00 | 5.40- 5.46 |
| 18 | MA | 4,4'-DDT | 0.733 | 0.735 | -0.3 | 111 | 0.00 | 5.61- 5.67 |
| 19 | B | Endrin Aldehyde | 0.769 | 0.658 | 14.4 | 94 | 0.00 | 6.01- 6.07 |
| 20 | B | Endosulfan Sulfate | 0.722 | 0.715 | 1.0 | 109 | 0.00 | 6.68- 6.74 |
| 21 | A | Methoxychlor | 0.362 | 0.402 | -11.0 | 120 | 0.00 | 6.38- 6.44 |
| 22 | | Mirex | 0.799 | 0.671 | 16.0 | 97 | 0.00 | 6.47- 6.53 |
| 23 | B | Endrin Ketone | 0.919 | 0.852 | 7.3 | 102 | 0.00 | 7.09- 7.15 |
| 24 | SA | Decachlorobiphenyl | 0.945 | 0.752 | 20.4# | 93 | 0.00 | 8.85- 8.91 |
| 25 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 108 | 0.00 | 1.43- 1.63 |
| 26 | L8 | Toxaphene{A} | | ----------NA---------- | | | | |
| 27 | L8 | Toxaphene{B} | | ----------NA---------- | | | | |
| 28 | L8 | Toxaphene{C} | | ----------NA---------- | | | | |
| 29 | L8 | Toxaphene{D} | | ----------NA---------- | | | | |
| 30 | L8 | Toxaphene{E} | | ----------NA---------- | | | | |
| 31 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 106 | 0.00 | 1.43- 1.63 |
| 32 | | Chlordane {A} | | ----------NA---------- | | | | |
| 33 | | Chlordane {B} | | ----------NA---------- | | | | |
| 34 | | Chlordane {C} | | ----------NA---------- | | | | |
| 35 | | Chlordane {D} | | ----------NA---------- | | | | |
| 36 | | Chlordane {E} | | ----------NA---------- | | | | |

***** Signal #2 *****

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** G4G1920-CC1911
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** 4G73382.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 109 | 0.00 | 1.29- 1.35 |
| 2 | SAB | Tetrachloro-m-xylene | 0.889 | 0.857 | 3.6 | 107 | 0.00 | 1.85- 1.91 |
| 3 | A | alpha-BHC | 1.165 | 1.232 | -5.8 | 108 | 0.00 | 2.33- 2.39 |
| 4 | MA | gamma-BHC | 1.060 | 1.055 | 0.5 | 104 | 0.00 | 2.65- 2.71 |
| 5 | MA | Heptachlor | 1.086 | 1.027 | 5.4 | 106 | 0.00 | 3.09- 3.15 |
| 6 | B | beta-BHC | 0.500 | 0.455 | 9.0 | 100 | 0.00 | 2.72- 2.78 |
| 7 | B | delta-BHC | 0.838 | 0.965 | -15.2 | 115 | 0.00 | 3.03- 3.09 |
| 8 | MB | Aldrin | 1.039 | 0.992 | 4.5 | 103 | 0.00 | 3.44- 3.50 |
| 9 | B | Heptachlor Epoxide | 0.963 | 0.871 | 9.6 | 100 | 0.00 | 4.12- 4.18 |
| 10 | B | gamma-Chlordane | 0.973 | 0.889 | 8.6 | 101 | 0.00 | 4.37- 4.43 |
| 11 | B | alpha-Chlordane | 0.957 | 0.866 | 9.5 | 101 | 0.00 | 4.56- 4.62 |
| 12 | A | Endosulfan I | 0.938 | 0.842 | 10.2 | 101 | 0.00 | 4.63- 4.69 |
| 13 | B | 4,4'-DDE | 0.929 | 0.885 | 4.7 | 104 | 0.00 | 4.82- 4.88 |
| 14 | MA | Dieldrin | 0.967 | 0.922 | 4.7 | 104 | 0.00 | 5.01- 5.07 |
| 15 | MA | Endrin | 0.729 | 0.852 | -16.9 | 128 | 0.00 | 5.45- 5.51 |
| 16 | A | 4,4'-DDD | 0.728 | 0.739 | -1.5 | 110 | -0.01 | 5.68- 5.74 |
| 17 | B | Endosulfan II | 0.895 | 0.831 | 7.2 | 102 | 0.00 | 5.78- 5.84 |
| 18 | MA | 4,4'-DDT | 0.502 | 0.588 | -17.1 | 114 | 0.00 | 6.15- 6.21 |
| 19 | B | Endrin Aldehyde | 0.700 | 0.637 | 9.0 | 99 | 0.00 | 6.30- 6.37 |
| 20 | B | Endosulfan Sulfate | 0.632 | 0.687 | -8.7 | 117 | 0.00 | 6.74- 6.80 |
| 21 | A | Methoxychlor | 0.290 | 0.336 | -15.9 | 122 | 0.00 | 7.35- 7.41 |
| 22 | | Mirex | 0.715 | 0.630 | 11.9 | 103 | 0.00 | 7.51- 7.57 |
| 23 | B | Endrin Ketone | 0.799 | 0.826 | -3.4 | 113 | 0.00 | 7.61- 7.67 |
| 24 | SA | Decachlorobiphenyl | 0.747 | 0.725 | 2.9 | 109 | 0.00 | 9.80- 9.86 |
| 25 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 108 | 0.00 | 1.22- 1.42 |
| 26 | L8 | Toxaphene{A} | | ----------NA---------- | | | | |
| 27 | L8 | Toxaphene{B} | | ----------NA---------- | | | | |
| 28 | L8 | Toxaphene{C} | | ----------NA---------- | | | | |
| 29 | L8 | Toxaphene{D} | | ----------NA---------- | | | | |
| 30 | L8 | Toxaphene{E} | | ----------NA---------- | | | | |
| 31 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 105 | 0.00 | 1.22- 1.42 |
| 32 | | Chlordane {A} | | ----------NA---------- | | | | |
| 33 | | Chlordane {B} | | ----------NA---------- | | | | |
| 34 | | Chlordane {C} | | ----------NA---------- | | | | |
| 35 | | Chlordane {D} | | ----------NA---------- | | | | |
| 36 | | Chlordane {E} | | ----------NA---------- | | | | |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
4g72949.D 4PST1911.M Fri Oct 07 15:45:45 2016 RPT1

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** G4G1920-CC1911
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** 4G73403.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\4G1920\4g73403.D\ECD1A.ch Vial: 2
Signal #2 : C:\msdchem\1\DATA\4G1920\4g73403.D\ECD2B.ch
Acq On : 7 Oct 2016 5:10 pm Operator: dharas
Sample : cc1911-25 Inst : GC4G
Misc : op97573,g4g1920,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\4PST1911.M (ChemStation Integrator)
Title : PEST/PCB
Last Update : Thu Oct 06 11:37:41 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 107 | 0.00 | 1.50- 1.56 |
| 2 | SAB | Tetrachloro-m-xylene | 0.861 | 0.860 | 0.1 | 106 | 0.00 | 1.96- 2.02 |
| 3 | A | alpha-BHC | 1.214 | 1.147 | 5.5 | 106 | 0.00 | 2.36- 2.42 |
| 4 | MA | gamma-BHC | 1.153 | 1.034 | 10.3 | 104 | 0.00 | 2.61- 2.67 |
| 5 | MA | Heptachlor | 1.057 | 1.019 | 3.6 | 111 | 0.00 | 3.04- 3.10 |
| 6 | B | beta-BHC | 0.508 | 0.460 | 9.4 | 103 | 0.00 | 2.68- 2.74 |
| 7 | B | delta-BHC | 1.001 | 0.894 | 10.7 | 104 | 0.00 | 2.84- 2.90 |
| 8 | MB | Aldrin | 1.061 | 0.956 | 9.9 | 103 | 0.00 | 3.34- 3.40 |
| 9 | B | Heptachlor Epoxide | 0.962 | 0.840 | 12.7 | 97 | 0.00 | 4.00- 4.06 |
| 10 | B | gamma-Chlordane | 1.083 | 0.848 | 21.7# | 95 | 0.00 | 4.15- 4.21 |
| 11 | B | alpha-Chlordane | 1.004 | 0.848 | 15.5 | 97 | 0.00 | 4.31- 4.37 |
| 12 | A | Endosulfan I | 0.975 | 0.850 | 12.8 | 100 | 0.00 | 4.48- 4.54 |
| 13 | B | 4,4'-DDE | 0.997 | 0.865 | 13.2 | 100 | 0.00 | 4.42- 4.48 |
| 14 | MA | Dieldrin | 1.012 | 0.897 | 11.4 | 101 | 0.00 | 4.78- 4.84 |
| 15 | MA | Endrin | 0.732 | 0.841 | -14.9 | 135 | 0.00 | 5.08- 5.14 |
| 16 | A | 4,4'-DDD | 0.810 | 0.726 | 10.4 | 101 | 0.00 | 5.22- 5.28 |
| 17 | B | Endosulfan II | 0.922 | 0.805 | 12.7 | 101 | 0.00 | 5.40- 5.46 |
| 18 | MA | 4,4'-DDT | 0.733 | 0.693 | 5.5 | 112 | 0.00 | 5.61- 5.67 |
| 19 | B | Endrin Aldehyde | 0.769 | 0.648 | 15.7 | 95 | 0.00 | 6.01- 6.07 |
| 20 | B | Endosulfan Sulfate | 0.722 | 0.700 | 3.0 | 111 | 0.00 | 6.68- 6.74 |
| 21 | A | Methoxychlor | 0.362 | 0.399 | -10.2 | 126 | 0.00 | 6.39- 6.45 |
| 22 | | Mirex | 0.799 | 0.694 | 13.1 | 100 | 0.00 | 6.47- 6.53 |
| 23 | B | Endrin Ketone | 0.919 | 0.795 | 13.5 | 99 | 0.00 | 7.09- 7.15 |
| 24 | SA | Decachlorobiphenyl | 0.945 | 0.810 | 14.3 | 101 | 0.00 | 8.85- 8.91 |
| 25 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 0# | 0.00 | 1.43- 1.63 |
| 26 | L8 | Toxaphene{A} | | ----------NA---------- | | | | |
| 27 | L8 | Toxaphene{B} | | ----------NA---------- | | | | |
| 28 | L8 | Toxaphene{C} | | ----------NA---------- | | | | |
| 29 | L8 | Toxaphene{D} | | ----------NA---------- | | | | |
| 30 | L8 | Toxaphene{E} | | ----------NA---------- | | | | |
| 31 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 0# | 0.00 | 1.43- 1.63 |
| 32 | | Chlordane {A} | | ----------NA---------- | | | | |
| 33 | | Chlordane {B} | | ----------NA---------- | | | | |
| 34 | | Chlordane {C} | | ----------NA---------- | | | | |
| 35 | | Chlordane {D} | | ----------NA---------- | | | | |
| 36 | | Chlordane {E} | | ----------NA---------- | | | | |

***** Signal #2 *****

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** G4G1920-CC1911
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** 4G73403.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 108 | 0.00 | 1.29- 1.35 |
| 2 | SAB | Tetrachloro-m-xylene | 0.889 | 0.849 | 4.5 | 108 | 0.00 | 1.85- 1.91 |
| 3 | A | alpha-BHC | 1.165 | 1.170 | -0.4 | 111 | 0.00 | 2.33- 2.39 |
| 4 | MA | gamma-BHC | 1.060 | 1.014 | 4.3 | 105 | 0.00 | 2.65- 2.71 |
| 5 | MA | Heptachlor | 1.086 | 1.027 | 5.4 | 108 | 0.00 | 3.09- 3.15 |
| 6 | B | beta-BHC | 0.500 | 0.464 | 7.2 | 104 | 0.00 | 2.73- 2.79 |
| 7 | B | delta-BHC | 0.838 | 0.881 | -5.1 | 115 | 0.00 | 3.03- 3.09 |
| 8 | MB | Aldrin | 1.039 | 0.967 | 6.9 | 104 | 0.00 | 3.44- 3.50 |
| 9 | B | Heptachlor Epoxide | 0.963 | 0.857 | 11.0 | 99 | 0.00 | 4.12- 4.18 |
| 10 | B | gamma-Chlordane | 0.973 | 0.875 | 10.1 | 101 | 0.00 | 4.37- 4.43 |
| 11 | B | alpha-Chlordane | 0.957 | 0.855 | 10.7 | 102 | 0.00 | 4.56- 4.62 |
| 12 | A | Endosulfan I | 0.938 | 0.836 | 10.9 | 101 | 0.00 | 4.63- 4.69 |
| 13 | B | 4,4'-DDE | 0.929 | 0.863 | 7.1 | 105 | 0.00 | 4.82- 4.88 |
| 14 | MA | Dieldrin | 0.967 | 0.897 | 7.2 | 104 | 0.00 | 5.01- 5.07 |
| 15 | MA | Endrin | 0.729 | 0.830 | -13.9 | 129 | 0.00 | 5.45- 5.51 |
| 16 | A | 4,4'-DDD | 0.728 | 0.716 | 1.6 | 110 | 0.00 | 5.68- 5.74 |
| 17 | B | Endosulfan II | 0.895 | 0.829 | 7.4 | 103 | 0.00 | 5.78- 5.84 |
| 18 | MA | 4,4'-DDT | 0.502 | 0.561 | -11.8 | 121 | 0.00 | 6.15- 6.21 |
| 19 | B | Endrin Aldehyde | 0.700 | 0.634 | 9.4 | 101 | 0.00 | 6.31- 6.37 |
| 20 | B | Endosulfan Sulfate | 0.632 | 0.678 | -7.3 | 119 | 0.00 | 6.74- 6.80 |
| 21 | A | Methoxychlor | 0.290 | 0.352 | -21.4# | 134 | 0.00 | 7.35- 7.41 |
| 22 | | Mirex | 0.715 | 0.666 | 6.9 | 106 | 0.00 | 7.51- 7.57 |
| 23 | B | Endrin Ketone | 0.799 | 0.772 | 3.4 | 107 | 0.00 | 7.61- 7.67 |
| 24 | SA | Decachlorobiphenyl | 0.747 | 0.777 | -4.0 | 116 | 0.00 | 9.80- 9.86 |
| 25 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 0# | 0.00 | 1.22- 1.42 |
| 26 | L8 | Toxaphene{A} | | ----------NA---------- | | | | |
| 27 | L8 | Toxaphene{B} | | ----------NA---------- | | | | |
| 28 | L8 | Toxaphene{C} | | ----------NA---------- | | | | |
| 29 | L8 | Toxaphene{D} | | ----------NA---------- | | | | |
| 30 | L8 | Toxaphene{E} | | ----------NA---------- | | | | |
| 31 | I | 1-bromo-2-nitrobenzene | 1.000 | 1.000 | 0.0 | 0# | 0.00 | 1.22- 1.42 |
| 32 | | Chlordane {A} | | ----------NA---------- | | | | |
| 33 | | Chlordane {B} | | ----------NA---------- | | | | |
| 34 | | Chlordane {C} | | ----------NA---------- | | | | |
| 35 | | Chlordane {D} | | ----------NA---------- | | | | |
| 36 | | Chlordane {E} | | ----------NA---------- | | | | |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
4g72948.D 4PST1911.M Mon Oct 10 11:38:10 2016 RPT1

8.10.12

8

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G5Y1190-ICC1190
**Lab FileID:** 5Y35988.D

Response Factor Report GC5Y5Z

Method : C:\msdchem\1\METHODS\EPH5Y1190.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Thu Sep 01 09:01:07 2016
Response via : Initial Calibration

Calibration Files
5 =5y35985.D 10 =5y35986.D 50 =5y35988.D 100 =5y35989.D
2 =5y35984.D 20 =5y35987.D =

| Compound | 5 | 10 | 50 | 100 | 2 | 20 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|
| 1)T C9 | 7.953 | 8.186 | 8.036 | 8.026 | 7.967 | 8.165 | 8.055 E5 | 1.22 |
| 2)T C10 | 8.019 | 8.274 | 8.115 | 8.103 | 8.073 | 8.251 | 8.139 E5 | 1.25 |
| 3)T C12 | 8.124 | 8.416 | 8.245 | 8.257 | 8.202 | 8.395 | 8.273 E5 | 1.36 |
| 4)T C14 | 8.280 | 8.608 | 8.431 | 8.404 | 8.385 | 8.561 | 8.445 E5 | 1.43 |
| 5)T C16 | 8.537 | 8.882 | 8.625 | 8.528 | 8.730 | 8.794 | 8.683 E5 | 1.65 |
| 6)T C18 | 8.814 | 9.173 | 8.838 | 8.519 | 9.055 | 9.033 | 8.906 E5 | 2.62 |
| 7)T C20 | 8.969 | 9.318 | 8.916 | 8.730 | 9.235 | 9.151 | 9.053 E5 | 2.44 |
| 8)T C21 | 9.075 | 9.451 | 9.020 | 8.805 | 9.335 | 9.286 | 9.162 E5 | 2.60 |
| 9)T C22 | 9.188 | 9.484 | 8.998 | 8.765 | 9.702 | 9.299 | 9.239 E5 | 3.63 |
| 10)T C24 | 9.137 | 9.464 | 8.984 | 8.716 | 9.537 | 9.288 | 9.188 E5 | 3.35 |
| 11)T C26 | 9.219 | 9.504 | 8.977 | 8.665 | 9.686 | 9.304 | 9.226 E5 | 3.97 |
| 12)T C28 | 9.008 | 9.328 | 8.835 | 8.496 | 9.336 | 9.155 | 9.026 E5 | 3.58 |
| 13)H EPH (C9-C28) | 8.694 | 9.007 | 8.668 | 8.501 | 8.937 | 8.890 | 8.783 E5 | 2.20 |
| 14)T C30 | 9.133 | 9.407 | 8.859 | 8.507 | 9.552 | 9.242 | 9.117 E5 | 4.18 |
| 15)T C32 | 8.945 | 9.308 | 8.756 | 8.403 | 9.301 | 9.101 | 8.969 E5 | 3.89 |
| 16)T C34 | 8.626 | 8.958 | 8.392 | 8.055 | 9.034 | 8.746 | 8.635 E5 | 4.24 |
| 17)T C36 | 8.541 | 8.936 | 8.311 | 7.984 | 8.954 | 8.671 | 8.566 E5 | 4.37 |
| 18)T C38 | 8.240 | 8.681 | 7.967 | 7.677 | 8.667 | 8.308 | 8.257 E5 | 4.76 |
| 19)T C40 | 7.655 | 8.054 | 7.576 | 7.334 | 7.911 | 7.878 | 7.735 E5 | 3.40 |
| 20)H EPH (>C28-C40) | 8.523 | 8.891 | 8.310 | 7.993 | 8.903 | 8.658 | 8.546 E5 | 4.12 |
| 21)H TOTAL PHC | 8.637 | 8.969 | 8.549 | 8.332 | 8.926 | 8.813 | 8.704 E5 | 2.80 |
| 22)S o-Terphenyl (S) | 9.505 | 9.885 | 9.569 | 9.437 | 9.761 | 9.763 | 9.653 E5 | 1.81 |
| 23)S 1-chlorooctadecan | 7.822 | 8.146 | 7.797 | 7.620 | 8.043 | 8.012 | 7.907 E5 | 2.46 |
| 24)S 2-Fluorobiphenyl | | | | | | | 0.000# | -1.00 |
| 25)S 2-Bromonaphthalen | | | | | | | 0.000# | -1.00 |

(#) = Out of Range

EPH5Y1190.M Thu Sep 01 09:06:12 2016

8.10.13
8

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G5Y1190-ICV1190
**Lab FileID:** 5Y35990.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Y1190\5y35990.D Vial: 17
Acq On : 1 Sep 2016 2:16 am Operator: sarahp1
Sample : icv1190-50 Inst : GC5Y5Z
Misc : op96611,g5y1190,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\msdchem\1\METHODS\EPH5Y1190.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Thu Sep 01 09:01:07 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 805.526 | 744.966 E3 | 7.5 | 93 | 0.00 | 3.40- 3.46 |
| 2 | T | C10 | 813.928 | 748.854 E3 | 8.0 | 92 | 0.00 | 4.37- 4.43 |
| 3 | T | C12 | 827.299 | 745.180 E3 | 9.9 | 90 | 0.00 | 6.35- 6.41 |
| 4 | T | C14 | 844.484 | 786.633 E3 | 6.9 | 93 | 0.00 | 8.16- 8.22 |
| 5 | T | C16 | 868.268 | 798.085 E3 | 8.1 | 93 | 0.00 | 9.79- 9.85 |
| 6 | T | C18 | 890.552 | 802.201 E3 | 9.9 | 91 | 0.00 | 11.27-11.33 |
| 7 | T | C20 | 905.330 | 813.193 E3 | 10.2 | 91 | 0.00 | 12.67-12.73 |
| 8 | T | C21 | 916.198 | 813.063 E3 | 11.3 | 90 | 0.00 | 13.36-13.42 |
| 9 | T | C22 | 923.910 | 818.830 E3 | 11.4 | 91 | 0.00 | 14.05-14.11 |
| 10 | T | C24 | 918.775 | 813.764 E3 | 11.4 | 91 | 0.00 | 15.37-15.43 |
| 11 | T | C26 | 922.586 | 810.254 E3 | 12.2 | 90 | 0.00 | 16.63-16.69 |
| 12 | T | C28 | 902.633 | 801.729 E3 | 11.2 | 91 | 0.00 | 17.81-17.87 |
| 13 | H | EPH (C9-C28) | 878.291 | 791.396 E3 | 9.9 | 91 | 0.00 | 3.30-18.10 |
| 14 | T | C30 | 911.681 | 801.910 E3 | 12.0 | 91 | 0.00 | 18.93-18.99 |
| 15 | T | C32 | 896.888 | 786.318 E3 | 12.3 | 90 | 0.00 | 19.98-20.04 |
| 16 | T | C34 | 863.538 | 776.202 E3 | 10.1 | 92 | 0.00 | 20.97-21.05 |
| 17 | T | C36 | 856.611 | 744.374 E3 | 13.1 | 90 | 0.00 | 22.03-22.09 |
| 18 | T | C38 | 825.673 | 718.862 E3 | 12.9 | 90 | 0.00 | 23.35-23.41 |
| 19 | T | C40 | 773.463 | 694.937 E3 | 10.2 | 92 | 0.00 | 25.11-25.17 |
| 20 | H | EPH (>C28-C40) | 854.642 | 753.767 E3 | 11.8 | 91 | 0.00 | 18.10-25.30 |
| 21 | H | TOTAL PHC | 870.408 | 778.853 E3 | 10.5 | 91 | 0.00 | 3.30-25.30 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5y35990.D EPH5Y1190.M Thu Sep 01 09:02:30 2016

8.10.14
8

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G5Y1211-CC1190
**Lab FileID:** 5Y36625.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Y1211\5y36625.D Vial: 3
Acq On : 6 Oct 2016 10:21 am Operator: sarahp1
Sample : cc1190-50 Inst : GC5Y5Z
Misc : op97508,g5y1211,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\msdchem\1\METHODS\EPH5Y1190.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Thu Sep 22 09:13:58 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 805.526 | 939.957 E3 | -16.7 | 117 | 0.00 | 3.37- 3.43 |
| 2 | T | C10 | 813.928 | 941.832 E3 | -15.7 | 116 | 0.00 | 4.34- 4.40 |
| 3 | T | C12 | 827.299 | 919.871 E3 | -11.2 | 112 | 0.00 | 6.31- 6.37 |
| 4 | T | C14 | 844.484 | 883.349 E3 | -4.6 | 105 | 0.00 | 8.12- 8.18 |
| 5 | T | C16 | 868.268 | 850.501 E3 | 2.0 | 99 | 0.00 | 9.75- 9.81 |
| 6 | T | C18 | 890.552 | 830.340 E3 | 6.8 | 94 | 0.00 | 11.22-11.28 |
| 7 | T | C20 | 905.330 | 813.066 E3 | 10.2 | 91 | 0.00 | 12.63-12.69 |
| 8 | T | C21 | 916.198 | 813.060 E3 | 11.3 | 90 | 0.00 | 13.32-13.38 |
| 9 | T | C22 | 923.910 | 804.901 E3 | 12.9 | 89 | 0.00 | 14.00-14.06 |
| 10 | T | C24 | 918.775 | 792.921 E3 | 13.7 | 88 | 0.00 | 15.32-15.38 |
| 11 | T | C26 | 922.586 | 785.939 E3 | 14.8 | 88 | 0.00 | 16.57-16.63 |
| 12 | T | C28 | 902.633 | 772.377 E3 | 14.4 | 87 | 0.00 | 17.76-17.82 |
| 13 | H | EPH (C9-C28) | 878.291 | 845.676 E3 | 3.7 | 98 | 0.00 | 3.30-18.10 |
| 14 | T | C30 | 911.681 | 775.411 E3 | 14.9 | 88 | 0.00 | 18.87-18.93 |
| 15 | T | C32 | 896.888 | 772.994 E3 | 13.8 | 88 | 0.00 | 19.92-19.98 |
| 16 | T | C34 | 863.538 | 750.116 E3 | 13.1 | 89 | 0.00 | 20.91-20.99 |
| 17 | T | C36 | 856.611 | 751.962 E3 | 12.2 | 90 | 0.00 | 21.96-22.02 |
| 18 | T | C38 | 825.673 | 739.019 E3 | 10.5 | 93 | 0.00 | 23.27-23.33 |
| 19 | T | C40 | 773.463 | 647.903 E3 | 16.2 | 86 | 0.00 | 25.00-25.06 |
| 20 | H | EPH (>C28-C40) | 854.642 | 739.568 E3 | 13.5 | 89 | 0.00 | 18.10-25.30 |
| 21 | H | TOTAL PHC | 870.408 | 810.307 E3 | 6.9 | 94 | 0.00 | 3.30-25.30 |
| 22 | S | o-Terphenyl (S) | 965.337 | 909.051 E3 | 5.8 | 95 | 0.00 | 11.94-12.00 |
| 23 | S | 1-chlorooctadecane (S) | 790.673 | 689.983 E3 | 12.7 | 88 | 0.00 | 13.25-13.31 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5y36451.D EPH5Y1190.M Thu Oct 06 14:21:39 2016

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G5Y1211-CC1190
**Lab FileID:** 5Y36632.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Y1211\5y36632.D Vial: 2
Acq On : 6 Oct 2016 2:41 pm Operator: sarahp1
Sample : cc1190-20 Inst : GC5Y5Z
Misc : op97541,g5y1211,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\msdchem\1\METHODS\EPH5Y1190.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Thu Oct 06 15:18:54 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 805.526 | 982.289 E3 | -21.9 | 120 | 0.00 | 3.37- 3.43 |
| 2 | T | C10 | 813.928 | 984.159 E3 | -20.9 | 119 | 0.00 | 4.33- 4.39 |
| 3 | T | C12 | 827.299 | 981.492 E3 | -18.6 | 117 | 0.00 | 6.30- 6.36 |
| 4 | T | C14 | 844.484 | 971.984 E3 | -15.1 | 114 | 0.00 | 8.12- 8.18 |
| 5 | T | C16 | 868.268 | 960.057 E3 | -10.6 | 109 | 0.00 | 9.75- 9.81 |
| 6 | T | C18 | 890.552 | 947.127 E3 | -6.4 | 105 | 0.00 | 11.22-11.28 |
| 7 | T | C20 | 905.330 | 926.749 E3 | -2.4 | 101 | 0.00 | 12.62-12.68 |
| 8 | T | C21 | 916.198 | 927.207 E3 | -1.2 | 100 | 0.00 | 13.31-13.37 |
| 9 | T | C22 | 923.910 | 916.300 E3 | 0.8 | 99 | 0.00 | 13.99-14.05 |
| 10 | T | C24 | 918.775 | 893.903 E3 | 2.7 | 96 | 0.00 | 15.31-15.37 |
| 11 | T | C26 | 922.586 | 877.021 E3 | 4.9 | 94 | 0.00 | 16.57-16.63 |
| 12 | T | C28 | 902.633 | 854.093 E3 | 5.4 | 93 | 0.00 | 17.75-17.81 |
| 13 | H | EPH (C9-C28) | 878.291 | 935.198 E3 | -6.5 | 106 | 0.00 | 3.30-18.10 |
| 14 | T | C30 | 911.681 | 850.430 E3 | 6.7 | 92 | 0.00 | 18.87-18.93 |
| 15 | T | C32 | 896.888 | 840.965 E3 | 6.2 | 92 | 0.00 | 19.91-19.97 |
| 16 | T | C34 | 863.538 | 807.793 E3 | 6.5 | 92 | 0.00 | 20.90-20.98 |
| 17 | T | C36 | 856.611 | 791.873 E3 | 7.6 | 91 | 0.00 | 21.95-22.01 |
| 18 | T | C38 | 825.673 | 724.825 E3 | 12.2 | 87 | 0.00 | 23.25-23.31 |
| 19 | T | C40 | 773.463 | 592.635 E3 | 23.4 | 75 | 0.00 | 24.98-25.04 |
| 20 | H | EPH (>C28-C40) | 854.642 | 768.087 E3 | 10.1 | 88 | 0.00 | 18.10-25.30 |
| 21 | H | TOTAL PHC | 870.408 | 879.494 E3 | -1.0 | 97 | 0.00 | 3.30-25.30 |
| 22 | S | o-Terphenyl (S) | 965.337 | 1020.885 E3 | -5.8 | 105 | 0.00 | 11.93-11.99 |
| 23 | S | 1-chlorooctadecane (S) | 790.673 | 776.699 E3 | 1.8 | 97 | 0.00 | 13.24-13.30 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5y36632.D EPH5Y1190.M Thu Oct 06 15:19:51 2016

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G5Y1211-CC1190
**Lab FileID:** 5Y36638.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Y1211\5y36638.D Vial: 3
Acq On : 6 Oct 2016 6:06 pm Operator: sarahp1
Sample : cc1190-50 Inst : GC5Y5Z
Misc : op97541,g5y1211,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\msdchem\1\METHODS\EPH5Y1190.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Thu Oct 06 15:18:54 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 805.526 | 961.600 E3 | -19.4 | 120 | 0.00 | 3.37- 3.43 |
| 2 | T | C10 | 813.928 | 963.354 E3 | -18.4 | 119 | 0.00 | 4.34- 4.40 |
| 3 | T | C12 | 827.299 | 941.164 E3 | -13.8 | 114 | 0.00 | 6.31- 6.37 |
| 4 | T | C14 | 844.484 | 917.845 E3 | -8.7 | 109 | 0.00 | 8.12- 8.18 |
| 5 | T | C16 | 868.268 | 901.790 E3 | -3.9 | 105 | 0.00 | 9.75- 9.81 |
| 6 | T | C18 | 890.552 | 895.449 E3 | -0.5 | 101 | 0.00 | 11.22-11.28 |
| 7 | T | C20 | 905.330 | 883.883 E3 | 2.4 | 99 | 0.00 | 12.63-12.69 |
| 8 | T | C21 | 916.198 | 888.107 E3 | 3.1 | 98 | 0.00 | 13.32-13.38 |
| 9 | T | C22 | 923.910 | 881.274 E3 | 4.6 | 98 | 0.00 | 14.00-14.06 |
| 10 | T | C24 | 918.775 | 867.987 E3 | 5.5 | 97 | 0.00 | 15.32-15.38 |
| 11 | T | C26 | 922.586 | 855.882 E3 | 7.2 | 95 | 0.00 | 16.58-16.64 |
| 12 | T | C28 | 902.633 | 836.385 E3 | 7.3 | 95 | 0.00 | 17.76-17.82 |
| 13 | H | EPH (C9-C28) | 878.291 | 899.560 E3 | -2.4 | 104 | 0.00 | 3.30-18.10 |
| 14 | T | C30 | 911.681 | 835.500 E3 | 8.4 | 94 | 0.00 | 18.87-18.93 |
| 15 | T | C32 | 896.888 | 834.632 E3 | 6.9 | 95 | 0.01 | 19.92-19.98 |
| 16 | T | C34 | 863.538 | 807.658 E3 | 6.5 | 96 | 0.01 | 20.91-20.99 |
| 17 | T | C36 | 856.611 | 808.802 E3 | 5.6 | 97 | 0.02 | 21.96-22.02 |
| 18 | T | C38 | 825.673 | 804.361 E3 | 2.6 | 101 | 0.02 | 23.27-23.33 |
| 19 | T | C40 | 773.463 | 790.299 E3 | -2.2 | 104 | 0.03 | 25.00-25.06 |
| 20 | H | EPH (>C28-C40) | 854.642 | 813.542 E3 | 4.8 | 98 | 0.00 | 18.10-25.30 |
| 21 | H | TOTAL PHC | 870.408 | 870.887 E3 | -0.1 | 101 | 0.00 | 3.30-25.30 |
| 22 | S | o-Terphenyl (S) | 965.337 | 971.458 E3 | -0.6 | 102 | 0.00 | 11.94-12.00 |
| 23 | S | 1-chlorooctadecane (S) | 790.673 | 763.558 E3 | 3.4 | 98 | 0.00 | 13.25-13.31 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5y36451.D EPH5Y1190.M Fri Oct 07 10:23:25 2016

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** G5Z1024-ICC1024
**Lab FileID:** 5Z29836.D

Response Factor Report GC5Y5Z

Method : C:\msdchem\1\METHODS\EPH5Z1024.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Tue Sep 20 09:42:33 2016
Response via : Initial Calibration

Calibration Files
5 =5z29833.D 10 =5z29834.D 50 =5z29836.D 100 =5z29837.D
2 =5z29832.D 20 =5z29835.D =

| Compound | 5 | 10 | 50 | 100 | 2 | 20 | Avg | %RSD |
|---|---|---|---|---|---|---|---|---|
| 1)T C9 | 7.124 | 7.464 | 6.996 | 6.978 | 6.882 | 7.179 | 7.104 E5 | 2.90 |
| 2)T C10 | 7.288 | 7.637 | 7.151 | 7.184 | 7.057 | 7.312 | 7.272 E5 | 2.78 |
| 3)T C12 | 7.579 | 7.978 | 7.519 | 7.591 | 7.348 | 7.633 | 7.608 E5 | 2.72 |
| 4)T C14 | 7.822 | 8.303 | 7.848 | 7.941 | 7.738 | 7.957 | 7.935 E5 | 2.49 |
| 5)T C16 | 8.057 | 8.614 | 8.146 | 8.217 | 8.102 | 8.305 | 8.240 E5 | 2.46 |
| 6)T C18 | 8.292 | 8.907 | 8.408 | 8.443 | 8.496 | 8.627 | 8.529 E5 | 2.53 |
| 7)T C20 | 8.411 | 9.045 | 8.541 | 8.569 | 8.679 | 8.832 | 8.680 E5 | 2.63 |
| 8)T C21 | 8.527 | 9.159 | 8.678 | 8.696 | 8.781 | 8.996 | 8.806 E5 | 2.63 |
| 9)T C22 | 8.569 | 9.177 | 8.692 | 8.709 | 9.163 | 9.037 | 8.891 E5 | 2.99 |
| 10)T C24 | 8.619 | 9.106 | 8.736 | 8.732 | 8.980 | 9.114 | 8.881 E5 | 2.40 |
| 11)T C26 | 8.621 | 9.037 | 8.762 | 8.731 | 9.010 | 9.144 | 8.884 E5 | 2.33 |
| 12)T C28 | 8.569 | 8.871 | 8.699 | 8.657 | 9.007 | 9.104 | 8.818 E5 | 2.39 |
| 13)H EPH (C9-C28) | 8.123 | 8.608 | 8.181 | 8.204 | 8.270 | 8.437 | 8.304 E5 | 2.21 |
| 14)T C30 | 8.734 | 8.858 | 8.792 | 8.729 | 9.204 | 9.230 | 8.924 E5 | 2.59 |
| 15)T C32 | 8.760 | 8.783 | 8.791 | 8.711 | 9.223 | 9.265 | 8.922 E5 | 2.81 |
| 16)T C34 | 8.478 | 8.458 | 8.488 | 8.401 | 8.606 | 8.973 | 8.567 E5 | 2.45 |
| 17)T C36 | 8.461 | 8.451 | 8.491 | 8.398 | 8.891 | 8.986 | 8.613 E5 | 2.97 |
| 18)T C38 | 8.593 | 8.427 | 8.259 | 8.146 | 9.033 | 8.757 | 8.536 E5 | 3.85 |
| 19)T C40 | 7.844 | 7.962 | 7.920 | 7.828 | 8.140 | 8.358 | 8.009 E5 | 2.55 |
| 20)H EPH (>C28-C40) | 8.478 | 8.490 | 8.457 | 8.369 | 8.849 | 8.928 | 8.595 E5 | 2.71 |
| 21)H TOTAL PHC | 8.241 | 8.569 | 8.273 | 8.259 | 8.463 | 8.600 | 8.401 E5 | 1.95 |
| 22)S o-Terphenyl (S) | 8.873 | 9.498 | 9.018 | 9.079 | 9.039 | 9.211 | 9.120 E5 | 2.35 |
| 23)S 1-chlorooctadecan | 7.341 | 7.881 | 7.476 | 7.499 | 7.551 | 7.731 | 7.580 E5 | 2.57 |
| 24)S 2-Fluorobiphenyl | | | | | | | 0.000# | -1.00 |
| 25)S 2-Bromonaphthalen | | | | | | | 0.000# | -1.00 |

(#) = Out of Range

EPH5Z1024.M Tue Sep 20 09:50:28 2016

8.10.18

8

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G5Z1024-ICV1024
**Lab FileID:** 5Z29838.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Z1024\5z29838.D Vial: 58
Acq On : 19 Sep 2016 9:55 pm Operator: sarahp1
Sample : icv1024-50 Inst : GC5Y5Z
Misc : op97053,g5z1024,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\msdchem\1\METHODS\EPH5Z1024.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Tue Sep 20 09:42:33 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 710.380 | 654.871 E3 | 7.8 | 94 | 0.00 | 3.16- 3.22 |
| 2 | T | C10 | 727.177 | 679.290 E3 | 6.6 | 95 | 0.00 | 4.12- 4.18 |
| 3 | T | C12 | 760.809 | 754.321 E3 | 0.9 | 100 | 0.00 | 6.08- 6.14 |
| 4 | T | C14 | 793.477 | 781.764 E3 | 1.5 | 100 | 0.00 | 7.89- 7.95 |
| 5 | T | C16 | 824.025 | 821.287 E3 | 0.3 | 101 | 0.00 | 9.51- 9.57 |
| 6 | T | C18 | 852.903 | 846.616 E3 | 0.7 | 101 | 0.00 | 10.97-11.03 |
| 7 | T | C20 | 867.953 | 874.717 E3 | -0.8 | 102 | 0.00 | 12.35-12.41 |
| 8 | T | C21 | 880.596 | 881.309 E3 | -0.1 | 102 | 0.00 | 13.04-13.10 |
| 9 | T | C22 | 889.120 | 891.767 E3 | -0.3 | 103 | 0.00 | 13.71-13.77 |
| 10 | T | C24 | 888.123 | 890.268 E3 | -0.2 | 102 | 0.00 | 14.85-14.91 |
| 11 | T | C26 | 888.421 | 879.222 E3 | 1.0 | 100 | 0.00 | 15.73-15.79 |
| 12 | T | C28 | 881.780 | 868.097 E3 | 1.6 | 100 | 0.00 | 16.69-16.75 |
| 13 | H | EPH (C9-C28) | 830.397 | 818.627 E3 | 1.4 | 100 | 0.00 | 3.10-16.90 |
| 14 | T | C30 | 892.441 | 858.999 E3 | 3.7 | 98 | 0.00 | 17.68-17.74 |
| 15 | T | C32 | 892.199 | 830.685 E3 | 6.9 | 94 | 0.00 | 18.66-18.72 |
| 16 | T | C34 | 856.729 | 807.111 E3 | 5.8 | 95 | 0.00 | 19.60-19.68 |
| 17 | T | C36 | 861.290 | 763.630 E3 | 11.3 | 90 | 0.00 | 20.52-20.58 |
| 18 | T | C38 | 853.588 | 734.803 E3 | 13.9 | 89 | 0.00 | 21.43-21.49 |
| 19 | T | C40 | 800.858 | 710.971 E3 | 11.2 | 90 | 0.00 | 22.53-22.59 |
| 20 | H | EPH (>C28-C40) | 859.518 | 784.366 E3 | 8.7 | 93 | 0.00 | 16.90-22.70 |
| 21 | H | TOTAL PHC | 840.104 | 807.207 E3 | 3.9 | 96 | 0.00 | 3.10-22.70 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5z29836.D EPH5Z1024.M Tue Sep 20 09:43:49 2016

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G5Z1032-CC1024
**Lab FileID:** 5Z30025.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Z1032\5z30025.D Vial: 2
Acq On : 6 Oct 2016 10:21 am Operator: sarahp1
Sample : cc1024-20 Inst : GC5Y5Z
Misc : op97337,g5z1032,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\MSDCHEM\1\METHODS\EPH5Z1024.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Tue Sep 27 16:33:21 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 710.380 | 791.878 E3 | -11.5 | 110 | 0.00 | 3.15- 3.21 |
| 2 | T | C10 | 727.177 | 825.827 E3 | -13.6 | 113 | -0.01 | 4.10- 4.16 |
| 3 | T | C12 | 760.809 | 881.021 E3 | -15.8 | 115 | -0.01 | 6.05- 6.11 |
| 4 | T | C14 | 793.477 | 938.575 E3 | -18.3 | 118 | -0.01 | 7.86- 7.92 |
| 5 | T | C16 | 824.025 | 990.456 E3 | -20.2 | 119 | -0.01 | 9.48- 9.54 |
| 6 | T | C18 | 852.903 | 1021.910 E3 | -19.8 | 118 | -0.01 | 10.95-11.01 |
| 7 | T | C20 | 867.953 | 1038.560 E3 | -19.7 | 118 | -0.01 | 12.32-12.38 |
| 8 | T | C21 | 880.596 | 1048.435 E3 | -19.1 | 117 | -0.01 | 13.01-13.07 |
| 9 | T | C22 | 889.120 | 1044.884 E3 | -17.5 | 116 | -0.01 | 13.68-13.74 |
| 10 | T | C24 | 888.123 | 1033.511 E3 | -16.4 | 113 | 0.00 | 14.83-14.89 |
| 11 | T | C26 | 888.421 | 1018.600 E3 | -14.7 | 111 | 0.00 | 15.71-15.77 |
| 12 | T | C28 | 881.780 | 994.464 E3 | -12.8 | 109 | -0.01 | 16.66-16.72 |
| 13 | H | EPH (C9-C28) | 830.397 | 969.010 E3 | -16.7 | 115 | 0.00 | 3.10-16.90 |
| 14 | T | C30 | 892.441 | 989.418 E3 | -10.9 | 107 | 0.00 | 17.65-17.71 |
| 15 | T | C32 | 892.199 | 977.060 E3 | -9.5 | 105 | -0.01 | 18.63-18.69 |
| 16 | T | C34 | 856.729 | 935.908 E3 | -9.2 | 104 | 0.00 | 19.56-19.64 |
| 17 | T | C36 | 861.290 | 930.891 E3 | -8.1 | 104 | 0.00 | 20.49-20.55 |
| 18 | T | C38 | 853.588 | 904.990 E3 | -6.0 | 103 | -0.01 | 21.39-21.45 |
| 19 | T | C40 | 800.858 | 870.483 E3 | -8.7 | 104 | -0.01 | 22.47-22.53 |
| 20 | H | EPH (>C28-C40) | 859.518 | 934.792 E3 | -8.8 | 105 | 0.00 | 16.90-22.70 |
| 21 | H | TOTAL PHC | 840.104 | 957.604 E3 | -14.0 | 110 | 0.00 | 3.10-22.70 |
| 22 | S | o-Terphenyl (S) | 911.965 | 1084.760 E3 | -18.9 | 118 | -0.01 | 11.64-11.70 |
| 23 | S | 1-chlorooctadecane (S) | 757.982 | 900.081 E3 | -18.7 | 116 | -0.01 | 12.94-13.00 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5z29913.D EPH5Z1024.M Thu Oct 06 14:38:43 2016

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** G5Z1032-CC1024
**Lab FileID:** 5Z30033.D

Evaluate Continuing Calibration Report

Data File : C:\msdchem\1\DATA\G5Z1032\5z30033.D Vial: 3
Acq On : 6 Oct 2016 3:12 pm Operator: sarahp1
Sample : cc1024-50 Inst : GC5Y5Z
Misc : op97541,g5z1032,15.0,,,2,1 Multiplr: 1.00
IntFile : autoint1.e

Method : C:\MSDCHEM\1\METHODS\EPH5Z1024.M (ChemStation Integrator)
Title : NJDEP Extractable Petroleum Hydrocarbons
Last Update : Tue Sep 27 16:33:21 2016
Response via : Multiple Level Calibration

Min. RRF : 0.100 Min. Rel. Area : 50% Max. R.T. Dev 0.50min
Max. RRF Dev : 30% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | T | C9 | 710.380 | 761.994 E3 | -7.3 | 109 | 0.00 | 3.15- 3.21 |
| 2 | T | C10 | 727.177 | 787.356 E3 | -8.3 | 110 | 0.00 | 4.10- 4.16 |
| 3 | T | C12 | 760.809 | 829.527 E3 | -9.0 | 110 | 0.00 | 6.06- 6.12 |
| 4 | T | C14 | 793.477 | 865.430 E3 | -9.1 | 110 | 0.00 | 7.87- 7.93 |
| 5 | T | C16 | 824.025 | 889.336 E3 | -7.9 | 109 | 0.00 | 9.49- 9.55 |
| 6 | T | C18 | 852.903 | 907.980 E3 | -6.5 | 108 | 0.00 | 10.95-11.01 |
| 7 | T | C20 | 867.953 | 918.901 E3 | -5.9 | 108 | 0.00 | 12.33-12.39 |
| 8 | T | C21 | 880.596 | 931.371 E3 | -5.8 | 107 | 0.00 | 13.01-13.07 |
| 9 | T | C22 | 889.120 | 930.480 E3 | -4.7 | 107 | 0.00 | 13.69-13.75 |
| 10 | T | C24 | 888.123 | 932.577 E3 | -5.0 | 107 | 0.00 | 14.83-14.89 |
| 11 | T | C26 | 888.421 | 931.749 E3 | -4.9 | 106 | 0.00 | 15.71-15.77 |
| 12 | T | C28 | 881.780 | 921.287 E3 | -4.5 | 106 | 0.00 | 16.67-16.73 |
| 13 | H | EPH (C9-C28) | 830.397 | 883.999 E3 | -6.5 | 108 | 0.00 | 3.10-16.90 |
| 14 | T | C30 | 892.441 | 924.176 E3 | -3.6 | 105 | 0.00 | 17.66-17.72 |
| 15 | T | C32 | 892.199 | 916.880 E3 | -2.8 | 104 | 0.00 | 18.63-18.69 |
| 16 | T | C34 | 856.729 | 874.507 E3 | -2.1 | 103 | 0.00 | 19.57-19.65 |
| 17 | T | C36 | 861.290 | 862.550 E3 | -0.1 | 102 | 0.00 | 20.49-20.55 |
| 18 | T | C38 | 853.588 | 826.510 E3 | 3.2 | 100 | 0.00 | 21.40-21.46 |
| 19 | T | C40 | 800.858 | 784.876 E3 | 2.0 | 99 | 0.00 | 22.48-22.54 |
| 20 | H | EPH (>C28-C40) | 859.518 | 864.917 E3 | -0.6 | 102 | 0.00 | 16.90-22.70 |
| 21 | H | TOTAL PHC | 840.104 | 877.638 E3 | -4.5 | 105 | 0.00 | 3.10-22.70 |
| 22 | S | o-Terphenyl (S) | 911.965 | 972.089 E3 | -6.6 | 108 | 0.00 | 11.65-11.71 |
| 23 | S | 1-chlorooctadecane (S) | 757.982 | 801.317 E3 | -5.7 | 107 | 0.00 | 12.94-13.00 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
5z29836.D EPH5Z1024.M Thu Oct 06 15:39:31 2016

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** GOA4125-ICC4125
**Lab FileID:** OA119877.D

Response Factor Report GCOA

Method : C:\MSDCHEM\1\METHODS\HOA4125.M (Chemstation Integrator)
Title : HERB
Last Update : Tue Sep 20 14:28:40 2016
Response via : Initial Calibration

Calibration Files
500 =OA119879.D 400 =OA119878.D 300 =OA119877.D 200 =OA119876.D
100 =OA119875.D 50 =OA119874.D

| | | Compound | 500 | 400 | 300 | 200 | 100 | 50 | Avg | | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) | | Dalapon | 2.368 | 2.419 | 2.442 | 2.598 | 2.707 | 2.866 | 2.567 | E7 | 7.54 |
| 2) | S | 2,4-DCAA | 1.250 | 1.274 | 1.312 | 1.409 | 1.603 | 1.838 | 1.448 | E7 | 15.90 |
| 3) | | Dicamba | 7.572 | 7.792 | 8.027 | 8.303 | 8.722 | 9.195 | 8.268 | E7 | 7.33 |
| 4) | | MCPP | 3.165 | 3.150 | 3.083 | 3.080 | 2.909 | | 3.077 | E4 | 3.31 |
| 5) | | MCPA | 4.487 | 4.461 | 4.380 | 4.433 | 4.216 | | 4.395 | E4 | 2.45 |
| 6) | | Dichloroprop | 1.518 | 1.581 | 1.665 | 1.813 | 2.112 | 2.363 | 1.842 | E7 | 18.00 |
| 7) | | 2,4-D | 1.819 | 1.904 | 1.982 | 2.167 | 2.473 | 2.748 | 2.182 | E7 | 16.58 |
| 8) | | Pentachlorophenol | 4.804 | 4.805 | 4.660 | 4.778 | 4.653 | 4.628 | 4.721 | E8 | 1.75 |
| 9) | | 2,4,5-TP | 1.370 | 1.403 | 1.407 | 1.457 | 1.488 | 1.547 | 1.445 | E8 | 4.51 |
| 10) | | 2,4,5-T | 1.299 | 1.319 | 1.323 | 1.350 | 1.385 | 1.420 | 1.349 | E8 | 3.39 |
| 11) | | 2,4-DB | 0.998 | 1.026 | 1.051 | 1.126 | 1.358 | 1.316 | 1.146 | E7 | 13.52 |
| 12) | | Dinoseb | 5.288 | 5.450 | 5.536 | 5.914 | 5.867 | 6.369 | 5.738 | E7 | 6.85 |
| 13) | | Picloram | 1.280 | 1.344 | 1.332 | 1.369 | 1.296 | 1.305 | 1.321 | E8 | 2.52 |

Signal #2

| | | Compound | 500 | 400 | 300 | 200 | 100 | 50 | Avg | | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) | | Dalapon | 1.026 | 1.055 | 1.073 | 1.144 | 1.195 | 1.257 | 1.125 | E7 | 7.96 |
| 2) | S | 2,4-DCAA | 0.683 | 0.705 | 0.724 | 0.777 | 0.876 | 1.016 | 0.797 | E7 | 16.00 |
| 3) | | Dicamba | 2.882 | 3.010 | 3.126 | 3.299 | 3.559 | 3.953 | 3.305 | E7 | 11.97 |
| 4) | | MCPP | 3.130 | 3.271 | 3.449 | 3.818 | 4.418 | | 3.617 | E4 | 14.28 |
| 5) | | MCPA | 4.903 | 5.155 | 5.528 | 6.278 | 7.656 | | 5.904 | E4 | 18.77 |
| 6) | | Dichloroprop | 0.707 | 0.737 | 0.772 | 0.840 | 0.964 | 1.103 | 0.854 | E7 | 17.89 |
| 7) | | 2,4-D | 0.946 | 0.985 | 1.010 | 1.089 | 1.204 | 1.369 | 1.100 | E7 | 14.57 |
| 8) | | Pentachlorophenol | 1.572 | 1.621 | 1.598 | 1.658 | 1.685 | 1.741 | 1.646 | E8 | 3.76 |
| 9) | | 2,4,5-TP | 5.044 | 5.204 | 5.287 | 5.542 | 5.759 | 6.129 | 5.494 | E7 | 7.31 |
| 10) | | 2,4,5-T | 5.161 | 5.277 | 5.323 | 5.552 | 5.691 | 6.298 | 5.550 | E7 | 7.46 |
| 11) | | 2,4-DB | 5.687 | 5.850 | 5.933 | 6.367 | 7.009 | 8.603 | 6.575 | E6 | 16.76 |
| 12) | | Dinoseb | 2.610 | 2.684 | 2.746 | 2.901 | 3.084 | 3.384 | 2.901 | E7 | 10.02 |
| 13) | | Picloram | 4.120 | 4.239 | 4.368 | 4.586 | 4.920 | 5.372 | 4.601 | E7 | 10.25 |

(#) = Out of Range

HOA4125.M Tue Sep 20 14:31:46 2016 RPT1

8.10.22
8

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GOA4125-ICV4125
**Lab FileID:** OA119880.D

Evaluate Continuing Calibration Report

Signal #1 : C:\MSDCHEM\1\DATA\GOA4125\OA119880.D\ECD1A.CH Vial: 8
Signal #2 : C:\MSDCHEM\1\DATA\GOA4125\OA119880.D\ECD2B.CH
Acq On : 9-20-16 01:14:14 PM Operator: vinced
Sample : icv4125-300 Inst : GCOA
Misc : op97082,GOA4125,100,,,10,1 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\HOA4125.M (Chemstation Integrator)
Title : HERB
Last Update : Tue Sep 20 14:28:40 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | Dalapon | 25.667 | 26.058 | E6 | -1.5 | 107 | 0.00 | 2.30- 2.36 |
| 2 | S | 2,4-DCAA | 14.477 | 13.287 | E6 | 8.2 | 101 | 0.00 | 7.16- 7.22 |
| 3 | | Dicamba | 82.685 | 83.685 | E6 | -1.2 | 104 | 0.00 | 7.35- 7.41 |
| 4 | | MCPP | 30.773 | 32.522 | E3 | -5.7 | 105 | 0.00 | 7.60- 7.66 |
| 5 | | MCPA | 43.955 | 43.234 | E3 | 1.6 | 99 | 0.00 | 7.77- 7.83 |
| 6 | | Dichloroprop | 18.421 | 15.831 | E6 | 14.1 | 95 | 0.00 | 8.20- 8.26 |
| 7 | | 2,4-D | 21.820 | 20.880 | E6 | 4.3 | 105 | 0.00 | 8.48- 8.54 |
| 8 | | Pentachlorophenol | 472.131 | 401.625 | E6 | 14.9 | 86 | 0.00 | 8.70- 8.76 |
| 9 | | 2,4,5-TP | 144.525 | 147.302 | E6 | -1.9 | 105 | 0.00 | 9.52- 9.58 |
| 10 | | 2,4,5-T | 134.940 | 147.574 | E6 | -9.4 | 112 | 0.00 | 9.87- 9.93 |
| 11 | | 2,4-DB | 11.459 | 11.040 | E6 | 3.7 | 105 | 0.00 | 10.58-10.64 |
| 12 | | Dinoseb | 57.376 | 65.123 | E6 | -13.5 | 118 | 0.00 | 12.00-12.06 |
| 13 | | Picloram | 132.126 | 105.815 | E6 | 19.9 | 79 | 0.00 | 11.75-11.81 |

***** Signal #2 *****

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | Dalapon | 11.250 | 11.463 | E6 | -1.9 | 107 | 0.00 | 2.48- 2.54 |
| 2 | S | 2,4-DCAA | 7.968 | 7.313 | E6 | 8.2 | 101 | 0.00 | 8.02- 8.08 |
| 3 | | Dicamba | 33.048 | 32.930 | E6 | 0.4 | 105 | 0.00 | 8.25- 8.31 |
| 4 | | MCPP | 36.173 | 35.978 | E3 | 0.5 | 104 | 0.00 | 8.40- 8.46 |
| 5 | | MCPA | 59.040 | 56.303 | E3 | 4.6 | 102 | 0.00 | 8.71- 8.77 |
| 6 | | Dichloroprop | 8.538 | 7.418 | E6 | 13.1 | 96 | 0.00 | 9.16- 9.22 |
| 7 | | 2,4-D | 11.005 | 10.773 | E6 | 2.1 | 107 | 0.00 | 9.59- 9.65 |
| 8 | | Pentachlorophenol | 164.597 | 139.505 | E6 | 15.2 | 87 | 0.00 | 10.09-10.15 |
| 9 | | 2,4,5-TP | 54.943 | 56.353 | E6 | -2.6 | 107 | 0.00 | 10.70-10.76 |
| 10 | | 2,4,5-T | 55.505 | 58.781 | E6 | -5.9 | 110 | 0.00 | 11.25-11.31 |
| 11 | | 2,4-DB | 6.575 | 6.305 | E6 | 4.1 | 106 | 0.00 | 11.97-12.03 |
| 12 | | Dinoseb | 29.015 | 32.435 | E6 | -11.8 | 118 | 0.00 | 12.37-12.43 |
| 13 | | Picloram | 46.008 | 35.411 | E6 | 23.0# | 81 | 0.00 | 13.82-13.88 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
OA119877.D HOA4125.M Tue Sep 20 14:32:14 2016 RPT1

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GOA4139-CC4125
**Lab FileID:** OA120267.D

Evaluate Continuing Calibration Report

Data File : C:\MSDCHEM\1\DATA\GOA4139\OA120267.D\ECD1A.CH Vial: 2
Acq On : 10-7-16 09:18:54 AM Operator: vinced
Sample : cc4125-200 Inst : GCOA
Misc : op97511,GOA4139,15.8,,,5,1 Multiplr: 1.00
IntFile : autoint1.e

Data File : C:\MSDCHEM\1\DATA\GOA4139\OA120267.D\ECD2B.CH Vial: 2
Acq On : 10-7-16 09:18:53 AM Operator: vinced
Sample : cc4125-200 Inst : GCOA
Misc : op97511,GOA4139,15.8,,,5,1 Multiplr: 1.00
IntFile : autoint2.e

Method : C:\MSDCHEM\1\METHODS\HOA4125.M (Chemstation Integrator)
Title : HERB
Last Update : Fri Oct 07 14:31:09 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 1 | Dalapon | 25.667 | 28.399 E6 | -10.6 | 109 | 0.00 | 2.29- 2.35 |
| 2 S | 2,4-DCAA | 14.477 | 15.970 E6 | -10.3 | 113 | 0.00 | 7.16- 7.22 |
| 3 | Dicamba | 82.685 | 91.454 E6 | -10.6 | 110 | 0.00 | 7.35- 7.41 |
| 4 | MCPP | 30.773 | 32.133 E3 | -4.4 | 104 | 0.00 | 7.60- 7.66 |
| 5 | MCPA | 43.955 | 44.928 E3 | -2.2 | 101 | 0.00 | 7.77- 7.83 |
| 6 | Dichloroprop | 18.421 | 21.395 E6 | -16.1 | 118 | 0.00 | 8.20- 8.26 |
| 7 | 2,4-D | 21.820 | 25.442 E6 | -16.6 | 117 | 0.00 | 8.48- 8.54 |
| 8 | Pentachlorophenol | 472.131 | 537.735 E6 | -13.9 | 113 | 0.00 | 8.70- 8.76 |
| 9 | 2,4,5-TP | 144.525 | 164.863 E6 | -14.1 | 113 | 0.00 | 9.52- 9.58 |
| 10 | 2,4,5-T | 134.940 | 151.466 E6 | -12.2 | 112 | 0.00 | 9.88- 9.94 |
| 11 | 2,4-DB | 11.459 | 14.074 E6 | -22.8# | 125 | 0.00 | 10.59-10.65 |
| 12 | Dinoseb | 57.376 | 69.809 E6 | -21.7# | 118 | 0.00 | 12.00-12.06 |
| 13 | Picloram | 132.126 | 147.862 E6 | -11.9 | 108 | 0.00 | 11.75-11.81 |
| ***** | Signal #2 ***** | | | | | | |
| 1 | Dalapon | 11.250 | 10.610 E6 | 5.7 | 93 | 0.00 | 2.48- 2.54 |
| 2 S | 2,4-DCAA | 7.968 | 7.944 E6 | 0.3 | 102 | 0.00 | 8.02- 8.08 |
| 3 | Dicamba | 33.048 | 32.960 E6 | 0.3 | 100 | 0.00 | 8.25- 8.31 |
| 4 | MCPP | 36.173 | 40.796 E3 | -12.8 | 107 | 0.00 | 8.41- 8.47 |
| 5 | MCPA | 59.040 | 70.509 E3 | -19.4 | 112 | 0.00 | 8.72- 8.78 |
| 6 | Dichloroprop | 8.538 | 8.104 E6 | 5.1 | 96 | 0.00 | 9.17- 9.23 |
| 7 | 2,4-D | 11.005 | 10.982 E6 | 0.2 | 101 | 0.00 | 9.59- 9.65 |
| 8 | Pentachlorophenol | 164.597 | 168.378 E6 | -2.3 | 102 | 0.00 | 10.09-10.15 |
| 9 | 2,4,5-TP | 54.943 | 54.078 E6 | 1.6 | 98 | 0.00 | 10.71-10.77 |
| 10 | 2,4,5-T | 55.505 | 53.361 E6 | 3.9 | 96 | 0.00 | 11.25-11.31 |
| 11 | 2,4-DB | 6.575 | 7.081 E6 | -7.7 | 111 | 0.00 | 11.98-12.04 |
| 12 | Dinoseb | 29.015 | 30.851 E6 | -6.3 | 106 | 0.00 | 12.38-12.44 |
| 13 | Picloram | 46.008 | 41.047 E6 | 10.8 | 89 | 0.00 | 13.82-13.88 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
OA119876.D HOA4125.M Fri Oct 07 14:31:20 2016 RPT1

8.10.24
8

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GOA4139-CC4125
**Lab FileID:** OA120276.D

Evaluate Continuing Calibration Report

Signal #1 : C:\MSDCHEM\1\DATA\GOA4139\OA120276.D\ECD1A.CH Vial: 3
Signal #2 : C:\MSDCHEM\1\DATA\GOA4139\OA120276.D\ECD2B.CH
Acq On : 10-7-16 01:34:50 PM Operator: vinced
Sample : cc4125-300 Inst : GCOA
Misc : op97538,GOA4139,15.4,,,5,2 Multiplr: 1.00
IntFile Signal #1: autoint1.e IntFile Signal #2: autoint2.e

Method : C:\MSDCHEM\1\METHODS\HOA4125.M (Chemstation Integrator)
Title : HERB
Last Update : Fri Oct 07 14:31:09 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 200%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | | Dalapon | 25.667 | 24.755 E6 | 3.6 | 101 | -0.02 | 2.28- 2.34 |
| 2 | S | 2,4-DCAA | 14.477 | 13.176 E6 | 9.0 | 100 | 0.00 | 7.16- 7.22 |
| 3 | | Dicamba | 82.685 | 81.455 E6 | 1.5 | 101 | 0.00 | 7.35- 7.41 |
| 4 | | MCPP | 30.773 | 30.259 E3 | 1.7 | 98 | 0.00 | 7.59- 7.65 |
| 5 | | MCPA | 43.955 | 40.007 E3 | 9.0 | 91 | 0.00 | 7.76- 7.82 |
| 6 | | Dichloroprop | 18.421 | 17.269 E6 | 6.3 | 104 | 0.00 | 8.20- 8.26 |
| 7 | | 2,4-D | 21.820 | 21.048 E6 | 3.5 | 106 | 0.00 | 8.48- 8.54 |
| 8 | | Pentachlorophenol | 472.131 | 471.454 E6 | 0.1 | 101 | 0.00 | 8.70- 8.76 |
| 9 | | 2,4,5-TP | 144.525 | 143.743 E6 | 0.5 | 102 | 0.00 | 9.52- 9.58 |
| 10 | | 2,4,5-T | 134.940 | 130.483 E6 | 3.3 | 99 | 0.00 | 9.87- 9.93 |
| 11 | | 2,4-DB | 11.459 | 11.780 E6 | -2.8 | 112 | 0.00 | 10.59-10.65 |
| 12 | | Dinoseb | 57.376 | 61.099 E6 | -6.5 | 110 | 0.00 | 11.99-12.05 |
| 13 | | Picloram | 132.126 | 125.895 E6 | 4.7 | 94 | 0.00 | 11.75-11.81 |

***** Signal #2 *****

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | | Dalapon | 11.250 | 10.279 E6 | 8.6 | 96 | -0.02 | 2.46- 2.52 |
| 2 | S | 2,4-DCAA | 7.968 | 6.453 E6 | 19.0 | 89 | 0.00 | 8.02- 8.08 |
| 3 | | Dicamba | 33.048 | 28.808 E6 | 12.8 | 92 | 0.00 | 8.25- 8.31 |
| 4 | | MCPP | 36.173 | 32.312 E3 | 10.7 | 94 | 0.00 | 8.40- 8.46 |
| 5 | | MCPA | 59.040 | 50.298 E3 | 14.8 | 91 | 0.00 | 8.71- 8.77 |
| 6 | | Dichloroprop | 8.538 | 6.919 E6 | 19.0 | 90 | 0.00 | 9.16- 9.22 |
| 7 | | 2,4-D | 11.005 | 8.914 E6 | 19.0 | 88 | 0.00 | 9.59- 9.65 |
| 8 | | Pentachlorophenol | 164.597 | 142.713 E6 | 13.3 | 89 | 0.00 | 10.09-10.15 |
| 9 | | 2,4,5-TP | 54.943 | 48.378 E6 | 11.9 | 92 | 0.00 | 10.70-10.76 |
| 10 | | 2,4,5-T | 55.505 | 45.265 E6 | 18.4 | 85 | 0.00 | 11.25-11.31 |
| 11 | | 2,4-DB | 6.575 | 5.570 E6 | 15.3 | 94 | 0.00 | 11.98-12.04 |
| 12 | | Dinoseb | 29.015 | 25.999 E6 | 10.4 | 95 | 0.00 | 12.37-12.43 |
| 13 | | Picloram | 46.008 | 36.241 E6 | 21.2# | 83 | 0.00 | 13.82-13.88 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
OA119877.D HOA4125.M Fri Oct 07 14:31:38 2016 RPT1

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** GXX5786-ICC5786
**Lab FileID:** XX195648.D

Response Factor Report HP G1530A

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Wed Aug 24 14:53:46 2016
Response via : Initial Calibration

Calibration Files
50 =xx195645.D 250 =xx195646.D 500 =xx195647.D 1000=xx195648.D
2000 =xx195649.D 3000 =xx195650.D

| | | Compound | 50 | 250 | 500 | 1000 | 2000 | 3000 | Avg | | %RSD |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) | S | Tetrachloro-m-xylen | 2.204 | 2.096 | 2.076 | 2.090 | 2.192 | 2.173 | 2.139 | E7 | 2.68 |
| 2) | | AR1221-A | | | | 1.160 | | | 1.160 | E5 | 0.00 |
| 3) | | AR1221-B | | | | 2.037 | | | 2.037 | E5 | 0.00 |
| 4) | | AR1221-C | | | | 6.156 | | | 6.156 | E5 | 0.00 |
| 5) | | AR1221-D | | | | 5.282 | | | 5.282 | E4 | 0.00 |
| 6) | | AR1221-E | | | | 7.028 | | | 7.028 | E4 | 0.00 |
| 7) | | AR1232-A | | | | 5.131 | | | 5.131 | E5 | 0.00 |
| 8) | | AR1232-B | | | | 3.495 | | | 3.495 | E5 | 0.00 |
| 9) | | AR1232-C | | | | 7.782 | | | 7.782 | E5 | 0.00 |
| 10) | | AR1232-D | | | | 2.851 | | | 2.851 | E5 | 0.00 |
| 11) | | AR1232-E | | | | 2.749 | | | 2.749 | E5 | 0.00 |
| 12) | | AR1242-A | | | | 5.938 | | | 5.938 | E5 | 0.00 |
| 13) | | AR1242-B | | | | 1.384 | | | 1.384 | E6 | 0.00 |
| 14) | | AR1242-C | | | | 5.074 | | | 5.074 | E5 | 0.00 |
| 15) | | AR1242-D | | | | 5.503 | | | 5.503 | E5 | 0.00 |
| 16) | | AR1242-E | | | | 6.048 | | | 6.048 | E5 | 0.00 |
| 17) | | AR1248-A | | | | 3.066 | | | 3.066 | E5 | 0.00 |
| 18) | | AR1248-B | | | | 9.241 | | | 9.241 | E5 | 0.00 |
| 19) | | AR1248-C | | | | 8.231 | | | 8.231 | E5 | 0.00 |
| 20) | | AR1248-D | | | | 8.498 | | | 8.498 | E5 | 0.00 |
| 21) | | AR1248-E | | | | 4.678 | | | 4.678 | E5 | 0.00 |
| 22) | | AR1248-F | | | | 9.409 | | | 9.409 | E5 | 0.00 |
| 23) | | AR1248-G | | | | 1.025 | | | 1.025 | E6 | 0.00 |
| 24) | | AR1254-A | | | | 7.377 | | | 7.377 | E5 | 0.00 |
| 25) | | AR1254-B | | | | 9.543 | | | 9.543 | E5 | 0.00 |
| 26) | | AR1254-C | | | | 7.598 | | | 7.598 | E5 | 0.00 |
| 27) | | AR1254-D | | | | 1.527 | | | 1.527 | E6 | 0.00 |
| 28) | | AR1254-E | | | | 1.202 | | | 1.202 | E6 | 0.00 |
| 29) | | AR1254-F | | | | 1.077 | | | 1.077 | E6 | 0.00 |
| 30) | | AR1254-G | | | | 1.505 | | | 1.505 | E6 | 0.00 |
| 31) | | AR1262-A | | | | 1.107 | | | 1.107 | E6 | 0.00 |
| 32) | | AR1262-B | | | | 1.792 | | | 1.792 | E6 | 0.00 |
| 33) | | AR1262-C | | | | 1.375 | | | 1.375 | E6 | 0.00 |
| 34) | | AR1262-D | | | | 4.043 | | | 4.043 | E6 | 0.00 |
| 35) | | AR1262-E | | | | 2.394 | | | 2.394 | E6 | 0.00 |
| 36) | | AR1268-A | | | | 3.924 | | | 3.924 | E6 | 0.00 |
| 37) | | AR1268-B | | | | 4.578 | | | 4.578 | E6 | 0.00 |
| 38) | | AR1268-C | | | | 3.485 | | | 3.485 | E6 | 0.00 |
| 39) | | AR1268-D | | | | 1.353 | | | 1.353 | E6 | 0.00 |
| 40) | | AR1268-E | | | | 9.700 | | | 9.700 | E6 | 0.00 |
| 41) | | AR1016-A | 4.296 | 3.954 | 3.928 | 3.862 | 3.769 | 3.666 | 3.912 | E5 | 5.52 |
| 42) | | AR1016-B | 7.876 | 7.210 | 7.130 | 7.023 | 6.821 | 6.641 | 7.117 | E5 | 5.99 |
| 43) | | AR1016-C | 1.776 | 1.654 | 1.665 | 1.670 | 1.667 | 1.651 | 1.680 | E6 | 2.81 |
| 44) | | AR1016-D | 6.453 | 6.105 | 6.116 | 6.093 | 6.024 | 5.945 | 6.123 | E5 | 2.85 |
| 45) | | AR1016-E | 6.806 | 6.361 | 6.439 | 6.455 | 6.439 | 6.404 | 6.484 | E5 | 2.49 |
| 46) | | AR1260-A | 2.095 | 2.037 | 2.060 | 2.065 | 2.178 | 2.195 | 2.105 | E6 | 3.14 |
| 47) | | AR1260-B | 0.994 | 0.975 | 0.975 | 0.968 | 1.023 | 1.029 | 0.994 | E6 | 2.66 |

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** GXX5786-ICC5786
**Lab FileID:** XX195648.D

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 48) | | AR1260-C | 9.106 | 8.715 | 8.884 | 8.849 | 9.448 | 9.544 | 9.091 | E5 | 3.73 |
| 49) | | AR1260-D | 2.643 | 2.761 | 2.868 | 2.857 | 3.053 | 3.098 | 2.880 | E6 | 5.98 |
| 50) | | AR1260-E | 1.792 | 1.646 | 1.675 | 1.667 | 1.788 | 1.816 | 1.731 | E6 | 4.37 |
| 51) | S | Decachlorobiphenyl | 2.210 | 2.042 | 2.021 | 2.045 | 2.172 | 2.207 | 2.116 | E7 | 4.22 |

Signal #2

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1) | S | Tetrachloro-m-xylen | 1.128 | 1.110 | 1.079 | 1.091 | 1.135 | 1.140 | 1.114 | E7 | 2.23 |
| 2) | | AR1221-A | | | | 6.822 | | | 6.822 | E4 | 0.00 |
| 3) | | AR1221-B | | | | 1.062 | | | 1.062 | E5 | 0.00 |
| 4) | | AR1221-C | | | | 2.651 | | | 2.651 | E5 | 0.00 |
| 5) | | AR1221-D | | | | 4.644 | | | 4.644 | E4 | 0.00 |
| 6) | | AR1221-E | | | | 3.177 | | | 3.177 | E4 | 0.00 |
| 7) | | AR1232-A | | | | 2.316 | | | 2.316 | E5 | 0.00 |
| 8) | | AR1232-B | | | | 1.805 | | | 1.805 | E5 | 0.00 |
| 9) | | AR1232-C | | | | 3.961 | | | 3.961 | E5 | 0.00 |
| 10) | | AR1232-D | | | | 1.639 | | | 1.639 | E5 | 0.00 |
| 11) | | AR1232-E | | | | 1.060 | | | 1.060 | E5 | 0.00 |
| 12) | | AR1242-A | | | | 3.008 | | | 3.008 | E5 | 0.00 |
| 13) | | AR1242-B | | | | 6.931 | | | 6.931 | E5 | 0.00 |
| 14) | | AR1242-C | | | | 2.823 | | | 2.823 | E5 | 0.00 |
| 15) | | AR1242-D | | | | 2.038 | | | 2.038 | E5 | 0.00 |
| 16) | | AR1242-E | | | | 2.702 | | | 2.702 | E5 | 0.00 |
| 17) | | AR1248-A | | | | 1.625 | | | 1.625 | E5 | 0.00 |
| 18) | | AR1248-B | | | | 4.502 | | | 4.502 | E5 | 0.00 |
| 19) | | AR1248-C | | | | 2.464 | | | 2.464 | E5 | 0.00 |
| 20) | | AR1248-D | | | | 3.274 | | | 3.274 | E5 | 0.00 |
| 21) | | AR1248-E | | | | 3.733 | | | 3.733 | E5 | 0.00 |
| 22) | | AR1248-F | | | | 4.670 | | | 4.670 | E5 | 0.00 |
| 23) | | AR1248-G | | | | 4.244 | | | 4.244 | E5 | 0.00 |
| 24) | | AR1254-A | | | | 4.180 | | | 4.180 | E5 | 0.00 |
| 25) | | AR1254-B | | | | 4.656 | | | 4.656 | E5 | 0.00 |
| 26) | | AR1254-C | | | | 3.763 | | | 3.763 | E5 | 0.00 |
| 27) | | AR1254-D | | | | 7.706 | | | 7.706 | E5 | 0.00 |
| 28) | | AR1254-E | | | | 6.092 | | | 6.092 | E5 | 0.00 |
| 29) | | AR1254-F | | | | 5.994 | | | 5.994 | E5 | 0.00 |
| 30) | | AR1254-G | | | | 7.662 | | | 7.662 | E5 | 0.00 |
| 31) | | AR1262-A | | | | 6.132 | | | 6.132 | E5 | 0.00 |
| 32) | | AR1262-B | | | | 9.701 | | | 9.701 | E5 | 0.00 |
| 33) | | AR1262-C | | | | 7.277 | | | 7.277 | E5 | 0.00 |
| 34) | | AR1262-D | | | | 1.758 | | | 1.758 | E6 | 0.00 |
| 35) | | AR1262-E | | | | 1.086 | | | 1.086 | E6 | 0.00 |
| 36) | | AR1268-A | | | | 1.945 | | | 1.945 | E6 | 0.00 |
| 37) | | AR1268-B | | | | 1.836 | | | 1.836 | E6 | 0.00 |
| 38) | | AR1268-C | | | | 1.532 | | | 1.532 | E6 | 0.00 |
| 39) | | AR1268-D | | | | 5.904 | | | 5.904 | E5 | 0.00 |
| 40) | | AR1268-E | | | | 4.342 | | | 4.342 | E6 | 0.00 |
| 41) | | AR1016-A | 2.072 | 1.910 | 1.882 | 1.840 | 1.783 | 1.752 | 1.873 | E5 | 6.08 |
| 42) | | AR1016-B | 4.302 | 3.944 | 3.854 | 3.780 | 3.684 | 3.610 | 3.862 | E5 | 6.36 |
| 43) | | AR1016-C | 9.420 | 8.519 | 8.405 | 8.365 | 8.296 | 8.236 | 8.540 | E5 | 5.17 |
| 44) | | AR1016-D | 3.921 | 3.517 | 3.436 | 3.385 | 3.329 | 3.287 | 3.479 | E5 | 6.65 |
| 45) | | AR1016-E | 2.583 | 2.499 | 2.459 | 2.448 | 2.425 | 2.408 | 2.470 | E5 | 2.57 |
| 46) | | AR1260-A | 7.668 | 7.183 | 7.169 | 7.273 | 7.412 | 7.413 | 7.353 | E5 | 2.55 |
| 47) | | AR1260-B | 5.820 | 5.453 | 5.418 | 5.444 | 5.530 | 5.532 | 5.533 | E5 | 2.68 |
| 48) | | AR1260-C | 5.335 | 5.148 | 5.128 | 5.203 | 5.290 | 5.314 | 5.236 | E5 | 1.70 |
| 49) | | AR1260-D | 1.278 | 1.269 | 1.285 | 1.319 | 1.347 | 1.345 | 1.307 | E6 | 2.63 |
| 50) | | AR1260-E | 8.062 | 7.668 | 7.717 | 7.922 | 8.158 | 8.253 | 7.963 | E5 | 2.98 |
| 51) | S | Decachlorobiphenyl | 1.157 | 0.926 | 0.908 | 0.928 | 0.979 | 0.993 | 0.982 | E7 | 9.37 |

(#) = Out of Range

8.10.26

8

# Initial Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5786-ICC5786
**Lab FileID:** XX195648.D

PCB5786.M Wed Aug 24 14:58:55 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5786-ICV5786
**Lab FileID:** XX195655.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\gx...6\xx195655.D\ECD1A.CH Vial: 36
Signal #2 : C:\msdchem\1\DATA\gxx5786\xx195655.D\ECD2B.CH
Acq On : 24 Aug 2016 1:09 pm Operator: josephr
Sample : icv5786-1000 Inst : HP G1530A
Misc : op96505,GXX5786,1.0,,,10,1 Multiplr: 1.00
IntFile Signal #1: events.e IntFile Signal #2: events2.e

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Wed Aug 24 14:53:46 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 150%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | S | Tetrachloro-m-xylene | 21.385 | 23.677 E6 | -10.7 | 113 | 0.00 | 2.77- 2.83 |
| 41 | | AR1016-A | 391.249 | 390.290 E3 | 0.2 | 101 | 0.00 | 3.15- 3.21 |
| 42 | | AR1016-B | 711.705 | 759.388 E3 | -6.7 | 108 | 0.00 | 3.55- 3.61 |
| 43 | | AR1016-C | 1.680 | 1.799 E6 | -7.1 | 108 | 0.00 | 4.11- 4.17 |
| 44 | | AR1016-D | 612.273 | 656.654 E3 | -7.2 | 108 | 0.00 | 4.28- 4.34 |
| 45 | | AR1016-E | 648.408 | 682.502 E3 | -5.3 | 106 | 0.00 | 4.78- 4.85 |
| 46 | | AR1260-A | 2.105 | 2.106 E6 | -0.0 | 102 | 0.00 | 7.16- 7.22 |
| 47 | | AR1260-B | 993.962 | 1089.537 E3 | -9.6 | 113 | 0.00 | 7.31- 7.37 |
| 48 | | AR1260-C | 909.103 | 992.104 E3 | -9.1 | 112 | 0.00 | 7.64- 7.71 |
| 49 | | AR1260-D | 2.880 | 3.233 E6 | -12.3 | 113 | 0.00 | 8.09- 8.15 |
| 50 | | AR1260-E | 1.731 | 1.854 E6 | -7.1 | 111 | 0.00 | 8.48- 8.54 |
| 51 | S | Decachlorobiphenyl | 21.162 | 22.259 E6 | -5.2 | 109 | 0.00 | 10.01-10.08 |
| ***** | | Signal #2 ***** | | | | | | |
| 1 | S | Tetrachloro-m-xylene | 11.139 | 12.232 E6 | -9.8 | 112 | 0.00 | 3.32- 3.38 |
| 41 | | AR1016-A | 187.295 | 188.889 E3 | -0.9 | 103 | 0.00 | 3.96- 4.02 |
| 42 | | AR1016-B | 386.236 | 406.162 E3 | -5.2 | 107 | 0.00 | 4.51- 4.57 |
| 43 | | AR1016-C | 854.000 | 898.775 E3 | -5.2 | 107 | 0.00 | 5.14- 5.20 |
| 44 | | AR1016-D | 347.914 | 364.222 E3 | -4.7 | 108 | 0.00 | 5.33- 5.39 |
| 45 | | AR1016-E | 247.019 | 256.690 E3 | -3.9 | 105 | 0.00 | 5.98- 6.04 |
| 46 | | AR1260-A | 735.326 | 696.493 E3 | 5.3 | 96 | 0.00 | 8.59- 8.65 |
| 47 | | AR1260-B | 553.265 | 586.990 E3 | -6.1 | 108 | 0.00 | 8.71- 8.77 |
| 48 | | AR1260-C | 523.633 | 555.791 E3 | -6.1 | 107 | 0.00 | 9.14- 9.20 |
| 49 | | AR1260-D | 1.307 | 1.422 E6 | -8.8 | 108 | 0.00 | 9.49- 9.55 |
| 50 | | AR1260-E | 796.347 | 849.098 E3 | -6.6 | 107 | 0.00 | 10.04-10.10 |
| 51 | S | Decachlorobiphenyl | 9.819 | 9.755 E6 | 0.7 | 105 | 0.00 | 11.71-11.77 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195648.D PCB5786.M Wed Aug 24 15:09:08 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5786-ICV5786
**Lab FileID:** XX195656.D

Evaluate Continuing Calibration Report

```
Signal #1 : C:\msdchem\1\DATA\gx...6\xx195656.D\ECD1A.CH Vial: 37
Signal #2 : C:\msdchem\1\DATA\gxx5786\xx195656.D\ECD2B.CH
Acq On    : 24 Aug 2016   1:26 pm                    Operator: josephr
Sample    : icv5786-1000                             Inst    : HP G1530A
Misc      : op96505,GXX5786,1.0,,,10,1               Multiplr: 1.00
IntFile Signal #1: events.e     IntFile Signal #2: events2.e

Method       : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title        :
Last Update  : Wed Aug 24 14:53:46 2016
Response via : Multiple Level Calibration

Min. RRF     :   0.000  Min. Rel. Area :  50%  Max. R.T. Dev  0.10min
Max. RRF Dev :  20%     Max. Rel. Area : 150%
```

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 2 | AR1221-A | 115.968 | 122.306 E3 | -5.5 | 105 | 0.00 | 2.19- 2.39 |
| 3 | AR1221-B | 203.717 | 211.141 E3 | -3.6 | 104 | 0.00 | 2.87- 3.07 |
| 4 | AR1221-C | 615.572 | 630.515 E3 | -2.4 | 102 | 0.00 | 3.08- 3.28 |
| 5 | AR1221-D | 52.818 | 55.527 E3 | -5.1 | 105 | 0.00 | 3.48- 3.68 |
| 6 | AR1221-E | 70.283 | 72.542 E3 | -3.2 | 103 | 0.00 | 3.71- 3.91 |
| 24 | AR1254-A | 737.712 | 730.099 E3 | 1.0 | 99 | 0.00 | 5.20- 5.40 |
| 25 | AR1254-B | 954.289 | 938.756 E3 | 1.6 | 98 | 0.00 | 5.55- 5.75 |
| 26 | AR1254-C | 759.766 | 754.251 E3 | 0.7 | 99 | 0.00 | 5.91- 6.11 |
| 27 | AR1254-D | 1.527 | 1.509 E6 | 1.2 | 99 | 0.00 | 6.08- 6.28 |
| 28 | AR1254-E | 1.202 | 1.186 E6 | 1.3 | 99 | 0.00 | 6.46- 6.66 |
| 29 | AR1254-F | 1.077 | 1.068 E6 | 0.8 | 99 | 0.00 | 6.70- 6.90 |
| 30 | AR1254-G | 1.505 | 1.497 E6 | 0.5 | 99 | 0.00 | 7.09- 7.29 |
| ***** | Signal #2 ***** | | | | | | |
| 2 | AR1221-A | 68.215 | 72.659 E3 | -6.5 | 107 | 0.00 | 2.76- 2.82 |
| 3 | AR1221-B | 106.191 | 111.372 E3 | -4.9 | 105 | 0.00 | 3.62- 3.82 |
| 4 | AR1221-C | 265.081 | 274.045 E3 | -3.4 | 103 | 0.00 | 3.89- 4.09 |
| 5 | AR1221-D | 46.442 | 49.690 E3 | -7.0 | 107 | 0.00 | 4.43- 4.63 |
| 6 | AR1221-E | 31.767 | 34.461 E3 | -8.5 | 108 | 0.00 | 4.52- 4.72 |
| 24 | AR1254-A | 417.978 | 416.167 E3 | 0.4 | 100 | 0.00 | 6.51- 6.71 |
| 25 | AR1254-B | 465.593 | 461.935 E3 | 0.8 | 99 | 0.00 | 6.77- 6.97 |
| 26 | AR1254-C | 376.295 | 372.595 E3 | 1.0 | 99 | 0.00 | 7.27- 7.47 |
| 27 | AR1254-D | 770.648 | 765.276 E3 | 0.7 | 99 | 0.00 | 7.43- 7.63 |
| 28 | AR1254-E | 609.235 | 605.768 E3 | 0.6 | 99 | 0.00 | 7.75- 7.95 |
| 29 | AR1254-F | 599.395 | 597.515 E3 | 0.3 | 100 | 0.00 | 8.26- 8.46 |
| 30 | AR1254-G | 766.235 | 763.102 E3 | 0.4 | 100 | 0.00 | 8.52- 8.72 |

```
   (#) = Out of Range              SPCC's out = 0  CCC's out = 0
    xx195648.D PCB5786.M       Wed Aug 24 15:09:09 2016
```

8.10.28

8

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5786-ICV5786
**Lab FileID:** XX195657.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\gx...6\xx195657.D\ECD1A.CH Vial: 38
Signal #2 : C:\msdchem\1\DATA\gxx5786\xx195657.D\ECD2B.CH
Acq On : 24 Aug 2016 1:43 pm Operator: josephr
Sample : icv5786-1000 Inst : HP G1530A
Misc : op96505,GXX5786,1.0,,,10,1 Multiplr: 1.00
IntFile Signal #1: events.e IntFile Signal #2: events2.e

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Wed Aug 24 14:53:46 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 150%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 7 | AR1232-A | 513.144 | 494.661 E3 | 3.6 | 96 | 0.00 | 3.08- 3.28 |
| 8 | AR1232-B | 349.540 | 345.951 E3 | 1.0 | 99 | 0.00 | 3.48- 3.68 |
| 9 | AR1232-C | 778.245 | 763.396 E3 | 1.9 | 98 | 0.00 | 4.04- 4.24 |
| 10 | AR1232-D | 285.104 | 281.104 E3 | 1.4 | 99 | 0.00 | 4.20- 4.40 |
| 11 | AR1232-E | 274.868 | 271.148 E3 | 1.4 | 99 | 0.00 | 4.71- 4.91 |
| 31 | AR1262-A | 1.107 | 1.099 E6 | 0.7 | 99 | 0.00 | 6.70- 6.90 |
| 32 | AR1262-B | 1.792 | 1.799 E6 | -0.4 | 100 | 0.00 | 7.24- 7.44 |
| 33 | AR1262-C | 1.375 | 1.374 E6 | 0.1 | 100 | 0.00 | 7.58- 7.78 |
| 34 | AR1262-D | 4.043 | 4.071 E6 | -0.7 | 101 | 0.00 | 8.02- 8.22 |
| 35 | AR1262-E | 2.394 | 2.403 E6 | -0.4 | 100 | 0.00 | 8.45- 8.65 |
| ***** | Signal #2 ***** | | | | | | |
| 7 | AR1232-A | 231.586 | 229.081 E3 | 1.1 | 99 | 0.00 | 3.89- 4.09 |
| 8 | AR1232-B | 180.512 | 179.727 E3 | 0.4 | 100 | 0.00 | 4.44- 4.64 |
| 9 | AR1232-C | 396.146 | 391.833 E3 | 1.1 | 99 | 0.00 | 5.07- 5.27 |
| 10 | AR1232-D | 163.907 | 163.133 E3 | 0.5 | 100 | 0.00 | 5.26- 5.46 |
| 11 | AR1232-E | 106.029 | 107.017 E3 | -0.9 | 101 | 0.00 | 5.91- 6.11 |
| 31 | AR1262-A | 613.156 | 614.246 E3 | -0.2 | 100 | 0.00 | 7.99- 8.19 |
| 32 | AR1262-B | 970.145 | 971.357 E3 | -0.1 | 100 | 0.00 | 8.64- 8.84 |
| 33 | AR1262-C | 727.743 | 735.212 E3 | -1.0 | 101 | 0.00 | 9.07- 9.27 |
| 34 | AR1262-D | 1.758 | 1.773 E6 | -0.9 | 101 | 0.00 | 9.42- 9.62 |
| 35 | AR1262-E | 1.086 | 1.101 E6 | -1.4 | 101 | 0.00 | 9.94-10.14 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195648.D PCB5786.M Wed Aug 24 15:09:10 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5786-ICV5786
**Lab FileID:** XX195658.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\gx...6\xx195658.D\ECD1A.CH Vial: 39
Signal #2 : C:\msdchem\1\DATA\gxx5786\xx195658.D\ECD2B.CH
Acq On : 24 Aug 2016 2:00 pm Operator: josephr
Sample : icv5786-1000 Inst : HP G1530A
Misc : op96505,GXX5786,1.0,,,10,1 Multiplr: 1.00
IntFile Signal #1: events.e IntFile Signal #2: events2.e

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Wed Aug 24 14:53:46 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 150%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 12 | AR1242-A | 593.808 | 600.737 E3 | -1.2 | 101 | 0.00 | 3.48- 3.68 |
| 13 | AR1242-B | 1.384 | 1.396 E6 | -0.9 | 101 | 0.00 | 4.04- 4.24 |
| 14 | AR1242-C | 507.434 | 515.637 E3 | -1.6 | 102 | 0.00 | 4.20- 4.40 |
| 15 | AR1242-D | 550.341 | 548.099 E3 | 0.4 | 100 | 0.00 | 4.71- 4.91 |
| 16 | AR1242-E | 604.805 | 602.154 E3 | 0.4 | 100 | 0.00 | 5.30- 5.50 |
| 36 | AR1268-A | 3.924 | 3.952 E6 | -0.7 | 101 | 0.00 | 8.45- 8.65 |
| 37 | AR1268-B | 4.578 | 4.677 E6 | -2.2 | 102 | 0.00 | 8.51- 8.71 |
| 38 | AR1268-C | 3.485 | 3.493 E6 | -0.2 | 100 | 0.00 | 8.78- 8.98 |
| 39 | AR1268-D | 1.353 | 1.368 E6 | -1.1 | 101 | 0.00 | 9.28- 9.48 |
| 40 | AR1268-E | 9.700 | 9.948 E6 | -2.6 | 103 | 0.00 | 9.68- 9.88 |
| ***** | Signal #2 ***** | | | | | | |
| 12 | AR1242-A | 300.777 | 326.382 E3 | -8.5 | 109 | 0.00 | 4.44- 4.64 |
| 13 | AR1242-B | 693.144 | 706.392 E3 | -1.9 | 102 | 0.00 | 5.07- 5.27 |
| 14 | AR1242-C | 282.345 | 290.663 E3 | -2.9 | 103 | 0.00 | 5.26- 5.46 |
| 15 | AR1242-D | 203.794 | 206.947 E3 | -1.5 | 102 | 0.00 | 5.91- 6.11 |
| 16 | AR1242-E | 270.245 | 267.054 E3 | 1.2 | 99 | 0.00 | 6.51- 6.71 |
| 36 | AR1268-A | 1.945 | 1.971 E6 | -1.3 | 101 | 0.00 | 9.94-10.14 |
| 37 | AR1268-B | 1.836 | 1.891 E6 | -3.0 | 103 | 0.00 | 10.01-10.21 |
| 38 | AR1268-C | 1.532 | 1.549 E6 | -1.1 | 101 | 0.00 | 10.38-10.58 |
| 39 | AR1268-D | 590.372 | 609.602 E3 | -3.3 | 103 | 0.00 | 10.78-10.98 |
| 40 | AR1268-E | 4.342 | 4.391 E6 | -1.1 | 101 | 0.00 | 11.26-11.46 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195648.D PCB5786.M Wed Aug 24 15:09:11 2016

# Initial Calibration Verification



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5786-ICV5786
**Lab FileID:** XX195659.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\gx...6\xx195659.D\ECD1A.CH Vial: 40
Signal #2 : C:\msdchem\1\DATA\gxx5786\xx195659.D\ECD2B.CH
Acq On : 24 Aug 2016 2:17 pm Operator: josephr
Sample : icv5786-1000 Inst : HP G1530A
Misc : op96505,GXX5786,1.0,,,10,1 Multiplr: 1.00
IntFile Signal #1: events.e IntFile Signal #2: events2.e

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Wed Aug 24 14:53:46 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 150%

| | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|
| 17 | AR1248-A | 306.591 | 289.515 E3 | 5.6 | 94 | 0.00 | 3.48- 3.68 |
| 18 | AR1248-B | 924.124 | 929.102 E3 | -0.5 | 101 | 0.00 | 4.04- 4.24 |
| 19 | AR1248-C | 823.058 | 858.406 E3 | -4.3 | 104 | 0.00 | 4.45- 4.65 |
| 20 | AR1248-D | 849.812 | 887.777 E3 | -4.5 | 104 | 0.00 | 4.71- 4.91 |
| 21 | AR1248-E | 467.823 | 495.619 E3 | -5.9 | 106 | 0.00 | 4.82- 5.02 |
| 22 | AR1248-F | 940.893 | 1032.620 E3 | -9.7 | 110 | 0.00 | 5.30- 5.50 |
| 23 | AR1248-G | 1.025 | 1.104 E6 | -7.7 | 108 | 0.00 | 5.55- 5.75 |
| ***** | Signal #2 ***** | | | | | | |
| 17 | AR1248-A | 162.475 | 154.637 E3 | 4.8 | 95 | 0.00 | 4.44- 4.64 |
| 18 | AR1248-B | 450.220 | 452.940 E3 | -0.6 | 101 | 0.00 | 5.07- 5.27 |
| 19 | AR1248-C | 246.380 | 253.110 E3 | -2.7 | 103 | 0.00 | 5.53- 5.73 |
| 20 | AR1248-D | 327.428 | 340.601 E3 | -4.0 | 104 | 0.00 | 5.91- 6.11 |
| 21 | AR1248-E | 373.318 | 399.393 E3 | -7.0 | 107 | 0.00 | 6.09- 6.29 |
| 22 | AR1248-F | 466.998 | 506.339 E3 | -8.4 | 108 | 0.00 | 6.51- 6.71 |
| 23 | AR1248-G | 424.369 | 466.444 E3 | -9.9 | 110 | 0.00 | 6.84- 7.04 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195648.D PCB5786.M Wed Aug 24 15:09:12 2016

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5823-CC5786
**Lab FileID:** XX198038.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\gx...3\xx198038.D\ECD1A.CH Vial: 96
Signal #2 : C:\msdchem\1\DATA\gxx5823\xx198038.D\ECD2B.CH
Acq On : 06 Oct 2016 2:28 pm Operator: humarahb
Sample : cc5786-500 Inst : HP G1530A
Misc : op97555,GXX5823,1000,,,1,1 Multiplr: 1.00
IntFile Signal #1: events.e IntFile Signal #2: events2.e

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Fri Sep 23 11:13:15 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 150%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | S | Tetrachloro-m-xylene | 21.385 | 22.363 E6 | -4.6 | 108 | 0.00 | 2.77- 2.83 |
| 2 | | AR1221-A | | ----------NA---------- | | | | |
| 3 | | AR1221-B | | ----------NA---------- | | | | |
| 4 | | AR1221-C | | ----------NA---------- | | | | |
| 5 | | AR1221-D | | ----------NA---------- | | | | |
| 6 | | AR1221-E | | ----------NA---------- | | | | |
| 7 | | AR1232-A | | ----------NA---------- | | | | |
| 8 | | AR1232-B | | ----------NA---------- | | | | |
| 9 | | AR1232-C | | ----------NA---------- | | | | |
| 10 | | AR1232-D | | ----------NA---------- | | | | |
| 11 | | AR1232-E | | ----------NA---------- | | | | |
| 12 | | AR1242-A | | ----------NA---------- | | | | |
| 13 | | AR1242-B | | ----------NA---------- | | | | |
| 14 | | AR1242-C | | ----------NA---------- | | | | |
| 15 | | AR1242-D | | ----------NA---------- | | | | |
| 16 | | AR1242-E | | ----------NA---------- | | | | |
| 17 | | AR1248-A | | ----------NA---------- | | | | |
| 18 | | AR1248-B | | ----------NA---------- | | | | |
| 19 | | AR1248-C | | ----------NA---------- | | | | |
| 20 | | AR1248-D | | ----------NA---------- | | | | |
| 21 | | AR1248-E | | ----------NA---------- | | | | |
| 22 | | AR1248-F | | ----------NA---------- | | | | |
| 23 | | AR1248-G | | ----------NA---------- | | | | |
| 24 | | AR1254-A | | ----------NA---------- | | | | |
| 25 | | AR1254-B | | ----------NA---------- | | | | |
| 26 | | AR1254-C | | ----------NA---------- | | | | |
| 27 | | AR1254-D | | ----------NA---------- | | | | |
| 28 | | AR1254-E | | ----------NA---------- | | | | |
| 29 | | AR1254-F | | ----------NA---------- | | | | |
| 30 | | AR1254-G | | ----------NA---------- | | | | |
| 31 | | AR1262-A | | ----------NA---------- | | | | |
| 32 | | AR1262-B | | ----------NA---------- | | | | |
| 33 | | AR1262-C | | ----------NA---------- | | | | |
| 34 | | AR1262-D | | ----------NA---------- | | | | |
| 35 | | AR1262-E | | ----------NA---------- | | | | |
| 36 | | AR1268-A | | ----------NA---------- | | | | |
| 37 | | AR1268-B | | ----------NA---------- | | | | |
| 38 | | AR1268-C | | ----------NA---------- | | | | |
| 39 | | AR1268-D | | ----------NA---------- | | | | |
| 40 | | AR1268-E | | ----------NA---------- | | | | |
| 41 | | AR1016-A | 391.249 | 393.159 E3 | -0.5 | 100 | 0.00 | 3.16- 3.22 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** GXX5823-CC5786
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** XX198038.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 42 | | AR1016-B | 711.705 | 795.151 | E3 | -11.7 | 112 | 0.00 | 3.55- 3.61 |
| 43 | | AR1016-C | 1.680 | 1.533 | E6 | 8.8 | 92 | 0.00 | 4.12- 4.18 |
| 44 | | AR1016-D | 612.273 | 642.657 | E3 | -5.0 | 105 | 0.00 | 4.28- 4.34 |
| 45 | | AR1016-E | 648.408 | 682.878 | E3 | -5.3 | 106 | 0.00 | 4.77- 4.84 |
| 46 | | AR1260-A | 2.105 | 1.814 | E6 | 13.8 | 88 | 0.02 | 7.18- 7.24 |
| 47 | | AR1260-B | 993.962 | 1039.411 | E3 | -4.6 | 107 | 0.00 | 7.30- 7.36 |
| 48 | | AR1260-C | 909.103 | 785.499 | E3 | 13.6 | 88 | 0.00 | 7.64- 7.71 |
| 49 | | AR1260-D | 2.880 | 2.893 | E6 | -0.5 | 101 | 0.00 | 8.10- 8.16 |
| 50 | | AR1260-E | 1.731 | 1.191 | E6 | 31.2# | 71 | 0.00 | 8.52- 8.58 |
| 51 | S | Decachlorobiphenyl | 21.162 | 22.761 | E6 | -7.6 | 113 | 0.00 | 9.99-10.06 |

***** Signal #2 *****

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 | S | Tetrachloro-m-xylene | 11.139 | 10.958 | E6 | 1.6 | 102 | 0.00 | 3.31- 3.37 |
| 2 | | AR1221-A | ----------NA---------- | | | | | | |
| 3 | | AR1221-B | ----------NA---------- | | | | | | |
| 4 | | AR1221-C | ----------NA---------- | | | | | | |
| 5 | | AR1221-D | ----------NA---------- | | | | | | |
| 6 | | AR1221-E | ----------NA---------- | | | | | | |
| 7 | | AR1232-A | ----------NA---------- | | | | | | |
| 8 | | AR1232-B | ----------NA---------- | | | | | | |
| 9 | | AR1232-C | ----------NA---------- | | | | | | |
| 10 | | AR1232-D | ----------NA---------- | | | | | | |
| 11 | | AR1232-E | ----------NA---------- | | | | | | |
| 12 | | AR1242-A | ----------NA---------- | | | | | | |
| 13 | | AR1242-B | ----------NA---------- | | | | | | |
| 14 | | AR1242-C | ----------NA---------- | | | | | | |
| 15 | | AR1242-D | ----------NA---------- | | | | | | |
| 16 | | AR1242-E | ----------NA---------- | | | | | | |
| 17 | | AR1248-A | ----------NA---------- | | | | | | |
| 18 | | AR1248-B | ----------NA---------- | | | | | | |
| 19 | | AR1248-C | ----------NA---------- | | | | | | |
| 20 | | AR1248-D | ----------NA---------- | | | | | | |
| 21 | | AR1248-E | ----------NA---------- | | | | | | |
| 22 | | AR1248-F | ----------NA---------- | | | | | | |
| 23 | | AR1248-G | ----------NA---------- | | | | | | |
| 24 | | AR1254-A | ----------NA---------- | | | | | | |
| 25 | | AR1254-B | ----------NA---------- | | | | | | |
| 26 | | AR1254-C | ----------NA---------- | | | | | | |
| 27 | | AR1254-D | ----------NA---------- | | | | | | |
| 28 | | AR1254-E | ----------NA---------- | | | | | | |
| 29 | | AR1254-F | ----------NA---------- | | | | | | |
| 30 | | AR1254-G | ----------NA---------- | | | | | | |
| 31 | | AR1262-A | ----------NA---------- | | | | | | |
| 32 | | AR1262-B | ----------NA---------- | | | | | | |
| 33 | | AR1262-C | ----------NA---------- | | | | | | |
| 34 | | AR1262-D | ----------NA---------- | | | | | | |
| 35 | | AR1262-E | ----------NA---------- | | | | | | |
| 36 | | AR1268-A | ----------NA---------- | | | | | | |
| 37 | | AR1268-B | ----------NA---------- | | | | | | |
| 38 | | AR1268-C | ----------NA---------- | | | | | | |
| 39 | | AR1268-D | ----------NA---------- | | | | | | |
| 40 | | AR1268-E | ----------NA---------- | | | | | | |
| 41 | | AR1016-A | 187.295 | 202.178 | E3 | -7.9 | 107 | 0.00 | 3.95- 4.01 |
| 42 | | AR1016-B | 386.236 | 381.132 | E3 | 1.3 | 99 | 0.00 | 4.49- 4.55 |
| 43 | | AR1016-C | 854.000 | 782.272 | E3 | 8.4 | 93 | 0.00 | 5.13- 5.19 |
| 44 | | AR1016-D | 347.914 | 325.192 | E3 | 6.5 | 95 | 0.00 | 5.31- 5.37 |
| 45 | | AR1016-E | 247.019 | 224.798 | E3 | 9.0 | 91 | 0.00 | 5.97- 6.03 |
| 46 | | AR1260-A | 735.326 | 769.438 | E3 | -4.6 | 107 | 0.00 | 8.57- 8.63 |
| 47 | | AR1260-B | 553.265 | 547.083 | E3 | 1.1 | 101 | 0.00 | 8.69- 8.75 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** GXX5823-CC5786
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** XX198038.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 48 | | AR1260-C | 523.633 | 486.651 | E3 | 7.1 | 95 | 0.00 | 9.12- 9.18 |
| 49 | | AR1260-D | 1.307 | 1.285 | E6 | 1.7 | 100 | 0.00 | 9.48- 9.54 |
| 50 | | AR1260-E | 796.347 | 649.721 | E3 | 18.4 | 84 | 0.00 | 10.02-10.08 |
| 51 | S | Decachlorobiphenyl | 9.819 | 9.126 | E6 | 7.1 | 101 | -0.01 | 11.68-11.74 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195647.D PCB5786.M Thu Oct 06 15:47:59 2016

8.10.32
8

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5823-CC5786
**Lab FileID:** XX198044.D

Evaluate Continuing Calibration Report

Signal #1 : C:\msdchem\1\DATA\gx...3\xx198044.D\ECD1A.CH Vial: 3
Signal #2 : C:\msdchem\1\DATA\gxx5823\xx198044.D\ECD2B.CH
Acq On : 06 Oct 2016 4:24 pm Operator: humarahb
Sample : cc5786-1000 Inst : HP G1530A
Misc : op97535,GXX5823,16.4,,,10,1 Multiplr: 1.00
IntFile Signal #1: events.e IntFile Signal #2: events2.e

Method : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title :
Last Update : Fri Sep 23 11:13:15 2016
Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.10min
Max. RRF Dev : 20% Max. Rel. Area : 150%

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | S | Tetrachloro-m-xylene | 21.385 | 23.255 E6 | -8.7 | 111 | 0.00 | 2.77- 2.83 |
| 2 | | AR1221-A | | ----------NA---------- | | | | |
| 3 | | AR1221-B | | ----------NA---------- | | | | |
| 4 | | AR1221-C | | ----------NA---------- | | | | |
| 5 | | AR1221-D | | ----------NA---------- | | | | |
| 6 | | AR1221-E | | ----------NA---------- | | | | |
| 7 | | AR1232-A | | ----------NA---------- | | | | |
| 8 | | AR1232-B | | ----------NA---------- | | | | |
| 9 | | AR1232-C | | ----------NA---------- | | | | |
| 10 | | AR1232-D | | ----------NA---------- | | | | |
| 11 | | AR1232-E | | ----------NA---------- | | | | |
| 12 | | AR1242-A | | ----------NA---------- | | | | |
| 13 | | AR1242-B | | ----------NA---------- | | | | |
| 14 | | AR1242-C | | ----------NA---------- | | | | |
| 15 | | AR1242-D | | ----------NA---------- | | | | |
| 16 | | AR1242-E | | ----------NA---------- | | | | |
| 17 | | AR1248-A | | ----------NA---------- | | | | |
| 18 | | AR1248-B | | ----------NA---------- | | | | |
| 19 | | AR1248-C | | ----------NA---------- | | | | |
| 20 | | AR1248-D | | ----------NA---------- | | | | |
| 21 | | AR1248-E | | ----------NA---------- | | | | |
| 22 | | AR1248-F | | ----------NA---------- | | | | |
| 23 | | AR1248-G | | ----------NA---------- | | | | |
| 24 | | AR1254-A | | ----------NA---------- | | | | |
| 25 | | AR1254-B | | ----------NA---------- | | | | |
| 26 | | AR1254-C | | ----------NA---------- | | | | |
| 27 | | AR1254-D | | ----------NA---------- | | | | |
| 28 | | AR1254-E | | ----------NA---------- | | | | |
| 29 | | AR1254-F | | ----------NA---------- | | | | |
| 30 | | AR1254-G | | ----------NA---------- | | | | |
| 31 | | AR1262-A | | ----------NA---------- | | | | |
| 32 | | AR1262-B | | ----------NA---------- | | | | |
| 33 | | AR1262-C | | ----------NA---------- | | | | |
| 34 | | AR1262-D | | ----------NA---------- | | | | |
| 35 | | AR1262-E | | ----------NA---------- | | | | |
| 36 | | AR1268-A | | ----------NA---------- | | | | |
| 37 | | AR1268-B | | ----------NA---------- | | | | |
| 38 | | AR1268-C | | ----------NA---------- | | | | |
| 39 | | AR1268-D | | ----------NA---------- | | | | |
| 40 | | AR1268-E | | ----------NA---------- | | | | |
| 41 | | AR1016-A | 391.249 | 397.901 E3 | -1.7 | 103 | 0.00 | 3.16- 3.22 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** GXX5823-CC5786
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** XX198044.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 42 | | AR1016-B | 711.705 | 764.392 | E3 | -7.4 | 109 | 0.00 | 3.55- 3.61 |
| 43 | | AR1016-C | 1.680 | 1.568 | E6 | 6.7 | 94 | 0.00 | 4.12- 4.18 |
| 44 | | AR1016-D | 612.273 | 657.374 | E3 | -7.4 | 108 | 0.00 | 4.28- 4.34 |
| 45 | | AR1016-E | 648.408 | 706.503 | E3 | -9.0 | 109 | 0.00 | 4.77- 4.84 |
| 46 | | AR1260-A | 2.105 | 1.935 | E6 | 8.1 | 94 | 0.02 | 7.18- 7.24 |
| 47 | | AR1260-B | 993.962 | 1096.388 | E3 | -10.3 | 113 | 0.00 | 7.30- 7.36 |
| 48 | | AR1260-C | 909.103 | 837.828 | E3 | 7.8 | 95 | 0.00 | 7.64- 7.71 |
| 49 | | AR1260-D | 2.880 | 3.149 | E6 | -9.3 | 110 | 0.00 | 8.10- 8.16 |
| 50 | | AR1260-E | 1.731 | 1.287 | E6 | 25.6# | 77 | 0.00 | 8.52- 8.58 |
| 51 | S | Decachlorobiphenyl | 21.162 | 24.923 | E6 | -17.8 | 122 | 0.00 | 9.99-10.06 |
| ***** | | Signal #2 ***** | | | | | | | |
| 1 | S | Tetrachloro-m-xylene | 11.139 | 11.118 | E6 | 0.2 | 102 | 0.00 | 3.31- 3.37 |
| 2 | | AR1221-A | ----------NA---------- | | | | | | |
| 3 | | AR1221-B | ----------NA---------- | | | | | | |
| 4 | | AR1221-C | ----------NA---------- | | | | | | |
| 5 | | AR1221-D | ----------NA---------- | | | | | | |
| 6 | | AR1221-E | ----------NA---------- | | | | | | |
| 7 | | AR1232-A | ----------NA---------- | | | | | | |
| 8 | | AR1232-B | ----------NA---------- | | | | | | |
| 9 | | AR1232-C | ----------NA---------- | | | | | | |
| 10 | | AR1232-D | ----------NA---------- | | | | | | |
| 11 | | AR1232-E | ----------NA---------- | | | | | | |
| 12 | | AR1242-A | ----------NA---------- | | | | | | |
| 13 | | AR1242-B | ----------NA---------- | | | | | | |
| 14 | | AR1242-C | ----------NA---------- | | | | | | |
| 15 | | AR1242-D | ----------NA---------- | | | | | | |
| 16 | | AR1242-E | ----------NA---------- | | | | | | |
| 17 | | AR1248-A | ----------NA---------- | | | | | | |
| 18 | | AR1248-B | ----------NA---------- | | | | | | |
| 19 | | AR1248-C | ----------NA---------- | | | | | | |
| 20 | | AR1248-D | ----------NA---------- | | | | | | |
| 21 | | AR1248-E | ----------NA---------- | | | | | | |
| 22 | | AR1248-F | ----------NA---------- | | | | | | |
| 23 | | AR1248-G | ----------NA---------- | | | | | | |
| 24 | | AR1254-A | ----------NA---------- | | | | | | |
| 25 | | AR1254-B | ----------NA---------- | | | | | | |
| 26 | | AR1254-C | ----------NA---------- | | | | | | |
| 27 | | AR1254-D | ----------NA---------- | | | | | | |
| 28 | | AR1254-E | ----------NA---------- | | | | | | |
| 29 | | AR1254-F | ----------NA---------- | | | | | | |
| 30 | | AR1254-G | ----------NA---------- | | | | | | |
| 31 | | AR1262-A | ----------NA---------- | | | | | | |
| 32 | | AR1262-B | ----------NA---------- | | | | | | |
| 33 | | AR1262-C | ----------NA---------- | | | | | | |
| 34 | | AR1262-D | ----------NA---------- | | | | | | |
| 35 | | AR1262-E | ----------NA---------- | | | | | | |
| 36 | | AR1268-A | ----------NA---------- | | | | | | |
| 37 | | AR1268-B | ----------NA---------- | | | | | | |
| 38 | | AR1268-C | ----------NA---------- | | | | | | |
| 39 | | AR1268-D | ----------NA---------- | | | | | | |
| 40 | | AR1268-E | ----------NA---------- | | | | | | |
| 41 | | AR1016-A | 187.295 | 184.918 | E3 | 1.3 | 101 | 0.00 | 3.95- 4.01 |
| 42 | | AR1016-B | 386.236 | 378.236 | E3 | 2.1 | 100 | 0.00 | 4.50- 4.56 |
| 43 | | AR1016-C | 854.000 | 810.371 | E3 | 5.1 | 97 | 0.00 | 5.13- 5.19 |
| 44 | | AR1016-D | 347.914 | 352.170 | E3 | -1.2 | 104 | 0.00 | 5.31- 5.37 |
| 45 | | AR1016-E | 247.019 | 233.262 | E3 | 5.6 | 95 | 0.00 | 5.96- 6.02 |
| 46 | | AR1260-A | 735.326 | 768.363 | E3 | -4.5 | 106 | 0.00 | 8.57- 8.63 |
| 47 | | AR1260-B | 553.265 | 559.232 | E3 | -1.1 | 103 | 0.00 | 8.69- 8.75 |

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5823-CC5786
**Lab FileID:** XX198044.D

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 48 | | AR1260-C | 523.633 | 506.163 | E3 | 3.3 | 97 | 0.00 | 9.12- 9.18 |
| 49 | | AR1260-D | 1.307 | 1.346 | E6 | -3.0 | 102 | 0.00 | 9.48- 9.54 |
| 50 | | AR1260-E | 796.347 | 657.733 | E3 | 17.4 | 83 | 0.00 | 10.02-10.08 |
| 51 | S | Decachlorobiphenyl | 9.819 | 9.429 | E6 | 4.0 | 102 | -0.01 | 11.68-11.74 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195648.D PCB5786.M Thu Oct 06 16:45:52 2016

8.10.33
8

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** GXX5823-CC5786
**Lab FileID:** XX198055.D

Evaluate Continuing Calibration Report

```
Signal #1 : C:\msdchem\1\DATA\gx...3\xx198055.D\ECD1A.CH Vial: 10
Signal #2 : C:\msdchem\1\DATA\gxx5823\xx198055.D\ECD2B.CH
Acq On    : 06 Oct 2016   7:37 pm                    Operator: humarahb
Sample    : cc5786-500                               Inst    : HP G1530A
Misc      : op97535,GXX5823,16.4,,,10,1              Multiplr: 1.00
IntFile Signal #1: events.e     IntFile Signal #2: events2.e

Method       : C:\MSDCHEM\1\METHODS\PCB5786.M (Chemstation Integrator)
Title        :
Last Update  : Fri Sep 23 11:13:15 2016
Response via : Multiple Level Calibration

Min. RRF     :   0.000  Min. Rel. Area :  50%  Max. R.T. Dev  0.10min
Max. RRF Dev :  20%     Max. Rel. Area : 150%
```

| | | Compound | AvgRF | CCRF | %Dev | Area% | Dev(min) | RT Window |
|---|---|---|---|---|---|---|---|---|
| 1 | S | Tetrachloro-m-xylene | 21.385 | 23.354 E6 | -9.2 | 112 | 0.00 | 2.77- 2.83 |
| 2 | | AR1221-A | | ----------NA---------- | | | | |
| 3 | | AR1221-B | | ----------NA---------- | | | | |
| 4 | | AR1221-C | | ----------NA---------- | | | | |
| 5 | | AR1221-D | | ----------NA---------- | | | | |
| 6 | | AR1221-E | | ----------NA---------- | | | | |
| 7 | | AR1232-A | | ----------NA---------- | | | | |
| 8 | | AR1232-B | | ----------NA---------- | | | | |
| 9 | | AR1232-C | | ----------NA---------- | | | | |
| 10 | | AR1232-D | | ----------NA---------- | | | | |
| 11 | | AR1232-E | | ----------NA---------- | | | | |
| 12 | | AR1242-A | | ----------NA---------- | | | | |
| 13 | | AR1242-B | | ----------NA---------- | | | | |
| 14 | | AR1242-C | | ----------NA---------- | | | | |
| 15 | | AR1242-D | | ----------NA---------- | | | | |
| 16 | | AR1242-E | | ----------NA---------- | | | | |
| 17 | | AR1248-A | | ----------NA---------- | | | | |
| 18 | | AR1248-B | | ----------NA---------- | | | | |
| 19 | | AR1248-C | | ----------NA---------- | | | | |
| 20 | | AR1248-D | | ----------NA---------- | | | | |
| 21 | | AR1248-E | | ----------NA---------- | | | | |
| 22 | | AR1248-F | | ----------NA---------- | | | | |
| 23 | | AR1248-G | | ----------NA---------- | | | | |
| 24 | | AR1254-A | | ----------NA---------- | | | | |
| 25 | | AR1254-B | | ----------NA---------- | | | | |
| 26 | | AR1254-C | | ----------NA---------- | | | | |
| 27 | | AR1254-D | | ----------NA---------- | | | | |
| 28 | | AR1254-E | | ----------NA---------- | | | | |
| 29 | | AR1254-F | | ----------NA---------- | | | | |
| 30 | | AR1254-G | | ----------NA---------- | | | | |
| 31 | | AR1262-A | | ----------NA---------- | | | | |
| 32 | | AR1262-B | | ----------NA---------- | | | | |
| 33 | | AR1262-C | | ----------NA---------- | | | | |
| 34 | | AR1262-D | | ----------NA---------- | | | | |
| 35 | | AR1262-E | | ----------NA---------- | | | | |
| 36 | | AR1268-A | | ----------NA---------- | | | | |
| 37 | | AR1268-B | | ----------NA---------- | | | | |
| 38 | | AR1268-C | | ----------NA---------- | | | | |
| 39 | | AR1268-D | | ----------NA---------- | | | | |
| 40 | | AR1268-E | | ----------NA---------- | | | | |
| 41 | | AR1016-A | 391.249 | 421.343 E3 | -7.7 | 107 | 0.00 | 3.16- 3.22 |

# Continuing Calibration Summary



**Job Number:** JC28902 **Sample:** GXX5823-CC5786
**Account:** HWINJM Honeywell International Inc. **Lab FileID:** XX198055.D
**Project:** HLANJPR: Study Area 6 Chrome Remedy

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 42 | | AR1016-B | 711.705 | 775.225 | E3 | -8.9 | 109 | 0.00 | 3.55- 3.61 |
| 43 | | AR1016-C | 1.680 | 1.674 | E6 | 0.4 | 101 | 0.00 | 4.12- 4.18 |
| 44 | | AR1016-D | 612.273 | 655.047 | E3 | -7.0 | 107 | 0.00 | 4.28- 4.34 |
| 45 | | AR1016-E | 648.408 | 688.110 | E3 | -6.1 | 107 | 0.00 | 4.77- 4.84 |
| 46 | | AR1260-A | 2.105 | 1.940 | E6 | 7.8 | 94 | 0.00 | 7.17- 7.23 |
| 47 | | AR1260-B | 993.962 | 976.032 | E3 | 1.8 | 100 | 0.00 | 7.30- 7.36 |
| 48 | | AR1260-C | 909.103 | 796.438 | E3 | 12.4 | 90 | 0.00 | 7.64- 7.71 |
| 49 | | AR1260-D | 2.880 | 2.713 | E6 | 5.8 | 95 | 0.00 | 8.09- 8.15 |
| 50 | | AR1260-E | 1.731 | 1.254 | E6 | 27.6# | 75 | 0.00 | 8.51- 8.57 |
| 51 | S | Decachlorobiphenyl | 21.162 | 19.692 | E6 | 6.9 | 97 | 0.00 | 10.00-10.07 |
| ***** | | Signal #2 ***** | | | | | | | |
| 1 | S | Tetrachloro-m-xylene | 11.139 | 11.156 | E6 | -0.2 | 103 | 0.00 | 3.31- 3.37 |
| 2 | | AR1221-A | ----------NA---------- | | | | | | |
| 3 | | AR1221-B | ----------NA---------- | | | | | | |
| 4 | | AR1221-C | ----------NA---------- | | | | | | |
| 5 | | AR1221-D | ----------NA---------- | | | | | | |
| 6 | | AR1221-E | ----------NA---------- | | | | | | |
| 7 | | AR1232-A | ----------NA---------- | | | | | | |
| 8 | | AR1232-B | ----------NA---------- | | | | | | |
| 9 | | AR1232-C | ----------NA---------- | | | | | | |
| 10 | | AR1232-D | ----------NA---------- | | | | | | |
| 11 | | AR1232-E | ----------NA---------- | | | | | | |
| 12 | | AR1242-A | ----------NA---------- | | | | | | |
| 13 | | AR1242-B | ----------NA---------- | | | | | | |
| 14 | | AR1242-C | ----------NA---------- | | | | | | |
| 15 | | AR1242-D | ----------NA---------- | | | | | | |
| 16 | | AR1242-E | ----------NA---------- | | | | | | |
| 17 | | AR1248-A | ----------NA---------- | | | | | | |
| 18 | | AR1248-B | ----------NA---------- | | | | | | |
| 19 | | AR1248-C | ----------NA---------- | | | | | | |
| 20 | | AR1248-D | ----------NA---------- | | | | | | |
| 21 | | AR1248-E | ----------NA---------- | | | | | | |
| 22 | | AR1248-F | ----------NA---------- | | | | | | |
| 23 | | AR1248-G | ----------NA---------- | | | | | | |
| 24 | | AR1254-A | ----------NA---------- | | | | | | |
| 25 | | AR1254-B | ----------NA---------- | | | | | | |
| 26 | | AR1254-C | ----------NA---------- | | | | | | |
| 27 | | AR1254-D | ----------NA---------- | | | | | | |
| 28 | | AR1254-E | ----------NA---------- | | | | | | |
| 29 | | AR1254-F | ----------NA---------- | | | | | | |
| 30 | | AR1254-G | ----------NA---------- | | | | | | |
| 31 | | AR1262-A | ----------NA---------- | | | | | | |
| 32 | | AR1262-B | ----------NA---------- | | | | | | |
| 33 | | AR1262-C | ----------NA---------- | | | | | | |
| 34 | | AR1262-D | ----------NA---------- | | | | | | |
| 35 | | AR1262-E | ----------NA---------- | | | | | | |
| 36 | | AR1268-A | ----------NA---------- | | | | | | |
| 37 | | AR1268-B | ----------NA---------- | | | | | | |
| 38 | | AR1268-C | ----------NA---------- | | | | | | |
| 39 | | AR1268-D | ----------NA---------- | | | | | | |
| 40 | | AR1268-E | ----------NA---------- | | | | | | |
| 41 | | AR1016-A | 187.295 | 189.093 | E3 | -1.0 | 100 | 0.00 | 3.95- 4.01 |
| 42 | | AR1016-B | 386.236 | 393.610 | E3 | -1.9 | 102 | 0.00 | 4.49- 4.55 |
| 43 | | AR1016-C | 854.000 | 802.521 | E3 | 6.0 | 95 | 0.00 | 5.13- 5.19 |
| 44 | | AR1016-D | 347.914 | 332.855 | E3 | 4.3 | 97 | 0.00 | 5.31- 5.37 |
| 45 | | AR1016-E | 247.019 | 232.324 | E3 | 5.9 | 94 | 0.00 | 5.96- 6.02 |
| 46 | | AR1260-A | 735.326 | 732.816 | E3 | 0.3 | 102 | 0.00 | 8.57- 8.63 |
| 47 | | AR1260-B | 553.265 | 523.349 | E3 | 5.4 | 97 | 0.00 | 8.69- 8.75 |

8.10.34
8

# Continuing Calibration Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy
**Sample:** GXX5823-CC5786
**Lab FileID:** XX198055.D

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 48 | | AR1260-C | 523.633 | 481.526 | E3 | 8.0 | 94 | 0.00 | 9.12- 9.18 |
| 49 | | AR1260-D | 1.307 | 1.173 | E6 | 10.3 | 91 | 0.00 | 9.47- 9.53 |
| 50 | | AR1260-E | 796.347 | 659.268 | E3 | 17.2 | 85 | 0.00 | 10.02-10.08 |
| 51 | S | Decachlorobiphenyl | 9.819 | 9.124 | E6 | 7.1 | 101 | -0.01 | 11.68-11.74 |

(#) = Out of Range SPCC's out = 0 CCC's out = 0
xx195647.D PCB5786.M Fri Oct 07 09:36:00 2016

SGS ACCUTEST New Jersey

Section 9

## Metals Analysis

### QC Data Summaries

Includes the following where applicable:

- Instrument Runlogs
- Initial and Continuing Calibration Blanks
- Initial and Continuing Calibration Checks
- High and Low Check Standards
- Interfering Element Check Standards
- Method Blank Summaries
- Matrix Spike and Duplicate Summaries
- Blank Spike and Lab Control Sample Summaries
- Serial Dilution Summaries
- IDL and Linear Range Summaries

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 20:15 | MA40457-STD1 | 1 | | STDA |
| 20:20 | MA40457-STD2 | 1 | | STDB |
| 20:26 | ZZZZZZ | 1 | | |
| 20:32 | ZZZZZZ | 1 | | |
| 20:38 | MA40457-ICV1 | 1 | | |
| 20:44 | MA40457-ICB1 | 1 | | |
| 20:50 | MA40457-CCV1 | 1 | | |
| 20:55 | MA40457-CCB1 | 1 | | |
| 21:01 | MA40457-CRI1 | 1 | | |
| 21:07 | MA40457-CRID1 | 1 | | |
| 21:13 | MA40457-ICSA1 | 1 | | |
| 21:19 | MA40457-ICSAB1 | 1 | | |
| 21:25 | MA40457-HSTD1 | 1 | | |
| 21:31 | MA40457-HSTD2 | 1 | | Minerals |
| 21:36 | ZZZZZZ | 1 | | |
| 21:42 | ZZZZZZ | 1 | | |
| 21:48 | ZZZZZZ | 1 | | |
| 21:54 | MA40457-CCV2 | 1 | | |
| 22:00 | MA40457-CCB2 | 1 | | |
| 22:06 | MA40457-CRIA1 | 1 | | |
| 22:12 | MP96352-MB2 | 1 | | |
| 22:18 | MP96352-B2 | 1 | | |
| 22:24 | ZZZZZZ | 1 | | |
| 22:30 | MP96373-MB1 | 1 | | Zn=3ppm |
| 22:35 | MP96373-B1 | 1 | | |
| 22:41 | MP96373-S1 | 1 | | |
| 22:47 | MP96373-S2 | 1 | | |
| 22:53 | JC28910-1 | 1 | | (sample used for QC only; not part of login JC28902) |
| 22:58 | MP96373-SD1 | 5 | | |
| 23:04 | MA40457-CCV3 | 1 | | |
| 23:10 | MA40457-CCB3 | 1 | | |
| 23:18 | MP96373-MB1 | 1 | | Confirmation |
| 23:24 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
Analyst: ND  Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 23:30 | JC28902-1 | 1 | | |
| ----------> | Last reportable sample/prep for job JC28902 | | | |
| 23:35 | ZZZZZZ | 1 | | |
| 23:41 | ZZZZZZ | 1 | | |
| 23:47 | MP96385-MB1 | 5 | | |
| 23:53 | MP96385-B1 | 5 | | |
| 23:59 | MP96385-S1 | 5 | | |
| 00:04 | MP96385-S2 | 5 | | |
| 00:10 | MA40457-CCV4 | 1 | | |
| 00:16 | MA40457-CCB4 | 1 | | |
| 00:22 | JC28768-1 | 5 | | (sample used for QC only; not part of login JC28902) |
| 00:28 | MP96385-SD1 | 25 | | |
| 00:33 | ZZZZZZ | 5 | | |
| 00:39 | ZZZZZZ | 5 | | |
| 00:45 | ZZZZZZ | 5 | | |
| 00:51 | MP96289-MB3 | 1 | | |
| 00:57 | MP96289-B3 | 1 | | |
| 01:03 | ZZZZZZ | 1 | | |
| 01:09 | ZZZZZZ | 1 | | |
| 01:14 | ZZZZZZ | 1 | | |
| 01:20 | MA40457-CCV5 | 1 | | |
| 01:26 | MA40457-CCB5 | 1 | | |
| 01:32 | ZZZZZZ | 1 | | |
| 01:38 | ZZZZZZ | 1 | | |
| 01:44 | MP96332-MB3 | 5 | | |
| 01:50 | MP96332-B3 | 5 | | |
| 01:55 | ZZZZZZ | 5 | | |
| 02:01 | ZZZZZZ | 1 | | |
| 02:07 | ZZZZZZ | 1 | | |
| 02:13 | ZZZZZZ | 1 | | |
| 02:19 | ZZZZZZ | 2 | | |
| 02:25 | MA40457-CCV6 | 1 | | |
| 02:30 | MA40457-CCB6 | 1 | | |
| 02:36 | ZZZZZZ | 2 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| | Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|---|
| | 02:42 | ZZZZZZ | 2 | | |
| | 02:48 | ZZZZZZ | 1 | | |
| | 02:54 | ZZZZZZ | 2 | | |
| | 03:00 | ZZZZZZ | 1 | | |
| | 03:05 | ZZZZZZ | 1 | | |
| | 03:11 | ZZZZZZ | 3 | | |
| | 03:17 | MA40457-CCV7 | 1 | | |
| | 03:23 | MA40457-CCB7 | 1 | | |
| | 03:29 | MA40457-CRI2 | 1 | | |
| | 03:35 | MA40457-CRID2 | 1 | | |
| | 03:41 | MA40457-CRIA2 | 1 | | |
| | 03:47 | MA40457-ICSA2 | 1 | | |
| | 03:53 | MA40457-ICSAB2 | 1 | | |
| | 03:58 | MA40457-CCV8 | 1 | | |
| | 04:04 | MA40457-CCB8 | 1 | | |
| ----------> | | Last reportable CCB for job JC28902 | | | |
| | 04:10 | ZZZZZZ | 1 | | |
| | 04:16 | ZZZZZZ | 1 | | |
| | 04:22 | ZZZZZZ | 1 | | |
| | 04:27 | ZZZZZZ | 2 | | |
| | 04:33 | ZZZZZZ | 1 | | |
| | 04:39 | ZZZZZZ | 1 | | |
| | 04:45 | ZZZZZZ | 5 | | |
| | 04:51 | ZZZZZZ | 10 | | |
| | 04:57 | ZZZZZZ | 3 | | |
| | 05:02 | ZZZZZZ | 2 | | |
| | 05:08 | MA40457-CCV9 | 1 | | |
| | 05:14 | MA40457-CCB9 | 1 | | |
| | 05:20 | ZZZZZZ | 2 | | |
| | 05:26 | ZZZZZZ | 1 | | |
| | 05:32 | ZZZZZZ | 1 | | |
| | 05:38 | ZZZZZZ | 1 | | |
| | 05:43 | ZZZZZZ | 1 | | |
| | 05:49 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 05:55 | ZZZZZZ | 1 | | |
| 06:01 | ZZZZZZ | 1 | | |
| 06:07 | ZZZZZZ | 1 | | |
| 06:12 | MA40457-CCV10 | 1 | | |
| 06:18 | MA40457-CCB10 | 1 | | |
| 06:24 | ZZZZZZ | 1 | | |
| 06:30 | ZZZZZZ | 1 | | |
| 06:36 | ZZZZZZ | 1 | | |
| 06:41 | ZZZZZZ | 1 | | |
| 06:47 | ZZZZZZ | 1 | | |
| 06:53 | ZZZZZZ | 1 | | |
| 06:59 | ZZZZZZ | 1 | | |
| 07:05 | MA40457-CCV11 | 1 | | |
| 07:11 | MA40457-CCB11 | 1 | | |
| 07:16 | MA40457-CRI3 | 1 | | |
| 07:22 | MA40457-CRID3 | 1 | | |
| 07:28 | MA40457-CRIA3 | 1 | | |
| 07:34 | MA40457-CCV12 | 1 | | |
| 07:40 | MA40457-CCB12 | 1 | | |
| 07:46 | ZZZZZZ | 1 | | |
| 07:52 | ZZZZZZ | 1 | | |
| 07:58 | ZZZZZZ | 1 | | |
| 08:04 | ZZZZZZ | 1 | | |
| 08:10 | ZZZZZZ | 1 | | |
| 08:16 | ZZZZZZ | 1 | | |
| 08:22 | ZZZZZZ | 1 | | |
| 08:28 | ZZZZZZ | 1 | | |
| 08:34 | ZZZZZZ | 1 | | |

Refer to raw data for calibration curve and standards.

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 20:15 | MA40457-STD1 | 2761 R | 80960 R | 3496 R | 6071 R |
| 20:20 | MA40457-STD2 | 2521 | 73433 | 3397 | 5149 |
| 20:26 | ZZZZZZ | 2598 | 75946 | 3405 | 5345 |
| 20:32 | ZZZZZZ | 2729 | 80633 | 3459 | 6016 |
| 20:38 | MA40457-ICV1 | 2579 | 75767 | 3412 | 5328 |
| 20:44 | MA40457-ICB1 | 2729 | 80849 | 3453 | 6030 |
| 20:50 | MA40457-CCV1 | 2610 | 76404 | 3418 | 5400 |
| 20:55 | MA40457-CCB1 | 2714 | 80520 | 3468 | 6036 |
| 21:01 | MA40457-CRI1 | 2693 | 79946 | 3436 | 5893 |
| 21:07 | MA40457-CRID1 | 2718 | 80967 | 3433 | 6009 |
| 21:13 | MA40457-ICSA1 | 2407 | 70185 | 3331 | 4817 |
| 21:19 | MA40457-ICSAB1 | 2392 | 70205 | 3310 | 4813 |
| 21:25 | MA40457-HSTD1 | 2665 | 79579 | 3415 | 5845 |
| 21:31 | MA40457-HSTD2 | 2421 | 71067 | 3274 | 4844 |
| 21:36 | ZZZZZZ | 2662 | 79604 | 3395 | 5984 |
| 21:42 | ZZZZZZ | 2629 | 78627 | 3405 | 6030 |
| 21:48 | ZZZZZZ | 2726 | 81765 | 3394 | 6107 |
| 21:54 | MA40457-CCV2 | 2594 | 76900 | 3326 | 5421 |
| 22:00 | MA40457-CCB2 | 2707 | 81328 | 3348 | 6081 |
| 22:06 | MA40457-CRIA1 | 2700 | 81073 | 3335 | 6035 |
| 22:12 | MP96352-MB2 | 2730 | 82170 | 3429 | 6139 |
| 22:18 | MP96352-B2 | 2596 | 77519 | 3300 | 5510 |
| 22:24 | ZZZZZZ | 2738 | 84029 | 3470 | 6189 |
| 22:30 | MP96373-MB1 | 2746 | 83522 | 3441 | 6205 |
| 22:35 | MP96373-B1 | 2631 | 79354 | 3334 | 5647 |
| 22:41 | MP96373-S1 | 2641 | 79506 | 3358 | 5636 |
| 22:47 | MP96373-S2 | 2646 | 79043 | 3365 | 5641 |
| 22:53 | JC28910-1 | 2740 | 82868 | 3371 | 6122 |
| 22:58 | MP96373-SD1 | 2720 | 82203 | 3377 | 6114 |
| 23:04 | MA40457-CCV3 | 2596 | 77543 | 3270 | 5458 |
| 23:10 | MA40457-CCB3 | 2715 | 82069 | 3365 | 6116 |
| 23:18 | MP96373-MB1 | No results reported for the elements associated with this internal standard. | | | |
| 23:24 | ZZZZZZ | 2720 | 83942 | 3387 | 6113 |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 23:30 | JC28902-1 | 2715 | 82557 | 3458 | 5891 |
| 23:35 | ZZZZZZ | 2629 | 79605 | 3425 | 5512 |
| 23:41 | ZZZZZZ | 2721 | 81422 | 3478 | 5628 |
| 23:47 | MP96385-MB1 | 2553 | 75779 | 3262 | 5353 |
| 23:53 | MP96385-B1 | 2562 | 76574 | 3313 | 5327 |
| 23:59 | MP96385-S1 | 2550 | 75390 | 3331 | 5211 |
| 00:04 | MP96385-S2 | 2558 | 75876 | 3292 | 5225 |
| 00:10 | MA40457-CCV4 | 2603 | 78004 | 3280 | 5518 |
| 00:16 | MA40457-CCB4 | 2714 | 80211 | 3288 | 6171 |
| 00:22 | JC28768-1 | 2543 | 75909 | 3309 | 5238 |
| 00:28 | MP96385-SD1 | 2632 | 80263 | 3287 | 5731 |
| 00:33 | ZZZZZZ | 2505 | 75673 | 3231 | 5140 |
| 00:39 | ZZZZZZ | 2524 | 75461 | 3254 | 5282 |
| 00:45 | ZZZZZZ | 2538 | 76864 | 3283 | 5350 |
| 00:51 | MP96289-MB3 | 2732 | 84315 | 3390 | 6242 |
| 00:57 | MP96289-B3 | 2636 | 80769 | 3314 | 5690 |
| 01:03 | ZZZZZZ | 2727 | 83603 | 3369 | 6075 |
| 01:09 | ZZZZZZ | 2738 | 83316 | 3387 | 6075 |
| 01:14 | ZZZZZZ | 2719 | 83265 | 3401 | 6001 |
| 01:20 | MA40457-CCV5 | 2620 | 79311 | 3350 | 5546 |
| 01:26 | MA40457-CCB5 | 2770 | 83780 | 3377 | 6260 |
| 01:32 | ZZZZZZ | 2760 | 83768 | 3424 | 6099 |
| 01:38 | ZZZZZZ | 2750 | 83795 | 3428 | 6059 |
| 01:44 | MP96332-MB3 | 2612 | 77585 | 3341 | 5465 |
| 01:50 | MP96332-B3 | 2614 | 78382 | 3349 | 5429 |
| 01:55 | ZZZZZZ | 2530 | 76360 | 3291 | 5241 |
| 02:01 | ZZZZZZ | 2727 | 82403 | 3413 | 5875 |
| 02:07 | ZZZZZZ | 2801 | 82695 | 3477 | 6367 |
| 02:13 | ZZZZZZ | 2755 | 80381 | 3536 | 5798 |
| 02:19 | ZZZZZZ | 2831 | 86035 | 3543 | 5985 |
| 02:25 | MA40457-CCV6 | 2685 | 79801 | 3401 | 5630 |
| 02:30 | MA40457-CCB6 | 2801 | 84843 | 3423 | 6321 |
| 02:36 | ZZZZZZ | 2791 | 83601 | 3518 | 5970 |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 02:42 | ZZZZZZ | 2764 | 83687 | 3488 | 5890 |
| 02:48 | ZZZZZZ | 2767 | 84223 | 3526 | 5884 |
| 02:54 | ZZZZZZ | 2777 | 84519 | 3450 | 6021 |
| 03:00 | ZZZZZZ | 2840 | 86138 | 3572 | 5859 |
| 03:05 | ZZZZZZ | 2766 | 83399 | 3462 | 5889 |
| 03:11 | ZZZZZZ | 2835 | 86601 | 3498 | 6072 |
| 03:17 | MA40457-CCV7 | 2644 | 80705 | 3285 | 5668 |
| 03:23 | MA40457-CCB7 | 2753 | 85630 | 3338 | 6341 |
| 03:29 | MA40457-CRI2 | 2709 | 84650 | 3277 | 6167 |
| 03:35 | MA40457-CRID2 | 2734 | 85756 | 3318 | 6304 |
| 03:41 | MA40457-CRIA2 | 2751 | 85570 | 3307 | 6355 |
| 03:47 | MA40457-ICSA2 | 2404 | 74040 | 3183 | 5016 |
| 03:53 | MA40457-ICSAB2 | 2411 | 74358 | 3183 | 5013 |
| 03:58 | MA40457-CCV8 | 2661 | 81124 | 3287 | 5738 |
| 04:04 | MA40457-CCB8 | 2751 | 83766 | 3312 | 6372 |
| 04:10 | ZZZZZZ | 2753 | 85993 | 3303 | 6390 |
| 04:16 | ZZZZZZ | 2657 | 82347 | 3281 | 5857 |
| 04:22 | ZZZZZZ | 2574 | 81289 | 3256 | 5310 |
| 04:27 | ZZZZZZ | 2699 | 84671 | 3348 | 6088 |
| 04:33 | ZZZZZZ | 2790 | 87098 | 3345 | 6432 |
| 04:39 | ZZZZZZ | 2665 | 83388 | 3316 | 5830 |
| 04:45 | ZZZZZZ | 2814 | 87384 | 3398 | 6221 |
| 04:51 | ZZZZZZ | 2819 | 86724 | 3384 | 6288 |
| 04:57 | ZZZZZZ | 2627 | 83105 | 3356 | 5878 |
| 05:02 | ZZZZZZ | 2825 | 86573 | 3464 | 6129 |
| 05:08 | MA40457-CCV9 | 2681 | 81461 | 3331 | 5708 |
| 05:14 | MA40457-CCB9 | 2818 | 86479 | 3369 | 6437 |
| 05:20 | ZZZZZZ | 2722 | 83733 | 3461 | 5986 |
| 05:26 | ZZZZZZ | 2769 | 84005 | 3369 | 5949 |
| 05:32 | ZZZZZZ | 2857 | 87989 | 3464 | 6485 |
| 05:38 | ZZZZZZ | No results reported for the elements associated with this internal standard. | | | |
| 05:43 | ZZZZZZ | 2846 | 87924 | 3457 | 6375 |
| 05:49 | ZZZZZZ | 999999 !a | 81960 | 3485 | 999999 !a |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP Date Analyzed: 10/05/16 Methods: SW846 6010B, SW846 6010C
Analyst: ND Run ID: MA40457
Parameters: Al,Sb,As,Ba,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Ni,K,Se,Ag,Na,Tl,V,Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 05:55 | ZZZZZZ | 2733 | 82946 | 3523 | 5635 |
| 06:01 | ZZZZZZ | 2909 | 87637 | 3538 | 6229 |
| 06:07 | ZZZZZZ | 2826 | 85520 | 3642 | 5943 |
| 06:12 | MA40457-CCV10 | 2764 | 82164 | 3404 | 5803 |
| 06:18 | MA40457-CCB10 | 2911 | 87176 | 3454 | 6555 |
| 06:24 | ZZZZZZ | 3017 | 89753 | 3675 | 6059 |
| 06:30 | ZZZZZZ | 3038 | 90724 | 3712 | 6052 |
| 06:36 | ZZZZZZ | 2996 | 89894 | 3782 | 5747 |
| 06:41 | ZZZZZZ | 2805 | 84846 | 3493 | 5888 |
| 06:47 | ZZZZZZ | 2903 | 87678 | 3587 | 6113 |
| 06:53 | ZZZZZZ | 2739 | 83237 | 3508 | 5845 |
| 06:59 | ZZZZZZ | 2690 | 84090 | 3545 | 5905 |
| 07:05 | MA40457-CCV11 | 2775 | 82871 | 3385 | 5826 |
| 07:11 | MA40457-CCB11 | 2880 | 87469 | 3429 | 6523 |
| 07:16 | MA40457-CRI3 | 2855 | 86343 | 3439 | 6353 |
| 07:22 | MA40457-CRID3 | 2901 | 87851 | 3441 | 6511 |
| 07:28 | MA40457-CRIA3 | 2879 | 87378 | 3426 | 6484 |
| 07:34 | MA40457-CCV12 | 2782 | 83154 | 3409 | 5834 |
| 07:40 | MA40457-CCB12 | 2896 | 88040 | 3460 | 6506 |
| 07:46 | ZZZZZZ | 2929 | 82735 | 3547 | 5825 |
| 07:52 | ZZZZZZ | 2909 | 87418 | 3486 | 6499 |
| 07:58 | ZZZZZZ | 2902 | 88003 | 3484 | 6481 |
| 08:04 | ZZZZZZ | 2934 | 88110 | 3505 | 6538 |
| 08:10 | ZZZZZZ | 2925 | 87615 | 3486 | 6518 |
| 08:16 | ZZZZZZ | 2906 | 88354 | 3514 | 6516 |
| 08:22 | ZZZZZZ | 2668 | 80455 | 3366 | 5593 |
| 08:28 | ZZZZZZ | 2683 | 79812 | 3401 | 5580 |
| 08:34 | ZZZZZZ | 2975 | 88454 | 3551 | 6608 |

R = Reference for ISTD limits. ! = Outside limits.

LEGEND:

| Istd# | Parameter | Limits |
|---|---|---|
| Istd#1 | Yttrium (2243) | 70-130 % |
| Istd#2 | Yttrium (3600) | 70-130 % |
| Istd#3 | Yttrium (3710) | 70-130 % |
| Istd#4 | Indium | 70-130 % |

(a) No samples reported for the elements associated with this internal standard.

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: result < RL  Run ID: MA40457  Units: ug/l

| Time: / Sample ID: | | | 20:44 ICB1 | | 20:55 CCB1 | | 22:00 CCB2 | | 23:10 CCB3 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Aluminum | 200 | 20 | 7.9 | <500 | 3.1 | <500 | -16 | <500 | -3.6 | <500 |
| Antimony | 20 | 1.2 | 0.70 | <20 | 0.50 | <20 | 0.30 | <20 | 0.0 | <20 |
| Arsenic | 20 | 1.5 | 1.0 | <20 | 1.7 | <20 | 0.80 | <20 | 1.8 | <20 |
| Barium | 200 | .5 | 0.20 | <200 | 0.60 | <200 | 0.50 | <200 | 0.60 | <200 |
| Beryllium | 2.0 | .3 | 0.40 | <2.0 | 0.50 | <2.0 | 0.30 | <2.0 | 0.20 | <2.0 |
| Bismuth | 20 | 2.3 | | | | | | | | |
| Boron | 100 | 1.9 | | | | | | | | |
| Cadmium | 5.0 | .2 | 0.20 | <5.0 | 0.50 | <5.0 | 0.20 | <5.0 | 0.50 | <5.0 |
| Calcium | 2000 | 8.2 | 10.3 | <5000 | 6.1 | <5000 | 4.7 | <5000 | 8.6 | <5000 |
| Chromium | 10 | .6 | 0.80 | <10 | 0.50 | <10 | 0.60 | <10 | 0.80 | <10 |
| Cobalt | 50 | .2 | 0.10 | <50 | 0.10 | <50 | 0.10 | <50 | 0.30 | <50 |
| Copper | 10 | .8 | 0.30 | <25 | 0.60 | <25 | 0.60 | <25 | 0.0 | <25 |
| Iron | 100 | 8.9 | 2.5 | <500 | -2.9 | <500 | -6.2 | <500 | 6.2 | <500 |
| Lead | 20 | 1 | -0.30 | <20 | 0.80 | <20 | 0.90 | <20 | 0.80 | <20 |
| Lithium | 20 | 2.9 | | | | | | | | |
| Magnesium | 2000 | 88 | -16 | <5000 | 8.5 | <5000 | 6.8 | <5000 | 53.7 | <5000 |
| Manganese | 15 | .1 | 0.20 | <15 | 0.30 | <15 | 0.20 | <15 | 0.30 | <15 |
| Molybdenum | 20 | .3 | anr | | | | | | | |
| Nickel | 10 | .4 | 0.10 | <40 | 0.30 | <40 | 0.10 | <40 | 0.30 | <40 |
| Palladium | 50 | 2.1 | | | | | | | | |
| Potassium | 2000 | 78 | -30 | <10000 | 17.2 | <10000 | -17 | <10000 | 23.4 | <10000 |
| Selenium | 20 | 2.6 | 0.0 | <20 | 0.60 | <20 | -1.3 | <20 | -1.6 | <20 |
| Silicon | 200 | 2.6 | | | | | | | | |
| Silver | 5.0 | .7 | -0.20 | <5.0 | 0.10 | <5.0 | -0.50 | <5.0 | -0.50 | <5.0 |
| Sodium | 2000 | 20 | 16.2 | <10000 | 30.3 | <10000 | 12.2 | <10000 | 3.4 | <10000 |
| Strontium | 10 | .2 | | | | | | | | |
| Sulfur | 50 | 4.8 | | | | | | | | |
| Thallium | 10 | 1.2 | 0.60 | <10 | 0.20 | <10 | 0.40 | <10 | 0.50 | <10 |
| Tin | 10 | .5 | | | | | | | | |
| Titanium | 10 | .7 | | | | | | | | |
| Tungsten | 50 | 1.1 | | | | | | | | |
| Vanadium | 50 | .5 | 0.30 | <50 | 0.20 | <50 | 0.30 | <50 | 0.70 | <50 |
| Zinc | 20 | .1 | 0.40 | <50 | 0.50 | <50 | 0.30 | <50 | 0.60 | <50 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: result < RL  Run ID: MA40457  Units: ug/l

| Time: / Sample ID: | | | 20:44 ICB1 | | 20:55 CCB1 | | 22:00 CCB2 | | 23:10 CCB3 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Zirconium | 10 | .3 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: result < RL  Run ID: MA40457  Units: ug/l

| Time: | | | 00:16 | | 01:26 | | 02:30 | | 03:23 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | CCB4 | | CCB5 | | CCB6 | | CCB7 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Aluminum | 200 | 20 | 1.6 | <500 | 0.50 | <200 | 17.9 | <500 | 9.4 | <500 |
| Antimony | 20 | 1.2 | 1.1 | <20 | 0.90 | <100 | 1.2 | <20 | 1.9 | <20 |
| Arsenic | 20 | 1.5 | 1.7 | <20 | 1.2 | <100 | 0.80 | <20 | 1.6 | <20 |
| Barium | 200 | .5 | 0.70 | <200 | 0.30 | <200 | 0.80 | <200 | 1.0 | <200 |
| Beryllium | 2.0 | .3 | 0.30 | <2.0 | 0.30 | <5.0 | 0.40 | <2.0 | 0.70 | <2.0 |
| Bismuth | 20 | 2.3 | | | | | | | | |
| Boron | 100 | 1.9 | | | | | | | | |
| Cadmium | 5.0 | .2 | 0.40 | <5.0 | 0.30 | <5.0 | 0.60 | <5.0 | 0.70 | <5.0 |
| Calcium | 2000 | 8.2 | 6.3 | <5000 | 6.1 | <2000 | 11.4 | <5000 | 20.0 | <5000 |
| Chromium | 10 | .6 | 0.90 | <10 | 0.60 | <10 | 0.80 | <10 | 1.3 | <10 |
| Cobalt | 50 | .2 | 0.10 | <50 | 0.10 | <50 | 0.40 | <50 | 0.40 | <50 |
| Copper | 10 | .8 | 0.70 | <25 | 0.0 | <10 | -0.20 | <25 | 0.50 | <25 |
| Iron | 100 | 8.9 | 3.1 | <500 | 13.0 | <100 | 10.9 | <500 | 26.1 | <500 |
| Lead | 20 | 1 | 1.0 | <20 | 1.2 | <100 | 0.90 | <20 | 0.80 | <20 |
| Lithium | 20 | 2.9 | | | | | | | | |
| Magnesium | 2000 | 88 | -32 | <5000 | 4.5 | <2000 | 5.1 | <5000 | -66 | <5000 |
| Manganese | 15 | .1 | 0.40 | <15 | 0.20 | <15 | 0.40 | <15 | 0.70 | <15 |
| Molybdenum | 20 | .3 | anr | | | | | | | |
| Nickel | 10 | .4 | 0.0 | <40 | 0.0 | <10 | 0.40 | <40 | 0.40 | <40 |
| Palladium | 50 | 2.1 | | | | | | | | |
| Potassium | 2000 | 78 | -11 | <10000 | 27.5 | <2000 | -30 | <10000 | -79 | <10000 |
| Selenium | 20 | 2.6 | 0.0 | <20 | -0.10 | <100 | 0.0 | <20 | 0.20 | <20 |
| Silicon | 200 | 2.6 | | | | | | | | |
| Silver | 5.0 | .7 | -0.50 | <5.0 | -0.60 | <10 | -0.40 | <5.0 | -0.70 | <5.0 |
| Sodium | 2000 | 20 | 73.4 | <10000 | 39.7 | <2000 | 47.1 | <10000 | 46.4 | <10000 |
| Strontium | 10 | .2 | | | | | | | | |
| Sulfur | 50 | 4.8 | | | | | | | | |
| Thallium | 10 | 1.2 | 0.60 | <10 | 0.50 | <100 | 0.10 | <10 | 0.40 | <10 |
| Tin | 10 | .5 | | | | | | | | |
| Titanium | 10 | .7 | | | | | | | | |
| Tungsten | 50 | 1.1 | | | | | | | | |
| Vanadium | 50 | .5 | 0.50 | <50 | 0.40 | <50 | 0.70 | <50 | 0.90 | <50 |
| Zinc | 20 | .1 | 0.50 | <50 | 0.40 | <20 | 0.70 | <50 | 0.80 | <50 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: result < RL  Run ID: MA40457  Units: ug/l

| Time: / Sample ID: | | | 00:16 CCB4 | | 01:26 CCB5 | | 02:30 CCB6 | | 03:23 CCB7 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Zirconium | 10 | .3 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: result < RL  Run ID: MA40457  Units: ug/l

| Time: | | | 04:04 | |
|---|---|---|---|---|
| Sample ID: | | | CCB8 | |
| Metal | RL | IDL | raw | final |
| Aluminum | 200 | 20 | 33.4 | <500 |
| Antimony | 20 | 1.2 | 0.40 | <20 |
| Arsenic | 20 | 1.5 | 0.90 | <20 |
| Barium | 200 | .5 | 1.4 | <200 |
| Beryllium | 2.0 | .3 | 0.80 | <2.0 |
| Bismuth | 20 | 2.3 | | |
| Boron | 100 | 1.9 | | |
| Cadmium | 5.0 | .2 | 0.60 | <5.0 |
| Calcium | 2000 | 8.2 | 27.9 | <5000 |
| Chromium | 10 | .6 | 1.3 | <10 |
| Cobalt | 50 | .2 | 0.50 | <50 |
| Copper | 10 | .8 | 1.1 | <25 |
| Iron | 100 | 8.9 | 19.5 | <500 |
| Lead | 20 | 1 | 0.80 | <20 |
| Lithium | 20 | 2.9 | | |
| Magnesium | 2000 | 88 | 20.8 | <5000 |
| Manganese | 15 | .1 | 0.80 | <15 |
| Molybdenum | 20 | .3 | anr | |
| Nickel | 10 | .4 | 0.40 | <40 |
| Palladium | 50 | 2.1 | | |
| Potassium | 2000 | 78 | -3.7 | <10000 |
| Selenium | 20 | 2.6 | -0.80 | <20 |
| Silicon | 200 | 2.6 | | |
| Silver | 5.0 | .7 | -0.60 | <5.0 |
| Sodium | 2000 | 20 | 20.6 | <10000 |
| Strontium | 10 | .2 | | |
| Sulfur | 50 | 4.8 | | |
| Thallium | 10 | 1.2 | 1.0 | <10 |
| Tin | 10 | .5 | | |
| Titanium | 10 | .7 | | |
| Tungsten | 50 | 1.1 | | |
| Vanadium | 50 | .5 | 0.80 | <50 |
| Zinc | 20 | .1 | 0.80 | <50 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: result < RL  Run ID: MA40457  Units: ug/l

| Time: | | | 04:04 | |
|---|---|---|---|---|
| Sample ID: | | | CCB8 | |
| Metal | RL | IDL | raw | final |
| Zirconium | 10 | .3 | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| Time: | | 20:38 | | | 20:50 | | | 21:54 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICV | ICV1 | | CCV | CCV1 | | CCV | CCV2 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | 40000 | 41300 | 103.3 | 40000 | 40500 | 101.3 | 40000 | 40600 | 101.5 |
| Antimony | 2000 | 2000 | 100.0 | 2000 | 1990 | 99.5 | 2000 | 1980 | 99.0 |
| Arsenic | 2000 | 2000 | 100.0 | 2000 | 1980 | 99.0 | 2000 | 1990 | 99.5 |
| Barium | 2000 | 1990 | 99.5 | 2000 | 2030 | 101.5 | 2000 | 2070 | 103.5 |
| Beryllium | 2000 | 2050 | 102.5 | 2000 | 2050 | 102.5 | 2000 | 2050 | 102.5 |
| Bismuth | | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | 2000 | 1980 | 99.0 | 2000 | 2000 | 100.0 | 2000 | 2010 | 100.5 |
| Calcium | 40000 | 41700 | 104.3 | 40000 | 40800 | 102.0 | 40000 | 41100 | 102.8 |
| Chromium | 2000 | 2020 | 101.0 | 2000 | 2020 | 101.0 | 2000 | 2000 | 100.0 |
| Cobalt | 2000 | 1980 | 99.0 | 2000 | 2010 | 100.5 | 2000 | 2010 | 100.5 |
| Copper | 2000 | 1950 | 97.5 | 2000 | 1980 | 99.0 | 2000 | 1990 | 99.5 |
| Iron | 40000 | 40900 | 102.3 | 40000 | 41200 | 103.0 | 40000 | 41900 | 104.8 |
| Lead | 2000 | 2000 | 100.0 | 2000 | 2020 | 101.0 | 2000 | 2010 | 100.5 |
| Lithium | | | | | | | | | |
| Magnesium | 40000 | 39900 | 99.8 | 40000 | 40800 | 102.0 | 40000 | 41100 | 102.8 |
| Manganese | 2000 | 2030 | 101.5 | 2000 | 2030 | 101.5 | 2000 | 2010 | 100.5 |
| Molybdenum | anr | | | | | | | | |
| Nickel | 2000 | 2000 | 100.0 | 2000 | 2010 | 100.5 | 2000 | 1990 | 99.5 |
| Palladium | | | | | | | | | |
| Potassium | 40000 | 39400 | 98.5 | 40000 | 40000 | 100.0 | 40000 | 41400 | 103.5 |
| Selenium | 2000 | 1980 | 99.0 | 2000 | 2000 | 100.0 | 2000 | 2000 | 100.0 |
| Silicon | | | | | | | | | |
| Silver | 250 | 256 | 102.4 | 250 | 248 | 99.2 | 250 | 248 | 99.2 |
| Sodium | 40000 | 39300 | 98.3 | 40000 | 40300 | 100.8 | 40000 | 41300 | 103.3 |
| Strontium | | | | | | | | | |
| Sulfur | | | | | | | | | |
| Thallium | 2000 | 2090 | 104.5 | 2000 | 2070 | 103.5 | 2000 | 2060 | 103.0 |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | 2000 | 1990 | 99.5 | 2000 | 2010 | 100.5 | 2000 | 2000 | 100.0 |
| Zinc | 2000 | 2030 | 101.5 | 2000 | 2040 | 102.0 | 2000 | 2050 | 102.5 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| Time: | | 20:38 | | | 20:50 | | | 21:54 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICV | ICV1 | | CCV | CCV1 | | CCV | CCV2 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| Time: | | 23:04 | | | 00:10 | | | 01:20 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CCV | CCV3 | | CCV | CCV4 | | CCV | CCV5 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | 40000 | 40700 | 101.8 | 40000 | 40300 | 100.8 | 40000 | 39400 | 98.5 |
| Antimony | 2000 | 1980 | 99.0 | 2000 | 1960 | 98.0 | 2000 | 1960 | 98.0 |
| Arsenic | 2000 | 2000 | 100.0 | 2000 | 1980 | 99.0 | 2000 | 1970 | 98.5 |
| Barium | 2000 | 2070 | 103.5 | 2000 | 2060 | 103.0 | 2000 | 2020 | 101.0 |
| Beryllium | 2000 | 2050 | 102.5 | 2000 | 2020 | 101.0 | 2000 | 1980 | 99.0 |
| Bismuth | | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | 2000 | 2020 | 101.0 | 2000 | 2010 | 100.5 | 2000 | 2000 | 100.0 |
| Calcium | 40000 | 41100 | 102.8 | 40000 | 40700 | 101.8 | 40000 | 39800 | 99.5 |
| Chromium | 2000 | 1990 | 99.5 | 2000 | 1970 | 98.5 | 2000 | 1930 | 96.5 |
| Cobalt | 2000 | 2000 | 100.0 | 2000 | 1970 | 98.5 | 2000 | 1970 | 98.5 |
| Copper | 2000 | 1990 | 99.5 | 2000 | 2000 | 100.0 | 2000 | 1950 | 97.5 |
| Iron | 40000 | 42000 | 105.0 | 40000 | 42000 | 105.0 | 40000 | 41100 | 102.8 |
| Lead | 2000 | 2010 | 100.5 | 2000 | 1980 | 99.0 | 2000 | 1980 | 99.0 |
| Lithium | | | | | | | | | |
| Magnesium | 40000 | 41500 | 103.8 | 40000 | 41200 | 103.0 | 40000 | 40300 | 100.8 |
| Manganese | 2000 | 2000 | 100.0 | 2000 | 1980 | 99.0 | 2000 | 1950 | 97.5 |
| Molybdenum | anr | | | | | | | | |
| Nickel | 2000 | 1980 | 99.0 | 2000 | 1950 | 97.5 | 2000 | 1940 | 97.0 |
| Palladium | | | | | | | | | |
| Potassium | 40000 | 41700 | 104.3 | 40000 | 41900 | 104.8 | 40000 | 40900 | 102.3 |
| Selenium | 2000 | 2000 | 100.0 | 2000 | 1980 | 99.0 | 2000 | 1980 | 99.0 |
| Silicon | | | | | | | | | |
| Silver | 250 | 247 | 98.8 | 250 | 247 | 98.8 | 250 | 242 | 96.8 |
| Sodium | 40000 | 41400 | 103.5 | 40000 | 41300 | 103.3 | 40000 | 40500 | 101.3 |
| Strontium | | | | | | | | | |
| Sulfur | | | | | | | | | |
| Thallium | 2000 | 2060 | 103.0 | 2000 | 2020 | 101.0 | 2000 | 2020 | 101.0 |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | 2000 | 2000 | 100.0 | 2000 | 1990 | 99.5 | 2000 | 1960 | 98.0 |
| Zinc | 2000 | 2070 | 103.5 | 2000 | 2050 | 102.5 | 2000 | 2050 | 102.5 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Time: | | 23:04 | | | 00:10 | | | 01:20 | |
| Sample ID: | CCV | CCV3 | | CCV | CCV4 | | CCV | CCV5 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| Time: | | 02:25 | | | 03:17 | | | 03:58 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CCV | CCV6 | | CCV | CCV7 | | CCV | CCV8 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | 40000 | 38800 | 97.0 | 40000 | 39400 | 98.5 | 40000 | 38800 | 97.0 |
| Antimony | 2000 | 1900 | 95.0 | 2000 | 1900 | 95.0 | 2000 | 1900 | 95.0 |
| Arsenic | 2000 | 1910 | 95.5 | 2000 | 1920 | 96.0 | 2000 | 1920 | 96.0 |
| Barium | 2000 | 1980 | 99.0 | 2000 | 2000 | 100.0 | 2000 | 1980 | 99.0 |
| Beryllium | 2000 | 1960 | 98.0 | 2000 | 1970 | 98.5 | 2000 | 1950 | 97.5 |
| Bismuth | | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | 2000 | 1930 | 96.5 | 2000 | 1970 | 98.5 | 2000 | 1970 | 98.5 |
| Calcium | 40000 | 39500 | 98.8 | 40000 | 39700 | 99.3 | 40000 | 39400 | 98.5 |
| Chromium | 2000 | 1920 | 96.0 | 2000 | 1890 | 94.5 | 2000 | 1870 | 93.5 |
| Cobalt | 2000 | 1930 | 96.5 | 2000 | 1910 | 95.5 | 2000 | 1900 | 95.0 |
| Copper | 2000 | 1920 | 96.0 | 2000 | 1930 | 96.5 | 2000 | 1930 | 96.5 |
| Iron | 40000 | 40600 | 101.5 | 40000 | 41000 | 102.5 | 40000 | 40800 | 102.0 |
| Lead | 2000 | 1930 | 96.5 | 2000 | 1920 | 96.0 | 2000 | 1910 | 95.5 |
| Lithium | | | | | | | | | |
| Magnesium | 40000 | 39800 | 99.5 | 40000 | 40000 | 100.0 | 40000 | 40000 | 100.0 |
| Manganese | 2000 | 1940 | 97.0 | 2000 | 1900 | 95.0 | 2000 | 1880 | 94.0 |
| Molybdenum | anr | | | | | | | | |
| Nickel | 2000 | 1900 | 95.0 | 2000 | 1870 | 93.5 | 2000 | 1850 | 92.5 |
| Palladium | | | | | | | | | |
| Potassium | 40000 | 39900 | 99.8 | 40000 | 41000 | 102.5 | 40000 | 40400 | 101.0 |
| Selenium | 2000 | 1910 | 95.5 | 2000 | 1920 | 96.0 | 2000 | 1920 | 96.0 |
| Silicon | | | | | | | | | |
| Silver | 250 | 239 | 95.6 | 250 | 240 | 96.0 | 250 | 239 | 95.6 |
| Sodium | 40000 | 39500 | 98.8 | 40000 | 39900 | 99.8 | 40000 | 39300 | 98.3 |
| Strontium | | | | | | | | | |
| Sulfur | | | | | | | | | |
| Thallium | 2000 | 1970 | 98.5 | 2000 | 1950 | 97.5 | 2000 | 1940 | 97.0 |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | 2000 | 1940 | 97.0 | 2000 | 1910 | 95.5 | 2000 | 1900 | 95.0 |
| Zinc | 2000 | 1990 | 99.5 | 2000 | 2010 | 100.5 | 2000 | 2020 | 101.0 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Time: | | 02:25 | | | 03:17 | | | 03:58 | |
| Sample ID: | CCV | CCV6 | | CCV | CCV7 | | CCV | CCV8 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

HIGH STANDARD CHECK SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| Time: / Sample ID: / Metal | HSTD True | 21:25 HSTD1 Results | % Rec | HSTD True | 21:31 HSTD2 Results | % Rec |
|---|---|---|---|---|---|---|
| Aluminum | | | | 300000 | 299000 | 99.7 |
| Antimony | 5000 | 4980 | 99.6 | | | |
| Arsenic | 5000 | 4900 | 98.0 | | | |
| Barium | 5000 | 5070 | 101.4 | | | |
| Beryllium | 5000 | 5090 | 101.8 | | | |
| Bismuth | | | | | | |
| Boron | | | | | | |
| Cadmium | 5000 | 4950 | 99.0 | | | |
| Calcium | | | | 150000 | 150000 | 100.0 |
| Chromium | 5000 | 5030 | 100.6 | | | |
| Cobalt | 5000 | 4910 | 98.2 | | | |
| Copper | 5000 | 5090 | 101.8 | | | |
| Iron | | | | 150000 | 147000 | 98.0 |
| Lead | 5000 | 5000 | 100.0 | | | |
| Lithium | | | | | | |
| Magnesium | | | | 300000 | 299000 | 99.7 |
| Manganese | 5000 | 5020 | 100.4 | | | |
| Molybdenum | anr | | | | | |
| Nickel | 5000 | 4900 | 98.0 | | | |
| Palladium | | | | | | |
| Potassium | | | | 150000 | 162000 | 108.0 |
| Selenium | 5000 | 4920 | 98.4 | | | |
| Silicon | | | | | | |
| Silver | 625 | 611 | 97.8 | | | |
| Sodium | | | | 150000 | 153000 | 102.0 |
| Strontium | | | | | | |
| Sulfur | | | | | | |
| Thallium | 5000 | 5160 | 103.2 | | | |
| Tin | | | | | | |
| Titanium | | | | | | |
| Tungsten | | | | | | |
| Vanadium | 5000 | 4970 | 99.4 | | | |
| Zinc | 5000 | 5130 | 102.6 | | | |

HIGH STANDARD CHECK SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40457  Units: ug/l

| | | | | | | |
|---|---|---|---|---|---|---|
| Time: | | 21:25 | | | 21:31 | |
| Sample ID: | HSTD | HSTD1 | | HSTD | HSTD2 | |
| Metal | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: CRI 70-130%  CRIA 70-130%  Run ID: MA40457  Units: ug/l

| Time: | | | | 21:01 | | 21:07 | | 22:06 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRI1 | | CRID1 | | CRIA1 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 200 | 500 | 100 | 205 | 102.5 | 84.5 | 84.5 | 521 | 104.2 |
| Antimony | 6.0 | 20 | 3.0 | 5.4 | 90.0 | 4.3 | 143.3*(a | 23.4 | 117.0 |
| Arsenic | 8.0 | 20 | 3.0 | 8.9 | 111.3 | 3.7 | 123.3 | 21.5 | 107.5 |
| Barium | 200 | | 4.0 | 210 | 105.0 | 4.3 | 107.5 | | |
| Beryllium | 2.0 | | 1.0 | 2.2 | 110.0 | 1.1 | 110.0 | | |
| Bismuth | 20 | | | | | | | | |
| Boron | 100 | | 10 | | | | | | |
| Cadmium | 3.0 | | 1.0 | 3.1 | 103.3 | 1.2 | 120.0 | | |
| Calcium | 5000 | 2000 | 1000 | 5100 | 102.0 | 1040 | 104.0 | 2100 | 105.0 |
| Chromium | 10 | | 2.0 | 11.0 | 110.0 | 2.6 | 130.0 | | |
| Cobalt | 50 | | 3.0 | 53.1 | 106.2 | 2.9 | 96.7 | | |
| Copper | 10 | | 2.0 | 10.7 | 107.0 | 2.4 | 120.0 | | |
| Iron | 100 | 500 | | 104 | 104.0 | | | 515 | 103.0 |
| Lead | 3.0 | 20 | 2.5 | 2.8 | 93.3 | 3.3 | 132.0*(a | 21.2 | 106.0 |
| Lithium | 20 | | | | | | | | |
| Magnesium | 5000 | 2000 | 100 | 5060 | 101.2 | 113 | 113.0 | 2070 | 103.5 |
| Manganese | 15 | | 3.0 | 16.4 | 109.3 | 3.2 | 106.7 | | |
| Molybdenum | 20 | | | anr | | | | | |
| Nickel | 10 | | 4.0 | 10.0 | 100.0 | 3.7 | 92.5 | | |
| Palladium | 50 | | | | | | | | |
| Potassium | 5000 | | 2000 | 4850 | 97.0 | 2060 | 103.0 | | |
| Selenium | 10 | 20 | 5.0 | 9.2 | 92.0 | 4.4 | 88.0 | 18.7 | 93.5 |
| Silicon | 200 | | | | | | | | |
| Silver | 5.0 | | 2.0 | 5.0 | 100.0 | 1.8 | 90.0 | | |
| Sodium | 5000 | | 1000 | 5010 | 100.2 | 1040 | 104.0 | | |
| Strontium | 10 | | | | | | | | |
| Sulfur | 50 | | | | | | | | |
| Thallium | 10 | | 2.0 | 11.4 | 114.0 | 2.4 | 120.0 | | |
| Tin | 10 | | | | | | | | |
| Titanium | 10 | | | | | | | | |
| Tungsten | 50 | | | | | | | | |
| Vanadium | 50 | | 2.0 | 52.8 | 105.6 | 2.4 | 120.0 | | |
| Zinc | 20 | | 10 | 21.8 | 109.0 | 10.6 | 106.0 | | |

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: CRI 70-130%  CRIA 70-130%  Run ID: MA40457  Units: ug/l

| Time: | | | | 21:01 | | 21:07 | | 22:06 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRI1 | | CRID1 | | CRIA1 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | 10 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested
(a) No samples reported for this element at this RL in the area bracketed by this QC.

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: CRI 70-130%  CRIA 70-130%  Run ID: MA40457  Units: ug/l

| Time: | | | | 03:29 | | 03:35 | | 03:41 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRI2 | | CRID2 | | CRIA2 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 200 | 500 | 100 | 201 | 100.5 | 98.0 | 98.0 | 496 | 99.2 |
| Antimony | 6.0 | 20 | 3.0 | 6.3 | 105.0 | 4.1 | 136.7*(a | 22.6 | 113.0 |
| Arsenic | 8.0 | 20 | 3.0 | 9.5 | 118.8 | 3.6 | 120.0 | 20.9 | 104.5 |
| Barium | 200 | | 4.0 | 211 | 105.5 | 4.8 | 120.0 | | |
| Beryllium | 2.0 | | 1.0 | 2.0 | 100.0 | 1.0 | 100.0 | | |
| Bismuth | 20 | | | | | | | | |
| Boron | 100 | | 10 | | | | | | |
| Cadmium | 3.0 | | 1.0 | 3.1 | 103.3 | 1.1 | 110.0 | | |
| Calcium | 5000 | 2000 | 1000 | 5000 | 100.0 | 1010 | 101.0 | 2030 | 101.5 |
| Chromium | 10 | | 2.0 | 10.7 | 107.0 | 2.3 | 115.0 | | |
| Cobalt | 50 | | 3.0 | 51.1 | 102.2 | 2.8 | 93.3 | | |
| Copper | 10 | | 2.0 | 12.1 | 121.0 | 2.9 | 145.0*(a | | |
| Iron | 100 | 500 | | 99.2 | 99.2 | | | 515 | 103.0 |
| Lead | 3.0 | 20 | 2.5 | 2.1 | 70.0 | 3.5 | 140.0*(a | 19.8 | 99.0 |
| Lithium | 20 | | | | | | | | |
| Magnesium | 5000 | 2000 | 100 | 5010 | 100.2 | 102 | 102.0 | 2150 | 107.5 |
| Manganese | 15 | | 3.0 | 15.3 | 102.0 | 2.9 | 96.7 | | |
| Molybdenum | 20 | | | anr | | | | | |
| Nickel | 10 | | 4.0 | 9.8 | 98.0 | 3.7 | 92.5 | | |
| Palladium | 50 | | | | | | | | |
| Potassium | 5000 | | 2000 | 5080 | 101.6 | 2060 | 103.0 | | |
| Selenium | 10 | 20 | 5.0 | 8.8 | 88.0 | 4.0 | 80.0 | 19.2 | 96.0 |
| Silicon | 200 | | | | | | | | |
| Silver | 5.0 | | 2.0 | 4.5 | 90.0 | 1.4 | 70.0 | | |
| Sodium | 5000 | | 1000 | 5050 | 101.0 | 1050 | 105.0 | | |
| Strontium | 10 | | | | | | | | |
| Sulfur | 50 | | | | | | | | |
| Thallium | 10 | | 2.0 | 10.7 | 107.0 | 1.9 | 95.0 | | |
| Tin | 10 | | | | | | | | |
| Titanium | 10 | | | | | | | | |
| Tungsten | 50 | | | | | | | | |
| Vanadium | 50 | | 2.0 | 50.6 | 101.2 | 2.3 | 115.0 | | |
| Zinc | 20 | | 10 | 21.9 | 109.5 | 10.7 | 107.0 | | |

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: CRI 70-130%  CRIA 70-130%  Run ID: MA40457  Units: ug/l

| Time: | | | | 03:29 | | 03:35 | | 03:41 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRI2 | | CRID2 | | CRIA2 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | 10 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested
(a) No samples reported for this element at this RL in the area bracketed by this QC.

INTERFERING ELEMENT CHECK STANDARDS SUMMARY
Part 1 - ICSA and ICSAB Standards

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 80 to 120 % Recovery  Run ID: MA40457  Units: ug/l

| Time: | | | 21:13 | | 21:19 | | 03:47 | | 03:53 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICSA | ICSAB | ICSA1 | | ICSAB1 | | ICSA2 | | ICSAB2 | |
| Metal | True | True | Results | % Rec | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 500000 | 500000 | 495000 | 99.0 | 492000 | 98.4 | 487000 | 97.4 | 481000 | 96.2 |
| Antimony | | 1000 | 2.2 | | 1000 | 100.0 | 2.6 | | 973 | 97.3 |
| Arsenic | | 1000 | -0.80 | | 1040 | 104.0 | -0.10 | | 1020 | 102.0 |
| Barium | | 500 | -0.60 | | 508 | 101.6 | -0.10 | | 505 | 101.0 |
| Beryllium | | 500 | 0.50 | | 495 | 99.0 | 0.30 | | 479 | 95.8 |
| Bismuth | | 500 | 10.8 | | 518 | 103.6 | 7.7 | | 504 | 100.8 |
| Boron | | 500 | 1.2 | | 484 | 96.8 | 0.20 | | 474 | 94.8 |
| Cadmium | | 1000 | 0.60 | | 1020 | 102.0 | 0.60 | | 1020 | 102.0 |
| Calcium | 400000 | 400000 | 381000 | 95.3 | 373000 | 93.3 | 373000 | 93.3 | 363000 | 90.8 |
| Chromium | | 500 | -1.5 | | 495 | 99.0 | -0.40 | | 464 | 92.8 |
| Cobalt | | 500 | 0.40 | | 490 | 98.0 | -0.10 | | 473 | 94.6 |
| Copper | | 500 | -6.3 | | 498 | 99.6 | -1.2 | | 490 | 98.0 |
| Iron | 200000 | 200000 | 186000 | 93.0 | 185000 | 92.5 | 187000 | 93.5 | 184000 | 92.0 |
| Lead | | 1000 | -0.40 | | 950 | 95.0 | 4.0 | | 920 | 92.0 |
| Lithium | | 500 | -26 | | 592 | 118.4 | -23 | | 552 | 110.4 |
| Magnesium | 500000 | 500000 | 485000 | 97.0 | 481000 | 96.2 | 477000 | 95.4 | 473000 | 94.6 |
| Manganese | | 500 | 3.6 | | 497 | 99.4 | 4.0 | | 464 | 92.8 |
| Molybdenum | | 500 | 0.30 | | 485 | 97.0 | 0.70 | | 481 | 96.2 |
| Nickel | | 1000 | -1.5 | | 976 | 97.6 | -1.8 | | 919 | 91.9 |
| Palladium | | 500 | -46 | | 469 | 93.8 | -44 | | 432 | 86.4 |
| Potassium | | | 66.3 | | 124 | | 41.4 | | 15.4 | |
| Selenium | | 1000 | 7.6 | | 997 | 99.7 | 5.4 | | 971 | 97.1 |
| Silicon | | 500 | -22 | | 484 | 96.8 | -20 | | 470 | 94.0 |
| Silver | | 1000 | 5.3 | | 958 | 95.8 | 3.8 | | 930 | 93.0 |
| Sodium | | | 3.9 | | 6.0 | | 23.7 | | 22.3 | |
| Strontium | | 500 | 6.1 | | 521 | 104.2 | 6.4 | | 516 | 103.2 |
| Sulfur | | 500 | 1.5 | | 484 | 96.8 | 2.1 | | 478 | 95.6 |
| Thallium | | 1000 | 1.3 | | 973 | 97.3 | 0.0 | | 937 | 93.7 |
| Tin | | 500 | -4.2 | | 469 | 93.8 | -4.3 | | 463 | 92.6 |
| Titanium | | 500 | -3.8 | | 483 | 96.6 | -3.3 | | 456 | 91.2 |
| Tungsten | | 500 | 2.9 | | 482 | 96.4 | 4.9 | | 473 | 94.6 |
| Vanadium | | 500 | -1.8 | | 485 | 97.0 | -1.4 | | 461 | 92.2 |
| Zinc | | 1000 | -4.6 | | 965 | 96.5 | -4.8 | | 966 | 96.6 |

INTERFERING ELEMENT CHECK STANDARDS SUMMARY
Part 1 - ICSA and ICSAB Standards

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SC100516M1.ICP  Date Analyzed: 10/05/16  Methods: SW846 6010B, SW846 6010C
QC Limits: 80 to 120 % Recovery  Run ID: MA40457  Units: ug/l

| Time: | | | 21:13 | | 21:19 | | 03:47 | | 03:53 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICSA | ICSAB | ICSA1 | | ICSAB1 | | ICSA2 | | ICSAB2 | |
| Metal | True | True | Results | % Rec | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | | 500 | 5.5 | | 498 | 99.6 | 6.0 | | 465 | 93.0 |

(*) Outside of QC limits
(anr) Analyte not requested

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: H5100616S1.CSV  Date Analyzed: 10/06/16  Methods: SW846 7471A, SW846 7471B
Analyst: JPM  Run ID: MA40466
Parameters: Hg

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 11:20 | MA40466-STD1 | 1 | | B=1.0658e-004,C=-2.2890e-002,R=0.9998783 |
| 11:21 | MA40466-STD2 | 1 | | STDB |
| 11:23 | MA40466-STD3 | 1 | | STDC |
| 11:24 | MA40466-STD4 | 1 | | STDD |
| 11:26 | MA40466-STD5 | 1 | | STDE |
| 11:27 | MA40466-STD6 | 1 | | STDF |
| 11:30 | MA40466-STD7 | 1 | | STDE |
| 11:32 | MA40466-STD8 | 1 | | STDF |
| 11:34 | MA40466-ICV1 | 1 | | |
| 11:35 | MA40466-ICB1 | 1 | | |
| 11:37 | MA40466-CCV1 | 1 | | |
| 11:38 | MA40466-CCB1 | 1 | | |
| 11:40 | MA40466-CRI1 | 1 | | |
| 11:42 | MP96393-MB1 | 1 | | |
| 11:43 | MP96393-B1 | 1 | | |
| 11:45 | MP96393-S1 | 1 | | |
| 11:46 | MP96393-S2 | 1 | | |
| 11:48 | JC28910-1 | 1 | | (sample used for QC only; not part of login JC28902) |
| 11:50 | ZZZZZZ | 1 | | |
| 11:51 | JC28902-1 | 1 | | |
| ----------> | Last reportable sample/prep for job JC28902 | | | |
| 11:52 | ZZZZZZ | 1 | | |
| 11:53 | ZZZZZZ | 1 | | |
| 11:55 | MA40466-CCV2 | 1 | | |
| 11:57 | MA40466-CCB2 | 1 | | |
| ----------> | Last reportable CCB for job JC28902 | | | |
| 11:58 | ZZZZZZ | 1 | | |
| 12:00 | ZZZZZZ | 1 | | |
| 12:01 | ZZZZZZ | 1 | | |
| 12:03 | ZZZZZZ | 1 | | |
| 12:05 | ZZZZZZ | 1 | | |
| 12:06 | ZZZZZZ | 1 | | |
| 12:08 | ZZZZZZ | 1 | | |
| 12:09 | ZZZZZZ | 1 | | |
| 12:11 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: H5100616S1.CSV Date Analyzed: 10/06/16 Methods: SW846 7471A, SW846 7471B
Analyst: JPM Run ID: MA40466
Parameters: Hg

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 12:13 | ZZZZZZ | 1 | | |
| 12:14 | MA40466-CCV3 | 1 | | |
| 12:16 | MA40466-CCB3 | 1 | | |
| 12:18 | ZZZZZZ | 1 | | |
| 12:19 | ZZZZZZ | 1 | | |
| 12:20 | ZZZZZZ | 1 | | |
| 12:22 | ZZZZZZ | 1 | | |
| 12:23 | ZZZZZZ | 1 | | |
| 12:24 | MP96353-MB2 | 1 | | |
| 12:26 | MP96353-B2 | 1 | | |
| 12:27 | ZZZZZZ | 1 | | |
| 12:29 | MA40466-CCV4 | 1 | | |
| 12:30 | MA40466-CCB4 | 1 | | |

Refer to raw data for calibration curve and standards.

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: H5100616S1.CSV  Date Analyzed: 10/06/16  Methods: SW846 7471A, SW846 7471B
QC Limits: result < RL  Run ID: MA40466  Units: ug/l

| Time: | | | 11:35 | | 11:38 | | 11:57 | |
|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | ICB1 | | CCB1 | | CCB2 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final |
| Mercury | 0.20 | .039 | -0.025 | <0.20 | -0.031 | <0.20 | -0.027 | <0.20 |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: H5100616S1.CSV Date Analyzed: 10/06/16 Methods: SW846 7471A, SW846 7471B
QC Limits: 90 to 110 % Recovery Run ID: MA40466 Units: ug/l

| Time: | | 11:34 | | | 11:37 | | | 11:55 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICV | ICV1 | | CCV | CCV1 | | CCV | CCV2 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Mercury | 3.0 | 3.0 | 100.0 | 2.5 | 2.5 | 100.0 | 2.5 | 2.5 | 100.0 |

(*) Outside of QC limits
(anr) Analyte not requested

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: H5100616S1.CSV  Date Analyzed: 10/06/16  Methods: SW846 7471A, SW846 7471B
QC Limits: 70 to 130 % Recovery  Run ID: MA40466  Units: ug/l

| Time: | | | 11:40 | |
|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRI1 | |
| Metal | True | True | Results | % Rec |
| Mercury | 0.20 | | 0.21 | 105.0 |

(*) Outside of QC limits
(anr) Analyte not requested

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 16:48 | MA40471-STD1 | 1 | | STDA |
| 16:54 | MA40471-STD2 | 1 | | STDB |
| 17:00 | ZZZZZZ | 1 | | |
| 17:06 | ZZZZZZ | 1 | | |
| 17:13 | MA40471-ICV1 | 1 | | |
| 17:23 | MA40471-ICB1 | 1 | | |
| 17:28 | MA40471-ICCV1 | 1 | | |
| 17:40 | MA40471-CCB1 | 1 | | |
| 17:47 | MA40471-CRI1 | 1 | | |
| 17:53 | MA40471-CRID1 | 1 | | TLNJ out |
| 17:59 | MA40471-CRIA1 | 1 | | |
| 18:05 | MA40471-ICSA1 | 1 | | |
| 18:11 | MA40471-ICSAB1 | 1 | | |
| 18:17 | MA40471-HSTD1 | 1 | | |
| 18:23 | MA40471-HSTD2 | 1 | | Minerals |
| 18:30 | ZZZZZZ | 1 | | |
| 18:36 | ZZZZZZ | 1 | | |
| 18:42 | ZZZZZZ | 1 | | |
| 18:48 | MA40471-CCV1 | 1 | | |
| 18:54 | MA40471-CCB2 | 1 | | |
| 19:00 | MA40471-CRID2 | 1 | | |
| 19:06 | ZZZZZZ | 5 | | |
| 19:12 | ZZZZZZ | 5 | | |
| 19:18 | MP96360-S1 | 5 | | |
| 19:24 | MP96360-S2 | 5 | | |
| 19:30 | MP96360-SD1 | 25 | | |
| 19:36 | MP96377-B1 | 1 | | |
| 19:42 | MP96377-MB1 | 1 | | |
| 19:48 | MP96377-S1 | 1 | | |
| 19:54 | MP96377-S2 | 1 | | |
| 20:00 | MA40471-CCV2 | 1 | | |
| 20:06 | MA40471-CCB3 | 1 | | |
| 20:13 | JC28888-2 | 1 | | (sample used for QC only; not part of login JC28902) |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 20:19 | MP96377-SD1 | 5 | | |
| 20:25 | ZZZZZZ | 1 | | |
| 20:31 | ZZZZZZ | 1 | | |
| 20:37 | ZZZZZZ | 1 | | |
| 20:43 | ZZZZZZ | 1 | | |
| 20:50 | ZZZZZZ | 1 | | |
| 20:56 | ZZZZZZ | 1 | | |
| 21:02 | ZZZZZZ | 1 | | |
| 21:08 | MA40471-CCV3 | 1 | | |
| 21:14 | MA40471-CCB4 | 1 | | |
| 21:20 | MP96277-MB1 | 1 | | |
| 21:26 | MP96277-MB2 | 1 | | |
| 21:32 | MP96277-B1 | 1 | | |
| 21:38 | MP96277-B2 | 1 | | |
| 21:44 | MP96277-S1 | 1 | | |
| 21:50 | MP96277-S2 | 1 | | |
| 21:56 | JC28495-2 | 1 | | (sample used for QC only; not part of login JC28902) |
| 22:02 | MP96277-SD1 | 5 | | |
| 22:08 | MP96277-S3 | 1 | | |
| 22:14 | MA40471-CCV4 | 1 | | |
| 22:20 | MA40471-CCB5 | 1 | | |
| 22:27 | MP96277-S4 | 1 | | |
| 22:33 | JC28495-2F | 1 | | (sample used for QC only; not part of login JC28902) |
| 22:39 | MP96277-SD2 | 5 | | |
| 22:45 | ZZZZZZ | 1 | | |
| 22:51 | ZZZZZZ | 1 | | |
| 22:57 | ZZZZZZ | 1 | | |
| 23:03 | ZZZZZZ | 1 | | |
| 23:09 | ZZZZZZ | 1 | | |
| 23:15 | ZZZZZZ | 1 | | |
| 23:21 | MA40471-CCV5 | 1 | | |
| 23:27 | MA40471-CCB6 | 1 | | |
| 23:34 | MA40471-CRID3 | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 23:40 | MA40471-CRI2 | 1 | | |
| 23:46 | MA40471-CRIA2 | 1 | | |
| 23:52 | MA40471-ICSA2 | 1 | | |
| 23:58 | MA40471-ICSAB2 | 1 | | |
| 00:04 | MA40471-CCV6 | 1 | | |
| 00:10 | MA40471-CCB7 | 1 | | |
| 00:16 | ZZZZZZ | 1 | | |
| 00:22 | ZZZZZZ | 1 | | |
| 00:28 | ZZZZZZ | 1 | | |
| 00:34 | ZZZZZZ | 1 | | |
| 00:40 | ZZZZZZ | 1 | | |
| 00:47 | ZZZZZZ | 1 | | |
| 00:53 | ZZZZZZ | 1 | | |
| 00:59 | ZZZZZZ | 1 | | |
| 01:05 | ZZZZZZ | 1 | | |
| 01:11 | ZZZZZZ | 1 | | |
| 01:17 | MA40471-CCV7 | 1 | | |
| 01:23 | MA40471-CCB8 | 1 | | |
| 01:29 | ZZZZZZ | 1 | | |
| 01:35 | ZZZZZZ | 1 | | |
| 01:41 | MP96382-B1 | 1 | | |
| 01:47 | MP96382-MB1 | 1 | | |
| 01:53 | MP96382-MB2 | 1 | | |
| 01:59 | MP96382-B2 | 1 | | |
| 02:05 | MP96382-S1 | 1 | | |
| 02:11 | MP96382-S2 | 1 | | |
| 02:17 | JC28861-2 | 1 | | (sample used for QC only; not part of login JC28902) |
| 02:24 | MP96382-SD1 | 5 | | |
| 02:30 | MA40471-CCV8 | 1 | | |
| 02:36 | MA40471-CCB9 | 1 | | |
| 02:42 | ZZZZZZ | 1 | | |
| 02:48 | ZZZZZZ | 1 | | |
| 02:54 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 03:01 | ZZZZZZ | 1 | | |
| 03:07 | ZZZZZZ | 1 | | |
| 03:13 | ZZZZZZ | 1 | | |
| 03:19 | ZZZZZZ | 1 | | |
| 03:25 | ZZZZZZ | 1 | | |
| 03:31 | ZZZZZZ | 1 | | |
| 03:37 | MA40471-CCV9 | 1 | | |
| 03:43 | MA40471-CCB10 | 1 | | |
| 03:49 | ZZZZZZ | 1 | | |
| 03:55 | ZZZZZZ | 1 | | |
| 04:02 | ZZZZZZ | 1 | | |
| 04:08 | ZZZZZZ | 1 | | |
| 04:14 | ZZZZZZ | 1 | | |
| 04:20 | ZZZZZZ | 1 | | |
| 04:26 | ZZZZZZ | 1 | | |
| 04:32 | ZZZZZZ | 1 | | |
| 04:38 | ZZZZZZ | 1 | | |
| 04:44 | MA40471-CCV10 | 1 | | |
| 04:50 | MA40471-CCB11 | 1 | | |
| 04:57 | ZZZZZZ | 1 | | |
| 05:03 | ZZZZZZ | 1 | | |
| 05:09 | MP96373-MB1 | 1 | | |
| ----------> | Last reportable sample/prep for job JC28902 | | | |
| 05:15 | ZZZZZZ | 1 | | |
| 05:21 | ZZZZZZ | 1 | | |
| 05:27 | ZZZZZZ | 1 | | |
| 05:33 | ZZZZZZ | 1 | | |
| 05:39 | ZZZZZZ | 1 | | |
| 05:45 | ZZZZZZ | 1 | | |
| 05:51 | MA40471-CCV11 | 1 | | |
| 05:57 | MA40471-CCB12 | 1 | | |
| 06:03 | ZZZZZZ | 1 | | |
| 06:09 | ZZZZZZ | 1 | | |
| 06:15 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| | Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|---|
| | 06:21 | ZZZZZZ | 1 | | |
| | 06:27 | ZZZZZZ | 1 | | |
| | 06:33 | ZZZZZZ | 1 | | |
| | 06:39 | ZZZZZZ | 1 | | |
| | 06:45 | ZZZZZZ | 1 | | |
| | 06:51 | ZZZZZZ | 1 | | |
| | 06:57 | MA40471-CCV12 | 1 | | |
| | 07:03 | MA40471-CCB13 | 1 | | |
| | 07:09 | MA40471-CRI3 | 1 | | |
| | 07:15 | MA40471-CRID4 | 1 | | TLNJ out |
| | 07:21 | MA40471-CRIA3 | 1 | | |
| | 07:27 | MA40471-ICSA3 | 1 | | |
| | 07:33 | MA40471-ICSAB3 | 1 | | |
| | 07:40 | MA40471-CCV13 | 1 | | |
| | 07:46 | MA40471-CCB14 | 1 | | |
| ----------> | Last reportable CCB for job JC28902 | | | | |
| | 07:52 | MP96388-MB1 | 1 | | |
| | 07:58 | MP96388-B1 | 1 | | |
| | 08:25 | MP96388-S1 | 1 | | |
| | 08:31 | MP96388-S2 | 1 | | |
| | 08:37 | JC28915-6 | 1 | | (sample used for QC only; not part of login JC28902) |
| | 08:43 | MP96388-SD1 | 5 | | |
| | 08:49 | ZZZZZZ | 1 | | |
| | 08:55 | ZZZZZZ | 1 | | |
| | 09:01 | ZZZZZZ | 1 | | |
| | 09:07 | MA40471-CCV14 | 1 | | |
| | 09:13 | MA40471-CCB15 | 1 | | |
| | 09:20 | ZZZZZZ | 1 | | |
| | 09:26 | ZZZZZZ | 1 | | |
| | 09:30 | ZZZZZZ | 1 | | |
| | 09:35 | ZZZZZZ | 1 | | |
| | 09:40 | ZZZZZZ | 1 | | |
| | 09:45 | ZZZZZZ | 1 | | |
| | 10:20 | MP96398-B1 | 1 | | To be reanalyzed with the batch. |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 10:24 | ZZZZZZ | 1 | | |
| 10:30 | MP96398-MB1 | 1 | | To be reanalyzed with the batch. |
| 10:34 | MA40471-CRI4 | 1 | | |
| 10:39 | MA40471-CCV15 | 1 | | |
| 10:44 | MA40471-CCB16 | 1 | | |

Refer to raw data for calibration curve and standards.

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP Date Analyzed: 10/06/16 Methods: EPA 200.7, SW846 6010C
Analyst: KS Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 16:48 | MA40471-STD1 | 3604 R | 174060 R | 29730 R | 7820 R |
| 16:54 | MA40471-STD2 | 3325 | 161780 | 28839 | 6691 |
| 17:00 | ZZZZZZ | 3426 | 166240 | 29183 | 6954 |
| 17:06 | ZZZZZZ | 3577 | 171890 | 29218 | 7772 |
| 17:13 | MA40471-ICV1 | 3422 | 165020 | 29090 | 6961 |
| 17:23 | MA40471-ICB1 | 3584 | 172150 | 29229 | 7792 |
| 17:28 | MA40471-ICCV1 | 3435 | 167040 | 29319 | 6987 |
| 17:40 | MA40471-CCB1 | 3588 | 173150 | 29296 | 7812 |
| 17:47 | MA40471-CRI1 | 3542 | 172320 | 29369 | 7599 |
| 17:53 | MA40471-CRID1 | 3568 | 172880 | 29444 | 7733 |
| 17:59 | MA40471-CRIA1 | 3579 | 174840 | 29721 | 7752 |
| 18:05 | MA40471-ICSA1 | 3180 | 154190 | 27981 | 6199 |
| 18:11 | MA40471-ICSAB1 | 3162 | 152970 | 27984 | 6188 |
| 18:17 | MA40471-HSTD1 | 3478 | 169540 | 29079 | 7438 |
| 18:23 | MA40471-HSTD2 | 3222 | 156670 | 28437 | 6234 |
| 18:30 | ZZZZZZ | 3466 | 168770 | 28970 | 7615 |
| 18:36 | ZZZZZZ | 3508 | 174490 | 29325 | 7771 |
| 18:42 | ZZZZZZ | 3566 | 171650 | 29389 | 7727 |
| 18:48 | MA40471-CCV1 | 3382 | 163420 | 29037 | 6875 |
| 18:54 | MA40471-CCB2 | 3556 | 169630 | 29292 | 7706 |
| 19:00 | MA40471-CRID2 | 3525 | 169710 | 29206 | 7626 |
| 19:06 | ZZZZZZ | 3547 | 171000 | 29504 | 7714 |
| 19:12 | ZZZZZZ | 3485 | 169250 | 29495 | 7435 |
| 19:18 | MP96360-S1 | 3447 | 166810 | 29281 | 7291 |
| 19:24 | MP96360-S2 | 3448 | 166570 | 29263 | 7284 |
| 19:30 | MP96360-SD1 | 3509 | 169510 | 29491 | 7621 |
| 19:36 | MP96377-B1 | 3416 | 165550 | 29610 | 7120 |
| 19:42 | MP96377-MB1 | 3527 | 170600 | 29777 | 7778 |
| 19:48 | MP96377-S1 | 3105 | 154750 | 28134 | 6267 |
| 19:54 | MP96377-S2 | 3121 | 152960 | 27908 | 6279 |
| 20:00 | MA40471-CCV2 | 3364 | 160240 | 28938 | 6861 |
| 20:06 | MA40471-CCB3 | 3526 | 169340 | 29390 | 7697 |
| 20:13 | JC28888-2 | 3150 | 155870 | 28149 | 6377 |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP Date Analyzed: 10/06/16 Methods: EPA 200.7, SW846 6010C
Analyst: KS Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 20:19 | MP96377-SD1 | 3344 | 163100 | 28756 | 7059 |
| 20:25 | ZZZZZZ | 3477 | 168170 | 31410 | 6599 |
| 20:31 | ZZZZZZ | 3158 | 156540 | 28521 | 6390 |
| 20:37 | ZZZZZZ | 3445 | 166540 | 31320 | 6581 |
| 20:43 | ZZZZZZ | 3175 | 154770 | 27991 | 6426 |
| 20:50 | ZZZZZZ | 3296 | 161160 | 29238 | 6937 |
| 20:56 | ZZZZZZ | 3175 | 155900 | 28276 | 6409 |
| 21:02 | ZZZZZZ | 3215 | 159600 | 28905 | 6686 |
| 21:08 | MA40471-CCV3 | 3395 | 162170 | 28688 | 6921 |
| 21:14 | MA40471-CCB4 | 3514 | 167240 | 28842 | 7658 |
| 21:20 | MP96277-MB1 | 3511 | 167680 | 28936 | 7674 |
| 21:26 | MP96277-MB2 | 3550 | 169860 | 29531 | 7760 |
| 21:32 | MP96277-B1 | 3407 | 164100 | 29178 | 7078 |
| 21:38 | MP96277-B2 | 3440 | 165160 | 29528 | 7160 |
| 21:44 | MP96277-S1 | 3310 | 162510 | 29195 | 6741 |
| 21:50 | MP96277-S2 | 3293 | 162240 | 29113 | 6703 |
| 21:56 | JC28495-2 | 3311 | 164140 | 29015 | 6875 |
| 22:02 | MP96277-SD1 | 3471 | 169570 | 29337 | 7435 |
| 22:08 | MP96277-S3 | 3291 | 161770 | 29211 | 6739 |
| 22:14 | MA40471-CCV4 | 3416 | 164810 | 28915 | 6980 |
| 22:20 | MA40471-CCB5 | 3583 | 170310 | 28971 | 7825 |
| 22:27 | MP96277-S4 | 3319 | 164190 | 29472 | 6786 |
| 22:33 | JC28495-2F | 3319 | 164740 | 29005 | 6899 |
| 22:39 | MP96277-SD2 | 3475 | 169370 | 29187 | 7434 |
| 22:45 | ZZZZZZ | 3215 | 160550 | 28720 | 6606 |
| 22:51 | ZZZZZZ | 3175 | 156670 | 28339 | 6182 |
| 22:57 | ZZZZZZ | 3251 | 162530 | 28709 | 6636 |
| 23:03 | ZZZZZZ | 3153 | 155450 | 28282 | 6140 |
| 23:09 | ZZZZZZ | 3570 | 173560 | 29602 | 7828 |
| 23:15 | ZZZZZZ | 3601 | 174700 | 29523 | 7886 |
| 23:21 | MA40471-CCV5 | 3447 | 166690 | 28901 | 7021 |
| 23:27 | MA40471-CCB6 | 3578 | 172920 | 29218 | 7822 |
| 23:34 | MA40471-CRID3 | 3614 | 174410 | 29291 | 7854 |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP Date Analyzed: 10/06/16 Methods: EPA 200.7, SW846 6010C
Analyst: KS Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 23:40 | MA40471-CRI2 | 3552 | 171260 | 28706 | 7627 |
| 23:46 | MA40471-CRIA2 | 3585 | 173310 | 28967 | 7797 |
| 23:52 | MA40471-ICSA2 | 3185 | 154410 | 27957 | 6220 |
| 23:58 | MA40471-ICSAB2 | 3186 | 153870 | 28010 | 6241 |
| 00:04 | MA40471-CCV6 | 3473 | 168140 | 29041 | 7060 |
| 00:10 | MA40471-CCB7 | 3603 | 173030 | 28787 | 7850 |
| 00:16 | ZZZZZZ | 3426 | 169220 | 29300 | 7174 |
| 00:22 | ZZZZZZ | 3334 | 165030 | 28926 | 6852 |
| 00:28 | ZZZZZZ | 3340 | 167010 | 29271 | 6867 |
| 00:34 | ZZZZZZ | 3550 | 175150 | 29829 | 7565 |
| 00:40 | ZZZZZZ | 3509 | 172450 | 29753 | 7490 |
| 00:47 | ZZZZZZ | 3603 | 173960 | 29423 | 7861 |
| 00:53 | ZZZZZZ | 3464 | 170240 | 29066 | 7257 |
| 00:59 | ZZZZZZ | 3333 | 166270 | 29163 | 6867 |
| 01:05 | ZZZZZZ | 3355 | 164190 | 29742 | 6888 |
| 01:11 | ZZZZZZ | 3591 | 173820 | 29233 | 7621 |
| 01:17 | MA40471-CCV7 | 3454 | 165910 | 28746 | 7038 |
| 01:23 | MA40471-CCB8 | 3692 | 177860 | 29605 | 8047 |
| 01:29 | ZZZZZZ | 3562 | 174510 | 29412 | 7591 |
| 01:35 | ZZZZZZ | 3650 | 177550 | 29795 | 7959 |
| 01:41 | MP96382-B1 | 3510 | 170290 | 29196 | 7273 |
| 01:47 | MP96382-MB1 | 3655 | 178580 | 29734 | 7991 |
| 01:53 | MP96382-MB2 | 3649 | 176480 | 29643 | 7975 |
| 01:59 | MP96382-B2 | 3544 | 172160 | 29462 | 7349 |
| 02:05 | MP96382-S1 | 3395 | 166950 | 29137 | 6967 |
| 02:11 | MP96382-S2 | 3464 | 169770 | 29553 | 7096 |
| 02:17 | JC28861-2 | 3485 | 171570 | 29556 | 7300 |
| 02:24 | MP96382-SD1 | 3613 | 175150 | 29485 | 7773 |
| 02:30 | MA40471-CCV8 | 3540 | 171100 | 29104 | 7192 |
| 02:36 | MA40471-CCB9 | 3704 | 178790 | 29653 | 8047 |
| 02:42 | ZZZZZZ | 3232 | 160840 | 28052 | 6424 |
| 02:48 | ZZZZZZ | 3455 | 171060 | 28958 | 7296 |
| 02:54 | ZZZZZZ | 3360 | 167230 | 28598 | 6929 |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP Date Analyzed: 10/06/16 Methods: EPA 200.7, SW846 6010C
Analyst: KS Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 03:01 | ZZZZZZ | 3498 | 171510 | 28956 | 7302 |
| 03:07 | ZZZZZZ | 3552 | 174010 | 29394 | 7377 |
| 03:13 | ZZZZZZ | 3245 | 157730 | 28255 | 6248 |
| 03:19 | ZZZZZZ | 3192 | 159990 | 27760 | 6400 |
| 03:25 | ZZZZZZ | 3316 | 165950 | 28469 | 6752 |
| 03:31 | ZZZZZZ | 3227 | 162010 | 27892 | 6516 |
| 03:37 | MA40471-CCV9 | 3492 | 167910 | 28529 | 7088 |
| 03:43 | MA40471-CCB10 | 3662 | 177300 | 28964 | 7952 |
| 03:49 | ZZZZZZ | 3257 | 161790 | 27956 | 6563 |
| 03:55 | ZZZZZZ | 3217 | 157860 | 27970 | 6161 |
| 04:02 | ZZZZZZ | 3215 | 160400 | 27623 | 6459 |
| 04:08 | ZZZZZZ | 3300 | 164750 | 28212 | 6712 |
| 04:14 | ZZZZZZ | 3248 | 163200 | 28025 | 6566 |
| 04:20 | ZZZZZZ | 3388 | 169310 | 28589 | 6982 |
| 04:26 | ZZZZZZ | 3587 | 175900 | 29416 | 7619 |
| 04:32 | ZZZZZZ | 3529 | 173800 | 29314 | 7454 |
| 04:38 | ZZZZZZ | 3288 | 163620 | 27919 | 6730 |
| 04:44 | MA40471-CCV10 | 3528 | 170450 | 28756 | 7152 |
| 04:50 | MA40471-CCB11 | 3679 | 178510 | 28876 | 7999 |
| 04:57 | ZZZZZZ | 3331 | 165370 | 28430 | 6810 |
| 05:03 | ZZZZZZ | 3526 | 170910 | 28428 | 7291 |
| 05:09 | MP96373-MB1 | 3687 | 177950 | 29022 | 8025 |
| 05:15 | ZZZZZZ | 3732 | 180150 | 29816 | 7691 |
| 05:21 | ZZZZZZ | 3710 | 177400 | 29762 | 7623 |
| 05:27 | ZZZZZZ | 3757 | 180790 | 29781 | 7686 |
| 05:33 | ZZZZZZ | No results reported for the elements associated with this internal standard. | | | |
| 05:39 | ZZZZZZ | No results reported for the elements associated with this internal standard. | | | |
| 05:45 | ZZZZZZ | No results reported for the elements associated with this internal standard. | | | |
| 05:51 | MA40471-CCV11 | 3546 | 170500 | 28362 | 7186 |
| 05:57 | MA40471-CCB12 | 3709 | 178290 | 29019 | 8042 |
| 06:03 | ZZZZZZ | No results reported for the elements associated with this internal standard. | | | |
| 06:09 | ZZZZZZ | 3792 | 181790 | 30168 | 7701 |
| 06:15 | ZZZZZZ | 3795 | 177300 | 29635 | 7716 |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP Date Analyzed: 10/06/16 Methods: EPA 200.7, SW846 6010C
Analyst: KS Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 06:21 | ZZZZZZ | 3648 | 173690 | 29130 | 7488 |
| 06:27 | ZZZZZZ | 3696 | 175230 | 29705 | 7610 |
| 06:33 | ZZZZZZ | 3823 | 182350 | 30514 | 7461 |
| 06:39 | ZZZZZZ | 3788 | 181800 | 30149 | 7387 |
| 06:45 | ZZZZZZ | 3783 | 180670 | 29744 | 7655 |
| 06:51 | ZZZZZZ | 3743 | 178790 | 29662 | 7599 |
| 06:57 | MA40471-CCV12 | 3553 | 169190 | 28783 | 7218 |
| 07:03 | MA40471-CCB13 | 3728 | 180400 | 29083 | 8106 |
| 07:09 | MA40471-CRI3 | 3638 | 176640 | 28936 | 7823 |
| 07:15 | MA40471-CRID4 | 3669 | 178810 | 28880 | 7949 |
| 07:21 | MA40471-CRIA3 | 3673 | 178080 | 29240 | 7960 |
| 07:27 | MA40471-ICSA3 | 3291 | 159380 | 28018 | 6391 |
| 07:33 | MA40471-ICSAB3 | 3293 | 157590 | 28057 | 6421 |
| 07:40 | MA40471-CCV13 | 3549 | 171860 | 28791 | 7184 |
| 07:46 | MA40471-CCB14 | 3674 | 177310 | 28665 | 7972 |
| 07:52 | MP96388-MB1 | 3718 | 179530 | 29672 | 8149 |
| 07:58 | MP96388-B1 | 3605 | 171320 | 29546 | 7459 |
| 08:25 | MP96388-S1 | 3334 | 163380 | 27978 | 6734 |
| 08:31 | MP96388-S2 | 3339 | 163850 | 28601 | 6747 |
| 08:37 | JC28915-6 | 3409 | 165890 | 28542 | 6906 |
| 08:43 | MP96388-SD1 | 3595 | 174510 | 28952 | 7567 |
| 08:49 | ZZZZZZ | 3545 | 173290 | 29840 | 7532 |
| 08:55 | ZZZZZZ | 3614 | 175540 | 29864 | 7796 |
| 09:01 | ZZZZZZ | 3525 | 171460 | 29415 | 7475 |
| 09:07 | MA40471-CCV14 | 3509 | 168790 | 28600 | 7115 |
| 09:13 | MA40471-CCB15 | 3624 | 176640 | 29581 | 7852 |
| 09:20 | ZZZZZZ | 3642 | 175930 | 29354 | 7866 |
| 09:26 | ZZZZZZ | 3640 | 175980 | 29348 | 7908 |
| 09:30 | ZZZZZZ | 3681 | 176820 | 29277 | 7994 |
| 09:35 | ZZZZZZ | 3626 | 174460 | 28861 | 7876 |
| 09:40 | ZZZZZZ | 3616 | 174230 | 29412 | 7865 |
| 09:45 | ZZZZZZ | 3632 | 175530 | 29486 | 7886 |
| 10:20 | MP96398-B1 | No results reported for the elements associated with this internal standard. | | | |

INTERNAL STANDARD SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
Analyst: KS  Run ID: MA40471
Parameters: Zn

| Time | Sample Description | Istd#1 | Istd#2 | Istd#3 | Istd#4 |
|---|---|---|---|---|---|
| 10:24 | ZZZZZZ | 3678 | 178810 | 32513 | 6837 |
| 10:30 | MP96398-MB1 | No results reported for the elements associated with this internal standard. | | | |
| 10:34 | MA40471-CRI4 | 3615 | 175550 | 29977 | 7803 |
| 10:39 | MA40471-CCV15 | 3517 | 169670 | 29087 | 7166 |
| 10:44 | MA40471-CCB16 | 3725 | 180600 | 30336 | 8156 |

R = Reference for ISTD limits.  ! = Outside limits.

LEGEND:

| Istd# | Parameter | Limits |
|---|---|---|
| Istd#1 | Yttrium (2243) | 70-130 % |
| Istd#2 | Yttrium (3600) | 70-130 % |
| Istd#3 | Yttrium (3710) | 70-130 % |
| Istd#4 | Indium | 70-130 % |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: | | | 17:23 | | 17:40 | | 18:54 | | 20:06 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | ICB1 | | CCB1 | | CCB2 | | CCB3 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Aluminum | 200 | 6.8 | anr | | | | | | | |
| Antimony | 6.0 | 1.6 | anr | | | | | | | |
| Arsenic | 3.0 | 1.5 | anr | | | | | | | |
| Barium | 200 | .2 | anr | | | | | | | |
| Beryllium | 1.0 | .05 | anr | | | | | | | |
| Bismuth | 20 | 1.5 | anr | | | | | | | |
| Boron | 100 | 1.1 | | | | | | | | |
| Cadmium | 3.0 | .2 | anr | | | | | | | |
| Calcium | 5000 | 13 | anr | | | | | | | |
| Chromium | 10 | .4 | anr | | | | | | | |
| Cobalt | 50 | .3 | anr | | | | | | | |
| Copper | 10 | .6 | anr | | | | | | | |
| Iron | 100 | 9.7 | anr | | | | | | | |
| Lead | 3.0 | 1.2 | anr | | | | | | | |
| Lithium | 20 | 1.3 | | | | | | | | |
| Magnesium | 5000 | 19 | anr | | | | | | | |
| Manganese | 15 | .1 | anr | | | | | | | |
| Molybdenum | 20 | .3 | | | | | | | | |
| Nickel | 10 | .3 | anr | | | | | | | |
| Palladium | 50 | 1.7 | | | | | | | | |
| Potassium | 10000 | 35 | anr | | | | | | | |
| Selenium | 10 | 1.9 | anr | | | | | | | |
| Silicon | 200 | 5.1 | | | | | | | | |
| Silver | 10 | .5 | anr | | | | | | | |
| Sodium | 10000 | 11 | anr | | | | | | | |
| Sulfur | 50 | 2.2 | anr | | | | | | | |
| Strontium | 10 | .1 | | | | | | | | |
| Thallium | 2.0 | 1.3 | anr | | | | | | | |
| Tin | 10 | .9 | | | | | | | | |
| Titanium | 10 | .4 | | | | | | | | |
| Tungsten | 50 | 2.3 | | | | | | | | |
| Vanadium | 50 | .3 | anr | | | | | | | |
| Zinc | 20 | 1 | 0.0 | <20 | 0.10 | <20 | 0.0 | <20 | 0.0 | <20 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: / Sample ID: | | | 17:23 ICB1 | | 17:40 CCB1 | | 18:54 CCB2 | | 20:06 CCB3 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Zirconium | 10 | .2 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: | | | 21:14 | | 22:20 | | 23:27 | | 00:10 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | CCB4 | | CCB5 | | CCB6 | | CCB7 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Aluminum | 200 | 6.8 | anr | | | | | | | |
| Antimony | 6.0 | 1.6 | anr | | | | | | | |
| Arsenic | 3.0 | 1.5 | anr | | | | | | | |
| Barium | 200 | .2 | anr | | | | | | | |
| Beryllium | 1.0 | .05 | anr | | | | | | | |
| Bismuth | 20 | 1.5 | anr | | | | | | | |
| Boron | 100 | 1.1 | | | | | | | | |
| Cadmium | 3.0 | .2 | anr | | | | | | | |
| Calcium | 5000 | 13 | anr | | | | | | | |
| Chromium | 10 | .4 | anr | | | | | | | |
| Cobalt | 50 | .3 | anr | | | | | | | |
| Copper | 10 | .6 | anr | | | | | | | |
| Iron | 100 | 9.7 | anr | | | | | | | |
| Lead | 3.0 | 1.2 | anr | | | | | | | |
| Lithium | 20 | 1.3 | | | | | | | | |
| Magnesium | 5000 | 19 | anr | | | | | | | |
| Manganese | 15 | .1 | anr | | | | | | | |
| Molybdenum | 20 | .3 | | | | | | | | |
| Nickel | 10 | .3 | anr | | | | | | | |
| Palladium | 50 | 1.7 | | | | | | | | |
| Potassium | 10000 | 35 | anr | | | | | | | |
| Selenium | 10 | 1.9 | anr | | | | | | | |
| Silicon | 200 | 5.1 | | | | | | | | |
| Silver | 10 | .5 | anr | | | | | | | |
| Sodium | 10000 | 11 | anr | | | | | | | |
| Sulfur | 50 | 2.2 | anr | | | | | | | |
| Strontium | 10 | .1 | | | | | | | | |
| Thallium | 2.0 | 1.3 | anr | | | | | | | |
| Tin | 10 | .9 | | | | | | | | |
| Titanium | 10 | .4 | | | | | | | | |
| Tungsten | 50 | 2.3 | | | | | | | | |
| Vanadium | 50 | .3 | anr | | | | | | | |
| Zinc | 20 | 1 | 0.10 | <20 | 0.20 | <20 | 0.20 | <20 | 0.30 | <20 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: / Sample ID: | | | 21:14 CCB4 | | 22:20 CCB5 | | 23:27 CCB6 | | 00:10 CCB7 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Zirconium | 10 | .2 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: | | | 01:23 | | 02:36 | | 03:43 | | 04:50 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | CCB8 | | CCB9 | | CCB10 | | CCB11 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Aluminum | 200 | 6.8 | anr | | | | | | | |
| Antimony | 6.0 | 1.6 | anr | | | | | | | |
| Arsenic | 3.0 | 1.5 | anr | | | | | | | |
| Barium | 200 | .2 | anr | | | | | | | |
| Beryllium | 1.0 | .05 | anr | | | | | | | |
| Bismuth | 20 | 1.5 | anr | | | | | | | |
| Boron | 100 | 1.1 | | | | | | | | |
| Cadmium | 3.0 | .2 | anr | | | | | | | |
| Calcium | 5000 | 13 | anr | | | | | | | |
| Chromium | 10 | .4 | anr | | | | | | | |
| Cobalt | 50 | .3 | anr | | | | | | | |
| Copper | 10 | .6 | anr | | | | | | | |
| Iron | 100 | 9.7 | anr | | | | | | | |
| Lead | 3.0 | 1.2 | anr | | | | | | | |
| Lithium | 20 | 1.3 | | | | | | | | |
| Magnesium | 5000 | 19 | anr | | | | | | | |
| Manganese | 15 | .1 | anr | | | | | | | |
| Molybdenum | 20 | .3 | | | | | | | | |
| Nickel | 10 | .3 | anr | | | | | | | |
| Palladium | 50 | 1.7 | | | | | | | | |
| Potassium | 10000 | 35 | anr | | | | | | | |
| Selenium | 10 | 1.9 | anr | | | | | | | |
| Silicon | 200 | 5.1 | | | | | | | | |
| Silver | 10 | .5 | anr | | | | | | | |
| Sodium | 10000 | 11 | anr | | | | | | | |
| Sulfur | 50 | 2.2 | anr | | | | | | | |
| Strontium | 10 | .1 | | | | | | | | |
| Thallium | 2.0 | 1.3 | anr | | | | | | | |
| Tin | 10 | .9 | | | | | | | | |
| Titanium | 10 | .4 | | | | | | | | |
| Tungsten | 50 | 2.3 | | | | | | | | |
| Vanadium | 50 | .3 | anr | | | | | | | |
| Zinc | 20 | 1 | 0.20 | <20 | 0.30 | <20 | 0.50 | <20 | 0.50 | <20 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: | | | 01:23 | | 02:36 | | 03:43 | | 04:50 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | CCB8 | | CCB9 | | CCB10 | | CCB11 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final | raw | final |
| Zirconium | 10 | .2 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: | | | 05:57 | | 07:03 | | 07:46 | |
|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | CCB12 | | CCB13 | | CCB14 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final |
| Aluminum | 200 | 6.8 | anr | | | | | |
| Antimony | 6.0 | 1.6 | anr | | | | | |
| Arsenic | 3.0 | 1.5 | anr | | | | | |
| Barium | 200 | .2 | anr | | | | | |
| Beryllium | 1.0 | .05 | anr | | | | | |
| Bismuth | 20 | 1.5 | anr | | | | | |
| Boron | 100 | 1.1 | | | | | | |
| Cadmium | 3.0 | .2 | anr | | | | | |
| Calcium | 5000 | 13 | anr | | | | | |
| Chromium | 10 | .4 | anr | | | | | |
| Cobalt | 50 | .3 | anr | | | | | |
| Copper | 10 | .6 | anr | | | | | |
| Iron | 100 | 9.7 | anr | | | | | |
| Lead | 3.0 | 1.2 | anr | | | | | |
| Lithium | 20 | 1.3 | | | | | | |
| Magnesium | 5000 | 19 | anr | | | | | |
| Manganese | 15 | .1 | anr | | | | | |
| Molybdenum | 20 | .3 | | | | | | |
| Nickel | 10 | .3 | anr | | | | | |
| Palladium | 50 | 1.7 | | | | | | |
| Potassium | 10000 | 35 | anr | | | | | |
| Selenium | 10 | 1.9 | anr | | | | | |
| Silicon | 200 | 5.1 | | | | | | |
| Silver | 10 | .5 | anr | | | | | |
| Sodium | 10000 | 11 | anr | | | | | |
| Sulfur | 50 | 2.2 | anr | | | | | |
| Strontium | 10 | .1 | | | | | | |
| Thallium | 2.0 | 1.3 | anr | | | | | |
| Tin | 10 | .9 | | | | | | |
| Titanium | 10 | .4 | | | | | | |
| Tungsten | 50 | 2.3 | | | | | | |
| Vanadium | 50 | .3 | anr | | | | | |
| Zinc | 20 | 1 | 0.60 | <20 | -0.10 | <20 | 0.10 | <20 |

BLANK RESULTS SUMMARY
Part 1 - Initial and Continuing Calibration Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: result < RL  Run ID: MA40471  Units: ug/l

| Time: | | | 05:57 | | 07:03 | | 07:46 | |
|---|---|---|---|---|---|---|---|---|
| Sample ID: | | | CCB12 | | CCB13 | | CCB14 | |
| Metal | RL | IDL | raw | final | raw | final | raw | final |
| Zirconium | 10 | .2 | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial Continuing Calibration Check

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 17:28 | |
|---|---|---|---|
| Sample ID: | ICCV | ICCV1 | |
| Metal | True | Results | % Rec |
| Aluminum | anr | | |
| Antimony | anr | | |
| Arsenic | anr | | |
| Barium | anr | | |
| Beryllium | anr | | |
| Bismuth | anr | | |
| Boron | | | |
| Cadmium | anr | | |
| Calcium | anr | | |
| Chromium | anr | | |
| Cobalt | anr | | |
| Copper | anr | | |
| Iron | anr | | |
| Lead | anr | | |
| Lithium | | | |
| Magnesium | anr | | |
| Manganese | anr | | |
| Molybdenum | | | |
| Nickel | anr | | |
| Palladium | | | |
| Potassium | anr | | |
| Selenium | anr | | |
| Silicon | | | |
| Silver | anr | | |
| Sodium | anr | | |
| Sulfur | anr | | |
| Strontium | | | |
| Thallium | anr | | |
| Tin | | | |
| Titanium | | | |
| Tungsten | | | |
| Vanadium | anr | | |
| Zinc | 2000 | 2040 | 102.0 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial Continuing Calibration Check

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| | | | |
|---|---|---|---|
| Time: | | 17:28 | |
| Sample ID: | ICCV | ICCV1 | |
| Metal | True | Results | % Rec |
| Zirconium | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 17:13 | | | 18:48 | | | 20:00 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICV | ICV1 | | CCV | CCV1 | | CCV | CCV2 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | anr | | | | | | | | |
| Antimony | anr | | | | | | | | |
| Arsenic | anr | | | | | | | | |
| Barium | anr | | | | | | | | |
| Beryllium | anr | | | | | | | | |
| Bismuth | anr | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | anr | | | | | | | | |
| Calcium | anr | | | | | | | | |
| Chromium | anr | | | | | | | | |
| Cobalt | anr | | | | | | | | |
| Copper | anr | | | | | | | | |
| Iron | anr | | | | | | | | |
| Lead | anr | | | | | | | | |
| Lithium | | | | | | | | | |
| Magnesium | anr | | | | | | | | |
| Manganese | anr | | | | | | | | |
| Molybdenum | | | | | | | | | |
| Nickel | anr | | | | | | | | |
| Palladium | | | | | | | | | |
| Potassium | anr | | | | | | | | |
| Selenium | anr | | | | | | | | |
| Silicon | | | | | | | | | |
| Silver | anr | | | | | | | | |
| Sodium | anr | | | | | | | | |
| Sulfur | anr | | | | | | | | |
| Strontium | | | | | | | | | |
| Thallium | anr | | | | | | | | |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | anr | | | | | | | | |
| Zinc | 2000 | 2030 | 101.5 | 2000 | 2070 | 103.5 | 2000 | 2050 | 102.5 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 17:13 | | | 18:48 | | | 20:00 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICV | ICV1 | | CCV | CCV1 | | CCV | CCV2 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 21:08 | | | 22:14 | | | 23:21 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CCV | CCV3 | | CCV | CCV4 | | CCV | CCV5 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | anr | | | | | | | | |
| Antimony | anr | | | | | | | | |
| Arsenic | anr | | | | | | | | |
| Barium | anr | | | | | | | | |
| Beryllium | anr | | | | | | | | |
| Bismuth | anr | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | anr | | | | | | | | |
| Calcium | anr | | | | | | | | |
| Chromium | anr | | | | | | | | |
| Cobalt | anr | | | | | | | | |
| Copper | anr | | | | | | | | |
| Iron | anr | | | | | | | | |
| Lead | anr | | | | | | | | |
| Lithium | | | | | | | | | |
| Magnesium | anr | | | | | | | | |
| Manganese | anr | | | | | | | | |
| Molybdenum | | | | | | | | | |
| Nickel | anr | | | | | | | | |
| Palladium | | | | | | | | | |
| Potassium | anr | | | | | | | | |
| Selenium | anr | | | | | | | | |
| Silicon | | | | | | | | | |
| Silver | anr | | | | | | | | |
| Sodium | anr | | | | | | | | |
| Sulfur | anr | | | | | | | | |
| Strontium | | | | | | | | | |
| Thallium | anr | | | | | | | | |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | anr | | | | | | | | |
| Zinc | 2000 | 2060 | 103.0 | 2000 | 2060 | 103.0 | 2000 | 2060 | 103.0 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Time: | | 21:08 | | | 22:14 | | | 23:21 | |
| Sample ID: | CCV | CCV3 | | CCV | CCV4 | | CCV | CCV5 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 00:04 | | | 01:17 | | | 02:30 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CCV | CCV6 | | CCV | CCV7 | | CCV | CCV8 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | anr | | | | | | | | |
| Antimony | anr | | | | | | | | |
| Arsenic | anr | | | | | | | | |
| Barium | anr | | | | | | | | |
| Beryllium | anr | | | | | | | | |
| Bismuth | anr | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | anr | | | | | | | | |
| Calcium | anr | | | | | | | | |
| Chromium | anr | | | | | | | | |
| Cobalt | anr | | | | | | | | |
| Copper | anr | | | | | | | | |
| Iron | anr | | | | | | | | |
| Lead | anr | | | | | | | | |
| Lithium | | | | | | | | | |
| Magnesium | anr | | | | | | | | |
| Manganese | anr | | | | | | | | |
| Molybdenum | | | | | | | | | |
| Nickel | anr | | | | | | | | |
| Palladium | | | | | | | | | |
| Potassium | anr | | | | | | | | |
| Selenium | anr | | | | | | | | |
| Silicon | | | | | | | | | |
| Silver | anr | | | | | | | | |
| Sodium | anr | | | | | | | | |
| Sulfur | anr | | | | | | | | |
| Strontium | | | | | | | | | |
| Thallium | anr | | | | | | | | |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | anr | | | | | | | | |
| Zinc | 2000 | 2050 | 102.5 | 2000 | 2080 | 104.0 | 2000 | 2020 | 101.0 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Time: | | 00:04 | | | 01:17 | | | 02:30 | |
| Sample ID: | CCV | CCV6 | | CCV | CCV7 | | CCV | CCV8 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 03:37 | | | 04:44 | | | 05:51 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CCV | CCV9 | | CCV | CCV10 | | CCV | CCV11 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Aluminum | anr | | | | | | | | |
| Antimony | anr | | | | | | | | |
| Arsenic | anr | | | | | | | | |
| Barium | anr | | | | | | | | |
| Beryllium | anr | | | | | | | | |
| Bismuth | anr | | | | | | | | |
| Boron | | | | | | | | | |
| Cadmium | anr | | | | | | | | |
| Calcium | anr | | | | | | | | |
| Chromium | anr | | | | | | | | |
| Cobalt | anr | | | | | | | | |
| Copper | anr | | | | | | | | |
| Iron | anr | | | | | | | | |
| Lead | anr | | | | | | | | |
| Lithium | | | | | | | | | |
| Magnesium | anr | | | | | | | | |
| Manganese | anr | | | | | | | | |
| Molybdenum | | | | | | | | | |
| Nickel | anr | | | | | | | | |
| Palladium | | | | | | | | | |
| Potassium | anr | | | | | | | | |
| Selenium | anr | | | | | | | | |
| Silicon | | | | | | | | | |
| Silver | anr | | | | | | | | |
| Sodium | anr | | | | | | | | |
| Sulfur | anr | | | | | | | | |
| Strontium | | | | | | | | | |
| Thallium | anr | | | | | | | | |
| Tin | | | | | | | | | |
| Titanium | | | | | | | | | |
| Tungsten | | | | | | | | | |
| Vanadium | anr | | | | | | | | |
| Zinc | 2000 | 2060 | 103.0 | 2000 | 2050 | 102.5 | 2000 | 2040 | 102.0 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | 03:37 | | | 04:44 | | | 05:51 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CCV | CCV9 | | CCV | CCV10 | | CCV | CCV11 | |
| Metal | True | Results | % Rec | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | | |
|---|---|---|---|---|---|---|
| Time: | | 06:57 | | | 07:40 | |
| Sample ID: | CCV | CCV12 | | CCV | CCV13 | |
| Metal | True | Results | % Rec | True | Results | % Rec |
| Aluminum | anr | | | | | |
| Antimony | anr | | | | | |
| Arsenic | anr | | | | | |
| Barium | anr | | | | | |
| Beryllium | anr | | | | | |
| Bismuth | anr | | | | | |
| Boron | | | | | | |
| Cadmium | anr | | | | | |
| Calcium | anr | | | | | |
| Chromium | anr | | | | | |
| Cobalt | anr | | | | | |
| Copper | anr | | | | | |
| Iron | anr | | | | | |
| Lead | anr | | | | | |
| Lithium | | | | | | |
| Magnesium | anr | | | | | |
| Manganese | anr | | | | | |
| Molybdenum | | | | | | |
| Nickel | anr | | | | | |
| Palladium | | | | | | |
| Potassium | anr | | | | | |
| Selenium | anr | | | | | |
| Silicon | | | | | | |
| Silver | anr | | | | | |
| Sodium | anr | | | | | |
| Sulfur | anr | | | | | |
| Strontium | | | | | | |
| Thallium | anr | | | | | |
| Tin | | | | | | |
| Titanium | | | | | | |
| Tungsten | | | | | | |
| Vanadium | anr | | | | | |
| Zinc | 2000 | 2070 | 103.5 | 2000 | 2060 | 103.0 |

CALIBRATION CHECK STANDARDS SUMMARY
Initial and Continuing Calibration Checks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 95 to 105 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | | |
|---|---|---|---|---|---|---|
| Time: | | 06:57 | | | 07:40 | |
| Sample ID: | CCV | CCV12 | | CCV | CCV13 | |
| Metal | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

HIGH STANDARD CHECK SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | | |
|---|---|---|---|---|---|---|
| Time: | | 18:17 | | | 18:23 | |
| Sample ID: | HSTD | HSTD1 | | HSTD | HSTD2 | |
| Metal | True | Results | % Rec | True | Results | % Rec |
| Aluminum | | | | | | |
| Antimony | anr | | | | | |
| Arsenic | anr | | | | | |
| Barium | anr | | | | | |
| Beryllium | anr | | | | | |
| Bismuth | anr | | | | | |
| Boron | | | | | | |
| Cadmium | anr | | | | | |
| Calcium | | | | | | |
| Chromium | anr | | | | | |
| Cobalt | anr | | | | | |
| Copper | anr | | | | | |
| Iron | | | | | | |
| Lead | anr | | | | | |
| Lithium | | | | | | |
| Magnesium | | | | | | |
| Manganese | anr | | | | | |
| Molybdenum | | | | | | |
| Nickel | anr | | | | | |
| Palladium | | | | | | |
| Potassium | | | | | | |
| Selenium | anr | | | | | |
| Silicon | | | | | | |
| Silver | anr | | | | | |
| Sodium | | | | | | |
| Sulfur | anr | | | | | |
| Strontium | | | | | | |
| Thallium | anr | | | | | |
| Tin | | | | | | |
| Titanium | | | | | | |
| Tungsten | | | | | | |
| Vanadium | anr | | | | | |
| Zinc | 5000 | 5210 | 104.2 | | | |

HIGH STANDARD CHECK SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 90 to 110 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | | |
|---|---|---|---|---|---|---|
| Time: | | 18:17 | | | 18:23 | |
| Sample ID: | HSTD | HSTD1 | | HSTD | HSTD2 | |
| Metal | True | Results | % Rec | True | Results | % Rec |
| Zirconium | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 17:47 | | 17:53 | | 17:59 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRI1 | | CRID1 | | CRIA1 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 200 | 500 | 100 | anr | | | | | |
| Antimony | 6.0 | 20 | 3.0 | anr | | | | | |
| Arsenic | 8.0 | 20 | 3.0 | anr | | | | | |
| Barium | 200 | | 4.0 | anr | | | | | |
| Beryllium | 2.0 | | 1.0 | anr | | | | | |
| Bismuth | 20 | | | anr | | | | | |
| Boron | 100 | | 10 | | | | | | |
| Cadmium | 3.0 | | 1.0 | anr | | | | | |
| Calcium | 5000 | 2000 | 1000 | anr | | | | | |
| Chromium | 10 | | 2.0 | anr | | | | | |
| Cobalt | 50 | | 3.0 | anr | | | | | |
| Copper | 10 | | 2.0 | anr | | | | | |
| Iron | 100 | 500 | | anr | | | | | |
| Lead | 3.0 | 20 | 2.5 | anr | | | | | |
| Lithium | 20 | | | | | | | | |
| Magnesium | 5000 | 2000 | 100 | anr | | | | | |
| Manganese | 15 | | 3.0 | anr | | | | | |
| Molybdenum | 20 | | | | | | | | |
| Nickel | 10 | | 4.0 | anr | | | | | |
| Palladium | 50 | | | | | | | | |
| Potassium | 5000 | | 2000 | anr | | | | | |
| Selenium | 10 | 20 | 5.0 | anr | | | | | |
| Silicon | 200 | | | | | | | | |
| Silver | 5.0 | | 2.0 | anr | | | | | |
| Sodium | 5000 | | 1000 | anr | | | | | |
| Sulfur | 50 | | | anr | | | | | |
| Strontium | 10 | | | | | | | | |
| Thallium | 10 | | 2.0 | anr | | | | | |
| Tin | 10 | | | | | | | | |
| Titanium | 10 | | | | | | | | |
| Tungsten | 50 | | | | | | | | |
| Vanadium | 50 | | 2.0 | anr | | | | | |
| Zinc | 20 | | 10 | 21.8 | 109.0 | 10.4 | 104.0 | | |

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 17:47 | | 17:53 | | 17:59 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRI1 | | CRID1 | | CRIA1 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | 10 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 19:00 | | 23:34 | | 23:40 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRID2 | | CRID3 | | CRI2 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 200 | 500 | 100 | anr | | | | | |
| Antimony | 6.0 | 20 | 3.0 | anr | | | | | |
| Arsenic | 8.0 | 20 | 3.0 | anr | | | | | |
| Barium | 200 | | 4.0 | anr | | | | | |
| Beryllium | 2.0 | | 1.0 | anr | | | | | |
| Bismuth | 20 | | | | | | | | |
| Boron | 100 | | 10 | | | | | | |
| Cadmium | 3.0 | | 1.0 | anr | | | | | |
| Calcium | 5000 | 2000 | 1000 | anr | | | | | |
| Chromium | 10 | | 2.0 | anr | | | | | |
| Cobalt | 50 | | 3.0 | anr | | | | | |
| Copper | 10 | | 2.0 | anr | | | | | |
| Iron | 100 | 500 | | | | | | | |
| Lead | 3.0 | 20 | 2.5 | anr | | | | | |
| Lithium | 20 | | | | | | | | |
| Magnesium | 5000 | 2000 | 100 | anr | | | | | |
| Manganese | 15 | | 3.0 | anr | | | | | |
| Molybdenum | 20 | | | | | | | | |
| Nickel | 10 | | 4.0 | anr | | | | | |
| Palladium | 50 | | | | | | | | |
| Potassium | 5000 | | 2000 | anr | | | | | |
| Selenium | 10 | 20 | 5.0 | anr | | | | | |
| Silicon | 200 | | | | | | | | |
| Silver | 5.0 | | 2.0 | anr | | | | | |
| Sodium | 5000 | | 1000 | anr | | | | | |
| Sulfur | 50 | | | | | | | | |
| Strontium | 10 | | | | | | | | |
| Thallium | 10 | | 2.0 | anr | | | | | |
| Tin | 10 | | | | | | | | |
| Titanium | 10 | | | | | | | | |
| Tungsten | 50 | | | | | | | | |
| Vanadium | 50 | | 2.0 | anr | | | | | |
| Zinc | 20 | | 10 | 10.5 | 105.0 | 10.5 | 105.0 | 22.3 | 111.5 |

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 19:00 | | 23:34 | | 23:40 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRID2 | | CRID3 | | CRI2 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | 10 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 23:46 | | 07:09 | | 07:15 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRIA2 | | CRI3 | | CRID4 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 200 | 500 | 100 | anr | | | | | |
| Antimony | 6.0 | 20 | 3.0 | anr | | | | | |
| Arsenic | 8.0 | 20 | 3.0 | anr | | | | | |
| Barium | 200 | | 4.0 | | | | | | |
| Beryllium | 2.0 | | 1.0 | | | | | | |
| Bismuth | 20 | | | | | | | | |
| Boron | 100 | | 10 | | | | | | |
| Cadmium | 3.0 | | 1.0 | | | | | | |
| Calcium | 5000 | 2000 | 1000 | anr | | | | | |
| Chromium | 10 | | 2.0 | | | | | | |
| Cobalt | 50 | | 3.0 | | | | | | |
| Copper | 10 | | 2.0 | | | | | | |
| Iron | 100 | 500 | | anr | | | | | |
| Lead | 3.0 | 20 | 2.5 | anr | | | | | |
| Lithium | 20 | | | | | | | | |
| Magnesium | 5000 | 2000 | 100 | anr | | | | | |
| Manganese | 15 | | 3.0 | | | | | | |
| Molybdenum | 20 | | | | | | | | |
| Nickel | 10 | | 4.0 | | | | | | |
| Palladium | 50 | | | | | | | | |
| Potassium | 5000 | | 2000 | | | | | | |
| Selenium | 10 | 20 | 5.0 | anr | | | | | |
| Silicon | 200 | | | | | | | | |
| Silver | 5.0 | | 2.0 | | | | | | |
| Sodium | 5000 | | 1000 | | | | | | |
| Sulfur | 50 | | | | | | | | |
| Strontium | 10 | | | | | | | | |
| Thallium | 10 | | 2.0 | | | | | | |
| Tin | 10 | | | | | | | | |
| Titanium | 10 | | | | | | | | |
| Tungsten | 50 | | | | | | | | |
| Vanadium | 50 | | 2.0 | | | | | | |
| Zinc | 20 | | 10 | | | 21.9 | 109.5 | 10.5 | 105.0 |

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 23:46 | | 07:09 | | 07:15 | |
|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRIA2 | | CRI3 | | CRID4 | |
| Metal | True | True | True | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | 10 | | | | | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | | 07:21 | |
|---|---|---|---|---|---|
| Sample ID: | CRI | CRIA | CRID | CRIA3 | |
| Metal | True | True | True | Results | % Rec |
| Aluminum | 200 | 500 | 100 | anr | |
| Antimony | 6.0 | 20 | 3.0 | anr | |
| Arsenic | 8.0 | 20 | 3.0 | anr | |
| Barium | 200 | | 4.0 | | |
| Beryllium | 2.0 | | 1.0 | | |
| Bismuth | 20 | | | | |
| Boron | 100 | | 10 | | |
| Cadmium | 3.0 | | 1.0 | | |
| Calcium | 5000 | 2000 | 1000 | anr | |
| Chromium | 10 | | 2.0 | | |
| Cobalt | 50 | | 3.0 | | |
| Copper | 10 | | 2.0 | | |
| Iron | 100 | 500 | | anr | |
| Lead | 3.0 | 20 | 2.5 | anr | |
| Lithium | 20 | | | | |
| Magnesium | 5000 | 2000 | 100 | anr | |
| Manganese | 15 | | 3.0 | | |
| Molybdenum | 20 | | | | |
| Nickel | 10 | | 4.0 | | |
| Palladium | 50 | | | | |
| Potassium | 5000 | | 2000 | | |
| Selenium | 10 | 20 | 5.0 | anr | |
| Silicon | 200 | | | | |
| Silver | 5.0 | | 2.0 | | |
| Sodium | 5000 | | 1000 | | |
| Sulfur | 50 | | | | |
| Strontium | 10 | | | | |
| Thallium | 10 | | 2.0 | | |
| Tin | 10 | | | | |
| Titanium | 10 | | | | |
| Tungsten | 50 | | | | |
| Vanadium | 50 | | 2.0 | | |
| Zinc | 20 | | 10 | | |

LOW CALIBRATION CHECK STANDARDS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 70 to 130 % Recovery  Run ID: MA40471  Units: ug/l

| | | | | | |
|---|---|---|---|---|---|
| Time: | | | | 07:21 | |
| Sample ID: | CRI | CRIA | CRID | CRIA3 | |
| Metal | True | True | True | Results | % Rec |
| Zirconium | 10 | | | | |

(*) Outside of QC limits
(anr) Analyte not requested

INTERFERING ELEMENT CHECK STANDARDS SUMMARY
Part 1 - ICSA and ICSAB Standards

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 80 to 120 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | 18:05 | | 18:11 | | 23:52 | | 23:58 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICSA | ICSAB | ICSA1 | | ICSAB1 | | ICSA2 | | ICSAB2 | |
| Metal | True | True | Results | % Rec | Results | % Rec | Results | % Rec | Results | % Rec |
| Aluminum | 500000 | 500000 | 487000 | 97.4 | 476000 | 95.2 | 483000 | 96.6 | 474000 | 94.8 |
| Antimony | | 1000 | -1.5 | | 987 | 98.7 | 0.10 | | 976 | 97.6 |
| Arsenic | | 1000 | 0.90 | | 1020 | 102.0 | 1.4 | | 1010 | 101.0 |
| Barium | | 500 | -0.80 | | 495 | 99.0 | -1.0 | | 500 | 100.0 |
| Beryllium | | 500 | -0.50 | | 480 | 96.0 | -0.50 | | 479 | 95.8 |
| Bismuth | | 500 | -2.7 | | 509 | 101.8 | -1.7 | | 506 | 101.2 |
| Boron | | 500 | -1.9 | | 472 | 94.4 | -2.3 | | 471 | 94.2 |
| Cadmium | | 1000 | -0.80 | | 1030 | 103.0 | -0.50 | | 1030 | 103.0 |
| Calcium | 400000 | 400000 | 370000 | 92.5 | 360000 | 90.0 | 368000 | 92.0 | 354000 | 88.5 |
| Chromium | | 500 | -1.4 | | 494 | 98.8 | -2.2 | | 489 | 97.8 |
| Cobalt | | 500 | 1.5 | | 473 | 94.6 | 1.3 | | 477 | 95.4 |
| Copper | | 500 | 6.6 | | 513 | 102.6 | 6.1 | | 513 | 102.6 |
| Iron | 200000 | 200000 | 183000 | 91.5 | 180000 | 90.0 | 180000 | 90.0 | 176000 | 88.0 |
| Lead | | 1000 | 3.6 | | 943 | 94.3 | -0.20 | | 938 | 93.8 |
| Lithium | | 500 | -19 | | 528 | 105.6 | -19 | | 536 | 107.2 |
| Magnesium | 500000 | 500000 | 489000 | 97.8 | 478000 | 95.6 | 484000 | 96.8 | 472000 | 94.4 |
| Manganese | | 500 | -0.20 | | 498 | 99.6 | 0.40 | | 499 | 99.8 |
| Molybdenum | | 500 | -1.1 | | 473 | 94.6 | -1.5 | | 469 | 93.8 |
| Nickel | | 1000 | 0.0 | | 972 | 97.2 | -0.10 | | 968 | 96.8 |
| Palladium | | 500 | 0.60 | | 529 | 105.8 | -1.5 | | 536 | 107.2 |
| Potassium | | | 99.8 | | 90.6 | | 163 | | 138 | |
| Selenium | | 1000 | 5.8 | | 978 | 97.8 | 5.2 | | 974 | 97.4 |
| Silicon | | 500 | 23.9 | | 524 | 104.8 | 25.0 | | 522 | 104.4 |
| Silver | | 1000 | -0.10 | | 1000 | 100.0 | 4.1 | | 994 | 99.4 |
| Sodium | | | -4.4 | | 13.3 | | 28.9 | | 33.5 | |
| Sulfur | | 500 | 41.9 | | 509 | 101.8 | 39.1 | | 518 | 103.6 |
| Strontium | | 500 | 5.4 | | 498 | 99.6 | 6.0 | | 503 | 100.6 |
| Thallium | | 1000 | -3.1 | | 979 | 97.9 | 0.10 | | 988 | 98.8 |
| Tin | | 500 | -9.7 | | 458 | 91.6 | -9.4 | | 458 | 91.6 |
| Titanium | | 500 | -2.9 | | 486 | 97.2 | -3.0 | | 483 | 96.6 |
| Tungsten | | 500 | 4.8 | | 475 | 95.0 | 4.5 | | 469 | 93.8 |
| Vanadium | | 500 | -0.20 | | 479 | 95.8 | -0.60 | | 471 | 94.2 |
| Zinc | | 1000 | -0.70 | | 951 | 95.1 | -0.10 | | 958 | 95.8 |

INTERFERING ELEMENT CHECK STANDARDS SUMMARY
Part 1 - ICSA and ICSAB Standards

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 80 to 120 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | 18:05 | | 18:11 | | 23:52 | | 23:58 | |
|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID: | ICSA | ICSAB | ICSA1 | | ICSAB1 | | ICSA2 | | ICSAB2 | |
| Metal | True | True | Results | % Rec | Results | % Rec | Results | % Rec | Results | % Rec |
| Zirconium | | 500 | -2.4 | | 482 | 96.4 | -2.4 | | 482 | 96.4 |

(*) Outside of QC limits
(anr) Analyte not requested

INTERFERING ELEMENT CHECK STANDARDS SUMMARY
Part 1 - ICSA and ICSAB Standards

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 80 to 120 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | 07:27 | | 07:33 | |
|---|---|---|---|---|---|---|
| Sample ID: | ICSA | ICSAB | ICSA3 | | ICSAB3 | |
| Metal | True | True | Results | % Rec | Results | % Rec |
| Aluminum | 500000 | 500000 | 481000 | 96.2 | 471000 | 94.2 |
| Antimony | | 1000 | -1.7 | | 959 | 95.9 |
| Arsenic | | 1000 | 1.2 | | 988 | 98.8 |
| Barium | | 500 | -1.0 | | 491 | 98.2 |
| Beryllium | | 500 | -0.50 | | 459 | 91.8 |
| Bismuth | | 500 | -1.2 | | 494 | 98.8 |
| Boron | | 500 | -3.1 | | 460 | 92.0 |
| Cadmium | | 1000 | -0.70 | | 1010 | 101.0 |
| Calcium | 400000 | 400000 | 359000 | 89.8 | 351000 | 87.8 |
| Chromium | | 500 | -1.6 | | 489 | 97.8 |
| Cobalt | | 500 | 1.3 | | 466 | 93.2 |
| Copper | | 500 | 5.6 | | 503 | 100.6 |
| Iron | 200000 | 200000 | 173000 | 86.5 | 169000 | 84.5 |
| Lead | | 1000 | 0.20 | | 930 | 93.0 |
| Lithium | | 500 | -18 | | 528 | 105.6 |
| Magnesium | 500000 | 500000 | 470000 | 94.0 | 456000 | 91.2 |
| Manganese | | 500 | -0.50 | | 493 | 98.6 |
| Molybdenum | | 500 | -1.2 | | 462 | 92.4 |
| Nickel | | 1000 | 0.20 | | 957 | 95.7 |
| Palladium | | 500 | -0.70 | | 523 | 104.6 |
| Potassium | | | 151 | | 180 | |
| Selenium | | 1000 | 2.3 | | 952 | 95.2 |
| Silicon | | 500 | 23.7 | | 510 | 102.0 |
| Silver | | 1000 | -1.3 | | 985 | 98.5 |
| Sodium | | | -11 | | -3.6 | |
| Sulfur | | 500 | 33.9 | | 496 | 99.2 |
| Strontium | | 500 | 5.8 | | 494 | 98.8 |
| Thallium | | 1000 | -0.70 | | 957 | 95.7 |
| Tin | | 500 | -8.9 | | 450 | 90.0 |
| Titanium | | 500 | -2.9 | | 480 | 96.0 |
| Tungsten | | 500 | 4.0 | | 462 | 92.4 |
| Vanadium | | 500 | -0.20 | | 471 | 94.2 |
| Zinc | | 1000 | -0.10 | | 945 | 94.5 |

INTERFERING ELEMENT CHECK STANDARDS SUMMARY
Part 1 - ICSA and ICSAB Standards

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: SD100616M2.ICP  Date Analyzed: 10/06/16  Methods: EPA 200.7, SW846 6010C
QC Limits: 80 to 120 % Recovery  Run ID: MA40471  Units: ug/l

| Time: | | | 07:27 | | 07:33 | |
|---|---|---|---|---|---|---|
| Sample ID: | ICSA | ICSAB | ICSA3 | | ICSAB3 | |
| Metal | True | True | Results | % Rec | Results | % Rec |
| Zirconium | | 500 | -2.6 | | 476 | 95.2 |

(*) Outside of QC limits
(anr) Analyte not requested

BLANK RESULTS SUMMARY
Part 2 - Method Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373
Matrix Type: SOLID

Methods: SW846 6010C
Units: mg/kg

Prep Date: 10/05/16

| Metal | RL | IDL | MDL | MB raw | final |
|---|---|---|---|---|---|
| Aluminum | 50 | .68 | 2 | 0.68 | <50 |
| Antimony | 2.0 | .12 | .29 | 0.020 | <2.0 |
| Arsenic | 2.0 | .15 | .21 | 0.15 | <2.0 |
| Barium | 20 | .02 | .081 | 0.12 | <20 |
| Beryllium | 0.20 | .005 | .022 | -0.010 | <0.20 |
| Bismuth | 2.0 | .15 | .24 | | |
| Boron | 10 | .11 | .45 | | |
| Cadmium | 0.50 | .02 | .05 | -0.010 | <0.50 |
| Calcium | 500 | .82 | 1.9 | 14.2 | <500 |
| Chromium | 1.0 | .04 | .12 | 0.060 | <1.0 |
| Cobalt | 5.0 | .02 | .059 | -0.010 | <5.0 |
| Copper | 2.5 | .06 | .22 | 0.44 | <2.5 |
| Iron | 50 | .89 | .79 | 2.2 | <50 |
| Lead | 2.0 | .1 | .22 | 0.050 | <2.0 |
| Lithium | 2.0 | .13 | .45 | | |
| Magnesium | 500 | 1.9 | 5.9 | -0.39 | <500 |
| Manganese | 1.5 | .01 | .036 | 0.050 | <1.5 |
| Molybdenum | 2.0 | .03 | .081 | | |
| Nickel | 4.0 | .03 | .076 | 0.050 | <4.0 |
| Palladium | 5.0 | .17 | .47 | | |
| Potassium | 1000 | 3.5 | 18 | -5.2 | <1000 |
| Selenium | 2.0 | .19 | .46 | -0.15 | <2.0 |
| Silicon | 20 | .26 | 3.7 | | |
| Silver | 0.50 | .05 | .099 | -0.040 | <0.50 |
| Sodium | 1000 | 1.1 | 3.9 | 3.4 | <1000 |
| Strontium | 1.0 | .01 | .024 | | |
| Sulfur | 5.0 | .22 | .59 | | |
| Thallium | 1.0 | .12 | .4 | -0.030 | <1.0 |
| Tin | 5.0 | .05 | .53 | | |
| Titanium | 1.0 | .04 | .13 | | |
| Tungsten | 5.0 | .11 | .33 | | |
| Vanadium | 5.0 | .03 | .083 | 0.050 | <5.0 |
| Zinc | 5.0 | .1 | .22 | 3.2 | <5.0 (a) |

BLANK RESULTS SUMMARY
Part 2 - Method Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373 Methods: SW846 6010C
Matrix Type: SOLID Units: mg/kg

Prep Date: 10/05/16

| Metal | RL | IDL | MDL | MB raw | final |
|---|---|---|---|---|---|
| Zirconium | 2.0 | .02 | .13 | | |

Associated samples MP96373: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(anr) Analyte not requested
(a) All reported results >10x MB value or with RL> 2X of this value.

MATRIX SPIKE AND DUPLICATE RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373
Matrix Type: SOLID

Methods: SW846 6010C
Units: mg/kg

Prep Date: 10/05/16

| Metal | JC28910-1 Original | MS | Spikelot MPSPK1 | % Rec | QC Limits |
|---|---|---|---|---|---|
| Aluminum | 376 | 3450 | 2540 | 121.2 | 75-125 |
| Antimony | 0.14 | 186 | 203 | 91.6 | 75-125 |
| Arsenic | 0.45 | 190 | 203 | 93.4 | 75-125 |
| Barium | 1.8 | 199 | 203 | 97.2 | 75-125 |
| Beryllium | 0.0 | 196 | 203 | 96.6 | 75-125 |
| Bismuth | | | | | |
| Boron | | | | | |
| Cadmium | 0.030 | 191 | 203 | 94.1 | 75-125 |
| Calcium | 25.6 | 2550 | 2540 | 99.5 | 75-125 |
| Chromium | 1.7 | 191 | 203 | 93.3 | 75-125 |
| Cobalt | 0.081 | 190 | 203 | 93.6 | 75-125 |
| Copper | 0.37 | 192 | 203 | 94.4 | 75-125 |
| Iron | 641 | 3180 | 2540 | 100.1 | 75-125 |
| Lead | 0.90 | 191 | 203 | 93.7 | 75-125 |
| Lithium | | | | | |
| Magnesium | 0.0 | 2540 | 2540 | 100.1 | 75-125 |
| Manganese | 1.8 | 192 | 203 | 93.7 | 75-125 |
| Molybdenum | anr | | | | |
| Nickel | 0.23 | 187 | 203 | 92.0 | 75-125 |
| Palladium | | | | | |
| Potassium | 13.4 | 2580 | 2540 | 101.2 | 75-125 |
| Selenium | 0.0 | 188 | 203 | 92.6 | 75-125 |
| Silicon | | | | | |
| Silver | 0.0 | 23.8 | 25.4 | 93.8 | 75-125 |
| Sodium | 8.1 | 2540 | 2540 | 99.8 | 75-125 |
| Strontium | | | | | |
| Sulfur | | | | | |
| Thallium | 0.0 | 196 | 203 | 96.6 | 75-125 |
| Tin | | | | | |
| Titanium | | | | | |
| Tungsten | | | | | |
| Vanadium | 1.4 | 192 | 203 | 93.9 | 75-125 |
| Zinc | 1.0 | 197 | 203 | 96.6 | 75-125 |

MATRIX SPIKE AND DUPLICATE RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373 Methods: SW846 6010C
Matrix Type: SOLID Units: mg/kg

Prep Date: 10/05/16

| Metal | JC28910-1 Original MS | Spikelot MPSPK1 | % Rec | QC Limits |
|---|---|---|---|---|
| Zirconium | | | | |

Associated samples MP96373: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(N) Matrix Spike Rec. outside of QC limits
(anr) Analyte not requested

MATRIX SPIKE AND DUPLICATE RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373
Matrix Type: SOLID

Methods: SW846 6010C
Units: mg/kg

Prep Date: 10/05/16

| Metal | JC28910-1 Original | MSD | Spikelot MPSPK1 | % Rec | MSD RPD | QC Limit |
|---|---|---|---|---|---|---|
| Aluminum | 376 | 3410 | 2610 | 116.1 | 1.2 | 20 |
| Antimony | 0.14 | 190 | 209 | 90.8 | 2.1 | 20 |
| Arsenic | 0.45 | 194 | 209 | 92.5 | 2.1 | 20 |
| Barium | 1.8 | 205 | 209 | 97.2 | 3.0 | 20 |
| Beryllium | 0.0 | 200 | 209 | 95.6 | 2.0 | 20 |
| Bismuth | | | | | | |
| Boron | | | | | | |
| Cadmium | 0.030 | 196 | 209 | 93.7 | 2.6 | 20 |
| Calcium | 25.6 | 2600 | 2610 | 98.5 | 1.9 | 20 |
| Chromium | 1.7 | 196 | 209 | 92.9 | 2.6 | 20 |
| Cobalt | 0.081 | 194 | 209 | 92.7 | 2.1 | 20 |
| Copper | 0.37 | 196 | 209 | 93.5 | 2.1 | 20 |
| Iron | 641 | 3390 | 2610 | 105.2 | 6.4 | 20 |
| Lead | 0.90 | 196 | 209 | 93.3 | 2.6 | 20 |
| Lithium | | | | | | |
| Magnesium | 0.0 | 2610 | 2610 | 99.8 | 2.7 | 20 |
| Manganese | 1.8 | 196 | 209 | 92.9 | 2.1 | 20 |
| Molybdenum | anr | | | | | |
| Nickel | 0.23 | 192 | 209 | 91.7 | 2.6 | 20 |
| Palladium | | | | | | |
| Potassium | 13.4 | 2630 | 2610 | 100.1 | 1.9 | 20 |
| Selenium | 0.0 | 192 | 209 | 91.8 | 2.1 | 20 |
| Silicon | | | | | | |
| Silver | 0.0 | 24.1 | 26.1 | 92.2 | 1.3 | 20 |
| Sodium | 8.1 | 2600 | 2610 | 99.1 | 2.3 | 20 |
| Strontium | | | | | | |
| Sulfur | | | | | | |
| Thallium | 0.0 | 201 | 209 | 96.1 | 2.5 | 20 |
| Tin | | | | | | |
| Titanium | | | | | | |
| Tungsten | | | | | | |
| Vanadium | 1.4 | 197 | 209 | 93.5 | 2.6 | 20 |
| Zinc | 1.0 | 201 | 209 | 95.6 | 2.0 | 20 |

MATRIX SPIKE AND DUPLICATE RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373 Methods: SW846 6010C
Matrix Type: SOLID Units: mg/kg

Prep Date: 10/05/16

| Metal | JC28910-1 Original | MSD | Spikelot MPSPK1 | % Rec | MSD RPD | QC Limit |
|---|---|---|---|---|---|---|
| Zirconium | | | | | | |

Associated samples MP96373: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(N) Matrix Spike Rec. outside of QC limits
(anr) Analyte not requested

SPIKE BLANK AND LAB CONTROL SAMPLE SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373
Matrix Type: SOLID

Methods: SW846 6010C
Units: mg/kg

Prep Date: 10/05/16

| Metal | BSP Result | Spikelot MPSPK1 | % Rec | QC Limits |
|---|---|---|---|---|
| Aluminum | 2270 | 2450 | 92.6 | 80-120 |
| Antimony | 176 | 196 | 89.8 | 80-120 |
| Arsenic | 175 | 196 | 89.3 | 80-120 |
| Barium | 179 | 196 | 91.3 | 80-120 |
| Beryllium | 178 | 196 | 90.8 | 80-120 |
| Bismuth | | | | |
| Boron | | | | |
| Cadmium | 177 | 196 | 90.3 | 80-120 |
| Calcium | 2310 | 2450 | 94.2 | 80-120 |
| Chromium | 171 | 196 | 87.2 | 80-120 |
| Cobalt | 173 | 196 | 88.2 | 80-120 |
| Copper | 175 | 196 | 89.3 | 80-120 |
| Iron | 2350 | 2450 | 95.9 | 80-120 |
| Lead | 174 | 196 | 88.7 | 80-120 |
| Lithium | | | | |
| Magnesium | 2320 | 2450 | 94.7 | 80-120 |
| Manganese | 174 | 196 | 88.7 | 80-120 |
| Molybdenum | anr | | | |
| Nickel | 170 | 196 | 86.7 | 80-120 |
| Palladium | | | | |
| Potassium | 2300 | 2450 | 93.8 | 80-120 |
| Selenium | 173 | 196 | 88.2 | 80-120 |
| Silicon | | | | |
| Silver | 21.8 | 24.5 | 88.9 | 80-120 |
| Sodium | 2320 | 2450 | 94.7 | 80-120 |
| Strontium | | | | |
| Sulfur | | | | |
| Thallium | 181 | 196 | 92.3 | 80-120 |
| Tin | | | | |
| Titanium | | | | |
| Tungsten | | | | |
| Vanadium | 173 | 196 | 88.2 | 80-120 |
| Zinc | 180 | 196 | 91.8 | 80-120 |

SPIKE BLANK AND LAB CONTROL SAMPLE SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373
Matrix Type: SOLID

Methods: SW846 6010C
Units: mg/kg

Prep Date: 10/05/16

| Metal | BSP Result | Spikelot MPSPK1 | % Rec | QC Limits |
|---|---|---|---|---|
| Zirconium | | | | |

Associated samples MP96373: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(anr) Analyte not requested

SERIAL DILUTION RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373
Matrix Type: SOLID

Methods: SW846 6010C
Units: ug/l

Prep Date: 10/05/16

| Metal | JC28910-1 Original | SDL 1:5 | %DIF | QC Limits |
|---|---|---|---|---|
| Aluminum | 3710 | 3620 | 2.4 | 0-10 |
| Antimony | 1.40 | 0.00 | 100.0(a) | 0-10 |
| Arsenic | 4.40 | 9.00 | 104.5(a) | 0-10 |
| Barium | 17.3 | 19.9 | 15.0 (a) | 0-10 |
| Beryllium | 0.00 | 0.00 | NC | 0-10 |
| Bismuth | | | | |
| Boron | | | | |
| Cadmium | 0.300 | 0.00 | 100.0(a) | 0-10 |
| Calcium | 252 | 357 | 41.7 (a) | 0-10 |
| Chromium | 16.3 | 20.1 | 23.3 (a) | 0-10 |
| Cobalt | 0.800 | 0.00 | 100.0(a) | 0-10 |
| Copper | 3.60 | 0.00 | 100.0(a) | 0-10 |
| Iron | 6320 | 6300 | 0.3 | 0-10 |
| Lead | 8.90 | 10.5 | 18.0 (a) | 0-10 |
| Lithium | | | | |
| Magnesium | 0.00 | 0.00 | NC | 0-10 |
| Manganese | 17.7 | 18.0 | 1.7 | 0-10 |
| Molybdenum | anr | | | |
| Nickel | 2.30 | 0.00 | 100.0(a) | 0-10 |
| Palladium | | | | |
| Potassium | 133 | 0.00 | 100.0(a) | 0-10 |
| Selenium | 0.00 | 0.00 | NC | 0-10 |
| Silicon | | | | |
| Silver | 0.00 | 0.00 | NC | 0-10 |
| Sodium | 80.2 | 117 | 46.0 (a) | 0-10 |
| Strontium | | | | |
| Sulfur | | | | |
| Thallium | 0.00 | 0.00 | NC | 0-10 |
| Tin | | | | |
| Titanium | | | | |
| Tungsten | | | | |
| Vanadium | 14.1 | 15.6 | 10.6 (a) | 0-10 |
| Zinc | 10.1 | 13.3 | 31.7*(b) | 0-10 |

SERIAL DILUTION RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96373 Methods: SW846 6010C
Matrix Type: SOLID Units: ug/l

Prep Date: 10/05/16

| Metal | JC28910-1 Original | SDL 1:5 | %DIF | QC Limits |
|---|---|---|---|---|
| Zirconium | | | | |

Associated samples MP96373: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(anr) Analyte not requested
(a) Percent difference acceptable due to low initial sample concentration (< 50 times IDL).
(b) Serial dilution indicates possible matrix interference.

BLANK RESULTS SUMMARY
Part 2 - Method Blanks

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96393 Methods: SW846 7471B
Matrix Type: SOLID Units: mg/kg

Prep Date: 10/06/16

| Metal | RL | IDL | MDL | MB raw | final |
|---|---|---|---|---|---|
| Mercury | 0.033 | .0065 | .0053 | -0.0019 | <0.033 |

Associated samples MP96393: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(anr) Analyte not requested

MATRIX SPIKE AND DUPLICATE RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96393 Methods: SW846 7471B
Matrix Type: SOLID Units: mg/kg

Prep Date: 10/06/16

| Metal | JC28910-1 Original | MS | Spikelot HGPWS1 | % Rec | QC Limits |
|---|---|---|---|---|---|
| Mercury | 0.0 | 0.33 | 0.322 | 102.6 | 80-120 |

Associated samples MP96393: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(N) Matrix Spike Rec. outside of QC limits
(anr) Analyte not requested

MATRIX SPIKE AND DUPLICATE RESULTS SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96393 Methods: SW846 7471B
Matrix Type: SOLID Units: mg/kg

Prep Date: 10/06/16

| Metal | JC28910-1 Original | MSD | Spikelot HGPWS1 | % Rec | MSD RPD | QC Limit |
|---|---|---|---|---|---|---|
| Mercury | 0.0 | 0.35 | 0.337 | 103.9 | 5.9 | 20 |

Associated samples MP96393: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(N) Matrix Spike Rec. outside of QC limits
(anr) Analyte not requested

SPIKE BLANK AND LAB CONTROL SAMPLE SUMMARY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

QC Batch ID: MP96393
Matrix Type: SOLID

Methods: SW846 7471B
Units: mg/kg

Prep Date: 10/06/16

| Metal | BSP Result | Spikelot HGPWS1 | % Rec | QC Limits |
|---|---|---|---|---|
| Mercury | 0.37 | 0.333 | 111.1 | 80-120 |

Associated samples MP96393: JC28902-1

Results < IDL are shown as zero for calculation purposes
(*) Outside of QC limits
(anr) Analyte not requested

# Instrument Detection Limits



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Instrument ID:** LEEMANHG5 **Effective Date:** 09/08/16

| Analyte | IDL ug/l |
|---|---|
| Mercury | .0388 |

The above applies to the following instrument runs:
MA40466

# Instrument Detection Limits



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Instrument ID:** SSTRACE3 **Effective Date:** 10/04/16

| Analyte | IDL ug/l |
|---|---|
| Aluminum | 19.7 |
| Antimony | 1.2 |
| Arsenic | 1.5 |
| Barium | .5 |
| Beryllium | .3 |
| Bismuth | 2.3 |
| Boron | 1.9 |
| Cadmium | .2 |
| Calcium | 8.2 |
| Chromium | .6 |
| Cobalt | .2 |
| Copper | .8 |
| Iron | 8.9 |
| Lead | 1 |
| Lithium | 2.9 |
| Magnesium | 88.1 |
| Manganese | .1 |
| Molybdenum | .3 |
| Nickel | .4 |
| Palladium | 2.1 |
| Potassium | 77.9 |
| Selenium | 2.6 |
| Silicon | 2.6 |
| Silver | .7 |
| Sodium | 19.9 |
| Sulfur | 4.8 |
| Strontium | .2 |
| Thallium | 1.2 |
| Tin | .5 |
| Titanium | .7 |
| Tungsten | 1.1 |
| Vanadium | .5 |
| Yttrium | 5 |
| Zinc | .1 |
| Zirconium | .3 |

The above applies to the following instrument runs:
MA40457

# Instrument Detection Limits



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Instrument ID:** SSTRACE4 **Effective Date:** 09/02/16

| Analyte | IDL ug/l |
|---|---|
| Aluminum | 6.8 |
| Antimony | 1.6 |
| Arsenic | 1.5 |
| Barium | .2 |
| Beryllium | .05 |
| Bismuth | 1.5 |
| Boron | 1.1 |
| Cadmium | .2 |
| Calcium | 12.6 |
| Chromium | .4 |
| Cobalt | .3 |
| Copper | .6 |
| Iron | 9.7 |
| Lead | 1.2 |
| Lithium | 1.3 |
| Magnesium | 19.2 |
| Manganese | .1 |
| Molybdenum | .3 |
| Nickel | .3 |
| Palladium | 1.7 |
| Potassium | 35.1 |
| Selenium | 1.9 |
| Silicon | 5.1 |
| Silver | .5 |
| Sodium | 11 |
| Sulfur | 2.2 |
| Strontium | .1 |
| Thallium | 1.3 |
| Tin | .9 |
| Titanium | .4 |
| Tungsten | 2.3 |
| Vanadium | .3 |
| Zinc | 1 |
| Zirconium | .2 |

The above applies to the following instrument runs:
MA40471

# Instrument Linear Ranges



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Instrument ID:** LEEMANHG5 **Effective Date:** 05/13/13

| Analyte | Linear Range ug/l |
|---|---|
| Mercury | 5 |

The above applies to the following instrument runs:
MA40466

# Instrument Linear Ranges



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Instrument ID:** SSTRACE3 **Effective Date:** 12/09/15

| Analyte | Linear Range ug/l |
|---|---|
| Aluminum | 600000 |
| Antimony | 10000 |
| Arsenic | 10000 |
| Barium | 10000 |
| Beryllium | 10000 |
| Bismuth | 10000 |
| Boron | 10000 |
| Cadmium | 10000 |
| Calcium | 300000 |
| Chromium | 10000 |
| Cobalt | 10000 |
| Copper | 10000 |
| Iron | 300000 |
| Lead | 10000 |
| Lithium | 10000 |
| Magnesium | 600000 |
| Manganese | 10000 |
| Molybdenum | 10000 |
| Nickel | 10000 |
| Palladium | 10000 |
| Potassium | 300000 |
| Selenium | 10000 |
| Silicon | 50000 |
| Silver | 1250 |
| Sodium | 300000 |
| Sulfur | 100000 |
| Strontium | 10000 |
| Thallium | 10000 |
| Tin | 10000 |
| Titanium | 10000 |
| Tungsten | 10000 |
| Vanadium | 10000 |
| Zinc | 10000 |
| Zirconium | 10000 |

The above applies to the following instrument runs:
MA40457

# Instrument Linear Ranges



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Instrument ID:** SSTRACE4 **Effective Date:** 12/09/15

| Analyte | Linear Range ug/l |
|---|---|
| Aluminum | 600000 |
| Antimony | 10000 |
| Arsenic | 10000 |
| Barium | 10000 |
| Beryllium | 10000 |
| Bismuth | 10000 |
| Boron | 10000 |
| Cadmium | 10000 |
| Calcium | 300000 |
| Chromium | 10000 |
| Cobalt | 10000 |
| Copper | 10000 |
| Iron | 300000 |
| Lead | 10000 |
| Lithium | 10000 |
| Magnesium | 600000 |
| Manganese | 10000 |
| Molybdenum | 10000 |
| Nickel | 10000 |
| Palladium | 10000 |
| Potassium | 300000 |
| Selenium | 10000 |
| Silicon | 50000 |
| Silver | 1250 |
| Sodium | 300000 |
| Sulfur | 100000 |
| Strontium | 10000 |
| Thallium | 10000 |
| Tin | 10000 |
| Titanium | 10000 |
| Tungsten | 10000 |
| Vanadium | 10000 |
| Zinc | 10000 |
| Zirconium | 10000 |

The above applies to the following instrument runs:
MA40471

SGS ACCUTEST New Jersey

Section 10

## General Chemistry

# QC Data Summaries

Includes the following where applicable:

- Method Blank and Blank Spike Summaries
- Duplicate Summaries
- Matrix Spike Summaries
- Instrument Runlogs/QC
- Percent Solids Raw Data Summary

METHOD BLANK AND SPIKE RESULTS SUMMARY
GENERAL CHEMISTRY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

| Analyte | Batch ID | RL | MB Result | Units | Spike Amount | BSP Result | BSP %Recov | QC Limits |
|---|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | GP574/GN53097 | 0.40 | 0.0 | mg/kg | 40 | 34.4 | 86.0 | 80-120% |
| Chromium, Hexavalent | GP574/GN53097 | | | mg/kg | 1260 | 1110 | 88.4 | 80-120% |
| Chromium, Hexavalent | GP574/GN53097 | | | mg/kg | 551 | 471 | 75.7 | 71-95% |
| Chromium, Hexavalent | GP648/GN53231 | 0.40 | 0.0 | mg/kg | 40 | 40.9 | 102.3 | 80-120% |
| Chromium, Hexavalent | GP648/GN53231 | | | mg/kg | 952 | 842 | 88.4 | 80-120% |
| Chromium, Hexavalent | GP648/GN53231 | | | mg/kg | 551 | 487 | 88.4 | 71-95% |
| Cyanide | GP585/GN53120 | 0.24 | 0.0 | mg/kg | 1 | 0.997 | 99.7 | 90-110% |

Associated Samples:
Batch GP574: JC28902-1
Batch GP585: JC28902-1
Batch GP648: JC28902-1R
(*) Outside of QC limits

DUPLICATE RESULTS SUMMARY
GENERAL CHEMISTRY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

| Analyte | Batch ID | QC Sample | Units | Original Result | DUP Result | RPD | QC Limits |
|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | GP574/GN53097 | JC28902-1 | mg/kg | 0.0 | 0.18 | 200.0(a) | 0-20% |
| Chromium, Hexavalent | GP648/GN53231 | JC28902-1R | mg/kg | 0.37 | 0.19 | 64.3(a) | 0-20% |
| Cyanide | GP585/GN53120 | JC28906-1 | mg/kg | 0.092 | 0.080 | 14.0 | 0-21% |
| Redox Potential Vs H2 | GN52967 | JC28819-1 | mv | 335 | 339 | 1.2 | 0-18% |
| pH | GN52968 | JC28819-1 | su | 7.77 | 7.90 | 1.7 | 0-5% |

Associated Samples:
Batch GP574: JC28902-1
Batch GP585: JC28902-1
Batch GP648: JC28902-1R
Batch GN52967: JC28902-1
Batch GN52968: JC28902-1
(*) Outside of QC limits
(a) RPD acceptable due to low duplicate and sample concentrations.

MATRIX SPIKE RESULTS SUMMARY
GENERAL CHEMISTRY

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

| Analyte | Batch ID | QC Sample | Units | Original Result | Spike Amount | MS Result | %Rec | QC Limits |
|---|---|---|---|---|---|---|---|---|
| Chromium, Hexavalent | GP574/GN53097 | JC28902-1 | mg/kg | 0.0 | 45.2 | 3.0 | 6.6N(a) | 75-125% |
| Chromium, Hexavalent | GP574/GN53097 | JC28902-1 | mg/kg | 0.0 | 860 | 1150 | 133.7N(b) | 75-125% |
| Chromium, Hexavalent | GP648/GN53231 | JC28902-1R | mg/kg | 0.37 | 46.6 | 1.1 | 1.6N(c) | 75-125% |
| Chromium, Hexavalent | GP648/GN53231 | JC28902-1R | mg/kg | 0.37 | 1010 | 1.7 | 0.1N(b) | 75-125% |
| Cyanide | GP585/GN53120 | JC28906-1 | mg/kg | 0.092 | 0.947 | 0.20 | 11.4N(d) | 21-163% |

Associated Samples:
Batch GP574: JC28902-1
Batch GP585: JC28902-1
Batch GP648: JC28902-1R
(*) Outside of QC limits
(N) Matrix Spike Rec. outside of QC limits
(a) Soluble XCR matrix spike recovery indicates possible matrix interference. Good post spike recovery (102%) on this sample.
(b) Insoluble XCR matrix spike recovery indicates possible matrix interference. See additional comments on soluble matrix spike recovery.
(c) Soluble XCR matrix spike recovery indicates possible matrix interference. Good post spike recovery (97.2%) on this sample.
(d) Spike recovery indicates possible matrix interference.

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: 816100701.TXT  Date Analyzed: 10/07/16  Methods: SW846 3060A/7199
Analyst: TT  Run ID: GN53097
Parameters: Chromium, Hexavalent

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 08:48 | GN53097-STD1 | 1 | | STDA |
| 08:56 | GN53097-STD2 | 1 | | STDB |
| 09:04 | GN53097-STD3 | 1 | | STDC |
| 09:12 | GN53097-STD4 | 1 | | STDD |
| 09:20 | GN53097-STD5 | 1 | | STDE |
| 09:29 | GN53097-CCV1 | 1 | | |
| 09:37 | GN53097-CCB1 | 1 | | |
| 09:45 | GP574-MB1 | 1 | | |
| 09:53 | GP574-MB1 | 1 | | |
| 10:00 | GP574-B1 | 4 | | |
| 10:08 | GP574-B1 | 4 | | |
| 10:16 | GP574-B2 | 130 | | |
| 10:24 | GP574-B2 | 130 | | |
| 10:32 | GP574-LC1 | 1 | | |
| 10:40 | GP574-LC1 | 10 | | |
| 10:48 | GP574-LC1 | 10 | | corrected for 97.3% sol |
| 10:56 | JC28902-1 | 1 | | |
| 11:04 | JC28902-1 | 1 | | |
| 11:12 | GP574-S1 | 1 | | |
| 11:20 | GP574-S1 | 1 | | |
| 11:27 | GP574-S2 | 1 | | |
| 11:35 | GP574-S2 | 1 | | |
| 11:43 | ZZZZZZ | 1 | | |
| 11:51 | ZZZZZZ | 1 | | |
| 11:59 | GP574-PS1 | 4 | | |
| 12:07 | GP574-PS1 | 4 | | |
| 12:15 | GN53097-CCV2 | 1 | | |
| 12:23 | GN53097-CCB2 | 1 | | |
| 12:31 | GP574-S2 | 100 | | |
| 12:39 | GP574-S2 | 100 | | |
| 12:47 | GN53097-CCV3 | 1 | | |
| 12:55 | GN53097-CCB3 | 1 | | |
| 13:23 | GP574-D1 | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: 816100701.TXT  Date Analyzed: 10/07/16  Methods: SW846 3060A/7199
Analyst: TT  Run ID: GN53097
Parameters: Chromium, Hexavalent

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 13:31 | GP574-D1 | 1 | | |
| 13:57 | GN53097-CCV4 | 1 | | |
| 14:04 | GN53097-CCB4 | 1 | | |

Refer to raw data for calibration curve and standards.

Instrument QC Summary
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: 816100701.TXT  Date Analyzed: 10/07/16  Methods: SW846 3060A/7199
Run ID: GN53097  Units: mg/l

| Sample Number | Parameter | Result | RL | IDL/MDL | True Value | % Recov. | QC Limits |
|---|---|---|---|---|---|---|---|
| GN53097-CCV1 | Chromium, Hexavalent | 0.24 | 0.010 | 0.0028 | .25 | 96.0 | 90-110 |
| GN53097-CCB1 | Chromium, Hexavalent | 0.0028 U | 0.010 | 0.0028 | | | |
| GN53097-CCV2 | Chromium, Hexavalent | 0.24 | 0.010 | 0.0028 | .25 | 96.0 | 90-110 |
| GN53097-CCB2 | Chromium, Hexavalent | 0.0028 U | 0.010 | 0.0028 | | | |
| GN53097-CCV3 | Chromium, Hexavalent | 0.24 | 0.010 | 0.0028 | .25 | 96.0 | 90-110 |
| GN53097-CCB3 | Chromium, Hexavalent | 0.0028 U | 0.010 | 0.0028 | | | |
| GN53097-CCV4 | Chromium, Hexavalent | 0.23 | 0.010 | 0.0028 | .25 | 92.0 | 90-110 |
| GN53097-CCB4 | Chromium, Hexavalent | 0.0028 U | 0.010 | 0.0028 | | | |

(!) Outside of QC limits

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: E100716W1.CN Date Analyzed: 10/07/16 Methods: EPA 335.4/LACHAT, SW846 9012B/LACHAT, SW846 CHAP
Analyst: YZ Run ID: GN53120
Parameters: Cyanide

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 09:36 | GN53120-STD1 | 1 | | STDA |
| 09:37 | GN53120-STD2 | 1 | | STDB |
| 09:39 | GN53120-STD3 | 1 | | STDC |
| 09:40 | GN53120-STD4 | 1 | | STDD |
| 09:41 | GN53120-STD5 | 1 | | STDE |
| 09:43 | GN53120-STD6 | 1 | | STDF |
| 09:44 | GN53120-STD7 | 1 | | STDG |
| 09:45 | GN53120-ICV1 | 1 | | |
| 09:47 | GN53120-ICB1 | 1 | | |
| 09:48 | GN53120-CCV1 | 1 | | |
| 09:50 | GN53120-CCB1 | 1 | | |
| 09:51 | GP561-MB2 | 1 | | |
| 09:52 | GP561-B2 | 1 | | |
| 09:54 | ZZZZZZ | 1 | | |
| 09:55 | ZZZZZZ | 1 | | |
| 09:56 | ZZZZZZ | 1 | | |
| 09:58 | ZZZZZZ | 1 | | |
| 09:59 | GP585-MB1 | 1 | | |
| 10:00 | GP585-B1 | 1 | | |
| 10:02 | GP585-S1 | 1 | | |
| 10:03 | GP585-S2 | 1 | | |
| 10:05 | GN53120-CCV2 | 1 | | |
| 10:06 | GN53120-CCB2 | 1 | | |
| 10:07 | GP585-D1 | 1 | | |
| 10:09 | JC28902-1 | 1 | | |
| 10:10 | ZZZZZZ | 1 | | |
| 10:11 | JC28906-1 | 1 | | (sample used for QC only; not part of login JC28902) |
| 10:13 | JC28906-2 | 1 | | (sample used for QC only; not part of login JC28902) |
| 10:14 | ZZZZZZ | 1 | | |
| 10:16 | ZZZZZZ | 1 | | |
| 10:17 | ZZZZZZ | 1 | | |
| 10:18 | ZZZZZZ | 1 | | |
| 10:20 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: E100716W1.CN Date Analyzed: 10/07/16 Methods: EPA 335.4/LACHAT, SW846 9012B/LACHAT, SW846 CHAP
Analyst: YZ Run ID: GN53120
Parameters: Cyanide

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 10:21 | GN53120-CCV3 | 1 | | |
| 10:22 | GN53120-CCB3 | 1 | | |
| 10:24 | ZZZZZZ | 1 | | |
| 10:25 | ZZZZZZ | 1 | | |
| 10:26 | ZZZZZZ | 1 | | |
| 10:28 | ZZZZZZ | 1 | | |
| 10:29 | ZZZZZZ | 1 | | |
| 10:31 | ZZZZZZ | 1 | | |
| 10:32 | GP586-MB1 | 1 | | |
| 10:33 | GP586-B1 | 1 | | |
| 10:35 | GP586-S1 | 1 | | |
| 10:36 | GP586-S2 | 1 | | |
| 10:37 | GN53120-CCV4 | 1 | | |
| 10:39 | GN53120-CCB4 | 1 | | |
| 10:40 | GP586-D1 | 1 | | |
| 10:41 | JC28920-2 | 1 | | (sample used for QC only; not part of login JC28902) |
| 10:43 | JC28920-4 | 1 | | (sample used for QC only; not part of login JC28902) |
| 10:44 | ZZZZZZ | 1 | | |
| 10:46 | ZZZZZZ | 1 | | |
| 10:47 | ZZZZZZ | 1 | | |
| 10:48 | ZZZZZZ | 1 | | |
| 10:50 | ZZZZZZ | 1 | | |
| 10:51 | ZZZZZZ | 1 | | |
| 10:52 | ZZZZZZ | 1 | | |
| 10:54 | GN53120-CCV5 | 1 | | |
| 10:55 | GN53120-CCB5 | 1 | | |
| 10:57 | ZZZZZZ | 1 | | |
| 10:58 | ZZZZZZ | 1 | | |
| 10:59 | ZZZZZZ | 1 | | |
| 11:01 | ZZZZZZ | 1 | | |
| 11:02 | ZZZZZZ | 1 | | |
| 11:03 | ZZZZZZ | 1 | | |
| 11:05 | ZZZZZZ | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: E100716W1.CN Date Analyzed: 10/07/16 Methods: EPA 335.4/LACHAT, SW846 9012B/LACHAT, SW846 CHAP
Analyst: YZ Run ID: GN53120
Parameters: Cyanide

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 11:06 | GP588-MB1 | 1 | | |
| 11:08 | GP588-B1 | 1 | | |
| 11:09 | GP588-D1 | 1 | | |
| 11:10 | GN53120-CCV6 | 1 | | |
| 11:12 | GN53120-CCB6 | 1 | | |
| 11:13 | LA26022-2A | 1 | | (sample used for QC only; not part of login JC28902) |
| 11:14 | ZZZZZZ | 1 | | |
| 11:16 | ZZZZZZ | 1 | | |
| 11:17 | ZZZZZZ | 1 | | |
| 11:18 | ZZZZZZ | 1 | | |
| 11:20 | ZZZZZZ | 1 | | |
| 11:21 | ZZZZZZ | 1 | | |
| 11:23 | ZZZZZZ | 1 | | |
| 11:24 | ZZZZZZ | 1 | | |
| 11:25 | ZZZZZZ | 1 | | |
| 11:27 | GN53120-CCV7 | 1 | | |
| 11:28 | GN53120-CCB7 | 1 | | |
| 11:29 | ZZZZZZ | 1 | | |
| 11:31 | ZZZZZZ | 1 | | |
| 11:32 | ZZZZZZ | 1 | | |
| 11:33 | ZZZZZZ | 1 | | |
| 11:35 | ZZZZZZ | 1 | | |
| 11:36 | ZZZZZZ | 1 | | |
| 11:38 | ZZZZZZ | 1 | | |
| 11:39 | GP488-MB3 | 1 | | |
| 11:40 | GP488-B3 | 1 | | |
| 11:42 | ZZZZZZ | 1 | | |
| 11:43 | GN53120-CCV8 | 1 | | |
| 11:44 | GN53120-CCB8 | 1 | | |
| 11:46 | ZZZZZZ | 1 | | |
| 11:47 | ZZZZZZ | 1 | | |
| 11:49 | ZZZZZZ | 1 | | |
| 11:50 | GP589-MB1 | 1 | | |

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: E100716W1.CN Date Analyzed: 10/07/16 Methods: EPA 335.4/LACHAT, SW846 9012B/LACHAT, SW846 CHAP
Analyst: YZ Run ID: GN53120
Parameters: Cyanide

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 11:51 | GP589-B1 | 1 | | |
| 11:53 | GP589-D1 | 1 | | |
| 11:54 | LA26009-3 | 1 | | (sample used for QC only; not part of login JC28902) |
| 11:55 | ZZZZZZ | 1 | | |
| 11:57 | ZZZZZZ | 1 | | |
| 12:00 | GN53120-CCV9 | 1 | | |
| 12:01 | GN53120-CCB9 | 1 | | |

Refer to raw data for calibration curve and standards.

Instrument QC Summary
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: E100716W1.CN  Date Analyzed: 10/07/16  Methods: EPA 335.4/LACHAT, SW846 9012B/LACHAT, SW846 CHAP
Run ID: GN53120  Units: mg/l

| Sample Number | Parameter | Result | RL | IDL/MDL | True Value | % Recov. | QC Limits |
|---|---|---|---|---|---|---|---|
| GN53120-ICV1 | Cyanide | 0.32 | 0.010 | 0.0027 | .3 | 106.7 | 90-110 |
| GN53120-ICB1 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV1 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB1 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV2 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB2 | Cyanide | -0.0027 | 0.010 | 0.0027 | | | |
| GN53120-CCV3 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB3 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV4 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB4 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV5 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB5 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV6 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB6 | Cyanide | -0.0040 | 0.010 | 0.0027 | | | |
| GN53120-CCV7 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB7 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV8 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB8 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |
| GN53120-CCV9 | Cyanide | 0.41 | 0.010 | 0.0027 | .4 | 102.5 | 90-110 |
| GN53120-CCB9 | Cyanide | 0.0027 U | 0.010 | 0.0027 | | | |

(!) Outside of QC limits

SGS Accutest Instrument Runlog
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: 816101002.TXT  Date Analyzed: 10/10/16  Methods: SW846 3060A/7199
Analyst: AT  Run ID: GN53231
Parameters: Chromium, Hexavalent

| Time | Sample Description | Dilution Factor | PS Recov | Comments |
|---|---|---|---|---|
| 17:32 | GN53231-STD1 | 1 | | STDA |
| 17:40 | GN53231-STD2 | 1 | | STDB |
| 17:48 | GN53231-STD3 | 1 | | STDC |
| 17:56 | GN53231-STD4 | 1 | | STDD |
| 18:04 | GN53231-STD5 | 1 | | STDE |
| 18:12 | GN53231-CCV1 | 1 | | |
| 18:20 | GN53231-CCB1 | 1 | | |
| 18:28 | GP648-MB1 | 1 | | |
| 18:36 | GP648-MB1 | 1 | | |
| 18:43 | GP648-B1 | 4 | | |
| 18:51 | GP648-B1 | 4 | | |
| 18:59 | GP648-B2 | 100 | | |
| 19:07 | GP648-B2 | 100 | | |
| 19:15 | GP648-LC1 | 1 | | |
| 19:23 | GP648-LC1 | 10 | | corrected for 97.3%sol |
| 19:31 | GP648-LC1 | 10 | | |
| 19:39 | JC28902-1R | 1 | | |
| 19:47 | JC28902-1R | 1 | | |
| 19:55 | GP648-S1 | 1 | | |
| 20:03 | GP648-S1 | 1 | | |
| 20:10 | GP648-S2 | 1 | | |
| 20:18 | GP648-S2 | 1 | | |
| 20:26 | GP648-D1 | 1 | | |
| 20:34 | GP648-D1 | 1 | | |
| 20:54 | GP648-PS1 | 4 | | |
| 21:02 | GP648-PS1 | 4 | | |
| 21:10 | GN53231-CCV2 | 1 | | |
| 21:18 | GN53231-CCB2 | 1 | | |

Refer to raw data for calibration curve and standards.

Instrument QC Summary
Inorganics Analyses

Login Number: JC28902
Account: HWINJM - Honeywell International Inc.
Project: HLANJPR: Study Area 6 Chrome Remedy

File ID: 816101002.TXT  Date Analyzed: 10/10/16  Methods: SW846 3060A/7199
Run ID: GN53231  Units: mg/l

| Sample Number | Parameter | Result | RL | IDL/MDL | True Value | % Recov. | QC Limits |
|---|---|---|---|---|---|---|---|
| GN53231-CCV1 | Chromium, Hexavalent | 0.27 | 0.010 | 0.0028 | .25 | 108.0 | 90-110 |
| GN53231-CCB1 | Chromium, Hexavalent | 0.0028 U | 0.010 | 0.0028 | | | |
| GN53231-CCV2 | Chromium, Hexavalent | 0.27 | 0.010 | 0.0028 | .25 | 108.0 | 90-110 |
| GN53231-CCB2 | Chromium, Hexavalent | 0.0028 U | 0.010 | 0.0028 | | | |

(!) Outside of QC limits

# Percent Solids Raw Data Summary



**Job Number:** JC28902
**Account:** HWINJM Honeywell International Inc.
**Project:** HLANJPR: Study Area 6 Chrome Remedy

**Sample:** JC28902-1 **Analyzed:** 05-OCT-16 by AT **Method:** SM2540 G-97
**ClientID:** WOOLSTON-TS-002

| | | |
|---|---|---|
| Wet Weight (Total) | 26.06 | g |
| Tare Weight | 19.98 | g |
| Dry Weight (Total) | 25.24 | g |
| Solids, Percent | 86.5 | % |

# ATTACHMENT B

# GEOTECHNICAL RESULTS (RUTGERS SOIL TESTING LABORATORY)

RUTGERS
New Jersey Agricultural Experiment Station

**Soil Testing Laboratory**
**Rutgers, The State University**
**ASB II**
**57 US Highway 1 South**
**New Brunswick, NJ 08901-8554**

# Soil Test Report
Lab #: 2016-54830

Entact
Caroline Panico
60 Kellogg St.
(Honeywell SA6)
Jersey City, NJ 07305

cpanico@entact.com
(630)669-4257

**Date Received:** 2016-10-03
**Date Reported:** 2016-10-11

**Sample ID:** Woolston-TS-002

## Results and Interpretations

Sandy Loam


**pH:** 5.94 Moderately acidic; below optimum for many plants but tolerated by acid-loving species.

**Lime Requirement Index:** 7.72

The Lime Requirement Index (LRI) is a measure of the buffering capacity of the soil, its resistance to pH change, and is used to determine the appropriate amount of limestone, when necessary. LRI value near 8.0 indicates low buffering capacity of soil and a lower rate of limestone amendment compared to soil with high buffering capacity (LRI near 7.0).

## Macronutrients (pounds per acre)

| | | |
|---|---|---|
| **Phosphorus:** | 12 | (Below Optimum) |
| **Potassium:** | 42 | (Below Optimum) |
| **Magnesium:** | 520 | (Above Optimum) |
| **Calcium:** | 1397 | (Below Optimum) |




by Mehlich 3 extraction

## Micronutrients (parts per million)

| Zinc(Zn) | Copper(Cu) | Manganese(Mn) | Boron(B) | Iron(Fe) |
|---|---|---|---|---|
| 1.46 (Adequate) | 1.51 (Adequate) | 5.28 (Adequate) | 0.78 (Adequate) | 101.30 (High) |

## Special Tests Results

Soluble Salts- Electrical conductivity= 0.15 mmho/cm

(Satisfactory)

Organic Matter by Carbon Analysis: Organic Matter=5.7%

Very High for Sandy Loam

Gravel Content- Larger than 2mm: 4.3%

Mechanical Analysis- Sand= 73% Silt=13% Clay= 14% Texture: Sandy Loam

USDA sieve analysis of sand fraction:

| Very Coarse | Coarse | Medium | Fine | Very Fine |
|---|---|---|---|---|
| 1-2mm | 0.5-1mm | 0.25-0.5mm | 0.1-0.25mm | 0.05-0.1mm |
| 1.6% | 3.0% | 18.0% | 60.5% | 16.9% |

**Comments:**

**Find Rutgers Cooperative Extension Fact Sheets at www.njaes.rutgers.edu/pubs**

Soil Program 2015
NAPT
Participating Laboratory

**10/19/16 E-mail Transmittal: Response to Email -- 101716 Horizon A Analytical Results 21319**
*(Attachment 15: EME Soils)*

## Graham, Stephanie

**From:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Sent:** Friday, December 09, 2016 10:52 AM
**To:** Graham, Stephanie
**Cc:** Ambrose, David M
**Subject:** FW: Response to Email -- 101716 Horizon A Analytical Results 21319
**Attachments:** EME Topsoil Organic Matter Cert.png

---

**From:** Clifford, Joseph T
**Sent:** Wednesday, October 19, 2016 6:29 PM
**To:** Kim Bell Hosea (k.bell@cea-enviro.com) <k.bell@cea-enviro.com>
**Cc:** Hague, William <william.hague@honeywell.com>; 'Egnaczyk, Steve' <segnaczyk@louisberger.com>; aalcorn@tpmlaw.com; Jeremy.Karpatkin@aporter.com
**Subject:** Response to Email -- 101716 Horizon A Analytical Results 21319

Kim,

EME has confirmed that they needed to increase the % organic matter to meet our site specifications for Horizon A Topsoil. They confirmed that the organic additive used is Sphagnum Peat Moss.
A copy of the supplier's letter certifying that the Peat Moss is also a virgin source material is attached. The analytical and geotechnical data provided in our new Horizon A source data package was run on the actual blended soils with this Peat Moss added.

Per agreed upon protocols going back to the SA7 project implementation, Honeywell provides the full analytical data packages to all parties to demonstrate acceptability of each new source prior to beginning import. Subsequent sample data collected per the frequency identified in the specifications is provided at the end of the project in the final closeout documentation. Honeywell is continuing that process for SA6.

Please let us know if you have any further questions.

Thank you. -Joe

---

**From:** Kim Hosea [mailto:k.hosea@cea-enviro.com]
**Sent:** Monday, October 17, 2016 11:05 AM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Cc:** Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>; Egnaczyk, Steve <segnaczyk@louisberger.com>; Alicia Clark Alcorn <aalcorn@tpmlaw.com>
**Subject:** 101716 Horizon A Analytical Results 21319

Good afternoon Joe –

We have reviewed the New Source of Horizon A Topsoil data for EME and have one question. During the Technical All-Parties pre-call on October 4, you stated that the EME soil was mostly acceptable but might need some amendments with on-site material to meet the required % of organic matter as specified in the 100% design and DC 2014-09-17. The

clean fill certification states that the material has not been comingled with other materials. Please confirm that amending the material was not required or, provide additional information regarding the use of an amendment.

Also, please provide confirmation data for the Horizon A, B, and C soils used on site to date and going forward. Our records contain one set of data each for Horizon C and B dated October 26, 2015, and September 15, 2015, respectively. The data is to be collected on an on-going basis from every 5,000 cubic yards of material brought on-site.

Thank you –

Kim

Kim Bell Hosea
Senior Vice-President
Carpenter Environmental Associates, Inc.
610 County Route 1, Unit 2F
Pine Island, New York 10969

k.hosea@cea-enviro.com
(O) 845-781-4844 ext. 309
(F) 845-782-5591
(M) 862-812-3397

The information in this e-mail is intended only for the use of the designated recipient(s) and may contain confidential and privileged information.
If the reader of this message is not the intended recipient(s), you are hereby notified that you have received this email in error and that any review, dissemination, distribution, or copying of this message is strictly prohibited. If you have received this communication in error, please notify the sender by reply e-mail and destroy all copies of the original message.




This message is the property of Amec Foster Wheeler plc and/or its subsidiaries and/or affiliates and is intended only for the named recipient(s). Its contents (including any attachments) may be confidential, legally privileged or otherwise protected from disclosure by law. Unauthorised use, copying, distribution or disclosure of any of it may be unlawful and is strictly prohibited. We assume no responsibility to persons other than the intended named recipient(s) and do not accept liability for any errors or omissions which are a result of email transmission. If you have received this message in error, please notify us immediately by reply email to the sender and confirm that the original message and any attachments and copies have been destroyed and deleted from your system. This disclaimer applies to any and all messages originating from us and set out above. If you do not wish to receive future unsolicited commercial electronic messages from us, **please forward this email to: unsubscribe@amecfw.com and include "Unsubscribe" in the subject line**. If applicable, you will continue to receive invoices, project communications and similar factual, non-commercial electronic communications.

Please click http://amecfw.com/email-disclaimer for notices and company information in relation to emails originating in the UK, Italy or France.

PARTAC PEAT CORPORATION
ONE KELSEY PARK, GREAT MEADOWS, NEW JERSEY 07838
800-247-BEAM (2326) • 908-637-4191 • FAX 908-637-8421
sales@beamclay.com • sales@partac.com

BEAM CLAY
THE PROFESSIONAL'S CHOICE
... SINCE 1922
www.beamclay.com

Kelsey Park Sod Farms

PARTAC
GOLF COURSE
TOP-DRESSINGS
www.partac.com

October 18, 2016

EME, Inc.
849 Route 539
New Egypt, NJ 08533

Att: Keith Prince

Dear Keith:

This is to certify that our **SPHAGNUM PEAT MOSS** comes from a virgin, non-contaminated source in Maine.

Sincerely yours,

PARTAC PEAT CORPORATION

*Jim*

James C. Kelsey, President

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 16 OF 25**

- **DCBs Applicable to SA-6 South Part 1**
  **(DCB 001 and 003-007.5)**

**FINAL DCB 001 – SURCHARGE INSTRUMENTATION REVISION**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 001 Minor (a)<br>Effective Date: 2/26/14 |
| Project Location: SA-6 NORTH, SA6-SOUTH | Associated RFI: |
| Title: Surcharge Instrumentation Revision | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

Description of Change/Modification:

1. **72 inch force main**. The Surcharge Monitoring Plan (Appendix N of 100% Design Report) has been modified to match the changes in surcharge pile geometry associated with the relocation of the Hydraulic Barrier Wall near the 72" force main. The Barrier wall has been moved to a minimum distance of 25 feet from the centerline of the force main. The surcharge pile has also been reconfigured so that the surcharge will not result in any stress increase on the 72 inch force main. Details of changes to the Design Drawings stemming from the Barrier Wall Relocation are included in DCB-002. Details related to changes to the Surcharge Monitoring Instrumentation are included in this DCB 001.
2. **Station Relocations due to interferences.** In addition to the changes related to the 72 inch force main Amec has relocated some instrument location on both SA6 North and SA-6 South to avoid foundations and traffic routes. Relocated instruments are in the same general area and will serve the same objectives as the original locations.
3. **Form revisions.** Amec has modified several of the reporting forms to allow for direct entry using a tablet application. Templates for the Daily Report Form, Instrument Installation and Monitoring Data Forms are attached.

SUMMARY OF CHANGES

- SA-6 North Area 1 Figure B1
  - Half setups 6 and 8 have been removed due to the reduced footprint of the surcharge pile.
  - Settlement Platforms # 4-10 along the force main have been eliminated - no fill is being placed over the force main and therefore no settlement platforms are required.
  - Survey Points on the FM will be reduced from 3 to 2. Survey Points are no longer required; however, two points will be retained for background information (See Figure B1)
  - 6 Acoustical Sensors have been added along the JCMUA 72" force main. Acoustical Monitoring is not part of Honeywell/Amec's Scope. PVSC/HMM/Pure Technologies will conduct the Acoustical Monitoring. Pure Technology is monitoring the system remotely and will advise PVSC/HMM if there is any noise detected during sheetpile driving and surcharging activities that would be attributable to failure of the wire wrap. Any detected wire breaks will initiate actions per the PVSC Response Plan.
  - Inclinometers. Inclinometers are no longer required however they have been retained as a contingency monitoring measure. Due to the change in role of these instruments a trigger level will no longer be required.
  - Vibration Monitoring. Vibration Monitoring will be conducted during sheetpile driving. HMM concluded that the force main should be able to tolerate accelerations of up to 1.9 in/sec. Honeywell/PVSC have agreed to an Upper Limit of 1 inch/second to provide a Factor of Safety of approximately 2.
- Figures C1 and D1 for SA-6 North
  - Figures have been updated to only show the instrument locations in the specific Area. For example on the original issue Figure C1 included the instrument locations for Area 2 and also the instrument locations for Area 1 and Area 3. In this revision Fig. C1 only shows the Area 2 instrumentation locations.
  - Half setup locations in Figure D1 were relabeled.
- Figures F1, G1 and H1 for SA-6 South
  - Figures have been updated to only show the instrument locations in the specific Area (1-3).
  - Figures have been updated to show changes in instrument locations made to avoid foundations and traffic routes.


| Reason for Change/Modification: | Explanation or Reason: Modified due to changes in surcharge adjacent to the 72" force main |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No<br><br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: The Figures showing instrument locations have also be updated to reflect minor adjustments made in field to avoid conflicts with foundations and traffic routing.<br>Field forms contain the same information. The forms have been reformatted to allow for tablet data entry. | Design Documents Affected:<br>Appendix N: Surcharge Monitoring Plan |


| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |

| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: |
|---|---|
| Samuel G Shallard | |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




SECTION A-A

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| VI-1 | 686123 | 602109 |
| VI-2 | 686029 | 602048 |
| VI-3 | 685960.00 | 602503.63 |
| VI-4 | 685865.62 | 602701.07 |
| FS1 | 685981 | 602115.11 |
| FS2 | 685863.13 | 602450.59 |
| FS3 | 685810.51 | 602689.13 |
| FS4 | 685723.32 | 602722.54 |
| HS1 | 685959.45 | 602413.93 |
| HS2 | 685929.16 | 602333.31 |
| HS3 | 685864.91 | 602293.50 |
| HS4 | 685919.95 | 602491.27 |
| HS5 | 685787.46 | 602414.04 |
| ~~HS6~~ | ~~685784.69~~ | ~~602649.88~~ |
| HS7 | 685695.59 | 602582.07 |
| ~~HS8~~ | ~~685828.15~~ | ~~602795.09~~ |
| HS9 | 685624.48 | 602691.07 |

| | | |
|---|---|---|
| SP1 | 685881.42 | 602204.89 |
| SP2 | 685757.23 | 602415.64 |
| SP3 | 685613.33 | 602662.16 |
| ~~SP4~~ | ~~685953.03~~ | ~~602533.30~~ |
| ~~SP5~~ | ~~685931.28~~ | ~~602578.16~~ |
| ~~SP6~~ | ~~685906.49~~ | ~~602633.51~~ |
| ~~SP7~~ | ~~685886.78~~ | ~~602676.31~~ |
| ~~SP8~~ | ~~685867.20~~ | ~~602721.11~~ |
| ~~SP9~~ | ~~685849.22~~ | ~~602763.68~~ |
| ~~SP10~~ | ~~685833.92~~ | ~~602781.17~~ |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. COMMENCE FILL AT THE SEDIMENTATION BASIN AND WORK TOWARDS THE HACKENSACK RIVER.
5. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
6. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.


| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1-1 | SETTLEMENT MONITORING POINT FULL - SETUP |
| HS-1-1 | SETTLEMENT MONITORING POINT HALF - SETUP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 6) |
| | 72-INCH FM ACOUSTICAL MONITORING POINT |
| SUR MON 1 | 72-INCH FM SURVEY MONITORING POINT |
| | STATION RELOCATED OR ELIMINATED DUE TO SURCHARGE PILE RECONFIGURATION |

0 15 30 60
SCALE IN FEET

Revised/Date: TDD 02/28/14
Checked/Date: SGS 02/28/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 NORTH<br>JERSEY CITY, NEW JERSEY<br>HONEYWELL SITE ID - 37472 | amec | INSTRUMENTATION LOCATION PLAN<br>AREA 1N<br>Project 3480-09-0006<br>Figure B1 |

Z:\Projects\HONEYWELL\JERSEY CITY\Dwg Design-Sht-ASD\ASD\SMR\150 Percent\Figure 1 Surcharge Settling Monitoring Plan - Area 1.dwg Wed, 26 Feb 2014 - 11:15am kary.dickson




| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS5 | 685595 | 602745 |
| FS6 | 685557 | 602880 |
| FS7 | 685445 | 603001 |
| SP11 | 685784 | 602832 |
| SP12 | 685602 | 603057 |
| SP13 | 685683 | 602935 |
| SP16 | 685618 | 602844 |
| SP17 | 685556 | 602977 |
| SP18 | 685563 | 602752 |
| SP19 | 685531 | 602839 |
| SP20 | 685429 | 602978 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\oplus_{VI-2}$ | INCLINOMETER LOCATION |
| $\blacksquare^{FS-1-1}$ | SETTLEMENT MONITORING POINT FULL – SET UP |
| $\square^{HS12}$ | SETTLEMENT MONITORING POINT HALF – SET UP |
| $\boxtimes^{SP12}$ | SETTLEMENT MONITORING PLATFORM |
| $\bigcirc^{RP}$ | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 5) |

Revised/Date: TDD 02/26/14
Checked/Date: SGS 02/28/14

0 15 30 60
SCALE IN FEET

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN
AREA 2N
Project 3480-09-0006
Figure C1

Z:\Projects\Honeywell\Jersey city\Dwg Design-SAS-CAD\Work\180 Percent\Figure 2 Surcharge Settling Monitoring Plan - Area 2.dwg Mon, 31 Mar 2014 - 2:59pm terry.donovan




| SETTLEMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS8 | 685406.37 | 603094.37 |
| FS9 | 685500.70 | 603127.23 |
| FS10 | 685585.02 | 603165.50 |
| FS11 | 685387.04 | 603338.90 |
| HS10 | 685499.90 | 603327.97 |
| HS11 | 685329.97 | 603205.81 |
| HS12 | 685428.53 | 603407.96 |
| HS13 | 685253.14 | 603316.22 |
| SP14 | 685625 | 603120 |
| SP15 | 685568 | 603093 |
| SP21 | 685302.66 | 603197.35 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

| | |
|---|---|
| $\oplus_{I-2}$ | INCLINOMETER LOCATION |
| $\blacksquare^{FS-1-1}$ | SETTLEMENT MONITORING POINT FULL - SET UP |
| $\blacksquare^{HS-1-1}$ | SETTLEMENT MONITORING POINT HALF - SET UP |
| $\boxtimes^{SP12}$ | SETTLEMENT MONITORING PLATFORM |
| $\bigcirc^{RP}$ | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 5) |

0 15 30 60
SCALE IN FEET

Revised/Date: TDD 02/26/14
Checked/Date: SGB 02/26/14

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN
AREA 3N
Project 3480-09-0006
Figure D1

X:\Projects\HONEYWELL\PROJECT CITY\Site Design\~SHE~1\SHEET\SHEET\192 Personal\Figure 3 Surcharge Retrofitting Monitoring Plan - Area 3.dwg Wed, 26 Feb 2014 - 12:19pm tony.simmons




| SETTELMENT MONITORING POINT | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS12 | 685304 | 603419 |
| FS13 | 685207 | 603389 |
| SP22 | 685186 | 603357 |
| SP23 | 685368 | 603473 |
| SP24 | 685357 | 603491 |
| SP25 | 685077 | 603485 |

INCLINOMETER LOCATION

FS12 — SETTLEMENT MONITORING POINT FULL – SET UP

HS12 — SETTLEMENT MONITORING POINT HALF – SET UP

SP12 — SETTLEMENT MONITORING PLATFORM

RP — APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 5)

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. RELOCATE POWER SUPPLY TO PW1 AND PW2 PRIOR TO SURCHARGE.
3. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
4. SURCHARGE PILE TO BE SLOPED TO THE SHED FACE WATER TO THE NORTH.
5. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.

Revised/Date: TDD 02/28/14
Checked/Date: SGS 02/28/14

0 15 30 60
SCALE IN FEET


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec

INSTRUMENTATION LOCATION PLAN
AREA 4N
Project 3480-09-0006
Figure E1

X:\Projects\CHEMICAL\JERSEY CITY\Data Design-SWE-GDR\GDR\SWMP\100 Percent\Figure 4 Surcharge Pad\Log Monitoring Plan - Area 4.dwg Wed, 05 Feb 2014 - 12:55pm tony.dimmon




SECTION A–A

| SETTELMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS–1 | 685276 | 601927 |
| FS–2 | 685324 | 601749 |
| HS–1 | 685597 | 601567 |
| HS–2 | 685511 | 601691 |
| HS–3 | 685422 | 601801 |
| HS–4 | 685313 | 601947 |
| HS–5 | 685480 | 601624 |
| HS–6 | 685519 | 601480 |
| HS–7 | 685413 | 601624 |
| HS–8 | 685204 | 601912 |
| VI–1 | 685624 | 601515 |
| VI–2 | 685580 | 601462 |
| SP–1 | 685568 | 601833 |
| SP–2 | 685411 | 601852 |
| SP–3 | 685277 | 602034 |

NOTES:

1. PRIOR TO SURCHARGING REMOVE SA–7 FENCE AND SA–7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARD ROUTE 440.
4. LOCATION OF SA–7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE AREA 2.

| | |
|---|---|
| VI–2 | INCLINOMETER LOCATION |
| FS–1–1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS–1–1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA–7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

0 20 40 80
SCALE IN FEET

Prepared/Date: TDD 02/28/14
Checked/Date: SGS 02/28/14


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN
AREA 1S
Project 3480-12-0317
Figure F1

Z:\Projects\HONEYWELL\JERSEY CITY\Dwg Design-Data-CAD\CAD\SA6S\Figure - Surcharge Area1 Instrumentation Plan.dwg Wed, 26 Feb 2014 - 9:45am tonyr.dickson




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
4. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-3 | 685147 | 602186 |
| FS-4 | 685000 | 602180 |
| FS-5 | 684747 | 602531 |
| HS-9 | 685226 | 602078 |
| HS-10 | 685015 | 602358 |
| HS-11 | 684873 | 602566 |
| HS-12 | 685122 | 602109 |
| HS-13 | 684729 | 602660 |
| HS-14 | 685108 | 602032 |
| HS-15 | 684880 | 602355 |
| SP-4 | 685192 | 602145 |
| SP-5 | 685065 | 602322 |
| SP-6 | 684932 | 602507 |
| SP-7 | 684732 | 602766 |
| SP-8 | 684728 | 602761 |

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS-1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP-12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

0 20 40 80
SCALE IN FEET

Prepared/Date: TDD 02/28/14
Checked/Date: SGS 02/28/14


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN
AREA 2S
Project 3480-12-0317
Figure G1

Z:\Projects\HONEYWELL\JERSEY CITY\Dwg Design-Build-GDR\GDR\SA6SR\Figure - Surcharge Area6 Instrumentation Plan.dwg Wed, 26 Feb 2014 - 10:57pm tony.dalessandro




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARDS ROUTE 440.
4. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-6 | 684538 | 602919 |
| FS-7 | 684638 | 602751 |
| HS-16 | 684678 | 602808 |
| HS-17 | 684488 | 603027 |
| HS-18 | 684333 | 603198 |
| HS-19 | 684211 | 603276 |
| HS-20 | 684542 | 602775 |
| HS-21 | 684409 | 602931 |
| HS-22 | 684263 | 603093 |

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL – SET UP |
| HS-1 | SETTLEMENT MONITORING POINT HALF – SET UP |
| SP-12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |

0 20 40 80
SCALE IN FEET

Prepared/Date: TDD 02/28/14
Checked/Date: SGB 02/28/14

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

INSTRUMENTATION LOCATION PLAN
AREA 3S
Project 3480-12-0317
Figure H1

J:\Projects\VARICHEM\LA_PROJECT CITY\Dwg Design-SGB-CAD\CAD\LSA3S\Figure - Surcharge Area3 Instrumentation Plan.dwg Wed, 26 Feb 2014 - 10:56am kerry.donovan

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **Report Date** |
| | **Location:** | Jersey City, New Jersey | **Report By** |
| | **Client:** | Honeywell | |

# DAILY FIELD REPORT

## SURCHARGE MONITORING PROGRAM

| General Information | | Today's Areas of Activity | |
|---|---|---|---|
| Active Surcharge Areas | | General Fill Placement Areas | |
| Weather Conditions | | Instrument Reading Areas | |

**FILL PLACEMENT**

**General Fill Placement Locations**

| Area 1N | Area 2N | Area 3N | Area 4N | Sed. Basin |
|---|---|---|---|---|
| | | | | |

| Area 1S | Area 2S | Area 3S |
|---|---|---|
| | | |

**Details of Today's Fill Placement**

| Photos Taken? | 1N | 2N | 3N | 4N | Sed. Basin | 1S | 2S | |
|---|---|---|---|---|---|---|---|---|

| Area 1N | Area 2N | Area 3N | Area 4N | Sed. Basin |
|---|---|---|---|---|
| | | | | |

| Area 1S | Area 2S | Area 3S |
|---|---|---|
| | | |

| Today's Fill Material Description | In-Place Density of Fill (tested) | In-Place Density of Fill (est.) |
|---|---|---|
| | | |

**INSTRUMENT READINGS**

**Today's Instrument Types Read (By Area)**

| Area 1N | Area 2N | Area 3N | Area 4N | Sed. Basin |
|---|---|---|---|---|
| | | | | |

| Area 1S | Area 2S | Area 3S |
|---|---|---|
| | | |

**Instrument Damage/Concerns**

**SLOPE STABILITY/SETTLEMENT OBSERVATIONS**

| Existing Fill Slopes Stable (Y/N) | Excess Settlement (Y/N) |
|---|---|
| | |

**ADDITIONAL NOTES/DISCUSSIONS**

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **SETTLEMENT PLATFORM #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# SETTLEMENT PLATFORM - FIELD DATA SHEET

| **Baseline Location** | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Date/Recorded By:** | |

| **Baseline Elevations** | |
|---|---|
| **Existing Ground Surface Elev.[1,2] (ft):** | |
| **Initial Reference Clamp Elev.[1] (ft):** | |
| **Date/Recorded By:** | |

Survey the Reference Clamp Elevation
BEFORE and AFTER adding riser pipe!

| **Date** | **Recorded by** | **Settlement Platform** | **Fill Placement** | **Notes** |
|---|---|---|---|---|
| | | **Reference Clamp Elevation[1] (ft)** | **Ground Surface Elevation[1,3] (ft)** | **(note when riser pipe is added)** |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Notes:

1. Measure/record elevations to the nearest 0.01 feet.
2. At installation, record existing ground surface elev. at/proximate to the installed platform; for determining fill thickness above existing grade.
3. During surcharge fill placement/monitoring period, record existing ground surface elev. (i.e., top of fill) at/proximate to the installed platform.

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **STANDPIPE PIEZOMETER #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# STANDPIPE PIEZOMETER - INSTALLATION SHEET

| **Baseline Location/Elevation** | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Existing Ground Surface Elev.[1](ft):** | |
| **Initial Top of Riser (TOR) Elev.[1] (ft):** | |
| **Date/Recorded By:** | |

| **Piezometer Construction Details[2]** | | | | |
|---|---|---|---|---|
| **Item** | **Depth** | | **Elevation** | |
| | **Top[2] (ft bgs)** | **Bottom[2] (ft bgs)** | **Top[2] (ft)** | **Bottom[2] (ft)** |
| **Riser:** | (-) | | | |
| **Grout:** | | | | |
| **Bentonite Plug:** | | | | |
| **Sand:** | | | | |
| **Screen:** | | | | |

| **Baseline Readings** | | | |
|---|---|---|---|
| **Date** | **Recorded By** | **Depth to Water[1] (ft btor)** | **Notes** |
| | | | |
| | | | |
| | | | |
| | | | |

Notes:

1. Measure/record elevations and groundwater depths to the nearest 0.01 feet.
2. Measure/record piezometer construction details to the nearest 0.01 feet.

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **SONDEX SYSTEM #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# SONDEX SYSTEM - INSTALLATION DATA SHEET

| **Baseline Survey Location & Elevation** | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Top of Riser (TOR) Elev. (ft):** | |
| **Date/Recorded By:** | |

| **Baseline Depths and Elevations** | | |
|---|---|---|
| **Item** | **Depth (ft bgs)[1]** | **Elevation (ft)[1]** |
| **Riser Stick-Up (ft):** | (-) | **-** |
| **Existing Ground Surface:** | - | |
| **Top O:** | | |
| **Bottom O/Top D:** | | |
| **Bottom D:** | | |
| **GWT:** | | |
| **Bottom of Sondex:** | | |

| **Ring Installation** | | | | | |
|---|---|---|---|---|---|
| **Ring Number** | **Target Depth (ft bgs)[1]** | **Target Stratum** | **Baseline Depth Readings** | | |
| | | | **Reading No. 1 (ft btor)[1]** | **Reading No. 2 (ft btor)[1]** | **Reading No. 3 (ft btor)[1]** |
| 1 | | | | | |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |

Notes: 1. Measure/record to nearest 0.01 feet.

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **MONITORING POINT (STATION) #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# VIBRATING WIRE PIEZOMETERS - INSTALLATION DATA SHEET

| Baseline Locations (VWP Shallow Boring No. 1) | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Ground Elev.:** | |
| **Date/Recorded By:** | |

| Baseline Locations (VWP Shallow Boring No. 2, if applicable) | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Ground Elev.:** | |
| **Date/Recorded By:** | |

| Baseline Locations (VWP Deep/RC Boring, if applicable) | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Ground Elev.:** | |
| **Date/Recorded By:** | |

| Baseline Strata Depths/Elevations | | |
|---|---|---|
| **Item** | **Depth (ft bgs)[1]** | **Elevation (ft)[1,2]** |
| **Existing Ground Surface:** | - | |
| **Top of Stratum O:** | | |
| **Bottom O / Top D:** | | |
| **Bottom of Stratum D:** | | |
| **Top of Stratum RC:** | | |
| **Bottome of Stratum RC:** | | |
| **Groundwater Table** | | |

| VWP Installation Record | | | | | |
|---|---|---|---|---|---|
| **VWP Designation** | **VWP Serial No.** | **Depth (ft bgs)[1]** | **Elevation (ft)[1,2]** | **Stratum** | **VWP Boring No.** |
| | | | | Center O | |
| | | | | Upper D | |
| | | | | Center D | |
| | | | | Lower D | |
| | | | | RC | |


| VWP Baseline Readings | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | **VWP Designation:** | | | | | | | | | | | **Notes** |
| | | **VWP Serial No.:** | | | | | | | | | | | |
| **Date** | **Recorded By:** | **Ground Surface Elev. (ft)[1]** | **Frequency (Hz)** | **Temperature (deg C)** | **Frequency (Hz)** | **Temperature (deg C)** | **Frequency (Hz)** | **Temperature (deg C)** | **Frequency (Hz)** | **Temperature (deg C)** | **Frequency (Hz)** | **Temperature (deg C)** | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

Notes:
1. Measure/record to nearest 0.01 feet.
2. Establish a single/representative baseline ground surface elevation (to the extent practical), based on elevation of associated Settlement Platform and compilation of VWP Borings.

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 South | **Inclinometer #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# INCLINOMETER - INSTALLATION DATA SHEET

| | | | |
|---|---|---|---|
| Existing Grade (ft.): | | Cable No.: | |
| Reference Elevation (ft): | | Cable Length: | |
| Date: | | Readout SN: | |
| Time (start): | | Probe SN: | |
| Time (finish): | | Read By: | |
| Installation Date: | | Datamate File Name: | |




| Stratum | ft bgs |
|---|---|
| Fill | |
| O | |
| D | |
| S1 | |

**Bottom Depth Readings**

| | Initial | Current |
|---|---|---|
| A0 | | |
| A180 | | |
| B0 | | |
| B180 | | |

**Settlement Joint Readings**

Depth to Joint No 1: _____

Depth to Joint No 2: _____

Depth to Joint No 3: _____

Depth to bottom of Inclinometer: _____

**Notes:**

Northing:_____

Easting:_____

A+ Axis Orientation:_____

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **SETTLEMENT PLATFORM #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# SETTLEMENT PLATFORM - FIELD DATA SHEET

| **Baseline Location** | |
|---|---|
| **Northing:** | |
| **Easting:** | |
| **Date/Recorded By:** | |

| **Baseline Elevations** | |
|---|---|
| **Existing Ground Surface Elev.[1,2] (ft):** | |
| **Initial Reference Clamp Elev.[1] (ft):** | |
| **Date/Recorded By:** | |

Survey the Reference Clamp Elevation
BEFORE and AFTER adding riser pipe!

| **Date** | **Recorded by** | **Settlement Platform** | **Fill Placement** | **Notes** |
|---|---|---|---|---|
| | | **Reference Clamp Elevation[1] (ft)** | **Ground Surface Elevation[1,3] (ft)** | **(note when riser pipe is added)** |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Notes:

1. Measure/record elevations to the nearest 0.01 feet.
2. At installation, record existing ground surface elev. at/proximate to the installed platform; for determining fill thickness above existing grade.
3. During surcharge fill placement/monitoring period, record existing ground surface elev. (i.e., top of fill) at/proximate to the installed platform.

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **STANDPIPE PIEZOMETER #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# STANDPIPE PIEZOMETER - FIELD DATA SHEET

| Date | Recorded By | Depth to Water [1] (ft btor) | Riser Added Today? (Yes/No) | Depth to Water [1, 2] (ft btor) | Riser Surveyed? [3] (Yes/No) | Riser Elevation [4] (ft) |
|---|---|---|---|---|---|---|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Notes:

1. Measure/record groundwater depths to the nearest 0.01 feet.
2. If riser is added on this date, re-measure the depth to water after adding riser.
3. **Measure/record TOR elev. periodically.**
4. Measure/record elevations to the nearest 0.01 feet.

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **SONDEX SYSTEM #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# SONDEX SYSTEM - FIELD DATA SHEET

| **Date:** | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| **Recorded By:** | | | | | | | | |
| **Ring Number** | **Depth (ft below top of riser)[1]** | | | | | | | |
| 1 | | | | | | | | |
| 2 | | | | | | | | |
| 3 | | | | | | | | |
| 4 | | | | | | | | |
| 5 | | | | | | | | |
| 6 | | | | | | | | |
| 7 | | | | | | | | |
| 8 | | | | | | | | |
| 9 | | | | | | | | |
| 10 | | | | | | | | |
| 11 | | | | | | | | |
| 12 | | | | | | | | |
| 13 | | | | | | | | |
| 14 | | | | | | | | |
| 15 | | | | | | | | |
| 16 | | | | | | | | |

Notes:

1. Measure/record to nearest 0.01 feet.
2. Note when riser pipe is added.
3. **Take Sondex depth readings immediately BEFORE (all) and AFTER (a few rings) adding riser pipe.**

| | | | |
|---|---|---|---|
| amec | **Project:** | Study Area 6 | **MONITORING POINT (STATION) #** |
| | **Location:** | Jersey City, New Jersey | |
| | **Client:** | Honeywell | |

# VIBRATING WIRE PIEZOMETERS - FIELD DATA SHEET

| **VWP Readings** | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **VWP Designation:** | | | | | | | | | | | | **Notes** |
| **VWP Serial No.:** | | | | | | | | | | | | |
| **Date** | **Recorded By:** | **Frequency (Hz)** | **Temp. (deg C)** | **Frequency (Hz)** | **Temp. (deg C)** | **Frequency (Hz)** | **Temp. (deg C)** | **Frequency (Hz)** | **Temp. (deg C)** | **Frequency (Hz)** | **Temp. (deg C)** | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

**FINAL DCB 003 – SA-6 GROUTED ANGLES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 003 Minor (a)<br>Effective Date: 8/14/13 |
| Project Location: SA6-SOUTH<br>Title: SA-6S grouted angle Sta 0+00 to Sta 18+50 | Associated RFI:<br>☐ Yes, RFI No. ___ ☑ None |
| Contractor (Subcontractor): Entact / JD Fields | Project No.: 3480130377 |

Description of Change/Modification:

Beginning at Sta 0+00 and continuing to Sta18+50 on SA-6 South grouted angle is to be included on the back of the sheetpile wall. Groundwater sampling and analysis for pH has confirmed that the hydraulic barrier seal from Sta 0+00 to Sta 17+80 should be constructed using grouted joints. The design originally presented additional grouting as an option pending pH data from Sta 5+50 to 17+80. pH data has since confirmed that grouting is necessary to Sta 18+50. Drawing G-003, Note HB19 is to be revised to read:

NOTE HB19

"THE AREA INDICATED ON SHEETS S-201 TO S-203 FROM STATION 0+00 TO STATION ~~17+80~~ 18+50 WILL BE SEALED WITH A CEMENT BENTONITE GROUT IN LIEU OF HYDRAULIC SEALANT. THIS PORTION OF THE WALL WILL BE FABRICATED WITH A 2 ½" X 3/8" ANGLE AND ½" HDPE GROUT PIPE FROM THE TOP OF THE INTERLOCK TO THE DEPTH OF STRATUM D SOILS. SEE DRAWING S-203 DETAIL BF AND SPECIFICATION SECTION 02180 FOR ADDITIONAL INFORMATION."

| | |
|---|---|
| Reason for Change/Modification:<br>☑ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: High pH groundwater conditions necessitate grout seal.<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments:<br>• Cost impacts to be determined by Construction Manager<br>• Content has been conveyed to the contractor prior to formal issue of this DCB | Design Documents Affected:<br>Drawing G-003 Note HB19 |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |

(Name / Signature): Samuel G. Ebel Jr.

Does DCB Result in CCO? ☐ Yes (b) ☐No

Date: 5/2/14

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**Memo**

| | | | |
|---|---|---|---|
| Date: | **8/12/2013** | cc: | **John Mojka, Honeywell**<br>**Maria Kaouris, Honeywell**<br>**Joe Clifford**<br>**Steve Mitchell**<br>**Dennis Nagg**<br>**Stu Bills** |
| From: | **Geoff Shallard** | | |
| To: | **Bill Hague, Honeywell** | | |
| Subject: | **Groundwater pH sampling** | | |

Amec collected groundwater pH readings from Study Area 6 North and South along the proposed hydraulic barrier wall alignment at 19 different locations as per the preapproved methodology. The locations and results are included in the attached figure.

Groundwater sampling screens were driven using direct push methodology to the desired depth of 12 feet below ground surface above Stratum D (aka meadow mat) which underlies the fill. From that depth, the outer casing of the drill rod was pulled back to expose a 2.5-foot long stainless steel screen. Utilizing a peristaltic pump, 3/8" poly tubing, and a multi-water quality checker, Horiba U-52, groundwater was purged from the screen and passed over the Horiba U-52 sensors in a flow through cell. Chemical parameters pH, turbidity, specific conductivity, temperature, ORP and DO were monitored and recorded in 5-minute intervals using the Low Flow Stabilization purging procedures as outlined in the New Jersey DEP Field Sampling Procedures Manual, 2005.

Calibration of the Horiba U-52 was performed onsite prior to sampling each day. The U-52 was calibrated for temperature, pH, specific conductivity, ORP, dissolved oxygen, and turbidity according to AMEC calibration Standard Operating Procedure which is based directly on the manufacturer's instructions.

Based on the groundwater pH sample results the hydraulic barriers between stations 0+00 and 5+00 at Study Area 6 North and between stations 0+00 and 18+50 at Study Area 6 South will be sealed with a cement grout as per Hydraulic Barrier Technical Requirements "HB19" in the Chromium Remedy 100% Design Drawings, dated June 2013.

Amec is certified with the NJDEP Office of Quality Assurance to perform field analysis of non-potable water for specific conductance, turbidity, dissolved oxygen, pH and temperature. The above mentioned field work was performed by Amec personnel.

Attachments:
Groundwater sample results (pH) figure

AMEC Environment & Infrastructure, Inc.
511 Congress Street
Portland, ME 04101
Tel 207-775-5401
Fax 207-772-4762
amec.com

GENERAL NOTES

GN1. COORDINATE USE OF SITE WITH HONEYWELL, THE ENGINEER, SITE OWNER, AND THE CURRENT TENANT ON THE SITE.

GN2. CONTRACTOR SHALL VISUALLY INSPECT THE SITE TO ASCERTAIN THE CONDITION IF EXISTING FEATURES AND FAMILIARIZE THEMSELVES WITH THE WORK.

GN3. THE CONTRACTOR SHALL BE RESPONSIBLE TO SECURE ALL NECESSARY PERMITS EXCEPT FOR SPECIFIED PERMITS SECURED BY HONEYWELL AND/OR THE SITE OWNER OR TENANT.

GN4. KNOWN UNDERGROUND UTILITIES AND STRUCTURES ARE SHOWN ON THE DRAWINGS. THE LOCATION OF THESE EXISTING UNDERGROUND UTILITIES AND STRUCTURES SHOULD BE CONSIDERED APPROXIMATE. THEREFORE, PRIOR TO THE COMMENCEMENT OF SITE ACTIVITIES, THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES OR STRUCTURES IN THE AREAS OF WORK (CALL BEFORE YOU DIG: NJ 1 CALL – 1–800–272–1000). IF UTILITIES ARE TO REMAIN IN PLACE, PROVIDE ADEQUATE MEANS OF PROTECTION. THE CONTRACTOR SHALL CONFIRM THAT ANY ABANDONED UTILITY LOCATED WITHIN THE LIMIT OF WORK HAS BEEN ABANDONED IN ACCORDANCE WITH THE REQUIREMENTS OF THE UTILITY OWNER AND THE CITY OF JERSEY CITY.

GN5. ALL SPECIFIED WORK SHALL BE IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS AND ORDINANCES.

GN6. BITUMINOUS PAVEMENT, CURBS, UTILITIES, FENCING AND ALL OTHER ASPECTS OF OFF–SITE FEATURES SHALL BE RESTORED UPON COMPLETION OF THE WORK UNLESS OTHERWISE INDICATED. ON–SITE DISTURBED AREAS SHALL BE FINISHED WITH TOPSOIL AND SEEDED, FINISHED WITH A GRAVEL SURFACE, OR PAVED AS INDICATED. IF SITE REDEVELOPMENT ACTIVITIES ARE SCHEDULED FOR STARTUP WITHIN 30 DAYS OF COMPLETION OF REMEDIAL CONSTRUCTION, ON–SITE AREAS (OUTSIDE NJDOT R.O.W.) INDICATED TO BE PAVED MAY BE FINISHED WITH GRAVEL.

GN7. A DECONTAMINATION PAD SHALL BE PLACED ADJACENT TO THE CURRENT WORK AREA. AS THE AREA OF EXCAVATION CHANGES THE PAD SHALL BE RELOCATED AS REQUIRED.

GN8. CONSTRUCTION WATER MANAGEMENT AND DEWATERING WILL BE REQUIRED DURING REMEDIAL CONSTRUCTION ACTIVITIES. GROUNDWATER DEPTH VARIES FROM APPROXIMATELY 4 FEET TO 7 FEET BELOW GROUND SURFACE. SOIL EXCAVATION WILL BE CONDUCTED TO A MAXIMUM APPROXIMATELY 18 FEET BELOW GROUND SURFACE IN CHROMIUM EXCAVATION AREAS. EXCAVATION AREAS ARE TO BE DEWATERED PRIOR TO EXCAVATION. SURFACE WATER AND GROUNDWATER THAT POTENTIALLY CONTACTS CONTAMINATED MATERIALS AND/OR IS REMOVED FROM AN EXCAVATION BY SUMPS OR DEWATERING WILL BE PROCESSED AT A CONSTRUCTION WATER TREATMENT SYSTEM AND DISCHARGED TO THE JCMUA SEWER SYSTEM. TREATMENT AND DISCHARGE OF DEWATERING WATER WILL BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF JCMUA, AND THE APPLICABLE TWA AND PVSC PERMITS AND APPROVALS TO BE SECURED BY HONEYWELL. CONTRACTOR TO PROVIDE ALL LAB TESTING.

GN9. THE DEWATERING DISCHARGE FROM SA–6 SOUTH WILL BE ROUTED TO THE CONSTRUCTION WATER TREATMENT SYSTEM LOCATED ON SA–6 NORTH.

GN10. SEQUENCING OF SITE PREPARATION, PAVEMENT REMOVAL, DEMOLITION ACTIVITIES, SET UP OF SCALES, MATERIALS STORAGE, ON–SITE TRAFFIC PLANNING/ROUTING, ESTABLISHMENT OF WORKER PARKING AREAS, OFFICE OR STORAGE TRAILERS, PERIMETER FENCING, DECONTAMINATION PADS, AND ANY OTHER NON–GROUND INTRUSIVE ACTIVITIES SHALL BE COORDINATED WITH THE SEQUENCE OF CONSTRUCTION.

GN11. DELINEATION OF EXCAVATION LIMITS AND DEPTHS ARE BASED ON THE LIMITS OF CHROMIUM IMPACT ESTABLISHED DURING THE SOIL SAMPLING AND TESTING PROGRAMS CONDUCTED TO ESTABLISH PRE–EXCAVATION SOIL CHARACTERIZATION LEVELS. ONLY LIMITED VERIFICATION SAMPLING WILL BE REQUIRED. CONTRACTOR SHALL MAKE PROVISIONS FOR WORKING IN ALTERNATE REMEDIATION AREAS WHILE SAMPLE RESULTS ARE BEING PROCESSED. IMPACTED SOIL SHALL BE LOADED DIRECTLY INTO HAUL TRUCKS TO THE EXTENT PRACTICAL. SOIL SUITABLE FOR REUSE ON–SITE SHALL BE SEGREGATED FROM IMPACTED SOIL TO BE DISPOSED OFF–SITE. REFER TO THE SOIL MANAGEMENT PLAN FOR ADDITIONAL REQUIREMENTS.

GN12. DURING SHORING INSTALLATION AND SOIL EXCAVATION ACTIVITIES ADJACENT TO AND AT ELEVATIONS BELOW ACTIVE/OCCUPIED EXISTING UTILITIES OR STRUCTURES, THE UTILITIES OR STRUCTURES SHALL BE MONITORED FOR SIGNS OF SOIL DISPLACEMENT OR MOVEMENT THAT WOULD INDICATE LOSS OF SOIL SUPPORT OR SETTLEMENT.

GN13. CONTRACTOR WILL BE REQUIRED TO MAINTAIN THE INTEGRITY OF BUILDINGS, EXISTING BULKHEAD, UTILITIES AND OTHER SITE FEATURES AND REPAIR ANY DAMAGE AT NO ADDITIONAL COST TO HONEYWELL.

GN14. DURING EXCAVATION ACTIVITIES, PROTECT THE EXPOSED SOIL FROM EXCESS DRYING (KEEP MOIST BUT NOT WET). ALSO PROTECT CUT SLOPES FROM EROSION DUE TO PRECIPITATION OR STORM RUNOFF AND DETERIORATION DUE TO CONSTRUCTION ACTIVITIES (FOOT OR EQUIPMENT TRAFFIC). USE OF A TACKAFIER OR TEMPORARY STABILIZATION FABRIC IS PERMITTED.

GN15. HONEYWELL WILL CONTRACT THE SOIL TRANSPORTATION AND DISPOSAL DIRECTLY WITH THE DISPOSAL FACILITY. THE CONTRACTOR WILL ASSIST IN THE PREPARATION OF DISPOSAL DOCUMENTATION (I.E. MANIFESTS, CHARACTERIZATION) REQUIRED BY THE DISPOSAL FACILITY.

GN16. THE HEPSCD AND JCMUA RESPECTIVELY WILL BE NOTIFIED 72 HOURS PRIOR TO THE START OF WORK AND/OR RESTART OF SEWER CONSTRUCTION.

GN17. ELEVATIONS ARE BASED ON NGVD 1929 DATUM. COORDINATES ARE IN THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD 1983.

GN18. EXISTING CONDITIONS SHOWN ON THESE PLANS ARE BASED ON THE UTILITY AND TOPOGRAPHIC SURVEY OF STUDY AREA 6 SOUTH FOR LOTS 9H, 9L, 10E, 10H, 11H, 11Y, 12A, 17, 18, 19, AND 20 IN BLOCK 1290.1 SITUATED IN HUDSON COUNTY, NEW JERSEY PREPARED BY MASER CONSULTING P.A. ON DECEMBER 17, 2010 UNDER THE DIRECT SUPERVISION GLEN J. LLOYD, P.L.S. LICENSE NO. GS037598.

GN19. FLOOD HAZARD AREA (EL 10.2 NGVD) SHOWN ON THESE PLANS IS BASED ON STATE OF NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION – DIVISION OF WATER RESOURCES TITLED DELINEATION OF FLOODWAY AND FLOOD HAZARD AREA FLOOD PROFILES – PASSAIC RIVER STA 410+00 TO 920+00.

GN20. WORK WITHIN THE N.J.D.O.T. R.O.W. WILL REQUIRE CO–ORDINATION WITH AND MAY REQUIRE SUBCONTRACTING WITH N.J.D.O.T. FOR TRAFFIC CONTROL AND OTHER SERVICES. THE COST OF ALL SUCH SERVICES WILL BE BORNE BY THE CONTRACTOR. WORK WITHIN 3 FEET OF THE 24 INCH GAS LINE WILL REQUIRE PSE&G OVERSIGHT.

GN21. CHROMIUM IMPACTED SOIL THAT ALSO CONTAIN NON–CHROMIUM COC'S THAT DO NOT MEET THE NJDEP'S DEFINITION OF HISTORIC FILL AS IDENTIFIED ON DRAWING C–104, WILL BE DISPOSED OFF SITE. SOILS THAT CONTAIN CONCENTRATIONS BELOW 20 MG/KG FOR HEXAVALENT CHROMIUM AND CONTAIN NON–CHROMIUM COC'S THAT MEET THE NJDEP'S DEFINITION OF HISTORIC FILL, WILL BE EXCAVATED, STAGED AND MANAGED SEPARATELY FROM CHROMIUM–IMPACTED SOILS. AS IDENTIFIED IN THE SMP, STOCKPILES OF SUCH HISTORIC FILL SOILS WILL BE TESTED TO CONFIRM THAT THE HEXAVALENT CHROMIUM CONCENTRATIONS ARE BELOW 20 MG/KG. IF SUCH SOILS ARE CONFIRMED TO BE BELOW 20 MG/KG FOR HEXAVALENT CHROMIUM, THIS SOIL MAY BE USED AS TEMPORARY SURCHARGE IN THE CAP AREAS, BACKFILL FOR EXCAVATIONS, OR TO RAISE THE GRADES FOR THE REDEVELOPMENT PROJECT OUTSIDE OF THE CAP AREA.

GN22. ACCESS RAMP TO THE GWTP WILL BE COMPLETED PRIOR TO THE IMPLEMENTATION OF THE CHROMIUM REMEDY.

GN23. GROUNDWATER TREATMENT PLANT AND ASSOCIATED UTILITIES, TRUCK CONTAINMENT PAD, AND THE GRAVEL BYPASS WILL BE COMPLETED EARLY IN THE IMPLEMENTATION OF THE CHROMIUM REMEDY.

STRUCTURAL STEEL

SS1. STEEL FILLER PLATES AND WEDGE PAIRS SHALL BE INSTALLED TO PROVIDE FULL BEARING BETWEEN SHEET PILES AND WALES.

SS2. SHOP AND FIELD WELDING PROCEDURES, ELECTRODE CLASSIFICATION, AND PREHEAT TEMPERATURE SHALL CONFORM TO AWS D1.1. WELDERS SHALL BE CERTIFIED IN ACCORDANCE WITH AWS D1.1 CRITERIA.

SS3. WHERE EXCAVATIONS ARE TO BE CONDUCTED ADJACENT TO THE HYDRAULIC BARRIER OR TEMPORARY EXCAVATION SUPPORT IS TO BE INSTALLED, THAT SHEETING OR SUPPORT SYSTEM WILL EXTEND A MINIMUM OF 1 FT ABOVE THE SURROUNDING GRADE UNTIL SUCH TIME AS THE EXCAVATION IS COMPLETED, AT WHICH TIME THE BARRIER WALL MAY BE TRIMMED TO THE GEOMEMBRANE SUBGRADE ELEVATION AND TEMPORARY SUPPORT MAY BE REMOVED. AT NO TIME DURING EXCAVATION WILL THE TOP OF THE BARRIER WALL OR TEMPORARY SUPPORT BE LESS THAN ELEVATION 10.7 OR LESS THAN THE ELEVATION OF THE GEOMEMBRANE LINER (WHICHEVER IS THE GREATER)

HYDRAULIC BARRIER TECHNICAL REQUIREMENTS

HB1. PERMANENT SHEET PILE SHALL BE ORDERED IN LENGTHS CONSISTENT WITH THAT REQUIRED TO MEET THE MINIMUM TOE AND TOP ELEVATIONS. FIELD SPLICING OF SHEETS WILL NOT BE PERMITTED. SHEETS WILL BE DRIVEN TO THE TOP DESIGN ELEVATION TO MINIMIZE THE NEED TO CUT SHEETS. SHEETS MAY BE DRIVEN DEEPER THAN THE "MINIMUM" DESIGN TOE TO MEET THE TOP ELEVATION REQUIREMENT. REFER TO DRAWINGS S–201 THRU S–203 FOR TOP OF SHEET ELEVATIONS.

HB2. HANDLE SHEET PILES IN A MANNER WHICH PREVENTS DAMAGE TO THE SHEET PILE AND EPOXY COATING. ANY DAMAGE TO THE SHEET OR EPOXY COATING WILL BE REPAIRED MEETING THE REQUIREMENTS NOTED IN HB11 BELOW. USE LIFTING HOLES AND STANDARD SAFETY LIFTING DEVICES OR PROVIDE SECONDARY SUPPORT DURING LIFTING.

HB3. SUPPORT SHEETS ON BLOCKS SPACED NOT MORE THAN 10 FT APART, AND NOT MORE THAN 2 FT FROM THE ENDS. SUPPORTS BETWEEN SHEETS, AND BETWEEN SHEET LIFTS, SHALL BE IN A VERTICAL PLANE.

HB4. IF SPUDDING IS REQUIRED DISCONTINUE SPUDDING MORE THAN 5 FT ABOVE THE MINIMUM TIP ELEVATIONS.

HB5. REMOVE AND REPLACE STEEL SHEET PILES FOUND TO BE OUT OF INTERLOCK, OUT OF TOLERANCE, DAMAGED, OR OTHERWISE DEFICIENT.

HB6. STAGE PILE DRIVING AND STEP SHEET PILE TIPS AS NECESSARY TO PREVENT PILE DISPLACEMENT FROM PLUMB.

HB7. SHEET PILES MAY BE WELDED TO ADJACENT SHEETS IF OTHER MEANS TO CONTROL SETTLEMENT DURING DRIVING IS PROVIDED. HOWEVER ANY WELDED AREAS WILL REQUIRE REPAIR CONSISTENT WITH THE REQUIREMENTS OF HB11 BELOW.

HB8. SHEETS WILL BE PITCHED AND DRIVEN IN A MANNER TO AVOID DAMAGE TO THE EPOXY COATING WHILE MAINTAINING THE SHEET PILE IN THE CORRECT PLAN LOCATION AND VERTICALITY. THE CONTRACTOR WILL UTILIZE MEANS AND METHODS TO PREVENT SHEETS FROM WARPING OR WRACKING.

HB9. PROVIDE CONTINUOUS INSPECTION OF SHEET PILE DRIVING. INSPECT LOCATION AND VERTICALITY WHEN SETTING SHEETS, AND WHEN SHEETS ARE DRIVEN HALF DEPTH.

HB10. MAINTAIN PILE DRIVING INSPECTION RECORD FOR EACH PAIR DRIVEN. INDICATE PILE HAMMER, RATE OF OPERATION, ENERGY, USE OF DRIVE HELMET AND CAP, ETC. PROVIDE A UNIQUE NUMBER FOR EACH PAIR, AND INDICATE LOCATION ON ALIGNMENT. DOCUMENT INSTALLATION DATE, SET TIME, DRIVE DURATION, AND TIME DRIVE COMPLETED, INITIAL PILE LENGTH, RE–HEADING OR CUTTING LENGTH(S), AND ANY ADDITIONAL INFORMATION REQUIRED FOR RECORD DRAWINGS. RECORD UNUSUAL CONDITIONS OR PROBLEM OBSERVED DURING DRIVING.

HB11. COAL TAR EPOXY COATING REQUIREMENTS:

a. COAT STEEL SHEET PILES, CONNECTOR PILES AND FABRICATED CONNECTOR PILES WITH TWO COATS, 8 MILS DRY FILM THICKNESS (DFT) EACH, COAL TAR EPOXY. COAL TAR EPOXY COATING SHALL BE APPLIED FROM THE FINAL TOP OF SHEET (WHEN TRIMMED FOR LINER INSTALLATION) TO THE BOTTOM OF THE SHEET OR A MAXIMUM OF 5 FEET BELOW THE INTERPRETED TOP OF STRATUM D ON BOTH THE OUTBOARD AND INBOARD FACES OF THE SHEETPILES.

b. COAL TAR EPOXY COATING SHALL BE "BITUMASTIC NO. 300–M" A MANUFACTURED BY CARBOLINE OR APPROVED EQUAL.

c. ALL SURFACES TO BE COATED SHALL BE SAND–BLASTED IN PREPARATION FOR APPLICATION OF THE COATING. SAND–BLASTING SHALL BE TO NEAR WHITE METAL, AT LEAST EQUIVALENT TO A COMMERCIAL BLAST AS DEFINED BY SSPC–SP–10. ALL SURFACES TO BE COATED MUST BE COMPLETELY DRY, FREE OF MOISTURE, SOIL, DUST AND GRIT AT THE TIME THE COATING IS APPLIED.

d. APPLICATION OF THE COATINGS AND CURING REQUIREMENTS SHALL BE IN CONFORMANCE WITH THE MANUFACTURER'S REQUIREMENTS.

e. WHERE WELDING, FASTENINGS, CUTTING OR OTHER WORK ARE TO BE ACCOMPLISHED AFTER INSTALLATION OF PILES, FIELD APPLIED PROTECTIVE COATS SHALL BE COMPLETED.

f. THE CONTRACTOR SHALL APPOINT AND PAY FOR AN INDEPENDENT INSPECTION AND TESTING AGENCY, APPROVED BY THE ENGINEER, TO INSPECT AND CERTIFY THE COATING PROCEDURE DURING EACH OF THE FOLLOWING CERTIFICATIONS:

i) CERTIFY THAT THE STEEL HAS BEEN PREPARED FOR COATING IN ACCORDANCE WITH THE COATING MANUFACTURER'S RECOMMENDATIONS AND ADDITIONAL REQUIREMENTS NOTED HEREIN.

i) CERTIFY THE THICKNESS OF THE TWO EPOXY COATS AND THAT EACH COAT IS APPLIED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND TO THE DRY FILM THICKNESS SPECIFIED.

iii) THE OWNER SHALL RESERVE THE RIGHT TO CONDUCT INDEPENDENT QUALITY ASSURANCE INSPECTIONS. REJECTED SHEETS WILL BE REPAIRED OR REPLACED ON NO ADDITIONAL COST TO THE OWNER.

HB12. SEALANT SHALL BE GUN GRADE SWELL SEAL WA HYDROPHILIC POLYURETHANE WATER STOP, MANUFACTURED BY DENEEF CONSTRUCTION CHEMICALS OF HOUSTON, TX. OR APPROVED EQUAL. REFER TO SPECIFICATIONS 01010 SECTION 5 SUBSECTION 5.

HB13. INSTALLATION OF SWELL SEAL SHALL BE PERFORMED IN ACCORDANCE WITH SPECIFICATION 02180 "SPECIAL INSTRUCTIONS" SECTION 3.03.

HB14. SHEET PILE WILL BE PROVIDED IN PREWELDED, PRECOATED PAIRS.

HB15. TEMPORARY SHEET PILE FOR EXCAVATIONS WILL BE LEFT A MINIMUM OF 1 FOOT ABOVE EXISTING GRADE OR 6–INCHES ABOVE 100 YEAR FLOOD ELEVATION WHICHEVER IS HIGHER.

HB16. AFTER CUTTING SHEETPILE TO FINAL ELEVATION, AS PART OF CAP CONSTRUCTION A SECTION OF GCL WILL BE PLACED BETWEEN THE TOP OF SHEETING AND THE CAP LINER IN AREAS BELOW THE SITE HISTORIC WATER SEE DRAWING C–301 DETAIL G FOR ADDITIONAL INFORMATION.

HB17. THE HYDRAULIC BARRIER WILL EXHIBIT FLOW PROPERTIES EQUAL OR BETTER THAN THAN A ONE FOOT WIDE BARRIER WITH A HYDRAULIC CONDUCTIVITY OF 1X10–6 CM/SEC.

HB18. FOR SHEET SEALING AND GROUTING BEFORE AND AFTER DRIVING, SEE SHEET C–515 DETAIL BF.

HB19. THE AREA INDICATED ON SHEETS S–201 TO S–203 FROM STATION 0+00 TO STATION 17+80 18+50 WILL BE SEALED WITH A CEMENT BENTONITE GROUT IN LIEU OF HYDRAULIC SEALANT. THIS PORTION OF THE WALL WILL BE FABRICATED WITH A 2 ½" X 3/8" ANGLE AND ½" HDPE GROUT PIPE FROM THE TOP OF THE INTERLOCK TO THE DEPTH OF STRATUM D SOILS. SEE DRAWING S–203 DETAIL BF AND SPECIFICATION SECTION 02180 FOR ADDITIONAL INFORMATION.

HB20. IN LOCATIONS WHERE CPT OR BORING ENCOUNTER REFUSAL AT DEPTHS OF <10 FEET TEST PITS OR PRE–TRENCHING WILL BE CONDUCTED TO VERIFY THAT POTENTIAL OBSTRUCTIONS HAVE BEEN REMOVED PRIOR TO DRIVING SHEETS.

HB21 PSE&G IS EVALUATING POLE RELOCATION AND RE–ROUTING OF ELECTRICAL SERVICE TEMPORARILY TO THE EAST SIDE OF ROUTE 440 TO FACILITATE HYDRAULIC BARRIER INSTALLATION. PSE&G PLANNING MAY ALSO BE IMPACTED BY THE ROUTE 440 WIDENING. IF CHANGES CANNOT BE IMPLEMENTED IT MAY BE NECESSARY TO INSTALL THE WALL INBOARD OF EXISTING LOCATIONS TO COMPLY WITH OSHA OVERHEAD CLEARANCE REQUIREMENTS AND DEFER REMEDIATION OF THE REMAINING STRIP.

SAMUEL G. SHALLARD

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 05/02/14 | REVISION OF GROUTED STATIONING - DCB003 | TDD | RJR | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD | | TDD | SHM |
| | | REVISION | | | | | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

GENERAL NOTES

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 587-2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | G-003 |
| SHEET | 3 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**FINAL DCB 004 – HB STRAIGHTENING**

**Honeywell RES** → Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 004 Minor (a)<br>Effective Date: 8/14/13 |
| Project Location: SA6-SOUTH | Associated RFI: |
| Title: Hydraulic Barrier Straightening SA6 South | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

Description of Change/Modification:

The hydraulic barrier alignment for SA-6 South between Station 21+00 and 22+00 is to be straightened to eliminate an offset in the wall that was an artifact of historic property lines that are no longer applicable. Corners, and the Stationing from 21+00 on is to be adjusted to account for the elimination of the 3-ft offset in the wall.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Modified straighten alignment and facilitate installation.<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: Drawings # S 203 and S 206 have been issued signed and sealed for replacement in design sets. CAD files of the change in the electronic file to the drawings noted are also included. The magnitude of the change is so small it is not readily discernible on the other drawings. | Design Documents Affected:<br>Design Drawings 9-13, 16-26, 29, 32, 33, 35, 36, 46-49, 51, 52, 55, 58 |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |


(Name / Signature): Samuel G. Shuttleworth


Does DCB Result in CCO? ☐ Yes(b) ☑ No


Date: 5/2/14

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.


SA-7
EXISTING SOIL CEMENT BENTONITE WALL
S 53°42'45" E
1488.21'
159.16
381.25'
HYDRAULIC BARRIER AND CEMENT BENTONITE WALL CONNECTION
B
S-203 C-301
25+86
146.96'
BLOCK 1290.1
LOTS 11H, 11V & 17
25+00
N 51°06'45" W — 159.00'
21+00
BLOCK 1290.1
LOT 9L
N 38°53'15" E
50.00'
N 51°06'45" W
10.00'
N 38°53'15" E
183.00'
354.96'
20+00
19+00
18+
24+00
23+00
22+00
HYDRAULIC BARRIER
BLOCK 1290.1
LOT 11W
550.26'
340.20'
HACKENSACK RIVER
(HEAD AND BULKHEAD LINE AS ADOPTED DECEMBER 6, 1923)
BENCHMARK
ELEV. 7.67
DESC.: PK NAIL
EXISTING GROUNDWATER EXTRACTION WELL I-5-MW-21VER
FORCEMAIN/CROSSING BARRIER WALL SEE DETAIL (WMS, No.) (S-11)
MH EL 3.56
TRAFFIC BOX
PW1-LDR6
PW1-LDR5
PW1-CD6
PW1-LDR1
PW1-CD1
PW2-LDR2
PW2-LDR1
PWV-ARV2
EXISTING LOT LINE (TYP.)
PAVED AREA
CONC. AREA
CONC. STORAGE
PAVED PARKING AREA
CONCRETE PAD
BUILDING SLAB AND FOUNDATION
DRAIN STRUCTURE
COVERED W/ STEEL PLATE
POLE #209530
POLE #209531
POLE #209532
INLET E
RIM EL 7.39
INV. EL 4.25 (12" CMP)
INV. EL 4.14 (6" CMP)
INV. EL 3.67 (12" CMP)
INV. EL 3.67 (12" CMP)
INV. EL 3.61 (12" CMP)
INV. EL 3.61 (12" CMP)
INV. EL 3.61




NOTES:

1. SEE SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. SEE SHEET G-003 AND G-004 FOR GENERAL NOTES.
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE LINER GRADE.

0 2 4 8
SCALE IN FEET
VERTICAL SCALE: 1" = 4'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |

TDD RJR SHM

SAMUEL G SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

# EXISTING SA-7 SCB WALL PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689-2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-206 |
| SHEET | 58 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR58-S-206 SCB Wall Plan Profile.dwg PLOT DATE: Fri, 02 May 2014 PLOT TIME: 10:59 AM

# FINAL DCB 005 – ANALYTICAL TESTING OF BACKFILL

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 005 Minor(a)<br>Effective Date: 9/24/13 |
| Project Location: SA-6 NORTH SA6-SOUTH | Associated RFI: |
| Title: Analytical Testing Frequency for Imported Borrow Materials | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

Description of Change/Modification:

The testing frequency for analytic parameters for imported borrow materials is to be modified to 1 test/ 5,000 CY of borrow material anticipated to be needed.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☑ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Honeywell directed modification.<br>Attachments: ☐ Yes ☑ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments:<br>The original specified minimum frequency was 1 sample per source. The frequency was increased to 1 sample per 5000 CY at the request of Honeywell, consistent with frequencies tested on imported virgin source materials on SA7. | Design Documents Affected:<br>Technical Specifications<br>Section 02315-10 2.13 Borrow Source Testing A. 1,2,3 Frequency |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |

| | |
|---|---|
| (Name / Signature): Samuel G. Ethridge | Does DCB Result in CCO? ☐ Yes(b) ☑ No<br>Date: 5/2/14 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

placed. Horizon B soils will be a uniform sandy loam having the following properties:

Sandy loam classification having 80% sand, ≤ 10% silt, 10% clay.
Ph range 5.5 – 7.0.
Organic Matter (by weight) 1.5-3.5%.

C. Soil Horizon C – During Interim Grading Horizon C Soil will be placed between the root barrier and the Horizon A soil. The first 6 inches of Horizon C soils to be placed directly above the root barrier will be compacted to a minimum 90% of Standard Proctor. To meet Final Grading and planting requirements Horizon A soils will be stripped as necessary and Horizon C soils shall be re-graded to provide an appropriate depth of 18 inches. Horizon C soil shall consist of uniform sandy loam having the following properties:

1. Sandy loam classification with 70-80% sand, ≤ 10% silt, 15-20% clay.
2. pH range 5.0 – 7.5.
3. Organic Matter (by weight) 1 % max.

## 2.13 BORROW SOURCE TESTING

A. Borrow source testing, including geotechnical characterization requirements, shall be conducted on all soil materials proposed for construction. Minimum third-party geotechnical laboratory testing requirements and frequency for materials are listed as follows:

1. Common Borrow, Geocomposite Drainage Layer Cover Soil, Cushion Fill, Dense Graded Aggregate, Planting Soils (Horizons B and C):

| Test | Methodology[1] | Frequency[2] |
|---|---|---|
| Particle-Size Analysis | ASTM D 422 | 1 test/5000 cy/material (to #200 Sieve) |
| Standard Proctor | ASTM D 698 | Min. 3 test/source/material 1 test/5000 cy |

2. Topsoil (Horizon A):
   Refer to Section 02900, "Topsoil and Seeding".
3. Crushed Stone:

| Test | Methodology[1] | Frequency[2] |
|---|---|---|
| Particle-Size Analysis | ASTM D 422 | 1 test/5000 cy/material (to #200 Sieve) |

B. Borrow Source Testing Notes:

1. Other testing methods may be considered acceptable, based on prior approval of the Engineer.
2. Testing frequency shall be as listed, at any change in borrow source, or at any discernable change in material delivered to the site (as determined by the Engineer).
   a. Common Borrow shall be certified clean from the borrow source or origin, based on analytical testing data, as approved by the Engineer.
      1. Soils shall be tested and certified "clean" relative to the NJDEP Technical Requirements pursuant to 7:26E 5.2(d) 2.

**FINAL DCB 006 – EXCAVATION SHAPES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 006 Major (a)(b)<br>Effective Date: 12/12/13 |
| Project Location: SA6-SOUTH | Associated RFI: |
| Title: Revised Excavation Shapes, Bottom of Excavation Elevations, and Post-Excavation Samples | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |


Description of Change/Modification:

The proposed bottom of excavation elevations have been modified in limited areas to expose Post-Excavation Samples as reported on the revised PDI summary tables which are attached to this DCB. Excavation Interval shapes have been revised to coincide with the revised bottom of excavation elevations and limits. This DCB also includes a color coded excavation bottom map to assist with interpreting the bottom of excavation elevations as depicted on the revised design drawings. In addition this DCB includes a table summarizing- Post-Excavation Reference (R) Samples for each area. These (R) samples are to be referenced in the weekly reports when a base PDI sample is not present in a specific 15 ft wide cells being used by Entact for construction control. This DCB includes the following documents:

- Design Drawings 16-25
- PDI Tables 1, 2, 3B, and 3C
- Figure 2 SA-6 South Color Coded Excavation Bottom
- Table 1 SA-6 South Reference Confirmation Samples

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Expose Confirmation Samples as Indentified in Revised PDI Tables<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☑ Yes ☐ No |
| Additional Comments: Major DCB anticipated to require review and approval by third parties. The changes result in an increase to the excavation quantity. | Design Documents Affected:<br>Drawings 16-25<br>PDI Tables 1, 2, 3B, and 3C |
| Honeywell (AP) Review:<br>Individual Discipline | Initial [signature] Date 12/20/16 |
| (Name / Signature): | Does DCB Result in CCO? ☑ Yes(b) ☐ No<br>Date: |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6–INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

NOTES:

1. REFER TO GENERAL NOTES SHEETS G–003 AND G–004
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002
3. CONTOURS ON THIS SHEET REPRESENT BOTTOM OF EXCAVATION.

0 25 50 100
SCALE IN FEET

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS | |
| 1 | 01/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | | | TDD | RJR | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
EXCAVATION PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 587-2888
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-111 |
| SHEET | 16 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR16-C-111 Excavation Erosion Control Plan.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 7:01 PM




## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20–240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |

TDD RJR TDD SHM

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CHROMIUM EXCAVATION INTERVAL 1


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-112
SHEET 17 OF 66

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR17-C-112 Chromium Excavation Interval 1.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:04 PM




MATCH LINE SEE ABOVE

LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | | | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | | RJR | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | TDD | TDD | SHM |
| | | REVISION | TDD | RJR | TDD | | SHM |

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

Honeywell
101 COLUMBIA RD. BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 2

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2500
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-113
SHEET 18 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR18-C-113 Chromium Excavation Interval 2.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:08 PM




## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | | TDD | RJR | TDD | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 3


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 587-2283
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-114 |
| SHEET | 19 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR19-C-114 Chromium Excavation Interval 3.dwg PLOT DATE: Tue, 07 Jan 2014 PLOT TIME: 8:55 PM




MATCH LINE SEE ABOVE

## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20–240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | | | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | | RJR | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | TDD | TDD | SHM |
| | | REVISION | | | | BY | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CHROMIUM EXCAVATION INTERVAL 4


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2220
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-115 |
| SHEET | 20 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR20-C-115 Chromium Excavation Interval 4.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:10 PM




MATCH LINE SEE ABOVE

LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20–240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN–SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6–INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | | TDD | RJR | TDD | SHM |

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CHROMIUM EXCAVATION INTERVAL 5


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-116 |
| SHEET | 21 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR21-C-116 Chromium Excavation Interval 5.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:03 PM




MATCH LINE SEE ABOVE

LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | | | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | TDD | RJR | TDD | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | RJR | TDD | TDD | SHM |

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400
SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CHROMIUM EXCAVATION INTERVAL 6


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2500
NJ Certification of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-117 |
| SHEET | 22 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR22-C-117 Chromium Excavation Interval 6.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:13 PM




MATCH LINE SEE ABOVE

LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | | | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | RJR | TDD | TDD | SHM |
| | | REVISION | | | | BY | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 7


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 890-2333
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-118 |
| SHEET | 23 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR23-C-118 Chromium Excavation Interval 7.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:18 PM




LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | | | TDD | SHM | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CHROMIUM EXCAVATION INTERVAL 8


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-119 |
| SHEET | 24 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR24-C-119 Chromium Excavation Interval 8.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:20 PM




## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | | | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | RJR | TDD | TDD | SHM |
| | | REVISION | | | | BY | APVD |

SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 9

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-120 |
| SHEET | 25 OF 66 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR25-C-120 Chromium Excavation Interval 9.dwg PLOT DATE: Wed, 11 Dec 2013 PLOT TIME: 8:22 PM

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

NEW JERSEY STATE HIGHWAY ROUTE 440

MATCH LINE SEE BELOW

BOT OF EXC AREA 14 = (2.50)

BOT OF EXC AREA 13 = 0.40

BOT OF EXC AREA 12 = 5.70

BOT OF EXC AREA 11 = (1.20)

BOT OF EXC AREA 8 = 0.40

BOT OF EXC AREA 10 = 2.10

BOT OF EXC AREA 9 = (1.20)

BOT OF EXC AREA 8 = 0.40

BOT OF EXC AREA 7 = (1.20)

BOT OF EXC AREA 6 = (2.50)

BOT OF EXC AREA 4 = (1.20)

BOT OF EXC AREA 5 = 2.10

BOT OF EXC AREA 7 = 0.40

BOT OF EXC AREA 2 = 2.10

BOT OF EXC AREA = (1.20)

SOIL RETENTION SYSTEM (TYP)

KELLOGG STREET

HACKENSACK RIVER

CAP AREA (TYP)

BOT OF EXC AREA 37 = 2.10

BOT OF EXC AREA 39 = 0.40

BOT OF EXC AREA 19 = 0.40

BOT OF EXC AREA 40 = 5.70

BOT OF EXC AREA 36 = (1.20)

BOT OF EXC AREA 38 = (4.30)

BOT OF EXC AREA 33 = (2.50)

BOT OF EXC AREA 21 = (1.20)

BOT OF EXC AREA 20 = (2.50)

BOT OF EXC AREA 17 = (1.20)

BOT OF EXC AREA 15 = 2.10

BOT OF EXC AREA 15 = (4.30)

BOT OF EXC AREA 14 = (2.50)

BOT OF EXC AREA 10 = 5.70

BOT OF EXC AREA 23 = 0.40

BOT OF EXC AREA 22 = (2.50)

BOT OF EXC AREA 16 = (2.50)

BOT OF EXC AREA 32 = 2.10

BOT OF EXC AREA 39 = (7.50)

BOT OF EXC AREA 24 = (7.50)

BOT OF EXC AREA 25 = (5.70)

BOT OF EXC AREA 41 = (1.20)

BOT OF EXC AREA 31 = (1.20)

BOT OF EXC AREA 30 = (2.50)

BOT OF EXC AREA 27 = (7.50)

BOT OF EXC AREA 28 = (5.9)

BOT OF EXC AREA 26 = (8.40)

MATCH LINE SEE ABOVE

EXCAVATION BOTTOM ELEVATION 5.7

EXCAVATION BOTTOM ELEVATION 4.2

EXCAVATION BOTTOM ELEVATION 2.1

EXCAVATION BOTTOM ELEVATION 0.4

EXCAVATION BOTTOM ELEVATION (1.2)

EXCAVATION BOTTOM ELEVATION (2.5)

EXCAVATION BOTTOM ELEVATION (4.3)

EXCAVATION BOTTOM ELEVATION (7.5)

EXCAVATION BOTTOM ELEVATION (8.4)

EXCAVATION BOTTOM ELEVATION (8.7)

EXCAVATION BOTTOM ELEVATION (8.9)

NOTES:

1. CONTOURS ON THIS SHEET REPRESENT BOTTOM OF EXCAVATION.
2. THE APPROVED 100% DESIGN DOCUMENTS OUTLINE CONDITIONS WHERE THE FINAL EXCAVATION BOTTOM MAY BE SHALLOWER IF STRATUM D IS ENCOUNTERED.

0 25 50 100
SCALE IN FEET

Prepared/Date: TDD 12/02/13
Checked/Date: SGS 12/02/13

Honeywell
101 COLUMBIA RD., P.O. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

SA-6 SOUTH
COLOR CODED EXCAVATION BOTTOM
FIGURE 2

EXISTING SOIL CEMENT BENTONITE WALL (TYP)

CAP AREA (TYP)

BOTTOM OF EXCAVATION ANTICIPATED TO EXTEND TO STRATUM D (SEE NOTE 1)

HYDRAULIC BARRIER (TYP)

MATCH LINE SEE BELOW

NEW JERSEY STATE HIGHWAY ROUTE 440

BOT OF EXC AREA 1 = (1.20)

BOT OF EXC AREA 2 = 2.10

BOT OF EXC AREA 3 = 0.40

BOT OF EXC AREA 4 = (1.20)

BOT OF EXC AREA 5 = 2.10

BOT OF EXC AREA 6 = (2.50)

BOT OF EXC AREA 7 = (1.20)

BOT OF EXC AREA 8 = 0.40

BOT OF EXC AREA 9 = (1.20)

BOT OF EXC AREA 10 = 2.10

BOT OF EXC AREA 11 = (1.20)

BOT OF EXC AREA 12 = 5.70

BOT OF EXC AREA 13 = 0.40

BOT OF EXC AREA 14 = (2.50)

KELLOGG STREET

HACKENSACK RIVER

CAP AREA (TYP)

BOT OF EXC AREA 15 = (4.30)

BOT OF EXC AREA 16 = (2.50)

BOT OF EXC AREA 17 = (1.20)

BOT OF EXC AREA 18 = 0.40

BOT OF EXC AREA 19 = 2.10

BOT OF EXC AREA 20 = (2.50)

BOT OF EXC AREA 21 = (1.20)

BOT OF EXC AREA 22 = (2.50)

BOT OF EXC AREA 23 = 0.40

BOT OF EXC AREA 24 = (7.50)

BOT OF EXC AREA 25 = (5.70)

BOT OF EXC AREA 26 = (8.40)

BOT OF EXC AREA 27 = (7.50)

BOT OF EXC AREA 28 = (5.70)

BOT OF EXC AREA 29 = (5.70)

BOT OF EXC AREA 30 = (2.50)

BOT OF EXC AREA 31 = (1.20)

BOT OF EXC AREA 32 = 2.10

BOT OF EXC AREA 33 = (2.50)

BOT OF EXC AREA 34 = 0.40

BOT OF EXC AREA 35 = (4.30)

BOT OF EXC AREA 36 = (1.20)

BOT OF EXC AREA 37 = 2.10

BOT OF EXC AREA 38 = (7.50)

BOT OF EXC AREA 39 = 2.10

BOT OF EXC AREA 40 = 5.70

BOT OF EXC AREA 41 = (1.20)

BOT OF EXC AREA 42 = (2.50)

BOT OF EXC AREA 43 = (1.20)

MATCH LINE SEE ABOVE

ANTICIPATED STRATUM D EXPOSURE

NOTES:

1. BOTTOM OF EXCAVATION IN STRATUM D AREAS REFLECT AVERAGE ELEVATIONS BASED ON GEOTECHNICAL BORINGS.
2. THE APPROVED 100% DESIGN DOCUMENTS OUTLINE CONDITIONS WHERE THE FINAL EXCAVATION BOTTOM MAY BE SHALLOWER IF STRATUM D IS ENCOUNTERED.

0 25 50 100
SCALE IN FEET

Prepared/Date: TDD 01/07/14
Checked/Date:

Honeywell
101 COLUMBIA RD., P.O. BOX 2106
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

SA-6 SOUTH
ANTICIPATED STRATUM D EXPOSURE
FIGURE 3

**TABLE 1 REVISED**
**Post-Excavation Sidewall Sample Statistics**
**Study Area 6 South**
**Sites 073, 124, 125, 134, 140, 163**
**Jersey City, NJ**

| Site ID | Sidewall Length (ft) | No. of Samples per proposed alternative frequency | No. of samples collected/analyzed | Frequency per ft. |
|---|---|---|---|---|
| 073 | 790 | 16 | 16 | 1:49 |
| 124 | 750 | 15 | 13 | 1:58 |
| 125 | 325 | 7 | 11 | 1:30 |
| 134* | 1,080 | 22 | 29 | 1:37 |
| 140 | 620 | 13 | 13 | 1:48 |
| 163** | 2,055 | 42 | 41 | 1:50 |
| All Sites | 5,620 | 115 | 123 | 1:45 |

NOTES:
NJDEP-approved alternative frequency = 1 Sample per 50 ft. of excavation sidewall
* Site 134 includes Boatyard
** Includes horizontal delineation samples
Revised Information since the June 28, 2013 100% Design Report.

**TABLE 2 REVISED**
**Post-Excavation Base Soil Sample Statistics**
**Study Area 6 South**
**Sites 073, 124, 125, 134, 140, 163**
**Jersey City, NJ**

| Site ID | Excavation Area ($ft^2$) | No. of Samples per proposed alternative frequency | No. of samples collected/analyzed | Frequency per $ft^2$ |
|---|---|---|---|---|
| 073 | 50,655 | 39 | 41 | 1:1235 |
| 124 | 76,500 | 59 | 62 | 1:1234 |
| 125 | 45,720 | 36 | 53 | 1:862 |
| 134* | 87,420 | 68 | 67 | 1:1305 |
| 140 | 79,970 | 62 | 52 | 1:1538 |
| 163*** | 36,640 | 29 | 39 | 1:940 |
| All Sites | 376,905 | 293 | 314 | 1:1200 |

NOTES:
NJDEP-approved alternative frequency = 1 Sample per 1,300 sq. ft. of excavation base
* Site 134 includes Boatyard
*** Includes vertical delineation samples
Revised Information since the June 28, 2013 100% Design Report.



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 073-SB-003 | | 7/14/2008 | | 0.90 | UJ | SW |
| 073-SB-003 | | 7/14/2008 | | 1.70 | | |
| 073-SB-003 | | 7/14/2008 | 5.8 | 0.97 | U | |
| 073-SB-004 | | 7/31/2008 | 5.9 | 10.70 | | SW |
| 073-SB-006 | | 7/31/2008 | | 2.50 | | SW |
| 073-SB-006 | | 7/31/2008 | 3.8 | 0.88 | U | |
| 073-SB-016 | | 8/7/2008 | | 2.20 | UJ | SW |
| 073-SB-016 | | 8/7/2008 | | 6.40 | | |
| 073-SB-016 | | 8/7/2008 | | 5.80 | | |
| 073-SB-016 | | 8/7/2008 | | 8.90 | J | |
| 073-SB-016 | | 8/7/2008 | | 4.90 | | |
| 073-SB-016 | | 8/7/2008 | | 13.10 | | |
| 073-SB-016 | | 8/7/2008 | -6.2 | 1.90 | UJ | |
| 073-SB-022 | | 4/19/2010 | | 12.30 | | SW |
| 073-SB-022 | D | 4/19/2010 | | 13.80 | | |
| 073-SB-022 | | 4/19/2010 | | 8.50 | | |
| 073-SB-022 | | 4/19/2010 | | 8.10 | | |
| 073-SB-022 | | 4/19/2010 | -5.4 | 7.70 | | |
| 073-SB-027 | | 4/20/2010 | 7.8 | 0.90 | U | SW |
| 073-SB-044 | | 4/21/2010 | 4 | 8.40 | | SW* |
| 073-SB-046 | | 4/21/2010 | | 7.20 | | SW |
| 073-SB-046 | | 4/21/2010 | | 4.90 | | |
| 073-SB-046 | | 4/21/2010 | | 17.20 | | |
| 073-SB-046 | | 4/21/2010 | 2.9 | 14.90 | J | |
| 073-SB-048 | | 4/21/2010 | | 12.60 | | SW |
| 073-SB-048 | | 4/21/2010 | | 5.40 | | |
| 073-SB-048 | | 4/21/2010 | | 0.55 | U | |
| 073-SB-048 | | 4/21/2010 | -5.7 | 0.81 | J | |
| 073-SB-051 | | 5/24/2010 | | 12.50 | | SW |
| 073-SB-051 | | 5/24/2010 | -5.8 | 5.00 | | |
| 073-SB-052 | | 5/24/2010 | -0.6 | 5.00 | | SW* |
| 073-SB-060 | | 8/5/2010 | 0.9 | 13.60 | | SW |
| 073-SB-063 | | 10/25/2010 | 8.8 | 17.00 | | SW |
| 073-SB-064 | | 10/25/2010 | 5.92 | 2.10 | | SW |
| 073-SB-071 | | 11/29/2010 | -3.6 | 5.10 | | SW |
| 073-SB-073 | | 11/29/2010 | 1.6 | 5.10 | | SW* |
| 073-SB-076 | | 2/15/2011 | -4.1 | 17.20 | J | SW |
| 073-SB-077 | | 3/21/2011 | 0.4 | 16.30 | | SW |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 073-SB-078 | | 1/16/2012 | | 0.70 | | SW |
| 073-SB-078 | | 1/16/2012 | 6.7 | 2.70 | | |
| 124-PT-01 | | 3/12/2008 | | 0.86 | U | SW |
| 124-PT-01 | | 3/12/2008 | | 0.90 | U | |
| 124-PT-01 | | 3/12/2008 | | 11.10 | | |
| 124-PT-01 | | 3/12/2008 | 3.3 | 18.60 | J | |
| 124-PT-02 | | 3/12/2008 | | 2.10 | | SW |
| 124-PT-02 | | 3/12/2008 | | 0.89 | U | |
| 124-PT-02 | | 3/12/2008 | | 2.60 | | |
| 124-PT-02 | | 3/12/2008 | 3.4 | 0.97 | UJ | |
| 124-SB-014 | | 9/7/2006 | | 2.26 | U | SW |
| 124-SB-014 | | 9/7/2006 | | 2.38 | U | |
| 124-SB-014 | | 9/7/2006 | | 2.62 | U | |
| 124-SB-014 | | 9/7/2006 | 4.5 | 17.40 | J | |
| 124-SB-017 | | 9/7/2006 | | 2.28 | U | SW |
| 124-SB-017 | | 9/7/2006 | | 2.99 | U | |
| 124-SB-017 | | 9/7/2006 | | 2.48 | U | |
| 124-SB-017 | | 9/7/2006 | | 2.69 | U | |
| 124-SB-017 | | 9/7/2006 | -0.6 | 2.39 | U | |
| 124-SB-019 | | 9/7/2006 | | 2.25 | U | SW |
| 124-SB-019 | | 9/7/2006 | | 2.74 | U | |
| 124-SB-019 | | 9/7/2006 | | 2.52 | U | |
| 124-SB-019 | D | 9/7/2006 | | 2.60 | U | |
| 124-SB-019 | | 9/7/2006 | | 2.28 | U | |
| 124-SB-019 | | 9/7/2006 | 0.9 | 2.47 | U | |
| 124-SB-048 | | 8/5/2009 | 1.2 | 1.00 | U | SW |
| 124-SB-050 | | 8/6/2009 | | 1.10 | U | SW |
| 124-SB-050 | | 8/6/2009 | | 1.80 | | |
| 124-SB-050 | | 8/6/2009 | 2.9 | 1.20 | | |
| 124-SB-056 | | 8/6/2009 | | 1.20 | | SW |
| 124-SB-056 | | 8/6/2009 | 4.7 | 2.70 | | |
| 124-SB-063 | | 5/7/2010 | 3.3 | 1.70 | | SW |
| 124-SB-065 | | 5/7/2010 | | 0.98 | U | SW |
| 124-SB-065 | | 5/7/2010 | | 0.68 | | |
| 124-SB-065 | | 5/7/2010 | 3.9 | 15.90 | | |
| 124-SB-074 | | 5/21/2010 | -2.2 | 15.90 | | SW* |
| 124-SB-075 | | 5/21/2010 | -1.8 | 15.90 | | SW* |
| 124-SB-075 | D | 5/21/2010 | -1.8 | 15.90 | | |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 124-SB-076 | | 5/21/2010 | -1.8 | 15.90 | | SW* |
| 124-SB-090 | | 8/18/2010 | 3.8 | 15.20 | | SW |
| 124-SB-108 | | 7/7/2008 | | 0.90 | U | SW |
| 124-SB-108 | | 7/7/2008 | | 0.93 | U | |
| 124-SB-108 | | 7/7/2008 | | 1.00 | U | |
| 124-SB-108 | | 7/7/2008 | | 10.00 | | |
| 124-SB-108 | | 7/7/2008 | 2.6 | 1.00 | U | |
| 124-SB-108 | D | 7/7/2008 | 2.6 | 2.80 | | |
| 124-SB-126 | | 10/26/2010 | 4.3 | 8.20 | | SW |
| 124-SB-126 | D | 10/26/2010 | 4.3 | 9.40 | | |
| 125-PT-15 | | 4/16/2008 | | 1.80 | U | SW |
| 125-PT-15 | | 4/16/2008 | | 1.90 | U | |
| 125-PT-15 | | 4/16/2008 | | 0.95 | UJ | |
| 125-PT-15 | | 4/16/2008 | 1.1 | 0.95 | U | |
| 125-SB-058 | | 7/6/2009 | | 5.70 | | SW |
| 125-SB-058 | | 7/6/2009 | | 4.90 | | |
| 125-SB-058 | | 7/6/2009 | 0.4 | 1.00 | U | |
| 125-SB-067 | | 8/6/2009 | | 3.80 | | SW |
| 125-SB-067 | | 7/8/2009 | 1.8 | 2.00 | U | |
| 125-SB-068 | | 8/7/2009 | | 8.70 | | SW |
| 125-SB-068 | | 8/7/2009 | 3 | 7.00 | | |
| 125-SB-079 | | 5/6/2010 | | 0.62 | UJ | SW |
| 125-SB-079 | | 5/6/2010 | 2.5 | 5.90 | | |
| 125-SB-080 | | 5/6/2010 | | 1.00 | J | SW |
| 125-SB-080 | | 5/6/2010 | 2.3 | 17.10 | | |
| 125-SB-081 | | 5/6/2010 | | 0.68 | | SW |
| 125-SB-081 | | 5/6/2010 | 3.7 | 17.70 | | |
| 125-SB-081 | D | 5/6/2010 | 3.7 | 17.20 | | |
| 125-SB-087 | | 8/18/2010 | 3.5 | 18.80 | J | SW |
| 125-SB-088 | | 10/26/2010 | | 2.50 | J | SW |
| 125-SB-088 | | 10/26/2010 | 2.2 | 3.60 | | |
| 125-SB-091 | | 3/23/2011 | 0.8 | 13.80 | J | SW |
| 125-SB-092 | | 3/23/2011 | 0.6 | 10.80 | | SW |
| 125-SB-118 | | 1/16/2012 | -3.5 | 10.80 | J | SW* |
| 125-SB-118 | | 1/16/2012 | -3.5 | 10.80 | J | |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 134-SB-017 | | 6/18/2008 | | 0.90 | UJ | SW |
| 134-SB-017 | | 6/18/2008 | | 1.00 | UJ | |
| 134-SB-017 | | 6/18/2008 | | 5.40 | J | |
| 134-SB-017 | | 6/18/2008 | | 19.40 | J | |
| 134-SB-017 | | 6/18/2008 | | 14.60 | J | |
| 134-SB-017 | D | 6/18/2008 | | 10.70 | J | |
| 134-SB-017 | | 6/18/2008 | -2.3 | 5.70 | J | |
| 134-SB-021 | | 6/19/2008 | | 6.60 | J | SW |
| 134-SB-021 | | 6/19/2008 | | 6.10 | J | |
| 134-SB-021 | | 6/19/2008 | | 13.90 | J | |
| 134-SB-021 | | 6/19/2008 | -0.1 | 15.40 | J | |
| 134-SB-023 | | 6/19/2008 | | 2.20 | UJ | SW |
| 134-SB-023 | | 6/19/2008 | | 1.90 | UJ | |
| 134-SB-023 | | 6/19/2008 | | 1.90 | UJ | |
| 134-SB-023 | | 6/19/2008 | | 9.00 | J | |
| 134-SB-023 | | 6/19/2008 | -0.3 | 9.10 | J | |
| 134-SB-025 | | 6/19/2008 | | 1.80 | UJ | SW |
| 134-SB-025 | | 6/19/2008 | | 1.90 | UJ | |
| 134-SB-025 | | 6/19/2008 | | 1.80 | J | |
| 134-SB-025 | | 6/19/2008 | | 14.20 | J | |
| 134-SB-025 | | 6/19/2008 | | 5.40 | J | |
| 134-SB-025 | | 6/19/2008 | | 0.97 | UJ | |
| 134-SB-025 | | 6/19/2008 | -4.3 | 7.00 | J | |
| 134-SB-027 | | 6/19/2008 | | 4.40 | | SW |
| 134-SB-027 | | 6/19/2008 | | 1.10 | J | |
| 134-SB-027 | | 6/19/2008 | | 6.60 | | |
| 134-SB-027 | | 6/19/2008 | | 14.50 | | |
| 134-SB-027 | | 6/19/2008 | | 11.40 | | |
| 134-SB-027 | D | 6/19/2008 | | 9.20 | | |
| 134-SB-027 | | 6/19/2008 | -2.7 | 1.00 | U | |
| 134-SB-034 | | 6/19/2008 | 6 | 1.10 | | SW |
| 134-SB-050 | | 7/15/2009 | | 2.10 | | SW |
| 134-SB-050 | | 7/15/2009 | | 2.20 | U | |
| 134-SB-050 | | 7/15/2009 | | 0.99 | J | |
| 134-SB-050 | | 7/15/2009 | | 5.10 | | |
| 134-SB-050 | | 7/15/2009 | | 1.20 | J | |
| 134-SB-050 | | 7/15/2009 | | 2.20 | U | |
| 134-SB-050 | | 7/15/2009 | -4.2 | 4.20 | U | |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 134-SB-053 | | 7/15/2009 | -3 | 6.10 | | SW* |
| 134-SB-058 | | 7/28/2009 | | 9.60 | J | SW |
| 134-SB-058 | | 7/28/2009 | | 4.40 | | |
| 134-SB-058 | | 7/28/2009 | -0.7 | 2.00 | UJ | |
| 134-SB-072 | | 4/22/2010 | -0.8 | 0.48 | U | SW |
| 134-SB-073 | | 4/23/2010 | 2.7 | 17.40 | | SW |
| 134-SB-074 | | 4/22/2010 | 2.2 | 18.00 | | SW |
| 134-SB-075 | | 4/22/2010 | 2.2 | 16.50 | | SW |
| 134-SB-087 | | 4/30/2010 | -0.4 | 9.90 | | SW |
| 134-SB-088 | | 4/30/2010 | 0.5 | 6.60 | | SW |
| 134-SB-089 | | 4/30/2010 | 0.1 | 8.30 | | SW |
| 134-SB-090 | | 4/30/2010 | 0.2 | 1.80 | | SW |
| 134-SB-092 | | 5/25/2010 | 3 | 17.50 | J | SW |
| 134-SB-094 | | 8/6/2010 | 3.47 | 8.60 | | SW |
| 134-SB-097 | | 8/6/2010 | | 14.50 | | SW |
| 134-SB-097 | | 8/6/2010 | | 0.48 | U | |
| 134-SB-097 | | 8/6/2010 | | 12.40 | | |
| 134-SB-097 | | 8/6/2010 | -0.5 | 6.60 | | |
| 134-SB-099 | | 8/6/2010 | | 9.70 | | SW |
| 134-SB-099 | | 8/6/2010 | | 1.20 | J | |
| 134-SB-099 | | 8/6/2010 | | 7.60 | J | |
| 134-SB-099 | | 8/6/2010 | | 7.20 | J | |
| 134-SB-099 | D | 8/6/2010 | | 6.80 | J | |
| 134-SB-099 | | 8/6/2010 | | 2.40 | J | |
| 134-SB-099 | | 8/6/2010 | -3.2 | 0.93 | J | |
| 134-SB-100 | | 8/6/2010 | | 2.00 | J | SW |
| 134-SB-100 | | 8/6/2010 | | 1.40 | J | |
| 134-SB-100 | | 8/6/2010 | | 2.60 | J | |
| 134-SB-100 | | 8/6/2010 | | 13.70 | J | |
| 134-SB-100 | D | 8/6/2010 | | 10.70 | J | |
| 134-SB-100 | | 8/6/2010 | | 0.58 | J | |
| 134-SB-100 | | 8/6/2010 | -2.1 | 18.70 | J | |
| 134-SB-101 | | 8/6/2010 | 0.9 | 1.40 | J | SW* |
| 134-SB-111 | | 10/25/2010 | 0.8 | 8.20 | | SW |
| 134-SB-126 | | 6/23/2011 | | 1.4 | | SW |
| 134-SB-126 | | 6/23/2011 | | 0.61 | J | |
| 134-SB-126 | | 6/23/2011 | | 1.2 | | |
| 134-SB-126 | | 6/23/2011 | | 8.4 | | |
| 134-SB-126 | | 6/23/2011 | | 7.9 | J | |
| 134-SB-126 | | 6/23/2011 | -1.7 | 10.5 | J | |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 134-SB-142 | | 9/27/2011 | | 13.7 | | SW |
| 134-SB-142 | | 9/27/2011 | -6.5 | 3.4 | | |
| 134-SB-144 | | 10/19/2011 | 6.1 | 6.6 | | SW |
| 134-SB-145 | | 10/19/2011 | 6.1 | 14.5 | | SW |
| 134-SB-146 | | 10/19/2011 | 5.9 | 3.2 | | SW** |
| 134-SB-152 | | 12/7/2011 | 6 | 15.5 | J | SW |
| 134-SB-152 | D | 12/7/2011 | 6 | 16.9 | | |
| 134-SB-156 | | 1/13/2012 | 6 | 10.1 | J | SW |
| 134-SB-157 | | 1/16/2012 | | 10.7 | | SW |
| 134-SB-157 | | 1/16/2012 | -6 | 15.2 | J | |
| 140-SB-003 | | 6/20/2005 | | 4.40 | J | SW |
| 140-SB-003 | | 6/20/2005 | | 2.00 | UJ | |
| 140-SB-003 | | 6/20/2005 | -0.8 | 7.60 | J | |
| 140-SB-014 | | 6/25/2008 | | 1.70 | UJ | SW |
| 140-SB-014 | | 6/25/2008 | 6.8 | 1.80 | UJ | |
| 140-SB-025 | | 7/30/2008 | -3.2 | 5.70 | J | SW* |
| 140-SB-027 | | 10/27/2008 | -2.1 | 7.40 | | SW |
| 140-SB-031 | | 7/16/2009 | | 5.80 | | SW |
| 140-SB-031 | | 7/16/2009 | | 1.40 | U | |
| 140-SB-031 | | 7/16/2009 | | 3.10 | | |
| 140-SB-031 | | 7/16/2009 | 1.5 | 6.00 | | |
| 140-SB-032 | | 7/16/2009 | | 0.87 | | SW |
| 140-SB-032 | | 7/16/2009 | | 0.95 | U | |
| 140-SB-032 | | 7/16/2009 | | 1.40 | U | |
| 140-SB-032 | | 7/16/2009 | | 13.00 | | |
| 140-SB-032 | | 7/16/2009 | -0.8 | 9.10 | | |
| 140-SB-034 | | 7/16/2009 | | 1.00 | U | SW |
| 140-SB-034 | | 7/16/2009 | | 1.90 | U | |
| 140-SB-034 | | 7/16/2009 | | 7.60 | | |
| 140-SB-034 | | 7/16/2009 | | 0.93 | U | |
| 140-SB-034 | | 7/16/2009 | -2 | 2.40 | | |
| 140-SB-059 | | 5/3/2010 | -0.8 | 2.70 | J | SW |
| 140-SB-060 | | 5/3/2010 | -4.8 | 2.70 | J | SW* |
| 140-SB-061 | | 5/3/2010 | -6.4 | 2.70 | UJ | SW* |
| 140-SB-061 | D | 5/3/2010 | -6.4 | 2.70 | UJ | |
| 140-SB-069 | | 5/4/2010 | | 0.95 | U | SW |
| 140-SB-069 | | 5/4/2010 | | 1.20 | UJ | |
| 140-SB-069 | | 5/4/2010 | | 8.80 | | |
| 140-SB-069 | | 5/4/2010 | | 11.70 | | |
| 140-SB-069 | | 5/4/2010 | | 0.55 | U | |
| 140-SB-069 | | 5/4/2010 | -2.3 | 0.65 | U | |
| 140-SB-071 | | 5/5/2010 | -1 | 13.20 | | SW |
| 140-SB-072 | | 5/5/2010 | 6.1 | 1.50 | J | SW |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 140-SB-076 | | 5/5/2010 | 0.7 | 4.30 | | SW |
| 140-SB-077 | | 8/18/2010 | | 1.00 | | SW |
| 140-SB-077 | | 8/18/2010 | | 6.80 | | |
| 140-SB-077 | | 8/18/2010 | -1.9 | 4.60 | | |
| 140-SB-105 | | 1/16/2012 | | 14.20 | | SW |
| 140-SB-105 | | 1/16/2012 | -0.8 | 17.10 | | |
| 163-SB-019 | | 11/8/2010 | | 2.2 | | HD |
| 163-SB-019 | | 11/8/2010 | | 0.94 | U | |
| 163-SB-019 | | 11/8/2010 | | 1 | | |
| 163-SB-019 | | 11/8/2010 | | 0.95 | U | |
| 163-SB-019 | | 11/8/2010 | | 0.92 | U | |
| 163-SB-019 | | 11/8/2010 | | 12.5 | | |
| 163-SB-019 | | 11/8/2010 | | 3.5 | | |
| 163-SB-019 | | 11/8/2010 | | 9.5 | | |
| 163-SB-019 | | 11/8/2010 | | 1.1 | | |
| 163-SB-019 | | 11/8/2010 | | 1.5 | U | |
| 163-SB-021 | | 11/8/2010 | | 0.81 | U | HD |
| 163-SB-021 | | 11/8/2010 | | 0.92 | UJ | |
| 163-SB-021 | | 11/8/2010 | | 0.85 | UJ | |
| 163-SB-021 | | 11/8/2010 | | 0.95 | UJ | |
| 163-SB-021 | | 11/8/2010 | | 0.9 | | |
| 163-SB-021 | | 11/8/2010 | | 9.2 | | |
| 163-SB-021 | | 11/8/2010 | | 4.7 | | |
| 163-SB-021 | | 11/8/2010 | | 5.2 | | |
| 163-SB-021 | | 11/8/2010 | | 4 | | |
| 163-SB-021 | | 11/8/2010 | | 4.1 | | |
| 163-SB-026 | | 9/15/2011 | | 3.1 | U | HD |
| 163-SB-027 | | 9/15/2011 | | 6.9 | | HD |
| 163-SB-028 | | 9/14/2011 | | 8.7 | | HD |
| 163-SB-029 | | 9/15/2011 | | 12.6 | | HD |
| 163-SB-030 | | 9/14/2011 | | 7.2 | | HD |
| 163-SB-030 | D | 9/14/2011 | | 9.9 | | |
| 163-SB-031 | | 9/14/2011 | | 13.2 | | HD |
| 163-SB-032A | | 3/22/2012 | | 0.68 | | HD |
| 163-SB-032A | D | 3/22/2012 | | 2.9 | | |
| 163-SB-035 | | 9/12/2011 | | 0.5 | | HD |
| 163-SB-036 | | 9/12/2011 | | 0.7 | | HD |
| 163-SB-037 | | 9/12/2011 | | 10.6 | | HD |
| 163-SB-038 | | 9/14/2011 | | 14.8 | | HD |
| 163-SB-039 | | 9/12/2011 | | 8 | | HD |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 163-SB-040 | | 9/9/2011 | | 0.59 | UJ | HD |
| 163-SB-040 | D | 9/9/2011 | | 0.58 | UJ | |
| 163-SB-051 | | 9/7/2011 | | 18.5 | | HD |
| 163-SB-051 | | 9/7/2011 | | 2.1 | | |
| 163-SB-051 | D | 9/7/2011 | | 2.8 | | |
| 163-SB-052 | | 9/8/2011 | | 0.9 | | HD |
| 163-SB-057 | | 9/7/2011 | | 1.9 | J | HD |
| 163-SB-058 | | 9/7/2011 | | 19.4 | | HD |
| 163-SB-058 | | 9/7/2011 | | 4.1 | | |
| 163-SB-058 | | 9/14/2011 | | 7.6 | | |
| 163-SB-059 | | 9/7/2011 | | 0.61 | UJ | HD |
| 163-SB-061 | | 9/12/2011 | | 0.62 | | HD |
| 163-SB-062 | | 9/9/2011 | | 2.2 | J | HD |
| 163-SB-062 | | 9/12/2011 | | 4.7 | | |
| 163-SB-066 | | 9/12/2011 | | 10.4 | | HD |
| 163-SB-066 | | 9/8/2011 | | 6.8 | | |
| 163-SB-067 | | 9/8/2011 | | 3.4 | J | HD |
| 163-SB-068 | | 9/8/2011 | | 16.4 | J | HD |
| 163-SB-068 | | 9/14/2011 | | 0.52 | U | |
| 163-SB-069 | | 9/7/2011 | | 15.2 | | HD |
| 163-SB-069 | | 9/12/2011 | | 0.81 | | |
| 163-SB-071 | | 10/19/2011 | | 11.4 | | HD |
| 163-SB-076 | | 10/19/2011 | | 1.5 | | HD |
| 163-SB-077 | | 10/19/2011 | | 15.1 | | HD |
| 163-SB-078 | | 10/19/2011 | | 1.5 | | HD |
| 163-SB-078 | | 10/19/2011 | | 8.3 | | |
| 163-SB-078 | D | 10/19/2011 | | 14.1 | | |
| 163-SB-079 | | 10/19/2011 | | 3.7 | | HD |
| 163-SB-080 | | 10/19/2011 | | 2 | | HD |
| 163-SB-080 | | 10/19/2011 | | 3.7 | J | |
| 163-SB-080 | | 10/19/2011 | | 3.9 | J | |
| 163-SB-080 | | 10/19/2011 | | 11.6 | J | |
| 163-SB-081 | | 11/21/2011 | | 1.2 | J | HD |
| 163-SB-081 | | 11/21/2011 | | 1.1 | J | |
| 163-SB-081 | | 11/21/2011 | | 9.8 | J | |
| 163-SB-081 | | 11/21/2011 | | 7.3 | J | |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3B**
**Final Post-Excavation Sidewall Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Target Elevation | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 163-SB-082 | | 10/24/2011 | | 4.5 | | HD |
| 163-SB-084 | | 10/24/2011 | | 3.9 | | HD |
| 163-SB-085 | | 10/24/2011 | | 17.3 | | HD |
| 163-SB-091 | | 12/7/2011 | | 13 | | HD |
| 163-SB-097 | | 1/13/2012 | | 0.48 | UJ | HD |
| 163-SB-100 | | 1/16/2012 | | 9.4 | J | HD |
| 163-SB-100 | D | 1/16/2012 | | 5.2 | J | |
| 163-SB-100 | | 1/16/2012 | | 0.48 | U | |
| 163-SB-110 | | 3/22/2012 | | 1 | UJ | HD |
| 163-SB-113 | | 3/22/2012 | | 4.7 | J | HD |

NOTES:
mg/kg = milligrams per kilogram
SW = post-excavation sidewall sample
SW* = sample defines horizontal limit of hexavalent chromium impacts, but is below the target bottom of excavation elevation. These samples are not counted in Table 1.
SW** = 134-SB-146 delineates an area in the northern portion of Site 163, so it is not counted in the tally for Site 134.
HD = soil sample defines horizontal limit of hexavalent chromium impacts
D = duplicate sample
U = detected below indicated value
J = Estimated Value


Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 073-SB-002 | | 7/14/2008 | 0.48 | 7.20 | J | B |
| 073-SB-007 | | 7/11/2008 | -3.88 | 6.80 | | B |
| 073-SB-008 | | 8/1/2008 | -0.55 | 18.30 | | B |
| 073-SB-009 | | 7/9/2008 | -6.72 | 1.20 | UJ | B |
| 073-SB-010 | | 7/11/2008 | -0.43 | 15.60 | | B* |
| 073-SB-011 | | 7/9/2008 | -1.37 | 5.10 | | B |
| 073-SB-017 | | 4/19/2010 | 0.61 | 9.60 | | B |
| 073-SB-018 | | 4/19/2010 | 0.32 | 14.30 | | B |
| 073-SB-019 | | 4/19/2010 | -3.17 | 9.00 | | B* |
| 073-SB-020 | | 4/19/2010 | -5.30 | 19.80 | | B* |
| 073-SB-021 | | 4/19/2010 | -5.32 | 5.80 | | B |
| 073-SB-024 | | 4/19/2010 | -0.81 | 1.00 | U | B |
| 073-SB-025 | | 4/19/2010 | 5.05 | 6.10 | | B |
| 073-SB-028 | | 4/20/2010 | 3.27 | 8.90 | | B |
| 073-SB-029 | | 4/20/2010 | 3.79 | 9.20 | | B |
| 073-SB-030 | | 4/20/2010 | 2.13 | 11.20 | | B |
| 073-SB-031 | | 12/8/2010 | 0.06 | 15.20 | | B |
| 073-SB-032 | | 4/20/2010 | 2.29 | 14.00 | J | B* |
| 073-SB-033 | | 4/20/2010 | -1.84 | 19.90 | | B |
| 073-SB-034 | | 4/20/2010 | -0.19 | 5.30 | J | B |
| 073-SB-035 | | 4/20/2010 | 1.45 | 10.90 | J | B |
| 073-SB-036 | | 4/20/2010 | -1.01 | 7.30 | | B |
| 073-SB-037 | | 4/21/2010 | -4.23 | 9.10 | | B |
| 073-SB-038 | | 4/21/2010 | 2.26 | 16.80 | | B |
| 073-SB-039 | | 4/21/2010 | 0.62 | 14.80 | | B |
| 073-SB-040 | | 4/21/2010 | 0.18 | 14.10 | | B* |
| 073-SB-041 | | 4/21/2010 | 3.83 | 5.10 | | B* |
| 073-SB-042 | | 4/21/2010 | 5.98 | 3.40 | | B* |
| 073-SB-045 | | 4/21/2010 | -2.19 | 7.60 | | B |
| 073-SB-047 | | 10/25/2010 | -6.90 | 8.30 | | B |
| 073-SB-049 | | 4/23/2010 | 1.10 | 6.00 | | B |
| 073-SB-050 | | 4/23/2010 | 0.28 | 4.10 | | B |
| 073-SB-053 | | 10/25/2010 | 4.27 | 6.80 | | B |
| 073-SB-054 | | 5/24/2010 | 4.44 | 0.96 | U | B*** |
| 073-SB-056 | | 8/5/2010 | 7.50 | 1.40 | | B* |
| 073-SB-057 | | 8/5/2010 | 7.52 | 0.89 | | B* |
| 073-SB-059 | | 8/5/2010 | 2.48 | 2.10 | | B |
| 073-SB-062 | | 8/5/2010 | -4.82 | 10.70 | | B |

Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 073-SB-065 | | 12/8/2010 | -5.04 | 0.53 | U | B |
| 073-SB-066 | | 12/8/2010 | -0.58 | 3.80 | | B |
| 073-SB-075 | | 2/15/2011 | -5.22 | 0.74 | | B |
| 124-PT-03 | | 3/12/2008 | 1.69 | 1.00 | UJ | B |
| 124-PT-04 | | 3/12/2008 | -0.07 | 11.00 | J | B |
| 124-PT-14 | | 3/14/2008 | 2.57 | 19.50 | | B |
| 124-SB-011 | | 9/7/2006 | 1.42 | 4.00 | | B |
| 124-SB-012 | | 10/26/2010 | -1.65 | 0.43 | U | B |
| 124-SB-013 | | 10/26/2010 | -3.48 | 0.48 | U | B |
| 124-SB-021 | | 6/24/2009 | 3.50 | 9.10 | J | B |
| 124-SB-022 | | 6/24/2009 | 4.65 | 19.40 | J | B |
| 124-SB-023 | | 6/24/2009 | -1.25 | 2.40 | U | B |
| 124-SB-024 | | 7/7/2009 | -2.81 | 12.00 | U | B |
| 124-SB-025 | | 7/7/2009 | -3.28 | 12.00 | U | B |
| 124-SB-026 | | 7/8/2009 | -2.80 | 9.30 | U | B |
| 124-SB-027 | | 7/8/2009 | -2.33 | 2.40 | U | B |
| 124-SB-029 | | 7/8/2009 | -2.84 | 3.80 | U | B |
| 124-SB-030 | | 8/3/2009 | -3.35 | 16.00 | U | B |
| 124-SB-031 | | 8/3/2009 | -2.52 | 13.00 | U | B |
| 124-SB-032 | | 8/3/2009 | -2.59 | 16.00 | U | B |
| 124-SB-033 | | 8/3/2009 | -1.27 | 9.10 | U | B |
| 124-SB-035 | | 8/3/2009 | -2.03 | 13.00 | U | B* |
| 124-SB-036 | | 8/3/2009 | -2.15 | 16.00 | U | B* |
| 124-SB-037 | | 8/4/2009 | -1.44 | 13.00 | U | B*** |
| 124-SB-038 | | 8/4/2009 | -0.77 | 14.00 | | B |
| 124-SB-039 | | 8/4/2009 | -2.66 | 0.96 | U | B |
| 124-SB-040 | | 8/4/2009 | -2.88 | 8.90 | | B |
| 124-SB-042 | | 8/4/2009 | 0.28 | 2.60 | U | B |
| 124-SB-043 | | 8/4/2009 | -0.81 | 4.10 | U | B*** |
| 124-SB-044 | | 10/26/2010 | -3.05 | 7.50 | U | B |
| 124-SB-045 | | 8/5/2009 | -1.75 | 7.60 | U | B |
| 124-SB-046 | | 8/5/2009 | 0.79 | 16.80 | | B* |
| 124-SB-047 | | 8/5/2009 | 0.39 | 13.00 | U | B |
| 124-SB-049 | | 8/5/2009 | 1.68 | 2.80 | | B |
| 124-SB-051 | | 8/6/2009 | 1.57 | 3.00 | | B |
| 124-SB-053 | | 8/6/2009 | 0.12 | 2.30 | | B |
| 124-SB-054 | | 8/6/2009 | 1.79 | 6.10 | | B |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 124-SB-066 | | 5/7/2010 | 1.75 | 2.00 | | B |
| 124-SB-067 | | 10/26/2010 | -2.88 | 0.69 | | B*** |
| 124-SB-068 | | 5/7/2010 | -2.81 | 6.30 | U | B |
| 124-SB-069 | | 5/18/2010 | -0.42 | 8.30 | | B |
| 124-SB-071 | | 5/18/2010 | 0.69 | 18.00 | | B* |
| 124-SB-073 | | 5/18/2010 | 2.35 | 0.57 | | B |
| 124-SB-077 | | 10/26/2010 | -2.23 | 1.60 | U | B |
| 124-SB-078 | | 5/21/2010 | -0.99 | 7.20 | U | B |
| 124-SB-079 | | 5/21/2010 | 0.70 | 1.90 | | B* |
| 124-SB-091 | | 12/8/2010 | -2.80 | 7.10 | U | B |
| 124-SB-092 | | 12/8/2010 | -2.20 | 6.80 | U | B |
| 124-SB-109 | | 7/7/2008 | 3.23 | 10.80 | J | B* |
| 124-SB-110 | | 7/7/2008 | -2.25 | 7.30 | U | B |
| 124-SB-117A | | 3/25/2011 | 4.73 | 17.20 | | B |
| 124-SB-121A | | 3/25/2011 | 2.02 | 0.51 | UJ | B |
| 124-SB-122 | | 12/6/2010 | -2.23 | 8.50 | U | B |
| 124-SB-123 | | 10/26/2010 | -2.75 | 7.00 | U | B |
| 124-SB-124 | | 10/26/2010 | 3.16 | 12.20 | | B* |
| 124-SB-125 | | 12/6/2010 | -1.51 | 6.10 | U | B |
| 124-SB-127 | | 11/8/2010 | 1.94 | 1.00 | | B |
| 124-SB-129 | | 3/25/2011 | -0.02 | 0.55 | UJ | B |
| 124-SB-130 | | 11/3/2011 | -0.82 | 11.00 | U | B |
| 124-SB-133 | | 11/3/2011 | -2.30 | 14.00 | U | B |
| 124-SB-134 | | 11/3/2011 | -2.25 | 14.00 | U | B |
| 124-SB-135 | | 11/11/2011 | -1.79 | 4.90 | U | B |
| 124-SB-136 | | 1/17/2012 | -2.29 | 12.00 | U | B |
| 124-SB-138 | | 1/17/2012 | -1.58 | 17.00 | U | B |
| 124-SB-139 | | 3/22/2012 | -1.73 | 6.80 | U | B |
| 125-PT-16 | | 4/16/2008 | 0.95 | 2.10 | U | B* |
| 125-PT-17 | | 10/26/2010 | -4.74 | 7.60 | U | B*** |
| 125-PT-20 | | 4/16/2008 | 0.73 | 12.50 | J | B |
| 125-PT-21 | | 4/16/2008 | 0.30 | 11.20 | J | B* |
| 125-PT-22 | | 4/17/2008 | -4.33 | 13.10 | J | B |
| 125-SB-007 | | 7/7/2008 | 0.60 | 9.20 | | B |
| 125-SB-009 | | 6/26/2008 | 0.85 | 6.60 | | B* |
| 125-SB-009A | | 7/30/2008 | -2.68 | 2.30 | U | B |
| 125-SB-017 | | 6/23/2009 | -3.49 | 9.20 | U | B |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 125-SB-018 | D | 6/23/2009 | -3.85 | 7.60 | U | B |
| 125-SB-019 | | 6/23/2009 | -3.28 | 11.00 | U | B |
| 125-SB-020 | | 6/23/2009 | -3.42 | 12.00 | U | B |
| 125-SB-021 | | 6/23/2009 | -4.00 | 7.80 | U | B |
| 125-SB-022 | | 6/23/2009 | -3.74 | 6.20 | U | B |
| 125-SB-024 | | 6/23/2009 | 0.34 | 2.30 | U | B* |
| 125-SB-025 | | 6/23/2009 | 0.41 | 2.00 | U | B |
| 125-SB-026 | | 6/24/2009 | 1.25 | 2.60 | U | B |
| 125-SB-027 | | 6/24/2009 | 1.04 | 2.10 | U | B |
| 125-SB-028 | | 6/24/2009 | 0.46 | 2.00 | U | B* |
| 125-SB-029 | | 6/25/2009 | 0.40 | 2.20 | U | B |
| 125-SB-030 | | 6/25/2009 | 0.75 | 2.40 | | B |
| 125-SB-031 | | 6/25/2009 | 1.08 | 2.00 | UJ | B |
| 125-SB-032 | | 6/25/2009 | 0.63 | 2.30 | U | B |
| 125-SB-033 | | 6/26/2009 | 0.70 | 1.20 | | B* |
| 125-SB-034 | | 6/26/2009 | -3.61 | 9.20 | U | B |
| 125-SB-035 | | 6/26/2009 | -1.52 | 2.30 | U | B |
| 125-SB-037 | | 6/26/2009 | -3.45 | 12.00 | U | B |
| 125-SB-038 | | 6/29/2009 | -3.34 | 4.50 | U | B |
| 125-SB-039 | | 6/29/2009 | -3.35 | 4.70 | U | B |
| 125-SB-044 | | 7/2/2009 | 0.70 | 1.20 | U | B |
| 125-SB-045 | | 7/2/2009 | 3.10 | 2.60 | | B* |
| 125-SB-046 | | 7/2/2009 | 0.60 | 8.50 | | B |
| 125-SB-048 | | 7/2/2009 | 0.50 | 7.70 | | B |
| 125-SB-049 | | 7/2/2009 | 0.60 | 7.10 | | B |
| 125-SB-050 | | 7/2/2009 | 1.20 | 4.00 | | B |
| 125-SB-052 | | 7/2/2009 | -2.40 | 2.90 | | B |
| 125-SB-053 | | 7/2/2009 | 0.20 | 9.80 | | B |
| 125-SB-055 | | 7/6/2009 | -2.20 | 1.60 | U | B |
| 125-SB-057 | | 7/6/2009 | 0.20 | 0.98 | U | B |
| 125-SB-061 | | 7/6/2009 | -2.40 | 3.20 | | B |
| 125-SB-062 | | 7/6/2009 | -2.30 | 2.40 | | B* |
| 125-SB-065 | | 7/7/2009 | 0.40 | 2.00 | U | B |
| 125-SB-066 | | 7/7/2009 | 0.60 | 4.00 | | B |
| 125-SB-069 | | 8/7/2009 | 2.07 | 2.00 | U | B |
| 125-SB-070 | | 5/4/2010 | -2.10 | 5.40 | J | B |
| 125-SB-071 | | 5/4/2010 | -3.30 | 4.00 | UJ | B |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 125-SB-072 | | 5/4/2010 | -3.40 | 2.50 | UJ | B |
| 125-SB-073 | | 5/4/2010 | -1.20 | 13.90 | J | B |
| 125-SB-074 | | 5/4/2010 | -1.40 | 7.70 | J | B |
| 125-SB-078 | | 5/6/2010 | -0.94 | 0.49 | U | B |
| 125-SB-086 | | 5/7/2010 | -1.70 | 2.50 | U | B |
| 125-SB-089 | | 10/26/2010 | 1.67 | 11.70 | | B |
| 125-SB-090 | | 3/23/2011 | -1.00 | 15.00 | | B |
| 134-SB-012 | | 8/1/2008 | -1.07 | 18.00 | J | B |
| 134-SB-013 | | 8/1/2008 | -5.63 | 2.00 | UJ | B |
| 134-SB-014 | | 6/24/2008 | 2.40 | 11.00 | | B |
| 134-SB-015 | | 8/1/2008 | -0.58 | 14.80 | | B |
| 134-SB-016R | | 9/27/2011 | -6.65 | 2.20 | | B |
| 134-SB-019 | | 6/18/2008 | -0.60 | 6.40 | | B |
| 134-SB-024 | | 6/19/2008 | -5.65 | 3.00 | UJ | B |
| 134-SB-026 | | 6/19/2008 | -0.43 | 3.30 | | B |
| 134-SB-032 | | 6/19/2008 | -6.12 | 1.40 | UJ | B |
| 134-SB-033 | | 6/19/2008 | 2.38 | 2.50 | | B |
| 134-SB-042 | | 7/8/2009 | -7.80 | 6.50 | U | B |
| 134-SB-043 | | 7/8/2009 | -7.40 | 5.90 | U | B |
| 134-SB-044 | | 7/8/2009 | -7.60 | 7.30 | U | B |
| 134-SB-046 | | 7/8/2009 | -7.00 | 2.90 | U | B |
| 134-SB-047 | | 7/15/2009 | -6.50 | 8.60 | U | B |
| 134-SB-049 | | 10/25/2010 | -7.97 | 4.50 | U | B |
| 134-SB-051 | | 7/15/2009 | 1.78 | 16.80 | | B |
| 134-SB-052 | | 7/15/2009 | -1.20 | 1.00 | U | B |
| 134-SB-054 | | 7/16/2009 | -7.13 | 6.50 | U | B |
| 134-SB-056 | | 7/28/2009 | 1.37 | 15.00 | | B |
| 134-SB-057 | | 7/28/2009 | 0.77 | 12.70 | | B |
| 134-SB-060 | | 7/28/2009 | 0.42 | 10.50 | J | B |
| 134-SB-061 | | 7/29/2009 | 1.24 | 15.70 | | B* |
| 134-SB-062 | | 7/29/2009 | 0.89 | 13.90 | | B* |
| 134-SB-063 | | 7/29/2009 | -6.65 | 2.80 | U | B |
| 134-SB-064 | | 7/29/2009 | -5.20 | 3.20 | U | B |
| 134-SB-065 | | 7/30/2009 | -6.67 | 1.40 | UJ | B |
| 134-SB-078 | | 4/22/2010 | -5.20 | 1.30 | U | B |
| 134-SB-080 | | 4/22/2010 | -7.94 | 5.30 | U | B |
| 134-SB-083 | | 4/22/2010 | -6.38 | 1.20 | | B |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 134-SB-084 | | 4/23/2010 | -5.60 | 4.30 | | B |
| 134-SB-085 | | 4/23/2010 | -6.40 | 2.90 | U | B |
| 134-SB-086 | | 4/23/2010 | -6.40 | 3.50 | | B |
| 134-SB-098 | | 8/6/2010 | 0.08 | 0.49 | U | B* |
| 134-SB-113 | | 3/25/2011 | -7.50 | 3.10 | U | B |
| 134-SB-114 | | 6/20/2011 | -6.59 | 0.6 | UJ | B |
| 134-SB-115 | | 6/20/2011 | -8.38 | 4 | J | B |
| 134-SB-116 | | 6/20/2011 | 1.20 | 1.8 | | B |
| 134-SB-117 | | 6/20/2011 | 0.85 | 1.3 | J | B* |
| 134-SB-118 | | 6/22/2011 | -7.89 | 0.71 | U | B |
| 134-SB-119 | | 6/22/2011 | -5.20 | 10.1 | | B* |
| 134-SB-120 | | 6/22/2011 | -8.68 | 6.3 | J | B |
| 134-SB-121 | | 6/22/2011 | -7.69 | 10.8 | J | B |
| 134-SB-122 | | 6/22/2011 | -5.77 | 12.5 | J | B |
| 134-SB-123 | | 6/23/2011 | -2.71 | 16.9 | | B |
| 134-SB-124 | | 6/23/2011 | -2.30 | 17.6 | | B |
| 134-SB-125 | | 6/23/2011 | -0.79 | 17.5 | | B* |
| 134-SB-127 | | 6/24/2011 | -4.47 | 0.87 | J | B |
| 134-SB-129 | | 6/23/2011 | -6.68 | 1.3 | | B |
| 134-SB-130 | | 6/23/2011 | -0.70 | 16 | | B* |
| 134-SB-131 | | 6/24/2011 | -6.10 | 1.4 | J | B |
| 134-SB-132 | | 6/24/2011 | -0.64 | 9.9 | | B |
| 134-SB-133 | | 6/24/2011 | -0.71 | 15.6 | | B |
| 134-SB-134 | | 6/24/2011 | 1.30 | 16.2 | J | B* |
| 134-SB-135 | | 6/27/2011 | 4.48 | 0.5 | U | B* |
| 134-SB-136 | | 6/27/2011 | -1.25 | 12.1 | | B |
| 134-SB-137 | | 6/27/2011 | -1.46 | 10.8 | | B |
| 134-SB-138 | | 6/27/2011 | -1.13 | 0.79 | J | B |
| 134-SB-139 | | 6/27/2011 | 2.00 | 2.1 | | B* |
| 134-SB-140 | | 6/27/2011 | -1.18 | 7.6 | J | B |
| 134-SB-141 | | 9/27/2011 | -8.91 | 3 | | B |
| 134-SB-147 | | 10/19/2011 | -6.80 | 0.71 | | B*** |
| 134-SB-150 | | 11/11/2011 | -6.40 | 16.00 | U | B |
| 134-SB-154 | | 1/13/2012 | 4.10 | 9.6 | J | B |
| 134-SB-155 | | 1/13/2012 | 4.10 | 0.49 | U | B |
| 134-SB-158 | | 1/18/2012 | -5.80 | 0.85 | | B |
| 134-SB-S08 | | 5/30/1997 | -7.41 | 3.70 | UJ | B |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 140-SB-007 | | 10/25/2010 | -6.06 | 2.20 | J | B |
| 140-SB-009 | | 7/11/2008 | -5.36 | 11.90 | | B |
| 140-SB-010 | | 10/25/2010 | -4.43 | 18.70 | | B |
| 140-SB-011 | | 7/7/2008 | 1.86 | 16.70 | J | B* |
| 140-SB-012 | | 6/24/2008 | 0.80 | 9.50 | J | B* |
| 140-SB-013 | | 6/25/2008 | -0.04 | 17.50 | J | B* |
| 140-SB-018 | | 8/7/2008 | -4.80 | 12.00 | U | B |
| 140-SB-026 | | 9/22/2008 | -2.68 | 19.60 | | B |
| 140-SB-028 | | 7/16/2009 | 4.30 | 1.80 | | B* |
| 140-SB-029 | | 7/16/2009 | -0.98 | 16.30 | J | B |
| 140-SB-030 | | 7/16/2009 | 2.54 | 0.98 | U | B* |
| 140-SB-033 | | 7/16/2009 | 5.76 | 12.10 | | B* |
| 140-SB-035 | | 7/17/2009 | -6.86 | 3.00 | U | B |
| 140-SB-038 | | 7/17/2009 | -6.60 | 13.00 | U | B |
| 140-SB-040 | | 7/30/2009 | -5.30 | 3.20 | UJ | B |
| 140-SB-041 | | 7/31/2009 | -6.74 | 15.00 | U | B |
| 140-SB-042 | | 7/31/2009 | -6.46 | 4.10 | UJ | B |
| 140-SB-043 | | 7/31/2009 | -0.15 | 5.10 | | B |
| 140-SB-044 | | 7/31/2009 | -4.80 | 16.50 | | B* |
| 140-SB-046 | | 8/7/2009 | -4.18 | 4.30 | U | B |
| 140-SB-047 | | 8/10/2009 | -5.70 | 2.00 | UJ | B |
| 140-SB-048 | | 8/10/2009 | -5.00 | 1.60 | U | B |
| 140-SB-049 | | 8/10/2009 | 0.30 | 2.30 | | B* |
| 140-SB-050 | | 8/10/2009 | -4.24 | 2.70 | UJ | B |
| 140-SB-051 | | 8/11/2009 | -6.50 | 8.30 | U | B |
| 140-SB-062 | | 5/3/2010 | -7.80 | 4.60 | U | B |
| 140-SB-063 | | 5/3/2010 | -7.80 | 7.90 | U | B |
| 140-SB-064 | | 5/3/2010 | -6.20 | 0.85 | UJ | B |
| 140-SB-065 | | 5/3/2010 | -5.80 | 0.82 | UJ | B |
| 140-SB-066 | | 5/4/2010 | -6.30 | 1.70 | | B |
| 140-SB-067 | | 5/4/2010 | -3.59 | 5.30 | U | B*** |
| 140-SB-068 | | 5/4/2010 | -2.72 | 1.40 | | B |
| 140-SB-070 | | 5/5/2010 | -0.56 | 17.50 | | B |
| 140-SB-074 | | 5/5/2010 | -2.86 | 2.80 | U | B |
| 140-SB-075 | | 5/5/2010 | -3.30 | 5.30 | UJ | B |
| 140-SB-078 | | 10/27/2010 | -1.40 | 11.10 | | B |
| 140-SB-079 | | 10/27/2010 | 0.10 | 15.00 | | B* |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 140-SB-080 | D | 10/27/2010 | 2.60 | 7.40 | | B* |
| 140-SB-081 | | 10/27/2010 | -0.40 | 11.20 | | B* |
| 140-SB-082 | | 10/27/2010 | -5.40 | 0.94 | U | B |
| 140-SB-083 | | 10/29/2010 | -1.40 | 7.60 | | B |
| 140-SB-084 | | 10/29/2010 | 0.60 | 1.00 | U | B* |
| 140-SB-085 | | 10/29/2010 | 0.60 | 6.70 | | B* |
| 140-SB-086 | | 10/29/2010 | -0.40 | 1.40 | | B* |
| 140-SB-088 | | 11/1/2010 | 0.10 | 1.80 | | B* |
| 140-SB-089 | | 11/1/2010 | 0.94 | 11.10 | J | B* |
| 140-SB-090 | | 11/1/2010 | -3.00 | 4.90 | UJ | B |
| 140-SB-091 | | 11/2/2010 | 1.00 | 0.92 | UJ | B* |
| 140-SB-094 | | 3/23/2011 | -3.40 | 1.10 | U | B |
| 140-SB-103 | | 11/8/2011 | -7.30 | 9.00 | U | B |
| 140-SB-104 | | 11/11/2011 | -2.00 | 4.60 | U | B |
| 140-SB-N07 | | 8/22/1997 | -7.00 | 2.80 | U | B |
| 163-SB-002A | | 9/9/2011 | | 4.1 | UJ | VD |
| 163-SB-003 | | 11/2/2010 | | 3.3 | | VD |
| 163-SB-006 | | 11/2/2010 | | 2.1 | J | VD |
| 163-SB-007 | | 11/2/2010 | | 0.93 | | VD |
| 163-SB-008 | | 11/3/2010 | | 10.8 | | VD |
| 163-SB-009 | | 11/3/2010 | | 12.5 | | VD |
| 163-SB-010 | | 11/3/2010 | | 9.6 | | VD |
| 163-SB-011 | | 11/3/2010 | | 12.3 | | VD |
| 163-SB-012 | | 11/3/2010 | | 0.78 | | VD |
| 163-SB-013 | | 11/3/2010 | | 0.9 | U | VD |
| 163-SB-014 | | 11/3/2010 | | 13.9 | | VD |
| 163-SB-015 | | 11/3/2010 | | 9.5 | J | VD |
| 163-SB-015 | | 11/3/2010 | | 1 | U | VD |
| 163-SB-016 | | 11/3/2010 | | 2.8 | J | VD |
| 163-SB-017 | | 11/8/2010 | | 15.5 | | VD |
| 163-SB-018 | | 11/8/2010 | | 1 | U | VD |
| 163-SB-020 | | 11/8/2010 | | 1.1 | | VD |
| 163-SB-023 | | 11/8/2010 | | 1.1 | UJ | VD |
| 163-SB-025 | | 11/8/2010 | | 1.9 | | VD |
| 163-SB-044 | | 9/8/2011 | | 1.4 | J | VD |
| 163-SB-050 | | 9/8/2011 | | 9.9 | J | VD |
| 163-SB-060 | | 9/7/2011 | | 6.1 | | VD |



Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**TABLE 3C**
**Final Post-Excavation Base Samples**
**Hexavalent Chromium Results**
Study Area 6 South
Sites 073, 124, 125, 134, 140, & 163
Jersey City, New Jersey

| Location ID | D | Date Sampled | Bottom Sample Elevation (msl) | Hex Cr Concentration (mg/kg) | Qual | Designation |
|---|---|---|---|---|---|---|
| 163-SB-063 | | 9/9/2011 | | 5.4 | J | VD |
| 163-SB-064 | | 9/9/2011 | | 0.48 | UJ | VD* |
| 163-SB-072 | | 10/19/2011 | | 10.2 | | VD |
| 163-SB-073 | | 10/19/2011 | | 0.55 | | VD |
| 163-SB-092 | | 12/7/2011 | | 0.44 | U | VD |
| 163-SB-093 | | 12/7/2011 | | 1.8 | | VD |
| 163-SB-096 | | 1/13/2012 | | 4.8 | | VD |
| 163-SB-101 | | 1/16/2012 | | 2 | | VD |
| 163-SB-102 | | 1/19/2012 | | 3 | | VD |
| 163-SB-103 | | 1/19/2012 | | 7.1 | J | VD |
| 163-SB-104 | | 2/2/2012 | | 0.64 | J | VD |
| 163-SB-105 | | 2/2/2012 | | 4.1 | J | VD |
| 163-SB-106 | | 2/2/2012 | | 10.8 | J | VD |
| 163-SB-107 | | 2/2/2012 | | 1.6 | | VD |
| 163-SB-108 | | 2/2/2012 | | 15.2 | J | VD |
| 163-SB-112 | | 3/22/2012 | | 15.1 | J | VD |
| 163-SB-114 | | 3/22/2012 | | 5.8 | J | VD |

NOTES:
mg/kg = milligrams per kilogram
B = post-excavation base sample
B* = post-excavation base sample that may be excavated due to multi-depth excavation extensions.
B** = post-excavation base sample not counted in Table 2 due to the proximity of a shallower post-excavation base sample that is counted in Table 2.
B*** = new bottom samples added based upon excavation means and methods
VD = soil sample defines vertical limit of hexavalent chromium impacts
VD* = vertical delineation sample that may be excavated due to multi-depth excavation extensions.
D = duplicate sample
U = detected below indicated value
J = Estimated Value


Created by: EGC 01/16/14
Checked by: DEN 01/16/14

**Table 1. SA-6 South Reference Confirmation Samples**

| Excavation Area | Base Confirmation Reference Boring | Northing | Easting | Base Confirmation Target Elevation (ft) | Proposed Bottom of Excavation (ft) |
|---|---|---|---|---|---|
| Area 1 | 124-SB-043 | 684256.35 | 602965.47 | -0.8 | (1.20) |
| Area 2 | 124-SB-073 | 684204.71 | 602890.72 | 2.4 | 2.10 |
| Area 3 | 124-SB-051 | 684296.42 | 602850.46 | 1.6 | 0.40 |
| Area 4 | 124-SB-121A | 684412.86 | 602766.12 | 2.0 | (1.20) |
| Area 5 | 124-SB-021 | 684412.28 | 602733.90 | 3.5 | 2.10 |
| Area 6 | 124-SB-136 | 684463.22 | 602783.72 | -2.3 | (2.50) |
| Area 7 | 125-PT-21 | 684473.00 | 602698.00 | 0.3 | (1.20) |
| Area 8 | 125-SB-029 | 684538.33 | 602583.70 | 0.4 | 0.40 |
| Area 9 | 125-SB-090 | 684511.63 | 602592.12 | -1.0 | (1.20) |
| Area 10 | 125-SB-069 | 684576.57 | 602529.91 | 2.1 | 2.10 |
| Area 11 | 125-SB-073 | 684675.38 | 602508.17 | -1.2 | (1.20) |
| Area 12 | 140-SB-033 | 684629.91 | 602309.51 | 5.8 | 5.70 |
| Area 13 | 140-SB-089 | 684660.67 | 602300.11 | 0.9 | 0.40 |
| Area 14 | 140-SB-083 | 684744.90 | 602306.70 | -1.4 | (2.50) |
| Area 15 | 134-SB-032 | 685001.00 | 602117.00 | -6.1 | (4.30) |
| Area 16 | 134-SB-061 | 685068.47 | 601973.95 | 1.2 | (2.50) |
| Area 17 | 134-SB-052 | 685126.33 | 601904.53 | -1.2 | (1.20) |
| Area 18 | 134-SB-033 | 685159.00 | 601914.00 | 2.4 | 2.10 |
| Area 19 | 134-SB-014 | 685266.00 | 601776.00 | 2.4 | 0.40 |
| Area 20 | 134-SB-137 | 685234.55 | 601798.48 | -1.5 | (2.50) |
| Area 21 | 134-SB-136 | 685225.05 | 601760.91 | -1.2 | (1.20) |
| Area 22 | 134-SB-124 | 685159.89 | 601776.21 | -2.3 | (2.50) |
| Area 23 | 134-SB-134 | 685242.19 | 601665.81 | 1.3 | 0.40 |
| Area 24 | 134-SB-129 | 685165.87 | 601710.70 | -6.7 | (7.50) |
| Area 25 | 134-SB-120 | 685113.61 | 601700.17 | -8.7 | (8.70) |
| Area 26 | 134-SB-115 | 685122.79 | 601623.09 | -8.4 | (8.40) |
| Area 27 | 134-SB-116 | 685100.03 | 601649.96 | 1.2 | (7.50) |
| Area 28 | 134-SB-141 | 685042.31 | 601722.72 | -8.9 | (8.90) |
| Area 29 | 134-SB-154 | 685024.00 | 601763.40 | 4.1 | 4.20 |
| Area 30 | 073-SB-011 | 685212.00 | 601570.00 | -1.4 | (2.50) |
| Area 31 | 073-SB-017 | 685193.11 | 601579.80 | 0.6 | (1.20) |
| Area 32 | 073-SB-030 | 685300.26 | 601630.92 | 2.1 | 2.10 |
| Area 33 | 073-SB-033 | 685344.33 | 601618.92 | -1.8 | (2.50) |
| Area 34 | 073-SB-032 | 685324.74 | 601663.53 | 2.3 | 2.10 |
| Area 35 | 073-SB-032 | 685324.74 | 601663.53 | 2.3 | 0.40 |
| Area 36 | 073-SB-008 | 685390.00 | 601606.00 | -0.6 | (1.20) |
| Area 37 | 073-SB-038 | 685395.78 | 601557.27 | 2.3 | 2.10 |
| Area 38 | 073-SB-037 | 685378.76 | 601531.70 | -4.2 | (4.30) |
| Area 39 | 073-SB-009 | 685288.00 | 601466.00 | -6.7 | (7.50) |
| Area 40 | 073-SB-042 | 685448.92 | 601515.04 | 6.0 | 5.70 |
| Area 41 | 134-SB-026 | 684916.00 | 601955.00 | -0.4 | (1.20) |

Notes:

1. This table identifies the base confirmation sample to be referneced when no sample falls within a particular excavation cell.
2. Refer to Figure 2 Color Coded Excavation Bottoms for cell and excavation area locations.

**FINAL DCB 007 –SA-6 DCB FRENCH DRAIN**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB Type: Major (a)<br>Effective Date: 3/25/14 |
| Project Location: SA-6 NORTH, SA6-SOUTH | Associated RFI: |
| Title: CONTINGENT GW EXTRACTION SYSTEM | ☐ Yes, RFI No. ___ ☑ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. This Bulletin describes a major change to that extraction system and explains the basis for that change.

Section 10.2 of the Design Report stated "Honeywell reserves the right to propose alternative groundwater extraction designs capable of meeting the criteria stated in Article III.A (58) of the Consent Decree. Additionally, Note 3 on the Contingent GW Extraction System Drawings SA-6 South C-201,202 and 203 and SA-6 North CN-201, 202 and 203 further elaborated that "Honeywell will continue to evaluate pertinent information gathered through dewatering and other construction operations. This information will be used to calibrate the groundwater capture model. Subject to the results of that model calibration and evaluation of the system design Honeywell may propose alternative groundwater extraction designs".

The SA-6 South Groundwater Modeling Report Appendix B Section 5 indicates that Honeywell evaluated various pumping scenarios including the option of French Drains/Central drain. The results of the central/French drain scenario were shown in Figure 5-3. From a modeling perspective it was concluded that the drain provided equivalent performance to the 9 wells.

Consistent with the approach indicated in the Design report, Honeywell has continued to evaluate data collected during the construction dewatering and excavation. Observations of the well point dewatering system have indicated a great deal of variability in hydraulic properties from point to point. Observation of the excavation has also shown significant variability in soil types and permeabilities.

Based on an evaluation of this variability and in consideration of the reduced maintenance advantages associated with the French drain system, Honeywell is proposing to modify the design to change the wells to a French Drain. This proposal is consistent with paragraph 58 of the First Amended Consent Decree on Remediation and Redevelopment of Study Area 6 North. This design change will impact drawings C-201, 202, 203 and CN-201,202,203. The use of trenches also

reduces the number of pumps, control panels, and cap penetrations. This will result in changes to the electrical drawings E-301, 302, 303 and EN-301-302 and 303.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Design changed based on information gathered during construction<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected:<br>Contingent GW system plans and Profiles 201-103<br>Electrical Drawings 301-303<br>C306 Well/Pump Detail |
| Honeywell (AP) Review:<br>Individual Discipline | Initial [signature] Date 12/20/16 |
| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**FINAL DCB 007.1 – SA-6 SOUTH CGWES TRENCH**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.1 Major<br>Effective Date: 06/10/14 |
| Project Location: SA-6 NORTH, SA6-SOUTH<br>Title: CONTINGENT GW EXTRACTION SYSTEM | Associated RFI:<br>☐ Yes, RFI No. ___ ☑ None |
| REPLACE WELLS WITH TRENCHES<br>Contractor (Subcontractor): Entact | Project No.: 3480130377 |

Description of Change/Modification:

DCB-007 has been issued to document changes to the Groundwater Removal System Design. This change includes changing from recovery wells to a "French drain" system. DCB 007 design will be issued is sections to allow for a "fast tracked" design and installation process.

Stage 1 (DCB-007.1) is limited to the French drain installation and the lower sections of the pump and access station manholes for SA-6 South. (see attached memo)

**The Drawings have certain design details clouded. These details have not been finalized and have not been issued for construction.**

**Subsequent stages of the design including the design for the SA-6N Groundwater Collection System will be issued under the DCB – 007 number. Examples DCB -007.2, DCB- 007.3.**

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☑ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Design changed based on information gathered during construction<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☐ No |
| Additional Comments: | Design Documents Affected:<br>Contingent GW system plans and Profiles 201-103<br>Electrical Drawings 301-303<br>C306 Well/Pump Detail |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |

| | |
|---|---|
| (Name / Signature): 6/10/14 | Does DCB Result in CCO? ☑ Yes(b) ☐ No<br>Date: |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

| | | | |
|---|---|---|---|
| Date: | **June 6, 2014** | cc: | **Joe Clifford, PE – Amec**<br>**Eric Christodoulatos - Amec** |
| From: | **Geoff Shallard, P.E.** | | |
| To: | **Stuart Bills - Amec** | | |
| Subject: | **DCB-007.1** | | |

DCB-007 has been issued to document changes to the Groundwater Removal System Design. This change includes changing from recovery wells to a "French drain" system

The new design will include installation of the following.

- a french drain including 8 inch HDPE perforated piping and 1 ½ inch crushed stone
- pump station manholes and associate frames and covers
- cleanout/access manholes and associated covers
- pumps and associated power and controls
- forcemain

Incidental to the basic design changes will include

- revisions to geomembrane liner grading
- revisions to final grades in the vicinity of pump stations

To facilitate progress the design details will be released in stages.

Stage 1 (DCB-007.1) is limited to the French drain installation and the lower sections of the pump and access station manholes for SA-6 South.

**The Drawings have certain design details clouded. These details have not been finalized and <u>have not been</u> issued for construction.**

**Subsequent stages of the design including the design for SA-6N will be issued under the DCB – 007 number. Examples DCB -007.2, DCB- 007.3.**

The pump station manhole should be constructed to the surcharge grade to allow for use of the system for groundwater control during surcharge and remedy construction prior to

capping. Manholes and the drain system will settle as the site consolidates. As a result flexibility needs to be retained to allow for setting access hatches to final grades. Temporary pumps will be used during the remedy.

| Drawing # | Title | Comments | Location |
|---|---|---|---|
| C-307 | Groundwater Extraction Trench Details | | STUDY AREA 6-South |
| C-201 | Groundwater Extraction Trench Plan and Profile | 0+00 to 9+50 | STUDY AREA 6-South |
| C-202 | Groundwater Extraction Trench Plan and Profile | 9+50 to 19+00 | STUDY AREA 6-South |
| C-203 | Groundwater Extraction Trench Plan and Profile | 19+00 to 22+40 | STUDY AREA 6-South |

Sincerely,


**Amec Environment & Infrastructure, Inc.**


Geoff Shallard

Associate Project Manager

**Attachments:**

Drawings C-201, C-202, C-203 C-307




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 06/06/14 | DCB 007-1 | TDD | SGS |
| DSGN | TDD | DR | RJR | CHK | TDD | APVD | SGS |

© 2014 HONEYWELL INTERNATIONAL INC. INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\C-201 Cont Ground Water Extraction Sys.dwg PLOT DATE: Fri, 06 Jun 2014 PLOT TIME: 12:52 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 06/06/14 | DCB 007-1 | TDD | RJR | TDD | TDD SGS |
| DSGN | TDD | | | | | SGS APVD |

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION
TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\C-202 Cont Ground Water Extraction Sys.dwg PLOT DATE: Fri, 06 Jun 2014 PLOT TIME: 1:00 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 06/06/14 | TDD | RJR | TDD | TDD |

REVISION: DCB 007-1

| BY | APVD |
|---|---|
| TDD | SHM |
| SGS | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2109, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd., Suite 113
Hamilton, NJ, 08619
(609) 584-2500
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\C-203 Cont Ground Water Extraction Sys.dwg PLOT DATE: Fri, 06 Jun 2014 PLOT TIME: 1:07 PM




## GROUNDWATER TRENCH TEMPORARY CONDITION (CA)

NTS

C–201 | C–307
C–202
C–203





## LINER ANCHOR TO CONCRETE STRUCTURE (CE)

NTS


TYP | C–307

## NOTES:

1. THE CONTRACTOR WILL LAY OUT THE ALIGNMENT. THE ALIGNMENT WILL BE INSPECTED BY THE CONTRACTOR AND ENGINEER PRIOR TO INITIATING INSTALLATION IN ANY AREA. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES, PILES, AND SURCHARGE MONITORING STATIONS.
2. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
3. CONTRACTOR TO USE PLATE BOLTED TO MANHOLE OR SIMILAR ARRANGEMENT TO BE APPROVED BY THE ENGINEER FOR COMBINING THE PITLESS ADAPTER AND SECONDARY CONTAINMENT.
4. PLACE STONE LOOSE IN TRENCH. RUN PLATE COMPACTOR OR EQUAL PRIOR TO INSTALLING FABRIC.
5. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.





PLAN VIEW




## TYPICAL ACCESS MANHOLE FINAL CONDITION STA.=3+63±, STA.=8+90±, STA.=14+35± (CB)

NTS


C–201 | C–307
C–202





## PIPE PERFORATIONS (CD)

NTS

TYP | C–307




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)

NTS

C–203 | C–307

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 06/06/14 | TDD | RJR | TDD | APVD |
| | REVISION | | | BY | APVD |
| | DCB 007-1 | | | TDD | SGS |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-307 |
| SHEET | OF 66 |

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**FINAL DCB 007.3 – SA-6 SOUTH CGWES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.3 Major (a)<br>Effective Date: 02/12/15 |
| Project Location: SA-6 SOUTH | Associated RFI: |
| Title: GW EXTRACTION SYSTEM | o Yes, RFI No. NA_ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench had not been finalized.
DCB-007.2 provided the details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.
DCB-007.3 provides the details for the SA-6S groundwater collection trenches and associated electrical supply and groundwater discharge piping.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. The revised Design uses a trench design. Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.3 impacts the following drawings
The following Issued for Construction Drawings Extraction System that was based on 9 extraction wells are deleted

- C-201 Plan and Profile
- C-202 Plan and Profile
- C-203 Plan and Profile
- C-304 System Details

The following drawings for the Trench design were added.

- C-201 Trench Plan and Profile
- C-202 Trench Plan and Profile
- C-203 Trench Plan and Profile
- C-204 Discharge Force Main Plan and Profile)
- C-304 Details
- C-306 Details
- C-310 Details).

The changes from the well concept to the trench will also impact the Electrical Drawings. E-101, E-301, E-302 and E-303. The Electrical changes will be issued separately under DCB 007.4. It is noted that DCB 007.2 and DCB 007.3 does show the details for all pumps, motors and controls for the trench design.

The changes from the well concept to the trench will also impact the Geomembrane Liner Grading. The Geomembrane liner changes will be issued separately under DCB 007.5.

Note; piezometric pairs will be installed as shown on both SA-6N and SA-6S. The piezometers on north were previously shown as clouded/temporarily deferred.


| Reason for Change/Modification: | Explanation or Reason: Design changed based on information gathered during construction |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No<br><br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system plans and profiles-see drawing list in description |


| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |

| (Name / Signature): | Does DCB Result in CCO? ☑ Yes (b) ☐ No |
|---|---|
| Samuel G Shallard | Date: 2/16/15 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL, OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON CASKETS.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 02/13/15 | TDD | | | TDD | SGS | SGS |
| 1 | 06/06/14 | | | | | TDD | SGS |

REVISION
DCB 007.3
DCB 007

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELLUERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:44 PM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | TDD | RJR | TDD |
| 1 | 06/06/14 | DCB 007 | TDD | SGS | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS | SGS |
| | | REVISION | BY | APVD | |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 Angelica Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SHM |
| DSGN | TDD | DR RJR | CHK TDD | APVD SGS |

SAMUEL G. SHALLARD
2/13/15
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | | BY | APVD |
| 3 | 02/13/15 | TDD | TDD | RJR | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | | RJR | SGS |
| 1 | 05/14/14 | DCB 007 | | TDD | SHM |
| | | REVISION | | RJR | APVD |
| | | DCB 007.3 | TDD | TDD | SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2529
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |





NOTES:

1. USE THUNDERLINE LINK–SEAL TYPE LS 300–C FOR 2"ø OR 3" ø PIPELINES AND TYPE LS 425–C FOR 1"ø AND 1–1/4" PIPELINES OR EQUAL AT ALL MANHOLES AND STRUCTURES.
2. USE PRESSURE GAGE AND PROBE ON PIPELINES THAT SLOPE UPWARDS FROM STRUCTURES ONLY, BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK–JOINT FLEXIBLE MANHOLE SLEEVE OR KOR–N–SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.

## TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL — X


NTS — C–304 | C–306




IN THE LEAK DETECTION ROAD BOXES WHERE THE TOP OF THE TRANSITION PIECE IS CLOSE TO THE UNDERSIDE OF THE ROAD BOX COVER A THREADED FLAT STEEL CAP IS INSTALLED DIRECTLY ON THE THREADED TRANSITION PIECE. A THREADED STEEL PLUG IS INSTALLED IN THE REMAINING LEAK DETECTION RISERS.


## LEAK DETECTION STATION — CG

NTS — C–204 | C–304





## LINER ANCHOR TO CONCRETE STRUCTURE — CE

NTS — TYP | C–304





## AIR RELEASE STATION — CF

NTS — C–204 | C–304





## DOUBLE CONTAINED ELBOW PIPE CLEANOUT — CH

NTS — C–204 | C–304




## EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT — CI

NTS — C–204 | C–304




## EXISTING 3" LEAK DETECTION STATION — CJ

NTS — C–204 | C–304

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND C–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

SAMUEL G. SHALLARD — NJ PROFESSIONAL ENGINEER — LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 02/13/15 | REO | RJR | REO | APVD | TDD SGS |
| 0 | 06/07/13 | | | | | TDD SHM |

DCB 007.3
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-304 |
| SHEET | 41 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR41-C-304_GWFM_Details.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:51 PM




PLAN





SECTION AA





SECTION BB

FLOW METER STRUCTURE DETAIL AZ
NTS STA 63+78 C-204 C-306





NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL AE
NTS C-201 C-202 C-203 C-306




EXISTING 3" FM TRENCH DETAIL CK
NTS STA 63+78 TO STA 68+91 C-204 C-306




NOTE:
SUBCONTRACTOR IS REQUIRED TO VERIFY PRIOR TO BEGINNING WORK FROM STA. 68+91 TO STA. 70+19

TRENCH DETAIL CL
NTS C-204 C-306

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. SEE SHEET C-304 FOR HATCH SPEC.

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | |
|---|---|---|---|
| 1 | 02/13/15 | TDD | SGS |
| 0 | 06/07/13 | TDD | SHM |

DCB 007.3
ISSUED FOR CONSTRUCTION

| REVISION | BY | CHK | APVD |
|---|---|---|---|
| REO | DR | RJR | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)


NTS

C-203 | C-310
C-204

- SET MANHOLE BASE AND RISER SECTIONS.
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 1.5" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC VITON O RINGS AND TEFLON SEALS |
| 1.5" DIA. FLEXHOSE | 1 | GRANGER OR APPROVED EQUAL | ITEM #3JT48 25' LENGTH EACH |
| 1.5" DIA. CAMLOCK QUICK DISCONNECTS | 1-MALE 1-FEMALE | GRANGER OR APPROVED EQUAL | ITEM #3LX22 ITEM #3LX14 |
| EXPLOSION-PROOF PLUG AND CONNECTOR | 2-SETS | MELTRIC 22-14043 22-18043 OR APPROVED EQUAL | INLINE PLUG AND RECEPTACLE W/ MALE CAP, HANDLES AND FINGER DRAW PLATES |
| 1" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC WITH VITON O RINGS AND TEFLON SEALS |
| 1.5" SWING CHECK VALVE | 1 | SPEARS OR APPROVED EQUAL | MODEL 4423-015 VITON SEAL AND O RINGS |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |





PLAN VIEW

## PIPE PERFORATIONS (CD)

NTS


TYP C-310




## TYPICAL ACCESS MANHOLE FINAL CONDITION STA.=3+63, STA.=8+90, STA.=14+35 (CB)

NTS

C-201 | C-310
C-202




## GROUNDWATER TRENCH TEMPORARY CONDITION (CA)

NTS

C-201 | C-310
C-202
C-203

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD | BY |
|---|---|---|---|---|---|
| 2 | 02/02/15 | DCB 007.3 | TDD | SGS | TDD |
| 1 | 06/06/14 | DCB 007 | TDD | SGS | SGS |
| DSGN | TDD | DR | RJR | TDD | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2109, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, N.J. 08619
609-890-2900
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

**FINAL DCB 007.4 – SA-6 SOUTH CGWES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 007.4 **DCB Type:** Major(a)<br>**Effective Date:** 9/3/15; **Rev. 1** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** GW Extraction System – Revisions of Electrical to Replace Wells with Trenches | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description:**

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification.

DCB-007.2 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

DCB-007.3 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping

DCB-007.4 provides the revised electrical plan, one line electrical drawings and electrical details for SA-6S.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. The revised Design uses a trench design. Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.4 is applicable to the Groundwater Extraction System electrical drawings for SA-6S (electrical plan and one line electrical drawing).


Drawings that are revised in this DCB are:
SA-6S


- C-201
- C-202
- C-203
- C-204
- C-306
- C-310
- E-301
- E-302
- E-303

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** : Design changed based on information gathered during construction |
| | **Attachments:** ☑ Yes ☐ No<br>C-201, C-202, C-203, C-204, C-306, C-310, E-301, E-302, E-303 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |

| | | | |
|---|---|---|---|
| **Additional Comments:** | | **Design Documents Affected:** C-201, C-202, C-203, C-204, C-306, C-310, E-301, E-302, E-303 | |
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☑ **Yes (b)** ☐ **No** |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON GASKETS.
10. INSTALL INSTRAMENTATION CONDUIT FOR PAIRE PIEZOMETERSREADIED WITH PULL STRINGS FOR FUTURE INSTRAMENTATION CABLE INSTALLED BY OTHERS.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 3 | 08/14/15 | DCB 007.4 | TDD | RJR | TDD | RJR | SGS |
| 2 | 02/13/15 | DCB 007.3 | | | | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | | | | TDD | SGS |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2333
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:13 AM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD | REVISION | BY | APVD |
|---|---|---|---|---|---|---|---|---|
| 4 | 08/14/15 | TDD | RJR | TDD | SGS | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | | | | | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | | | | | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | | | | | DCB 007 | TDD | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 110
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28016900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-202
SHEET OF 66

THE DRAWING IS THE PROPERTY OF AMEC; NOT UNDER ALL PATENTS AND PATENTABLE FEATURES AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | TDD | DR | RJR | TDD | | SGS |
| 4 | 08/14/15 | DCB 007.4 | | | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | | | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | | | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | | | TDD | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04241600
9/2/15

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE LICENSE AGREEMENT DATED 1/1/2007 TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

HACKENSACK RIVER

PIERHEAD AND BULKH

SA-7

SA-6 SOUTH

SA-6 NORTH

NOTE:
CONTRACTOR TO VERIFY CONDITION OF EXISTING E&I AND FM AND STATION OF TIE-INS PRIOR TO INITIATING WORK.

AZ C-204 | C-306 DROP STRUCTURE STA=63+78 END NEW 2" FM AND START OF EXISTING 3" HDPE FM IN 6" HDPE

AW C-204 | E-303 ELECTRICAL HANHOLE DETAIL (TYP) NOTE IF AVAILABLE REUSE EXISTING ELECTRICAL PULL BOX IN THIS LOCATION

CI C-204 | C-304 EXISTING PW-1 CLEANOUT STATION STA 69+70 INV=2.40 (RECORD)

CJ C-204 | C-304 EXISTING PW-1 LEAK DETECTION STATION STA 70+11 INV=9.35 (RECORD)

CF C-204 | C-304 AIR RELEASE STATION STA 70+19 GRADE EL=16.3

STA=70+19 END OF EXISTING 3" FM AND START OF NEW 2" FM TO SA-6 NORTH

EXISITNG 2" REGIONAL GROUNDWATER FORCE MAIN FROM EW 115-MW-215BR

EXISITNG 3" EFFLUENT AND 1½" SANITARY FM

EXISTING 2"I AND 2"E CONDUITS

CK C-204 | C-306 EXISTING 3" FM TRENCH DETAIL FORCE MAIN FROM FLOW METER STRUCTURE STA 63+78 TO STA 68+91

STA=68+91 EXISTING REGIONAL GROUNDWATER EXTRACTION WELL 115-MW-215BR

CL C-204 | C-306 EXISTING 6"X3" FM TRENCH DETAIL

EXISTING SA-7 SCB WALL

EXTRACTION TRENCH

FINAL REMEDY CONTOURS (TYP)

CM C-204 | E-303 PIEZOMETER CONDUIT DETAIL

CG C-204 | C-304 LEAK DETECTION STATION STA=61+48, GRADE EL=10.1

CH C-204 | C-304 DOUBLE CONTAINED ELBOW PIPE CLEANOUT STATION STA=61+39, GRADE EL=10.0

SA-6 NORTH FINAL REMEDY GRADE

CH C-204 | C-304 DOUBLE CONTAINED ELBOW PIPE CLEANOUT STATION STA=72+50, GRADE EL=10.0

1" RGS CONDUIT 2" SCH 80 PVC

2" HDPE IN 4" HDPE

EXISITNG 2"I AND 3"E CONDUITS

SA-6 NORTH GROUNDWATER EXTRACTION FORCE MAIN (SEE SHEET CN-203)

EXISTING HYDRAULIC BARRIER

CAP TWO 2" HDPE IN 4" HDPE GW FORCE MAINE 5 FEET OUTSIDE FOUNDATION OF GWTP

EXISTING GROUNDWATER TREATMENT BUILDING

EXISTING 72 IN. FM

SA-6 SOUTH CAP AREA

2" RGS CONTROL CONDUIT 2" PVC SCH 40 POWER CONDIT

PROPOSED HYDRAULIC BARRIER

CC C-204 | C-310 VALVE VAULT STA 60+31±, GRADE EL=18.1

GROUNDWATER EXTRACTION PUMP STATION STA 19+74 EXTRACTION TRENCH= STA 60+24 EXTRACTION FORCE MAIN

MATCH LINE SHEET C-203, C-204

MATCH LINE SHEET C-202

MATCH LINE BELOW

END EXISTING 3" HDPE IN 6" HDPE REDUCE TO 2" HDPE IN 4" HDPE STA=70+19, INV= 10.1

AIR RELEASE STATION STA=71+75 GRADE EL=17.8 C-204 | C-304 CF

EXISTING PW-1 LEAK DETECTION STA 70+13 INV=9.35 (RECORD) C-204 | C-304 CJ

EXISTING 3" CLEANOUT STA 69+70 INV=2.4 (RECORD) C-204 | C-304 CI

EXISTING SA-7 SCB WALL

PROPOSED SA-6 NORTH REMEDY GRADE

FUTURE DEVELOPMENT 48" STORM INV=4.0 BY OTHERS

STA=68+91 REGIONAL GROUNDWATER EXTRACTION WELL 115-MW-215BR

INV=10.1

INV=9.35 (RECORD)

EXISTING 72" FORCE MAIN, TOP OF PIPE EL= ± 13.8

CAP TWO 2" HDPE IN 4" HDPE GW FORCE MAINS 5 FEET OUTSIDE FOUNDATION OF GWTPSTA 73+38 INV=11.16

EXISTING GROUNDWATER TREATMENT BUILDING STA 73+43

INV=2.4

EXISTING 54" FM ABANDONED

SA-7 BULKHEAD AREA

SA-6 NORTH

GROUNDWATER EXTRACTION PUMP STATION STA 60+24± CENTER C-204 | C-310 CC

PROPOSED VALVE VAULT STA 60+31± GRADE EL=18.1

2" HDPE DR 11 FM IN 4" HDPE DR17

INSTALL 2" THICK INSULATION BOARD OVER FM WERE COVER IS LESS THEN 3'

CG C-204 | C-304 DOUBLE CONTAINED ELBOW PIPE CLEANOUT STA=61+39, GRADE EL=10.0

CH C-204 | C-304 LEAK DETECTION STATION STA=61+48

AZ C-204 | C-306 DROP STRUCTURE STA=63+78± GRADE EL=9.7 PROPOSED 2" HDPE DR11 IN A 4" HDPE DR17 INV. IN=7.5, EXISTING 3" HDPE FM IN 6" HDPE INV. OUT=0.97

INV=14.7

INV=14.3

GEOMEMBRANE GRADE

STA 61+37 90° ELBOW INV.=7.51

FINAL REMEDY GRADE

FUTURE DEVELOPMENT 60" DRAIN PIPE INV=4.1 BY OTHERS

EXISTING GRADE

EXISTING GRADE

INV=6.7

INV=6.7

INV=7.5

EXISTING SA-7 SOUTH SCB WALL

2" HDPE DR 11 FM IN 4" HDPE DR17

EXISTING 3" HDPE IN 6" HDPE STA 63+78 TO STA 70+19

EXISTING SA-7 PERIMETER POOL ALONG SCB WALL EL=5.0

INV=(3.5)

EXISTING SA-7 SCB WEST WALL

INV=0.97

EXISTING 3" HDPE DR11 FM INSIDE 6" HDPE DR17 PIPE

SA-7

SA-6 SOUTH

SA-7 BULKHEAD AREA

MATCH LINE ABOVE

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.
5. AT STATION 66+65, IF AVAILABLE, REUSE EXISITNG ELECTRICAL PULL BOX.
6. FROM STATION 63+78 TO STATION 68+91 REMOVE ANY EXISTING WIRING REMAINING IN THE 2" E+I CONDUITS.
7. FORCEMAIN TO BE CAPPED AND TEMINATED 5 FEET OUTSIDE THE GROUNDWATER TREATMENT PLANT. INSTALL 4'x4'x4' GRANITE MARKER AT END OF FORCEMAIN. TOP 2" ABOVE GRADE TO DOCUMENTATION LOCATION.
8. 2" PVC POWER CONDUIT TO BE INSTALLED. WIRING TO BE INSTALLED BY OTHERS UNDER FUTURE CONTRACT. INSTALL NON-DEGRADABLE PULL STRINGS FOR FUTURE USE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
Date 8/18/15

| NO. | DATE | REVISION | DR | CHK | APVD |
|---|---|---|---|---|---|
| 4 | 08/14/15 | DCB 007.4 | RJR | TDD | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | RJR | SGS | |
| 1 | 05/14/14 | DCB 007 | TDD | SHM | |
| DSGN | | | TDD | BY | APVD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28019900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTED FEATURES, AND/OR COPYRIGHTABLE INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




PLAN





SECTION AA





SECTION BB

DROP STRUCTURE DETAIL (AZ)
NTS STA 63+78 C-204 C-306





NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL (AE)
NTS C-201 C-202 C-203 C-306




EXISTING 3" FM TRENCH DETAIL (CK)
NTS STA 63+78 TO STA 68+91 C-204 C-306




TRENCH DETAIL (CL)
NTS C-204 C-306

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
9/2/15

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | | REO | RJR | REO | SHM | SHM |
| | | | | | | RJR | SGS |
| | | | | | | TDD | SGS |
| | | | | | | TDD | SHM |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | | |
| 1 | 02/13/15 | DCB 007.3 | | | | | |
| 2 | 08/14/15 | DCB 007.4 | | | | | |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 587-2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)

NTS

C-203 | C-204 | C-310

- SET MANHOLE BASE AND RISER SECTIONS. (NITC)
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

NOTE:

INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |

SAMUEL G. SHALLARD

NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| DSGN | | | TDD | RJR | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | | | TDD | SGS |
| 2 | 02/02/15 | DCB 007.3 | | | TDD | SGS |
| 3 | 08/14/15 | DCB 007.4 | | | RJR | SGS |

Honeywell
101 COLUMBIA RD BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
609-890-2333
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE RIGID GALVANIZED STEEL (RGS) UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIERD.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| EH | ELECTRIC HANDHOLE |
| EW | EXTRACTION WELL |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| TSP | TWISTED SHIELDED PAIR |
| TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| V | VOLTAGE |
| W | WIRE |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 08/14/15 | TDD | RJR | SHM | SGS |
| 0 | 06/07/13 | | | | |

REVISION BY: RJR TDD SHM SGS

ISSUED FOR CONSTRUCTION

DCB 007.4

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2020
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-301 |
| SHEET | 64 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## EXTRACTION WELL PUMP CONTROL PANEL DETAIL — AO

NTS — TYP E-302


NOTES:

1. ALL CONDUITS SHALL BE 1" RGS MINIMUM, UNLESS OTHERWISE SHOWN. WHEN DISTANCE IS LESS THAN 6 FEET, LIQUID TIGHT METAL FLEXIBLE CONDUIT MAY BE USED.
2. LOCATE THE PUMP MOTOR STARTER WITHIN 3' OF THE EXTRACTION WELL PUMP STATION.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.


NOT PART OF THIS CONTRACT
ELECTRICAL POWER AND INSTRUMENTATION CONTROLS TO BE RE-EVALUATED FOLLOWING INITIAL DRAWDOWN AND TRENCH PERFORMANCE EVALUATION.




## PUMP CONTROL PANEL WIRING DIAGRAM — AP

NTS — TYP E-302

TYPICAL FOR ONE LEVEL TRANSDUCER AND ONE EXTRACTION WELL PUMP CONTROL (SEE NOTE 3)





## INVERTER DRIVE WIRING DIAGRAM — AQ

NTS — TYP E-302

FIELD TERMINAL STRIP CONNECTION SUMMARY

| | |
|---|---|
| GND | EARTH GROUND |
| 10 | RED TRANSDUCER WIRE |
| 11 | BLUE TRANSDUCER WIRE |
| 22 | MALE QD RECEPTACLE BROWN AND BLACK |
| 26 | MALE QD RECEPTACLE BLUE |
| 27 | MALE QD RECEPTACLE WHITE |
| 32 | FAULT CONTACT SUPPLY |
| 33 | FAULT CONTACT RETURN |

FEMALE QUICK DISCONNECT PLUG




## PLUG & TERMINAL STRIP WIRING DIAGRAM — AR

NTS — TYP E-302

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 08/14/15 | RJR | SGS | | |
| 0 | 06/07/13 | TDD | TDD | RJR | SHM |

DCB 007.4
ISSUED FOR CONSTRUCTION
REVISION
BY APVD
SHM

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


WIRING DIAGRAMS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 585-2283
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.





DUCT WAY NOTES:

1. CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS, OR AS SPECIFIED.
2. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAY #4@12" OC MIN 2. EXTEND 4' BEYOND ROAD EDGE.
3. MINIMUM COVER TO TOP OF CONCRETE ENVELOPE SHALL BE 24" [610mm].
4. INSTALL IN A 4'-0" MAX WIDTH TRENCH SIMILAR TO DETAIL Z ON C-306.


DUCT BANK DETAILS — NTS — AT — TYP E-303




ELECTRICAL HANDHOLE DETAIL — NTS — AW — C-201, C-202, C-203 — E-303




PIEZOMETER CONDUIT DETAIL — NTS — CM — TYP E-303




NOTES:

1. MAINTAIN SEPARATION OF POWER AND INSTRUMENTATION CONDUCTORS IN ELECTRIC HANDHOLE.
2. WHERE POWER AND INSTRUMENTATION CONDUCTORS CROSS THEY SHALL CROSS PERPENDICULAR TO EACH OTHER.
3. ELECTRICAL HAND HOLES SHALL BE LOCATED TO AVOID CLEANOUT MANHOLES.

ELECTRICAL HANDHOLE ORIENTATION DETAIL — NTS — AY — C-201, C-202, C-203 — E-303

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

| DSGN | DR | CHK | APVD |
|---|---|---|---|
| TDD | RJR | SGS | SGS |

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS:
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

ELECTRICAL DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA27015500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-303 |
| SHEET | 66 OF 66 |

**FINAL DCB 007.4.1 – SA-6 SOUTH CGWES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 7.4.1 **DCB Type:** Major(a)<br>**Effective Date:** 5/24/16 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** GW Extraction System – Revisions of Electrical to Replace Wells with Trenches | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description:**

DCB-007 series has documented changes to the contingent GW system design. Details related to the administrative basis for the change are provided in DCB 007.1 (issued to Entact on 6/12/14).

Several major changes have been issued in the past covering the change from Individual Wells to a Trench Drain system and the elimination of all wiring, pumps, and controls from the Entact Chromium Remedy scope of work.

This DCB 7.4.1 is being issued to address further changes in the SA-6 South design, including but not limited to:

- Elimination of Drop Structure at the junction of SA-6 / SA7
- Elimination of flow meter
- Conduit sizing changes

Drawings that are revised in this DCB are:

- C-201
- C-202
- C-203
- C-204
- C-304
- C-305
- C-306
- C-310
- E-301 (Not for Construction)
- E-302 (Not for Construction)
- E-303

**Clarification of Entact Scope of Work:**

- The provision of pumps, electrical wiring and instrumentation for the Contingent Groundwater system has been removed from Entact's scope of work.
- The installation of the FM and E&I conduits remain in Entact's scope, as depicted on the drawings.
- Running of conduit to the piezometers remains in Entact's scope. No instrumentation or wiring will be installed in the piezometers as part of the initial Chromium Remedy. The need and type of instrumentation will be determined based on the initial rounds and evaluation of the performance of the Contingent System.
- All E&I conduit will be, at a minimum, Sched 40 PVC meeting the National Electric Code.


**Clarification of Entact Scope of Work (continued):**


- SA-6/7 Meter / Drop structure has been eliminated and replaced with two 45 degree transitions. This detail needs to be reviewed with the fabricator and details shall be submitted to the engineer for approval.
- In the SA-6S east end, AmecFW had to relocate the last pull box and build in some bends. Therefore, the conduit was increased to 1.5 inch.
- The revised design calls for a minimum 24" of cover for direct burial of conduit.
- The E&I conduit from SA-7 to the SA-6S Pump Station is now shown as concrete encased (location shown on Drawing C-203, Detail AA shown on C-305).

DCB 7.2.2 will document changes to the SA-6 North Contingent GW Extraction system. DCB 7.2.2 will follow in a separate submittal.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** : Design changed due to changes in the recovery concept, permitted discharge location and site grading |
| | **Attachments:** ☑ Yes ☐ No<br>C-201, C-202, C-203, C-204, C-304, C-305, C-306, C-310, E-301 (Not IFC), E-302 (Not IFC), E-303 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>C-201, C-202, C-203, C-204, C-304, C-305, C-306, C-310, E-301 (Not IFC), E-302 (Not IFC), E-303 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 5/24/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☑ **Yes (b)** ☐ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON CASKETS.
10. INSTALL INSTRUMENTATION CONDUIT FOR PAIRED PIEZOMETERS READIED WITH PULL STRINGS FOR FUTURE INSTRUMENTATION CABLE INSTALLED BY OTHERS.
11. CONCRETE ENCASEMENT REQUIRED IF BURIAL DEPTH IS LESS THAN 24" OR OTHERWISE NOTED FOR E&I CONDUIT.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 4 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 3 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 2 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS |
| DSGN | | DR TDD CHK RJR APVD SGS | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 9:24 AM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 5 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 4 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS |
| DSGN | | DR TDD CHK RJR APVD TDD | | |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR35-C-202_Cont_GWE_Trench.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 9:26 AM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD | BY |
|---|---|---|---|---|---|
| 5 | 05/20/16 | DCB 007.4.1 | TDD | | TDD |
| 4 | 08/14/15 | DCB 007.4 | RJR | | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | | SHM |
| DSGN | | DR | RJR | APVD | SGS |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON ITS RETURN. IT IS NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

HACKENSACK RIVER

PIERHEAD AND BULKHEA

LEAK DETECTION STATION STA=63+95, GRADE EL=6.5 (CG C-204 C-304)

1" PVC CONDUIT

DOUBLE CONTAINED WYE PIPE CLEANOUT STATION STA=63+98, GRADE=7.0 (CI C-204 C-304)

CONTRACTOR TO SUBMIT FORCE MAIN FABRICATION DETAILS FOR ENGINEERS APPROVAL.

ELECTRICAL HANHOLE DETAIL (TYP) NOTE IF AVAILABLE REUSE EXISTING ELECTRICAL PULL BOX IN THIS LOCATION (AW C-204 E-303)

EXISTING 2"ø CONTROL AND 2"ø POWER CONDUITS

EXISTING PW-1 CLEANOUT STATION STA 69+70 INV=2.40 (RECORD) (CI C-204 C-304)

STA=70+19 END OF EXISTING 3" FM AND START OF NEW 2" FM TO SA-6 NORTH FIELD VERIFY END OF EXISTING 3" PIPE.

EXISITNG 2" REGIONAL GROUNDWATER FORCE MAIN FROM EW 115-MW-215BR

EXISITNG 3" EFFLUENT AND 1½" SANITARY FM

EXISTING 2"ø CONTROL AND 2"ø POWER CONDUITS

DOUBLE CONTAINED WYE PIPE CLEANOUT STATION STA=72+20, GRADE=17.4 (CI C-204 C-304)

SA-6 SOUTH 2" HDPE IN 4" HDPE

EXISTING 2"ø CONTROL AND 3"ø POWER CONDUITS

SA-6 NORTH 2" HDPE IN 4" HDPE

EXISTING 3" FM TRENCH DETAIL FORCE MAIN FROM STA 64+00 TO STA 68+91 (CK C-204 C-306)

STA=68+91 EXISTING REGIONAL GROUNDWATER EXTRACTION WELL 115-MW-215BR

EXISTING 6"X3" FM TRENCH DETAIL (CL C-204 C-306)

VERIFY PRESENCE/CONDITION OF EXISTING PW-1 LEAK DETECTION STATION/ STA 70+17 INV=9.35 (RECORD) (REPLACE IF NECESSARY) (CL C-204 C-306)

1"ø PVC CONDUIT (SEE SHEET CN-203)

AIR RELEASE STATION STA 71+50 GRADE EL=18.5 (CF C-204 C-304)

SA-6 NORTH GROUNDWATER EXTRACTION FORCE MAINS (SEE SHEET CN-203)

EXISTING HYDRAULIC BARRIER

EXISTING 72" FM

EXISTING GROUNDWATER TREATMENT BUILDING

SA-6 NORTH FORCE MAINS FROM EWP#1 AND EWP#2 2" HDPE IN 4" HDPE

SA-6 NORTH

JUNCTION MANHOLE #1 INSTALL 4'X6'X4' DEEP STRUCTURE AGAINST GROUNDWATER TREATMENT PLANT FOUNDATION GRADE=16.15. CAP SA-6 NORTH AND SOUTH FORCE MAINS. (AZ C-204 C-304)

SA-7

EXISTING SA-7 SCB WALL

EXTRACTION TRENCH

2" PVC INSTRUMENTATION CONDUIT

FINAL REMEDY CONTOURS (TYP)

PROPOSED HYDRAULIC BARRIER

EXTRATION PIPE TRENCH OUTSIDE SA-6 SOUTH CAP (AB C-204 C-305)

DOUBLE CONTAINED ELBOW PIPE CLEANOUT STATION STA=61+39, GRADE EL=10.0 (CH C-204 C-304)

NOTE:
CONTRACTOR TO VERIFY CONDITION OF EXISTING E&I AND FM AND STATION OF TIE-INS PRIOR TO INITIATING WORK.

SA-6 NORTH FINAL REMEDY GRADE

EXISTING SA-7 SCB WALL

SA-6 SOUTH

SA-6 SOUTH CAP AREA

EXTRACTION PIPE TRENCH OVER CAP (AA C-204 C-305)

INSTRUMENTATION CONDUIT TRENCH (AU C-204 C-305)

VALVE VAULT STA 60+31±, GRADE EL=18.1 (CC C-204 C-310)

GROUNDWATER EXTRACTION PUMP STA 19+74 EXTRACTION TRENCH= STA 60+24 EXTRACTION FORCE MAIN (CC C-204 C-310)

MATCH LINE SHEET C-203, C-204

MATCH LINE SHEET C-202

MATCH LINE BELOW

END EXISTING 3" HDPE IN 6" HDPE REDUCE TO 2" HDPE IN 4" HDPE STA=70+19, INV= 10.1

EXISTING PW-1 LEAK DETECTION STA 70+13 INV=9.35 (RECORD) (CJ C-204 C-304)

EXISTING 3" CLEANOUT STA 69+70 INV=2.4 (RECORD) (CI C-204 C-304)

EXISTING SA-7 SCB WALL

PROPOSED SA-6 NORTH REMEDY GRADE

FUTURE DEVELOPMENT 48" STORM INV=4.0 BY OTHERS

STA=68+91 REGIONAL GROUNDWATER EXTRACTION WELL 115-MW-215BR

DOUBLE CONTAINED WYE PIPE CLEANOUT STATION STA=70+20, RADE=17.4 (CF C-204 C-304)

AIR RELESE STATION STA=71+50, GRADE=18.5 (CF C-204 C-304)

EXISTING GROUNDWATER TREATMENT BUILDING STA 73+85.2

INSTALL 2" THICK INSULATION BOARD OVER FM WERE COVER IS LESS THEN 3'

INV=13.3
INV=13.3

STA=73+77 INV=13.2
STA=73+82 INV=13.2

INV=10.1
INV=9.35 (RECORD DRAWING)

INV=2.4

EXISTING

NEW

EXISTING 54" FM ABANDONED

SA-7 BULKHEAD AREA

SA-6 NORTH

GROUNDWATER EXTRACTION PUMP STATION STA 60+24± CENTER (CC C-204 C-331)

PROPOSED VALVE VAULT STA 60+31± GRADE EL=18.1

INSTALL 2" THICK INSULATION BOARD OVER FM WERE COVER IS LESS THAN 3'

2" HDPE DR 11 FM IN 4" HDPE DR17

DOUBLE CONTAINED ELBOW PIPE CLEANOUT STA=61+39, GRADE EL=10.0 (CH C-204 C-304)

CONTRACTOR TO SUBMIT FORCE MAIN FABRICATION DETAILS FOR ENGINEERS APPROVAL.

FUTURE DEVELOPMENT 60" DRAIN PIPE INV=4.1 BY OTHERS

LEAK DETECTION STATION STA=63+95, GRADE=6.5 (CG C-204 C-304)

DOUBLE CONTAINED WYE PIPE CLEANOUT STATION STA=63+98, GRADE=7.0 (CI C-204 C-304)

INV=14.7
INV=14.3

GEOMEMBRANE GRADE

FINAL REMEDY GRADE

EXISTING GRADE

EXISTING GRADE

STA 61+37 90° ELBOW INV.=7.51

EXISTING SA-7 SOUTH SCB WALL

INV=6.7

2" HDPE DR 11 FM IN 4" HDPE DR17

INV=5.8

4"x2" TO 6"x3" TRANSITION TO BE SUBMITTED FOR ENGINEERS APPROVAL

EXISTING 3" HDPE IN 6" HDPE STA 64+10 TO STA 70+19

INV=5.3

INV=2.8

INV=1.1

EXISTING SA-7 PERIMETER POOL ALONG SCB WALL EL=5.0

EXISTING SA-7 SHEET PILE WEST WALL TOP EL=4.00

INV=(3.5)

SA-7

NEW

SA-6 SOUTH

SA-7 BULKHEAD AREA

EXISTING

EXISTING 3" HDPE DR11 FM INSIDE 6" HDPE DR17 PIPE

MATCH LINE ABOVE

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.
5. AT STATION 66+65, IF AVAILABLE, REUSE EXISTING ELECTRICAL PULL BOX.
6. FROM STATION 63+78 TO STATION 68+91 REMOVE ANY EXISTING WIRING REMAINING IN THE 2" E+I CONDUITS.
7. FORCE MAIN TO BE CAPPED AND TERMINATED INSIDE THE INSTALLED 4'x6'x4' DEEP JUNCTION STRUCTURE OUTSIDE THE GROUNDWATER TREATMENT PLANT.
8. 2" PVC POWER CONDUIT TO BE INSTALLED. WIRING TO BE INSTALLED BY OTHERS UNDER FUTURE CONTRACT. INSTALL NON-DEGRADABLE PULL STRINGS FOR FUTURE USE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 5 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 4 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | RJR | SGS |
| 1 | 05/14/14 | DCB 007 | TDD | SHM |
| DSGN | TDD | DR RJR | CHK TDD | APVD SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-204
SHEET OF 66





NOTES:

1. USE THUNDERLINE LINK–SEAL TYPE LS 300–C FOR 2"ø OR 3" ø PIPELINES AND TYPE LS 425–C FOR 1"ø AND 1–1/4" PIPELINES OR EQUAL AT ALL MANHOLES AND STRUCTURES.
2. USE PRESSURE GAGE AND PROBE ON PIPELINES THAT SLOPE UPWARDS FROM STRUCTURES ONLY, BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK–JOINT FLEXIBLE MANHOLE SLEEVE OR KOR–N–SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.


## TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL (X | C–304 | C–304)

NTS





## JUNCTION MANHOLE #1 @ GWTP (AZ | C–204 | C–304)

NTS





## AIR RELEASE STATION (CF | C–204 | C–304)

NTS





## LEAK DETECTION STATION (CG | C–204 | C–304)

NTS





## DOUBLE CONTAINED ELBOW PIPE CLEANOUT (CH | C–204 | C–304)

NTS





## EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT (CI | C–204 | C–304)

NTS




## EXISTING 3" LEAK DETECTION STATION (CJ | C–204 | C–304)

NTS




## LINER ANCHOR TO CONCRETE STRUCTURE (CE | TYP | C–304)

NTS

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND C–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| DSGN | REO | DR | RJR | REO |
| 4 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 3 | 08/05/15 | DCB 37.1 REVISED DETAIL CE | RJR | SGS |
| 2 | 07/28/15 | DCB 37 REVISED DETAIL CE | RJR | SGS |
| 1 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| | | | BY | APVD |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SHM

Honeywell
115 FABER RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-304 |
| SHEET | 41 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC




EXTRACTION PIPE TRENCH TO SA6-N

NTS Y C-203 C-303 C-305





EXTRACTION PIPE TRENCH OVER CAP

(INSIDE SA-6S CAP AREA)

VALVE VAULT TO STA 61+32±

NTS AA C-201 C-202 C-203 C-305





EXTRACTION PIPE TRENCH

(OUTSIDE SA-6S CAP AREA)


STA. 61+32 TO STA. 63+72±

NTS AB C-201 C-202 C-203 C-305




EXTRACTION PIPE TRENCH WITH PIEZOMETER SERVICE AND INSTRUMENTATION OVER CAP

NTS Z C-201 C-202 C-305




OUTSIDE CAP

(SEE DETAIL CM ON E-303)

OVER CAP

PIEZOMETER INSTRUMENTATION CONDUIT TRENCH

NTS AU C-201 C-203 C-305

NOTE:

1. PROVIDE CONCRETE ENCASEMENT IF CONDUIT IS LESS THAN 24-INCHES BELOW DEVELOPMENT GRADE.
2. INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD

NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 05/20/16 | TDD | REO | RJR | REO | SGS |
| 0 | 06/07/13 | TDD | | | | SHM |

DCB 007 4.1

ISSUED FOR CONSTRUCTION

REVISION

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-305 |
| SHEET | 41 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR41-C-305 Conting Pump Well Details.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 9:35 AM





PLAN





SECTION AA

ELIMINATION OF STRUCTURE
STA 64+10
NTS

AZ
C-204 | C-306



SECTION BB





NOTE:

PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.


PIEZOMETER DETAIL
NTS

AE
C-201 | C-306
C-202
C-203




EXISTING 3" FM TRENCH DETAIL
NTS STA 63+78 TO STA 68+91

CK
C-204 | C-306




TRENCH DETAIL
NTS

CL
C-204 | C-306

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | REO | REO | RJR | REO | SHM | SHM |
| 3 | 05/20/16 | | | DCB 007.4.1 | | TDD | SGS |
| 2 | 08/14/15 | | | DCB 007.4 | | RJR | SGS |
| 1 | 02/13/15 | | | DCB 007.3 | | TDD | SGS |
| 0 | 06/07/13 | | | ISSUED FOR CONSTRUCTION | | TDD | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR43-C-306 Extraction Well Details.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 9:36 AM




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)

NTS

C-203 C-204 C-310

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |

- SET MANHOLE BASE AND RISER SECTIONS. (NITC)
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

NOTE:

INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 4 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 3 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 2 | 02/02/15 | DCB 007.3 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS |
| DSGN | TDD | DR | RJR | BY | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE SCH 40 PVC DB UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| DB | DIRECT BURIAL |
| EB | ENCASED BURIAL |
| EH | ELECTRIC HANDHOLE |
| EW | EXTRACTION WELL |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| TSP | TWISTED SHIELDED PAIR |
| TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| V | VOLTAGE |
| W | WIRE |

NOT FOR CONSTRUCTION

Fri, 20 May 2016

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DR | CHK | APVD |
|---|---|---|---|---|
| DSGN | TDD | RJR | SHM | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD SHM SGS |
| 1 | 08/14/15 | DCB 007.4 | | RJR SGS |
| 2 | 05/20/16 | DCB 007.4.1 | | TDD SGS |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2828
NJ Certificate of Authorization Number
24GA28010800

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-301 |
| SHEET | 64 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## EXTRACTION WELL PUMP CONTROL PANEL DETAIL (AO)

NTS

TYP E-302


NOTES:

1. ALL CONDUITS SHALL BE 1" PVC MINIMUM, UNLESS OTHERWISE SHOWN. WHEN DISTANCE IS LESS THAN 6 FEET, LIQUID TIGHT METAL FLEXIBLE CONDUIT MAY BE USED.
2. LOCATE THE PUMP MOTOR STARTER WITHIN 3' OF THE EXTRACTION WELL PUMP STATION.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

NOT PART OF THIS CONTRACT
ELECTRICAL POWER AND INSTRUMENTATION CONTROLS TO BE RE-EVALUATED FOLLOWING INITIAL DRAWDOWN AND TRENCH PERFORMANCE EVALUATION





## PUMP CONTROL PANEL WIRING DIAGRAM (AP)

NTS

TYPICAL FOR ONE LEVEL TRANSDUCER AND ONE EXTRACTION WELL PUMP CONTROL (SEE NOTE 3)

TYP E-302




## INVERTER DRIVE WIRING DIAGRAM (AQ)


NTS

TYP E-302

### FIELD TERMINAL STRIP CONNECTION SUMMARY

| | |
|---|---|
| GND | EARTH GROUND |
| 10 | RED TRANSDUCER WIRE |
| 11 | BLUE TRANSDUCER WIRE |
| 22 | MALE QD RECEPTACLE BROWN AND BLACK |
| 26 | MALE QD RECEPTACLE BLUE |
| 27 | MALE QD RECEPTACLE WHITE |
| 32 | FAULT CONTACT SUPPLY |
| 33 | FAULT CONTACT RETURN |

### FEMALE QUICK DISCONNECT PLUG




## PLUG & TERMINAL STRIP WIRING DIAGRAM (AR)

NTS

TYP E-302

NOT FOR CONSTRUCTION

FRI, 20 May 2016

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 05/20/16 | TDD | | | SHM | TDD | SHM |
| 1 | 08/14/15 | | DCB 007.4.1 | | | RJR | SGS |
| 0 | 06/07/13 | | DCB 007.4 | | | TDD | SHM |
| | | TDD | RJR | SHM | APVD | ISSUED FOR CONSTRUCTION | |
| | | | | | | REVISION | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


WIRING DIAGRAMS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 588-2329
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |


FILE NAME: Pr... HONEYWELL JERSEY CITY C... D... SA6-C3D CAD SA6-N r... S... GW E r... Tr... CR65-E-302 W r... D r... d... PLOT DATE: Fr, 20 M... 2016 PLOT TIME: 3:05 PM





DUCT WAY NOTES:

1. ENCASED BURIAL REQUIRED IF THE COVER DEPTH IS LESS THAN 24" OR OTHERWISE SPECIFIED
2. CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS, OR AS SPECIFIED.
3. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAY WITH LESS THAN 24" OF COVER #4@12" OC MIN 2. EXTEND 4' BEYOND ROAD EDGE.
4. ~~CONCRETE ENVELOPE SHALL BE 24" [610mm].~~
5. INSTALL IN A 4'-0" MAX WIDTH TRENCH SIMILAR TO DETAIL Z ON C-306.


DUCT BANK DETAILS (AT)
NTS
C-201 | E-303
C-203




ELECTRICAL HANDHOLE DETAIL (AW)
NTS
C-201 | E-303
C-202
C-203




PIEZOMETER CONDUIT DETAIL (CM)
NTS
C-305 | E-303




ELECTRICAL HANDHOLE ORIENTATION DETAIL (AY)
NTS
C-201 | E-303
C-202
C-203

ELECTRICAL NOTES:

1. MAINTAIN SEPARATION OF POWER AND INSTRUMENTATION CONDUCTORS IN ELECTRIC HANDHOLE.
2. WHERE POWER AND INSTRUMENTATION CONDUCTORS CROSS THEY SHALL CROSS PERPENDICULAR TO EACH OTHER.
3. ELECTRICAL HAND HOLES SHALL BE LOCATED TO AVOID CLEANOUT MANHOLES.
4. INSTALL ELECTRICAL HANDHOLES AT MAXIMUM 250 FOOT SPACING.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

| NO | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 05/20/16 | TDD | DCB 007.4.1 | TDD | SGS |
| 1 | 08/14/15 | RJR | DCB 007.4 | RJR | SGS |
| 0 | 06/07/13 | TDD | ISSUED FOR CONSTRUCTION | TDD | SGS |
| | | | REVISION | BY | APVD |

SAMUEL G SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

ELECTRICAL DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 584-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-303 |
| SHEET | 66 OF 66 |

**FINAL DCB 007.4.2 – EI REVISIONS CONTINGENT GROUNDWATER**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** DCB 7.4.2 **Type:** Minor(a)<br>**Effective Date:** 12/20/2016 |
| **Project Location:** SA-6 North and South | **Associated RFI:** |
| **Title:** Contingent GW E&I Revisions | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** The Contingent GW system was modified from wells to trenches. This resulted in a reduction in from 9 pumps on the North, and 9 pumps on the South, to 2 pump stations on North, and 1 pump station on South. The electrical and instrumentation (E&I) requirements and associated conduit runs changed accordingly.

This DCB documents a number of minor field changes that have been conveyed by the EOR to Entact during the course of the work and also includes revisions to the (E series) electrical drawings for both SA-6N and SA-6S.

The IFC conduit runs were designed to allow for hard wiring of the piezometric pairs used to monitor the gradients. The piezometric instrumentation conduit run has been eliminated on SA-6S. The piezometric pairs will initially be monitored manually. Manual monitoring may be supplemented by use of data loggers (Solinst Levelogger or similar) in selected wells. Based on the technical advancement in data loggers subsequent to the IFC design, data collection options that do not require hard wiring are a viable and preferred. Wireless data loggers eliminate the risk of damage and associated subsurface repair in the future. As a result, conduit runs for the piezometers were deleted from SA-6S. Due to the progress of work and scheduling, a piezometer conduit was installed on SA-6N; however, wiring has not been installed and it is the engineer's recommendation that wireless installation be used.

Investigation of existing conduit runs at the west end of SA-7 indicated that one 2-inch conduit shown on the IFC design as existing was not present. A new conduit run was added in its place.


All pump stations, force-mains and E&I conduit runs except as noted above have been installed.

The reason for considering this a "Contingent" System is that modeling predictions indicate that **no pumping** will be required i.e. there is no technical design basis for determining a flow rate. In the absence of a theoretical or verified design flow the forcemains have been sized at 2 inches in diameter and the pumps and associated wiring to operate at 5 GPM. Larger pumps and wire sizes could be readily installed in the unlikely event they are required. As of the date of issue of this DCB, pumping has not been required. This covers a period of more than 12 months on SA-6S, and 4 months on SA-6N. To provide an allowance for pumping at some nominal flow rate, pumps and power have been sized assuming a steady 5 GPM flow rate. The pump and controls design is based on operation of only one pump station at a time. The 5 GPM is based on the capacity of the existing GWTP effluent pumps. The forcemain and pumps have been sized for greater capacity, and greater flows could be readily achieved, if the effluent pump capacity was increased. It is recommended that a final decision on pump sizes, and related wiring and instrumentation, be revisited if it is determined that pumping is required. The GWTP has been modified under separate contract with BSTI to accommodate the flow and E&I controls.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |

| | | | |
|---|---|---|---|
| **Additional Comments:** | | **Design Documents Affected:** E-301, E-302 and E-302A (SA-6S). EN-301, EN-302 and EN-302A (SA-6N) | |
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** 12/21/16 |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☐ **Yes (b)** ☑ **No** |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE SCH 40 PVC DB UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDUIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.
9. THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| DB | DIRECT BURIAL |
| EB | ENCASED BURIAL |
| EH | ELECTRIC HANDHOLE |
| FWE | FURNISHED WITH EQUIPMENT |
| FVNR | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| JB | JUNCTION BOX |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| MPCB | MOTOR PROTECTION CIRCUIT BREAKER |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| SPD | SURGE PROTECTIVE DEVICE |
| TSP | TWISTED SHIELDED PAIR |
| V | VOLTAGE |
| W | WIRE |

TIMOTHY C. KESSLER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| | | TDD | RJR | SHM | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD SHM APVD |
| 1 | 08/14/15 | DCB 007.4 | | | | RJR SGS |
| 2 | 05/20/16 | DCB 007.4.1 | | | | TDD SGS |
| 3 | 12/02/16 | DCB 007.4.2 | | | | SGS TCK |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG E-301
SHEET 64 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




6 SOUTH PUMP STATION CONTROL SCHEMATIC
NTS




5KVA 480V–120/240V
MINIMUM POWER ZONE

TYPICAL PUMP STATION ONE LINE
NTS

NOTE:

THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

☐ TERMINAL IN PUMP PANEL

FIELD WIRING

TIMOTHY C. KESSLER, P.E.

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 12/02/16 | SGS | TCK | | |
| 2 | 05/20/16 | TDD | SGS | | |
| 1 | 08/14/15 | RJR | SGS | | |
| 0 | 06/07/13 | TDD | SHM | | APVD |
| | ISSUED FOR CONSTRUCTION | | BY | | SGS |
| | REVISION | | | | |

DCB 007.4.2
DCB 007.4.1
DCB 007.4

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134,
140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


ELECTRICAL


WIRING DIAGRAM


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |




PUMP STATION CONTROL PANEL DETAIL
NTS




PUMP STATION CONTROL PANEL BACK DETAIL
NTS

NOTE:

THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.


**BILL OF MATERIALS**


| ITEM | QTY | DESCRIPTION | MFG | PART NO. |
|---|---|---|---|---|
| 1 | 1 | 60" H x 52" W x 18" D 2-Door NEMA 3R Pad-Mount Enclosure with back panel | Hoffman or Equal | A60R5218FSLP & A49P48N |
| 2 | 1 | 4 inch cooling fan with bracket and thermostat, 120 Vac | Hoffman or Equal | A4AXFN, ABRKT4, & ATEMNO |
| 3 | 1 | 400 Watt heater with fan and thermostat, 120 Vac | Hoffman or Equal | DAH4001B |
| 4 | 4 | 175A Power Distribution Terminal Block, #2/0 to #14 AWG Wire Size Range, IP20 Finger-Safe | Bussmann or Equal | PDBFS220 |
| 5 | 2 | Square D H-Frame, 30A, 3P, 600V, Thermal-Magnetic Circuit Breaker and NEMA 1 Surface -Mount Enclosure | Square D or Equal | HDL36030 & J250S |
| 6 | 1 | Type 1 Surge Protective Device, 480V, 3 Phase Delta, 3-Wire + Ground with Transient Filter and Surge Counter | Joslyn or Equal | JSP240-3D480-FB |
| 7 | 1 | Square D Mini-Power Zone, 5kVA, 480V-240/120V, NEMA 3R Enclosure with Primary & Secondary Main Breakers | Square D or Equal | MPZ5S40F |
| 8 | 5 | Square D Type QO Plug-On Circuit Breaker, 15A, 1P, 120/240V for MPZ Panelboard | Square D or Equal | QO115 |
| 9 | 1 | Square D Type QO Plug-On Circuit Breaker, 15A, 1P, 120/240V with 30 mA Ground Fault Protection for MPZ Panelboard | Square D or Equal | QO115EPD |
| 10 | 1 | Duplex 15A, 125V, GFCI Type Receptacle, Heavy Duty, 2P, 3-Wire Grounded, Ivory | Hubbell or Equal | GF15IL |
| 11 | 1 | Handy Box and Receptacle Cover | Raco or Equal | 8660 & 864 |
| 12 | 1 | Copper Bonded Steel Ground Rod, 3/4" Dia x 10 Ft Long | Erico or Equal | 613400 |
| 13 | 1 | 3-Phase Motor Protection Relay, 120Vac Control Power, 13 Protective Functions, Trip and Alarm Fail-Safe Relays | Littelfuse Powr-Gard | PGR-6150-120 |
| 14 | 1 | Operator Interface for Motor Protection Relay | Littelfuse Powr-Gard | PGR-6150-OPI |
| 15 | 1 | Motor Protection Circuit Breaker, Red/Yellow Lockable Knob, 480v, 3 PH, 60Hz 2.5 to 4A Adjustable Range with Front-Mounted N.O. Aux Contact | Allen-Bradley | 140M-C2E-B40-KY & 140M-C-AFA10 |
| 16 | 1 | IEC Contactor, 9A, 480V, 3 Ph, 60 Hz 120V, 1 N.O. Aux Contact, 60Hz Coil | Allen-Bradley | 100-C09D10 |
| 17 | 1 | 3 Position Selector Switch, Spring-Return from Left, 2 Contact Blocks with Hand-Off-Auto Legend Plate | Allen-Bradley | 800T-J4B & 800T-X511 |
| 18 | 1 | Green LED Pilot Light, 120Vac, 60 Hz | Allen-Bradley | 800T-QH2G |
| 19 | 1 | NEMA 4/13 Die Cast, 2-Hole Surface Mount Pushbutton Enclosure | Allen-Bradley | 800T-2TZ |
| 20 | 1 | DPDT Plug-In Relay, 24VDC Coil, LED, Push-to-Test and Manual Override and Socket | Allen-Bradley | 700-HA32Z24-3-4 & 700-HN100 |
| 21 | Lot | DIN Rail #3 for Mounting Components as required | Allen-Bradley | 199-DR1 |
| 22 | Lot | DIN Rail, 30A Terminal Blocks, End Anchors, End Barriers as required | Allen-Bradley | 1492-N22, 1492-HM1 1492-N23, 1492-NM36 |




EXTRACTION WELL PUMP CONTROL PANEL DETAIL
NTS

AO
TYP E-302A




SECTION A

NOTES:

1. 7 BARS PERPENDICULAR TO 5'-4" DIMENSION TOP AND BOTTOM.
   4 BARS PERPENDICULAR TO 2'-6" DIMENSION TOP AND BOTTOM

CONTROL PANEL PAD DETAIL
NTS

TIMOTHY C. KESSLER, P.E.
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 12/02/16 | TDD | DCB 007.4.2 | SHM | SGS |
| 2 | 05/20/16 | TDD | DCB 007.4.1 | SHM | SGS |
| 1 | 08/14/15 | RJR | DCB 007.4 | SHM | SGS |
| 0 | 06/07/13 | TDD | ISSUED FOR CONSTRUCTION | BY | APVD |
| | | | REVISION | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INC. INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND OF COPYRIGHTED INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


ELECTRICAL

WIRING DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302A |
| SHEET | 65A OF 66 |




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE POLYVINYL CHLORIDE DIRECT BURIAL UNLESS NOTED OTHERWISE.
4. ALL PROPOSED CONDUITS WILL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE.
5. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE.
6. THE CONTRACTOR SHALL INSTALL THE 3"ø PVC SCH 40 CONDUIT FROM THE EXTRACTION WELLS INTO AND INCLUDE THE CONSTRUCTION OF THE EH @ THE GWTP. THE CONDUIT FROM THIS EH TO THE GWTP AND INSIDE WILL BE INSTALLED BY OTHERS IN THE FUTURE.
7. THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| EH | ELECTRIC HANDHOLE |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| SPD | SURGE PROTECTIVE DEVICE |
| TSP | TWISTED SHIELDED PAIR |
| V | VOLTAGE |
| W | WIRE |

| NO. | DATE | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | | GCP | RJR | GCP | SGS | SGS |
| 3 | 12/02/16 | DCB 007.4.2 | | | SGS | TCK |
| 2 | 05/06/16 | DCB 007.2.2 | | | TDD | SGS |
| 1 | 09/02/15 | DCB 007.2.1 | | | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | GCP | SGS |

TIMOTHY C. KESSLER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDIUM
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-301 |
| SHEET | 67 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR67-EN-301 ONE LINE DIAGRAM.dwg PLOT DATE: Thu, 15 Dec 2016 PLOT TIME: 3:43 PM




## 6 NORTH PUMP STATION 1 CONTROL SCHEMATIC

NTS




## 6 NORTH PUMP STATION 2 CONTROL SCHEMATIC

NTS

### NOTE:

THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

□ TERMINAL IN PUMP PANEL

_ _ _ _ _ _ _ _ _ FIELD WIRING

TIMOTHY C. KESSLER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | DSGN | DR | CHK | BY | APVD |
|---|---|---|---|---|---|---|
| 3 | 12/02/16 | | | | SGS | TCK |
| 2 | 05/06/16 | | | | TDD | SGS |
| 1 | 09/02/15 | | | | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | GCP | SGS |
| | | DCB 007.4.2 | GCP | RJR | GCP | APVD |
| | | DCB 007.2.2 | | | | |
| | | DCB 007.2.1 | | | | |

SGS LICENSE NUMBER 24GE03749500

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.
THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


ELECTRICAL

ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-302 |
| SHEET | 68 OF 70 |




NOTE:


THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.





EXTRACTION WELL PUMP CONTROL PANEL BACK DETAIL
NTS


**BILL OF MATERIALS**

| ITEM | QTY | DESCRIPTION | MFG | PART NO. |
|---|---|---|---|---|
| 1 | 1 | 60" H x 52" W x 18" D 2-Door NEMA 3R Pad-Mount Enclosure with back panel | Hoffman or Equal | A60R5218FSLP & A49P48N |
| 2 | 1 | 4 inch cooling fan with bracket and thermostat, 120 Vac | Hoffman or Equal | A4AXFN, ABRKT4, & ATEMNO |
| 3 | 1 | 400 Watt heater with fan and thermostat, 120 Vac | Hoffman or Equal | DAH4001B |
| 4 | 4 | 175A Power Distribution Terminal Block, #2/0 to #14 AWG Wire Size Range, IP20 Finger-Safe | Bussmann or Equal | PDBFS220 |
| 5 | 2 | Square D H-Frame, 30A, 3P, 600V, Thermal-Magnetic Circuit Breaker and NEMA 1 Surface -Mount Enclosure | Square D or Equal | HDL36030 & J250S |
| 6 | 1 | Type 1 Surge Protective Device, 480V, 3 Phase Delta, 3-Wire + Ground with Transient Filter and Surge Counter | Joslyn or Equal | JSP240-3D480-FB |
| 7 | 1 | Square D Mini-Power Zone, 5kVA, 480V-240/120V, NEMA 3R Enclosure with Primary & Secondary Main Breakers | Square D or Equal | MPZ5S40F |
| 8 | 5 | Square D Type QO Plug-On Circuit Breaker, 15A, 1P, 120/240V for MPZ Panelboard | Square D or Equal | QO115 |
| 9 | 1 | Square D Type QO Plug-On Circuit Breaker, 15A, 1P, 120/240V with 30 mA Ground Fault Protection for MPZ Panelboard | Square D or Equal | QO115EPD |
| 10 | 1 | Duplex 15A, 125V, GFCI Type Receptacle, Heavy Duty, 2P, 3-Wire Grounded, Ivory | Hubbell or Equal | GF15IL |
| 11 | 1 | Handy Box and Receptacle Cover | Raco or Equal | 8660 & 864 |
| 12 | 1 | Copper Bonded Steel Ground Rod, 3/4" Dia x 10 Ft Long | Erico or Equal | 613400 |
| 13 | 1 | 3-Phase Motor Protection Relay, 120Vac Control Power, 13 Protective Functions, Trip and Alarm Fail-Safe Relays | Littelfuse Powr-Gard | PGR-6150-120 |
| 14 | 1 | Operator Interface for Motor Protection Relay | Littelfuse Powr-Gard | PGR-6150-OP1 |
| 15 | 1 | Motor Protection Circuit Breaker, Red/Yellow Lockable Knob, 480v, 3 PH, 60Hz 2.5 to 4A Adjustable Range with Front-Mounted N.O. Aux Contact | Allen-Bradley | 140M-C2E-B40-KY & 140M-C-AFA10 |
| 16 | 1 | IEC Contactor, 9A, 480V, 3 Ph, 60 Hz 120V, 1 N.O. Aux Contact, 60Hz Coil | Allen-Bradley | 100-C09D10 |
| 17 | 1 | 3 Position Selector Switch, Spring-Return from Left, 2 Contact Blocks with Hand-Off-Auto Legend Plate | Allen-Bradley | 800T-J4B & 800T-X511 |
| 18 | 1 | Green LED Pilot Light, 120Vac, 60 Hz | Allen-Bradley | 800T-QH2G |
| 19 | 1 | NEMA 4/13 Die Cast, 2-Hole Surface Mount Pushbutton Enclosure | Allen-Bradley | 800T-2TZ |
| 20 | 1 | DPDT Plug-In Relay, 24VDC Coil, LED, Push-to-Test and Manual Override and Socket | Allen-Bradley | 700-HA32Z24-3-4 & 700-HN100 |
| 21 | Lot | DIN Rail #3 for Mounting Components as required | Allen-Bradley | 199-DR1 |
| 22 | Lot | DIN Rail, 30A Terminal Blocks, End Anchors, End Barriers as required | Allen-Bradley | 1492-N22, 1492-HM1 1492-N23, 1492-NM36 |





PUMP STATION CONTROL PANEL DETAIL
NTS




PLAN





SECTION A

NOTES:


1. 7 BARS PERPENDICULAR TO 5'-4" DIMENSION TOP AND BOTTOM.
   4 BARS PERPENDICULAR TO 2'-6" DIMENSION TOP AND BOTTOM

CONTROL PANEL PAD DETAIL
NTS




PUMP STATION CONTROL PANEL DETAIL
NTS

AQ
TYP E-302A




TYPICAL PUMP STATION ONE LINE
NTS

5KVA 480V-120/240V MINIMUM POWER ZONE

TIMOTHY C. KESSLER, P.E.
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 12/02/16 | DCB 007.4.2 | TDD | SGS |
| 2 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 1 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | DR | RJR | BY |
| | | TDD | SHM | APVD |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

WIRING DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-302A |
| SHEET | 65A OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**FINAL DCB 007.5 – CONTINGENT SYSTEM**

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.5 Major<br>Effective Date: 02/24/15 |
| Project Location: SA-6 SOUTH | |
| Title: GW EXTRACTION SYSTEM | |
| Revision to the Geomembrane/Subgrade surface. | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification.

DCB-007.2 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

DCB-007.3 provided the final details for the SA-6S groundwater collection trenches and associated electrical supply and groundwater discharge piping

DCB-007.4 issue pending. This DCB will provide the revised one line electrical drawings for SA-6N and SA-6S. In the revised design there is one extraction manhole on SA-6S and two extraction manholes in SA-6N.

DCB-007.5 provides a revised subgrade/Geomembrane surface as discussed below.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each Open Space Area and common header system. The trench design has one pump station in SA-6S and 2 pump stations in SA-6N.

Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.5 is applicable to the SA-6N and SA-6S subgrade/Geomembrane surface. The change from wells to trenches resulted in numerous changes in grading. There were typically depression in the subgrade around each well to allow for installation of control vaults at each well and associated force mains leading from each well. These depressions have been eliminated and the Geomembrane surface smoothed at these locations. A depressed area has been added at each pump station and associated force main. The changes simplify the grading and Geomembrane installation

The changes impact the following drawings.
For 6A-South:

- C-122
- C-123
- C-124

For 6A-North:

- CN-123
- CN-124

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Design changed based on information gathered during construction<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system one line electrical design. |
| Honeywell (AP) Review:<br>Individual Discipline | Initial Date |
| (Name / Signature): 2/24/15 | Does DCB Result in CCO? ☑ Yes (b) ☐ No<br>Date: |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

SA-7

MATCH LINE SHEET C-123

D C-122 C-301 TYPICAL EDGE DETAIL ALONG EXISTING SCB WALL

EXISTING SOIL CEMENT BENTONITE WALL

HYDRAULIC BARRIER/SCB CONNECTION C-122 C-301 B

CB C-122 C-310 ACCESS MANHOLE

2X2 INLET PER RECORD MAPPING NOT RECOVERED

A C-122 C-301 5+00 CAP AREA BUILDUP (TYP) (SEE NOTE 3)

6+00 4+00 3+00 2+00 1+00

UTILITY CORRIDOR

PROPOSED HYDRAULIC BARRIER SEE PLAN AND PROFILE SHEETS S-201 THRU S-203

F C-122 C-301 TYPICAL EDGE DETAIL ALONG PROPOSED HYDRAULIC BARRIER

G C-122 C-301 TYPICAL EDGE DETAIL GCL INSTALLATION BELOW GROUNDWATER TABLE

P C-122 C-309 TYPICAL UTILITY CORRIDOR/ HYDRAULIC BARRIER WALL CROSSING DETAIL

INLET 'B' TC 9.54 GR 9.01 INV 5.26(18" RCP-N) INV 4.91(18" RCP-S)

INLET 'B' TC 8.33 GR 7.84 INV 6.29(NW) INV 5.89(SE)

INLET 'B' TC 8.48 GR 7.98 INV 4.66(N) INV 4.56(S)

MANHOLE RIM 10.17 INV. 3.70(8"-N,E,& W) INV. 3.67(S) FILLED W/DEBRIS UNABLE TO DETERMINE PIPE TYPE

TERMINUS NOT FOUND (TYP.)

KELLOGG STREET

NEW JERSEY STATE HIGHWAY ROUTE 440

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | | | SHM |
| 1 | 02/24/15 | TDD | RJR | TDD | APVD |
| 0 | 06/07/13 | TDD | SHM | TDD | SHM |

DCB 007.5
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-122 |
| SHEET | 27 OF 66 |

MATCH LINE SHEET C-124

MATCH LINE SHEET C-122

CB C-123 C-310 ACCESS MANHOLE

D C-123 C-301 TYPICAL EDGE DETAIL ALONG EXISTING SCB WALL

EXISTING SOIL CEMENT BENTONITE WALL

UTILITY CORRIDOR

P C-123 C-309 TYPICAL UTILITY CORRIDOR/ HYDRAULIC BARRIER WALL CROSSING DETAIL

F C-123 C-301 TYPICAL EDGE DETAIL ALONG HYDRAULIC BARRIER

A C-123 C-301 CAP AREA BUILDUP (TYP) (SEE NOTE 3)

CB C-123 C-310 ACCESS MANHOLE

G C-123 C-301 TYPICAL EDGE DETAIL GCL INSTALLATION BELOW GROUNDWATER TABLE

HYDRAULIC BARRIER SEE PLAN AND PROFILE SHEETS S-201 THRU S-203

KELLOGG STREET

DROYERS COVE

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 02/24/15 | TDD | RJR | TDD | SHM |
| 0 | 06/07/13 | | | | |

REVISION BY APVD

ISSUED FOR CONSTRUCTION TDD SHM

DCB 007.5 TDD SGS

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GEOMEMBRANE GRADING PLAN


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28001600

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-123 |
| SHEET | 28 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR28-C-123 Geomembrane Grading Plan.dwg PLOT DATE: Tue, 24 Feb 2015 PLOT TIME: 2:25 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 02/24/15 | TDD | TDD | RJR | SHM |
| 1 | 10/11/13 | | | | |
| 0 | 06/07/13 | | | | |

DCB 007.5
MODIFIED BARRIER WALL ALIGNMENT
ISSUED FOR CONSTRUCTION

| REVISION | BY | APVD |
|---|---|---|
| | TDD | SGS |
| | RJR | SGS |
| | TDD | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC. MATERIAL DESCRIBED THEREON, NOR THE

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-124 |
| SHEET | 29 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR29-C-124 Geomembrane Grading Plan.dwg PLOT DATE: Tue, 24 Feb 2015 PLOT TIME: 2:29 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TO OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | TDD | RJR | TDD |
| 1 | 02/24/15 | DCB 007.5 | TDD | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS | |
| | | REVISION | BY | APVD | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-123 |
| SHEET | 28 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR28-C-123 Geomembrane Grade.dwg PLOT DATE: Tue, 24 Feb 2015 PLOT TIME: 2:33 PM




MATCH LINE SHEET CN-123

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TOP OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 02/24/15 | TDD | RJR | TDD | APVD |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD | SGS |
| | | DCB 007.5 | | TDD | SGS |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-124 |
| SHEET | 29 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR29-C-124 Geomembrane Grade.dwg PLOT DATE: Wed, 25 Feb 2015 PLOT TIME: 7:42 AM

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 17 OF 25**

- **DCBs Applicable to SA-6 South Part 2**
  **(DCB 008.1 and 009)**

**FINAL DCB 008.1 – AREA 1S SURCHARGE PILE GEOMETRY**

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 008.1 Major (a)<br>Effective Date: 8/14/13 |
| Project Location: SA-6 NORTH<br>Title: 1S Surcharge Pile Geometry | Associated RFI:<br>☐ Yes, RFI No. ___ ☑ None |
| Contractor (Subcontractor): Entact | Project No.: 3480130377 |

Description of Change/Modification:
Due to decisions to defer shallow excavation adjacent to the bulkhead, Amec has made a minor modification in the surcharge pile geometry and final grading geometry along the western edge of Area S1 to reduce the re-work that will be required when the bulkhead is completed and the deferred area remediated.

DCB-008 will be issued in two sections
DCB-008.1 Surcharge Pile Revisions
DCN-008.2 Subgrade and Final Grading

DCB-008.1 The crest of the surcharge (elevation 24) is being moved approximately 16 ft. to the east of the Barrier Wall.
The top of the Barrier Wall "as installed" steps from elevation 14 to elevation 16.
Where the Barrier wall is at elevation 14 the toe of slope will extend beyond the wall as shown in Figure 1.
Where the Barrier Wall is at elevation 16 the toe will terminate at the Barrier Wall.
It is anticipated that displacement will be seen at the inclinometers. It is also anticipated that the rate of fill placement will be limited within 75 ft. of the Barrier Wall by displacement at the inclinometers. It is considered likely that filling from elevation 13 to elevation 16 may take a week or more between lifts.
All materials placed outside the Barrier Wall will be imported clean surcharge fill. A placement plan should be developed for the toe between the bulkhead and Barrier Wall to minimize equipment loading on the bulkhead. At a minimum the top 12 inches of the constructed pile will be "imported surcharge"
The west face of the slope will be covered with erosion control fabric.


| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason<br>Reduce construction loads on the existing bulkhead pending bulkhead improvements. Minimize re-work in the "deferred area".<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☐Yes ☑ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: Major DCB anticipated, requires review and approval by third parties. | Design Documents Affected:<br>Drawings<br>C 108 Rev 2 |

| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| (Name / Signature): Shallard | | Does DCB Result in CCO? Date: | ☐ Yes Yes (b) ☑ No |
| Distribution: | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

JOB NO. SA-65 SHEET 1 OF 2
PHASE Surcharge 15 TASK
JOB NAME DCB 008.1
BY S.G. Ballard DATE 6/23/14
CHECKED BY DATE

amec
511 Congress Street Suite 200
Portland, ME 04101
+1 (207) 775-5401 Fax +1 (207) 772-4762





Typical Section
Top of Barrier Wall
Elev 14.

Fig 1


JOB NO. SA-65 SHEET 2 OF 2
PHASE Surcharge 15 TASK
JOB NAME DCB 008.1
BY SGS DATE 6/23/14
CHECKED BY DATE


amec
511 Congress Street Suite 200
Portland, ME 04101
+1 (207) 775-5401 Fax +1 (207) 772-4762




Typical Section
Top of Barrier Wall
Elev. 16.

Fig 2




SECTION 1-1

NOTES:

1. REFER TO GENERAL NOTES SHEETS G-003, G-004, AND THE SURCHARGE MONITORING PLAN FOR SA-6 SOUTH.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. REFER TO NOTES ON SHEET C-107.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 06/20/14 | TDD | RJR | RJR | SHM |
| 1 | 10/11/13 | TDD | RJR | SGS | SHM |
| 0 | 06/07/13 | TDD | TDD | SHM | SHM |

DCB 008.1
MODIFIED BARRIER WALL ALIGNMENT
ISSUED FOR CONSTRUCTION
REVISION

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CAP AREA SURCHARGE GRADING PLAN
AREA 1S

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-108 |
| SHEET | 13 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC; INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR13-C-108 Cap Area Surcharge Grading Plan Area 1.dwg PLOT DATE: Fri, 20 Jun 2014 PLOT TIME: 2:11 PM

**FINAL DCB 009 – SITE 163 EXCAVATION**

**DESIGN CHANGE BULLETIN**

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6, Jersey City, New Jersey** | **DCB No.: 009, Minor(a)**<br>**Effective Date: 7/28/14** |
| **Project Location: SA-6 North & South** | **Associated RFI:** |
| **Title: Site 163 Excavation** | ☐ Yes, RFI No. _____ ☒ None |
| **Contractor (*Subcontractor*): ENTACT** | **Project No.: 3480130377** |

**Description of Change/Modification:**


In lieu of in-situ treatment of an area of soil from 3 to 4 feet below grade on Site 163, Entact will now excavate those soils pre-characterized as 20-240 mg/kg for hexavalent chromium and consolidate the soils in the Open Space AOC. The area shown on revised Drawing C-114. This is a change from excavating only to 3 ft bgs as stipulated in the 100% Design. Volume of additional pre-characterized 20 – 240 mg/kg soil generated in this area is estimated to be 155 CYs.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☒ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:**<br>Increase depth of excavation in one area at Site 163<br>**Attachments:** ☒ Yes ☐ No<br>**Cost Implication:** ☐ Yes ☒ No<br>**>$50K** ☐ Yes ☒ No<br>**Schedule Impact** ☐ Yes ☒ No |
| **Additional Comments:** It is noted that | **Design Documents Affected:**<br>Drawing C-114 |
| **Honeywell (AP) Review:**<br>**Individual: Geoff Shallard Discipline: EOR** | **Initial** 8/20/14 **Date** |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☒ No<br>**Date** |

**Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec**

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval.
(b) – If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20–240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN–SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED
- DEFERRED AREA

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6–INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD | REVISION |
|---|---|---|---|---|---|---|
| 4 | 08/05/14 | TDD | RJR | TDD | | DCB9 SITE 163 EXCAVATION, DCB10 DEFERRED AREA |
| 3 | 05/16/14 | | | | | LOT 163 EXCAVATION 3 TO 4 FT BGS |
| 2 | 12/12/13 | | | | | EXCAVATION REVISIONS |
| 1 | 10/11/13 | | | | | MODIFIED BARRIER WALL ALIGNMENT |
| 0 | 06/07/13 | | | | | ISSUED FOR CONSTRUCTION |

| | BY | APVD |
|---|---|---|
| TDD | SGS | |
| TDD | DEN | |
| TDD | SGS | |
| RJR | SGS | |
| TDD | SHM | |
| TDD | APVD | |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
SHM LICENSE NUMBER 43607

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

CHROMIUM EXCAVATION INTERVAL 3

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 889 - 2629
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-114 |
| SHEET | 19 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR19-C-114 Chromium Excavation Interval 3.dwg PLOT DATE: Tue, 05 Aug 2014 PLOT TIME: 1:39 PM

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 18 OF 25**

- **DCBs Applicable to SA-6 South Part 3 (DCB 010-032)**

**FINAL DCB 010 – DEGEN DEFERRED AREA**

**DESIGN CHANGE BULLETIN**

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6, Jersey City, New Jersey** | **DCB Type: 010, Minor (a)**<br>**Effective Date: 05/19/14** |
| **Project Location: SA-6 South**<br>**Title: Degen Deferred Area** | **Associated RFI:**<br>☐ Yes, RFI No. _____ ☒ None |
| **Contractor (*Subcontractor*): ENTACT** | **Project No.: 3480130377** |

**Description of Change/Modification:**

Honeywell will defer all excavation in the area shown on the attached **Figure 1**. This area includes a portion of Cell 153 and Cell 154 through Cell 156 in their entirety (see Photo 1). This design change is necessary due to unanticipated subsurface conditions. Approximately 5 feet of concrete was encountered in the subgrade of this area during excavation in Cell 153 (see cross-section A-A'). The concrete was also observed to have flowed around structural elements of the bulkhead. Demolition of the concrete to facilitate the excavation as shown on the Issued for Construction Design posed an unacceptably high potential for damage and loss of integrity to the bulkhead in this area (see Photo 2). Therefore, removal of the concrete/asphalt berm, demolition of subsurface concrete, and excavation to the specified design elevations will be deferred until implementation of the bulkhead portion of the Bayfront Redevelopment Plan.
Note Exc. 10 on sheet C-104 should be hand annotated as deleted. A new sheet C-104 will not be issued.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☒ Unforeseen or Differing Site Conditions<br>☒ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:** Deferred Excavation Due to Unanticipated Excessive Concrete<br>**Attachments:** ☒ Yes ☐ No<br>**Cost Implication:** ☒ Yes ☐ No<br>**>$50K** TBD<br>**Schedule Impact** ☐ Yes ☒ No |
| **Additional Comments:** DCB anticipated to require review and approval by third parties. | **Design Documents Affected:**<br>Drawings C-112, C-113, C- 114, C-115 and C-104 |
| **Honeywell (AP) Review:**<br>**Individual: Geoff Shallard** **Discipline: EOR** | **Initial** **Date** 5/20/14 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☒ Yes ☐ No<br>**Date** |

**Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec**

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval.
(b) – If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





Figure 1 - Deferred Area

LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
  PCINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM D EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE
- LIMIT OF EXCAVATION AREA

ENTACT 332 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 04-14-14 TO 05-01-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ



Photo 1 - Deferred Area at SA-6 South (Site 073)

JOB NO. 3480130377 SHEET 1 OF 1
PHASE TASK
JOB NAME SA-6 CHROMIUM REMEDY
BY DEM DATE 5/13/14
CHECKED BY DATE

amec
American Metro Center 200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
+1 (609) 689-2829 Fax +1 (609) 689-2838

# SECTION A-A'







**Photo 2 - Bulkhead at Deferred Area at SA-6 South (Site 073)**




## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED
- DEFERRED AREA

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 08/05/14 | DCB9 SITE 163 EXCAVATION, DCB10 DEFERRED AREA | TDD | SGS |
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | TDD | DR | RJR | BY | APVD |

SAMUEL G. SHALLARD
SHM LICENSE NUMBER 43507
NJ PROFESSIONAL ENGINEER

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC. THE MATERIAL DESCRIBED THEREON, NOR THE USE OF

Honeywell
101 COLUMBIA RD. BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CHROMIUM EXCAVATION INTERVAL 1


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 587-2200
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-112 |
| SHEET | 17 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR17-C-112 Chromium Excavation Interval 1.dwg PLOT DATE: Wed, 20 Aug 2014 PLOT TIME: 2:53 PM




MATCH LINE SEE ABOVE

## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED
- DEFERRED AREA

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 08/05/14 | DCB9 SITE 163 EXCAVATION, DCB10 DEFERRED AREA | TDD | | SGS |
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | | SHM |
| | | REVISION | BY | | APVD |
| | | | TDD | RJR | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 2


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-113 |
| SHEET | 18 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR18-C-113 Chromium Excavation Interval 2.dwg PLOT DATE: Wed, 20 Aug 2014 PLOT TIME: 2:52 PM




LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20-240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED
- DEFERRED AREA

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 4 | 08/05/14 | DCB9 SITE 163 EXCAVATION, DCB10 DEFERRED AREA | TDD | SGS |
| 3 | 05/16/14 | LOT 163 EXCAVATION 3 TO 4 FT BGS | TDD | DEN |
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | TDD | DR RJR | BY APVD |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 3


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 587-2200
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-114
SHEET 19 OF 66

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR19-C-114 Chromium Excavation Interval 3.dwg PLOT DATE: Wed, 20 Aug 2014 PLOT TIME: 2:52 PM




MATCH LINE SEE ABOVE

## LEGEND

- HEXAVALENT CHROMIUM SOIL CONTAMINATION UNDER 20 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION BETWEEN 20–240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 240 PPM
- HEXAVALENT CHROMIUM SOIL CONTAMINATION OVER 1000 PPM
- AREAS OF IN-SITU TREATMENT BELOW 3 FEET
- NO EXCAVATION REQUIRED
- DEFERRED AREA

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

NOTE: EXCAVATION IS INTENDED TO TERMINATE AT TOP OF STRATUM D LAYER IF ENCOUNTERED. CONTRACTOR SHALL REVIEW PROJECT BORING LOGS TO VERIFY ANTICIPATED TOP OF STRATUM D ELEVATIONS. CONTRACTOR MAY BE REQUIRED TO REMOVE UP TO 6-INCHES OF STRATUM D BASED ON DIRECTION OF THE ENGINEER.

0 25 50 100
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 08/05/14 | DCB 10 DEFERRED AREA | TDD | SGS | |
| 2 | 12/12/13 | EXCAVATION REVISIONS | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | | TDD | RJR | TDD | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2108, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
CHROMIUM EXCAVATION INTERVAL 4

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2500
NJ Certification of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-115 |
| SHEET | 20 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR20-C-115 Chromium Excavation Interval 4.dwg PLOT DATE: Wed, 20 Aug 2014 PLOT TIME: 2:53 PM

**FINAL DCB 011 – MWAP REVISED TABLES**

## DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6, Jersey City, New Jersey** | **DCB No.: 011, Minor(a)**<br>**Effective Date: 7/28/14** |
| **Project Location: SA-6 North & South** | **Associated RFI:**<br>☐ Yes, RFI No. _____ ☒ None |
| **Title: Revised Monitoring Well Abandonment Plan Tables** | **Project No.: 3480130377** |
| **Contractor (*Subcontractor*): ENTACT** | |

**Description of Change/Modification:**

Revised tables of wells to be abandoned and retained are provided. The designation (abandon/retain) of several wells has been modified to accommodate the changing site conditions and future work at the site.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☒ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:**<br>Clarify well abandonment requirements<br>**Attachments:** ☒ Yes ☐ No<br>**Cost Implication:** ☐ Yes ☒ No<br>**>$50K** ☐ Yes ☒ No<br>**Schedule Impact** ☐ Yes ☒ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Appendix A-2, Monitoring Well Abandonment Plan Tables |
| **Honeywell (AP) Review:**<br>**Individual: Geoff Shallard Discipline: EOR** | **Initial** GS **Date** 7/30/14 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☒ No<br>**Date** |

**Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec**

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval.
(b) – If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-EW-4 (aka 087-MW-142) | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-EW-5 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-EW-6 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-EW-7 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-001 | **Abandon** | S-3 Injection Program | Plaintiffs Requested Monitoring of this Well |
| | | 087-MW-101 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-102 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-103 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-104 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-105 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-106 (aka 087-MW-121) | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-106 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-107 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-108 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-109 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-110 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-111 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-112 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-113 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-114 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-115 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-116 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-117 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-118 | **Retain** | Non-Cr - JCDPW-1B UST AOC | Post remediation GW monitoring |
| | | 087-MW-119 | **Retain** | Non-Cr - JCDPW-1B UST AOC | Post remediation GW monitoring |
| | | 087-MW-120 | **Retain** | Non-Cr - JCDPW-1B UST AOC | Post remediation GW monitoring |
| | | 087-MW-121 (aka 087-MW-106) | | See Above | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 087-MW-122 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-123 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-124 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-125 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-126 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-127 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-128 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-129 | **Retain** | Non-Cr - JCMUA-1A UST AOC | UST AOC Monitoring |
| | | 087-MW-140 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-141 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-142 (aka 087-EW-4) | | See Above | |
| | | 087-MW-A26 | **Retain*** | Site-wide LTMP | Shallow GW level monitoring near Rt. 440 sewers |
| | | 087-MW-I30 | Retain | None | |
| | | 087-MW-O19 | Abandon | None | |
| | | 087-MW-O23 | **Retain** | Non-Cr - CEA | Monitoring for CEA |
| | | 087-MW-O29 | **Retain** | In-Situ | Monitoring GW for In-Situ Program |
| | | 087-MW-S19 | Abandon (hold off) | None | |
| | | 087-MW-U28 | Abandon | None | |
| | | 087-MW-W25 | Abandon | None | |
| | | 087-MW-Y20 | Abandon | None | |
| | | ME-02 (aka 087-SB-410) | Abandon | Geotech - Methane Monitoring | |
| | | ME-03 (aka 087-SB-409) | Abandon | Geotech - Methane Monitoring | |
| | | ME-04 (aka 087-SB-408) | Abandon | Geotech - Methane Monitoring | |
| | | 087-PZ-001 | Abandon | None | |
| | | 087-PZ-003 | Abandon | None | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

Added to list of wells to be abandoned
Removed from list of wells to be abandoned

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 087-PZ-005 | Abandon | None | |
| | 088 | 088-MW-001 | **Retain*** | Site-wide LTMP | Shallow GW level monitoring near Rt. 440 sewers |
| | | 088-MW-002 | Abandon | None | |
| | | 088-MW-101 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | Monitoring for EAISB Program |
| | | 088-MW-102 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | Monitoring for EAISB Program |
| | | 088-MW-103 | Abandon | Non-Cr - JCIA-1A UST AOC | Monitoring for EAISB Program |
| | | 088-MW-105 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-106 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-107 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-108 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-109 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-110 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-111 | **Retain** | Non-Cr - JCIA-1B UST AOC | Post remediation GW monitoring |
| | | 088-MW-112 | **Retain** | Non-Cr - JCIA-1B UST AOC | Post remediation GW monitoring |
| | | 088-MW-113 | **Retain** | Non-Cr - JCIA-1B UST AOC | Post remediation GW monitoring |
| | | 088-MW-114 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-115 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-G19 | Abandon | None | |
| | | ME-01 (aka 088-SB-306) | Abandon | Geotech - Methane Monitoring | |
| | | 088-PZ-001 | Abandon | None | |
| | | 088-PZ-003 | Abandon | None | |
| SA-6 South | 73 | 073-MW-3 | **Retain** | None | |
| | | 073-MW-4 | Abandon | None | |
| | | 073-MW-5 | Abandon | None | |
| | | 073-MW-BB11 | Abandon | None | |
| | | 073-MW-Y10 | Abandon | None | |
| | | 073-PZ-001 | Abandon | None | |
| | 124 | 124-MW-01 | Abandon | | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

Added to list of wells to be abandoned
Removed from list of wells to be abandoned

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 124-MW-02 | Abandon | None | |
| | | 124-MW-07 | Abandon | | |
| | | 124-MW-09 | Abandon | | |
| | | 124-MW-10 | **Retain** | None | Potential additional offsite GW monitoring |
| | | 124-MW-11 | **Retain** | None | Potential additional offsite GW monitoring |
| | | ME-01 (aka 124-SB-503) | Abandon | Geotech - Methane Monitoring | |
| | 125 | 125-MW-01 | Abandon | None | |
| | | ME-02 (aka 125-SB-501) | Abandon | Geotech - Methane Monitoring | |
| | | 125-PZ-001 | Abandon | None | |
| | | 125-PZ-003 | Abandon | None | |
| | 134 | 134-MW-01 | Abandon | | |
| | | 134-MW-02 | **Retain** | Non-Cr - CEA | Quarterly source area monitoring for MNA |
| | | 134-MW-Q08 | Abandon | None | |
| | | 134-MW-V09 | **Retain** | Non-Cr - CEA | Quarterly source area monitoring for MNA |
| | | ME-03 (aka 134-SB-503) | Abandon | Geotech - Methane Monitoring | |
| | | ME-04 (aka 134-SB-504) | Abandon | Geotech - Methane Monitoring | |
| | | 134-PZ-001 | Abandon | None | |
| | | 134-PZ-003 | Abandon | None | |
| | 140 | 140-MW-01 | Abandon | | |
| | | 140-MW-04 | **Retain** | Non-Cr - CEA | Monitor for previous owner's MNA/CEA program |
| | | 140-MW-06 | Abandon | None | |
| | | 140-MW-07 | Abandon | None | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 140-MW-08 | Retain | Non-Cr | In Non-Cr Former UST AOC Excavation |
| | | 140-MW-1R | **Retain** | Non-Cr - CEA | Monitor for previous owner's MNA/CEA program |
| | | 140-PZ-001 | Abandon | None | |
| | | 140-MW-106 | Abandon | None | |
| | 163 | 163-MW-1 | **Retain** | Non-Cr - CEA | Monitoring for CEA |
| | | 163-MW-CC8R | Abandon | | |
| | | 163-MW-R05 | Abandon | None | |
| | | 163-MW-2R | **Retain** | Non-Cr & Chromium | Quarterly monitoring of VOC plume fringe (See Table 1b) |
| | | 163-MW-Y6R | Abandon | | |

* Retain if feasible, monitoring well is in excavation area.

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1b**
**PROPOSED SHALLOW ZONE WELLS**
**FOR POST-REMEDY INSTALLATION**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Well | New / Replace / Retain | Related Monitoring Program | Reason to Install |
|---|---|---|---|---|
| SA-6 North | 115-W1-SO | Retain | SA-6 North LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-W6-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-E4-SO | Retain | SA-6 North LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-E5-SO | Retain | SA-6 North LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | SA6N-PZ1-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ1-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ2-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ2-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ3-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ3-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ4-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ4SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ5-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ5-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| SA-6 South | 115-E1-SO | Abandon | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-E1A-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-W3-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-W5-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | SA6S-PZ1-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ1-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ2-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ2-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ3-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ3-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ4-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ4SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1b**
**PROPOSED SHALLOW ZONE WELLS**
**FOR POST-REMEDY INSTALLATION**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Well | New / Replace / Retain | Related Monitoring Program | Reason to Install |
|---|---|---|---|---|
| | SA6S-PZ5-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ5-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-MW-01 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-02 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-03 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-04 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-05 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-06 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-07 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-08 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-09 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-10 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-11 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | 163-MW-2R (SA6S-MW-12) | Retain | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 2**
**PROPOSED INTERMEDIATE ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-MW-13 | **Retain** | | |
| | | 087-MW-A26D | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-W25D | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-O29D | **Retain** | S-3 Injection | Monitor S-3 Injection |
| | | 087-MW-O19D | **Retain*** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-35 | Abandon | GWET LTMP | |
| | | 087-OBS-1D | **Retain** | GWET LTMP | |
| | | 087-OBS-1L | **Retain** | GWET LTMP | |
| | | 087-OBS-2D | **Retain** | GWET LTMP | |
| | | 087-OBS-3L | **Retain** | GWET LTMP | |
| | | 087-OBS-5D | **Retain** | GWET LTMP | |
| | | 087-OBS-6D | Abandon | GWET LTMP | |
| | | 087-PZ-002 | Abandon | SA-6N Design Investigation | |
| | | 087-PZ-004 | Abandon | SA-6N Design Investigation | |
| | | 087-PZ-006 | Abandon | SA-6N Design Investigation | |
| | 088 | 088-MW-15 | **Retain** | GWET LTMP | Define regional flow direction quarterly |
| | | 088-PZ-002 | Abandon | SA-6N Design Investigation | |
| | | 088-PZ-004 | Abandon | SA-6N Design Investigation | |
| SA-6 South | 73 | 073-PZ-002 | Abandon | SA-6S Design Investigation | |
| | 124 | 124-MW-102D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-103D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-104D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-105D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-GO2D | **Retain** | Deep Overburden Invest. | Define regional flow direction quarterly |
| | 125 | 125-PZ-002 | Abandon | SA-6S Design Investigation | |
| | | 125-PZ-004 | Abandon | SA-6S Design Investigation | |
| | 134 | 134-PZ-002 | **Retain** | SA-6S Design Investigation | Define regional flow direction quarterly |
| | | 134-PZ-004 | Abandon | SA-6S Design Investigation | |
| | 140 | 140-PZ-002 | Abandon | SA-6S Design Investigation | |
| | | 140-MW-P05D | **Retain** | Deep Overburden Invest. | Define regional flow direction quarterly |

**TABLE 2**
**PROPOSED INTERMEDIATE ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

| | | | | | |
|---|---|---|---|---|---|
| SA-7 | 115 | 115-E1-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E1-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-E2-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E2-DO | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E3-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E3-DO | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E4-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E4-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-E5-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E5-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-E6-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E6-DO | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-17 | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-20 | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-A12T | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-E14D | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-U14D | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-W1-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-W4-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-W4-DO | Abandon | | |

*Optionally, to be re-located north of the open space area

**TABLE 3**
**PROPOSED DEEP ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Related**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-MW-A26T | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-W25T | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-OBS-1T | **Retain** | | |
| | | 087-OBS-4T | **Retain** | GWET LTMP | Monitor GWET drawdown |
| | | 087-OBS-5T | **Retain** | | |
| | | 087-MW-01 | **Retain** | GWET LTMP | Monitor S-3 Injection |
| | | 087-MW-02 | **Retain** | | |
| | | 087-MW-03 | Abandon | None | |
| | | 087-MW-08 | **Retain** | | |
| | | 087-MW-34 | **Retain** | | |
| | | 087-IW-01 | **Retain** | S-3 Injection | Inject and monitor S-3 Injection |
| | 088 | 088-MW-G19T | **Retain** | S-3 Injection | Monitor S-3 Injection |
| | | 088-IW-01 | **Retain** | S-3 Injection | Inject and monitor S-3 Injection |
| | | 088-IW-02 | **Retain** | S-3 Injection | Inject and monitor S-3 Injection |
| SA-6 South | 124 | 124-MW-GO2T | **Retain** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-102T | Abandon | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-103L | Abandon | Plume Diversion | Collect In-situ groundwater sample prior to capping |
| | | 124-MW-104T | Abandon* | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-104L | **Retain*** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-105T | **Retain*** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-106T | **Retain*** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-107T | Abandon | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-06 | Abandon | None | |
| SA-7 | 115 | 115-MW-04 | **Retain** | | |
| | | 115-MW-05 | **Retain** | | |

| | | | | | |
|---|---|---|---|---|---|
| | | 115-MW-21 | **Retain** | | |
| | | 115-MW-E14T | **Retain** | | |
| | | 115-MW-U14T | **Retain** | | |
| Offsite, South of SA-6 South | 119 | 119-MW-01T | **Retain** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 119-MW-02T | **Retain** | Plume Diversion | "L-Well" Monitoring Plan Sampling |

* Retain if feasible, monitoring well is in excavation area.
*Abandon: monitoring well could not be retained durnig excavation.

**TABLE 4**
**PROPOSED BEDROCK WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-MW-O29T | Abandon | None | |
| | | 087-MW-I30T | Abandon | None | |
| | | 087-MW-14 | Abandon | None | |
| SA-6 South | 073 | 073-MW-1BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 073-MW-10BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | 119 | 119-MW-16BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | 124 | 124-MW-8BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 124-MW-17BR-1 | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 124-MW-17BR-2 | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | 140 | 140-MW-9BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| SA-7 | 115 | 115-MW-208BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 115-MW-211BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 115-MW-215BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 115-MW-216BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |

**FINAL DCB 012 – HYDROCARBON SOILS IN CAP**

**DESIGN CHANGE BULLETIN**

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6, Jersey City, New Jersey** | **DCB No.: 012, Minor(a)**<br>**Effective Date: 10/28/14** |
| **Project Location: SA-6 North & South** | **Associated RFI:** |
| **Title: Hydrocarbon Soils in Cap Area** | ☐ Yes, RFI No. _____ ☒ None |
| **Contractor (*Subcontractor*): ENTACT** | **Project No.: 3480130377** |

**Description of Change/Modification:**

Hydrocarbon-impacted soils have been identified based on odor and PID readings as being co-mingled with the chromium-impacted soil in the SA-6 South chromium excavation. Hydrocarbon-impacted soil will be stockpiled separately from the non-hydrocarbon-impacted soil. Stockpiles will be sampled and analyzed for characterization as described in correspondence with NJDEP. It was determined that some of the hydrocarbon-impacted soil containing elevated levels of VOCs were to be disposed offsite, but certain other of hydrocarbon-impacted soil could be consolidated within the SA-6 South Open Space Area as long as the soil meets all other applicable reuse requirements of the Soil Management Plan (Appendix G – SA-6 North 100% Design Report). Hydrocarbon soils approved by the Engineer for placement under the SA-6 South cap will be consolidated in defined areas.

Placement and consolidation of the identified hydrocarbon-impacted soil will be conducted according to Specification 02315 – Earthwork. To the extent possible, the hydrocarbon-impacted soil should be placed in the Open Space Area and covered with non-hydrocarbon-impacted, chromium-impacted soil prior to construction of the cap over the soils. The vertical and horizontal limits of these areas will be documented in the final remedial action report.

Placement of hydrocarbon soils within the SA-6 South Open Space AOC was approved by the Plaintiffs in an email dated June 19, 2014 and by the NJDEP in an email dated October 2, 2014.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☒ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:**<br>Develop guidelines and requirements for the handling of hydrocarbon-impacted soils in the Open Space AOC |
| | **Attachments:** ☐ Yes ☒ No |
| | **Cost Implication:** ☒ Yes ☐ No<br>**>$50K** ☒ Yes ☐ No<br>**Schedule Impact** ☒ Yes ☐ No |
| **Additional Comments:** | **Design Documents Affected:**<br>None |

**Honeywell (AP) Review:**

**Individual: Geoff Shallard** **Discipline: EOR** **Initial** GS **Date** 11/5/14

**DESIGN CHANGE BULLETIN**

| | |
|---|---|
| **(Name / Signature):** | **Does DCB Result in CCO?** ☒ Yes (b) ☐ No<br>**Date** |
| **Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval.
(b) – If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**FINAL DCB 015 – ASPHALT AND CONCRETE UNDER CAP**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6 Jersey City, NJ** | **DCB No: 015; DCB Type: Minor(a)** |
| | **Effective Date: 10/31/14** |
| **Project Location: SA-6 NORTH and SOUTH** | **Associated RFI:** |
| **Title: Asphalt / Concrete under the Cap** | ☐Yes, RFI No. ___ ☑ None |
| | **Project No.: 3480130377** |
| **Contractor (Subcontractor): ENTACT** | |

**Description of Change/Modification:**

Amec has revised the Soil Management Plan (Appendix G – SA-6 North 100% Design Report) to indicate that any asphalt or concrete that meets NJDEP reuse requirements or is granted a variance by the NJDEP may be reused onsite as backfill or placed underneath the cap.

Prior excavation on SA-6 South, sixteen (16) samples of the asphalt pavement were collected in-situ throughout the excavation footprint. Concentrations of arsenic in six (6) of the samples exceed the RDCSRS of 19 mg/kg for arsenic. Entact has removed the arsenic-impacted asphalt from the excavation area and stockpiled it in the cap area. Honeywell requested approval from NJDEP and Plaintiffs to consolidate the asphalt in either the SA-6 North or SA-6 South Open Space Areas, in lieu of disposing of the arsenic-impacted asphalt offsite. Placement of the arsenic-impacted asphalt in either the SA-6 North or SA-6 South Open Space Area was approved by the Plaintiffs in an email dated September 9, 2014 and by the NJDEP in an email dated October 15, 2014.

Therefore, Entact is hereby directed to consolidate the subject arsenic-impacted asphalt in either the SA-6 North or SA-6 South Open Space Areas in a footprint that does not exceed 44,000 SF and cover the asphalt with chromium-impacted soil prior to construction of the cap over the soils. The vertical and horizontal limits of these areas will be documented in the final remedial action report.

Placement and consolidation of concrete or asphalt underneath the cap will be conducted according to Specification 02315 – Earthwork.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:** NJDEP variance required to place impacted asphalt and concrete under the cap |
| | **Attachments:** ☑ Yes ☐ No |
| | **Cost Implication:** ☐ Yes ☑ No<br>**>$50k** ☐ Yes ☑ No<br>**Schedule Implication** ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** SA-6 North 100% Design Appendix G - Soil Management Plan |

**Honeywell (AP) Review:**

**Individual: Samuel G. Shallard** **Discipline:** **Initial:** **Date:** 11/6/14

| | |
|---|---|
| **(Name / Signature):** Samuel G. Shallard | **Does DCB Result in CCO?** ☐ Yes (b)☑ No<br>**Date:** |
| **Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

All above grade demolition activities will be conducted by Jersey City entities or by others.

Concrete and asphalt will be characterized by sampling per NJDEP's procedure on "Guidance for Characterization of Concrete and Clean Material Certification for Recycling" for recycling purposes pursuant to N.J.A.C. 7:26A or for beneficial reuse onsite pursuant to N.J.A.C. 7:26-1.7(g). Concrete determined to meet NJDEP reuse requirements, or which is granted a variance by NJDEP to meet reuse requirements, may be reused onsite as backfill in excavations or placed under the cap. Asphalt determined to meet NJDEP reuse requirements, or which is granted a variance by NJDEP to meet reuse requirements, may be used as sub-grade fill under new asphalt paved areas or placed under the cap. Concrete and asphalt that do not meet these NJDEP reuse or variance requirements will be disposed of offsite.

## 2.4 SA-6 SOUTH CONSTRUCTION DEBRIS MANAGEMENT

Asphalt and concrete removal at SA-6 South will be as shown on the Chromium Remedy Design Drawings. All concrete and asphalt materials will be managed in accordance with Section 02220 of the Technical Specifications. Honeywell has or is in the process of implementing demolition of building superstructures at SA-6 South prior to the implementation of the remedial actions. All buildings have been or will be demolished to their concrete slab foundations. All aboveground superstructure materials (concrete, steel, wood, etc) have or will be disposed of offsite. To the extent possible, any remaining concrete, asphalt and steel materials that do not interfere with remedial construction will be left in place. Concrete and asphalt will be generated during the remedial process from the following areas:

- Paved surfaces within the SA-6 South Open Space Area; and
- Paved surfaces and building slabs within the excavation areas within the SA-6 South Development Area.

Concrete and asphalt will be characterized by sampling per NJDEP's procedure on "Guidance for Characterization of Concrete and Clean Material Certification for Recycling" for recycling purposes pursuant to N.J.A.C. 7:26A or for beneficial reuse onsite pursuant to N.J.A.C. 7:26-1.7(g). Concrete determined to meet NJDEP reuse requirements, or which is granted a variance by NJDEP to meet reuse requirements, may be reused onsite as backfill in excavations or placed under the cap. Asphalt

determined to meet NJDEP reuse requirements, or which is granted a variance by NJDEP to meet reuse requirements, may be used as sub-grade fill under new asphalt paved areas or placed under the cap. Concrete and asphalt that do not meet these NJDEP reuse or variance requirements will be disposed of offsite.

**FINAL DCB 016 – SITE 163 RESTORATION**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6 Jersey City, NJ** | **DCB No: 016; DCB Type: Minor(a)** |
| | **Effective Date: 12/01/14** |
| **Project Location: SA-6 NORTH and SOUTH** | **Associated RFI:** |
| **Title: Site 163 Backfill Protection** | ☐Yes, RFI No. ____ ☑ None |
| | **Project No.: 3480130377** |
| **Contractor (Subcontractor): ENTACT** | |

**Description of Change/Modification:**

The Southern limits of the Site 163 Chromium remediation extend close to the existing bulkhead. The bulkhead is in a dilapidated condition and has deteriorated subsequent to design of the remedy. During implementation of the remedy the condition of the bulkhead was visually assessed. As a result of this assessment it was determined that it was necessary to add additional protection to the backfill placed in Site 163 pending installation of the permanent replacement bulkhead. It was necessary to implement the restoration of the site rapidly after excavation to avoid the potential for inundation under high tides.

The design was modified in the field to include placement of geotextile fabrics and a sloped rip-rap facing to provide additional protection to the backfill.

The bulkhead condition is considered to be dynamic. It is recommended that this section of the bulkhead continue to be monitored pending replacement of the bulkhead.

Field Sketches were prepared to convey the general concepts and the final detailing was field engineered. Photos of the finished stabilized outer face are attached.


| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:** Condition of bulkhead deteriorated between design and implementation. |
| | **Attachments:** ☑ Yes ☐ No |
| | **Cost Implication:** ☑ Yes ☐ No<br>**>$50k** ☐ Yes ☑ No<br>**Schedule Implication** ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual: Samuel G. Shallard** **Discipline:** | **Initial:**  **Date:** 12/17 |
| **(Name / Signature):** Samuel G. Shallard | **Does DCB Result in CCO?** ☑ Yes (b)☐ No<br>**Date: 12/03/14** |

**Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec**

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.


JOB NO. _____ SHEET _____ OF _____
PHASE _____ TASK _____
JOB NAME Site 163 Restoration
BY SDS DATE 11/12/14
CHECKED BY _____ DATE _____

amec
American Metro Center 200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
+1 (609) 689-2829 Fax +1 (609) 689-2838




JOB NO. _____ SHEET _____ OF _____
PHASE _____ TASK _____
JOB NAME Site 163 Restoration
BY SGS DATE 11/12/14
CHECKED BY _____ DATE _____


amec
American Metro Center 200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
+1 (609) 689-2829 Fax +1 (609) 689-2838




(A) TYPICAL SECTION OPEN to COVE




(B) TYPICAL SECTION EAST END




(C)


DEERE
11.18.2014 08:15


DEERE
11.18.2014 10:36


11.19.2014 10:39


DEERE
11.19.2014 12:55


11.21.2014 11:37

**FINAL DCB 017 – SA-6 NORTH AREA 1N HISTORIC FILL**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 017 Minor (a)<br>Effective Date: |
| Project Location: SA-6 NORTH, SA6-SOUTH | Associated RFI: |
| Title: SA-6N Area 1N 2 ft. Cut Historic Fill | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

The SA-6 North Remedial Action Work Plan, SA-6 100% Remedial Design Report, and the SA-6 North Consent Decree provides for the removal of the upper 2 ft., of historic fill from the SA-6 North Open Space Area. It is recognized that the original surface grade fluctuated significantly on SA-6N. For practical excavation control a more uniform excavation surface has been developed. That surface is based on a 2 ft. nominal cut +/- 1 ft. The areas selected for cut will be areas previously identified as historic fill with hexavalent chromium concentration of <20 mg/kg.

To increase capacity for movement of 20-240 mg/kg chromium impacted soils from SA-6 South to SA-6 North approximately 10,000 CY of historic fill will be excavated from SA-6 North. The final quantity may be adjusted based on survey quantities of impacted soils compacted and stockpiled in SA-6 South.

The excavation will be conducted to the lines and grades shown on Drawing CN XXX attached.

The bottom of excavation will be surveyed by a registered land surveyor.

Contractor shall stockpile the excavated material in designated location(s) mutually agreeable to Honeywell and Amec Foster Wheeler. The excavated materials will be sampled by Amec Foster Wheeler to determine the final disposition according to Section 2.2.4 of the Soil Management Plan (copy of section attached), as summarized as follows:

- Excavated materials that are confirmed <20 mg/kg for hexavalent chromium will be designated for reuse as backfill in excavations with the SA-6 North or SA-6 South Development Areas in accordance with the placement and compaction requirements of the Earthwork specifications (Section 02315) or may be placed above the cap but below the two feet of clean fill required by paragraph 56(c) of the SA-6 North Consent Decree.
- Excavated materials that are confirmed >20 mg/kg for hexavalent chromium will be designated for placement within the SA-6 North or SA-6 South Open Space Areas to be later covered with the cap.

The contractor will be notified by Amec Foster Wheeler as to the final disposition of the stockpiled excavated material.


| Reason for Change/Modification: | Explanation or Reason: Increase impacted soil capacity under the SA-6N Open Space cap. |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: |


| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |

| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No |
|---|---|
| Samuel G Shallard | Date: 3/20/15 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. CONTOURS SHOWN HEREON REPRESENT THE PROPOSED BOTTOM OF EXCAVATION TO REMOVE APPROXIMATELY 2 FEET OF HISTORIC FILL FROM SURCHARGE AREA 1N.
2. EXCAVATION OF HISTORICAL FILL WILL BEGIN UPON APPROVED REMOVAL OF ALL SURCHARGE MATERIAL AND COMPLETION OF A PRE-EXCAVATION SURVEY BY A REGISTERED LAND SURVEYOR.
3. BOTTOM OF EXCAVATION CONTOURS MAY BE ADJUSTED BASED ON PRE-EXCAVATION SURVEY AND VERIFICATION OF ACTUAL SURCHARGE SETTLEMENT.
4. EXCAVATED HISTORIC FILL MATERIAL WILL BE STOCKPILED IN AN AREA DESIGNATED BY AMEC PERSONNEL FOR UTILIZATION DURING FUTURE DEVEOPMENT OR SAMPLED IN ACCORDANCE WITH THE SOIL MANAGEMENT PLAN TO DETERMINE FINAL DISPOSITION.

0 15 30 60
SCALE IN FEET

FILE NAME: C:\Dorsovri\SA-6 North\2013 Excavation Surfaces\Area 1N Historic Fill Removal\Area 1N Historic Fill Removal.dwg PLOT DATE: Thu, 19 Mar 2015 PLOT TIME: 3:46 PM

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | TDD | TDD | SGS | SGS | | |

REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE, REPORTS, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07960

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
SURCHARGE AREA 1N
HISTORIC FILL REMOVAL
GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 113
Hamilton, NJ 08619
(609) 585 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | 2/26/15 |
| PROJ | 3480-13-0377 |
| DWG | CN-101 |
| SHEET | 1 OF |

**FINAL DCB 018 – SA-6S SITE 163 DCB FOR CONCRETE**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB Type: Minor (a)<br>Effective Date: 12/23/2014 |
| Project Location: SA-6 NORTH, SA6-SOUTH | Associated RFI: |
| Title: Site 163 Deferred Areas | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

When conducting the Site 163 shallow excavation remedy along the cove, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. These locations were inspected by the Amec engineer and it was determined that removal could be detrimental to the integrity of the bulkhead.

The location and description of the three isolated and small Deferred Areas are shown on the attached drawing.


The total volume of the materials left in place is estimated to be less than 35 cubic yards.

As noted the material left in place was concrete. There was no visible sign of the concrete being "chromium impacted".

The remediation of this de minimis material will be completed along with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed.

| | |
|---|---|
| Reason for Change/Modification:<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Modified due to field conditions.<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: |
| Honeywell (AP) Review:<br>Individual Discipline | Initial [signature] Date 12/20/16 |
| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




SITE 163 DEFERRED EXCAVATION AREA 1:

REMOVAL OF EXISTING CONCRETE MAY IMPACT BULKHEAD INTEGRITY

DESIGN EXCAVATION BOTTOM = 5.20 FT (NGVD 29)

PROJECTED REMOVAL VOLUME = 10 CY

SITE 163 DEFERRED EXCAVATION AREA 2:

REMOVAL OF EXISTING STEEL VAULT FILLED WITH SAND MAY IMPACT BULKHEAD INTEGRITY

DESIGN EXCAVATION BOTTOM = 3.60 FT (NGVD 29)

PROJECTED REMOVAL VOLUME = 5 CY

SITE 163 DEFERRED EXCAVATION AREA 3:

REMOVAL OF EXISTING SOIL AND CONCRETE MAY IMPACT BULKHEAD INTEGRITY

DESIGN EXCAVATION BOTTOM = 5.60 FT (NGVD 29)

PROJECTED REMOVAL VOLUME = 20 CY

0 10 20 40
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | REVISION | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| DSGN | TDD | | RJR | TDD | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
CONSTRUCTION DRAWINGS

SITE 163
DEFERRED EXCAVATION AREAS

amec foster wheeler
Environment & Infrastructure, Inc.
200 Horizon Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 588-2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 01/21/15 |
| PROJ | 3480-10-0027 |
| DWG | 001 |
| SHEET | 1 OF 1 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 Deferment Areas\Figure 1 Site 163 Deferment Areas.dwg PLOT DATE: Wed, 21 Jan 2015 PLOT TIME: 11:46 AM

**FINAL DCB 021 – SURCHARGE IN AREA**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 021 Minor (a)<br>Effective Date: 3/4/15 |
| Project Location: SA-6 SOUTH | Associated RFI: |
| Title: 3S Surcharge Pile Geometry on East End | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

Description of Change/Modification:


Reason for deferral:

The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. See attached figure. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason.<br>Avoids placement of fill outside of the protective limits of the Barrier Wall. |
| | Attachments: ☑ Yes ☐ No |
| | Cost Implication: ☐Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected:<br>Changes the limit of surcharge fill however no specification of drawing change is considered to be necessary. |

| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |
| (Name / Signature): Samuel Shallard | | Does DCB Result in CCO? Date: 3/25/15 | ☐ Yes Yes (b) ☑ No |
| Distribution: | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARDS ROUTE 440.
4. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-6 | 684538 | 602919 |
| FS-7 | 684638 | 602751 |
| HS-16 | 684678 | 602808 |
| HS-17 | 684488 | 603027 |
| HS-18 | 684333 | 603198 |
| HS-19 | 684211 | 603276 |
| HS-20 | 684542 | 602775 |
| HS-21 | 684409 | 602931 |
| HS-22 | 684263 | 603093 |
| SP-8 | 684728 | 602761 |
| VRC-7 | 684643 | 602742 |

| | |
|---|---|
| VI-2 | INCLINOMETER LOCATION |
| FS-1 | SETTLEMENT MONITORING POINT FULL - SET UP |
| HS-1 | SETTLEMENT MONITORING POINT HALF - SET UP |
| SP-12 | SETTLEMENT MONITORING PLATFORM |
| RP | APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7) |
| VRC1 | VIBRATING WIRE PIEZOMETER IN STRATUM RC |

Attachment A

DCB 021 Eliminate Surcharge Area 3S Deferred Area

0 20 40 80
SCALE IN FEET


Prepared/Date: RJR 12/16/13
Checked/Date: AE 12/16/13

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | INSTRUMENTATION LOCATION PLAN 3S<br>Figure H-1 |

Z:\Projects\HONEYWELL\JERSEY CITY\Civil Design-SA6-CSY\CAD\SA6SY\Figure - Surcharge Area3 Instrumentation Plan.dwg Mon, 16 Dec 2013 - 9:54am roylor/taylor

JOB NO. _____ SHEET 1 OF 1
PHASE _____ TASK DCB
JOB NAME Modified 3S Surcharge
BY Ari Eslamineja DATE 3/25/15
CHECKED BY _____ DATE _____

amec
American Metro Center 200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
+1 (609) 689-2829 Fax +1 (609) 689-2838




Attachment B

DCB 021 Area 3S Eliminate Surcharge Deferred Area

**FINAL DCB 026.1 – CGWS DELETE PUMPS AND CONTROLS**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No 026.1: Minor (a) |
| | Effective Date: 05/19/2015 |
| Project Location: SA-6 | Associated RFI: |
| Title: Contingent GW System Delete Pumps & Controls | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB 026.1 serves to provide notice to Entact that specific components related to the Contingent GW system are being removed from the scope. Associated drawing revisions and supplemental detail will be provided in DCB 026.2.

Supply and installation of items listed below will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6N and 6S. These changes impact the three Groundwater extraction Pump Stations and associated electrical and instrumentation wiring.

Revised Contingent Groundwater drawings will be issued under DCB 026.2

- DWG C-310 Detail CC
  - Submersible Grinder Pump Model HPGR200 and associated electrical wiring.
  - Level switches, level alarm, Pump Power Control Panel and associated electrical and instrumentation cable.
  - 1.5 inch flex discharge hose.
- DWG C-204. Flow Meter and Flow Meter Structure as detailed on DWG 306. Delete in its entirety including all associated instrument cable and conduit.

Contingent GW force mains, electrical and instrument conduit will be installed as shown with pull string/wire to permit installation of electrical and instrumentation wire by others.

Please Note that the above Geomembrane pump station including all pumps, wiring and controls will be installed as shown.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>√ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason:<br>Attachments: ☐ Yes √ No<br>Cost Implication: √ Yes ☐ No<br>>$50k √ Yes ☐ No<br>Schedule Implication ☐ Yes √ No |
| Additional Comments: | Design Documents Affected:<br>C-204,C-310, E-301, E-302<br>CN-201,CN-301,CN-302 CN-305<br>EN-301, EN-302 |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| (Name / Signature):<br>Samuel Shallard | | | Does DCB Result in CCO? ☐ Yes (b) ☐ No<br>Date: May 19, 2015 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**FINAL DCB 027 – ELIMINATE UTILITY CORRIDOR**

Honeywell RES

Honeywell.com


DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 27 **DCB Type:** Major (a)<br>**Effective Date:** 6/15/15 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Eliminate Utility Corridor by Route 440 | ☐ Yes, RFI Nos. ☑ None |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor):** ENTACT | |

Bayfront Redevelopment Civil Designer has eliminated one utility corridor along the eastern portion of SA-6 South (water main and sewer line were relocated to another utility corridor). This DCB provides the associated adjustment in the Geomembrane Subgrade design. In addition, it was identified that minor changes in the Bayfront final grades of up to 0.25 ft may be made in the landscaped areas (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Final Grade surface has been verified to meet the minimum and average requirements of the SA-6 South Consent Decree and the 100% Design.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See additional comments<br>**Attachments:** ☑ Yes ☐ No<br>Drawing C-122<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** CHA revisions to the Development utilities resulted in the relocation of a firewater and sanitary sewer line near Route 440. The relocation eliminated the necessity for a utility corridor. Eliminating the corridor from the subgrade simplifies the geomembrane installation, eliminates two penetrations of the SA-7 SCB Wall, and reduces the extent of submerged barrier wall to geomembrane connection.<br>Final and Subgrade surfaces have been prepared for use with the Machine Control. A Construction Control Grid has also been established for the purpose of documenting compliance with the 100% Design. | **Design Documents Affected:**<br>Drawing C-122 |
| **Honeywell (AP) Review:** | |
| **Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 12/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 05/29/15 | ELIMINATE UTILITY CORRIDOR | TDD | SGS | |
| 1 | 02/24/15 | DCB 007.5 | TDD | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | TDD | RJR | TDD | SHM | |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GEOMEMBRANE GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 588 - 2629
http://www.amecfw.com/usa/northeast/default.aspx

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-122 |
| SHEET | 27 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR27-C-122 Geomembrane Grading Plan.dwg PLOT DATE: Mon, 01 Jun 2015 PLOT TIME: 12:21 PM

**FINAL DCB 028 – SCB WALL CONNECTION**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 28 **DCB Type:** Minor (a)<br>**Effective Date:** 5/29/15 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Revised Gas Venting System and Cap Details | ☑ Yes, RFI Nos. 38, 42, 45 ☐ None |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor):** ENTACT | |

This DCB was prepared in response to RFIs related to the cap termination details beyond the SCB/VHB wall, GCL to SCB/sheetpile barriers and Geofoam Block locations above the liner.


These clarifications have been made by modifying the Cap Details.


The original drawing sheets will be voided and replaced by the following revised sheets:

- C-121 – Gas Venting System and Details, Rev. 3 (5/29/15)
- C-301 – Cap Details, Rev. 3 (5/29/15)
- C-309 – Miscellaneous Details, Rev. 3 (5/27/15)

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:** Design clarification<br>**Attachments:** ☑ Yes ☐ No<br>C-121, C-301 and C-309<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | Design Documents Affected: |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 6/12/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





## GEOFOAM BLOCK SUMMARY

| NUMBER | LENGTH |
|---|---|
| 1 | 8' |
| 2 | 8' |
| 3 | 32' |
| 4 | 8' |
| 5 | 32' |
| 6 | 16' |
| 7 | 8' |
| 8 | 8' |
| 9 | 8' |
| 10 | 32' |
| 11 | 32' |
| 12 | 8' |
| 13 | 8' |

GEOFOAM BLOCKS EPS 19 4' WIDE x 1' THICK LENGTH VARIES

## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. WHERE BLOCKS ARE PLACED BELOW THE WATER TABLE, MEASURES WILL BE IMPLEMENTED TO CONTROL GROUNDWATER LEVELS AND FILL PLACEMENT SO THAT BLOCKS DO NOT FLOAT.
4. GEOFOAM BLOCKS ARE DEPICTED ON THIS DRAWING FOR PLAN LOCATION. BLOCKS WILL BE PLACED ABOVE THE LLDPE.
5. THE CLASS A GEOSYNTHETIC WHICH LAPS OVER THE SCB AND SHEETPILE BARRIER WALLS IS DESIGNED TO PROTECT THE LLDPE FROM PUNCTURING FROM THE STRUCTURAL WALL. THE 15 FT. DIMENSION WAS SELECTED TO PROVIDE FOR DEPLOYMENT OF A SINGLE ROLL WIDTH. GCL AREAS ARE MINIMUMS. IF THE CONTRACTOR WISHES TO USE FULL ROLL WIDTHS THE AREA OF GAS VENT OR CLASS A GEOTEXTILE MAY BE REDUCED ACCORDINGLY. PANEL DEPLOYMENT SHOULD BE REVIEWED WITH THE ENGINEER PRIOR TO DEPLOYMENT.




NOTE:
PERFORATED PIPE TO BE CORRUGATED SLOTTED PE PIPE.

GAS VENT DETAIL
NTS
AN
C-121 C-121

0 25 50 100
SCALE IN FEET

SAMUEL G. SHALLARD
N.J. PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 3 | 05/29/15 | CAP/EDGE DETAILS AND CORRIDORS | TDD | RJR | TDD | RJR | SHM |
| 2 | 05/20/15 | REVISED EDGE DETAILS | | | | RJR | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | | | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD | SHM |
| | | REVISION | | | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GAS VENTING SYSTEM AND DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2629
NJ Certificate of Authorization number 24GA28000300

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-121 |
| SHEET | 26 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR26-C-121 Gas Venting System and Details.dwg PLOT DATE: Mon, 01 Jun 2015 PLOT TIME: 12:19 PM

## CONSENT DECREE NOTES:


THE CAP SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE UNITED STATES DISTRICT COURT, DISTRICT OF NEW JERSEY, CONSENT DECREE REGARDING REMEDIATION AND REDEVELOPMENT OF STUDY AREA 6 NORTH AS FOLLOWS:

- ARTICLE III CHROMIUM REMEDIATION, SECTION A CHROMIUM REMEDY, SUBSECTION 56(a): EXCLUSIVE OF ROADWAYS, THE CAP SHALL BE OVERLAIN BY LAYERS OF CLEAN FILL, BACKFILL AND/OR OVERBURDEN WITH AN AVERAGE DEPTH OF AT LEAST THREE FEET AND A MINIMUM DEPTH OF AT LEAST TWO FEET PROVIDED THAT ANY LAYER THAT INCORPORATES OVERBURDEN SHALL BE BELOW AT LEAST TWO FEET OF CLEAN FILL. ONE FOOT OF CLEAN FILL, COVERED WITH BITUMINOUS BLACKTOP, SHALL BE SUFFICIENT COVER WHERE ROADS, WALKWAYS, OR OTHER PAVED SURFACES ARE LOCATED WITHIN THE AOC 1 OPEN SPACE AREA.
- ARTICLE III CHROMIUM REMEDIATION, SECTION B LONG-TERM MONITORING, MAINTENANCE, AND PROTECTION OF ENGINEERING AND INSTITUTIONAL CONTROLS, SUBSECTION 60(j)(v)(6): IF THE LOWEST ELEVATION FOR THE BEDDING FOR ANY UTILITY LINE, INCLUDING IRRIGATION OR SPRINKLER LINES, IS TWO FEET FROM THE TOP OF THE WARNING LAYER OF THE CAP, THE UTILITY LINE SHALL BE PLACED IN A UTILITY CORRIDOR.
- ARTICLE III SUBSECTION 56(a) "AND A DISTINCTIVE COLORED WARNING LAYER WITH MARKINGS IN ENGLISH AND SPANISH THAT WOULD DETER PENETRATION OF THE CAP IN THE EVENT THAT DIGGING OCCURRED IN THE VICINITY OF THE CAP.

### LANDSCAPING AREAS





FINAL GRADING TREE AND SHRUB PLANTING AREAS




FINAL GRADING GRASS AREAS

EXISTING MATERIAL OR CONSOLIDATED SUBGRADE FILL COMPACTED PER SUBGRADE PREPARATION SECTION OF SPECIFICATION 02315 "EARTHWORK".(TYP)





REMEDY CONDITION IN AREAS OF FUTURE ROADWAY


NOTES:

1. THE INITIAL 12 INCHES OF MATERIAL PLACED OVER THE GDL THE SHALL MEET THE SPECIFICATION FOR GEOCOMPOSITE DRAINAGE LAYER PROTECTIVE COVER SOIL.
2. THE CONSENT DECREE REQUIRES INSTALLATION OF A WARNING LAYER ABOVE THE GEOMEMBRANE LINER. (SEE CONSENT DECREE NOTES.) THIS REQUIREMENT MAY BE MET BY THE FOLLOWING.
   (A) SUPPLYING AND INSTALLING A GDL WHICH IS FABRICATED WITH TOP LAYER OF GEOTEXTILE THAT BOTH MEETS THE TECHNICAL SPECIFICATIONS FOR THE GDL AND THE CONSENT DECREE REQUIREMENTS FOR THE WARNING LAYER
   (B) INSTALLING A SEPARATE WARNING LAYER THAT MEETS THE REQUIREMENTS OF THE CONSENT DECREE.
3. STRUCTURAL FILL UNDER ROADWAYS SPECIFICATION 2315. NJDOT I-5 & I-8 COMPACTED TO 95% ASTM D698.
4. FOR FINAL DEVELOPMENT CUT OUT "ROADBOX" 18" DEEP AND REPLACE WITH 12" SUBGRADE FILL AND 6" PF FLEXIBLE PAVEMENT OR AS REQUIRED BY JERSEY CITY STANDARD ENGINEERING.

CAP AREA BUILD UP DETAIL (A) TYP C-301
NTS





TYPICAL HYDRAULIC BARRIER / SCB CONNECTION DETAIL (B) TYP C-301
NTS





NOTE:
THIS DETAIL APPLIES TO ALL MEMBRANE PENETRATIONS.

PIPE BOOT (C) TYP C-301
NTS





NOTE:
WELL EXTENSION CONCRETE SHALL BE PERFORMED IN ACCORDANCE WITH THE NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION, FIELD SAMPLING PROCEDURE MANUAL, APPENDIX 6.1, AUGUST 2005, EXCEPT DEPTH OF NEW CONCRETE PAD SHALL BE AS SHOWN.

PIEZOMETER/WELL EXTENSION DETAIL (E) TYP C-301
NTS




SECTION 1-1
NTS




TYPICAL UTILITY CORRIDOR HYDRAULIC BARRIER WALL CROSSING DETAIL (P) C-121 C-122 C-123 C-124 C-301
NTS

NOTE:
1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 05/29/15 | TDD | RJR | TDD | APVD |
| 2 | 05/13/15 | REVISED DETAILS | TDD | SGS | |
| 1 | 05/05/15 | REVISED DETAIL | TDD | SGS | |
| 0 | 06/07/13 | REVISED EDGE DETAILS | TDD | SGS | |
| | | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
CAP DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619 (609) 585-7229
NJ Certificate of Authorization Number 24GA28010500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-301 |
| SHEET | 37 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR37-C-301 Cap Details.dwg PLOT DATE: Mon, 01 Jun 2015 PLOT TIME: 12:25 PM




## TYPICAL EDGE DETAIL ABOVE GROUNDWATER TABLE

NTS


BO
C-121 | C-309




## PAVEMENT SECTION DETAIL

NTS

BA
C-108 | C-309
C-109
C-110





NOTE:
NO HISTORIC FILL SHALL BE PLACED ON SA-7

## EXCAVATION AREA

NTS


BJ
TYP | C-309




## PAVEMENT TRANSITION DETAIL

NTS


BL
TYP | C-309




## EXCAVATION EDGE RESTORATION DETAIL

NTS

BM
TYP | C-309




**BELOW GROUNDWATER**


**GCL AREAS STA 0+00 TO STA 3+22**

## TYPICAL EDGE DETAIL - LINER BELOW FINAL SCB ELEVATION

NTS

BN
C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

## TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G
TYP | C-309

NOTE:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 05/27/15 | TDD | RJR | TDD | SHM |
| 2 | 05/20/15 | REVISED DETAILS | | | |
| 1 | 05/05/15 | REVISED DETAILS | | | |
| 0 | 06/07/13 | REVISED DETAIL | | | |
| | | ISSUED FOR CONSTRUCTION | | | |
| | | REVISION | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
MISCELLANEOUS DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619 (609) 890-3939
N:\Certificate of Authorization Number\24GA27013900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-309 |
| SHEET | 45 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR45-C-309 Miscellanious Details.dwg PLOT DATE: Mon, 01 Jun 2015 PLOT TIME: 12:31 PM

**FINAL DCB 029 – PIEZOMETER LOCATIONS**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6 Jersey City, NJ** | **DCB No.: 29 DCB Type: Minor (a)** |
| | **Effective Date: 6/5/15** |
| **Project Location: SA-6 South** | **Associated RFI:** |
| **Title: SA-6 South Contingent GW Piezometer Locations** | ☐ Yes, RFI No. __ ☑ None (Request via e-mail) |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor): ENTACT** | |

**Description of Change/Modification:**

The general location of the paired piezometers was depicted in the Plan view of the Contingent system.

Specific coordinates were not included.

ENTACT has requested specific coordinates.

In preparing the coordinates Amec Foster Wheeler reviewed the locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the barrier wall.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐Design Revision<br>☐ Owner/Client Request<br>☑ Other (See Explanation) | **Explanation or Reason:** Adjustments to avoid conflicts with future development and to keep piezometers out of roadways. |
| | Attachments: ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: |
| Honeywell (AP) Review:<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial** **Date** |
| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: 6/15/15 |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

PZ16
N=684751.18
E=602508.94

PZ15
N=684735.78
E=602497.53

PZ14
N=684420.82
E=602907.51

PZ13
N=684391.71
E=602893.97

PZ12
N=684207.73
E=603276.91

PZ11
N=684200.51
E=603290.09

PZ19
685587.17
601500.99

PZ20
N=685584.00
E=601504.14

PZ18
N=685136.43
E=601988.86

PZ17
N=685121.22
E=601977.60

HORIZONTAL SCALE: 1" = 40'

0 20 40 80

SCALE IN FEET

Prepared/Date: RJR 07/09/15
Checked/Date: SGS 07/09/15

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019300

Piezometer Location
Project 3480-13-0377
Figure 1

Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design-SAs-2&3\CAD\SA6-North+South+RA_Excavation_Trench\GRSH-C-201_Cont_Offs_Trench.dwg Thu, 09 Jul 2015 - 8:47pm roger.ripster

**FINAL DCB 030 – SA-6 SOUTH FINAL GRADING**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.: DCB 030 Type:** Minor(a)<br>**Effective Date: 11/12/2015** |
| **Project Location:** SA-6<br>**Title:** Final Grade Revisions | **Associated RFI:**<br>☑ Yes, RFI Nos. 057 ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description. The Final Grades were revised to allow for a 0.25 increase in subgrade elevations eastern portions of SA-6 where subgrade had not been completed at the time (July 2015). The changes in subgrade were made in conjunction with the elimination of the utility corridor near the jug handle. The Subgrade changes were conveyed in DCB 027.**

**In parallel with the grade changes Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage.**

**Offsets from the final cover soil will be used in the Machine Control to complete cover soil grading as noted in RFI 057. This DCB impacts Final Grade Drawings C-125, C-126 and C-127 and the associated electronic files.**

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See description above<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Drawings C-125, C-126, C-127 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 11/19/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | TDD | DR RJR CHK TDD | APVD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THIE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 588 - 2629
http://www.amecfw.com/environment/

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-125 |
| SHEET | 30 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR30-C-125 Final Grade Plan.dwg PLOT DATE: Mon, 16 Nov 2015 PLOT TIME: 10:45 AM

SA-7

MATCH LINE SHEET C-127

MATCH LINE SHEET C-125

TYPICAL SA-7 EDGE DETAIL (H, C-126 | C-301)

TEMPORARY CONSTRUCTION FENCE (L, C-126 | C-302)

INSTALL TEMPORARY ROCK OUTLET FILTER (TYP) (AK, C-126 | C-307)

SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005) (AG, C-126 | C-307)

EXISTING SOIL CEMENT BENTONITE WALL, SEE PLAN AND PROFILE SHEETS S-204 THRU S-206

EXISTING SA-7 PERIMETER ROAD RELOCATE AS NECESSARY TO ACCOMMODATE FINAL GRADING AND EROSION CONTROL MEASURES

RELOCATED SA-7 PAVED PERIMETER ROAD

TYPICAL VEGETATED SWALE (Q, C-126 | C-303)

HYDRAULIC BARRIER, SEE PLAN AND PROFILE SHEETS S-201 THRU S-203

SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005) (AG, C-126 | C-307)

TEMPORARY CONSTRUCTION TRAILERS

CHAINLINK FENCE ON PRECAST CONCRETE BARRIER (TYP) (M, C-126 | C-302)

INSTALL 186 LF 12" HDPE @ 0.5%

MATERIAL STORAGE AREA

KELLOGG STREET

DROYERS COVE

CHAIN LINK FENCE WITH DOUBLE GATE

STABILIZED CONSTRUCTION ACCESS (J, C-126 | C-302; AH, C-126 | C-307)

APPROXIMATE LIMIT OF DISTURBANCE (TYP) (SEE NOTE EXC7 ON SHEET G-004)

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 11/16/15 | TDD | SGS | SHM | SHM |
| 0 | 06/07/13 | TDD | SHM | APVD | |
| | REVISION | | BY | | |

DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25'
ISSUED FOR CONSTRUCTION

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
REMEDIATION FINAL GRADING, DRAINAGE, AND EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
2790 Whitehorse-Hamilton Square, Suite 113
Hamilton, NJ, 08619, (609) 888-2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-126 |
| SHEET | 31 OF 66 |




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |

TDD RJR TDD

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SHM

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.
THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATEN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 889 - 2629
NJ Certificate of Authorization Number 24GA28019500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-127 |
| SHEET | 32 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR32-C-127 Final Grade Plan.dwg PLOT DATE: Mon, 16 Nov 2015 PLOT TIME: 10:13 AM

**FINAL DCB 030.1 – SA-6 SOUTH FINAL GRADE**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 030.1 **DCB Type:** Minor(a)<br>**Effective Date:** 4/15/16 |
| **Project Location:** SA-6 South<br>**Title:** Final Grade Revisions | **Associated RFI:**<br>☐ Yes: ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** DCB 030 provided for revision to the Final Grades to allow for a 0.25 foot increase in subgrade elevations in the eastern portions of SA-6S Open Space AOC.


DCB 030.1 relates to the Final Grades in the "Development AOC" south of the Open Space AOC. Both the Open Space AOC and the Development AOC grading is shown on the Final Grade Drawings C-125, C-126 and C-127.


The associated electronic files for the grading will be transmitted as part of this DCB. The Development Plan grading is shown at 1 ft. contours. Due to the relatively "flat" final grades,p 1 ft. contours as shown in the hard copy do not provide details on break points. The electronic files provided as part of this DCB do provide detailed information on the grading. Therefore the electronic files will be used for grading.

The Final Cover Soil types are shown on the Restoration Plan C-128. Sheet C 309 Civil Details has been updated to reflect the use of Skaps 121 as the demarcation layer.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See description above |
| | **Attachments:** ☑ Yes ☐ No<br>Drawings C-125, C-126, C-127, C-128, C-309 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Drawings C-125, C-126, C-127, C-128, C-309 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 4/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.


RELOCATED SA-7 PAVED PERIMETER ROAD
H C-125 C-301
TYPICAL SA-7 EDGE DETAIL
AK C-125 C-307
INSTALL TEMPORARY ROCK OUTLET FILTER (TYP)
EXISTING SA-7 PAVED PERIMETER ROAD RELOCATE AS NECESSARY TO ACCOMMODATE FINAL GRADING AND EROSION CONTROL MEASURES
EXISTING SOIL CEMENT BENTONITE WALL (SEE PLAN AND PROFILE SHEETS S-204 THRU S-206)
INLET 'B' TC 9.54 GR 9.01 INV 5.26(18"RCP-N) INV 4.91(18"RCP-S)
INLET 'B' TC 8.33 GR 7.84 INV 6.29(NW) INV 5.89(SE)
INLET 'B' TC 8.48 GR 8.98 INV 4.66(N) INV 4.56(S)
INLET FILTER (TYP) A2 C-125 C-307
HYDRAULIC BARRIER (SEE PLAN AND PROFILE SHEETS S-201 THRU S-203)
SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005) AG C-125 C-307
CHAINLINK FENCE ON PRECAST CONCRETE BARRIER (TYP) M C-125 C-302
APPROXIMATE LIMIT OF DISTURBANCE (TYP) (SEE NOTE EXC7 ON SHEET G-004)
MANHOLE RIM 10.17 INV. 3.70(8"-N,E,& W) INV. 3.67(S) FILLED W/DEBRIS UNABLE TO DETERMINE PIPE TYPE
TERMINUS NOT FOUND (TYP.)
MATCH LINE SHEET C-126
KELLOGG STREET
(80' WIDE R.O.W.)
NEW JERSEY STATE HIGHWAY ROUTE 440
POLE #68605JC
POLE #71494JC
POLE #E68604JC
POLE #67229JC
POLE #67226
POLE #72504JC
POLE #69477 W/ LIGHT
POLE #71105JC
CB 8.72
CB 8.60
CB 8.67
CB 7.93
CB 7.79
CB 15.48
CB 15.05
CB 11.83
CB 11.62
CB 10.14
CB 10.24
CB 8.70
CB 8.59
CB 8.64
CB 8.85
CB 9.53
CB 9.78
CB 10.34
CB 10.80
CB 11.17
CB 8.97
CB 9.08
CB 9.64
CB 10.24
CB 9.50
CB 8.52
CB 8.88
CB 9.22
CB 8.60
CB 9.69
CB 9.19
CB 8.23
CB 8.52
CB 8.16
CB 10.74
CB 10.14
CB 7.69
CB 8.31
CB 8.52
CB 8.48
CB 9.09
CB 9.28
CB 8.95
CB 9.08
CB 8.97
CB 9.52
CB 9.54
CB 9.33
CB 9.25
CB 10.24
CB 10.57
CB 11.03
CB 10.69
CB 10.52
CB 9.87
CB 11.18
CB 11.46
CB 11.48
CB 10.59
CB 10.54
CB 9.76
CB 10.03
CB 10.66
CB 11.20
CB 11.37
CB 10.88
CB 11.31
CB 10.28
CB 10.05
CB 9.98
CB 10.17
CB 9.70
CB 10.37
CB 9.78
CB 9.95
CB 10.14
CB 11.37
CB 10.24
CB 9.33
CB 9.25
CB 9.54
CB 9.06
CB 9.08
CB 8.97
CB 9.52
CB 9.64
CB 10.24
CB 9.50
CB 10.17
CB 11.17
CB 9.78
CB 10.34
CB 10.80




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 2 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | TDD DR RJR | TDD | APVD |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER: 43507
SHM | BY | APVD

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS LOANED SUBJECT TO THE CONDITIONED AGREEMENT THAT IT SHALL NOT BE REPRODUCED, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


REMEDIATION FINAL GRADING, DRAINAGE, AND EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-126 |
| SHEET | 31 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR31-C-126 Final Grade Plan.dwg PLOT DATE: Mon, 18 Apr 2016 PLOT TIME: 12:02 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS | |
| 2 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |

TDD RJR TDD SHM

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-127 |
| SHEET | 32 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR32-C-127 Final Grade Plan.dwg PLOT DATE: Mon, 18 Apr 2016 PLOT TIME: 12:05 PM




NOTE:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND
3. EXISTING ASPHALTIC PAVEMENT AREAS TO BE FIELD INSPECTED BY LSRP DURING RESTORATION ACTIVITIES. FINAL HISTORIC FILL CAP IN THESE AREAS MAY INCLUDE CRACK FILLING OR INSTALLING A GRAVEL COVER SYSTEM.

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 2 | 05/06/15 | REVISED EDGE DETAIL | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | TDD | DR RJR CHK TDD APVD | BY | APVD |

SAMUEL G. SHALLARD
SHM LICENSE NUMBER 43507
NJ PROFESSIONAL ENGINEER

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IDEAS CONTAINED HEREIN ARE SUBJECT TO THE CONDITIONS SET FORTH IN THE AGREEMENT BETWEEN HONEYWELL AND AMEC. THE MATERIAL DESCRIBED THEREIN, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

RESTORATION PLAN


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-128 |
| SHEET | 33 OF 66 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND IS NOT TO BE REPRODUCED THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREIN, NOR THE USE OF

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR33-C-128 Surface Restoration Plan.dwg PLOT DATE: Mon, 18 Apr 2016 PLOT TIME: 12:17 PM





## TYPICAL EDGE DETAIL ABOVE GROUNDWATER TABLE

NTS — BO — C-121 | C-309




## PAVEMENT SECTION DETAIL


NTS — BA — C-108 | C-109 | C-110 | C-309




NOTE:
NO HISTORIC FILL SHALL BE PLACED ON SA-7


## EXCAVATION AREA

NTS — BJ — TYP | C-309





## HISTORIC FILL CAP PLANTER AREAS

BB — TYP | C-309





## PAVEMENT TRANSITION DETAIL

NTS — BL — TYP | C-309




## EXCAVATION EDGE RESTORATION DETAIL

NTS — BM — TYP | C-309





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 15+00

## TYPICAL EDGE DETAIL - LINER BELOW FINAL SCB ELEVATION

NTS — BN — C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

## TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS — G — TYP | C-309

NOTE:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

| NO. | DATE | REVISION | CHK | DR |
|---|---|---|---|---|
| 5 | 04/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 4 | 07/21/15 | REVISED DETAIL BN | RJR | SGS |
| 3 | 05/27/15 | REVISED DETAILS | TDD | SGS |
| 2 | 05/20/15 | REVISED DETAILS | RJR | SGS |
| 1 | 05/05/15 | REVISED DETAIL | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | | BY | APVD |
| | TDD | | TDD | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

MISCELLANEOUS DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-309 |
| SHEET | 45 OF 66 |

**FINAL DCB 030.2 – SA-6 SOUTH FINAL GRADING AND RESTORATION**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 030.2 **Type:** Minor(a)<br>**Effective Date:** September 2016 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Cap Final Grading and Development Area grading and Restoration | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** This DCB summarizes several field engineering directions provided to Entact. This DCB includes several minor revisions to the final grading in the SA-6 South Chromium Remedy Cap and Development Areas. The changes have been made to improve surface water flows and enhance Sedimentation and Erosion Control Drawings C-125, C-126 and C-127 cover the area of both the Cap and the Development Area. The Restoration details previously shown on drawing C-128 have been added to these three drawings. C-128 has been deleted from the set.

- Installation of a crushed stone toe drain along SA-7 toe, and use of the former asphalt roadway to conduct stormwater to the Hackensack River, in lieu of the "in-slope" parabolic swale shown in the IFC design. The drain is located where the toe of slope temporarily terminates in SA-7 pending raising SA-7 to the Bayfront Development grades. The toe drain is considered to be more resilient than the original swale design and will provide equal or better sedimentation and erosion control.
- Adding topsoil over the eastern 300 ft. of the cap along SA-7/SA-6S boundary to provide for a gradual transition from the SA-7 paved road to the SA-6S Final Grades.
- Extent of demarcation geotextile, crushed stone, and DGA placed over the Development Area to meet covering of Historic Fill regulations. The restoration grades were modified to accommodate placement of gravel over foundations and pavement in a number of areas that were not included in the IFC restoration drawing.
- Installation of Erosion Control mat on the steep edge slopes on the north and south sides of SA-6S. The precise limits of mat will be determined in the field based on observed performance.
- Installation of supplement diversion berms to direct water through the culverts under the temporary roads. The location and size of the berms shown on the drawings may be modified in the field based on observation of the performance in storm events
- Installation/restoration of stone check dams and diversion dams near the surface water outfall to the Hackensack River on SA-7. The precise location and dimension of the check dams will be field engineered based on observed flow during storm events.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>Documents minor changes in grading and improved stormwater control.<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>C-125, C-126, C-127.<br>C-128 deleted. |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 12/01/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |




NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002
3. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | TDD | | RJR | TDD | SHM | SHM |
| 3 | 11/29/16 | DCB 030.2 | | | | TDD | SGS |
| 2 | 4/15/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | | | | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | | | | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 889 - 2829
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-125 |
| SHEET | 30 OF 66 |




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| DSGN | TDD | DR RJR | TDD | SHM |
| 3 | 11/29/16 | DCB 030.2 | TDD | SGS |
| 2 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND EROSION SEDIMENT CONTROL PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-126 |
| SHEET | 31 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR31-C-126 Final Grade Plan.dwg PLOT DATE: Thu, 01 Dec 2016 PLOT TIME: 9:11 AM




NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002
3. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 4 | 11/29/16 | TDD | | RJR | TDD |
| 3 | 4/18/16 | DCB 030.2 | | | |
| 2 | 11/16/15 | DCB 30.1 - REVISED GRADING AND RESTORATION | | | |
| 1 | 10/11/13 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | | | |
| 0 | 06/07/13 | MODIFIED BARRIER WALL ALIGNMENT | | | |
| | | ISSUED FOR CONSTRUCTION | | | |
| | | REVISION | BY | CHK | APVD |
| | | | TDD | SGS | SGS |
| | | | TDD | SGS | SHM |
| | | | RJR | SGS | |
| | | | TDD | SHM | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-127 |
| SHEET | 32 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR32-C-127 Final Grade Plan.dwg PLOT DATE: Thu, 01 Dec 2016 PLOT TIME: 9:15 AM

**FINAL DCB 032 – SA-6 SOUTH IN-SITU**

# DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB Type:** Major (a)<br>**Effective Date:** 6/18/15 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** SA-6 South, Site 163 In-situ Injections | ☐ Yes, RFI No. ___ ☑ None |
| | **Project No.:** 3480150438.5710.571001 |
| **Contractor (Subcontractor):** ERFS | |

Amec Foster Wheeler and ERFS performed in-situ injections of calcium polysulfide (CAPS) at SA-6 South, Site 163 in July & August 2014. 6-month performance assessment soil samples were collected and analytical results indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI). Honeywell will implement additional CAPS injections at several of the areas that remain >20 m/kg for Cr(VI). See attached memorandum, figures, and Table 1 prepared by Amec Foster Wheeler. While the specific scope of this next field phase is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved *Work Plan for In-Situ Treatment of Chromium Impacted Soil*, dated September 2012.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** Initial injections did not fully reduce soil sample concentrations of Cr(VI) to 20 m/kg. |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** *Work Plan for In-Situ Treatment of Chromium Impacted Soil* (Amec Work Plan), dated September 2012 |

| | | | |
|---|---|---|---|
| **Honeywell (AP) Review:** | | | |
| **Individual:** Dennis Nagg | **Discipline:** | **Initial:** | **Date:** |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☑ **Yes (b)** ☐ **No** |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# Memo

**Date:** June 18, 2015

**From:** Joe Clifford/Dennis Nagg/Ted Toskos – Amec Foster Wheeler

**To:** Bill Hague – Honeywell

**cc:** John Morris, Maria Kaouris, John Mojka – Honeywell
Jeremy Karpatkin, Michael Daneker – Arnold & Porter

**Subject:** Summary of Proposed Additional In-Situ Treatment Program for Hexavalent Chromium Impacted Soils, SA-6 South, Site 163

Amec Foster Wheeler E & I (Amec Foster Wheeler), on behalf of Honeywell, has prepared this memorandum to summarize the proposed additional injections of calcium polysulfide (CAPS) for in-situ treatment of hexavalent chromium (Cr(VI)) impacted soils at SA-6 South at Site 163, the former Posnak and Turkish location (the Site). Analytical results from the 6-month performance assessment soil sampling were summarized in a submittal to All Parties, dated June 10, 2015 and indicated that seven of the fifteen treatment areas at the Site are now <20 milligrams per kilogram (m/kg) for Cr(VI).

As indicated at the Special Master All-Hands meeting on May 19, 2015 and in the 6-month performance assessment soil sampling summary memo, Honeywell will implement additional CAPS injections at seven of the eight areas that remain >20 m/kg for Cr(VI). Although the Amec Work Plan specified that results of soil sampling conducted 3 years after the completion of injections would determine treatment efficacy, due to the planned start of the Bayfront Redevelopment project expected by the second quarter 2016, Honeywell has decided to implement the additional injections at this time to increase the probability of program success prior to the 3 year sampling event.

These seven areas which will have this additional treatment include Areas H, I, J, K, L, M, and N. **Figure 2D** through **Figure 2F** (revised from the September 5, 2014 summary of the completed CAPS injection program) are included and show proposed injection point (IP) and temporary well point (TWP) locations for the seven areas. Due to the proximity of Area F to the bulkhead along Droyers Cove and the potential for unpredictable subsurface preferential pathways in that area, additional injections will not be implemented in this area. Instead, Honeywell will defer

200 American Metro Blvd
Suite 113
Hamilton, NJ 08619
609-689-2829
amecfw.com

addressing this area until the bulkhead improvements are implemented as part of the Bayfront Redevelopment project.

### Scope of Proposed Additional In-Situ Injection Program

The attached **Table 1** indicates the injection volume estimates for the additional in-situ injection program for Areas H, I, J, K, L, M, & N. The calculation of injection volume estimates are generally similar to those for the original injection program with the following exceptions:

- The factor for the CAPS Stoichiometric Dosage Solution was increased from 2.5X to 5X; and
- The injection approach may be differentiated in treatment areas based on whether the areas lie north or south of the northern edge of the curbline of the new Kellogg Street proposed for the Bayfront Redevelopment.

The doubling of the CAPS Stoichiometric Dosage factor is recommended for these remaining areas for the following reasons:

- Initial treatment in these zones did not demonstrate the same efficacy as was observed in other Site 163 areas and SA-6 North Treatment areas 7 and 8
- The imminent timing pressures to complete implementation of remaining in-situ measures so as not to impact the Bayfront Redevelopment which is planned to start with the Kellogg Street properties.

As shown on **Figure 2D** through **Figure 2F,** the spacing between IPs may be reduced (increased number of IPSs) in treatment areas or portions of treatment areas that lie north of the new Kellogg Street curbline. This increased injection point density will potentially invoke a more robust dispersion of CAPS solution.

The proposed additional in-situ injection program for Areas H, I, J, K, L, M, & N as indicated on the attached **Figure 2D** through **Figure 2F** and **Table 1** is summarized as follows.

- Means and methods will generally follow the Amec Work Plan; ERFS' In-Situ Chemical Reduction Implementation Work Plan, dated September 2013; and ERFS Health and Safety Plan, dated June 2013 (Revised July 2014).
- Additional injections to occur in Areas H, I, J, K, L, M, & N from approximately 8 to 18 feet below grade.

- Injections in each area are to occur over a 6-foot vertical profile.
- A total of 4,100 gallons of 29% CAPS will be mixed with approximately 37,300 gallons of potable water to produce the CAPS solution.
- The 41,400 gallons of CAPS solution will be injected into approximately 86 injection locations.
- Areas surrounding injection locations will be monitored for evidence of daylighting.
- If daylighting occurs, the liquid will be contained at the daylighting site and be allowed to seep back into the ground.
- Injection activities will be adjusted as necessary to eliminate excessive daylighting.
- Thirty-four (34) 1-inch diameter PVC TWPs will be drilled and installed within and adjacent to the treatment areas.
- The following measurements will be taken and recorded in TWPs prior to the start of injections (baseline), during injections, and following completion of injections:
    - Depth to groundwater;
    - Groundwater quality parameters, including pH, oxidation/reduction potential (ORP), specific conductivity (SC), and total dissolved solids (TDS);
    - Hydrogen sulfide (H2S) and volatile organic compounds (VOCs) in the headspace of the PVC riser pipe; and
    - Groundwater color and/or odor.
- The breathing zones at storage, mixing, and injection areas will be monitored for hydrogen sulfide ($H_2S$).
- The breathing zones at drilling locations will be monitored for volatile organic compounds (VOCs) and $H_2S$.
- Honeywell will obtain a new Discharge to Groundwater – Permit By Rule from NJDEP for the injection activities.
- All as-built IP and TWP locations will be surveyed to determine their position.

### Interim Performance Assessment Soil Sampling and Reporting

Approximately six months after the completion of these additional injections in Areas H, I, J, K, L, M, and N (weather permitting), Honeywell will collect soil samples at generally the same

locations as those collected in April 2015 and generally using the same protocol. All of the 6-month performance assessment soil samples will be analyzed for the following:

- Total chromium;
- Hexavalent chromium;
- Sulfide;
- pH; and
- Oxidation Reduction Potential (ORP).

Upon receipt of final validated analytical results, the 6-month performance assessment soil sampling will be summarized in a memorandum and on tables and “chem-box” figures and will be transmitted to All Parties in a timely manner.

The Amec Work Plan also called for a performance assessment three years after completion of the injections. As has been previously discussed with the parties, Honeywell has advised it may seek to conduct the second performance assessment sooner than 3 years after completion of the Site 163 injection program, and in that case will provide a proposal to the parties for their review and comment.


**FIGURES**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT, (1) THE DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OF RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CAD\HONEYWELL\JERSEY CITY\SA 6 SOUTH\SITE 163\3480110298\in-situ\current drawings\3480110298-4100-RAP0-000F.dwg Wed, 10 Jun 2015 - 7:56am scott.rudisin Layout: 10-12

## LEGEND

- SHALLOW GROUNDWATER MONITORING WELL LOCATION
- 2nd INJECTION PROPOSED IN–SITU TEMPORARY MONITORING WELL POINT
- 2nd INJECTION PROPOSED IN–SITU INJECTION POINT
- A — IN–SITU TREATMENT OF IMPACTED SOIL (20–87 MG/KG HEX Cr) BELOW 3 FEET BGS (SUBJECT TO FINAL GRADE CONFIRMATION)
- SURFACE WATER (HACKENSACK RIVER)
- AREA EXCAVATED AS PART OF THE CHROMIUM REMEDY
- APPROXIMATE EDGE OF BULKHEAD/WATER LINE
- LIMITS OF DELINEATION TO 20 PPM HEXAVALENT CHROMIUM
- PROPERTY LINE
- NORTHERN EDGE OF BAYFRONT REDEVELOPMENT CURBLINE OF NEW KELLOGG STREET




| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480110298
*DRAWING:* 3480110298–4100–RAP0–000F

*PREPARED/DATE:* STR 08/13/12


*CHECKED/DATE:* DEN 08/13/12

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 2D**
2□d INJECTION PROPOSED IN-SITU TREATMENT AREAS - AS-BUILT INJECTION POINT & TEMPORARY WELL POINT LOCATIONS
10□ 12□DEPTH INTERVAL
SITE 163 CHROMIUM
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN ELEVATED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.

P:\CAD\MONEWELL\JERSEY CITY\SA 6 SOUTH\SITE 163\3480110298\in-situ\current drawings\3480110298-4100-RAP0-000F.dwg Wed, 10 Jun 2015 - Adam.scott.eadie Layout: 12-14




| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480110298
*DRAWING:* 3480110298-4100-RAP0-000F

*PREPARED/DATE:* STR 07/01/14


*CHECKED/DATE:* DEN 07/01/14

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 2E**
2nd INJECTION PROPOSED IN-SITU TREATMENT AREAS - AS-BUILT INJECTION POINT & TEMPORARY WELL POINT LOCATIONS
12-14 DEPTH INTERVAL
SITE 163 CHROMIUM
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT, (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND PROPRIETARY TO AMEC FOSTER WHEELER AND (2) THIS DOCUMENT MAY NOT BE DISCLOSED, REPRODUCED OR DISTRIBUTED TO ANY PERSON OR ENTITY (OTHER THAN THE CLIENT IN THE COURSE OF ITS BUSINESS) AND MAY NOT BE RELIED ON BY ANY PERSON OR ENTITY (OTHER THAN THE CLIENT FOR WHICH IT WAS PREPARED AND ITS AFFILIATES IN THE COURSE OF THEIR BUSINESS) WITHOUT THE PRIOR WRITTEN CONSENT OF AMEC FOSTER WHEELER. AMEC FOSTER WHEELER ACCEPTS NO RESPONSIBILITY OR LIABILITY FOR ANY USE OF OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IN THE CLIENT'S BUSINESS SECTOR AND FOR ANY PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OF OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY




| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

Amec Foster Wheeler PROJECT No. 3480110298
DRAWING: 3480110298-4100-RAP0-000F

| PREPARED/DATE: | CHECKED/DATE: |
|---|---|
| STR 07/01/14 | DEN 07/01/14 |

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 2F**
2nd INJECTION PROPOSED IN-SITU TREATMENT AREAS - AS-BUILT INJECTION POINT & TEMPORARY WELL POINT LOCATIONS
14- 16 DEPTH INTERVAL
SITE 163 CHROMIUM
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\CAD\WORKEWELL\JERSEY CITY\SA 6 SOUTH\SITE 163\3480110298\in-situ\current drawings\3480110298-4100-RAP0-000F.dwg Wed, 10 Jun 2015 - 8:06am scott.corbin Layout: 14-16

**TABLE 1**

**TABLE 1**
**INJECTION ESTIMATES**
**SA-6 SOUTH, SITE 163**

Honeywell Inc.
Jersey City, New Jersey

## SOUTH OF THE CURBLINE

| Treatment Area | Totals | H | I | J | K | L | M | N |
|---|---|---|---|---|---|---|---|---|
| **Depth Interval (ft bgs)** | | 10-12 | 10-12 | 12-14 | 12-14 | 12-14 | 14-16 | 14-16 |
| **Thickness (ft)** | | 2 | 2 | 2 | 2 | 2 | 2 | 2 |
| **Area ($ft^2$)** | | 562 | 472 | 464 | 622 | 1,461 | 581 | 200 |
| Area of injection, SF | 3,801 | 562 | 472 | 464 | 622 | 900 | 581 | 200 |
| Zone of Injection (feet below grade) | | 10-12 | 10-12 | 12-14 | 12-14 | 12-14 | 14-16 | 14-16 |
| Height of Injection (feet) | | 2 | 2 | 2 | 2 | 2 | 2 | 2 |
| Soil Volume for reagent addition (bcy) | | 42 | 35 | 34 | 46 | 67 | 43 | 15 |
| Soil Pore Volume (gallons at 30%) | 17,060 | 2522 | 2118 | 2083 | 2792 | 4039 | 2608 | 898 |
| Hex Cr Concentration, ppm | | 39.0 | 35.0 | 32.9 | 81.0 | 51.0 | 27.0 | 93.0 |
| Assumed Soil Density (tons/cy) | | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 |
| Weight of soil in treatment zone (lbs) | | 133,215 | 111,881 | 109,985 | 147,437 | 213,333 | 137,719 | 47,407 |
| Total mass load exceeding 20 ppm Hex Cr | 26 | 3 | 2 | 1 | 9 | 7 | 1 | 3.5 |
| CaSx Dose at 1X ==> 25.3 lbs of CsSx 29% solution per 1 lb of Cr (VI) **[x=5]** | | 25.3 | 25.3 | 25.3 | 25.3 | 25.3 | 25.3 | 25.3 |
| CaSx Stoichiometric Dosage @29% Solution | | 5.00 | 5.00 | 5.00 | 5.00 | 5.00 | 5.00 | 5.00 |
| CaSx Dose at 10X [at 1X ==> 25.3 lbs of CsSx 29% solution per 1 lb of Cr (VI)] | | 126.5 | 126.5 | 126.5 | 126.5 | 126.5 | 126.5 | 126.5 |
| CaSx (lbs) @29% Solution for total Hex Cr Mass at 2.5X | | 320 | 212 | 179 | 1,138 | 837 | 122 | 438 |
| CaSx 29% solution Density, lbs/gal | | 10.6 | 10.6 | 10.6 | 10.6 | 10.6 | 10.6 | 10.6 |
| CaSx (Gallons) @29% Solution for total Hex Cr Mass at 2.5X | | 30 | 20 | 17 | 107 | 79 | 12 | 41 |
| CaSx solution application volume (gallons at 25% volume exchange) | | 631 | 530 | 521 | 698 | 1,010 | 652 | 224 |
| Additional CaSx (Gallons) @29% Solution for 2-ft interval above and below | | 60 | 40 | 34 | 215 | 158 | 23 | 83 |
| Additional CaSx solution application volume (gallons at 25% volume exchange) for 2-ft interval above and below | | 1,261 | 1,059 | 1,041 | 1,396 | 2,020 | 1,304 | 449 |
| Total CaSx (Gallons) @29% Solution (from 2-ft above to 2-ft below zone) | | 91 | 60 | 51 | 322 | 237 | 35 | 124 |
| Total CaSx solution application volume (gallons at 25% volume exchange) from 2-ft above to 2-ft below zone | | 1,892 | 1,589 | 1,562 | 2,094 | 3,030 | 1,956 | 673 |
| Additional 10% CaSx (Gallons) @29% Solution safety factor | | 9 | 6 | 5 | 32 | 24 | 3 | 12 |
| Additional 10% CaSx solution application volume (gallons at 25% volume exchange) from 2-ft above to 2-ft below zone | | 189 | 159 | 156 | 209 | 303 | 196 | 67 |
| TOTAL CaSx (Gallons) @29% Solution (Calculated) | 1,011 | 100 | 66 | 56 | 354 | 260 | 38 | 136 |
| **TOTAL CaSx (Gallons) @29% Solution (Rounded up)** | 1,030 | **100** | **70** | **60** | **360** | **260** | **40** | **140** |
| **TOTAL CaSx solution application volume (gallons at 25% volume exchange)** | 14,075 | **2,081** | **1,748** | **1,718** | **2,303** | **3,333** | **2,151** | **741** |
| CaSx Solutiuon Injected Concentration | | 1.4% | 1.2% | 1.0% | 4.5% | 2.3% | 0.5% | 5.5% |
| Max # DP Injectors (depth = midpoint of treatment interval, 150 sf coverage/pt) | 29 | 4 | 3 | 3 | 4 | 10 | 4 | 1 |
| # of Injectors Rounded Up | **32** | **4** | **3** | **4** | **5** | **10** | **4** | **2** |

## NORTH OF THE CURBLINE

| Treatment Area | Totals | H | I | K | L-1 | L-2 | N |
|---|---|---|---|---|---|---|---|
| **Depth Interval (ft bgs)** | | 10-12 | 10-12 | 12-14 | 12-14 | 12-14 | 14-16 |
| **Thickness (ft)** | | 2 | 2 | 2 | 2 | 2 | 2 |
| **Area ($ft^2$)** | | 562 | 337 | 817 | 900 | 3,162 | 478 |
| Area of injection, SF | 6,256 | 562 | 337 | 817 | 900 | 3162 | 478 |
| Zone of Injection (feet below grade) | | 10-12 | 10-12 | 12-14 | 12-14 | 12-14 | 14-16 |
| Height of Injection (feet) | | 2 | 2 | 2 | 2 | 2 | 2 |
| Soil Volume for reagent addition (bcy) | | 42 | 25 | 61 | 67 | 234 | 35 |
| Soil Pore Volume (gallons at 30%) | 28,079 | 2522 | 1513 | 3667 | 4039 | 14192 | 2145 |
| Hex Cr Concentration, ppm | | 39.0 | 35.0 | 81.0 | 102.0 | 68.0 | 93.0 |
| Assumed Soil Density (tons/cy) | | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 |
| Weight of soil in treatment zone (lbs) | | 133,215 | 79,881 | 193,659 | 213,333 | 749,511 | 113,304 |
| Total mass load exceeding 20 ppm Hex Cr | 77 | 3 | 1 | 12 | 17 | 36 | 8.3 |
| CaSx Dose at 1X ==> 25.3 lbs of CsSx 29% solution per 1 lb of Cr (VI) **[x=5]** | | 25.3 | 25.3 | 25.3 | 25.3 | 25.3 | 25.3 |
| CaSx Stoichiometric Dosage @29% Solution | | 5.00 | 5.00 | 5.00 | 5.00 | 5.00 | 5.00 |
| CaSx Dose at 10X [at 1X ==> 25.3 lbs of CsSx 29% solution per 1 lb of Cr (VI)] | | 126.5 | 126.5 | 126.5 | 126.5 | 126.5 | 126.5 |
| CaSx (lbs) @29% Solution for total Hex Cr Mass at 2.5X | | 320 | 152 | 1,494 | 2,213 | 4,551 | 1,046 |
| CaSx 29% solution Density, lbs/gal | | 10.6 | 10.6 | 10.6 | 10.6 | 10.6 | 10.6 |
| CaSx (Gallons) @29% Solution for total Hex Cr Mass at 2.5X | | 30 | 14 | 141 | 209 | 429 | 99 |
| CaSx solution application volume (gallons at 25% volume exchange) | | 631 | 378 | 917 | 1,010 | 3,548 | 536 |
| Additional CaSx (Gallons) @29% Solution for 2-ft interval above and below | | 60 | 29 | 282 | 418 | 859 | 197 |
| Additional CaSx solution application volume (gallons at 25% volume exchange) for 2-ft interval above and below | | 1,261 | 756 | 1,833 | 2,020 | 7,096 | 1,073 |
| Total CaSx (Gallons) @29% Solution (from 2-ft above to 2-ft below zone) | | 91 | 43 | 423 | 626 | 1,288 | 296 |
| Total CaSx solution application volume (gallons at 25% volume exchange) from 2-ft above to 2-ft below zone | | 1,892 | 1,134 | 2,750 | 3,030 | 10,644 | 1,609 |
| Additional 10% CaSx (Gallons) @29% Solution safety factor | | 9 | 4 | 42 | 63 | 129 | 30 |
| Additional 10% CaSx solution application volume (gallons at 25% volume exchange) from 2-ft above to 2-ft below zone | | 189 | 113 | 275 | 303 | 1,064 | 161 |
| TOTAL CaSx (Gallons) @29% Solution (Calculated) | 3,044 | 100 | 47 | 465 | 689 | 1,417 | 326 |
| **TOTAL CaSx (Gallons) @29% Solution (Rounded up)** | 3,070 | **100** | **50** | **470** | **700** | **1,420** | **330** |
| **TOTAL CaSx solution application volume (gallons at 25% volume exchange)** | 23,165 | **2,081** | **1,248** | **3,025** | **3,333** | **11,708** | **1,770** |
| CaSx Solutiuon Injected Concentration | | 1.4% | 1.2% | 4.5% | 6.1% | 3.5% | 5.4% |
| Max # DP Injectors (depth = midpoint of treatment interval, 150 sf coverage/pt) | 42 | 4 | 2 | 5 | 6 | 21 | 3 |
| Add 25% more injection pts | 12 | 1 | 1 | 2 | 2 | 5 | 1 |
| **Total Injection Pts** | **54** | **5** | **3** | **7** | **8** | **26** | **4** |



Prepared By: DN 06/09/15
Checked By:

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 19 OF 25**

- **DCBs Applicable to SA-6 South Part 4**
  **(DCB 034-060)**

**FINAL DCB 034 – CONSTRUCTION CONTROL GRID**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 34 **DCB Type:** Minor (a) |
| | **Effective Date:** 6/15/15 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Survey Clarification | ☐ Yes, RFI Nos. ☐ None |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor):** ENTACT | |

Design Surface. The 100% Design CAD files defines the subgrade surface. The surface is developed in CAD as a Triangular Irregular Network (TIN). For construction control and verification of compliance with Cover thickness requirements in the Consent Decree and Open Space Design Standards the Construction Control Grid (as noted above) will be applied to the TIN.

Specification 01460 sets out the requirements for survey. In conducting a detailed review of the design of the subgrade, and methods of implementation including the use of GPS based machine control the following clarifications to the documentation requirements at defined in following sections.

- SECTION 1.04. C. The Contractor shall establish a grid system (Construction Control Grid) with a maximum spacing of 25 feet with additional grid points as required for grade breaks (toe, top of slopes) over the entire limits of Work. The grid system shall be established for the purpose of determining required excavation and fill thickness.

- SECTION 1.04 E. Vertical and horizontal control shall be sufficient to assure work is constructed within 0.1 foot of proposed fill thickness requirements (or proposed grades as indicated) and location.

- SECTION 1.05 F. Spot Elevations - Survey shall be constructed to provide an accuracy of 0.1 feet vertically. Ninety percent of all spot elevations placed on the maps shall have an accuracy of at least 0.1', and the remaining 10 percent shall not be in error by more than one-half (1/2) the contour interval (0.5').

- The slopes shall be visually inspected to verify that they are uniform (straight line) for top of slope to bottom of slope.

- The net result of these clarifications is an increase in the number of points on the Construction Control Grid.

The elevation at each 25 ft. grid node will be documented as the "Design Elevation". Where nodes fell on steep slopes the single node will be deleted and replaced with two points at the top of slope and bottom of slope. Points will also added to the Construction Control Grid along the boundaries of the cap and isolated supplemental points added at specific locations to provide supplemental information. Points falling in the 25 ft grid will be subject to the tolerances specified in SECTION 1.04 E. Break points added to replace Grid Points that fell on slopes and Boundary Points will be treated as Spot Elevations as defined in SECTION 1.05 F.

The Contractor (QC), Engineer (QA) and Surveyor (licensed surveyor) will all record elevations at the same locations.


Contractor Layout. The contractor will add points based on the TIN and utilize the contour plots produced from the TIN to aid in layout of the work as necessary.

Registered Survey Documentation. The registered surveyor will survey and record the elevations on the Construction Control Grid. This information will be used to certify that the subgrade has been built to the design elevations.

The Contractor (QC), Engineer (QA) and Surveyor (licensed surveyor) will all record elevations at the same locations.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>Clarification only. See "additional comments".<br><br>**Attachments:** ☑ Yes ☐ No<br><br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:**<br>The subgrade surface is very complex. The DCB clarifies how the 25 ft. Construction Control Grid and supplemental break points should be used to meet the design intent. | **Design Documents Affected:**<br>Add as an addendum to Spec 01460. |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 7/22/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




Prepared/Date: RJR 07/02/15
Checked/Date: TDD 07/02/15


**Honeywell**
101 COLUMBIA RD, BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013900

SA-6 SOUTH CONSTRUCTION CONTROL GRID
FIGURE 1 OF 2
Project 3480-13-0377
Figure 1.1

J:\Projects\HONEYWELL\JERSEY CITY\Cad Design - SA6 - 2301\DAD\SA6S_Xref\SA-6 South Construction Control Grid.dwg Thu, 02 Jul 2015 - 10:55am roger.rhoder




Prepared/Date: RJR 07/02/15
Checked/Date: TDD 07/02/15

**Honeywell**
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013400

SA-6 SOUTH CONSTRUCTION CONTROL GRID
FIGURE 2 OF 2
Project 3480-13-0377
Figure 1.2

Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design-SA6-C3D\CAD\SA6S\Xref\SA-6 South Construction Control Grid.dwg Thu, 02 Jul 2015 10:59pm ingler.rispler

# FINAL DCB 035 – GAS VENT SYSTEM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 35 **DCB Type:** Minor (a)<br>**Effective Date:** 7/16/15 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Revised Gas Vent System Alignment | ☑ Yes, RFI Nos. 50 & 51 ☐ None |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor):** ENTACT | |

**Description**

The alignment of the gas vent system piping and trench was modified in the west portion of the SA-6 South cap to establish smooth grades in the utility corridors and avoid contingent groundwater extraction system components.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 7/22/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**REQUEST FOR INFORMATION**

| GENERAL INFORMATION | |
|---|---|
| **Project Name: Honeywell SA-6** | **RFI No.: 50** |
| | **Date Information Required: ASAP** |
| **Project Location: Jersey City, NJ** | **Date Information Provided: 7/8/15** |
| **Site Owner: Honeywell** | **Project No.: 8140C** |
| **Client: AMEC** | **RFI Results in a Design Change Bulletin:** |
| **Contractor(*Subcontractor*): ENTACT** | ☐ Yes, DCB No. _____ ☒ No |

**REQUEST**

**Information Requested:**
ENTACT requests the elimination of gas vent pipe/trench within the utility corridors in locations shown (in red) on the attached drawing due to constructability issues.


| | | |
|---|---|---|
| **Relevant Design Documents:**<br>Honeywell SA6 100% Chromium Remedy Design Drawings C-121 | **Attachments:** Yes ☒ No ☐ | |
| **RFI Originator: Caroline Panico** | **Initial: CP** | **Date: 7/8/15** |

| RESPONSE | | |
|---|---|---|
| **RFI Received By:** | **Initial:** | **Date:** |
| **AMEC Response:** See Fig 1 gas vent slope detail. Detail to be used in steep slopes of utility corridors. The 8" pipe will remain continuous from east to west as depicted in the original design | | |
| **AMEC Review:** | | |
| **Individual** SC Shalland | **Discipline** EOR | **Initial** [signature] **Date** 7/16/15 |
| **Distribution:** | | |


JOB NO. _____ SHEET _____ OF _____
PHASE _____ TASK _____
JOB NAME SA-6 Gas Vent Slope
BY SCS DATE 7/16/15
CHECKED BY _____ DATE _____

amec
511 Congress Street Suite 200
Portland, ME 04101
+1 (207) 775-5401 Fax +1 (207) 772-4762

NTS.




Typical Section Utility Corridor




SECTION XX is typical detail as shown on GAS VENT DETAIL AN C-121

Wrap Gas Vent Pipe with min 1 layer of GDL or Class A Geotextile. Overlap wrap min 1/4 of pipe circumference

SEQUENCE,

1. Excavate trench on slope. Extra 6" on typical detail is not required but can be used
2. Wrap HDPE as noted
3. Backfill with sand or 3/8 quarry screenings
4. Install 2-3 ft wide strip of gas vent GDL over pipe on slope.
5. Place gas vent GDL over entire subgrade per design. In locations where GDL is required install GCL in lieu of gas vent

Fig 1

**REQUEST FOR INFORMATION**

| GENERAL INFORMATION | |
|---|---|
| **Project Name: Honeywell SA-6** | **RFI No.: 51** |
| | **Date Information Required: ASAP** |
| **Project Location: Jersey City, NJ** | **Date Information Provided: 7/16/15** |
| **Site Owner: Honeywell** | **Project No.: 8140C** |
| **Client: AMEC** | **RFI Results in a Design Change Bulletin:** |
| **Contractor(*Subcontractor*): ENTACT** | ☐ Yes, DCB No. _____ ☒ No |

**REQUEST**

**Information Requested:**
Attached is ENTACT's proposed re-alignment of the gas vent pipe/trench on the west side of the SA6 South cap.
ENTACT also requests the latest version of Drawing C-121 in AutoCAD.

| | | |
|---|---|---|
| **Relevant Design Documents:**<br>Honeywell SA6 100% Chromium Remedy Design Drawings C-121 | **Attachments:** Yes ☒ No ☐ | |
| **RFI Originator: Caroline Panico** | **Initial: CP** | **Date: 7/16/15** |

**RESPONSE**


| | | |
|---|---|---|
| **RFI Received By:** Eric Christodoulatos | **Initial:** EGC | **Date:** 7/16/15 |

**AMEC Response:**
Gas vent layout as shown in red is acceptable. In response to a separate verbal request today amec fw is issuing the C-121 linework associated with the GCL.

**AMEC Review:**

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| SC Shallard | EOR | | 7/16/15 |

**Distribution:**




Proposed Adjustment to Gas Venting Pipe Alignment

Design Gas Venting System Pipe Alignment

| REV | DATE | BY | CHK'D | APR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| | | | | | |

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

DRAWING NAME
PROPOSED GAS VENT PIPING ALIGNMENT

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ


**FINAL DCB 035.2 – GAS VENT SYSTEM – DETAIL AN**

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 035.2 **DCB Type:** Minor (a)<br>**Effective Date:8/18/15** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Gas Vent Goose Neck Assembly Detail AN | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** The Design detail assembly has been modified to reflect changes resulting from collaboration between Entact and AmecFW. | |
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:** See additional comments<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** The gas vent system was designed based on modeling by Dr. J Chanton and will be subject to performance monitoring upon cap completion. The assembly modification will allow for easier changes in size of elimination upon based on actual emissions. | **Design Documents Affected:** C-121, Detail AN |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 8/19/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





# NOTES:


1. PERFORATED PIPE TO BE CORRUGATED SLOTTED PE PIPE.
2. SPACERS MAY BE PREFABRICATED AS PART OF THE 4.5" DIA VENT PIPE.

## GAS VENT DETAIL

NTS

AN
C–121 C–121





## GEOFOAM BLOCK SUMMARY

| NUMBER | LENGTH |
|---|---|
| 1 | 8' |
| 2 | 8' |
| 3 | 32' |
| 4 | 8' |
| 5 | 32' |
| 6 | 16' |
| 7 | 8' |
| 8 | 8' |
| 9 | 8' |
| 10 | 32' |
| 11 | 32' |
| 12 | 8' |
| 13 | 8' |

GEOFOAM BLOCKS EPS 19 4' WIDE x 1' THICK LENGTH VARIES

## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. WHERE BLOCKS ARE PLACED BELOW THE WATER TABLE, MEASURES WILL BE IMPLEMENTED TO CONTROL GROUNDWATER LEVELS AND FILL PLACEMENT SO THAT BLOCKS DO NOT FLOAT.
4. GEOFOAM BLOCKS ARE DEPICTED ON THIS DRAWING FOR PLAN LOCATION. BLOCKS WILL BE PLACED ABOVE THE LLDPE.
5. THE CLASS A GEOSYNTHETIC WHICH LAPS OVER THE SCB AND SHEETPILE BARRIER WALLS IS DESIGNED TO PROTECT THE LLDPE FROM PUNCTURING FROM THE STRUCTURAL WALL. THE 15 FT. DIMENSION WAS SELECTED TO PROVIDE FOR DEPLOYMENT OF A SINGLE ROLL WIDTH. GCL AREAS ARE MINIMUMS. IF THE CONTRACTOR WISHES TO USE FULL ROLL WIDTHS THE AREA OF GAS VENT OR CLASS A GEOTEXTILE MAY BE REDUCED ACCORDINGLY. PANEL DEPLOYMENT SHOULD BE REVIEWED WITH THE ENGINEER PRIOR TO DEPLOYMENT.




## NOTES:

1. PERFORATED PIPE TO BE CORRUGATED SLOTTED PE PIPE.
2. SPACERS MAY BE PREFABRICATED AS PART OF THE 4.5" DIA VENT PIPE.

## GAS VENT DETAIL

NTS

AN
C-121 C-121

0 25 50 100
SCALE IN FEET

SAMUEL G. SHALLARD
N.J PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|---|
| 4 | 08/13/15 | REVISED DETAIL AN | TDD | RJR | TDD | APVD |
| 3 | 05/29/15 | CAP/EDGE DETAILS AND CORRIDORS | | RJR | SGS | |
| 2 | 05/20/15 | REVISED EDGE DETAILS | | RJR | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD | SHM | |
| | | | | BY | APVD | |
| | | | | SHM | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GAS VENTING SYSTEM AND DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 888 - 2828
In Collaboration with Arcadis and Langan

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-121 |
| SHEET | 26 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR26-C-121 Gas Venting System and Details.dwg PLOT DATE: Thu, 13 Aug 2015 PLOT TIME: 8:30 AM

**FINAL DCB 035.3 – GCL AND GEOTEXT CLARIFICATION**

DESIGN CHANGE BULLETIN


| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 35.3 **DCB Type:** Minor (a)<br>**Effective Date:** 10/06/15 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Revised Gas Venting System and Cap Details | ☑ Yes, RFI No. 60 ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description.** This DCB was prepared in response to RFI-060 regarding the strip of 16 oz. geotextile adjacent to the SCB wall and Barrier Wall as shown with the red balloon in the attached annotated PDF of C-121 (rev 4, 8/13/15). This area was inspected in the field and this DCB serves to verify direction provided by the EOR at that time.

GCL is required to be installed over the SCB wall and Barrier Wall at these locations as shown. The GCL serves to protect the geomembrane from the Barrier Wall/SCB walls and acts as a redundant hydraulic barrier under the geomembrane in areas where the geomembrane may be immersed below the groundwater. The GCL should extend from the walls and associated utility corridor onto the elevated subgrade plateau where the 16 oz. geotextile is shown. It is acceptable to substitute either GCL or Gas Vent layer for the 16 oz. geotextile. A substitution using the materials noted will have no impact on the remedy.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:** Design clarification<br>**Attachments:** ☑ Yes ☐ No<br>Annotated C-121<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 10/6/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





## GEOFOAM BLOCK SUMMARY

| NUMBER | LENGTH |
|---|---|
| 1 | 8' |
| 2 | 8' |
| 3 | 32' |
| 4 | 8' |
| 5 | 32' |
| 6 | 16' |
| 7 | 8' |
| 8 | 8' |
| 9 | 8' |
| 10 | 32' |
| 11 | 32' |
| 12 | 8' |
| 13 | 8' |

GEOFOAM BLOCKS EPS 19 4' WIDE x 1' THICK LENGTH VARIES

## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. WHERE BLOCKS ARE PLACED BELOW THE WATER TABLE, MEASURES WILL BE IMPLEMENTED TO CONTROL GROUNDWATER LEVELS AND FILL PLACEMENT SO THAT BLOCKS DO NOT FLOAT.
4. GEOFOAM BLOCKS ARE DEPICTED ON THIS DRAWING FOR PLAN LOCATION. BLOCKS WILL BE PLACED ABOVE THE LLDPE.
5. THE CLASS A GEOSYNTHETIC WHICH LAPS OVER THE SCB AND SHEETPILE BARRIER WALLS IS DESIGNED TO PROTECT THE LLDPE FROM PUNCTURING FROM THE STRUCTURAL WALL. THE 15 FT. DIMENSION WAS SELECTED TO PROVIDE FOR DEPLOYMENT OF A SINGLE ROLL WIDTH. GCL AREAS ARE MINIMUMS. IF THE CONTRACTOR WISHES TO USE FULL ROLL WIDTHS THE AREA OF GAS VENT OR CLASS A GEOTEXTILE MAY BE REDUCED ACCORDINGLY. PANEL DEPLOYMENT SHOULD BE REVIEWED WITH THE ENGINEER PRIOR TO DEPLOYMENT.




## NOTES:

1. PERFORATED PIPE TO BE CORRUGATED SLOTTED PE PIPE.
2. SPACERS MAY BE PREFABRICATED AS PART OF THE 4.5" DIA VENT PIPE.

GAS VENT DETAIL — AN C-121 C-121

NTS

0 25 50 100
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 4 | 08/13/15 | TDD | RJR | TDD | SHM | RJR SGS |
| 3 | 05/29/15 | | | | | RJR SGS |
| 2 | 05/20/15 | | | | | RJR SGS |
| 1 | 10/11/13 | | | | | RJR SGS |
| 0 | 06/07/13 | | | | | TDD SHM |

REVISED DETAIL AN
CAP/EDGE DETAILS AND CORRIDORS
REVISED EDGE DETAILS
MODIFIED BARRIER WALL ALIGNMENT
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE LIBERAL AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GAS VENTING SYSTEM AND DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 Horsehill & Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2929
NJ Certificate of Authorization number 24GA28018400

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-121 |
| SHEET | 26 OF 66 |

**FINAL DCB 036 – REVISED C-309**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 36 **DCB Type:** Minor (a)<br>**Effective Date:** 7/22/15 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Revision to Detail BN Sheet C-309 | ☐ Yes, RFI Nos. ☑ None |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor):** ENTACT | |

**Description**


Detail BN has been modified to extend the LLDPE up and over the SCB Wall. The prior detail showed both the GDL and geomembrane terminating at the wall.

Extending the LLDPE over the SCB wall raise the connection above the water table and perimeter pool elevations and a "below groundwater connection condition" and the related sand bentonite connection detail below the GCL as shown on the Rev 3 dated 5/27/15 BN detail.


The submerged detail (Detail G) will still be required where the GCL overlaps the sheetpile Hydraulic Barrier. This does include the "sand bentonite plug". The Bentonite to Sand ratio shall be a nominal amount of 8% bentonite by weight. The Bentonite should be a sodium bentonite, min 90 BBL yield, equal or better than Baroid Aquagel.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 7/22/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




TYPICAL EDGE DETAIL ABOVE GROUNDWATER TABLE
NTS
BO
C-121 | C-309





PAVEMENT SECTION DETAIL
NTS
BA
C-108 | C-309
C-109
C-110





NOTE:
NO HISTORIC FILL SHALL BE PLACED ON SA-7


EXCAVATION AREA
NTS
BJ
TYP | C-309




PAVEMENT TRANSITION DETAIL
NTS
BL
TYP | C-309




EXCAVATION EDGE
RESTORATION DETAIL
NTS
BM
TYP | C-309





**BELOW GROUNDWATER**

**GCL AREAS STA 0+00 TO STA 15+00**

TYPICAL EDGE DETAIL - LINER BELOW FINAL SCB ELEVATION
NTS
BN
C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER
NTS
G
TYP | C-309

NOTE:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 4 | 07/21/15 | TDD | TDD | RJR | TDD | RJR |
| 3 | 05/27/15 | | | | | TDD |
| 2 | 05/20/15 | | | | | RJR |
| 1 | 05/05/15 | | | | | TDD |
| 0 | 06/07/13 | | | | | TDD |

REVISED DETAIL BN
REVISED DETAILS
REVISED DETAILS
REVISED DETAIL
ISSUED FOR CONSTRUCTION
REVISION

SGS
SGS
SGS
SGS
SHM
APVD

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND COPYRIGHTABLE RIGHTS. IT IS LOANED SUBJECT TO RETURN UPON DEMAND AND SUBJECT TO THE AGREEMENT THAT NO COPIES, REPRODUCTIONS, OR PATENTABLE DESIGNS ARE MADE, AND NO INFORMATION SHALL BE DISCLOSED TO ANY UNAUTHORIZED PERSON WITHOUT THE WRITTEN PERMISSION OF AMEC. ANY REPRODUCTION OF THE DRAWING, IN WHOLE OR PART, OR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
MISCELLANEOUS DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28046600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-309 |
| SHEET | 45 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR45-C-309 Miscellanious Details.dwg PLOT DATE: Tue, 21 Jul 2015 PLOT TIME: 3:15 PM

**FINAL DCB 037 – DETAIL CD DWG 304**

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 37 **DCB Type:** Minor (a)<br>**Effective Date:** 7/28/15 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Add notes to Detail CE to address above and below GW connection detail | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description**

**Detail CE Drawing C-304.** Sheet 304 is reissued to include the changes noted below on Detail CE. As with many other components in the design this detail requires a submittal from ENTACT/ESI to show their proposed installation details. It is possible that the submittal may result in changes to the fastening method.


Detail CE, as issued, showed GCL under the LLDPE. GCL will only be placed under the geomembrane at locations where the connection detail is below the groundwater table. Gas Vent will be placed at all locations above the groundwater table.

Several revisions have been made as noted below. The notes and components added cover conditions where the connection detail may be below groundwater and where structures/connections are above groundwater. The following changes have been made.

- GDL has been shown above the LLDPE geomembrane.
- Notations have been added to indicate that Gas Vent layer will be used under the LLDPE where the connection is above groundwater and GCL where the detail is below the groundwater.
- The amount of slack was reduced from approx. 3 inches to approx. 1 inch. This reduction is based upon the fact that the site has already been surcharged and primary consolidation removed. One inch of slack is adequate to accommodate any secondary consolidation.
- Note added to indicate that the top of the boot will be a minimum of 6 inches above the groundwater table if the structure is located below the groundwater.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>C-304 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 7/29/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





NOTES:

1. USE THUNDERLINE LINK–SEAL TYPE LS 300–C FOR 2"ø OR 3" ø PIPELINES AND TYPE LS 425–C FOR 1"ø AND 1–1/4" PIPELINES OR EQUAL AT ALL MANHOLES AND STRUCTURES.
2. USE PRESSURE GAGE AND PROBE ON PIPELINES THAT SLOPE UPWARDS FROM STRUCTURES ONLY, BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK–JOINT FLEXIBLE MANHOLE SLEEVE OR KOR–N–SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.

## TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL (X)


NTS — C–304 | C–306




IN THE LEAK DETECTION ROAD BOXES WHERE THE TOP OF THE TRANSITION PIECE IS CLOSE TO THE UNDERSIDE OF THE ROAD BOX COVER A THREADED FLAT STEEL CAP IS INSTALLED DIRECTLY ON THE THREADED TRANSITION PIECE. A THREADED STEEL PLUG IS INSTALLED IN THE REMAINING LEAK DETECTION RISERS.


## LEAK DETECTION STATION (CG)

NTS — C–204 | C–304





## LINER ANCHOR TO CONCRETE STRUCTURE (CE)

NTS — TYP | C–304





## AIR RELEASE STATION (CF)

NTS — C–204 | C–304





## DOUBLE CONTAINED ELBOW PIPE CLEANOUT (CH)

NTS — C–204 | C–304




## EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT (CI)

NTS — C–204 | C–304




## EXISTING 3" LEAK DETECTION STATION (CJ)

NTS — C–204 | C–304

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND C–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | REO | CHK | RJR | REO | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|---|---|---|
| 2 | 07/28/15 | DCB 37 REVISED DETAIL CE | | | | RJR | SGS | | SHM | |
| 1 | 02/13/15 | DCB 007.3 | | | | TDD | SGS | | SHM | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD | SHM | | SHM | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTED FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS LOANED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-304 |
| SHEET | 41 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR41-C-304_GWFM_Details.dwg PLOT DATE: Tue, 28 Jul 2015 PLOT TIME: 10:56 AM

**FINAL DCB 037.2 – MANHOLE BOOT DETAIL**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No. 037.2: Type: Minor** (a)<br>**Effective Date:** 8/7/15 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Revised Final 4ft manhole Boot Detail | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description.**

**AmecFW has conducted further review of this detail with Entact/ESI including field review to improve constructability.**

**DCB 037.2 supersedes DCB 037.1.**

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See comments |
| | **Attachments:** ☑ Yes ☐ No<br>Revised Detail CE |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments: The detail provides for an extended boot to accommodate any secondary consolidation rather than attempting to fabricate folds/slack into a circular boot. 1 inch of settlement would result in approximately 2% strain. The LLDPE can tolerate in excess of 200% strain. This detail simplifies fabrication, eliminates folds and will be capable of accommodating more settlement than either the original batten design or DCB 037.1 design.** | **Design Documents Affected:**<br>NA |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 8/7/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





# LINER ANCHOR TO CONCRETE STRUCTURE

NTS


CE
TYP | C-304





TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL (X)
NTS
C-304 | C-306





LEAK DETECTION STATION (CG)
NTS
C-204 | C-304





AIR RELEASE STATION (CF)
NTS
C-204 | C-304





DOUBLE CONTAINED ELBOW PIPE CLEANOUT (CH)
NTS
C-204 | C-304




LINER ANCHOR TO CONCRETE STRUCTURE (CE)
NTS
TYP C-304




EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT (CI)
NTS
C-204 | C-304




EXISTING 3" LEAK DETECTION STATION (CJ)
NTS
C-204 | C-304

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

| NO. | DATE | BY | CHK | APVD |
|---|---|---|---|---|
| 3 | 08/05/15 | RJR | SGS | |
| 2 | 07/28/15 | RJR | SGS | |
| 1 | 02/13/15 | TDD | SGS | |
| 0 | 06/07/13 | TDD | SHM | |

REVISION

DSGN | DR | CHK | APVD
REQ | REQ | REQ

DCB 37.1 REVISED DETAIL CE
DCB 37 REVISED DETAIL CE
DCB 007.3
ISSUED FOR CONSTRUCTION

Honeywell
101 COLUMBIA RD., BOX 2108, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 183
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 131
Hamilton, NJ 08619
(609) 587-3500
NJ Certificate of Authorization Number 24GA28019600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-12-0317
DWG C-304
SHEET 41 OF 66

THE COPYRIGHT IN THE PROPERTY OF AMEC ENVIRONMENT & INFRASTRUCTURE, INC. AND ITS SUBCONSULTANTS AND MAY NOT BE USED, REPRODUCED OR MODIFIED IN ANY WAY, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREIN, FOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SAR-CSD\CAD\SA6-North-South-DW_Extraction_Trench\ICR41-C-304_DWFM_Details.dwg PLOT DATE: Wed, 05 Aug 2015 PLOT TIME: 3:49 PM

**FINAL DCB 039 – SUBGRADE SOIL WEDGE**


DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 039 **DCB Type:** (a)<br>**Effective Date:** 7/30/15 |
| **Project Location:** SA-6<br>**Title:** Corridor B SCB Detail | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** Entact was granted approval to install a wedge of soil in the B Street corridor against the SCB wall. There is a step up in this location from the corridor subgrade to the top of the SCB wall. The intent of the Entact request was to provide a more gradual transition between the corridor subgrade and SCB Wall. Amec reviewed the CHA utility drawings and determined that there were no utility structures within this location that would be impacted by the change i.e. the change has no impact on the future development, The remaining corridor to SCB wall detail will be installed as shown on the contract drawings. | |
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other-Entact Request | **Explanation or Reason:** See additional comments<br>**Attachments:** ☑ Yes ☐ No<br>Annotated Detail BN<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>NA |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 8/7/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




TYPICAL EDGE DETAIL ABOVE GROUNDWATER TABLE (B0)
NTS
C-121 | C-309





PAVEMENT SECTION DETAIL (BA)
NTS
C-108 | C-309
C-109
C-110





NOTE:
NO HISTORIC FILL SHALL BE PLACED ON SA-7


EXCAVATION AREA (BJ)
NTS
TYP | C-309




PAVEMENT TRANSITION DETAIL (BL)
NTS
TYP | C-309





EXCAVATION EDGE RESTORATION DETAIL (BM)
NTS
TYP | C-309




DCB 039
DETAIL BN B STREET
8/7/15

TYPICAL EDGE DETAIL - LINER BELOW FINAL SCB ELEVATION (BN)
NTS
C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)
NTS
TYP | C-309

NOTE:
1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

| NO. | DATE | DSGN | DR | CHK | REVISION |
|---|---|---|---|---|---|
| 4 | 07/21/15 | TDD | RJR | TDD | REVISED DETAIL BN |
| 3 | 05/27/15 | | | | REVISED DETAILS |
| 2 | 05/20/15 | | | | REVISED DETAILS |
| 1 | 05/05/15 | | | | REVISED DETAIL |
| 0 | 06/07/13 | | | | ISSUED FOR CONSTRUCTION |

APVD: BY | APVD
RJR | SGS
TDD | SGS
RJR | SGS
TDD | SGS
TDD | SHM

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD, BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
MISCELLANEOUS DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2029
NJ Certificate of Authorization Number 24GA28000400

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-309 |
| SHEET | 45 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**FINAL DCB 041 – WARNING LAYER**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 041 **DCB Type:** Minor (a)<br>**Effective Date:8/19/15** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Warning Tape with Do Not Dig Markings | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** Drawings C-301 1and CN-301 provide a Typical Utility Corridor/Hydraulic Barrier Wall Crossing Detail which calls for "Distinctive colored warning layer with markings in English and Spanish."

Entact Notified AmecFW that the vendor had experienced difficulty during set up and could not produce an acceptable quality of lettering on the orange non-woven geotextile (due to ink blurring).

As an option Entact proposed installing a standard direct burial utility marking tape.

AmecFW approved use of a 6 inch wide yellow PE tape with 3.5 inch bold back lettering as meeting the specified requirements for a distinctive colored high visibility marking. The tape will be placed at no more than 5 ft. on center.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐Unforeseen or Differing Site Conditions<br>☐Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:** See comments<br><br>**Attachments:** ☑ Yes ☐ No<br>Revised Detail CE<br><br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:**<br>The 6 inch wide yellow tape provides a greater contrast and higher visibility against the orange background than the black lettering printed on the orange fabric. It is considered to be "an or-equal" or better option and was approved accordingly. | **Design Documents Affected:**<br>Attached PDF from tape manufacturer with size and lettering.<br>Letters from manufacturer regarding suitability for application. |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 8/19/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

Systems Pack Inc.
649 E. HIGHLAND ROAD
MACEDONIA, OHIO 44056
"Manufacturers of Design Ideas"
(330) 467-5729
FAX (330) 468-2299

July 13, 2015

Adam Ewert
**ENTACT, LLC**
1 E. Oak Hill Drive, Suite 102
Westmont, IL 60559

RE: Warning Tape Certification/Warranty Statement

Dear Adam,

Please use this letter as confirmation that the polyethylene tape we have quoted for the Entact – Honeywell - Jersey City project is suitable for burial applications.

Polyethylene (PE resin) tapes are suitable for a buried warning barrier as they are inert and not biodegradable. Deterioration is only noted when PE is exposed to prolonged sunlight. PE does not migrate in soil and floats in water. PE produces no effects on aquatic or terra environments. When placed in landfills, they do not release gases or other compounds (known to pollute water resources.)

SPI warrants to the buyer that its products are free from defects in material and workmanship, but limits its obligation to replacement of the product. This warranty is in lieu of any other warranty, expresses or implied, including but not limited to any implied warranty of merchantability or fitness for a particular use, and of any other obligations or liability on SPI's part. SPI shall not be liable for any loss, damage, expense or consequential damages of any kind arising in connection with the use, or inability to use, its products.

If you have any questions or need further information on this or any of our products, please let Peter Daly @ IWT Cargoguard or myself know.

Best regards,

*Trish Righetti*

Trish Righetti

Systems Pack Inc.
649 E. HIGHLAND ROAD
MACEDONIA, OHIO 44056

"Manufacturers of Design Ideas"

(330) 467-5729
FAX (330) 468-2299

July 15, 2015

Adam Ewert
**ENTACT, LLC**
1 E. Oak Hill Drive, Suite 102
Westmont, IL 60559

RE: Warning Tape Certification/Warranty Statement – Inks and Printing

Dear Adam,

Please use this letter in conjunction with our initial Certification/Warranty as confirmation that the inks used to print polyethylene tape we have quoted for the Entact – Honeywell - Jersey City project is suitable for burial applications.

Solvent inks are permanently adhered to the polyethylene tapes and (once ink is dry) can only be removed by applied, chemical means. This particular tape and ink combination was designed and been used as an underground marking tape for over 25 years with no quality or sustainability issues. We are confident in its performance for your current application.

If you have any questions or need further information on this or any of our products, please let Peter Daly @ IWT Cargoguard or myself know.

Best regards,

Trish Righetti

Trish Righetti

Systems Pack Inc.
649 E. HIGHLAND ROAD
MACEDONIA, OHIO 44056
"Manufacturers of Design Ideas"
(330) 467-5729
FAX (330) 468-2299

# 4 mil Mil PE Barricade Tape

I. SPECIFICATIONS:
Barricade warning tapes will consist of high visibility safety yellow or red polyethylene with bold black letters. Standard letter height minimum of two inches (2"+). Tapes help prevent accidents by increasing visibility of hazards and can be tied, stapled or nailed in place.

II. TEST DATA:
Material Identification: Nominal 4 Mil Polyethylene,
6" wide
Test Procedure: ASTM-D-882, Method A
Specimen Conditions: 73ºF / 50% R.H.
Test Temperature: 73ºF
Elongation: 552%
Tensile Strength (Transverse): 2,100 psi
Tensile Strength (Longitudinal): 2,870 psi
Roll Weight (6" x 1000') 9.0 lbs.

Suitable for burial




| | | | |
|---|---|---|---|
| Sales Order Number: | 24106040 / 0030 v2 | Material: | 4 MIL POLYETHYLENE (PE) |
| Date: | 07.10.2015 | Colors: | yellow/black |
| Artist: RP Revised By: | RP | Size: | 6" x 1000' |

Prepared by Trish Righetti 7/10/2015
Revised by T. Righetti 7/15/2015 – Tape width and minimum print height

**FINAL DCB 042 – ANCHOR TRENCHES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 042 **DCB Type:** Minor(a)<br>**Effective Date: 8/21/15** |
| **Project Location:** SA-6<br>**Title:** Anchor Trench Applicability | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** The anchor trench section of the Specification 02372 CAP GEOMEMBRANE LINER Section 3.02 is standard industry language and part of AmecFW's standard Geomembrane Specification. During the process of finalizing development of the capping system in the 100% Design, the Engineer determined that anchor trenches were not required for either the SA-6N or SA-6S Caps. As such, Paragraph 3.02 is no longer required and therefore the following is deleted in its entirety.

SECTION 02372

CAP GEOMEMBRANE LINER

3.02 ANCHOR TRENCH

A. The anchor trench shall be constructed as shown on the Drawings and/or as specified herein.

B. The anchor trench shall be adequately drained to prevent water ponding and softening of adjacent soils. The anchor trench shall be backfilled and compacted.

C. Geosynthetic material in the anchor trench shall be temporarily anchored with sandbags or other suitable materials until final approvals are obtained.

D. Backfilling of the anchor trench shall be conducted when the geomembrane is in its most contracted (taut) state.

E. Care shall be taken when backfilling and compacting the trenches to prevent any damage to the lining materials.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br><br>**Attachments:** ☐ Yes ☑ No<br><br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Delete Section 3.02 Anchor Trench from Spec 02372 |

**Honeywell (AP) Review:**


**Individual:** Geoff Shallard **Discipline:** EOR **Initial:** **Date:** 8/21


**FINAL DCB 043 – TOP OF HB AND SCB**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 043 **DCB Type:** Minor(a)<br>**Effective Date: 8/20/15** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Top of Barrier Wall/SCB Wall Revisions (S-201 and S-204), Utility Corridor Changes | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** The most easterly utility corridor was eliminated from the Development Plan allowing for a revision to the cap subgrade and related revisions to the top of the Barrier Wall and SCB Wall. | |
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See additional comments<br>**Attachments:** ☑ Yes ☐ No<br>Drawings S-201 and S-204<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Eliminating the corridor allows grades and top of wall to be lifted in this area. This change reduces the amount of cap and cap wall connection that is immersed. Cap subgrade and Final Grade revisions were issued under DCB 027. | **Design Documents Affected:**<br>Drawings S-201 and S-204 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 9/2/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 1+54 | -3 | AZ 19-700 |
| STRUCTURAL | 1+54 | 5+00 | -19 | AZ 19-700 |
| STRUCTURAL | 5+00 | 12+60 | -22 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FUTURE UTILITIES WILL REQUIRE WALL PENETRATIONS AT THESE TWO LOCATIONS.
4. REFER TO SHEET G-003, NOTE HB19 AND DETAIL "BE" ON SHEET C-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE

0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 08/20/15 | TDD | RJR | TDD | | TDD | SHM |
| 0 | 06/07/13 | | | | | TDD | SGS |

REVISION
ISSUED FOR CONSTRUCTION
DCB 043

THIS DRAWING IS THE PROPERTY OF AMEC; INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
HYDRAULIC BARRIER PLAN & PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
2 Princess Road, Lawrenceville, NJ 08648
Hamilton, NJ, (609) 895-0071 Fax (609) 689-2829
NJ Certificate of Authorization Number 24GA28018800

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | S-201 |
| SHEET | 53 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR53-S-201 Hydraulic Barrier Wall Plan Profile.dwg PLOT DATE: Thu, 20 Aug 2015 PLOT TIME: 2:27 PM




NOTES:

1. SEE SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. SEE SHEET G-003 AND G-004 FOR GENERAL NOTES.
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE LINER GRADE.

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

0 2 4 8
SCALE IN FEET
VERTICAL SCALE: 1" = 4'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 09/02/15 | PROPOSED SCB WALL ELEVATION | TDD | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |
| | | | TDD | RJR | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
EXISTING SA-7 SCB WALL
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619 (609) 890-2929
NJ Certificate of Authorization Number 24GA28010000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG S-204
SHEET 56 OF 66

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR56-S-204 SCB Wall Plan Profile.dwg PLOT DATE: Thu, 03 Sep 2015 PLOT TIME: 9:33 AM

# FINAL DCB 046 – PLANTING SOILS

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 046 **DCB Type:** Minor (a)<br>**Effective Date:** 9/17/15 |
| **Project Location:** SA-6<br>**Title:** Planting Soil Specifications | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** Revisions to the Planting soil Specifications. | |
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See additional comments<br><br>**Attachments:** ☑ Yes ☐ No<br>Dr. Jason Grabosky letter<br>Specification 02315, Section 2.12 , Table 1<br><br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Extensive searching of available soil suppliers (including 6 identified by Dr. Grabosky/Rutgers University) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | **Design Documents Affected:**<br>Specification 02315, Section 2.12 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 10/22/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

RUTGERS
School of Environmental and Biological Sciences

Urban and Community Forestry Program
Dept. of Ecology Evolutionand Natural Resources
Environmental and Natural Resources Bld, Room 144
Rutgers, The State University of New Jersey
14 College Farm Road
New Brunswick, NJ 08901-8551

September 17, 2015

To whom it may concern:

I was contacted by the Mr Shallard of ***Amec Foster Wheeler Environment & Infrastructure, Inc*** with regard to questions on the soil materials available for a NJ Project. Honeywell/AmecFW submitted results of analysis of Planting Soil samples from multiple vendors, selected from a list provided by Rutgers, for Horizon A, B and C that are under consideration for use on the SA-6 Project (refer to attached excel table). These data were to be used to select the vendor and soil products available for each of the soil layers to be used on the project. It is my understanding that multiple vendors have been contacted including those provided by Rutgers (email May 13th 2015) as potential sources and, that the list and samples provided, is indicative of what is available in the market place at this time.

While the list of criteria (Sand/Silt/clay/organics/pH) is applicable to all samples the importance of each of these criteria varies due to the intended purpose of each Horizon.
In my review I have identified samples listed which I consider acceptable, or acceptable subject to minor modification, to meet the project goals. The following samples are acceptable to accomplish the goals of the many design demands on this system.

Horizon A topsoil:
Nature's Choice (NC-TS-002-NCCWS) as the preferred or Nature's Choice (NC-TS-002-NCCW).
Both exceed the gravel percentage component of the specification, however one might envision the percentages as targets, and the excess of gravel in these cases does not change the functional behavior of the material for plant growth or drainage potential. NCCW has a higher organic component which is high enough to exhibit shrinkage as the organic materials decompose, so while a functionally acceptable soil material for the purpose, the shrinkage will be noticed on landscape edges next to structures such as sidewalks, thus CCCWS is preferred. The acceptable gravel content of the specification should be revised upward from 5% to <10%.

Horizon B:
Nature's Choice (NC-HC-001) would be a good choice, as the lower organic level is not problematic, and actually sets a natural layering and gradation as underlayment to the topsoil. The pH increases from 5.0 in the topsoil to 5.96, and I do not see this as an issue, several species may well prefer the nutrient availability afforded by the higher pH. One might consider adding some organic content and blending into the B horizon material. I am not in favor of the effort and expense, as the proposed layers will change in organic content and develop a natural progression on their own over time. The Sand % should be changed from a single number of 80% to a range of 80-90%. The pH maximum should be increased from 7 to 7.5. Organic content should be changed from a range of 1.5 - 3.5% to <4%.

Horizon C:
Nature's Choice Sample (NC-HC1-002) is very close to meeting the originally specified requirements. The Clay content is 12% as compared with the specified maximum of 15-20% and the pH was reported to be

RUTGERS
School of Environmental
and Biological Sciences

7.57 as compared with the 7.5 specified. These deviations are not considered to be significant. This sample will meet the original design objectives. The Clay Content specification should be broadened to 10-20% and pH specification modified to less than 7.7 to provide for consistency between the sample and specifications.
Advanced Soil Technologies (AST-HB-002) is also a potential candidate if the sand content could be reduced to <80%. The organic level is elevated, but not problematic. Organic content should be changed from 1% maximum to <4%.

Table 1 attached summarizes the proposed changes.

In total the three layers would be very reasonable for acceptable landscape growth expectations, and provide available moisture for plants and drainage potential in a normal manner *as long as the materials are not heavily compacted after placement by construction equipment.*

As with any project, the key to success will ultimately be in the construction management/traffic controls/equipment storage planning as related to the protection of the soil investment after placement. This will be particularly important with the landscape contractor equipment in planting the trees and other landscape elements, as much as with the pavement contracting for sidewalks and structures.

Respectfully submitted,



Jason Grabosky
John and Eleanor Faculty Scholar in Urban and Community Forestry
Department of Ecology, Evolution and Natural Resources
Rutgers University
New Brunswick, NJ

RUTGERS
School of Environmental and Biological Sciences

Table 1 summarizes the modified criteria based on availability. Provision of soils meeting the criteria listed in Table 1 below will meet the objectives of providing soils that are suitable for the SA-6 project. These changes have been reviewed with the AmecFW Engineer of Record and it is recommended that both the project specification and Open Space Design Standard be amended as noted in the Table 1 below.

| SA-6 Planting Soil Specification-TABLE 1 | | | | | | |
|---|---|---|---|---|---|---|
| Revision 1 September 2015 | | | | | | |
| **Material SPEC 02315 SECT 2.12** | **Description (USDA soil triangle)** | **% Sand** | **% Silt** | **% Clay** | **% Organic Matter** | **pH** |
| Horizon A Modified | Friable Fertile Sandy loam/loamy sand | 60-80 | ▫20 | <20 | 3.5-6 | 5-6.5 |
| Horizon B Modified | Loamy sand | 80-90 | <10 | 10-15 | <4% | 5.5-7.5 |
| Horizon C Modified | Sandy loam to loamy sand | 70-80 | <10 | 10-20 | <4% | 5-7.7 |

1. *Horizon C. Clay content lowered from a minimum of 15% to a minimum of 10%. Organic content increased from <1 to <4%. pH content maximum increased from 7.5 to 7.7.*
2. *Horizon B. Sand changed from a single number of 80% to a range of 80-90%. pH maximum increased from 7 to 7.5. Organic content changed from a range of 1.5- 3.5% to <4%.*
3. *Horizon A. Gravel content increased from 5% maximum to <10%.*
4. *Soil Descriptions. The Planting Soil specifications include soil descriptions based on the USDA Soil Texture Triangle. Soils provided should be consistent with the Soil Texture Triangle.*

| SA-6 Planting Soil Specification-TABLE 1 | | | | | | |
|---|---|---|---|---|---|---|
| Revision 1 September 2015 | | | | | | |
| **Material SPEC 02315 SECT 2.12** | **Description (USDA soil triangle)** | **% Sand** | **% Silt** | **% Clay** | **% Organic Matter** | **pH** |
| Horizon A Topsoil | Friable fertile loam, fine sandy loam or sandy loam | -- | -- | -- | 3.5-6% | 5.0-6.5 |
| Horizon A Modified 9/16/15 | Friable Fertile Sandy loam/loamy sand | 60-80 | <=20 | <20 | 3.5-6 | 5-6.5 |
| Horizon B | Sandy Loam | 80-85% | ≤10% | 10-15% | 1.5-3.5% | 5.5-7.0 |
| Horizon B Modified 9/16/15 | Loamy sand | 80-90 | <10 | 10-15% | <4% | 5.5-7.5 |
| Horizon C | Uniform Sandy Loam | 70-80% | ≤10% | 15-20% | 1% max | 5.0-7.5 |
| Horizon C Modified 9/16/15 | Sandy loam to loamy sand | 70-80 | <10 | 10 – 20% | <4% | 5-7.7 |

1. *Soil Descriptions. The Planting Soil specifications include soil descriptions based on the USDA Soil Texture Triangle. Soils provided should be consistent with the Soil Texture Triangle.*

2.12 PLANTING SOILS

Planting Soils have been designated as Horizon A, B and C. Soil Horizon A – Topsoil will be a nominal thickness of 6 inches and shall conform to the requirement noted below.

A. Topsoil - Topsoil shall be placed over the Horizon B and C planting soils to final development grades shown in the design drawings. Topsoil will have a nominal depth of 6 inches. Topsoil shall be in accordance with Section 02900, "Topsoil and Seeding". Topsoil shall be certified clean from the borrow source or origin, based on analytical testing data, as approved by the Engineer. Topsoil shall be natural, friable, fertile loam, fine sandy loam or loamy sand with an organic matter content of 3.5% - 6% and a pH range of 5.0 – 6.5. Sand 60-80%, Silt ≤20%, Clay <20%. Specification 02900 requires that all materials pass a 1.5 inch sieve. Spec 02900 will be modified to allow <10% Gravel.

B. Soil Horizon B - soils will only be used in areas where the total depth of cover soils exceeds 36 inches. During the Interim Phase no Horizon B soil will be placed. Horizon B soils will be a loamy sand having the following properties:

Loamy Sand classification having ~~80~~ 80-90% sand, < 10% silt, 10-15% clay.
pH range 5.5 – 7.5 ~~7.0~~.
Organic Matter (by weight) ~~1.5-3.5~~ < 4 %

C. Soil Horizon C – During Interim Grading Horizon C Soil will be placed between the root barrier and the Horizon A soil. The first 6 inches of Horizon C soils to be placed directly above the root barrier will be compacted to a minimum 90% of Standard Proctor. To meet Final Grading and planting requirements Horizon A soils will be stripped as necessary and Horizon C soils shall be re-graded to provide an appropriate depth of 18 inches. Horizon C soil shall consist of sandy loam to loamy sand having the following properties:

1. Sandy loam to loamy sand classification with 70-80% sand, <10% silt, ~~10 – 15%~~ 10 - 20% clay.
2. pH range 5.0 – 7.7 ~~7.5~~.
3. Organic Matter (by weight) ~~1~~ < 4 % ~~max~~.

**Horizon A Soils- Geotechnical Sample Results**
**Study Area 6**
**Jersey City, NJ**

| Sample Date | Material | % Sand | % Silt | % Clay | % Gravel[2] | % Organic Matter | pH |
|---|---|---|---|---|---|---|---|
| | **Revised Specification Values[1]** | **60 - 80%** | **≤20%** | **<20%** | **<10%** | **3.5 - 6%** | **5.0 - 6.5** |
| 6/11/2015 | Advanced Soil Technologies Topsoil (AST TS -001) | 80.0% | 10.0% | 10.0% | 11.7% | 4.3% | 7.84 |
| 6/15/2015 | Natures Choice Topsoil (NC TS-001) | 75.0% | 13.0% | 11.0% | 21.6% | 5.4% | 7.33 |
| 6/29/2015 | Advanced Soil Technologies (AST HA-002) | 74.0% | 14.0% | 12.0% | 11.4% | 9.0% | 7.48 |
| 7/6/2015 | Nature's Choice (NC-HB1-002) | 76.0% | 10.0% | 14.0% | 13.3% | 3.9% | 7.46 |
| 7/7/2015 | Nature's Choice (NC-TS-002-NCCWS) | 68.0% | 20.0% | 12.0% | 5.8% | 3.8% | 5 |
| 7/7/2015 | Nature's Choice (NC-TS-002-NCCW) | 64.0% | 22.0% | 14.0% | 6.9% | 6.4% | 5 |

**Notes:**

1.) Specification values revised according to letter from Dr. Jason Grabosky of Rutgers University, dated September 17, 2015.
Samples deemed acceptable in Dr. Grabosky's letter are highlighted in green.

2.) Refer to Specification 02900 - Topsoil and Seeding, Section 2.01.B.2.

**Horizon B Soils - Geotechnical Sample Results**
**Study Area 6**
**Jersey City, NJ**

| Sample Date | Material | % Sand | % Silt | % Clay | % Organic Matter | pH |
|---|---|---|---|---|---|---|
| | **Revised Specification Values[1]** | **80 - 90%** | **<10%** | **10 - 15%** | **<4%** | **5.5 - 7.5** |
| 6/11/2015 | Advanced Soils Technologies (AST HB-001) | 87.0% | 7.0% | 6.0% | 5.4% | 7.19 |
| 6/11/2015 | Advanced Soils Technologies (AST HC-001) | 67.0% | 20.0% | 13.0% | 2.3% | 7.56 |
| 6/15/2015 | Nature's Choice (NC-HB-001) | 78.0% | 8.0% | 13.0% | 2.9% | 7.05 |
| 6/15/2015 | Nature's Choice (NC-HC-001) | 84.0% | 3.0% | 13.0% | 0.2% | 5.96 |
| 6/29/2015 | Advanced Soils Technologies (AST HB-002) | 87.0% | 7.0% | 6.0% | 4.0% | 7.4 |
| 6/29/2015 | Advanced Soils Technologies (AST HC-002) | 72.0% | 14.0% | 14.0% | 0.9% | 7.8 |
| 7/6/2015 | Nature's Choice (NC-HB1-002) | 76.0% | 10.0% | 14.0% | 3.9% | 6.66 |

**Note:**
1.) Specification values revised according to letter from Dr. Jason Grabosky of Rutgers University, dated September 17, 2015. Samples deemed acceptable in Dr. Grabosky's letter are highlighted in green.

**Horizon C Soils - Geotechnical Sample Results**
**Study Area 6**
**Jersey City, NJ**

| Sample Date | Material | % Sand | % Silt | % Clay | % Organic Matter | pH |
|---|---|---|---|---|---|---|
| | **Revised Specification Values[1]** | **70 - 80%** | **<10%** | **10 - 20%** | **<4%** | **5.0 - 7.7** |
| 6/11/2015 | Advanced Soils Technologies (AST HB-001) | 87.0% | 7.0% | 6.0% | 5.4% | 7.19 |
| 6/11/2015 | Advanced Soils Technologies (AST HC-001) | 67.0% | 20.0% | 13.0% | 2.3% | 7.56 |
| 6/15/2015 | Nature's Choice (NC-HB-001) | 78.0% | 8.0% | 13.0% | 2.9% | 7.05 |
| 6/15/2015 | Nature's Choice (NC-HC-001) | 84.0% | 3.0% | 13.0% | 0.2% | 5.96 |
| 6/29/2015 | Advanced Soils Technologies (AST HB-002) | 87.0% | 7.0% | 6.0% | 4.0% | 7.4 |
| 6/29/2015 | Advanced Soils Technologies (AST HC-002) | 72.0% | 14.0% | 14.0% | 0.9% | 7.8 |
| 7/6/2015 | Nature's Choice (NC-HC1-002) | 79.0% | 9.0% | 12.0% | 0.3% | 7.57 |
| 7/6/2015 | Nature's Choice (NC-HC2-002) | 85.0% | 9.0% | 6.0% | 0.3% | 8.25 |
| 7/6/2015 | Nature's Choice (NC-HC3-002) | 85.0% | 11.0% | 4.0% | 0.1% | 8.37 |

**Note:**
1.) Specification values revised according to letter from Dr. Jason Grabosky of Rutgers University, dated September 17, 2015. Samples deemed acceptable in Dr. Grabosky's letter are highlighted in green.

**FINAL DCB 048 – SA-6S SITE 163 DCB**


DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** **DCB Type:** Major (a)<br>**Effective Date:** 9/28/15 |
| **Project Location:** SA-6 South, Site 163<br>**Title:** Site 163 Excavation | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description:** Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. The residential footprint includes the area north of the northern curbline of the future River Front Park/Riverside Drive/Kellogg Street to be constructed during the Bayfront Redevelopment project. A plan view and cross sections of the excavation area are included in the attached Figure 1. Soils that were treated successfully will not be subject to excavation or to further sampling. The remaining chromium-impacted soils identified in the area south of the northern curbline are within the future River Front Park/Riverside Drive /Kellogg Street as depicted on the attached Figure 2 and will be subject to a deed restriction and not be subject to further sampling.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>Noted in Description<br>**Attachments:** ☑ Yes ☐ No<br>Figure 1<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>A new drawing C-129 will be issued showing the limits of excavation depicted on Figure 1. |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 10/1/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☑ **Yes (b)** ☐ **No**<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





NOTE: AREA NORTH OF PROPOSED EXCAVATION PREVIOUSLY COMPLETED AND BACKFILLED WITH CLEAN IMPORTED MATERIAL OR HISTORIC FILL (<20 PPM HEX CR)





SECTION A−A'





SECTION B−B'




SECTION C−C'




SECTION D−D'




SECTION E−E'




LEGEND

- PDI BOTTOM SAMPLE LOCATION
- PDI SIDEWALL SAMPLE LOCATION
- LIMIT OF EXCAVATION
- OVERBURDEN (<20 PPM HEX CR)
- CHROMIUM IMPACTED SOIL (20−240 PPM HEX CR)

NOTES:

1. HONEYWELL WILL EXCAVATE THE AREA DEPICTED ON THIS FIGURE AND IS PLANNING LOGISTICS WITH IT'S CONSTRUCTION MANAGEMENT TEAM AND REMEDIAL CONTRACTOR(S).
1. UNDER THE EXCAVATION SCENARIO, HONEYWELL WILL CONTINUE TO EVALUATE USING SHEETPILE FOR TEMPORARY EXCAVATION SUPPORT, BACKSLOPING, OR A COMBINATION OF BOTH.
2. OVERBURDEN MATERIAL WILL BE EXCAVATED, STOCKPILED, AND HANDLED IN ACCORDANCE WITH THE APPROVED SOIL MANAGEMENT PLAN IN THE 100% DESIGN.
3. CHROMIUM−IMPACTED MATERIAL WILL BE EXCAVATED, STOCKPILED, AND HANDLED IN ACCORDANCE WITH THE APPROVED SOIL MANAGEMENT PLAN IN THE 100% DESIGN.
4. BACKFILLING WILL OCCUR UPON VERIFICATION BY INDEPENDENT THIRD PARTY LICENSED LAND SURVEYOR THAT HORIZONTAL AND VERTICAL EXTENTS OF EXCAVATION HAVE BEEN ACHIEVED.
5. HONEYWELL MAY IMPLEMENT THIS EXCAVATION BY THE END OF 2015.
6. HONEYWELL MAY ELECT TO USE A CONTRACTOR OTHER THAN ENTACT TO IMPLEMENT THIS EXCAVATION ACTIVITY.
7. THE PROPOSED EXCAVATION FOOTPRINT IS 6,335 SF AND 5 BOTTOM SAMPLES SATISFIES THE NJDEP APPROVED FREQUENCY OF 1:1300 SF AS IDENTIFIED IN THE 100% DESIGN REPORT.

Prepared/Date: TDD 9/22/15
Checked/Date: DEN 9/22/15

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD. BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec foster wheeler<br>Environment & Infrastructure, Inc.<br>200 American Metro Blvd, Suite 113<br>Hamilton, NJ, 08619, (609) 689 - 2529 | SITE 163 - ADDITIONAL<br>CHROMIUM EXCAVATION AREAS<br>FIGURE 1 |

C:\Donovan\SA−6 South Excavation Limits April 2012\2013 Excavation Shapes\SA−6 South Design Change Bulletin\Site 163 Excavation Shp\Figure 1 Site 163 Additional Excavation Areas.dwg Thu, 26 Sep 2013 − 10:28am tony.donovan

HACKENSACK RIVER

NOTE: AREA NORTH OF PROPOSED EXCAVATION PREVIOUSLY COMPLETED AND BACKFILLED WITH CLEAN IMPORTED MATERIAL OR HISTORIC FILL (<20 PPM HEX CR)

FUTURE CURB LINE (TYP)

IN-SITU TREATMENT AREAS WITH SOILS THAT REMAIN >20 PPM FOR HEXAVALENT CHROMIUM (TYP)

NOTE: APPROXIMATE AREA SUBJECT TO A DEED RESTRICTION UNDER RIVERFRONT PARK, RIVERSIDE DRIVE, OR KELLOGG STREET

APPROXIMATE LOCATION OF EXISTING BULKHEAD (TYP)

DROYERS COVE

0 20 40 80
HORIZONTAL SCALE

Prepared/Date: TDD 9/24/15
Checked/Date: DEN 9/24/15

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2529

SITE 163
DEED RESTRICTED AREAS
FIGURE 2

C:\Darrenm\SA-6 South Excavation Limits April 2013\2013 Excavation Shapes\SA-6 South Design Change Bulletins\Site 163 Excavation SP\Figure 2 Site 163 Deed Restricted Areas.dwg Mon, 28 Sep 2015 - 4:15pm tonyAdamonis

**FINAL DCB 048.1 – SA-6S SITE 163 EXCAVATION SURVEY**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 48.1 **DCB Type:** Minor (a)<br>**Effective Date:** 12/21/15 |
| **Project Location:** SA-6 South, Site 163 | **Associated RFI:** |
| **Title:** Site 163 Survey Control | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** Amec Foster Wheeler (AmecFW), Entact and Maser Consulting have developed alternative methods for documentation/survey of the excavation bottom in Site 163. The alternative methods were developed in light of safety considerations for surveyor access into a sheet piled excavation to elevation –8.0. The bottom of the excavation will be in very low strength Stratum O soils. These alternative survey control methods are different from those previously used in the SA-6 South Development Area.

The existing SOP requires "excavation to grade" using the Machine Control, followed by use of a GPS Rover to check grade by the Entact QC engineer, and finally the GPS Rover documentation survey of the Bottom of Excavation by Maser (the registered surveyor). Through this process a high level of confidence has been developed in the accuracy of the Machine Control.

The Site 163 SOP is based on the use of GPS based Machine Control for documentation of the bottom of excavation elevation.

SITE 163 EXCAVATION SOP

*Temporary Sheetpile will form the perimeter of the Cr excavation. The sheetpile limits have been designed to extend to the defined <20 ppm PDI Sidewall locations. The location of the installed sheetpile will be surveyed by Maser to document the lateral limits of excavation.*

*Excavation Equipment. The excavator used for survey documentation will be equipped with twin Trimble Model MS990 Receivers and Model CB430 Display. The Model MS990 Receivers are linked to a Model SPS852 Base Station located on the project site.*

*Excavation: During excavation, Entact will conduct a daily calibration check at ground surface prior to excavation. Entact QC will verify the bottom of excavation is at or below the design elevation by means of the Machine Control.*

*When the design bottom elevation has been reached, calibration will be rechecked in the presence of the Maser Surveyor.*

*Following the Surveyor Calibration check, the following steps will be performed:*

- *The bucket will be set at the "Bottom" PDI points and the elevations recorded.*
- *Elevations (Z) will be recorded at locations (X,Y) designated by the Surveyor, based on the Surveyor's professional opinion of the number and location of points that are necessary to generate the required Bottom of Excavation Topographic Map.*
- *If Stratum D is observed, readings will be taken to record the "plan" limit of the Stratum D.*
- *The above information will be entered into the Excavation Table to be signed by Maser.*

*Excavation Submittal: Due to the small size of Site 163, a single submittal package will be prepared and submitted by Honeywell to the Special Master and Plaintiffs.*


*The submittal will include:*

- *Excavation Table listing all Bottom PDI points*
- *Excavation Plan (Entact) showing limits of excavation, PDI locations and spot elevations.*
- *Summary Statement regarding observations (Honeywell/AmecFW)*


For inclusion in the Declarations, Maser will also prepare a bottom of excavation topographic map which will also show the limits of excavation (sheet pile alignment).

| Reason for Change/Modification: | **Explanation or Reason:** |
|---|---|
| ☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Attachments:** ☑ Yes ☐ No<br>Site 163 Figure 2 |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>NA |
| **Honeywell (AP) Review:** | |
| **Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 1/14/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





NOTE: AREA NORTH OF PROPOSED EXCAVATION PREVIOUSLY COMPLETED AND BACKFILLED WITH CLEAN IMPORTED MATERIAL OR HISTORIC FILL (<20 PPM HEX CR)





SECTION A−A'





SECTION B−B'




SECTION C−C'




SECTION D−D'




SECTION E−E'

LEGEND

- PDI BOTTOM SAMPLE LOCATION
- PDI SIDEWALL SAMPLE LOCATION
- OVERBURDEN (<20 PPM HEX CR)
- CHROMIUM IMPACTED SOIL (20−240 PPM HEX CR)

**NOTES:**

1. HONEYWELL WILL EXCAVATE THE AREA DEPICTED ON THIS FIGURE AND IS PLANNING LOGISTICS WITH IT'S CONSTRUCTION MANAGEMENT TEAM AND REMEDIAL CONTRACTOR(S).
1. UNDER THE EXCAVATION SCENARIO, HONEYWELL WILL CONTINUE TO EVALUATE USING SHEETPILE FOR TEMPORARY EXCAVATION SUPPORT, BACKSLOPING, OR A COMBINATION OF BOTH.
2. OVERBURDEN MATERIAL WILL BE EXCAVATED, STOCKPILED, AND HANDLED IN ACCORDANCE WITH THE APPROVED SOIL MANAGEMENT PLAN IN THE 100% DESIGN.
3. CHROMIUM−IMPACTED MATERIAL WILL BE EXCAVATED, STOCKPILED, AND HANDLED IN ACCORDANCE WITH THE APPROVED SOIL MANAGEMENT PLAN IN THE 100% DESIGN.
4. BACKFILLING WILL OCCUR UPON VERIFICATION BY INDEPENDENT THIRD PARTY LICENSED LAND SURVEYOR THAT HORIZONTAL AND VERTICAL EXTENTS OF EXCAVATION HAVE BEEN ACHIEVED.
5. HONEYWELL MAY IMPLEMENT THIS EXCAVATION BY THE END OF 2015.
6. HONEYWELL MAY ELECT TO USE A CONTRACTOR OTHER THAN ENTACT TO IMPLEMENT THIS EXCAVATION ACTIVITY.
7. THE PROPOSED EXCAVATION FOOTPRINT IS 6,335 SF AND 5 BOTTOM SAMPLES SATISFIES THE NJDEP APPROVED FREQUENCY OF 1:1300 SF AS IDENTIFIED IN THE 100% DESIGN REPORT.

Prepared/Date: TDD 9/22/15
Checked/Date: DEN 9/22/15

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2529

SITE 163 - ADDITIONAL
CHROMIUM EXCAVATION AREAS
FIGURE 2

C:\Denover\SA−6 South Excavation Limits April 2012\2013 Excavation Shapes\SA−6 South Design Change Bulletins\Site 163 Excavation Shpfls 163 Additional Excavation Areas.dwg Thu, 24 Sep 2015 − 3:09pm tony.dunsmore

**FINAL DCB 050 – WARNING TAPE ABOVE ROOT BARRIER**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 50 **DCB Type:** Minor (a)<br>**Effective Date:** 10/02/15 |
| **Project Location:** SA-6 North and South | **Associated RFI:** |
| **Title:** Warning Tape above Root Barrier | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** ENTACT installed warning tape above the geocomposite drainage layer (GDL), as called for in Drawings C-301 and CN-301. As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope.

The warning tape will be the same tape used above the orange GDL warning fabric, i.e. a 6 inch wide yellow PE tape with 3.5 inch bold back lettering which meets the specified requirements for a distinctive colored high-visibility marking. The tape will be placed at no more than 5 ft. on center.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>**Attachments:** ☐ Yes ☑ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 10/2/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**FINAL DCB 055 – USDA CLASSIFICATION**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 55 **DCB Type:** Minor(a)<br>**Effective Date:** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Planting Soil Gradations USDA Clarification | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than USCS.

The ASTM methodology, which includes hydrometer, remains the same, with the exception that a #270 sieve should be added to align with the USDA classification of silt at 0.05 mm.

The laboratory reports should clearly designate that the classification is based on USDA and any values stated for Gravel/Sand/Silt &Clay should also be calculated based on the USDA analysis.


The Specification values for the Horizon A, Horizon B and Horizon C soils are all defined based on the USDA Soil Classification. When calculating the Sand, Silt and Clay percentage, the Gravel component (% retained on the #10 sieve), should be removed from the calculation.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Otherp | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No<br>USCS and USDA Classification Comparison |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>NA |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 4/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# USCS vs. USDA Particle Size Comparison

## USDA Soil Classification System




## Unified Soil Classification System

OhioEPA

**FINAL DCB 057 – NATURE'S CHOICE – HORIZON C ONLY**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 057 **DCB Type:** Minor (a)<br>**Effective Date:** 03/21/16 |
| **Project Location:** SA-6<br>**Title:** Planting Soil Specifications (Nature's Choice - Horizon C ONLY) | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** Revisions to the Horizon C planting soil specifications for the Nature's Choice Horizon C Soil Source Only. | |
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See additional comments<br>**Attachments:** ☑ Yes ☐ No<br>Laboratory reports of chemical analysis<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the Parties. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DCB 046. | **Design Documents Affected:**<br>Specification 02315, Section 2.12.C<br>Open Space Design Standards, Section 2.1.2 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 4/26/2016 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# Attachment A – Supplemental Requirements for DCB 057

During the March 17 teleconference, Honeywell explained that the proposed material would come from an excavation pit (with concentration characteristics similar to those from which data was previously collected). Based on the information provided by Honeywell, plaintiffs will accept Honeywell's proposal to use the Nature's Choice material as Horizon C soils at Study Areas 6 North and South so long as Honeywell agrees to the following conditions:

1. Plaintiffs' agreement to use soils in excess of the 100% Design 1 ppm hexavalent chromium standard is limited to the Nature's Choice materials in question for use as Horizon C soils and is not a modification of the 100% Design standards as they apply to any future fill, repair or restoration work. This limited deviation from the 100% Design is set forth in this Design Change Bulletin.

2. The Nature's Choice materials shall contain less than 1.8 mg/kg hexavalent chromium. In addition, Honeywell shall use best efforts to maintain an average hexavalent chromium concentration as estimated based on the upper limit of the $95^{th}$ percentile confidence interval around the mean of 1.1 mg/kg in the Horizon C soils.

3. The Nature's Choice materials shall be sampled for hexavalent chromium no less frequently than once every 5,000 cubic yards. Hexavalent chromium sampling shall use composite samples that are made up of a minimum of 10 grab samples. The grab samples shall be collected as evenly as possible throughout the volume of material being sampled to ensure true representation of the hexavalent chromium concentrations coming onto the Study Area 6 sites.

4. All other sampling and analysis protocols will follow the customarily used NJDEP and USEPA protocols. To be consistent with the NJDEP protocols, one of the individual 10 grab samples will be used for all other required analytical parameters (VOCs, SVOCs, metals, etc.) to demonstrate compliance with clean fill requirements.

**FINAL DCB 058 – SA-6 SOUTH CP TEMP CONSTRUCTION ROAD**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 058 **DCB Type:** Minor (a)<br>**Effective Date:** 5/6/16 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Temporary Construction Road in SA-6 South Cap | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor.

The Chromium Remedy Design indicates that the Open Space AOC will be finished with topsoil and be seeded. Section 2.2.1.B of the Open Space Design Standards ("OSDS," Appendix L of the SA-6 North 100% Design Report) was written in anticipation of the need for "temporary construction roads" across the cap, post Chromium Remedy completion, and prior to construction of the final redevelopment roads. These construction road(s) will initially be used to provide access for general site inspections, access for the long term monitoring plan and maintenance activities such as mowing.

The roads will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade". The Topsoil shown within the construction road limits would be replaced with a load bearing geotextile (min 8 oz. non-woven) and 6 inches of Dense Grade Aggregate consistent with the OSDS "temporary construction road" requirements.

Table I of the OSDS was developed to show the minimum cover requirements for specific traffic loading conditions. The analysis supporting Table 1 was shared with the Plaintiffs during development of the OSDS. These communications were documented in Response to Plaintiff's Comments dated 07/13/2012. The calculation provided indicates that a 36 inch cover was adequate to provide protection of the cap when subject to H20 truck loading. When graded to the Chromium Remedy grades the typical fill depth in "B Street" is 8 ft. (OSDS Figure 4I is attached for reference). At the northern end of B Street, as the remedy surface transitions into SA-7, the minimum depth is 4 ft. These conditions meet the 36 inch cover requirement stated in Table 1.


The road as constructed during the Chromium Remedy will therefore meet Section 2.2.1.B of the OSDS.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>**Attachments:** ☑ Yes ☐ No<br>Table 1 (Page 20 of OSDS); Section 2.2.1.B of OSDS (pages 24 – 25); Figure 4I<br>Cost Implication: ☐ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☐ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 6/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

NOTE:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND
3. EXISTING ASPHALTIC PAVEMENT AREAS TO BE FIELD INSPECTED BY LSRP DURING RESTORATION ACTIVITIES. FINAL HISTORIC FILL CAP IN THESE AREAS MAY INCLUDE CRACK FILLING OR INSTALLING A GRAVEL COVER SYSTEM.




| | |
|---|---|
| SHEET | 33 OF |
| DWG | C-128 |
| PROJ | 3480-12-0317 |
| DATE | |

BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"

VERIFY SCALE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization 24GA28010900


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

RESTORATION PLAN

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 4 | 6/20/16 | DCB 30.2 - ROAD B ACCESS GRADING | TDD | SGS |
| 3 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 2 | 05/06/15 | REVISED EDGE DETAIL | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |


| DSGN | DR | CHK | APVD |
|---|---|---|---|
| TDD | RJR | TDD | SHM |


SAMUEL G. SHALLARD
6/21/16
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.





FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR33-C-128 Surface Restoration Plan.dwg PLOT DATE: Mon, 20 Jun 2016 PLOT TIME: 2:15 PM




CONSTRUCTION ACCESS ROAD DETAIL
NTS
(TOP PLATEAU)




CONSTRUCTION ACCESS ROAD DETAIL
NTS
(APPROACH SLOPE)

0 10 20 40
HORIZONTAL SCALE FEET

0 4 8
VERTICAL SCALE FEET

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Cap Grading\C-128A Cap Access Road.dwg PLOT DATE: Mon, 25 Jul 2016 PLOT TIME: 12:26 PM

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 0 | 7/25/16 | 30-65 temp Const Road Details | TDD | SGS | SGS | TDD |
| DSGN | TDD | | TDD | | | |

Honeywell
101 COLUMBIA RD. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134,
140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

CONSTRUCTION ACCESS ROAD
FUTURE B STREET

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, N.J. 08619
(609) 689 - 2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON
ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-128A |
| SHEET | 33A OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Table 1: Allowable Ground Pressure versus Fill Depth**

| Maximum Ground Pressure | Fill Depth Over Warning Layer/Liner |
|---|---|
| **Maximum Ground Pressure for Maintenance Equipment** | |
| < 5 psi | 12 inches |
| 5-10 psi | 18 inches |
| >10-40 psi | 24 inches |
| | |
| **Additional Maximum Ground Pressure for Temporary Roads** | |
| Fully Loaded Highway Truck (>40-80 psi) | 36 inches |
| | |
| **Permanent Roadways** | |
| No maximum ground pressure limit | 36 inches |

The load limits on temporary roads and on Landscape and Hardscape Areas allow for heavier loads where a rigid pavement or temporary load spreading system such as matts is used to spread the load and reduce the bearing pressures to below the limits specified in Table 1, and where a licensed New Jersey Professional Engineer has certified to Honeywell and Jersey City that the rigid pavement or temporary load spreading system will reduce the bearing pressures to below the limits specified in Table 1.

## E. Bearing Area – Foundations, Footers and Separation from Cap

1. Each point load from a Permissible Development Element shall have a minimum bearing area of 2 square feet except that traffic light poles and street light poles shall have a minimum bearing area of 3.5 square feet.
2. Each Permissible Development Element requiring a footer shall have a shallow footer.
3. Anchoring systems for Permissible Development Elements such as site furnishings shall be designed for surface mounting on spread footings. Hardscape areas shall accommodate surface mounted anchoring on spread footings.

Remedy and such certification will be included in a Development Plan reviewed and approved by the Special Master or the Federal Court. No curb and pavement box design shall be certified or approved unless it is demonstrated that it will not jeopardize the integrity of the Chromium Remedy.

8. Through trucks are prohibited on Roadways. Roadways shall be posted to prohibit through trucks. Jersey City shall prohibit through trucks and require the posting of such prohibition in an ordinance prior to the installation of the Roadways. The standard becomes effective upon the effective date of a Jersey City ordinance prohibiting through trucks on Roadways.

9. Every five years from the initial surfacing, a licensed New Jersey Professional Engineer shall inspect all Roadways in the Open Space Areas to evaluate whether the condition of any Roadway or segment thereof has compromised or is likely to compromise the structural integrity of the underlying subgrade or utilities. Within 30 days of the completion of the inspection, the licensed New Jersey Professional Engineer shall submit a certified report to Honeywell and Jersey City that describes the inspection undertaken and the repairs needed, if any, in order to address any condition that has compromised or is likely to compromise the structural integrity of the underlying subgrade or utilities. Within 18 months of the submission of the report, the repairs described in the report shall be completed. In the event that in the report the licensed New Jersey Professional Engineer deems a condition to constitute an emergency requiring immediate repair, such repair shall be made as soon as possible, and, if necessary, interim measures shall be employed to protect the cap, subgrade and utilities. Within 60 days of completion of the repairs, emergency or otherwise, a licensed New Jersey Professional Engineer shall inspect the repairs and certify that the repairs have been satisfactorily completed.

**B. Temporary Construction Roads**. The following requirements apply to all temporary construction roads:

1. In the event temporary construction roads are installed, these roads shall be limited to the locations designated for Roadways in the 100% Design on Drawings CN-515 and C-516. Temporary roads shall be installed using a load bearing geotextile fabric to isolate the wearing surface from the

subgrade. A wearing surface shall be installed that is sufficient to handle the intended temporary traffic loadings. Temporary roads shall be designed consistent with the projected loads and frequency. Temporary roads shall be designed to be protective of the Chromium Remedy. A licensed New Jersey Professional Engineer shall certify that the temporary road design is protective of the Chromium Remedy and such certification shall be included in a Development Plan reviewed and approved by the Special Master or the Federal Court. No temporary road design shall be certified or approved unless it is demonstrated that it will not jeopardize the integrity of the Chromium Remedy.

2. The load limitations specificed in Section 2.1.4.D of the OSDS and Section 02374 Part 3.3 G 7 of the Technical Specifications shall apply to all loads on the temporary roadways.

### *2.2.2 Hardscape Areas including Pedestrian Thoroughfare*

Hardscape Areas shall have a minimum separation of 12 inches between the Warning Layer/Liner and the underside of the hard surfacing. The surface and subgrade materials shall be of sufficient strength to accommodate Maintenance Equipment.

### *2.2.3 Utilities*

All utilities including those supporting the pump and treat system for groundwater remediation, with the exception of any extraction wells or collection trenches, shall be placed above the Cap as required in Paragraph 56(b) of the Study Area 6 North Consent Decree.

### *2.2.4 Utility Corridors*

**A. Public Utilities.** All public utilities shall be located in a designated utility corridor and shall be installed in accordance with Paragraphs 60(j)(v)(6) and (7) of the Study Area 6 North Consent Decree. The location of the utility corridors is shown on Drawing CN-515 of the Study Area 6 North 100% Design and C-516 of the Study Area 6 South 100% Design. During the Initial Development Period, the modification of designated utility corridors or the designation of additional utility corridors, if necessary shall be subject to the review and approval of Honeywell, Jersey City, and the Special Master.

MATCH LINE VIEW BELOW

GRAND BLVD.

C STREET

D STREET

SA-7 SLURRY WALL

FRONTAGE

STREET

HYDRAULIC BARRIER

GRAND BLVD.

SA-7 SLURRY WALL

GRAND BLVD.

RIVERSIDE DRIVE

A STREET

B STREET

HYDRAULIC BARRIER

MATCH LINE VIEW ABOVE

| Depth to Liner Table | | |
|---|---|---|
| Minimum Depth | Maximum Depth | Color |
| 2.0 | 2.5 | |
| 2.5 | 3.0 | |
| 3.0 | 4.0 | |
| 4.0 | 4.5 | |
| 4.5 | 14.6 | |

LEGEND

- HARD SCAPE
- SIDEWALK
- MAJOR TREES
- MIONOR TREES
- SA-7 SLURRY WALL
- HYDRAULIC BARRIER

Prepared/Date: RJR 06/09/13
Checked/Date: SGS 06/09/13

0 20 40 80
SCALE IN FEET

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

OPEN SPACE DESIGN STANDARDS
CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

PROMENADE
LANDSCAPING AND SOIL SPOT
DEPTHS TO WARNING LAYER/LINER
Figure 4I

Z:\Projects\HONEYWELL\JERSEY CITY\Dwg Design-SA6-CSD\DAS\DAS\Figure 4I Landscaping Depths.dwg Thu, 06 Jun 2013 - 2:49pm roger.fiedler

**FINAL DCB 059 – HORIZON B AND C SOILS**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 059 **DCB Type:** Minor (a)<br>**Effective Date:** 4/20/16 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Planting Soil Specifications | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description**. Planting Soil Source Acceptance Variance for Select Horizon B and C Soils.

DCB-046 expanded the ranges of acceptable physical parameters (gradations, pH and organic content) in Horizon B and C soils that were included in the Earthwork Specification 02315. DCB-046 was accepted by all Parties and Specification 02315 was revised accordingly.

Subsequent to the acceptance of DCB-046, Entact encountered difficulty locating available Horizon B and C sources that comply with the revised Specification and meet hexavalent chromium design criteria of 1 mg/kg or less.

This DCB-059 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. Based on the agreement, Honeywell will proceed to import fill material from suppliers as noted below to support the project needs for Horizon B and Horizon C soils to meet the demands for fill quantity and schedule for cover soils on SA-6 South and North.

It is noted that an exhaustive search of potential sources resulted in a short list of potentially viable Horizon B and C sources being recommended, following consultation with Dr. Grabosky who provided his recommendations in correspondence dated March 17, 2016. Dr. Grabosky's recommendation is attached and made part of this DCB. The specific sub set of soil sources agreed to by all parties is as follows:

| Horizon B Approved Sources | Horizon C Approved Sources |
|---|---|
| Cedar Hill | Natures Choice (Per DCB-057) |
| EME - B001 | Impact - AB33 |
| Impact - AD17 | Impact - AD25 |

**DCB-059 applies to the completion of importing soils for SA-6 North and South grades as presented in the 100% design and does not permanently change the Earthwork Specification 02315 for physical parameters (gradations, pH and organic content) in Horizon B and C soils that were memorialized in DCB-046.**

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>**Attachments:** ☑ Yes ☐ No<br>Dr. Jason Grabosky letter (3/17/16)<br>Plaintiffs' letter dated 04/15/16.<br>Cost Implication: ☐ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☐ No |
| **Additional Comments:** See DCB-057 for acceptability conditions of Nature's Choice Horizon C soils. | **Design Documents Affected:**<br>Specification 02315, Section 2.12 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 4/26/2016 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# DR. JASON GRABOSKY RECOMMENDATION

RUTGERS
School of Environmental and Biological Sciences

Urban and Community Forestry Program
Dept. of Ecology Evolutionand Natural Resources
Environmental and Natural Resources Bld, Room 144
Rutgers, The State University of New Jersey
14 College Farm Road
New Brunswick, NJ 08901-8551

March 17, 2016

To all concerned:

I spoke on the phone with Geoff in between meetings during the past week. For all concerned, there was a delay in this set of conversations due to some snags in our e-mail communications (I was not getting e-mails through my server for some reason), but we developed some work arounds to share the soils tables under review and spoke during a brief conversation on Tuesday Morning from 8:00-8:15 a.m. once I had the soils tables in front of me while chatting over the phone.

There are issues with the Nature's choice source, in terms of supply and in terms of some testing results. For that reason, it has been necessary to identify alternative Horizon B and Horizon C sources. To reduce risks in material supply, chemistry and gradation, I have identified multiple sources/mixes for both Horizon B and Horizon C. In making specific recommendations I also considered both the expense of shipping, and the environmental cost (or the carbon footprint) in shipping, and the limitations in time management from the haulage/transportation logistics.

**Horizon B:**
In a technical sense, Nature's choice remains an approved and acceptable layer B material. However, there is an open question of availability of material in the volume needed for project execution.

The Cedar Hill material can fit the B Layer source designation. Clay is at 10% right at the lower end of the clay specification. As discussed with Geoff Shallard, in an engineering/drainage view, this is a good material. We would also have to consider a lower the min clay value in the specification to account for variability. The pH of this material (6.22) seems to be in line with the goals for the specification. Given a concession in lowering the clay content also opens consideration of the Impact Materials.

Impact AD17 : While the fines (silts and clays) are flipped from a best case scenario (and thus falling out of specification), the material would suit for the B horizon. In the clay component, this material is comparable to the Cedar Hill material. The silts exceed the specified maximum percentage. However, this maximum is largely in consideration of frost heave susceptibility. For the depths of the B layer relative to expected frost penetration to depth in Jersey City, especially in consideration of all future climate predictions of warmer temperatures, the frost potential is deemed less critical. Indeed, the pH is a tad high, but not so much as to consider it unworkable from a horticulture management sense. The sand portion of the Impact AD17 blend (which is the bulk of the blend) sits 10 minutes away from the site in Kearny, NJ and therefore has a low carbon footprint and ease of logistics. Additionally, it may yield a continuum in similarity if the C horizon also is determined to come from an Impact source.

EME B001-HORB: The EME grouping of materials benefit from a high level of control, and would be considered a useful source ***if*** the material could lower the organics to <4. Given the systems in question,

there is every possibility of shrinkage over time as the OM degrades, which could have negative impacts on the final developed site. A principal detraction of this source would be distance (about 65 miles), both in expense in shipping, the environmental cost (or carbon footprint if you will) in shipping from and the limitations in time management from the haulage/transportation logistics.

**Horizon C**

Impact AB33 and Impact AD25: While the fines (silts and clays) are flipped from a best case scenario (and thus falling out of specification), the materials would suit for the C horizon. pH is in line with the specification. I have a preference for the AB33 for the lower pH and slight increase in clay, but both would be suitable. Of the materials in the tables, a discussion with Geoff indicated the sands in the Impact materials are coarse and to our benefit in workability and drainage capacity, which for the level of construction traffic on site, works toward the stability of the system in a physical-mechanical sense. The sand portion which is the bulk of the Impact blends also is located in Kearny, NJ and therefore has a low carbon footprint and ease of logistics.

EME B002-HORC: The EME grouping of materials benefit from a high level of control, and would be considered a useful source ***if*** the material could lower the organics to <4. Given the systems in question, there is every possibility of shrinkage over time as the OM degrades, which could have negative impacts on the final developed site. A principal detraction of this source would be distance (about 65 miles), both in expense in shipping, the environmental cost (or carbon footprint if you will) in shipping from and the limitations in time management from the haulage/transportation logistics.

**Recommendations:**
I would retain EME as a Vendor option for both Horizon B and Horizon C with an assumption the organic fractions can be reduced. While the materials seem very good, the costs likely outweigh the advantages for the B and C horizons. The vast majority of the plant root systems are in the A horizon, thus the goals for the lower levels are about support, drainage and depth/distance to cap. Given the timing and the difficulty associated with getting materials into conformance I make the following recommendations. Pragmatically, one might argue I am siding on convenience. However, upon the consideration of developing a system, I feel what we develop from the recommendations provides a working solution, albeit with a higher system pH than originally targeted. The plant palette was chosen to bias toward shallower rooting species, and the higher ph will encourage the proliferation of roots where the mineral nutrition is available, which biases toward the surface with the increased pH of the lower layers. We provide a loamy-sand to sandy loam transition in the b to c horizon depths, which would provide a continuum for the water column through the layers provided compaction of each layer is not excessive and the interface blending described in the early documentation occurs. The increase of pH does not place the plant species selected into peril to my knowledge.

I would recommend:

Horizon B soils:

Adopt Impact AD17% as the primary source, and Cedar Hill as the secondary source. To accomplish this in specification language, adjust the B layer % Silt to <15% and % Clay to 5-15%. Raise acceptable pH to 7.6 from 7.5 or figure out how to lower the AD17 pH in the mix process.

RUTGERS
School of Environmental
and Biological Sciences

Horizon C soils:

Adopt Impact AB33% as the primary source. To accomplish this in specification language, adjust the C layer % Silt to <15% and % Clay to 5-15%. Retain the Impact AD25 as an alternative to Impact AB33%.

Respectfully submitted,



Jason Grabosky
John and Eleanor Kuser Faculty Scholar in Urban and Community Forestry
Director: S.E.B.S. General Honors Program
Co-Director: Center for Resilient Landscapes, a USDA FS/Rutgers Joint Venture
Editor-in-Chief; Arboriculture & Urban Forestry
Department of Ecology, Evolution and Natural Resources

**PLAINTIFFS' RESPONSE LESTTER (4/15/16)**

BRUCE J. TERRIS
CAROLYN SMITH PRAVLIK
KATHLEEN L. MILLIAN
ALICIA C. ALCORN
ZENIA SANCHEZ FUENTES
PATRICK A. SHELDON
TODD A. GLUCKMAN

**TERRIS, PRAVLIK & MILLIAN, LLP**
1121 12TH STREET, N.W.
WASHINGTON, D.C. 20005-4632
(202) 682-2100
FAX 202-289-6795
tpminfo@tpmlaw.com

MICHAEL L. HUANG
NICHOLAS SOARES
BENJAMIN S. DAVIS
STEPHANIE ANN MADISON

LYNN E. CUNNINGHAM
Of Counsel

April 15, 2016

VIA ELECTRONIC MAIL

Jeremy Karpatkin
Arnold & Porter, LLP
Thurman Arnold Building
555 12th Street, N.W.
Washington, DC 20004-1206

Re: Study Areas 6 North and South – DCB 2016-3-18 Horizon B and C Soil Specifications

Dear Jeremy:

We write to provide plaintiffs' position with respect to the Design Change Bulletin (DCB) DCB 2016-03-18 that seeks to modify the geotechnical specifications for Horizon B and C soils, which the parties previously modified in September 2015. We note that, like the September 2015 modification, the current proposal of Honeywell would apply to all Horizon B and C soils to be brought to the site, not just in the initial phases of development, but permanently. As set forth in the 100% Design and the Open Space Design Standards (OSDS), there is to be a distinction between the characteristics of the soils in Horizon B and Horizon C to ensure the growth of only appropriate types of vegetation and trees on top of the cap, so as not to endanger the cap. *See* Technical Specification 2315 Earthwork, 2.12 Planting Soils; OSDS 2.1.2 Restrictions on the Use and Placement of Fill, Subsection D Specific Requirements for Fill Soils in Landscaped Areas.

On April 7, 2016, plaintiffs requested additional information regarding the planned schedule for the importation and use of the Horizon B soils. Honeywell provided the requested information on April 12, 2016. Plaintiffs and their experts have reviewed the April 12 response. Plaintiffs agree with Honeywell's analysis that Horizon B soils may be imported and placed now in the Study Area 6 South Open Space, and that Horizon B soils cannot be placed in the Study Area 6 North Open Space until the redevelopment.

Plaintiffs understand that Honeywell wishes to have multiple sources of Horizon B and C soils available for use so that it will not incur delays such as those incurred this winter with respect to Horizon C soils. However, Honeywell is proposing to change permanently the geotechnical specifications for both Horizon B and C soils based on the analysis by Dr. Grabosky of particular sources for the Horizon B and C soils. Dr. Grabosky's analysis establishes that the particular soil sources that he recommends, based upon the potential sources

provided to him by Honeywell, will maintain the necessary distinction between the soil horizons even though the recommended sources may deviate slightly from the geotechnical specifications as modified in September 2015.

Based upon the recommendations of Dr. Grabosky as set forth in his correspondence of March 17, 2016, which was included with DCB 2016-03-18, as set forth below, plaintiffs will agree to the use at Study Area 6 of certain particular sources for Horizon B and C soils addressed by Dr. Grabosky, even though some of the sources may deviate slightly from the geotechnical specifications in the 100% Design for Horizon B and C soils. However, plaintiffs are not willing to agree to modify permanently the geotechnical specifications for the Horizon B and C soils of the 100% Design standards to accommodate use of the sources for Horizon B and C soils under consideration by Honeywell at this time.

Plaintiffs agree to the use of Horizon B soils for the Study Area 6 North and South Open Space areas from Nature's Choice, Cedar Hill, and EME (EME-B001 blend) because these sources meet the geotechnical specifications. In addition, plaintiffs agree to the use of Horizon B soils from Impact Environmental, which deviate from the geotechnical specifications, as a secondary source should the Nature's Choice, Cedar Hill, and EME (EME-B001 blend) soils not be available. Plaintiffs do not agree to the use of the EME (Horizon "B" Modified) soils because of the high organic material content of the soils.

Plaintiffs agree to the use of Horizon C soils for the Study Areas 6 North and South Open Space areas from Nature's Choice as set forth in DCB 2016-03-21. In addition, plaintiffs agree to the use of Horizon C soils from Impact Environmental (Impact AB33 and Impact AD25), which deviate from the geotechnical specifications, as secondary sources should Nature's Choice not be available. Plaintiffs do not agree to the use of the Horizon C soils from EME because Dr. Grabosky did not recommend the use of these sources and because of the high organic material content of those soils.

Plaintiffs' agreement to the use of certain Horizon B and C sources that deviate from the geotechnical standards, as set forth above, is not an agreement to modify the 100% Design standards as they apply to any future fill, repair, or restoration work. This more limited agreement to deviate from the 100% Design should be set forth in a modified Design Change Bulletin.

Please contact me with any questions. We look forward to your response.

Sincerely,



Bruce J. Terris
Kathleen L. Millian
Alicia C. Alcorn
*Counsel for Plaintiffs*

cc: Senator Robert Torricelli
Tom Lewis/Steve Egnaczyk
Michael Daneker
William Hague
John Morris
Kevin Coakley/Liza Walsh/Agnes Antonian
Jeremy Farrell/Jason Watson/Bhavini Doshi
Frank Borin/Kevin Kinsella
Davis Isabel/ Eric Tomaszewski

**FINAL DCB 060 – REVISED DRAWING C-310**

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN


| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 060 **DCB Type:** Minor (a)<br>**Effective Date:** 5/31/16 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Revised Drawing C-310 | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

Updated Drawing C-310 (Rev. 5, 5/31/16) is attached. The drawing documents the vault sketch transmitted to Entact on 5/20/16.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No<br>Drawing C-310 |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 6/15/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)

NTS

C-203 C-204 C-310

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |

NOTE:

INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

- SET MANHOLE BASE AND RISER SECTIONS. (NITC)
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

NOTE:

1. FIELD SHIM WITH TOPSOIL TO GRADE UP TO THE TOP OF THE COVER.
2. USE PREVIOUSLY DELIVERED COVER BY PRECAST MANUFACTURING CO. DATED 4/16/14 STOCK# ATH3050D.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 5 | 05/31/16 | REVISION TO VAULT DCB 007.4.1 | TDD | TDD | APVD | SGS |
| 4 | 05/20/16 | DCB 007.4 | TDD | TDD | | SGS |
| 3 | 08/14/15 | DCB 007.3 | RJR | SGS | | SGS |
| 2 | 02/02/15 | DCB 007 | TDD | SGS | | SGS |
| 1 | 06/06/14 | | TDD | SGS | | SGS |

DSGN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR46-C-310_Cont_GWE_Trench_Details.dwg PLOT DATE: Tue, 31 May 2016 PLOT TIME: 2:02 PM

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 20 OF 25**

- **Initial Declaration #1**

CHROMIUM REMEDY
SA-6 SOUTH

INITIAL DECLARATION #1

**UNITED STATES DISTRICT COURT**
**DISTRICT OF NEW JERSEY**

JERSEY CITY INCINERATOR AUTHORITY,

Plaintiffs,

v.

HONEYWELL INTERNATIONAL INC., et al.,

Defendants.

Civil Action No. 05-5993 Consolidated with Docket No 05-5955 under Docket No. 95-2097 (DMC)
Civil Action No 06-22 Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097

Civil Action No. 06-0022 (JLL)
(Consolidated under Civ. No. 05-5955 (JLL))

Initial SA-6 South Consent Decree Declaration

On August 14, 2012, the USDC DNJ entered into the First Amended Consent Decree Regarding Remediation and Redevelopment of Study Area 6 South ("SA 6 South Consent Decree"); pursuant to Article III, Honeywell may file one or more Declarations showing compliance with said SA 6 South Consent Decree. The Initial SA 6 South Consent Decree Declaration is filed by Honeywell with the consent of the other parties to memorialize Honeywell's partial compliance with the terms of the SA 6 South Consent Decree.

We, the undersigned, declare as follows:

1. William J. Hague, Director of Remediation Design and Construction for Honeywell International Inc. ("Honeywell") for Study Area 6 South (SA-6 South) New Jersey Department of Environmental Protection (NJDEP) Sites 073, 124, 125, 134, 140 and 163. Mr. Hague has direct responsibility on behalf of Honeywell for the management of remediation construction activities at SA-6 South related to the implementation of the Chromium Remedy as defined in Article III of the First Amended Consent Decree Regarding Remediation and Redevelopment of Study Area 6 South, filed August 14, 2012 ("Consent Decree"). Remediation and site restoration activities were performed in accordance with the Consent Decree, the NJDEP Technical Requirements for Site

Remediation, and the NJDEP-approved *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan for Chromium* to address chromium contamination at SA-6 South, dated December 23, 2008; NJDEP-approved *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan,* to address chromium contamination at Site 163 only, dated, May 18th 2012 (collectively referred to as the RAWPs), the SA-6 Chromium Remedy 100% Design Report dated June 28, 2013 ("100% Design"); and the 5 field changes that materially impacted the 100% Design, listed on page 4 and 5 of this Declaration (referred to herein as "Related Field Changes") with the continued oversight and supervision of the appointed Special Master. The SA-6 Chromium Remedy 100% Design, including Design Drawings and Technical Specifications was developed consistent with the Consent Decree and NJDEP-approved RAWPs and was approved by all Parties. On June 12, 2013, the Special Master approved the SA-6 100% Design for submittal to the Court so that the proposed implementation of the remedy could start on time, subject to Honeywell's confirmation regarding several issues. On June 28, 2013 Honeywell submitted the Final 100% Design Submittal for the Study Area 6 North and South projects ("Final 100% Design").

2. The elements of the remedy that are the subject of this Declaration were substantially completed between July 2013 and March 31, 2015.

3. This is an initial Declaration. Future Declarations will document the work on the elements of the remedy set forth in the Consent Decree implemented or completed after March 31, 2015.

4. To implement the requirements of the Consent Decree, Honeywell retained AMEC Environment and Infrastructure, Inc. (now Amec Foster Wheeler) to design and coordinate the construction activities related to the Chromium Remedy of SA-6 South. Amec Foster Wheeler is the Engineer of Record for the design and implementation of construction activities related to the Chromium Remedy of Study Area 6 South. Mr. Joseph T. Clifford is a licensed Professional Engineer in the State of New Jersey, a Principal Engineer (Professional Engineer, NJ, GE38067) at Amec Foster Wheeler and is the engineer at Amec Foster Wheeler with primary responsibility for management of the design and construction coordination activities at SA-6 South.

5. For planning and implementation purposes, the work was divided into the following elements; excavation, barrier wall installation, backfill activities and soil management. Based on our professional opinion, the data and information set forth for the specific work elements noted in and attached to this Declaration -- excavation, barrier wall installation, backfill activities and soil management -- were performed consistent with the 100% Design and Related Field Changes.

Declaration #1 pertains to the following elements of the SA-6 South Chromium Remedy.

I. Excavation

II. Barrier Wall Installation

III. Backfill Activities

IV. Soil Management

Further details related to elements I-IV are provided below.

Supporting Documentation is provided in the Attachments.

Excavation. This Declaration addresses excavation of soils at SA- 6 South containing hexavalent chromium at levels greater than 20 milligrams/kilogram ("mg/kg") to meet the requirements of Paragraphs 59(a), (b) and (c) of the Consent Decree during the period of October 22, 2013 through December 22, 2014. SA-6 South was divided into two general areas as defined in the Consent Decree: the "Open Space Area of Concern (AOC)" and the "Development AOC".

Pre-Design Investigation (PDI) sampling and analytical results delineated the lateral and vertical limits of excavation and 156 15-foot wide cells were established to subdivide the SA6 South excavation for tracking and reporting. This PDI program was based on standards and conditions set forth in the RAWP, which was approved by the NJDEP, and supplemental discussions held during a January 11, 2012 meeting with the NJDEP wherein sampling frequency was discussed. The PDI sample results established the original depth(s) of excavation for an excavation cell or general area, with the understanding that if Stratum D (i.e., "meadow mat") was encountered or if other field conditions impacted achieving the design excavation depth, the excavation may be halted at a shallower depth.

Honeywell conducted the excavation operations as detailed in the SA-6 South Standard Operating Procedure (SOP) - Confirmation of Excavation Limits, dated March 3, 2014 (and including Honeywell's April 24, 2014 letter and attachments). In addition, Honeywell collected the survey data necessary to prepare a topographic map.

Following the excavation of distinct portions (or cells) of the excavation, the horizontal and vertical extents of the completed cells were surveyed and Honeywell submitted documentation confirming the completion of excavation. In their submittals, Honeywell summarized the activities undertaken to complete the excavation of the referenced cells as required by the 100% Design and included the following statement from Honeywell's engineer, Amec Foster Wheeler: "Amec inspectors certify to the best of our technical ability

that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling had been met." Honeywell also noted, where applicable/appropriate, that the excavation in the referenced cells terminated [by depth] in the Stratum D and provided an Excavation Bottom Map that included the surveyed post-excavation bottom elevations for the cell(s). In addition, Honeywell provided an updated figure depicting the 156 cells comprising the SA6 South excavation that was used as an excavation progress chart, attached a figure of the excavation cells, and included an excavation bottom map. Honeywell further requested approval to backfill cells. During the course of the excavation, the Special Master acknowledged receipt of Honeywell's submittals and the notification that the contractor was ready to backfill the respective cells.

- The hexavalent chromium impacted soils in the SA-6 Development AOC were excavated so as to meet or exceed the lines and grades (i.e., lateral and vertical limits of excavation) established in the 100% Design and Related Field Changes. A topographic map of the bottom of the excavation is provided on the Drawing titled "SA-6 South As-Built Excavation Plan," Drawing No. C-111 – Excavation Plan (Attachment A-1) and prepared by R. Thomas Hugg NJ Professional Land Surveyor.
- The extent of Stratum D exposed by the excavation is also shown on the SA-6 South As-Built Excavation Plan, Drawing No. C-111 (Attachment A-1).
- The Limits of Excavation are shown on a drawing titled "Figure 1.1 - SA-6 South As-Built Limit of Excavation Map" (Attachment A-2).
- The horizontal and vertical limits of excavation were adjusted in several areas. The adjustments were documented in the following field changes that were submitted to Plaintiffs and the Special Master in the form of emails or Design Change Bulletins:
    - Proposed Bottom of Excavation Elevation (dated, 2013-12-12)
    - Increase Excavation from 3 to 4 feet Below Grade at Site 163 to Reduce In-Situ Treatment of Shallow Soils (dated, 2014-05-06)
    - Deferral of Concrete/Asphalt Berm along Bulkhead at Site 073 (dated 2014-5-19)
    - Deferral of Excavation along Bulkhead at Site 163 due to Unanticipated Subsurface Concrete and Steel Structures (dated, 2015-01-23)
- Excavation tables which document the PDI locations and depths and actual excavation depths are provided in Attachment B. Three sets of tables are provided. Attachment B-1 addresses the eastern portion of the main excavation area starting at Route 440 moving west. Attachment B-2 addresses the remainder of the main excavation area up to the "deferred Area" by the bulkhead. Attachment B-3 addresses the excavation areas at Site 163.

- Attachments B-1 and B-2 each contain three sets of tables. Tables 1.0 and 3.0 provide the coordinates of the PDI bottom and sidewall points and a comparison of the actual excavation depth and design depth at the established PDI locations. Table 2.0 tabulates the design elevation and final excavation elevation at the center points of the cells used for excavation control. Attachment B-3 includes Tables 1.0 and 3.0 (Table 2.0 is not included because the excavation cells were not extended into Site 163). The tables were prepared by R. Thomas Hugg, NJ Professional Land Surveyor.
- As presented in the 100% Design, the location of confirmatory analytical points developed during the PDI soil sampling were surveyed by a registered surveyor to verify that the excavation was carried to or beyond the confirmatory points. Attachments B-1 and B-2 provide a list of confirmatory points by cell and indicate the original coordinates and both the original and final grade elevations. An as-built figure of the excavation confirmatory points is provided as Attachment B-4.
- As demonstrated by completion reports prepared by Amec Foster Wheeler which have been periodically submitted to the Special Master, the bottom and lateral limits (and to the extent that an excavation cell bordered the perimeter barrier wall, the perimeter barrier wall as well) of each excavation cell were visually inspected by personnel from Amec Foster Wheeler for the potential presence of visible hexavalent chromium-impacted materials and/or any visually suspect ("anomalous") material. To the extent that additional hexavalent-chromium-impacted materials and/or visually suspect material were observed, Honeywell contractors conducted further removal activities until Amec Foster Wheeler inspectors were satisfied upon visual inspection that the materials had been removed and/or confirmation samples were collected to confirm that the requirements of the 100% Design for SA-6 South ("Approved Design") were met.
- Each cell identified in paragraph 3 has been excavated down to Stratum D or to the elevation indicated in the Approved Design. The bottom of excavation was surveyed by a New Jersey Licensed Surveyor and a plot of the survey results is included in Attachment A-1.

A drawing titled SA-6 South As-Built: Excavation Confirmation Points shows the PDI locations in plan view.

Items listed above will also be provided in the final Remedial Action Report.

I. Barrier Wall. The SA-6 South Chromium Remedy includes a containment system consisting of a vertical hydraulic barrier wall, a flexible geomembrane liner cap, and contingent groundwater pumping system. The vertical barrier wall "encloses" the Open Space AOC

utilizing the existing SA-7 Soil-Cement-Bentonite (SCB) Barrier Wall on the northern boundary and new steel sheet pile hydraulic barriers that have been constructed along the, southern perimeter of the Open Space AOC, the western perimeter (adjacent to the Hackensack River bulkhead), and along the eastern perimeter of the Open Space AOC (adjacent to Route 440). The steel sheet pile barrier wall was installed along the southern, eastern and western sides of the Open Space AOC and keyed into the meadow mat (Stratum D) or Stratum O to meet the requirements of paragraph 69(b) of the Consent Decree. Barrier wall driving commenced on August 15, 2013 and was completed on July 22, 2014. The barrier wall consists of welded pairs of sheets. The (connecting) field joints were sealed with a cement bentonite grout between Station 0+00 and Station 17+80 (east wall and eastern portion of south wall) and with hydrophilic sealant between Station 17+80 and Station 25+86 (west portion of southern wall and west wall).

- The Barrier wall was installed to the line and grade defined in the 100% Design and Related Field Changes.
- Field Change 2013-9-12, related to a minor straightening of the alignment and increase in cap area following acquisition of the "Boatyard Property" as part of Site 134.
- The top of the Barrier Wall is currently at the installed elevation consistent with temporary flood control and subgrade/surcharge requirements. The top of the wall will be trimmed to final elevations prior to cap deployment. The final elevations will be included in a supplemental Declaration.
- As-Built drawings of the Barrier Wall Plan and Profile are provided in Attachment C.

II. Backfill. Soil excavated from the Site is required by paragraph 67 of the Consent Decree to be replaced by backfill soil. Backfilling within the Open Space AOC includes the spreading/placing, compacting, and grading of onsite non-chromium impacted and chromium-impacted soils in accordance with the approved RAWP. Any backfill soil brought to the Site is required to either meet all applicable federal and NJDEP criteria, including NJDEP residential soil criteria, or comply with the beneficial soil reuse plan that is approved by the NJDEP and subject to review and comment by the Parties and approval by the Special Master.

- Compaction tables showing field compaction test results and a drawing showing test locations for work completed through March 31, 2015 are provided in Attachment D. Backfill compaction testing was performed as described in the SA6 South 100% Design, in accordance with the specifications set forth in NJDEP-approved SA 6 South RAWP and Soil Reuse Plan. The Final Site grading will be provided in a future Declaration.

- Drawing D-1 indicates the top of the backfill grade in the Development AOC as of March 31, 2015.
- Attachment D-2 comprises 5 drawings showing the locations of Backfill Compaction Test results conducted at the specified frequency of 1 test per 2,500 square feet of backfilled area. Attachment D-3 comprises tables summarizing Backfill Compaction Test results conducted at a reduced frequency of 5 tests per acre as provided for in the 100% Design Technical Specifications. If any area failed to meet the requirements for compaction, the area was reworked and retested. All test results are included. The final test result at every location met the specified compaction criteria.

III. Soil Management. Excavated soils were managed consistent with paragraph 59 of the Consent Decree from October 2013 through March 31, 2015. The Consent Decree provided for different soil management requirements for soils containing hexavalent chromium at concentrations greater than 20 mg/kg. The Soil Management Plan (SMP) (Appendix G of the 100% Design) establishes guidelines and the minimum requirements for the reuse and disposal of soil, concrete, and asphalt during the implementation of the chromium (and non-chromium) remedies at the Site.

Soils with a concentration of 1,000 mg/kg or greater of hexavalent chromium were removed from the site for disposal at Heritage Environmental Services, Indianapolis, in accordance with paragraph 59(a)i of the Consent Decree. Excavated soils with hexavalent chromium concentrations of 20-1,000 mg/kg were managed in accordance with the requirements of paragraph 59(b) of the Consent Decree. Petroleum contaminated soil containing less than 240 mg/kg and classified as non-hazardous was disposed at the Middlesex County Landfill and Bayshore Recycling or placed under the SA-6 South cap. Non-Hazardous mercury soil was disposed at the Middlesex County Landfill and Bayshore Recycling. Non-Hazardous Concrete was disposed of at the New Jersey Meadowlands Commission (NJMC).

The Summary of Soil Management Activities is tabulated in Attachment E. The Soil Management Activities table shows the disposition of the designated soil classifications, as defined by paragraph 50 of the Consent Decree, managed during excavation activities at SA-6 South as of March 31, 2015. Excavated soils used as subgrade fill and placed in the Open Space AOC were graded to the design subgrade following removal of the clean surcharge materials.

1. Based on our professional experience, the data and information set forth in and attached to this Declaration, and our supervision of the SA-6 South construction activities, we believe that hexavalent chromium-impacted materials greater than 20 mg/kg and as defined in the 100% Design have been removed from the excavated areas and areas on the perimeter barrier wall in the Development AOC in accordance with the Consent Decree and the Approved Design.

2. We certify that the foregoing is true and correct to the best of our respective knowledge.

William J Hague

Date March 2, 2016

Joseph P Clifford PE NJ, GE38067

Date March 7, 2016

**List of Attachments**

A. Excavation Limits

A1 – Drawing – SA-6 South As-Built Excavation Plan (Drawing No. C-111 – Excavation Plan)

A2 – Figure 1.1 - SA-6 South As-Built Limit of Excavation Map

B. Confirmatory Survey

B1 – SA-6 South Excavation Confirmatory Points (east)

- Table 1.0 – 1.8 PDI Locations
- Table 2.0 - 2.7 Center Points
- Table 3.0 – 3.2 Sidewall

B2 - SA-6 South Excavation Confirmatory Points (west)

- Table 1.0 – 1.8 PDI Locations
- Table 2.0 – 2.7 Center Points
- Table 3.0 – 3.2 Sidewall

B3 – SA-6 South Excavation Site 163

- Table 1.0 PDI Locations
- Table 3.0 Sidewall

B4 – Figure 1.2 - SA-6 South As-Built Excavation Confirmation Points

B5 – Figure 1.3 - SA-6 South Excavation Cell Layout

C. Drawings S-201, S-202, S-203 Hydraulic Barrier Plan & Profile

D. Backfill

D1 – Figure 2.1 - SA-6 South As-Built - Backfill Topographic Progress Map

D2 – Figure Backfill Compaction Locations BF-01 to B-45

Figure Backfill Compaction Locations BF-46 to BF-94

Figure Backfill Compaction Locations BF-95 to BF-136

Figure Backfill Compaction Locations RF-01 to RF-21

Figure Backfill Compaction Locations RF 22 to RF-39

D3 – Field Density Test Summary Log Table (Pages 1 to 7)

Field Density Test Summary Log Table (Pages 1 to 4)

E. Table Summary of Soil Management Activities

**ATTACHMENT A**

**EXCAVATION LIMITS**

**ATTACHMENT A-1**

**DRAWING – SA-6 SOUTH AS-BUILT EXCAVATION PLAN**

**(DRAWING NO. C-111 – EXCAVATION PLAN)**

FILE NAME: C:\Civil 3D Projects\320151\Survey\Y-SURV-SA6S-FINAL.dwg PLOT DATE: Wed, 14 Oct 2015 PLOT TIME: 11:42 AM




**GENERAL NOTES**

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW POST-EXCAVATION ELEVATIONS WITHIN THE SA6 SOUTH EXCAVATION AREA AT THE PROJECT SITE.
2. POST-EXCAVATION LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM 10/23/13 THROUGH 12/22/14. POST EXCAVATION SURFACES AND CONTOURS WERE GENERATED BY ENTACT AND CONFIRMED BY MASER CONSULTING P.A. WITH MINOR ADJUSTMENTS.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER
XXXXX

SHEET 1 OF 1
DWG C-111
PROJ 3480-10-0027
DATE 3/3/15

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

EXCAVATION PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 3/13/15 | REVISED PER CLIENT COMMENTS 3/4/15 | BSB | RTH |

DSGN BSB | DR | CHK JR | APVD RTH

R. THOMAS HUGG
LICENSE NUMBER GS36737
NJ PROFESSIONAL LAND SURVEYOR

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**ATTACHMENT A-2**

**FIGURE 1.1 – SA-6 SOUTH AS-BUILT LIMIT OF EXCAVATION MAP**

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

DESIGN EXCAVATION LIMIT

AS BUILT BOTTOM OF EXCAVATION LIMIT

DEFERRED EXCAVATION AREAS (DC 2014-05-19)

0 40 80 160

SCALE IN FEET

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

FIGURE 1.1
LIMIT OF EXCAVATION MAP

PROJECT NAME & LOCATION

HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

# ATTACHMENT B

# CONFIRMATORY SURVEY

**ATTACHMENT B-1**

**SA-6 SOUTH EXCAVATION CONFIRMATORY POINTS (EAST)**

**Table 1.0 – 1.8 PDI Locations**

**Table 2.0 – 2.7 Center Points**

**Table 3.0 – 3.2 Sidewall**

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -0.8 | 124-SB-043R | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684134.6 | 603208.6 | -0.8 | 124-SB-130 | 2 | 10/24/2013 | -1.2 | Stratum D Reached |
| 684150.2 | 603204.3 | -1.4 | 124-SB-037 | 3 | 10/31/2013 | -0.8 | Stratum D Reached |
| 684138.4 | 603182.8 | -0.8 | 124-SB-043R | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -0.8 | 124-SB-043R | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684145.4 | 603158.6 | -0.8 | 124-SB-038 | 6 | 11/5/2013 | -0.7 | Stratum D Reached |
| 684186.5 | 603160.3 | -2.1 | 124-SB-036 | 7 | 11/5/2013 | -0.8 | Stratum D Reached |
| 684142.9 | 603119.3 | 0.7 | 124-SB-079 | 7 | 11/7/2013 | -0.7 | Stratum D Reached |
| 684156.2 | 603128.2 | -1.8 | 124-SB-045 | 8 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684180.8 | 603117.2 | -1.3 | 124-SB-033 | 9 | 11/7/2013 | -1.3 | Stratum D Reached |
| 684208.6 | 603119.4 | -4.5 | 124-SB-C04 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684204.6 | 603115.9 | -1.6 | 124-SB-138 | 10 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684221.9 | 603112.3 | -2.9 | 124-SB-067 | 11 | 11/14/2013 | -1.3 | Stratum D Reached |
| 684191.5 | 603080.1 | -3.1 | 124-SB-044 | 12 | 11/14/2013 | -2.0 | Stratum D Reached |
| 684181.7 | 603072.3 | -1.0 | 124-SB-078 | 12 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684217.2 | 603081.8 | -2.0 | 124-SB-035 | 13 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684241.3 | 603065.1 | -2.2 | 124-SB-122 | 14 | 11/21/2013 | -1.3 | Stratum D Reached |
| 684196.6 | 603033.7 | -2.2 | 124-SB-077 | 14 | 11/25/2013 | -0.7 | Stratum D Reached |
| 684184.0 | 603001.0 | -3.5 | 124-SB-013 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684258.4 | 603074.7 | -2.6 | 124-SB-032 | 15 | 12/5/2013 | -1.9 | Stratum D Reached |
| 684221.8 | 603013.0 | -0.8 | 124-SB-043R | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684262.7 | 603034.6 | -1.7 | 124-SB-139 | 17 | 12/10/2013 | -1.3 | Stratum D Reached |
| 684220.6 | 603006.7 | 0.8 | 124-SB-046 | 17 | 12/10/2013 | -0.8 | Stratum D Reached |
| 684181.0 | 602955.9 | 1.7 | 124-SB-049 | 18 | 12/10/2013 | -1.1 | Stratum D Reached |
| 684215.6 | 602967.4 | 0.4 | 124-SB-047 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684211.8 | 602961.2 | -1.5 | 124-SB-125 | 19 | 12/10/2013 | -0.6 | Stratum D Reached |
| 684304.7 | 603027.7 | -2.5 | 124-SB-031 | 19 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.4 | 124-SB-073R | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684283.2 | 602988.7 | -2.8 | 124-SB-068 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |

* Elevations based on NGVD 1929 Datum. Coordinates are in the New Jersey state plane coordinate system, NAD 1983.

## SA-6 South Excavation: Confirmatory Points (Table 1.1)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684257.2 | 602964.2 | 0.7 | 124-SB-071 | 20 | 12/12/2013 | -1.2 | Stratum D Reached |
| 684256.4 | 602965.5 | -0.8 | 124-SB-043 | 20 | 12/12/2013 | -0.7 | Stratum D Reached |
| 684229.0 | 602947.0 | -1.6 | 124-SB-012 | 20 | 12/12/2013 | -1.5 | Stratum D Reached |
| 684217.9 | 602935.3 | -1.8 | 124-SB-135 | 20 | 12/12/2013 | -1.6 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.4 | 124-SB-073R | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684291.1 | 602978.2 | -2.3 | 124-SB-134 | 21 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.4 | 124-SB-073R | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684204.7 | 602890.6 | 2.4 | 124-SB-073 | 22 | 1/9/2014 | 2.0 | Target Elevation Reached |
| 684218.2 | 602907.9 | 1.8 | 124-SB-054 | 22 | 1/9/2014 | -0.1 | Target Elevation Reached |
| 684272.8 | 602944.8 | -0.8 | 124-SB-043R | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684258.9 | 602918.2 | 0.1 | 124-SB-053 | 23 | 12/19/2013 | -0.8 | Stratum D Reached |
| 684338.0 | 602980.2 | -2.9 | 124-SB-040 | 23 | 12/19/2013 | -2.1 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.4 | 124-SB-073R | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -0.8 | 124-SB-043R | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.4 | 124-SB-073R | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684338.6 | 602935.1 | -3.4 | 124-SB-030 | 25 | 1/2/2014 | -1.7 | Stratum D Reached |
| 684300.2 | 602911.6 | 0.3 | 124-SB-042 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 1.6 | 124-SB-051R | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |
| 684264.7 | 602869.3 | 0.0 | 124-SB-129 | 26 | 1/2/2014 | -1.3 | Stratum D Reached |
| 684273.8 | 602864.2 | 1.6 | 124-SB-051R | 26 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684294.0 | 602874.0 | 1.4 | 124-SB-011 | 27 | 1/10/2014 | -1.2 | Stratum D Reached |
| 684373.8 | 602937.7 | -2.3 | 124-SB-133 | 27 | 1/10/2014 | -2.4 | Stratum D Reached |
| 684285.9 | 602856.5 | 1.6 | 124-SB-051R | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684296.4 | 602850.5 | 1.6 | 124-SB-051 | 28 | 1/16/2014 | 0.2 | Target Elevation Reached |
| 684308.9 | 602854.3 | 1.9 | 124-SB-127 | 28 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684398.5 | 602909.7 | -2.7 | 124-SB-039 | 29 | 1/16/2014 | -2.7 | Stratum D Reached |
| 684343.7 | 602873.5 | -0.4 | 124-SB-069 | 29 | 1/16/2014 | -1.7 | Stratum D Reached |
| 684305.4 | 602833.3 | 3.5 | 124-SB-021R | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684392.6 | 602878.7 | -2.8 | 124-SB-123 | 30 | 1/23/2014 | -2.4 | Stratum D Reached |
| 684311.9 | 602821.5 | 3.5 | 124-SB-021R | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684381.0 | 602861.0 | -2.3 | 124-SB-110 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684362.9 | 602837.4 | 3.2 | 124-SB-124 | 31 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684340.0 | 602818.0 | 3.2 | 124-SB-109 | 31 | 1/23/2014 | -1.6 | Stratum D Reached |
| 684318.6 | 602806.8 | 3.5 | 124-SB-021R | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684416.9 | 602861.1 | -2.8 | 124-SB-029 | 32 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684335.2 | 602800.6 | 3.5 | 124-SB-021R | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684411.9 | 602839.0 | -2.2 | 124-SB-092 | 33 | 1/30/2014 | -2.5 | Stratum D Reached |
| 684348.7 | 602791.2 | 3.5 | 124-SB-021R | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684372.0 | 602797.0 | 2.6 | 124-PT-14 | 34 | 2/4/2014 | -1.9 | Stratum D Reached |
| 684355.8 | 602781.0 | 3.5 | 124-SB-021R | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684458.4 | 602838.3 | -2.3 | 124-SB-027 | 35 | 2/4/2014 | -2.7 | Stratum D Reached |
| 684367.5 | 602768.5 | 3.5 | 124-SB-021R | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684440.8 | 602806.0 | -2.8 | 124-SB-091 | 36 | 2/11/2014 | -2.7 | Stratum D Reached |
| 684371.2 | 602753.4 | 3.5 | 124-SB-021R | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684394.0 | 602777.3 | 4.7 | 124-SB-117A | 36 | 2/11/2014 | -1.6 | Stratum D Reached |
| 684473.9 | 602819.4 | -2.8 | 124-SB-026 | 37 | 2/11/2014 | -2.9 | Stratum D Reached |
| 684430.7 | 602784.0 | -1.3 | 124-SB-023 | 37 | 2/11/2014 | -3.6 | Stratum D Reached |
| 684412.9 | 602766.1 | 2.0 | 124-SB-121A | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684400.0 | 602762.0 | -0.1 | 124-PT-04 | 37 | 2/11/2014 | -2.2 | Stratum D Reached |
| 684380.7 | 602742.6 | 3.5 | 124-SB-021R | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684463.2 | 602783.7 | -2.3 | 124-SB-136 | 38 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684397.4 | 602736.2 | 3.5 | 124-SB-021R | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684448.4 | 602763.0 | 4.7 | 124-SB-022 | 39 | 2/20/2014 | -2.7 | Stratum D Reached |
| 684412.3 | 602733.9 | 3.5 | 124-SB-021 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684505.3 | 602786.0 | -2.8 | 124-SB-024 | 40 | 2/27/2014 | -3.4 | Stratum D Reached |
| 684482.9 | 602770.8 | -3.3 | 124-SB-025 | 40 | 2/27/2014 | -3.0 | Stratum D Reached |
| 684430.0 | 602730.0 | 1.7 | 124-PT-03 | 40 | 2/27/2014 | 0.0 | Target Elevation Reached |
| 684468.5 | 602745.2 | 1.8 | 124-SB-066 | 40 | 2/27/2014 | -2.2 | Stratum D Reached |
| 684491.3 | 602754.6 | -2.3 | 124-SB-136R | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | 125-SB-029R | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684524.5 | 602765.0 | -3.5 | 125-SB-017 | 42 | 3/5/2014 | -3.1 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | 125-SB-029R | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684513.0 | 602736.0 | -4.3 | 125-PT-22 | 43 | 3/5/2014 | -3.5 | Stratum D Reached |
| 684496.0 | 602718.9 | -1.7 | 125-SB-086 | 43 | 3/5/2014 | -2.6 | Stratum D Reached |
| 684473.0 | 602698.0 | 0.3 | 125-PT-21 | 43 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684446.6 | 602677.9 | 0.5 | 125-SB-028 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684543.1 | 602743.1 | -3.9 | 125-SB-018 | 44 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684431.0 | 602654.0 | 0.7 | 125-PT-20 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684467.4 | 602652.6 | 1.0 | 125-SB-027 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684495.1 | 602674.9 | 0.4 | 125-SB-025 | 45 | 3/11/2014 | 0.3 | Target Elevation Reached |
| 684512.8 | 602689.3 | 0.3 | 125-SB-024 | 45 | 3/11/2014 | -3.6 | Stratum D Reached |
| 684561.9 | 602720.2 | -3.3 | 125-SB-019 | 46 | 3/17/2014 | -3.0 | Stratum D Reached |
| 684543.0 | 602699.0 | -4.7 | 125-PT-17 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684539.5 | 602702.1 | -3.7 | 125-SB-022 | 46 | 3/17/2014 | -3.3 | Stratum D Reached |
| 684503.0 | 602661.0 | 1.0 | 125-PT-16 | 46 | 3/17/2014 | -2.9 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | 125-SB-029R | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.3 | 124-SB-136R | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684481.2 | 602625.7 | 1.7 | 125-SB-089 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684488.7 | 602626.5 | 1.3 | 125-SB-026 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684581.0 | 602697.1 | -3.4 | 125-SB-020 | 48 | 3/20/2014 | -2.9 | Stratum D Reached |
| 684558.6 | 602678.9 | -4.0 | 125-SB-021 | 48 | 3/20/2014 | -3.4 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | 125-SB-029R | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |
| 684545.6 | 602650.2 | -3.3 | 125-SB-038 | 49 | 3/20/2014 | -3.3 | Stratum D Reached |
| 684597.3 | 602676.1 | -3.5 | 125-SB-037 | 49 | 3/25/2014 | -2.6 | Stratum D Reached |
| 684574.9 | 602657.9 | -3.4 | 125-SB-039 | 49 | 3/25/2014 | -3.3 | Stratum D Reached |
| 684535.1 | 602625.9 | 0.6 | 125-SB-032 | 49 | 3/25/2014 | -3.3 | Stratum D Reached |
| 684516.6 | 602611.2 | 1.1 | 125-SB-031 | 49 | 3/25/2014 | 0.1 | Target Elevation Reached |
| 684511.6 | 602592.1 | -1.0 | 125-SB-090 | 50 | 3/25/2014 | -1.3 | Target Elevation Reached |
| 684526.0 | 602608.3 | 0.4 | 125-SB-029R | 50 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684574.8 | 602647.4 | -2.3 | 124-SB-136R | 50 | 3/25/2014 | -3.6 | Stratum D Reached |
| 684514.6 | 602580.4 | -1.0 | 125-SB-090R | 51 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684535.3 | 602597.8 | 0.4 | 125-SB-029R | 51 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684584.1 | 602636.9 | -2.3 | 124-SB-136R | 51 | 3/28/2014 | -3.0 | Stratum D Reached |
| 684619.0 | 602648.6 | -1.5 | 125-SB-035 | 52 | 3/28/2014 | -2.5 | Stratum D Reached |
| 684596.6 | 602630.5 | -3.6 | 125-SB-034 | 52 | 3/28/2014 | -3.0 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684574.5 | 602612.8 | 0.7 | 125-SB-033 | 52 | 3/28/2014 | -3.4 | Stratum D Reached |
| 684556.8 | 602598.4 | 0.8 | 125-SB-030 | 52 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684538.3 | 602583.7 | 0.4 | 125-SB-029 | 52 | 3/28/2014 | 0.4 | Target Elevation Reached |
| 684523.8 | 602562.3 | -0.9 | 125-SB-078 | 52 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684579.0 | 602588.0 | 0.9 | 125-SB-009 | 53 | 4/1/2014 | -2.2 | Stratum D Reached |
| 684557.0 | 602576.5 | 0.4 | 125-SB-029R | 53 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684533.6 | 602556.0 | -1.0 | 125-SB-090R | 53 | 4/1/2014 | -1.4 | Target Elevation Reached |
| 684620.4 | 602605.9 | 0.4 | 125-SB-065 | 54 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684641.2 | 602623.7 | -2.1 | 125-SB-070 | 54 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684597.0 | 602588.0 | -2.7 | 125-SB-009A | 54 | 4/1/2014 | -2.2 | Stratum D Reached |
| 684573.7 | 602577.0 | 0.7 | 125-SB-044 | 54 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684557.6 | 602564.1 | 1.2 | 125-SB-050 | 54 | 4/1/2014 | 0.2 | Target Elevation Reached |
| 684632.0 | 602597.9 | -1.4 | 140-SB-083R | 55 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684576.2 | 602552.1 | 0.4 | 125-SB-029R | 55 | 4/4/2014 | 0.3 | Target Elevation Reached |
| 684664.6 | 602597.6 | -3.3 | 125-SB-071 | 56 | 4/4/2014 | -2.5 | Stratum D Reached |
| 684642.2 | 602579.5 | 0.2 | 125-SB-053 | 56 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684601.1 | 602556.0 | 3.1 | 125-SB-045 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684583.0 | 602540.8 | 0.6 | 125-SB-066 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684576.6 | 602529.9 | 2.1 | 125-SB-069 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684574.5 | 602511.9 | 2.1 | 125-SB-069R | 57 | 4/9/2014 | 1.6 | Target Elevation Reached |
| 684606.0 | 602536.9 | 0.4 | 125-SB-029R | 57 | 4/9/2014 | 0.1 | Target Elevation Reached |
| 684636.4 | 602554.1 | -2.4 | 125-SB-052 | 57 | 4/9/2014 | -1.2 | Stratum D Reached |
| 684591.8 | 602507.6 | 2.1 | 125-SB-069R | 58 | 4/9/2014 | 1.5 | Target Elevation Reached |
| 684679.9 | 602578.9 | -2.3 | 125-SB-062 | 58 | 4/9/2014 | -2.6 | Stratum D Reached |
| 684620.0 | 602524.0 | 0.6 | 125-SB-007 | 58 | 4/9/2014 | 0.2 | Target Elevation Reached |
| 684600.1 | 602523.2 | 0.6 | 125-SB-049 | 58 | 4/9/2014 | -0.1 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684123.8 | 603224.1 | -1.2 | C1 | 1 | 10/24/2013 | -1.7 | Stratum D Reached |
| 684124.9 | 603209.0 | -1.2 | C2 | 2 | 10/31/2013 | -0.9 | Stratum D Reached |
| 684132.1 | 603196.4 | -1.2 | C3 | 3 | 10/31/2013 | -1.1 | Stratum D Reached |
| 684138.4 | 603182.8 | -1.2 | C4 | 4 | 10/31/2013 | -0.5 | Stratum D Reached |
| 684146.2 | 603165.7 | -1.2 | C5 | 5 | 10/31/2013 | -0.6 | Stratum D Reached |
| 684153.8 | 603153.9 | -1.2 | C6 | 6 | 11/5/2013 | -0.6 | Stratum D Reached |
| 684163.6 | 603140.8 | -1.2 | C7 | 7 | 11/7/2013 | -1.0 | Stratum D Reached |
| 684171.5 | 603131.4 | -1.2 | C8 | 8 | 11/7/2013 | -1.1 | Stratum D Reached |
| 684179.9 | 603119.5 | -1.2 | C9 | 9 | 11/7/2013 | -1.2 | Stratum D Reached |
| 684187.6 | 603106.3 | -1.2 | C10 | 10 | 11/14/2013 | -1.4 | Stratum D Reached |
| 684195.7 | 603093.1 | -1.2 | C11 | 11 | 11/14/2013 | -1.5 | Stratum D Reached |
| 684200.6 | 603078.4 | -1.2 | C12 | 12 | 11/14/2013 | -1.8 | Stratum D Reached |
| 684206.7 | 603063.8 | -1.2 | C13 | 13 | 11/21/2013 | -1.6 | Stratum D Reached |
| 684214.8 | 603050.6 | -1.2 | C14 | 14 | 11/21/2013 | -1.7 | Stratum D Reached |
| 684222.7 | 603033.3 | -1.2 | C15 | 15 | 12/5/2013 | -0.8 | Stratum D Reached |
| 684221.8 | 603013.0 | -1.2 | C16 | 16 | 12/5/2013 | -0.7 | Stratum D Reached |
| 684234.5 | 603010.3 | -1.2 | C17 | 17 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684247.3 | 602999.0 | -1.2 | C18 | 18 | 12/10/2013 | -0.5 | Stratum D Reached |
| 684238.6 | 602972.8 | -1.2 | C19 | 19 | 12/12/2013 | -1.0 | Stratum D Reached |
| 684187.4 | 602932.2 | 2.1 | C19-1 | 19 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684248.1 | 602961.0 | -1.2 | C20 | 20 | 12/12/2013 | -1.7 | Stratum D Reached |
| 684198.3 | 602920.8 | 2.1 | C20-1 | 20 | 12/12/2013 | 2.0 | Target Elevation Reached |
| 684267.7 | 602959.2 | -1.2 | C-21 | 21 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684200.8 | 602904.5 | 2.1 | C-21-1 | 21 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684272.8 | 602944.8 | -1.2 | C-22 | 22 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684207.2 | 602890.0 | 2.1 | C-22-1 | 22 | 1/9/2014 | 2.1 | Target Elevation Reached |
| 684281.0 | 602931.9 | -1.2 | C-23 | 23 | 12/19/2013 | -0.9 | Stratum D Reached |
| 684217.2 | 602879.5 | 2.1 | C-23-1 | 23 | 12/19/2013 | 1.9 | Target Elevation Reached |
| 684293.5 | 602922.8 | -1.2 | C-24 | 24 | 1/2/2014 | -0.9 | Stratum D Reached |
| 684227.9 | 602869.9 | 2.1 | C-24-1 | 24 | 1/2/2014 | 2.1 | Target Elevation Reached |
| 684302.0 | 602910.0 | -1.2 | C-25 | 25 | 1/2/2014 | -1.1 | Stratum D Reached |
| 684247.0 | 602862.1 | 0.4 | C-25-1 | 25 | 1/2/2014 | 0.4 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684325.2 | 602907.2 | -1.2 | C-26 | 26 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684273.8 | 602864.2 | 0.4 | C-26-1 | 26 | 1/10/2014 | 0.3 | Target Elevation Reached |
| 684335.7 | 602896.8 | -1.2 | C-27 | 27 | 1/10/2014 | -1.5 | Stratum D Reached |
| 684285.9 | 602856.5 | 0.4 | C-27-1 | 27 | 1/10/2014 | 0.4 | Target Elevation Reached |
| 684347.4 | 602890.7 | -1.2 | C-28 | 28 | 1/16/2014 | -1.8 | Stratum D Reached |
| 684295.1 | 602846.5 | 0.4 | C-28-1 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684357.8 | 602876.2 | -1.2 | C-29 | 29 | 1/16/2014 | -2.1 | Stratum D Reached |
| 684305.4 | 602833.3 | 2.1 | C-29-1 | 29 | 1/16/2014 | 2.1 | Target Elevation Reached |
| 684373.5 | 602871.7 | -2.5 | C-30 | 30 | 1/23/2014 | -2.1 | Stratum D Reached |
| 684311.9 | 602821.5 | 2.1 | C-30-1 | 30 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684384.9 | 602861.2 | -2.5 | C-31 | 31 | 1/23/2014 | -2.3 | Stratum D Reached |
| 684318.6 | 602806.8 | 2.1 | C-31-1 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684383.8 | 602841.5 | -2.5 | C-32 | 32 | 1/30/2014 | -1.8 | Stratum D Reached |
| 684335.2 | 602800.6 | 2.1 | C-32-1 | 32 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684393.5 | 602830.6 | -2.5 | C-33 | 33 | 1/30/2014 | -1.9 | Stratum D Reached |
| 684348.7 | 602791.2 | 2.1 | C-33-1 | 33 | 1/30/2014 | 2.0 | Target Elevation Reached |
| 684412.7 | 602824.5 | -2.5 | C-34 | 34 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684355.8 | 602781.0 | 2.1 | C-34-1 | 34 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684422.4 | 602815.2 | -2.5 | C-35 | 35 | 2/4/2014 | -2.1 | Stratum D Reached |
| 684367.5 | 602768.5 | 2.1 | C-35-1 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684432.1 | 602801.8 | -2.5 | C-36 | 36 | 2/11/2014 | -2.4 | Stratum D Reached |
| 684371.2 | 602753.4 | 2.1 | C-36-1 | 36 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684440.7 | 602791.6 | -2.5 | C-37 | 37 | 2/11/2014 | -2.5 | Stratum D Reached |
| 684380.7 | 602742.6 | 2.1 | C-37-1 | 37 | 2/11/2014 | 2.1 | Target Elevation Reached |
| 684460.4 | 602787.7 | -2.5 | C-38 | 38 | 2/20/2014 | -2.8 | Stratum D Reached |
| 684397.4 | 602736.2 | 2.1 | C-38-1 | 38 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684471.9 | 602777.2 | -2.5 | C-39 | 39 | 2/20/2014 | -2.9 | Stratum D Reached |
| 684416.4 | 602732.1 | 2.1 | C-39-1 | 39 | 2/20/2014 | 2.1 | Target Elevation Reached |
| 684481.8 | 602765.6 | -2.5 | C-40 | 40 | 2/27/2014 | -3.1 | Stratum D Reached |
| 684427.0 | 602721.5 | 0.4 | C-40-1 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684491.3 | 602754.6 | -2.5 | C-41 | 41 | 2/27/2014 | -2.9 | Stratum D Reached |
| 684432.9 | 602706.0 | 0.4 | C-41-1 | 41 | 2/27/2014 | 0.1 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684496.7 | 602740.4 | -2.5 | C-42 | 42 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684439.6 | 602692.4 | 0.4 | C-42-1 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684507.5 | 602729.5 | -2.5 | C-43 | 43 | 3/5/2014 | -3.3 | Stratum D Reached |
| 684447.1 | 602679.0 | 0.4 | C-43-1 | 43 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684524.2 | 602722.2 | -2.5 | C-44 | 44 | 3/11/2014 | -3.5 | Stratum D Reached |
| 684454.3 | 602665.7 | 0.4 | C-44-1 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684536.0 | 602714.2 | -2.5 | C-45 | 45 | 3/11/2014 | -3.2 | Stratum D Reached |
| 684464.6 | 602655.3 | 0.4 | C-45-1 | 45 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684535.1 | 602693.1 | -2.5 | C-46 | 46 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684472.4 | 602641.2 | 0.4 | C-46-1 | 46 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684544.9 | 602683.5 | -2.5 | C-47 | 47 | 3/17/2014 | -3.2 | Stratum D Reached |
| 684483.8 | 602632.5 | 0.4 | C-47-1 | 47 | 3/17/2014 | 0.2 | Target Elevation Reached |
| 684551.5 | 602667.8 | -2.5 | C-48 | 48 | 3/20/2014 | -3.0 | Stratum D Reached |
| 684492.6 | 602619.5 | 0.4 | C-48-1 | 48 | 3/20/2014 | 0.4 | Target Elevation Reached |
| 684564.6 | 602658.9 | -2.5 | C-49 | 49 | 3/25/2014 | -3.0 | Stratum D Reached |
| 684501.1 | 602607.9 | 0.4 | C-49-1 | 49 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684574.8 | 602647.4 | -2.5 | C-50 | 50 | 3/25/2014 | -3.6 | Stratum D Reached |
| 684526.0 | 602608.3 | 0.4 | C-50-1 | 50 | 3/25/2014 | 0.3 | Target Elevation Reached |
| 684507.7 | 602591.7 | -1.2 | C-50-2 | 50 | 3/25/2014 | -1.3 | Target Elevation Reached |
| 684584.1 | 602636.9 | -2.5 | C-51 | 51 | 3/28/2014 | -3.0 | Stratum D Reached |
| 684535.3 | 602597.8 | 0.4 | C-51-1 | 51 | 3/28/2014 | 0.3 | Target Elevation Reached |
| 684514.6 | 602580.4 | -1.2 | C-51-2 | 51 | 3/28/2014 | -1.4 | Target Elevation Reached |
| 684596.7 | 602626.3 | -2.5 | C-52 | 52 | 3/28/2014 | -2.9 | Stratum D Reached |
| 684547.0 | 602587.9 | 0.4 | C-52-1 | 52 | 3/28/2014 | 0.2 | Target Elevation Reached |
| 684524.8 | 602569.7 | -1.2 | C-52-2 | 52 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684602.1 | 602612.0 | -2.5 | C-53 | 53 | 4/1/2014 | -2.3 | Stratum D Reached |
| 684557.0 | 602576.5 | 0.4 | C-53-1 | 53 | 4/1/2014 | 0.3 | Target Elevation Reached |
| 684533.6 | 602556.0 | -1.2 | C-53-2 | 53 | 4/1/2014 | -1.4 | Target Elevation Reached |
| 684610.8 | 602599.7 | -2.5 | C-54 | 54 | 4/4/2014 | -2.0 | Stratum D Reached |
| 684560.2 | 602558.1 | 0.4 | C-54-1 | 54 | 4/4/2014 | 0.3 | Target Elevation Reached |
| 684632.0 | 602597.9 | -2.5 | C-55 | 55 | 4/4/2014 | -2.4 | Stratum D Reached |
| 684576.2 | 602552.1 | 0.4 | C-55-1 | 55 | 4/4/2014 | 0.3 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684641.4 | 602586.6 | -2.5 | C-56 | 56 | 4/4/2014 | -2.5 | Stratum D Reached |
| 684586.1 | 602541.3 | 0.4 | C-56-1 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |
| 684656.7 | 602578.2 | -2.5 | C-57 | 57 | 4/9/2014 | -2.4 | Stratum D Reached |
| 684606.0 | 602536.9 | 0.4 | C-57-1 | 57 | 4/9/2014 | 0.1 | Target Elevation Reached |
| 684574.5 | 602511.9 | 2.1 | C-57-2 | 57 | 4/9/2014 | 1.6 | Target Elevation Reached |
| 684662.3 | 602565.2 | -2.5 | C-58 | 58 | 4/9/2014 | -2.7 | Stratum D Reached |
| 684616.2 | 602527.5 | 0.4 | C-58-1 | 58 | 4/9/2014 | 0.3 | Target Elevation Reached |
| 684591.8 | 602507.6 | 2.1 | C-58-2 | 58 | 4/9/2014 | 1.5 | Target Elevation Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

## SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0)

| Sidewall Target Coordinates | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684162.0 | 603071.0 | 0.6 | 124-SB-017 | 11 | 11/14/2013 | -0.2 | Stratum D Reached |
| 684174.6 | 603009.0 | -1.8 | 124-SB-075 | 14 | 11/21/2013 | -0.1 | Stratum D Reached |
| 684170.5 | 603030.7 | -1.8 | 124-SB-076 | 13 | 11/21/2013 | -0.1 | Stratum D Reached |
| 684173.5 | 602976.5 | -2.2 | 124-SB-074 | 16 | 12/5/2013 | -0.6 | Stratum D Reached |
| 684174.4 | 602980.6 | 1.2 | 124-SB-048 | 16 | 12/5/2013 | -0.5 | Stratum D Reached |
| 684172.0 | 602944.6 | 4.3 | 124-SB-126 | 18 | 12/10/2013 | -0.9 | Stratum D Reached |
| 684178.0 | 602906.0 | 4.5 | 124-SB-014 | 20 | 12/12/2013 | 2.0 | Stratum D Reached |
| 684192.9 | 602874.5 | 3.8 | 124-SB-090 | 22 | 12/19/2013 | 2.1 | Target Elevation Reached |
| 684234.9 | 602864.2 | 0.9 | 124-SB-019 | 25 | 1/2/2014 | 0.5 | Target Elevation Reached |
| 684289.2 | 602837.4 | 2.9 | 124-SB-050 | 28 | 1/16/2014 | 0.3 | Target Elevation Reached |
| 684301.0 | 602795.0 | 2.6 | 124-SB-108 | 31 | 1/23/2014 | 1.9 | Target Elevation Reached |
| 684328.2 | 602790.2 | 3.3 | 124-SB-063 | 32 | 1/30/2014 | 1.8 | Target Elevation Reached |
| 684338.1 | 602786.6 | 4.7 | 124-SB-056 | 33 | 1/30/2014 | 1.7 | Target Elevation Reached |
| 684348.0 | 602746.0 | 3.4 | 124-PT-02 | 35 | 2/4/2014 | 2.0 | Target Elevation Reached |
| 684386.0 | 602707.0 | 3.3 | 124-PT-01 | 39 | 2/20/2014 | 2.0 | Target Elevation Reached |
| 684411.1 | 602714.2 | 3.9 | 124-SB-065 | 40 | 2/27/2014 | 0.2 | Target Elevation Reached |
| 684408.4 | 602664.2 | 2.2 | 125-SB-088 | 42 | 3/5/2014 | 0.1 | Target Elevation Reached |
| 684419.7 | 602644.6 | 1.8 | 125-SB-067 | 44 | 3/11/2014 | 0.2 | Target Elevation Reached |
| 684457.0 | 602620.0 | 1.1 | 125-PT-15 | 47 | 3/17/2014 | 0.1 | Target Elevation Reached |
| 684479.5 | 602597.5 | 3.7 | 125-SB-081 | 49 | 3/20/2014 | 0.1 | Target Elevation Reached |
| 684495.3 | 602579.6 | 0.8 | 125-SB-091 | 50 | 3/25/2014 | -1.4 | Target Elevation Reached |
| 684499.2 | 602575.0 | 2.3 | 125-SB-080 | 51 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684513.9 | 602557.6 | 0.6 | 125-SB-092 | 52 | 3/28/2014 | -1.3 | Target Elevation Reached |
| 684519.3 | 602551.3 | 2.5 | 125-SB-079 | 53 | 4/1/2014 | -1.5 | Target Elevation Reached |
| 684552.7 | 602504.6 | 3.5 | 125-SB-087 | 56 | 4/4/2014 | 0.2 | Target Elevation Reached |

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**

R. Thomas Hugg 9/22/15

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**ATTACHMENT B-2**

**SA-6 SOUTH EXCAVATION CONFIRMATORY POINTS (WEST)**

**Table 1.0 – 1.8 PDI Locations**

**Table 2.0 – 2.7 Center Points**

**Table 3.0 – 3.2 Sidewall**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation: Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685514.6 | 601446.5 | 3.8 | 073-SB-029 | 152 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685482.2 | 601420.6 | 4.4 | 073-SB-054 | 152 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685458.7 | 601392.0 | 7.5 | 073-SB-056 | 152 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685474.8 | 601425.1 | 7.5 | 073-SB-057 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685502.9 | 601465.5 | 3.3 | 073-SB-028 | 150 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685463.0 | 601435.2 | 2.5 | 073-SB-059 | 150 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685490.0 | 601478.5 | 6.0 | 073-SB-042R | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 6.0 | 073-SB-042R | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 6.0 | 073-SB-042R | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 6.0 | 073-SB-042R | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685448.9 | 601515.0 | 6.0 | 073-SB-042 | 145A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685433.1 | 601528.8 | 6.0 | 073-SB-042R | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.2 | 073-SB-037R | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685411.9 | 601522.2 | -0.6 | 073-SB-066 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685427.6 | 601544.4 | 6.0 | 073-SB-042R | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685430.7 | 601568.7 | 3.8 | 073-SB-041 | 142A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685378.8 | 601531.7 | -4.2 | 073-SB-037 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685371.0 | 601525.0 | -2.2 | 073-SB-045 | 142A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685395.8 | 601557.3 | 2.3 | 073-SB-038 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.3 | 073-SB-038R | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685410.7 | 601592.8 | 0.2 | 073-SB-040 | 140A | 4/24/2014 | -1.3 | Target Elevation Reached |
| 685381.0 | 601558.0 | -3.9 | 073-SB-007 | 140A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685379.3 | 601577.9 | 0.6 | 073-SB-039 | 139A | 4/24/2014 | -4.3 | Target Elevation Reached |
| 685358.5 | 601560.3 | -1.0 | 073-SB-036 | 139A | 4/24/2014 | -4.7 | Target Elevation Reached |
| 685390.7 | 601590.5 | -0.6 | 073-SB-008R | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685390.0 | 601606.0 | -0.6 | 073-SB-008 | 138A | 4/29/2014 | -1.6 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | 073-SB-030R | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685339.7 | 601592.9 | 1.5 | 073-SB-035 | 137A | 4/29/2014 | -2.9 | Target Elevation Reached |

* Elevations based on NGVD 1929 Datum. Coordinates are in the New Jersey state plane coordinate system, NAD 1983.

| SA-6 South Excavation: Confirmatory Points (Table 1.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685328.7 | 601577.4 | 2.1 | 073-SB-030R | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -6.7 | 073-SB-009R | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685329.7 | 601419.3 | -6.9 | 073-SB-047 | 145B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685314.6 | 601432.4 | -6.7 | 073-SB-009R | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685318.9 | 601448.7 | -5.3 | 073-SB-021 | 143B | 5/8/2014 | -7.9 | Target Elevation Reached |
| 685306.3 | 601465.9 | -6.7 | 073-SB-009R | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685329.1 | 601510.6 | -5.2 | 073-SB-075 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685310.4 | 601484.5 | -4.8 | 073-SB-062 | 141B | 5/12/2014 | -8.0 | Target Elevation Reached |
| 685321.1 | 601501.8 | -5.0 | 073-SB-065 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685288.0 | 601466.0 | -6.7 | 073-SB-009 | 141B | 5/12/2014 | -7.7 | Target Elevation Reached |
| 685284.5 | 601485.3 | -5.3 | 073-SB-020 | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -6.7 | 073-SB-009R | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685256.2 | 601505.4 | -3.2 | 073-SB-019 | 138B | 5/14/2014 | -7.7 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | 073-SB-030R | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -0.6 | 073-SB-008R | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685344.3 | 601618.9 | -1.8 | 073-SB-033 | 136 | 5/5/2014 | -2.9 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | 073-SB-030R | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -0.6 | 073-SB-008R | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685362.2 | 601641.7 | -0.2 | 073-SB-034 | 135 | 5/8/2014 | -2.8 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | 073-SB-030R | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685248.2 | 601551.5 | 0.3 | 073-SB-050 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685230.4 | 601535.5 | 0.3 | 073-SB-018 | 135 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685358.1 | 601659.9 | -0.6 | 073-SB-008R | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -1.8 | 073-SB-033R | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | 073-SB-030R | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | 0.6 | 073-SB-017R | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685212.0 | 601570.0 | -1.4 | 073-SB-011 | 133 | 5/22/2014 | -3.3 | Target Elevation Reached |
| 685324.0 | 601643.0 | -0.4 | 073-SB-010 | 133 | 5/14/2014 | -2.7 | Target Elevation Reached |
| 685300.3 | 601630.9 | 2.1 | 073-SB-030 | 133 | 5/14/2014 | 1.8 | Target Elevation Reached |
| 685338.7 | 601665.5 | 2.3 | 073-SB-032R | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | 134-SB-136R | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685215.0 | 601563.9 | 0.6 | 073-SB-017R | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.3 | 073-SB-032R | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | 073-SB-030R | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685194.1 | 601565.5 | 0.6 | 073-SB-017R | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685216.3 | 601579.5 | 1.1 | 073-SB-049 | 132 | 5/22/2014 | -3.0 | Target Elevation Reached |
| 685324.7 | 601663.5 | 2.3 | 073-SB-032 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685193.1 | 601579.8 | 0.6 | 073-SB-017 | 131 | 5/22/2014 | -2.7 | Target Elevation Reached |
| 685301.9 | 601671.1 | 0.1 | 073-SB-031 | 131 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.3 | 073-SB-032R | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | 073-SB-030R | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685202.7 | 601594.7 | -1.4 | 073-SB-011R | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.3 | 073-SB-032R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | 134-SB-136R | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | 073-SB-030R | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685193.4 | 601601.4 | -1.4 | 073-SB-011R | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | 0.6 | 073-SB-017R | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685195.4 | 601621.6 | -2.7 | 134-SB-123 | 129 | 5/27/2014 | -7.9 | Target Elevation Reached |
| 685212.1 | 601635.4 | -0.6 | 134-SB-132 | 129 | 5/27/2014 | -8.2 | Target Elevation Reached |
| 685242.2 | 601665.8 | 1.3 | 134-SB-134 | 129 | 5/27/2014 | 0.2 | Target Elevation Reached |
| 685305.3 | 601707.9 | -1.2 | 134-SB-140 | 129 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685158.2 | 601591.1 | -6.6 | 134-SB-114 | 129 | 5/27/2014 | -7.6 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.3 | 073-SB-032R | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | 073-SB-030R | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685289.8 | 601729.8 | 2.0 | 134-SB-139 | 128 | 5/27/2014 | -1.3 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.3 | 073-SB-032R | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | 073-SB-030R | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 1.3 | 134-SB-134R | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -6.7 | 134-SB-129R | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 2.4 | 134-SB-014R | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685276.2 | 601720.2 | 4.5 | 134-SB-135 | 127 | 5/27/2014 | -1.2 | Target Elevation Reached |
| 685237.1 | 601700.2 | 1.3 | 134-SB-134R | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685258.0 | 601714.0 | -1.1 | 134-SB-012 | 127 | 5/29/2014 | -1.4 | Target Elevation Reached |
| 685226.8 | 601681.6 | -0.7 | 134-SB-133 | 127 | 6/2/2014 | -7.6 | Target Elevation Reached |
| 685172.0 | 601639.0 | -5.6 | 134-SB-013 | 127 | 6/5/2014 | -7.7 | Target Elevation Reached |
| 685285.7 | 601758.3 | 2.4 | 134-SB-014R | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | 134-SB-136R | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685122.8 | 601623.1 | -8.4 | 134-SB-115 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685155.2 | 601653.8 | -5.8 | 134-SB-122 | 126 | 6/10/2014 | -7.8 | Target Elevation Reached |
| 685178.8 | 601676.4 | -6.1 | 134-SB-131 | 126 | 6/10/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685212.9 | 601702.0 | -0.7 | 134-SB-130 | 126 | 6/10/2014 | -7.7 | Target Elevation Reached |
| 685277.9 | 601769.3 | 2.4 | 134-SB-014R | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685269.3 | 601754.4 | -1.1 | 134-SB-138 | 125 | 6/2/2014 | -1.7 | Target Elevation Reached |
| 685158.0 | 601676.7 | -6.7 | 134-SB-129R | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | 134-SB-115R | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 2.4 | 134-SB-014R | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685266.0 | 601776.0 | 2.4 | 134-SB-014 | 124 | 6/10/2014 | -2.9 | Target Elevation Reached |
| 685100.0 | 601650.0 | 1.2 | 134-SB-116 | 124 | 6/17/2014 | -8.2 | Stratum D Reached |
| 685136.1 | 601677.4 | -7.7 | 134-SB-121 | 124 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685262.3 | 601792.9 | 2.4 | 134-SB-014R | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -1.5 | 134-SB-137R | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685225.1 | 601760.9 | -1.3 | 134-SB-136 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685165.9 | 601710.7 | -6.7 | 134-SB-129 | 123 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | 134-SB-120R | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685252.4 | 601807.4 | 2.4 | 134-SB-014R | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601798.5 | -1.5 | 134-SB-137 | 122 | 6/17/2014 | -2.8 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.3 | 134-SB-136R | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -6.7 | 134-SB-129R | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685113.6 | 601700.2 | -8.7 | 134-SB-120 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685242.2 | 601818.1 | 2.4 | 134-SB-014R | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685201.0 | 601787.0 | -0.6 | 134-SB-015 | 121 | 6/20/2014 | -2.5 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.3 | 134-SB-136R | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.3 | 124-SB-124R | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685175.7 | 601754.9 | -4.5 | 134-SB-127 | 121 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685140.4 | 601734.6 | -0.8 | 134-SB-125 | 121 | 6/20/2014 | -7.4 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | 134-SB-120R | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685079.9 | 601677.2 | 0.9 | 134-SB-117 | 121 | 6/20/2014 | -6.8 | Stratum D Reached |
| 685233.4 | 601829.1 | 2.4 | 134-SB-014R | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -1.5 | 134-SB-137R | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.3 | 134-SB-136R | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685112.0 | 601735.0 | -6.7 | 134-SB-016 | 120 | 6/25/2014 | -7.5 | Stratum D Reached |
| 685094.8 | 601725.1 | -5.2 | 134-SB-119 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685062.9 | 601695.5 | -7.9 | 134-SB-118 | 120 | 6/25/2014 | -6.4 | Stratum D Reached |
| 685159.9 | 601776.2 | -2.3 | 134-SB-124 | 120 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685223.8 | 601840.5 | 2.4 | 134-SB-014R | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -1.5 | 134-SB-137R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685170.4 | 601797.8 | 0.4 | 134-SB-060 | 119 | 6/25/2014 | -1.4 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.7 | 601780.4 | -2.3 | 124-SB-124R | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685208.4 | 601850.6 | 2.4 | 134-SB-033R | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.4 | 134-SB-033R | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.4 | 134-SB-033R | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.4 | 134-SB-033R | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.9 | 601738.9 | 4.1 | 134-SB-155 | 118B | 6/30/2014 | -7.1 | Stratum D Reached |
| 685042.3 | 601722.7 | -8.9 | 134-SB-141 | 118B | 7/8/2014 | -7.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -8.9 | 134-SB-141R | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685040.6 | 601747.5 | -6.8 | 134-SB-147 | 116B | 7/8/2014 | -6.9 | Stratum D Reached |
| 685024.0 | 601763.4 | 4.1 | 134-SB-154 | 115B | 7/10/2014 | -5.6 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.4 | 134-SB-033R | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685132.0 | 601873.0 | -5.5 | 134-SB-019 | 114A | 12/8/2014 | -5.7 | Stratum D Reached |
| 685014.9 | 601776.3 | 4.1 | 134-SB-154R | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 685159.0 | 601914.0 | 2.4 | 134-SB-033 | 113A | 7/3/2014 | 0.7 | Target Elevation Reached |
| 685116.0 | 601878.0 | 0.8 | 134-SB-057 | 113A | 7/3/2014 | -2.0 | Stratum D Reached |
| 685006.3 | 601780.6 | 4.1 | 134-SB-154R | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685157.5 | 601925.6 | 2.4 | 134-SB-033R | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685126.3 | 601904.5 | -1.2 | 134-SB-052 | 112A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.1 | 134-SB-154R | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685145.9 | 601933.8 | 2.4 | 134-SB-033R | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | 134-SB-052R | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.1 | 134-SB-154R | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.4 | 134-SB-033R | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | 134-SB-052R | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.1 | 134-SB-154R | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.4 | 134-SB-033R | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685111.5 | 601936.0 | 1.4 | 134-SB-056 | 109A | 7/10/2014 | -1.3 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.1 | 134-SB-154R | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.4 | 134-SB-033R | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | 134-SB-052R | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.1 | 134-SB-154R | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685117.6 | 601982.8 | 0.9 | 134-SB-062 | 107A | 7/17/2014 | -5.0 | Stratum D Reached |
| 685087.5 | 601965.4 | 1.8 | 134-SB-051 | 107A | 7/17/2014 | -5.1 | Stratum D Reached |
| 684939.3 | 601841.8 | 4.1 | 134-SB-154R | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684928.5 | 601848.2 | 4.1 | 134-SB-154R | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685068.4 | 601974.0 | -3.3 | 134-SB-061 | 106A | 11/20/2014 | -5.7 | Stratum D Reached |
| 685046.6 | 601950.7 | 1.2 | 134-SB-061R | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685076.6 | 601999.1 | -6.7 | 134-SB-065 | 105 | 7/23/2014 | -4.7 | Stratum D Reached |
| 685029.8 | 601954.8 | 1.2 | 134-SB-061R | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685087.0 | 602018.0 | -5.7 | 134-SB-024 | 104 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685017.7 | 601961.5 | 1.2 | 134-SB-061R | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685065.1 | 602014.9 | -5.2 | 134-SB-064 | 103 | 7/29/2014 | -5.1 | Stratum D Reached |
| 685036.9 | 601997.8 | -5.2 | 134-SB-078 | 103 | 7/29/2014 | -6.2 | Stratum D Reached |
| 685012.7 | 601978.2 | -7.5 | 134-SB-113 | 103 | 11/20/2014 | -7.6 | Stratum D Reached |
| 685021.0 | 602007.9 | -7.9 | 134-SB-080 | 102 | 7/31/2014 | -6.0 | Stratum D Reached |
| 685024.9 | 602029.4 | -7.8 | 134-SB-042 | 101 | 8/4/2014 | -5.6 | Stratum D Reached |
| 684982.2 | 601991.3 | 0.1 | 134-SB-098 | 101 | 8/4/2014 | -8.0 | Stratum D Reached |
| 685016.6 | 602043.2 | -6.1 | 134-SB-032R | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685003.8 | 602054.0 | -6.4 | 134-SB-083 | 99 | 8/6/2014 | -5.4 | Stratum D Reached |
| 685001.8 | 602054.2 | -7.4 | 134-SB-S08 | 99 | 8/6/2014 | -5.2 | Stratum D Reached |
| 685033.1 | 602098.5 | -6.7 | 134-SB-063 | 98 | 8/8/2014 | -5.4 | Stratum D Reached |
| 684988.8 | 602075.4 | -7.4 | 134-SB-043 | 97 | 8/8/2014 | -4.6 | Stratum D Reached |
| 684959.7 | 602075.1 | -7.1 | 134-SB-054 | 96 | 8/12/2014 | -5.1 | Stratum D Reached |
| 685001.0 | 602117.0 | -6.1 | 134-SB-032 | 95 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684972.2 | 602122.1 | -6.1 | 134-SB-032R | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684941.6 | 602113.9 | -7.6 | 134-SB-044 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684945.3 | 602113.6 | -5.6 | 134-SB-084 | 93 | 8/14/2014 | -5.1 | Stratum D Reached |
| 684966.5 | 602131.5 | -6.4 | 134-SB-085 | 93 | 8/14/2014 | -4.4 | Stratum D Reached |
| 684994.9 | 602150.7 | -6.4 | 134-SB-086 | 93 | 8/14/2014 | -5.0 | Stratum D Reached |
| 684955.8 | 602150.0 | -6.1 | 134-SB-032R | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.6 | 602152.9 | -7.0 | 134-SB-046 | 91 | 8/18/2014 | -4.9 | Stratum D Reached |
| 684969.5 | 602171.1 | -6.5 | 134-SB-047 | 91 | 8/18/2014 | -5.2 | Stratum D Reached |
| 684915.0 | 602157.9 | -6.4 | 134-SB-150 | 90 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684948.5 | 602187.3 | -5.8 | 134-SB-158 | 90 | 8/20/2014 | -5.2 | Stratum D Reached |
| 684908.2 | 602155.7 | -8.0 | 134-SB-049 | 89 | 8/20/2014 | -5.9 | Stratum D Reached |
| 684943.6 | 602214.1 | -6.9 | 140-SB-035 | 88 | 8/25/2014 | -6.7 | Stratum D Reached |
| 684905.5 | 602180.6 | -7.8 | 140-SB-063 | 88 | 8/25/2014 | -6.1 | Stratum D Reached |
| 684875.3 | 602175.3 | -7.8 | 140-SB-062 | 87 | 8/25/2014 | -5.8 | Stratum D Reached |
| 684875.5 | 602187.9 | -7.3 | 140-SB-103 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684915.0 | 602239.0 | -6.1 | 140-SB-007 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |
| 684896.1 | 602229.3 | -6.6 | 140-SB-038 | 85 | 8/29/2014 | -5.7 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684862.9 | 602228.0 | -6.1 | 134-SB-032R | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684901.7 | 602269.3 | -5.3 | 140-SB-040 | 83 | 9/4/2014 | -5.7 | Stratum D Reached |
| 684826.5 | 602208.8 | -6.5 | 140-SB-051 | 83 | 9/4/2014 | -4.7 | Stratum D Reached |
| 684854.3 | 602237.3 | -6.7 | 140-SB-041 | 83 | 9/4/2014 | -4.9 | Stratum D Reached |
| 684771.0 | 602188.4 | -4.8 | 140-SB-044 | 82 | 9/10/2014 | -5.2 | Stratum D Reached |
| 684800.2 | 602210.9 | -6.5 | 140-SB-042 | 82 | 9/10/2014 | -4.7 | Stratum D Reached |
| 684865.2 | 602271.1 | -6.2 | 140-SB-064 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684830.9 | 602252.5 | -6.3 | 140-SB-066 | 81 | 9/17/2014 | -3.1 | Stratum D Reached |
| 684716.6 | 602169.4 | -0.2 | 140-SB-043 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684755.4 | 602222.4 | -5.7 | 140-SB-047 | 80 | 9/23/2014 | -4.6 | Stratum D Reached |
| 684823.4 | 602275.4 | -5.0 | 140-SB-048 | 80 | 9/17/2014 | -2.8 | Stratum D Reached |
| 684687.1 | 602171.5 | 0.3 | 140-SB-049 | 79 | 9/23/2014 | -3.9 | Stratum D Reached |
| 684721.0 | 602200.6 | -4.2 | 140-SB-046 | 79 | 9/23/2014 | -5.1 | Stratum D Reached |
| 684680.8 | 602178.0 | -3.3 | 140-SB-075 | 79 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684695.5 | 602194.5 | -4.8 | 140-SB-018 | 79 | 9/23/2014 | -4.4 | Stratum D Reached |
| 684767.0 | 602244.0 | -4.4 | 140-SB-010 | 79 | 9/23/2014 | -4.0 | Stratum D Reached |
| 684818.0 | 602299.0 | -5.4 | 140-SB-009 | 78 | 9/23/2014 | -3.3 | Stratum D Reached |
| 684855.0 | 602329.0 | -5.8 | 140-SB-065 | 78 | 9/23/2014 | -2.7 | Stratum D Reached |
| 684656.0 | 602192.0 | -2.7 | 140-SB-026 | 77 | 9/29/2014 | -2.3 | Stratum D Reached |
| 684740.4 | 602255.2 | -5.4 | 140-SB-082 | 77 | 9/29/2014 | -3.5 | Stratum D Reached |
| 684815.0 | 602348.7 | -3.4 | 140-SB-094 | 76 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684787.4 | 602330.2 | -0.4 | 140-SB-086 | 75 | 10/2/2014 | -4.0 | Stratum D Reached |
| 684744.9 | 602306.7 | -1.4 | 140-SB-083 | 75 | 10/2/2014 | -4.5 | Stratum D Reached |
| 684713.1 | 602276.0 | -0.4 | 140-SB-081 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684668.4 | 602240.2 | 0.1 | 140-SB-079 | 75 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684643.7 | 602221.3 | -4.2 | 140-SB-050 | 75 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684628.7 | 602233.7 | -2.9 | 140-SB-074 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684703.0 | 602285.6 | 2.6 | 140-SB-080 | 74 | 10/2/2014 | -3.1 | Stratum D Reached |
| 684733.7 | 602322.4 | 0.6 | 140-SB-084 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.9 | 602371.9 | 0.1 | 140-SB-088 | 74 | 10/2/2014 | -2.9 | Stratum D Reached |
| 684653.9 | 602259.3 | -1.4 | 140-SB-078 | 73 | 10/2/2014 | -3.6 | Stratum D Reached |
| 684755.3 | 602343.3 | 0.6 | 140-SB-085 | 73 | 10/7/2014 | -1.6 | Stratum D Reached |
| 684660.7 | 602300.1 | 0.9 | 140-SB-089 | 72 | 10/9/2014 | -2.8 | Stratum D Reached |
| 684693.1 | 602326.3 | -3.0 | 140-SB-090 | 72 | 10/7/2014 | -3.3 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684745.4 | 602367.1 | 1.0 | 140-SB-091 | 72 | 10/7/2014 | -0.1 | Target Elevation Reached |
| 684640.0 | 602295.0 | 1.9 | 140-SB-011 | 71 | 10/9/2014 | -4.0 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | 125-SB-029R | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684629.9 | 602309.5 | 5.8 | 140-SB-033 | 70 | 10/9/2014 | 2.4 | Target Elevation Reached |
| 684725.2 | 602383.8 | 0.4 | 125-SB-029R | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684642.9 | 602315.4 | 0.9 | 140-SB-089R | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684764.0 | 602429.2 | -7.0 | 140-SB-N07 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | 125-SB-029R | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684632.0 | 602327.7 | 5.8 | 140-SB-033R | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684669.3 | 602386.6 | -0.6 | 140-SB-070 | 68 | 10/21/2014 | -2.3 | Stratum D Reached |
| 684679.0 | 602393.0 | 0.0 | 140-SB-013 | 68 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684760.1 | 602448.4 | -1.4 | 140-SB-083R | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | 125-SB-029R | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684629.6 | 602343.1 | 5.8 | 140-SB-033R | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684749.9 | 602465.0 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684700.0 | 602423.0 | 0.8 | 140-SB-012 | 67 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684715.4 | 602440.1 | -1.0 | 140-SB-029 | 67 | 10/21/2014 | -1.4 | Stratum D Reached |
| 684662.8 | 602394.7 | -1.4 | 140-SB-083R | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -1.4 | 140-SB-083R | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | 125-SB-073R | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | 125-SB-029R | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684666.6 | 602417.0 | -2.7 | 140-SB-068 | 66 | 10/21/2014 | -3.0 | Stratum D Reached |
| 684735.5 | 602488.2 | -1.4 | 140-SB-083R | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | 125-SB-029R | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | 125-SB-073R | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | 125-SB-029R | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -1.4 | 140-SB-083R | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684666.2 | 602452.6 | 2.5 | 140-SB-030 | 64 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684735.4 | 602510.4 | -3.6 | 140-SB-067 | 64 | 10/24/2014 | -2.3 | Stratum D Reached |
| 684713.8 | 602503.3 | 4.3 | 140-SB-028 | 63 | 10/27/2014 | -2.4 | Stratum D Reached |
| 684727.7 | 602515.9 | -2.0 | 140-SB-104 | 63 | 10/27/2014 | -2.2 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | 125-SB-029R | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | 125-SB-073R | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | 125-SB-029R | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684653.2 | 602490.5 | 0.2 | 125-SB-057 | 61 | 10/24/2014 | -2.6 | Stratum D Reached |
| 684675.4 | 602508.2 | -1.2 | 125-SB-073 | 61 | 10/27/2014 | -2.5 | Stratum D Reached |

| SA-6 South Excavation: Confirmatory Points (Table 1.8) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684697.8 | 602526.3 | -2.2 | 125-SB-055 | 61 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684707.1 | 602549.9 | -3.4 | 125-SB-072 | 61 | 10/28/2014 | -2.8 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | 125-SB-029R | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | 125-SB-073R | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | 125-SB-029R | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | 125-SB-069R | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684678.4 | 602552.4 | -2.4 | 125-SB-061 | 59 | 10/28/2014 | -2.9 | Stratum D Reached |
| 684615.0 | 602501.1 | 0.5 | 125-SB-048 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684633.9 | 602516.6 | 0.6 | 125-SB-046 | 59 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684656.3 | 602534.7 | -1.4 | 125-SB-074 | 59 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684604.5 | 602498.0 | 2.1 | 125-SB-069R | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684916.0 | 601955.0 | -0.4 | 134-SB-026 | Area 41 | 12/10/2014 | -2.0 | Target Elevation Reached |

143-SB-43R: "R" designation indicates Reference Confirmatory Point for a designated Bottom Excavation Area. Coordinates come from Center Points within that specific cell.

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

| SA-6 South Excavation: Center Points (Table 2.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685460.6 | 601379.6 | 5.7 | C-153 | 153 | 4/24/2014 | 3.9 | Target Elevation Reached- Cell only partially excavated |
| 685497.5 | 601425.0 | 5.7 | C-152 | 152 | 4/24/2014 | 4.2 | Target Elevation Reached |
| 685453.0 | 601392.1 | 5.7 | C-152-1 | 152 | 4/24/2014 | 3.7 | Target Elevation Reached |
| 685467.8 | 601422.4 | 5.7 | C-151 | 151 | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685489.7 | 601438.8 | 5.7 | C-151-1 | 151 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685448.1 | 601407.0 | 5.7 | C-151-2 | 151 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685511.4 | 601454.1 | 3.3 | C-151-3 | 151 | 4/25/2014 | 3.0 | Target Elevation Reached |
| 685455.0 | 601431.7 | 5.7 | C-150 | 150 | 4/24/2014 | 2.1 | Target Elevation Reached |
| 685480.8 | 601450.0 | 5.7 | C-150-1 | 150 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685502.2 | 601463.5 | 2.8 | C-150-2 | 150 | 4/25/2014 | 2.8 | Target Elevation Reached |
| 685490.0 | 601478.5 | 5.7 | C-149 | 149 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685480.3 | 601489.8 | 5.7 | C-148 | 148 | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685469.5 | 601500.3 | 5.7 | C-147 | 147 | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685454.7 | 601508.1 | 5.7 | C-146 | 146A | 4/24/2014 | 5.6 | Target Elevation Reached |
| 685444.3 | 601518.5 | 5.7 | C-145 | 145A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685403.0 | 601506.0 | -4.3 | C-144 | 144A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685433.1 | 601528.8 | 5.7 | C-144-1 | 144A | 4/24/2014 | 5.4 | Target Elevation Reached |
| 685396.1 | 601517.4 | -4.3 | C-143 | 143A | 4/24/2014 | -5.3 | Target Elevation Reached |
| 685427.6 | 601544.4 | 5.7 | C-143-1 | 143A | 4/24/2014 | 5.5 | Target Elevation Reached |
| 685386.6 | 601530.7 | -4.3 | C-142 | 142A | 4/24/2014 | -4.8 | Target Elevation Reached |
| 685416.3 | 601555.6 | 5.7 | C-142-1 | 142A | 4/24/2014 | 1.9 | Target Elevation Reached |
| 685379.5 | 601542.9 | -4.3 | C-141 | 141A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685409.8 | 601567.0 | 2.1 | C-141-1 | 141A | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685371.7 | 601554.8 | -4.3 | C-140 | 140A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685401.1 | 601580.7 | 2.1 | C-140-1 | 140A | 4/24/2014 | -1.5 | Target Elevation Reached |
| 685352.9 | 601555.6 | -4.3 | C-139 | 139A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685390.7 | 601590.5 | -1.2 | C-139-1 | 139A | 4/24/2014 | -1.6 | Target Elevation Reached |
| 685368.1 | 601592.3 | -1.2 | C-138 | 138A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601567.5 | 2.1 | C-138-1 | 138A | 4/29/2014 | 1.7 | Target Elevation Reached |
| 685359.7 | 601603.5 | -1.2 | C-137 | 137A | 4/29/2014 | -1.5 | Target Elevation Reached |
| 685328.7 | 601577.4 | 2.1 | C-137-1 | 137A | 4/29/2014 | 1.8 | Target Elevation Reached |
| 685333.1 | 601413.4 | -7.5 | C-146-B | 146B | 5/5/2014 | -8.0 | Target Elevation Reached |
| 685320.3 | 601420.2 | -7.5 | C-145-B | 145B | 5/5/2014 | -7.8 | Target Elevation Reached |
| 685314.6 | 601432.4 | -7.5 | C-144-B | 144B | 5/8/2014 | -8.2 | Target Elevation Reached |
| 685307.0 | 601446.0 | -7.5 | C-143-B | 143B | 5/8/2014 | -8.0 | Target Elevation Reached |
| 685306.3 | 601465.9 | -7.5 | C142-B | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685304.8 | 601483.2 | -7.5 | C-141-B | 141B | 5/12/2014 | -7.9 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685295.5 | 601493.5 | -7.5 | C-140-B | 140B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685283.3 | 601504.6 | -7.5 | C-139-B | 139B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685266.5 | 601506.3 | -7.5 | C-138-B | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685277.8 | 601539.2 | 2.1 | C-137-B | 137B | 5/19/2014 | 1.6 | Target Elevation Reached |
| 685368.8 | 601630.8 | -1.2 | C-136-2 | 136 | 5/5/2014 | -1.5 | Target Elevation Reached |
| 685343.4 | 601610.1 | -2.5 | C-136 | 136 | 5/5/2014 | -2.8 | Target Elevation Reached |
| 685315.0 | 601587.9 | 2.1 | C-136-1 | 136 | 5/5/2014 | 1.7 | Target Elevation Reached |
| 685366.5 | 601648.5 | -1.2 | C-135-1 | 135 | 5/8/2014 | -1.4 | Target Elevation Reached |
| 685348.8 | 601634.5 | -2.5 | C-135 | 135 | 5/8/2014 | -2.6 | Target Elevation Reached |
| 685272.1 | 601572.6 | 2.1 | C-135-2 | 135 | 5/19/2014 | 1.7 | Target Elevation Reached |
| 685236.7 | 601544.8 | -1.2 | C-135-3 | 135 | 5/19/2014 | -1.3 | Target Elevation Reached |
| 685358.1 | 601659.9 | -1.2 | C-134-1 | 134 | 5/8/2014 | -1.5 | Target Elevation Reached |
| 685338.6 | 601644.9 | -2.5 | C-134 | 134 | 5/8/2014 | -2.9 | Target Elevation Reached |
| 685276.4 | 601595.5 | 2.1 | C-134-2 | 134 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685225.7 | 601553.7 | -1.2 | C-134-3 | 134 | 5/19/2014 | -1.2 | Target Elevation Reached |
| 685322.3 | 601651.3 | -1.2 | C-133-1 | 133 | 5/14/2014 | -1.7 | Target Elevation Reached |
| 685338.7 | 601665.5 | 0.4 | C-133 | 133 | 5/12/2014 | -0.1 | Target Elevation Reached |
| 685264.0 | 601607.6 | 2.1 | C-133-2 | 133 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685215.0 | 601563.9 | -1.2 | C-133-3 | 133 | 5/19/2014 | -1.4 | Target Elevation Reached |
| 685332.3 | 601683.5 | 2.1 | C-132-1 | 132 | 5/12/2014 | 1.7 | Target Elevation Reached |
| 685314.3 | 601666.4 | -1.2 | C-132 | 132 | 5/14/2014 | -1.5 | Target Elevation Reached |
| 685210.3 | 601579.7 | -2.5 | C-132-B | 132 | 5/22/2014 | -3.2 | Target Elevation Reached |
| 685194.1 | 601565.5 | -1.2 | C-132-B1 | 132 | 5/22/2014 | -1.6 | Target Elevation Reached |
| 685257.3 | 601619.3 | 2.1 | C-132-2 | 132 | 5/19/2014 | 1.8 | Target Elevation Reached |
| 685307.8 | 601677.9 | -1.2 | C-131 | 131 | 5/14/2014 | -1.4 | Target Elevation Reached |
| 685202.7 | 601594.7 | -2.5 | C-131-B | 131 | 5/22/2014 | -2.9 | Target Elevation Reached |
| 685184.3 | 601577.4 | -1.2 | C-131-B1 | 131 | 5/22/2014 | -2.1 | Target Elevation Reached |
| 685328.1 | 601694.6 | 2.1 | C-131-1 | 131 | 5/14/2014 | 1.9 | Target Elevation Reached |
| 685248.7 | 601630.4 | 2.1 | C-131-2 | 131 | 5/19/2014 | 2.0 | Target Elevation Reached |
| 685193.4 | 601601.4 | -2.5 | C-130-B | 130 | 5/22/2014 | -2.5 | Target Elevation Reached |
| 685300.8 | 601690.9 | -1.2 | C-130 | 130 | 5/19/2014 | -1.5 | Target Elevation Reached |
| 685176.5 | 601589.8 | -1.2 | C-130-B1 | 130 | 5/22/2014 | -1.9 | Target Elevation Reached |
| 685240.0 | 601641.1 | 2.1 | C-130-2 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685321.3 | 601708.0 | 2.1 | C-130-1 | 130 | 5/19/2014 | 1.9 | Target Elevation Reached |
| 685294.8 | 601706.8 | -1.2 | C-129-A | 129 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685311.8 | 601720.4 | 2.1 | C-129-A1 | 129 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685186.2 | 601619.2 | -7.5 | C-129-B | 129 | 5/27/2014 | -8.0 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685236.4 | 601661.1 | 0.4 | C-129-1 | 129 | 5/27/2014 | 0.1 | Target Elevation Reached |
| 685263.1 | 601682.1 | 2.1 | C-129-2 | 129 | 5/22/2014 | 1.8 | Target Elevation Reached |
| 685303.5 | 601732.5 | 2.1 | C-128-A-1 | 128 | 5/22/2014 | 1.9 | Target Elevation Reached |
| 685286.6 | 601718.1 | -1.2 | C-128-A | 128 | 5/22/2014 | -1.4 | Target Elevation Reached |
| 685269.5 | 601703.1 | 2.1 | C-128-A-2 | 128 | 5/22/2014 | 1.7 | Target Elevation Reached |
| 685245.3 | 601687.9 | 0.4 | C-128-A-3 | 128 | 5/29/2014 | 0.2 | Target Elevation Reached |
| 685174.0 | 601627.1 | -7.5 | C-128-B | 128 | 6/2/2014 | -7.5 | Target Elevation Reached |
| 685295.0 | 601745.8 | 0.4 | C-127-A | 127 | 5/29/2014 | 0.3 | Target Elevation Reached |
| 685271.3 | 601725.5 | -1.2 | C-127-A-1 | 127 | 5/29/2014 | -1.3 | Target Elevation Reached |
| 685237.1 | 601700.2 | 0.4 | C-127-A-2 | 127 | 6/2/2014 | 0.1 | Target Elevation Reached |
| 685171.9 | 601645.3 | -7.5 | C-127-B | 127 | 6/5/2014 | -7.5 | Target Elevation Reached |
| 685285.7 | 601758.3 | 0.4 | C-126-A-1 | 126 | 6/2/2014 | 0.4 | Target Elevation Reached |
| 685254.1 | 601730.8 | -1.2 | C-126-A | 126 | 6/2/2014 | -1.4 | Target Elevation Reached |
| 685166.8 | 601663.7 | -7.5 | C-126-3 | 126 | 6/10/2014 | -7.6 | Target Elevation Reached |
| 685122.3 | 601624.7 | -8.4 | C-126-4 | 126 | 6/10/2014 | -8.8 | Target Elevation Reached |
| 685277.9 | 601769.3 | 0.4 | C-125 | 125 | 6/2/2014 | -0.6 | Target Elevation Reached |
| 685241.9 | 601742.6 | -1.2 | C-125-1 | 125 | 6/5/2014 | -1.4 | Target Elevation Reached |
| 685158.0 | 601676.7 | -7.5 | C-125-2 | 125 | 6/17/2014 | -8.0 | Stratum D Reached |
| 685110.5 | 601637.9 | -8.4 | C-125-3 | 125 | 6/17/2014 | -8.1 | Stratum D Reached |
| 685270.5 | 601782.3 | 0.4 | C-124 | 124 | 6/10/2014 | 0.1 | Target Elevation Reached |
| 685261.7 | 601778.9 | -2.5 | C-124-1 | 124 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685230.8 | 601752.7 | -1.2 | C-124-2 | 124 | 6/10/2014 | -1.4 | Target Elevation Reached |
| 685172.8 | 601704.6 | -7.5 | C-124-4 | 124 | 6/17/2014 | -7.7 | Stratum D Reached |
| 685128.8 | 601669.1 | -8.7 | C-124-5 | 124 | 6/17/2014 | -7.8 | Stratum D Reached |
| 685104.8 | 601647.4 | -7.5 | C-124-6 | 124 | 6/17/2014 | -8.6 | Stratum D Reached |
| 685262.3 | 601792.9 | 0.4 | C-123 | 123 | 6/10/2014 | 0.3 | Target Elevation Reached |
| 685250.2 | 601784.5 | -2.5 | C-123-1 | 123 | 6/10/2014 | -2.8 | Target Elevation Reached |
| 685221.2 | 601763.9 | -1.2 | C-123-2 | 123 | 6/10/2014 | -1.7 | Target Elevation Reached |
| 685162.4 | 601719.5 | -7.5 | C-123-3 | 123 | 6/20/2014 | -7.7 | Stratum D Reached |
| 685121.9 | 601682.4 | -8.7 | C-123-4 | 123 | 6/20/2014 | -7.8 | Stratum D Reached |
| 685091.7 | 601659.6 | -7.5 | C-123-5 | 123 | 6/20/2014 | -8.1 | Stratum D Reached |
| 685252.4 | 601807.4 | 0.4 | C-122 | 122 | 6/13/2014 | 0.2 | Target Elevation Reached |
| 685234.5 | 601792.7 | -2.5 | C-122-1 | 122 | 6/13/2014 | -2.6 | Target Elevation Reached |
| 685207.9 | 601771.1 | -1.2 | C-122-2 | 122 | 6/13/2014 | -1.7 | Target Elevation Reached |
| 685154.7 | 601728.1 | -7.5 | C-122-5 | 122 | 6/20/2014 | -7.5 | Stratum D Reached |
| 685108.5 | 601694.5 | -8.7 | C-122-6 | 122 | 6/20/2014 | -6.9 | Stratum D Reached |
| 685086.9 | 601671.6 | -7.5 | C-122-3 | 122 | 6/20/2014 | -7.4 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.3) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685242.2 | 601818.1 | 0.4 | C-121 | 121 | 6/17/2014 | 0.3 | Target Elevation Reached |
| 685214.5 | 601794.9 | -2.5 | C-121-3 | 121 | 6/20/2014 | -2.6 | Target Elevation Reached |
| 685189.3 | 601776.9 | -1.2 | C-121-2 | 121 | 6/20/2014 | -1.7 | Target Elevation Reached |
| 685163.9 | 601758.7 | -2.5 | C-121-5 | 121 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685127.3 | 601725.9 | -7.5 | C-121-6 | 121 | 6/25/2014 | -7.0 | Stratum D Reached |
| 685104.7 | 601708.0 | -8.7 | C-121-7 | 121 | 6/25/2014 | -6.1 | Stratum D Reached |
| 685073.0 | 601686.3 | -7.5 | C-121-8 | 121 | 6/25/2014 | -7.1 | Stratum D Reached |
| 685233.4 | 601829.1 | 0.4 | C-120-1 | 120 | 6/20/2014 | 0.1 | Target Elevation Reached |
| 685205.7 | 601808.2 | -2.5 | C-120 | 120 | 6/20/2014 | -2.7 | Target Elevation Reached |
| 685179.5 | 601790.4 | -1.2 | C-120-2 | 120 | 6/20/2014 | -1.5 | Target Elevation Reached |
| 685153.6 | 601765.8 | -2.5 | C-120-3 | 120 | 6/25/2014 | -2.7 | Target Elevation Reached |
| 685095.6 | 601718.8 | -7.5 | C-120-4 | 120 | 6/25/2014 | -6.9 | Stratum D Reached |
| 685223.8 | 601840.5 | 0.4 | C-119 | 119 | 6/25/2014 | 0.0 | Target Elevation Reached |
| 685196.9 | 601820.6 | -2.5 | C-119-1 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685172.6 | 601798.3 | -1.2 | C-119-2 | 119 | 6/25/2014 | -1.2 | Target Elevation Reached |
| 685145.7 | 601780.4 | -2.5 | C-119-3 | 119 | 6/25/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601724.8 | -7.5 | C-119-4 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685208.4 | 601850.6 | 2.1 | C-118 | 118A | 6/25/2014 | -0.2 | Target Elevation Reached |
| 685197.6 | 601860.1 | 2.1 | C-117 | 117A | 6/25/2014 | -0.4 | Target Elevation Reached |
| 685189.6 | 601872.3 | 2.1 | C-116 | 116A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685176.1 | 601884.2 | 2.1 | C-115 | 115A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685069.7 | 601734.8 | -7.5 | C-118-1 | 118B | 6/30/2014 | -6.1 | Stratum D Reached |
| 685057.7 | 601744.9 | -7.5 | C-117-1 | 117B | 7/8/2014 | -6.5 | Stratum D Reached |
| 685031.8 | 601746.6 | -7.5 | C-116-1 | 116B | 7/8/2014 | -7.0 | Stratum D Reached |
| 685022.1 | 601754.6 | -7.5 | C-115-1 | 115B | 7/10/2014 | -5.9 | Stratum D Reached |
| 685177.7 | 601903.0 | 2.1 | C-114 | 114A | 6/30/2014 | 0.5 | Target Elevation Reached |
| 685147.1 | 601873.7 | -1.2 | C-114-1 | 114A | 6/30/2014 | -1.3 | Target Elevation Reached |
| 685014.9 | 601776.3 | 4.2 | C-114-2 | 114B | 7/10/2014 | 3.9 | Target Elevation Reached |
| 684985.2 | 601787.3 | 4.2 | C-114-3 | 114B | 7/17/2014 | -1.8 | Increased excavation depth - UST location |
| 685166.0 | 601912.1 | 2.1 | C-113-1 | 113A | 7/3/2014 | 0.9 | Target Elevation Reached |
| 685134.0 | 601884.4 | -1.2 | C-113-2 | 113A | 7/3/2014 | -1.7 | Target Elevation Reached |
| 685006.3 | 601780.6 | 4.2 | C-113-3 | 113B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684998.3 | 601772.8 | 4.2 | C-113-4 | 113B | 7/17/2014 | -2.1 | Increased excavation depth - UST location |
| 685157.5 | 601925.6 | 2.1 | C-112 | 112A | 7/8/2014 | 0.0 | Target Elevation Reached |
| 685124.9 | 601894.4 | -1.2 | C-112-1 | 112A | 7/3/2014 | -1.6 | Target Elevation Reached |
| 684996.9 | 601793.0 | 4.2 | C-112-2 | 112B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685002.7 | 601764.7 | 4.2 | C-112-3 | 112B | 7/17/2014 | -2.0 | Increased excavation depth - UST location |

| SA-6 South Excavation: Center Points (Table 2.4) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685145.9 | 601933.8 | 2.1 | C-111-1 | 111A | 7/8/2014 | 1.6 | Target Elevation Reached |
| 685114.0 | 601907.9 | -1.2 | C-111 | 111A | 7/8/2014 | -1.6 | Target Elevation Reached |
| 684986.6 | 601802.0 | 4.2 | C-111-4 | 111B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685137.8 | 601946.4 | 2.1 | C-110 | 110A | 7/10/2014 | 1.6 | Target Elevation Reached |
| 685105.5 | 601922.1 | -1.2 | C-110-1 | 110A | 7/8/2014 | -2.0 | Target Elevation Reached |
| 684971.7 | 601811.5 | 4.2 | C-110-4 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |
| 685129.5 | 601955.7 | 2.1 | C-109 | 109A | 7/10/2014 | 1.5 | Target Elevation Reached |
| 685097.4 | 601930.7 | -1.2 | C-109-1 | 109A | 7/10/2014 | -1.5 | Target Elevation Reached |
| 684960.2 | 601820.4 | 4.2 | C-109-4 | 109B | 7/17/2014 | 3.5 | Target Elevation Reached |
| 685119.7 | 601973.5 | 2.1 | C-108-1 | 108A | 7/17/2014 | 1.6 | Target Elevation Reached |
| 685087.5 | 601946.0 | -1.2 | C-108 | 108A | 7/10/2014 | -1.4 | Target Elevation Reached |
| 684950.4 | 601832.8 | 4.2 | C-108-4 | 108B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 685110.1 | 601981.8 | -4.3 | C-107-1 | 107A | 7/17/2014 | -4.8 | Stratum D Reached |
| 685069.0 | 601948.1 | -1.2 | C-107-2 | 107A | 7/17/2014 | -1.3 | Target Elevation Reached |
| 684939.3 | 601841.8 | 4.2 | C-107-4 | 107B | 7/17/2014 | 3.6 | Target Elevation Reached |
| 684928.5 | 601848.2 | 4.2 | C-106-4 | 106B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 685089.2 | 601980.6 | -4.3 | C-106 | 106A | 7/23/2014 | -5.3 | Stratum D Reached |
| 685046.6 | 601950.7 | -2.5 | C-106-1 | 106A | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685080.0 | 601994.5 | -4.3 | C-105 | 105 | 7/23/2014 | -5.2 | Stratum D Reached |
| 685029.8 | 601954.8 | -2.5 | C-105-1 | 105 | 7/23/2014 | -2.8 | Target Elevation Reached |
| 685062.9 | 602000.7 | -4.3 | C-104 | 104 | 7/29/2014 | -5.3 | Stratum D Reached |
| 685017.7 | 601961.5 | -2.5 | C-104-1 | 104 | 7/29/2014 | -5.7 | Stratum D Reached |
| 685027.6 | 601993.5 | -4.3 | C-103 | 103 | 7/29/2014 | -6.5 | Stratum D Reached |
| 685021.1 | 602004.8 | -4.3 | C-102 | 102 | 7/31/2014 | -6.1 | Stratum D Reached |
| 685014.2 | 602023.1 | -4.3 | C-101 | 101 | 8/4/2014 | -5.8 | Stratum D Reached |
| 685016.6 | 602043.2 | -4.3 | C-100 | 100 | 8/6/2014 | -6.2 | Stratum D Reached |
| 685015.8 | 602057.5 | -4.3 | C-99 | 99 | 8/6/2014 | -5.6 | Stratum D Reached |
| 685008.9 | 602072.0 | -4.3 | C-98 | 98 | 8/8/2014 | -5.2 | Stratum D Reached |
| 685000.4 | 602084.6 | -4.3 | C-97 | 97 | 8/8/2014 | -4.8 | Stratum D Reached |
| 684989.2 | 602093.1 | -4.3 | C-96 | 96 | 8/12/2014 | -5.5 | Stratum D Reached |
| 684975.6 | 602105.6 | -4.3 | C-95 | 95 | 8/12/2014 | -5.6 | Stratum D Reached |
| 684972.2 | 602122.1 | -4.3 | C-94 | 94 | 8/14/2014 | -4.6 | Stratum D Reached |
| 684974.5 | 602139.6 | -4.3 | C-93 | 93 | 8/14/2014 | -4.2 | Stratum D Reached |
| 684955.8 | 602150.0 | -4.3 | C-92 | 92 | 8/18/2014 | -4.6 | Stratum D Reached |
| 684946.7 | 602163.1 | -4.3 | C-91 | 91 | 8/18/2014 | -4.8 | Stratum D Reached |
| 684941.7 | 602173.1 | -4.3 | C-90 | 90 | 8/20/2014 | -4.9 | Stratum D Reached |
| 684922.3 | 602179.9 | -4.3 | C-89 | 89 | 8/20/2014 | -5.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.5) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684912.0 | 602189.2 | -4.3 | C-88 | 88 | 8/25/2014 | -6.3 | Stratum D Reached |
| 684895.8 | 602194.1 | -4.3 | C-87 | 87 | 8/25/2014 | -6.0 | Stratum D Reached |
| 684880.8 | 602203.6 | -4.3 | C-86 | 86 | 8/29/2014 | -5.8 | Stratum D Reached |
| 684872.8 | 602212.7 | -4.3 | C-85 | 85 | 8/29/2014 | -5.2 | Stratum D Reached |
| 684862.9 | 602228.0 | -4.3 | C-84 | 84 | 9/4/2014 | -5.6 | Stratum D Reached |
| 684820.9 | 602207.7 | -2.5 | C-83 | 83 | 9/4/2014 | -4.5 | Stratum D Reached |
| 684812.4 | 602218.7 | -2.5 | C-82 | 82 | 9/10/2014 | -4.1 | Stratum D Reached |
| 684788.9 | 602227.5 | -2.5 | C-81 | 81 | 9/17/2014 | -5.0 | Stratum D Reached |
| 684778.7 | 602237.4 | -2.5 | C-80 | 80 | 9/17/2014 | -4.6 | Stratum D Reached |
| 684759.2 | 602240.0 | -2.5 | C-79 | 79 | 9/23/2014 | -4.1 | Stratum D Reached |
| 684758.4 | 602256.3 | -2.5 | C-78 | 78 | 9/23/2014 | -3.4 | Stratum D Reached |
| 684753.6 | 602273.9 | -2.5 | C-77 | 77 | 9/29/2014 | -3.8 | Stratum D Reached |
| 684731.1 | 602272.7 | -2.5 | C-76 | 76 | 9/29/2014 | -3.0 | Stratum D Reached |
| 684735.0 | 602292.1 | -2.5 | C-75 | 75 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684732.6 | 602313.2 | -2.5 | C-74 | 74 | 10/2/2014 | -3.2 | Stratum D Reached |
| 684799.5 | 602381.3 | -2.5 | C-73 | 73 | 10/7/2014 | -2.7 | Stratum D Reached |
| 684752.7 | 602351.0 | 0.4 | C-73-1 | 73 | 10/7/2014 | 0.1 | Target Elevation Reached |
| 684662.4 | 602274.6 | -2.5 | C-73-2 | 73 | 10/7/2014 | -2.1 | Stratum D Reached |
| 684788.0 | 602395.1 | -2.5 | C-72 | 72 | 10/7/2014 | -2.5 | Stratum D Reached |
| 684743.1 | 602361.9 | 0.4 | C-72-1 | 72 | 10/7/2014 | -0.2 | Target Elevation Reached |
| 684664.8 | 602296.2 | -2.5 | C-72-2 | 72 | 10/7/2014 | -3.0 | Stratum D Reached |
| 684783.1 | 602411.4 | -2.5 | C-71 | 71 | 10/9/2014 | -2.7 | Stratum D Reached |
| 684734.3 | 602372.2 | 0.4 | C-71-1 | 71 | 10/9/2014 | 0.2 | Target Elevation Reached |
| 684652.0 | 602308.3 | -2.5 | C-71-2 | 71 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684772.6 | 602425.4 | -2.5 | C-70 | 70 | 10/9/2014 | -2.5 | Stratum D Reached |
| 684725.2 | 602383.8 | 0.4 | C-70-1 | 70 | 10/9/2014 | 0.1 | Target Elevation Reached |
| 684674.6 | 602346.3 | -2.5 | C-70-2 | 70 | 10/9/2014 | -2.4 | Stratum D Reached |
| 684642.9 | 602315.4 | 0.4 | C-70-3 | 70 | 10/9/2014 | -0.4 | Target Elevation Reached |
| 684626.5 | 602306.7 | 5.7 | C-70-4 | 70 | 10/9/2014 | 4.8 | Target Elevation Reached |
| 684762.8 | 602431.3 | -2.5 | C-69 | 69 | 10/14/2014 | -2.7 | Stratum D Reached |
| 684715.1 | 602395.2 | 0.4 | C-69-1 | 69 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684670.5 | 602360.9 | -2.5 | C-69-2 | 69 | 10/14/2014 | -2.4 | Stratum D Reached |
| 684632.0 | 602327.7 | 5.7 | C-69-3 | 69 | 10/14/2014 | 3.2 | Target Elevation Reached |
| 684760.1 | 602448.4 | -2.5 | C-68 | 68 | 10/14/2014 | -2.5 | Stratum D Reached |
| 684706.4 | 602407.6 | 0.4 | C-68-1 | 68 | 10/14/2014 | 0.1 | Target Elevation Reached |
| 684671.6 | 602375.8 | -2.5 | C-68-2 | 68 | 10/14/2014 | -2.2 | Stratum D Reached |
| 684629.6 | 602343.1 | 5.7 | C-68-3 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |

| SA-6 South Excavation: Center Points (Table 2.6) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 684749.9 | 602465.0 | -2.5 | C-67 | 67 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684698.4 | 602419.3 | 0.4 | C-67-1 | 67 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684662.8 | 602394.7 | -2.5 | C-67-2 | 67 | 10/21/2014 | -2.8 | Stratum D Reached |
| 684743.0 | 602477.1 | -2.5 | C-66 | 66 | 10/21/2014 | -2.1 | Stratum D Reached |
| 684726.5 | 602463.1 | 0.4 | C-66-1 | 66 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684704.4 | 602442.0 | -1.2 | C-66-2 | 66 | 10/21/2014 | -1.6 | Stratum D Reached |
| 684689.4 | 602431.1 | 0.4 | C-66-3 | 66 | 10/21/2014 | 0.1 | Target Elevation Reached |
| 684664.0 | 602411.1 | -2.5 | C-66-4 | 66 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684735.5 | 602488.2 | -2.5 | C-65 | 65 | 10/24/2014 | -2.5 | Stratum D Reached |
| 684719.9 | 602481.3 | 0.4 | C-65-1 | 65 | 10/24/2014 | 0.1 | Target Elevation Reached |
| 684701.3 | 602460.9 | -1.2 | C-65-2 | 65 | 10/24/2014 | -2.4 | Stratum D Reached |
| 684680.3 | 602442.8 | 0.4 | C-65-3 | 65 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684657.6 | 602419.2 | -2.5 | C-65-4 | 65 | 10/21/2014 | -3.2 | Stratum D Reached |
| 684713.4 | 602487.7 | -1.2 | C-64 | 64 | 10/24/2014 | -1.8 | Stratum D Reached |
| 684653.2 | 602444.8 | 0.4 | C-64-1 | 64 | 10/21/2014 | -4.0 | Increased excavation depth - UST location |
| 684701.6 | 602502.1 | -1.2 | C-63 | 63 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684648.6 | 602457.4 | 0.4 | C-63-1 | 63 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684686.3 | 602512.3 | -1.2 | C-62 | 62 | 10/27/2014 | -2.6 | Stratum D Reached |
| 684645.5 | 602469.8 | 0.4 | C-62-1 | 62 | 10/21/2014 | -0.3 | Target Elevation Reached |
| 684689.4 | 602527.1 | -1.2 | C-61 | 61 | 10/28/2014 | -2.7 | Stratum D Reached |
| 684639.4 | 602487.5 | 0.4 | C-61-1 | 61 | 10/21/2014 | -0.2 | Target Elevation Reached |
| 684675.5 | 602538.7 | -1.2 | C-60 | 60 | 10/28/2014 | -3.1 | Stratum D Reached |
| 684629.9 | 602496.7 | 0.4 | C-60-1 | 60 | 10/21/2014 | -0.4 | Target Elevation Reached |
| 684613.5 | 602491.1 | 2.1 | C-60-2 | 60 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 684665.2 | 602547.7 | -1.2 | C-59 | 59 | 10/27/2014 | -2.8 | Stratum D Reached |
| 684620.0 | 602510.0 | 0.4 | C-59-1 | 59 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684604.5 | 602498.0 | 2.1 | C-59-2 | 59 | 10/21/2014 | 1.7 | Target Elevation Reached |
| 685023.9 | 601966.6 | -2.5 | C-104L | 104 | 11/20/2014 | -6.9 | Stratum D Reached |
| 685033.9 | 601960.1 | -2.5 | C-105L | 105 | 11/20/2014 | -6.6 | Stratum D Reached |
| 685039.4 | 601938.6 | -2.5 | C-106L | 106 | 11/20/2014 | -6.3 | Stratum D Reached |
| 685043.6 | 601927.9 | Stratum D | C-107L | Lens Area | 11/25/2014 | -6.2 | Stratum D Reached |
| 685042.9 | 601906.9 | Stratum D | C-108L | Lens Area | 11/25/2014 | -6.8 | Stratum D Reached |
| 685057.6 | 601895.2 | Stratum D | C-109L | Lens Area | 12/8/2014 | -6.6 | Stratum D Reached |
| 685055.4 | 601873.1 | Stratum D | C-110L | Lens Area | 12/8/2014 | -7.5 | Stratum D Reached |
| 685071.5 | 601867.1 | Stratum D | C-111L | Lens Area | 12/8/2014 | -7.6 | Stratum D Reached |
| 685086.2 | 601861.8 | Stratum D | C-112L | Lens Area | 12/8/2014 | -7.3 | Stratum D Reached |

| SA-6 South Excavation: Center Points (Table 2.7) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685092.3 | 601848.6 | Stratum D | C-113L | Lens Area | 12/8/2014 | -7.0 | Stratum D Reached |

2 This is the Bottom Elevation identified in the 100% design. It is one of the predetermined bottom elevations that correspond with the 9 excavation intervals shown in the design.

Green shading indicates 100% Design Bottom Elevation Field Modified to reach < 20 PPM soils .

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685443.0 | 601355.0 | 5.8 | 073-SB-003 | 153 | 4/24/2014 | 4.0 | Target Elevation Reached |
| 685441.6 | 601380.0 | 6.7 | 073-SB-078 | 152 | 4/24/2014 | 3.9 | Target Elevation Reached |
| 685490.9 | 601459.8 | 7.8 | 073-SB-027 | 150 | 4/24/2014 | 3.8 | Target Elevation Reached |
| 685459.6 | 601448.4 | 5.9 | 073-SB-064 | 149 | 4/24/2014 | 2.0 | Target Elevation Reached |
| 685438.1 | 601430.2 | 8.8 | 073-SB-063 | 149 | 4/24/2014 | 1.8 | Target Elevation Reached |
| 685470.0 | 601487.0 | 5.9 | 073-SB-004 | 148 | 4/24/2014 | 5.7 | Target Elevation Reached |
| 685471.0 | 601475.6 | 4.3 | 073-SB-079 | 148 | 7/31/2014 | 4.3 | Expanded Excavation 4 |
| 685451.0 | 601460.9 | 7.1 | 073-SB-082 | 148 | 7/31/2014 | 2.2 | Expanded Excavation 4 |
| 685441.0 | 601496.0 | 4.0 | 073-SB-044 | 146A | 4/24/2014 | 5.4 | Expanded Excavation 3 |
| 685383.5 | 601506.5 | 0.9 | 073-SB-060 | 143A | 4/24/2014 | -4.4 | Target Elevation Reached |
| 685368.1 | 601516.7 | 0.4 | 073-SB-077 | 142A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685341.4 | 601558.3 | 2.9 | 073-SB-046 | 139A | 4/24/2014 | -4.5 | Target Elevation Reached |
| 685309.0 | 601571.0 | 3.8 | 073-SB-006 | 137A | 4/29/2014 | 1.9 | Target Elevation Reached |
| 685339.2 | 601410.1 | -5.7 | 073-SB-048 | 146B | 5/5/2014 | -7.7 | Target Elevation Reached |
| 685319.6 | 601464.4 | -5.4 | 073-SB-022 | 143B | 5/8/2014 | -7.5 | Target Elevation Reached |
| 685332.6 | 601487.8 | -3.6 | 073-SB-071 | 142B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685344.0 | 601523.8 | -4.1 | 073-SB-076 | 141B | 5/12/2014 | -7.6 | Target Elevation Reached |
| 685316.0 | 601542.0 | -6.2 | 073-SB-016 | 138B | 5/14/2014 | -7.8 | Target Elevation Reached |
| 685304.5 | 601530.7 | -5.8 | 073-SB-051 | 138B | 5/14/2014 | -7.5 | Target Elevation Reached |
| 685296.0 | 601562.0 | -0.6 | 073-SB-052 | 136 | 5/19/2014 | 2.1 | Expanded Excavation 3 |
| 685423.8 | 601494.3 | 1.6 | 073-SB-073 | 145A | 4/24/2014 | 5.4 | Expanded Excavation 3 |
| 685132.7 | 601748.9 | -1.7 | 134-SB-126 | 120 | 6/25/2014 | -7.2 | Stratum D Reached |
| 685210.2 | 601831.4 | -0.8 | 134-SB-072 | 119 | 6/25/2014 | -2.5 | Target Elevation Reached |
| 685116.0 | 601754.5 | -6.0 | 134-SB-157 | 119 | 6/30/2014 | -6.9 | Stratum D Reached |
| 685201.0 | 601844.0 | 0.9 | 134-SB-101 | 118A | 6/25/2014 | -0.1 | Target Elevation Reached |
| 685165.3 | 601806.2 | 3.5 | 134-SB-094 | 118B | 6/25/2014 | -1.6 | Target Elevation Reached |
| 685131.0 | 601787.0 | -2.3 | 134-SB-017 | 118B | 6/25/2014 | -3.3 | Target Elevation Reached |
| 685197.0 | 601868.0 | 6.0 | 134-SB-034 | 117A | 6/25/2014 | -0.3 | Target Elevation Reached |
| 685073.0 | 601769.4 | -6.5 | 134-SB-142 | 116B | 7/8/2014 | -6.3 | Stratum D Reached |
| 685168.1 | 601879.4 | -0.7 | 134-SB-058 | 115A | 6/30/2014 | -1.6 | Target Elevation Reached |
| 685137.3 | 601854.1 | 2.7 | 134-SB-073 | 115A | 6/30/2014 | -1.4 | Target Elevation Reached |
| 685043.3 | 601773.2 | 6.0 | 134-SB-152 | 115B | 7/10/2014 | -5.5 | Stratum D Reached |
| 685178.1 | 601893.6 | -3.0 | 134-SB-053 | 114 | 6/25/2014 | -0.1 | Expanded Excavation 3 |
| 685111.7 | 601863.3 | 2.2 | 134-SB-074 | 113A | 7/3/2014 | -1.3 | Expanded Excavation 3 |
| 685013.2 | 601803.0 | 6.0 | 134-SB-156 | 112B | 7/17/2014 | 3.7 | Target Elevation Reached |
| 685095.0 | 601890.0 | 2.2 | 134-SB-075 | 111A | 7/8/2014 | -1.6 | Expanded Excavation 3 |
| 684976.1 | 601816.3 | 6.1 | 134-SB-144 | 110B | 7/17/2014 | 3.9 | Target Elevation Reached |


| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.1) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685081.0 | 601928.1 | -5.5 | 134-SB-021 | 109A | 11/25/2014 | -5.8 | Expanded Excavation 3 |
| 685081.0 | 601936.0 | 3.0 | 134-SB-092 | 108 | 7/10/2014 | -1.6 | Expanded Excavation 3 |
| 685042.0 | 601935.0 | -0.3 | 134-SB-023 | 107A | 7/17/2014 | -2.7 | Expanded Excavation 3 |
| 684949.4 | 601849.3 | 6.1 | 134-SB-145 | 107B | 7/17/2014 | 3.8 | Target Elevation Reached |
| 684999.6 | 601940.6 | -4.5 | 134-SB-097 | 104 | 11/20/2014 | -7.2 | Stratum D Reached |
| 684969.0 | 601950.0 | -4.3 | 134-SB-025 | 103 | 7/31/2014 | -5.3 | Stratum D Reached |
| 684966.4 | 601991.2 | 0.8 | 134-SB-111 | 100 | 8/4/2014 | -5.8 | Stratum D Reached |
| 684986.0 | 602025.0 | -2.7 | 134-SB-027 | 100 | 8/6/2014 | -6.3 | Stratum D Reached |
| 684948.7 | 602072.2 | -3.2 | 134-SB-099 | 96 | 8/12/2014 | -5.4 | Stratum D Reached |
| 684925.0 | 602120.8 | -4.2 | 134-SB-050 | 92 | 8/18/2014 | -5.5 | Stratum D Reached |
| 684887.0 | 602147.0 | -2.1 | 134-SB-100 | 89 | 8/20/2014 | -5.8 | Stratum D Reached |
| 684869.0 | 602167.0 | -6.4 | 140-SB-061 | 87 | 8/25/2014 | -5.9 | Expanded Excavation 3 |
| 684821.2 | 602190.7 | -4.8 | 140-SB-060 | 84 | 9/4/2014 | -5.2 | Stratum D Reached |
| 684779.8 | 602174.6 | -0.8 | 140-SB-059 | 83 | 9/10/2014 | -5.6 | Stratum D Reached |
| 684727.5 | 602143.2 | 0.7 | 140-SB-076 | 83 | 9/10/2014 | -4.5 | Stratum D Reached |
| 684701.3 | 602132.8 | -0.8 | 140-SB-003 | 82 | 9/10/2014 | -4.8 | Stratum D Reached |
| 684686.4 | 602158.8 | -0.8 | 140-SB-105 | 80 | 9/17/2014 | -4.8 | Stratum D Reached |
| 684651.0 | 602180.0 | -2.1 | 140-SB-027 | 77 | 9/29/2014 | -2.8 | Stratum D Reached |
| 684630.0 | 602210.0 | -1.9 | 140-SB-077 | 75 | 10/2/2014 | -3.0 | Stratum D Reached |
| 684622.2 | 602287.4 | -2.0 | 140-SB-034 | 71 | 10/9/2014 | -3.0 | Stratum D Reached |
| 684597.0 | 602258.0 | -3.2 | 140-SB-025 | 71 | 10/9/2014 | -3.2 | Stratum D Reached |
| 684626.0 | 602343.0 | 6.8 | 140-SB-014 | 68 | 10/14/2014 | 3.5 | Target Elevation Reached |
| 684613.7 | 602330.2 | 6.1 | 140-SB-072 | 68 | 10/14/2014 | 4.5 | Target Elevation Reached |
| 684649.1 | 602367.2 | -1.0 | 140-SB-071 | 68 | 10/14/2014 | -2.8 | Stratum D Reached |
| 684648.1 | 602370.8 | -0.8 | 140-SB-032 | 67 | 10/21/2014 | -3.1 | Stratum D Reached |
| 684649.1 | 602409.4 | -2.3 | 140-SB-069 | 65 | 10/21/2014 | -3.4 | Stratum D Reached |
| 684629.1 | 602423.3 | 1.5 | 140-SB-031 | 64 | 10/21/2014 | -3.5 | Stratum D Reached |
| 684633.2 | 602474.4 | 0.4 | 125-SB-058 | 61 | 10/21/2014 | -0.1 | Target Elevation Reached |
| 684616.1 | 602485.8 | 3.0 | 125-SB-068 | 60 | 10/21/2014 | 1.8 | Target Elevation Reached |
| 684588.4 | 602494.2 | -3.5 | 125-SB-119 | 59 | 10/21/2014 | 1.5 | Expanded Excavation 3 |
| 685087.0 | 601829.1 | -6.0 | 134-SB-171 | Lens Area | 12/8/2014 | -6.1 | Expanded Excavation 4 |
| 685053.5 | 601827.8 | -6.5 | 134-SB-170 | Lens Area | 12/8/2014 | -6.8 | Expanded Excavation 4 |

| SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.2) | | | | | | | |
|---|---|---|---|---|---|---|---|
| Sidewall Target Coordinates | | | | | As-built Elevations | | |
| Northing | Easting | Elevation 2 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685029.7 | 601840.0 | -5.5 | 134-SB-175 | Lens Area | 12/8/2014 | -6.7 | Expanded Excavation 4 |
| 685003.5 | 601868.2 | -5.8 | 134-SB-177 | Lens Area | 12/8/2014 | -5.9 | Expanded Excavation 4 |
| 684917.7 | 601947.9 | -1.2 | 134-SB-087 | Area 41 | 12/10/2014 | -2.1 | Target Elevation Reached |
| 684936.3 | 601954.8 | -1.2 | 134-SB-088 | Area 41 | 12/10/2014 | -2.4 | Target Elevation Reached |
| 684918.0 | 601975.0 | -1.2 | 134-SB-089 | Area 41 | 12/10/2014 | -1.7 | Target Elevation Reached |
| 684904.3 | 601963.0 | -1.2 | 134-SB-090 | Area 41 | 12/10/2014 | -1.6 | Target Elevation Reached |

3 Horizontal and/or vertical expansion of excavation due to visual inspection and analytical sampling resulted in removal of the PDI Sidewall Sample. The objectives of the 100% design and the target excavation limits were achieved.

4 Additional sidewall sample collected and analyzed to establish expanded excavation limit.

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.**



1/27/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**ATTACHMENT B-3**

**SA-6 SOUTH EXCAVATION SITE 163**

**Table 1.0 PDI Locations**

**Table 3.0 Sidewall**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Excavation (Site 163): Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685185.6 | 601432.8 | 5.8 | 163-SB-107 | N/A | 10/30/2014 | 5.0 | Area 43 - Target Elevation Reached |
| 685169.6 | 601446.1 | 6.0 | 163-SB-020 | N/A | 10/30/2014 | 4.8 | Area 43 - Target Elevation Reached |
| 685102.9 | 601588.4 | 5.2 | 163-SB-015 | N/A | 10/30/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685125.0 | 601586.5 | 6.3 | 163-SB-043 | N/A | 10/30/2014 | 5.7 | Area 163 - Target Elevation Reached |
| 685037.6 | 601660.2 | 4.5 | 163-SB-010 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685029.9 | 601632.6 | 5.2 | 163-SB-013 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685028.1 | 601625.3 | 6.8 | 163-SB-064 | N/A | 11/5/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 685064.3 | 601635.5 | 4.9 | 163-SB-112 | N/A | 11/5/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685069.7 | 601654.2 | 5.0 | 163-SB-011 | N/A | 11/5/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 685054.7 | 601600.3 | 3.6 | 163-SB-063 | N/A | 10/31/2014 | 3.5 | Area 163 - Target Elevation Reached |
| 685062.5 | 601603.2 | 4.6 | 163-SB-014 | N/A | 10/31/2014 | 3.4 | Area 163 - Target Elevation Reached |
| 685100.1 | 601617.6 | 5.3 | 163-SB-012 | N/A | 10/31/2014 | 3.7 | Area 163 - Target Elevation Reached |
| 684984.0 | 601680.9 | 5.5 | 163-SB-101 | N/A | 11/7/2014 | 5.0 | Area 163 - Target Elevation Reached |
| 684997.7 | 601696.5 | 5.5 | 163-SB-093 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685012.8 | 601711.3 | 5.6 | 163-SB-092 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 685001.4 | 601739.4 | 6.6 | 163-SB-086 | N/A | 11/7/2014 | 4.8 | Area 163 - Target Elevation Reached |
| 684854.7 | 601827.8 | 5.7 | 163-SB-008 | N/A | 11/12/2014 | 5.1 | Area 163 - Target Elevation Reached |
| 684889.4 | 601833.1 | 6.2 | 163-SB-072 | N/A | 11/12/2014 | 4.7 | Area 163 - Target Elevation Reached |
| 684901.6 | 601758.2 | 7.6 | 163-SB-065 | N/A | 11/12/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 684913.3 | 601758.5 | 5.7 | 163-SB-009 | N/A | 11/12/2014 | 5.1 | Area 163 - Target Elevation Reached |
| 684943.7 | 601757.2 | 5.9 | 163-SB-073 | N/A | 11/12/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684970.6 | 601767.7 | 3.3 | 163-SB-007 | N/A | 11/12/2014 | 3.1 | Area 163 - Target Elevation Reached |
| 684970.3 | 601782.2 | 3.3 | 163-SB-060 | N/A | 11/12/2014 | 2.6 | Area 163 - Target Elevation Reached |
| 684784.2 | 602004.7 | 4.9 | 163-SB-114 | N/A | 12/12/2014 | 4.0 | Area 42 - Target Elevation Reached |
| 684779.6 | 601989.9 | 4.8 | 163-SB-003 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |
| 684756.5 | 602015.6 | 5.8 | 163-SB-108 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |

1 This is the actual elevation of the PDI Bottom sample included in the 100% design.

* Elevations based on NGVD 1929 Datum. Coordinates are in the New Jersey state plane coordinate system, NAD 1983.

## SA-6 South Excavation: Sidewall Confirmatory Points (Table 3.0)

| Sidewall Target Coordinates | | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Corresponding Cell # | Date Obtained | Elevation | Comments |
| 685197.1 | 601418.1 | 5.2 | 163-SB-097 | N/A | 10/30/2014 | 5.0 | Area 43 - Target Elevation Reached |
| 685181.4 | 601455.3 | 6.0 | 163-SB-035 | N/A | 10/30/2014 | 5.1 | Area 43 - Target Elevation Reached |
| 685158.1 | 601437.3 | 7.0 | 163-SB-061 | N/A | 10/30/2014 | 8.9 | Area 43 - Deferred to preserve Bulk Head 2 |
| 685160.1 | 601457.8 | 7.5 | 163-SB-036 | N/A | 10/30/2014 | 4.6 | Area 43 - Target Elevation Reached |
| 685026.9 | 601624.6 | 7.8 | 163-SB-076 | N/A | 11/5/2014 | 4.0 | Area 163 - Target Elevation Reached |
| 685045.9 | 601596.1 | 7.9 | 163-SB-077 | N/A | 10/31/2014 | 3.2 | Area 163 - Target Elevation Reached |
| 685072.2 | 601547.5 | 7.1 | 163-SB-062 | N/A | 10/30/2014 | 3.6 | Area 163 - Target Elevation Reached |
| 684993.2 | 601662.1 | 6.4 | 163-SB-100 | N/A | 11/7/2014 | 4.2 | Area 163 - Target Elevation Reached |
| 684961.1 | 601691.9 | 7.3 | 163-SB-113 | N/A | 11/7/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684871.6 | 601791.8 | 5.6 | 163-SB-066 | N/A | 11/12/2014 | 7.2 | Area 163 - Deferred to preserve Bulk Head 2 |
| 684893.3 | 601758.8 | 5.6 | 163-SB-085 | N/A | 11/12/2014 | 4.8 | Area 163 - Target Elevation Reached |
| 684929.4 | 601730.4 | 5.2 | 163-SB-084 | N/A | 11/12/2014 | 5.0 | Area 163 - Target Elevation Reached |
| 684891.6 | 601853.5 | 6.9 | 163-SB-051 | N/A | 11/12/2014 | 4.5 | Area 163 - Target Elevation Reached |
| 684852.1 | 601829.3 | 5.6 | 163-SB-052 | N/A | 11/12/2014 | 4.9 | Area 163 - Target Elevation Reached |
| 684843.0 | 601829.0 | 5.6 | 163-SB-067 | N/A | 11/12/2014 | 6.8 | Area 163 - Deferred to preserve Bulk Head 2 |
| 684797.0 | 601966.1 | 5.7 | 163-SB-069 | N/A | 12/12/2014 | 4.1 | Area 42 - Target Elevation Reached |
| 684807.5 | 602016.1 | 5.9 | 134-SB-146 | N/A | 12/12/2014 | 4.1 | Area 42 - Target Elevation Reached |
| 684750.1 | 602027.2 | 6.4 | 163-SB-091 | N/A | 12/12/2014 | 4.5 | Area 42 - Target Elevation Reached |
| 684747.0 | 601998.4 | 6.0 | 163-SB-058 | N/A | 12/12/2014 | 4.4 | Area 42 - Target Elevation Reached |
| 684751.6 | 601971.2 | 5.6 | 163-SB-071 | N/A | 12/12/2014 | 4.2 | Area 42 - Target Elevation Reached |
| 685138.0 | 601563.6 | 6.2 | 163-SB-078 | N/A | 12/22/2014 | 4.7 | Area 163-1 - Target Elevation reached |
| 685083.7 | 601558.5 | 6.0 | 163-SB-017 | N/A | 12/22/2014 | 4.3 | Area 163-1 - Target Elevation reached |
| 685165.5 | 601546.0 | 6.5 | 163-SB-080 | N/A | 12/22/2014 | 5.6 | Area 163-1 - Target Elevation reached |

2 Work adjacent the bulkhead had been deferred and will be completed in accordance with the Consent Order Consolidating the 100% Design for Study Area 6 North and Study Area 6 South filed into the court on July 9, 2013.

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades.**

R. Thomas Hugg 1/26/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**ATTACHMENT B-4**

**FIGURE 1.2 - SA-6 SOUTH AS-BUILT EXCAVATION CONFIRMATION POINTS**

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

CONFIRMATORY BOTTOM SAMPLE ELEVATION

CONFIRMATORY SIDEWALL SAMPLE ELEVATION

0.0 POINT ELEVATION

POINT POINT DESCRIPTION

EXCAVATION TO STRATUM D

DESIGN EXCAVATION AREA

DESIGN EXCAVATION LIMIT

0 40 80 160

SCALE IN FEET

J.H. 02/01/16

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME


FIGURE 1.2
EXCAVATION CONFIRMATION POINTS

PROJECT NAME & LOCATION

HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT B-5**

**FIGURE 1.3 - SA-6 SOUTH EXCAVATION CELL LAYOUT**




ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

FIGURE 1.3
EXCAVATION CELL LAYOUT

PROJECT NAME & LOCATION


HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

J.H. 02/01/16

**ATTACHMENT C**


**DRAWINGS S-201, S-202, S-203**

**HYDRAULIC BARRIER PLAN & PROFILE**




NOTES:

1. PLAN LOCATION AND TOP ELEVATION OF HYDRAULIC BARRIER BASED ON SURVEY COMPLETED BY ENTACT DURING INSTALLATION. ADDITIONAL SURVEY WILL BE COMPLETED WHEN THE HYDRAULIC BARRIER IS CUT TO FINAL DESIGN ELEVATION DURING LINER INSTALLATION.
2. BOTTOM OF HYDRAULIC BARRIER AND EXTENT OF EPOXY COATING BASED ON ENTACT TOP SURVEY AND SHEET PILE FABRICATION DRAWINGS. ALL SHEETS DELIVERED TO THE SITE WERE INSPECTED BY AMEC PERSONNEL TO VERIFY LENGTHS AND EPOXY COATING.
3. STRATUM D SHOWN FOR REFERENCE ONLY AND IS BASED ON GEOTECHNICAL BORINGS COMPLETED DURING THE PRELIMINARY DESIGN INVESTIGATION.




SCALE IN FEET
VERTICAL SCALE: 1" = 10'

SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APV'D |
|---|---|---|---|---|---|
| 1 | 3/20/15 | TDD | RJR | TDD | |

DECLARATION #1 - ISSUED FOR CLIENT REVIEW

| REVISION | BY | APV'D |
|---|---|---|
| | TDD | SGS |

SGS
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER

3/20/15

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS


CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | 2/17/15 |
| PROJ | 3480-10-0027 |
| DWG | S-201 |
| SHEET | OF |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 North and South As-Builts\SA-6 South VHBIS-201 Hydraulic Barrier Profile.dwg PLOT DATE: Sat, 28 Mar 2015 PLOT TIME: 3:23 PM




NOTES:

1. REFER TO NOTES 1 THRU 4 ON SHEET S-201




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 3/20/15 | TDD | DR | RJR | TDD |

DECLARATION #1 - ISSUED FOR CLIENT REVIEW

| REVISION | BY | APVD |
|---|---|---|
| | TDD | SGS |

SGS NJ PROFESSIONAL ENGINEER LICENSE NUMBER

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394


DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 888 - 2829

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | 2/17/15 |
| PROJ | 3480-10-0027 |
| DWG | S-202 |
| SHEET | OF |




MATCH LINE SHEET S-202


NOTES:

1. REFER TO NOTES 1 THRU 4 ON SHEET S-201




SEE NOTE HB19 ON SHEET GN-003

SHEET SEALING DETAIL F
NTS
SN-201 CN-301




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 3/20/15 | TDD | TDD | RJR | TDD |

REVISION

1 - DECLARATION #1 - ISSUED FOR CLIENT REVIEW

| BY | APVD |
|---|---|
| TDD | SGS |

SGS NJ PROFESSIONAL ENGINEER LICENSE NUMBER

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suites 113
Hamilton, NJ, 08619
(609) 689 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/17/15 |
| PROJ | 3480-10-0027 |
| DWG | S-203 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**ATTACHMENT D**

**BACKFILL**

**ATTACHMENT D-1**

**FIGURE 2.1 - SA-6 SOUTH AS-BUILT - BACKFILL TOPOGRAPHIC PROGRESS MAP**

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

NOTE:
CONTOURS SHOWN HEREON REPRESENT THE CURRENT TOP OF BACKFILL AS SURVEYED BY ENTACT ON 12/29/2014.

AS BUILT BOTTOM OF EXCAVATION LIMIT

MAJOR CONTOUR

MINOR CONTOUR

0 40 80 160
SCALE IN FEET

ENTACT 302 UnRy Plaza Latrobe, PA 15650

DRAWING NAME:
FIGURE 2.1
BACKFILL TOPOGRAPHIC PROGRESS MAP

PROJECT NAME & LOCATION:
HONEYWELL SA-6 SOUTH REMEDIATION
JERSEY CITY, NJ

JH 9/15/15

**ATTACHMENT D-2**


**Figure Backfill Compaction Locations BF-01 to B-45**

**Figure Backfill Compaction Locations BF-46 to BF-94**

**Figure Backfill Compaction Locations BF-95 to BF-136**

**Figure Backfill Compaction Locations RF-01 to RF-21**

**Figure Backfill Compaction Locations RF 22 to RF-39**




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JN 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-01 TO BF-45

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-46 TO BF-94

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on testing frequency specified in 02315 3.13 A. 2. a.

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| | | | | | | JH | 9/15/15 |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS EVERY 2,500 SF BF-95 TO BF-136

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ




NOTE:


Testing locations are based on reduced testing frequency specified in 02315 3.13 A. 3.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-01 TO RF-21

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE:

Testing locations are based on reduced testing frequency specified in 02315 3.13 A. 3.

JH 9/15/15

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: BACKFILL COMPACTION LOCATIONS
5 TESTS PER ACRE
RF-22 TO RF-39, SITE 163, AND LOAM

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT D-3**

**Field Density Test Summary Log Table (Pages 1 to 7)**

**Field Density Test Summary Log Table (Pages 1 to 4)**

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-01 | | 684138.4 | 603182.3 | -0.5 | | | | | | | 4 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-01-01 | 12/5/2013 | 684144.2 | 603184.2 | 1.0 | 136.4 | 3.7 | 142.6 | 7.8 | 96 | 95 | 4 | Weldon WC QP | | Sor |
| 3 | BF-01-02 | 12/5/2013 | 684137.8 | 603181.7 | 1.9 | 139.9 | 4.3 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 4 | BF-01-03 | 12/6/2013 | 684140.2 | 603182.7 | 2.5 | 141.2 | 5.0 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 5 | BF-01-04 | 12/6/2013 | 684136.6 | 603190.0 | 3.5 | 141.2 | 5.6 | 142.6 | 7.8 | 99 | 95 | 4 | Weldon WC QP | | Sor |
| 6 | BF-01-05 | 12/6/2013 | 684134.9 | 603186.7 | 4.5 | 143.2 | 4.8 | 142.6 | 7.8 | 100 | 95 | 4 | Weldon WC QP | | Sor |
| 7 | BF-01-06 | 12/6/2013 | 684141.1 | 603182.6 | 5.8 | 139.6 | 6.0 | 142.6 | 7.8 | 98 | 95 | 4 | Weldon WC QP | | Sor |
| 8 | BF-01-07 | 12/10/2013 | 684147.6 | 603186.8 | 6.2 | 146.7 | 5.1 | 142.6 | 7.8 | 103 | 95 | 4 | Weldon WC QP | | Sor |
| 9 | BF-01-08 | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 120.1 | 3.4 | 128.9 | 12.1 | 93 | 95 | 4 | Weldon WC Screenings | recompact lift | Sor |
| 9 | BF-01-08R | 12/10/2013 | 684140.2 | 603189.6 | 7.1 | 129.9 | 4.9 | 128.9 | 12.1 | 101 | 95 | 4 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 10 | BF-01-09 | 12/12/2013 | 684130.1 | 603175.5 | 8.1 | 126.4 | 3.3 | 128.9 | 12.1 | 98 | 95 | 4 | Weldon WC Screenings | | Sor |
| 11 | BF-01-10 | 12/31/2013 | 684140.0 | 603184.3 | 9.0 | 139.6 | 7.4 | 128.9 | 12.1 | 108 | 95 | 4 | Weldon WC Screenings | | Sor |
| 1 | BF-02 | | 684153.8 | 603153.9 | -0.6 | | | | | | | 6 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-02-01 | 12/5/2013 | 684162.8 | 603161.3 | 1.4 | 138.2 | 5.7 | 142.6 | 7.8 | 97 | 95 | 6 | Weldon WC QP | | Sor |
| 3 | BF-02-02 | 12/5/2013 | 684160.8 | 603162.3 | 2.4 | 136.2 | 4.5 | 142.6 | 7.8 | 96 | 95 | 6 | Weldon WC QP | | Sor |
| 4 | BF-02-03 | 12/6/2013 | 684157.7 | 603161.3 | 2.7 | 147.2 | 5.6 | 142.6 | 7.8 | 103 | 95 | 6 | Weldon WC QP | | Sor |
| 5 | BF-02-04 | 12/6/2013 | 684145.7 | 603162.1 | 3.7 | 143.5 | 5.0 | 142.6 | 7.8 | 101 | 95 | 6 | Weldon WC QP | | Sor |
| 6 | BF-02-05 | 12/6/2013 | 684156.9 | 603171.0 | 4.4 | 145.7 | 4.1 | 142.6 | 7.8 | 102 | 95 | 6 | Weldon WC QP | | Sor |
| 7 | BF-02-06 | 12/6/2013 | 684150.1 | 603155.4 | 5.6 | 140.4 | 4.6 | 142.6 | 7.8 | 98 | 95 | 6 | Weldon WC QP | | Sor |
| 8 | BF-02-07 | 12/10/2013 | 684135.5 | 603153.5 | 6.1 | 149.4 | 4.0 | 142.6 | 7.8 | 105 | 95 | 6 | Weldon WC QP | | Sor |
| 9 | BF-02-08 | 12/10/2013 | 684157.9 | 603174.9 | 7.2 | 125.8 | 5.2 | 128.9 | 12.1 | 98 | 95 | 6 | Weldon WC Screenings | | Sor |
| 1 | BF-03 | | 684179.9 | 603119.5 | -1.2 | | | | | | | 9 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-03 | | | | | | | | | | | 9 | Type A Material | No compaction testing required | |
| 3 | BF-03-01* | 11/22/2013 | 684198.1 | 603131.6 | 0.2 | 133.3 | 3.4 | 142.6 | 7.8 | 93 | 95 | 9 | Weldon WC QP | | Sor |
| 4 | BF-03-02* | 11/22/2013 | 684155.7 | 603111.6 | 1.5 | 130.8 | 2.8 | 142.6 | 7.8 | 92 | 95 | 9 | Weldon WC QP | | Sor |
| 5 | BF-03-03 | 12/5/2013 | 684177.4 | 603121.5 | 2.5 | 135.7 | 2.0 | 128.9 | 12.1 | 105 | 95 | 9 | Weldon WC Screenings | | Sor |
| 6 | BF-03-04 | 12/12/2013 | 684180.5 | 603126.9 | 4.6 | 124.7 | 3.2 | 128.9 | 12.1 | 97 | 95 | 9 | Weldon WC Screenings | | Sor |
| 7 | BF-03-05 | 12/12/2013 | 684177.1 | 603132.4 | 5.3 | 132.5 | 2.8 | 128.9 | 12.1 | 103 | 95 | 9 | Weldon WC Screenings | | Sor |
| 8 | BF-03-06 | 12/16/2013 | 684172.4 | 603128.5 | 6.4 | 128.3 | 2.9 | 128.9 | 12.1 | 100 | 95 | 9 | Weldon WC Screenings | | Sor |
| 9 | BF-03-07 | 1/6/2014 | 684177.1 | 603113.8 | 6.6 | 131.2 | 10.4 | 128.9 | 12.1 | 102 | 95 | 9 | Weldon WC Screenings | | Sor |
| 10 | BF-03-08 | 1/9/2014 | 684178.2 | 603121.8 | 8.2 | 128.2 | 5.9 | 128.9 | 12.1 | 99 | 95 | 9 | Weldon WC Screenings | | Sor |
| 1 | BF-04 | | 684195.7 | 603093.1 | -1.5 | | | | | | | 11 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-04 | | | | | | | | | | | 11 | Type A Material | No compaction testing required | |
| 3 | BF-04-01 | 12/5/2013 | 684198.0 | 603094.8 | 2.6 | 131.0 | 3.6 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 4 | BF-04-02 | 12/12/2013 | 684206.6 | 603104.7 | 3.5 | 125.8 | 3.9 | 128.9 | 12.1 | 98 | 95 | 11 | Weldon WC Screenings | | Sor |
| 5 | BF-04-03 | 12/16/2013 | 684217.5 | 603111.1 | 4.9 | 129.9 | 2.9 | 128.9 | 12.1 | 101 | 95 | 11 | Weldon WC Screenings | | Sor |
| 6 | BF-04-04 | 12/31/2013 | 684213.6 | 603115.0 | 5.9 | 124.6 | 3.2 | 128.9 | 12.1 | 97 | 95 | 11 | Weldon WC Screenings | | Sor |
| 7 | BF-04-05 | 1/9/2014 | 684195.8 | 603100.0 | 8.2 | 131.2 | 4.8 | 128.9 | 12.1 | 102 | 95 | 11 | Weldon WC Screenings | | Sor |
| 1 | BF-05 | | 684200.8 | 603078.4 | -1.8 | | | | | | | 12 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-05 | | | | | | | | | | | 12 | Type A Material | No compaction testing required | |
| 3 | BF-05-01 | 12/5/2013 | 684185.2 | 603057.9 | 2.6 | 133.8 | 4.7 | 128.9 | 12.1 | 104 | 95 | 12 | Weldon WC Screenings | | Sor |
| 4 | BF-05-02 | 12/12/2013 | 684179.9 | 603057.7 | 3.0 | 121.5 | 3.0 | 128.9 | 12.1 | 94 | 95 | 12 | Weldon WC Screenings | recompact lift | Sor |
| 4 | BF-05-02R | 12/16/2013 | 684186.2 | 603070.2 | 3.1 | 133.0 | 9.3 | 128.9 | 12.1 | 103 | 95 | 12 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-05-03 | 12/31/2013 | 684181.6 | 603060.8 | 4.5 | 124.7 | 2.9 | 128.9 | 12.1 | 97 | 95 | 12 | Weldon WC Screenings | | Sor |
| 6 | BF-05-04 | 1/9/2013 | 684186.1 | 603053.5 | 5.8 | 129.7 | 3.3 | 128.9 | 12.1 | 101 | 95 | 12 | Weldon WC Screenings | | Sor |
| 7 | BF-05-05 | 1/9/2013 | 684180.6 | 603048.6 | 6.5 | 131.1 | 3.4 | 128.9 | 12.1 | 102 | 95 | 12 | Weldon WC Screenings | | Sor |
| 8 | BF-05-06 | 3/19/2014 | 684180.6 | 603060.4 | 7.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 12 | Weldon WC Screenings | | Sor |
| 1 | BF-06 | | 684214.8 | 603050.6 | -1.7 | | | | | | | 14 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-06 | | | | | | | | | | | 14 | Crushed concrete | No compaction testing required | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 3 | BF-06-01 | 12/31/2013 | 684229.9 | 603061.3 | 2.2 | 137.7 | 3.4 | 128.9 | 12.1 | 107 | 95 | 14 | Weldon WC Screenings | | Sor |
| 4 | BF-06-02 | 12/31/2013 | 684228.8 | 603062.8 | 3.5 | 133.1 | 3.4 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 5 | BF-06-03 | 1/6/2014 | 684234.0 | 603066.8 | 4.2 | 123.7 | 9.5 | 128.9 | 12.1 | 96 | 95 | 14 | Weldon WC Screenings | | Sor |
| 6 | BF-06-04 | 1/9/2014 | 684230.8 | 603071.3 | 6.2 | 133.1 | 4.2 | 128.9 | 12.1 | 103 | 95 | 14 | Weldon WC Screenings | | Sor |
| 7 | BF-06-05 | 1/9/2014 | 684213.9 | 603095.7 | 7.3 | 133.8 | 5.0 | 128.9 | 12.1 | 104 | 95 | 14 | Weldon WC Screenings | | Sor |
| 1 | BF-07 | | 684222.7 | 603033.3 | -0.8 | | | | | | | 15 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-07 | | | | | | | | | | | 15 | Crushed concrete | No compaction testing required | |
| 3 | BF-07-01 | 12/31/2013 | 684196.2 | 603014.9 | 2.5 | 133.1 | 2.6 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | | Sor |
| 4 | BF-07-02 | 12/31/2013 | 684192.8 | 603021.1 | 3.9 | 133.2 | 3.4 | 128.9 | 12.1 | 103 | 95 | 15 | Weldon WC Screenings | Numbering error; skipped from 02 to 04 | Sor |
| 6 | BF-07-04 | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 118.5 | 3.9 | 128.9 | 12.1 | 92 | 95 | 15 | Weldon WC Screenings | recompact lift | Sor |
| 6 | BF-07-04R | 1/9/2014 | 684196.9 | 603018.8 | 5.7 | 122.6 | 4.3 | 128.9 | 12.1 | 95 | 95 | 15 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 7 | BF-07-05 | 1/9/2014 | 684195.0 | 603021.0 | 6.4 | 128.4 | 6.7 | 128.9 | 12.1 | 100 | 95 | 15 | Weldon WC Screenings | | Sor |
| 1 | BF-08 | | 684221.8 | 603013.0 | -0.7 | | | | | | | 16 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-08 | | | | | | | | | | | 16 | Crushed concrete | No compaction testing required | |
| 3 | BF-08-01 | 12/31/2013 | 684246.9 | 603039.8 | 2.0 | 127.2 | 3.2 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 4 | BF-08-02 | 12/31/2013 | 684240.5 | 603043.2 | 3.1 | 132.7 | 2.9 | 128.9 | 12.1 | 103 | 95 | 16 | Weldon WC Screenings | | Sor |
| 5 | BF-08-03 | 1/6/2014 | 684231.7 | 603038.8 | 3.9 | 127.0 | 8.4 | 128.9 | 12.1 | 99 | 95 | 16 | Weldon WC Screenings | | Sor |
| 6 | BF-08-04 | 1/9/2014 | 684242.3 | 603046.8 | 5.4 | 130.1 | 4.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 7 | BF-08-05 | 1/9/2014 | 684236.3 | 603066.0 | 7.1 | 129.8 | 6.2 | 128.9 | 12.1 | 101 | 95 | 16 | Weldon WC Screenings | | Sor |
| 1 | BF-09 | | 684208.5 | 602989.4 | -0.5 | | | | | | | 17 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-09 | | | | | | | | | | | 17 | Crushed concrete | No compaction testing required | |
| 3 | BF-09-01 | 1/28/2014 | 684209.7 | 602987.6 | 2.5 | 124.0 | 7.9 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 4 | BF-09-02 | 1/28/2014 | 684213.6 | 602980.4 | 3.4 | 123.4 | 6.1 | 128.9 | 12.1 | 96 | 95 | 17 | Weldon WC Screenings | | Sor |
| 5 | BF-09-03 | 1/28/2014 | 684204.2 | 602981.5 | 4.2 | 124.9 | 7.1 | 128.9 | 12.1 | 97 | 95 | 17 | Weldon WC Screenings | | Sor |
| 1 | BF-10 | | 684269.0 | 603014.0 | -0.5 | | | | | | | 18 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-10 | | | | | | | | | | | 18 | Crushed concrete | No compaction testing required | |
| 3 | BF-10-01 | 1/20/2014 | 684275.4 | 603018.2 | 2.2 | 133.1 | 7.7 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | | Sor |
| 4 | BF-10-02 | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 118.8 | 3.1 | 128.9 | 12.1 | 92 | 95 | 18 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-10-02R | 1/28/2014 | 684267.5 | 603026.1 | 3.2 | 133.3 | 6.1 | 128.9 | 12.1 | 103 | 95 | 18 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-10-03 | 1/28/2014 | 684271.8 | 603014.4 | 4.1 | 125.7 | 5.4 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 6 | BF-10-04 | 3/21/2014 | 684267.9 | 603017.5 | 5.2 | 126.4 | 6.8 | 128.9 | 12.1 | 98 | 95 | 18 | Weldon WC Screenings | | Sor |
| 1 | BF-11 | | 684208.5 | 602989.4 | -1.0 | | | | | | | 19 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-11 | | | | | | | | | | | 19 | Crushed concrete | No compaction testing required | |
| 3 | BF-11-01 | 1/28/2014 | 684216.6 | 602952.7 | 2.1 | 125.2 | 8.8 | 128.9 | 12.1 | 97 | 95 | 19 | Weldon WC Screenings | | Sor |
| 4 | BF-11-02 | 1/28/2014 | 684223.4 | 602953.8 | 3.4 | 129.8 | 4.2 | 128.9 | 12.1 | 101 | 95 | 19 | Weldon WC Screenings | | Sor |
| 5 | BF-11-03 | 1/28/2014 | 684211.6 | 602949.0 | 4.0 | 123.4 | 6.6 | 128.9 | 12.1 | 96 | 95 | 19 | Weldon WC Screenings | | Sor |
| 1 | BF-12 | | 684286.7 | 602988.6 | -1.7 | | | | | | | 20 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-12 | | | | | | | | | | | 20 | Crushed concrete | No compaction testing required | |
| 3 | BF-12-01 | 1/20/2014 | 684291.7 | 602995.2 | 1.8 | 133.3 | 8.3 | 128.9 | 12.1 | 103 | 95 | 20 | Weldon WC Screenings | | Sor |
| 4 | BF-12-02 | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 121.6 | 4.0 | 128.9 | 12.1 | 94 | 95 | 20 | Weldon WC Screenings | Scraped and re-rolled due to frost | Sor |
| 4 | BF-12-02R | 1/28/2014 | 684288.5 | 602989.8 | 2.9 | 128.5 | 5.8 | 128.9 | 12.1 | 100 | 95 | 20 | Weldon WC Screenings | second reading after addl compaction | Sor |
| 5 | BF-12-03 | 1/28/2014 | 684291.3 | 602995.4 | 3.7 | 136.9 | 7.5 | 128.9 | 12.1 | 106 | 95 | 20 | Weldon WC Screenings | | Sor |
| 1 | BF-13 | | 684235.7 | 602919.6 | -0.9 | | | | | | | 22 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-13 | | | | | | | | | | | 22 | Crushed concrete | No compaction testing required | |
| 3 | BF-13-01 | 1/28/2014 | 684235.6 | 602919.1 | 2.1 | 130.1 | 5.8 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | Sor |
| 3 | BF-13-01R | 3/12/2014 | 684238.5 | 602922.0 | 2.1 | 132.0 | 2.9 | 135.8 | 6.4 | 97 | 95 | 22 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-13-02 | 3/12/2014 | 684238.4 | 602918.2 | 3.4 | 133.0 | 1.4 | 135.8 | 6.4 | 98 | 95 | 22 | Tilcon MH DGA | | V5N |
| 5 | BF-13-03 | 3/19/2014 | 684235.1 | 602916.0 | 4.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 1 | BF-14 | | 684312.1 | 602956.0 | -0.9 | | | | | | | 23 | Crushed concrete | Bottom of excavation elevation | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-14 | | | | | | | | | | | 23 | Crushed concrete | No compaction testing required | |
| 3 | BF-14-01 | 1/20/2014 | 684312.7 | 602965.2 | 1.8 | 133.9 | 7.0 | 128.9 | 12.1 | 104 | 95 | 23 | Weldon WC Screenings | | Sor |
| 3 | BF-14-01R | 3/13/2013 | 684289.6 | 602935.7 | 1.8 | 132.0 | 1.7 | 135.8 | 6.4 | 97 | 95 | 23 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-14-02 | 3/14/2014 | 684301.9 | 602952.7 | 2.6 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 23 | Tilcon MH DGA | | V5N |
| 1 | BF-15 | | 684260.7 | 602896.7 | -0.9 | | | | | | | 24 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-15 | | | | | | | | | | | 24 | Crushed concrete | No compaction testing required | |
| 3 | BF-15-01 | 1/28/2014 | 684259.0 | 602897.1 | 2.1 | 123.6 | 9.0 | 128.9 | 12.1 | 96 | 95 | 24 | Weldon WC Screenings | | Sor |
| 3 | BF-15-01R | 3/12/2014 | 684264.5 | 602902.2 | 2.1 | 131.0 | 2.4 | 135.8 | 6.4 | 96 | 95 | 24 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-15-02 | 3/12/2014 | 684260.5 | 602900.2 | 2.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 24 | Tilcon MH DGA | | V5N |
| 1 | BF-16 | | 684326.7 | 602937.0 | -1.1 | | | | | | | 25 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-16 | | | | | | | | | | | 25 | Crushed concrete | No compaction testing required | |
| 3 | BF-16-01 | 1/20/2014 | 684331.9 | 602942.7 | 1.6 | 136.1 | 7.4 | 128.9 | 12.1 | 106 | 95 | 25 | Weldon WC Screenings | | Sor |
| 3 | BF-16-01R | 3/13/2014 | 6844330.0 | 602937.2 | 1.8 | 132.2 | 1.4 | 135.8 | 6.4 | 97 | 95 | 25 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-16-02 | 3/14/2014 | 684326.7 | 602930.0 | 2.5 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 25 | Tilcon MH DGA | | V5N |
| 1 | BF-17 | | 684283.7 | 602879.0 | 0.4 | | | | | | | 26 | Crushed concrete | Bottom of excavation elevation-Stratum O | |
| 2 | BF-17 | | | | | | | | | | | 26 | Crushed concrete | No compaction testing required | |
| 3 | BF-17-01 | 3/12/2014 | 684284.6 | 602882.1 | 2.1 | 130.0 | 2.9 | 135.8 | 6.4 | 96 | 95 | 26 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-17-02 | 3/14/2014 | 684273.7 | 602879.1 | 3.1 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 26 | Tilcon MH DGA | | V5N |
| 1 | BF-18 | | 684350.8 | 602909.6 | -1.5 | | | | | | | 27 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-18 | | | | | | | | | | | 27 | Crushed concrete | No compaction testing required | |
| 3 | BF-18-01 | 3/13/2014 | 684313.5 | 602885.6 | 1.5 | 132.4 | 1.4 | 135.8 | 6.4 | 97 | 95 | 27 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-18-02 | 3/14/2014 | 684344.0 | 602911.5 | 2.7 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 27 | Tilcon MH DGA | | V5N |
| 1 | BF-19 | | 684313.2 | 602860.4 | 0.3 | | | | | | | 28 | Crushed concrete | Bottom of excavation elevation - Stratum O | |
| 2 | BF-19 | | | | | | | | | | | 28 | Crushed concrete | No compaction testing required | |
| 3 | BF-19-01 | 3/14/2014 | 684322.1 | 602872.7 | 2.8 | 134.0 | 0.9 | 135.8 | 6.4 | 99 | 95 | 28 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-19-02 | 3/17/2014 | 684301.4 | 602851.5 | 3.6 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 28 | Tilcon MH DGA | | V5N |
| 1 | BF-20 | | 684370.9 | 602887.4 | -1.7 | | | | | | | 29 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-20 | | | | | | | | | | | 29 | Crushed concrete | No compaction testing required | |
| 3 | BF-20-01 | 3/17/2014 | 6843640.5 | 602862.1 | 2.0 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 29 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 1 | BF-21 | | 684330.4 | 602835.9 | 1.9 | | | | | | | 30 | Crushed concrete | Bottom of excavation elevation - Startum O | |
| 2 | BF-21-01 | 3/14/2014 | 684343.3 | 602842.2 | 2.4 | 132.0 | 1.6 | 135.8 | 6.4 | 97 | 95 | 30 | Tilcon MH DGA | Removed wet screenings to crushed concrete and placed Brid | V5N |
| 3 | BF-21-02 | 3/17/2014 | 684307.4 | 602827.3 | 3.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 30 | Tilcon MH DGA | Bridge Lift over Stratum O | V5N |
| 4 | BF-21-03 | 3/19/2014 | 684314.6 | 602830.9 | 3.9 | 122.5 | 5.1 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 5 | BF-21-04 | 3/20/2014 | 684314.4 | 602815.1 | 4.5 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 6 | BF-21-05 | 3/20/2014 | 684321.1 | 602814.1 | 5.2 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 7 | BF-21-06 | 3/20/2014 | 684308.3 | 602802.2 | 5.8 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 8 | BF-21-07 | 3/20/2014 | 684305.8 | 602806.3 | 6.7 | 123.3 | 4.0 | 128.9 | 12.1 | 96 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 9 | BF-21-08 | 3/20/2014 | 684314.4 | 602804.8 | 7.6 | 122.5 | 4.9 | 128.9 | 12.1 | 95 | 95 | 30 | Weldon WC Screenings | Truck Ramp to Kellogg Street | V5N |
| 10 | BF-21-09 | 3/20/2014 | 684310.5 | 602806.6 | 8.4 | 132.5 | 1.9 | 135.8 | 6.4 | 98 | 95 | 30 | Tilcon MH DGA | Truck Ramp to Kellogg Street | V5N |
| 1 | BF-22 | | 684391.2 | 602864.3 | -2.3 | | | | | | | 31 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-22 | | | | | | | | | | | 31 | Crushed concrete | No compaction testing required | |
| 3 | BF-22-01 | 3/17/2014 | 684387.3 | 602845.0 | 1.4 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 31 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 1 | BF-23 | | 684350.9 | 602814.5 | -1.6 | | | | | | | 32 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-23 | | | | | | | | | | | 32 | Crushed concrete | No compaction testing required | |
| 3 | BF-23-01 | 3/14/2014 | 684360.9 | 602818.8 | 2.4 | 132.0 | 2.0 | 135.8 | 6.4 | 97 | 95 | 32 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-23-02 | 3/17/2014 | 684339.8 | 602809.6 | 3.5 | 134.0 | 1.1 | 135.8 | 6.4 | 99 | 95 | 32 | Tilcon MH DGA | | V5N |
| 1 | BF-24 | | 684411.0 | 602842.4 | -1.8 | | | | | | | 33 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-24 | | | | | | | | | | | 33 | Crushed concrete | No compaction testing required | |
| 3 | BF-24-01 | 3/17/2014 | 684402.4 | 602827.4 | 1.1 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 33 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-25 | | 684369.5 | 602729.2 | -1.8 | | | | | | | 34 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-25 | | | | | | | | | | | 34 | Crushed concrete | No compaction testing required | |
| 3 | BF-25-01 | 3/14/2014 | 684379.5 | 602796.3 | 2.0 | 131.0 | 2.1 | 135.8 | 6.4 | 96 | 95 | 34 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-25-02 | 3/17/2014 | 684354.8 | 602790.5 | 3.4 | 133.0 | 1.5 | 135.8 | 6.4 | 98 | 95 | 34 | Tilcon MH DGA | | V5N |
| 1 | BF-26 | | 684433.4 | 602818.8 | -2.1 | | | | | | | 35 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-26 | | | | | | | | | | | 35 | Crushed concrete | No compaction testing required | |
| 3 | BF-26-01 | 3/18/2014 | 684433.9 | 602828.3 | 0.3 | 134.0 | 0.8 | 135.8 | 6.4 | 99 | 95 | 35 | Tilcon MH DGA | Removed wet screenings to crushed concrete and replaced wi | V5N |
| 4 | BF-26-02 | 3/18/2014 | 684431.7 | 602817.7 | 0.8 | 133.0 | 1.3 | 135.8 | 6.4 | 98 | 95 | 35 | Tilcon MH DGA | | V5N |
| 1 | BF-27 | | 684389.4 | 602765.0 | -1.8 | | | | | | | 36 | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-27 | | | | | | | | | | | 36 | Crushed concrete | No compaction testing required | |
| 3 | BF-27-01 | 3/14/2014 | 684398.2 | 602773.8 | 1.8 | 133.0 | 1.6 | 135.8 | 6.4 | 98 | 95 | 36 | Tilcon MH DGA | | V5N |
| 0 | BF-28 | | 684457.0 | 602790.8 | -2.8 | | | | | | | 38 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-28-01 | 3/12/2014 | 684461.2 | 602789.3 | -0.4 | 133.2 | 1.0 | 135.8 | 6.4 | 98 | 95 | 38 | Tilcon MH DGA | | V5N |
| 0 | BF-29 | | 684418.8 | 602735.2 | 2.1 | | | | | | | 39 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-29-01 | 3/26/2014 | 684404.6 | 602731.3 | 3.3 | 134.0 | 1.2 | 135.8 | 6.4 | 99 | 95 | 39 | Tilcon MH DGA | | V5N |
| 0 | BF-30 | | 684476.8 | 602765.1 | -3.1 | | | | | | | 40 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-30-01 | 3/12/2014 | 684478.9 | 602766.2 | -0.7 | 133.2 | 1.1 | 135.8 | 6.4 | 98 | 95 | 40 | Tilcon MH DGA | | V5N |
| 0 | BF-31 | | 684436.0 | 602712.8 | 0.1 | | | | | | | 41 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-32 | | 684498.7 | 602739.5 | -2.2 | | | | | | | 42 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-32-01 | 3/12/2014 | 684496.6 | 602743.0 | -0.9 | 131.0 | 2.3 | 135.8 | 6.4 | 96 | 95 | 42 | Tilcon MH DGA | | V5N |
| 0 | BF-33 | | 684453.0 | 602683.2 | 0.1 | | | | | | | 43 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-34 | | 684517.5 | 602716.8 | -2.5 | | | | | | | 44 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-34-01 | 3/12/2014 | 684515.6 | 602715.4 | -1.1 | 131.0 | 2.0 | 135.8 | 6.4 | 96 | 95 | 44 | Tilcon MH DGA | | V5N |
| 0 | BF-35 | | 684471.3 | 602661.2 | 0.2 | | | | | | | 45 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-36 | | 684538.2 | 602694.6 | -3.0 | | | | | | | 46 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-36-01 | 3/18/2014 | 684535.1 | 602700.7 | -1.9 | 134.5 | 0.5 | 135.8 | 6.4 | 99 | 95 | 46 | Tilcon MH DGA | | V5N |
| 0 | BF-37 | | 684490.0 | 602636.8 | 0.2 | | | | | | | 47 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-38 | | 684558.4 | 602671.7 | -3.0 | | | | | | | 48 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-38-01 | 3/21/2014 | 684551.4 | 602683.6 | -1.7 | 131.9 | 1.9 | 135.8 | 6.4 | 97 | 95 | 48 | Tilcon MH DGA | | V5N |
| 0 | BF-39 | | 684510.6 | 602614.8 | 0.4 | | | | | | | 49 | Stratum O | Bottom of excavation elevation | |
| 0 | BF-40 | | 684557.4 | 602644.9 | -3.6 | | | | | | | 50 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-40-01 | 3/26/2014 | 684572.2 | 602653.5 | -1.4 | 134.8 | 0.5 | 135.8 | 6.4 | 99 | 95 | 50 | Tilcon MH DGA | | V5N |
| 0 | BF-62 | | 684776.7 | 602362.5 | -2.5 | | | | | | | 73 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-62-1 | 10/15/2014 | 684764.3 | 602354.7 | 0.6 | 125.0 | 2.0 | 128.5 | 10.5 | 97 | 95 | 73 (No) | Weldon LH Screenings | Placed on Tilcon MH DGA | V5N |
| 0 | BF-64 | | 684785.0 | 602349.9 | -2.5 | | | | | | | 74 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-64-1 | 10/3/2014 | 684773.5 | 602338.3 | -1.2 | 128.5 | 4.7 | 128.5 | 10.5 | 100 | 95 | 74 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 3 | BF-64-2 | 10/15/2014 | 684772.1 | 602344.3 | 0.6 | 126.0 | 2.2 | 128.5 | 10.5 | 98 | 95 | 74 (No) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-65 | | 684701.4 | 602272.1 | -2.5 | | | | | | | 75 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-65-1 | 10/3/2014 | 684679.6 | 602257.6 | -1.6 | 127.0 | 3.1 | 128.5 | 10.5 | 99 | 95 | 75 (So) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 0 | BF-66 | | 684793.7 | 602335.5 | -2.5 | | | | | | | 75 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 1 | BF-66-1 | 10/3/2014 | 684788.5 | 602328.1 | -0.9 | 128.5 | 4.3 | 128.5 | 10.5 | 100 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 2 | BF-66-2 | 10/15/2014 | 684783.5 | 602334.9 | 0.6 | 125.0 | 2.9 | 128.5 | 10.5 | 97 | 95 | 75 (No) | Weldon LH Screenings | Screenings removed 10/8/14 and replaced with Tilcon MH DG | V5N |
| 0 | BF-67 | | 684709.6 | 602254.1 | -3.0 | | | | | | | 76 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-67-1 | 10/3/2014 | 684686.5 | 602239.8 | -1.3 | 124.0 | 2.5 | 128.5 | 10.5 | 96 | 95 | 76 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-67-2 | 10/27/2014 | 684684.5 | 602237.6 | 5.3 | 122.5 | 3.5 | 128.5 | 10.5 | 95 | 95 | 76 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-68 | | 684804.3 | 602317.4 | -3.5 | | | | | | | 77 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-68-1 | 10/3/2014 | 684796.5 | 602311.9 | -0.9 | 128.5 | 4.5 | 128.5 | 10.5 | 100 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-68-2 | 10/15/2014 | 684800.9 | 602313.3 | 0.5 | 125.0 | 2.2 | 128.5 | 10.5 | 97 | 95 | 77 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 0 | BF-69 | | 684720.3 | 602238.4 | -3.5 | | | | | | | 77 (So) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | BF-69-1 | 10/3/2014 | 684698.8 | 602228.5 | -1.1 | 124.6 | 2.9 | 128.5 | 10.5 | 97 | 95 | 77 (So) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 5 | BF-69-2 | 10/27/2014 | 684700.3 | 602225.0 | 5.5 | 122.0 | 3.2 | 128.5 | 10.5 | 95 | 95 | 77 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-70 | | 684813.9 | 602301.9 | -3.5 | | | | | | | 78 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 2 | BF-70-1 | 10/3/2014 | 685808.5 | 602301.5 | -0.9 | 128.5 | 4.0 | 128.5 | 10.5 | 100 | 95 | 78 (No) | Weldon LH Screenings | Placed on processed concrete bridge lift | V5N |
| 3 | BF-70-2 | 10/15/2014 | 685811.9 | 602297.1 | 0.7 | 127.0 | 4.0 | 128.5 | 10.5 | 99 | 95 | 78 (No) | Weldon LH Screenings | | V5N |
| 0 | BF-71 | | 684732.5 | 602221.3 | -3.3 | | | | | | | 79 (So) | Stratum D | | |
| 5 | BF-71-1 | 10/27/2014 | 684725.0 | 602212.2 | 5.6 | 125.0 | 2.5 | 128.5 | 10.5 | 97 | 95 | 79 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-72 | | 684824.9 | 602287.1 | -3.3 | | | | | | 95 | 79 (No) | Stratum D | Bottom of excavation elevation. Excavated to Meadow Mat | |
| 3 | BF-72-1 | 10/15/2014 | 684820.2 | 602286.1 | 0.4 | 125.5 | 1.9 | 128.5 | 10.5 | 98 | 95 | 79 (No) | Weldon LH Screenings | Placed on Weldon WC Screenings | V5N |
| 0 | BF-73 | | 684742.6 | 602208.4 | -5.0 | | | | | | 95 | 80 | Stratum D | Bottom of excavation elevation | |
| 6 | BF-73-1 | 10/27/2014 | 684743.1 | 602204.3 | 5.5 | 127.0 | 6.2 | 128.5 | 10.5 | 99 | 95 | 80 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-74 | | 684837.6 | 602270.4 | -4.8 | | | | | | | 81 (No) | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-74-1 | 9/18/2014 | 684834.9 | 602268.1 | -1.5 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 81 (No) | Weldon WC QP | Placed on Type A Material | V5N |
| 1 | BF-75 | | 684756.2 | 602190.9 | -5.0 | | | | | | | 81 (So) | Concrete/DGA | Bottom of excavation elevation | |
| 2 | BF-75-1 | 9/18/2014 | 684755.1 | 602200.0 | -2.4 | 128.0 | 3.6 | 131.9 | 9.5 | 97 | 95 | 81 (So) | Weldon WC QP | | V5N |
| 6 | BF-75-2 | 10/27/2014 | 684759.2 | 602193.9 | 5.4 | 128.5 | 6.5 | 128.5 | 10.5 | 100 | 95 | 81 (So) | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-76 | | 684829.0 | 602234.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 2 | BF-76-1 | 9/18/2014 | 684826.4 | 602234.0 | -2.4 | 126.0 | 4.5 | 131.9 | 9.5 | 96 | 95 | 82 | Weldon WC QP | Placed on processed concrete | V5N |
| 6 | BF-76-2 | 10/27/2014 | 684794.7 | 602203.1 | 5.5 | 128.0 | 4.6 | 128.5 | 10.5 | 100 | 95 | 82 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-77 | | 684848.6 | 602232.5 | -4.5 | | | | | | | 83 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-77-1 | 9/18/2014 | 684844.7 | 602224.8 | -1.2 | 126.0 | 5.0 | 131.9 | 9.5 | 96 | 95 | 83 | Weldon WC QP | Placed on Type A Material | V5N |
| 6 | BF-77-2 | 10/27/2014 | 684807.1 | 609195.1 | 5.4 | 128.5 | 5.4 | 128.5 | 10.5 | 100 | 95 | 83 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 1 | BF-78 | | 684864.2 | 602226.5 | -5.6 | | | | | | | 84 | Concrete/DGA | Bottom of excavation elevation | |
| 3 | BF-78-1 | 9/18/2014 | 684851.2 | 602210.9 | -0.7 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 84 | Weldon WC QP | Placed on Type A Material | V5N |
| 7 | BF-78-2 | 10/27/2014 | 684830.5 | 602190.3 | 5.4 | 128.5 | 7.1 | 128.5 | 10.5 | 100 | 95 | 84 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-79 | | 684877.8 | 602216.4 | -5.2 | | | | | | | 85 | | Bottom of excavation elevation | |
| 4 | BF-79-1 | 9/18/2014 | 684856.5 | 602180.7 | 1.0 | 128.0 | 2.9 | 131.9 | 9.5 | 97 | 95 | 85 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 0 | BF-80 | | 684890.3 | 602202.5 | -5.8 | | | | | | | 86 | | Bottom of excavation elevation | |
| 4 | BF-80-1 | 9/18/2014 | 684874.0 | 602174.3 | 1.3 | 125.0 | 3.9 | 131.9 | 9.5 | 95 | 95 | 86 | Weldon WC QP | Placed on Weldon WC Screenings | V5N |
| 7 | BF-80-2 | 10/27/2014 | 684873.1 | 602169.9 | 5.1 | 128.5 | 4.1 | 128.5 | 10.5 | 100 | 95 | 86 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-81 | | 684904.5 | 602186.6 | -6.1 | | | | | | | 88 | | Bottom of excavation elevation. Excavated to Meadow mat | |
| 4 | BF-81-1 | 9/18/2014 | 684886.9 | 602163.0 | 1.8 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 88 | Weldon WC QP | | V5N |
| 7 | BF-81-2 | 10/27/2014 | 684883.9 | 602156.7 | 5.0 | 127.0 | 4.7 | 128.5 | 10.5 | 99 | 95 | 88 | Weldon LH Screenings | Placed on Type A Material | V5N |
| 0 | BF-82 | | 684923.8 | 602171.9 | -4.8 | | | | | | | 89 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 5 | BF-82-1 | 9/18/2014 | 684898.0 | 602149.9 | 3.1 | 128.0 | 3.4 | 131.9 | 9.5 | 97 | 95 | 89 | Weldon WC QP | | V5N |
| 6 | BF-82-2 | 10/27/2014 | 684915.2 | 602163.5 | 5.3 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 89 | Weldon LH Screenings | | V5N |
| 0 | BF-83 | | 684941.9 | 602148.5 | -4.8 | | | | | | | 91 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-83-1 | 8/26/2014 | 684958.8 | 602165.2 | -3.0 | 129.7 | 7.0 | 131.9 | 9.5 | 98 | 95 | 91 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 6 | BF-83-2 | 9/18/2014 | 684920.6 | 602131.1 | 4.1 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 91 | Weldon WC QP | | V5N |
| 7 | BF-83-3 | 10/27/2014 | 684933.2 | 602141.4 | 5.6 | 128.5 | 3.6 | 128.5 | 10.5 | 100 | 95 | 91 | Weldon LH Screenings | | V5N |
| 0 | BF-84 | | 684959.7 | 602128.6 | -4.2 | | | | | | | 93 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-84-1 | 8/15/2014 | 684969.1 | 602137.6 | -3.2 | 129.3 | 3.2 | 131.9 | 9.5 | 98 | 95 | 93 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-84-2 | 9/18/2014 | 684937.9 | 602110.2 | 4.7 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 93 | Weldon WC QP | | V5N |
| 6 | BF-84-3 | 10/27/2014 | 684953.2 | 602121.7 | 5.6 | 128.5 | 3.2 | 128.5 | 10.5 | 100 | 95 | 93 | Weldon LH Screenings | | V5N |
| 0 | BF-85 | | 684976.0 | 602107.0 | -4.8 | | | | | | | 95 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-85-1 | 8/15/2014 | 684987.2 | 602117.0 | -3.4 | 126.0 | 3.6 | 131.9 | 9.5 | 96 | 95 | 95 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-85-2 | 9/18/2014 | 684960.1 | 602086.7 | 4.8 | 125.0 | 4.9 | 131.9 | 9.5 | 95 | 95 | 95 | Weldon WC QP | | V5N |
| 6 | BF-85-3 | 10/27/2014 | 684973.5 | 602102.2 | 5.7 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 95 | Weldon LH Screenings | | V5N |
| 0 | BF-86 | | 684993.0 | 602080.9 | -4.8 | | | | | | | 97 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BF-86-1 | 8/15/2014 | 684999.9 | 602082.3 | -3.4 | 126.0 | 3.7 | 131.9 | 9.5 | 96 | 95 | 97 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 5 | BF-86-2 | 10/27/2014 | 684990.4 | 602076.5 | 5.5 | 128.5 | 5.7 | 128.5 | 10.5 | 100 | 95 | 97 | Weldon LH Screenings | | V5N |
| 0 | BF-87 | | 685010.3 | 602052.3 | -5.0 | | | | | | | 99 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-87-1 | 8/15/2014 | 685010.8 | 602056.6 | -3.7 | 125.0 | 4.2 | 131.9 | 9.5 | 95 | 95 | 99 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-88 | | 685019.7 | 602037.1 | -5.1 | | | | | | | 100 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-88-1 | 8/8/2014 | 685025.4 | 602022.1 | -3.9 | 126.6 | 3.9 | 131.9 | 9.5 | 96 | 95 | 100 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-89 | | 685025.3 | 602021.0 | -4.8 | | | | | | | 101 | Stratum D | Bottom of excavation elevation. Excavated to Meadow mat | |
| 1 | BF-89-1 | 8/26/2014 | 685029.3 | 602037.1 | -3.3 | 131.9 | 7.3 | 131.9 | 9.5 | 100 | 95 | 101 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-90 | | 685035.2 | 602003.7 | -5.1 | | | | | | | 103 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-90-1 | 8/6/2014 | 685049.1 | 602012.4 | -3.5 | 128.0 | 3.1 | 131.9 | 9.5 | 97 | 95 | 103 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-91 | | 685048.2 | 601986.6 | -5.2 | | | | | | | 104 | Stratum D | Bottom of excavation elevation; Excavated to Meadow mat | |
| 1 | BF-91-01 | 7/30/2014 | 685067.2 | 602016.2 | -4.2 | 136.5 | 4.3 | 142.6 | 7.8 | 96 | 95 | 104 | Weldon WC QP | | V5N |
| 2 | BF-91-02 | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.4 | 6.5 | 142.6 | 7.8 | 85 | 95 | 104 | Weldon WC QP | New blast area. QP visually changed. | V5N |
| 2 | BF-91-02R | 8/1/2014 | 685062.8 | 602085.0 | -3.2 | 121.0 | 7.4 | 142.6 | 9.5 | 85 | 95 | 104 | Weldon WC QP | Rerolled area still fails. Collect sample for Proctor | V5N |
| 2 | BF-91-02RR | 8/4/2014 | 685062.8 | 602085.0 | -2.9 | 125.3 | 7.4 | 131.9 | 9.5 | 95 | 95 | 104 | Weldon WC QP | Used new dry density of 131.9 PCF per new Proctor results | V5N |
| 0 | BF-93 | | 685084.9 | 601963.3 | -1.2 | | | | | | | | Stratum O | Bottom of excavation elevation | |
| 1 | BF-93-01 | 7/18/2014 | 685112.8 | 601983.8 | -0.4 | 136.5 | 3.5 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 2 | BF-93-02 | 7/30/2014 | 685091.5 | 601975.9 | 1.1 | 136.5 | 3.9 | 142.6 | 7.8 | 96 | 95 | 107 (No) | Weldon WC QP | | V5N |
| 1 | BF-94 | | 685105.9 | 601939.3 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-94-01 | 7/18/2014 | 685104.8 | 601941.5 | 1.7 | 136.0 | 3.8 | 142.6 | 7.8 | 95 | 95 | 109 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-95 | | 685125.6 | 601915.0 | -1.2 | | | | | | | 111 (No) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-95-01 | 7/16/2014 | 685121.8 | 601910.5 | 1.7 | 135.0 | 3.6 | 142.6 | 7.8 | 95 | 95 | 111 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-96 | | 685144.3 | 601891.9 | -1.2 | | | | | | | | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-96-01 | 7/10/2014 | 685150.5 | 601896.1 | 1.9 | 137.0 | 4.8 | 142.6 | 7.8 | 96 | 95 | 113 (No) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-97 | | 685196.4 | 601880.1 | 2.1 | | | | | | | | Stratum O | Bottom of excavati0n elevation | |
| 1 | BF-97-01 | 7/7/2014 | 685187.0 | 601867.3 | 2.7 | 135.5 | 4.6 | 142.6 | 7.8 | 95 | 95 | 116 (No) | Weldon WC QP | | V5N |
| 0 | BF-101 | | 685222.6 | 601822.8 | 0.4 | | | | | | | 120 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-101-01 | 6/27/2014 | 685213.8 | 601814.2 | 1.0 | 136.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 120 (No) | Weldon WC QP | | V5N |
| 0 | BF-102 | | 685148.9 | 601780.9 | -2.5 | | | | | | | 119 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-102-01 | 6/27/2014 | 685148.8 | 601788.7 | -0.8 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 119 | Weldon WC QP | | V5N |
| 1 | BF-103 | | 685084.0 | 601708.8 | -7.5 | | | | | | | 120 (So) | | | |
| 2 | BF-103-01 | 7/1/2014 | 685102.8 | 601721.9 | -4.9 | 137.5 | 2.5 | 142.6 | 7.8 | 96 | 95 | 120 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-105 | | 685102.9 | 601692.4 | -7.5 | | | | | | | 122 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-105-01 | 6/27/2014 | 685126.9 | 601702.6 | -5.7 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-104 | | 685218.6 | 601799.3 | -2.5 | | | | | | | 121 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-104-01 | 6/27/2014 | 685205.5 | 601790.7 | 0.9 | 135.5 | 3.4 | 142.6 | 7.8 | 95 | 95 | 121 (No) | Weldon WC QP | | V5N |
| 0 | BF-106 | | 685225.5 | 601777.9 | -1.2 | | | | | | | 122 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF 106-01 | 6/18/2014 | 685230.1 | 601784.7 | 0.5 | 140.0 | 1.7 | 142.6 | 7.8 | 98 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 2 | BF 106-02 | 6/27/2014 | 685221.4 | 601777.8 | 1.0 | 135.4 | 3.4 | 142.6 | 7.8 | 95 | 95 | 122 (No) | Weldon WC QP | | V5N |
| 1 | BF-107 | | 685115.2 | 601682.1 | -7.5 | | | | | | | 123 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF 107-01 | 6/24/2014 | 685134.6 | 601695.5 | -5.9 | 136.9 | 2.5 | 142.6 | 7.8 | 96 | 95 | 123 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-108 | | 685235.5 | 601760.6 | -1.2 | | | | | | | 124 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-108-01 | 6/18/2014 | 685235.2 | 601757.6 | 0.8 | 138.0 | 2.6 | 142.6 | 7.8 | 97 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 2 | BF-108-02 | 6/27/2014 | 685253.4 | 601761.5 | 1.4 | 135.0 | 3.4 | 142.6 | 7.8 | 95 | 95 | 124 (No) | Weldon WC QP | | V5N |
| 1 | BF-109 | | 685135.2 | 601666.9 | -7.5 | | | | | | | 124 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-109-01 | 6/18/2014 | 685144.9 | 601672.5 | -5.8 | 136.0 | 5.1 | 142.6 | 7.8 | 95 | 95 | 124 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 1 | BF-111 | | 685154.6 | 601650.7 | -7.5 | | | | | | | 126 (So) | Crushed concrete | Bottom of excavation elevation | |
| 2 | BF-111-01 | 6/18/2014 | 685157.7 | 601655.0 | -5.4 | 140.0 | 1.5 | 142.6 | 7.8 | 98 | 95 | 126 (So) | Weldon WC QP | Placed on concrete/QP bridge lift | V5N |
| 0 | BF-124 | | 685346.3 | 601612.6 | -1.2 | | | | | | | 136 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-124-01 | 5/9/2014 | 685359.1 | 601618.5 | 0.3 | 130.8 | 1.3 | 135.8 | 6.4 | 96 | 95 | 136 | Tilcon MH DGA | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**Testing Frequency - 1 Test per 2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | BF-126 | | 685363.5 | 601589.4 | -1.2 | | | | | | | 138 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-126-01 | 5/9/2014 | 685355.3 | 601576.3 | 0.2 | 128.0 | 3.3 | 128.9 | 12.1 | 99 | 95 | 138 | Weldon WC Screenings | | V5N |
| 0 | BF-128 | | 685382.2 | 601566.3 | -2.5 | | | | | | | 140 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-128-01 | 4/29/2014 | 685369.8 | 601556.5 | -1.8 | 130.0 | 1.2 | 135.8 | 6.4 | 96 | 95 | 140 | Tilcon MH DGA | | V5N |
| 2 | BF-128-02 | 4/29/2014 | 685381.4 | 601569.9 | -0.8 | 132.2 | 1.5 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 3 | BF-128-03 | 4/29/2014 | 685382.7 | 601573.8 | 0.3 | 132.0 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 4 | BF-128-04 | 4/29/2014 | 685386.7 | 601571.4 | 1.5 | 132.3 | 1.3 | 135.8 | 6.4 | 97 | 95 | 140 | Tilcon MH DGA | | V5N |
| 5 | BF-128-05 | 4/29/2014 | 685389.9 | 601573.7 | 2.7 | 133.9 | 1.4 | 135.8 | 6.4 | 99 | 95 | 140 | Tilcon MH DGA | | V5N |
| 0 | BF-129 | | 685308.1 | 601468.7 | -7.5 | | | | | | | 142 (So) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-129-01 | 5/9/2014 | 685315.6 | 601465.0 | -6.4 | 135.5 | 1.3 | 135.8 | 6.4 | 100 | 95 | 142 (So) | Tilcon MH DGA | | V5N |
| 0 | BF-130 | | 685401.7 | 601541.7 | 1.9 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | BF-130-01 | 4/28/2014 | 685410.7 | 601558.5 | 2.7 | 132.0 | 2.2 | 135.8 | 6.4 | 97 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 2 | BF-130-02 | 4/28/2014 | 685414.5 | 601553.3 | 3.6 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 3 | BF-130-03 | 4/28/2014 | 685414.9 | 601555.5 | 4.8 | 136.0 | 1.6 | 135.8 | 6.4 | 100 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 4 | BF-130-04 | 4/28/2014 | 685420.1 | 601558.2 | 5.5 | 135.0 | 1.9 | 135.8 | 6.4 | 99 | 95 | 142 (No) | Tilcon MH DGA | | V5N |
| 0 | BF-131 | | 685426.9 | 601523.7 | 3.2 | | | | | | | 144 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-131-01 | 4/25/2014 | 685440.9 | 601531.9 | 5.9 | 120.0 | 1.4 | 135.8 | 6.4 | 88 | 95 | 144 | Tilcon MH DGA | recompact lift | V5N |
| 1 | BF-131-01R | 4/28/2014 | 685440.9 | 601531.9 | 5.9 | 139.9 | 1.4 | 135.8 | 6.4 | 103 | 95 | 144 | Tilcon MH DGA | second reading after addl compaction | V5N |
| 0 | BF-132 | | 685452.9 | 601506.1 | 5.6 | | | | | | | 146 | Stratum O | Bottom of excavation elevation | |
| 1 | BF-132-01 | 4/25/2014 | 685438.7 | 601505.6 | 6.1 | 135.0 | 1.0 | 135.8 | 6.4 | 99 | 95 | 144 | Tilcon MH DGA | | V5N |

***Notes:*** Maximum Dry Density (gravel corrected) for Weldon WC QP based on Sor Testing Laboratories Report No. 13-2027 dated 12/9/13. Sample collected from on site soils.
Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Maximum Dry Density for Weldon LH Screenings based on Vertical V Laboratory Report No. 12643 dated 9/29/14.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID BF-01-01 where:

BF = Backfill (At frequency of 1 test/2500 SF)
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again
= Area subject to re-compaction

* *Initial field testing indicated compaction of greater then 95% (see attached Sor Testing Lab (STL) memo). Laboratory results for initially provided Weldon WC QP sample indicated a maximum dry density of 136.7 pcf. Using this density the compaction results are greater than the 95%. Laboratory tests on later deliveries indicated density results of 142.6 pcf. This range is typical of what can be expected for this type of source. The Engineer of Record (EOR) directed that the results be reported using the higher more conservative value and that the STL field test report verifying the higher passing results be attached to the final documentation. It is further noted that the Design Documents do not designate this area for compaction as Structural Fill per Specification Section 02315 Section 3.12, Structural Fill 95%; Non Structural Fill 90% Standard Proctor. The 95% value noted in this Table was implemented to provide for uniform compaction in areas slated for future development. It is the EOR's opinion that these two samples meet the 100% Design and project requirements.*

# SOR TESTING LABORATORIES, INC.

*Geotechnical Engineering - Materials Testing - Forensic Studies*
98 Sand Park Rd., Cedar Grove, NJ 07009
(973) 239-6001 Fax (973) 239-8380

Kamil Sor, Ph.D.
Orhun Sor, P.E.
Yilmaz Arhan, Ph.D.
Kenneth Rowbotham, P.E.
Atilla Sencar, P.E.



This report is the confidential property of the Client, and information
Contained may not be published or reproduced without our written permission.


| | | | |
|---|---|---|---|
| Client: | Entact Environmental Services | | |
| Project: | Honeywell SA-6, Jersey City NJ | | |
| Subject: | In-Place Density Tests | | |
| Job No.: | 13-208 | Report No.: 13-1994 | Date: 12/3/13 |

At the request of the client, on November 22, 2013 a field technician from Sor Testing Laboratories, Inc. reported to the project site for the purpose of performing in-place density tests over previously compacted lifts of materials at locations indicated by the client's representative.

Using a nuclear density gauge, our technician performed two density tests at locations 01BF-2 and 02BF-2 per the client's instructions. The proctor value of 136.7 pcf at our optimum moisture content of 8.1% was also provided by the client.

Test results were 97.5% and 95.7% compaction.

Technician: J.C. Jean-Toussaint

Very truly yours,

SOR TESTING LABORATORIES, INC.

Atilla Sencar, P.E.
Senior Engineer

AS/jh
Attachment

cc: (1) Client, Attn: Craig Cymbor (Email: ccymbor@entact.com)
(1) Client, Attn: Caroline Panico (Email: cpanico@entact.com)
(1) Client, Attn: Andrew Rizzuto (Email: arizzuto@entact.com)

# SOR TESTING LABORATORIES, INC.

*Geotechnical Engineering · Materials Testing · Forensic Studies*

98 Sand Park Rd., Cedar Grove, N.J. 07009
(973) 239-6001 • Fax (973) 239-8380

Kamil Sor, Ph.D.
Orhun Sor, P.E.
Peter G. Mickus, P.E.


## NUCLEAR DENSITY TEST DATA

Client: Entact Date: 11-22-2013
Project: HoneyWell SA-6 Job No.: 13-208 Report No. 13-1994
Daily Standard Count: _____ Density: 1975 Moisture 627

| TEST NUMBER | 1 | X | 2 | X | | | |
|---|---|---|---|---|---|---|---|
| Station | | | | | | | |
| Offset | | | | | | | |
| Elevation | 01BF-2 | | 02BF-2 | | | | |
| Mode & Depth (inches) | NORMAL/+10" | | NORMAL +10" | | | | |
| Density Count | N/A | | N/A | | | | |
| Wet Density (P.C.F.) | 137.8 | | 134.6 | | | | |
| Moisture Count | N/A | | N/A | | | | |
| Dry Density (P.C.F.) | 133.3 | | 130.8 | | | | |
| Moisture (P.C.F.) | 4.5 | | 3.6 | | | | |
| Moisture (%) | 3.4 | | 2.8 | | | | |
| Proctor Density (P.C.F.) | 136.7 | | 136.7 | | | | |
| Optimum Moisture (%) | | | | | | | |
| % Compaction | 97.5 | | 95.7 | | | | |
| Moisture Correction | | | | | | | |

REMARKS:

Jean C. Jean Mouaint
INSPECTOR

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | RF-03 | | 684270.2 | 603012.0 | | | | | | | | 18 | | | |
| 7 | RF-03-01 | 3/21/2014 | 684267.9 | 603017.5 | 6.1 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 18 | Weldon WC Screenings | | V5N |
| 8 | RF-03-02 | 4/8/2014 | 684272.9 | 605018.7 | 7.6 | 122.4 | 8.1 | 128.9 | 12.1 | 95 | 95 | 18 | Weldon WC Screenings | | V5N |
| | RF-04 | | 684235.2 | 602919.8 | | | | | | | | 22 | | | |
| 6 | RF-04-01 | 3/21/2014 | 684227.0 | 602916.6 | 5.5 | 124.0 | 3.6 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 7 | RF-04-02 | 3/26/2014 | 684266.5 | 602908.5 | 6.2 | 123.6 | 3.7 | 128.9 | 12.1 | 96 | 95 | 22 | Weldon WC Screenings | | V5N |
| 8 | RF-04-03 | 4/1/2014 | 684384.8 | 602904.9 | 7.1 | 125.8 | 3.0 | 128.9 | 12.1 | 98 | 95 | 22 | Weldon WC Screenings | | V5N |
| 9 | RF-04-04 | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 120.0 | 3.6 | 128.9 | 12.1 | 93 | 95 | 22 | Weldon WC Screenings | Recompact lift | V5N |
| 9 | RF-04-04R | 4/3/2014 | 684220.8 | 602926.9 | 8.2 | 125.0 | 4.1 | 128.9 | 12.1 | 97 | 95 | 22 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 10 | RF-04-05 | 4/17/2014 | 684241.5 | 602924.2 | 8.8 | 130.0 | 3.0 | 128.9 | 12.1 | 101 | 95 | 22 | Weldon WC Screenings | | V5N |
| | RF-05 | | 684328.5 | 602935.0 | | | | | | | | 25 | | | |
| 5 | RF-05-01 | 3/24/2014 | 684347.1 | 602947.5 | 3.3 | 122.5 | 4.5 | 128.9 | 12.1 | 95 | 95 | 25 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 6 | RF-05-02 | 3/26/2014 | 684348.1 | 602942.0 | 4.1 | 123.5 | 3.7 | 128.9 | 12.1 | 96 | 95 | 25 | Weldon WC Screenings | | V5N |
| 7 | RF-05-03 | 4/1/2014 | 684351.4 | 602937.8 | 5.4 | 125.0 | 2.6 | 128.9 | 12.1 | 97 | 95 | 25 | Weldon WC Screenings | | V5N |
| 8 | RF-05-04 | 4/3/2014 | 684339.0 | 602933.4 | 6.4 | 128.9 | 4.7 | 128.9 | 12.1 | 100 | 95 | 25 | Weldon WC Screenings | | V5N |
| 9 | RF-05-05 | 4/8/2014 | 684327.1 | 602942.3 | 7.6 | 126.4 | 8.3 | 128.9 | 12.1 | 98 | 95 | 25 | Weldon WC Screenings | | V5N |
| 10 | RF-05-06 | 4/17/2014 | 684348.8 | 602945.1 | 8.2 | 135.0 | 6.4 | 128.9 | 12.1 | 105 | 95 | 25 | Weldon WC Screenings | | V5N |
| | RF-06 | | 684335.0 | 602869.1 | | | | | | | | 29 | | | |
| 2 | RF-06-01 | 4/1/2014 | 684383.7 | 602908.8 | 3.0 | 126.0 | 2.7 | 128.9 | 12.1 | 98 | 95 | 29 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 3 | RF-06-02 | 4/1/2014 | 684384.8 | 602904.9 | 4.1 | 125.0 | 2.8 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 4 | RF-06-03 | 4/3/2014 | 684358.9 | 602890.5 | 5.9 | 127.6 | 4.0 | 128.9 | 12.1 | 99 | 95 | 29 | Weldon WC Screenings | | V5N |
| 5 | RF-06-04 | 4/8/2014 | 684340.1 | 602867.1 | 6.9 | 123.0 | 4.6 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | | V5N |
| 6 | RF-06-05 | 4/14/2014 | 684340.1 | 602867.1 | 7.5 | 124.8 | 3.0 | 128.9 | 12.1 | 97 | 95 | 29 | Weldon WC Screenings | | V5N |
| 7 | RF-06-06 | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 118.5 | 3.0 | 128.9 | 12.1 | 92 | 95 | 29 | Weldon WC Screenings | Recompact lift | V5N |
| 7 | RF-06-06R | 4/17/2014 | 684337.1 | 602897.4 | 8.5 | 122.0 | 3.2 | 128.9 | 12.1 | 95 | 95 | 29 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| | RF-07 | | 684392.9 | 602838.1 | | | | | | | | 32 | | | |
| 4 | RF-07-01 | 4/3/2014 | 684425.2 | 602890.4 | 3.0 | 125.3 | 5.1 | 128.9 | 12.1 | 97 | 95 | 32 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-07-02 | 4/3/2014 | 684418.6 | 602854.9 | 4.1 | 126.3 | 5.5 | 128.9 | 12.1 | 98 | 95 | 32 | Weldon WC Screenings | | V5N |
| 6 | RF-07-03 | 4/8/2014 | 684410.5 | 602847.3 | 5.6 | 122.7 | 2.5 | 128.9 | 12.1 | 95 | 95 | 32 | Weldon WC Screenings | | V5N |
| 7 | RF-07-04 | 4/14/2014 | 684410.5 | 602847.3 | 6.3 | 123.1 | 2.7 | 128.9 | 12.1 | 96 | 95 | 32 | Weldon WC Screenings | | V5N |
| 8 | RF-07-05 | 4/17/2014 | 684394.3 | 602842.1 | 7.1 | 135.0 | 6.1 | 128.9 | 12.1 | 105 | 95 | 32 | Weldon WC Screenings | | V5N |
| 9 | RF-07-06 | 4/21/2014 | 684394.8 | 602836.9 | 8.2 | 128.9 | 2.2 | 128.9 | 12.1 | 100 | 95 | 32 | Weldon WC Screenings | | V5N |
| | RF-08 | | 684406.9 | 602771.1 | | | | | | | | 36 | | | |
| 4 | RF-08-01 | 4/3/2014 | 684421.7 | 602797.1 | 2.9 | 129.0 | 6.0 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 5 | RF-08-02 | 4/8/2014 | 684429.7 | 602790.1 | 4.0 | 124.9 | 3.0 | 128.9 | 12.1 | 97 | 95 | 36 | Weldon WC Screenings | | V5N |
| 6 | RF-08-03 | 4/15/2014 | 684439.0 | 602813.0 | 5.0 | 124.2 | 4.7 | 128.9 | 12.1 | 96 | 95 | 36 | Weldon WC Screenings | | V5N |
| 7 | RF-08-04 | 4/17/2014 | 684400.4 | 602773.4 | 6.1 | 137.0 | 5.6 | 128.9 | 12.1 | 106 | 95 | 36 | Weldon WC Screenings | | V5N |
| 8 | RF-08-05 | 4/21/2014 | 684429.8 | 602794.0 | 6.8 | 128.9 | 3.5 | 128.9 | 12.1 | 100 | 95 | 36 | Weldon WC Screenings | | V5N |
| 9 | RF-08-06 | 4/21/2014 | 684443.6 | 602550.4 | 8.0 | 122.5 | 6.9 | 128.9 | 12.1 | 95 | 95 | 36 | Weldon WC Screenings | | V5N |
| | RF-09 | | 684479.9 | 602754.0 | | | | | | | | 40 | | | |
| 3 | RF-09-01 | 4/7/2014 | 684489.3 | 602750.3 | 0.8 | 128.7 | 6.8 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | Placed on Tilcon MH DGA | V5N |
| 4 | RF-09-02 | 4/11/2014 | 684498.7 | 602757.9 | 2.1 | 122.4 | 3.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 5 | RF-09-03 | 4/11/2014 | 684503.3 | 602770.3 | 3.2 | 129.3 | 8.5 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 6 | RF-09-04 | 4/14/2014 | 684503.3 | 602770.3 | 4.1 | 128.9 | 5.7 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 7 | RF-09-05 | 4/21/2014 | 684479.1 | 602753.1 | 5.4 | 128.9 | 5.3 | 128.9 | 12.1 | 100 | 95 | 40 | Weldon WC Screenings | | V5N |
| 8 | RF-09-06 | 4/21/2014 | 684446.9 | 602799.1 | 6.4 | 123.0 | 2.0 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 9 | RF-09-07 | 5/15/2014 | 684479.0 | 602751.5 | 6.9 | 124.5 | 4.4 | 128.9 | 12.1 | 97 | 95 | 40 | Weldon WC Screenings | | V5N |
| 10 | RF-09-08 | 5/19/2014 | 684494.7 | 602760.2 | 8.1 | 122.5 | 5.9 | 128.9 | 12.1 | 95 | 95 | 40 | Weldon WC Screenings | | V5N |
| 1 | RF-10 | | 684474.1 | 602682.1 | 0.2 | | | | | | | 44 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-10 | | 684474.1 | 602682.1 | | | | | | | | 44 | Type A Material | No compaction testing required | |
| 3 | RF-10-01 | 4/25/2014 | 684476.1 | 602679.3 | 2.5 | 138.0 | 1.4 | 128.9 | 12.1 | 107 | 95 | 44 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-10-02 | 5/8/2014 | 684445.5 | 602680.1 | 5.8 | 132.0 | 6.6 | 128.9 | 12.1 | 102 | 95 | 44 | Weldon WC Screenings | | V5N |
| 5 | RF-10-03 | 5/15/2014 | 684463.8 | 602677.8 | 7.1 | 124.1 | 4.2 | 128.9 | 12.1 | 96 | 95 | 44 | Weldon WC Screenings | | V5N |
| 6 | RF-10-04 | 5/19/2014 | 684466.2 | 602672.2 | 8.2 | 122.5 | 6.8 | 128.9 | 12.1 | 95 | 95 | 44 | Weldon WC Screenings | | V5N |
| 2 | RF-11 | | 684545.0 | 602673.2 | | | | | | | | 48 | Type A Material | Placed on Tilcon MH DGA | |
| 3 | RF-11-01 | 4/11/2014 | 684533.0 | 602676.0 | 1.0 | 126.0 | 3.8 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Placed on Type A Material; Against HB wall | V5N |
| 4 | RF-11-02 | 4/11/2014 | 684575.1 | 602679.9 | 2.1 | 125.6 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 5 | RF-11-03 | 4/14/2014 | 684575.1 | 602679.9 | 2.8 | 126.8 | 2.2 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 6 | RF-11-04 | 4/17/2014 | 684579.8 | 602684.6 | 3.8 | 122.5 | 3.0 | 128.9 | 12.1 | 95 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 7 | RF-11-05 | 4/17/2014 | 684585.7 | 602686.5 | 4.5 | 126.8 | 4.0 | 128.9 | 12.1 | 98 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 8 | RF-11-06 | 5/15/2014 | 684569.9 | 602672.5 | 7.3 | 124.5 | 4.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 9 | RF-11-07 | 5/19/2014 | 685562.2 | 602686.4 | 8.3 | 124.5 | 3.5 | 128.9 | 12.1 | 97 | 95 | 48 | Weldon WC Screenings | Against HB wall | V5N |
| 1 | RF-12 | | 684540.0 | 602601.3 | 0.3 | | | | | | | 51 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-12 | | 684540.0 | 602601.3 | | | | | | | | 51 | Type A Material | No compaction testing required | |
| 3 | RF-12-01 | 4/25/2014 | 684557.9 | 602605.6 | 2.3 | 130.2 | 2.2 | 128.9 | 12.1 | 101 | 95 | 51 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-12-02 | 5/6/2014 | 684516.3 | 602580.6 | 6.0 | 128.6 | 5.6 | 128.9 | 12.1 | 100 | 95 | 51 | Weldon WC Screenings | | V5N |
| 5 | RF-12-03 | 5/15/2014 | 684526.7 | 602594.1 | 7.3 | 124.8 | 3.9 | 128.9 | 12.1 | 97 | 95 | 51 | Weldon WC Screenings | | V5N |
| 6 | RF-12-04 | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 121.3 | 7.1 | 128.9 | 12.1 | 94 | 95 | 51 | Weldon WC Screenings | Recompact lift | V5N |
| 6 | RF-12-04R | 5/20/2014 | 684522.6 | 602585.3 | 8.1 | 122.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 51 | Weldon WC Screenings | Second reading after re-rolling | V5N |
| 1 | RF-13 | | 684610.2 | 602590.4 | -2.3 | | | | | | | 54 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-13 | | 684610.2 | 602590.4 | | | | | | | | 54 | Type A Material | No compaction testing required | |
| 3 | RF-13-01 | 4/11/2014 | 684619.5 | 602515.3 | 1.6 | 126.5 | 7.8 | 128.9 | 12.1 | 98 | 95 | 54 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-13-02 | 4/14/2014 | 684619.5 | 602515.3 | 2.7 | 124.5 | 2.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT NO. | TEST I.D. | DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | ENTACT CELL # | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | RF-13-03 | 4/17/2014 | 684641.5 | 602614.6 | 3.6 | 123.0 | 4.1 | 128.9 | 12.1 | 95 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 6 | RF-13-04 | 4/17/2014 | 684646.7 | 602619.5 | 4.4 | 132.9 | 5.5 | 128.9 | 12.1 | 103 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 7 | RF-13-05 | 5/15/2014 | 684640.0 | 602620.1 | 5.4 | 125.0 | 3.7 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | Against HB | V5N |
| 8 | RF-13-06 | 5/15/2014 | 684613.8 | 602605.5 | 6.9 | 125.0 | 4.5 | 128.9 | 12.1 | 97 | 95 | 54 | Weldon WC Screenings | | V5N |
| 9 | RF-13-07 | 5/20/2014 | 684614.3 | 602606.0 | 7.8 | 121.3 | 8.0 | 128.9 | 12.1 | 94 | 95 | 54 | Weldon WC Screenings | Top lift. Will retest prior to final restoration | V5N |
| 0 | RF-14 | | 684653.1 | 602535.0 | -2.6 | | | | | | | 59 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-14-1 | 10/30/2014 | 684656.5 | 602532.8 | -1.3 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 1 | RF-14-2 | 11/5/2014 | 684662.9 | 602542.6 | 0.0 | 134.0 | 0.6 | 135.8 | 6.4 | 99 | 95 | 59 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-15 | | 684684.3 | 602484.0 | -2.2 | | | | | | | 63 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-15-1 | 10/27/2014 | 684656.4 | 602466.0 | 0.6 | 135.8 | 2.0 | 135.8 | 6.4 | 100 | 95 | 63 | Tilcon MH DGA | Bridge lift | V5N |
| 0 | RF-16 | | 684687.2 | 602408.0 | -2.2 | | | | | | | 67 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-16-1 | 10/27/2014 | 684767.7 | 602426.9 | 0.3 | 129.0 | 2.3 | 135.8 | 6.4 | 95 | 95 | 67 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-16-2 | 11/5/2014 | 684767.6 | 602428.4 | 1.2 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 67 | Weldon WC Screenings | | V5N |
| 0 | RF-17 | | 684750.4 | 602403.5 | -2.2 | | | | | | | 70 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-17-1 | 10/10/2014 | 684773.5 | 602414.1 | -0.8 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 70 | Tilcon MH DGA | Bridge lift | V5N |
| 2 | RF-17-2 | 11/5/2014 | 684723.7 | 602387.9 | 1.5 | 124.0 | 3.8 | 128.9 | 12.1 | 96 | 95 | 70 | Weldon WC Screenings | | V5N |
| 0 | RF-18 | | 684686.8 | 602294.5 | -2.4 | | | | | | | 73 | Stratum D | Bottom of excavation elevation | |
| 1 | RF-18-1 | 10/10/2014 | 684659.1 | 602250.1 | -1.3 | 134.5 | 1.0 | 135.8 | 6.4 | 99 | 95 | 73 | Tilcon MH DGA | Bridge lift | V5N |
| 6 | RF-18-2 | 11/5/2014 | 684636.8 | 602258.1 | 5.5 | 124.0 | 3.7 | 128.9 | 12.1 | 96 | 95 | 73 | Weldon WC Screenings | Placed on Type A material | V5N |
| | RF-19 | | 684790.8 | 602339.5 | -2.5 | | | | | | | 75 | Stratum D | Bottom of excavation elevation | |
| 3 | RF-19-1 | 11/5/2014 | 684776.9 | 602328.5 | 1.8 | 124.0 | 3.9 | 128.9 | 12.1 | 96 | 95 | 75 | Weldon WC Screenings | | V5N |
| | RF-21 | | 684826.8 | 602292.8 | -3.3 | | | | | | | 79 | | Bottom of excavation elevation | |
| 2 | RF-21-1 | 9/24/2014 | 684821.0 | 602290.8 | -1.2 | 126.0 | 1.8 | 128.9 | 12.1 | 98 | 95 | 79 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| 4 | RF-21-2 | 11/5/2014 | 684823.4 | 602288.0 | 1.8 | 133.0 | 1.7 | 135.8 | 6.4 | 98 | 95 | 79 | Tilcon MH DGA | | V5N |
| | RF-22 | | 684775.9 | 602192.8 | -4.8 | | | | | | | 82 | | Bottom of excavation elevation | |
| 3 | RF-22-1 | 9/24/2014 | 684777.7 | 602191.8 | -1.1 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 82 | Weldon WC Screenings | Placed on concrete/QP bridge lift | V5N |
| | RF-23 | | 684878.7 | 602219.3 | -5.6 | | | | | | | 85 | | Bottom of excavation elevation | |
| 1 | RF-23-01 | 9/2/2014 | 684887.1 | 602212.2 | -4.2 | 133.0 | 2.0 | 135.8 | 6.4 | 98 | 95 | 85 | Tilcon MH DGA | | V5N |
| 2 | RF-23-02 | 9/12/2014 | 684873.8 | 602198.8 | -1.2 | 128.9 | 7.6 | 128.9 | 12.1 | 100 | 95 | 85 | Weldon WC Screenings | Placed on Type A material | V5N |
| 3 | RF-23-03 | 9/24/2014 | 684867.7 | 602209.0 | 0.0 | 122.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 85 | Weldon WC Screenings | | V5N |
| 5 | RF-23-04 | 11/5/2014 | 684877.6 | 602222.8 | 2.5 | 134.0 | 0.7 | 135.8 | 6.4 | 99 | 95 | 85 | Tilcon MH DGA | | V5N |
| | RF-24 | | 684934.2 | 602167.2 | -4.8 | | | | | | | 90 | | Bottom of excavation elevation | |
| 1 | RF-24-01 | 9/2/2014 | 684928.8 | 602165.1 | -3.5 | 133.5 | 1.3 | 135.8 | 6.4 | 98 | 95 | 90 | Tilcon MH DGA | | V5N |
| 2 | RF-24-02 | 9/8/2014 | 684921.5 | 602154.5 | -2.1 | 122.0 | 4.4 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| 3 | RF-24-03 | 9/12/2014 | 684903.2 | 602144.2 | 0.9 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 90 | Weldon WC Screenings | | V5N |
| 4 | RF-24-04 | 9/24/2014 | 684931.9 | 602159.7 | 1.7 | 122.0 | 12.0 | 128.9 | 12.1 | 95 | 95 | 90 | Weldon WC Screenings | | V5N |
| | RF-25 | | 684988.1 | 602095.1 | -4.8 | | | | | | | 96 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-25-01 | 9/8/2014 | 684973.3 | 602081.8 | 1.6 | 123.0 | 3.9 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | | V5N |
| 4 | RF-25-02 | 9/12/2014 | 684969.6 | 602072.9 | 3.7 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 96 | Weldon WC Screenings | Placed on Type A Material | V5N |
| | RF-26 | | 685029.1 | 602031.1 | -4.8 | | | | | | | 101 | Weldon WC QP | Bottom of excavation elevation | |
| 2 | RF-26-01 | 9/2/2014 | 685038.3 | 602030.1 | -2.5 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 101 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-26-02 | 9/8/2014 | 685029.6 | 602011.4 | 1.4 | 122.0 | 4.2 | 128.9 | 12.1 | 95 | 95 | 101 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-26-03 | 9/12/2014 | 685013.2 | 602014.1 | 3.2 | 128.9 | 3.1 | 128.9 | 12.1 | 100 | 95 | 101 | Weldon WC Screenings | | V5N |
| | RF-27 | | 685076.1 | 601973 | -1.2 | | | | | | | 106 | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-27-01 | 9/8/2014 | 685054.4 | 601963.6 | 2.4 | 122.0 | 4.8 | 128.9 | 12.1 | 95 | 95 | 106 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-27-02 | 9/12/2014 | 685064.1 | 601957.1 | 3.5 | 128.9 | 4.1 | 128.9 | 12.1 | 100 | 95 | 106 | Weldon WC Screenings | | V5N |
| NA | RF-27-LOAM | 12/15/2014 | 685045.9 | 601945.1 | -4.4 | 129.0 | 3.0 | 135.8 | 6.4 | 95 | 95 | 106 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| | RF-28 | | 685132.5 | 601902.9 | 2.1 | | | | | | | 112 (No) | Weldon WC QP | Bottom of excavation elevation | |
| 3 | RF-28-01 | 7/28/2014 | 685136.7 | 601901.8 | 3.7 | 122.5 | 6.1 | 128.9 | 12.1 | 95 | 95 | 112 (No) | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 4 | RF-28-02 | 9/2/2014 | 685126.1 | 601909.3 | 4.9 | 125.0 | 3.0 | 128.9 | 12.1 | 97 | 95 | 112 | Weldon WC Screenings | | V5N |
| 5 | RF-28-03 | 9/8/2014 | 685135.2 | 601900.4 | 6.4 | 125.0 | 3.3 | 128.9 | 12.1 | 97 | 95 | 112 (No) | Weldon WC Screenings | | V5N |
| NA | RF-28-LOAM | 12/15/2014 | 685085.0 | 601862.1 | -4.7 | 135.8 | 4.0 | 135.8 | 6.4 | 100 | 95 | 112 | Tilcon MH DGA | Bottom of lens of anomalous material excavation | V5N |
| 1 | RF-29 | | 685049.3 | 601738.7 | -4.3 | | | | | | | 117 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-29-01 | 7/16/2014 | 685064.7 | 601757.6 | -2.9 | 131.7 | 3.5 | 135.8 | 6.4 | 97 | 95 | 117 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-29-02 | 7/22/2014 | 685068.9 | 601785.4 | -0.8 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 117 | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-29-03 | 7/28/2014 | 685071.0 | 601762.7 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04 | 7/28/2014 | 685068.0 | 601754.7 | 0.8 | 117.0 | 9.0 | 128.9 | 12.1 | 91 | 95 | 117 | Weldon WC Screenings | | V5N |
| 5 | RF-29-04R | 7/30/2014 | 685068.0 | 601754.7 | 0.8 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | Re-rolled area and let dry | V5N |
| 6 | RF-29-05 | 7/30/2014 | 685070.3 | 601762.8 | 1.7 | 122.0 | 5.6 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06 | 8/1/2014 | 685079.5 | 601759.0 | 3.2 | 120.9 | 4.5 | 128.9 | 12.1 | 94 | 95 | 117 | Weldon WC Screenings | | V5N |
| 7 | RF-29-06R | 8/1/2014 | 685079.5 | 601759.0 | 2.8 | 123.5 | 5.8 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | Re-rolled area | V5N |
| 8 | RF-29-07 | 8/4/2014 | 685070.6 | 601753.8 | 3.7 | 126.1 | 7.2 | 128.9 | 12.1 | 98 | 95 | 117 | Weldon WC Screenings | | V5N |
| 9 | RF-29-08 | 8/6/2014 | 685072.8 | 601758.1 | 4.3 | 123.0 | 6.8 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 10 | RF-29-09 | 8/8/2014 | 685074.4 | 601753.5 | 5.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 11 | RF-29-10 | 8/11/2014 | 685078.3 | 601760.5 | 6.1 | 123.0 | 4.5 | 128.9 | 12.1 | 95 | 95 | 117 | Weldon WC Screenings | | V5N |
| 12 | RF-29-11 | 8/15/2014 | 685079.8 | 601756.2 | 7.5 | 123.7 | 3.7 | 128.9 | 12.1 | 96 | 95 | 117 | Weldon WC Screenings | | V5N |
| | RF-30 | | 685179.4 | 601785.6 | 0.4 | | | | | | | 120 | | | |
| 2 | RF-30-01 | 7/1/2014 | 685218.1 | 601814.2 | 2.0 | 122.0 | 7.5 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | Placed on Weldon WC QP | V5N |
| 3 | RF-30-02 | 7/25/2014 | 685216.3 | 601818.6 | 3.0 | 124.0 | 4.3 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 4 | RF-30-03 | 7/30/2014 | 685213.1 | 601816.1 | 3.8 | 123.5 | 5.0 | 128.9 | 12.1 | 96 | 95 | 120 | Weldon WC Screenings | | V5N |
| 5 | RF-30-04 | 8/6/2014 | 685205.4 | 601798.5 | 4.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 6 | RF-30-05 | 8/8/2014 | 685215.8 | 601802.1 | 5.2 | 123.0 | 5.8 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| LIFT | | | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | ENTACT | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 7 | RF-30-06 | 8/11/2014 | 685218.8 | 601812.7 | 6.2 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 8 | RF-30-07 | 8/15/2014 | 685216.3 | 6018806.8 | 7.2 | 123.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | 120 | Weldon WC Screenings | | V5N |
| 1 | RF-31 | | 685121.7 | 601682.3 | -4.3 | | | | | | | 123 | Concrete Bridge Lift | Bottom of excavation elevation | |
| 2 | RF-31-01 | 7/22/2014 | 685126.3 | 601690.0 | -2.2 | 126.3 | 3.4 | 128.9 | 12.1 | 98 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 3 | RF-31-02 | 7/28/2014 | 685124.5 | 601686.4 | -0.1 | 122.5 | 7.7 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | Placed on Type A Material | V5N |
| 4 | RF-31-03 | 7/30/2014 | 685115.0 | 601683.8 | 1.1 | 122.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 5 | RF-31-04 | 7/30/2014 | 685123.7 | 601688.2 | 2.3 | 122.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-31-05 | 8/1/2014 | 685120.9 | 601687.7 | 3.0 | 128.9 | 6.2 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-31-06 | 8/4/2014 | 685122.7 | 601686.6 | 3.9 | 128.9 | 5.8 | 128.9 | 12.1 | 100 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-31-07 | 8/6/2014 | 685132.5 | 601689.3 | 4.8 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 9 | RF-31-08 | 8/8/2014 | 685118.7 | 601690.5 | 5.5 | 125.0 | 2.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 10 | RF-31-09 | 8/11/2014 | 685136.4 | 601690.8 | 6.6 | 125.0 | 3.5 | 128.9 | 12.1 | 97 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 11 | RF-31-10 | 8/15/2014 | 685122.6 | 601682.9 | 7.6 | 123.0 | 7.4 | 128.9 | 12.1 | 95 | 95 | 123 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-32 | | 684498.6 | 602739.4 | -1.2 | | | | | | | 125 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-32-01 | 6/12/2014 | 685241.5 | 601740.7 | 0.0 | 134.0 | 1.3 | 135.8 | 6.4 | 99 | 95 | 125 | Tilcon MH DGA | | V5N |
| 2 | RF-32-02 | 7/16/2014 | 685227.6 | 601725.4 | 0.9 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 3 | RF-32-03 | 7/16/2014 | 685239.4 | 601736.4 | 2.0 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 4 | RF-32-04 | 7/30/2014 | 685248.5 | 601750.7 | 3.4 | 123.5 | 6.0 | 128.9 | 12.1 | 96 | 95 | 125 | Weldon WC Screenings | | V5N |
| 5 | RF-32-05 | 8/6/2014 | 685249.6 | 601745.6 | 4.6 | 123.0 | 5.9 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 6 | RF-32-06 | 8/8/2014 | 685249.1 | 601742.7 | 5.6 | 123.0 | 5.7 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 7 | RF-32-07 | 8/11/2014 | 685237.6 | 601735.2 | 6.5 | 123.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 8 | RF-32-08 | 8/15/2014 | 685238.9 | 601747.0 | 7.3 | 123.0 | 7.0 | 128.9 | 12.1 | 95 | 95 | 125 | Weldon WC Screenings | | V5N |
| 1 | RF-33 | | 685179.2 | 601631.6 | -7.5 | | | | | | | 128 | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-33-01 | 6/5/2014 | 685182.8 | 601626.5 | -5.1 | 132.0 | 3.7 | 135.8 | 6.4 | 97 | 95 | 128 | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-33-02 | 7/28/2014 | 685146.0 | 601639.6 | -0.9 | 123.7 | 6.4 | 128.9 | 12.1 | 96 | 95 | 128 | Weldon WC Screenings | Placed on Type A Material/QP Ramp | V5N |
| 4 | RF-33-03 | 7/30/2014 | 685159.9 | 601630.8 | 0.8 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 5 | RF-33-04 | 7/30/2014 | 685144.1 | 601632.9 | 1.3 | 122.0 | 6.5 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 6 | RF-33-05 | 8/1/2014 | 685171.2 | 601638.5 | 3.2 | 128.9 | 6.0 | 128.9 | 12.1 | 100 | 95 | 128 | Weldon WC Screenings | | V5N |
| 7 | RF-33-06 | 8/1/2014 | 685156.8 | 601643.7 | 3.9 | 127.0 | 5.0 | 128.9 | 12.1 | 99 | 95 | 128 | Weldon WC Screenings | | V5N |
| 8 | RF-33-07 | 8/6/2014 | 685176.1 | 601633.1 | 4.7 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 9 | RF-33-08 | 8/8/2014 | 685166.7 | 601630.5 | 5.5 | 123.0 | 6.2 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 10 | RF-33-09 | 8/11/2014 | 685166.3 | 601631.6 | 6.6 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 11 | RF-33-10 | 8/15/2014 | 685165.2 | 601633.6 | 7.9 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 128 | Weldon WC Screenings | | V5N |
| 0 | RF-34 | | 685278.4 | 601673.3 | -1.2 | | | | | | | 130 | Stratum O | Bottom of excavation elevation | |
| 1 | RF-34-01 | 6/5/2014 | 685303.0 | 601691.1 | 0.3 | 132.0 | 3.6 | 135.8 | 6.4 | 97 | 95 | 130 | Tilcon MH DGA | | V5N |
| 2 | RF-34-02 | 6/24/2014 | 685298.9 | 601690.4 | 1.6 | 122.0 | 5.5 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 3 | RF-34-03 | 6/27/2014 | 685295.5 | 601692.8 | 2.5 | 122.5 | 7.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 4 | RF-34-04 | 7/16/2014 | 685293.1 | 601684.6 | 3.2 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 5 | RF-34-05 | 7/30/2014 | 685290.2 | 601690.3 | 4.5 | 123.5 | 6.5 | 128.9 | 12.1 | 96 | 95 | 130 | Weldon WC Screenings | | V5N |
| 6 | RF-34-06 | 8/8/2014 | 685289.5 | 601690.7 | 5.5 | 123.0 | 6.9 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 7 | RF-34-07 | 8/8/2014 | 685292.7 | 601686.1 | 6.6 | 123.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | 130 | Weldon WC Screenings | | V5N |
| 8 | RF-34-08 | 8/15/2014 | 685286.1 | 601677.8 | 7.6 | 126.0 | 2.3 | 128.9 | 12.1 | 98 | 95 | 130 | Weldon WC Screenings | | V5N |
| 0 | RF-35 | | 6852228.7 | 601575.4 | 2.1 | | | | | | | 133 | | Bottom of excavation elevation | |
| 1 | RF-35-01 | 7/16/2014 | 685219.7 | 601566.3 | 3.5 | 123.3 | 6.2 | 128.9 | 12.1 | 96 | 95 | 133 | Weldon WC Screenings | | V5N |
| 2 | RF-35-02 | 7/16/2014 | 685234.2 | 601582.4 | 4.3 | 124.9 | 4.9 | 128.9 | 12.1 | 97 | 95 | 133 | Weldon WC Screenings | | V5N |
| 3 | RF-35-03 | 7/25/2014 | 685238.5 | 601578.0 | 5.8 | 122.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 4 | RF-35-04 | 8/8/2014 | 685239.0 | 601569.1 | 6.9 | 123.0 | 6.6 | 128.9 | 12.1 | 95 | 95 | 133 | Weldon WC Screenings | | V5N |
| 0 | RF-36 | | 685334.4 | 601603.7 | -1.2 | | | | | | | 136 | | Bottom of excavation elevation | |
| 1 | RF-36-01 | 6/24/2014 | 685349.2 | 601617.6 | 1.7 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 2 | RF-36-02 | 6/27/2014 | 685330.9 | 601606.5 | 2.6 | 125.0 | 6.5 | 128.9 | 12.1 | 97 | 95 | 136 | Weldon WC Screenings | | V5N |
| 3 | RF-36-03 | 6/27/2014 | 685339.9 | 601612.8 | 3.4 | 123.7 | 6.8 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 4 | RF-36-04 | 7/16/2014 | 685343.2 | 601621.5 | 4.3 | 123.8 | 5.5 | 128.9 | 12.1 | 96 | 95 | 136 | Weldon WC Screenings | | V5N |
| 5 | RF-36-05 | 7/28/2014 | 685346.6 | 601606.1 | 5.4 | 122.0 | 5.2 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 6 | RF-36-06 | 8/8/2014 | 685345.5 | 601605.6 | 6.7 | 126.0 | 1.6 | 128.9 | 12.1 | 98 | 95 | 136 | Weldon WC Screenings | | V5N |
| 7 | RF-36-07 | 8/15/2014 | 685335.6 | 601611.4 | 7.7 | 123.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 136 | Weldon WC Screenings | | V5N |
| 1 | RF-37 | | 685295.3 | 601495.2 | -7.8 | | | | | | | 140 (So) | Crushed Concrete | Bottom of excavation elevation | |
| 2 | RF-37-01 | 5/15/2014 | 685286.1 | 601481.2 | -5.1 | 132.0 | 2.5 | 135.8 | 6.4 | 97 | 95 | 140 (So) | Tilcon MH DGA | Placed on concrete bridge lift | V5N |
| 3 | RF-37-02 | 5/21/2014 | 685294.5 | 601489.0 | -4.2 | 122.5 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 4 | RF-37-03 | 7/7/2014 | 685282.8 | 601485.7 | 4.5 | 128.9 | 6.1 | 128.9 | 12.1 | 100 | 95 | 140 (So) | Weldon WC Screenings | 1st lift over Type A Material | V5N |
| 5 | RF-37-04 | 7/28/2014 | 685281.8 | 601490.5 | 5.9 | 123.7 | 5.4 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 6 | RF-37-05 | 7/28/2014 | 685310.0 | 601513.3 | 6.6 | 123.0 | 4.7 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 7 | RF-37-06 | 8/8/2014 | 685297.5 | 601485.6 | 7.1 | 124.0 | 4.1 | 128.9 | 12.1 | 96 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 8 | RF-37-07 | 8/15/2014 | 685288.7 | 601489.2 | 8.0 | 123.0 | 5.0 | 128.9 | 12.1 | 95 | 95 | 140 (So) | Weldon WC Screenings | | V5N |
| 0 | RF-38 | | 685399.1 | 601540.2 | -1.2 | | | | | | | 142 (No) | Stratum O | Bottom of excavation elevation | |
| 1 | RF-38-01 | 5/9/2014 | 685391.8 | 601532.2 | -0.2 | 124.6 | 2.5 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 2 | RF-38-02 | 5/21/2014 | 685389.4 | 601534.3 | 0.2 | 122.5 | 5.6 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 3 | RF-38-03 | 6/24/2014 | 685386.6 | 601538.7 | 4.0 | 125.0 | 3.4 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 4 | RF-38-04 | 6/27/2014 | 685392.8 | 601538.8 | 5.3 | 124.0 | 6.0 | 128.9 | 12.1 | 96 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 5 | RF-38-05 | 7/28/2014 | 685385.3 | 601533.9 | 6.3 | 122.0 | 6.4 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 6 | RF-38-06 | 8/8/2014 | 685382.7 | 601533.1 | 7.1 | 125.0 | 3.2 | 128.9 | 12.1 | 97 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 7 | RF-38-07 | 8/15/2014 | 685382.8 | 601528.2 | 7.9 | 123.0 | 6.0 | 128.9 | 12.1 | 95 | 95 | 142 (No) | Weldon WC Screenings | | V5N |
| 0 | RF-39 | | 685485.1 | 601397.7 | 3.8 | | | | | | | 153 | Stratum O | Bottom of excavation elevation | |

# FIELD DENSITY TEST SUMMARY LOG
## Testing Frequency - 5 Tests per Acre
## HONEYWELL STUDY AREA 6 REMEDIATION PROJECT
## JERSEY CITY, NEW JERSEY

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | ENTACT | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | CELL # | LIFT MATERIAL | NOTES | COMPANY |
| 1 | RF-39-01 | 5/5/2014 | 685451.1 | 601421.7 | 4.3 | 126.3 | 3.9 | 128.9 | 12.1 | 98 | 95 | 153 | Weldon WC Screenings | | V5N |
| 2 | RF-39-02 | 5/5/2014 | 685477.5 | 601397.7 | 5.6 | 123.3 | 4.1 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 3 | RF-39-03 | 5/5/2014 | 685492.5 | 601460.8 | 6.4 | 123.8 | 7.4 | 128.9 | 12.1 | 96 | 95 | 153 | Weldon WC Screenings | | V5N |
| 0 | Site 163-1 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-1-1 | 10/30/2014 | 685176.1 | 601448.3 | 5.7 | 126.0 | 2.4 | 128.9 | 12.1 | 98 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 2 | Site 163 -1-2 | 10/30/2014 | 685173.8 | 601449.0 | 7.4 | 123.0 | 5.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 West Excavation | V5N |
| 0 | Site 163-2 | | | | 4.5 | | | | | | | Site 163 | | Bottom of excavation elevation | |
| 1 | Site 163-2-1 | 11/5/2014 | 685070.9 | 601614.2 | 6.1 | 122.0 | 6.3 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| 2 | Site 163-2-2 | 11/14/2014 | 685070.5 | 601616.0 | 7.5 | 122.0 | 5.4 | 128.9 | 12.1 | 95 | 95 | Site 163 | Weldon WC Screenings | Site 163 Main Excavation | V5N |
| | | | | | | | | | | | | | | | |

***Notes:*** Maximum Dry Density for Weldon WC Screenings based on Sor Testing Laboratories Report No. 13-1877 dated 11/6/13.
Maximum Dry Density (gravel corrected) for Tilcon MH DGA based on Sor Testing Laboratories Report No. 13-1334 dated 8/7/13.
Re-used on site historical fill material (Type A) will not be tested for compaction per Specification Section 02315-3.13 A.2.b
Moisture content not to exceed 3% above optimum per Specification Section 02315-2.04C
Bottom of excavation elevation based on Maser survey data (Center Point elevations)
Sample ID RF-01-01 where:

RF = Reduced Frequency
01 = Test Location (as noted on Backfill Compaction Location Figure)
01 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again
= Area subject to re-compaction

# ATTACHMENT E

# TABLE SUMMARY OF SOIL MANAGEMENT ACTIVITIES

**ATTACHMENT E**
**SUMMARY OF SOIL MANAGEMENT ACTIVITIES**

STUDY AREA 6 SOUTH
SA-6 CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY

| Excavated Material Description | Approximate Excavation Volume (CYs) | Approximate Off Site Disposal Volume (CYs) | Approximate Reused As Backfill in Development Area Volume (CYs) | Approximate Volume Consolidated Under South Cap (CYs) | Approximate Volume Consolidated Under North Cap (CYs) |
|---|---|---|---|---|---|
| <20 mg/kg Overburden Non-Chromium-Impacted | 65,000 | 21,500 | 15,000 | 20,000 | 8,500 |
| 20-240 mg/kg Chromium-Impacted | 48,000 | 15,200 | 0 | 11,800 | 21,000 |
| 240-1,000 mg/kg Chromium-Impacted | 20,000 | 5,300 | 0 | 14,700 | 0 |
| >1,000 mg/kg Chromium-Impacted | 23,500 | 17,500 | 0 | 6,000 | 0 |
| Concrete | 6,500 | 1,500 | 5,000 | 0 | 0 |
| **Total** | **163,000** | **61,000** | **20,000** | **52,500** | **29,500** |

**Notes:**

1. 6,000 CYs (>1,000) consolidated under South cap is soil that was re-classified as <1,000 Hex Cr based upon stockpile reuse sampling results.
2. The volumes provided on this table are estimated and may be based upon conversion factors or other non-surveyed means of soil measurement procedures.



Revised By: TDD 09/14/15
Checked By: DEN 09/14/15

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 21 OF 25**

- **Declaration #2 Part 1**

**Attachments A – F (Part 1)**

CHROMIUM REMEDY
SA-6 SOUTH

DECLARATION #2

3458855-3

**UNITED STATES DISTRICT COURT DISTRICT OF NEW JERSEY**

JERSEY CITY INCINERATOR AUTHORITY,

Plaintiffs, v.

HONEYWELL INTERNATIONAL INC., et al.,

Defendants.

Civil Action No. 05-5993 Consolidated with Docket No 05-5955 under Docket No. 95-2097 (DMC)
Civil Action No 06-22 Consolidated with Docket No. 05-5955 (DMC) under Docket No. 95-2097

Civil Action No. 06-0022 (JLL)
(Consolidated under Civ. No. 05-5955 (JLL))

Second SA-6 South Consent Decree Declaration

On August 14, 2012, the USDC DNJ entered the First Amended Consent Decree Regarding Remediation and Redevelopment of Study Area 6 South ("SA-6 South Consent Decree"). Pursuant to Article III, Honeywell may file one or more Declarations showing compliance with the SA-6 South Consent Decree. The initial SA-6 South Consent Decree Declaration ("Declaration #1) was filed by Honeywell with the consent of the other parties to memorialize Honeywell's partial compliance with the terms of the SA-6 South Consent Decree on March 18, 2016. This second SA-6 South Declaration ("Declaration #2) is hereby filed by Honeywell with the consent of the other parties to memorialize partial compliance with the terms of the SA-6 South Consent Decree completed subsequent to Declaration #1.

We, the undersigned, declare as follows:

1. William J. Hague is Director of Remediation Design and Construction for Honeywell International Inc. ("Honeywell") for SA-6 South New Jersey Department of Environmental Protection (NJDEP) Sites 073, 124, 125, 134, 140 and 163. Mr. Hague has direct responsibility on behalf of Honeywell for the management of remediation construction activities at SA-6 South related to the implementation of the Chromium Remedy as defined in Article III of the SA-6 South Consent Decree.

2. Remediation and site restoration activities were performed in accordance with the SA-6 South Consent Decree, the NJDEP Technical Requirements for Site Remediation, the NJDEP-approved *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan for Chromium* to address chromium contamination at SA-6 South, dated December 23, 2008, the NJDEP- approved *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan,* to address chromium contamination at Site 163 only, dated, May 18, 2012 (collectively referred to as the RAWPs), the Chromium Remedy 100% Design Report for Study Area 6 North & Study Area 6 South dated June 28, 2013 ("SA-6 100% Design"), and three field changes (DC 2014-3-25 - "Contingent GW Extraction System: Replace Wells with Trenches," DC 2015-3-04 – " 3S Surcharge Pile Geometry on East End" and DC 2015-2-24 - "GW Extraction System: Revision to Geomembrane / Subgrade Surface") that materially impacted the 100% Design (referred to herein as "Design Changes"), with the continued oversight and supervision of the appointed Special Master. The SA-6 100% Design, including Design Drawings and Technical Specifications, was developed consistent with the SA-6 North & SA-6 South Consent Decrees and NJDEP-approved RAWPs and was approved by all Parties. On June 12, 2013, the Special Master approved the SA-6 100% Design for submittal to the Court, subject to Honeywell's confirmation regarding several issues. On June 28, 2013 Honeywell submitted the Final – Issued for Construction Chromium Remedy 100% Design Submittal for the Study Area 6 North and South projects ("Final 100% Design") to the Court, and the Court entered the 100% Design on July 9, 2013.

3. The elements of the remedy that are the subject of this Declaration were substantially completed between April 2015 and November 2015.

4. This is the second Declaration for SA-6 South. Future Declarations will document the work on the elements of the remedy set forth in the SA-6 South Consent Decree implemented or completed after November 2015.

5. To implement the requirements of the SA-6 South Consent Decree, Honeywell retained AMEC Environment and Infrastructure, Inc. (now Amec Foster Wheeler Environment & Infrastructure, Inc., "Amec Foster Wheeler") to design and coordinate the construction activities related to the Chromium Remedy of SA-6 South. Amec Foster Wheeler is the Engineer of Record for the design and implementation of construction

activities related to the Chromium Remedy of SA-6 South. Amec Foster Wheeler engaged Entact, LLC ("Entact") to perform the construction. Entact was responsible for implementing the SA-6 South construction in accordance with the Final 100% Design and Design Changes. Entact reported directly to Amec Foster Wheeler and provided the final construction details, including as-built drawings, upon project completion. Mr. Joseph T. Clifford is a licensed Professional Engineer in the State of New Jersey, a Principal Engineer (Professional Engineer, NJ, GE38067) at Amec Foster Wheeler and is the engineer at Amec Foster Wheeler with primary responsibility for management of the design and construction coordination activities at SA-6 South.

6. Based on our professional opinion, the data and information set forth for the specific work elements noted in and attached to this Declaration were performed consistent with the Final 100% Design and Design Changes.

7. Declaration #2 pertains to the following elements of the SA-6 South Chromium Remedy:

I. Contingent Groundwater Collection Trench,

II. Cap Subgrade,

III. Cap Geosynthetics, and

IV. Hydraulic Barrier Wall Final Elevation

Further details related to elements I-IV are provided below. Supporting documentation is provided in the Attachments.

I. Contingent Groundwater Collection Trench. This Declaration addresses installation of the Contingent Groundwater Collection Trench and associated manhole structures and piezometers to be used for documenting hydraulic gradients across the Barrier Walls at SA-6 South. The contingent groundwater system design was changed from a well-based collection system to a trench-based collection system in DC 2014-3-25. The trench was installed between May 22, 2014 and February 11, 2015 and is designed to meet the requirements of Paragraphs 69(c) of the Consent Decree. Piezometric pairs were installed to allow for the collection of groundwater elevation data to meet the requirements of Paragraphs 69(e) of the Consent Decree. The Contingent Groundwater Collection Trench is located within the SA-6 South Open Space Area of Concern (AOC).

The Contingent Groundwater Collection Trench runs along the east-west axis of the SA-6 South Open Space. The bottom of the trench is designed to be just above the top of the Stratum D soils. Groundwater modeling

indicated that the trench will be effective in meeting the capture zone specified in Section 69(d).

Honeywell collected the survey data necessary to document the plan and profile of the collection trench. The Contingent Groundwater Collection Trench Record Drawing is provided in this Declaration as Attachment A. Specific piezometer locations are provided on Figure 1 in Attachment A-1.

II. Cap Subgrade

a. Surcharge Program. The main purpose of the surcharge program in the Open Space Cap AOC was to remove settlement that would be detrimental to the remedy and permissible development. Surcharging was performed by placing fill materials to reach the surcharge design loads and then monitoring the areas to confirm that the objectives of the program had been met. The Surcharge Program was implemented moving from West to East. For planning and documentation purposes the Surcharge was split into 3 areas: Area 1S, Area 2S and Area 3S. Individual reports were submitted monthly during the course of the program. Surcharge Monitoring Plan Monthly Report No. 12, for the March 2015 reporting period, dated April 2015 indicated that surcharging in Areas 1S, 2S and 3S was complete. In addition, during the course of the surcharge program, DC 2015-3-4 was submitted concerning surcharge in the 0-12 foot-wide Deferred Area strip along Route 440. Mueser Rutledge Consulting Engineers (”MRCE”) prepared a letter dated September 29, 2015 stating that truncation of the easterly tip of the Surcharge pile in the deferred area by Route 440 would have no material impact on evaluation of achievement of the surcharge goals on SA-6 South. (Work adjacent to Route 440 had been deferred and will be completed in accordance with the Consent Order Consolidating the 100% Design for Study Area 6 North and Study Area 6 South filed into the Court on July 9, 2013.) The surcharge reports, which were peer reviewed by MRCE, concluded that the surcharge goal had been met for each area. MRCE letters acknowledging achievement of surcharge goals in Areas 1S, 2S, and 3S, as well as the September 29, 2015 letter, are included in Attachment C. The surcharge reports were also reviewed by O’Connell and Lawrence Inc. on behalf of the Plaintiffs. The Surcharge Completion Evaluation tables for each area are included in Attachment B.

b. Grading. Following surcharge, the cap was graded and compacted in accordance with the lines, grades and compaction requirements indicated in the Final 100% Design and Design Change DC 2015-02-24. Subgrade preparation was performed between May 11, 2015 and October 9, 2015. To document compliance with the grading requirements, a Construction Control Grid was established consistent with Specification 01460. The Construction Control Grid is included as Attachment D-1. Summary tables prepared by Maser Consulting PA (NJ licensed surveyor) comparing the design grades and actual grades at the Construction Control Grid nodes are included as Attachment D-2 confirming that all nodes are within tolerance. A topographic survey of the SA-6 South subgrade was prepared by Maser Consulting (Attachment E).

III. Cap Geosynthetics. Installation of the cap geosynthetics followed Maser Consulting's certification that the subgrade surface conformed to the specified Construction Control Grid. Amec Foster Wheeler provided QA approval of Maser's documented subgrade elevations prior to issuing to Langan Engineering and Environmental Services, Inc, ("Langan") for approval for geosynthetics deployment. In addition, as part of the subgrade approvals, Amec Foster Wheeler provided QA approval of the sand bentonite GCL to barrier wall connections (signed GCL to barrier wall logs are included in Appendix H of the Langan Cap Geosynthetic Quality Assurance (QA) Report for Study Area 6 South). The cap geosynthetics were placed between July 20, 2015 and November 4, 2015. The cap geosynthetics included components that were designed to meet the technical requirements of Section 65(a) of the Consent Decree. The cap geosynthetics scope included the following key tasks:

- Subgrade inspection for acceptability prior to geosynthetics deployment,
- Gas Vent/Geotextile and GCL installation over the subgrade and under the geomembrane,
- Geomembrane Installation-60 mil LLDPE,
- Geocomposite drainage/warning layer installation, and
- Warning tape installation.

Honeywell contracted with Langan to provide Independent QA for the SA-6 cap geosynthetics installation. As the Independent QA Engineer, Langan performed the QA activities specified in the Langan Cap Geosynthetic Quality Assurance (QA) Report for Study Area 6 South ("Langan Report"),

including monitoring, field oversight, and documentation. The report certifies that placement of the SA-6 South cap geosynthetics was completed in compliance with the construction design documents (see Attachment F).

Acceptance of the geosynthetic materials used for the SA-6 South Cap Construction was completed by Amec Foster Wheeler based on the results of the manufacturer's production quality testing (AGRU America, Inc. and their subcontracted companies). The Amec Foster Wheeler Engineer of Record provided a full-time site Geosynthetics Inspector to inspect materials deployment, installation and documentation for compliance with the Final 100% Design of the capping system. The Geosynthetics Inspector observed the placement of the GDL cover soil to verify that the soil was placed in accordance with the Earthwork and GDL specifications (02315 and 02374, respectively) and that the GDL was not damaged or unnecessarily stressed. The GDL cover soil will be included in a future Declaration. The Geosynthetics Inspector also observed the fabrication, installation and extrusion welding and vacuum testing of all boots.

QC for geosynthetics installation was provided by Entact and their specialty installer ESI. Entact also contracted with Geotechnics, Inc. to conduct the specified offsite laboratory testing required as part of the capping project, such as destructive seam testing. All ESI field QC and Geotechnics laboratory testing is incorporated into the Langan QA Report and are the subject of the Langan QA Certification. Langan offsite QA laboratory testing was completed by TRI Environmental, Inc. The Langan Report and the Langan engineer certification are included in Attachment F. As-built drawings of the cap geosynthetics (i.e, 60 mil Textured LLDPE Geomembrane, Gas vent Layer/Geosynthetic Clay Liner (GVL/GCL) Layout, Geocomposite Drainage Layer (GDL) Layout) are included as Attachment G.

IV. Hydraulic Barrier Wall Final Elevation. In Declaration #1, Honeywell declared the completion of hydraulic barrier installation at SA-6 South in accordance with the Final 100% Design and Related Design Changes. At the time of the Initial Declaration, the top of hydraulic barrier wall had been left at elevations consistent with the temporary flood control and subgrade/surcharge requirements.

The top of the hydraulic barrier wall was then trimmed to final elevation in preparation for cap placement. Hydraulic barrier wall cutting began June 9,

2015 and was completed on October 7, 2015. In Declaration #1, Honeywell indicated that "the final elevations will be included in a supplemental Declaration". The As-Built Drawings submitted as part of Declaration #1 have been updated to show the final top of wall of both the SCB wall and hydraulic sheet pile wall (Attachment H).

Items listed above will also be provided in the final Remedial Action Report.

1. Based on our professional experience, the data and information set forth in and attached to this Declaration, and our supervision of the SA-6 South construction activities, we believe that the Contingent Groundwater Collection Trench, Cap Subgrade, Cap Geosynthetics, and Hydraulic Barrier Wall Final Elevations were installed/completed in accordance with the SA-6 South Consent Decree and the Final 100% Design and Related Design Changes.

2. We certify that the foregoing is true and correct to the best of our respective knowledge.

William J. Hague

Date

Joseph T. Clifford PE NJ, GE38067

Date

## List of Attachments

A. Contingent Groundwater Collection Trench Record Drawing

A-1 – Figure 1: Monitoring Well Locations

B. Surcharge Completion Evaluation Tables

C. MRCE Surcharge Completion Letters

D. SA-6 South Cap Subgrade Approval

D-1 – Construction Control Grid

D-2 – SA-6 South Subgrade Grid Points

E. SA-6 South Cap Subgrade Topographic Survey

F. Langan SA-6 South Cap Quality Assurance Report

G. SA-6 South Cap As-Built Drawings

G-1 – SA-6 South Cap Panel Layout (60 mil Textured LLDPE Geomembrane)

G-2 – SA-6 South Cap GVL / GCL Layout (Class A Geotextile / Gas Vent Layer / Geosynthetic Clay Liner)


G-3 – SA-6 South Cap GDL Layout (Geocomposite Drainage Layer)

H. SA-6 South Hydraulic Barrier Wall Plan and Profile As-Built

I. Design Changes

**ATTACHMENT A**
**CONTINGENT GROUNDWATER COLLECTION TRENCH**
**RECORD DRAWING**

# PLAN VIEW




# PROFILE VIEW




## LEGEND

- 8" PERFORATED HDPE PIPE INVER (ELEV. TYPICAL)
- 4FT DIA. MANHOLE RISER PROFILE
- SCB WALL
- HYDRAULIC BARRIER WALL
- CAP SUBGRADE CONTOUR (DESIGN)
- CAP FINAL GRADE CONTOUR (DESIGN)
- 4FT DIA. MANHOLE
- 1.5" CLEAN STONE TRENCH (WIDTH VARIES 3' TO 12')

| REV | DATE | BY | CHK'D | APPR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 1/13/16 | CDC | AE | AE | RECORD DRAWING |
| 1 | 2/10/16 | CDC | AE | AE | ADDED ANNOTATION EDITS |
| 2 | 2/19/16 | CDC | AE | AE | REVISED ANNOTATION EDITS AND ADJUSTED MANHOLE REFERNCES |

J.H. 06/21/2016


ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP
CONTINGENT GROUNDWATER COLLECTION TRENCH
RECORD DRAWING 02/19/15

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT A-1**
**FIGURE 1: MONITORING WELL LOCATIONS**

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DISCLOSED, AND OTHER USE OF RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THE PARTY'S SOLE RISK AND RESPONSIBILITY.




SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| 2 | 02/01/16 | UPDATE WITH NEW WELLS / REMOVE ABANDONED WELLS | STR | DEN |
| 1 | 04/10/13 | ADDED 2 NEW MONITORING WELLS | STR | DEN |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488-5710-MWL0-F900

*PREPARED/DATE:* STR 04/20/16

*CHECKED/DATE:* DEN 05/06/16

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 1**
MONITORING WELL LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\2007\HOMEWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710-01\CURRENT DRAWINGS\3480150488-5710-MWL0-F900.dwg Thu, 07 Jul 2016 - 10:44am wcutt.wutkin Layout: SITE

**ATTACHMENT B**
**SURCHARGE COMPLETION EVALUATION TABLES**

## TABLE 1S-1
## SURCHARGE COMPLETION EVALUATION
## SUMMARY OF EFFECTIVE STRESS

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-01** | 2616 | 3236 | **124%** | Data as of November 2014. Pore pressure elevated 5 ft in Stratum D and 3 ft in Stratum RC. |
| **S_FS-02** | 2627 | 3201 | **122%** | Data as of November 2014. Pore pressure elevated 4.5 ft in Stratum D. |
| **S_HS-01** | 3064 | 3292 | **107%** | Data as of November 2014. |
| **S_HS-02** | 2571 | 2962 | **115%** | Data as of November 2014. Pore pressure elevated 3 ft in Stratum D. |
| **S_HS-03** | 2400 | 2541 | **106%** | Data as of November 2014. Pore pressure elevated 11 ft in Stratum D and 5.5 ft in Stratum RC. |
| **S_HS-04** | 2548 | 3053 | **120%** | Data as of November 2014. Pore pressure elevated 5 ft in Stratum D. |
| **S_HS-05** | 2583 | 2919 | **113%** | Data as of November 2014. |
| **S_HS-06** | 2881 | 3205 | **111%** | Data as of November 2014. Pore pressure elevated 1.5 ft in Stratum D and 7 ft in Stratum RC. |
| **S_HS-07** | 2494 | 3130 | **126%** | Data as of November 2014. |
| **S_HS-08** | 2595 | 2880 | **111%** | Data as of November 2014. Pore pressure elevated 5 ft in Stratum D. |

**TABLE 2S-1**
**SURCHARGE COMPLETION EVALUATION**
**AMEC CORRECTED RESULTS JANUARY 2015**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| S_FS-03 | 2343 | 2984 | 127% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_FS-04 | 2359 | 2909 | 123% | VWP data through 1/18/15; SP data through 1/30/15. |
| S_FS-05 | 1839 | 1833 | 100% | VWP data through 1/29/15; SP data through 1/30/15. |
| S_HS-09 | 2232 | 3194 | 143% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-10 | 2479 | 2777 | 112% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-11 | 2342 | 2656 | 113% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-12 | 2482 | 2877 | 116% | VWP data through 1/12/15; SP data through 1/30/15. |
| S_HS-13 | 2100 | 2412 | 115% | VWP data as of 1/29/15; SP data through 1/30/15. |
| S_HS-14 | 2138 | 2839 | 133% | VWP data as of 1/12/15; SP data through 1/30/15. |
| S_HS-15 | 2637 | 3234 | 123% | VWP data as of 1/12/15; SP data through 1/30/15. |

**TABLE 3S-1**
**SURCHARGE COMPLETION EVALUATION**

| SURCHARGE MONITORING POINT | FINAL DEVELOPMENT CONDITION | SURCHARGE CONDITIONS | SURCHARGE COMPLETION EVALUATION | |
|---|---|---|---|---|
| | Middle of Stratum D | Middle of Stratum D | Middle of Stratum D<br>Effective Stress Conditions / Comparisons | |
| | Effective Stress (psf) | Effective Stress (psf) | Percent Complete | Comments |
| **S_FS-06** | 2099 | 2664 | **127%** | Data through March 2015 |
| **S_FS-07** | 2376 | 2691 | **113%** | Data through March 2015 |
| **S_HS-16** | 2522 | 2619 | **104%** | Data through March 2015 |
| **S_HS-17** | 1751 | 2046 | **117%** | Data through March 2015 |
| **S_HS-18** | 970 | 1458 | **150%** | Data through March 2015 |
| **S_HS-19** | 845 | 1206 | **143%** | Data through March 2015 |
| **S_HS-20** | 2484 | 2499 | **101%** | Data through March 2015 |
| **S_HS-21** | 1504 | 1978 | **132%** | Data through March 2015 |
| **S_HS-22** | 966 | 1198 | **124%** | Data through March 2015 |

**ATTACHMENT C**
**MRCE SURCHARGE COMPLETION LETTERS**

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacollo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

April 24, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 1S Surcharge Review
SA-6 South
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) October 27, 2014 review of Area 1S indicated settlement monitoring location S_FS-02 did not meet the defined surcharge program goal as of September 23, 2014. AMEC provided MRCE with updated settlement and piezometer monitoring data for Area 1S location S_FS-02 on April 14, 2015. The MRCE review of April 14, 2015 AMEC settlement and piezometer monitoring data for Area 1S location S_FS-02 is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated November 18, 2014 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressure. Post-surcharge total stress was calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken on November 25, 2014. Calculated post-surcharge effective stress for S_FS-02 is presented in Table 1. MRCE compared the calculated post-surcharge effective stress with the "Final Post-Development Conditions" effective stress estimate provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 1S monitoring locations have met the surcharge program goal as of November 25, 2014.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

Table 1. MRCE SA-6 South Surcharge Monitoring Review for Area 1S (April 2015)

| Source: | | AMEC | | | | MRCE | | | | | | | | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Settlement Monitoring Point | Layer | Center of the Layer EL. (ft) | Pre-Surcharge Conditions Total Stress (psf) | Final Development Condition Effective Stress (psf) | Surcharge Conditions Effective Stress | Settlement Monitoring Data | | VWP Monitoring Data | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion (November 2014) |
| | | | | | | Date of Recording | Fill Thickness (ft) | Date of Recording | Elevation Head (ft) | | | | | |
| S_FS-01 | Center D | -8.6 | 1852.5 | 2616.3 | 2451.0 | 9/22/2014 | 17.15 | 9/23/2014 | 11.83 | 3996.3 | 1274.8 | 2721.4 | 104% | 124% |
| S_FS-02 | Center D | -11.16 | 2083.8 | 2627.1 | 2428.0 | 11/25/2014 | 21.17 | 11/18/2014 | 11.6 | 4730.1 | 1420.2 | 3309.8 | 126% | 122% |
| S_HS-01 | Center D | -11.2 | 2260.0 | 3064.0 | 3196.0 | 9/22/2014 | 15.31 | 9/23/2014 | 3.09 | 4173.8 | 891.7 | 3282.1 | 107% | 107% |
| S_HS-02 | Center D | -9.6 | 2103.8 | 2570.7 | 2774.0 | 9/22/2014 | 15.22 | 9/23/2014 | 7.11 | 4006.3 | 1042.7 | 2963.6 | 115% | 115% |
| S_HS-03 | Center D | -9.4 | 1942.5 | 2400.1 | 2440.0 | 9/22/2014 | 15.9 | 9/23/2014 | 12.19 | 3930.0 | 1347.2 | 2582.8 | 108% | 106% |
| S_HS-04 | Center D | -8.3 | 1841.3 | 2548.2 | 2595.0 | 9/22/2014 | 15.54 | 9/23/2014 | 9.4 | 3783.8 | 1104.5 | 2679.3 | 105% | 120% |
| S_HS-05 | Center D | -8.5 | 2031.3 | 2583.0 | 2703.0 | 9/22/2014 | 13.89 | 9/23/2014 | 6.25 | 3767.6 | 920.4 | 2847.2 | 110% | 113% |
| S_HS-06 | Center D | -10.4 | 2126.3 | 2880.7 | 3214.0 | 9/22/2014 | 16.24 | 9/23/2014 | 2.75 | 4156.3 | 820.6 | 3335.7 | 116% | 111% |
| S_HS-07 | Center D | -9.5 | 1867.5 | 2493.7 | 2894.0 | 9/22/2014 | 17.84 | 9/23/2014 | 6.65 | 4097.5 | 1007.8 | 3089.7 | 124% | 126% |
| S_HS-08 | Center D | -7.7 | 1787.5 | 2595.0 | 2707.0 | 9/22/2014 | 16.29 | 9/23/2014 | 7.74 | 3823.8 | 963.5 | 2860.3 | 110% | 111% |

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Michael J. Chow
Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

February 06, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 2S Surcharge Review
SA-6 North
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of February 06, 2015 AMEC settlement and piezometer monitoring data for Area 2S is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated between January 12-29, 2015 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken at corresponding dates, between January 14-30, 2015. Calculated post-surcharge effective stresses are presented in Table 1. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 2S monitoring locations have met the surcharge program goal as of 01/30/2015.

Very truly yours,
**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

Table 1. MRCE SA-6 Surcharge Monitoring Review for Area 2S

| Settlement Monitoring Point | Layer | Existing EL (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| S_FS-03 | Center O | -3.3 | 1332.5 | 2208.4 | 1/14/2015 | 1/12/2015 | 19.7 | 9.9 | 3798.8 | 823.7 | 2975.1 | 135% | - |
| | Top D | -5.8 | 1525.0 | 2291.7 | | | 19.7 | 13.0 | 3991.3 | 1172.5 | 2818.8 | 123% | - |
| | Center D | -7.0 | 1716.3 | 2342.5 | | | 19.7 | 13.4 | 4182.6 | 1273.6 | 2909.0 | 124% | 145% |
| | Bottom D | -8.3 | 1907.5 | 2393.4 | | | 19.7 | 6.5 | 4373.8 | 926.0 | 3447.7 | 144% | - |
| S_FS-04 | Center O | -1.5 | 1204.5 | 2223.3 | 1/23/2015 | 1/18/2015 | 19.8 | 7.6 | 3683.3 | 566.0 | 3117.3 | 140% | - |
| | Top D | -4.5 | 1353.0 | 2287.6 | | | 19.8 | 12.4 | 3831.8 | 1050.2 | 2781.6 | 122% | - |
| | Center D | -6.2 | 1620.8 | 2358.7 | | | 19.8 | 13.0 | 4099.6 | 1196.8 | 2902.7 | 123% | 134% |
| | Bottom D | -7.7 | 1888.5 | 2429.9 | | | 19.8 | 10.6 | 4367.3 | 1143.8 | 3223.5 | 133% | - |
| | RC | -46.5 | 6613.5 | 4771.3 | | | 19.8 | 3.9 | 9092.3 | 3147.5 | 5944.8 | 125% | - |
| S_FS-05 | Center O | -0.6 | 1185.0 | 1696.9 | 1/30/2015 | 1/29/2015 | 14.5 | 5.9 | 2992.5 | 406.8 | 2585.7 | 152% | - |
| | Top D | -3.6 | 1350.0 | 1768.3 | | | 14.5 | 8.1 | 3157.5 | 730.1 | 2427.4 | 137% | - |
| | Center D | -5.1 | 1617.8 | 1839.5 | | | 14.5 | 20.3 | 3425.3 | 1583.1 | 1842.2 | 100% | 115% |
| | Bottom D | -6.6 | 1885.5 | 1910.7 | | | 14.5 | 9.8 | 3693.0 | 1022.7 | 2670.3 | 140% | - |
| S_HS-09 | Center O | -4.0 | 1272.5 | 2097.7 | 1/14/2015 | 1/12/2015 | 18.2 | 9.1 | 3547.5 | 818.7 | 2728.8 | 130% | - |
| | Center D | -8.0 | 1656.3 | 2231.9 | | | 18.2 | 6.4 | 3931.3 | 896.7 | 3034.6 | 136% | 156% |
| S_HS-10 | Center O | -2.1 | 1831.3 | 2384.9 | 1/14/2015 | 1/12/2015 | 12.6 | 6.6 | 3406.3 | 545.4 | 2860.9 | 120% | - |
| | Center D | -4.4 | 2088.8 | 2478.6 | | | 12.6 | 10.2 | 3663.8 | 912.3 | 2751.5 | 111% | 131% |
| S_HS-11 | Center O | -5.2 | 1660.0 | 2218.6 | 1/14/2015 | 1/12/2015 | 12.8 | 9.0 | 3253.8 | 887.3 | 2366.4 | 107% | - |
| | Center D | -7.5 | 1986.3 | 2342.0 | | | 12.8 | 7.4 | 3580.1 | 927.9 | 2652.2 | 113% | 132% |
| | RC | -50.2 | 7257.5 | 4930.1 | | | 12.8 | 3.8 | 8851.3 | 3372.7 | 5478.5 | 111% | - |
| S_HS-12 | Center O | -3.9 | 1485.0 | 2350.9 | 1/14/2015 | 1/12/2015 | 15.9 | 10.1 | 3477.5 | 871.7 | 2605.8 | 111% | - |
| | Center D | -7.9 | 1875.3 | 2482.1 | | | 15.9 | 9.4 | 3867.8 | 1076.4 | 2791.4 | 112% | 130% |
| | RC | -52.4 | 7238.0 | 5077.5 | | | 15.9 | 1.8 | 9230.5 | 3382.1 | 5848.4 | 115% | - |
| S_HS-13 | Center O | -2.0 | 1261.5 | 1962.8 | 1/30/2015 | 1/292015 | 16.0 | 17.0 | 3255.3 | 1183.7 | 2071.5 | 106% | - |
| | Center D | -5.2 | 1664.0 | 2100.1 | | | 16.0 | 14.9 | 3657.8 | 1253.6 | 2404.1 | 114% | 129% |
| S_HS-14 | Center O | -2.0 | 1365.0 | 2023.3 | 1/14/2015 | 1/12/2015 | 17.6 | 10.6 | 3563.8 | 783.7 | 2780.0 | 137% | - |
| | Center D | -6.3 | 1691.5 | 2137.6 | | | 17.6 | 10.4 | 3890.3 | 1039.6 | 2850.7 | 133% | 148% |
| S_HS-15 | Center O | -2.8 | 1858.8 | 2539.5 | 1/14/2015 | 1/12/2015 | 16.6 | 11.5 | 3928.8 | 889.8 | 3039.0 | 120% | - |
| | Center D | -6.8 | 2111.9 | 2636.6 | | | 4181.9 | 964.7 | 3217.2 | 122% | 3217.2 | 122% | 140% |

"Note that the Amec calculations referenced by MRCE were subsequently updated. Please refer to Table 2S-1 for the final values used. The correction does not impact the conclusion."

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

April 24, 2015

AMEC Environment & Infrastructure
511 Congress Street
Portland Me 04101

Attention: Mr. Geoff Shallard

Re: Area 3S Surcharge Review
SA-6 South
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

The Mueser Rutledge Consulting Engineers (MRCE) review of March 30, 2015 AMEC settlement and piezometer monitoring data for Area 3S is summarized below:

AMEC indicated from borings and sampling the Vibrating Wire Piezometers (VWP) were set at the center of the compressible clay layer, which provides the most conservative pore water pressure reading for the effective stress evaluation. All the stress calculations are at the center of the compressible layers.

MRCE used latest measured elevation head dated between March 24-13, 2015 from "Vibrating Wire Piezometer – Data Report" to calculate the post-surcharge pore water pressures. Post-surcharge total stresses were calculated based on the fill thickness measurements from the "Settlement Platform – Data Report" taken on March 19, 2015. Calculated post-surcharge effective stresses are presented in Table 1. MRCE compared the calculated post-surcharge effective stresses with the "Final Post-Development Conditions" effective stress estimates provided by AMEC. The defined goal of surcharge program was to achieve an effective stress greater than the "Final Post-Development Conditions."

This review finds all Area 3S monitoring locations have met the surcharge program goal as of 03/30/2015.

Very truly yours,

**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, P.E.

MP:F:\111\11173\2014 Surcharge Removal Review\SA-6_Area 3S\MRCE Review-Area 3S-April15.docx

Table 1. MRCE SA-6 South Surcharge Monitoring Review for Area 3S (April 2015)

| Settlement Monitoring Point | Layer | Existing EL (ft) | Pre-Surcharge Conditions | Proposed Final Development Conditions | Date of Recording used in calculations | | Fill Thickness (ft) | Elevation Head (ft) | Post-Surcharge Conditions | | | MRCE | AMEC |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Total Stress (psf) | Effective Stress (psf) | Fill Thickness | VWP Elevation | | | Total Stress (psf) | Pore Water Pressure (psf) | Effective Stress (psf) | % Completion | % Completion |
| S_FS-06 | Top D | -2.7 | 1365.0 | 2031.3 | 3/19/2015 | 3/24/2015 | 14.3 | 6.6 | 3148.8 | 574.1 | 2574.7 | 127% | - |
| | Center D | -3.9 | 1620.0 | 2099.1 | | | 14.3 | 7.2 | 3403.8 | 693.3 | 2710.5 | 129% | 127% |
| | Bottom D | -5.2 | 1875.0 | 2166.9 | | | 14.3 | 9.6 | 3658.8 | 919.8 | 2739.0 | 126% | - |
| S_FS-07 | Center O | -0.8 | 1234.0 | 2256.5 | 3/19/2015 | 3/24/2015 | 16.9 | 4.8 | 3346.5 | 348.9 | 2997.6 | 133% | - |
| | Top D | -3.0 | 1388.0 | 2323.2 | | | 16.9 | 5.2 | 3500.5 | 510.7 | 2989.8 | 129% | - |
| | Center D | -4.3 | 1587.8 | 2376.3 | | | 16.9 | 11.8 | 3700.3 | 999.5 | 2700.8 | 114% | 113% |
| | Bottom D | -5.5 | 1787.5 | 2429.4 | | | 16.9 | 6.9 | 3900.0 | 775.1 | 3124.9 | 129% | - |
| | RC | -34.3 | 5220.0 | 4145.9 | | | 16.9 | 3.4 | 7332.5 | 2352.4 | 4980.1 | 120% | - |
| S_HS-16 | Center O | -0.6 | 1222.5 | 2420.6 | 3/19/2015 | 3/24/2015 | 18.0 | 5.3 | 3472.5 | 368.2 | 3104.3 | 128% | - |
| | Center D | -4.1 | 1551.5 | 2521.8 | | | 18.0 | 14.7 | 3801.5 | 1173.1 | 2628.4 | 104% | 104% |
| S_HS-17 | Center D | -3.8 | 1460.0 | 1750.9 | 3/19/2015 | 3/24/2015 | 10.3 | 7.4 | 2743.8 | 697.6 | 2046.1 | 117% | 117% |
| S_HS-18 | Center D | -2.5 | 1406.0 | 969.9 | 3/19/2015 | 3/24/2015 | 3.5 | 3.6 | 1841.0 | 382.5 | 1458.5 | 150% | 150% |
| S_HS-19 | Center D | -0.6 | 1207.5 | 844.5 | 3/19/2015 | 3/24/2015 | 3.0 | 4.9 | 1578.8 | 345.1 | 1233.7 | 146% | 143% |
| S_HS-20 | Center O | -1.2 | 1209.5 | 2392.7 | 3/19/2015 | 3/24/2015 | 15.1 | 5.3 | 3093.3 | 403.7 | 2689.5 | 112% | - |
| | Center D | -4.4 | 1494.3 | 2484.0 | | 3/13/2015 | 15.1 | 9.7 | 3378.0 | 878.6 | 2499.4 | 101% | 101% |
| S_HS-21 | Center D | -4.3 | 1581.5 | 1503.7 | 3/19/2015 | 3/24/2015 | 6.1 | 1.6 | 2339.0 | 367.5 | 1971.5 | 131% | 132% |
| S_HS-22 | Center D | -2.6 | 1436.8 | 966.3 | 3/19/2015 | 3/24/2015 | 1.7 | 4.6 | 1651.8 | 450.5 | 1201.2 | 124% | 124% |

Mueser Rutledge
Consulting Engineers
14 Penn Plaza · 225 West 34th Street · New York, NY 10122
Tel: (917) 339-9300 · Fax: (917) 339-9400
www.mrce.com

David M. Cacoilo
Peter W. Deming
Roderic A. Ellman, Jr.
Francis J. Arland
David R. Good
Walter E. Kaeck
*Partners*

Tony D. Canale
Jan Cermak
Sitotaw Y. Fantaye
*Associate Partners*

Alfred H. Brand
James L. Kaufman
Hugh S. Lacy
Joel Moskowitz
George J. Tamaro
Elmer A. Richards
John W. Fowler
*Consultants*

Domenic D'Argenzio
Robert K. Radske
Ketan H. Trivedi
Hiren J. Shah
Alice Arana
Joel L. Volterra
Sissy Nikolaou
Anthony DeVito
Frederick C. Rhyner
*Senior Associates*

Douglas W. Christie
Gregg V. Piazza
Pablo V. Lopez
Steven R. Lowe
James M. Tantalla
Andrew R. Tognon
T. C. Michael Law
Andrew Pontecorvo
Renzo D. Verastegui
Alex Krutovskiy
Srinivas Yenamandra
*Associates*

Joseph N. Courtade
*Director of Finance and Administration*

Martha J. Huguet
*Director of Marketing*

September 29, 2015

AMEC Environmental & Infrastructure
511 Congress Street
Portland, ME 04101

Attn: Mr. Samuel G. Shallard
Re: DC 03-04-15
Area 3S Surcharge Pile Geometry on East End
Jersey City, NJ
MRCE File 11173

Dear Mr. Shallard:

This letter is in response to DC-03-04-15 "3S Surcharge Pile Geometry on East End," which requests change of the surcharge program at Area 3S to eliminate surcharge pre-load of a small area at the east end of the fill along the west side of Route 440.The April 24, 2015 MRCE letter summarized the settlement and piezometer monitoring data and confirmed that all monitoring locations in Area 3S satisfied the surcharge program goals. However, MRCE was not aware of the request of DC-03-04-15 at that review.

AMEC suggested that truncating the eastern tip of the wedge shaped surcharge fill will not significantly affect the goals of the Remedy/Surcharge program since the change in grade is from 0 – 5 ft. MRCE agrees with AMEC that since the increase in final grade is small, surcharging will have no significant affect. MRCE also reviewed available geotechnical data for the area in question, and finds that the compressible strata is pre-loaded such that no settlement will occur.

**Examining Pre-Consolidation Stress**

MRCE reviewed the soil profile closest to the "Deferred Area" and laboratory testing for compressible Stratum D. Boring location plan and summary of consolidation tests for Stratum D are attached (see Drawing B-1, Figure S-1, Plate 13 & Plate 18). The pre-consolidation stress (P'c) of the compressible layer Stratum D was tested for design of the Study Area 7 remediation. This test data was used to compute the pre-consolidation stress using two methods. The first method calculated the average P'c from the laboratory consolidation tests, resulting in P'c = 1930 psf. The second method calculated the effective overburden pressure at midpoint of Stratum D and multiplied it by the average OCR (overconsolidation ratio) defined by consolidation testing. With the average OCR = 2.23 and the average effective overburden stress = 1064 psf, the resulting average P'c = 2372 psf.

(see Appendix A). Settlement would only occur at the compressible layer if the effective stress due to filling exceeds 1930 to 2372 psf.

**Estimated Stress at Final Conditions**

Based on DC-03-04-15, the final grade will increase by 0 to 0.5 ft. The additional soil placed on top of the 12 ft wide area ranges from a height of 0 to 3 ft. Assuming an average height of the added soil as 1.5 ft and the maximum increase of grade, the final effective stress at the midpoint of Stratum D = 1314 psf, which is less than the lower bound of P'c = 1930 psf. (see Appendix A)

Since the effective vertical stress due to the final grade including planned added soil is less than the P'c of Stratum D, no settlement is expected. This technical review supports the AMEC evaluation that surcharging is not needed in the area addressed by DC-03-04-15.

Very truly yours,
**MUESER RUTLEDGE CONSULTING ENGINEERS**

By: _____
Peter W. Deming, NJ PE # 24GE04652200


**Attachments**

| | |
|---|---|
| Drawing B-1 | Boring Location Plan |
| Figure S-1 | Soil Profile |
| Plate 18 | Consolidation Test Boring SB-210D |
| Plate 13 | Consolidation Test Boring SB-211D |

**Appendices**

| | |
|---|---|
| Appendix A | Calculations of Stresses |

# ATTACHMENTS




GRAPHIC SCALE

100' 50' 0 100' 200'

## LEGEND:

- – Geotechnical borings performed by CT&E under the inspection of MRCE in 1997.
- – Environmental borings performed by CT&E under the inspection of Brown and Root.
- – Nested monitoring wells performed by CT&E under the inspection of Parsons.
- – SB-100 Series: Shallow COPR characterization borings performed by B&B under the inspection of MRCE in 2003.
- – GEO Series: Geotechnical water borings performed by CMI under the inspection of MRCE in 2003.
- – SB-200 Series: Perimeter geotechnical borings performed by B&B under the inspection of MRCE in 2003.
- – SB-300 Series: Phase 2 Perimeter geotechnical borings performed by B&B under the inspection of MRCE in 2004.
- – MW Series: Shallow monitoring wells performed by CMI under the inspection of MRCE in 2003.
- – CPT Probes performed by Furgo Geosciences under the inspection of Parsons and MRCE in 2003.
- – SB-400 Series: Phase 2 geotechnical borings performed by B&B under the inspection of MRCE in 2004.
- – Test pits performed under the inspection of MRCE in 1997.
- – Test pits performed by Conti under the inspection of MRCE in 2004.

## NOTES:

1. See drawing K-1 for section location.
2. See drawing T-2 for general strata descriptions, notes and legend.

THIS DRAWING, THE PROPERTY OF HONEYWELL, IS FURNISHED SUBJECT TO RETURN ON DEMAND AND THE CONDITION THAT THE INFORMATION AND TECHNOLOGY EMBODIED HEREIN SHALL NOT BE DISCLOSED OR USED AND THE DRAWING SHALL NOT BE REPRODUCED OR COPIED IN WHOLE OR IN PART EXCEPT AS PREVIOUSLY AUTHORIZED IN WRITING. ANY PERSON WHO MAY RECEIVE OR OBSERVE THIS DESIGN WILL BE HELD STRICTLY LIABLE FOR ANY VIOLATION WHETHER WILLFUL OR NEGLIGENT.

| REV. | DATE | BY | DESCRIPTION |
|---|---|---|---|
| 1 | 7/9/04 | | PHASE 2 SUBSURFACE INVESTIGATION UPDATE |

STUDY AREA 7

JERSEY CITY NEW JERSEY

**Honeywell**

101 COLUMBIA ROAD, MORRISTOWN, NEW JERSEY 07962

PROJECT NO. 35037

MUESER RUTLEDGE CONSULTING ENGINEERS

14 PENN PLAZA – 225 W. 34TH STREET, NEW YORK, NY 10122

| SCALE | MADE BY | DATE | FILE NO. |
|---|---|---|---|
| GRAPHIC | B.B. | 2/18/04 | 10210 |
| | CHK'D BY K.R. | DATE 7/8/04 | DRAWING NO. |

BORING LOCATION PLAN

B-1

MUESER RUTLEDGE CONSULTING ENGINEERS

SHEET ____ OF ____

FILE 11173


MADE BY APS DATE 9/28/15

PROJECT CHROMIUM REMEDY SA-6


CHECKED BY ____ DATE ____

SUBJECT SOIL PROFILE

FIGURE S-1




(D) Compressible Layer








PLATE NO. 18

| CURVE NO. | INCREMENT FROM (TSF) | INCREMENT TO (TSF) |
|---|---|---|
| ① | 0.18 | 0.37 |
| ② | 0.73 | 1.46 |
| ③ | 11.69 | 23.39 |

SPECIMEN DESCRIPTION: SOFT BLACK ORGANIC SILTY CLAY, TRACE FINE SAND, FINE SAND POCKETS (OL)

STRATUM D

**PROPERTIES OF PLASTICITY LIMIT SPECIMEN**

UNIFIED SOILS CLASSIFICATION - OL
LIQUID LIMIT, $w_L$ = 36
PLASTICITY LIMIT, $w_p$ = 22
PLASTICITY INDEX, $I_p$ = 14
NATURAL WATER CONT., $\%_w$ = 42.9
LIQUIDITY INDEX, $(w-w_p)/I_p$ = 1.5
SPECIFIC GRAVITY, $G_s$ = 2.61

**PROPERTIES OF CONSOLIDATION SPECIMEN**

ELEVATION OF SPECIMEN = -3.2
DEPTH OF SPECIMEN (FT) = 16.0
DIAMETER OF SPECIMEN (IN) = 2.5
INITIAL THICKNESS OF SPECIMEN (IN) = 1.0045
INITIAL WATER CONTENT, % = 38.9
FINAL WATER CONTENT, % = 27.1
INITIAL DEGREE OF SATURATION, % = 91.8
FINAL DEGREE OF SATURATION, % = 92.8

— — — — INITIAL VOID RATIO, $e_o$ = 1.107
- - - - - - - FINAL VOID RATIO, $e_f$ = 0.761
ESTIMATED PRECONSOLIDATION STRESS (TSF), $P_c$ = 0.53
EXISTING OVERBURDEN STRESS (TSF), $P_o$ = 0.347
COMPRESSION INDEX, $C_c$ = 0.292
SWELLING INDEX, $C_s$ =0.06 REBOUND FROM e = 0.486

**STUDY AREA 7**

JERSEY CITY NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
225 WEST 34TH STREET, NEW YORK, N.Y. 10122


MADE BY. BEE/MM DATE: 01-22-04
CHKD BY. WJP DATE: 02-02-04

FILE NO. 10028

CONSOLIDATION TEST
BORING 120-SB-210D SAMPLE 1U

PLATE NO. 18

MRCE Form CONSOL-1








PLATE NO. 13

| CURVE NO. | INCREMENT FROM (TSF) | INCREMENT TO (TSF) |
|---|---|---|
| ① | 0.36 | 0.73 |
| ② | 1.46 | 2.91 |
| ③ | 2.91 | 5.82 |

SPECIMEN DESCRIPTION: STIFF BROWN PEAT (Pt)

STRATUM D

**PROPERTIES OF PLASTICITY LIMIT SPECIMEN**

UNIFIED SOILS CLASSIFICATION - Pt
LIQIUD LIMIT, $w_L$ = 541
PLASTICITY LIMIT, $w_P$ = 379
PLASTICITY INDEX, $I_P$ = 161
NATURAL WATER CONT., $\%_w$ = 229 6
LIQUIDITY INDEX, $(w-w_P)/I_P$ = -0.93
SPECIFIC GRAVITY, $G_s$ = 1.78

**PROPERTIES OF CONSOLIDATION SPECIMEN**

ELEVATION OF SPECIMEN = -5.0
DEPTH OF SPECIMEN (FT) = 19.5
DIAMETER OF SPECIMEN (IN) = 150
INITIAL THICKNESS OF SPECIMEN (IN) = 0.9946
INITIAL WATER CONTENT, % = 289.0
FINAL WATER CONTENT, % = 212.4
INITIAL DEGREE OF SATURATION, % = 91.8
FINAL DEGREE OF SATURATION, % = 94.7

INITIAL VOID RATIO, $e_o$ = 5.597
FINAL VOID RATIO, $e_f$ = 3.989
ESTIMATED PRECONSOLIDATION STRESS (TSF), $P_c$ = 1.4
EXISTING OVERBURDEN STRESS (TSF), $P_o$ = 0.52
COMPRESSION INDEX, $C_c$ = 3.62
SWELLING INDEX, $C_s$ = 0 58, REBOUND FROM e = 2.242

**STUDY AREA 7**

JERSEY CITY NEW JERSEY

MUESER RUTLEDGE CONSULTING ENGINEERS
225 WEST 34TH STREET, NEW YORK, N.Y. 10122

MADE BY: BEE DATE: 01-06-04
CHKD BY: WJP DATE: 01-27-04

FILE NO. 10028

**CONSOLIDATION TEST**
BORING 115-SB-211D SAMPLE 1U

PLATE NO. 13

MRCE Form CONSOL-1

# APPENDIX A

**MUESER RUTLEDGE CONSULTING ENGINEERS**

FILE 11173

MADE BY APS DATE 9/28/15

PROJECT CHROMIUM REMEDY SA-6

CHECKED BY ____ DATE ____

SUBJECT CALCULATION OF STRESSES

## APPENDIX A

① Using average Pc from consolidation tests:

Pc (SB-210D) = 0.53 tsf = 1060 psf

Pc (SB-211D) = 1.4 tsf = 2800 psf

Pc (average) = 1930 psf

② Using OCR from consolidation tests:

At ELEV. -2.5 ⇒ $\sigma'_v$ = 120pcf x 13.5 ft − 62.4pcf x 10 ft

= 1064 psf

OCR(SB-210D) = 1.77

OCR(SB-211D) = 2.69

OCR(average) = 2.23

1064 psf x 2.23 = 2372 psf

AVERAGE ① & ② = 2151 psf

③ Stress at Final Condition




Final Effective overburden stress:

$\sigma'_{vf}$ = 1064 + (1.5+0.5) x 125pcf


= 1314 psf < 1930 psf

Added soil avg height = 1.5'

Max. increase in grade = 0.5'

**ATTACHMENT D**
**SA-6 SOUTH CAP SUBGRADE APPROVAL**

**ATTACHMENT D-1**
**CONSTRUCTION CONTROL GRID**




Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013800

SA-6 SOUTH CONSTRUCTION CONTROL GRID
FIGURE 1 OF 2
Pr□□□r 3480-13-0377
F□□r□ 1.1

Pr□□□r d/D□□□ RJR 07/02/15
C:□□□□ d/D□□□ TDD 07/02/15

Z:\Projects\HONEYWELL\JERSEY CITY\Cad Design - SA6 - 2301\CAD\SA6S\Xref\SA-6 South Construction Control Grid.dwg Thu, 02 Jul 2015 - 10:55am Inger.Hojer




Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28013400

SA-6 SOUTH CONSTRUCTION CONTROL GRID
FIGURE 2 OF 2
Pr□□□3480-13-0377
F□□r□ 1:2

Pr□□r d/D□□□RJR 07/02/15
C:□□□□d/D□□□TDD 07/02/15

Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-CSS\CAD\SA6S\Xref\SA-6 South Construction Control Grid.dwg Thu, 02 Jul 2015 - 10:59am ingler.rispler

**ATTACHMENT D-2**
**SA-6 SOUTH SUBGRADE GRID POINTS**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Cap Subgrade: Grid Points (Table 1.0)

| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
|---|---|---|---|---|---|---|---|---|
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2 | 685518.44 | 601481.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 3 | 685543.44 | 601481.51 | 15.3 | GRID | 7/2/2015 | 15.3 | 0.0 | Point surveyed within Tolerance |
| 4 | 685493.44 | 601506.51 | 14.2 | GRID | 7/2/2015 | 14.2 | 0.0 | Point surveyed within Tolerance |
| 6 | 685543.44 | 601506.51 | 16.6 | GRID | 7/2/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 7 | 685568.44 | 601506.51 | 17.0 | GRID | 7/2/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |
| 8 | 685468.44 | 601531.51 | 13.1 | GRID | 7/2/2015 | 13.1 | 0.0 | Point surveyed within Tolerance |
| 9 | 685493.44 | 601531.51 | 13.7 | GRID | 7/2/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 10 | 685543.44 | 601531.51 | 14.8 | GRID | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 11 | 685568.44 | 601531.51 | 15.0 | GRID | 7/2/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 12 | 685593.44 | 601531.51 | 18.1 | GRID | 7/2/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 14 | 685468.44 | 601556.51 | 13.9 | GRID | 7/2/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 15 | 685493.44 | 601556.51 | 15.9 | GRID | 7/2/2015 | 15.8 | -0.1 | Point surveyed within Tolerance |
| 16 | 685518.44 | 601556.51 | 16.7 | GRID | 7/2/2015 | 16.8 | 0.1 | Point surveyed within Tolerance |
| 17 | 685543.44 | 601556.51 | 17.0 | GRID | 7/2/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 18 | 685568.44 | 601556.51 | 14.1 | GRID | 7/2/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 19 | 685593.44 | 601556.51 | 17.4 | GRID | 7/2/2015 | 17.5 | 0.1 | Point surveyed within Tolerance |
| 20 | 685443.44 | 601581.51 | 13.3 | GRID | 7/2/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 21 | 685468.44 | 601581.51 | 14.4 | GRID | 7/2/2015 | 14.4 | 0.0 | Point surveyed within Tolerance |
| 22 | 685493.44 | 601581.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 23 | 685518.44 | 601581.51 | 16.6 | GRID | 7/2/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 24 | 685543.44 | 601581.51 | 17.5 | GRID | 7/2/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 25 | 685568.44 | 601581.51 | 17.0 | GRID | 7/2/2015 | 17.1 | 0.1 | Point surveyed within Tolerance |
| 26 | 685418.44 | 601606.51 | 11.9 | GRID | 7/2/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 27 | 685443.44 | 601606.51 | 13.8 | GRID | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 29 | 685493.44 | 601606.51 | 15.3 | GRID | 7/2/2015 | 15.3 | 0.0 | Point surveyed within Tolerance |
| 30 | 685518.44 | 601606.51 | 16.2 | GRID | 7/2/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 31 | 685543.44 | 601606.51 | 16.7 | GRID | 7/2/2015 | 16.8 | 0.1 | Point surveyed within Tolerance |
| 32 | 685393.44 | 601631.51 | 11.4 | GRID | 7/2/2015 | 11.5 | 0.1 | Point surveyed within Tolerance |
| 33 | 685418.44 | 601631.51 | 13.2 | GRID | 7/2/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 34 | 685443.44 | 601631.51 | 13.8 | GRID | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 35 | 685468.44 | 601631.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 36 | 685493.44 | 601631.51 | 14.8 | GRID | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 37 | 685518.44 | 601631.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 38 | 685543.44 | 601631.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 39 | 685393.44 | 601656.51 | 12.6 | GRID | 7/2/2015 | 12.7 | 0.1 | Point surveyed within Tolerance |
| 40 | 685443.44 | 601656.51 | 13.7 | GRID | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 41 | 685468.44 | 601656.51 | 15.6 | GRID | 7/2/2015 | 15.7 | 0.1 | Point surveyed within Tolerance |
| 42 | 685493.44 | 601656.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 43 | 685518.44 | 601656.51 | 16.6 | GRID | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 44 | 685368.44 | 601681.51 | 11.6 | GRID | 7/2/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 45 | 685393.44 | 601681.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 46 | 685443.44 | 601681.51 | 13.7 | GRID | 7/2/2015 | 13.6 | -0.1 | Point surveyed within Tolerance |
| 47 | 685468.44 | 601681.51 | 15.5 | GRID | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 48 | 685493.44 | 601681.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 49 | 685343.44 | 601706.51 | 11.0 | GRID | 7/2/2015 | 10.9 | -0.1 | Point surveyed within Tolerance |
| 50 | 685393.44 | 601706.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 51 | 685443.44 | 601706.51 | 13.6 | GRID | 7/2/2015 | 13.5 | -0.1 | Point surveyed within Tolerance |
| 52 | 685468.44 | 601706.51 | 15.4 | GRID | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 53 | 685493.44 | 601706.51 | 14.3 | GRID | 7/2/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 54 | 685318.44 | 601731.51 | 10.7 | GRID | 7/2/2015 | 10.6 | -0.1 | Point surveyed within Tolerance |
| 55 | 685368.44 | 601731.51 | 16.2 | GRID | 7/2/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 56 | 685393.44 | 601731.51 | 16.3 | GRID | 7/2/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 57 | 685443.44 | 601731.51 | 13.5 | GRID | 7/2/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 58 | 685343.44 | 601756.51 | 16.6 | GRID | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 59 | 685368.44 | 601756.51 | 16.3 | GRID | 7/2/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 61 | 685443.44 | 601756.51 | 13.5 | GRID | 7/2/2015 | 13.6 | 0.1 | Point surveyed within Tolerance |
| 62 | 685293.44 | 601781.51 | 10.5 | GRID | 7/2/2015 | 10.4 | -0.1 | Point surveyed within Tolerance |
| 63 | 685318.44 | 601781.51 | 17.4 | GRID | 7/2/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 64 | 685343.44 | 601781.51 | 16.9 | GRID | 7/2/2015 | 16.9 | 0.0 | Point surveyed within Tolerance |
| 65 | 685368.44 | 601781.51 | 16.5 | GRID | 7/2/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 66 | 685393.44 | 601781.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 67 | 685418.44 | 601781.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 69 | 685268.44 | 601806.51 | 11.0 | GRID | 7/2/2015 | 11.0 | 0.0 | Point surveyed within Tolerance |
| 70 | 685318.44 | 601806.51 | 18.1 | GRID | 7/2/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 71 | 685343.44 | 601806.51 | 17.7 | GRID | 7/2/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 72 | 685368.44 | 601806.51 | 17.1 | GRID | 7/2/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 73 | 685393.44 | 601806.51 | 16.7 | GRID | 7/2/2015 | 16.6 | -0.1 | Point surveyed within Tolerance |
| 74 | 685418.44 | 601806.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 75 | 685243.44 | 601831.51 | 12.7 | GRID | 7/2/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 77 | 685318.44 | 601831.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 78 | 685343.44 | 601831.51 | 18.3 | GRID | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 79 | 685368.44 | 601831.51 | 17.7 | GRID | 7/2/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 80 | 685393.44 | 601831.51 | 17.2 | GRID | 7/2/2015 | 17.3 | 0.1 | Point surveyed within Tolerance |
| 81 | 685243.44 | 601856.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 82 | 685268.44 | 601856.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 83 | 685293.44 | 601856.51 | 15.7 | GRID | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 85 | 685368.44 | 601856.51 | 18.0 | GRID | 7/2/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 86 | 685218.44 | 601881.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 87 | 685243.44 | 601881.51 | 16.4 | GRID | 7/2/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 88 | 685268.44 | 601881.51 | 18.7 | GRID | 7/2/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 89 | 685293.44 | 601881.51 | 18.6 | GRID | 7/2/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 90 | 685343.44 | 601881.51 | 15.2 | GRID | 7/2/2015 | 15.2 | 0.0 | Point surveyed within Tolerance |
| 91 | 685368.44 | 601881.51 | 11.8 | GRID | 7/2/2015 | 11.8 | 0.0 | Point surveyed within Tolerance |
| 92 | 685193.44 | 601906.51 | 15.5 | GRID | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 93 | 685218.44 | 601906.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 94 | 685243.44 | 601906.51 | 18.7 | GRID | 7/2/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 95 | 685268.44 | 601906.51 | 18.6 | GRID | 7/2/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 96 | 685293.44 | 601906.51 | 18.5 | GRID | 7/2/2015 | 18.4 | -0.1 | Point surveyed within Tolerance |
| 97 | 685318.44 | 601906.51 | 18.3 | GRID | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 99 | 685193.44 | 601931.51 | 15.7 | GRID | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 101 | 685243.44 | 601931.51 | 18.6 | GRID | 7/2/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 102 | 685268.44 | 601931.51 | 18.5 | GRID | 7/2/2015 | 18.4 | -0.1 | Point surveyed within Tolerance |
| 103 | 685293.44 | 601931.51 | 18.4 | GRID | 7/2/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 104 | 685168.44 | 601956.51 | 14.6 | GRID | 7/2/2015 | 14.6 | 0.0 | Point surveyed within Tolerance |
| 105 | 685193.44 | 601956.51 | 18.0 | GRID | 7/14/2015 | 18.1 | 0.1 | Point surveyed within Tolerance |
| 107 | 685243.44 | 601956.51 | 18.3 | GRID | 7/14/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 108 | 685268.44 | 601956.51 | 18.3 | GRID | 7/14/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 109 | 685293.44 | 601956.51 | 18.2 | GRID | 7/14/2015 | 18.3 | 0.1 | Point surveyed within Tolerance |
| 110 | 685143.44 | 601981.51 | 13.6 | GRID | 7/14/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 111 | 685168.44 | 601981.51 | 17.2 | GRID | 7/14/2015 | 17.3 | 0.1 | Point surveyed within Tolerance |
| 112 | 685193.44 | 601981.51 | 17.4 | GRID | 7/14/2015 | 17.5 | 0.1 | Point surveyed within Tolerance |
| 113 | 685218.44 | 601981.51 | 17.7 | GRID | 7/14/2015 | 17.8 | 0.1 | Point surveyed within Tolerance |
| 114 | 685243.44 | 601981.51 | 17.8 | GRID | 7/14/2015 | 17.9 | 0.1 | Point surveyed within Tolerance |
| 115 | 685268.44 | 601981.51 | 17.9 | GRID | 7/14/2015 | 18.0 | 0.1 | Point surveyed within Tolerance |
| 116 | 685118.44 | 602006.51 | 13.0 | GRID | 7/14/2015 | 13.1 | 0.1 | Point surveyed within Tolerance |
| 117 | 685168.44 | 602006.51 | 16.6 | GRID | 7/14/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 118 | 685193.44 | 602006.51 | 16.8 | GRID | 7/14/2015 | 16.9 | 0.1 | Point surveyed within Tolerance |
| 119 | 685218.44 | 602006.51 | 17.1 | GRID | 7/14/2015 | 17.2 | 0.1 | Point surveyed within Tolerance |
| 121 | 685268.44 | 602006.51 | 17.5 | GRID | 7/14/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 122 | 685118.44 | 602031.51 | 13.0 | GRID | 7/14/2015 | 13.1 | 0.1 | Point surveyed within Tolerance |
| 123 | 685143.44 | 602031.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 124 | 685168.44 | 602031.51 | 16.2 | GRID | 7/14/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 125 | 685193.44 | 602031.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 126 | 685218.44 | 602031.51 | 16.5 | GRID | 7/14/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 127 | 685118.44 | 602056.51 | 14.0 | GRID | 7/14/2015 | 13.9 | -0.1 | Point surveyed within Tolerance |
| 128 | 685143.44 | 602056.51 | 16.2 | GRID | 7/14/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 129 | 685168.44 | 602056.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 130 | 685193.44 | 602056.51 | 16.2 | GRID | 7/14/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 131 | 685218.44 | 602056.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 132 | 685068.44 | 602081.51 | 4.4 | GRID | 7/14/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 134 | 685143.44 | 602081.51 | 16.5 | GRID | 7/14/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 135 | 685168.44 | 602081.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 136 | 685193.44 | 602081.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 137 | 685218.44 | 602081.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 140 | 685093.44 | 602106.51 | 4.8 | GRID | 7/14/2015 | 4.9 | 0.1 | Point surveyed within Tolerance |
| 141 | 685118.44 | 602106.51 | 5.0 | GRID | 7/14/2015 | 5.1 | 0.1 | Point surveyed within Tolerance |
| 142 | 685168.44 | 602106.51 | 16.6 | GRID | 7/14/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 143 | 685193.44 | 602106.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 146 | 685143.44 | 602131.51 | 5.4 | GRID | 7/14/2015 | 5.5 | 0.1 | Point surveyed within Tolerance |
| 138 | 685043.44 | 602106.51 | 4.6 | GRID | 7/24/2015 | 4.5 | -0.1 | Point surveyed within Tolerance |
| 144 | 685068.44 | 602131.51 | 15.0 | GRID | 7/24/2015 | 15.0 | 0.0 | Point surveyed within Tolerance |
| 145 | 685118.44 | 602131.51 | 5.2 | GRID | 7/24/2015 | 5.1 | -0.1 | Point surveyed within Tolerance |
| 147 | 685043.44 | 602156.51 | 15.1 | GRID | 7/24/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 148 | 685093.44 | 602156.51 | 17.9 | GRID | 7/24/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 149 | 685143.44 | 602156.51 | 5.6 | GRID | 7/24/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 150 | 685168.44 | 602156.51 | 5.8 | GRID | 7/24/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 151 | 684993.44 | 602181.51 | 5.6 | GRID | 7/24/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 152 | 685018.44 | 602181.51 | 15.7 | GRID | 7/24/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 153 | 685043.44 | 602181.51 | 15.2 | GRID | 7/24/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 154 | 685068.44 | 602181.51 | 17.5 | GRID | 7/24/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 155 | 685093.44 | 602181.51 | 17.5 | GRID | 7/24/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 156 | 685118.44 | 602181.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 157 | 685143.44 | 602181.51 | 14.7 | GRID | 7/24/2015 | 14.7 | 0.0 | Point surveyed within Tolerance |
| 159 | 684968.44 | 602206.51 | 6.1 | GRID | 7/24/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 160 | 685018.44 | 602206.51 | 18.3 | GRID | 7/24/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 161 | 685068.44 | 602206.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 162 | 684993.44 | 602231.51 | 18.8 | GRID | 7/24/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 163 | 685018.44 | 602231.51 | 16.0 | GRID | 7/24/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 164 | 685068.44 | 602231.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 165 | 685093.44 | 602231.51 | 15.0 | GRID | 7/24/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 166 | 684968.44 | 602256.51 | 19.4 | GRID | 7/24/2015 | 19.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 167 | 684993.44 | 602256.51 | 19.1 | GRID | 7/24/2015 | 19.1 | 0.0 | Point surveyed within Tolerance |
| 168 | 685018.44 | 602256.51 | 16.3 | GRID | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 169 | 685043.44 | 602256.51 | 18.4 | GRID | 7/24/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 170 | 685068.44 | 602256.51 | 18.1 | GRID | 7/24/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 171 | 684918.44 | 602281.51 | 7.1 | GRID | 7/24/2015 | 7.2 | 0.1 | Point surveyed within Tolerance |
| 172 | 684968.44 | 602281.51 | 19.6 | GRID | 7/24/2015 | 19.6 | 0.0 | Point surveyed within Tolerance |
| 173 | 684993.44 | 602281.51 | 16.8 | GRID | 7/24/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 174 | 685018.44 | 602281.51 | 19.0 | GRID | 7/24/2015 | 19.0 | 0.0 | Point surveyed within Tolerance |
| 175 | 685043.44 | 602281.51 | 18.7 | GRID | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 176 | 685068.44 | 602281.51 | 18.4 | GRID | 7/24/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 178 | 684943.44 | 602306.51 | 20.2 | GRID | 7/24/2015 | 20.2 | 0.0 | Point surveyed within Tolerance |
| 179 | 684968.44 | 602306.51 | 19.9 | GRID | 7/24/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 180 | 684993.44 | 602306.51 | 17.1 | GRID | 7/24/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 181 | 685018.44 | 602306.51 | 19.3 | GRID | 7/24/2015 | 19.3 | 0.0 | Point surveyed within Tolerance |
| 182 | 685043.44 | 602306.51 | 16.4 | GRID | 7/24/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 183 | 684918.44 | 602331.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 184 | 684943.44 | 602331.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 185 | 684968.44 | 602331.51 | 17.6 | GRID | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 186 | 684993.44 | 602331.51 | 19.8 | GRID | 7/24/2015 | 19.8 | 0.0 | Point surveyed within Tolerance |
| 187 | 685018.44 | 602331.51 | 17.0 | GRID | 7/24/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |
| 188 | 684893.44 | 602356.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 189 | 684918.44 | 602356.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 190 | 684943.44 | 602356.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 191 | 684968.44 | 602356.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 192 | 684993.44 | 602356.51 | 17.5 | GRID | 7/24/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 193 | 684843.44 | 602381.51 | 8.7 | GRID | 7/24/2015 | 8.7 | 0.0 | Point surveyed within Tolerance |
| 194 | 684868.44 | 602381.51 | 17.4 | GRID | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 195 | 684893.44 | 602381.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 196 | 684918.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 197 | 684943.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 198 | 684968.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 199 | 684993.44 | 602381.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 200 | 684868.44 | 602406.51 | 17.0 | GRID | 7/24/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 201 | 684893.44 | 602406.51 | 17.3 | GRID | 7/24/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 202 | 684918.44 | 602406.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 203 | 684943.44 | 602406.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 204 | 684968.44 | 602406.51 | 17.8 | GRID | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 206 | 684843.44 | 602431.51 | 16.1 | GRID | 7/24/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 207 | 684868.44 | 602431.51 | 16.6 | GRID | 7/24/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 208 | 684893.44 | 602431.51 | 17.0 | GRID | 7/24/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 209 | 684918.44 | 602431.51 | 17.4 | GRID | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 210 | 684943.44 | 602431.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 214 | 684868.44 | 602456.51 | 16.3 | GRID | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 215 | 684893.44 | 602456.51 | 16.7 | GRID | 7/24/2015 | 16.7 | 0.0 | Point surveyed within Tolerance |
| 216 | 684918.44 | 602456.51 | 17.1 | GRID | 7/24/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 222 | 684893.44 | 602481.51 | 16.4 | GRID | 7/24/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 223 | 684918.44 | 602481.51 | 16.9 | GRID | 7/24/2015 | 16.8 | -0.1 | Point surveyed within Tolerance |
| 205 | 684818.44 | 602431.51 | 15.0 | GRID | 8/10/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 211 | 684793.44 | 602456.51 | 14.0 | GRID | 8/10/2015 | 14.0 | 0.0 | Point surveyed within Tolerance |
| 212 | 684818.44 | 602456.51 | 15.2 | GRID | 8/10/2015 | 15.2 | 0.0 | Point surveyed within Tolerance |
| 213 | 684843.44 | 602456.51 | 15.7 | GRID | 8/10/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 218 | 684793.44 | 602481.51 | 14.3 | GRID | 8/10/2015 | 14.2 | -0.1 | Point surveyed within Tolerance |
| 219 | 684818.44 | 602481.51 | 14.9 | GRID | 8/10/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 220 | 684843.44 | 602481.51 | 15.4 | GRID | 8/10/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 221 | 684868.44 | 602481.51 | 15.9 | GRID | 8/10/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 224 | 684768.44 | 602506.51 | 13.3 | GRID | 8/10/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 225 | 684793.44 | 602506.51 | 14.0 | GRID | 8/10/2015 | 14.0 | 0.0 | Point surveyed within Tolerance |
| 226 | 684818.44 | 602506.51 | 14.6 | GRID | 8/10/2015 | 14.5 | -0.1 | Point surveyed within Tolerance |
| 227 | 684843.44 | 602506.51 | 15.1 | GRID | 8/10/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 228 | 684868.44 | 602506.51 | 15.6 | GRID | 8/10/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 229 | 684893.44 | 602506.51 | 16.1 | GRID | 8/10/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 232 | 684793.44 | 602531.51 | 16.3 | GRID | 8/10/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 233 | 684818.44 | 602531.51 | 16.8 | GRID | 8/10/2015 | 16.7 | -0.1 | Point surveyed within Tolerance |
| 234 | 684843.44 | 602531.51 | 17.3 | GRID | 8/10/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 235 | 684868.44 | 602531.51 | 17.9 | GRID | 8/10/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 239 | 684843.44 | 602556.51 | 17.1 | GRID | 8/10/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 240 | 684868.44 | 602556.51 | 17.6 | GRID | 8/10/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 217 | 684768.44 | 602481.51 | 13.2 | GRID | 8/12/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 230 | 684743.44 | 602531.51 | 12.6 | GRID | 8/12/2015 | 12.6 | 0.0 | Point surveyed within Tolerance |
| 231 | 684768.44 | 602531.51 | 15.8 | GRID | 8/12/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 245 | 684793.44 | 602581.51 | 14.1 | GRID | 8/12/2015 | 14.1 | 0.0 | Point surveyed within Tolerance |
| 246 | 684818.44 | 602581.51 | 14.1 | GRID | 8/12/2015 | 14.1 | 0.0 | Point surveyed within Tolerance |
| 247 | 684843.44 | 602581.51 | 14.3 | GRID | 8/12/2015 | 14.4 | 0.1 | Point surveyed within Tolerance |
| 252 | 684818.44 | 602606.51 | 14.3 | GRID | 8/12/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 236 | 684718.44 | 602556.51 | 7.5 | GRID | 8/13/2015 | 7.4 | -0.1 | Point surveyed within Tolerance |
| 237 | 684743.44 | 602556.51 | 15.6 | GRID | 8/13/2015 | 15.7 | 0.1 | Point surveyed within Tolerance |
| 241 | 684693.44 | 602581.51 | 5.8 | GRID | 8/13/2015 | 5.8 | 0.0 | Point surveyed within Tolerance |
| 242 | 684718.44 | 602581.51 | 13.2 | GRID | 8/13/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 243 | 684743.44 | 602581.51 | 15.7 | GRID | 8/13/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 244 | 684768.44 | 602581.51 | 13.9 | GRID | 8/13/2015 | 13.8 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.6) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 249 | 684743.44 | 602606.51 | 16.5 | GRID | 8/13/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 250 | 684768.44 | 602606.51 | 16.0 | GRID | 8/13/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 251 | 684793.44 | 602606.51 | 14.5 | GRID | 8/13/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 255 | 684768.44 | 602631.51 | 17.0 | GRID | 8/13/2015 | 17.1 | 0.1 | Point surveyed within Tolerance |
| 256 | 684793.44 | 602631.51 | 16.3 | GRID | 8/13/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 257 | 684818.44 | 602631.51 | 16.2 | GRID | 8/13/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 261 | 684793.44 | 602656.51 | 14.5 | GRID | 8/13/2015 | 14.6 | 0.1 | Point surveyed within Tolerance |
| 248 | 684693.44 | 602606.51 | 5.2 | GRID | 9/4/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 253 | 684693.44 | 602631.51 | 5.5 | GRID | 9/4/2015 | 5.5 | 0.0 | Point surveyed within Tolerance |
| 254 | 684718.44 | 602631.51 | 5.8 | GRID | 9/4/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 259 | 684718.44 | 602656.51 | 6.1 | GRID | 9/4/2015 | 6.0 | -0.1 | Point surveyed within Tolerance |
| 260 | 684743.44 | 602656.51 | 6.4 | GRID | 9/4/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 263 | 684743.44 | 602681.51 | 6.7 | GRID | 9/4/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 264 | 684768.44 | 602681.51 | 7.0 | GRID | 9/4/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 265 | 684793.44 | 602681.51 | 7.4 | GRID | 9/4/2015 | 7.3 | -0.1 | Point surveyed within Tolerance |
| 2069 | 684743.44 | 602706.51 | 17.8 | GRID | 9/4/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 2070 | 684743.44 | 602731.51 | 15.4 | GRID | 9/4/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 2071 | 684718.44 | 602756.51 | 15.8 | GRID | 9/4/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 2072 | 684718.44 | 602706.51 | 18.0 | GRID | 9/4/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 2073 | 684693.44 | 602706.51 | 15.4 | GRID | 9/4/2015 | 15.3 | -0.1 | Point surveyed within Tolerance |
| 2074 | 684693.44 | 602731.51 | 18.4 | GRID | 9/4/2015 | 18.5 | 0.1 | Point surveyed within Tolerance |
| 2075 | 684693.44 | 602756.51 | 18.8 | GRID | 9/4/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 2076 | 684693.44 | 602781.51 | 19.2 | GRID | 9/4/2015 | 19.3 | 0.1 | Point surveyed within Tolerance |
| 2079 | 684668.44 | 602756.51 | 16.4 | GRID | 9/4/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 2080 | 684668.44 | 602731.51 | 16.0 | GRID | 9/4/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 2081 | 684668.44 | 602706.51 | 18.3 | GRID | 9/4/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 2082 | 684668.44 | 602681.51 | 17.9 | GRID | 9/4/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 2083 | 684668.44 | 602656.51 | 14.9 | GRID | 9/4/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 2084 | 684643.44 | 602706.51 | 18.6 | GRID | 9/4/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 2085 | 684643.44 | 602731.51 | 16.3 | GRID | 9/4/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 2086 | 684643.44 | 602756.51 | 16.8 | GRID | 9/4/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 2090 | 684618.44 | 602731.51 | 16.6 | GRID | 9/4/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 2101 | 684593.44 | 602706.51 | 6.8 | GRID | 9/4/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2077 | 684668.44 | 602806.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2078 | 684668.44 | 602781.51 | 17.1 | GRID | 9/9/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 2087 | 684643.44 | 602781.51 | 17.3 | GRID | 9/9/2015 | 17.2 | -0.1 | Point surveyed within Tolerance |
| 2088 | 684643.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2089 | 684643.44 | 602831.51 | 17.7 | GRID | 9/9/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 2091 | 684618.44 | 602756.51 | 17.1 | GRID | 9/9/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 2092 | 684618.44 | 602781.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.7) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2093 | 684618.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2094 | 684618.44 | 602831.51 | 17.7 | GRID | 9/9/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 2095 | 684618.44 | 602856.51 | 20.3 | GRID | 9/9/2015 | 20.3 | 0.0 | Point surveyed within Tolerance |
| 2096 | 684593.44 | 602881.51 | 19.6 | GRID | 9/9/2015 | 19.5 | -0.1 | Point surveyed within Tolerance |
| 2097 | 684593.44 | 602856.51 | 19.9 | GRID | 9/9/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 2098 | 684593.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 2099 | 684593.44 | 602781.51 | 17.5 | GRID | 9/9/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 2100 | 684593.44 | 602756.51 | 17.2 | GRID | 9/9/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 2102 | 684568.44 | 602731.51 | 7.4 | GRID | 9/9/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 2103 | 684568.44 | 602781.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2104 | 684568.44 | 602831.51 | 19.9 | GRID | 9/9/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 2105 | 684568.44 | 602856.51 | 19.4 | GRID | 9/9/2015 | 19.4 | 0.0 | Point surveyed within Tolerance |
| 2106 | 684568.44 | 602881.51 | 18.8 | GRID | 9/9/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 2111 | 684543.44 | 602856.51 | 18.7 | GRID | 9/9/2015 | 18.8 | 0.1 | Point surveyed within Tolerance |
| 2112 | 684543.44 | 602831.51 | 19.5 | GRID | 9/9/2015 | 19.5 | 0.0 | Point surveyed within Tolerance |
| 2113 | 684543.44 | 602806.51 | 19.6 | GRID | 9/9/2015 | 19.6 | 0.0 | Point surveyed within Tolerance |
| 2114 | 684518.44 | 602831.51 | 18.6 | GRID | 9/9/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 2115 | 684518.44 | 602856.51 | 18.1 | GRID | 9/9/2015 | 18.2 | 0.1 | Point surveyed within Tolerance |
| 2126 | 684493.44 | 602831.51 | 9.6 | GRID | 9/9/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 2109 | 684543.44 | 602931.51 | 13.9 | GRID | 9/16/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 2110 | 684543.44 | 602906.51 | 6.4 | GRID | 9/16/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |
| 2116 | 684518.44 | 602906.51 | 12.9 | GRID | 9/16/2015 | 13.0 | 0.1 | Point surveyed within Tolerance |
| 2132 | 684468.44 | 602856.51 | 5.9 | GRID | 9/16/2015 | 6.0 | 0.1 | Point surveyed within Tolerance |
| 2108 | 684543.44 | 602956.51 | 14.3 | GRID | 9/18/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 2117 | 684518.44 | 602931.51 | 13.7 | GRID | 9/18/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 2118 | 684518.44 | 602956.51 | 16.8 | GRID | 9/18/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 2119 | 684518.44 | 602981.51 | 15.9 | GRID | 9/18/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 2121 | 684493.44 | 603006.51 | 14.5 | GRID | 9/18/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 2122 | 684493.44 | 602981.51 | 14.9 | GRID | 9/18/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 2123 | 684493.44 | 602956.51 | 15.5 | GRID | 9/18/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 2124 | 684493.44 | 602931.51 | 16.6 | GRID | 9/18/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 2125 | 684493.44 | 602906.51 | 13.4 | GRID | 9/18/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 2127 | 684468.44 | 603031.51 | 13.1 | GRID | 9/18/2015 | 13.1 | 0.0 | Point surveyed within Tolerance |
| 2128 | 684468.44 | 603006.51 | 13.5 | GRID | 9/18/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 2129 | 684468.44 | 602981.51 | 13.9 | GRID | 9/18/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 2130 | 684468.44 | 602956.51 | 14.4 | GRID | 9/18/2015 | 14.5 | 0.1 | Point surveyed within Tolerance |
| 2131 | 684468.44 | 602931.51 | 15.0 | GRID | 9/18/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 2133 | 684443.44 | 602881.51 | 7.9 | GRID | 9/18/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 2134 | 684443.44 | 602906.51 | 12.1 | GRID | 9/18/2015 | 12.1 | 0.0 | Point surveyed within Tolerance |
| 2135 | 684443.44 | 602931.51 | 13.8 | GRID | 9/18/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.8) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2136 | 684443.44 | 602956.51 | 13.3 | GRID | 9/18/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 2137 | 684443.44 | 602981.51 | 12.8 | GRID | 9/18/2015 | 12.9 | 0.1 | Point surveyed within Tolerance |
| 2138 | 684443.44 | 603006.51 | 12.4 | GRID | 9/18/2015 | 12.5 | 0.1 | Point surveyed within Tolerance |
| 2139 | 684443.44 | 603031.51 | 12.0 | GRID | 9/18/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 2146 | 684418.44 | 603006.51 | 11.3 | GRID | 9/18/2015 | 11.4 | 0.1 | Point surveyed within Tolerance |
| 2147 | 684418.44 | 602981.51 | 11.7 | GRID | 9/18/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 2148 | 684418.44 | 602956.51 | 12.1 | GRID | 9/18/2015 | 12.1 | 0.0 | Point surveyed within Tolerance |
| 2149 | 684418.44 | 602906.51 | 9.8 | GRID | 9/21/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 2150 | 684393.44 | 602931.51 | 8.6 | GRID | 9/18/2015 | 8.6 | 0.0 | Point surveyed within Tolerance |
| 2151 | 684393.44 | 602956.51 | 11.0 | GRID | 9/18/2015 | 10.9 | -0.1 | Point surveyed within Tolerance |
| 2152 | 684393.44 | 602981.51 | 10.5 | GRID | 9/18/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 2140 | 684443.44 | 603056.51 | 11.7 | GRID | 9/22/2015 | 11.6 | -0.1 | Point surveyed within Tolerance |
| 2141 | 684443.44 | 603081.51 | 11.4 | GRID | 9/22/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 2142 | 684418.44 | 603106.51 | 10.2 | GRID | 9/22/2015 | 10.2 | 0.0 | Point surveyed within Tolerance |
| 2143 | 684418.44 | 603081.51 | 10.4 | GRID | 9/22/2015 | 10.5 | 0.1 | Point surveyed within Tolerance |
| 2144 | 684418.44 | 603056.51 | 10.7 | GRID | 9/22/2015 | 10.6 | -0.1 | Point surveyed within Tolerance |
| 2145 | 684418.44 | 603031.51 | 10.9 | GRID | 9/22/2015 | 10.8 | -0.1 | Point surveyed within Tolerance |
| 2153 | 684393.44 | 603006.51 | 10.1 | GRID | 9/22/2015 | 10.1 | 0.0 | Point surveyed within Tolerance |
| 2154 | 684393.44 | 603031.51 | 9.9 | GRID | 9/22/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 2155 | 684393.44 | 603056.51 | 9.7 | GRID | 9/22/2015 | 9.6 | -0.1 | Point surveyed within Tolerance |
| 2156 | 684393.44 | 603106.51 | 9.4 | GRID | 9/23/2015 | 9.3 | -0.1 | Point surveyed within Tolerance |
| 2157 | 684393.44 | 603131.51 | 9.3 | GRID | 9/23/2015 | 9.2 | -0.1 | Point surveyed within Tolerance |
| 2161 | 684368.44 | 603131.51 | 8.6 | GRID | 9/23/2015 | 8.6 | 0.0 | Point surveyed within Tolerance |
| 2162 | 684368.44 | 603106.51 | 8.8 | GRID | 9/23/2015 | 8.7 | -0.1 | Point surveyed within Tolerance |
| 2163 | 684368.44 | 603056.51 | 8.8 | GRID | 9/22/2015 | 8.8 | 0.0 | Point surveyed within Tolerance |
| 2164 | 684368.44 | 603031.51 | 9.0 | GRID | 9/22/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 2165 | 684368.44 | 603006.51 | 9.2 | GRID | 9/22/2015 | 9.1 | -0.1 | Point surveyed within Tolerance |
| 2166 | 684368.44 | 602981.51 | 9.4 | GRID | 9/22/2015 | 9.3 | -0.1 | Point surveyed within Tolerance |
| 2167 | 684343.44 | 603006.51 | 8.3 | GRID | 9/22/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2168 | 684343.44 | 603031.51 | 8.1 | GRID | 9/22/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2169 | 684343.44 | 603056.51 | 8.2 | GRID | 9/23/2015 | 8.2 | 0.0 | Point surveyed within Tolerance |
| 2170 | 684343.44 | 603106.51 | 8.4 | GRID | 9/23/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2178 | 684318.44 | 603031.51 | 4.7 | GRID | 9/23/2015 | 4.8 | 0.1 | Point surveyed within Tolerance |
| 2179 | 684293.44 | 603056.51 | 4.3 | GRID | 9/23/2015 | 4.3 | 0.0 | Point surveyed within Tolerance |
| 2304 | 684318.44 | 603081.51 | 5.4 | GRID | 9/23/2015 | 5.3 | -0.1 | Point surveyed within Tolerance |
| 2160 | 684368.44 | 603156.51 | 8.6 | GRID | 9/23/2015 | 8.5 | -0.1 | Point surveyed within Tolerance |
| 2171 | 684343.44 | 603131.51 | 8.4 | GRID | 9/23/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2180 | 684293.44 | 603081.51 | 7.4 | GRID | 9/23/2015 | 7.3 | -0.1 | Point surveyed within Tolerance |
| 2195 | 684268.44 | 603081.51 | 5.8 | GRID | 9/23/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 2303 | 684293.44 | 603106.51 | 7.1 | GRID | 9/23/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.9) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2159 | 684368.44 | 603181.51 | 6.4 | GRID | 9/24/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 2172 | 684343.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2173 | 684343.44 | 603206.51 | 6.8 | GRID | 9/24/2015 | 6.7 | -0.1 | Point surveyed within Tolerance |
| 2174 | 684318.44 | 603231.51 | 8.8 | GRID | 9/28/2015 | 8.7 | -0.1 | Point surveyed within Tolerance |
| 2175 | 684318.44 | 603206.51 | 6.8 | GRID | 9/24/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2176 | 684318.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2177 | 684318.44 | 603156.51 | 6.2 | GRID | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2181 | 684293.44 | 603131.51 | 5.9 | GRID | 9/24/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2182 | 684293.44 | 603156.51 | 6.3 | GRID | 9/24/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 2183 | 684293.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.6 | 0.1 | Point surveyed within Tolerance |
| 2184 | 684293.44 | 603206.51 | 8.0 | GRID | 9/28/2015 | 8.0 | 0.0 | Point surveyed within Tolerance |
| 2185 | 684293.44 | 603231.51 | 8.3 | GRID | 9/28/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2190 | 684268.44 | 603206.51 | 7.4 | GRID | 9/28/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 2191 | 684268.44 | 603181.51 | 7.5 | GRID | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2192 | 684268.44 | 603156.51 | 6.2 | GRID | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2193 | 684268.44 | 603131.51 | 5.9 | GRID | 9/24/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2194 | 684268.44 | 603106.51 | 3.1 | GRID | 9/24/2015 | 3.1 | 0.0 | Point surveyed within Tolerance |
| 2196 | 684243.44 | 603131.51 | 3.0 | GRID | 9/24/2015 | 3.0 | 0.0 | Point surveyed within Tolerance |
| 2197 | 684243.44 | 603181.51 | 7.6 | GRID | 9/28/2015 | 7.5 | -0.1 | Point surveyed within Tolerance |
| 2198 | 684243.44 | 603206.51 | 7.3 | GRID | 9/28/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2206 | 684218.44 | 603156.51 | 7.7 | GRID | 9/28/2015 | 7.7 | 0.0 | Point surveyed within Tolerance |
| 2186 | 684293.44 | 603256.51 | 8.5 | GRID | 9/28/2015 | 8.5 | 0.0 | Point surveyed within Tolerance |
| 2188 | 684268.44 | 603256.51 | 8.2 | GRID | 9/28/2015 | 8.1 | -0.1 | Point surveyed within Tolerance |
| 2189 | 684268.44 | 603231.51 | 7.8 | GRID | 9/28/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 2199 | 684243.44 | 603231.51 | 7.5 | GRID | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2205 | 684218.44 | 603206.51 | 7.3 | GRID | 9/28/2015 | 7.2 | -0.1 | Point surveyed within Tolerance |
| 2208 | 684193.44 | 603181.51 | 7.5 | GRID | 9/28/2015 | 7.4 | -0.1 | Point surveyed within Tolerance |
| 2187 | 684268.44 | 603281.51 | 7.1 | GRID | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2200 | 684243.44 | 603256.51 | 7.8 | GRID | 10/7/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 2201 | 684243.44 | 603281.51 | 7.3 | GRID | 10/7/2015 | 7.2 | -0.1 | Point surveyed within Tolerance |
| 2202 | 684218.44 | 603281.51 | 6.9 | GRID | 10/7/2015 | 6.9 | 0.0 | Point surveyed within Tolerance |
| 2203 | 684218.44 | 603256.51 | 7.1 | GRID | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2204 | 684218.44 | 603231.51 | 7.4 | GRID | 10/7/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 2209 | 684193.44 | 603206.51 | 7.3 | GRID | 10/7/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2210 | 684193.44 | 603231.51 | 7.3 | GRID | 10/7/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2211 | 684193.44 | 603256.51 | 6.7 | GRID | 10/7/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 2212 | 684168.44 | 603256.51 | 6.5 | GRID | 10/7/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2213 | 684168.44 | 603231.51 | 6.4 | GRID | 10/7/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |
| 2214 | 684168.44 | 603206.51 | 7.6 | GRID | 10/7/2015 | 7.6 | 0.0 | Point surveyed within Tolerance |
| 2215 | 684143.44 | 603231.51 | 6.4 | GRID | 10/7/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.0) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 548 | 685583.37 | 601539.44 | 15.1 | BRK | 7/2/2015 | 15.2 | 0.1 | Point surveyed within Tolerance |
| 549 | 685595.90 | 601578.00 | 14.2 | BRK | 7/2/2015 | 14.3 | 0.1 | Point surveyed within Tolerance |
| 550 | 685562.63 | 601543.70 | 17.5 | BRK | 7/2/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 551 | 685559.49 | 601547.97 | 13.9 | BRK | 7/2/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 552 | 685555.56 | 601552.54 | 13.9 | BRK | 7/2/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 553 | 685552.50 | 601556.70 | 17.4 | BRK | 7/2/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 554 | 685602.63 | 601551.44 | 17.7 | BRK | 7/2/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 555 | 685524.90 | 601529.98 | 13.1 | BRK | 7/2/2015 | 13.2 | 0.1 | Point surveyed within Tolerance |
| 556 | 685521.85 | 601534.13 | 16.6 | BRK | 7/2/2015 | 16.4 | -0.2 | Point surveyed within Tolerance |
| 557 | 685518.43 | 601506.14 | 15.5 | BRK | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 559 | 685566.10 | 601602.95 | 17.4 | BRK | 7/2/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 560 | 685557.11 | 601621.51 | 16.2 | BRK | 7/2/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 583 | 685469.10 | 601609.94 | 16.0 | BRK | 7/2/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 584 | 685468.06 | 601601.70 | 14.5 | BRK | 7/2/2015 | 14.6 | 0.1 | Point surveyed within Tolerance |
| 585 | 685534.63 | 601655.70 | 15.5 | BRK | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 586 | 685515.15 | 601685.29 | 14.8 | BRK | 7/2/2015 | 14.6 | -0.2 | Point surveyed within Tolerance |
| 587 | 685503.84 | 601702.15 | 14.5 | BRK | 7/2/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 588 | 685484.63 | 601722.61 | 15.5 | BRK | 7/8/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 589 | 685482.47 | 601731.53 | 11.1 | BRK | 7/2/2015 | 11.1 | 0.0 | Point surveyed within Tolerance |
| 590 | 685467.89 | 601733.01 | 13.1 | BRK | 7/2/2015 | 13.2 | 0.1 | Point surveyed within Tolerance |
| 591 | 685467.14 | 601729.90 | 15.3 | BRK | 7/2/2015 | 15.2 | -0.1 | Point surveyed within Tolerance |
| 592 | 685465.84 | 601749.83 | 15.2 | BRK | 7/2/2015 | 15.1 | -0.1 | Point surveyed within Tolerance |
| 593 | 685444.26 | 601779.76 | 13.6 | BRK | 7/2/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 594 | 685429.29 | 601800.21 | 15.1 | BRK | 7/2/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 595 | 685453.48 | 601767.05 | 15.1 | BRK | 7/2/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 603 | 685418.25 | 601641.07 | 13.5 | BRK | 7/2/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 604 | 685415.60 | 601650.93 | 15.9 | BRK | 7/2/2015 | 15.6 | -0.3 | Point surveyed within Tolerance |
| 605 | 685417.81 | 601680.87 | 15.9 | BRK | 7/2/2015 | 15.8 | -0.1 | Point surveyed within Tolerance |
| 606 | 685421.62 | 601680.64 | 13.4 | BRK | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 607 | 685417.84 | 601705.42 | 16.1 | BRK | 7/2/2015 | 15.9 | -0.2 | Point surveyed within Tolerance |
| 608 | 685421.83 | 601705.56 | 13.4 | BRK | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 609 | 685420.68 | 601733.21 | 13.5 | BRK | 7/2/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 610 | 685416.60 | 601732.96 | 16.2 | BRK | 7/2/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 611 | 685420.69 | 601759.40 | 13.5 | BRK | 7/2/2015 | 13.6 | 0.1 | Point surveyed within Tolerance |
| 612 | 685417.42 | 601761.34 | 16.1 | BRK | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 613 | 685367.91 | 601704.46 | 13.3 | BRK | 7/2/2015 | 13.4 | 0.1 | Point surveyed within Tolerance |
| 614 | 685370.79 | 601706.98 | 15.9 | BRK | 7/2/2015 | 15.7 | -0.2 | Point surveyed within Tolerance |
| 615 | 685343.44 | 601731.17 | 13.7 | BRK | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 616 | 685345.91 | 601734.17 | 16.3 | BRK | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 617 | 685303.14 | 601806.86 | 18.3 | BRK | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 618 | 685298.77 | 601809.67 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 619 | 685294.54 | 601809.78 | 15.4 | BRK | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 620 | 685288.92 | 601805.68 | 10.7 | BRK | 7/2/2015 | 10.7 | 0.0 | Point surveyed within Tolerance |
| 621 | 685298.85 | 601821.38 | 15.8 | BRK | 7/2/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 622 | 685295.94 | 601825.31 | 12.5 | BRK | 7/2/2015 | 12.6 | 0.1 | Point surveyed within Tolerance |
| 623 | 685294.65 | 601831.82 | 12.5 | BRK | 7/2/2015 | 12.6 | 0.1 | Point surveyed within Tolerance |
| 624 | 685291.75 | 601835.75 | 15.8 | BRK | 7/2/2015 | 15.5 | -0.3 | Point surveyed within Tolerance |
| 625 | 685324.58 | 601840.13 | 15.9 | BRK | 7/2/2015 | 15.7 | -0.2 | Point surveyed within Tolerance |
| 626 | 685321.52 | 601844.26 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 627 | 685322.67 | 601852.58 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 628 | 685319.64 | 601856.68 | 15.8 | BRK | 7/2/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 629 | 685341.40 | 601852.72 | 15.7 | BRK | 7/2/2015 | 15.4 | -0.3 | Point surveyed within Tolerance |
| 630 | 685338.40 | 601856.76 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 631 | 685345.65 | 601844.39 | 15.9 | BRK | 7/2/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 632 | 685347.89 | 601841.36 | 18.4 | BRK | 7/8/2015 | 18.3 | -0.1 | Point surveyed within Tolerance |
| 633 | 685372.85 | 601864.55 | 15.3 | BRK | 7/2/2015 | 15.4 | 0.1 | Point surveyed within Tolerance |
| 634 | 685364.47 | 601869.99 | 15.2 | BRK | 7/8/2015 | 15.1 | -0.1 | Point surveyed within Tolerance |
| 635 | 685361.56 | 601873.92 | 12.0 | BRK | 7/2/2015 | 12.1 | 0.1 | Point surveyed within Tolerance |
| 636 | 685354.92 | 601876.46 | 12.0 | BRK | 7/2/2015 | 12.1 | 0.1 | Point surveyed within Tolerance |
| 637 | 685350.44 | 601879.24 | 15.3 | BRK | 7/2/2015 | 15.2 | -0.1 | Point surveyed within Tolerance |
| 639 | 685353.62 | 601747.98 | 16.4 | BRK | 7/8/2015 | 16.3 | -0.1 | Point surveyed within Tolerance |
| 640 | 685357.16 | 601746.52 | 13.8 | BRK | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 641 | 685361.58 | 601753.32 | 13.9 | BRK | 7/2/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 642 | 685364.98 | 601751.93 | 16.3 | BRK | 7/2/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 645 | 685381.55 | 601830.67 | 17.5 | BRK | 7/8/2015 | 17.4 | -0.1 | Point surveyed within Tolerance |
| 646 | 685385.39 | 601829.73 | 14.8 | BRK | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 647 | 685383.26 | 601850.36 | 17.6 | BRK | 7/8/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 648 | 685408.65 | 601820.74 | 16.6 | BRK | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 672 | 685359.01 | 601899.40 | 14.5 | BRK | 7/2/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 673 | 685328.78 | 601922.42 | 18.1 | BRK | 7/2/2015 | 18.2 | 0.1 | Point surveyed within Tolerance |
| 674 | 685299.89 | 601934.58 | 18.3 | BRK | 7/2/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 675 | 685300.62 | 601938.23 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 676 | 685305.79 | 601944.00 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 677 | 685308.02 | 601946.97 | 18.2 | BRK | 7/2/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 679 | 685305.33 | 601869.91 | 16.0 | BRK | 7/2/2015 | 16.1 | 0.1 | Point surveyed within Tolerance |
| 680 | 685303.05 | 601872.98 | 18.5 | BRK | 7/2/2015 | 18.1 | -0.4 | Point surveyed within Tolerance |
| 681 | 685268.99 | 601832.99 | 12.1 | BRK | 7/2/2015 | 12.2 | 0.1 | Point surveyed within Tolerance |
| 682 | 685272.64 | 601835.66 | 15.1 | BRK | 7/2/2015 | 14.7 | -0.4 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 683 | 685218.81 | 601931.92 | 18.6 | BRK | 7/2/2015 | 18.2 | -0.4 | Point surveyed within Tolerance |
| 684 | 685217.81 | 601935.62 | 16.0 | BRK | 7/2/2015 | 16.1 | 0.1 | Point surveyed within Tolerance |
| 979 | 685388.74 | 601749.07 | 13.5 | BRK | 7/2/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 980 | 685384.77 | 601750.03 | 16.2 | BRK | 7/2/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 678 | 685292.65 | 601972.35 | 18.1 | BRK | 7/14/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 685 | 685217.77 | 601956.54 | 18.2 | BRK | 7/14/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 686 | 685214.25 | 601958.05 | 15.7 | BRK | 7/14/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 688 | 685246.08 | 602006.05 | 17.3 | BRK | 7/14/2015 | 17.4 | 0.1 | Point surveyed within Tolerance |
| 689 | 685249.42 | 602007.82 | 14.8 | BRK | 7/14/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |
| 690 | 685250.13 | 602009.68 | 14.8 | BRK | 7/14/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 691 | 685253.44 | 602011.40 | 17.3 | BRK | 7/14/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 692 | 685256.80 | 602026.88 | 16.9 | BRK | 7/14/2015 | 17.0 | 0.1 | Point surveyed within Tolerance |
| 822 | 685209.17 | 602098.14 | 16.1 | BRK | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 823 | 685187.68 | 602127.24 | 16.4 | BRK | 7/14/2015 | 16.5 | 0.1 | Point surveyed within Tolerance |
| 824 | 685169.69 | 602121.14 | 16.9 | BRK | 7/14/2015 | 17.0 | 0.1 | Point surveyed within Tolerance |
| 825 | 685159.60 | 602134.77 | 5.6 | BRK | 7/14/2015 | 5.7 | 0.1 | Point surveyed within Tolerance |
| 826 | 685142.99 | 602100.91 | 16.8 | BRK | 7/14/2015 | 16.7 | -0.1 | Point surveyed within Tolerance |
| 827 | 685132.68 | 602114.85 | 5.2 | BRK | 7/14/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 828 | 685117.94 | 602082.20 | 16.5 | BRK | 7/14/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 829 | 685108.04 | 602096.62 | 4.9 | BRK | 7/14/2015 | 4.9 | 0.0 | Point surveyed within Tolerance |
| 830 | 685097.56 | 602070.88 | 13.7 | BRK | 7/14/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 831 | 685091.62 | 602084.47 | 4.6 | BRK | 7/14/2015 | 4.7 | 0.1 | Point surveyed within Tolerance |
| 832 | 685079.08 | 602074.23 | 4.4 | BRK | 7/14/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 833 | 685087.23 | 602063.24 | 5.1 | BRK | 7/14/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 834 | 685228.90 | 602033.89 | 16.5 | BRK | 7/14/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 835 | 685232.50 | 602033.47 | 14.1 | BRK | 7/14/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 836 | 685239.46 | 602034.31 | 14.1 | BRK | 7/14/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 837 | 685243.00 | 602035.55 | 16.6 | BRK | 7/14/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 838 | 685241.70 | 602050.98 | 16.3 | BRK | 7/14/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 839 | 685057.33 | 602100.46 | 4.4 | BRK | 7/24/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 840 | 685060.41 | 602121.19 | 14.5 | BRK | 7/24/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 841 | 685068.93 | 602108.10 | 4.6 | BRK | 7/24/2015 | 4.7 | 0.1 | Point surveyed within Tolerance |
| 842 | 685048.44 | 602112.41 | 4.6 | BRK | 7/24/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 843 | 685096.92 | 602128.82 | 5.0 | BRK | 7/24/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 844 | 685091.28 | 602143.63 | 15.2 | BRK | 7/24/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 845 | 685121.55 | 602147.05 | 5.3 | BRK | 7/24/2015 | 5.4 | 0.1 | Point surveyed within Tolerance |
| 846 | 685109.62 | 602161.54 | 17.8 | BRK | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 847 | 685117.56 | 602193.69 | 17.4 | BRK | 7/24/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 848 | 685118.92 | 602197.25 | 14.9 | BRK | 7/24/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 849 | 685119.73 | 602203.55 | 14.8 | BRK | 7/24/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 850 | 685121.10 | 602206.98 | 17.3 | BRK | 7/24/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 851 | 685114.98 | 602226.59 | 17.2 | BRK | 7/24/2015 | 17.1 | -0.1 | Point surveyed within Tolerance |
| 852 | 685105.19 | 602198.82 | 17.4 | BRK | 7/24/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 853 | 685103.22 | 602203.76 | 14.8 | BRK | 7/24/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 854 | 685088.02 | 602208.76 | 17.4 | BRK | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 855 | 685089.52 | 602212.18 | 14.9 | BRK | 7/24/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 856 | 685085.84 | 602227.09 | 15.1 | BRK | 7/24/2015 | 15.2 | 0.1 | Point surveyed within Tolerance |
| 857 | 685083.49 | 602230.12 | 17.6 | BRK | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 858 | 685094.99 | 602252.22 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 859 | 685081.79 | 602269.14 | 18.1 | BRK | 7/24/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 860 | 685047.09 | 602237.51 | 15.7 | BRK | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 861 | 685043.77 | 602234.95 | 18.2 | BRK | 7/24/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 862 | 685039.91 | 602232.72 | 15.7 | BRK | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 863 | 685042.37 | 602238.43 | 15.7 | BRK | 7/24/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 864 | 685066.11 | 602161.84 | 17.8 | BRK | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 865 | 685062.13 | 602161.07 | 15.3 | BRK | 7/24/2015 | 15.4 | 0.1 | Point surveyed within Tolerance |
| 866 | 685052.96 | 602208.15 | 17.8 | BRK | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 867 | 685049.31 | 602206.51 | 15.4 | BRK | 7/24/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 868 | 685045.11 | 602202.48 | 15.6 | BRK | 7/24/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 869 | 685042.10 | 602200.70 | 17.9 | BRK | 7/24/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 870 | 685022.96 | 602172.09 | 15.4 | BRK | 7/24/2015 | 15.3 | -0.1 | Point surveyed within Tolerance |
| 871 | 685044.91 | 602142.21 | 14.8 | BRK | 7/24/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 872 | 684994.42 | 602217.26 | 18.7 | BRK | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 873 | 684975.68 | 602242.79 | 19.1 | BRK | 7/24/2015 | 19.1 | 0.0 | Point surveyed within Tolerance |
| 874 | 685005.71 | 602243.75 | 18.8 | BRK | 7/24/2015 | 18.7 | -0.1 | Point surveyed within Tolerance |
| 875 | 685009.09 | 602245.47 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 876 | 685025.00 | 602263.80 | 16.2 | BRK | 7/24/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 877 | 685027.83 | 602266.24 | 18.7 | BRK | 7/24/2015 | 18.6 | -0.1 | Point surveyed within Tolerance |
| 878 | 685053.73 | 602299.58 | 18.7 | BRK | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 879 | 685053.33 | 602303.33 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 880 | 685060.48 | 602307.84 | 16.2 | BRK | 7/24/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 881 | 685039.62 | 602323.93 | 18.6 | BRK | 7/24/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 882 | 685021.34 | 602349.28 | 18.4 | BRK | 7/24/2015 | 18.3 | -0.1 | Point surveyed within Tolerance |
| 883 | 685006.56 | 602373.52 | 17.5 | BRK | 7/24/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 884 | 684985.52 | 602400.52 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 885 | 684968.75 | 602423.06 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 886 | 684958.59 | 602266.06 | 19.6 | BRK | 7/24/2015 | 19.5 | -0.1 | Point surveyed within Tolerance |
| 887 | 684944.51 | 602285.23 | 19.9 | BRK | 7/24/2015 | 20.0 | 0.1 | Point surveyed within Tolerance |
| 888 | 684924.17 | 602312.77 | 20.4 | BRK | 7/24/2015 | 20.3 | -0.1 | Point surveyed within Tolerance |
| 889 | 684896.37 | 602343.10 | 18.0 | BRK | 7/24/2015 | 17.9 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 890 | 684880.77 | 602362.80 | 17.8 | BRK | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 891 | 684869.32 | 602354.21 | 8.2 | BRK | 7/24/2015 | 8.3 | 0.1 | Point surveyed within Tolerance |
| 892 | 684884.22 | 602334.10 | 7.9 | BRK | 7/24/2015 | 8.0 | 0.1 | Point surveyed within Tolerance |
| 893 | 684908.58 | 602301.22 | 7.4 | BRK | 7/24/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 894 | 684928.96 | 602273.71 | 7.0 | BRK | 7/24/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 895 | 684943.18 | 602254.50 | 6.7 | BRK | 7/24/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 896 | 684960.30 | 602231.40 | 6.4 | BRK | 7/24/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 897 | 684979.15 | 602205.95 | 6.0 | BRK | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 898 | 685010.86 | 602163.13 | 5.3 | BRK | 7/24/2015 | 5.4 | 0.1 | Point surveyed within Tolerance |
| 899 | 685032.93 | 602133.34 | 4.9 | BRK | 7/24/2015 | 4.9 | 0.0 | Point surveyed within Tolerance |
| 900 | 684953.81 | 602443.85 | 17.6 | BRK | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 901 | 684933.84 | 602472.48 | 17.2 | BRK | 7/24/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 919 | 684835.00 | 602400.55 | 9.0 | BRK | 7/24/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 920 | 684843.87 | 602407.12 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 902 | 684913.09 | 602504.45 | 16.5 | BRK | 8/10/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 910 | 684887.04 | 602531.88 | 18.2 | BRK | 8/10/2015 | 18.2 | 0.0 | Point surveyed within Tolerance |
| 909 | 684858.28 | 602571.33 | 14.7 | BRK | 8/12/2015 | 14.8 | 0.1 | Point surveyed within Tolerance |
| 913 | 684795.24 | 602555.71 | 13.7 | BRK | 8/12/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 914 | 684795.33 | 602552.00 | 16.1 | BRK | 8/12/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 915 | 684770.38 | 602552.44 | 15.8 | BRK | 8/12/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 916 | 684771.04 | 602556.03 | 13.3 | BRK | 8/12/2015 | 13.4 | 0.1 | Point surveyed within Tolerance |
| 917 | 684841.91 | 602602.61 | 16.6 | BRK | 8/12/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 911 | 684720.03 | 602604.99 | 14.7 | BRK | 8/13/2015 | 14.6 | -0.1 | Point surveyed within Tolerance |
| 921 | 684754.50 | 602627.17 | 17.2 | BRK | 8/13/2015 | 17.1 | -0.1 | Point surveyed within Tolerance |
| 923 | 684774.69 | 602642.80 | 17.3 | BRK | 8/13/2015 | 17.2 | -0.1 | Point surveyed within Tolerance |
| 925 | 684807.26 | 602664.88 | 13.8 | BRK | 8/13/2015 | 13.7 | -0.1 | Point surveyed within Tolerance |
| 912 | 684710.93 | 602615.25 | 5.5 | BRK | 9/4/2015 | 5.6 | 0.1 | Point surveyed within Tolerance |
| 922 | 684744.74 | 602640.33 | 6.3 | BRK | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 924 | 684765.25 | 602655.54 | 6.7 | BRK | 9/4/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 927 | 684774.96 | 602705.07 | 7.4 | BRK | 9/4/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 929 | 684725.10 | 602668.09 | 6.3 | BRK | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 933 | 684699.13 | 602648.83 | 5.7 | BRK | 9/4/2015 | 5.8 | 0.1 | Point surveyed within Tolerance |
| 934 | 684677.32 | 602632.66 | 5.2 | BRK | 9/4/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 936 | 684665.76 | 602624.13 | 5.0 | BRK | 9/4/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 2216 | 684768.70 | 602713.78 | 14.5 | BRK | 9/4/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 2217 | 684755.49 | 602705.02 | 14.8 | BRK | 9/4/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |
| 2218 | 684750.54 | 602706.29 | 17.4 | BRK | 9/4/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 2219 | 684719.51 | 602728.09 | 18.1 | BRK | 9/4/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 2220 | 684721.25 | 602731.77 | 15.4 | BRK | 9/4/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2223 | 684714.82 | 602681.95 | 17.8 | BRK | 9/4/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 2224 | 684695.23 | 602678.31 | 15.2 | BRK | 9/4/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 2225 | 684691.16 | 602677.76 | 17.9 | BRK | 9/4/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 2226 | 684679.26 | 602656.42 | 17.5 | BRK | 9/4/2015 | 17.4 | -0.1 | Point surveyed within Tolerance |
| 2227 | 684678.94 | 602651.43 | 14.9 | BRK | 9/4/2015 | 14.8 | -0.1 | Point surveyed within Tolerance |
| 2228 | 684668.13 | 602643.12 | 14.5 | BRK | 9/4/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 2229 | 684657.26 | 602634.26 | 5.1 | BRK | 9/4/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 2230 | 684652.03 | 602663.18 | 15.1 | BRK | 9/4/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 2231 | 684641.00 | 602654.19 | 5.6 | BRK | 9/4/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 2232 | 684642.38 | 602682.88 | 18.2 | BRK | 9/4/2015 | 18.2 | 0.0 | Point surveyed within Tolerance |
| 2233 | 684640.23 | 602679.29 | 15.5 | BRK | 9/4/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 2234 | 684618.68 | 602681.55 | 6.2 | BRK | 9/4/2015 | 6.3 | 0.1 | Point surveyed within Tolerance |
| 2235 | 684632.71 | 602692.99 | 18.3 | BRK | 9/4/2015 | 18.2 | -0.1 | Point surveyed within Tolerance |
| 2236 | 684620.10 | 602708.58 | 18.7 | BRK | 9/4/2015 | 18.6 | -0.1 | Point surveyed within Tolerance |
| 2239 | 684603.43 | 602700.25 | 6.6 | BRK | 9/4/2015 | 6.7 | 0.1 | Point surveyed within Tolerance |
| 2312 | 684688.25 | 602662.99 | 17.6 | BRK | 9/4/2015 | 17.7 | 0.1 | Point surveyed within Tolerance |
| 2222 | 684686.52 | 602801.63 | 17.2 | BRK | 9/9/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 2240 | 684580.79 | 602728.00 | 7.2 | BRK | 9/9/2015 | 7.3 | 0.1 | Point surveyed within Tolerance |
| 2241 | 684592.09 | 602737.22 | 17.0 | BRK | 9/9/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 2245 | 684652.97 | 602837.52 | 18.0 | BRK | 9/9/2015 | 17.9 | -0.1 | Point surveyed within Tolerance |
| 2248 | 684632.99 | 602849.23 | 20.5 | BRK | 9/9/2015 | 20.5 | 0.0 | Point surveyed within Tolerance |
| 2249 | 684573.19 | 602760.13 | 17.4 | BRK | 9/9/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 2250 | 684562.02 | 602751.01 | 7.8 | BRK | 9/9/2015 | 7.9 | 0.1 | Point surveyed within Tolerance |
| 2251 | 684549.64 | 602787.35 | 17.3 | BRK | 9/9/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 2252 | 684539.27 | 602778.90 | 8.4 | BRK | 9/9/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2253 | 684568.32 | 602806.28 | 17.4 | BRK | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2254 | 684565.58 | 602809.03 | 20.0 | BRK | 9/9/2015 | 19.9 | -0.1 | Point surveyed within Tolerance |
| 2255 | 684590.81 | 602830.43 | 20.3 | BRK | 9/9/2015 | 20.3 | 0.0 | Point surveyed within Tolerance |
| 2256 | 684593.43 | 602827.27 | 17.6 | BRK | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2257 | 684611.57 | 602875.64 | 20.3 | BRK | 9/9/2015 | 20.2 | -0.1 | Point surveyed within Tolerance |
| 2261 | 684576.88 | 602901.09 | 18.3 | BRK | 9/9/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 2266 | 684529.13 | 602867.21 | 18.0 | BRK | 9/9/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 2269 | 684529.62 | 602815.05 | 19.2 | BRK | 9/9/2015 | 19.2 | 0.0 | Point surveyed within Tolerance |
| 2270 | 684517.71 | 602805.33 | 9.0 | BRK | 9/9/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 2313 | 684666.34 | 602822.94 | 17.7 | BRK | 9/9/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 2259 | 684588.87 | 602908.31 | 19.0 | BRK | 9/16/2015 | 19.1 | 0.1 | Point surveyed within Tolerance |
| 2262 | 684562.28 | 602912.39 | 6.5 | BRK | 9/16/2015 | 6.6 | 0.1 | Point surveyed within Tolerance |
| 2263 | 684546.99 | 602879.91 | 18.1 | BRK | 9/16/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 2264 | 684536.89 | 602894.42 | 6.3 | BRK | 9/16/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2265 | 684518.89 | 602881.69 | 6.2 | BRK | 9/16/2015 | 6.3 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.6) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2267 | 684498.05 | 602850.83 | 14.8 | BRK | 9/16/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 2268 | 684490.45 | 602861.57 | 6.0 | BRK | 9/16/2015 | 6.1 | 0.1 | Point surveyed within Tolerance |
| 2275 | 684469.16 | 602880.75 | 13.2 | BRK | 9/16/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 2278 | 684497.26 | 602878.64 | 6.1 | BRK | 9/16/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2279 | 684491.48 | 602886.80 | 12.8 | BRK | 9/16/2015 | 12.7 | -0.1 | Point surveyed within Tolerance |
| 2282 | 684569.90 | 602930.04 | 6.6 | BRK | 9/16/2015 | 6.6 | 0.0 | Point surveyed within Tolerance |
| 2283 | 684564.16 | 602938.23 | 13.2 | BRK | 9/16/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 2284 | 684462.82 | 602873.57 | 6.8 | BRK | 9/16/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2271 | 684492.19 | 603028.63 | 14.1 | BRK | 9/18/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 2272 | 684495.31 | 603031.35 | 11.3 | BRK | 9/18/2015 | 11.4 | 0.1 | Point surveyed within Tolerance |
| 2276 | 684420.78 | 602931.95 | 12.7 | BRK | 9/18/2015 | 12.7 | 0.0 | Point surveyed within Tolerance |
| 2277 | 684418.27 | 602928.58 | 9.9 | BRK | 9/18/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 2280 | 684466.73 | 602909.21 | 16.2 | BRK | 9/18/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 2281 | 684469.26 | 602906.05 | 13.5 | BRK | 9/18/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 2308 | 684541.16 | 602978.86 | 13.9 | BRK | 9/18/2015 | 13.8 | -0.1 | Point surveyed within Tolerance |
| 2309 | 684537.93 | 602976.16 | 16.7 | BRK | 9/18/2015 | 16.7 | 0.0 | Point surveyed within Tolerance |
| 2310 | 684519.64 | 603003.49 | 12.7 | BRK | 9/18/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 2311 | 684516.52 | 603000.77 | 15.4 | BRK | 9/18/2015 | 15.5 | 0.1 | Point surveyed within Tolerance |
| 2273 | 684467.44 | 603056.98 | 12.7 | BRK | 9/22/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 2274 | 684470.54 | 603059.69 | 10.0 | BRK | 9/22/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 2285 | 684396.21 | 603081.17 | 9.6 | BRK | 9/22/2015 | 9.5 | -0.1 | Point surveyed within Tolerance |
| 2286 | 684394.95 | 603084.82 | 7.0 | BRK | 9/22/2015 | 6.9 | -0.1 | Point surveyed within Tolerance |
| 2287 | 684370.17 | 603081.08 | 6.5 | BRK | 9/22/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2288 | 684369.73 | 603084.51 | 8.8 | BRK | 9/22/2015 | 8.8 | 0.0 | Point surveyed within Tolerance |
| 2291 | 684343.83 | 603080.68 | 5.9 | BRK | 9/23/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2292 | 684344.02 | 603084.27 | 8.3 | BRK | 9/23/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2293 | 684318.43 | 603058.47 | 7.6 | BRK | 9/23/2015 | 7.5 | -0.1 | Point surveyed within Tolerance |
| 2294 | 684314.63 | 603057.98 | 5.0 | BRK | 9/23/2015 | 5.1 | 0.1 | Point surveyed within Tolerance |
| 2306 | 684383.22 | 603153.36 | 9.0 | BRK | 9/23/2015 | 8.9 | -0.1 | Point surveyed within Tolerance |
| 2307 | 684386.53 | 603155.86 | 6.6 | BRK | 9/23/2015 | 6.5 | -0.1 | Point surveyed within Tolerance |
| 2289 | 684346.82 | 603155.61 | 8.4 | BRK | 9/24/2015 | 8.3 | -0.1 | Point surveyed within Tolerance |
| 2290 | 684344.28 | 603158.02 | 7.0 | BRK | 9/24/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 2296 | 684244.61 | 603103.27 | 6.2 | BRK | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2297 | 684317.01 | 603131.31 | 6.5 | BRK | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2298 | 684318.88 | 603129.97 | 8.1 | BRK | 9/24/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2299 | 684244.49 | 603157.76 | 7.5 | BRK | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2300 | 684238.78 | 603154.40 | 3.1 | BRK | 9/28/2015 | 3.1 | 0.0 | Point surveyed within Tolerance |
| 2301 | 684221.74 | 603183.65 | 7.8 | BRK | 9/28/2015 | 7.7 | -0.1 | Point surveyed within Tolerance |
| 2302 | 684225.10 | 603177.88 | 3.3 | BRK | 9/28/2015 | 3.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.0) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 545 | 685526.43 | 601442.32 | 12.9 | BNDY | 7/2/2015 | 13.0 | 0.1 | Point surveyed within Tolerance |
| 546 | 685543.45 | 601459.45 | 13.4 | BNDY | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 547 | 685561.91 | 601478.03 | 14.2 | BNDY | 7/2/2015 | 14.2 | 0.0 | Point surveyed within Tolerance |
| 558 | 685516.84 | 601455.37 | 13.7 | BNDY | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 561 | 685572.96 | 601633.24 | 10.0 | BNDY | 7/2/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 562 | 685589.38 | 601610.88 | 10.2 | BNDY | 7/2/2015 | 10.1 | -0.1 | Point surveyed within Tolerance |
| 563 | 685606.33 | 601587.78 | 9.9 | BNDY | 7/2/2015 | 10.0 | 0.1 | Point surveyed within Tolerance |
| 564 | 685633.80 | 601550.37 | 9.8 | BNDY | 7/2/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 565 | 685622.62 | 601565.61 | 10.0 | BNDY | 7/2/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 566 | 685614.41 | 601530.85 | 15.7 | BNDY | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 567 | 685591.47 | 601507.77 | 15.0 | BNDY | 7/2/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 568 | 685577.88 | 601494.10 | 14.6 | BNDY | 7/2/2015 | 14.6 | 0.0 | Point surveyed within Tolerance |
| 569 | 685488.06 | 601495.42 | 14.3 | BNDY | 7/2/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 570 | 685501.08 | 601477.69 | 14.9 | BNDY | 7/2/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 571 | 685474.31 | 601513.30 | 13.6 | BNDY | 7/2/2015 | 13.6 | 0.0 | Point surveyed within Tolerance |
| 572 | 685459.92 | 601533.74 | 12.8 | BNDY | 7/2/2015 | 12.8 | 0.0 | Point surveyed within Tolerance |
| 573 | 685442.87 | 601556.12 | 12.4 | BNDY | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 574 | 685428.08 | 601576.27 | 12.2 | BNDY | 7/2/2015 | 12.2 | 0.0 | Point surveyed within Tolerance |
| 575 | 685413.27 | 601596.44 | 11.9 | BNDY | 7/2/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 576 | 685398.47 | 601616.59 | 11.4 | BNDY | 7/2/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 577 | 685383.68 | 601636.74 | 11.3 | BNDY | 7/2/2015 | 11.3 | 0.0 | Point surveyed within Tolerance |
| 578 | 685368.88 | 601656.89 | 11.3 | BNDY | 7/2/2015 | 11.2 | -0.1 | Point surveyed within Tolerance |
| 579 | 685558.28 | 601653.23 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 581 | 685543.38 | 601673.52 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 582 | 685528.60 | 601693.65 | 9.8 | BNDY | 7/2/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 596 | 685514.37 | 601713.04 | 9.8 | BNDY | 7/2/2015 | 9.7 | -0.1 | Point surveyed within Tolerance |
| 597 | 685499.50 | 601733.28 | 9.7 | BNDY | 7/2/2015 | 9.8 | 0.1 | Point surveyed within Tolerance |
| 598 | 685485.10 | 601752.90 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 599 | 685469.40 | 601774.28 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 600 | 685454.74 | 601794.25 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 601 | 685439.85 | 601814.53 | 9.7 | BNDY | 7/2/2015 | 9.6 | -0.1 | Point surveyed within Tolerance |
| 602 | 685425.01 | 601834.73 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 638 | 685354.08 | 601677.04 | 11.3 | BNDY | 7/2/2015 | 11.1 | -0.2 | Point surveyed within Tolerance |
| 643 | 685324.49 | 601717.35 | 10.8 | BNDY | 7/2/2015 | 10.6 | -0.2 | Point surveyed within Tolerance |
| 644 | 685339.29 | 601697.19 | 11.0 | BNDY | 7/2/2015 | 10.6 | -0.4 | Point surveyed within Tolerance |
| 649 | 685309.86 | 601737.62 | 10.6 | BNDY | 7/2/2015 | 10.6 | 0.0 | Point surveyed within Tolerance |
| 650 | 685295.20 | 601757.86 | 10.5 | BNDY | 7/2/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 651 | 685280.51 | 601778.09 | 10.4 | BNDY | 7/2/2015 | 10.3 | -0.1 | Point surveyed within Tolerance |
| 652 | 685265.70 | 601798.24 | 10.7 | BNDY | 7/2/2015 | 10.8 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 653 | 685250.90 | 601818.38 | 11.9 | BNDY | 7/2/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 654 | 685236.09 | 601838.53 | 15.1 | BNDY | 7/2/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 655 | 685221.28 | 601858.68 | 15.6 | BNDY | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 656 | 685206.48 | 601878.81 | 15.5 | BNDY | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 657 | 685191.67 | 601898.96 | 15.5 | BNDY | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 658 | 685176.87 | 601919.10 | 15.4 | BNDY | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 659 | 685410.29 | 601854.79 | 9.6 | BNDY | 7/2/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 660 | 685395.44 | 601875.02 | 9.6 | BNDY | 7/2/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 661 | 685380.66 | 601895.14 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 662 | 685365.91 | 601915.23 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 663 | 685351.03 | 601935.49 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 664 | 685336.28 | 601955.58 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 687 | 685162.06 | 601939.25 | 14.9 | BNDY | 7/2/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 665 | 685321.52 | 601975.69 | 10.0 | BNDY | 7/14/2015 | 9.9 | -0.1 | Point surveyed within Tolerance |
| 666 | 685306.70 | 601995.87 | 10.0 | BNDY | 7/14/2015 | 9.9 | -0.1 | Point surveyed within Tolerance |
| 667 | 685292.04 | 602015.84 | 10.0 | BNDY | 7/14/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 668 | 685277.22 | 602036.03 | 10.0 | BNDY | 7/14/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 669 | 685262.73 | 602055.75 | 9.9 | BNDY | 7/14/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 670 | 685247.66 | 602076.28 | 10.0 | BNDY | 7/14/2015 | 10.1 | 0.1 | Point surveyed within Tolerance |
| 671 | 685232.64 | 602096.74 | 10.2 | BNDY | 7/14/2015 | 10.1 | -0.1 | Point surveyed within Tolerance |
| 693 | 685147.26 | 601959.39 | 14.3 | BNDY | 7/14/2015 | 14.4 | 0.1 | Point surveyed within Tolerance |
| 694 | 685132.45 | 601979.53 | 13.7 | BNDY | 7/14/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 695 | 685117.65 | 601999.68 | 13.2 | BNDY | 7/14/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 696 | 685102.93 | 602019.90 | 10.3 | BNDY | 7/14/2015 | 10.4 | 0.1 | Point surveyed within Tolerance |
| 697 | 685088.04 | 602039.97 | 6.1 | BNDY | 7/14/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 698 | 685073.23 | 602060.11 | 4.7 | BNDY | 7/14/2015 | 4.8 | 0.1 | Point surveyed within Tolerance |
| 699 | 685058.42 | 602080.25 | 4.3 | BNDY | 7/14/2015 | 4.4 | 0.1 | Point surveyed within Tolerance |
| 705 | 685217.90 | 602116.82 | 10.4 | BNDY | 7/14/2015 | 10.3 | -0.1 | Point surveyed within Tolerance |
| 706 | 685203.10 | 602136.97 | 10.5 | BNDY | 7/14/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 700 | 685043.62 | 602100.40 | 4.5 | BNDY | 7/24/2015 | 4.4 | -0.1 | Point surveyed within Tolerance |
| 701 | 685028.81 | 602120.54 | 4.8 | BNDY | 7/24/2015 | 4.9 | 0.1 | Point surveyed within Tolerance |
| 702 | 685014.01 | 602140.69 | 5.1 | BNDY | 7/24/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 703 | 684999.20 | 602160.83 | 5.4 | BNDY | 7/24/2015 | 5.4 | 0.0 | Point surveyed within Tolerance |
| 704 | 684984.40 | 602180.97 | 5.7 | BNDY | 7/24/2015 | 5.7 | 0.0 | Point surveyed within Tolerance |
| 707 | 685188.31 | 602157.12 | 6.0 | BNDY | 7/24/2015 | 6.1 | 0.1 | Point surveyed within Tolerance |
| 708 | 685173.51 | 602177.27 | 6.0 | BNDY | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 709 | 685143.92 | 602217.57 | 11.2 | BNDY | 7/24/2015 | 11.2 | 0.0 | Point surveyed within Tolerance |
| 710 | 685158.71 | 602197.42 | 11.1 | BNDY | 7/24/2015 | 11.0 | -0.1 | Point surveyed within Tolerance |
| 711 | 685129.12 | 602237.73 | 11.4 | BNDY | 7/24/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 712 | 685114.32 | 602257.88 | 11.6 | BNDY | 7/24/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 713 | 685099.53 | 602278.03 | 11.8 | BNDY | 7/24/2015 | 11.7 | -0.1 | Point surveyed within Tolerance |
| 714 | 685084.73 | 602298.18 | 12.0 | BNDY | 7/24/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 715 | 685069.94 | 602318.33 | 12.0 | BNDY | 7/24/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 716 | 685055.15 | 602338.47 | 11.9 | BNDY | 7/24/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 717 | 685040.35 | 602358.63 | 11.9 | BNDY | 7/24/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 718 | 685025.55 | 602378.78 | 11.8 | BNDY | 7/24/2015 | 11.9 | 0.1 | Point surveyed within Tolerance |
| 719 | 685010.76 | 602398.93 | 11.8 | BNDY | 7/24/2015 | 11.9 | 0.1 | Point surveyed within Tolerance |
| 720 | 684995.96 | 602419.08 | 11.8 | BNDY | 7/24/2015 | 11.7 | -0.1 | Point surveyed within Tolerance |
| 721 | 684981.17 | 602439.24 | 11.7 | BNDY | 7/24/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 722 | 684966.37 | 602459.39 | 11.6 | BNDY | 7/24/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 723 | 684951.57 | 602479.54 | 11.5 | BNDY | 7/24/2015 | 11.5 | 0.0 | Point surveyed within Tolerance |
| 724 | 684936.78 | 602499.69 | 11.5 | BNDY | 7/24/2015 | 11.6 | 0.1 | Point surveyed within Tolerance |
| 731 | 684969.59 | 602201.11 | 6.0 | BNDY | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 732 | 684954.79 | 602221.26 | 6.3 | BNDY | 7/24/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 733 | 684939.98 | 602241.40 | 6.6 | BNDY | 7/24/2015 | 6.6 | 0.0 | Point surveyed within Tolerance |
| 734 | 684925.18 | 602261.55 | 6.9 | BNDY | 7/24/2015 | 6.8 | -0.1 | Point surveyed within Tolerance |
| 735 | 684910.37 | 602281.69 | 7.1 | BNDY | 7/24/2015 | 7.2 | 0.1 | Point surveyed within Tolerance |
| 736 | 684895.57 | 602301.83 | 7.4 | BNDY | 7/24/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 737 | 684880.76 | 602321.98 | 7.8 | BNDY | 7/24/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 738 | 684865.95 | 602342.12 | 8.2 | BNDY | 7/24/2015 | 8.2 | 0.0 | Point surveyed within Tolerance |
| 739 | 684851.15 | 602362.27 | 8.5 | BNDY | 7/24/2015 | 8.5 | 0.0 | Point surveyed within Tolerance |
| 740 | 684827.24 | 602394.80 | 9.0 | BNDY | 7/24/2015 | 8.9 | -0.1 | Point surveyed within Tolerance |
| 741 | 684821.28 | 602402.91 | 15.7 | BNDY | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 725 | 684921.98 | 602519.84 | 11.6 | BNDY | 8/10/2015 | 11.5 | -0.1 | Point surveyed within Tolerance |
| 726 | 684907.19 | 602539.99 | 11.6 | BNDY | 8/10/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 727 | 684892.39 | 602560.14 | 11.6 | BNDY | 8/10/2015 | 11.7 | 0.1 | Point surveyed within Tolerance |
| 728 | 684877.59 | 602580.30 | 11.6 | BNDY | 8/10/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 742 | 684806.74 | 602422.70 | 15.0 | BNDY | 8/10/2015 | 15.0 | 0.0 | Point surveyed within Tolerance |
| 743 | 684792.02 | 602442.92 | 14.4 | BNDY | 8/10/2015 | 14.4 | 0.0 | Point surveyed within Tolerance |
| 729 | 684862.80 | 602600.45 | 11.7 | BNDY | 8/12/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 730 | 684848.00 | 602620.60 | 11.7 | BNDY | 8/12/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 761 | 684777.12 | 602462.99 | 13.8 | BNDY | 8/12/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 762 | 684762.31 | 602483.14 | 13.2 | BNDY | 8/12/2015 | 13.1 | -0.1 | Point surveyed within Tolerance |
| 763 | 684747.51 | 602503.28 | 12.8 | BNDY | 8/12/2015 | 12.7 | -0.1 | Point surveyed within Tolerance |
| 744 | 684833.20 | 602640.76 | 11.7 | BNDY | 8/13/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 745 | 684818.41 | 602660.91 | 11.7 | BNDY | 8/13/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 764 | 684732.70 | 602523.42 | 12.5 | BNDY | 8/13/2015 | 12.4 | -0.1 | Point surveyed within Tolerance |
| 765 | 684717.90 | 602543.56 | 7.9 | BNDY | 8/13/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 766 | 684703.09 | 602563.72 | 6.7 | BNDY | 8/13/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 767 | 684687.11 | 602585.46 | 5.5 | BNDY | 8/13/2015 | 5.5 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 746 | 684803.61 | 602681.06 | 9.1 | BNDY | 9/4/2015 | 9.1 | 0.0 | Point surveyed within Tolerance |
| 747 | 684790.60 | 602698.78 | 7.5 | BNDY | 9/4/2015 | 7.6 | 0.1 | Point surveyed within Tolerance |
| 768 | 684672.87 | 602604.82 | 4.9 | BNDY | 9/4/2015 | 5.0 | 0.1 | Point surveyed within Tolerance |
| 769 | 684656.51 | 602623.72 | 5.0 | BNDY | 9/4/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 2000 | 684774.23 | 602717.67 | 12.4 | BNDY | 9/4/2015 | 12.5 | 0.1 | Point surveyed within Tolerance |
| 2001 | 684757.86 | 602736.57 | 12.9 | BNDY | 9/4/2015 | 12.8 | -0.1 | Point surveyed within Tolerance |
| 2002 | 684741.50 | 602755.47 | 13.2 | BNDY | 9/4/2015 | 13.1 | -0.1 | Point surveyed within Tolerance |
| 2003 | 684725.13 | 602774.36 | 13.5 | BNDY | 9/4/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 2004 | 684708.76 | 602793.26 | 13.8 | BNDY | 9/4/2015 | 13.7 | -0.1 | Point surveyed within Tolerance |
| 2065 | 684591.05 | 602699.29 | 6.7 | BNDY | 9/4/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 2066 | 684607.42 | 602680.39 | 6.3 | BNDY | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 2067 | 684623.78 | 602661.50 | 5.9 | BNDY | 9/4/2015 | 5.8 | -0.1 | Point surveyed within Tolerance |
| 2068 | 684640.15 | 602642.60 | 5.4 | BNDY | 9/4/2015 | 5.4 | 0.0 | Point surveyed within Tolerance |
| 2005 | 684692.39 | 602812.16 | 14.0 | BNDY | 9/9/2015 | 13.9 | -0.1 | Point surveyed within Tolerance |
| 2006 | 684676.02 | 602831.05 | 13.6 | BNDY | 9/9/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 2007 | 684659.66 | 602849.95 | 13.7 | BNDY | 9/9/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 2008 | 684643.29 | 602868.85 | 13.8 | BNDY | 9/9/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 2009 | 684626.92 | 602887.74 | 13.9 | BNDY | 9/9/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 2010 | 684610.55 | 602906.64 | 14.0 | BNDY | 9/9/2015 | 14.1 | 0.1 | Point surveyed within Tolerance |
| 2058 | 684476.47 | 602831.57 | 9.8 | BNDY | 9/9/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 2059 | 684492.84 | 602812.67 | 9.3 | BNDY | 9/9/2015 | 9.4 | 0.1 | Point surveyed within Tolerance |
| 2060 | 684509.31 | 602793.66 | 8.9 | BNDY | 9/9/2015 | 9.0 | 0.1 | Point surveyed within Tolerance |
| 2061 | 684525.58 | 602774.88 | 8.5 | BNDY | 9/9/2015 | 8.4 | -0.1 | Point surveyed within Tolerance |
| 2062 | 684541.94 | 602755.98 | 8.0 | BNDY | 9/9/2015 | 8.1 | 0.1 | Point surveyed within Tolerance |
| 2063 | 684558.31 | 602737.08 | 7.6 | BNDY | 9/9/2015 | 7.6 | 0.0 | Point surveyed within Tolerance |
| 2064 | 684574.68 | 602718.19 | 7.2 | BNDY | 9/9/2015 | 7.1 | -0.1 | Point surveyed within Tolerance |
| 2011 | 684589.12 | 602931.38 | 6.6 | BNDY | 9/16/2015 | 6.7 | 0.1 | Point surveyed within Tolerance |
| 2012 | 684575.96 | 602946.57 | 13.3 | BNDY | 9/16/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 2057 | 684459.70 | 602850.93 | 5.9 | BNDY | 9/16/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2013 | 684545.08 | 602982.23 | 13.8 | BNDY | 9/18/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 2014 | 684561.45 | 602963.33 | 14.7 | BNDY | 9/18/2015 | 14.8 | 0.1 | Point surveyed within Tolerance |
| 2015 | 684528.71 | 603001.12 | 12.8 | BNDY | 9/18/2015 | 12.8 | 0.0 | Point surveyed within Tolerance |
| 2016 | 684512.34 | 603020.02 | 11.9 | BNDY | 9/18/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 2017 | 684495.97 | 603038.92 | 11.0 | BNDY | 9/18/2015 | 11.1 | 0.1 | Point surveyed within Tolerance |
| 2051 | 684361.89 | 602963.84 | 6.7 | BNDY | 9/18/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 2052 | 684378.26 | 602944.95 | 7.7 | BNDY | 9/18/2015 | 7.8 | 0.1 | Point surveyed within Tolerance |
| 2053 | 684394.63 | 602926.05 | 8.9 | BNDY | 9/18/2015 | 9.0 | 0.1 | Point surveyed within Tolerance |
| 2054 | 684411.00 | 602907.15 | 10.1 | BNDY | 9/18/2015 | 10.0 | -0.1 | Point surveyed within Tolerance |
| 2055 | 684427.94 | 602887.59 | 8.4 | BNDY | 9/18/2015 | 8.5 | 0.1 | Point surveyed within Tolerance |
| 2056 | 684443.73 | 602869.36 | 10.4 | BNDY | 9/18/2015 | 10.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2018 | 684479.61 | 603057.81 | 10.1 | BNDY | 9/23/2015 | 10.1 | 0.0 | Point surveyed within Tolerance |
| 2019 | 684463.24 | 603076.71 | 9.2 | BNDY | 9/22/2015 | 9.1 | -0.1 | Point surveyed within Tolerance |
| 2020 | 684446.87 | 603095.61 | 8.3 | BNDY | 9/22/2015 | 8.3 | 0.0 | Point surveyed within Tolerance |
| 2021 | 684430.50 | 603114.50 | 7.5 | BNDY | 9/22/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2022 | 684414.13 | 603133.40 | 6.8 | BNDY | 9/23/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2023 | 684397.77 | 603152.30 | 6.3 | BNDY | 9/23/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2046 | 684280.05 | 603058.33 | 4.2 | BNDY | 9/23/2015 | 4.2 | 0.0 | Point surveyed within Tolerance |
| 2047 | 684296.42 | 603039.43 | 4.3 | BNDY | 9/23/2015 | 4.3 | 0.0 | Point surveyed within Tolerance |
| 2048 | 684312.79 | 603020.53 | 4.6 | BNDY | 9/23/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 2049 | 684329.16 | 603001.64 | 5.1 | BNDY | 9/22/2015 | 5.1 | 0.0 | Point surveyed within Tolerance |
| 2050 | 684345.53 | 602982.74 | 5.8 | BNDY | 9/22/2015 | 5.8 | 0.0 | Point surveyed within Tolerance |
| 2024 | 684381.40 | 603171.20 | 6.5 | BNDY | 9/23/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2045 | 684263.69 | 603077.22 | 5.9 | BNDY | 9/23/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2025 | 684365.03 | 603190.09 | 6.6 | BNDY | 9/24/2015 | 6.5 | -0.1 | Point surveyed within Tolerance |
| 2026 | 684348.66 | 603208.99 | 6.8 | BNDY | 9/24/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2027 | 684332.29 | 603227.89 | 6.8 | BNDY | 9/28/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2028 | 684315.93 | 603246.78 | 7.7 | BNDY | 9/28/2015 | 7.8 | 0.1 | Point surveyed within Tolerance |
| 2041 | 684198.59 | 603153.14 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2042 | 684214.58 | 603133.91 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2043 | 684230.98 | 603114.98 | 4.6 | BNDY | 9/24/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 2044 | 684247.32 | 603096.12 | 6.2 | BNDY | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2029 | 684299.56 | 603265.68 | 7.9 | BNDY | 9/28/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 2040 | 684182.05 | 603171.63 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2030 | 684283.19 | 603284.58 | 8.1 | BNDY | 10/7/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2031 | 684258.41 | 603313.18 | 8.2 | BNDY | 10/7/2015 | 8.1 | -0.1 | Point surveyed within Tolerance |
| 2032 | 684238.18 | 603303.29 | 7.1 | BNDY | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2033 | 684215.72 | 603292.32 | 6.8 | BNDY | 10/7/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2034 | 684193.26 | 603281.34 | 6.5 | BNDY | 10/7/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2035 | 684170.80 | 603270.36 | 6.4 | BNDY | 10/7/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 2036 | 684148.33 | 603259.38 | 6.3 | BNDY | 10/7/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2037 | 684124.13 | 603238.34 | 6.1 | BNDY | 10/7/2015 | 6.2 | 0.1 | Point surveyed within Tolerance |
| 2038 | 684149.11 | 603209.50 | 6.1 | BNDY | 10/7/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2039 | 684165.48 | 603190.60 | 6.1 | BNDY | 10/7/2015 | 6.2 | 0.1 | Point surveyed within Tolerance |
| 2305 | 684268.00 | 603302.11 | 8.1 | BNDY | 10/7/2015 | 8.2 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

3 Points in 0.1 - 0.5 ft. tolerance are due to a slight overcut in the top of slopes where it wouldn't be suitable for backfill due to compaction difficulties.

**Per SPECIFICATION 01460 SURVEY. SECTION 1.05 F. Spot Elevations - Survey shall be constructed to provide an accuracy of 0.1 feet vertically. Ninety percent of all spot elevations placed on the maps shall have an accuracy of at least 0.1', and the remaining 10 percent shall not be in error by more than one-half (1/2) the contour interval (0.5'). Break points added to replace Grid Points that fell on slopes and Boundary Points will be treated as Spot Elevations as defined in Section 1.05 F.**

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Grid Points depicted in Table 1, Break Points in Table 2, Boundary Points in Table 3, and topographic spot elevations are correct, and representative of the as-built cap subgrade throughout the SA6 South cap.**

R. Thomas Hugg 2/12/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

**ATTACHMENT E**
**SA-6 SOUTH GEOMEMBRANE GRADING PLAN**

LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

0 20 40 80

SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GEOMEMBRANE GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT GEOMEMBRANE GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM 7/2/15 THROUGH 10/7/15. GEOMEMBRANE GRADING SURFACES AND CONTOURS WERE GENERATED BY ENTACT, CHECKED BY AMEC AND CONFIRMED BY MASER CONSULTING P.A.*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 7/12/16 | REVISED ASBUILT TOPO PER ENTACTS COMMENTS | BSB | RTH |
| DSGN | | DR CHK | | APVD |

R. THOMAS HUGG

NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
GEOMEMBRANE GRADING
PLAN

FILE NUMBER
12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 889 - 2629

VERIFY SCALE


BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/11/16 |
| PROJ | 3480-10-0027 |
| DWG | C-122 |
| SHEET | 1 OF 3 |

FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-ASBT-SUBGRD-SOUTH-CAP-10-07-15.dwg PLOT DATE: Wed, 19 Oct 2016 PLOT TIME: 3:35 PM

FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-ASBT-SUBGRD-SOUTH-CAP-10-07-15.dwg PLOT DATE: Wed, 19 Oct 2016 PLOT TIME: 3:35 PM

MATCH LINE SHEET C-124




LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

SCALE IN FEET: 0 20 40 80

MATCH LINE SHEET C-122

NJ STATE PLANE COORDINATE SYSTEM (NAD83) W E

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER 12001511A

SHEET 2 OF 3 | DWG C-123 | PROJ 3480-10-0027 | DATE 2/11/16

BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"

VERIFY SCALE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

GEOMEMBRANE GRADING PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962


STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 7/12/16 | REVISED ASBUILT TOPO PER ENTACT'S COMMENTS | BSB | RTH |

DSGN | DR | CHK | APVD

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-ASBT-SUBGRD-SOUTH-CAP-10-07-15.dwg PLOT DATE: Wed, 19 Oct 2016 PLOT TIME: 3:34 PM

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER 12001511A

SHEET 3 OF 3
DWG C-124
PROJ 3480-10-0027
DATE 2/11/16
BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"
VERIFY SCALE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

GEOMEMBRANE GRADING PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 7/12/16 | REVISED ASBUILT TOPO PER ENTACT'S COMMENTS | BSB | RTH |

| DSGN | DR | CHK | APVD |
|---|---|---|---|
| | | | |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**ATTACHMENT F**
**LANGAN SA-6 SOUTH CAP**
**QUALITY ASSURANCE REPORT**
**PART 1**

**ATTACHMENT F**
**LANGAN SA-6 SOUTH CAP QUALITY ASSURANCE REPORT**

LANGAN

ENGINEERING & ENVIRONMENTAL SERVICES

Technical Excellence
Practical Experience
Client Responsiveness

# Cap Geosynthetic Quality Assurance (QA) Report

## Honeywell SA-6 South

SA-6 South
Jersey City, New Jersey
**Project Number: 100530001**

April 2016

Honeywell





# Cap Geosynthetic Quality Assurance (QA) Report (SA-6 South)

# for

# SA-6 South
# Jersey City, New Jersey

***Prepared For:***

**Honeywell International, Inc.**
**115 Tabor Road**
**Morris Plains, New Jersey 07950**

***Prepared By:***

**Langan Engineering and Environmental Services, Inc.**
**300 Kimball Drive**
**Parsippany, NJ 07054**

**April 2016**
**Langan Project No. 100530001**

LANGAN

# CAP GEOSYNTHETIC QUALITY ASSURANCE (QA) REPORT

***Prepared By:***
**Langan Engineering & Environmental Services, Inc.**
**300 Kimball Drive**
**Parsippany, NJ 07054**

Dan Bosworth
Senior Staff Engineer

Jeffrey Stoicescu, P.E.
Associate
New Jersey Professional Engineer License No. 24GE04504400

LANGAN

# ENGINEER'S CONSTRUCTION CERTIFICATION

I certify that the placement of the SA-6 South geosynthetics witnessed by myself, and / or a person under my direct supervision, was completed in compliance with the design documents.

Print Name: Jeffrey Stoicescu, P.E. Title: Senior Associate

Signature: Date: 10/14/2016



LANGAN

# TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 1**

**2.0 SA-6 SOUTH CAP CONSTRUCTION AND DOCUMENTATION ..... 2**

2.1 General ..... 2

2.2 Survey Control / Subgrade Elevations ..... 2

2.3 Soil Subgrade Preparation ..... 3

2.4 SA-6 South Cap Components ..... 4

*2.4.1 Geotextiles* ..... 4

*2.4.2 Geocomposite Venting Layer (GVL)* ..... 6

*2.4.3 Geosynthetic Clay Liner (GCL)* ..... 8

2.4.3.1 Bentonite Sand Plug ..... 9

2.4.3.2 GCL to Barrier Wall Connection Details ..... 10

2.4.4 60-mil Low Linear Density Polyethylene (LLDPE) Geomembrane ..... 10

2.4.4.1 Trial Weld Logs ..... 12

2.4.4.2 Non-Destructive Testing Results ..... 12

2.4.4.3 Destructive Testing Results ..... 13

2.4.4.4 Repair Reports ..... 15

2.4.4.5 Geomembrane Penetrations & Pipe Boot Installation ..... 16

*2.4.4.5.1 Monitoring Wells* ..... 17

*2.4.4.5.2 Gas Vents* ..... 17

*2.4.4.5.3 Piezometers* ..... 17

*2.4.4.5.4 Pump Station and Access Manholes* ..... 17

2.4.5 Geocomposite Drainage Layer (GDL) ..... 17

2.4.6 Non-Compliance Issues ..... 18

**3.0 DECLARATIONS ..... 20**

3.1 General ..... 20

3.2 Limitations ..... 20


## TABLES


Table 1 LLDPE Geomembrane Seam Property Requirements

Table 2 Summary of ESI / Langan QA Testing - Extrusion Welds


## FIGURES


Figure 1 Typical Soil Subgrade Approved for Geomembrane Placement

Figure 2 16 oz. Geotextile Placed Over HB Wall (southern end of SA-6 South)

Figure 3 16 oz. Geotextile / GVL Over SCB Wall (northern end of SA-6 South)

Figure 4 Typical Placement of GVL & Joining of the Net with Plastic Fasteners

Figure 5 Typical Sewing of GVL (for top layer of geotextile)

Figure 6 ESI Securing GCL with Staples

Figure 7 ESI Placing Granular Bentonite along GCL Seams

Figure 8 Typical Construction of Bentonite Sand Plug along HB Wall

Figure 9 Typical Construction of a Geomembrane Pipe Boot

Figure 10 ESI Conducting Sewing of Geotextile (GDL)

## APPENDICES


| | |
|---|---|
| Appendix A | Record Drawings |
| | *A1. GVL / GCL Record Drawing* |
| | *A2. LLDPE Geomembrane Record Drawing* |
| | *A3. GDL Record Drawing* |
| Appendix B | Langan CQA Plan |
| Appendix C | SA-6 South Certificate of Completion |
| Appendix D | Survey Construction Details |
| | *D1. Final Maser Subgrade Tables* |
| | *D2. Subgrade Construction Control Grid* |
| Appendix E | Soil Subgrade Approval |
| | *E1. ESI Certificate of Subgrade Surface Acceptance* |
| | *E2. Langan Certificate of Soil Surface* |
| Appendix F | Langan Daily Reports & Supporting Photo Logs |
| Appendix G | Receiving Inspection Reports (RIRs) |
| Appendix H | GCL to Barrier Wall Connection Logs |
| Appendix I | ESI Panel Placement Logs |
| Appendix J | ESI Trial Weld Logs |
| Appendix K | ESI Seam Control (Non-Destructive) Test Logs |
| Appendix L | ESI Repair Report |
| Appendix M | ESI Destruct Sample Information Logs |
| Appendix N | Laboratory Destruct Test Results |
| Appendix O | Penetration & Pipe Boot Logs |
| Appendix P | Summary of Non-Compliance & Corrective Action Sheets |

## LIST OF ACRONYMS

AO – Add-On
AOC – Area of Concern
BO – Burnout
CF – Custom Fit Repairs
CQA – Construction Quality Assurance
DCB – Design Change Bulletin
DO – Damage By Others
DS – Destruct Sample (Fusion)
DSX – Destruct Sample (Extrusion)
EOR – Engineer of Record
FS – Failed Seam
GCL – Geosynthetic Clay Liner
GDL – Geocomposite Drainage Layer
GVL – Geocomposite Venting Layer
HB – Hydraulic Barrier
IFC – Issued for Construction
LF – Linear Feet
LLDPE – Linear Low-Density Polyethylene
PB – Pipe Boot
PSI – Pounds per Square Inch
RCRA – Resource Conservation & Recovery Act
RFI – Request for Information
RAR – Remedial Action Report
RIR – Receiving Inspection Report
RP - Repair
RW – Roller Wrinkle
SA-6 – Study Area 6
SCB – Soil Cement Bentonite
SI – Subgrade Irregularity
SJ – Seam Joint
QA - Quality Assurance
QA Report – Cap Geosynthetic Quality Assurance Report
QC – Quality Control
WR - Wrinkle

## 1.0 INTRODUCTION

The purpose of this Cap Geosynthetic Quality Assurance Report (QA Report) is to present the observations made, and data collected during the construction of an engineered cap placed within the Study Area 6 (SA-6) South Open Space Area of Concern (AOC) located in Jersey City, New Jersey (Site). The capping activities at SA-6 South included the preparation of the soil subgrade, placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), linear low-density polyethylene (LLDPE) geomembrane, and a geocomposite drainage layer (GDL). Langan Engineering & Environmental Services, Inc. (Langan) was contracted by Honeywell International, Inc. (Honeywell) to provide independent Quality Assurance (QA) for the installation of the geosynthetic components of the cap.

The Chromium Remedy *100% Design* Issued for Construction dated June 2013, (*100% Design*) was prepared by AMEC Foster Wheeler Environment & Infrastructure, Inc. (Amec Foster Wheeler) on behalf of Honeywell, to address chromium contamination at SA-6 South. The *100% Design* required installation of a Resource Conservation and Recovery Act (RCRA) – equivalent geosynthetic cap system, including a venting layer for naturally occurring methane, covering approximately eight acres of the designated Open Space AOC. As part of this QA Report, the Record Drawings, which outline the placement and construction of the various geosynthetic components of the cap, have been provided as *Appendix A*. Other design details discussed herein, including the Issued for Construction (IFC) drawings, geosynthetics specifications, and geosynthetic products approved for this site are incorporated by reference only. Refer to Amec Foster Wheeler documents titled "*100% Design*," dated June 2013, and "*Remedial Action Report (RAR) for Chromium*" for these details.

This QA Report documents the results of the QA Geosynthetic activities conducted during the construction of the cap at SA-6 South by both Langan and Amec Foster Wheeler field personnel. Refer to the Construction Quality Assurance (CQA) Plan prepared by Langan in June 2015 (attached as *Appendix B*) for a description of the scope conducted by Langan, as well as the roles and responsibilities of the owner, Engineer of Record (EOR), earthwork contractor, and liner contractor. Design Change Bulletins (DCBs) and Requests for Information (RFIs) which were generated subsequent to the *100% Design*, and relevant to the QA scope were reviewed and approved by the EOR, and are further summarized in the EOR Closure Report.

This QA Report specifically includes the following documentation of the cap construction activities:

- The Record Drawings;
- Summary of the various phases of the work observed as part of this QA Report;
- Daily Reports indicating the work activities completed each day and other pertinent information;
- Daily cap construction forms submitted by the Geosynthetic Installer which includes: Repair Reports, Trial Weld Logs, Panel Placement Forms, Seam Control Forms, Destructive & Non-Destructive Test Forms, and Subgrade Approval Forms;
- Field testing results for fusion welds and extrusion welds;
- Laboratory testing results for the destructive samples collected (i.e., fusion & extrusion welds);

- Photographs depicting daily work activities and the various phases of the capping activities; and
- Independent QA's certification that the placement of the SA-6 South geosynthetics was implemented in general compliance with the design documents.

This QA Report addresses the cap construction of SA-6 South only. The cap construction at SA-6 North is proposed to commence in the spring of 2016 and will be addressed in a separate QA Report (to be provided upon completion of the SA-6 North cap).

## 2.0 SA-6 SOUTH CAP CONSTRUCTION AND DOCUMENTATION

### 2.1 General

This Section describes the construction methods used and the Quality Control (QC) and QA documentation completed as part of the construction of SA-6 South. This Section also provides the results of the QC and QA testing that was performed during field activities by Langan (QA Engineer), Environmental Specialties International (ESI) as the Geosynthetic Installer, and Entact, LLC (Entact) as the Construction Contractor and QC.

QA activities commenced on July 7, 2015, with Langan conducting observation of the soil subgrade preparation for the western end of SA-6 South (near the Hackensack River). Geocomposite / geotextile placement began on July 20, 2015 and continued until capping activities were completed by November 4, 2015. Relevant observations and QA/QC testing during this timeframe are defined further in this section. A project Certificate of Completion (completed and verified by Entact) certifying that the SA-6 South cap has been constructed and completed in compliance with the project drawings and technical specifications is attached as *Appendix C*.

### 2.2 Survey Control / Subgrade Elevations

Entact subcontracted Maser Consulting, P.A. (Maser), a licensed New Jersey land surveyor, who provided surveying services during the construction of the cap. Maser completed surveying of the cap from the initial subgrade preparation phases to the placement of the geomembrane. Maser surveyed the subgrade elevations of the cap prior to material placement and tabulated the survey results as compared to the design elevations on the construction control grid. These survey activities included:

1. Measurement of elevations of the subgrade surface in accordance with a pre-determined Construction Control Grid. Conformance to the design lines and grades was verified by Amec Foster Wheeler and Entact by comparing the actual elevations with the design elevations on the Construction Control Grid. The accepted subgrade elevations, and corresponding Construction Control Grid for SA-6 South are provided within *Appendix D1* and *Appendix D2*, respectively.
2. Measurement of the as-built conditions including the perimeter or termination of the geomembrane and geotextile over the hydraulic barrier (HB), and Soil Cement Bentonite

(SCB) wall, as well as, the location of the geomembrane repairs, boots / penetrations, and other pertinent information related to the construction of the cap.

3. The subgrade surface was observed to verify uniformity of grade between the construction control grid points.

This survey information is shown on the final Record Drawings attached in *Appendix A.* Amec Foster Wheeler provided QA review and verification of the Maser survey data.

## 2.3 Soil Subgrade Preparation

Soil subgrade preparation was required prior to the placement of the geotextile and the geomembrane in the areas to be capped. Soil subgrade preparation for the cap was completed by Entact using the following procedures:

- Step 1: Entact conducted rough grading of the subgrade surfaces with the use of track-mounted dozers to prepare the appropriate grades and to clear the surface of large objects (i.e. rocks, metals, debris, etc.);
- Step 2: The subgrade surface was fine-graded and compacted in accordance with the project specifications presented in the *100% Design* package. Subgrade sections not meeting survey or compaction requirements were re-worked by Entact until specified conditions were achieved. At the conclusion of this step, Entact provided a certification that the surface met the grading and compaction requirements. The certifications included the Construction Control Grid tabulation prepared by Maser (as defined in *Section 2.2*) and issuance of a Certificate of Subgrade Surface Acceptance as defined in further detail below;
- Step 3: When precipitation was forecast, the prepared subgrade surface was temporarily covered with a polyethylene plastic sheet to protect the soil from overnight precipitation; and
- Step 4: The subgrade surface would be uncovered in approximate 100 ft. sections (moving from west to east across SA-6), followed by extra fine grading conducted by laborers who cleared the surface of extraneous materials greater than ½-inch in diameter, followed by repair and re-compaction of any areas that became inadvertently wetted.

Entact and ESI also conducted their own observation of the subgrade surface to confirm if the surface was acceptable for the placement of the geosynthetic material. Upon notification by Entact that the grading was acceptable, Langan conducted an independent observation to identify that the subgrade was prepared in general accordance with the *100% Design*.

If the soil subgrade surface was deemed acceptable with no additional re-work required, the Langan QA and Entact QC representative signed and submitted an acceptance form for the approved subgrade. The daily QA subgrade approval forms are provided in *Appendix E*, with the ESI Certificate of Subgrade Surface Acceptance forms provided in *Appendix E1*, and the Langan Certificate of Soil Surface provided in *Appendix E2.* In the event the subgrade surface was not

deemed acceptable, Steps 2, 3, and 4 outlined above were repeated until an acceptable subgrade surface was achieved (based on conditions outlined in the Langan Certificate of Soil Surface forms) and confirmed by Langan and Entact.

*Figure 1* below shows a typical section of subgrade approved for geomembrane placement. Additional photos and summaries of the subgrade preparation activities conducted each day are presented in the Daily Reports and Daily Photo Logs provided in *Appendix F.*

**Figure 1 – Typical Soil Subgrade Approved for Geomembrane Placement**



## 2.4 SA-6 South Cap Components

### *2.4.1 Geotextiles*

After approval of various sections of the subgrade surface, a 16 oz. geotextile layer was placed over the HB and SCB barrier walls around the perimeter of the capped area. According to the *100% Design* package, this geotextile layer was designed to protect the 60-mil LLDPE geomembrane from potential puncture damage from the perimeter barriers / walls. The approved 16 oz. non-woven geotextile fabric layer (i.e., defined as SKAPS GE-116 in Amec Foster Wheeler's *EOR Closure Report*) was delivered to the project site, offloaded, and staged onsite by Entact. For each delivery, Amec Foster Wheeler prepared a Receiving Inspection Report (RIR) to document receipt of acceptable materials. The RIRs outlining the date, material, quantity, and other pertinent details of the geotextile rolls delivered to the Site are provided in *Appendix G*.

The 16 oz. geotextile was installed by ESI at locations shown on the Record Drawings. Geotextile was placed along the boundaries of SA-6 South over the HB and SCB wall located along the western, northern, southern, and eastern boundaries of the cap. The 15 ft. wide geotextile panels were placed with approximately 13 ft. inbound of the perimeter of the HB and SCB walls, along with 2 ft. of geotextile extending outbound of the perimeter containment walls.

Geotextile panels were overlapped at least 12-inches and seamed using a dual hot wedge welder that melted the two surfaces together to form a bond (also referred to as leistering). The 16 oz. geotextile was placed along the boundary areas of SA-6 at locations above the Site water table (i.e. locations where geosynthetic clay liner was not required). The geotextile (on the interior of the Cap) overlapped the geocomposite venting layer and was leistered in place following the procedure outlined above. *Figure 2* below shows the 16 oz. geotextile being placed over the HB wall (southern end of SA-6 South cap), and *Figure 3* shows the geotextile overlapping the GVL Note, the GVL roll was placed in a general north to south direction across SA-6, while the 16 oz. geotextile roll was placed in a general east to west direction.

**Figure 2 – 16 oz. Geotextile Placed Over HB Wall (southern end of SA-6 South)**



**Figure 3 – 16 oz. Geotextile / GVL Over SCB Wall (northern end of SA-6 South)**



### *2.4.2 Geocomposite Venting Layer (GVL)*

Prior to placement of the 60-mil LLDPE geomembrane, GVL was placed over the soil subgrade at locations above the water table to serve as a venting layer for naturally occurring methane that may emanate from below the cap.

The approved GVL (i.e., defined as SKAPS TN-220-2-6 in *EOR Closure Report*) consisted of an extruded polyethylene drainage net structure (or geonet) sandwiched between two non-woven geotextile layers. The GVL was delivered to the Site, offloaded, and staged onsite by Entact. The RIRs for the GVL delivered to the Site are provided in *Appendix G*.

The GVL was placed by ESI, over the approved soil subgrade for areas above the Site water table at locations shown on the Record Drawings (*Appendix A1*).

The GVL rolls were typically oriented in a north to south direction. The leading edge of the GVL panels was held in place by sand bags until the subsequent panels could be placed and seamed. The placement strategy for this material was to limit the amount of GVL to be placed in a day, to an area that could also be covered by the LLDPE geomembrane that day. This strategy was used to minimize the risk of the GVL and underlying subgrade from becoming wet during overnight rain events. GVL panels were not placed during precipitation events, in the presence of excessive moisture, or during high winds.

GVL panels were placed according to Section 02380 – Gas Venting System as defined in *100% Design* package. GVL was generally placed with the predominant flow direction towards the edge of the cap with the GVL running parallel to any slopes or elevation changes (i.e. running up/down the slope and not across the slope). For adjacent GVL panels, the following minimum seaming requirements were met:

- Adjacent rolls of GVL were placed so that the geonet overlapped by 2 to 3-inches, and the geotextiles overlapped by at least 4-inches;
- The bottom layer of geotextile (underneath the geonet) was overlapped to ensure that no areas of the soil subgrade were exposed;
- White plastic fasteners were placed at a maximum of every 5 ft. along the seam to connect adjacent pieces of GVL. Additional fasteners were requested by the QA team when the seams extended down slopes or at significant subgrade elevation changes. *Figure 4* below shows placement of the white plastic fasteners; and
- Once the geonet was tied with a sufficient number of fasteners, the top geotextile of the GVL was continuously sewn as shown in *Figure 5* below.

**Figure 4 – Typical Placement of GVL & Joining of the Net with Plastic Fasteners**



**Figure 5 – Typical Sewing of GVL (for top layer of geotextile)**



During placement of the GVL, butt seams, rips, tears, or other damaged areas of the GVL were repaired by exposing an appropriate area of geonet, placing fasteners as defined in the project specifications, and covering the area with a new piece of geotextile which was leistered in-place. Additional details of the GVL placement are further described in the Langan Daily Reports and Photo Logs provided in *Appendix F*.

### *2.4.3 Geosynthetic Clay Liner (GCL)*

The approved GCL consisted of granular sodium bentonite clay sandwiched between, supported, and encapsulated by two geotextiles, and held together by needled punching. The approved GCL (i.e., Cetco Bentomat DN) was delivered to the Site, offloaded, and staged onsite by Entact. The RIRs for the GCL rolls delivered to the Site are provided within *Appendix G*.

The approved GCL was deployed by ESI in accordance with Section 02375 – Geosynthetic Clay Liner as defined in the *100% Design* package. GCL was placed directly over the approved soil subgrade, at locations situated below (to 1 ft. above) the Site water table. These areas generally consisted of: the bottom of utility corridors, the bottom of drainage swales and Site elevation changes, and the eastern end of SA-6 South (where the subgrade is depressed to allow the surface grading to tie in with Route 440). These locations are shown on the Record Drawings.


For areas where the edges of the GCL terminated on a slope, staples were used to secure the GCL in place as shown below in *Figure 6*. The staples were placed along the top 6-inches of the GCL edge and were placed through the GCL and secured into the underlying soil subgrade. The GVL overlapped the edge of the GCL a minimum of 12-inches and was then leistered to the GCL. When staples were used, the GVL was placed over the staples (at least of 1 ft. of overlap), to mitigate the potential of the staples coming in contact with the geomembrane.

**Figure 6 – ESI Securing GCL with Staples**



During placement of the GCL, granular bentonite was placed along the GCL seams as outlined in the project specifications and shown on *Figure 7* below. No GCL was placed during precipitation, in the presence of excessive moisture, or during high winds.

**Figure 7 – ESI Placing Granular Bentonite along GCL Seams**



Additional details on the placement of the GCL are further described in the Langan Daily Reports and supporting photo logs provided in *Appendix F*.

#### *2.4.3.1 Bentonite Sand Plug*

As outlined in specification Section 02375 – Geosynthetic Clay Liner of the *100% Design* package, a sand bentonite plug was constructed on the inboard side of the HB wall for the low-lying areas (below the Site groundwater table) along the edges of SA-6 South. This bentonite sand plug was constructed in the field by Entact by mixing clean sand with sodium montmorillonite at a 90% sand to 10% bentonite ratio.

The plug was constructed to a depth of approximately 18-inches below the HB wall elevation, and was approximately 2 ft. thick. Additional details on the edge connection details are provided below in *Section 2.4.3.2*. *Figure 8* below also shows the typical construction of the bentonite sand plug along the HB wall.

**Figure 8 – Typical Construction of Bentonite Sand Plug along HB Wall**



#### *2.4.3.2 GCL to Barrier Wall Connection Details*

GCL to Barrier Wall Logs are provided within *Appendix H*. As per the approved Langan CQA Plan, Amec Foster Wheeler completed a GCL to Barrier Wall (HB Wall & SCB) Connection Detail form for the low-lying areas of SA-6 South (below the Site water table). This form documented that the bentonite sand plug was appropriately constructed, that the barrier wall was clean and exposed, and that the appropriate GCL overlap (1 ft. minimum) was maintained.

### 2.4.4 60-mil Low Linear Density Polyethylene (LLDPE) Geomembrane

A textured LLDPE geomembrane manufactured to a nominal 60-mil thickness was placed over the GVL and GCL layers at the Site to mitigate groundwater infiltration through the cap. The rolls of the approved 60-mil LLDPE geomembrane were delivered to the Site, offloaded, and staged onsite by Entact. The RIRs for the LLDPE geomembrane are provided in *Appendix G*.

The 60-mil LLDPE geomembrane was placed directly over the GVL and GCL geotextiles. The 60-mil geomembrane was placed in accordance with specification Section 02372 – Cap Geomembrane Liner as defined in the *100% Design* Package. The location and placement of the LLDPE panels is documented on the ESI Panel Placement Logs provided in *Appendix I*.

ESI deployed the geomembrane rolls in a general north to south orientation. Hand clamps were used on the edge of the panels to aid in the final positioning, as required. The leading edge of the LLDPE geomembrane panels were held in place by sand bags until the subsequent panels

could be placed and seamed via fusion welding methodology. The number of panels deployed in a single day was limited to the amount that could be field seamed that day. No panels were placed during precipitation, in the presence of excessive moisture, or during high winds. The minimum temperature for seaming was specified as 32°F, with a maximum temperature of 104°F. No cold or hot weather seaming was conducted as temperatures did not reach below 32°F, or above 104°F during geomembrane installation.

Each individual LLDPE panel was observed for damage by ESI, Entact, and Langan during the installation process. Prior to seaming, the approved geomembrane was observed by Langan to ensure that the material was free of defects or damage prior to seaming. Areas observed to be damaged / defective, or areas where the geomembrane had to be custom cut to conform to the subgrade contours, were marked for repair. Repairs were completed in the field by ESI via patching and welding the geomembrane as further described below. All repairs were documented and recorded on the Record Drawings (*Appendix A2*). Additional details on the repair methodology and types of repairs are further described in *Section 2.4.4.4*.

The LLDPE geomembrane was seamed in the field by two welding methods: extrusion and double-fusion. Extrusion welding was used for repairs, short seams, and areas where the double fusion could not operate. Extrusion welding was performed with a hand held extrusion welding gun. The double-fusion seaming (fusion welding) was performed using a self-propelled "wedge welder" which formed an air channel between the two seams. Fusion welding was performed with a minimum of 4-inches overlap as per the project specifications.

The integrity of the welds was monitored by both destructive and non-destructive test methods. The destructive testing consisted of collecting samples from the completed seams at a minimum frequency of one sample per 500 ft. of weld (for both fusion and extrusion welds). A representative of Langan was onsite to confirm the locations of the destructive samples along with a representative of ESI.

The destructive samples were analyzed by Geotechnics, Inc. (Geotechnics) the Contractor's Material Quality Control Laboratory. Langan also collected additional QA samples (approximate 15% of total samples collected) and submitted samples to TRI Environmental, Inc. (TRI) for independent QA testing. Destructive sample locations were repaired in the field and tested with a vacuum box. All destructive sample locations have been recorded and are shown on the Record Drawings (*Appendix A2*). The laboratory results of the destruct samples are discussed further in *Section 2.4.4.3* below.

In addition to the destructive testing, non-destructive testing was completed by ESI during cap construction. Two types of non-destructive tests were used at the Site: air channel tests (pressure tests) and vacuum box tests as defined further below:

1. Pressure Testing - The pressure tests were conducted on 100% of all the double fusion welded seams where both ends of the seam were clamped and sealed and a pressure needle was inserted into the air channel. The air channel was then pressurized to thirty pounds per square inch (psi) and the pressure was maintained for a minimum of five minutes. If the pressure did not stabilize, or a pressure drop greater than four psi was noted over a five minute span, then the seam was deemed unacceptable and the faulty

area was isolated and repaired. Results of the non-destructive testing are discussed further in *Section 2.4.4.2* below.

2. Vacuum Box Testing - For patch / repair work and other areas where extrusion welding was required, the extrusion welds were vacuum box tested by ESI. A soapy solution was applied to the weld area, and a vacuum box was placed over the weld for a minimum of ten seconds and observed for the appearance of soap bubbles. Any areas where these bubbles appeared were marked, repaired, and retested. Any areas that failed the vacuum box test were identified as a non-compliance issue and are discussed further in *Section 2.4.6* below.

At seams or locations where vacuum box or pressure testing could not be conducted (i.e. boot penetrations), the extrusion welds were visually inspected by observing the welding process and checking the weld for uniformity and completeness. Individual forms were generated to document the installation of each boot / penetration. Additional details on the pipes / penetrations encountered on the cap are further described in *Section 2.4.4.5*.

For additional details on the geomembrane placement, destructive and non-destructive testing, patch / repair work, and other geomembrane related construction activities, refer to the Langan Daily Reports and Photo Logs provided in *Appendix F*.

#### *2.4.4.1 Trial Weld Logs*

Prior to any seaming of the geomembrane each day, the fusion and/or extrusion welding equipment was used to conduct trial welds (or test strips) to confirm that the material and equipment met the specification requirements. Test strips were collected (using the same 60 mil LLDPE geomembrane placed across the cap) by completing a sample fusion or extrusion weld. This activity included producing several types of seams to qualify that a specific seamer and apparatus would yield the desired specified performance requirements. These seam types included: smooth-to-smooth, smooth-to-textured, and textured-to-textured. It should be noted that the 60 mil geomembrane installed across the cap was textured (60-mil Microspike); however, the manufacturer's product has a smooth edge for welding.

The trial welds were cut and tested on a portable tensiometer by ESI. Langan and Entact observed the trial weld tests to confirm that the minimum peel and shear values were obtained (as per specification Section 02372 – Cap Geomembrane Liner defined in the *100% Design* package). These trial welds were completed prior to commencement of seaming at the start of each day, and once every four hours. The results of daily trial weld logs are provided in *Appendix J*.

#### *2.4.4.2 Non-Destructive Testing Results*

Non-Destructive Pressure Testing was conducted along the geomembrane panels, and the repaired / patched areas (i.e., using vacuum box testing) by ESI, as per the project specifications. The results of the non-destructive testing for each of the panel seams were provided in the Seam Control Logs shown in *Appendix K*. Additionally, the associated repairs

and the corresponding vacuum box testing results are presented in the ESI Repair Report attached in *Appendix L*.

During the construction of the cap at SA-6 South, there were two non-destructive tests (one pressure test and one vacuum box test) that failed during the field testing which consisted of the following:

1. Failed non-destructive (pressure) test for geomembrane panel seams Panel #7 / Panel #8 and identified as Repair (RP)-13 (as shown on the Record Drawings); and
2. Failed non-destructive test (vacuum box test) for repair RP-215 (Panel #50).

Both of these failures were subsequently repaired by ESI in general accordance with specification Section 02372 – Cap Geomembrane Liner and were documented as non-compliance issues which are further described in *Section 2.4.6* below.

#### *2.4.4.3 Destructive Testing Results*

Destructive testing was conducted for the fusion and extrusion welding that was completed along the edge of the geomembrane panels. Destruct samples were collected at a minimum sampling interval of 500 linear feet (LF) of seaming length for the initial twenty-five (25) samples. The locations of the destruct samples were identified in the field by the Independent QA Monitor (Langan) and are shown on the Record Drawings (*Appendix A2*). Once the destruct sample locations were determined, ESI cut and tested the destruct samples (as per the project specifications).

Six 1-inch wide specimens were cut from the destruct sample for field testing. These samples were then tested by a tensiometer equipped with a drive/pull apparatus rate of 20-inches per minute. Three of the specimens were tested for peel strength, and the remaining three for shear strength. The samples were tested to confirm that the geomembrane met the specified peel and shear strength values outlined in *Table 1* below. Additional details on the test results are provided on the Destructive Sample Information Logs attached as *Appendix M.*

**Table 1 – LLDPE Geomembrane Seam Property Requirements**

| Property | Test Method | 60-mil LLDPE Value |
|---|---|---|
| Shear Strength (min. avg.) | ASTM D 6392 | 90 lb/in |
| Peel Strength – Extrusion (min. avg.) | ASTM D 6392 | 66 lb/in |
| Peel Strength – Fusion (min. avg.) | ASTM D 6392 | 75 lb/in |

In addition to the field testing completed by ESI, a total of twenty-nine (29) fusion weld destruct samples, and fifteen (15) extrusion weld samples were sent to Geotechnics for lab verification.

A total of twenty-nine (29) fusion weld destruct samples (DS-1 through DS-29) were collected during the capping of SA-6. For the first 25 QA samples collected, all samples met the specified destructive testing requirements outlined in *Table 1*. As per the specification, the frequency of fusion weld destruct sampling was reduced from every 500 LF of welded seam to every 1,500 LF of welded seam. A summary of the peel and shear QA testing conducted for the 29 fusion weld samples collected is summarized in *Appendix N*.

A total of fifteen (15) extrusion destruct samples were collected throughout the capping of SA-6 South. *Table 2* below summarizes the results of the extrusion weld destruct samples collected as well as the corresponding laboratory data, peel and shear averages, and compliance with specification Section 02372 – Cap Geomembrane Liner outlined in the *100% Design* package.

**Table 2 – Summary of ESI / Langan QA Testing - Extrusion Welds**

| Honeywell SA-6 Capping | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| *Comparison of ESI / Langan (QA) Destruct Samples - Extrusion Welds* | | | | | | | | | | |
| ***Sample ID*** | ***Weld Type*** | ***Submitted By:*** | ***Test*** | ***Peel Strength (ppi)*** | | | | | **Avg. Strength (ppi)** | ***Meets Spec Requirement*** |
| EXT-DS-1 | Extrusion | Langan | Peel | 97 | 97 | 127 | 130 | 128 | **116** | **Yes** |
| DSX-1 | | Entact | Peel | 109.3 | 107.5 | 109.8 | 120.5 | 110 | **111.4** | **Yes** |
| EXT-DS-1 | | Langan | Shear | 133 | 172 | 148 | 181 | 146 | **156** | **Yes** |
| DSX-1 | | Entact | Shear | 115.7 | 119.8 | 118.1 | 117.5 | 116.2 | **117.5** | **Yes** |
| DSX-2 | Extrusion | Entact | Peel | 133.5 | 118.8 | 126.4 | 120.1 | 115.4 | **122.8** | **Yes** |
| | | | Shear | 132.7 | 150.3 | 145.5 | 135.4 | 130.3 | **138.8** | **Yes** |
| DSX-3 | Extrusion | Entact | Peel | 123.7 | 117.2 | 117.9 | 119.1 | 120.2 | **119.6** | **Yes** |
| | | | Shear | 126 | 128.6 | 125.1 | 124.5 | 125.1 | **125.9** | **Yes** |
| DSX-4 | Extrusion | Entact | Peel | 128.4 | 132.1 | 133.5 | 134.4 | 139.5 | **133.6** | **Yes** |
| | | | Shear | 144.7 | 143.7 | 141.8 | 150.7 | 145.7 | **145.3** | **Yes** |
| DSX-5 | Extrusion | Entact | Peel | 107.5 | 115.8 | 111.6 | 113.9 | 119.3 | **113.6** | **Yes** |
| | | | Shear | 131.7 | 136.9 | 151.8 | 137 | 149.5 | **141.4** | **Yes** |
| DSX-6 | Extrusion | Entact | Peel | 151.4 | 144.8 | 130.9 | 139.9 | 150.1 | **143.4** | **Yes** |
| | | | Shear | 164.9 | 162.3 | 151.5 | 155.6 | 159.7 | **158.8** | **Yes** |
| DSX-7 | Extrusion | Entact | Peel | 123.7 | 126.8 | 128.7 | 122.2 | 120.7 | **124.4** | **Yes** |
| | | | Shear | 134.6 | 133.7 | 134.8 | 136.2 | 135.5 | **135.0** | **Yes** |
| DSX-8 | Extrusion | Entact | Peel | 129.6 | 119.5 | 124.3 | 130.9 | 120 | **124.9** | **Yes** |
| | | | Shear | 131.6 | 130.7 | 129.7 | 134.4 | 127.8 | **130.8** | **Yes** |
| DSX-9 | Extrusion | Entact | Peel | 108.7 | 124.4 | 120.8 | 112 | 111.6 | **115.5** | **Yes** |
| | | | Shear | 132.8 | 126.8 | 133.9 | 116.1 | 122.8 | **126.5** | **Yes** |
| DSX-10 | Extrusion | Entact | Peel | 118.7 | 122.1 | 118.1 | 120.8 | 136.1 | **123.2** | **Yes** |
| | | | Shear | 123 | 145.2 | 149.5 | 130.7 | 145.6 | **138.8** | **Yes** |
| DSX-11 | Extrusion | Langan | Peel | 125 | 134 | 123 | 121 | 124 | **125** | **Yes** |
| | | Entact | Peel | 125.1 | 118.2 | 125.9 | 123.3 | 120.6 | **122.6** | **Yes** |
| | | Langan | Shear | 164 | 157 | 141 | 137 | 142 | **148** | **Yes** |
| | | Entact | Shear | 122.6 | 124.6 | 126.1 | 127.9 | 128.2 | **125.9** | **Yes** |
| DSX-12 | Extrusion | Entact | Peel | 130.4 | 121.3 | 148.4 | 118.2 | 138.9 | **131.4** | **Yes** |
| | | | Shear | 126.2 | 123.7 | 125 | 124.2 | 122.7 | **124.4** | **Yes** |
| DSX-13 | Extrusion | Entact | Peel | 117 | 97.9 | 123.5 | 66 | 55.6 | **92.0** | **No** |
| | | | Shear | 131.2 | 129 | 133 | 132.9 | 124.6 | **130.1** | **Yes** |
| DSX-14 | Extrusion | Entact | Peel | 119 | 119.7 | 118.8 | 123.3 | 122.6 | **120.7** | **Yes** |
| | | | Shear | 120.9 | 121.4 | 121.7 | 129.5 | 127.4 | **124.2** | **Yes** |
| DSX-15 | Extrusion | Entact | Peel | 119.5 | 114.1 | 123.8 | 111.4 | 106.8 | **115.1** | **Yes** |
| | | | Shear | 132.1 | 135.2 | 138.5 | 137.4 | 141.7 | **137.0** | **Yes** |

As highlighted above on *Table 2*, one destruct sample DSX-13 failed to meet the peel strength criteria for one of the five specimens tested. While the average of the five specimens tested for this specimen did comply with the project specifications, the extrusion weld in this area was designated as non-compliant. As such, the weld was subsequently patched, repaired, and re-tested and documented as Repair RP-487 in *Appendix L*. An additional extrusion weld destruct sample was collected and labeled as DSX-15. Additional details on this non-compliance issue are described in further detail in *Section 2.4.6*.

In addition, Langan collected a total of six QA samples (4 fusion weld samples and 2 extrusion weld samples) to verify the results of the Geosynthetic Installer's laboratory data. Langan's QA

samples were submitted to Texas Research Institute Environmental, Inc. (TRI). The results of the ESI and Langan destruct samples indicated that the peel and shear strength values met the requirements outlined in the project specifications. Furthermore, the additional QA samples collected by Langan yielded values that were in close proximity to the values obtained by ESI (which were generally lower than the values obtained by Langan's QA laboratory). The Laboratory Destruct Test Results are provided in *Appendix N*.

#### *2.4.4.4 Repair Reports*

The ESI Repair Report is provided in *Appendix L*. Several different types of repairs were observed and recorded during field activities by ESI. These corresponding repairs are shown on the Record Drawings (*Appendix A2*), and consisted of the following types:

- Custom Fit Repairs (CF) – Custom Fit Repairs consisted of areas of the geomembrane cap where the geomembrane was cut (and subsequently repaired) to allow the geomembrane to conform to the cap contours. These areas were typically located where there were abrupt elevation changes, such as drainage and utility swales, utility corridors, and planting areas;
- Wrinkles (WR) – Wrinkles consisted of areas where excess geomembrane was observed. Where the size of the wrinkle was determined to be detrimental to the geomembrane (i.e. wrinkles with the potential for folding), the wrinkle was cut, and the excess geomembrane was overlapped and sealed with an extrusion weld in accordance with the project specifications;
- Roller Wrinkles (RW) & Burnouts (BO) – Roller wrinkles can occur when slight differences in length between the two geomembrane edges being welded resulted in formation of a wrinkle along the geomembrane seam. Wedge burnouts occurred where the wedge became jammed thus causing the welder to burn / melt through the geomembrane seam. These areas were subsequently patched and repaired according to the project specifications;
- Destruct Samples (DS) – These areas consisted of the geomembrane destruct samples that were cut for laboratory testing. The removal of the sample creates a hole in the seam, thus these areas were subsequently patched according to the project specifications;
- Pipe Boots (PB) – Pipe boots were installed where penetrations of the geomembrane occurred such as at wells, piezometers, gas vents, and access manholes. Additional details are provided in *Section 2.4.4.5;*
- Add On (AO) – AO areas consisted of sections of SA-6 where an additional piece of geomembrane was required to finish a geomembrane run across the cap (from north to south);
- Seam Joints (SJ) – Seam joints consisted of the areas where non-destructive testing (pressure testing) was conducted along a "T" section of the geomembrane;
- Subgrade Irregularities (SI) – Subgrade Irregularities consisted of areas along the geomembrane cap where a rock or object larger than ½-inch in diameter was encountered underneath the geomembrane after the material had been placed. These

areas were subsequently cut, the rock/debris removed, and the area patched / repaired according to the project specifications. These SIs were identified as non-compliance issues and are discussed in further detail in *Section 2.4.6* below;

- Damage By Others (DO) – DO consisted of damage / punctures to the geomembrane cap caused by equipment or personnel during grading of the protective cover soil. These DO instances were identified as non-compliance issues and are discussed in further detail in *Section 2.4.6* below.
- Failed Seam (FS) – Failed seams consisted of fusion / extrusion weld samples that were collected, and failed to meet the strength criteria of the material as outlined in Section 02372 – Cap Geomembrane Liner presented in the *100% Design* Package (and summarized in *Table 1*). These FS instances were identified as non-compliance issues and are further described in *Section 2.4.6* below.


For additional details on the geomembrane repairs and non-compliance issues observed during field activities refer to the *Appendices L and P,* respectively.

#### *2.4.4.5 Geomembrane Penetrations & Pipe Boot Installation*

The geomembrane penetration and pipe boot logs are provided in *Appendix O*. The pipe boots were field fabricated by ESI, and the boots were installed at monitoring wells, gas vents, piezometers, and access manhole penetrations across the cap.

The geomembrane boots consisted of a vertical (minimum of 2 ft.) section of LLDPE being wrapped around the penetration (i.e. well, gas vent, etc.) from the base to the top of the penetration. The geomebrane wrap was then heat sealed and an extrusion weld was placed with a vertical seam connecting the two pieces of geomembrane. The end of the boot terminated in a skirt section which was placed over the boot. The skirt and the geomembrane overlapped a minimum of 18-inches and the skirt was welded to the geomembrane. A neoprene rubber gasket was used between the boot and the penetration and secured with a 1-inch wide stainless steel clamp (or two ½-inch clamps). An LLDPE sacrificial sheet was then placed between the boot and the clamp for protection and a butyl sealant was applied along the top of the boot. *Figure 9* below shows the typical construction of a geomembrane pipe boot in the field by ESI. The welding of each boot was observed by Langan, and each boot fabrication was documented on an individual boot fabrication form provided in *Appendix O*. The four typical types of penetrations present on the SA-6 South cap are defined below.

**Figure 9 – Typical Construction of a Geomembrane Pipe Boot**



*2.4.4.5.1 Monitoring Wells*

A total of four (4) monitoring wells were located within the SA-6 South cap. The monitoring wells were constructed with PVC and were encased in a 4-inch metal casing. Refer to *Appendix O* for the penetration and boot logs for monitoring wells: 073-MW-1BR, 115-E1A-SO, 115-W3-SO, and 115-W5-SO.

*2.4.4.5.2 Gas Vents*

A total of eight (8) gas vents were constructed through the cap. Gas vents were completed in accordance with Section 02380 – Gas Venting System of the *100% Design* Package to allow any naturally occurring methane to vent to the atmosphere. Refer to *Appendix O* for the penetration and boot logs for gas vents GV-0 through GV-7, with the corresponding locations shown on the Record Drawings (*Appendix A2*).

*2.4.4.5.3 Piezometers*

A total of five (5) piezometers were installed through the cap to allow the project team to compare the groundwater within capped area to the groundwater immediately outside of the cap. Piezometers were encased within a 4-inch steel casing. Refer to *Appendix O* for the penetration and boots logs for piezometers PZ-12, PZ-14, PZ-16, PZ-18, and PZ-20, and to the Record Drawings (*Appendix A2*) for the corresponding piezometer locations.

*2.4.4.5.4 Pump Station and Access Manholes*

A total of one pump station and three (3) access manholes were completed with field fabricated geomembrane boots. Refer to *Appendix O* for the penetration and boot logs for Access Manhole #1, Access Manhole #2, Access Manhole #3, and Access Manhole #4, with the corresponding locations shown on the Record Drawings (*Appendix A2).*


### 2.4.5 Geocomposite Drainage Layer (GDL)

To facilitate drainage and transport of infiltrated surface water off the cap, a geocomposite drainage layer (GDL) consisting of a geonet with a non-woven geotextile bonded to both sides (i.e., defined as SKAPS TN 330-2-6 ) was delivered to the Site, offloaded, and staged onsite by Entact in accordance with the project specifications. The RIRs for the delivered GDL rolls are provided in *Appendix G*. The GDL was placed at the Site by ESI and was placed directly over the geomembrane cap as shown on the Record Drawings (*Appendix A3*).

GDL panels were placed according to the specification Section 02374 – Geocomposite Drainage Layer as defined in the *100% Design* package. For adjacent GDL panels, the following minimum seaming requirements were met:

- Adjacent rolls of GDL were overlapped so that the geonet overlapped by 2 to 3-inches, and the geotextiles overlapped by at least 4-inches;
- The bottom layer of geotextile (underneath the geonet) was overlapped so that no areas of the underlying geomembrane were exposed;
- White plastic fasteners were placed at a maximum of every 5 ft. along the seam. Additional fasteners were requested by the QA team when the seams extended down the slopes or elevation changes were noted; and
- Once the geonet was tied with a sufficient number of fasteners, the top geotextile of the GDL was continuously sewn as shown in *Figure 10* below.

**Figure 10 – ESI Conducting Sewing of Geotextile (GDL)**



During placement of the GDL, butt seams, rips, tears, or other damaged areas of the GDL were repaired by exposing an appropriate area of geonet, placing fasteners as defined in the project specifications, and covering the area with a new piece of orange geotextile (same as the GDL geotextile) which was heat sealed in place.

Once the GDL was placed, Entact placed protective cover soil (i.e., 1 ft. layer of material) directly over the GDL. In addition, yellow caution tape was placed every 55-inches over the GDL prior to protective cover soil placement. The caution type had bold type which indicated "Danger Do Not Dig – Peligro No Excavar" in English and Spanish. Additional details on the GDL placement are provided in the Langan Daily Reports and Photo Logs provided in *Appendix F*.

### 2.4.6 Non-Compliance Issues

The Summary of Non-Compliance & Corrective Action Sheets are provided in *Appendix P*. During the SA-6 capping activities, any QA field tests, observations, or failed samples that did not comply with the project specifications were documented and recorded as a non-compliance issue. A total of twelve (12) non-compliance issues were identified throughout the capping of SA-6 South and are summarized below:

1. Subgrade Irregularities – Refer to Sheet Numbers 1, 2, 4, 6, and 8 of the Non-Compliance & Corrective Action Sheets (*Appendix P*). In general, the subgrade irregularities consisted of stones or other material greater than ½-inch in size that was encountered below the geomembrane cap after the material had been placed and

secured. These objects were removed by cutting the geomembrane, removing the object, and patching the geomembrane in accordance with the project specifications. The subgrade showed no indication of these items at the time of subgrade approval, and it is postulated that these items were dislodged from the subgrade as the GVL was drawn across the subgrade surface;

2. Subgrade Irregularity (Hydrated GCL) – Refer to Sheet Numbers 7, 9, and 10 (*Appendix P*). In general, the Hydrated GCL Subgrade Irregularities consisted of areas where the underlying GCL layer had become saturated following heavy rain events. The saturation of the GCL was due to the unfinished grading of the SA-6 cap, as well as equipment failures, which resulted in water ponding along the edges of the cap during high intensity rain events. This ponding caused the water to move laterally across limited portions of the cap thus wetting the GCL layer prior to cover soil placement. For these areas, the geomembrane was cut to expose the GCL followed by replacement of the wetted GCL. Visual observation of the underlying subgrade soils exhibited no damage or washout of the subgrade. Repair activities were conducted so that the resulting materials were placed in accordance with the project specifications;
3. Failed Vacuum Box Test – Refer to Sheet Number 5 (*Appendix P*). During vacuum box testing of repair RP-215, a failed extrusion weld was identified. As such, a new geomembrane patch (RP-222) was placed over the failed extrusion weld, and subsequently tested using the vacuum box to verify the integrity of the new weld;
4. Failed Non-Destruct Test – Refer to Sheet Number 3 (*Appendix P*). A failed non-destruct test (pressure test) was encountered along Panel Seams #7/8. Based on the length of the failed seam (approximately 6 ft. along the southern end of SA-6), the entire seam was patched and repaired (approximate 2 ft. by 6 ft. patch). Vacuum box testing was then conducted to confirm the integrity of the new extrusion welds;
5. Failed Destruct Sample – Refer to Sheet Number 11 (*Appendix P*). Extrusion weld destruct sample DSX-13, which was collected from repair RP-477, failed one of the five test specimens for peel strength testing (Note: averages of the five specimens conformed to the project specifications). A new patch was placed over RP-477, and was identified as a Failed Seam (FS). It should be noted that the new patch was identified as repair RP-486. Once completed, an additional extrusion weld destruct sample (DSX-15) was collected to confirm the new patch met the specification requirements. Subsequent laboratory testing confirmed that the DSX-15 destruct sample complied with the project specification strength requirements; and
6. Geomembrane Puncture (Equipment) – Refer to Sheet Number 12 (*Appendix P*). During final grading of the protective cover soil by Entact, an excavator bucket punctured the geomembrane liner along the northern end of SA-6 South (along the SCB Wall). This puncture was subsequently repaired / patched, welded, and vacuum box tested by ESI, according to the project specifications. The repair associated with the puncture was identified as repair RP-488, and was listed as Damage by Others (DO).

Additional details on the non-compliance issues encountered, as well as the subsequent repair activities, are further described in the Langan Daily Reports and Photo Logs provided in *Appendix F*.

# 3.0 DECLARATIONS

## 3.1 General

Langan personnel have monitored the construction and field activities completed for the capping of SA-6 South specific to the subgrade preparation and placement of the geotextile and geocomposite materials as defined herein. Based on the field observations made by Langan along with the field and laboratory test data collected by the Contractor and Subcontractors, it is our professional opinion that the construction observed at SA-6 South complied with the approved *100% Design* package. Additional details on the work and approval of materials is outlined in the *EOR Closure Report*.

## 3.2 Limitations

This Cap Geosynthetic Quality Assurance Report (QA Report) was prepared by Langan (in conjunction with Amec Foster Wheeler) for the exclusive use of Honeywell. This QA Report applies specifically to the subgrade preparation and construction of the geosynthetics components of the SA-6 South cap only.

The construction observations and monitoring were conducted under the conditions stated. Conclusions made in this report were based on these observations and data obtained from field and laboratory tests conducted on the QA samples collected.

The topographic survey measurements were completed by Entact and their licensed surveyor Maser and subject to review and approval by Amec Foster Wheeler. Langan did not independently verify the accuracy of this data.


Acceptance of the geosynthetic materials used for the SA-6 South cap construction was completed by Amec Foster Wheeler. Furthermore, the QC laboratory testing was completed by Geotechnics (under the direction of Entact) and QA laboratory testing was completed by TRI (under the direction of Langan).


The approval of all materials used for this project was completed by Amec Foster Wheeler in the *EOR Closure Report*. The geosynthetic production quality testing was completed by AGRU America, Inc. and their subcontracted companies working on their behalf. Langan did not independently verify the accuracy of the conformance test data.

# Appendix A : Record Drawings

*A1. GVL / GCL Record Drawing*
*A2. LLDPE Geomembrane Record Drawing*
*A3. GDL Record Drawing*

# *A1. GVL / GCL Record Drawing*




0 80 160 Feet

## LEGEND

- GEOCOMPOSITE GAS VENT LAYER (GVL)
- GEOSYNTHETIC CLAY LINER (GCL)
- Class A/16 oz Geotextile
- SCB WALL
- HB WALL (Inner Edge)
- GAS VENT PIPE
- GAS VENT (NOT TO SCALE)
- SPOT ELEVATION (ft) (X 0.0)


J.H. 01/28/2016


ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SA6 SOUTH CAP GVL/GCL LAYOUT
Class A Geotextile/Gas Vent Layer/Geosythetic Clay Liner
01/28/16

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *A2. LLDPE Geomembrane Record Drawing*




## LEGEND

- RP-1 (Repair Number)
- LINER SEAM/EDGE
- SCB WALL
- HB WALL (Inner Edge)

RP: Repair
DSX: Destructive Extrusion Weld Test
DS: Destructive Fusion Weld Test
P: Panel
\- Bead

NOTE: Refer to ESI Repair Report for repair details

0 80 160 Feet


J.H. 01/28/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP PANEL LAYOUT
60 mil Textured LLDPE Geomembrane
01/28/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# *A3. GDL Record Drawing*




LEGEND

GEOCOMPOSITE DRAINAGE LAYER (GDL)

SCB WALL

HB WALL (Inner Edge)

0 80 160 Feet

J.H. 01/27/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

SA6 SOUTH CAP GDL LAYOUT
GEOCOMPOSITE DRAINAGE LAYER 01/27/16

PROJECT NAME & LOCATION

HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

# Appendix B
# Langan CQA Plan

# CONSTRUCTION QUALITY ASSURANCE (CQA) PLAN

# for

# Geosynthetic Cap Installation
# Study Area 6
# Jersey City, New Jersey

***Prepared For:***

**Honeywell International, Inc.**
**101 Columbia Rd.**
**Box 2105**
**Morristown, NJ 07962**

***Prepared By:***

**Langan Engineering and Environmental Services, Inc.**
**River Drive Center 1, 619 River Drive**
**Elmwood Park, NJ 07407**

**July 2015**

**Langan Project No. 10053001**

LANGAN

# CONSTRUCTION QUALITY ASSURANCE (CQA) PLAN

***Prepared By:***
**Langan Engineering & Environmental Services, Inc.**
**River Drive Center 1**
**619 River Drive**
**Elmwood Park, NJ 07407**

Vikki Hon, EIT
Staff Engineer

Dan Bosworth
Senior Staff Engineer

Jeffrey Stoicescu, P.E.
Associate
New Jersey Professional Engineer License No. 24GE04504400

Rory Johnston, P.E.
Principal / Vice President
New Jersey Professional Engineer License No. GE04080500

LANGAN

LANGAN

# TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 1**
1.1 Purpose ..... 1
**2.0 PERSONNEL RESPONSBILITIES, AUTHORITY, AND QUALIFICATIONS ..... 2**
2.1 General ..... 2
2.2 Owner ..... 2
2.3 Design Engineer ..... 2
2.4 Construction Contractor ..... 3
2.5 Cap Geosynthetics Quality Assurance Engineer ..... 4
**3.0 QUALITY CONTROL MEETINGS ..... 6**
3.1 Daily Tailgate Safety Meeting ..... 6
3.2 QA/QC Coordination Meeting ..... 6
3.3 Progress Meeting ..... 6
3.4 Geosynthetic Pre-Installation Meeting ..... 7
3.5 Observation and Testing Records ..... 7
**4.0 CONSTRUCTION QUALITY ASSURANCE ..... 8**
4.1 General ..... 8
4.2 Subgrade Preparation ..... 8
4.2.1 Quality Assurance ..... 8
4.3 Gas Venting System ..... 9
4.3.1.1 Quality Assurance ..... 9
4.4 Geomembrane Layer ..... 10
4.4.1 Quality Assurance ..... 10
4.5 Geocomposite Drainage Layer 2 (Surface water infiltration drainage) ..... 11
4.5.1 Quality Assurance ..... 12
4.6 Root Barrier ..... 12
4.6.1 Quality Assurance ..... 13
4.7 Geosynthetic Clay Liner ..... 13
4.7.1 Quality Assurance ..... 13
4.8 Earthwork ..... 14
**5.0 CAP GEOSYNTHETICS QA REPORT ..... 14**

## TABLES

Table 1 Geosynthetic Material Testing Methods & Frequency

## FIGURES

Figure 1 SA-6 Liner Installation Organization Chart

## APPENDICES

Appendix A QA/QC Forms
- A1 – Certification of Completion
- A2 – Receiving Inspection Report Table
- A3 – Individual Photographic Log
- A4 – Geosynthetics Inventory and Certification Log
- A5 – Subgrade Surface Checklist
- A6 – Trial Weld Log
- A7 – Panel Placement Log
- A8 – Seam Testing Chain of Custody Form
- A9 – Seam Control and Non-Destructive Test Log
- A10 – Repair Log
- A11 – Conformance Test Chain of Custody Form
- A12 – Destructive Seam Field Test
- A13 – Destructive Sample Tracking Summary
- A14 – Penetration Sealing Observation / Cap to Barrier Installation Observation
- A15 – Geosynthetic Daily Inspection Report
- A16 – Notice of Non-Compliance and Corrective Action Form

## 1.0 INTRODUCTION

Honeywell International Inc. (Honeywell) is currently remediating Study Area 6 (SA-6), located in Jersey City, New Jersey (Site). SA-6 encompasses work in two areas: SA-6 North and SA-6 South, which are separated by Study Area 7 (SA-7). The Open Space areas at SA-6 North and SA-6 South will be covered with an engineered cap that includes a linear low-density polyethylene (LLDPE) geomembrane cover, a gas venting layer, a geocomposite drainage layer (GDL), a geosynthetic clay liner (GCL), and other related geosynthetic cap components. Technical specifications and design drawings for the engineered cap may be found in the document titled "100% Specification and Design Drawings."

Honeywell retained Langan Engineering and Environmental Services, Inc. (Langan) as the Independent Quality Assurance (QA) Engineer for the cap geosynthetics installation. This Construction Quality Assurance (CQA) Plan has been prepared in support of this site remediation project with pertinent supporting details outlined herein.

### 1.1 Purpose

The purpose of this CQA Plan is to describe the quality assurance and control procedures required for the construction of the geosynthetic components of the capping system for the Study Area 6 site, encompassing SA-6 North and SA-6 South.

The ultimate goal of this CQA program is to ensure that proper construction techniques and procedures are implemented throughout the course of this phase of the SA-6 project in accordance with the project specifications. Upon completion of the construction activities, a Cap Geosynthetics QA Report will be prepared.


All of the involved parties will receive a copy of this CQA Plan including the Owner, Construction Contractor, Capping System Subcontractor, Geosynthetic Installer, and the Independent Quality Assurance Engineer. The roles and responsibilities of these parties are outlined further in Section 2.0.

## 2.0 PERSONNEL RESPONSBILITIES, AUTHORITY, AND QUALIFICATIONS

### 2.1 General

The principal parties involved in the permitting, design, and construction of the final capping system for the SA-6 site include the Owner, Design Engineer, Construction Contractor, and the Independent Quality Assurance Engineer. Additional entities include the Geosynthetic Installer and Material Quality Control Laboratory. The project organization chart is shown on Figure 1. Descriptions of the individual parties are provided in the sections below.

**Figure 1 – SA-6 Liner Installation Organization Chart**




### 2.2 Owner

Honeywell, as Owner, is ultimately responsible for the construction of the capping of SA-6. The Owner has retained the Design Engineer, Construction Contractor, and the Independent Quality Assurance Engineer.

### 2.3 Design Engineer

Amec Foster Wheeler Environment & Infrastructure, Inc. (AmecFW), as the Design Engineer, was responsible for preparing the final design of the capping system, as well as plans and specifications for the construction work. The final design includes relevant aspects of the capping system, including details of the subgrade preparation, gas venting system, utility trenches, geosynthetic placement details, soil cover requirements, and other relevant design considerations. Samuel G. Shallard is the Engineer of Record (EOR) for AmecFW.

Technical specifications and design can be found in the document titled "100% Specifications and Design Drawings."

Personnel involved with the design engineering portions of the project are outlined herein:

- **Engineer-of-Record**
  Mr. Samuel Shallard shall serve as the Engineer of Record (EOR) and technical lead. Mr. Shallard will also be the lead engineer in resolving technical questions that arise during project execution.

- **Quality Assurance Manager**
  Mr. David Ambrose shall serve as the Quality Assurance (QA) Manager. He shall be directly responsible for subcontractor conformance to the technical specifications and project requirements.

- **Field Engineering**
  Ms. Ari Eslaminejad will serve as the EOR site representative.

### 2.4 Construction Contractor

AmecFW shall also serve as Construction Contractor (Contractor), and is responsible for constructing the soil capping system in accordance with the design criteria, plans, and specifications while using the necessary construction procedures and techniques. The Contractor has engaged ENTACT (Subcontractor) to support AmecFW with these activities.

A New Jersey licensed land surveyor will be contracted to conduct the licensed surveying tasks required in the contract documents and in this CQA Plan as well as to prepare the required record documents.

The Contractor shall provide sufficient project management and project supervision staff to ensure the submission and approval of materials, and that the execution of the work is completed in a timely manner and in accordance with the plans and specifications. Work shall be completed to the standards defined by this CQA plan and the plans and specifications. The Construction Manager, or a designated representative, shall be present during construction activities to oversee work by contractor personnel and/or subcontractor personnel. The Construction Manager or designated representative will coordinate activities directly with the Owner's representative and representatives of the Independent Quality Assurance (QA) Engineer. The Contractor shall be responsible for the repair or replacement of any items or work found defective. The Construction Manager will be supported by the AmecFW Quality Assurance Manager.

For the SA-6 capping project, AmecFW has provided a list of the capping construction team including subcontractors and corresponding responsibilities. A summary of these team members is provided below and presented on the organization chart shown on Figure 1.

- **Construction Manager**
  Mr. Stuart Bills shall serve as the AmecFW Construction Manager and Site Health & Safety Officer with the responsibility for the day-to-day Site activities. He shall report directly to the Honeywell Manager of Construction and the Honeywell Remediation Manager. Mr. Bills shall be responsible for the project implementation schedule, budget, and subcontractor oversight.

- **Project Controls**
  Mr. Eric Christodoulatos shall be responsible for coordinating and tracking submittal approvals and Request for Information (RFI) responses with the EOR. He will also be responsible for project financial cost and schedule tracking and projections.

- **Capping System Subcontractor – ENTACT**
  ENTACT is contracted to AmecFW to perform the cap construction. ENTACT will be responsible for installing the SA-6 capping system in accordance with "100% Specifications and Design Drawings." ENTACT will also be responsible for coordinating scheduling, project deviations, work plans, and any other pertinent construction details directly with the project team. ENTACT will report directly to AmecFW, and will provide the final construction details, including as-built drawings, upon project completion.

- **Geosynthetic Installer – ESI**
  ESI (Installer) is subcontracted to ENTACT. ESI will be responsible for installing the SA-6 geosynthetic materials in accordance with the project plans and specifications, and will work directly with ENTACT. ESI will also be responsible for coordinating scheduling, project deviations, work plans, and any other pertinent construction details directly with the project team.

- **Material Quality Control Laboratory – Geotechnics**
  Geotechnics is subcontracted to ENTACT. Geotechnics will be responsible for supplying laboratory testing results required as part of the capping project, such as destructive seam testing.

### 2.5 Cap Geosynthetics Quality Assurance Engineer

Langan has been retained by Honeywell to provide Independent Quality Assurance for the SA-6 Cap Geosynthetics installation. The Quality Assurance (QA) Engineer will perform the activities specified in this CQA Plan (i.e. monitoring, field oversight, and documentation) and provide a Cap Geoynthetics QA report at the conclusion of the project for the work observed. At a minimum, the Independent QA engineering staff will include a Geosynthetic QA Manager, QA Engineer, and on-site Field Technician, as outlined herein.

**Geosynthetic QA Manager – Mr. Jeffrey Stoicescu, P.E.**

**Duties:**

- Review design criteria, plans, and specifications for clarity and completeness so that the CQA Plan can be implemented.
- Advise the Lead Quality Assurance Engineer and On-Site Field Technician on CQA requirements and procedures. For similar projects, the project manager will support the EOR and field team members on a variety of Requests for Information and Submittals that will vary either the construction sequence or materials.
- Schedule and coordinate CQA inspection activities.
- Routinely update the Owner and Design Engineer on cap geosynthetic status throughout the duration of the geosynthetic portion of the project.
- Attend conference calls as required to provide potential solutions to requests when requested by the EOR.

**Authority:**

The Geosynthetic QA manager has the authority to determine whether or not materials, procedures, and/or installed materials meet the minimum project requirements, and to reject any materials, procedures, and/or installed work that fails to meet the project requirements. The project manager will advise the EOR, Contractor, and Owner of the rejection of materials, procedures, or installed work.

**Lead Quality Assurance Engineer – Mr. Dan Bosworth**

**Duties:**

- Direct and support the CQA personnel in performing observations and material tests;
- Confirm that the testing data is accurately recorded and maintained;
- Verify that the raw data is properly recorded, validated, reduced, summarized, and interpreted;
- Review and interpretation of data sheets and reports;
- Notify the Geosynthetic QA Manager of potential conflicts with the design drawings;
- Coordinate with the EOR to reject defective work and verify that corrective measures are implemented;
- Identify work that should be accepted, rejected, or uncovered for observation, or that may require special testing, inspection or approval.

**Authority:**

The Lead QA Engineer shall have the authority to observe and test any material and/or work, and render a decision as to whether the work is acceptable (based on the testing), and ensure that any work that does fail is removed and replaced with acceptable materials and/or workmanship.

**On-site Field Technician – Mr. Dan Bosworth and/or Mr. Connor Shields**

**Duties:**

- Perform site monitoring of the work in progress to assess compliance with the design criteria, plans, and specifications;
- Observe deliveries received on site as required on the Receiving Inspection Report provided as Appendix A2;
- Verify that the tests are conducted according to this CQA Plan;
- Report to the Lead QA Engineer results of inspections, including work that is not of acceptable quality or that fails to meet the specified design; and
- Complete inspection and testing forms as necessary.

**Authority:**

The on-site technician will have the authority to observe and test material and render a decision of whether the work is acceptable based on observation of testing and help ensure that work that does not conform to the approved plans and specifications is removed and replaced with acceptable materials and/or workmanship.

## 3.0 QUALITY CONTROL MEETINGS

### 3.1 Daily Tailgate Safety Meeting

A daily tailgate meeting will be held prior to commencement of any work activities for the day at approximately 6 A.M or time designated by the Construction Manager. The Contractor, Subcontractor, Geosynthetic Installer, and on-site quality assurance personnel involved in the field work procedures for that specific day shall be present at this meeting. The Daily Meeting shall include relevant aspects of the work for the day and its potential relationship to relevant health and safety (H&S) aspects outlined in their respective H&S plans. Individuals who arrive after the tailgate meeting has been conducted shall convene with the Construction Manager or other designate for the H&S briefing prior to starting work.

### 3.2 QA/QC Coordination Meeting

A QA/QC coordination meeting will be held prior to the construction of the capping system. Representatives of Honeywell, the EOR, the Construction Contractor, and the Independent QA Engineer will be present. The agenda for this meeting may include, but not be limited to:

- Familiarize each involved party with the CQA Plan and its role relative to the design criteria, site construction and closure plans, specifications, and construction documentation;
- Review the responsibilities of each involved party;
- Review the Contractor's projected work schedule and methodology;
- Determine any changes, if necessary, to the CQA Plan that are needed to ensure that the capping system will be constructed to meet the specific design;
- Review lines of authority and communication for each organization;
- Discuss the established procedures or protocol for observations and tests including sampling strategies;
- Discuss the established procedures or protocol for handling design change bulletins, construction deficiencies, repairs, and retesting;
- Review methods for documenting and reporting inspection data;
- Review methods for distributing and storing documents and reports;
- Review work area security and safety protocol;
- Review procedures for the location and protection of construction materials and for the prevention of damage to the materials from inclement weather or other adverse events;
- Conduct a site walk-around to review construction materials where available and to inspect equipment storage locations; and
- Minutes of the preconstruction meeting will be prepared by the Quality Assurance On-site field technician and will be distributed to all parties.

### 3.3 Progress Meeting

Progress meetings will be held once a week on Tuesdays at 8:30 A.M or at an alternate time designated by the Construction Manager. These meetings shall be scheduled between the primary parties involved with this project. At a minimum, a Representative of Honeywell, the Contractor's Construction Manager, the EOR, and a representative of the Independent QA team shall be present. At times, a subcontractor may be requested to attend as well.

### 3.4 Geosynthetic Pre-Installation Meeting

A progress meeting will be held prior to commencing installation of the geomembrane and/or geosynthetic materials. At a minimum the attendees shall be the Contractor's Construction Manager, the Lead Quality Assurance Engineer and On-Site Field Technician, as well as representatives from ENTACT and ESI. The agenda for this meeting will include but is not limited to the following:

- Discussion of CQA procedures and requirements;
- Review Panel Layouts;
- Review of Repair tracking methods and drawings;
- Discussion of procedures or protocol for observations and tests including sampling strategies;
- Installation sequence and methods;
- Projected work schedule; and
- Minutes of the geosynthetic pre-installation meeting will be prepared by the Project Controls representative and will be distributed to all parties.

### 3.5 Observation and Testing Records

There will be observation and testing records that will be utilized in conjunction with the construction oversight performed by the Quality Assurance (QA) Field Technician. The observation logs listed below contain the data to be recorded by the Quality Control Representative and can be found in Appendix A. The QA on-site field Technician will complete the following observation and testing records:

- Geomembrane Observation Records – The geomembrane inspection records forms consisting of:
    - Material delivery checklist (see Appendix A4)
    - Subgrade surface acceptance records (see Appendix A5)
    - Trial weld logs (see Appendix A6)
    - Panel placement record (see Appendices A7)
    - Panel seaming log (see Appendix A8)
    - Non-destructive testing log (see Appendix A9)
    - Repair log (see Appendix A10)
    - Conformance Test Chain of Custody Form (A11)
    - Destructive testing log (see Appendices A12 and A13)
    - Penetration Sealing Observation / Cap to Barrier Installation Observation (see Appendix A14)
    - Daily inspection report for the geomembrane liner (see Appendix A15)
- Other related forms including certification of completion (see Appendix A1), receiving inspection report table (see Appendix A2), and notice of non-compliance and corrective action form (see Appendix A16).

The QA on-site field technician overseeing geomembrane installation will independently document related data contained within the records listed above to provide the information to review the Contractor's geomembrane capping system subcontractor documentation prior to acceptance of the installed geomembrane cap. The Contractor shall provide access to the work

site and shall provide the QA on-site field technician access to all field data and records, as built drawings, and shall collect duplicate samples as required for testing by the QA on-site field technician laboratory subcontractor as required.

In addition, the on-site field technician will maintain a field notebook onsite to document observations, test results, weather conditions, work defects, etc. that occur during observation of construction activities.

## 4.0 CONSTRUCTION QUALITY ASSURANCE

### 4.1 General

The final capping system consists of the following layers, from bottom to top:

- A gas venting system (geocomposite drainage layer and vents);
- A 60-mil geomembrane LLDPE layer;
- A geocomposite drainage layer with warning layer;
- 12-inch thick geocomposite drainage layer cover soil;
- 16 oz woven geotextile root barrier; and
- Soil layers consisting of structural fills, planting soils, and capped with a 6-inch minimum topsoil layer.

The layers of the capping system are described in the sections below.

### 4.2 Subgrade Preparation

The subgrade layer of the capping system is shown on construction drawing C-301, provided in "100% Specifications and Design Drawings." The soil surface for the capping system (subgrade) is currently under construction to prepare the surface in accordance with the subgrade specification. These subgrade surface conditions will require review and approval by the Independent QA Engineer and Capping System Contractor and geosynthetics installer prior to placement of the geosynthetic materials as defined below.

#### 4.2.1 Quality Assurance

The subgrade observation and approval QA/QC forms have been provided in Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance to Section 02372 found in "100% Specifications and Design Drawings" and note deviations from the technical specifications;
- Observe subgrade preparation; and
- Review documentation to verify compliance.

Testing and installation documentation referenced above that is developed by the Subcontractor will be submitted to the QA Engineer for review. Copies of this documentation will be included as

part of the Cap Geosynthetics QA Report prepared by the Independent QA Engineer. The Cap Geosynthetics QA Report for the subgrade preparation shall, at a minimum, include the following:

- Documentation of qualifications of all contractors and CQA personnel.
- Daily reports prepared by the QA Engineer;
- Subgrade acceptance certificates for each area to be covered by the cap system, signed by the Geosynthetics Installer, the Subcontractor, and QA Engineer;
- Daily construction progress reports clearly showing subgrade preparation; and
- Quality control documentation, as detailed in this CQA Plan.

### 4.3 Gas Venting System

The gas vent layer shall be comprised of a layer of geocomposite drainage material and a gooseneck-shaped vent to facilitate communication between soil gas under the cap and the atmosphere. This gas venting system is shown on drawings C-121 and C-301 in "100% Specifications and Design Drawings."

Section 02374 from "100% Specifications and Design Drawings" is summarized on Table 1 and indicates the requirements for the geocomposite gas venting layer. Requirements include, but are not limited to:

- Packaging, shipment, and storage of material;
- Handling and placement requirements;
- Seaming procedures; and
- Material repairs.

The specification requirements for the goose-neck shaped vent, which have been provided in Section 02380 in "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Gas vent pipe materials; and
- Installation of the pipes via pipe laying, jointing, and pipe cutting.

#### 4.3.1.1 Quality Assurance

The GDL and gas vent QA/QC forms have been provided as Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Sections 02372 and 02380, provided in "100% Specifications and Design Drawings," and note deviations from technical specifications;
- Observe subgrade preparation;
- Overlapping of geocomposite and connection procedures;
- Material repairs;
- Observe pipe materials handling and storage;
- Observe installation of gas vent system; and
- Review of QC Documents to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Contractor will be submitted to the QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the QA Engineer. The Cap Geosynthetics QA Report for the geocomposite layer shall, at a minimum, include the following:

- Documentation of qualifications of all installers and CQA personnel;
- Daily reports prepared by the QA Engineer; and
- Daily construction progress reports clearly showing geocomposite and piping materials placed by date.

### 4.4 Geomembrane Layer

The geomembrane selected for use in the cover system is a 60-mil (0.060 inch) thick LLDPE. A microspike double-sided textured geomembrane has been approved for use on this project. Work shall consist of installing the LLDPE geomembrane and the overlying geocomposite in the areas as shown on the construction drawing C-301 provided in "100% Specifications and Design Drawings."

The specification requirements for the geomembrane layer, which have been provided in Section 02372 of "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Packaging, shipment, and storage of material;
- Handling and placement requirements;
- Non-destructive and destructive seam testing procedures; and
- Material repairs.

#### 4.4.1 Quality Assurance

Prior to the start of capping activities the geosynthetic installer shall provide the Design and Independent QA Engineers with a panel layout drawing.

The Subcontractor's installer shall furnish the certified test results for all geomembrane to be used to the EOR, or EOR representative, for review as part of the required shop submittals prior to shipment to the site. The EOR, or EOR representative, will review the test results for conformance with the criteria included in the contract specifications.

The geomembrane layer QA/QC forms have been provided as Appendix A. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Section 02372 provided in "100% Specifications and Design Drawings" and note deviations from technical specifications;
- Review subgrade preparation and approval to place geomembrane materials;
- Observe effect of weather conditions on geomembrane installation;
- Seam preparation;
- Seaming equipment and procedures;
- Overlapping and temporary bonding;
- Test seams;
- Non-destructive and destructive seam testing;

- Penetration sealing observations for gas vents, piezometers, and groundwater collection system manhole to the LLDPE.
    - Note cap to barrier exterior detail will be observed and documented by AmecFW field engineering representative.
- Repair procedures and testing ;
    - Defective areas may include:
        - Large holes, tears, cold bends, cracks, etc.:
        - Other localized flaws;
        - Small to large tears and large lengths of failed seams;
        - Areas of inadequate seams; and
- Documentation to demonstrate compliance.

Testing and installation documentation referenced above that is developed by the Capping System Subcontractor will be submitted to the QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the Independent QA Engineer. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The Cap Geosynthetics QA Report for the geomembrane layer shall, at a minimum, include the following:

- Summary of required submittals, documentation, and QC testing results outlined in Contractor's Construction Quality Assurance Plan (CQA)
- Daily reports prepared by the Quality Assurance Engineer.
- Record drawing(s) (panel layout with all associated data) received and approved by the QA Engineer.
- Subgrade acceptance certificates for each area to be covered by the cap system, signed by the Contractor's Installer and the Contractor.
- Relevant completed QA data sheets from Appendix A.

### 4.5 Geocomposite Drainage Layer 2 (Surface water infiltration drainage)

The cap cross-section will utilize two layers of drainage net. The geocomposite drainage layers (GDLs) will be both directly above and below the 60-mil geomembrane layer as shown on drawing C-301 in "100% Specifications and Design Drawings." The GDL above the membrane is allow for drainage and transport of infiltrated surface water, and the GDL below the membrane is for gas venting. This section focuses on the installation of the GDL above the membrane.

The specification requirements for the geomembrane layer, which have been provided in Section 02374 in "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Packaging, shipment, and storage of material;
- Handling and placement requirements;
- Seaming procedures;
- Material repairs; and
- Cover soil placement for the GDL above the geomembrane.

### 4.5.1 Quality Assurance

The geocomposite manufacturer shall provide certified copies of laboratory test results on the following specifications listed in Appendix A.

The Construction Contractor will furnish the certified test results for all geocomposite placed to the QA Engineer for review as part of the required shop submittals. The EOR, or EOR representative, will review the test results for conformance with the criteria included in the contract specifications.

The GDL QA/QC forms have been provided as Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Section 02372 of "100% Specifications and Design Drawings" and note deviations from technical specifications;
- Observe subgrade preparation;
- Overlapping and connection procedures;
- Material repairs; and
- Documentation to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Capping System Subcontractor will be submitted to the Independent QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the Independent QA Engineer. The report sections outlining the geocomposite layer shall, at a minimum, include the following:

- Daily reports prepared by the Independent QA Engineer; and
- Daily construction progress reports clearly showing geocomposite placed by date.

## 4.6 Root Barrier

The capping system shall contain a woven geotextile root barrier layer. This barrier layer is located directly above the GDL cover soil layer, as indicated in drawing C-301 in "100% Specifications and Design Drawings."

The specification requirements for the geotextile layer, which have been provided in Section 02373 of "100% Specifications and Design Drawings" and summarized on Table 1, includes, but are not limited to:

- Product materials;
- Application of geotextile; and
- Installation of geotextile fabrics.

### 4.6.1 Quality Assurance

The QA/QC forms have been provided as Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, are not limited to:

- Confirm work has been completed in accordance with Section 02373 of "100% Specifications and Design Drawings" and note deviations from technical specifications;
- Observe geotextile installation;
- Overlapping;
- Material repairs; and
- Documentation to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Contractor will be submitted to the QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the QA Engineer. The relevant sections of report outlining the geotextile layer shall, at a minimum, include the following:

- Daily reports prepared by the QA Engineer; and
- Daily construction progress reports clearly showing geotextiles placed by date.

## 4.7 Geosynthetic Clay Liner

The geosynthetic clay liner (GCL) shall be used as a secondary hydraulic barrier in locations where the cap may be submerged below the groundwater table, as indicated on drawing C-309 provided in "100% Specifications and Design Drawings."

The specification requirements for the clay liner, which have been provided in Section 02375 in "100% Specifications and Design Drawings" as well as summarized on Table 1, includes, but are not limited to:

- Material delivery, handling, and storage;
- GCL placement;
- Seaming; and
- Damage repairs.

### 4.7.1 Quality Assurance

The various technical specifications pertaining to the GCL are outlined within the QA/QC forms contained within Appendix A. The forms outlined in Appendix A shall be used as a guideline for the typical information required for the submittal. Actual form submitted by the Contractor may vary from those presented. The QA engineer observations may include, but are not limited to:

- Confirm work has been completed in accordance with Specification Section 02375 and note deviations from technical specifications;
- Observe geotextile installation;
- Observe overlapping and seaming of GCL;
- Material repairs;

- Observe GCL hydration; and
- Documentation to demonstrate compliance.

All testing and installation documentation referenced above that is developed by the Contractor will be submitted to the Independent QA Engineer for review. Copies of all of this documentation will be included as part of the Cap Geosynthetics QA Report prepared by the QA Engineer. The certification report for the GCL shall, at a minimum, include the following:

- Daily reports prepared by the QA Engineer; and
- Daily construction progress reports clearly showing GCL placed by date.

### 4.8 Earthwork

As shown on drawing C-301 in "100% Specifications and Design Drawings," the soil materials used in the construction of this capping system consist of the following layers:

- Geocomposite drainage soil;
- Planting soil layers consisting of topsoil underlain by soil layers capable of support tree and shrub growth;
- Structural fill to be placed under roadways;
- Common borrow placed in select areas under roadways or to raise the subgrade to appropriate elevations.

The relevant quality control/quality assurance observations and specifications governing placement and testing of each layer are summarized in a separate Construction Quality Control Plan prepared by AmecFW.

## 5.0 CAP GEOSYNTHETICS QA REPORT

The QA Engineer in conjunction with the EOR and Contractor shall prepare a Cap Geosynthetic QA Report documenting work completed in this CQA Plan. This report shall contain at a minimum:

- As-built drawings from the Contractor;
- Conformed technical specifications from the EOR;
- Summary of DCB, submittals, and RFIs by the EOR;
- Reference to the QC data reported by the Contractor;
- Summary of QA/QC forms outlined in Appendix A prepared by the Independent QA Engineer and Contractor; and
- Photographic logs and QA/QC forms by the Independent QA Engineer.

# Tables

Table 1 – Geosynthetic Material Testing Methods & Frequency

ENTACT

**TABLE 1: GEOSYNTHETIC MATERIAL TESTING METHODS & FREQUENCY**
**Honeywell SA6 South**
**Jersey City, New Jersey**

| Materials to be Tested | Sample Location | Parameter | Test Method | Frequency | Value | Specification/ Reference | Notes | QC Tests Needed | QC Tests Completed | QA Tests Completed | Material Quantity |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **60 mil LLDPE MicroSpike Double Sided Geomembrane** | Manufacturer - AgruAmerica | *Conformance Testing:* | | | | | | | | | ***394,910 Square Feet*** |
| | | Thickness | ASTM D5994 | 1/roll | 57 MARV | 02372-2.02 and Table 02372-1 | | 34 | 0 | 0 | ***34 rolls*** |
| | | Density | ASTM D1505/D792 | 1/200,00 lbs | 0.939 g/cc | | Density value change approved per Submittal 091 | 1 | 0 | 0 | ***129,200 lbs*** |
| | | Tensile Properties | ASTM D6693 | 1/20,000 lbs | 90 lbs/in (strength)/250% elongation | | | 7 | 0 | 0 | |
| | | Tear Resistance | ASTM D1004 | 1/45,000 lbs | 33 lbs | | | 3 | 0 | 0 | |
| | | Puncture Resistance | ASTM D4833 | 1/45,000 lbs | 66 lbs | | | 3 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603 | 1/20,000 lbs | 2%-3% | | | 7 | 0 | 0 | |
| | | Carbon Black Dispersion | ASTM D5596 | 1/45,000 lbs | 9 in Cat 1 or 2 and 1 in Cat 3 | | | 3 | 0 | 0 | |
| | | Asperity Height | ASTM D7466 | 1/Second roll | 10 mils (min) | | Asperity Test Method change approved per Submittal 091 | 17 | 0 | 0 | |
| | | Oxidative Induction Time | ASTM D3895 | 1/100,000 lbs | 100 minutes | | | 4 | 0 | 0 | |
| | QC Laboratory - Geotechnics | *3rd Party Laboratory Testing* | | | | | | | | | |
| | | Thickness | ASTM D5994 | 1/100,000 square feet | 57 MARV | 02372-2.02 and Table 02372-1 | | 4 | 0 | 0 | |
| | | Density | ASTM D1505/D792 | 1/100,000 square feet | 0.939 g/cc | | Density value change approved per Submittal 091 | 4 | 0 | 0 | |
| | | Tensile Properties | ASTM D6693 | 1/100,000 square feet | 90 lbs/in (strength)/250% elongation | | | 4 | 0 | 0 | |
| | | Tear Resistance | ASTM D1004 | 1/100,000 square feet | 33 lbs | | | 4 | 0 | 0 | |
| | | Puncture Resistance | ASTM D4833 | 1/100,000 square feet | 66 lbs | | | 4 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603 | 1/100,000 square feet | 2%-3% | | | 4 | 0 | 0 | |
| | | Carbon Black Dispersion | ASTM D5596 | 1/100,000 square feet | 9 in Cat 1 or 2 and 1 in Cat 3 | | | 4 | 0 | 0 | |
| | | Asperity Height | ASTM D7466 | 1/100,000 square feet | 10 mils (min) | | Asperity Test Method change approved per Submittal 091 | 4 | 0 | 0 | |
| | | Interface Strength | ASTM D5321 | 1/100,000 square feet | Peak = 26 degrees; Residual = 22.5 degrees | | | 4 | 0 | 0 | |
| | | *Field Quality Control Testing:* | | | | | | | | | |
| | | Start-Up Testing Peel (Tensiometer) | ASTM D6392 | Start of each shift and every 5 hrs | 66 lb/in & FTB (extrusion weld); 75 lb/in & FTB (fusion weld) | 02372-3.06.A.1 | Test 3 peel/3 shear | 100% | 0 | 0 | |
| | | Start-Up Testing Shear (Tensiometer) | ASTM D6392 | Start of each shift and every 5 hrs | 90 lb/in | 02372-3.06.A.1 | Test 3 peel/3 shear | 100% | 0 | 0 | |
| | | Non-Destructive Field Seam Continuity Testing | Vacuum Testing | Full seam length (extrusion weld) | No bubbles in viewing window for 10 seconds | 02372-3.06.B.2 | | 100% | 0 | 0 | |
| | | Non-Destructive Field Seam Continuity Testing | Air Pressure Testing | Full seam length (fusion weld) | <4 psi pressure loss over 5 min @ 25-30 psi pressure | 02372-3.06.B.3 | | 100% | 0 | 0 | |
| | | Destructive Testing Shear (Tensiometer) | ASTM D6392 | 1/500 ft of seam | 66 lb/in & FTB (extrusion weld); 75 lb/in & FTB (fusion weld) | 02372-3.07.D | Test 3 peel/3 shear | 35 | 0 | 0 | |
| | | Destructive Testing Peel (Tensiometer) | ASTM D6392 | 1/500 ft of seam | 90 lb/in | 02372-3.07.D | Test 3 peel/3 shear | 35 | 0 | 0 | |
| | Lab QC-Geotechnics | Destructive Testing Shear (Laboratory) | ASTM D6392 | 1/500 ft of seam | 66 lb/in & FTB (extrusion weld); 75 lb/in & FTB (fusion weld) | 02372-3.07.E | Test 5 peel/5 shear. 5 out of 5 must pass peel and shear | 35 | 0 | 0 | |
| | | Destructive Testing Peel (Laboratory) | ASTM D6392 | 1/500 ft of seam | 90 lb/in | 02372-3.07.E | Test 5 peel/5 shear. 5 out of 5 must pass peel and shear | 35 | 0 | 0 | |
| ***Transnet 33-2-6 Geocomposite w/Warning Layer (Drainage Layer)*** | Manufacturer - SKAPS | *Conformance Testing:* | | | | 02374-2.2.A | | | | | ***394,800 Square Feet*** |
| | | **Resin** | | | | | | | | | ***141 Rolls*** |
| | | Polymer Density | ASTM D1505 | 1/lot | >0.94 g/cm3 | | | TBD | | | |
| | | Melt Flow Index | ASTM D1238 | 1/lot | ≤1.0 g/10 min | | | TBD | | | |
| | | **Geonet** | | | | | | | | | |
| | | Thickness, min avg | ASTM D5199 | 1/50,000 sf | 200 mil | | | 8 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603/D4218 | 1/50,000 sf | 2-3% | | | 8 | 0 | 0 | |
| | | Tensile Strength, MD | ASTM D7179 | 1/50,000 sf | 45 lbs/in | | Most current ASTM test method for tensile strength | 8 | 0 | 0 | |
| | | **Geotextile** | | | | | | | | | |
| | | Mass/Unit Area, MARV | ASTM D5261 | 1/100,000 sf | 6 oz/sy | | | 4 | 0 | 0 | |
| | | Grab Tensile, MARV | ASTM D4632 | 1/100,000 sf | 158 lbs | | | 4 | 0 | 0 | |
| | | Tear Strength, MARV | ASTM D4533 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Puncture Strength, MARV | ASTM D4833 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Permittivity, MARV | ASTM D4491 | 1/500,000 sf | 0.5 $sec^{-1}$ | | | 1 | 0 | 0 | |
| | | AOS, US Sieve | ASTM D4751 | 1/500,000 sf | 0.25 mm | | | 1 | 0 | 0 | |
| | | UV Resistance | ASTM D4355/G 154 | 1/resin formulation | 90% retained after 500 hrs | | | 1 | 0 | 0 | |
| | | **Geocomposite** | | | | | | | | | |
| | | Transmissivitiy, min | ASTM D4716 | 1/200,000 sf | $8.0x10^{-4}$ | | Normal compressive load load should be 750 psf at gradient of 0.316 | 2 | 0 | 0 | |
| | | Ply Adhesion, min avg | ASTM D7005 | 1/100,000 sf | 0.5 lbs/in | | Ply AdhesionTest Method change approved per Submittal 081 | 4 | 0 | 0 | |
| | QC Laboratory - Geotechnics | *Testing with Site Specific Soils* | | | | | | | | | |
| | | Interface - GDL/Geomembrane | ASTM D5321 | 1/100,000 sf | | 02374-2.3 | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| | | Interface - GDL/Cover Soil (Celgene) | ASTM D5321 | 1/100,000 sf | Peak = 26 degrees; Residual = 22.5 degrees | | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| | | Transmissivity | ASTM D4716 | 1/100,000 sf | 8.0x10-4 | | Normal compressive load load should be 750 psf at gradient of 0.316 | 4 | 0 | 0 | |

| Materials to be Tested | Sample Location | Parameter | Test Method | Frequency | Value | Specification/ Reference | Notes | QC Tests Needed | QC Tests Completed | QA Tests Completed | Material Quantity |
|---|---|---|---|---|---|---|---|---|---|---|---|
| ***Transnet 22-2-6 Geocomposite (Gas Vent System)*** | Manufacturer - SKAPS | *Conformance Testing:* | | | | 02374-2.2.A | | | | | ***311,750 Square Feet*** |
| | | **Resin** | | | | | | | | | ***86 Rolls*** |
| | | Polymer Density | ASTM D1505 | 1/lot | >0.94 g/cm3 | | | TBD | 0 | 0 | |
| | | Melt Flow Index | ASTM D1238 | 1/lot | ≤1.0 g/10 min | | | TBD | 0 | 0 | |
| | | **Geonet** | | | | | | | | | |
| | | Thickness, min avg | ASTM D5199 | 1/50,000 sf | 200 mil | | | 7 | 0 | 0 | |
| | | Carbon Black Content | ASTM D1603/D4218 | 1/50,000 sf | 2-3% | | | 7 | 0 | 0 | |
| | | Tensile Strength, MD | ASTM D7179 | 1/50,000 sf | 45 lbs/in | | Most current ASTM test method for tensile strength | 7 | 0 | 0 | |
| | | **Geotextile** | | | | | | | | | |
| | | Mass/Unit Area, MARV | ASTM D5261 | 1/100,000 sf | 6 oz/sy | | | 4 | 0 | 0 | |
| | | Grab Tensile, MARV | ASTM D4632 | 1/100,000 sf | 158 lbs | | | 4 | 0 | 0 | |
| | | Tear Strength, MARV | ASTM D4533 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Puncture Strength, MARV | ASTM D4833 | 1/100,000 sf | 57 lbs | | | 4 | 0 | 0 | |
| | | Permittivity, MARV | ASTM D4491 | 1/500,000 sf | 0.5 $sec^{-1}$ | | | 1 | 0 | 0 | |
| | | AOS, US Sieve | ASTM D4751 | 1/500,000 sf | 0.25 mm | | | 1 | 0 | 0 | |
| | | UV Resistance | ASTM D4355/G 154 | 1/resin formulation | 90% retained after 500 hrs | | | TBD | | | |
| | | **Geocomposite** | | | | | | | | | |
| | | Transmissivitiy, min | ASTM D4716 | 1/200,000 sf | $8.0x10^{-4}$ | | Transmissivity requirement for gas vent system deleted per Addendum #5; Clarification #3 | 2 | 0 | 0 | |
| | | Ply Adhesion, min avg | ASTM D7005 | 1/100,000 sf | 0.5 lbs/in | | Ply Adhesion Test Method change approved per Submittal 081 | 4 | 0 | 0 | |
| | QC Laboratory - Geotechnics | *Testing with Site Specific Soils* | | | | | | | | | |
| | | Interface - GVS/Geomembrane | ASTM D5321 | 1/100,000 sf | | 02374-2.3 | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| | | Interface - GVS/Subgrade Soil | ASTM D5321 | 1/100,000 sf | Peak = 26 degrees; Residual = 22.5 degrees | | Peform test at normal pressure of 1.5, 3.0, 4.5 psi with displacement rate of 0.04 in/min (wet condition) | 4 | 0 | 0 | |
| ***Bentomat DN Geosynthetic Clay Liner*** | Manufacturer - CETCO | *Manufacturer Certification:* | | | | | | | | | ***69,600*** |
| | | **Geotextile** | | | | 02375 - Tables 1 & 2 | | | | | ***32 Rolls*** |
| | | Mass/Unit Cap, MARV (Non-Woven) | ASTM D5261 | 1/200,000 sf | 6.0 oz/sy | | | 1 | 0 | 0 | ***83,200 lbs*** |
| | | Mass/Unit Carrier, MARV (Non-Woven) | ASTM D5261 | 1/200,000 sf | 6.0 oz/sy | | | 1 | 0 | 0 | |
| | | **Bentonite** | | | | | | | | | |
| | | Swell Index | ASTM D5890 | 1/100,000 lb | 24 ml min | | | 1 | 0 | 0 | |
| | | Moisture Content | ASTM D4643 | 1/100,000 lb | 35% max | | | 1 | 0 | 0 | |
| | | Fluid Loss | ASTM D5891 | 1/100,000 lb | 18 ml max | | | 1 | 0 | 0 | |
| | | **Finished GCL** | | | | | | | | | |
| | | Mass/Unit Area Bentonite | ASTM D5993 | 1/40,000 sf | 0.75 lb/sf MARV | | | 2 | 0 | 0 | |
| | | Tensile Strength, MD | ASTM D6768 | 1/40,000 sf | 50 lb/in MARV | | Testing frequency change approved per Submittal 092 | 2 | 0 | 0 | |
| | | Peel Strength | ASTM D6496 | 1/40,000 sf | 12 lb/in MARV | | | 2 | 0 | 0 | |
| | | | ASTM D4632 | 1/40,000 sf | 60 lb MARV | | | 2 | 0 | 0 | |
| | | Hydraulic Conductivity | ASTM D5887 | 1/Week | $5 \times 10^{-11}$ m/sec | | | TBD | | | |
| | | Index Flux | ASTM D5887 | 1/Week | $1 \times 10^{-8}$ $m^3/m^2$/sec | | | TBD | | | |
| | | Internal Shear Strength | ASTM D6243 | Periodically | 150 psf Typical (non-slope areas); 500 psf Typical | | | 1 | | | |
| | | | | | | | | | | | |

# Appendix A

# QA/QC Forms

A1 – Certification of Completion
A2 – Receiving Inspection Report Table
A3 – Individual Photographic Log
A4 – Geosynthetics Inventory and Certification Log
A5 – Subgrade Surface Checklist
A6 – Trial Weld Log
A7 – Panel Placement Log
A8 – Seam Testing Chain of Custody Form
A9 – Seam Control and Non-Destructive Test Log
A10 – Repair Log
A11 – Conformance Test Chain of Custody Form
A12 – Destructive Seam Field Test
A13 – Destructive Sample Tracking Summary
A14 – Penetration Sealing Observation / Cap to Barrier Installation Observation
A15 – Geosynthetic Daily Inspection
A16 – Notice of Non-Compliance and Corrective Action Form

# Appendix A1

# Certification of Completion

LANGAN

# Certificate of Completion

Sheet # _____

| | | | | | |
|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | |
| Project No. | | Layer | Primary | Secondary | Tertiary |
| Owner/ Contr. | | Type | Partial | Substantial | Final |
| QA Monitor | | Date | | | |

| Description and Area of Work Being Certified: |
|---|
| |

I hereby certify that the above identified work has been inspected and it has been properly installed. I further certify all required testing has been completed and the results are acceptable to the CQA Officer. The liner system is suitable for its intended use.

| **Independent CQA Monitor** | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | |

| **Geosynthetic Installer Representative** | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | |

| **Owner Representative** | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | |

| Notes, Observations, Comments: |
|---|
| |

# PROJECT COMPLETION REPORT

Project Name: _____ Project Manager: _____

Job Number: _____ Superintendent: _____

Date Completed: _____

| Item Number | Item Description | Completed Quantity |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | Total Linear Feet of Anchor Trench | |
| | Vertical Feet of Liner in Trench (per Detail) | |

| Item Number | Item Description | Completed Quantity |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | Total Linear Feet of Tie in to Existing | |
| | Total Linear Feet of Tie in Slope to Floor | |

The Quantities Listed Above Are Based On The Following :

- ☐ Field measurements
- ☐ Quantities are agreed to at this time
- ☐ Quantities listed include geosynthetics in anchor trench
- ☐ Job 100% complete
- ☐ Field change orders were Issued How Many? _____

**Check All Applicable Boxes Below:**

- ☐ Quantities listed include tie in / run out details
- ☐ Quantities to be verified by survey
- ☐ Quantities listed are per completed survey
- ☐ Job is partially complete.
- ☐ Anticipated remob date is: _____

☐ The project has been left, by ESI, in a clean and orderly fashion acceptable to customer.

_____
Initial by Customer / Rep

☐ All work has been found satisfactorily completed and the work satisfies the Project plans and specifications

_____
Initial by Customer / Rep

**ESI Owned Materials Left On Site**

| Material Description | Roll Count | Total Square Feet | Notes |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

_____
ESI Superintendent Signature

_____
Print Name

_____
Date

_____
Authorized Signature

_____
Print Name

_____
Title / Company

_____
Date

*Rev 2-10-10*

# Appendix A2

# Receiving Inspection Report Table

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: | | | | | | | | | Contract Number: |
| Received From: | | | | | | | | | Receiving Report Number: |
| Address: | | | | | | | | | Date: |
| QC Inspection by: | | QC Date: | | Inv. Or Packing Slip No.: | | Inv. Or Packing Slip Date: | | | PO Number: |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Reels | Total Packages | Received By: |
| | | | | | | | | | Received At: |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | | | | | |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: | | Car # | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.: | Freight Bill (Pro) No.: | Weight: | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# Appendix A3

# Individual Photographic Log

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

**PHOTOGRAPHIC LOG**
Photo #

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** |
|---|---|---|
| **Date:** | | |
| **Direction Taken:** | | |
| **Description:** | | |

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

**PHOTOGRAPHIC LOG**
Photo #

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** |
|---|---|---|
| **Date:** | | |
| **Direction Taken:** | | |
| **Description:** | | |

# Appendix A4

# Geosynthetics Inventory and Certification Log

LANGAN

# Geosynthetics Inventory and Certification Log

Sheet # _____

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | | | | |
| Project No. | | Layer | Primary | | Secondary | | | Tertiary |
| Owner/ Contr. | | Material Type: | HDPE | GN | GT | GC | GCL | OTHER |
| QA Monitor | | Texture: Smooth | | | Thickness: | | Width: | |

| Roll Number | Lot/Batch Number | Roll Length | Roll Area | Date Roll Received | Date Cert.'s Received | Date Roll Approved |
|---|---|---|---|---|---|---|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| Total | | - | - | | | |
| Running Total | | | - | | | |
| Notes, Observations, Comments: | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Geosynthetic Installer Representative _____ Date _____

Independent CQA Monitor _____ Date _____

# Appendix A5

# Subgrade Surface Checklist & Data Sheet

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: _____ PROJECT NO: _____

LOCATION: _____

AREA ACCEPTED: _____

PANEL NUMBERS: _____

GRADE ACCEPTANCE: INSPECTOR: _____

GENERAL CONTRACTOR: _____

OWNER: _____

AUTHORIZED REPRESENTATIVE: _____

The undersigned, _____,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on _____ and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| _____ | _____ | _____ |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| _____ | _____ | _____ |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# Appendix A6

# Trial Weld Log

# Environmental Specialties International, Inc.
## Preweld Test Report



**Project Name:** _____ **Job #** _____ **Superintendent:** _____

**Material Type:** _____

**Job Description:** _____

**Reported By** _____ **Other** _____

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| | | |
|---|---|---|
| **Pond** | | **Peel Test Extrusion Minimum** _____ PPI |
| **Cell** | | **Peel Test Fusion Minimum** _____ PPI |
| **Cap** | | **Shear Test Minimum** _____ PPI |

| Weld Date / Liner Type | Time am \| pm | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A \| B | Coupon 2 A \| B | Coupon 3 A \| B | Coupon 4 A \| B | Coupon 5 A \| B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |
| | : | | | | | | | Peel | | | | | | |
| TO | | | | | | | | Shear | | | | | | |

# Appendix A7

# Panel Placement Log

# Daily Panel Placement

Page ____

Project Name: Honeywell Job # 12-11-1399 Deployment Date ____

Superintendent: Fortino Ayala Material Type: LLPE 60 MIL

[ ] Primary Secondary [ ] Cell [ ] Pond [ ] Cap [X] Other: ____

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 22.5

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | - | SF |
| **Total Pay Area This Page** | - | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | - | SF |
| Total Panel SF To Date | - | SF |
| **Total Pay Area To Date Including Anchor Trench** | - | |
| Initial Quantity Previous | - | SF |
| Initial Quantity This Page | - | SF |
| Initial Quantity To Date | - | SF |

# Appendix A8

# Seam Testing Chain of Custody Form

## SEAM TESTING
# CHAIN OF CUSTODY FORM

SEND YOUR SEAMS TO

PROJECT NAME / PROJECT NUMBER: _____
PROJECT LOCATION: _____

| No. | Seam ID (Include Seam ID, Panel ID, welder, etc.) | MATERIAL DESCRIPTION | FUSION | EXTRUSION | Solvent Weld |
|---|---|---|---|---|---|
| 1 | | | | | |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |

TEST METHOD
*(Please check which test method is applicable)*

O SHEAR – ASTM 04437
PEEL – ASTM 04437

O SHEAR – ASTM 06214
PEEL – ASTM 06214

O SHEAR – ASTM 04437 NSF Modified
Crosshead Speed = 2"/min
PEEL – ASTM 04437 NSF Modified
Crosshead Speed = 2"/min

O SHEAR – ASTM 04437 NSF Modified
Crosshead Speed = 20"/min
PEEL – ASTM 04437 NSF Modified
Crosshead Speed 20"/min

O SHEAR – ASTM 06392
PEEL – ASTM 06392
HDPE

O SHEAR – ASTM 03083
Crosshead Speed = 20"/min
PEEL – ASTM 0413
Crosshead Speed = 2"/min

O SHEAR – ASTM 06392
PEEL – ASTM 06392
LLDPE/PVC

O SHEAR – ASTM 0751
PEEL – ASTM 0413
Crosshead Speed = 2"/min

SPECIFICATIONS/NOTES:
OPEN on SATURDAYS for SEAM TESTING.
To ensure that your package is delivered/received on Saturdays; please fax, e-mail or call to let us know the AIRBILL # of your package. This helps us track for SATURDAY DELIVERY.

Thickness required? O Yes O NO
SOLVENT WELD
Curing Time: _____ Curing Temp:_____

**REPORT TO:**
Name: _____
Company: _____
Address: _____
_____
Tel No.: _____
Fax No.: _____
E-mail: _____

**FIELD CONTACT:**
Name: _____
Pager: _____
Mobil: _____
Phone: _____
Fax: _____
E-mail: _____

**RELEASED BY:**
Name: _____
Company: _____
Date/Time: _____

**RECEIVED BY:**
Name: _____
Precision Geosynthetic Labs
Date/Time: _____

**Shipped Via**
O Fedex
O UPS
O Airborne
O DHL
O US Mail
O Hand Carry
O Others

# Appendix A9

# Seam Control and Non-Destructive Test Log

# Environmental Specialties International, Inc.

## Seam Control Form

Page _____ of _____

**Project Name:** _____ **Job #** _____ **Superintendent:** _____

**Material Type:** _____ **Cell** ☐ **Air Pressure Test** _____ **PSI**

**Job Description:** _____ **Pond** ☐ **Air Pressure Hold Time** _____ **Minutes**

**Reported By** _____ **Other** _____ **Cap** ☐ **Allowable Air Pressure Loss** _____ **PSI**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | : | : | | |
| **Seam Notes** | | | | | | | | | | | | | | |

# Appendix A10

# Repair Log

# Environmental Specialties International, Inc.
## Repair Report

Page _____ of _____

**Reported By:** _____ **Superintendent:** _____ **Job # :** _____

**Project Name:** _____ **Cell** ☐ **Cap** ☐

**Material Type:** _____ **Pond** ☐ **Other** _____

**Job Description:** _____

| **Damage Codes** | | | | **SF Patch Material** | **Test Type** | **Abbrv.** | **Repair Types** |
|---|---|---|---|---|---|---|---|
| CR –Crease | BO –Burn Out | PB –Pipe Boot | CF –Custom Fit | | Vacuum | *S=South | C--Cap Strip |
| DS –Destruct Sample | FS --Failed Seam | MatD –Material Defect | LL –Lost Lap | | Air Pressure | *N=North | P--Patch |
| SI –Subgrade Irregularity | WR –Wrinkle | WS –Welder Restart | MD –Mechanical Damage | **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| SJ –Seam Joint | AV –Airvent | RW –Roller Wrinkle | DO –Damage By Others | | Air Lance | *E=East | |
| | AO –Add On | FM –Fishmouth | AT –Air test | | | | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |
| | | | | | | x | | | | | | | |

Rev 5-26-09

# Appendix A11

# Conformance Test Chain of Custody Form

# CONFORMANCE TEST CHAIN OF CUSTODY FORM

Page _____ of _____

PROJECT NAME / PROJECT NUMBER: _____

PROJECT LOCATION: _____

**GEOMEMBRANE TESTING**

| Sample ID | Thickness ASTM D5199 or D5994 | Density ASTM D1505 Or D792 | Carbon Black Content ASTM D1603 | Carbon Dispersion D3015 / D5596 | Tensile ASTM D638 GM13 / NSF54 | Tear Resistance ASTM D1004 (Die C) | Puncture D4833 /101CM2065 | Melt Flow Index ASTM D1238, cond. E | Dimensional Stability ASTM D1204 | Low Temp. Brittleness D746 / D1790 | NCTL ASTM D5397 Hours _____ | Other ASTM _____ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

## NONWOVEN OR WOVEN GEOTXTILE TESTING

| Sample ID | Thickness ASTM D5199 Or D1777 | Mass Per Area ASTM D5261 or D3776 | Grab Tensile ASTM D4632 | Trapezoid Tear ASTM D4533 | Puncture Resistance ASTM D4833 | Mullen Burst ASTM D3776 | Permittivity ASTM D4491 | AOS ASTM D4751 | Wide Width Tensile ASTM D4595 | UV (hrs _____) ASTM D4355 | Other ASTM _____ | Other ASTM _____ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

## GEOCOMPOSITE / GEONET / GEOGRID TESTING

| Sample ID | Thickness ASTM D5199 or D1777 | Density ASTM1505 or D792 | Carbon Black Content ASTM D1603 | Mass Per Area ASRM D5261 or D3776 | Melt Flow Index ASTM D1238, cond. E | Peel ASTM D413 F904 or GRI-GC7 | Transmissivity* ASTM D4716 | Compression ASTM D1621 | Tensile Strength ASTM D1682 or D5035 | Wide Width Tensile ASTM D4595 | Rib Tensile Strength GRI-GG1 | Junction Strength GRI-GG2 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

* Transmissivity Test Parameters: Normal Load: _____, Gradient: _____, Seating Time: _____, Boundary Condition: _____

# CONFORMANCE TEST CHAIN OF CUSTODY FORM

Page _____ of _____

| **REPORT TO:** | **FIELD CONTACT:** | **Released by:** | **Shipped Via:** |
|---|---|---|---|
| Name: _____ | Name: _____ | Name: _____ | O Fedex |
| Company: _____ | Pager: _____ | Date/Time: _____ | O UPS |
| Address: _____ | Mobil: _____ | **Received by:** | O Airborne |
| _____ | Phone: _____ | Name: _____ | O DHL |
| Tel No.: _____ | Fax: _____ | PGL | O US Mail |
| Fax No.: _____ | E-mail: _____ | Date/Time: _____ | O Others |
| E-mail: _____ | | | |

# Appendix A12

# Destructive Seam Field Test

# Environmental Specialties International, Inc.
## Destructive Sample Information

Page _____ of _____

**Project Name:** _____ **Job #** _____ **Superintendent:** _____

**Material Type:** _____

**Job Description:** _____

**Reported By** _____ **Other** _____

**Cell** ☐ **Pond** ☐ **Cap** ☐

**Peel Test Extrusion Minimum** _____ PPI

**Peel Test Fusion Minimum** _____ PPI

**Shear Test Minimum** _____ PPI

| D.S No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A / B | Coupon 2 A / B | Coupon 3 A / B | Coupon 4 A / B | Coupon 5 A / B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |
| | | | | | | | | Peel | | | | | | |
| | DS Location and Notes | | | | | | | Shear | | | | | | |

*Rev 2-26-10*

# Appendix A13

# Destructive Sample Tracking Summary

LANGAN

# Geosynthetic Installer
# Destructive Sample Tracking Summary

Sheet #_____

| | | | | | | |
|---|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | | Notes, Observations, Comments: |
| Project No. | | Layer | Primary | Secondary | Tertiary | |
| Owner/Contr. | | | | | | |
| QA Monitor | | | | | | |

| DS No. | Seam No. | Machine/ Operator | Date Welded | Roll No. | Lot No. | QA Monitor | Average Test Results | | | | Overall (P/F) | Comments and Subsequent Tracking No.'s |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Lab (P/F) | | Field (P/F) | | | |
| | | | | | | | Peel | Shear | Peel | Shear | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | |

LANGAN

# Independent CQA Monitor
# Destructive Sample Tracking Summary

Sheet #_____

| | | | | | | |
|---|---|---|---|---|---|---|
| Project Name | | Material Desc. | | | | Notes, Observations, Comments: |
| Project No. | | Layer | Primary | Secondary | Tertiary | |
| Owner/Contr. | | | | | | |
| QA Monitor | | | | | | |


| DS No. | Seam No. | Machine/ Operator | Date Welded | Roll No. | Lot No. | QA Monitor | Average Test Results | | | | Overall (P/F) | Comments and Subsequent Tracking No.'s |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Lab (P/F) | | Field (P/F) | | | |
| | | | | | | | Peel | Shear | Peel | Shear | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | |


# Appendix A14

# Penetration Sealing Observations / Cap to Barrier Installation Observation

| **Project:** Study Area 6 South | **Date:** _____ |
|---|---|

QA – Gas Vent and Piezometer Penetrations








| ***Check applicable Detail:**<br>☐ Prefabricated material design dimensions<br>☐ 18-in. overlap between boot and geomembrane<br>☐ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure<br>☐ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection<br>☐ If penetration is greater than 4-in. in diameter, a second clamp shall be used.<br>☐ Boot connection field tested to ensure seal (ex. vacuum box testing) | **Location:**<br><br>**Independent CQA Monitor Signature:**<br><br>_____ |
|---|---|

**Comments:**

| **Project:** Study Area 6 South | **Date:** _____ |
|---|---|

QA – Groundwater Collection Manhole Penetration




Note - GCL only required if the boot is located in an area where the LLDPE is below the water table

| ***Check applicable Detail:**<br>☐ Note any dimension changes in comments section<br>☐ 18-in. overlap between boot and geomembrane<br>☐ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure<br>☐ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection<br>☐ If penetration is greater than 4-in. in diameter, a second clamp shall be used<br>☐ Boot connection field tested to ensure seal (ex. vacuum box testing) | **Location:**<br><br>**Independent CQA Monitor Signature:**<br>_____ |
|---|---|

**Comments:**


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** _____ |
|---|---|

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

| ***Check applicable Detail:**<br>☐ Box Cut Dimension<br>☐ Barrier wall clean/exposed<br>☐ Sand Bentonite Mix | **Location:** |
|---|---|
| **Comments:** | **AmecFW QA Signature:** _____ |

# Appendix A15

# Geosynthetic Daily Inspection Report

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES



# SITE OBSERVATION REPORT

| | | |
|---|---|---|
| **PROJECT No.:**<br>**PROJECT:**<br><br>**LOCATION:** | **CLIENT:**<br><br>**TASK.:** | **DATE:**<br>**WEATHER:**<br>**TIME:** |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day** |

***Site Activities***

***Non-Conformance Item / Corrective Actions***

***Action Items Pending***

***Action Items – Weekly Completions***

***Near Misses / Incidents***

***Future Activities Scheduled***

***Photograph Log***

Cc

By:

| | | |
|---|---|---|
| **PROJECT No.:**<br>**PROJECT:**<br><br>**LOCATION:** | **CLIENT:**<br><br>**TASK.:** | **DATE:**<br><br>**WEATHER:**<br><br>**TIME:** |

| **Daily QA Documents Completed** | | | | | |
|---|---|---|---|---|---|
| | Sheet #'s | Comment | | Sheet #'s | Comment |
| A2 – Receiving and Inspection | | | A11 – Conformance Test Chain of Custody | | |
| A3 – Photo Log | | | A12 – Destructive Seam Field Test | | |
| A4 – Geosynthetic Inventory Log | | | A13 – Destructive Lab Sample Tracking Summary | | |
| A5 -Subgrade Surface | | | A14 – Penetration and Edge Detail Observations | | |
| A6 – Trial Weld Log | | | A16 – Notice Non-Compliance / Corrective Action | | |
| A7 – Panel Placement Log | | | *List Others:* | | |
| A8 – Seam Testing Chain of Custody | | | | | |
| A9 – Seam / Non-Destructive Test Log | | | | | |
| A10 – Repair Log | | | | | |

# Appendix A16

# Notice of Non-Compliance and Corrective Action Form

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # _____

| General Project Information | |
|---|---|
| Project Name<br>Project No.<br>Owner/Contr.<br>QA Monitor | Date<br>Contractor in NC<br>Non-Compliance No.<br>Notes: |
| **Reference** | |
| Item<br>Specification Sec. No. | Drawing No.<br>Other: |
| **Description of Non-Compliance** | |
| Cross Reference (QA Inspection Form & Sheet No.): | |
| **Contractor's Response** | |
| | |
| **Follow Up Action Required** | |
| | |
| **Follow Up Action Taken** | |
| Cross Reference (QA Inspection Form & Sheet No.): | |

Geosynthetic Installer Representative _____ Date _____

Independent CQA Monitor _____ Date _____

# Appendix C
# SA-6 South Certificate of Completion

***LANGAN***

# Certificate of Completion

Sheet # 1

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | LLDPE Geomembrane Cap | | |
| Project No. | 100530001 | Layer | **Primary** | Secondary | Tertiary |
| Owner/ Contr. | Honeywell / AmecFW | Type | Partial | Substantial | **Final** |
| QA Monitor | Langan | Date | 12/01/2015 | | |

Description and Area of Work Being Certified: Completion of capping of SA-6 South which included: placement of GVL/GCL, placement of LLDPE geomembrane, and placement of GDL. Material was placed in accordance with the Record Drawings and project specifications. To date, the geosynthetic components of SA-6 South are complete and summarized in the *QA Completion Report*.

I hereby certify that the above identified work has been inspected and it has been properly installed. I further certify all required testing has been completed and the results are acceptable to the CQA Officer. The liner system is suitable for its intended use.

| **Independent CQA Monitor** | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 3/30/16 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| **Geosynthetic Installer Representative** | |
|---|---|
| Name: | Fortino Ayala |
| Date: | 3/30/16 |
| Title | Superintendent |
| Representing: | Environmental Specialties International Inc. |
| Signature: | |

# Appendix D: Survey Construction Details

*D1. Final Maser Subgrade Tables*
*D2. Subgrade Construction Control Grid*

# *D1. Final Maser Subgrade Tables*

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

# SA-6 South Cap Subgrade: Grid Points (Table 1.0)

| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
|---|---|---|---|---|---|---|---|---|
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2 | 685518.44 | 601481.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 3 | 685543.44 | 601481.51 | 15.3 | GRID | 7/2/2015 | 15.3 | 0.0 | Point surveyed within Tolerance |
| 4 | 685493.44 | 601506.51 | 14.2 | GRID | 7/2/2015 | 14.2 | 0.0 | Point surveyed within Tolerance |
| 6 | 685543.44 | 601506.51 | 16.6 | GRID | 7/2/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 7 | 685568.44 | 601506.51 | 17.0 | GRID | 7/2/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |
| 8 | 685468.44 | 601531.51 | 13.1 | GRID | 7/2/2015 | 13.1 | 0.0 | Point surveyed within Tolerance |
| 9 | 685493.44 | 601531.51 | 13.7 | GRID | 7/2/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 10 | 685543.44 | 601531.51 | 14.8 | GRID | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 11 | 685568.44 | 601531.51 | 15.0 | GRID | 7/2/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 12 | 685593.44 | 601531.51 | 18.1 | GRID | 7/2/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 14 | 685468.44 | 601556.51 | 13.9 | GRID | 7/2/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 15 | 685493.44 | 601556.51 | 15.9 | GRID | 7/2/2015 | 15.8 | -0.1 | Point surveyed within Tolerance |
| 16 | 685518.44 | 601556.51 | 16.7 | GRID | 7/2/2015 | 16.8 | 0.1 | Point surveyed within Tolerance |
| 17 | 685543.44 | 601556.51 | 17.0 | GRID | 7/2/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 18 | 685568.44 | 601556.51 | 14.1 | GRID | 7/2/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 19 | 685593.44 | 601556.51 | 17.4 | GRID | 7/2/2015 | 17.5 | 0.1 | Point surveyed within Tolerance |
| 20 | 685443.44 | 601581.51 | 13.3 | GRID | 7/2/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 21 | 685468.44 | 601581.51 | 14.4 | GRID | 7/2/2015 | 14.4 | 0.0 | Point surveyed within Tolerance |
| 22 | 685493.44 | 601581.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 23 | 685518.44 | 601581.51 | 16.6 | GRID | 7/2/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 24 | 685543.44 | 601581.51 | 17.5 | GRID | 7/2/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 25 | 685568.44 | 601581.51 | 17.0 | GRID | 7/2/2015 | 17.1 | 0.1 | Point surveyed within Tolerance |
| 26 | 685418.44 | 601606.51 | 11.9 | GRID | 7/2/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 27 | 685443.44 | 601606.51 | 13.8 | GRID | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 29 | 685493.44 | 601606.51 | 15.3 | GRID | 7/2/2015 | 15.3 | 0.0 | Point surveyed within Tolerance |
| 30 | 685518.44 | 601606.51 | 16.2 | GRID | 7/2/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 31 | 685543.44 | 601606.51 | 16.7 | GRID | 7/2/2015 | 16.8 | 0.1 | Point surveyed within Tolerance |
| 32 | 685393.44 | 601631.51 | 11.4 | GRID | 7/2/2015 | 11.5 | 0.1 | Point surveyed within Tolerance |
| 33 | 685418.44 | 601631.51 | 13.2 | GRID | 7/2/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 34 | 685443.44 | 601631.51 | 13.8 | GRID | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 35 | 685468.44 | 601631.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 36 | 685493.44 | 601631.51 | 14.8 | GRID | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 37 | 685518.44 | 601631.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 38 | 685543.44 | 601631.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 39 | 685393.44 | 601656.51 | 12.6 | GRID | 7/2/2015 | 12.7 | 0.1 | Point surveyed within Tolerance |
| 40 | 685443.44 | 601656.51 | 13.7 | GRID | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 41 | 685468.44 | 601656.51 | 15.6 | GRID | 7/2/2015 | 15.7 | 0.1 | Point surveyed within Tolerance |
| 42 | 685493.44 | 601656.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 43 | 685518.44 | 601656.51 | 16.6 | GRID | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 44 | 685368.44 | 601681.51 | 11.6 | GRID | 7/2/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 45 | 685393.44 | 601681.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 46 | 685443.44 | 601681.51 | 13.7 | GRID | 7/2/2015 | 13.6 | -0.1 | Point surveyed within Tolerance |
| 47 | 685468.44 | 601681.51 | 15.5 | GRID | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 48 | 685493.44 | 601681.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 49 | 685343.44 | 601706.51 | 11.0 | GRID | 7/2/2015 | 10.9 | -0.1 | Point surveyed within Tolerance |
| 50 | 685393.44 | 601706.51 | 16.0 | GRID | 7/2/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 51 | 685443.44 | 601706.51 | 13.6 | GRID | 7/2/2015 | 13.5 | -0.1 | Point surveyed within Tolerance |
| 52 | 685468.44 | 601706.51 | 15.4 | GRID | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 53 | 685493.44 | 601706.51 | 14.3 | GRID | 7/2/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 54 | 685318.44 | 601731.51 | 10.7 | GRID | 7/2/2015 | 10.6 | -0.1 | Point surveyed within Tolerance |
| 55 | 685368.44 | 601731.51 | 16.2 | GRID | 7/2/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 56 | 685393.44 | 601731.51 | 16.3 | GRID | 7/2/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 57 | 685443.44 | 601731.51 | 13.5 | GRID | 7/2/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 58 | 685343.44 | 601756.51 | 16.6 | GRID | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 59 | 685368.44 | 601756.51 | 16.3 | GRID | 7/2/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 61 | 685443.44 | 601756.51 | 13.5 | GRID | 7/2/2015 | 13.6 | 0.1 | Point surveyed within Tolerance |
| 62 | 685293.44 | 601781.51 | 10.5 | GRID | 7/2/2015 | 10.4 | -0.1 | Point surveyed within Tolerance |
| 63 | 685318.44 | 601781.51 | 17.4 | GRID | 7/2/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 64 | 685343.44 | 601781.51 | 16.9 | GRID | 7/2/2015 | 16.9 | 0.0 | Point surveyed within Tolerance |
| 65 | 685368.44 | 601781.51 | 16.5 | GRID | 7/2/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 66 | 685393.44 | 601781.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 67 | 685418.44 | 601781.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 69 | 685268.44 | 601806.51 | 11.0 | GRID | 7/2/2015 | 11.0 | 0.0 | Point surveyed within Tolerance |
| 70 | 685318.44 | 601806.51 | 18.1 | GRID | 7/2/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 71 | 685343.44 | 601806.51 | 17.7 | GRID | 7/2/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 72 | 685368.44 | 601806.51 | 17.1 | GRID | 7/2/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 73 | 685393.44 | 601806.51 | 16.7 | GRID | 7/2/2015 | 16.6 | -0.1 | Point surveyed within Tolerance |
| 74 | 685418.44 | 601806.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 75 | 685243.44 | 601831.51 | 12.7 | GRID | 7/2/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 77 | 685318.44 | 601831.51 | 15.7 | GRID | 7/2/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 78 | 685343.44 | 601831.51 | 18.3 | GRID | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 79 | 685368.44 | 601831.51 | 17.7 | GRID | 7/2/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 80 | 685393.44 | 601831.51 | 17.2 | GRID | 7/2/2015 | 17.3 | 0.1 | Point surveyed within Tolerance |
| 81 | 685243.44 | 601856.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 82 | 685268.44 | 601856.51 | 16.1 | GRID | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 83 | 685293.44 | 601856.51 | 15.7 | GRID | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 85 | 685368.44 | 601856.51 | 18.0 | GRID | 7/2/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 86 | 685218.44 | 601881.51 | 15.6 | GRID | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 87 | 685243.44 | 601881.51 | 16.4 | GRID | 7/2/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 88 | 685268.44 | 601881.51 | 18.7 | GRID | 7/2/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 89 | 685293.44 | 601881.51 | 18.6 | GRID | 7/2/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 90 | 685343.44 | 601881.51 | 15.2 | GRID | 7/2/2015 | 15.2 | 0.0 | Point surveyed within Tolerance |
| 91 | 685368.44 | 601881.51 | 11.8 | GRID | 7/2/2015 | 11.8 | 0.0 | Point surveyed within Tolerance |
| 92 | 685193.44 | 601906.51 | 15.5 | GRID | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 93 | 685218.44 | 601906.51 | 16.3 | GRID | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 94 | 685243.44 | 601906.51 | 18.7 | GRID | 7/2/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 95 | 685268.44 | 601906.51 | 18.6 | GRID | 7/2/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 96 | 685293.44 | 601906.51 | 18.5 | GRID | 7/2/2015 | 18.4 | -0.1 | Point surveyed within Tolerance |
| 97 | 685318.44 | 601906.51 | 18.3 | GRID | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 99 | 685193.44 | 601931.51 | 15.7 | GRID | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 101 | 685243.44 | 601931.51 | 18.6 | GRID | 7/2/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 102 | 685268.44 | 601931.51 | 18.5 | GRID | 7/2/2015 | 18.4 | -0.1 | Point surveyed within Tolerance |
| 103 | 685293.44 | 601931.51 | 18.4 | GRID | 7/2/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 104 | 685168.44 | 601956.51 | 14.6 | GRID | 7/2/2015 | 14.6 | 0.0 | Point surveyed within Tolerance |
| 105 | 685193.44 | 601956.51 | 18.0 | GRID | 7/14/2015 | 18.1 | 0.1 | Point surveyed within Tolerance |
| 107 | 685243.44 | 601956.51 | 18.3 | GRID | 7/14/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 108 | 685268.44 | 601956.51 | 18.3 | GRID | 7/14/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 109 | 685293.44 | 601956.51 | 18.2 | GRID | 7/14/2015 | 18.3 | 0.1 | Point surveyed within Tolerance |
| 110 | 685143.44 | 601981.51 | 13.6 | GRID | 7/14/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 111 | 685168.44 | 601981.51 | 17.2 | GRID | 7/14/2015 | 17.3 | 0.1 | Point surveyed within Tolerance |
| 112 | 685193.44 | 601981.51 | 17.4 | GRID | 7/14/2015 | 17.5 | 0.1 | Point surveyed within Tolerance |
| 113 | 685218.44 | 601981.51 | 17.7 | GRID | 7/14/2015 | 17.8 | 0.1 | Point surveyed within Tolerance |
| 114 | 685243.44 | 601981.51 | 17.8 | GRID | 7/14/2015 | 17.9 | 0.1 | Point surveyed within Tolerance |
| 115 | 685268.44 | 601981.51 | 17.9 | GRID | 7/14/2015 | 18.0 | 0.1 | Point surveyed within Tolerance |
| 116 | 685118.44 | 602006.51 | 13.0 | GRID | 7/14/2015 | 13.1 | 0.1 | Point surveyed within Tolerance |
| 117 | 685168.44 | 602006.51 | 16.6 | GRID | 7/14/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 118 | 685193.44 | 602006.51 | 16.8 | GRID | 7/14/2015 | 16.9 | 0.1 | Point surveyed within Tolerance |
| 119 | 685218.44 | 602006.51 | 17.1 | GRID | 7/14/2015 | 17.2 | 0.1 | Point surveyed within Tolerance |
| 121 | 685268.44 | 602006.51 | 17.5 | GRID | 7/14/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 122 | 685118.44 | 602031.51 | 13.0 | GRID | 7/14/2015 | 13.1 | 0.1 | Point surveyed within Tolerance |
| 123 | 685143.44 | 602031.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 124 | 685168.44 | 602031.51 | 16.2 | GRID | 7/14/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 125 | 685193.44 | 602031.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 126 | 685218.44 | 602031.51 | 16.5 | GRID | 7/14/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 127 | 685118.44 | 602056.51 | 14.0 | GRID | 7/14/2015 | 13.9 | -0.1 | Point surveyed within Tolerance |
| 128 | 685143.44 | 602056.51 | 16.2 | GRID | 7/14/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 129 | 685168.44 | 602056.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 130 | 685193.44 | 602056.51 | 16.2 | GRID | 7/14/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 131 | 685218.44 | 602056.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 132 | 685068.44 | 602081.51 | 4.4 | GRID | 7/14/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 134 | 685143.44 | 602081.51 | 16.5 | GRID | 7/14/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 135 | 685168.44 | 602081.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 136 | 685193.44 | 602081.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 137 | 685218.44 | 602081.51 | 16.1 | GRID | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 140 | 685093.44 | 602106.51 | 4.8 | GRID | 7/14/2015 | 4.9 | 0.1 | Point surveyed within Tolerance |
| 141 | 685118.44 | 602106.51 | 5.0 | GRID | 7/14/2015 | 5.1 | 0.1 | Point surveyed within Tolerance |
| 142 | 685168.44 | 602106.51 | 16.6 | GRID | 7/14/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 143 | 685193.44 | 602106.51 | 16.3 | GRID | 7/14/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 146 | 685143.44 | 602131.51 | 5.4 | GRID | 7/14/2015 | 5.5 | 0.1 | Point surveyed within Tolerance |
| 138 | 685043.44 | 602106.51 | 4.6 | GRID | 7/24/2015 | 4.5 | -0.1 | Point surveyed within Tolerance |
| 144 | 685068.44 | 602131.51 | 15.0 | GRID | 7/24/2015 | 15.0 | 0.0 | Point surveyed within Tolerance |
| 145 | 685118.44 | 602131.51 | 5.2 | GRID | 7/24/2015 | 5.1 | -0.1 | Point surveyed within Tolerance |
| 147 | 685043.44 | 602156.51 | 15.1 | GRID | 7/24/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 148 | 685093.44 | 602156.51 | 17.9 | GRID | 7/24/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 149 | 685143.44 | 602156.51 | 5.6 | GRID | 7/24/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 150 | 685168.44 | 602156.51 | 5.8 | GRID | 7/24/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 151 | 684993.44 | 602181.51 | 5.6 | GRID | 7/24/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 152 | 685018.44 | 602181.51 | 15.7 | GRID | 7/24/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 153 | 685043.44 | 602181.51 | 15.2 | GRID | 7/24/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 154 | 685068.44 | 602181.51 | 17.5 | GRID | 7/24/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 155 | 685093.44 | 602181.51 | 17.5 | GRID | 7/24/2015 | 17.6 | 0.1 | Point surveyed within Tolerance |
| 156 | 685118.44 | 602181.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 157 | 685143.44 | 602181.51 | 14.7 | GRID | 7/24/2015 | 14.7 | 0.0 | Point surveyed within Tolerance |
| 159 | 684968.44 | 602206.51 | 6.1 | GRID | 7/24/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 160 | 685018.44 | 602206.51 | 18.3 | GRID | 7/24/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 161 | 685068.44 | 602206.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 162 | 684993.44 | 602231.51 | 18.8 | GRID | 7/24/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 163 | 685018.44 | 602231.51 | 16.0 | GRID | 7/24/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 164 | 685068.44 | 602231.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 165 | 685093.44 | 602231.51 | 15.0 | GRID | 7/24/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 166 | 684968.44 | 602256.51 | 19.4 | GRID | 7/24/2015 | 19.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 167 | 684993.44 | 602256.51 | 19.1 | GRID | 7/24/2015 | 19.1 | 0.0 | Point surveyed within Tolerance |
| 168 | 685018.44 | 602256.51 | 16.3 | GRID | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 169 | 685043.44 | 602256.51 | 18.4 | GRID | 7/24/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 170 | 685068.44 | 602256.51 | 18.1 | GRID | 7/24/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 171 | 684918.44 | 602281.51 | 7.1 | GRID | 7/24/2015 | 7.2 | 0.1 | Point surveyed within Tolerance |
| 172 | 684968.44 | 602281.51 | 19.6 | GRID | 7/24/2015 | 19.6 | 0.0 | Point surveyed within Tolerance |
| 173 | 684993.44 | 602281.51 | 16.8 | GRID | 7/24/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 174 | 685018.44 | 602281.51 | 19.0 | GRID | 7/24/2015 | 19.0 | 0.0 | Point surveyed within Tolerance |
| 175 | 685043.44 | 602281.51 | 18.7 | GRID | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 176 | 685068.44 | 602281.51 | 18.4 | GRID | 7/24/2015 | 18.4 | 0.0 | Point surveyed within Tolerance |
| 178 | 684943.44 | 602306.51 | 20.2 | GRID | 7/24/2015 | 20.2 | 0.0 | Point surveyed within Tolerance |
| 179 | 684968.44 | 602306.51 | 19.9 | GRID | 7/24/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 180 | 684993.44 | 602306.51 | 17.1 | GRID | 7/24/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 181 | 685018.44 | 602306.51 | 19.3 | GRID | 7/24/2015 | 19.3 | 0.0 | Point surveyed within Tolerance |
| 182 | 685043.44 | 602306.51 | 16.4 | GRID | 7/24/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 183 | 684918.44 | 602331.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 184 | 684943.44 | 602331.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 185 | 684968.44 | 602331.51 | 17.6 | GRID | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 186 | 684993.44 | 602331.51 | 19.8 | GRID | 7/24/2015 | 19.8 | 0.0 | Point surveyed within Tolerance |
| 187 | 685018.44 | 602331.51 | 17.0 | GRID | 7/24/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |
| 188 | 684893.44 | 602356.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 189 | 684918.44 | 602356.51 | 17.9 | GRID | 7/24/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 190 | 684943.44 | 602356.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 191 | 684968.44 | 602356.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 192 | 684993.44 | 602356.51 | 17.5 | GRID | 7/24/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 193 | 684843.44 | 602381.51 | 8.7 | GRID | 7/24/2015 | 8.7 | 0.0 | Point surveyed within Tolerance |
| 194 | 684868.44 | 602381.51 | 17.4 | GRID | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 195 | 684893.44 | 602381.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 196 | 684918.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 197 | 684943.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 198 | 684968.44 | 602381.51 | 17.8 | GRID | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 199 | 684993.44 | 602381.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 200 | 684868.44 | 602406.51 | 17.0 | GRID | 7/24/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 201 | 684893.44 | 602406.51 | 17.3 | GRID | 7/24/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 202 | 684918.44 | 602406.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 203 | 684943.44 | 602406.51 | 17.7 | GRID | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 204 | 684968.44 | 602406.51 | 17.8 | GRID | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 206 | 684843.44 | 602431.51 | 16.1 | GRID | 7/24/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 207 | 684868.44 | 602431.51 | 16.6 | GRID | 7/24/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 208 | 684893.44 | 602431.51 | 17.0 | GRID | 7/24/2015 | 16.9 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 209 | 684918.44 | 602431.51 | 17.4 | GRID | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 210 | 684943.44 | 602431.51 | 17.6 | GRID | 7/24/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 214 | 684868.44 | 602456.51 | 16.3 | GRID | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 215 | 684893.44 | 602456.51 | 16.7 | GRID | 7/24/2015 | 16.7 | 0.0 | Point surveyed within Tolerance |
| 216 | 684918.44 | 602456.51 | 17.1 | GRID | 7/24/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 222 | 684893.44 | 602481.51 | 16.4 | GRID | 7/24/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 223 | 684918.44 | 602481.51 | 16.9 | GRID | 7/24/2015 | 16.8 | -0.1 | Point surveyed within Tolerance |
| 205 | 684818.44 | 602431.51 | 15.0 | GRID | 8/10/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 211 | 684793.44 | 602456.51 | 14.0 | GRID | 8/10/2015 | 14.0 | 0.0 | Point surveyed within Tolerance |
| 212 | 684818.44 | 602456.51 | 15.2 | GRID | 8/10/2015 | 15.2 | 0.0 | Point surveyed within Tolerance |
| 213 | 684843.44 | 602456.51 | 15.7 | GRID | 8/10/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 218 | 684793.44 | 602481.51 | 14.3 | GRID | 8/10/2015 | 14.2 | -0.1 | Point surveyed within Tolerance |
| 219 | 684818.44 | 602481.51 | 14.9 | GRID | 8/10/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 220 | 684843.44 | 602481.51 | 15.4 | GRID | 8/10/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 221 | 684868.44 | 602481.51 | 15.9 | GRID | 8/10/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 224 | 684768.44 | 602506.51 | 13.3 | GRID | 8/10/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 225 | 684793.44 | 602506.51 | 14.0 | GRID | 8/10/2015 | 14.0 | 0.0 | Point surveyed within Tolerance |
| 226 | 684818.44 | 602506.51 | 14.6 | GRID | 8/10/2015 | 14.5 | -0.1 | Point surveyed within Tolerance |
| 227 | 684843.44 | 602506.51 | 15.1 | GRID | 8/10/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 228 | 684868.44 | 602506.51 | 15.6 | GRID | 8/10/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 229 | 684893.44 | 602506.51 | 16.1 | GRID | 8/10/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 232 | 684793.44 | 602531.51 | 16.3 | GRID | 8/10/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 233 | 684818.44 | 602531.51 | 16.8 | GRID | 8/10/2015 | 16.7 | -0.1 | Point surveyed within Tolerance |
| 234 | 684843.44 | 602531.51 | 17.3 | GRID | 8/10/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 235 | 684868.44 | 602531.51 | 17.9 | GRID | 8/10/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 239 | 684843.44 | 602556.51 | 17.1 | GRID | 8/10/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 240 | 684868.44 | 602556.51 | 17.6 | GRID | 8/10/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 217 | 684768.44 | 602481.51 | 13.2 | GRID | 8/12/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 230 | 684743.44 | 602531.51 | 12.6 | GRID | 8/12/2015 | 12.6 | 0.0 | Point surveyed within Tolerance |
| 231 | 684768.44 | 602531.51 | 15.8 | GRID | 8/12/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 245 | 684793.44 | 602581.51 | 14.1 | GRID | 8/12/2015 | 14.1 | 0.0 | Point surveyed within Tolerance |
| 246 | 684818.44 | 602581.51 | 14.1 | GRID | 8/12/2015 | 14.1 | 0.0 | Point surveyed within Tolerance |
| 247 | 684843.44 | 602581.51 | 14.3 | GRID | 8/12/2015 | 14.4 | 0.1 | Point surveyed within Tolerance |
| 252 | 684818.44 | 602606.51 | 14.3 | GRID | 8/12/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 236 | 684718.44 | 602556.51 | 7.5 | GRID | 8/13/2015 | 7.4 | -0.1 | Point surveyed within Tolerance |
| 237 | 684743.44 | 602556.51 | 15.6 | GRID | 8/13/2015 | 15.7 | 0.1 | Point surveyed within Tolerance |
| 241 | 684693.44 | 602581.51 | 5.8 | GRID | 8/13/2015 | 5.8 | 0.0 | Point surveyed within Tolerance |
| 242 | 684718.44 | 602581.51 | 13.2 | GRID | 8/13/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 243 | 684743.44 | 602581.51 | 15.7 | GRID | 8/13/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 244 | 684768.44 | 602581.51 | 13.9 | GRID | 8/13/2015 | 13.8 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.6) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 249 | 684743.44 | 602606.51 | 16.5 | GRID | 8/13/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 250 | 684768.44 | 602606.51 | 16.0 | GRID | 8/13/2015 | 16.0 | 0.0 | Point surveyed within Tolerance |
| 251 | 684793.44 | 602606.51 | 14.5 | GRID | 8/13/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 255 | 684768.44 | 602631.51 | 17.0 | GRID | 8/13/2015 | 17.1 | 0.1 | Point surveyed within Tolerance |
| 256 | 684793.44 | 602631.51 | 16.3 | GRID | 8/13/2015 | 16.4 | 0.1 | Point surveyed within Tolerance |
| 257 | 684818.44 | 602631.51 | 16.2 | GRID | 8/13/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 261 | 684793.44 | 602656.51 | 14.5 | GRID | 8/13/2015 | 14.6 | 0.1 | Point surveyed within Tolerance |
| 248 | 684693.44 | 602606.51 | 5.2 | GRID | 9/4/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 253 | 684693.44 | 602631.51 | 5.5 | GRID | 9/4/2015 | 5.5 | 0.0 | Point surveyed within Tolerance |
| 254 | 684718.44 | 602631.51 | 5.8 | GRID | 9/4/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 259 | 684718.44 | 602656.51 | 6.1 | GRID | 9/4/2015 | 6.0 | -0.1 | Point surveyed within Tolerance |
| 260 | 684743.44 | 602656.51 | 6.4 | GRID | 9/4/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 263 | 684743.44 | 602681.51 | 6.7 | GRID | 9/4/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 264 | 684768.44 | 602681.51 | 7.0 | GRID | 9/4/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 265 | 684793.44 | 602681.51 | 7.4 | GRID | 9/4/2015 | 7.3 | -0.1 | Point surveyed within Tolerance |
| 2069 | 684743.44 | 602706.51 | 17.8 | GRID | 9/4/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 2070 | 684743.44 | 602731.51 | 15.4 | GRID | 9/4/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 2071 | 684718.44 | 602756.51 | 15.8 | GRID | 9/4/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 2072 | 684718.44 | 602706.51 | 18.0 | GRID | 9/4/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 2073 | 684693.44 | 602706.51 | 15.4 | GRID | 9/4/2015 | 15.3 | -0.1 | Point surveyed within Tolerance |
| 2074 | 684693.44 | 602731.51 | 18.4 | GRID | 9/4/2015 | 18.5 | 0.1 | Point surveyed within Tolerance |
| 2075 | 684693.44 | 602756.51 | 18.8 | GRID | 9/4/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 2076 | 684693.44 | 602781.51 | 19.2 | GRID | 9/4/2015 | 19.3 | 0.1 | Point surveyed within Tolerance |
| 2079 | 684668.44 | 602756.51 | 16.4 | GRID | 9/4/2015 | 16.4 | 0.0 | Point surveyed within Tolerance |
| 2080 | 684668.44 | 602731.51 | 16.0 | GRID | 9/4/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 2081 | 684668.44 | 602706.51 | 18.3 | GRID | 9/4/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 2082 | 684668.44 | 602681.51 | 17.9 | GRID | 9/4/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 2083 | 684668.44 | 602656.51 | 14.9 | GRID | 9/4/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 2084 | 684643.44 | 602706.51 | 18.6 | GRID | 9/4/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 2085 | 684643.44 | 602731.51 | 16.3 | GRID | 9/4/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 2086 | 684643.44 | 602756.51 | 16.8 | GRID | 9/4/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 2090 | 684618.44 | 602731.51 | 16.6 | GRID | 9/4/2015 | 16.6 | 0.0 | Point surveyed within Tolerance |
| 2101 | 684593.44 | 602706.51 | 6.8 | GRID | 9/4/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2077 | 684668.44 | 602806.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2078 | 684668.44 | 602781.51 | 17.1 | GRID | 9/9/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 2087 | 684643.44 | 602781.51 | 17.3 | GRID | 9/9/2015 | 17.2 | -0.1 | Point surveyed within Tolerance |
| 2088 | 684643.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2089 | 684643.44 | 602831.51 | 17.7 | GRID | 9/9/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 2091 | 684618.44 | 602756.51 | 17.1 | GRID | 9/9/2015 | 17.1 | 0.0 | Point surveyed within Tolerance |
| 2092 | 684618.44 | 602781.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.7) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2093 | 684618.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2094 | 684618.44 | 602831.51 | 17.7 | GRID | 9/9/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 2095 | 684618.44 | 602856.51 | 20.3 | GRID | 9/9/2015 | 20.3 | 0.0 | Point surveyed within Tolerance |
| 2096 | 684593.44 | 602881.51 | 19.6 | GRID | 9/9/2015 | 19.5 | -0.1 | Point surveyed within Tolerance |
| 2097 | 684593.44 | 602856.51 | 19.9 | GRID | 9/9/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 2098 | 684593.44 | 602806.51 | 17.6 | GRID | 9/9/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 2099 | 684593.44 | 602781.51 | 17.5 | GRID | 9/9/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 2100 | 684593.44 | 602756.51 | 17.2 | GRID | 9/9/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 2102 | 684568.44 | 602731.51 | 7.4 | GRID | 9/9/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 2103 | 684568.44 | 602781.51 | 17.4 | GRID | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2104 | 684568.44 | 602831.51 | 19.9 | GRID | 9/9/2015 | 19.9 | 0.0 | Point surveyed within Tolerance |
| 2105 | 684568.44 | 602856.51 | 19.4 | GRID | 9/9/2015 | 19.4 | 0.0 | Point surveyed within Tolerance |
| 2106 | 684568.44 | 602881.51 | 18.8 | GRID | 9/9/2015 | 18.8 | 0.0 | Point surveyed within Tolerance |
| 2111 | 684543.44 | 602856.51 | 18.7 | GRID | 9/9/2015 | 18.8 | 0.1 | Point surveyed within Tolerance |
| 2112 | 684543.44 | 602831.51 | 19.5 | GRID | 9/9/2015 | 19.5 | 0.0 | Point surveyed within Tolerance |
| 2113 | 684543.44 | 602806.51 | 19.6 | GRID | 9/9/2015 | 19.6 | 0.0 | Point surveyed within Tolerance |
| 2114 | 684518.44 | 602831.51 | 18.6 | GRID | 9/9/2015 | 18.6 | 0.0 | Point surveyed within Tolerance |
| 2115 | 684518.44 | 602856.51 | 18.1 | GRID | 9/9/2015 | 18.2 | 0.1 | Point surveyed within Tolerance |
| 2126 | 684493.44 | 602831.51 | 9.6 | GRID | 9/9/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 2109 | 684543.44 | 602931.51 | 13.9 | GRID | 9/16/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 2110 | 684543.44 | 602906.51 | 6.4 | GRID | 9/16/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |
| 2116 | 684518.44 | 602906.51 | 12.9 | GRID | 9/16/2015 | 13.0 | 0.1 | Point surveyed within Tolerance |
| 2132 | 684468.44 | 602856.51 | 5.9 | GRID | 9/16/2015 | 6.0 | 0.1 | Point surveyed within Tolerance |
| 2108 | 684543.44 | 602956.51 | 14.3 | GRID | 9/18/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 2117 | 684518.44 | 602931.51 | 13.7 | GRID | 9/18/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 2118 | 684518.44 | 602956.51 | 16.8 | GRID | 9/18/2015 | 16.8 | 0.0 | Point surveyed within Tolerance |
| 2119 | 684518.44 | 602981.51 | 15.9 | GRID | 9/18/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 2121 | 684493.44 | 603006.51 | 14.5 | GRID | 9/18/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 2122 | 684493.44 | 602981.51 | 14.9 | GRID | 9/18/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 2123 | 684493.44 | 602956.51 | 15.5 | GRID | 9/18/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 2124 | 684493.44 | 602931.51 | 16.6 | GRID | 9/18/2015 | 16.7 | 0.1 | Point surveyed within Tolerance |
| 2125 | 684493.44 | 602906.51 | 13.4 | GRID | 9/18/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 2127 | 684468.44 | 603031.51 | 13.1 | GRID | 9/18/2015 | 13.1 | 0.0 | Point surveyed within Tolerance |
| 2128 | 684468.44 | 603006.51 | 13.5 | GRID | 9/18/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 2129 | 684468.44 | 602981.51 | 13.9 | GRID | 9/18/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 2130 | 684468.44 | 602956.51 | 14.4 | GRID | 9/18/2015 | 14.5 | 0.1 | Point surveyed within Tolerance |
| 2131 | 684468.44 | 602931.51 | 15.0 | GRID | 9/18/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 2133 | 684443.44 | 602881.51 | 7.9 | GRID | 9/18/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 2134 | 684443.44 | 602906.51 | 12.1 | GRID | 9/18/2015 | 12.1 | 0.0 | Point surveyed within Tolerance |
| 2135 | 684443.44 | 602931.51 | 13.8 | GRID | 9/18/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.8) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2136 | 684443.44 | 602956.51 | 13.3 | GRID | 9/18/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 2137 | 684443.44 | 602981.51 | 12.8 | GRID | 9/18/2015 | 12.9 | 0.1 | Point surveyed within Tolerance |
| 2138 | 684443.44 | 603006.51 | 12.4 | GRID | 9/18/2015 | 12.5 | 0.1 | Point surveyed within Tolerance |
| 2139 | 684443.44 | 603031.51 | 12.0 | GRID | 9/18/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 2146 | 684418.44 | 603006.51 | 11.3 | GRID | 9/18/2015 | 11.4 | 0.1 | Point surveyed within Tolerance |
| 2147 | 684418.44 | 602981.51 | 11.7 | GRID | 9/18/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 2148 | 684418.44 | 602956.51 | 12.1 | GRID | 9/18/2015 | 12.1 | 0.0 | Point surveyed within Tolerance |
| 2149 | 684418.44 | 602906.51 | 9.8 | GRID | 9/21/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 2150 | 684393.44 | 602931.51 | 8.6 | GRID | 9/18/2015 | 8.6 | 0.0 | Point surveyed within Tolerance |
| 2151 | 684393.44 | 602956.51 | 11.0 | GRID | 9/18/2015 | 10.9 | -0.1 | Point surveyed within Tolerance |
| 2152 | 684393.44 | 602981.51 | 10.5 | GRID | 9/18/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 2140 | 684443.44 | 603056.51 | 11.7 | GRID | 9/22/2015 | 11.6 | -0.1 | Point surveyed within Tolerance |
| 2141 | 684443.44 | 603081.51 | 11.4 | GRID | 9/22/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 2142 | 684418.44 | 603106.51 | 10.2 | GRID | 9/22/2015 | 10.2 | 0.0 | Point surveyed within Tolerance |
| 2143 | 684418.44 | 603081.51 | 10.4 | GRID | 9/22/2015 | 10.5 | 0.1 | Point surveyed within Tolerance |
| 2144 | 684418.44 | 603056.51 | 10.7 | GRID | 9/22/2015 | 10.6 | -0.1 | Point surveyed within Tolerance |
| 2145 | 684418.44 | 603031.51 | 10.9 | GRID | 9/22/2015 | 10.8 | -0.1 | Point surveyed within Tolerance |
| 2153 | 684393.44 | 603006.51 | 10.1 | GRID | 9/22/2015 | 10.1 | 0.0 | Point surveyed within Tolerance |
| 2154 | 684393.44 | 603031.51 | 9.9 | GRID | 9/22/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 2155 | 684393.44 | 603056.51 | 9.7 | GRID | 9/22/2015 | 9.6 | -0.1 | Point surveyed within Tolerance |
| 2156 | 684393.44 | 603106.51 | 9.4 | GRID | 9/23/2015 | 9.3 | -0.1 | Point surveyed within Tolerance |
| 2157 | 684393.44 | 603131.51 | 9.3 | GRID | 9/23/2015 | 9.2 | -0.1 | Point surveyed within Tolerance |
| 2161 | 684368.44 | 603131.51 | 8.6 | GRID | 9/23/2015 | 8.6 | 0.0 | Point surveyed within Tolerance |
| 2162 | 684368.44 | 603106.51 | 8.8 | GRID | 9/23/2015 | 8.7 | -0.1 | Point surveyed within Tolerance |
| 2163 | 684368.44 | 603056.51 | 8.8 | GRID | 9/22/2015 | 8.8 | 0.0 | Point surveyed within Tolerance |
| 2164 | 684368.44 | 603031.51 | 9.0 | GRID | 9/22/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 2165 | 684368.44 | 603006.51 | 9.2 | GRID | 9/22/2015 | 9.1 | -0.1 | Point surveyed within Tolerance |
| 2166 | 684368.44 | 602981.51 | 9.4 | GRID | 9/22/2015 | 9.3 | -0.1 | Point surveyed within Tolerance |
| 2167 | 684343.44 | 603006.51 | 8.3 | GRID | 9/22/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2168 | 684343.44 | 603031.51 | 8.1 | GRID | 9/22/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2169 | 684343.44 | 603056.51 | 8.2 | GRID | 9/23/2015 | 8.2 | 0.0 | Point surveyed within Tolerance |
| 2170 | 684343.44 | 603106.51 | 8.4 | GRID | 9/23/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2178 | 684318.44 | 603031.51 | 4.7 | GRID | 9/23/2015 | 4.8 | 0.1 | Point surveyed within Tolerance |
| 2179 | 684293.44 | 603056.51 | 4.3 | GRID | 9/23/2015 | 4.3 | 0.0 | Point surveyed within Tolerance |
| 2304 | 684318.44 | 603081.51 | 5.4 | GRID | 9/23/2015 | 5.3 | -0.1 | Point surveyed within Tolerance |
| 2160 | 684368.44 | 603156.51 | 8.6 | GRID | 9/23/2015 | 8.5 | -0.1 | Point surveyed within Tolerance |
| 2171 | 684343.44 | 603131.51 | 8.4 | GRID | 9/23/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2180 | 684293.44 | 603081.51 | 7.4 | GRID | 9/23/2015 | 7.3 | -0.1 | Point surveyed within Tolerance |
| 2195 | 684268.44 | 603081.51 | 5.8 | GRID | 9/23/2015 | 5.9 | 0.1 | Point surveyed within Tolerance |
| 2303 | 684293.44 | 603106.51 | 7.1 | GRID | 9/23/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Grid Points (Table 1.9) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2159 | 684368.44 | 603181.51 | 6.4 | GRID | 9/24/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 2172 | 684343.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2173 | 684343.44 | 603206.51 | 6.8 | GRID | 9/24/2015 | 6.7 | -0.1 | Point surveyed within Tolerance |
| 2174 | 684318.44 | 603231.51 | 8.8 | GRID | 9/28/2015 | 8.7 | -0.1 | Point surveyed within Tolerance |
| 2175 | 684318.44 | 603206.51 | 6.8 | GRID | 9/24/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2176 | 684318.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2177 | 684318.44 | 603156.51 | 6.2 | GRID | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2181 | 684293.44 | 603131.51 | 5.9 | GRID | 9/24/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2182 | 684293.44 | 603156.51 | 6.3 | GRID | 9/24/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 2183 | 684293.44 | 603181.51 | 6.5 | GRID | 9/24/2015 | 6.6 | 0.1 | Point surveyed within Tolerance |
| 2184 | 684293.44 | 603206.51 | 8.0 | GRID | 9/28/2015 | 8.0 | 0.0 | Point surveyed within Tolerance |
| 2185 | 684293.44 | 603231.51 | 8.3 | GRID | 9/28/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2190 | 684268.44 | 603206.51 | 7.4 | GRID | 9/28/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 2191 | 684268.44 | 603181.51 | 7.5 | GRID | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2192 | 684268.44 | 603156.51 | 6.2 | GRID | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2193 | 684268.44 | 603131.51 | 5.9 | GRID | 9/24/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2194 | 684268.44 | 603106.51 | 3.1 | GRID | 9/24/2015 | 3.1 | 0.0 | Point surveyed within Tolerance |
| 2196 | 684243.44 | 603131.51 | 3.0 | GRID | 9/24/2015 | 3.0 | 0.0 | Point surveyed within Tolerance |
| 2197 | 684243.44 | 603181.51 | 7.6 | GRID | 9/28/2015 | 7.5 | -0.1 | Point surveyed within Tolerance |
| 2198 | 684243.44 | 603206.51 | 7.3 | GRID | 9/28/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2206 | 684218.44 | 603156.51 | 7.7 | GRID | 9/28/2015 | 7.7 | 0.0 | Point surveyed within Tolerance |
| 2186 | 684293.44 | 603256.51 | 8.5 | GRID | 9/28/2015 | 8.5 | 0.0 | Point surveyed within Tolerance |
| 2188 | 684268.44 | 603256.51 | 8.2 | GRID | 9/28/2015 | 8.1 | -0.1 | Point surveyed within Tolerance |
| 2189 | 684268.44 | 603231.51 | 7.8 | GRID | 9/28/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 2199 | 684243.44 | 603231.51 | 7.5 | GRID | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2205 | 684218.44 | 603206.51 | 7.3 | GRID | 9/28/2015 | 7.2 | -0.1 | Point surveyed within Tolerance |
| 2208 | 684193.44 | 603181.51 | 7.5 | GRID | 9/28/2015 | 7.4 | -0.1 | Point surveyed within Tolerance |
| 2187 | 684268.44 | 603281.51 | 7.1 | GRID | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2200 | 684243.44 | 603256.51 | 7.8 | GRID | 10/7/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 2201 | 684243.44 | 603281.51 | 7.3 | GRID | 10/7/2015 | 7.2 | -0.1 | Point surveyed within Tolerance |
| 2202 | 684218.44 | 603281.51 | 6.9 | GRID | 10/7/2015 | 6.9 | 0.0 | Point surveyed within Tolerance |
| 2203 | 684218.44 | 603256.51 | 7.1 | GRID | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2204 | 684218.44 | 603231.51 | 7.4 | GRID | 10/7/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 2209 | 684193.44 | 603206.51 | 7.3 | GRID | 10/7/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2210 | 684193.44 | 603231.51 | 7.3 | GRID | 10/7/2015 | 7.3 | 0.0 | Point surveyed within Tolerance |
| 2211 | 684193.44 | 603256.51 | 6.7 | GRID | 10/7/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 2212 | 684168.44 | 603256.51 | 6.5 | GRID | 10/7/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2213 | 684168.44 | 603231.51 | 6.4 | GRID | 10/7/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |
| 2214 | 684168.44 | 603206.51 | 7.6 | GRID | 10/7/2015 | 7.6 | 0.0 | Point surveyed within Tolerance |
| 2215 | 684143.44 | 603231.51 | 6.4 | GRID | 10/7/2015 | 6.5 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.0) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 548 | 685583.37 | 601539.44 | 15.1 | BRK | 7/2/2015 | 15.2 | 0.1 | Point surveyed within Tolerance |
| 549 | 685595.90 | 601578.00 | 14.2 | BRK | 7/2/2015 | 14.3 | 0.1 | Point surveyed within Tolerance |
| 550 | 685562.63 | 601543.70 | 17.5 | BRK | 7/2/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 551 | 685559.49 | 601547.97 | 13.9 | BRK | 7/2/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 552 | 685555.56 | 601552.54 | 13.9 | BRK | 7/2/2015 | 14.0 | 0.1 | Point surveyed within Tolerance |
| 553 | 685552.50 | 601556.70 | 17.4 | BRK | 7/2/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 554 | 685602.63 | 601551.44 | 17.7 | BRK | 7/2/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 555 | 685524.90 | 601529.98 | 13.1 | BRK | 7/2/2015 | 13.2 | 0.1 | Point surveyed within Tolerance |
| 556 | 685521.85 | 601534.13 | 16.6 | BRK | 7/2/2015 | 16.4 | -0.2 | Point surveyed within Tolerance |
| 557 | 685518.43 | 601506.14 | 15.5 | BRK | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 559 | 685566.10 | 601602.95 | 17.4 | BRK | 7/2/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 560 | 685557.11 | 601621.51 | 16.2 | BRK | 7/2/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 583 | 685469.10 | 601609.94 | 16.0 | BRK | 7/2/2015 | 15.9 | -0.1 | Point surveyed within Tolerance |
| 584 | 685468.06 | 601601.70 | 14.5 | BRK | 7/2/2015 | 14.6 | 0.1 | Point surveyed within Tolerance |
| 585 | 685534.63 | 601655.70 | 15.5 | BRK | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 586 | 685515.15 | 601685.29 | 14.8 | BRK | 7/2/2015 | 14.6 | -0.2 | Point surveyed within Tolerance |
| 587 | 685503.84 | 601702.15 | 14.5 | BRK | 7/2/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 588 | 685484.63 | 601722.61 | 15.5 | BRK | 7/8/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 589 | 685482.47 | 601731.53 | 11.1 | BRK | 7/2/2015 | 11.1 | 0.0 | Point surveyed within Tolerance |
| 590 | 685467.89 | 601733.01 | 13.1 | BRK | 7/2/2015 | 13.2 | 0.1 | Point surveyed within Tolerance |
| 591 | 685467.14 | 601729.90 | 15.3 | BRK | 7/2/2015 | 15.2 | -0.1 | Point surveyed within Tolerance |
| 592 | 685465.84 | 601749.83 | 15.2 | BRK | 7/2/2015 | 15.1 | -0.1 | Point surveyed within Tolerance |
| 593 | 685444.26 | 601779.76 | 13.6 | BRK | 7/2/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 594 | 685429.29 | 601800.21 | 15.1 | BRK | 7/2/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 595 | 685453.48 | 601767.05 | 15.1 | BRK | 7/2/2015 | 15.0 | -0.1 | Point surveyed within Tolerance |
| 603 | 685418.25 | 601641.07 | 13.5 | BRK | 7/2/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 604 | 685415.60 | 601650.93 | 15.9 | BRK | 7/2/2015 | 15.6 | -0.3 | Point surveyed within Tolerance |
| 605 | 685417.81 | 601680.87 | 15.9 | BRK | 7/2/2015 | 15.8 | -0.1 | Point surveyed within Tolerance |
| 606 | 685421.62 | 601680.64 | 13.4 | BRK | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 607 | 685417.84 | 601705.42 | 16.1 | BRK | 7/2/2015 | 15.9 | -0.2 | Point surveyed within Tolerance |
| 608 | 685421.83 | 601705.56 | 13.4 | BRK | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 609 | 685420.68 | 601733.21 | 13.5 | BRK | 7/2/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 610 | 685416.60 | 601732.96 | 16.2 | BRK | 7/2/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 611 | 685420.69 | 601759.40 | 13.5 | BRK | 7/2/2015 | 13.6 | 0.1 | Point surveyed within Tolerance |
| 612 | 685417.42 | 601761.34 | 16.1 | BRK | 7/2/2015 | 16.1 | 0.0 | Point surveyed within Tolerance |
| 613 | 685367.91 | 601704.46 | 13.3 | BRK | 7/2/2015 | 13.4 | 0.1 | Point surveyed within Tolerance |
| 614 | 685370.79 | 601706.98 | 15.9 | BRK | 7/2/2015 | 15.7 | -0.2 | Point surveyed within Tolerance |
| 615 | 685343.44 | 601731.17 | 13.7 | BRK | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 616 | 685345.91 | 601734.17 | 16.3 | BRK | 7/2/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 617 | 685303.14 | 601806.86 | 18.3 | BRK | 7/2/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 618 | 685298.77 | 601809.67 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 619 | 685294.54 | 601809.78 | 15.4 | BRK | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 620 | 685288.92 | 601805.68 | 10.7 | BRK | 7/2/2015 | 10.7 | 0.0 | Point surveyed within Tolerance |
| 621 | 685298.85 | 601821.38 | 15.8 | BRK | 7/2/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 622 | 685295.94 | 601825.31 | 12.5 | BRK | 7/2/2015 | 12.6 | 0.1 | Point surveyed within Tolerance |
| 623 | 685294.65 | 601831.82 | 12.5 | BRK | 7/2/2015 | 12.6 | 0.1 | Point surveyed within Tolerance |
| 624 | 685291.75 | 601835.75 | 15.8 | BRK | 7/2/2015 | 15.5 | -0.3 | Point surveyed within Tolerance |
| 625 | 685324.58 | 601840.13 | 15.9 | BRK | 7/2/2015 | 15.7 | -0.2 | Point surveyed within Tolerance |
| 626 | 685321.52 | 601844.26 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 627 | 685322.67 | 601852.58 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 628 | 685319.64 | 601856.68 | 15.8 | BRK | 7/2/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 629 | 685341.40 | 601852.72 | 15.7 | BRK | 7/2/2015 | 15.4 | -0.3 | Point surveyed within Tolerance |
| 630 | 685338.40 | 601856.76 | 12.4 | BRK | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 631 | 685345.65 | 601844.39 | 15.9 | BRK | 7/2/2015 | 15.9 | 0.0 | Point surveyed within Tolerance |
| 632 | 685347.89 | 601841.36 | 18.4 | BRK | 7/8/2015 | 18.3 | -0.1 | Point surveyed within Tolerance |
| 633 | 685372.85 | 601864.55 | 15.3 | BRK | 7/2/2015 | 15.4 | 0.1 | Point surveyed within Tolerance |
| 634 | 685364.47 | 601869.99 | 15.2 | BRK | 7/8/2015 | 15.1 | -0.1 | Point surveyed within Tolerance |
| 635 | 685361.56 | 601873.92 | 12.0 | BRK | 7/2/2015 | 12.1 | 0.1 | Point surveyed within Tolerance |
| 636 | 685354.92 | 601876.46 | 12.0 | BRK | 7/2/2015 | 12.1 | 0.1 | Point surveyed within Tolerance |
| 637 | 685350.44 | 601879.24 | 15.3 | BRK | 7/2/2015 | 15.2 | -0.1 | Point surveyed within Tolerance |
| 639 | 685353.62 | 601747.98 | 16.4 | BRK | 7/8/2015 | 16.3 | -0.1 | Point surveyed within Tolerance |
| 640 | 685357.16 | 601746.52 | 13.8 | BRK | 7/2/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 641 | 685361.58 | 601753.32 | 13.9 | BRK | 7/2/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 642 | 685364.98 | 601751.93 | 16.3 | BRK | 7/2/2015 | 16.2 | -0.1 | Point surveyed within Tolerance |
| 645 | 685381.55 | 601830.67 | 17.5 | BRK | 7/8/2015 | 17.4 | -0.1 | Point surveyed within Tolerance |
| 646 | 685385.39 | 601829.73 | 14.8 | BRK | 7/2/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 647 | 685383.26 | 601850.36 | 17.6 | BRK | 7/8/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 648 | 685408.65 | 601820.74 | 16.6 | BRK | 7/2/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 672 | 685359.01 | 601899.40 | 14.5 | BRK | 7/2/2015 | 14.4 | -0.1 | Point surveyed within Tolerance |
| 673 | 685328.78 | 601922.42 | 18.1 | BRK | 7/2/2015 | 18.2 | 0.1 | Point surveyed within Tolerance |
| 674 | 685299.89 | 601934.58 | 18.3 | BRK | 7/2/2015 | 18.4 | 0.1 | Point surveyed within Tolerance |
| 675 | 685300.62 | 601938.23 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 676 | 685305.79 | 601944.00 | 15.8 | BRK | 7/2/2015 | 15.8 | 0.0 | Point surveyed within Tolerance |
| 677 | 685308.02 | 601946.97 | 18.2 | BRK | 7/2/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 679 | 685305.33 | 601869.91 | 16.0 | BRK | 7/2/2015 | 16.1 | 0.1 | Point surveyed within Tolerance |
| 680 | 685303.05 | 601872.98 | 18.5 | BRK | 7/2/2015 | 18.1 | -0.4 | Point surveyed within Tolerance |
| 681 | 685268.99 | 601832.99 | 12.1 | BRK | 7/2/2015 | 12.2 | 0.1 | Point surveyed within Tolerance |
| 682 | 685272.64 | 601835.66 | 15.1 | BRK | 7/2/2015 | 14.7 | -0.4 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 683 | 685218.81 | 601931.92 | 18.6 | BRK | 7/2/2015 | 18.2 | -0.4 | Point surveyed within Tolerance |
| 684 | 685217.81 | 601935.62 | 16.0 | BRK | 7/2/2015 | 16.1 | 0.1 | Point surveyed within Tolerance |
| 979 | 685388.74 | 601749.07 | 13.5 | BRK | 7/2/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 980 | 685384.77 | 601750.03 | 16.2 | BRK | 7/2/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 678 | 685292.65 | 601972.35 | 18.1 | BRK | 7/14/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 685 | 685217.77 | 601956.54 | 18.2 | BRK | 7/14/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 686 | 685214.25 | 601958.05 | 15.7 | BRK | 7/14/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 688 | 685246.08 | 602006.05 | 17.3 | BRK | 7/14/2015 | 17.4 | 0.1 | Point surveyed within Tolerance |
| 689 | 685249.42 | 602007.82 | 14.8 | BRK | 7/14/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |
| 690 | 685250.13 | 602009.68 | 14.8 | BRK | 7/14/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 691 | 685253.44 | 602011.40 | 17.3 | BRK | 7/14/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 692 | 685256.80 | 602026.88 | 16.9 | BRK | 7/14/2015 | 17.0 | 0.1 | Point surveyed within Tolerance |
| 822 | 685209.17 | 602098.14 | 16.1 | BRK | 7/14/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 823 | 685187.68 | 602127.24 | 16.4 | BRK | 7/14/2015 | 16.5 | 0.1 | Point surveyed within Tolerance |
| 824 | 685169.69 | 602121.14 | 16.9 | BRK | 7/14/2015 | 17.0 | 0.1 | Point surveyed within Tolerance |
| 825 | 685159.60 | 602134.77 | 5.6 | BRK | 7/14/2015 | 5.7 | 0.1 | Point surveyed within Tolerance |
| 826 | 685142.99 | 602100.91 | 16.8 | BRK | 7/14/2015 | 16.7 | -0.1 | Point surveyed within Tolerance |
| 827 | 685132.68 | 602114.85 | 5.2 | BRK | 7/14/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 828 | 685117.94 | 602082.20 | 16.5 | BRK | 7/14/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 829 | 685108.04 | 602096.62 | 4.9 | BRK | 7/14/2015 | 4.9 | 0.0 | Point surveyed within Tolerance |
| 830 | 685097.56 | 602070.88 | 13.7 | BRK | 7/14/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 831 | 685091.62 | 602084.47 | 4.6 | BRK | 7/14/2015 | 4.7 | 0.1 | Point surveyed within Tolerance |
| 832 | 685079.08 | 602074.23 | 4.4 | BRK | 7/14/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 833 | 685087.23 | 602063.24 | 5.1 | BRK | 7/14/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 834 | 685228.90 | 602033.89 | 16.5 | BRK | 7/14/2015 | 16.5 | 0.0 | Point surveyed within Tolerance |
| 835 | 685232.50 | 602033.47 | 14.1 | BRK | 7/14/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 836 | 685239.46 | 602034.31 | 14.1 | BRK | 7/14/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 837 | 685243.00 | 602035.55 | 16.6 | BRK | 7/14/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 838 | 685241.70 | 602050.98 | 16.3 | BRK | 7/14/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 839 | 685057.33 | 602100.46 | 4.4 | BRK | 7/24/2015 | 4.5 | 0.1 | Point surveyed within Tolerance |
| 840 | 685060.41 | 602121.19 | 14.5 | BRK | 7/24/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 841 | 685068.93 | 602108.10 | 4.6 | BRK | 7/24/2015 | 4.7 | 0.1 | Point surveyed within Tolerance |
| 842 | 685048.44 | 602112.41 | 4.6 | BRK | 7/24/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 843 | 685096.92 | 602128.82 | 5.0 | BRK | 7/24/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 844 | 685091.28 | 602143.63 | 15.2 | BRK | 7/24/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 845 | 685121.55 | 602147.05 | 5.3 | BRK | 7/24/2015 | 5.4 | 0.1 | Point surveyed within Tolerance |
| 846 | 685109.62 | 602161.54 | 17.8 | BRK | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 847 | 685117.56 | 602193.69 | 17.4 | BRK | 7/24/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 848 | 685118.92 | 602197.25 | 14.9 | BRK | 7/24/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 849 | 685119.73 | 602203.55 | 14.8 | BRK | 7/24/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.3) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 850 | 685121.10 | 602206.98 | 17.3 | BRK | 7/24/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 851 | 685114.98 | 602226.59 | 17.2 | BRK | 7/24/2015 | 17.1 | -0.1 | Point surveyed within Tolerance |
| 852 | 685105.19 | 602198.82 | 17.4 | BRK | 7/24/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 853 | 685103.22 | 602203.76 | 14.8 | BRK | 7/24/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 854 | 685088.02 | 602208.76 | 17.4 | BRK | 7/24/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 855 | 685089.52 | 602212.18 | 14.9 | BRK | 7/24/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 856 | 685085.84 | 602227.09 | 15.1 | BRK | 7/24/2015 | 15.2 | 0.1 | Point surveyed within Tolerance |
| 857 | 685083.49 | 602230.12 | 17.6 | BRK | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 858 | 685094.99 | 602252.22 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 859 | 685081.79 | 602269.14 | 18.1 | BRK | 7/24/2015 | 18.1 | 0.0 | Point surveyed within Tolerance |
| 860 | 685047.09 | 602237.51 | 15.7 | BRK | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 861 | 685043.77 | 602234.95 | 18.2 | BRK | 7/24/2015 | 18.1 | -0.1 | Point surveyed within Tolerance |
| 862 | 685039.91 | 602232.72 | 15.7 | BRK | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 863 | 685042.37 | 602238.43 | 15.7 | BRK | 7/24/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 864 | 685066.11 | 602161.84 | 17.8 | BRK | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 865 | 685062.13 | 602161.07 | 15.3 | BRK | 7/24/2015 | 15.4 | 0.1 | Point surveyed within Tolerance |
| 866 | 685052.96 | 602208.15 | 17.8 | BRK | 7/24/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 867 | 685049.31 | 602206.51 | 15.4 | BRK | 7/24/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 868 | 685045.11 | 602202.48 | 15.6 | BRK | 7/24/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 869 | 685042.10 | 602200.70 | 17.9 | BRK | 7/24/2015 | 17.8 | -0.1 | Point surveyed within Tolerance |
| 870 | 685022.96 | 602172.09 | 15.4 | BRK | 7/24/2015 | 15.3 | -0.1 | Point surveyed within Tolerance |
| 871 | 685044.91 | 602142.21 | 14.8 | BRK | 7/24/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 872 | 684994.42 | 602217.26 | 18.7 | BRK | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 873 | 684975.68 | 602242.79 | 19.1 | BRK | 7/24/2015 | 19.1 | 0.0 | Point surveyed within Tolerance |
| 874 | 685005.71 | 602243.75 | 18.8 | BRK | 7/24/2015 | 18.7 | -0.1 | Point surveyed within Tolerance |
| 875 | 685009.09 | 602245.47 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 876 | 685025.00 | 602263.80 | 16.2 | BRK | 7/24/2015 | 16.3 | 0.1 | Point surveyed within Tolerance |
| 877 | 685027.83 | 602266.24 | 18.7 | BRK | 7/24/2015 | 18.6 | -0.1 | Point surveyed within Tolerance |
| 878 | 685053.73 | 602299.58 | 18.7 | BRK | 7/24/2015 | 18.7 | 0.0 | Point surveyed within Tolerance |
| 879 | 685053.33 | 602303.33 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 880 | 685060.48 | 602307.84 | 16.2 | BRK | 7/24/2015 | 16.1 | -0.1 | Point surveyed within Tolerance |
| 881 | 685039.62 | 602323.93 | 18.6 | BRK | 7/24/2015 | 18.5 | -0.1 | Point surveyed within Tolerance |
| 882 | 685021.34 | 602349.28 | 18.4 | BRK | 7/24/2015 | 18.3 | -0.1 | Point surveyed within Tolerance |
| 883 | 685006.56 | 602373.52 | 17.5 | BRK | 7/24/2015 | 17.5 | 0.0 | Point surveyed within Tolerance |
| 884 | 684985.52 | 602400.52 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 885 | 684968.75 | 602423.06 | 17.7 | BRK | 7/24/2015 | 17.7 | 0.0 | Point surveyed within Tolerance |
| 886 | 684958.59 | 602266.06 | 19.6 | BRK | 7/24/2015 | 19.5 | -0.1 | Point surveyed within Tolerance |
| 887 | 684944.51 | 602285.23 | 19.9 | BRK | 7/24/2015 | 20.0 | 0.1 | Point surveyed within Tolerance |
| 888 | 684924.17 | 602312.77 | 20.4 | BRK | 7/24/2015 | 20.3 | -0.1 | Point surveyed within Tolerance |
| 889 | 684896.37 | 602343.10 | 18.0 | BRK | 7/24/2015 | 17.9 | -0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 890 | 684880.77 | 602362.80 | 17.8 | BRK | 7/24/2015 | 17.8 | 0.0 | Point surveyed within Tolerance |
| 891 | 684869.32 | 602354.21 | 8.2 | BRK | 7/24/2015 | 8.3 | 0.1 | Point surveyed within Tolerance |
| 892 | 684884.22 | 602334.10 | 7.9 | BRK | 7/24/2015 | 8.0 | 0.1 | Point surveyed within Tolerance |
| 893 | 684908.58 | 602301.22 | 7.4 | BRK | 7/24/2015 | 7.5 | 0.1 | Point surveyed within Tolerance |
| 894 | 684928.96 | 602273.71 | 7.0 | BRK | 7/24/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 895 | 684943.18 | 602254.50 | 6.7 | BRK | 7/24/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 896 | 684960.30 | 602231.40 | 6.4 | BRK | 7/24/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 897 | 684979.15 | 602205.95 | 6.0 | BRK | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 898 | 685010.86 | 602163.13 | 5.3 | BRK | 7/24/2015 | 5.4 | 0.1 | Point surveyed within Tolerance |
| 899 | 685032.93 | 602133.34 | 4.9 | BRK | 7/24/2015 | 4.9 | 0.0 | Point surveyed within Tolerance |
| 900 | 684953.81 | 602443.85 | 17.6 | BRK | 7/24/2015 | 17.5 | -0.1 | Point surveyed within Tolerance |
| 901 | 684933.84 | 602472.48 | 17.2 | BRK | 7/24/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 919 | 684835.00 | 602400.55 | 9.0 | BRK | 7/24/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 920 | 684843.87 | 602407.12 | 16.3 | BRK | 7/24/2015 | 16.3 | 0.0 | Point surveyed within Tolerance |
| 902 | 684913.09 | 602504.45 | 16.5 | BRK | 8/10/2015 | 16.6 | 0.1 | Point surveyed within Tolerance |
| 910 | 684887.04 | 602531.88 | 18.2 | BRK | 8/10/2015 | 18.2 | 0.0 | Point surveyed within Tolerance |
| 909 | 684858.28 | 602571.33 | 14.7 | BRK | 8/12/2015 | 14.8 | 0.1 | Point surveyed within Tolerance |
| 913 | 684795.24 | 602555.71 | 13.7 | BRK | 8/12/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 914 | 684795.33 | 602552.00 | 16.1 | BRK | 8/12/2015 | 16.2 | 0.1 | Point surveyed within Tolerance |
| 915 | 684770.38 | 602552.44 | 15.8 | BRK | 8/12/2015 | 15.7 | -0.1 | Point surveyed within Tolerance |
| 916 | 684771.04 | 602556.03 | 13.3 | BRK | 8/12/2015 | 13.4 | 0.1 | Point surveyed within Tolerance |
| 917 | 684841.91 | 602602.61 | 16.6 | BRK | 8/12/2015 | 16.5 | -0.1 | Point surveyed within Tolerance |
| 911 | 684720.03 | 602604.99 | 14.7 | BRK | 8/13/2015 | 14.6 | -0.1 | Point surveyed within Tolerance |
| 921 | 684754.50 | 602627.17 | 17.2 | BRK | 8/13/2015 | 17.1 | -0.1 | Point surveyed within Tolerance |
| 923 | 684774.69 | 602642.80 | 17.3 | BRK | 8/13/2015 | 17.2 | -0.1 | Point surveyed within Tolerance |
| 925 | 684807.26 | 602664.88 | 13.8 | BRK | 8/13/2015 | 13.7 | -0.1 | Point surveyed within Tolerance |
| 912 | 684710.93 | 602615.25 | 5.5 | BRK | 9/4/2015 | 5.6 | 0.1 | Point surveyed within Tolerance |
| 922 | 684744.74 | 602640.33 | 6.3 | BRK | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 924 | 684765.25 | 602655.54 | 6.7 | BRK | 9/4/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 927 | 684774.96 | 602705.07 | 7.4 | BRK | 9/4/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 929 | 684725.10 | 602668.09 | 6.3 | BRK | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 933 | 684699.13 | 602648.83 | 5.7 | BRK | 9/4/2015 | 5.8 | 0.1 | Point surveyed within Tolerance |
| 934 | 684677.32 | 602632.66 | 5.2 | BRK | 9/4/2015 | 5.3 | 0.1 | Point surveyed within Tolerance |
| 936 | 684665.76 | 602624.13 | 5.0 | BRK | 9/4/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 2216 | 684768.70 | 602713.78 | 14.5 | BRK | 9/4/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 2217 | 684755.49 | 602705.02 | 14.8 | BRK | 9/4/2015 | 14.9 | 0.1 | Point surveyed within Tolerance |
| 2218 | 684750.54 | 602706.29 | 17.4 | BRK | 9/4/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 2219 | 684719.51 | 602728.09 | 18.1 | BRK | 9/4/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 2220 | 684721.25 | 602731.77 | 15.4 | BRK | 9/4/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2223 | 684714.82 | 602681.95 | 17.8 | BRK | 9/4/2015 | 17.7 | -0.1 | Point surveyed within Tolerance |
| 2224 | 684695.23 | 602678.31 | 15.2 | BRK | 9/4/2015 | 15.3 | 0.1 | Point surveyed within Tolerance |
| 2225 | 684691.16 | 602677.76 | 17.9 | BRK | 9/4/2015 | 17.9 | 0.0 | Point surveyed within Tolerance |
| 2226 | 684679.26 | 602656.42 | 17.5 | BRK | 9/4/2015 | 17.4 | -0.1 | Point surveyed within Tolerance |
| 2227 | 684678.94 | 602651.43 | 14.9 | BRK | 9/4/2015 | 14.8 | -0.1 | Point surveyed within Tolerance |
| 2228 | 684668.13 | 602643.12 | 14.5 | BRK | 9/4/2015 | 14.5 | 0.0 | Point surveyed within Tolerance |
| 2229 | 684657.26 | 602634.26 | 5.1 | BRK | 9/4/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 2230 | 684652.03 | 602663.18 | 15.1 | BRK | 9/4/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 2231 | 684641.00 | 602654.19 | 5.6 | BRK | 9/4/2015 | 5.6 | 0.0 | Point surveyed within Tolerance |
| 2232 | 684642.38 | 602682.88 | 18.2 | BRK | 9/4/2015 | 18.2 | 0.0 | Point surveyed within Tolerance |
| 2233 | 684640.23 | 602679.29 | 15.5 | BRK | 9/4/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 2234 | 684618.68 | 602681.55 | 6.2 | BRK | 9/4/2015 | 6.3 | 0.1 | Point surveyed within Tolerance |
| 2235 | 684632.71 | 602692.99 | 18.3 | BRK | 9/4/2015 | 18.2 | -0.1 | Point surveyed within Tolerance |
| 2236 | 684620.10 | 602708.58 | 18.7 | BRK | 9/4/2015 | 18.6 | -0.1 | Point surveyed within Tolerance |
| 2239 | 684603.43 | 602700.25 | 6.6 | BRK | 9/4/2015 | 6.7 | 0.1 | Point surveyed within Tolerance |
| 2312 | 684688.25 | 602662.99 | 17.6 | BRK | 9/4/2015 | 17.7 | 0.1 | Point surveyed within Tolerance |
| 2222 | 684686.52 | 602801.63 | 17.2 | BRK | 9/9/2015 | 17.2 | 0.0 | Point surveyed within Tolerance |
| 2240 | 684580.79 | 602728.00 | 7.2 | BRK | 9/9/2015 | 7.3 | 0.1 | Point surveyed within Tolerance |
| 2241 | 684592.09 | 602737.22 | 17.0 | BRK | 9/9/2015 | 17.0 | 0.0 | Point surveyed within Tolerance |
| 2245 | 684652.97 | 602837.52 | 18.0 | BRK | 9/9/2015 | 17.9 | -0.1 | Point surveyed within Tolerance |
| 2248 | 684632.99 | 602849.23 | 20.5 | BRK | 9/9/2015 | 20.5 | 0.0 | Point surveyed within Tolerance |
| 2249 | 684573.19 | 602760.13 | 17.4 | BRK | 9/9/2015 | 17.3 | -0.1 | Point surveyed within Tolerance |
| 2250 | 684562.02 | 602751.01 | 7.8 | BRK | 9/9/2015 | 7.9 | 0.1 | Point surveyed within Tolerance |
| 2251 | 684549.64 | 602787.35 | 17.3 | BRK | 9/9/2015 | 17.3 | 0.0 | Point surveyed within Tolerance |
| 2252 | 684539.27 | 602778.90 | 8.4 | BRK | 9/9/2015 | 8.4 | 0.0 | Point surveyed within Tolerance |
| 2253 | 684568.32 | 602806.28 | 17.4 | BRK | 9/9/2015 | 17.4 | 0.0 | Point surveyed within Tolerance |
| 2254 | 684565.58 | 602809.03 | 20.0 | BRK | 9/9/2015 | 19.9 | -0.1 | Point surveyed within Tolerance |
| 2255 | 684590.81 | 602830.43 | 20.3 | BRK | 9/9/2015 | 20.3 | 0.0 | Point surveyed within Tolerance |
| 2256 | 684593.43 | 602827.27 | 17.6 | BRK | 9/9/2015 | 17.6 | 0.0 | Point surveyed within Tolerance |
| 2257 | 684611.57 | 602875.64 | 20.3 | BRK | 9/9/2015 | 20.2 | -0.1 | Point surveyed within Tolerance |
| 2261 | 684576.88 | 602901.09 | 18.3 | BRK | 9/9/2015 | 18.3 | 0.0 | Point surveyed within Tolerance |
| 2266 | 684529.13 | 602867.21 | 18.0 | BRK | 9/9/2015 | 18.0 | 0.0 | Point surveyed within Tolerance |
| 2269 | 684529.62 | 602815.05 | 19.2 | BRK | 9/9/2015 | 19.2 | 0.0 | Point surveyed within Tolerance |
| 2270 | 684517.71 | 602805.33 | 9.0 | BRK | 9/9/2015 | 9.0 | 0.0 | Point surveyed within Tolerance |
| 2313 | 684666.34 | 602822.94 | 17.7 | BRK | 9/9/2015 | 17.6 | -0.1 | Point surveyed within Tolerance |
| 2259 | 684588.87 | 602908.31 | 19.0 | BRK | 9/16/2015 | 19.1 | 0.1 | Point surveyed within Tolerance |
| 2262 | 684562.28 | 602912.39 | 6.5 | BRK | 9/16/2015 | 6.6 | 0.1 | Point surveyed within Tolerance |
| 2263 | 684546.99 | 602879.91 | 18.1 | BRK | 9/16/2015 | 18.0 | -0.1 | Point surveyed within Tolerance |
| 2264 | 684536.89 | 602894.42 | 6.3 | BRK | 9/16/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2265 | 684518.89 | 602881.69 | 6.2 | BRK | 9/16/2015 | 6.3 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Break Points (Table 2.6) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2267 | 684498.05 | 602850.83 | 14.8 | BRK | 9/16/2015 | 14.8 | 0.0 | Point surveyed within Tolerance |
| 2268 | 684490.45 | 602861.57 | 6.0 | BRK | 9/16/2015 | 6.1 | 0.1 | Point surveyed within Tolerance |
| 2275 | 684469.16 | 602880.75 | 13.2 | BRK | 9/16/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 2278 | 684497.26 | 602878.64 | 6.1 | BRK | 9/16/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2279 | 684491.48 | 602886.80 | 12.8 | BRK | 9/16/2015 | 12.7 | -0.1 | Point surveyed within Tolerance |
| 2282 | 684569.90 | 602930.04 | 6.6 | BRK | 9/16/2015 | 6.6 | 0.0 | Point surveyed within Tolerance |
| 2283 | 684564.16 | 602938.23 | 13.2 | BRK | 9/16/2015 | 13.3 | 0.1 | Point surveyed within Tolerance |
| 2284 | 684462.82 | 602873.57 | 6.8 | BRK | 9/16/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2271 | 684492.19 | 603028.63 | 14.1 | BRK | 9/18/2015 | 14.2 | 0.1 | Point surveyed within Tolerance |
| 2272 | 684495.31 | 603031.35 | 11.3 | BRK | 9/18/2015 | 11.4 | 0.1 | Point surveyed within Tolerance |
| 2276 | 684420.78 | 602931.95 | 12.7 | BRK | 9/18/2015 | 12.7 | 0.0 | Point surveyed within Tolerance |
| 2277 | 684418.27 | 602928.58 | 9.9 | BRK | 9/18/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 2280 | 684466.73 | 602909.21 | 16.2 | BRK | 9/18/2015 | 16.2 | 0.0 | Point surveyed within Tolerance |
| 2281 | 684469.26 | 602906.05 | 13.5 | BRK | 9/18/2015 | 13.5 | 0.0 | Point surveyed within Tolerance |
| 2308 | 684541.16 | 602978.86 | 13.9 | BRK | 9/18/2015 | 13.8 | -0.1 | Point surveyed within Tolerance |
| 2309 | 684537.93 | 602976.16 | 16.7 | BRK | 9/18/2015 | 16.7 | 0.0 | Point surveyed within Tolerance |
| 2310 | 684519.64 | 603003.49 | 12.7 | BRK | 9/18/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 2311 | 684516.52 | 603000.77 | 15.4 | BRK | 9/18/2015 | 15.5 | 0.1 | Point surveyed within Tolerance |
| 2273 | 684467.44 | 603056.98 | 12.7 | BRK | 9/22/2015 | 12.6 | -0.1 | Point surveyed within Tolerance |
| 2274 | 684470.54 | 603059.69 | 10.0 | BRK | 9/22/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 2285 | 684396.21 | 603081.17 | 9.6 | BRK | 9/22/2015 | 9.5 | -0.1 | Point surveyed within Tolerance |
| 2286 | 684394.95 | 603084.82 | 7.0 | BRK | 9/22/2015 | 6.9 | -0.1 | Point surveyed within Tolerance |
| 2287 | 684370.17 | 603081.08 | 6.5 | BRK | 9/22/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2288 | 684369.73 | 603084.51 | 8.8 | BRK | 9/22/2015 | 8.8 | 0.0 | Point surveyed within Tolerance |
| 2291 | 684343.83 | 603080.68 | 5.9 | BRK | 9/23/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2292 | 684344.02 | 603084.27 | 8.3 | BRK | 9/23/2015 | 8.2 | -0.1 | Point surveyed within Tolerance |
| 2293 | 684318.43 | 603058.47 | 7.6 | BRK | 9/23/2015 | 7.5 | -0.1 | Point surveyed within Tolerance |
| 2294 | 684314.63 | 603057.98 | 5.0 | BRK | 9/23/2015 | 5.1 | 0.1 | Point surveyed within Tolerance |
| 2306 | 684383.22 | 603153.36 | 9.0 | BRK | 9/23/2015 | 8.9 | -0.1 | Point surveyed within Tolerance |
| 2307 | 684386.53 | 603155.86 | 6.6 | BRK | 9/23/2015 | 6.5 | -0.1 | Point surveyed within Tolerance |
| 2289 | 684346.82 | 603155.61 | 8.4 | BRK | 9/24/2015 | 8.3 | -0.1 | Point surveyed within Tolerance |
| 2290 | 684344.28 | 603158.02 | 7.0 | BRK | 9/24/2015 | 7.0 | 0.0 | Point surveyed within Tolerance |
| 2296 | 684244.61 | 603103.27 | 6.2 | BRK | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2297 | 684317.01 | 603131.31 | 6.5 | BRK | 9/24/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2298 | 684318.88 | 603129.97 | 8.1 | BRK | 9/24/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2299 | 684244.49 | 603157.76 | 7.5 | BRK | 9/28/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2300 | 684238.78 | 603154.40 | 3.1 | BRK | 9/28/2015 | 3.1 | 0.0 | Point surveyed within Tolerance |
| 2301 | 684221.74 | 603183.65 | 7.8 | BRK | 9/28/2015 | 7.7 | -0.1 | Point surveyed within Tolerance |
| 2302 | 684225.10 | 603177.88 | 3.3 | BRK | 9/28/2015 | 3.3 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

Points in 0.1 - 0.5 ft. tolerance are due to a slight overcut in the top of slopes where it wouldn't be suitable for backfill due to compaction difficulties.

| SA-6 South Cap Subgrade: Boundary Points (Table 3.0) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 545 | 685526.43 | 601442.32 | 12.9 | BNDY | 7/2/2015 | 13.0 | 0.1 | Point surveyed within Tolerance |
| 546 | 685543.45 | 601459.45 | 13.4 | BNDY | 7/2/2015 | 13.4 | 0.0 | Point surveyed within Tolerance |
| 547 | 685561.91 | 601478.03 | 14.2 | BNDY | 7/2/2015 | 14.2 | 0.0 | Point surveyed within Tolerance |
| 558 | 685516.84 | 601455.37 | 13.7 | BNDY | 7/2/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 561 | 685572.96 | 601633.24 | 10.0 | BNDY | 7/2/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 562 | 685589.38 | 601610.88 | 10.2 | BNDY | 7/2/2015 | 10.1 | -0.1 | Point surveyed within Tolerance |
| 563 | 685606.33 | 601587.78 | 9.9 | BNDY | 7/2/2015 | 10.0 | 0.1 | Point surveyed within Tolerance |
| 564 | 685633.80 | 601550.37 | 9.8 | BNDY | 7/2/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 565 | 685622.62 | 601565.61 | 10.0 | BNDY | 7/2/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 566 | 685614.41 | 601530.85 | 15.7 | BNDY | 7/2/2015 | 15.8 | 0.1 | Point surveyed within Tolerance |
| 567 | 685591.47 | 601507.77 | 15.0 | BNDY | 7/2/2015 | 15.1 | 0.1 | Point surveyed within Tolerance |
| 568 | 685577.88 | 601494.10 | 14.6 | BNDY | 7/2/2015 | 14.6 | 0.0 | Point surveyed within Tolerance |
| 569 | 685488.06 | 601495.42 | 14.3 | BNDY | 7/2/2015 | 14.3 | 0.0 | Point surveyed within Tolerance |
| 570 | 685501.08 | 601477.69 | 14.9 | BNDY | 7/2/2015 | 15.0 | 0.1 | Point surveyed within Tolerance |
| 571 | 685474.31 | 601513.30 | 13.6 | BNDY | 7/2/2015 | 13.6 | 0.0 | Point surveyed within Tolerance |
| 572 | 685459.92 | 601533.74 | 12.8 | BNDY | 7/2/2015 | 12.8 | 0.0 | Point surveyed within Tolerance |
| 573 | 685442.87 | 601556.12 | 12.4 | BNDY | 7/2/2015 | 12.4 | 0.0 | Point surveyed within Tolerance |
| 574 | 685428.08 | 601576.27 | 12.2 | BNDY | 7/2/2015 | 12.2 | 0.0 | Point surveyed within Tolerance |
| 575 | 685413.27 | 601596.44 | 11.9 | BNDY | 7/2/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 576 | 685398.47 | 601616.59 | 11.4 | BNDY | 7/2/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 577 | 685383.68 | 601636.74 | 11.3 | BNDY | 7/2/2015 | 11.3 | 0.0 | Point surveyed within Tolerance |
| 578 | 685368.88 | 601656.89 | 11.3 | BNDY | 7/2/2015 | 11.2 | -0.1 | Point surveyed within Tolerance |
| 579 | 685558.28 | 601653.23 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 581 | 685543.38 | 601673.52 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 582 | 685528.60 | 601693.65 | 9.8 | BNDY | 7/2/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 596 | 685514.37 | 601713.04 | 9.8 | BNDY | 7/2/2015 | 9.7 | -0.1 | Point surveyed within Tolerance |
| 597 | 685499.50 | 601733.28 | 9.7 | BNDY | 7/2/2015 | 9.8 | 0.1 | Point surveyed within Tolerance |
| 598 | 685485.10 | 601752.90 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 599 | 685469.40 | 601774.28 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 600 | 685454.74 | 601794.25 | 9.6 | BNDY | 7/2/2015 | 9.7 | 0.1 | Point surveyed within Tolerance |
| 601 | 685439.85 | 601814.53 | 9.7 | BNDY | 7/2/2015 | 9.6 | -0.1 | Point surveyed within Tolerance |
| 602 | 685425.01 | 601834.73 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 638 | 685354.08 | 601677.04 | 11.3 | BNDY | 7/2/2015 | 11.1 | -0.2 | Point surveyed within Tolerance |
| 643 | 685324.49 | 601717.35 | 10.8 | BNDY | 7/2/2015 | 10.6 | -0.2 | Point surveyed within Tolerance |
| 644 | 685339.29 | 601697.19 | 11.0 | BNDY | 7/2/2015 | 10.6 | -0.4 | Point surveyed within Tolerance |
| 649 | 685309.86 | 601737.62 | 10.6 | BNDY | 7/2/2015 | 10.6 | 0.0 | Point surveyed within Tolerance |
| 650 | 685295.20 | 601757.86 | 10.5 | BNDY | 7/2/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 651 | 685280.51 | 601778.09 | 10.4 | BNDY | 7/2/2015 | 10.3 | -0.1 | Point surveyed within Tolerance |
| 652 | 685265.70 | 601798.24 | 10.7 | BNDY | 7/2/2015 | 10.8 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.1) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 653 | 685250.90 | 601818.38 | 11.9 | BNDY | 7/2/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 654 | 685236.09 | 601838.53 | 15.1 | BNDY | 7/2/2015 | 15.1 | 0.0 | Point surveyed within Tolerance |
| 655 | 685221.28 | 601858.68 | 15.6 | BNDY | 7/2/2015 | 15.6 | 0.0 | Point surveyed within Tolerance |
| 656 | 685206.48 | 601878.81 | 15.5 | BNDY | 7/2/2015 | 15.4 | -0.1 | Point surveyed within Tolerance |
| 657 | 685191.67 | 601898.96 | 15.5 | BNDY | 7/2/2015 | 15.5 | 0.0 | Point surveyed within Tolerance |
| 658 | 685176.87 | 601919.10 | 15.4 | BNDY | 7/2/2015 | 15.4 | 0.0 | Point surveyed within Tolerance |
| 659 | 685410.29 | 601854.79 | 9.6 | BNDY | 7/2/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 660 | 685395.44 | 601875.02 | 9.6 | BNDY | 7/2/2015 | 9.6 | 0.0 | Point surveyed within Tolerance |
| 661 | 685380.66 | 601895.14 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 662 | 685365.91 | 601915.23 | 9.7 | BNDY | 7/2/2015 | 9.7 | 0.0 | Point surveyed within Tolerance |
| 663 | 685351.03 | 601935.49 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 664 | 685336.28 | 601955.58 | 9.9 | BNDY | 7/2/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 687 | 685162.06 | 601939.25 | 14.9 | BNDY | 7/2/2015 | 14.9 | 0.0 | Point surveyed within Tolerance |
| 665 | 685321.52 | 601975.69 | 10.0 | BNDY | 7/14/2015 | 9.9 | -0.1 | Point surveyed within Tolerance |
| 666 | 685306.70 | 601995.87 | 10.0 | BNDY | 7/14/2015 | 9.9 | -0.1 | Point surveyed within Tolerance |
| 667 | 685292.04 | 602015.84 | 10.0 | BNDY | 7/14/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 668 | 685277.22 | 602036.03 | 10.0 | BNDY | 7/14/2015 | 10.0 | 0.0 | Point surveyed within Tolerance |
| 669 | 685262.73 | 602055.75 | 9.9 | BNDY | 7/14/2015 | 9.9 | 0.0 | Point surveyed within Tolerance |
| 670 | 685247.66 | 602076.28 | 10.0 | BNDY | 7/14/2015 | 10.1 | 0.1 | Point surveyed within Tolerance |
| 671 | 685232.64 | 602096.74 | 10.2 | BNDY | 7/14/2015 | 10.1 | -0.1 | Point surveyed within Tolerance |
| 693 | 685147.26 | 601959.39 | 14.3 | BNDY | 7/14/2015 | 14.4 | 0.1 | Point surveyed within Tolerance |
| 694 | 685132.45 | 601979.53 | 13.7 | BNDY | 7/14/2015 | 13.8 | 0.1 | Point surveyed within Tolerance |
| 695 | 685117.65 | 601999.68 | 13.2 | BNDY | 7/14/2015 | 13.2 | 0.0 | Point surveyed within Tolerance |
| 696 | 685102.93 | 602019.90 | 10.3 | BNDY | 7/14/2015 | 10.4 | 0.1 | Point surveyed within Tolerance |
| 697 | 685088.04 | 602039.97 | 6.1 | BNDY | 7/14/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 698 | 685073.23 | 602060.11 | 4.7 | BNDY | 7/14/2015 | 4.8 | 0.1 | Point surveyed within Tolerance |
| 699 | 685058.42 | 602080.25 | 4.3 | BNDY | 7/14/2015 | 4.4 | 0.1 | Point surveyed within Tolerance |
| 705 | 685217.90 | 602116.82 | 10.4 | BNDY | 7/14/2015 | 10.3 | -0.1 | Point surveyed within Tolerance |
| 706 | 685203.10 | 602136.97 | 10.5 | BNDY | 7/14/2015 | 10.6 | 0.1 | Point surveyed within Tolerance |
| 700 | 685043.62 | 602100.40 | 4.5 | BNDY | 7/24/2015 | 4.4 | -0.1 | Point surveyed within Tolerance |
| 701 | 685028.81 | 602120.54 | 4.8 | BNDY | 7/24/2015 | 4.9 | 0.1 | Point surveyed within Tolerance |
| 702 | 685014.01 | 602140.69 | 5.1 | BNDY | 7/24/2015 | 5.2 | 0.1 | Point surveyed within Tolerance |
| 703 | 684999.20 | 602160.83 | 5.4 | BNDY | 7/24/2015 | 5.4 | 0.0 | Point surveyed within Tolerance |
| 704 | 684984.40 | 602180.97 | 5.7 | BNDY | 7/24/2015 | 5.7 | 0.0 | Point surveyed within Tolerance |
| 707 | 685188.31 | 602157.12 | 6.0 | BNDY | 7/24/2015 | 6.1 | 0.1 | Point surveyed within Tolerance |
| 708 | 685173.51 | 602177.27 | 6.0 | BNDY | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 709 | 685143.92 | 602217.57 | 11.2 | BNDY | 7/24/2015 | 11.2 | 0.0 | Point surveyed within Tolerance |
| 710 | 685158.71 | 602197.42 | 11.1 | BNDY | 7/24/2015 | 11.0 | -0.1 | Point surveyed within Tolerance |
| 711 | 685129.12 | 602237.73 | 11.4 | BNDY | 7/24/2015 | 11.4 | 0.0 | Point surveyed within Tolerance |
| 712 | 685114.32 | 602257.88 | 11.6 | BNDY | 7/24/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.2) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 713 | 685099.53 | 602278.03 | 11.8 | BNDY | 7/24/2015 | 11.7 | -0.1 | Point surveyed within Tolerance |
| 714 | 685084.73 | 602298.18 | 12.0 | BNDY | 7/24/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 715 | 685069.94 | 602318.33 | 12.0 | BNDY | 7/24/2015 | 12.0 | 0.0 | Point surveyed within Tolerance |
| 716 | 685055.15 | 602338.47 | 11.9 | BNDY | 7/24/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 717 | 685040.35 | 602358.63 | 11.9 | BNDY | 7/24/2015 | 11.9 | 0.0 | Point surveyed within Tolerance |
| 718 | 685025.55 | 602378.78 | 11.8 | BNDY | 7/24/2015 | 11.9 | 0.1 | Point surveyed within Tolerance |
| 719 | 685010.76 | 602398.93 | 11.8 | BNDY | 7/24/2015 | 11.9 | 0.1 | Point surveyed within Tolerance |
| 720 | 684995.96 | 602419.08 | 11.8 | BNDY | 7/24/2015 | 11.7 | -0.1 | Point surveyed within Tolerance |
| 721 | 684981.17 | 602439.24 | 11.7 | BNDY | 7/24/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 722 | 684966.37 | 602459.39 | 11.6 | BNDY | 7/24/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 723 | 684951.57 | 602479.54 | 11.5 | BNDY | 7/24/2015 | 11.5 | 0.0 | Point surveyed within Tolerance |
| 724 | 684936.78 | 602499.69 | 11.5 | BNDY | 7/24/2015 | 11.6 | 0.1 | Point surveyed within Tolerance |
| 731 | 684969.59 | 602201.11 | 6.0 | BNDY | 7/24/2015 | 6.0 | 0.0 | Point surveyed within Tolerance |
| 732 | 684954.79 | 602221.26 | 6.3 | BNDY | 7/24/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 733 | 684939.98 | 602241.40 | 6.6 | BNDY | 7/24/2015 | 6.6 | 0.0 | Point surveyed within Tolerance |
| 734 | 684925.18 | 602261.55 | 6.9 | BNDY | 7/24/2015 | 6.8 | -0.1 | Point surveyed within Tolerance |
| 735 | 684910.37 | 602281.69 | 7.1 | BNDY | 7/24/2015 | 7.2 | 0.1 | Point surveyed within Tolerance |
| 736 | 684895.57 | 602301.83 | 7.4 | BNDY | 7/24/2015 | 7.4 | 0.0 | Point surveyed within Tolerance |
| 737 | 684880.76 | 602321.98 | 7.8 | BNDY | 7/24/2015 | 7.8 | 0.0 | Point surveyed within Tolerance |
| 738 | 684865.95 | 602342.12 | 8.2 | BNDY | 7/24/2015 | 8.2 | 0.0 | Point surveyed within Tolerance |
| 739 | 684851.15 | 602362.27 | 8.5 | BNDY | 7/24/2015 | 8.5 | 0.0 | Point surveyed within Tolerance |
| 740 | 684827.24 | 602394.80 | 9.0 | BNDY | 7/24/2015 | 8.9 | -0.1 | Point surveyed within Tolerance |
| 741 | 684821.28 | 602402.91 | 15.7 | BNDY | 7/24/2015 | 15.7 | 0.0 | Point surveyed within Tolerance |
| 725 | 684921.98 | 602519.84 | 11.6 | BNDY | 8/10/2015 | 11.5 | -0.1 | Point surveyed within Tolerance |
| 726 | 684907.19 | 602539.99 | 11.6 | BNDY | 8/10/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 727 | 684892.39 | 602560.14 | 11.6 | BNDY | 8/10/2015 | 11.7 | 0.1 | Point surveyed within Tolerance |
| 728 | 684877.59 | 602580.30 | 11.6 | BNDY | 8/10/2015 | 11.6 | 0.0 | Point surveyed within Tolerance |
| 742 | 684806.74 | 602422.70 | 15.0 | BNDY | 8/10/2015 | 15.0 | 0.0 | Point surveyed within Tolerance |
| 743 | 684792.02 | 602442.92 | 14.4 | BNDY | 8/10/2015 | 14.4 | 0.0 | Point surveyed within Tolerance |
| 729 | 684862.80 | 602600.45 | 11.7 | BNDY | 8/12/2015 | 11.7 | 0.0 | Point surveyed within Tolerance |
| 730 | 684848.00 | 602620.60 | 11.7 | BNDY | 8/12/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 761 | 684777.12 | 602462.99 | 13.8 | BNDY | 8/12/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 762 | 684762.31 | 602483.14 | 13.2 | BNDY | 8/12/2015 | 13.1 | -0.1 | Point surveyed within Tolerance |
| 763 | 684747.51 | 602503.28 | 12.8 | BNDY | 8/12/2015 | 12.7 | -0.1 | Point surveyed within Tolerance |
| 744 | 684833.20 | 602640.76 | 11.7 | BNDY | 8/13/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 745 | 684818.41 | 602660.91 | 11.7 | BNDY | 8/13/2015 | 11.8 | 0.1 | Point surveyed within Tolerance |
| 764 | 684732.70 | 602523.42 | 12.5 | BNDY | 8/13/2015 | 12.4 | -0.1 | Point surveyed within Tolerance |
| 765 | 684717.90 | 602543.56 | 7.9 | BNDY | 8/13/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 766 | 684703.09 | 602563.72 | 6.7 | BNDY | 8/13/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 767 | 684687.11 | 602585.46 | 5.5 | BNDY | 8/13/2015 | 5.5 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

## SA-6 South Cap Subgrade: Boundary Points (Table 3.3)

| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
|---|---|---|---|---|---|---|---|---|
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 746 | 684803.61 | 602681.06 | 9.1 | BNDY | 9/4/2015 | 9.1 | 0.0 | Point surveyed within Tolerance |
| 747 | 684790.60 | 602698.78 | 7.5 | BNDY | 9/4/2015 | 7.6 | 0.1 | Point surveyed within Tolerance |
| 768 | 684672.87 | 602604.82 | 4.9 | BNDY | 9/4/2015 | 5.0 | 0.1 | Point surveyed within Tolerance |
| 769 | 684656.51 | 602623.72 | 5.0 | BNDY | 9/4/2015 | 5.0 | 0.0 | Point surveyed within Tolerance |
| 2000 | 684774.23 | 602717.67 | 12.4 | BNDY | 9/4/2015 | 12.5 | 0.1 | Point surveyed within Tolerance |
| 2001 | 684757.86 | 602736.57 | 12.9 | BNDY | 9/4/2015 | 12.8 | -0.1 | Point surveyed within Tolerance |
| 2002 | 684741.50 | 602755.47 | 13.2 | BNDY | 9/4/2015 | 13.1 | -0.1 | Point surveyed within Tolerance |
| 2003 | 684725.13 | 602774.36 | 13.5 | BNDY | 9/4/2015 | 13.4 | -0.1 | Point surveyed within Tolerance |
| 2004 | 684708.76 | 602793.26 | 13.8 | BNDY | 9/4/2015 | 13.7 | -0.1 | Point surveyed within Tolerance |
| 2065 | 684591.05 | 602699.29 | 6.7 | BNDY | 9/4/2015 | 6.7 | 0.0 | Point surveyed within Tolerance |
| 2066 | 684607.42 | 602680.39 | 6.3 | BNDY | 9/4/2015 | 6.3 | 0.0 | Point surveyed within Tolerance |
| 2067 | 684623.78 | 602661.50 | 5.9 | BNDY | 9/4/2015 | 5.8 | -0.1 | Point surveyed within Tolerance |
| 2068 | 684640.15 | 602642.60 | 5.4 | BNDY | 9/4/2015 | 5.4 | 0.0 | Point surveyed within Tolerance |
| 2005 | 684692.39 | 602812.16 | 14.0 | BNDY | 9/9/2015 | 13.9 | -0.1 | Point surveyed within Tolerance |
| 2006 | 684676.02 | 602831.05 | 13.6 | BNDY | 9/9/2015 | 13.7 | 0.1 | Point surveyed within Tolerance |
| 2007 | 684659.66 | 602849.95 | 13.7 | BNDY | 9/9/2015 | 13.7 | 0.0 | Point surveyed within Tolerance |
| 2008 | 684643.29 | 602868.85 | 13.8 | BNDY | 9/9/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 2009 | 684626.92 | 602887.74 | 13.9 | BNDY | 9/9/2015 | 13.9 | 0.0 | Point surveyed within Tolerance |
| 2010 | 684610.55 | 602906.64 | 14.0 | BNDY | 9/9/2015 | 14.1 | 0.1 | Point surveyed within Tolerance |
| 2058 | 684476.47 | 602831.57 | 9.8 | BNDY | 9/9/2015 | 9.8 | 0.0 | Point surveyed within Tolerance |
| 2059 | 684492.84 | 602812.67 | 9.3 | BNDY | 9/9/2015 | 9.4 | 0.1 | Point surveyed within Tolerance |
| 2060 | 684509.31 | 602793.66 | 8.9 | BNDY | 9/9/2015 | 9.0 | 0.1 | Point surveyed within Tolerance |
| 2061 | 684525.58 | 602774.88 | 8.5 | BNDY | 9/9/2015 | 8.4 | -0.1 | Point surveyed within Tolerance |
| 2062 | 684541.94 | 602755.98 | 8.0 | BNDY | 9/9/2015 | 8.1 | 0.1 | Point surveyed within Tolerance |
| 2063 | 684558.31 | 602737.08 | 7.6 | BNDY | 9/9/2015 | 7.6 | 0.0 | Point surveyed within Tolerance |
| 2064 | 684574.68 | 602718.19 | 7.2 | BNDY | 9/9/2015 | 7.1 | -0.1 | Point surveyed within Tolerance |
| 2011 | 684589.12 | 602931.38 | 6.6 | BNDY | 9/16/2015 | 6.7 | 0.1 | Point surveyed within Tolerance |
| 2012 | 684575.96 | 602946.57 | 13.3 | BNDY | 9/16/2015 | 13.3 | 0.0 | Point surveyed within Tolerance |
| 2057 | 684459.70 | 602850.93 | 5.9 | BNDY | 9/16/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2013 | 684545.08 | 602982.23 | 13.8 | BNDY | 9/18/2015 | 13.8 | 0.0 | Point surveyed within Tolerance |
| 2014 | 684561.45 | 602963.33 | 14.7 | BNDY | 9/18/2015 | 14.8 | 0.1 | Point surveyed within Tolerance |
| 2015 | 684528.71 | 603001.12 | 12.8 | BNDY | 9/18/2015 | 12.8 | 0.0 | Point surveyed within Tolerance |
| 2016 | 684512.34 | 603020.02 | 11.9 | BNDY | 9/18/2015 | 12.0 | 0.1 | Point surveyed within Tolerance |
| 2017 | 684495.97 | 603038.92 | 11.0 | BNDY | 9/18/2015 | 11.1 | 0.1 | Point surveyed within Tolerance |
| 2051 | 684361.89 | 602963.84 | 6.7 | BNDY | 9/18/2015 | 6.8 | 0.1 | Point surveyed within Tolerance |
| 2052 | 684378.26 | 602944.95 | 7.7 | BNDY | 9/18/2015 | 7.8 | 0.1 | Point surveyed within Tolerance |
| 2053 | 684394.63 | 602926.05 | 8.9 | BNDY | 9/18/2015 | 9.0 | 0.1 | Point surveyed within Tolerance |
| 2054 | 684411.00 | 602907.15 | 10.1 | BNDY | 9/18/2015 | 10.0 | -0.1 | Point surveyed within Tolerance |
| 2055 | 684427.94 | 602887.59 | 8.4 | BNDY | 9/18/2015 | 8.5 | 0.1 | Point surveyed within Tolerance |
| 2056 | 684443.73 | 602869.36 | 10.4 | BNDY | 9/18/2015 | 10.4 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.4) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2018 | 684479.61 | 603057.81 | 10.1 | BNDY | 9/23/2015 | 10.1 | 0.0 | Point surveyed within Tolerance |
| 2019 | 684463.24 | 603076.71 | 9.2 | BNDY | 9/22/2015 | 9.1 | -0.1 | Point surveyed within Tolerance |
| 2020 | 684446.87 | 603095.61 | 8.3 | BNDY | 9/22/2015 | 8.3 | 0.0 | Point surveyed within Tolerance |
| 2021 | 684430.50 | 603114.50 | 7.5 | BNDY | 9/22/2015 | 7.5 | 0.0 | Point surveyed within Tolerance |
| 2022 | 684414.13 | 603133.40 | 6.8 | BNDY | 9/23/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2023 | 684397.77 | 603152.30 | 6.3 | BNDY | 9/23/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2046 | 684280.05 | 603058.33 | 4.2 | BNDY | 9/23/2015 | 4.2 | 0.0 | Point surveyed within Tolerance |
| 2047 | 684296.42 | 603039.43 | 4.3 | BNDY | 9/23/2015 | 4.3 | 0.0 | Point surveyed within Tolerance |
| 2048 | 684312.79 | 603020.53 | 4.6 | BNDY | 9/23/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 2049 | 684329.16 | 603001.64 | 5.1 | BNDY | 9/22/2015 | 5.1 | 0.0 | Point surveyed within Tolerance |
| 2050 | 684345.53 | 602982.74 | 5.8 | BNDY | 9/22/2015 | 5.8 | 0.0 | Point surveyed within Tolerance |
| 2024 | 684381.40 | 603171.20 | 6.5 | BNDY | 9/23/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2045 | 684263.69 | 603077.22 | 5.9 | BNDY | 9/23/2015 | 5.9 | 0.0 | Point surveyed within Tolerance |
| 2025 | 684365.03 | 603190.09 | 6.6 | BNDY | 9/24/2015 | 6.5 | -0.1 | Point surveyed within Tolerance |
| 2026 | 684348.66 | 603208.99 | 6.8 | BNDY | 9/24/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2027 | 684332.29 | 603227.89 | 6.8 | BNDY | 9/28/2015 | 6.8 | 0.0 | Point surveyed within Tolerance |
| 2028 | 684315.93 | 603246.78 | 7.7 | BNDY | 9/28/2015 | 7.8 | 0.1 | Point surveyed within Tolerance |
| 2041 | 684198.59 | 603153.14 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2042 | 684214.58 | 603133.91 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2043 | 684230.98 | 603114.98 | 4.6 | BNDY | 9/24/2015 | 4.6 | 0.0 | Point surveyed within Tolerance |
| 2044 | 684247.32 | 603096.12 | 6.2 | BNDY | 9/24/2015 | 6.2 | 0.0 | Point surveyed within Tolerance |
| 2029 | 684299.56 | 603265.68 | 7.9 | BNDY | 9/28/2015 | 7.9 | 0.0 | Point surveyed within Tolerance |
| 2040 | 684182.05 | 603171.63 | 6.1 | BNDY | 9/28/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |
| 2030 | 684283.19 | 603284.58 | 8.1 | BNDY | 10/7/2015 | 8.1 | 0.0 | Point surveyed within Tolerance |
| 2031 | 684258.41 | 603313.18 | 8.2 | BNDY | 10/7/2015 | 8.1 | -0.1 | Point surveyed within Tolerance |
| 2032 | 684238.18 | 603303.29 | 7.1 | BNDY | 10/7/2015 | 7.1 | 0.0 | Point surveyed within Tolerance |
| 2033 | 684215.72 | 603292.32 | 6.8 | BNDY | 10/7/2015 | 6.9 | 0.1 | Point surveyed within Tolerance |
| 2034 | 684193.26 | 603281.34 | 6.5 | BNDY | 10/7/2015 | 6.5 | 0.0 | Point surveyed within Tolerance |
| 2035 | 684170.80 | 603270.36 | 6.4 | BNDY | 10/7/2015 | 6.4 | 0.0 | Point surveyed within Tolerance |
| 2036 | 684148.33 | 603259.38 | 6.3 | BNDY | 10/7/2015 | 6.4 | 0.1 | Point surveyed within Tolerance |
| 2037 | 684124.13 | 603238.34 | 6.1 | BNDY | 10/7/2015 | 6.2 | 0.1 | Point surveyed within Tolerance |
| 2038 | 684149.11 | 603209.50 | 6.1 | BNDY | 10/7/2015 | 6.1 | 0.0 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

| SA-6 South Cap Subgrade: Boundary Points (Table 3.5) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Bottom Target Coordinates (based on TIN surface) | | | | | As-built Elevations | | | |
| Point # | Northing | Easting | Elevation 1 | Description | Date Obtained | Elevation | Deviation 2 | Comments |
| 2039 | 684165.48 | 603190.60 | 6.1 | BNDY | 10/7/2015 | 6.2 | 0.1 | Point surveyed within Tolerance |
| 2305 | 684268.00 | 603302.11 | 8.1 | BNDY | 10/7/2015 | 8.2 | 0.1 | Point surveyed within Tolerance |

1 This is the design elevation at Construction Control Grid Points.

2 Deviation = Surveyed Elevation - Design Elevation

**Per SPECIFICATION 01460 SURVEY. SECTION 1.05 F. Spot Elevations - Survey shall be constructed to provide an accuracy of 0.1 feet vertically. Ninety percent of all spot elevations placed on the maps shall have an accuracy of at least 0.1', and the remaining 10 percent shall not be in error by more than one-half (1/2) the contour interval (0.5'). Break points added to replace Grid Points that fell on slopes and Boundary Points will be treated as Spot Elevations as defined in Section 1.05 F.**

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Grid Points depicted in Table 1, Break Points in Table 2, Boundary Points in Table 3, and topographic spot elevations are correct, and representative of the as-built cap subgrade throughout the SA6 South cap.**


R. Thomas Hugg 2/12/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**

# *D2. Subgrade Construction Control Grid*




## LEGEND

- GRID POINT
- BREAK POINT
- BOUNDARY POINT
- DESIGN SUBGRADE CONTOUR

SCALE IN FEET: 0 15 30 60

## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GRID, BREAK AND BOUNDARY POINTS AND ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.
2. GRID, BREAK, AND BOUNDARY POINT ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM 1/2/15 THROUGH 10/7/15.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.


MASER CONSULTING, P.A. PH: 609.390.1927 - FA: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER
12001151A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

CONSTRUCTION CONTROL GRID
CAP SUBGRADE SURVEY

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 2/12/16 | ISSUED FOR CLIENT REVIEW | | |

DSGN | DR | CHK | APVD

R:\THOMAS HUGG

NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE 2/12/16
PROJ 3480-10-0027
DWG
SHEET 1 OF 1


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829



THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.



FILE NAME: C:\U...r...r...D...\...T...\12001151AS...r d d...S...\...C...S...r d L...\...M...F...\...dr...2d...\ PLOT DATE: Fr...12F... 2016 PLOT TIME: 7:58 PM

# Appendix E: Soil Subgrade Approval

*E1. ESI Certificate of Subgrade Surface Acceptance*

*E2. Langan Certificate of Soil Surface*

# *E1. ESI Certificate of Subgrade Surface Acceptance*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

**INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.**

PROJECT NAME: Honeywell PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Approx. 14,703 sf.

PANEL NUMBERS: 1 TO 4

GRADE ACCEPTANCE: INSPECTOR:

GENERAL CONTRACTOR: ENTACT

OWNER:

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala, certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/20/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Signature | Title | DATE |
|---|---|---|
| | Project Superintendent | 7/20/15 |

| | INDEPENDENT CQA MONITOR | 7/20/15 |
|---|---|---|

OWNER REPRESENTATIVE

| Signature | Title | DATE |
|---|---|---|
| Carolina Ramos | QC Manager | 7/20/15 |

7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,680 SF.

PANEL NUMBERS: 5 TO 9 over composite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/21/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/21/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT EQA MONITOR | 7/21/15 |

OWNER REPRESENTATIVE

| | QC Manager | 7-21-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,726 SF

PANEL NUMBERS: 10 TO 13 over Geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/22/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/22/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7-22-15 |

OWNER REPRESENTATIVE

| Carolyn Parnell | QC Manager | 7-22-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 18,495 SF

PANEL NUMBERS: 14 TO 18 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

NOTE: SUBGRADE APPROVED BUT NOT COVERED AREA, 11,300 SF.

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/23/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/23/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7-23-15 |

OWNER REPRESENTATIVE

| Carolyn Parnes | QC Manager Entact | 7-23-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 22,140 SF

PANEL NUMBERS: 19 to 24 Over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/24/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 7/24/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7/24/15 |

OWNER REPRESENTATIVE

| Carolyn Harris | QC Manager - Entact | 7-24-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 22,005 SF.

PANEL NUMBERS: 25 to 30 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/28/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 7/28/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7/28/15 |

OWNER REPRESENTATIVE

| | QC Manager - Entact | 7/28/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,693 SF

PANEL NUMBERS: 31 to 34 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 7/29/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 7/29/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 7/29/15 |
| OWNER REPRESENTATIVE | | |
| Carolyn Parnell | QC Manager - Entact | 7/29/15 |
| *Signature* | *Title* | *DATE* |

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 20,226 sf

PANEL NUMBERS: 35 to 46 most over GCL

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/3/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/3/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | Independent CQA Monitor | 8/3/15 |

OWNER REPRESENTATIVE

| | | |
|---|---|---|
| | | 8-3-15 |
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 11003 sf

PANEL NUMBERS: 47 to 49 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/5/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/05/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 8/5/15 |

OWNER REPRESENTATIVE

| | QC Manager / Entact | 8/5/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 15,120 sf

PANEL NUMBERS: SC to S4 over reconfiguration

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/6/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/6/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT QA MONITOR | 8/6/15 |

OWNER REPRESENTATIVE

| | QC Manager Entact | 8/6/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 13,230 sf

PANEL NUMBERS: 55 to 60 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/7/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/7/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 8/7/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| Carolina Ramos | QC Manager - Entact | 8-7-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 18,309 SF

PANEL NUMBERS 61 to 65 and perimeter soil tie

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/10/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 8/10/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 8/10/15 |

OWNER REPRESENTATIVE

| Carolyn Parnes | QC Manager Entact | 8/10/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 18,225 SF

PANEL NUMBERS: 66 to 71 over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8/13/15 and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 8/13/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 8/13/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| Carolina Parra | QC Manager Entact | 8/13/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,705 SF

PANEL NUMBERS: P- 72 to 75 Over geocomposite

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 14-Aug and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 14-Aug |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| | INDEPENDENT CQA MONITOR | 8/14/15 |
|---|---|---|

OWNER REPRESENTATIVE

| | QC Manager - Entact | 8-14-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER ENVIRONMENTAL SPECIALTIES INTERNATIONAL INC

PROJECT NAME Honeywell Chromium Area PROJECT NO 12-11-1399

LOCATION Jersey City, NJ

AREA ACCEPTED Aprox 14 705 SF

PANEL NUMBERS P- 76 to 86 over GCL

GRADE ACCEPTANCE INSPECTOR AMEC

GENERAL CONTRACTOR ENTACT

OWNER Honeywell

AUTHORIZED REPRESENTATIVE

The undersigned Fortino Ayala certifies that he/she is a representative of Environmental Specialties International Inc authorized to execute this certificate that he/she has visually inspected the subgrade surface described above on 9-Sep and found the surface to be acceptable for installation of the geomembrane

This certification is based on observation of the surface of the subgrade only No subsurface inspections or test have been performed and Environmental Specialties International Inc makes no representations or warranties regarding conditions which may exist below the surface of the subgrade

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 9-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| | INDEPENDENT CQA MONITOR | 9/9/15 |
|---|---|---|

OWNER REPRESENTATIVE

| Carolyn Ramos | QC Mgr - Entact | 9-9-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

7941 PECUE LANE SUITE A - BATON ROUGE, LA 70809 - PHONE 225 291 2700 - FAX 225-291 2788

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 15,075 SF

PANEL NUMBERS: P- 87 to 90 Over subgrade.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 15-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| *Fortino Ayala* | Project Superintendent | 15-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/15/15 |

OWNER REPRESENTATIVE

| Carlos Vasco | QC Manager - Entact | 9-15-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,963 SF

PANEL NUMBERS: P- 91 to 94 Over subgrade.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 16-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC

| Fortino Ayala | Project Superintendent | 16-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/16/15 |

OWNER REPRESENTATIVE

| | QC Manager-Gatel | 9-16-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 11,205 SF

PANEL NUMBERS: P- 95 to 97 Over subgrade.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 17-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 17-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| | INDEPENDENT CQP MONITOR | 9/17/15 |
|---|---|---|

OWNER REPRESENTATIVE

| Caroline Hamin | QC Manager | 9-17-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 11,070 SF

PANEL NUMBERS: P- 98 to 106 Over subgrade and some over GCL

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 18-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 18-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/18/15 |

OWNER REPRESENTATIVE

| | QC Manager | 9-18-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,625 SF

PANEL NUMBERS: P- 107 to 110 Over subgrade

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 22-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 22-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 9/22/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

| Carlos Ramos | QC Manager | 9-22-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,569 SF

PANEL NUMBERS: P- 111 to 114 Over subgrade

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 23-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 23-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/23/15 |

OWNER REPRESENTATIVE

| Carolyn Parnes | QC Manager - Entact | 9-23-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,681 SF

PANEL NUMBERS: P- 115 to 118 Over subgrade

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 24-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 24-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 9/24/15 |

OWNER REPRESENTATIVE

| Carolyn Lanier | QC Manager Entact | 9-24-15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 7,425 SF

PANEL NUMBERS: P- 119 to 120 Over subgrade, some liner over GCL at ditch design.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 25-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 25-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |

OWNER REPRESENTATIVE

| | INDEPENDENT CQA MONITOR | 9/25/15 |
|---|---|---|
| | QC Manager Entact | 9-25-15 |
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 14,895 SF

PANEL NUMBERS: P- 121 to 125 Over subgrade, some liner over GCL at ditch and perim.

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 29-Sep and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| Fortino Ayala | Project Superintendent | 29-Sep |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| OWNER REPRESENTATIVE | INDEPENDENT CQA MONITOR | 9/29/15 |
| Jaclyn Pasco | QC Manager - Entact | 9-29-15 |
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# CERTIFICATE OF SUBGRADE SURFACE ACCEPTANCE

INSTALLER: ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

PROJECT NAME: Honeywell Chromium Area PROJECT NO: 12-11-1399

LOCATION: Jersey City, NJ

AREA ACCEPTED: Aprox. 15,205 SF

PANEL NUMBERS: P- 126 to 134 Over subgrade, some liner over GCL At cap design .

GRADE ACCEPTANCE: INSPECTOR: AMEC

GENERAL CONTRACTOR: ENTACT

OWNER: Honeywell

AUTHORIZED REPRESENTATIVE:

The undersigned, Fortino Ayala ,certifies that he/she is a representative of Environmental Specialties International, Inc. authorized to execute this certificate, that he/she has visually inspected the subgrade surface described above on 8-Oct and found the surface to be acceptable for installation of the geomembrane.

This certification is based on observation of the surface of the subgrade only. No subsurface inspections or test have been performed and Environmental Specialties International, Inc. makes no representations or warranties regarding conditions which may exist below the surface of the subgrade.

AUTHORIZED REPRESENTATIVE OF ENVIRONMENTAL SPECIALTIES INTERNATIONAL, INC.

| *Fortino Ayala* | Project Superintendent | 8-Oct |
|---|---|---|
| *Signature* | *Title* | *DATE* |
| | INDEPENDENT CQA MONITOR | 10/8/15 |

OWNER REPRESENTATIVE

| Caroline Parnell | QC Mgr - Entact | 10/8/15 |
|---|---|---|
| *Signature* | *Title* | *DATE* |

*7943 PECUE LANE SUITE A ~ BATON ROUGE, LA. 70809 ~ PHONE 225-291-2700 ~ FAX 225-291-2788*

# *E2. Langan Certificate of Soil Surface*

**LANGAN**

# Certificate of Soil Surface

Sheet # 1

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 24+35 TO STA 23+35 (WEST END) | | |
| QA Monitor | LANGAN | Date | 7/20/2015 | | |

Description of Soil Surface to be lined: WEST END OF SA-6 SOUTH (~STA. 24+35) TO APPROX. 100 FT. EAST (STA. 23+35) - RUNNING NORTH TO SOUTH THROUGH APPROX. GRID POINT ~~8~~ 13.09. SOIL APPEARS TO BE GRADED, COMPACTED AND FREE OF DEBRIS (> ½"), AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/20/15 |
| Title | ~~SENIOR STAFF~~ LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-20-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: Soil Graded, compacted, And Free of Debris (>½")
As outlined In Section 02372-8

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | West End | N-S | Refer to Photograph Log (11/20/15) |
| | 2 | West End | N-S | Photos 2, 3, 4 w/ Descriptions |

1. Refer to Photo Log (11/20/15)
Photos 2, 3, 4 for Corresponding Photos

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 2

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 23+35 to ~Sta. 22+35 | | |
| QA Monitor | Langan | Date | 7/21/2015 | | |

Description of Soil Surface to be lined: Area immediately East from subgrade approval on 7/20/15. Located from approx. Sta. 23+35 to Sta. 22+35 (100 ft. East from installed CQA on 7/20/15. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/21/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-22-15 |
| Title | Entrak QC Manager |
| Representing: | Entrak |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8.
GEOMEMBRANE CAP PANELS 5-9 PLACED OVER AREA.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #9 | STA. 23+35 | LOOKING EAST | REFER TO PHOTO LOG (7/21/15), PHOTO #9 |
| | 2 PHOTO #10 | STA 23+35 | EAST/SOUTHEAST | REFER TO PHOTO LOG (7/21/15), PHOTO #10 |

1. REFER TO PHOTO LOG (7/21/15)
PHOTOS 9, 10 FOR SUPPORTING SUBGRADE PHOTOS

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 3

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530601 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 22+35 TO STA. 21+40 | | |
| QA Monitor | LANGAN | Date | 7/22/15 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST FROM PREVIOUSLY APPROVED SUBGRADE ON 7/21/15. LOCATED FROM APPROX. STA. 22+35 TO STA. 21+40 (APPROX. 95 FT EAST OF GEOMEMBRANE INSTALLED ON 7/21/15. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/22/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-23-15 |
| Title | QC Manager |
| Representing: | Enhul |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: Soil Graded, Compacted, And Free of Debris (7 ½")
As outlined in Section 02372-8

Geomembrane Cap Panels 10-13 Placed over Area

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo # 2 | | Looking East | Refer to Photo Log (11/22/15) Photo # 2 |
| | 2 Photo # 3 | | Looking NE | Refer to Photo Log (11/22/15) Photo # 3 |
| 1. Refer to Photo Log (11/22/15) Photos 2, 3 for supporting subgrade Photos | | | | 2. |

**LANGAN**

# Certificate of Soil Surface

Sheet # 4

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / ANECFW | Cell No. | ~STA. 21+40 TO STA. 19+90 | | |
| QA Monitor | LANGAN | Date | 7/23/15 | | |

Description of Soil Surface to be lined: AREA IMMEDIATELY EAST FROM PREVIOUSLY APPROVED SUBGRADE ON 7/22/15. LOCATED FROM APPROXIMATE STATION STA. 21+40 (~P-13') TO STA. 19+90 (APPROX 150 FT. EAST OF GEOMEMBRANE INSTALLED ON 7/22/15'). SOIL APPEARS TO BE GRADED, COMPACTED + FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPEC'S.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | Y |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/23/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-23-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: Soil Graded, compacted, and fiber of Debris (2½") As outlined in Section 023.72-8.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 Photo #3 | Sta 21.40 | Looking East | Refer to Photo Log (7/23/15) Photo #3 |
| | 2 Photo #5 | Sta 21+00 | Looking NE | Refer to Photo Log (7/23/15) Photo #5 |
| 1. Refer to Photo Log (7/23/15) Photos 3.5 for supporting subgrade photos<br>Additional subgrade details also shown on Photos 4+6 | | | | 2. |

**LANGAN**

# Certificate of Soil Surface

Sheet # 5

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ± Sta. 19+90 to Sta. 19+00 | | |
| QA Monitor | Langan | Date | 7/24/15 | | |

Description of Soil Surface to be lined: Additional ± 90 ft. Section of soil approved east of Geomembrane Panels installed on 7/23/15 (P-18). Subgrade Approved from ± Sta. 19+90 to Sta. 19+00 (Subgrade previously approved to Sta. 19+90) / Geomembrane installed to ± Sta. 20+25 on 7/23/15). Soil appears to be graded, compacted, and free of debris (≥ ½"), and in conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/24/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-24-15 |
| Title | qc Manager Entact |
| Representing: | Entact |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02372-8.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #8 | STA 20+25 | LOOKING EAST | REFER TO PHOTO LOG (11/24/15) PHOTO #8 |
| | 2 PHOTO #9 | STA. 19+80 | LOOKING SOUTH | REFER TO PHOTO LOG (11/24/15) PHOTO #9 |

1. REFER TO PHOTO LOG (11/24/15) PHOTOS 8,9 FOR SUPPORTING SUBGRADE PHOTOS

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 6

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | STA. 19+00 TO STA. 18+20 | | |
| QA Monitor | LANGAN | Date | 7/28/15 | | |

Description of Soil Surface to be lined: ADDITIONAL ~80 FT. SECTION OF SOIL APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 7/24/15 (P-24). NO SUBGRADE APPROVED ON 7/27/15. SUBGRADE APPROVED FROM ~STA. 19+00 TO STA. 18+20. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 7/28/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7-28-15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

-ADDITIONAL ~40 FT. OF SOIL APPROVED AT END OF DAY TO ALLOW ESI TO INSTALL EXTRA 2 PANELS OF GEOMEMBRANE. SOIL APPROVED TO APPROX. STA 17+80.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~BD 6775.158Y | LOOKING NW | REFER TO PHOTO LOG (11/25/15) PHOTO #3 |
| | 2 PHOTO #4 | ~19.00 | LOOKING EAST | REFER TO PHOTO LOG (11/25/15) PHOTO #4 |
| 1. REFER TO PHOTO LOG (11/25/15) PHOTOS 3, 4, 5 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

**LANGAN**

# Certificate of Soil Surface

Sheet # 7

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 117+80 to Sta. 117+00 | | |
| QA Monitor | Langan | Date | 7/29/15 | | |

Description of Soil Surface to be lined: ~80 ft. Section of Soil Approved East of Geomembrane Panels Installed on 7/28/15 (P-30). Subgrade Approved From Approx. Sta. 117+80 to Sta. 117+00, Soil Appears to Be Graded, Compacted, And Free of Debris (>½"), and in Conformance With Project Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 7/29/30 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 7/29/30 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | Caroline Panico |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED UP TO 1ST UTILITY CORRIDOR

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | ESTA. 17+80 | LOOKING N | REFER TO 7/29/15 PHOTO LOG PHOTO #5 |
| | 2 PHOTO #8 | SEND CAP | LOOKING E | REFER TO 7/29/15 PHOTO LOG PHOTO #8 |

1. REFER TO PHOTO LOG (7/29/15)
PHOTOS 5, 8 FOR SUPPORTING SUBGRADE PHOTOS

2.

**LANGAN**

# Certificate of Soil Surface

Sheet # 8

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 17+00 to Sta. 15+80 | | |
| QA Monitor | Langan | Date | 8/3/15 | | |

Description of Soil Surface to be lined: ~120 ft. Section of Soil Approved East of Geomembrane Panels Installed on 7/29/15 (P-34). Subgrade Approved From Approx. Sta. 17+00 to Sta. 15+80 (to East Side of 1st Utility Corridor) Through 1st Utility Corridor. Soil Appears to Be Graded, Compacted, And Free of Debris (>½") And in Conformance w/ Project Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/3/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | |
| Date: | |
| Title | |
| Representing: | |
| Signature: | Cathleen Parrino - Entact QC Manager |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED FOR GCL PLACEMENT WITHIN UTILITY CORRIDOR + GEOMEMBRANE / GVL PLACEMENT OUTSIDE OF CORRIDOR

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | CORRIDOR | LOOKING N | REFER TO 8/3/15 PHOTO LOG PHOTO #1 |
| | 2 PHOTO #3 | CORRIDOR | LOOKING S | REFER TO 8/3/15 PHOTO LOG PHOTO #3 |

1. REFER TO PHOTO LOG (8/3/15) PHOTOS 1, 2, 3 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 9

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 15+80 TO ~STA. 15+10 | | |
| QA Monitor | LANGAN | Date | 8/5/15 | | |

Description of Soil Surface to be lined: ~170 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/3/15 (P-42). SUBGRADE APPROVED FROM ~STA. 15+80 TO ~STA. 15+10. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/5/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-5-15 |
| Title | QC Manager Entact |
| Representing: | Entact |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7 ½")
AS OUTLINED IN SECTION 02372-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT ABOVE) GROUNDWATER ELEVATION

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | GP 165-15.4 | LOOKING W | REFER TO 8/5/15 PHOTO LOG PHOTO #5 |
| | 2 PHOTO #6 | STA. 15+80 | LOOKING S | REFER TO 8/5/15 PHOTO LOG PHOTO #6 |
| 1. REFER TO PHOTO LOG (8/5/15) PHOTOS 5, 6 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 10


| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 15+10 to ~Sta 14+00 | | |
| QA Monitor | Langan | Date | 8/6/15 | | |

Description of Soil Surface to be lined: ~110 ft. Section of soil subgrade advanced East of Geomembrane Panels installed on 8/5/15 (P-49). Subgrade advanced from ~Sta. 15+10 to ~Sta. 14+00. Soil appears to be graded, compacted, and free of debris (7½") and in conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - no changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/6/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-6-15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8
- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #17 | ± STA. 15+10 | LOOKING E | REFER TO 8/6/15 PHOTO LOG (PHOTO #17) |
| | 2 PHOTO #9 | ± STA. 15+10 | LOOKING S | REFER TO 8/6/15 PHOTO LOG (PHOTO #9) |
| 1. REFER TO PHOTO LOG (8/6/15) PHOTOS 17, 8, AND 9 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 11

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~ Sta. 14+00 to ~ Sta. 13+00 | | |
| QA Monitor | Langan | Date | 8/7/15 | | |

Description of Soil Surface to be lined: ~100 ft. section of soil subgrade approved east of geomembrane panels installed on 8/6/15 (P-54). Subgrade approved from ~ Sta. 14+00 to ~ Sta. 13+00. Soil appears to be graded, compacted, and free of debris (7½") and in conformance with project spec.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/7/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8/7/15 |
| Title | QC Manager |
| Representing: | Entech |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02317Z-8.

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (~1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #6 | STA. 14+00 | LOOKING E | REFER TO 8/17/15 PHOTO LOG (PHOTO #6) |
| | 2 | | | |

1. REFER TO PHOTO LOG (8/17/15) PHOTO 6 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 12

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell 5A-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 13+00 to ~Sta. 12+00 | | |
| QA Monitor | Langan | Date | 8/10/15 | | |

Description of Soil Surface to be lined: ~100 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 8/7/15 (P-60). Subgrade Approved From ~Sta. 13+00 to ~Sta. 12+00 Soil Appears to be Graded, Compacted, and Free of Debris (> ½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/10/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Parnio |
| Date: | 8/10/15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | Caroline Parnio |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (> 1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | ~STA. 13+00 | LOOKING N | REFER TO 8/10/15 PHOTO LOG (PHOTO #5) |
| | 2 PHOTO #6 | ~STA. 13+00 | LOOKING E | REFER TO 8/10/15 PHOTO LOG (PHOTO #6) |

1. REFER TO PHOTO LOG (8/10/15) PHOTOS #5, 6 FOR SUPPORTING SUBGRADE PHOTOS.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 13

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | Subgrade | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 12+00 to ~Sta. 11+00 | | |
| QA Monitor | Langan | Date | 8/13/15 | | |

Description of Soil Surface to be lined: ~100 ft. section of soil subgrade approved for use of geomembrane panels installed on 8/10/15 (P-65). Subgrade approved from ~Sta. 12+00 to ~Sta. 11+00. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 8/13/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-13-15 |
| Title | QC Manager |
| Representing: | Entrac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½")
AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS AREA WAS ABOVE WATER TABLE (>1 FT.)

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | @ STA 11+50 | LOOKING SW | REFER TO 8/13/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | @ STA 11+50 | LOOKING SE | REFER TO 8/13/15 PHOTO LOG (PHOTO #2) |

1. REFER TO PHOTO LOG (8/13/15) PHOTOS 1, 2 FOR SUPPORTING SUBGRADE PHOTOS.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 14

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 11+00 TO ~STA. 10+20 | | |
| QA Monitor | LANGAN | Date | 8/14/15 | | |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/13/15 (P-171). SUBGRADE APPROVED FROM STA. 11+00 TO ~STA. 10+20. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 8/14/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 8-14-15 |
| Title | QC Manager |
| Representing: | Entrada |
| Signature: | Caroline Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> ½")
AS OUTLINED IN SECTION 02372-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN EDGE OF SA-6 AREA BELOW (TO 1 FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |
| 1. | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 15

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / AMEC FW | Cell No. | ~STA. 10+20 TO ~STA. 9+50 | | |
| QA Monitor | Langan | Date | 9/9/15 | | |

Description of Soil Surface to be lined: ~770 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 8/14/15 (P.175). SUBGRADE APPROVED THROUGH 2ND UTILITY CORRIDOR FROM APPROX. STA. 10+20 TO STA. 9+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/9/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/9/15 |
| Title | QC Manager |
| Representing: | ENTACT |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

- SOIL APPROVED FOR GCL PLACEMENT ALONG EASTERN + WESTERN SLOPES OF UTILITY CORRIDOR + SOUTHERN SLOPE (LOWER BENCH) OF SOUTHERN END OF SA-6 AREA BELOW (TO 1FT. ABOVE) GROUNDWATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | ~STA 10+00 | LOOKING SW | REFER TO 9/9/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | ~STA. 10+00 | LOOKING NE | REFER TO 9/9/15 PHOTO LOG (PHOTO #3) |

1. REFER TO PHOTO LOG (9/9/15) PHOTOS 2,3 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 16


| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 9+50 to ~Sta. 8+50 |
| QA Monitor | Langan | Date | 9/15/15 |

Description of Soil Surface to be lined: ~100 ft. section of soil subgrade approved east of geomembrane panels installed on 9/9/15 (P-86). Subgrade approved east of 2nd utility corridor from approx. Sta. 9+50 to ~Sta. 8+50. Soil appears to be graded, compacted, and free of debris (>½") and in conformance with project specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/15/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-15-15 |
| Title | Entact QC Manager |
| Representing: | ENTACT |
| Signature: |  |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8

~~THE~~ GCL PLACED ALONG SOUTHERN SLOPE OF SA-6 SOUTH (LOWER BENCH) AT AREA BELOW (TO 1FT. ABOVE) GROUNDWATER TABLE

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 9+50 | LOOKING S | REFER TO 9/15/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 9+50 | LOOKING E | REFER TO 9/15/15 PHOTO LOG |
| 1. REFER TO PHOTO LOG (9/15/15) PHOTOS 1,2 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2. |

LANGAN

# Certificate of Soil Surface

Sheet # 17

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 8+50 TO ~STA. 7+70 | | |
| QA Monitor | LANGAN | Date | 9/16/15 | | |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/15/15 (P-90). SUBGRADE APPROVED FROM APPROXIMATE STA. 8+50 (P-90) TO APPROX STA. 7+70. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOUDREAU |
| Date: | 9/16/15 |
| Title | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/16/15 |
| Title | QC Manager |
| Representing: | Entact |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (> 1/2") AS OUTLINED IN SECTION 02372-8

NO GCL PLACED ALONG SA-6 AS AREAS OUTSIDE OF GROUNDWATER ZONE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #17 | ~STA 8+80 | LOOKING N/NE | REFER TO 9/16/15 PHOTO LOG (PHOTO #17) |
| | 2 | | | |

1. REFER TO PHOTO LOG (9/16/15) PHOTO #17 FOR SUPPORTING SUBGRADE PHOTOS

2.

LANGAN

# Certificate of Soil Surface

Sheet # 18

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Arlec FW | Cell No. | ~Sta. 7+70 to ~Sta. 7+00 | | |
| QA Monitor | Langan | Date | 9/17/15 | | |

Description of Soil Surface to be lined: ~70 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/16/15 (P-94). Subgrade Approved From Approximate Sta. 7+70 (P-94) to Approximate Sta. 7+00 (western slope of 3rd utility corridor). Soil Appears to be Graded, Compacted, And Free of Debris (>1½") and in conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| **QUALITY** | **Y/N/NA** |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/17/15 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/17/15 |
| Title | QC Manager |
| Representing: | Entac |
| Signature: | |

**LANGAN**

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED ALONG SA-6 AS NO AREAS BELOW (TO 1 FT. ABOVE) GROUNDWATER

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 | | | |
| | 2 | | | |

1.

2.

LANGAN

# Certificate of Soil Surface

Sheet # 19

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 7+00 TO ~STA. 6+40 | | |
| QA Monitor | LANGAN | Date | 9/18/15 | | |

Description of Soil Surface to be lined: ~60 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/17/15 (P-97). SUBGRADE APPROVED THROUGH 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 7+00 TO ~STA. 6+40 (EASTERN SIDE OF 3RD UTILITY CORRIDOR). SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/18/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9/18/15 |
| Title: | QC Manager |
| Representing: | Entek |
| Signature: | |

LANGAN

Notes, Observations, Comments SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 023172-8.

- GCL PLACED ALONG BOTTOM AND SIDE SLOPES (APPROX 2 FT. TO 3FT. EACH BOTTOM) OF 3RD UTILITY CORRIDOR (LOCATED AT APPROX. STA. 6+80). GCL ALSO PLACED ALONG SOUTHERN END OF CORRIDOR (LOWER BENCH) BELOW TO 1 FT. ABOVE WATER TABLE.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 6+80 | LOOKING S | REFER TO 9/18/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 6+86 | LOOKING N | REFER TO 9/18/15 PHOTO LOG (PHOTO #2) |
| 1 REFER TO PHOTO LOG (9/18/15) PHOTOS 1, 2 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2 |

LANGAN

# Certificate of Soil Surface


Sheet # 20


| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 6+40 TO ~STA. 5+30 | | |
| QA Monitor | LANGAN | Date | 9/22/15 | | |

Description of Soil Surface to be lined: ~110 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/18/15 (P-98-103 / EAST-WEST ORIENTATION). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 6+40 TO ~STA. 5+30. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | |
| Suitable for placement of GCL | |
| Smooth | |
| Any changes required? If so the contractor and owner's representative must be notified. | |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BOSWORTH |
| Date: | 9/22/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-22-15 |
| Title: | QC Manager |
| Representing: | Entact |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8

- NO GCL PLACED AS APPROVED SUBGRADE OUTSIDE OF WATER TABLE INFLUENCE. ONLY GVL REQUIRED

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | 25TH. 6+40 | LOOKING N | REFER TO 9/22/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | 25TH 5+90 | LOOKING S | REFER TO 9/22/15 PHOTO LOG (PHOTO #3) |
| 1 REFER TO PHOTO LOG (9/22/15) PHOTOS 1, 2, 3 FOR SUPPORTING SUBGRADE PHOTOS | | | | 2 |

LANGAN

# Certificate of Soil Surface

Sheet # 21

| | | | | | |
|---|---|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 5+30 TO ~STA. 4+50 | | |
| QA Monitor | LANGAN | Date | 9/23/15 | | |

Description of Soil Surface to be lined: ~480 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEC-MEMBRANE PANELS INSTALLED ON 9/22/15 (PANEL #110). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 5+30 TO APPROX. STA. 4+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name: | DANIEL BUSWORTH |
| Date: | 9/23/15 |
| Title: | LEAD QA ENGINEER |
| Representing: | LANGAN |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 9-23-15 |
| Title: | QC Manager |
| Representing: | Caroline Panico |
| Signature: | ENTACT |

LANGAN

Notes, Observations, Comments SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8.

- GCL PLACED ALONG NORTHERN AND SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO 1FT. ABOVE) THE GROUNDWATER TABLE AS SHOWN ON PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #1 | ~STA. 4+90 | LOOKING S | REFER TO 9/23/15 PHOTO LOG (PHOTO #1) |
| | 2 PHOTO #2 | ~STA. 4+70 | LOOKING W | REFER TO 9/23/15 PHOTO LOG (PHOTO #2) |

1 REFER TO PHOTO LOG (9/23/15) PHOTOS 1, 2 FOR SUPPORTING SUBSEQUENT PHOTOS

2

LANGAN

# Certificate of Soil Surface

Sheet # 22


| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 4+50 to ~Sta. 3+80 | | |
| QA Monitor | Langan | Date | 9/24/15 | | |

Description of Soil Surface to be lined: ~480 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/23/15 (Panel N114). Subgrade Approved for Area East of 3rd Utility Corridor From Approximate Sta. 4+50 to Approx. Sta. 3+80. Soil Appears to Be Graded, Compacted, and Free of Debris (>½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bodworth |
| Date: | 9/24/15 |
| Title: | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-24-15 |
| Title: | QC Manager |
| Representing: | Entrie |
| Signature: |  |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (7½") AS OUTLINED IN SECTION 02372-8

- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO 1FT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG BOTTOM + SLOPES OF UTILITY/DRAINAGE DITCHES RUNNING N-S THROUGH SA-6, AND AS SHOWN ON THE PROJECT DRAWINGS

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 4+50 | LOOKING S | REFER TO 9/24/15 PHOTO LOG (PHOTO #3) |
| | 2 PHOTO #4 | ~STA. 4+50 | LOOKING E | REFER TO 9/24/15 PHOTO LOG (PHOTO #4) |

1 REFER TO PHOTO LOG (9/24/15) PHOTOS 3,4 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR PICTURES OF GCL

2

LANGAN

# Certificate of Soil Surface

Sheet # 23

| | | | |
|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 3+80 to ~Sta. 3+30 |
| QA Monitor | Langan | Date | 9/25/15 |

Description of Soil Surface to be lined: ~ 50 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/24/15 (Panel #118). Subgrade Approved for Area East of 3rd Utility Corridor from Approximate Sta. 3+80 to Approx. Sta. 3+30. Soil Appears to Be Graded, Compacted, and Free of Debris (>½") and in Conformance with Project Specs.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N - No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 9/25/15 |
| Title: | Lead QA Engineer |
| Representing: | Langan |
| Signature: |  |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Carolina Panico |
| Date: | 9-25-15 |
| Title: | QC Manager |
| Representing: | Entuc |
| Signature: | Carolina Panico |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1/2") AS OUTLINED IN SECTION 02372-8

- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AND AT AREAS BELOW (TO 1 FT. ABOVE) THE GROUNDWATER TABLE, AS DEFINED ON THE PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #5 | ~STA. 3+50 | LOOKING E | REFER TO 9/25/15 PHOTO LOG (PHOTO #5) |
| | 2 PHOTO #6 | ~STA. 3+40 | LOOKING N | REFER TO 9/25/15 PHOTO LOG (PHOTO #6) |
| 1 REFER TO PHOTO LOG (9/25/15) PHOTOS 5,6 FOR SUPPORTING SUBGRADE PHOTOS (WITH GCL) | | | | 2 |

LANGAN

# Certificate of Soil Surface

Sheet # 24

| | | | |
|---|---|---|---|
| Project Name | HONEYWELL SA-6 SOUTH | Material Desc. | GEOMEMBRANE + GCL |
| Project No. | 100530001 | General Desc. | (Subgrade) / Operations / LCRS |
| Owner/ Contr. | HONEYWELL / AMEC FW | Cell No. | ~STA. 3+30 TO ~STA. 2+50 |
| QA Monitor | LANGAN | Date | 9/29/15 |

Description of Soil Surface to be lined: ~80 FT. SECTION OF SOIL SUBGRADE APPROVED EAST OF GEOMEMBRANE PANELS INSTALLED ON 9/25/15 (PANEL #120). SUBGRADE APPROVED FOR AREA EAST OF 3RD UTILITY CORRIDOR FROM APPROXIMATE STA. 3+30 TO APPROX. STA. 2+50. SOIL APPEARS TO BE GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AND IN CONFORMANCE WITH PROJECT SPECS.

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified | N - NO CHANGES |

| Independent CQA Monitor | |
|---|---|
| Name | DANIEL BOSWORTH |
| Date | 9/29/15 |
| Title | LEAD QA ENGINEER |
| Representing | LANGAN |
| Signature | |

| Geosynthetic Installer Representative | |
|---|---|
| Name | Carolina Panico |
| Date | 9-29-15 |
| Title | QC Manager |
| Representing | Entact |
| Signature | Carolina Panico |

LANGAN

Observations/Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>1½") AS OUTLINED IN SECTION 02372-8.

- GCL PLACED ALONG NORTHERN & SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW, (TO 1 FT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG LOWER BENCH ON EASTERN END OF SA-6 AS SHOWN ON THE PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #2 | STA. 3+30 | LOOKING S | REFER TO 9/29/15 PHOTO LOG (PHOTO #2) |
| | 2 PHOTO #3 | STA. 2+90 | LOOKING E | REFER TO 9/29/15 PHOTO LOG (PHOTO #3) |

1 REFER TO PHOTO LOG (9/29/15) PHOTOS 2,3 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR PICTURES OF GCL.

2

LANGAN

# Certificate of Soil Surface

Sheet # 25

| | | | | | |
|---|---|---|---|---|---|
| Project Name | Honeywell SA-6 South | Material Desc. | Geomembrane + GCL | | |
| Project No. | 100530001 | General Desc. | (Subgrade) | Operations | LCRS |
| Owner/ Contr. | Honeywell / Amec FW | Cell No. | ~Sta. 2+50 to ~Sta 1+50 | | |
| QA Monitor | Langan | Date | 10/8/2015 | | |

Description of Soil Surface to be lined: ~100 ft. Section of Soil Subgrade Approved East of Geomembrane Panels Installed on 9/29/15 (Panel # 125). Subgrade Approved for Area East of 3rd Utility Corridor from Approximate Sta. 2+50 to Approx. Sta. 1+50 (Eastern End of SA-6, Route 440). Soil Anchors to be Graded, Compacted, and Free of Debris (>½") and in Conformance w/ Specs

I hereby certify that the above surface area is suitable for the installation of geosynthetics, and I shall be responsible for its integrity and suitability in accordance with the specifications from this date to the completion of the installation.

| Visual Inspection of Subgrade Surface | |
|---|---|
| QUALITY | Y/N/NA |
| **Geomembrane** | |
| Smooth | Y |
| Uniform | Y |
| Relatively free from abrupt changes in grade, rocks larger than ½, sharp objects, and debris | Y |
| Free of standing water | Y |
| Surface area to be lined has been properly prepared | Y |
| **Geocomposite Clay Liner** | |
| Free from wheel ruts, debris, rocks, sticks, and rocks larger than 1 inch | Y |
| Suitable for placement of GCL | Y |
| Smooth | Y |
| Any changes required? If so the contractor and owner's representative must be notified. | N-No Changes |

| Independent CQA Monitor | |
|---|---|
| Name: | Daniel Bosworth |
| Date: | 10/8/2015 |
| Title | Lead QA Engineer |
| Representing: | Langan |
| Signature: | |

| Geosynthetic Installer Representative | |
|---|---|
| Name: | Caroline Panico |
| Date: | 10/8/15 |
| Title | QC Manager |
| Representing: | ENTACT |
| Signature: | |

LANGAN

Notes, Observations, Comments: SOIL GRADED, COMPACTED, AND FREE OF DEBRIS (>½") AS OUTLINED IN SECTION 02372-8
- GCL PLACED ALONG NORTHERN + SOUTHERN BOUNDARIES OF SA-6 CAP AT AREAS BELOW (TO LFT. ABOVE) THE GROUNDWATER TABLE. GCL ALSO PLACED ALONG LOWER BENCH ON EASTERN END OF SA-6 AS SHOWN ON PROJECT DRAWINGS.

| Photographs | Number | Location | Orientation | Notes |
|---|---|---|---|---|
| | 1 PHOTO #3 | ~STA. 1+70 | LOOKING N/NW | REFER TO 10/8/15 PHOTO LOG (PHOTO #3) |
| | 2 PHOTO #4 | ~STA. 2+00 | LOOKING S | REFER TO 10/8/15 PHOTO LOG (PHOTO #4) |
| 1 REFER TO PHOTO LOG (10/8/15) PHOTOS 3,4 FOR SUPPORTING SUBGRADE PHOTOS. ALSO REFER TO PHOTO LOG FOR SUPPORTING PHOTOS OF GVL + GCL | | | | 2 |

# Appendix F
# Langan Daily Reports & Supporting Photo Logs

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/7/2015 |
| **PROJECT:** | SA-6 Capping | | **WEATHER:** | 75/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Soil Subgrade Inspection | **TIME:** | 0600 – 1400 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #1** |
|---|---|
| **Thatcher Foundations**<br>*Equipment:* Dozer, Steel Drum Roller, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Dave Ambrose<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT**: Keith Goisse |

## ***Site Activities***

- Langan onsite to conduct soil subgrade inspection. Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area.
- Langan and ENTACT (two laborers) conducted visual inspection of the prepared soil subgrade. This area included the furthest western part of the cap (Sta. 24+00) to just east of Sta. 18+50.
- In general, the following soil subgrade properties were observed:
    - Some debris (wood fragments),small rocks, etc. were observed along the slopes and elevation changes from Sta. 24+00 to Sta. 18+50. It is recommended during the pull back and removal of the plastic tarp (in preparation for installation of liner), ENTACT should provide laborers with a wheelbarrow and equipment to collect various debris as it is encountered.
    - Along the slopes of the smaller swales, utility corridors, street channels, etc. some soft and loose material was noted. As recommended above, as the plastic is removed for liner installation activities, Entact should provide laborers to dress the slopes (i.e. remove any loose debris and conduct compaction (as required) with a hand tamper), as necessary.
- In addition to the general soil subgrade properties outlined above, some soft / wet areas (some with free standing water) were encountered. The location of these wet areas was in the general vicinity of the collection manhole (Sta. 21+00), where the soil subgrade was very soft (able to sink into the soil while walking). Langan conducted a site walk with AmecFW to collect GPS locations of these soft, underlying areas. The attached figure provides the swales, corridors, and trenches within vicinity of the collection manhole that do not meet the soil subgrade requirements. Additional grading / compaction activities will be required prior to liner installation within these areas.
    - Note: The locations on the attached figure do not represent every area that needs additional preparation activities. The general soil subgrade properties outlined above could represent varying locations as the entire soil area could not be observed due to the plastic being placed over the cap area. The locations outlined on the attached figure are meant to provide “critical” areas that may require more substantial work activities in order to have the subgrade properly prepared to the specifications.

Cc Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Observations Requiring Contractor / QA Engineer Review***

- Based on the soil subgrade inspection, the soil has not been approved for liner installation activities based on the wet / soft spots encountered (as outlined within this report). It is also recommended that laborers are provided when the plastic sheeting is removed so that the loose debris can be collected, and additional grading / compacting activities can be conducted (as required) along the slopes and contours.

***Action Items Pending***

- QA Engineer - Review SA-6 capping specifications and drawings. Review product submittals (as provided) and ensure that all data, drawings, and pertinent documents are ready for liner installation kickoff (planned for the week of 7/13).

***Action Items – Weekly Completions***

- None to Date

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Cap Installation Kickoff meeting scheduled for Thursday (7/9/15). At this time an additional soil subgrade inspection should be conducted with ESI representatives.

Cc: Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Photograph Log***



Photo 1: Completed soil subgrade with plastic sheeting cover (looking west toward Sta. 24+00).



Photo 2: Entact conducting grading and compacting activities to the area east of Sta. 19+00.

***Photograph Log (continued)***



Photo 3: Graded and compacted soil subgrade near Sta. 24+00 (acceptable subgrade).



Photo 4: Miscellaenouos debris (wood, rocks, etc.) encountered. Debris removed from subgrade, however, while plastic sheeting is removed in prep for installation, additional observations shall be conducted to ensure all debris is removed prior to liner installation.

***Photograph Log (continued)***



Photo 5: Loose material and debris encountered along swale slope.



Photo 6: Standing water encountered along northern drainage swale / tree bulb.

***Photograph Log (continued)***




Photo 7: Standing water / soft area in vicinity of collection manhole (Sta. 21+00).



Photo 8: Soft / wet soil in vicinity of manhole. Indentations / footprints visible.

LANGAN




Notes:
1. Locations GPS surveyed by Langan and AMEC for soil subgrade areas requiring additional preparation activities prior to liner placement.
2. This Figure represents critical locations that were observed by the project team and does not include every area that may require additional preparation work. As the plastic sheeting is removed from the cap, ENTACT should provide sufficient manpower to remove potential miscellaneous debris, and re-grade / compact slopes, as required.
3. Subgrade observations collected on 7/7/15 and 7/13/15 by Langan field personnel and represent the areas between the western most boundary (Sta 24+00), and east of Sta17+50. The area to the east of Sta. 17+50 has not yet been observed.

LANGAN
River Drive Center 1, 619 River Drive, Elmwood Park, NJ 07407-1338
T: 201.794.6900 F: 201.794.0366 www.langan.com
NEW JERSEY NEW YORK VIRGINIA CALIFORNIA
PENNSYLVANIA CONNECTICUT FLORIDA
ABU DHABI ATHENS DOHA
DUBAI ISTANBUL
Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.
Langan International LLC
Collectively known as Langan

Project
Honeywell
CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY
HUDSON COUNTY NEW JERSEY

Drawing Title
SA-6 SOUTH CAP SUBGRADE INSPECTIONS

| | |
|---|---|
| Project No. 100530001 | Figure 7 |
| Date 8/20/2015 | |
| Scale N.T.S. | |
| Drawn By ATR | |
| Last Revised 8/20/2015 | |

© 2013 Langan

Path: \\langan.com\data\EP\data0\100530001\ArcGIS\ArcMap_Documents\SA-6 South Cap Subgrade Inspections.mxd

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/13/2015 |
| **PROJECT:** | SA-6 Capping | | **WEATHER:** | 80/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Soil Subgrade Inspection | **TIME:** | 0600 – 1100 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #2** |
|---|---|
| **Thatcher Foundations**<br>*Equipment:* Dozers, Steel Drum Rollers, Misc. Hand Tools (shovels, rakes) | **AmecFW**:Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT**: Keith Goisse |

## ***Site Activities***

- Langan onsite to conduct soil subgrade inspection, and to observe placement of first layer of geocomposite (gas venting layer) for SA-6 south capping. Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area.
- Based on subsequent conversations with the project team, no material was to be placed during the day (GDL or LLDPE) as the geomembrane was undergoing final conformance testing requirements and had not yet been delivered to the Site. As such, Langan and AmecFW conducted a visual inspection of the prepared soil subgrade. These areas included the locations previously identified during the Day #1 soil subgrade inspection, as well as additional areas completed since that date from Sta. 18+50 to Sta. 17+50, as shown in the attached Figure (Sheet 7).
- In general, the following soil subgrade properties were observed:
  - ENTACT had opened and dried the areas immediately west of the collection manhole. Additionally, ENTACT provided laborers to dress and repair the slopes, as required. Refer to Sheet 3 for example of slope that would require dressing. The additional areas east of the collection manhole will also be opened and dried, with additional preparation being completed, as required. Refer to Sheet 7 for areas that ENTACT has repaired soil to appropriate subgrade.
  - The slopes of the smaller swales, utility corridors, street channels, etc. some soft and loose material was noted. As the plastic is removed for liner installation activities, ENTACT should provide laborers to dress the slopes (i.e. remove any loose debris and conduct compaction (as required) with a hand tamper), as necessary.
- In addition to the general soil subgrade properties outlined above, some soft / wet areas (some with free standing water) were encountered east of the previously inspected areas. The coordinates of these locations were collected and are shown on Sheet 7. Additional grading / compaction activities will be required prior to liner installation within these areas.
  - Note: The locations on the attached figure do not represent every area that needs additional preparation activities. The general soil subgrade properties outlined above could represent varying locations as the entire soil area could not be observed due to the plastic being placed over the cap area.

Cc Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

The locations outlined on the attached figure are meant to provide "critical" areas that may require more substantial work activities in order to have the subgrade properly prepared to the specifications.

***Observations Requiring Contractor / QA Engineer Review***

- Based on the soil subgrade inspection conducted to date, it appears that the soil west of the collection manhole is acceptable to commence with installation activities. However, ENTACT shall provide laborers as the plastic is removed to conduct slope dressing and re-compaction (as required), as well as, to remove any unacceptable debris (i.e. rocks, misc. debris, etc.) from the subgrade. If further soil deterioration is encountered prior to the placement of the GDL and liner material, additional re-grading and re-compaction of the soil subgrade may be required. As such, the final soil subgrade inspection form will not be completed until immediately prior to GDL and liner placement.
- Based on the wet / soft spots encountered (as outlined within this report) east of the collection manhole, it appears that this soil subgrade is not suitable for liner installation activities. Additional preparation work (i.e. drying, re-compaction, etc.) is required prior to liner placement. It is also recommended that laborers are provided when the plastic sheeting is removed so that any loose debris can be collected, and additional grading / compacting activities can be conducted (as required) along the slopes and contours.

***Action Items Pending***

- QA Engineer - Review SA-6 capping specifications and drawings. Review product submittals (as provided) and ensure that all data, drawings, and pertinent documents are ready for liner installation kickoff (planned to commence on 7/15).

***Action Items – Weekly Completions***

- None to Date

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work will be conducted tomorrow (7/14) by ENTACT.
- Preparation and coordination to ensure that liner placement can begin on Wednesday (7/15).

Cc: Jeff Stoicescu, Rory Johnston, Vikki Hon, File

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Photograph Log***



Photo 1: Example of washed slope that would require regarding and re-compaction activities.



Photo 2: Swale / root bulb with standing water and soft / wet bottom. Additional prep work required.

***Photograph Log (continued)***



Photo 3: ENTACT dressing slopes west of collection manhole.



Photo 4: Area west of collection manhole. Opened and dried. ENTACT dressing slopes (as required).

***Photograph Log (continued)***



Photo 5: Wet area located east of collection manhole on top deck (still requires drying and re-compaction).



Photo 6: Dry area re-compacted west of collection manhole.


***Photograph Log (continued)***




Photo 7: ENTACT filling and re-compacting depressions / voids in subgrade along southern edge of SA-6.



Photo 8: Grading and compacting soil east of collection manhole near Sta. 17+50.




## Legend

★ Respresents slopes and elevation changes that will require dressing (i.e. debris removal, re-compaction, etc.)

## Status

Represents areas that have been dried, regraded, and re-compacted. Soil appears acceptable for liner placement

Represents areas where ENTACT is presently drying and conducting regrading and re-compaction as required.

Represents areas that exhibit soft / wet subgrade. Soil not acceptable for liner placement.

Notes:
1. This Figure represents critical locations that were observed by the project team and does not include every area that may require additional preparation work. As the plastic sheeting is removed from the cap, ENTACT should provide sufficient manpower to remove potential miscellaneous debris, and re-grade / compact slopes, as required.
2. Subgrade observations collected on 7/7/15 and 7/13/15 by Langan field personnel and represent the areas between the western most boundary (Sta 24+00), and east of Sta17+50. The area to the east of Sta. 17+50 has not yet been observed.

LANGAN
River Drive Center 1, 619 River Drive
Elmwood Park, NJ 07407-1338
T: 201.794.6900 F: 201.794.0366 www.langan.com
Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.
Langan International LLC
Collectively known as Langan
NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project
Honeywell
CHROMIUM REMEDY STUDY AREA 6 SOUTH
JERSEY CITY
HUDSON COUNTY NEW JERSEY

Drawing Title
SA-6 SOUTH CAP SUBGRADE LANGAN FIELD OBSERVATIONS

| | |
|---|---|
| Project No. | 100530001 |
| Date | 7/13/2015 |
| Scale | N.T.S. |
| Drawn By | ATR |
| Last Revised | 7/14/2015 |
| SHEET | 7 |

© 2012 Langan

Path: \\langan.com\data\EP\data0\100530001\ArcGIS\ArcMap_Documents\SA-6 South Cap Subgrade Langan Field Observations.mxd

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/20/2015 |
| **PROJECT:** | SA-6 Capping | | **WEATHER:** | 80/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1900 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #3**<br>**AmecFW**:Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth, Jeff Stoicescu<br>**ENTACT**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) starting at the west end of the SA-6 south. Material to be placed from the western end (west of Sta. 24+00, located at approximate Sta. 24+35) of SA-6 for approximately 100 ft. east to approximate Sta. 23+35.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area).
- Prior to placement of GVL or Cap, the plastic sheeting protecting the soil subgrade from the work area was removed. Final soil subgrade inspection was conducted for the area outlined above. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3, 4, and 5 of the daily photo log for 7/20/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the area of approximate Sta. 24+35 to Sta. 23+35 as outlined above.
- Upon soil subgrade approval, and prior to placement of the GVL and Liner, it was determined that an onsite meeting to discuss the revised panel layout and placement would be conducted between AmecFW, Langan, and ENTACT. During this meeting, the revised panel layout, seaming, soil subgrade approval, and other pertinent issues were discussed. Upon review of these topics, it was determined that ESI could begin with placement of GVL and Liner.
- ESI began by placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed on the western end of the Site (Sta. 24+35) moving east. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 7/20/15 Photo Log for supporting photographs.
- After installation of GVL, geomembrane liner was installed beginning at the western end of the Site and moving east. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from Sta. 24+35 to approximate Sta. 23+35. A total of four panels were installed (P-1, P-2,

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

P-3, and P-4), with seams overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing. The results of the pre-trial weld are provided in the associated QA form submitted for today (7/20), *Trial Weld Log.*

- Upon installation and welding of the geomembrane panels, based on required working permit hours, it was determined that non-destructive testing, and liner repair work would be conducted on 7/21/15. A destructive sample (DS-1) was collected, however, this sample was not shipped on 7/20/15 due to the extended working hours. Sample to be recorded on the *Destruct Log* and shipped on 7/21/15.

## ***Non-Conformance Items / Corrective Actions***

- None Encountered.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log. Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, etc.)
- Review laboratory results for destruct sample DS-1.

## ***Action Items – Weekly Completions***

- None to Date

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 23+35 to Sta. 22+35).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | |
| A2 – Receiving and Inspection | Sheet 1 (7/20) | RIR for 12 rolls of LLDPE delivered on 7/20/15 (Report Number 47) |
| A3 – Photo Log | Pages 1 - 8 | Total of 16 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date with LLDPE included until 7/20/15 |
| A5 – Subgrade Approval | Sheets 1 & ESI Form 7/20 | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 1 | One trial weld log provided by ESI and confirmed by Langan. |
| A7 – Panel Placement Log | Sheet 1 | One panel placement log provided by ESI and confirmed by Langan |
| A8 – Seam Testing COC | | N / A for 7/20/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A for 7/20/15 |
| A10 – Repair Log | | N / A no patch / repair work completed on 7/20 |
| A11 – Conformance COC | | N / A for 7/20/15 |
| A12 – Destructive Seam Field Test | | N / A DS-1 collected, however this repair and paperwork will be completed on 7/21 |
| A13 – Destruct. Sample Summary | | N / A to be updated on 7/21 |
| A14 – Penetration & Edge Form | | N / A penetrations for wells to be booted and completed at a later date |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking south away from SA-6

**Description:**

Entact / ESI offloading rolls of 60-mil geomembrane liner according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking west toward Sta. 24+00

**Description:**

Entact removing plastic sheeting to uncover and expose soil subgrade between Sta. 24+35 and Sta. 23+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking north toward Grid Point 11
15.00

**Description:**

Prepared soil subgrade approved for liner placement. Slopes compacted and free of loose debris > ½ inch.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking north along Sta. 23+50 corridor

**Description:**

Prepared soil subgrade approved for liner placement Soil compacted and free of loose debris (> ½ inch), based on visual observations.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking north along Sta. 24+00

**Description:**

Prepared soil subgrade approved for liner placement. Based on visual observations, soil is graded, compacted, and free of loose debris, as defined by the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking south / southeast along southern wall of SA-6 cap.

**Description:**

16 oz. geotextile installed along sheet pile wall according to specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking north / northwest near Sta. 24+00.

**Description:**

ESI placing GVL along western end of SA-6 cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/20/15

**Direction Taken:**

Looking north near Sta. 24+00

**Description:**

White plastic fasteners placed at minimum 5 ft. intervals along GVL geonet as outlined in specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/20/15

**Direction Taken:**

Looking north near Sta. 24+00.

**Description:**

ESI sewing geotextile seams along installed GVL panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/20/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/20/15

**Direction Taken:**

Looking east near Grid Point 11
15.0

**Description:**

ESI cutting GVL to allow proper conforming within swale / tree bulb contour. Cut patched with GVL and



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking south away from SA-6 cap.

**Description:**

ESI conducting trial weld for LLDPE (geomembrane) seaming as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking south along western end of SA-6 cap.

**Description:**

Placement of LLDPE (geomembrane) along western end of cap (Sta. 24+35). Panel #1 (P-1) from approved geomembrane roll (Roll #283031).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #13 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking south away from SA-6 cap.

**Description:**

Placement of Panel #2 (P-2) east of P-1.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #14 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking south along western end of SA-6 cap.

**Description:**

Fusion welding conducted between Panel #1 (P-1) and Panel #2 (P-2).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking northwest along western end of SA-6 south cap.

**Description:**

Installed LLDPE geomembrane panels (P-1, P-2).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #16 (07/20/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/20/15

**Direction Taken:**

Looking northeast from western end of SA-6 South cap.

**Description:**

Installed LLDPE geomembrane panels (P-3 ,P-4)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/21/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 83/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #4**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #4 (P-4) installed on 7/20/15 (located at approximate Sta. 23+25) running approximately 100 ft. east (Sta. 22+35).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting non-destructive testing and patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/20/15 (Panels 1-4). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed with the project specifications (refer to *Preweld Test Report* for 7/21/15 for results).
- A total of eight repairs (RP-1 through RP-8) were observed and fixed (according to the project specifications) from Panel #1 through Panel #4. The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted, as outlined in the project specifications.
- Some non-conformance issues were observed, outside of the "custom fit" repairs noted above (refer to *Notice of Non-Compliance and Corrective Action* forms), and were documented on Sheet #1 and Sheet #2 as non-compliance. These issues were also recorded within the *Repair Log* as a subgrade irregularity and are identified as RP-3 and RP-8. The non-compliance issues encountered were identified based on debris / rocks that were observed underneath the geomembrane cap. The rocks were removed from these areas and the hole was patched / repaired according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – *Sheet #1* and *Sheet #2* for 7/21/15.
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/20/15, Entact removed the plastic sheeting protecting the soil subgrade for the next 100 ft. section of work area (approximate Sta. 23+35 to Sta. 22+35). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/21/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to *Photos #9 & 10* of the daily photo log for 7/21/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 23+35 to Sta. 22+35 as outlined above.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 23+35 (east of P-4) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *7/21/15 Photo Log* for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #4 (located at approximate Sta. 23+35) on 7/20/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 23+35 to Sta. 22+35. A total of four panel lengths were installed (P-5, P-6, P-7, P-8, P-9) by ESI. Note: Encountered the end of the geomembrane roll while placing Panel #6 (P-6). Butt seam required between P-6 and P-7. A destructive test sample (DS-2) was also collected from this seam (one sample for ESI, and one sample for Langan). The results of trial welding test for the destructive sample are outlined in the *Preweld Test Report* for 7/21/15. A total of ten 1-inch specimens were collected for peel and shear strength testing (5 tests for each).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/20), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted patch / repair work and non-destructive testing on Panels 5-9 (as outlined in the project specifications). During the non-destructive testing conducted between Panel 7 (P-7) and Panel 8 (P-8), the non-destruct test failed and a non-compliance issue was noted. Since P-7 only extended approximately 6 ft. (north to south), the entire seam would be patched and repaired (according to the project specifications) on 7/22/15.
- It should also be noted that pipe booting activities were conducted on piezometer PZ20 and well 073-MW-1BR as outlined in the project specifications. These two penetrations were sealed with geomembrane according to the project specifications. However, the final clamps with gasket have not yet been installed. The *Gas Vent and Piezometer Penetrations* Form will be filled and out and confirmed by Langan and ESI once these activities are completed.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 1 (Sheet #1) – Subgrade irregularity identified as RP-3 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #2). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 1 Notice of Non-Compliance*
- Non-Conformance No. 2 (Sheet #2) – Subgrade irregularity identified as RP-8 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #2). Stone was subsequently removed and hole was patched/repaired following project specs and further defined in *Sheet 2 Notice of Non-Compliance.*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Non-Conformance No. 3 (Proposed Sheet #3) – Failed seam
    - During non-destruct testing of P-7 and P-8 (6 ft. run north to south), the test failed as pressure could not be held within 4 psi (as outlined in project specifications). ESI will patch and repair the entire 6 ft. seam length (according to project specs) and this non-compliance issue will be documented on 7/22/15 and issued a repair number.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/21/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.)
- Review laboratory results for destruct sample DS-2. Note: QA destruct sample also collected (DS-2) by Langan.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Reviewed laboratory destruct sample results for samples DS-1. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 22+35 to Sta. 21+35).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/21/15 |
| A3 – Photo Log | Pages 1 – 9 | Total of 18 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date |
| A5 – Subgrade Approval | Sheet 2 & ESI (7/21/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A6 – Trial Weld Log | Sheet 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/21/15. |
| A7 – Panel Placement Log | Page 2 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/21/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | One Destruct Seam Testing COC for samples collected to date. |
| A9 – Seam/Non-Destruct. Test Log | Page 1 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/21/15. |
| A10 – Repair Log | Page 1 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/21/15 |
| A11 – Conformance COC | | N / A for 7/21/15 |
| A12 – Destructive Seam Field Test | Page 1 | Destructive Seam Field Test log completed by ESI and confirmed by Langan for samples on 7/21/15 |
| A13 – Destruct. Sample Summary | Sheet 1 | Destructive Sample Summary completed by ESI and confirmed by Langan on 7/21/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | Sheets 1 & 2 | Notice of Non-Compliance forms completed by Langan and confirmed by ESI/Entact for 7/21/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking north to the east of P-4

**Description:**

Entact preparing soil subgrade for liner placement between Sta. 23+35 and Sta. 22+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking down at installed geomembrane cap (near Break Point 548
15.12)

**Description:**

ESI conducting capping repair work around Break Point 548-15.12). Cap patched and sealed with extrusion welds (documented in Repair Log as RP-1).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking east toward installed Panel #4 (P-4). Placed on 7/20/15

**Description:**

Non-destructive weld test performed by ESI between Panel #3 and Panel #4. Non-destruct conducted according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking north along approximate Sta. 24+00

**Description:**

ESI patching / repairing area along swale / contour to allow for geomembrane to conform to grade. Patching recorded in Repair Log as RP-1.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking west toward RP-3

**Description:**

ESI conducting extrusion welding on RP-3. RP-3 identified as non-conformance repair. Rock observed underneath geomembrane.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east down along geomembrane liner near Sta. 24+00.

**Description:**

ESI conducting vacuum box testing on extrusion welds as per project specifications. Vacuum box test being conducted on RP-1.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/21/15

**Direction Taken:**

Looking north toward well

**Description:**

ESI installing geomembrane boot around well 073-MW-1BR according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking west along western end of cap at well piezometer PZ20

**Description:**

ESI installing geomembrane boot around piezometer PZ20 as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east beyond Sta. 23+35 (east of P-4)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking east along southern section of SA-6 (from approximate Sta. 23+35)

**Description:**

Prepared soil subgrade as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking northeast along northern end of SA-6

**Description:**

ESI placing 16 oz. geotextile around northern soil cement bentonite (SCB) wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking south near Sta. 23+35

**Description:**

ESI placing GVL (N-S orientation) to the east of installed geomembrane liner. GVL placed from approximate Sta. 23+35 to Sta. 22+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking south along SA-6

**Description:**

Plastic fasteners placed at maximum of 5 ft. spacing for tying adjacent panels of GVL (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

PHOTOGRAPHIC LOG
Photo #13 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking north near Sta. 23+35

**Description:**

ESI sewing top of geotextile seem on GVL as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/21/15

**Direction Taken:**

Looking south near Sta. 23+00

**Description:**

ESI placing 60-mil geomembrane cap, Panel #5 (P-5).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (07/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/21/15

**Direction Taken:**

Looking north along northern slope of SA-6

**Description:**

ESI conducting fusion welding between geomembrane P-4 and P-5 panel seams (as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #17 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking south along geomembrane Panel #6 (P-6).

**Description:**

Installed geomembrane Panel #6 (P-6).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #18 (07/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/21/15

**Direction Taken:**

Looking north along SA-6 cap.

**Description:**

Installed geomembrane panels to approximate Sta. 22+35.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/22/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/82° F, Clear, Sunny, Wind (15 mph) |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #5**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #9 (P-9) installed on 7/21/15 (located at approximate Sta. 22+35) running approximately 95 ft. east to Sta. 21+40.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting non-destructive testing and patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/21/15 (Panels 5-9). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed with the project specifications (refer to *Preweld Test Report* for 7/22/15 for results. Extrusion testing identified with as EXT on form).
- A total of six repairs (RP-9 through RP-14) were observed and fixed (according to the project specifications) from Panel #5 through Panel #9. The majority of these repairs were associated with piezometer pipe boots and repairs for the destructive samples collected. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-conformance issue was observed, outside of the repairs noted above (refer to *Notice of Non-Compliance and Corrective Action* forms), and was documented on Sheet #3 as non-compliance. This issue was also recorded within the Repair Log as a failed seam test (non-destruct test) and identified as RP-13.
- The non-compliance issue encountered was a failed non-destructive seam test conducted between Panels 7/8. The failed seam was along the southern end of SA-6 and was only 6 ft. in total length (butt end of seam as outlined in the 7/21/15 report). As such, the seam was patched according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – Sheet #3 for 7/21/15.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Upon completion of the cap detailing, ESI began to install GDL panels beginning at the western end of the Site (Sta. 24+35) and moving east. The GDL panels were installed over the geomembrane cap previously placed on 7/20/15, and were installed to just before the first destructive sample collected (DS-1) along Panels 3/4.
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/21/15 and installing GDL, Entact removed the plastic sheeting protecting the soil subgrade for the next 95 ft. section of work area (approximate Sta. 22+35 to Sta. 21+40). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/22/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 & 3 of the daily photo log for 7/22/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 22+35 to Sta. 21+40 as outlined above.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 22+35 (east of P-9) moving east (for approximately 95 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 7/22/15 Photo Log for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #9 (located at approximate Sta. 22+35) on 7/21/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 22+35 to Sta. 21+40. A total of four panel lengths were installed (P-10, P-11, P-12, and P-13) by ESI.
- A destructive test sample (DS-3) was collected from the Panel 10/11 seam, within the 500 ft. linear foot requirement outlined in the project specifications. The results of trial welding test for the destructive sample are outlined in the *Preweld Test Report* for 7/22/15. A total of ten 1-inch specimens were collected for peel and shear strength testing (5 tests for each).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/22), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted patch / repair work and non-destructive testing on Panels 10-13 (as outlined in the project specifications). The patches associated with Panels 10-13 will be completed with extrusion welds on 7/23/15.
- It should also be noted that pipe booting activities were conducted well 115-W3-SO (located on Panel #8, northern slope) as outlined in the project specifications. The penetration was sealed with geomembrane according to the project specifications. However, the final clamps with gasket have not yet been installed. The *Gas Vent and Piezometer Penetrations* Form will be filled and out and confirmed by Langan and ESI once these activities are completed. Additionally, a gas vent pipe (GV-7) was covered with geomembrane, and will be cut, sealed, and booted according to the specifications at a future date.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 3 (Sheet #3) – Failed seam, identified as RP-13 on *Repair Log*
    - During non-destruct testing of P-7 and P-8 (6 ft. run north to south), the test failed as pressure could not be held within 4 psi (as outlined in project specifications). This area was patched and repaired along the entire 6 ft. seam length (according to project specs) as outlined on *Sheet #3*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

*Notice of Non-Compliance*.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/22/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/21/15.
- Review laboratory results for Destruct Sample (DS-3)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/21/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Destructive Sample Summary,* and *Certificate of Subgrade Acceptance* forms. Additional review of Preweld Test Report, Seam Control Form, and Repair Report required prior to acceptance.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-2, as well as Langan QA sample (DS-2). Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 21+40 to Sta. 20+40).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/22/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date |
| A5 – Subgrade Approval | Sheet 3 & ESI (7/22/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/22/15. |
| A7 – Panel Placement Log | Page 3 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/22/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | One Destruct Seam Testing COC for samples collected to date. |
| A9 – Seam/Non-Destruct. Test Log | Page 2 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/22/15. |
| A10 – Repair Log | Page 1 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/22/15 |
| A11 – Conformance COC | | N / A for 7/22/15 |
| A12 – Destructive Seam Field Test | Sheet 1 | Destructive Seam Field Test log completed by ESI and confirmed by Langan for samples on 7/22/15 |
| A13 – Destruct. Sample Summary | Page 1 | Destructive Sample Summary completed by ESI and confirmed by Langan on 7/22/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | Sheet 3 | Notice of Non-Compliance forms completed by Langan and confirmed by ESI/Entact for 7/22/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking northwest toward western end of SA-6 South.

**Description:**

ESI installing GDL along western end of SA-6, from Sta. 24+35 moving east (area previously covered with geomembrane liner on 7/20/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

Prepared soil subgrade for geomembrane placement. Approximate 95 ft. section east of geomembrane installed on 7/21/15, approved. Approximate location of Sta. 22+35 to Sta. 21+40.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking northeast through approximate Sta. 22+00 corridor.

**Description:**

Soil subgrade approved for geomembrane placement for 7/22/15. Soil graded, compacted, and free of debris (>1/2 inch) as outlined in the project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2215

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

16 oz. geotextile placed by ESI along southern wall of SA-6 with 2 ft. of overlap (outside of sheet pile wall) and one roll width inside.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking south along approx. Sta. 22+35.

**Description:**

ESI placing GVL along approved soil subgrade.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/22/15

**Direction Taken:**

Looking north along Sta. 22+35

**Description:**

White plastic fasteners placed at a maximum of 5 ft. intervals for tying adjacent panels (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking north along Sta. 22+35

**Description:**

ESI sewing geotextile along adjacent GVL panels (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/22/15

**Direction Taken:**

Looking south along installed geomembrane panels.

**Description:**

ESI deploying geomembrane panels (P-10 through P-14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking north along panel P-10

**Description:**

Installed Panel #10 (P-10) labeled with roll number (282018).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/22/15

**Direction Taken:**

Looking along geomembrane cap panels P-9 and P-10.

**Description:**

ESI conducting fusion welding between geomembrane P-9 and P-10 panel seams (as per project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/22/15

**Direction Taken:**

Looking along geomembrane panels

**Description:**

ESI conducting non-destructive testing as outlined in project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
7/22/15

**Direction Taken:**

Looking northeast along installed geomembrane cap for 7/21/15

**Description:**

Installed geomembrane cap weighted at end of day with sand bags.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/23/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/82° F, Clear, Sunny, Wind |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #6**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #13 (P-13) installed on 7/22/15 (located at approximate Sta. 21+40) running approximately 150 ft. east to Sta. 19+90.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying GDL along the western end of the cap. Based on the minor repairs required from the geomembrane placement on 7/22/15, it was determined that extrusion weld repairs would be conducted tomorrow (7/24/15).
- A total of 11 rolls (7 north to south runs over SA-6; approximately 165 ft.) of GDL were deployed along the western end of SA-6. GDL was installed to cover the geomembrane panels placed on 7/20/15 and 7/21/15 (GLD installed up to P-9). Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and geotextile seams sewn along the geotextile for adjacent panels.
- While ESI was and installing GDL along the western end of SA-6, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 150 ft. section of work area (approximate Sta. 21+40 to Sta. 19+90). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/23/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3,4,5, and 6 of the daily photo log for 7/23/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 21+40 to Sta. 19+90 as outlined above.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After geotextile was placed, GVL was installed from approximate Sta. 21+40 (east of P-13) moving east (for approximately 150 ft.) to Sta. 19+90. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally the top panel of geotextile was sewn along the seams (according to the project specifications). Refer to 7/23/15 Photo Log for supporting photographs.

- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #13 (located at approximate Sta. 21+40) on 7/22/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 21+40 to Sta. 19+90. A total of five panel lengths were installed (P-14, P-15, P-16, P-17 and P-18) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/23), *Trial Weld Log.*
- As outlined above, no extrusion welding and detailing activities were conducted by ESI. These activities are scheduled to be completed tomorrow (7/24) for the repairs associated with geomembrane capping from 7/22/15 and 7/23/15. It should also be noted that two destructive fusion weld samples will be collected on 7/24/15 from Panels 14-18. An extrusion weld sample will also be required once detailing activities commence in the morning.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items to be recorded from 7/23/15 as no repair work was completed.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/21/15 and 7/22/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- ESI – complete repair / patch work and collect appropriate destruct samples for fusion and extrusion welding (as outlined in project specifications.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, as well as reviewed and approved ESI submitted forms.
- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/21/15 and 7/22/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Destructive Sample Summary,* and *Certificate of Subgrade Acceptance* forms. Additional review of Preweld Test Report, Seam Control Form, and Repair Report required prior to acceptance.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-3. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 19+90 to Sta. 19+00).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/23/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/23/15 |
| A5 – Subgrade Approval | Sheet 4 & ESI (7/23/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/23/15. |
| A7 – Panel Placement Log | Page 4 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/23/15 |
| A8 – Destruct Seam Testing COC | | No destruct samples collected on 7/23/15. No updates |
| A9 – Seam/Non-Destruct. Test Log | Pages 3-4 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/23/15. |
| A10 – Repair Log | | N / A no repairs conducted on 7/23/15 |
| A11 – Conformance COC | | N / A for 7/23/15 |
| A12 – Destructive Seam Field Test | | N / A no destructive tests conducted on 7/23/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 7/23/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A16 – Notice of Non-Compliance | | N / A no repairs completed on 7/23/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/23/15

**Direction Taken:**

Looking north along western end of SA-6

**Description:**

GDL installed along western end of cap over geomembrane placed on 7/20/15 and 7/21/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking south along western end of SA-6

**Description:**

ESI placing GDL. Plastic fasteners spaced at maximum of 5 ft. and geotextile sewed along adjacent panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3(07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking east along southern boundary wall (sheet piling) of SA-6 from approximate Sta. 21+40

**Description:**

Soil subgrade approved for geomembrane placement for 7/23/15. Soil graded, compacted, and free of debris (>1/2 inch) as outlined in the project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/2315

**Direction Taken:**

Looking north along SA-6 at approximate Sta. 21+40

**Description:**

Approved soil subgrade for geomembrane placement. Subgrade prepared in accordance with project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking northeast toward Sta. 21+00 (collection manhole)

**Description:**

Approved soil subgrade for geomembrane placement. Soil prepared in accordance with project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking at prepared soil subgrade around collection manhole. Located by approximate break point 979-13.50

**Description:**

Soil subgrade prepared around collection manhole.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 21+20.

**Description:**

ESI placing GVL according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking north along SA-6

**Description:**

GVL panels installed according to project specifications. Plastic fasteners placed at maximum of 5 ft. spacing and geotextile sewed along adjacent panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/23/15

**Direction Taken:**

Looking east through Sta. 21+00

**Description:**

Installed GVL to approximate Sta. 20+30.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/23/15

**Direction Taken:**

Looking northeast at approximate Sta. 21+20

**Description:**

ESI placing geomembrane cap (Panels 14 & 15) on top of GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/23/15

**Direction Taken:**

Looking northwestern by northern slope of SA-6

**Description:**

ESI conducting fusion welding between Panels 13/14



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking south at southern end of SA-6

**Description:**

Installed geomembrane panel #14 (P-14) labeled with corresponding geomembrane roll number.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking north at approximate Sta. 20+90

**Description:**

ESI placing geomembrane panels. Material placed around collection manhole (Sta. 21+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/23/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Installed geomembrane cap with GDL visible at far western end.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/24/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 75/90° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1700 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #7**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #18 (P-18) installed on 7/23/15 (located at approximate Sta. 20+25) running approximately 90 ft. east to Sta. 19+00. Note: Soil subgrade approved to approximate Sta. 19+90 on 7/23/15. Geomembrane cap only installed to approximate Sta. 20+25 by ESI (additional 35 ft. of approved subgrade in addition to 90 ft. approved on 7/24/15).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/23/15 (Panels 14-18). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/24/15 for results (extrusion testing identified as EXT. on form).
- A total of seventeen repairs (RP-15 through RP-31) were observed and fixed (according to the project specifications) from Panel #9 through Panel #18 (repair / detailing work conducted on panels installed from 7/22/15 and 7/23/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Some additional repairs (including “custom fit” cuts to conform the geomembrane) required, however, these repairs will be completed on Monday (7/27) to allow ESI to continue to place geomembrane to the east.
- One extrusion weld destruct sample (DSX-1) was collected from Panel #13 (located on RP-17). Extrusion weld destruct samples collected every 500 lf. of welding (as outlined in project specs).
- One non-conformance issue was observed, outside of the repairs noted above (refer to *Notice of Non-Compliance and Corrective Action* forms), and was documented on Sheet #4 as non-compliance. This issue was also recorded within the Repair Log as a subgrade irregularity and was noted and repaired (RP-30) following the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was conducting cap detailing for the geomembrane cap placed on 7/22/15 and 7/23/15, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 90 ft. section of work area (approximate Sta. 19+90 to Sta. 19+00). Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/24/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #8 & 9 of the daily photo log for 7/24/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 19+90 to Sta. 19+00 as outlined above.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 20+25 (east of P-18) moving east (for approximately 135 ft. total [35 ft. remaining from 7/23/15 + 90 ft. approved on 7/24]). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Along the slopes and elevation changes, additional fasteners were placed along the geonet to provide additional support within these sloped areas. Additionally the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to 7/24/15 Photo Log for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #18 (located at approximate Sta. 20+25) on 7/23/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 20+25 to Sta. 19+00. A total of six panel lengths were installed (P-19, P-20, P-21, P-22, P-23, P-24) by ESI.
- Two destructive test samples (DS-4 & DS-5) were collected from the Panel 14/15 and 17/18 seam, within the 500 ft. linear foot requirement outlined in the project specifications. The results of the trial welding tests for the destructive samples are outlined in the *Preweld Test Report* for 7/24/15. A total of ten 1-inch specimens were collected for peel and shear strength testing (5 tests for each) for each sample.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/24), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted non-destructive testing on Panels 19-24 (as outlined in the project specifications). No patch / repair work on the installed panels was conducted. Patches associated with Panels 19-24 will be completed with extrusion welds and vacuum box testing on Monday (7/27/15). Additionally, some additional patchwork for the panels installed on 7/23/15 will also be completed, as outlined above.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 4 (Sheet #4) – Subgrade irregularity identified as RP-30 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #17). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 4 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/24/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/23/15 forms.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Review laboratory test results for destruct samples DS-4 and DS-5 (fusion) and DSX-1 (extrusion). Note: QA sample (DSX-1) also collected by Langan.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/23/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Destructive Sample Summary,* and *Certificate of Subgrade Acceptance* forms. Submittal of additional forms from 7/23/15 and review of Seam Control Form, required prior to acceptance.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-3. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 19+00 to Sta. 18+00).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/24/15 |
| A3 – Photo Log | Pages 1 – 9 | Total of 18 photos outlining pertinent daily observations and descriptions for 7/24/15 |
| A4 – Geosynthetic Inventory Log | Sheet 1 | Completed to date |
| A5 – Subgrade Approval | Sheet 5 & ESI (7/24/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/24/15. |
| A7 – Panel Placement Log | Page 5 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/24/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A8 – Destruct Seam Testing COC | Sheet 1 | One Destruct Seam Testing COC for samples collected to date. |
| A9 – Seam/Non-Destruct. Test Log | Pages 4-5 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/24/15. |
| A10 – Repair Log | Pages 1-2 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/24/15 |
| A11 – Conformance COC | | N / A for 7/24/15 |
| A12 – Destructive Seam Field Test | Sheet 1 | Destructive Seam Field Test log completed by ESI and confirmed by Langan for samples on 7/24/15 |
| A13 – Destruct. Sample Summary | Page 1 | Destructive Sample Summary completed by ESI and confirmed by Langan on 7/24/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | Sheet 4 | Notice of Non-Compliance forms completed by Langan and confirmed by ESI/Entact for 7/24/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/24/15

**Direction Taken:**

Looking north/northwest at RP-17

**Description:**

ESI conducting patch / repair work to geomembrane. Areas of cap cut to allow geomembrane "custom fit" around slopes and contours.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking along geomembrane cap and extrusion welding RP-15.

**Description:**

ESI conducting extrusion welding on patches and repairs. Extrusion weld areas to be tested with vacuum box (as outlined in project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking along geomembrane cap at DS-3 area

**Description:**

ESI preparing to conduct extrusion welding on geomembrane patch repair. Repair placed along seam where destruct sample DS-3 was collected.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2415

**Direction Taken:**

Looking along geomembrane liner

**Description:**

ESI conducting vacuum box testing (as outlined in project specs)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/24/15

**Direction Taken:**

Looking south along geomembrane cap at DS-4 location.

**Description:**

ESI collecting destruct sample (DS-4) on northern slope of SA-6 as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/24/15

**Direction Taken:**

Looking south/southeast along collection manhole (approx. Sta. 21+00)

**Description:**

ESI conducting grinding and extrusion welding around patches /repairs to “custom fit” geomembrane cap around contours.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Inside ESI work trailer

**Description:**

Tensiometer (machine number: 2003) used to conduct destruct / trial weld sampling for fusion and extrusion welds (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Prepared soil subgrade from approximate Sta. 19+90 to Sta. 19+00. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking south at approximate Sta. 19+80

**Description:**

Soil subgrade prepared for soil placement (approved from approximate Sta. 19+90 to Sta. 19+00) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking west along geomembrane cap at Sta. 21+00

**Description:**

ESI conducting geomembrane repair work around collection manhole (following project specs). Temporary boot installed around collection manhole to seal cap for weekend. Permanent / final boot to be installed at a later date.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking east / southeast along southern end of SA-6

**Description:**

ESI placing 16 oz. geotextile along southern boundary of SA-6 (over sheet pile wall) with 2 ft. of overlap outside (width of roll overlapped onto SA-6), as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking north along SA-6 at approximate Sta. 20+25.

**Description:**

ESI placing rolls of GVL along approved soil subgrade.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/24/15

**Direction Taken:**

Looking south along SA-6 cap (approximate Sta. 20+25)

**Description:**

ESI placing white plastic fasteners (maximum of 5 ft. spacing) along geonet for adjacent GVL panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking south along SA-6

**Description:**

Additional plastic fasteners installed along slopes for GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/24/15

**Direction Taken:**

Looking south along SA-6 (installed Panel #19)

**Description:**

ESI placing 60-mil geomembrane cap, Panel #19 (P-19) placed and labeled with corresponding roll number.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (07/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/24/15

**Direction Taken:**

Looking south / southwest along SA-6 cap

**Description:**

ESI conducting fusion welding between geomembrane P-19 and P-20 as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #17 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking north along installed geomembrane cap

**Description:**

Sand bags used to weight down geomembrane cap. Additional sandbags placed along slopes and elevation changes.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #18 (07/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/24/15

**Direction Taken:**

Looking east along SA-6 for installed geomembrane cap (to approx. Sta. 19+00)

**Description:**

Installed geomembrane panels to approximate Sta. 19+00.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/27/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 80/90° F, Hazy, Light Rain |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #8**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #24 (P-24) installed on 7/24/15 (located at approximate Sta. 19+00) running approximately 100 ft. east to Sta. 18+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying GDL along the western end of the cap. GDL was placed to approximate Sta. 21+00 (near collection manhole) which included the placement of 9 rolls (14 different panels) of GDL from P-9 (geomembrane installed on 7/21/15) to P-14 (geomembrane installed up to 7/23/15). Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and sewing of the geotextile completed for adjacent geocomposite panels.
- While ESI was and installing GDL along the western end of SA-6, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 80 ft. section of work area (approximate Sta. 19+00 to Sta. 18+20). Based on visual inspection of the soil, two areas were identified that did not meet the subgrade requirements.
    - The drainage swale located along Sta. 19+00 at Break Point 675-18.54 collected rainwater from storms on 7/26/15. As such the area was soft / wet and did not meet the subgrade requirements. The installed geomembrane and GVL (from 7/24/15) was pulled back and this area was left open to dry. Refer to Photo #2 of 7/27/15 Photo Log.
    - An additional location was identified to the southern end of the SA-6 cap near approximate Bound Point 655-15.58. The 16 oz. geotextile was pulled back from this area and the soil subgrade was allowed to dry. Refer to Photo 3 of 7/27/15 Photo Log.
- Based on the information outlined above, no soil subgrade was approved for GVL and geocomposite placement, as the soil did not conform with the project specifications. As such, no soil subgrade approval forms were completed for 7/27/15.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- With no subgrade approval for additional panel placement (no panel layout forms completed for 7/27/15), ESI conducted patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/23/15 and 7/24/15 (Panels 19-24). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/27/15 for results (extrusion testing identified as EXT. on form).
- A total of twenty-one repairs (RP-31 through RP-51) were observed and fixed (according to the project specifications) from Panels #18 through Panel #24 (repair / detailing work conducted on panels installed from 7/23/15 and 7/24/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. Note: No non-compliance issues were observed as patch / repair work conducted consisted primarily of custom fit repairs to allow geomembrane to conform to SA-6 contours.
- A total of three non-destructive samples were collected for lab testing (as outlined in the project specs). Two fusion weld samples DS-6 (panel seams 20/21) and DS-7 (Panel seams 23/24), along with one extrusion weld sample DSX-2 (south end of SA-6 on P-15) were collected within the 500 linear foot specification requirements.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no new geomembrane panels were placed and the repairs associated with 7/27/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Trail Weld Log, Seam Control, and Repair Report identified on 7/21/15 and 7/22/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Review laboratory test results for destruct samples DS-6 and DS-7 (fusion) and sample DSX-2 (extrusion).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-5 (fusion) and destruct sample DSX-1 (extrusion). Note: QA sample (DSX-1) also reviewed and in compliance with project specs. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 19+00 to Sta. 18+00) to ensure soil subgrade complies with project specs.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/27/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/27/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 7/27/15 |
| A6 – Trial Weld Log | Page 1 | One trial weld log provided by ESI and confirmed by Langan for pre and destruct welds completed up to 7/27/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 7/27/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with samples from 7/27/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 7/27/15 |
| A10 – Repair Log | Pages 2-3 | One repair report provided by ESI and confirmed by Langan for repairs conducted on 7/27/15. |
| A11 – Conformance COC | | N / A for 7/27/15 |
| A12 – Destructive Seam Field Test | Page 1 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 7/27/15. |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with sample information from 7/27/15 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | | No non-compliance issues identified as no new panels were installed |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/27/15

**Direction Taken:**

Looking south along SA-6 near Sta. 21+25.

**Description:**

ESI placing GDL along panels previously installed on 7/22/15 & 7/23/15 (GDL placed up to Panel #14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking northwest along Break Point 675-15.84.

**Description:**

GVL & Geomembrane cap pulled back to expose wet / soft area encountered from rain on 7/26/15. Area opened to dry prior to placing GVL and Geomembrane.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Additional wet / soft area identified along southern end of SA-6 (approximate Bound Point 655-15.58) Geotextile & GVL pulled back to allow area to dry prior to placing additional material.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/2715

**Direction Taken:**

Looking north / northeast along SA-6 (by geomembrane P-14).

**Description:**

ESI deploying GDL up to Panel #14 (P-14).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking northwest – collection manhole in background (Sta.21+00)

**Description:**

ESI conducting vacuum box testing on RP-31 after completion of extrusion welding.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking along SA-6 cap at RP-26

**Description:**

ESI conducting vacuum box testing on RP-26 ( as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESi cutting destructive test DSX-2 for extrusion weld completed alongRP-32 (identified as RP-34 and located along southern edge of SA-6 cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking south along SA-6

**Description:**

Patch / repair work conducted on southern slope of SA-6. Repairs extrusion welded and vacuum box tested (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking west along SA-6 (panel 20/21 seam)

**Description:**

ESI collecting destruct sample along Panel 20/21 seam (DS-6).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/27/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/27/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

ESI collecting destruct along Panel 23/24 seam (DS-7).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking east along SA-6 cap (panel 23/24 seam)

**Description:**

ESI patching area for DS-7.DS-7 was patched, welded, and vacuum box tested (as outlined in project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/27/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/27/15

**Direction Taken:**

Looking southwest along SA-6 cap

**Description:**

ESI completing the day with patch / repair work on “custom fit” patches around xx.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/28/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 78/92° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #9**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #24 (P-24) installed on 7/24/15 (located at approximate Sta. 19+00) running approximately 80 ft. east to Sta. 18+20. Note: No geomembrane placed on 7/27/15, as soil subgrade was not approved for two wet / soft areas identified at approx. Sta. 19+00 (further described in 7/27/15 report).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI finishing patch / repair work (cap detailing) and vacuum box testing for the geomembrane cap that was installed on 7/24/15 (Panels 19-24). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/28/15 for results (extrusion testing identified as EXT. on form).
- A total of thirty-six repairs (RP-52 through RP-87) were observed and fixed (according to the project specifications) from Panel #19 through Panel #24 (repair / detailing work conducted on panels installed on 7/24/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/24/15, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 100 ft. section of work area (approximate Sta. 19+00 to Sta. 18+00). The previously identified wet / soft areas along Sta. 19+00 were dried, graded, and compacted according to the project specs. Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/28/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3,4,5 of the daily photo log for 7/28/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

The soil subgrade inspection sheet was submitted for the approximate area of Sta. 19+00 to Sta. 17+80 (west of utility corridor).

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 19+00 (east of P-24) moving east (for approximately 80 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *7/28/15 Photo Log* for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #24 (located at approximate Sta. 19+00) on 7/24/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 19+00 to Sta. 18+20. An additional approximately 40 ft. section of subgrade was approved from approximate Sta. 18+20 to Sta. 17+80 to allow ESI to place an additional two panels to the east. A total of six panel lengths were installed (P-25, P-26, P-27, P-28, P-29, P-30) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/28), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted non-destructive testing on Panels 25-30 (as outlined in the project specifications). Additionally, one extrusion weld sample (DSX-3) was collected (as per project specifications) from RP-82 and sent to the approved laboratory for analysis. No patch / repair work on the installed panels was conducted. Patches associated with Panels 25-30 will be completed with extrusion welds and vacuum box testing on Wednesday (7/29/15). Additionally, two destruct samples for the fusion welding will be collected (as required by the project specs) on 7/29/15.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 7/28/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/28/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Repair Report identified on 7/27/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Review laboratory test results for destruct sample DSX-3 (extrusion).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15, 7/24/15, and 7/27/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-7 (fusion) and destruct sample DSX-1 through DSX-2 (extrusion). Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 17+80 to Sta. 17+00) through utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/24/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 7/28/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/28/15 |
| A5 – Subgrade Approval | Sheet 6 & ESI (7/28/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheets 1, 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/28/15. |
| A7 – Panel Placement Log | Page 6 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/28/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 7/28 |
| A9 – Seam/Non-Destruct. Test Log | Sheets 5,6,7 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/28/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A10 – Repair Log | Sheets 2,3,4,5 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/28/15 |
| A11 – Conformance COC | | N / A for 7/28/15 |
| A12 – Destructive Seam Field Test | Sheet 1 | Updated with information from destruct sample on 7/28 |
| A13 – Destruct. Sample Summary | Sheet 1 | Destruct Sample Summary provided by ESI and confirmed by Langan for sample DSX-3 |
| A14 – Penetration & Edge Form | | N / A to be completed once clamps for pipe boots are installed. |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted as repair / patching in compliance with project specs. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along Panel #19 (P-19)

**Description:**

Completed repair / patch work (from7/27) along P-19. Repairs RP-46, RP-47, RP-48, and RP-49.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along Panel Seam 17/18

**Description:**

Completed repair / patch work along Panel 17/18 seam. Repair RP-31 shown.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking northwest along drainage swale near Break Point 675-15.84

**Description:**

Soil subgrade around drainage swale dried, graded, and compacted (according to specs). Area previously identified as soft/wet on 7/27/15. Based on visual observation area approved for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/2815

**Direction Taken:**

Looking east along southern end of SA-6 cap.

**Description:**

Soil subgrade approved from approximate Sta. 19+00 to Sta.18+20.Area graded, compacted, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along Y-channel located at approximate Break Point 684-16.04

**Description:**

Soil subgrade approved for geomembrane placement. Soil graded, compacted, and free of debris (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking north along approx. Sta. 19+00

**Description:**

ESI placing geocomposite. White plastic fasteners placed at a maximum of 5ft., and geotextile sewn (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/28/15

**Direction Taken:**

Looking north at approximate Sta. 19+00

**Description:**

ESi sewing GVL geotextile for adjacent geocompoiste panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking south at approximate Sta. 19+00

**Description:**

ESI deploying geomembrane cap over GVL. Panel #25 (P-25) being placed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking south along Panel 24/25 seam (approximate Sta. 19+00)

**Description:**

ESI conducting fusion welding along Panel 24 (installed on 7/24) and Panel 25 (installed on 7/28).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (07/28/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/28/15

**Direction Taken:**

Looking south along Panel #25 (P-25)

**Description:**

Panel #25 (P-25) placed and labeled with corresponding roll number shown.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking south at approximate Sta. 18+00

**Description:**

GVL installed to approximate Sta. 17+80



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (07/28/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/28/15

**Direction Taken:**

Looking northeast along SA-6 cap

**Description:**

Installed geomembrane cap to approx. 17+80



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/29/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 77/92° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1715 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #10**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #30 (P-30) installed on 7/28/15 (located at approximate Sta. 17+80) running approximately 80 ft. east to Sta. 17+00 (up to 1st utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI finishing patch / repair work (cap detailing) and vacuum box testing for the geomembrane cap that was installed on 7/28/15 (Panels 25-30). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/29/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-two repairs (RP-88 through RP-129) were observed and fixed (according to the project specifications) from Panel #25 through Panel #30 (repair / detailing work conducted on panels installed on 7/28/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Additionally, pipe boots were completed (with seals and clamps) for PZ-20, 073-MW-1BR, 115-W3-SO, and GV-7, however, the final butyl seal around the top of the boot is required prior to completion of the *Pipe Boot and Penetration Logs.*
- While ESI was conducting cap detailing for the geomembrane cap placed on 7/28/15, Entact removed the plastic sheeting protecting the soil subgrade for the next approximate 80 ft. section of work area (approximate Sta. 17+80 to Sta. 17+00). Prior to soil approval, the area was spot checked for survey elevations and was approved as acceptable and within the grading requirements. Final soil subgrade inspection was conducted for this area by Langan and Entact (refer to *Soil Subgrade Approval* forms from 7/29/15). Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Refer to Photos #5 and 8 of the daily photo log for 7/29/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 17+80 to Sta. 17+00 (up to 1st utility corridor).

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 17+80 (east of P-30) moving east (for approximately 80 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *7/29/15 Photo Log* for supporting photographs.
- After installation of GVL, geomembrane cap was installed continuing east of previously installed Panel #30 (located at approximate Sta. 17+80) on 7/28/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were installed from approximate Sta. 17+80 to Sta. 17+00. A total of four panel lengths were installed (P-31, P-32, P-33, P-34) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (7/29), *Trial Weld Log.*
- Upon installation and welding of the geomembrane panels, ESI conducted non-destructive testing on Panels 31-34 (as outlined in the project specifications). Additionally, three non-destruct samples were collected (DS-8, DS-9, and DSX-4). DS-8 was collected from Panel 26/27, DS-9 from Panel 29/30, and DSX-4 (extrusion weld) was collected from Panel #27 (RP-102).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 7/29/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/29/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Confirm revisions for Repair Report and Seam Control identified on 7/28/15.
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 1 piezometer, and 1 gas vent).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Review laboratory test results for destruct sample DS-8 and DS-9 (fusion), along with DSX-4 (extrusion).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15, 7/24/15, and 7/27/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance* forms.
- Completed Langan Daily Report, Photo Log, and Soil Subgrade Approval Form for 7/28/15. Revisions for Repair Report and Seam Control Form required prior to sign-off.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-7 (fusion) and destruct sample DSX-1 through DSX-3 (extrusion). Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 17+80 to Sta. 17+00) through utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/29/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 7/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 7/29/15 |
| A5 – Subgrade Approval | Sheet 7 & ESI (7/29/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 7/29/15. |
| A7 – Panel Placement Log | Page 7 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 7/29/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 7/28 |
| A9 – Seam/Non-Destruct. Test Log | Sheets 5,6,7 | Non-destruct test log provided by ESI and confirmed by Langan for geomembrane placed on 7/28/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A10 – Repair Log | Sheets 5,6,7 | Repair Log provided by ESI and confirmed by Langan for repairs conducted on 7/29/15 |
| A11 – Conformance COC | | N / A for 7/28/15 |
| A12 – Destructive Seam Field Test | Sheet 1, 2 | Updated with information from destruct sample on 7/28 |
| A13 – Destruct. Sample Summary | Sheet 1 | Destruct Sample Summary provided by ESI and updated for sample DSX-3 |
| A14 – Penetration & Edge Form | | N / A additional review of QA form required prior to completion |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 7/29 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking north along Panel 20/21 seam

**Description:**

Completed patch / repair work (from 7/28). RP-71 and RP-73



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/29/15

**Direction Taken:**

Looking at geomembrane at Panel 26/27

**Description:**

ESI collecting destruct sample (DS-8) along Panel 26/27 seam, located at northern slope of SA-6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along western end of SA-6

**Description:**

Final boot installed along well 073-MW-1BR, with supporting gasket and double clamps.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along western end of cap (PZ-20)

**Description:**

Geomembrane boot installed around PZ-20. Secured with gasket and double clamps.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking north along SA-6 (previously installed liner)

**Description:**

Prepared soil subgrade approved for liner placement. Based on visual observations, soil is graded, compacted, and free of loose debris, as defined by the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along SA-6 cap (eastern end of Panel 27)

**Description:**

ESI conducting vacuum box test on repair / patch extrusion weld (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/29/15

**Direction Taken:**

Looking north along SA-6 at approximate Sta. 17+80

**Description:**

ESI deploying GVL along approximate Sta. 17+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/29/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Entact placing sand / bentonite plug at southern end of utility corridor (approximate Sta. 16+20).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking south along approximate Sta. 17+80

**Description:**

ESI deploying geomembrane at approximate Sta. 17+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking west along SA-6 cap (from Panel #31).

**Description:**

ESI conducting fusion welding along Panel 30/31 seam as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking south / southeast along southern end of SA-6 cap (P-32)

**Description:**

PZ-18 stickup located on southern and western end of SA-6 (on Panel #32). PZ-18 to be booted and sealed (as outlined in project specs) on 7/30/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (07/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/29/15

**Direction Taken:**

Looking northeast along SA-6 cap

**Description:**

Installed geomembrane panels (P-31 & P-32). ESI conducting fusion welding (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 7/30/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 76/85° F, Overcast, PM T-Storms |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1500 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #11**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL), and geocomposite clay liner (GVL), continuing from western end of SA-6 South. Material to be placed from Panel #34 (P-34) installed on 7/29/15 (located at approximate Sta. 17+00) through 1st utility corridor located at approximate Sta. 16+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work (cap detailing) for the geomembrane cap that was installed on 7/29/15 (Panels 31-34). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 7/30/15 for results (extrusion testing identified as EXT. on form).
- A total of fifteen repairs (RP-130 through RP-144) were observed and fixed (according to the project specifications) from Panels #31 through Panel #34 (repair / detailing work conducted on panels installed from 7/29/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), and also to remove wrinkles observed around changes in elevation. These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- As outlined above, no non-conformance issues were observed during repair/patch work conducted on 7/30/15, as repairs were associated with conforming the geomembrane to the SA-6 contours.
- Based on the expected weather forecast of early afternoon thunderstorms, it was determined that no GCL would be placed within the utility corridor. As such, no soil subgrade was approved for GCL placement and no panel placement forms were completed.
- ESI instead deployed GDL along the western end of the cap. GDL was placed to approximate Sta. 20+00 which included the placement of 12 rolls (rolls from north to south of SA-6; 17 different panel numbers with butt seams) of GDL from P-14 to P-21. GDL Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and sewing of the geotextile completed for adjacent geocomposite panels (with orange fabric obtained from extra roll of GDL).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- In addition to GDL placement, Entact began to build an access ramp toward the western end of the SA-6 cap to bring in protective cover soil for placement over GDL. Prior to ramp construction, approved caution tape (as outlined in the project specs was placed at a maximum 55-inch distance on top of the GDL prior to protective cover soil being spread.
- A total of one non-destructive sample (DS-10) was collected for lab testing (as outlined in the project specs). DS-10 was comprised of a fusion weld sample from Panels 32/33.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 7/30/15 consisted of custom fit design or wrinkle removal to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/30/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 1 gas vent).
- Review laboratory destruct samples (peel and shear) for DS-10 and DSX-4

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-9, and DSX-1 through DSX-3. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work for the next 100 ft. run east (approximately from Sta. 17+00 to Sta. 16+00) through the 1st utility corridor.
- Begin placement of GCL along 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/30/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/30/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 7/30/15 |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for pre and destruct welds completed up to 7/30/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 7/30/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample from 7/30/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 7/30/15 |
| A10 – Repair Log | Page 7 | One repair report provided by ESI and confirmed by Langan for repairs conducted on 7/30/15. |
| A11 – Conformance COC | | N / A for 7/30/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 7/30/15. |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with sample information from 7/30/15 |
| A14 – Penetration & Edge Form | | N / A to be completed for PZ-18 once final clamps and gaskets are installed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed on 7/30/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/30/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/30/15

**Direction Taken:**

Looking southeast along southern end of cap

**Description:**

ESI conducting booting activities for PZ-18 (located on P-32).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/30/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/30/15

**Direction Taken:**

Looking west along installed geomembrane cap (taken from approx. Sta. 17+50)

**Description:**

Installed geomembrane cap to date.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3(07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/30/15

**Direction Taken:**

Looking southwest along geomembrane cap

**Description:**

ESI conducting patch / repair work for panels installed on 7/29/15 (Panels 31-34).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
7/30/15

**Direction Taken:**

Looking southeast along SA=6 cap.

**Description:**

ESI conducting vacuum box testing (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/30/15

**Direction Taken:**

Looking north along SA-6

**Description:**

ESi deploying GDL over previously installed geomembrane cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/30/15

**Direction Taken:**

Looking west along SA-6 cap from approx. Sta. 17+50

**Description:**

Installed GDL up to approx. Sta. 21+00 (collection manhole).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/30/15

**Direction Taken:**

Looking west along northern slope of SA-6

**Description:**

Entact beginning to build ramp and access-way for soil placement over GDL. Warning tape placed at approx. 55-inch intervals over GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (07/30/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/30/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Ramp built up to SA-6 for placement of cover soil over installed GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 7/31/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 73/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0600 – 1700 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #12**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from Panel #21 (P-21) to approximate Panel #33 (P-33). Based on the PM thunderstorms from 7/30/15, soil subgrade through the utility corridor could not be approved due to soft / wet areas identified. As such, ESI prepped to deploy GDL over the installed geomembrane areas.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI filling sand bags for GVL / geomembrane placement.
- While ESI was filling sandbags, Langan, AmecFW, and Entact conducted a review of the as-built panel layout to confirm repairs and associated panel locations. Once this information was confirmed, ESI began to deploy GDL over the installed geomembrane.
- ESI deployed GDL along the western end of the cap. GDL was placed from approximate Sta. 20+00 (approx. P-21 location) to approx. Sta. 17+00 (approx. P-33 location) which included the placement of 21 rolls (rolls from north to south of SA-6; 28 different panel numbers with butt seams) of GDL from P-21 to P-33. GDL Panels were placed according to the project specifications with white plastic fasteners placed at a maximum of 5 ft. and sewing of the geotextile completed for adjacent geocomposite panels (with orange fabric obtained from extra roll of GDL).
- No geomembrane patch / repair work was conducted as part of the 7/31/15 daily activities. Similarly, no new panels were installed as soil subgrade was not approved.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed for work activities completed on 7/31/15. No geomembrane panels installed, and no patch / repair work or sampling was conducted.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 7/31/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 1 gas vent).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Additional subgrade preparation work to remove soft / wet areas for the next 100 ft. run east (approximately from Sta. 17+00 to Sta. 16+00) through the 1st utility corridor.
- Begin placement of GCL along 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 7/31/15 |
| A3 – Photo Log | Pages 1 – 2 | Total of 4 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 7/31/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 7/31/15 |
| A6 – Trial Weld Log | | N / A – no trial welds conducted for 7/31/15 activities |
| A7 – Panel Placement Log | | N / A no panels placed on 7/30/15 |
| A8 – Destruct Seam Testing COC | | N / A no non-destruct samples collected on 7/31/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 7/31/15 |
| A10 – Repair Log | | N / A no repair report for 7/31/15 activities |
| A11 – Conformance COC | | N / A for 7/31/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 7/31/15 |
| A13 – Destruct. Sample Summary | | N / A no updates from 7/31/15 |
| A14 – Penetration & Edge Form | | N / A to be completed for PZ-18 once final clamps and gaskets are installed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed on 7/31/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (07/31/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
7/31/15

**Direction Taken:**

Looking north along 1st utility corridor (located at approx. Sta. 16+50

**Description:**

Utility corridor with wet / soft areas identified due to heavy rains. Soil subgrade not approved for GCL placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (07/31/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
7/31/15

**Direction Taken:**

Looking south along geomembrane cap (near approx. Sta. 19+90)

**Description:**

ESI deploying GCL over previously installed geomembrane panels near Sta. 19+90 (over Panels 21 & 22).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/31/15

**Direction Taken:**

Looking west along SA-6 (installed GDL)from approximate Sta. 17+20

**Description:**

Installed GDL up to approximate Sta. 17+20 along SA-6 (from western end).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (07/31/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
7/31/15

**Direction Taken:**

Looking west along northern end of SA-6 (at approx.. Sta. 18+00.

**Description:**

Installed GDL to date



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/3/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 73/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1945 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #13**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #34 (P-34) installed on 7/29/15 (located at approximate Sta. 17+00) running through first utility corridor approximately 120 ft. east to Sta. 15+80 (to eastern end of 1st utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing an additional two panels of GDL (moving east from Panel #33) to cover up to geomembrane Panel #34 (P-34). While GDL was being placed, Langan and Entact conducted soil subgrade approval from approximate Sta. 17+00 to Sta. 15+80 (through 1st utility corridor). Refer to *Soil Subgrade Approval* forms from 8/3/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1,2, and 3 of the daily photo log for 8/3/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 17+00 to Sta. 15+80 (to eastern side of 1st utility corridor).
- Geocomposite clay liner (GCL), GVL and Cap placement began with ESI placing the GCL along the bottom and slopes of the utility corridor (shown in the *8/3/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite. Note: Prior to GCL placement, a soil transition slope (approx. 2 ft. by 2 ft. was constructed along the northern slope of the utility corridor to allow the GCL to transition over the slope without having to conform to the 90 deg. turns of the SCB wall). This soil slope modification was approved prior to construction.
- In addition to the GCL (placed within the utility corridor), 16 oz. geotextile was placed along the boundaries of the SA-6 South Cap (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/3/15 Photo Log* for supporting photographs.

- After installation of GCL and GVL through the utility corridor, geomembrane cap was installed continuing east of previously installed Panel #34 (located at approximate Sta. 17+00) on 7/29/15. Panels were oriented from east to west through the utility corridor (as proposed in the approved Panel Layout) and were installed through the utility corridor (located at approx. Sta. 16+50) running from the top of the western slope to the top of the eastern slope. Additional panels were installed outside of the utility corridor and were T (butt seamed) into the east-west panels from inside the utility corridor (the panels outside of the utility corridor reverted back to the north-south orientation as indicated on the approved panel layout). A total of twelve panel lengths (different dimensions and sizes) were installed (P-35, P-36, P-37, P-38, P-39, P-40, P-41, P-42, P-43, P-44, P-45, and P-46) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/3), *Trial Weld Log.*
- Installation and welding of the geomembrane panels was conducted until approximately 8 pm to ensure that the utility corridor was properly covered and sealed due to expected overnight storms. As such, no non-destructive testing on the installed panels was conducted. Additionally, no patch / repair work was completed, and no destructive samples were collected. These activities will be completed tomorrow (8/4/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no patch / repair work was conducted on geomembrane cap.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/3/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 15+80 to Sta. 14+80) east of utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/3/15 |
| A3 – Photo Log | Pages 1 – 8 | Total of 16 photos outlining pertinent daily observations and descriptions for 7/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/3/15 |
| A5 – Subgrade Approval | Sheet 8 & ESI (8/3/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Sheet 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/3/15. |
| A7 – Panel Placement Log | Pages 8 & 9 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/3/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/3/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 8/3/15 |
| A10 – Repair Log | | N / A no repairs conducted on 8/3/15 |
| A11 – Conformance COC | | N / A for 8/3/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 8/3/15 |
| A13 – Destruct. Sample Summary | | N / A no updates to form (no samples collected on 8/3) |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/3/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking north along 1st utility corridor (located at approx. Sta. 16+50

**Description:**

Utility corridor subgrade dried, graded, and compacted after storm. Area approved for geomembrane placement (as per project specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking west along northern end of SA-6

**Description:**

ESI constructing approx. 2 ft. by 2 ft. soil slope up to SCB wall. Approved change from having GCL and geomembrane with 90 deg. bends along SCB wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south along 1st utility corridor (approx. Sta. 16+50)

**Description:**

Approved soil subgrade for cap placement. Soil graded, compacted, and free of debris (>1/2"), as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south / southwest along utility corridor (approx. Sta. 16+50)

**Description:**

ESI installing GCL along bottom of utility corridor (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/03/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/3/15

**Direction Taken:**

Looking south along bottom of utility corridor

**Description:**

ESi overlapping GCL panels (minimum of 1 ft.) as outlined in project specs. Bentonite used to seal seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/03/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/3/15

**Direction Taken:**

Looking north along bottom of utility corridor

**Description:**

ESI placing granular bentonite along GCL seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking west along utility corridor (approx. Sta. 16+50)

**Description:**

ESI installing GCL along slopes of corridor to minimum elevation (approx. El. 14) as outlined in the project specifications. GCL overlapped a minimum of 1 ft. along seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking southwest along utility corridor.

**Description:**

GCL installed along base and western wall of utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south along western slope of utility corridor

**Description:**

GCL overlapped a minimum of 2 ft. over the top of the corridor slope. GCL secured with 6-inch staples along top of panel.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south along eastern end of utility corridor.

**Description:**

GVL panel installed over top of GCL (minimum of 1 ft. overlap) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking south down along utility corridor

**Description:**

GCL installed throughout utility corridor. ESI prepping to cover GCL with geomembrane cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at utility corridor)

**Description:**

ESI placing geomembrane panels along southern end of utility corridor. Panels oriented in east to west direction (perpendicular to slope), as outlined in approved panel layout.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/3/15

**Direction Taken:**

Looking west / northwest at northern end of utility corridor.

**Description:**

ESI conducting fusion welding of Panels 35/36 located at northern end of utility corridor (oriented east to west).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking north along 1st utility corridor (located at approx. Sta. 16+50)

**Description:**

Geomembrane panels placed over GCL along utility corridor. Panels oriented perpendicular to slope (east to west).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #15 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/3/15

**Direction Taken:**

Looking east along northern end of SA-6

**Description:**

ESI placing geomembrane panel along southern end of GCL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #16 (08/03/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/3/15

**Direction Taken:**

Looking south along utility corridor

**Description:**

Geomembrane panels installed along utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/4/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 70/85° F, AM Rain, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0600 – 1630 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #14**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from east of Panel #42 installed on 8/3/15 (located at approx. Sta. 15+80) moving east approximately 100 ft. to approximate Sta. 14+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Based on the AM storms / rain, ESI could not conduct patch / repair work (i.e. extrusion welding) on the geomembrane panels installed on 8/3/15 due to the inclement weather. Observation of the next section of soil subgrade (approx. Sta. 15+80 to 14+80) was conducted and soft / wet areas were identified with ponding water (due to the storms). As such, soil subgrade was not approved for additional panel placement. Refer to *8/4/15 Photo Log* for subgrade photos. ESI offsite until 12 PM for weather to clear.
- Entact removed the protective plastic layer covering the soil subgrade and conducted drying activities, re-grading, and re-compaction of the soil (as required).
- ESI back onsite at approximately 12 PM to conduct patch / repair work for the panels installed on 8/3/15 (Panels 35-46). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 8/4/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-one repairs (RP-145 through RP-185) were observed and fixed (according to the project specifications) from Panel #35 through Panel #46 (repair / detailing work conducted on panels installed on 8/3/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- No non-conformance issues were noted as repairs consisted of custom fit design or routine patch / repair work to allow geomembrane to conform to SA-6 contours.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of two destruct samples, DS-11 and DS-12 (fusion weld samples) were collected for laboratory analysis. DS-11 was collected from panel seam 36/37 and DS-12 was collected from panel seam 42/43

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance items observed. Repairs associated with 8/4/15 consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/4/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).
- Review laboratory results for DS-11 and DS-12

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15 as well as reviewed and approved ESI *Daily Panel Placement*, *Preweld Test Report*, and *Certificate of Subgrade Acceptance, etc.* forms.
- Reviewed laboratory destruct sample results for samples DS-1 through DS-10, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Additional subgrade preparation work to remove soft / wet areas for the next 80 ft. run east (approximately from Sta. 15+80 to Sta. 15+00) of 1st utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/4/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions |
| A4 – Geosynthetic Inventory Log | | N / A – no updates for 8/4/15 |
| A5 – Subgrade Approval | | N / A – no subgrade approval for 8/4/15 |
| A6 – Trial Weld Log | Page 2 | Preweld test form for 8/4/15 provided by ESI and confirmed by Langan for prewelds up to 8/4/15 |
| A7 – Panel Placement Log | | N / A no panels placed on 8/4/15 |
| A8 – Destruct Seam Testing COC | Sheet 1 | Updated with destruct sample information from 8/4/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 7,8,9,10,11 | Seam Control Form for 8/4/15 provided by ESI and confirmed by Langan for non-destruct tests completed up to 8/4/15 |
| A10 – Repair Log | Pages 7,8,9 | Repair Log for 8/4/15 provided by ESI and confirmed by Langan for repairs completed up to 8/4/15 |
| A11 – Conformance COC | | N / A for 8/4/15 |
| A12 – Destructive Seam Field Test | Sheet 2 | Destruct Sample Information provided by ESI and confirmed by Langan for destruct samples collected on 8/4/15 (DS-11 and DS-12) |
| A13 – Destruct. Sample Summary | Sheet 2 | Updated with destruct sample information from 8/4/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues observed |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/4/15

**Direction Taken:**

Looking south along SA-6 (at approx. Sta. 15+80)

**Description:**

Soil subgrade immediately east of previously installed panels (from 8/3) at approx. Sta. 15+80. Wet / soft areas identified and area not suitable for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/4/15

**Direction Taken:**

Looking west along SA-6 (at approx. Sta. 15+80) at drainage swale / corridor located at Grid Point 165-15.01

**Description:**

Water ponding from rain storm from 8/3. Soil subgrade not acceptable for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3(08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking down along SA-6 utility corridor (southwestern slope) near Break Point 832-4.44

**Description:**

ESI conducting patch repair work along installed panels from 8/3 (Panels 35-46)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking east along SA-6 cap

**Description:**

ESI conducting vacuum box testing along patch / repair work from Panels 35-46.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking along the northwestern slope of utility corridor (looking at approximate Break Point 823-16.40)

**Description:**

Patch / repair work along northwestern slope of utility corridor (RP-151 & RP-157).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/4/15

**Direction Taken:**

Looking north / northwest along utility corridor (looking at northwest slope).

**Description:**

ESI conducting patch / repair work along utility corridor. Also conducting extrusion welding and vacuum box testing (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking west along southern slope of SA-6 (near Break Point 842-4.57)

**Description:**

ESI collecting destruct sample (DS-12) along Panel 42/43 seam.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking west / northwest along SA=6 cap.

**Description:**

ESI labeling and marking repairs upon completion of vacuum box testing.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/4/15

**Direction Taken:**

Looking east along SA-6 cap

**Description:**

ESI conducting extrusion weld along patches / repairs (as outlined in project specs).



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/5/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 70/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0600 – 1700 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #15**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #42 (P-42) installed on 8/3/15 (located at approximate Sta. 15+80) running approximately 70 ft. east to Sta. 15+10.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work for three wrinkles (refer to *Repair Log* 8/5/15) that were identified along Panels 35-46 which were placed on 8/3/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/5/15).
- A total of nine repairs (RP-186 through RP-194) were observed and fixed (according to the project specifications) from Panel #35 and Panel #36. As outlined above, these repairs were associated with removing geomembrane wrinkles to allow the cap to conform to the contours of SA-6 South grade. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications. Note: no repairs of the geomembrane from 8/5/15 were identified as non-compliance issues.
- Additionally, while the geomembrane was being patched / repaired, ESI also installed the penetration boots for the wells, piezometers, and gas vents protruding through the cap (Note: Penetration logs will be completed once final sealant is placed around top of boot). Orange composite (GDL) was also placed over butt seams of the geocomposite and leistered in place. These patching activities were completed (as needed) to allow Entact to continue placing protective cover soil over the installed GDL along the western end of SA6. The final GDL layer was inspected by Entact and Langan to ensure that all repairs / patches were completed prior to soil placement.
- While patch / repair work was being conducted, Langan and Entact conducted soil subgrade approval from approximate Sta. 15+80 to Sta. 15+10. Refer to *Soil Subgrade Approval* forms from 8/5/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

that the surface was free of any loose material. Refer to Photos #5,6 of the daily photo log for 8/5/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 15+80 to Sta. 15+10.

- Cap placement began with ESI placing the GCL along the southern slope (lower bench along southern end of SA-6 located below the groundwater table) of the southern edge of SA-6 (refer to *8/5/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- In addition to the GCL (placed along the southern slope), 16 oz. geotextile was placed along the northern boundary of the SA-6 South Cap, and also along the southern boundary east of the GCL (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.
- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/5/15 Photo Log* for supporting photographs.
- After installation of GCL and GVL along the SA-6 boundaries, geomembrane cap was installed continuing east of previously installed Panel #42 (located at approximate Sta. 15+80) on 8/3/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GCL layers. A total of three panel lengths were installed (P-47, P-48, P-49) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/5), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. As such, no non-destructive testing on the installed panels was conducted. Additionally, no patch / repair work was completed, and no destructive samples were collected. These activities will be completed tomorrow (8/6/15). Note: An extrusion weld sample (DSX-5) was collected from the patch / repair work previously completed on 8/4/15.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as repair work was conducted to remove wrinkles from the cap to allow the geomembrane to properly conform to the contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/5/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).
- Review laboratory data for extrusion destruct sample DSX-5

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, and 8/4/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-4. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 15+10 to Sta. 14+10) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/5/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 8/5/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/5/15 |
| A5 – Subgrade Approval | Sheet 9 & ESI (8/5/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 2 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/5/15. |
| A7 – Panel Placement Log | Page 10 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/5/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with information from destruct sample (DSX-5) collected on 8/5/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destruct tests conducted on 8/5/15 |
| A10 – Repair Log | Pages 9-10 | One Repair Log provided by ESI and confirmed by Langan for 8/5/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/5/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destruct sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/5/15 |
| A13 – Destruct. Sample Summary | Sheet 1 | Updated with destruct sample information from 8/5/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/5/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/5/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI finalizing GDL cap by covering and patching butt seams and associated repairs (as required).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking southwest along SA-6 cap (at GV-6 location)

**Description:**

ESI constructing boot and placing sacrificial sheet around GV-6 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3(08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking north at northeastern slope of utility corridor (located at approx. Grid Point 149-5.59

**Description:**

ESI conducting patch repair work for wrinkles identified from geomembrane panel placement (from 8/3/15).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking south along southern edge of SA-6 cap (located at PZ-18)

**Description:**

Installed geomembrane boot around PZ-18 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking west (from approx. Sta. 15+80) at approximate Grid Point 165-15.01

**Description:**

Soil subgrade at approximate Grid Point 165-15.01. Soil has been dried, re-graded, and re-compacted for panel placement. Soil subgrade prepared in accordance with project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south at southern end of SA-6 cap (taken from approximate Sta. 15+80)

**Description:**

Previously identified soft / wet area from 8/4/15. Soil allowed to dry and was re-compacted (as required). Soil acceptable for geomembrane placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Entact spreading protective cover soil along previously installed GDL (located at western end of cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south along southern end of SA-6 (approximate Sta. 15+80)

**Description:**

ESI placing GCL along lower elevations (to 1 ft. above the groundwater table). Panels placed moving east from Sta. 15+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking north at tops of installed GCL panels

**Description:**

Support staples (with rounded heads) placed along the top of the GCL panels for support (as outlined in project specs). Staples to be overlapped with 1 ft. minimum of GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/05/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/5/15

**Direction Taken:**

Looking north along SA-6 (immediately east of approx. Sta. 15+80).

**Description:**

ESI deploying GVL immediately east of approx. Sta. 15+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking north along SA-6 at Collection Manhole #2

**Description:**

ESI deploying geomembrane panels over installed GVL east of Sta. 15+80.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/05/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/5/15

**Direction Taken:**

Looking south along Panel #47 (P-47)

**Description:**

ESI conducting fusion welding along Panel seam 42/47 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/6/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/88° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1600 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #16**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #49 (P-49) installed on 8/5/15 (located at approximate Sta. 15+10) running approximately 110 ft. east to Sta. 14+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL over the previously installed geomembrane panels from 8/3/15. A total of 10 panel lengths of GDL were placed along the west side of the utility corridor and along the western slope of the utility corridor with end points of the GDL terminating along the approximate center of the utility corridor (east to west orientation). The GDL was placed north to south outside of the corridor and east to west within the corridor and secured with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile was sewn (according to the project specs).
- While GDL was being placed over the previously installed geomembrane, Langan and Entact conducted soil subgrade approval from approximate Sta. 15+10 to Sta. 14+00. Refer to *Soil Subgrade Approval* forms from 8/6/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #7,8, and 9 of the daily photo log for 8/6/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 15+10 to Sta. 14+00.
- Cap placement began with ESI placing the GCL along the southern slope (lower bench along southern end of SA-6 located below the groundwater table) of the southern edge of SA-6 (refer to *8/6/15 Photo Log*) as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with granular bentonite.
- Prior to deploying any geomembrane panels over the GCL, it was confirmed that the GCL maintained intimate contact between the material and the HB wall (southern boundary wall). Soil was removed from the top of the sheet piles (as required) by Entact. Refer to Photo #14 of the *Photo Log 8/6/15*.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- In addition to the GCL (placed along the southern slope), 16 oz. geotextile was placed along the northern boundary of the SA-6 South Cap, and also along the southern boundary east of the GCL (located at the areas above the groundwater table and outside of the GCL) over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications.
- GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/6/15 Photo Log* for supporting photographs.
- After installation of GCL, 16 oz. geotextile (along SA-6 boundaries) and GVL, geomembrane cap was installed continuing east of previously installed Panel #49 (located at approximate Sta. 15+10) on 8/5/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of four panel lengths (lengths defined as running the approximate 165 ft. north to south distance of the cap) were installed (P-50, P-51, P-52, P-53, P-54) by ESI. Note: P-51 terminated approximately 6 ft. short of the southern boundary of the SA-6 cap. As such, the remaining section was taken from an additional roll (G15C277060) and labeled as Panel #52 (P-52).
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/6), *Trial Weld Log.*
- Upon panel installation and fusion welding, ESI conducted non-destructive seam testing in accordance with the project specs. No patch / repair work was completed, and no destructive samples were collected as work activities were completed after non-destruct testing was completed. These additional activities will be completed tomorrow (8/7/15).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as non-destruct testing was in conformance with the project specs and no patch / repair work, or vacuum box testing was conducted on 8/6/15.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/6/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Log (once boot and associated sealing activities are completed for manhole located at Sta. 21+00).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 2 piezometers, and 3 gas vents).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, and 8/5/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-5. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 14+00 to Sta. 13+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/6/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 8/6/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/6/15 |
| A5 – Subgrade Approval | Sheet 10 & ESI (8/6/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Pages 2-3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/6/15. |
| A7 – Panel Placement Log | Page 11 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/6/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/6/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 11-12 | Seam Control Form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/6/15 |
| A10 – Repair Log | | N / A no repairs completed on 8/6/15 |
| A11 – Conformance COC | | N / A for 8/6/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 8/6/15 |
| A13 – Destruct. Sample Summary | | N / A no updates as no destruct samples collected |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/6/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/6/15

**Direction Taken:**

Looking north through utility corridor (at western slope of utility corridor)

**Description:**

ESI preparing to deploy GDL along utility corridor (over previously installed panels 35-46)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/6/15

**Direction Taken:**

Looking south along SA-6 (approximate Sta. 17+00)

**Description:**

ESI placing GDL over installed geomembrane panels (P-34 & P-35). White plastic fasteners spaced at maximum of 5 ft. intervals and geotextile seam sewn (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking south / southeast at bottom of southeast utility corridor slope (located at approx. Break Point 831-4.62

**Description:**

ESI placing GDL along southeastern slope of utility corridor. Panels oriented east to west to run parallel with slope (as outlined in the approved panel layout).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/6/15

**Direction Taken:**

Looking northwest along western slope of utility corridor (approx. Sta. 16+50).

**Description:**

Installed GDL along utility corridor (western slope).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking north along southern slope of SA-6 (southern edge of SA-6).

**Description:**

ESI placing GCL along southern edge of SA-6 slope (east of Sta. 15+10). Pins / staples placed along top 6-inches of GCL to anchor into subgrade slope.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking south / southwest along southern slope of SA-6 (approximate Sta. 14+70).

**Description:**

ESI placing GCL along southern slope (lower bench) of SA-6. GCL placed at areas below (up to 1 ft. above) the Site water table.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking east along SA-6 (from approx. Sta. 15+10).

**Description:**

Soil subgrade along the southern end of SA-6 approved for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

Approved soil subgrade for geomembrane placement. Soil prepared as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/6/15

**Direction Taken:**

Looking south / southwest along SA-6 (at approximate Sta. 15+10)

**Description:**

Prepared soil subgrade according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/06/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
8/6/15

**Direction Taken:**

Looking north along SA-6 (east of approx. Sta. 15+10).

**Description:**

ESI deploying GVL. White plastic fasteners spaced at a minimum of 5 ft., and the top layer of geotextile sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking north along western end of SA-6 cap

**Description:**

Entact covering GDL along western end of cap with protective cover soil. Caution tape spaced at a maximum of 55-inches over GDL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking northwest along SA-6 cap (from approx. Sta. 14+00)

**Description:**

ESI placing geomembrane over GVL layer from approx. Sta. 15+10 to approx. Sta. 14+00



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking northwest along SA-6 cap (from approx. Sta. 14+30)

**Description:**

ESI conducting fusion welding along installed panel seams (Panels 50-54)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (08/06/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/6/15

**Direction Taken:**

Looking east along southern wall of SA-6 cap (approx. Sta. 14+70)

**Description:**

Entact pulling back GCL to ensure that HB wall (southern boundary wall) maintains intimate contact with GCL.



# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 8/7/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 68/82° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0600 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #17**<br>**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #54 (P-54) installed on 8/6/15 (located at approximate Sta. 14+00) running approximately 100 ft. east to Sta. 13+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 50-54 which were placed on 8/6/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/7/15).
- A total of twenty-three repairs (RP-195 through RP-217) were observed and fixed (according to the project specifications) from Panels #50 through Panel #54 (repair / detailing work conducted on panels installed on 8/6/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-conformance issue was observed for a failed vacuum box test during testing of RP-215. The failed weld was patched and re-welded as outlined on Sheet #5.
- A total of three destruct samples were collected (DS-13, DS-14, and DSX-6). DS-13 and DS-14 (fusion) were collected from Panels 47/48 and 50/51, respectively. DSX-6 (extrusion) was collected from Panel #48 on RP-198.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for Collection Manhole #2. Note: The penetration log for Collection Manhole #2 will be completed once the boot has been sealed and covered according to the project specifications (to be completed on 8/10/15), and the final sealant is placed around top of boot.
- Langan and Entact conducted soil subgrade approval from approximate Sta. 14+00 to Sta. 13+00 while

patch work was being completed by ESI. Refer to *Soil Subgrade Approval* forms from 8/7/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material.Refer to Photo #6 of the daily photo log for 8/7/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 14+00 to Sta. 13+00.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 14+00 (east of P-54) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/7/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #54 (located at approximate Sta. 14+00) on 8/6/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-55, P-56, P-57, P-58, P-59, P-60) by ESI. Note:, during placement of Panel #55 and #59, the roll of geomembrane was completed, thus, Panel #56 was placed for the last 11 ft. (from roll G15C283029) to complete the southern end and Panel #60 (P-60) was placed for the last 15 ft. (from roll G15C276053) to complete the northern end of SA-6.
- During installation of the Cap, geomembrane seams were overlapped a minimum of 4-inches for fusion welding (according to project specs). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specs. A total of six 1-inch specimens were collected for peel and shear testing (3 samples/each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/7), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. Once completed, non-destructive testing on the installed panels was conducted. Non-destruct testing was conducted in accordance with the project specs and is further summarized on the *Seam Control Form (8/7/15).* After non-destructive testing the work day was terminated and no patch / repair work was completed. These activities will be completed on Monday (8/10/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 5 (Sheet #5) – Failed vacuum box test of RP-215 on *Repair Log*
    - Failed vacuum box test of RP-215 (Panel #50). Failed weld was covered with a new patch and welded (RP-222) as per project specs and further defined in *Sheet 5 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/7/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 14+35).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-13, DS-14 and DSX-6

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, and 8/6/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-12, and DSX-1 through DSX-5. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 13+00 to Sta. 12+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/7/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/7/15 |
| A5 – Subgrade Approval | Sheet 11 & ESI (8/7/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/7/15. |
| A7 – Panel Placement Log | Page 12 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/7/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 8/7/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 12-14 | One Seam Control form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/7/15 |
| A10 – Repair Log | Pages 10-11 | One Repair Log provided by ESI and confirmed by Langan for 8/7/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/7/15 |
| A12 – Destructive Seam Field Test | Page 2 | Provided for destruct samples DS-13, DS-14, and DSX-6 collected for 8/7/15 |
| A13 – Destruct. Sample Summary | Sheet 2 | Updated with destruct samples collected on 8/7/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 5 | One Notice of Non-Compliance form created by Langan (Sheet #5) for failed vacuum box test |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/7/15

**Direction Taken:**

Looking south along SA-6 cap (RP-216)

**Description:**

ESI conducting vacuum box testing (according to project specs) on seam joint located on southern edge of SA-6 (Panels 50,51,52)




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | 100530001 |

**Date:**
8/7/15

**Direction Taken:**

Looking south along SA-6 at Panels 50/51

**Description:**

ESI collecting destruct sample (DS-14) along fusion welded seam (Panels 50/51). Sample collected near northern edge of SA-6



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking south near approx. Sta. 15+70 (at Access Manhole #2)

**Description:**

ESI placing LLDPE boot (RP-218) around Access Manhole #2 (located at approximate Sta. 15+70).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking north along SA-6 cap (western end)

**Description:**

Entact spreading protective cover soil along western end of SA-6. Yellow caution tape placed at maximum of 55-inch spacing (as outlined in project specs)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking at geomembrane cap (RP-215) located at Panel #50

**Description:**

Failed vacuum box test at RP-215. Leak detected during vacuum box testing of extrusion weld. Failed weld to be patched / repaired as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking east along SA-6 (from approximate Sta. 14+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking south along SA-6 (approx. Sta. 13+70)

**Description:**

ESI deploying GVL (approx. Sta. 13+70). White plastic fasteners spaced at maximum of 5 ft. (as outlined in project specs) and top geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/7/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 13+75)

**Description:**

ESI deploying geomembrane over GVL. (at approx. Sta. 13+75)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/7/15

**Direction Taken:**

Looking southeast along SA-6 (Panels 57/58)

**Description:**

ESI conducting fusion welding along Panel 57/58 seam (welding conducted according to project specs)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (08/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/7/15

**Direction Taken:**

Looking west along southern end of SA-6 (approximate Sta. 13+20)

**Description:**

ESI conducting fusion welding along Panels 58/59,down southern slope of SA-6



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/10/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/78° F, Overcast |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1645 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #18**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #60 (P-60) installed on 8/7/15 (located at approximate Sta. 13+00) running approximately 100 ft. east to Sta. 12+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 55-60 which were placed on 8/7/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/10/15).
- A total of thirty-one repairs (RP-218 through RP-248) were observed and fixed (according to the project specifications) from Panels #55 through Panel #60 (repair / detailing work conducted on panels installed on 8/7/15). Refer to 8/10/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for well 115-W5-SO, and completed placing the geomembrane patch around Access Manhole #2. Note: The penetration log for well 115-W5-SO will be completed once the boot has been sealed and covered according to the project specifications and the final sealant is placed around top of boot.
- Langan and Entact conducted soil subgrade approval from approximate Sta. 13+00 to Sta. 12+00 while patch work was being completed by ESI. Refer to *Soil Subgrade Approval* forms from 8/10/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #5 and #6 of the daily photo log for 8/10/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 13+00 to Sta. 12+00.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 13+00 (east of P-60) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/10/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #60 (located at approximate Sta. 13+00) on 8/7/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-61, P-62, P-63, P-64, and P-65) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/10), *Trial Weld Log.*
- Installation and fusion welding of the geomembrane panels was conducted until the end of the work day. Once completed, non-destructive testing on the installed panels was conducted. Non-destruct testing was conducted in accordance with the project specs and is further summarized on the *Seam Control Form (8/10/15).* After non-destructive testing the work day was terminated and no patch / repair work was completed.
- A total of three destructive samples were collected (two fusion and one extrusion weld). Fusion weld destruct samples (DS-15, DS-16) were collected from Panel Seams 54/55 and 59/61 respectively. DSX-7 was collected along Panel 53/54 seam. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/10/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-15, DS-16, DS-17, and DSX-7

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, and 8/7/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-14, and DSX-1 through DSX-6. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 12+00 to Sta. 11+00) continuing east along SA-6.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/10/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 14 photos outlining pertinent daily observations and descriptions for 8/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/10/15 |
| A5 – Subgrade Approval | Sheet 12 & ESI (8/10/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/10/15. |
| A7 – Panel Placement Log | Page 13 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/10/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct samples collected on 8/10/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 14 | One Seam Control form provided by ESI and confirmed by Langan for non-destruct tests completed on 8/10/15 |
| A10 – Repair Log | Pages 11-12 | One Repair Log provided by ESI and confirmed by Langan for 8/10/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 8/10/15 |
| A12 – Destructive Seam Field Test | Page 2 | One destruct sample information form provided by ESI and confirmed by Langan for 8/10/15 |
| A13 – Destruct. Sample Summary | Sheet 2 | Updated with destruct sample information from 8/10/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues noted on 8/10/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking south / southwest along geomembrane cap at Access Manhole #2 (approx. Sta. 15+70)

**Description:**

ESI installing geomembrane boot and patching cap around Access Manhole #2 (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI conducting patch / repair work for "custom fit" patches around slopes & contours. Patch work conducted as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking west along SA-6 cap (at RP-215)

**Description:**

ESI conducting vacuum box testing (as outlined in project specs) on patch (RP-222) placed over RP-215 to repair failed extrusion weld.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking north / northeast SA-6 (at RP-223)

**Description:**

ESI conducting extrusion welding along northern end of SA-6 at RP-223 (where DS-14 collected)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking north along SA-6 (from approx. Sta. 13+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (from approx. Sta. 13+00)

**Description:**

Prepared soil subgrade for geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking west along SA-6 cap (at RP-215)

**Description:**

Failed vacuum box test (RP-215), patched and repaired (RP-222) according to project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (from approx. Sta. 13+00)

**Description:**

ESI deploying 16 oz. geotextile along southern boundary of SA-6. Textile overlapping HB wall by 2 ft. with remaining roll width inside SA-6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking north along SA-6 (from approx. Sta. 13+00)

**Description:**

ESI deploying GVL along approved soil subgrade.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking south along SA-6 (from approx. Sta. 12+50)

**Description:**

White plastic fasteners spaced at a maximum of 5 ft. along geonet with top layer of geotextile sewn (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/10/15

**Direction Taken:**

Looking north / northeast along SA-6 (at approximate Sta. 13+00)

**Description:**

ESi deploying geomembrane over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking west along geomembrane (at Panels 60/61)

**Description:**

ESI conducting fusion welding along Panel Seam 60/61.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/10/15

**Direction Taken:**

Looking north along geomembrane cap (at Panels 62/63)

**Description:**

Patch / repair placed over destruct sample (DS-17) located at approximate center of SA-6 on Panels 62/63 seam.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #14 (08/10/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/10/15

**Direction Taken:**

Looking south along geomembrane cap (at well 115-W5-S0)

**Description:**

ESI placing gasket and sealing GVL for placement of geomembrane boot around well 115-W5-SO.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/12/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 71/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #19**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-65) installed on 8/10/15 (located at approximate Sta. 12+00) running approximately 100 ft. east to Sta. 11+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work along the panels previously installed Panels 61-66 which were placed on 8/10/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (8/12/15).
- A total of four repairs (RP-249 through RP-252) were observed and fixed (according to the project specifications) from Panels #64 through Panel #66 (repair / detailing work conducted on panels installed on 8/10/15). Refer to 8/12/15 *Repair Report* for supporting information. The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed / construction penetration boots for well 115-W5-SO and gas vent #5 (GV-5). Note: These penetration logs will be completed once the final clamps and seal (butyl seal) have been completed according to the project specifications and the final sealant is placed around top of boot.
- While ESI was conducting repair / patch work, Langan and Entact conducted soil subgrade observation from approximate Sta. 12+00 to Sta. 11+00. Based on visual inspection, the soil subgrade appeared to contain areas of soft / wet subgrade due to rainstorms from 8/11/15. Based on these soft areas, soil subgrade was not approved for geomembrane placement. Entact conducted additional preparation work (i.e. drying the soil and re-grading and re-compacting) as required, to conform the subgrade to the project specifications (refer to Photo #7 of the daily photo log for 8/12/15)

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After completing patch / repair work from the panels installed on 8/10/15, ESI began to place GDL continuing east along the utility corridor. GDL was placed along the eastern slope of the utility corridor (located at approximate Sta. 16+50). Panels were oriented east to west within the utility corridor, and reverted back to the north and south orientation outside of the corridor (refer to the *8/12/15 Photo Log* for supporting photos)
- GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/12/15 Photo Log* for supporting photographs.
- No new geomembrane panels were placed as the soil subgrade for the next 100 ft. section was not approved. No destruct samples were collected, as DS-17 was collected on 8/10/15 during panel placement.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 5 ft. spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues recorded as no new geomembrane panels were placed and the patch / repair work conducted on geomembrane cap was in compliance with the project specifications.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/12/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, and 8/10/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 100 ft. run east (approximately from Sta. 12+00 to Sta. 11+00) east of utility corridor.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/12/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 8/12/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/12/15 |
| A5 – Subgrade Approval | | N / A no subgrade approved due to soft / wet conditions observed from storms on 8/11/15 |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/12/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 8/12/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/12/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 14-15 | Updated with vacuum box test conducted from 8/12/15 on Panels 64/66 |
| A10 – Repair Log | Page 12 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 8/12/15 |
| A11 – Conformance COC | | N / A for 8/12/15 |
| A12 – Destructive Seam Field Test | | N / A no destructive samples collected on 8/12/15 |
| A13 – Destruct. Sample Summary | | N / A no destructive samples collected on 8/12/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/12/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking west along SA-6 cap (from approximate Sta. 19+00)

**Description:**

Entact spreading protective cover soil along western end of SA-6 (over previously installed geomembrane and GDL panels). Caution tape placed on top of GDL at maximum of 55-inch intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking west along northern end of SA-6 cap (at well 115-W5-SO)

**Description:**

ESI constructing geomembrane boot around monitoring well 115-W5-SO



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3(08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking east along northern end of SA-6 cap

**Description:**

ESI conducting extrusion welding (as per project specifications) along geomembrane boot (RP-246)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/12/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

ESI conducting vacuum box testing along monitoring well boot (extrusion weld) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking north / northwest along SA-6 cap (at approximate Sta. 16+00)

**Description:**

ESi welding geomembrane boot over gas vent (GV-5) as outlined in project specs (located at approx. Sta. 16+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking north along SA-6 cap (at approx. Sta. 16+00)

**Description:**

ESi conducting vacuum box testing along extrusion welds for geomembrane boot GV-5.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/12/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta. 12+00)

**Description:**

Entact conducting soil preparation activities for geomembrane placement on 8/13/15. Subgrade exhibitied soft / wet areas in the morning from rain storms on 8/11/15. Soil allowed to dry and re-graded and re-compacted (as required).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/12/15

**Direction Taken:**

Looking east along southern end of SA-6 through 1st utility corridor (approximate Sta. 16+50)

**Description:**

ESI deploying GDL along eastern end of 1st utility corridor (at approx. Sta. 16+50)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #9 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking east along SA-6 (through 1st utility corridor)

**Description:**

ESI deploying GDL along eastern slope of utility corridor (approximate Sta. 16+50) working from the south end to the north end of the corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #10 (08/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/12/15

**Direction Taken:**

Looking west along SA-6 cap (at approximate Sta. 16+00)

**Description:**

ESI placing clamps over geomembrane boot for SV-5 (sacrificial sheet placed prior to clamping as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/13/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 70/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #20**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-65) installed on 8/10/15 (located at approximate Sta. 12+00) running approximately 100 ft. east to Sta. 11+00.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 12+00 to Sta. 11+00. Refer to *Soil Subgrade Approval* forms from 8/13/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 8/13/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 12+00 to Sta. 11+00. Note: The soft / wet areas identified on 8/12/15 were allowed to dry and were repaired for geomembrane placement.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 12+00 (east of P-65) moving east (for approximately 100 ft.). GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/13/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #65 (located at approximate Sta. 12+00) on 8/10/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth
**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

installed (P-67, P-68, P-69, P-70, and P-71) by ESI.

- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/13), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 11+00, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (8/13/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, no patch / repair work was conducted, and any associated repairs will be completed on 8/14/15.
- After completing non-destructive testing along the panels installed today (8/13/15), ESI began to place GDL continuing east from the 1st utility corridor (located at approx. Sta. 16+50). Panels were oriented from north to south (as outlined in the proposed GDL layout). GDL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/13/15 Photo Log* for supporting photographs.
- A total of two destructive samples were collected (two fusion welds). Fusion weld destruct samples (DS-18, DS-19) were collected from Panel Seams 64/65 and 68/69, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 55-inch spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17, DS-18, and DS-19 (once received)

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, and 8/12/15 as well as reviewed and approved daily ESI form submittals.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for the next approximate 80 ft. run east (approximately from Sta. 11+00 to Sta. 10+20) to Access Manhole #3 (ESI demobilization point).
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/13/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/13/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/13/15 |
| A5 – Subgrade Approval | Sheet 13 & ESI (8/13/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/13/15. |
| A7 – Panel Placement Log | Page 14 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/13/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/13/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 15-16 | Updated with vacuum box test conducted from 8/13/15 on Panels 67 through 71 |
| A10 – Repair Log | | N / A no repairs completed on 8/13/15 |
| A11 – Conformance COC | | N / A for 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/13/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/13/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/13/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking south / southwest along SA-6 (from approximate Sta. 11+50)

**Description:**

Prepared soil subgrade for next approximate 100 ft. of geomembrane (from approximate Sta. 12+00 to Sta. 11+00). Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking south / southeast along SA-6 (at approximate Sta. 11+50)

**Description:**

Soil subgrade prepped for geomembrane placement. Soil graded, compacted, and free of loose debris (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 12+00)

**Description:**

ESI placing GVL along approved soil subgrade. White plastic fasteners spaced at maximum of 5 ft. intervals and top geotextile sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/13/15

**Direction Taken:**

Looking south along SA-6 cap (approximate Sta. 12+00)

**Description:**

ESI sewing top layer of geotextile along GVL (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 12+00)

**Description:**

ESi placing geomembrane cap over GVL (at approx. Sta. 12+00)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking northwest along SA-6 cap (Panels 65/67)

**Description:**

ESi conducting fusion welding along Panel 65/67 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking west along geomembrane cap at DS-19 (RP-254)

**Description:**

Geomembrane patch leistered over DS-19 (RP-254). Patch to be completed on 8/14/15 with extrusion weld and vacuum box testing (as outlined in project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/13/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/13/15

**Direction Taken:**

Looking northwest along SA-6 cap

**Description:**

ESI deploying GDL along western end of cap (located at approximate Sta. 15+00).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 8/14/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 78/95° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0600 – 1430 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #21**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad, Brian Shea, Philemon Onyango
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing from western end of SA-6 South. Material to be placed from Panel #65 (P-71) installed on 8/13/15 (located at approximate Sta. 11+00) running approximately 80 ft. east to Sta. 10+20 (western slope of 2nd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 11+00 to Sta. 10+20. Refer to *Soil Subgrade Approval* forms from 8/14/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 11+00 to Sta. 10+20.
- Geocomposite clay liner (GCL), GVL and Cap placement began with ESI placing the GCL along the southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- In addition to the GCL (placed along the southern slope below the groundwater table), 16 oz. geotextile was placed along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 11+00 (east of P-71) moving east (for approximately 80 ft.) to Sta. 10+20. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *8/14/15 Photo Log* for supporting photographs.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #71 (located at approximate Sta. 11+00) on 8/13/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-72, P-73, P-74, and P-75) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (8/14), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 10+20, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (8/14/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. ESI conducted patch / repair work for the panels installed on 8/13/15 (Panels 66-71) and 8/14/15 (Panels 72-75). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 8/14/15 for results (extrusion testing identified as EXT. on form).
- A total of ten repairs (RP-253 through RP-262) were observed and fixed (according to the project specifications) from Panel #71 through Panel #75 (repair / detailing work conducted on panels installed on 8/13/15 & 8/14/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Upon completion of patch / repair activities, ESI began to pack and load equipment for their 2-week demob from the Site.
- A total of two destructive samples were collected (two fusion welds). Fusion weld destruct samples (DS-20, DS-21) were collected from Panel Seams 70/71 and 74/75, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact placed protective cover soil over the previously installed geomembrane and GDL panels at the western end of SA-6. Protective cover soil was placed in 1 ft. lifts with caution tape placed at a maximum of 55-inch spacing, placed over the GDL prior to soil placement.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 8/13/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DS-17, DS-18, DS-19, DS-20, and DS-21 (once received)

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, and 8/13/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-16, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South after 2-week demobilization is complete.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 8/14/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 8/14/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 8/14/15 |
| A5 – Subgrade Approval | Sheet 14 & ESI (8/14/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 3 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 8/14/15. |
| A7 – Panel Placement Log | Page 15 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 8/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 8/14/15 |
| A9 – Seam/Non-Destruct. Test Log | Page 15-16 | Updated with vacuum box test conducted from 8/13/15 on Panels 67 through 71 and 8/14/15 on Panels 71 through 75 |
| A10 – Repair Log | Page 13 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 8/14/15 |
| A11 – Conformance COC | | N / A for 8/14/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 8/14/15 |
| A13 – Destruct. Sample Summary | Page 1 | Updated with 8/14/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 8/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking west along southern end of SA-6 (from approximate Sta. 11+00)

**Description:**

ESI placing GCL along southern slope of SA-6 (soil below to 1 ft. above the water table). Stakes / staples placed on top of slope (top 6-inches of GCL to hold GCL in-place).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Installed GCL panels along southern slope with anchor supports (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking north along SA-6 (from approximate Sta. 10+50)

**Description:**

GVL placed be ESI according to project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
8/14/15

**Direction Taken:**

Looking north along SA-6 cap (from approximate Sta. 10+80

**Description:**

Geomembrane panels placed over GDL and fusion welded (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

ESi conducting fusion welding for Panels 71/72 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (08/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 cap (at Panel 74/75 seam)

**Description:**

ESi collecting destruct sample (DS-21) at Panel 74/75 seam (fusion weld).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking south along southern end of SA-6 cap (along lower bench)

**Description:**

Geomembrane panels 74 and 75 installed and labeled along southern end of cap.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (08/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
8/14/15

**Direction Taken:**

Looking along SA-6 camp (Panel 74/75) seam at DS-21

**Description:**

Destruct sample (DS-21) patched and extrusion welded as per project specs. Noted as Repair RP-261 on Repair Log.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/9/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 75/86° F, Clear AM, Clouds & Rain PM |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1830 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #22**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad, Brian Shea<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), and 60-mil geomembrane liner (Cap) continuing from western end of SA-6 South. Material to be placed from Panel #75 (P-75) installed on 8/14/15 (located at approximate Sta. 10+20 – western slope of utility corridor) running approximately 70 ft. east through 2nd utility corridor to approximate Sta. 9+50 (eastern slope of 2nd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 10+20 to Sta. 9+50. Refer to *Soil Subgrade Approval* forms from 9/9/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 10+20 to Sta. 9+50.
- While subgrade approval was being conducted, ESI completed patch / repair work for cap wrinkles that were observed from panel placement on 8/14/15. A total of thirty repairs (RP-263 through RP-292) were observed and fixed (according to the project specifications) from Panel #71 and Panel #73 (repair / detailing work conducted on panels installed on 8/14/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), where wrinkles were observed. These areas were subsequently patched and sealed with extrusion welds. No vacuum box testing was conducted on these repairs, and will be completed tomorrow (9/10).
- No non-conformance issues were recorded as patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GCL and Cap placement began with ESI placing the GCL along the eastern and western slopes of the utility corridor and southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite.
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #75 (located at approximate Sta. 10+20) on 8/14/15 and through the 2nd utility corridor. Panels were oriented from east to west (as proposed in the approved Panel Layout) and were placed on top of the GCL layer. A total of eleven panel lengths (panel lengths identified as the approximate 80 ft. run from east to west across the corridor, as well as geomembrane pieces which were used to complete the southern end of the corridor) were installed (P-76, P-77, P-78, P-79, P-80, P-81, P-82, P-83, P-84, P-85, and P-86) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/9), *Trial Weld Log.*
- No non-destructive testing or patch / repair work was conducted upon completion of geomembrane panel placement to approximate Sta. 9+50, as panel placement and fusion welded activities concluded the work day.
- One destructive sample was collected – DSX-8 (extrusion weld). Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- Additionally, Entact completed Site preparation activities for expectation of rainstorms tomorrow (9/10).

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/9/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 3 gas vents).
- Review laboratory results for DSX-8 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, and 8/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/9/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 9/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/9/15 |
| A5 – Subgrade Approval | Sheet 15 & ESI (9/9/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/9/15. |
| A7 – Panel Placement Log | Pages 16-17 | One panel placement log provided by ESI and confirmed by Langan for geomembrane placed on 9/9/15 |
| A8 – Destruct Seam Testing COC | Page 1 | Updated with destruct sample information collected from 9/9/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no vacuum box testing conducted on 9/9/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | Pages 13-14 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/9/15 |
| A11 – Conformance COC | | N / A for 9/9/15 |
| A12 – Destructive Seam Field Test | Page 3 | One destructive sample information form provided by ESI and confirmed by Langan for destruct samples collected on 9/9/15 |
| A13 – Destruct. Sample Summary | Page 3 | Updated with 9/9/15 destruct sample information |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/9/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north / northwest along edge of GDL placed up to Panel #56 (approximate Sta. 14+20)

**Description:**

Protective cover soil placed from west end of SA-6 to approximate Sta. 14+20. Yellow caution tape spaced at maximum 55-inch intervals as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking southwest along 2nd utility corridor (located at approximate Sta. 10+00).

**Description:**

Prepared soil subgrade through 2nd utility corridor (approximate Sta. 10+00). Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north / northeast along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

Prepared soil subgrade through 2nd utility corridor. Soil graded, compacted, and free of debris as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along SA-6

**Description:**

ESI conducting patch / repair work along Panels 73/74. Wrinkles cut and geomembrane patched and repaired with extrusion weld as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approx. Sta. 10+00)

**Description:**

ESi deploying GCL along 2nd utility corridor. GCL placed north to south (along bottom of corridor) and east to west (along slopes of corridor).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along 2nd utility corridor

**Description:**

ESi placing granular bentonite along GCL seams (overlapped a minimum of 1 ft.) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along southern end of SA-6 cap through 2nd utility corridor

**Description:**

GCL panels (oriented east to west) placed along eastern slope and southern end of utility corridor. Overlapped a minimum of 1 ft. (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along northern end of SA-6 cap

**Description:**

ESI completing GCL placement along eastern slope of 2nd utility corridor (approximate Sta. 10+00)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

GCL deployed along 2nd utility corridor, as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor

**Description:**

ESI placing geomembrane cap over GCL. Panels oriented from east to west through utility corridor as outlined in the approved panel layout.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along southern end of SA-6 (through 2nd utility corridor)

**Description:**

ESi placing geomembrane cap over GCL along southern end of corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

ESI conducting fusion welding along Panel Seams 81/84



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (09/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/9/15

**Direction Taken:**

Looking north along 2nd utility corridor (approximate Sta. 10+00)

**Description:**

Geomembrane cap placed through 2nd utility corridor and seams fusion welded according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/11/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/77° F, Clear AM, Clouds & Rain PM |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #23**<br>**AmecFW**: Dave Ambrose<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from geomembrane Panel #56 (located at approximate Sta. 14+20 – location where GDL had previously been placed to along with protective cover soil) running approximately 220 ft. east to Panel #68 (approximate Sta. 12+00)..
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing for the repairs completed on 9/11/15 (as outlined in projecte specs). One vacuum box testing was complete, ESI began placing GDL from approximate Sta. 14+20 (Panel #56) to approximate Sta. 12+00 (Panel #68). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL were cut with the first wrap of geocomposite removed prior to use
    - Roll 64021010124 – 10 ft. removed
    - Roll 64021010133 – 8 ft. removed
    - Roll 64021010126 – 10 ft. removed
    - Roll 64021010116- 5 ft. removed
    - Roll 64021010112 – 10 ft. removed
        - Note: this roll was not identified during the GDL inspection, however based on damage to the protective plastic liner observed in the field, the outside layer of GDL was removed.
    - Roll 64021010119 – 10 ft. removed
- Due to the inclement weather from 9/10/15 and potential storms over the weekend, the protective plastic covering the soil subgrade to the east was not removed. As such, no soil subgrade approval was conducted and no additional geomembrane panels were placed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- One non-conformance issues was observed during placement of GDL. A rock was encountered underneath geomembrane panel #57. This non-conformance issue was recorded as RP-293 and will be patched and repaired on Monday (9/14).
- Upon completion of GDL placement to the approved panel location, a visual observation of the top of the western slope of the 2nd utility corridor was conducted by Langan and Entact. The geomembrane panels were pulled back to expose the GCL. Visual observation confirmed that the GCL was dry and no water had drained underneath the panels. The top of the slope was then sealed with a fusion weld "T-seams" along Panel #75 (oriented north to south) and Panel #76 through Panel #81 (oriented east to west).
- Geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/11), *Trial Weld Log.* Note: non-destructive testing was completed on the welded seams (to be completed Monday – 9/14/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 6 (Sheet #6) – Subgrade irregularity identified as RP-293 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #57). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 6 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/11/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 4 gas vents).
- Review laboratory results for DSX-8 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, and 8/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-7. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/11/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/11/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/11/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/11/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/11/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/11/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 9/11/15 |
| A10 – Repair Log | Pages 13-14 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/9/15 |
| A11 – Conformance COC | | N / A for 9/11/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/11/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/11/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet #6 | One non-compliance issue identified on 9/11/15 and recorded on Sheet #6 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/11/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/11/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI conducting vacuum box testing for extrusion welds for cap repairs (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/11/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/11/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 14+00)

**Description:**

ESI deploying GDL along SA-6 cap. GDL secured with white plastic fasteners (spaced at 5 ft. maximum intervals) and sewn along the top layer of geotextile (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 13+80).

**Description:**

ESI securing GDL with white plastic fasteners spaced at maximum of 5 ft. intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking west along SA-6

**Description:**

GDL placed to approximate Sta. 12+00



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

ESI placed patch over subgrade irregularity (RP-293). Details of patch are outlined in non-conformance Sheet #6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/11/15

**Direction Taken:**

Looking east along SA-6 cap (top western slope of 2nd utility corridor).

**Description:**

ESi conducting fusion welding between Panels 75 / 80 (top western slope of 2nd utility corridor) as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking north along SA-6 cap (at GV-

**Description:**

ESI constructing geomembrane boot around gas vent: GV-4 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/11/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/11/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta.

**Description:**

ESI completing geomembrane boot around GV-4.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/14/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 58/74° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #24**
**AmecFW**: Stu Bills, Geoff Shallard, Dave Ambrose
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing from western end of SA-6 South. Material to be placed from geomembrane Panel #68 (located at approximate Sta. 12+00 – location where GDL had previously been placed to - based on approved as-built drawings) running approximately 170 ft. east to Panel #74 located at top of western slope of 2nd utility corridor (approximate Sta. 10+30).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL from approximate Sta. 12+00 (Panel #68) to approximate Sta. 10+30 (Panel #75). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.
- While GDL was being placed, ESI conducted non-destructive testing (air pressure testing) of the geomembrane panel seams installed on 9/9/15 in accordance with the project specifications. Refer to *Seam Control Form* (9/14/15) for non-destructive testing details.
- Once non-destructive testing was completed, ESI completed patch / repair along the panels previously installed, Panels 76-86 which were placed on 9/9/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/14/15).
- A total of twenty-three repairs (RP-293 through RP-315) were observed and fixed (according to the project specifications) from Panels #76 through Panel #86 (repair / detailing work conducted on panels installed on 9/11/15). Refer to 9/14/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for gas vent GV-3, and completed placing the geomembrane patch around Access Manhole #3. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.
- One destructive sample (DS-22) was collected (fusion) from Panel Seams 79/80. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/14/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-22 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, and 9/11/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-21, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/14/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 9/14/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/14/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/11/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/14/15 |
| A8 – Destruct Seam Testing COC | | Updated with destruct sample information collected on 9/14/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 16-18 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/14/15 |
| A10 – Repair Log | Pages 14-16 | One repair report provided by ESI and confirmed by Langan for geomembrane repairs conducted on 9/14/15 |
| A11 – Conformance COC | | N / A for 9/14/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/14/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/14/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/14/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/14/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 11+80)

**Description:**

ESI sewing seams of GDL as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/14/15

**Direction Taken:**

Looking east along SA-6 cap (through 2nd utility corridor)

**Description:**

ESI conducting non-destructive testing as outlined in project specs. Pressure testing conducted between Panel Seams 76 / 77.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 11+20).

**Description:**

ESI securing GDL with white plastic fasteners spaced at maximum of 5 ft. intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap (approximate Sta. 10+40).

**Description:**

ESI constructing geomembrane boot around gas vent GV-3.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap (western slope of 2nd utility corridor).

**Description:**

ESI completed patch / repair over seam joint for non-destruct testing. Patch overlapped, sealed, and extrusion welded as outlined in project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/14/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Entact spreading protective cover soil over placed GDL. Warning caution tape spaced at maximum 55-inch intervals, as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Seam joint patches placed over non-destruct test seams and patched and repaired according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/14/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/14/15

**Direction Taken:**

Looking southeast along SA-6 cap (at approximate Sta. 10+20).

**Description:**

ESI installing geomembrane boot around Access Manhole #3 located along western slope of 2nd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/14/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/14/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

Completed geomembrane boot with extrusion welds and vacuum box testing completed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/15/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #25**
**AmecFW**: Geoff Shallard, Dave Ambrose, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## *Site Activities*

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), and continuing from eastern end of 2nd utility corridor. Material to be placed from Panels #76, 77, 78, 79, 80, 81, and 86 (panels running east to west through utility corridor) installed on 9/9/15 (located at approximate Sta. 9+50) running approximately 100 ft. east to Sta. 8+50. Panels installed today (9/15) will "T" into the panels outlined above as panels will revert back to north-south orientation outside of utility corridor (as per the approved panel layout).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 9+50 (eastern end of 2nd utility corridor) to Sta. 8+50. Refer to *Soil Subgrade Approval* forms from 9/15/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 9/15/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 9+50 to Sta. 8+50.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 9+50 (east of 2nd utility corridor) moving east (for approximately 100 ft.) to approximate Sta. 8+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/15/15 Photo Log* for supporting photographs.
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panels #76-81, and #86 (running east-west through 2nd utility corridor) on 9/9/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-87, P-88, P-89, and P-90) by ESI.

- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/15), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 8+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/15/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/16/15.
- One destructive sample (DS-23) was collected (fusion) from Panel Seams 88/89. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- ESI pulled back the installed geomembrane panels along the northern and southern ends of the 2nd utility corridor to expose the underlying GCL. The GCL appeared to be hydrated (approximate 10 ft. wide section along southern end of corridor and approximate 4 ft. wide section along northern end of corridor) from rainwater infiltration that washed back underneath the cap due to the soil subgrade outside of the cap which was not yet completed to grade. These sections of GCL were cut and removed and the area was left open to dry overnight. New GCL pieces will be placed (according to the project specs) on 9/16/15.
- With cap activities complete, ESI filled sandbags for the remainder of the work day.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/15/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-23 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, and 9/14/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-22, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/15/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 9/15/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/15/15 |
| A5 – Subgrade Approval | Sheet 16 & ESI (9/15/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 4 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/15/15. |
| A7 – Panel Placement Log | Page 18 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/15/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/15/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 19-20 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/15/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | N / A no repairs completed for 9/15/15 |
| A11 – Conformance COC | | N / A for 9/15/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/15/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/15/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/15/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 9+50)

**Description:**

Soil subgrade approved for GVL and geomembrane placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking east along northern end of SA-6 cap (from approximate Sta. 9+50)

**Description:**

Soil subgrade prepared for GVL and geomembrane placement as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (from approximate Sta. 9+50 to Sta. 8+50)

**Description:**

ESI placing GCL along lower bench of southern slope of SA-6 cap (areas below to 1 ft. above the water table) as outlined in the project specs. GCL overlapped a minimum of 1 ft. and sealed with bentonite along the seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking north along southern slope of SA-6

**Description:**

Stakes / staples placed along top 6-inches of GCL to secure material.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking north along SA-6 cap (eastern top of 2nd utility corridor)

**Description:**

ESI deploying GVL as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking north along SA-6 cap

**Description:**

GVL placed from approximate Sta. 9+50 to approximate Sta. 8+50.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/15/15

**Direction Taken:**

Looking southwest along SA-6 cap (at approximate Sta. 9+20).

**Description:**

ESI conducting fusion welding along geomembrane seams (P-87 & P-88) as per project specifications



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/15/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/15/15

**Direction Taken:**

Looking east along southern slope of SA-6

**Description:**

Geomembrane panels pulled back to remove approximate 10' wide piece of GCL along southern end of 2nd utility corridor. GCL removed was wet / hydrated from rainwater during storms. GCL cut and removed – to be replaced and sealed on 9/16/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/15/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/15/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 8+50).

**Description:**

GVL and geomembrane panels placed to approximate Sta. 8+50. Panels welded with non-destructive testing conducted (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/16/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 63/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #26**<br>**AmecFW**: Geoff Shallard, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), and continuing from eastern end of 2nd utility corridor. Material to be placed from Panel #90 (P-90) installed on 9/15/15 and located at approximate Sta. 8+50 running approximately 80 ft. east to Sta. 7+70.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting vacuum box testing on the repairs completed from 9/14/15 (through 2nd utility corridor). ESI also conducted patch / repair work for the panels installed on 9/15/15 (Panels 87-90). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 9/16/15 for results (extrusion testing identified as EXT. on form).
- A total of forty-four repairs (RP-316 through RP-349) were observed and fixed (according to the project specifications) from Panel #87 through Panel #90 (repair / detailing work conducted on panels installed on 9/15/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications.
- Along with the repair work, ESI also placed the new pieces of GCL (refer to Photo Log) for the northern and southern areas along the 2nd utility corridor where the GCL was hydrated. One area along the southern section required the liner to be cut to pull back and expose the GCL. As such, this repair (RP-331) was identified as a non-conformance issue (subgrade irregularity) and is further defined below.
- While patch / repair work was being completed, Langan and Entact conducting soil subgrade approval from approximate Sta. 8+50 (moving east from P-90) to Sta. 7+70. Refer to *Soil Subgrade Approval* forms from 9/16/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photo #6 of the daily photo log for 9/16/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 8+50 to Sta. 7+70.

- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 8+50 (moving east of P-90) moving east (for approximately 80 ft.) to approximate Sta. 7+70. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/16/15 Photo Log* for supporting photographs.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, the following rolls of GVL were cut with the first wrap of geocomposite removed prior to use
    - Roll 65211010130 – 8 ft. removed
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #90 on 9/15/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-91, P-92, P-93, and P-94) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/16), *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 7+70, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/16/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/17/15.
- One destructive sample (DSX-9) was collected (extrusion weld) from Panel Seams 88/89. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 7 (Sheet #7) – Subgrade irregularity identified as RP-293 on *Repair Log*
    - GCL underneath geomembrane liner along southern end of utility corridor hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final). Geomembrane liner pulled back and cut to remove and replace sections of GCL. This patch was noted as a subgrade irregularity and was patched/repaired following project specs and is further defined on *Sheet 7 Notice of Non-Compliance*

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/16/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DSX-9 (once received).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, and 9/15/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-23, and DSX-1 through DSX-8. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 2nd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/16/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/16/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/16/15 |
| A5 – Subgrade Approval | Sheet 17 & ESI (9/16/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A6 – Trial Weld Log | Pages 4-5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/16/15. |
| A7 – Panel Placement Log | Page 19 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/16/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/16/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 20-21 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/16/15 |
| A10 – Repair Log | Pages 15-17 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/16/15 |
| A11 – Conformance COC | | N / A for 9/16/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/16/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/16/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 7 | One non-compliance issues identified and further defined on Sheet 7 for 9/16/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking south along western slope of 2nd utility corridor

**Description:**

ESI conducting vacuum box testing (as per project specs) for geomembrane boot around Access Manhole #3 (RP-262).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (southern section of 2nd utility corridor)

**Description:**

ESI placing new panels of GCL for hydrated areas that were previously removed on 9/15/15. New pieces overlapped a minimum of 1 ft. and sealed with granular bentonite along the seams.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking along southern end of SA-6 cap (along GCL)

**Description:**

ESI spreading granular bentonite along GCL seams (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking south along SA-6 cap (top southwest corner of 2nd utility corridor)

**Description:**

Vacuum box testing being conducted on RP-299 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking east along northern end of SA-6 cap (northern end of 2nd utility corridor)

**Description:**

New panel of GCL placed along SCB wall (northeast corner of 2nd utility corridor). GCL removed as area was hydrated from previous storms.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (southern end of 2nd utility corridor)

**Description:**

Geomembrane panels patched and repaired after exposing and replacing pieces of GCL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/16/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/16/15

**Direction Taken:**

Looking north / northeast along SA-6 Cap (from approximate Sta. 8+50).

**Description:**

ESI deploying GVL. Approved soil subgrade to the east. Soil compacted, graded, and free of debris (>1/2") as outlined in the project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/16/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/16/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 8+50).

**Description:**

ESi conducting sewing along the top layer of GVL as outlined in the project specs. White plastic fasteners spaced at a maximum of 5 ft. along the geonet also placed prior to sewing.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 8+10).

**Description:**

White plastic fasteners spaced at a maximum of 5 ft. along GVL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/16/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 8+20)

**Description:**

ESI deploying geomembrane panels over placed GVL (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #11 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:** 9/16/15

**Direction Taken:**

Looking along SA-6 cap (Panels 90/91)

**Description:**

ESI conducting fusion welding along Panel Seams 90 / 91 (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #12 (09/16/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:** 9/16/15

**Direction Taken:**

Looking along southern end of SA-6 cap

**Description:**

ESI conducting non-destructive testing (pressure testing) along Panel Seam 90 / 91 as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/17/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 65/85° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #27**
**AmecFW**: Stu, Bills, Geoff Shallard, Dave Ambrose, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), continuing from eastern end of 2nd utility corridor. Material to be placed from Panel #94 (P-94) installed on 9/16/15 and located at approximate Sta. 7+70 running approximately 70 ft. east to Sta. 7+00 (top western slope of 3rd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair work for the panels installed on 9/16/15 (Panels 91-94). Prior to any repair work, trial welding was conducted to confirm that the extrusion welds conformed to the project specifications (refer to *Preweld Test Report* for 9/17/15 for results (extrusion testing identified as EXT. on form).
- A total of seventeen repairs (RP-350 through RP-366) were observed and fixed (according to the project specifications) from Panel #91 through Panel #94 (repair / detailing work conducted on panels installed on 9/16/15). The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs), as well as seam joint repairs where non-destructive testing was conducted along the panel seams. These areas were subsequently patched and sealed with extrusion welds, and confirmed with vacuum box testing being conducted as outlined in the project specifications. Additionally, custom fit repairs were conducted along the top eastern slope of the 2nd utility corridor (Panel #80) to remove observed wrinkles in the geomembrane panels. Vacuum box testing was then completed on the repairs (as per the project specifications) to confirm the integrity of the extrusion welds.
- Once the patch / repair work was completed ESI began placing GDL from approximate Sta. 10+30 (Panel #75) to approximate Sta. 9+60 (Panel #87). GDL was placed through the 2nd utility corridor with the panels oriented east to west, and was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While GDL placement was being conducted, Langan and Entact completed soil subgrade approval from approximate Sta. 7+70 (moving east from P-94) to Sta. 7+00 (top western slope of 3rd utility corridor). Refer to *Soil Subgrade Approval* forms from 9/17/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 7+70 to Sta. 7+00.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 7+70 (moving east of P-94) moving east (for approximately 70 ft.) to approximate Sta. 7+00. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/17/15 Photo Log* for supporting photographs.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove first wrap of geocomposite prior to use
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panel #94 on 9/16/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of three panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-95, P-96, and P-97) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/17), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 7+00, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/17/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/18/15.
- One destructive sample (DS-24) was collected (fusion weld) from Panel Seams 91/92. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/17/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 5 gas vents).
- Review laboratory results for DS-24 (once received).

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, and 9/16/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-23, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 through, and east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

## ***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/17/15 |
| A3 – Photo Log | Pages 1 – 3 | Total of 6 photos outlining pertinent daily observations and descriptions for 9/17/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/17/15 |
| A5 – Subgrade Approval | Sheet 18 & ESI (9/17/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/17/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A7 – Panel Placement Log | Page 20 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/17/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/17/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 21 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/17/15 |
| A10 – Repair Log | Pages 15-18 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/16/15 and 9/17/15 |
| A11 – Conformance COC | | N / A for 9/17/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/17/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/17/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/17/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/17/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/17/15

**Direction Taken:**

Looking west along SA-6 cap (at destruct sample location DS-24)

**Description:**

ESI completing patch / repair work for destruct sample DS-24 collected along Panel 91 / 92 seam.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/17/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/17/15

**Direction Taken:**

Looking north along SA-6 through 2nd utility corridor (approximate Sta. 10+00)

**Description:**

ESI placing GDL along 2nd utility corridor over placed geomembrane panels. One panel ran north-south through bottom of utility corridor. Remaining panels oriented east-west along slopes of corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/17/15

**Direction Taken:**

Looking south along SA-6 (through 2nd utility corridor)

**Description:**

ESI placing GDL panels along western slope of 2nd utility corridor. Panels oriented east to west and secured with white plastic fasteners and sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/17/15

**Direction Taken:**

Looking south along SA-6 cap (approximate Sta. 7+50).

**Description:**

ESI deploying GVL with white plastic fasteners spaced at maximum of 5 ft. and top layer of geotextile sewn (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/17/15

**Direction Taken:**

Looking north along SA-6 cap (approximate Sta. 7+40).

**Description:**

ESI deploying geomembrane panels over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/17/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/17/15

**Direction Taken:**

Looking south along SA-6 cap

**Description:**

Geomembrane panels placed and fusion welded (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/18/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 66/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #28**
**AmecFW**: Stu, Bills, Geoff Shallard, Dave Ambrose, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL) geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), through 3rd utility corridor (located at approximate Sta. 6+80). Material to be placed from Panel #97 (P-97) installed on 9/17/15 and located at approximate Sta. 7+00 running approximately 60 ft. east through 3rd utility corridor to Sta. 6+40 (top eastern side of 3rd utility corridor).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 7+00 (P-97 installed on 9/17/15) through the 3rd utility corridor to Sta. 6+40. Refer to *Soil Subgrade Approval* forms from 9/18/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 7+00 to Sta. 6+40.
- GCL and Cap placement began with ESI placing GVL along the eastern and western slopes of the 3rd utility corridor. GVL was placed at the areas above the groundwater table down the slopes of the corridor (GCL areas comprised the bottom of the utility corridor to approximately 2 ft. to 3 ft. up the side slopes). GVL was secured with white plastic fasteners spaced at a maximum of 5 ft. and was sewn along the top layer of geotextile (as outlined in the project specs).
- GCL was then placed along the bottom of the 3rd utility corridor, and along the eastern and western slopes of the utility corridor and southern slope of SA-6 (lower bench) located below (to 1 ft. above) the water table as shown on the project drawings and outlined in the specifications. The GCL was overlapped a minimum of 1 ft. and was sealed along the seams with a granular bentonite. The GVL overlapped the GCL a minimum of 1 ft. along the bottom slopes of the corridor, and the GCL was secured into the side slopes via soil stakes / staples.
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #97 (located at approximate Sta. 7+-00) on 9/17/15 and through the 3rd utility corridor. Panels

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

were oriented from east to west (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers.

- A total of nine panel lengths (panel lengths identified as the approximate 68 ft. run from east to west across the corridor, as well as geomembrane pieces which were used to complete the southern end of the corridor) were installed (P-98, P-99, P-100, P-101, P-102, P-103, P-104, P-105, and P-106) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/18), *Trial Weld Log.*
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- Upon completion of geomembrane panel placement to approximate Sta. 6+40, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/18/15) for non-destructive testing details. Based on the panel placement, minimal repairs were required along the installed panels. As such, patches were leistered over the repairs with the final extrusion welds to be completed on 9/21/15.
- Two destructive samples (DS-25 and DS-26) were collected (fusion welds) from Panel Seams 94/95 and 97/97, respectively. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.
- During cap placement activities, Entact spread protective cover soil moving east from approximate Sta. 14+20. Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/18/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2$^{nd}$ utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 6 gas vents).
- Review laboratory results for DS-25 and DS-26 (once received).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, and 9/17/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-24, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 through, and east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/18/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/18/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/18/15 |
| A5 – Subgrade Approval | Sheet 19 & ESI (9/18/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/18/15. |
| A7 – Panel Placement Log | Page 21 & 22 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/18/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/18/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 22-24 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/18/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A10 – Repair Log | | N / A repairs patched and leistered, however, no welding or vacuum box testing completed |
| A11 – Conformance COC | | N / A for 9/18/15 |
| A12 – Destructive Seam Field Test | Page 2 | Updated with destruct information collected on 9/18/15 |
| A13 – Destruct. Sample Summary | Page 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/18/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/18/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking south through 3rd utility corridor (located at approximate Sta. 6+80).

**Description:**

Soil subgrade graded, compacted, and free of debris (>1/2") as outlined in the project specs. Subgrade approved through 3rd utility corridor (approximate Sta. 7+00 to Sta. 6+40).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/18/15

**Direction Taken:**

Looking north through 3rd utility corridor

**Description:**

Soil subgrade approved for panel placement through 3rd utility corridor. Subgrade prepared according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south along 3rd utility corridor (western slope).

**Description:**

ESI placing GVL along eastern and western slopes of 3rd utility corridor. GVL placed to approximate 2 ft. to 3 ft. from bottom of corridor (GCL proposed along bottom of corridor and up bottom slopes). GVL to overlap GCL a minimum of 1 ft. (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking south through 3rd utility corridor

**Description:**

GVL deployed along western slope of 3rd utility (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking north through 3rd utility corridor

**Description:**

GVL placed along eastern and western slopes of 3rd utility corridor (placed according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking south from within 3rd utility corridor

**Description:**

ESI placing GCL along bottom of 3rd utility corridor. GCL placed according to project specs (at areas below to 1 ft. above the water table). GVL overlapped a minimum of 1 ft. over GCL, and GCL anchored into slope with soil stakes / staples.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/18/15

**Direction Taken:**

Looking south through 3rd utility corridor

**Description:**

GCL and GVL placed along bottom and slopes of 3rd utility corridor (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/18/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/18/15

**Direction Taken:**

Looking north / northeast at northern end of 3rd utility corridor

**Description:**

ESi deploying geomembrane panels over GVL and GCL as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

ESI conducting fusion welding along panel seams 97 /100 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking north along top western slope of 3rd utility corridor

**Description:**

Geomembrane panels placed and welded (according to project specs). Panels oriented from east to west running through 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/18/15

**Direction Taken:**

Looking along SA-6 cap (Panels 1000/101)

**Description:**

ESI conducting non-destructive testing (air pressure tests) for Panel Seams 100 / 101 as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking north along 3rd utility corridor

**Description:**

Geomembrane panels placed and welded (according to project specs) through 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/21/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 66/83° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1500 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #29** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Dave Ambrose, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL), continuing through 2nd utility corridor (located at approximate Sta. 10+00).. Material to be placed from eastern slope of 2nd utility corridor (Panels 76-81; running east to west) located at approximate Sta. 10+30) running approximately 250 ft. east to Panel #93 (located at approximate Sta. 7+80).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI placing GDL from approximate Sta. 10+30 (eastern slope of 2nd utility corridor) to approximate Sta. 7+80 (Panel #93). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals. Additionally, the top layer of geotextile was sewn (as outlined in the project specs).
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.
- Once GDL was completed to the (based on the approved as-builts) , ESI completed patch / repair along the panels previously installed, Panels 95-106 which were placed on 9/17/15 and 9/18/15. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/21/15).
- A total of thirty-two repairs (RP-367 through RP-398) were observed and fixed (according to the project specifications) from Panels #95 through Panel #106 (repair / detailing work conducted on panels installed on 9/17/15 and 9/18/15). Refer to 9/21/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for gas vent GV-2. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- One destructive sample (DSX-10) was collected (extrusion) from RP-376. Destruct samples were collected at 500 LF intervals and in accordance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/21/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 3 piezometers, and 6 gas vents).
- Review laboratory data for destruct sample DSX-10 (extrusion) once received

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, and 9/18/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-9. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/21/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/21/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/21/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed for 9/21/15. |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/21/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 9/21/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected on 9/21/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 9/21/15 |
| A10 – Repair Log | Pages 18-19 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/21/15 |
| A11 – Conformance COC | | N / A for 9/21/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct information collected on 9/21/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | Destruct Sample Information provided by ESI and confirmed by Langan for 9/21/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified for activities completed on 9/21/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/21/15

**Direction Taken:**

Looking north / northeast along 2nd utility corridor (located at approximate Sta. 10+00).

**Description:**

ESI deploying GDL along eastern slope, northern end of 2nd utility corridor. GDL placed according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/21/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 9+00).

**Description:**

GDL deployed moving east from 2nd utility corridor. GDL secured with white plastic fasteners spaced at a maximum of 5 ft. intervals, and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at gas vent GV-2)

**Description:**

ESI constructing geomembrane boot around gas vent GV-2



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/21/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/21/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at RP-370).

**Description:**

ESI conducting patch / repair work and extrusion welds (according to project specs) for repairs from 9/17/15 and 9/18/15.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at GV-2)

**Description:**

ESI completing geomembrane boot around gas vent GV-2. Geomembrane skirt to be placed over penetration and extrusion welded with 18-inches of overlap (as outlined in project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at RP-367)

**Description:**

ESI conducting vacuum box testing on extrusion weld repairs (as outlined in project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking along SA-6 cap (at GV-2)

**Description:**

Final boot, skirt, and welds completed for GV-2 as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (09/21/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/21/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at DSX-10)

**Description:**

Patch / repair work completed for destruct sample DSX-10 (extrusion weld) collected from RP-376.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/22/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 62/84° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1530 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #30**
**AmecFW**: Stu Bills, Dave Ambrose, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL) and 60-mil geomembrane liner (Cap), continuing past eastern side of 3rd utility corridor. Material to be placed from Panels #98, 99, 100, 101, 102, 103, and 106 (panels running east to west through 3rd utility corridor) installed on 9/18/15 (located at approximate Sta. 6+40) running approximately 110 ft. east to Sta. 5+30. Panels installed today (9/22) will "T" into the panels outlined above as panels will revert back to north-south orientation outside of utility corridor (as per the approved panel layout).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with Langan and Entact conducting soil subgrade approval from approximate Sta. 6+40 (eastern end of 3rd utility corridor) to Sta. 5+30. Refer to *Soil Subgrade Approval* forms from 9/22/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 and #3 of the daily photo log for 9/22/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 6+40 to Sta. 5+30.
- While subgrade inspection was being conducted, ESI conducted vacuum box testing for the repairs completed on 9/21/15, and also installed the remaining panels of GDL from geomembrane Panel #93 to Panel #96.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, one roll of GDL was required to be cut to remove the first wrap of geocomposite prior to use – Roll #64021010086 (8 ft. cut).
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 6+40 (east of 3rd utility corridor) moving east (for approximately 110 ft.) to approximate Sta. 5+30. GVL was placed according to

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/22/15 Photo Log* for supporting photographs.

- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, one roll of GVL was required to be cut to remove the first wrap of geocomposite prior to use – Roll #65211010113 (8 ft. cut)
- After installation of the GVL, geomembrane cap was installed continuing east of previously installed Panels #98-103, and #106 (running east-west through 3rd utility corridor) on 9/18/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-107, P-108, P-109, and P-110) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, trial welds (smooth to smooth, texture to texture, and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/22), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 5+30, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/22/15) for non-destructive testing details.
- Once non-destructive testing was completed, ESI conducted patch / repair along the panels installed, Panels 107-110. Prior to repair work a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/22/15).
- A total of nineteen repairs (RP-399 through RP-417) were observed and fixed (according to the project specifications) from Panels #107 through Panel #110 (repair / detailing work conducted on panels installed on 9/22/15). Refer to 9/22/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for piezometer PZ-14. Note: The penetration logs for all boots to date will be completed once the boot has been sealed with butyl sealant.
- No destructive samples were collected, as an RFI was submitted to AmecFW, and based on the results of the first 26 destruct samples – the sampling frequency was decreased from 500 LF to 1500 LF as samples yielded zero failures with all 26 exhibited shear and peel results greater than the minimum requirements (as per the project specs).
- During cap placement activities, Entact spread protective cover soil for the area immediately west of the 2nd utility corridor (approximate Sta. 10+20). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project specs and patch / repair work consisted of custom fit design to allow geomembrane to conform to SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/15/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 4 piezometers, and 5 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, and 9/21/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/22/15 |
| A3 – Photo Log | Pages 1 – 6 | Total of 12 photos outlining pertinent daily observations and descriptions for 9/22/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/22/15 |
| A5 – Subgrade Approval | Sheet 20 & ESI (9/22/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 5 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/22/15. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A7 – Panel Placement Log | Page 23 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/22/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/22/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 24-25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/22/15 |
| A10 – Repair Log | Pages 19-20 | One repair log provided by ESI and confirmed by Langan for repairs completed for 9/22/15 |
| A11 – Conformance COC | | N / A for 9/22/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/22/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/22/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/22/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking east past 3rd utility corridor (past Sta. 6+40).

**Description:**

Soil subgrade approved for the area east of the 3rd utility corridor. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 6+40)

**Description:**

Soil subgrade approved for geomembrane placement (looking north along end of geomembrane previously installed on 9/18). Subgrade prepared according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking south along subgrade (east of 3rd utility corridor) at approximate Sta. 5+90

**Description:**

Soil subgrade prepared for geomembrane placement according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/22/15

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

ESI placing 16 oz. geotextile along southern boundary of SA-6 (sheet pile wall). Geotextile overlapped 2 ft. to the outside with remaining roll width inside as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 6+20)

**Description:**

ESI deploying GVL panels along approved soil subgrade. GVL secured with white plastic fasteners spaced at maximum 5 ft. intervals with top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 6+00)

**Description:**

GVL panels placed along soil subgrade. White plastic fasteners spaced at maximum 5 ft. intervals.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/22/15

**Direction Taken:**

Looking south / southeast along SA-6 cap (at approximate Sta. 5+80)

**Description:**

ESI deploying geomembrane panels over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/22/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/22/15

**Direction Taken:**

Looking down along SA-6 cap (top eastern slope of 3rd utility corridor)

**Description:**

ESI conducting fusion welding between Panel Seams 101 / 107 as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/22/15

**Direction Taken:**

Looking north along Panel #107 (east of 3rd utility corridor)

**Description:**

Panel #107 (running north to south) past top of eastern slope of 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/18/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/18/15

**Direction Taken:**

Looking down at SA-6 cap (top eastern slope of 3rd utility corridor)

**Description:**

Non-destructive testing at Seam Joint 102/103/107. Testing conducted according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/22/15

**Direction Taken:**

Looking along SA-6 cap (at piezometer PZ-14)

**Description:**

ESI placing geomembrane boot around piezometer PZ-14 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/22/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/22/15

**Direction Taken:**

Looking west at northern end of 2nd utility corridor

**Description:**

ESI conducting patch / repair work (custom fit repair) along northern end of 2nd utility corridor (RP-412).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/23/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 58/79° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1700 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #31**<br>**AmecFW**: Stu Bills, Dave Ambrose, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing past eastern side of 3rd utility corridor. Material to be placed from Panels #110 installed on 9/22/15 (located at approximate Sta. 5+30) running approximately 80 ft. east to Sta. 4+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #96/97 (approximate Sta. 7+00) through 3rd utility corridor to approximate Sta. 5+30 (Panel #110 placed on 9/22/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL was required to be cut to remove the first wrap of geocomposite prior to use:
    - Roll #64021010103 - 5 ft. cut and removed
    - Roll #64021010105 – 8 ft. cut and removed
- Langan and Entact conducting soil subgrade approval from east of Panel #110 (located at approximate Sta. 5+30) to approximate Sta. 4+50. Refer to *Soil Subgrade Approval* forms from 9/23/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #1 and #2 of the daily photo log for 9/23/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 5+30 to Sta. 4+50.
- GVL and Cap placement began with ESI placing the 16 oz. geotextile at the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The geotextile was overlapped approximately 2 ft. outside of the cap (remaining roll width inside), as outlined in the specifications. After the 16 oz. geotextile was placed, GVL was installed from approximate Sta. 5+30 (east of 3rd utility

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

corridor) moving east (for approximately 80 ft.) to approximate Sta. 4+50. GVL was placed according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/23/15 Photo Log* for supporting photographs.

- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- In addition to the GVL, GCL was placed along the northern and southern edges of SA-6 at areas below (to 1 ft. above) the groundwater table (as shown on the drawings and outlined in the project specs). GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- After installation of the GVL and GCL, geomembrane cap was installed continuing east of previously installed Panel #110 on 9/22/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-111, P-112, P-113, and P-114) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, a trial weld (smooth to smooth) was conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/23), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 4+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/23/15) for non-destructive testing details.
- One patch / repair (RP-418) was completed as a pipe boot for well 115-E1A-SO located at Panel #109. The boot was constructed according to the project specs (final butyl seal still to be applied). No destruct samples were collected from 9/23/15.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and no patch / repair work was conducted.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/23/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 2 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), and Main Access Manhole #3 (located at western slope of 2nd utility corridor).

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, and 9/22/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/23/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/23/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/23/15 |
| A5 – Subgrade Approval | Sheet 21 & ESI (9/23/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Pages 5-6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/23/15. |
| A7 – Panel Placement Log | Page 24 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/23/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 9/23/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/23/15 |
| A10 – Repair Log | Page 20 | One repair log provided by ESI and confirmed by Langan for repairs completed for 9/23/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| ***Appendix / QA Forms*** | ***Sheet / Page Numbers*** | ***Comments*** |
|---|---|---|
| A11 – Conformance COC | | N / A for 9/23/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 9/23/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 9/23/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues identified on 9/23/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 4+90)

**Description:**

Soil subgrade approved for the area east of Panel #110 (P-110) installed on 9/22/15. Subgrade graded, compacted, and free of debris (>1/2").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking west / northwest along SA-6 cap (looking toward place panels from 9/22/15)

**Description:**

Soil subgrade approved for geomembrane placement from approximate Sta. 5+30 to approximate Sta. 4+50.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/23/15

**Direction Taken:**

Looking south along 3rd utility corridor (approximate Sta. 6+80)

**Description:**

ESI deploying GDL panels (oriented from east to west) through 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking north along 3rd utility corridor (approximate Sta. 6+80)

**Description:**

ESI placing GDL panels (oriented from east to west) moving north along 3rd utility corridor.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

ESI placing 16 oz. geotextile along southern boundary of SA-6. GCL also placed at marked areas below (to 1 ft. above the groundwater table) as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/23/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/23/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 5+00)

**Description:**

GVL panels placed along soil subgrade. White plastic fasteners spaced at maximum 5 ft. intervals as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 5+10)

**Description:**

ESI deploying geomembrane panels over GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/23/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/23/15

**Direction Taken:**

Looking down along SA-6 cap (Panels 110 / 111 seam)

**Description:**

ESI conducting fusion welding between Panel Seams 110 / 111 as per project specifications.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/24/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 59/80° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

| **CONTRACTOR & EQUIPMENT:** | **PERSONNEL ON SITE:** **Day #32** |
|---|---|
| **ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite venting layer (GVL), geosynthetic clay liner (GCL), and 60-mil geomembrane liner (Cap), continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #114 installed on 9/23/15 (located at approximate Sta. 4+50) running approximately 70 ft. east to Sta. 3+80.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair along the panels previously installed, Panels 111-114 which were placed on 9/23/15. Prior to repair work, a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/24/15).
- A total of seven repairs (RP-419 through RP-424) were observed and fixed (according to the project specifications) from Panels #111 through Panel #114 (repair / detailing work conducted on panels installed on 9/23/15). Refer to 9/24/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications.
- One non-compliance issue was observed and was noted on *Sheet #8 Notice of Non-Compliance and Corrective Action Form.* This non-compliance was also noted on the Repair Log as a subgrade irregularity and was identified as RP-423. This non-compliance issue was identified based on a rock that was observed underneath the geomembrane cap. The rock was removed from underneath the liner and the hole was patched / repaired according to the project specifications and further outlined in the *Non-Compliance and Corrective Action* forms – *Sheet #8* for 9/24/15.
- While the geomembrane was being patched / repaired, ESI also installed a penetration boot for well 115-E1A-SO and Access Manhole #4. Note: The penetration logs for all boots to date will be completed once the boots have been sealed with butyl sealant (not yet completed).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was completing patch / repair work, Langan and Entact conducted soil subgrade approval from east of Panel #114 (located at approximate Sta. 4+50) to approximate Sta. 3+80. Refer to *Soil Subgrade Approval* forms from 9/24/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3 and #4 of the daily photo log for 9/24/2015, for supporting subgrade photos. This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 4+50 to Sta. 3+80.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the areas within the SA-6 cap along the bottom and side slopes of the drainage/utility ditches located from approximate Sta. 4+50 to Sta. 3+80. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- After the GCL was placed, GVL was installed from approximate Sta. 4+50 (Panel #114) moving east (for approximately 70 ft.) to approximate Sta. 3+80. GVL was placed along the areas outside of the water GCL (outside of the water table influence) and according to the project specifications with white plastic fasteners spaced at a maximum of 5 ft. Additionally, the top panel of geotextile was sewed along the seams (according to the project specifications). Refer to *9/24/15 Photo Log* for supporting photographs. Note: The GVL was cut along the drainage / utility to expose the GCL as a minimum of 1 ft. of overlap was required along the ditches where the GVL and GCL intersected.
- As per the QA inspection conducted on the GVL on September 3, 2015, by AmecFW, no rolls of GVL were required to be cut to remove the first wrap of geocomposite prior to use.
- After installation of the GVL and GCL, geomembrane cap was installed continuing east of previously installed Panel #114 on 9/23/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GVL and GCL layers. A total of four panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-115, P-116, P-117, and P-118) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, two trial welds (smooth to smooth and smooth to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/24), *Trial Weld Log*.
- Upon completion of geomembrane panel placement to approximate Sta. 4+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/24/15) for non-destructive testing details.
- No patch / repair work was conducted on Panels #115 through #118 as part of the activities on 9/24/15.
- Two destructive samples were collected for laboratory testing. DS-27 (fusion) was collected from Panel Seam 110/111 and is noted as RP-422 on the *Repair Log*. Fusion weld destruct samples collected at 1500 LF intervals (as per the approved RFI to reduce the sampling frequency from 500 LF to 1500 LF). One extrusion weld sample (DSX-11) was also collected from RP-421 and is noted as RP-424 on the *Repair Log*. Extrusion weld samples collected at 500 LF intervals as per the project specs.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 8 (Sheet #8) – Subgrade irregularity identified as RP-423 on *Repair Log*
    - Stone identified underneath geomembrane cap (Panel #111). Stone was subsequently removed, and hole was patched/repaired following project specs and further defined in *Sheet 8 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/24/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory destruct data for destruct samples DS-27 and DSX-11.

## ***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, and 9/23/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-26, and DSX-1 through DSX-10. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

## ***Near Misses / Incidents***

- None Encountered

## ***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas of SA-6 east of 3rd Utility Corridor. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/24/15 |
| A3 – Photo Log | Pages 1 – 7 | Total of 13 photos outlining pertinent daily observations and descriptions for 9/24/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/24/15 |
| A5 – Subgrade Approval | Sheet 22 & ESI (9/24/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/24/15. |
| A7 – Panel Placement Log | Page 25 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/24/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information from 9/24/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 25-26 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/24/15 |
| A10 – Repair Log | Pages 20-21 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/24/15 |
| A11 – Conformance COC | | N / A for 9/24/15 |
| A12 – Destructive Seam Field Test | Page 3 | Updated with destruct sample information from 9/24/15 |
| A13 – Destruct. Sample Summary | Sheet 3 | One destruct sample summary form provided by ESI and confirmed by Langan for 9/24/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | Sheet 8 | One non-compliance issue identified on 9/24/15 and identified on Sheet #8 and the Repair Log as a subgrade irregularity. |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/24/15

**Direction Taken:**

Looking west along SA-6 cap (Panel #110 / #111 seam)

**Description:**

Patch / repair work completed for destruct sample DS-27 collected at Panel #110/111 seam (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 cap (at well 115-E1A-SO)

**Description:**

ESI placing gaskets and seals and prepping well 115-E1A-SO for geomembrane boot.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 4+50)

**Description:**

Soil subgrade for next area graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking east / northeast along soil subgrade (from approximate Sta. 4+50)

**Description:**

Subgrade prepared according to project specs and approved for panel placement.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking south along SA-6 cap (at access manhole #4)

**Description:**

ESI constructing geomembrane boot and skirt for access manhole #4 (according to project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking east along northern end of SA-6

**Description:**

ESI placing GCL along northern SCB wall for areas below (to 1 ft. above) the groundwater table (as per project drawings and specifications).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/24/15

**Direction Taken:**

Looking west along SA-6 cap

**Description:**

Completed geomembrane boot around Access Manhole #4. Patch placed per project specs and extrusion welded with vacuum box testing being completed.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/24/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/24/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

GCL placed along SCB wall as per project drawings. GCL anchored into slope of subgrade with soil stakes / staples. Seams overlapped a minimum of 1 ft. and sealed with granular bentonite.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 4+20)

**Description:**

ESI placing GCL along drainage/utility ditches/swales for areas below (to 1 ft. above the groundwater table). GCL placed according to the project specs and at the locations shown on the project drawings.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 cap (at approximate Sta. 4+10)

**Description:**

ESI placing GVL as per project specs with white plastic fasteners spaced at maximum of 5 ft. and the top layer of geotextile sewn



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #11 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking east along SA-6 cap

**Description:**

GVL cut along bottom of utility/drainage ditches to expose GCL. Minimum of 1 ft. of overlap along GVL and GCL edges.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #12 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/24/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+50)

**Description:**

ESI deploying geomembrane panels



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #13 (09/24/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/24/15

**Direction Taken:**

Looking north along SA-6 (at panel seams 114/115)

**Description:**

ESI conducting fusion welding (as per project specifications) along Panel Seams 114 / 115.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 9/25/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 63/73° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1630 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #33**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #118 installed on 9/24/15 (located at approximate Sta. 3+80) running approximately 50 ft. east to Sta. 3+30.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI conducting patch / repair along the panels previously installed, Panels 114-118 which were placed on 9/24/15. Prior to repair work, a preweld test was conducted to confirm the extrusion welds met the requirements of the project specs. Refer to *Preweld Trial Log* (9/25/15).
- A total of twenty repairs (RP-425 through RP-444) were observed and fixed (according to the project specifications) from Panels #114 through Panel #118 (repair / detailing work conducted on panels installed on 9/24/15). Refer to 9/25/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. No non-compliance issues were identified as patch / repair work completed was custom fit repairs to allow geomembrane to conform to SA-6 contours. Note: RP-425 has been marked in the field by the project team, however, the repair (pipe boot for GV-2) has not yet been completed.
- Site activities commenced with ESI deploying rolls of GDL from Panel #110 (approximate Sta. 5+30) to approximate Sta. 4+50 (Panel #114 placed on 9/23/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, no rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #118 (located at approximate Sta. 3+80) to approximate Sta. 3+30. Refer to *Soil Subgrade Approval* forms from 9/25/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #5 and #6 of the daily photo log for 9/25/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 3+80 to Sta. 3+30.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 3+80 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs). Note: no GVL was placed as the subgrade required GCL placement for the entire area (below the water table elevation).
- After installation of the GCL, geomembrane cap was installed continuing east of previously installed Panel #118 on 9/24/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL layer. A total of two panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-119 and P-120) by ESI.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, two trial welds (smooth to smooth and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/25), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 3+30, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/25/15) for non-destructive testing details.
- ESI completed patch / repair work for the minor repairs associated with the placement of Panels 119 & 120 (RP-437 through RP-444) as identified previously in this report and reflected on the *Repair Log* from 9/25/15.
- No destructive samples were collected from 9/25/15
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 2nd utility corridor (approximate Sta. 10+00). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of custom fit repairs to allow the geomembrane to conform to the SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/25/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, and 9/24/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/25/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 9/25/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/25/15 |
| A5 – Subgrade Approval | Sheet 23 & ESI (9/25/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/25/15. |
| A7 – Panel Placement Log | Page 26 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/25/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected for 9/25/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 26-27 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/25/15 |
| A10 – Repair Log | Pages 21-22 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/25/15 |
| A11 – Conformance COC | | N / A for 9/25/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected from 9/25/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected from 9/25/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered from 9/25/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking along SA-6 cap (at Access Manhole #4)

**Description:**

Completed geomembrane boot placed around Access Manhole #4. Boot constructed according to project specs with geomembrane skirt and extrusion welds.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 4+60

**Description:**

ESI placing conducting patch / repair work (custom fit repairs) for panels placed on 9/24/15 as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/25/15

**Direction Taken:**

Looking east along northern end of SA-6 cap

**Description:**

ESI conducting vacuum box testing for extrusion weld repairs (as per project specs).




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+60)

**Description:**

ESI deploying GDL over geomembrane panels. GDL placed according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking east along SA-6 (at approximate Sta. 3+80)

**Description:**

ESI placing GCL over soil subgrade. GCL placed at locations shown on the project drawings and according to project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 3+40)

**Description:**

ESI placing GCL as per project drawings. GCL placed according to project specs with minimum of 1 ft. overlap and sealed with granular bentonite.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 3+80)

**Description:**

ESI deploying geomembrane panels over GCL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (09/25/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/25/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (at RP-439)

**Description:**

ESI conducting patch / repair work (custom fit repairs) for panels P-119 and P-120.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 9/29/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 69/79° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 0630 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #34**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #120 installed on 9/25/15 (located at approximate Sta. 3+30) running approximately 80 ft. east to Sta. 2+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #114 (approximate Sta. 4+50) to approximate Sta. 3+80 (Panel #118 placed on 9/24/15). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- As per the QA inspection conducted on the GDL on September 3, 2015, by AmecFW, the following rolls of GDL were required to be cut to remove the first wrap of geocomposite prior to use:
    - Roll #64021010072 – Approximately 8 ft. removed
    - Roll #64021010064 – Roll not on inspection list. Approximately 30 ft. removed due to damage observed from forklift
- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #120 (located at approximate Sta. 3+30) to approximate Sta. 2+50. Refer to *Soil Subgrade Approval* forms from 9/29/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #2 and #3 of the daily photo log for 9/29/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 3+30 to Sta. 2+50.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 3+30 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- Upon placement of the GCL, GVL was placed along the upper elevations within the areas outside of the water table influence (as shown on the project drawings). GVL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals and the top layer of geotextile sewn.
- After installation of the GCL and GVL, geomembrane cap was installed continuing east of previously installed Panel #120 on 9/25/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of five panel lengths (panel lengths identified as the approximate 165 ft. run from north to south across SA-6) were installed (P-120, P-121, P-122, P-123, P-124, and P-125) by ESI. Note: During placement of geomembrane panel P-123, the roll of geomembrane terminated within the SA-6 approximately 20 ft. from the southern end of the cap. Thus an additional panel (P-124) was required to complete the geomembrane run from north to south.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, three trial welds (smooth to smooth, smooth to texture, and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (9/29), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 2+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (9/29/15) for non-destructive testing details. Once, non-destructive testing was completed, ESI then conducted patch/ repair work for the panels installed.
- A total of eleven repairs (RP-445 through RP-455) were observed and fixed (according to the project specifications) from Panels #121 through Panel #125 (repair / detailing work conducted on panels installed on 9/24/15). Refer to 9/29/15 *Repair Report.* The majority of these repairs were cuts that were made on the geomembrane to allow the cap to conform to the contours of SA-6 South grade (custom fit repairs). These areas were subsequently patched and sealed with extrusion welds, with vacuum box testing then conducted as outlined in the project specifications. No non-compliance issues were identified as patch / repair work completed was custom fit repairs to allow geomembrane to conform to SA-6 contours.
- No destructive samples were collected from 9/29/15
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of custom fit repairs to allow the geomembrane to conform to the SA-6 contours.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 9/29/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 6 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, and 9/25/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 9/29/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 9/29/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 9/29/15 |
| A5 – Subgrade Approval | Sheet 24 & ESI (9/29/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 9/29/15. |
| A7 – Panel Placement Log | Page 27 | One panel placement log provided by ESI and confirmed by Langan for panels placed on 9/29/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected for 9/29/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 27-28 | One seam control form provided by ESI and confirmed by Langan for air pressure testing conducted on 9/29/15 |
| A10 – Repair Log | Page 22 | One repair log provided by ESI and confirmed by Langan for repairs completed on 9/29/15 |
| A11 – Conformance COC | | N / A for 9/29/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected from 9/29/15 |
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected from 9/29/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before log can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered from 9/29/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 4+00)

**Description:**

ESI deploying GDL over installed geomembrane panels. GDL placed according to project specs with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta.3+30)

**Description:**

Soil subgrade east of Panel #120 prepared for panel placement. Subgrade prepared according to project specs (graded, compacted, and free of debris >1/2").



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (09/25/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/25/15

**Direction Taken:**

Looking east along SA-6 (toward approximate Sta. 2+90)

**Description:**

Soil subgrade prepared for panel placement from approximate Sta. 3+30 to approximate Sta. 2+50.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 3+30)

**Description:**

ESI deploying GCL over approved soil subgrade. GCL placed at areas below (to 1 ft. above) the groundwater table as shown on the project drawings.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #5 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 (along approximate Sta. 3+00)

**Description:**

ESI placing GCL over soil subgrade. GCL placed at locations shown on the project drawings and according to project specs. GCL overlapped a minimum of 1 ft. and sealed with granular bentonite.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #6 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (at approximate Sta. 2+90)

**Description:**

GVL and GCL placed over approved subgrade prior to placement of geomembrane panels. GCL placed at areas below (to 1 ft. above) the groundwater table (as shown on project drawings) with GVL placed on the upper bench above water table areas.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
9/29/15

**Direction Taken:**

Looking south along SA-6 cap (at approximate Sta. 3+00)

**Description:**

ESI deploying geomembrane panels over GCL and GVL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (09/29/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
9/29/15

**Direction Taken:**

Looking west along SA-6 cap (at Panel Seams 121/122)

**Description:**

ESI conducting fusion welding (as per project specifications) along Panel Seams 121 / 122.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking north along SA-6 (along Panel 123 / 124)

**Description:**

Geomembrane panels placed on 9/29/15, welded, and tested according to project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (09/29/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
9/29/15

**Direction Taken:**

Looking south along southern end of SA-6 (at RP-447 through RP-449)

**Description:**

ESI completing patch / repair work for custom fit repairs along Panels 122 and 124. Patch / repair work completed according to project specs with extrusion welded and vacuum box testing completed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | | **DATE:** | 10/07/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 60/72° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | | **TIME:** | 0630 – 1600 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #35**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor, and patch / repair work associated with panels placed from 9/29/15.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing patch / repair work for minor wrinkles from panels previously placed on 9/29/15 (Panels 121 – 125). During the patch / repair work it was observed that the GCL underlying the geomembrane panels was hydrated with standing water present at two areas:
    - Area 1 was comprised of the drainage / utility swale located along the southern end of SA-6 (approximate Sta. 3+50 to Sta. 2+60 ). At this area, a sump pump pit was located immediately outside of SA-6 cap to the south. During the storm events over the weekend, this pump at one point shut down thus causing a build-up (ponding) of water that extended laterally into the swale and hydrating the GCL.
    - Area 2 was located along the northern end of the cap (approximate Sta. 4+00 to Sta. 3+40) along the SCB wall. During the storm events water from the adjacent roadway (higher elevation than the SA-6 cap as final grading has not yet been completed) ran along the edges of SA-6 causing some soil washout, which allowed the water to infiltrate laterally over the SCB wall and onto the lower portion of SA-6.
- For both of these areas, the geomembrane cap was pulled back to expose the hydrated GCL. The GCL was then cut and removed to expose the underlying soil subgrade. Visual observation of the subgrade showed that the soil was in good condition (firm and unyielding) with no wet or wash out areas observed. New GCL was then placed in these areas with minimum of 1 ft. of overlap and granular bentonite placed along the seams as per project specifications. Refer to *10/7/15 Photograph Log* for supporting Site photos.
- Once the new GCL was placed, the geomembrane panels were patch / repaired (as required) over these areas.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- A total of twenty repairs (RP-456 through RP-475) were observed and fixed (according to the project specifications) from Panels #119 through Panel #122 (repair / detailing work for replaced GCL on panels installed from 9/29/15). Refer to 10/7/15 *Repair Report.* The majority of these repairs were patch / repairs associated with the removal and replacing of the hydrated GCL. These repairs were identified as subgrade irregularities on the *Repair Report,* and were identified as non-compliance issues on *Sheet #9* and *Sheet #10 Notice of Non-Compliance* forms, respectively. Note: RP-457 which consisted of a pipe boot for GV-0 was marked in the field and noted on the Repair Report (as RP-457), however the boot and repair itself has not yet been completed.
- Two destructive samples were collected from 10/7/15. Destruct sample DS-28 (fusion) was collected from Panel #123/125, and sample DSX-12 was collected from RP-459 (Panel #123).
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 9 (Sheet #9) – Subgrade irregularity (hydrated GCL) identified as repairs RP-458 through RP-473 on *Repair Log*
    - GCL underneath geomembrane liner along southern end SA-6 (swale) hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final) and failure of sump pump in area during storm. Geomembrane liner pulled back and cut to remove and replace sections of GCL. These patches were noted as a subgrade irregularities and were completed following project specs and are further defined on *Sheet 9 Notice of Non-Compliance*
- Non-Conformance No. 10 (Sheet #10) – Subgrade irregularity (hydrated GCL) identified as RP-474 and RP-475 on *Repair Log*
    - GCL underneath geomembrane liner along northern end of SA-6 cap (along SCB wall) hydrated from rainwater accumulating outside of cap due to subgrade (subgrade outside of the cap not final). Geomembrane liner pulled back and cut to remove and replace sections of GCL. These patches were noted as a subgrade irregularities and were patched/repaired following project specs as further defined on *Sheet 10 Notice of Non-Compliance*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/7/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 4 piezometers, and 7 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DS-28 and DSX-12.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, and 9/29/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-27, and DSX-1 through DSX-11. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/7/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 9 photos outlining pertinent daily observations and descriptions for 10/7/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/7/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/7/15 |
| A6 – Trial Weld Log | Page 6 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/7/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/7/15 |
| A8 – Destruct Seam Testing COC | Page 2 | Updated with destruct sample information collected form 10/7/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing conducted on 10/7/15 |
| A10 – Repair Log | Pages 22-23 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/7/15 |
| A11 – Conformance COC | | N / A for 10/7/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/7/15 |
| A13 – Destruct. Sample Summary | Sheet 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/7/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before logs can be completed |
| A16 – Notice of Non-Compliance | Sheet #9 and Sheet #10 | Two non-compliance forms completed (Sheet #9 and Sheet #10) for cutting and removal of hydrated GCL |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/7/15

**Direction Taken:**

Looking east along SA-6 cap (Panel 123 / 125 seam)

**Description:**

ESI collecting destruct sample DS-28 (fusion) along Panel 123 / 125 seam as per project specs.




LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
10/7/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (swale at approximate Sta.

**Description:**

GCL hydrated / silted from stormwater during weekend rain events. Sump pump area located immediately outside of the cap failed, thus causing a water build-up and ponding that moved laterally into the swale and hydrating the GCL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|


**Date:**
9/25/15

**Direction Taken:**

Looking east along southern end of SA-6 cap (approximate Sta. 3+00)

**Description:**

Geomembrane cap pulled back to expose hydrated GCL.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/7/15

**Direction Taken:**

Looking east along southern end of SA-6 cap

**Description:**

Hydrated GCL removed and soil subgrade exposed. Subgrade in good condition with no wet, or washed out areas observed.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/7/15

**Direction Taken:**

Looking west along southern end of SA-6 cap

**Description:**

ESI placing new GCL over soil subgrade. GCL overlapped a minimum of 1 ft. and sealed with granular bentonite as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/7/15

**Direction Taken:**

Looking east along approximate Sta. 3+00

**Description:**

ESI conducting patch / repair work to the geomembrane cap after placing new GCL



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/7/15

**Direction Taken:**

Looking east along northern end of SA-6 cap (along SCB wall)

**Description:**

Geomembrane cap pulled back to expose hydrated / wet GCL located along northern end of SA-6. GCL hydrated from water infiltrating from storm runoff and washout from the road (cap at lower elevation that roadway – final grading not completed outside of cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (10/07/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/7/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

Hydrated GCL along SCB wall (lower elevation than roadway outside of SA-6 cap).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (10/07/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/7/15

**Direction Taken:**

Looking west along northern end of SA-6 cap

**Description:**

New GCL placed along northern end of SA-6.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 10/08/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 62/77° F, Clear, Sunny |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1830 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #36**<br>**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of placement of geosynthetic clay liner (GCL), geocomposite venting layer (GVL), 60-mil geomembrane liner (Cap), and geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor. Material to be placed from Panel #125 installed on 9/29/15 (located at approximate Sta. 2+50) running approximately 100 ft. east to Sta. 1+50.
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI deploying rolls of GDL from Panel #118 (approximate Sta. 3+80) to approximate Sta. 2+50 (Panel #125). GDL was placed according to project specifications with white plastic fasteners spaced at a maximum of 5 ft., and top layer of geotextile sewn along the panel seams.
- While ESI was placing GDL, Langan and Entact conducted soil subgrade approval from east of Panel #125 (located at approximate Sta. 2+50) to approximate Sta. 1+50. Refer to *Soil Subgrade Approval* forms from 10/08/15 for additional details. Based on visual inspection, the soil subgrade appeared to be firm and unyielding with no soft / wet areas observed. Furthermore, miscellaneous debris (rocks, debris, etc.) were removed so that the surface was free of any loose material. Refer to Photos #3 and #4 of the daily photo log for 10/08/2015, for supporting subgrade photos (along with GCL placement). This area was also surveyed to meet the grading requirements as outlined in the project specifications. The soil subgrade inspection sheet was submitted for the approximate area of Sta. 2+50 to Sta. 1+50.
- GVL and Cap placement began with ESI placing the GCL along the boundaries of the SA-6 South Cap over the sheet pile and surrounding barrier walls. The GCL was overlapped approximately 2 ft. outside of the cap and was placed along the areas below (to 1 ft. above) the water table (as shown on the drawings and outlined in the project specs). This included the remaining area within the SA-6, as the lower bench east of Sta. 2+50 was comprised of areas below the water table elevation. GCL was overlapped a minimum of 1 ft. along the seams with granular bentonite placed along the edges (as outlined in the project specs).
- Upon placement of the GCL, GVL was placed along the upper elevations within the areas outside of the water table influence (as shown on the project drawings). GVL was placed according to project

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

specifications with white plastic fasteners spaced at a maximum of 5 ft. intervals and the top layer of geotextile sewn.

- After installation of the GCL and GVL, geomembrane cap was installed continuing east of previously installed Panel #125 on 9/29/15. Panels were oriented from north to south (as proposed in the approved Panel Layout) and were placed on top of the GCL and GVL layers. A total of ten varying panel lengths were placed by ESI (Panels #126-134). Note: the dimensions of these panel lengths varied as the geomembrane panels were conformed to fit along the eastern end of the SA-6 cap.
- During installation of the Cap, geomembrane seams were overlapped a minimum of four inches for fusion welding (according to the project specifications). Prior to welding activities, three trial welds (smooth to smooth, smooth to texture, and texture to texture) were conducted to confirm that the equipment met the required specifications. A total of six 1-inch specimens were collected for peel and shear testing (3 samples for each test). The results of the pre-trial weld are provided in the associated QA form submitted for today (10/8), *Trial Weld Log.*
- Upon completion of geomembrane panel placement to approximate Sta. 1+50, ESI conducted non-destructive testing in accordance with the project specifications. Refer to *Seam Control Form* (10/08/15) for non-destructive testing details. Once, non-destructive testing was completed, ESI then conducted minor patch/ repair work for the panels installed (pipe boots PZ-12).
- A total of one repair (RP-476) was completed (according to the project specifications) for Panel #132 (pipe boot PZ-12). Refer to 10/8/15 *Repair Report* for additional details on the pipe boot. Note: no non-compliance issues were observed during the geomembrane placement and testing conducted on 10/8/15.
- One destructive sample was collected from 10/8/15. Destruct sample DS-29 (fusion) was collected from Panel #128/132 seam.
- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.

## ***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as non-destructive testing was in conformance with the project and patch / repair work completed consisted of pipe boot installations around PZ-12.

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/8/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (once clamps and gaskets have been installed for 3 wells, 5 piezometers, and 8 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1 (once boot and associated sealing activities are completed for manhole located at Sta. 21+00), and Manhole #2 (once concrete extension is added and the manhole is clamped and sealed – located at approximate Sta. 15+70), Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DS-29.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, and 10/07/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-28, and DSX-1 through DSX-12. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue subgrade preparation work for remaining areas along far eastern end of SA-6. Ensure subgrade is graded, compacted, and free of debris, as well as surveyed to specifications.
- Continue with GVL and Geomembrane Cap placement moving east along SA-6 South.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/8/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 10/8/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/8/15 |
| A5 – Subgrade Approval | Sheet 25 & ESI (10/8/15) | Two subgrade approval forms provided. One by Independent QA and one from Geosynthetic Installer. |
| A6 – Trial Weld Log | Pages 6-7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/8/15. |
| A7 – Panel Placement Log | Pages 28-29 | One panel placement log provided by ESI and confirmed by Langan for prewelds completed on 10/8/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/8/15 |
| A9 – Seam/Non-Destruct. Test Log | Pages 28-30 | One seam control form provided by ESI and confirmed by Langan for pressure testing conducted on 10/8/15 |
| A10 – Repair Log | Page 23 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A11 – Conformance COC | | N / A for 10/8/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/8/15 |
| A13 – Destruct. Sample Summary | Sheet 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/8/15 |
| A14 – Penetration & Edge Form | | N / A final butyl seal required around boots before logs can be completed |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/8/15

**Direction Taken:**

Looking south along SA-6 (at approximate Sta. 3+80)

**Description:**

ESI deploying GDL over geomembrane panels (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/8/15

**Direction Taken:**

Looking north along SA-6 (approximate Sta. 3+20)

**Description:**

ESI deploying GDL over geomembrane panels.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking north / northwest along SA-6 (at approximate Sta. 1+70)

**Description:**

Approved soil subgrade for GCL and GVL placement. Soil graded, compacted, and free of debris (>1/2") as outlined in project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking south along eastern end of SA-6 cap (at approximate Sta. 2+00).

**Description:**

ESI placing GCL along eastern end of SA-6 cap (as shown in project drawings) as per project specs.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast toward eastern end of SA-6

**Description:**

GVL and GCL placed over soil subgrade. GCL overlapped a minimum of 1 ft. with granular bentonite placed along seams (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast toward eastern end of SA-6

**Description:**

ESI deploying geomembrane panels over GVL and GCL (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #7 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/8/15

**Direction Taken:**

Looking northeast along SA-6

**Description:**

ESI deploying geomembrane over eastern section of SA-6 (adjacent to Route 440)



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #8 (10/08/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/8/15

**Direction Taken:**

Looking east at eastern end of SA-6 (along Route 440).

**Description:**

ESI conducting fusion welding along Panel Seams 132/133 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking northwest along SA-6 cap (at pipe boot for piezometer PZ-12).

**Description:**

Pipe boot and skirt patch / repair completed for piezometer PZ-12.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (10/08/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/8/15

**Direction Taken:**

Looking northeast along SA-6

**Description:**

Pipe boot PZ-12 completed with extrusion welds and vacuum box tested to confirm integrity (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 10/09/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 58/75° F, Clear, Overcast, PM T'Storm |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0630 – 1730 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #37**
**AmecFW**: Stu Bills, Brian Shea, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of placement of geocomposite drainage layer (GDL) continuing along eastern side of 3rd utility corridor, and to eastern end of SA-6, and patch / repair work associated with panels placed from 10/8/15 (Panels #126-134).
- Prior to Site activities, a daily health & safety (H&S) tailgate meeting was conducted with onsite personnel and contractors regarding work to be completed and potential hazards / complications that may be encountered during daily activities. Appropriate personal protective equipment (PPE) was donned (hard hat, safety vest, gloves, eyeglasses, and tyvek suit) prior to entering the work area (SA-6 capping area). It should be noted that after GVL has been placed on SA-6, modified level D PPE (tyvek suit, rubber boots, etc.) was not required.
- Site activities commenced with ESI completing patch / repair work for panels previously placed on 10/8/15 (Panels #126-134). A total of nine repairs (RP-477 through RP-485) were observed and fixed (according to the project specifications) from Panels #126 through Panel #134. Refer to 10/9/15 *Repair Report* for additional details. The majority of these repairs were custom fit details (allow the geomembrane to conform to the SA-6 contours) or seam joint repairs (joints where non-destructive testing was completed). Repairs were patched, sealed with an extrusion weld, and vacuum box tested (according to project specs).
- Two destructive samples were collected from 10/9/15. Destruct sample DSX-13 (extrusion) was collected from RP-477 (Panel #125) and DSX-14 (extrusion) was collected from RP-480 (Panel #132).
- Upon completion of the patch / repair work, ESI completed the final monitoring well, piezometer, and gas vent boots by placing the final butyl sealant around the top of the boot. Additionally, 1-inch pipe bands were placed around the conical Access Manholes (as per project specs).
- With the pipe boots completed, ESI deployed GDL from Panel #125 to Panel #134 (panels placed on 10/9/15). GDL was placed according to project specs with white plastic fasteners spaced at a maximum of 5 ft. and the top layer of geotextile sewn.
- Note: As per the AmecFW GDL Cover Soil Siltation Evaluation and Mitigation Measures Memo (Memo) submitted October 26, 2015, three areas in the field were identified where GDL was exposed and silts were deposited directly onto the GDL. In response to the protective cover soil siltation, three new pieces of GDL were placed directly over the potentially impacted areas to assist in drainage. Additional details of these areas and mitigation measures are further described in the AmecFW Memo, with supporting photographs provided.

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

- During cap placement activities, Entact continued to spread protective cover soil for the area through the 3rd utility corridor (approximate Sta. 6+80, moving east). Protective cover soil was placed following the project specs with warning caution tape spaced at maximum of 55-inch intervals.
- Upon completion of the daily activities, ESI demobilized from the Site, as SA-6 capping activities were completed.

***Non-Conformance Items / Corrective Actions***

- No non-conformance issues were recorded as patch / repair work completed consisted of custom fit repairs and seam joint patches to allow the geomembrane to conform to the SA-6 contours.

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/9/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Complete Well / Piezometer Penetration Logs (for 3 wells, 5 piezometers, and 8 gas vents).
- Complete Collection Manhole Penetration Logs for Manhole #1, and Manhole #2, Main Access Manhole #3 (located at western slope of 2nd utility corridor), and Manhole #4.
- Review laboratory data for destruct samples DSX-13 and DSX-14.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, and 10/08/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-12. Laboratory results in compliance with shear and peel requirements as outlined in project specifications.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Continue with protective cover soil placement along eastern end of SA-6.
- Ensure destruct samples are in compliance with project specs and complete associated paperwork and construction certification report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/9/15 |
| A3 – Photo Log | Pages 1 – 5 | Total of 10 photos outlining pertinent daily observations and descriptions for 10/9/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/8/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/9/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/9/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/9/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/9/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 10/9/15 |
| A10 – Repair Log | Pages 23-24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/9/15 |
| A11 – Conformance COC | | N / A for 10/9/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/9/15 |
| A13 – Destruct. Sample Summary | Page 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/9/15 |
| A14 – Penetration & Edge Form | Sheets #1-18 | Final penetration & edge forms completed for piezometers, wells, gas vents, and access manholes. |
| A16 – Notice of Non-Compliance | | N / A no non-compliance issues encountered on 10/8/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #1 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking along SA-6 cap

**Description:**

ESI preparing geomembrane seam for extrusion weld trial log



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #2 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking west along southern end of SA-6 cap (Panel #125)

**Description:**

ESI conducting patch / repair work after collecting destruct sample DSX-13 from RP-477 (Panel #125).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking east along southern end of SA-6 (Panel #125)

**Description:**

Completed patch / repair for RP-483 with extrusion welds and subsequent vacuum box testing (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6 (at piezometer PZ-12)

**Description:**

ESI placing final butyl seal around piezometer PZ-12



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6 (at PZ-12)

**Description:**

Final geomembrane boot around piezometer PZ-12 completed with butyl seal. Boot and skirt extrusion welded and vacuum box tested (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking east along SA-6

**Description:**

Final butyl seal placed around top of gas vent GV-1 (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6

**Description:**

ESI placing final 1-inch band clamp around Manhole #4 with final butyl seal applied (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (10/09/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |


**Date:**
10/9/15

**Direction Taken:**

Looking south along SA-6

**Description:**

ESI deploying GDL over geomembrane panels placed on 10/9/15. GDL placed according to project spec with white plastic fasteners at a maximum of 5 ft. and the top layer of geotextile sewn.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #9 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking northwest along SA-6 cap (along SCB wall leading to Lighting Utility Corridor)

**Description:**

New layer of GDL (approximate 50 ft. by 7.5 ft.) placed along SCB wall over areas where runoff may have caused potential siltation inside GDL. Additional details outlined in the AmecFW Memo.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #10 (10/09/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/9/15

**Direction Taken:**

Looking northeast along SA-6 (lighting corridor looking north)

**Description:**

New layer of GDL (approximate 20 ft. by 3.75 ft.) placed along lighting corridor (looking north) and identified as area where potential siltation may have occurred. Additional details are outlined in the AmecFW Memo.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** Honeywell International, Inc. | **DATE:** | 10/12/2015 |
| **PROJECT:** | SA-6 South Capping | | **WEATHER:** | 72° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** Geocomposite & Cap Placement | **TIME:** | 1520 – 1720 |

**CONTRACTOR & EQUIPMENT:**
**ENTACT & ESI**
*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes)

**PERSONNEL ON SITE:** **Day #38**
**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad
**Langan:** Dan Bosworth
**ENTACT / ESI**: Keith Goisse, Caroline Panico

## ***Site Activities***

- Langan onsite for observation of patch / repair work associated with a failed destruct test (DSX-13) for RP-477 located on Panel #125.
- Based on results of the laboratory destruct testing, 1 of 5 specimens exhibited a peel value less than the 66 lb/in value allotted (as per the project specs) for destruct sample DSX-13. Based on this one failure anomaly, the repair associated with DSX-13 (RP-477) was covered with a new patch, welded, and vacuum box tested (as per project specs). In addition, a new destruct sample DSX-15 was collected to confirm the integrity of the new welds associated with the new patch. Note: the average of the 5 peel specimens complied with the project specs (total of 92 lb/in).
- Site activities commenced with ESI completing patch / repair work for RP-477. A new 5 ft. by 15 ft. patch was placed over the repair, sealed with an extrusion weld, and vacuum box tested as per project specs. Once the new repair (RP-487) was complete, a new destruct sample, DSX-15, was collected to confirm the integrity of the weld.
- One destructive sample was collected from 10/12/15. Destruct sample DSX-15 (extrusion) was collected from RP-487 (placed over RP-477). Subsequent laboratory testing yielded peel and shear values that were in compliance with the project specs.

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 11 (Sheet #11) – Failed destruct sample (DSX-13) collected from RP-477 from Panel #125 (failed one of the five specimens for peel testing)
    - Geomembrane patch was placed over RP-477, welded, and vacuum box tested (as per project specs). Additionally, a new destruct sample (DSX-15) was collected from the new patch (RP-487) to confirm the integrity of the new weld. This repair was noted as a failed destruct sample and was completed following project specs and as further defined on *Sheet 11 Notice of Non-Compliance.*

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Pending***

- Complete Daily Report and Photo Log (for 10/12/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).
- Review laboratory data for destruct samples DSX-15.

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, 10/08/15, and 10/09/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-14. Laboratory results in compliance with shear and peel requirements as outlined in project specifications with the exception of DSX-13. Subsequent patch / repair work defined within this report for the failed destruct sample.

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Ensure new destruct sample (DSX-15) adheres to project specifications. Subsequent review of the data yielded peel and shear values that were in compliance with the project specs.
- Complete associated paperwork and begin construction certification report.

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 10/12/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 8 photos outlining pertinent daily observations and descriptions for 10/12/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 10/12/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 10/12/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 10/12/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 10/12/15 |
| A8 – Destruct Seam Testing COC | Page 3 | Updated with destruct sample information collected form 10/12/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 10/12/15 |
| A10 – Repair Log | Page 24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 10/12/15 |
| A11 – Conformance COC | | N / A for 10/12/15 |
| A12 – Destructive Seam Field Test | Page 4 | Updated with destruct sample information from 10/12/15 |
| A13 – Destruct. Sample Summary | Page 4 | One destruct sample information provided by ESI and confirmed by Langan for destruct samples collected from 10/12/15 |
| A14 – Penetration & Edge Form | | N / A no penetration and edge forms completed for 10/12/15 |
| A16 – Notice of Non-Compliance | Sheet #11 | One non-compliance issue encountered on 10/12/15 and documented on *Sheet #11 Notice of Non-Compliance* |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking east along southern end of SA-6 (Panel #125)

**Description:**

ESI placing new patch over RP-477/RP-483 where destruct specimen (1 of 5 ) failed to meet project specs (Note: Average of 5 specimens was acceptable).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (10/12/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
10/12/15

**Direction Taken:**

Looking south along southern end of SA-6 (Panel #125)

**Description:**

ESI leistering and grinding RP-487 for extrusion welding and subsequent vacuum box testing (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #3 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking south along SA-6 (at RP-487)

**Description:**

ESI conducting extrusion welding (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

## PHOTOGRAPHIC LOG
Photo #4 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

Patch / repair RP-487 completed with extrusion welds (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESI conducting vacuum box testing (as per project specs) for RP-487



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking west along southern end of SA-6

**Description:**

ESI cutting destruct sample DSX-15 from RP-487 to confirm integrity of welds.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #7 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking east along southern end of SA-6

**Description:**

ESI conducting patch repair work for destruct sample DSX-15 (noted as RP-486 on Repair Report).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #8 (10/12/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
10/12/15

**Direction Taken:**

Looking north / northeast along southern end of SA-6

**Description:**

Final patch / repair work completed with extrusion welds and vacuum box testing (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# SITE OBSERVATION REPORT

| | | | | | |
|---|---|---|---|---|---|
| **PROJECT No.:** | 10053001 | **CLIENT:** | Honeywell International, Inc. | **DATE:** | 11/04/2015 |
| **PROJECT:** | SA-6 South Capping | | | **WEATHER:** | 55 / 70° F, Clear |
| **LOCATION:** | 60 Kellogg St., Jersey City New Jersey | **TASK.:** | Geocomposite & Cap Placement | **TIME:** | 0845 – 1215 |

| | |
|---|---|
| **CONTRACTOR & EQUIPMENT:**<br>**ENTACT & ESI**<br>*Equipment:* Dozers, Steel Drum Rollers, Skytrak 10 Forklift, Deere 333E Bobcat, Misc. Hand Tools (shovels, rakes) | **PERSONNEL ON SITE:** **Day #39**<br>**AmecFW**: Stu Bills, Dave Ambrose, Ari Eslaminejad<br>**Langan:** Dan Bosworth<br>**ENTACT / ESI**: Keith Goisse, Caroline Panico |

## ***Site Activities***

- Langan onsite for observation of patch / repair work associated with an equipment puncture that was observed along the northern end of SA-6 (at SCB wall) at approximate Sta. 2+95.
- Based on conversations with the project team, it is understood that during final grading of the area, the tooth of an excavator bucket punctured the GDL and underlying geomembrane cap. This error was attributed to malfunctioning GPS equipment, as the SCB wall (outside of the Cap) was not programmed into the GPS.
- Site activities commenced with ESI completing patch / repair work at the puncture location (along edge of SCB wall at approximate Sta. 2+95. A new piece of GCL was initially placed over the puncture area and a 2 ft. by 1.5 ft. geomembrane patch was then placed over the puncture, and sealed with an extrusion weld (as per project specs). Vacuum box testing could not be completed by ESI, as the patch / repair was located right on the edge of the SCB wall (refer to supporting photo log from 11/4/15).

## ***Non-Conformance Items / Corrective Actions***

- Non-Conformance No. 12 (Sheet #12) – Equipment puncture through geomembrane cap.
    - Geomembrane patch was placed over equipment puncture along SCB wall (at approximate Sta. 2+95) and extrusion welded (as per project specs). Prior to patch / repair work, a new piece of GCL was placed over the puncture. This repair was noted as an equipment puncture and was completed following the project specs and as further defined on *Sheet 12 Notice of Non-Compliance.*

## ***Action Items – Pending***

- Complete Daily Report and Photo Log (for 11/04/15). Review and confirm supporting QA paperwork (Soil subgrade approval, trail weld log, panel placement, notice of non-compliance, etc.).

Cc Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Action Items – Weekly Completions***

- Completed Daily Report, Photo Log, and Soil Subgrade Approval for 7/20/15, 7/21/15, 7/22/15, 7/23/15 and 7/24/15, 7/27/15, 7/28/15, 7/29/15, 7/30/15, 7/31/15, 8/3/15, 8/4/15, 8/5/15, 8/6/15, 8/7/15, 8/10/15, 8/12/15, 8/13/15, 8/15/15, 9/9/15, 9/11/15, 9/14/15, 9/15/15, 9/16/15, 9/17/15, 9/18/15, 9/21/15, 9/22/15, 9/23/15, 9/24/15, 9/25/15, 9/29/15, 10/07/15, 10/08/15, 10/09/15, and 10/12/15 as well as reviewed and approved daily ESI form submittals (i.e. Subgrade, Panel Placement, etc.)
- Reviewed laboratory destruct sample results for samples DS-1 through DS-29, and DSX-1 through DSX-15. Laboratory results in compliance with shear and peel requirements as outlined in project specifications with the exception of DSX-13 (details previously defined in *10/12/15 Daily Report*).

***Near Misses / Incidents***

- None Encountered

***Future Activities Scheduled***

- Complete associated paperwork and begin construction certification report.

***Daily QA Documents Completed***

| | | |
|---|---|---|
| A1 – Certificate of Completion | | To be completed at termination of project |
| A2 – Receiving and Inspection | | N / A – no material delivered on 11/04/15 |
| A3 – Photo Log | Pages 1 – 4 | Total of 7 photos outlining pertinent daily observations and descriptions for 11/04/15 |
| A4 – Geosynthetic Inventory Log | | Completed to date; no updates from 11/4/15 |
| A5 – Subgrade Approval | | N / A no subgrade approval completed on 11/4/15 |
| A6 – Trial Weld Log | Page 7 | One trial weld log provided by ESI and confirmed by Langan for prewelds completed up to 11/4/15. |
| A7 – Panel Placement Log | | N / A no panels placed on 11/4/15 |
| A8 – Destruct Seam Testing COC | | N / A no destruct samples collected on 11/4/15 |
| A9 – Seam/Non-Destruct. Test Log | | N / A no non-destructive testing completed on 11/4/15 |
| A10 – Repair Log | Page 24 | One repair log provided by ESI and confirmed by Langan for repairs completed on 11/4/15 |
| A11 – Conformance COC | | N / A for 11/4/15 |
| A12 – Destructive Seam Field Test | | N / A no destruct samples collected on 11/4/15 |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

***Daily QA Documents Completed (continued)***

| | | |
|---|---|---|
| A13 – Destruct. Sample Summary | | N / A no destruct samples collected on 11/4/15 |
| A14 – Penetration & Edge Form | | N / A no penetration and edge forms completed for 11/4/15 |
| A16 – Notice of Non-Compliance | Sheet #12 | One non-compliance issue encountered on 11/4/15 and documented on *Sheet #12 Notice of Non-Compliance* |

Cc: Jeff Stoicescu, Rory Johnston, Geoff Shallard, Stu Bills, Dave Ambrose

By: Dan Bosworth

**Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.**

LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #1 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking north along northern end of SA-6 cap (SCB wall) at approximate Sta. 2+95

**Description:**

Minor puncture along SCB wall from excavator bucket. Tooth of bucket penetrated through GDL and into underlying geomembrane layer.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #2 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall

**Description:**

Area around puncture cleared to allow ESI to complete patch / repair work (as per project specs).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #3 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking south along SCB wall

**Description:**

ESI replacing GCL underneath puncture at SCB wall.



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #4 (11/04/2015)

| **Project:** Honeywell SA-6 South Capping | **Location:** SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **Project No.** **100530001** |
|---|---|---|

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall (northern end of SA-6)

**Description:**

New geomembrane patch leistered over puncture



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #5 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking east along SA-6 (at SCB wall)

**Description:**

ESI conducting extrusion welding over new patch / repair (RP-488).



LANGAN
ENGINEERING & ENVIRONMENTAL SERVICES

# PHOTOGRAPHIC LOG
Photo #6 (11/04/2015)

| Project: | Location: | Project No. |
|---|---|---|
| Honeywell SA-6 South Capping | SA-6 South (Parallel to Kellogg St.) Jersey City, New Jersey | **100530001** |

**Date:**
11/4/15

**Direction Taken:**

Looking north along SCB wall

**Description:**

Extrusion welding along patch completed (as per project specs). Vacuum box testing unable to be conducted based on the location of the patch (on edge of SCB wall). Weld visually inspected by Entact / Langan.



# Appendix G
# Receiving Inspection Reports (RIRs)

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02375 |
| Received From: CETCO | | | | | | | | | Receiving Report Number: 27 |
| Address: Lovell Plant, 92 HWY 37, Lovell WY 82431 | | | | | | | | | Date: 6/15/15 |
| QC Inspection by: CP | | QC Date: 6/15/15 | | Inv. Or Packing Slip No.: | | Inv. Or Packing Slip Date: 6/10/15 | | | PO Number: E8140C-082 |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | 5 | | | | | 43 | 48 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 15 | Rolls | Bentomat DN GCL for SA6 North and South Caps (32,625 SF/39,241 lbs)<br>Sammons Truck #2531; Shipper No - 031527601 | 0 | 0 |
| 2 | 14 | Rolls | Bentomat DN GCL for SA6 North and South Caps (30,450 SF/34,183 lbs)<br>Corcoran Truck #9805; Shipper No - 031527602 | 0 | 0 |
| 3 | 14 | Rolls | Bentomat DN GCL for SA6 North and South Caps (30,450 SF/39,067 lbs)<br>Adams Trucking Truck #347; Shipper No - 031527603 | 0 | 0 |
| 4 | 5 | Bags | Granular Bentonite (250 lbs)<br>Sammons Truck #2531; Shipper No - 031527601 | 0 | 0 |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Trailer Trucks (Sammons, Corcoran, Adams) | | Car #<br>See above | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:<br>BOL and Packing List Attached | Freight Bill (Pro) No.:<br>BOL and Packing List Attached | Weight:<br>112,741 lbs (total) | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527603** | **Previous Page**

**Straight Bill of Lading - Original** Loader: JANDER Time In: 6/11/15-15:22:37 Time Out: **6/11/15-16:42:11**

**Carrier**: ADAMS TRUCKING
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/10/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 347 Trailer #: 395/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 32625.0000 SF | 30450.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 39067.3500 |

Gross: 46000.0000 Tare: 0.0000 **Total**: 46000

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

**CETCO**

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:**

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation.

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527603
ORDER DATE: 5/05/2015
SHIP DATE:. 6/11/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574

| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004066 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004068 | 150.0 | 14.5 | 2175.0 | 3160.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004073 | 150.0 | 14.5 | 2175.0 | 3225.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004074 | 150.0 | 14.5 | 2175.0 | 3165.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004075 | 150.0 | 14.5 | 2175.0 | 3230.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004076 | 150.0 | 14.5 | 2175.0 | 3205.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004077 | 150.0 | 14.5 | 2175.0 | 3210.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004078 | 150.0 | 14.5 | 2175.0 | 3235.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004079 | 150.0 | 14.5 | 2175.0 | 3260.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004080 | 150.0 | 14.5 | 2175.0 | 3285.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004081 | 150.0 | 14.5 | 2175.0 | 3330.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004084 | 150.0 | 14.5 | 2175.0 | 3290.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004085 | 150.0 | 14.5 | 2175.0 | 3315.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004090 | 150.0 | 14.5 | 2175.0 | 3300.0 |
| | | | | | | | ======== | |
| | | | | | | | 30450.0 | |
| | | | | | | | ======== | |
| | | | | | | | | ======== |
| ORDER TOTALS..... | | | | | | | | 45380.0 |

TOTAL ITEMS..... 14

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527601** | **Previous Page**

**Straight Bill of Lading - Original** Loader: HMCKI Time In: 6/9/15-17:41:01 Time Out: **6/9/15-19:01:07**

**Carrier**: SAMMONS
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/10/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 2531 Trailer #: 3232/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 34800.0000 SF | 32625.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 39241.7578 |
| 5.0000 EACH | 5.0000 EACH | | COMMODITY GRANULAR-50<br>(10902/024)<br>CLAY-BENTONITE-GROUND<br>CLASS 50 ITEM 48170 / 3295232<br>3295232 | 250.0000 |

Gross: 47700.0000 Tare: 0.0000 **Total**: 47700

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

CETCO

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:** 6-10-15 507599020

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527601
ORDER DATE: 5/05/2015
SHIP DATE:. 6/09/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574


| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004064 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004070 | 150.0 | 14.5 | 2175.0 | 3200.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004071 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004072 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004082 | 150.0 | 14.5 | 2175.0 | 3330.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004094 | 150.0 | 14.5 | 2175.0 | 3235.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004095 | 150.0 | 14.5 | 2175.0 | 3200.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004101 | 150.0 | 14.5 | 2175.0 | 3125.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004102 | 150.0 | 14.5 | 2175.0 | 3090.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004103 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004104 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004107 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004108 | 150.0 | 14.5 | 2175.0 | 3150.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004109 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004110 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| | | | | | | | 32625.0 | |
| LO-CG 50-LT | 50B | EA | | | | | 5.0 | 250.0 |
| | | | | | | | 5.0 | |

ORDER TOTALS..... 47720.0

TOTAL ITEMS..... 16

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527602** Previous Page

**Straight Bill of Lading - Original** Loader: DRICH Time In: 6/10/15-11:00:30 Time Out: **6/10/15-12:13:36**

**Carrier**: CORCORAN
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/10/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 9805 Trailer #: 547/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 34800.0000 SF | 30450.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 34183.9313 |

Gross: 44830.0000 Tare: 0.0000 **Total**: 44830

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

CETCO

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:** J. Carter

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation.

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527602
ORDER DATE: 5/05/2015
SHIP DATE:. 6/10/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574

| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004086 | 150.0 | 14.5 | 2175.0 | 3335.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004087 | 150.0 | 14.5 | 2175.0 | 3270.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004088 | 150.0 | 14.5 | 2175.0 | 3305.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004089 | 150.0 | 14.5 | 2175.0 | 3290.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004091 | 150.0 | 14.5 | 2175.0 | 3250.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004092 | 150.0 | 14.5 | 2175.0 | 3190.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004093 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004096 | 150.0 | 14.5 | 2175.0 | 3210.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004097 | 150.0 | 14.5 | 2175.0 | 3170.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004098 | 150.0 | 14.5 | 2175.0 | 3125.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004099 | 150.0 | 14.5 | 2175.0 | 3130.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004100 | 150.0 | 14.5 | 2175.0 | 3120.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004105 | 150.0 | 14.5 | 2175.0 | 3120.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004106 | 150.0 | 14.5 | 2175.0 | 3145.0 |
| | | | | | | | ======== | |
| | | | | | | | 30450.0 | |
| | | | | | | | ======== | |

ORDER TOTALS..... 44830.0

TOTAL ITEMS..... 14

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02380 Gas Venting System |
| Received From: Advanced Drainage Systems, Inc. (ADS) | | | | | | | | | Receiving Report Number: 28 |
| Address: Logan Township NJ | | | | | | | | | Date: 6/15/15 |
| QC Inspection by: CP | | QC Date: 6/15/15 | | Inv. Or Packing Slip No.: BOL #2946738 | | Inv. Or Packing Slip Date: 6/13/15 | | | PO Number: E8140C-082 |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Reels | Total Packages | Received By: ENTACT |
| 4 | | | | 115 | | | | 119 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 2,300 | LF | 8” ADS Single Wall Heavy Duty Perforated Pipe (115 – 20’ lengths) for gas venting system | 0 | 0 |
| 2 | 120 | EA | 8” ADS Internal Couplers | 0 | 0 |
| 3 | 10 | EA | 8” ADS Injection Molded Tees | 0 | 0 |
| 4 | 40 | EA | 8” ADS 45 Degree Bends | 0 | 0 |
| 5 | 2 | EA | 8” ADS Snap End Caps | 0 | 0 |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ADS | | Car # 25694 | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.: | Freight Bill (Pro) No.: BOL - 2946738 | Weight: 3090 lbs | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02375 |
| Received From: CETCO | | | | | | | | | Receiving Report Number: 29 |
| Address: Lovell Plant, 92 HWY 37, Lovell WY 82431 | | | | | | | | | Date: 6/18/15 |
| QC Inspection by: CP | | QC Date: 6/18/15 | | Inv. Or Packing Slip No.: | | Inv. Or Packing Slip Date: 6/15/15 | | | PO Number: E8140C-082 |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | | | | 4 | 4 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |


| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 4 | Rolls | Bentomat DN GCL for SA6 North and South Caps (8,700 SF/11,162 lbs)<br>SA Express Truck #9202; Shippers No 031527604 | 0 | 0 |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: SA Express | | Car # 031527604 | Payment: | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:<br>BOL and Packing List Attached | Freight Bill (Pro) No.:<br>BOL and Packing List Attached | Weight:<br>11,162 lbs (total) | Amount: | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

CETCO

AMERICAN COLLOID COMPANY



**Shippers No : 031527604** Previous Page

**Straight Bill of Lading - Original** Loader: JANDER Time In: 6/15/15-15:28:10 Time Out: **6/15/15-16:17:03**

**Carrier**: SA EXPRESS
**Consigned To** :
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257

JERSEY CITY NJ 07305
Phone:

CETCO 2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192
**Deliver Date** : 12/31/2015
**Ship Date** : 06/16/2015 **Via**: NATI
FOB ORIGIN

**Sold To** : 1823 **Ship To** : 208
Consigned PO: 21574
Truck #: 9202 Trailer #: 53301/

**Shipping Plant:** CETCO LOVELL PLANT 92 HWY 37 LOVELL WY 82431
Product Lots: Seal #: --enter here-- Container/Pro #:

**Global Comments:** ALL SHIPMENTS LOADED ON FLATBED OR OPEN TOP TRAILERS MUST BE COVERED WITH ADEQUATE TARPAULIN PRIOR TO HIGHWAY MOVEMENT. CARRIER WILL BE HELD FULLY RESPONSIBLE FOR LOSS OR DAMAGE OCCURRING TO UNPROTECTED LOADS. LOADS MAY NOT BE UNTARPED FOR ANY REASON PRIOR TO DELIVERY TO THE CUSTOMER UNTARPING THE LOAD MAY RESULT IN REJECTION OF THE MATERIAL AND LIABILITY TO THE CARRIER
**Customer Comments:**
**Order Comments:** CALL AHEAD CAROLINE PANICO 630.669.4257
**Quote #:**

| Order Qty | Shipped Qty | HM | Product Size / Description | Weight |
|---|---|---|---|---|
| 8700.0000 SF | 8700.0000 SF | | BENTOMAT DN<br>(DOUBLE NON-WOVEN)<br>CLOTH,FABRIC OR PIECE GOODS,NOI,OTHER THAN FOR THE MANUFACTURE OF CLOTHING:<br>CLASS 65 / ITEM 49265 SUB 10 | 11162.1000 |

Gross: 0.0000 Tare: 0.0000 **Total**: 11162

Subject to section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges

CETCO

If the charges are to be prepaid, write or stamp here, "Prepaid."
**Prepaid**
Shipper liable for the linehaul charges only. COD charges to be paid by: Consignee

Phone:
Fax:
Attn:

Mark with an 'X' to designate hazardous materials as defined in title 49 of the code of Federal Regulations. Received Subject to the classifications and lawfully filed tariffs in effect on the date of issued of this billing of lading, the properly described above in apparent good order, expect as noted (contents and conditions of contents of packages unknown) marked, consigned, and destined as indicated above which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of the said property over all or any portion of the said route to destination , and as to each party at any time interested in all or any said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Stright Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification of tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.

**Carrier:**

This is to certify that the above named materials are properly classified, described, packaged, and labeled and are in proper condition for transportation according to the applicable regulations of the department of Transportation.

**Per** _____ **Placards Required?** Yes / No **Supplied?** Yes / No

# P A C K I N G  L I S T

COLLOID ENVIRONMENTAL TECH LLC
2870 FORBS AVENUE
HOFFMAN ESTATES IL 60192

ORDER NO:.. 031527604
ORDER DATE: 5/05/2015
SHIP DATE:. 6/15/2015

SOLD TO: 1823
ESI
7943 PECUE LANE

BATON ROUGE LA 70809

SHIP FROM:. CETCO LOVELL PLANT
FRT TERMS:. PREPAID & ADD
SHIP VIA:.. AMERICO LOGISTICS

SHIP TO: 208
HONEYWELL CHRONIUM AREA
60 KELLOGG STREET
attn: CAROLINE PANICO
630-669-4257
JERSEY CITY NJ 07305

PO: 21574

| PRODUCT | SIZE | U/M | LOT # | ROLL# | LNGTH | WIDTH | SHIP QTY | WEIGHT |
|---|---|---|---|---|---|---|---|---|
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004065 | 150.0 | 14.5 | 2175.0 | 3115.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004067 | 150.0 | 14.5 | 2175.0 | 3155.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004069 | 150.0 | 14.5 | 2175.0 | 3180.0 |
| LO-BENTOMAT DN | | SFT | SF 201524LO | 00004083 | 150.0 | 14.5 | 2175.0 | 3340.0 |
| | | | | | | | 8700.0 | |

ORDER TOTALS..... 12790.0

TOTAL ITEMS..... 4

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 33 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/7/15 |
| QC Inspection by: CP | | QC Date: 7/6/15 | | Inv. Or Packing Slip No.: C00008103 | | Inv. Or Packing Slip Date: 7/2/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (96,570 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Landstar | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008103 | Freight Bill (Pro) No.: Packing List Attached | Weight: 25,658 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008103
Ship Date: 7/2/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010001 | 3,625.00 |
| 2 | 0065211010002 | 3,625.00 |
| 3 | 0065211010003 | 3,625.00 |
| 4 | 0065211010004 | 3,625.00 |
| 5 | 0065211010005 | 3,625.00 |
| 6 | 0065211010006 | 3,625.00 |
| 7 | 0065211010007 | 3,625.00 |
| 8 | 0065211010008 | 3,625.00 |
| 9 | 0065211010009 | 3,625.00 |
| 10 | 0065211010010 | 3,625.00 |
| 11 | 0065211010011 | 3,625.00 |
| 12 | 0065211010012 | 3,625.00 |
| 13 | 0065211010013 | 3,625.00 |
| 14 | 0065211010014 | 3,625.00 |
| 15 | 0065211010015 | 3,625.00 |
| 16 | 0065211010016 | 3,625.00 |
| 17 | 0065211010017 | 3,625.00 |
| 18 | 0065211010018 | 3,625.00 |
| 19 | 0065211010019 | 3,625.00 |
| 20 | 0065211010020 | 3,625.00 |
| 21 | 0065211010021 | 3,625.00 |
| 22 | 0065211010022 | 3,625.00 |
| 23 | 0065211010023 | 3,625.00 |
| 24 | 0065211010024 | 2,320.00 |
| 25 | 0065211010025 | 3,625.00 |
| 26 | 0065211010026 | 3,625.00 |
| 27 | 0065211010027 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 96,570.00
Total Weight (lbs): 25,658.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Landstar
Date: 7/2/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5487399

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02373 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 33 |
| Address: 335 Athena Drive – Warehouse A001, Athens, GA 30601 | | | | | | | | | Date: 6/29/15 |
| QC Inspection by: CP | | QC Date: 6/29/15 | | Inv. Or Packing Slip No.: BOL-48066 | | Inv. Or Packing Slip Date: 6/26/15 | | | PO Number: 8140C-080 (IWT/Cargo-Guard) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | | | | 25 | 25 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 25 | Rolls | SKAPS GE116 – 180 x 360 (16 oz/sy non- woven geotextile) (15,000 square yards) | 0 | 0 |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: SKAPS Industries | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.: | Freight Bill (Pro) No.: 48066 Packing List Attached | Weight: 15,292 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# Straight Bill of Lading

**Original - Not Negotiable**

**SKAPS Industries**
335 Athena Drive - Warehouse A001
Athens, GA 30601
UNITED STATES

Phone: 706-354-3700
Fax: 706-354-3737

| | |
|---|---|
| **Bill of Lading # DDA:** | 048066 |
| **BOL Date:** | 6/26/15 |
| **Sales Order # ORA:** | 038335 |
| **Customer PO #:** | 20252 |

**Prepay & Add**

| **Sold To:** | **Ship To:** |
|---|---|
| **Iwt/Cargo-Guard**<br>P.O. Box 454<br>Waretown, NJ, 08758<br>UNITED STATES | **Entact**<br>60 Kellogg St.<br>Jersey City, NJ 07305<br>UNITED STATES<br>Attn: Dan Harris<br>Phone: 405-206-4659 |

| **Trailer #** 6 | **Seal #** N/A | **Carrier** Medallion Transport & Logistic |
|---|---|---|

| Ln | Product | No. of Rolls | Weight (LBS) | Square Yards |
|---|---|---|---|---|
| 1 | GE116-180 x 360 | 25 | 15,292 | 15,000.00 |
| | | **25** | **15,292** | **15,000.00** |

## Comments:

**Any discrepancies must be reported, within 3 days of receipt of goods, to SKAPS Industries**

**Required delivery dates are subject to change.**

Construction job site delivery

Customer has equipment to off-load truck

Received at Athens, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route, to destination and as to each party at any time interested in all or any of said property, that every service performed hereunder shall be subject to either: (a) if the shipper noted herein is SKAPS Industries, as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the contract for truck transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries, then SKAPS Industries is acting solely as the agent for the denoted Shipper and thus every aspect of the service to be performed hereunder between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff, if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper, in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation Carrier, having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries, subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

| | |
|---|---|
| SHIPPER **SKAPS Industries - Athens, GA 30601** | CARRIER |
| PER | PER |
| EMERGENCY RESPONSE TELEPHONE NUMBER **706-354-3700** | DATE |

TIME IN: 10:55 am TIME OUT: 11:30 am PRO #:

DRIVER NAME: DRIVER PHONE:

RECEIVED BY: _____ SIGN _____ PHONE# _____

# Packing List

## BOL NO. 48066

**Customer** 271
**Customer PO** 20252
**Customer Name** Iwt/Cargo-Guard
**Ship To** Entact
60 Kellogg St.
Jersey City,NJ 07305

**Order No** ORA-038335
**Due Date**
**Site Location** Athens Warehouse 01

| Item Number | # OF ROLLS | Product Quantity | Label |
|---|---|---|---|
| 1 GE116-180 x 360 | 25 | 15,000 Y2 | |
| 38335.1 | 1 | 600 Y2 | 0001 |
| 38335.2 | 1 | 600 Y2 | 0001 |
| 38335.3 | 1 | 600 Y2 | 0001 |
| 38335.4 | 1 | 600 Y2 | 0001 |
| 38335.5 | 1 | 600 Y2 | 0001 |
| 38335.6 | 1 | 600 Y2 | 0001 |
| 38335.7 | 1 | 600 Y2 | 0001 |
| 38335.8 | 1 | 600 Y2 | 0001 |
| 38335.9 | 1 | 600 Y2 | 0001 |
| 38335.10 | 1 | 600 Y2 | 0001 |
| 38335.11 | 1 | 600 Y2 | 0001 |
| 38335.12 | 1 | 600 Y2 | 0001 |
| 38335.13 | 1 | 600 Y2 | 0001 |
| 38335.14 | 1 | 600 Y2 | 0001 |
| 38335.15 | 1 | 600 Y2 | 0001 |
| 38335.16 | 1 | 600 Y2 | 0001 |
| 38335.17 | 1 | 600 Y2 | 0001 |
| 38335.18 | 1 | 600 Y2 | 0001 |
| 38335.19 | 1 | 600 Y2 | 0001 |
| 38335.20 | 1 | 600 Y2 | 0001 |
| 38335.21 | 1 | 600 Y2 | 0001 |
| 38335.22 | 1 | 600 Y2 | 0001 |
| 38335.23 | 1 | 600 Y2 | 0001 |
| 38335.24 | 1 | 600 Y2 | 0001 |
| 38335.25 | 1 | 600 Y2 | 0001 |

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 34 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/7/15 |
| QC Inspection by: CP | | QC Date: 7/6/15 | | Inv. Or Packing Slip No.: C00008112 | | Inv. Or Packing Slip Date: 7/2/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (98,600 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Landmark | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008112 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,540 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

**STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE**

# SKAPS Industries

571 Industrial Parkway
Commerce, GA 30529
Ph: 706-336-7000 Fax: 706-336-7007

Bill of Lading # : C00008112
Ship Date : 7/2/2015
Sales Order #: C002021
Customer Name : ESI
Cust. P.O. # : 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal # :

SHIP-TO:
Project: Honeywell Chronium Area, NJ
Address: 60 Kellogg St
City, State, Zip : Jersey City, NJ 07605
Contact: Caroline Panico
Phone: 630-669-4257

**Product Code: TN**

| No | Roll# | Sq. Ft. |
|---|---|---|
| 1 | 0065211010028 | 3625 |
| 2 | 0065211010029 | 3625 |
| 3 | 0065211010030 | 3625 |
| 4 | 0065211010031 | 3625 |
| 5 | 0065211010032 | 3625 |
| 6 | 0065211010033 | 3625 |
| 7 | 0065211010034 | 3625 |
| 8 | 0065211010035 | 3625 |
| 9 | 0065211010036 | 3625 |
| 10 | 0065211010037 | 3625 |
| 11 | 0065211010038 | 3625 |
| 12 | 0065211010039 | 3625 |
| 13 | 0065211010040 | 4350 |
| 14 | 0065211010041 | 3625 |
| 15 | 0065211010042 | 3625 |
| 16 | 0065211010043 | 3625 |
| 17 | 0065211010044 | 3625 |
| 18 | 0065211010045 | 3625 |
| 19 | 0065211010046 | 3625 |
| 20 | 0065211010047 | 3625 |
| 21 | 0065211010048 | 3625 |
| 22 | 0065211010049 | 3625 |
| 23 | 0065211010050 | 3625 |
| 24 | 0065211010051 | 3625 |
| 25 | 0065211010052 | 3625 |
| 26 | 0065211010053 | 3625 |
| 27 | 0065211010054 | 3625 |
| Total Rolls : | | 27 |
| Total Sq. Feet: | | 98,600.00 |
| Total Weight (lbs): | | 29,540.00 |

Bags of ties : 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE , GA 30529

**ATTN RECEIVER : Please sign below if you have received the above mentioned items and any discrepancies must be reported to SKAPS Industries within 7 days of receipt of goods.**

| Receiver Print Name | Receiver's Signature |
|---|---|
| Received Date | Receiver's Company Name : |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings : _____
Driver's Name : _____
Driver's Sign : _____
Driver's Cell Phone # : _____
Trucking Co. : _____
Trucking Co. Phone # : _____
Broker : Landmark
Date : 7/2/2015
Truck Departure Time : _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5487484

**CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY**

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed hereunder shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for Truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be performed hereunder between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this is a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries. Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 35 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/8/15 |
| QC Inspection by: CP | | QC Date: 7/8/15 | | Inv. Or Packing Slip No.: C00008122 | | Inv. Or Packing Slip Date: 7/6/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Millennium Trucking | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008122 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,628 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008122
Ship Date: 7/6/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: Edwin Diaz

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010055 | 3,625.00 |
| 2 | 0065211010056 | 3,625.00 |
| 3 | 0065211010057 | 3,625.00 |
| 4 | 0065211010058 | 3,625.00 |
| 5 | 0065211010059 | 3,625.00 |
| 6 | 0065211010060 | 3,625.00 |
| 7 | 0065211010061 | 3,625.00 |
| 8 | 0065211010062 | 3,625.00 |
| 9 | 0065211010063 | 3,625.00 |
| 10 | 0065211010064 | 3,625.00 |
| 11 | 0065211010065 | 3,625.00 |
| 12 | 0065211010066 | 3,625.00 |
| 13 | 0065211010067 | 3,625.00 |
| 14 | 0065211010068 | 3,625.00 |
| 15 | 0065211010069 | 3,625.00 |
| 16 | 0065211010070 | 3,625.00 |
| 17 | 0065211010071 | 3,625.00 |
| 18 | 0065211010072 | 3,625.00 |
| 19 | 0065211010073 | 3,625.00 |
| 20 | 0065211010074 | 3,625.00 |
| 21 | 0065211010075 | 3,625.00 |
| 22 | 0065211010076 | 3,625.00 |
| 23 | 0065211010077 | 3,625.00 |
| 24 | 0065211010078 | 3,625.00 |
| 25 | 0065211010079 | 3,625.00 |
| 26 | 0065211010080 | 3,625.00 |
| 27 | 0065211010081 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 26,628.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items.**
**Driver's Sign:** Eric Brooks

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: Eric Brooks
Driver's Sign: Eric Brooks
Driver's Cell Phone #: 478-244-8201
Trucking Co.: Millennium Trucking
Trucking Co. Phone #: 770-817-1790
Broker: ATS Logistics
Date: 7/6/15
Truck Departure Time: 3:15 pm

**Comments:**
Driver please call 24 hours prior to delivery
Freight view shipper # : 5487537

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 36 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/8/15 |
| QC Inspection by: CP | | QC Date: 7/8/15 | | Inv. Or Packing Slip No.: C00008137 | | Inv. Or Packing Slip Date: 7/7/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Universal truckload, Inc | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008137 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,130 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008137
Ship Date: 7/7/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: Sara Pauly

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010082 | 3,625.00 |
| 2 | 0065211010083 | 3,625.00 |
| 3 | 0065211010084 | 3,625.00 |
| 4 | 0065211010085 | 3,625.00 |
| 5 | 0065211010086 | 3,625.00 |
| 6 | 0065211010087 | 3,625.00 |
| 7 | 0065211010088 | 3,625.00 |
| 8 | 0065211010089 | 3,625.00 |
| 9 | 0065211010090 | 3,625.00 |
| 10 | 0065211010091 | 3,625.00 |
| 11 | 0065211010092 | 3,625.00 |
| 12 | 0065211010093 | 3,625.00 |
| 13 | 0065211010094 | 3,625.00 |
| 14 | 0065211010095 | 3,625.00 |
| 15 | 0065211010096 | 3,625.00 |
| 16 | 0065211010097 | 3,625.00 |
| 17 | 0065211010098 | 3,625.00 |
| 18 | 0065211010099 | 3,625.00 |
| 19 | 0065211010100 | 3,625.00 |
| 20 | 0065211010101 | 3,625.00 |
| 21 | 0065211010102 | 3,625.00 |
| 22 | 0065211010103 | 3,625.00 |
| 23 | 0065211010104 | 3,625.00 |
| 24 | 0065211010105 | 3,625.00 |
| 25 | 0065211010106 | 3,625.00 |
| 26 | 0065211010107 | 3,625.00 |
| 27 | 0065211010108 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 26,130.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:**

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name:
Driver's Sign:
Driver's Cell Phone #: 254-541-7655
Trucking Co.: Emt Trucking LLC
Trucking Co. Phone #: 254-541-7655
Broker: Universal Truckload, Inc.
Date: 7/7/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5487538

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 37 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/10/15 |
| QC Inspection by: CP | | QC Date: 7/10/15 | | Inv. Or Packing Slip No.: C00008143 | | Inv. Or Packing Slip Date: 7/7/15 | | | PO Number: Environmental Specialties Inc. (ESI) |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Liberty Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008143 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,033 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008143
Ship Date: 7/7/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER:
SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010109 | 3,625.00 |
| 2 | 0065211010110 | 3,625.00 |
| 3 | 0065211010111 | 3,625.00 |
| 4 | 0065211010112 | 3,625.00 |
| 5 | 0065211010113 | 3,625.00 |
| 6 | 0065211010114 | 3,625.00 |
| 7 | 0065211010115 | 3,625.00 |
| 8 | 0065211010116 | 3,625.00 |
| 9 | 0065211010117 | 3,625.00 |
| 10 | 0065211010118 | 3,625.00 |
| 11 | 0065211010119 | 3,625.00 |
| 12 | 0065211010120 | 3,625.00 |
| 13 | 0065211010121 | 3,625.00 |
| 14 | 0065211010122 | 3,625.00 |
| 15 | 0065211010123 | 3,625.00 |
| 16 | 0065211010124 | 3,625.00 |
| 17 | 0065211010125 | 3,625.00 |
| 18 | 0065211010126 | 3,625.00 |
| 19 | 0065211010127 | 3,625.00 |
| 20 | 0065211010128 | 3,625.00 |
| 21 | 0065211010129 | 3,625.00 |
| 22 | 0065211010130 | 3,625.00 |
| 23 | 0065211010131 | 3,625.00 |
| 24 | 0065211010132 | 3,625.00 |
| 25 | 0065211010133 | 3,625.00 |
| 26 | 0065211010134 | 3,625.00 |
| 27 | 0065211010135 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 26,033.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**
**Driver's Sign:**

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries witnin 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**
1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.: LIBERTY LOGISTICS
Trucking Co. Phone #:
Broker: Meranu Leasing Inc. DBA Liberty Logistics
Date: 7/7/15
Truck Departure Time:

**Comments:**
Driver please call 24 hours prior to delivery
Freight view shipper # : 5487504

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) If the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occuring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 38 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/14/15 |
| QC Inspection by: CP | | QC Date: 7/15/15 | | Inv. Or Packing Slip No.: C00008174 | | Inv. Or Packing Slip Date: 7/10/15 | | | PO Number: IWT/Cargo-Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,040 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Load Pro | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008174 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,692 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008174
Ship Date: 7/10/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010002 | 2,800.00 |
| 2 | 0064021010003 | 2,800.00 |
| 3 | 0064021010004 | 2,800.00 |
| 4 | 0064021010005 | 2,800.00 |
| 5 | 0064021010006 | 2,800.00 |
| 6 | 0064021010007 | 2,240.00 |
| 7 | 0064021010008 | 2,800.00 |
| 8 | 0064021010009 | 2,800.00 |
| 9 | 0064021010010 | 2,800.00 |
| 10 | 0064021010011 | 2,800.00 |
| 11 | 0064021010012 | 2,800.00 |
| 12 | 0064021010013 | 2,800.00 |
| 13 | 0064021010014 | 2,800.00 |
| 14 | 0064021010015 | 2,800.00 |
| 15 | 0064021010016 | 2,800.00 |
| 16 | 0064021010017 | 2,800.00 |
| 17 | 0064021010018 | 2,800.00 |
| 18 | 0064021010019 | 2,800.00 |
| 19 | 0064021010020 | 2,240.00 |
| 20 | 0064021010021 | 3,360.00 |
| 21 | 0064021010022 | 2,800.00 |
| 22 | 0064021010023 | 2,800.00 |
| 23 | 0064021010024 | 2,800.00 |
| 24 | 0064021010025 | 2,800.00 |
| 25 | 0064021010026 | 2,800.00 |
| 26 | 0064021010027 | 2,800.00 |
| 27 | 0064021010028 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,040.00
Total Weight (lbs): 28,692.00

Bags of Ties: 2

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Load Pro
Date: 7/10/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5514893

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 39 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/14/15 |
| QC Inspection by: CP | | QC Date: 7/15/15 | | Inv. Or Packing Slip No.: C00008181 | | Inv. Or Packing Slip Date: 7/13/15 | | | PO Number: IWT/Cargo-Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,390 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: TQL | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008181 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,911 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008181
Ship Date: 7/13/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010029 | 2,800.00 |
| 2 | 0064021010030 | 2,800.00 |
| 3 | 0064021010031 | 2,660.00 |
| 4 | 0064021010032 | 2,800.00 |
| 5 | 0064021010033 | 2,800.00 |
| 6 | 0064021010034 | 2,800.00 |
| 7 | 0064021010035 | 2,800.00 |
| 8 | 0064021010036 | 2,800.00 |
| 9 | 0064021010037 | 2,730.00 |
| 10 | 0064021010038 | 2,800.00 |
| 11 | 0064021010039 | 2,800.00 |
| 12 | 0064021010040 | 2,800.00 |
| 13 | 0064021010041 | 2,800.00 |
| 14 | 0064021010042 | 2,800.00 |
| 15 | 0064021010043 | 2,800.00 |
| 16 | 0064021010044 | 2,800.00 |
| 17 | 0064021010045 | 2,800.00 |
| 18 | 0064021010046 | 2,800.00 |
| 19 | 0064021010047 | 2,800.00 |
| 20 | 0064021010048 | 2,800.00 |
| 21 | 0064021010049 | 2,800.00 |
| 22 | 0064021010050 | 2,800.00 |
| 23 | 0064021010051 | 2,800.00 |
| 24 | 0064021010052 | 2,800.00 |
| 25 | 0064021010053 | 2,800.00 |
| 26 | 0064021010054 | 2,800.00 |
| 27 | 0064021010055 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,390.00
Total Weight (lbs): 28,911.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name _____ Receiver's Signature _____

Receive Date _____ Receiver's Company Name _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: TQL
Date: 7/13/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5521502

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 40 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008185 | | Inv. Or Packing Slip Date: 7/13/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (97,875 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Landstar | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008185 | Freight Bill (Pro) No.: Packing List Attached | Weight: 27,625 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

7/15

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008185
Ship Date: 7/13/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010140 | 3,625.00 |
| 2 | 0065211010141 | 3,625.00 |
| 3 | 0065211010142 | 3,625.00 |
| 4 | 0065211010143 | 3,625.00 |
| 5 | 0065211010144 | 3,625.00 |
| 6 | 0065211010145 | 3,625.00 |
| 7 | 0065211010146 | 3,625.00 |
| 8 | 0065211010147 | 3,625.00 |
| 9 | 0065211010148 | 3,625.00 |
| 10 | 0065211010149 | 3,625.00 |
| 11 | 0065211010150 | 3,625.00 |
| 12 | 0065211010151 | 3,625.00 |
| 13 | 0065211010152 | 3,625.00 |
| 14 | 0065211010153 | 3,625.00 |
| 15 | 0065211010154 | 3,625.00 |
| 16 | 0065211010155 | 3,625.00 |
| 17 | 0065211010156 | 3,625.00 |
| 18 | 0065211010157 | 3,625.00 |
| 19 | 0065211010158 | 3,625.00 |
| 20 | 0065211010159 | 3,625.00 |
| 21 | 0065211010160 | 3,625.00 |
| 22 | 0065211010161 | 3,625.00 |
| 23 | 0065211010162 | 3,625.00 |
| 24 | 0065211010163 | 3,625.00 |
| 25 | 0065211010164 | 3,625.00 |
| 26 | 0065211010165 | 3,625.00 |
| 27 | 0065211010166 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 97,875.00
Total Weight (lbs): 27,625.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Landstar
Date: 7/13/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery.
Freight view shipper # : 5523988

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 41 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008187 | | Inv. Or Packing Slip Date: 7/13/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer) (95,845 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Medallion Transport and Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008187 | Freight Bill (Pro) No.: Packing List Attached | Weight: 26,210 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008187
Ship Date: 7/13/15
Sales Order #: C002021
Custorner Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010136 | 3,625.00 |
| 2 | 0065211010137 | 3,625.00 |
| 3 | 0065211010138 | 3,625.00 |
| 4 | 0065211010139 | 3,625.00 |
| 5 | 0065211010167 | 3,625.00 |
| 6 | 0065211010168 | 3,625.00 |
| 7 | 0065211010169 | 3,625.00 |
| 8 | 0065211010170 | 3,625.00 |
| 9 | 0065211010171 | 3,625.00 |
| 10 | 0065211010172 | 3,625.00 |
| 11 | 0065211010173 | 3,625.00 |
| 12 | 0065211010174 | 3,625.00 |
| 13 | 0065211010175 | 1,595.00 |
| 14 | 0065211010176 | 3,625.00 |
| 15 | 0065211010177 | 3,625.00 |
| 16 | 0065211010178 | 3,625.00 |
| 17 | 0065211010179 | 3,625.00 |
| 18 | 0065211010180 | 3,625.00 |
| 19 | 0065211010181 | 3,625.00 |
| 20 | 0065211010182 | 3,625.00 |
| 21 | 0065211010183 | 3,625.00 |
| 22 | 0065211010184 | 3,625.00 |
| 23 | 0065211010185 | 3,625.00 |
| 24 | 0065211010186 | 3,625.00 |
| 25 | 0065211010187 | 3,625.00 |
| 26 | 0065211010188 | 3,625.00 |
| 27 | 0065211010189 | 3,625.00 |

Total Rolls: 27
Total Sq Feet: 95,845.00
Total Weight (lbs): 26,210.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Medallion Transport & Logistics LLC.
Date: 7/13/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5516945

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 42 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008193 | | Inv. Or Packing Slip Date: 7/14/15 | | | PO Number: IWT CargoGuard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,530 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Liberty Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008193 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,055 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008193
Ship Date: 7/14/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: Dhiru Patel

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010001 | 2,800.00 |
| 2 | 0064021010057 | 2,800.00 |
| 3 | 0064021010058 | 2,730.00 |
| 4 | 0064021010059 | 2,800.00 |
| 5 | 0064021010060 | 2,800.00 |
| 6 | 0064021010061 | 2,800.00 |
| 7 | 0064021010062 | 2,800.00 |
| 8 | 0064021010063 | 2,800.00 |
| 9 | 0064021010064 | 2,800.00 |
| 10 | 0064021010065 | 2,800.00 |
| 11 | 0064021010066 | 2,800.00 |
| 12 | 0064021010067 | 2,800.00 |
| 13 | 0064021010068 | 2,800.00 |
| 14 | 0064021010069 | 2,800.00 |
| 15 | 0064021010070 | 2,800.00 |
| 16 | 0064021010071 | 2,800.00 |
| 17 | 0064021010072 | 2,800.00 |
| 18 | 0064021010073 | 2,800.00 |
| 19 | 0064021010074 | 2,800.00 |
| 20 | 0064021010075 | 2,800.00 |
| 21 | 0064021010076 | 2,800.00 |
| 22 | 0064021010077 | 2,800.00 |
| 23 | 0064021010078 | 2,800.00 |
| 24 | 0064021010079 | 2,800.00 |
| 25 | 0064021010080 | 2,800.00 |
| 26 | 0064021010081 | 2,800.00 |
| 27 | 0064021010082 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,530.00
Total Weight (lbs): 29,055.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** Curtis Davis

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: Curtis Davis
Driver's Sign: CURTIS DAVIS
Driver's Cell Phone #: 601339410 9
Trucking Co.: LIBERTY LOGISTIC
Trucking Co. Phone #: 6[illegible]3394105
Broker: Meranu Leasing Inc. DBA Liberty Logistics
Date: 7/14/15
Truck Departure Time:

**Comments:**
Driver please call 24 hours prior to delivery
Freight view shipper # : 5523946

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 43 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008200 | | Inv. Or Packing Slip Date: 7/15/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 16 | 18 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 16 | Rolls | TN 220-2-6 Geocomposite (Gas Vent Layer)<br>(75,530 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Coyote | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008200 | Freight Bill (Pro) No.:<br>Packing List Attached | Weight:<br>16,243 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

7/14

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008200
Ship Date: 7/15/15
Sales Order #: C002021
Customer Name: Environmental Specialties Int'l, Inc-ESI
Cust. P.O. #: 21702
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Honeywell Chromium Area, NJ
Address: 60 Kellogg Street
City, State, Zip: Jersey City, NJ, 07305
Contact: Caroline Panico
Phone: 630-669-4257

SIGN HERE FOR SHIPPER: Julio Rodriguez

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Product Code: TN220-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0065211010190 | 3,480.00 |
| 2 | 0065211010191 | 3,480.00 |
| 3 | 0065211010192 | 3,480.00 |
| 4 | 0065211010193 | 3,480.00 |
| 5 | 0065211010194 | 3,480.00 |
| 6 | 0065211010195 | 3,480.00 |
| 7 | 0065211010196 | 3,625.00 |
| 8 | 0065211010197 | 3,625.00 |
| 9 | 0065211010198 | 3,625.00 |
| 10 | 0065211010199 | 3,625.00 |
| 11 | 0065211010200 | 3,625.00 |
| 12 | 0065211010201 | 3,625.00 |
| 13 | 0065211010202 | 3,625.00 |
| 14 | 0065211010203 | 3,625.00 |
| 15 | 0065211010204 | 3,625.00 |
| 16 | 0065211010205 | 3,625.00 |

Total Rolls: 16
Total Sq Feet: 57,130.00
Total Weight (lbs): 16,243.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** x

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: FLOYD RISS
Driver's Sign:
Driver's Cell Phone #: 404 980 3304
Trucking Co.: FSK
Trucking Co. Phone #: SAME
Broker: Coyote 3:00 PM
Date: 7/15/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5516953

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 44 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008197 | | Inv. Or Packing Slip Date: 7/15/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 29 | 31 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 29 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (78,540 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Freightquote | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008197 | Freight Bill (Pro) No.: Packing List Attached | Weight: 30,326 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

7/16

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008197
Ship Date: 7/15/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: Roohi Patel

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010056 | 2,240.00 |
| 2 | 0064021010110 | 2,800.00 |
| 3 | 0064021010111 | 2,240.00 |
| 4 | 0064021010112 | 3,150.00 |
| 5 | 0064021010113 | 2,800.00 |
| 6 | 0064021010114 | 2,800.00 |
| 7 | 0064021010115 | 2,800.00 |
| 8 | 0064021010116 | 2,800.00 |
| 9 | 0064021010117 | 2,800.00 |
| 10 | 0064021010118 | 2,800.00 |
| 11 | 0064021010119 | 2,800.00 |
| 12 | 0064021010120 | 2,800.00 |
| 13 | 0064021010121 | 3,430.00 |
| 14 | 0064021010122 | 2,170.00 |
| 15 | 00640210101221 | 1,120.00 |
| 16 | 0064021010123 | 2,800.00 |
| 17 | 0064021010124 | 2,800.00 |
| 18 | 0064021010125 | 2,590.00 |
| 19 | 0064021010126 | 2,870.00 |
| 20 | 0064021010127 | 3,080.00 |
| 21 | 0064021010128 | 2,450.00 |
| 22 | 0064021010129 | 2,800.00 |
| 23 | 0064021010130 | 2,800.00 |
| 24 | 0064021010131 | 2,800.00 |
| 25 | 0064021010132 | 2,800.00 |
| 26 | 0064021010133 | 2,800.00 |
| 27 | 0064021010134 | 2,800.00 |
| 28 | 0064021010135 | 2,800.00 |
| 29 | 0064021010136 | 2,800.00 |

Total Rolls: 29
Total Sq Feet: 78,540.00
Total Weight (lbs): 30,326.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.:
Trucking Co. Phone #:
Broker: Freightquote
Date: 7/15/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5530510

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive rpt

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 45 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/16/15 | | Inv. Or Packing Slip No.: C00008201 | | Inv. Or Packing Slip Date: 7/15/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,600 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Coyote | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008201 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,088 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

7/16

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008201
Ship Date: 7/15/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: Rooshi Patel
SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010083 | 2,800.00 |
| 2 | 0064021010084 | 2,800.00 |
| 3 | 0064021010085 | 2,800.00 |
| 4 | 0064021010086 | 2,800.00 |
| 5 | 0064021010087 | 2,800.00 |
| 6 | 0064021010088 | 2,800.00 |
| 7 | 0064021010089 | 2,800.00 |
| 8 | 0064021010090 | 2,800.00 |
| 9 | 0064021010091 | 2,800.00 |
| 10 | 0064021010092 | 2,800.00 |
| 11 | 0064021010093 | 2,800.00 |
| 12 | 0064021010094 | 2,800.00 |
| 13 | 0064021010095 | 2,800.00 |
| 14 | 0064021010096 | 2,800.00 |
| 15 | 0064021010097 | 2,800.00 |
| 16 | 0064021010098 | 2,800.00 |
| 17 | 0064021010099 | 2,800.00 |
| 18 | 0064021010100 | 2,800.00 |
| 19 | 0064021010101 | 2,800.00 |
| 20 | 0064021010102 | 2,800.00 |
| 21 | 0064021010103 | 2,800.00 |
| 22 | 0064021010104 | 2,800.00 |
| 23 | 0064021010105 | 2,800.00 |
| 24 | 0064021010106 | 2,800.00 |
| 25 | 0064021010107 | 2,800.00 |
| 26 | 0064021010108 | 2,800.00 |
| 27 | 0064021010109 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,600.00
Total Weight (lbs): 29,088.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon-Fri 6am-2pm
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Coyote
Date: 7/15/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5530505

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive.rpt

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02372 |
| Received From: Agru/America Inc. | | | | | | | | | Receiving Report Number: 46 |
| Address: 500 Garrison Road, Georgetown, SC 29440 | | | | | | | | | Date: 7/17/15 |
| QC Inspection by: CP | | QC Date: 7/17/15 | | Inv. Or Packing Slip No.: 046962 | | Inv. Or Packing Slip Date: 7/16/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Spools | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 12 | | | 12 | 24 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 12 | Rolls | 60 mil LLDPE MicroSpike Geomembrane (139,380 square feet) | 0 | 0 |
| 2 | 12 | Spools | LLDPE Welding Rod | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: LTL | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:046962 | Freight Bill (Pro) No.: Packing List Attached | Weight: 45,500 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# TRAIGHT BILL OF LADING - SHORT FORM - ORIGINAL - NOT NEGOTIABLE

B/L NO. 046962

| AME OF CARRIER | CARRIER'S NO. | DATE |
|---|---|---|
| BEST WAY FRT LTL | | 7/16/2015 |

CEIVED, subject to the classifications and lawfully filed tariffs in effect on the date of issue of this Bill of Lading,
property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below which said carrier (the word carrier beir
derstood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver t
other carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any
d property, that every service to be performed hereunder, shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the da
reof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
**ipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification or tariff which governs the transportation of this shipment, and the said terms and conditio**
**hereby agreed to by the shipper and accepted for himself and his assigns.**

| | |
|---|---|
| ROM: SHIPPER (ORIGIN) | **AGRU/AMERICA, INC.**<br>500 GARRISON ROAD<br>GEORGETOWN, SOUTH CAROLINA 29440<br>(843) 546-0600 |
| EMERGENCY RESPONSE PHONE NO. | |
| TO: CONSIGNEE | HONEYWELL CHROMIUM AREA<br>ENVIRONMENTAL SPECIALTIES |
| STREET | 60 KELLOGG STREET |
| DESTINATION | JERSEY CITY, NJ 07305<br>DANIEL HARRIS 405-206-4659 |
| | ZIP |

| ELIVERING ARRIER | ROUTE | VEHICLE NUMBER |
|---|---|---|
| | | |

| NO. PACKAGES | + HM | KIND OF PACKAGE, DESCRIPTION OF ARTICLES SPECIAL MARKS AND EXCEPTIONS | *WEIGHT (SUBJECT TO CORR.) | CLASS OR RATE | ✓ | CHARGES (FOR CARRIER USE ONLY |
|---|---|---|---|---|---|---|
| 139,380<br>264 | | LL DBL MICRO 60MIL 23FT<br>WELD ROD MFG BLACK LDPE 5MM | | | | 36.923C<br>1706 |

| Item Key | Lot Number | Quantity |
|---|---|---|
| L-LL-MSDS-60-23 | G15C276054 | 11,615 |
| L-LL-MSDS-60-23 | G15C276055 | 11,615 |
| L-LL-MSDS-60-23 | G15C276057 | 11,615 |
| L-LL-MSDS-60-23 | G15C282013 | 11,615 |
| L-LL-MSDS-60-23 | G15C282014 | 11,615 |
| L-LL-MSDS-60-23 | G15C282017 | 11,615 |
| L-LL-MSDS-60-23 | G15C282020 | 11,615 |
| L-LL-MSDS-60-23 | G15C282023 | 11,615 |
| L-LL-MSDS-60-23 | G15C283027 | 11,615 |
| L-LL-MSDS-60-23 | G15C283028 | 11,615 |
| L-LL-MSDS-60-23 | G15C283029 | 11,615 |
| L-LL-MSDS-60-23 | G15C283030 | 11,615 |

Total Weight: ~~46,260 LB~~ 45,500 lbs.
Total Packages: ~~139,644~~ 12 Rolls
Order No.: 28919 Order Date: 05/04/15 Request Date: 06/30/15
Location: GTOWN P.O. No.: 21570
12 Spools - Weld Rod

**MIT C.O.D. TO:**
**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

**C.O.D.** Amt $

C.O.D. FEE
☑ Prepaid
☐ Collect $

the shipment moves between two ports by a carrier by ter, the law requires that the bill of lading shall state ether it is "carrier's or shipper's weight"

**hipper's imprint in lieu of stamp; not a part of bill of lading roved by the Interstate Commerce Commission**

NOTE: Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property.
**The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding**
$ per

Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement:
The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges
(Signature of Consignor)

**TOTAL CHARGES $**
Freight charges are PREPAID unless marked collect. ☐ Check box if charges are Collect

is is to certify that the above named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation, according to the applicable regulations of the Department of Transportation

Shipper, Per Agent, Per

manent post office address of shipper

Page 1 of 1

+ MARK WITH "X" TO DESIGNATE HAZARDOUS MATERIAL AS DEFINED IN TITLE 49 OF FEDERAL REGULATIONS.

hen transporting hazardous materials include the technical or chemical name for n.o.s. (not otherwise specified) or generic description of material with appropriate UN or NA number as defined in US DOT Emergency Response mmunication Standard (HM-126C). Provide emergency response phone number in case of incident or accident.

1

# Shipping Release

1706
369230

| OA # | 28919 | Date | 7/16/15 |
|---|---|---|---|

| Driver's Name/Truck Company | Customer | Destination | | | Pictures Taken |
|---|---|---|---|---|---|
| George Williams / LTL | Environmental Specialties | City: Jersey City | State: NJ | | YES ● NO |
| **Time In:** 8:57 | **Time Out:** 9:59 | Inspector: C.H. / J.S. | Loader: C.H. | | |

## Roll #

| | G | YEAR | | M | WK of YR | | DOW | ROLL # | | | External Visual | Straps OK | Core OK | Weld Rod OK |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | G | 1 | 5 | C | 2 | 7 | 6 | 0 | 5 | 4 | Yes ● No | Yes ● No | Yes ● No | Yes ● No |
| 2 | G | 1 | 5 | \| | 2 | 7 | 6 | 0 | 5 | 5 | Yes No | Yes No | Yes No | Yes No |
| 3 | G | 1 | 5 | \| | 2 | 7 | 6 | 0 | 5 | 7 | Yes No | Yes No | Yes No | Yes No |
| 4 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 1 | 3 | Yes No | Yes No | Yes No | Yes No |
| 5 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 1 | 4 | Yes No | Yes No | Yes No | Yes No |
| 6 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 1 | 7 | Yes No | Yes No | Yes No | Yes No |
| 7 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 2 | 0 | Yes No | Yes No | Yes No | Yes No |
| 8 | G | 1 | 5 | \| | 2 | 8 | 2 | 0 | 2 | 3 | Yes No | Yes No | Yes No | Yes No |
| 9 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 2 | 7 | Yes No | Yes No | Yes No | Yes No |
| 10 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 2 | 8 | Yes No | Yes No | Yes No | Yes No |
| 11 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 2 | 9 | Yes No | Yes No | Yes No | Yes No |
| 12 | G | 1 | 5 | \| | 2 | 8 | 3 | 0 | 3 | 0 | Yes No | Yes No | Yes No | Yes No |
| 13 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 14 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 15 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 16 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 17 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 18 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 19 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 20 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 21 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 22 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 23 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 24 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 25 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 26 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |
| 27 | G | 1 | 5 | | | | | | | | Yes No | Yes No | Yes No | Yes No |

## CONTAINER/MISC

CONTAINER#

TIES

WELD ROD

12 spools 5mm LC BIA
CFD810090

BENTONITE BAGS

STRAPS

PALLETS

| | |
|---|---|
| External Visual Check: | Clean Roll; Damage (Holes, Tears); Telescoping; Liner Defects (Volds, Bug Marks, Etc.) Legible Markings on Roll |
| Strap Check: | 6' Foot Spacing; Check for Wear, Cuts |
| Core Check: | Check for Craks, Defects |
| Weld Rod Check: | (If Necessary): Secure Load; Lot # on BOL; Check Type |
| Comments: | |

Revised 11/11/14

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02372 |
| Received From: Agru/America Inc. | | | | | | | | | Receiving Report Number: 47 |
| Address: 500 Garrison Road, Georgetown, SC 29440 | | | | | | | | | Date: 7/20/15 |
| QC Inspection by: CP | | QC Date: 7/20/15 | | Inv. Or Packing Slip No.: 046977 | | Inv. Or Packing Slip Date: 7/16/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Spools | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 12 | | | 12 | 24 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 12 | Rolls | 60 mil LLDPE MicroSpike Geomembrane (139,380 square feet) | 0 | 0 |
| 2 | 12 | Spools | LLDPE Welding Rod | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Best Way Freight | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:046977 | Freight Bill (Pro) No.: Packing List Attached | Weight: 45,500 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

# STRAIGHT BILL OF LADING - SHORT FORM - ORIGINAL - NOT NEGOTIABLE

B/L NO. 046977

| NAME OF CARRIER | CARRIER'S NO. | DATE |
|---|---|---|
| BEST WAY FRT Bishopville Spec. | | 7/16/2015 |

**RECEIVED, subject to the classifications and lawfully filed tariffs in effect on the date of issue of this Bill of Lading,**
the property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any of said property, that every service to be performed hereunder, shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
**Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification or tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.**

**FROM:**
SHIPPER
(ORIGIN)

**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

EMERGENCY RESPONSE PHONE NO.

**TO:**
CONSIGNEE HONEYWELL CHROMIUM AREA
ENVIRONMENTAL SPECIALTIES
STREET 60 KELLOGG STREET
JERSEY CITY, NJ 07305
DESTINATION DANIEL HARRIS 405-206-4659
ZIP

| DELIVERING CARRIER | ROUTE | VEHICLE NUMBER |
|---|---|---|
| | | |

| NO. PACKAGES | + HM | KIND OF PACKAGE, DESCRIPTION OF ARTICLES SPECIAL MARKS AND EXCEPTIONS | *WEIGHT (SUBJECT TO CORR.) | CLASS OR RATE | ✓ | CHARGES (FOR CARRIER USE ONLY) |
|---|---|---|---|---|---|---|
| 139,380 | | LL DBL MICRO 60MIL 23FT | | | | |

| Item Key | Lot Number | Quantity |
|---|---|---|
| L-LL-MSDS-60-23 | G15C276052 | 11,615 |
| L-LL-MSDS-60-23 | G15C276053 | 11,615 |
| L-LL-MSDS-60-23 | G15C276056 | 11,615 |
| L-LL-MSDS-60-23 | G15C277061 | 11,615 |
| L-LL-MSDS-60-23 | G15C277062 | 11,615 |
| L-LL-MSDS-60-23 | G15C277064 | 11,615 |
| L-LL-MSDS-60-23 | G15C282011 | 11,615 |
| L-LL-MSDS-60-23 | G15C282012 | 11,615 |
| L-LL-MSDS-60-23 | G15C282016 | 11,615 |
| L-LL-MSDS-60-23 | G15C282021 | 11,615 |
| L-LL-MSDS-60-23 | G15C283031 | 11,615 |
| L-LL-MSDS-60-23 | G15C283033 | 11,615 |

Total Weight: ~~45,996 LB~~ 45,500 lbs.
Total Packages: ~~139,380~~ 12 Rolls
Order No.: 28919 Order Date: 05/04/15 Request Date: 06/30/15
Location: GTOWN P.O. No.: 21570

**REMIT C.O.D. TO:**
AGRU/AMERICA, INC.
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

**C.O.D.** Amt $

**C.O.D. FEE**
☑ Prepaid
☐ Collect $

*If the shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's or shipper's weight".

† Shipper's imprint in lieu of stamp; not a part of bill of lading approved by the Interstate Commerce Commission.

NOTE: Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property.
**The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding**
$ per

Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement:
The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges.
(Signature of Consignor)

**TOTAL CHARGES $**

Freight charges are PREPAID unless marked collect. ☐ Check box if charges are Collect.

"This is to certify that the above named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation, according to the applicable regulations of the Department of Transportation".

Shipper, Per JB + Agent, Per Dan Beam

Page 1 of 1
Permanent post office address of shipper

**+ MARK WITH "X" TO DESIGNATE HAZARDOUS MATERIAL AS DEFINED IN TITLE 49 OF FEDERAL REGULATIONS.**
When transporting hazardous materials include the technical or chemical name for n.o.s. (not otherwise specified) or generic description of material with appropriate UN or NA number as defined in US DOT Emergency Response Communication Standard (HM-126C). Provide emergency response phone number in case of incident or accident.

1

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02372 |
| Received From: Agru/America Inc. | | | | | | | | | Receiving Report Number: 47 |
| Address: 500 Garrison Road, Georgetown, SC 29440 | | | | | | | | | Date: 7/21/15 |
| QC Inspection by: CP | | QC Date: 7/21/15 | | Inv. Or Packing Slip No.: 046973 | | Inv. Or Packing Slip Date: 7/16/15 | | | PO Number: ESI |
| Boxes | Barrels | Bags | Crates | Spools | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 12 | | | 12 | 24 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 12 | Rolls | 60 mil LLDPE MicroSpike Geomembrane (139,380 square feet) | 0 | 0 |
| 2 | 12 | Spools | LLDPE Welding Rod | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Best Way Freight | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:046973 | Freight Bill (Pro) No.:<br>Packing List Attached | Weight:<br>44,900 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

## STRAIGHT BILL OF LADING - SHORT FORM - ORIGINAL - NOT NEGOTIABLE

B/L NO. 046973

| NAME OF CARRIER | CARRIER'S NO. | DATE |
|---|---|---|
| BEST WAY FRT LTL | | 7/16/2015 |

**RECEIVED, subject to the classifications and lawfully filed tariffs in effect on the date of issue of this Bill of Lading,**
the property described below, in apparent good order, except as noted (contents and condition of contents of packages unknown), marked, consigned, and destined as indicated below which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination. It is mutually agreed as to each carrier of all or any of said property over all or any portion of said route to destination, and as to each party at any time interested in all or any of said property, that every service to be performed hereunder, shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Uniform Freight Classifications in effect on the date hereof, if this is a rail or a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment.
**Shipper hereby certifies that he is familiar with all the terms and conditions of the said bill of lading, set forth in the classification or tariff which governs the transportation of this shipment, and the said terms and conditions are hereby agreed to by the shipper and accepted for himself and his assigns.**

**FROM:**
SHIPPER
(ORIGIN)

**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

EMERGENCY RESPONSE PHONE NO.

**TO:**
CONSIGNEE HONEYWELL CHROMIUM AREA
ENVIRONMENTAL SPECIALTIES
STREET 60 KELLOGG STREET
JERSEY CITY, NJ 07305
DESTINATION DANIEL HARRIS 405-206-4659
ZIP

| DELIVERING CARRIER | ROUTE | VEHICLE NUMBER |
|---|---|---|
| | | |

| NO. PACKAGES | + HM | KIND OF PACKAGE, DESCRIPTION OF ARTICLES SPECIAL MARKS AND EXCEPTIONS | *WEIGHT (SUBJECT TO CORR.) | CLASS OR RATE | ✓ | CHARGES (FOR CARRIER USE ONLY) |
|---|---|---|---|---|---|---|
| 139,380<br>264 | | LL DBL MICRO 60MIL 23FT<br>WELD ROD MFG BLACK LDPE 5MM | | | | |

| Item Key | Lot Number | Quantity |
|---|---|---|
| L-LL-MSDS-60-23 | G15C276058 | 11,615 |
| L-LL-MSDS-60-23 | G15C277059 | 11,615 |
| L-LL-MSDS-60-23 | G15C277060 | 11,615 |
| L-LL-MSDS-60-23 | G15C277065 | 11,615 |
| L-LL-MSDS-60-23 | G15C282015 | 11,615 |
| L-LL-MSDS-60-23 | G15C282018 | 11,615 |
| L-LL-MSDS-60-23 | G15C282019 | 11,615 |
| L-LL-MSDS-60-23 | G15C282022 | 11,615 |
| L-LL-MSDS-60-23 | G15C283024 | 11,615 |
| L-LL-MSDS-60-23 | G15C283025 | 11,615 |
| L-LL-MSDS-60-23 | G15C283026 | 11,615 |
| L-LL-MSDS-60-23 | G15C283032 | 11,615 |

Total Weight: ~~46,260 LB~~ 44,900 lbs.
Total Packages: ~~139,644~~ 12 Rolls
Order No.: 28919 Order Date: 05/04/15 Request Date: 06/30/15
Location: GTOWN P.O. No.: 21570
12 Spools - Weld Rod

**REMIT C.O.D. TO:**
**AGRU/AMERICA, INC.**
500 GARRISON ROAD
GEORGETOWN, SOUTH CAROLINA 29440
(843) 546-0600

**C.O.D.** Amt $

**C.O.D. FEE**
☑ Prepaid
☐ Collect $

*If the shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's or shipper's weight".

† Shipper's imprint in lieu of stamp; not a part of bill of lading approved by the Interstate Commerce Commission.

NOTE: Where the rate is dependent on value, shippers are required to state specifically in writing the agreed or declared value of the property.
**The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding**
$ per

Subject to Section 7 of conditions, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement:
The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges.
(Signature of Consignor)

**TOTAL CHARGES $**
Freight charges are PREPAID unless marked collect. ☐ Check box if charges are Collect.

"This is to certify that the above named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation, according to the applicable regulations of the Department of Transportation".

Shipper, Per X Agent, Per

Page 1 of 1
Permanent post office address of shipper

**+ MARK WITH "X" TO DESIGNATE HAZARDOUS MATERIAL AS DEFINED IN TITLE 49 OF FEDERAL REGULATIONS.**
When transporting hazardous materials include the technical or chemical name for n.o.s. (not otherwise specified) or generic description of material with appropriate UN or NA number as defined in US DOT Emergency Response Communication Standard (HM-126C). Provide emergency response phone number in case of incident or accident.

1

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 49 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 9/30/15 |
| QC Inspection by: CP | | QC Date: 9/30/15 | | Inv. Or Packing Slip No.: C00008780 | | Inv. Or Packing Slip Date: 9/29/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,110 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Universal Truckload, Inc | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008780 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,827 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by: Date: | Entered by: Date: | Finalized by: Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008780
Ship Date: 9/29/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010137 | 2,800.00 |
| 2 | 0064021010138 | 2,800.00 |
| 3 | 0064021010139 | 2,800.00 |
| 4 | 0064021010140 | 2,800.00 |
| 5 | 0064021010141 | 2,800.00 |
| 6 | 0064021010142 | 2,800.00 |
| 7 | 0064021010143 | 2,800.00 |
| 8 | 0064021010144 | 2,800.00 |
| 9 | 0064021010145 | 1,960.00 |
| 10 | 0064021010146 | 2,800.00 |
| 11 | 0064021010147 | 2,800.00 |
| 12 | 0064021010148 | 2,800.00 |
| 13 | 0064021010149 | 2,800.00 |
| 14 | 0064021010150 | 2,800.00 |
| 15 | 0064021010151 | 2,800.00 |
| 16 | 0064021010152 | 2,800.00 |
| 17 | 0064021010153 | 2,800.00 |
| 18 | 0064021010154 | 2,800.00 |
| 19 | 0064021010155 | 2,800.00 |
| 20 | 0064021010156 | 2,800.00 |
| 21 | 0064021010157 | 2,800.00 |
| 22 | 0064021010158 | 2,800.00 |
| 23 | 0064021010159 | 2,800.00 |
| 24 | 0064021010160 | 2,800.00 |
| 25 | 0064021010161 | 2,800.00 |
| 26 | 0064021010162 | 2,800.00 |
| 27 | 0064021010163 | 3,150.00 |

Total Rolls: 27
Total Sq Feet: 75,110.00
Total Weight (lbs): 28,827.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Carolina Garcia | Carolina Garcia |
| Receive Date | Receiver's Company Name |
| 9-30-15 | ENTACT |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Universal Truckload, Inc.
Date: 9/29/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5848420

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries. Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns

Honeywell RES

Honeywell.com

# Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 50 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/19/15 |
| QC Inspection by: CP | | QC Date: 10/19/15 | | Inv. Or Packing Slip No.: C00008923 | | Inv. Or Packing Slip Date: 10/16/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,810 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Medallion Transport & Logistics, LLC | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008923 | Freight Bill (Pro) No.: Packing List Attached | Weight: 29,175 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008923
Ship Date: 10/16/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010191 | 2,800.00 |
| 2 | 0064021010192 | 3,010.00 |
| 3 | 0064021010193 | 2,800.00 |
| 4 | 0064021010194 | 2,800.00 |
| 5 | 0064021010195 | 2,800.00 |
| 6 | 0064021010196 | 2,800.00 |
| 7 | 0064021010197 | 2,800.00 |
| 8 | 0064021010198 | 2,800.00 |
| 9 | 0064021010199 | 2,800.00 |
| 10 | 0064021010200 | 2,800.00 |
| 11 | 0064021010201 | 2,800.00 |
| 12 | 0064021010202 | 2,800.00 |
| 13 | 0064021010203 | 2,800.00 |
| 14 | 0064021010204 | 2,800.00 |
| 15 | 0064021010205 | 2,800.00 |
| 16 | 0064021010206 | 2,800.00 |
| 17 | 0064021010207 | 2,800.00 |
| 18 | 0064021010208 | 2,800.00 |
| 19 | 0064021010209 | 2,800.00 |
| 20 | 0064021010210 | 2,800.00 |
| 21 | 0064021010211 | 2,800.00 |
| 22 | 0064021010213 | 2,800.00 |
| 23 | 0064021010214 | 2,800.00 |
| 24 | 0064021010215 | 2,800.00 |
| 25 | 0064021010216 | 2,800.00 |
| 26 | 0064021010217 | 2,800.00 |
| 27 | 0064021010218 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 75,810.00
Total Weight (lbs): 29,175.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Medallion Transport & Logistics LLC.
Date: 10/16/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5910099

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

COMShippingDefinitive rpt

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 51 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/19/15 |
| QC Inspection by: CP | | QC Date: 10/19/15 | | Inv. Or Packing Slip No.: C00008925 | | Inv. Or Packing Slip Date: 10/17/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (76,160 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Meranu Leasing Inc., DBA Liberty Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008925 | Freight Bill (Pro) No.: Packing List Attached | Weight: | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008925
Ship Date: 10/17/15
Sales Order #: C001905
Customer Name: lwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010219 | 2,800.00 |
| 2 | 0064021010220 | 2,940.00 |
| 3 | 0064021010221 | 2,800.00 |
| 4 | 0064021010222 | 2,800.00 |
| 5 | 0064021010223 | 2,800.00 |
| 6 | 0064021010224 | 2,030.00 |
| 7 | 0064021010225 | 2,800.00 |
| 8 | 0064021010226 | 2,800.00 |
| 9 | 0064021010227 | 2,800.00 |
| 10 | 0064021010228 | 2,800.00 |
| 11 | 0064021010229 | 2,800.00 |
| 12 | 0064021010230 | 2,800.00 |
| 13 | 0064021010231 | 2,800.00 |
| 14 | 0064021010232 | 2,800.00 |
| 15 | 0064021010233 | 2,800.00 |
| 16 | 0064021010234 | 2,800.00 |
| 17 | 0064021010235 | 2,800.00 |
| 18 | 0064021010236 | 2,940.00 |
| 19 | 0064021010237 | 2,800.00 |
| 20 | 0064021010238 | 3,010.00 |
| 21 | 0064021010239 | 2,800.00 |
| 22 | 0064021010240 | 2,940.00 |
| 23 | 0064021010241 | 2,800.00 |
| 24 | 0064021010242 | 3,500.00 |
| 25 | 0064021010243 | 2,800.00 |
| 26 | 0064021010244 | 2,800.00 |
| 27 | 0064021010245 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 76,160.00
Total Weight (lbs): 49,561.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: Meranu Leasing Inc. DBA Liberty Logistics
Date: 10/17/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919359

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries. Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 52 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/21/15 |
| QC Inspection by: CP | | QC Date: 10/21/15 | | Inv. Or Packing Slip No.: C00008954 | | Inv. Or Packing Slip Date: 10/20/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 29 | 31 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 29 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (75,390 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ATS Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008954 | Freight Bill (Pro) No.: Packing List Attached | Weight: 30,732 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008954
Ship Date: 10/20/15 10/21/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 00640210101691 | 1,330.00 |
| 2 | 0064021010212 | 1,960.00 |
| 3 | 00640210102121 | 910.00 |
| 4 | 0064021010258 | 1,960.00 |
| 5 | 0064021010274 | 2,800.00 |
| 6 | 0064021010275 | 2,800.00 |
| 7 | 0064021010276 | 2,940.00 |
| 8 | 0064021010277 | 2,100.00 |
| 9 | 00640210102771 | 980.00 |
| 10 | 0064021010278 | 3,640.00 |
| 11 | 0064021010279 | 2,800.00 |
| 12 | 0064021010280 | 2,940.00 |
| 13 | 0064021010281 | 2,800.00 |
| 14 | 0064021010282 | 2,800.00 |
| 15 | 0064021010283 | 3,360.00 |
| 16 | 0064021010284 | 2,800.00 |
| 17 | 0064021010285 | 2,800.00 |
| 18 | 0064021010286 | 2,660.00 |
| 19 | 0064021010288 | 2,800.00 |
| 20 | 0064021010289 | 2,800.00 |
| 21 | 0064021010290 | 2,800.00 |
| 22 | 0064021010291 | 2,800.00 |
| 23 | 0064021010292 | 2,800.00 |
| 24 | 0064021010293 | 2,800.00 |
| 25 | 0064021010294 | 2,800.00 |
| 26 | 0064021010295 | 3,010.00 |
| 27 | 0064021010296 | 2,800.00 |
| 28 | 0064021010297 | 2,800.00 |
| 29 | 0064021010298 | 2,800.00 |

Total Rolls: 29
Total Sq Feet: 75,390.00
Total Weight (lbs): 30,732.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delayed payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: ROSS
Driver's Sign: _____
Driver's Cell Phone #: 844 2[illegible]
Trucking Co.: [illegible]
Trucking Co. Phone #: _____
Broker: ATS Logistics
Date: 10/20/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919743

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 53 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/21/15 |
| QC Inspection by: CP | | QC Date: 10/21/15 | | Inv. Or Packing Slip No.: C00008937 | | Inv. Or Packing Slip Date: 10/19/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 31 | 33 | Received At: SA6 Site<br>60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 31 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (80,640 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: Medallion Transport & Logistics LLC | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008937 | Freight Bill (Pro) No.: Packing List Attached | Weight: 31,321 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008937
Ship Date: 10/19/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 00640210102241 | 840.00 |
| 2 | 0064021010246 | 2,800.00 |
| 3 | 0064021010247 | 2,800.00 |
| 4 | 0064021010248 | 2,800.00 |
| 5 | 0064021010249 | 2,800.00 |
| 6 | 0064021010250 | 3,150.00 |
| 7 | 0064021010251 | 2,800.00 |
| 8 | 0064021010252 | 2,800.00 |
| 9 | 0064021010253 | 2,800.00 |
| 10 | 0064021010254 | 2,800.00 |
| 11 | 0064021010255 | 2,800.00 |
| 12 | 0064021010256 | 2,800.00 |
| 13 | 0064021010257 | 2,800.00 |
| 14 | 00640210102581 | 980.00 |
| 15 | 0064021010259 | 3,150.00 |
| 16 | 0064021010260 | 2,520.00 |
| 17 | 0064021010261 | 2,800.00 |
| 18 | 0064021010262 | 2,800.00 |
| 19 | 0064021010263 | 2,800.00 |
| 20 | 0064021010264 | 2,800.00 |
| 21 | 0064021010265 | 2,800.00 |
| 22 | 0064021010266 | 2,800.00 |
| 23 | 0064021010267 | 2,800.00 |
| 24 | 0064021010268 | 2,800.00 |
| 25 | 0064021010269 | 2,800.00 |
| 26 | 0064021010270 | 2,800.00 |
| 27 | 0064021010271 | 2,800.00 |
| 28 | 0064021010272 | 2,800.00 |
| 29 | 0064021010287 | 1,610.00 |
| 30 | 00640210102871 | 1,190.00 |
| 31 | 0064021010305 | 2,800.00 |

Total Rolls: 31
Total Sq Feet: 80,640.00
Total Weight (lbs): 31,321.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:**

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

| Receiver Print Name | Receiver's Signature |
|---|---|
| Receive Date | Receiver's Company Name |

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name:
Driver's Sign:
Driver's Cell Phone #:
Trucking Co.:
Trucking Co. Phone #:
Broker: Medallion Transport & Logistics LLC.
Date: 10/19/15
Truck Departure Time:

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919713

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 54 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/22/15 |
| QC Inspection by: CP | | QC Date: 10/22/15 | | Inv. Or Packing Slip No.: C00008956 | | Inv. Or Packing Slip Date: 10/20/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (70,070 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ATS Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008956 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,718 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008956
Ship Date: 10/20/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010273 | 1,680.00 |
| 2 | 00640210102731 | 840.00 |
| 3 | 0064021010299 | 2,800.00 |
| 4 | 0064021010300 | 2,800.00 |
| 5 | 0064021010301 | 3,010.00 |
| 6 | 0064021010302 | 2,800.00 |
| 7 | 0064021010303 | 2,800.00 |
| 8 | 0064021010304 | 2,800.00 |
| 9 | 0064021010306 | 2,800.00 |
| 10 | 0064021010307 | 2,800.00 |
| 11 | 0064021010308 | 2,800.00 |
| 12 | 0064021010309 | 2,940.00 |
| 13 | 0064021010310 | 2,800.00 |
| 14 | 0064021010311 | 1,400.00 |
| 15 | 00640210103111 | 1,400.00 |
| 16 | 0064021010312 | 2,800.00 |
| 17 | 0064021010313 | 2,800.00 |
| 18 | 0064021010314 | 2,800.00 |
| 19 | 0064021010315 | 2,800.00 |
| 20 | 0064021010316 | 2,800.00 |
| 21 | 0064021010317 | 2,800.00 |
| 22 | 0064021010318 | 2,800.00 |
| 23 | 0064021010319 | 2,800.00 |
| 24 | 0064021010320 | 2,800.00 |
| 25 | 0064021010321 | 2,800.00 |
| 26 | 0064021010322 | 2,800.00 |
| 27 | 0064021010324 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 70,070.00
Total Weight (lbs): 28,718.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: ATS Logistics
Date: 10/20/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919766

Load# 166210

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

Honeywell RES

Honeywell.com

## Receiving Inspection Report

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Location: Honeywell SA-6 | | | | | | | | | Specification Number: 02374 |
| Received From: SKAPS Industries | | | | | | | | | Receiving Report Number: 54 |
| Address: 571 Industrial Parkway, Commerce GA 30529 | | | | | | | | | Date: 10/22/15 |
| QC Inspection by: CP | | QC Date: 10/22/15 | | Inv. Or Packing Slip No.: C00008956 | | Inv. Or Packing Slip Date: 10/20/15 | | | PO Number: IWT Cargo Guard |
| Boxes | Barrels | Bags | Crates | Bundles | Drums | Kegs | Rolls | Total Packages | Received By: ENTACT |
| | | | | 2 | | | 27 | 29 | Received At: SA6 Site 60 Kellogg Street, Jersey City NJ |

| Line | Quantity | Unit | Description | Over | Short |
|---|---|---|---|---|---|
| 1 | 27 | Rolls | TN 330-2-6 Geocomposite (Geocomposite Drainage Layer) (70,070 square feet) | 0 | 0 |
| 2 | 2 | Bags | Plastic ties | 0 | 0 |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | | | | | |
| 14 | | | | | |
| 15 | | | | | |
| 16 | | | | | |
| 17 | | | | | |
| 18 | | | | | |
| 19 | | | | | |
| 20 | | | | | |

| | | | | | |
|---|---|---|---|---|---|
| Shipped Via: ATS Logistics | | Car # | Payment: NA | Show O.S.&D. Report No. in the space provided if over, short or damaged noted above. | O.S.&D. Report No.: |
| Waybill No.:C00008956 | Freight Bill (Pro) No.: Packing List Attached | Weight: 28,718 lbs | Amount: NA | | |

| For Receiving Clerk Use Only: | | |
|---|---|---|
| Itemized by:<br><br>Date: | Entered by:<br><br>Date: | Finalized by:<br><br>Date: |

STRAIGHT BILL OF LADING ORIGINAL-NOT NEGOTIABLE

SKAPS Industries
571 Industrial Parkway
Commerce, GA 30529
Ph: 7060-336-7000 Fax: 706-336-7007

Bill of Lading #: C00008956
Ship Date: 10/20/15
Sales Order #: C001905
Customer Name: Iwt/Cargo-Guard
Cust. P.O. #: 20252
Ship Via: Flatbed
Delivery Terms: Plant / PPA
Container #:
Seal #:

SHIP-TO:
Project: Entact, NJ
Address: 60 Kellogg St.
City, State, Zip: Jersey City, NJ, 07305
Contact: Dan Harris
Phone: 405-206-4659

SIGN HERE FOR SHIPPER: _____

SHIPPER ADDRESS: 571 INDUSTRIAL PKWY.
COMMERCE, GA 30529

**Product Code: TN330-2-6**

| No | Roll # | Sq. Ft. |
|---|---|---|
| 1 | 0064021010273 | 1,680.00 |
| 2 | 00640210102731 | 840.00 |
| 3 | 0064021010299 | 2,800.00 |
| 4 | 0064021010300 | 2,800.00 |
| 5 | 0064021010301 | 3,010.00 |
| 6 | 0064021010302 | 2,800.00 |
| 7 | 0064021010303 | 2,800.00 |
| 8 | 0064021010304 | 2,800.00 |
| 9 | 0064021010306 | 2,800.00 |
| 10 | 0064021010307 | 2,800.00 |
| 11 | 0064021010308 | 2,800.00 |
| 12 | 0064021010309 | 2,940.00 |
| 13 | 0064021010310 | 2,800.00 |
| 14 | 0064021010311 | 1,400.00 |
| 15 | 00640210103111 | 1,400.00 |
| 16 | 0064021010312 | 2,800.00 |
| 17 | 0064021010313 | 2,800.00 |
| 18 | 0064021010314 | 2,800.00 |
| 19 | 0064021010315 | 2,800.00 |
| 20 | 0064021010316 | 2,800.00 |
| 21 | 0064021010317 | 2,800.00 |
| 22 | 0064021010318 | 2,800.00 |
| 23 | 0064021010319 | 2,800.00 |
| 24 | 0064021010320 | 2,800.00 |
| 25 | 0064021010321 | 2,800.00 |
| 26 | 0064021010322 | 2,800.00 |
| 27 | 0064021010324 | 2,800.00 |

Total Rolls: 27
Total Sq Feet: 70,070.00
Total Weight (lbs): 28,718.00

Bags of Ties: 2

**Driver sign below if you have received above mentioned items :**

**Driver's Sign:** _____

ATTN RECEIVER: Please sign below if you have received the items mentioned on the BOL and any discrepencies must be reported to SKAPS Industries within 7 days of receipt of goods.

Receiver Print Name | Receiver's Signature

Receive Date | Receiver's Company Name

**Driver Requirements:**

1) For Monday delivery driver must call on Friday.
2) Driver must call 706-336-7000 when unloaded.
3) Driver must call and advise of any delay in transit.
4) A copy of this bill-of-lading must accompany freight invoice, failure to do this will result in delaved payments.

Delivery Timings: Mon - Fri 6:00 AM to 2:00 PM
Driver's Name: _____
Driver's Sign: _____
Driver's Cell Phone #: _____
Trucking Co.: _____
Trucking Co. Phone #: _____
Broker: ATS Logistics
Date: 10/20/15
Truck Departure Time: _____

**Comments:**

Driver please call 24 hours prior to delivery
Freight view shipper # : 5919766

Load# 166210

CARRIER MUST COLLECT THE FREIGHT FROM THE BROKER ONLY

Received at Commerce, GA from SKAPS Industries the property described above, in apparent good order except as noted (contents and condition of packages unknown), marked, consigned, and destined as indicated above, which said Carrier (the word "Carrier" being understood throughout this Shipping Order as meaning the person or corporation in possession of the property) agrees to carry to the place of delivery at said destination. It is mutually agreed as to each Carrier of all or any of said property, over all or any portion of said route to destination and as to each party at any time interested in all or any of said property, that every service performed here under shall be subject to either: (a) if the shipper noted herein is SKAPS Industries as indicated by the designation of the "Shipper" to be SKAPS Industries, then the Shipper and Carrier are subject to the terms and conditions contained in the Contract for truck Transportation existing between the parties or (b) if the Shipper noted herein is not SKAPS Industries then SKAPS Industries is acting solely as the agent for the denoted Shipper, and thus every aspect of the service to be perform here under between the Shipper and the Carrier shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set forth (1) in Official Southern, Western, and Illinois Freight Classifications in effect on the date hereof, if this a rail-water shipment, or (2) in the applicable motor carrier classification or tariff if this is a motor carrier shipment. When acting in the capacity of an agent for a Shipper in placing the material in transit on behalf of a Shipper, SKAPS Industries accepts no liability for loss of cargo, damage to containers, or any other consequences occurring during transportation. Carrier having agreed that the transportation arrangement was initiated by the Shipper and not by SKAPS Industries Subject to the above terms and conditions as to which party is the Shipper, Shipper hereby certifies that he is familiar with the terms and conditions that govern the transportation of this shipment, and the said terms and conditions are hereby agreed and accepted for himself and his assigns.

# Appendix H
# GCL to Barrier Wall Connection Logs


Honeywell

# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** 9/16/15 |
|---|---|

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)

NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)

NTS TYP C-309

| ***Check applicable Detail:** | **Location:** |
|---|---|
| ☑ Box Cut Dimension<br>☑ Barrier wall clean/exposed<br>☑ Sand Bentonite Mix | - **Hydraulic Barrier Wall stations 9+00 to 10+75 (approximately).**<br>- **South side of the C Street corridor.** |
| **Comments:**<br>- Roll #4109 was placed down the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/15/15.<br>- All strips on the east side of the corridor were placed on 9/15/15. On 9/15/15, Amec and Langan directed Entact to remove the wet SCB plug, and replace it with new GCL and SCB plug mix. The replacement process was completed on 9/16/15. | **Amec Foster Wheeler QA Signature:** B Shea |

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/18/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall stations 6+50 to 6+75 (approximately).**
- **South side of the D Street corridor.**

**Comments:**

- Roll #4070 was placed in the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/18/15.

**Amec Foster Wheeler QA Signature:** B Shea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/24/15

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)

NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)

NTS TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall stations 4+00 to 5+00 (approximately).**

**Comments:**

- Roll #4064 was placed.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/24/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 3+25 to 4+00 (approximately)**

**Comments:**

- Rolls #4094 and #4095 were placed.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/25/15

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)

NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)

NTS TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 3+00 to 3+25 (approximately)**

**Comments:**

- Rolls #4101 and #4090 were placed.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/29/15

QA - GCL to Barrier Wall Connection Detail




BELOW GROUNDWATER


GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION

NTS

BN C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER

NTS

G TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 2+30 to 3+00 (approximately)**

**Comments:**

- Rolls #4107, #4108, #4072 and #4110 were placed.

**Amec Foster Wheeler QA Signature:** _____

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 10/8/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)
NTS
C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)
NTS
TYP | C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Hydraulic Barrier Wall - Stations 0 to 2+30 (approximately)**

**Comments:**

- Rolls #4086 and # 4102 were placed.

**Amec Foster Wheeler QA Signature:** _____

Honeywell


# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 8/6/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) C-121 | C-309
NTS

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) TYP C-309
NTS

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **South side of the B Street Corridor**
- **Stations 15+00 to 17+00**

**Comments:**

- Roll #4078 was placed over the sheet pile wall on 8/5/15 and 8/6/15.
- On 8/6/15 Amec Foster Wheeler directed Entact to fold back the GCL in order to ensure clean contact between the GCL and the top of the Hydraulic Barrier Wall.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


# STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 8/3/15

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) NTS TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **North side of the B Street Corridor**
- **Stations 14+60 to 15+00**

**Comments:**

- Roll #4078 was placed over the SCB Wall on 8/3/15.
- Entact installed a 45° "buffer" slope from the bottom of the corridor to the top corner of the SCB wall, in order to avoid forming a 90° angle with the GCL at the bottom corner of the wall. This method was approved by Geoff Shallard prior to installation.

**Amec Foster Wheeler QA Signature:** B Shea


Honeywell

## STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

| **Project:** Study Area 6 South | **Date:** 9/9/15 |
|---|---|

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) NTS TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Soil Cement Bentonite Wall stations 8+00 to 8+50 (approximately).**
- **North side of the C Street corridor.**

**Comments:**

- Roll #4109 was placed down the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/9/15.
- Roll #4073 was placed on the northwest corner of the corridor slopes, overlapping the SCB Wall on 9/9/15.
- Roll #4087 was placed on the northeast corner of the corridor slopes, overlapping the SCB Wall on 9/9/15.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 9/18/15

QA - GCL to Barrier Wall Connection Detail





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 3+22

TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) NTS C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) NTS TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Soil Cement Bentonite Wall stations 5+00 to 5+75 (approximately).**
- **North side of the D Street corridor**

**Comments:**

- Roll #4070 was placed in the center of the corridor, overlapping the SCB Wall and HB Wall, on 9/18/15.

**Amec Foster Wheeler QA Signature:** BShea

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South


**Date:** 9/24/15

QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN)
NTS
C-121 C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)
NTS
TYP C-309

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☐ Sand Bentonite Mix

**Location:**

- **Soil Cement Bentonite Wall stations 2+50 to 3+00 (approximately).**

**Comments:**

**Amec Foster Wheeler QA Signature:** _____

Honeywell


STUDY AREA 6 - CAP INSTALLATION

amec foster wheeler

**Project:** Study Area 6 South

**Date:** 10/8/15


QA - GCL to Barrier Wall Connection Detail




TYPICAL EDGE DETAIL – LINER BELOW FINAL SCB ELEVATION (BN) C-121 | C-309

NTS

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G) TYP | C-309

NTS

***Check applicable Detail:**

- ☑ Box Cut Dimension
- ☑ Barrier wall clean/exposed
- ☑ Sand Bentonite Mix

**Location:**

- **Soil Cement Bentonite Wall stations 0+00 to 2+50 (approximately).**

**Comments:**

- Rolls #4071 and #4102 were placed over the SCB Wall.

**Amec Foster Wheeler QA Signature:** _____

# Appendix I
# ESI Panel Placement Logs

7/20/15

INDEPENDENT CQA MONITOR

Daily Panel Placement

Page 1

**Project Name:** HONEYWELL Job # 12-11-1399 Deployment Date 7-20-15

**Superintendent:** FORTINO AYALA **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other: CAP CONSTRUCTION

**Description** (i.e. Phase #, Cell #, Pond # etc.) **Roll Stock Width** 23

**Panel # 1** Roll # G15C283031

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

23' / 22.5' / 163' 162' 162' 163' / 22.5' / 23'

Notes:

Initial SF - Lineal Feet Trench
Final SF 3,645 -

**Panel # 2** Roll # G15C283031

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

23' / 22.5' / 163' 162' 163' 165' / 22.5' / 23'

Notes:

Initial SF - Lineal Feet Trench
Final SF 3,656.25 -

**Panel # 3** Roll # G15C283031

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

165' 163' 165' 168'

Notes:

Initial SF - Lineal Feet Trench
Final SF 3,690 -

**Panel # 4** Roll # G15C292021

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

23' / 22.5' / 168' 165' 165' 168' / 22.5' / 23'

Notes:

Initial SF - Lineal Feet Trench
Final SF 3,712.5 -

**Panel #** Roll #

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF - Lineal Feet Trench
Final SF -

**Panel #** Roll #

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF - Lineal Feet Trench
Final SF -

**Panel #** Roll #

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF - Lineal Feet Trench
Final SF -

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | - | SF |
| **Total Pay Area This Page** | - | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | - | SF |
| Total Panel SF To Date | - | SF |
| **Total Pay Area To Date Including Anchor Trench** | - | |
| Initial Quantity Previous | - | SF |
| Initial Quantity This Page | - | SF |
| Initial Quantity To Date | - | SF |

14,703.75

7/21/15

INDEPENDENT CQA MONITOR

**Daily Panel Placement** Page 2.

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date**


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description (i.e. Phase #, Cell #, Pond # etc.)** Cap construction Single layer **Roll Stock Width** 22.5

**Panel #** 5 **Roll #** G15C282021

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,678.75 -
Lineal Feet Trench

**Panel #** 6 **Roll #** G15C282021

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,555 -
Lineal Feet Trench

**Panel #** 7 **Roll #** G15C277065

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 112.5 -
Lineal Feet Trench

**Panel #** 8 **Roll #** G15C277065

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF





Notes:

Initial SF -
Final SF 3,667.5 -
Lineal Feet Trench

**Panel #** 9 **Roll #** G15C277065

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF




Notes:

Initial SF -
Final SF 3,667.5 -
Lineal Feet Trench

**Panel #** **Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF -
Final SF -
Lineal Feet Trench

**Panel #** **Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF -
Final SF -
Lineal Feet Trench

**Panel #** **Roll #**

Final Length Avg. LF
Final Width Avg. LF
Initial Length Avg. LF
Initial Width Avg. LF

Notes:

Initial SF -
Final SF -
Lineal Feet Trench

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | **SF** |
| **Total Panel SF This Page** | - | **SF** |
| **Total Pay Area This Page** | - | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | - | SF |
| Total Panel SF To Date | - | SF |
| **Total Pay Area To Date Including Anchor Trench** | - | |
| Initial Quantity Previous | - | SF |
| Initial Quantity This Page | - | SF |
| Initial Quantity To Date | - | SF |

14,680.5

INDEPENDENT CQA MONITOR 7/22/15

## Daily Panel Placement

Page 3

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/22/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 10** | **Roll #** G15C282018

| | | |
|---|---|---|
| Final Length Avg. | 163.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,668 | |

**Panel # 11** | **Roll #** G15C282018

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel # 12** | **Roll #** G15C282018

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel # 13** | **Roll #** G15C276052

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | **-** | **SF** |
| **Total Panel SF This Page** | **14,726** | **SF** |
| **Total Pay Area This Page** | **14,726** | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 29,385 | SF |
| Total Panel SF To Date | 44,111 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **44,111** | |
| Initial Quantity Previous | 30,452 | SF |
| Initial Quantity This Page | 15,226 | SF |
| Initial Quantity To Date | 45,678 | SF |

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 22 OF 25**

- **Declaration #2 Part 2**

**Attachments F (Part 2) – I**

**ATTACHMENT F**
**LANGAN SA-6 SOUTH CAP**
**QUALITY ASSURANCE REPORT**
**PART 2**

INDEPENDENT CQA MONITOR 7-23-15

## Daily Panel Placement

Page 4

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/23/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

Primary Secondary Cell Pond Cap [X] Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 14** Roll # G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench | |
| Final SF | 3,690 | | |

**Panel # 15** Roll # G15C276052

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench | |
| Final SF | 3,701 | | |

**Panel # 16** Roll # G15C277064

| | | |
|---|---|---|
| Final Length Avg. | 165.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench | |
| Final SF | 3,713 | | |

**Panel # 17** Roll # G15C277064

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,830 | Lineal Feet Trench | |
| Final SF | 3,701 | | |

**Panel # 18** Roll # G15C277064

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,690 | | |

**Panel #** Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **18,495** | SF |
| **Total Pay Area This Page** | **18,495** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 44,111 | SF |
| Total Panel SF To Date | 62,606 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **62,606** | |
| Initial Quantity Previous | 45,678 | SF |
| Initial Quantity This Page | 19,171 | SF |
| Initial Quantity To Date | 64,849 | SF |

7/24/15 Independent CQA Monitor

**Daily Panel Placement** Page 5


**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/24/15

**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:


**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 19 | Roll # G15C276056 | | |
|---|---|---|---|
| Final Length Avg. | 164.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,690 | | |





Notes:

| Panel # 20 | Roll # G15C276056 | | |
|---|---|---|---|
| Final Length Avg. | 164.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 3,830 | Lineal Feet Trench | |
| Final SF | 3,690 | | |





Notes:

| Panel # 21 | Roll # G15C276056 | | |
|---|---|---|---|
| Final Length Avg. | 164.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 3,830 | Lineal Feet Trench | |
| Final SF | 3,690 | | |





Notes:

| Panel # 22 | Roll # G15C277061 | | |
|---|---|---|---|
| Final Length Avg. | 164.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,690 | | |





Notes:

| Panel # 23 | Roll # G15C277061 | | |
|---|---|---|---|
| Final Length Avg. | 164.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,690 | | |





Notes:

| Panel # 24 | Roll # G15C277061 | | |
|---|---|---|---|
| Final Length Avg. | 164.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,690 | | |





Notes:

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |




Notes:

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |




Notes:

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **22,140** | SF |
| **Total Pay Area This Page** | **22,140** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 62,606 | SF |
| Total Panel SF To Date | 84,746 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **84,746** | |
| Initial Quantity Previous | 64,849 | SF |
| Initial Quantity This Page | 22,931 | SF |
| Initial Quantity To Date | 87,780 | SF |

INDEPENDENT CQA MONITOR

7/29/15

## Daily Panel Placement

Page 6


**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/28/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary **Secondary** ☐ **Cell** ☐ **Pond** ☐ **Cap** ☒ **Other:**

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23


| Panel # 25 | Roll # G15C277059 |
|---|---|
| Final Length Avg. | 163.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.50 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,807 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,679 | |


| Panel # 26 | Roll # G15C277059 |
|---|---|
| Final Length Avg. | 163.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.00 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,795 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,668 | |


| Panel # 27 | Roll # G15C277059 |
|---|---|
| Final Length Avg. | 163.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.50 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,784 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,668 | |


| Panel # 28 | Roll # G15C283028 |
|---|---|
| Final Length Avg. | 163.50 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 164.50 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,784 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,679 | |


| Panel # 29 | Roll # G15C283028 |
|---|---|
| Final Length Avg. | 164.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.00 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,795 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,690 | |


| Panel # 30 | Roll # G15C283028 |
|---|---|
| Final Length Avg. | 164.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 165.50 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 3,807 | Lineal Feet Trench |
|---|---|---|
| Final SF | 3,690 | |


| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |




Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |

| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |




Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | 22,073 | SF |
| **Total Pay Area This Page** | 22,073 | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 84,746 | SF |
| Total Panel SF To Date | 106,819 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **106,819** | |
| Initial Quantity Previous | 87,780 | SF |
| Initial Quantity This Page | 22,770 | SF |
| Initial Quantity To Date | 110,550 | SF |

INDEPENDENT CQA MONITOR

7/30/15

## Daily Panel Placement

Page 7

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 07/29/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 31** | **Roll #** G15C282015

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel # 32** | **Roll #** G15C282015

| | | |
|---|---|---|
| Final Length Avg. | 163.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,784 | Lineal Feet Trench |
| Final SF | 3,668 | |

**Panel # 33** | **Roll #** G15C282015

| | | |
|---|---|---|
| Final Length Avg. | 163.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,668 | |

**Panel # 34** | **Roll #** G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,807 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,693** | SF |
| **Total Pay Area This Page** | **14,693** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 106,819 | SF |
| Total Panel SF To Date | 121,511 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **121,511** | |
| Initial Quantity Previous | 110,550 | SF |
| Initial Quantity This Page | 15,180 | SF |
| Initial Quantity To Date | 125,730 | SF |

8/4/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement



**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/03/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 35 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 94.00 | LF |
| Final Width Avg. | 21.50 | LF |
| Initial Length Avg. | 95.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,185 | Lineal Feet Trench | |
| Final SF | 2,021 | | |

### Panel # 36 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 94.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 95.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,197 | Lineal Feet Trench | |
| Final SF | 2,126 | | |

### Panel # 37 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 96.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 98.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,254 | Lineal Feet Trench | |
| Final SF | 2,171 | | |

### Panel # 38 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 99.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 101.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,335 | Lineal Feet Trench | |
| Final SF | 2,239 | | |

### Panel # 39 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 101.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 103.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,369 | Lineal Feet Trench | |
| Final SF | 2,284 | | |

### Panel # 40 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 100.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 101.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 2,335 | Lineal Feet Trench | |
| Final SF | 2,261 | | |

### Panel # 41 — Roll # G15C276055

| | | |
|---|---|---|
| Final Length Avg. | 35.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 37.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 851 | Lineal Feet Trench | |
| Final SF | 788 | | |

### Panel # 42 — Roll # G15C282017

| | | |
|---|---|---|
| Final Length Avg. | 167.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,758 | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **17,647** | SF |
| **Total Pay Area This Page** | **17,647** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 121,511 | SF |
| Total Panel SF To Date | 139,159 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **139,159** | |
| Initial Quantity Previous | 125,730 | SF |
| Initial Quantity This Page | 18,412 | SF |
| Initial Quantity To Date | 144,141 | SF |

8/4/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 9

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/03/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 43 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 35.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 36.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 840 | Lineal Feet Trench | |
| Final SF | 799 | | |

Notes:

| Panel # 44 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 56.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 57.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,323 | Lineal Feet Trench | |
| Final SF | 1,260 | | |

Notes:

| Panel # 45 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 25.00 | LF | |
| Final Width Avg. | 10.00 | LF | |
| Initial Length Avg. | 28.00 | LF | |
| Initial Width Avg. | 11.00 | LF | |
| Initial SF | 308 | Lineal Feet Trench | |
| Final SF | 250 | | |

Notes:

| Panel # 46 | Roll # G15C276053 | | |
|---|---|---|---|
| Final Length Avg. | 27.00 | LF | |
| Final Width Avg. | 10.00 | LF | |
| Initial Length Avg. | 28.00 | LF | |
| Initial Width Avg. | 11.50 | LF | |
| Initial SF | 322 | Lineal Feet Trench | |
| Final SF | 270 | | |

Notes: TRIM OFF P-45

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

Notes:

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

Notes:

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

Notes:

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **2,579** | SF |
| **Total Pay Area This Page** | **2,579** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 139,159 | SF |
| Total Panel SF To Date | 141,737 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **141,737** | |
| Initial Quantity Previous | 144,141 | SF |
| Initial Quantity This Page | 2,792 | SF |
| Initial Quantity To Date | 146,933 | SF |

8/7/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 10

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/05/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL


☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap [X] Other:


**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|
| 47 | G15C276053 | 167.00 LF | 22.50 LF | 168.50 LF | 23.00 LF | 3,876 | 3,758 | |
| 48 | G15C276053 | 167.00 LF | 22.50 LF | 168.00 LF | 23.00 LF | 3,864 | 3,758 | |
| 49 | G15C283033 | 167.00 LF | 22.50 LF | 168.00 LF | 23.00 LF | 3,864 | 3,758 | |
| | | | | | | - | - | |
| | | | | | | - | - | |
| | | | | | | - | - | |
| | | | | | | - | - | |
| | | | | | | - | - | |

Notes:




| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **11,273** | SF |
| **Total Pay Area This Page** | **11,273** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 141,737 | SF |
| Total Panel SF To Date | 153,010 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **153,010** | |
| Initial Quantity Previous | 146,933 | SF |
| Initial Quantity This Page | 11,604 | SF |
| Initial Quantity To Date | 158,537 | SF |

8/7/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 11

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/06/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 50** | **Roll #** G15C283033

| | | |
|---|---|---|
| Final Length Avg. | 167.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 168.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,876 | Lineal Feet Trench | |
| Final SF | 3,769 | | |

**Panel # 51** | **Roll #** G15C283033

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,784 | Lineal Feet Trench | |
| Final SF | 3,679 | | |

**Panel # 52** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 5.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 6.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 138 | Lineal Feet Trench | |
| Final SF | 113 | | |

**Panel # 53** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,899 | Lineal Feet Trench | |
| Final SF | 3,780 | | |

**Panel # 54** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,780 | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **15,120** | SF |
| **Total Pay Area This Page** | **15,120** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 153,010 | SF |
| Total Panel SF To Date | 168,130 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **168,130** | |
| Initial Quantity Previous | 158,537 | SF |
| Initial Quantity This Page | 15,583 | SF |
| Initial Quantity To Date | 174,119 | SF |

8/10/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 12

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/07/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 55** | **Roll #** G15C277060

| | | |
|---|---|---|
| Final Length Avg. | 157.00 | LF |
| Final Width Avg. | 11.25 | LF |
| Initial Length Avg. | 158.00 | LF |
| Initial Width Avg. | 11.50 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 1,817 | Lineal Feet Trench | |
| Final SF | 1,766 | | |

**Panel # 56** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 11.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 12.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 288 | Lineal Feet Trench | |
| Final SF | 248 | | |

**Panel # 57** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 167.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench | |
| Final SF | 3,769 | | |

**Panel # 58** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 168.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,864 | Lineal Feet Trench | |
| Final SF | 3,735 | | |

**Panel # 59** | **Roll #** G15C283029

| | | |
|---|---|---|
| Final Length Avg. | 150.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 151.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,473 | Lineal Feet Trench | |
| Final SF | 3,375 | | |

**Panel # 60** | **Roll #** G15C276053

| | | |
|---|---|---|
| Final Length Avg. | 15.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 16.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 380 | Lineal Feet Trench | |
| Final SF | 338 | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **13,230** | SF |
| **Total Pay Area This Page** | **13,230** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 168,130 | SF |
| Total Panel SF To Date | 181,360 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **181,360** | |
| Initial Quantity Previous | 174,119 | SF |
| Initial Quantity This Page | 13,708 | SF |
| Initial Quantity To Date | 187,827 | SF |

8/13/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 13

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/10/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 61 | Roll # G15C282011 | | |
|---|---|---|---|
| Final Length Avg. | 164.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 166.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Notes: | | | |
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,701 | | |

| Panel # 62 | Roll # G15C282011 | | |
|---|---|---|---|
| Final Length Avg. | 163.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 165.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Notes: | | | |
| Initial SF | 3,795 | Lineal Feet Trench | |
| Final SF | 3,679 | | |

| Panel # 63 | Roll # G15C282011 | | |
|---|---|---|---|
| Final Length Avg. | 163.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 164.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Notes: | | | |
| Initial SF | 3,784 | Lineal Feet Trench | |
| Final SF | 3,668 | | |

| Panel # 64 | Roll # G15C282013 | | |
|---|---|---|---|
| Final Length Avg. | 162.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 164.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Notes: 190 SQ FT OFF P-64 .CORRECTED | | | |
| Initial SF | 3,784 | Lineal Feet Trench | |
| Final SF | 3,467 | | |

| Panel # 65 | Roll # G15C282013 | | |
|---|---|---|---|
| Final Length Avg. | 162.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 164.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Notes: | | | |
| Initial SF | 3,772 | Lineal Feet Trench | |
| Final SF | 3,645 | | |

| Panel # 66 | Roll # G15C282013 | | |
|---|---|---|---|
| Final Length Avg. | 15.50 | LF | |
| Final Width Avg. | 12.25 | LF | |
| Initial Length Avg. | 16.50 | LF | |
| Initial Width Avg. | 13.00 | LF | |
| Notes: | | | |
| Initial SF | 215 | Lineal Feet Trench | |
| Final SF | 190 | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Panel # | Roll # | | |
|---|---|---|---|
| Final Length Avg. | | LF | |
| Final Width Avg. | | LF | |
| Initial Length Avg. | | LF | |
| Initial Width Avg. | | LF | |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **18,349** | SF |
| **Total Pay Area This Page** | **18,349** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 181,360 | SF |
| Total Panel SF To Date | 199,709 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **199,709** | |
| Initial Quantity Previous | 187,827 | SF |
| Initial Quantity This Page | 19,167 | SF |
| Initial Quantity To Date | 206,994 | SF |

8/14/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 14

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/13/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

[ ] Primary Secondary [ ] Cell [ ] Pond [ ] Cap [X] Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 67** | **Roll #** G15C282013

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,761 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 68** | **Roll #** G15C282020

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 69** | **Roll #** G15C282020

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 70** | **Roll #** G15C282020

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel # 71** | **Roll #** G15C277062

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,761 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | 18,225 | SF |
| **Total Pay Area This Page** | 18,225 | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 199,709 | SF |
| Total Panel SF To Date | 217,934 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **217,934** | |
| Initial Quantity Previous | 206,994 | SF |
| Initial Quantity This Page | 18,768 | SF |
| Initial Quantity To Date | 225,762 | SF |

8/17/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 15

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 08/14/15


**Superintendent:** Fortino Ayala **Material Type:** LLDPE 60 MIL

☐ Primary **Secondary** ☐ **Cell** ☐ **Pond** ☐ **Cap** ☒ **Other:**

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel #** 72 **Roll #** G15C277062

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel #** 73 **Roll #** G15C277062

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel #** 74 **Roll #** G15C276054

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,807 | Lineal Feet Trench |
| Final SF | 3,690 | |

**Panel #** 75 **Roll #** G15C276054

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,679 | |

**Panel #** **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,704** | SF |
| **Total Pay Area This Page** | **14,704** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 217,934 | SF |
| Total Panel SF To Date | 232,638 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **232,638** | |
| Initial Quantity Previous | 225,762 | SF |
| Initial Quantity This Page | 15,169 | SF |
| Initial Quantity To Date | 240,930 | SF |

INDEPENDENT CQA MONITOR

9/16/15

## Daily Panel Placement

Page 16

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/09/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 76 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 78.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 79.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 1,817 | Lineal Feet Trench |
| Final SF | 1,755 | |

### Panel # 77 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 81.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 82.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 1,886 | Lineal Feet Trench |
| Final SF | 1,823 | |

### Panel # 78 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 84.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 87.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 2,001 | Lineal Feet Trench |
| Final SF | 1,890 | |

### Panel # 79 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 84.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 87.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 2,001 | Lineal Feet Trench |
| Final SF | 1,890 | |

### Panel # 80 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 83.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 84.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 1,944 | Lineal Feet Trench |
| Final SF | 1,879 | |

### Panel # 81 — Roll # G15C276054

| | | |
|---|---|---|
| Final Length Avg. | 82.50 | LF |
| Final Width Avg. | 21.75 | LF |
| Initial Length Avg. | 85.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 1,955 | Lineal Feet Trench |
| Final SF | 1,794 | |

### Panel # 82 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 28.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 29.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 667 | Lineal Feet Trench |
| Final SF | 630 | |

### Panel # 83 — Roll # G15C282019

| | | |
|---|---|---|
| Final Length Avg. | 26.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 27.00 | LF |
| Initial Width Avg. | 23.00 | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | 621 | Lineal Feet Trench |
| Final SF | 585 | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | **-** | **SF** |
| **Total Panel SF This Page** | **12,246** | **SF** |
| **Total Pay Area This Page** | **12,246** | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 232,638 | SF |
| Total Panel SF To Date | 244,884 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **244,884** | |
| Initial Quantity Previous | 240,930 | SF |
| Initial Quantity This Page | 12,892 | SF |
| Initial Quantity To Date | 253,822 | SF |

9/16/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 17


**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/09/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23


| Panel # 84 | Roll # G15C276054 |
|---|---|
| Final Length Avg. | 35.00 LF |
| Final Width Avg. | 22.50 LF |
| Initial Length Avg. | 36.00 LF |
| Initial Width Avg. | 23.00 LF |




Notes:

| Initial SF | 828 | Lineal Feet Trench |
|---|---|---|
| Final SF | 788 | |


| Panel # 85 | Roll # G15C276054 |
|---|---|
| Final Length Avg. | 17.00 LF |
| Final Width Avg. | 5.00 LF |
| Initial Length Avg. | 18.00 LF |
| Initial Width Avg. | 11.50 LF |




Notes: TRIM FROM P-85

| Initial SF | 207 | Lineal Feet Trench |
|---|---|---|
| Final SF | 85 | |


| Panel # 86 | Roll # G15C276054 |
|---|---|
| Final Length Avg. | 10.00 LF |
| Final Width Avg. | 5.00 LF |
| Initial Length Avg. | 11.00 LF |
| Initial Width Avg. | 11.50 LF |




Notes:

| Initial SF | 127 | Lineal Feet Trench |
|---|---|---|
| Final SF | 50 | |


| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |


| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |


| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |


| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |

| Panel # | Roll # |
|---|---|
| Final Length Avg. | LF |
| Final Width Avg. | LF |
| Initial Length Avg. | LF |
| Initial Width Avg. | LF |



Notes:

| Initial SF | - | Lineal Feet Trench |
|---|---|---|
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **923** | SF |
| **Total Pay Area This Page** | **923** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 244,884 | SF |
| Total Panel SF To Date | 245,806 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **245,806** | |
| Initial Quantity Previous | 253,822 | SF |
| Initial Quantity This Page | 1,162 | SF |
| Initial Quantity To Date | 254,983 | SF |

9/16/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 18

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/15/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 87** | **Roll #** G15C282012

| | | |
|---|---|---|
| Final Length Avg. | 166.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,853 | Lineal Feet Trench |
| Final SF | 3,746 | |

**Panel # 88** | **Roll #** G15C282012

| | | |
|---|---|---|
| Final Length Avg. | 167.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,769 | |

**Panel # 89** | **Roll #** G15C282012

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 170.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,910 | Lineal Feet Trench |
| Final SF | 3,780 | |

**Panel # 90** | **Roll #** G15C276058

| | | |
|---|---|---|
| Final Length Avg. | 168.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,780 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **15,075** | SF |
| **Total Pay Area This Page** | **15,075** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 245,806 | SF |
| Total Panel SF To Date | 260,881 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **260,881** | |
| Initial Quantity Previous | 254,983 | SF |
| Initial Quantity This Page | 15,537 | SF |
| Initial Quantity To Date | 270,520 | SF |

D136 9/18/15 INDEPENDENT QA MONITOR

## Daily Panel Placement

Page 19

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/16/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 91 — Roll # G15C276058

| | | |
|---|---|---|
| Final Length Avg. | 167.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 168.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,876 | Lineal Feet Trench |
| Final SF | 3,758 | |

### Panel # 92 — Roll # G15C276058

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,735 | |

### Panel # 93 — Roll # G15C283026

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,735 | |

### Panel # 94 — Roll # G15C283026

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 167.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,841 | Lineal Feet Trench |
| Final SF | 3,735 | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Material in Anchor Trench

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | **-** | **SF** |
| **Total Panel SF This Page** | **14,963** | **SF** |
| **Total Pay Area This Page** | **14,963** | **SF** |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 261,032 | SF |
| Total Panel SF To Date | 275,995 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **275,995** | |
| Initial Quantity Previous | 270,559 | SF |
| Initial Quantity This Page | 15,399 | SF |
| Initial Quantity To Date | 285,958 | SF |

9/18/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 20


**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/17/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL


☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 95 | Roll # G15C283026 | Panel # 96 | Roll # G15C276057 | Panel # 97 | Roll # G15C276057 |
|---|---|---|---|---|---|
| Final Length Avg. | 166.00 LF | 166.00 LF | 166.00 LF |
| Final Width Avg. | 12.50 LF | 22.50 LF | 22.50 LF |
| Initial Length Avg. | 167.00 LF | 168.00 LF | 168.00 LF |
| Initial Width Avg. | 23.00 LF | 23.00 LF | 23.00 LF |
| Notes: | | | |
| Initial SF | 3,841 | Lineal Feet Trench | 3,864 | Lineal Feet Trench | 3,864 | Lineal Feet Trench |
| Final SF | 2,075 | | 3,735 | | 3,735 | |




| Panel # | Roll # | Panel # | Roll # | Panel # | Roll # |
|---|---|---|---|---|---|
| Final Length Avg. | LF | LF | LF |
| Final Width Avg. | LF | LF | LF |
| Initial Length Avg. | LF | LF | LF |
| Initial Width Avg. | LF | LF | LF |
| Notes: | | | |
| Initial SF | - | Lineal Feet Trench | - | Lineal Feet Trench | - | Lineal Feet Trench |
| Final SF | - | | - | | - | |

| Panel # | Roll # | Panel # | Roll # |
|---|---|---|---|
| Final Length Avg. | LF | LF |
| Final Width Avg. | LF | LF |
| Initial Length Avg. | LF | LF |
| Initial Width Avg. | LF | LF |
| Notes: | | |
| Initial SF | - | Lineal Feet Trench | - | Lineal Feet Trench |
| Final SF | - | | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **9,545** | SF |
| **Total Pay Area This Page** | **9,545** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 275,995 | SF |
| Total Panel SF To Date | 285,540 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **285,540** | |
| Initial Quantity Previous | 285,958 | SF |
| Initial Quantity This Page | 11,569 | SF |
| Initial Quantity To Date | 297,527 | SF |

9/21/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 21

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/18/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # 98 | Roll # G15C276057 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,530 | | |

23 / 22.5 / 70 68 68 70 / 22.5 / 23

Notes:

| Panel # 99 | Roll # G15C276057 | | |
|---|---|---|---|
| Final Length Avg. | 68.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,541 | | |

23 / 22.5 / 70 68 69 70 / 22.5 / 23

Notes:

| Panel # 100 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,541 | | |

23 / 22.5 / 70 69 68 70 / 22.5 / 23

Notes:

| Panel # 101 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,622 | Lineal Feet Trench | |
| Final SF | 1,530 | | |

23 / 22.5 / 71 68 68 70 / 22.5 / 23

Notes:

| Panel # 102 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,530 | | |

23 / 22.5 / 70 68 68 70 / 22.5 / 23

Notes:

| Panel # 103 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 68.00 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 70.00 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 1,610 | Lineal Feet Trench | |
| Final SF | 1,530 | | |

23 / 22.5 / 70 68 68 70 / 22.5 / 23

Notes:

| Panel # 104 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 29.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 30.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 702 | Lineal Feet Trench | |
| Final SF | 664 | | |

23 / 22.5 / 33 32 27 28 / 22.5 / 23

Notes:

| Panel # 105 | Roll # G15C282022 | | |
|---|---|---|---|
| Final Length Avg. | 26.50 | LF | |
| Final Width Avg. | 22.50 | LF | |
| Initial Length Avg. | 27.50 | LF | |
| Initial Width Avg. | 23.00 | LF | |
| Initial SF | 633 | Lineal Feet Trench | |
| Final SF | 596 | | |

23 / 22.5 / 28 27 26 27 / 22.5 / 23

Notes:

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **10,463** | SF |
| **Total Pay Area This Page** | **10,463** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 285,540 | SF |
| Total Panel SF To Date | 296,002 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **296,002** | |
| Initial Quantity Previous | 297,527 | SF |
| Initial Quantity This Page | 11,006 | SF |
| Initial Quantity To Date | 308,532 | SF |

9/21/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 22

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/18/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|
| 106 | G15C282022 | 31.00 LF | 22.50 LF | 32.50 LF | 23.00 LF | 748 | 698 | |
| | | | | | | - | - | |
| | | | | | | - | - | |
| | | | | | | - | - | |
| | | | | | | - | - | |
| | | | | | | - | - | |

Notes:




| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **698** | SF |
| **Total Pay Area This Page** | **698** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 296,002 | SF |
| Total Panel SF To Date | 296,700 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **296,700** | |
| Initial Quantity Previous | 308,532 | SF |
| Initial Quantity This Page | 748 | SF |
| Initial Quantity To Date | 309,280 | SF |

9/23/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 23

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/22/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary ☐ Secondary ☐ Cell ☐ Pond ☒ Cap ☐ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 107** | **Roll #** G15C283024

| | | |
|---|---|---|
| Final Length Avg. | 163.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,784 | Lineal Feet Trench |
| Final SF | 3,668 | |

**Panel # 108** | **Roll #** G15C283024

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel # 109** | **Roll #** G15C283024

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,656 | |

**Panel # 110** | **Roll #** G15C282016

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,645 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,625** | SF |
| **Total Pay Area This Page** | **14,625** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 298,360 | SF |
| Total Panel SF To Date | 312,985 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **312,985** | |
| Initial Quantity Previous | 309,280 | SF |
| Initial Quantity This Page | 15,100 | SF |
| Initial Quantity To Date | 324,379 | SF |

9/24/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 24

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/23/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 111 — Roll # G15C282016

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench |
| Final SF | 3,645 | |

### Panel # 112 — Roll # G15C282016

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

### Panel # 113 — Roll # G15C283032

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench |
| Final SF | 3,645 | |

### Panel # 114 — Roll # G15C283032

| | | |
|---|---|---|
| Final Length Avg. | 161.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 113.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 2,599 | Lineal Feet Trench |
| Final SF | 3,634 | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Panel # — Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

### Material in Anchor Trench

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,569** | SF |
| **Total Pay Area This Page** | **14,569** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 312,985 | SF |
| Total Panel SF To Date | 327,553 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **327,553** | |
| Initial Quantity Previous | 324,379 | SF |
| Initial Quantity This Page | 13,869 | SF |
| Initial Quantity To Date | 338,248 | SF |

9/28/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 25

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/24/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 115** | **Roll #** G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 161.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 163.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,749 | Lineal Feet Trench | |
| Final SF | 3,634 | | |

**Panel # 116** | **Roll #** G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 162.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 164.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,772 | Lineal Feet Trench | |
| Final SF | 3,656 | | |

**Panel # 117** | **Roll #** G15C282023

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench | |
| Final SF | 3,690 | | |

**Panel # 118** | **Roll #** G15C283025

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench | |
| Final SF | 3,701 | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,681** | SF |
| **Total Pay Area This Page** | **14,681** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 327,553 | SF |
| Total Panel SF To Date | 342,235 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **342,235** | |
| Initial Quantity Previous | 338,248 | SF |
| Initial Quantity This Page | 15,134 | SF |
| Initial Quantity To Date | 353,382 | SF |

10/6/15

INDEPENDENT C&A MONITOR

## Daily Panel Placement

Page 26

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/25/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

[ ] Primary [ ] Secondary [ ] Cell [ ] Pond [X] Cap [ ] Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 119** | **Roll #** G15C283025

| | | |
|---|---|---|
| Final Length Avg. | 164.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,818 | Lineal Feet Trench |
| Final SF | 3,701 | |

**Panel # 120** | **Roll #** G15C283025

| | | |
|---|---|---|
| Final Length Avg. | 165.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 166.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 3,830 | Lineal Feet Trench |
| Final SF | 3,724 | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

**Panel #** | **Roll #**

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |



Notes:

| | | |
|---|---|---|
| Initial SF | - | Lineal Feet Trench |
| Final SF | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | 7,425 | SF |
| **Total Pay Area This Page** | 7,425 | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 342,235 | SF |
| Total Panel SF To Date | 349,660 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **349,660** | |
| Initial Quantity Previous | 353,382 | SF |
| Initial Quantity This Page | 7,648 | SF |
| Initial Quantity To Date | 361,030 | SF |

10/7/15 | INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 27

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 09/29/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

**Panel # 121** | Roll # G15C283030

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 170.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,910 | Lineal Feet Trench | |
| Final SF | 3,735 | | |

**Panel # 122** | Roll # G15C283030

| | | |
|---|---|---|
| Final Length Avg. | 166.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 171.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,933 | Lineal Feet Trench | |
| Final SF | 3,735 | | |

**Panel # 123** | Roll # G15C283030

| | | |
|---|---|---|
| Final Length Avg. | 148.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 150.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,450 | Lineal Feet Trench | |
| Final SF | 3,330 | | |

**Panel # 124** | Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 18.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 19.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 437 | Lineal Feet Trench | |
| Final SF | 405 | | |

**Panel # 125** | Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 164.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench | |
| Final SF | 3,690 | | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |





Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Panel #** | Roll #

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | | |
|---|---|---|---|
| Initial SF | - | Lineal Feet Trench | |
| Final SF | - | | |

**Material in Anchor Trench**

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,895** | SF |
| **Total Pay Area This Page** | **14,895** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 349,660 | SF |
| Total Panel SF To Date | 364,555 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **364,555** | |
| Initial Quantity Previous | 361,030 | SF |
| Initial Quantity This Page | 15,525 | SF |
| Initial Quantity To Date | 376,555 | SF |

10/12/15

INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 28

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 10/08/15


**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap [X] Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

### Panel # 126 — Roll # G15C283027

| | | |
|---|---|---|
| Final Length Avg. | 163.50 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 4 FEET EXTRA REQUESTED BY CUSTOMER. (SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,679 | |

### Panel # 127 — Roll # G152823027

| | | |
|---|---|---|
| Final Length Avg. | 162.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 169.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 4 FEET EXTRA REQUESTED BY CUSTOMER ( SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 3,887 | Lineal Feet Trench |
| Final SF | 3,645 | |

### Panel # 128 — Roll # G15C283027

| | | |
|---|---|---|
| Final Length Avg. | 149.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 150.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 4 FEET EXTRA REQUESTED BY CUSTOMER ( SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 3,450 | Lineal Feet Trench |
| Final SF | 3,353 | |

### Panel # 129 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 12.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 17.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 5 FEET EXTRA REQUESTED MY CUSTOMER. (SOUTH SIDE )

| | | |
|---|---|---|
| Initial SF | 391 | Lineal Feet Trench |
| Final SF | 270 | |

### Panel # 130 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 4.00 | LF |
| Final Width Avg. | 20.00 | LF |
| Initial Length Avg. | 9.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 207 | Lineal Feet Trench |
| Final SF | 80 | |

### Panel # 131 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 8.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 11.50 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes:

| | | |
|---|---|---|
| Initial SF | 265 | Lineal Feet Trench |
| Final SF | 180 | |

### Panel # 132 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | 160.00 | LF |
| Final Width Avg. | 22.50 | LF |
| Initial Length Avg. | 165.00 | LF |
| Initial Width Avg. | 23.00 | LF |





Notes: 5 FEET

| | | |
|---|---|---|
| Initial SF | 3,795 | Lineal Feet Trench |
| Final SF | 3,600 | |

### Panel # 133 — Roll # G15C282014

| | | |
|---|---|---|
| Final Length Avg. | | LF |
| Final Width Avg. | | LF |
| Initial Length Avg. | | LF |
| Initial Width Avg. | | LF |




Notes:

| | | |
|---|---|---|
| Initial SF | 173 | Lineal Feet Trench |
| Final SF | 133 | |

### Material in Anchor Trench

| | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **14,939** | SF |
| **Total Pay Area This Page** | **14,939** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 364,555 | SF |
| Total Panel SF To Date | 379,494 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **379,494** | |
| Initial Quantity Previous | 376,555 | SF |
| Initial Quantity This Page | 16,055 | SF |
| Initial Quantity To Date | 392,609 | SF |

10/12/15 INDEPENDENT CQA MONITOR

## Daily Panel Placement

Page 29

**Project Name:** Honeywell **Job #** 12-11-1399 **Deployment Date** 10/08/15

**Superintendent:** Fortino Ayala **Material Type:** LLPE 60 MIL

☐ Primary Secondary ☐ Cell ☐ Pond ☐ Cap ☒ Other:

**Description** (i.e. Phase #, Cell #, Pond # etc.) Cap construction Single layer **Roll Stock Width** 23

| Panel # | Roll # | Final Length Avg. | Final Width Avg. | Initial Length Avg. | Initial Width Avg. | Notes: | Initial SF | Final SF | Lineal Feet Trench |
|---|---|---|---|---|---|---|---|---|---|
| 134 | G15C282014 | 38.00 LF | 7.00 LF | 39.00 LF | 8.00 LF | 8 / 7 / 39 / 38 / 38 / 39 / 7 / 8 | 312 | 266 | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |
| | | LF | LF | LF | LF | | - | - | |

| Material in Anchor Trench | | |
|---|---|---|
| Total LF In Trench This Page | - | LF |
| Depth and Width Allowed in Trench | | LF |
| **Total SF Trench This Page** | - | SF |
| **Total Panel SF This Page** | **266** | SF |
| **Total Pay Area This Page** | **266** | SF |
| LF In Trench Previous | - | LF |
| LF In Trench To Date | - | LF |
| SF In Trench Previous | - | SF |
| Total SF in Trench to Date | - | SF |
| Total Panel SF Previous | 379,494 | SF |
| Total Panel SF To Date | 379,760 | SF |
| **Total Pay Area To Date Including Anchor Trench** | **379,760** | |
| Initial Quantity Previous | 392,609 | SF |
| Initial Quantity This Page | 312 | SF |
| Initial Quantity To Date | 392,921 | SF |

# Appendix J
# ESI Trial Weld Logs

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/20/15 | 17:03 | MODESTO L. | 2003 | 650 | 860 | | 95 | Peel | 96 | 101 | 95 | 109 | 99 | 99 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 102 | | 109 | | 105 | | | | | | |
| 7/21/15 | 6:50 | EMMANUEL V. | EXT 512 | | 530 | 530 | 80 | Peel | 96 | | 94 | | 98 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 99 | | 98 | | 98 | | | | | | |
| 7/21/15 | 13:45 | MODESTO L. | 2003 | 650 | 860 | | 93 | Peel | 102 | 97 | 102 | 98 | 100 | 102 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 103 | | 96 | | 105 | | | | | | |
| 7/21/15 | 14:09 | MODESTO L. | 2003 | 500 | 860 | | 93 | Peel | 95 | 99 | 95 | 100 | 98 | 101 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 102 | | 103 | | 92 | | | | | | |
| 7/21/15 | 15:14 | MODESTO L. | 2003 | 550 | 860 | | 90 | Peel | 89 | 92 | 90 | 85 | 89 | 91 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 98 | | 94 | | 98 | | | | | | |
| 7/22/15 | 6:37 | EMMANUEL V. | EXT 512 | | 500 | 490 | 70 | Peel | 98 | | 94 | | 93 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 117 | | 117 | | 118 | | | | | | |
| 7/22/15 | 13:14 | MODESTO L. | 2003 | 650 | 860 | | 83 | Peel | 100 | 99 | 107 | 95 | 102 | 104 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 117 | | 115 | | 116 | | | | | | |
| 7/22/15 | 14:58 | MODESTO L. | 2003 | 550 | 860 | | 84 | Peel | 92 | 98 | 97 | 98 | 90 | 103 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 125 | | 121 | | 118 | | | | | | |
| 7/23/15 | 13:19 | MODESTO L. | 2003 | 650 | 860 | | 83 | Peel | 107 | 102 | 107 | 103 | 107 | 98 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 116 | | 106 | | 112 | | | | | | |
| 7/23/15 | 13:25 | MODESTO L. | 2003 | 550 | 860 | | 83 | Peel | 127 | 118 | 123 | 122 | 123 | 116 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 130 | | 125 | | 130 | | | | | | |
| 7/24/15 | 6:50 | EMMANUEL V. | EXT 512 | | 500 | 490 | 69 | Peel | 90 | | 112 | | 103 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 127 | | 127 | | 128 | | | | | | |
| 7/24/15 | 13:14 | MODESTO L. | 2003 | 650 | 860 | | 83 | Peel | 97 | 101 | 96 | 106 | 103 | 101 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 120 | | 122 | | 119 | | | | | | |
| 7/24/15 | 13:17 | MODESTO L. | 2003 | 500 | 860 | | 83 | Peel | 96 | 101 | 101 | 106 | 96 | 105 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 117 | | 111 | | 118 | | | | | | |
| 7/24/15 | 13:21 | MODESTO L. | 2003 | 550 | 860 | | 83 | Peel | 93 | 102 | 97 | 100 | 105 | 95 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 111 | | 111 | | 110 | | | | | | |
| 7/27/15 | 13:15 | EMMANUEL V. | EXT 512 | | 500 | 450 | 85 | Peel | 122 | | 122 | | 121 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 118 | | 125 | | 126 | | | | | | |
| 7/28/15 | 7:00 | EMMANUEL V. | EXT 512 | | 500 | 450 | 75 | Peel | 102 | | 102 | | 107 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 137 | | 132 | | 131 | | | | | | |

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/28/15 | 13:14 | MODESTO L. | 2003 | 650 | 860 | | 90 | Peel | 99 | 101 | 96 | 94 | 97 | 94 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 103 | | 110 | | 111 | | | | | | |
| 7/28/15 | 13:17 | MODESTO L. | 2003 | 550 | 860 | | 90 | Peel | 97 | 100 | 98 | 94 | 98 | 94 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 101 | | 103 | | 104 | | | | | | |
| 7/28/15 | 13:19 | MODESTO L. | 2003 | 500 | 860 | | 90 | Peel | 99 | 102 | 105 | 104 | 100 | 101 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 110 | | 108 | | 107 | | | | | | |
| 7/29/15 | 6:45 | EMMANUEL V. | EXT 512 | | 490 | 400 | 75 | Peel | 98 | | 103 | | 104 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 121 | | 118 | | 120 | | | | | | |
| 7/29/15 | 15:08 | MODESTO L. | 2003 | 650 | 860 | | 94 | Peel | 101 | 92 | 103 | 92 | 101 | 93 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 108 | | 110 | | 110 | | | | | | |
| 7/30/15 | 6:40 | EMMANUEL V. | EXT 512 | | 480 | 400 | 79 | Peel | 114 | | 96 | | 110 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 116 | | 111 | | | | | | |
| 8/3/15 | 14:53 | MODESTO L. | 2003 | 450 | 860 | | 89 | Peel | 109 | 109 | 110 | 115 | 107 | 111 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 113 | | 117 | | 113 | | | | | | |
| 8/3/15 | 15:12 | MODESTO L. | 2003 | 650 | 860 | | 90 | Peel | 93 | 101 | 94 | 101 | 93 | 94 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 122 | | 125 | | 121 | | | | | | |
| 8/3/15 | 15:15 | MODESTO L. | 2003 | 400 | 860 | | 90 | Peel | 90 | 95 | 91 | 96 | 100 | 107 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 128 | | 116 | | 120 | | | | | | |
| 8/3/15 | 19:14 | MODESTO L. | 1480 | 450 | 860 | | 88 | Peel | 101 | 99 | 98 | 103 | 98 | 100 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 111 | | 110 | | 113 | | | | | | |
| 8/3/15 | 19:15 | MODESTO L. | 1480 | 400 | 860 | | 88 | Peel | 92 | 96 | 94 | 96 | 96 | 95 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 108 | | 110 | | 111 | | | | | | |
| 8/4/15 | 12:37 | PEDRO S. | EXT 512 | | 500 | 500 | 89 | Peel | 114 | | 118 | | 119 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 128 | | 135 | | 126 | | | | | | |
| 8/5/15 | 7:05 | PEDRO S. | EXT 512 | | 500 | 500 | 75 | Peel | 118 | | 117 | | 118 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 124 | | 126 | | 120 | | | | | | |
| 8/5/15 | 14:50 | MODESTO L. | 2025 | 450 | 860 | | 88 | Peel | 97 | 106 | 100 | 104 | 100 | 106 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 113 | | 115 | | 118 | | | | | | |
| 8/5/15 | 14:55 | MODESTO L. | 2025 | 600 | 860 | | 88 | Peel | 94 | 101 | 104 | 95 | 100 | 101 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 118 | | 119 | | 116 | | | | | | |
| 8/6/15 | 14:03 | MODESTO L. | 2025 | 450 | 860 | | 82 | Peel | 104 | 92 | 94 | 100 | 91 | 100 | | | | | PASS |
| S P T | PM | | | | | | | Shear | 116 | | 119 | | 119 | | | | | | |

## *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/6/15 | 14:06 | MODESTO L. | 2025 | 600 | 860 | | 82 | Peel | 92 | 100 | 94 | 100 | 93 | 103 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 111 | | 113 | | 116 | | | | | | |
| 8/6/15 | 14:08 | MODESTO L. | 2025 | 400 | 860 | | 82 | Peel | 112 | 110 | 112 | 112 | 111 | 109 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 115 | | 111 | | 113 | | | | | | |
| 8/7/15 | 6:43 | PEDRO S. | EXT 512 | | 530 | 530 | 69 | Peel | 123 | | 126 | | 126 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 133 | | 134 | | 130 | | | | | | |
| 8/7/15 | 13:11 | MODESTO L. | 2025 | 600 | 860 | | 84 | Peel | 99 | 104 | 100 | 100 | 95 | 102 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 113 | | 112 | | 115 | | | | | | |
| 8/7/15 | 13:15 | MODESTO L. | 2025 | 450 | 860 | | 84 | Peel | 100 | 97 | 98 | 103 | 105 | 99 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 112 | | 114 | | 116 | | | | | | |
| 8/7/15 | 13:18 | MODESTO L. | 2025 | 400 | 860 | | 84 | Peel | 114 | 114 | 107 | 107 | 110 | 105 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 112 | | 115 | | 116 | | | | | | |
| 8/10/15 | 6:54 | PEDRO S. | EXT 512 | | 530 | 530 | 70 | Peel | 127 | | 124 | | 131 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 135 | | 138 | | 135 | | | | | | |
| 8/10/15 | 10:55 | MODESTO L. | 2025 | 600 | 860 | | 80 | Peel | 97 | 93 | 97 | 91 | 104 | 99 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 113 | | 117 | | 119 | | | | | | |
| 8/10/15 | 14:00 | PEDRO S. | EXT 512 | | 530 | 530 | 81 | Peel | 120 | | 118 | | 111 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 128 | | 123 | | 124 | | | | | | |
| 8/10/15 | 15:20 | MODESTO L. | 2025 | 600 | 860 | | 81 | Peel | 104 | 104 | 106 | 101 | 100 | 109 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 122 | | 121 | | 121 | | | | | | |
| 8/12/15 | 8:15 | PEDRO S. | EXT 512 | | 530 | 530 | 72 | Peel | 119 | | 119 | | 116 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 128 | | 127 | | 123 | | | | | | |
| 8/13/15 | 8:30 | MODESTO L. | 2025 | 600 | 860 | | 72 | Peel | 104 | 99 | 105 | 101 | 98 | 100 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 122 | | 121 | | 122 | | | | | | |
| 8/14/15 | 9:00 | MODESTO L. | 2025 | 600 | 860 | | 77 | Peel | 93 | 99 | 91 | 97 | 91 | 100 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 116 | | 118 | | 119 | | | | | | |
| 8/14/15 | 9:03 | MODESTO L. | 2025 | 450 | 860 | | 77 | Peel | 99 | 97 | 101 | 99 | 108 | 96 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 115 | | 118 | | 116 | | | | | | |
| 8/14/15 | 9:05 | MODESTO L. | 2025 | 400 | 860 | | 77 | Peel | 112 | 113 | 114 | 113 | 114 | 116 | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 118 | | 119 | | 118 | | | | | | |
| 8/14/15 | 11:00 | EMMANUEL V. | EXT 512 | | 500 | 500 | 82 | Peel | 105 | | 111 | | 106 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 113 | | 115 | | | | | | |

# *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/9/15 | 7:50 | PEDRO S. | EXT 512 | | 550 | 550 | 76 | Peel | 104 | | 106 | | 103 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 114 | | 116 | | | | | | |
| 9/9/15 | 15:00 | PEDRO S. | 2025 | 400 | 860 | | 90 | Peel | 95 | 91 | 93 | 95 | 90 | 93 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 120 | | 117 | | 118 | | | | | | |
| 9/9/15 | 15:05 | PEDRO S. | 2025 | 350 | 860 | | 90 | Peel | 92 | 95 | 89 | 91 | 93 | 90 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 119 | | 121 | | 117 | | | | | | |
| 9/9/15 | 15:10 | PEDRO S. | 2025 | 300 | 860 | | 90 | Peel | 106 | 97 | 103 | 98 | 104 | 101 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 118 | | 119 | | 118 | | | | | | |
| 9/11/15 | 13:55 | PEDRO S. | 2025 | 300 | 860 | | 79 | Peel | 100 | 100 | 102 | 101 | 104 | 103 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 98 | | 101 | | 106 | | | | | | |
| 9/11/15 | 14:20 | EMMANUEL V. | EXT 512 | | 510 | 510 | 79 | Peel | 93 | | 93 | | 97 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 107 | | 109 | | 100 | | | | | | |
| 9/14/15 | 10:57 | EMMANUEL V. | EXT 512 | | 550 | 550 | 68 | Peel | 108 | | 106 | | 109 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 113 | | 111 | | 110 | | | | | | |
| 9/14/15 | 13:30 | EMMANUEL V. | EXT 512 | | 540 | 540 | 74 | Peel | 111 | | 107 | | 114 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 116 | | 119 | | 115 | | | | | | |
| 9/15/15 | 9:50 | PEDRO S. | 2025 | 400 | 860 | | 70 | Peel | 105 | 100 | 106 | 103 | 102 | 103 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 120 | | 122 | | 123 | | | | | | |
| 9/15/15 | 9:51 | PEDRO S. | 2025 | 350 | 860 | | 70 | Peel | 103 | 102 | 106 | 108 | 108 | 102 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 118 | | 118 | | 116 | | | | | | |
| 9/15/15 | 9:52 | PEDRO S. | 2025 | 300 | 860 | | 70 | Peel | 102 | 103 | 101 | 102 | 102 | 99 | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 112 | | 110 | | 108 | | | | | | |
| 9/15/15 | 13:00 | PEDRO S. | 2025 | 350 | 860 | | 81 | Peel | 100 | 99 | 101 | 98 | 102 | 101 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 109 | | 106 | | 106 | | | | | | |
| 9/16/15 | 7:20 | EMMANUEL V. | EXT 512 | | 550 | 550 | 66 | Peel | 104 | | 106 | | 109 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 108 | | 111 | | 110 | | | | | | |
| 9/16/15 | 13:00 | PEDRO S. | 2025 | 450 | 860 | | 83 | Peel | 93 | 90 | 93 | 89 | 92 | 95 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 108 | | 104 | | 105 | | | | | | |
| 9/16/15 | 13:01 | PEDRO S. | 2025 | 350 | 860 | | 83 | Peel | 88 | 91 | 83 | 86 | 90 | 90 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 103 | | 102 | | 107 | | | | | | |
| 9/16/15 | 13:02 | PEDRO S. | 2025 | 300 | 860 | | 83 | Peel | 100 | 98 | 101 | 103 | 100 | 103 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 106 | | 107 | | 109 | | | | | | |

## *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/16/15 | 14:15 | EMMANUEL V. | EXT 512 | | 550 | 550 | 85 | Peel | 97 | | 94 | | 96 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 98 | | 100 | | 97 | | | | | | |
| 9/17/15 | 7:20 | EMMANUEL V. | EXT 512 | | 550 | 550 | 65 | Peel | 104 | | 99 | | 101 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 106 | | 106 | | 103 | | | | | | |
| 9/17/15 | 14:20 | PEDRO S. | 2025 | 450 | 860 | | 86 | Peel | 93 | 95 | 89 | 94 | 95 | 90 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 113 | | 109 | | 111 | | | | | | |
| 9/17/15 | 14:21 | PEDRO S. | 2025 | 350 | 860 | | 86 | Peel | 90 | 90 | 91 | 92 | 89 | 93 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 106 | | 103 | | 102 | | | | | | |
| 9/18/15 | 11:00 | PEDRO S. | 2025 | 450 | 860 | | 80 | Peel | 100 | 100 | 99 | 100 | 98 | 96 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 103 | | 102 | | 106 | | | | | | |
| 9/18/15 | 11:01 | PEDRO S. | 2025 | 350 | 860 | | 80 | Peel | 93 | 96 | 95 | 94 | 95 | 95 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 101 | | 104 | | 102 | | | | | | |
| 9/18/15 | 13:00 | PEDRO S. | 2025 | 450 | 860 | | 85 | Peel | 101 | 98 | 99 | 100 | 96 | 99 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 106 | | 105 | | 103 | | | | | | |
| 9/18/15 | 13:01 | PEDRO S. | 2025 | 350 | 860 | | 85 | Peel | 91 | 94 | 96 | 95 | 93 | 96 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 102 | | 102 | | 103 | | | | | | |
| 9/18/15 | 13:03 | PEDRO S. | 2025 | 300 | 860 | | 85 | Peel | 98 | 101 | 99 | 100 | 96 | 100 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 104 | | 103 | | 102 | | | | | | |
| 9/21/15 | 11:10 | EMMANUEL V. | EXT 512 | | 550 | 550 | 68 | Peel | 91 | | 90 | | 93 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 108 | | 103 | | 106 | | | | | | |
| 9/21/15 | 13:02 | EMMANUEL V. | EXT 512 | | 550 | 550 | 73 | Peel | 90 | | 90 | | 93 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 102 | | 103 | | 102 | | | | | | |
| 9/22/15 | 10:20 | PEDRO S. | 2025 | 450 | 860 | | 67 | Peel | 99 | 106 | 102 | 103 | 100 | 105 | | | | | PASS |
| S TO S | AM | | | | | | | Shear | 110 | | 107 | | 111 | | | | | | |
| 9/22/15 | 10:21 | PEDRO S. | 2025 | 350 | 860 | | 67 | Peel | 108 | 101 | 108 | 99 | 107 | 102 | | | | | PASS |
| S TO T | AM | | | | | | | Shear | 116 | | 115 | | 113 | | | | | | |
| 9/22/15 | 10:23 | PEDRO S. | 2025 | 300 | 860 | | 67 | Peel | 101 | 103 | 100 | 100 | 98 | 102 | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 106 | | 106 | | 109 | | | | | | |
| 9/22/15 | 13:05 | EMMANUEL V. | EXT 512 | | 550 | 550 | 73 | Peel | 98 | | 99 | | 101 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 106 | | 109 | | 107 | | | | | | |
| 9/23/15 | 7:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 62 | Peel | 93 | | 94 | | 97 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 111 | | 109 | | 108 | | | | | | |

## *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 **PPI**

**Job Description:** Single Layer cap **Secondary** **Cell** **Peel Test Fusion Minimum** 75 **PPI**

**Reported By :** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 **PPI**

**Other :** Cap construction

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/23/15 | 15:25 | PEDRO S. | 2025 | 450 | 860 | | 79 | Peel | 93 | 92 | 96 | 96 | 92 | 93 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 102 | | 102 | | 102 | | | | | | |
| 9/24/15 | 7:20 | EMMANUEL V. | EXT 512 | | 550 | 550 | 62 | Peel | 118 | | 115 | | 112 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 122 | | 119 | | 118 | | | | | | |
| 9/24/15 | 14:30 | PEDRO S. | 2025 | 450 | 860 | | 80 | Peel | 89 | 89 | 88 | 89 | 87 | 88 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 100 | | 102 | | 102 | | | | | | |
| 9/24/15 | 14:31 | PEDRO S. | 2025 | 350 | 860 | | 80 | Peel | 85 | 87 | 85 | 91 | 86 | 89 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 101 | | 100 | | 103 | | | | | | |
| 9/25/15 | 7:00 | PEDRO S. | EXT 512 | | 550 | 550 | 65 | Peel | 106 | | 109 | | 110 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 112 | | 116 | | 119 | | | | | | |
| 9/25/15 | 14:15 | PEDRO S. | EXT 512 | 450 | 860 | | 74 | Peel | 89 | 89 | 89 | 90 | 91 | 88 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 100 | | 101 | | 100 | | | | | | |
| 9/25/15 | 14:17 | PEDRO S. | EXT 512 | | 550 | 550 | 73 | Peel | 99 | | 101 | | 100 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 103 | | 105 | | 102 | | | | | | |
| 9/29/15 | 14:30 | EMMANUEL V. | EXT 512 | | 550 | 550 | 80 | Peel | 98 | | 100 | | 99 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 106 | | 104 | | 103 | | | | | | |
| 9/29/15 | 14:30 | PEDRO S. | 2025 | 400 | 860 | | 80 | Peel | 92 | 91 | 94 | 90 | 89 | 87 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 103 | | 102 | | 102 | | | | | | |
| 9/29/15 | 14:31 | PEDRO S. | 2025 | 300 | 860 | | 80 | Peel | 93 | 90 | 89 | 91 | 88 | 90 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 103 | | 101 | | 102 | | | | | | |
| 9/29/15 | 14:32 | PEDRO S. | 2025 | 350 | 860 | | 80 | Peel | 90 | 88 | 89 | 93 | 92 | 90 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 104 | | 101 | | 101 | | | | | | |
| 10/7/15 | 8:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 59 | Peel | 96 | | 96 | | 108 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 130 | | 129 | | 127 | | | | | | |
| 10/7/15 | 13:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 73 | Peel | 93 | | 90 | | 92 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 126 | | 127 | | 124 | | | | | | |
| 10/8/15 | 14:00 | PEDRO S. | 2025 | 450 | 860 | | 73 | Peel | 103 | 108 | 103 | 107 | 101 | 104 | | | | | PASS |
| S TO S | PM | | | | | | | Shear | 124 | | 126 | | 123 | | | | | | |
| 10/8/15 | 14:01 | PEDRO S. | 2025 | 350 | 860 | | 73 | Peel | 109 | 108 | 112 | 108 | 109 | 105 | | | | | PASS |
| S TO T | PM | | | | | | | Shear | 127 | | 125 | | 126 | | | | | | |
| 10/8/15 | 14:03 | PEDRO S. | 2025 | 300 | 860 | | 73 | Peel | 119 | 126 | 121 | 121 | 120 | 121 | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 123 | | 124 | | 123 | | | | | | |

## *Environmental Specialties International Inc.*
## Preweld Test Report

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Single Layer cap **Secondary** **Cell**

**Reported By :** Lyssa-Tran Tran **Cap** x

**Other :** Cap construction

**Peel Test Extrusion Minimum** 66 **PPI**

**Peel Test Fusion Minimum** 75 **PPI**

**Shear Test Minimum** 90 **PPI**

**Liner Types** **S = Smooth** **T = Textured** **SG = Super Grip**

| Weld Date / Liner Type | Time AM \| PM | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Ambient Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10/8/15 | 17:00 | EMMANUEL V. | EXT 512 | | 550 | 550 | 68 | Peel | 119 | | 119 | | 119 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 122 | | 123 | | 126 | | | | | | |
| 10/9/15 | 7:30 | PEDRO S. | EXT 512 | | 550 | 550 | 61 | Peel | 116 | | 118 | | 123 | | | | | | PASS |
| T TO T | AM | | | | | | | Shear | 129 | | 131 | | 127 | | | | | | |
| 10/9/15 | 13:00 | PEDRO S. | EXT 512 | | 550 | 550 | 70 | Peel | 110 | | 113 | | 113 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 123 | | 124 | | 122 | | | | | | |
| 10/12/15 | 15:30 | EDFY N. | EXT 512 | | 550 | 550 | 76 | Peel | 114 | | 112 | | 117 | | | | | | PASS |
| T TO T | PM | | | | | | | Shear | 125 | | 130 | | 123 | | | | | | |
| 11/4/15 | 10:40 | EDFY N. | EXT 77 | | 550 | 550 | 67 | Peel | 103 | | 94 | | 98 | | | | | | Pass |
| T TO T | AM | | | | | | | Shear | 131 | | 129 | | 125 | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |
| | : | | | | | | | Peel | | | | | | | | | | | |
| TO | | | | | | | | Shear | | | | | | | | | | | |

# Appendix K
# ESI Seam Control (Non-Destructive) Test Logs

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/20/15 | 1 / 2 | 135 | 17:25 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 6:35 / 30 | 6:40 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | SEOS TO 135'N (COVER BY RP-6 ) | | | | | |
| 7/20/15 | 1 / 2 | 28 | 17:46 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7:00 / 30 | 7:05 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | 135'N (COVER BY RP-6 ) TO NEOS | | | | | |
| 7/20/15 | 2 / 3 | 98 | 17:55 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 6:35 / 30 | 6:40 / 30 | 0 | PASS |
| Seam Notes | NEOS TO SEOS | | | | | | | | SEOS TO 98'N ( RP-1 ) | | | | | |
| 7/20/15 | 2 / 3 | 67 | 18:09 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7:01 / 30 | 7:06 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | 98'N ( RP-1 ) TO NEOS | | | | | |
| 7/20/15 | 3 / 4 | 94 | 18:20 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7:12 / 30 | 7:17 / 27 | 3 | PASS |
| Seam Notes | SEOS TO NEOS | | | | | | | | SEOS TO 94'N ( RP-2 ) | | | | | |
| 7/20/15 | 3 / 4 | 72 | 18:34 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 7 :12 / 30 | 7:17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | 94'N ( RP-2 ) TO NEOS | | | | | |
| 7/21/15 | 4 / 5 | 165 | 14:14 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 14 46 / 30 | 14 51 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 6 / 7 | 22.5 | 14:30 PM | MODESTO L. | 2003 | 500 | 860 | | 7/21/15 | Air Pressure | 15 03 / 30 | 15 08 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 5 / 7 | 6 | 14:38 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 14 55 / 30 | 15 00 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/21/15 | 5 / 6 | 157 | 14:39 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 14 55 / 30 | 15 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 7 / 8 | 6 | 14:47 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Vacuum | | | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 6 / 8 | 157 | 14:48 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 15 16 / 30 | 15 21 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/21/15 | 8 / 9 | 163 | 15:17 PM | MODESTO L. | 2003 | 650 | 860 | | 7/21/15 | Air Pressure | 15 46 / 30 | 15 51 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/22/15 | 9 / 10 | 52 | 13:30 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 11 / 30 | 14 16 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | SEOS TO 52'N (RP-15 ) | | | | | | |
| 7/22/15 | 9 / 10 | 111 | 13:38 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 11 / 30 | 14 16 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | 52'N (RP-15 ) TO NEOS | | | | | | |
| 7/22/15 | 10 / 11 | 164 | 13:50 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 12 / 30 | 14 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/22/15 | 11 / 12 | 164 | 14:10 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 14 21 / 30 | 14 26 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/22/15 | 12 / 13 | 164 | 15:00 PM | MODESTO L. | 2003 | 650 | 860 | | 7/22/15 | Air Pressure | 15 17 / 30 | 15 22 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/23/15 | 13 / 14 | 46 | 13:30 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 16 20 / 30 | 16 25 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 46'S (RP-17 ) | | | | | | | | | | | | | |
| 7/23/15 | 13 / 14 | 118 | 13:37 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 16 26 / 30 | 16 31 / 27 | 3 | PASS |
| Seam Notes | 46'S (RP-17 ) TO SEOS | | | | | | | | | | | | | |
| 7/23/15 | 14 / 15 | 164 | 13:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 32 / 30 | 15 37 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/23/15 | 15 / 16 | 78 | 14:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 16 07 / 30 | 16 12 / 28 | 2 | PASS |
| Seam Notes | NEOS TO 78'S (RP-25 ) | | | | | | | | | | | | | |
| 7/23/15 | 15 / 16 | 87 | 14:27 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 40 / 30 | 15 45 / 30 | 0 | PASS |
| Seam Notes | 78'S (RP-25 ) TO SEOS | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 23 | 14:43 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 09 / 30 | 15 14 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 23'S (RP-22 ) | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 57 | 14:43 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 57 / 30 | 16 02 / 30 | 0 | PASS |
| Seam Notes | 23'S (RP-22 ) TO 80'S ( RP-27) | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 35 | 14:54 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 51 / 30 | 15 56 / 30 | 0 | PASS |
| Seam Notes | 80'S ( RP-27 ) TO 115'S (RP-28) | | | | | | | | | | | | | |
| 7/23/15 | 16 / 17 | 15 | 14:59 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 51 / 30 | 15 56 / 30 | 0 | PASS |
| Seam Notes | 115'S (RP-28 ) TO 130'S (RP-29) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/23/15 | 16 / 17 | 35 | 15:01 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 42 / 30 | 15 47 / 28 | 2 | PASS |
| Seam Notes | 130'S (RP-29) TO SEOS | | | | | | | | | | | | | |
| 7/23/15 | 17 / 18 | 101 | 15:07 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 55 / 30 | 16 00 / 27 | 3 | PASS |
| Seam Notes | NEOS TO 101'S (RP-31) | | | | | | | | | | | | | |
| 7/23/15 | 17 / 18 | 63 | 15:23 PM | MODESTO L. | 2003 | 650 | 860 | | 7/23/15 | Air Pressure | 15 47 / 30 | 15 52 / 30 | 0 | PASS |
| Seam Notes | 101'S (RP-31) TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 18 / 19 | 55 | 14:25 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 48 / 30 | 16 53 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 55'S (RP-44) | | | | | | | | | | | | | |
| 7/24/15 | 18 / 19 | 109 | 14:33 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 02 / 30 | 16 07 / 28 | 2 | PASS |
| Seam Notes | 55'S (RP-44) TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 19 / 20 | 164 | 14:50 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 06 / 30 | 16 12 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/24/15 | 20 / 21 | 30 | 15:10 PM | MODESTO L. | 2003 | 550 | 860 | | 7/24/15 | Air Pressure | 16 44 / 30 | 16 49 / 28 | 2 | PASS |
| Seam Notes | NEOS TO 30'S (RP-51) | | | | | | | | | | | | | |
| 7/24/15 | 20 / 21 | 98 | 15:14 PM | MODESTO L. | 2003 | 550 | 860 | | 7/24/15 | Air Pressure | 16 42 / 30 | 16 47 / 28 | 2 | PASS |
| Seam Notes | 30'S (RP-51) TO 128'S (RP-40) | | | | | | | | | | | | | |
| 7/24/15 | 20 / 21 | 36 | 15:29 PM | MODESTO L. | 2003 | 550 | 860 | | 7/24/15 | Air Pressure | 16 12 / 30 | 16 17 / 28 | 2 | PASS |
| Seam Notes | 128'S (RP-40) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/24/15 | 21 / 22 | 84 | 15:35 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 36 / 30 | 16 41 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 84'S (RP-67) | | | | | | | | | | | | | |
| 7/24/15 | 21 / 22 | 80 | 15:48 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 27 / 30 | 16 32 / 30 | 0 | PASS |
| Seam Notes | 84'S (RP-67) TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 22 / 23 | 76 | 15:50 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 35 / 30 | 16 40 / 27 | 3 | PASS |
| Seam Notes | NEOS TO 76'S (RP-68) | | | | | | | | | | | | | |
| 7/24/15 | 22 / 23 | 21 | 16:01 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 38 / 30 | 16 43 / 30 | 0 | PASS |
| Seam Notes | 76'S (RP-68) TO 97'S (RP-76) | | | | | | | | | | | | | |
| 7/24/15 | 22 / 23 | 67 | 16:04 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 24 / 30 | 16 29 / 30 | 0 | PASS |
| Seam Notes | 97'S (RP-76)TO SEOS | | | | | | | | | | | | | |
| 7/24/15 | 23 / 24 | 164 | 16:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/24/15 | Air Pressure | 16 52 / 30 | 16 57 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/28/15 | 24 / 25 | 127 | 13:25 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 01 / 30 | 16 06 / 29 | 1 | PASS |
| Seam Notes | NEOS TO 127'S (RP-88) | | | | | | | | | | | | | |
| 7/28/15 | 24 / 25 | 37 | 13:44 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 00 / 30 | 16 05 / 30 | 0 | PASS |
| Seam Notes | 127'S (RP-88 )TO SEOS | | | | | | | | | | | | | |
| 7/28/15 | 25 / 26 | 110 | 13:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 09 / 30 | 16 14 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 110'N (RP-95 ) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/29/15 | 25 / 26 | 19 | 7:45 AM | EMMANUEL V. | EXT 512 | | 490 | 400 | 7/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 110'N( RP-95 ) TO 129'N (RP-95 ) | | | | | | | | | | | | | |
| 7/28/15 | 25 / 26 | 34 | 14:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 13 / 30 | 16 18 / 30 | 0 | PASS |
| Seam Notes | 129'N (RP-95 )TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 26 / 27 | 71 | 13:53 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 16 / 30 | 16 21 / 27 | 3 | PASS |
| Seam Notes | SEOS TO 71'N (RP-97) | | | | | | | | | | | | | |
| 7/28/15 | 26 / 27 | 92 | 14:04 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 17 / 30 | 16 22 / 30 | 0 | PASS |
| Seam Notes | 71'N (RP-97) TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 27 / 28 | 34 | 14:22 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 22 / 30 | 16 27 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 34'N (RP-121) | | | | | | | | | | | | | |
| 7/28/15 | 27 / 28 | 129 | 14:27 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 22 / 30 | 16 27 / 30 | 0 | PASS |
| Seam Notes | 34'N (RP-121 ) TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 28 / 29 | 61 | 15:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 29 / 30 | 16 34 / 28 | 2 | PASS |
| Seam Notes | SEOS TO 61'N (RP-115) | | | | | | | | | | | | | |
| 7/29/15 | 28 / 29 | 12 | 10:45 AM | EMMANUEL V. | EXT 512 | | 490 | 400 | 7/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 61'N (RP-115)TO 73'N(RP-114) | | | | | | | | | | | | | |
| 7/28/15 | 28 / 29 | 47 | 16:01 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 32 / 30 | 16 37 / 30 | 0 | PASS |
| Seam Notes | 73'N (RP-114)TO 120'N (RP-105) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7/28/15 | 28 / 29 | 44 | 16:09 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 36 / 30 | 16 41 / 29 | 1 | PASS |
| Seam Notes | 120'N (RP-105)TO NEOS | | | | | | | | | | | | | |
| 7/28/15 | 29 / 30 | 125 | 16:16 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 38 / 30 | 16 43 / 28 | 2 | PASS |
| Seam Notes | SEOS TO 125'N (RP-108) | | | | | | | | | | | | | |
| 7/28/15 | 29 / 30 | 39 | 16:26 PM | MODESTO L. | 2003 | 650 | 860 | | 7/28/15 | Air Pressure | 16 38 / 30 | 16 43 / 28 | 2 | PASS |
| Seam Notes | 125'N (RP-108) TO NEOS | | | | | | | | | | | | | |
| 7/29/15 | 30 / 31 | 163 | 15:30 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 41 / 30 | 16 46 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/29/15 | 31 / 32 | 163 | 15:52 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 50 / 30 | 16 55 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/29/15 | 32 / 33 | 163 | 16:15 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 53 / 30 | 16 58 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 7/29/15 | 33 / 34 | 25 | 8:00 AM | EMMANUEL V. | EXT 512 | | 480 | 400 | 7/30/15 | Vacuum | | | 0 | PASS |
| Seam Notes | SEOS TO 21'N (RP-133) | | | | | | | | | | | | | |
| 7/29/15 | 33 / 34 | 139 | 16:33 PM | MODESTO L. | 2003 | 650 | 860 | | 7/29/15 | Air Pressure | 16 54 / 30 | 16 59 / 29 | 1 | PASS |
| Seam Notes | 21'N (RP-133) TO NEOS | | | | | | | | | | | | | |
| 8/3/15 | 35 / 36 | 84 | 15:22 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 45 / 30 | 14 40 / 29 | 1 | PASS |
| Seam Notes | EEOS TO 84'W(RP-153) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 35 / 36 | 10 | 15:35 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 38 / 30 | 13 43 / 30 | 0 | PASS |
| Seam Notes | 84'W ( RP-153) TO WEOS | | | | | | | | | | | | | |
| 8/3/15 | 36 / 37 | 95 | 15:43 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 29 / 30 | 13 34 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 37 / 38 | 98 | 16:01 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 23 / 30 | 13 28 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 38 / 39 | 101 | 16:28 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 14 / 30 | 13 19 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 39 / 40 | 102 | 16:52 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 13 05 / 30 | 13 10 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 35 | 10 | 17:26 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 45 / 30 | 13 50 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 10'S (RP-157) | | | | | | | | | | | | | |
| 8/3/15 | 34 / 35 | 11 | 17:27 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 38 / 30 | 13 43 / 30 | 0 | PASS |
| Seam Notes | 10'S (RP-157) TO SEOS | | | | | | | | | | | | | |
| 8/3/15 | 34 / 36 | 22.5 | 17:29 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 31 / 30 | 13 36 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 37 | 22.5 | 17:34 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 20 / 30 | 13 25 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 34 / 38 | 22.5 | 17:39 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 09 / 30 | 13 14 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 39 | 22.5 | 17:44 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 05 / 30 | 13 10 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 40 | 22.5 | 17:47 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 12 36 / 30 | 12 41 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 34 / 41 | 38 | 17:50 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 12 30 / 30 | 13 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 42 / 43 | 38 | 18:11 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 14 13 / 30 | 14 18 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 40 / 42 | 22.5 | 18:13 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 14 / 30 | 14 19 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 39 / 42 | 22.5 | 18:16 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 07 / 30 | 14 12 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 38 / 42 | 22.5 | 18:19 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 07 / 30 | 14 12 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 37 / 42 | 22.5 | 18:21 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 36 / 42 | 22.5 | 18:24 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 53 / 30 | 13 58 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 35 / 42 | 22.5 | 18:28 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 13 53 / 30 | 13 58 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 45 / 46 | 10 | 18:36 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 12 48 / 30 | 12 53 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 44 / 46 | 27 | 18:39 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 12 48 / 30 | 12 48 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 44 / 45 | 25 | 18:41 PM | MODESTO L. | 2003 | 650 | 860 | | 8/4/15 | Air Pressure | 12 42 / 30 | 12 47 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 43 / 46 | 10 | 18:48 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 14 25 / 30 | 14 30 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 43 / 44 | 23 | 18:49 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 14 19 / 30 | 14 24 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 40 / 43 | 17 | 18:55 PM | MODESTO L. | 2003 | 450 | 860 | | 8/4/15 | Air Pressure | 14 16 / 30 | 14 21 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 40 / 44 | 48 | 18:57 PM | MODESTO L. | 2003 | 400 | 860 | | 8/4/15 | Air Pressure | 14 17 / 30 | 14 22 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | EEOS TO 48'W (RP-184) | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/3/15 | 40 / 44 | 13 | 19:17 PM | MODESTO L. | 1480 | 400 | 860 | | 8/4/15 | Air Pressure | 13 00 / 30 | 13 05 / 30 | 0 | PASS |
| Seam Notes | 48'W (RP-184) TO WEOS | | | | | | | | | | | | | |
| 8/3/15 | 40 / 41 | 23 | 19:25 PM | MODESTO L. | 1480 | 450 | 860 | | 8/4/15 | Air Pressure | 12 30 / 30 | 12 35 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 41 / 44 | 18 | 19:28 PM | MODESTO L. | 1480 | 400 | 860 | | 8/4/15 | Air Pressure | 12 42 / 30 | 12 47 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/3/15 | 41 / 45 | 10 | 19:31 PM | MODESTO L. | 1480 | 400 | 860 | | 8/4/15 | Air Pressure | 12 42 / 30 | 12 47 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/5/15 | 42 / 47 | 167 | 16:20 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 26 / 30 | 15 31 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/5/15 | 47 / 48 | 106 | 16:50 PM | MODESTO L. | 2025 | 450 | 860 | | 8/6/15 | Air Pressure | 15 37 / 30 | 15 42 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 106'S (RP-195 ) | | | | | | | | | | | | | |
| 8/5/15 | 47 / 48 | 61 | 17:13 PM | MODESTO L. | 2025 | 450 | 860 | | 8/6/15 | Air Pressure | 15 37 / 30 | 15 42 / 30 | 0 | PASS |
| Seam Notes | 106'S (RP-195 ) TO SEOS | | | | | | | | | | | | | |
| 8/5/15 | 48 / 49 | 86 | 18:15 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 50 / 30 | 15 55 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 86'S (RP-196 ) | | | | | | | | | | | | | |
| 8/5/15 | 48 / 49 | 81 | 18:29 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 52 / 30 | 15 57 / 30 | 0 | PASS |
| Seam Notes | 86'S (RP-196 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/6/15 | 49 / 50 | 167 | 14:15 PM | MODESTO L. | 2025 | 450 | 860 | | 8/6/15 | Air Pressure | 15 54 / 30 | 15 59 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 51 / 52 | 22.5 | 14:45 PM | MODESTO L. | 2025 | 400 | 860 | | 8/6/15 | Air Pressure | 15 58 / 30 | 16 03 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 50 / 51 | 163 | 14:50 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 55 / 30 | 16 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 50 / 52 | 5 | 15:05 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 55 / 30 | 16 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 51 / 53 | 164 | 15:10 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 15 59 / 30 | 16 04 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 52 / 53 | 5 | 15:24 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 16 00 / 30 | 16 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/6/15 | 53 / 54 | 15 | 15:33 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 16 06 / 30 | 16 11 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 15'S (RP-197 ) | | | | | | | | | | | | | |
| 8/6/15 | 53 / 54 | 153 | 15:35 PM | MODESTO L. | 2025 | 600 | 860 | | 8/6/15 | Air Pressure | 16 04 / 30 | 16 09 / 29 | 1 | PASS |
| Seam Notes | 15'S (RP-197 ) TO SEOS | | | | | | | | | | | | | |
| 8/7/15 | 55 / 56 | 22.5 | 13:30 PM | MODESTO L. | 2025 | 400 | 860 | | 8/7/15 | Air Pressure | 15 04 / 30 | 15 09 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/7/15 | 54 / 55 | 157 | 13:34 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 41 / 30 | 14 46 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 54 / 56 | 11 | 13:50 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 41 / 30 | 14 46 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 55 / 57 | 101 | 14:00 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 31 / 30 | 14 36 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 101'N (RP-220) | | | | | | | | | | | | | |
| 8/7/15 | 55 / 57 | 19 | 14:16 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 31 / 30 | 14 36 / 30 | 0 | PASS |
| Seam Notes | 101'N (RP-220) TO 120'N (RP-221 ) | | | | | | | | | | | | | |
| 8/7/15 | 55 / 57 | 37 | 14:19 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 48 / 30 | 14 53 / 30 | 0 | PASS |
| Seam Notes | 120'N (RP-221 ) TO NEOS | | | | | | | | | | | | | |
| 8/7/15 | 56 / 57 | 11 | 14:24 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 14 48 / 30 | 14 53 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 59 / 60 | 22.5 | 14:26 PM | MODESTO L. | 2025 | 400 | 860 | | 8/7/15 | Air Pressure | 15 11 / 30 | 15 16 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 57 / 58 | 167 | 14:28 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 15 02 / 30 | 15 07 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/7/15 | 58 / 59 | 150 | 14:57 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 15 30 / 30 | 15 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/7/15 | 58 / 60 | 15 | 15:25 PM | MODESTO L. | 2025 | 600 | 860 | | 8/7/15 | Air Pressure | 16 01 / 30 | 16 06 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 59 / 61 | 150 | 11:06 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 11 55 / 30 | 12 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 60 / 61 | 15 | 11:24 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 61 / 62 | 164 | 11:27 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 11 56 / 30 | 12 01 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 62 / 63 | 163 | 11:38 AM | MODESTO L. | 2025 | 600 | 860 | | 8/10/15 | Air Pressure | 11 59 / 30 | 12 04 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 63 / 64 | 163 | 15:50 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 39 / 30 | 8 44 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/10/15 | 64 / 66 | 8 | 16:20 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 46 / 30 | 8 51 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | SEOS TO 8'N ( RP-252 ) | | | | | | |
| 8/10/15 | 64 / 66 | 13 | 16:21 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 48 / 30 | 8 52 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | 8'N (RP-252 ) TO NEOS | | | | | | |
| 8/10/15 | 64 / 65 | 141 | 16:25 PM | MODESTO L. | 2025 | 600 | 860 | | 8/12/15 | Air Pressure | 8 38 / 30 | 8 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/12/15 | 64 / 66 | 24 | 8:30 AM | PEDRO S. | EXT 512 | | 530 | 530 | 8/12/15 | Vacuum | | | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 65 / 67 | 162 | 8:45 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 53<br>30 | 10 58<br>29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 67 / 68 | 162 | 9:10 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 30<br>30 | 10 35<br>28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 68 / 69 | 100 | 9:25 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 11 03<br>30 | 11 08<br>30 | 0 | PASS |
| Seam Notes | DS-19 WAS COLLECTED BEFORE NON-DESTRUCTIVE TESTING WAS COMPLETED | | | | | | | | SEOS TO 100'N (RP-254/DS-19 ) | | | | | |
| 8/13/15 | 68 / 69 | 62 | 9:32 AM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 11 00<br>30 | 11 05<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | 100'N (RP-254/DS-19 ) TO NEOS | | | | | |
| 8/13/15 | 69 / 70 | 162 | 9:39 PM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 32<br>30 | 10 37<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/13/15 | 70 / 71 | 162 | 10:05 PM | MODESTO L. | 2025 | 600 | 860 | | 8/13/15 | Air Pressure | 10 33<br>30 | 10 38<br>29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/14/15 | 71 / 72 | 57 | 9:45 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11 14<br>30 | 11 19<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | SEOS TO 57'N (RP-258 ) | | | | | |
| 8/14/15 | 71 / 72 | 76 | 9:51 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11 25<br>30 | 11 30<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | 57'N (RP-258 ) TO 133'N (RP-259 ) | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8/14/15 | 71 / 72 | 29 | 10:03 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11:34 / 30 | 11:39 / 30 | 0 | PASS |
| Seam Notes | 133'N (RP-259 ) TO NEOS | | | | | | | | | | | | | |
| 8/14/15 | 72 / 73 | 163 | 10:14 AM | MODESTO L. | 2025 | 450 | 860 | | 8/14/15 | Air Pressure | 11:15 / 30 | 11:20 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/14/15 | 73 / 74 | 164 | 10:35 AM | MODESTO L. | 2025 | 450 | 860 | | 8/14/15 | Air Pressure | 11:16 / 30 | 11:21 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 8/14/15 | 74 / 75 | 60 | 10:54 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11:30 / 30 | 11:35 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 60'N (RP-260 ) | | | | | | | | | | | | | |
| 8/14/15 | 74 / 75 | 104 | 11:03 AM | MODESTO L. | 2025 | 600 | 860 | | 8/14/15 | Air Pressure | 11:30 / 30 | 11:35 / 30 | 0 | PASS |
| Seam Notes | 60'N (RP-260 ) TO NEOS | | | | | | | | | | | | | |
| 9/9/15 | 76 / 77 | 86 | 15:51 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 30 / 30 | 8 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 77 / 78 | 86 | 16:05 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 31 / 30 | 8 36 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 78 / 79 | 86 | 16:19 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 49 / 30 | 8 54 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 79 / 80 | 83 | 16:59 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 8 32 / 30 | 8 37 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported By** Lyssa Tran **Cap** x

**Other** Cap construction

**Air Pressure Test** 30 PSI

**Air Pressure Hold Time** 5 Minutes

**Allowable Air Pressure Loss** 4 PSI

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/9/15 | 80 / 81 | 85 | 17:20 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 02 / 30 | 9 07 / 27 | 3 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 85 / 86 | 11 | 17:34 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 9 51 / 30 | 9 56 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 84 / 86 | 13 | 17:37 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 51 / 30 | 9 56 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 84 / 85 | 17 | 17:40 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 54 / 30 | 9 59 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 83 / 84 | 23 | 17:46 PM | PEDRO S. | 2025 | 350 | 860 | | 9/14/15 | Air Pressure | 9 30 / 30 | 9 35 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 83 / 85 | 3 | 17:48 PM | PEDRO S. | 2025 | 350 | 860 | | 9/16/15 | Vacuum | | | 0 | PASS |
| Seam Notes | | | | | | | | | | COVER BY SJ RP-302 | | | | |
| 9/9/15 | 82 / 83 | 26 | 17:50 PM | PEDRO S. | 2025 | 350 | 860 | | 9/14/15 | Air Pressure | 9 31 / 30 | 9 36 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 81 / 82 | 22.5 | 17:57 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 9 02 / 30 | 9 07 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 81 / 83 | 22.5 | 18:03 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 9 30 / 30 | 9 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/9/15 | 81 / 84 | 24 | 18:06 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 51 / 30 | 9 56 / 30 | 0 | PASS |
| Seam Notes | WEOS TO 24'E ( RP- 315 ) | | | | | | | | | | | | | |
| 9/9/15 | 81 / 84 | 12 | 18:08 PM | PEDRO S. | 2025 | 400 | 860 | | 9/16/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 24'E ( RP-315 ) TO EEOS | | | | | | | | | | | | | |
| 9/9/15 | 75 / 82 | 30 | 18:10 PM | PEDRO S. | 2025 | 400 | 860 | | 9/14/15 | Air Pressure | 9 31 / 30 | 9 36 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 81 | 23 | 14:17 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 35 / 30 | 7 40 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/9/15 | 75 / 80 | 22.5 | 14:21 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 36 / 30 | 7 41 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 79 | 23 | 14:24 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 36 / 30 | 7 41 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 78 | 22.5 | 14:28 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 7 37 / 30 | 7 42 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 77 | 22.5 | 14:33 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 8 01 / 30 | 8 06 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/11/15 | 75 / 76 | 22.5 | 14:37 PM | PEDRO S. | 2025 | 300 | 860 | | 9/14/15 | Air Pressure | 8 01 / 30 | 8 06 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/15/15 | 87 / 88 | 167 | 10:34 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 11 45 / 30 | 11 50 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 88 / 89 | 168 | 10:55 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 11 43 / 30 | 11 48 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 89 / 90 | 81 | 11:17 AM | PEDRO | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 11 45 / 30 | 11 50 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 81'N (RP-328 ) | | | | | | | | | | | | | |
| 9/15/15 | 89 / 90 | 64 | 11:30 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 13 00 / 30 | 13 05 / 30 | 0 | PASS |
| Seam Notes | 81'N (RP-328 ) TO 145'N (RP-326 ) | | | | | | | | | | | | | |
| 9/15/15 | 89 / 90 | 23 | 11:39 AM | PEDRO S. | 2025 | 400 | 860 | | 9/15/15 | Air Pressure | 13 02 / 30 | 13 07 / 30 | 0 | PASS |
| Seam Notes | 145'N (RP-326 ) TO NEOS | | | | | | | | | | | | | |
| 9/15/15 | 81 / 87 | 8 | 11:43 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 30 / 30 | 14 35 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 8'N (RP-319 ) | | | | | | | | | | | | | |
| 9/15/15 | 81 / 87 | 14.5 | 11:44 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 25 / 30 | 14 30 / 30 | 0 | PASS |
| Seam Notes | 8'N (RP-319 ) TO NEOS | | | | | | | | | | | | | |
| 9/15/15 | 80 / 87 | 22.5 | 11:46 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 79 / 87 | 6 | 11:50 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 14 00 / 30 | 14 05 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 6'N (RP-322) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/15/15 | 79 / 87 | 12.5 | 11:51 AM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 40 / 30 | 13 45 / 28 | 2 | PASS |
| Seam Notes | 6'N (RP-322) TO NEOS | | | | | | | | | | | | | |
| 9/15/15 | 78 / 87 | 22.5 | 13:05 PM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 23 / 30 | 13 28 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 77 / 87 | 22.5 | 13:07 PM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 22 / 30 | 13 27 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/15/15 | 76 / 87 | 23 | 13:10 PM | PEDRO S. | 2025 | 350 | 860 | | 9/15/15 | Air Pressure | 13 22 / 30 | 13 27 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/16/15 | 90 / 91 | 168 | 13:36 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 35 / 30 | 14 40 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/16/15 | 91 / 92 | 152 | 13:55 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 40 / 30 | 14 45 / 28 | 2 | PASS |
| Seam Notes | SEOS TO 151'N (RP-351 ) | | | | | | | | | | | | | |
| 9/16/15 | 91 / 92 | 15 | 14:10 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 44 / 30 | 14 49 / 29 | 1 | PASS |
| Seam Notes | 151'N ( RP-351 ) TO NEOS | | | | | | | | | | | | | |
| 9/16/15 | 92 / 93 | 167 | 14:16 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 40 / 30 | 14 45 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/16/15 | 93 / 94 | 144 | 14:34 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 50 / 30 | 14 55 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 144'N (RP-354 ) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/16/15 | 93 / 94 | 23 | 14:48 PM | PEDRO S. | 2025 | 450 | 860 | | 9/16/15 | Air Pressure | 14 51 / 30 | 15 56 / 30 | 0 | PASS |
| Seam Notes | 144'N (RP-354 ) TO NEOS | | | | | | | | | | | | | |
| 9/17/15 | 94 / 95 | 33 | 14:31 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 28 / 30 | 15 33 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 33'N (RP-370 ) | | | | | | | | | | | | | |
| 9/17/15 | 94 / 95 | 92 | 14:35 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 15 / 30 | 15 20 / 30 | 0 | PASS |
| Seam Notes | 33'N(RP-370) TO 125'N (RP-368 ) | | | | | | | | | | | | | |
| 9/17/15 | 94 / 95 | 41 | 14:44 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 15 / 30 | 15 20 / 30 | 0 | PASS |
| Seam Notes | 125'N (RP-368 ) TO NEOS | | | | | | | | | | | | | |
| 9/17/15 | 95 / 96 | 128 | 14:51 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 25 / 30 | 15 30 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 128'S (RP-373) | | | | | | | | | | | | | |
| 9/17/15 | 95 / 96 | 38 | 15:06 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 26 / 30 | 15 31 / 30 | 0 | PASS |
| Seam Notes | 128'S (RP- 373 ) TO SEOS | | | | | | | | | | | | | |
| 9/17/15 | 96 / 97 | 101 | 15:13 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 30 / 30 | 15 35 / 28 | 2 | PASS |
| Seam Notes | NEOS TO 101'S (RP- 377 ) | | | | | | | | | | | | | |
| 9/17/15 | 96 / 97 | 16 | 13:48 PM | EMMANUEL V. | EXT 512 | | 550 | 550 | 9/21/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 101'S (RP-377 ) TO 117'S (RP- 376 ) | | | | | | | | | | | | | |
| 9/17/15 | 96 / 97 | 49 | 15:21 PM | PEDRO S. | 2025 | 450 | 860 | | 9/17/15 | Air Pressure | 15 36 / 30 | 15 41 / 29 | 1 | PASS |
| Seam Notes | 117'S (RP-376 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/18/15 | 98 / 99 | 70 | 11:26 AM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 14 / 30 | 14 19 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 99 / 100 | 70 | 11:41 AM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 08 / 30 | 14 13 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 100 / 101 | 71 | 11:53 AM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 07 / 30 | 14 12 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 101 / 102 | 70 | 13:07 PM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 06 / 30 | 14 11 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 102 / 103 | 70 | 13:22 PM | PEDRO S. | 2025 | 450 | 860 | | 9/18/15 | Air Pressure | 14 05 / 30 | 14 10 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 104 / 105 | 32 | 13:41 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 15 04 / 30 | 15 09 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 105 / 106 | 27 | 13:51 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 15 12 / 30 | 15 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 103 / 106 | 22.5 | 14:00 PM | PEDRO S. | 2025 | 300 | 860 | | 9/18/15 | Air Pressure | 15 12 / 30 | 15 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 103 / 105 | 23 | 14:06 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 15 04 / 30 | 15 09 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 **PSI**

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 **Minutes**

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 **PSI**

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/18/15 | 103 / 104 | 16 | 14:10 PM | PEDRO S. | 2025 | 300 | 860 | | 9/18/15 | Air Pressure | 15 04<br>30 | 15 09<br>30 | 0 | PASS |
| Seam Notes | EEOS TO 16'W ( RP-383 ) | | | | | | | | | | | | | |
| 9/18/15 | 103 / 104 | 10 | 14:13 PM | PEDRO S. | 2025 | 300 | 860 | | 9/18/15 | Air Pressure | 14 55<br>30 | 15 00<br>30 | 0 | PASS |
| Seam Notes | 16'W (RP-383 ) TO WEOS | | | | | | | | | | | | | |
| 9/18/15 | 97 / 98 | 22.5 | 14:20 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 38<br>30 | 14 43<br>28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 99 | 22.5 | 14:22 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 38<br>30 | 14 43<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 100 | 22.5 | 14:25 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 40<br>30 | 14 45<br>28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 101 | 22.5 | 14:28 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 40<br>30 | 14 45<br>29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 102 | 22.5 | 14:30 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 46<br>30 | 14 511<br>29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/18/15 | 97 / 103 | 12 | 14:33 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 48<br>30 | 14 53<br>30 | 0 | PASS |
| Seam Notes | NEOS TO 12'S (RP-384) | | | | | | | | | | | | | |
| 9/18/15 | 97 / 103 | 10.5 | 14:35 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 55<br>30 | 15 00<br>30 | 0 | PASS |
| Seam Notes | 12'S (RP-384 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/18/15 | 97 / 104 | 32 | 14:37 PM | PEDRO S. | 2025 | 350 | 860 | | 9/18/15 | Air Pressure | 14 55 / 30 | 15 00 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 106 / 107 | 36 | 10:41 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 11 37 / 30 | 11 42 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 103 / 107 | 14 | 10:45 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 38 / 30 | 11 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 102 / 107 | 23 | 10:47 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 38 / 30 | 11 43 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 101 / 107 | 22.5 | 10:50 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 39 / 30 | 11 44 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 100 / 107 | 22.5 | 10:53 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 40 / 30 | 11 45 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 99 / 107 | 23 | 10:56 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 49 / 30 | 11 54 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 98 / 107 | 23 | 11:00 AM | PEDRO S. | 2025 | 350 | 860 | | 9/22/15 | Air Pressure | 11 48 / 30 | 11 53 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 107 / 108 | 163 | 11:06 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 13 13 / 30 | 13 18 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In / PSI IN | AT Time Out / PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/22/15 | 108 / 109 | 164 | 11:24 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 13 14 / 30 | 13 19 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/22/15 | 109 / 110 | 163 | 11:42 AM | PEDRO S. | 2025 | 450 | 860 | | 9/22/15 | Air Pressure | 13 15 / 30 | 13 20 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/23/15 | 110 / 111 | 162 | 15:38 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 50 / 30 | 16 55 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/23/15 | 111 / 112 | 15 | 15:52 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 48 / 30 | 16 53 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 15'S (RP-419 ) | | | | | | | | | | | | | |
| 9/23/15 | 111 / 112 | 147 | 15:54 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 48 / 30 | 16 53 / 29 | 1 | PASS |
| Seam Notes | 15'S (RP-419 ) TO SEOS | | | | | | | | | | | | | |
| 9/23/15 | 112 / 113 | 162 | 16:12 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 51 / 30 | 16 56 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/23/15 | 113 / 114 | 28 | 16:42 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 53 / 30 | 16 58 / 29 | 1 | PASS |
| Seam Notes | NEOS TO 28'S (RP-421 ) | | | | | | | | | | | | | |
| 9/23/15 | 113 / 114 | 138 | 16:46 PM | PEDRO S. | 2025 | 450 | 860 | | 9/23/15 | Air Pressure | 16 59 / 30 | 17 04 / 30 | 0 | PASS |
| Seam Notes | 28'S (RP-421 ) TO SEOS | | | | | | | | | | | | | |
| 9/24/15 | 114 / 115 | 162 | 14:51 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 46 / 30 | 15 51 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/24/15 | 115 / 116 | 28 | 15:14 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 47 / 30 | 15 52 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 28'S (RP-426 ) | | | | | | | | | | | | | |
| 9/24/15 | 115 / 116 | 135 | 15:17 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 48 / 30 | 15 53 / 30 | 0 | PASS |
| Seam Notes | 28'S (RP-426 ) TO SEOS | | | | | | | | | | | | | |
| 9/24/15 | 116 / 117 | 164 | 15:31 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 15 52 / 30 | 15 57 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/24/15 | 117 / 118 | 121 | 15:51 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 16 04 / 30 | 16 09 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 121'S (RP-427 ) | | | | | | | | | | | | | |
| 9/24/15 | 117 / 118 | 44 | 16:02 PM | PEDRO S. | 2025 | 450 | 860 | | 9/24/15 | Air Pressure | 16 13 / 30 | 16 18 / 30 | 0 | PASS |
| Seam Notes | 121'S (RP-427 ) TO SEOS | | | | | | | | | | | | | |
| 9/25/15 | 118 / 119 | 164 | 14:30 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 17 / 30 | 15 22 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 22 | 14:53 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 22 / 30 | 15 27 / 30 | 0 | PASS |
| Seam Notes | NEOS TO 22'S (RP-438 ) | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 72 | 14:55 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 21 / 30 | 15 26 / 28 | 2 | PASS |
| Seam Notes | 22'S (RP-438 ) TO 94'S (RP-437 ) | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 33 | 15:00 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 21 / 30 | 15 26 / 30 | 0 | PASS |
| Seam Notes | 94'S (RP-437 ) TO 127'S (RP-439 ) | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/25/15 | 119 / 120 | 12 | 15:58 PM | PEDRO S. | EXT 512 | | 550 | 550 | 9/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | 127'S ( RP-439 ) TO 139'S (RP-440 ) | | | | | | | | | | | | | |
| 9/25/15 | 119 / 120 | 26 | 15:03 PM | PEDRO S. | 2025 | 450 | 860 | | 9/25/15 | Air Pressure | 15 15<br>30 | 15 20<br>30 | 0 | PASS |
| Seam Notes | 139'S ( RP-440 ) TO SEOS | | | | | | | | | | | | | |
| 9/29/15 | 120 / 121 | 166 | 16:46 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 15 10<br>30 | 15 15<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 121 / 122 | 143 | 15:04 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 15 40<br>30 | 15 45<br>29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-445 / 122 | 17 | 15:30 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 52<br>30 | 15 57<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-446 / 122 | 5 | 15:34 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 51<br>30 | 15 56<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-445 / 121 | 17 | 15:38 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 52<br>30 | 15 57<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | RP-446 / 121 | 5 | 15:41 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 15 51<br>30 | 15 56<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 123 / 124 | 22.5 | 15:45 PM | PEDRO S. | 2025 | 300 | 860 | | 9/29/15 | Air Pressure | 16 12<br>30 | 16 17<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** [ ] **Pond** [ ] **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** [ ] **Cell** [ ] **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** [x] **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9/29/15 | 124 / 125 | 19 | 15:52 PM | PEDRO S. | 2025 | 350 | 860 | | 9/29/15 | Air Pressure | 16 12 / 30 | 16 17 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 123 / 125 | 18 | 15:55 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 12 / 30 | 16 17 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 18'N (RP-454 ) | | | | | | | | | | | | | |
| 9/29/15 | 123 / 125 | 129 | 16:21 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 35 / 30 | 16 40 / 30 | 0 | PASS |
| Seam Notes | 18'N (RP-454 ) TO NEOS | | | | | | | | | | | | | |
| 9/29/15 | 122 / 124 | 19 | 15:58 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 10 / 30 | 16 15 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 9/29/15 | 122 / 123 | 23 | 16:00 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 10 / 30 | 16 15 / 30 | 0 | PASS |
| Seam Notes | SEOS TO 23'N (RP-450 ) | | | | | | | | | | | | | |
| 9/29/15 | 122 / 123 | 126 | 16:03 PM | PEDRO S. | 2025 | 400 | 860 | | 9/29/15 | Air Pressure | 16 40 / 30 | 16 45 / 30 | 0 | PASS |
| Seam Notes | 23'N (RP-450 ) TO NEOS | | | | | | | | | | | | | |
| 9/29/15 | RP-445 / RP-446 | 2 | 15:28 PM | PEDRO S. | 2025 | 300 | 860 | | 9/29/15 | Vacuum | | | 0 | PASS |
| Seam Notes | COVER BY RP-447 | | | | | | | | | | | | | |
| 10/8/15 | 125 / 126 | 159 | 15:00 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 16 45 / 30 | 16 50 / 29 | 1 | PASS |
| Seam Notes | NEOS TO 159'S ( RP-477 ) | | | | | | | | | | | | | |
| 10/8/15 | 125 / 126 | 5 | 15:33 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 15 / 30 | 17 20 / 30 | | PASS |
| Seam Notes | 159'N (RP-477 ) TO SEOS | | | | | | | | | | | | | |

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10/8/15 | 126 / 127 | 163 | 15:38 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 16 45 / 30 | 16 50 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 128 / 129 | 22.5 | 16:05 PM | PEDRO S. | 2025 | 300 | 860 | | 10/8/15 | Air Pressure | 17 29 / 30 | 17 34 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 127 / 129 | 12 | 16:12 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 30 / 30 | 17 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 127 / 128 | 149 | 16:13 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 16 45 / 30 | 16 50 / 28 | 2 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 130 / 131 | 9 | 16:30 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 40 / 30 | 17 45 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 131 / 132 | 11 | 16:32 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 39 / 30 | 17 44 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 133 / 134 | 7 | 16:35 PM | PEDRO S. | 2025 | 300 | 860 | | 10/8/15 | Air Pressure | 17 47 / 30 | 17 52 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 129 / 132 | 12 | 16:43 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 30 / 30 | 17 35 / 30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 128 / 132 | 81 | 16:44 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 31 / 30 | 17 36 / 29 | 1 | PASS |
| Seam Notes | | | | | | | | | | | | | | |

SEOS TO 81'N (RP-476 )

# *Environmental Specialties International Inc.*
## Seam Control Form

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Air Pressure Test** 30 PSI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Air Pressure Hold Time** 5 Minutes

**Reported By** Lyssa Tran **Cap** x **Allowable Air Pressure Loss** 4 PSI

**Other** Cap construction

**17,515** **Total LF of Welding to Date Combined** **Extrusion LF Weld Total To Date** **96** **Fusion LF Weld Total To Date:** **17,419**

| Weld Date | Seam No. | Seam Length | Time Welded | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | Test Date | Test Type | AT Time In PSI IN | AT Time Out PSI OUT | PSI Loss | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10/8/15 | 128 / 132 | 25 | 16:53 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 31<br>30 | 17 36<br>30 | 0 | PASS |
| Seam Notes | 81'N (RP-476 ) TO NEOS | | | | | | | | | | | | | |
| 10/8/15 | 128 / 131 | 22.5 | 16:55 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 39<br>30 | 17 44<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 128 / 130 | 20 | 16:59 PM | PEDRO S. | 2025 | 350 | 860 | | 10/8/15 | Air Pressure | 17 40<br>30 | 17 45<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 132 / 134 | 38 | 17:06 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 48<br>30 | 17 52<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| 10/8/15 | 132 / 133 | 38 | 17:11 PM | PEDRO S. | 2025 | 450 | 860 | | 10/8/15 | Air Pressure | 17 45<br>30 | 17 50<br>30 | 0 | PASS |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |
| | / | | : | | | | | | | | | | 0 | |
| Seam Notes | | | | | | | | | | | | | | |

# Appendix L
# ESI Repair Report

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-1 | CF | 2/3 | | 98'N OF SEOS ( VALLEY DESIGN) | P | 2.5 | x | 63 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-2 | WR | 3/4 | | 94'N OF SEOS | P | 2 | x | 12 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-3 | SI | | 3 | 60'N OF 2/3 & 11'E | P | 2 | x | 2.5 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-4 | DS-1 | 3/4 | | 18'N OF SEOS | P | 2 | X | 28 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-5 | CF | | 3 | 140'N OF 2/3 & 6'E | P | 2 | x | 10 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-6 | PB | 1/2 | | 135'N OF SEOS (PB 8") | P | 5 | x | 5 | 52.5 | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-7 | PB | | 1 | 85'N OF 1/2 & 17'W (PB 4") | P | 3 | x | 4 | 36.58 | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-8 | SI | | 2 | 86'N OF 2/3 & 2'W | P | 1.5 | x | 2 | | 7/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/21/15 |
| RP-9 | RW | 4/5 | | SEOS | P | 1.5 | x | 3 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-10 | SJ | 5/6/7 | | SJ 5/6/7 | P | 1.5 | X | 2 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-11 | RW | 5/7 | | SEOS | P | 2 | x | 4 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-12 | DS-2 | 6/7 | | 10'E OF WEOS | P | 2 | x | 5.5 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-13 | FS | 7/8 | | E.S. & COVER OVER SJ 6/7/8 | P | 2 | x | 6 | | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-14 | PB | | 8 | 147'N OF 6/8 & 4'E ( PB 8") | P | 5 | x | 5 | 52.5 | 7/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/22/15 |
| RP-15 | BO | 9/10 | | 52'N OF SEOS | P | 2 | x | 3 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-16 | DS-3 | 11/12 | | 100'N OF SEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-17 | CF | 13/14 | | 46'S OF NEOS (VALLEY DESIGN) | P | 2 | x | 42 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-18 | DSX-1 | | 13 | ON RP-17 | P | 2 | X | 6 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-19 | DS-4 | 14/15 | | 16'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-20 | CF | 14/15 | 15 | 57'S OF NEOS | P | 2 | x | 20 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-21 | CF | 15/16 | | 37'S OF NEOS | P | 2 | x | 16 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-22 | BO | 16/17 | | 23'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | | 7/30/15 |
| RP-23 | DS-5 | 17/18 | | 75'S OF NEOS | P | 2 | x | 5 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-24 | PB | 16 | | 80'S OF 16/17 & 13'W (MH 48") | P | 10 | x | 10 | 174.7 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-25 | CF | 15/16 | | 78'S OF NEOS | P | 2 | x | 15 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/24/15 |
| RP-26 | CF | | 16 | 100'S OF 16/17 & 15'W | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-27 | BO | 16/17 | | 80'S OF NEOS (PATCH)& 7'W (EXT) | P | 2 | x | 2 | 84 | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-28 | BO | 16/17 | | 115'S OF NEOS | P | 2 | x | 10 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-29 | BO | 16/17 | | 130'S OF NEOS | P | 2 | x | 8 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-30 | SI | | 17 | 110'S OF 17/18 & 4'W | P | 2 | x | 2 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-31 | BO | 17/18 | | 101'S OF NEOS | P | 2 | x | 23 | | 7/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-32 | AO | | 15 | SEOP (TRIANGLE ) | B | | x | | 324 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-33 | CF | | 16 | 134'S OF 16/17 & 6'W | P | 2 | x | 13 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-34 | DSX-2 | RP-32/15 | 15 | 10'E OF RP-32 | P | 2 | x | 4.5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-35 | WR | | 17 | 94'S OF 16/17 & 3'W | P | 2 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-36 | WR | | 17 | 88'S OF 16/17 & 3'W | P | 1.5 | x | 4 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-37 | WR | | 17 | 88'S OF 16/17 & 15'W | P | 2 | x | 6 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-38 | WR | | 17 | 101'S OF 16/17 & 10'W | P | 2 | x | 8 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-39 | DS-6 | 20/21 | | 155'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-40 | BO | 20/21 | | 128'S OF NEOS | P | 2 | x | 7 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-41 | WR | | 18 | 75'S OF 18/19 & 11'W | P | 2 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-42 | CR | 17/18 | | 60'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-43 | WR | | 18 | 55'S OF 18/19 & 8'W | P | 2 | x | 7 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-44 | BO | 18/19 | | 55'S OF NEOS | P | 2 | x | 6 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-45 | WR | | 19 | 33'S OF 19/20 & 10'W | P | 2 | X | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-46 | WR | 19/20 | | 29'S OF NEOS | P | 2 | x | 4.5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-47 | WR | | 19 | 33'S OF 19/20 &15'W | P | 1.5 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-48 | WR | | 19 | 21'S OF 19/20 & 9'W | P | 2 | x | 2 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-49 | WR | | 19 | 14'S OF 19/20 & 11'W | P | 1.5 | x | 3 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-50 | WR | | 20 | 30'S OF 20/21 & 14'W | P | 1.5 | x | 2 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-51 | BO | 20/21 | | 30'S OF NEOS | P | 2 | x | 5 | | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-52 | WR | | 17 | BETWEEN RP-35 & RP-38 | B | | x | | 60 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-53 | WR | | 17 | BETWEEN RP-36 & RP-38 | B | | x | | 108 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-54 | WR | | 17 | BETWEEN RP-37 & RP-38 | B | | x | | 96 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-55 | CF | | 16 | BETWEEN RP-24 & RP-27 | B | | x | | 60 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-56 | CF | | 18 | BETWEEN RP-41 & RP-43 | B | | x | | 180 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-57 | CF | | 18 | BETWEEN RP-42 & RP-43 | B | | x | | 156 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/27/15 |
| RP-58 | CF | | 19 | BETWEEN RP-48 & RP-49 | B | | x | | 60 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-59 | CF | | 19 | BETWEEN RP-47 & RP-48 | B | | x | | 72 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-60 | CF | | 19 | BETWEEN RP-45,RP-46& RP-48 | B | | x | | 180 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-61 | CF | | 20 | BETWEEN RP-50 & RP-51 | B | | x | | 144 | 7/27/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-62 | WR | | 21 | 10'S OF 21/22 & 8'W | P | 2 | x | 14 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-63 | WR | | 21 | 6'S OF 21/22 & 13'W | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-64 | WR | | 21 | BETWEEN RP-63 & RP-65 | B | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-65 | WR | | 21 | 20'S OF 21/22 & 18'W | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-66 | WR | | 22 | 20'S OF 22/23 & 5'W | P | 1.5 | x | 12 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-67 | BO | 21/22 | | 84'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-68 | BO | 22/23 | | 76'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-69 | WR | | 22 | 130'S OF 21/22 & 6'E | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-70 | WR | | 22 | BETWEEN RP-69 & RP-71 | B | | x | | 60 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-71 | CR | 21/22 | | 137'S OF NEOS | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-72 | WR | | 21 | BETWEEN RP-71 & RP-73 | B | | x | | 24 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-73 | WR | | 21 | 130'S OF 21/22 & 4'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-74 | WR | | 21 | BETWEEN RP-73 & RP-75 | B | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-75 | WR | | 21 | 129'S OF 21/22 & 9'W | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-76 | BO | 22/23 | | 97'S OF NEOS | P | 1.5 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/28/15 |
| RP-77 | WR | | 23 | 118'S OF 22/23 & 7'E | P | 2 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-78 | WR | | 23 | BETWEEN RP-77 & RP-79 | B | | x | | 48 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-79 | WR | | 23 | 124'S OF 22/23 & 7'E | P | 2 | x | 11 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-80 | WR | | 23 | BETWEEN RP-79 & RP-81 | B | | x | | 84 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-81 | WR | | 23 | 134'S 22/23 & 9'E | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-82 | DS-7 | 23/24 | | 87'S OF NEOS | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-83 | DSX-3 | RP-82/23 | | ON RP-82/83( 87'S OF NEOS) | P | 2 | x | 5 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-84 | CR | 23/24 | | 116'S OF NEOS | P | 1.5 | x | 2 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-85 | CF | | 23 | 125'S OF 23/24 & 3'W | P | 2 | x | 3 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-86 | CF | | 23 | BETWEEN RP-85 & RP-87 | B | | x | | 168 | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-87 | CF | | 23 | 140'S OF 23/24 & 10'W | P | 2 | x | 4 | | 7/28/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-88 | BO | 24/25 | | 127'S OF NEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-89 | WR | | 24 | BETWEEN RP-88 & RP-90 | B | | x | | 60 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-90 | WR | | 24 | 127'S OF 24/25 & 5'W | P | 2 | x | 2.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-91 | CF | | 25 | 100'N OF 25/26 & 6'W | P | 2 | x | 6 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-92 | CF | | 25 | BETWEEN RP-91 & RP-93 | B | | X | | 120 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-93 | CF | | 25 | 121'N OF 25/26 & 12'W ( T-SHAPE) | P | 2 | x | 22 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-94 | CF | | 25 | BETWEEN RP-93 & RP-95 | B | | x | | 84 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-95 | CF | 25/26 | | 110'N TO 129'N OF SEOS | P | 2 | x | 19 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-96 | DS-8 | 26/27 | | 128'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-97 | BO | 26/27 | | 71'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-98 | CF | | 27 | BETWEEN RP-97 & RP-100 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-99 | CR | 26/27 | | 38'N OF SEOS | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-100 | CF | | 27 | 55'N OF 26/27 & 13'E | P | 2 | x | 30 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-101 | CF | | 27 | BETWEEN RP-100 & RP-102 | B | | x | | 144 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-102 | CF | | 27 | 87'N OF 26/27 & 7'E | P | 2 | x | 6.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-103 | CF | 27/28 | | 117'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-104 | CF | | 28 | BETWEEN RP-103 & RP-105 | B | | x | | 156 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-105 | BO | 28/29 | | 120'N OF SEOS | P | 2 | x | 15 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-106 | CF | | 28 | BETWEEN RP-105 & RP-107 | B | | x | | 192 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-107 | CF | | 28 | 134'N OF 27/28 & 4'E | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-108 | BO | 29/30 | | 125'N OF SEOS | P | 2 | x | 10 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-109 | DS-9 | 29/30 | | 80'N OF SEOS | P | 2 | x | 5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-110 | CF | | 28 | 85'N OF 28/29 & 3'W | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-111 | CF | | 28 | BETWEEN RP-110 & RP-112 | B | | x | | 180 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-112 | WR | 28/29 | | 68'N OF SEOS | P | 2 | x | 8 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-113 | WR | | 28 | BETWEEN RP-112 & RP-114 | B | | x | | 36 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-114 | WS | 28/29 | | 73'N OF SEOS | P | 2 | x | 3 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-115 | BO | 28/29 | | 61'N OF SEOS | P | 1.5 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-116 | WR | | 28 | 29'N OF 27/28 & 1'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-117 | WR | | 28 | BETWEEN RP-116 & RP-118 | B | | x | | 72 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-118 | WR | | 28 | 29'N OF 27/28 &9'E | P | 2 | X | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-119 | WR | | 28 | BETWEEN RP-118 & RP-120 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-120 | WR | | 28 | 29'N OF 27/28 & 13'E | P | 1 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-121 | BO | 27/28 | | 34'N OF SEOS | P | 2 | x | 7 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-122 | CF | | 27 | BETWEEN RP-121 & RP-123 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-123 | CF | | 27 | 34'N OF 27/28 & 5'W | P | 1.5 | x | 1.5 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-124 | CF | | 28 | 34'N OF 27/28 & 10'E | P | 2 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-125 | CF | | 28 | BETWEEN RP-124 & RP-126 | B | | x | | 108 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-126 | CF | | 28 | 45'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-127 | CF | | 28 | BETWEEN RP-126 & RP-128 | B | | x | | 24 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-128 | CF | | 28 | 48'N OF 27/28 & 6'E | P | 1.5 | x | 2 | | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-129 | PB | | 11 | 80'N OF 10/11 & 8'E (PB 8") | P | 3 | x | 3 | 52.5 | 7/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/29/15 |
| RP-130 | DS-10 | 32/33 | | 20'N OF SEOS | P | 2 | x | 5.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-131 | DSX-4 | RP-102/27 | | ON EASTSIDE OF RP-102/27 | P | 2 | x | 5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-132 | PB | | 32 | 13'N OF 31/32 & 1'E (PB 4") | P | 3 | x | 4 | 36.6 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-133 | WR | 33/34 | | SEOS TO 21'N | P | 2.5 | x | 21 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-134 | WR | | 34 | BETWEEN RP-133 & RP-135(N.SIDE) | B | | x | | 84 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-135 | WR | | 34 | 18'N OF 33/34 & 11'E | P | 3 | x | 10 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-136 | WR | | 34 | FROM RP-135 TO SEOP | B | | x | | 180 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-137 | WR | | 34 | BETWEEN RP-133 & RP-135(S.SIDE) | B | | x | | 120 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-138 | WR | | 34 | BETWEEN RP-137 & RP-139 | B | | x | | 36 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-139 | WR | | 34 | 13'N OF 33/34 & 6'E | P | 1.5 | x | 1.5 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-140 | WR | | 34 | BETWEEN RP-135 & RP-141 | B | | x | | 168 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-141 | WR | | 34 | 36'N OF 33/34 & 10'E | P | 1 | x | 2 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-142 | CF | | 30 | 112'N OF 29/30 & 5'E | P | 2 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-143 | CF | | 30 | BETWEEN RP-142 & RP-144 | B | | x | | 48 | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-144 | CF | | 30 | 98'N OF 29/30 & 7'E | P | 1.5 | x | 14 | | 7/30/15 | EMMANUEL V. | EXT 512 | VBOX | P | 7/30/15 |
| RP-145 | DS-11 | 36/37 | | 90'W OF EEOS & SJ 34/36/37 | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-146 | SJ | 41/44/45 | | SJ 41/44/45 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-147 | SJ | 44/45/46 | | SJ 44/45/46 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-148 | SJ | 40/41/44 | | SJ 40/41/44 | P | 2 | x | 5.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-149 | SJ | 34/40/41 | | SJ 34/40/41 | P | 3 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-150 | SJ | 34/39/40 | | SJ 34/39/40 | P | 1.5 | x | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-151 | SJ | 34/38/39 | | SJ 34/38/39 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-152 | SJ | 34/37/38 | | SJ 34/37/38 | P | 2 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-153 | BO | 35/36 | | 84'W OF EEOS | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-154 | WR | | 36 | BETWEEN RP-153 & RP-155 | B | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-155 | WR | | 36 | 84'W OF 35/36 & 5'S | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-156 | SJ | 34/35/36 | | SJ 34/35/36 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-157 | BO | 34/35 | | 10'S OF NEOS | P | 1.5 | X | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-158 | WR | | 35 | 65'W OF 35/36 & 11'N | P | 1.5 | X | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-159 | WR | | 35 | FROM RP-158 TO N.END OF P-35 | P | | x | | 144 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-160 | DS-12 | 42/43 | | 20'N OF SEOS | P | 2 | x | 5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-161 | SJ | 43/44/46 | | SJ 43/44/46 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-162 | WR | 44/46 | | 5'W OF EEOS | P | 1.5 | X | 3 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-163 | WR | | 44 | BETWEEN RP-162 & RP-164 | B | | x | | 36 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-164 | WR | | 44 | 5'W OF 44/46 & 5'N | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-165 | WR | | 44 | BETWEEN RP-162 RP-166 | B | | x | | 216 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-166 | WR | 40/44 | | 16'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-167 | SJ | 40/42/43 | | SJ 40/42/43 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-168 | SJ | 39/40/42 | | SJ 39/40/42 | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-169 | SJ | 38/39/42 | | SJ 38/39/42 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-170 | SJ | 37/38/42 | | SJ 37/38/42 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-171 | SJ | 36/37/42 | | SJ 36/37/42 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-172 | WR | 36/42 | | 6'S OF NEOS | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-173 | WR | | 42 | BETWEEN RP-172 & RP-174 | B | | x | | 108 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-174 | WR | | 42 | 6'S OF 36/42 & 10'E | P | 3 | x | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-175 | CR | 35/42 | | 15'S OF NEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-176 | WR | | 42 | BETWEEN RP-174 & RP-175 | B | | x | | 132 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-177 | SJ | 35/36/42 | | SJ 35/36/42 | P | 2 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-178 | CR | 35/36 | | 15'W OF EEOS | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-179 | WR | | 35 | 30'W OF 35/36 & 10'N | P | 2 | x | 4 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-180 | WR | | 35 | FROM RP-179 TO N.END OF P-35 | B | | x | | 156 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-181 | CR | 44/45 | | 11'W OF EEOS | P | 1.5 | x | 2.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBIOX | P | 8/4/15 |
| RP-182 | WR | | 44 | BETWEEN RP-181 & RP-183 | B | | x | | 204 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-183 | CR | 40/44 | | 42'W OF EEOS | P | 1.5 | x | 1.5 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-184 | BO | 40/44 | | 48'W OF EEOS | P | 2 | x | 7 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-185 | SJ | 40/43/44 | | SJ 40/43/44 | P | 1.5 | x | 2 | | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-186 | DSX-5 | RP-160/42 | | ON RP-160/42 | P | 2 | x | 5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-187 | WR | | 42 | 7'N OF 39/42 &1'E TO 6'E | B | | x | | 78 | 8/4/15 | PEDRO S. | EXT 512 | VBOX | P | 8/4/15 |
| RP-188 | PB | | 25 | 74'S OF 24/25 & 5'E (PB 8") | P | 3 | x | 3 | 52.5 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-189 | WR | | 35 | 15'W OF 35/36 & 16'N | P | 2 | x | 7 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-190 | WR | | 35 | BETWEEN RP-189 & RP-191 | B | | x | | 84 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-191 | WR | | 35 | 15'W OF 35/36 & 6'N | P | 1.5 | x | 1.5 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-192 | WR | | 36 | 10'W OF 36/37 & 7'N | P | 1.5 | x | 2 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-193 | WR | | 36 | BETWEEN RP-192 & RP-194 | B | | x | | 180 | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-194 | WR | | 36 | 10'W OF 36/37 & 24'N | P | 2 | x | 4 | | 8/5/15 | PEDRO S. | EXT 512 | VBOX | P | 8/5/15 |
| RP-195 | BO | 47/48 | | 106'S OF NEOS | P | 2 | x | 6.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-196 | BO | 48/49 | | 86'S OF NEOS | P | 2 | x | 4 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-197 | BO | 53/54 | | 15'S OF NEOS | P | 2 | x | 7 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-198 | WR | 48/49 | | 94'S OF NEOS | P | 2 | x | 28 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-199 | CR | 42/47 | | 50'S OF NEOS | P | 2 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-200 | CF | | 47 | 56'S OF NEOS(SURFACE DESIGN) | P | 2 | x | 38 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-201 | CF | | 47 | 38'S OF 42/47 & 8'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-202 | CF | | 47 | BETWEEN RP-201 & RP-203 | B | | x | | 240 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-203 | CF | | 47 | 59'S OF 42/47 & 18'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-204 | DS-13 | 47/48 | | 70'S OF NEOS | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-205 | CF | | 47 | FROM RP-200 TO MANHOLE | B | | x | | 216 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-206 | WR | | 48 | 46'S OF 47/48 & 4'E | P | 1.5 | x | 1.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-207 | WR | | 48 | BETWEEN RP-206 & RP-208 | B | | x | | 180 | 8/7/15 | PEDRO S. | EXT 512 | VNOX | P | 8/7/15 |
| RP-208 | WR | | 48 | 64'S OF 48/49 & 6'W | P | 2 | x | 11 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-209 | WR | | 48 | BETWEEN RP-208 & RP-210 | B | | x | | 36 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-210 | WR | | 48 | 57'S OF 48/49 & 4'W | P | 2.5 | x | 2.5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-211 | DSX-6 | RP-198/48 | | ON W.END OF RP-198/48 | P | 2 | x | 5 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-212 | WR | 49/50 | | 72'S OF NEOS | P | 2 | x | 9 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-213 | WR | | 50 | 75'S OF 49/50 & 8'E | P | 2 | x | 7 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-214 | WR | | 50 | BETWEEN RP-213 & RP-215 | B | | x | | 24 | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-215 | WR | | 50 | 78'S OF 49/50 & 2'E | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | F | 8/10/15 |
| RP-216 | SJ | 50/51/52 | | SJ 50/51/52 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-217 | SJ | 51/52/53 | | SJ 51/52/53 | P | 2 | x | 2 | | 8/7/15 | PEDRO S. | EXT 512 | VBOX | P | 8/7/15 |
| RP-218 | PB | | 47 | 87'S OF 42/47 & 11'E(MH 48" ) | P | 9.5 | x | 9.5 | 175 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-219 | PB | | 38 | 3'W OF 37/38 & 3'S (PB 8") | P | 3.5 | x | 4 | 52.5 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-220 | BO | 55/57 | | 101'N OF SEOS | P | 2 | x | 2.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-221 | BO | 55/57 | | 120'N OF SEOS | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-222 | WR | | 50 | REPAIR LEAK OVER RP-215 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-223 | DS-14 | 50/51 | | 35'S OF NEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-224 | WR | 51/53 | | 20'S OF NEOS | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-225 | WR | | 53 | BETWEEN RP-224 & RP-226 | B | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-226 | WR | | 53 | 20'S OF 51/53 & 14'E | P | 2 | x | 8 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-227 | WR | | 53 | 30'S OF 53/54 & 5'W | P | 1.5 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-228 | WR | | 53 | BETWEEN RP-227 & RP-229 | B | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-229 | WR | | 53 | 35'S OF 51/53 & 5'W | P | 2 | x | 11 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-230 | DS-15 | 54/55 | | 72'S OF NEOS | P | 2 | x | 4.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-231 | SJ | 54/55/56 | | SJ 54/55/56 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-232 | SJ | 55/56/57 | | SJ 55/56/57 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-233 | CF | | 55 | 76'N OF 55/57 & 3'W | P | 2 | X | 13 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-234 | CF | | 55 | BETWEEN RP-233 & RP-235 | B | | x | | 24 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-235 | CF | | 55 | 80'N OF 55/57 & 2'W | P | 2 | x | 3.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-236 | CF | | 58 | 128'S OF 57/58 7'E | P | 3 | x | 4 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-237 | CF | | 58 | BETWEEN RP-236 & RP-238 | B | | x | | 168 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-238 | CF | | 58 | 140'S OF 57/58 & 20'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-239 | CF | | 58 | BETWEEN RP-236 & RP-240 | B | | x | | 96 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-240 | CF | | 58 | 125'S OF 57/58 & 17'E | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-241 | CF | | 58 | BETWEEN RP-239 & RP-242 | B | | x | | 36 | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-242 | CF | | 58 | 128'S OF 57/58 & 15'E | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-243 | PB | | 58 | 75'S OF 57/58 & 6'E (PB 8") | p | 4 | x | 4 | 52.5 | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-244 | SJ | 58/59/60 | | SJ 58/59/60 | P | 1.5 | x | 1.5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-245 | DSX-7 | RP-197/53 | | ON RP-197/53 | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-246 | PB | | 62 | 135'N OF 61/62 & 2'E (PB 8") | P | 3 | x | 4 | 52.5 | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-247 | SJ | 59/60/61 | | SJ 59/60/61 | P | 2 | x | 2 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-248 | DS-16 | 59/61 | | 6'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-249 | DS-17 | 62/63 | | 90'N OF SEOS | P | 2 | x | 5 | | 8/10/15 | PEDRO S. | EXT 512 | VBOX | P | 8/10/15 |
| RP-250 | CR | | 65 | 2'N OF 65/66 & 5'E | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-251 | SJ | 64/65/66 | | SJ 64/65/66 | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |
| RP-252 | BO | 65/66 | | 8'N OF SEOS | P | 2 | x | 2 | | 8/12/15 | PEDRO S. | EXT 512 | VBOX | P | 8/12/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-253 | DS-18 | 64/65 | | 128'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-254 | DS-19 | 68/69 | | 100'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-255 | PB | | 71 | 9'N OF 71/72 & 5'W (PB 4") | P | 5 | x | 6 | 36.6 | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-256 | DS-20 | 72/73 | | 10'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-257 | PB | | 74 | 92'N OF 73/74 & 1'E (PB 8") | P | 3.5 | x | 4 | 52.5 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/14/15 |
| RP-258 | BO | 71/72 | | 57'N OF SEOS | P | 2 | x | 2 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-259 | BO | 71/72 | | 133'N OF SEOS | P | 2 | x | 2.5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-260 | BO | 74/75 | | 60'N OF SEOS | P | 2 | x | 6 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-261 | DS-21 | 74/75 | | 75'N OF SEOS | P | 2 | x | 5 | | 8/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 8/14/15 |
| RP-262 | PB | 78/79 | | WEOS (MH 48") | P | 10 | x | 11 | 175 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-263 | CF | | 73 | FROM RP-264 TO 4'N | B | | x | | 48 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-264 | CF | | 73 | 23'N OF 72/73 & 5'E | P | 2.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-265 | CF | | 73 | BETWEEN RP-264 & RP-266 | B | | x | | 84 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-266 | CF | | 73 | 14'N OF 72/73 & 7'E | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-267 | CF | | 73 | BETWEEN RP-266 & RP-272 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-268 | CF | | 73 | FROM RP-269 TO 3'W | B | | x | | 36 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-269 | CF | | 73 | 14'N OF 72/73 &18'E | P | 2 | x | 9 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-270 | CF | | 73 | BETWEEN RP-269 & RP-271 | B | | x | | 108 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-271 | CF | | 73 | 4'N OF 72/73 & 9'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-272 | CF | | 73 | 15'N OF 72/73 & 15'E | P | 2 | x | 10 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-273 | CF | | 73 | BETWEEN RP-272 & RP-274 | B | | x | | 36 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-274 | CF | | 73 | 23'N OF 72/73 & 15'E | P | 2 | x | 6 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-275 | CF | | 73 | FROM RP-274 TO 5'N | B | | x | | 60 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-276 | CF | | 73 | FROM RP-277 TO 12'E | B | | x | | 144 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-277 | CF | | 73 | 50'N OF 72/73 & 5'E | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-278 | CF | | 73 | 46'N OF 73/74 & 5'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-279 | CF | | 73 | BETWEEN RP-278 & RP-280 | B | | x | | 156 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-280 | CF | | 73 | 59'N OF 73/74 & 16'W | P | 1.5 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-281 | CF | | 71 | 137'N OF 71/72 & 2'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-282 | CF | | 71 | BETWEEN RP-281 & RP-283 | B | | x | | 120 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-283 | CF | | 71 | 125'N OF 71/72 & 8'W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-284 | CF | | 71 | 164'N OF 71/72 & 8'W | P | 2 | x | 4 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-285 | CF | | 71 | BETWEEN RP-284 & RP-286 | B | | x | | 132 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-286 | CF | | 71 | 142'N OF 71/72 & 3'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-287 | CF | | 71 | FROM RP-288 TO 8'N | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-288 | CF | | 71 | 137'N OF 71/72 & 9.5' W | P | 1.5 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-289 | DSX-8 | RP-284/71 | | ON RP-284/71 | P | 2 | x | 5 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-290 | WR | 68/69 | | 132'N OF SEOS | P | 2 | x | 2 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-291 | WR | | 68 | BETWEEN RP-290 & RP-292 | B | | x | | 96 | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-292 | WR | | 68 | 126'N OF 68/69 & 10'W | P | 2 | x | 3 | | 9/9/15 | PEDRO S. | EXT 512 | VBOX | P | 9/11/15 |
| RP-293 | SI | | 57 | 136'N OF 56/57 & 7'E | P | 2 | x | 2 | | 9/11/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/11/15 |
| RP-294 | SJ | | | SJ 75/80/81 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-295 | SJ | | | SJ 75/79/80 | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-296 | SJ | | | SJ 75/77/78 | P | 2 | x | 3 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-297 | SJ | | | SJ 75/76/77 | P | 1 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-298 | DS-22 | 79/80 | | 78'E OF WEOS | P | 2 | x | 4 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-299 | SJ | | | SJ 75/81/82 | P | 2.5 | x | 14 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-300 | SJ | | | SJ 81/82/83 | P | 1.5 | x | 1.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-301 | SJ | | | SJ 81/83/84 | P | 1 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-302 | SJ | | | SJ 83/84/85 | P | 2 | x | 4 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-303 | SJ | | | SJ 84/85/86 | P | 1 | x | 1 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-304 | WR | 84/85 | | 7'W OF EEOS | P | 1.5 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-305 | WR | | 84 | BETWEEN RP-304 & RP-306 | B | | x | | 204 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-306 | WR | | 84 | 7'W OF 84/85 & 17'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-307 | WR | | 84 | FROM RP-308 TO 12'SW | B | | x | | 144 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-308 | WR | | 84 | 20'E OF 81/84 & 13'S | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-309 | WR | 75/82 | | 14'N OF SEOS | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-310 | WR | | 82 | BETWEEN RP-309 & RP-311 | B | | x | | 240 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-311 | WR | 82/83 | | 15'N OF SEOS | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-312 | WR | | 82 | 6'N OF 82/83 & 6.5' W | P | 1.5 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-313 | WR | | 82 | BETWEEN RP-312 & RP-314 | B | | x | | 132 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-314 | WR | | 82 | 19'N OF 82/83 & 6'W | P | 1.5 | x | 1.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-315 | BO | 81/84 | | 24'E OF WEOS | | | x | | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-316 | DS-23 | 88/89 | | 116'N OF SEOS | p | 2 | x | 4.5 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-317 | WR | | 79 | BETWEEN RP-298 & RP-318 | B | | x | | 66 | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-318 | WR | | 79 | 78'E OF 79/80 & 7'N | P | 2 | x | 2 | | 9/14/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-319 | BO | 81/87 | | 8'N OF SEOS | P | 2 | x | 5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-320 | SJ | | | SJ 80/81/87 | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-321 | SJ | | | SJ 79/80/87 | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-322 | WR | 79/87 | | 6'N OF SEOS | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-323 | SJ | | | SJ 78/79/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-324 | SJ | | | SJ 77/78/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-325 | SJ | | | SJ 76/77/87 | P | 1.5 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-326 | CF | 89/90 | | 145'N OF SEOS | P | 2 | x | 2 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-327 | CF | | 89 | 145'N OF 89/90 & 6'W | B | | x | | 72 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-328 | CF | 89/90 | | 81'N OF NEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-329 | CF | | 89 | 81'N OF 89/90 & 5'W | B | | x | | 60 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-330 | DSX-9 | RP-316/88 | | RP-316/88 | P | 2 | x | 4.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-331 | SI | | 83 | 9'S OF 83/84 & 8'W (END OF PANEL) | P | 2 | x | 18 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-332 | SJ | | | SJ 84/86/87 | P | 3 | x | 12 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-333 | CR | | 84/86 | EEOS | P | 2 | x | 2.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-334 | WR | | 84 | BETWEEN RP-315 & RP-335 | B | | x | | 12 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-335 | WR | | 84 | 7'W OF 81/84 & 3.5'S | P | 3 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-336 | SJ | | | SJ 81/84/87 | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-337 | CF | 84/87 | | BETWEEN RP-332 & RP-336 | B | | x | | 216 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-338 | WR | 81/84 | | 24'E TO EEOS | B | | x | | 36 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-339 | WR | | 81 | 11'N OF 81/87 & 4'W | P | 1.5 | x | 1.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-340 | WR | | 81 | BETWEEN RP-339 & RP-341 | B | | x | | 138 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-341 | WR | | 81 | 13'W OF 81/84 & 3'N | P | 2 | x | 3.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-342 | AO | | 76 | ADD ON NORTH SIDE OF P-76 | P | 8 | x | 16 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-343 | CF | 76/77 | | 66'E OF WEOS | P | 2 | x | 3 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-344 | CF | | 77 | BETWEEN RP-343 & RP-345 | B | | x | | 36 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-345 | CF | | 77 | 66'E OF 76/77 & 5'S | P | 2 | x | 6 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-346 | CF | | 77 | BETWEEN RP-345 & RP-347 | B | | x | | 48 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-347 | CF | | 77 | 66'E OF 76/77 & 10'S | P | 1.5 | x | 1.5 | | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-348 | WR | | 85 | 4'W OF 84/85 & 4'S | B | | x | | 48 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-349 | WR | | 84 | 4'W OF 84/85 & 8'N | B | | x | | 96 | 9/16/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/16/15 |
| RP-350 | DS-24 | 91/92 | | 45'N OF SEOS | P | 2 | x | 5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-351 | CF | 91/92 | | 151'N OF SEOS | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-352 | CF | | 91 | BETWEEN RP-351 & RP-353 | B | | x | | 216 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-353 | CF | | 91 | 151'N OF 91/92 & 19.5'W | P | 3 | x | 3 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-354 | CF | 93/94 | | 144'N OF SEOS | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-355 | CF | | 94 | BETWEEN RP-354 & RP-356 | B | | x | | 72 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-356 | CF | | 94 | 144'N OF 93/94 & 10'E | P | 2 | x | 4.5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-357 | CF | | 90 | 29'N OF 90/91 & 4'W | P | 2 | x | 3 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-358 | CF | | 90 | BETWEEN RP-357 & RP-359 | B | | x | | 60 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-359 | CF | | 90 | 31'N OF 90/91 & 9'W | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-360 | CF | | 90 | BETWEEN RP-359 & RP-361 | B | | x | | 24 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-361 | CF | | 90 | 31'N OF 90/91 & 13'W | P | 2 | x | 2.5 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-362 | WR | | 80 | 11'S OF 80/87 & 5'W | P | 1 | x | 2 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-363 | WR | | 80 | BETWEEN RP-362 & RP-365 | B | | x | | 54 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-364 | WR | 79/80 | | 8.5'W OF EEOS | P | 2 | x | 2 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-365 | WR | | 8O | 5'S OF 80/87 & 10'W | P | 2 | x | 4 | | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-366 | WR | | 80 | BETWEEN RP-364 & RP-365 | B | | x | | 60 | 9/17/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/17/15 |
| RP-367 | DS-25 | 94/95 | | 100'N OF SEOS | P | 2 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-368 | CF | 94/95 | | 125'N OF SEOS | P | 2 | x | 6 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-369 | PB | | 95 | 95'N OF 94/95 & 6'E (PB 8") | P | 4 | x | 4.5 | 52.5 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-370 | CF | 94/95 | | 33'N OF SEOS | P | 2.5 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-371 | CF | | 95 | BETWEEN RP-370 & RP-372 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-372 | CF | | 95 | 33'N OF 94/95 & 6.5'E | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-373 | BO | 95/96 | | 128'S OF NEOS | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-374 | DS-26 | 96/97 | | 33'S OF NEOS | P | 2 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-375 | CF | 96/97 | | 95'S OF NEOS | P | 2 | x | 8 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-376 | CF | 96/97 | | FROM RP-377 TO 117'S | P | 2 | x | 14 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-377 | CF | | 96 | 101'S OF 96/97 TO 15'W | P | 4 | x | 15 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-378 | CF | | 96 | 105'S OF OF 96/97 & 13'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-379 | CF | | 96 | 101'S OF 96/97 & 17'W | P | 3 | x | 4.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-380 | CF | | 96 | 93'S OF 96/97 & 8'W | P | 2.5 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-381 | CF | | 96 | BETWEEN RP-380 & RP-382 | B | | x | | 48 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-382 | CF | | 96 | 86.5'S OF 96/97 & 4'W | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-383 | BO | 103/104 | | 16'W OF EEOS | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-384 | BO | 97/103 | | 12'S OF NEOS | | | x | | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-385 | SI | | 94 | 126'N OF 94/95 & 8'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-386 | DSX-10 | RP-376/96 | | RP-376/96 (DSX-10 ) | P | 2 | x | 5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/21/15 |
| RP-387 | SJ | | | SJ 97/103/104 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-388 | CF | | 97 | BETWEEN RP-384 & RP-389 | B | | x | | 24 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-389 | CF | | 97 | 12'S OF 97/103 & 3.5'W | P | 1 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-390 | SJ | | | SJ 97/102/103 | P | 2 | x | 2.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-391 | SJ | | | SJ 97/101/102 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-392 | SJ | | | SJ 97/100/101 | P | 1 | x | 1.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-393 | SJ | | | SJ 97/99/100 | P | 1.5 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-394 | SJ | | | SJ 97/98/99 | P | 2 | x | 2 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-395 | CF | | 103 | FROM RP-383 TO 5'N | B | | x | | 60 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-396 | CF | | 103 | 4'N FROM RP-397 & 14'NW | B | | x | | 168 | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-397 | SJ | | | SJ 103/104/105 | P | 2 | x | 3.5 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-398 | SJ | | | SJ 103/105/106 | P | 3 | x | 4 | | 9/21/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-399 | CF | | 107 | 122'S OF 107/108 & 4'W | B | | x | | 192 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-400 | SJ | | | SJ 103/106/107 | P | 2 | x | 2.5 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-401 | SJ | | | SJ 102/103/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-402 | SJ | | | SJ 101/102/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-403 | SJ | | | SJ 100/101/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-404 | SJ | | | SJ 99/100/107 | P | 2 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-405 | SJ | | | SJ 98/99/107 | P | 1.5 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-406 | CF | | 98 | FROM RP-412 TO N.E. CORNER | B | | x | | 144 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-407 | CF | | 98 | FROM RP-412 TO N.W. CORNER | B | | x | | 168 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-408 | CF | | 107 | 13'S OF 107/108 & 4.5'W | P | 1.5 | x | 3 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-409 | CF | | 107 | BETWEEN RP-408 & RP-411 | B | | x | | 168 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-410 | CF | | 107 | 6'S OF 107/108 & 5'W | B | | x | | 60 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-411 | CF | | 107 | 5'S OF 98/107 & 4'E | P | 1.5 | x | 2 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-412 | CF | | 98 | BETWEEN RP-406 & RP-407 | P | 2 | x | 22 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-413 | CF | | 108 | 143'S OF 108/109 & 3'E | P | 1.5 | x | 1.5 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-414 | CF | | 108 | FROM RP-413 TO 17'S | B | | x | | 204 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-415 | CF | | 107 | FROM RP-416 TO 4'W | B | | x | | 48 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-416 | CF | | 107 | 154'S OF 107/108 & 6'W | P | 2 | x | 4 | | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-417 | CF | | 107 | FROM RP-416 TO 4'E | B | | x | | 48 | 9/22/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/22/15 |
| RP-418 | PB | | 109 | 152'S OF 108/109 & 2.5'E (PB 4") | P | 4 | x | 6 | 36.6 | 9/23/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/23/15 |
| RP-419 | PB | 111/112 | | 15'S OF NEOS (PB 8") | P | 3.5 | x | 4.5 | 52.5 | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-420 | PB | | 113 | 82'S OF 112/113 & 14' ( MH 48" ) | P | 9 | x | 11 | 175 | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-421 | BO | 113/114 | | 28'S OF NEOS | P | 2 | x | 4.5 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-422 | DS-27 | 110/111 | | 120'S OF NEOS | P | 2 | x | 5 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-423 | SI | | 111 | 15'S OF 111/112 & 6'E | P | 1.5 | x | 2 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-424 | DSX-11 | RP-421/114 | | RP-421/114 (DSX-11 ) | P | 2 | x | 6 | | 9/24/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/24/15 |
| RP-425 | PB | 114/115 | | 68'S OF NEOS (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/8/15 |
| RP-426 | CF | 115/116 | | 28'S OF NEOS | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-427 | CF | 117/118 | | 121'S OF NEOS | P | 2 | x | 13 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-428 | WR | | 115 | 12'S OF 114/115 & 3'E | P | 2 | x | 3.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-429 | WR | | 115 | BETWEEN RP-428 & RP-430 | B | | x | | 120 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-430 | WR | | 115 | 12'S OF 114/115 &15.5'E | P | 2 | x | 3.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-431 | CF | | 115 | BETWEEN RP-426 & RP-432 | B | | x | | 48 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-432 | CF | | 115 | FROM RP-431 TO 15'NW | P | 2 | x | 15 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-433 | DO | | 117 | 123'S OF 117/118 & 6'E | P | 1.5 | x | 1.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-434 | CF | | 118 | BETWEEN RP-427 & RP-435 | B | | x | | 12 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-435 | CF | | 118 | FROM RP-436 TO 5'N | B | | x | | 60 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-436 | CF | | 118 | BETWEEN RP-434 & RP-435 | P | 2 | x | 14 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/25/15 |
| RP-437 | CF | 119/120 | | 94'S OF NEOS | P | 2 | x | 3 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-438 | CF | 119/120 | | 22'S OF NEOS | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-439 | CF | 119/120 | | 127'S OF NEOS | P | 2 | x | 9 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-440 | CF | 119/120 | | 139'S OF NEOS | P | 2.5 | x | 4 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-441 | CF | | 119 | FROM RP-437 TO 14'W | B | | x | | 168 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit | |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot | |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out | |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test | |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-442 | CF | | 119 | BETWEEN RP-440 & RP-443 | B | | x | | 192 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-443 | CF | | 119 | 149'S OF 119/120 & 17.5'W | P | 2 | x | 2.5 | | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-444 | CF | 119/120 | | BETWEEN RP-439 & RP-440 | B | | x | | 144 | 9/25/15 | PEDRO S. | EXT 512 | VBOX | P | 9/29/15 |
| RP-445 | AO | RP-445 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-446 | AO | RP-446 | | ON SEAM CONTROL | P | 5 | x | 17 | | 9/29/15 | PEDRO S. | 2025 | Air Pressure | P | 9/29/15 |
| RP-447 | SJ | | | RP-445/RP-446/122 | P | 2 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-448 | SJ | | | RP-446/121/122 | P | 2.5 | x | 3 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-449 | CF | | 122 | FROM RP-448 TO 10'E | B | | x | | 120 | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-450 | BO | 122/123 | | 23'N OF SEOS | P | 2.5 | x | 4 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-451 | SJ | | | P122/123/124 | P | 1.5 | x | 2 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-452 | SJ | | | P 123/124/125 | P | 1.5 | x | 1.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-453 | CF | | 125 | FROM RP-454 TO 11'S | P | 3.5 | x | 11 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-454 | CF | 123/125 | | 18'N OF SEOS | P | 3 | x | 9.5 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-455 | CF | | 125 | FROM RP-454 TO 10'N | P | 3.5 | x | 10 | | 9/29/15 | EMMANUEL V. | EXT 512 | VBOX | P | 9/29/15 |
| RP-456 | DS-28 | 123/125 | | 90'N OF SEOS | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-457 | PB | | 125 | 68'S OF P125/126 & 4'W (PB 8") | P | 3 | x | 3.5 | 52.5 | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-458 | SI | | 125 | ON RP-453 & RP-455 | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-459 | SI | 120,121,122, | &123 | BETWEEN RP-454 TO RP-473 | P | 2 | x | 91 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-460 | DSX-12 | RP-459/123 | | N.SIDE OF RP-459 ( DSX-12 ) | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-461 | SI | | 122 | BETWEEN RP-450 & RP-459 | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-462 | SI | | 122 | FROM RP-461 TO 3'NW | B | | x | | 36 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | |
|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-463 | SI | | 122 | FROM RP-459 TO 5'S | P | 2 | x | 5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-464 | SI | | | SJ 121/122/RP-459 | P | 2 | x | 4 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-465 | SI | | 121 | BETWEEN RP-459 & RP-468 | B | | x | | 6 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-466 | SI | 121/122 | | FROM RP-467 TO RP-465 & RP-468 | B | | x | | 108 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-467 | SI | | 121 | 9'SE OF RP-465 , RP-466 & RP-468 | P | 2 | x | 2.5 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-468 | SI | | 121 | BETWEEN RP-465 & RP-469 | B | | x | | 42 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-469 | SI | | 121 | BETWEEN RP-468 & RP-470 | B | | x | | 132 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-470 | SI | | 121 | 11'SW OF RP-468 | P | 2 | x | 3 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-471 | SI | | 121 | BETWEEN RP-468 & RP-472 | B | | x | | 12 | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-472 | SI | | 121 | FROM RP-471 TO SEOP | P | 2 | x | 23 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-473 | SI | 119/120 | | BETWEEN RP-439,RP-444& RP-440 | P | 2 | x | 17 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-474 | SI | 119/120 | | NEOS TO 16'S | P | 2 | x | 16 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-475 | SI | | 117 | NEOP & 5'W OF 117/118 | P | 2 | x | 14 | | 10/7/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/7/15 |
| RP-476 | PB | 128/132 | 132 | 81'N OF SEOS & 3'E (PB 4") | P | 3 | x | 6 | 36.6 | 10/8/15 | EMMANUEL V. | EXT 512 | VBOX | P | 10/9/15 |
| RP-477 | SI | 125/126 | 125 | 159'S OF NEOS & 13' W | P | 2 | x | 13 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-478 | SJ | | | P 127/128/129 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-479 | SJ | | | P 128/129/132 | P | 2 | x | 3 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-480 | DS-29 | 128/132 | | 25'N OF SEOS | P | 2 | x | 7 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-481 | SJ | | | P 128/131/132 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-482 | SJ | | | P 128/130/131 | P | 2 | x | 2.5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-483 | DSX-13 | RP-477/125 | | N.SIDE OF RP-477 (DSX-13) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |

# *Environmental Specialties International Inc.*

## Repair Report

**Project Name** Honeywell **Job # :** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond**

**Job Description:** Cap Single Layer **Secondary** **Cell**

**Reported by :** Lyssa Tran **Cap** x

**Other:** Cap construction

| Damage Codes | | | | | | |
|---|---|---|---|---|---|---|
| CR --Crease | FS --Failed Seam | MatD --Material Defect | LL --Lost Lap | CF --Custom Fit |
| DS --Destruct Sample | WR --Wrinkle | WS --Welder Restart | MD --Mechanical Damage | PB --Pipe Boot |
| SI --Subgrade Irregularity | AV --Airvent | RW --Roller Wrinkle | DO --Damage By Others | BO --Burn Out |
| SJ --Seam Joint | AO --Add On | CS --Concrete Structure | | AT -Air Test |

| SF Patch Material | Test Type | Abbrv. | Repair Types |
|---|---|---|---|
| 4984.5 | Vacuum | *S=South | C--Cap Strip |
| | Air Pressure | *N=North | P--Patch |
| **LF Welded** | Spark | *W=West | B--Extrusion Bead |
| 6926.06 | Air Lance | *E=East | |

| Repair Number | Damage Code | Seam Number | Panel Number | Location | Repair Type | Patch (Feet) | | | Bead (Inches) | Date Welded | Operator Name | Machine Number | Test Type | Test Results | Date Complete |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RP-484 | DSX-14 | RP-480/132 | | E.SIDE OF RP-480 ( DSX-14) | P | 2 | x | 5 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-485 | SJ | | | P 132/133/143 | P | 2 | x | 2 | | 10/9/15 | PEDRO S. | EXT 512 | VBOX | P | 10/9/15 |
| RP-486 | DSX-15 | RP-487/125 | | N.SIDE OF RP-487 (DSX-15) | P | 2 | x | 5 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-487 | FS | | 125 | DS-13 FAIL (CAP OVER RP-477/RP-483) | P | 5 | x | 15 | | 10/12/15 | EDFY E. | EXT 512 | VBOX | P | 10/12/15 |
| RP-488 | DO | | 123 | 6' S OF NEOS ON SCB WALL EDGE | P | 3 | x | 2.5 | | 11/4/15 | EDFY E. | EXT 512 | NA | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |
| | | | | | | | x | | | | | | | | |

# Appendix M
# ESI Destruct Sample Information Logs

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DS-1 | 3 / 4 | 7/20/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 109 | 101 | 107 | 103 | 108 | 105 | 102 | 105 | 104 | 107 | PASS |
| | | | | | | | | Shear | 113 | | 113 | | 102 | | 109 | | 112 | | |
| | DS Location and Notes | 18'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-2 | 6 / 7 | 7/21/15 | MODESTO L. | 2003 | 500 | 860 | | Peel | 78 | 99 | 102 | 98 | 112 | 108 | 106 | 103 | 107 | 111 | PASS |
| | | | | | | | | Shear | 115 | | 118 | | 120 | | 113 | | 119 | | |
| | DS Location and Notes | 10'E OF WEOS | | | | | | | | | | | | | | | | | |
| DS-3 | 11 / 12 | 7/22/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 106 | 103 | 105 | 105 | 107 | 104 | 103 | 104 | 109 | 97 | PASS |
| | | | | | | | | Shear | 111 | | 109 | | 108 | | 105 | | 108 | | |
| | DS Location and Notes | 100'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-4 | 14 / 15 | 7/23/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 121 | 113 | 115 | 108 | 112 | 117 | 102 | 115 | 118 | 113 | PASS |
| | | | | | | | | Shear | 126 | | 128 | | 129 | | 127 | | 125 | | |
| | DS Location and Notes | 16'S OF NEOS | | | | | | | | | | | | | | | | | |
| DS-5 | 17 / 18 | 7/23/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 119 | 114 | 115 | 101 | 113 | 114 | 118 | 102 | 116 | 110 | PASS |
| | | | | | | | | Shear | 121 | | 118 | | 120 | | 123 | | 122 | | |
| | DS Location and Notes | 75'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-1 | RP-17 / 13 | 7/24/15 | EMMANUEL V. | EXT 512 | | 500 | 490 | Peel | 102 | | 103 | | 107 | | 98 | | 99 | | PASS |
| | | | | | | | | Shear | 120 | | 121 | | 117 | | 121 | | 120 | | |
| | DS Location and Notes | ON RP-17 | | | | | | | | | | | | | | | | | |
| DSX-2 | RP-32 / 15 | 7/27/15 | EMMANUEL V. | EXT 512 | | 500 | 450 | Peel | 126 | | 120 | | 123 | | 122 | | 108 | | PASS |
| | | | | | | | | Shear | 122 | | 122 | | 120 | | 119 | | 116 | | |
| | DS Location and Notes | ON RP-32/15 (10'E OF WEOS) | | | | | | | | | | | | | | | | | |
| DS-6 | 20 / 21 | 7/24/15 | MODESTO L. | 2003 | 550 | 860 | | Peel | 101 | 101 | 100 | 103 | 104 | 106 | 105 | 106 | 110 | 99 | PASS |
| | | | | | | | | Shear | 114 | | 107 | | 111 | | 110 | | 111 | | |
| | DS Location and Notes | 155'S OF NEOS | | | | | | | | | | | | | | | | | |
| DS-7 | 23 / 24 | 7/24/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 106 | 106 | 103 | 105 | 104 | 104 | 100 | 102 | 103 | 102 | PASS |
| | | | | | | | | Shear | 109 | | 111 | | 107 | | 106 | | 108 | | |
| | DS Location and Notes | 87'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-3 | RP-82 / 23 | 7/28/15 | EMMANUEL V. | EXT 512 | | 500 | 450 | Peel | 99 | | 99 | | 104 | | 98 | | 102 | | PASS |
| | | | | | | | | Shear | 109 | | 115 | | 117 | | 112 | | 118 | | |
| | DS Location and Notes | RP-82/23 ( 87'S OF NEOS) | | | | | | | | | | | | | | | | | |
| DS-8 | 26 / 27 | 7/28/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 103 | 101 | 107 | 104 | 104 | 110 | 100 | 105 | 104 | 99 | PASS |
| | | | | | | | | Shear | 122 | | 120 | | 117 | | 120 | | 121 | | |
| | DS Location and Notes | 128'N OF SEOS | | | | | | | | | | | | | | | | | |

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DS-9 | 29 / 30 | 7/28/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 111 | 108 | 114 | 107 | 104 | 100 | 111 | 107 | 110 | 110 | PASS |
| | | | | | | | | Shear | 118 | | 118 | | 117 | | 119 | | 118 | | |
| | DS Location and Notes | 80'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-10 | 32 / 33 | 7/29/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 99 | 110 | 114 | 109 | 110 | 116 | 105 | 106 | 100 | 108 | PASS |
| | | | | | | | | Shear | 118 | | 118 | | 122 | | 121 | | 119 | | |
| | DS Location and Notes | 20'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-4 | RP-102 / 27 | 7/29/15 | EMMANUEL V. | EXT 512 | | 490 | 400 | Peel | 123 | | 125 | | 119 | | 120 | | 122 | | PASS |
| | | | | | | | | Shear | 127 | | 124 | | 130 | | 129 | | 128 | | |
| | DS Location and Notes | ON EAST SIDE OF RP-102/27 | | | | | | | | | | | | | | | | | |
| DS-11 | 36 / 37 | 8/3/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 104 | 99 | 104 | 104 | 98 | 104 | 97 | 106 | 98 | 107 | PASS |
| | | | | | | | | Shear | 113 | | 112 | | 112 | | 115 | | 113 | | |
| | DS Location and Notes | 90'W OF EEOS | | | | | | | | | | | | | | | | | |
| DS-12 | 42 / 43 | 8/3/15 | MODESTO L. | 2003 | 650 | 860 | | Peel | 101 | 105 | 106 | 103 | 110 | 100 | 109 | 104 | 101 | 103 | PASS |
| | | | | | | | | Shear | 111 | | 110 | | 115 | | 116 | | 116 | | |
| | DS Location and Notes | 20'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-5 | RP-160 / 42 | 8/4/15 | PEDRO S. | EXT 512 | | 500 | 500 | Peel | 91 | | 98 | | 111 | | 109 | | 111 | | PASS |
| | | | | | | | | Shear | 118 | | 119 | | 116 | | 115 | | 110 | | |
| | DS Location and Notes | ON RP-160/42 | | | | | | | | | | | | | | | | | |
| DS-13 | 47 / 48 | 8/5/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 118 | 101 | 113 | 103 | 112 | 105 | 110 | 100 | 103 | 116 | PASS |
| | | | | | | | | Shear | 129 | | 121 | | 123 | | 122 | | 122 | | |
| | DS Location and Notes | 70'S OF NEOS | | | | | | | | | | | | | | | | | |
| DS-14 | 50 / 51 | 8/6/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 109 | 112 | 117 | 108 | 113 | 110 | 114 | 112 | 112 | 111 | PASS |
| | | | | | | | | Shear | 132 | | 130 | | 128 | | 131 | | 132 | | |
| | DS Location and Notes | 35'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-6 | RP-198 / 48 | 8/6/15 | PEDRO S. | EXT 512 | | 530 | 530 | Peel | 121 | | 125 | | 122 | | 119 | | 116 | | PASS |
| | | | | | | | | Shear | 118 | | 119 | | 121 | | 118 | | 118 | | |
| | DS Location and Notes | ON RP-198/48 | | | | | | | | | | | | | | | | | |
| DS-15 | 54 / 55 | 8/7/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 101 | 107 | 105 | 107 | 106 | 103 | 101 | 99 | 100 | 106 | PASS |
| | | | | | | | | Shear | 121 | | 119 | | 119 | | 126 | | 120 | | |
| | DS Location and Notes | 72'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-7 | RP-197 / 53 | 8/10/15 | PEDRO S. | EXT 512 | | 530 | 530 | Peel | 109 | | 109 | | 110 | | 112 | | 109 | | PASS |
| | | | | | | | | Shear | 119 | | 121 | | 120 | | 123 | | 119 | | |
| | DS Location and Notes | ON RP-197/53 | | | | | | | | | | | | | | | | | |
| DS-16 | 59 / 61 | 8/10/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 106 | 110 | 100 | 98 | 103 | 100 | 101 | 105 | 100 | 99 | PASS |
| | | | | | | | | Shear | 121 | | 123 | | 119 | | 117 | | 124 | | |
| | DS Location and Notes | 6'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-17 | 62 / 63 | 8/10/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 111 | 112 | 113 | 105 | 113 | 111 | 109 | 111 | 108 | 111 | PASS |
| | | | | | | | | Shear | 124 | | 128 | | 126 | | 120 | | 125 | | |
| | DS Location and Notes | 90'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-18 | 64 / 65 | 8/10/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 111 | 105 | 110 | 113 | 109 | 111 | 108 | 101 | 108 | 109 | PASS |
| | | | | | | | | Shear | 121 | | 123 | | 124 | | 122 | | 123 | | |
| | DS Location and Notes | 128'N OF SEOS | | | | | | | | | | | | | | | | | |

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DS-19 | 68 / 69 | 8/13/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 101 | 106 | 100 | 103 | 103 | 107 | 104 | 105 | 103 | 106 | PASS |
| | | | | | | | | Shear | 122 | | 125 | | 121 | | 124 | | 126 | | |
| | DS Location and Notes | 100'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-20 | 72 / 73 | 8/14/15 | MODESTO L. | 2025 | 450 | 860 | | Peel | 96 | 102 | 98 | 102 | 100 | 106 | 96 | 98 | 99 | 102 | PASS |
| | | | | | | | | Shear | 115 | | 115 | | 114 | | 118 | | 115 | | |
| | DS Location and Notes | 10'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-21 | 74 / 75 | 8/14/15 | MODESTO L. | 2025 | 600 | 860 | | Peel | 103 | 103 | 103 | 107 | 106 | 105 | 104 | 105 | 103 | 105 | PASS |
| | | | | | | | | Shear | 119 | | 120 | | 123 | | 116 | | 118 | | |
| | DS Location and Notes | 75'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-8 | RP-284 / 71 | 9/9/15 | PEDRO S. | EXT 512 | | 550 | 550 | Peel | 106 | | 100 | | 100 | | 103 | | 101 | | PASS |
| | | | | | | | | Shear | 119 | | 116 | | 117 | | 120 | | 119 | | |
| | DS Location and Notes | ON RP-284/71 | | | | | | | | | | | | | | | | | |
| DS-22 | 79 / 80 | 9/9/15 | PEDRO S. | 2025 | 400 | 860 | | Peel | 119 | 115 | 116 | 118 | 114 | 113 | 113 | 113 | 116 | 118 | PASS |
| | | | | | | | | Shear | 117 | | 117 | | 116 | | 113 | | 112 | | |
| | DS Location and Notes | 78'E OF WEOS | | | | | | | | | | | | | | | | | |
| DS-23 | 88 / 89 | 9/15/15 | PEDRO S. | 2025 | 400 | 860 | | Peel | 97 | 95 | 101 | 102 | 97 | 94 | 96 | 95 | 97 | 96 | PASS |
| | | | | | | | | Shear | 113 | | 116 | | 117 | | 111 | | 116 | | |
| | DS Location and Notes | 116'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-9 | RP-316 / 88 | 9/16/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 100 | | 100 | | 99 | | 103 | | 105 | | PASS |
| | | | | | | | | Shear | 119 | | 119 | | 118 | | 116 | | 120 | | |
| | DS Location and Notes | RP-316/88 | | | | | | | | | | | | | | | | | |
| DS-24 | 91 / 92 | 9/16/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 109 | 98 | 110 | 96 | 108 | 100 | 105 | 97 | 98 | 108 | PASS |
| | | | | | | | | Shear | 111 | | 116 | | 112 | | 118 | | 113 | | |
| | DS Location and Notes | 45'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-25 | 94 / 95 | 9/17/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 114 | 109 | 114 | 109 | 114 | 110 | 116 | 104 | 113 | 107 | PASS |
| | | | | | | | | Shear | 126 | | 127 | | 122 | | 120 | | 126 | | |
| | DS Location and Notes | 100'N OF SEOS | | | | | | | | | | | | | | | | | |
| DS-26 | 96 / 97 | 9/17/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 98 | 85 | 100 | 98 | 100 | 100 | 98 | 92 | 96 | 98 | PASS |
| | | | | | | | | Shear | 104 | | 106 | | 109 | | 109 | | 110 | | |
| | DS Location and Notes | 33'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-10 | RP-376 / 96 | 9/21/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 95 | | 94 | | 99 | | 98 | | 98 | | PASS |
| | | | | | | | | Shear | 101 | | 101 | | 103 | | 105 | | 101 | | |
| | DS Location and Notes | RP-376/96 | | | | | | | | | | | | | | | | | |
| DS-27 | 110 / 111 | 9/23/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 112 | 116 | 114 | 116 | 105 | 120 | 109 | 114 | 110 | 115 | PASS |
| | | | | | | | | Shear | 127 | | 128 | | 127 | | 125 | | 125 | | |
| | DS Location and Notes | 120'S OF NEOS | | | | | | | | | | | | | | | | | |
| DSX-11 | RP-421 / 114 | 9/24/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 117 | | 116 | | 108 | | 108 | | 112 | | PASS |
| | | | | | | | | Shear | 119 | | 112 | | 111 | | 116 | | 114 | | |
| | DS Location and Notes | RP-421/114 | | | | | | | | | | | | | | | | | |
| DS-28 | 123 / 125 | 9/29/15 | PEDRO S. | 2025 | 400 | 860 | | Peel | 115 | 127 | 112 | 123 | 119 | 117 | 109 | 113 | 106 | 126 | PASS |
| | | | | | | | | Shear | 141 | | 138 | | 133 | | 136 | | 137 | | |
| | DS Location and Notes | 90'N OF SEOS | | | | | | | | | | | | | | | | | |

## *Environmental Specialties International Inc.*

## Destructive Sample Information

**Project Name:** Honeywell **Job #** 12-11-1399 **Superintendent:** Fortino Ayala

**Material Type:** LLDPE 60 MIL DST **Primary** **Pond** **Peel Test Extrusion Minimum** 66 PPI

**Job Description:** Cap Single Layer **Secondary** **Cell** **Peel Test Fusion Minimum** 75 PPI

**Reported By:** Lyssa-Tran Tran **Cap** x **Shear Test Minimum** 90 PPI

**Other:** Cap Construction

| D.S. No. | Seam No. | Weld Date | Operator Name/ ID | Mach No. | Mach Speed | Mach Temp | Preheat Temp | | Coupon 1 A | Coupon 1 B | Coupon 2 A | Coupon 2 B | Coupon 3 A | Coupon 3 B | Coupon 4 A | Coupon 4 B | Coupon 5 A | Coupon 5 B | Test Results |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DSX-12 | RP-459 / 123 | 10/7/15 | EMMANUEL V. | EXT 512 | | 550 | 550 | Peel | 106 | | 110 | | 111 | | 105 | | 104 | | PASS |
| | | | | | | | | Shear | 128 | | 129 | | 128 | | 131 | | 127 | | |
| | DS Location and Notes | N.SIDE OF RP-459 | | | | | | | | | | | | | | | | | |
| DS-29 | 128 / 132 | 10/8/15 | PEDRO S. | 2025 | 450 | 860 | | Peel | 112 | 116 | 106 | 123 | 116 | 109 | 125 | 113 | 125 | 112 | PASS |
| | | | | | | | | Shear | 133 | | 139 | | 130 | | 136 | | 134 | | |
| | DS Location and Notes | 25'N OF SEOS | | | | | | | | | | | | | | | | | |
| DSX-13 | RP-477 / 125 | 10/9/15 | PEDRO S. | EXT 512 | | 550 | 550 | Peel | 121 | | 118 | | 120 | | 119 | | 121 | | FAIL |
| | | | | | | | | Shear | 136 | | 133 | | 137 | | 136 | | 131 | | |
| | DS Location and Notes | N.SIDE OF RP-477 (DSX-13 FAIL AT LAB , TRACK TO DSX-15 ) | | | | | | | | | | | | | | | | | |
| DSX-14 | RP-480 / 132 | 10/9/15 | PEDRO S. | EXT 512 | | 550 | 550 | Peel | 118 | | 117 | | 125 | | 119 | | 120 | | PASS |
| | | | | | | | | Shear | 138 | | 139 | | 138 | | 136 | | 134 | | |
| | DS Location and Notes | E.SIDE OF RP-480 | | | | | | | | | | | | | | | | | |
| DSX-15 | RP-487 / 125 | 10/12/15 | EDFY N. | EXT 512 | | 550 | 550 | Peel | 122 | | 113 | | 114 | | 117 | | 108 | | PASS |
| | | | | | | | | Shear | 133 | | 117 | | 131 | | 128 | | 126 | | |
| | DS Location and Notes | N.SIDE OF RP-487/125 | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |
| | / | | | | | | | Peel | | | | | | | | | | | |
| | | | | | | | | Shear | | | | | | | | | | | |
| | DS Location and Notes | | | | | | | | | | | | | | | | | | |

# Appendix N
# Laboratory Destruct Test Results

# *Entact / ESI – Fusion Weld Destruct Sample Laboratory Data*

# Honeywell SA-6 Capping

## *Comparison of ESI / Langan (QA) Destruct Samples - Fusion Weld*

| *Sample ID* | *Weld Type* | *Submitted By:* | *Test* | *Peel Strength (ppi)* | | | | | Avg. Strength (ppi) | *Meets Spec Requirement* |
|---|---|---|---|---|---|---|---|---|---|---|
| DS-1 | Fusion | Entact | Side A Peel | 126.4 | 122.5 | 125.3 | 125.4 | 124.7 | **124.9** | **Yes** |
| | | | Side B Peel | 120.8 | 118.5 | 118.9 | 117.8 | 116.5 | **118.5** | **Yes** |
| | | | Shear | 126.7 | 137.9 | 136.1 | 142.3 | 138.8 | **136.4** | **Yes** |
| DS-2 | Fusion | Langan | Side A Peel | 138 | 142 | 138 | 140 | 134 | **138** | **Yes** |
| | | Entact | Side A Peel | 126.3 | 125.8 | 126.5 | 128.8 | 129.3 | **127.3** | **Yes** |
| | | Langan | Side B Peel | 139 | 143 | 140 | 138 | 134 | **139** | **Yes** |
| | | Entact | Side B Peel | 121.8 | 123.1 | 124.6 | 123.1 | 124.3 | **123.4** | **Yes** |
| | | Langan | Shear | 139 | 146 | 143 | 147 | 145 | **144** | **Yes** |
| | | Entact | Shear | 127.9 | 133.2 | 138.3 | 135 | 132.4 | **133.4** | **Yes** |
| DS-3 | Fusion | Entact | Side A Peel | 127.5 | 120.8 | 122.1 | 123.2 | 123.7 | **123.5** | **Yes** |
| | | | Side B Peel | 124.2 | 118.4 | 121.2 | 119.7 | 120.1 | **120.7** | **Yes** |
| | | | Shear | 131.3 | 127.3 | 127.8 | 128.8 | 127.5 | **128.5** | **Yes** |
| DS-4 | Fusion | Entact | Side A Peel | 108.7 | 105 | 107.7 | 109.8 | 104.7 | **107.2** | **Yes** |
| | | | Side B Peel | 110.4 | 109 | 107.1 | 107.9 | 108.3 | **108.5** | **Yes** |
| | | | Shear | 115.3 | 115.1 | 117.8 | 115.6 | 115.4 | **115.8** | **Yes** |
| DS-5 | Fusion | Entact | Side A Peel | 112 | 110.3 | 114.6 | 111.8 | 112.2 | **112.2** | **Yes** |
| | | | Side B Peel | 107.3 | 101 | 105.6 | 105.2 | 104.2 | **104.7** | **Yes** |
| | | | Shear | 117.7 | 117.5 | 121.3 | 120.2 | 118.2 | **119.0** | **Yes** |
| DS-6 | Fusion | Entact | Side A Peel | 115.2 | 113.8 | 116.8 | 99.3 | 119.9 | **113.0** | **Yes** |
| | | | Side B Peel | 120.3 | 109.4 | 115.4 | 102.9 | 110.5 | **111.7** | **Yes** |
| | | | Shear | 125.1 | 123.5 | 124.6 | 125.6 | 122.2 | **124.2** | **Yes** |
| DS-7 | Fusion | Entact | Side A Peel | 117 | 115.9 | 119.8 | 115.7 | 116.1 | **116.9** | **Yes** |
| | | | Side B Peel | 113.1 | 113.6 | 115.8 | 110.9 | 111.7 | **113.0** | **Yes** |
| | | | Shear | 125.6 | 124.3 | 124 | 128.7 | 125.7 | **125.7** | **Yes** |
| DS-8 | Fusion | Entact | Side A Peel | 121.5 | 124.7 | 123.3 | 126.9 | 124.2 | **124.1** | **Yes** |
| | | | Side B Peel | 115.6 | 116.6 | 115.5 | 119.4 | 116.7 | **116.8** | **Yes** |
| | | | Shear | 135.4 | 127.5 | 130.7 | 127.8 | 126.1 | **129.5** | **Yes** |
| DS-9 | Fusion | Entact | Side A Peel | 122.8 | 123.5 | 124.5 | 123.4 | 128.6 | **124.6** | **Yes** |
| | | | Side B Peel | 120.1 | 120.1 | 119.9 | 121 | 124.1 | **121.0** | **Yes** |
| | | | Shear | 136.1 | 131.2 | 131.9 | 134.5 | 130.7 | **132.9** | **Yes** |
| DS-10 | Fusion | Langan | Side A Peel | 121 | 121 | 124 | 123 | 122 | **122.2** | **Yes** |
| | | Entact | Side A Peel | 119.3 | 119.8 | 118.3 | 125.2 | 119.4 | **120.4** | **Yes** |
| | | Langan | Side B Peel | 121 | 118 | 120 | 117 | 125 | **120.2** | **Yes** |
| | | Entact | Side B Peel | 116.7 | 118.5 | 109.6 | 113.5 | 113.9 | **114.4** | **Yes** |
| | | Langan | Shear | 134 | 133 | 134 | 129 | 130 | **132.0** | **Yes** |
| | | Entact | Shear | 135.9 | 132.1 | 132.1 | 134.7 | 134.2 | **133.8** | **Yes** |
| DS-11 | Fusion | Entact | Side A Peel | 127.4 | 124.6 | 126.7 | 125.4 | 123.5 | **125.5** | **Yes** |
| | | | Side B Peel | 126.5 | 120.8 | 128.3 | 123.9 | 123.5 | **124.6** | **Yes** |
| | | | Shear | 134.6 | 135.4 | 138.6 | 136.1 | 136.6 | **136.3** | **Yes** |
| DS-12 | Fusion | Entact | Side A Peel | 129.7 | 131.2 | 135.1 | 130.6 | 134.7 | **132.3** | **Yes** |
| | | | Side B Peel | 118.9 | 116.7 | 128.9 | 115.9 | 120.3 | **120.1** | **Yes** |
| | | | Shear | 146.2 | 141.4 | 143.3 | 142.2 | 141.7 | **143.0** | **Yes** |
| DS-13 | Fusion | Entact | Side A Peel | 121.3 | 114.1 | 110.8 | 123.4 | 118.8 | **117.7** | **Yes** |
| | | | Side B Peel | 113.9 | 121.3 | 116.3 | 120 | 119.6 | **118.2** | **Yes** |
| | | | Shear | 137.1 | 138.9 | 140.2 | 130.3 | 142.7 | **137.8** | **Yes** |
| DS-14 | Fusion | Entact | Side A Peel | 121.8 | 120.9 | 120.2 | 121.7 | 127.6 | **122.4** | **Yes** |
| | | | Side B Peel | 123.1 | 122.6 | 121.6 | 126.7 | 132.6 | **125.3** | **Yes** |
| | | | Shear | 141.2 | 143.6 | 142 | 139.6 | 140.9 | **141.5** | **Yes** |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| DS-15 | Fusion | Entact | Side A Peel | 106.6 | 109.7 | 106.8 | 108.7 | 107.2 | **107.8** | **Yes** |
| | | | Side B Peel | 113.7 | 108.9 | 110.1 | 109.7 | 107.2 | **109.9** | **Yes** |
| | | | Shear | 132.5 | 127.1 | 124.3 | 127.2 | 127.3 | **127.7** | **Yes** |
| DS-16 | Fusion | Entact | Side A Peel | 111.4 | 114.2 | 118.3 | 113.6 | 108.7 | **113.2** | **Yes** |
| | | | Side B Peel | 114.1 | 113.2 | 119.3 | 114 | 112.7 | **114.7** | **Yes** |
| | | | Shear | 113.6 | 133.4 | 136.1 | 132.2 | 135.1 | **130.1** | **Yes** |
| DS-17 | Fusion | Entact | Side A Peel | 121.1 | 121.9 | 122.3 | 122.4 | 120.6 | **121.7** | **Yes** |
| | | | Side B Peel | 121.9 | 116 | 118.1 | 123.6 | 121 | **120.1** | **Yes** |
| | | | Shear | 136.1 | 136.1 | 135.6 | 138.7 | 136.8 | **136.7** | **Yes** |
| DS-18 | Fusion | Entact | Side A Peel | 112.6 | 120.7 | 118.2 | 114.7 | 116.6 | **116.6** | **Yes** |
| | | | Side B Peel | 110.3 | 109.4 | 113.4 | 112 | 114.1 | **111.8** | **Yes** |
| | | | Shear | 138.8 | 135.9 | 133.9 | 136.1 | 136.7 | **136.3** | **Yes** |
| DS-19 | Fusion | Entact | Side A Peel | 114.6 | 118 | 113.7 | 112.8 | 112.9 | **114.4** | **Yes** |
| | | | Side B Peel | 118.1 | 121.2 | 117.2 | 118.6 | 119.1 | **118.8** | **Yes** |
| | | | Shear | 138.1 | 136.2 | 133.6 | 133.1 | 133.9 | **135.0** | **Yes** |
| DS-20 | Fusion | Entact | Side A Peel | 119.6 | 118.8 | 114.7 | 117.4 | 116.3 | **117.4** | **Yes** |
| | | | Side B Peel | 112.7 | 117.6 | 116.1 | 114.6 | 113.8 | **115.0** | **Yes** |
| | | | Shear | 140.9 | 135.7 | 140.4 | 142.7 | 141.4 | **140.2** | **Yes** |
| DS-21 | Fusion | Langan | Side A Peel | 113 | 115 | 114 | 116 | 115 | **114.6** | **Yes** |
| | | Entact | Side A Peel | 117.8 | 118.5 | 113.2 | 112.4 | 112.1 | **114.8** | **Yes** |
| | | Langan | Side B Peel | 120 | 119 | 122 | 130 | 128 | **123.8** | **Yes** |
| | | Entact | Side B Peel | 112.3 | 122.1 | 120 | 109.4 | 112 | **115.2** | **Yes** |
| | | Langan | Shear | 142 | 147 | 145 | 142 | 144 | **144.0** | **Yes** |
| | | Entact | Shear | 145.9 | 144.4 | 147.2 | 143.7 | 142.9 | **144.8** | **Yes** |
| DS-22 | Fusion | Entact | Side A Peel | 120 | 125.9 | 118.4 | 117.9 | 118.2 | **120.1** | **Yes** |
| | | | Side B Peel | 125.9 | 123.5 | 118.4 | 120.4 | 120.1 | **121.7** | **Yes** |
| | | | Shear | 137.9 | 131.6 | 134.7 | 132.4 | 133.5 | **134.0** | **Yes** |
| DS-23 | Fusion | Entact | Side A Peel | 108.9 | 113.2 | 109.4 | 109.7 | 113.9 | **111.0** | **Yes** |
| | | | Side B Peel | 118.3 | 114.9 | 109.3 | 111.3 | 122 | **115.2** | **Yes** |
| | | | Shear | 128.5 | 129.2 | 129.7 | 130.9 | 129.5 | **129.6** | **Yes** |
| DS-24 | Fusion | Entact | Side A Peel | 120 | 118.2 | 118.6 | 120.2 | 119.2 | **119.2** | **Yes** |
| | | | Side B Peel | 109.8 | 112.1 | 112.9 | 115.4 | 114.4 | **112.9** | **Yes** |
| | | | Shear | 128.9 | 132.4 | 135.2 | 135 | 124.9 | **131.3** | **Yes** |
| DS-25 | Fusion | Entact | Side A Peel | 117.6 | 110.4 | 117.8 | 116.8 | 118.4 | **116.2** | **Yes** |
| | | | Side B Peel | 119.6 | 125 | 120.3 | 125.5 | 126.9 | **123.5** | **Yes** |
| | | | Shear | 129.9 | 131.1 | 135.5 | 135.3 | 134.2 | **133.2** | **Yes** |
| DS-26 | Fusion | Entact | Side A Peel | 115.7 | 115.5 | 112.9 | 117.9 | 117.6 | **115.9** | **Yes** |
| | | | Side B Peel | 98.1 | 99.5 | 104.4 | 101.9 | 118.5 | **104.5** | **Yes** |
| | | | Shear | 130.9 | 126.7 | 133 | 126.4 | 130.8 | **129.6** | **Yes** |
| DS-27 | Fusion | Entact | Side A Peel | 111.1 | 105.2 | 109.7 | 109.1 | 108.5 | **108.7** | **Yes** |
| | | | Side B Peel | 121.6 | 114.8 | 120.1 | 125 | 121.6 | **120.6** | **Yes** |
| | | | Shear | 126 | 125.7 | 127.8 | 128.4 | 132.1 | **128.0** | **Yes** |
| DS-28 | Fusion | Entact | Side A Peel | 111.1 | 107.3 | 111.3 | 108.5 | 108.7 | **109.4** | **Yes** |
| | | | Side B Peel | 112.3 | 107.8 | 109.9 | 107.8 | 123.9 | **112.3** | **Yes** |
| | | | Shear | 132.8 | 129 | 129.7 | 128.6 | 134.3 | **130.9** | **Yes** |
| DS-29 | Fusion | Langan | Side A Peel | 111 | 112 | 110 | 112 | 114 | **111.8** | **Yes** |
| | | Entact | Side A Peel | 111.4 | 112.5 | 115.4 | 116.7 | 119.3 | **115.1** | **Yes** |
| | | Langan | Side B Peel | 113 | 124 | 111 | 121 | 115 | **116.8** | **Yes** |
| | | Entact | Side B Peel | 121.1 | 118.5 | 115.5 | 115.6 | 120.3 | **118.2** | **Yes** |
| | | Langan | Shear | 138 | 140 | 140 | 138 | 138 | **138.8** | **Yes** |
| | | Entact | Shear | 129.5 | 131.7 | 131.7 | 130.7 | 132.1 | **131.1** | **Yes** |

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-09
LAB ID NO.: L15084-09-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-1**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 126.4 | SE1 | <10 |
| 2 | 122.5 | SE1 | <10 |
| 3 | 125.3 | SE1 | <10 |
| 4 | 125.4 | SE1 | <10 |
| 5 | 124.7 | SE1 | <10 |
| **AVERAGE** | **124.9** | | |
| STD. DEV. | 1.30 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 120.8 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 118.9 | SE1 | <10 |
| 4 | 117.8 | SE1 | <10 |
| 5 | 116.5 | SE1 | <10 |
| **AVERAGE** | **118.5** | | |
| STD. DEV. | 1.41 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.7 | SE1 |
| 2 | 137.9 | SE1 |
| 3 | 136.1 | SE1 |
| 4 | 142.3 | SE1 |
| 5 | 138.8 | SE1 |
| **AVERAGE** | **136.4** | |
| STD. DEV. | 5.23 | |

CHECKED BY: JC DATE: 7/22/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-09
LAB ID NO.: L15084-09-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-2**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 126.3 | SE1 | <10 |
| 2 | 125.8 | SE1 | <10 |
| 3 | 126.5 | SE1 | <10 |
| 4 | 128.8 | SE1 | <10 |
| 5 | 129.3 | SE1 | <10 |
| **AVERAGE** | **127.3** | | |
| STD. DEV. | 1.42 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.8 | SE1 | <10 |
| 2 | 123.1 | SE1 | <10 |
| 3 | 124.6 | SE1 | <10 |
| 4 | 123.1 | SE1 | <10 |
| 5 | 124.3 | SE1 | <10 |
| **AVERAGE** | **123.4** | | |
| STD. DEV. | 1.00 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 127.9 | SE1 |
| 2 | 133.2 | SE1 |
| 3 | 138.3 | SE1 |
| 4 | 135.0 | SE1 |
| 5 | 132.4 | SE1 |
| **AVERAGE** | **133.4** | |
| STD. DEV. | 3.40 | |

CHECKED BY: NC DATE: 7/22/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-11
LAB ID NO.: L15084-11-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-3**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 127.5 | SE1 | <10 |
| 2 | 120.8 | SE1 | <10 |
| 3 | 122.1 | SE1 | <10 |
| 4 | 123.2 | SE1 | <10 |
| 5 | 123.7 | SE1 | <10 |
| **AVERAGE** | **123.5** | | |
| STD. DEV. | 2.25 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 124.2 | SE1 | <10 |
| 2 | 118.4 | SE1 | <10 |
| 3 | 121.2 | SE1 | <10 |
| 4 | 119.7 | SE1 | <10 |
| 5 | 120.1 | SE1 | <10 |
| **AVERAGE** | **120.7** | | |
| STD. DEV. | 1.96 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.3 | SE1 |
| 2 | 127.3 | SE1 |
| 3 | 127.8 | SE1 |
| 4 | 128.8 | SE1 |
| 5 | 127.5 | SE1 |
| **AVERAGE** | **128.5** | |
| STD. DEV. | 1.47 | |

CHECKED BY: JAM DATE: 7/23/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-12
LAB ID NO.: L15084-12-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-4**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 108.7 | SE1 | <10 |
| 2 | 105.0 | SE1 | <10 |
| 3 | 107.7 | SE1 | <10 |
| 4 | 109.8 | SE1 | <10 |
| 5 | 104.7 | SE1 | <10 |
| **AVERAGE** | **107.2** | | |
| STD. DEV. | 2.02 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 110.4 | SE1 | <10 |
| 2 | 109.0 | SE1 | <10 |
| 3 | 107.1 | SE1 | <10 |
| 4 | 107.9 | SE1 | <10 |
| 5 | 108.3 | SE1 | <10 |
| **AVERAGE** | **108.5** | | |
| STD. DEV. | 1.11 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 115.3 | SE1 |
| 2 | 115.1 | SE1 |
| 3 | 117.8 | SE1 |
| 4 | 115.6 | SE1 |
| 5 | 115.4 | SE1 |
| **AVERAGE** | **115.8** | |
| STD. DEV. | 0.99 | |

CHECKED BY: JAM DATE: 7/27/15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-12 L  L15084-12-02  7/27/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-12
LAB ID NO.: L15084-12-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-5**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 112.0 | SE1 | <10 |
| 2 | 110.3 | SE1 | <10 |
| 3 | 114.6 | SE1 | <10 |
| 4 | 111.8 | SE1 | <10 |
| 5 | 112.2 | SE1 | <10 |
| **AVERAGE** | **112.2** | | |
| STD. DEV. | 1.38 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 107.3 | SE1 | <10 |
| 2 | 101.0 | SE1 | <10 |
| 3 | 105.6 | SE1 | <10 |
| 4 | 105.2 | SE1 | <10 |
| 5 | 104.2 | SE1 | <10 |
| **AVERAGE** | **104.7** | | |
| STD. DEV. | 2.09 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 117.7 | SE1 |
| 2 | 117.5 | SE1 |
| 3 | 121.3 | SE1 |
| 4 | 120.2 | SE1 |
| 5 | 118.2 | SE1 |
| **AVERAGE** | **119.0** | |
| STD. DEV. | 1.50 | |

CHECKED BY: JK DATE: 7/27/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-13
LAB ID NO.: L15084-13-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-6**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 115.2 | SE1 | <10 |
| 2 | 113.8 | SE1 | <10 |
| 3 | 116.8 | SE1 | <10 |
| 4 | 99.3 | SE1 | <10 |
| 5 | 119.9 | SE1 | <10 |
| **AVERAGE** | **113.0** | | |
| STD. DEV. | 7.14 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 120.3 | SE1 | <10 |
| 2 | 109.4 | SE1 | <10 |
| 3 | 115.4 | SE1 | <10 |
| 4 | 102.9 | SE1 | <10 |
| 5 | 110.5 | SE1 | <10 |
| **AVERAGE** | **111.7** | | |
| STD. DEV. | 5.86 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 125.1 | SE1 |
| 2 | 123.5 | SE1 |
| 3 | 124.6 | SE1 |
| 4 | 125.6 | SE1 |
| 5 | 122.2 | SE1 |
| **AVERAGE** | **124.2** | |
| STD. DEV. | 1.22 | |

CHECKED BY: NC DATE: 7/28/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-13
LAB ID NO.: L15084-13-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-7**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 117.0 | SE1 | <10 |
| 2 | 115.9 | SE1 | <10 |
| 3 | 119.8 | SE1 | <10 |
| 4 | 115.7 | SE1 | <10 |
| 5 | 116.1 | SE1 | <10 |
| **AVERAGE** | **116.9** | | |
| STD. DEV. | 1.52 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 113.1 | SE1 | <10 |
| 2 | 113.6 | SE1 | <10 |
| 3 | 115.8 | SE1 | <10 |
| 4 | 110.9 | SE1 | <10 |
| 5 | 111.7 | SE1 | <10 |
| **AVERAGE** | **113.0** | | |
| STD. DEV. | 1.69 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 125.6 | SE1 |
| 2 | 124.3 | SE1 |
| 3 | 124.0 | SE1 |
| 4 | 128.7 | SE1 |
| 5 | 125.7 | SE1 |
| **AVERAGE** | **125.7** | |
| STD. DEV. | 1.66 | |

CHECKED BY: NC DATE: 7/28/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-15
LAB ID NO.: L15084-15-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-8**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.5 | SE1 | <10 |
| 2 | 124.7 | SE1 | <10 |
| 3 | 123.3 | SE1 | <10 |
| 4 | 126.9 | SE1 | <10 |
| 5 | 124.2 | SE1 | <10 |
| **AVERAGE** | **124.1** | | |
| STD. DEV. | 1.77 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 115.6 | SE1 | <10 |
| 2 | 116.6 | SE1 | <10 |
| 3 | 115.5 | SE1 | <10 |
| 4 | 119.4 | SE1 | <10 |
| 5 | 116.7 | SE1 | <10 |
| **AVERAGE** | **116.8** | | |
| STD. DEV. | 1.41 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 135.4 | SE1 |
| 2 | 127.5 | SE1 |
| 3 | 130.7 | SE1 |
| 4 | 127.8 | SE1 |
| 5 | 126.1 | SE1 |
| **AVERAGE** | **129.5** | |
| STD. DEV. | 3.31 | |

CHECKED BY: JO DATE: 7.30-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-15
LAB ID NO.: L15084-15-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-9**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 122.8 | SE1 | <10 |
| 2 | 123.5 | SE1 | <10 |
| 3 | 124.5 | SE1 | <10 |
| 4 | 123.4 | SE1 | <10 |
| 5 | 128.6 | SE1 | <10 |
| **AVERAGE** | **124.6** | | |
| STD. DEV. | 2.09 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 120.1 | SE1 | <10 |
| 2 | 120.1 | SE1 | <10 |
| 3 | 119.9 | SE1 | <10 |
| 4 | 121.0 | SE1 | <10 |
| 5 | 124.1 | SE1 | <10 |
| **AVERAGE** | **121.0** | | |
| STD. DEV. | 1.58 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 136.1 | SE1 |
| 2 | 131.2 | SE1 |
| 3 | 131.9 | SE1 |
| 4 | 134.5 | SE1 |
| 5 | 130.7 | SE1 |
| **AVERAGE** | **132.9** | |
| STD. DEV. | 2.07 | |

CHECKED BY: JO DATE: 7-30-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-16
LAB ID NO.: L15084-16-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-10**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 119.3 | SE1 | <10 |
| 2 | 119.8 | SE1 | <10 |
| 3 | 118.3 | SE1 | <10 |
| 4 | 125.2 | SE1 | <10 |
| 5 | 119.4 | SE1 | <10 |
| **AVERAGE** | **120.4** | | |
| STD. DEV. | 2.45 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 116.7 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 109.6 | SE1 | <10 |
| 4 | 113.5 | SE1 | <10 |
| 5 | 113.9 | SE1 | <10 |
| **AVERAGE** | **114.4** | | |
| STD. DEV. | 3.04 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 135.9 | SE1 |
| 2 | 132.1 | SE1 |
| 3 | 132.1 | SE1 |
| 4 | 134.7 | SE1 |
| 5 | 134.2 | SE1 |
| **AVERAGE** | **133.8** | |
| STD. DEV. | 1.49 | |

CHECKED BY: JO DATE: 7-31-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-18
LAB ID NO.: L15084-18-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-11**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 127.4 | SE1 | <10 |
| 2 | 124.6 | SE1 | <10 |
| 3 | 126.7 | SE1 | <10 |
| 4 | 125.4 | SE1 | <10 |
| 5 | 123.5 | SE1 | <10 |
| **AVERAGE** | **125.5** | | |
| STD. DEV. | 1.40 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 126.5 | SE1 | <10 |
| 2 | 120.8 | SE1 | <10 |
| 3 | 128.3 | SE1 | <10 |
| 4 | 123.9 | SE1 | <10 |
| 5 | 123.5 | SE1 | <10 |
| **AVERAGE** | **124.6** | | |
| STD. DEV. | 2.59 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 134.6 | SE1 |
| 2 | 135.4 | SE1 |
| 3 | 138.6 | SE1 |
| 4 | 136.1 | SE1 |
| 5 | 136.6 | SE1 |
| **AVERAGE** | **136.3** | |
| STD. DEV. | 1.35 | |

CHECKED BY: JO DATE: 8-5-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-18
LAB ID NO.: L15084-18-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-12**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 129.7 | SE1 | <10 |
| 2 | 131.2 | SE1 | <10 |
| 3 | 135.1 | SE1 | <10 |
| 4 | 130.6 | SE1 | <10 |
| 5 | 134.7 | SE1 | <10 |
| **AVERAGE** | **132.3** | | |
| STD. DEV. | 2.21 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 118.9 | SE1 | <10 |
| 2 | 116.7 | SE1 | <10 |
| 3 | 128.9 | SE1 | <10 |
| 4 | 115.9 | SE1 | <10 |
| 5 | 120.3 | SE1 | <10 |
| **AVERAGE** | **120.1** | | |
| STD. DEV. | 4.65 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 146.2 | SE1 |
| 2 | 141.4 | SE1 |
| 3 | 143.3 | SE1 |
| 4 | 142.2 | SE1 |
| 5 | 141.7 | SE1 |
| **AVERAGE** | **143.0** | |
| STD. DEV. | 1.74 | |

CHECKED BY: J.O DATE: 8-5-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-18 L L15084-18-02 8/5/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-20
LAB ID NO.: L15084-20-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-13**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.3 | SE1 | <10 |
| 2 | 114.1 | SE1 | <10 |
| 3 | 110.8 | SE1 | <10 |
| 4 | 123.4 | SE1 | <10 |
| 5 | 118.8 | SE1 | <10 |
| **AVERAGE** | **117.7** | | |
| STD. DEV. | 4.63 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 113.9 | SE1 | <10 |
| 2 | 121.3 | SE1 | <10 |
| 3 | 116.3 | SE1 | <10 |
| 4 | 120.0 | SE1 | <10 |
| 5 | 119.6 | SE1 | <10 |
| **AVERAGE** | **118.2** | | |
| STD. DEV. | 2.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 137.1 | SE1 |
| 2 | 138.9 | SE1 |
| 3 | 140.2 | SE1 |
| 4 | 130.3 | SE1 |
| 5 | 142.7 | SE1 |
| **AVERAGE** | **137.8** | |
| STD. DEV. | 4.19 | |

CHECKED BY: JO DATE: 8-10-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-20
LAB ID NO.: L15084-20-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-14**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.8 | SE1 | <10 |
| 2 | 120.9 | SE1 | <10 |
| 3 | 120.2 | SE1 | <10 |
| 4 | 121.7 | SE1 | <10 |
| 5 | 127.6 | SE1 | <10 |
| **AVERAGE** | **122.4** | | |
| STD. DEV. | 2.64 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 123.1 | SE1 | <10 |
| 2 | 122.6 | SE1 | <10 |
| 3 | 121.6 | SE1 | <10 |
| 4 | 126.7 | SE1 | <10 |
| 5 | 132.6 | SE1 | <10 |
| **AVERAGE** | **125.3** | | |
| STD. DEV. | 4.03 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 141.2 | SE1 |
| 2 | 143.6 | SE1 |
| 3 | 142.0 | SE1 |
| 4 | 139.6 | SE1 |
| 5 | 140.9 | SE1 |
| **AVERAGE** | **141.5** | |
| STD. DEV. | 1.32 | |

CHECKED BY: JO DATE: 8-10-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-21
LAB ID NO.: L15084-21-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-15**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 106.6 | SE1 | <10 |
| 2 | 109.7 | SE1 | <10 |
| 3 | 106.8 | SE1 | <10 |
| 4 | 108.7 | SE1 | <10 |
| 5 | 107.2 | SE1 | <10 |
| **AVERAGE** | **107.8** | | |
| STD. DEV. | 1.20 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 113.7 | SE1 | <10 |
| 2 | 108.9 | SE1 | <10 |
| 3 | 110.1 | SE1 | <10 |
| 4 | 109.7 | SE1 | <10 |
| 5 | 107.2 | SE1 | <10 |
| **AVERAGE** | **109.9** | | |
| STD. DEV. | 2.14 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.5 | SE1 |
| 2 | 127.1 | SE1 |
| 3 | 124.3 | SE1 |
| 4 | 127.2 | SE1 |
| 5 | 127.3 | SE1 |
| **AVERAGE** | **127.7** | |
| STD. DEV. | 2.66 | |

CHECKED BY: JO DATE: 8-11-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-21
LAB ID NO.: L15084-21-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-16**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.4 | SE1 | <10 |
| 2 | 114.2 | SE1 | <10 |
| 3 | 118.3 | SE1 | <10 |
| 4 | 113.6 | SE1 | <10 |
| 5 | 108.7 | SE1 | <10 |
| **AVERAGE** | **113.2** | | |
| STD. DEV. | 3.18 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 114.1 | SE1 | <10 |
| 2 | 113.2 | SE1 | <10 |
| 3 | 119.3 | SE1 | <10 |
| 4 | 114.0 | SE1 | <10 |
| 5 | 112.7 | SE1 | <10 |
| **AVERAGE** | **114.7** | | |
| STD. DEV. | 2.38 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 113.6 | SE1 |
| 2 | 133.4 | SE1 |
| 3 | 136.1 | SE1 |
| 4 | 132.2 | SE1 |
| 5 | 135.1 | SE1 |
| **AVERAGE** | **130.1** | |
| STD. DEV. | 8.35 | |

CHECKED BY: JO DATE: 8-11-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-22
LAB ID NO.: L15084-22-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-17**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 121.1 | SE1 | <10 |
| 2 | 121.9 | SE1 | <10 |
| 3 | 122.3 | SE1 | <10 |
| 4 | 122.4 | SE1 | <10 |
| 5 | 120.6 | SE1 | <10 |
| **AVERAGE** | **121.7** | | |
| STD. DEV. | 0.70 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.9 | SE1 | <10 |
| 2 | 116.0 | SE1 | <10 |
| 3 | 118.1 | SE1 | <10 |
| 4 | 123.6 | SE1 | <10 |
| 5 | 121.0 | SE1 | <10 |
| **AVERAGE** | **120.1** | | |
| STD. DEV. | 2.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 136.1 | SE1 |
| 2 | 136.1 | SE1 |
| 3 | 135.6 | SE1 |
| 4 | 138.7 | SE1 |
| 5 | 136.8 | SE1 |
| **AVERAGE** | **136.7** | |
| STD. DEV. | 1.09 | |

CHECKED BY: JO DATE: 8-14-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-22 L L15084-22-01 8/14/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-22
LAB ID NO.: L15084-22-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-18**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 112.6 | SE1 | <10 |
| 2 | 120.7 | SE1 | <10 |
| 3 | 118.2 | SE1 | <10 |
| 4 | 114.7 | SE1 | <10 |
| 5 | 116.6 | SE1 | <10 |
| **AVERAGE** | **116.6** | | |
| STD. DEV. | 2.79 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 110.3 | SE1 | <10 |
| 2 | 109.4 | SE1 | <10 |
| 3 | 113.4 | SE1 | <10 |
| 4 | 112.0 | SE1 | <10 |
| 5 | 114.1 | SE1 | <10 |
| **AVERAGE** | **111.8** | | |
| STD. DEV. | 1.78 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 138.8 | SE1 |
| 2 | 135.9 | SE1 |
| 3 | 133.9 | SE1 |
| 4 | 136.1 | SE1 |
| 5 | 136.7 | SE1 |
| **AVERAGE** | **136.3** | |
| STD. DEV. | 1.57 | |

CHECKED BY: JO DATE: 8-14-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-22
LAB ID NO.: L15084-22-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-19**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 114.6 | SE1 | <10 |
| 2 | 118.0 | SE1 | <10 |
| 3 | 113.7 | SE1 | <10 |
| 4 | 112.8 | SE1 | <10 |
| 5 | 112.9 | SE1 | <10 |
| **AVERAGE** | **114.4** | | |
| STD. DEV. | 1.91 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 118.1 | SE1 | <10 |
| 2 | 121.2 | SE1 | <10 |
| 3 | 117.2 | SE1 | <10 |
| 4 | 118.6 | SE1 | <10 |
| 5 | 119.1 | SE1 | <10 |
| **AVERAGE** | **118.8** | | |
| STD. DEV. | 1.34 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 138.1 | SE1 |
| 2 | 136.2 | SE1 |
| 3 | 133.6 | SE1 |
| 4 | 133.1 | SE1 |
| 5 | 133.9 | SE1 |
| **AVERAGE** | **135.0** | |
| STD. DEV. | 1.89 | |

CHECKED BY: JO DATE: 8-14-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-23
LAB ID NO.: L15084-23-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-20**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 119.6 | SE1 | <10 |
| 2 | 118.8 | SE1 | <10 |
| 3 | 114.7 | SE1 | <10 |
| 4 | 117.4 | SE1 | <10 |
| 5 | 116.3 | SE1 | <10 |
| **AVERAGE** | **117.4** | | |
| STD. DEV. | 1.75 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 112.7 | SE1 | <10 |
| 2 | 117.6 | SE1 | <10 |
| 3 | 116.1 | SE1 | <10 |
| 4 | 114.6 | SE1 | <10 |
| 5 | 113.8 | SE1 | <10 |
| **AVERAGE** | **115.0** | | |
| STD. DEV. | 1.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 140.9 | SE1 |
| 2 | 135.7 | SE1 |
| 3 | 140.4 | SE1 |
| 4 | 142.7 | SE1 |
| 5 | 141.4 | SE1 |
| **AVERAGE** | **140.2** | |
| STD. DEV. | 2.39 | |

CHECKED BY: NC DATE: 8/17/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-23
LAB ID NO.: L15084-23-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-21**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 117.8 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 113.2 | SE1 | <10 |
| 4 | 112.4 | SE1 | <10 |
| 5 | 112.1 | SE1 | <10 |
| **AVERAGE** | **114.8** | | |
| STD. DEV. | 2.77 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 112.3 | SE1 | <10 |
| 2 | 122.1 | SE1 | <10 |
| 3 | 120.0 | SE1 | <10 |
| 4 | 109.4 | SE1 | <10 |
| 5 | 112.0 | SE1 | <10 |
| **AVERAGE** | **115.2** | | |
| STD. DEV. | 4.96 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 145.9 | SE1 |
| 2 | 144.4 | SE1 |
| 3 | 147.2 | SE1 |
| 4 | 143.7 | SE1 |
| 5 | 142.9 | SE1 |
| **AVERAGE** | **144.8** | |
| STD. DEV. | 1.55 | |

CHECKED BY: NC DATE: 8/17/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-25
LAB ID NO.: L15084-25-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-22**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 120.0 | SE1 | <10 |
| 2 | 125.9 | SE1 | <10 |
| 3 | 118.4 | SE1 | <10 |
| 4 | 117.9 | SE1 | <10 |
| 5 | 118.2 | SE1 | <10 |
| **AVERAGE** | **120.1** | | |
| STD. DEV. | 3.00 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 125.9 | SE1 | <10 |
| 2 | 123.5 | SE1 | <10 |
| 3 | 118.4 | SE1 | <10 |
| 4 | 120.4 | SE1 | <10 |
| 5 | 120.1 | SE1 | <10 |
| **AVERAGE** | **121.7** | | |
| STD. DEV. | 2.68 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 137.9 | SE1 |
| 2 | 131.6 | SE1 |
| 3 | 134.7 | SE1 |
| 4 | 132.4 | SE1 |
| 5 | 133.5 | SE1 |
| **AVERAGE** | **134.0** | |
| STD. DEV. | 2.20 | |

CHECKED BY: JO DATE: 9-15-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-26
LAB ID NO.: L15084-26-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-23**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 108.9 | SE1 | <10 |
| 2 | 113.2 | SE1 | <10 |
| 3 | 109.4 | SE1 | <10 |
| 4 | 109.7 | SE1 | <10 |
| 5 | 113.9 | SE1 | <10 |
| **AVERAGE** | **111.0** | | |
| STD. DEV. | 2.09 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 118.3 | SE1 | <10 |
| 2 | 114.9 | SE1 | <10 |
| 3 | 109.3 | SE1 | <10 |
| 4 | 111.3 | SE1 | <10 |
| 5 | 122.0 | SE1 | <10 |
| **AVERAGE** | **115.2** | | |
| STD. DEV. | 4.60 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 128.5 | SE1 |
| 2 | 129.2 | SE1 |
| 3 | 129.7 | SE1 |
| 4 | 130.9 | SE1 |
| 5 | 129.5 | SE1 |
| **AVERAGE** | **129.6** | |
| STD. DEV. | 0.78 | |

CHECKED BY: JAM DATE: 9/16/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-28
LAB ID NO.: L15084-28-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-24**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 120.0 | SE1 | <10 |
| 2 | 118.2 | SE1 | <10 |
| 3 | 118.6 | SE1 | <10 |
| 4 | 120.2 | SE1 | <10 |
| 5 | 119.2 | SE1 | <10 |
| **AVERAGE** | **119.2** | | |
| STD. DEV. | 0.77 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 109.8 | SE1 | <10 |
| 2 | 112.1 | SE1 | <10 |
| 3 | 112.9 | SE1 | <10 |
| 4 | 115.4 | SE1 | <10 |
| 5 | 114.4 | SE1 | <10 |
| **AVERAGE** | **112.9** | | |
| STD. DEV. | 1.94 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 128.9 | SE1 |
| 2 | 132.4 | SE1 |
| 3 | 135.2 | SE1 |
| 4 | 135.0 | SE1 |
| 5 | 124.9 | SE1 |
| **AVERAGE** | **131.3** | |
| STD. DEV. | 3.92 | |

CHECKED BY: J.O DATE: 9-18-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-29
LAB ID NO.: L15084-29-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-25**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 117.6 | SE1 | <10 |
| 2 | 110.4 | SE1 | <10 |
| 3 | 117.8 | SE1 | <10 |
| 4 | 116.8 | SE1 | <10 |
| 5 | 118.4 | SE1 | <10 |
| **AVERAGE** | **116.2** | | |
| STD. DEV. | 2.94 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 119.6 | SE1 | <10 |
| 2 | 125.0 | SE1 | <10 |
| 3 | 120.3 | SE1 | <10 |
| 4 | 125.5 | SE1 | <10 |
| 5 | 126.9 | SE1 | <10 |
| **AVERAGE** | **123.5** | | |
| STD. DEV. | 2.94 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 129.9 | SE1 |
| 2 | 131.1 | SE1 |
| 3 | 135.5 | SE1 |
| 4 | 135.3 | SE1 |
| 5 | 134.2 | SE1 |
| **AVERAGE** | **133.2** | |
| STD. DEV. | 2.28 | |

CHECKED BY: JAC DATE: 9/21/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-29
LAB ID NO.: L15084-29-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-26**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 115.7 | SE1 | <10 |
| 2 | 115.5 | SE1 | <10 |
| 3 | 112.9 | SE1 | <10 |
| 4 | 117.9 | SE1 | <10 |
| 5 | 117.6 | SE1 | <10 |
| **AVERAGE** | **115.9** | | |
| STD. DEV. | 1.79 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 98.1 | SE1 | <10 |
| 2 | 99.5 | SE1 | <10 |
| 3 | 104.4 | SE1 | <10 |
| 4 | 101.9 | SE1 | <10 |
| 5 | 118.5 | SE1 | <10 |
| **AVERAGE** | **104.5** | | |
| STD. DEV. | 7.33 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 130.9 | SE1 |
| 2 | 126.7 | SE1 |
| 3 | 133.0 | SE1 |
| 4 | 126.4 | SE1 |
| 5 | 130.8 | SE1 |
| **AVERAGE** | **129.6** | |
| STD. DEV. | 2.58 | |

CHECKED BY: JAM DATE: 9/21/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-31
LAB ID NO.: L15084-31-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-27**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.1 | SE1 | <10 |
| 2 | 105.2 | SE1 | <10 |
| 3 | 109.7 | SE1 | <10 |
| 4 | 109.1 | SE1 | <10 |
| 5 | 108.5 | SE1 | <10 |
| **AVERAGE** | **108.7** | | |
| STD. DEV. | 1.96 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.6 | SE1 | <10 |
| 2 | 114.8 | SE1 | <10 |
| 3 | 120.1 | SE1 | <10 |
| 4 | 125.0 | SE1 | <10 |
| 5 | 121.6 | SE1 | <10 |
| **AVERAGE** | **120.6** | | |
| STD. DEV. | 3.32 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.0 | SE1 |
| 2 | 125.7 | SE1 |
| 3 | 127.8 | SE1 |
| 4 | 128.4 | SE1 |
| 5 | 132.1 | SE1 |
| **AVERAGE** | **128.0** | |
| STD. DEV. | 2.29 | |

CHECKED BY: JD DATE: 9-25-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-32
LAB ID NO.: L15084-32-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-28**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.1 | SE1 | <10 |
| 2 | 107.3 | SE1 | <10 |
| 3 | 111.3 | SE1 | <10 |
| 4 | 108.5 | SE1 | <10 |
| 5 | 108.7 | SE1 | <10 |
| **AVERAGE** | **109.4** | | |
| STD. DEV. | 1.57 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 112.3 | SE1 | <10 |
| 2 | 107.8 | SE1 | <10 |
| 3 | 109.9 | SE1 | <10 |
| 4 | 107.8 | SE1 | <10 |
| 5 | 123.9 | SE1 | <10 |
| **AVERAGE** | **112.3** | | |
| STD. DEV. | 6.01 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.8 | SE1 |
| 2 | 129.0 | SE1 |
| 3 | 129.7 | SE1 |
| 4 | 128.6 | SE1 |
| 5 | 134.3 | SE1 |
| **AVERAGE** | **130.9** | |
| STD. DEV. | 2.26 | |

CHECKED BY: JPK DATE: 10-8-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-32 L L15084-32-02 10/8/2015

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC.
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-34
LAB ID NO.: L15084-34-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: DOUBLE FUSION

**SAMPLE I.D.: DS-29**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| *OUTSIDE TRACK (WELD "A")* | | | |
| 1 | 111.4 | SE1 | <10 |
| 2 | 112.5 | SE1 | <10 |
| 3 | 115.4 | SE1 | <10 |
| 4 | 116.7 | SE1 | <10 |
| 5 | 119.3 | SE1 | <10 |
| **AVERAGE** | **115.1** | | |
| STD. DEV. | 2.85 | | |
| *INSIDE TRACK (WELD "B")* | | | |
| 1 | 121.1 | SE1 | <10 |
| 2 | 118.5 | SE1 | <10 |
| 3 | 115.5 | SE1 | <10 |
| 4 | 115.6 | SE1 | <10 |
| 5 | 120.3 | SE1 | <10 |
| **AVERAGE** | **118.2** | | |
| STD. DEV. | 2.32 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 129.5 | SE1 |
| 2 | 131.7 | SE1 |
| 3 | 131.7 | SE1 |
| 4 | 130.7 | SE1 |
| 5 | 132.1 | SE1 |
| **AVERAGE** | **131.1** | |
| STD. DEV. | 0.94 | |

CHECKED BY: JAM DATE: 10/12/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# *Langan – Fusion Weld Destruct Sample Laboratory Data*

Date: 2015-07-23

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17032** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17032**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-2 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 138 | 142 | 138 | 140 | 134 | **138** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 139 | 143 | 140 | 138 | 134 | **139** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 139 | 146 | 143 | 147 | 145 | **144** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-08-04

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

e-mail:dbosworth@langan.com

**Bill To:**

**Langan Environmental Services**
**100530001**

Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17198** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Melissa Hunter
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17198**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-10 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 121 | 121 | 124 | 123 | 122 | **122** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 121 | 118 | 120 | 117 | 125 | **120** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 134 | 133 | 134 | 129 | 130 | **132** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-08-27

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17632** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17632**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-21 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 113 | 115 | 114 | 116 | 115 | **115** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 120 | 119 | 122 | 130 | 128 | **124** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 142 | 147 | 145 | 142 | 144 | **144** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-10-14

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **18404** |
| Material(s) Tested: | (1) Heat Fusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS
## TRI Client: Langan Environmental Services
## Project: Honeywell SA-6 South Capping

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 18404**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DS-29 \| Weld: Heat Fusion** | | | | | | |
| **Side: A** | | | | | | **Peel A** |
| Peel Strength (ppi) | 111 | 112 | 110 | 112 | 114 | **112** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Side: B** | | | | | | **Peel B** |
| Peel Strength (ppi) | 113 | 124 | 111 | 121 | 115 | **117** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 138 | 140 | 140 | 138 | 138 | **139** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

# *Entact / ESI – Extrusion Weld Destruct Sample Laboratory Data*

# Honeywell SA-6 Capping

## *Comparison of ESI / Langan (QA) Destruct Samples - Extrusion Welds*

| ***Sample ID*** | ***Weld Type*** | ***Submitted By:*** | ***Test*** | ***Peel Strength (ppi)*** | | | | | **Avg. Strength (ppi)** | ***Meets Spec Requirement*** |
|---|---|---|---|---|---|---|---|---|---|---|
| EXT-DS-1 | Extrusion | Langan | Peel | 97 | 97 | 127 | 130 | 128 | **116** | **Yes** |
| DSX-1 | | Entact | Peel | 109.3 | 107.5 | 109.8 | 120.5 | 110 | **111.4** | **Yes** |
| EXT-DS-1 | | Langan | Shear | 133 | 172 | 148 | 181 | 146 | **156** | **Yes** |
| DSX-1 | | Entact | Shear | 115.7 | 119.8 | 118.1 | 117.5 | 116.2 | **117.5** | **Yes** |
| DSX-2 | Extrusion | Entact | Peel | 133.5 | 118.8 | 126.4 | 120.1 | 115.4 | **122.8** | **Yes** |
| | | | Shear | 132.7 | 150.3 | 145.5 | 135.4 | 130.3 | **138.8** | **Yes** |
| DSX-3 | Extrusion | Entact | Peel | 123.7 | 117.2 | 117.9 | 119.1 | 120.2 | **119.6** | **Yes** |
| | | | Shear | 126 | 128.6 | 125.1 | 124.5 | 125.1 | **125.9** | **Yes** |
| DSX-4 | Extrusion | Entact | Peel | 128.4 | 132.1 | 133.5 | 134.4 | 139.5 | **133.6** | **Yes** |
| | | | Shear | 144.7 | 143.7 | 141.8 | 150.7 | 145.7 | **145.3** | **Yes** |
| DSX-5 | Extrusion | Entact | Peel | 107.5 | 115.8 | 111.6 | 113.9 | 119.3 | **113.6** | **Yes** |
| | | | Shear | 131.7 | 136.9 | 151.8 | 137 | 149.5 | **141.4** | **Yes** |
| DSX-6 | Extrusion | Entact | Peel | 151.4 | 144.8 | 130.9 | 139.9 | 150.1 | **143.4** | **Yes** |
| | | | Shear | 164.9 | 162.3 | 151.5 | 155.6 | 159.7 | **158.8** | **Yes** |
| DSX-7 | Extrusion | Entact | Peel | 123.7 | 126.8 | 128.7 | 122.2 | 120.7 | **124.4** | **Yes** |
| | | | Shear | 134.6 | 133.7 | 134.8 | 136.2 | 135.5 | **135.0** | **Yes** |
| DSX-8 | Extrusion | Entact | Peel | 129.6 | 119.5 | 124.3 | 130.9 | 120 | **124.9** | **Yes** |
| | | | Shear | 131.6 | 130.7 | 129.7 | 134.4 | 127.8 | **130.8** | **Yes** |
| DSX-9 | Extrusion | Entact | Peel | 108.7 | 124.4 | 120.8 | 112 | 111.6 | **115.5** | **Yes** |
| | | | Shear | 132.8 | 126.8 | 133.9 | 116.1 | 122.8 | **126.5** | **Yes** |
| DSX-10 | Extrusion | Entact | Peel | 118.7 | 122.1 | 118.1 | 120.8 | 136.1 | **123.2** | **Yes** |
| | | | Shear | 123 | 145.2 | 149.5 | 130.7 | 145.6 | **138.8** | **Yes** |
| DSX-11 | Extrusion | Langan | Peel | 125 | 134 | 123 | 121 | 124 | **125** | **Yes** |
| | | Entact | Peel | 125.1 | 118.2 | 125.9 | 123.3 | 120.6 | **122.6** | **Yes** |
| | | Langan | Shear | 164 | 157 | 141 | 137 | 142 | **148** | **Yes** |
| | | Entact | Shear | 122.6 | 124.6 | 126.1 | 127.9 | 128.2 | **125.9** | **Yes** |
| DSX-12 | Extrusion | Entact | Peel | 130.4 | 121.3 | 148.4 | 118.2 | 138.9 | **131.4** | **Yes** |
| | | | Shear | 126.2 | 123.7 | 125 | 124.2 | 122.7 | **124.4** | **Yes** |
| DSX-13 | Extrusion | Entact | Peel | 117 | 97.9 | 123.5 | 66 | 55.6 | **92.0** | **No** |
| | | | Shear | 131.2 | 129 | 133 | 132.9 | 124.6 | **130.1** | **Yes** |
| DSX-14 | Extrusion | Entact | Peel | 119 | 119.7 | 118.8 | 123.3 | 122.6 | **120.7** | **Yes** |
| | | | Shear | 120.9 | 121.4 | 121.7 | 129.5 | 127.4 | **124.2** | **Yes** |
| DSX-15 | Extrusion | Entact | Peel | 119.5 | 114.1 | 123.8 | 111.4 | 106.8 | **115.1** | **Yes** |
| | | | Shear | 132.1 | 135.2 | 138.5 | 137.4 | 141.7 | **137.0** | **Yes** |

You created this PDF from an application that is not licensed to print to novaPDF printer (http://www.novapdf.com)

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-12
LAB ID NO.: L15084-12-01
MATERIAL: 60 MIL HDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-1**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 109.3 | SE3 | <10 |
| 2 | 107.5 | SE3 | <10 |
| 3 | 109.8 | SE3 | <10 |
| 4 | 120.5 | SE3 | <10 |
| 5 | 110.0 | SE3 | <10 |
| **AVERAGE** | **111.4** | | |
| STD. DEV. | 4.62 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 115.7 | SE1 |
| 2 | 119.8 | SE1 |
| 3 | 118.1 | SE1 |
| 4 | 117.5 | SE1 |
| 5 | 116.2 | SE1 |
| **AVERAGE** | **117.5** | |
| STD. DEV. | 1.45 | |

CHECKED BY: JO DATE: 7-27-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-13
LAB ID NO.: L15084-13-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-2**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| 1 | 133.5 | SE3 | <10 |
| 2 | 118.8 | SE3 | <10 |
| 3 | 126.4 | SE3 | <10 |
| 4 | 120.1 | SE3 | <10 |
| 5 | 115.4 | SE3 | <10 |
| **AVERAGE** | **122.8** | | |
| STD. DEV. | 6.41 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.7 | SE2 |
| 2 | 150.3 | SE1 |
| 3 | 145.5 | SE1 |
| 4 | 135.4 | SE1 |
| 5 | 130.3 | SE2 |
| **AVERAGE** | **138.8** | |
| STD. DEV. | 7.72 | |

CHECKED BY: NC DATE: 7/28/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-15
LAB ID NO.: L15084-15-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-3**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 123.7 | SE3 | <10 |
| 2 | 117.2 | SE3 | <10 |
| 3 | 117.9 | SE3 | <10 |
| 4 | 119.1 | SE3 | <10 |
| 5 | 120.2 | SE3 | <10 |
| **AVERAGE** | **119.6** | | |
| STD. DEV. | 2.28 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.0 | SE1 |
| 2 | 128.6 | SE1 |
| 3 | 125.1 | SE1 |
| 4 | 124.5 | SE1 |
| 5 | 125.1 | SE1 |
| **AVERAGE** | **125.9** | |
| STD. DEV. | 1.45 | |

CHECKED BY: JO DATE: 7-30-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-16
LAB ID NO.: L15084-16-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-4**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 128.4 | SE3 | <10 |
| 2 | 132.1 | SE3 | <10 |
| 3 | 133.5 | SE3 | <10 |
| 4 | 134.4 | SE3 | <10 |
| 5 | 139.5 | SE3 | <10 |
| **AVERAGE** | **133.6** | | |
| STD. DEV. | 3.60 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 144.7 | SE1 |
| 2 | 143.7 | SE1 |
| 3 | 141.8 | SE1 |
| 4 | 150.7 | SE1 |
| 5 | 145.7 | SE1 |
| **AVERAGE** | **145.3** | |
| STD. DEV. | 2.98 | |

CHECKED BY: JO DATE: 7-31-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-19
LAB ID NO.: L15084-19-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-5**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 107.5 | SE2 | <10 |
| 2 | 115.8 | SE2 | <10 |
| 3 | 111.6 | SE2 | <10 |
| 4 | 113.9 | SE2 | <10 |
| 5 | 119.3 | SE2 | <10 |
| **AVERAGE** | **113.6** | | |
| STD. DEV. | 3.97 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.7 | SE1 |
| 2 | 136.9 | SE1 |
| 3 | 151.8 | SE1 |
| 4 | 137.0 | SE1 |
| 5 | 149.5 | SE1 |
| **AVERAGE** | **141.4** | |
| STD. DEV. | 7.84 | |

CHECKED BY: JO DATE: 8-6-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-20
LAB ID NO.: L15084-20-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-6**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 151.4 | SE3 | <10 |
| 2 | 144.8 | SE3 | <10 |
| 3 | 130.9 | SE3 | <10 |
| 4 | 139.9 | SE3 | <10 |
| 5 | 150.1 | SE3 | <10 |
| **AVERAGE** | **143.4** | | |
| STD. DEV. | 7.47 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 164.9 | SE1 |
| 2 | 162.3 | SE1 |
| 3 | 151.5 | SE1 |
| 4 | 155.6 | SE1 |
| 5 | 159.7 | SE1 |
| **AVERAGE** | **158.8** | |
| STD. DEV. | 4.77 | |

CHECKED BY: JO DATE: 8-10-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-21
LAB ID NO.: L15084-21-03
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-7**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 123.7 | SE3 | <10 |
| 2 | 126.8 | SE3 | <10 |
| 3 | 128.7 | SE3 | <10 |
| 4 | 122.2 | SE3 | <10 |
| 5 | 120.7 | SE3 | <10 |
| **AVERAGE** | **124.4** | | |
| STD. DEV. | 2.94 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 134.6 | SE1 |
| 2 | 133.7 | SE1 |
| 3 | 134.8 | SE1 |
| 4 | 136.2 | SE1 |
| 5 | 135.5 | SE1 |
| **AVERAGE** | **135.0** | |
| STD. DEV. | 0.85 | |

CHECKED BY: JO DATE: 8-11-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-21 D L15084-21-03 8/11/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-24
LAB ID NO.: L15084-24-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-8**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 129.6 | SE3 | <10 |
| 2 | 119.5 | SE3 | <10 |
| 3 | 124.3 | SE3 | <10 |
| 4 | 130.9 | SE3 | <10 |
| 5 | 120.0 | SE3 | <10 |
| **AVERAGE** | **124.9** | | |
| STD. DEV. | 4.72 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.6 | SE1 |
| 2 | 130.7 | SE1 |
| 3 | 129.7 | SE1 |
| 4 | 134.4 | SE1 |
| 5 | 127.8 | SE1 |
| **AVERAGE** | **130.8** | |
| STD. DEV. | 2.18 | |

CHECKED BY: JO DATE: 9-11-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING

ASTM D 6392

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-27
LAB ID NO.: L15084-27-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-9**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 108.7 | SE3 | <10 |
| 2 | 124.4 | SE3 | <10 |
| 3 | 120.8 | SE3 | <10 |
| 4 | 112.0 | SE3 | <10 |
| 5 | 111.6 | SE3 | <10 |
| **AVERAGE** | **115.5** | | |
| STD. DEV. | 6.02 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.8 | SE1 |
| 2 | 126.8 | SE1 |
| 3 | 133.9 | SE1 |
| 4 | 116.1 | SE1 |
| 5 | 122.8 | SE1 |
| **AVERAGE** | **126.5** | |
| STD. DEV. | 6.58 | |

CHECKED BY: JAN DATE: 9/17/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

## PEEL AND SHEAR TEST RESULTS
## DESTRUCTIVE SEAM TESTING
**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-30
LAB ID NO.: L15084-30-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-10**

### PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 118.7 | SE3 | <10 |
| 2 | 122.1 | SE3 | <10 |
| 3 | 118.1 | SE3 | <10 |
| 4 | 120.8 | SE3 | <10 |
| 5 | 136.1 | SE3 | <10 |
| **AVERAGE** | **123.2** | | |
| STD. DEV. | 6.63 | | |

### BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 123.0 | SE1 |
| 2 | 145.2 | SE1 |
| 3 | 149.5 | SE1 |
| 4 | 130.7 | SE1 |
| 5 | 145.6 | SE1 |
| **AVERAGE** | **138.8** | |
| STD. DEV. | 10.17 | |

CHECKED BY: JO DATE: 9-22-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-27 D L15084-30-01 9/22/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

Geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-31
LAB ID NO.: L15084-31-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-11**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 125.1 | SE3 | <10 |
| 2 | 118.2 | SE3 | <10 |
| 3 | 125.9 | SE3 | <10 |
| 4 | 123.3 | SE3 | <10 |
| 5 | 120.6 | SE3 | <10 |
| **AVERAGE** | **122.6** | | |
| STD. DEV. | 2.86 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 122.6 | SE1 |
| 2 | 124.6 | SE1 |
| 3 | 126.1 | SE1 |
| 4 | 127.9 | SE1 |
| 5 | 128.2 | SE1 |
| **AVERAGE** | **125.9** | |
| STD. DEV. | 2.09 | |

CHECKED BY: JO DATE: 9-25-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-31 D L15084-31-01 9/25/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-32
LAB ID NO.: L15084-32-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-12**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 130.4 | SE3 | <10 |
| 2 | 121.3 | SE3 | <10 |
| 3 | 148.4 | SE3 | <10 |
| 4 | 118.2 | SE3 | <10 |
| 5 | 138.9 | SE3 | <10 |
| **AVERAGE** | **131.4** | | |
| STD. DEV. | 11.16 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 126.2 | SE1 |
| 2 | 123.7 | SE1 |
| 3 | 125.0 | SE1 |
| 4 | 124.2 | SE1 |
| 5 | 122.7 | SE1 |
| **AVERAGE** | **124.4** | |
| STD. DEV. | 1.18 | |

CHECKED BY: JDK DATE: 10-8-15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-32 D L15084-32-01 10/8/2015

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-34
LAB ID NO.: L15084-34-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-13**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| 1 | 117.0 | SE2 | <10 |
| 2 | 97.9 | SE2 | <10 |
| 3 | 123.5 | SE2 | <10 |
| 4 | 66.0 | AD1 | 100 |
| 5 | 55.6 | AD1 | 100 |
| **AVERAGE** | **92.0** | | |
| STD. DEV. | 27.04 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 131.2 | SE1 |
| 2 | 129.0 | SE1 |
| 3 | 133.0 | SE1 |
| 4 | 132.9 | SE1 |
| 5 | 124.6 | SE1 |
| **AVERAGE** | **130.1** | |
| STD. DEV. | 3.13 | |

CHECKED BY: JAM DATE: 10/12/15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-34
LAB ID NO.: L15084-34-02
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-14**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 119.0 | SE2 | <10 |
| 2 | 119.7 | SE2 | <10 |
| 3 | 118.8 | SE2 | <10 |
| 4 | 123.3 | SE2 | <10 |
| 5 | 122.6 | SE2 | <10 |
| **AVERAGE** | **120.7** | | |
| STD. DEV. | 1.89 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 120.9 | SE1 |
| 2 | 121.4 | SE1 |
| 3 | 121.7 | SE1 |
| 4 | 129.5 | SE1 |
| 5 | 127.4 | SE1 |
| **AVERAGE** | **124.2** | |
| STD. DEV. | 3.56 | |

CHECKED BY: JAM DATE: 10/12/15

C:\Excel\Templates\[HDP&S-DFusion.xls]Sheet1

\\geoserver\Data Drive\Synthetics\2015 SYNTHETICS\084 - ENTACT - HONEYWELL SA6 NORTH & SOUTH CAPS\[L15084-34 D L15084-34-02 10/12/15

# PEEL AND SHEAR TEST RESULTS
# DESTRUCTIVE SEAM TESTING

**ASTM D 6392**

geotechnics
INTEGRITY IN TESTING

CLIENT: ENTACT, LLC
CLIENT PROJECT: HONEYWELL SA6 NORTH & SOUTH CAPS
PROJECT NO.: L15084-35
LAB ID NO.: L15084-35-01
MATERIAL: 60 MIL LLDPE
SEAM TYPE: EXTRUSION

**SAMPLE I.D.: DSX-15**

## PEEL ADHESION

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE | PEEL INCURSION (%) |
|---|---|---|---|
| | | | |
| 1 | 119.5 | SE2 | <10 |
| 2 | 114.1 | SE2 | <10 |
| 3 | 123.8 | SE2 | <10 |
| 4 | 111.4 | SE2 | <10 |
| 5 | 106.8 | SE2 | <10 |
| **AVERAGE** | **115.1** | | |
| STD. DEV. | 5.98 | | |

## BONDED SEAM (SHEAR) STRENGTH

| REPLICATE No. | PEAK LOAD (lbs/in) | EPA BREAK CLASSIFICATION CODE |
|---|---|---|
| 1 | 132.1 | SE1 |
| 2 | 135.2 | SE1 |
| 3 | 138.5 | SE1 |
| 4 | 137.4 | SE1 |
| 5 | 141.7 | SE1 |
| **AVERAGE** | **137.0** | |
| STD. DEV. | 3.22 | |

CHECKED BY: JDK DATE: 10-13-15



544 Braddock Avenue • East Pittsburgh, PA 15112 • 412-823-7600 • FAX 412-823-8999 • www.geotechnics.net

# *Langan – Extrusion Weld Destruct Sample Laboratory Data*

Date: 2015-07-28

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

e-mail:dbosworth@langan.com

**Bill To:**

**Langan Environmental Services**
**100530001**


Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **17111** |
| Material(s) Tested: | (1) Single Extrusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,



Jennifer Tenney
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS - SINGLE TRACK
**TRI Client: Langan Environmental Services**
**Project: Honeywell SA-6 South Capping**

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 17111**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: EXT DS-1 \| Weld: Single Extrusion** | | | | | | |
| **Side: Peel** | | | | | | **Peel** |
| Peel Strength (ppi) | 97 | 97 | 127 | 130 | 128 | **116** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 133 | 172 | 148 | 181 | 146 | **156** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

Date: 2015-10-05

**Mail To:**
**Dan Bosworth**
**Langan Environmental Services**
**619 River Drive**
**Elmwood Park , NJ , 07090**

**Bill To:**

**Langan Environmental Services**
**100530001**

e-mail:dbosworth@langan.com

Dear Mr. Bosworth,

Thank you for consulting with TRI/Environmental, Inc. (TRI) for your geosynthetics testing needs. TRI is pleased to submit this final report for laboratory testing.

| | |
|---|---|
| **Project:** | **Honeywell SA-6 South Capping** |
| TRI Job Reference Number: | **18270** |
| Material(s) Tested: | (1) Single Extrusion Weld Seam(s) |
| Test(s) Requested: | SAME DAY Peel and Shear<br>(ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.) |

| Codes: | |
|---|---|
| AD | Adhesion Failure (100% Peel) |
| BRK | Break in sheeting away from Seam edge. |
| SE | Break in sheeting at edge of seam. |
| AD-BRK | Break in sheeting after some adhesion failure - partial peel. |
| SIP | Separation in the plane of the sheet (leaving the bond intact). |
| FTB | Film tearing bond (all non "AD" failures). |
| NON-FTB | 100% peel. |

If you have any questions or require any additional information, please call us at 1-800-880-8378.
Sincerely,

Melissa Hunter

Melissa Hunter
Project Manager
Geosynthetic Services Division
http://www.geosyntheticstestinc.com

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

## DESTRUCTIVE SEAM QUALITY ASSURANCE TEST RESULTS - SINGLE TRACK
**TRI Client: Langan Environmental Services**
**Project: Honeywell SA-6 South Capping**

**Material: 60 mil. LLDPE**
**SAME DAY Peel and Shear (ASTM D 6392/GRI GM19/D 4437/NSF 54/882 mod.)**
**TRI Log#: 18270**

| | TEST REPLICATE NUMBER | | | | | |
|---|---|---|---|---|---|---|
| PARAMETER | 1 | 2 | 3 | 4 | 5 | MEAN |
| **Sample ID: DSX-11 \| Weld: Single Extrusion** | | | | | | |
| **Side: Peel** | | | | | | **Peel** |
| Peel Strength (ppi) | 125 | 134 | 123 | 121 | 124 | **125** |
| Peel Incursion (%) | <5 | <5 | <5 | <5 | <5 | |
| Peel Locus Of Failure Code | SE | SE | SE | SE | SE | |
| Peel NSF Failure Code | FTB | FTB | FTB | FTB | FTB | |
| **Shear** | | | | | | **Shear** |
| Shear Strength (ppi) | 164 | 157 | 141 | 137 | 142 | **148** |
| Shear Elongation @ Break (%) | >50 | >50 | >50 | >50 | >50 | |


The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.


# Appendix O
# Penetration & Pipe Boot Logs

**Project:** Study Area 6 South

**Date:** 7/22/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 073-MW-1BR located at western end of SA-6 Cap on Panel 1/2 seam (approx. 135 ft. north of south end of Cap). Identified as RP-6 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/21/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 9/25/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 115-E1A-SO located in proximity to northern boundary of SA-6 Cap on Panel #111 / 112 (approx. 15 ft. south of north end of Cap). Identified as RP-419 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing conducted on 9/24/15. Final butyl sealant applied at completion of project on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 7/23/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 115-W3-SO located along northern slope of SA-6 Cap on Panel #8 (approx. 147 ft. north of south end of Cap). Identified as RP-14 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BSilva 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/22/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 8/13/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Well 115-W5-SO located in proximity to northern boundary of SA-6 Cap on Panel #61 62 (approx. 135 ft. north of south end of Cap). Identified as RP-246 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing conducted on 8/12/15. Final butyl sealant applied at completion of project on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 10/09/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-0 located at approximate center of SA-6 Cap on Panel #125 (approximately 68 ft. south of north end of cap). Identified as RP-457 on *As Built* and *Repair Report*

**AmecFW QA Signature:** BShea 10/9/15

**Independent CQA Monitor Signature:** 10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 10/9/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 10/09/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-1 located at approximate center of SA-6 Cap on Panel #114 / 115 seam. Identified as RP-425 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 10/8/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/22/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-2 located at approximate center of SA-6 Cap on Panel #95. Identified as RP-369 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/21/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/15/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-3 located at approximate center of SA-6 Cap on Panel #74 (along Panel #73/74 seam). Identified as RP-257 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/14/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 9/14/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-4 located at approximate center of SA-6 Cap on Panel #58. Identified as RP-243 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BSlwg 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/11/15. Final butyl sealant applied at completion of project on 10/9/15

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 8/13/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-5 located at approximate center of SA-6 Cap on Panel #38 (approx. 3 ft. west of Panel 37/38/42 joint). Identified as RP-219 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/12/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell


**STUDY AREA 6 - CAP INSTALLATION**

LANGAN

| **Project:** Study Area 6 South | **Date:** 8/6/2015 |
|---|---|

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-6 located at approximate center of SA-6 Cap on Panel #25 (approx. 74 ft. south of north end of Cap). Identified as RP-188 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/5/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 7/30/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Gas Vent GV-7 located at approximate center of SA-6 Cap on Panel #11 (approx. 80 ft. north of south end of Cap). Identified as RP-129 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

B.Shea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/29/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 10/9/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-12 located along eastern end of SA-6 (approx. 81 ft. north of south end of Cap). Identified as RP-476 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 10/8/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 9/24/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-14 located along southern edge of SA-6 Cap on Panel #109 (approx. 152 ft. south of north end of Cap). Identified as RP-418 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 9/23/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


STUDY AREA 6 - CAP INSTALLATION


LANGAN

**Project:** Study Area 6 South

**Date:** 8/17/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-16 located along southern edge of SA-6 Cap on Panel #71 (approx. 9 ft. north of south end of Cap). Identified as RP-255 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/14/15. Final butyl sealant applied at project completion on 10/9/15.

Honeywell


**STUDY AREA 6 - CAP INSTALLATION**


LANGAN

**Project:** Study Area 6 South

**Date:** 7/31/2015

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-18 located along southern edge of SA-6 Cap on Panel #31/32 seam (approx. 13 ft. north of south end of Cap). Identified as RP-132 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/30/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell


**STUDY AREA 6 - CAP INSTALLATION**

LANGAN

| **Project:** Study Area 6 South | **Date:** 7/22/2015 |
|---|---|

## QA – Gas Vent and Piezometer Penetrations




***Check applicable Detail:**

- ☒ Fabricated in field
- ☒ 18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ If penetration is greater than 4-in. in diameter, a second clamp shall be used.
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded
- ☒ LLDPE telescoping sleeve placed around boot
- ☒ Caulked Butyl Sealant around top edge of liner

**Location:** Piezometer PZ-20 located at western end of SA-6 Cap on Panel 1 seam (approx. 85 ft. north of south end of Cap). Identified as RP-7 on *As Built* and *Repair Report*

**AmecFW QA Signature:**

BShea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/21/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 7/27/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE

NTS

CE TYP C--304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #1 located on Panel #16 (P-16) at approximate Sta. 19+25 (SCB Wall Sta. Numbering). Identified as RP-24 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Monitor Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 7/24/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 8/11/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE

NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #2 located on Panel #47 (P-47) at approximate Sta. 14+00 (SCB Wall Sta. Numbering). Identified as RP-218 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B.Shea 10/9/15

**Independent CQA Signature:**

10/9/15

**Comments:** Geomembrane boot fabrication, construction, welding, and testing completed on 8/10/15. Final butyl sealant applied at project completion on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 9/15/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE

NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #3 located on Panel #75/78/79 seams (western slope of 2nd utility corridor). Identified as RP-262 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B Shea 10/9/15

**Independent CQA Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/14/15. Final butyl sealant applied at completion of project on 10/9/15.


Honeywell

**STUDY AREA 6 - CAP INSTALLATION**

**Project:** Study Area 6 South

**Date:** 9/25/2015

## QA – Manhole Boot Installation




LINER ANCHOR TO CONCRETE STRUCTURE
NTS

CE TYP C-304

***Check applicable Detail:**

- ☒ Fabricated in field
- ☒18-in. overlap between boot and geomembrane
- ☒ Neoprene rubber gasket and/or silicone caulking shall be used between the boot or shroud and the penetration structure
- ☒ LLDPE sacrificial sheet shall be used between the boot or shroud and the clamp for protection
- ☒ SS Band Clamps tightened and uniform
- ☒ Caulked Butyl Sealant around top edge of liner
- ☒ Boot connection (minimum 18-inch overlap) field tested to ensure seal (ex. vacuum box testing) and observed boot vertical seam and penetration edges extrusion welded

**Location:** Access Manhole #4 located on Panel #113 (approximate center of SA-6), approximately 82 ft. south of north end of Cap. Identified as RP-420 on *As-Built* and *Repair Log*

**AmecFW QA Signature:**

B.Shea 10/9/15

**Independent CQA Signature:**

10/9/15

**Comments:** Boot fabrication, construction, welding, and testing completed on 9/24/15. Final butyl sealant applied at completion of project on 10/9/15.

# Appendix P
# Summary of Non-Compliance & Corrective Action Sheets

**LANGAN**

## Notice of Non-Compliance and Corrective Action

Sheet # 1

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/21/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 1<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #3 (P-3). This non-compliance issue is also noted on the 7/21/15 Repair Report, and is identified as RP-3. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 2 ft. by 2.5 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to Photo #5 of 7/21/15 photo log for repair of RP-3.

Geosynthetic Installer Representative Carolina Ramos Date 7-21-15

Independent CQA Monitor [signature] Date 7-21-15

**LANGAN**

# Notice of Non-Compliance and Corrective Action

Sheet # 2

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/21/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 2<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |
| **Description of Non-Compliance** | |
| *Cross Reference (QA Inspection Form & Sheet No.):*<br>Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #2 (P-2). This non-compliance issue is also noted on the 7/21/15 Repair Report, and is identified as RP-8. The location of this repair was recorded and logged (via GPS) by the team. | |
| **Contractor's Response** | |
| Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair. | |
| **Follow Up Action Required** | |
| Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response. | |
| **Follow Up Action Taken** | |
| *Cross Reference (QA Inspection Form & Sheet No.):*<br>Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 1.5 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). | |

Geosynthetic Installer Representative Carolina Parris Date 7-21-15

Independent CQA Monitor Date 7-21-15

**LANGAN**

# Notice of Non-Compliance and Corrective Action

Sheet # 3

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/22/15<br>Contractor in NC: ESI / Entact<br>Non-Compliance No.: 3<br>Notes: Non-Destructive Test |
| **Reference** | |
| Item: Non-Destructive Test Failure<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Failure of Non-Destructive Test along Panel seams 7/8 (located on southern end of SA-6). This non-compliance issue is also noted on the 7/22/15 Repair Report, and is identified as RP-13. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Failure of panel seam 7/8 during non-destructive testing confirmed. Based on length of failed seam (approximately 6 ft.), the entire seam length will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Based on length of seam to be repaired the area will be patched and sealed with extrusion welds following the project specifications and as outlined in the Contractor's Response above.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Based on length of failed seam (approximately 6 ft.), the entire seam was patched and repaired. This failure was repaired with approximate 2 ft. by 6 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolina Garcia Date 7-22-15

Independent CQA Monitor Date 7-22-15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 4

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 7/24/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 10<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #17 (P-17). This non-compliance issue is also noted on the 7/24/15 Repair Report, and is identified as RP-30. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 2 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolina Ramos Date 7/27/15

Independent CQA Monitor Date 7/27/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 5

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 8/7/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 5<br>Notes: Vacuum Box Test |
| **Reference** | |
| Item: Vacuum Box Test Failure<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Failed vacuum box test (i.e. leak) detected during vacuum box testing of RP-215 at Panel #50 (P-50). This non-compliance issue is also noted on the 8/7/15 Repair Report, and is identified as a failed test result ("F") for RP-215. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Failed vacuum box test for RP-215 identified and confirmed. Failed weld to be patched and welded according to project specifications, and confirmed via vacuum test.

**Follow Up Action Required**

Patch / repair failed weld with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Failed extrusion weld (identified during vacuum box testing) was patched with an approximate 2 ft. by 2 ft. geomembrane patch over the extrusion weld (Noted as RP-222 on Repair Log). The patch was overlapped a minimum of 4-inches beyond the edges of the failed weld, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to Photos 3,7 of the 8/10/15 Photo Log for supporting photographs.

Geosynthetic Installer Representative Carolina Parra Date 8/10/15

Independent CQA Monitor Date 8/10/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 6

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 9/11/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 6<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #57 (P-57). This non-compliance issue is also noted on the 9/11/15 Repair Report, and is identified as RP-293. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 1.5 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolyn Parnell Date 9/14/15

Independent CQA Monitor Date 9/14/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 7

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 9/16/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 7<br>Notes: Subgrade Irregularity |
| **Reference** | |
| Item: Subgrade Irregularity – Hydrated GCL<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane panel cut to expose underlying geosynthetic clay liner (GCL). GCL wet / hydrated from weekend storms. Ground surface elevation outside of the SA-6 cap (along southern end of SA-6) was higher than cap grades which caused surface water to flow towards the cap during a major rain event. Rainwater able to pool / pond and infiltrate underneath geomembrane panels thus hydrating GCL. This non-compliance issue is also noted on the 9/16/15 Repair Report, and is identified as RP-331. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Hydrated GCL confirmed as subgrade irregularity. GCL to be cut (where hydrated), removed, and replaced and the geomembrane will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove hydrated GCL from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane cap was cut and GCL was exposed. Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. The cut in the geomembrane was then repaired with approximate 2 ft. by 18 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to Photos #2 and #3 of 9/16/15 photo log for placement of new GCL

Geosynthetic Installer Representative Carolina Ramos Date 9/17/15

INDEPENDENT CQA MONITOR [signature] Date 9/17/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 8

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 9/24/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 8<br>Notes: Soil Subgrade |
| **Reference** | |
| Item: Soil Subgrade<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock / loose debris (>1/2 – inches) observed underneath geomembrane cap at Panel #111 (P-111). This non-compliance issue is also noted on the 9/24/15 Repair Report, and is identified as RP-423. The location of this repair was recorded and logged (via GPS) by the team.

**Contractor's Response**

Loose debris / rock area identified as subgrade irregularity. Rock to be removed and the area will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove rock / debris from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Rock was removed from underneath geomembrane as a small hole (<2-inches) was made in the cap to remove the stone. This hole was then repaired with approximate 1.5 ft. by 2 ft. geomembrane patch. The patch was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372).

Geosynthetic Installer Representative Carolina Ramos Date 9/25/15

Independent CQA Monitor Date 9/25/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 9

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 10/7/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 9<br>Notes: Subgrade Irregularity |
| **Reference** | |
| Item: Subgrade Irregularity – Hydrated GCL<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane Panels #121-125 (southern end of SA-6 within swale) cut to expose underlying geosynthetic clay liner (GCL). GCL wet / hydrated from weekend storms. Ground surface elevation outside of the SA-6 cap (along southern end of SA-6) was higher than cap grades which caused surface water to flow towards the cap during a major rain event. Rainwater able to pool / pond and infiltrate underneath geomembrane panels from failure of pump during storms thus hydrating GCL along the southern end of SA-6. This non-compliance issue is also noted on the 10/7/15 Repair Report, and is identified as the following repairs (RP-458 through RP-473). The location of these repairs were recorded and logged (via GPS) by the team (southern swale of SA-6).

**Contractor's Response**

Hydrated GCL confirmed as subgrade irregularity. GCL to be cut (where hydrated), removed, and replaced and the geomembrane will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove hydrated GCL from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane cap was cut and GCL was exposed (southern swale of SA-6). Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. Various cuts in the geomembrane were then repaired. Patches were overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to *10/7/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carolina Ramos Date 10/8/15

Independent CQA Monitor [signature] Date 10/8/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 10

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 10/7/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 10<br>Notes: Subgrade Irregularity |
| **Reference** | |
| Item: Subgrade Irregularity – Hydrated GCL<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane Panels #117 and Panel #119/120 (northern end of SA-6 along SCB wall) cut to expose underlying geosynthetic clay liner (GCL). GCL wet / hydrated from weekend storms. Ground surface elevation outside of the SA-6 cap (along northern end of SA-6) was higher than cap grades which caused surface water to flow towards the cap during a major rain event. Rainwater and wash out along adjacent roadway (higher elevation) along northern end of SA-6 (SCB wall) able to infiltrate laterally and hydrate GCL. This non-compliance issue is also noted on the 10/7/15 Repair Report, and is identified as RP-474 and RP-475 (two cuts along geomembrane to fold back geomembrane cap). The location of these repairs were recorded and logged (via GPS) by the team.

**Contractor's Response**

Hydrated GCL confirmed as subgrade irregularity. GCL to be cut (where hydrated), removed, and replaced and the geomembrane will be patched / repaired, and sealed with an extrusion weld as outlined in the project specifications. Vacuum box testing will then be conducted to confirm repair.

**Follow Up Action Required**

Remove hydrated GCL from underneath cap and patch / repair area with extrusion welds following project specifications and as outlined in the Contractor's Response.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane cap was cut and GCL was exposed (along northern end of SA-6 at SCB wall). Hydrated GCL was removed from underneath geomembrane, and new pieces of GCL were cut and overlapped (minimum of 1 ft.) and sealed with granular bentonite along the seams. Various cuts in the geomembrane were then repaired (RP-474 & RP-475). Patches were overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the hole was properly patched (as outlined in Section 02372). Refer to *10/7/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carolina Ramos Date 10/8/15

Independent CQA Monitor Date 10/8/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 11

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 10/12/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 11<br>Notes: Failed Destruct Sample |
| **Reference** | |
| Item: Failed Destruct Sample<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Destruct sample DSX-13 (RP-483) collected from RP-477 from Panel #125, failed on one of the five specimens for peel testing completed by the Geosynthetic Installer's Laboratory (Note: average of the five specimens was acceptable). Based on this failure, RP-477 (entire patch) was covered with a new patch and sealed with an extrusion weld. This non-compliance issue was also noted on the 10/12/15 Repair Report, and is identified as RP-486. The location of this repair was recorded and logged (via GPS) by the team (southern swale).

**Contractor's Response**

Destruct sample DSX-13 failure for one of five specimens confirmed. Repair associated with destruct sample (P-125 on southern end of SA-6) to be covered with new patch, sealed, and extrusion welded according to project specifications. Additional destruct sample to be taken from new extrusion weld (from new patch) to confirm repair.

**Follow Up Action Required**

Place patch over RP-477 and repaired and sealed with extrusion weld, according to project specs.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*

Geomembrane patch was placed over RP-477 and was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Once extrusion welding was completed, vacuum box testing was conducted along the seams to confirm the patch was properly sealed (as outlined in Section 02372). Additionally, once the new patch (RP-486) was completed, an additional extrusion destruct sample (DSX-15) was collected (referred to as RP-487) to confirm the integrity of the new weld. Refer to *10/12/15 Photograph Log* for supporting non-compliance photos.

Geosynthetic Installer Representative Carolyn Ramos Date 10/13/15

Independent CQA Monitor Date 10/13/15

LANGAN

# Notice of Non-Compliance and Corrective Action

Sheet # 12

| General Project Information | |
|---|---|
| Project Name: SA-6 South<br>Project No.: 100530001<br>Owner/Contr.: Honeywell / AmecFW<br>QA Monitor: Langan | Date: 11/04/15<br>Contractor in NC: Entact<br>Non-Compliance No.: 11<br>Notes: Equipment Puncture |
| **Reference** | |
| Item: Equipment Puncture through Cap<br>Specification Sec. No.: 02372 | Drawing No.:<br>Other: |

**Description of Non-Compliance**

*Cross Reference (QA Inspection Form & Sheet No.):*

Equipment puncture through geomembrance cap observed along SCB wall (northern end of SA-6 cap). Puncture to be patched / repaired according to project specs. Additional details on the patch / repair work completed are described in the *11/4/15 Daily Report* and *11/4/15 Photograph Log*. This non-compliance issue was also noted on the 11/04/15 Repair Report, and is identified as RP-488. The location of this repair was recorded and logged (via GPS) by the team (along SCB wall).

**Contractor's Response**

Equipment puncture through geomembrane along SCB wall confirmed. Puncture to be covered with new patch, sealed, and extrusion welded according to project specifications.

**Follow Up Action Required**

Place patch over puncture location and repair and seal with extrusion weld according to project specs.

**Follow Up Action Taken**

*Cross Reference (QA Inspection Form & Sheet No.):*


Geomembrane patch was placed over the equipment puncture and was overlapped a minimum of 4-inches beyond the edges of the cut, conformed so that the edges were rounded, and sealed with an extrusion weld (as outlined in Section 02372). Prior to welding, a new piece of GCL was placed along the SCB wall over the puncture area. Upon completion of extrusion welding, vacuum box testing could not be completed based on the location of the patch (along edge of SCB wall). The welds were visually inspected by Entact and Langan. Refer to *11/04/15 Photograph Log* for supporting non-compliance photos.


Geosynthetic Installer Representative Carlos Ramos Date 11/5/15

Independent CQA Monitor Date 11/5/15

**ATTACHMENT G**
**SA-6 SOUTH CAP AS-BUILT DRAWINGS**

**ATTACHMENT G-1**
**SA-6 SOUTH CAP PANEL LAYOUT**
**(60 MIL TEXTURED LLDPE GEOMEMBRANE)**




## LEGEND

RP-1 (Repair Number)

LINER SEAM/EDGE

SCB WALL

HB WALL (Inner Edge)

RP: Repair

DSX: Destructive Extrusion Weld Test

DS: Destructive Fusion Weld Test

P: Panel

\- Bead

0 80 160 Feet

NOTE: Refer to ESI Repair Report for repair details

J.H. 01/28/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME

SA6 SOUTH CAP PANEL LAYOUT
60 mil Textured LLDPE Geomembrane
01/28/16

PROJECT NAME & LOCATION

HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT G-2**
**SA-6 SOUTH CAP GVL/GCL LAYOUT**
**(CLASS A GEOTEXTILE / GAS VENT LAYER / GEOSYNTHETIC CLAY LINER)**

HACKENSACK RIVER

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

ROUTE 440

0 80 160 Feet

## LEGEND

- GEOCOMPOSITE GAS VENT LAYER (GVL)
- GEOSYNTHETIC CLAY LINER (GCL)
- Class A/16 oz Geotextile
- SCB WALL
- HB WALL (Inner Edge)
- GAS VENT PIPE
- GAS VENT (NOT TO SCALE)
- SPOT ELEVATION (ft) (X 0.0)

J.H. 01/28/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: SA6 SOUTH CAP GVL/GCL LAYOUT
Class A Geotextile/Gas Vent Layer/Geosythetic Clay Liner
01/28/16

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT G-3**
**SA-6 SOUTH CAP GDL LAYOUT**
**(GEOCOMPOSITE DRAINAGE LAYER)**

HACKENSACK RIVER

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

ROUTE 440

## LEGEND

GEOCOMPOSITE DRAINAGE LAYER (GDL)

SCB WALL

HB WALL (Inner Edge)

0 80 160 Feet

J.H. 01/27/2016

ENTACT 302 Unity Plaza Latrobe, PA 15650


DRAWING NAME

SA6 SOUTH CAP GDL LAYOUT
GEOCOMPOSITE DRAINAGE LAYER 01/27/16

PROJECT NAME & LOCATION


HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT H**
**SA-6 SOUTH HYDRAULIC BARRIER WALL**
**PLAN AND PROFILE AS-BUILT**




NOTES:

1. PLAN LOCATION AND TOP ELEVATION OF HYDRAULIC BARRIER BASED ON SURVEY COMPLETED UNDER SUPERVISON OF MASER AND REPRSENTS THE FINAL ELEVATION AFTER THE WALL WAS CUT TO MATCH DESIGN LINER GRADES.
2. BOTTOM OF HYDRAULIC BARRIER AND EXTENT OF EPOXY COATING BASED ON ENTACT TOP SURVEY AND SHEET PILE FABRICATION DRAWINGS. ALL SHEETS DELIVERED TO THE SITE WERE INSPECTED BY AMEC PERSONNEL TO VERIFY LENGTHS AND EPOXY COATING.
3. STRATUM D SHOWN FOR REFERENCE ONLY AND IS BASED ON GEOTECHNICAL BORINGS COMPLETED DURING THE PRELIMINARY DESIGN INVESTIGATION.




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 2/10/16 | TDD | TDD | RJR | TDD |

REVISION: DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT

| BY | APVD |
|---|---|
| TDD | SGS |

NJ PROFESSIONAL ENGINEER LICENSE NUMBER: SGS

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2629

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-201 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTED MATERIAL, AND IS LOANED SUBJECT TO RETURN UPON DEMAND. IT IS NOT TO BE REPRODUCED, IN WHOLE OR IN PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:06 PM




NOTES:

1. REFER TO NOTES 1 THRU 3 ON SHEET S-201




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| 1 | 2/10/16 | DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT | TDD | APVD | TDD | SGS |
| DSGN | | DR | RJR | TDD | | SGS |

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL


HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 585 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-202 |
| SHEET | OF |


FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:05 PM




MATCH LINE SHEET S-202


NOTES:

1. REFER TO NOTES 1 THRU 3 ON SHEET S-201




SEE NOTE HB19 ON SHEET GN-003

SHEET SEALING DETAIL (F)
NTS
SN-201 | CN-301




0 5 10 20
SCALE IN FEET
VERTICAL SCALE: 1" = 10'

0 20 40 80
SCALE IN FEET
HORIZONTAL SCALE: 1" = 40'

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 2/10/16 | TDD | RJR | TDD | |

DECLARATION NO 2 - SA-6 SOUTH VHB AS BUILT

REVISION BY TDD APVD SGS

NJ PROFESSIONAL ENGINEER LICENSE NUMBER SGS

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 588 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 2/10/16 |
| PROJ | 3480-10-0027 |
| DWG | S-203 |
| SHEET | OF |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Declarations\Declaration No 2\SA-6 South VHB\SA-6 South VHB Final Profile.dwg PLOT DATE: Tue, 18 Oct 2016 PLOT TIME: 7:02 PM

**ATTACHMENT I**
**DESIGN CHANGES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB Type: Major (a)<br>Effective Date: 3/25/14 |
| Project Location: SA-6 NORTH, SA6-SOUTH | Associated RFI: |
| Title: CONTINGENT GW EXTRACTION SYSTEM | ☐ Yes, RFI No. ___ ☑ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. This Bulletin describes a major change to that extraction system and explains the basis for that change.

Section 10.2 of the Design Report stated "Honeywell reserves the right to propose alternative groundwater extraction designs capable of meeting the criteria stated in Article III.A (58) of the Consent Decree. Additionally, Note 3 on the Contingent GW Extraction System Drawings SA-6 South C-201,202 and 203 and SA-6 North CN-201, 202 and 203 further elaborated that "Honeywell will continue to evaluate pertinent information gathered through dewatering and other construction operations. This information will be used to calibrate the groundwater capture model. Subject to the results of that model calibration and evaluation of the system design Honeywell may propose alternative groundwater extraction designs".

The SA-6 South Groundwater Modeling Report Appendix B Section 5 indicates that Honeywell evaluated various pumping scenarios including the option of French Drains/Central drain. The results of the central/French drain scenario were shown in Figure 5-3. From a modeling perspective it was concluded that the drain provided equivalent performance to the 9 wells.

Consistent with the approach indicated in the Design report, Honeywell has continued to evaluate data collected during the construction dewatering and excavation. Observations of the well point dewatering system have indicated a great deal of variability in hydraulic properties from point to point. Observation of the excavation has also shown significant variability in soil types and permeabilities.

Based on an evaluation of this variability and in consideration of the reduced maintenance advantages associated with the French drain system, Honeywell is proposing to modify the design to change the wells to a French Drain. This proposal is consistent with paragraph 58 of the First Amended Consent Decree on Remediation and Redevelopment of Study Area 6 North. This design change will impact drawings C-201, 202, 203 and CN-201,202,203. The use of trenches also

reduces the number of pumps, control panels, and cap penetrations. This will result in changes to the electrical drawings E-301, 302, 303 and EN-301-302 and 303.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Design changed based on information gathered during construction<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected:<br>Contingent GW system plans and Profiles 201-103<br>Electrical Drawings 301-303<br>C306 Well/Pump Detail |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |

| | |
|---|---|
| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.1 Major<br>Effective Date: 06/10/14 |
| Project Location: SA-6 NORTH, SA6-SOUTH<br>Title: CONTINGENT GW EXTRACTION SYSTEM | Associated RFI:<br>☐ Yes, RFI No. ___ ☑ None |
| REPLACE WELLS WITH TRENCHES<br>Contractor (Subcontractor): Entact | Project No.: 3480130377 |

Description of Change/Modification:

DCB-007 has been issued to document changes to the Groundwater Removal System Oesign. This change includes changing from recovery wells to a "French drain" system. DCB 007 design will be issued is sections to allow for a "fast tracked" design and installation process.

Stage 1 (DCB-007.1) is limited to the French drain installation and the lower sections of the pump and access station manholes for SA-6 South. (see attached memo)

**The Drawings have certain design details clouded. These details have not been finalized and have not been issued for construction.**

**Subsequent stages of the design including the design for the SA-6N Groundwater Collection System will be issued under the DCB – 007 number. Examples DCB -007.2, DCB- 007.3.**

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☑ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Design changed based on information gathered during construction<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☐ No |
| Additional Comments: | Design Documents Affected:<br>Contingent GW system plans and Profiles 201-103<br>Electrical Drawings 301-303<br>C306 Well/Pump Detail |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |

(Name / Signature): 6/10/14

Does DCB Result in CCO? ☑ Yes(b) ☐ No

Date:

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

| | | | |
|---|---|---|---|
| Date: | June 6, 2014 | cc: | Joe Clifford, PE – Amec<br>Eric Christodoulatos - Amec |
| From: | Geoff Shallard, P.E. | | |
| To: | Stuart Bills - Amec | | |
| Subject: | DCB-007.1 | | |

DCB-007 has been issued to document changes to the Groundwater Removal System Design. This change includes changing from recovery wells to a "French drain" system

The new design will include installation of the following.

- a french drain including 8 inch HDPE perforated piping and 1 ½ inch crushed stone
- pump station manholes and associate frames and covers
- cleanout/access manholes and associated covers
- pumps and associated power and controls
- forcemain

Incidental to the basic design changes will include

- revisions to geomembrane liner grading
- revisions to final grades in the vicinity of pump stations

To facilitate progress the design details will be released in stages.

Stage 1 (DCB-007.1) is limited to the French drain installation and the lower sections of the pump and access station manholes for SA-6 South.

**The Drawings have certain design details clouded. These details have not been finalized and <u>have not been</u> issued for construction.**

**Subsequent stages of the design including the design for SA-6N will be issued under the DCB – 007 number. Examples DCB -007.2, DCB- 007.3.**

The pump station manhole should be constructed to the surcharge grade to allow for use of the system for groundwater control during surcharge and remedy construction prior to

capping. Manholes and the drain system will settle as the site consolidates. As a result flexibility needs to be retained to allow for setting access hatches to final grades. Temporary pumps will be used during the remedy.

| Drawing # | Title | Comments | Location |
|---|---|---|---|
| C-307 | Groundwater Extraction Trench Details | | STUDY AREA 6-South |
| C-201 | Groundwater Extraction Trench Plan and Profile | 0+00 to 9+50 | STUDY AREA 6-South |
| C-202 | Groundwater Extraction Trench Plan and Profile | 9+50 to 19+00 | STUDY AREA 6-South |
| C-203 | Groundwater Extraction Trench Plan and Profile | 19+00 to 22+40 | STUDY AREA 6-South |

Sincerely,


Amec Environment & Infrastructure, Inc.


Geoff Shallard

Associate Project Manager

**Attachments:**

Drawings C-201, C-202, C-203 C-307




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 06/06/14 | TDD | RJR | TDD | SGS |

DCB 007-J

REVISION BY TDD APVD SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS LOANED CONDITIONED UPON THE TERMS AGREED TO BY THE RECIPIENT. REPRODUCTION OF THE DRAWING, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\C-201 Cont Ground Water Extraction Sys.dwg PLOT DATE: Fri, 06 Jun 2014 PLOT TIME: 12:52 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43907

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 06/06/14 | DCB 007.1 | TDD | SGS |
| DSGN | TDD | DR RJR | CHK TDD | APVD SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28019600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\C-202 Cont Ground Water Extraction Sys.dwg PLOT DATE: Fri, 06 Jun 2014 PLOT TIME: 1:00 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | DR | CHK | APVD |
|---|---|---|---|---|
| 1 | 06/06/14 | TDD | RJR | TDD |

DCB 007-1
REVISION

| BY | APVD |
|---|---|
| TDD | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 587-2929
NJ Certificate of Authorization Number 24GA28019500


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\C-203 Cont Ground Water Extraction Sys.dwg PLOT DATE: Fri, 06 Jun 2014 PLOT TIME: 1:07 PM





GROUNDWATER TRENCH TEMPORARY CONDITION (CA)
NTS
C-201 C-202 C-203 C-307





LINER ANCHOR TO CONCRETE STRUCTURE (CE)
NTS
TYP C-307

## NOTES:


1. THE CONTRACTOR WILL LAY OUT THE ALIGNMENT. THE ALIGNMENT WILL BE INSPECTED BY THE CONTRACTOR AND ENGINEER PRIOR TO INITIATING INSTALLATION IN ANY AREA. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES, PILES, AND SURCHARGE MONITORING STATIONS.
2. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
3. CONTRACTOR TO USE PLATE BOLTED TO MANHOLE OR SIMILAR ARRANGEMENT TO BE APPROVED BY THE ENGINEER FOR COMBINING THE PITLESS ADAPTER AND SECONDARY CONTAINMENT.
4. PLACE STONE LOOSE IN TRENCH. RUN PLATE COMPACTOR OR EQUAL PRIOR TO INSTALLING FABRIC.
5. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.




PLAN VIEW





TYPICAL ACCESS MANHOLE FINAL CONDITION
STA.=3+63±, STA.=8+90±, STA.=14+35± (CB)
NTS
C-201 C-202 C-307





SECTION VIEW
PLAN VIEW

PIPE PERFORATIONS (CD)
NTS
TYP C-307




SECTION A-A'




GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)
NTS
C-203 C-307

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| DSGN | | DCB 007-1 | TDD | APVD |
| DR | | RJR | TDD | SGS |
| TDD | 1 | 06/06/14 | BY | APVD |
| | | | TDD | SGS |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-307 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.2 Major<br>Effective Date: 11/20/14 |
| Project Location: SA-6 NORTH | Associated RFI: |
| Title: GW EXTRACTION SYSTEM | o Yes, RFI No. ____ þ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification. DCB-007.2 provides the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. Section 10.3 of the Design Report stated "Honeywell reserves the right to propose alternative groundwater extraction designs capable of meeting the criteria stated in Article III.A (56) of the Consent Decree.

Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.2 is applicable to the SA-6N Groundwater Extraction System trench design.

The design was modeled by Cornerstone. The model results indicate that the design will achieve the required gradients. Figure 1, 2 and 3 from the model runs are attached for reference.

The changes impact the following drawings
The following Issued for Construction Drawings are deleted

- CN-201
- CN-202
- CN-203

These following drawings were added

Contingent Groundwater Extractions System Plan and Profile


- CN-201
- CN-202
- CN-203
- CN-204 (discharge force main and electrical)
- CN-310 (Groundwater Extraction Trench Details).


The changes from the well concept to the trench will also impact the Geomembrane Liner Grading CN-123 and CN-124. The Geomembrane liner changes will be issued separately.

It is noted that the 5 piezometric pairs on SA-6N are not included in this DCB. Amec is currently evaluating data collection and transmission options for the piezometers. The piezometer designs will be issued in a separate DCB.

| Reason for Change/Modification: | Explanation or Reason: Design changed based on information gathered during construction |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No<br><br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system plans and profiles-see drawing list in description |
| Honeywell (AP) Review:<br>Individual Discipline Initial Date | |
| (Name / Signature): Ronald G. Blackett | Does DCB Result in CCO? ☑ Yes (b) ☐ No<br>Date: 4/21/14 |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FOR FORCE MAIN PROFILE INFORMATION SEE SHEET CN-204.
4. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
5. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM C AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
6. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
7. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4
8. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON GASKETS.
9. PIEZOMETRIC PAIRS MAY BE INSTALLED USING SOLAR PANELS FOR POWER AND CELL TOWER OR SATELLITE DATA TRANSMITTING. DESIGN OF PIEZOMETRIC PAIR WILL BE ISSUED UNDER SEPARATE COVER.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD

| NO | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 11/19/14 | | TDD | RJR | TDD | TDD | SGS |
| 1 | 09/13/13 | DCB 007.2 | | | | RJR | SGS |
| 0 | 06/07/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | | | TDD | SGS |
| | | ISSUED FOR CONSTRUCTION | | | | | |
| | | REVISION | | | | | |

NJ PROFESSIONAL ENGINEER
SGS LICENSE NUMBER 43597

Honeywell
101 COLUMBIA RD BOX 2100, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

THIS DRAWING IS THE PROPERTY OF AMEC INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE

amec
Environment & Infrastructure Inc
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
609-890-2333
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-201 |
| SHEET | 33 OF 70 |

FILE NAME Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-CS\PCAD\SA6-North-South-GW_Extraction_Trench\NORTH\CN-201-Cont Pump Well Sections.dwg PLOT DATE Wed, 19 Nov 2014 PLOT TIME 2:55 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-201 FOR NOTES.
4. BARRIER WALL ALIGNMENT SUBJECT TO FINAL LAYOUT CHANGES.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43597

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/19/14 | TDD | RJR | TDD | SGS |
| 1 | 09/13/13 | RJR | SGS | | |
| 0 | 06/07/13 | TDD | SGS | | |
| | | BY | APVD | | |

DCB 007.2
HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE


amec
Environmental & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2629
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-202 |
| SHEET | 34 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CACKSA6-North-South-GW_Extraction_Trench\NORTH\CN-202-Cont_GWE_Trench.dwg PLOT DATE: Thu, 20 Nov 2014 PLOT TIME: 3:15 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-201 FOR NOTES.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

| NO | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/18/14 | TDD | RJR | TDD | SGS |
| 1 | 09/13/13 | RJR | SGS | | |
| 0 | 08/07/13 | TDD | SGS | | |

DCR 007.2
HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION

SAMUEL G SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GS

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2823
NJ Certificate of Authorization Number 24GA28011900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-203 |
| SHEET | 35 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. THE DESIGN OF THE CONTINGENT GROUNDWATER EXTRACTION SYSTEM IS CONCEPTUAL AND HAS BEEN BASED ON THE AVAILABLE HYDROGEOLOGIC INFORMATION. THE DESIGN IS BASED ON A THEORETICAL SCENARIO USING CONSERVATIVE ASSUMPTIONS. HONEYWELL WILL CONTINUE TO EVALUATE PERTINENT INFORMATION GATHERED THROUGH DEWATERING AND OTHER CONSTRUCTION OPERATIONS. THIS INFORMATION WILL BE USED TO CALIBRATE THE GROUNDWATER CAPTURE MODEL. SUBJECT TO RESULTS OF THAT MODEL CALIBRATION AND EVALUATION OF THE IMPACTS ON THE SYSTEM DESIGN HONEYWELL MAY PROPOSE ALTERNATIVE GROUNDWATER EXTRACTION DESIGNS CAPABLE OF MEETING THE CRITERIA STATED IN ARTICLE III A 58 OF THE CONSENT DECREE.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G SHALLARD

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 2 | 11/19/14 | TDD | RJR | TDD | TDD | SGS |
| 1 | 09/13/13 | RJR | SGS | RJR | TDD | SGS |
| 0 | 06/07/13 | TDD | SGS | TDD | TDD | SGS |

REVISION

DCB 007.2
HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREIN, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., P.O. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 067 AND 068
JERSEY CITY, NEW JERSEY


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28017500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-204 |
| SHEET | 36 OF 70 |





## PIPE PERFORATIONS (CD)

NTS — TYP | CN-310


CONSTRUCTION SEQUENCE

- SET MANHOLE BASE AND RISER SECTIONS.
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- OR ADJUST DESIGN GRADE TO MATCH AVAILABLE RISERS – SUBJECT TO ENGINEERS APPROVAL.





## LINER ANCHOR TO CONCRETE STRUCTURE (CE)

NTS — TYP | CN-310




## TYPICAL ACCESS MANHOLE FINAL CONDITION (CB)

NTS — STA=1+55±, AND STA=18+00± — CN-201 | CN-310 | CN-203





## GROUNDWATER EXTRACTION PUMP STATION STA 7+35± & STA 12+50± (CC)

NTS — CN-202 | CN-203 | CN-310


## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 1.5" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC VITON O RINGS AND TEFLON SEALS |
| 1.5" DIA. FLEXHOSE | 1 | GRANGER OR APPROVED EQUAL | ITEM #3JT48 25' LENGTH EACH |
| 1.5" DIA. CAMLOCK QUICK DISCONNECTS | 1-MALE 1-FEMALE | GRANGER OR APPROVED EQUAL | ITEM #3LX22 ITEM #3LX14 (GET FROM GRANGER) |
| EXPLOSION-PROOF PLUG AND CONNECTOR | 2-SETS | MELTRIC 22-14043 22-18043 OR APPROVED EQUAL | INLINE PLUG AND RECEPTACLE W/ MALE CAP. HANDLES AND FINGER DRAW PLATES |
| 1" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC WITH VITON O RINGS AND TEFLON SEALS |
| 1.5" SWING CHECK VALVE | 1 | SPEARS OR APPROVED EQUAL | MODEL 4423-015 VITON SEAL AND O RINGS |
| 36" X 50" VALVE VAULT HATCH | 1 | PENNSYLVANIA INSERT CORP STOCK# ATH30500 H*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |




## ELBOW PIPE CLEANOUT (CF)

NTS — CN-202 | CN-310




## GROUNDWATER TRENCH SURCHARGE CONDITION (CA)

NTS — TYP | CN-310

SAMUEL G SHALLARD — NJ PROFESSIONAL ENGINEER LICENSE NUMBER 23687

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 2 | 11/19/14 | DCB 007 2 | TDD | SGS |
| 1 | 05/14/14 | DCB 007 | TDD | SGS |
| DSGN | | CHK | APVD | SGS |
| TDD | | RJR | TDD | |

Honeywell — 101 COLUMBIA RD, BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH DETAILS


amec — Environment & Infrastructure, Inc. 200 American Metro Blvd, Suite 113 Hamilton, NJ 08619 (609) 689-2029 NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

DATE
PROJ 3480-12-0317
DWG CN-310
SHEET 45 OF 70

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWINGS, IN WHOLE OR PART, NOR USE ANY PART OF THE DRAWINGS FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SAB-C3D\CADD\SAB-North-South-GW_Extraction_Trench\NCR45-CN-310 Extraction Trench Details.dwg PLOT DATE: Thu, 20 Nov 2014 PLOT TIME: 3:14 PM




LEGEND

5.0 Predicted Heads

5.0 Measured Heads


**NTS**

FIGURE 1

Model Calibration
Predicted versus Measured Heads
Model Layer 1 (Shallow Zone)

Study Area 6 North
Jersey City, NJ

cornerstone environmental




## LEGEND

Contingent Pumping System Drain Line

**3.2** ← Head Diff. Across Wall

5.0 Predicted Heads


**NTS**

FIGURE 2

Post-development Predicted Heads
SA-7 Perimeter Pools Non-functioning
Head in Drain at +2.0'

Study Area 6 North
Jersey City, NJ

cornerstone environmental




## LEGEND

Contingent Pumping System Drain Line

**3.2** ← Head Diff. Across Wall

5.0 Predicted Heads

**NTS**

FIGURE 3

Post-development Predicted Heads
SA-7 Perimeter Pools Non-functioning
Head in Drain at +3.0'

Study Area 6 North
Jersey City, NJ

cornerstone environmental

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.3 Major (a)<br>Effective Date: 02/12/15 |
| Project Location: SA-6 SOUTH | Associated RFI: |
| Title: GW EXTRACTION SYSTEM | o Yes, RFI No. NA_ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench had not been finalized.
DCB-007.2 provided the details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.
DCB-007.3 provides the details for the SA-6S groundwater collection trenches and associated electrical supply and groundwater discharge piping.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. The revised Design uses a trench design. Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.3 impacts the following drawings
The following Issued for Construction Drawings Extraction System that was based on 9 extraction wells are deleted

- C-201 Plan and Profile
- C-202 Plan and Profile
- C-203 Plan and Profile
- C-304 System Details

The following drawings for the Trench design were added.

- C-201 Trench Plan and Profile
- C-202 Trench Plan and Profile
- C-203 Trench Plan and Profile
- C-204 Discharge Force Main Plan and Profile)
- C-304 Details
- C-306 Details
- C-310 Details).

The changes from the well concept to the trench will also impact the Electrical Drawings. E-101, E-301, E-302 and E-303. The Electrical changes will be issued separately under DCB 007.4. It is noted that DCB 007.2 and DCB 007.3 does show the details for all pumps, motors and controls for the trench design.

The changes from the well concept to the trench will also impact the Geomembrane Liner Grading. The Geomembrane liner changes will be issued separately under DCB 007.5.

Note; piezometric pairs will be installed as shown on both SA-6N and SA-6S. The piezometers on north were previously shown as clouded/temporarily deferred.


| Reason for Change/Modification: | Explanation or Reason: Design changed based on information gathered during construction |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No<br><br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system plans and profiles-see drawing list in description |


| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |

| (Name / Signature): | Does DCB Result in CCO? ☑ Yes (b) ☐ No |
|---|---|
| Samuel G Shallard | Date: 2/16/15 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON GASKETS.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 2 | 02/13/15 | TDD | TDD | RJR | TDD | SGS |
| 1 | 06/06/14 | TDD | | | | SGS |

REVISION
1 DCB 007
2 DCB 007.3

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:44 PM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | TDD | RJR | TDD |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS | APVD |
| DSGN | | | BY | | |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-202
SHEET OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SHM |
| DSGN | TDD | DR RJR | BY TDD | APVD SGS |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS LOANED UNDER THE CONDITIONS THAT IT SHALL NOT BE REPRODUCED, USED OR DISCLOSED TO ANY PERSON, FIRM OR CORPORATION FOR ANY PURPOSE WHATSOEVER, AND THAT NEITHER IT NOR THE INFORMATION IT DISCLOSES SHALL BE USED IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREIN, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR36-C-203_Cont_GWE_Trench.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:18 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

SAMUEL G. SHALLARD
N.J. PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 02/13/15 | TDD | SGS | RJR | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | | RJR | SGS |
| 1 | 05/14/14 | DCB 007 | | TDD | SHM |
| | | DCB 007.3 | | BY | APVD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609)689-2829
NJ Certificate of Authorization Number 24GA28010600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR37-C-204_Cont_GWE_Trench_FM.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 1:09 PM





NOTES:

1. USE THUNDERLINE LINK–SEAL TYPE LS 300–C FOR 2"ø OR 3" ø PIPELINES AND TYPE LS 425–C FOR 1"ø AND 1–1/4" PIPELINES OR EQUAL AT ALL MANHOLES AND STRUCTURES.
2. USE PRESSURE GAGE AND PROBE ON PIPELINES THAT SLOPE UPWARDS FROM STRUCTURES ONLY, BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK–JOINT FLEXIBLE MANHOLE SLEEVE OR KOR–N–SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.

## TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL (X)


NTS — C–304 | C–306




IN THE LEAK DETECTION ROAD BOXES WHERE THE TOP OF THE TRANSITION PIECE IS CLOSE TO THE UNDERSIDE OF THE ROAD BOX COVER A THREADED FLAT STEEL CAP IS INSTALLED DIRECTLY ON THE THREADED TRANSITION PIECE. A THREADED STEEL PLUG IS INSTALLED IN THE REMAINING LEAK DETECTION RISERS.

## LEAK DETECTION STATION (CG)

NTS — C–204 | C–304




## LINER ANCHOR TO CONCRETE STRUCTURE (CE)

NTS — TYP | C–304




## AIR RELEASE STATION (CF)

NTS — C–204 | C–304




## DOUBLE CONTAINED ELBOW PIPE CLEANOUT (CH)

NTS — C–204 | C–304




## EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT (CI)

NTS — C–204 | C–304




## EXISTING 3" LEAK DETECTION STATION (CJ)

NTS — C–204 | C–304

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND C–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 02/13/15 | REO | RJR | REO | APVD | TDD SGS |
| 0 | 06/07/13 | DSGN | DR | CHK | APVD | TDD SHM |

DCB 007.3
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IT'S USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 889 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-304 |
| SHEET | 41 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR41-C-304_GWFM_Details.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:51 PM




PLAN





SECTION AA





SECTION BB

FLOW METER STRUCTURE DETAIL AZ
NTS STA 63+78 C-204 C-306





NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL AE
NTS C-201 C-202 C-203 C-306




EXISTING 3" FM TRENCH DETAIL CK
NTS STA 63+78 TO STA 68+91 C-204 C-306




NOTE:
SUBCONTRACTOR IS REQUIRED TO VERIFY PRIOR TO BEGINNING WORK FROM STA. 68+91 TO STA. 70+19

TRENCH DETAIL CL
NTS C-204 C-306

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. SEE SHEET C-304 FOR HATCH SPEC.

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 02/13/15 | TDD | SGS | | SHM |
| 0 | 06/07/13 | TDD | SHM | RJR | REO |
| | | BY | APVD | REO | |

DCB 007.3
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THIE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689-2229
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR43-C-306 Extraction Well Details.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:53 PM




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)


NTS

C-203 | C-310
C-204


- SET MANHOLE BASE AND RISER SECTIONS.
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 1.5" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC VITON O RINGS AND TEFLON SEALS |
| 1.5" DIA. FLEXHOSE | 1 | GRANGER OR APPROVED EQUAL | ITEM #3JT48 25' LENGTH EACH |
| 1.5" DIA. CAMLOCK QUICK DISCONNECTS | 1-MALE 1-FEMALE | GRANGER OR APPROVED EQUAL | ITEM #3LX22 ITEM #3LX14 |
| EXPLOSION-PROOF PLUG AND CONNECTOR | 2-SETS | MELTRIC 22-14043 22-18043 OR APPROVED EQUAL | INLINE PLUG AND RECEPTACLE W/ MALE CAP, HANDLES AND FINGER DRAW PLATES |
| 1" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC WITH VITON O RINGS AND TEFLON SEALS |
| 1.5" SWING CHECK VALVE | 1 | SPEARS OR APPROVED EQUAL | MODEL 4423-015 VITON SEAL AND O RINGS |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D !*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |




SECTION VIEW





PLAN VIEW

## PIPE PERFORATIONS (CD)

NTS


TYP C-310




## TYPICAL ACCESS MANHOLE FINAL CONDITION STA.=3+63, STA.=8+90, STA.=14+35 (CB)

NTS

C-201 | C-310
C-202




## GROUNDWATER TRENCH TEMPORARY CONDITION (CA)

NTS

C-201 | C-310
C-202
C-203

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 02/02/15 | TDD | SGS | TDD | SGS |
| 1 | 06/06/14 | REVISION | | BY | APVD |

DCB 007.3
DCB 007

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 584-2929
NJ Certificate of Authorization Number 24GA28010300

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR46-C-310_Cont_GWE_Trench_Details.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:04 PM

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.5 Major<br>Effective Date: 02/24/15 |
| Project Location: SA-6 SOUTH | |
| Title: GW EXTRACTION SYSTEM | |
| Revision to the Geomembrane/Subgrade surface. | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification.

DCB-007.2 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

DCB-007.3 provided the final details for the SA-6S groundwater collection trenches and associated electrical supply and groundwater discharge piping

DCB-007.4 issue pending. This DCB will provide the revised one line electrical drawings for SA-6N and SA-6S. In the revised design there is one extraction manhole on SA-6S and two extraction manholes in SA-6N.

DCB-007.5 provides a revised subgrade/Geomembrane surface as discussed below.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each Open Space Area and common header system. The trench design has one pump station in SA-6S and 2 pump stations in SA-6N.

Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.5 is applicable to the SA-6N and SA-6S subgrade/Geomembrane surface. The change from wells to trenches resulted in numerous changes in grading. There were typically depression in the subgrade around each well to allow for installation of control vaults at each well and associated force mains leading from each well. These depressions have been eliminated and the Geomembrane surface smoothed at these locations. A depressed area has been added at each pump station and associated force main. The changes simplify the grading and Geomembrane installation

The changes impact the following drawings.
For 6A-South:

- C-122
- C-123
- C-124

For 6A-North:

- CN-123
- CN-124

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Design changed based on information gathered during construction<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system one line electrical design. |
| Honeywell (AP) Review:<br>Individual Discipline | Initial Date |
| (Name / Signature): 2/24/15 | Does DCB Result in CCO? ☑ Yes (b) ☐ No<br>Date: |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43307

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | TDD | RJR | TDD | SHM |
| 1 | 02/24/15 | TDD | SGS | | |
| 0 | 06/07/13 | TDD | SHM | | |

REVISION BY APVD

ISSUED FOR CONSTRUCTION

DCB 007.5

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
220 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-122 |
| SHEET | 27 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 02/24/15 | TDD | RJR | TDD | SHM |
| 0 | 06/07/13 | TDD | SHM | SHM | APVD |

ISSUED FOR CONSTRUCTION
REVISION
DCB 007.5
BY

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD., BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 588 - 2629
NJ Certificate of Authorization Number 24GA28018600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-123 |
| SHEET | 28 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C30\CAD\SA6S\CR28-C-123 Geomembrane Grading Plan.dwg PLOT DATE: Tue, 24 Feb 2015 PLOT TIME: 2:26 PM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. CONTOURS DEPICTED ON THIS SHEET REPRESENT THE SUBGRADE ELEVATIONS (NGVD 29) FOR LINER SYSTEM INSTALLATION

0 20 40 80
SCALE IN FEET

| NO. | DATE | DSGN | DR | REVISION | CHK | APVD |
|---|---|---|---|---|---|---|
| 2 | 02/24/15 | TDD | RJR | DCB 007.5 | TDD | SHM |
| 1 | 10/11/13 | | | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | | | ISSUED FOR CONSTRUCTION | TDD | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. P.O. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GEOMEMBRANE GRADING PLAN


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR COPYRIGHTABLE INFORMATION AND USE IS CONDITIONED UPON THE TERMS AND CONDITIONS STATED IN THE AGREEMENT BETWEEN AMEC AND ITS CLIENT. REPRODUCTION OF THIS DRAWING, IN WHOLE OR PART, FOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC, THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC, IS PROHIBITED AND WILL BE AT THE RISK OF THE USER.

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-124 |
| SHEET | 29 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6SC\R29-C-124 Geomembrane Grading Plan.dwg PLOT DATE: Tue, 24 Feb 2015 PLOT TIME: 2:29 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TO OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | | TDD | RJR | TDD | | |
| 1 | 02/24/15 | DCB 007.5 | | | | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD | SGS |
| | | REVISION | | | | BY | APVD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2629
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-123 |
| SHEET | 28 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TOP OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 02/24/15 | TDD | RJR | TDD | SGS |
| 1 | 09/13/13 | DCB 007.5 | | | |
| 0 | 06/07/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | | SGS |
| | | ISSUED FOR CONSTRUCTION | TDD | | SGS |
| | | REVISION | BY | | APVD |

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

GEOMEMBRANE GRADING PLAN

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28010600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-124 |
| SHEET | 29 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design\SA6-C3D\CAD\SA6N\100 Percent\CR29-C-124 Geomembrane Grade.dwg PLOT DATE: Wed, 25 Feb 2015 PLOT TIME: 7:42 AM

**Honeywell RES**

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: Minor (a)<br>Effective Date: 3/4/15 |
| Project Location: SA-6 SOUTH | Associated RFI: |
| Title: 3S Surcharge Pile Geometry on East End | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

Description of Change/Modification:


Reason for deferral:

The surcharge pile has been constructed to the design height of the barrier wall. The strip or land between the barrier wall and the property line is one of the "deferred areas" and varies in width from 0 to 12 feet. See attached figure. Final Development grades east of the barrier wall are at essentially the same grade as the existing grade. As such there is no additional load generated by the development grades and therefore there is no necessity of surcharge.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason.<br>Avoids placement of fill outside of the protective limits of the Barrier Wall. |
| | Attachments: ☑ Yes ☐ No |
| | Cost Implication: ☐Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected:<br>Changes the limit of surcharge fill however no specification of drawing change is considered to be necessary. |

| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| (Name / Signature): Samuel Shallard | | Does DCB Result in CCO? ☐ Yes Yes (b) ☑ No<br>Date: 3/25/15 | |
| Distribution: | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. PRIOR TO SURCHARGING REMOVE SA-7 FENCE AND SA-7 FLOODLIGHTS.
2. GEOTECHNICAL MONITORING INSTRUMENTATION TO BE INSTALLED PRIOR TO SURCHARGE.
3. COMMENCE FILL AT THE HACKENSACK RIVER AND WORK EAST TOWARDS ROUTE 440.
4. LOCATION OF SA-7 PERIMETER POOL RISER PIPES ARE APPROXIMATE. RISER PIPES TO BE FIELD VERIFIED AND EXTENDED WITH SURCHARGE AND MONITORED.
5. AFTER COMPLETION OF AREAS 1 AND 3 SURCHARGE LOADING, REMAINING FILL FROM THESE AREAS WILL BE COMBINED TO FORM THE SURCHARGE FOR AREA 2.

| SETTLEMENT MONITORING POINTS | | |
|---|---|---|
| DESCRIPTION | NORTHING | EASTING |
| FS-6 | 684538 | 602919 |
| FS-7 | 684638 | 602751 |
| HS-16 | 684678 | 602808 |
| HS-17 | 684488 | 603027 |
| HS-18 | 684333 | 603198 |
| HS-19 | 684211 | 603276 |
| HS-20 | 684542 | 602775 |
| HS-21 | 684409 | 602931 |
| HS-22 | 684253 | 603093 |
| SP-8 | 684728 | 602761 |
| VRC-7 | 684643 | 602742 |

- VI-2 — INCLINOMETER LOCATION
- FS-1 — SETTLEMENT MONITORING POINT FULL - SET UP
- HS-1 — SETTLEMENT MONITORING POINT HALF - SET UP
- SP-12 — SETTLEMENT MONITORING PLATFORM
- RP — APPROXIMATE LOCATION OF SA-7 PERIMETER POOL RISER PIPE (SEE NOTE 7)
- VRC1 — VIBRATING WIRE PIEZOMETER IN STRATUM RC

Attachment A

DC 03-04-15 Eliminate Surcharge Area 3S Deferred Area


0 20 40 80
SCALE IN FEET

Prepared/Date: EJR 12/10/13
Checked/Date: AE 12/15/13

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | INSTRUMENTATION LOCATION PLAN 3S<br>Figure 11 |

JOB NO. _____ SHEET 1 OF 1
PHASE _____ TASK DCB
JOB NAME Modified 3S Surcharge
BY Ari Eslaminejad DATE 3/25/15
CHECKED BY _____ DATE _____

amec
American Metro Center 200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
+1 (609) 689-2829 Fax +1 (609) 689-2838




Attachment B

DC 03-04-15 Area 3S Eliminate Surcharge Deferred Area

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No 026.1: Minor (a) |
| | Effective Date: 05/19/2015 |
| Project Location: SA-6 | Associated RFI: |
| Title: Contingent GW System Delete Pumps & Controls | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB 026.1 serves to provide notice to Entact that specific components related to the Contingent GW system are being removed from the scope. Associated drawing revisions and supplemental detail will be provided in DCB 026.2.

Supply and installation of items listed below will be deferred pending closure of the caps and stabilization of the groundwater levels and quality within the contingent groundwater system on both SA-6N and 6S. These changes impact the three Groundwater extraction Pump Stations and associated electrical and instrumentation wiring.

Revised Contingent Groundwater drawings will be issued under DCB 026.2

- DWG C-310 Detail CC
  - Submersible Grinder Pump Model HPGR200 and associated electrical wiring.
  - Level switches, level alarm, Pump Power Control Panel and associated electrical and instrumentation cable.
  - 1.5 inch flex discharge hose.
- DWG C-204. Flow Meter and Flow Meter Structure as detailed on DWG 306. Delete in its entirety including all associated instrument cable and conduit.

Contingent GW force mains, electrical and instrument conduit will be installed as shown with pull string/wire to permit installation of electrical and instrumentation wire by others.

Please Note that the above Geomembrane pump station including all pumps, wiring and controls will be installed as shown.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>√ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason:<br>Attachments: ☐ Yes √ No<br>Cost Implication: √ Yes ☐ No<br>>$50k √ Yes ☐ No<br>Schedule Implication ☐ Yes √ No |
| Additional Comments: | Design Documents Affected:<br>C-204,C-310, E-301, E-302<br>CN-201,CN-301,CN-302 CN-305<br>EN-301, EN-302 |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| (Name / Signature):<br>Samuel Shallard | | | Does DCB Result in CCO? ☐ Yes (b) ☐ No<br>Date: May 19, 2015 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 007.4 **DCB Type:** Major(a)<br>**Effective Date:** 9/3/15; **Rev. 1** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** GW Extraction System – Revisions of Electrical to Replace Wells with Trenches | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description:**

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification.

DCB-007.2 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

DCB-007.3 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping

DCB-007.4 provides the revised electrical plan, one line electrical drawings and electrical details for SA-6S.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. The revised Design uses a trench design. Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.4 is applicable to the Groundwater Extraction System electrical drawings for SA-6S (electrical plan and one line electrical drawing).


Drawings that are revised in this DCB are:
SA-6S


- C-201
- C-202
- C-203
- C-204
- C-306
- C-310
- E-301
- E-302
- E-303

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** : Design changed based on information gathered during construction |
| | **Attachments:** ☑ Yes ☐ No<br>C-201, C-202, C-203, C-204, C-306, C-310, E-301, E-302, E-303 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |

| | | | |
|---|---|---|---|
| **Additional Comments:** | | **Design Documents Affected:** C-201, C-202, C-203, C-204, C-306, C-310, E-301, E-302, E-303 | |
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☑ **Yes (b)** ☐ **No** |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON GASKETS.
10. INSTALL INSTRAMENTATION CONDUIT FOR PAIRE PIEZOMETERSREADIED WITH PULL STRINGS FOR FUTURE INSTRAMENTATION CABLE INSTALLED BY OTHERS.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 08/14/15 | RJR | SGS | TDD | SGS |
| 2 | 02/13/15 | TDD | SGS | | |
| 1 | 06/06/14 | TDD | SGS | | |
| | REVISION | BY | APVD | | |

DCB 007.4
DCB 007.3
DCB 007

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 585-7900
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
9/2/15

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | TDD | | RJR | TDD | | SGS |
| 4 | 08/14/15 | | | DCB 007.4 | | RJR | SGS |
| 3 | 02/13/15 | | | DCB 007.3 | | TDD | SGS |
| 2 | 07/30/14 | | | DCB 007.1 | | TDD | SGS |
| 1 | 06/06/14 | | | DCB 007 | | TDD | SGS |

THIS DRAWING IS THE PROPERTY OF AMEC; INCLUDING ALL PATENTED AND PATENTABLE IDEAS, AND IS CONDITIONED UPON THE RECIPIENT'S AGREEMENT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 110
Hamilton, NJ, 08619
(609) 989 - 2829
N.J. Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR35-C-202_Cont_GWE_Trench.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:11 AM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.




HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
SGS LICENSE NUMBER 43507
NJ PROFESSIONAL ENGINEER

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 4 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SHM |
| DSGN | TDD | DR RJR | CHK TDD | APVD SGS |

Honeywell
101 COLUMBIA RD. BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.
5. AT STATION 66+65, IF AVAILABLE, REUSE EXISITNG ELECTRICAL PULL BOX.
6. FROM STATION 63+78 TO STATION 68+91 REMOVE ANY EXISTING WIRING REMAINING IN THE 2" E+I CONDUITS.
7. FORCEMAIN TO BE CAPPED AND TEMINATED 5 FEET OUTSIDE THE GROUNDWATER TREATMENT PLANT. INSTALL 4"x4"x4' GRANITE MARKER AT END OF FORCEMAIN. TOP 2" ABOVE GRADE TO DOCUMENTATION LOCATION.
8. 2" PVC POWER CONDUIT TO BE INSTALLED. WIRING TO BE INSTALLED BY OTHERS UNDER FUTURE CONTRACT. INSTALL NON-DEGRADABLE PULL STRINGS FOR FUTURE USE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 4 | 08/14/15 | RJR | SGS | | |
| 3 | 02/13/15 | TDD | SGS | | |
| 2 | 05/16/14 | RJR | SGS | | |
| 1 | 05/14/14 | TDD | SHM | | |
| | REVISION | | BY | APVD | |
| | DCB 007.4 | | | TDD | SGS |
| | DCB 007.3 | | | | |
| | REVISED GROUNDWATER EXTRACTION PUMP STATION DCB 007 | | | | |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USE AS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR37-C-204_Cont_GWE_Trench_FM.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 8:16 AM




PLAN





SECTION AA





SECTION BB

DROP STRUCTURE DETAIL (AZ)
NTS STA 63+78 C-204 C-306





NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL (AE)
NTS C-201 C-306 C-202 C-203




EXISTING 3" FM TRENCH DETAIL (CK)
NTS STA 63+78 TO STA 68+91 C-204 C-306




TRENCH DETAIL (CL)
NTS C-204 C-306

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| | | | REO | RJR | APVD | SHM |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD SHM |
| 1 | 02/13/15 | DCB 007.3 | | | | TDD SGS |
| 2 | 08/14/15 | DCB 007.4 | | | | RJR SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 588 - 2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C2D\CADD\SA6-North-South-GW_Extraction_Trench\CR43-C-306 Extraction Well Details.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:18 AM




GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)

NTS

C-203 | C-204 | C-310

- SET MANHOLE BASE AND RISER SECTIONS. (NITC)
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

NOTE:

INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | TDD | | TDD | RJR | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS | TDD | SGS |
| 2 | 02/02/15 | DCB 007.3 | TDD | SGS | RJR | SGS |
| 3 | 08/14/15 | DCB 007.4 | | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 153
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

FILE NAME= Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CADD\SA6-North-South-GW_Extraction_Trench\CR46-C-310_Cont_GWE_Trench_Details.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:19 AM




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE RIGID GALVANIZED STEEL (RGS) UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIERD.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| EH | ELECTRIC HANDHOLE |
| EW | EXTRACTION WELL |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| TSP | TWISTED SHIELDED PAIR |
| TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| V | VOLTAGE |
| W | WIRE |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 08/14/15 | TDD | RJR | SHM | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | |
| | | DCB 007.4 | | | |
| | | REVISION | | BY | APVD |
| | | | | RJR | SGS |
| | | | | TDD | SHM |
| | | | | BY | APVD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6, SOUTH
SITES 073, 124, 125, 134,
140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-301 |
| SHEET | 64 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## EXTRACTION WELL PUMP CONTROL PANEL DETAIL (AO)

NTS

TYP E-302


NOTES:

1. ALL CONDUITS SHALL BE 1" RGS MINIMUM, UNLESS OTHERWISE SHOWN. WHEN DISTANCE IS LESS THAN 6 FEET, LIQUID TIGHT METAL FLEXIBLE CONDUIT MAY BE USED.
2. LOCATE THE PUMP MOTOR STARTER WITHIN 3' OF THE EXTRACTION WELL PUMP STATION.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

NOT PART OF THIS CONTRACT
ELECTRICAL POWER AND INSTRUMENTATION CONTROLS TO BE RE-EVALUATED FOLLOWING INITIAL DRAWDOWN AND TRENCH PERFORMANCE EVALUATION.





## PUMP CONTROL PANEL WIRING DIAGRAM (AP)

NTS

TYPICAL FOR ONE LEVEL TRANSDUCER AND ONE EXTRACTION WELL PUMP CONTROL (SEE NOTE 3)

TYP E-302




## INVERTER DRIVE WIRING DIAGRAM (AQ)


NTS

TYP E-302

FIELD TERMINAL STRIP CONNECTION SUMMARY

| | |
|---|---|
| GND | EARTH GROUND |
| 10 | RED TRANSDUCER WIRE |
| 11 | BLUE TRANSDUCER WIRE |
| 22 | MALE QD RECEPTACLE BROWN AND BLACK |
| 26 | MALE QD RECEPTACLE BLUE |
| 27 | MALE QD RECEPTACLE WHITE |
| 32 | FAULT CONTACT SUPPLY |
| 33 | FAULT CONTACT RETURN |

FEMALE QUICK DISCONNECT PLUG




## PLUG & TERMINAL STRIP WIRING DIAGRAM (AR)

NTS

TYP E-302

SAMUEL G SHALLARD

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 08/14/15 | TDD | RJR | RJR | SHM |
| 0 | 06/07/13 | DCB 007.4 | | | |

| NO. | REVISION | BY | APVD |
|---|---|---|---|
| 0 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| 1 | | RJR | SGS |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


WIRING DIAGRAMS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2283
NJ Certificate of Authorization Number
24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.





DUCT WAY NOTES:

1. CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS, OR AS SPECIFIED.
2. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAY #4@12" OC MIN 2. EXTEND 4' BEYOND ROAD EDGE.
3. MINIMUM COVER TO TOP OF CONCRETE ENVELOPE SHALL BE 24" [610mm].
4. INSTALL IN A 4'-0" MAX WIDTH TRENCH SIMILAR TO DETAIL Z ON C-306.


DUCT BANK DETAILS (AT)
NTS — TYP E-303




ELECTRICAL HANDHOLE DETAIL (AW)
NTS — C-201 E-303, C-202, C-203




PIEZOMETER CONDUIT DETAIL (CM)
NTS — TYP E-303




NOTES:

1. MAINTAIN SEPARATION OF POWER AND INSTRUMENTATION CONDUCTORS IN ELECTRIC HANDHOLE.
2. WHERE POWER AND INSTRUMENTATION CONDUCTORS CROSS THEY SHALL CROSS PERPENDICULAR TO EACH OTHER.
3. ELECTRICAL HAND HOLES SHALL BE LOCATED TO AVOID CLEANOUT MANHOLES.

ELECTRICAL HANDHOLE ORIENTATION DETAIL (AY)
NTS — C-201 E-303, C-202, C-203

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS APVD

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 08/14/15 | TDD | RJR | SGS | SGS | RJR |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD SGS |
| | | DCB 007.4 | | | | RJR SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

ELECTRICAL DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-303 |
| SHEET | 66 OF 66 |

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 7.4.1 **DCB Type:** Major(a)<br>**Effective Date:** 5/24/16 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** GW Extraction System – Revisions of Electrical to Replace Wells with Trenches | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description:**

DCB-007 series has documented changes to the contingent GW system design. Details related to the administrative basis for the change are provided in DCB 007.1 (issued to Entact on 6/12/14).

Several major changes have been issued in the past covering the change from Individual Wells to a Trench Drain system and the elimination of all wiring, pumps, and controls from the Entact Chromium Remedy scope of work.

This DCB 7.4.1 is being issued to address further changes in the SA-6 South design, including but not limited to:

- Elimination of Drop Structure at the junction of SA-6 / SA7
- Elimination of flow meter
- Conduit sizing changes

Drawings that are revised in this DCB are:

- C-201
- C-202
- C-203
- C-204
- C-304
- C-305
- C-306
- C-310
- E-301 (Not for Construction)
- E-302 (Not for Construction)
- E-303

**Clarification of Entact Scope of Work:**

- The provision of pumps, electrical wiring and instrumentation for the Contingent Groundwater system has been removed from Entact's scope of work.
- The installation of the FM and E&I conduits remain in Entact's scope, as depicted on the drawings.
- Running of conduit to the piezometers remains in Entact's scope. No instrumentation or wiring will be installed in the piezometers as part of the initial Chromium Remedy. The need and type of instrumentation will be determined based on the initial rounds and evaluation of the performance of the Contingent System.
- All E&I conduit will be, at a minimum, Sched 40 PVC meeting the National Electric Code.


**Clarification of Entact Scope of Work (continued):**


- SA-6/7 Meter / Drop structure has been eliminated and replaced with two 45 degree transitions. This detail needs to be reviewed with the fabricator and details shall be submitted to the engineer for approval.
- In the SA-6S east end, AmecFW had to relocate the last pull box and build in some bends. Therefore, the conduit was increased to 1.5 inch.
- The revised design calls for a minimum 24" of cover for direct burial of conduit.
- The E&I conduit from SA-7 to the SA-6S Pump Station is now shown as concrete encased (location shown on Drawing C-203, Detail AA shown on C-305).

DCB 7.2.2 will document changes to the SA-6 North Contingent GW Extraction system. DCB 7.2.2 will follow in a separate submittal.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** : Design changed due to changes in the recovery concept, permitted discharge location and site grading |
| | **Attachments:** ☑ Yes ☐ No<br>C-201, C-202, C-203, C-204, C-304, C-305, C-306, C-310, E-301 (Not IFC), E-302 (Not IFC), E-303 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>C-201, C-202, C-203, C-204, C-304, C-305, C-306, C-310, E-301 (Not IFC), E-302 (Not IFC), E-303 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 5/24/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☑ **Yes (b)** ☐ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON CASKETS.
10. INSTALL INSTRUMENTATION CONDUIT FOR PAIRED PIEZOMETERS READIED WITH PULL STRINGS FOR FUTURE INSTRUMENTATION CABLE INSTALLED BY OTHERS.
11. CONCRETE ENCASEMENT REQUIRED IF BURIAL DEPTH IS LESS THAN 24" OR OTHERWISE NOTED FOR E&I CONDUIT.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS APVD

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 4 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 3 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 2 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS |

DSGN TDD DR RJR CHK TDD APVD SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2529
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CADS\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 9:24 AM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 5 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 4 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SGS |
| DSGN | TDD | DR | RJR | CHK | TDD | APVD | SGS |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR35-C-202_Cont_GWE_Trench.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 9:26 AM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 5 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 4 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SHM |
| 1 | 06/06/14 | DCB 007 | TDD | APVD |
| DSGN | TDD | DR | RJR | CHK | TDD | APVD | SGS |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.
5. AT STATION 66+65, IF AVAILABLE, REUSE EXISTING ELECTRICAL PULL BOX.
6. FROM STATION 63+78 TO STATION 68+91 REMOVE ANY EXISTING WIRING REMAINING IN THE 2" E+I CONDUITS.
7. FORCE MAIN TO BE CAPPED AND TERMINATED INSIDE THE INSTALLED 4'x6'x4' DEEP JUNCTION STRUCTURE OUTSIDE THE GROUNDWATER TREATMENT PLANT.
8. 2" PVC POWER CONDUIT TO BE INSTALLED. WIRING TO BE INSTALLED BY OTHERS UNDER FUTURE CONTRACT. INSTALL NON-DEGRADABLE PULL STRINGS FOR FUTURE USE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

| NO. | DATE | REVISION | DR | CHK | APVD |
|---|---|---|---|---|---|
| 5 | 05/20/16 | DCB 007.4.1 | TDD | RJR | TDD |
| 4 | 08/14/15 | DCB 007.4 | TDD | SGS | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | RJR | SGS | SGS |
| 1 | 05/14/14 | DCB 007 | TDD | SHM | APVD |
| DSGN | | | TDD | BY | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC





NOTES:

1. USE THUNDERLINE LINK–SEAL TYPE LS 300–C FOR 2"ø OR 3" ø PIPELINES AND TYPE LS 425–C FOR 1"ø AND 1–1/4" PIPELINES OR EQUAL AT ALL MANHOLES AND STRUCTURES.
2. USE PRESSURE GAGE AND PROBE ON PIPELINES THAT SLOPE UPWARDS FROM STRUCTURES ONLY, BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK–JOINT FLEXIBLE MANHOLE SLEEVE OR KOR–N–SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.


## TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL (X, C–304 | C–304)

NTS





## JUNCTION MANHOLE #1 @ GWTP (AZ, C–204 | C–304)

NTS





## AIR RELEASE STATION (CF, C–204 | C–304)

NTS





## LEAK DETECTION STATION (CG, C–204 | C–304)

NTS





## DOUBLE CONTAINED ELBOW PIPE CLEANOUT (CH, C–204 | C–304)

NTS





## EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT (CI, C–204 | C–304)

NTS




## EXISTING 3" LEAK DETECTION STATION (CJ, C–204 | C–304)

NTS




## LINER ANCHOR TO CONCRETE STRUCTURE (CE, TYP C–304)

NTS

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND C–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

SAMUEL G. SHALLARD — NJ PROFESSIONAL ENGINEER — LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| DSGN | | DR | | |
| 4 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 3 | 08/05/15 | DCB 37.1 REVISED DETAIL CE | RJR | SGS |
| 2 | 07/28/15 | DCB 37 REVISED DETAIL CE | RJR | SGS |
| 1 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| | | REO | RJR | REO |

THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND DATA, IS CONTAINED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-304 |
| SHEET | 41 OF 66 |




EXTRACTION PIPE TRENCH TO SA6-N

NTS C-203 C-303 Y C-305





EXTRACTION PIPE TRENCH OVER CAP

(INSIDE SA-6S CAP AREA)

VALVE VAULT TO STA 61+32±

NTS C-201 C-202 C-203 AA C-305





EXTRACTION PIPE TRENCH

(OUTSIDE SA-6S CAP AREA)


STA. 61+32 TO STA. 63+72±

NTS C-201 C-202 C-203 AB C-305




EXTRACTION PIPE TRENCH WITH PIEZOMETER SERVICE AND INSTRUMENTATION OVER CAP

NTS C-201 C-202 Z C-305




OUTSIDE CAP OVER CAP

(SEE DETAIL CM ON E-303)

PIEZOMETER INSTRUMENTATION CONDUIT TRENCH

NTS C-201 C-203 AU C-305

NOTE:

1. PROVIDE CONCRETE ENCASEMENT IF CONDUIT IS LESS THAN 24-INCHES BELOW DEVELOPMENT GRADE.
2. INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 05/20/16 | TDD | REO | RJR | REO | SGS |
| 0 | 06/07/13 | TDD | REO | RJR | REO | SHM |

DCB 007 4.1
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018800


VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-305 |
| SHEET | 41 OF 66 |




PLAN





SECTION AA



SECTION BB

ELIMINATION OF STRUCTURE
STA 64+10
NTS


AZ
C-204 | C-306




NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.


PIEZOMETER DETAIL
NTS

AE
C-201 | C-306
C-202
C-203




EXISTING 3" FM TRENCH DETAIL
NTS STA 63+78 TO STA 68+91

CK
C-204 | C-306




TRENCH DETAIL
NTS

CL
C-204 | C-306

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 3 | 05/20/16 | REO | REO | RJR | REO | TDD | SGS |
| 2 | 08/14/15 | DCB 007.4.1 | | | | RJR | SGS |
| 1 | 02/13/15 | DCB 007.4 | | | | TDD | SGS |
| 0 | 06/07/13 | DCB 007.3 | | | | TDD | SHM |
| | | ISSUED FOR CONSTRUCTION | | | | TDD | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74±

NTS

C-203 C-204 | C-310 (CC)

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |

- SET MANHOLE BASE AND RISER SECTIONS. (NITC)
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

NOTE:

INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

SAMUEL G. SHALLARD

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 45307

| NO | DATE | DSGN | DR | CHK | APVD | REVISION | BY | APVD |
|---|---|---|---|---|---|---|---|---|
| 4 | 05/20/16 | TDD | | | | DCB 007.4.1 | TDD | SGS |
| 3 | 08/14/15 | | RJR | | | DCB 007.4 | RJR | SGS |
| 2 | 02/02/15 | | | RJR | | DCB 007.3 | TDD | SGS |
| 1 | 06/06/14 | | | | TDD | DCB 007 | TDD | SGS |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE SCH 40 PVC DB UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| DB | DIRECT BURIAL |
| EB | ENCASED BURIAL |
| EH | ELECTRIC HANDHOLE |
| EW | EXTRACTION WELL |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| TSP | TWISTED SHIELDED PAIR |
| TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| V | VOLTAGE |
| W | WIRE |

NOT FOR CONSTRUCTION

Fri, 20 May 2016

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 0 | 06/07/13 | TDD | RJR | SHM | APVD |
| 1 | 08/14/15 | | | | |
| 2 | 05/20/16 | | | | |

ISSUED FOR CONSTRUCTION

| BY | APVD |
|---|---|
| TDD | SGS |
| RJR | SGS |
| TDD | SHM |
| | SGS |

DCB 007.4.1
DCB 007.4

REVISION

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

ONE LINE DIAGRAM


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2828
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-301 |
| SHEET | 64 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Pr... HONEYWELL\JERSEY CITY\C...D\...-SA6-C3D\CAD\SA6-N\r...-S...-GW-E\r...\...Tr...\CR64-E-301 ONE LINE DIAGRAM d... PLOT DATE: Fr., 20 M... 2016 PLOT TIME: 3:22 PM




## EXTRACTION WELL PUMP CONTROL PANEL DETAIL (AO)

NTS

TYP E-302


NOTES:

1. ALL CONDUITS SHALL BE 1" PVC MINIMUM, UNLESS OTHERWISE SHOWN. WHEN DISTANCE IS LESS THAN 6 FEET, LIQUID TIGHT METAL FLEXIBLE CONDUIT MAY BE USED.
2. LOCATE THE PUMP MOTOR STARTER WITHIN 3' OF THE EXTRACTION WELL PUMP STATION.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

NOT PART OF THIS CONTRACT
ELECTRICAL POWER AND INSTRUMENTATION CONTROLS TO BE RE-EVALUATED FOLLOWING INITIAL DRAWDOWN AND TRENCH PERFORMANCE EVALUATION





## PUMP CONTROL PANEL WIRING DIAGRAM (AP)

NTS

TYPICAL FOR ONE LEVEL TRANSDUCER AND ONE EXTRACTION WELL PUMP CONTROL (SEE NOTE 3)

TYP E-302




## INVERTER DRIVE WIRING DIAGRAM (AQ)


NTS

TYP E-302

### FIELD TERMINAL STRIP CONNECTION SUMMARY

| | |
|---|---|
| GND | EARTH GROUND |
| 10 | RED TRANSDUCER WIRE |
| 11 | BLUE TRANSDUCER WIRE |
| 22 | MALE QD RECEPTACLE BROWN AND BLACK |
| 26 | MALE QD RECEPTACLE BLUE |
| 27 | MALE QD RECEPTACLE WHITE |
| 32 | FAULT CONTACT SUPPLY |
| 33 | FAULT CONTACT RETURN |

### FEMALE QUICK DISCONNECT PLUG




## PLUG & TERMINAL STRIP WIRING DIAGRAM (AR)

NTS

TYP E-302

NOT FOR CONSTRUCTION

Fri, 20 May 2016

| NO. | DATE | DR | CHK | APVD |
|---|---|---|---|---|
| DSGN | TDD | RJR | SHM | SHM |
| 2 | 05/20/16 | | | TDD |
| 1 | 08/14/15 | | | RJR |
| 0 | 06/07/13 | | | TDD |

ISSUED FOR CONSTRUCTION

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

WIRING DIAGRAMS


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689-2229
NJ Certificate of Authorization Number 24GA28010900

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |





## DUCT WAY NOTES:

1. ENCASED BURIAL REQUIRED IF THE COVER DEPTH IS LESS THAN 24" OR OTHERWISE SPECIFIED
2. CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS, OR AS SPECIFIED.
3. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAY WITH LESS THAN 24" OF COVER #4@12" OC MIN 2. EXTEND 4' BEYOND ROAD EDGE.
4. ~~CONCRETE ENVELOPE SHALL BE 24" [610mm].~~
5. INSTALL IN A 4'-0" MAX WIDTH TRENCH SIMILAR TO DETAIL Z ON C-306.


DUCT BANK DETAILS (AT)
NTS
C-201 | E-303
C-203




ELECTRICAL HANDHOLE DETAIL (AW)
NTS
C-201 | E-303
C-202
C-203




PIEZOMETER CONDUIT DETAIL (CM)
NTS
C-305 | E-303




ELECTRICAL HANDHOLE ORIENTATION DETAIL (AY)
NTS
C-201 | E-303
C-202
C-203

ELECTRICAL NOTES:

1. MAINTAIN SEPARATION OF POWER AND INSTRUMENTATION CONDUCTORS IN ELECTRIC HANDHOLE.
2. WHERE POWER AND INSTRUMENTATION CONDUCTORS CROSS THEY SHALL CROSS PERPENDICULAR TO EACH OTHER.
3. ELECTRICAL HAND HOLES SHALL BE LOCATED TO AVOID CLEANOUT MANHOLES.
4. INSTALL ELECTRICAL HANDHOLES AT MAXIMUM 250 FOOT SPACING.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 05/20/16 | TDD | RJR | SGS | SGS |
| 1 | 06/14/15 | RJR | TDD | SGS | |
| 0 | 06/07/13 | TDD | RJR | SGS | |

REVISION
ISSUED FOR CONSTRUCTION
DCB 007.4.1
DCB 007.4

BY APVD

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

ELECTRICAL DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-303 |
| SHEET | 66 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR66-E-303 Electrical Details.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 8:50 AM

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 23 OF 25**

- **Declaration #5 Part 1**

**Attachments A – P (Part 1)**

**IN THE UNITED STATES DISTRICT COURT**
**FOR THE DISTRICT OF NEW JERSEY**

| | |
|---|---|
| JERSEY CITY INCINERATOR AUTHORITY *et al.*,<br><br>Plaintiffs,<br><br>*v.*<br><br>HONEYWELL INTERNATIONAL INC., *et al.*<br><br>Defendants. | CHROMIUM REMEDY SA-6 DECLARATION #5<br><br>Civil Action No. 05-5993 (Consolidated with Docket No. 05-5955 under Docket No. 95-2097 (JLL))<br><br>Civil Action No. 06-22 (Consolidated with Docket No. 05-5955 under Docket. No. 95-2097 (JLL)) |

## Study Area 6 North Consent Decree Declaration #5

On August 14, 2012, the United States District Court for the District of New Jersey entered the First Amended Consent Decree Regarding Remediation and Redevelopment of Study Area 6 North ("SA-6 North Consent Decree") and the First Amended Consent Decree Regarding Remediation and Redevelopment of Study Area South ("SA-6 South Consent Decree") (referred to together as "SA-6 Consent Decrees"). Pursuant to Article III, Honeywell may file one or more Declarations showing compliance with the SA-6 Consent Decrees. The initial SA-6 South Consent Decree Declaration ("Declaration #1) was filed by Honeywell with the consent of the other parties to memorialize Honeywell's partial compliance with the terms of the SA-6 South Consent Decree on March 18, 2016, ECF No. 1403-1. A second SA-6 South Declaration (Declaration #2) was filed by Honeywell on January 30, 2017, ECF No. 1464-1 with the consent of the other parties to memorialize partial compliance with the terms of the SA-6 South Consent Decree completed subsequent to Declaration #1. The initial SA-6 North Consent Decree Declaration ("Declaration #3") was filed by Honeywell with the consent of the other parties to memorialize Honeywell's partial compliance with the terms of the SA-6 North Consent Decree on May 9, 2017, ECF No. 1484. A second SA-6 North Declaration ("Declaration #4") was filed by Honeywell on June 21, 2017, ECF No. 1487 with the consent of the other parties to memorialize partial compliance with the terms of the SA-6 North Consent Decree completed subsequent to Declaration #3. Declaration #5 is hereby filed by Honeywell with the consent of the other parties to memorialize partial compliance with the terms of the SA-6 Consent Decrees that were not included in Declarations #1, #2, #3 and #4.

We, the undersigned, declare as follows:

1. William J. Hague is Director of Remediation Design and Construction for Honeywell International Inc. ("Honeywell") for Study Area 6 North (SA-6 North) New Jersey Department of Environmental Protection (NJDEP) Sites 087 and 088 and Study Area 6 (SA-6 South) NJDEP Sites 073, 124, 125, 134, 140 and 163. Mr. Hague has direct responsibility on behalf of Honeywell for the management of remediation construction activities at SA-6 North and South related to the implementation of the Chromium Remedy as defined in Article III of the SA-6 Consent Decrees.

2. Remediation and site restoration activities documented in this Declaration were performed in accordance with the SA-6 Consent Decrees, the NJDEP Technical Requirements for Site Remediation, the NJDEP-approved *Remedial Action Selection Report/Remedial Action Work Plan* to address chromium contamination at SA-6 North, dated January 2008 and amended in February 2008; the NJDEP-approved *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan for Chromium* to address chromium contamination at SA-6 South, dated December 23, 2008, the NJDEP- approved *Supplemental Remedial Investigation Report, Remedial Action Selection Report, and Remedial Action Work Plan*, to address chromium contamination at Site 163 only, dated, May 18, 2012 (collectively referred to as the RAWPs), the Final – Issued for Construction ("IFC") Chromium Remedy 100% Design Report for Study Area 6 North & Study Area 6 South dated June 28, 2013 ("Final 100% Design"); sixteen field changes that materially affected the Final 100% Design (DC 2013-8-14: HB Wall – "Hydraulic Barrier/Surcharge Relocation adjacent to 72 inch FM SA-6 North," DC 2014-7-28 – "Revised Monitoring Well Abandonment Plan Tables," DC 2014-11-20 – "GW Extraction System (North)," DC 2015-2-12 – "GW Extraction System (South)," DC 2015-6-18 (North) – "SA-6 North, Site 087 In-situ Injections," DC 2015-9-17 – "Planting Soil Specifications," DC 2015-9-28 – "Site 163 Excavation," DC 2015-9-03 – "GW Extraction System – Revisions of Electrical to Replace Wells with Trenches," DC 2015-10-22 – "Move Western Limit of Stratum D Repair," DC 2016-3-21 – " Planting Soil Specifications, Nature's Choice Only," DC 2016-4-20 – "Planting Soil Specifications," DC 2016-05-06 – "Temporary Construction Road in SA-6 South Cap," DC 2016-11-09 – "Site Restoration," DC 2016-12-20 – "Contingent GW E&I Revisions," DC September 2016-North – "Interim Grading SA-6N," and DC September 2016-South – "Cap Final Grading and Development Final Grading and Restoration"), and fifteen field changes that were minor in nature (DC 2014-5-19 – "Degen Deferred Area," DC 2014-12-23 – "Site 163 Deferred Areas," DC 2015-4-30 – "JCIA Trash Pit Closure," DC 2015-6-05 – "SA-6 South Contingent GW Piezometer Locations," DC 2015-10-02 – "Warning Tape above Root Barrier," DC 2015-11-12 – "Final Grade Revisions," DC 2016-2-02 – "Increase Grade 0.25' In Landscape Area," DC 2016-2-22 – "Geomembrane Subgrade Revisions," DC 2016-2-25 – "Barrier Wall & SCB Wall Plan

and Profile," DC 2016-4-15 – "Final Grade Revisions," DC 2016-5-3 – "Planting Soil Gradations USDA Clarification," DC 2016-5-11 – "SA-6 North Interim Grade Revisions," DC 2016-5-20 – "Geomembrane Subgrade Revisions – Pump Station #1 Corridor," DC 2016-6-06 – "GW Extraction System – FM and E&I," and DC 2016-7-14 – "North Cap – Field Engineered Subgrade Adjustments") referred to herein as "Design Changes" and included as Attachment P, and with the continued oversight and supervision of the appointed Special Master. The Final 100% Design, including Design Drawings and Technical Specifications, was developed consistent with the SA-6 Consent Decrees and NJDEP-approved RAWPs and was approved by all Parties. On June 12, 2013, the Special Master approved the SA-6 100% Design for submittal to the Court so that the proposed implementation of the remedy could start on time, subject to Honeywell's confirmation regarding several issues. On June 28, 2013, Honeywell submitted the Final 100% Design to the Court (ECF No. 1176), and the Court entered the Final 100% Design on July 9, 2013 (ECF No. 1180).

3. The elements of the remedy that are the subject of this Declaration were substantially completed between June 2013 and December 2016. The timeframe of this Declaration # 5 overlaps with that of previously entered Declaration #1 (ECF No. 1403-1), Declaration #2 (ECF No. 1464-1), Declaration #3 (ECF No. 1484) and Declaration #4 (ECF No.1487) because the Declarations are developed based upon the completion of major remediation components and several of the Declaration #5 remediation components (such as monitoring well installation/abandonment and in-situ treatment) required long durations which were started soon after mobilization in June 2013.

4. In five areas, the work to implement the Chromium Remedy required by the SA-6 Consent Decrees was deferred with the approval of the Parties and the Special Master, based on field conditions. After the Chromium Remedy has been fully implemented in the Deferred Areas, a future Declaration will be submitted to document the Deferred Areas Chromium Remedy work.

5. To implement the requirements of the SA-6 Consent Decrees, Honeywell retained AMEC Environment and Infrastructure, Inc. (now Amec Foster Wheeler Environment & Infrastructure, Inc., "Amec Foster Wheeler") to design and coordinate the construction activities related to the Chromium Remedy of SA-6 North and South. Amec Foster Wheeler is the Engineer of Record for the design and implementation of construction activities related to the Chromium Remedy of SA-6 North and South. Amec Foster Wheeler engaged Entact, LLC ("Entact") to perform the construction. Entact was responsible for implementing the SA-6 North and South construction in accordance with

the Final 100% Design and Design Changes. Entact reported directly to Amec Foster Wheeler and provided the final construction details, including Record Drawings, upon project completion. Mr. Joseph T. Clifford is a licensed Professional Engineer in the State of New Jersey (Professional Engineer, NJ, GE38067), a Principal Engineer at Amec Foster Wheeler and is the engineer at Amec Foster Wheeler with primary responsibility for management of the design and construction coordination activities at SA-6 North and South.

6. It is our professional opinion that the data and information set forth for the specific work elements noted in and attached to this Declaration were performed consistent with the Final 100% Design and Design Changes.

7. Declaration #5 pertains to the following elements of the SA-6 Chromium Remedy:

I. SA-6 South 60 Kellogg and Site 163 Excavations;
II. SA-6 North and South Contingent Groundwater Force Main, Electrical and Piezometers;
III. SA-6 North and South Gas Vent Systems;
IV. SA-6 North and South Deferred Areas;
V. SA-6 North and South In-situ Treatment;
VI. SA-6 North Meadow Mat Repair near Trash Pit;
VII. SA-6 North and South Cap Cover Soils;
VIII. SA-6 North and South Development Area Grading;
IX. SA-6 North and South Soil Erosion and Sediment Control;
X. SA-6 North and South Monitoring Well Abandonment;
XI. SA-6 South Monitoring Well Installation; and
XII. SA-6 North and South Institutional Controls.

Further details related to elements I-XII are provided below. Supporting documentation is provided in the Attachments. Excluding the Deferred Areas and installation of wiring for the contingent groundwater collection trench, construction activities in accordance with the Final 100% Design and Design Changes related to the remediation of both SA-6 North South are considered complete. Honeywell still needs to submit a report on the shallow groundwater remedy for the Development AOC, pursuant to paragraph 70 of the Study Area 6 South Consent Decree, and to implement required institutional controls (e.g., deed notices and conservation restrictions). The contingent groundwater collection trench, force mains, and electrical and instrumentation (E&I) conduits associated with the groundwater remedy have been installed. The installation of associated wiring was completed in the second quarter of 2017. The pumps will be stored on-site and installed if the long term groundwater monitoring program indicates the need for pumping.

Remedial Action Reports for both Sites are being prepared in accordance with the NJDEP Technical Requirements for Site Remediation (TRSR), (New Jersey Administrative Code [N.J.A.C.] 7:26E-5.7) for submission to NJDEP, the Parties, and the Court. The project is now considered to be in the Long Term Monitoring phase.

Honeywell is preparing final Construction Completion Reports ("CCR") for Study Area 6 North and for Study Area 6 South to document the completion of the Study Area 6 North and South Remedy, except for the deferred areas, consistent with requirements of the SA-6 Consent Decrees. The CCRs will include the final Record Drawings. Once approved, each CCR will be entered with the Court, along with a Consent Order explaining that the CCR supersedes the 100% Design, pursuant to paragraph 5 of the Consent Order Entering Consolidated 100% Design for Study Area 6 North and Study Area 6 South, *Jersey City Municipal Utilities Auth., et al., v. Honeywell*, D.N.J., Consol. Cases, Civ. No. 95-2097, July 9, 2013, ECF No. 1180. Honeywell will prepare an additional CCR upon completion of each of the deferred areas. Once approved, each CCR for a deferred area will be submitted by Honeywell to the Court along with an appropriate Consent Order for approval and entry. The CCR, along with its Consent Order and attachments, "shall supplant" the 100% Design documentation submitted to the Court in July 2013 with ECF No. 1180 "for all further purposes referencing the 100% Design under the Study Area 6 North Consent Decree and the Study Area 6 South Consent Decree and any amendments thereto." *See* ECF No. 1180, para. 5.

Thus, all future activity and any related need for final Record Drawing documentation of the Chromium Remedies at Study Area 6 North and Study Area 6 South will be based on the CCRs approved and entered by the Court pursuant to the requirements of the Consent Order Entering Consolidated 100% Design for Study Area 6 North and Study Area 6 South, ECF No. 1180, and the LTMP. Future versions of the LTMP will reference the CCRs, along with its Consent Order and attachments, for each aspect of the Chromium Remedies at Study Area 6 North and Study Area 6 South.

I. SA-6 South 60 Kellogg and Site 163 Excavations. Following demolition of the 60 Kellogg Street building raised slab, Amec Foster Wheeler personnel collected a soil sample biased to a greenish discoloration in surficial soils identified between timber piles that formerly supported the 60 Kellogg Street building. This initial soil sample confirmed the presence of COPR and resulted in a shallow excavation plan to remove these soils. On June 2, 2016, the excavation was conducted to depths ranging from approximately 2.9 ft to 4.2 ft below ground surface ("bgs"). The bottom and sides of the excavation at the final limits were visually inspected by Amec Foster

Wheeler personnel. All of the original greenish discoloration was removed but some whitish material was observed in several sidewall locations. The excavation was subsequently extended to approximately 14 ft by 14 ft in width and length to remove additional soil exhibiting whitish discolorations. Five soil samples were collected from the excavation: one from each sidewall and one from the bottom of the excavation. Sidewall samples were biased to include residual whitish material where observed. The bottom sample was located in the area where additional suspect material was also observed during excavation. All hexavalent chromium results were less than 20 mg/kg. An excavation completion certification was submitted to the Special Master and Parties for review on June 28, 2016 and is included as Attachment A-1. A copy of the Maser Excavation Table and a detailed Bottom of Excavation Drawing are included in Attachment A-2. The 60 Kellogg excavation is shown on the updated Maser Excavation Plan included in Attachment B-1.

In the Final 100% Design, remediation at Site 163 included a combination of shallow excavation to a depth of four feet bgs and in-situ injection treatment in chromium-impacted soils deeper than four feet bgs. The Site 163 shallow excavation is addressed in Declaration #1. Following the initial in-situ treatment event there was a technical disagreement among the parties of the efficacy of treatment of chromium-impacted soils at varying depths. Therefore, an agreement regarding additional remediation was reached between the Parties and documented in DC 2015-9-28.

DC 2015-9-28 modified the excavation depths in select areas of Site 163 and is addressed in Declaration #1. Chromium-impacted soils that were deeper than four feet bgs in the future residential area of Site 163 were excavated. In the non-residential area of Site 163, chromium-impacted soils deeper than four feet bgs were left in place and pursuant to the SA-6 South Consent Decree, paragraph 61, ownership of the area will be transferred to the City of Jersey City and a deed notice and conservation restriction will be implemented. The Site 163 deed noticed area where chromium-impacted soils remain in place is shown on Figure 5 in Attachment G.

To accomplish the Site 163 additional excavation, temporary sheeting was installed and a phased excavation was conducted to the design depths identified in DC 2015-9-28. An e-mail certification of excavation

completion was submitted to the Parties for review on April 25, 2016, and an e-mail response to verbal questions was provided on May 5, 2016. The certification and e-mail response are included as Attachment C-1. A copy of the Maser Excavation table and a detailed bottom of Excavation Drawing are included in Attachment C-2. The excavation limits are shown on the updated Maser Excavation Plan (Attachment B-1).

Declaration #3 included e-mail certifications of excavation completion for the SA-6 North excavation areas. For consistency, e-mail certifications for the SA-6 South excavation are included in this Declaration #5 in Attachment B-2. As previously noted in Declaration No. 1 for SA-6 South, following the excavation of distinct portions (or cells) of the excavation, the horizontal and vertical extents of the completed cells were surveyed and Honeywell submitted documentation confirming the completion of excavation. In their submittals, Honeywell summarized the activities undertaken to complete the excavation of the referenced cells and included the following statement from Honeywell's Engineer, Amec Foster Wheeler: "Amec inspectors certify to the best of our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling had been met." Honeywell also noted, where applicable/appropriate, that the excavation in the referenced cells terminated by depth in the Stratum D and provided an Excavation Bottom Map that included the surveyed post-excavation bottom elevations for the cell(s). Honeywell further requested an acknowledgement that the Special Master was in receipt of the email and accompanying information in order that Honeywell could proceed with backfill. The Special Master monitored the excavation pursuant to the First Amended Consent Decree Regarding Remediation and Redevelopment Of Study Area 6 North ("SA-6 North Consent Decree") and the First Amended Consent Decree Regarding Remediation And Redevelopment Of Study Area South ("SA-6 South Consent Decree"). At a Special Master All Parties meeting in April 2014, the parties discussed the process for acknowledging Honeywell's notification that the contractor was ready to backfill a certain portion of excavated cells; and an e-mail from then-counsel for the Special Master, Kevin J. Coakley, Esq., (included in Attachment B-2) outlined the procedure that would be followed. At the meeting, and in Mr. Coakley's email, the parties also acknowledged Honeywell's intention to backfill Cells 44-56.

II. SA-6 North and South Contingent Groundwater Force Main, Electrical and Piezometers. Details on the contingent groundwater collection trenches were provided in Declaration #2 (SA-6 South) and Declaration #4 (SA-6 North). This Declaration provides the Record Drawings, in Attachment D, for the installation of the effluent force mains and electrical and instrumentation ("E&I") conduit conducted pursuant to the Final 100% Design and DC 2014-11-20, DC 2015-2-12, DC 2015-9-03, DC 2016-6-6, and DC 2016-12-20. The force main discharge point was changed from the JCMUA grit chamber to the Groundwater Treatment Plant ("GWTP"). The force mains and E&I conduits and associated structures were installed from the Pump Station manholes to the GWTP by Entact. Connection at the treatment plant and piping within the GWTP were performed by Brownfield Science and Technology Inc. (BSTI). The Entact Record Drawings indicate the final installed locations for the force mains and conduit (Attachment D-1). The BSTI Record Drawing shows the connection and piping within the GWTP (Attachment D-2).

Declaration #2 identifies the deferral of certain components of the contingent groundwater collection trenches until completion of the cap and stabilization of the groundwater system. The previously deferred components of the groundwater collection trenches are now complete, including the installation of the pumps, starter panels, level controls, flow meter instrumentation and automated shutdown control components in June 2017. The Contingent Groundwater Extraction System will be operated, as needed, in accordance with the final LTMP.

The location of paired piezometers to be used for evaluation of groundwater gradients across the barrier walls were included in Declaration #2 for SA-6 South and Declaration # 4 for SA-6 North. Declaration #2 (SA-6 South) and Declaration #4 (SA-6 North) included figures showing the piezometer design locations. In this Declaration, Honeywell is providing figures that show the as-built locations for the paired piezometers. Minor relocations were required to account for development details such as sidewalk and road locations (DC 2015-06-05). Tables showing screen elevations are included in the figure for each piezometer set. The figures are included in Attachment E.

III. SA-6 North and South Gas Vent Systems. The gas vent system for each cap area includes a geocomposite layer installed below the geomembrane, an 8-

inch diameter collection pipe running the east-west length of the cap, and vents. The limits of the gas vent geocomposite layer, plan location of the collection pipe, and location of the vents were provided in Declaration #2 (SA-6 South) and Declaration #4 (SA-6 North). The Record Drawings were modified to include the gas vent coordinates (see Attachment F).

IV. SA-6 North and South Deferred Areas. Portions of the following areas were designated as Deferred Areas.

- SA-6 North EA-1 along Route 440
- SA-6 North EA-2/3 along Route 440
- SA-6 North Shallow Excavation in Former Treatment Area 7
- SA-6 South Route 440
- SA-6 South Bulkhead

The Deferred Areas are localized areas that were identified for remediation by excavation in the approved 100% Design. SA-6 North EA-1 and EA-2/3, and a portion of SA-6 South along Route 440 were deferred due to their proximity to the old PSE&G 24 inch ductile iron/leaded joint gas line. These areas are referred to as the Route 440 Right-of-Way Deferred Areas in the CCRs for SA-6 North and South.

Excavation adjacent to the SA-6 South Bulkhead, referred to in the SA-6 South CCR as the Site 073 Bulkhead Deferred Area, was deferred due to the poor condition of the bulkhead combined with extensive concrete and isolated deep excavation (DC 2014-5-19, DC 2014-12-23). It was agreed upon with the parties to defer this area pending installation of the new bulkhead. The planned limits of the Deferred Areas are shown in Attachment G. The Deferred Areas will be subject to a Deed Notice until these areas are remediated, at which time the Deed Notices will be terminated.

V. SA-6 North and South In-situ Treatment. In-situ Treatment was implemented at the locations listed below. A General Remedy Plan showing all in-situ locations is included in Attachment H. Treatment Area specific figures are also included in the attachment.

- SA-6 South Site 163 – Site 163 was excavated in lieu of in-situ treatment as discussed in Section 7.I of this Declaration.
- SA-6 North Treatment Area 7 – Honeywell implemented in-situ injections in TA-7 in June 2013 and a 3-Year post-treatment performance assessment sampling event in June 2016 in accordance with a Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 2013 (“TA-7 & TA-8 Revised WP”). Eight soil samples were collected during the 3-

Year sampling event (four shallow samples and four deep samples). The samples were analyzed for hexavalent chromium using United States Environmental Protection Agency (USEPA) Method 7199 and indicated that seven of the eight post-treatment soils samples were below 20 mg/kg hexavalent chromium. One recalcitrant sample in the shallow portion of TA-7 exceeded 20 mg/kg hexavalent chromium. Correspondence provided to all Parties by Honeywell dated August 16, 2016 indicated Honeywell's proposal to excavate the shallow soils following relocation of the fueling system in this area by JCMUA (DN #10 as shown in Attachment G). In the meantime, Honeywell will establish a deed notice for this area. Once the shallow soils have been excavated, the deed notice will be terminated. This area lies within the Bayfront Development Block 6 and will not be impacted by Development activities.

- SA-6 North Treatment Area 8 – Injections and 3-Year sampling in TA-8 were performed concurrently with TA-7 in accordance with the TA-7 & TA-8 Revised WP. Eight soil samples were collected during the 3-Year sampling event (four shallow samples and four deep samples). The samples were analyzed for hexavalent chromium using USEPA Method 7199 and indicated that TA-8 has been remediated to below 20 mg/kg hexavalent chromium.
- SA-6 North Treatment Area 10 – In-situ treatment area 10 (TA-10) is located immediately proximate to and north of the hydraulic barrier and overlies a section of the 72-inch diameter force main (FM). Because of the proximity of the FM, excavation of impacted soils in TA-10 would potentially result in structurally impacting the FM during removal of the impacted soils. Therefore, Honeywell implemented an in-situ injection program in the portion of TA-10 (subarea TA-10-1) that lies north of the northern curb line of the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project (DC 2015-06-18 (North). The remainder of the TA-10 area, a portion of subarea TA-10-1 that lies south of the northern curb line of the future Stegman Boulevard and subareas TA-10-2 and TA-10-3, will be capped by Stegman Boulevard and be subject to a Deed Notice and Conservation Restriction (DN #7 as shown in Attachment G). Honeywell conducted an injection event at TA-10-1 between August and September 2015 and 6-Month post-treatment soil sampling was conducted in March 2016 in accordance with an Updated Work Plan for In-Situ Treatment of Chromium Impacted Soils, dated August 2015 (Updated Work Plan). The 6-Month post-treatment soil samples were analyzed for hexavalent chromium using USEPA Method 7199 and indicated that the majority of areas treated were now below 20 mg/kg for hexavalent chromium, as detailed in a May 6, 2016 technical

memorandum. However, 5 out of 20 sample points exceeded 20 mg/kg; therefore, Honeywell implemented a supplemental Calcium Polysulfide ("CAPS") injection program to further remediate soils in these areas in accordance with a July 11, 2016 submittal entitled, Additional In-Situ Injection of Calcium Polysulfide for Treatment of Hexavalent Chromium Impacted Soils, and a technical memorandum entitled, Proposed In-Situ Treatment Event for Remaining Hexavalent Chromium Impacted Soils – Treatment Area 10-1 SA-6 North, dated July 8, 2016 (Proposed Implementation Plan). Modifications were made to the initial approach which included a slower and prolonged injection delivery approach over the course of several weeks through injection wells installed in the area. Honeywell performed the subsequent modified slower and prolonged re-injection approach at TA-10-1 between August and October 2016. Twenty post-treatment soil samples were subsequently collected on December 5, 2016. The 6-Month post-treatment soil samples were analyzed for hexavalent chromium using USEPA Method 7199 and indicated that nineteen of the twenty samples were below 20 mg/kg hexavalent chromium, but one recalcitrant sample exceeded the 20 mg/kg hexavalent chromium criteria. Honeywell implemented an additional slower and prolonged injection event in the exceedance location on January 26, 2017 and February 2, 2017 in accordance with a technical memorandum titled, Summary of Additional In-Situ Injection of Calcium Polysulfide for Treatment of Hexavalent Chromium Impacted Soils, SA-6 North, TA-10-1, dated January 12, 2017. Post-treatment re-sampling at the re-injection location occurred in March 2017 and the results showed that the one soil sample collected in December 2016 that exceeded 20 mg/kg hexavalent chromium is now below 20 mg/kg hexavalent chromium. TA-10 location and limits are shown in Attachment H. TA-10 limits were modified as a result of DC 2013-8-14 related to the hydraulic barrier wall alignment.

VI. SA-6 North Meadow Mat Repair near Trash Pit. The former JCIA Incinerator pit penetrates through the Stratum D. The 100% Design Report indicated that "it has been determined that the Stratum D (Meadow Mat) layer is absent in a 25-30 ft. halo around the JCIA Trash Pit. It is believed that portions of the Stratum D were removed during the construction of the trash pit." To mitigate this condition, measures were implemented to repair the Stratum D around the trash pit, north of the barrier wall alignment. The repair was conducted by excavating the area to elevation 3. Vinyl sheetpile was then driven from elevation 3 on an alignment that was approximately 25 ft. outside of the exterior walls of the main trash pit. The limits of Stratum D north of the Barrier Wall were interpreted based on prior GeoProbe and investigation

borings. The alignment was selected to intersect the Stratum D. The sheetpile was driven approximately 3 ft. into the Stratum D. The final alignment deviated slightly from the initial design alignment at some locations to avoid timber piles that were encountered along the alignment (in accordance with DC 2015-10-22). A geosynthetic clay blanket was then placed over the area at elevation 3 between the vinyl sheetpile, trash pit and barrier wall (DC 2015-04-30). The Record Drawings for the Stratum D repair is included in Attachment I.

After completion of Stratum D repairs, but prior to backfilling inside and around the trash pit, the concrete walls south of the barrier wall (under the cap and inside the containment) were penetrated ("breached or punctured") below the groundwater table to reduce the potential for perched groundwater in the pit under the cap.

VII. SA-6 North and South Cap Cover Soils. Protective cover soil, Horizon C, Horizon B, Horizon A and structural fill under roadways composed of Clean Fill meeting the NJ Residential standards were placed above the cap geosynthetics in accordance with the 100% Design and the following Design Changes:

- DC September 2016-South
- DC 2015-9-17
- DC 2016-3-21
- DC 2016-4-20
- DC September 2016-North
- DC 2016-04-15
- DC 2016-05-03
- DC 2015-11-12

The average thickness of the cap cover soils, and minimum thickness of the cap cover soils, meet the requirements of Section 56 (c) of the SA-6 North Consent Decree and Section 65 (c) of the SA-6 South Consent Decree, namely, an average of 36-inches or more, with a minimum of 24-inches of protective cover soil above the cap warning layer. To deter root penetration in planned landscape areas, a bright white colored woven geotextile root barrier was installed above the first 12-inches of protective cover soil across the entire cap area and then covered by the Horizon A-C soils as required by the Final 100% Design. Prior to the placement of the Horizon A-C soils warning tape was placed on top of the root barrier pursuant to DC 2015-10-02. Registered surveys of the top of the root barrier are included in Attachment J for both the North and South cap areas. The surveyed elevations of the installed root barrier

are critical to any future ground disturbance work as it provides a reference point for potential supplemental requirements which are to be implemented as described in the LTMP. Structural Fill under Roadways was placed in future roadways above the protective cover soil. Structural fill Record Drawings for the SA-6 North and SA-6 South caps are included in Attachment K. The placement of the root barrier, warning tape and structural fill under roadways meets the provisions of the Open Space Design Standards (OSDS) Appendix L to the Final 100% Design.

In the landscape areas, 6 inches of Horizon C were placed, compacted, and compaction tested to verify compliance with the specification. Following approval of the 6-inch compacted layer the remainder of the Horizon C, B and A soils were placed in accordance with the Final 100% Design and Design Changes DC 2015-9-17, DC 2015-11-12, DC 2016-3-21, DC 2016-04-15, DC 2016-4-20, DC 2016-05-03, DC September 2016-South and DC September 2016-North. The total depth and type of Horizon soil varied based on the planting classification/depth. SA-6 North and South cap compaction logs for structural fill and 6-inches of Horizon C are included in Attachment L.

The elevations of the cover soils and root barrier were recorded at the Construction Control Grid nodes. The SA-6 North Open Space Cap Area – Construction Control Grid Summary Table and the SA-6 South Open Space Cap Area – Construction Control Grid Summary Table document the elevation readings and cover soil type thicknesses to confirm that the minimum specified thickness requirements were met in the cap areas. The “North Cap Final Grading Plan” and “South Cap Topsoil Grading Plan” are registered surveys of the surface grades following placement of Horizon A soil. The SA-6 North and South Construction Control Grid Summary tables are included in this Declaration as Attachment M-1. The Grading Plans are included as Attachment M-2.

Horizon A topsoil, as approved by the Parties, was placed to the remediation design grades. The cap area and adjacent slopes were hydro-seeded with a seed mix prepared in accordance with the Standards for Soil Erosion and Sediment Control in New Jersey. Horizon A soil was placed over the entirety of the Open Space Areas, including the future roadway corridors, with the exception of the future B Street on SA-6 South and the future Riverside Drive on SA-6 North. In the Final 100% Design, SA-6 South B Street was to be restored with topsoil and grass. Honeywell modified B Street into a temporary roadway by DC 2016-05-06 to provide access for site inspections, long term monitoring

activities, and general maintenance. Construction details for the SA-6 South B Street temporary roadway were identified in DC 2016-05-06 and approved by the Parties. The temporary roadway on the future Riverside Drive on SA-6 North was installed consistent with the Final 100% Design. The temporary road locations are shown on the Maser finished grade drawings (Attachment M-2) and the SA-6 North and South Restoration Plans, included in Attachments N-4.

VIII. SA-6 North and South Development Area Grading

- SA-6 North. The SA-6 North Chromium Remedy designated isolated Additional Excavation Areas outside of the limits of the cap portion of the remedy. These areas are located within the external boundaries of the SA-6 North Non-Chromium Remedy. The IFC Chromium Remedy restoration plan also indicated restoration of areas occupied by the former JCIA entity and an area of soil/debris piles west of the JCMUA digester structures. A revised Restoration Drawing (CN-127) has been issued as part of DC 2016-11-09 to indicate the limits of restoration to be performed in SA-6 North. There are three Restoration surface finishes: asphalt paving, 1 ft. of clean fill including topsoil and seeding, and installation of a geotextile demarcation layer and 6 inches of clean crushed stone. The As-Built limits of each area are shown in Attachment N-4. Table 1 – Stone Cover Thickness Summary for SA-6 North provides survey data documenting crushed stone thickness in areas where the 6 inch crushed stone cover was placed over historic fill. The table and accompanying figure are included in Attachment N-1.

  A survey grid was established over the JCIA crushed stone area. Elevations were taken at the nodes and tabulated in Table 1 – Stone Cover Thickness Summary for SA-6 North to document compliance with the design requirements. The SA-6 North "As-Built Restoration Plan" drawing is included in Attachment N-4. The drawing titled "Final Grading for Excavation Areas" is a registered survey of the surface of the Clean Fill and is included in Attachment N-3.

- SA-6 South. The Development area was covered in its entirety with a geotextile demarcation layer and a minimum of 6 inches of clean fill (crushed stone or Dense Graded Aggregate) with the exception of the temporary slope that transitions from the vegetated Open Space AOC cap to the post remediation grades in the Development Area. A survey grid was also established over the area. Elevations were taken at the nodes and tabulated in Table 1 – Stone Cover Thickness Summary for SA-6 South to

document compliance with the design requirements. The table and accompanying figure are included in Attachment N-2. The SA-6 South "As-Built Restoration Plan" drawing is included in Attachment N-4. The drawing titled "SA-6 South Stone Layer" is a registered survey of the surface of the Clean Fill and is included in Attachment N-3.

IX. SA-6 North and South Soil Erosion and Sediment Control. Post-Construction Sedimentation and Erosion Control measures including final seeding were implemented in accordance with the approved 100% Design, DC September 2016-North, DC September 2016-South, NJ Sedimentation and Erosion Control manual, and the Sedimentation and Control plan approved by Hudson, Essex, and Passaic Soil Conservation District on May 16, 2013. The IFC designs for SA-6 North and SA-6 South were amended to add a toe drain where the cap slope meets existing grade on SA-7 (DC September 2016-North, DC September 2016-South). The toe drain and associated check drains, and other controls left in place at the end of the work are shown in Attachment N-4. Erosion control mat (or "blanket") was also placed over the more steeply sloped areas of the cap. A drawing showing the location of the erosion control mat on the SA-6 North and South caps is included in Attachment Q. Where these measures were implemented, perimeter silt fence was reduced or eliminated. The installed measures are considered to be more resilient than the 100% Design and satisfy the SESC permit requirements. Honeywell will maintain these controls in accordance with the Long Term Monitoring Plan.

X. SA-6 North and South Monitoring Well Abandonment. The Monitoring Well Abandonment Plan (MWAP) in the 100% Design and DC 2014-7-28 established the monitoring wells and piezometers that would be abandoned or retained during the course of the remedy. The MWAP also included a list of new monitoring wells and piezometers to be installed during the Chromium Remedy. Amec Foster Wheeler and Entact abandoned the designated monitoring wells and piezometers from October 2013 to October 2016. Wells designated as "retain" in the MWAP were protected and adjusted accordingly during the course of construction.

XI. SA-6 South Monitoring Well Installation. Twelve monitoring wells were installed in the SA-6 South Development Area in February 2016 in accordance with the 100% Design. The purpose of the wells is to monitor post remedy water quality in the SA-6 South Development Area. A figure showing the as-built locations of the wells is included in Attachment O.

XII. SA-6 North and South Institutional Controls. Honeywell will establish appropriate institutional controls at SA-6 North and South that supplement the remedial actions in accordance with the SA-6 Consent Decrees. These include the following:

- Deed notices;
- Remedial action permit for soils;
- Remedial action permit for groundwater;
- Potential revision of the boundary of the shallow groundwater CEA based upon post-remediation shallow groundwater results from SA-6 South Development AOC; and
- Conservation restrictions on both SA-6 Open Space Areas, at TA-10 and on the Deed Noticed portion of Site 163.

Additional details regarding the Institutional Controls are provided in the SA-6 North and South Construction Completion Reports (CCRs). Draft deed notices and remedial action permit applications are included as attachments in the CCRs.

1. Based on our professional experience, the data and information set forth in and attached to this Declaration, and our supervision of the SA-6 construction activities, we believe that the aforementioned remediation activities were completed in accordance with the SA-6 North and South Consent Decrees and the Final 100% Design and Design Changes.

2. We certify that the foregoing is true and correct to the best of our respective knowledge.

William J. Hague

Date

Joseph T. Clifford PE NJ, GE38067

Date 10/16/2017

## List of Attachments

A. 60 Kellogg Excavation

A-1. 60 Kellogg Excavation Certification E-mail

A-2. 60 Kellogg Confirmation Points and Post Excavation Plan

B. SA-6 South Excavation

B-1. SA-6 South Excavation Plan

B-2. SA-6 South E-mail Certifications of Excavation Completion

C. Site 163 Excavation

C-1. Site 163 Excavation Certification E-mail

C-2. Site 163 Post Confirmation Points and Post Excavation Plan

D. SA-6 North and South Contingent Groundwater Extraction System Record Drawings

D-1. Force Main, Electrical Conduit and Instrumentation

D-2. GWTP Interior Piping and Instrumentation

E. SA-6 North and South Piezometer As-Built Locations

F. SA-6 North and South Gas Vent Record Drawings

G. SA-6 North and South Deferred Areas (Figure 5)

H. In-Situ Locations and Summary Tables

I. Stratum D Repair Record Drawing

J. SA-6 North and South Root Barrier Topographic

K. SA-6 North and South Structural Fill Record Drawings

L. SA-6 North and South Cap Compaction Logs

M. SA-6 North and South Cap Cover Soils and Final Grades

M-1. SA-6 North and South Construction Control Grid As-Built Summaries

M-2. SA-6 North and South Final Grade Topographic

N. SA-6 North and South Development Area Final Grading

N-1. SA-6 North Construction Control Grid As-Built Summary and Survey Control Grid Drawing

N-2. SA-6 South Construction Control Grid As-Built Summary and Survey Control Grid Drawing

N-3. SA-6 North and South Development Area Topographics

N-4. SA-6 North and South Restoration Plans

O. SA-6 South Development Area Monitoring Well Locations

P. Design Changes

Q. SA-6 North and South Soil Erosion and Sediment Control Record Drawing

**ATTACHMENT A-1**
**60 KELLOGG EXCAVATION CERTIFICATION E-MAIL**

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, August 03, 2016 2:00 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E; Shallard, Samuel G.
**Subject:** FW: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Here is SM acknowledgement of 60 Kellogg

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, July 13, 2016 5:29 PM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Morris, John <John.Morris@honeywell.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>; Jeremy.Karpatkin@aporter.com <Jeremy.Karpatkin@aporter.com>; Liza Walsh (LWalsh@TheWalshFirm.com) <LWalsh@TheWalshFirm.com>; Hector Ruiz (HRuiz@TheWalshFirm.com) <HRuiz@TheWalshFirm.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; Kim Hosea (k.hosea@cea-enviro.com) <k.hosea@cea-enviro.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Bill,

The Special Master acknowledges receipt of your June 28, 2016 email and the supporting documentation accompanying the SA-6 South Excavation Complete Submittal for the 60 Kellogg Building Area and your subsequent emails confirming that the white-ish material observed in the excavation was included in the sidewall soil samples collected where residual material was observed for final confirmation and represented in the final post-excavation soil sampling results provided in your June 28 email and where all hexavalent chromium results were reported at less than 20 mg/kg.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, July 12, 2016 11:16 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Lewis, Thomas <tlewis@louisberger.com>; Morris, John <John.Morris@honeywell.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; Jeremy.Karpatkin@aporter.com <Jeremy.Karpatkin@aporter.com>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; Kim Hosea (k.hosea@cea-enviro.com) <k.hosea@cea-enviro.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Steve,

I have reviewed your email question with the Amec field team who observed the excavation and collected the post-excavation sidewall soil samples.
Amec indicates that the whitish material was included in the sidewall soil samples where residual material was observed.
Please let us know if you have any remaining questions on this item.

Regards,
Bill Hague

**William J. Hague P.E.**

Honeywell
Director - Remediation Design & Construction
Corporate HSE&R
115 Tabor Road
Morris Plains, NJ 07950
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Saturday, July 02, 2016 5:22 PM
**To:** Hague, William
**Cc:** RGT Special Master; Lewis, Thomas; Morris, John; JFarrell@jcnj.org; Francis J. Borin; JWatson@jcnj.org; Clifford, Joseph T; Daneker, Michael D.; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); ' (kmillian@tpmlaw.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; Jeremy.Karpatkin@aporter.com; 'Ben Ross (bross@disposalsafety.com)'; Kim Hosea (k.hosea@cea-enviro.com)
**Subject:** RE: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Bill,

Please see the following regarding the June 28, 2016 Excavation Complete Submittal for the 60 Kellogg Building Area:

The email states that "the post-excavation soil sampling location selection was biased according to field observations and not just geometrically predetermined" and that "Sidewall samples were biased to include residual whitish material if observed." Please confirm, as requested in my June 16 email, that the white-ish material was directly sampled and analyzed to determine whether hexavalent chromium concentrations in this material are above or below 20 ppm.

In addition, your email states: "The excavation was subsequently extended to approximately 14 ft by 14 ft in width and length to remove additional soil exhibiting whitish discolorations". However, as noted in my June 16 email, during my June 14 site visit I observed what appeared to be white-ish material in the southwestern face of the excavation, approximately 2 feet below the surface at what appeared to be the final excavation boundary. If the white-ish material was directly sampled and determined to contain less that 20ppm hexavalent

chromium, then leaving residual material in the excavation is not an issue. However, if the white-ish material was determined to contain hexavalent chromium above 20ppm, please confirm whether or not the observed white-ish material was subsequently removed as part of continued excavation efforts so that no white-ish material confirmed above 20 ppm hexavalent chromium remained visible at the excavation boundaries.

We look forward to your response.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, June 28, 2016 9:45 PM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Lewis, Thomas <tlewis@louisberger.com>; Morris, John <John.Morris@honeywell.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; '(kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; Jeremy.Karpatkin@aporter.com <Jeremy.Karpatkin@aporter.com>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; Kim Hosea (k.hosea@cea-enviro.com) <k.hosea@cea-enviro.com>
**Subject:** SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Steve,

We are providing this email notification that our laboratory data validation has been completed, all soil sample results showing concentrations of hexavalent chromium < 20 ppm are now final, thus, the added Excavation Area at 60 Kellogg Street can now be closed out (which is part of the SA-6 South Chromium Remedy).

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of excavation completion covers the work completed on 06/02/16. This submittal includes the excavation around the 60 Kellogg Street Building (Site 125 on SA-6 South) where suspect material had been observed and sampled in accordance with the submittal to All Parties, dated May 17, 2016. We are also addressing your email to Honeywell dated June 16, 2016 with clarification that the post-excavation soil sampling location selection was biased according to field observations and not just geometrically predetermined.

Attachments to the submittal include the Maser Table with bottom and sidewall confirmation points, and an Excavation Bottom Map showing sample locations and excavation limits.

- Initially, Amec personnel collected a soil sample (post demolition of the 60 Kellogg building raised slab) biased to a greenish discoloration in surficial soils identified between timber piles that formerly supported the 60 Kellogg building.
- This initial soil sample confirmed the presence of COPR and resulted in a proposed shallow excavation plan to address these soils by removing an area ~10 ft by 10 ft by 3 ft deep in size around this sample location (as detailed in the May 17, 2016 submittal to the parties).

- On June 2, 2016, the excavation was conducted to depths ranging from approximately 2.9 ft to 4.2 ft Below Ground Surface.
- The bottom and sides of the excavation at the final limits were visually inspected by Amec personnel. All of the original greenish discoloration was removed but some whitish material was observed in several sidewall locations.
- The excavation was subsequently extended to approximately 14 ft by 14 ft in width and length to remove additional soil exhibiting whitish discolorations.
- Five soil samples were collected from the excavation: one from each sidewall and one from the bottom of the excavation. Sidewall samples were biased to include residual whitish material if observed. The bottom sample was located the area where additional suspect material was also observed during excavation.
- This sampling frequency meets the approved frequencies established in the 100% Design.
- Coordinates for Survey of the finished excavation at the bottom and sidewall sample locations are tabulated in the Maser Tables.
- Sample locations are shown on the Entact “As Built” Excavation Figure attached.
- The final post-excavation soil sampling results were as follow:
    - 125-SB-308 <0.55 mg/Kg
    - 125-SB-309 0.66 mg/Kg
    - 125-SB-310 <0.52 mg/Kg
    - 125-SB-311 2.3 mg/Kg
    - 125-SB-312 1.9 mg/Kg
- All hexavalent chromium results were less than 20 mg/kg, thus, no further remediation is necessary.
- Maser collected bottom of excavation points to prepare a topographic Map of the bottom of excavation.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.

Regards,
Bill Hague

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**ATTACHMENT A-2**
**60 KELLOGG EXCAVATION**
**CONFIRMATION POINTS AND POST EXCAVATION PLAN**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South: 60 Kellogg Excavation (2016): Post Excavation Points (Table 1.0)

| Bottom Target Coordinates | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 684474.8 | 602542.4 | 6.3 | 125-SB-312 | 6/10/2016 | 6.2 | Target Elevation Reached |

## SA-6 South: 60 Kellogg Excavation (2016): Sidewall Post Excavation Points (Table 2.0)


| Sidewall Target Coordinates | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 684465.7 | 602542.9 | 6.0 | 125-SB-308 | 6/10/2016 | 6.0 | Target Elevation Reached |
| 684460.7 | 602551.9 | 6.8 | 125-SB-309 | 6/10/2016 | 6.7 | Target Elevation Reached |
| 684476.4 | 602554.5 | 6.0 | 125-SB-310 | 6/10/2016 | 6.0 | Target Elevation Reached |
| 684477.8 | 602543.5 | 6.4 | 125-SB-311 | 6/10/2016 | 6.4 | Target Elevation Reached |

1 This is the actual elevation of the samples that were collected post excavation (6/2/16).

**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Post Excavation Points depicted in Table 1, Post Excavation Sidewall Points Table 2 are correct, and representative of the as-built post-excavation grades.**

R. Thomas Hugg 6/17/16

**R. THOMAS HUGG**
**NEW JERSEY PROFESSIONAL LAND SURVEYOR**
**LICENSE NO. 36737**





Prepared/Date: TDD 6/3/16
Checked/Date:

| | | |
|---|---|---|
| CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec foster wheeler | 60 KELLOGG STREET<br>POST EXCAVATION PLAN<br>Project 3480-15-0488<br>FIGURE 1 |

C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South 60 Kellogg\Figure 1 60 Kellogg Post Excavation.dwg Fri, 03 Jun 2016 - 9:25am tony.donovan

**ATTACHMENT B-1**
**SA-6 SOUTH EXCAVATION PLAN**




## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW POST-EXCAVATION ELEVATIONS WITHIN THE SA6 SOUTH, SITE 163 & SITE 60 KELLOGG EXCAVATION AREAS AT THE PROJECT SITE.
2. POST-EXCAVATION LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM 10/23/13 THROUGH 12/22/14, 1/4/16 THROUGH 3/4/16 & 6/10/16. POST EXCAVATION SURFACES AND CONTOURS WERE GENERATED BY ENTACT AND CONFIRMED BY MASER CONSULTING P.A. WITH MINOR ADJUSTMENTS.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 3 | 7/30/16 | UPDATED DESIGN BOE LIMITS | BSB | RTH |
| 2 | 7/12/16 | ADDED SITE 163 DATA & 60 KELLOGG TOPO | BSB | RTH |
| 1 | 3/13/15 | REVISED PER CLIENT COMMENTS 3/4/15 | BSB | RTH |

DSGN BSB | DR | CHK JR | APVD RTH

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
EXCAVATION PLAN

FILE NUMBER
XXXXX

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 08223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 890 - 2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 3/3/15 |
| PROJ | 3480-10-0027 |
| DWG | C-111 |
| SHEET | 1 OF 1 |

FILE NAME: C:\Civil 3D Projects\12001511A\Survey\V-SURV-SA6S-FINAL.dwg PLOT DATE: Mon, 01 Aug 2016 PLOT TIME: 3:09 PM

**ATTACHMENT B-2**
**SA-6 SOUTH E-MAIL CERTIFICATIONS OF EXCAVATION COMPLETION**

## Egnaczyk, Steve

**From:** Kevin J. Coakley <KCoakley@connellfoley.com>
**Sent:** Friday, April 25, 2014 8:56 AM
**To:** 'kmillian@tpmlaw.com'; 'aalcorn@tpmlaw.com'; 'eric@golub-isabel.com'; 'kkinsella@decotiislaw.com'; 'Michael D. Daneker (Michael.Daneker@aporter.com)'; 'Jeremy Karpatkin (Jeremy.Karpatkin@aporter.com)'; 'Jeremy Farrell' (JFarrell@jcnj.org)
**Cc:** 'rgtspecialmaster@aol.com'; Sean Jackson (Sean@RosemontAssocs.com); Egnaczyk, Steve; Lewis, Thomas; Liza M. Walsh; Agnes Antonian
**Subject:** Honeywell Excavation Submittals

Dear Counsel:

During Tuesday's Special Master All Parties Meeting, it was agreed that Honeywell would continue to provide notifications to the parties certifying that cells within the SA6 North and South excavation have been completed in accordance with the 100% Design and request an email acknowledgement only from the Special Master that the Special Master is in receipt of the supporting documentation accompanying the notification. The Special Master's technical representative will continue to perform periodic visual inspections of the completed excavation areas prior to backfilling and provide a response to Honeywell's email submittals within 48-hours.

Honeywell will continue to conduct the excavation operations as detailed in the SA-6 South Standard Operating Procedure (SOP) - Confirmation of Excavation Limits, dated March 3, 2014 that provides Honeywell's basis for assessing and demonstrating that the limits of excavation as defined in the 100% Design are being met and documented.

Specifically and as noted in Honeywell's April 17, 2014 Response to Plaintiffs' Comments regarding Excavation of Cells 44-52, Honeywell will:

- continue to collect the survey data necessary to prepare the topographic map as indicated in the first bullet of Section 5.0 in the SOP,
- prepare the topographic map to meet the requirements of Section 02315 Part 3.03 Topographic Surveys, Part C. Post Excavation Survey of the Technical Specifications, and
- provide the topographic survey as part of the final certification.

Honeywell acknowledges that as it is no longer waiting for ICO acknowledgement of the above described progress reports on cell excavation confirmation, and therefore Honeywell will be proceeding at risk as it relates to these specific issues from ICO's perspective, or for that matter, Jersey City's perspective as well. Honeywell will continue to submit these reports to all parties at the same time it transmits them to the Special Master.

Please respond to this email within 48 hours if you do not concur that this description represents the agreement reached at Tuesday's meeting.

**Kevin J. Coakley**

Partner
Connell Foley LLP
85 Livingston Avenue
Roseland, NJ 07068
Office: (973) 535-0500
Direct: (973) 533-4230
Fax: (973) 535-9217

kcoakley@connellfoley.com
www.connellfoley.com
Vcard

STATEMENT OF CONFIDENTIALITY: The information contained in this transmission including any attached documentation is privileged and confidential. It is intended only for the use of the individual or entity named above. If the reader of this message is not the intended recipient, you are hereby notified that any dissemination, distribution or copy of this communication is strictly prohibited. If you have received this communication in error, please notify Connell Foley LLP immediately by replying to this email. Please delete all copies of this message and any attachments immediately.

IRS CIRCULAR 230 DISCLOSURE: As required by U.S. Treasury Regulations governing tax practice, you are advised that any written tax advice contained herein was not intended or written to be used, and cannot be used, by any taxpayer for the purpose of avoiding tax penalties that may be imposed under the Internal Revenue Code.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:41 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA6 South Remedy Implementation

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, November 01, 2013 10:06 AM
**To:** Clifford, Joseph T; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; ' (John.Morris@honeywell.com)'; 'cpravlik@tpmlaw.com'; ' (Michael_Daneker@aporter.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA6 South Remedy Implementation

Joe,

This email responds to your email of October 29, 2013 requesting approval to backfill cells 1 and 2 at the Study Area 6 South excavation. The October 29 email responded to the Special Master's email of October 26 and prior emails, which requested that Honeywell confirm that the excavation areas were completed and provide supporting documents that describe the survey protocol addressing how the excavation was completed, especially in areas where the meadow mat was encountered above the projected excavation depth. The Special Master also requested a document tracking the progress and status of the excavation. In its October 29 submittal Honeywell attached two documents: (1) Excavation Bottom Elevations Plan for the period of 10/22/13 to 10/24/13 and (b) Excavation and Backfill Progress Summary End of October 2, 2013 Plan. The Excavation Bottom Elevations Plan shows that the excavation in Cells 1 and 2 was performed to Stratum D. The October 29, email confirms that the excavation in both cells terminates in Stratum D as visually confirmed by Amec personnel. Amec inspectors certified that the impacted soils in the 100% Design have been removed and that the requirements to allow backfilling have been met. In addition, I observed the conditions of the excavation on Tuesday, 10/29 and then again, with the Special Master on Wednesday, October 30, 2013. The Special Master and his team's visual observations are consistent with Amec's representation that the Stratum D is clearly visible as a continuous layer in these two cells. The Special Master has also received Plaintiffs letter of October 31, 2013 approving Honeywell's request. Based on Honeywell's certified representations in the October 29, 2013 email and the documents attached thereto, the Special Master's observations, and the fact that the Stratum D is well defined and continuous, the Special Master approves backfilling of Cells 1 and 2.

To ensure that in the future the confirmation process is efficient and does not delay the project going forward, the Special Master requests that in addition to the documents provided with the October 29 email, Honeywell include additional information clearly defining the final excavation depths in the cells and, as requested before, drawings showing the extent of the meadow mat. Such information will also support the Excavation Declarations that will be filed with the Court to document compliance with the Consent Order and the 100% Design. While the initial two cells had a clearly defined final depth of excavation for each cell, that is not likely to be the case in the future, especially when the excavation cells become larger. The Special Master suggests that a table (similar to the example shown below) would provide the necessary information to the Special Master and the parties to ensure an efficient and effective review and confirmation. This table should provide a reference to the PDI sample result(s) that established the original depth(s) of excavation for the Excavation Cell or general area, realizing that an explanation would be required if meadow mat was

encountered and the excavation was halted at a shallower depth or if other field conditions impacted achieving the design excavation depth. This table is similar to what was provided during the COPR excavation.

| Excavation Cell | 100% Design PDI Sample Result Depths(s) and sample location(s) | Actual Excavation Depth(s) and reference, for example: bgs, MSL | Comments/Exceptions |
|---|---|---|---|
| 1 | (-) 9.5 ft based on PDI Confirmatory Sample Location XXX-SB-XXX | (-) 4.5 ft. | Excavated to depth of meadow mat at (-) 4.5 ft MSL. |
| 2 | (-) 8.5 ft in Area A *[Areas to be defined in the Excavation Bottom Plan;* (-) 6 ft in Area B | Area A: (-) 9 ft<br>Area B: (-) 8.5 ft | |

The Special Master is looking forward to further discussing these issues at the next technical call. At that time the Special Master would like to address the number of survey points that will be necessary to document the excavation bottom, especially in the larger cells with anticipated varying depths of excavation.

Further, we request that Honeywell prepare for discussion a form of Declaration to be filed with the Court showing excavation completion in accordance with the 100% Design. We would expect that the form of Declaration will be in a format substantially similar to that filed in connection with Study Area 7.

Regards, Steve

Steven J. Egnaczyk
Program Director
THE Louis Berger Group, INC.
350 Eagleview Boulevard |Suite 250 | Exton, PA 19341-1178
Phone: 610.363.5395 | Fax: 610.363.5390
Cell: 610.212.1492
Email: segnaczyk@louisberger.com
http://www.louisberger.com

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Tuesday, October 29, 2013 9:05 PM
**To:** Egnaczyk, Steve; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; ' (John.Morris@honeywell.com)'; 'cpravlik@tpmlaw.com'; ' (Michael_Daneker@aporter.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; Isabelle Procaccino; McWatters, Michael
**Subject:** RE: SA6 South Remedy Implementation

Steve,

I am sending this email on behalf of Honeywell.

As discussed at our weekly meetings, we are at a point of being ready to backfill and approval of the submittal content is critical to moving forward.

Below is a description of completed excavation activities for which we are requesting an acknowledgement in order that we can proceed with backfill.

We are also attaching herein two supporting drawings:

1. Exhibit A - depicts the 156, 15-ft wide cells that comprise the SA-6 South excavation which will be used as a excavation progress chart;
2. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for the first two cells completed as described below.

- *Full scale excavation of Chromium Impacted Materials began on 10/21/2013.*
- *For planning and implementation purposes, the excavation is subdivided into 156, 15 ft wide cells with Cell 1 located near Route 440.*
- *For the period ending 10/24/2013 excavation is complete for Cells 1 and 2.*
- *The excavation in both cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, a bottom-of-excavation confirmatory point is located within Cell 2.*
- *The surveyed coordinates of the bottom-of-excavation confirmatory point are included in the attached figure.*
- *The easterly limit of Cell 1 and the north and south limits of Cells 1 and 2 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*

Honeywell acknowledges that your email includes a request for potential additional information regarding locations where meadow is encountered, we will respond separately to that item.

Please let us know if you have comments or questions on the information contained in this email. Thank you. –Joe

**Joseph T. Clifford, P.E.**
**AMEC Environment & Infrastructure**
**200 American Metro Blvd, Suite 113, Hamilton NJ 08619**
**973-455-4163 direct dial**
**610-505-9315 cell**

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Saturday, October 26, 2013 2:34 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; ' (John.Morris@honeywell.com)'; 'cpravlik@tpmlaw.com'; ' (Michael_Daneker@aporter.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com;

Clifford, Joseph T; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; Isabelle Procaccino; McWatters, Michael; Clifford, Joseph T
**Subject:** SA6 South Remedy Implementation

Bill,

As we discussed earlier this week, please advise when you plan to forward the information Honeywell proposes to provide to the Special Master and the parties to confirm the completion of excavation for delineated excavation cells. We are also expecting a document that will track the progress and status of the excavation (i.e., a drawing delineating the excavation grids similar to the drawing provide for the SA7 COPR Excavation). Recognizing that excavation work is now underway, it is important to get these items to us so the parties and the Special Master have sufficient time to review them without causing delay to your planned schedule to backfill the completed cells. In addition, during this week's site construction meeting there were some new drawings that Honeywell has generated that appear to show the projected extent of the meadow mat within each excavation cell. The presence of the meadow mat in the excavation cells raises a question as to how Honeywell intends to document/address the areas where meadow mat is encountered above the anticipated floor of excavation (especially if the meadow mat was not previously anticipated in such an area). A description of the survey protocol addressing this issue as well as the new drawings that Honeywell has generated would be useful for the parties to have as we follow the implementation of the excavation plan; please confirm when Honeywell can provide these new drawings and survey protocols to the Special Master and Plaintiffs.

Regards, Steve

Steven J. Egnaczyk
Program Director
THE Louis Berger Group, INC.
350 Eagleview Boulevard |Suite 250 | Exton, PA 19341-1178
Phone: 610.363.5395 | Fax: 610.363.5390
Cell: 610.212.1492
Email: segnaczyk@louisberger.com
http://www.louisberger.com

THINK GREEN: Please do not print this email unless absolutely necessary.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc. (LBG), the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:41 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA6 South Remedy Implementation

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, November 08, 2013 10:08 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amec.com>; Mojka, John <John.Mojka@Honeywell.com>; Bills, Stuart B <Stuart.Bills@amec.com>
**Subject:** FW: SA6 South Remedy Implementation

FYI

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, November 08, 2013 3:29 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA6 South Remedy Implementation

Bill,

We are in receipt of your email of November 5 regarding Excavation Bottom Elevations for the period 10-25-13 to 10-31-13 and your notification that your contractor is ready to backfill Excavation Cells 3, 4 and 5. During my site visit on November 5, I observed the excavation area and that Excavation Cells 3, 4, and 5 were fully excavated to the meadow mat. In addition, during our discussion on November 6 you clarified the information shown on the Figure ("Excavation Bottom Elevations, Period 10-25-13 to 10-31-13") and the Table prepared by Maser ("SA-6 South Excavation: Confirmatory Points") that were included in your November 5 submittal. The Special Master looks forward to receiving this figure and table in future submittals revised as we discussed as this will aid the Special Master in evaluating the excavation completion. Please be advised that the Special Master continues to evaluate what the process should be regarding excavation completion/backfill approval and we will be following up with the parties shortly. Recognizing that this part of the site is still within the boundary of the meadow mat the Special Master is comfortable in authorizing the backfill of Excavation Cells 3, 4 and 5.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, November 05, 2013 5:36 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA6 South Remedy Implementation

Steve,

As discussed at our weekly meeting today, we are hereby notifying you that our contractor is ready to backfill Cells 3, 4 and 5 starting on Friday Nov 8.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

Below is a description of completed excavation activities specific for these Cells consistent with the language provided in our description of completed Cells 1 and 2.

- *For the period 10/25/2013 to 10/31/2013 excavation is complete for Cells 3, 4 and 5.*
- *The excavation in all cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, a bottom-of-excavation confirmatory point is located within Cell 3.*
- *The surveyed location of the bottom-of-excavation confirmatory point is included in the attached figure.*
- *The north and south limits of Cells 3, 4 and 5 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*

We are also attaching herein three supporting documents:

1. Excavation Progress Map through October 31, 2013 - depicts the 156, 15-ft wide cells that comprise the SA-6 South excavation and the updated excavation progress chart;
2. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for Cells 3, 4 and 5 which have been completed as described below.
3. Post-Excavation Confirmatory Sample Table Survey 103113 – provides the PDI Sampling Location and updated survey information post-excavation which corresponds to this set of Cells.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:41 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 6 through 9

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, November 15, 2013 11:13 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 6 through 9
**Importance:** High

Bill,

We are in receipt of your email of November 13 and attached Excavation Bottom Map and Post-Excavation Confirmatory Sample Table Survey regarding Excavation Bottom Elevations for the period 11-1-13 to 11-7-13. The November 13 email includes information regarding the excavation procedures and certifies that the excavation met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 6, 7, 8 and 9 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on November 12 and observed the excavation area. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 6, 7, 8 and 9 were fully excavated to the meadow mat. Therefore, the Special Master has no objection to Honeywell's proposal to backfill these cells. The Special Master reiterates the concern raised previously and discussed yesterday on the technical call with Joe Clifford and ICO representatives as it relates to how the depth of excavation points have been identified. As this area is entirely meadow mat, the Special Master is comfortable with Honeywell proceeding with backfill. However, the Special Master still has unresolved questions as it relates to those cells where the depth of excavation will not reach or be defined by the meadow mat. It is our expectation that we can discuss, and hopefully resolve, those issues at Tuesday's meeting.

Regards, Steve

Steven J. Egnaczyk
Program Director
THE Louis Berger Group, INC.
350 Eagleview Boulevard |Suite 250 | Exton, PA 19341-1178
Phone: 610.363.5395 | Fax: 610.363.5390
Cell: 610.212.1492
Email: segnaczyk@louisberger.com
http://www.louisberger.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should

immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, November 13, 2013 8:39 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 6 through 9

Steve,

As a follow up to our weekly meeting yesterday, we are hereby notifying you that our contractor is ready to backfill Cells 6 through 9 starting on Friday Nov 15th.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

Below is a description of completed excavation activities specific for these cells. consistent

- *For the period 11/01/2013 to 11/07/2013 excavation is complete for Cells 6, 7, 8 and 9.*
- *The excavation in all cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, bottom of excavation confirmatory points are located within Cells 6, 7, 8 and 9.*
- *The surveyed location of the bottom of excavation confirmatory points are included in the attached figure.*
- *The location of confirmatory sidewall samples are listed in the PDI. To date none of the PDI confirmatory sidewall sample locations have been encountered.*
- *The north and south limits of Cells 6, 7, 8 and 9 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
-

We are also attaching two supporting documents:

1. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for Cells 6 through 9 which have been completed.
2. Post-Excavation Confirmatory Sample Table Survey 1109713 – provides the PDI Sampling Location and updated survey information post-excavation which corresponds to this set of Cells.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells.

Thank you
Bill Hague

**Honeywell**

## William J. Hague P.E.

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:42 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 10 through 12

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Monday, November 25, 2013 3:50 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 10 through 12
**Importance:** High

Bill,

We are in receipt of your email of November 21 and attached Excavation Bottom Map – 111413, Confirmatory Points Certification - 111413 and Excavation Progress Map – 111413 regarding Excavation Bottom Elevations for the period 11-8-13 to 11-14-13. The November 21 email includes information regarding the excavation procedures and certifies that the excavation met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 10, 11 and 12 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on November 21 and observed the excavation area. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 10, 11 and 12 were fully excavated to the meadow mat. Therefore, the Special Master has no objection to Honeywell's proposal to backfill these cells.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, November 21, 2013 1:24 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 10 through 12

Steve,

As discussed in our all parties meeting Tuesday, we are hereby notifying you that our contractor is ready to backfill Cells 10 through 12 starting on Friday Nov 22th.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

Below is a description of completed excavation activities specific for these cells.

- *For the period 11/08/2013 to 11/14/2013 excavation is complete for Cells 10, 11 and 12.*
- *The excavation in all cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, bottom of excavation confirmatory points are located within Cells 10, 11 and 12.*
- *The surveyed location of the bottom of excavation confirmatory points are included in the attached figure.*
- *The first confirmatory PDI sidewall sample is identified in Cell 11. The sample location is inside the temporary sheetpile which was driven along the section Kellogg Street Jughandle.*
- *The north and south limits of Cells 10, 11 and 12 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*

We are also attaching three supporting documents:

1. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for Cells 10 through 12 which have been completed.
2. Post-Excavation Confirmatory Sample Table Survey 111413 – provides the PDI Sampling Location and updated survey information post-excavation which corresponds to this set of Cells.
3. Excavation Progress Map – includes excavation status of the cells as of 111413.

We are in the process of working with Amec and the surveyor on making improvements to the supporting documents as discussed in our meeting and should have those soon.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962

973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:42 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 13 through 16

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Sunday, December 22, 2013 8:07 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 13 through 16
**Importance:** High

Bill,

We are in receipt of your email of December 16 and attached Confirmation Points Certification – 112113, Excavation Bottom Map – 112513 (Rev.1), Excavation Progress Map – 112113, Confirmation Points Certification – 120513, Excavation Bottom Map – 120513 (Rev.1), and Excavation Progress Map – 120513. The December 16 email includes information regarding the excavation procedures and certifies that the excavation met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 13, 14, 15 and 16 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on November 21, November 26, December 3, and December 5 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 13, 14, 15 and 16 were fully excavated to the meadow mat. Therefore, the Special Master has no objection to Honeywell's proposal to backfill these cells.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, December 16, 2013 10:23 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell

Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 13 through 16

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 13 through 16 .

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers two periods:

- 11/15/13 to 11/25/13 - Cells 13 and 14
- 11/26/13 to 12/05/13 - Cells 15 and 16

For ease of review the attachments for each period are grouped together.

1. The bottom of excavation for Cells 13, 14, 15 and 16 was terminated in Stratum D. Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.
2. Excavation Bottom Elevation Figures are included for both periods.
    1. Confirmatory points located within Cells 13 and 14 are shown on the Excavation Bottom Elevation figure for 11/15 to 11/25
    2. Confirmatory Bottom points located within Cells 15 and the Sidewall Samples for Cell 16 are shown on the Excavation Bottom Elevation figure for 11/26 to 12/05. A Reference Confirmatory Point was used for the bottom of Cell 16
3. Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A separate table is included for each period and the Cells which are the subject of the submittal period are highlighted in yellow.
4. The north and south limits of Cells 13, 14, 15 and 16 consist of sheet pile.
5. Sheet pile on the excavation face has been cleaned of visible soil materials.
6. The bottom and lateral limits of each cell were visually inspected by Amec personnel.
7. Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
8. Excavation progress Maps are shown for each period. Excavation is continuing in Cells 17 and 18 as shown in the Excavation Progress Map.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you will be on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction

Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:42 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 17 through 20

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, January 24, 2014 10:58 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 17 through 20
**Importance:** High

Bill,

We are in receipt of your email of January 8, 2014 and the following attachments: Confirmation Points Certification – 121213, Excavation Bottom Map – 121313 (Rev.2), and Excavation Progress Map – 121213. The January 8 email includes information regarding the excavation procedures and certifies that the excavation of Cells 17 through 20 met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 17, 18, 19 and 20 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on December 10, December 13, and December 17, 2013 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 17 and 18 were fully excavated to the meadow mat and that Excavation Cells 19 and 20 were partially excavated to the meadow mat. For the areas of Excavation Cells 19 and 20 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Map – 121313 (Rev.2)" showing the Excavation Bottom Elevations for the period 12-06-13 to 12-12-13 and "Confirmation Points Certification – 121213" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 19 and 20:

| Excavation Cell No.* | Bottom Target Coordinate (MSL) | Actual Coordinates (of the confirmatory bottom sample survey point) (MSL) |
|---|---|---|
| 19 | 2.4 | 2.0 |
| 20 | 2.4 | 2.0 |

*where meadow mat was not encountered

Honeywell notes on the Confirmation Points Certification table that in establishing the Bottom Target Coordinate for an excavation cell based on the PDI results reported in the 100% Design, an "R" designates a "Reference Confirmatory Point for a designated Bottom Excavation Area" that has not been shown on the Excavation Bottom Figure (i.e., the excavation has not yet reached the cell where the PDI boring was located). In future submittals, it would be helpful if Honeywell

would provide the location or reference the Cell Number of the Reference Point on the Excavation Bottom Figure for reference purposes even if the respective excavation cell where the PDI result is located has not yet been reached.

Based on the information provided by Honeywell in this notification and the discussions held during this week's Special Master All Parties Meeting where Plaintiffs noted no objection, the Special Master has no objection to Honeywell's proposal to backfill these cells.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, January 08, 2014 11:25 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 17 through 20

Steve,

We are providing this email notification that our contractor is read to backfill Cells 17 through 20.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the period 12/06/13 to 12/12/13.

Cells 17, 18, 19 and 20

- The bottom of excavation for Cells 17, 18, was terminated in Stratum D. The majority of the bottom of Cells 19, 20, was terminated in Stratum D. The Southern section of cells 19 and 20 was terminated in Stratum O <20 PPM soils.
- Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.
- An Excavation Bottom Elevation Figure is included for the period.
- Confirmatory points located within Cells 17, 18, 19 and 20 are shown on the Excavation Bottom Elevation figure.
- Confirmatory Sidewall Samples for Cells 18 and 20 are shown on the Excavation Bottom Elevation figure.
- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.
- The northern limits of Cells 17, 18, 19 and 20 consist of sheet pile Barrier Wall. Approximately half of the southern extent of Cell 17 is terminated at the temporary sheetpile. The remainder of cell 17 and

cells 18, 19 and 20 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.

- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- Excavation progress Maps are provided. Excavation is continuing in Cells 21 and 22.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you will be on-site this week to review the progress. Also please note we did upload data on backfill materials yesterday in response to earlier comments

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:43 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 21 through 25

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, March 06, 2014 4:38 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Bill,
Thanks very much for your reply. Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, March 06, 2014 4:36 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Steve
Thanks for your note below. I have reviewed the results with the Amec team for rows 21 through 25 and can confirm that all survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.

Regards
Bill Hague

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Tuesday, March 04, 2014 2:26 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Bill,

We are in receipt of your email of January 28, 2014 and the following attachments: Confirmation Points Certification – 010914 (rev1), Excavation Bottom Elevations Period – 121313 to 010914 (Rev.1), and Excavation Progress Map – 010914. The January 28 email includes information regarding the excavation procedures and certifies that the excavation of Cells 21 through 25 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 21, 22, 23, 24 and 25 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on December 17, 19, 24 and 31, 2013 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 21 through 25 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevation of the meadow mat. For the areas of Excavation Cells 21 through 25 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 121313 to 010914 (Rev.1)" showing the Excavation Bottom Elevations for the period 12-13-13 to 1-09-14 and "Confirmation Points Certification – 010914" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 21 and 25:

| Excavation Cell No.* | Bottom Target Coordinate (MSL) | Actual Coordinates (of the confirmatory bottom sample survey point) (MSL) |
|---|---|---|
| 21 | 2.4 | 1.9 |
| 22 | 2.4 | 2.0 |
| 22 | 1.8 | -0.1 |
| 23 | 2.4 | -1.9 |
| 24 | 2.4 | 2.1 |
| 25 | 1.6 | 0.4 |

*where meadow mat was not encountered

In addition, the Special Master acknowledges Plaintiffs' February 21, 2014 email regarding excavation of cells 21-29 where Plaintiffs noted they have no further comments regarding the excavation of cells 21-29 and agreed that cells 21-29 have been excavated to the appropriate depth and may be backfilled.

The Special Master has no objection to Honeywell's proposal to backfill Cells 21 through 25, subject to Honeywell confirming by email that it agrees that the following statement, inserted in its subsequent Excavation Completion Reports, also applies to these cells (numbers 21 thru 25):

"All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered."

Please confirm via email.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, January 28, 2014 2:02 PM

**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Steve
Apologies to all, I had the incorrect attachments on the initial email. Correct attachments are provided here.
Thanks
Bill

---

**From:** Hague, William
**Sent:** Tuesday, January 28, 2014 1:35 PM
**To:** 'Egnaczyk, Steve'
**Cc:** 'RGT Special Master'; 'Kevin J. Coakley (KCoakley@connellfoley.com)'; ''Liza M. Walsh' (LWalsh@connellfoley.com)'; ''AGNES ANTONIAN' (AAntonian@connellfoley.com)'; 'Lewis, Thomas'; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; 'JFarrell@jcnj.org'; 'Dfanciullo@jcnj.org'; 'David Isabel'; 'Eric Tomaszewski'; 'Francis J. Borin'; 'Clifford, Joseph T'; 'KKINSELLA@decotiislaw.com'; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; 'McWatters, Michael'; 'JWatson@jcnj.org'
**Subject:** SA-6S : Excavation Completion in Cells 21 through 25

Steve,

We are providing this email notification that our contractor is read to backfill Cells 21 through 25.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the period: 12/13/13 to 01/09/14 - Cells 21, 22, 23, 24 and 25.

- *The majority of the bottom of Cells 21, 22, 23, 24 and 25 were terminated in Stratum D. The Southern limit of cells 21, 22, 23, 24 and 25 were terminated in Stratum O <20 PPM soils.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *An Excavation Bottom Elevation Figure is included for the period.*
- *Confirmatory Bottom Points located within Cells 21, 22, 23, 24 and 25 are shown on the Excavation Bottom Elevation figure.*
- *A Confirmatory Sidewall Sample for Cells 22 and 25 is also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.*
- *The northern limits of Cells 21, 22, 23, 24 and 25 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 21, 22, 23, 24 and 25 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*

- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps are provided. Excavation is continuing in Cells 26, 27, and 28.*

Note that we are also preparing a PDI location map for the SA-6 South area as requested by Kim Hosea at the last Special Master All Hands mtg and should have this available tomorrow which we will release with the next cell excavation summary email..

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 26 through 29

-----Original Message-----
From: Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
Sent: Friday, March 07, 2014 5:54 PM
To: Hague, William
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; (kmillian@tpmlaw.com); Morris, John (MTO); cpravlik@tpmlaw.com; Daneker, Michael; DelisleB@jcnj.org; Aalcorn@tpmlaw.com; MWeaver@tpmlaw.com; Jeremy.Karpatkin@aporter.com; JFarrell@jcnj.org; David Isabel; Eric Tomaszewski; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; Ben Ross (bross@disposalsafety.com); Bruce A. Bell; Kim Bell Hosea (k.bell@cea-enviro.com); McWatters, Michael; JWatson@jcnj.org
Subject: Re: SA-6S : Excavation Completion in Cells 26 through 29

Bill,
Thanks very much.
Steve

Sent from my iPhone

On Mar 7, 2014, at 5:39 PM, "Hague, William"
<william.hague@honeywell.com<mailto:william.hague@honeywell.com>> wrote:

Steve
To follow up on your email below. We confirm that all survey points in the excavation cells 26 through 29 were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.

Please contact me if there are any additional questions.

Regards
Bill Hague

From: Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
Sent: Friday, March 07, 2014 2:04 PM
To: Hague, William
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com<mailto:KCoakley@connellfoley.com>); 'Liza M. Walsh' (LWalsh@connellfoley.com<mailto:LWalsh@connellfoley.com>); 'AGNES ANTONIAN' (AAntonian@connellfoley.com<mailto:AAntonian@connellfoley.com>); Lewis, Thomas; '(kmillian@tpmlaw.com<mailto:kmillian@tpmlaw.com>)'; Morris, John (MTO); 'cpravlik@tpmlaw.com<mailto:cpravlik@tpmlaw.com>'; Daneker, Michael; 'DelisleB@jcnj.org<mailto:DelisleB@jcnj.org>'; 'Aalcorn@tpmlaw.com<mailto:Aalcorn@tpmlaw.com>'; 'MWeaver@tpmlaw.com<mailto:MWeaver@tpmlaw.com>';

'Jeremy.Karpatkin@aporter.com<mailto:Jeremy.Karpatkin@aporter.com>'; JFarrell@jcnj.org<mailto:JFarrell@jcnj.org>; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com<mailto:KKINSELLA@decotiislaw.com>; 'Ben Ross (bross@disposalsafety.com<mailto:bross@disposalsafety.com>)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com<mailto:k.bell@cea-enviro.com>)'; McWatters, Michael; JWatson@jcnj.org<mailto:JWatson@jcnj.org>
Subject: RE: SA-6S : Excavation Completion in Cells 26 through 29
Importance: High

Bill,

We are in receipt of your email of January 29, 2014 and the following attachments: Confirmation Points Certification – 011614 (rev1), Excavation Bottom Elevations Period – 011014 to 011614 (Rev.1), and Excavation Progress Map – 011614. The January 29 email includes information regarding the excavation procedures and certifies that the excavation of Cells 26 through 29 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 26, 27, 28 and 29 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on December 31, 2013 and January 7, 9 and 14, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 26 through 29 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevations of the meadow mat. For the areas of Excavation Cells 26 through 29 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 011014 to 011614 (Rev.1)" showing the Excavation Bottom Elevations for the period 1-10-14 to 1-16-14 and "Confirmation Points Certification – 011614" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 26 through 29:

Excavation Cell No.*

Bottom Target Coordinate – based on PDI
(MSL)

Bottom Target Coordinate – based on Predetermined Bottom Elevations1
(MSL)

Actual Coordinates
(of the confirmatory bottom sample survey point)
(MSL)

26

1.6

0.4

0.3**

27

1.6

0.4

0.4**

28

1.6

0.4

0.2

29

3.5

2.1

2.1**

*where meadow mat was not encountered
**elevation based on Surveyed Center Point
1 Corresponds with the 9 “standardized” excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

Honeywell also provided confirmation that the southern limit of excavation of cells 26, 27, 28, and 29 terminates at the less than (“<”)20 ppm line (delineated by Honeywell) at the bottom of excavation and the cells are cut back at a stable slope beyond the 20ppm line.

In addition, the Special Master acknowledges Plaintiffs' February 21, 2014 email regarding excavation of cells 21-29 where Plaintiffs noted they have no further comments regarding the excavation of cells 21-29 and agreed that cells 21-29 have been excavated to the appropriate depth and may be backfilled.

The Special Master has no objection to Honeywell's proposal to backfill Cells 26 through 29, subject to Honeywell confirming that it agrees that the following statement, inserted in its subsequent Excavation Completion Reports, also applies to these cells (numbers 26 thru 29):

"All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered."

Please confirm via email.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, “LB”), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

From: Hague, William [mailto:william.hague@honeywell.com]

Sent: Wednesday, January 29, 2014 2:27 PM
To: Egnaczyk, Steve
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com<mailto:KCoakley@connellfoley.com>); 'Liza M. Walsh' (LWalsh@connellfoley.com<mailto:LWalsh@connellfoley.com>); 'AGNES ANTONIAN' (AAntonian@connellfoley.com<mailto:AAntonian@connellfoley.com>); Lewis, Thomas; ' (kmillian@tpmlaw.com<mailto:kmillian@tpmlaw.com>)'; Morris, John (MTO); 'cpravlik@tpmlaw.com<mailto:cpravlik@tpmlaw.com>'; Daneker, Michael; 'DelisleB@jcnj.org<mailto:DelisleB@jcnj.org>'; 'Aalcorn@tpmlaw.com<mailto:Aalcorn@tpmlaw.com>'; 'MWeaver@tpmlaw.com<mailto:MWeaver@tpmlaw.com>'; 'Jeremy.Karpatkin@aporter.com<mailto:Jeremy.Karpatkin@aporter.com>'; JFarrell@jcnj.org<mailto:JFarrell@jcnj.org>; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com<mailto:KKINSELLA@decotiislaw.com>; 'Ben Ross (bross@disposalsafety.com<mailto:bross@disposalsafety.com>)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com<mailto:k.bell@cea-enviro.com>)'; McWatters, Michael; JWatson@jcnj.org<mailto:JWatson@jcnj.org>
Subject: RE: SA-6S : Excavation Completion in Cells 26 through 29

Steve,

We are providing this email notification that our contractor is read to backfill Cells 26 through 29.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the period: 01/10/14 to 01/16/14 - Cells 26, 27, 28 and 29.

Ø The majority of the bottom of Cells 26, 27, 28, and 29 were terminated in Stratum D. The Southern limit of cells 26, 27, 28, and 29 were terminated in Stratum O <20 PPM soils.

Ø Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.

Ø An Excavation Bottom Elevation Figure is included for the period.

Ø Confirmatory Bottom Points located within Cells 26, 27, 28, and 29 are shown on the Excavation Bottom Elevation figure.

Ø A Confirmatory Sidewall Sample for Cell 28 is also shown on the Excavation Bottom Elevation figure.

Ø Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.

Ø The northern limits of Cells 26, 27, 28, and 29 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 26, 27, 28, and 29 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.

Ø Sheet pile on the excavation face has been cleaned of visible soil materials.

Ø The bottom and lateral limits of each cell were visually inspected by Amec personnel.

Ø Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.

Ø Excavation progress Maps are provided. Excavation is continuing in Cells 30 and 31.

Note that this submittal includes the additional PDI Reference Bottom Sample Location Map for SA-6 South requested during the January 21, 2014 SM Meeting. This location map corresponds to the Figure presented depicting the 41 individual color-coded bottom excavation areas within SA-6 South, and the Reference Boring Summary Table identifying the coordinates and the corresponding Cell location previously provided to the parties.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

Honeywell
William J. Hague P.E.
Director - Remediation Design & Construction Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com<mailto:william.hague@honeywell.com>

_____
The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 30 through 37

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Monday, March 10, 2014 10:32 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 30 through 37

Bill,
Thanks very much. The additional figures you provided record the progress of excavation for Cells 30-35. Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, March 10, 2014 10:23 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 30 through 37

Steve,

We believe your question arises from the fact that we submitted a single email package of tables and supporting figures for several weekly periods.

I have asked Amec to provide just the original Excavation Bottom Map for each of the four weekly periods which document the surveying for Cells 30 through 37. These survey maps are attached for weeks ending 01/23/14 (Cells 30 and 31), 01/30/14 (Cells 32 and 33), 02/06/14 (Cells 34 and 35), and 02/13/14 (Cells 36 and 37).

Please let me know if you have any other questions.

Regards,
Bill Hague

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, March 07, 2014 2:11 PM
**To:** Hague, William

**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 30 through 37

Bill,

We are in receipt of your email of February 28, 2014 and the following attachments: Confirmation Points Certification – 021314, Excavation Bottom Elevations Period – 020914 to 021314, and Excavation Progress Maps – 012314, – 013014, – 020614, and– 021314. The February 28 email includes information regarding the excavation procedures and certifies that the excavation of Cells 30 through 37 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 30, 31, 32, 33, 34, 35, 36 and 37 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on January 16, 23, 28, 30, and February 4 and 11, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 30 through 37 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevations of the meadow mat. For the areas of Excavation Cells 30 through 37 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 020914 to 021314" showing the Excavation Bottom Elevations for the period 2-9-14 to 2-13-14 and "Confirmation Points Certification – 021314" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 30 through 37:

| Excavation Cell No.* | Bottom Target Coordinate – based on PDI (MSL) | Bottom Target Coordinate – based on Predetermined Bottom Elevations[1] (MSL) | (of the c |
|---|---|---|---|
| 30 | 3.5 | 2.1 | |
| 31 | 3.5 | 2.1 | |
| 32 | 3.5 | 2.1 | |
| 33 | 3.5 | 2.1 | |
| 34 | 3.5 | 2.1 | |
| 35 | 3.5 | 2.1 | |
| 36 | 3.5 | 2.1 | |
| 37 | 3.5 | 2.1 | |

*where meadow mat was not encountered

**elevation based on Surveyed Center Point

[1] Corresponds with the 9 "standardized" excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

Please note Figure: "Excavation Bottom Elevations Period – 020914 to 021314" appears to show current excavation to Stratum D (gray shading) only in Excavation Cells 36 and 37 and Excavation Cells 30 through 35 with cross-hatching depicting "Previously Submitted Data". However, the Special Master is not aware of a previous submittal showing Cells 30 through 35 with gray shading denoting being excavated to Stratum D and Table: "Confirmation Points Certification – 021314"reports that Stratum D was reached in portions of Excavation Cells 30 through 37. Please confirm whether the Figure is correct.

Honeywell also provided confirmation that the southern limit of excavation of cells 30 through 37 terminates at the less than ("<")20 ppm line (delineated by Honeywell) at the bottom of excavation and [the cells] are cut back at a stable slope beyond the 20ppm line.

In addition, the Special Master acknowledges Plaintiffs' March 5, 2014 correspondence regarding excavation of cells 30-39 where Plaintiffs noted they believe that Honeywell has excavated cells 30 through 39 to the appropriate depth.

Following confirmation of the question raised above regarding the depiction of areas excavated to the meadow mat, the Special Master has no objection to Honeywell's proposal to backfill Cells 30 through 37.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, February 28, 2014 10:29 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 26 through 29

Steve,

We are providing this email notification that our contractor is read to backfill Cells 30 through 37.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following individual periods:

01/17/14 to 01/23/14 - Cells 30 and 31
01/24/14 to 01/30/14 – Cells 32 and 33
01/31/14 to 02/06/14 – Cells 34 and 35
02/07/14 to 02/13/14 – Cells 36 and 37

- *The majority of the bottom of Cells 30 through 37 were terminated in Stratum D. The Southern limit of cells 30 through 37 were terminated in Stratum O <20 PPM soils. Area 4 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *An Excavation Bottom Elevation Figure is included for Cells 30 through 37.*
- *Confirmatory Bottom Points located within Cells 30 through 37 are shown on the Excavation Bottom Elevation figure.*
- *A Confirmatory Sidewall Sample for Cell 31, 32,33, and 35 are also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 30 through 37.*

- *The northern limits of Cells 30 through 37 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 30 and 37 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps for each grouping of cells are provided*
- *Excavation is continuing in Cells 38 and 39.*
- *Amec confirms that all survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Note that this submittal includes the additional "four corner points" identifying the surveyed locations and elevations of excavation bottoms which were completed above the meadow mat consistent with our comment responses to the parties.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:43 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 38 and 39

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, March 07, 2014 2:19 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 38 and 39

Bill,

We are in receipt of your email of March 3, 2014 and the following attachments: Confirmation Points Certification – 022014, Excavation Bottom Elevations Period – 021414 to 022014, and Excavation Progress Map – 022014. The March 3 email includes information regarding the excavation procedures and certifies that the excavation of Cells 38 and 39 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 38 and 39 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on February 11 and 18, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 38 through 39 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevations of the meadow mat. For the areas of Excavation Cells 38 and 39 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 021414 to 022014" showing the Excavation Bottom Elevations for the period 2-14-14 to 2-20-14 and "Confirmation Points Certification – 022014" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 38 and 39:

| Excavation Cell No.* | Bottom Target Coordinate – based on PDI (MSL) | Bottom Target Coordinate – based Predetermined Bottom Elevations[1] (MSL) | Actual Coordinate (of the confirmatory bottom samp (MSL) |
|---|---|---|---|
| 38 | 3.5 | 2.1 | 2.1 |
| 39 | 3.5 | 2.1 | 2.0 |

*where meadow mat was not encountered

[1] Corresponds with the 9 "standardized" excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

Honeywell also provided confirmation that the southern limit of excavation of cells 38 and 39 terminates at the less than ("<")20 ppm line (delineated by Honeywell) at the bottom of excavation and [the cells] are cut back at a stable slope beyond the 20ppm line.

In addition, the Special Master acknowledges Plaintiffs' March 5, 2014 correspondence regarding excavation of cells 30-39 where Plaintiffs noted they believe that Honeywell has excavated cells 30 through 39 to the appropriate depth.

The Special Master has no objection to Honeywell's proposal to backfill Cells 38 and 39.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, March 03, 2014 8:03 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 38 and 39

Steve,

We are providing this email notification that our contractor is read to backfill Cells 38 and 39.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following individual period: 02/14/14 to 02/20/14 – Cells 38 and 39

Please note that we will be sending to your attention later today the SOP you requested for excavation depth/ survey confirmation.

- *The majority of the bottom of Cells 38 and 39 were terminated in Stratum D. The Southern limit of cells 38 and 39 were terminated in Stratum O <20 PPM soils. Area 4 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *Excavation Bottom Elevation Figures are included for each of the cell groupings noted above.*
- *Confirmatory Bottom Points located within Cells 38 and 39 are shown on the Excavation Bottom Elevation figures.*
- *A Confirmatory Sidewall Sample for Cell 39 is also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 38 and 39.*
- *The northern limits of Cells 38 and 39 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 38 and 39 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*

- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps for Cells 38 and 39. Excavation is continuing in Cells 40 and 41.*
- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Note that this submittal includes the additional language regarding certification that elevations of excavation bottoms were at or below design excavation elevations and representative of final excavation complete grade(s) throughout the portion of cells where we did not encounter Stratum D.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 40 through 43

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, March 28, 2014 4:21 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 40 through 43

Bill,

We are in receipt of your email of March 23, 2014 and the following attachments: Confirmation Points Certification – 022714 and Confirmation Points Certification – 030614 containing the Confirmation Points Certification Tables and the following figures: Excavation Bottom Elevations - Period 022114 to 022714, Excavation Bottom Elevations Period - 022814 to 030614, Excavation Progress Map – 022714, and Excavation Progress Map – 030614. The March 23 email includes information regarding the excavation procedures and certifies that the excavation of Cells 40 through 43 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 40 through 43 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on February 18 and 25 and March 4 and March 11, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 40 through 43 were excavated to the meadow mat and the attached tables and survey elevations report the final survey elevation of the meadow mat. For the areas of Excavation Cells 40 through 43 that were not excavated to the meadow mat, Honeywell provided the following figures and tables: Excavation Bottom Elevations Period – 022114 to 022414 (Figure), Excavation Bottom Elevations Period – 022814 to 030614 (Figure) and ENTACT Letters of Transmittal dated March 11, 2014 (re: Survey Data and Verification – Cells 40 and 41) and March 14, 2014 (re: Survey Data and Verification – Cells 42 and 43) that compare the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation and the Bottom Target Coordinates based on the Predetermined Bottom Elevations versus the Surveyed Center Point Elevation that shows the following for Excavation Cells 40 through 43:

| Excavation Cell No.* | Reference Table 1.2 | | Referenc | |
|---|---|---|---|---|
| | Bottom Target Coordinate – based on PDI (MSL) | Actual Coordinates (of the confirmatory bottom sample survey point) (MSL) | Bottom Target Coordinate – based Predetermined Bottom Elevations** (MSL) | T |
| 40 | 1.7 | 0.0 | 0.4 | |
| 41 | 0.4 | 0.1 | 0.4 | |
| 42 | 0.4 | 0.1 | 0.4 | |

| | | | |
|---|---|---|---|
| 43 | 0.5 | 0.1 | 0.4 |

*where Stratum D (meadow mat) was not encountered

** Correspond to the 9 “standardized” excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

In addition, Honeywell confirmed in the email that “All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.” In addition, the ENTACT transmittals include a verification that Maser Consulting, P.A. (“Maser)has surveyed the bottom of excavations and that the final excavation grade(s) are at or below the design excavation grades throughout the corresponding excavation cells and a certification from Maser that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.

Honeywell also provided confirmation that the Southern Limit of excavation of Cells 40, 41, 42, and 43 terminate at the less than (“<”)20 ppm line (delineated by Honeywell) at the bottom of excavation and [the cells] are cut back at a stable slope beyond the 20ppm line and that Standardized Excavation Interval - Area 7 was excavated down to Stratum D.

Lastly, the Special Master acknowledges Plaintiffs' March 28, 2014 email regarding excavation of cells 40-43 where Plaintiffs noted they believe cells 40 through 43 have been excavated to the appropriate depth.

The Special Master has no objection to Honeywell's proposal to backfill Cells 40 through 43.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, “LB”), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, March 23, 2014 7:33 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 40 through 43

Steve,

We are providing this email notification that our contractor is read to backfill Cells 40, 41, 42 and 43.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following individual periods:

02/21/14 to 02/27/14 – Cells 40 and 41
02/28/14 to 03/06/14 – Cells 42 and 43

- *The majority of Cells 40 and 41 were terminated in Stratum D. Approximately half of the bottom of Cells 42 and 43 were terminated in Stratum D. The Southern limit of cells 40, 41, 42 and 43 were terminated in Stratum O <20 PPM soils. Area 7 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *The Excavation Bottom Elevation Figures is included for the cells noted above.*
- *Confirmatory Bottom Points located within Cells 40, 42 and 43 are shown on the Excavation Bottom Elevation figures.*
- *Confirmatory Sidewall Samples for Cell 40 and 42 are also shown on the Excavation Bottom Elevation figures.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 40 and 41 and Cells 42 and 43 for each of the weekly periods.*
- *The northern limits of Cells 40, 41, 42 and 43 consist of sheet pile Barrier Wall. The Southern Limit of excavation of Cells 40, 41, 42 and 43 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps for each grouping are provided. Excavation is continuing in Cells 44 through 48.*
- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Note that this submittal includes the additional language regarding certification that elevations of excavation bottoms were at or below design excavation elevations and representative of final excavation complete grade(s) throughout the portion of cells where we did not encounter Stratum D.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, March 06, 2017 10:00 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA6South excavation of cells 44-52

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

---

**From:** Karpatkin, Jeremy C. [mailto:Jeremy.Karpatkin@apks.com]
**Sent:** Monday, March 06, 2017 9:58 AM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Subject:** FW: SA6South excavation of cells 44-52

_____
Jeremy C. Karpatkin
**Arnold & Porter Kaye Scholer LLP**
601 Massachusetts Ave., NW | Washington | DC 20001-3743
T: +1 202.942.5564 | F: +1 202.942.5999
jeremy.karpatkin@apks.com | www.apks.com

---

**From:** segnaczyk@louisberger.com
**Sent:** Thursday, April 17, 2014 4:12 PM
**To:** Hague, William
**Cc:** aantonian@connellfoley.com; kcoakley@connellfoley.com; lwalsh@connellfoley.com; tlewis@louisberger.com; Daneker, Michael D.; Karpatkin, Jeremy C.; Morris, John (MTO); 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; kmillian@tpmlaw.com; Graham, Stephanie; 'A. Kim Bell Hosea'; b.bell@cea-enviro.com; bross@disposalsafety.com; rgtspecialmaster@aol.com; aalcorn@tpmlaw.com
**Subject:** RE: SA6South excavation of cells 44-52

Bill,
Letter was received.
Thanks, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, April 17, 2014 4:04 PM
**To:** Egnaczyk, Steve
**Cc:** 'Agnes Antonian'; 'Kevin Coakley'; 'Liza M. Walsh'; Lewis, Thomas; Daneker, Michael; 'Jeremy Karpatkin'; Morris, John (MTO); 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; Kathleen L. Millian; Graham, Stephanie; 'A. Kim Bell Hosea'; 'Bruce A. Bell'; BRoss@disposalsafety.com; 'Senator Robert Torricelli'; Alicia Clark Alcorn
**Subject:** RE: SA6South excavation of cells 44-52

Steve
Our response to this letter you reference went out about ½ hour ago at 3:25.
Let me know if you have an issue getting access.

Regards
Bill

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, April 17, 2014 3:52 PM
**To:** Hague, William
**Cc:** 'Agnes Antonian'; 'Kevin Coakley'; 'Liza M. Walsh'; Lewis, Thomas; Daneker, Michael; 'Jeremy Karpatkin'; Morris, John (MTO); 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; Kathleen L. Millian; 'A. Kim Bell Hosea'; 'Bruce A. Bell'; BRoss@disposalsafety.com; 'Senator Robert Torricelli'; Alicia Clark Alcorn
**Subject:** RE: SA6South excavation of cells 44-52

Bill,

Could you please provide the status of your reply to Plaintiff's letter regarding excavation of cells 44-52?

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Alicia Clark Alcorn [mailto:aalcorn@tpmlaw.com]
**Sent:** Friday, April 11, 2014 12:33 PM
**To:** 'Senator Robert Torricelli'
**Cc:** 'Agnes Antonian'; 'Kevin Coakley'; 'Liza M. Walsh'; Lewis, Thomas; Egnaczyk, Steve; 'Michael Daneker'; 'Jeremy Karpatkin'; 'Hague, William'; 'John Morris (john.morris@honeywell.com)'; 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; Kathleen L. Millian; 'A. Kim Bell Hosea'; 'Bruce A. Bell'; BRoss@disposalsafety.com
**Subject:** SA6South excavation of cells 44-52

Please see the attached.

Alicia C. Alcorn
Terris, Pravlik & Millian, LLP
1121 12th Street N.W.
Washington, DC 20005-4632
Main Telephone: 202-682-2100 ext.8471
Direct Dial: 202-204-8471
Facsimile: 202-289-6795
E-Mail: aalcorn@tpmlaw.com

The information in this e-mail is intended only for the use of the designated recipient(s) and may contain confidential and privileged information. If the reader of this e-mail is not the intended recipient(s), you are hereby notified that you have received this e-mail in error and that any review, dissemination, distribution, or copying of this message is strictly prohibited. If you have received this e-mail in error, please notify the sender by reply e-mail and destroy all copies of the original e-mail.

---

This communication may contain information that is legally privileged, confidential or exempt from disclosure. If you are not the intended recipient, please note that any dissemination, distribution, or copying of this communication is strictly prohibited. Anyone who receives this message in error should notify the sender immediately by telephone or by return e-mail and delete it from his or her computer.

For more information about Arnold & Porter Kaye Scholer LLP, click here:
http://www.apks.com

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 17, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Response to Comments Provided by Plaintiffs, April 11, 2004**
**Excavation of Cells 44 Through 52**
**Study Area 6 South**

Dear Senator Torricelli:

Honeywell has attached a memorandum prepared by its engineer, Amec, responding to comments provided by Plaintiffs on April 11th, pertaining to the excavation of cells 44 through 52 in Study Area 6 South.

If you have any questions, please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:sgf

Encl: 04/17/14 Amec Memorandum re: Response to Comments on Study Area 6 South – Excavation of Cells 44 Through 52

cc: (electronic copy only)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell

John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

**Memo**

| | | | |
|---|---|---|---|
| Date: | **4/17/2014** | cc: | **John Morris, Maria Kaouris, John Mojka, Jeremy Karpatkin, Michael Daneker** |
| From: | **Joe Clifford/Geoff Shallard** | | |
| To: | **Bill Hague** | | |
| Subject: | **Response to Comments on Study Area 6 South – Excavation of Cells 44 Through 52** | | |

AMEC Environment & Infrastructure, Inc. (Amec), on behalf of Honeywell, has prepared the following responses to the comments that were submitted by Plaintiffs regarding the Study Area 6 South – Excavation of Cells 44 through 52 in a letter dated April 11, 2014. For convenience, Amec has listed each comment from Terris, Pravlik & Millian, LLP and the corresponding technical response from Amec.

## Responses to Comments from Terris, Pravlik and Millian (TPM)

**Terris, Pravlik and Millian Comment (TPM-1):**
*On March 3, 2014, Honeywell provided the SA-6 South Standard Operating Procedure Confirmation of Excavation Limits ("SOP"). Plaintiffs are in the process of reviewing and preparing technical comments on the SOP which we will circulate to all parties in the near future. However, we note that the documentation of the excavation of cells 42-52 provided by Honeywell does not conform to the requirements of Honeywell's SOP.*

**Amec Response:** Contrary to the Plaintiffs' assertion, Amec believes that the documentation of cells 44-52 (we assume the 42-52 was a typographical error) is being provided in conformance with the Honeywell SOP as explained in Amec's second response below.

**Terris, Pravlik and Millian Comment (TPM-2):**
*In Particular, the SOP (p.3) states that for the bottom excavation in excavation areas where Stratum D is encountered, "[t]he Surveyor documents the elevations at the approximate corners and center of each excavation cell and other points that they deem necessary to prepare the topographic survey." With respect to cells 44-52, the documentation provided by Honeywell does not include survey data for the corner points of the Stratum D excavation area within each cell. If these data were collected, Honeywell should provide the data to the Special Master and parties. If the corner points data were not collected, we request that Honeywell provide an explanation as to why the SOP is not being followed. In addition, if the data were not collected,*

AMEC
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
Tel 609-689-2829
Fax 609-689-2838
amec.com

*Honeywell should require that the contractors go back and collect all the data points required by the SOP.*

**Amec Response:** Amec confirms that the surveyor has collected the data necessary to prepare the topographic map as indicated in the first bullet of Section 5.0 in the SOP. The topographic map will be prepared to meet the requirements of Section 02315 Part 3.03 Topographic Surveys, Part C. Post Excavation Survey of the Technical Specifications. Copies of the survey points at Stratum D approximate to the corners of cells 44-52 are attached. The topographic survey will be provided as part of the final certification.

**Terris, Pravlik and Millian Comment (TPM-3):**
*Based upon the documentation provided by Honeywell regarding the excavation areas within cells 44-52 that were excavated to a depth other than the Stratum D, plaintiffs concur that Honeywell has excavated those areas to the appropriate depth. As to the excavation areas within cells 44-52 that were to be excavated to the Stratum D, plaintiffs will wait for Honeywell's response to these comments prior to making a determination as to whether excavation was to the appropriate depth.*

**Amec Response:** The requested information has been provided as noted above.

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

−2.2 −2.5 −2.6 −2.5 −2.6 −3.2 −3.3 −3.3

−2.8 −3.1

9 58 57 56 55 54 53 52 51 50 49 48 47 46 45 44 43 42 41 40 39 38

BOT OF EXC
AREA 6 = (2.50)

−3.7

BOT OF EXC
AREA 7 = (1.20)

−2.7 −2.8 −3.8

−2.7 −3.3 −3.3 −2.8 −2.8 −3.3

BOT OF EXC
AREA 8 = 0.40

LIMIT OF STRATUM D EXPOSURE PER
THIRD PARTY SURVEY (TYP)

BOT OF EXC
AREA 9 = (1.20)

LIMIT OF ANTICIPATED STRATUM D
EXPOSURE PER DESIGN (TYP)

−3.8 BOE ELEVATION AT EDGE OF STRATUM D
PER THIRD PARTY SURVEY (TYP)

0 5 10 20
SCALE IN FEET

Prepared/Date: TDD 4/18/14
Checked/Date: SGS 4/18/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD, BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | SA-6 SOUTH<br>STRATUM D CELLS 44 THRU 52<br>FIGURE 1 |

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:55 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6S : Excavation Completion in Cells 44 through 48

Same as last email, don't see an acknowledgement from SM, use this as placeholder.

---

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:44 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Subject:** FW: SA-6S : Excavation Completion in Cells 44 through 48

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, April 06, 2014 1:11 PM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; Daneker, Michael <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 44 through 48

Steve,

We are providing this email notification that our contractor is read to backfill Cells 44, 45, 46, 47 and 48.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following two individual periods:

03/07/14 to 03/13/14 – Cells 44 and 45
03/14/14 to 03/20/14 – Cells 46, 47 and 48

- *Approximately half of the bottom of Cells 44 and 45 were terminated in Stratum D. The Southern limit of cells 44 and 45 were terminated in Stratum O <20 PPM soils. Area 7 was carried down to Stratum D.*

- *Approximately 30-40% of the bottom of Cells 46, 47 and 48 were terminated in Stratum D. The Southern limit of cells 46, 47 and 48 were terminated in Stratum O <20 PPM soils. Area 7 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises up to 2 feet above the general elevation of the Stratum D on these cells. The ridge appears to be more prominent as the excavation has advanced to the west. The ridge is part of the contiguous Stratum D geologic horizon.*
- *A significant number of pilings are being encountered. The pilings supported the 60 Kellogg St warehouse structure. Pilings are being sheared flush with the bottom of excavation.*
- *Excavation Bottom Elevation Figures are included for the cells noted above.*
- *Confirmatory Bottom Points located within Cells 44, 45, 46, 47 and 48 are shown on the Excavation Bottom Elevation figure.*
- *A Confirmatory Sidewall Sample 125-SB-067 for Cell 44 and Sample 125-PT-15 for Cell 47 are also shown on the respective Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 44 and 45 for the week ending 03/13/14 and Cells 46, 47 and 48 for the week ending 03/20/14.*
- *The northern limits of Cells 44, 45, 46, 47 and 48 consist of sheet pile Barrier Wall. The Southern Limit of excavation of Cells 44, 45, 46, 47 and 48 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials. There are several joints where excess grout from the grouted joint is evident adhering to the sheets. Some grout that is strongly adhering to the sheet was left in place.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation Progress Maps are provided. Excavation is continuing in Cells 49 and 50.*
- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Thanks
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 49 through 52

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, April 09, 2014 10:53 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 49 through 52

Bill,
Thanks very much. Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, April 09, 2014 10:50 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 49 through 52

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 49, 50, 51 and 52.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 03/21/14 to 03/27/14.

- *Approximately 60% of the bottom of Cells 49, 50, 51 and 52 were terminated in Stratum D. The Southern limit of cells 49, 50, 51 and 52 were terminated in Stratum O*

- *An Excavation Bottom Elevation Figure is included for the cells noted above.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises above the general elevation of the Stratum D on these cells. The ridge is part of the contiguous Stratum D geologic horizon.*
- *A significant number of pilings continue to be encountered. The pilings supported the 60 Kellogg St warehouse structure. Pilings are being sheared flush with the bottom of excavation.*
- *Confirmatory Bottom Points located within Cells 49, 50, 51 and 52 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples 125-SB-081 for Cell 49, 125-SB-091 for Cell 50, 125-SB-080 for Cell 51 and 125-SB-092 for Cell 52 are also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 49, 50, 51 and 52.*
- *The northern limits of Cells 49, 50, 51 and 52 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 49, 50, 51 and 52 terminate at the*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Maps is provided. Excavation is continuing in Cells 53 and 54.*

- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Please note that additional lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the southern limits of Cells 50, 51 and 52, Stratum O is divided by the line separating designated Area 8 from Area 9.

Thanks
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:54 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6S : Excavation Completion in Cells 53 through 56

Eric, there was a period in time where the SM had my email incorrect, so I don't think I have the acknowledgement for this one. Use this as placeholder

---

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:45 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Subject:** FW: SA-6S : Excavation Completion in Cells 53 through 56

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, April 11, 2014 8:32 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; Daneker, Michael <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 53 through 56

Steve,

We are providing this email notification that our contractor is read to backfill Cells 53, 54, 55 and 56.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 03/28/14 to 04/04/14.

- *Approximately 40% of the bottom of Cells 53, 54, 55 and 56 were terminated in Stratum D. The Southern limit of cells 53, 54, 55 and 56 were terminated in Stratum O <20 PPM soils.*

- *An Excavation Bottom Elevation Figure is included for the cells noted above.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises above the general elevation of the Stratum D on these cells. The ridge is part of the contiguous Stratum D geologic horizon. Portion of the top of the ridge was removed in Cells 55 and 56 to permit clean excavation to the Area 8 boundary.*
- *Lines has been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the southern limits of Cells 53, 54, 55 and 56 the Stratum O is divided by Area 8, Area 9 and Area 10*
- *Pilings from the 60 Kellogg St warehouse were sheared flush with the bottom of excavation.*
- *Confirmatory Bottom Points located within Cells 53, 54, 55 and 56 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples 125-SB-079 for Cell 53, and 125-SB-087, 125-SB-080 for Cell 56, are also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 53, 54, 55 and 56*
- *The northern limits of Cells 53, 54, 55 and 56 consist of sheet pile Barrier Wall. The Southern Limit of excavation of Cells 53, 54, 55 and 56 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided. Excavation is continuing in Cells 57 and 58.*

- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Thanks
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 57 & 58

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, May 01, 2014 5:23 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 57 & 58
**Importance:** High

Bill,

The Special Master is in receipt of your April 28, 2014 email and the supporting documentation regarding Excavation Completion in Cells 57 and 58 and the notification that the contractor is ready to backfill Cells 57 and 58. We have no objection to Honeywell's proposal to backfill Cells 57 and 58.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, April 28, 2014 7:49 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 57 & 58

Steve,

We are providing this email notification that our contractor is read to backfill Cells 57 and 58.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 04/05/14 to 04/11/14.

- *Approximately 40% of the bottom of Cells 57 and 58 were terminated in Stratum D. The Southern limit of cells 57 and 58 were terminated in Stratum O <20 PPM soils.*
- *An Excavation Bottom Elevation Figure is included for the cells noted above.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises above the general elevation of the Stratum D on these cells. The ridge is part of the contiguous Stratum D geologic horizon. Portion of the top of the ridge was removed in cells 57 and 58 to permit clean excavation to the Area 8 boundary.*
- *Lines has been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the southern limits of Cells 57 and 58 the Stratum O is terminated at the respective Area 8 and Area 10 excavation elevations.*
- *Pilings from the 60 Kellogg St warehouse were sheared flush with the bottom of excavation.*
- *Confirmatory Bottom Points located within Cells 57 and 58 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples. There were no confirmatory sidewall samples in cells 57 and 58.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 57 and 58.*
- *The northern limits of Cells 57 and 58 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 57 and 58 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided. Excavation has been temporarily terminated in Cell 59. The excavation and backfill faces will be stabilized and excavation will be started at the western portion of the site in Cell 153/154.*

- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Also please find attached the Figure 1 showing Stratum D corner elevations as discussed at our last all parties meeting. We had previously sent this figure for Cells 44-52 in response to plaintiffs comments, so we are herein attaching the figure for Cells 53-58.

Thanks
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road

Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:12 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 59 through 68

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, December 12, 2014 11:47 AM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JWatson@jcnj.org; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; Morris, John (MTO) <John.Morris@honeywell.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 59 through 68

Bill,

The Special Master is in receipt of your November 24, 2014 email and the supporting documentation regarding Excavation Completion in Cells 59-68 and your notification that the requirements to allow backfilling have been met. Honeywell has also reported that as indicated in the previous submittal for Cells 69-75, the lens of anomalous white material approximately 2 feet below ground surface (BGS) was also observed in Cells 68 to 61. Consistent with the response to Cells 69 to 75 and as reported in Honeywell's November 17 response to Plaintiffs' November 11, 2014 email, the anomalous white material was previously identified and sampled during the PDI program and found to be less than 20 ppm hexavalent chromium in all locations shown on the updated Figure 1. Honeywell further reported in the November 17 response that an additional sample of the material was collected at the same depth during the active excavation and this result was also reported at less than 20 ppm hexavalent chromium.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, November 24, 2014 12:31 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael;

JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 59 through 68

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 59 through 68.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 10/17/14 to 10/30/14.

This Excavation Submittal includes Cells 59 through 68.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- As indicated in the previous submittal for cells 69-75 Amec inspectors identified a lens of white material approximately 2 ft. below ground surface. This lens was also observed in Cells 68 to 61. Based on review of the PDI data and a targeted sample taken from the lens at the time of excavation that lens shows no indication of the presence of chromium above 20 mg/KG. The extent and testing of the lens has been addressed in previous emails with the Special Master and Plaintiffs.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas in the Cells 59 through 68.
- The bottom of excavation for Area 11 and Area 14 were both terminated in Stratum D.
- The bottom of excavation for Areas 8, 10 and 12 were terminated in Stratum O, at or below the respective Excavation Bottom Elevations.
- The contiguous excavation in SA-6S between Cell 1 and Cell 156 is complete excluding the deferred Area by the Hackensack River.
- Excavation will proceed in Site 163 and the lens of anomalous material extending south of Cell 104.
- Confirmatory Bottom Points are located within Cells 59, 61, 63, 64 66, 67, and 68. Reference Points were also used in Cells 59, 60, 61, 62, 63, 65, 66, 67, and 68.
- The northern excavation limit was the Barrier Wall.
- The southern limit of Cells 59 through Cell 68 is sloped excavation.
- There were Confirmatory Sidewall Samples in Cells 59, 60, 61, 64, 65, 67, and 68.

As previously discussed, we intend on issuing a separate certification email on the Site 163 shallow excavation and an amended certification once the Cell 104 anomalous material excavation is complete.

Regards,

Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, December 01, 2014 10:32 AM
**To:** Ambrose, David M; Shallard, Samuel G.
**Cc:** Bills, Stuart B; Christodoulatos, Eric G
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 69-75

This is the last set of cells that SM has responded to.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, November 26, 2014 10:01 AM
**To:** 'Hague, William'; Clifford, Joseph T
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 69-75

Bill/Joe,

The Special Master is in receipt of your November 3, 2014 email and the supporting documentation regarding Excavation Completion in Cells 69-75 and your notification that the requirements to allow backfilling have been met. In addition, the Special Master is in receipt of Honeywell's November 17 email response and updated Figure 1 showing locations of additional analytical information and the extent of the observed anomalous white material in response to Plaintiffs' November 11, 2014 email. As reported in Honeywell's November 17 response, the anomalous white material was previously identified and sampled during the PDI program and found to be less than 20 ppm hexavalent chromium in all locations shown on the updated Figure 1. Honeywell then collected an additional sample of the material at the same depth during the active excavation and this result was also reported at less than 20 ppm hexavalent chromium.

Regards, Steve

**Steven J. Egnaczyk**
Program Director | Environmental and Disaster Management Services

direct +1.610.363.5395
mobile +1.610.212.1492
fax +1.610.363.5390
email segnaczyk@louisberger.com
web louisberger.com

**Louis Berger**
350 Eagleview Boulevard | Exton | PA | 19341-1178| USA

*Celebrating 60 Years*

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Monday, November 03, 2014 2:37 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 69-75

Steve,

I am providing this email on behalf of Honeywell.

We are providing this email notification that our contractor is ready to backfill Cells 69 through 75.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 10/03/14 to 10/16/14.

This Excavation Submittal includes Cells 69 through 75.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors identified a lens of white material approximately 2 ft. below ground surface over at the southern end of Cell 70. Review of the PDI data shows sidewall soil samples at a similar depth interval ( 140-SB-025, 140-SB-034 and 140-SB-072) indicated hexavalent chromium results that were
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas in the Cells 69 through 75.
- Area 14 was terminated in Stratum D.
- Areas elevations for 8, 12 and 13 were terminated in Stratum O at or below at the respective Excavation Bottom Elevations.
- Excavation will proceed from Cell 68 to the east.
- The excavation will continue through Cell 59 at which point it will connect to the previously excavated area of Cells 1 through 58.
- Confirmatory Bottom Points located within Cells 75, 74, 73, 72, 71, 70 and 69.
- The northern excavation limit was the Barrier Wall.

- The southern limit of Cells 69 through the eastern portion of Cell 71 is sloped excavation. The southern limit of the western portion of Cell 71 and Cells 72 through 75 is temporary sheetpile.
- There were Confirmatory Sidewall Samples in Cells 71 (2 locations) and 75.

Regards.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:25 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 76-79
**Attachments:** GCL Area 100314_2.pdf

---

**From:** Clifford, Joseph T
**Sent:** Wednesday, November 05, 2014 10:47 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org; Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 76-79

Steve,

I am providing this email on behalf of Honeywell.

We are providing this response to your clarification request received in an email dated October 30, 2014 regarding the Excavation Complete Submittal on Cells 76 - 79. HON has reviewed the requested information with Amec and can offer the following statements:

- The 100% Design for Cell 76 and 77 indicates excavation to Stratum D at a target elevation of -2.5 feet.
- After reaching the Stratum D layer within the excavation, Amec inspectors identified a limited discontinuity in the Stratum D surface.
- Amec instructed the contractor to remove additional material which revealed that the discontinuity was smaller than thought, and then directed the contractor to repair the area using GCL in accordance with 100% Design.
- Amec confirms that the excavation limits and the repaired area both meet the requirements of the 100% Design.

We are also including an updated figure of the actual GCL repair area, with the “drawing scale” now added, in response to a separate email request from Kim Hosea received on October 27, 2014.

Please let us know if you need more information on this item.

Regards.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, October 30, 2014 6:28 PM
**To:** Hague, William; Clifford, Joseph T
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 76-79

Bill/Joe,

The Special Master is in receipt of your October 24, 2014 email and the supporting documentation regarding Excavation Completion in Cells 76-79 and your notification that the requirements to allow backfilling have been met. Honeywell reports that in the southern limit of Cells 76/77 there were portions of the Stratum D material missing. Honeywell also reports their contractor successfully completed repairs to this area. Please provide a certification which confirms that: 1) impacted soils as defined in the 100% Design were removed from the discontinuous area to the design depth for Excavation Area 14, and 2) the area was repaired and the requirements to allow backfilling as required in the 100% Design were met.

Regards, Steve

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Friday, October 24, 2014 7:27 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 76-79

Steve,

I am providing this email on behalf of Honeywell.

We are providing this email notification that our contractor is ready to backfill Cells 76 through 79.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 09/25/14 to 10/02/14.

This Excavation Submittal includes Cells 76 through 79.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- The northern excavation limit was the Barrier Wall.
- The southern limit is temporary sheet pile.
- There was one Confirmatory Sidewall Samples in Cell 77.
- All Cells are in Area 14.
- Area 14 was designed to terminate in Stratum D.
- All cells terminated in Stratum D with the exception of an area of discontinuous Stratum D as discussed below.
- At the southern limit of Cell 76/77, a discontinuity was identified in the Stratum D. The area of the discontinuity is shown on the attached Figure titled “As Built GCL Area Cells 75, 76 and 77”. There appeared to be a vertical displacement downward in the stratum D along the western edge of the area shaded in yellow on the figure. Excavation revealed that the Stratum D sloped back up to the typical Stratum D top elevation along the eastern edge of the area. To establish continuity in the Stratum D a Geosynthetic Clay Liner (GCL) was deployed over the area as depicted by the green shading on the figure. The Stratum D was continuous east of the repair area.
- The Confirmatory Bottom Point sample locations are provided for Cells 76 through 79.
- Excavation will proceed from Cell 75 to the east.

Regards.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Monday, October 20, 2014 10:49 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 80 through 83

**Importance:** High

**Follow Up Flag:** Follow up
**Flag Status:** Completed

*Stuart B. Bills*
**Senior Associate Construction Manager**
**AMEC E&I, Inc.**
**(252) 202-1411**

**stuart.bills@amec.com**
**www.amec.com**

***Confidentiality Notice: The above message may contain information covered by the attorney-client and/or litigation work product privileges. The message should be treated as Privileged and Confidential unless specifically stated otherwise within the message. If you are not the intended recipient of this message, please delete it immediately and notify the sender of the error. This message should not be forwarded without the approval of counsel.***

---

**From:** Clifford, Joseph T
**Sent:** Monday, October 20, 2014 10:25 AM
**To:** Shallard, Samuel G.; Bills, Stuart B; Nagg, Dennis E
**Cc:** Ambrose, David M; Mojka, John
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 80 through 83
**Importance:** High

Good to go.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, October 15, 2014 9:51 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 80 through 83
**Importance:** High

Bill,

The Special Master is in receipt of your October 10, 2014 email and the supporting documentation regarding Excavation Completion in Cells 80-83 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, October 10, 2014 1:14 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 80 through 83

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 80 through 83.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 09/05/14 to 09/25/14.

This Excavation Submittal includes Cells 80 through 83.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- Cells 80 through 83 are all in Area 14 which was designed to terminate in Stratum D.
- Cells 80 through 83 all terminated in Stratum D.
- The Confirmatory Bottom Point sample locations are provided for Cells 80 through 83 on the attached Excavation Bottom Map.
- The northern excavation limit was the Barrier Wall.
- The southern limit is partially temporary sheet pile (Cell 80 and part of 81) and partially sloped excavation (Cell 83, 82 and part of 81).
- There were Confirmatory Sidewall Samples in Cells 80, 82 and 83.
- Excavation will proceed from Cell 79 to the east.

Regards,

Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:15 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 84-89

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, October 16, 2014 1:12 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amec.com>; Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 84-89

Joe,
Thanks very much. Steve

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Thursday, October 16, 2014 11:58 AM
**To:** Egnaczyk, Steve; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 84-89

Steve,

I am sending this email on behalf of Honeywell.

Per your request, attached please find the Maser Consulting Survey Data Table inclusive of Cells 84 - 89 with the signed ENTACT Letter of Transmittal cover page.

This attachment replaces the one submitted in the original email from Bill Hague on October 2, 2014 which did not include the ENTACT transmittal.

Please let us know if you need any other information relative to Cells 84 – 89 completion submittal.

Regards.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, October 15, 2014 9:49 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 84-89
**Importance:** High

Bill,

The Special Master is in receipt of your October 2, 2014 email and the supporting documentation regarding Excavation Completion in Cells 84-89 and the notification that the contractor is ready to backfill these Cells. Consistent with previous submittals, please either provide the ENTACT Letter of Transmittal with the signed Survey Data Verification, confirming that Maser Consulting, P.A. ("Maser) has surveyed the bottom of excavations and that the final excavation grade(s) are at or below the design excavation grades throughout the corresponding excavation cells or confirmation that this verification is not applicable to this submittal.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, October 02, 2014 7:38 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 84-89

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 84 through 89.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 08/22/14 to 09/04/14.

This Excavation Submittal includes Cells 84 through 89.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All cells were terminated were terminated in Stratum D.
- Confirmatory Bottom Points located within Cells 89, 88, 87, 86, 85. A Reference Point was used for Cell 84.
- The northern excavation limit was the Barrier Wall.
- The southern limit is sloped excavation.
- There were Confirmatory Sidewall Samples in Cells 89 and 84.
- It is noted that the southerly limit of the <20 PPM line was straightened in Cells 84 through 89 and carried further to the south to simplify excavation geometry in this area. We excavated in a straight line between 134-SB-100 (Cell 89) and 140-SB-059 (Cell 83) to simply excavation rather than jogging back in to 140-SB-060 (Cell 84). This results in the sidewall sample in Cell 84 (140-SB-060) being located within the final excavation limits.
- Excavation will proceed from Cell 83 to the east.

Regards,
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Friday, September 05, 2014 10:36 AM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 90 through 99

Stuart Bills
AMEC E&I

Sent via the Samsung GALAXY S®4, an AT&T 4G LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:09/05/2014 10:34 (GMT-05:00)
To: "Shallard, Samuel G." ,"Bills, Stuart B"
Cc: "Nagg, Dennis E" ,"Ambrose, David M" ,"Mojka, John"
Subject: FW: SA-6S : Excavation Completion in Cells 90 through 99

Good to go

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, September 05, 2014 10:02 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 90 through 99
Bill,
The Special Master is in receipt of your September 3, 2014 email and the supporting documentation regarding Excavation Completion in Cells 90 through 99 and the notification that the contractor is ready to backfill these Cells.
Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, September 03, 2014 9:37 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 90 through 99
Steve,

We are providing this email notification that our contractor is ready to backfill Cells 90 through 99.
We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.
This submittal notification of SA-6 South excavation completion covers the individual period from 08/08/14 to 08/21/14.
It is noted that a sidewall sample was taken from of a thin lens of grayish material identified directly above the Stratum D in the face of the step up from Area 15 into Area 16 in Cell 104. This sample came back with a validated result of hexavalent chromium > 20 ppm. Further investigation and sampling is being conducted as needed to delineate and remove this material.
As discussed, this over-excavation of the 100% Design footprint (based upon the 20 ppm contour established during the PDI) will result in an amended certification email for affected cells and additional laboratory data on sidewall will be provided once validated.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All cells were terminated were terminated in Stratum D.
- Confirmatory Bottom Points located within Cells 99, 98, 97, 96, 95, 93, 91, and 90.
- The northern excavation limit was the Barrier Wall. The southern limit is sloped excavation
- There were Confirmatory Sidewall Samples in Cells 92 and 96.
- Excavation will proceed from Cell 89 to the east.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:12 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, February 04, 2015 6:23 PM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Ben Davis <bdavis@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41
**Importance:** High

Bill,

The Special Master is in receipt of your January 7, 2015 email and the supporting documentation regarding the Amended Certification for Excavation Complete in Cells 100 to 106A and new Excavation Complete Certification for Area 41 and your notification that the requirements to allow backfilling have been met. Please confirm that the certification statements contained in your email refer to both the expanded excavation in Cells 100 to 106A and Area 41.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, January 07, 2015 2:40 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T;

KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41

**AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41**

Steve,

We are providing an amended certification regarding completion of excavation in Cells 100 to 106A which was originally submitted by Honeywell to the parties by email on August 18, 2014.

As discussed in the September 16, 2014 monthly Special Master meeting/call, Honeywell and Amec indicated that an amended certification would be needed based upon analytical information received on the anomalous material indicating hexavalent concentrations > 20 ppm.

Subsequent to the original submittal, Honeywell also directed Amec to determine the lateral extent of the anomaly and collect additional sidewall soil samples consistent with our approved plans. Honeywell kept the parties informed that the additional delineation would require some time as other site conditions including stockpile management had to be completed by the excavation contractor before a drill rig could access the area.

The investigation resulted in collection of a total of 16 soil samples for hexavalent chromium, 15 of these using a drill rig and the last one collected as a post-excavation sidewall sample (see Figure 10 Anomalous Lens Boring Location Map attached).

The lateral extent of the lens was defined by locations of soil samples 134-SB-170, 134-SB-171, 134-SB175 and 134-SB-177, which all had hexavalent chromium < 20 ppm. This last soil sample designated as 134-SB-177 was collected post-excavation and confirmed to be < 20 ppm. The area was excavated to these soil sample locations in late November/early December and inspected by Amec and resurveyed by Maser on December 8, 2014.

The investigation program confirmed that the lens was present just above the Stratum D. Excavation was continued laterally to the excavation limits or until there was no visible grey lens. Area 41 is a small isolated excavation area identified in the 100% Design which was performed concurrent with the anomaly material excavation. The faces of excavation were inspected by Amec as noted below:

- Coordinates for Survey of the finished excavation to Stratum D are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal.
- The excavation was extended from Cell 104 in a Southwest to West direction.
- The bottom of the excavation followed the surface of the Stratum D.
- The excavation was extended to the limits defined by the investigation.
- The bottom of the excavation was visually inspected by Amec personnel to confirm that all of the grey lens had been removed and Stratum D exposed.
- The sidewall slopes were laid back to provide stable conditions.
- The limits of the excavation were visually inspected by Amec personal to confirm that the grey lens was no longer visible.
- In cases where the lens was determined to still be visible the excavation was expanded and the process repeated until a visibly clean limit was established.

- Additional confirmation sampling was conducted in these cases to provide a sidewall sampling frequency that met the NJDEP Technical Regulation requirements incorporated into the approved 100% Design.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- There was a total of 8 Confirmatory Sidewall Samples, 4 locations for the limits of the Cell 104 anomalous material and 4 locations for Area 41.
- 10 Confirmatory Center Point elevations were recorded consistent with the Cell Layout to provide a record in this submittal of the elevation of the Stratum D. Additional coordinates were surveyed and will be used for production of the excavation bottom survey.

An Amended Excavation Bottom Elevation Map showing the additional area of excavation of visually-impacted concrete and subsequent soil > 20 ppm is attached and highlighted in gray.

The added < 20 ppm soil sample confirmatory locations are also shown on the map. Analytical data for the additional soil samples collected in this excavation area was provided in the SA-6 Monthly Progress Reports and is updated in Figure 10 attached.

The Maser Survey Table showing the confirmatory points has been updated to reflect the added soil sample locations with hexavalent chromium < 20 ppm (highlighted in yellow on page 19 of 20 and labeled as “Lens Area”) which are additional sidewall confirmatory samples for SA-6 South.

As all of the over excavation for this anomalous material extended to Stratum D, no additional bottom samples were necessary.

Lastly, during a recent weekly progress meeting, you asked about a single point in the HON/Amec submittal of Excavation Complete in Cells 59 through 68 (originally submitted on November 24, 2014). Specifically you asked if the table correctly identified the Target Elevation for the Depth of Excavation in the Maser Table for point C-70-3. Amec Engineers have reviewed the Maser table and concur that the Target Depth for point C-70-3 should be 0.4 feet (consistent with the target excavation depth for Area 13) and the corrected Maser table (attached).

Regards
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:37 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal - Area 41

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, February 11, 2015 5:31 PM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; Ben Davis <bdavis@tpmlaw.com> (bdavis@tpmlaw.com) <bdavis@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal - Area 41
**Importance:** High

Bill,

The Special Master is in receipt of your February 9, 2015 email and the supporting documentation regarding Excavation Completion in Area 41 and your notification that the requirements to allow backfilling have been met.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, February 09, 2015 2:48 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal - Area 41

Steve,

We are providing an amended certification regarding completion of excavation in Area 41 which was originally submitted by Honeywell to the parties by email on January 7, 2015.

In response to your questions raised last week via phone call with Amec, we understand that a clarification was requested to certify that the standard inspections were also performed specific to Area 41 and not just Cells 100 to 106A.

As a result, we are providing this amended certification for Area 41 only.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

The following statements and attached data are specific to Area 41:

- Coordinates for Survey of the finished excavation are tabulated in the Maser Tables.
- The bottom of the excavation was terminated in Stratum O.
- One PDI bottom sample location 134-SB-026 is associated with Area 41 and is shaded yellow on Page 9 of the Maser Table.
- The sidewall slopes were laid back to provide stable conditions.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- There was a total of 4 Confirmatory Sidewall Samples for Area 41. These samples and included and shaded yellow on Page 20 of the Maser Table. The samples form the corners of the Excavation.
- The Excavation Bottom Elevation Map showing Area 41 is attached.
- The bottom and sides of the excavation was visually inspected by Amec personnel to confirm there was no indication of visibly impacted soils.
- Backfill in Area 41 has been initiated.

Note that there were no changes needed to the attachments.

Please let us know if you have any other questions on this item.
Regards,
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly

notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Wednesday, August 13, 2014 2:52 PM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

**Importance:** High

Stuart Bills
AMEC E&I
Sent via the Samsung GALAXY S®4, an AT&T 4G LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:08/13/2014 14:10 (GMT-05:00)
To: "Bills, Stuart B" ,"Mojka, John"
Cc: "Kaouris, Maria" ,"Ambrose, David M" ,"Shallard, Samuel G."
Subject: FW: SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

fyi

---

**From:** Egnaczyk, Steve [segnaczyk@louisberger.com]
**Sent:** Wednesday, August 13, 2014 11:32 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

Bill,
The Special Master is in receipt of your August 4, 2014 email and the supporting documentation regarding Excavation Completion in Cells 106B through 118B and 107A through 114A and the notification that the contractor is ready to backfill these Cells.
Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, August 04, 2014 7:59 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T;

Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 106B through 118B and 107A through 114A.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 06/30/14 to 07/14/14.

As previously indicated, select cells are being split into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

Cells 106 through 118 are physically divided into an A and B designation by a peninsula of

Commencing at Cell 105 the cells are no longer divided by the

Please note that the Maser table has been updated to include the missing reference points in Cells 117 and 119.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 106B through 118B and 107A through 114A, the excavation is terminated at the respective Area 15, 16, 17, 18, 24, 28 and 29 excavation elevations.
- Excavation will proceed from Cell 106 to the east to Cell 104.
- Cells 118 B, 117 B, 116B and a significant portion of 115B encountered Stratum D and was terminated accordingly (see Excavation Bottom Elevation figure). In general the northern portion of the excavation (Cells with A designation) was terminated in Stratum O at or below the Target Elevations.
- Stratum D was encountered in the easterly portion of Cell 107 A (Area 15). Area 15 (-4.3 bottom elev.) will be excavated to Stratum D as the excavation moves to the east.
- In Cells 112B to 114B the excavation limits were deepened to beyond the defined chromium impacted soil limits to remove soils below 3 UST's.
- Confirmatory Bottom Points located within Cells 106B through 118B and 107A through 114A are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were Confirmatory Sidewall Samples in Cells 113A, 111A, 109A, 107A, 118B, 116B, 115B, 112B, 110B and 107B.
- The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

Question regarding Cell 117 was addressed in the submittal for Cells 106B through 118B and 107A through 114A, submitted to Parties on August 4, 2014.

**Christodoulatos, Eric G**

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:17 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6S : Excavation Completion in Cells 115a to 120

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, July 24, 2014 9:41 AM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; Daneker, Michael <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 115a to 120

Bill,

I have one (1) question regarding the submittal: Could you please clarify/confirm why there was no entry for Cell 117 on Maser Table 1.4 listing the SA-6 South Excavation: Confirmatory Points (Page 5 of 1) provided with the ENTACT Transmittal)?

Otherwise, the Special Master is in receipt of your July 16, 2014 email and the supporting documentation regarding Excavation Completion in Cells 115a to 120 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, July 16, 2014 8:53 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea

(k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 115a to 120

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 115A to 120.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 06/26/14 to 06/30/14.

As previously indicated, select cells are being split into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

For reporting purposes Cells 120 is treated as a complete cell without the A and B designation.
Cells 115 through 119 are physically divided into an A and B designation by a peninsula of <20 PPM soil.
For this report both the A and B portion of Cell 119 is included.
For Cells 115 through 118 only the A portion is included. The B portion of these cells will be included in future submittals.

.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 121 through 125, the excavation is terminated at the respective Area 17, 18, 19, 20, 21, 22, 24 and 28 excavation elevations.
- Excavation will proceed from Cell 119B to the east to Cell 116B. Excavation will proceed from Cell 114A to the east to Cell 112A.
- A significant portion of the Southern portion of the cells encountered Stratum D and was terminated accordingly (see Excavation Bottom Elevation figure). The northern portion of the excavation was terminated in Stratum O at or below the Target Elevations.
- In Cells 115 to 118 the excavation limits were extended to the south and deepened to beyond the defined chromium impacted soil limits to remove VOC impacted soils
- Confirmatory Bottom Points located within Cells 115A through 120 are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were Confirmatory Sidewall Samples in Cells 115, 117, 119, and 120.

- The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:38 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 121 through 125

-----Original Message-----
From: Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
Sent: Thursday, July 10, 2014 5:51 AM
To: Hague, William
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
Subject: RE: SA-6S : Excavation Completion in Cells 121 through 125

Bill,

The Special Master is in receipt of your July 3, 2014 email and the supporting documentation regarding Excavation Completion in Cells 121 through 125 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

From: Hague, William [william.hague@honeywell.com]
Sent: Thursday, July 03, 2014 10:29 AM
To: Egnaczyk, Steve
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
Subject: SA-6S : Excavation Completion in Cells 121 through 125

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 121 to 125.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 06/11/14 to 06/25/14.

As previously indicated, select cells are being split into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

During daily excavation and survey confirmation, Cells 121 through 125 were completed in full without the need to subdivide into A and B sections. Therefore, in this submittal the full north to south area of each cell was completed without the A/B designation as reflected in the Excavation Bottom Elevation Figure and Maser Tables.

* Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits

* Sheet pile on the excavation face has been cleaned of visible soil materials.

* The bottom and lateral limits of each cell were visually inspected by Amec personnel.

* Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.

* An Excavation Progress Map is provided.

* All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.

* Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 121 through 125, the excavation is terminated at the respective Area 19, 20, 21, 22, 23, 25 26, and 27 excavation elevations.

* Excavation will proceed from Cell 120 to the east to Cell 114. Starting in Cell 120 the excavation will again be split into A and B segments with a peninsula of <20 PPM soils separating the A and B areas.

* A significant portion of the Southern portion of the cells encountered Stratum D and was terminated accordingly (see Excavation Bottom Elevation figure). The northern portion of the excavation was terminated in Stratum O at or below the Target Elevations.

* Confirmatory Bottom Points located within Cells 121 through 125 are shown on the Excavation Bottom Elevation figure.

* The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were no Confirmatory Sidewall Samples in Cells 121 to 125. The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Regards,
Bill

Honeywell

William J. Hague P.E.
Director - Remediation Design & Construction Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com<mailto:william.hague@honeywell.com>

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Friday, June 27, 2014 9:30 AM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 126 to 128

**Importance:** High

**Follow Up Flag:** Follow up
**Flag Status:** Completed

Stuart Bills
AMEC E&I
Sent via the Samsung GALAXY S®4, an AT&T 4G
LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:06/27/2014 09:25 (GMT-05:00)
To: "Bills, Stuart B" ,"Shallard, Samuel G." ,"Nagg, Dennis E"
Cc: "Mojka, John" ,"Kaouris, Maria"
Subject: FW: SA-6S : Excavation Completion in Cells 126 to 128

Fyi.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, June 27, 2014 9:23 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 126 to 128
**Importance:** High

Bill,

The Special Master is in receipt of your June 19, 2014 email and the supporting documentation regarding Excavation Completion in Cells 126 to 128 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, June 19, 2014 8:01 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 126 to 128

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 126 to 128.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 05/22/14 to 06/10/14.

As previously indicated cells are being spilt into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

During daily excavation and survey confirmation Cells 129 through 133 were divided into A and B sections as reflected in the Maser Tables. There is no clean unexcavated dividing line in the middle of site as there was in Cells 137 through 146. For this submittal the full north south area of each cell was completed as indicated in the Excavation Bottom Elevation figure.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 129 to 133, the excavation is terminated at the respective Area 21, 22, 23, 26, 30, 32 and 34 excavation elevations.
- Excavation will proceed from Cell 125 to the east into Cell 123.
- The excavation was continued to the Target Elevations in all locations.

- A limited portion of the deeper excavations Area 24 and 26 (southern portion of the excavation) was terminated at or below the Target level which was coincidental with the upper surface of the Stratum D. The remainder of the excavations was terminated in Stratum O.
- Confirmatory Bottom Points located within Cells 126 through 129 are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were no Confirmatory Sidewall Samples in Cells 126 to 129. The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Per the SOP, we are showing the corner elevations as discussed.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Thursday, June 12, 2014 5:14 PM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 129 through 133

**Importance:** High

**Follow Up Flag:** Follow up
**Flag Status:** Completed

Stuart Bills
AMEC E&I
Sent via the Samsung GALAXY S®4, an AT&T 4G
LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:06/12/2014 17:06 (GMT-05:00)
To: "Shallard, Samuel G." ,"Bills, Stuart B" ,"Nagg, Dennis E"
Cc: "Kaouris, Maria" ,"Mojka, John"
Subject: FW: SA-6S : Excavation Completion in Cells 129 through 133

FYI.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, June 11, 2014 5:26 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 129 through 133
**Importance:** High

Bill,
The Special Master is in receipt of your June 8, 2014 email and the supporting documentation regarding Excavation Completion in Cells 129 to 133 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, June 08, 2014 5:57 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 129 through 133

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 129 to 133.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 05/20/14 to 05/27/14.

As previously indicated cells are being spilt into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

During daily excavation and survey confirmation Cells 129 through 133 were divided into A and B sections as reflected in the Maser Tables. There is no clean unexcavated dividing line in the middle of site as there was in Cells 137 through 146. For this submittal the full north south area of each cell was completed as indicated in the Excavation Bottom Elevation figure.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells except for those areas noted for deferral.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 129 to 133, the excavation is terminated at the respective Area 21, 23, 30, 31, 32, 34, and 35 excavation elevations.
- Excavation will proceed from Cell 128 to the east into Cell 125.
- The bottom of cells 129 through 133 were terminated in Stratum O.

- Confirmatory Bottom Points located within Cells 129 through 133 are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall.
- There were no Confirmatory Sidewall Samples in Cells 129-133. The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Per the SOP, we are showing the corner elevations as discussed at our last all parties meeting.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

Please note: This e-mail documented excavation completion in cells 137B through 146B. The cells identified in the subject line were mislabeled. EGC 2/27/17

**Christodoulatos, Eric G**

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:36 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 134 to 136 and 138B to 145B

**Importance:** High

1st of many emails you requested

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Sunday, June 08, 2014 7:17 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 134 to 136 and 138B to 145B
**Importance:** High

Bill,

The Special Master is in receipt of your May 27, 2014 email and the supporting documentation regarding Excavation Completion in Cells 134 to 136 and 138B to 145B and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, May 27, 2014 7:58 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 134 to 136 and 138B to 145B

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 134 to 136 and 138B to 145B.

As discussed in our weekly meetings, we have separated the western cells into A and B designations with A being the portion of cells closest to the barrier wall and B being the portion closest to Kellogg St. We provided in a previous email on May 18, 2014 the figure.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 05/01/14 to 05/19/14.

- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided.*
- *All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells except for those areas noted for deferral.*
- *Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 134 to 136 and 138B to 146B, the excavation is terminated at the respective Area 31, 32, 33, 36 and 39 excavation elevations.*
- *Excavation will proceed from Cell 134 to the east.*

*EXCAVATION CELLS 137B THROUGH 146B*

- *The bottom of Cells 137B through 146B were terminated in Stratum O.*
- *Confirmatory Bottom Points located within Cells 137B through 146B are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples are shown in Cells 138B, 141B, 142B 143B and 146B.*
- *Sample 073-SB-051 is interior to the excavation approximately on the dividing line of Cells 138B and 139B. This is an area where the excavation limits shown on the 100% design for Cells 139B and 140B was adjusted to the north to simplify the excavation geometry.*
- *The northern limits of Cells 137 B THROUGH 146 B terminates at the 20 PPM line that is interior to the site. The profile of the excavation face is composed of very loose Stratum O sands overlain by several feet of historic fill. The slope had to be laid back much more than at the east end of the site to provide a stable slope. This results in the top of slope being significantly further beyond the <20 PPM line than the eastern portion of the site.*
- *The Southern limits of Cells 137 B to 146 B were terminated at the temporary sheet pile that forms the southern limit of excavation in these cells.*

*EXCAVATION CELLS 134 to 136*

- *These cells were not split.*
- *For Cells 134 through 136, the bottom of the excavation was terminated in Stratum O.*
- *The Southern limits of Cells 134 through 136 were terminated at the temporary sheet pile that forms the southern limit of excavation in these cells which is coincident with the <20 PPM line..*
- *Confirmatory Bottom Points located within Cells 134 to 136 are shown on the Excavation Bottom Elevation figure.*

- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal.*
- *The northern limits of Cells 134 to 136 consist of sheet pile Barrier Wall.*

Per the SOP, we are showing the corner elevations as discussed at our last all parties meeting.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:36 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Tuesday, May 27, 2014 3:43 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

Bill,

The Special Master is in receipt of your May 18, 2014 email and the supporting documentation regarding Excavation Completion in Cells 137A to 146A and 147 to 152 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, May 18, 2014 8:31 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 137A to 146A and 147 to 152 .

As discussed in our weekly meetings, we have separated the western cells into A and B designations with A being the portion of cells closest to the barrier wall and B being the portion closest to Kellogg St. We are providing herein a new figure (see SA-6 South Split Cells 4.pdf which provides the graphical delineation for purposes of better understanding our statements below.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 04/25/14 to 04/29/14.

*EXCAVATION CELLS 149 THROUGH 152*

- *Excavation commenced on 4/14 in the western portion of the site. This portion of the site had a surface primarily composed of a series of foundations and slabs at variable elevations.*
- *Due to the presence of several feet of concrete, Cell 153 is only partially excavated at this time and as a result is not being included in the email indicating that excavation is complete at this time.*
- *The approved 100% Design in this area (Area 40) indicated deferral of excavation below elevation 5.7.*
- *Visual inspection of the bottom and sidewalls of Cells 149 through 152 indicated the presence of chromium impacted concrete. Removal of these materials vertically resulted in excavation below elevation 5.7. Visually impacted concrete was removed laterally along the south easterly edge of the Cell 150 into Cell 149 as evidenced by the limit of excavation shown on the Bottom Excavation Elevation figure.*
- *Cells 149 through 152 were terminated in historic fill.*
- *Confirmatory Bottom Points located within Cells 148-152 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples are shown in Cells 149, 150 and 152.*
- *The northern limits of Cells 149-152 consist of sheet pile Barrier Wall.*
- *The Southern limit of cells 149-152 were terminated in 0 <20 PPM historic fill soils.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% Design limits. In several areas of Cell 149-152 the excavation depth was increased (we were able to get additional materials and minimize future deferral volumes remaining) and these locations are shown with a green shading. These areas are also outlined in Excavation Bottom Elevation figure.*

*EXCAVATION CELLS 147 to 148 and 137A to 146A*

- *The cell excavation designations in this area have been split into subparts A and B. The A designation is applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell. This designation clarification was made for two reasons:*
    - *For Cells 137 through 146, the excavation area is not continuous north to south, meaning there is an area of <20 PPM soils not requiring excavation In the middle of the cells (see Figure 2 Color Coded Excavation Bottom).*
    - *For Cells 136 to the east this approach was used to facilitate surveying of the subarea A (including corners and center points). This reduces the time cycle between excavation and backfill adjacent to the hydraulic barrier which helps to minimize sheet deflection.*
- *Cells 137A through 146A, 147 and 148 excavation was terminated in either historic fill or Stratum O.*
- *The Southern limit of Cells 137A to 146A, 145 and 148 was terminated in either historic fill or Stratum O <20 PPM soils.*
- *Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 137A-146A and 147 to 148, the excavation is terminated at the respective Area 32, 33, 36, 37, 38 and 40 excavation elevations.*
- *Confirmatory Bottom Points located within Cells 137A-146A, 147 and 148 are shown on the Excavation Bottom Elevation figure.*

- *Confirmatory Sidewall Samples are shown in Cells 137A, 139A, 142A, 143A and 148.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal.*
- *The northern limits of Cells 137 to 146 consist of sheet pile Barrier Wall.*
- *The Southern Limit of excavation of Cells 137A to 146A, 147 and 148 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided.*
- *Excavation will proceed from Cell 136A to the east and from Cell 146B to the east.*
- *All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells except for those areas noted for deferral.*

Per the SOP, we are showing the corner elevations as discussed at our last all parties meeting.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:10 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: Amendment to SA-6S : Excavation Completion in Cells 149 to 152

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, October 29, 2014 4:15 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amec.com>; Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: Amendment to SA-6S : Excavation Completion in Cells 149 to 152

Bill/Joe,

The Special Master is in receipt of your October 23, 2014 email providing supplementation information for the Amended Certification for Excavation Completion in Cells 149 to 152 emailed on October 1, 2014 and that the requirements to allow backfilling have been met.

Regards, Steve

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Thursday, October 23, 2014 8:32 AM
**To:** Egnaczyk, Steve; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: Amendment to SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

**SUPPLEMENTAL INFORMATION FOR AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 149 TO 152 EMAILED ON OCTOBER 1, 2014.**

Steve,

I am sending this email on behalf of Honeywell.

In response to your email dated October 10 to Bill Hague, Honeywell and Amec are providing the following supplemental information:

- The top portion of the design excavation in Cells 149 through 152 consisted of a combination of reinforced and unreinforced concrete. As indicated in the May 27th submittal the concrete at the design limits was observed to be chromium impacted: "Visual inspection of the bottom of excavation and sidewalls of Cells 149 through 152 indicated the presence of chromium impacted concrete in the concrete sidewall". The excavation was therefore expanded to remove the visibly impacted concrete.

- The expansion of the design excavation necessitated obtaining additional sidewall samples. Two new Confirmatory Sidewall Soil Samples (designated 073-SB-079 and 073-SB-082) were collected and documented in the Maser table attached to the October 1, 2014 email from Honeywell (see page 14 of 15).

- The Final Limits of excavation (highlighted in green) and location of the Confirmatory Sidewall Soil Samples are shown on the Bottom Excavation Map (Amended) attached to the October 1, 2014 email from Honeywell.

- The bottom of excavation elevation matched the adjacent excavation in Cell 149 and Cell 150. As indicated in the Bottom Excavation Map (Amended), the southern portion of the additional excavation was excavated to elevation 2 and the northern portion to approximately elevation 4.

- The vertical and horizontal limits of excavation were surveyed by Maser, including supplemental survey points for use in preparation of the as-built excavation topographic map that will accompany the Declaration which will be submitted following completion of the SA-6S excavation.

- The additional excavation area depicted on the Bottom Excavation Map (Amended and highlighted in green) represents the boundaries of the area resurveyed on July 31, 2014.

- The bottom and lateral limits of the additional excavation area were visually inspected by Amec personnel prior to the July 31, 2014 Maser Survey. Amec personnel did not observe any additionally impacted soils.

- Amec inspectors certify to the best of our technical ability that impacted soils as defined in the 100% Design have been removed from the additional excavation area and that the requirements to allow backfilling have been met.

We are re-submitting the two attachments from our October 1, 2014 transmittal.

Please let us know if you have any more questions regarding this Amended Submittal for Cells 149 to 152.

Regards.

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, October 10, 2014 3:24 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: Amendment to SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152
**Importance:** High

Bill,

The Special Master is in receipt of your October 1, 2014 email below regarding the Amended Certification for Excavation Complete in Cells 149 to 152 and provides the following comments:

1. Because Honeywell needed to perform additional excavation to address this area of contamination that extended beyond the defined excavation boundaries presented in the color-coded excavation map (i.e., Figure 4 that depicts the 41 areas of the SA6 South excavation and the pre-determined depths of excavation) to fully comply with the SA6 South 100% Design, consistent with the initial May 27, 2014 submittal, please provide a re-certification from Honeywell/AMEC/Maser that:
    a. The bottom and lateral limits of the expanded excavation area were visually inspected by Honeywell/Amec personnel and no additional visually impacted area was observed.
    b. Impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling [of this additional excavation area ]have been met.
    c. The additional excavation area depicted on the attached figure (and highlighted in green) represents the boundaries of area resurveyed on July 31, 2014.
2. Please confirm whether any additional survey points were collected in the expanded excavation area from the bottom of the completed excavation area.

Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, October 01, 2014 10:40 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** Amendment to SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

**AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 149 TO 152.**

Steve,

We are providing an amended certification regarding completion of excavation in Cells 149 to 152 which was originally submitted by Honeywell to the parties by email on May 27, 2014.

As noted in the original May 27, 2014 email for these cells, the following observation was noted by the Amec engineer:

- *Visual inspection of the bottom and sidewalls of Cells 149 through 152 indicated the presence of chromium impacted concrete. Removal of these materials vertically resulted in excavation below elevation 5.7. Visually impacted concrete was removed laterally along the south easterly edge of the Cell 150 into Cell 149 as evidenced by the limit of excavation shown on the Bottom Excavation Elevation figure.*

Once the visually-impacted concrete was removed, Honeywell made the original email certification to the parties.

Subsequent to the submittal, Honeywell also directed Amec to collect two additional sidewall soil samples on the eastern excavation edge 073-SB-079 and 073-SB-080. While hexavalent chromium in soil sample 073-SB-079 was < 20 ppm, the second sample 073-SB-080 was > 20 ppm, which necessitated a step out soil sample approximately five feet to the east. This last soil sample designated as 073-SB-082 was confirmed to be < 20 ppm and the contractor returned to this area to remove the small area of residual soil > 20 ppm. The area was excavated in July and resurveyed on July 31, 2014.

An Amended Excavation Bottom Elevation Map showing the additional area of excavation of visually-impacted concrete and subsequent soil > 20 ppm is attached and highlighted in green. As shown in this figure, the area slightly enlarges the limits of Cells 148, 149 and 150.

The added < 20 ppm soil sample confirmatory locations are also shown on the map. Analytical data for the three soil samples collected in this excavation area was provided in the SA-6 Monthly Progress Report No. 2014-07 submitted to the parties on August 14, 2014.

Lastly, the Maser Survey Table showing the confirmatory points has been updated to reflect the two recent soil sample locations with hexavalent chromium < 20 ppm (highlighted in green on page 14 of 15) which are additional sidewall confirmatory samples for SA-6 South.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the

attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

---

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

---

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Tuesday, January 31, 2017 10:45 AM
**To:** Christodoulatos, Eric G
**Cc:** Shallard, Samuel G.
**Subject:** FW: SA-6 South Site 163 Post-Remediation Sampling

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

Found it!

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, May 13, 2015 7:55 PM
**To:** Kathleen L. Millian <kmillian@tpmlaw.com>; Michael.Daneker@aporter.com
**Cc:** RGT Special Master <RGTSpecialMaster@aol.com>; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO) <tom.byrne@honeywell.com>; Kaouris, Maria <Maria.Kaouris@Honeywell.com>; Alicia Clark Alcorn <aalcorn@tpmlaw.com>; Carolyn Smith Pravlik <cpravlik@tpmlaw.com>; Lewis, Thomas <tlewis@louisberger.com>; McWatters, Michael <mmcwatters@louisberger.com>; Ben Davis <bdavis@tpmlaw.com>; Toskos, Theodoros <Theodoros.Toskos@amec.com>; Morris, John (MTO) [John.Morris@honeywell.com] <John.Morris@honeywell.com>; Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>
**Subject:** RE: SA-6 South Site 163 Post-Remediation Sampling

All,

As Honeywell has provided the information requested by Plaintiffs' in their April 30, email, the Special Master requests the parties be prepared to address the issue of "rebound" at next week's Special Master All Parties Meeting. The Special Master refers to the discussion in Honeywell's April 3, 2015 correspondence regarding post-treatment "rebound" of residual soil concentrations of hexavalent chromium, and specifically, to define "rebound" should there be detections of hexavalent chromium above 20 ppm during post-remediation sampling at Site 163, as well as Treatment Areas 7, 8, and 10 on SA6 North.

Regards, Steve

---

**From:** Clifford, Joseph T [mailto:joseph.clifford@amecfw.com]
**Sent:** Wednesday, May 13, 2015 9:03 AM
**To:** Kathleen L. Millian; Egnaczyk, Steve
**Cc:** RGT Special Master; Michael.Daneker@aporter.com; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO); Kaouris, Maria; Alicia Clark Alcorn; Carolyn Smith Pravlik; Lewis, Thomas; McWatters, Michael; Ben Davis; Toskos, Theodoros; Morris, John (MTO) [John.Morris@honeywell.com]; Hague, William [william.hague@honeywell.com]
**Subject:** RE: SA-6 South Site 163 Post-Remediation Sampling

Kathy/Steve,

I am sending this email on behalf of Honeywell.

Please find attached the figure you requested showing the location of the Soil Boring 140-SB-P05 which was the location used for the cores sent to Battelle. The figure also shows the proximate PDI soil delineation used in the 100% Design. The area around this boring was excavated to Stratum D.

Let us know if you have any other questions on this item.

Thank you. -Joe

---

**From:** Kathleen L. Millian [mailto:kmillian@tpmlaw.com]
**Sent:** Thursday, April 30, 2015 3:13 PM
**To:** Morris, John (MTO); Hague, William
**Cc:** RGT Special Master; Clifford, Joseph T; Michael.Daneker@aporter.com; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO); Kaouris, Maria; Alicia Clark Alcorn; Carolyn Smith Pravlik; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mmcwatters@louisberger.com; Ben Davis; Toskos, Theodoros
**Subject:** RE: SA-6 South Site 163 Post-Remediation Sampling

Plaintiffs write concerning the issue of potential rebound at Site 163. On April 3, 2015, Honeywell submitted to the Special Master a memorandum prepared by Amec Foster Wheeler, entitled "Analysis of Chromium 'Rebound,' with Application to Site 163." Some of Amec's positions on rebound are based on a draft report that was prepared by Battelle in September 2008, entitled "Investigation of Chromium in SA-6S Core Segments."

Plaintiffs' experts, Benjamin Ross, Ph.D. and George Flowers, Ph.D., request certain additional information to enable a full understanding of the September 2008 draft report. In particular, we request to know the location from which the core segments were taken. Plaintiffs request that Honeywell provide a figure of the relevant portion of Study Area 6 South showing both: (1) the location from which the core was taken; and (2) the locations of and contaminant levels at the borings which were used to delineate the hexavalent chromium in the vicinity of the core.

Thank your for your attention to this matter.

Sincerely,

Kathleen L. Millian
TERRIS, PRAVLIK & MILLIAN, LLP
1121 12th Street, N.W.
Washington, D.C. 20005
Main Telephone: 202-682-2100
Direct Dial: 202-204-8478
Facsimile: 202-289-6795
email: kmillian@tpmlaw.com

The information in this e-mail is intended only for the use of the designated recipient(s) and may contain confidential and privileged information.
If the reader of this message is not the intended recipient(s), you are hereby notified that you have received this email in error and that any review, dissemination, distribution, or copying of this message is strictly prohibited. If you have received this communication in error, please notify the sender by reply e-mail and destroy all copies of the original message.

**From:** Graham, Stephanie [mailto:Stephanie.Graham@honeywell.com]
**Sent:** Friday, April 03, 2015 4:17 PM
**To:** RGT Special Master
**Cc:** Joseph.Clifford@amecfw.com; Michael.Daneker@aporter.com; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO); Hague, William; Kaouris, Maria; Morris, John (MTO); Alicia Clark Alcorn; Kathleen L. Millian; Carolyn Smith Pravlik; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mmcwatters@louisberger.com; Ben Davis; Toskos, Theodoros
**Subject:** SA-6 South Site 163 Post-Remediation Sampling

Attached please find Honeywell correspondence re:

**Site 163 Post-Remediation Sampling**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Please note that this information has also been made available on the Louis Berger SharePoint Site.

Thank you,

Stephanie Graham

**Amec Foster Wheeler**
c/o Honeywell
101 Columbia Tpke
Morristown, NJ 07962
Phone: 973-455-4209

This message is the property of Amec Foster Wheeler plc and/or its subsidiaries and/or affiliates and is intended only for the named recipient(s). Its contents (including any attachments) may be confidential, legally privileged or otherwise protected from disclosure by law. Unauthorised use, copying, distribution or disclosure of any of it may be unlawful and is strictly prohibited. We assume no responsibility to persons other than the intended named recipient(s) and do not accept liability for any errors or omissions which are a result of email transmission. If you have received this message in error, please notify us immediately by reply email to the sender and confirm that the original message and any attachments and copies have been destroyed and deleted from your system. This disclaimer applies to any and all messages originating from us and set out above. For Canada and the United States: If you believe this is an unsolicited email and do not wish to receive future commercial electronic messages from us, please click unsubscribe@amecfw.com and include "Unsubscribe" in the subject line.

Please click http://amecfw.com/email-disclaimer for notices and company information in relation to emails originating in the UK, Italy or France.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Tuesday, January 03, 2017 10:47 AM
**To:** Christodoulatos, Eric G; Shallard, Samuel G.
**Subject:** FW: SA-6 South Excavation Complete Submittal - Site 163

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

Here is the first part. I will search for the follow up email.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, December 31, 2014 10:57 AM
**To:** Hague, William
**Cc:** RGT Special Master ; Kevin J. Coakley (KCoakley@connellfoley.com) ; 'Liza M. Walsh' (LWalsh@connellfoley.com) ; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) ; Lewis, Thomas ; ' (kmillian@tpmlaw.com)' ; 'Aalcorn@tpmlaw.com' ; 'cpravlik@tpmlaw.com' ; Ben Davis ; 'Daneker, Michael' ; 'Jeremy.Karpatkin@aporter.com' ; Morris, John (MTO) ; 'DelisleB@jcnj.org' ; JFarrell@jcnj.org; JWatson@jcnj.org; 'David Isabel' ; 'Eric Tomaszewski' ; Francis J. Borin ; KKINSELLA@decotiislaw.com; Clifford, Joseph T ; 'Ben Ross (bross@disposalsafety.com)' ; 'Bruce A. Bell' ; 'Kim Bell Hosea (k.bell@cea-enviro.com)' ; McWatters, Michael
**Subject:** RE: SA-6 South Excavation Complete Submittal - Site 163

Bill,

The Special Master is in receipt of your December 11, 2014 email and the supporting documentation regarding Excavation Completion of Site 163 and the small (undesignated) diamond shaped area west of the "main" Site 163 excavation area and your notification that the requirements to allow backfilling have been met. Honeywell also reports that as a result of an inspection and evaluation of the Droyer's Cove bulkhead and associated mass concrete located along the shoreline of Droyer's Cove that borders the southern limit of the excavation, a decision was reached by Honeywell as to the safe limits of excavation and several areas were deferred from excavation. The Special Master concurs with Plaintiffs' request contained in their December 19 email that Honeywell provide information regarding the three (3) areas shown in the figure attached to your email (Excavation Bottom Elevations, Site 163, Period 10-30-4 to 11-13-14) that have been deferred from excavation.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, December 11, 2014 4:34 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal - Site 163

Steve,

We are providing this email notification that our contractor is ready to backfill the shallow (0-4 feet below grade) soil excavation in Site 163.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 10/30/14 to 11/13/14.

This submittal covers the main Chromium portion of the Site 163 excavation and the diamond shaped area west of the "main excavation". Additional shallow excavation will be conducted to remove non-chromium impacted soils west of the "main excavation" limits shown. The Issued for Construction design indicated Excavation for site 163 using below ground surface depths. These depths were converted to elevation (NGVD 29 datum) prior to implementation of the excavation. All excavation depths and the Maser table reports based on elevations.

Due to the shallow depth and geometry of the excavation "cell numbering" was not used.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% Design limits.
- Temporary sheetpile which was driven at the southern limit for the excavation of Cells 106 through 129 was still in place and served as the northern limit of the Site 163 excavation. The face of the temporary sheet was cleaned of visible soil materials.
- The southern excavation limit was designed with variable offsets from the Droyer's Cove bulkhead based on the PDI samples. The bulkhead and associated mass concrete was inspected as excavation progressed and decisions reached as to the safe limits of removal. As a result of this inspection and evaluation process one concrete structure was left in place at the southwest corner of the excavation and a sliver of material was left in place at the south east corner as shown on the Excavation Bottom Elevation plan. There was no visual indication of chromium impact in the concrete left in place.
- The top 6 inches of the "deadmen" for the bulkhead were exposed in the bottom of the excavation.
- The bottom and lateral limits of the excavation was visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met subject to the isolated areas noted above.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the steps in bottom elevations in the Excavation Area.
- The bottom of excavation was terminated in Stratum O or fill at or below the respective Excavation Bottom Elevations.
- Excavation will proceed to remove the Lens of Anomalous material that extended beyond the design limit by Cell 104.
- There were 11 Confirmatory Sidewall Samples taken in the main area and 4 Confirmatory sidewall samples in the Diamond shaped area.

We note that a field decision was made to add an additional protective measure to protect the clean backfill. This measure included use of a geotextile and riprap/crushed concrete with the objective of increasing erosion protection

until the new bulkhead is installed by Bayfront. The Design Change Bulletin showing this enhancement of the 100% Design is being prepared for distribution to the parties.

Regards
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**ATTACHMENT C-1**
**SITE 163 EXCAVATION CERTIFICATION E-MAIL**

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:18 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Submittal - Site 163 Residential Area
**Attachments:** Final AB PDI Locations Site 163_ Feb 2016_1.pdf; Figure 1 - Site 163 Addtional Excavation Areas.pdf; Confirmation Points Cert site163 2016 Chrome area_041316-signed.pdf

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, April 25, 2016 10:53 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>
**Subject:** SA-6 South Excavation Submittal - Site 163 Residential Area

Steve,

We are providing this email notification that our contractor is complete in Excavation Area at Site 163 Residential Footprint which is part of the SA-6 South Chromium Remedy. The excavation of this specific area within Site 163 was developed subsequent to the 100% Design (which originally identified this area as an in-situ treatment area) and as a result is documented by the figures included in the approved Design Change Bulletin - DCB 2015-0928.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of Site 163 excavation completion covers the individual period of 12/28/15 to 02/19/16. This submittal includes the full extent of Site 163 as shown on the approved DCB 2015-0928 drawings.

- The submittal include a “Maser” signed table of the Confirmation Points and the Entact “As Built” Excavation Figure.
- The excavation was conducted using temporary sheetpile on all sides. The sheetpile was driven so that the inside face of the sheetpile was at or slightly beyond the excavation limits shown on Figure 1 of DCB 2015-0928. (copy attached).
- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.

- The bottom excavation elevations were measured using the Machine Control GPS.
- The bottom of excavation elevations were at or below the design Bottom of Excavation Elevations.
- For safety reasons no entry was permitted to inspect the bottom of the excavation. The bottom of the excavation was visually inspected by Amec personnel from outside the sheetpile.
- The Bottom of Excavation was observed to be of a consistent elevation and at or below the elevation at the survey confirmation locations.
- As shown on the As Built excavation bottom figure only one area was noted to be at being Stratum D. Stratum D fragments were detected at in other isolated locations within the deepest excavation. The majority of the excavation was terminated in a silty sand, Stratum O type soil.
- The web of the sheetpile was outside of the designated excavation limit.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design and subsequent DCB 2015-0928 have been removed and that the requirements to allow backfilling were met.
- Lines have been added to the As Built Excavation Map to delineate the limits of the steps in bottom elevations in the Excavation Area.
- Changes in elevation between areas was small and therefore near vertical faces were excavated at locations where the design bottom elevations changed.
- There were 5 Confirmatory Sidewall, and 5 Confirmatory Bottom locations exposed during the excavation and these are depicted on the Maser Survey Tables and Entact Bottom of Excavation Figure.

Please call or email me with any questions.
Regards,
Bill Hague

**William J. Hague P.E.**

Honeywell
Director - Remediation Design & Construction
Corporate HSE&R
115 Tabor Road
Morris Plains, NJ 07950
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:22 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: Response to Verbal Questions on Site 163 Excavation

---

**From:** Clifford, Joseph T
**Sent:** Thursday, May 05, 2016 7:40 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>
**Subject:** Response to Verbal Questions on Site 163 Excavation

Steve,

I am sending this email on behalf of Honeywell, and in response to your call on April 27, 2016, when you asked two questions regarding our April 25, 2016 - Site 163 Excavation Completion Email Notification to the parties.

Below are the questions and our responses.

1. **What is our rationale for the BOE design for Area B, which does not have a bottom PDI sample?**

   - *"PDI samples from across the localized area were used and interpolated consistent with the 100% Design approach. The approved DCB 2015-0928 explicitly stated that Honeywell would implement this excavation without any additional sampling required."*

2. **We mention that no Amec inspections were performed in the bottom of the excavation, yet at some point we did have Entact laborers in the backfill placing geotextile**.

   - *"At the time of excavation completion, the bottom soils were deemed too soft to safely enter the excavation. The excavation was sufficiently dewatered to allow our inspections from the existing grade as necessary to attest to our inspection protocols. Once the initial bridge lift was placed and the bottom stabilized, Entact crew was able to enter the excavation to place the geotextile in accordance with the 100% Design specifications."*

If these responses adequately address your inquiry, Honeywell would be pleased to provide an Amended Certification of Excavation Complete Email adding these clarifications upon your request.

Please contact me on my cell at 610-505-9315 or Bill Hague at 973-455-2175 with any further questions on this item.

Thank you. -Joe

**Joseph T. Clifford, P.E.**
Sr. Principal Engineer

Cell Phone (610) 505- 9315
Email joseph.clifford@amecfw.com

**ATTACHMENT C-2**
**SITE 163 EXCAVATION CONFIRMATION POINTS**
**AND POST EXCAVATION PLAN**

MASER CONSULTING P.A.

Engineers
Planners
Surveyors
Landscape Architects
Environmental Scientists

156 Stagecoach Road
Marmora, NJ 08223
T: 609.390.1927
F: 609.390.0040
www.maserconsulting.com

## SA-6 South: Site 163 Chrome Excavation (2016): Confirmatory Points (Table 1.0)

| Bottom Target Coordinates (based on PDI) | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 685069.7 | 601654.2 | -3.0 | 163-SB-011 | 1/15/2016 | -3.2 | Target Elevation Reached |
| 685102.9 | 601588.4 | -6.7 | 163-SB-015 | 1/19/2016 | -6.8 | Target Elevation Reached |
| 685184.5 | 601554.4 | -6.7 | 163-SB-104 | 2/12/2016 | -7.1 | Target Elevation Reached |
| 685186.5 | 601509.2 | -8.0 | 163-SB-016 | 2/19/2016 | -8.3 | Target Elevation Reached 2 |
| 685247.3 | 601467.8 | -6.6 | 163-SB-105 | 2/19/2016 | -7.1 | Target Elevation Reached |

## SA-6 South: Site 163 Chrome Excavation (2016): Sidewall Confirmatory Points (Table 2.0)

| Sidewall Target Coordinates | | | | As-built Elevations | | |
|---|---|---|---|---|---|---|
| Northing | Easting | Elevation 1 | Sample ID | Date Obtained | Elevation | Comments |
| 685138.0 | 601563.6 | -5.3 | 163-SB-078 | 1/19/2016 | -6.9 | Target Elevation Reached |
| 685165.5 | 601546.0 | -3.5 | 163-SB-080 | 2/12/2016 | -7.1 | Target Elevation Reached |
| 685201.0 | 601525.8 | -5.0 | 163-SB-019 | 2/19/2016 | -7.1 | Target Elevation Reached |
| 685207.2 | 601503.5 | -3.0 | 163-SB-037 | 2/19/2016 | -7.1 | Target Elevation Reached |
| 685247.6 | 601452.5 | -5.2 | 163-SB-021 | 2/19/2016 | -7.2 | Target Elevation Reached |

1 This is the actual elevation of the PDI sample included with the approved Figure 1 - Site 163 Additional Chromium Excavation Areas dated 9/22/15.

2 Elevation -8.3 ft. was coincidental with the top of Stratum D.


**Maser Consulting P.A. certifies that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Sidewall Confirmatory Sidewall Points Table 2 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades.**


R Thomas Hugg 3/16/16

**R. THOMAS HUGG**

**NEW JERSEY PROFESSIONAL LAND SURVEYOR**

**LICENSE NO. 36737**




CONFIRMATORY BOTTOM SAMPLE ELEVATION

CONFIRMATORY SIDEWALL SAMPLE ELEVATION

0.0 POINT ELEVATION
POINT POINT DESCRIPTION

CURRENT EXCAVATION TO STRATUM D

DESIGN EXCAVATION AREA

DESIGN EXCAVATION LIMIT


Temporary sheetpile alignment used in the SA6 South main excavation

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA-6 SOUTH, SITE 163 (2016) AS-BUILT: EXCAVATION CONFIRMATION POINTS

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT D-1**
**SA-6 NORTH AND SOUTH CONTINGENT GROUNDWATER EXTRACTION SYSTEM RECORD DRAWINGS – FORCE MAIN, ELECTRICAL CONDUIT AND INSTRUMENTATION**




RECORD DRAWING - 01/06/17

## LEGEND

- FORCEMAIN STATIONS
- ELECTRIC HANDHOLE
- SCB WALL
- HB WALL (Inner Edge)
- ELECTRICAL CONDUIT
- FORCEMAIN
- TEXT — ELECTRICAL DESCRIPTION
- TEXT — FORCEMAIN DESCRIPTION

0 80 160 Feet

SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | Contingent Groundwater Extraction System – NORTH CAP |
| 1 | 01/06/17 | EJP | AE | AE | ADDED FORCEMAIN AND CONDUIT CROSS SECTION |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: Contingent Groundwater Extraction System NORTH CAP 01/06/17

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

HACKENSACK RIVER

SA6 SOUTH CAP

SA6 NORTH CAP

RECORD DRAWING - 12/19/16

Refer to SA-6 South Design Drawing C-204 (DCB 007.4.1) for existing conduit and force main piping not installed under this contract.

Electrical Conduit N: 685652.46 E: 601553.03 El: 5.56'
Leak Detection N: 685567.13 E: 601564.17 El: 7.17'
Electrical Conduit N: 685686.91 E: 601587.96 El: 5.35'
Electrical Handhole N: 685651.58 E: 601550.68 El: 8.07'
3"x6" Pipe Top Elevation N: 685682.79 E: 601584.79 El: 1.88'
Wye Cleanout N: 685664.9 E: 601571.73 El: 7.05'
2"x4" Pipe Top Elevation N: 685651.98 E: 601553.89 El: 1.39'
Electrical Conduit N: 685648.24 E: 601550.95 El: 6.18'
(2) 2" Sch 40 Conduit
2"x4" Pipe Top Elevation N: 685648.24 E: 601553.73 El: 5.66'
Electrical Conduit N: 685598.02 E: 601613.38 El: 6.75'
2"x4" Pipe Top Elevation N: 685600.48 E: 601613.46 El: 6.63'
(2) 2" Sch 40 Conduit
Electrical Conduit N: 685556.99 E: 601675.64 El: 6.97'
2"x4" Pipe Top Elevation N: 685556.62 E: 601675.48 El: 6.97'
Electric Handhole N: 685503.38 E: 601742.91 El: 8.95'
Electrical Conduit N: 685500.28 E: 601743.38 El: 8.63'
Electrical Conduit N: 685481.75 E: 601730.52 El: 14.76'
Electrical Conduit N: 685504.28 E: 601742.83 El: 7.41'
2"x4" Pipe Top Elevation N: 685490.18 E: 601732.46 El: 14.71'
Elbow Cleanout N: 685505.72 E: 601750.51 El: 10.07'
2"x4" Pipe Top Elevation N: 685504.22 E: 601747.65 El: 7.22'
Electrical Conduit N: 685451.98 E: 601737.99 El: 15.7'
2"x4" Pipe Top Elevation N: 685443.98 E: 601741.93 El: 15.56'
(2) 2" Sch 40 Conduit
Electrical Conduit N: 685388.59 E: 601747.89 El: 16.03'
2"x4" Pipe Top Elevation N: 685412.93 E: 601747.24 El: 15.85'
Extraction Pump Station N: 685404.24 E: 601751.91 El: 18.9'
Electric Handhole N: 685392.63 E: 601751.17 El: 19.0'

(1) 2" Sch 40 Conduit
Electrical Conduit N: 685556.58 E: 601639.67 El: 5.5'
Electrical Conduit N: 685924.07 E: 601730.25 El: 5.85'
Electrical Conduit N: 685785.02 E: 601689.56 El: 5.27'
Electric Handhole N: 685822.78 E: 601730.68 El: 5.97'
(1) 2" Sch 40 Conduit
Electrical Conduit N: 685872.04 E: 601781.15 El: 5.3'
Existing Cleanout N: 685998.35 E: 601903.64 El: 8.31'
Existing Cleanout N: 686003.68 E: 601906.17 El: 8.26'
Electrical Conduit N: 685930.19 E: 601842.34 El: 5.53'
Electrical Conduit N: 686002.3 E: 601914.11 El: 8.4'
Electric Handhole N: 686005.13 E: 601916.99 El: 8.21'

Electric Handhole N: 686061.6 E: 602027.4 El: 16.68'
2"x4" Pipe Top Elevation El: 13.67'
2"x4" Pipe Top Elevation N: 686082.76 E: 602076.12 El: 13.16'
(3) 2" Sch 40 Conduit
2"x4" Pipe Top Elevation El: 14.18'
Air Release N: 686118.07 E: 602132.79 El: 18.43'
Electric Handhole N: 686048.48 E: 602026.15 El: 16.74'
3"x6" tie-in to 2"x4" Pipe N: 686049.98 E: 602030.64 El: 13.65'
(2) 2" Sch 40 Conduit
Electrical Conduit N: 686071.04 E: 602063.12 El: 13.92'
Electrical Conduit N: 686104.12 E: 602103.38 El: 14.53'
(3) 2" Sch 40 Conduit
2"x4" Pipe Top Elevation El: 14.57'
Electric Handhole N: 686087.6 E: 602084.41 El: 17.83'
(1) 2" Sch 40 Conduit
2"x4" Pipe Top Elevation N: 686104.56 E: 602178.43 El: 15.02'
Elbow Cleanout N: 686089.39 E: 602214.99 El: 17.95'
Electrical Conduit N: 686105.54 E: 602174.55 El: 15.51'
(3) 2" Sch 40 Conduit
2"x4" Pipe Top Elevation N: 686161.11 E: 602254.31 El: 13.79'
(4) 2" Sch 40 Conduit
(2) 3" Sch 40 Conduit
Groundwater Treatment Plant
Electric Handhole N: 686562.11 E: 602275.94 El: 15.34'
Electrical Conduit N: 685785.02 E: 601689.56 El: 5.27'
Electric Handhole N: 686115.89 E: 602294.68 El: 16.83'

## LEGEND

- FO[illegible]AIN STATIONS
- EL[illegible]C HANDHOLE
- SC[illegible]LL
- HB WALL (Inner Edge)
- ELECTRICAL CONDUIT
- FORCEMAIN
- TEXT ELECTRICAL DESCRIPTION
- TEXT FORCEMAIN DESCRIPTION

0 80 160 Feet

SCALE


| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | CONTINGENT GROUNDWATER EXTRACTION SYSTEM – SOUTH CAP |
| 1 | 12/19/16 | EJP | AE | AE | ADDED NOTES INDICATING QUANTITY OF CONDUITS |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
CONTINGENT GROUNDWATER EXTRACTION SYSTEM
SOUTH CAP
12/19/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT D-2**
**SA-6 NORTH AND SOUTH CONTINGENT GROUNDWATER EXTRACTION SYSTEM RECORD DRAWING – GWTP INTERIOR PIPING AND INSTRUMENTATION**




RECORD DRAWING - 01/03/17

BSTI
science that works for you
3157 Limestone Rd., Cochranville Pa, 19330

Notes:
1. Below ground piping daylights inside the building at the wall penetration.
2. All below ground piping was heat traced and insulated prior to backfilling.
3. Flow meters were not installed at the time of construction, spool pieces were used in place of the meters.

**GWTP ADDITIONAL WELL P&ID**

Honeywell - Jersey City

Jersey City, NJ

| Date: | Drawn By: | Checked By: | BSTI Job Number: | Figure Number: |
|---|---|---|---|---|
| **1/03/17** | **GW** | **TF** | **759** | **1** |

**ATTACHMENT E**
**SA-6 NORTH AND SOUTH PIEZOMETER AS-BUILT LOCATIONS**

PZ3
N=685484.20
E=603365.30

PZ4
N=685478.80
E=603361.60

PZ5
N=685779.80
E=602959.30

PZ6
N=685773.10
E=602956.00

PZ2
N=685111.30
E=603710.20

PZ1
N=685108.30
E=603718.30

NEW JERSEY STATE
HIGHWAY ROUTE 440

MULTI– STORY
MASONRY

FINAL REMEDY
GRADE CONTOURS

SA–7

| SA-6 North Piezometers | | | |
|---|---|---|---|
| Well ID | TOC Elevation[1] | Top of Screen Elevation | Bottom of Well Elevation |
| PZ-1 | 10.09 | 4.28 | -0.72 |
| PZ-2 | 13.68 | 3.47 | -1.53 |
| PZ-3 | 15.83 | 3.96 | -1.04 |
| PZ-4 | 19.02 | 3.76 | -1.24 |
| PZ-5 | 22.13 | 4.06 | -0.94 |
| PZ-6 | 24.01 | 3.76 | -1.24 |
| PZ-7 | 19.43 | -0.76 | -5.76 |
| PZ-8 | 19.23 | 3.96 | -1.04 |
| PZ-9 | 18.27 | 3.23 | -1.77 |
| PZ-10 | 18.51 | 3.48 | -1.52 |

Notes:
1) TOC Elevations will change after final adjustment of piezometers.
2) All screens are 5 ft long.

PZ7
N=685973.90
E=602442.30

PZ8
N=685947.70
E=602430.40

PZ9
N=686064.80
E=602088.20

PZ10
N=686066.40
E=602101.80

PZ5
N=685779.80
E=602959.30

PZ6
N=685773.10
E=602956.00

FINAL REMEDY
GRADE CONTOURS

SA–7

Prepared/Date: RJR 01/23/17
Checked/Date: TDD 01/23/17

RECORD DRAWING - 01/23/17

SCALE IN FEET
HORIZONTAL SCALE
0 20 40 80

Honeywell
115 TARBOR ROAD MORRIS
PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019000

Piezometer As Built Location
Project 3480-13-0377
Figure 1

J:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SAM--DSR\DWG\SAM--North-South--RM_Extraction_Trench\Figure - Piezometer Location.dwg Tue, 14 Feb 2017 - 2:19pm roger.rhoter

RECORD DRAWING - 12/20/16

PZ16
N=684751.18
E=602508.94

PZ15
N=684735.78
E=602497.53

PZ14
N=684420.82
E=602907.51

PZ13
N=684391.71
E=602893.97

PZ12
N=684207.73
E=603276.91

PZ11
N=684200.51
E=603290.09

FINAL REMEDY GRADE CONTOURS AS BUILT SURFACE 2016-0922

INSTRUMENTATION CONDUIT DELETED

| SA-6 South Piezometers | | | |
|---|---|---|---|
| Well ID | TOC Elevation[1] | Top of Screen Elevation | Bottom of Well Elevation |
| PZ-11 | 15.89 | 5.67 | 0.67 |
| PZ-12 | 15.97 | 5.77 | 0.77 |
| PZ-13 | 16.02 | 5.86 | 0.86 |
| PZ-14 | 16.03 | 5.86 | 0.86 |
| PZ-15 | 14.16 | 3.91 | -1.09 |
| PZ-16 | 19.00 | 4.34 | -0.66 |
| PZ-17 | 18.07 | 3.13 | -1.87 |
| PZ-18 | 18.20 | 3.40 | -1.60 |
| PZ-19 | 17.91 | 3.16 | -1.84 |
| PZ-20 | 18.38 | 3.32 | -1.68 |

**Notes:**
1) TOC Elevations will change after final adjustment of piezometer.
2) All screens are 5 ft long.

PZ20
N=685584.00
E=601504.14

PZ19
N=685587.17
E=601500.99

PZ18
N=685136.43
E=601988.86

PZ17
N=685121.22
E=601977.60

EXISTING GROUNDWATER EXTRACTION WELL 115-MW-201BR

EXISTING GROUNDWATER TREATMENT PLANT

BENCHMARK ELEV.: 7.87 DESC.: PK NAIL

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

Prepared/Date: RJR 12/20/16
Checked/Date: SGS 12/20/16

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28070900

Piezometer As Built Location
Project 3480-13-0377
Figure 2

RECORD DRAWINGS - 12/20/16

Z:\Projects\HONEYWELL_WORK\ CITY\Cop Design--3480--CSD\CAD\3480--North-South--RIR_Extraction_Trench\GRA-C-201_Cont_RIR_Trench.dwg Tue, 05 Sep 2017 - 2:49pm tony.donovan

**ATTACHMENT F**
**SA-6 NORTH AND SOUTH GAS VENT RECORD DRAWINGS**

N

HACKENSACK RIVER

GAS VENT #6
N: 685983.7
E: 602246.3
EL: 17.07'

GAS VENT #5
N: 685862.9
E: 602483.9
EL: 19.87'

GAS VENT #4
N: 685785.2
E: 602766.1
EL: 24.22'

MATCH LINE SEE BELOW

RECORD DRAWING - 02/14/17

MATCH LINE SEE ABOVE

GAS VENT #3
N: 685570.8
E: 603027.7
EL: 23.63'

GAS VENT #2
N: 685366.8
E: 603295.2
EL: 17.31'

GAS VENT #1
N: 685187.5
E: 603530
EL: 14.49'

0 40 80 Feet
SCALE

## LEGEND

- CLASS A/16 OZ GEOTEXTILE
- GEOCOMPOSITE GAS VENT LAYER (GVL)
- GEOSYNTHETIC CLAY LINER (GCL)
- GAS VENT (NOT TO SCALE)
- GAS VENT PIPE
- SCB WALL
- HB WALL (Inner Edge)


NOTE: Drawing is schematic in nature. Actual seam locations may vary due to the geomembrane grading.


| REV | DATE | BY | CHK'D | APPR'VD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 10/27/16 | EP | CP | CP | RECORD DRAWING |
| 1 | 11/04/16 | EP | CP | CP | RECORD DRAWING |
| 2 | 11/21/16 | EP | CP | CP | RECORD DRAWING |
| 3 | 11/29/16 | EP | CP | CP | RECORD DRAWING |
| 4 | 02/14/16 | EP | CP | CP | RECORD DRAWING |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 NORTH CAP GVL/GCL Layout
Class A Geotextile/Gas Vent Layer/Geosynthetic Clay Liner
02/14/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




0 80 160 Feet

RECORD DRAWING - 02/14/17

## LEGEND

- GEOCOMPOSITE GAS VENT LAYER (GVL)
- GEOSYNTHETIC CLAY LINER (GCL)
- Class A/16 oz Geotextile
- SCB WALL
- HB WALL (Inner Edge)
- GAS VENT PIPE
- GAS VENT (NOT TO SCALE)

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 1 | 02/14/17 | EJP | AE | AE | ADDED GAS VENT DETAIL |


ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
SA6 SOUTH CAP GVL/GCL LAYOUT
Class A Geotextile/Gas Vent Layer/Geosynthetic Clay Liner
02/14/17

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

**ATTACHMENT G**
**SA-6 NORTH AND SOUTH DEFERRED AREAS (FIGURE 5)**

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (I) THIS DOCUMENT, CONTAINS PROPRIETARY INFORMATION, HAS BEEN PREPARED FOR THE EXPRESS PURPOSE OF CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (II) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS SPECIFICALLY PREPARED. ANY OTHER USE OF RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.


N
HACKENSACK RIVER
SA-6 NORTH
SA-6 NORTH RESIDENTIAL AREA
72-INCH FORCE MAIN
DN □10
DN □9
DN □7
DN □9
DN □6
SA-6 NORTH (OPEN SPACE AREA)
TRACT 1
SA-7
DN □4
DN □5
SA-7 RESIDENTIAL AREA NFA OBTAINED
TRACT 2
SA-6 SOUTH
SA-6 SOUTH OPEN SPACE AOC
SA-6 SOUTH RESIDENTIAL AOC
DN □14
DN □2
DN □1
DN □3
115-CF-BH1S
115-CF-BH2N
115-CF-BH2S
115-CF-BH3N
115-PZ-503
115-CF-BH4N
115-CF-BH5N
115-CF-BH5S
115-CF-BH6S
115-CF-BH7S
115-CF-BH7N
115-CF-BH93
115-CF-BH101
115-CF-BH94
115-CF-BH104
115-CF-BH96
115-CF-BH106
115-CF-BH102
115-CF-BH111
115-CF-BH103
115-CF-BH114
115-CF-BH105
115-CF-BH116
115-PZ-500
115-CF-BH112
115-CF-BH115
115-WC-0970
115-WC-1060
115-WC-10901
115-WC-11201
115-WC-13903
115-WC-1480
115-PZ-502
115-WC-E191A
115-PZ-501
FIRST AVE.
SECOND AVE.
THIRD AVE.
FOURTH AVE.
STEGMAN PKWY
RIVERSIDE DR.
A ST.
B ST.
C ST.
D ST.
E ST.
F ST.
KELLOGG STREET
TRILOBAL ST.
MARION JAMES BLVD.
MLK DRIVE
WEST SIDE AVE.
NEWARK BAY
HUDSON RIVER
PENNSYLVANIA RAILROAD
NEW JERSEY TURNPIKE
NEWARK BAY EXTENSION
HOLLAND TUNNEL
HOLLAND TUNNEL
HOLLAND TUNNEL

# ATTACHMENT H
# IN-SITU LOCATIONS AND SUMMARY TABLES

WHICH, IF HAS BEEN DELIVERED, MAY NOT BE USED OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




UTILITY LOCATIONS BASED ON ALTA/ASCM LAND TITLE SURVEY FOR BLOCK 1290.1 – LOTS 2D,2E,15D, 15B & 16A, DATED 5/23/08

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150438
*DRAWING:* TARGETED IN-SITU TREATMENT AREAS-03

*PREPARED/DATE:* STR 06/09/15

*CHECKED/DATE:* DN 06/09/15


amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE □□RE□I□E□□**
TARGETED IN-SITU TREATMENT AREAS
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY

P:\JOBS\WHOLE\JERSEY CITY\SA 6 NORTH\REPORT\3480150438\5710\CURRENT DRAWINGS\TARGETED IN-SITU TREATMENT AREAS-03.dwg Tue, 09 Jun 2015 - 3:56pm rcotrupia Layout: FIG 2

UNLESS OTHERWISE AGREED IN A WRITTEN CONTRACT BETWEEN AMEC FOSTER WHEELER AND ITS CLIENT: (1) THIS DOCUMENT CONTAINS INFORMATION, DATA AND DESIGN THAT IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED; AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN DELIVERED. ANY OTHER USE OR RELIANCE ON THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK AND RESPONSIBILITY.




TARGETED TREATMENT AREA 10-1
- 5 INJECTION POINTS – SPACED @ 15' O.C.
- CONTAMINATED ZONE 12'-14'
- INJECTION ZONE 10'-16'
- NUMBER OF INJECTION POINTS MAY BE ADJUSTED IN THE FIELD

AREA = APPROX. 800 SF

PROPOSED HYDRAULIC BARRIER WALL.

LEGEND

- DECEMBER 2016 SOIL BORING
- MARCH 2017 SOIL BORING
- MARCH 2016 (6-MONTH) SOIL BORING
- PREVIOUS SOIL BORINGS
- EXISTING NEW PERMANENT MONITORING WELL LOCATION
- INJECTION POINT LOCATION
- EXISTING OBSERVATION TEMPORARY WELL POINT (TWP)
- <20 ppm HEXAVALENT CHROMIUM SAMPLE LOCATION
- 20-240 ppm HEXAVALENT CHROMIUM SAMPLE LOCATION
- >240 ppm HEXAVALENT CHROMIUM SAMPLE LOCATION
- BLOCK/LOT LINE (APPROXIMATE LOCATION)
- STORM SEWER
- 72" FORCEMAIN SANITARY SEWER
- 54" OUTFALL (ABANDONED)
- NORTHERN EDGE OF BAYFRONT REDEVELOPMENT CURBLINE OF NEW STEGMAN BOULEVARD
- LIMITS OF TARGETED IN-SITU TREATMENT
- RELOCATED HYDRAULIC BARRIER
- APPROXIMATE LIMITS OF AREA WHERE DETECTED HEXAVALENT CHROMIUM CONCENTRATION VALUES >20 mg/kg
- EXISTING BUILDINGS
- IN-SITU TREATMENT AREA
- U NOT DETECTED
- J ESTIMATED CONCENTRATION

UTILITY LOCATIONS BASED ON ALTA/ASCM LAND TITLE SURVEY FOR BLOCK 1290.1 – LOTS 2D,2E,15D, 15B & 16A, DATED 5/23/08

NOTES:

1. SEE FIGURE 2 FOR LOCATION OF DETAIL MAP.
2. FIGURE PROVIDED TO SUMMARIZE MULTIPLE SAMPLING EVENTS FROM RI TO POST-INJECTION PERFORMANCE ASSESSMENTS.

0 10 20 40
SCALE IN FEET

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| 1 | 07/28/16 | REVISED TO ADJUST INJECTION POINTS (INCLUDED IN 07/28/16 DGW-PBR APPLICATION) | STR | DEN |

*Amec Foster Wheeler PROJECT No.* 3480150438
*DRAWING:* TARGETED IN-SITU TREATMENT NORTHERN PORTION 02

*PREPARED/DATE:* STR 06/05/15
*CHECKED/DATE:* DN 06/05/15

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE □□ □RE□I□E□□**
IN-SITU INJECTION
NORTHERN PORTION OF
TREATMENT AREA 10-1
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY


P:\GROUP\HOBOKEN\JERSEY CITY\SA 6 NORTH\REPORT\3480150438\CAD\FIGURES\TARGETED IN-SITU TREATMENT NORTHERN PORTION 02.dwg Tue, 29 Aug 2017 - 10:57am chorne Anyfield Layout: Fig 5A




| 087-SB-662 | | |
|---|---|---|
| Sample Depth | 16 - 17 | 17 - 17.5 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.92 U | 1.7 |

| 087-SB-660 | | |
|---|---|---|
| Sample Depth | 2 - 3 | 3 - 4 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | **26.3 J** | 1.3 |

| 087-SB-661 | | |
|---|---|---|
| Sample Depth | 16 - 17 | 17 - 17.5 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.77 U | 1.7 |




| 087-SB-H25 | | |
|---|---|---|
| 02-04 | **43.6** | J |
| 04-06 | 7.6 | J |
| 06-08 | 2 | U |
| 08-10 | 2 | U |
| 10-12 | 2 | U |
| 14-16 | 2 | U |
| 16-18 | **84.4** | |
| 18-20 | 2 | U |

**Targeted Treatment Area 7**

- 12 Injection Points
- Contaminated Zone 2' – 4' & 16' – 18'
- Injection Zone 0' – 6' & 14' – 17' (adjusted in the field from 20', due to detection of meadow mat at 17' bgs)

| 087-SB-659 | | |
|---|---|---|
| Sample Depth | 2 - 3 | 3 - 4 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.54 U | 0.55 U |

**Legend**

- Shallow Soil Boring
- Deep Soil Boring
- Previous Soil Sample Location (Hexavalent Chromium Result < 20 ppm)
- Previous Soil Sample Location (Hexavalent Chromium Result > 20 ppm)
- SS — Storm Sewer
- CB — Catch Basin
- MH — Manhole
- Buried Electrical Utility
- Treatment Area 7

20 10 0 20

Scale In Feet

Project Number:
3480150488

Prepared/Date:
WSL 06/22/2016


Checked/Date:
DEN 06/22/2016

amec foster wheeler
ENVIRONMENT & INFRASTRUCTURE
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**Figure 1**
Treatment Area 7
In-situ Chemical Injection Treatment Process
Study Area 6 North
Jersey City, New Jersey

| 087-SB-O29 | | |
|---|---|---|
| 00-02 | 4.5 | J |
| 02-04 | 2.5 | UJ |
| 04-06 | 2.5 | UJ |
| 06-08 | 4.1 | J |
| 08-10 | 5.5 | J |
| 10-12 | **68.8** | J |
| 12-14 | 2.5 | UJ |
| 14-16 | 13.7 | J |
| 16-18 | 9.5 | J |
| 18-20 | **25.4** | UJ |

| 087-SB-658 | | |
|---|---|---|
| Sample Depth | 10 - 11 | 11 - 12 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.74 | 0.49 U |




**Targeted Treatment Area 8**

- 6 Injection Points
- Contaminated Zone 10' – 12' & 18' – 20'
- Injection Zone 8' – 14' & 15' – 17.5' (adjusted in the field from 16' – 22', due to detection of meadow mat at 17' bgs)

| 087-SB-657B | | |
|---|---|---|
| Sample Depth | 15.5 - 16.5 | 16.5 - 17.5 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.81 U | 0.82 |

| 087-SB-663 | | |
|---|---|---|
| Sample Depth | 15.5 - 16.5 | 16.5 - 17.5 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.92 | 0.69 U |

| 087-SB-657A | | |
|---|---|---|
| Sample Depth | 10 - 11 | 11 - 12 |
| Sample Date | 6/27/2016 | 6/27/2016 |
| HEXAVALENT CHROMIUM | 0.49 U | 0.61 |




**Legend**

- ⊗ Soil Boring (Refusal, No Samples Taken)
- ◓ Shallow Soil Boring
- ◒ Deep Soil Boring
- Previous Soil Sample Location (Hexavalent Chromium Result < 20 ppm)
- Previous Soil Sample Location (Hexavalent Chromium Result > 20 ppm)
- SS Storm Sewer
- CB Catch Basin
- MH Manhole
- Treatment Area 8

10 5 0 10

Scale In Feet

Project Number:
3480150488

Prepared/Date:
WSL 06/26/2013


Checked/Date:
DEN 06/14/2016


amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**Figure 2**
**Treatment Area 8**
**In-situ Chemical Injection Treatment Process**
Study Area 6 North
Jersey City, New Jersey

**ATTACHMENT I**
**STRATUM D REPAIR RECORD DRAWING**





## TOP OF VINYL SHEET PILE PROFILE


HORIZONTAL SCALE: 1"=20'

VERTICAL SCALE: 1"=5'





## TYPICAL REPAIR SECTION ALONG HYDRAULIC BARRIER

NTS




## SAND BENTONITE KEY DETAIL

NTS




## GCL CONNECTION TO HYDRAULIC BARRIER

NTS

LEGEND

- VINLY SHEET PILE AS BUILT
- HYDRAULIC BARRIER AS BUILT
- EXCAVATION CONTOURS
- GEOSYNTHETIC CLAY LINER (GCL)
- 3.7 — GCL SPOT ELEVATION

RECORD DRAWING - 12/08/16

NOTES

1. TRASH PIT WAS BACKFILLED WITH SOIL TO THE TOP OF THE CONCRETE WALLS WHICH WERE DEMOLISHED TO AN APPROXIMATE ELEVATION OF 7.0 FT TO 10.0 FT.
2. SUMP VAULT WAS BACKFILLED WITH FLOWABLE FILL TO AN APPROXIMATE ELEVATION OF 5.0 FT AND THEN SOIL BACKFILL WAS PLACED TO THE TOP OF THE VAULT AT AN ELEVATION OF APPROXIMATELY 12.0 FT.

0 20 40 FEET

SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/8/16 | EJP | AE | AE | AB-JCIA Trash Pit Meadow Mat Repair |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: JCIA Trash Pit As Built Vinyl Sheetpile and Meadow Mat Repair 12/08/16

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**ATTACHMENT J**
**SA-6 NORTH AND SOUTH ROOT BARRIER TOPOGRAPHIC**

MATCH LINE SHEET CN-124A

BARRIER WALL LIMIT (TYP.)

ROUTE 440

INSIDE SOUTHWEST EDGE OF SCB WALL LIMITS

LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 NORTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM JULY 2016 THROUGH SEPT. 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 150 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12001511A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
NORTH CAP GDL COVER
SOIL GRADING PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2929


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | 11/16/16 |
| PROJ | 3480-10-0027 |
| DWG | CN-123A |
| SHEET | 1 OF 2 |

**Honeywell**
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 NORTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR CHK | APVD | |


R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS38737


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC. THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.



FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\NORTH CAP GDL COVER SOIL SURVEY-11-16-16.dwg PLOT DATE: Tue, 31 Jan 2017 PLOT TIME: 12:10 PM

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\NORTH CAP GDL COVER SOIL SURVEY-1-11-16.dwg PLOT DATE: Tue, 31 Jan 2017 PLOT TIME: 1:27 PM




## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 NORTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM JULY 2016 THROUGH SEPT. 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29*

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER: 12001511A

| | |
|---|---|
| SHEET | 2 OF 2 |
| DWG | CN-124A |
| PROJ | 3480-10-0027 |
| DATE | 11/16/16 |

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
NORTH CAP GDL COVER SOIL GRADING PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 NORTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|

DSGN | DR | CHK | APVD

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING.

MATCH LINE SHEET C-126

INSIDE SOUTHWEST EDGE OF SCB WALL LIMITS

BARRIER WALL LIMIT (TYP.)

LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM OCT. 2015 THROUGH MAY 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

| NO. | DATE | REVISION | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| DSGN | | | | | | | |


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12001511A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP GDL COVER
SOIL GRADING PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ 08619
(609) 689 - 2929



VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 11/17/16 |
| PROJ | 3480-10-0027 |
| DWG | C-125 |
| SHEET | 1 OF 3 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.



FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SOUTH CAP GDL COVER SOIL SURVEY-11-17-16.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 4:32 PM




## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM OCT. 2015 THROUGH MAY 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS35737

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR | CHK | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC; INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP GDL COVER
SOIL GRADING PLAN

FILE NUMBER 12001511A


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 08223


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 11/17/16 |
| PROJ | 3480-10-0027 |
| DWG | C-126 |
| SHEET | 2 OF 3 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SOUTH CAP GDL COVER SOIL SURVEY-11-17-16.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 4:08 PM




LEGEND:

5 MAJOR CONTOUR

4 MINOR CONTOUR

0 20 40 80

SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT GDL COVER SOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP GDL COVER SOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM OCT. 2015 THROUGH MAY 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

NOTE: ROOT BARRIER INSTALLED DIRECTLY ON THE AS-BUILT GDL COVER SOIL CONTOURS SHOWN ON THIS DRAWING


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12001511A

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR | CHK | APVD |

R. THOMAS HUGG

NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS38737


Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962


STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP GDL COVER
SOIL GRADING PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 889 - 2829


VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | 11/17/16 |
| PROJ | 3480-10-0027 |
| DWG | C-127 |
| SHEET | 3 OF 3 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.



FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SOUTH CAP GDL COVER SOIL SURVEY-11-17-16.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 4:09 PM

**ATTACHMENT K**
**SA-6 NORTH AND SOUTH STRUCTURAL FILL RECORD DRAWINGS**







STRUCTURAL FILL CROSS SECTION
NTS

LEGEND

- Structural Fill Under Roadways
- SCE[illegible]LL
- HB WALL (Inner Edge)

0 80 160 Feet

SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/7/16 | EJP | AE | AE | STRUCTURAL FILL UNDER ROADWAYS – NORTH CAP |
| 1 | 12/15/16 | EJP | AE | AE | ADDED FUTURE DEVELOPMENT LAYOUT & STRUCTURAL FILL X-SECTION |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
Structural Fill Under Roadways
NORTH CAP
12/15/16

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

N

GRAND BLVD.

RIVERSIDE DRIVE

A STREET

B STREET

C STREET

D STREET

FRONTAGE STREET

RIVER

D

B

C

A

18

19

20

21

22

23

MATCH LINE SEE BELOW

MATCH LINE SEE ABOVE

RECORD DRAWING - 12/15/16

LEGEND


Structural Fill Under Roadways

SCE[illegible]LL

HB WALL (Inner Edge)

0 80 160 Feet

SCALE




STRUCTURAL FILL CROSS SECTION
NTS

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/7/16 | EJP | AE | AE | STRUCTURAL FILL UNDER ROADWAYS – SOUTH CAP |
| 1 | 12/15/16 | EJP | AE | AE | ADDED FUTURE DEVELOPMENT LAYOUT & STRUCTURAL FILL X-SECTION |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: STRUCTURAL FILL UNDER ROADWAYS SOUTH CAP 12/15/16

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

**ATTACHMENT L**
**SA-6 NORTH AND SOUTH CAP COMPACTION LOGS**

# 1.0 Field Density Test Summary Log

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | TEST | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | CS-01-1 | 7/13/2016 | 686056.7 | 602102.5 | 11.70 | 107.6 | 7.8 | 117 | 8.6 | 92.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-02-1 | 7/13/2016 | 686078.8 | 602160.6 | 12.30 | 111.1 | 7.5 | 117 | 8.6 | 95.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-03-1 | 7/13/2016 | 686035.6 | 602132.4 | 12.50 | 107.5 | 7.8 | 117 | 8.6 | 92.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-04-1 | 7/13/2016 | 685983.2 | 602018.1 | 12.90 | 111.1 | 7.5 | 117 | 8.6 | 95.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-05-1 | 7/13/2016 | 685959.4 | 602142.7 | 13.50 | 110 | 7.5 | 117 | 8.6 | 94.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-06-1 | 7/13/2016 | 685999.9 | 602165.7 | 15.70 | 112.15 | 7 | 117 | 8.6 | 96.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-07-1 | 7/13/2016 | 686052.5 | 602190.6 | 12.30 | 110 | 8.4 | 117 | 8.6 | 94.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-08-1 | 7/13/2016 | 685932.8 | 602188.2 | 14.00 | 107.5 | 7.8 | 117 | 8.6 | 91.9 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-09-1 | 7/13/2016 | 685996.5 | 602222 | 15.90 | 108.16 | 8.3 | 117 | 8.6 | 93.0 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-10-1 | 7/13/2016 | 686031.2 | 602252.7 | 12.40 | 111.1 | 7.2 | 117 | 8.6 | 95.0 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-11-1 | 7/18/2016 | 686019.3 | 602311.2 | 13.10 | 121.1 | 5.2 | 117 | 8.6 | 103.5 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-12-1 | 7/18/2016 | 686002.8 | 602277.9 | 13.00 | 116.6 | 5.3 | 117 | 8.6 | 99.7 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-13-1 | 7/18/2016 | 685956.2 | 602253.6 | 16.30 | 115.9 | 5.1 | 117 | 8.6 | 99.1 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-14-1 | 7/18/2016 | 685902.6 | 602234.8 | 14.50 | 117.2 | 7.9 | 117 | 8.6 | 100.2 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | SF-01-1 | 7/18/2016 | 686054.2 | 602111.9 | 13.40 | 117.5 | 3.9 | 112.2 | 9.7 | 104.7 | 95 | 1 | Structural Fill | Final Elevation | V5N |
| 1 | SF-02-1 | 7/18/2016 | 686072.1 | 602155.3 | 13.41 | 118.1 | 1.8 | 112.2 | 9.7 | 105.3 | 95 | 1 | Structural Fill | | V5N |
| 2 | SF-02-2 | 7/18/2016 | 686067.9 | 602166.2 | 13.80 | 113.1 | 2.5 | 112.2 | 9.7 | 100.8 | 95 | 1 | Structural Fill | Final Elevation | V5N |
| 1 | SF-03-1 | 7/18/2016 | 686058.0 | 602202.1 | 13.40 | 114.9 | 1.6 | 112.2 | 9.7 | 102.4 | 95 | 1 | Structural Fill | | V5N |
| 1 | SF-04-1 | 7/18/2016 | 686035.3 | 602247.1 | 13.30 | 115.0 | 2.2 | 112.2 | 9.7 | 102.5 | 95 | 2 | Structural Fill | | V5N |
| 1 | HC-24-1 | 8/29/2016 | 685713.6 | 602653.3 | 21.60 | 115.4 | 8.5 | 126 | 9.5 | 91.6 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-25-1 | 8/29/2016 | 685766.9 | 602684.5 | 18.80 | 116.7 | 8.8 | 126 | 9.5 | 92.6 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-26-1 | 8/29/2016 | 685809.6 | 602705.3 | 18.70 | 118.9 | 8.4 | 126 | 9.5 | 94.4 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-92-1 | 9/16/2016 | 685103.9 | 603560.3 | 13.90 | 105.7 | 7.5 | 126 | 9.5 | 83.9 | 90 | 12 | Horizon C | HC-92-1R (Page 8) | V5N |
| 1 | HC-01-1 | 7/20/2016 | 686011.1 | 602089.8 | 12.90 | 120.5 | 5.2 | 126 | 9.5 | 95.6 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-12-1 | 7/20/2016 | 685987.4 | 602075.7 | 13.50 | 107.0 | 3.8 | 112.2 | 9.7 | 95.4 | 95 | 1 | Structural Fill | | V5N |
| 1 | SF-13-1 | 7/20/2016 | 685963.8 | 602121.8 | 14.20 | 107.6 | 3.7 | 112.2 | 9.7 | 95.9 | 95 | 1 | Structural Fill | | V5N |
| 1 | SF-14-1 | 7/20/2016 | 685931.2 | 602176.8 | 14.90 | 108.5 | 3.5 | 112.2 | 9.7 | 96.7 | 95 | 2 | Structural Fill | | V5N |
| 1 | CS-15-1 | 7/22/2016 | 685859.2 | 602274.7 | 15.30 | 113.6 | 5.3 | 117 | 8.6 | 97.1 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-16-1 | 7/22/2016 | 685889.8 | 602275.9 | 15.50 | 115.1 | 7.5 | 117 | 8.6 | 98.4 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-17-1 | 7/22/2016 | 685930.0 | 602308.4 | 16.90 | 114.7 | 5.2 | 117 | 8.6 | 98.0 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-18-1 | 7/22/2016 | 685978.5 | 602322.4 | 13.70 | 115.2 | 6.3 | 117 | 8.6 | 98.5 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-19-1 | 7/22/2016 | 685995.4 | 602358.6 | 13.60 | 112.3 | 7.3 | 117 | 8.6 | 96.0 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-20-1 | 7/22/2016 | 685974.2 | 602407.6 | 14.20 | 110.5 | 8.5 | 117 | 8.6 | 94.4 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-21-1 | 7/22/2016 | 685955.3 | 602367.3 | 14.20 | 115.2 | 4.6 | 117 | 8.6 | 98.5 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-22-1 | 7/22/2016 | 685908.8 | 602343.5 | 15.00 | 121.8 | 9.2 | 117 | 8.6 | 104.1 | 90 | 3 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | TEST | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | CS-23-1 | 7/22/2016 | 685867.1 | 602319.4 | 16.10 | 113.1 | 5.3 | 117 | 8.6 | 96.7 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | HC-02-1 | 7/20/2016 | 685997.1 | 602121.8 | 13.40 | 120.0 | 5.0 | 126 | 9.5 | 95.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-03-1 | 7/20/2016 | 686032.1 | 602156.7 | 12.40 | 119.3 | 5.6 | 126 | 9.5 | 94.7 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 2 | SF-03-2 | 7/22/2016 | 686050.7 | 602208.4 | 14.20 | 114.8 | 1.7 | 112.2 | 9.7 | 102.3 | 95 | 1 | Structural Fill | Final Elevation | V5N |
| 2 | SF-04-2 | 7/22/2016 | 686035.2 | 602238.3 | 14.20 | 115.6 | 1.4 | 112.2 | 9.7 | 103.0 | 95 | 1 | Structural Fill | Final Elevation | V5N |
| 1 | HC-04-1 | 7/20/2016 | 686008.8 | 602201.9 | 16.20 | 122.0 | 5.4 | 126 | 9.5 | 96.8 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-05-1 | 7/20/2016 | 685970.9 | 602168.3 | 14.40 | 119.5 | 5.6 | 126 | 9.5 | 94.8 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-05-1 | 7/28/2016 | 686021.4 | 602296.2 | 14.40 | 107.5 | 8.2 | 112.2 | 9.7 | 95.8 | 95 | 3 | Structural Fill | Final Elevation | V5N |
| 2 | SF-12-2 | 7/28/2016 | 685986.7 | 602075.0 | 14.00 | 108.8 | 7.5 | 112.2 | 9.7 | 97.0 | 95 | 1 | Structural Fill | Final Elevation | V5N |
| 2 | SF-13-2 | 7/28/2016 | 685958.4 | 602125.9 | 15.00 | 107.6 | 8.0 | 112.2 | 9.7 | 95.9 | 95 | 1 | Structural Fill | Final Elevation | V5N |
| 1 | SF-15-1 | 7/28/2016 | 685894.5 | 602235.3 | 15.80 | 106.7 | 8.3 | 112.2 | 9.7 | 95.1 | 95 | 3 | Structural Fill | | V5N |
| 1 | CS-24-1 | 8/3/2016 | 685812.8 | 602367.6 | 16.10 | 108.1 | 8.3 | 117 | 8.6 | 92.4 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-25-1 | 8/3/2016 | 685841.8 | 602355.4 | 16.40 | 107.6 | 8.9 | 117 | 8.6 | 92.0 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-26-1 | 8/3/2016 | 685887.8 | 602387.1 | 18.10 | 108.9 | 8.8 | 117 | 8.6 | 93.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-27-1 | 8/3/2016 | 685931.8 | 602410.4 | 15.10 | 107.6 | 9.5 | 117 | 8.6 | 92.0 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-28-1 | 8/3/2016 | 685951.7 | 602456.4 | 14.70 | 108.9 | 8.5 | 117 | 8.6 | 93.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-29-1 | 8/3/2016 | 685908.7 | 602454.7 | 15.80 | 110.0 | 6.5 | 117 | 8.6 | 94.0 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-30-1 | 8/3/2016 | 685864.2 | 602431.3 | 16.00 | 107.6 | 8.8 | 117 | 8.6 | 92.0 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-31-1 | 8/3/2016 | 685820.3 | 602408.9 | 16.90 | 110.0 | 6.1 | 117 | 8.6 | 94.0 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | HC-06-1 | 7/22/2016 | 685943.5 | 602217.1 | 16.60 | 121.2 | 8.2 | 126 | 9.5 | 96.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-07-1 | 7/22/2016 | 685985.9 | 602241.3 | 16.50 | 123.9 | 10.2 | 126 | 9.5 | 98.3 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-08-1 | 7/28/2016 | 685953.9 | 602285.9 | 17.12 | 114.2 | 8.9 | 126 | 9.5 | 90.6 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-09-1 | 7/28/2016 | 685921.7 | 602262.1 | 15.00 | 113.5 | 9.2 | 126 | 9.5 | 90.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-10-1 | 8/5/2016 | 685897.1 | 602316.3 | 15.80 | 117.5 | 8.2 | 126 | 9.5 | 93.3 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-11-1 | 8/5/2016 | 685939.6 | 602343.2 | 17.70 | 119.5 | 7.1 | 126 | 9.5 | 94.8 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | SF-06-1 | 8/5/2016 | 686001.6 | 602337.9 | 14.70 | 110.0 | 2.3 | 112.2 | 9.7 | 98.0 | 95 | 3 | Structural Fill | Final Elevation | V5N |
| 1 | SF-07-1 | 8/5/2016 | 685981.7 | 602383.3 | 15.20 | 111.0 | 1.1 | 112.2 | 9.7 | 98.9 | 95 | 3 | Structural Fill | Final Elevation | V5N |
| 2 | SF-14-2 | 8/5/2016 | 685921.2 | 602172.6 | 15.20 | 110.0 | 1.8 | 112.2 | 9.7 | 98.0 | 95 | 2 | Structural Fill | Final Elevation | V5N |
| 2 | SF-15-2 | 8/5/2016 | 685896.6 | 602231.8 | 16.40 | 110.0 | 1.8 | 112.2 | 9.7 | 98.0 | 95 | 3 | Structural Fill | Final Elevation | V5N |
| 1 | SF-16-1 | 8/5/2016 | 685843.1 | 602309.5 | 16.40 | 111.0 | 1.1 | 112.2 | 9.7 | 98.9 | 95 | 3 | Structural Fill | Final Elevation | V5N |
| 1 | CS-32-1 | 8/10/2016 | 685796.3 | 602441.1 | 17.30 | 106.1 | 8.8 | 117 | 8.6 | 90.7 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-33-1 | 8/10/2016 | 685845.9 | 602479.3 | 16.50 | 105.6 | 10.0 | 117 | 8.6 | 90.3 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-34-1 | 8/10/2016 | 685890.1 | 602491.3 | 18.50 | 105.9 | 7.2 | 117 | 8.6 | 90.5 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-35-1 | 8/10/2016 | 685926.5 | 602522.2 | 11.00 | 108.3 | 9.6 | 117 | 8.6 | 92.6 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-36-1 | 8/10/2016 | 685910.8 | 602551.9 | 15.70 | 105.9 | 9.8 | 117 | 8.6 | 90.5 | 90 | 5 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | TEST | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | CS-37-1 | 8/10/2016 | 685859.0 | 602544.1 | 19.20 | 110.0 | 7.8 | 117 | 8.6 | 94.0 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-38-1 | 8/10/2016 | 685818.5 | 602520.0 | 19.60 | 106.0 | 10.2 | 117 | 8.6 | 90.6 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-39-1 | 8/10/2016 | 685771.2 | 602499.5 | 17.90 | 106.0 | 10.2 | 117 | 8.6 | 90.6 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-40-1 | 8/10/2016 | 685761.7 | 602455.7 | 17.10 | 112.2 | 7.8 | 117 | 8.6 | 95.9 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-41-1 | 8/10/2016 | 685727.7 | 602509.9 | 17.80 | 105.6 | 9.2 | 117 | 8.6 | 90.3 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-42-1 | 8/10/2016 | 685750.8 | 602543.2 | 17.90 | 105.6 | 8.9 | 117 | 8.6 | 90.3 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-43-1 | 8/10/2016 | 685790.6 | 602568.0 | 17.10 | 106.0 | 8.9 | 117 | 8.6 | 90.6 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-44-1 | 8/10/2016 | 685829.9 | 602580.0 | 19.50 | 112.5 | 7.8 | 117 | 8.6 | 96.2 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-45-1 | 8/10/2016 | 685883.5 | 602613.3 | 16.10 | 105.5 | 9.2 | 117 | 8.6 | 90.2 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | SF-08-1 | 8/10/2016 | 685947.6 | 602444.5 | 15.50 | 107.6 | 5.6 | 112.2 | 9.7 | 95.9 | 95 | 4 | Structural Fill | Final Elevation | V5N |
| 1 | HC-12-1 | 8/5/2016 | 685923.2 | 602385.8 | 15.60 | 118.5 | 9.6 | 126 | 9.5 | 94.0 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-13-1 | 8/5/2016 | 685878.4 | 602355.3 | 18.70 | 116.5 | 11.6 | 126 | 9.5 | 92.5 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-14-1 | 8/5/2016 | 685857.5 | 602397.8 | 19.00 | 116.5 | 10.6 | 126 | 9.5 | 92.5 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-15-1 | 8/5/2016 | 685901.5 | 602426.6 | 16.00 | 117.5 | 8.9 | 126 | 9.5 | 93.3 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-16-1 | 8/11/2016 | 685877.5 | 602467.2 | 16.50 | 119.8 | 4.5 | 126 | 9.5 | 95.1 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | SF-09-1 | 8/11/2016 | 685919.3 | 602481.2 | 16.30 | 107.8 | 5.2 | 112.2 | 9.7 | 96.1 | 95 | 4 | Structural Fill | Final Elevation | V5N |
| 1 | SF-18-1 | 8/11/2016 | 685796.5 | 602421.3 | 18.00 | 107.8 | 5.0 | 112.2 | 9.7 | 96.1 | 95 | 4 | Structural Fill | | V5N |
| 1 | SF-19-1 | 8/11/2016 | 685765.4 | 602477.7 | 18.70 | 108.5 | 5.2 | 112.2 | 9.7 | 96.7 | 95 | 5 | Structural Fill | | V5N |
| 1 | CS-46-1 | 8/16/2016 | 685858.5 | 602654.7 | 16.70 | 106.7 | 5.4 | 117 | 8.6 | 91.2 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-47-1 | 8/16/2016 | 685816.0 | 602640.9 | 14.90 | 117.6 | 6.3 | 117 | 8.6 | 100.5 | 90 | 6 | GDL Cover Soil | Start Reduced Frequency | V5N |
| 1 | CS-48-1 | 8/16/2016 | 685772.5 | 602607.5 | 15.30 | 118.0 | 7.6 | 117 | 8.6 | 100.9 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-49-1 | 8/16/2016 | 685725.8 | 602586.9 | 16.30 | 115.6 | 7.1 | 117 | 8.6 | 98.8 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-50-1 | 8/16/2016 | 685696.7 | 602558.7 | 17.20 | 116.2 | 5.8 | 117 | 8.6 | 99.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-51-1 | 8/16/2016 | 685666.9 | 602613.2 | 18.90 | 112.5 | 4.4 | 117 | 8.6 | 96.2 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-52-1 | 8/16/2016 | 685706.9 | 602626.6 | 18.00 | 118.2 | 5.7 | 117 | 8.6 | 101.0 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-53-1 | 8/16/2016 | 685738.4 | 602639.4 | 17.60 | 114.5 | 6.7 | 117 | 8.6 | 97.9 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-54-1 | 8/16/2016 | 685793.1 | 602675.7 | 17.50 | 113.7 | 6.0 | 117 | 8.6 | 97.2 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-55-1 | 8/16/2016 | 685830.0 | 602699.4 | 15.70 | 113.0 | 8.9 | 117 | 8.6 | 96.6 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-94-1 | 8/19/2016 | 685064.3 | 603656.9 | 7.50 | 109.8 | 5.4 | 117 | 8.6 | 93.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-95-1 | 8/19/2016 | 685177.8 | 603698.4 | 6.20 | 113.7 | 7.9 | 117 | 8.6 | 97.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | HC-17-1 | 8/11/2016 | 685824.6 | 602442.2 | 17.50 | 122.7 | 6.4 | 126 | 9.5 | 97.4 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-18-1 | 8/11/2016 | 685791.3 | 602476.8 | 20.80 | 118.5 | 5.8 | 126 | 9.5 | 94.0 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-19-1 | 8/11/2016 | 685833.9 | 602502.6 | 19.80 | 124.1 | 5.3 | 126 | 9.5 | 98.5 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | SF-10-1 | 8/19/2016 | 685907.4 | 602542.6 | 16.80 | 120.0 | 2.4 | 112.2 | 9.7 | 107.0 | 95 | 5 | Structural Fill | | V5N |
| 1 | SF-17-1 | 8/19/2016 | 685816.7 | 602355.7 | 17.40 | 119.0 | 1.2 | 112.2 | 9.7 | 106.1 | 95 | 4 | Structural Fill | Final Elevation | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | LOCATION ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | SF-20-1 | 8/19/2016 | 685723.9 | 602524.1 | 19.30 | 115.8 | 2.8 | 112.2 | 9.7 | 103.2 | 95 | 5 | Structural Fill | Final Elevation | V5N |
| 1 | CS-57-1 | 8/24/2016 | 685725.4 | 602744.3 | 23.00 | 119.0 | 6.2 | 117 | 8.6 | 101.7 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-58-1 | 8/24/2016 | 685648.5 | 602672.7 | 19.40 | 114.0 | 7.6 | 117 | 8.6 | 97.4 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-59-1 | 8/24/2016 | 685678.3 | 602742.7 | 22.60 | 120.3 | 5.3 | 117 | 8.6 | 102.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-60-1 | 8/24/2016 | 685783.3 | 602811.9 | 19.60 | 114.3 | 8.3 | 117 | 8.6 | 97.7 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-61-1 | 8/24/2016 | 685983.1 | 602881.8 | 19.10 | 118.6 | 6.6 | 117 | 8.6 | 101.4 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-62-1 | 8/24/2016 | 685690.9 | 602859.0 | 21.30 | 115.6 | 4.5 | 117 | 8.6 | 98.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-63-1 | 8/24/2016 | 685600.9 | 602803.9 | 19.90 | 116.4 | 6.2 | 117 | 8.6 | 99.5 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-64-1 | 8/24/2016 | 685711.9 | 602937.4 | 20.40 | 108.3 | 3.9 | 117 | 8.6 | 92.6 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-65-1 | 8/24/2016 | 685611.8 | 602885.6 | 20.30 | 110.2 | 4.8 | 117 | 8.6 | 94.2 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-66-1 | 8/24/2016 | 685705.6 | 603007.6 | 19.70 | 117.8 | 7.7 | 117 | 8.6 | 100.7 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-67-1 | 8/24/2016 | 685615.9 | 602991.2 | 21.40 | 113.1 | 6.6 | 117 | 8.6 | 96.7 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-68-1` | 8/24/2016 | 685536.6 | 602916.2 | 19.40 | 112.3 | 6.2 | 117 | 8.6 | 96.0 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | SF-11-1 | 8/24/2016 | 685873.3 | 602605.8 | 17.50 | 115.1 | 2.4 | 112.2 | 9.7 | 103.7 | 95 | 5 | Structural Fill | | V5N |
| 1 | SF-24-1 | 8/24/2016 | 685854.9 | 602653.8 | 17.90 | 112.2 | 1.9 | 112.2 | 9.7 | 100.0 | 95 | 5 | Structural Fill | Final Elevation | V5N |
| 1 | CS-56-1 | 8/29/2016 | 685809.2 | 602783.8 | 15.90 | 111.2 | 6.3 | 117 | 8.6 | 95.0 | 90 | 9 | GDL Cover Soil | Moved point to Area 9 | V5N |
| 1 | CS-69-1 | 8/29/2016 | 685642.2 | 603080.6 | 18.90 | 110.3 | 3.9 | 117 | 8.6 | 94.3 | 90 | 10W | GDL Cover Soil | | V5N |
| 1 | CS-73-1 | 8/29/2016 | 685596.9 | 603156.9 | 17.20 | 113.3 | 5.7 | 117 | 8.6 | 96.8 | 90 | 10W | GDL Cover Soil | | V5N |
| 1 | CS-75-1 | 8/29/2016 | 685451.4 | 603140.5 | 10.70 | 119.1 | 5.6 | 117 | 8.6 | 101.8 | 90 | 10 | GDL Cover Soil | Corridor | V5N |
| 1 | DGA-1-1 | 8/29/2016 | 685498.1 | 603803.2 | 9.10 | 129.1 | 1.7 | 135.9 | 9.5 | 95.0 | 95 | MUA | DGA | Driveway | V5N |
| 1 | DGA-2-1 | 8/29/2016 | 685479.7 | 603838.2 | 8.70 | 129.4 | 1.6 | 135.9 | 9.5 | 95.2 | 95 | MUA | DGA | Driveway | V5N |
| 1 | DGA-3-1 | 8/29/2016 | 685462.6 | 603871.9 | 8.40 | 131.0 | 1.5 | 135.9 | 9.5 | 96.4 | 95 | MUA | DGA | Driveway | V5N |
| 1 | HC-23-1 | 8/19/2016 | 685768.3 | 602522.6 | 18.50 | 116.8 | 9.7 | 126 | 9.5 | 92.7 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-28-1 | 8/31/2016 | 685753.3 | 602747.5 | 23.20 | 115.2 | 8.3 | 126 | 9.5 | 91.4 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-29-1 | 8/31/2016 | 685711.3 | 602718.5 | 23.00 | 113.4 | 10.9 | 126 | 9.5 | 90.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 2 | SF-10-2 | 8/29/2016 | 685907.0 | 602542.6 | 16.90 | 115.8 | 0.9 | 112.2 | 9.7 | 103.2 | 95 | 5 | Structural Fill | Final Elevation | V5N |
| 2 | SF-11-2 | 8/29/2016 | 685878.3 | 602607.5 | 17.60 | 116.2 | 1.1 | 112.2 | 9.7 | 103.6 | 95 | 5 | Structural Fill | Final Elevation | V5N |
| 2 | SF-18-2 | 8/29/2016 | 685782.4 | 602413.8 | 18.10 | 119.7 | 0.9 | 112.2 | 9.7 | 106.7 | 95 | 4 | Structural Fill | Final Elevation | V5N |
| 2 | SF-19-2 | 8/29/2016 | 685755.2 | 602456.9 | 18.80 | 118.4 | 0.7 | 112.2 | 9.7 | 105.5 | 95 | 5 | Structural Fill | Final Elevation | V5N |
| 1 | SF-21-1 | 8/29/2016 | 685788.0 | 602599.6 | 17.50 | 112.7 | 1.2 | 112.2 | 9.7 | 100.4 | 95 | 6 | Structural Fill | | V5N |
| 2 | SF-21-2 | 8/29/2016 | 685735.3 | 602583.2 | 18.40 | 117.9 | 1.0 | 112.2 | 9.7 | 105.1 | 95 | 6 | Structural Fill | Final Elevation | V5N |
| 1 | SF-22-1 | 8/29/2016 | 685788.0 | 602599.6 | 16.40 | 115.8 | 1.3 | 112.2 | 9.7 | 103.2 | 95 | 6 | Structural Fill | | V5N |
| 2 | SF-22-2 | 8/29/2016 | 685777.9 | 602614.3 | 17.40 | 113.0 | 1.0 | 112.2 | 9.7 | 100.7 | 95 | 6 | Structural Fill | Final Elevation | V5N |
| 1 | SF-23-1 | 8/29/2016 | 685822.7 | 602629.9 | 16.50 | 111.7 | 1.4 | 112.2 | 9.7 | 99.6 | 95 | 6 | Structural Fill | | V5N |
| 2 | SF-23-2 | 8/29/2016 | 685825.2 | 602646.2 | 17.50 | 121.4 | 1.0 | 112.2 | 9.7 | 108.2 | 95 | 6 | Structural Fill | Final Elevation | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | TEST | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | SF-35-1 | 8/29/2016 | 685689.1 | 602585.9 | 19.30 | 117.3 | 0.9 | 112.2 | 9.7 | 104.5 | 95 | 6 | Structural Fill | | V5N |
| 1 | SF-36-1 | 8/29/2016 | 685656.5 | 602646.9 | 20.20 | 117.3 | 1.6 | 112.2 | 9.7 | 104.5 | 95 | 8 | Structural Fill | Final Elevation | V5N |
| 1 | SF-37-1 | 8/29/2016 | 685618.4 | 602697.5 | 20.70 | 108.6 | 2.7 | 112.2 | 9.7 | 96.8 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 1 | HC-30-1 | 8/31/2016 | 686686.8 | 602719.5 | 22.90 | 125.9 | 8.7 | 126 | 9.5 | 99.9 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-31-1 | 8/31/2016 | 685632.8 | 602740.5 | 20.40 | 123.4 | 10.8 | 126 | 9.5 | 97.9 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-32-1 | 8/31/2016 | 685685.6 | 602764.1 | 23.40 | 113.4 | 7.4 | 126 | 9.5 | 90.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-33-1 | 8/31/2016 | 685727.2 | 602785.9 | 24.00 | 113.4 | 7.8 | 126 | 9.5 | 90.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-34-1 | 8/31/2016 | 685766.6 | 602816.6 | 23.10 | 114.4 | 6.6 | 126 | 9.5 | 90.8 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-35-1 | 8/31/2016 | 685741.4 | 602861.8 | 23.70 | 115.8 | 6.9 | 126 | 9.5 | 91.9 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-36-1 | 8/31/2016 | 685690.7 | 602833.7 | 21.70 | 117.7 | 7.6 | 126 | 9.5 | 93.4 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-37-1 | 8/31/2016 | 685656.1 | 602815.9 | 20.80 | 113.4 | 8.1 | 126 | 9.5 | 90.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-38-1 | 8/31/2016 | 685609.9 | 602779.5 | 20.40 | 115.1 | 9.2 | 126 | 9.5 | 91.3 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-39-1 | 8/31/2016 | 685592.8 | 602825.4 | 20.30 | 118.1 | 10.2 | 126 | 9.5 | 93.7 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-40-1 | 8/31/2016 | 685635.7 | 602852.3 | 20.90 | 116.1 | 9.9 | 126 | 9.5 | 92.1 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-41-1 | 8/31/2016 | 685681.5 | 602878.3 | 21.90 | 121.1 | 8.2 | 126 | 9.5 | 96.1 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-42-1 | 8/31/2016 | 685732.8 | 602895.5 | 20.90 | 117.1 | 7.8 | 126 | 9.5 | 92.9 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-27-1 | 9/1/2016 | 685785.7 | 602767.0 | 22.40 | 115.4 | 8.6 | 126 | 9.5 | 91.6 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-43-1 | 9/2/2016 | 685692.1 | 602950.2 | 21.10 | 127.0 | 9.9 | 126 | 9.5 | 100.8 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 2 | SF-35-2 | 8/31/2016 | 685677.8 | 602581.4 | 19.50 | 110.5 | 0.9 | 112.2 | 9.7 | 98.5 | 95 | 6 | Structural Fill | Final Elevation | V5N |
| 1 | SF-38-1 | 8/31/2016 | 685584.9 | 602752.8 | 20.80 | 110.9 | 1.7 | 112.2 | 9.7 | 98.8 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 1 | SF-39-1 | 8/31/2016 | 685552.4 | 602813.4 | 20.90 | 109.0 | 1.4 | 112.2 | 9.7 | 97.1 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 1 | SF-44-1 | 8/31/2016 | 685384.5 | 603107.9 | 11.70 | 109.1 | 1.7 | 112.2 | 9.7 | 97.2 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | SF-45-1 | 8/31/2016 | 685416.7 | 603122.6 | 11.40 | 114.9 | 2.3 | 112.2 | 9.7 | 102.4 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | SF-46-1 | 8/31/2016 | 685463.1 | 603138.2 | 11.50 | 117.0 | 2.6 | 112.2 | 9.7 | 104.3 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | SF-47-1 | 8/31/2016 | 685499.8 | 603155.4 | 11.80 | 113.5 | 1.5 | 112.2 | 9.7 | 101.2 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | SF-48-1 | 8/31/2016 | 685543.0 | 603169.7 | 12.40 | 122.2 | 1.8 | 112.2 | 9.7 | 108.9 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | SF-49-1 | 8/31/2016 | 685580.7 | 603190.4 | 14.10 | 114.0 | 2.4 | 112.2 | 9.7 | 101.6 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | CS-70-1 | 9/1/2016 | 685518.2 | 603005.1 | 22.20 | 107.7 | 3.9 | 117 | 8.6 | 92.1 | 90 | 10W | GDL Cover Soil | | V5N |
| 1 | CS-71-1 | 9/1/2016 | 685425.6 | 603080.3 | 17.00 | 112.9 | 6.5 | 117 | 8.6 | 96.5 | 90 | 10W | GDL Cover Soil | | V5N |
| 1 | CS-72-1 | 9/1/2016 | 685558.2 | 603808.0 | 21.10 | 106.3 | 4.7 | 117 | 8.6 | 91.3 | 90 | 10W | GDL Cover Soil | | V5N |
| 1 | CS-74-1 | 9/1/2016 | 685553.7 | 603203.7 | 15.60 | 111.6 | 4.5 | 117 | 8.6 | 95.4 | 90 | 11 | GDL Cover Soil | | V5N |
| 1 | CS-76-1 | 9/1/2016 | 685407.5 | 603198.1 | 18.50 | 119.5 | 5.3 | 117 | 8.6 | 102.1 | 90 | 11 | GDL Cover Soil | | V5N |
| 1 | CS-77-1 | 9/1/2016 | 685455.1 | 603251.1 | 15.10 | 113.9 | 4.3 | 117 | 8.6 | 97.3 | 90 | 11 | GDL Cover Soil | | V5N |
| 1 | CS-78-1 | 9/1/2016 | 685525.3 | 603246.0 | 14.70 | 117.4 | 6.8 | 117 | 8.6 | 100.3 | 90 | 11 | GDL Cover Soil | | V5N |
| 1 | HC-44-1 | 9/2/2016 | 685685.5 | 602922.7 | 22.00 | 114.5 | 11.1 | 126 | 9.5 | 90.9 | 90 | 9 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | TEST | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 2 | SF-44-2 | 9/1/2016 | 685376.0 | 603128.1 | 12.90 | 113.7 | 2.3 | 112.2 | 9.7 | 101.3 | 95 | 10 | Structural Fill | Corridor | V5N |
| 2 | SF-45-2 | 9/1/2016 | 685427.3 | 603121.1 | 12.40 | 111.6 | 0.7 | 112.2 | 9.7 | 99.5 | 95 | 10 | Structural Fill | Corridor | V5N |
| 2 | SF-46-2 | 9/1/2016 | 685470.5 | 603140.4 | 12.50 | 112.4 | 2.3 | 112.2 | 9.7 | 100.2 | 95 | 10 | Structural Fill | Corridor | V5N |
| 2 | SF-47-2 | 9/1/2016 | 685511.7 | 603155.8 | 12.90 | 109.0 | 2.8 | 112.2 | 9.7 | 97.1 | 95 | 10 | Structural Fill | Corridor | V5N |
| 3 | SF-47-3 | 9/1/2016 | 685497.9 | 603142.1 | 13.70 | 106.8 | 1.9 | 112.2 | 9.7 | 95.2 | 95 | 10 | Structural Fill | Corridor | V5N |
| 2 | SF-48-2 | 9/1/2016 | 685556.8 | 603171.4 | 13.80 | 115.0 | 2.6 | 112.2 | 9.7 | 102.5 | 95 | 10 | Structural Fill | Corridor | V5N |
| 3 | SF-48-3 | 9/1/2016 | 685539.6 | 603160.2 | 14.50 | 110.6 | 1.7 | 112.2 | 9.7 | 98.6 | 95 | 10 | Structural Fill | Corridor | V5N |
| 2 | SF-49-2 | 9/1/2016 | 685586.0 | 603189.3 | 15.50 | 113.9 | 2.1 | 112.2 | 9.7 | 101.5 | 95 | 10 | Structural Fill | Corridor | V5N |
| 3 | SF-49-3 | 9/1/2016 | 685587.9 | 603182.3 | 16.70 | 110.4 | 2.3 | 112.2 | 9.7 | 98.4 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | HC-45-1 | 9/2/2016 | 685613.1 | 602897.6 | 20.90 | 120.4 | 11.2 | 126 | 9.5 | 95.6 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-46-1 | 9/2/2016 | 685561.8 | 602872.7 | 20.30 | 121.0 | 9.3 | 126 | 9.5 | 96.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-47-1 | 9/9/2016 | 685537.9 | 602916.9 | 20.00 | 118.8 | 8.4 | 126 | 9.5 | 94.3 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-48-1 | 9/9/2016 | 685583.8 | 602941.4 | 20.80 | 113.6 | 7.6 | 126 | 9.5 | 90.2 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 3 | SF-44-3 | 9/2/2016 | 685386.8 | 603098.2 | 13.50 | 114.6 | 1.5 | 112.2 | 9.7 | 102.1 | 95 | 10 | Structural Fill | Corridor | V5N |
| 4 | SF-44-4 | 9/2/2016 | 685379.0 | 603091.5 | 14.30 | 112.2 | 1.4 | 112.2 | 9.7 | 100.0 | 95 | 10 | Structural Fill | Corridor | V5N |
| 3 | SF-45-3 | 9/2/2016 | 685416.0 | 603110.5 | 13.40 | 112.0 | 1.4 | 112.2 | 9.7 | 99.8 | 95 | 10 | Structural Fill | Corridor | V5N |
| 4 | SF-45-4 | 9/2/2016 | 685414.5 | 603134.8 | 14.60 | 117.7 | 2.4 | 112.2 | 9.7 | 104.9 | 95 | 10 | Structural Fill | Corridor | V5N |
| 3 | SF-46-3 | 9/2/2016 | 685468.8 | 603132.3 | 13.60 | 109.4 | 2.3 | 112.2 | 9.7 | 97.5 | 95 | 10 | Structural Fill | Corridor | V5N |
| 4 | SF-46-4 | 9/2/2016 | 685459.8 | 603149.2 | 14.20 | 115.6 | 4.5 | 112.2 | 9.7 | 103.0 | 95 | 10 | Structural Fill | Corridor | V5N |
| 4 | SF-47-4 | 9/2/2016 | 685504.7 | 603162.0 | 15.00 | 111.7 | 1.9 | 112.2 | 9.7 | 99.6 | 95 | 10 | Structural Fill | Corridor | V5N |
| 4 | SF-48-4 | 9/2/2016 | 685553.1 | 603160.5 | 15.90 | 115.6 | 1.9 | 112.2 | 9.7 | 103.0 | 95 | 10 | Structural Fill | Corridor | V5N |
| 4 | SF-49-4 | 9/2/2016 | 685598.7 | 603192.5 | 17.10 | 115.0 | 1.5 | 112.2 | 9.7 | 102.5 | 95 | 10 | Structural Fill | Corridor | V5N |
| 5 | SF-44-5 | 9/6/2016 | 685384.8 | 603100.8 | 15.70 | 112.6 | 1.3 | 112.2 | 9.7 | 100.4 | 95 | 10 | Structural Fill | Corridor | V5N |
| 5 | SF-45-5 | 9/6/2016 | 685421.0 | 603123.8 | 15.50 | 111.2 | 0.6 | 112.2 | 9.7 | 99.1 | 95 | 10 | Structural Fill | Corridor | V5N |
| 5 | SF-46-5 | 9/6/2016 | 685468.8 | 603153.0 | 15.50 | 114.8 | 1.6 | 112.2 | 9.7 | 102.3 | 95 | 10 | Structural Fill | Corridor | V5N |
| 5 | SF-47-5 | 9/6/2016 | 685504.2 | 603163.1 | 16.00 | 112.2 | 2.0 | 112.2 | 9.7 | 100.0 | 95 | 10 | Structural Fill | Corridor | V5N |
| 5 | SF-48-5 | 9/6/2016 | 685545.7 | 603167.0 | 17.00 | 114.0 | 1.0 | 112.2 | 9.7 | 101.6 | 95 | 10 | Structural Fill | Corridor | V5N |
| 5 | SF-49-5 | 9/6/2016 | 685589.2 | 603187.0 | 17.70 | 115.4 | 0.7 | 112.2 | 9.7 | 102.9 | 95 | 10 | Structural Fill | Corridor | V5N |
| 1 | SF-74-1 | 9/6/2016 | 684991.4 | 603626.7 | 10.00 | 110.1 | 2.2 | 112.2 | 9.7 | 98.1 | 95 | 7 | Structural Fill | | V5N |
| 1 | SF-75-1 | 9/6/2016 | 685034.3 | 603648.9 | 9.00 | 115.2 | 1.3 | 112.2 | 9.7 | 102.7 | 95 | 7 | Structural Fill | | V5N |
| 1 | SF-76-1 | 9/6/2016 | 685079.9 | 603671.0 | 8.10 | 116.6 | 1.1 | 112.2 | 9.7 | 103.9 | 95 | 7 | Structural Fill | | V5N |
| 1 | SF-77-1 | 9/6/2016 | 685125.3 | 603689.7 | 7.30 | 112.0 | 1.5 | 112.2 | 9.7 | 99.8 | 95 | 7 | Structural Fill | | V5N |
| 1 | SF-78-1 | 9/6/2016 | 685172.3 | 603710.2 | 7.70 | 108.3 | 1.5 | 112.2 | 9.7 | 96.5 | 95 | 7 | Structural Fill | | V5N |
| 1 | CS-88-1 | 9/9/2016 | 685132.1 | 603471.8 | 12.00 | 112.8 | 12.6 | 117 | 8.6 | 96.4 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-89-1 | 9/9/2016 | 685169.3 | 603521.9 | 13.90 | 110.0 | 12.5 | 117 | 8.6 | 94.0 | 90 | 12 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT | | TEST | LOCATION | | | FIELD DRY | FIELD MOISTURE | PROCTOR MAXIMUM DRY | OPTIMUM MOISTURE | FIELD PERCENT | SPECIFIED PERCENT | | | | TESTING |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | CS-90-1 | 9/9/2016 | 685268.8 | 603557.9 | 7.20 | 125.5 | 5.3 | 117 | 8.6 | 107.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-91-1 | 9/9/2016 | 685224.0 | 603612.4 | 6.10 | 123.9 | 4.4 | 117 | 8.6 | 105.9 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-92-1 | 9/9/2016 | 685120.8 | 603577.5 | 13.30 | 117.7 | 12.5 | 117 | 8.6 | 100.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-93-1 | 9/9/2016 | 685042.5 | 603563.7 | 10.70 | 112.8 | 12.6 | 117 | 8.6 | 96.4 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | HC-49-1 | 9/9/2016 | 685632.4 | 602967.4 | 22.10 | 120.9 | 8.3 | 126 | 9.5 | 96.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-50-1 | 9/9/2016 | 685653.4 | 602989.2 | 21.40 | 114.6 | 7.8 | 126 | 9.5 | 91.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-51-1 | 9/12/2016 | 685642.6 | 603022.5 | 21.10 | 117.7 | 7.3 | 126 | 9.5 | 93.4 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-52-1 | 9/12/2016 | 685608.9 | 603003.9 | 21.90 | 114.8 | 7.7 | 126 | 9.5 | 91.1 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | SF-25-1 | 9/9/2016 | 685816.9 | 602808.8 | 19.70 | 107.9 | 0.7 | 112.2 | 9.7 | 96.2 | 95 | 9 | Structural Fill | | V5N |
| 1 | SF-26-1 | 9/9/2016 | 685807.0 | 602858.9 | 19.90 | 107.2 | 0.9 | 112.2 | 9.7 | 95.5 | 95 | 9 | Structural Fill | | V5N |
| 1 | SF-27-1 | 9/9/2016 | 685764.8 | 602882.0 | 20.30 | 112.2 | 1.0 | 112.2 | 9.7 | 100.0 | 95 | 9 | Structural Fill | | V5N |
| 1 | SF-28-1 | 9/9/2016 | 685759.8 | 602946.2 | 20.90 | 107.7 | 1.0 | 112.2 | 9.7 | 96.0 | 95 | 9 | Structural Fill | | V5N |
| 1 | SF-29-1 | 9/9/2016 | 685724.7 | 602967.2 | 20.90 | 109.8 | 0.7 | 112.2 | 9.7 | 97.9 | 95 | 9 | Structural Fill | | V5N |
| 1 | SF-34-1 | 9/9/2016 | 685609.4 | 603156.3 | 18.80 | 107.3 | 1.4 | 112.2 | 9.7 | 95.6 | 95 | 10 | Structural Fill | Final Elevation | V5N |
| 1 | SF-40-1 | 9/9/2016 | 685511.6 | 602875.5 | 20.20 | 116.1 | 1.3 | 112.2 | 9.7 | 103.5 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 6 | SF-44-6 | 9/9/2016 | 685379.5 | 603113.0 | 16.70 | 119.9 | 1.2 | 112.2 | 9.7 | 106.9 | 95 | 10 | Structural Fill | Corridor - Final Elevation | V5N |
| 6 | SF-45-6 | 9/9/2016 | 685417.8 | 603125.7 | 17.70 | 111.4 | 1.3 | 112.2 | 9.7 | 99.3 | 95 | 10 | Structural Fill | Corridor - Final Elevation | V5N |
| 6 | SF-46-6 | 9/9/2016 | 685459.9 | 603141.3 | 17.20 | 118.2 | 1.2 | 112.2 | 9.7 | 105.3 | 95 | 10 | Structural Fill | Corridor - Final Elevation | V5N |
| 6 | SF-47-6 | 9/9/2016 | 685503.4 | 603156.5 | 17.40 | 111.4 | 1.3 | 112.2 | 9.7 | 99.3 | 95 | 10 | Structural Fill | Corridor - Final Elevation | V5N |
| 6 | SF-48-6 | 9/9/2016 | 685542.9 | 603167.8 | 18.00 | 109.7 | 0.5 | 112.2 | 9.7 | 97.8 | 95 | 10 | Structural Fill | Corridor - Final Elevation | V5N |
| 6 | SF-49-6 | 9/9/2016 | 685585.9 | 603190.5 | 18.10 | 117.2 | 1.1 | 112.2 | 9.7 | 104.5 | 95 | 10 | Structural Fill | Corridor - Final Elevation | V5N |
| 1 | HC-53-1 | 9/12/2016 | 685562.7 | 602969.1 | 20.70 | 113.7 | 5.2 | 126 | 9.5 | 90.2 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-54-1 | 9/12/2016 | 685924.9 | 602941.0 | 20.00 | 118.7 | 7.4 | 126 | 9.5 | 94.2 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-55-1 | 9/12/2016 | 685496.4 | 603002.0 | 22.20 | 121.1 | 7.0 | 126 | 9.5 | 96.1 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-56-1 | 9/12/2016 | 685541.3 | 603022.2 | 20.60 | 117.7 | 6.4 | 126 | 9.5 | 93.4 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-57-1 | 9/12/2016 | 685582.8 | 603050.8 | 23.00 | 117.1 | 7.1 | 126 | 9.5 | 92.9 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-58-1 | 9/12/2016 | 685623.4 | 603079.4 | 19.70 | 118.5 | 7.6 | 126 | 9.5 | 94.0 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-59-1 | 9/12/2016 | 685595.3 | 603109.6 | 18.70 | 113.4 | 7.2 | 126 | 9.5 | 90.0 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-60-1 | 9/12/2016 | 685558.4 | 603089.5 | 21.30 | 114.9 | 10.0 | 126 | 9.5 | 91.2 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-61-1 | 9/12/2016 | 685513.2 | 603080.7 | 21.00 | 120.7 | 9.0 | 126 | 9.5 | 95.8 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-62-1 | 9/12/2016 | 685479.1 | 603082.3 | 20.10 | 115.2 | 9.0 | 126 | 9.5 | 91.4 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-63-1 | 9/12/2016 | 685464.5 | 603107.4 | 16.30 | 127.2 | 8.2 | 126 | 9.5 | 101.0 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-64-1 | 9/12/2016 | 685549.8 | 603137.7 | 17.10 | 119.2 | 9.1 | 126 | 9.5 | 94.6 | 90 | 10W | Horizon C | Back Scatter | V5N |
| 1 | HC-84-1 | 9/16/2016 | 685149.3 | 603473.7 | 12.90 | 140.0 | 6.5 | 126 | 9.5 | 111.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-85-1 | 9/16/2016 | 685181.9 | 603500.3 | 14.50 | 132.8 | 7.4 | 126 | 9.5 | 105.4 | 90 | 12 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | LOCATION ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | SF-31-1 | 9/12/2016 | 685698.8 | 603047.0 | 20.60 | 104.8 | 2.1 | 112.2 | 9.7 | 93.4 | 95 | 10W | Structural Fill | SF-31-1R (Page 10) | V5N |
| 1 | SF-32-1 | 9/12/2016 | 685674.9 | 603084.1 | 20.10 | 114.3 | 2.2 | 112.2 | 9.7 | 101.9 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 1 | SF-33-1 | 9/12/2016 | 685636.1 | 603109.1 | 19.80 | 116.7 | 1.4 | 112.2 | 9.7 | 104.0 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 1 | SF-41-1 | 9/12/2016 | 685488.9 | 602934.6 | 20.10 | 117.4 | 1.3 | 112.2 | 9.7 | 104.6 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 1 | SF-42-1 | 9/12/2016 | 685453.4 | 602993.1 | 18.80 | 113.6 | 1.3 | 112.2 | 9.7 | 101.2 | 95 | 10W | Structural Fill | | V5N |
| 1 | SF-43-1 | 9/12/2016 | 685417.9 | 603050.3 | 18.00 | 120.5 | 1.6 | 112.2 | 9.7 | 107.4 | 95 | 10W | Structural Fill | | V5N |
| 2 | SF-74-2 | 9/12/2016 | 685922.0 | 603639.7 | 11.10 | 107.4 | 1.4 | 112.2 | 9.7 | 95.7 | 95 | 7 | Structural Fill | Final Elevation | V5N |
| 2 | SF-75-2 | 9/12/2016 | 685032.9 | 603647.8 | 10.20 | 111.3 | 1.9 | 112.2 | 9.7 | 99.2 | 95 | 7 | Structural Fill | | V5N |
| 2 | SF-76-2 | 9/12/2016 | 685078.6 | 603666.6 | 9.40 | 107.8 | 1.0 | 112.2 | 9.7 | 96.1 | 95 | 7 | Structural Fill | | V5N |
| 2 | SF-77-2 | 9/12/2016 | 685124.8 | 603686.5 | 8.30 | 122.6 | 0.4 | 112.2 | 9.7 | 109.3 | 95 | 7 | Structural Fill | | V5N |
| 2 | SF-78-2 | 9/12/2016 | 685171.5 | 603702.0 | 8.50 | 120.9 | 1.0 | 112.2 | 9.7 | 107.8 | 95 | 7 | Structural Fill | | V5N |
| 1 | CS-79-1 | 9/14/2016 | 685460.8 | 603320.9 | 12.30 | 108.4 | 4.4 | 117 | 8.6 | 92.6 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-80-1 | 9/14/2016 | 685363.7 | 603260.3 | 14.80 | 112.2 | 4.0 | 117 | 8.6 | 95.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-81-1 | 9/14/2016 | 685314.2 | 603305.3 | 16.60 | 111.4 | 2.4 | 117 | 8.6 | 95.2 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-82-1 | 9/14/2016 | 685340.0 | 603361.1 | 14.60 | 109.4 | 3.6 | 117 | 8.6 | 93.5 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-83-1 | 9/14/2016 | 685428.3 | 603400.0 | 10.40 | 105.4 | 3.7 | 117 | 8.6 | 90.1 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-84-1 | 9/14/2016 | 685372.9 | 603440.9 | 8.70 | 112.6 | 4.6 | 117 | 8.6 | 96.2 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-85-1 | 9/14/2016 | 685225.6 | 603341.5 | 13.50 | 107.2 | 4.5 | 117 | 8.6 | 91.6 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-86-1 | 9/14/2016 | 685194.1 | 603420.0 | 11.10 | 108.7 | 4.3 | 117 | 8.6 | 92.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-87-1 | 9/14/2016 | 685379.7 | 603494.2 | 7.80 | 114.4 | 4.7 | 117 | 8.6 | 97.8 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | SF-30-1 | 9/14/2016 | 685715.6 | 603030.6 | 20.40 | 109.0 | 2.5 | 112.2 | 9.7 | 97.1 | 95 | 9 | Structural Fill | | V5N |
| 1 | HC-86-1 | 9/16/2016 | 685218.9 | 603514.8 | 13.40 | 125.6 | 6.5 | 126 | 9.5 | 99.7 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-87-1 | 9/16/2016 | 685257.0 | 603523.4 | 9.70 | 137.8 | 8.5 | 126 | 9.5 | 109.4 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-88-1 | 9/16/2016 | 685222.5 | 603581.8 | 8.20 | 135.3 | 8.3 | 126 | 9.5 | 107.4 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-89-1 | 9/16/2016 | 685193.5 | 603514.6 | 12.40 | 121.4 | 7.5 | 126 | 9.5 | 96.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-90-1 | 9/16/2016 | 685154.9 | 603541.7 | 14.40 | 130.7 | 8.2 | 126 | 9.5 | 103.7 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-91-1 | 9/16/2016 | 685130.5 | 603507.9 | 15.30 | 126.3 | 6.2 | 126 | 9.5 | 100.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-92-1R | 9/16/2016 | 685103.9 | 603560.3 | 13.90 | 131.2 | 7.8 | 126 | 9.5 | 104.1 | 90 | 12 | Horizon C | Back Scatter; re-test | V5N |
| 1 | HC-93-1 | 9/16/2016 | 685158.5 | 603571.5 | 13.70 | 129.0 | 7.8 | 126 | 9.5 | 102.4 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-94-1 | 9/16/2016 | 685188.9 | 603612.2 | 8.60 | 135.5 | 7.0 | 126 | 9.5 | 107.5 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-95-1 | 9/16/2016 | 685154.8 | 603655.0 | 7.80 | 117.6 | 9.6 | 126 | 9.5 | 93.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-96-1 | 9/16/2016 | 685118.9 | 603631.3 | 9.50 | 113.4 | 9.5 | 126 | 9.5 | 90.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-97-1 | 9/16/2016 | 685068.2 | 603614.3 | 10.00 | 115.0 | 6.3 | 126 | 9.5 | 91.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-65-1 | 9/21/2016 | 685396.8 | 603159.5 | 16.50 | 122.8 | 12.4 | 126 | 9.5 | 97.5 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-66-1 | 9/21/2016 | 685443.4 | 603171.9 | 15.90 | 124.1 | 12.2 | 126 | 9.5 | 98.5 | 90 | 13 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | TEST | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | HC-67-1 | 9/21/2016 | 685504.6 | 603210.9 | 18.70 | 130.8 | 13.2 | 126 | 9.5 | 103.8 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | SF-61-1 | 9/16/2016 | 685187.4 | 603409.9 | 12.30 | 115.1 | 1.1 | 112.2 | 9.7 | 102.6 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-62-1 | 9/16/2016 | 685220.9 | 603427.0 | 11.50 | 114.8 | 1.8 | 112.2 | 9.7 | 102.3 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-63-1 | 9/16/2016 | 685258.9 | 603458.9 | 9.70 | 116.0 | 1.8 | 112.2 | 9.7 | 103.4 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-64-1 | 9/16/2016 | 685298.0 | 603490.9 | 9.00 | 117.8 | 1.0 | 112.2 | 9.7 | 105.0 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-65-1 | 9/16/2016 | 685327.5 | 603571.4 | 8.70 | 118.9 | 1.4 | 112.2 | 9.7 | 106.0 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-66-1 | 9/16/2016 | 685294.2 | 603549.0 | 8.50 | 115.0 | 1.4 | 112.2 | 9.7 | 102.5 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-67-1 | 9/16/2016 | 685264.5 | 603588.1 | 7.50 | 114.9 | 1.3 | 112.2 | 9.7 | 102.4 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 1 | SF-68-1 | 9/16/2016 | 685234.2 | 603626.7 | 7.10 | 120.5 | 1.7 | 112.2 | 9.7 | 107.4 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-69-1 | 9/16/2016 | 685202.1 | 603666.6 | 7.40 | 115.5 | 1.5 | 112.2 | 9.7 | 102.9 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-70-1 | 9/16/2016 | 685149.2 | 603437.2 | 13.00 | 117.3 | 1.1 | 112.2 | 9.7 | 104.5 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-71-1 | 9/16/2016 | 685105.7 | 603488.2 | 12.90 | 117.5 | 1.1 | 112.2 | 9.7 | 104.7 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-72-1 | 9/16/2016 | 685061.4 | 603541.1 | 12.10 | 119.4 | 1.5 | 112.2 | 9.7 | 106.4 | 95 | 12 | Structural Fill | | V5N |
| 1 | SF-73-1 | 9/16/2016 | 685019.3 | 603590.9 | 11.10 | 109.6 | 1.5 | 112.2 | 9.7 | 97.7 | 95 | 12 | Structural Fill | | V5N |
| 3 | SF-75-3 | 9/16/2016 | 685048.3 | 603631.9 | 10.80 | 112.4 | 1.1 | 112.2 | 9.7 | 100.2 | 95 | 7 | Structural Fill | Final Elevation | V5N |
| 1 | HC-68-1 | 9/21/2016 | 685468.1 | 603245.9 | 15.60 | 126.8 | 12.5 | 126 | 9.5 | 100.6 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-69-1 | 9/21/2016 | 685415.3 | 603236.1 | 18.50 | 120.0 | 11.5 | 126 | 9.5 | 95.2 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-70-1 | 9/21/2016 | 685377.4 | 603205.9 | 19.00 | 120.2 | 12.5 | 126 | 9.5 | 95.4 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-71-1 | 9/21/2016 | 685343.8 | 603244.9 | 15.80 | 136.7 | 11.6 | 126 | 9.5 | 108.5 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-72-1 | 9/21/2016 | 685385.8 | 603275.1 | 15.00 | 125.8 | 12.5 | 126 | 9.5 | 99.8 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-73-1 | 9/21/2016 | 685455.7 | 603281.1 | 14.80 | 125.9 | 12.7 | 126 | 9.5 | 99.9 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-74-1 | 9/21/2016 | 685420.3 | 603319.5 | 13.60 | 133.3 | 13.8 | 126 | 9.5 | 105.8 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-75-1 | 9/21/2016 | 685356.5 | 603338.7 | 15.60 | 118.7 | 9.8 | 126 | 9.5 | 94.2 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-76-1 | 9/21/2016 | 685317.1 | 603293.5 | 17.40 | 114.0 | 10.5 | 126 | 9.5 | 90.5 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-77-1 | 9/21/2016 | 685280.8 | 603340.2 | 16.70 | 120.3 | 8.9 | 126 | 9.5 | 95.5 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-78-1 | 9/21/2016 | 685319.9 | 603353.4 | 15.80 | 128.0 | 8.9 | 126 | 9.5 | 101.6 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-79-1 | 9/21/2016 | 685392.9 | 603361.5 | 14.80 | 113.6 | 11.0 | 126 | 9.5 | 90.2 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-80-1 | 9/21/2016 | 685366.5 | 603390.4 | 14.10 | 113.4 | 11.0 | 126 | 9.5 | 90.0 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-81-1 | 9/21/2016 | 685330.2 | 603424.2 | 18.60 | 114.0 | 9.9 | 126 | 9.5 | 90.5 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-82-1 | 9/21/2016 | 685315.5 | 603390.5 | 14.90 | 118.9 | 9.6 | 126 | 9.5 | 94.4 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-83-1 | 9/21/2016 | 685251.5 | 603374.3 | 16.20 | 117.5 | 9.2 | 126 | 9.5 | 93.3 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-20-1 | 8/11/2016 | 685874.8 | 602528.7 | 19.50 | 117.0 | 5.2 | 126 | 9.5 | 92.9 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-21-1 | 8/19/2016 | 685852.9 | 602578.1 | 17.60 | 117.1 | 9.1 | 126 | 9.5 | 92.9 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-22-1 | 8/19/2016 | 685815.3 | 602550.0 | 20.10 | 118.5 | 8.9 | 126 | 9.5 | 94.0 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 2 | SF-25-2 | 9/21/2016 | 685815.2 | 602802.2 | 20.30 | 107.3 | 1.2 | 112.2 | 9.7 | 95.6 | 95 | 9 | Structural Fill | Final Elevation | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | LOCATION ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | SF-26-2 | 9/21/2016 | 685805.7 | 602859.6 | 20.20 | 109.0 | 1.2 | 112.2 | 9.7 | 97.1 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 2 | SF-27-2 | 9/21/2016 | 685764.4 | 602879.3 | 21.60 | 111.9 | 1.1 | 112.2 | 9.7 | 99.7 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 2 | SF-28-2 | 9/21/2016 | 685759.9 | 602945.9 | 21.30 | 105.1 | 0.9 | 112.2 | 9.7 | 93.7 | 95 | 9 | Structural Fill | SF-28-2R (Page 10) | V5N |
| 1 | SF-31-1R | 9/21/2016 | 685674.0 | 603030.0 | 20.60 | 106.6 | 1.9 | 112.2 | 9.7 | 95.0 | 95 | 10W | Structural Fill | Re-test from 9/12/16 | V5N |
| 1 | SF-50-1 | 9/21/2016 | 685544.9 | 603236.4 | 16.10 | 116.3 | 3.7 | 112.2 | 9.7 | 103.7 | 95 | 11 | Structural Fill | | V5N |
| 1 | SF-51-1 | 9/21/2016 | 685512.5 | 603275.8 | 14.90 | 109.0 | 2.7 | 112.2 | 9.7 | 97.1 | 95 | 11 | Structural Fill | | V5N |
| 1 | SF-52-1 | 9/21/2016 | 685474.8 | 603320.8 | 13.50 | 111.2 | 2.0 | 112.2 | 9.7 | 99.1 | 95 | 13 | Structural Fill | | V5N |
| 1 | SF-53-1 | 9/21/2016 | 685451.1 | 603352.7 | 12.30 | 112.6 | 2.5 | 112.2 | 9.7 | 100.4 | 95 | 13 | Structural Fill | | V5N |
| 1 | SF-54-1 | 9/21/2016 | 685418.6 | 603393.2 | 11.20 | 112.2 | 1.8 | 112.2 | 9.7 | 100.0 | 95 | 13 | Structural Fill | | V5N |
| 1 | SF-55-1 | 9/21/2016 | 685388.8 | 603432.7 | 10.00 | 116.4 | 1.2 | 112.2 | 9.7 | 103.7 | 95 | 13 | Structural Fill | | V5N |
| 1 | SF-56-1 | 9/21/2016 | 685357.4 | 603473.3 | 9.20 | 109.9 | 1.1 | 112.2 | 9.7 | 98.0 | 95 | 13 | Structural Fill | | V5N |
| 1 | SF-57-1 | 9/21/2016 | 685345.4 | 603162.0 | 16.80 | 109.2 | 2.7 | 112.2 | 9.7 | 97.3 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 1 | SF-58-1 | 9/21/2016 | 685313.8 | 603223.0 | 16.40 | 108.7 | 1.7 | 112.2 | 9.7 | 96.9 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 1 | SF-59-1 | 9/21/2016 | 685280.5 | 603280.7 | 15.70 | 117.8 | 1.6 | 112.2 | 9.7 | 105.0 | 95 | 11 | Structural Fill | Final Elevation | V5N |
| 1 | SF-60-1 | 9/21/2016 | 685237.1 | 603333.1 | 15.10 | 110.0 | 1.6 | 112.2 | 9.7 | 98.0 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-65-2 | 9/21/2016 | 685327.5 | 603511.4 | 9.50 | 106.2 | 1.2 | 112.2 | 9.7 | 94.7 | 95 | 12 | Structural Fill | SF-65-2R (Page 11) | V5N |
| 2 | SF-67-2 | 9/21/2016 | 685261.2 | 603594.2 | 8.50 | 110.8 | 1.4 | 112.2 | 9.7 | 98.8 | 95 | 12 | Structural Fill | | V5N |
| 2 | SF-68-2 | 9/21/2016 | 685235.2 | 603625.3 | 8.10 | 106.6 | 1.3 | 112.2 | 9.7 | 95.0 | 95 | 12 | Structural Fill | | V5N |
| 2 | SF-69-2 | 9/21/2016 | 685200.6 | 603661.2 | 8.40 | 111.1 | 2.1 | 112.2 | 9.7 | 99.0 | 95 | 12 | Structural Fill | | V5N |
| 3 | SF-76-3 | 9/21/2016 | 685079.7 | 603667.9 | 10.20 | 113.9 | 1.4 | 112.2 | 9.7 | 101.5 | 95 | 7 | Structural Fill | Final Elevation | V5N |
| 3 | SF-77-3 | 9/21/2016 | 685126.3 | 603688.7 | 9.30 | 115.5 | 1.4 | 112.2 | 9.7 | 102.9 | 95 | 7 | Structural Fill | Final Elevation | V5N |
| 3 | SF-78-3 | 9/21/2016 | 685171.1 | 603708.0 | 9.80 | 107.5 | 2.0 | 112.2 | 9.7 | 95.8 | 95 | 7 | Structural Fill | Final Elevation | V5N |
| 2 | SF-28-2R | 9/28/2016 | 685759.9 | 602945.9 | 21.30 | 110.0 | 1.3 | 112.2 | 9.7 | 98.0 | 95 | 9 | Structural Fill | Re-test from 9/21/16 | V5N |
| 2 | SF-29-2 | 9/28/2016 | 685724.2 | 602963.6 | 22.10 | 116.1 | 1.4 | 112.2 | 9.7 | 103.5 | 95 | 9 | Structural Fill | Final Elevation | V5N |
| 2 | SF-30-2 | 9/28/2016 | 685721.9 | 603032.1 | 20.80 | 108.6 | 1.0 | 112.2 | 9.7 | 96.8 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 2 | SF-31-2 | 9/28/2016 | 685681.0 | 603029.6 | 21.10 | 107.2 | 1.3 | 112.2 | 9.7 | 95.5 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 2 | SF-42-2 | 9/28/2016 | 685452.8 | 602991.9 | 19.50 | 110.7 | 2.8 | 112.2 | 9.7 | 98.7 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 2 | SF-43-2 | 9/28/2016 | 685420.1 | 603045.0 | 18.80 | 107.3 | 2.4 | 112.2 | 9.7 | 95.6 | 95 | 10W | Structural Fill | Final Elevation | V5N |
| 2 | SF-50-2 | 9/28/2016 | 685545.7 | 603239.7 | 17.30 | 116.2 | 2.0 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill | Final Elevation | V5N |
| 2 | SF-51-2 | 9/28/2016 | 685573.3 | 603275.6 | 15.50 | 111.4 | 1.3 | 112.2 | 9.7 | 99.3 | 95 | 11 | Structural Fill | Final Elevation | V5N |
| 2 | SF-52-2 | 9/28/2016 | 685477.1 | 603319.6 | 14.10 | 114.7 | 1.5 | 112.2 | 9.7 | 102.2 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-53-2 | 9/28/2016 | 685450.4 | 603352.9 | 13.10 | 113.3 | 1.6 | 112.2 | 9.7 | 101.0 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-54-2 | 9/28/2016 | 685422.3 | 603390.4 | 12.00 | 114.2 | 1.2 | 112.2 | 9.7 | 101.8 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-55-2 | 9/28/2016 | 685390.8 | 603429.9 | 10.80 | 115.1 | 1.0 | 112.2 | 9.7 | 102.6 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-56-2 | 9/28/2016 | 685358.3 | 603469.2 | 10.00 | 120.1 | 1.1 | 112.2 | 9.7 | 107.0 | 95 | 13 | Structural Fill | Final Elevation | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 NORTH CAP**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**


| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | LOCATION ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | SF-61-2 | 9/28/2016 | 685193.4 | 603386.6 | 13.30 | 122.8 | 2.2 | 112.2 | 9.7 | 109.4 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-62-2 | 9/28/2016 | 685223.2 | 603428.2 | 12.50 | 110.4 | 1.0 | 112.2 | 9.7 | 98.4 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-63-2 | 9/28/2016 | 685259.7 | 603460.0 | 11.10 | 113.6 | 1.4 | 112.2 | 9.7 | 101.2 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-64-2 | 9/28/2016 | 685299.4 | 603486.9 | 9.80 | 114.6 | 1.6 | 112.2 | 9.7 | 102.1 | 95 | 13 | Structural Fill | Final Elevation | V5N |
| 2 | SF-65-2R | 9/28/2016 | 685327.5 | 603511.4 | 9.50 | 119.8 | 1.1 | 112.2 | 9.7 | 106.8 | 95 | 13 | Structural Fill | Re-test from 9/21 | V5N |
| 2 | SF-66-2 | 9/28/2016 | 685298.5 | 603550.4 | 9.50 | 118.1 | 1.2 | 112.2 | 9.7 | 105.3 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 3 | SF-67-3 | 9/28/2016 | 685263.1 | 603589.9 | 9.50 | 113.2 | 1.1 | 112.2 | 9.7 | 100.9 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 3 | SF-68-3 | 9/28/2016 | 685233.3 | 603627.8 | 9.40 | 112.8 | 1.4 | 112.2 | 9.7 | 100.5 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 3 | SF-69-3 | 9/28/2016 | 685201.4 | 603664.6 | 9.60 | 113.8 | 1.6 | 112.2 | 9.7 | 101.4 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 2 | SF-70-2 | 9/28/2016 | 685149.5 | 603436.1 | 14.00 | 116.6 | 1.2 | 112.2 | 9.7 | 103.9 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 2 | SF-71-2 | 9/28/2016 | 685102.8 | 603489.6 | 13.40 | 111.7 | 1.4 | 112.2 | 9.7 | 99.6 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 2 | SF-72-2 | 9/28/2016 | 685058.3 | 603539.5 | 12.90 | 110.4 | 1.8 | 112.2 | 9.7 | 98.4 | 95 | 12 | Structural Fill | Final Elevation | V5N |
| 2 | SF-73-2 | 9/28/2016 | 685017.1 | 603590.8 | 12.20 | 111.8 | 1.2 | 112.2 | 9.7 | 99.6 | 95 | 12 | Structural Fill | Final Elevation | V5N |

R = Will be placed after sample ID if the test location is reworked and the compaction test is run again

## 2.0 Test Location Drawings

- **GDL Cover Soil (Initial and Reduced Frequency)**
- **Horizon C**
- **Structural Fill**

# SA-6 NORTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION ⊕CS-XX

GDL COVER SOIL ELEVATION CONTOURS


ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

DRAWING NAME: GDL COVER SOIL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | T. COLLIER | APPROVED BY | | | |
| DATE | 7/12/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 NORTH




NOTES:

1) Testing locations are based on testing frequency specified by approval of RFI-076

LEGEND:

COMPACTION TEST LOCATION ⊕CS-XX

GDL COVER SOIL ELEVATION CONTOURS

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

DRAWING NAME: GDL COVER SOIL REDUCED FREQUENCY COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | T. COLLIER | APPROVED BY | | | |
| DATE | 8/18/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 NORTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:


COMPACTION TEST LOCATION HC-XX

STRUCTURAL FILL LIMITS

ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102

| | | | | | |
|---|---|---|---|---|---|
| DRAWING NAME | HORIZON C COMPACTION LOCATIONS | | | | |
| PROJECT NAME & LOCATION | HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ | | | | |
| DRAWN BY | T. COLLIER | APPROVED BY | | | |
| DATE | 7/15/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 NORTH



NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION — SF-XX

STRUCTURAL FILL LIMITS

| | |
|---|---|
| ENTACT | 302 Unity Plaza<br>Latrobe, PA 15650<br>412-357-1102 |
| DRAWING NAME | STRUCTURAL FILL COMPACTION LOCATIONS |
| PROJECT NAME & LOCATION | HONEYWELL SA-6 REMEDIATION<br>JERSEY CITY, NJ |

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | T. COLLIER | APPROVED BY | | | |
| DATE | 7/15/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# 1.0 Field Density Test Summary Log

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-03-1 | 10/20/2015 | 685534.39 | 601506.6 | 17.45 | 114.3 | 3.3 | 117 | 8.6 | 97.7 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-04-1 | 10/20/2015 | 685573.6 | 601571 | 18.25 | 118 | 4.1 | 117 | 8.6 | 100.9 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-05-1 | 10/20/2015 | 685530.6 | 601543.8 | 17.84 | 116.6 | 6.4 | 117 | 8.6 | 99.7 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-06-1 | 10/20/2015 | 685488.8 | 601532.7 | 14.72 | 118.6 | 7.1 | 117 | 8.6 | 101.4 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-07-1 | 10/20/2015 | 685512.5 | 601575.8 | 17.71 | 115 | 5.9 | 117 | 8.6 | 98.3 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-08-1 | 10/20/2015 | 685536.3 | 601610.7 | 17.61 | 117.3 | 5.4 | 117 | 8.6 | 100.3 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-09-1 | 10/20/2015 | 685492.5 | 601601.9 | 16.43 | 122.4 | 3.7 | 117 | 8.6 | 104.6 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-10-1 | 10/20/2015 | 685448.8 | 601585.8 | 14.79 | 114.5 | 5.6 | 117 | 8.6 | 97.9 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-11-1 | 10/20/2015 | 685477.6 | 601634.6 | 17.08 | 122.2 | 5.8 | 117 | 8.6 | 104.4 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-12-1 | 10/20/2015 | 685503.5 | 601668.8 | 17.32 | 115.3 | 5.9 | 117 | 8.6 | 98.5 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-13-1 | 10/20/2015 | 685462.1 | 601659.8 | 16.59 | 115.5 | 4.5 | 117 | 8.6 | 98.7 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-14-1 | 10/20/2015 | 685423.8 | 601646.8 | 14.54 | 117.9 | 3.2 | 117 | 8.6 | 100.8 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-15-1 | 10/20/2015 | 685444.3 | 601687.7 | 14.73 | 114.8 | 5 | 117 | 8.6 | 98.1 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-16-1 | 10/20/2015 | 685460.2 | 601724.9 | 16.34 | 115.8 | 4 | 117 | 8.6 | 99.0 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-17-1 | 10/20/2015 | 685433.8 | 601722.1 | 14.62 | 113.7 | 7.3 | 117 | 8.6 | 97.2 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-18-1 | 10/20/2015 | 685394.4 | 601715.0 | 17.21 | 118.9 | 3.4 | 117 | 8.6 | 101.6 | 90 | 1 | GDL Cover Soil | | V5N |
| 1 | CS-129-1 | 11/4/2015 | 684281.4 | 603180.2 | 8.75 | 120.2 | 8.0 | 117 | 8.6 | 102.7 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-130-1 | 11/4/2015 | 684216.2 | 603153.2 | 8.83 | 113.6 | 6.7 | 117 | 8.6 | 97.1 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-131-1 | 11/4/2015 | 684261.4 | 603206.7 | 8.42 | 114.1 | 10.9 | 117 | 8.6 | 97.5 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-132-1 | 11/4/2015 | 684292.4 | 603250.5 | 9.53 | 118.3 | 6.2 | 117 | 8.6 | 101.1 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-133-1 | 11/4/2015 | 684236.5 | 603231.2 | 8.64 | 111.6 | 8.1 | 117 | 8.6 | 95.4 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-134-1 | 11/4/2015 | 684175.3 | 603214.9 | 8.57 | 122.5 | 7.7 | 117 | 8.6 | 104.7 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-135-1 | 11/4/2015 | 684215.0 | 603254.8 | 8.32 | 118.4 | 6.6 | 117 | 8.6 | 101.2 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-136-1 | 11/4/2015 | 684251.9 | 603305.8 | 8.40 | 115.1 | 8.8 | 117 | 8.6 | 98.4 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-137-1 | 11/4/2015 | 684189.5 | 603274.7 | 7.64 | 116.9 | 9.3 | 117 | 8.6 | 99.9 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-138-1 | 11/4/2015 | 684143.3 | 603253.5 | 7.36 | 117.9 | 10.5 | 117 | 8.6 | 100.8 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | CS-125-1 | 11/6/2015 | 684314.5 | 603125.9 | 7.68 | 111.2 | 8.2 | 117 | 8.6 | 95.0 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-126-1 | 11/6/2015 | 684270.3 | 603123.5 | 7.05 | 120.0 | 9.7 | 117 | 8.6 | 102.6 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-127-1 | 11/6/2015 | 684305.4 | 603158.0 | 7.55 | 115.7 | 7.6 | 117 | 8.6 | 98.9 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-128-1 | 11/6/2015 | 684334.4 | 603202.5 | 7.75 | 117.7 | 7.4 | 117 | 8.6 | 100.6 | 90 | 2 | GDL Cover Soil | | V5N |
| 1 | SF-17-1 | 11/6/2015 | 684184.8 | 603260.8 | 8.67 | 126.8 | 5.4 | 133 | 8.6 | 95.3 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | SF-18-1 | 11/6/2015 | 684230.8 | 603283.7 | 9.16 | 127.2 | 5.9 | 133 | 8.6 | 95.6 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | CS-117-1 | 11/10/2015 | 684405.2 | 603020.3 | 11.64 | 111.0 | 5.2 | 117 | 8.6 | 94.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-118-1 | 11/10/2015 | 684350.5 | 603002.3 | 9.66 | 115.2 | 7.3 | 117 | 8.6 | 98.5 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-119-1 | 11/10/2015 | 684384.6 | 603051.2 | 10.55 | 116.0 | 6.3 | 117 | 8.6 | 99.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-120-1 | 11/10/2015 | 684422.3 | 603088.8 | 11.72 | 115.7 | 6.6 | 117 | 8.6 | 98.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-122-1 | 11/10/2015 | 684307.2 | 603059.7 | 8.50 | 116.8 | 7.5 | 117 | 8.6 | 99.8 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-110-1 | 11/11/2015 | 684445.1 | 602994.4 | 13.50 | 115.5 | 9.7 | 117 | 8.6 | 98.7 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-111-1 | 11/11/2015 | 684477.2 | 602955.6 | 15.83 | 125.3 | 9.0 | 117 | 8.6 | 107.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-112-1 | 11/11/2015 | 684507.0 | 602999.4 | 16.21 | 122.7 | 9.0 | 117 | 8.6 | 104.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-113-1 | 11/11/2015 | 684455.2 | 602974.1 | 14.56 | 118.0 | 9.0 | 117 | 8.6 | 100.9 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-114-1 | 11/11/2015 | 684396.7 | 602954.9 | 12.21 | 120.6 | 10.0 | 117 | 8.6 | 103.1 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-115-1 | 11/11/2015 | 684426.7 | 603002.4 | 12.86 | 118.5 | 8.4 | 117 | 8.6 | 101.3 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-116-1 | 11/11/2015 | 684459.1 | 603046.2 | 13.60 | 122.3 | 8.1 | 117 | 8.6 | 104.5 | 90 | 4 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-121-1 | 11/11/2015 | 684364.2 | 603084.9 | 9.73 | 121.3 | 9.3 | 117 | 8.6 | 103.7 | 90 | 4 | GDL Cover Soil | | V5N |
| 1 | CS-123-1 | 11/11/2015 | 684344.5 | 603105.3 | 9.51 | 119.7 | 10.3 | 117 | 8.6 | 102.3 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | CS-124-1 | 11/11/2015 | 684370.5 | 603148.7 | 9.80 | 116.4 | 11.3 | 117 | 8.6 | 99.5 | 90 | 3 | GDL Cover Soil | | V5N |
| 1 | SF-15-1 | 11/11/2015 | 684280.3 | 603136.7 | 7.80 | 131.4 | 7.0 | 133 | 8.6 | 98.8 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-15-2 | 11/11/2015 | 684279.3 | 603138.5 | 9.15 | 129.9 | 6.8 | 133 | 8.6 | 97.7 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 3 | SF-15-3 | 11/11/2015 | 684271.2 | 603129.6 | 9.64 | 132.5 | 3.3 | 133 | 8.6 | 99.6 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 1 | SF-16-1 | 11/11/2015 | 684316.8 | 603171.2 | 8.29 | 133.6 | 6.8 | 133 | 8.6 | 100.5 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-16-2 | 11/11/2015 | 684319.3 | 603178.5 | 9.48 | 133.6 | 5.4 | 133 | 8.6 | 100.5 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 3 | SF-16-3 | 11/11/2015 | 684314.6 | 603172.8 | 10.70 | 135.6 | 5.0 | 133 | 8.6 | 102.0 | 95 | 3 | Structural Fill -Liberty | | V5N |
| 2 | SF-17-2 | 11/11/2015 | 684184.9 | 603258.9 | 9.56 | 126.4 | 6.7 | 133 | 8.6 | 95.0 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 2 | SF-18-2 | 11/11/2015 | 684234.3 | 603282.9 | 9.71 | 133.9 | 6.3 | 133 | 8.6 | 100.7 | 95 | 2 | Structural Fill -Liberty | East Side | V5N |
| 1 | HC-10-1 | 11/13/2015 | 685444.5 | 601588.5 | 15.22 | 114.6 | 9.5 | 126 | 9.5 | 91.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-11-1 | 11/13/2015 | 685477.6 | 601635.1 | 17.64 | 122.2 | 9.7 | 126 | 9.5 | 97.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-128-1 | 11/13/2015 | 684307.4 | 603209.5 | 9.94 | 114.5 | 10.8 | 126 | 9.5 | 90.9 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-129-1 | 11/13/2015 | 684280.0 | 603181.7 | 9.33 | 110.0 | 10.2 | 126 | 9.5 | 87.3 | 90 | 2 | Horizon C | SF-129-1R (Page 2) | V5N |
| 1 | HC-13-1 | 11/13/2015 | 685461.4 | 601657.1 | 17.20 | 122.5 | 9.3 | 126 | 9.5 | 97.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-131-1 | 11/13/2015 | 684261.3 | 603208.3 | 8.99 | 119.8 | 10.7 | 126 | 9.5 | 95.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-130-1 | 11/13/2015 | 684238.9 | 603170.2 | 9.33 | 121.4 | 10.6 | 126 | 9.5 | 96.3 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-132-1 | 11/13/2015 | 684294.6 | 603252.5 | 10.11 | 114.6 | 13.1 | 126 | 9.5 | 91.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-133-1 | 11/13/2015 | 684236.1 | 603230.2 | 9.14 | 124.7 | 11.3 | 126 | 9.5 | 99.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-134-1 | 11/13/2015 | 684173.7 | 603204.1 | 9.17 | 120.2 | 11 | 126 | 9.5 | 95.4 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-135-1 | 11/13/2015 | 684223.3 | 603252.6 | 8.92 | 120 | 11.5 | 126 | 9.5 | 95.2 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-136-1 | 11/13/2015 | 684264.7 | 603275 | 9.06 | 128.5 | 10.45 | 126 | 9.5 | 102.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-137-1 | 11/13/2015 | 684206.1 | 603237.7 | 9.16 | 118.4 | 10.5 | 126 | 9.5 | 94.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-138-1 | 11/13/2015 | 684160.6 | 603231.8 | 7.70 | 110.2 | 12.4 | 126 | 9.5 | 87.5 | 90 | 2 | Horizon C | SF-138-1R (Page 2) | V5N |
| 1 | HC-14-1 | 11/13/2015 | 685422.6 | 601647.6 | 15.13 | 117.4 | 9.9 | 126 | 9.5 | 93.2 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-15-1 | 11/13/2015 | 684443.2 | 601689.6 | 15.42 | 117.3 | 9.9 | 126 | 9.5 | 93.1 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | CS-106-1 | 11/17/2015 | 684477.6 | 602852.8 | 7.70 | 117.5 | 8.0 | 117 | 8.6 | 100.4 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-107-1 | 11/17/2015 | 684525.2 | 602897.0 | 7.36 | 108.0 | 4.3 | 117 | 8.6 | 92.3 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-108-1 | 11/17/2015 | 684553.4 | 602948.7 | 15.71 | 123.4 | 7.5 | 117 | 8.6 | 105.5 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | CS-109-1 | 11/17/2015 | 684499.0 | 602921.5 | 14.74 | 119.4 | 5.9 | 117 | 8.6 | 102.1 | 90 | 5 | GDL Cover Soil | | V5N |
| 1 | HC-118-1 | 11/17/2015 | 684353.8 | 603000.7 | 10.34 | 113.6 | 11.1 | 126 | 9.5 | 90.2 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-119-1 | 11/17/2015 | 684385.6 | 603051.8 | 11.10 | 120.1 | 12.4 | 126 | 9.5 | 95.3 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-120-1 | 11/17/2015 | 684417.3 | 603086.2 | 12.07 | 128.7 | 10.9 | 126 | 9.5 | 102.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-121-1 | 11/17/2015 | 684363.8 | 603008.5 | 10.29 | 116.5 | 8.3 | 126 | 9.5 | 92.5 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-122-1 | 11/17/2015 | 684319.6 | 603062.6 | 9.47 | 115.4 | 10.1 | 126 | 9.5 | 91.6 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-123-1 | 11/17/2015 | 684343.7 | 603110.5 | 10.08 | 122.0 | 12.0 | 126 | 9.5 | 96.8 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-124-1 | 11/17/2015 | 684373.8 | 603148.2 | 10.36 | 116.8 | 9.5 | 126 | 9.5 | 92.7 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-125-1 | 11/17/2015 | 684322.9 | 603123.8 | 9.85 | 113.4 | 11.3 | 126 | 9.5 | 90.0 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-126-1 | 11/17/2015 | 684294.5 | 603104.5 | 9.33 | 113.7 | 9.7 | 126 | 9.5 | 90.2 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-127-1 | 11/17/2015 | 684344.3 | 603150.7 | 10.16 | 118.9 | 11.6 | 126 | 9.5 | 94.4 | 90 | 3 | Horizon C | Back Scatter | V5N |
| 1 | HC-129-1R | 11/17/2015 | 684276.4 | 603183.7 | 9.24 | 113.4 | 9.2 | 126 | 9.5 | 90.0 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-138-1R | 11/17/2015 | 684162.8 | 603230.4 | 7.91 | 114.8 | 10.3 | 126 | 9.5 | 91.1 | 90 | 2 | Horizon C | Back Scatter | V5N |
| 1 | HC-108-1 | 11/19/2015 | 684536.2 | 902967.2 | 18.62 | 113.4 | 10.0 | 126 | 9.5 | 90.0 | 90 | 5 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | HC-109-1 | 11/19/2015 | 684492.9 | 602930.4 | 18.27 | 127.2 | 10.0 | 126 | 9.5 | 101.0 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-110-1 | 11/19/2015 | 684449.3 | 602900.5 | 14.40 | 115.7 | 10.0 | 126 | 9.5 | 91.8 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-111-1 | 11/19/2015 | 684475.6 | 602955.2 | 16.38 | 118.6 | 11.3 | 126 | 9.5 | 94.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-112-1 | 11/19/2015 | 684507.3 | 602998.5 | 16.87 | 119.2 | 9.9 | 126 | 9.5 | 94.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-113-1 | 11/19/2015 | 684452.2 | 602978.3 | 14.98 | 121.1 | 12.1 | 126 | 9.5 | 96.1 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-114-1 | 11/19/2015 | 684397.7 | 602956.1 | 12.85 | 121.5 | 10.7 | 126 | 9.5 | 96.4 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-115-1 | 11/19/2015 | 684428.1 | 603001.7 | 13.53 | 125.5 | 9.9 | 126 | 9.5 | 99.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-116-1 | 11/19/2015 | 684461.4 | 603048.2 | 14.24 | 115.4 | 9.9 | 126 | 9.5 | 91.6 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | HC-117-1 | 11/19/2015 | 684402.1 | 603019.3 | 12.08 | 121.6 | 10.5 | 126 | 9.5 | 96.5 | 90 | 4 | Horizon C | Back Scatter | V5N |
| 1 | SF-12-1 | 11/19/2015 | 684485.9 | 602888.7 | 15.10 | 129.8 | 3.5 | 133 | 8.6 | 97.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-13-1 | 11/19/2015 | 684515.4 | 602913.9 | 15.90 | 129.9 | 4.3 | 133 | 8.6 | 97.7 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 1 | SF-14-1 | 11/19/2015 | 684548.8 | 602937.5 | 16.40 | 125.4 | 3.5 | 133 | 8.6 | 94.3 | 95 | 5 | Structural Fill -Liberty | SF-14-1R (Page 3) | V5N |
| 1 | SF-14-1R | 11/19/2015 | 684548.8 | 602937.5 | 16.40 | 127.3 | 3.5 | 133 | 8.6 | 95.7 | 95 | 5 | Structural Fill -Liberty | Re-roll/re-test; D Street-shallow | V5N |
| 1 | SF-19-1 | 11/19/2015 | 684505.8 | 602882.5 | 8.54 | 129.3 | 3.3 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-19-2 | 11/19/2015 | 684507.6 | 602881.4 | 9.70 | 126.4 | 4.4 | 133 | 8.6 | 95.0 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 3 | SF-19-3 | 11/19/2015 | 684507.5 | 602880.7 | 10.66 | 131.5 | 3.7 | 133 | 8.6 | 98.9 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 4 | SF-19-4 | 11/19/2015 | 684508.0 | 602880.1 | 11.49 | 131.0 | 4.7 | 133 | 8.6 | 98.5 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | SF-20-1 | 11/19/2015 | 684546.3 | 602907.6 | 8.77 | 129.3 | 4.3 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-20-2 | 11/19/2015 | 684545.4 | 602907.4 | 9.83 | 129.9 | 3.2 | 133 | 8.6 | 97.7 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 3 | SF-20-3 | 11/19/2015 | 684547.9 | 602908.6 | 10.90 | 130.1 | 3.5 | 133 | 8.6 | 97.8 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 4 | SF-20-4 | 11/19/2015 | 684548.3 | 602910.0 | 11.78 | 129.3 | 3.5 | 133 | 8.6 | 97.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | CS-100-1 | 11/24/2015 | 684631.4 | 602847.9 | 21.61 | 115.7 | 8.1 | 117 | 8.6 | 98.9 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-101-1 | 11/24/2015 | 684579.4 | 602829.3 | 21.00 | 122.2 | 5.3 | 117 | 8.6 | 104.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-103-1 | 11/24/2015 | 684559.4 | 602849.9 | 20.50 | 117.0 | 4.5 | 117 | 8.6 | 100.0 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-104-1 | 11/24/2015 | 684591.9 | 602894.4 | 20.26 | 118.5 | 6.3 | 117 | 8.6 | 101.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-105-1 | 11/24/2015 | 684549.1 | 602875.2 | 19.46 | 116.3 | 8.1 | 117 | 8.6 | 99.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-93-1 | 11/24/2015 | 684673.4 | 602728.7 | 17.07 | 115.0 | 9.4 | 117 | 8.6 | 98.3 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-95-1 | 11/24/2015 | 684652.5 | 602744.8 | 17.71 | 126.5 | 5.5 | 117 | 8.6 | 108.1 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-96-1 | 11/24/2015 | 684681.1 | 602793.4 | 18.36 | 119.7 | 6.8 | 117 | 8.6 | 102.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-97-1 | 11/24/2015 | 684634.5 | 602782.1 | 18.43 | 115.4 | 6.5 | 117 | 8.6 | 98.6 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-98-1 | 11/24/2015 | 684578.8 | 602757.8 | 18.44 | 117.4 | 6.3 | 117 | 8.6 | 100.3 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-99-1 | 11/24/2015 | 684610.9 | 602806.5 | 18.70 | 118.6 | 6.8 | 117 | 8.6 | 101.4 | 90 | 6 | GDL Cover Soil | | V5N |
| 5 | SF-19-5 | 11/24/2015 | 684507.1 | 602879.1 | 13.03 | 133.2 | 5.6 | 133 | 8.6 | 100.2 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 6 | SF-19-6 | 11/24/2015 | 684506.8 | 602882.9 | 14.10 | 131.8 | 3.7 | 133 | 8.6 | 99.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 7 | SF-19-7 | 11/24/2015 | 684510.4 | 602881.3 | 15.06 | 130.9 | 4.2 | 133 | 8.6 | 98.4 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 5 | SF-20-5 | 11/24/2015 | 684546.9 | 602907.7 | 12.52 | 126.8 | 6.7 | 133 | 8.6 | 95.3 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 6 | SF-20-6 | 11/24/2015 | 684545.9 | 602910.3 | 13.50 | 133.1 | 4.7 | 133 | 8.6 | 100.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 7 | SF-20-7 | 11/24/2015 | 684540.5 | 602910.5 | 14.48 | 129.1 | 4.7 | 133 | 8.6 | 97.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 1 | CS-102-1 | 12/8/2015 | 684522.1 | 602789.6 | 9.92 | 119.0 | 9.9 | 117 | 8.6 | 101.7 | 90 | 6 | GDL Cover Soil | | V5N |
| 1 | CS-86-1 | 12/8/2015 | 684691.4 | 602613.8 | 6.27 | 120.7 | 8.5 | 117 | 8.6 | 103.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-87-1 | 12/8/2015 | 684741.0 | 602650.3 | 9.32 | 120.8 | 8.7 | 117 | 8.6 | 103.2 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-88-1 | 12/8/2015 | 684774.1 | 602700.3 | 8.44 | 122.0 | 9.4 | 117 | 8.6 | 104.3 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-89-1 | 12/8/2015 | 684713.8 | 602685.9 | 19.10 | 113.6 | 5.5 | 117 | 8.6 | 97.1 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-90-1 | 12/8/2015 | 684663.9 | 602654.3 | 15.96 | 115.2 | 6.4 | 117 | 8.6 | 98.5 | 90 | 7 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-91-1 | 12/8/2015 | 684668.9 | 602109.2 | 19.40 | 113.2 | 8.2 | 117 | 8.6 | 96.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-92-1 | 12/8/2015 | 684729.2 | 602749.3 | 16.89 | 117.9 | 7.2 | 117 | 8.6 | 100.8 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | CS-94-1 | 12/8/2015 | 684610.2 | 602684.0 | 7.41 | 116.3 | 9.6 | 117 | 8.6 | 99.4 | 90 | 7 | GDL Cover Soil | | V5N |
| 1 | HC-100-1 | 12/8/2015 | 684624.6 | 602844.3 | 22.22 | 116.6 | 10.6 | 126 | 9.5 | 92.5 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-101-1 | 12/8/2015 | 684579.3 | 602829.2 | 21.65 | 128.5 | 9.0 | 126 | 9.5 | 102.0 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-102-1 | 12/8/2015 | 684517.4 | 602793.0 | 10.54 | 115.0 | 11.3 | 126 | 9.5 | 91.3 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-103-1 | 12/8/2015 | 684558.5 | 602852.7 | 20.94 | 121.1 | 10.2 | 126 | 9.5 | 96.1 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-104-1 | 12/8/2015 | 684589.0 | 602899.7 | 20.69 | 119.1 | 11.1 | 126 | 9.5 | 94.5 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-105-1 | 12/8/2015 | 684547.5 | 602874.7 | 20.00 | 114.1 | 12.6 | 126 | 9.5 | 90.6 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-106-1 | 12/8/2015 | 684488.5 | 602824.5 | 11.23 | 117.5 | 10.4 | 126 | 9.5 | 93.3 | 90 | 5 | Horizon C | Back Scatter | V5N |
| 1 | HC-97-1 | 12/8/2015 | 684634.5 | 602785.1 | 19.13 | 113.4 | 10.4 | 126 | 9.5 | 90.0 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-98-1 | 12/8/2015 | 684580.8 | 602761.3 | 19.04 | 114.9 | 10.3 | 126 | 9.5 | 91.2 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | HC-99-1 | 12/8/2015 | 684613.8 | 602809.7 | 19.33 | 115.5 | 9.6 | 126 | 9.5 | 91.7 | 90 | 6 | Horizon C | Back Scatter | V5N |
| 1 | SF-10-1 | 12/8/2015 | 684712.0 | 602632.9 | 8.47 | 146.3 | 3.0 | 133 | 8.6 | 110.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 1 | SF-11-1 | 12/8/2015 | 684764.1 | 602680.4 | 9.70 | 138.2 | 4.8 | 133 | 8.6 | 103.9 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 2 | SF-12-2 | 12/8/2015 | 684486.5 | 602887.8 | 16.20 | 132.2 | 7.3 | 133 | 8.6 | 99.4 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-12-3 | 12/8/2015 | 684483.4 | 602896.1 | 17.66 | 129.1 | 8.2 | 133 | 8.6 | 97.1 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 2 | SF-13-2 | 12/8/2015 | 684519.0 | 602908.4 | 17.00 | 127.7 | 6.0 | 133 | 8.6 | 96.0 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-13-3 | 12/8/2015 | 684517.8 | 602915.5 | 18.34 | 130.7 | 6.3 | 133 | 8.6 | 98.3 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 2 | SF-14-2 | 12/8/2015 | 684545.3 | 602935.8 | 17.44 | 127.2 | 6.6 | 133 | 8.6 | 95.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 3 | SF-14-3 | 12/8/2015 | 684538.7 | 602936.2 | 18.35 | 127.2 | 7.0 | 133 | 8.6 | 95.6 | 95 | 5 | Structural Fill -Liberty | D Street Corridor-shallow benc | V5N |
| 8 | SF-19-8 | 12/8/2015 | 684511.3 | 602878.7 | 16.16 | 133.8 | 6.3 | 133 | 8.6 | 100.6 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 9 | SF-19-9 | 12/8/2015 | 684512.4 | 602884.5 | 17.40 | 120.8 | 7.0 | 133 | 8.6 | 90.8 | 95 | 5 | Structural Fill -Liberty | SF-19-9R (Page 4) | V5N |
| 9 | SF-19-9R | 12/8/2015 | 684512.0 | 602884.0 | 17.40 | 130.2 | 7.4 | 133 | 8.6 | 97.9 | 95 | 5 | Structural Fill -Liberty | Re-test lift after rolling | V5N |
| 8 | SF-20-8 | 12/8/2015 | 684559.3 | 602906.9 | 15.66 | 127.8 | 7.6 | 133 | 8.6 | 96.1 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 9 | SF-20-9 | 12/8/2015 | 684559.5 | 602915.7 | 17.27 | 126.7 | 7.4 | 133 | 8.6 | 95.3 | 95 | 5 | Structural Fill -Liberty | Location added to D Street | V5N |
| 2 | SF-10-2 | 12/10/2015 | 684716.8 | 602639.7 | 9.79 | 132.4 | 6.0 | 133 | 8.6 | 99.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-10-3 | 12/10/2015 | 684718.1 | 602641.1 | 10.74 | 129.7 | 3.0 | 133 | 8.6 | 97.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 2 | SF-11-2 | 12/10/2015 | 684763.0 | 602675.2 | 10.41 | 130.5 | 6.0 | 133 | 8.6 | 98.1 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-11-3 | 12/10/2015 | 684762.5 | 602675.9 | 11.33 | 125.7 | 3.0 | 133 | 8.6 | 94.5 | 95 | 7 | Structural Fill -Liberty | SF-11-3R (Page 4) | V5N |
| 4 | SF-10-4 | 12/14/2015 | 684719.5 | 602644.8 | 11.71 | 126.4 | 1.9 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 5 | SF-10-5 | 12/14/2015 | 684713.2 | 602644.6 | 12.77 | 126.4 | 2.5 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 6 | SF-10-6 | 12/14/2015 | 684716.5 | 602649.2 | 13.99 | 126.5 | 3.4 | 133 | 8.6 | 95.1 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 3 | SF-11-3R | 12/14/2015 | 684762.0 | 602675.0 | 11.33 | 126.4 | 1.5 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | Re-test lift after rolling | V5N |
| 4 | SF-11-4 | 12/14/2015 | 684761.3 | 602678.2 | 12.57 | 127.9 | 2.1 | 133 | 8.6 | 96.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 5 | SF-11-5 | 12/14/2015 | 684770.8 | 602673.9 | 13.60 | 126.6 | 3.2 | 133 | 8.6 | 95.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 6 | SF-11-6 | 12/14/2015 | 684762.3 | 602666.3 | 14.54 | 126.6 | 3.9 | 133 | 8.6 | 95.2 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 7 | SF-10-7 | 12/15/2015 | 684716.8 | 602641.2 | 15.03 | 131.0 | 5.3 | 133 | 8.6 | 98.5 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 8 | SF-10-8 | 12/15/2015 | 684716.0 | 602649.9 | 16.07 | 126.7 | 3.3 | 133 | 8.6 | 95.3 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 9 | SF-10-9 | 12/15/2015 | 684719.3 | 602639.9 | 16.86 | 128.9 | 5.7 | 133 | 8.6 | 96.9 | 95 | 7 | Structural Fill -Liberty | C Street Corridor-final el | V5N |
| 7 | SF-11-7 | 12/15/2015 | 684765.3 | 602680.3 | 15.76 | 126.3 | 3.4 | 133 | 8.6 | 95.0 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 8 | SF-11-8 | 12/15/2015 | 684762.4 | 602675.2 | 16.71 | 128.1 | 5.7 | 133 | 8.6 | 96.3 | 95 | 7 | Structural Fill -Liberty | C Street Corridor | V5N |
| 9 | SF-11-9 | 12/15/2015 | 684752.5 | 602686.1 | 16.86 | 130.0 | 7.4 | 133 | 8.6 | 97.7 | 95 | 7 | Structural Fill -Liberty | C Street Corridor-final el | V5N |
| 5 | SF-10-5R | 3/6/2016 | 684712.8 | 602643.3 | 13.55 | 108.2 | 2.5 | 112.2 | 9.7 | 96.4 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | SF-10-4R | 3/16/2016 | 684708.7 | 602643.3 | 12.47 | 111.6 | 2.8 | 112.2 | 9.7 | 99.5 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 4 | SF-11-4R | 3/16/2016 | 684760.2 | 602681.4 | 12.15 | 112.0 | 2.5 | 112.2 | 9.7 | 99.8 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 5 | SF-11-5R | 3/16/2016 | 684748.8 | 602679.9 | 13.15 | 108.0 | 2.4 | 112.2 | 9.7 | 96.3 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 6 | SF-10-6R | 3/17/2016 | 684707.5 | 602634.2 | 15.23 | 109.5 | 2.3 | 112.2 | 9.7 | 97.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 7 | SF-10-7R | 3/17/2016 | 684716.6 | 602642.7 | 16.50 | 114.0 | 3.2 | 112.2 | 9.7 | 101.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 6 | SF-11-6R | 3/17/2016 | 684750.5 | 602661.5 | 15.23 | 107.3 | 2.2 | 112.2 | 9.7 | 95.6 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 7 | SF-11-7R | 3/17/2016 | 684750.3 | 602672.5 | 16.40 | 115.4 | 2.5 | 112.2 | 9.7 | 102.9 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 1 | CS-12-1R | 4/14/2016 | 685504.9 | 601673 | 17.30 | 121.5 | 8.7 | 117 | 8.6 | 103.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-16-1R | 4/14/2016 | 685457.6 | 601721.7 | 16.30 | 117.9 | 7.8 | 117 | 8.6 | 100.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-17-1R | 4/14/2016 | 685434.6 | 601718.5 | 14.70 | 122.5 | 8.0 | 117 | 8.6 | 104.7 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-18-1R | 4/14/2016 | 685395.1 | 601714.8 | 17.20 | 120.3 | 5.3 | 117 | 8.6 | 102.8 | 90 | 1 | GDL Cover Soil | Reworked area | V5N |
| 1 | CS-19-1 | 4/14/2016 | 685414.3 | 601758.3 | 17.20 | 120.6 | 5.6 | 117 | 8.6 | 103.1 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-20-1 | 4/14/2016 | 685421.8 | 601782.3 | 17.30 | 122.8 | 7.0 | 117 | 8.6 | 105.0 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-21-1 | 4/14/2016 | 685388.8 | 601769.3 | 17.40 | 120.0 | 6.8 | 117 | 8.6 | 102.6 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-22-1 | 4/14/2016 | 685341.2 | 601751.2 | 17.60 | 119.0 | 8.0 | 117 | 8.6 | 101.7 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-23-1 | 4/14/2016 | 685366.5 | 601794.2 | 18.10 | 121.4 | 4.7 | 117 | 8.6 | 103.8 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-24-1 | 4/14/2016 | 685390.4 | 601829.7 | 18.20 | 114.8 | 6.0 | 117 | 8.6 | 98.1 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-25-1 | 4/14/2016 | 685348.8 | 601819.2 | 19.00 | 121.5 | 7.7 | 117 | 8.6 | 103.8 | 90 | 8 | GDL Cover Soil | | V5N |
| 1 | CS-26-1 | 4/14/2016 | 685305.2 | 601804.9 | 19.30 | 117.9 | 5.4 | 117 | 8.6 | 100.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-27-1 | 4/14/2016 | 685325.1 | 601846.4 | 16.90 | 120.3 | 7.0 | 117 | 8.6 | 102.8 | 90 | 9 | GDL Cover Soil | | V5N |
| 1 | CS-28-1 | 4/15/2016 | 685354.8 | 601891.6 | 16.00 | 125.7 | 6.8 | 117 | 8.6 | 107.4 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-29-1 | 4/15/2016 | 685310.4 | 601883.3 | 19.60 | 120.1 | 7.3 | 117 | 8.6 | 102.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-30-1 | 4/15/2016 | 685259.5 | 601859.9 | 17.30 | 120.9 | 6.7 | 117 | 8.6 | 103.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-31-1 | 4/15/2016 | 685289.6 | 601902.5 | 19.60 | 125.3 | 7.4 | 117 | 8.6 | 107.1 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | HC-08-1 | 4/15/2016 | 685535.1 | 601617.9 | 17.00 | 115.8 | 9.8 | 126 | 9.8 | 91.9 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-09-1 | 4/15/2016 | 685492.6 | 601603.4 | 17.10 | 116.4 | 9.7 | 126 | 9.5 | 92.4 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-12-1 | 4/15/2016 | 685500.6 | 601671.6 | 17.90 | 115.1 | 9.4 | 126 | 9.5 | 91.3 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-16-1 | 4/15/2016 | 685457.5 | 601729.1 | 16.80 | 120.2 | 9.4 | 126 | 9.5 | 95.4 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-04-01 | 4/18/2016 | 685309.3 | 601839.5 | 14.50 | 107.5 | 1.7 | 112.2 | 9.7 | 95.8 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-04-02 | 4/18/2016 | 685311.3 | 601840.4 | 16.00 | 110.5 | 1.6 | 112.2 | 9.7 | 98.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 3 | SF-04-03 | 4/18/2016 | 685289.9 | 601837.7 | 17.60 | 108.1 | 1.8 | 112.2 | 9.7 | 96.3 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | SF-05-01 | 4/18/2016 | 685325.3 | 601867.3 | 18.00 | 114.9 | 2.0 | 112.2 | 9.7 | 102.4 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | SF-06-01 | 4/18/2016 | 685357.4 | 601889.1 | 17.50 | 111.6 | 2.0 | 112.2 | 9.7 | 99.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 4 | SF-04-04 | 4/20/2016 | 685294.4 | 601842.4 | 19.10 | 106.6 | 2.0 | 112.2 | 9.7 | 95.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-05-02 | 4/20/2016 | 685320.8 | 601866.4 | 19.70 | 107.7 | 2.0 | 112.2 | 9.7 | 96.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 2 | SF-06-02 | 4/20/2016 | 685348.9 | 601890.6 | 19.50 | 106.6 | 2.0 | 112.2 | 9.7 | 95.0 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor | V5N |
| 1 | HC-17-01 | 4/20/2016 | 685432.8 | 601721.6 | 15.20 | 122.4 | 9.5 | 126 | 9.5 | 97.1 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-18-01 | 4/20/2016 | 685393.5 | 601712.7 | 17.70 | 117.2 | 10.2 | 126 | 9.5 | 93.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-19-01 | 4/20/2016 | 685419.8 | 601751.3 | 15.30 | 117.4 | 9.5 | 126 | 9.5 | 93.2 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-20-01 | 4/20/2016 | 685423.4 | 601782.8 | 17.80 | 125.8 | 8.8 | 126 | 9.5 | 99.8 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-21-01 | 4/20/2016 | 685383.0 | 601770.6 | 18.20 | 127.3 | 8.9 | 126 | 9.5 | 101.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-22-01 | 4/20/2016 | 685340.2 | 601758.3 | 18.30 | 118.4 | 8.6 | 126 | 9.5 | 94.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-23-01 | 4/20/2016 | 685366.4 | 601793.6 | 18.50 | 122.2 | 8.8 | 126 | 9.5 | 97.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-24-01 | 4/20/2016 | 685392.1 | 601831.1 | 18.90 | 119.7 | 8.4 | 126 | 9.5 | 95.0 | 90 | 8 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | HC-25-01 | 4/20/2016 | 685351.7 | 601822.1 | 19.40 | 129.8 | 9.2 | 126 | 9.5 | 103.0 | 90 | 8 | Horizon C | Back Scatter | V5N |
| 1 | HC-26-01 | 4/20/2016 | 685303.8 | 601806.5 | 19.90 | 113.4 | 8.1 | 126 | 9.5 | 90.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | HC-27-01 | 4/20/2016 | 685361.7 | 601845.0 | 19.70 | 121.0 | 9.0 | 126 | 9.5 | 96.0 | 90 | 9 | Horizon C | Back Scatter | V5N |
| 1 | CS-01-01 | 4/20/2016 | 685552.1 | 601486.2 | 16.40 | 111.2 | 9.0 | 117 | 8.6 | 95.1 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-02-01 | 4/20/2016 | 685571.4 | 601519.1 | 18.50 | 120.5 | 9.1 | 117 | 8.6 | 103.0 | 90 | 10 | GDL Cover Soil | | V5N |
| 1 | CS-47-01 | 4/22/2016 | 685133.2 | 602127.9 | 6.50 | 117.0 | 8.6 | 117 | 8.6 | 100.0 | 90 | 13 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | CS-48-01 | 4/22/2016 | 685161.9 | 602170.3 | 7.10 | 115.8 | 8.4 | 117 | 8.6 | 99.0 | 90 | 14 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | CS-49-01 | 4/22/2016 | 685114.8 | 602135.6 | 6.40 | 111.2 | 8.4 | 117 | 8.6 | 95.0 | 90 | 14 | GDL Cover Soil | B Street Corridor | V5N |
| 1 | HC-05-01 | 4/22/2016 | 685511.7 | 601549.5 | 18.30 | 113.4 | 8.2 | 126 | 9.5 | 90.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-06-01 | 4/22/2016 | 685479.0 | 601533.4 | 15.00 | 119.7 | 8.0 | 126 | 9.5 | 95.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | HC-07-01 | 4/22/2016 | 685514.3 | 601578.6 | 18.30 | 113.4 | 8.2 | 126 | 9.5 | 90.0 | 90 | 1 | Horizon C | Back Scatter | V5N |
| 1 | SF-01-01 | 4/22/2016 | 685510.3 | 601523.6 | 16.60 | 107.7 | 8.0 | 112.2 | 9.7 | 96.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-02-01 | 4/22/2016 | 685547.6 | 601542.6 | 18.30 | 102.0 | 8.1 | 112.2 | 9.7 | 90.9 | 95 | 10 | Structural Fill - Tilcon | SF-02-01R (Page 6) | V5N |
| 1 | SF-03-01 | 4/22/2016 | 685585.2 | 601572.6 | 18.20 | 106.6 | 8.2 | 112.2 | 9.7 | 95.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | SF-02-01R | 4/22/2016 | 685547.6 | 601542.6 | 18.30 | 106.6 | 8.1 | 112.2 | 9.7 | 95.0 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; reroll and retes | V5N |
| 1 | HC-04-01 | 4/26/2016 | 685586.2 | 601559.0 | 19.40 | 117.5 | 9.1 | 126 | 9.5 | 93.3 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-02-01 | 4/26/2016 | 685575.9 | 601519.7 | 19.30 | 114.2 | 10.6 | 126 | 9.5 | 90.6 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-03-01 | 4/26/2016 | 685531.2 | 601505.9 | 17.90 | 124.3 | 8.1 | 126 | 9.5 | 98.7 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 1 | HC-01-01 | 4/26/2016 | 685554.0 | 601483.2 | 16.80 | 114.7 | 9.6 | 126 | 9.5 | 91.0 | 90 | 10 | Horizon C | Back Scatter | V5N |
| 2 | SF-01-02 | 4/26/2016 | 685512.5 | 601525.3 | 17.50 | 118.2 | 7.0 | 112.2 | 9.7 | 105.3 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 2 | SF-02-02 | 4/26/2016 | 685553.1 | 601555.1 | 18.90 | 114.9 | 4.7 | 112.2 | 9.7 | 102.4 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 2 | SF-03-02 | 4/26/2016 | 685577.3 | 601575.2 | 19.30 | 120.3 | 4.9 | 112.2 | 9.7 | 107.2 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive | V5N |
| 1 | CS-32-01 | 4/26/2016 | 685305.2 | 601932.9 | 19.50 | 117.6 | 7.2 | 117 | 8.6 | 100.5 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-33-01 | 4/26/2016 | 685271.2 | 601934.8 | 19.60 | 117.0 | 10.6 | 117 | 8.6 | 100.0 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-34-01 | 4/26/2016 | 685225.8 | 601921.4 | 19.80 | 117.7 | 9.8 | 117 | 8.6 | 100.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-35-01 | 4/26/2016 | 685251.7 | 601967.3 | 19.30 | 117.6 | 10.5 | 117 | 8.6 | 100.5 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-36-01 | 4/26/2016 | 685269.0 | 601997.3 | 18.80 | 114.6 | 9.7 | 117 | 8.6 | 97.9 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | SF-07-01 | 4/26/2016 | 685096.6 | 606106.8 | 7.10 | 130.5 | 6.2 | 112.2 | 9.7 | 116.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | SF-08-01 | 4/26/2016 | 685131.5 | 602130.1 | 7.40 | 129.9 | 5.8 | 112.2 | 9.7 | 115.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | SF-09-01 | 4/26/2016 | 685163.1 | 602153.3 | 7.60 | 127.8 | 5.7 | 112.2 | 9.7 | 113.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-07-02 | 4/26/2016 | 685098.7 | 602108.8 | 7.90 | 124.6 | 4.8 | 112.2 | 9.7 | 111.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-08-02 | 4/26/2016 | 685134.0 | 602134.2 | 8.20 | 116.8 | 3.7 | 112.2 | 9.7 | 104.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 2 | SF-09-02 | 4/26/2016 | 685173.6 | 602160.2 | 8.60 | 128.1 | 5.5 | 112.2 | 9.7 | 114.2 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-07-03 | 4/27/2016 | 685096.6 | 602106.8 | 9.40 | 113.2 | 2.8 | 112.2 | 9.7 | 100.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-08-03 | 4/27/2016 | 685131.5 | 602133.6 | 9.60 | 112.5 | 3.2 | 112.2 | 9.7 | 100.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 3 | SF-09-03 | 4/27/2016 | 685168.9 | 602159.4 | 10.00 | 116.2 | 2.9 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-07-04 | 4/28/2016 | 685089.9 | 602105.5 | 10.40 | 107.2 | 4.7 | 112.2 | 9.7 | 95.5 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-08-04 | 4/28/2016 | 685130.3 | 602135.1 | 10.50 | 108.4 | 2.6 | 112.2 | 9.7 | 96.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 4 | SF-09-04 | 4/28/2016 | 685158.3 | 602159.3 | 10.80 | 110.9 | 3.7 | 112.2 | 9.7 | 98.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-07-05 | 4/28/2016 | 658087.4 | 602109.5 | 11.30 | 106.9 | 4.6 | 112.2 | 9.7 | 95.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-08-05 | 4/28/2016 | 685126.7 | 602137.8 | 11.60 | 115.8 | 3.2 | 112.2 | 9.7 | 103.2 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 5 | SF-09-05 | 4/28/2016 | 685164.5 | 602163.5 | 11.50 | 112.6 | 3.3 | 112.2 | 9.7 | 100.4 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | CS-37-01 | 4/28/2016 | 685234.1 | 601983.7 | 18.80 | 121.7 | 8.8 | 117 | 8.6 | 104.0 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-38-01 | 4/28/2016 | 685185.5 | 601970.6 | 18.70 | 116.6 | 6.7 | 117 | 8.6 | 99.7 | 90 | 12 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-39-01 | 4/28/2016 | 685213.8 | 602102.2 | 18.20 | 122.0 | 8.3 | 117 | 8.6 | 104.3 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-40-01 | 4/28/2016 | 685227.8 | 602065.5 | 17.70 | 119.1 | 8.7 | 117 | 8.6 | 101.8 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-41-01 | 4/28/2016 | 685193.2 | 602041.5 | 17.40 | 120.0 | 10.9 | 117 | 8.6 | 102.6 | 90 | 12 | GDL Cover Soil | | V5N |
| 1 | CS-42-01 | 4/28/2016 | 685152.5 | 602025.7 | 17.30 | 119.6 | 8.9 | 117 | 8.6 | 102.2 | 90 | 13 | GDL Cover Soil | | V5N |
| 6 | SF-07-06 | 4/29/2016 | 658082.9 | 602108.5 | 12.26 | 114.3 | 2.7 | 112.2 | 9.7 | 101.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 6 | SF-08-06 | 4/29/2016 | 685136.5 | 602126.5 | 12.47 | 110.8 | 2.4 | 112.2 | 9.7 | 98.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 6 | SF-09-06 | 4/29/2016 | 685146.5 | 602166.6 | 12.35 | 113.3 | 2.4 | 112.2 | 9.7 | 101.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | HC-28-01 | 4/29/2016 | 685334.6 | 601903.6 | 19.80 | 119.8 | 9.5 | 126 | 9.5 | 95.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-29-01 | 4/29/2016 | 685294.7 | 601866.8 | 20.20 | 128.7 | 8.4 | 126 | 9.5 | 102.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-30-01 | 4/29/2016 | 685258.9 | 601854.0 | 17.80 | 114.7 | 10.7 | 126 | 9.5 | 91.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-31-01 | 4/29/2016 | 685286.1 | 601905.7 | 20.20 | 124.7 | 9.2 | 126 | 9.5 | 99.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-32-01 | 4/29/2016 | 685294.9 | 601951.8 | 19.90 | 124.5 | 8.7 | 126 | 9.5 | 98.8 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-33-01 | 4/29/2016 | 685267.6 | 601932.2 | 20.10 | 114.7 | 10.2 | 126 | 9.5 | 91.0 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-35-01 | 4/29/2016 | 685251.4 | 601960.8 | 19.80 | 113.7 | 10.5 | 126 | 9.5 | 90.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 7 | SF-07-07 | 5/2/2016 | 685098.9 | 602107.7 | 13.20 | 113.7 | 2.2 | 112.2 | 9.7 | 101.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 7 | SF-08-07 | 5/2/2016 | 685131.4 | 602134.6 | 13.40 | 113.2 | 3.4 | 112.2 | 9.7 | 100.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 7 | SF-09-07 | 5/2/2016 | 685141.4 | 602154.3 | 13.20 | 113.0 | 2.1 | 112.2 | 9.7 | 100.7 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-07-08 | 5/2/2016 | 685090.8 | 602099.0 | 14.20 | 119.6 | 4.0 | 112.2 | 9.7 | 106.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-08-08 | 5/2/2016 | 685126.1 | 602130.8 | 14.50 | 116.2 | 2.6 | 112.2 | 9.7 | 103.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 8 | SF-09-08 | 5/2/2016 | 685060.5 | 602159.1 | 14.00 | 117.3 | 3.4 | 112.2 | 9.7 | 104.5 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | CS-43-01 | 5/2/2016 | 685178.7 | 602060.3 | 17.20 | 119.7 | 10.1 | 117 | 8.6 | 102.3 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-44-01 | 5/2/2016 | 685227.7 | 602065.5 | 17.70 | 115.8 | 7.3 | 117 | 8.6 | 99.0 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-45-01 | 5/2/2016 | 685152.4 | 602803.2 | 17.60 | 114.5 | 7.1 | 117 | 8.6 | 97.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | CS-46-01 | 5/2/2016 | 685108.7 | 602067.4 | 15.00 | 109.9 | 7.8 | 117 | 8.6 | 93.9 | 90 | 13 | GDL Cover Soil | | V5N |
| 1 | HC-34-01 | 5/2/2016 | 685227.3 | 601914.0 | 20.50 | 117.5 | 10.3 | 126 | 9.5 | 93.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-36-01 | 5/2/2016 | 685269.4 | 601989.1 | 19.50 | 119.1 | 11.1 | 126 | 9.5 | 94.5 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-37-01 | 5/2/2016 | 685232.0 | 601988.5 | 19.30 | 115.0 | 9.8 | 126 | 9.5 | 91.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-38-01 | 5/2/2016 | 685181.9 | 601969.6 | 19.30 | 113.7 | 11.7 | 126 | 9.5 | 90.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-39-01 | 5/2/2016 | 685213.9 | 602004.5 | 18.70 | 116.0 | 8.9 | 126 | 9.5 | 92.1 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-40-01 | 5/2/2016 | 685226.0 | 602151.1 | 18.10 | 125.0 | 10.0 | 126 | 9.5 | 99.2 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 1 | HC-41-01 | 5/2/2016 | 685199.7 | 602037.5 | 18.00 | 120.1 | 10.4 | 126 | 9.5 | 95.3 | 90 | 12 | Horizon C | Back Scatter | V5N |
| 9 | SF-07-09 | 5/5/2016 | 685008.1 | 602099.3 | 14.90 | 120.0 | 3.5 | 112.2 | 9.7 | 107.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 9 | SF-08-09 | 5/5/2016 | 685134.3 | 602127.7 | 15.00 | 123.4 | 3.2 | 112.2 | 9.7 | 110.0 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 9 | SF-09-09 | 5/5/2016 | 685169.3 | 602144.8 | 14.90 | 115.7 | 4.2 | 112.2 | 9.7 | 103.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-07-10 | 5/5/2016 | 685087.7 | 602155.6 | 16.50 | 120.4 | 4.4 | 112.2 | 9.7 | 107.3 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-08-10 | 5/5/2016 | 685117.3 | 602137.9 | 16.60 | 111.9 | 3.8 | 112.2 | 9.7 | 99.7 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 10 | SF-09-10 | 5/5/2016 | 685155.3 | 602167.4 | 16.30 | 107.8 | 3.1 | 112.2 | 9.7 | 96.1 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor | V5N |
| 1 | HC-42-01 | 5/5/2016 | 685157.1 | 602028.8 | 17.80 | 117.3 | 11.6 | 126 | 9.5 | 93.1 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-43-01 | 5/5/2016 | 685169.9 | 602065.8 | 17.80 | 117.2 | 12.1 | 126 | 9.5 | 93.0 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-44-01 | 5/5/2016 | 685193.6 | 602102.8 | 18.00 | 124.0 | 11.7 | 126 | 9.5 | 98.4 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-45-01 | 5/5/2016 | 685166.2 | 602112.5 | 18.40 | 123.3 | 10.3 | 126 | 9.5 | 97.9 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-46-01 | 5/5/2016 | 685107.4 | 602064.3 | 15.40 | 125.5 | 11.6 | 126 | 9.5 | 99.6 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | HC-47-01 | 5/5/2016 | 685140.2 | 602092.3 | 18.30 | 121.2 | 9.2 | 126 | 9.5 | 96.2 | 90 | 13 | Horizon C | Back Scatter | V5N |
| 1 | CS-50-01 | 5/11/2016 | 685060.3 | 602129.0 | 16.00 | 114.9 | 9.2 | 117 | 8.6 | 98.2 | 90 | 14 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-51-01 | 5/11/2016 | 685095.6 | 602173.6 | 18.80 | 115.3 | 9.2 | 117 | 8.6 | 98.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-52-01 | 5/11/2016 | 685118.1 | 602212.6 | 18.30 | 116.9 | 9.2 | 117 | 8.6 | 99.9 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-53-01 | 5/11/2016 | 685077.2 | 602198.8 | 18.80 | 115.3 | 9.8 | 117 | 8.6 | 98.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-54-01 | 5/11/2016 | 685018.9 | 602196.7 | 19.40 | 113.0 | 8.8 | 117 | 8.6 | 96.6 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-55-01 | 5/11/2016 | 685037.7 | 602225.0 | 16.90 | 112.7 | 13.2 | 117 | 8.6 | 96.3 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-57-01 | 5/11/2016 | 685029.4 | 602258.5 | 17.50 | 116.7 | 11.6 | 117 | 8.6 | 99.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-58-01 | 5/11/2016 | 684989.3 | 602236.4 | 20.10 | 117.6 | 9.4 | 117 | 8.6 | 100.5 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-59-01 | 5/11/2016 | 685005.7 | 602278.3 | 17.80 | 119.0 | 11.8 | 117 | 8.6 | 101.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-61-01 | 5/11/2016 | 684990.1 | 602311.3 | 18.30 | 112.5 | 14.7 | 117 | 8.6 | 96.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-62-01 | 5/11/2016 | 684954.1 | 602272.2 | 20.80 | 116.1 | 9.5 | 117 | 8.6 | 99.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-63-01 | 5/11/2016 | 684978.4 | 602338.7 | 18.70 | 110.8 | 6.8 | 117 | 8.6 | 94.7 | 90 | 15 | GDL Cover Soil | | V5N |
| 11 | SF-07-11 | 5/11/2016 | 685085.8 | 602102.0 | 17.60 | 108.4 | 2.1 | 112.2 | 9.7 | 96.6 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 11 | SF-08-11 | 5/11/2016 | 685120.0 | 602122.7 | 17.80 | 107.5 | 2.5 | 112.2 | 9.7 | 95.8 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 11 | SF-09-11 | 5/11/2016 | 685157.2 | 602150.4 | 17.70 | 109.8 | 2.6 | 112.2 | 9.7 | 97.9 | 95 | 11 | Structural Fill - Tilcon | B Street Corridor-final el | V5N |
| 3 | SF-01-03 | 5/11/2016 | 685512.3 | 601525.2 | 19.30 | 113.1 | 2.0 | 112.2 | 9.7 | 100.8 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 3 | SF-02-03 | 5/11/2016 | 685546.3 | 601552.4 | 19.40 | 116.2 | 2.4 | 112.2 | 9.7 | 103.6 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 3 | SF-03-03 | 5/11/2016 | 685585.6 | 601575.9 | 19.30 | 116.9 | 2.0 | 112.2 | 9.7 | 104.2 | 95 | 10 | Structural Fill - Tilcon | Riverside Drive; final el | V5N |
| 1 | HC-48-01 | 5/16/2016 | 685126.3 | 602180.8 | 19.30 | 114.6 | 14.9 | 126 | 9.5 | 91.0 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-49-01 | 5/16/2016 | 685093.4 | 602149.0 | 17.00 | 145.7 | 9.9 | 126 | 9.5 | 115.6 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-50-01 | 5/16/2016 | 685061.4 | 602128.9 | 16.50 | 119.8 | 13.2 | 126 | 9.5 | 95.1 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-51-01 | 5/16/2016 | 685096.6 | 602178.9 | 19.30 | 120.1 | 11.0 | 126 | 9.5 | 95.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-52-01 | 5/16/2016 | 685119.9 | 602212.3 | 18.80 | 114.5 | 11.6 | 126 | 9.5 | 90.9 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-53-01 | 5/16/2016 | 685054.2 | 602219.1 | 19.60 | 118.1 | 10.7 | 126 | 9.5 | 93.7 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-54-01 | 5/16/2016 | 685019.8 | 602191.5 | 19.80 | 114.2 | 12.4 | 126 | 9.5 | 90.6 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-55-01 | 5/16/2016 | 685054.2 | 602219.1 | 19.60 | 120.1 | 12.8 | 126 | 9.5 | 95.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-56-01 | 5/16/2016 | 685075.9 | 602263.9 | 19.80 | 116.8 | 12.7 | 126 | 9.5 | 92.7 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-57-01 | 5/16/2016 | 685032.7 | 602252.7 | 17.90 | 118.6 | 9.8 | 126 | 9.5 | 94.1 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-58-01 | 5/16/2016 | 684988.4 | 602235.8 | 20.60 | 114.7 | 11.1 | 126 | 9.5 | 91.0 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | HC-59-01 | 5/16/2016 | 685010.1 | 602267.9 | 18.10 | 122.6 | 8.7 | 126 | 9.5 | 97.3 | 90 | 14 | Horizon C | Back Scatter | V5N |
| 1 | CS-56-01 | 5/16/2016 | 685025.1 | 602299.5 | 20.30 | 118.5 | 11.5 | 117 | 8.6 | 101.3 | 90 | 14 | GDL Cover Soil | | V5N |
| 1 | CS-60-01 | 5/16/2016 | 685025.9 | 602329.2 | 18.00 | 113.1 | 11.9 | 117 | 8.6 | 96.7 | 90 | 14 | GDL Cover Soil | | V5N |
| 5 | SF-04-05 | 5/16/2016 | 685352.5 | 601871.7 | 19.40 | 114.6 | 1.5 | 112.2 | 9.7 | 102.1 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 3 | SF-05-03 | 5/16/2016 | 685321.5 | 601855.6 | 19.70 | 117.7 | 1.8 | 112.2 | 9.7 | 104.9 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 3 | SF-06-03 | 5/16/2016 | 685289.7 | 601832.8 | 19.70 | 108.3 | 1.4 | 112.2 | 9.7 | 96.5 | 95 | 9 | Structural Fill - Tilcon | A Street Corridor; final el | V5N |
| 1 | CS-64-01 | 5/18/2016 | 684999.1 | 602372.6 | 18.70 | 115.6 | 7.7 | 117 | 8.6 | 98.8 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-65-01 | 5/18/2016 | 684995.4 | 602360.5 | 18.90 | 116.5 | 11.3 | 117 | 8.6 | 99.6 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-66-01 | 5/18/2016 | 684907.9 | 602343.4 | 19.00 | 120.8 | 9.0 | 117 | 8.6 | 103.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-67-01 | 5/18/2016 | 684935.3 | 602386.4 | 18.90 | 115.3 | 11.1 | 117 | 8.6 | 98.5 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-68-01 | 5/18/2016 | 684960.5 | 602427.3 | 18.80 | 112.6 | 9.6 | 117 | 8.6 | 96.2 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-69-01 | 5/18/2016 | 684918.4 | 602414.4 | 18.70 | 114.0 | 11.0 | 117 | 8.6 | 97.4 | 90 | 15 | GDL Cover Soil | | V5N |
| 1 | CS-71-01 | 5/18/2016 | 684888.7 | 602434.3 | 18.00 | 116.7 | 12.4 | 117 | 8.6 | 99.7 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-72-01 | 5/18/2016 | 684917.8 | 602480.4 | 18.00 | 117.5 | 8.8 | 117 | 8.6 | 100.4 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | HC-49-01R | 5/18/2016 | 685093.4 | 602149.0 | 17.00 | 117.5 | 9.9 | 126 | 9.5 | 93.3 | 90 | 14 | Horizon C | Back Scatter; re-run test | V5N |
| 1 | CS-70-01 | 5/20/2016 | 684860.3 | 602329.6 | 18.20 | 111.8 | 7.6 | 117 | 8.6 | 95.6 | 90 | 16 | GDL Cover Soil | | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| LIFT NO. | TEST I.D. | TEST DATE | LOCATION NORTHING | LOCATION EASTING | ELEV. (FT) | FIELD DRY DENSITY (PCF) | FIELD MOISTURE CONTENT (%) | PROCTOR MAXIMUM DRY DENSITY (PCF) | OPTIMUM MOISTURE CONTENT (%) | FIELD PERCENT COMPACTION | SPECIFIED PERCENT COMPACTION | AREA | LIFT MATERIAL | NOTES | TESTING COMPANY |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | CS-73-01 | 5/20/2016 | 684869.9 | 602462.4 | 17.40 | 115.6 | 11.7 | 117 | 8.6 | 98.8 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-74-01 | 5/20/2016 | 684821.2 | 602444.5 | 16.60 | 116.4 | 12.6 | 117 | 8.6 | 99.5 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | CS-75-01 | 5/20/2016 | 684852.3 | 602488.7 | 16.60 | 114.2 | 10.0 | 117 | 8.6 | 97.6 | 90 | 16 | GDL Cover Soil | | V5N |
| 1 | HC-60-01 | 5/20/2016 | 685036.3 | 602315.7 | 18.50 | 117.4 | 9.5 | 126 | 9.5 | 93.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-61-01 | 5/20/2016 | 685958.1 | 602318.7 | 19.30 | 123.7 | 11.9 | 126 | 9.5 | 98.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-62-01 | 5/20/2016 | 684943.1 | 602291.6 | 21.70 | 116.8 | 10.2 | 126 | 9.5 | 92.7 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-63-01 | 5/20/2016 | 684974.6 | 602334.4 | 19.20 | 116.1 | 13.3 | 126 | 9.5 | 92.1 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-64-01 | 5/20/2016 | 685000.9 | 602370.5 | 19.20 | 116.7 | 9.4 | 126 | 9.5 | 92.6 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-65-01 | 5/20/2016 | 684954.1 | 602361.6 | 19.50 | 120.6 | 13.2 | 126 | 9.5 | 95.7 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-66-01 | 5/20/2016 | 684906.2 | 602342.6 | 19.50 | 114.5 | 11.8 | 126 | 9.5 | 90.9 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-68-01 | 5/20/2016 | 684955.8 | 602413.4 | 19.40 | 120.4 | 12.5 | 126 | 9.5 | 95.6 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-69-01 | 5/20/2016 | 684906.3 | 602419.1 | 19.00 | 123.7 | 10.1 | 126 | 9.5 | 98.2 | 90 | 15 | Horizon C | Back Scatter | V5N |
| 1 | HC-70-01 | 5/20/2016 | 684858.7 | 302396.2 | 18.70 | 124.3 | 11.1 | 126 | 9.5 | 98.7 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-71-01 | 5/20/2016 | 684882.1 | 602433.1 | 18.50 | 114.6 | 13.6 | 126 | 9.5 | 91.0 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-72-01 | 5/20/2016 | 684913.9 | 602473.4 | 18.60 | 124.6 | 11.3 | 126 | 9.5 | 98.9 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-73-01 | 5/20/2016 | 684870.2 | 602464.3 | 18.00 | 122.3 | 12.4 | 126 | 9.5 | 97.1 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-74-01 | 5/20/2016 | 684819.9 | 602423.5 | 16.90 | 124.6 | 11.3 | 126 | 9.5 | 98.9 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | CS-76-01 | 5/27/2016 | 684877.8 | 602531.3 | 19.20 | 107.5 | 6.6 | 117 | 8.6 | 91.9 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-77-01 | 5/27/2016 | 684831.7 | 602514.5 | 15.90 | 111.5 | 9.1 | 117 | 8.6 | 95.3 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-78-01 | 5/27/2016 | 684774.7 | 602493.1 | 14.40 | 111.0 | 8.8 | 117 | 8.6 | 94.9 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-79-01 | 5/27/2016 | 684809.3 | 602541.2 | 17.60 | 111.8 | 6.4 | 117 | 8.6 | 95.6 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-80-01 | 5/27/2016 | 684830.6 | 602582.9 | 15.20 | 113.6 | 9.0 | 117 | 8.6 | 97.1 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-81-01 | 5/27/2016 | 684786.1 | 602567.2 | 14.90 | 113.7 | 8.1 | 117 | 8.6 | 97.2 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-82-01 | 5/27/2016 | 684747.7 | 602551.4 | 14.30 | 108.8 | 8.0 | 117 | 8.6 | 93.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-83-01 | 5/27/2016 | 684775.8 | 602598.9 | 15.40 | 108.9 | 8.7 | 117 | 8.6 | 93.1 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-84-01 | 5/27/2016 | 684806.4 | 602648.6 | 15.30 | 107.6 | 10.1 | 117 | 8.6 | 92.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | CS-85-01 | 5/27/2016 | 684758.7 | 602624.2 | 18.20 | 111.2 | 7.6 | 117 | 8.6 | 95.0 | 90 | 17 | GDL Cover Soil | | V5N |
| 1 | HC-67-01 | 5/27/2016 | 684934.5 | 602386.8 | 19.50 | 122.9 | 10.4 | 126 | 9.5 | 97.5 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-75-01 | 5/27/2016 | 684852.9 | 602485.9 | 17.20 | 114.0 | 7.0 | 126 | 9.5 | 90.5 | 90 | 16 | Horizon C | Back Scatter | V5N |
| 1 | HC-76-01 | 6/2/2016 | 684876.3 | 602531.1 | 19.70 | 119.3 | 9.3 | 126 | 9.5 | 94.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-77-01 | 6/2/2016 | 684830.6 | 602514.8 | 16.40 | 122.3 | 8.4 | 126 | 9.5 | 97.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-78-01 | 6/2/2016 | 684776.0 | 602494.2 | 15.10 | 114.4 | 8.4 | 126 | 9.5 | 90.8 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-79-01 | 6/2/2016 | 684810.5 | 602540.7 | 18.10 | 122.2 | 7.3 | 126 | 9.5 | 97.0 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-80-01 | 6/2/2016 | 684834.1 | 602583.5 | 15.80 | 121.5 | 8.2 | 126 | 9.5 | 96.4 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-81-01 | 6/2/2016 | 684789.9 | 602568.2 | 15.50 | 122.3 | 12.2 | 126 | 9.5 | 97.1 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-82-01 | 6/2/2016 | 684752.2 | 602543.1 | 17.30 | 126.2 | 10.2 | 126 | 9.5 | 100.2 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-83-01 | 6/2/2016 | 684781.1 | 602601.8 | 16.00 | 118.6 | 10.2 | 126 | 9.5 | 94.1 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-84-01 | 6/2/2016 | 684801.5 | 602638.4 | 17.70 | 124.5 | 9.3 | 126 | 9.5 | 98.8 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-85-01 | 6/2/2016 | 684757.6 | 602625.7 | 18.70 | 121.4 | 8.7 | 126 | 9.5 | 96.3 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-86-01 | 6/2/2016 | 684704.4 | 602572.9 | 8.10 | 126.9 | 11.6 | 126 | 9.5 | 100.7 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-87-01 | 6/2/2016 | 684739.4 | 602607.5 | 18.30 | 124.2 | 9.8 | 126 | 9.5 | 98.6 | 90 | 17 | Horizon C | Back Scatter | V5N |
| 1 | HC-88-01 | 6/2/2016 | 684755.1 | 602716.9 | 16.70 | 113.2 | 13.2 | 126 | 9.5 | 90.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-89-01 | 6/2/2016 | 684729.9 | 602698.7 | 19.60 | 115.7 | 11.8 | 126 | 9.5 | 91.8 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-90-01 | 6/2/2016 | 684676.0 | 602662.2 | 19.50 | 127.3 | 11.2 | 126 | 9.5 | 101.0 | 90 | 7 | Horizon C | Back Scatter | V5N |

**FIELD DENSITY TEST SUMMARY LOG**
**SA6 SOUTH CAP**
**Testing Frequency - 1 Test/2,500 Square Feet**
**HONEYWELL STUDY AREA 6 REMEDIATION PROJECT**
**JERSEY CITY, NEW JERSEY**

| | | | | | | FIELD | FIELD | PROCTOR | OPTIMUM | FIELD | SPECIFIED | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LIFT | | TEST | LOCATION | | | DRY | MOISTURE | MAXIMUM DRY | MOISTURE | PERCENT | PERCENT | | | | TESTING |
| NO. | TEST I.D. | DATE | NORTHING | EASTING | ELEV. (FT) | DENSITY (PCF) | CONTENT (%) | DENSITY (PCF) | CONTENT (%) | COMPACTION | COMPACTION | AREA | LIFT MATERIAL | NOTES | COMPANY |
| 1 | HC-91-01 | 6/2/2016 | 684684.9 | 602718.4 | 17.30 | 120.5 | 12.8 | 126 | 9.5 | 95.6 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-92-01 | 6/2/2016 | 684700.5 | 602765.4 | 20.60 | 113.6 | 9.3 | 126 | 9.5 | 90.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-93-01 | 6/2/2016 | 684673.2 | 602735.5 | 17.70 | 116.1 | 13.6 | 126 | 9.5 | 92.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-94-01 | 6/2/2016 | 684616.3 | 602716.8 | 18.00 | 125.0 | 9.4 | 126 | 9.5 | 99.2 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-95-01 | 6/2/2016 | 684650.6 | 602768.2 | 18.70 | 120.9 | 12.6 | 126 | 9.5 | 96.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 1 | HC-96-01 | 6/2/2016 | 684681.4 | 602798.3 | 18.90 | 113.5 | 12.7 | 126 | 9.5 | 90.0 | 90 | 7 | Horizon C | Back Scatter | V5N |
| 8 | SF-10-8R | 6/2/2016 | 684712.5 | 602638.8 | 17.50 | 111.0 | 1.5 | 112.2 | 8.6 | 99.1 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 8 | SF-11-8R | 6/2/2016 | 684758.7 | 602671.8 | 17.40 | 110.5 | 1.8 | 112.2 | 8.6 | 98.7 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 9 | SF-10-9R | 6/2/2016 | 684715.2 | 602640.1 | 18.40 | 113.7 | 1.4 | 112.2 | 8.6 | 101.5 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 9 | SF-11-9R | 6/2/2016 | 684759.7 | 602673.9 | 18.40 | 115.7 | 1.4 | 112.2 | 8.6 | 103.3 | 95 | 7 | Structural Fill - Tilcon | Replace lifts of Liberty SF | V5N |
| 10 | SF-19-10 | 6/15/2016 | 684509.5 | 602871.3 | 18.50 | 108.3 | 2.9 | 112.2 | 8.6 | 96.7 | 95 | 5 | Structural Fill - Tilcon | D Street Corridor-final el | V5N |
| 10 | SF-20-10 | 6/15/2016 | 684550.8 | 602901.1 | 19.00 | 108.7 | 2.6 | 112.2 | 8.6 | 97.0 | 95 | 5 | Structural Fill - Tilcon | D Street Corridor-final el | V5N |


Notes: Maximum Dry Density for Celgene GDL Cover Soil (CS) based on Vertical 5 Northeast Inc Sample ID 12691 approved in Entact Submittal 112B
Maximum Dry Density for 6 inch lift of Horizon C based on Vertical 5 Northeast Inc Sample ID 12934
Maximum Dry Density for Liberty Structural Fill (SF) based on Vertical 5 Northeast Inc Sample ID 12924 approved in Entact Submittal 117A
Maximum Dry Density for Tilcon Structural Fill (SF) based on Vertical 5 Northeast Inc Sample ID 13163 approved in Entact Submittal 128
Sample ID CS-1-2 Where:
CS=Cover Soil; HC=Horizon C; SF=Structural Fill
1 = Test Location as noted on Compaction Location Figures
2 = Number of test performed at that location (sequential)
R = Will be placed after sample ID if the test location is reworked and the compaction test is run again


HC-107 became a Structural Fill test location after the D Street Corridor was widened

## 2.0 Test Location Drawings

- **GDL Cover Soil**
- **Horizon C**
- **Structural Fill**

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION CS-XX

GDL COVER SOIL ELEVATION CONTOURS


ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102


DRAWING NAME: GDL COVER SOIL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | C. CYMBOR | APPROVED BY | | | |
| DATE | 10/15/15 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

2) HC-107 became a structural fill test location after the D street corridor was widened.

LEGEND:

COMPACTION TEST LOCATION HC-XX

GDL COVER SOIL ELEVATION CONTOURS



ENTACT
302 Unity Plaza
Latrobe, PA 15650
412-357-1102



DRAWING NAME: HORIZON C PLANTING SOIL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | | |
| DATE | 06/17/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

# SA-6 SOUTH




NOTES:

1) Testing locations are based on testing frequency specified in 012315 3.13 A. 2. a.

LEGEND:

COMPACTION TEST LOCATION SF-XX

PLANTING SOIL BOUNDARIES

STRUCTURAL FILL

ENTACT 302 Unity Plaza Latrobe, PA 15650 412-357-1102

DRAWING NAME: STRUCTURAL COMPACTION LOCATIONS

PROJECT NAME & LOCATION: HONEYWELL SA-6 REMEDIATION JERSEY CITY, NJ

| | | | | | |
|---|---|---|---|---|---|
| DRAWN BY | J. HOSGOOD | APPROVED BY | | | |
| DATE | 05/19/16 | DATE | | SHEET NO. | 1 OF 1 |
| DRAWING NO. | 1 | | | PROJECT NO. | |

**ATTACHMENT M-1**
**SA-6 NORTH AND SOUTH CONSTRUCTION CONTROL GRID AS-BUILT SUMMARIES**

Honeywell SA-6 North
Chromium Remedy
Jersey City, New Jersey

Created By: T. Donovan 2/20/17
Checked By:

**TABLE 1. SA-6 NORTH OPEN SPACE CAP AREA - CONSTRUCTION CONTROL GRID AS BUILT SUMMARY**

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 686039.50 | 602096.13 | GRID_DGA | 10.64 | 10.56 | 1.29 | | 16.57 | 1.00 | | 6.02 |
| 2 | 686061.08 | 602108.76 | GRID_DGA | 10.58 | 10.52 | 1.29 | | 16.90 | 0.70 | | 6.37 |
| 3 | 686091.59 | 602155.60 | GRID | 11.36 | 11.29 | 1.23 | | 16.99 | | 2.57 | 5.70 |
| 4 | 686070.02 | 602142.97 | GRID_DGA | 10.84 | 10.76 | 1.16 | | 16.83 | 0.41 | | 6.07 |
| 5 | 686048.45 | 602130.34 | GRID | 10.56 | 10.57 | 1.18 | | 15.03 | | 0.52 | 4.47 |
| 6 | 686026.87 | 602117.70 | GRID | 10.91 | 10.98 | 1.12 | 0.75 | 15.07 | | 0.61 | 4.09 |
| 7 | 686005.30 | 602105.07 | GRID | 11.56 | 11.50 | 1.17 | 0.87 | 15.32 | | 0.65 | 3.82 |
| 8 | 685983.72 | 602092.44 | GRID | 11.61 | 11.63 | 1.19 | | 15.12 | | 0.67 | 3.49 |
| 9 | 685971.09 | 602114.02 | GRID | 11.86 | 11.83 | 1.25 | | 15.75 | | 0.69 | 3.92 |
| 10 | 685992.67 | 602126.65 | GRID | 11.77 | 11.80 | 1.13 | 0.55 | 16.19 | | 0.66 | 4.39 |
| 11 | 686014.24 | 602139.28 | GRID | 11.79 | 11.73 | 1.20 | 0.63 | 15.85 | | 0.68 | 4.12 |
| 12 | 686035.82 | 602151.91 | GRID | 11.71 | 11.64 | 1.24 | 0.83 | 15.55 | | 0.55 | 3.91 |
| 13 | 686057.39 | 602164.54 | GRID | 11.64 | 11.57 | 1.27 | | 15.73 | | 0.54 | 4.16 |
| 14 | 686078.96 | 602177.17 | GRID_DGA | 11.44 | 11.43 | 1.25 | | 17.54 | 0.82 | | 6.11 |
| 15 | 686066.33 | 602198.75 | GRID | 11.03 | 10.99 | 1.22 | | 15.83 | | 0.51 | 4.84 |
| 16 | 686044.76 | 602186.12 | GRID | 11.35 | 11.27 | 1.32 | | 15.74 | | 0.59 | 4.46 |
| 17 | 686023.18 | 602173.48 | GRID | 11.89 | 11.83 | 1.23 | 0.48 | 16.53 | | 0.87 | 4.70 |
| 18 | 686001.61 | 602160.85 | GRID | 14.57 | 14.50 | 1.22 | 0.53 | 16.84 | | 0.60 | 2.34 |
| 19 | 685980.04 | 602148.22 | GRID | 12.38 | 12.33 | 1.23 | 0.51 | 16.81 | | 0.67 | 4.48 |
| 20 | 685958.46 | 602135.59 | GRID | 12.13 | 12.08 | 1.26 | | 15.95 | | 0.58 | 3.87 |
| 21 | 685945.83 | 602157.16 | GRID | 12.44 | 12.39 | 1.20 | | 16.22 | | 0.61 | 3.83 |
| 22 | 685967.40 | 602169.80 | GRID | 12.81 | 12.77 | 1.14 | 0.65 | 17.17 | | 0.63 | 4.39 |
| 23 | 685988.98 | 602182.43 | GRID | 12.14 | 12.09 | 1.19 | 0.69 | 17.09 | | 0.69 | 5.01 |
| 24 | 686010.55 | 602195.06 | GRID | 14.47 | 14.42 | 1.23 | 0.49 | 16.71 | | 0.57 | 2.29 |
| 25 | 686032.13 | 602207.69 | GRID | 11.37 | 11.28 | 1.20 | | 15.45 | | 0.60 | 4.17 |
| 26 | 686053.70 | 602220.32 | GRID | 10.39 | 10.40 | 1.15 | | 15.50 | | 0.68 | 5.10 |
| 27 | 686041.07 | 602241.90 | GRID | 10.76 | 10.73 | 1.20 | | 15.16 | | 0.62 | 4.44 |
| 28 | 686019.49 | 602229.26 | GRID | 11.60 | 11.52 | 1.18 | | 15.47 | | 0.55 | 3.95 |
| 29 | 685997.92 | 602216.63 | GRID | 14.67 | 14.59 | 1.18 | 0.54 | 16.92 | | 0.60 | 2.32 |
| 30 | 685976.35 | 602204.00 | GRID | 12.32 | 12.25 | 1.23 | 0.81 | 17.43 | | 0.68 | 5.18 |
| 31 | 685954.77 | 602191.37 | GRID | 15.71 | 15.66 | 1.24 | 0.54 | 17.95 | | 0.51 | 2.29 |
| 32 | 685933.20 | 602178.74 | GRID | 12.68 | 12.64 | 1.15 | | 16.47 | | 0.62 | 3.83 |
| 33 | 685920.57 | 602200.31 | GRID | 12.83 | 12.78 | 1.26 | | 16.79 | | 0.58 | 4.00 |
| 34 | 685942.14 | 602212.94 | GRID | 15.17 | 15.22 | 1.14 | 0.53 | 17.48 | | 0.60 | 2.26 |
| 35 | 685985.29 | 602238.21 | GRID | 14.86 | 14.82 | 1.21 | 0.51 | 17.18 | | 0.64 | 2.35 |
| 36 | 686006.86 | 602250.84 | GRID | 11.98 | 12.02 | 1.18 | | 16.08 | | 0.93 | 4.06 |
| 37 | 686028.44 | 602263.47 | GRID | 11.27 | 11.24 | 1.23 | | 15.04 | | 0.56 | 3.80 |
| 38 | 686037.38 | 602297.68 | GRID | 12.00 | 11.92 | 1.18 | | 14.32 | | 0.53 | 2.40 |
| 39 | 686015.81 | 602285.04 | GRID | 11.49 | 11.43 | 1.24 | | 15.23 | | 0.63 | 3.80 |
| 40 | 685972.66 | 602259.78 | GRID | 15.08 | 15.02 | 1.14 | 0.61 | 17.36 | | 0.59 | 2.34 |
| 41 | 685951.08 | 602247.15 | GRID | 15.04 | 14.98 | 1.15 | 0.59 | 17.29 | | 0.57 | 2.31 |
| 42 | 685929.51 | 602234.52 | GRID | 12.86 | 12.82 | 1.20 | 0.58 | 17.48 | | 0.86 | 4.67 |
| 43 | 685907.93 | 602221.89 | GRID | 13.08 | 13.07 | 1.17 | | 17.13 | | 0.62 | 4.06 |
| 44 | 685895.30 | 602243.46 | GRID | 13.52 | 13.47 | 1.19 | | 17.24 | | 0.57 | 3.77 |
| 45 | 685916.88 | 602256.09 | GRID | 13.17 | 13.10 | 1.17 | 0.61 | 17.66 | | 0.69 | 4.56 |
| 46 | 685960.03 | 602281.36 | GRID | 15.36 | 15.32 | 1.14 | 0.58 | 17.66 | | 0.63 | 2.34 |
| 47 | 686003.17 | 602306.62 | GRID | 11.73 | 11.65 | 1.21 | | 15.60 | | 0.67 | 3.94 |
| 48 | 686024.75 | 602319.25 | GRID | 12.19 | 12.12 | 1.17 | | 14.66 | | 0.62 | 2.54 |
| 49 | 686012.12 | 602340.82 | GRID | 12.39 | 12.32 | 1.15 | | 14.94 | | 0.61 | 2.62 |
| 50 | 685990.54 | 602328.19 | GRID | 11.98 | 11.95 | 1.23 | | 15.86 | | 0.57 | 3.91 |
| 51 | 685968.97 | 602315.56 | GRID | 15.54 | 15.45 | 1.20 | 0.54 | 17.75 | | 0.56 | 2.29 |
| 52 | 685947.39 | 602302.93 | GRID | 15.65 | 15.59 | 1.19 | 0.55 | 17.91 | | 0.59 | 2.32 |
| 53 | 685925.82 | 602290.30 | GRID | 13.41 | 13.36 | 1.14 | 0.61 | 18.00 | | 0.81 | 4.64 |
| 54 | 685904.25 | 602277.67 | GRID | 14.31 | 14.30 | 1.13 | 0.60 | 17.89 | | 0.65 | 3.59 |
| 55 | 685882.67 | 602265.03 | GRID | 13.85 | 13.86 | 1.19 | | 17.46 | | 0.63 | 3.60 |
| 56 | 685870.04 | 602286.61 | GRID | 13.98 | 13.97 | 1.16 | | 17.23 | | 0.63 | 3.26 |
| 57 | 685891.61 | 602299.24 | GRID | 14.49 | 14.43 | 1.23 | 0.74 | 18.12 | | 0.60 | 3.69 |
| 58 | 685913.19 | 602311.87 | GRID | 13.72 | 13.67 | 1.15 | 0.78 | 18.28 | | 0.82 | 4.61 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 59 | 685956.34 | 602337.14 | GRID | 15.80 | 15.80 | 1.10 | 0.59 | 18.01 | | 0.52 | 2.21 |
| 60 | 685977.91 | 602349.77 | GRID | 12.23 | 12.30 | 1.10 | | 16.24 | | 0.66 | 3.94 |
| 61 | 685999.49 | 602362.40 | GRID | 12.58 | 12.53 | 1.16 | | 15.23 | | 0.57 | 2.70 |
| 62 | 685986.85 | 602383.97 | GRID | 12.78 | 12.70 | 1.18 | | 15.57 | | 0.66 | 2.87 |
| 63 | 685965.28 | 602371.34 | GRID | 12.56 | 12.56 | 1.14 | | 16.56 | | 0.68 | 4.00 |
| 64 | 685943.71 | 602358.71 | GRID | 13.58 | 13.65 | 1.08 | 0.78 | 18.09 | | 0.69 | 4.44 |
| 65 | 685900.56 | 602333.45 | GRID | 13.96 | 13.89 | 1.24 | 0.65 | 18.69 | | 0.97 | 4.80 |
| 66 | 685878.98 | 602320.81 | GRID | 14.75 | 14.69 | 1.19 | 0.54 | 18.60 | | 0.54 | 3.91 |
| 67 | 685866.35 | 602342.39 | GRID | 17.54 | 17.50 | 1.29 | 0.42 | 19.79 | | 0.57 | 2.28 |
| 68 | 685887.93 | 602355.02 | GRID | 16.72 | 16.69 | 1.18 | 0.50 | 19.13 | | 0.76 | 2.44 |
| 69 | 685909.50 | 602367.65 | GRID | 16.46 | 16.40 | 1.25 | 0.51 | 18.85 | | 0.70 | 2.45 |
| 70 | 685931.07 | 602380.28 | GRID | 13.75 | 13.66 | 1.23 | 0.69 | 18.14 | | 0.83 | 4.48 |
| 71 | 685952.65 | 602392.91 | GRID | 12.92 | 12.94 | 1.12 | | 16.85 | | 0.61 | 3.91 |
| 72 | 685974.22 | 602405.55 | GRID | 12.98 | 12.93 | 1.16 | | 15.89 | | 0.63 | 2.96 |
| 73 | 685961.59 | 602427.12 | GRID | 13.18 | 13.11 | 1.18 | | 16.16 | | 0.59 | 3.05 |
| 74 | 685940.02 | 602414.49 | GRID | 13.36 | 13.29 | 1.20 | | 17.26 | | 0.67 | 3.97 |
| 75 | 685918.44 | 602401.86 | GRID | 14.05 | 14.02 | 1.23 | 0.54 | 18.33 | | 0.73 | 4.31 |
| 76 | 685896.87 | 602389.23 | GRID | 16.74 | 16.67 | 1.30 | 0.43 | 19.19 | | 0.78 | 2.52 |
| 77 | 685875.29 | 602376.59 | GRID | 17.09 | 17.06 | 1.14 | 0.53 | 19.57 | | 0.84 | 2.51 |
| 78 | 685853.72 | 602363.96 | GRID | 17.76 | 17.72 | 1.13 | 0.59 | 20.29 | | 0.85 | 2.57 |
| 79 | 685832.15 | 602351.33 | GRID | 14.72 | 14.77 | 1.06 | | 18.51 | | 0.68 | 3.75 |
| 80 | 685819.51 | 602372.91 | GRID | 14.97 | 14.97 | 1.15 | | 18.71 | | 0.62 | 3.73 |
| 81 | 685841.09 | 602385.54 | GRID | 17.74 | 17.65 | 1.19 | 0.60 | 20.26 | | 0.81 | 2.61 |
| 82 | 685862.66 | 602398.17 | GRID | 17.23 | 17.16 | 1.25 | 0.52 | 19.81 | | 0.88 | 2.65 |
| 83 | 685884.24 | 602410.80 | GRID | 14.48 | 14.40 | 1.24 | 0.57 | 19.37 | | 0.79 | 4.96 |
| 84 | 685905.81 | 602423.43 | GRID | 14.24 | 14.19 | 1.19 | 0.58 | 18.79 | | 0.73 | 4.60 |
| 85 | 685927.39 | 602436.06 | GRID | 13.74 | 13.67 | 1.18 | | 17.55 | | 0.64 | 3.88 |
| 86 | 685948.96 | 602448.69 | GRID | 13.37 | 13.42 | 1.09 | | 16.57 | | 0.71 | 3.15 |
| 87 | 685936.33 | 602470.27 | GRID | 13.57 | 13.51 | 1.25 | | 16.83 | | 0.64 | 3.32 |
| 88 | 685914.75 | 602457.64 | GRID | 14.15 | 14.12 | 1.25 | | 17.96 | | 0.63 | 3.84 |
| 89 | 685893.18 | 602445.01 | GRID | 14.63 | 14.56 | 1.24 | 0.63 | 19.11 | | 0.62 | 4.55 |
| 90 | 685871.61 | 602432.37 | GRID | 14.76 | 14.70 | 1.17 | 0.63 | 19.70 | | 0.90 | 5.00 |
| 91 | 685828.46 | 602407.11 | GRID | 15.65 | 15.59 | 1.27 | 0.75 | 20.03 | | 0.84 | 4.45 |
| 92 | 685806.88 | 602394.48 | GRID | 15.23 | 15.20 | 1.23 | | 18.99 | | 0.71 | 3.79 |
| 93 | 685794.25 | 602416.05 | GRID | 15.45 | 15.41 | 1.22 | | 19.18 | | 0.57 | 3.77 |
| 94 | 685815.83 | 602428.69 | GRID | 15.80 | 15.71 | 1.25 | 0.54 | 20.34 | | 0.75 | 4.63 |
| 95 | 685837.40 | 602441.32 | GRID | 15.52 | 15.42 | 1.26 | 0.56 | 20.38 | | 0.91 | 4.96 |
| 96 | 685858.97 | 602453.95 | GRID | 15.04 | 14.98 | 1.22 | 0.55 | 19.91 | | 0.79 | 4.93 |
| 97 | 685880.55 | 602466.58 | GRID | 14.86 | 14.78 | 1.25 | 0.52 | 19.54 | | 0.69 | 4.76 |
| 98 | 685902.12 | 602479.21 | GRID | 14.72 | 14.65 | 1.30 | 0.48 | 18.74 | | 0.68 | 4.09 |
| 99 | 685923.70 | 602491.84 | GRID | 13.72 | 13.72 | 1.17 | | 17.22 | | 0.70 | 3.50 |
| 100 | 685889.49 | 602500.79 | GRID | 17.49 | 17.44 | 1.17 | 0.52 | 19.80 | | 0.67 | 2.37 |
| 101 | 685867.92 | 602488.15 | GRID | 15.14 | 15.07 | 1.23 | 0.56 | 19.94 | | 0.64 | 4.87 |
| 102 | 685846.34 | 602475.52 | GRID | 15.31 | 15.24 | 1.20 | 0.85 | 20.22 | | 0.67 | 4.98 |
| 103 | 685803.19 | 602450.26 | GRID | 18.93 | 18.84 | 1.17 | 0.58 | 21.16 | | 0.56 | 2.32 |
| 104 | 685781.62 | 602437.63 | GRID | 15.73 | 15.71 | 1.18 | | 19.45 | | 0.63 | 3.75 |
| 105 | 685768.99 | 602459.20 | GRID | 15.98 | 15.97 | 1.18 | | 19.68 | | 0.58 | 3.71 |
| 106 | 685812.14 | 602484.47 | GRID | 18.65 | 18.59 | 1.19 | 0.56 | 20.98 | | 0.65 | 2.39 |
| 107 | 685833.71 | 602497.10 | GRID | 18.09 | 18.02 | 1.17 | 0.59 | 20.44 | | 0.66 | 2.42 |
| 108 | 685855.28 | 602509.73 | GRID | 17.94 | 17.87 | 1.17 | 0.59 | 20.32 | | 0.69 | 2.45 |
| 109 | 685876.86 | 602522.36 | GRID | 17.80 | 17.73 | 1.18 | 0.59 | 20.19 | | 0.70 | 2.46 |
| 110 | 685898.43 | 602534.99 | GRID | 14.36 | 14.27 | 1.27 | | 18.20 | | 0.74 | 3.92 |
| 111 | 685885.80 | 602556.57 | GRID | 14.84 | 14.77 | 1.27 | | 18.68 | | 0.81 | 3.91 |
| 112 | 685864.23 | 602543.93 | GRID | 18.08 | 18.01 | 1.23 | 0.49 | 20.46 | | 0.73 | 2.45 |
| 113 | 685842.65 | 602531.30 | GRID | 18.20 | 18.14 | 1.16 | 0.59 | 20.57 | | 0.68 | 2.43 |
| 114 | 685821.08 | 602518.67 | GRID | 18.36 | 18.27 | 1.21 | 0.53 | 20.80 | | 0.78 | 2.53 |
| 115 | 685799.50 | 602506.04 | GRID | 18.79 | 18.74 | 1.16 | 0.59 | 21.07 | | 0.58 | 2.33 |
| 116 | 685756.36 | 602480.78 | GRID | 16.23 | 16.18 | 1.18 | | 19.89 | | 0.61 | 3.71 |
| 117 | 685743.73 | 602502.35 | GRID | 16.48 | 16.52 | 1.07 | | 20.07 | | 0.66 | 3.55 |
| 118 | 685765.30 | 602514.98 | GRID | 16.75 | 16.68 | 1.18 | 0.57 | 21.20 | | 0.86 | 4.53 |
| 119 | 685786.87 | 602527.61 | GRID | 18.94 | 18.88 | 1.17 | 0.57 | 21.29 | | 0.68 | 2.41 |
| 120 | 685808.45 | 602540.25 | GRID | 18.53 | 18.46 | 1.18 | 0.56 | 20.97 | | 0.77 | 2.51 |
| 121 | 685830.02 | 602552.88 | GRID | 18.33 | 18.27 | 1.19 | 0.56 | 20.79 | | 0.77 | 2.52 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 122 | 685873.17 | 602578.14 | GRID | 15.36 | 15.31 | 1.27 | | 19.10 | | 0.68 | 3.79 |
| 123 | 685894.74 | 602590.77 | GRID | 14.81 | 14.76 | 1.16 | | 17.23 | | 0.58 | 2.47 |
| 124 | 685882.11 | 602612.35 | GRID | 14.99 | 14.96 | 1.16 | | 17.79 | | 0.72 | 2.82 |
| 125 | 685860.54 | 602599.71 | GRID | 15.99 | 15.91 | 1.21 | 0.52 | 19.74 | | 0.83 | 3.82 |
| 126 | 685817.39 | 602574.45 | GRID | 18.44 | 18.37 | 1.27 | 0.49 | 20.87 | | 0.74 | 2.50 |
| 127 | 685774.24 | 602549.19 | GRID | 16.49 | 16.44 | 1.14 | 0.77 | 21.07 | | 0.80 | 4.63 |
| 128 | 685752.67 | 602536.56 | GRID | 16.85 | 16.79 | 1.15 | 0.60 | 21.32 | | 0.82 | 4.53 |
| 129 | 685731.09 | 602523.92 | GRID | 16.74 | 16.76 | 1.21 | | 20.13 | | 0.63 | 3.37 |
| 130 | 685718.46 | 602545.50 | GRID | 16.81 | 16.81 | 1.14 | | 19.98 | | 0.68 | 3.17 |
| 131 | 685740.04 | 602558.13 | GRID | 16.27 | 16.28 | 1.18 | 0.47 | 20.64 | | 0.65 | 4.36 |
| 132 | 685761.61 | 602570.76 | GRID | 15.94 | 15.88 | 1.16 | 0.56 | 19.95 | | 0.93 | 4.07 |
| 133 | 685783.18 | 602583.39 | GRID | 15.83 | 15.75 | 1.25 | 0.54 | 19.89 | | 0.94 | 4.14 |
| 134 | 685804.76 | 602596.02 | GRID | 15.84 | 15.76 | 1.19 | 0.56 | 19.94 | | 0.75 | 4.18 |
| 135 | 685826.33 | 602608.66 | GRID | 16.00 | 15.95 | 1.18 | 0.65 | 20.01 | | 0.66 | 4.07 |
| 136 | 685847.91 | 602621.29 | GRID | 16.26 | 16.20 | 1.16 | 0.63 | 20.06 | | 0.91 | 3.86 |
| 137 | 685869.48 | 602633.92 | GRID | 15.24 | 15.26 | 1.07 | | 18.13 | | 0.69 | 2.87 |
| 138 | 685856.85 | 602655.49 | GRID | 15.64 | 15.73 | 1.09 | | 18.55 | | 0.60 | 2.82 |
| 139 | 685792.13 | 602617.60 | GRID | 13.96 | 13.90 | 1.18 | | 18.18 | | 0.67 | 4.27 |
| 140 | 685770.55 | 602604.97 | GRID | 14.16 | 14.13 | 1.17 | | 18.11 | | 0.61 | 3.99 |
| 141 | 685748.98 | 602592.34 | GRID | 14.61 | 14.58 | 1.13 | | 18.18 | | 0.71 | 3.60 |
| 142 | 685727.40 | 602579.70 | GRID | 15.16 | 15.09 | 1.23 | | 19.11 | | 0.57 | 4.03 |
| 143 | 685705.83 | 602567.07 | GRID | 15.94 | 15.93 | 1.19 | | 19.61 | | 0.64 | 3.68 |
| 144 | 685693.20 | 602588.65 | GRID | 17.26 | 17.26 | 1.09 | | 21.18 | | 0.85 | 3.92 |
| 145 | 685714.77 | 602601.28 | GRID | 16.13 | 16.06 | 1.25 | 0.70 | 20.46 | | 0.86 | 4.41 |
| 146 | 685736.35 | 602613.91 | GRID | 15.75 | 15.67 | 1.33 | | 20.11 | | 0.72 | 4.44 |
| 147 | 685757.92 | 602626.54 | GRID | 15.41 | 15.49 | 1.16 | | 19.80 | | 0.90 | 4.31 |
| 148 | 685779.50 | 602639.17 | GRID | 15.25 | 15.26 | 1.08 | | 19.22 | | 0.72 | 3.96 |
| 149 | 685844.22 | 602677.07 | GRID | 13.32 | 13.36 | 1.20 | | 18.01 | | 0.55 | 4.65 |
| 150 | 685810.01 | 602686.01 | GRID | 16.70 | 16.61 | 1.18 | 0.61 | 20.57 | | 0.61 | 3.96 |
| 151 | 685788.44 | 602673.38 | GRID | 16.42 | 16.36 | 1.19 | 0.54 | 20.83 | | 0.79 | 4.47 |
| 152 | 685766.86 | 602660.75 | GRID | 16.43 | 16.35 | 1.20 | 0.62 | 21.13 | | 0.87 | 4.77 |
| 153 | 685723.72 | 602635.48 | GRID | 16.66 | 16.61 | 1.21 | 0.53 | 21.71 | | 0.72 | 5.10 |
| 154 | 685702.14 | 602622.85 | GRID | 17.06 | 16.98 | 1.21 | 0.59 | 21.93 | | 0.67 | 4.95 |
| 155 | 685680.57 | 602610.22 | GRID | 17.48 | 17.47 | 1.08 | | 21.48 | | 0.81 | 4.01 |
| 156 | 685667.94 | 602631.80 | GRID | 17.80 | 17.85 | 1.15 | | 21.64 | | 0.76 | 3.79 |
| 157 | 685689.51 | 602644.43 | GRID | 18.11 | 18.17 | 1.09 | 0.53 | 22.47 | | 0.58 | 4.30 |
| 158 | 685732.66 | 602669.69 | GRID | 19.97 | 20.01 | 1.14 | 0.52 | 22.22 | | 0.56 | 2.21 |
| 159 | 685797.38 | 602707.58 | GRID | 19.67 | 19.62 | 1.19 | 0.56 | 21.97 | | 0.59 | 2.35 |
| 160 | 685806.32 | 602741.79 | GRID | 17.62 | 17.35 | 1.22 | 0.56 | 21.91 | | 0.62 | 4.56 |
| 161 | 685784.75 | 602729.16 | GRID | 17.65 | 17.43 | 1.05 | 0.72 | 22.65 | | 0.55 | 5.21 |
| 162 | 685741.60 | 602703.90 | GRID | 20.85 | 20.87 | 1.10 | 0.56 | 23.17 | | 0.64 | 2.30 |
| 163 | 685720.03 | 602691.26 | GRID | 18.49 | 18.44 | 1.27 | 0.70 | 23.25 | | 0.79 | 4.81 |
| 164 | 685676.88 | 602666.00 | GRID | 18.69 | 18.78 | 1.04 | 0.56 | 22.74 | | 0.67 | 3.96 |
| 165 | 685655.30 | 602653.37 | GRID | 17.94 | 18.01 | 1.12 | | 21.74 | | 0.72 | 3.72 |
| 166 | 685642.67 | 602674.94 | GRID | 18.05 | 18.12 | 1.02 | | 21.84 | | 0.68 | 3.72 |
| 167 | 685664.25 | 602687.58 | GRID | 18.71 | 18.73 | 1.21 | 0.56 | 22.88 | | 0.73 | 4.15 |
| 168 | 685685.82 | 602700.21 | GRID | 20.99 | 21.08 | 1.11 | 0.48 | 23.42 | | 0.75 | 2.34 |
| 169 | 685750.54 | 602738.10 | GRID | 21.47 | 21.51 | 1.22 | 0.50 | 23.89 | | 0.74 | 2.38 |
| 170 | 685772.12 | 602750.73 | GRID | 18.51 | 18.43 | 1.34 | 0.67 | 23.26 | | 0.63 | 4.83 |
| 171 | 685824.21 | 602810.20 | GRID | 17.16 | 17.20 | 1.21 | | 20.85 | | 0.67 | 3.65 |
| 172 | 685759.49 | 602772.31 | GRID | 21.61 | 21.52 | 1.31 | 0.46 | 23.89 | | 0.61 | 2.37 |
| 173 | 685737.91 | 602759.68 | GRID | 21.92 | 21.90 | 1.25 | 0.47 | 24.19 | | 0.57 | 2.29 |
| 174 | 685716.34 | 602747.04 | GRID | 21.92 | 21.88 | 1.24 | 0.50 | 24.16 | | 0.54 | 2.28 |
| 175 | 685694.76 | 602734.41 | GRID | 21.52 | 21.60 | 1.01 | 0.62 | 23.88 | | 0.66 | 2.28 |
| 176 | 685673.19 | 602721.78 | GRID | 21.00 | 20.93 | 1.27 | 0.45 | 23.46 | | 0.81 | 2.53 |
| 177 | 685651.62 | 602709.15 | GRID | 18.72 | 18.72 | 1.16 | 0.54 | 22.89 | | 0.66 | 4.17 |
| 178 | 685630.04 | 602696.52 | GRID | 18.13 | 18.19 | 1.05 | | 22.02 | | 0.76 | 3.83 |
| 179 | 685617.41 | 602718.09 | GRID | 18.18 | 18.27 | 1.16 | | 22.00 | | 0.64 | 3.73 |
| 180 | 685638.98 | 602730.72 | GRID | 18.73 | 18.70 | 1.20 | 0.54 | 22.97 | | 0.69 | 4.26 |
| 181 | 685660.56 | 602743.36 | GRID | 21.00 | 21.00 | 1.24 | 0.45 | 23.51 | | 0.82 | 2.51 |
| 182 | 685682.13 | 602755.99 | GRID | 21.49 | 21.51 | 1.21 | 0.52 | 23.78 | | 0.56 | 2.28 |
| 183 | 685703.71 | 602768.62 | GRID | 22.02 | 22.02 | 1.17 | 0.53 | 24.25 | | 0.54 | 2.24 |
| 184 | 685725.28 | 602781.25 | GRID | 22.23 | 22.18 | 1.14 | 0.59 | 24.49 | | 0.60 | 2.32 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 185 | 685746.85 | 602793.88 | GRID | 22.14 | 22.15 | 1.17 | 0.51 | 24.45 | | 0.62 | 2.30 |
| 186 | 685768.43 | 602806.51 | GRID | 21.43 | 21.45 | 1.13 | 0.52 | 23.75 | | 0.65 | 2.30 |
| 187 | 685790.00 | 602819.14 | GRID | 17.88 | 17.86 | 1.16 | | 21.66 | | 0.65 | 3.81 |
| 188 | 685811.58 | 602831.78 | GRID | 17.43 | 17.42 | 1.27 | | 20.93 | | 0.59 | 3.51 |
| 189 | 685798.95 | 602853.35 | GRID | 17.64 | 17.66 | 1.14 | | 21.17 | | 0.55 | 3.50 |
| 190 | 685777.37 | 602840.72 | GRID | 18.26 | 18.34 | 1.17 | | 21.93 | | 0.57 | 3.59 |
| 191 | 685755.80 | 602828.09 | GRID | 21.84 | 21.86 | 1.17 | 0.51 | 24.29 | | 0.76 | 2.43 |
| 192 | 685734.22 | 602815.46 | GRID | 22.53 | 22.54 | 1.23 | 0.53 | 24.93 | | 0.71 | 2.38 |
| 193 | 685712.65 | 602802.82 | GRID | 20.06 | 20.06 | 1.22 | 0.46 | 24.83 | | 0.66 | 4.77 |
| 194 | 685691.07 | 602790.19 | GRID | 19.57 | 19.49 | 1.19 | 0.54 | 24.33 | | 0.67 | 4.84 |
| 195 | 685647.93 | 602764.93 | GRID | 21.00 | 20.99 | 1.20 | 0.52 | 23.46 | | 0.75 | 2.47 |
| 196 | 685626.35 | 602752.30 | GRID | 18.75 | 18.67 | 1.29 | 0.55 | 23.00 | | 0.71 | 4.33 |
| 197 | 685604.78 | 602739.67 | GRID | 18.21 | 18.20 | 1.12 | | 22.23 | | 0.84 | 4.02 |
| 198 | 685592.15 | 602761.24 | GRID | 18.21 | 18.22 | 1.15 | | 21.91 | | 0.56 | 3.70 |
| 199 | 685613.72 | 602773.87 | GRID | 18.75 | 18.67 | 1.26 | 0.53 | 22.95 | | 0.57 | 4.27 |
| 200 | 685635.30 | 602786.50 | GRID | 21.00 | 20.95 | 1.25 | 0.51 | 23.42 | | 0.71 | 2.47 |
| 201 | 685678.44 | 602811.77 | GRID | 19.56 | 19.58 | 1.11 | 0.70 | 24.31 | | 0.60 | 4.73 |
| 202 | 685700.02 | 602824.40 | GRID | 20.02 | 19.97 | 1.19 | 0.67 | 24.83 | | 0.62 | 4.86 |
| 203 | 685721.59 | 602837.03 | GRID | 22.65 | 22.67 | 1.18 | 0.51 | 24.87 | | 0.50 | 2.20 |
| 204 | 685743.17 | 602849.66 | GRID | 22.10 | 22.13 | 1.17 | 0.49 | 24.36 | | 0.57 | 2.22 |
| 205 | 685764.74 | 602862.29 | GRID | 18.85 | 18.77 | 1.17 | 0.63 | 22.28 | | 0.64 | 3.51 |
| 206 | 685786.31 | 602874.92 | GRID | 17.86 | 17.81 | 1.22 | | 21.39 | | 0.54 | 3.58 |
| 207 | 685773.68 | 602896.50 | GRID | 18.08 | 18.06 | 1.18 | | 21.86 | | 0.72 | 3.80 |
| 208 | 685752.11 | 602883.87 | GRID | 18.97 | 19.03 | 1.03 | 0.63 | 22.63 | | 0.66 | 3.60 |
| 209 | 685687.39 | 602845.97 | GRID | 20.02 | 20.00 | 1.15 | 0.57 | 24.57 | | 0.68 | 4.57 |
| 210 | 685665.81 | 602833.34 | GRID | 19.55 | 19.59 | 1.08 | 0.61 | 23.89 | | 0.65 | 4.30 |
| 211 | 685644.24 | 602820.71 | GRID | 19.05 | 19.05 | 1.14 | 0.58 | 23.39 | | 0.61 | 4.34 |
| 212 | 685622.66 | 602808.08 | GRID | 18.61 | 18.60 | 1.17 | 0.55 | 23.01 | | 0.67 | 4.41 |
| 213 | 685601.09 | 602795.45 | GRID | 18.75 | 18.71 | 1.27 | 0.52 | 22.84 | | 0.56 | 4.13 |
| 214 | 685579.52 | 602782.81 | GRID | 18.18 | 18.25 | 1.13 | | 21.89 | | 0.54 | 3.65 |
| 215 | 685566.88 | 602804.39 | GRID | 18.12 | 18.11 | 1.14 | | 21.85 | | 0.52 | 3.74 |
| 216 | 685588.46 | 602817.02 | GRID | 18.75 | 18.67 | 1.27 | 0.52 | 22.65 | | 0.62 | 3.98 |
| 217 | 685610.03 | 602829.65 | GRID | 18.59 | 18.50 | 1.18 | 0.60 | 22.81 | | 0.65 | 4.30 |
| 218 | 685631.61 | 602842.28 | GRID | 19.04 | 18.99 | 1.16 | 0.62 | 23.37 | | 0.95 | 4.38 |
| 219 | 685653.18 | 602854.91 | GRID | 19.53 | 19.55 | 1.07 | 0.62 | 23.89 | | 1.01 | 4.34 |
| 220 | 685674.75 | 602867.55 | GRID | 20.03 | 20.02 | 1.11 | 0.62 | 24.22 | | 0.84 | 4.20 |
| 221 | 685696.33 | 602880.18 | GRID | 20.18 | 20.16 | 1.11 | 0.60 | 24.47 | | 0.64 | 4.31 |
| 222 | 685717.90 | 602892.81 | GRID | 19.62 | 19.66 | 1.09 | 0.56 | 23.82 | | 0.90 | 4.16 |
| 223 | 685739.48 | 602905.44 | GRID | 19.01 | 18.92 | 1.19 | 0.63 | 22.64 | | 0.62 | 3.71 |
| 224 | 685761.05 | 602918.07 | GRID | 18.29 | 18.32 | 1.22 | | 22.24 | | 0.73 | 3.92 |
| 225 | 685748.42 | 602939.65 | GRID | 18.43 | 18.47 | 1.18 | | 22.39 | | 0.71 | 3.92 |
| 226 | 685726.85 | 602927.02 | GRID | 19.03 | 18.97 | 1.26 | 0.55 | 22.88 | | 0.58 | 3.91 |
| 227 | 685705.27 | 602914.38 | GRID | 19.61 | 19.53 | 1.16 | 0.66 | 23.04 | | 0.57 | 3.52 |
| 228 | 685683.70 | 602901.75 | GRID | 20.20 | 20.13 | 1.22 | 0.57 | 23.81 | | 0.59 | 3.67 |
| 229 | 685662.12 | 602889.12 | GRID | 20.02 | 20.02 | 1.15 | 0.54 | 23.49 | | 0.65 | 3.47 |
| 230 | 685640.55 | 602876.49 | GRID | 19.52 | 19.54 | 1.14 | 0.54 | 23.07 | | 0.66 | 3.53 |
| 231 | 685618.97 | 602863.86 | GRID | 19.03 | 19.08 | 1.10 | 0.56 | 22.81 | | 0.61 | 3.73 |
| 232 | 685597.40 | 602851.23 | GRID | 18.60 | 18.59 | 1.11 | 0.62 | 22.68 | | 0.70 | 4.09 |
| 233 | 685575.83 | 602838.59 | GRID | 18.78 | 18.75 | 1.20 | 0.54 | 22.55 | | 0.64 | 3.80 |
| 234 | 685554.25 | 602825.96 | GRID | 17.97 | 18.06 | 1.16 | | 21.75 | | 0.59 | 3.69 |
| 235 | 685541.62 | 602847.54 | GRID | 17.86 | 17.92 | 1.18 | | 21.67 | | 0.58 | 3.74 |
| 236 | 685563.19 | 602860.17 | GRID | 18.75 | 18.66 | 1.27 | 0.61 | 22.39 | | 0.53 | 3.73 |
| 237 | 685584.77 | 602872.80 | GRID | 18.60 | 18.60 | 1.09 | 0.64 | 22.51 | | 0.56 | 3.92 |
| 238 | 685606.34 | 602885.43 | GRID | 19.02 | 19.02 | 1.18 | 0.54 | 22.58 | | 0.55 | 3.57 |
| 239 | 685627.92 | 602898.06 | GRID | 19.51 | 19.52 | 1.14 | 0.61 | 22.83 | | 0.51 | 3.31 |
| 240 | 685649.49 | 602910.69 | GRID | 20.01 | 19.95 | 1.23 | 0.57 | 23.11 | | 0.55 | 3.16 |
| 241 | 685671.07 | 602923.33 | GRID | 20.18 | 20.20 | 1.17 | 0.58 | 23.31 | | 0.59 | 3.11 |
| 242 | 685692.64 | 602935.96 | GRID | 19.60 | 19.59 | 1.13 | 0.62 | 23.05 | | 0.64 | 3.46 |
| 243 | 685714.21 | 602948.59 | GRID | 19.04 | 19.00 | 1.26 | 0.48 | 22.87 | | 0.62 | 3.87 |
| 244 | 685735.79 | 602961.22 | GRID | 18.51 | 18.49 | 1.21 | | 22.43 | | 0.66 | 3.94 |
| 245 | 685723.16 | 602982.80 | GRID | 18.53 | 18.52 | 1.20 | | 22.36 | | 0.62 | 3.83 |
| 246 | 685701.58 | 602970.16 | GRID | 19.05 | 19.08 | 1.18 | 0.51 | 22.78 | | 0.67 | 3.70 |
| 247 | 685680.01 | 602957.53 | GRID | 19.58 | 19.55 | 1.26 | 0.46 | 22.76 | | 0.61 | 3.21 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 248 | 685658.43 | 602944.90 | GRID | 20.16 | 20.15 | 1.14 | 0.64 | 23.30 | | 0.62 | 3.15 |
| 249 | 685636.86 | 602932.27 | GRID | 20.00 | 19.94 | 1.15 | 0.65 | 23.22 | | 0.57 | 3.28 |
| 250 | 685615.29 | 602919.64 | GRID | 19.50 | 19.56 | 1.04 | 0.62 | 22.98 | | 0.57 | 3.41 |
| 251 | 685593.71 | 602907.01 | GRID | 19.00 | 19.07 | 1.07 | 0.56 | 22.73 | | 0.53 | 3.66 |
| 252 | 685572.14 | 602894.37 | GRID | 18.60 | 18.55 | 1.18 | 0.59 | 22.38 | | 0.61 | 3.82 |
| 253 | 685550.56 | 602881.74 | GRID | 18.57 | 18.55 | 1.17 | 0.58 | 22.21 | | 0.56 | 3.67 |
| 254 | 685528.99 | 602869.11 | GRID | 17.73 | 17.73 | 1.24 | | 21.45 | | 0.56 | 3.72 |
| 255 | 685516.36 | 602890.69 | GRID | 17.57 | 17.61 | 1.18 | | 21.36 | | 0.58 | 3.75 |
| 256 | 685537.93 | 602903.32 | GRID | 18.58 | 18.49 | 1.27 | 0.67 | 22.17 | | 0.58 | 3.68 |
| 257 | 685559.51 | 602915.95 | GRID | 18.68 | 18.65 | 1.14 | 0.72 | 22.56 | | 0.49 | 3.91 |
| 258 | 685581.08 | 602928.58 | GRID | 18.99 | 19.05 | 1.07 | 0.65 | 22.95 | | 0.54 | 3.90 |
| 259 | 685602.65 | 602941.21 | GRID | 19.49 | 19.53 | 1.16 | 0.52 | 23.23 | | 0.58 | 3.70 |
| 260 | 685624.23 | 602953.84 | GRID | 19.99 | 19.97 | 1.15 | 0.67 | 23.40 | | 0.70 | 3.43 |
| 261 | 685645.80 | 602966.47 | GRID | 20.13 | 20.16 | 1.16 | 0.61 | 23.41 | | 0.62 | 3.25 |
| 262 | 685667.38 | 602979.11 | GRID | 19.53 | 19.53 | 1.20 | 0.55 | 23.08 | | 0.72 | 3.56 |
| 263 | 685688.95 | 602991.74 | GRID | 18.81 | 18.76 | 1.29 | 0.58 | 22.42 | | 0.69 | 3.66 |
| 264 | 685710.53 | 603004.37 | GRID | 18.48 | 18.54 | 1.20 | | 22.05 | | 0.61 | 3.52 |
| 265 | 685697.89 | 603025.94 | GRID | 18.39 | 18.48 | 1.15 | | 21.70 | | 0.65 | 3.21 |
| 266 | 685676.32 | 603013.31 | GRID | 18.59 | 18.54 | 1.24 | | 22.15 | | 0.68 | 3.61 |
| 267 | 685654.75 | 603000.68 | GRID | 19.51 | 19.51 | 1.11 | 0.63 | 23.71 | | 0.80 | 4.20 |
| 268 | 685633.17 | 602988.05 | GRID | 20.07 | 20.03 | 1.18 | 0.58 | 23.65 | | 0.66 | 3.62 |
| 269 | 685611.60 | 602975.42 | GRID | 19.98 | 20.00 | 1.15 | 0.52 | 23.63 | | 0.65 | 3.63 |
| 270 | 685590.02 | 602962.79 | GRID | 19.48 | 19.52 | 1.12 | 0.60 | 23.57 | | 0.61 | 4.05 |
| 271 | 685568.45 | 602950.15 | GRID | 18.98 | 19.04 | 1.16 | 0.48 | 23.24 | | 0.62 | 4.20 |
| 272 | 685546.87 | 602937.52 | GRID | 18.57 | 18.63 | 1.18 | 0.53 | 22.96 | | 0.60 | 4.33 |
| 273 | 685525.30 | 602924.89 | GRID | 18.12 | 18.05 | 1.24 | 0.55 | 22.50 | | 0.61 | 4.44 |
| 274 | 685503.73 | 602912.26 | GRID | 17.38 | 17.44 | 1.17 | | 21.14 | | 0.59 | 3.70 |
| 275 | 685491.09 | 602933.83 | GRID | 17.19 | 17.24 | 1.18 | | 20.90 | | 0.54 | 3.67 |
| 276 | 685512.67 | 602946.47 | GRID | 18.19 | 18.22 | 1.05 | 0.63 | 22.50 | | 0.59 | 4.28 |
| 277 | 685577.39 | 602984.36 | GRID | 19.47 | 19.48 | 1.15 | 0.66 | 23.74 | | 0.70 | 4.26 |
| 278 | 685598.97 | 602996.99 | GRID | 19.97 | 19.91 | 1.32 | 0.46 | 23.71 | | 0.69 | 3.81 |
| 279 | 685620.54 | 603009.62 | GRID | 20.05 | 20.01 | 1.18 | 0.56 | 23.56 | | 0.70 | 3.55 |
| 280 | 685642.11 | 603022.25 | GRID | 19.44 | 19.50 | 1.18 | 0.52 | 24.00 | | 0.71 | 4.51 |
| 281 | 685663.69 | 603034.89 | GRID | 18.20 | 18.22 | 1.19 | | 21.70 | | 0.67 | 3.49 |
| 282 | 685685.26 | 603047.52 | GRID | 18.26 | 18.32 | 1.18 | | 21.37 | | 0.65 | 3.05 |
| 283 | 685672.63 | 603069.09 | GRID | 18.07 | 18.12 | 1.10 | | 21.01 | | 0.67 | 2.89 |
| 284 | 685651.06 | 603056.46 | GRID | 17.94 | 18.00 | 1.20 | | 21.31 | | 0.71 | 3.31 |
| 285 | 685629.48 | 603043.83 | GRID | 21.67 | 21.65 | 1.15 | 0.59 | 23.96 | | 0.57 | 2.31 |
| 286 | 685607.91 | 603031.20 | GRID | 19.79 | 19.81 | 1.16 | 0.55 | 23.88 | | 0.66 | 4.08 |
| 287 | 685586.33 | 603018.57 | GRID | 19.85 | 19.83 | 1.19 | 0.56 | 23.94 | | 0.72 | 4.11 |
| 288 | 685564.76 | 603005.93 | GRID | 19.33 | 19.42 | 1.09 | 0.53 | 23.90 | | 0.66 | 4.48 |
| 289 | 685543.19 | 602993.30 | GRID | 21.46 | 21.49 | 1.14 | 0.54 | 23.78 | | 0.61 | 2.29 |
| 290 | 685521.61 | 602980.67 | GRID | 21.01 | 20.97 | 1.15 | 0.58 | 23.40 | | 0.70 | 2.43 |
| 291 | 685478.46 | 602955.41 | GRID | 16.94 | 16.99 | 1.09 | | 20.68 | | 0.67 | 3.69 |
| 292 | 685500.04 | 602968.04 | GRID | 18.02 | 18.05 | 1.17 | 0.51 | 22.43 | | 0.65 | 4.38 |
| 293 | 685465.83 | 602976.98 | GRID | 16.69 | 16.75 | 1.09 | | 20.41 | | 0.65 | 3.66 |
| 294 | 685487.41 | 602989.61 | GRID | 17.82 | 17.88 | 1.14 | 0.53 | 22.22 | | 0.78 | 4.33 |
| 295 | 685508.98 | 603002.25 | GRID | 20.83 | 20.90 | 1.04 | 0.59 | 23.15 | | 0.62 | 2.25 |
| 296 | 685552.13 | 603027.51 | GRID | 18.92 | 18.95 | 1.13 | 0.58 | 23.44 | | 0.71 | 4.49 |
| 297 | 685573.70 | 603040.14 | GRID | 18.91 | 18.96 | 1.08 | 0.58 | 23.47 | | 0.64 | 4.50 |
| 298 | 685595.28 | 603052.77 | GRID | 21.38 | 21.34 | 1.21 | 0.54 | 23.71 | | 0.62 | 2.37 |
| 299 | 685616.85 | 603065.40 | GRID | 21.23 | 21.26 | 1.10 | 0.56 | 23.65 | | 0.73 | 2.39 |
| 300 | 685638.42 | 603078.03 | GRID | 17.74 | 17.70 | 1.28 | | 21.13 | | 0.62 | 3.43 |
| 301 | 685660.00 | 603090.67 | GRID | 17.82 | 17.89 | 1.10 | | 20.67 | | 0.62 | 2.78 |
| 302 | 685647.37 | 603112.24 | GRID | 17.52 | 17.44 | 1.30 | | 20.57 | | 0.70 | 3.13 |
| 303 | 685625.79 | 603099.61 | GRID | 17.29 | 17.27 | 1.14 | | 20.86 | | 0.60 | 3.59 |
| 304 | 685604.22 | 603086.98 | GRID | 17.92 | 17.88 | 1.18 | 0.61 | 22.29 | | 0.53 | 4.42 |
| 305 | 685582.64 | 603074.35 | GRID | 20.50 | 20.54 | 1.09 | 0.57 | 22.88 | | 0.68 | 2.34 |
| 306 | 685561.07 | 603061.71 | GRID | 18.31 | 18.36 | 1.10 | 0.83 | 22.76 | | 0.60 | 4.40 |
| 307 | 685539.50 | 603049.08 | GRID | 18.46 | 18.49 | 1.22 | 0.72 | 22.81 | | 0.71 | 4.33 |
| 308 | 685517.92 | 603036.45 | GRID | 18.40 | 18.48 | 1.06 | 0.83 | 23.26 | | 0.72 | 4.77 |
| 309 | 685496.35 | 603023.82 | GRID | 20.47 | 20.49 | 1.09 | 0.59 | 22.74 | | 0.57 | 2.25 |
| 310 | 685474.77 | 603011.19 | GRID | 17.50 | 17.54 | 1.12 | 0.54 | 21.76 | | 0.60 | 4.22 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 311 | 685453.20 | 602998.56 | GRID | 16.44 | 16.51 | 1.05 | | 20.17 | | 0.67 | 3.66 |
| 312 | 685440.57 | 603020.13 | GRID | 16.19 | 16.28 | 1.12 | | 19.91 | | 0.62 | 3.63 |
| 313 | 685462.14 | 603032.76 | GRID | 16.99 | 17.04 | 1.02 | 0.68 | 21.69 | | 0.69 | 4.65 |
| 314 | 685483.72 | 603045.39 | GRID | 19.75 | 19.79 | 1.17 | 0.48 | 22.02 | | 0.58 | 2.23 |
| 315 | 685526.87 | 603070.66 | GRID | 19.88 | 19.90 | 1.08 | 0.61 | 22.23 | | 0.65 | 2.33 |
| 316 | 685548.44 | 603083.29 | GRID | 19.69 | 19.78 | 0.99 | 0.64 | 21.96 | | 0.56 | 2.18 |
| 317 | 685570.01 | 603095.92 | GRID | 19.49 | 19.54 | 1.14 | 0.50 | 21.91 | | 0.72 | 2.36 |
| 318 | 685591.59 | 603108.55 | GRID | 17.02 | 17.04 | 1.08 | 0.66 | 21.59 | | 0.55 | 4.55 |
| 319 | 685613.16 | 603121.18 | GRID | 16.87 | 16.87 | 1.16 | | 20.18 | | 0.66 | 3.30 |
| 320 | 685634.74 | 603133.81 | GRID | 17.16 | 17.10 | 1.27 | | 19.80 | | 0.59 | 2.70 |
| 321 | 685622.10 | 603155.39 | GRID | 16.90 | 16.93 | 1.10 | | 19.32 | | 0.58 | 2.39 |
| 322 | 685600.53 | 603142.76 | GRID | 16.40 | 16.47 | 1.19 | | 19.83 | | 0.65 | 3.36 |
| 323 | 685578.96 | 603130.13 | GRID | 18.86 | 18.83 | 1.23 | 0.53 | 21.21 | | 0.63 | 2.39 |
| 324 | 685557.38 | 603117.49 | GRID | 18.63 | 18.71 | 1.11 | 0.52 | 21.10 | | 0.76 | 2.39 |
| 325 | 685535.81 | 603104.86 | GRID | 18.73 | 18.80 | 1.08 | 0.55 | 21.08 | | 0.64 | 2.27 |
| 326 | 685514.23 | 603092.23 | GRID | 18.91 | 18.91 | 1.14 | 0.55 | 21.21 | | 0.61 | 2.31 |
| 327 | 685492.66 | 603079.60 | GRID | 16.60 | 16.67 | 1.06 | 0.92 | 21.35 | | 0.65 | 4.68 |
| 328 | 685449.51 | 603054.34 | GRID | 19.10 | 19.10 | 1.12 | 0.58 | 21.41 | | 0.60 | 2.31 |
| 329 | 685427.94 | 603041.70 | GRID | 15.94 | 16.04 | 1.10 | | 19.65 | | 0.57 | 3.62 |
| 330 | 685415.31 | 603063.28 | GRID | 15.66 | 15.72 | 1.14 | | 19.41 | | 0.59 | 3.70 |
| 331 | 685436.88 | 603075.91 | GRID | 15.90 | 15.85 | 1.17 | 0.62 | 20.35 | | 0.65 | 4.50 |
| 332 | 685458.45 | 603088.54 | GRID | 15.67 | 15.68 | 1.16 | 0.55 | 20.28 | | 0.65 | 4.60 |
| 333 | 685480.03 | 603101.17 | GRID | 15.16 | 15.20 | 1.11 | 0.77 | 20.14 | | 0.65 | 4.94 |
| 334 | 685501.60 | 603113.80 | GRID | 15.10 | 15.19 | 1.06 | 0.57 | 20.00 | | 0.69 | 4.81 |
| 335 | 685523.18 | 603126.44 | GRID | 14.95 | 15.03 | 1.12 | 0.53 | 19.78 | | 0.68 | 4.75 |
| 336 | 685544.75 | 603139.07 | GRID | 15.14 | 15.18 | 1.13 | 0.51 | 19.47 | | 0.57 | 4.29 |
| 337 | 685566.32 | 603151.70 | GRID | 15.78 | 15.87 | 1.08 | 0.54 | 19.38 | | 0.74 | 3.51 |
| 338 | 685587.90 | 603164.33 | GRID | 15.43 | 15.46 | 1.20 | | 19.03 | | 0.57 | 3.56 |
| 339 | 685609.47 | 603176.96 | GRID | 16.50 | 16.59 | 1.12 | | 18.78 | | 0.61 | 2.19 |
| 340 | 685575.27 | 603185.91 | GRID | 11.80 | 11.78 | 1.21 | | 18.59 | | 0.68 | 6.81 |
| 341 | 685553.69 | 603173.27 | GRID | 10.42 | 10.51 | 1.05 | | 18.71 | | 0.63 | 8.20 |
| 342 | 685532.12 | 603160.64 | GRID | 10.09 | 10.04 | 1.26 | | 18.52 | | 0.54 | 8.48 |
| 343 | 685510.54 | 603148.01 | GRID | 9.91 | 9.94 | 1.19 | | 18.02 | | 0.54 | 8.08 |
| 344 | 685424.25 | 603097.48 | GRID | 15.09 | 15.16 | 1.16 | 0.71 | 19.17 | | 0.52 | 4.01 |
| 345 | 685390.04 | 603106.43 | GRID | 9.11 | 9.08 | 1.20 | | 17.78 | | 0.62 | 8.70 |
| 346 | 685411.62 | 603119.06 | GRID | 9.24 | 9.17 | 1.30 | | 17.72 | | 0.60 | 8.55 |
| 347 | 685433.19 | 603131.69 | GRID | 9.37 | 9.32 | 1.26 | | 17.70 | | 0.51 | 8.38 |
| 348 | 685454.76 | 603144.32 | GRID | 9.49 | 9.45 | 1.28 | | 17.79 | | 0.59 | 8.34 |
| 349 | 685476.34 | 603156.95 | GRID | 9.62 | 9.59 | 1.28 | | 17.87 | | 0.55 | 8.29 |
| 350 | 685497.91 | 603169.58 | GRID | 13.21 | 13.26 | 1.15 | | 17.94 | | 0.57 | 4.68 |
| 351 | 685519.49 | 603182.22 | GRID | 13.84 | 13.87 | 1.20 | | 18.13 | | 0.64 | 4.26 |
| 352 | 685541.06 | 603194.85 | GRID | 14.19 | 14.20 | 1.17 | | 18.37 | | 0.56 | 4.17 |
| 353 | 685562.64 | 603207.48 | GRID | 14.90 | 14.90 | 1.12 | | 18.16 | | 0.61 | 3.26 |
| 354 | 685584.21 | 603220.11 | GRID | 15.51 | 15.46 | 1.16 | | 18.14 | | 0.51 | 2.68 |
| 355 | 685571.58 | 603241.69 | GRID | 14.54 | 14.49 | 1.21 | | 17.48 | | 0.62 | 2.99 |
| 356 | 685550.00 | 603229.05 | GRID | 14.29 | 14.32 | 1.08 | | 17.75 | | 0.63 | 3.43 |
| 357 | 685506.86 | 603203.79 | GRID | 17.07 | 17.10 | 1.16 | 0.54 | 19.42 | | 0.63 | 2.33 |
| 358 | 685485.28 | 603191.16 | GRID | 14.88 | 14.82 | 1.24 | 0.62 | 18.75 | | 0.49 | 3.92 |
| 359 | 685442.13 | 603165.90 | GRID | 14.41 | 14.50 | 1.10 | 0.58 | 18.22 | | 0.75 | 3.72 |
| 360 | 685377.41 | 603128.00 | GRID | 9.11 | 9.04 | 1.27 | | 17.75 | | 0.56 | 8.71 |
| 361 | 685364.78 | 603149.58 | GRID | 14.69 | 14.63 | 1.25 | | 18.19 | | 0.73 | 3.56 |
| 362 | 685386.35 | 603162.21 | GRID | 15.08 | 15.09 | 1.17 | 0.55 | 19.17 | | 0.77 | 4.07 |
| 363 | 685407.93 | 603174.84 | GRID | 14.79 | 14.82 | 1.15 | 0.55 | 19.03 | | 0.64 | 4.21 |
| 364 | 685429.50 | 603187.47 | GRID | 14.89 | 14.90 | 1.13 | 0.57 | 18.89 | | 0.67 | 3.98 |
| 365 | 685451.08 | 603200.10 | GRID | 14.75 | 14.77 | 1.07 | 0.63 | 18.85 | | 0.69 | 4.08 |
| 366 | 685494.22 | 603225.36 | GRID | 17.09 | 17.11 | 1.15 | 0.53 | 19.31 | | 0.52 | 2.20 |
| 367 | 685515.80 | 603238.00 | GRID | 14.00 | 14.03 | 1.21 | | 18.43 | | 0.99 | 4.40 |
| 368 | 685537.37 | 603250.63 | GRID | 13.80 | 13.75 | 1.13 | | 17.51 | | 0.66 | 3.76 |
| 369 | 685524.74 | 603272.20 | GRID | 13.13 | 13.21 | 1.10 | | 16.32 | | 0.62 | 3.10 |
| 370 | 685503.17 | 603259.57 | GRID | 13.26 | 13.29 | 1.20 | | 16.69 | | 0.54 | 3.41 |
| 371 | 685481.59 | 603246.94 | GRID | 14.00 | 14.07 | 1.10 | 0.54 | 18.04 | | 0.49 | 3.97 |
| 372 | 685460.02 | 603234.31 | GRID | 14.22 | 14.25 | 1.13 | 0.57 | 18.97 | | 0.65 | 4.71 |
| 373 | 685438.44 | 603221.68 | GRID | 16.96 | 16.94 | 1.11 | 0.63 | 19.23 | | 0.56 | 2.30 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 374 | 685416.87 | 603209.04 | GRID | 17.23 | 17.16 | 1.16 | 0.60 | 19.58 | | 0.66 | 2.42 |
| 375 | 685395.30 | 603196.41 | GRID | 17.44 | 17.36 | 1.17 | 0.62 | 19.67 | | 0.52 | 2.31 |
| 376 | 685373.72 | 603183.78 | GRID | 17.69 | 17.60 | 1.19 | 0.61 | 19.94 | | 0.53 | 2.33 |
| 377 | 685352.15 | 603171.15 | GRID | 14.44 | 14.39 | 1.30 | | 17.86 | | 0.62 | 3.47 |
| 378 | 685339.52 | 603192.72 | GRID | 14.19 | 14.22 | 1.20 | | 17.58 | | 0.63 | 3.36 |
| 379 | 685361.09 | 603205.36 | GRID | 17.42 | 17.33 | 1.22 | 0.57 | 19.70 | | 0.57 | 2.36 |
| 380 | 685382.66 | 603217.99 | GRID | 17.12 | 17.06 | 1.21 | 0.57 | 19.46 | | 0.62 | 2.40 |
| 381 | 685404.24 | 603230.62 | GRID | 16.85 | 16.77 | 1.23 | 0.54 | 19.11 | | 0.58 | 2.34 |
| 382 | 685425.81 | 603243.25 | GRID | 16.59 | 16.52 | 1.21 | 0.55 | 18.85 | | 0.58 | 2.33 |
| 383 | 685447.39 | 603255.88 | GRID | 13.76 | 13.72 | 1.28 | 0.48 | 17.80 | | 0.70 | 4.08 |
| 384 | 685468.96 | 603268.51 | GRID | 13.36 | 13.40 | 1.11 | 0.59 | 16.81 | | 0.62 | 3.41 |
| 385 | 685490.54 | 603281.14 | GRID | 12.45 | 12.36 | 1.23 | | 15.82 | | 0.53 | 3.46 |
| 386 | 685512.11 | 603293.78 | GRID | 12.49 | 12.58 | 1.07 | | 15.66 | | 0.65 | 3.07 |
| 387 | 685477.90 | 603302.72 | GRID | 7.40 | 7.37 | 1.23 | | 14.99 | | 0.54 | 7.62 |
| 388 | 685456.33 | 603290.09 | GRID | 12.77 | 12.68 | 1.32 | 0.46 | 16.15 | | 0.55 | 3.46 |
| 389 | 685434.76 | 603277.46 | GRID | 13.24 | 13.20 | 1.17 | 0.58 | 17.27 | | 0.55 | 4.07 |
| 390 | 685413.18 | 603264.82 | GRID | 16.13 | 16.05 | 1.24 | 0.58 | 18.35 | | 0.47 | 2.29 |
| 391 | 685391.61 | 603252.19 | GRID | 16.40 | 16.31 | 1.27 | 0.54 | 18.62 | | 0.50 | 2.31 |
| 392 | 685326.88 | 603214.30 | GRID | 13.94 | 13.90 | 1.19 | | 17.30 | | 0.62 | 3.40 |
| 393 | 685314.25 | 603235.87 | GRID | 13.69 | 13.71 | 1.24 | | 17.06 | | 0.61 | 3.36 |
| 394 | 685335.83 | 603248.50 | GRID | 14.18 | 14.11 | 1.23 | 0.57 | 18.41 | | 0.63 | 4.30 |
| 395 | 685357.40 | 603261.14 | GRID | 13.68 | 13.60 | 1.26 | 0.51 | 18.45 | | 0.71 | 4.86 |
| 396 | 685378.98 | 603273.77 | GRID | 13.32 | 13.25 | 1.28 | 0.50 | 18.05 | | 0.65 | 4.80 |
| 397 | 685400.55 | 603286.40 | GRID | 12.97 | 12.94 | 1.21 | 0.53 | 17.47 | | 0.50 | 4.53 |
| 398 | 685422.12 | 603299.03 | GRID | 12.59 | 12.50 | 1.29 | 0.51 | 16.80 | | 0.61 | 4.30 |
| 399 | 685443.70 | 603311.66 | GRID | 12.10 | 12.12 | 1.22 | 0.49 | 15.51 | | 0.53 | 3.39 |
| 400 | 685465.27 | 603324.29 | GRID | 11.00 | 10.96 | 1.20 | | 14.66 | | 0.59 | 3.69 |
| 401 | 685486.85 | 603336.92 | GRID | 11.45 | 11.40 | 1.24 | | 14.24 | | 0.65 | 2.84 |
| 402 | 685474.21 | 603358.50 | GRID | 10.92 | 10.83 | 1.20 | | 13.33 | | 0.61 | 2.50 |
| 403 | 685452.64 | 603345.87 | GRID | 10.40 | 10.37 | 1.12 | | 13.85 | | 0.59 | 3.48 |
| 404 | 685431.07 | 603333.24 | GRID | 11.39 | 11.37 | 1.29 | 0.46 | 14.72 | | 0.54 | 3.35 |
| 405 | 685409.49 | 603320.60 | GRID | 11.85 | 11.87 | 1.17 | 0.55 | 16.33 | | 0.56 | 4.46 |
| 406 | 685387.92 | 603307.97 | GRID | 12.26 | 12.26 | 1.18 | 0.56 | 16.82 | | 0.56 | 4.56 |
| 407 | 685366.34 | 603295.34 | GRID | 15.15 | 15.09 | 1.32 | 0.46 | 17.37 | | 0.50 | 2.28 |
| 408 | 685344.77 | 603282.71 | GRID | 15.58 | 15.48 | 1.29 | 0.50 | 17.82 | | 0.55 | 2.33 |
| 409 | 685323.20 | 603270.08 | GRID | 16.36 | 16.28 | 1.30 | 0.50 | 18.60 | | 0.53 | 2.33 |
| 410 | 685301.62 | 603257.45 | GRID | 13.44 | 13.46 | 1.19 | | 16.84 | | 0.63 | 3.38 |
| 411 | 685288.99 | 603279.02 | GRID | 13.27 | 13.22 | 1.29 | | 16.60 | | 0.56 | 3.38 |
| 412 | 685310.56 | 603291.65 | GRID | 15.99 | 15.93 | 1.20 | 0.55 | 18.33 | | 0.64 | 2.40 |
| 413 | 685332.14 | 603304.28 | GRID | 15.20 | 15.15 | 1.22 | 0.53 | 17.49 | | 0.59 | 2.34 |
| 414 | 685353.71 | 603316.92 | GRID | 14.55 | 14.59 | 1.14 | 0.52 | 16.77 | | 0.52 | 2.18 |
| 415 | 685375.29 | 603329.55 | GRID | 11.61 | 11.55 | 1.26 | 0.54 | 16.21 | | 0.56 | 4.65 |
| 416 | 685440.01 | 603367.44 | GRID | 9.82 | 9.82 | 1.15 | | 13.22 | | 0.65 | 3.40 |
| 417 | 685461.58 | 603380.07 | GRID | 10.40 | 10.43 | 1.05 | | 12.66 | | 0.54 | 2.23 |
| 418 | 685427.38 | 603389.02 | GRID | 9.30 | 9.32 | 1.13 | | 12.50 | | 0.60 | 3.18 |
| 419 | 685405.80 | 603376.38 | GRID | 9.77 | 9.72 | 1.25 | | 13.12 | | 0.65 | 3.40 |
| 420 | 685384.23 | 603363.75 | GRID | 13.05 | 13.03 | 1.16 | 0.56 | 15.28 | | 0.52 | 2.25 |
| 421 | 685362.66 | 603351.12 | GRID | 13.51 | 13.43 | 1.25 | 0.54 | 15.74 | | 0.53 | 2.31 |
| 422 | 685341.08 | 603338.49 | GRID | 14.17 | 14.08 | 1.26 | 0.53 | 16.38 | | 0.52 | 2.31 |
| 423 | 685319.51 | 603325.86 | GRID | 14.83 | 14.73 | 1.26 | 0.54 | 17.05 | | 0.52 | 2.32 |
| 424 | 685297.93 | 603313.23 | GRID | 15.63 | 15.59 | 1.20 | 0.54 | 17.98 | | 0.65 | 2.39 |
| 425 | 685276.36 | 603300.59 | GRID | 13.18 | 13.15 | 1.23 | | 16.56 | | 0.58 | 3.40 |
| 426 | 685254.78 | 603287.96 | GRID | 13.17 | 13.11 | 1.13 | | 15.45 | | 0.62 | 2.34 |
| 427 | 685242.15 | 603309.54 | GRID | 12.84 | 12.83 | 1.14 | | 15.38 | | 0.55 | 2.55 |
| 428 | 685263.73 | 603322.17 | GRID | 13.03 | 13.02 | 1.24 | | 16.51 | | 0.63 | 3.49 |
| 429 | 685285.30 | 603334.80 | GRID | 15.10 | 15.09 | 1.17 | 0.54 | 17.41 | | 0.61 | 2.32 |
| 430 | 685306.88 | 603347.43 | GRID | 14.45 | 14.38 | 1.22 | 0.56 | 16.68 | | 0.53 | 2.30 |
| 431 | 685328.45 | 603360.06 | GRID | 13.79 | 13.70 | 1.28 | 0.52 | 16.02 | | 0.51 | 2.31 |
| 432 | 685350.02 | 603372.69 | GRID | 13.13 | 13.06 | 1.15 | 0.62 | 15.39 | | 0.56 | 2.33 |
| 433 | 685371.60 | 603385.33 | GRID | 12.48 | 12.43 | 1.26 | 0.48 | 14.73 | | 0.55 | 2.29 |
| 434 | 685393.17 | 603397.96 | GRID | 8.98 | 8.94 | 1.28 | | 12.48 | | 0.70 | 3.54 |
| 435 | 685414.75 | 603410.59 | GRID | 8.79 | 8.79 | 1.10 | | 11.82 | | 0.61 | 3.03 |
| 436 | 685402.11 | 603432.16 | GRID | 8.32 | 8.31 | 1.26 | | 11.18 | | 0.52 | 2.87 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 437 | 685380.54 | 603419.53 | GRID | 8.23 | 8.28 | 1.08 | | 11.77 | | 0.55 | 3.49 |
| 438 | 685358.97 | 603406.90 | GRID | 12.00 | 11.93 | 1.19 | 0.58 | 14.20 | | 0.50 | 2.28 |
| 439 | 685337.39 | 603394.27 | GRID | 12.75 | 12.68 | 1.23 | 0.55 | 14.99 | | 0.53 | 2.31 |
| 440 | 685294.24 | 603369.01 | GRID | 14.07 | 13.99 | 1.25 | 0.53 | 16.29 | | 0.52 | 2.30 |
| 441 | 685272.67 | 603356.37 | GRID | 14.73 | 14.71 | 1.13 | 0.60 | 16.96 | | 0.52 | 2.25 |
| 442 | 685251.10 | 603343.74 | GRID | 12.92 | 12.90 | 1.16 | 0.64 | 16.53 | | 0.54 | 3.62 |
| 443 | 685229.52 | 603331.11 | GRID | 12.50 | 12.46 | 1.18 | | 15.39 | | 0.63 | 2.92 |
| 444 | 685216.89 | 603352.69 | GRID | 12.12 | 12.06 | 1.16 | | 15.31 | | 0.62 | 3.26 |
| 445 | 685260.04 | 603377.95 | GRID | 14.33 | 14.32 | 1.17 | 0.54 | 16.57 | | 0.54 | 2.25 |
| 446 | 685281.61 | 603390.58 | GRID | 10.97 | 10.91 | 1.27 | 0.52 | 15.81 | | 0.62 | 4.90 |
| 447 | 685303.19 | 603403.21 | GRID | 10.51 | 10.57 | 1.14 | 0.57 | 15.15 | | 0.60 | 4.58 |
| 448 | 685324.76 | 603415.84 | GRID | 12.35 | 12.26 | 1.23 | 0.57 | 14.59 | | 0.53 | 2.33 |
| 449 | 685346.33 | 603428.47 | GRID | 11.39 | 11.33 | 1.20 | 0.59 | 13.65 | | 0.53 | 2.32 |
| 450 | 685367.91 | 603441.11 | GRID | 7.52 | 7.57 | 1.15 | | 11.21 | | 0.59 | 3.63 |
| 451 | 685389.48 | 603453.74 | GRID | 7.90 | 7.82 | 1.24 | | 10.57 | | 0.52 | 2.74 |
| 452 | 685376.85 | 603475.31 | GRID | 5.95 | 6.03 | 1.12 | | 10.16 | | 0.54 | 4.13 |
| 453 | 685355.28 | 603462.68 | GRID | 6.11 | 6.20 | 1.16 | | 10.70 | | 0.56 | 4.50 |
| 454 | 685333.70 | 603450.05 | GRID | 8.34 | 8.36 | 1.22 | 0.64 | 12.61 | | 0.62 | 4.25 |
| 455 | 685312.13 | 603437.42 | GRID | 9.03 | 9.03 | 1.26 | 0.49 | 13.13 | | 0.51 | 4.10 |
| 456 | 685290.55 | 603424.79 | GRID | 9.41 | 9.37 | 1.26 | 0.50 | 13.26 | | 0.59 | 3.89 |
| 457 | 685268.98 | 603412.15 | GRID | 9.87 | 9.93 | 1.17 | 0.49 | 13.64 | | 0.52 | 3.71 |
| 458 | 685247.41 | 603399.52 | GRID | 10.52 | 10.47 | 1.22 | 0.52 | 14.39 | | 0.61 | 3.91 |
| 459 | 685225.83 | 603386.89 | GRID | 11.16 | 11.17 | 1.21 | 0.48 | 15.22 | | 0.50 | 4.05 |
| 460 | 685204.26 | 603374.26 | GRID | 11.35 | 11.40 | 1.14 | | 15.12 | | 0.58 | 3.72 |
| 461 | 685170.05 | 603383.20 | GRID | 11.44 | 11.42 | 1.19 | | 14.74 | | 0.63 | 3.31 |
| 462 | 685191.63 | 603395.83 | GRID | 10.53 | 10.46 | 1.26 | | 14.04 | | 0.57 | 3.58 |
| 463 | 685213.20 | 603408.47 | GRID | 9.67 | 9.60 | 1.28 | | 13.73 | | 0.60 | 4.13 |
| 464 | 685234.78 | 603421.10 | GRID | 8.87 | 8.86 | 1.25 | | 12.86 | | 0.60 | 4.00 |
| 465 | 685256.35 | 603433.73 | GRID | 8.24 | 8.15 | 1.32 | | 12.01 | | 0.60 | 3.86 |
| 466 | 685277.92 | 603446.36 | GRID | 7.61 | 7.53 | 1.30 | | 11.17 | | 0.61 | 3.64 |
| 467 | 685299.50 | 603458.99 | GRID | 6.94 | 6.92 | 1.28 | | 10.32 | | 0.60 | 3.40 |
| 468 | 685321.07 | 603471.62 | GRID | 6.73 | 6.66 | 1.26 | | 10.49 | | 0.62 | 3.83 |
| 469 | 685342.65 | 603484.25 | GRID | 6.20 | 6.18 | 1.20 | | 10.26 | | 0.63 | 4.07 |
| 470 | 685364.22 | 603496.89 | GRID | 7.22 | 7.13 | 1.34 | | 9.65 | | 0.60 | 2.51 |
| 471 | 685330.01 | 603505.83 | GRID | 6.71 | 6.64 | 1.25 | | 10.05 | | 0.62 | 3.40 |
| 472 | 685308.44 | 603493.20 | GRID | 6.75 | 6.68 | 1.21 | | 10.21 | | 0.60 | 3.52 |
| 473 | 685286.87 | 603480.57 | GRID | 6.67 | 6.63 | 1.26 | | 10.41 | | 0.57 | 3.77 |
| 474 | 685265.29 | 603467.93 | GRID | 7.10 | 7.04 | 1.21 | | 11.31 | | 0.59 | 4.27 |
| 475 | 685243.72 | 603455.30 | GRID | 7.93 | 7.85 | 1.24 | | 12.11 | | 0.58 | 4.26 |
| 476 | 685222.14 | 603442.67 | GRID | 8.76 | 8.69 | 1.23 | | 13.00 | | 0.61 | 4.31 |
| 477 | 685200.57 | 603430.04 | GRID | 9.58 | 9.54 | 1.25 | | 13.82 | | 0.57 | 4.28 |
| 478 | 685179.00 | 603417.41 | GRID | 10.40 | 10.49 | 1.00 | | 14.03 | | 0.58 | 3.54 |
| 479 | 685157.42 | 603404.78 | GRID | 11.22 | 11.29 | 1.18 | | 14.34 | | 0.53 | 3.05 |
| 480 | 685144.79 | 603426.35 | GRID | 11.28 | 11.21 | 1.26 | | 14.05 | | 0.55 | 2.84 |
| 481 | 685166.36 | 603438.98 | GRID | 11.12 | 11.19 | 1.16 | | 14.85 | | 0.54 | 3.66 |
| 482 | 685187.94 | 603451.61 | GRID | 10.24 | 10.16 | 1.32 | 0.50 | 14.12 | | 0.57 | 3.96 |
| 483 | 685209.51 | 603464.25 | GRID | 9.59 | 9.51 | 1.24 | 0.58 | 13.20 | | 0.59 | 3.69 |
| 484 | 685231.09 | 603476.88 | GRID | 8.45 | 8.51 | 1.19 | | 12.25 | | 0.59 | 3.74 |
| 485 | 685252.66 | 603489.51 | GRID | 7.43 | 7.39 | 1.30 | | 11.38 | | 0.58 | 4.00 |
| 486 | 685274.23 | 603502.14 | GRID | 6.66 | 6.58 | 1.24 | | 10.54 | | 0.57 | 3.96 |
| 487 | 685295.81 | 603514.77 | GRID | 6.62 | 6.55 | 1.31 | | 10.22 | | 0.59 | 3.67 |
| 488 | 685317.38 | 603527.40 | GRID | 6.76 | 6.73 | 1.26 | | 10.04 | | 0.61 | 3.31 |
| 489 | 685304.75 | 603548.98 | GRID | 6.57 | 6.49 | 1.19 | | 10.00 | | 0.58 | 3.51 |
| 490 | 685283.18 | 603536.35 | GRID | 6.38 | 6.33 | 1.26 | 0.52 | 10.17 | | 0.58 | 3.84 |
| 491 | 685261.60 | 603523.71 | GRID | 7.89 | 7.84 | 1.26 | 0.52 | 11.20 | | 0.55 | 3.36 |
| 492 | 685240.03 | 603511.08 | GRID | 8.48 | 8.49 | 1.14 | 0.58 | 12.59 | | 0.59 | 4.10 |
| 493 | 685218.45 | 603498.45 | GRID | 11.61 | 11.53 | 1.34 | 0.50 | 14.00 | | 0.69 | 2.48 |
| 494 | 685196.88 | 603485.82 | GRID | 12.06 | 12.10 | 1.22 | 0.45 | 14.64 | | 0.87 | 2.54 |
| 495 | 685175.31 | 603473.19 | GRID | 10.51 | 10.48 | 1.26 | 0.49 | 14.84 | | 0.57 | 4.35 |
| 496 | 685153.81 | 603460.42 | GRID | 11.70 | 11.63 | 1.15 | 0.60 | 15.39 | | 0.56 | 3.76 |
| 497 | 685132.16 | 603447.92 | GRID | 10.93 | 10.87 | 1.25 | | 14.16 | | 0.60 | 3.29 |
| 498 | 685119.53 | 603469.50 | GRID | 10.60 | 10.53 | 1.26 | | 14.17 | | 0.54 | 3.64 |
| 499 | 685141.10 | 603482.13 | GRID | 11.02 | 10.97 | 1.28 | 0.61 | 15.29 | | 0.61 | 4.32 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 500 | 685162.67 | 603494.76 | GRID | 13.25 | 13.25 | 1.20 | 0.52 | 15.51 | | 0.55 | 2.27 |
| 501 | 685184.25 | 603507.39 | GRID | 12.67 | 12.59 | 1.23 | 0.52 | 14.91 | | 0.56 | 2.32 |
| 502 | 685205.82 | 603520.03 | GRID | 12.19 | 12.12 | 1.18 | 0.61 | 14.41 | | 0.51 | 2.30 |
| 503 | 685248.97 | 603545.29 | GRID | 7.38 | 7.33 | 1.15 | 0.62 | 11.50 | | 0.60 | 4.17 |
| 504 | 685270.55 | 603557.92 | GRID | 6.00 | 5.92 | 1.20 | | 10.00 | | 0.56 | 4.07 |
| 505 | 685292.12 | 603570.55 | GRID | 6.56 | 6.48 | 1.18 | | 9.98 | | 0.56 | 3.50 |
| 506 | 685279.49 | 603592.13 | GRID | 5.80 | 5.77 | 1.12 | | 9.99 | | 0.54 | 4.22 |
| 507 | 685257.91 | 603579.49 | GRID | 5.22 | 5.16 | 1.19 | | 10.04 | | 0.62 | 4.88 |
| 508 | 685236.34 | 603566.86 | GRID | 6.77 | 6.73 | 1.21 | 0.55 | 10.70 | | 0.55 | 3.97 |
| 509 | 685193.19 | 603541.60 | GRID | 12.09 | 12.02 | 1.21 | 0.55 | 14.33 | | 0.55 | 2.31 |
| 510 | 685171.62 | 603528.97 | GRID | 12.56 | 12.49 | 1.20 | 0.56 | 14.79 | | 0.53 | 2.30 |
| 511 | 685150.04 | 603516.34 | GRID | 13.22 | 13.15 | 1.20 | 0.57 | 15.43 | | 0.52 | 2.29 |
| 512 | 685128.47 | 603503.70 | GRID | 13.69 | 13.61 | 1.21 | 0.58 | 15.91 | | 0.51 | 2.30 |
| 513 | 685106.89 | 603491.07 | GRID | 10.45 | 10.38 | 1.30 | | 14.19 | | 0.56 | 3.81 |
| 514 | 685072.69 | 603500.02 | GRID | 10.37 | 10.29 | 1.29 | | 13.95 | | 0.51 | 3.66 |
| 515 | 685094.26 | 603512.65 | GRID | 10.49 | 10.44 | 1.23 | | 14.21 | | 0.55 | 3.78 |
| 516 | 685115.84 | 603525.28 | GRID | 13.34 | 13.25 | 1.24 | 0.55 | 15.56 | | 0.53 | 2.32 |
| 517 | 685137.41 | 603537.91 | GRID | 12.86 | 12.79 | 1.20 | 0.60 | 15.13 | | 0.54 | 2.34 |
| 518 | 685158.99 | 603550.54 | GRID | 12.44 | 12.36 | 1.24 | 0.55 | 14.66 | | 0.51 | 2.30 |
| 519 | 685180.56 | 603563.17 | GRID | 11.47 | 11.39 | 1.20 | 0.59 | 13.86 | | 0.68 | 2.47 |
| 520 | 685202.13 | 603575.80 | GRID | 7.85 | 7.77 | 1.18 | 0.61 | 12.28 | | 0.53 | 4.51 |
| 521 | 685223.71 | 603588.44 | GRID | 5.90 | 5.86 | 1.24 | 0.71 | 9.74 | | 0.57 | 3.89 |
| 522 | 685245.28 | 603601.07 | GRID | 5.05 | 4.98 | 1.16 | | 9.86 | | 0.53 | 4.88 |
| 523 | 685266.86 | 603613.70 | GRID | 6.24 | 6.18 | 1.16 | | 9.99 | | 0.55 | 3.81 |
| 524 | 685232.65 | 603622.64 | GRID | 5.04 | 4.97 | 1.16 | | 9.93 | | 0.60 | 4.97 |
| 525 | 685211.08 | 603610.01 | GRID | 5.49 | 5.42 | 1.15 | 0.66 | 9.89 | | 0.59 | 4.46 |
| 526 | 685189.50 | 603597.38 | GRID | 7.44 | 7.42 | 1.14 | 0.56 | 11.66 | | 0.60 | 4.24 |
| 527 | 685167.93 | 603584.75 | GRID | 8.65 | 8.55 | 1.33 | 0.71 | 13.41 | | 0.60 | 4.86 |
| 528 | 685124.78 | 603559.48 | GRID | 12.62 | 12.54 | 1.21 | 0.56 | 14.88 | | 0.57 | 2.34 |
| 529 | 685103.21 | 603546.85 | GRID | 12.96 | 12.87 | 1.19 | 0.60 | 15.28 | | 0.62 | 2.41 |
| 530 | 685081.63 | 603534.22 | GRID | 10.49 | 10.39 | 1.27 | | 14.29 | | 0.63 | 3.90 |
| 531 | 685060.06 | 603521.59 | GRID | 10.02 | 9.94 | 1.16 | | 13.16 | | 0.58 | 3.22 |
| 532 | 685047.43 | 603543.16 | GRID | 9.71 | 9.63 | 1.22 | | 13.26 | | 0.59 | 3.64 |
| 533 | 685090.57 | 603568.43 | GRID | 10.17 | 10.88 | 1.18 | 0.80 | 14.90 | | 0.59 | 4.02 |
| 534 | 685112.15 | 603581.06 | GRID | 12.15 | 12.07 | 1.19 | 0.60 | 14.38 | | 0.52 | 2.31 |
| 535 | 685133.72 | 603593.69 | GRID | 11.84 | 11.74 | 1.21 | 0.57 | 14.12 | | 0.59 | 2.38 |
| 536 | 685176.87 | 603618.95 | GRID | 7.02 | 7.11 | 1.05 | 0.56 | 10.80 | | 0.58 | 3.69 |
| 537 | 685198.45 | 603631.58 | GRID | 5.13 | 5.07 | 1.15 | 0.69 | 9.95 | | 0.61 | 4.88 |
| 538 | 685220.02 | 603644.22 | GRID | 5.06 | 4.98 | 1.28 | | 10.03 | | 0.53 | 5.04 |
| 539 | 685207.39 | 603665.79 | GRID | 5.13 | 5.05 | 1.19 | | 10.27 | | 0.58 | 5.22 |
| 540 | 685185.81 | 603653.16 | GRID | 4.86 | 4.83 | 1.23 | 0.55 | 9.94 | | 0.57 | 5.12 |
| 541 | 685164.24 | 603640.53 | GRID | 6.44 | 6.37 | 1.18 | 0.61 | 10.16 | | 0.61 | 3.80 |
| 542 | 685121.09 | 603615.26 | GRID | 11.45 | 11.38 | 1.16 | 0.61 | 13.72 | | 0.57 | 2.34 |
| 543 | 685099.52 | 603602.63 | GRID | 11.36 | 11.29 | 1.28 | 0.49 | 13.62 | | 0.56 | 2.32 |
| 544 | 685077.94 | 603590.00 | GRID | 11.95 | 11.87 | 1.22 | 0.56 | 14.17 | | 0.52 | 2.30 |
| 545 | 685056.37 | 603577.37 | GRID | 12.70 | 12.62 | 1.24 | 0.53 | 14.90 | | 0.51 | 2.28 |
| 546 | 685034.79 | 603564.74 | GRID | 9.43 | 9.36 | 1.18 | | 13.36 | | 0.54 | 4.00 |
| 547 | 685022.16 | 603586.31 | GRID | 9.24 | 9.26 | 1.09 | | 13.10 | | 0.54 | 3.84 |
| 548 | 685043.74 | 603598.94 | GRID | 9.32 | 9.23 | 1.17 | 0.64 | 13.35 | | 0.60 | 4.13 |
| 549 | 685065.31 | 603611.58 | GRID | 8.45 | 8.43 | 1.11 | 0.59 | 12.43 | | 0.61 | 4.00 |
| 550 | 685086.89 | 603624.21 | GRID | 8.04 | 8.01 | 1.13 | 0.62 | 11.72 | | 0.64 | 3.71 |
| 551 | 685108.46 | 603636.84 | GRID | 7.31 | 7.25 | 1.15 | 0.69 | 11.36 | | 0.60 | 4.11 |
| 552 | 685130.03 | 603649.47 | GRID | 6.70 | 6.63 | 1.23 | 0.69 | 10.52 | | 0.55 | 3.89 |
| 553 | 685151.61 | 603662.10 | GRID | 6.04 | 5.96 | 1.19 | 0.65 | 9.61 | | 0.54 | 3.66 |
| 554 | 685173.18 | 603674.73 | GRID | 4.86 | 4.82 | 1.26 | | 9.89 | | 0.62 | 5.07 |
| 555 | 685194.76 | 603687.36 | GRID | 4.69 | 4.77 | 1.17 | | 10.54 | | 0.51 | 5.77 |
| 556 | 685182.12 | 603708.94 | GRID | 5.90 | 5.96 | 1.04 | | 10.59 | | 0.55 | 4.63 |
| 557 | 685160.55 | 603696.31 | GRID | 4.82 | 4.84 | 1.18 | | 10.11 | | 0.59 | 5.27 |
| 558 | 685138.98 | 603683.68 | GRID | 4.85 | 4.82 | 1.18 | | 9.79 | | 0.52 | 4.96 |
| 559 | 685117.40 | 603671.04 | GRID | 5.40 | 5.31 | 1.28 | | 10.00 | | 0.53 | 4.69 |
| 560 | 685095.83 | 603658.41 | GRID | 5.97 | 5.89 | 1.17 | | 10.51 | | 0.58 | 4.62 |
| 561 | 685074.25 | 603645.78 | GRID | 6.54 | 6.48 | 1.15 | | 10.80 | | 0.55 | 4.33 |
| 562 | 685052.68 | 603633.15 | GRID | 6.98 | 7.07 | 1.15 | | 11.30 | | 0.56 | 4.23 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 563 | 685031.11 | 603620.52 | GRID | 7.81 | 7.72 | 1.18 | | 11.85 | | 0.56 | 4.13 |
| 564 | 685009.53 | 603607.89 | GRID | 8.48 | 8.41 | 1.31 | | 12.47 | | 0.60 | 4.06 |
| 565 | 684987.96 | 603595.26 | GRID | 8.91 | 8.93 | 1.21 | | 13.55 | | 0.56 | 4.62 |
| 566 | 684975.33 | 603616.83 | GRID | 8.32 | 8.23 | 1.26 | | 13.10 | | 0.51 | 4.86 |
| 567 | 684996.90 | 603629.46 | GRID | 7.82 | 7.82 | 1.08 | | 11.94 | | 0.56 | 4.12 |
| 568 | 685018.47 | 603642.09 | GRID | 7.36 | 7.29 | 1.22 | | 11.76 | | 0.62 | 4.47 |
| 569 | 685040.05 | 603654.72 | GRID | 6.85 | 6.87 | 1.10 | | 11.25 | | 0.59 | 4.38 |
| 570 | 685061.62 | 603667.36 | GRID | 6.36 | 6.29 | 1.18 | | 10.99 | | 0.59 | 4.70 |
| 571 | 685083.20 | 603679.99 | GRID | 5.86 | 5.81 | 1.13 | | 10.74 | | 0.55 | 4.93 |
| 572 | 685104.77 | 603692.62 | GRID | 5.45 | 5.38 | 1.20 | | 10.25 | | 0.49 | 4.88 |
| 573 | 685126.35 | 603705.25 | GRID | 4.99 | 4.90 | 1.20 | | 10.19 | | 0.54 | 5.29 |
| 574 | 685147.92 | 603717.88 | GRID | 4.79 | 4.75 | 1.16 | | 10.14 | | 0.52 | 5.39 |
| 576 | 685005.84 | 603663.67 | GRID | 7.30 | 7.22 | 1.18 | | 11.60 | | 0.84 | 4.37 |
| 577 | 684984.27 | 603651.03 | GRID | 7.85 | 7.77 | 1.18 | | 11.66 | | 0.71 | 3.89 |
| 578 | 684962.69 | 603638.40 | GRID | 8.32 | 8.31 | 1.26 | | 12.50 | | 0.80 | 4.19 |
| 1000 | 685974.79 | 602058.24 | BNDY | 11.80 | 11.80 | 1.13 | | 14.01 | | 0.70 | 2.22 |
| 1001 | 685996.44 | 602070.73 | BNDY | 11.10 | 11.05 | 1.14 | | 14.64 | | 0.94 | 3.58 |
| 1002 | 686018.09 | 602083.22 | BNDY | 10.56 | 10.58 | 1.10 | 0.61 | 14.35 | | 0.59 | 3.77 |
| 1003 | 686034.27 | 602092.56 | BNDY_DGA | 10.61 | 10.57 | 1.29 | | 17.04 | 2.60 | | 6.47 |
| 1004 | 686042.93 | 602090.28 | BNDY_DGA | 10.62 | 10.58 | 1.26 | | 17.24 | 1.39 | | 6.67 |
| 1005 | 686053.71 | 602087.45 | BNDY_DGA | 10.57 | 10.58 | 1.14 | | 17.25 | 0.93 | | 6.67 |
| 1006 | 686070.10 | 602097.03 | BNDY | 10.84 | 10.88 | 1.05 | | 17.32 | | 0.68 | 6.44 |
| 1007 | 686075.12 | 602116.13 | BNDY | 10.67 | 10.65 | 1.18 | | 17.35 | | 0.75 | 6.69 |
| 1008 | 686083.05 | 602120.71 | BNDY | 10.85 | 10.86 | 1.10 | | 17.41 | | 0.59 | 6.55 |
| 1009 | 686107.56 | 602134.84 | BNDY | 7.89 | 7.93 | 1.22 | | 17.52 | | 0.47 | 9.59 |
| 1010 | 686096.69 | 602158.58 | BNDY | 8.00 | 7.99 | 1.14 | | 17.46 | | 0.45 | 9.48 |
| 1012 | 686086.24 | 602181.43 | BNDY_DGA | 8.11 | 8.10 | 1.24 | | 17.83 | 0.54 | | 9.73 |
| 1013 | 686075.78 | 602204.28 | BNDY | 8.22 | 8.22 | 1.24 | | 16.14 | | 0.75 | 7.93 |
| 1014 | 686065.33 | 602227.13 | BNDY | 8.33 | 8.37 | 1.05 | | 15.57 | | 0.67 | 7.20 |
| 1015 | 686054.87 | 602249.98 | BNDY | 8.44 | 8.48 | 1.21 | | 15.22 | | 0.51 | 6.73 |
| 1016 | 686051.14 | 602258.14 | BNDY | 6.56 | 6.62 | 1.09 | | 15.14 | | 0.66 | 8.52 |
| 1017 | 686043.71 | 602274.37 | BNDY | 11.67 | 11.64 | 1.22 | | 14.80 | | 0.77 | 3.16 |
| 1018 | 686052.80 | 602278.53 | BNDY | 11.86 | 11.86 | 1.13 | | 14.91 | | 0.52 | 3.05 |
| 1019 | 686041.80 | 602300.26 | BNDY | 12.11 | 12.13 | 1.09 | | 14.33 | | 0.76 | 2.20 |
| 1020 | 686030.48 | 602322.60 | BNDY | 12.36 | 12.38 | 1.06 | | 14.43 | | 0.58 | 2.05 |
| 1021 | 686019.16 | 602344.95 | BNDY | 12.61 | 12.63 | 1.09 | | 14.62 | | 0.50 | 1.99 |
| 1022 | 686007.84 | 602367.29 | BNDY | 12.86 | 12.85 | 1.12 | | 14.89 | | 0.53 | 2.04 |
| 1023 | 685996.52 | 602389.63 | BNDY | 13.11 | 13.11 | 1.11 | | 15.16 | | 0.52 | 2.05 |
| 1024 | 685985.21 | 602411.98 | BNDY | 13.36 | 13.32 | 1.11 | | 15.39 | | 0.56 | 2.06 |
| 1025 | 685973.89 | 602434.32 | BNDY | 13.61 | 13.58 | 1.12 | | 15.69 | | 0.62 | 2.11 |
| 1026 | 685962.60 | 602456.68 | BNDY | 13.71 | 13.66 | 1.19 | | 15.88 | | 0.72 | 2.22 |
| 1027 | 685951.80 | 602479.33 | BNDY | 13.94 | 13.92 | 1.13 | | 15.96 | | 0.53 | 2.04 |
| 1028 | 685941.01 | 602501.98 | BNDY | 14.13 | 14.09 | 1.12 | | 16.18 | | 0.69 | 2.09 |
| 1029 | 685930.21 | 602524.63 | BNDY | 9.88 | 9.84 | 1.28 | | 16.44 | | 0.67 | 6.59 |
| 1030 | 685919.41 | 602547.28 | BNDY | 14.51 | 14.45 | 1.26 | | 16.55 | | 0.57 | 2.10 |
| 1031 | 685908.62 | 602569.92 | BNDY | 14.70 | 14.70 | 1.11 | | 16.72 | | 0.53 | 2.02 |
| 1032 | 685897.82 | 602592.57 | BNDY | 14.89 | 14.86 | 1.16 | | 16.92 | | 0.59 | 2.05 |
| 1033 | 685887.02 | 602615.22 | BNDY | 15.08 | 15.12 | 1.05 | | 17.13 | | 0.66 | 2.01 |
| 1034 | 685876.23 | 602637.87 | BNDY | 15.27 | 15.28 | 1.06 | | 17.28 | | 0.61 | 2.00 |
| 1035 | 685865.39 | 602660.49 | BNDY | 15.50 | 15.51 | 1.07 | | 17.53 | | 0.60 | 2.02 |
| 1036 | 685854.39 | 602683.02 | BNDY | 13.51 | 13.43 | 1.24 | | 17.77 | | 0.57 | 4.34 |
| 1037 | 685843.40 | 602705.56 | BNDY | 14.54 | 14.57 | 1.05 | | 18.02 | | 0.59 | 3.45 |
| 1038 | 685832.40 | 602728.09 | BNDY | 14.67 | 14.59 | 1.28 | | 18.42 | | 0.59 | 3.83 |
| 1039 | 685821.41 | 602750.62 | BNDY | 14.66 | 14.66 | 1.10 | | 18.86 | | 0.66 | 4.20 |
| 1040 | 685808.84 | 602776.37 | BNDY | 14.65 | 14.69 | 1.18 | | 19.58 | | 0.88 | 4.90 |
| 1041 | 685836.50 | 602789.20 | BNDY | 12.94 | 12.95 | 1.11 | | 19.13 | | 0.70 | 6.18 |
| 1042 | 685852.65 | 602796.69 | BNDY | 12.80 | 12.84 | 1.14 | | 19.45 | | 0.66 | 6.60 |
| 1043 | 685850.84 | 602802.07 | BNDY | 12.79 | 12.76 | 1.21 | | 19.80 | | 0.84 | 7.04 |
| 1044 | 685842.61 | 602820.98 | BNDY | 18.03 | 16.59 | 2.58 | | 20.36 | | 0.62 | 3.77 |
| 1045 | 685838.18 | 602831.15 | BNDY | 18.25 | 18.18 | 1.16 | | 20.39 | | 0.68 | 2.22 |
| 1046 | 685836.38 | 602830.34 | BNDY | 18.14 | 18.09 | 1.16 | | 20.39 | | 0.54 | 2.30 |
| 1047 | 685832.35 | 602839.53 | BNDY | 14.22 | 14.15 | 1.17 | | 20.38 | | 0.64 | 6.23 |
| 1048 | 685830.31 | 602838.50 | BNDY | 14.00 | 14.07 | 1.18 | | 20.42 | | 0.68 | 6.35 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1049 | 685818.27 | 602864.66 | BNDY | 14.00 | 14.06 | 1.04 | | 20.35 | | 0.51 | 6.29 |
| 1050 | 685807.77 | 602887.48 | BNDY | 14.00 | 14.00 | 1.14 | | 20.51 | | 0.61 | 6.51 |
| 1051 | 685797.27 | 602910.31 | BNDY | 14.00 | 13.91 | 1.23 | | 20.72 | | 0.65 | 6.80 |
| 1052 | 685786.76 | 602933.13 | BNDY | 12.00 | 12.04 | 1.15 | | 20.91 | | 0.50 | 8.87 |
| 1053 | 685776.25 | 602955.94 | BNDY | 12.00 | 11.99 | 1.24 | | 21.05 | | 0.56 | 9.06 |
| 1054 | 685765.76 | 602978.77 | BNDY | 12.00 | 12.06 | 1.19 | | 21.12 | | 0.56 | 9.06 |
| 1055 | 685755.26 | 603001.59 | BNDY | 11.84 | 11.43 | 1.53 | | 21.22 | | 0.62 | 9.79 |
| 1056 | 685744.76 | 603024.41 | BNDY | 11.50 | 11.48 | 1.14 | | 21.13 | | 0.71 | 9.64 |
| 1057 | 685734.25 | 603047.23 | BNDY | 11.50 | 11.46 | 1.23 | | 20.88 | | 0.65 | 9.41 |
| 1058 | 685723.69 | 603070.02 | BNDY | 11.50 | 11.56 | 1.14 | | 20.68 | | 0.57 | 9.12 |
| 1059 | 685713.13 | 603092.80 | BNDY | 11.50 | 11.52 | 1.23 | | 20.35 | | 0.59 | 8.84 |
| 1060 | 685704.90 | 603110.56 | BNDY | 11.50 | 11.47 | 1.16 | | 20.14 | | 0.60 | 8.67 |
| 1061 | 685679.62 | 603098.84 | BNDY | 11.50 | 11.56 | 1.17 | | 20.38 | | 0.69 | 8.83 |
| 1062 | 685667.86 | 603124.24 | BNDY | 11.50 | 11.42 | 1.18 | | 20.39 | | 0.63 | 8.97 |
| 1063 | 685658.74 | 603143.90 | BNDY | 12.00 | 12.06 | 1.18 | | 19.64 | | 0.54 | 7.57 |
| 1064 | 685651.29 | 603140.51 | BNDY | 12.69 | 12.70 | 1.19 | | 19.73 | | 0.69 | 7.03 |
| 1065 | 685634.84 | 603162.84 | BNDY | 13.26 | 13.33 | 1.17 | | 19.16 | | 0.64 | 5.83 |
| 1066 | 685619.86 | 603183.04 | BNDY | 13.75 | 13.82 | 1.08 | | 18.52 | | 0.62 | 4.69 |
| 1067 | 685604.77 | 603203.18 | BNDY | 14.35 | 14.32 | 1.22 | | 18.51 | | 0.60 | 4.19 |
| 1068 | 685589.69 | 603223.32 | BNDY | 15.61 | 15.64 | 1.06 | | 18.16 | | 0.56 | 2.52 |
| 1069 | 685574.11 | 603243.17 | BNDY | 14.59 | 14.64 | 1.08 | | 17.45 | | 0.50 | 2.80 |
| 1070 | 685558.86 | 603263.21 | BNDY | 14.78 | 13.85 | 2.04 | | 17.81 | | 0.58 | 3.96 |
| 1071 | 685549.17 | 603276.30 | BNDY | 14.27 | 14.01 | 1.48 | | 16.80 | | 0.62 | 2.78 |
| 1072 | 685536.47 | 603288.67 | BNDY | 13.32 | 13.30 | 1.17 | | 15.84 | | 0.65 | 2.54 |
| 1073 | 685533.78 | 603291.95 | BNDY | 13.22 | 13.17 | 1.18 | | 15.73 | | 0.61 | 2.55 |
| 1074 | 685528.21 | 603303.34 | BNDY | 12.92 | 12.85 | 1.22 | | 15.45 | | 0.59 | 2.60 |
| 1075 | 685512.73 | 603323.11 | BNDY | 9.77 | 9.76 | 1.21 | | 14.76 | | 0.56 | 5.00 |
| 1076 | 685497.08 | 603342.92 | BNDY | 11.91 | 11.87 | 1.15 | | 14.13 | | 0.71 | 2.26 |
| 1077 | 685481.35 | 603362.67 | BNDY | 11.11 | 11.19 | 1.16 | | 13.18 | | 0.57 | 1.99 |
| 1078 | 685465.52 | 603382.38 | BNDY | 10.50 | 10.43 | 1.17 | | 12.52 | | 0.50 | 2.09 |
| 1079 | 685449.61 | 603402.03 | BNDY | 9.90 | 9.93 | 1.07 | | 11.93 | | 0.53 | 2.00 |
| 1080 | 685433.60 | 603421.63 | BNDY | 9.20 | 9.26 | 1.09 | | 11.34 | | 0.55 | 2.08 |
| 1081 | 685417.51 | 603441.17 | BNDY | 8.74 | 8.82 | 1.12 | | 10.79 | | 0.54 | 1.97 |
| 1082 | 685401.32 | 603460.67 | BNDY | 8.22 | 8.28 | 1.04 | | 10.25 | | 0.53 | 1.97 |
| 1083 | 685385.04 | 603480.11 | BNDY | 5.89 | 5.97 | 1.17 | | 9.76 | | 0.54 | 3.78 |
| 1084 | 685368.67 | 603499.49 | BNDY | 7.32 | 7.25 | 1.31 | | 9.40 | | 0.62 | 2.15 |
| 1085 | 685352.21 | 603518.83 | BNDY | 7.00 | 6.94 | 1.25 | | 9.97 | | 0.57 | 3.04 |
| 1086 | 685335.68 | 603538.11 | BNDY | 6.99 | 6.96 | 1.13 | | 9.94 | | 0.55 | 2.98 |
| 1087 | 685319.13 | 603557.40 | BNDY | 7.00 | 6.94 | 1.30 | | 9.95 | | 0.58 | 3.01 |
| 1088 | 685302.59 | 603576.68 | BNDY | 6.99 | 7.04 | 1.06 | | 9.99 | | 0.58 | 2.95 |
| 1089 | 685286.05 | 603595.97 | BNDY | 6.96 | 6.92 | 1.13 | | 9.97 | | 0.60 | 3.06 |
| 1090 | 685269.51 | 603615.25 | BNDY | 6.96 | 6.93 | 1.12 | | 10.06 | | 0.67 | 3.14 |
| 1091 | 685252.96 | 603634.53 | BNDY | 6.96 | 6.93 | 1.16 | | 10.06 | | 0.59 | 3.13 |
| 1092 | 685236.42 | 603653.82 | BNDY | 6.96 | 6.95 | 1.14 | | 10.08 | | 0.61 | 3.13 |
| 1093 | 685219.88 | 603673.10 | BNDY | 6.96 | 7.00 | 1.16 | | 10.48 | | 0.60 | 3.49 |
| 1094 | 685203.33 | 603692.39 | BNDY | 4.81 | 4.74 | 1.33 | | 10.87 | | 0.61 | 6.13 |
| 1095 | 685186.79 | 603711.67 | BNDY | 7.00 | 6.92 | 1.16 | | 10.73 | | 0.61 | 3.81 |
| 1096 | 685170.25 | 603730.95 | BNDY | 7.00 | 6.97 | 1.29 | | 10.58 | | 0.61 | 3.61 |
| 1097 | 685161.74 | 603740.86 | BNDY_SW | 7.00 | 6.96 | 1.14 | | 10.09 | 0.44 | | 3.13 |
| 1098 | 685140.27 | 603730.95 | BNDY_SW | 7.00 | 6.97 | 1.11 | | 10.28 | 0.43 | | 3.31 |
| 1099 | 685117.46 | 603720.43 | BNDY_SW | 7.00 | 6.97 | 1.15 | | 10.55 | 0.59 | | 3.58 |
| 1100 | 685094.65 | 603709.90 | BNDY_SW | 7.00 | 6.99 | 1.14 | | 10.83 | 0.69 | | 3.84 |
| 1101 | 685071.85 | 603699.37 | BNDY_SW | 7.00 | 6.97 | 1.12 | | 11.02 | 0.74 | | 4.06 |
| 1102 | 685049.04 | 603688.85 | BNDY_SW | 7.00 | 6.95 | 1.14 | | 11.23 | 1.11 | | 4.27 |
| 1103 | 685026.23 | 603678.32 | BNDY_SW | 7.15 | 7.09 | 1.24 | | 11.35 | 0.89 | | 4.26 |
| 1104 | 685003.42 | 603667.80 | BNDY_SW | 7.30 | 7.24 | 1.25 | | 11.41 | 0.71 | | 4.17 |
| 1105 | 684980.62 | 603657.27 | BNDY_SW | 8.03 | 7.95 | 1.17 | | 11.75 | 0.96 | | 3.80 |
| 1106 | 684957.81 | 603646.75 | BNDY_SW | 8.50 | 8.48 | 1.14 | | 11.85 | 0.50 | | 3.38 |
| 1107 | 684944.97 | 603640.17 | BNDY_SW | 8.55 | 10.75 | 1.26 | | 12.02 | -0.40 | | 1.92 |
| 1108 | 684968.60 | 603612.89 | BNDY | 8.50 | 8.50 | 3.49 | | 13.68 | | 0.52 | 5.18 |
| 1109 | 684985.25 | 603593.67 | BNDY | 8.86 | 8.93 | 3.01 | | 13.81 | | 0.51 | 4.88 |
| 1110 | 685001.90 | 603574.45 | BNDY | 9.63 | 9.66 | 2.31 | | 13.76 | | 0.51 | 4.10 |
| 1111 | 685018.55 | 603555.23 | BNDY | 9.76 | 9.72 | 2.21 | | 13.91 | | 0.51 | 4.20 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1112 | 685035.20 | 603536.01 | BNDY | 9.94 | 9.97 | 1.92 | | 14.10 | | 0.54 | 4.13 |
| 1113 | 685051.85 | 603516.79 | BNDY | 10.18 | 10.27 | 1.68 | | 14.17 | | 0.52 | 3.91 |
| 1114 | 685068.50 | 603497.56 | BNDY | 10.43 | 10.52 | 1.35 | | 14.58 | | 0.52 | 4.07 |
| 1115 | 685085.15 | 603478.34 | BNDY | 10.68 | 10.66 | 1.20 | | 14.95 | | 0.50 | 4.29 |
| 1116 | 685101.80 | 603459.12 | BNDY | 10.94 | 10.93 | 1.10 | | 14.92 | | 0.53 | 3.99 |
| 1117 | 685118.45 | 603439.90 | BNDY | 11.19 | 11.22 | 1.09 | | 14.91 | | 0.54 | 3.69 |
| 1118 | 685135.10 | 603420.68 | BNDY | 11.45 | 11.41 | 1.20 | | 14.98 | | 0.57 | 3.57 |
| 1119 | 685151.75 | 603401.46 | BNDY | 11.41 | 11.41 | 1.18 | | 14.97 | | 0.58 | 3.56 |
| 1120 | 685168.40 | 603382.23 | BNDY | 11.46 | 11.46 | 1.12 | | 14.83 | | 0.53 | 3.37 |
| 1121 | 685185.05 | 603363.01 | BNDY | 11.50 | 11.46 | 1.16 | | 14.78 | | 0.77 | 3.32 |
| 1122 | 685201.70 | 603343.79 | BNDY | 12.44 | 12.35 | 1.18 | | 14.96 | | 0.56 | 2.61 |
| 1123 | 685218.35 | 603324.57 | BNDY | 12.72 | 12.71 | 1.14 | | 15.08 | | 0.51 | 2.37 |
| 1124 | 685235.00 | 603305.35 | BNDY | 12.97 | 13.02 | 1.05 | | 15.00 | | 0.56 | 1.98 |
| 1125 | 685251.65 | 603286.13 | BNDY | 13.23 | 13.26 | 1.07 | | 15.27 | | 0.59 | 2.01 |
| 1126 | 685264.65 | 603271.12 | BNDY | 13.44 | 13.45 | 1.09 | | 15.45 | | 0.53 | 1.99 |
| 1127 | 685280.05 | 603244.81 | BNDY | 13.71 | 13.78 | 1.02 | | 15.73 | | 0.46 | 1.95 |
| 1128 | 685292.68 | 603223.24 | BNDY | 13.96 | 14.02 | 1.07 | | 15.98 | | 0.52 | 1.96 |
| 1129 | 685305.31 | 603201.67 | BNDY | 14.21 | 14.25 | 1.17 | | 16.22 | | 0.50 | 1.97 |
| 1130 | 685317.94 | 603180.09 | BNDY | 14.47 | 14.50 | 1.21 | | 16.54 | | 0.53 | 2.04 |
| 1131 | 685330.57 | 603158.52 | BNDY | 14.57 | 14.63 | 1.19 | | 16.82 | | 0.53 | 2.19 |
| 1132 | 685343.21 | 603136.94 | BNDY | 14.30 | 14.35 | 1.04 | | 16.98 | | 0.51 | 2.62 |
| 1133 | 685355.84 | 603115.37 | BNDY | 8.98 | 9.01 | 2.92 | | 17.04 | | 0.58 | 8.03 |
| 1134 | 685368.47 | 603093.80 | BNDY | 8.98 | 8.94 | 2.98 | | 17.14 | | 0.71 | 8.20 |
| 1135 | 685381.10 | 603072.22 | BNDY | 8.98 | 9.05 | 2.88 | | 17.74 | | 0.53 | 8.69 |
| 1136 | 685391.11 | 603055.12 | BNDY | 8.98 | 9.65 | 2.24 | | 17.94 | | 0.49 | 8.29 |
| 1137 | 685406.36 | 603029.07 | BNDY | 13.38 | 13.41 | 1.09 | | 18.27 | | 0.60 | 4.86 |
| 1138 | 685418.99 | 603007.50 | BNDY | 13.33 | 13.39 | 1.08 | | 18.49 | | 0.52 | 5.10 |
| 1139 | 685431.63 | 602985.92 | BNDY | 13.28 | 13.33 | 1.18 | | 18.74 | | 0.57 | 5.41 |
| 1140 | 685444.26 | 602964.35 | BNDY | 13.32 | 13.38 | 1.10 | | 19.02 | | 0.61 | 5.64 |
| 1141 | 685456.89 | 602942.78 | BNDY | 13.38 | 13.37 | 1.27 | | 19.23 | | 0.54 | 5.86 |
| 1142 | 685469.52 | 602921.20 | BNDY | 13.43 | 13.49 | 1.17 | | 19.53 | | 0.60 | 6.03 |
| 1143 | 685482.15 | 602899.63 | BNDY | 13.49 | 13.50 | 1.16 | | 19.72 | | 0.60 | 6.22 |
| 1144 | 685494.78 | 602878.05 | BNDY | 13.47 | 13.50 | 1.18 | | 19.93 | | 0.54 | 6.43 |
| 1145 | 685507.41 | 602856.48 | BNDY | 13.46 | 13.48 | 1.07 | | 20.09 | | 0.63 | 6.61 |
| 1146 | 685520.05 | 602834.91 | BNDY | 13.46 | 13.48 | 1.18 | | 20.20 | | 0.55 | 6.71 |
| 1147 | 685532.68 | 602813.33 | BNDY | 13.54 | 13.55 | 1.17 | | 20.36 | | 0.59 | 6.80 |
| 1148 | 685545.31 | 602791.76 | BNDY | 13.81 | 13.77 | 1.16 | | 20.40 | | 0.61 | 6.63 |
| 1149 | 685557.94 | 602770.18 | BNDY | 13.83 | 13.83 | 1.25 | | 20.53 | | 0.56 | 6.70 |
| 1150 | 685570.57 | 602748.61 | BNDY | 13.75 | 13.74 | 1.26 | | 20.66 | | 0.74 | 6.92 |
| 1151 | 685583.20 | 602727.03 | BNDY | 13.66 | 13.65 | 1.23 | | 20.54 | | 0.65 | 6.90 |
| 1152 | 685595.84 | 602705.46 | BNDY | 13.58 | 13.64 | 1.19 | | 20.62 | | 0.78 | 6.98 |
| 1153 | 685608.47 | 602683.89 | BNDY | 13.44 | 13.47 | 1.20 | | 20.47 | | 0.71 | 7.00 |
| 1154 | 685621.10 | 602662.31 | BNDY | 13.14 | 13.20 | 1.13 | | 20.45 | | 0.67 | 7.25 |
| 1155 | 685633.73 | 602640.74 | BNDY | 12.80 | 12.88 | 1.15 | | 20.33 | | 0.74 | 7.46 |
| 1156 | 685646.36 | 602619.16 | BNDY | 12.55 | 12.60 | 1.15 | | 20.22 | | 0.75 | 7.62 |
| 1157 | 685658.99 | 602597.59 | BNDY | 12.31 | 12.25 | 1.26 | | 20.01 | | 0.75 | 7.75 |
| 1158 | 685671.62 | 602576.02 | BNDY | 12.18 | 12.21 | 1.18 | | 19.80 | | 0.81 | 7.60 |
| 1159 | 685684.26 | 602554.44 | BNDY | 12.08 | 12.09 | 1.25 | | 19.52 | | 0.68 | 7.43 |
| 1160 | 685696.89 | 602532.87 | BNDY | 12.13 | 12.11 | 1.15 | | 19.32 | | 0.62 | 7.21 |
| 1161 | 685709.52 | 602511.29 | BNDY | 12.23 | 12.24 | 1.12 | | 19.09 | | 0.72 | 6.86 |
| 1162 | 685722.15 | 602489.72 | BNDY | 12.45 | 12.42 | 1.26 | | 18.78 | | 0.66 | 6.35 |
| 1163 | 685734.78 | 602468.14 | BNDY | 12.73 | 12.71 | 1.14 | | 18.53 | | 0.64 | 5.82 |
| 1164 | 685747.41 | 602446.57 | BNDY | 12.85 | 12.82 | 1.15 | | 18.28 | | 0.65 | 5.47 |
| 1165 | 685760.05 | 602425.00 | BNDY | 12.99 | 13.05 | 1.02 | | 18.02 | | 0.57 | 4.97 |
| 1166 | 685772.68 | 602403.42 | BNDY | 13.23 | 13.26 | 1.22 | | 17.82 | | 0.60 | 4.55 |
| 1167 | 685785.31 | 602381.85 | BNDY | 13.53 | 13.47 | 1.17 | | 17.58 | | 0.69 | 4.12 |
| 1168 | 685797.94 | 602360.27 | BNDY | 13.74 | 13.72 | 1.24 | | 17.32 | | 0.71 | 3.60 |
| 1169 | 685810.57 | 602338.70 | BNDY | 13.90 | 13.90 | 1.13 | | 17.05 | | 0.65 | 3.15 |
| 1170 | 685823.20 | 602317.13 | BNDY | 13.91 | 13.89 | 1.26 | | 16.85 | | 0.73 | 2.97 |
| 1171 | 685833.24 | 602300.00 | BNDY | 8.48 | 8.46 | 1.27 | | 16.60 | | 0.66 | 8.14 |
| 1172 | 685837.79 | 602292.20 | BNDY | 13.90 | 13.95 | 1.15 | | 16.53 | | 0.58 | 2.58 |
| 1173 | 685848.45 | 602274.01 | BNDY | 14.27 | 14.25 | 1.23 | | 16.52 | | 0.73 | 2.27 |
| 1174 | 685861.10 | 602252.40 | BNDY | 14.02 | 14.01 | 1.10 | | 16.04 | | 0.52 | 2.03 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1175 | 685873.73 | 602230.83 | BNDY | 13.77 | 13.76 | 1.13 | | 15.81 | | 0.57 | 2.05 |
| 1176 | 685886.36 | 602209.26 | BNDY | 13.48 | 13.52 | 1.08 | | 15.56 | | 0.64 | 2.04 |
| 1177 | 685899.00 | 602187.68 | BNDY | 13.28 | 13.25 | 1.19 | | 15.35 | | 0.61 | 2.10 |
| 1178 | 685911.63 | 602166.11 | BNDY | 13.00 | 12.99 | 1.16 | | 15.04 | | 0.53 | 2.05 |
| 1179 | 685924.26 | 602144.54 | BNDY | 12.75 | 12.76 | 1.12 | | 14.76 | | 0.52 | 2.00 |
| 1180 | 685936.89 | 602122.96 | BNDY | 12.50 | 12.52 | 1.13 | | 14.52 | | 0.50 | 2.00 |
| 1181 | 685949.52 | 602101.39 | BNDY | 12.26 | 12.34 | 1.11 | | 14.38 | | 0.65 | 2.03 |
| 1182 | 685962.15 | 602079.81 | BNDY | 12.13 | 12.15 | 1.08 | | 14.14 | | 0.52 | 1.98 |
| 1183 | 685396.47 | 603045.97 | BNDY | 13.03 | 13.01 | 1.15 | | 18.03 | | 0.60 | 5.02 |
| 1184 | 684951.95 | 603632.11 | BNDY | 8.50 | 8.42 | 3.58 | | 13.38 | | 0.52 | 4.96 |
| 2000 | 685963.46 | 602222.86 | BRK | 12.50 | 12.59 | 1.02 | 0.64 | 17.35 | | 0.84 | 4.76 |
| 2001 | 685959.21 | 602224.98 | BRK | 15.00 | 14.92 | 1.31 | 0.49 | 17.36 | | 0.64 | 2.44 |
| 2002 | 686044.61 | 602255.15 | BRK | 11.35 | 11.28 | 1.17 | | 15.00 | | 0.54 | 3.72 |
| 2003 | 685995.00 | 602272.86 | BRK | 12.51 | 12.56 | 1.08 | 0.66 | 16.51 | | 0.69 | 3.95 |
| 2004 | 685991.78 | 602270.98 | BRK | 14.98 | 14.91 | 1.22 | 0.52 | 17.19 | | 0.54 | 2.28 |
| 2005 | 685981.32 | 602293.82 | BRK | 15.27 | 15.24 | 1.25 | 0.48 | 17.49 | | 0.52 | 2.25 |
| 2006 | 685984.59 | 602295.74 | BRK | 12.76 | 12.75 | 1.17 | 0.70 | 16.70 | | 0.81 | 3.96 |
| 2007 | 685937.03 | 602325.83 | BRK | 15.91 | 15.88 | 1.18 | 0.51 | 18.27 | | 0.69 | 2.38 |
| 2008 | 685933.35 | 602323.67 | BRK | 13.45 | 13.48 | 1.11 | 0.80 | 18.31 | | 1.00 | 4.84 |
| 2009 | 685852.16 | 602416.10 | BRK | 17.66 | 17.60 | 1.14 | 0.61 | 20.02 | | 0.66 | 2.42 |
| 2010 | 685936.65 | 602267.67 | BRK | 13.02 | 13.10 | 1.12 | 0.68 | 17.74 | | 0.93 | 4.64 |
| 2011 | 685940.05 | 602269.66 | BRK | 15.49 | 15.45 | 1.15 | 0.58 | 17.75 | | 0.57 | 2.30 |
| 2012 | 685849.90 | 602419.96 | BRK | 15.33 | 15.27 | 1.16 | 0.68 | 20.05 | | 0.93 | 4.78 |
| 2013 | 685796.12 | 602561.30 | BRK | 18.52 | 18.50 | 1.19 | 0.50 | 20.83 | | 0.64 | 2.33 |
| 2014 | 685794.18 | 602564.61 | BRK | 15.98 | 16.08 | 1.06 | 0.87 | 20.62 | | 0.81 | 4.54 |
| 2015 | 685850.37 | 602564.79 | BRK | 18.26 | 18.19 | 1.27 | 0.48 | 20.47 | | 0.57 | 2.28 |
| 2016 | 685853.96 | 602566.89 | BRK | 15.74 | 15.81 | 1.18 | 0.57 | 20.38 | | 0.72 | 4.57 |
| 2017 | 685836.81 | 602585.82 | BRK | 18.40 | 18.35 | 1.29 | 0.46 | 20.64 | | 0.55 | 2.29 |
| 2018 | 685840.09 | 602587.74 | BRK | 15.92 | 15.87 | 1.21 | 0.87 | 20.36 | | 0.70 | 4.50 |
| 2019 | 685920.13 | 602349.50 | BRK | 16.22 | 16.25 | 1.20 | 0.46 | 18.61 | | 0.71 | 2.37 |
| 2020 | 685922.56 | 602345.35 | BRK | 13.69 | 13.75 | 1.16 | 0.55 | 18.50 | | 0.89 | 4.75 |
| 2021 | 685856.33 | 602313.51 | BRK | 8.60 | 8.60 | 1.25 | | 17.85 | | 0.65 | 9.25 |
| 2022 | 685851.29 | 602322.14 | BRK | 8.60 | 8.69 | 1.17 | | 17.95 | | 0.66 | 9.26 |
| 2023 | 685843.45 | 602327.59 | BRK | 14.35 | 14.32 | 1.27 | | 17.83 | | 0.59 | 3.50 |
| 2024 | 685860.64 | 602306.13 | BRK | 14.29 | 14.24 | 1.16 | | 17.43 | | 0.67 | 3.19 |
| 2025 | 685912.14 | 602513.81 | BRK | 9.97 | 9.92 | 1.29 | | 17.65 | | 0.73 | 7.73 |
| 2026 | 685914.02 | 602508.21 | BRK | 13.91 | 13.90 | 1.17 | | 17.51 | | 0.64 | 3.61 |
| 2027 | 685826.05 | 602460.69 | BRK | 15.80 | 15.75 | 1.28 | 0.76 | 20.63 | | 0.87 | 4.88 |
| 2028 | 685824.03 | 602464.16 | BRK | 18.39 | 18.45 | 1.07 | 0.52 | 20.70 | | 0.65 | 2.24 |
| 2029 | 685833.67 | 602645.46 | BRK | 13.55 | 13.60 | 1.12 | | 18.09 | | 0.57 | 4.48 |
| 2030 | 685815.80 | 602627.68 | BRK | 15.32 | 15.40 | 1.05 | | 18.60 | | 0.59 | 3.20 |
| 2031 | 685813.88 | 602630.17 | BRK | 13.75 | 13.84 | 1.03 | | 18.16 | | 0.64 | 4.33 |
| 2032 | 685705.01 | 602711.44 | BRK | 18.93 | 18.85 | 1.34 | 0.63 | 23.69 | | 0.72 | 4.85 |
| 2033 | 685708.54 | 602713.51 | BRK | 21.49 | 21.43 | 1.21 | 0.54 | 23.71 | | 0.53 | 2.28 |
| 2034 | 685697.16 | 602677.88 | BRK | 20.80 | 20.86 | 1.16 | 0.53 | 23.18 | | 0.73 | 2.31 |
| 2035 | 685701.40 | 602680.36 | BRK | 18.36 | 18.31 | 1.27 | 0.69 | 23.22 | | 0.68 | 4.91 |
| 2036 | 685711.77 | 602657.46 | BRK | 20.09 | 20.03 | 1.24 | 0.48 | 22.43 | | 0.68 | 2.40 |
| 2037 | 685756.42 | 602678.84 | BRK | 17.22 | 17.19 | 1.22 | 0.88 | 22.05 | | 0.77 | 4.86 |
| 2038 | 685753.99 | 602681.99 | BRK | 19.87 | 19.96 | 1.11 | 0.51 | 22.16 | | 0.59 | 2.20 |
| 2039 | 685731.99 | 602720.32 | BRK | 17.52 | 17.48 | 1.29 | 0.62 | 23.88 | | 0.73 | 6.39 |
| 2040 | 685728.85 | 602725.67 | BRK | 21.65 | 21.70 | 1.05 | 0.59 | 23.91 | | 0.57 | 2.21 |
| 2041 | 685707.79 | 602655.13 | BRK | 17.63 | 17.71 | 1.19 | 0.68 | 22.38 | | 0.62 | 4.68 |
| 2042 | 685764.85 | 602717.51 | BRK | 18.00 | 18.00 | 1.23 | 0.69 | 22.97 | | 0.65 | 4.97 |
| 2043 | 685761.00 | 602715.25 | BRK | 20.74 | 20.69 | 1.14 | 0.58 | 23.04 | | 0.62 | 2.35 |
| 2044 | 685822.01 | 602722.01 | BRK | 14.67 | 14.70 | 1.23 | 0.58 | 21.05 | | 0.52 | 6.36 |
| 2045 | 685818.67 | 602720.05 | BRK | 17.24 | 17.25 | 1.10 | 0.60 | 21.20 | | 0.59 | 3.95 |
| 2046 | 685829.80 | 602697.60 | BRK | 17.01 | 16.95 | 1.19 | 0.52 | 20.49 | | 0.63 | 3.54 |
| 2047 | 685833.01 | 602699.48 | BRK | 14.54 | 14.53 | 1.17 | | 20.39 | | 0.73 | 5.86 |
| 2048 | 685746.78 | 602645.58 | BRK | 16.45 | 16.51 | 1.20 | 0.66 | 21.38 | | 0.79 | 4.87 |
| 2049 | 685835.75 | 602641.45 | BRK | 15.78 | 15.83 | 1.16 | | 18.86 | | 0.58 | 3.04 |
| 2050 | 685783.49 | 602786.36 | BRK | 18.41 | 18.42 | 1.22 | 0.57 | 22.93 | | 0.64 | 4.51 |
| 2051 | 685780.08 | 602784.37 | BRK | 21.01 | 20.96 | 1.25 | 0.48 | 23.23 | | 0.54 | 2.27 |
| 2052 | 685805.33 | 602792.97 | BRK | 14.90 | 14.94 | 1.21 | | 21.06 | | 0.58 | 6.12 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2053 | 685802.49 | 602795.13 | BRK | 17.00 | 17.00 | 1.18 | | 21.20 | | 0.55 | 4.21 |
| 2054 | 685827.17 | 602830.98 | BRK | 17.00 | 17.09 | 1.10 | | 20.52 | | 0.60 | 3.43 |
| 2055 | 685744.19 | 602649.99 | BRK | 19.16 | 19.17 | 1.08 | 0.60 | 21.56 | | 0.71 | 2.39 |
| 2056 | 685800.49 | 602883.22 | BRK | 18.20 | 18.19 | 1.12 | | 20.84 | | 0.55 | 2.65 |
| 2057 | 685789.54 | 602905.78 | BRK | 18.45 | 18.41 | 1.14 | | 21.05 | | 0.53 | 2.65 |
| 2058 | 685822.88 | 602664.93 | BRK | 13.52 | 13.60 | 1.10 | | 18.05 | | 0.55 | 4.45 |
| 2059 | 685820.20 | 602668.39 | BRK | 15.71 | 15.70 | 1.19 | | 19.00 | | 0.72 | 3.31 |
| 2060 | 685800.10 | 602650.98 | BRK | 15.00 | 15.03 | 1.11 | | 18.73 | | 0.69 | 3.70 |
| 2061 | 685801.75 | 602648.60 | BRK | 13.74 | 13.73 | 1.11 | | 18.24 | | 0.73 | 4.51 |
| 2062 | 685776.28 | 602694.14 | BRK | 17.21 | 17.27 | 1.11 | 0.69 | 21.94 | | 0.65 | 4.67 |
| 2063 | 685774.25 | 602697.61 | BRK | 19.87 | 19.79 | 1.17 | 0.58 | 22.10 | | 0.56 | 2.31 |
| 2064 | 685811.43 | 602860.66 | BRK | 17.94 | 17.92 | 1.15 | | 20.58 | | 0.55 | 2.66 |
| 2065 | 685790.56 | 602471.83 | BRK | 19.18 | 19.11 | 1.26 | 0.47 | 21.43 | | 0.59 | 2.32 |
| 2066 | 685787.33 | 602469.94 | BRK | 16.76 | 16.78 | 1.19 | 0.86 | 21.14 | | 0.76 | 4.36 |
| 2067 | 685775.15 | 602491.78 | BRK | 16.78 | 16.81 | 1.20 | 0.67 | 21.30 | | 0.85 | 4.49 |
| 2068 | 685778.43 | 602493.70 | BRK | 19.31 | 19.24 | 1.24 | 0.49 | 21.55 | | 0.57 | 2.31 |
| 2069 | 685657.73 | 602799.64 | BRK | 19.07 | 19.02 | 1.29 | 0.63 | 23.81 | | 0.65 | 4.79 |
| 2070 | 685654.59 | 602797.80 | BRK | 21.50 | 21.41 | 1.16 | 0.62 | 23.72 | | 0.52 | 2.30 |
| 2071 | 685671.07 | 602778.48 | BRK | 19.12 | 19.17 | 1.20 | 0.67 | 23.85 | | 0.66 | 4.68 |
| 2072 | 685667.93 | 602776.64 | BRK | 21.54 | 21.46 | 1.25 | 0.55 | 23.77 | | 0.51 | 2.31 |
| 2073 | 685709.39 | 602857.87 | BRK | 20.11 | 20.18 | 1.16 | 0.72 | 24.96 | | 0.64 | 4.78 |
| 2074 | 685711.30 | 602854.60 | BRK | 22.59 | 22.62 | 1.21 | 0.46 | 24.98 | | 0.70 | 2.37 |
| 2075 | 685729.75 | 602872.58 | BRK | 19.68 | 19.68 | 1.20 | 0.62 | 24.61 | | 0.57 | 4.92 |
| 2076 | 685731.81 | 602869.06 | BRK | 22.22 | 22.20 | 1.24 | 0.46 | 24.79 | | 0.89 | 2.59 |
| 2077 | 685795.65 | 602764.51 | BRK | 18.03 | 17.99 | 1.24 | 0.48 | 22.38 | | 0.54 | 4.39 |
| 2078 | 685800.03 | 602767.07 | BRK | 14.66 | 14.70 | 1.16 | 0.69 | 21.81 | | 0.69 | 7.11 |
| 2079 | 685792.82 | 602762.85 | BRK | 18.08 | 18.07 | 1.25 | 0.52 | 22.66 | | 0.62 | 4.59 |
| 2080 | 685789.43 | 602760.87 | BRK | 20.65 | 20.68 | 1.16 | 0.50 | 22.89 | | 0.55 | 2.21 |
| 2081 | 685557.32 | 602969.16 | BRK | 18.98 | 19.01 | 1.22 | 0.75 | 23.66 | | 0.68 | 4.65 |
| 2082 | 685555.43 | 602972.39 | BRK | 21.47 | 21.40 | 1.16 | 0.60 | 23.83 | | 0.67 | 2.43 |
| 2083 | 685468.23 | 603121.32 | BRK | 13.59 | 13.65 | 1.17 | | 18.70 | | 0.70 | 5.05 |
| 2084 | 685465.10 | 603126.67 | BRK | 9.50 | 9.54 | 1.23 | | 18.12 | | 0.64 | 8.59 |
| 2085 | 685475.11 | 603069.32 | BRK | 16.56 | 16.64 | 1.15 | 0.76 | 21.28 | | 0.62 | 4.64 |
| 2086 | 685471.46 | 603067.19 | BRK | 19.02 | 19.03 | 1.08 | 0.61 | 21.30 | | 0.59 | 2.27 |
| 2087 | 685533.61 | 603016.66 | BRK | 18.93 | 19.00 | 1.19 | 0.74 | 23.64 | | 0.72 | 4.65 |
| 2088 | 685530.40 | 603014.78 | BRK | 21.37 | 21.27 | 1.18 | 0.62 | 23.74 | | 0.67 | 2.47 |
| 2089 | 685536.26 | 602955.65 | BRK | 18.58 | 18.61 | 1.19 | 0.84 | 23.25 | | 0.68 | 4.64 |
| 2090 | 685534.28 | 602959.03 | BRK | 21.09 | 21.02 | 1.21 | 0.57 | 23.52 | | 0.71 | 2.50 |
| 2091 | 685507.65 | 603059.40 | BRK | 20.05 | 19.97 | 1.19 | 0.60 | 22.39 | | 0.62 | 2.41 |
| 2092 | 685504.39 | 603057.50 | BRK | 17.59 | 17.56 | 1.29 | 0.81 | 22.35 | | 0.67 | 4.80 |
| 2093 | 685594.51 | 603202.52 | BRK | 16.10 | 16.14 | 1.07 | | 18.54 | | 0.55 | 2.40 |
| 2094 | 685596.79 | 603198.62 | BRK | 13.16 | 13.12 | 1.20 | | 18.61 | | 0.65 | 5.49 |
| 2095 | 685405.10 | 603081.78 | BRK | 15.51 | 15.52 | 1.14 | | 19.24 | | 0.65 | 3.72 |
| 2096 | 685395.56 | 603083.28 | BRK | 9.07 | 9.17 | 1.14 | | 18.76 | | 0.53 | 9.60 |
| 2097 | 685399.62 | 603139.55 | BRK | 9.23 | 9.31 | 1.13 | | 17.85 | | 0.58 | 8.54 |
| 2098 | 685395.05 | 603147.36 | BRK | 15.10 | 15.02 | 1.19 | 0.64 | 18.27 | | 0.70 | 3.24 |
| 2099 | 685423.65 | 603147.98 | BRK | 9.36 | 9.42 | 1.13 | | 17.85 | | 0.56 | 8.43 |
| 2100 | 685441.55 | 603117.41 | BRK | 9.37 | 9.45 | 1.18 | | 18.22 | | 0.72 | 8.77 |
| 2101 | 685420.05 | 603154.14 | BRK | 14.02 | 14.06 | 1.10 | | 18.05 | | 0.60 | 3.99 |
| 2102 | 685444.98 | 603111.56 | BRK | 13.85 | 13.90 | 1.13 | | 18.81 | | 0.77 | 4.91 |
| 2103 | 685491.69 | 603130.73 | BRK | 13.60 | 13.69 | 1.14 | | 18.65 | | 0.58 | 4.96 |
| 2104 | 685488.65 | 603135.92 | BRK | 9.67 | 9.73 | 1.17 | | 18.01 | | 0.54 | 8.28 |
| 2105 | 685470.76 | 603211.63 | BRK | 14.81 | 14.88 | 1.06 | 0.95 | 19.20 | | 0.64 | 4.33 |
| 2106 | 685468.49 | 603181.46 | BRK | 10.83 | 10.89 | 1.17 | 0.71 | 18.67 | | 0.97 | 7.78 |
| 2107 | 685463.60 | 603179.43 | BRK | 14.36 | 14.39 | 1.15 | 0.67 | 18.47 | | 0.84 | 4.08 |
| 2108 | 685616.58 | 603185.75 | BRK | 13.50 | 13.55 | 1.15 | | 18.52 | | 0.62 | 4.98 |
| 2109 | 685614.80 | 603180.19 | BRK | 16.50 | 16.58 | 1.08 | | 18.66 | | 0.58 | 2.07 |
| 2110 | 685473.49 | 603213.23 | BRK | 17.03 | 16.95 | 1.18 | 0.59 | 19.31 | | 0.59 | 2.36 |
| 2111 | 685663.53 | 603121.70 | BRK | 12.50 | 12.57 | 1.17 | | 20.53 | | 0.63 | 7.96 |
| 2112 | 685647.93 | 603127.59 | BRK | 17.52 | 17.45 | 1.31 | | 20.17 | | 0.56 | 2.72 |
| 2113 | 685675.50 | 603099.74 | BRK | 12.76 | 12.84 | 1.09 | | 20.43 | | 0.55 | 7.59 |
| 2114 | 685660.09 | 603105.58 | BRK | 17.84 | 17.78 | 1.25 | | 20.64 | | 0.57 | 2.85 |
| 2115 | 685722.72 | 603040.48 | BRK | 13.00 | 12.98 | 1.12 | | 21.30 | | 0.69 | 8.33 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA / SIDEWALK (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2116 | 685712.78 | 603034.66 | BRK | 18.74 | 18.82 | 1.01 | | 21.47 | | 0.66 | 2.65 |
| 2117 | 685693.81 | 603081.49 | BRK | 13.00 | 13.04 | 1.07 | | 20.64 | | 0.63 | 7.60 |
| 2118 | 685684.52 | 603076.05 | BRK | 18.35 | 18.40 | 1.04 | | 20.79 | | 0.63 | 2.39 |
| 2119 | 685708.47 | 603061.11 | BRK | 13.00 | 13.08 | 1.11 | | 20.93 | | 0.60 | 7.85 |
| 2120 | 685698.80 | 603055.44 | BRK | 18.58 | 18.52 | 1.16 | | 21.14 | | 0.65 | 2.62 |
| 2121 | 685773.30 | 602954.21 | BRK | 13.00 | 13.04 | 1.16 | | 21.26 | | 0.55 | 8.22 |
| 2122 | 685763.36 | 602948.39 | BRK | 18.75 | 18.78 | 1.07 | | 21.80 | | 0.53 | 3.02 |
| 2123 | 685736.47 | 603019.56 | BRK | 13.00 | 13.08 | 1.06 | | 21.52 | | 0.79 | 8.43 |
| 2124 | 685726.38 | 603013.65 | BRK | 18.84 | 18.84 | 1.21 | | 21.65 | | 0.58 | 2.81 |
| 2125 | 685749.74 | 602998.36 | BRK | 13.00 | 13.08 | 1.04 | | 21.42 | | 0.63 | 8.34 |
| 2126 | 685739.58 | 602992.41 | BRK | 18.88 | 18.91 | 1.10 | | 21.96 | | 0.50 | 3.06 |
| 2127 | 685762.24 | 602976.71 | BRK | 13.00 | 13.03 | 1.14 | | 21.38 | | 0.68 | 8.35 |
| 2128 | 685752.10 | 602970.77 | BRK | 18.86 | 18.84 | 1.23 | | 22.08 | | 0.69 | 3.24 |
| 2129 | 685784.68 | 602932.96 | BRK | 13.00 | 13.07 | 1.09 | | 21.06 | | 0.64 | 7.99 |
| 2130 | 685776.69 | 602925.78 | BRK | 18.66 | 18.66 | 1.19 | | 21.44 | | 0.52 | 2.77 |
| 2131 | 685530.42 | 603217.59 | BRK | 14.69 | 14.71 | 1.22 | | 18.23 | | 0.62 | 3.52 |
| 2132 | 685527.38 | 603215.81 | BRK | 17.52 | 17.47 | 1.15 | 0.63 | 19.77 | | 0.53 | 2.31 |
| 2133 | 685368.49 | 603242.19 | BRK | 14.15 | 14.21 | 1.19 | 0.55 | 18.91 | | 0.70 | 4.69 |
| 2134 | 685370.51 | 603238.74 | BRK | 16.71 | 16.63 | 1.19 | 0.62 | 19.08 | | 0.65 | 2.46 |
| 2135 | 685350.10 | 603224.13 | BRK | 17.00 | 16.93 | 1.28 | 0.51 | 19.27 | | 0.55 | 2.34 |
| 2136 | 685348.20 | 603227.37 | BRK | 14.48 | 14.56 | 1.18 | 0.78 | 18.99 | | 0.56 | 4.42 |
| 2137 | 685398.33 | 603339.67 | BRK | 11.28 | 11.38 | 1.05 | 0.84 | 15.97 | | 0.58 | 4.60 |
| 2138 | 685396.24 | 603343.25 | BRK | 13.68 | 13.60 | 1.23 | 0.56 | 15.92 | | 0.53 | 2.32 |
| 2139 | 685420.59 | 603353.66 | BRK | 10.74 | 10.81 | 1.17 | 0.63 | 13.92 | | 0.73 | 3.11 |
| 2140 | 685415.13 | 603354.10 | BRK | 13.30 | 13.31 | 1.22 | 0.50 | 15.53 | | 0.51 | 2.23 |
| 2141 | 685497.87 | 603316.26 | BRK | 7.28 | 7.33 | 1.20 | | 14.80 | | 0.64 | 7.46 |
| 2142 | 685502.33 | 603310.60 | BRK | 12.09 | 12.16 | 1.19 | | 15.11 | | 0.62 | 2.95 |
| 2143 | 685313.22 | 603384.52 | BRK | 10.87 | 10.92 | 1.21 | 0.77 | 15.61 | | 0.60 | 4.69 |
| 2144 | 685315.87 | 603381.57 | BRK | 13.41 | 13.46 | 1.18 | 0.47 | 15.64 | | 0.53 | 2.18 |
| 2145 | 685073.63 | 603554.95 | BRK | 13.10 | 13.03 | 1.16 | 0.61 | 15.32 | | 0.52 | 2.28 |
| 2146 | 685066.32 | 603557.78 | BRK | 10.60 | 10.54 | 1.19 | 0.59 | 14.18 | | 0.60 | 3.64 |
| 2147 | 685216.30 | 603555.13 | BRK | 8.12 | 8.15 | 1.08 | 0.88 | 12.63 | | 0.61 | 4.49 |
| 2148 | 685212.78 | 603553.07 | BRK | 10.75 | 10.67 | 1.32 | 0.50 | 12.97 | | 0.53 | 2.30 |
| 2149 | 685223.70 | 603530.49 | BRK | 10.97 | 10.95 | 1.17 | 0.56 | 13.28 | | 0.61 | 2.34 |
| 2150 | 685227.20 | 603532.54 | BRK | 8.54 | 8.55 | 1.23 | 0.73 | 13.02 | | 0.58 | 4.48 |
| 2151 | 685148.13 | 603569.83 | BRK | 12.29 | 12.20 | 1.22 | 0.57 | 14.53 | | 0.54 | 2.33 |
| 2152 | 685146.90 | 603573.50 | BRK | 9.72 | 9.65 | 1.32 | 0.74 | 14.48 | | 0.63 | 4.83 |
| 2153 | 685143.40 | 603571.74 | BRK | 12.28 | 12.20 | 1.23 | 0.55 | 14.49 | | 0.51 | 2.29 |
| 2154 | 685155.60 | 603606.50 | BRK | 10.79 | 10.75 | 1.18 | 0.55 | 13.01 | | 0.54 | 2.26 |
| 2155 | 685159.12 | 603608.56 | BRK | 8.10 | 8.15 | 1.06 | 0.79 | 12.68 | | 0.58 | 4.53 |
| 2156 | 685143.43 | 603628.34 | BRK | 7.92 | 7.82 | 1.34 | 0.78 | 12.53 | | 0.61 | 4.71 |
| 2157 | 685139.90 | 603626.27 | BRK | 10.61 | 10.52 | 1.20 | 0.58 | 12.92 | | 0.62 | 2.40 |
| 2158 | 685236.54 | 603364.19 | BRK | 12.91 | 12.84 | 1.27 | 0.56 | 16.78 | | 0.56 | 3.94 |
| 2159 | 685239.27 | 603365.79 | BRK | 15.00 | 14.91 | 1.32 | 0.49 | 17.32 | | 0.60 | 2.41 |

Honeywell SA-6 South
Chromium Remedy
Jersey City, New Jersey

Created By: T. Donovan 12/21/16
Checked By: S. Shallard 12/21/16

**TABLE 1. SA-6 SOUTH OPEN SPACE CAP AREA - CONSTRUCTION CONTROL GRID AS BUILT SUMMARY**

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 | 685518.44 | 601481.51 | GRID | 15.72 | 15.73 | 1.11 | 0.55 | 20.00 | | 0.66 | 4.28 |
| 3 | 685543.44 | 601481.51 | GRID | 15.32 | 15.35 | 1.13 | 0.68 | 20.09 | | 0.57 | 4.74 |
| 4 | 685493.4362 | 601506.5129 | GRID | 14.21 | 14.19 | 1.29 | | 19.44 | | 0.55 | 5.25 |
| 6 | 685543.44 | 601506.51 | GRID | 16.56 | 16.64 | 1.12 | 0.45 | 20.14 | | 0.61 | 3.50 |
| 7 | 685568.44 | 601506.51 | GRID | 16.96 | 16.94 | 1.19 | 0.49 | 20.13 | | 0.55 | 3.19 |
| 8 | 685468.44 | 601531.51 | GRID | 13.09 | 13.12 | 1.11 | 0.74 | 18.81 | | 0.54 | 5.69 |
| 9 | 685493.44 | 601531.51 | GRID | 13.72 | 13.75 | 1.19 | 0.52 | 19.99 | | 0.54 | 6.24 |
| 10 | 685543.4362 | 601531.5129 | GRID | 14.75 | 14.84 | 1.17 | | 20.09 | | 0.53 | 5.25 |
| 11 | 685568.44 | 601531.51 | GRID | 15.00 | 15.08 | 1.18 | 0.64 | 20.29 | | 0.59 | 5.21 |
| 12 | 685593.44 | 601531.51 | GRID | 18.07 | 17.96 | 1.28 | 0.58 | 20.29 | | 0.46 | 2.32 |
| 14 | 685468.44 | 601556.51 | GRID | 13.86 | 13.86 | 1.21 | 0.56 | 18.98 | | 0.59 | 5.12 |
| 15 | 685493.44 | 601556.51 | GRID | 15.86 | 15.83 | 1.23 | 0.52 | 20.07 | | 0.50 | 4.24 |
| 16 | 685518.44 | 601556.51 | GRID | 16.67 | 16.76 | 1.14 | 0.48 | 20.07 | | 0.53 | 3.32 |
| 17 | 685543.4362 | 601556.5129 | GRID | 17.01 | 16.97 | 1.29 | | 20.19 | | 0.61 | 3.22 |
| 18 | 685568.4362 | 601556.5129 | GRID | 14.11 | 14.15 | 1.11 | | 20.23 | | 0.57 | 6.08 |
| 19 | 685593.44 | 601556.51 | GRID | 17.41 | 17.49 | 1.17 | 0.48 | 20.16 | | 0.55 | 2.67 |
| 20 | 685443.44 | 601581.51 | GRID | 13.26 | 13.31 | 1.11 | 0.65 | 18.25 | | 0.49 | 4.94 |
| 21 | 685468.44 | 601581.51 | GRID | 14.37 | 14.35 | 1.28 | 0.68 | 18.91 | | 0.49 | 4.56 |
| 22 | 685493.44 | 601581.51 | GRID | 15.75 | 15.69 | 1.30 | 0.49 | 20.04 | | 0.56 | 4.35 |
| 23 | 685518.44 | 601581.51 | GRID | 16.64 | 16.64 | 1.21 | 0.48 | 20.09 | | 0.51 | 3.45 |
| 24 | 685543.44 | 601581.51 | GRID | 17.49 | 17.50 | 1.10 | 0.50 | 20.15 | | 0.56 | 2.64 |
| 25 | 685568.4362 | 601581.5129 | GRID | 17.03 | 17.13 | 1.15 | | 20.10 | | 0.57 | 2.97 |
| 26 | 685418.44 | 601606.51 | GRID | 11.91 | 11.97 | 1.19 | 0.53 | 17.40 | | 0.60 | 5.43 |
| 27 | 685443.44 | 601606.51 | GRID | 13.82 | 13.80 | 1.30 | 0.65 | 18.39 | | 0.62 | 4.59 |
| 29 | 685493.44 | 601606.51 | GRID | 15.28 | 15.29 | 1.24 | 0.74 | 19.99 | | 0.60 | 4.70 |
| 30 | 685518.44 | 601606.51 | GRID | 16.15 | 16.21 | 1.17 | 0.67 | 20.09 | | 0.59 | 3.89 |
| 31 | 685543.44 | 601606.51 | GRID | 16.75 | 16.75 | 1.21 | 0.53 | 20.13 | | 0.58 | 3.37 |
| 32 | 685393.44 | 601631.51 | GRID | 11.44 | 11.47 | 1.19 | 0.72 | 17.23 | | 0.62 | 5.76 |
| 33 | 685418.44 | 601631.51 | GRID | 13.25 | 13.31 | 1.14 | 0.62 | 17.90 | | 0.55 | 4.58 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 34 | 685443.44 | 601631.51 | GRID | 13.79 | 13.80 | 1.19 | 0.51 | 18.27 | | 0.57 | 4.47 |
| 35 | 685468.44 | 601631.51 | GRID | 15.71 | 15.71 | 1.25 | 0.48 | 18.78 | | 0.66 | 3.06 |
| 36 | 685493.44 | 601631.51 | GRID | 14.79 | 14.80 | 1.26 | 0.54 | 19.52 | | 0.59 | 4.72 |
| 37 | 685518.44 | 601631.51 | GRID | 15.60 | 15.58 | 1.26 | 0.73 | 20.08 | | 0.61 | 4.50 |
| 38 | 685543.44 | 601631.51 | GRID | 16.01 | 15.98 | 1.26 | 0.58 | 20.10 | | 0.56 | 4.12 |
| 39 | 685393.44 | 601656.51 | GRID | 12.63 | 12.66 | 1.19 | 0.57 | 17.68 | | 0.58 | 5.02 |
| 40 | 685443.44 | 601656.51 | GRID | 13.74 | 13.70 | 1.21 | 0.59 | 18.34 | | 0.65 | 4.64 |
| 41 | 685468.44 | 601656.51 | GRID | 15.64 | 15.68 | 1.18 | 0.54 | 18.67 | | 0.57 | 3.00 |
| 42 | 685493.44 | 601656.51 | GRID | 16.11 | 16.13 | 1.22 | 0.48 | 19.10 | | 0.46 | 2.98 |
| 43 | 685518.44 | 601656.51 | GRID | 16.65 | 16.55 | 1.24 | 0.64 | 20.05 | | 0.51 | 3.50 |
| 44 | 685368.44 | 601681.51 | GRID | 11.59 | 11.63 | 1.22 | 0.66 | 17.43 | | 0.50 | 5.80 |
| 45 | 685393.44 | 601681.51 | GRID | 15.72 | 15.72 | 1.24 | 0.47 | 18.05 | | 0.62 | 2.34 |
| 46 | 685443.44 | 601681.51 | GRID | 13.67 | 13.64 | 1.25 | 0.47 | 18.22 | | 0.63 | 4.58 |
| 47 | 685468.44 | 601681.51 | GRID | 15.52 | 15.52 | 1.25 | 0.47 | 18.58 | | 0.57 | 3.06 |
| 48 | 685493.44 | 601681.51 | GRID | 15.97 | 15.95 | 1.26 | 0.47 | 18.97 | | 0.58 | 3.02 |
| 49 | 685343.44 | 601706.51 | GRID | 10.97 | 10.90 | 1.36 | 0.52 | 17.39 | | 0.54 | 6.49 |
| 50 | 685393.44 | 601706.51 | GRID | 15.97 | 15.96 | 1.21 | 0.58 | 18.27 | | 0.52 | 2.31 |
| 51 | 685443.44 | 601706.51 | GRID | 13.55 | 13.52 | 1.27 | 0.67 | 18.14 | | 0.51 | 4.62 |
| 52 | 685468.44 | 601706.51 | GRID | 15.38 | 15.37 | 1.21 | 0.48 | 18.07 | | 0.50 | 2.69 |
| 53 | 685493.44 | 601706.51 | GRID | 14.27 | 14.32 | 1.20 | 0.55 | 18.36 | | 0.50 | 4.04 |
| 54 | 685318.44 | 601731.51 | GRID | 10.69 | 10.63 | 1.18 | 0.52 | 17.92 | | 0.54 | 7.29 |
| 55 | 685368.44 | 601731.51 | GRID | 16.17 | 16.14 | 1.22 | 0.60 | 18.51 | | 0.55 | 2.37 |
| 56 | 685393.44 | 601731.51 | GRID | 16.28 | 16.24 | 1.25 | 0.50 | 18.61 | | 0.62 | 2.37 |
| 57 | 685443.44 | 601731.51 | GRID | 13.53 | 13.48 | 1.32 | 0.50 | 18.08 | | 0.54 | 4.60 |
| 58 | 685343.44 | 601756.51 | GRID | 16.57 | 16.54 | 1.14 | 0.52 | 18.99 | | 0.65 | 2.45 |
| 59 | 685368.44 | 601756.51 | GRID | 16.33 | 16.35 | 1.15 | 0.60 | 18.71 | | 0.61 | 2.36 |
| 61 | 685443.44 | 601756.51 | GRID | 13.55 | 13.55 | 1.12 | 0.84 | 18.09 | | 0.61 | 4.53 |
| 62 | 685293.4362 | 601781.5129 | GRID | 10.50 | 10.42 | 1.25 | | 19.14 | | 0.60 | 8.73 |
| 63 | 685318.44 | 601781.51 | GRID | 17.40 | 17.40 | 1.15 | 0.50 | 19.62 | | 0.57 | 2.22 |
| 64 | 685343.44 | 601781.51 | GRID | 16.94 | 16.91 | 1.13 | 0.53 | 19.47 | | 0.65 | 2.55 |
| 65 | 685368.44 | 601781.51 | GRID | 16.55 | 16.53 | 1.20 | 0.58 | 18.97 | | 0.66 | 2.44 |
| 66 | 685393.44 | 601781.51 | GRID | 16.31 | 16.26 | 1.21 | 0.62 | 18.61 | | 0.51 | 2.34 |
| 67 | 685418.44 | 601781.51 | GRID | 16.14 | 16.13 | 1.17 | 0.52 | 18.36 | | 0.53 | 2.22 |
| 69 | 685268.4362 | 601806.5129 | GRID | 11.03 | 10.95 | 1.32 | | 19.36 | | 0.56 | 8.41 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 70 | 685318.44 | 601806.51 | GRID | 18.11 | 18.05 | 1.20 | 0.50 | 20.30 | | 0.56 | 2.25 |
| 71 | 685343.44 | 601806.51 | GRID | 17.66 | 17.63 | 1.17 | 0.45 | 19.87 | | 0.56 | 2.24 |
| 72 | 685368.44 | 601806.51 | GRID | 17.12 | 17.11 | 1.13 | 0.56 | 19.39 | | 0.59 | 2.28 |
| 73 | 685393.44 | 601806.51 | GRID | 16.68 | 16.61 | 1.20 | 0.52 | 18.96 | | 0.63 | 2.35 |
| 74 | 685418.44 | 601806.51 | GRID | 16.28 | 16.27 | 1.19 | 0.48 | 18.56 | | 0.56 | 2.29 |
| 75 | 685243.4362 | 601831.5129 | GRID | 12.66 | 12.64 | 1.28 | | 19.11 | | 0.46 | 6.47 |
| 77 | 685318.4362 | 601831.5129 | GRID | 15.70 | 15.68 | 1.28 | | 20.55 | | 0.55 | 4.87 |
| 78 | 685343.44 | 601831.51 | GRID | 18.29 | 18.27 | 1.19 | 0.47 | 20.61 | | 0.68 | 2.34 |
| 79 | 685368.44 | 601831.51 | GRID | 17.73 | 17.67 | 1.22 | 0.45 | 20.02 | | 0.59 | 2.35 |
| 80 | 685393.44 | 601831.51 | GRID | 17.22 | 17.25 | 1.05 | 0.51 | 19.27 | | 0.46 | 2.02 |
| 81 | 685243.44 | 601856.51 | GRID | 15.58 | 15.64 | 1.18 | 0.50 | 20.33 | | 0.52 | 4.69 |
| 82 | 685268.44 | 601856.51 | GRID | 16.08 | 16.08 | 1.25 | 0.48 | 20.55 | | 0.54 | 4.47 |
| 83 | 685293.4362 | 601856.5129 | GRID | 15.74 | 15.83 | 1.18 | | 20.72 | | 0.65 | 4.89 |
| 85 | 685368.44 | 601856.51 | GRID | 18.00 | 17.99 | 1.20 | 0.45 | 20.24 | | 0.60 | 2.26 |
| 86 | 685218.44 | 601881.51 | GRID | 15.64 | 15.58 | 1.16 | 0.60 | 20.38 | | 0.58 | 4.81 |
| 87 | 685243.44 | 601881.51 | GRID | 16.37 | 16.38 | 1.15 | 0.55 | 20.84 | | 0.66 | 4.47 |
| 88 | 685268.44 | 601881.51 | GRID | 18.72 | 18.68 | 1.16 | 0.54 | 20.97 | | 0.58 | 2.29 |
| 89 | 685293.44 | 601881.51 | GRID | 18.57 | 18.49 | 1.19 | 0.60 | 20.86 | | 0.58 | 2.37 |
| 90 | 685343.4362 | 601881.5129 | GRID | 15.15 | 15.20 | 1.20 | | 20.12 | | 0.48 | 4.91 |
| 91 | 685368.4362 | 601881.5129 | GRID | 11.78 | 11.78 | 1.23 | | 17.65 | | 0.52 | 5.86 |
| 92 | 685193.44 | 601906.51 | GRID | 15.54 | 15.50 | 1.14 | 0.75 | 20.38 | | 0.69 | 4.89 |
| 93 | 685218.44 | 601906.51 | GRID | 16.30 | 16.26 | 1.19 | 0.53 | 20.87 | | 0.69 | 4.61 |
| 94 | 685243.44 | 601906.51 | GRID | 18.74 | 18.67 | 1.21 | 0.56 | 21.09 | | 0.66 | 2.43 |
| 95 | 685268.44 | 601906.51 | GRID | 18.62 | 18.56 | 1.17 | 0.58 | 20.84 | | 0.53 | 2.28 |
| 96 | 685293.44 | 601906.51 | GRID | 18.47 | 18.40 | 1.16 | 0.59 | 20.71 | | 0.56 | 2.31 |
| 97 | 685318.44 | 601906.51 | GRID | 18.31 | 18.32 | 1.14 | 0.49 | 20.56 | | 0.60 | 2.23 |
| 99 | 685193.44 | 601931.51 | GRID | 15.75 | 15.79 | 1.10 | 0.81 | 20.60 | | 0.78 | 4.81 |
| 101 | 685243.44 | 601931.51 | GRID | 18.58 | 18.54 | 1.17 | 0.53 | 20.81 | | 0.57 | 2.27 |
| 102 | 685268.44 | 601931.51 | GRID | 18.48 | 18.43 | 1.15 | 0.58 | 20.72 | | 0.56 | 2.29 |
| 103 | 685293.44 | 601931.51 | GRID | 18.37 | 18.36 | 1.19 | 0.51 | 20.57 | | 0.51 | 2.21 |
| 104 | 685168.44 | 601956.51 | GRID | 14.56 | 14.64 | 1.11 | 0.65 | 19.76 | | 0.63 | 5.12 |
| 105 | 685193.44 | 601956.51 | GRID | 18.03 | 18.13 | 1.04 | 0.52 | 20.27 | | 0.58 | 2.14 |
| 107 | 685243.44 | 601956.51 | GRID | 18.28 | 18.37 | 1.05 | 0.55 | 20.57 | | 0.61 | 2.20 |
| 108 | 685268.44 | 601956.51 | GRID | 18.29 | 18.38 | 1.03 | 0.58 | 20.62 | | 0.63 | 2.24 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 109 | 685293.44 | 601956.51 | GRID | 18.22 | 18.30 | 1.02 | 0.57 | 20.56 | | 0.66 | 2.26 |
| 110 | 685143.44 | 601981.51 | GRID | 13.64 | 13.74 | 1.03 | 0.59 | 18.81 | | 0.77 | 5.08 |
| 111 | 685168.44 | 601981.51 | GRID | 17.22 | 17.31 | 1.04 | 0.56 | 19.46 | | 0.55 | 2.15 |
| 112 | 685193.44 | 601981.51 | GRID | 17.44 | 17.54 | 1.01 | 0.60 | 19.70 | | 0.56 | 2.16 |
| 113 | 685218.44 | 601981.51 | GRID | 17.67 | 17.75 | 1.04 | 0.55 | 19.88 | | 0.55 | 2.13 |
| 114 | 685243.44 | 601981.51 | GRID | 17.85 | 17.94 | 1.00 | 0.62 | 20.15 | | 0.59 | 2.21 |
| 115 | 685268.44 | 601981.51 | GRID | 17.92 | 18.01 | 1.02 | 0.52 | 20.30 | | 0.75 | 2.29 |
| 116 | 685118.44 | 602006.51 | GRID | 13.00 | 13.10 | 1.00 | 0.58 | 17.83 | | 0.59 | 4.74 |
| 117 | 685168.44 | 602006.51 | GRID | 16.62 | 16.71 | 1.05 | 0.55 | 19.20 | | 0.72 | 2.49 |
| 118 | 685193.44 | 602006.51 | GRID | 16.85 | 16.94 | 1.06 | 0.52 | 19.20 | | 0.67 | 2.26 |
| 119 | 685218.44 | 602006.51 | GRID | 17.08 | 17.16 | 1.05 | 0.55 | 19.37 | | 0.60 | 2.20 |
| 121 | 685268.44 | 602006.51 | GRID | 17.52 | 17.59 | 1.05 | 0.58 | 19.69 | | 0.47 | 2.10 |
| 122 | 685118.44 | 602031.51 | GRID | 13.00 | 13.10 | 1.12 | 0.45 | 17.95 | | 0.59 | 4.85 |
| 123 | 685143.44 | 602031.51 | GRID | 16.11 | 16.20 | 1.03 | 0.55 | 19.08 | | 0.61 | 2.87 |
| 124 | 685168.44 | 602031.51 | GRID | 16.20 | 16.30 | 1.15 | 0.55 | 18.90 | | 0.52 | 2.60 |
| 125 | 685193.44 | 602031.51 | GRID | 16.32 | 16.39 | 1.18 | 0.50 | 18.93 | | 0.68 | 2.54 |
| 126 | 685218.44 | 602031.51 | GRID | 16.50 | 16.59 | 1.07 | 0.53 | 18.92 | | 0.72 | 2.32 |
| 127 | 685118.44 | 602056.51 | GRID | 14.00 | 13.92 | 1.26 | 0.59 | 18.61 | | 0.55 | 4.69 |
| 128 | 685143.44 | 602056.51 | GRID | 16.15 | 16.22 | 1.06 | 0.55 | 19.10 | | 0.64 | 2.87 |
| 129 | 685168.44 | 602056.51 | GRID | 16.07 | 16.16 | 1.02 | 0.56 | 19.07 | | 0.53 | 2.91 |
| 130 | 685193.44 | 602056.51 | GRID | 16.21 | 16.29 | 1.13 | 0.45 | 18.77 | | 0.54 | 2.48 |
| 131 | 685218.44 | 602056.51 | GRID | 16.34 | 16.43 | 1.08 | 0.57 | 18.64 | | 0.55 | 2.21 |
| 132 | 685068.4362 | 602081.5129 | GRID | 4.37 | 4.46 | 1.01 | | 18.34 | 0.75 | | 13.88 |
| 134 | 685143.44 | 602081.51 | GRID | 16.50 | 16.58 | 1.08 | 0.50 | 19.05 | | 0.56 | 2.46 |
| 135 | 685168.44 | 602081.51 | GRID | 16.30 | 16.39 | 1.00 | 0.58 | 19.11 | | 0.59 | 2.72 |
| 136 | 685193.44 | 602081.51 | GRID | 16.11 | 16.19 | 1.00 | 0.59 | 18.95 | | 0.61 | 2.77 |
| 137 | 685218.44 | 602081.51 | GRID | 16.14 | 16.23 | 1.10 | 0.46 | 18.61 | | 0.56 | 2.38 |
| 138 | 685043.4362 | 602106.5129 | GRID | 4.55 | 4.49 | 1.27 | | 18.20 | | 0.55 | 13.71 |
| 140 | 685093.4362 | 602106.5129 | GRID | 4.78 | 4.86 | 1.01 | | 19.05 | 0.56 | | 14.19 |
| 141 | 685118.4362 | 602106.5129 | GRID | 5.02 | 5.08 | 1.02 | | 19.08 | | 0.64 | 14.00 |
| 142 | 685168.44 | 602106.51 | GRID | 16.64 | 16.73 | 1.02 | 0.61 | 19.09 | | 0.59 | 2.36 |
| 143 | 685193.44 | 602106.51 | GRID | 16.31 | 16.40 | 1.01 | 0.57 | 19.12 | | 0.67 | 2.72 |
| 144 | 685068.44 | 602131.51 | GRID | 14.98 | 15.01 | 1.16 | 0.66 | 19.13 | | 0.53 | 4.12 |
| 145 | 685118.4362 | 602131.5129 | GRID | 5.19 | 5.13 | 1.15 | | 19.05 | 0.55 | | 13.92 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 146 | 685143.4362 | 602131.5129 | GRID | 5.42 | 5.50 | 1.01 | | 19.07 | 0.54 | | 13.57 |
| 147 | 685043.44 | 602156.51 | GRID | 15.05 | 15.06 | 1.23 | 0.64 | 19.70 | | 0.54 | 4.64 |
| 148 | 685093.44 | 602156.51 | GRID | 17.85 | 17.78 | 1.18 | 0.58 | 20.09 | | 0.56 | 2.31 |
| 149 | 685143.4362 | 602156.5129 | GRID | 5.59 | 5.61 | 1.10 | | 19.11 | 0.54 | | 13.50 |
| 150 | 685168.4362 | 602156.5129 | GRID | 5.82 | 5.88 | 1.03 | | 18.70 | 0.50 | | 12.82 |
| 151 | 684993.44 | 602181.51 | GRID | 5.65 | 5.58 | 1.19 | 0.77 | 19.43 | | 0.59 | 13.85 |
| 152 | 685018.44 | 602181.51 | GRID | 15.74 | 15.82 | 1.18 | 0.56 | 20.06 | | 0.58 | 4.24 |
| 153 | 685043.44 | 602181.51 | GRID | 15.20 | 15.28 | 1.15 | 0.83 | 20.01 | | 0.51 | 4.73 |
| 154 | 685068.44 | 602181.51 | GRID | 17.51 | 17.56 | 1.06 | 0.55 | 20.16 | | 0.80 | 2.59 |
| 155 | 685093.44 | 602181.51 | GRID | 17.55 | 17.57 | 1.06 | 0.58 | 19.93 | | 0.72 | 2.36 |
| 156 | 685118.44 | 602181.51 | GRID | 17.55 | 17.55 | 1.11 | 0.59 | 19.76 | | 0.51 | 2.21 |
| 157 | 685143.44 | 602181.51 | GRID | 14.65 | 14.72 | 1.13 | 0.52 | 19.19 | | 0.49 | 4.47 |
| 159 | 684968.44 | 602206.51 | GRID | 6.08 | 6.09 | 1.08 | 0.60 | 20.30 | | 0.57 | 14.21 |
| 160 | 685018.44 | 602206.51 | GRID | 18.26 | 18.28 | 1.10 | 0.58 | 20.45 | | 0.50 | 2.17 |
| 161 | 685068.44 | 602206.51 | GRID | 17.61 | 17.61 | 1.08 | 0.63 | 20.11 | | 0.72 | 2.50 |
| 162 | 684993.44 | 602231.51 | GRID | 18.81 | 18.84 | 1.12 | 0.57 | 21.06 | | 0.53 | 2.22 |
| 163 | 685018.44 | 602231.51 | GRID | 16.00 | 15.94 | 1.18 | 0.90 | 20.74 | | 0.72 | 4.80 |
| 164 | 685068.44 | 602231.51 | GRID | 17.85 | 17.78 | 1.22 | 0.54 | 20.12 | | 0.58 | 2.34 |
| 165 | 685093.44 | 602231.51 | GRID | 15.01 | 15.11 | 1.06 | 0.94 | 19.88 | | 0.69 | 4.77 |
| 166 | 684968.44 | 602256.51 | GRID | 19.36 | 19.37 | 1.10 | 0.55 | 21.58 | | 0.56 | 2.21 |
| 167 | 684993.44 | 602256.51 | GRID | 19.06 | 19.05 | 1.13 | 0.55 | 21.28 | | 0.55 | 2.23 |
| 168 | 685018.44 | 602256.51 | GRID | 16.25 | 16.26 | 1.08 | 0.69 | 20.98 | | 0.76 | 4.72 |
| 169 | 685043.44 | 602256.51 | GRID | 18.43 | 18.44 | 1.11 | 0.60 | 20.65 | | 0.50 | 2.21 |
| 170 | 685068.44 | 602256.51 | GRID | 18.10 | 18.08 | 1.14 | 0.56 | 20.30 | | 0.52 | 2.22 |
| 171 | 684918.44 | 602281.51 | GRID | 7.15 | 7.15 | 1.13 | 0.90 | 21.67 | | 0.49 | 14.52 |
| 172 | 684968.44 | 602281.51 | GRID | 19.61 | 19.63 | 1.07 | 0.59 | 21.81 | | 0.52 | 2.17 |
| 173 | 684993.44 | 602281.51 | GRID | 16.82 | 16.83 | 1.10 | 0.94 | 21.50 | | 0.70 | 4.68 |
| 174 | 685018.44 | 602281.51 | GRID | 19.00 | 19.00 | 1.09 | 0.59 | 21.27 | | 0.58 | 2.27 |
| 175 | 685043.44 | 602281.51 | GRID | 18.69 | 18.68 | 1.13 | 0.60 | 20.91 | | 0.50 | 2.23 |
| 176 | 685068.44 | 602281.51 | GRID | 18.36 | 18.36 | 1.08 | 0.61 | 20.60 | | 0.55 | 2.24 |
| 178 | 684943.44 | 602306.51 | GRID | 20.15 | 20.17 | 1.10 | 0.53 | 22.37 | | 0.57 | 2.20 |
| 179 | 684968.44 | 602306.51 | GRID | 19.86 | 19.89 | 1.17 | 0.48 | 22.09 | | 0.55 | 2.20 |
| 180 | 684993.44 | 602306.51 | GRID | 17.07 | 17.10 | 1.10 | 0.90 | 21.85 | | 0.75 | 4.75 |
| 181 | 685018.44 | 602306.51 | GRID | 19.26 | 19.27 | 1.09 | 0.55 | 21.57 | | 0.66 | 2.30 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 182 | 685043.44 | 602306.51 | GRID | 16.45 | 16.37 | 1.23 | 0.83 | 21.20 | | 0.69 | 4.84 |
| 183 | 684918.44 | 602331.51 | GRID | 17.91 | 17.93 | 1.19 | 0.49 | 22.38 | | 0.53 | 4.45 |
| 184 | 684943.44 | 602331.51 | GRID | 17.80 | 17.81 | 1.15 | 0.52 | 22.29 | | 0.53 | 4.48 |
| 185 | 684968.44 | 602331.51 | GRID | 17.57 | 17.49 | 1.23 | 0.54 | 22.04 | | 0.49 | 4.55 |
| 186 | 684993.44 | 602331.51 | GRID | 19.82 | 19.76 | 1.22 | 0.53 | 22.09 | | 0.58 | 2.33 |
| 187 | 685018.44 | 602331.51 | GRID | 17.03 | 16.94 | 1.18 | 0.99 | 21.41 | | 0.52 | 4.47 |
| 188 | 684893.44 | 602356.51 | GRID | 17.90 | 17.86 | 1.21 | 0.48 | 22.14 | | 0.49 | 4.28 |
| 189 | 684918.44 | 602356.51 | GRID | 17.87 | 17.86 | 1.14 | 0.57 | 22.28 | | 0.55 | 4.42 |
| 190 | 684943.44 | 602356.51 | GRID | 17.85 | 17.84 | 1.18 | 0.49 | 22.25 | | 0.51 | 4.41 |
| 191 | 684968.44 | 602356.51 | GRID | 17.68 | 17.67 | 1.16 | 0.52 | 22.06 | | 0.47 | 4.39 |
| 192 | 684993.44 | 602356.51 | GRID | 17.48 | 17.47 | 1.17 | 0.53 | 22.05 | | 0.55 | 4.58 |
| 193 | 684843.44 | 602381.51 | GRID | 8.70 | 8.73 | 1.20 | 0.46 | 21.34 | | 0.56 | 12.61 |
| 194 | 684868.44 | 602381.51 | GRID | 17.37 | 17.31 | 1.20 | 0.52 | 21.87 | | 0.53 | 4.56 |
| 195 | 684893.44 | 602381.51 | GRID | 17.65 | 17.65 | 1.19 | 0.47 | 22.09 | | 0.53 | 4.44 |
| 196 | 684918.44 | 602381.51 | GRID | 17.82 | 17.83 | 1.10 | 0.60 | 22.19 | | 0.58 | 4.37 |
| 197 | 684943.44 | 602381.51 | GRID | 17.81 | 17.81 | 1.17 | 0.52 | 22.24 | | 0.56 | 4.44 |
| 198 | 684968.44 | 602381.51 | GRID | 17.78 | 17.79 | 1.20 | 0.51 | 22.12 | | 0.49 | 4.34 |
| 199 | 684993.44 | 602381.51 | GRID | 17.62 | 17.62 | 1.16 | 0.49 | 22.02 | | 0.53 | 4.40 |
| 200 | 684868.44 | 602406.51 | GRID | 16.97 | 16.99 | 1.16 | 0.46 | 21.53 | | 0.52 | 4.54 |
| 201 | 684893.44 | 602406.51 | GRID | 17.32 | 17.32 | 1.13 | 0.54 | 21.87 | | 0.54 | 4.55 |
| 202 | 684918.44 | 602406.51 | GRID | 17.63 | 17.62 | 1.21 | 0.50 | 22.11 | | 0.59 | 4.49 |
| 203 | 684943.44 | 602406.51 | GRID | 17.73 | 17.70 | 1.17 | 0.58 | 22.11 | | 0.51 | 4.42 |
| 204 | 684968.44 | 602406.51 | GRID | 17.76 | 17.73 | 1.17 | 0.55 | 22.07 | | 0.53 | 4.34 |
| 205 | 684818.44 | 602431.51 | GRID | 15.03 | 15.11 | 1.12 | 0.52 | 20.06 | | 0.51 | 4.95 |
| 206 | 684843.44 | 602431.51 | GRID | 16.11 | 16.09 | 1.23 | 0.48 | 20.63 | | 0.51 | 4.54 |
| 207 | 684868.44 | 602431.51 | GRID | 16.57 | 16.59 | 1.15 | 0.54 | 21.17 | | 0.52 | 4.58 |
| 208 | 684893.44 | 602431.51 | GRID | 17.00 | 16.94 | 1.22 | 0.54 | 21.54 | | 0.53 | 4.59 |
| 209 | 684918.44 | 602431.51 | GRID | 17.37 | 17.34 | 1.20 | 0.53 | 21.70 | | 0.53 | 4.36 |
| 210 | 684943.44 | 602431.51 | GRID | 17.60 | 17.63 | 1.17 | 0.48 | 22.03 | | 0.51 | 4.40 |
| 211 | 684793.44 | 602456.51 | GRID | 14.01 | 13.97 | 1.24 | 0.62 | 19.12 | | 0.52 | 5.15 |
| 212 | 684818.44 | 602456.51 | GRID | 15.20 | 15.17 | 1.24 | 0.45 | 19.70 | | 0.54 | 4.53 |
| 213 | 684843.44 | 602456.51 | GRID | 15.74 | 15.74 | 1.19 | 0.50 | 20.31 | | 0.56 | 4.57 |
| 214 | 684868.44 | 602456.51 | GRID | 16.27 | 16.27 | 1.15 | 0.57 | 20.85 | | 0.56 | 4.58 |
| 215 | 684893.44 | 602456.51 | GRID | 16.69 | 16.68 | 1.17 | 0.50 | 21.13 | | 0.57 | 4.45 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 216 | 684918.44 | 602456.51 | GRID | 17.11 | 17.07 | 1.19 | 0.56 | 21.26 | | 0.53 | 4.19 |
| 217 | 684768.44 | 602481.51 | GRID | 13.24 | 13.23 | 1.15 | 0.64 | 18.03 | | 0.57 | 4.80 |
| 218 | 684793.44 | 602481.51 | GRID | 14.27 | 14.21 | 1.27 | 0.53 | 18.74 | | 0.57 | 4.53 |
| 219 | 684818.44 | 602481.51 | GRID | 14.86 | 14.85 | 1.18 | 0.51 | 19.41 | | 0.56 | 4.56 |
| 220 | 684843.44 | 602481.51 | GRID | 15.42 | 15.44 | 1.18 | 0.49 | 19.97 | | 0.50 | 4.53 |
| 221 | 684868.44 | 602481.51 | GRID | 15.93 | 15.91 | 1.20 | 0.49 | 20.48 | | 0.51 | 4.57 |
| 222 | 684893.44 | 602481.51 | GRID | 16.43 | 16.40 | 1.16 | 0.58 | 21.03 | | 0.55 | 4.63 |
| 223 | 684918.44 | 602481.51 | GRID | 16.87 | 16.84 | 1.17 | 0.58 | 21.07 | | 0.55 | 4.23 |
| 224 | 684768.44 | 602506.51 | GRID | 13.31 | 13.28 | 1.25 | 0.58 | 18.06 | | 0.59 | 4.77 |
| 225 | 684793.44 | 602506.51 | GRID | 13.98 | 14.03 | 1.04 | 0.65 | 18.50 | | 0.55 | 4.47 |
| 226 | 684818.44 | 602506.51 | GRID | 14.55 | 14.49 | 1.19 | 0.69 | 19.12 | | 0.55 | 4.63 |
| 227 | 684843.44 | 602506.51 | GRID | 15.10 | 15.05 | 1.22 | 0.58 | 19.68 | | 0.55 | 4.63 |
| 228 | 684868.44 | 602506.51 | GRID | 15.62 | 15.62 | 1.16 | 0.60 | 20.33 | | 0.59 | 4.71 |
| 229 | 684893.44 | 602506.51 | GRID | 16.12 | 16.18 | 1.12 | 0.56 | 20.66 | | 0.46 | 4.48 |
| 230 | 684743.44 | 602531.51 | GRID | 12.58 | 12.60 | 1.14 | 0.76 | 17.67 | | 0.52 | 5.07 |
| 231 | 684768.44 | 602531.51 | GRID | 15.82 | 15.81 | 1.21 | 0.47 | 18.01 | | 0.52 | 2.20 |
| 232 | 684793.44 | 602531.51 | GRID | 16.25 | 16.22 | 1.22 | 0.47 | 18.48 | | 0.56 | 2.26 |
| 233 | 684818.44 | 602531.51 | GRID | 16.76 | 16.69 | 1.26 | 0.47 | 18.91 | | 0.49 | 2.22 |
| 234 | 684843.44 | 602531.51 | GRID | 17.30 | 17.35 | 1.12 | 0.54 | 19.59 | | 0.58 | 2.24 |
| 235 | 684868.44 | 602531.51 | GRID | 17.86 | 17.87 | 1.17 | 0.50 | 20.12 | | 0.59 | 2.26 |
| 236 | 684718.44 | 602556.51 | GRID | 7.45 | 7.45 | 1.21 | 0.84 | 17.22 | | 0.55 | 9.77 |
| 237 | 684743.44 | 602556.51 | GRID | 15.59 | 15.67 | 1.18 | 0.46 | 17.80 | | 0.50 | 2.14 |
| 239 | 684843.44 | 602556.51 | GRID | 17.05 | 17.13 | 1.05 | 0.57 | 19.29 | | 0.55 | 2.16 |
| 240 | 684868.44 | 602556.51 | GRID | 17.59 | 17.65 | 1.03 | 0.56 | 19.81 | | 0.58 | 2.17 |
| 241 | 684693.4362 | 602581.5129 | GRID | 5.82 | 5.81 | 1.28 | | 17.31 | | 0.57 | 11.50 |
| 242 | 684718.44 | 602581.51 | GRID | 13.18 | 13.26 | 1.14 | 0.51 | 17.84 | | 0.47 | 4.58 |
| 243 | 684743.44 | 602581.51 | GRID | 15.71 | 15.69 | 1.19 | 0.49 | 17.99 | | 0.59 | 2.30 |
| 244 | 684768.44 | 602581.51 | GRID | 13.86 | 13.79 | 1.26 | 0.55 | 18.43 | | 0.51 | 4.64 |
| 245 | 684793.44 | 602581.51 | GRID | 14.14 | 14.11 | 1.13 | 0.68 | 18.80 | | 0.54 | 4.69 |
| 246 | 684818.44 | 602581.51 | GRID | 14.12 | 14.10 | 1.19 | 0.55 | 19.01 | | 0.53 | 4.90 |
| 247 | 684843.44 | 602581.51 | GRID | 14.33 | 14.41 | 1.11 | 0.77 | 19.01 | | 0.56 | 4.59 |
| 248 | 684693.4362 | 602606.5129 | GRID | 5.20 | 5.29 | 1.15 | | 18.71 | | 0.56 | 13.41 |
| 249 | 684743.44 | 602606.51 | GRID | 16.46 | 16.49 | 1.12 | 0.54 | 19.12 | | 0.59 | 2.64 |
| 250 | 684768.44 | 602606.51 | GRID | 15.98 | 16.03 | 1.19 | 0.53 | 19.10 | | 0.54 | 3.07 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 251 | 684793.44 | 602606.51 | GRID | 14.46 | 14.37 | 1.24 | 0.54 | 19.06 | | 0.54 | 4.69 |
| 252 | 684818.44 | 602606.51 | GRID | 14.27 | 14.32 | 1.10 | 0.60 | 19.08 | | 0.53 | 4.76 |
| 253 | 684693.4362 | 602631.5129 | GRID | 5.45 | 5.52 | 1.07 | | 19.05 | | 0.56 | 13.53 |
| 254 | 684718.4362 | 602631.5129 | GRID | 5.80 | 5.85 | 1.10 | | 19.11 | | 0.52 | 13.26 |
| 255 | 684768.44 | 602631.51 | GRID | 17.04 | 17.07 | 1.17 | 0.45 | 19.31 | | 0.55 | 2.23 |
| 256 | 684793.44 | 602631.51 | GRID | 16.34 | 16.43 | 1.03 | 0.56 | 19.09 | | 0.50 | 2.66 |
| 257 | 684818.44 | 602631.51 | GRID | 16.19 | 16.18 | 1.12 | 0.59 | 19.04 | | 0.52 | 2.86 |
| 259 | 684718.4362 | 602656.5129 | GRID | 6.06 | 5.98 | 1.28 | | 19.35 | | 0.52 | 13.37 |
| 260 | 684743.4362 | 602656.5129 | GRID | 6.41 | 6.45 | 1.08 | | 19.24 | | 0.62 | 12.79 |
| 261 | 684793.44 | 602656.51 | GRID | 14.54 | 14.62 | 1.12 | 0.61 | 19.07 | | 0.55 | 4.46 |
| 263 | 684743.4362 | 602681.5129 | GRID | 6.67 | 6.69 | 1.22 | | 19.49 | | 0.64 | 12.81 |
| 264 | 684768.4362 | 602681.5129 | GRID | 7.01 | 7.01 | 1.13 | | 18.98 | | 0.59 | 11.97 |
| 265 | 684793.4362 | 602681.5129 | GRID | 7.37 | 7.34 | 1.21 | | 17.88 | | 0.65 | 10.54 |
| 545 | 685526.43 | 601442.32 | BNDY | 12.92 | 13.01 | 1.02 | 0.57 | 15.13 | | 0.54 | 2.12 |
| 546 | 685543.45 | 601459.45 | BNDY | 13.45 | 13.37 | 1.27 | 0.46 | 15.63 | | 0.52 | 2.25 |
| 547 | 685561.91 | 601478.03 | BNDY | 14.24 | 14.20 | 1.12 | 0.59 | 16.42 | | 0.51 | 2.22 |
| 548 | 685583.37 | 601539.44 | BRK | 15.12 | 15.18 | 1.13 | 0.81 | 20.20 | | 0.48 | 5.02 |
| 549 | 685595.8952 | 601578.0005 | BRK | 14.21 | 14.27 | 1.19 | | 18.24 | | 0.50 | 3.96 |
| 550 | 685562.63 | 601543.70 | BRK | 17.48 | 17.45 | 1.17 | 0.49 | 20.14 | | 0.54 | 2.69 |
| 551 | 685559.4866 | 601547.9749 | BRK | 13.94 | 14.02 | 1.16 | | 20.17 | | 0.59 | 6.15 |
| 552 | 685555.5634 | 601552.5373 | BRK | 13.93 | 13.97 | 1.17 | | 20.10 | | 0.47 | 6.13 |
| 553 | 685552.5036 | 601556.6952 | BRK | 17.37 | 17.31 | 1.21 | | 20.17 | | 0.56 | 2.86 |
| 554 | 685602.63 | 601551.44 | BRK | 17.71 | 17.63 | 1.26 | 0.49 | 20.17 | | 0.52 | 2.54 |
| 555 | 685524.8988 | 601529.9774 | BRK | 13.12 | 13.20 | 1.18 | | 20.09 | | 0.55 | 6.89 |
| 556 | 685521.8453 | 601534.1334 | BRK | 16.56 | 16.41 | 1.25 | | 20.11 | | 0.58 | 3.70 |
| 557 | 685518.43 | 601506.14 | BRK | 15.53 | 15.44 | 1.25 | 0.47 | 20.01 | | 0.53 | 4.57 |
| 558 | 685516.84 | 601455.37 | BNDY | 13.73 | 13.68 | 1.13 | 0.56 | 18.14 | | 0.45 | 4.47 |
| 559 | 685566.10 | 601602.95 | BRK | 17.39 | 17.30 | 1.29 | 0.63 | 20.11 | | 0.89 | 2.81 |
| 560 | 685557.11 | 601621.51 | BRK | 16.15 | 16.11 | 1.29 | 0.53 | 19.95 | | 0.50 | 3.83 |
| 561 | 685572.96 | 601633.24 | BNDY | 9.96 | 10.05 | 1.17 | 0.46 | 13.83 | | 0.57 | 3.79 |
| 562 | 685589.38 | 601610.88 | BNDY | 10.19 | 10.10 | 1.25 | 0.48 | 13.66 | | 0.54 | 3.56 |
| 563 | 685606.3327 | 601587.7847 | BNDY | 9.93 | 10.03 | 1.06 | | 13.51 | | 0.55 | 3.48 |
| 564 | 685633.80 | 601550.37 | BNDY | 9.78 | 9.77 | 1.23 | 0.48 | 13.00 | | 0.75 | 3.23 |
| 565 | 685622.62 | 601565.61 | BNDY | 9.96 | 10.03 | 1.14 | 0.48 | 13.19 | | 0.56 | 3.16 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 566 | 685614.41 | 601530.85 | BNDY | 15.70 | 15.79 | 1.01 | 0.58 | 17.88 | | 0.50 | 2.09 |
| 567 | 685591.47 | 601507.77 | BNDY | 15.02 | 15.06 | 1.08 | 0.54 | 17.21 | | 0.53 | 2.15 |
| 568 | 685577.88 | 601494.10 | BNDY | 14.55 | 14.65 | 1.13 | 0.45 | 16.73 | | 0.50 | 2.09 |
| 569 | 685488.0585 | 601495.4211 | BNDY | 14.30 | 14.31 | 1.09 | | 18.26 | | 0.52 | 3.95 |
| 570 | 685501.08 | 601477.69 | BNDY | 14.94 | 14.96 | 1.05 | 0.55 | 18.25 | | 0.51 | 3.29 |
| 571 | 685474.3133 | 601513.2966 | BNDY | 13.64 | 13.58 | 1.31 | | 18.30 | | 0.52 | 4.71 |
| 572 | 685459.92 | 601533.74 | BNDY | 12.84 | 12.83 | 1.08 | 0.65 | 18.25 | | 0.64 | 5.42 |
| 573 | 685442.87 | 601556.12 | BNDY | 12.43 | 12.43 | 1.11 | 0.87 | 18.08 | | 0.53 | 5.66 |
| 574 | 685428.08 | 601576.27 | BNDY | 12.19 | 12.21 | 1.06 | 0.59 | 17.34 | | 0.65 | 5.14 |
| 575 | 685413.27 | 601596.44 | BNDY | 11.95 | 12.02 | 1.10 | 0.53 | 17.08 | | 0.57 | 5.06 |
| 576 | 685398.47 | 601616.59 | BNDY | 11.42 | 11.44 | 1.17 | 0.55 | 17.02 | | 0.55 | 5.58 |
| 577 | 685383.68 | 601636.74 | BNDY | 11.34 | 11.31 | 1.18 | 0.59 | 16.96 | | 0.64 | 5.65 |
| 578 | 685368.88 | 601656.89 | BNDY | 11.27 | 11.24 | 1.18 | 0.58 | 15.82 | | 0.53 | 4.58 |
| 579 | 685558.28 | 601653.23 | BNDY | 9.90 | 9.93 | 1.22 | 0.51 | 13.58 | | 0.54 | 3.65 |
| 581 | 685543.38 | 601673.52 | BNDY | 9.88 | 9.87 | 1.24 | 0.48 | 13.37 | | 0.49 | 3.50 |
| 582 | 685528.60 | 601693.65 | BNDY | 9.84 | 9.81 | 1.10 | 0.61 | 13.23 | | 0.50 | 3.41 |
| 583 | 685469.10 | 601609.94 | BRK | 15.99 | 15.91 | 1.21 | 0.66 | 18.82 | | 0.57 | 2.91 |
| 584 | 685468.06 | 601601.70 | BRK | 14.55 | 14.56 | 1.21 | 0.80 | 18.89 | | 0.60 | 4.33 |
| 585 | 685534.63 | 601655.70 | BRK | 15.46 | 15.38 | 1.32 | 0.46 | 19.31 | | 0.51 | 3.93 |
| 586 | 685515.15 | 601685.29 | BRK | 14.82 | 14.60 | 1.37 | 0.56 | 18.44 | | 0.55 | 3.84 |
| 587 | 685503.84 | 601702.15 | BRK | 14.49 | 14.45 | 1.13 | 0.62 | 17.92 | | 0.47 | 3.48 |
| 588 | 685484.63 | 601722.61 | BRK | 15.55 | 15.47 | 1.25 | 0.54 | 17.98 | | 0.53 | 2.52 |
| 589 | 685482.47 | 601731.53 | BRK | 11.10 | 11.14 | 1.21 | 0.78 | 17.58 | | 0.57 | 6.44 |
| 590 | 685467.89 | 601733.01 | BRK | 13.13 | 13.22 | 1.16 | 0.84 | 17.99 | | 0.51 | 4.77 |
| 591 | 685467.14 | 601729.90 | BRK | 15.25 | 15.18 | 1.19 | 0.63 | 18.01 | | 0.48 | 2.83 |
| 592 | 685465.84 | 601749.83 | BRK | 15.15 | 15.09 | 1.19 | 0.58 | 17.93 | | 1.01 | 2.84 |
| 593 | 685444.26 | 601779.76 | BRK | 13.57 | 13.66 | 1.14 | 0.78 | 17.81 | | 0.59 | 4.15 |
| 594 | 685429.29 | 601800.21 | BRK | 15.09 | 15.00 | 1.31 | 0.49 | 17.52 | | 0.66 | 2.53 |
| 595 | 685453.48 | 601767.05 | BRK | 15.07 | 14.98 | 1.26 | 0.56 | 17.98 | | 0.57 | 3.00 |
| 596 | 685514.37 | 601713.04 | BNDY | 9.77 | 9.72 | 1.19 | 0.52 | 12.96 | | 0.54 | 3.25 |
| 597 | 685499.50 | 601733.28 | BNDY | 9.70 | 9.78 | 1.22 | 0.52 | 12.69 | | 0.52 | 2.91 |
| 598 | 685485.10 | 601752.90 | BNDY | 9.64 | 9.66 | 1.33 | 0.50 | 12.54 | | 0.54 | 2.89 |
| 599 | 685469.40 | 601774.28 | BNDY | 9.60 | 9.70 | 1.11 | 0.45 | 12.32 | | 0.67 | 2.62 |
| 600 | 685454.74 | 601794.25 | BNDY | 9.64 | 9.70 | 1.20 | 0.60 | 12.05 | | 0.55 | 2.35 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 601 | 685439.85 | 601814.53 | BNDY | 9.68 | 9.64 | 1.28 | 0.42 | 12.00 | | 0.58 | 2.36 |
| 602 | 685425.01 | 601834.73 | BNDY | 9.73 | 9.66 | 1.29 | 0.40 | 11.86 | | 0.52 | 2.20 |
| 603 | 685418.25 | 601641.07 | BRK | 13.45 | 13.41 | 1.26 | 0.62 | 18.04 | | 0.60 | 4.63 |
| 604 | 685415.60 | 601650.93 | BRK | 15.85 | 15.62 | 1.37 | 0.55 | 18.05 | | 0.51 | 2.43 |
| 605 | 685417.81 | 601680.87 | BRK | 15.90 | 15.77 | 1.24 | 0.56 | 18.14 | | 0.57 | 2.37 |
| 606 | 685421.62 | 601680.64 | BRK | 13.35 | 13.42 | 1.20 | 0.79 | 18.06 | | 0.57 | 4.64 |
| 607 | 685417.84 | 601705.42 | BRK | 16.07 | 15.91 | 1.40 | 0.48 | 18.33 | | 0.54 | 2.42 |
| 608 | 685421.83 | 601705.56 | BRK | 13.40 | 13.43 | 1.20 | 0.80 | 18.14 | | 0.51 | 4.71 |
| 609 | 685420.68 | 601733.21 | BRK | 13.46 | 13.54 | 1.08 | 0.86 | 18.20 | | 0.59 | 4.66 |
| 610 | 685416.60 | 601732.96 | BRK | 16.18 | 16.19 | 1.13 | 0.55 | 18.33 | | 0.45 | 2.14 |
| 611 | 685420.69 | 601759.40 | BRK | 13.52 | 13.60 | 1.13 | 0.70 | 18.20 | | 0.56 | 4.60 |
| 612 | 685417.42 | 601761.34 | BRK | 16.06 | 16.08 | 1.13 | 0.57 | 18.32 | | 0.54 | 2.24 |
| 613 | 685367.91 | 601704.46 | BRK | 13.34 | 13.35 | 1.18 | 0.73 | 18.01 | | 0.54 | 4.66 |
| 614 | 685370.79 | 601706.98 | BRK | 15.89 | 15.67 | 1.46 | 0.48 | 18.25 | | 0.64 | 2.58 |
| 615 | 685343.44 | 601731.17 | BRK | 13.71 | 13.67 | 1.28 | 0.58 | 18.23 | | 0.52 | 4.55 |
| 616 | 685345.91 | 601734.17 | BRK | 16.30 | 16.33 | 1.07 | 0.50 | 18.48 | | 0.57 | 2.15 |
| 617 | 685303.14 | 601806.86 | BRK | 18.27 | 18.27 | 1.14 | 0.47 | 20.42 | | 0.55 | 2.15 |
| 618 | 685298.7657 | 601809.6667 | BRK | 15.77 | 15.84 | 1.26 | | 20.32 | | 0.63 | 4.48 |
| 619 | 685294.5364 | 601809.7779 | BRK | 15.35 | 15.41 | 1.17 | | 20.16 | | 0.57 | 4.75 |
| 620 | 685288.9198 | 601805.6788 | BRK | 10.72 | 10.67 | 1.28 | | 19.94 | | 0.56 | 9.26 |
| 621 | 685298.8544 | 601821.3782 | BRK | 15.76 | 15.72 | 1.27 | | 20.29 | | 0.57 | 4.57 |
| 622 | 685295.9426 | 601825.3091 | BRK | 12.49 | 12.56 | 1.16 | | 20.29 | | 0.51 | 7.72 |
| 623 | 685294.6542 | 601831.8216 | BRK | 12.53 | 12.55 | 1.14 | | 20.38 | | 0.51 | 7.83 |
| 624 | 685291.7461 | 601835.7476 | BRK | 15.79 | 15.46 | 1.52 | | 20.41 | | 0.54 | 4.95 |
| 625 | 685324.5764 | 601840.1333 | BRK | 15.86 | 15.66 | 1.46 | | 20.55 | | 0.51 | 4.89 |
| 626 | 685321.5217 | 601844.257 | BRK | 12.44 | 12.40 | 1.25 | | 20.60 | | 0.54 | 8.19 |
| 627 | 685322.6741 | 601852.5775 | BRK | 12.42 | 12.40 | 1.28 | | 20.57 | | 0.62 | 8.16 |
| 628 | 685319.6365 | 601856.6782 | BRK | 15.82 | 15.69 | 1.32 | | 20.47 | | 0.51 | 4.78 |
| 629 | 685341.3972 | 601852.7202 | BRK | 15.72 | 15.42 | 1.39 | | 20.31 | | 0.53 | 4.89 |
| 630 | 685338.4032 | 601856.762 | BRK | 12.37 | 12.42 | 1.17 | | 20.32 | | 0.53 | 7.90 |
| 631 | 685345.647 | 601844.394 | BRK | 15.88 | 15.94 | 1.28 | | 20.33 | | 0.54 | 4.39 |
| 632 | 685347.89 | 601841.36 | BRK | 18.39 | 18.30 | 1.25 | 0.49 | 20.52 | | 0.47 | 2.22 |
| 633 | 685372.8508 | 601864.5453 | BRK | 15.31 | 15.40 | 1.18 | | 19.83 | | 0.57 | 4.43 |
| 634 | 685364.474 | 601869.9863 | BRK | 15.23 | 15.14 | 1.17 | | 20.03 | | 0.59 | 4.88 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 635 | 685361.5623 | 601873.917 | BRK | 11.96 | 12.06 | 1.26 | | 20.08 | | 0.62 | 8.03 |
| 636 | 685354.9207 | 601876.4641 | BRK | 12.04 | 12.13 | 1.10 | | 20.05 | | 0.52 | 7.92 |
| 637 | 685350.4407 | 601879.237 | BRK | 15.34 | 15.19 | 1.38 | | 20.08 | | 0.55 | 4.89 |
| 638 | 685354.08 | 601677.04 | BNDY | 11.30 | 11.10 | 1.30 | 0.63 | 17.09 | | 0.64 | 5.99 |
| 639 | 685353.62 | 601747.98 | BRK | 16.38 | 16.33 | 1.30 | 0.50 | 18.71 | | 0.57 | 2.38 |
| 640 | 685357.16 | 601746.52 | BRK | 13.83 | 13.77 | 1.31 | 0.74 | 18.66 | | 0.70 | 4.90 |
| 641 | 685361.58 | 601753.32 | BRK | 13.86 | 13.90 | 1.17 | 0.89 | 18.69 | | 0.76 | 4.79 |
| 642 | 685364.98 | 601751.93 | BRK | 16.31 | 16.20 | 1.29 | 0.53 | 18.71 | | 0.69 | 2.51 |
| 643 | 685324.49 | 601717.35 | BNDY | 11.30 | 10.63 | 1.80 | 0.47 | 17.27 | | 0.60 | 6.64 |
| 644 | 685339.29 | 601697.19 | BNDY | 11.30 | 10.61 | 1.91 | 0.46 | 17.08 | | 0.61 | 6.47 |
| 645 | 685381.55 | 601830.67 | BRK | 17.46 | 17.42 | 1.20 | 0.47 | 19.67 | | 0.58 | 2.25 |
| 646 | 685385.39 | 601829.73 | BRK | 14.82 | 14.77 | 1.30 | 0.68 | 19.40 | | 0.76 | 4.64 |
| 647 | 685383.26 | 601850.36 | BRK | 17.59 | 17.51 | 1.20 | 0.49 | 19.67 | | 0.48 | 2.16 |
| 648 | 685408.65 | 601820.74 | BRK | 16.62 | 16.54 | 1.18 | 0.62 | 18.93 | | 0.59 | 2.39 |
| 649 | 685309.86 | 601737.62 | BNDY | 10.63 | 10.59 | 1.22 | 0.52 | 18.08 | | 0.60 | 7.49 |
| 650 | 685295.20 | 601757.86 | BNDY | 10.54 | 10.64 | 1.05 | 0.48 | 18.48 | | 0.61 | 7.85 |
| 651 | 685280.5071 | 601778.0937 | BNDY | 10.44 | 10.29 | 1.31 | | 18.88 | | 0.59 | 8.59 |
| 652 | 685265.6993 | 601798.2407 | BNDY | 10.74 | 10.78 | 1.29 | | 19.03 | | 0.55 | 8.25 |
| 653 | 685250.8952 | 601818.3828 | BNDY | 11.94 | 11.95 | 1.30 | | 19.05 | | 0.51 | 7.11 |
| 654 | 685236.0879 | 601838.5324 | BNDY | 15.09 | 15.11 | 1.09 | | 19.55 | | 0.76 | 4.45 |
| 655 | 685221.28 | 601858.68 | BNDY | 15.58 | 15.61 | 1.12 | 0.49 | 20.00 | | 0.62 | 4.39 |
| 656 | 685206.48 | 601878.81 | BNDY | 15.50 | 15.41 | 1.22 | 0.50 | 19.99 | | 0.57 | 4.59 |
| 657 | 685191.67 | 601898.96 | BNDY | 15.50 | 15.46 | 1.13 | 0.54 | 20.04 | | 0.65 | 4.58 |
| 658 | 685176.87 | 601919.10 | BNDY | 15.42 | 15.45 | 1.18 | 0.47 | 19.84 | | 0.46 | 4.39 |
| 659 | 685410.29 | 601854.79 | BNDY | 9.65 | 9.55 | 1.35 | 0.42 | 11.85 | | 0.53 | 2.30 |
| 660 | 685395.44 | 601875.02 | BNDY | 9.64 | 9.58 | 1.12 | 0.55 | 11.73 | | 0.48 | 2.16 |
| 661 | 685380.6628 | 601895.1371 | BNDY | 9.65 | 9.67 | 1.10 | | 11.74 | | 0.52 | 2.07 |
| 662 | 685365.9126 | 601915.2263 | BNDY | 9.73 | 9.69 | 1.12 | | 11.83 | | 0.68 | 2.14 |
| 663 | 685351.03 | 601935.49 | BNDY | 9.87 | 9.86 | 1.26 | 0.47 | 12.08 | | 0.49 | 2.22 |
| 664 | 685336.28 | 601955.58 | BNDY | 9.93 | 9.88 | 1.29 | 0.47 | 12.19 | | 0.54 | 2.30 |
| 665 | 685321.52 | 601975.69 | BNDY | 9.98 | 9.91 | 1.26 | 0.46 | 12.26 | | 0.63 | 2.35 |
| 666 | 685306.70 | 601995.87 | BNDY | 9.98 | 9.92 | 1.28 | 0.47 | 12.31 | | 0.65 | 2.40 |
| 667 | 685292.04 | 602015.84 | BNDY | 9.96 | 9.96 | 1.22 | 0.49 | 12.21 | | 0.54 | 2.25 |
| 668 | 685277.22 | 602036.03 | BNDY | 9.95 | 10.01 | 1.08 | 0.57 | 12.29 | | 0.63 | 2.28 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 669 | 685262.73 | 602055.75 | BNDY | 9.91 | 9.95 | 1.17 | 0.48 | 12.51 | | 0.55 | 2.56 |
| 670 | 685247.66 | 602076.28 | BNDY | 10.02 | 10.09 | 1.19 | 0.47 | 12.62 | | 0.63 | 2.53 |
| 671 | 685232.64 | 602096.74 | BNDY | 10.21 | 10.12 | 1.33 | 0.51 | 12.86 | | 0.58 | 2.74 |
| 672 | 685359.0086 | 601899.4038 | BRK | 14.46 | 14.43 | 1.20 | | 16.65 | | 0.51 | 2.22 |
| 673 | 685328.78 | 601922.42 | BRK | 18.12 | 18.18 | 1.07 | 0.53 | 20.32 | | 0.54 | 2.14 |
| 674 | 685299.89 | 601934.58 | BRK | 18.32 | 18.37 | 1.12 | 0.50 | 20.55 | | 0.56 | 2.18 |
| 675 | 685300.62 | 601938.23 | BRK | 15.84 | 15.80 | 1.23 | 0.91 | 20.55 | | 0.79 | 4.75 |
| 676 | 685305.79 | 601944.00 | BRK | 15.75 | 15.75 | 1.22 | 0.90 | 20.52 | | 0.79 | 4.77 |
| 677 | 685308.02 | 601946.97 | BRK | 18.23 | 18.08 | 1.25 | 0.63 | 20.49 | | 0.52 | 2.40 |
| 678 | 685292.65 | 601972.35 | BRK | 18.06 | 18.06 | 1.10 | 0.58 | 20.23 | | 0.49 | 2.17 |
| 679 | 685305.3308 | 601869.9088 | BRK | 15.99 | 16.07 | 1.18 | | 20.59 | | 0.51 | 4.52 |
| 680 | 685303.05 | 601872.98 | BRK | 18.54 | 18.11 | 1.67 | 0.46 | 20.73 | | 0.49 | 2.62 |
| 681 | 685268.9883 | 601832.9886 | BRK | 12.10 | 12.16 | 1.10 | | 20.11 | | 0.49 | 7.95 |
| 682 | 685272.6449 | 601835.6573 | BRK | 15.11 | 14.74 | 1.54 | | 20.26 | | 0.53 | 5.52 |
| 683 | 685218.81 | 601931.92 | BRK | 18.60 | 18.17 | 1.55 | 0.48 | 20.90 | | 0.70 | 2.73 |
| 684 | 685217.81 | 601935.62 | BRK | 16.04 | 16.10 | 1.19 | 0.98 | 20.79 | | 0.71 | 4.69 |
| 685 | 685217.77 | 601956.54 | BRK | 18.21 | 18.12 | 1.16 | 0.63 | 20.43 | | 0.53 | 2.31 |
| 686 | 685214.25 | 601958.05 | BRK | 15.65 | 15.75 | 1.15 | 0.95 | 20.47 | | 0.82 | 4.73 |
| 687 | 685162.06 | 601939.25 | BNDY | 14.94 | 14.89 | 1.18 | 0.63 | 19.38 | | 0.54 | 4.48 |
| 688 | 685246.08 | 602006.05 | BRK | 17.34 | 17.40 | 1.13 | 0.51 | 19.62 | | 0.57 | 2.21 |
| 689 | 685249.42 | 602007.82 | BRK | 14.83 | 14.91 | 1.18 | 0.87 | 19.55 | | 0.79 | 4.64 |
| 690 | 685250.13 | 602009.68 | BRK | 14.79 | 14.82 | 1.19 | 0.93 | 19.48 | | 0.74 | 4.66 |
| 691 | 685253.44 | 602011.40 | BRK | 17.28 | 17.25 | 1.18 | 0.51 | 19.51 | | 0.56 | 2.25 |
| 692 | 685256.80 | 602026.88 | BRK | 16.95 | 17.03 | 1.07 | 0.54 | 19.19 | | 0.55 | 2.16 |
| 693 | 685147.26 | 601959.39 | BNDY | 14.32 | 14.41 | 1.03 | 0.54 | 18.38 | | 0.66 | 3.97 |
| 694 | 685132.45 | 601979.53 | BNDY | 13.68 | 13.77 | 1.02 | 0.59 | 18.27 | | 0.81 | 4.50 |
| 695 | 685117.65 | 601999.68 | BNDY | 13.18 | 13.25 | 1.05 | 0.59 | 17.65 | | 0.56 | 4.40 |
| 696 | 685102.93 | 602019.90 | BNDY | 10.35 | 10.37 | 1.24 | 0.77 | 17.17 | | 0.64 | 6.79 |
| 697 | 685088.04 | 602039.97 | BNDY | 6.10 | 6.14 | 1.10 | 0.90 | 17.13 | | 0.61 | 10.99 |
| 698 | 685073.2297 | 602060.1093 | BNDY | 4.74 | 4.79 | 1.16 | | 17.18 | | 0.67 | 12.39 |
| 699 | 685058.4247 | 602080.2525 | BNDY | 4.27 | 4.36 | 1.16 | | 17.74 | 1.10 | | 13.38 |
| 700 | 685043.6189 | 602100.3969 | BNDY | 4.49 | 4.45 | 1.17 | | 18.06 | | 0.53 | 13.61 |
| 701 | 685028.81 | 602120.54 | BNDY | 4.79 | 4.88 | 1.12 | 0.72 | 18.10 | | 0.55 | 13.22 |
| 702 | 685014.01 | 602140.69 | BNDY | 5.10 | 5.19 | 1.06 | 0.60 | 19.00 | | 0.56 | 13.80 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 703 | 684999.20 | 602160.83 | BNDY | 5.40 | 5.38 | 1.11 | 0.66 | 19.06 | | 0.51 | 13.68 |
| 704 | 684984.40 | 602180.97 | BNDY | 5.71 | 5.66 | 1.13 | 0.65 | 19.13 | | 0.52 | 13.47 |
| 705 | 685217.90 | 602116.82 | BNDY | 10.37 | 10.28 | 1.24 | 0.54 | 13.02 | | 0.58 | 2.74 |
| 706 | 685203.10 | 602136.97 | BNDY | 10.48 | 10.57 | 1.15 | 0.59 | 13.16 | | 0.60 | 2.60 |
| 707 | 685188.3051 | 602157.12 | BNDY | 6.02 | 6.10 | 2.95 | | 15.50 | 2.87 | | 9.40 |
| 708 | 685173.5091 | 602177.2715 | BNDY | 6.02 | 5.97 | 3.02 | | 15.58 | 2.86 | | 9.61 |
| 709 | 685143.92 | 602217.57 | BNDY | 11.24 | 11.16 | 1.16 | 0.57 | 13.60 | | 0.53 | 2.44 |
| 710 | 685158.71 | 602197.42 | BNDY | 11.06 | 11.02 | 1.19 | 0.55 | 13.49 | | 0.69 | 2.47 |
| 711 | 685129.12 | 602237.73 | BNDY | 11.43 | 11.43 | 1.13 | 0.55 | 13.87 | | 0.49 | 2.44 |
| 712 | 685114.32 | 602257.88 | BNDY | 11.62 | 11.62 | 1.08 | 0.65 | 14.13 | | 0.69 | 2.51 |
| 713 | 685099.53 | 602278.03 | BNDY | 11.79 | 11.71 | 1.25 | 0.53 | 14.35 | | 0.61 | 2.64 |
| 714 | 685084.73 | 602298.18 | BNDY | 11.98 | 11.98 | 1.15 | 0.48 | 14.60 | | 0.52 | 2.62 |
| 715 | 685069.94 | 602318.33 | BNDY | 11.95 | 11.96 | 1.18 | 0.46 | 14.94 | | 0.51 | 2.98 |
| 716 | 685055.15 | 602338.47 | BNDY | 11.91 | 11.90 | 1.12 | 0.56 | 15.16 | | 0.55 | 3.26 |
| 717 | 685040.35 | 602358.63 | BNDY | 11.85 | 11.88 | 1.11 | 0.56 | 15.42 | | 0.52 | 3.54 |
| 718 | 685025.55 | 602378.78 | BNDY | 11.82 | 11.88 | 1.05 | 0.59 | 15.64 | | 0.54 | 3.76 |
| 719 | 685010.76 | 602398.93 | BNDY | 11.80 | 11.88 | 1.07 | 0.52 | 15.58 | | 0.52 | 3.71 |
| 720 | 684995.96 | 602419.08 | BNDY | 11.79 | 11.72 | 1.23 | 0.53 | 15.49 | | 0.51 | 3.77 |
| 721 | 684981.17 | 602439.24 | BNDY | 11.72 | 11.71 | 1.13 | 0.53 | 15.47 | | 0.53 | 3.76 |
| 722 | 684966.37 | 602459.39 | BNDY | 11.57 | 11.61 | 1.15 | 0.50 | 15.40 | | 0.51 | 3.80 |
| 723 | 684951.57 | 602479.54 | BNDY | 11.50 | 11.53 | 1.06 | 0.56 | 15.22 | | 0.47 | 3.70 |
| 724 | 684936.78 | 602499.69 | BNDY | 11.52 | 11.60 | 1.01 | 0.59 | 14.95 | | 0.50 | 3.35 |
| 725 | 684921.98 | 602519.84 | BNDY | 11.56 | 11.53 | 1.14 | 0.56 | 14.69 | | 0.53 | 3.16 |
| 726 | 684907.19 | 602539.99 | BNDY | 11.59 | 11.57 | 1.27 | 0.54 | 14.43 | | 0.49 | 2.86 |
| 727 | 684892.39 | 602560.14 | BNDY | 11.60 | 11.67 | 1.08 | 0.54 | 14.18 | | 0.47 | 2.51 |
| 728 | 684877.59 | 602580.30 | BNDY | 11.56 | 11.60 | 1.17 | 0.48 | 14.20 | | 0.53 | 2.60 |
| 729 | 684862.80 | 602600.45 | BNDY | 11.68 | 11.71 | 1.23 | 0.51 | 14.36 | | 0.49 | 2.65 |
| 730 | 684848.00 | 602620.60 | BNDY | 11.71 | 11.79 | 1.16 | 0.45 | 14.81 | | 0.52 | 3.02 |
| 731 | 684969.59 | 602201.11 | BNDY | 6.02 | 6.01 | 1.11 | 0.55 | 20.03 | | 0.57 | 14.03 |
| 732 | 684954.79 | 602221.26 | BNDY | 6.32 | 6.37 | 1.09 | 0.59 | 20.16 | | 0.51 | 13.79 |
| 733 | 684939.98 | 602241.40 | BNDY | 6.63 | 6.62 | 1.11 | 0.92 | 20.27 | | 0.52 | 13.66 |
| 734 | 684925.18 | 602261.55 | BNDY | 6.93 | 6.84 | 1.29 | 0.86 | 20.94 | | 0.47 | 14.09 |
| 735 | 684910.37 | 602281.69 | BNDY | 7.13 | 7.19 | 1.13 | 0.84 | 20.92 | | 0.46 | 13.73 |
| 736 | 684895.57 | 602301.83 | BNDY | 7.40 | 7.44 | 1.20 | 0.82 | 20.94 | | 0.56 | 13.50 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 737 | 684880.76 | 602321.98 | BNDY | 7.76 | 7.85 | 1.08 | 0.89 | 20.93 | | 0.51 | 13.09 |
| 738 | 684865.95 | 602342.12 | BNDY | 8.16 | 8.16 | 1.16 | 0.55 | 20.95 | | 0.55 | 12.79 |
| 739 | 684851.15 | 602362.27 | BNDY | 8.46 | 8.54 | 1.05 | 0.62 | 20.93 | | 0.54 | 12.39 |
| 740 | 684827.24 | 602394.80 | BNDY | 8.95 | 8.94 | 1.26 | 0.82 | 20.67 | | 0.55 | 11.73 |
| 741 | 684821.28 | 602402.91 | BNDY | 15.66 | 15.65 | 1.13 | 0.58 | 20.43 | | 0.55 | 4.78 |
| 742 | 684806.74 | 602422.70 | BNDY | 15.05 | 15.04 | 1.14 | 0.53 | 19.80 | | 0.54 | 4.76 |
| 743 | 684792.02 | 602442.92 | BNDY | 14.42 | 14.43 | 1.17 | 0.55 | 19.16 | | 0.55 | 4.74 |
| 744 | 684833.20 | 602640.76 | BNDY | 11.75 | 11.84 | 1.18 | 0.50 | 14.82 | | 0.50 | 2.98 |
| 745 | 684818.41 | 602660.91 | BNDY | 11.73 | 11.80 | 1.18 | 0.52 | 14.89 | | 0.52 | 3.09 |
| 746 | 684803.6081 | 602681.0604 | BNDY | 9.08 | 9.10 | 1.17 | | 15.19 | | 0.61 | 6.09 |
| 747 | 684790.6 | 602698.7769 | BNDY | 7.50 | 7.59 | 0.99 | | 14.25 | | 0.54 | 6.66 |
| 761 | 684777.12 | 602462.99 | BNDY | 13.79 | 13.79 | 1.14 | 0.55 | 18.36 | | 0.58 | 4.58 |
| 762 | 684762.31 | 602483.14 | BNDY | 13.20 | 13.12 | 1.16 | 0.56 | 17.73 | | 0.51 | 4.61 |
| 763 | 684747.51 | 602503.28 | BNDY | 12.75 | 12.70 | 1.20 | 0.52 | 17.42 | | 0.52 | 4.72 |
| 764 | 684732.70 | 602523.42 | BNDY | 12.49 | 12.41 | 1.28 | 0.67 | 17.11 | | 0.53 | 4.70 |
| 765 | 684717.90 | 602543.56 | BNDY | 7.90 | 7.91 | 1.20 | 0.82 | 16.49 | | 0.53 | 8.58 |
| 766 | 684703.09 | 602563.72 | BNDY | 6.74 | 6.81 | 1.10 | 0.78 | 17.01 | | 0.53 | 10.20 |
| 767 | 684687.1063 | 602585.4579 | BNDY | 5.47 | 5.54 | 1.11 | | 17.10 | | 0.54 | 11.56 |
| 768 | 684672.8746 | 602604.8211 | BNDY | 4.91 | 4.96 | 1.19 | | 17.31 | | 0.65 | 12.35 |
| 769 | 684656.5065 | 602623.7179 | BNDY | 4.99 | 5.01 | 1.17 | | 18.32 | | 0.68 | 13.31 |
| 822 | 685209.17 | 602098.14 | BRK | 16.12 | 16.21 | 1.02 | 0.54 | 18.37 | | 0.60 | 2.16 |
| 823 | 685187.68 | 602127.24 | BRK | 16.40 | 16.47 | 1.16 | 0.47 | 19.02 | | 0.73 | 2.55 |
| 824 | 685169.69 | 602121.14 | BRK | 16.91 | 16.98 | 1.08 | 0.50 | 19.19 | | 0.63 | 2.21 |
| 825 | 685159.5985 | 602134.7709 | BRK | 5.60 | 5.69 | 1.05 | | 19.16 | | 0.59 | 13.47 |
| 826 | 685142.99 | 602100.91 | BRK | 16.77 | 16.71 | 1.18 | 0.56 | 19.07 | | 0.56 | 2.36 |
| 827 | 685132.6767 | 602114.8475 | BRK | 5.21 | 5.29 | 1.19 | | 19.05 | | 0.53 | 13.77 |
| 828 | 685117.94 | 602082.20 | BRK | 16.50 | 16.46 | 1.14 | 0.56 | 19.07 | | 0.59 | 2.61 |
| 829 | 685108.0441 | 602096.6184 | BRK | 4.85 | 4.94 | 1.06 | | 19.03 | | 0.51 | 14.09 |
| 830 | 685097.56 | 602070.88 | BRK | 13.71 | 13.78 | 1.03 | 0.69 | 18.44 | | 0.66 | 4.66 |
| 831 | 685091.6225 | 602084.4656 | BRK | 4.62 | 4.71 | 1.06 | | 18.83 | | 0.55 | 14.12 |
| 832 | 685079.0777 | 602074.2284 | BRK | 4.44 | 4.53 | 1.06 | | 18.20 | | 0.69 | 13.67 |
| 833 | 685087.2307 | 602063.2368 | BRK | 5.15 | 5.21 | 1.14 | | 17.68 | | 0.59 | 12.47 |
| 834 | 685228.90 | 602033.89 | BRK | 16.52 | 16.51 | 1.25 | 0.48 | 18.98 | | 0.74 | 2.47 |
| 835 | 685232.50 | 602033.47 | BRK | 14.10 | 14.17 | 1.18 | 1.01 | 18.97 | | 0.70 | 4.80 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 836 | 685239.46 | 602034.31 | BRK | 14.12 | 14.21 | 1.16 | 1.14 | 18.93 | | 0.77 | 4.72 |
| 837 | 685243.00 | 602035.55 | BRK | 16.62 | 16.54 | 1.16 | 0.59 | 18.94 | | 0.65 | 2.40 |
| 838 | 685241.70 | 602050.98 | BRK | 16.30 | 16.34 | 1.19 | 0.49 | 18.61 | | 0.59 | 2.26 |
| 839 | 685057.3284 | 602100.4637 | BRK | 4.41 | 4.45 | 1.21 | | 18.40 | | 0.46 | 13.95 |
| 840 | 685060.41 | 602121.19 | BRK | 14.47 | 14.50 | 1.20 | 0.51 | 19.02 | | 0.53 | 4.53 |
| 841 | 685068.9275 | 602108.102 | BRK | 4.57 | 4.65 | 1.09 | | 18.88 | | 0.54 | 14.23 |
| 842 | 685048.4367 | 602112.4097 | BRK | 4.57 | 4.61 | 1.19 | | 18.48 | | 0.53 | 13.88 |
| 843 | 685096.9218 | 602128.8191 | BRK | 4.97 | 5.04 | 1.16 | | 19.06 | | 0.58 | 14.03 |
| 844 | 685091.28 | 602143.63 | BRK | 15.20 | 15.25 | 1.18 | 0.50 | 19.15 | | 0.51 | 3.90 |
| 845 | 685121.5544 | 602147.0482 | BRK | 5.33 | 5.37 | 1.16 | | 19.33 | | 0.60 | 13.96 |
| 846 | 685109.62 | 602161.54 | BRK | 17.81 | 17.77 | 1.15 | 0.52 | 19.91 | | 0.46 | 2.14 |
| 847 | 685117.56 | 602193.69 | BRK | 17.43 | 17.36 | 1.17 | 0.57 | 19.64 | | 0.53 | 2.27 |
| 848 | 685118.92 | 602197.25 | BRK | 14.89 | 14.96 | 1.09 | 1.00 | 19.53 | | 0.69 | 4.58 |
| 849 | 685119.73 | 602203.55 | BRK | 14.81 | 14.87 | 1.06 | 0.73 | 19.58 | | 0.72 | 4.71 |
| 850 | 685121.10 | 602206.98 | BRK | 17.27 | 17.30 | 1.06 | 0.63 | 19.45 | | 0.47 | 2.16 |
| 851 | 685114.98 | 602226.59 | BRK | 17.17 | 17.11 | 1.14 | 0.60 | 19.49 | | 0.64 | 2.38 |
| 852 | 685105.19 | 602198.82 | BRK | 17.35 | 17.38 | 1.08 | 0.57 | 19.73 | | 0.69 | 2.35 |
| 853 | 685103.22 | 602203.76 | BRK | 14.79 | 14.84 | 1.21 | 0.71 | 19.78 | | 0.71 | 4.94 |
| 854 | 685088.02 | 602208.76 | BRK | 17.36 | 17.29 | 1.26 | 0.52 | 19.91 | | 0.72 | 2.62 |
| 855 | 685089.52 | 602212.18 | BRK | 14.88 | 14.95 | 1.17 | 0.68 | 19.88 | | 0.68 | 4.92 |
| 856 | 685085.84 | 602227.09 | BRK | 15.07 | 15.15 | 1.09 | 0.93 | 19.98 | | 0.75 | 4.83 |
| 857 | 685083.49 | 602230.12 | BRK | 17.63 | 17.55 | 1.17 | 0.62 | 20.00 | | 0.66 | 2.45 |
| 858 | 685094.99 | 602252.22 | BRK | 17.70 | 17.67 | 1.13 | 0.59 | 19.87 | | 0.48 | 2.20 |
| 859 | 685081.79 | 602269.14 | BRK | 18.05 | 18.07 | 1.13 | 0.52 | 20.27 | | 0.56 | 2.21 |
| 860 | 685047.09 | 602237.51 | BRK | 15.69 | 15.73 | 1.22 | 0.82 | 20.41 | | 0.70 | 4.68 |
| 861 | 685043.77 | 602234.95 | BRK | 18.21 | 18.13 | 1.22 | 0.55 | 20.43 | | 0.54 | 2.30 |
| 862 | 685039.91 | 602232.72 | BRK | 15.73 | 15.69 | 1.31 | 0.80 | 20.46 | | 0.73 | 4.77 |
| 863 | 685042.37 | 602238.43 | BRK | 15.71 | 15.79 | 1.16 | 0.88 | 20.48 | | 0.66 | 4.69 |
| 864 | 685066.11 | 602161.84 | BRK | 17.75 | 17.67 | 1.18 | 0.55 | 19.94 | | 0.54 | 2.27 |
| 865 | 685062.13 | 602161.07 | BRK | 15.28 | 15.35 | 1.13 | 0.72 | 19.97 | | 0.63 | 4.62 |
| 866 | 685052.96 | 602208.15 | BRK | 17.82 | 17.75 | 1.23 | 0.56 | 20.21 | | 0.67 | 2.47 |
| 867 | 685049.31 | 602206.51 | BRK | 15.37 | 15.37 | 1.24 | 0.75 | 20.21 | | 0.73 | 4.84 |
| 868 | 685045.11 | 602202.48 | BRK | 15.62 | 15.59 | 1.28 | 0.76 | 20.22 | | 0.72 | 4.63 |
| 869 | 685042.10 | 602200.70 | BRK | 17.89 | 17.81 | 1.17 | 0.61 | 20.22 | | 0.63 | 2.40 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 870 | 685022.96 | 602172.09 | BRK | 15.38 | 15.35 | 1.17 | 0.96 | 19.96 | | 0.59 | 4.62 |
| 871 | 685044.91 | 602142.21 | BRK | 14.83 | 14.76 | 1.27 | 0.48 | 19.40 | | 0.54 | 4.63 |
| 872 | 684994.42 | 602217.26 | BRK | 18.66 | 18.67 | 1.09 | 0.58 | 20.88 | | 0.53 | 2.20 |
| 873 | 684975.68 | 602242.79 | BRK | 19.14 | 19.08 | 1.17 | 0.58 | 21.41 | | 0.59 | 2.33 |
| 874 | 685005.71 | 602243.75 | BRK | 18.78 | 18.75 | 1.14 | 0.55 | 21.02 | | 0.59 | 2.27 |
| 875 | 685009.09 | 602245.47 | BRK | 16.25 | 16.35 | 1.06 | 0.57 | 20.97 | | 0.66 | 4.63 |
| 876 | 685025.00 | 602263.80 | BRK | 16.24 | 16.33 | 1.15 | 0.55 | 20.95 | | 0.66 | 4.62 |
| 877 | 685027.83 | 602266.24 | BRK | 18.73 | 18.65 | 1.18 | 0.59 | 20.94 | | 0.52 | 2.29 |
| 878 | 685053.73 | 602299.58 | BRK | 18.74 | 18.68 | 1.16 | 0.57 | 20.90 | | 0.49 | 2.22 |
| 879 | 685053.33 | 602303.33 | BRK | 16.27 | 16.33 | 1.18 | 0.93 | 20.86 | | 0.54 | 4.52 |
| 880 | 685060.48 | 602307.84 | BRK | 16.22 | 16.14 | 1.22 | 0.53 | 19.44 | | 0.52 | 3.30 |
| 881 | 685039.62 | 602323.93 | BRK | 18.58 | 18.51 | 1.17 | 0.55 | 21.05 | | 0.51 | 2.54 |
| 882 | 685021.34 | 602349.28 | BRK | 18.40 | 18.31 | 1.20 | 0.58 | 21.16 | | 0.49 | 2.84 |
| 883 | 685006.56 | 602373.52 | BRK | 17.51 | 17.47 | 1.15 | 0.61 | 21.78 | | 0.46 | 4.31 |
| 884 | 684985.52 | 602400.52 | BRK | 17.74 | 17.67 | 1.21 | 0.53 | 22.01 | | 0.57 | 4.34 |
| 885 | 684968.75 | 602423.06 | BRK | 17.72 | 17.72 | 1.22 | 0.47 | 22.01 | | 0.53 | 4.29 |
| 886 | 684958.59 | 602266.06 | BRK | 19.57 | 19.50 | 1.20 | 0.56 | 21.80 | | 0.54 | 2.30 |
| 887 | 684944.51 | 602285.23 | BRK | 19.93 | 19.97 | 1.15 | 0.45 | 22.12 | | 0.55 | 2.15 |
| 888 | 684924.17 | 602312.77 | BRK | 20.38 | 20.34 | 1.14 | 0.58 | 22.59 | | 0.53 | 2.25 |
| 889 | 684896.37 | 602343.10 | BRK | 18.02 | 17.95 | 1.19 | 0.59 | 22.22 | | 0.51 | 4.28 |
| 890 | 684880.77 | 602362.80 | BRK | 17.79 | 17.78 | 1.22 | 0.55 | 22.11 | | 0.52 | 4.32 |
| 891 | 684869.32 | 602354.21 | BRK | 8.25 | 8.30 | 1.13 | 0.89 | 22.08 | | 0.58 | 13.78 |
| 892 | 684884.22 | 602334.10 | BRK | 7.94 | 7.99 | 1.06 | 0.98 | 22.09 | | 0.52 | 14.10 |
| 893 | 684908.58 | 602301.22 | BRK | 7.44 | 7.48 | 1.17 | 0.86 | 22.10 | | 0.58 | 14.63 |
| 894 | 684928.96 | 602273.71 | BRK | 7.02 | 6.99 | 1.14 | 0.98 | 21.67 | | 0.63 | 14.67 |
| 895 | 684943.18 | 602254.50 | BRK | 6.73 | 6.71 | 1.22 | 0.82 | 21.32 | | 0.57 | 14.60 |
| 896 | 684960.30 | 602231.40 | BRK | 6.38 | 6.42 | 1.18 | 0.57 | 20.89 | | 0.52 | 14.46 |
| 897 | 684979.15 | 602205.95 | BRK | 5.99 | 6.03 | 1.21 | 0.65 | 20.37 | | 0.55 | 14.34 |
| 898 | 685010.86 | 602163.13 | BRK | 5.34 | 5.42 | 1.14 | 0.51 | 19.49 | | 0.57 | 14.07 |
| 899 | 685032.93 | 602133.34 | BRK | 4.89 | 4.95 | 1.17 | 0.68 | 19.05 | | 0.63 | 14.11 |
| 900 | 684953.81 | 602443.85 | BRK | 17.56 | 17.51 | 1.17 | 0.55 | 21.86 | | 0.48 | 4.35 |
| 901 | 684933.84 | 602472.48 | BRK | 17.17 | 17.21 | 1.09 | 0.52 | 21.01 | | 0.50 | 3.80 |
| 902 | 684913.09 | 602504.45 | BRK | 16.54 | 16.57 | 1.17 | 0.48 | 20.21 | | 0.49 | 3.64 |
| 909 | 684858.28 | 602571.33 | BRK | 14.73 | 14.82 | 1.13 | 0.85 | 19.30 | | 0.55 | 4.48 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 910 | 684887.04 | 602531.88 | BRK | 18.22 | 18.19 | 1.14 | 0.56 | 20.48 | | 0.59 | 2.29 |
| 911 | 684720.03 | 602604.99 | BRK | 14.67 | 14.64 | 1.11 | 0.57 | 19.08 | | 0.55 | 4.44 |
| 912 | 684710.9277 | 602615.2523 | BRK | 5.53 | 5.61 | 1.16 | | 19.11 | | 0.60 | 13.50 |
| 913 | 684795.24 | 602555.71 | BRK | 13.67 | 13.76 | 1.17 | 0.70 | 18.40 | | 0.57 | 4.65 |
| 914 | 684795.33 | 602552.00 | BRK | 16.14 | 16.20 | 1.10 | 0.54 | 18.41 | | 0.46 | 2.21 |
| 915 | 684770.38 | 602552.44 | BRK | 15.78 | 15.71 | 1.25 | 0.51 | 18.02 | | 0.56 | 2.31 |
| 916 | 684771.04 | 602556.03 | BRK | 13.34 | 13.44 | 1.16 | 0.88 | 18.06 | | 0.54 | 4.62 |
| 917 | 684841.91 | 602602.61 | BRK | 16.61 | 16.54 | 1.19 | 0.55 | 19.02 | | 0.55 | 2.47 |
| 919 | 684835.00 | 602400.55 | BRK | 8.95 | 8.99 | 1.22 | 0.88 | 20.89 | | 0.55 | 11.90 |
| 920 | 684843.87 | 602407.12 | BRK | 16.31 | 16.30 | 1.27 | 0.54 | 20.99 | | 0.56 | 4.68 |
| 921 | 684754.50 | 602627.17 | BRK | 17.19 | 17.10 | 1.18 | 0.57 | 19.37 | | 0.52 | 2.27 |
| 922 | 684744.7356 | 602640.3266 | BRK | 6.26 | 6.33 | 1.19 | | 19.37 | | 0.64 | 13.04 |
| 923 | 684774.69 | 602642.80 | BRK | 17.28 | 17.19 | 1.28 | 0.49 | 19.50 | | 0.54 | 2.31 |
| 924 | 684765.2453 | 602655.538 | BRK | 6.71 | 6.79 | 1.08 | | 19.28 | | 0.64 | 12.49 |
| 925 | 684807.26 | 602664.88 | BRK | 13.82 | 13.73 | 1.17 | 0.59 | 17.20 | | 0.58 | 3.47 |
| 927 | 684774.9564 | 602705.0711 | BRK | 7.36 | 7.44 | 1.09 | | 18.03 | | 0.51 | 10.59 |
| 929 | 684725.0996 | 602668.0939 | BRK | 6.28 | 6.34 | 1.15 | | 19.63 | | 0.66 | 13.30 |
| 933 | 684699.1256 | 602648.8297 | BRK | 5.72 | 5.76 | 1.22 | | 19.31 | | 0.57 | 13.56 |
| 934 | 684677.3237 | 602632.6599 | BRK | 5.25 | 5.34 | 1.04 | | 18.86 | | 0.54 | 13.52 |
| 936 | 684665.7626 | 602624.1345 | BRK | 5.02 | 4.97 | 1.21 | | 18.48 | | 0.61 | 13.50 |
| 979 | 685388.74 | 601749.07 | BRK | 13.50 | 13.43 | 1.33 | 0.88 | 18.64 | | 0.68 | 5.21 |
| 980 | 685384.77 | 601750.03 | BRK | 16.23 | 16.26 | 1.10 | 0.62 | 18.63 | | 0.66 | 2.38 |
| 2000 | 684774.23 | 602717.67 | BNDY | 12.40 | 12.49 | 1.04 | 0.83 | 15.78 | | 0.66 | 3.29 |
| 2001 | 684757.86 | 602736.57 | BNDY | 12.87 | 12.80 | 1.20 | 0.52 | 16.10 | | 0.68 | 3.30 |
| 2002 | 684741.50 | 602755.47 | BNDY | 13.17 | 13.10 | 1.18 | 0.53 | 16.38 | | 0.62 | 3.28 |
| 2003 | 684725.13 | 602774.36 | BNDY | 13.48 | 13.39 | 1.19 | 0.53 | 16.61 | | 0.57 | 3.21 |
| 2004 | 684708.76 | 602793.26 | BNDY | 13.77 | 13.70 | 1.16 | 0.60 | 16.89 | | 0.54 | 3.19 |
| 2005 | 684692.39 | 602812.16 | BNDY | 13.98 | 13.89 | 1.30 | 0.49 | 17.19 | | 0.67 | 3.29 |
| 2006 | 684676.02 | 602831.05 | BNDY | 13.61 | 13.67 | 1.18 | 0.79 | 17.06 | | 0.49 | 3.39 |
| 2007 | 684659.66 | 602849.95 | BNDY | 13.71 | 13.73 | 1.17 | 0.61 | 17.34 | | 0.64 | 3.60 |
| 2008 | 684643.29 | 602868.85 | BNDY | 13.80 | 13.79 | 1.15 | 0.81 | 17.47 | | 0.65 | 3.67 |
| 2009 | 684626.92 | 602887.74 | BNDY | 13.90 | 13.94 | 1.08 | 0.71 | 17.56 | | 0.58 | 3.62 |
| 2010 | 684610.55 | 602906.64 | BNDY | 13.99 | 14.08 | 1.02 | 0.60 | 17.68 | | 0.55 | 3.60 |
| 2011 | 684589.1204 | 602931.3825 | BNDY | 6.65 | 6.66 | 1.24 | | 17.76 | | 0.56 | 11.10 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2012 | 684575.9627 | 602946.5728 | BNDY | 13.30 | 13.28 | 1.28 | | 17.39 | | 0.53 | 4.11 |
| 2013 | 684545.08 | 602982.23 | BNDY | 13.75 | 13.76 | 1.26 | 0.65 | 16.62 | | 0.50 | 2.86 |
| 2014 | 684561.447 | 602963.331 | BNDY | 14.75 | 14.79 | 1.14 | | 17.09 | | 0.63 | 2.31 |
| 2015 | 684528.71 | 603001.12 | BNDY | 12.84 | 12.83 | 1.19 | 0.64 | 16.17 | | 0.51 | 3.34 |
| 2016 | 684512.34 | 603020.02 | BNDY | 11.93 | 12.01 | 1.13 | 0.72 | 15.83 | | 0.54 | 3.82 |
| 2017 | 684495.97 | 603038.92 | BNDY | 11.01 | 11.06 | 1.06 | 0.77 | 15.35 | | 0.67 | 4.29 |
| 2018 | 684479.61 | 603057.81 | BNDY | 10.10 | 10.06 | 1.15 | 0.82 | 14.80 | | 0.62 | 4.74 |
| 2019 | 684463.24 | 603076.71 | BNDY | 9.19 | 9.14 | 1.31 | 0.50 | 14.33 | | 1.61 | 5.19 |
| 2020 | 684446.87 | 603095.61 | BNDY | 8.28 | 8.34 | 1.16 | 0.66 | 13.64 | | 1.10 | 5.30 |
| 2021 | 684430.50 | 603114.50 | BNDY | 7.48 | 7.52 | 1.16 | 0.84 | 12.50 | | 0.88 | 4.98 |
| 2022 | 684414.13 | 603133.40 | BNDY | 6.81 | 6.88 | 1.19 | 0.74 | 12.07 | | 0.62 | 5.20 |
| 2023 | 684397.77 | 603152.30 | BNDY | 6.28 | 6.36 | 1.16 | 0.88 | 12.13 | | 0.67 | 5.76 |
| 2024 | 684381.40 | 603171.20 | BNDY | 6.50 | 6.46 | 1.26 | 0.84 | 12.10 | | 0.96 | 5.65 |
| 2025 | 684365.0301 | 603190.0917 | BNDY | 6.55 | 6.51 | 1.27 | | 11.97 | | 0.46 | 5.46 |
| 2026 | 684348.6621 | 603208.9884 | BNDY | 6.83 | 6.80 | 1.26 | | 11.99 | | 0.61 | 5.18 |
| 2027 | 684332.29 | 603227.89 | BNDY | 6.81 | 6.78 | 1.16 | 0.68 | 11.94 | | 1.42 | 5.16 |
| 2028 | 684315.93 | 603246.78 | BNDY | 7.74 | 7.83 | 1.11 | 0.59 | 11.86 | | 1.48 | 4.04 |
| 2029 | 684299.56 | 603265.68 | BNDY | 7.92 | 7.91 | 1.17 | 0.67 | 11.63 | | 1.43 | 3.73 |
| 2030 | 684283.19 | 603284.58 | BNDY | 8.06 | 8.14 | 1.02 | 0.63 | 11.32 | | 1.30 | 3.19 |
| 2031 | 684258.4125 | 603313.1804 | BNDY | 8.20 | 8.12 | 1.24 | | 11.68 | | 1.77 | 3.56 |
| 2032 | 684238.1787 | 603303.292 | BNDY | 7.08 | 7.09 | 1.16 | | 10.44 | | 0.75 | 3.35 |
| 2033 | 684215.7175 | 603292.3151 | BNDY | 6.83 | 6.86 | 1.21 | | 10.58 | | 0.55 | 3.72 |
| 2034 | 684193.2563 | 603281.3381 | BNDY | 6.47 | 6.48 | 1.17 | | 10.48 | | 0.63 | 4.00 |
| 2035 | 684170.795 | 603270.3612 | BNDY | 6.39 | 6.38 | 1.17 | | 10.11 | | 0.59 | 3.73 |
| 2036 | 684148.3338 | 603259.3842 | BNDY | 6.33 | 6.35 | 1.08 | | 9.61 | | 0.55 | 3.26 |
| 2037 | 684124.1262 | 603238.3439 | BNDY | 6.10 | 6.16 | 1.05 | | 8.89 | | 0.48 | 2.73 |
| 2038 | 684149.11 | 603209.50 | BNDY | 6.10 | 6.14 | 1.11 | 0.70 | 9.04 | | 0.52 | 2.90 |
| 2039 | 684165.48 | 603190.60 | BNDY | 6.10 | 6.16 | 1.12 | 0.59 | 9.08 | | 0.55 | 2.92 |
| 2040 | 684182.05 | 603171.63 | BNDY | 6.11 | 6.14 | 1.12 | 0.58 | 9.08 | | 0.54 | 2.95 |
| 2041 | 684198.59 | 603153.14 | BNDY | 6.13 | 6.06 | 1.18 | 0.65 | 9.09 | | 0.52 | 3.04 |
| 2042 | 684214.58 | 603133.91 | BNDY | 6.10 | 6.15 | 1.16 | 0.57 | 9.10 | | 0.49 | 2.95 |
| 2043 | 684230.9841 | 603114.9778 | BNDY | 4.58 | 4.59 | 1.07 | | 9.74 | | 0.60 | 5.15 |
| 2044 | 684247.3179 | 603096.1207 | BNDY | 6.24 | 6.21 | 1.14 | | 9.60 | | 0.58 | 3.39 |
| 2045 | 684263.6863 | 603077.2236 | BNDY | 5.91 | 5.92 | 1.08 | | 9.72 | | 0.67 | 3.80 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2046 | 684280.05 | 603058.33 | BNDY | 4.16 | 4.18 | 1.17 | 0.61 | 9.87 | | 0.67 | 5.69 |
| 2047 | 684296.42 | 603039.43 | BNDY | 4.26 | 4.26 | 1.09 | 0.66 | 9.98 | | 0.58 | 5.73 |
| 2048 | 684312.79 | 603020.53 | BNDY | 4.62 | 4.62 | 1.19 | 0.55 | 10.27 | | 0.59 | 5.65 |
| 2049 | 684329.16 | 603001.64 | BNDY | 5.15 | 5.11 | 1.26 | 0.53 | 10.53 | | 0.62 | 5.41 |
| 2050 | 684345.53 | 602982.74 | BNDY | 5.85 | 5.82 | 1.29 | 0.45 | 10.79 | | 0.54 | 4.97 |
| 2051 | 684361.89 | 602963.84 | BNDY | 6.71 | 6.75 | 1.04 | 0.65 | 11.24 | | 0.74 | 4.49 |
| 2052 | 684378.26 | 602944.95 | BNDY | 7.74 | 7.79 | 1.21 | 0.69 | 12.20 | | 0.63 | 4.41 |
| 2053 | 684394.63 | 602926.05 | BNDY | 8.91 | 8.97 | 1.16 | 0.50 | 13.28 | | 0.56 | 4.31 |
| 2054 | 684411.00 | 602907.15 | BNDY | 10.10 | 10.02 | 1.24 | 0.53 | 14.50 | | 0.67 | 4.48 |
| 2055 | 684427.9409 | 602887.5938 | BNDY | 8.45 | 8.54 | 0.99 | | 15.56 | | 0.66 | 7.02 |
| 2056 | 684443.7347 | 602869.3601 | BNDY | 10.37 | 10.38 | 1.10 | | 16.56 | | 0.56 | 6.18 |
| 2057 | 684459.7017 | 602850.9264 | BNDY | 5.87 | 5.95 | 1.18 | | 17.65 | | 0.53 | 11.70 |
| 2058 | 684476.47 | 602831.57 | BNDY | 9.77 | 9.75 | 1.17 | 0.68 | 18.94 | | 0.51 | 9.19 |
| 2059 | 684492.84 | 602812.67 | BNDY | 9.33 | 9.41 | 1.12 | 0.52 | 20.12 | | 0.55 | 10.71 |
| 2060 | 684509.31 | 602793.66 | BNDY | 8.89 | 8.98 | 1.11 | 0.50 | 20.99 | | 0.53 | 12.00 |
| 2061 | 684525.58 | 602774.88 | BNDY | 8.46 | 8.43 | 1.27 | 0.51 | 20.87 | | 0.49 | 12.44 |
| 2062 | 684541.94 | 602755.98 | BNDY | 8.03 | 8.12 | 1.07 | 0.71 | 20.87 | | 0.59 | 12.75 |
| 2063 | 684558.31 | 602737.08 | BNDY | 7.60 | 7.61 | 1.21 | 0.56 | 20.23 | | 0.63 | 12.62 |
| 2064 | 684574.68 | 602718.19 | BNDY | 7.16 | 7.15 | 1.12 | 0.56 | 20.08 | | 0.53 | 12.93 |
| 2065 | 684591.05 | 602699.29 | BNDY | 6.73 | 6.70 | 1.10 | 0.66 | 20.05 | | 0.56 | 13.35 |
| 2066 | 684607.42 | 602680.39 | BNDY | 6.29 | 6.33 | 1.19 | 0.82 | 19.71 | | 0.57 | 13.37 |
| 2067 | 684623.78 | 602661.50 | BNDY | 5.86 | 5.85 | 1.21 | 0.55 | 19.23 | | 0.61 | 13.38 |
| 2068 | 684640.15 | 602642.60 | BNDY | 5.43 | 5.37 | 1.14 | 0.87 | 18.68 | | 0.53 | 13.31 |
| 2069 | 684743.44 | 602706.51 | GRID | 17.78 | 17.79 | 1.16 | 0.48 | 20.00 | | 0.57 | 2.21 |
| 2070 | 684743.44 | 602731.51 | GRID | 15.37 | 15.39 | 1.16 | 0.71 | 19.42 | | 0.60 | 4.03 |
| 2071 | 684718.44 | 602756.51 | GRID | 15.80 | 15.79 | 1.14 | 1.03 | 20.68 | | 0.61 | 4.88 |
| 2072 | 684718.44 | 602706.51 | GRID | 18.02 | 18.02 | 1.18 | 0.50 | 20.38 | | 0.52 | 2.36 |
| 2073 | 684693.44 | 602706.51 | GRID | 15.37 | 15.35 | 1.18 | 1.24 | 20.69 | | 0.56 | 5.34 |
| 2074 | 684693.44 | 602731.51 | GRID | 18.43 | 18.47 | 1.13 | 0.53 | 21.03 | | 0.50 | 2.56 |
| 2075 | 684693.44 | 602756.51 | GRID | 18.84 | 18.84 | 1.10 | 0.60 | 21.19 | | 0.58 | 2.36 |
| 2076 | 684693.44 | 602781.51 | GRID | 19.25 | 19.26 | 1.08 | 0.59 | 21.45 | | 0.52 | 2.19 |
| 2077 | 684668.44 | 602806.51 | GRID | 17.44 | 17.40 | 1.22 | 0.51 | 21.63 | | 0.62 | 4.23 |
| 2078 | 684668.44 | 602781.51 | GRID | 17.08 | 17.10 | 1.14 | 0.56 | 21.38 | | 0.54 | 4.28 |
| 2079 | 684668.44 | 602756.51 | GRID | 16.38 | 16.40 | 1.16 | 0.57 | 21.08 | | 0.53 | 4.69 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2080 | 684668.44 | 602731.51 | GRID | 15.99 | 15.95 | 1.21 | 0.70 | 21.03 | | 0.55 | 5.08 |
| 2081 | 684668.44 | 602706.51 | GRID | 18.32 | 18.33 | 1.11 | 0.52 | 20.75 | | 0.54 | 2.43 |
| 2082 | 684668.44 | 602681.51 | GRID | 17.91 | 17.82 | 1.27 | 0.50 | 20.31 | | 0.49 | 2.48 |
| 2083 | 684668.44 | 602656.51 | GRID | 14.93 | 14.87 | 1.28 | 0.80 | 19.61 | | 0.56 | 4.73 |
| 2084 | 684643.44 | 602706.51 | GRID | 18.61 | 18.56 | 1.22 | 0.53 | 20.88 | | 0.57 | 2.32 |
| 2085 | 684643.44 | 602731.51 | GRID | 16.27 | 16.19 | 1.29 | 0.50 | 21.08 | | 0.59 | 4.88 |
| 2086 | 684643.44 | 602756.51 | GRID | 16.85 | 16.78 | 1.22 | 0.52 | 21.19 | | 0.56 | 4.40 |
| 2087 | 684643.44 | 602781.51 | GRID | 17.25 | 17.23 | 1.23 | 0.49 | 21.59 | | 0.57 | 4.36 |
| 2088 | 684643.44 | 602806.51 | GRID | 17.61 | 17.60 | 1.18 | 0.76 | 21.92 | | 0.55 | 4.32 |
| 2089 | 684643.44 | 602831.51 | GRID | 17.71 | 17.69 | 1.21 | 0.83 | 22.32 | | 0.55 | 4.63 |
| 2090 | 684618.44 | 602731.51 | GRID | 16.56 | 16.60 | 1.19 | 0.45 | 21.10 | | 0.58 | 4.50 |
| 2091 | 684618.44 | 602756.51 | GRID | 17.06 | 17.07 | 1.18 | 0.52 | 21.45 | | 0.55 | 4.38 |
| 2092 | 684618.44 | 602781.51 | GRID | 17.42 | 17.43 | 1.14 | 0.57 | 21.79 | | 0.55 | 4.37 |
| 2093 | 684618.44 | 602806.51 | GRID | 17.59 | 17.56 | 1.21 | 0.58 | 22.16 | | 0.54 | 4.59 |
| 2094 | 684618.44 | 602831.51 | GRID | 17.69 | 17.63 | 1.21 | 0.55 | 22.41 | | 0.55 | 4.79 |
| 2095 | 684618.44 | 602856.51 | GRID | 20.32 | 20.30 | 1.17 | 0.57 | 22.66 | | 0.64 | 2.37 |
| 2096 | 684593.44 | 602881.51 | GRID | 19.56 | 19.51 | 1.16 | 0.58 | 22.18 | | 0.75 | 2.67 |
| 2097 | 684593.44 | 602856.51 | GRID | 19.93 | 19.88 | 1.22 | 0.49 | 22.40 | | 0.73 | 2.52 |
| 2098 | 684593.44 | 602806.51 | GRID | 17.57 | 17.50 | 1.24 | 0.53 | 22.20 | | 0.57 | 4.70 |
| 2099 | 684593.44 | 602781.51 | GRID | 17.47 | 17.47 | 1.17 | 0.57 | 21.94 | | 0.58 | 4.47 |
| 2100 | 684593.44 | 602756.51 | GRID | 17.23 | 17.22 | 1.22 | 0.48 | 21.62 | | 0.62 | 4.40 |
| 2101 | 684593.44 | 602706.51 | GRID | 6.81 | 6.79 | 1.23 | 0.60 | 20.38 | | 0.58 | 13.59 |
| 2102 | 684568.44 | 602731.51 | GRID | 7.41 | 7.46 | 1.13 | 0.55 | 20.44 | | 0.68 | 12.97 |
| 2103 | 684568.44 | 602781.51 | GRID | 17.44 | 17.39 | 1.22 | 0.57 | 21.82 | | 0.53 | 4.43 |
| 2104 | 684568.44 | 602831.51 | GRID | 19.87 | 19.85 | 1.12 | 0.65 | 22.32 | | 0.70 | 2.47 |
| 2105 | 684568.44 | 602856.51 | GRID | 19.43 | 19.38 | 1.21 | 0.56 | 21.98 | | 0.77 | 2.59 |
| 2106 | 684568.44 | 602881.51 | GRID | 18.79 | 18.77 | 1.16 | 0.57 | 21.39 | | 0.75 | 2.62 |
| 2108 | 684543.4362 | 602956.5129 | GRID | 14.35 | 14.32 | 1.26 | | 19.11 | | 0.55 | 4.79 |
| 2109 | 684543.4362 | 602931.5129 | GRID | 13.88 | 13.96 | 1.03 | | 19.21 | | 0.65 | 5.25 |
| 2110 | 684543.4362 | 602906.5129 | GRID | 6.37 | 6.46 | 1.14 | | 19.75 | | 0.58 | 13.29 |
| 2111 | 684543.44 | 602856.51 | GRID | 18.74 | 18.76 | 1.12 | 0.57 | 21.17 | | 0.72 | 2.41 |
| 2112 | 684543.44 | 602831.51 | GRID | 19.47 | 19.49 | 1.14 | 0.55 | 21.74 | | 0.58 | 2.26 |
| 2113 | 684543.44 | 602806.51 | GRID | 19.60 | 19.64 | 1.10 | 0.65 | 22.07 | | 0.59 | 2.43 |
| 2114 | 684518.44 | 602831.51 | GRID | 18.61 | 18.57 | 1.28 | 0.45 | 20.90 | | 0.60 | 2.33 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2115 | 684518.44 | 602856.51 | GRID | 18.10 | 18.16 | 1.20 | 0.46 | 20.30 | | 0.49 | 2.15 |
| 2116 | 684518.4362 | 602906.5129 | GRID | 12.95 | 12.99 | 1.11 | | 19.06 | | 0.59 | 6.08 |
| 2117 | 684518.4362 | 602931.5129 | GRID | 13.70 | 13.78 | 1.16 | | 19.13 | | 0.54 | 5.35 |
| 2118 | 684518.44 | 602956.51 | GRID | 16.84 | 16.83 | 1.11 | 0.58 | 19.00 | | 0.49 | 2.18 |
| 2119 | 684518.44 | 602981.51 | GRID | 15.93 | 15.93 | 1.10 | 0.60 | 18.18 | | 0.54 | 2.24 |
| 2121 | 684493.44 | 603006.51 | GRID | 14.49 | 14.44 | 1.20 | 0.53 | 16.76 | | 0.59 | 2.32 |
| 2122 | 684493.44 | 602981.51 | GRID | 14.91 | 14.90 | 1.14 | 0.57 | 17.23 | | 0.62 | 2.33 |
| 2123 | 684493.44 | 602956.51 | GRID | 15.48 | 15.48 | 1.19 | 0.54 | 17.94 | | 0.55 | 2.47 |
| 2124 | 684493.44 | 602931.51 | GRID | 16.57 | 16.66 | 1.01 | 0.62 | 18.79 | | 0.50 | 2.13 |
| 2125 | 684493.4362 | 602906.5129 | GRID | 13.39 | 13.44 | 1.16 | | 18.71 | | 0.60 | 5.27 |
| 2126 | 684493.44 | 602831.51 | GRID | 9.60 | 9.61 | 1.19 | 0.48 | 19.85 | | 0.50 | 10.24 |
| 2127 | 684468.44 | 603031.51 | GRID | 13.11 | 13.10 | 1.17 | 0.53 | 15.41 | | 0.62 | 2.31 |
| 2128 | 684468.44 | 603006.51 | GRID | 13.49 | 13.50 | 1.10 | 0.58 | 15.81 | | 0.63 | 2.31 |
| 2129 | 684468.44 | 602981.51 | GRID | 13.91 | 13.92 | 1.21 | 0.50 | 16.27 | | 0.64 | 2.35 |
| 2130 | 684468.44 | 602956.51 | GRID | 14.41 | 14.46 | 1.09 | 0.58 | 16.76 | | 0.60 | 2.30 |
| 2131 | 684468.44 | 602931.51 | GRID | 15.04 | 15.05 | 1.12 | 0.55 | 17.57 | | 0.54 | 2.52 |
| 2132 | 684468.4362 | 602856.5129 | GRID | 5.94 | 5.95 | 1.12 | | 18.08 | | 0.61 | 12.13 |
| 2133 | 684443.4362 | 602881.5129 | GRID | 7.90 | 7.89 | 1.11 | | 16.78 | | 0.71 | 8.89 |
| 2134 | 684443.4362 | 602906.5129 | GRID | 12.14 | 12.14 | 1.14 | | 16.66 | | 0.62 | 4.52 |
| 2135 | 684443.44 | 602931.51 | GRID | 13.75 | 13.83 | 1.07 | 0.61 | 16.15 | | 0.65 | 2.33 |
| 2136 | 684443.44 | 602956.51 | GRID | 13.27 | 13.32 | 1.16 | 0.47 | 15.60 | | 0.65 | 2.28 |
| 2137 | 684443.44 | 602981.51 | GRID | 12.85 | 12.85 | 1.09 | 0.62 | 15.17 | | 0.61 | 2.32 |
| 2138 | 684443.44 | 603006.51 | GRID | 12.44 | 12.46 | 1.11 | 0.54 | 14.78 | | 0.67 | 2.32 |
| 2139 | 684443.44 | 603031.51 | GRID | 12.01 | 11.99 | 1.15 | 0.58 | 14.38 | | 0.67 | 2.39 |
| 2140 | 684443.44 | 603056.51 | GRID | 11.69 | 11.64 | 1.14 | 0.55 | 13.96 | | 0.63 | 2.32 |
| 2141 | 684443.44 | 603081.51 | GRID | 11.40 | 11.37 | 1.15 | 0.60 | 13.63 | | 0.51 | 2.26 |
| 2142 | 684418.44 | 603106.51 | GRID | 10.24 | 10.18 | 1.26 | 0.49 | 12.46 | | 0.54 | 2.28 |
| 2143 | 684418.44 | 603081.51 | GRID | 10.44 | 10.46 | 1.10 | 0.59 | 12.79 | | 0.64 | 2.33 |
| 2144 | 684418.44 | 603056.51 | GRID | 10.65 | 10.58 | 1.17 | 0.59 | 13.22 | | 0.79 | 2.64 |
| 2145 | 684418.44 | 603031.51 | GRID | 10.92 | 10.83 | 1.21 | 0.77 | 13.42 | | 0.61 | 2.59 |
| 2146 | 684418.44 | 603006.51 | GRID | 11.27 | 11.35 | 1.04 | 0.73 | 13.83 | | 0.71 | 2.48 |
| 2147 | 684418.44 | 602981.51 | GRID | 11.70 | 11.69 | 1.19 | 0.50 | 14.07 | | 0.69 | 2.38 |
| 2148 | 684418.44 | 602956.51 | GRID | 12.12 | 12.10 | 1.21 | 0.52 | 14.50 | | 0.67 | 2.40 |
| 2149 | 684418.44 | 602906.51 | GRID | 9.84 | 9.79 | 1.34 | 0.64 | 15.00 | | 0.55 | 5.21 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2150 | 684393.44 | 602931.51 | GRID | 8.63 | 8.62 | 1.19 | 0.75 | 13.32 | | 0.64 | 4.70 |
| 2151 | 684393.44 | 602956.51 | GRID | 10.95 | 10.94 | 1.19 | 0.66 | 13.29 | | 0.49 | 2.34 |
| 2152 | 684393.44 | 602981.51 | GRID | 10.53 | 10.56 | 1.21 | 0.65 | 13.01 | | 0.60 | 2.45 |
| 2153 | 684393.44 | 603006.51 | GRID | 10.15 | 10.09 | 1.19 | 0.55 | 12.68 | | 0.79 | 2.59 |
| 2154 | 684393.44 | 603031.51 | GRID | 9.91 | 9.90 | 1.17 | 0.58 | 12.31 | | 0.66 | 2.41 |
| 2155 | 684393.44 | 603056.51 | GRID | 9.70 | 9.65 | 1.20 | 0.56 | 12.02 | | 0.61 | 2.37 |
| 2156 | 684393.44 | 603106.51 | GRID | 9.38 | 9.33 | 1.25 | 0.53 | 11.70 | | 0.52 | 2.37 |
| 2157 | 684393.44 | 603131.51 | GRID | 9.32 | 9.24 | 1.18 | 0.64 | 11.91 | | 0.61 | 2.67 |
| 2159 | 684368.4362 | 603181.5129 | GRID | 6.44 | 6.36 | 1.29 | | 11.99 | | 0.55 | 5.63 |
| 2160 | 684368.44 | 603156.51 | GRID | 8.56 | 8.52 | 1.29 | 0.53 | 11.62 | | 0.62 | 3.10 |
| 2161 | 684368.44 | 603131.51 | GRID | 8.65 | 8.58 | 1.18 | 0.62 | 11.41 | | 0.52 | 2.83 |
| 2162 | 684368.44 | 603106.51 | GRID | 8.75 | 8.68 | 1.19 | 0.64 | 11.31 | | 0.59 | 2.63 |
| 2163 | 684368.44 | 603056.51 | GRID | 8.85 | 8.80 | 1.14 | 0.61 | 11.37 | | 0.52 | 2.57 |
| 2164 | 684368.44 | 603031.51 | GRID | 8.98 | 8.95 | 1.14 | 0.56 | 11.52 | | 0.58 | 2.56 |
| 2165 | 684368.44 | 603006.51 | GRID | 9.17 | 9.13 | 1.25 | 0.52 | 11.54 | | 0.55 | 2.41 |
| 2166 | 684368.44 | 602981.51 | GRID | 9.38 | 9.32 | 1.32 | 0.48 | 11.79 | | 0.67 | 2.47 |
| 2167 | 684343.44 | 603006.51 | GRID | 8.26 | 8.19 | 1.28 | 0.48 | 10.85 | | 0.60 | 2.66 |
| 2168 | 684343.44 | 603031.51 | GRID | 8.15 | 8.11 | 1.17 | 0.58 | 10.78 | | 0.56 | 2.66 |
| 2169 | 684343.44 | 603056.51 | GRID | 8.17 | 8.16 | 1.13 | 0.58 | 10.76 | | 0.54 | 2.60 |
| 2170 | 684343.44 | 603106.51 | GRID | 8.37 | 8.37 | 1.09 | 0.66 | 10.91 | | 0.55 | 2.53 |
| 2171 | 684343.44 | 603131.51 | GRID | 8.36 | 8.39 | 1.08 | 0.62 | 10.97 | | 0.54 | 2.59 |
| 2172 | 684343.4362 | 603181.5129 | GRID | 6.47 | 6.46 | 1.14 | | 11.46 | | 1.02 | 5.01 |
| 2173 | 684343.4362 | 603206.5129 | GRID | 6.78 | 6.70 | 1.26 | | 11.85 | | 0.56 | 5.15 |
| 2174 | 684318.44 | 603231.51 | GRID | 8.81 | 8.74 | 1.22 | 0.54 | 11.68 | | 1.18 | 2.94 |
| 2175 | 684318.44 | 603206.51 | GRID | 6.84 | 6.89 | 1.08 | 0.66 | 11.28 | | 0.81 | 4.39 |
| 2176 | 684318.4362 | 603181.5129 | GRID | 6.51 | 6.46 | 1.20 | | 10.99 | | 0.59 | 4.53 |
| 2177 | 684318.4362 | 603156.5129 | GRID | 6.25 | 6.17 | 1.22 | | 10.85 | | 0.59 | 4.68 |
| 2178 | 684318.44 | 603031.51 | GRID | 4.71 | 4.79 | 1.14 | 0.66 | 10.30 | | 0.46 | 5.52 |
| 2179 | 684293.44 | 603056.51 | GRID | 4.35 | 4.27 | 1.18 | 0.76 | 10.05 | | 0.57 | 5.78 |
| 2180 | 684293.44 | 603081.51 | GRID | 7.37 | 7.32 | 1.30 | 0.71 | 10.21 | | 0.60 | 2.89 |
| 2181 | 684293.4362 | 603131.5129 | GRID | 5.94 | 5.89 | 1.23 | | 10.45 | | 0.60 | 4.56 |
| 2182 | 684293.4362 | 603156.5129 | GRID | 6.32 | 6.33 | 1.11 | | 10.59 | | 0.52 | 4.26 |
| 2183 | 684293.44 | 603181.51 | GRID | 6.52 | 6.60 | 1.18 | 0.55 | 10.75 | | 0.55 | 4.15 |
| 2184 | 684293.44 | 603206.51 | GRID | 7.97 | 7.98 | 1.14 | 0.58 | 10.92 | | 0.57 | 2.94 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2185 | 684293.44 | 603231.51 | GRID | 8.29 | 8.21 | 1.26 | 0.61 | 11.13 | | 0.58 | 2.92 |
| 2186 | 684293.44 | 603256.51 | GRID | 8.50 | 8.46 | 1.43 | 0.45 | 11.56 | | 1.03 | 3.09 |
| 2187 | 684268.44 | 603281.51 | GRID | 7.07 | 7.05 | 1.28 | 0.53 | 11.07 | | 0.56 | 4.02 |
| 2188 | 684268.44 | 603256.51 | GRID | 8.18 | 8.12 | 1.25 | 0.52 | 11.04 | | 0.62 | 2.92 |
| 2189 | 684268.44 | 603231.51 | GRID | 7.79 | 7.80 | 1.10 | 0.59 | 10.86 | | 0.54 | 3.06 |
| 2190 | 684268.44 | 603206.51 | GRID | 7.41 | 7.49 | 1.12 | 0.56 | 10.77 | | 0.58 | 3.29 |
| 2191 | 684268.44 | 603181.51 | GRID | 7.46 | 7.49 | 1.18 | 0.49 | 10.64 | | 0.56 | 3.16 |
| 2192 | 684268.44 | 603156.51 | GRID | 6.21 | 6.19 | 1.12 | 0.66 | 10.48 | | 0.55 | 4.30 |
| 2193 | 684268.4362 | 603131.5129 | GRID | 5.85 | 5.85 | 1.18 | | 10.29 | | 0.59 | 4.44 |
| 2194 | 684268.4362 | 603106.5129 | GRID | 3.07 | 3.12 | 1.06 | | 10.16 | | 0.62 | 7.04 |
| 2195 | 684268.4362 | 603081.5129 | GRID | 5.85 | 5.88 | 1.13 | | 9.88 | | 0.41 | 4.01 |
| 2196 | 684243.44 | 603131.51 | GRID | 2.98 | 3.02 | 1.10 | 0.67 | 10.13 | | 0.53 | 7.11 |
| 2197 | 684243.44 | 603181.51 | GRID | 7.56 | 7.52 | 1.27 | 0.50 | 10.45 | | 0.55 | 2.92 |
| 2198 | 684243.44 | 603206.51 | GRID | 7.25 | 7.29 | 1.08 | 0.66 | 10.59 | | 0.52 | 3.29 |
| 2199 | 684243.44 | 603231.51 | GRID | 7.47 | 7.47 | 1.20 | 0.54 | 10.70 | | 0.58 | 3.23 |
| 2200 | 684243.44 | 603256.51 | GRID | 7.83 | 7.79 | 1.22 | 0.54 | 10.69 | | 0.53 | 2.90 |
| 2201 | 684243.4362 | 603281.5129 | GRID | 7.25 | 7.20 | 1.20 | | 10.52 | | 0.58 | 3.32 |
| 2202 | 684218.4362 | 603281.5129 | GRID | 6.93 | 6.95 | 1.14 | | 10.53 | | 0.50 | 3.58 |
| 2203 | 684218.44 | 603256.51 | GRID | 7.09 | 7.10 | 1.19 | 0.57 | 10.44 | | 0.58 | 3.34 |
| 2204 | 684218.44 | 603231.51 | GRID | 7.43 | 7.43 | 1.19 | 0.52 | 10.42 | | 0.52 | 2.99 |
| 2205 | 684218.44 | 603206.51 | GRID | 7.25 | 7.21 | 1.19 | 0.56 | 10.38 | | 0.53 | 3.18 |
| 2206 | 684218.44 | 603156.51 | GRID | 7.69 | 7.70 | 1.14 | 0.54 | 10.15 | | 0.59 | 2.45 |
| 2208 | 684193.4362 | 603181.5129 | GRID | 7.48 | 7.44 | 1.27 | 0.45 | 10.16 | | 0.60 | 2.72 |
| 2209 | 684193.4362 | 603206.5129 | GRID | 7.25 | 7.28 | 1.09 | 0.59 | 10.17 | | 0.56 | 2.89 |
| 2210 | 684193.4362 | 603231.5129 | GRID | 7.34 | 7.30 | 1.19 | 0.56 | 10.19 | | 0.52 | 2.89 |
| 2211 | 684193.4362 | 603256.5129 | GRID | 6.74 | 6.76 | 1.14 | | 10.24 | | 0.60 | 3.48 |
| 2212 | 684168.4362 | 603256.5129 | GRID | 6.51 | 6.46 | 1.22 | | 10.03 | | 0.59 | 3.57 |
| 2213 | 684168.4362 | 603231.5129 | GRID | 6.45 | 6.50 | 1.15 | 0.61 | 10.04 | | 0.59 | 3.54 |
| 2214 | 684168.4362 | 603206.5129 | GRID | 7.60 | 7.60 | 1.10 | 0.67 | 10.06 | | 0.60 | 2.46 |
| 2215 | 684143.4362 | 603231.5129 | GRID | 6.43 | 6.49 | 1.19 | | 9.76 | | 0.65 | 3.27 |
| 2216 | 684768.70 | 602713.78 | BRK | 14.50 | 14.53 | 1.15 | 0.48 | 17.86 | | 0.58 | 3.34 |
| 2217 | 684755.49 | 602705.02 | BRK | 14.78 | 14.86 | 1.07 | 0.56 | 19.36 | | 0.60 | 4.50 |
| 2218 | 684750.5364 | 602706.2925 | BRK | 17.38 | 17.30 | 1.18 | 0.54 | 19.62 | | 0.52 | 2.32 |
| 2219 | 684719.5112 | 602728.0937 | BRK | 18.07 | 17.99 | 1.30 | 0.45 | 20.61 | | 0.56 | 2.62 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2220 | 684721.25 | 602731.77 | BRK | 15.36 | 15.36 | 1.23 | 0.79 | 20.54 | | 0.55 | 5.18 |
| 2222 | 684686.52 | 602801.63 | BRK | 17.16 | 17.18 | 1.08 | 0.70 | 20.72 | | 0.60 | 3.54 |
| 2223 | 684714.8245 | 602681.948 | BRK | 17.78 | 17.74 | 1.25 | 0.48 | 20.02 | | 0.55 | 2.28 |
| 2224 | 684695.23 | 602678.31 | BRK | 15.18 | 15.25 | 1.15 | 0.79 | 20.15 | | 0.63 | 4.90 |
| 2225 | 684691.1633 | 602677.7592 | BRK | 17.91 | 17.89 | 1.21 | 0.48 | 20.16 | | 0.58 | 2.27 |
| 2226 | 684679.2563 | 602656.4152 | BRK | 17.47 | 17.43 | 1.18 | 0.53 | 19.79 | | 0.65 | 2.37 |
| 2227 | 684678.94 | 602651.43 | BRK | 14.87 | 14.85 | 1.28 | 0.60 | 19.57 | | 0.56 | 4.72 |
| 2228 | 684668.1313 | 602643.1239 | BRK | 14.48 | 14.54 | 1.04 | | 19.15 | | 0.57 | 4.61 |
| 2229 | 684657.2632 | 602634.2584 | BRK | 5.13 | 5.21 | 1.15 | | 18.69 | | 0.53 | 13.48 |
| 2230 | 684652.03 | 602663.18 | BRK | 15.06 | 15.12 | 1.05 | 0.59 | 19.65 | | 0.53 | 4.53 |
| 2231 | 684641.00 | 602654.19 | BRK | 5.58 | 5.57 | 1.24 | 0.68 | 19.21 | | 0.54 | 13.64 |
| 2232 | 684642.3753 | 602682.8752 | BRK | 18.24 | 18.17 | 1.23 | 0.52 | 20.37 | | 0.45 | 2.20 |
| 2233 | 684640.23 | 602679.29 | BRK | 15.45 | 15.55 | 1.11 | 0.72 | 20.20 | | 0.63 | 4.65 |
| 2234 | 684618.68 | 602681.55 | BRK | 6.20 | 6.28 | 1.15 | 0.79 | 20.09 | | 0.70 | 13.81 |
| 2235 | 684632.7117 | 602692.9947 | BRK | 18.26 | 18.21 | 1.27 | 0.46 | 20.60 | | 0.66 | 2.39 |
| 2236 | 684620.0994 | 602708.5791 | BRK | 18.67 | 18.58 | 1.22 | 0.51 | 20.95 | | 0.63 | 2.37 |
| 2239 | 684603.43 | 602700.25 | BRK | 6.62 | 6.69 | 1.10 | 0.65 | 20.52 | | 0.63 | 13.83 |
| 2240 | 684580.79 | 602728.00 | BRK | 7.24 | 7.30 | 1.12 | 0.76 | 20.82 | | 0.76 | 13.52 |
| 2241 | 684592.09 | 602737.22 | BRK | 16.96 | 16.96 | 1.12 | 0.64 | 21.25 | | 0.53 | 4.30 |
| 2245 | 684652.97 | 602837.52 | BRK | 17.97 | 17.92 | 1.14 | 0.63 | 21.66 | | 0.60 | 3.73 |
| 2248 | 684632.9903 | 602849.2342 | BRK | 20.53 | 20.48 | 1.21 | 0.55 | 22.74 | | 0.51 | 2.27 |
| 2249 | 684573.19 | 602760.13 | BRK | 17.37 | 17.33 | 1.24 | 0.50 | 21.53 | | 0.54 | 4.21 |
| 2250 | 684562.02 | 602751.01 | BRK | 7.76 | 7.85 | 1.13 | 0.58 | 21.32 | | 0.62 | 13.46 |
| 2251 | 684549.64 | 602787.35 | BRK | 17.30 | 17.31 | 1.11 | 0.56 | 21.81 | | 0.53 | 4.50 |
| 2252 | 684539.27 | 602778.90 | BRK | 8.39 | 8.43 | 1.20 | 0.65 | 21.45 | | 0.51 | 13.02 |
| 2253 | 684568.32 | 602806.28 | BRK | 17.40 | 17.45 | 1.20 | 0.67 | 22.12 | | 0.56 | 4.67 |
| 2254 | 684565.5811 | 602809.0345 | BRK | 19.99 | 19.95 | 1.16 | 0.56 | 22.34 | | 0.68 | 2.40 |
| 2255 | 684590.8103 | 602830.4334 | BRK | 20.31 | 20.27 | 1.13 | 0.58 | 22.50 | | 0.52 | 2.23 |
| 2256 | 684593.43 | 602827.27 | BRK | 17.57 | 17.64 | 1.18 | 0.48 | 22.33 | | 0.55 | 4.69 |
| 2257 | 684611.5712 | 602875.6442 | BRK | 20.29 | 20.21 | 1.18 | 0.58 | 22.52 | | 0.54 | 2.31 |
| 2259 | 684588.8716 | 602908.3113 | BRK | 19.04 | 19.11 | 1.12 | 0.49 | 21.37 | | 0.65 | 2.26 |
| 2261 | 684576.8825 | 602901.086 | BRK | 18.28 | 18.32 | 1.19 | 0.46 | 21.15 | | 0.68 | 2.84 |
| 2262 | 684562.2754 | 602912.3889 | BRK | 6.48 | 6.55 | 1.12 | | 20.16 | | 0.60 | 13.61 |
| 2263 | 684546.9908 | 602879.913 | BRK | 18.10 | 18.01 | 1.23 | 0.58 | 20.48 | | 0.52 | 2.46 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2264 | 684536.885 | 602894.4246 | BRK | 6.32 | 6.38 | 1.19 | | 19.87 | | 0.58 | 13.49 |
| 2265 | 684518.8905 | 602881.693 | BRK | 6.20 | 6.26 | 1.20 | | 19.67 | | 0.59 | 13.41 |
| 2266 | 684529.1345 | 602867.2143 | BRK | 18.03 | 17.99 | 1.12 | 0.61 | 20.34 | | 0.56 | 2.35 |
| 2267 | 684498.05 | 602850.83 | BRK | 14.79 | 14.79 | 1.20 | 0.65 | 19.61 | | 0.55 | 4.81 |
| 2268 | 684490.4473 | 602861.5687 | BRK | 6.02 | 6.09 | 1.20 | | 19.03 | | 0.62 | 12.94 |
| 2269 | 684529.6237 | 602815.0512 | BRK | 19.24 | 19.20 | 1.12 | 0.59 | 21.47 | | 0.55 | 2.26 |
| 2270 | 684517.71 | 602805.33 | BRK | 8.99 | 9.02 | 1.13 | 0.68 | 21.32 | | 0.55 | 12.30 |
| 2271 | 684492.1914 | 603028.6259 | BRK | 14.08 | 14.16 | 1.03 | 0.59 | 16.31 | | 0.52 | 2.14 |
| 2272 | 684495.31 | 603031.35 | BRK | 11.32 | 11.38 | 1.05 | 0.93 | 16.05 | | 0.61 | 4.68 |
| 2273 | 684467.4432 | 603056.9831 | BRK | 12.70 | 12.63 | 1.22 | 0.56 | 14.91 | | 0.51 | 2.28 |
| 2274 | 684470.54 | 603059.69 | BRK | 9.95 | 9.95 | 1.10 | 0.62 | 14.78 | | 0.50 | 4.83 |
| 2275 | 684469.1556 | 602880.7528 | BRK | 13.16 | 13.25 | 1.10 | | 18.07 | | 0.59 | 4.83 |
| 2276 | 684420.7841 | 602931.9468 | BRK | 12.65 | 12.68 | 1.12 | 0.56 | 15.04 | | 0.67 | 2.36 |
| 2277 | 684418.27 | 602928.58 | BRK | 9.85 | 9.93 | 1.18 | 0.79 | 14.81 | | 0.62 | 4.88 |
| 2278 | 684497.2553 | 602878.6355 | BRK | 6.10 | 6.09 | 1.23 | | 18.81 | | 0.55 | 12.72 |
| 2279 | 684491.4795 | 602886.7988 | BRK | 12.77 | 12.69 | 1.19 | | 18.60 | | 0.56 | 5.92 |
| 2280 | 684466.7342 | 602909.2074 | BRK | 16.17 | 16.17 | 1.12 | 0.53 | 18.34 | | 0.51 | 2.16 |
| 2281 | 684469.256 | 602906.0452 | BRK | 13.48 | 13.50 | 1.17 | | 18.23 | | 0.53 | 4.73 |
| 2282 | 684569.9023 | 602930.035 | BRK | 6.56 | 6.58 | 1.18 | | 19.90 | | 0.54 | 13.32 |
| 2283 | 684564.1649 | 602938.2256 | BRK | 13.23 | 13.27 | 1.17 | | 19.44 | | 0.54 | 6.18 |
| 2284 | 684462.8239 | 602873.5669 | BRK | 6.77 | 6.86 | 1.15 | | 17.80 | | 0.62 | 10.94 |
| 2285 | 684396.208 | 603081.167 | BRK | 9.60 | 9.51 | 1.21 | 0.58 | 11.89 | | 0.58 | 2.38 |
| 2286 | 684394.9524 | 603084.8241 | BRK | 7.02 | 6.94 | 1.29 | 0.80 | 11.83 | | 0.57 | 4.89 |
| 2287 | 684370.173 | 603081.0797 | BRK | 6.46 | 6.46 | 1.22 | 0.84 | 11.35 | | 0.60 | 4.88 |
| 2288 | 684369.7302 | 603084.5148 | BRK | 8.77 | 8.80 | 1.17 | 0.57 | 11.25 | | 0.54 | 2.45 |
| 2289 | 684346.8159 | 603155.6092 | BRK | 8.42 | 8.34 | 1.28 | 0.58 | 11.18 | | 0.62 | 2.85 |
| 2290 | 684344.2815 | 603158.0189 | BRK | 6.97 | 6.96 | 1.23 | | 11.16 | | 0.71 | 4.20 |
| 2291 | 684343.8322 | 603080.6842 | BRK | 5.89 | 5.86 | 1.21 | 0.87 | 10.84 | | 0.55 | 4.98 |
| 2292 | 684344.0192 | 603084.2703 | BRK | 8.28 | 8.25 | 1.22 | 0.54 | 10.86 | | 0.58 | 2.62 |
| 2293 | 684318.4322 | 603058.4683 | BRK | 7.59 | 7.53 | 1.25 | 0.52 | 10.36 | | 0.61 | 2.83 |
| 2294 | 684314.6302 | 603057.9817 | BRK | 5.03 | 5.12 | 1.16 | 0.82 | 10.34 | | 0.61 | 5.23 |
| 2296 | 684244.6142 | 603103.2697 | BRK | 6.25 | 6.16 | 1.25 | | 9.75 | | 0.58 | 3.59 |
| 2297 | 684317.0076 | 603131.3066 | BRK | 6.55 | 6.47 | 1.30 | | 10.67 | | 0.58 | 4.21 |
| 2298 | 684318.8822 | 603129.9683 | BRK | 8.06 | 8.09 | 1.10 | 0.56 | 10.73 | | 0.57 | 2.64 |

| POINT NUMBER | NORTHING | EASTING | DESC | DESIGN SUBGRADE ELEV (FT) | SURVEYED SUBGRADE ELEV (FT) | INSTALLED GDL COVER SOIL (FT) | INSTALLED COMPACTED HORIZON C (FT) | SURVEYED FINAL GRADE ELEV (FT) | INSTALLED DGA (FT) | INSTALLED HORIZON A (FT) | TOTAL COVER (FT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 2299 | 684244.4868 | 603157.7645 | BRK | 7.52 | 7.53 | 1.10 | 0.61 | 10.36 | | 0.59 | 2.83 |
| 2300 | 684238.7773 | 603154.4036 | BRK | 3.11 | 3.14 | 1.22 | 0.59 | 10.26 | | 0.58 | 7.12 |
| 2301 | 684221.7368 | 603183.6523 | BRK | 7.75 | 7.68 | 1.20 | 0.55 | 10.33 | | 0.57 | 2.66 |
| 2302 | 684225.099 | 603177.8813 | BRK | 3.30 | 3.26 | 1.21 | 0.80 | 10.31 | | 0.59 | 7.05 |
| 2303 | 684293.4362 | 603106.5129 | GRID | 7.12 | 7.15 | 1.15 | 0.75 | 10.33 | | 0.55 | 3.18 |
| 2304 | 684318.4362 | 603081.5129 | GRID | 5.36 | 5.28 | 1.35 | 0.78 | 10.53 | | 0.63 | 5.25 |
| 2305 | 684268.0011 | 603302.1104 | BNDY | 8.15 | 8.20 | 1.14 | | 11.54 | | 1.61 | 3.34 |
| 2306 | 684383.2214 | 603153.3604 | BRK | 8.95 | 8.87 | 1.19 | 0.61 | 11.85 | | 0.54 | 2.98 |
| 2307 | 684386.53 | 603155.86 | BRK | 6.58 | 6.53 | 1.30 | 0.82 | 11.96 | | 0.56 | 5.43 |
| 2308 | 684541.16 | 602978.86 | BRK | 13.86 | 13.78 | 1.33 | 0.77 | 18.44 | | 0.49 | 4.66 |
| 2309 | 684537.9282 | 602976.1552 | BRK | 16.66 | 16.72 | 1.03 | 0.54 | 19.01 | | 0.56 | 2.29 |
| 2310 | 684519.64 | 603003.49 | BRK | 12.67 | 12.64 | 1.25 | 0.82 | 17.60 | | 0.56 | 4.95 |
| 2311 | 684516.5171 | 603000.7679 | BRK | 15.43 | 15.47 | 1.05 | 0.58 | 17.70 | | 0.59 | 2.22 |
| 2312 | 684688.247 | 602662.9919 | BRK | 17.62 | 17.65 | 1.20 | 0.46 | 19.87 | | 0.55 | 2.21 |
| 2313 | 684666.34 | 602822.94 | BRK | 17.70 | 17.62 | 1.21 | 0.58 | 21.27 | | 0.48 | 3.65 |

**ATTACHMENT M-2**
**SA-6 NORTH AND SOUTH FINAL GRADE TOPOGRAPHIC**

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW FINAL GRADING ELEVATIONS WITHIN THE SA6 NORTH CAP AREA AT THE PROJECT SITE.*
2. *FINAL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM NOV. 4, 2016 THROUGH NOV. 28, 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER: GS35737

| NO. | DATE | REVISION | BY |
|---|---|---|---|
| 0. | 1/24/17 | SA-6 NORTH FINAL GRADING | DMS RTH |
| | | DR CHK | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 NORTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
NORTH CAP FINAL GRADING PLAN

FILE NUMBER
12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/22/16 |
| PROJ | 3480-10-0027 |
| DWG | CN-125 |
| SHEET | 1 OF 2 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\NORTH CAP TOPSOIL GRADING PLAN-12-22-16.dwg PLOT DATE: Tue, 31 Jan 2017 PLOT TIME: 12:47 PM

LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW FINAL GRADING ELEVATIONS WITHIN THE SA6 NORTH CAP AREA AT THE PROJECT SITE.*
2. *FINAL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS FROM NOV. 4, 2016 THROUGH NOV. 28, 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 196 STAGECOACH ROAD - MARMORA, NJ 08223

FILE NUMBER 12001511A

| NO | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 0 | 1/24/17 | SA-6 NORTH FINAL GRADING | DMS | RTH |
| DSGN | | DR CHK | APVD | |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 NORTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS


CIVIL
NORTH CAP FINAL GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 890-2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/22/16 |
| PROJ | 3480-10-0027 |
| DWG | CN-126 |
| SHEET | 2 OF 2 |

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\NORTH CAP TOPSOIL GRADING PLAN-12-22-16.dwg PLOT DATE: Tue, 31 Jan 2017 PLOT TIME: 12:46 PM




LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

## GENERAL NOTES

1. *THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT TOPSOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.*
2. *AS-BUILT SOUTH CAP TOPSOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS ON JUNE 23, 2016 & FROM OCT. 3 THROUGH NOV. 3, 2016*
3. *HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.*

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | | DR CHK | APVD | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC. THE MATERIAL DESCRIBED THEREON.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP TOPSOIL
GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 -2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/20/16 |
| PROJ | 3480-10-0027 |
| DWG | C-128 |
| SHEET | 1 OF 3 |

FILE NUMBER 12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SA6S GDL SOUTH TOPSOIL.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 5:54 PM

## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT TOPSOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.
2. AS-BUILT SOUTH CAP TOPSOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS ON JUNE 23, 2016 & FROM OCT. 3 THROUGH NOV. 3, 2016
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

| NO. | DATE | REVISION | BY |
|---|---|---|---|
| DSGN | | DR | CHK |
| | | APVD | APVD |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP TOPSOIL
GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/20/16 |
| PROJ | 3480-10-0027 |
| DWG | C-129 |
| SHEET | 2 OF 3 |

FILE NUMBER 12001511A

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SA6S GDL SOUTH TOPSOIL.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 5:54 PM




LEGEND:

5 MAJOR CONTOUR
4 MINOR CONTOUR

0 20 40 80
SCALE IN FEET

## GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW AS-BUILT TOPSOIL GRADING ELEVATIONS WITHIN THE SA6 SOUTH CAP AREA AT THE PROJECT SITE.
2. AS-BUILT SOUTH CAP TOPSOIL GRADING LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. ON MULTIPLE FIELD VISITS ON JUNE 23, 2016 & FROM OCT. 3 THROUGH NOV. 3, 2016
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.

MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223

FILE NUMBER 12001511A

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737

| NO. | DATE | REVISION | BY |
|---|---|---|---|
| DSGN | | DR | CHK |
| | | | APVD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SOUTH CAP TOPSOIL
GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2229

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 12/20/16 |
| PROJ | 3480-10-0027 |
| DWG | C-130 |
| SHEET | 3 OF 3 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\SA6S GDL SOUTH TOPSOIL.dwg PLOT DATE: Wed, 21 Dec 2016 PLOT TIME: 5:54 PM

**ATTACHMENT N-1**
**SA-6 NORTH DEVELOPMENT AREA SURVEY CONTROL GRID AND AS-BUILT SUMMARY**

SURVEY CONTROL GRID POINT
HISTORIC FILL CAP (SEE NOTE 1)

SA–6 NORTH DEVELOPMENT AREA (SEE NOTE 2)

SA–6 NORTH OPEN SPACE CAP AREA

JCIA TRASH PIT

FORMER BUILDING FOOTPRINT (TYP)

HYDRAULIC BARRIER WALL (TYP)

HIGHWAY ROUTE 440

NEW JERSEY STATE H

NOTES:

1. REFER TO TABLE 1 – STONE COVER THICKNESS SUMMARY FOR SURVEY DOCUMENTATION OF 6 INCH HISTORIC FILL CAP INSTALLATION. TABLE PROVIDES SURVEYED SUBGRADE PRIOR TO DEPLOYMENT OF DEMARCATION LAYER AND FINAL TOP OF STONE ELEVATIONS.
2. HISTORIC FILL CAP OVER REMAINDER OF SA–6 NORTH DEVELOPMENT AREA TO BE INSTALLED BY OTHERS AS PART OF THE NON CHROMIUM REMEDIATION ACTIVITIES.

LEGEND

- HISTORIC FILL CAP – AASHTO #57 STONE
- EXISTING CONCRETE
- VEGETATIVE CAP AREA

0 40 80 160
SCALE IN FEET

Prepared/Date: TDD 2/23/17
Checked/Date: NAW 2/27/17

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 889 - 2529
NJ Certificate of Authorization Number 24GA28016900

SURVEY CONTROL GRID
HISTORIC FILL STONE CAP
Project 3480-13-0354
FIGURE 1

C:\Dsconvn\SA–6 North\2013 Excavation Surfaces\SA–6 North RAR\SA–6 North HF Stone Cap Control Grid.dwg Mon, 27 Feb 2017 – 4:21pm tony.dsonvn

Honeywell SA-6 North

Devlopment Area Historic Fill Cap - JCIA Stone Area

Jersey City, New Jersey

Prepared By: T. Donovan 2/21/17

Checked By:

**TABLE 1 - STONE COVER THICKNESS SUMMARY**

| Point | Northing | Easting | Surveyed Subgrade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|
| 1 | 685523.28 | 603405.93 | 13.40 | 13.93 | 0.53 |
| 2 | 685513.73 | 603399.02 | 13.18 | 13.79 | 0.61 |
| 3 | 685496.18 | 603389.85 | 12.79 | 13.32 | 0.53 |
| 4 | 685481.52 | 603381.02 | 12.44 | 12.96 | 0.52 |
| 5 | 685474.27 | 603376.65 | 12.22 | 12.78 | 0.56 |
| 6 | 685460.54 | 603393.63 | 11.78 | 12.33 | 0.55 |
| 7 | 685472.85 | 603404.64 | 12.25 | 12.76 | 0.52 |
| 8 | 685487.69 | 603412.55 | 12.17 | 12.74 | 0.57 |
| 9 | 685474.43 | 603429.07 | 12.00 | 12.73 | 0.72 |
| 10 | 685458.39 | 603417.84 | 11.98 | 12.52 | 0.54 |
| 11 | 685446.63 | 603409.72 | 11.32 | 11.84 | 0.52 |
| 12 | 685433.57 | 603424.77 | 10.72 | 11.35 | 0.63 |
| 13 | 685448.21 | 603436.25 | 12.08 | 12.63 | 0.55 |
| 14 | 685463.05 | 603446.44 | 11.72 | 12.66 | 0.94 |
| 15 | 685475.20 | 603454.36 | 11.89 | 12.55 | 0.67 |
| 16 | 685462.84 | 603470.96 | 11.02 | 11.69 | 0.67 |
| 17 | 685447.76 | 603461.24 | 11.71 | 12.28 | 0.58 |
| 18 | 685433.94 | 603450.78 | 11.97 | 12.53 | 0.56 |
| 19 | 685419.97 | 603439.68 | 10.56 | 11.08 | 0.53 |
| 20 | 685408.16 | 603454.03 | 10.12 | 10.66 | 0.54 |
| 21 | 685423.48 | 603464.23 | 11.91 | 12.45 | 0.54 |
| 22 | 685439.65 | 603475.75 | 11.10 | 11.64 | 0.55 |
| 23 | 685451.75 | 603485.07 | 10.30 | 10.83 | 0.53 |
| 24 | 685439.98 | 603500.51 | 10.17 | 10.74 | 0.56 |
| 25 | 685425.05 | 603487.84 | 11.95 | 12.50 | 0.55 |
| 26 | 685410.56 | 603477.32 | 12.19 | 12.72 | 0.53 |
| 27 | 685397.54 | 603467.19 | 9.67 | 10.36 | 0.68 |
| 28 | 685384.42 | 603482.80 | 9.58 | 10.13 | 0.55 |
| 29 | 685399.85 | 603492.96 | 12.37 | 12.89 | 0.52 |
| 30 | 685416.20 | 603503.33 | 12.77 | 13.29 | 0.53 |
| 31 | 685375.27 | 603494.81 | 9.31 | 9.87 | 0.56 |
| 32 | 685362.92 | 603508.54 | 8.95 | 9.81 | 0.86 |
| 33 | 685349.54 | 603524.64 | 9.29 | 10.07 | 0.78 |
| 34 | 685336.73 | 603539.80 | 9.41 | 10.19 | 0.78 |
| 35 | 685327.61 | 603550.13 | 9.40 | 9.92 | 0.52 |
| 36 | 685281.01 | 603603.74 | 9.37 | 9.97 | 0.60 |
| 37 | 685297.06 | 603616.87 | 9.99 | 10.86 | 0.86 |
| 38 | 685310.26 | 603627.35 | 12.43 | 13.39 | 0.96 |
| 39 | 685307.69 | 603654.40 | 13.06 | 13.61 | 0.56 |
| 40 | 685289.59 | 603641.42 | 10.44 | 12.02 | 1.59 |
| 41 | 685276.06 | 603630.23 | 9.72 | 10.23 | 0.52 |
| 42 | 685264.24 | 603623.31 | 9.41 | 9.93 | 0.53 |
| 43 | 685251.42 | 603639.00 | 9.41 | 9.97 | 0.56 |
| 44 | 685269.54 | 603651.81 | 10.00 | 10.67 | 0.67 |
| 45 | 685282.97 | 603662.38 | 11.65 | 12.21 | 0.56 |
| 46 | 685295.57 | 603673.40 | 12.02 | 12.60 | 0.59 |
| 47 | 685281.54 | 603688.46 | 11.24 | 11.76 | 0.53 |
| 48 | 685265.41 | 603673.94 | 10.38 | 10.92 | 0.54 |
| 49 | 685250.53 | 603659.83 | 9.63 | 10.18 | 0.55 |
| 50 | 685239.56 | 603652.46 | 9.51 | 10.07 | 0.56 |
| 51 | 685226.86 | 603666.40 | 9.69 | 10.28 | 0.59 |
| 52 | 685243.34 | 603682.70 | 9.97 | 10.56 | 0.59 |
| 53 | 685257.98 | 603695.42 | 10.53 | 11.07 | 0.54 |
| 54 | 685269.45 | 603704.51 | 10.76 | 11.30 | 0.53 |


| Point | Northing | Easting | Surveyed Subgrade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|
| 55 | 685256.97 | 603718.61 | 10.55 | 11.09 | 0.53 |
| 56 | 685241.17 | 603707.77 | 10.38 | 10.94 | 0.56 |
| 57 | 685224.67 | 603695.14 | 10.22 | 10.74 | 0.52 |
| 58 | 685209.82 | 603685.37 | 10.11 | 10.68 | 0.57 |
| 59 | 685194.95 | 603703.46 | 10.22 | 10.76 | 0.55 |
| 60 | 685214.38 | 603715.59 | 10.41 | 10.95 | 0.54 |
| 61 | 685230.39 | 603726.61 | 10.24 | 10.74 | 0.50 |
| 62 | 685245.62 | 603735.46 | 10.16 | 10.71 | 0.55 |
| 63 | 685236.23 | 603751.65 | 9.73 | 10.27 | 0.53 |
| 64 | 685217.43 | 603741.69 | 9.76 | 10.35 | 0.59 |
| 65 | 685200.22 | 603730.88 | 10.20 | 10.74 | 0.54 |
| 66 | 685183.06 | 603719.28 | 10.07 | 10.62 | 0.55 |
| 67 | 685215.11 | 603762.34 | 9.51 | 10.04 | 0.53 |
| 68 | 685198.78 | 603753.76 | 9.67 | 10.19 | 0.53 |
| 69 | 685182.41 | 603745.26 | 9.93 | 10.46 | 0.53 |
| 70 | 685170.23 | 603740.01 | 9.86 | 10.40 | 0.54 |
| 71 | 685487.22 | 603436.76 | 12.20 | 13.00 | 0.80 |
| 72 | 685503.86 | 603416.27 | 12.84 | 13.46 | 0.63 |
| 73 | 685390.17 | 603506.35 | 10.58 | 11.11 | 0.54 |
| 74 | 685403.99 | 603517.82 | 10.57 | 11.38 | 0.82 |
| 75 | 685420.55 | 603530.44 | 10.62 | 11.15 | 0.53 |
| 76 | 685435.83 | 603541.23 | 10.96 | 11.50 | 0.54 |
| 77 | 685445.86 | 603525.47 | 10.53 | 11.05 | 0.53 |
| 78 | 685456.27 | 603509.54 | 10.15 | 10.73 | 0.58 |
| 79 | 685464.15 | 603492.32 | 10.00 | 10.57 | 0.56 |
| 80 | 685476.15 | 603475.42 | 11.16 | 11.95 | 0.79 |
| 81 | 685486.05 | 603458.89 | 11.72 | 12.25 | 0.54 |
| 82 | 685501.34 | 603442.04 | 12.18 | 12.71 | 0.54 |
| 83 | 685515.44 | 603422.88 | 12.98 | 13.65 | 0.67 |
| 84 | 685537.55 | 603414.23 | 13.51 | 14.07 | 0.55 |
| 85 | 685551.27 | 603428.10 | 13.13 | 13.66 | 0.52 |
| 86 | 685548.41 | 603440.18 | 13.49 | 14.03 | 0.54 |
| 87 | 685541.41 | 603454.32 | 13.35 | 13.91 | 0.57 |
| 88 | 685532.50 | 603476.98 | 12.70 | 13.34 | 0.64 |
| 89 | 685544.94 | 603483.88 | 12.71 | 13.59 | 0.88 |
| 90 | 685538.89 | 603498.74 | 12.66 | 13.60 | 0.94 |
| 91 | 685530.51 | 603516.92 | 12.74 | 13.39 | 0.66 |
| 92 | 685520.97 | 603537.61 | 12.38 | 13.27 | 0.89 |
| 93 | 685512.89 | 603555.37 | 12.23 | 13.27 | 1.04 |
| 94 | 685495.92 | 603547.56 | 11.67 | 12.44 | 0.76 |
| 95 | 685479.71 | 603539.89 | 11.10 | 11.83 | 0.73 |
| 96 | 685464.81 | 603533.26 | 10.74 | 11.38 | 0.64 |
| 97 | 685472.16 | 603517.09 | 11.08 | 11.61 | 0.54 |
| 98 | 685481.21 | 603497.24 | 11.35 | 11.94 | 0.60 |
| 99 | 685490.04 | 603478.09 | 11.85 | 12.51 | 0.66 |
| 100 | 685500.34 | 603455.60 | 11.92 | 12.64 | 0.72 |
| 101 | 685427.26 | 603512.07 | 10.33 | 10.99 | 0.66 |
| 102 | 685379.17 | 603518.49 | 9.78 | 10.34 | 0.56 |
| 103 | 685393.80 | 603530.86 | 10.18 | 10.88 | 0.70 |
| 104 | 685409.67 | 603542.63 | 10.99 | 11.58 | 0.60 |
| 105 | 685381.45 | 603544.08 | 10.36 | 11.34 | 0.98 |
| 106 | 685365.37 | 603534.17 | 9.71 | 10.25 | 0.54 |
| 107 | 685352.32 | 603547.96 | 9.81 | 10.43 | 0.63 |
| 108 | 685389.63 | 603576.42 | 14.44 | 15.20 | 0.77 |
| 109 | 685366.42 | 603569.28 | 15.75 | 16.27 | 0.52 |
| 110 | 685340.26 | 603569.27 | 10.00 | 10.92 | 0.93 |
| 111 | 685328.33 | 603585.65 | 9.98 | 11.34 | 1.36 |
| 112 | 685316.29 | 603601.04 | 10.17 | 11.67 | 1.50 |
| 113 | 685305.80 | 603594.64 | 9.69 | 10.44 | 0.75 |

| Point | Northing | Easting | Surveyed Subgrade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|
| 114 | 685296.15 | 603585.30 | 9.59 | 10.11 | 0.52 |
| 115 | 685311.07 | 603568.24 | 9.65 | 10.19 | 0.53 |
| 116 | 685328.51 | 603567.24 | 9.61 | 10.24 | 0.63 |
| 117 | 685345.79 | 603583.34 | 13.54 | 14.27 | 0.73 |
| 118 | 685333.45 | 603600.60 | 13.43 | 14.58 | 1.14 |
| 119 | 685325.77 | 603626.43 | 14.91 | 15.43 | 0.52 |
| 120 | 685350.68 | 603598.21 | 16.53 | 17.10 | 0.58 |
| 121 | 685368.10 | 603581.44 | 16.64 | 17.55 | 0.91 |
| 122 | 685360.58 | 603611.90 | 17.22 | 18.06 | 0.84 |
| 123 | 685345.88 | 603628.53 | 15.60 | 16.15 | 0.55 |
| 124 | 685333.37 | 603644.98 | 14.14 | 14.69 | 0.56 |
| 125 | 685225.73 | 603771.87 | 9.55 | 10.09 | 0.54 |
| 126 | 685245.80 | 603780.16 | 9.48 | 10.07 | 0.59 |
| 127 | 685257.19 | 603762.86 | 9.46 | 10.12 | 0.66 |
| 128 | 685269.18 | 603745.93 | 9.68 | 10.39 | 0.70 |
| 129 | 685281.52 | 603729.15 | 10.50 | 11.13 | 0.63 |
| 130 | 685293.33 | 603712.58 | 11.00 | 11.62 | 0.62 |
| 131 | 685306.67 | 603697.52 | 11.76 | 12.43 | 0.68 |
| 132 | 685321.33 | 603680.67 | 12.75 | 13.30 | 0.55 |
| 133 | 685335.92 | 603661.97 | 13.65 | 14.42 | 0.77 |
| 134 | 685349.41 | 603644.44 | 14.73 | 15.33 | 0.60 |
| 135 | 685364.16 | 603623.73 | 16.79 | 17.31 | 0.51 |
| 136 | 685378.92 | 603614.62 | 18.62 | 19.18 | 0.56 |
| 137 | 685399.77 | 603592.18 | 17.89 | 18.41 | 0.52 |
| 138 | 685392.67 | 603606.73 | 17.60 | 18.12 | 0.52 |
| 139 | 685402.01 | 603613.49 | 16.49 | 17.03 | 0.53 |
| 140 | 685390.10 | 603622.47 | 16.99 | 17.53 | 0.54 |
| 141 | 685378.98 | 603636.66 | 16.21 | 16.85 | 0.64 |
| 142 | 685366.30 | 603654.95 | 15.01 | 15.57 | 0.56 |
| 143 | 685350.79 | 603674.67 | 14.05 | 14.65 | 0.60 |
| 144 | 685336.85 | 603693.57 | 13.41 | 14.14 | 0.73 |
| 145 | 685322.26 | 603713.63 | 12.60 | 13.14 | 0.54 |
| 146 | 685308.59 | 603731.80 | 11.28 | 11.81 | 0.52 |
| 147 | 685294.62 | 603748.51 | 9.81 | 10.57 | 0.76 |
| 148 | 685282.83 | 603766.87 | 9.34 | 9.89 | 0.55 |
| 149 | 685274.40 | 603783.71 | 9.06 | 9.62 | 0.56 |
| 150 | 685268.12 | 603790.72 | 9.42 | 9.94 | 0.53 |
| 151 | 685289.85 | 603800.78 | 9.35 | 9.89 | 0.54 |
| 152 | 685303.57 | 603776.68 | 9.19 | 9.75 | 0.57 |
| 153 | 685319.57 | 603756.13 | 10.34 | 10.91 | 0.57 |
| 154 | 685333.72 | 603737.28 | 11.95 | 12.47 | 0.53 |
| 155 | 685345.08 | 603719.79 | 13.05 | 13.59 | 0.54 |
| 156 | 685360.35 | 603698.16 | 14.23 | 14.76 | 0.53 |
| 157 | 685374.32 | 603676.80 | 15.12 | 15.65 | 0.53 |
| 158 | 685389.93 | 603655.19 | 15.62 | 16.16 | 0.53 |
| 159 | 685401.91 | 603636.79 | 15.63 | 16.18 | 0.55 |
| 160 | 685391.44 | 603671.29 | 15.47 | 15.99 | 0.52 |
| 161 | 685385.41 | 603693.60 | 15.28 | 15.80 | 0.52 |
| 162 | 685377.78 | 603707.36 | 14.43 | 14.98 | 0.55 |
| 163 | 685364.28 | 603727.60 | 12.72 | 13.26 | 0.55 |
| 164 | 685349.70 | 603747.91 | 10.91 | 11.53 | 0.61 |
| 165 | 685336.19 | 603767.24 | 9.87 | 10.42 | 0.55 |
| 166 | 685322.07 | 603786.53 | 9.07 | 9.61 | 0.54 |
| 167 | 685305.98 | 603809.37 | 9.65 | 10.17 | 0.52 |
| 168 | 685329.67 | 603820.48 | 9.47 | 9.98 | 0.51 |
| 169 | 685342.02 | 603796.31 | 9.07 | 9.63 | 0.56 |
| 170 | 685355.84 | 603775.69 | 9.72 | 10.27 | 0.55 |
| 171 | 685369.79 | 603755.44 | 10.37 | 10.99 | 0.61 |
| 172 | 685385.02 | 603732.34 | 12.49 | 13.15 | 0.66 |

| Point | Northing | Easting | Surveyed Subgrade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|
| 173 | 685397.71 | 603713.91 | 14.76 | 15.30 | 0.54 |
| 174 | 685408.35 | 603697.47 | 15.32 | 15.86 | 0.53 |
| 175 | 685397.48 | 603685.54 | 15.35 | 15.88 | 0.53 |
| 176 | 685428.19 | 603703.15 | 15.28 | 15.79 | 0.51 |
| 177 | 685417.14 | 603723.85 | 14.22 | 14.75 | 0.54 |
| 178 | 685404.09 | 603740.98 | 11.84 | 12.38 | 0.55 |
| 179 | 685391.77 | 603759.07 | 10.06 | 10.93 | 0.87 |
| 180 | 685379.63 | 603776.72 | 9.57 | 10.13 | 0.56 |
| 181 | 685367.64 | 603792.79 | 9.03 | 9.68 | 0.64 |
| 182 | 685357.17 | 603809.89 | 8.94 | 9.45 | 0.51 |
| 183 | 685345.58 | 603826.40 | 9.33 | 9.86 | 0.53 |
| 184 | 685366.65 | 603836.85 | 9.33 | 9.86 | 0.53 |
| 185 | 685379.98 | 603814.87 | 9.03 | 9.59 | 0.56 |
| 186 | 685391.37 | 603794.93 | 9.01 | 9.74 | 0.73 |
| 187 | 685407.13 | 603774.52 | 9.48 | 10.41 | 0.93 |
| 188 | 685423.08 | 603753.63 | 10.55 | 11.15 | 0.60 |
| 189 | 685434.08 | 603734.68 | 12.31 | 13.00 | 0.70 |
| 190 | 685445.77 | 603715.19 | 14.85 | 15.39 | 0.53 |
| 191 | 685463.49 | 603692.91 | 15.29 | 15.82 | 0.53 |
| 192 | 685457.66 | 603689.90 | 15.26 | 15.78 | 0.52 |
| 193 | 685445.74 | 603698.83 | 15.27 | 15.83 | 0.56 |
| 194 | 685449.80 | 603735.42 | 10.28 | 10.86 | 0.58 |
| 195 | 685469.91 | 603741.38 | 10.24 | 10.77 | 0.53 |
| 196 | 685453.16 | 603745.70 | 9.87 | 10.66 | 0.79 |
| 197 | 685439.76 | 603765.07 | 9.59 | 10.31 | 0.72 |
| 198 | 685426.86 | 603783.39 | 9.21 | 9.92 | 0.71 |
| 199 | 685413.18 | 603801.19 | 8.97 | 9.89 | 0.91 |
| 200 | 685400.85 | 603819.70 | 8.61 | 9.55 | 0.94 |
| 201 | 685392.46 | 603841.26 | 8.58 | 9.41 | 0.83 |
| 202 | 685406.36 | 603847.95 | 8.60 | 9.35 | 0.75 |
| 203 | 685418.02 | 603853.38 | 8.77 | 9.45 | 0.68 |
| 204 | 685427.53 | 603832.24 | 9.21 | 9.87 | 0.66 |
| 205 | 685438.23 | 603811.58 | 9.26 | 9.97 | 0.72 |
| 206 | 685449.14 | 603790.99 | 9.32 | 10.09 | 0.77 |
| 207 | 685460.27 | 603768.49 | 9.57 | 10.32 | 0.75 |
| 208 | 685428.91 | 603801.39 | 9.20 | 10.01 | 0.81 |
| 209 | 685417.88 | 603822.74 | 9.09 | 9.67 | 0.58 |
| 210 | 685497.04 | 603588.38 | 12.31 | 13.18 | 0.87 |
| 211 | 685477.45 | 603579.45 | 11.74 | 12.65 | 0.91 |
| 212 | 685459.42 | 603571.21 | 11.61 | 12.36 | 0.76 |
| 213 | 685440.57 | 603562.49 | 11.56 | 12.45 | 0.89 |
| 214 | 685423.05 | 603554.41 | 11.60 | 12.53 | 0.94 |
| 215 | 685404.25 | 603562.11 | 12.72 | 13.53 | 0.81 |
| 216 | 685449.84 | 603545.77 | 10.80 | 11.38 | 0.58 |
| 217 | 685471.28 | 603556.45 | 11.16 | 11.67 | 0.52 |
| 218 | 685491.10 | 603564.10 | 11.68 | 12.25 | 0.56 |
| 219 | 685506.90 | 603572.07 | 11.95 | 12.76 | 0.81 |
| 220 | 685523.96 | 603581.32 | 12.73 | 13.26 | 0.53 |
| 221 | 685534.03 | 603559.97 | 12.14 | 12.99 | 0.85 |
| 222 | 685542.20 | 603541.68 | 12.37 | 13.14 | 0.77 |
| 223 | 685548.91 | 603522.61 | 12.67 | 13.34 | 0.67 |
| 224 | 685558.06 | 603503.06 | 12.65 | 13.20 | 0.55 |
| 225 | 685566.03 | 603482.88 | 12.58 | 13.14 | 0.57 |
| 226 | 685573.22 | 603462.46 | 12.67 | 13.18 | 0.51 |
| 227 | 685581.27 | 603441.54 | 12.44 | 13.09 | 0.65 |
| 228 | 685587.54 | 603426.70 | 12.30 | 12.84 | 0.54 |
| 229 | 685572.50 | 603421.26 | 12.31 | 12.86 | 0.54 |
| 230 | 685565.98 | 603440.95 | 12.68 | 13.48 | 0.80 |
| 231 | 685557.49 | 603462.88 | 12.83 | 13.42 | 0.59 |

| Point | Northing | Easting | Surveyed Subgrade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|
| 232 | 685608.18 | 603443.66 | 13.01 | 13.59 | 0.58 |
| 233 | 685598.62 | 603464.93 | 12.90 | 13.48 | 0.58 |
| 234 | 685587.85 | 603487.26 | 12.48 | 13.15 | 0.67 |
| 235 | 685579.62 | 603508.01 | 12.24 | 12.99 | 0.75 |
| 236 | 685572.20 | 603522.38 | 12.66 | 13.41 | 0.76 |
| 237 | 685562.43 | 603542.98 | 13.26 | 13.88 | 0.62 |
| 238 | 685552.43 | 603565.49 | 12.64 | 13.18 | 0.54 |
| 239 | 685494.23 | 603640.21 | 12.90 | 13.44 | 0.54 |
| 240 | 685543.89 | 603583.80 | 12.58 | 13.15 | 0.58 |
| 241 | 685533.66 | 603603.95 | 12.49 | 13.04 | 0.56 |
| 242 | 685526.28 | 603622.07 | 12.35 | 13.03 | 0.68 |
| 243 | 685542.16 | 603646.27 | 11.45 | 12.06 | 0.60 |
| 244 | 685527.72 | 603655.76 | 11.54 | 12.08 | 0.54 |
| 245 | 685514.57 | 603677.21 | 11.59 | 12.12 | 0.53 |
| 246 | 685503.62 | 603700.80 | 11.20 | 11.97 | 0.78 |
| 247 | 685492.98 | 603723.16 | 10.86 | 11.39 | 0.54 |
| 248 | 685483.20 | 603746.84 | 10.66 | 11.18 | 0.52 |
| 249 | 685481.37 | 603719.29 | 11.13 | 11.65 | 0.52 |
| 250 | 685492.42 | 603695.95 | 11.81 | 12.34 | 0.53 |
| 251 | 685502.78 | 603671.70 | 11.97 | 12.52 | 0.54 |
| 252 | 685482.06 | 603661.74 | 13.49 | 14.01 | 0.53 |
| 253 | 685473.47 | 603663.87 | 15.37 | 15.90 | 0.54 |
| 254 | 685463.53 | 603643.83 | 15.47 | 16.01 | 0.54 |
| 255 | 685513.89 | 603647.90 | 11.79 | 12.36 | 0.57 |
| 256 | 685509.17 | 603613.94 | 12.81 | 13.68 | 0.87 |
| 257 | 685514.16 | 603595.86 | 13.08 | 13.61 | 0.54 |
| 258 | 685486.38 | 603615.52 | 13.80 | 14.41 | 0.61 |
| 259 | 685536.92 | 603627.15 | 11.68 | 12.20 | 0.52 |
| 260 | 685548.62 | 603608.36 | 11.64 | 12.21 | 0.57 |
| 261 | 685560.01 | 603585.43 | 11.85 | 12.54 | 0.68 |
| 262 | 685570.20 | 603565.58 | 11.95 | 12.48 | 0.53 |
| 263 | 685579.38 | 603546.97 | 12.06 | 12.58 | 0.52 |
| 264 | 685590.49 | 603525.08 | 11.82 | 12.37 | 0.55 |
| 265 | 685600.46 | 603540.04 | 11.90 | 12.41 | 0.52 |
| 266 | 685612.62 | 603519.30 | 11.06 | 11.68 | 0.62 |
| 267 | 685609.19 | 603497.93 | 12.03 | 12.66 | 0.63 |
| 268 | 685620.49 | 603503.16 | 11.38 | 11.94 | 0.57 |
| 269 | 685594.15 | 603558.21 | 11.20 | 11.95 | 0.75 |
| 270 | 685584.11 | 603580.26 | 11.38 | 12.00 | 0.62 |
| 271 | 685573.64 | 603602.92 | 11.34 | 12.04 | 0.70 |
| 272 | 685564.04 | 603622.10 | 11.70 | 12.25 | 0.55 |
| 273 | 685554.89 | 603641.58 | 11.65 | 12.19 | 0.55 |
| 274 | 685417.33 | 603602.10 | 16.31 | 16.85 | 0.54 |
| 275 | 685469.91 | 603605.18 | 14.84 | 15.38 | 0.54 |
| 276 | 685444.27 | 603592.66 | 15.68 | 16.21 | 0.53 |
| 277 | 685446.73 | 603627.16 | 15.45 | 15.99 | 0.54 |
| 278 | 685418.24 | 603625.60 | 15.55 | 16.09 | 0.54 |

**ATTACHMENT N-2**
**SA-6 SOUTH DEVELOPMENT AREA SURVEY CONTROL GRID AND AS-BUILT SUMMARY**




NOTES:

1. REFER TO ATTACHED TABLE FOR SURVEY DOCUMENTATION OF 6 INCH HISTORIC FILL CAP INSTALLATION. TABLE PROVIDES SURVEYED SUBGRADE PRIOR TO DEPLOYMENT OF HISTORIC FILL DEMARCATION LAYER AND FINAL TOP OF STONE ELEVATIONS.
2. REFER TO FIGURE 1 FOR INSTALLED HISTORIC FILL CAP LIMITS.

0 50 100 200
SCALE IN FEET

Prepared/Date: TDD 11/15/16
Checked/Date: DEN 11/15/16
Revised/Date: TDD 12/21/16

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD., BOX 2105<br>MORRISTOWN, NJ 07962 | NON-CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec foster wheeler<br>Environment & Infrastructure, Inc.<br>200 American Metro Blvd, Suite 113<br>Hamilton, NJ, 08619, (609) 689 - 2929<br>NJ Certificate of Authorization No.for 24GA28012600 | HISTORIC FILL CAP<br>SURVEY CONTROL GRID<br>PROJECT 3480-16-0515<br>FIGURE 2 |

C:\Drawings\JSR-6 South Excavation Limits April 2013 Excavation Shapes\JSR-6 South Non Cr Excavation\JSR – Development Area Restoration.dwg Wed, 21 Dec 2016 – 8:48pm tony.dacovero

Honeywell SA-6 South
Devlopment Area Historic Fill Cap
Jersey City, New Jersey

Prepared By: T. Donovan 10/21/16
Checked By: N. Warner 11/17/16
Revised By: T.Donovan 12/21/16

**TABLE 1 - STONE COVER THICKNESS SUMMARY**

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 1 | 684850.53 | 601890.86 | 8.48 | 8.98 | 9.03 | 0.55 |
| 2 | 684878.09 | 601886.77 | 7.98 | 8.48 | 8.51 | 0.54 |
| 3 | 684938.83 | 601910.40 | 7.94 | 8.44 | 8.49 | 0.55 |
| 4 | 684788.76 | 601960.51 | 8.44 | 8.94 | 8.98 | 0.54 |
| 5 | 684838.82 | 601960.40 | 8.42 | 8.92 | 8.95 | 0.53 |
| 6 | 684888.87 | 601960.14 | 8.34 | 8.84 | 8.88 | 0.54 |
| 7 | 684941.99 | 601977.09 | 8.47 | 8.97 | 8.99 | 0.52 |
| 8 | 684978.23 | 601947.46 | 7.96 | 8.46 | 8.59 | 0.63 |
| 9 | 684788.61 | 602010.46 | 8.05 | 8.55 | 8.56 | 0.52 |
| 10 | 684838.88 | 602010.42 | 8.02 | 8.52 | 8.54 | 0.52 |
| 11 | 684888.76 | 602010.35 | 8.28 | 8.78 | 8.84 | 0.56 |
| 12 | 684938.87 | 602010.44 | 8.42 | 8.92 | 8.98 | 0.56 |
| 13 | 684988.66 | 602010.40 | 8.79 | 9.29 | 9.36 | 0.58 |
| 14 | 685038.80 | 602010.45 | 9.11 | 9.61 | 9.64 | 0.54 |
| 15 | 684784.65 | 602084.60 | 8.12 | 8.62 | 8.69 | 0.57 |
| 16 | 684838.95 | 602060.58 | 8.45 | 8.95 | 8.96 | 0.52 |
| 17 | 684888.63 | 602060.53 | 8.50 | 9.00 | 9.04 | 0.54 |
| 18 | 684938.91 | 602060.54 | 8.34 | 8.84 | 8.89 | 0.55 |
| 19 | 684988.96 | 602060.41 | 8.46 | 8.96 | 9.06 | 0.60 |
| 20 | 685036.50 | 602069.93 | 9.48 | 9.98 | 10.06 | 0.58 |
| 21 | 684738.84 | 602104.02 | 8.01 | 8.51 | 8.72 | 0.71 |
| 22 | 684788.71 | 602110.46 | 8.27 | 8.77 | 8.81 | 0.54 |
| 23 | 684838.96 | 602110.44 | 7.56 | 8.06 | 8.31 | 0.75 |
| 24 | 684888.70 | 602110.46 | 7.95 | 8.45 | 8.47 | 0.52 |
| 25 | 684938.82 | 602110.49 | 8.21 | 8.71 | 8.82 | 0.61 |
| 26 | 684991.33 | 602121.34 | 8.49 | 8.99 | 9.09 | 0.61 |
| 27 | 684702.90 | 602119.08 | 6.79 | 7.29 | 7.34 | 0.55 |
| 28 | 684738.91 | 602160.55 | 6.64 | 7.14 | 7.16 | 0.52 |
| 29 | 684788.83 | 602160.58 | 7.88 | 8.38 | 8.43 | 0.55 |
| 30 | 684838.77 | 602160.57 | 7.48 | 7.98 | 8.03 | 0.55 |
| 31 | 684888.90 | 602160.51 | 7.75 | 8.25 | 8.29 | 0.54 |
| 32 | 684949.21 | 602173.60 | 8.49 | 8.99 | 9.11 | 0.62 |
| 33 | 684638.88 | 602197.41 | 6.52 | 7.02 | 7.05 | 0.53 |
| 34 | 684688.86 | 602210.42 | 6.54 | 7.04 | 7.10 | 0.57 |
| 35 | 684738.91 | 602210.37 | 6.75 | 7.25 | 7.30 | 0.56 |
| 36 | 684788.78 | 602210.40 | 7.03 | 7.53 | 7.62 | 0.59 |
| 37 | 684838.87 | 602210.43 | 7.28 | 7.78 | 7.85 | 0.57 |
| 38 | 684895.42 | 602235.22 | 7.46 | 7.96 | 8.18 | 0.72 |
| 39 | 684586.72 | 602271.55 | 6.93 | 7.43 | 7.48 | 0.55 |
| 40 | 684638.81 | 602260.41 | 6.47 | 6.97 | 7.00 | 0.53 |
| 41 | 684688.77 | 602260.49 | 6.73 | 7.23 | 7.27 | 0.53 |
| 42 | 684738.85 | 602260.36 | 6.96 | 7.46 | 7.49 | 0.52 |
| 43 | 684788.88 | 602260.50 | 7.25 | 7.75 | 7.79 | 0.54 |
| 44 | 684838.81 | 602260.36 | 7.42 | 7.92 | 7.98 | 0.57 |
| 45 | 684638.83 | 602310.40 | 7.11 | 7.61 | 7.63 | 0.52 |
| 46 | 684689.00 | 602310.59 | 6.95 | 7.45 | 7.48 | 0.53 |
| 47 | 684738.74 | 602310.39 | 7.14 | 7.64 | 7.72 | 0.58 |
| 48 | 684788.83 | 602310.46 | 7.37 | 7.87 | 7.88 | 0.51 |
| 49 | 684848.05 | 602300.52 | 7.44 | 7.94 | 8.22 | 0.78 |
| 50 | 684619.91 | 602360.46 | 7.98 | 8.48 | 8.51 | 0.54 |
| 51 | 684688.83 | 602360.58 | 7.63 | 8.13 | 8.15 | 0.52 |
| 52 | 684739.13 | 602360.50 | 7.50 | 8.00 | 8.06 | 0.56 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 53 | 684816.55 | 602343.81 | 7.51 | 8.01 | 8.44 | 0.93 |
| 54 | 684638.63 | 602410.42 | 8.46 | 8.96 | 8.99 | 0.53 |
| 55 | 684688.76 | 602410.52 | 8.28 | 8.78 | 8.83 | 0.55 |
| 56 | 684781.49 | 602402.20 | 8.51 | 9.01 | 9.03 | 0.53 |
| 57 | 684688.66 | 602460.47 | 8.63 | 9.13 | 9.21 | 0.58 |
| 58 | 684737.30 | 602478.82 | 9.54 | 10.04 | 10.29 | 0.75 |
| 59 | 684588.71 | 602510.27 | 8.28 | 8.78 | 8.81 | 0.53 |
| 60 | 684638.69 | 602510.50 | 8.25 | 8.75 | 8.78 | 0.53 |
| 61 | 684688.88 | 602510.53 | 8.64 | 9.14 | 9.16 | 0.52 |
| 62 | 684530.78 | 602520.13 | 9.17 | 9.67 | 9.70 | 0.53 |
| 63 | 684584.76 | 602578.22 | 7.41 | 7.91 | 7.98 | 0.57 |
| 64 | 684675.41 | 602559.84 | 8.52 | 9.02 | 9.39 | 0.87 |
| 65 | 684488.74 | 602610.39 | 8.41 | 8.91 | 8.94 | 0.53 |
| 66 | 684538.76 | 602610.26 | 7.83 | 8.33 | 8.36 | 0.53 |
| 67 | 684633.33 | 602608.11 | 8.53 | 9.03 | 9.32 | 0.79 |
| 69 | 684488.79 | 602660.54 | 8.16 | 8.66 | 8.74 | 0.57 |
| 70 | 684575.62 | 602667.46 | 8.52 | 9.02 | 9.31 | 0.79 |
| 71 | 684370.71 | 602715.69 | 9.25 | 9.75 | 9.76 | 0.51 |
| 72 | 684438.80 | 602710.54 | 8.64 | 9.14 | 9.20 | 0.56 |
| 73 | 684496.01 | 602718.89 | 8.52 | 9.02 | 9.04 | 0.52 |
| 74 | 684388.65 | 602760.45 | 9.06 | 9.56 | 9.61 | 0.55 |
| 75 | 684438.79 | 602760.46 | 8.68 | 9.18 | 9.23 | 0.55 |
| 76 | 684514.09 | 602738.44 | 9.50 | 10.00 | 10.15 | 0.65 |
| 77 | 684338.82 | 602810.43 | 9.53 | 10.03 | 10.05 | 0.53 |
| 78 | 684388.72 | 602810.44 | 8.98 | 9.48 | 9.53 | 0.54 |
| 79 | 684431.95 | 602851.50 | 9.53 | 10.03 | 10.08 | 0.56 |
| 80 | 684236.11 | 602854.74 | 9.99 | 10.49 | 10.69 | 0.71 |
| 81 | 684288.76 | 602860.37 | 9.66 | 10.16 | 10.20 | 0.55 |
| 82 | 684338.78 | 602860.35 | 9.47 | 9.97 | 10.00 | 0.53 |
| 83 | 684388.99 | 602860.30 | 9.41 | 9.91 | 9.94 | 0.53 |
| 84 | 684172.97 | 602894.67 | 10.97 | 11.47 | 11.49 | 0.52 |
| 85 | 684238.76 | 602910.44 | 10.12 | 10.62 | 10.67 | 0.55 |
| 86 | 684288.63 | 602910.46 | 9.80 | 10.30 | 10.37 | 0.57 |
| 87 | 684326.56 | 602906.44 | 9.50 | 10.00 | 10.04 | 0.54 |
| 88 | 684188.78 | 602960.47 | 10.27 | 10.77 | 10.80 | 0.53 |
| 89 | 684238.84 | 602960.43 | 9.81 | 10.31 | 10.34 | 0.53 |
| 90 | 684288.81 | 602960.31 | 9.25 | 9.75 | 9.80 | 0.54 |
| 91 | 684338.79 | 602960.55 | 9.95 | 10.45 | 10.46 | 0.52 |
| 92 | 684188.77 | 603010.41 | 9.41 | 9.91 | 9.96 | 0.55 |
| 93 | 684238.70 | 603010.36 | 9.06 | 9.56 | 9.58 | 0.51 |
| 94 | 684288.66 | 603010.40 | 9.20 | 9.70 | 9.74 | 0.54 |
| 95 | 684188.60 | 603060.40 | 8.75 | 9.25 | 9.28 | 0.53 |
| 96 | 684238.88 | 603060.50 | 8.62 | 9.12 | 9.15 | 0.52 |
| 97 | 684188.84 | 603110.46 | 8.35 | 8.85 | 8.88 | 0.53 |
| 98 | 684138.84 | 603160.56 | 8.35 | 8.85 | 8.87 | 0.52 |
| 99 | 684183.32 | 603156.53 | 8.43 | 8.93 | 8.96 | 0.53 |
| 100 | 684138.93 | 603210.41 | 8.41 | 8.91 | 8.92 | 0.51 |
| 101 | 684154.79 | 603090.07 | 8.48 | 8.98 | 9.00 | 0.53 |
| 102 | 684114.14 | 603210.60 | 8.43 | 8.93 | 8.97 | 0.54 |
| 103 | 684158.66 | 603187.23 | 8.41 | 8.91 | 8.96 | 0.55 |
| 104 | 684649.94 | 602460.53 | 8.45 | 8.95 | 8.98 | 0.53 |
| 105 | 684842.24 | 601884.19 | 8.99 | 9.49 | 9.54 | 0.55 |
| 106 | 684743.69 | 602009.93 | 8.47 | 8.97 | 8.99 | 0.53 |
| 107 | 684465.34 | 602799.24 | 9.48 | 9.98 | 10.01 | 0.53 |
| 108 | 684162.46 | 602987.20 | 10.56 | 11.06 | 11.11 | 0.55 |
| 109 | 684299.28 | 602791.88 | 9.91 | 10.41 | 10.46 | 0.56 |
| 111 | 684469.46 | 602592.76 | 9.75 | 10.25 | 10.29 | 0.54 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 112 | 684426.35 | 602551.07 | 8.95 | 9.45 | 9.67 | 0.71 |
| 113 | 684465.37 | 602513.85 | 9.54 | 10.04 | 10.19 | 0.66 |
| 114 | 684506.30 | 602540.54 | 9.09 | 9.59 | 9.62 | 0.53 |
| 115 | 684300.35 | 602633.76 | 9.37 | 9.87 | 9.96 | 0.59 |
| 116 | 684241.58 | 602696.86 | 9.64 | 10.14 | 10.20 | 0.55 |
| 117 | 684322.55 | 602660.05 | 9.71 | 10.21 | 10.22 | 0.51 |
| 118 | 684280.62 | 602729.42 | 9.98 | 10.48 | 10.68 | 0.70 |
| 119 | 684226.49 | 602751.17 | 11.31 | 11.81 | 11.91 | 0.60 |
| 120 | 684192.72 | 602724.85 | 10.86 | 11.36 | 11.41 | 0.55 |
| 121 | 684129.32 | 602792.92 | 10.28 | 10.78 | 10.85 | 0.57 |
| 122 | 684189.03 | 602766.50 | 11.19 | 11.69 | 11.70 | 0.52 |
| 123 | 684206.60 | 602825.41 | 10.84 | 11.34 | 11.37 | 0.53 |
| 124 | 684271.32 | 602794.41 | 11.65 | 12.15 | 12.16 | 0.52 |
| 125 | 684352.11 | 602692.92 | 9.51 | 10.01 | 10.15 | 0.65 |
| 126 | 684141.54 | 602849.80 | 10.73 | 11.23 | 11.25 | 0.52 |
| 127 | 684105.24 | 602861.12 | 10.75 | 11.25 | 11.26 | 0.51 |
| 128 | 684061.00 | 602864.26 | 10.95 | 11.45 | 11.45 | 0.50 |
| 129 | 684084.37 | 602909.12 | 11.19 | 11.69 | 11.73 | 0.54 |
| 130 | 684124.50 | 602949.30 | 11.31 | 11.81 | 11.83 | 0.52 |
| 131 | 684163.34 | 602941.90 | 10.84 | 11.34 | 11.36 | 0.52 |
| 132 | 684316.22 | 602732.34 | 10.46 | 10.96 | 11.00 | 0.54 |
| 133 | 684338.20 | 602754.97 | 9.70 | 10.20 | 10.27 | 0.57 |
| 134 | 685355.89 | 601230.69 | 9.11 | 9.61 | 9.61 | 0.50 |
| 135 | 685324.33 | 601302.06 | 9.00 | 9.50 | 9.69 | 0.68 |
| 136 | 685275.64 | 601348.34 | 9.19 | 9.69 | 9.72 | 0.53 |
| 137 | 685322.51 | 601333.80 | 8.76 | 9.26 | 9.29 | 0.53 |
| 138 | 685391.57 | 601355.09 | 9.53 | 10.03 | 10.12 | 0.59 |
| 139 | 685438.87 | 601360.40 | 9.62 | 10.12 | 10.13 | 0.51 |
| 140 | 685233.03 | 601403.24 | 9.48 | 9.98 | 10.27 | 0.79 |
| 141 | 685288.85 | 601410.45 | 9.33 | 9.83 | 9.88 | 0.55 |
| 142 | 685352.13 | 601375.02 | 8.13 | 8.63 | 8.75 | 0.62 |
| 143 | 685381.70 | 601415.65 | 8.02 | 8.52 | 8.59 | 0.57 |
| 144 | 685438.76 | 601401.67 | 9.16 | 9.66 | 10.08 | 0.92 |
| 145 | 685488.71 | 601410.53 | 9.19 | 9.69 | 9.76 | 0.56 |
| 146 | 685185.04 | 601463.89 | 8.49 | 8.99 | 9.22 | 0.73 |
| 147 | 685238.86 | 601460.43 | 7.80 | 8.30 | 8.34 | 0.54 |
| 148 | 685288.63 | 601460.34 | 7.93 | 8.43 | 8.49 | 0.56 |
| 149 | 685338.77 | 601460.53 | 7.95 | 8.45 | 8.52 | 0.57 |
| 150 | 685388.72 | 601460.53 | 8.14 | 8.64 | 8.82 | 0.67 |
| 151 | 685438.85 | 601460.42 | 8.51 | 9.01 | 9.10 | 0.59 |
| 152 | 685138.89 | 601510.39 | 8.45 | 8.95 | 9.07 | 0.61 |
| 153 | 685171.47 | 601516.47 | 7.95 | 8.45 | 8.52 | 0.57 |
| 154 | 685238.84 | 601510.42 | 7.91 | 8.41 | 8.50 | 0.60 |
| 155 | 685288.87 | 601510.50 | 7.99 | 8.49 | 8.58 | 0.59 |
| 156 | 685338.72 | 601510.43 | 8.06 | 8.56 | 8.60 | 0.54 |
| 157 | 685388.81 | 601510.45 | 8.25 | 8.75 | 8.77 | 0.52 |
| 158 | 685091.55 | 601573.95 | 9.01 | 9.51 | 9.54 | 0.53 |
| 159 | 685139.17 | 601560.87 | 8.01 | 8.51 | 8.52 | 0.51 |
| 160 | 685188.95 | 601560.43 | 7.98 | 8.48 | 8.49 | 0.52 |
| 161 | 685238.79 | 601560.52 | 7.95 | 8.45 | 8.57 | 0.63 |
| 162 | 685288.79 | 601560.44 | 8.02 | 8.52 | 8.59 | 0.57 |
| 163 | 685338.83 | 601560.54 | 8.14 | 8.64 | 8.69 | 0.56 |
| 164 | 685388.81 | 601560.55 | 8.26 | 8.76 | 8.80 | 0.53 |
| 165 | 685108.25 | 601601.30 | 8.02 | 8.52 | 8.57 | 0.55 |
| 166 | 685141.73 | 601615.66 | 8.10 | 8.60 | 8.56 | 0.47 |
| 167 | 685188.81 | 601610.44 | 8.01 | 8.51 | 8.60 | 0.59 |
| 168 | 685238.77 | 601610.51 | 8.02 | 8.52 | 8.56 | 0.54 |


| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 169 | 685288.72 | 601610.43 | 8.09 | 8.59 | 8.63 | 0.54 |
| 170 | 685338.74 | 601610.37 | 8.22 | 8.72 | 8.75 | 0.53 |
| 171 | 685042.54 | 601644.70 | 8.49 | 8.99 | 9.01 | 0.53 |
| 172 | 685088.79 | 601660.54 | 7.97 | 8.47 | 8.51 | 0.54 |
| 173 | 685138.80 | 601660.45 | 7.97 | 8.47 | 8.48 | 0.51 |
| 174 | 685188.79 | 601660.67 | 8.58 | 9.08 | 9.14 | 0.55 |
| 175 | 685238.85 | 601660.43 | 8.57 | 9.07 | 9.20 | 0.62 |
| 176 | 685288.82 | 601660.43 | 8.30 | 8.80 | 8.81 | 0.51 |
| 177 | 685378.00 | 601603.14 | 9.01 | 9.51 | 9.56 | 0.55 |
| 178 | 684985.35 | 601708.30 | 8.48 | 8.98 | 9.03 | 0.55 |
| 179 | 685038.72 | 601710.44 | 7.95 | 8.45 | 8.47 | 0.52 |
| 180 | 685088.70 | 601710.51 | 7.95 | 8.45 | 8.48 | 0.53 |
| 181 | 685138.70 | 601710.42 | 8.00 | 8.50 | 8.53 | 0.53 |
| 182 | 685188.77 | 601710.45 | 8.10 | 8.60 | 8.65 | 0.54 |
| 183 | 685245.18 | 601696.62 | 9.11 | 9.61 | 9.67 | 0.56 |
| 184 | 684938.65 | 601760.43 | 8.48 | 8.98 | 9.01 | 0.53 |
| 185 | 684988.83 | 601760.39 | 7.79 | 8.29 | 8.35 | 0.57 |
| 186 | 685038.79 | 601760.40 | 7.88 | 8.38 | 8.38 | 0.50 |
| 187 | 685088.76 | 601760.49 | 7.94 | 8.44 | 8.47 | 0.52 |
| 188 | 685138.85 | 601760.56 | 7.99 | 8.49 | 8.52 | 0.53 |
| 189 | 685188.77 | 601760.47 | 8.08 | 8.58 | 8.62 | 0.54 |
| 190 | 685243.48 | 601776.76 | 8.52 | 9.02 | 9.53 | 1.01 |
| 191 | 684938.83 | 601810.34 | 7.95 | 8.45 | 8.50 | 0.55 |
| 192 | 684988.71 | 601810.51 | 7.92 | 8.42 | 8.44 | 0.52 |
| 193 | 685038.93 | 601810.65 | 7.93 | 8.43 | 8.45 | 0.52 |
| 194 | 685088.74 | 601810.48 | 8.01 | 8.51 | 8.55 | 0.55 |
| 195 | 685138.84 | 601810.44 | 8.15 | 8.65 | 8.70 | 0.55 |
| 196 | 685188.76 | 601810.45 | 8.23 | 8.73 | 8.76 | 0.53 |
| 197 | 684900.77 | 601820.97 | 8.49 | 8.99 | 9.03 | 0.55 |
| 198 | 684938.61 | 601860.44 | 7.95 | 8.45 | 8.49 | 0.54 |
| 199 | 684988.79 | 601860.38 | 7.92 | 8.42 | 8.50 | 0.57 |
| 200 | 685038.71 | 601860.53 | 7.95 | 8.45 | 8.56 | 0.61 |
| 201 | 685088.78 | 601860.46 | 8.08 | 8.58 | 8.59 | 0.51 |
| 202 | 685138.76 | 601860.39 | 8.27 | 8.77 | 8.82 | 0.56 |
| 203 | 684989.00 | 601910.71 | 7.95 | 8.45 | 8.48 | 0.53 |
| 204 | 685038.68 | 601910.43 | 8.04 | 8.54 | 8.56 | 0.51 |
| 205 | 685089.10 | 601910.60 | 8.17 | 8.67 | 8.70 | 0.53 |
| 206 | 685153.99 | 601894.76 | 8.50 | 9.00 | 9.18 | 0.69 |
| 207 | 685038.79 | 601960.46 | 8.16 | 8.66 | 8.72 | 0.56 |
| 208 | 685088.76 | 601960.51 | 8.20 | 8.70 | 8.75 | 0.55 |
| 209 | 685088.34 | 601998.68 | 8.53 | 9.03 | 9.08 | 0.55 |
| 210 | 685238.84 | 601433.13 | 7.83 | 8.33 | 8.95 | 1.12 |
| 211 | 685464.45 | 601375.39 | 9.22 | 9.72 | 9.76 | 0.53 |
| 212 | 684965.05 | 601707.90 | 7.69 | 8.19 | 8.22 | 0.53 |
| 213 | 685514.96 | 601424.03 | 12.02 | 12.52 | 12.57 | 0.55 |
| 214 | 685394.14 | 601276.89 | 9.54 | 10.04 | 10.07 | 0.54 |
| 215 | 685280.99 | 601380.01 | 9.16 | 9.66 | 9.68 | 0.53 |
| 216 | 685494.34 | 601395.26 | 9.62 | 10.12 | 10.14 | 0.52 |
| 217 | 685418.92 | 601304.80 | 10.54 | 11.04 | 11.06 | 0.52 |
| 218 | 685304.76 | 601272.35 | 8.73 | 9.23 | 9.26 | 0.52 |
| 219 | 685238.01 | 601363.97 | 8.56 | 9.06 | 9.30 | 0.75 |
| 220 | 685189.66 | 601417.66 | 7.95 | 8.45 | 8.73 | 0.78 |
| 221 | 685148.00 | 601467.87 | 9.25 | 9.75 | 9.81 | 0.56 |
| 222 | 685098.56 | 601526.04 | 7.53 | 8.03 | 8.09 | 0.56 |
| 223 | 685056.74 | 601591.18 | 7.60 | 8.10 | 8.31 | 0.71 |
| 224 | 684992.62 | 601668.34 | 7.03 | 7.53 | 7.79 | 0.76 |
| 225 | 684881.94 | 601800.15 | 6.54 | 7.04 | 7.33 | 0.79 |

| Point | Northing | Easting | Surveyed Subgrade | Proposed Final Grade | Surveyd Final Grade | Installed Stone Thickness |
|---|---|---|---|---|---|---|
| 226 | 684845.03 | 601850.20 | 8.45 | 8.95 | 9.13 | 0.69 |
| 227 | 684794.36 | 601918.98 | 7.45 | 7.95 | 8.06 | 0.61 |
| 228 | 684724.35 | 602006.36 | 7.22 | 7.72 | 7.74 | 0.52 |

**ATTACHMENT N-3**
**SA-6 NORTH AND SOUTH DEVELOPMENT AREA TOPOGRAPHICS**

HACKENSACK RIVER

ROUTE 440




**LEGEND:**

- —5— MAJOR CONTOUR
- —4— MINOR CONTOUR
- —3— POSITIVE ELEVATION
- —(-2)— NEGATIVE ELEVATION

0 20 40 80
SCALE IN FEET

**GENERAL NOTES**

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW FINAL GRADE ELEVATIONS WITHIN THE SA6 NORTH EXCAVATION AREAS AT THE PROJECT SITE.
2. FINAL GRADE LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. AND ENTACT ON MULTIPLE FIELD VISITS FROM 8/21/15 THROUGH 4/28/16.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12001511A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

FINAL GRADING PLAN FOR EXCAVATION AREAS 1, 2/3, 4 AND 5

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 NORTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609)689 - 2629


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 8/23/16 |
| PROJ | 3480-10-0027 |
| DWG | CN-114A |
| SHEET | 1 OF 2 |

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 0 | 01/26/17 | SA-6 NORTH FINAL GRADING | BSB | RTH |

DSGN GE DR CHK BSB RTH


R. THOMAS HUGG
N.J. PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC. THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\V-SURV-SA6N-BACK-FILL EA1-EA5.dwg PLOT DATE: Tue, 31 Jan 2017 PLOT TIME: 1:02 PM

*HACKENSACK RIVER*




EA8




EA7

*ROUTE 440*

**LEGEND:**

- MAJOR CONTOUR
- MINOR CONTOUR
- POSITIVE ELEVATION
- NEGATIVE ELEVATION

0 15 30 60
SCALE IN FEET

**GENERAL NOTES**

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW FINAL GRADE ELEVATIONS WITHIN THE SA6 NORTH EXCAVATION AREAS AT THE PROJECT SITE.
2. FINAL GRADE LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. AND ENTACT ON MULTIPLE FIELD VISITS FROM 8/21/15 THROUGH 4/28/16.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 156 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12001511A

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL

FINAL GRADING PLAN
FOR EXCAVATION
AREAS 7 AND 8

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 NORTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2929


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 8/23/16 |
| PROJ | 3480-10-0027 |
| DWG | CN-115A |
| SHEET | 2 OF 2 |


| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 0 | 01/26/17 | SA-6 NORTH FINAL GRADING | BSB | RTH |

| DSGN | DR | CHK | APVD |
|---|---|---|---|
| GE | | BSB | RTH |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER GS36737


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


FILE NAME: C:\Civil 3D Projects\2012\12001511A\Survey\V-SURV-SA6N-BACK-FILL-EA7-8.dwg PLOT DATE: Thu, 26 Jan 2017 PLOT TIME: 2:57 PM




GENERAL NOTES

1. THE SOLE PURPOSE OF THIS PLAN IS TO SHOW TOP OF STONE ELEVATIONS WITHIN THE SA6 SOUTH EXCAVATION AREAS AT THE PROJECT SITE.
2. STONE LAYER LOCATIONS AND ELEVATIONS WERE OBTAINED BY MASER CONSULTING P.A. AND ENTACT ON MULTIPLE FIELD VISITS FROM 10/5/16, 10/6/16, AND 10/20/16.
3. HORIZONTAL DATUM NAD 1983, VERTICAL DATUM NGVD29.


MASER CONSULTING, P.A. PH: 609.390.1927 - FAX: 609.390.0040
ENGINEERS - PLANNERS - SURVEYORS - LANDSCAPE ARCHITECTS - ENVIRONMENTAL SCIENTISTS
MARMORA OFFICE - 158 STAGECOACH ROAD - MARMORA, NJ 080223


FILE NUMBER 12-1511A

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
AS BUILT DRAWINGS

CIVIL
SA6 SOUTH STONE LAYER


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"


| | |
|---|---|
| DATE | 12/19/16 |
| PROJ | 3480-10-0027 |
| DWG | C-113 |
| SHEET | 1 OF 1 |

| NO. | DATE | REVISION | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|
| DSGN | | M.H.S. | DR | B.S.B. | BSB | R.T.H. |

R. THOMAS HUGG
NJ PROFESSIONAL LAND SURVEYOR
LICENSE NUMBER 24GS36737


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**ATTACHMENT N-4**
**SA-6 NORTH AND SOUTH RESTORATION PLANS**




NOTE:

1. REFER TO CONSTRUCTION CONTROL GRID FIGURE AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE WITHIN THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL. THE VEGETATED SLOPE ALONG SA-7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. REMAINING RESTORATION AREAS IDENTIFIED ON THE CHROMIUM REMEDY 100% DESIGN DRAWINGS WILL BE ADDRESSED AS PART OF THE NON CHROMIUM REMEDIATION WORK CURRENTLY BEING COMPLETED. FINAL RESTORATION OF ALL AREAS IS SCHEDULED TO BE COMPLETE IN MARCH 2017.

STONE COVER
DGA COVER
VEGETATED COVER
RESTORATION BY OTHERS
PAVEMENT COVER
STONE TOE DRAIN
CONCRETE COVER
SD — STORM DRAIN PIPE


0 80 160 FEET
SCALE


| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 1/7/17 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
AS BUILT RESTORATION PLAN
SA-6 NORTH – SHEET 001
1/6/17

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ




NOTE: NO HISTORIC FILL SHALL BE PLACED ON SA–7

TYPICAL VEGETATED SLOPE
NTS

NOTE:

1. REFER TO FIGURE 2 FOR CONSTRUCTION CONTROL GRID AND ATTACHED TABLES FOR SURVEY DOCUMENTATION OF 6 INCH GRAVEL HISTORIC FILL CAP INSTALLATION.
2. OPEN SPACE CAP AREA WITHIN LIMITS OF THE BARRIER WALLS IS COVERED WITH CLEAN IMPORTED SOILS TO THE DEPTHS IDENTIFIED IN THE DESIGN. THE VEGETATED SLOPE ON THE DEVELOPMENT AREA IS COVERED WITH A MINIMUM OF 12 INCHES OF CLEAN IMPORTED FILL AS SHOWN ON THE TYPICAL VEGETATED SLOPE DETAIL. THE VEGETATED SLOPE ALONG SA–7 WAS CONSTRUCTED ENTIRELY FROM CLEAN IMPORTED FILL.
3. EXISTING PAVEMENT WAS FIELD INSPECTED BY LSRP AND SUBJECT TO MINOR CRACK FILLING TO SATISFY HISTORIC FILL CAP REQUIREMENTS.
4. STEEL SHEETPILE WALL WAS INSTALLED AS EXCAVATION SUPPORT ALONG THIS AREA AND THEN CUT BELOW CURRENT GRADE AND LEFT IN PLACE. THE TOP OF SHEETPILE IS GENERALLY 0.5 TO 2.0 FT BELOW CURRENT GRADES.

STONE COVER
VEGETATED COVER
PAVEMENT COVER
CONCRETE COVER
STONE COVER IN PLANTER AREAS
RIPARIAN ZONE
DGA COVER
STONE TOE DRAIN
STEEL SHEETPILE WALL
STORM DRAIN PIPE
STORM DRAIN CATCH BASIN

0 80 160 FEET
SCALE

| REV | DATE | BY | CHKD | APVD | DESCRIPTION |
|---|---|---|---|---|---|
| 0 | 12/12/16 | EJP | AE | AE | AS BUILT RESTORATION PLAN |

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME: AS BUILT RESTORATION PLAN SA–6 SOUTH – SHEET 001 12/12/16

PROJECT NAME & LOCATION: HONEYWELL SA–6 REMEDIATION JERSEY CITY, NJ


**ATTACHMENT O**
**SA-6 SOUTH DEVELOPMENT AREA MONITORING WELL LOCATIONS**

IS CONFIDENTIAL AND MAY NOT BE COPIED OR DISCLOSED, AND (2) THIS DOCUMENT MAY ONLY BE USED BY THE CLIENT IN THE COURSE AND FOR THE EXPRESS PURPOSE FOR WHICH IT HAS BEEN STATED AND AS SHOWN ON THE DOCUMENT. ANY REUSE OF THIS DOCUMENT OR ITS CONTENTS FOR ANY OTHER PURPOSE, OR AS AN EXTENSION TO THIS PROJECT, OR ANY MODIFICATION TO THE DOCUMENT WITHOUT THE EXPRESS WRITTEN PERMISSION OF AMEC FOSTER WHEELER ENVIRONMENT & INFRASTRUCTURE, INC. SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO AMEC FOSTER WHEELER ENVIRONMENT & INFRASTRUCTURE, INC. AND ITS SUBCONSULTANTS.

N

LEGEND

- EXISTING SA–6 SOUTH SHALLOW MONITORING WELL LOCATION
- PIEZOMETER
- EXISTING SITE 115 SHALLOW MONITORING WELLS (INSTALLED ON SA–6 SOUTH DURING SA–7 REMEDY)
- OPEN SPACE AOC
- DEVELOPMENT AOC
- PROPERTY LINE
- AS–BUILT CHROMIUM EXCAVATION LIMIT
- HYDRAULIC BARRIER (SA–6 SOUTH)
- HYDRAULIC BARRIER WALL (SA–7)
- AS–BUILT LOCATION OF CONTINGENT GROUNDWATER COLLECTION TRENCH AND MANHOLES




0 100 200 400
SCALE IN FEET

SOURCE:
BASEMAP TOPOGRAPHIC SURVEY COMPLETED BY MASER CONSULTING, P.A. 331 NEWMAN SPRINGS ROAD, SUITE 203, RED BANK, NEW JERSEY.
JOB NO. 10000292A, DATED DECEMBER 17, 2010.

| REV. | DATE | STATUS | PRPD BY | CHKD BY |
|---|---|---|---|---|
| | | | | |

*Amec Foster Wheeler PROJECT No.* 3480150488
*DRAWING:* 3480150488–5710–MWLO–F900

*PREPARED/DATE:* STR 07/08/16
*CHECKED/DATE:* DEN 07/08/16

amec foster wheeler

ENVIRONMENT & INFRASTRUCTURE. Inc.
200 AMERICAN METRO BLVD, SUITE 113
HAMILTON, NEW JERSEY 08619

**FIGURE 10**
MONITORING WELL LOCATIONS
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

P:\2000\HONEYWELL\JERSEY CITY\SA 6 SOUTH\3480150488\5710\5710M\CURRENT DRAWINGS\3480150488–5710–MWLO–F900.dwg Wed, 07 Dec 2016 – 2:37pm scottj.ruefli Layout: cr

**ATTACHMENT P**
**DESIGN CHANGES**
**PART 1**

| SA-6 North/South Field Change Log | | | | |
|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** |
| **2** | **DC 2013-8-14 (HB Wall)** | Modifications to the Barrier Wall alignment and Surcharge Program to address concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of 72 inch force main. Design drawings have been modified and design calculations revised in support of the required modifications to subgrade/liner grading and final grades. | Submitted to all Parties on September 12, 2013. | North |
| **7.2** | **DC 2014-11-20** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2014-11-20 includes the french drain installation, electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016. | North |
| **7.22** | **DC 2016-6-6** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2016-6-10 includes the revised electrical supply and discharge piping for SA-6 North. | Submitted to Parties as Attachment to Declaration 004. (Design Change ID changed from DC 2016-6-10 to DC 2016-6-6 to reflect actual date on Design Change form). | North |
| **7.3** | **DC 2015-2-12** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-2-24 is a follow up to DC 2014-6-10, the SA-6 South CGWES trench design. DC 2015-2-24 includes details for electrical supply and discharge piping. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | South |
| **7.4** | **DC 2015-9-03** | AmecFW documented the SA-6 Contingent Groundwater system change to a trench system. The design will be released to Entact in stages to facilitate constructability. DC 2015-9-03 is a follow up to DC 2015-2-24, the SA-6 South CGWES electrical supply. DC 2015-9-03 provides a revised electrical plan. | Submitted to Parties as Attachment to Declaration 002 response memo on July 19, 2016 | South |
| **7.4.2** | **DC 2016-12-20** | This DCB documents a number of minor field changes that have been conveyed by the EOR to Entact during the course of the work and also includes revisions to the (E series) electrical drawings for both SA-6N and SA-6S. | Included as an attachment to Declaration 005. | SA-6 North & SA-6 South |
| **10** | **DC 2014-5-19** | Defer removal of concrete/asphalt berm, demolition of subsurface concrete, and excavation to design elevations in the SA-6 South excavation area adjacent the bulkhead. | Submitted to all Parties on May 19, 2014. | South |
| **11** | **DC 2014-7-28** | Update the list of monitoring wells to be abandoned / retained. | Submitted to all Parties on August 26, 2014. | SA-6 North & SA-6 South |
| **18** | **DC 2014-12-23** | During shallow excavation along the cove on Site 163, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. The structures will be left in place and remediation will be completed with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed. The total volume of the three isolated areas left in place is estimated to be 35 cubic yards. | Submitted to all Parties on January 28, 2015. | South |
| **23** | **DC 2015-04-30** | A concrete protuberance was encountered 12-13 feet below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched to clear the concrete, then lowered to design depth. | Submitted to Contractor only as clarification or response to RFI. | North |
| **29** | **DC 2015-06-05** | Amec Foster Wheeler reviewed the piezometer locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall. | Submitted to Parties on August 27, 2015. | South |
| **30** | **DC 2015-11-12** | Amec Foster Wheeler has provided Final Cap Grades (in CAD) to Entact. Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage. | Included as an attachment to Declaration 005. | South |
| **30.1** | **DC 2016-04-15** | Amec Foster Wheeler has provided final restoration grades for SA-6 South Development Area. The DCB also includes the final cover types in revised Drawing C-128. | Included as an attachment to Declaration 005. | South |
| **30.2** | **September 2016-South** | The design change documents revisions to the final grading and SESCP drawings on the SA-6 South Chromium Remedy. Minor grading changes were performed in the field to improve surface drainage. In addition, the extent of demarcation fabric, crushed stone and DGA placed over the Development Area was increased to meet historic fill regulations. SESCP changes included installation of crushed stone toe drain along SA-7, installation of erosion mat, installation of supplemental diversion berms, and installation of stone check dams. | Included as an attachment to Declaration 005. | South |
| **33** | **DC 2015-06-18 (North)** | Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72- inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil, dated February 19, 2013. | Submitted to all Parties on 6/22/15. | North |
| **46** | **DC 2015-9-17** | Extensive searching of available soil suppliers (including 6 specifically identified as potential sources/vendors by Dr. Grabosky) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | Submitted to Parties on September 23, 2015. | SA-6 North & SA-6 South |

| SA-6 North/South Field Change Log | | | | |
|---|---|---|---|---|
| **AmecFW ID** | **Changed Item Identifier** | **Description of Change** | **Comments** | **Site** |
| **48** | **DC 2015-09-28** | Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. | Submitted to Parties on October 1, 2015. | South |
| **50** | **DC 2015-10-02** | As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope. | Submitted to Parties on October 8, 2015. | SA-6 North & SA-6 South |
| **51** | **DC 2015-10-22** | Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D. In lieu of removing sheetpile, the western side was relocated approximately 6 ft. further west. This will result in an expansion of the repair plan area from approximately 14,000 SF to approximately 14,500 SF. This change has no impact of the functionality of the chromium remedy or on the future site development. | Submitted to Contractor only as clarification or response to RFI. | North |
| **54** | **DC 2016-02-02** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. | Submitted to Parties as Attachment to Declaration 004. (Design Change ID changed from DC 2016-02-03 to DC 2016-02-02 to reflect actual date on Design Change form). | North |
| **54.1** | **DC 2016-02-22** | AmecFW revised the SA-6 North cap subgrade in a single localized area in order to accommodate Entact's request to relocate Pump Station #1 (RFI 64). The subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.<br>In addition, for grading purposes, any hydraulic barrier sheets within the Sedimentation Basin that have sections below elevation 12.0 will be trimmed to a uniform elevation of 11.5. | Submitted to Parties as Attachment to Declaration 004. | North |
| **54.2** | **DC 2016-02-25** | This DCB has been issued to provide Entact with the latest SA-6 North HB Wall and SCB wall plan and profile drawings (SN-201 thru SN-205), which were modified to reflect changes made in DC 2016-02-22. | Submitted to Parties as Attachment to Declaration 004. | North |
| **54.3** | **DC 2016-5-11** | The interim grade in the SA-6 North landscape area has been raised by a nominal amount of 0.25' (no changes were made to the roadway grades). The difference between the adjusted Geomembrane Subgrade surface and Interim Grade surface has been verified to meet the minimum and average requirements of the SA-6 North Consent Decree and the 100% Design. As part of DC 2016-5-11, AmecFW issued SA-6 North Interim Grades to Entact. | Submitted to Parties as Attachment to Declaration 004. | North |
| **54.4** | **DC 2016-5-20** | After further review, AmecFW lowered the geomembrane Pump Station #1 on the SA-6 North cap in order to provide additional separation between the geomembrane and the bottom of the vault. (Refer to DC 2016-02-22). | Submitted to Parties on June 15, 2016. | North |
| **54.5** | **DC 2016-7-14** | Design change documenting minor field changes needed to achieve positive drainage in the cap area. | Included as an attachment to November 2016 monthly progress report and included in the finalized Declaration 004. | North |
| **54.6** | **September 2016-North** | The design change documents revisions to the interim/final grading and SESCP drawings on the SA-6 North Chromium Remedy. Minor grading changes were performed in the field to improve surface drainage pending redevelopment. SESCP changes included installation of crushed stone toe drain along SA-7, installation of erosion mat, installation of supplemental diversion berms, and installation of stone check dams. | Included as an attachment to Declaration 005. | North |
| **55** | **DC 2016-05-03** | The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than the USCS classification system. | Submitted to Contractor only as clarification or response to RFI. | SA-6 North & SA-6 South |
| **57** | **DC 2016-03-21** | Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the parties, as documented in the attached emails. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DC 2015-09-17. | Submitted to Parties on March 22, 2016. | SA-6 North & SA-6 South |
| **58** | **DC 2016-05-06** | To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor. The road will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade" | Submitted to Parties on June 30, 2016. | South |
| **59** | **DC 2016-04-20** | This DCB documents the approved sources of Horizon B and Horizon C materials, as agreed to by all parties on the Special Master All-Hands monthly call on April 19, 2016. | Submitted to Parties on April 21, 2016. | SA-6 North & SA-6 South |
| **61** | **DC 2016-11-09** | The limits and the type of restoration north of the SA-6N cap has been modified to be integrated with the SA-6N Non Chrome Remedy. | Included as an attachment to Declaration 005. | North |

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 002 Major (a)(b)<br>Effective Date: 8/14/13 |
| Project Location: SA-6 NORTH | Associated RFI: |
| Title: Hydraulic Barrier/Surcharge Relocation adjacent to 72 inch FM SA-6 North | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

Description of Change/Modification:

The Barrier Wall alignment and Surcharge Program from Station 14+50 to Station 22+13 has been modified to address the concerns of NJDEP/PVSC/JCMUA and Honeywell regarding protection of the 72 inch forcemain. The relocation also impacts subgrade/liner grading and final grades for the Chromium Remedy. Design Drawings have to be modified and design calculations revised in support of the design modification. The Surcharge Monitoring Plan has also been amended and acoustical monitoring will be installed by PVSC.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Modified due to barrier wall relocation in conjunction with 72-in FM protection.<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: Major DCB anticipated, requires review and approval by third parties. | Design Documents Affected:<br>Drawings – 8-11,13-15, 20,29, 31-35, 45-53, 54, 55, 56, 58, 59 |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| | | | |

(Name / Signature):
Samuel G Shallard

Does DCB Result in CCO? ☐ Yes Yes (b) ☑ No
Date:

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

| DESIGN CHANGE BULLETIN | | | |
|---|---|---|---|
| **Sheet #** | **Drawing #** | **Drawing Title** | **Comments** |
| 14 | CN-109 | Cap Area Surcharge Grading Plan Area 1N | Drawings Revised due to Hydraulic Barrier realignment |
| 29 | CN-124 | Geomembrane Grading Plan | Drawings Revised due to Hydraulic Barrier realignment |
| 31 | CN-126 | Interim Grading, Drainage, and Soil Erosion Sediment Control Plan | Drawings Revised due to Hydraulic Barrier realignment |
| 51 | CN-515 | Utility Corridor Locations | Drawings Revised due to Hydraulic Barrier realignment |
| 55 | SN-202 | Hydraulic Barrier Plan and Profile | Drawings Revised due to Hydraulic Barrier realignment |
| 56 | SN-203 | Hydraulic Barrier Plan and Profile | Drawings Revised due to Hydraulic Barrier realignment |
| 59 | SN-206 | 72 Inch Force Main Protection Plan and Details | Drawings Revised due to Hydraulic Barrier realignment |
| 8 | C-103 | Existing Conditions Plan | Drawings with incidental line work changes |
| 9 | C-104 | General Remedy Plan | Drawings with incidental line work changes |
| 10 | C-105 | Subgrade Demolition Plan | Drawings with incidental line work changes |
| 11 | C-106 | Civil Traffic Control and Decontamination Plan | Drawings with incidental line work changes |
| 13 | C-108 | Civil Cap Area Surcharge Grading Plan Area 1S | Drawings with incidental line work changes |
| 15 | C-110 | Civil Cap Area Surcharge Grading Plan Area 3S | Drawings with incidental line work changes |
| 20 | C-115 | Civil Chromium Excavation Interval 4 | Drawings with incidental line work changes |

| | | | |
|---|---|---|---|
| 32 | C-127 | Civil Remediation Final Grading, Drainage, and Soil Erosion Sediment Control Plan | Drawings with incidental line work changes |
| 33 | C-128 | Civil Restoration Plan | Drawings with incidental line work changes |
| 34 | C-201 | Civil Contingent Groundwater Extraction System Plan and Profile | Drawings with incidental line work changes |
| 35 | C-202 | Civil Contingent Groundwater Extraction System Plan and Profile | Drawings with incidental line work changes |
| 45 | C-309 | Miscellaneous Details | Drawings with incidental line work changes |
| 46 | C-501 | Cap Cross Section Plan | Drawings with incidental line work changes |
| 47 | C-502 | Cap Cross Sections | Drawings with incidental line work changes |
| 48 | C-503 | Cap Cross Sections | Drawings with incidental line work changes |
| 49 | C-504 | Cap Cross Sections | Drawings with incidental line work changes |
| 50 | C-505 | Cap Profile | Drawings with incidental line work changes |
| 52 | C-517 | Structural Fill Under Roadways | Drawings with incidental line work changes |
| 53 | S-201 | Hydraulic Barrier Plan and Profile | Drawings with incidental line work changes |
| 54 | S-202 | Hydraulic Barrier Plan and Profile | Drawings with incidental line work changes |
| 58 | S-206 | Existing SA-7 SCB Wall Plan and Profile | Drawings with incidental line work changes |
| 62 | S-504 | Temporary Support of Excavation Plans | Drawings with incidental line work changes |

**DESIGN CHANGE BULLETIN**

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6, Jersey City, New Jersey** | **DCB No.: 011, Minor(a)**<br>**Effective Date: 7/28/14** |
| **Project Location: SA-6 North & South** | **Associated RFI:**<br>☐ Yes, RFI No. _____ ☒ None |
| **Title: Revised Monitoring Well Abandonment Plan Tables** | **Project No.: 3480130377** |
| **Contractor (*Subcontractor*): ENTACT** | |

**Description of Change/Modification:**

Revised tables of wells to be abandoned and retained are provided. The designation (abandon/retain) of several wells has been modified to accommodate the changing site conditions and future work at the site.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☒ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:**<br>Clarify well abandonment requirements<br>**Attachments:** ☒ Yes ☐ No<br>**Cost Implication:** ☐ Yes ☒ No<br>**>$50K** ☐ Yes ☒ No<br>**Schedule Impact** ☐ Yes ☒ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Appendix A-2, Monitoring Well Abandonment Plan Tables |
| **Honeywell (AP) Review:**<br>**Individual: Geoff Shallard Discipline: EOR** | **Initial** GS **Date** 7/30/14 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☒ No<br>**Date** |

**Distribution: Caroline Panico, ENTACT; Adam Ewert, ENTACT; Keith Goisse, ENTACT; Kurt Gimbel, ENTACT; Dennis Nagg, Amec; Stuart Bills, Amec; David Ambrose, Amec**

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval.
(b) – If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-EW-4 (aka 087-MW-142) | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-EW-5 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-EW-6 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-EW-7 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-001 | **Abandon** | S-3 Injection Program | Plaintiffs Requested Monitoring of this Well |
| | | 087-MW-101 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-102 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-103 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-104 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-105 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-106 (aka 087-MW-121) | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-106 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-107 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-108 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-109 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-110 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-111 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-112 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-113 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-114 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-115 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-116 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-117 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-118 | **Retain** | Non-Cr - JCDPW-1B UST AOC | Post remediation GW monitoring |
| | | 087-MW-119 | **Retain** | Non-Cr - JCDPW-1B UST AOC | Post remediation GW monitoring |
| | | 087-MW-120 | **Retain** | Non-Cr - JCDPW-1B UST AOC | Post remediation GW monitoring |
| | | 087-MW-121 (aka 087-MW-106) | | See Above | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 087-MW-122 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-123 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-124 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-125 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-126 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-127 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-128 | **Retain** | Non-Cr - JCDPW-1A/3A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-129 | **Retain** | Non-Cr - JCMUA-1A UST AOC | UST AOC Monitoring |
| | | 087-MW-140 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-141 | **Retain** | Non-Cr - JCMUA-1A UST AOC | Monitoring for EAISB Program |
| | | 087-MW-142 (aka 087-EW-4) | | See Above | |
| | | 087-MW-A26 | **Retain*** | Site-wide LTMP | Shallow GW level monitoring near Rt. 440 sewers |
| | | 087-MW-I30 | Retain | None | |
| | | 087-MW-O19 | Abandon | None | |
| | | 087-MW-O23 | **Retain** | Non-Cr - CEA | Monitoring for CEA |
| | | 087-MW-O29 | **Retain** | In-Situ | Monitoring GW for In-Situ Program |
| | | 087-MW-S19 | Abandon (hold off) | None | |
| | | 087-MW-U28 | Abandon | None | |
| | | 087-MW-W25 | Abandon | None | |
| | | 087-MW-Y20 | Abandon | None | |
| | | ME-02 (aka 087-SB-410) | Abandon | Geotech - Methane Monitoring | |
| | | ME-03 (aka 087-SB-409) | Abandon | Geotech - Methane Monitoring | |
| | | ME-04 (aka 087-SB-408) | Abandon | Geotech - Methane Monitoring | |
| | | 087-PZ-001 | Abandon | None | |
| | | 087-PZ-003 | Abandon | None | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

Added to list of wells to be abandoned
Removed from list of wells to be abandoned

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 087-PZ-005 | Abandon | None | |
| | 088 | 088-MW-001 | **Retain*** | Site-wide LTMP | Shallow GW level monitoring near Rt. 440 sewers |
| | | 088-MW-002 | Abandon | None | |
| | | 088-MW-101 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | Monitoring for EAISB Program |
| | | 088-MW-102 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | Monitoring for EAISB Program |
| | | 088-MW-103 | Abandon | Non-Cr - JCIA-1A UST AOC | Monitoring for EAISB Program |
| | | 088-MW-105 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-106 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-107 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-108 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-109 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-110 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-111 | **Retain** | Non-Cr - JCIA-1B UST AOC | Post remediation GW monitoring |
| | | 088-MW-112 | **Retain** | Non-Cr - JCIA-1B UST AOC | Post remediation GW monitoring |
| | | 088-MW-113 | **Retain** | Non-Cr - JCIA-1B UST AOC | Post remediation GW monitoring |
| | | 088-MW-114 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-115 | Abandon (hold off) | Non-Cr - JCIA-1A UST AOC | |
| | | 088-MW-G19 | Abandon | None | |
| | | ME-01 (aka 088-SB-306) | Abandon | Geotech - Methane Monitoring | |
| | | 088-PZ-001 | Abandon | None | |
| | | 088-PZ-003 | Abandon | None | |
| SA-6 South | 73 | 073-MW-3 | **Retain** | None | |
| | | 073-MW-4 | Abandon | None | |
| | | 073-MW-5 | Abandon | None | |
| | | 073-MW-BB11 | Abandon | None | |
| | | 073-MW-Y10 | Abandon | None | |
| | | 073-PZ-001 | Abandon | None | |
| | 124 | 124-MW-01 | Abandon | | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

Added to list of wells to be abandoned
Removed from list of wells to be abandoned

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 124-MW-02 | Abandon | None | |
| | | 124-MW-07 | Abandon | | |
| | | 124-MW-09 | Abandon | | |
| | | 124-MW-10 | **Retain** | None | Potential additional offsite GW monitoring |
| | | 124-MW-11 | **Retain** | None | Potential additional offsite GW monitoring |
| | | ME-01 (aka 124-SB-503) | Abandon | Geotech - Methane Monitoring | |
| | 125 | 125-MW-01 | Abandon | None | |
| | | ME-02 (aka 125-SB-501) | Abandon | Geotech - Methane Monitoring | |
| | | 125-PZ-001 | Abandon | None | |
| | | 125-PZ-003 | Abandon | None | |
| | 134 | 134-MW-01 | Abandon | | |
| | | 134-MW-02 | **Retain** | Non-Cr - CEA | Quarterly source area monitoring for MNA |
| | | 134-MW-Q08 | Abandon | None | |
| | | 134-MW-V09 | **Retain** | Non-Cr - CEA | Quarterly source area monitoring for MNA |
| | | ME-03 (aka 134-SB-503) | Abandon | Geotech - Methane Monitoring | |
| | | ME-04 (aka 134-SB-504) | Abandon | Geotech - Methane Monitoring | |
| | | 134-PZ-001 | Abandon | None | |
| | | 134-PZ-003 | Abandon | None | |
| | 140 | 140-MW-01 | Abandon | | |
| | | 140-MW-04 | **Retain** | Non-Cr - CEA | Monitor for previous owner's MNA/CEA program |
| | | 140-MW-06 | Abandon | None | |
| | | 140-MW-07 | Abandon | None | |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1a**
**PROPOSED SHALLOW ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| | | 140-MW-08 | Retain | Non-Cr | In Non-Cr Former UST AOC Excavation |
| | | 140-MW-1R | **Retain** | Non-Cr - CEA | Monitor for previous owner's MNA/CEA program |
| | | 140-PZ-001 | Abandon | None | |
| | | 140-MW-106 | Abandon | None | |
| | 163 | 163-MW-1 | **Retain** | Non-Cr - CEA | Monitoring for CEA |
| | | 163-MW-CC8R | Abandon | | |
| | | 163-MW-R05 | Abandon | None | |
| | | 163-MW-2R | **Retain** | Non-Cr & Chromium | Quarterly monitoring of VOC plume fringe (See Table 1b) |
| | | 163-MW-Y6R | Abandon | | |

* Retain if feasible, monitoring well is in excavation area.

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1b**
**PROPOSED SHALLOW ZONE WELLS**
**FOR POST-REMEDY INSTALLATION**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Well | New / Replace / Retain | Related Monitoring Program | Reason to Install |
|---|---|---|---|---|
| SA-6 North | 115-W1-SO | Retain | SA-6 North LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-W6-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-E4-SO | Retain | SA-6 North LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-E5-SO | Retain | SA-6 North LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | SA6N-PZ1-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ1-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ2-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ2-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ3-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ3-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ4-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ4SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ5-SI | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6N-PZ5-SO | New | SA-6 North LTMP | Monitor hydraulic gradients across hyd. Barrier |
| SA-6 South | 115-E1-SO | Abandon | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-E1A-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-W3-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | 115-W5-SO | Retain | SA-6 South LTMP | Monitor hydraulic gradients across SA-7 SCB |
| | SA6S-PZ1-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ1-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ2-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ2-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ3-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ3-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ4-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ4SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 1b**
**PROPOSED SHALLOW ZONE WELLS**
**FOR POST-REMEDY INSTALLATION**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Well | New / Replace / Retain | Related Monitoring Program | Reason to Install |
|---|---|---|---|---|
| | SA6S-PZ5-SI | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-PZ5-SO | New | SA-6 South LTMP | Monitor hydraulic gradients across hyd. Barrier |
| | SA6S-MW-01 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-02 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-03 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-04 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-05 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-06 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-07 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-08 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-09 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-10 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | SA6S-MW-11 | New | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |
| | 163-MW-2R (SA6S-MW-12) | Retain | SA-6S Development AOC LTMP | Monitor post remedy GW quality in Development AOC |

* Retain if feasible, monitoring well is in excavation area.

**TABLE 2**
**PROPOSED INTERMEDIATE ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-MW-13 | **Retain** | | |
| | | 087-MW-A26D | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-W25D | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-O29D | **Retain** | S-3 Injection | Monitor S-3 Injection |
| | | 087-MW-O19D | **Retain*** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-35 | Abandon | GWET LTMP | |
| | | 087-OBS-1D | **Retain** | GWET LTMP | |
| | | 087-OBS-1L | **Retain** | GWET LTMP | |
| | | 087-OBS-2D | **Retain** | GWET LTMP | |
| | | 087-OBS-3L | **Retain** | GWET LTMP | |
| | | 087-OBS-5D | **Retain** | GWET LTMP | |
| | | 087-OBS-6D | Abandon | GWET LTMP | |
| | | 087-PZ-002 | Abandon | SA-6N Design Investigation | |
| | | 087-PZ-004 | Abandon | SA-6N Design Investigation | |
| | | 087-PZ-006 | Abandon | SA-6N Design Investigation | |
| | 088 | 088-MW-15 | **Retain** | GWET LTMP | Define regional flow direction quarterly |
| | | 088-PZ-002 | Abandon | SA-6N Design Investigation | |
| | | 088-PZ-004 | Abandon | SA-6N Design Investigation | |
| SA-6 South | 73 | 073-PZ-002 | Abandon | SA-6S Design Investigation | |
| | 124 | 124-MW-102D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-103D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-104D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-105D | Abandon | Deep Overburden Invest. | |
| | | 124-MW-GO2D | **Retain** | Deep Overburden Invest. | Define regional flow direction quarterly |
| | 125 | 125-PZ-002 | Abandon | SA-6S Design Investigation | |
| | | 125-PZ-004 | Abandon | SA-6S Design Investigation | |
| | 134 | 134-PZ-002 | **Retain** | SA-6S Design Investigation | Define regional flow direction quarterly |
| | | 134-PZ-004 | Abandon | SA-6S Design Investigation | |
| | 140 | 140-PZ-002 | Abandon | SA-6S Design Investigation | |
| | | 140-MW-P05D | **Retain** | Deep Overburden Invest. | Define regional flow direction quarterly |

**TABLE 2**
**PROPOSED INTERMEDIATE ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

| | | | | | |
|---|---|---|---|---|---|
| SA-7 | 115 | 115-E1-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E1-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-E2-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E2-DO | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E3-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E3-DO | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E4-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E4-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-E5-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E5-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-E6-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-E6-DO | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-17 | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-20 | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-A12T | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-E14D | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-MW-U14D | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-W1-DO | Abandon | SA-7 Perimeter Pools | |
| | | 115-W4-DI | **Retain** | SA-7 Perimeter Pools | PP Monitoring |
| | | 115-W4-DO | Abandon | | |

*Optionally, to be re-located north of the open space area

**TABLE 3**
**PROPOSED DEEP ZONE WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Related**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-MW-A26T | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-MW-W25T | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 087-OBS-1T | **Retain** | | |
| | | 087-OBS-4T | **Retain** | GWET LTMP | Monitor GWET drawdown |
| | | 087-OBS-5T | **Retain** | | |
| | | 087-MW-01 | **Retain** | GWET LTMP | Monitor S-3 Injection |
| | | 087-MW-02 | **Retain** | | |
| | | 087-MW-03 | Abandon | None | |
| | | 087-MW-08 | **Retain** | | |
| | | 087-MW-34 | **Retain** | | |
| | | 087-IW-01 | **Retain** | S-3 Injection | Inject and monitor S-3 Injection |
| | 088 | 088-MW-G19T | **Retain** | S-3 Injection | Monitor S-3 Injection |
| | | 088-IW-01 | **Retain** | S-3 Injection | Inject and monitor S-3 Injection |
| | | 088-IW-02 | **Retain** | S-3 Injection | Inject and monitor S-3 Injection |
| SA-6 South | 124 | 124-MW-GO2T | **Retain** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-102T | Abandon | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-103L | Abandon | Plume Diversion | Collect In-situ groundwater sample prior to capping |
| | | 124-MW-104T | Abandon* | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-104L | **Retain*** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-105T | **Retain*** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-106T | **Retain*** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-107T | Abandon | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 124-MW-06 | Abandon | None | |
| SA-7 | 115 | 115-MW-04 | **Retain** | | |
| | | 115-MW-05 | **Retain** | | |

| | | | | | |
|---|---|---|---|---|---|
| | | 115-MW-21 | **Retain** | | |
| | | 115-MW-E14T | **Retain** | | |
| | | 115-MW-U14T | **Retain** | | |
| Offsite, South of SA-6 South | 119 | 119-MW-01T | **Retain** | Plume Diversion | "L-Well" Monitoring Plan Sampling |
| | | 119-MW-02T | **Retain** | Plume Diversion | "L-Well" Monitoring Plan Sampling |

* Retain if feasible, monitoring well is in excavation area.
*Abandon: monitoring well could not be retained durnig excavation.

**TABLE 4**
**PROPOSED BEDROCK WELLS**
**FOR ABANDONMENT / RETAINMENT**

**Added to list of wells to be abandoned**
**Removed from list of wells to be abandoned**

| Study Area | Site | Well | Abandon / Retain | Related Monitoring Program | Reason to Retain |
|---|---|---|---|---|---|
| SA-6 North | 087 | 087-MW-O29T | Abandon | None | |
| | | 087-MW-I30T | Abandon | None | |
| | | 087-MW-14 | Abandon | None | |
| SA-6 South | 073 | 073-MW-1BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 073-MW-10BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | 119 | 119-MW-16BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | 124 | 124-MW-8BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 124-MW-17BR-1 | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 124-MW-17BR-2 | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | 140 | 140-MW-9BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| SA-7 | 115 | 115-MW-208BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 115-MW-211BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 115-MW-215BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |
| | | 115-MW-216BR | **Retain** | GWET LTMP | Annual GWET LTMP water quality sampling |

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.2 Major<br>Effective Date: 11/20/14 |
| Project Location: SA-6 NORTH | Associated RFI: |
| Title: GW EXTRACTION SYSTEM | o Yes, RFI No. ____ þ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification. DCB-007.2 provides the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. Section 10.3 of the Design Report stated "Honeywell reserves the right to propose alternative groundwater extraction designs capable of meeting the criteria stated in Article III.A (56) of the Consent Decree.

Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.2 is applicable to the SA-6N Groundwater Extraction System trench design.

The design was modeled by Cornerstone. The model results indicate that the design will achieve the required gradients. Figure 1, 2 and 3 from the model runs are attached for reference.

The changes impact the following drawings
The following Issued for Construction Drawings are deleted

- CN-201
- CN-202
- CN-203

These following drawings were added

Contingent Groundwater Extractions System Plan and Profile

- CN-201
- CN-202
- CN-203
- CN-204 (discharge force main and electrical)
- CN-310 (Groundwater Extraction Trench Details).

The changes from the well concept to the trench will also impact the Geomembrane Liner Grading CN-123 and CN-124. The Geomembrane liner changes will be issued separately.

It is noted that the 5 piezometric pairs on SA-6N are not included in this DCB. Amec is currently evaluating data collection and transmission options for the piezometers. The piezometer designs will be issued in a separate DCB.


| Reason for Change/Modification: | Explanation or Reason: Design changed based on information gathered during construction |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No<br><br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system plans and profiles-see drawing list in description |


| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |

| (Name / Signature): | Does DCB Result in CCO? ☑ Yes (b) ☐ No |
|---|---|
| Ronald G Shultz | Date: 11/21/14 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FOR FORCE MAIN PROFILE INFORMATION SEE SHEET CN-204.
4. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
5. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
6. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
7. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
8. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON GASKETS.
9. PIEZOMETRIC PAIRS MAY BE INSTALLED USING SOLAR PANELS FOR POWER AND CELL TOWER OR SATELLITE DATA TRANSMITTING. DESIGN OF PIEZOMETRIC PAIR WILL BE ISSUED UNDER SEPARATE COVER.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/19/14 | TDD | TDD | RJR | SGS |
| 1 | 09/13/13 | RJR | RJR | TDD | SGS |
| 0 | 06/07/13 | TDD | TDD | BY | APVD |

DCB 007.2
HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

SGS
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43597

Honeywell
101 COLUMBIA RD. BOX 2104, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, N.J. 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-201 |
| SHEET | 33 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR33-CN-201-Cont Pump Well Sections.dwg PLOT DATE: Wed, 19 Nov 2014 PLOT TIME: 2:55 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-201 FOR NOTES.
4. BARRIER WALL ALIGNMENT SUBJECT TO FINAL LAYOUT CHANGES.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/19/14 | TDD | SGS | | |
| 1 | 09/13/13 | RJR | SGS | | |
| 0 | 06/07/13 | TDD | SGS | | |
| | | BY | APVD | | |

DCB 007.2
HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION

TDD RJR SGS
NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 28 29
NJ Certificate of Authorization Number 24GA28019900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-202 |
| SHEET | 34 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR34-CN-202-Cont_GWE_Trench.dwg PLOT DATE: Thu, 20 Nov 2014 PLOT TIME: 3:15 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-201 FOR NOTES.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

| NO | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/19/14 | TDD | RJR | TDD | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD | SGS |
| | | REVISION | | BY | APVD |

DCB 007.2

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43307

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA29010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-203 |
| SHEET | 35 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR35-CN-203-Cont_GWE_Trench.dwg PLOT DATE: Thu, 20 Nov 2014 PLOT TIME: 3:16 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. THE DESIGN OF THE CONTINGENT GROUNDWATER EXTRACTION SYSTEM IS CONCEPTUAL AND HAS BEEN BASED ON THE AVAILABLE HYDROGEOLOGIC INFORMATION. THE DESIGN IS BASED ON A THEORETICAL SCENARIO USING CONSERVATIVE ASSUMPTIONS. HONEYWELL WILL CONTINUE TO EVALUATE PERTINENT INFORMATION GATHERED THROUGH DEWATERING AND OTHER CONSTRUCTION OPERATIONS. THIS INFORMATION WILL BE USED TO CALIBRATE THE GROUNDWATER CAPTURE MODEL. SUBJECT TO RESULTS OF THAT MODEL CALIBRATION AND EVALUATION OF THE IMPACTS ON THE SYSTEM DESIGN HONEYWELL MAY PROPOSE ALTERNATIVE GROUNDWATER EXTRACTION DESIGNS CAPABLE OF MEETING THE CRITERIA STATED IN ARTICLE III A 58 OF THE CONSENT DECREE.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/19/14 | TDD | SGS | | |
| 1 | 09/13/13 | RJR | SGS | | |
| 0 | 06/07/13 | TDD | SGS | BY | APVD |

DCB 007.2
HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM
ISSUED FOR CONSTRUCTION
REVISION
TDD RJR TDD SGS

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-204 |
| SHEET | 36 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.





## PIPE PERFORATIONS (CD)

NTS — TYP | CN-310


CONSTRUCTION SEQUENCE

- SET MANHOLE BASE AND RISER SECTIONS.
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- OR ADJUST DESIGN GRADE TO MATCH AVAILABLE RISERS – SUBJECT TO ENGINEERS APPROVAL.





## LINER ANCHOR TO CONCRETE STRUCTURE (CE)

NTS — TYP | CN-310




## TYPICAL ACCESS MANHOLE FINAL CONDITION (CB)

NTS STA=1+55±, AND STA=18+00± — CN-201 | CN-203 | CN-310





## GROUNDWATER EXTRACTION PUMP STATION STA 7+35± & STA 12+50± (CC)

NTS — CN-202 | CN-203 | CN-310


## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H303031911 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 1.5" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC VITON O RINGS AND TEFLON SEALS |
| 1.5" DIA. FLEXHOSE | 1 | GRANGER OR APPROVED EQUAL | ITEM #3JT48 25' LENGTH EACH |
| 1.5" DIA. CAMLOCK QUICK DISCONNECTS | 1–MALE 1–FEMALE | GRANGER OR APPROVED EQUAL | ITEM #3LX22 ITEM #3LX14 (GET FROM GRANGER) |
| EXPLOSION–PROOF PLUG AND CONNECTOR | 2–SETS | MELTRIC 22–14043 22–18043 OR APPROVED EQUAL | INLINE PLUG AND RECEPTACLE W/ MALE CAP, HANDLES AND FINGER DRAW PLATES |
| 1" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC WITH VITON O RINGS AND TEFLON SEALS |
| 1.5" SWING CHECK VALVE | 1 | SPEARS OR APPROVED EQUAL | MODEL 4423–015 VITON SEAL AND O RINGS |
| 36' X 50" VALVE VAULT HATCH | 1 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON–LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |




## ELBOW PIPE CLEANOUT (CF)

NTS — CN-202 | CN-310




## GROUNDWATER TRENCH SURCHARGE CONDITION (CA)

NTS — TYP | CN-310

SAMUEL G SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43667

| NO. | DATE | DSGN | BY | APVD |
|---|---|---|---|---|
| 2 | 11/19/14 | TDD | SGS | SGS |
| 1 | 05/14/14 | TDD | SGS | SGS |
| | DCB 007.2 | | TDD | APVD |
| | DCB 007 | | RJR | TDD |
| | REVISION | | CHK | DR |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07932

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-310 |
| SHEET | 45 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CADD\SA6-North-South-GW_Extraction_Trench\NCR45-CN-310 Extraction Trench Details.dwg PLOT DATE: Thu, 20 Nov 2014 PLOT TIME: 3:14 PM




LEGEND

5.0 Predicted Heads

5.0 Measured Heads

NTS

FIGURE 1

Model Calibration
Predicted versus Measured Heads
Model Layer 1 (Shallow Zone)

Study Area 6 North
Jersey City, NJ

cornerstone environmental






FIGURE 2

Post-development Predicted Heads
SA-7 Perimeter Pools Non-functioning
Head in Drain at +2.0'

Study Area 6 North
Jersey City, NJ

cornerstone environmental




## LEGEND

Contingent Pumping System Drain Line

**3.2** ← Head Diff. Across Wall

5.0 Predicted Heads

**NTS**

FIGURE 3

Post-development Predicted Heads
SA-7 Perimeter Pools Non-functioning
Head in Drain at +3.0'

Study Area 6 North
Jersey City, NJ

cornerstone environmental

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 007.3 Major (a)<br>Effective Date: 02/12/15 |
| Project Location: SA-6 SOUTH | Associated RFI: |
| Title: GW EXTRACTION SYSTEM | o Yes, RFI No. NA_ None |
| REPLACE WELLS WITH TRENCHES | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench had not been finalized.
DCB-007.2 provided the details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.
DCB-007.3 provides the details for the SA-6S groundwater collection trenches and associated electrical supply and groundwater discharge piping.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. The revised Design uses a trench design. Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.3 impacts the following drawings
The following Issued for Construction Drawings Extraction System that was based on 9 extraction wells are deleted

- C-201 Plan and Profile
- C-202 Plan and Profile
- C-203 Plan and Profile
- C-304 System Details

The following drawings for the Trench design were added.

- C-201 Trench Plan and Profile
- C-202 Trench Plan and Profile
- C-203 Trench Plan and Profile
- C-204 Discharge Force Main Plan and Profile)
- C-304 Details
- C-306 Details
- C-310 Details).

The changes from the well concept to the trench will also impact the Electrical Drawings. E-101, E-301, E-302 and E-303. The Electrical changes will be issued separately under DCB 007.4. It is noted that DCB 007.2 and DCB 007.3 does show the details for all pumps, motors and controls for the trench design.

The changes from the well concept to the trench will also impact the Geomembrane Liner Grading. The Geomembrane liner changes will be issued separately under DCB 007.5.

Note; piezometric pairs will be installed as shown on both SA-6N and SA-6S. The piezometers on north were previously shown as clouded/temporarily deferred.


| Reason for Change/Modification: | Explanation or Reason: Design changed based on information gathered during construction |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Attachments: ☑ Yes ☐ No<br><br>Cost Implication: ☑ Yes ☐No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: Contingent GW system plans and profiles-see drawing list in description |


| Honeywell (AP) Review: | | | |
|---|---|---|---|
| Individual | Discipline | Initial | Date |
| | | | |

| (Name / Signature): | Does DCB Result in CCO? ☑ Yes (b) ☐ No |
|---|---|
| Samuel G Shallard | Date: 2/16/15 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL, OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON CASKETS.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 02/13/15 | TDD | | | TDD | SGS | SGS |
| 1 | 06/06/14 | | | | | TDD | SGS |

REVISION
DCB 007.3
DCB 007

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELLUERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:44 PM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | TDD | RJR | TDD |
| 1 | 06/06/14 | DCB 007 | TDD | SGS | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS | SGS |
| | | REVISION | BY | APVD | |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 Angelica Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SHM |
| DSGN | TDD | DR RJR | CHK TDD | APVD SGS |

SAMUEL G. SHALLARD
2/13/15
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD., BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | | | BY | APVD |
| 3 | 02/13/15 | TDD | TDD | RJR | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | | RJR | SGS |
| 1 | 05/14/14 | DCB 007 | | TDD | SHM |
| | | REVISION | | RJR | APVD |
| | | DCB 007.3 | TDD | TDD | SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2529
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |





NOTES:

1. USE THUNDERLINE LINK–SEAL TYPE LS 300–C FOR 2"ø OR 3" ø PIPELINES AND TYPE LS 425–C FOR 1"ø AND 1–1/4" PIPELINES OR EQUAL AT ALL MANHOLES AND STRUCTURES.
2. USE PRESSURE GAGE AND PROBE ON PIPELINES THAT SLOPE UPWARDS FROM STRUCTURES ONLY, BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK–JOINT FLEXIBLE MANHOLE SLEEVE OR KOR–N–SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.

## TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL — X


NTS — C–304 | C–306




IN THE LEAK DETECTION ROAD BOXES WHERE THE TOP OF THE TRANSITION PIECE IS CLOSE TO THE UNDERSIDE OF THE ROAD BOX COVER A THREADED FLAT STEEL CAP IS INSTALLED DIRECTLY ON THE THREADED TRANSITION PIECE. A THREADED STEEL PLUG IS INSTALLED IN THE REMAINING LEAK DETECTION RISERS.


## LEAK DETECTION STATION — CG

NTS — C–204 | C–304





## LINER ANCHOR TO CONCRETE STRUCTURE — CE

NTS — TYP | C–304





## AIR RELEASE STATION — CF

NTS — C–204 | C–304





## DOUBLE CONTAINED ELBOW PIPE CLEANOUT — CH

NTS — C–204 | C–304




## EXISTING DOUBLE CONTAINED WYE PIPE CLEANOUT — CI

NTS — C–204 | C–304




## EXISTING 3" LEAK DETECTION STATION — CJ

NTS — C–204 | C–304

NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND C–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002.

SAMUEL G. SHALLARD — NJ PROFESSIONAL ENGINEER — LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 1 | 02/13/15 | REO | RJR | REO | APVD | TDD SGS |
| 0 | 06/07/13 | | | | | TDD SHM |

DCB 007.3
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-304 |
| SHEET | 41 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR41-C-304_GWFM_Details.dwg PLOT DATE: Fri, 13 Feb 2015 PLOT TIME: 2:51 PM




PLAN





SECTION AA





SECTION BB

FLOW METER STRUCTURE DETAIL AZ
NTS STA 63+78 C-204 C-306





NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL AE
NTS C-201 C-202 C-203 C-306




EXISTING 3" FM TRENCH DETAIL CK
NTS STA 63+78 TO STA 68+91 C-204 C-306




NOTE:
SUBCONTRACTOR IS REQUIRED TO VERIFY PRIOR TO BEGINNING WORK FROM STA. 68+91 TO STA. 70+19

TRENCH DETAIL CL
NTS C-204 C-306

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.
3. SEE SHEET C-304 FOR HATCH SPEC.

STEPHEN H. MITCHELL
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04322400

| NO. | DATE | DSGN | |
|---|---|---|---|
| 1 | 02/13/15 | TDD | SGS |
| 0 | 06/07/13 | TDD | SHM |

DCB 007.3
ISSUED FOR CONSTRUCTION

| REVISION | BY | CHK | APVD |
|---|---|---|---|
| REO | DR | RJR | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL

CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |




## GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)


NTS

C-203 | C-310
C-204

- SET MANHOLE BASE AND RISER SECTIONS.
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 1.5" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC VITON O RINGS AND TEFLON SEALS |
| 1.5" DIA. FLEXHOSE | 1 | GRANGER OR APPROVED EQUAL | ITEM #3JT48 25' LENGTH EACH |
| 1.5" DIA. CAMLOCK QUICK DISCONNECTS | 1-MALE 1-FEMALE | GRANGER OR APPROVED EQUAL | ITEM #3LX22 ITEM #3LX14 |
| EXPLOSION-PROOF PLUG AND CONNECTOR | 2-SETS | MELTRIC 22-14043 22-18043 OR APPROVED EQUAL | INLINE PLUG AND RECEPTACLE W/ MALE CAP, HANDLES AND FINGER DRAW PLATES |
| 1" TRUE UNION BALL VALVE | 1 | CHEMTROL OR APPROVED EQUAL | TRUE UNION SERIES PVC WITH VITON O RINGS AND TEFLON SEALS |
| 1.5" SWING CHECK VALVE | 1 | SPEARS OR APPROVED EQUAL | MODEL 4423-015 VITON SEAL AND O RINGS |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |





PLAN VIEW

## PIPE PERFORATIONS (CD)

NTS


TYP C-310




## TYPICAL ACCESS MANHOLE FINAL CONDITION STA.=3+63, STA.=8+90, STA.=14+35 (CB)

NTS

C-201 | C-310
C-202




## GROUNDWATER TRENCH TEMPORARY CONDITION (CA)

NTS

C-201 | C-310
C-202
C-203

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD | BY |
|---|---|---|---|---|---|
| 2 | 02/02/15 | DCB 007.3 | TDD | SGS | TDD |
| 1 | 06/06/14 | DCB 007 | TDD | SGS | SGS |
| DSGN | TDD | DR | RJR | TDD | APVD |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2109, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, N.J. 08619
609-890-2900
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-310 |
| SHEET | OF 66 |

# DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB Type:** Major (a)<br>**Effective Date:** 6/18/15 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** SA-6 North, Site 087 In-situ Injections | ☐ Yes, RFI No. ___ ☑ None |
| | **Project No.:** 3480150438.5710.571001 |
| **Contractor (Subcontractor):** ERFS | |

Injections of calcium polysulfide (CAPS) will be implemented in a limited portion of TA-10, north of the northern curbline for the future Stegman Boulevard to be constructed during the Bayfront Redevelopment project. Monitoring wells installed in the injection area and between the injection area and the adjacent 72-inch force main will be used to measure sulfate conditions in shallow groundwater. If necessary, clean potable water may be injected into the monitoring wells to dilute the sulfate concentrations in the shallow groundwater adjacent to the 72-inch force main. See attached memorandum, figures, and Table 1 prepared by Amec Foster Wheeler. While the specific scope of the proposed injections is provided in the attachment, the work will generally be performed in accordance with Amec Foster Wheeler's approved *Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil*, dated February 19, 2013.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** Focused injections north of 72-inch force main to avoid impact to concrete shell of pipeline. |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** *Revised Work Plan for In-Situ Treatment of Chromium Impacted Soil*, dated February 19, 2013 and *Work Plan for In-Situ Treatment of Chromium Impacted Soils*, dated January 29, 2014 |

**Honeywell (AP) Review:**

| | | | |
|---|---|---|---|
| **Individual:** Dennis Nagg | **Discipline:** | **Initial:** | **Date:** |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☑ **Yes (b)** ☐ **No** |
| | | **Date:** | |

**Distribution:**

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

**Honeywell RES**

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 046 **DCB Type:** Minor (a)<br>**Effective Date:** 9/17/15 |
| **Project Location:** SA-6<br>**Title:** Planting Soil Specifications | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** Revisions to the Planting soil Specifications. | |
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See additional comments<br>**Attachments:** ☑ Yes ☐ No<br>Dr. Jason Grabosky letter<br>Specification 02315, Section 2.12 , Table 1<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Extensive searching of available soil suppliers (including 6 identified by Dr. Grabosky/Rutgers University) indicated that current sources could substantially meet the most critical, but not all, IFC specifications. In response, AmecFW submitted the provided borrow source testing data per specifications to Dr. Grabosky for his review. Dr. Grabosky selected specific blends from the list that he identified as acceptable for use within the Open Space Areas. In addition, Dr. Grabosky recommended minor revisions to the specifications that the AmecFW engineer has accepted. Dr. Grabosky's letter and specification revision recommendation are attached. | **Design Documents Affected:**<br>Specification 02315, Section 2.12 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 10/22/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

RUTGERS
School of Environmental and Biological Sciences

Urban and Community Forestry Program
Dept. of Ecology Evolutionand Natural Resources
Environmental and Natural Resources Bld, Room 144
Rutgers, The State University of New Jersey
14 College Farm Road
New Brunswick, NJ 08901-8551

September 17, 2015

To whom it may concern:

I was contacted by the Mr Shallard of ***Amec Foster Wheeler Environment & Infrastructure, Inc*** with regard to questions on the soil materials available for a NJ Project. Honeywell/AmecFW submitted results of analysis of Planting Soil samples from multiple vendors, selected from a list provided by Rutgers, for Horizon A, B and C that are under consideration for use on the SA-6 Project (refer to attached excel table). These data were to be used to select the vendor and soil products available for each of the soil layers to be used on the project. It is my understanding that multiple vendors have been contacted including those provided by Rutgers (email May 13th 2015) as potential sources and, that the list and samples provided, is indicative of what is available in the market place at this time.

While the list of criteria (Sand/Silt/clay/organics/pH) is applicable to all samples the importance of each of these criteria varies due to the intended purpose of each Horizon.
In my review I have identified samples listed which I consider acceptable, or acceptable subject to minor modification, to meet the project goals. The following samples are acceptable to accomplish the goals of the many design demands on this system.

Horizon A topsoil:
Nature's Choice (NC-TS-002-NCCWS) as the preferred or Nature's Choice (NC-TS-002-NCCW).
Both exceed the gravel percentage component of the specification, however one might envision the percentages as targets, and the excess of gravel in these cases does not change the functional behavior of the material for plant growth or drainage potential. NCCW has a higher organic component which is high enough to exhibit shrinkage as the organic materials decompose, so while a functionally acceptable soil material for the purpose, the shrinkage will be noticed on landscape edges next to structures such as sidewalks, thus CCCWS is preferred. The acceptable gravel content of the specification should be revised upward from 5% to <10%.

Horizon B:
Nature's Choice (NC-HC-001) would be a good choice, as the lower organic level is not problematic, and actually sets a natural layering and gradation as underlayment to the topsoil. The pH increases from 5.0 in the topsoil to 5.96, and I do not see this as an issue, several species may well prefer the nutrient availability afforded by the higher pH. One might consider adding some organic content and blending into the B horizon material. I am not in favor of the effort and expense, as the proposed layers will change in organic content and develop a natural progression on their own over time. The Sand % should be changed from a single number of 80% to a range of 80-90%. The pH maximum should be increased from 7 to 7.5. Organic content should be changed from a range of 1.5 - 3.5% to <4%.

Horizon C:
Nature's Choice Sample (NC-HC1-002) is very close to meeting the originally specified requirements. The Clay content is 12% as compared with the specified maximum of 15-20% and the pH was reported to be

RUTGERS
School of Environmental
and Biological Sciences

7.57 as compared with the 7.5 specified. These deviations are not considered to be significant. This sample will meet the original design objectives. The Clay Content specification should be broadened to 10-20% and pH specification modified to less than 7.7 to provide for consistency between the sample and specifications.
Advanced Soil Technologies (AST-HB-002) is also a potential candidate if the sand content could be reduced to <80%. The organic level is elevated, but not problematic. Organic content should be changed from 1% maximum to <4%.

Table 1 attached summarizes the proposed changes.

In total the three layers would be very reasonable for acceptable landscape growth expectations, and provide available moisture for plants and drainage potential in a normal manner *as long as the materials are not heavily compacted after placement by construction equipment.*

As with any project, the key to success will ultimately be in the construction management/traffic controls/equipment storage planning as related to the protection of the soil investment after placement. This will be particularly important with the landscape contractor equipment in planting the trees and other landscape elements, as much as with the pavement contracting for sidewalks and structures.

Respectfully submitted,



Jason Grabosky
John and Eleanor Faculty Scholar in Urban and Community Forestry
Department of Ecology, Evolution and Natural Resources
Rutgers University
New Brunswick, NJ

RUTGERS
School of Environmental and Biological Sciences

Table 1 summarizes the modified criteria based on availability. Provision of soils meeting the criteria listed in Table 1 below will meet the objectives of providing soils that are suitable for the SA-6 project. These changes have been reviewed with the AmecFW Engineer of Record and it is recommended that both the project specification and Open Space Design Standard be amended as noted in the Table 1 below.

| SA-6 Planting Soil Specification-TABLE 1 | | | | | | |
|---|---|---|---|---|---|---|
| Revision 1 September 2015 | | | | | | |
| **Material SPEC 02315 SECT 2.12** | **Description (USDA soil triangle)** | **% Sand** | **% Silt** | **% Clay** | **% Organic Matter** | **pH** |
| Horizon A Modified | Friable Fertile Sandy loam/loamy sand | 60-80 | ▫20 | <20 | 3.5-6 | 5-6.5 |
| Horizon B Modified | Loamy sand | 80-90 | <10 | 10-15 | <4% | 5.5-7.5 |
| Horizon C Modified | Sandy loam to loamy sand | 70-80 | <10 | 10-20 | <4% | 5-7.7 |

1. *Horizon C. Clay content lowered from a minimum of 15% to a minimum of 10%. Organic content increased from <1 to <4%. pH content maximum increased from 7.5 to 7.7.*
2. *Horizon B. Sand changed from a single number of 80% to a range of 80-90%. pH maximum increased from 7 to 7.5. Organic content changed from a range of 1.5- 3.5% to <4%.*
3. *Horizon A. Gravel content increased from 5% maximum to <10%.*
4. *Soil Descriptions. The Planting Soil specifications include soil descriptions based on the USDA Soil Texture Triangle. Soils provided should be consistent with the Soil Texture Triangle.*

| SA-6 Planting Soil Specification-TABLE 1 | | | | | | |
|---|---|---|---|---|---|---|
| Revision 1 September 2015 | | | | | | |
| **Material SPEC 02315 SECT 2.12** | **Description (USDA soil triangle)** | **% Sand** | **% Silt** | **% Clay** | **% Organic Matter** | **pH** |
| Horizon A Topsoil | Friable fertile loam, fine sandy loam or sandy loam | -- | -- | -- | 3.5-6% | 5.0-6.5 |
| Horizon A Modified 9/16/15 | Friable Fertile Sandy loam/loamy sand | 60-80 | <=20 | <20 | 3.5-6 | 5-6.5 |
| Horizon B | Sandy Loam | 80-85% | ≤10% | 10-15% | 1.5-3.5% | 5.5-7.0 |
| Horizon B Modified 9/16/15 | Loamy sand | 80-90 | <10 | 10-15% | <4% | 5.5-7.5 |
| Horizon C | Uniform Sandy Loam | 70-80% | ≤10% | 15-20% | 1% max | 5.0-7.5 |
| Horizon C Modified 9/16/15 | Sandy loam to loamy sand | 70-80 | <10 | 10 – 20% | <4% | 5-7.7 |

1. *Soil Descriptions. The Planting Soil specifications include soil descriptions based on the USDA Soil Texture Triangle. Soils provided should be consistent with the Soil Texture Triangle.*

2.12 PLANTING SOILS

Planting Soils have been designated as Horizon A, B and C. Soil Horizon A – Topsoil will be a nominal thickness of 6 inches and shall conform to the requirement noted below.

A. Topsoil - Topsoil shall be placed over the Horizon B and C planting soils to final development grades shown in the design drawings. Topsoil will have a nominal depth of 6 inches. Topsoil shall be in accordance with Section 02900, "Topsoil and Seeding". Topsoil shall be certified clean from the borrow source or origin, based on analytical testing data, as approved by the Engineer. Topsoil shall be natural, friable, fertile loam, fine sandy loam or loamy sand with an organic matter content of 3.5% - 6% and a pH range of 5.0 – 6.5. Sand 60-80%, Silt ≤20%, Clay <20%. Specification 02900 requires that all materials pass a 1.5 inch sieve. Spec 02900 will be modified to allow <10% Gravel.

B. Soil Horizon B - soils will only be used in areas where the total depth of cover soils exceeds 36 inches. During the Interim Phase no Horizon B soil will be placed. Horizon B soils will be a loamy sand having the following properties:

Loamy Sand classification having ~~80~~ 80-90% sand, < 10% silt, 10-15% clay.
pH range 5.5 – 7.5 ~~7.0~~.
Organic Matter (by weight) ~~1.5-3.5~~ < 4 %

C. Soil Horizon C – During Interim Grading Horizon C Soil will be placed between the root barrier and the Horizon A soil. The first 6 inches of Horizon C soils to be placed directly above the root barrier will be compacted to a minimum 90% of Standard Proctor. To meet Final Grading and planting requirements Horizon A soils will be stripped as necessary and Horizon C soils shall be re-graded to provide an appropriate depth of 18 inches. Horizon C soil shall consist of sandy loam to loamy sand having the following properties:

1. Sandy loam to loamy sand classification with 70-80% sand, <10% silt, ~~10 – 15%~~ 10 - 20% clay.
2. pH range 5.0 – 7.7 ~~7.5~~.
3. Organic Matter (by weight) ~~1~~ < 4 % ~~max~~.

**Horizon A Soils- Geotechnical Sample Results**
**Study Area 6**
**Jersey City, NJ**

| Sample Date | Material | % Sand | % Silt | % Clay | % Gravel[2] | % Organic Matter | pH |
|---|---|---|---|---|---|---|---|
| | **Revised Specification Values[1]** | **60 - 80%** | **≤20%** | **<20%** | **<10%** | **3.5 - 6%** | **5.0 - 6.5** |
| 6/11/2015 | Advanced Soil Technologies Topsoil (AST TS -001) | 80.0% | 10.0% | 10.0% | 11.7% | 4.3% | 7.84 |
| 6/15/2015 | Natures Choice Topsoil (NC TS-001) | 75.0% | 13.0% | 11.0% | 21.6% | 5.4% | 7.33 |
| 6/29/2015 | Advanced Soil Technologies (AST HA-002) | 74.0% | 14.0% | 12.0% | 11.4% | 9.0% | 7.48 |
| 7/6/2015 | Nature's Choice (NC-HB1-002) | 76.0% | 10.0% | 14.0% | 13.3% | 3.9% | 7.46 |
| 7/7/2015 | Nature's Choice (NC-TS-002-NCCWS) | 68.0% | 20.0% | 12.0% | 5.8% | 3.8% | 5 |
| 7/7/2015 | Nature's Choice (NC-TS-002-NCCW) | 64.0% | 22.0% | 14.0% | 6.9% | 6.4% | 5 |

**Notes:**

1.) Specification values revised according to letter from Dr. Jason Grabosky of Rutgers University, dated September 17, 2015.
Samples deemed acceptable in Dr. Grabosky's letter are highlighted in green.

2.) Refer to Specification 02900 - Topsoil and Seeding, Section 2.01.B.2.

**Horizon B Soils - Geotechnical Sample Results**
**Study Area 6**
**Jersey City, NJ**

| Sample Date | Material | % Sand | % Silt | % Clay | % Organic Matter | pH |
|---|---|---|---|---|---|---|
| | **Revised Specification Values[1]** | **80 - 90%** | **<10%** | **10 - 15%** | **<4%** | **5.5 - 7.5** |
| 6/11/2015 | Advanced Soils Technologies (AST HB-001) | 87.0% | 7.0% | 6.0% | 5.4% | 7.19 |
| 6/11/2015 | Advanced Soils Technologies (AST HC-001) | 67.0% | 20.0% | 13.0% | 2.3% | 7.56 |
| 6/15/2015 | Nature's Choice (NC-HB-001) | 78.0% | 8.0% | 13.0% | 2.9% | 7.05 |
| 6/15/2015 | Nature's Choice (NC-HC-001) | 84.0% | 3.0% | 13.0% | 0.2% | 5.96 |
| 6/29/2015 | Advanced Soils Technologies (AST HB-002) | 87.0% | 7.0% | 6.0% | 4.0% | 7.4 |
| 6/29/2015 | Advanced Soils Technologies (AST HC-002) | 72.0% | 14.0% | 14.0% | 0.9% | 7.8 |
| 7/6/2015 | Nature's Choice (NC-HB1-002) | 76.0% | 10.0% | 14.0% | 3.9% | 6.66 |

**Note:**
1.) Specification values revised according to letter from Dr. Jason Grabosky of Rutgers University, dated September 17, 2015. Samples deemed acceptable in Dr. Grabosky's letter are highlighted in green.

**Horizon C Soils - Geotechnical Sample Results**
**Study Area 6**
**Jersey City, NJ**

| Sample Date | Material | % Sand | % Silt | % Clay | % Organic Matter | pH |
|---|---|---|---|---|---|---|
| | **Revised Specification Values[1]** | **70 - 80%** | **<10%** | **10 - 20%** | **<4%** | **5.0 - 7.7** |
| 6/11/2015 | Advanced Soils Technologies (AST HB-001) | 87.0% | 7.0% | 6.0% | 5.4% | 7.19 |
| 6/11/2015 | Advanced Soils Technologies (AST HC-001) | 67.0% | 20.0% | 13.0% | 2.3% | 7.56 |
| 6/15/2015 | Nature's Choice (NC-HB-001) | 78.0% | 8.0% | 13.0% | 2.9% | 7.05 |
| 6/15/2015 | Nature's Choice (NC-HC-001) | 84.0% | 3.0% | 13.0% | 0.2% | 5.96 |
| 6/29/2015 | Advanced Soils Technologies (AST HB-002) | 87.0% | 7.0% | 6.0% | 4.0% | 7.4 |
| 6/29/2015 | Advanced Soils Technologies (AST HC-002) | 72.0% | 14.0% | 14.0% | 0.9% | 7.8 |
| 7/6/2015 | Nature's Choice (NC-HC1-002) | 79.0% | 9.0% | 12.0% | 0.3% | 7.57 |
| 7/6/2015 | Nature's Choice (NC-HC2-002) | 85.0% | 9.0% | 6.0% | 0.3% | 8.25 |
| 7/6/2015 | Nature's Choice (NC-HC3-002) | 85.0% | 11.0% | 4.0% | 0.1% | 8.37 |

**Note:**
1.) Specification values revised according to letter from Dr. Jason Grabosky of Rutgers University, dated September 17, 2015. Samples deemed acceptable in Dr. Grabosky's letter are highlighted in green.

Honeywell RES


DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** **DCB Type:** Major (a)<br>**Effective Date:** 9/28/15 |
| **Project Location:** SA-6 South, Site 163<br>**Title:** Site 163 Excavation | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description:** Chromium-impacted soils within the residential footprint of Site 163 that remained at levels above 20 ppm hexavalent chromium after in-situ treatment will be excavated in lieu of additional in-situ treatment and further sampling. The residential footprint includes the area north of the northern curbline of the future River Front Park/Riverside Drive/Kellogg Street to be constructed during the Bayfront Redevelopment project. A plan view and cross sections of the excavation area are included in the attached Figure 1. Soils that were treated successfully will not be subject to excavation or to further sampling. The remaining chromium-impacted soils identified in the area south of the northern curbline are within the future River Front Park/Riverside Drive /Kellogg Street as depicted on the attached Figure 2 and will be subject to a deed restriction and not be subject to further sampling.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>Noted in Description<br>**Attachments:** ☑ Yes ☐ No<br>Figure 1<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>A new drawing C-129 will be issued showing the limits of excavation depicted on Figure 1. |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 10/1/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☑ **Yes (b)** ☐ **No**<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.





NOTE: AREA NORTH OF PROPOSED EXCAVATION PREVIOUSLY COMPLETED AND BACKFILLED WITH CLEAN IMPORTED MATERIAL OR HISTORIC FILL (<20 PPM HEX CR)





SECTION A−A'





SECTION B−B'




SECTION C−C'




SECTION D−D'




SECTION E−E'




LEGEND

- PDI BOTTOM SAMPLE LOCATION
- PDI SIDEWALL SAMPLE LOCATION
- LIMIT OF EXCAVATION
- OVERBURDEN (<20 PPM HEX CR)
- CHROMIUM IMPACTED SOIL (20−240 PPM HEX CR)

NOTES:

1. HONEYWELL WILL EXCAVATE THE AREA DEPICTED ON THIS FIGURE AND IS PLANNING LOGISTICS WITH IT'S CONSTRUCTION MANAGEMENT TEAM AND REMEDIAL CONTRACTOR(S).
1. UNDER THE EXCAVATION SCENARIO, HONEYWELL WILL CONTINUE TO EVALUATE USING SHEETPILE FOR TEMPORARY EXCAVATION SUPPORT, BACKSLOPING, OR A COMBINATION OF BOTH.
2. OVERBURDEN MATERIAL WILL BE EXCAVATED, STOCKPILED, AND HANDLED IN ACCORDANCE WITH THE APPROVED SOIL MANAGEMENT PLAN IN THE 100% DESIGN.
3. CHROMIUM−IMPACTED MATERIAL WILL BE EXCAVATED, STOCKPILED, AND HANDLED IN ACCORDANCE WITH THE APPROVED SOIL MANAGEMENT PLAN IN THE 100% DESIGN.
4. BACKFILLING WILL OCCUR UPON VERIFICATION BY INDEPENDENT THIRD PARTY LICENSED LAND SURVEYOR THAT HORIZONTAL AND VERTICAL EXTENTS OF EXCAVATION HAVE BEEN ACHIEVED.
5. HONEYWELL MAY IMPLEMENT THIS EXCAVATION BY THE END OF 2015.
6. HONEYWELL MAY ELECT TO USE A CONTRACTOR OTHER THAN ENTACT TO IMPLEMENT THIS EXCAVATION ACTIVITY.
7. THE PROPOSED EXCAVATION FOOTPRINT IS 6,335 SF AND 5 BOTTOM SAMPLES SATISFIES THE NJDEP APPROVED FREQUENCY OF 1:1300 SF AS IDENTIFIED IN THE 100% DESIGN REPORT.

Prepared/Date: TDD 9/22/15
Checked/Date: DEN 9/22/15

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD. BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec foster wheeler<br>Environment & Infrastructure, Inc.<br>200 American Metro Blvd, Suite 113<br>Hamilton, NJ, 08619, (609) 689 - 2529 | SITE 163 - ADDITIONAL<br>CHROMIUM EXCAVATION AREAS<br>FIGURE 1 |

C:\Donovan\SA−6 South Excavation Limits April 2012\2013 Excavation Shapes\SA−6 South Design Change Bulletin\Site 163 Excavation Shp\Figure 1 Site 163 Additional Excavation Areas.dwg Thu, 26 Sep 2013 − 10:28am tony.donovan

HACKENSACK RIVER

NOTE: AREA NORTH OF PROPOSED EXCAVATION PREVIOUSLY COMPLETED AND BACKFILLED WITH CLEAN IMPORTED MATERIAL OR HISTORIC FILL (<20 PPM HEX CR)

FUTURE CURB LINE (TYP)

IN-SITU TREATMENT AREAS WITH SOILS THAT REMAIN >20 PPM FOR HEXAVALENT CHROMIUM (TYP)

NOTE: APPROXIMATE AREA SUBJECT TO A DEED RESTRICTION UNDER RIVERFRONT PARK, RIVERSIDE DRIVE, OR KELLOGG STREET

APPROXIMATE LOCATION OF EXISTING BULKHEAD (TYP)

DROYERS COVE

0 20 40 80
HORIZONTAL SCALE

Prepared/Date: TDD 9/24/15
Checked/Date: DEN 9/24/15

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2529

SITE 163
DEED RESTRICTED AREAS
FIGURE 2

C:\Darrenm\SA-6 South Excavation Limits April 2013\2013 Excavation Shapes\SA-6 South Design Change Bulletins\Site 163 Excavation SP\Figure 2 Site 163 Deed Restricted Areas.dwg Mon, 28 Sep 2015 - 4:15pm tonyAdamonis

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 007.4 **DCB Type:** Major(a)<br>**Effective Date:** 9/3/15; **Rev. 1** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** GW Extraction System – Revisions of Electrical to Replace Wells with Trenches | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description:**

DCB-007.1 was issued for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification.

DCB-007.2 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

DCB-007.3 provided the final details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping

DCB-007.4 provides the revised electrical plan, one line electrical drawings and electrical details for SA-6S.

The 100% Design included a Conceptual Design for the Groundwater Extraction system that was based on use of 9 extraction wells in each open space area and common header system. The revised Design uses a trench design. Details related to the Administrative basis for the change are provided in DCB 007.1.

DCB 007.4 is applicable to the Groundwater Extraction System electrical drawings for SA-6S (electrical plan and one line electrical drawing).


Drawings that are revised in this DCB are:
SA-6S


- C-201
- C-202
- C-203
- C-204
- C-306
- C-310
- E-301
- E-302
- E-303

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** : Design changed based on information gathered during construction |
| | **Attachments:** ☑ Yes ☐ No<br>C-201, C-202, C-203, C-204, C-306, C-310, E-301, E-302, E-303 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |

| | | | |
|---|---|---|---|
| **Additional Comments:** | | **Design Documents Affected:** C-201, C-202, C-203, C-204, C-306, C-310, E-301, E-302, E-303 | |
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☑ **Yes (b)** ☐ **No** |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF FILTER STONE AND HDPE PIPE.
5. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
6. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
7. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
8. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
9. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON GASKETS.
10. INSTALL INSTRAMENTATION CONDUIT FOR PAIRE PIEZOMETERSREADIED WITH PULL STRINGS FOR FUTURE INSTRAMENTATION CABLE INSTALLED BY OTHERS.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 3 | 08/14/15 | TDD | RJR | TDD | | RJR | SGS |
| 2 | 02/13/15 | | | | | TDD | SGS |
| 1 | 06/06/14 | | DCB 007.4 | | | TDD | SGS |
| | | | DCB 007.3 | | | | |
| | | | DCB 007 | | | | |
| | | | REVISION | | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134,
140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2626
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-201 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR34-C-201_Cont_GWE_Trench.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:13 AM




## NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD | REVISION | BY | APVD |
|---|---|---|---|---|---|---|---|---|
| 4 | 08/14/15 | TDD | RJR | TDD | SGS | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | | | | | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | | | | | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | | | | | DCB 007 | TDD | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

THE DRAWING IS THE PROPERTY OF AMEC; NO WORK ALL PATENTED AND PATENTABLE FEATURES AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR IN PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 Horizon Center Blvd, Suite 110
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28016900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-202 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR35-C-202_Cont_GWE_Trench.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:11 AM




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. REFER TO NOTES ON SHEET C-201.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 8'
0 4 8 16
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 4 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS |
| 2 | 07/30/14 | DCB 007.1 | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | SHM |
| DSGN | TDD | DR | RJR | CHK | TDD | APVD | SGS |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE04243600
9/2/15

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE LICENSE AGREEMENT DATED 1/1/2007 TO WHICH YOU ARE A PARTY. REPRODUCTION OF THIS DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

GROUNDWATER EXTRACTION TRENCH PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-203 |
| SHEET | OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR36-C-203_Cont_GWE_Trench.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:09 AM

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 24 OF 25**

- **Declaration #5 Part 2**

**Attachments P (Part 2) – Q**

**ATTACHMENT P**
**DESIGN CHANGES**
**PART 2**

HACKENSACK RIVER

PIERHEAD AND BULKH

SA-7

SA-6 SOUTH

SA-6 NORTH

NOTE:
CONTRACTOR TO VERIFY CONDITION OF EXISTING E&I AND FM AND STATION OF TIE-INS PRIOR TO INITIATING WORK.

AZ C-204 | C-306 DROP STRUCTURE STA=63+78 END NEW 2" FM AND START OF EXISTING 3" HDPE FM IN 6" HDPE

AW C-204 | E-303 ELECTRICAL HANHOLE DETAIL (TYP) NOTE IF AVAILABLE REUSE EXISTING ELECTRICAL PULL BOX IN THIS LOCATION

CI C-204 | C-304 EXISTING PW-1 CLEANOUT STATION STA 69+70 INV=2.40 (RECORD)

CJ C-204 | C-304 EXISTING PW-1 LEAK DETECTION STATION STA 70+11 INV=9.35 (RECORD)

CF C-204 | C-304 AIR RELEASE STATION STA 70+19 GRADE EL=16.3

STA=70+19 END OF EXISTING 3" FM AND START OF NEW 2" FM TO SA-6 NORTH

EXISITNG 2" REGIONAL GROUNDWATER FORCE MAIN FROM EW 115-MW-215BR

EXISITNG 3" EFFLUENT AND 1½" SANITARY FM

EXISTING 2"I AND 2"E CONDUITS

CK C-204 | C-306 EXISTING 3" FM TRENCH DETAIL FORCE MAIN FROM FLOW METER STRUCTURE STA 63+78 TO STA 68+91

STA=68+91 EXISTING REGIONAL GROUNDWATER EXTRACTION WELL 115-MW-215BR

CL C-204 | C-306 EXISTING 6"X3" FM TRENCH DETAIL

EXISTING SA-7 SCB WALL

EXTRACTION TRENCH

FINAL REMEDY CONTOURS (TYP)

CM C-204 | E-303 PIEZOMETER CONDUIT DETAIL

CG C-204 | C-304 LEAK DETECTION STATION STA=61+48, GRADE EL=10.1

CH C-204 | C-304 DOUBLE CONTAINED ELBOW PIPE CLEANOUT STATION STA=61+39, GRADE EL=10.0

SA-6 NORTH FINAL REMEDY GRADE

CH C-204 | C-304 DOUBLE CONTAINED ELBOW PIPE CLEANOUT STATION STA=72+50, GRADE EL=10.0

1" RGS CONDUIT 2" SCH 80 PVC

2" HDPE IN 4" HDPE

EXISITNG 2"I AND 3"E CONDUITS

SA-6 NORTH GROUNDWATER EXTRACTION FORCE MAIN (SEE SHEET CN-203)

EXISTING HYDRAULIC BARRIER

CAP TWO 2" HDPE IN 4" HDPE GW FORCE MAINE 5 FEET OUTSIDE FOUNDATION OF GWTP

EXISTING GROUNDWATER TREATMENT BUILDING

EXISTING 72 IN. FM

SA-6 SOUTH CAP AREA

2" RGS CONTROL CONDUIT 2" PVC SCH 40 POWER CONDIT

PROPOSED HYDRAULIC BARRIER

CC C-204 | C-310 VALVE VAULT STA 60+31±, GRADE EL=18.1

GROUNDWATER EXTRACTION PUMP STATION STA 19+74 EXTRACTION TRENCH= STA 60+24 EXTRACTION FORCE MAIN

MATCH LINE SHEET C-203, C-204

MATCH LINE SHEET C-202

MATCH LINE BELOW

END EXISTING 3" HDPE IN 6" HDPE REDUCE TO 2" HDPE IN 4" HDPE STA=70+19, INV= 10.1

AIR RELEASE STATION STA=71+75 GRADE EL=17.8 C-204 | C-304 CF

EXISTING PW-1 LEAK DETECTION STA 70+13 INV=9.35 (RECORD) C-204 | C-304 CJ

EXISTING 3" CLEANOUT STA 69+70 INV=2.4 (RECORD) C-204 | C-304 CI

EXISTING SA-7 SCB WALL

PROPOSED SA-6 NORTH REMEDY GRADE

FUTURE DEVELOPMENT 48" STORM INV=4.0 BY OTHERS

STA=68+91 REGIONAL GROUNDWATER EXTRACTION WELL 115-MW-215BR

INV=10.1

INV=9.35 (RECORD)

EXISTING 72" FORCE MAIN, TOP OF PIPE EL= ± 13.8

CAP TWO 2" HDPE IN 4" HDPE GW FORCE MAINS 5 FEET OUTSIDE FOUNDATION OF GWTPSTA 73+38 INV=11.16

EXISTING GROUNDWATER TREATMENT BUILDING STA 73+43

INV=2.4

EXISTING 54" FM ABANDONED

SA-7 BULKHEAD AREA

SA-6 NORTH

GROUNDWATER EXTRACTION PUMP STATION STA 60+24± CENTER C-204 | C-310 CC

PROPOSED VALVE VAULT STA 60+31± GRADE EL=18.1

2" HDPE DR 11 FM IN 4" HDPE DR17

INSTALL 2" THICK INSULATION BOARD OVER FM WERE COVER IS LESS THEN 3'

CG C-204 | C-304 DOUBLE CONTAINED ELBOW PIPE CLEANOUT STA=61+39, GRADE EL=10.0

CH C-204 | C-304 LEAK DETECTION STATION STA=61+48

AZ C-204 | C-306 DROP STRUCTURE STA=63+78± GRADE EL=9.7 PROPOSED 2" HDPE DR11 IN A 4" HDPE DR17 INV. IN=7.5, EXISTING 3" HDPE FM IN 6" HDPE INV. OUT=0.97

INV=14.7

INV=14.3

GEOMEMBRANE GRADE

STA 61+37 90° ELBOW INV.=7.51

FINAL REMEDY GRADE

FUTURE DEVELOPMENT 60" DRAIN PIPE INV=4.1 BY OTHERS

EXISTING GRADE

EXISTING GRADE

INV=6.7

INV=6.7

INV=7.5

EXISTING SA-7 SOUTH SCB WALL

2" HDPE DR 11 FM IN 4" HDPE DR17

EXISTING 3" HDPE IN 6" HDPE STA 63+78 TO STA 70+19

EXISTING SA-7 PERIMETER POOL ALONG SCB WALL EL=5.0

INV=(3.5)

EXISTING SA-7 SCB WEST WALL

INV=0.97

EXISTING 3" HDPE DR11 FM INSIDE 6" HDPE DR17 PIPE

SA-7

SA-6 SOUTH

SA-7 BULKHEAD AREA

MATCH LINE ABOVE

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. DEWATER AS NECESSARY TO PROVIDE SUITABLE CONDITIONS FOR PLACEMENT OF STONE AND HDPE PIPE.
4. USE SHEETING/SHORING TRENCH BOXES OR OTHER MEANS AS NECESSARY TO ALLOW FOR PLACEMENT OF STONE AND HDPE PIPE.
5. AT STATION 66+65, IF AVAILABLE, REUSE EXISITNG ELECTRICAL PULL BOX.
6. FROM STATION 63+78 TO STATION 68+91 REMOVE ANY EXISTING WIRING REMAINING IN THE 2" E+I CONDUITS.
7. FORCEMAIN TO BE CAPPED AND TEMINATED 5 FEET OUTSIDE THE GROUNDWATER TREATMENT PLANT. INSTALL 4'x4'x4' GRANITE MARKER AT END OF FORCEMAIN. TOP 2" ABOVE GRADE TO DOCUMENTATION LOCATION.
8. 2" PVC POWER CONDUIT TO BE INSTALLED. WIRING TO BE INSTALLED BY OTHERS UNDER FUTURE CONTRACT. INSTALL NON-DEGRADABLE PULL STRINGS FOR FUTURE USE.

HORIZONTAL SCALE: 1" = 40'
0 20 40 80
SCALE IN FEET

VERTICAL SCALE: 1" = 5'
0 2.5 5 10
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
Date 8/18/15

| NO. | DATE | REVISION | DR | CHK | APVD |
|---|---|---|---|---|---|
| 4 | 08/14/15 | DCB 007.4 | RJR | TDD | SGS |
| 3 | 02/13/15 | DCB 007.3 | TDD | SGS | SGS |
| 2 | 05/16/14 | REVISED GROUNDWATER EXTRACTION PUMP STATION | RJR | SGS | |
| 1 | 05/14/14 | DCB 007 | TDD | SHM | |
| DSGN | | | TDD | BY | APVD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION FORCE MAIN PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28019900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-204 |
| SHEET | OF 66 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE AND PATENTED FEATURES, AND/OR COPYRIGHTABLE INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




PLAN





SECTION AA





SECTION BB

DROP STRUCTURE DETAIL (AZ)
NTS STA 63+78 C-204 C-306





NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL (AE)
NTS C-201 C-202 C-203 C-306




EXISTING 3" FM TRENCH DETAIL (CK)
NTS STA 63+78 TO STA 68+91 C-204 C-306




TRENCH DETAIL (CL)
NTS C-204 C-306

NOTES:
1. REFER TO GENERAL NOTES SHEET G-003 AND C-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| | | | | | SHM | SHM |
| | | | | | APVD | TDD |
| | | | | | REO | SGS |
| | | | | | | SGS |
| | | | RJR | RJR | | RJR |
| 2 | 08/14/15 | REO | | | | |
| 1 | 02/13/15 | | | | | |
| 0 | 06/07/13 | | | | | |

ISSUED FOR CONSTRUCTION
DCB 007.3
DCB 007.4
REVISION

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 587-2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-306 |
| SHEET | 42 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




GROUNDWATER EXTRACTION PUMP STATION STA.=19+74± (CC)

NTS

C-203 | C-204 | C-310

- SET MANHOLE BASE AND RISER SECTIONS. (NITC)
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- DESIGN GRADE TO MATCH AVAILABLE RISERS REVIEW WITH ENGINEER PRIOR TO INSTALLING RISERS AND PERMANENT COVER.

NOTE:

INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.

## PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36' X 50" VALVE VAULT HATCH | 2 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I*2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, AND HOLD OPEN ARM |
| FLEX COUPLING | 2 | ETHYLENE, LLC OR APPROVED EQUAL | FLEXIJOINT COUPLING MIN. (2) BELLOWS, TEFLON-LINED W/ 316 SS FLANGES, POWER BAKED EPOXY COATING, AND VITON GASKETS |

SAMUEL G. SHALLARD

NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| | | | TDD | RJR | TDD | SGS |
| 1 | 06/06/14 | DCB 007 | TDD | RJR | APVD | SGS |
| 2 | 02/02/15 | DCB 007.3 | TDD | RJR | TDD | SGS |
| 3 | 08/14/15 | DCB 007.4 | TDD | RJR | TDD | SGS |

DSGN TDD

Honeywell
101 COLUMBIA RD BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
GROUNDWATER EXTRACTION TRENCH DETAILS


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
609-890-2333
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

DATE
PROJ 3480-12-0317
DWG C-310
SHEET OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR46-C-310_Cont_GWE_Trench_Details.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:19 AM




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE RIGID GALVANIZED STEEL (RGS) UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIERD.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| EH | ELECTRIC HANDHOLE |
| EW | EXTRACTION WELL |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| TSP | TWISTED SHIELDED PAIR |
| TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| V | VOLTAGE |
| W | WIRE |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 08/14/15 | TDD | RJR | SHM | SGS |
| 0 | 06/07/13 | TDD | RJR | SHM | SGS |

REVISION BY

ISSUED FOR CONSTRUCTION

DCB 007.4

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 890-2020
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-301 |
| SHEET | 64 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION, AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




## EXTRACTION WELL PUMP CONTROL PANEL DETAIL — AO

NTS — TYP E-302


NOTES:

1. ALL CONDUITS SHALL BE 1" RGS MINIMUM, UNLESS OTHERWISE SHOWN. WHEN DISTANCE IS LESS THAN 6 FEET, LIQUID TIGHT METAL FLEXIBLE CONDUIT MAY BE USED.
2. LOCATE THE PUMP MOTOR STARTER WITHIN 3' OF THE EXTRACTION WELL PUMP STATION.

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.


NOT PART OF THIS CONTRACT
ELECTRICAL POWER AND INSTRUMENTATION CONTROLS TO BE RE-EVALUATED FOLLOWING INITIAL DRAWDOWN AND TRENCH PERFORMANCE EVALUATION.




## PUMP CONTROL PANEL WIRING DIAGRAM — AP

NTS — TYP E-302

TYPICAL FOR ONE LEVEL TRANSDUCER AND ONE EXTRACTION WELL PUMP CONTROL (SEE NOTE 3)





## INVERTER DRIVE WIRING DIAGRAM — AQ

NTS — TYP E-302

FIELD TERMINAL STRIP CONNECTION SUMMARY

| | |
|---|---|
| GND | EARTH GROUND |
| 10 | RED TRANSDUCER WIRE |
| 11 | BLUE TRANSDUCER WIRE |
| 22 | MALE QD RECEPTACLE BROWN AND BLACK |
| 26 | MALE QD RECEPTACLE BLUE |
| 27 | MALE QD RECEPTACLE WHITE |
| 32 | FAULT CONTACT SUPPLY |
| 33 | FAULT CONTACT RETURN |

FEMALE QUICK DISCONNECT PLUG




## PLUG & TERMINAL STRIP WIRING DIAGRAM — AR

NTS — TYP E-302

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 08/14/15 | RJR | SGS | | |
| 0 | 06/07/13 | TDD | TDD | RJR | SHM |

DCB 007.4
ISSUED FOR CONSTRUCTION
REVISION
BY APVD
SHM

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


WIRING DIAGRAMS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 585-2283
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.





DUCT WAY NOTES:

1. CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS, OR AS SPECIFIED.
2. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAY #4@12" OC MIN 2. EXTEND 4' BEYOND ROAD EDGE.
3. MINIMUM COVER TO TOP OF CONCRETE ENVELOPE SHALL BE 24" [610mm].
4. INSTALL IN A 4'-0" MAX WIDTH TRENCH SIMILAR TO DETAIL Z ON C-306.


DUCT BANK DETAILS — AT
NTS — TYP | E-303




ELECTRICAL HANDHOLE DETAIL — AW
NTS — C-201, C-202, C-203 | E-303




PIEZOMETER CONDUIT DETAIL — CM
NTS — TYP | E-303




NOTES:

1. MAINTAIN SEPARATION OF POWER AND INSTRUMENTATION CONDUCTORS IN ELECTRIC HANDHOLE.
2. WHERE POWER AND INSTRUMENTATION CONDUCTORS CROSS THEY SHALL CROSS PERPENDICULAR TO EACH OTHER.
3. ELECTRICAL HAND HOLES SHALL BE LOCATED TO AVOID CLEANOUT MANHOLES.

ELECTRICAL HANDHOLE ORIENTATION DETAIL — AY
NTS — C-201, C-202, C-203 | E-303

NOTES:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| DSGN | TDD | | RJR | SGS | SGS | APVD |
| 1 | 08/14/15 | DCB 007.4 | | | | RJR SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS:
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

ELECTRICAL DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA27015500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-303 |
| SHEET | 66 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR66-E-303 Electrical Details.dwg PLOT DATE: Fri, 14 Aug 2015 PLOT TIME: 9:41 AM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 051 **DCB Type:** Minor (a)<br>**Effective Date:** 10/22/15 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** Move western Limit of Stratum D Repair | ☑ Yes, RFI Nos. ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** Pre-trenching on the vinyl sheetpile alignment revealed a significant number of old timber piles along the vinyl sheetpile alignment. The location with the most significant conflicts was along the western edge of the proposed repair. Removal of the piles would create openings in the Stratum D.


In lieu of removing sheetpile the western side was relocated approximately 6 ft. further west. The flexibility of the sheets was used to avoid piles at other locations. This will result in an expansion of the repair plan area from approximately 14,000 SF to, approximately 14,500 SF.

This change has no impact of the functionality of the chromium remedy or on the future site development.


Drawing SN-302 has been amended to indicate the installed location of the vinyl sheetpile wall and the timber piles that were identified and left in place.

| | |
|---|---|
| Reason for Change/Modification:<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Drawing SN-302 (Rev 01) |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 11/18/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |


(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




SAND BENTONITE KEY DETAIL





GCL CONNECTION TO HYDRAULIC BARRIER




OPEN EXCAVATION GCL BARRIER
WALL OPTION

SECTION 1+57
ALONG HYDRAULIC BARRIER
VIEW LOOKING SOUTH




OPEN EXCAVATION OPTION

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.

SEQUENCE OF CONSTRUCTION

1. INSTALL HYDRAULIC BARRIER WALL.
2. EXCAVATE TO APRROXIMATELY ELEVATION 4 (APPROXIMATELY 1 FOOT OVER THE GROUNDWATER LEVEL).
3. INSTALL A SEALED VINLY SHEETPILE WALL AROUND THE PERIMETER OF THE REPAIR.
4. INSTALL A BENTONITE SAND CONNECTION DETAIL IN ACCORDANCE WITH DETAIL B1.
5. PLACE GCL LAYER OVER THE AREA OF THE REPAIR.
6. BACKFILL TO GRADE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 1 | 11/16/15 | TDD | RJR | TDD | SGS | TDD | SGS |
| 0 | 06/07/13 | REVISION / ISSUED FOR CONSTRUCTION | | | | | |

DCB 051 MOVE SHEETPILE TO AVOID TIMBER PILES

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

STRATUM D REPAIR
JCIA TRASH PIT AREA

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619 (609) 890-2329
NJ Cert of Authorization 24GA28010300

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-302 |
| SHEET | 61 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR61-SN-302 JCIA Pit Stratum D Restoration.dwg PLOT DATE: Mon, 16 Nov 2015 PLOT TIME: 12:20 PM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 057 **DCB Type:** Minor (a)<br>**Effective Date:** 03/21/16 |
| **Project Location:** SA-6<br>**Title:** Planting Soil Specifications (Nature's Choice - Horizon C ONLY) | **Associated RFI:**<br>☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |
| **Description.** Revisions to the Horizon C planting soil specifications for the Nature's Choice Horizon C Soil Source Only. | |
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See additional comments<br><br>**Attachments:** ☑ Yes ☐ No<br>Laboratory reports of chemical analysis<br><br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Nature's Choice was identified as the source that best met the physical requirements for Horizon C soils by Dr. Grabosky; however, several samples of Nature's Choice Horizon C soils have hexavalent chromium concentration >1.0 mg/kg. Consequently, Honeywell is proposing a design change to allow the hexavalent chromium concentration in Nature's Choice Horizon C soils to be less than 1.8 mg/kg, as agreed to by the Parties. For future sampling, hexavalent chromium soil samples will be composited from 10 grab sample locations per 5,000 CY (maximum). There are additional conditions in Attachment A that are part of this DCB and specific to Nature's Choice Horizon C soil. All other requirements specified in the 100% Design for imported soils will be met by the Nature's Choice Horizon C soils as amended in previous DCB 046. | **Design Documents Affected:**<br>Specification 02315, Section 2.12.C<br>Open Space Design Standards, Section 2.1.2 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 4/26/2016 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# Attachment A – Supplemental Requirements for DCB 057

During the March 17 teleconference, Honeywell explained that the proposed material would come from an excavation pit (with concentration characteristics similar to those from which data was previously collected). Based on the information provided by Honeywell, plaintiffs will accept Honeywell's proposal to use the Nature's Choice material as Horizon C soils at Study Areas 6 North and South so long as Honeywell agrees to the following conditions:

1. Plaintiffs' agreement to use soils in excess of the 100% Design 1 ppm hexavalent chromium standard is limited to the Nature's Choice materials in question for use as Horizon C soils and is not a modification of the 100% Design standards as they apply to any future fill, repair or restoration work. This limited deviation from the 100% Design is set forth in this Design Change Bulletin.

2. The Nature's Choice materials shall contain less than 1.8 mg/kg hexavalent chromium. In addition, Honeywell shall use best efforts to maintain an average hexavalent chromium concentration as estimated based on the upper limit of the 95$^{th}$ percentile confidence interval around the mean of 1.1 mg/kg in the Horizon C soils.

3. The Nature's Choice materials shall be sampled for hexavalent chromium no less frequently than once every 5,000 cubic yards. Hexavalent chromium sampling shall use composite samples that are made up of a minimum of 10 grab samples. The grab samples shall be collected as evenly as possible throughout the volume of material being sampled to ensure true representation of the hexavalent chromium concentrations coming onto the Study Area 6 sites.

4. All other sampling and analysis protocols will follow the customarily used NJDEP and USEPA protocols. To be consistent with the NJDEP protocols, one of the individual 10 grab samples will be used for all other required analytical parameters (VOCs, SVOCs, metals, etc.) to demonstrate compliance with clean fill requirements.

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 059 **DCB Type:** Minor (a)<br>**Effective Date:** 4/20/16 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Planting Soil Specifications | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description**. Planting Soil Source Acceptance Variance for Select Horizon B and C Soils.

DCB-046 expanded the ranges of acceptable physical parameters (gradations, pH and organic content) in Horizon B and C soils that were included in the Earthwork Specification 02315. DCB-046 was accepted by all Parties and Specification 02315 was revised accordingly.

Subsequent to the acceptance of DCB-046, Entact encountered difficulty locating available Horizon B and C sources that comply with the revised Specification and meet hexavalent chromium design criteria of 1 mg/kg or less.

This DCB-059 was developed to document an agreement reached by all parties on the Special Master All-Hands monthly call on April 19, 2016. Based on the agreement, Honeywell will proceed to import fill material from suppliers as noted below to support the project needs for Horizon B and Horizon C soils to meet the demands for fill quantity and schedule for cover soils on SA-6 South and North.

It is noted that an exhaustive search of potential sources resulted in a short list of potentially viable Horizon B and C sources being recommended, following consultation with Dr. Grabosky who provided his recommendations in correspondence dated March 17, 2016. Dr. Grabosky's recommendation is attached and made part of this DCB. The specific sub set of soil sources agreed to by all parties is as follows:

| Horizon B Approved Sources | Horizon C Approved Sources |
|---|---|
| Cedar Hill | Natures Choice (Per DCB-057) |
| EME - B001 | Impact - AB33 |
| Impact - AD17 | Impact - AD25 |

**DCB-059 applies to the completion of importing soils for SA-6 North and South grades as presented in the 100% design and does not permanently change the Earthwork Specification 02315 for physical parameters (gradations, pH and organic content) in Horizon B and C soils that were memorialized in DCB-046.**

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>**Attachments:** ☑ Yes ☐ No<br>Dr. Jason Grabosky letter (3/17/16)<br>Plaintiffs' letter dated 04/15/16.<br>Cost Implication: ☐ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☐ No |
| **Additional Comments:** See DCB-057 for acceptability conditions of Nature's Choice Horizon C soils. | **Design Documents Affected:**<br>Specification 02315, Section 2.12 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 4/26/2016 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# DR. JASON GRABOSKY RECOMMENDATION

RUTGERS
School of Environmental and Biological Sciences

Urban and Community Forestry Program
Dept. of Ecology Evolutionand Natural Resources
Environmental and Natural Resources Bld, Room 144
Rutgers, The State University of New Jersey
14 College Farm Road
New Brunswick, NJ 08901-8551

March 17, 2016

To all concerned:

I spoke on the phone with Geoff in between meetings during the past week. For all concerned, there was a delay in this set of conversations due to some snags in our e-mail communications (I was not getting e-mails through my server for some reason), but we developed some work arounds to share the soils tables under review and spoke during a brief conversation on Tuesday Morning from 8:00-8:15 a.m. once I had the soils tables in front of me while chatting over the phone.

There are issues with the Nature's choice source, in terms of supply and in terms of some testing results. For that reason, it has been necessary to identify alternative Horizon B and Horizon C sources. To reduce risks in material supply, chemistry and gradation, I have identified multiple sources/mixes for both Horizon B and Horizon C. In making specific recommendations I also considered both the expense of shipping, and the environmental cost (or the carbon footprint) in shipping, and the limitations in time management from the haulage/transportation logistics.

**Horizon B:**
In a technical sense, Nature's choice remains an approved and acceptable layer B material. However, there is an open question of availability of material in the volume needed for project execution.

The Cedar Hill material can fit the B Layer source designation. Clay is at 10% right at the lower end of the clay specification. As discussed with Geoff Shallard, in an engineering/drainage view, this is a good material. We would also have to consider a lower the min clay value in the specification to account for variability. The pH of this material (6.22) seems to be in line with the goals for the specification. Given a concession in lowering the clay content also opens consideration of the Impact Materials.

Impact AD17 : While the fines (silts and clays) are flipped from a best case scenario (and thus falling out of specification), the material would suit for the B horizon. In the clay component, this material is comparable to the Cedar Hill material. The silts exceed the specified maximum percentage. However, this maximum is largely in consideration of frost heave susceptibility. For the depths of the B layer relative to expected frost penetration to depth in Jersey City, especially in consideration of all future climate predictions of warmer temperatures, the frost potential is deemed less critical. Indeed, the pH is a tad high, but not so much as to consider it unworkable from a horticulture management sense. The sand portion of the Impact AD17 blend (which is the bulk of the blend) sits 10 minutes away from the site in Kearny, NJ and therefore has a low carbon footprint and ease of logistics. Additionally, it may yield a continuum in similarity if the C horizon also is determined to come from an Impact source.

EME B001-HORB: The EME grouping of materials benefit from a high level of control, and would be considered a useful source ***if*** the material could lower the organics to <4. Given the systems in question,

there is every possibility of shrinkage over time as the OM degrades, which could have negative impacts on the final developed site. A principal detraction of this source would be distance (about 65 miles), both in expense in shipping, the environmental cost (or carbon footprint if you will) in shipping from and the limitations in time management from the haulage/transportation logistics.

**Horizon C**

Impact AB33 and Impact AD25: While the fines (silts and clays) are flipped from a best case scenario (and thus falling out of specification), the materials would suit for the C horizon. pH is in line with the specification. I have a preference for the AB33 for the lower pH and slight increase in clay, but both would be suitable. Of the materials in the tables, a discussion with Geoff indicated the sands in the Impact materials are coarse and to our benefit in workability and drainage capacity, which for the level of construction traffic on site, works toward the stability of the system in a physical-mechanical sense. The sand portion which is the bulk of the Impact blends also is located in Kearny, NJ and therefore has a low carbon footprint and ease of logistics.

EME B002-HORC: The EME grouping of materials benefit from a high level of control, and would be considered a useful source ***if*** the material could lower the organics to <4. Given the systems in question, there is every possibility of shrinkage over time as the OM degrades, which could have negative impacts on the final developed site. A principal detraction of this source would be distance (about 65 miles), both in expense in shipping, the environmental cost (or carbon footprint if you will) in shipping from and the limitations in time management from the haulage/transportation logistics.

**Recommendations:**
I would retain EME as a Vendor option for both Horizon B and Horizon C with an assumption the organic fractions can be reduced. While the materials seem very good, the costs likely outweigh the advantages for the B and C horizons. The vast majority of the plant root systems are in the A horizon, thus the goals for the lower levels are about support, drainage and depth/distance to cap. Given the timing and the difficulty associated with getting materials into conformance I make the following recommendations. Pragmatically, one might argue I am siding on convenience. However, upon the consideration of developing a system, I feel what we develop from the recommendations provides a working solution, albeit with a higher system pH than originally targeted. The plant palette was chosen to bias toward shallower rooting species, and the higher ph will encourage the proliferation of roots where the mineral nutrition is available, which biases toward the surface with the increased pH of the lower layers. We provide a loamy-sand to sandy loam transition in the b to c horizon depths, which would provide a continuum for the water column through the layers provided compaction of each layer is not excessive and the interface blending described in the early documentation occurs. The increase of pH does not place the plant species selected into peril to my knowledge.

I would recommend:

Horizon B soils:

Adopt Impact AD17% as the primary source, and Cedar Hill as the secondary source. To accomplish this in specification language, adjust the B layer % Silt to <15% and % Clay to 5-15%. Raise acceptable pH to 7.6 from 7.5 or figure out how to lower the AD17 pH in the mix process.

RUTGERS
School of Environmental and Biological Sciences

Horizon C soils:

Adopt Impact AB33% as the primary source. To accomplish this in specification language, adjust the C layer % Silt to <15% and % Clay to 5-15%. Retain the Impact AD25 as an alternative to Impact AB33%.

Respectfully submitted,



Jason Grabosky
John and Eleanor Kuser Faculty Scholar in Urban and Community Forestry
Director: S.E.B.S. General Honors Program
Co-Director: Center for Resilient Landscapes, a USDA FS/Rutgers Joint Venture
Editor-in-Chief; Arboriculture & Urban Forestry
Department of Ecology, Evolution and Natural Resources

**PLAINTIFFS' RESPONSE LESTTER (4/15/16)**

BRUCE J. TERRIS
CAROLYN SMITH PRAVLIK
KATHLEEN L. MILLIAN
ALICIA C. ALCORN
ZENIA SANCHEZ FUENTES
PATRICK A. SHELDON
TODD A. GLUCKMAN

**TERRIS, PRAVLIK & MILLIAN, LLP**
1121 12TH STREET, N.W.
WASHINGTON, D.C. 20005-4632
(202) 682-2100
FAX 202-289-6795
tpminfo@tpmlaw.com

MICHAEL L. HUANG
NICHOLAS SOARES
BENJAMIN S. DAVIS
STEPHANIE ANN MADISON

LYNN E. CUNNINGHAM
Of Counsel

April 15, 2016

VIA ELECTRONIC MAIL

Jeremy Karpatkin
Arnold & Porter, LLP
Thurman Arnold Building
555 12th Street, N.W.
Washington, DC 20004-1206

Re: Study Areas 6 North and South – DCB 2016-3-18 Horizon B and C Soil Specifications

Dear Jeremy:

We write to provide plaintiffs' position with respect to the Design Change Bulletin (DCB) DCB 2016-03-18 that seeks to modify the geotechnical specifications for Horizon B and C soils, which the parties previously modified in September 2015. We note that, like the September 2015 modification, the current proposal of Honeywell would apply to all Horizon B and C soils to be brought to the site, not just in the initial phases of development, but permanently. As set forth in the 100% Design and the Open Space Design Standards (OSDS), there is to be a distinction between the characteristics of the soils in Horizon B and Horizon C to ensure the growth of only appropriate types of vegetation and trees on top of the cap, so as not to endanger the cap. *See* Technical Specification 2315 Earthwork, 2.12 Planting Soils; OSDS 2.1.2 Restrictions on the Use and Placement of Fill, Subsection D Specific Requirements for Fill Soils in Landscaped Areas.

On April 7, 2016, plaintiffs requested additional information regarding the planned schedule for the importation and use of the Horizon B soils. Honeywell provided the requested information on April 12, 2016. Plaintiffs and their experts have reviewed the April 12 response. Plaintiffs agree with Honeywell's analysis that Horizon B soils may be imported and placed now in the Study Area 6 South Open Space, and that Horizon B soils cannot be placed in the Study Area 6 North Open Space until the redevelopment.

Plaintiffs understand that Honeywell wishes to have multiple sources of Horizon B and C soils available for use so that it will not incur delays such as those incurred this winter with respect to Horizon C soils. However, Honeywell is proposing to change permanently the geotechnical specifications for both Horizon B and C soils based on the analysis by Dr. Grabosky of particular sources for the Horizon B and C soils. Dr. Grabosky's analysis establishes that the particular soil sources that he recommends, based upon the potential sources

provided to him by Honeywell, will maintain the necessary distinction between the soil horizons even though the recommended sources may deviate slightly from the geotechnical specifications as modified in September 2015.

Based upon the recommendations of Dr. Grabosky as set forth in his correspondence of March 17, 2016, which was included with DCB 2016-03-18, as set forth below, plaintiffs will agree to the use at Study Area 6 of certain particular sources for Horizon B and C soils addressed by Dr. Grabosky, even though some of the sources may deviate slightly from the geotechnical specifications in the 100% Design for Horizon B and C soils. However, plaintiffs are not willing to agree to modify permanently the geotechnical specifications for the Horizon B and C soils of the 100% Design standards to accommodate use of the sources for Horizon B and C soils under consideration by Honeywell at this time.

Plaintiffs agree to the use of Horizon B soils for the Study Area 6 North and South Open Space areas from Nature's Choice, Cedar Hill, and EME (EME-B001 blend) because these sources meet the geotechnical specifications. In addition, plaintiffs agree to the use of Horizon B soils from Impact Environmental, which deviate from the geotechnical specifications, as a secondary source should the Nature's Choice, Cedar Hill, and EME (EME-B001 blend) soils not be available. Plaintiffs do not agree to the use of the EME (Horizon "B" Modified) soils because of the high organic material content of the soils.

Plaintiffs agree to the use of Horizon C soils for the Study Areas 6 North and South Open Space areas from Nature's Choice as set forth in DCB 2016-03-21. In addition, plaintiffs agree to the use of Horizon C soils from Impact Environmental (Impact AB33 and Impact AD25), which deviate from the geotechnical specifications, as secondary sources should Nature's Choice not be available. Plaintiffs do not agree to the use of the Horizon C soils from EME because Dr. Grabosky did not recommend the use of these sources and because of the high organic material content of those soils.

Plaintiffs' agreement to the use of certain Horizon B and C sources that deviate from the geotechnical standards, as set forth above, is not an agreement to modify the 100% Design standards as they apply to any future fill, repair, or restoration work. This more limited agreement to deviate from the 100% Design should be set forth in a modified Design Change Bulletin.

Please contact me with any questions. We look forward to your response.

Sincerely,



Bruce J. Terris
Kathleen L. Millian
Alicia C. Alcorn
*Counsel for Plaintiffs*

cc: Senator Robert Torricelli
Tom Lewis/Steve Egnaczyk
Michael Daneker
William Hague
John Morris
Kevin Coakley/Liza Walsh/Agnes Antonian
Jeremy Farrell/Jason Watson/Bhavini Doshi
Frank Borin/Kevin Kinsella
Davis Isabel/ Eric Tomaszewski

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 058 **DCB Type:** Minor (a)<br>**Effective Date:** 5/6/16 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Temporary Construction Road in SA-6 South Cap | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

To allow for traffic flow within the project site following completion of the SA-6S Cap, a road will be installed within the "B Street" corridor.

The Chromium Remedy Design indicates that the Open Space AOC will be finished with topsoil and be seeded. Section 2.2.1.B of the Open Space Design Standards ("OSDS," Appendix L of the SA-6 North 100% Design Report) was written in anticipation of the need for "temporary construction roads" across the cap, post Chromium Remedy completion, and prior to construction of the final redevelopment roads. These construction road(s) will initially be used to provide access for general site inspections, access for the long term monitoring plan and maintenance activities such as mowing.

The roads will be constructed by continuing the "Structural Fill under Roadways to within 6 inches of final grade". The Topsoil shown within the construction road limits would be replaced with a load bearing geotextile (min 8 oz. non-woven) and 6 inches of Dense Grade Aggregate consistent with the OSDS "temporary construction road" requirements.

Table I of the OSDS was developed to show the minimum cover requirements for specific traffic loading conditions. The analysis supporting Table 1 was shared with the Plaintiffs during development of the OSDS. These communications were documented in Response to Plaintiff's Comments dated 07/13/2012. The calculation provided indicates that a 36 inch cover was adequate to provide protection of the cap when subject to H20 truck loading. When graded to the Chromium Remedy grades the typical fill depth in "B Street" is 8 ft. (OSDS Figure 4I is attached for reference). At the northern end of B Street, as the remedy surface transitions into SA-7, the minimum depth is 4 ft. These conditions meet the 36 inch cover requirement stated in Table 1.


The road as constructed during the Chromium Remedy will therefore meet Section 2.2.1.B of the OSDS.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>**Attachments:** ☑ Yes ☐ No<br>Table 1 (Page 20 of OSDS); Section 2.2.1.B of OSDS (pages 24 – 25); Figure 4I<br>Cost Implication: ☐ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☐ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 6/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

NOTE:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND
3. EXISTING ASPHALTIC PAVEMENT AREAS TO BE FIELD INSPECTED BY LSRP DURING RESTORATION ACTIVITIES. FINAL HISTORIC FILL CAP IN THESE AREAS MAY INCLUDE CRACK FILLING OR INSTALLING A GRAVEL COVER SYSTEM.




| | |
|---|---|
| SHEET | 33 OF |
| DWG | C-128 |
| PROJ | 3480-12-0317 |
| DATE | |

BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"

VERIFY SCALE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization 24GA28010900


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

RESTORATION PLAN

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 4 | 6/20/16 | DCB 30.2 - ROAD B ACCESS GRADING | TDD | SGS |
| 3 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 2 | 05/06/15 | REVISED EDGE DETAIL | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |


| DSGN | DR | CHK | APVD |
|---|---|---|---|
| TDD | RJR | TDD | SHM |


SAMUEL G. SHALLARD
6/21/16
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.





FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\CR33-C-128 Surface Restoration Plan.dwg PLOT DATE: Mon, 20 Jun 2016 PLOT TIME: 2:15 PM




CONSTRUCTION ACCESS ROAD DETAIL
NTS
(TOP PLATEAU)




CONSTRUCTION ACCESS ROAD DETAIL
NTS
(APPROACH SLOPE)

0 10 20 40
HORIZONTAL SCALE FEET

0 4 8
VERTICAL SCALE FEET

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Cap Grading\C-128A Cap Access Road.dwg PLOT DATE: Mon, 25 Jul 2016 PLOT TIME: 12:26 PM

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | DR | CHK | APVD | BY |
|---|---|---|---|---|---|---|
| 0 | 7/25/16 | 30-65 temp Const Road Details | TDD | SGS | SGS | TDD |
| DSGN | TDD | | TDD | | | |

Honeywell
101 COLUMBIA RD. BOX 2245, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134,
140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

CONSTRUCTION ACCESS ROAD
FUTURE B STREET

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, N.J. 08619
(609) 689 - 2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON
ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-128A |
| SHEET | 33A OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

**Table 1: Allowable Ground Pressure versus Fill Depth**

| Maximum Ground Pressure | Fill Depth Over Warning Layer/Liner |
|---|---|
| **Maximum Ground Pressure for Maintenance Equipment** | |
| < 5 psi | 12 inches |
| 5-10 psi | 18 inches |
| >10-40 psi | 24 inches |
| | |
| **Additional Maximum Ground Pressure for Temporary Roads** | |
| Fully Loaded Highway Truck (>40-80 psi) | 36 inches |
| | |
| **Permanent Roadways** | |
| No maximum ground pressure limit | 36 inches |

The load limits on temporary roads and on Landscape and Hardscape Areas allow for heavier loads where a rigid pavement or temporary load spreading system such as matts is used to spread the load and reduce the bearing pressures to below the limits specified in Table 1, and where a licensed New Jersey Professional Engineer has certified to Honeywell and Jersey City that the rigid pavement or temporary load spreading system will reduce the bearing pressures to below the limits specified in Table 1.

## E. Bearing Area – Foundations, Footers and Separation from Cap

1. Each point load from a Permissible Development Element shall have a minimum bearing area of 2 square feet except that traffic light poles and street light poles shall have a minimum bearing area of 3.5 square feet.
2. Each Permissible Development Element requiring a footer shall have a shallow footer.
3. Anchoring systems for Permissible Development Elements such as site furnishings shall be designed for surface mounting on spread footings. Hardscape areas shall accommodate surface mounted anchoring on spread footings.

Remedy and such certification will be included in a Development Plan reviewed and approved by the Special Master or the Federal Court. No curb and pavement box design shall be certified or approved unless it is demonstrated that it will not jeopardize the integrity of the Chromium Remedy.

8. Through trucks are prohibited on Roadways. Roadways shall be posted to prohibit through trucks. Jersey City shall prohibit through trucks and require the posting of such prohibition in an ordinance prior to the installation of the Roadways. The standard becomes effective upon the effective date of a Jersey City ordinance prohibiting through trucks on Roadways.

9. Every five years from the initial surfacing, a licensed New Jersey Professional Engineer shall inspect all Roadways in the Open Space Areas to evaluate whether the condition of any Roadway or segment thereof has compromised or is likely to compromise the structural integrity of the underlying subgrade or utilities. Within 30 days of the completion of the inspection, the licensed New Jersey Professional Engineer shall submit a certified report to Honeywell and Jersey City that describes the inspection undertaken and the repairs needed, if any, in order to address any condition that has compromised or is likely to compromise the structural integrity of the underlying subgrade or utilities. Within 18 months of the submission of the report, the repairs described in the report shall be completed. In the event that in the report the licensed New Jersey Professional Engineer deems a condition to constitute an emergency requiring immediate repair, such repair shall be made as soon as possible, and, if necessary, interim measures shall be employed to protect the cap, subgrade and utilities. Within 60 days of completion of the repairs, emergency or otherwise, a licensed New Jersey Professional Engineer shall inspect the repairs and certify that the repairs have been satisfactorily completed.

**B. Temporary Construction Roads**. The following requirements apply to all temporary construction roads:

1. In the event temporary construction roads are installed, these roads shall be limited to the locations designated for Roadways in the 100% Design on Drawings CN-515 and C-516. Temporary roads shall be installed using a load bearing geotextile fabric to isolate the wearing surface from the

subgrade. A wearing surface shall be installed that is sufficient to handle the intended temporary traffic loadings. Temporary roads shall be designed consistent with the projected loads and frequency. Temporary roads shall be designed to be protective of the Chromium Remedy. A licensed New Jersey Professional Engineer shall certify that the temporary road design is protective of the Chromium Remedy and such certification shall be included in a Development Plan reviewed and approved by the Special Master or the Federal Court. No temporary road design shall be certified or approved unless it is demonstrated that it will not jeopardize the integrity of the Chromium Remedy.

2. The load limitations specificed in Section 2.1.4.D of the OSDS and Section 02374 Part 3.3 G 7 of the Technical Specifications shall apply to all loads on the temporary roadways.

### *2.2.2 Hardscape Areas including Pedestrian Thoroughfare*

Hardscape Areas shall have a minimum separation of 12 inches between the Warning Layer/Liner and the underside of the hard surfacing. The surface and subgrade materials shall be of sufficient strength to accommodate Maintenance Equipment.

### *2.2.3 Utilities*

All utilities including those supporting the pump and treat system for groundwater remediation, with the exception of any extraction wells or collection trenches, shall be placed above the Cap as required in Paragraph 56(b) of the Study Area 6 North Consent Decree.

### *2.2.4 Utility Corridors*

**A. Public Utilities.** All public utilities shall be located in a designated utility corridor and shall be installed in accordance with Paragraphs 60(j)(v)(6) and (7) of the Study Area 6 North Consent Decree. The location of the utility corridors is shown on Drawing CN-515 of the Study Area 6 North 100% Design and C-516 of the Study Area 6 South 100% Design. During the Initial Development Period, the modification of designated utility corridors or the designation of additional utility corridors, if necessary shall be subject to the review and approval of Honeywell, Jersey City, and the Special Master.

MATCH LINE VIEW BELOW

GRAND BLVD.

C STREET

D STREET

SA-7 SLURRY WALL

FRONTAGE

STREET

HYDRAULIC BARRIER

GRAND BLVD.

SA-7 SLURRY WALL

RIVERSIDE DRIVE

A STREET

B STREET

GRAND BLVD.

HYDRAULIC BARRIER

MATCH LINE VIEW ABOVE

| Depth to Liner Table | | |
|---|---|---|
| Minimum Depth | Maximum Depth | Color |
| 2.0 | 2.5 | |
| 2.5 | 3.0 | |
| 3.0 | 4.0 | |
| 4.0 | 4.5 | |
| 4.5 | 14.6 | |

LEGEND

- HARD SCAPE
- SIDEWALK
- MAJOR TREES
- MIONOR TREES
- SA-7 SLURRY WALL
- HYDRAULIC BARRIER

Prepared/Date: RJR 06/09/13
Checked/Date: SGS 06/09/13

0 20 40 80
SCALE IN FEET

Honeywell
101 COLUMBIA RD. BOX 2105
MORRISTOWN, NJ 07962

OPEN SPACE DESIGN STANDARDS
CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec

PROMENADE
LANDSCAPING AND SOIL SPOT
DEPTHS TO WARNING LAYER/LINER
Figure 4I

Z:\Projects\HONEYWELL\JERSEY CITY\Dwg Design-SA6-CSD\DAP\DAP5\Figure 4I Landscaping Depths.dwg Thu, 06 Jun 2013 - 2:49pm roger.fiedler

DESIGN CHANGE BULLETIN


| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 61 **Type:** Minor(a)<br>**Effective Date:** 11/9/16 |
| **Project Location:** SA-6N | **Associated RFI:** |
| **Title:** Site Restoration | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** The limits and the type of restoration north of the SA-6N cap has been modified to be integrated with the SA-6N Non Chrome Remedy. This DCB information confirms direction provided to Entact following discussions with JCMUA and the SA-6N Non Chrome Remedy Contractor (OSC). A modified Restoration Drawing CN-127 is attached. The drawing includes the changes in scope that have occurred subsequent to the "IFC" drawings. The following items are specifically noted:

- EA-7 and EA-8: Final Grading of these areas and placement of Historic Fill Cover will be conducted as part of the Non Chrome remedy along the Hackensack River.
- The former JCIA property that has become part of the JCMUA owned Lot 6 will receive a geotextile demarcation layer and 6 inches of crushed stone cover over the historic fill. A survey control grid similar to that used on the SA-6S Development Area will be set out and submitted to AmecFW for approval. The grid will be used to document that the thickness requirements have been met. A survey grid matrix documenting the elevations and depth at each grid point will be provided along with a topographic survey of the surface of the restored area.
- Historic Fill stockpiles west of the former JCMUA digesters will be processed by others.
- The footprint of the Chromium Remedy Construction Water Treatment plant will be finished with crushed stone over an LLDPE demarcation layer.
- A temporary fence will be erected along the Lot 6 Boundary. JCMUA will install a new fence following their re-purposing of the former JCIA property in Lot 6.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>Changed limits of disturbance/interface with the Non Chrome scope and changes in Property Lines |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>CN-127 |
| **Honeywell (AP) Review:** | |
| **Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 12/28/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTE:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.

0 40 80 160
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APV'D |
|---|---|---|---|---|
| 2 | 12/10/16 | DCB 061 - REVISED RESTORATION LIMITS | TDD | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR | BY | APV'D |
| | TDD | RJR | TDD | SGS |

SAMUEL G SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507


Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

RESTORATION PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, New Jersey 08619
609.890.3500 Fax 609.890.3699
NJ Cert of Authorization 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-127 |
| SHEET | 32 OF 70 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** DCB 7.4.2 **Type:** Minor(a)<br>**Effective Date:** 12/20/2016 |
| **Project Location:** SA-6 North and South | **Associated RFI:** |
| **Title:** Contingent GW E&I Revisions | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** The Contingent GW system was modified from wells to trenches. This resulted in a reduction in from 9 pumps on the North, and 9 pumps on the South, to 2 pump stations on North, and 1 pump station on South. The electrical and instrumentation (E&I) requirements and associated conduit runs changed accordingly.

This DCB documents a number of minor field changes that have been conveyed by the EOR to Entact during the course of the work and also includes revisions to the (E series) electrical drawings for both SA-6N and SA-6S.

The IFC conduit runs were designed to allow for hard wiring of the piezometric pairs used to monitor the gradients. The piezometric instrumentation conduit run has been eliminated on SA-6S. The piezometric pairs will initially be monitored manually. Manual monitoring may be supplemented by use of data loggers (Solinst Levelogger or similar) in selected wells. Based on the technical advancement in data loggers subsequent to the IFC design, data collection options that do not require hard wiring are a viable and preferred. Wireless data loggers eliminate the risk of damage and associated subsurface repair in the future. As a result, conduit runs for the piezometers were deleted from SA-6S. Due to the progress of work and scheduling, a piezometer conduit was installed on SA-6N; however, wiring has not been installed and it is the engineer's recommendation that wireless installation be used.

Investigation of existing conduit runs at the west end of SA-7 indicated that one 2 inch conduit shown on the IFC design as existing was not present. A new conduit run was added in its place.


All pump stations, force-mains and E&I conduit runs except as noted above have been installed.

The reason for considering this a "Contingent" System is that modeling predictions indicate that **no pumping** will be required i.e. there is no technical design basis for determining a flow rate. In the absence of a theoretical or verified design flow the forcemains have been sized at 2 inches in diameter and the pumps and associated wiring to operate at 5 GPM. Larger pumps and wire sizes could be readily installed in the unlikely event they are required. As of the date of issue of this DCB, pumping has not been required. This covers a period of more than 12 months on SA-6S, and 4 months on SA-6N. To provide an allowance for pumping at some nominal flow rate, pumps and power have been sized assuming a steady 5 GPM flow rate. The pump and controls design is based on operation of only one pump station at a time. The 5 GPM is based on the capacity of the existing GWTP effluent pumps. The forcemain and pumps have been sized for greater capacity, and greater flows could be readily achieved, if the effluent pump capacity was increased. It is recommended that a final decision on pump sizes, and related wiring and instrumentation, be revisited if it is determined that pumping is required. The GWTP has been modified under separate contract with RSTI to

| **Reason for Change/Modification:** | **Explanation or Reason:** |
|---|---|
| ☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Attachments:** ☑ Yes ☐ No |
| 12/21/16 | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |

| | | | |
|---|---|---|---|
| **Additional Comments:** | | **Design Documents Affected:** E-301, E-302 and E-302A (SA-6S). EN-301, EN-302 and EN-302A (SA-6N) | |
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** 12/21/16 |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☐ **Yes (b)** ☑ **No** |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE SCH 40 PVC DB UNLESS NOTED OTHERWISE.
4. ALL CONDUITS WILL BE SUPPLIED AND INSTALLED AS PART OF SA-6 CHROMIUM REMEDY.
5. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
6. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE IF REQUIRED.
7. CONTRACTOR SHALL CONNECT THE 2-2" EXISTING CONDUITS @ THE JUNCTION EH NEAR EXISTING WELL 115-MW-215BR TO THE CONDUITS RUNNING PARALLEL TO THE 3" FM PIPE ON THE WEST SIDE OF SA-7 STA 63+78 TO 68+91.
8. PULL STRING/WIRE TO BE INSTALLED IN ALL E&I CONDUIT FOR WIRE INSTALLATION IN THE FUTURE BY OTHERS.
9. THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| DB | DIRECT BURIAL |
| EB | ENCASED BURIAL |
| EH | ELECTRIC HANDHOLE |
| FWE | FURNISHED WITH EQUIPMENT |
| FVNR | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| JB | JUNCTION BOX |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| MPCB | MOTOR PROTECTION CIRCUIT BREAKER |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| SPD | SURGE PROTECTIVE DEVICE |
| TSP | TWISTED SHIELDED PAIR |
| V | VOLTAGE |
| W | WIRE |

TIMOTHY C. KESSLER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03748500

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 3 | 12/02/16 | | | | | SGS | TCK |
| 2 | 05/20/16 | | | | | TDD | SGS |
| 1 | 08/14/15 | | | | | RJR | SGS |
| 0 | 06/07/13 | | | | | TDD | SHM |
| | | TDD | | RJR | SHM | SGS | APVD |

ISSUED FOR CONSTRUCTION
DCB 007.4
DCB 007.4.1
DCB 007.4.2

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010600


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-301 |
| SHEET | 64 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




6 SOUTH PUMP STATION CONTROL SCHEMATIC
NTS




5KVA 480V–120/240V
MINIMUM POWER ZONE

TYPICAL PUMP STATION ONE LINE
NTS

NOTE:

THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

□ TERMINAL IN PUMP PANEL

FIELD WIRING

TIMOTHY C. KESSLER, P.E.

NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 12/02/16 | DCB 007.4.2 | SGS | TCK | |
| 2 | 05/20/16 | DCB 007.4.1 | TDD | SGS | |
| 1 | 08/14/15 | DCB 007.4 | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |

TDD RJR SHM SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD., MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134,
140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


WIRING DIAGRAM


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302 |
| SHEET | 65 OF 66 |


FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\CR65-E-302 Wiring Diagram.dwg PLOT DATE: Mon, 05 Dec 2016 PLOT TIME: 6:14 AM




PUMP STATION CONTROL PANEL DETAIL
NTS





PUMP STATION CONTROL PANEL BACK DETAIL
NTS

## NOTE:

THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE–EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.


**BILL OF MATERIALS**


| ITEM | QTY | DESCRIPTION | MFG | PART NO. |
|---|---|---|---|---|
| 1 | 1 | 60" H x 52" W x 18" D 2-Door NEMA 3R Pad-Mount Enclosure with back panel | Hoffman or Equal | A60R5218FSLP & A49P48N |
| 2 | 1 | 4 inch cooling fan with bracket and thermostat, 120 Vac | Hoffman or Equal | A4AXFN, ABRKT4, & ATEMNO |
| 3 | 1 | 400 Watt heater with fan and thermostat, 120 Vac | Hoffman or Equal | DAH4001B |
| 4 | 4 | 175A Power Distribution Terminal Block, #2/0 to #14 AWG Wire Size Range, IP20 Finger-Safe | Bussmann or Equal | PDBFS220 |
| 5 | 2 | Square D H-Frame, 30A, 3P, 600V, Thermal-Magnetic Circuit Breaker and NEMA 1 Surface -Mount Enclosure | Square D or Equal | HDL36030 & J250S |
| 6 | 1 | Type 1 Surge Protective Device, 480V, 3 Phase Delta, 3-Wire + Ground with Transient Filter and Surge Counter | Joslyn or Equal | JSP240-3D480-FB |
| 7 | 1 | Square D Mini-Power Zone, 5kVA, 480V-240/120V, NEMA 3R Enclosure with Primary & Secondary Main Breakers | Square D or Equal | MPZ5S40F |
| 8 | 5 | Square D Type QO Plug-On Circuit Breaker, 15A, 1P, 120/240V for MPZ Panelboard | Square D or Equal | QO115 |
| 9 | 1 | Square D Type QO Plug-On Circuit Breaker, 15A, 1P, 120/240V with 30 mA Ground Fault Protection for MPZ Panelboard | Square D or Equal | QO115EPD |
| 10 | 1 | Duplex 15A, 125V, GFCI Type Receptacle, Heavy Duty, 2P, 3-Wire Grounded, Ivory | Hubbell or Equal | GF15IL |
| 11 | 1 | Handy Box and Receptacle Cover | Raco or Equal | 8660 & 864 |
| 12 | 1 | Copper Bonded Steel Ground Rod, 3/4" Dia x 10 Ft Long | Erico or Equal | 613400 |
| 13 | 1 | 3-Phase Motor Protection Relay, 120Vac Control Power, 13 Protective Functions, Trip and Alarm Fail-Safe Relays | Littelfuse Powr-Gard | PGR-6150-120 |
| 14 | 1 | Operator Interface for Motor Protection Relay | Littelfuse Powr-Gard | PGR-6150-OPI |
| 15 | 1 | Motor Protection Circuit Breaker, Red/Yellow Lockable Knob, 480v, 3 PH, 60Hz 2.5 to 4A Adjustable Range with Front-Mounted N.O. Aux Contact | Allen-Bradley | 140M-C2E-B40-KY & 140M-C-AFA10 |
| 16 | 1 | IEC Contactor, 9A, 480V, 3 Ph, 60 Hz 120V, 1 N.O. Aux Contact, 60Hz Coil | Allen-Bradley | 100-C09D10 |
| 17 | 1 | 3 Position Selector Switch, Spring-Return from Left, 2 Contact Blocks with Hand-Off-Auto Legend Plate | Allen-Bradley | 800T-J4B & 800T-X511 |
| 18 | 1 | Green LED Pilot Light, 120Vac, 60 Hz | Allen-Bradley | 800T-QH2G |
| 19 | 1 | NEMA 4/13 Die Cast, 2-Hole Surface Mount Pushbutton Enclosure | Allen-Bradley | 800T-2TZ |
| 20 | 1 | DPDT Plug-In Relay, 24VDC Coil, LED, Push-to-Test and Manual Override and Socket | Allen-Bradley | 700-HA32Z24-3-4 & 700-HN100 |
| 21 | Lot | DIN Rail #3 for Mounting Components as required | Allen-Bradley | 199-DR1 |
| 22 | Lot | DIN Rail, 30A Terminal Blocks, End Anchors, End Barriers as required | Allen-Bradley | 1492-N22, 1492-HM1 1492-N23, 1492-NM36 |




EXTRACTION WELL PUMP CONTROL PANEL DETAIL
NTS

AO
TYP E–302A




SECTION A

NOTES:

1. 7 BARS PERPENDICULAR TO 5'–4" DIMENSION TOP AND BOTTOM.
   4 BARS PERPENDICULAR TO 2'–6" DIMENSION TOP AND BOTTOM

CONTROL PANEL PAD DETAIL
NTS

TIMOTHY C. KESSLER, P.E.
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 12/02/16 | TDD | TDD | RJR | SGS |
| 2 | 05/20/16 | TDD | TDD | SGS | SGS |
| 1 | 08/14/15 | RJR | SGS | SGS | SGS |
| 0 | 06/07/13 | TDD | SHM | BY | APVD |

REVISION

ISSUED FOR CONSTRUCTION

DCB 007.4.4

DCB 007.4.1

DCB 007.4

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

WIRING DIAGRAM


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | E-302A |
| SHEET | 65A OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

EXISTING MAIN DISTRIBUTION PANEL
WITHIN EXISTING GROUNDWATER
TREATMENT PLANT





NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE POLYVINYL CHLORIDE DIRECT BURIAL UNLESS NOTED OTHERWISE.
4. ALL PROPOSED CONDUITS WILL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE.
5. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE.
6. THE CONTRACTOR SHALL INSTALL THE 3"ø PVC SCH 40 CONDUIT FROM THE EXTRACTION WELLS INTO AND INCLUDE THE CONSTRUCTION OF THE EH @ THE GWTP. THE CONDUIT FROM THIS EH TO THE GWTP AND INSIDE WILL BE INSTALLED BY OTHERS IN THE FUTURE.
7. THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| EH | ELECTRIC HANDHOLE |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| SPD | SURGE PROTECTIVE DEVICE |
| TSP | TWISTED SHIELDED PAIR |
| V | VOLTAGE |
| W | WIRE |




| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 3 | 12/02/16 | DCB 007.4.2 | GCP | RJR | GCP | SGS | TCK |
| 2 | 05/06/16 | DCB 007.2.2 | | | | TDD | SGS |
| 1 | 09/02/15 | DCB 007.2.1 | | | | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | GCP | SGS |

TIMOTHY C. KESSLER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 889 - 2829
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-301 |
| SHEET | 67 OF 70 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




6 NORTH PUMP STATION 1 CONTROL SCHEMATIC

NTS




6 NORTH PUMP STATION 2 CONTROL SCHEMATIC

NTS

NOTE:

THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.

□ TERMINAL IN PUMP PANEL

FIELD WIRING

TIMOTHY C. KESSLER
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 3 | 12/02/16 | DCB 007.4.2 | SGS | TCK |
| 2 | 05/06/16 | DCB 007.2.2 | SGS | SGS |
| 1 | 09/02/15 | DCB 007.2.1 | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | GCP | SGS |
| DSGN | | DR GCP | CHK RJR | APVD GCP |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL


ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 890-2929
NJ Certificate of Authorization Number
24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-302 |
| SHEET | 68 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTE:


THE WIRE SIZING AND CONFIGURATION SHOWN IS BASED ON INFORMATION AVAILABLE AS OF DECEMBER 2016. IF IT IS DETERMINED THAT IT IS NECESSARY TO ACTIVATE THE CONTINGENT GROUNDWATER SYSTEM, PUMP SIZING AND CONTROLS SHOULD BE RE-EVALUATED BASED ON THE PROJECTED PUMPING RATES AND DURATION DETERMINED AT THAT TIME. PUMPS, CONDUITS AND WIRE HAVE BEEN SIZED CONSERVATIVELY. HEAVIER WIRE AND LARGER PUMPS COULD BE INSTALLED IN THE EXISTING CONDUIT IN THE EVENT IT WAS DEEMED NECESSARY.





EXTRACTION WELL PUMP CONTROL PANEL BACK DETAIL
NTS


**BILL OF MATERIALS**


| ITEM | QTY | DESCRIPTION | MFG | PART NO. |
|---|---|---|---|---|
| 1 | 1 | 60" H x 52" W x 18" D 2-Door NEMA 3R Pad-Mount Enclosure with back panel | Hoffman or Equal | A60R5218FSLP & A49P48N |
| 2 | 1 | 4 inch cooling fan with bracket and thermostat, 120 Vac | Hoffman or Equal | A4AXFN, ABRKT4, & ATEMNO |
| 3 | 1 | 400 Watt heater with fan and thermostat, 120 Vac | Hoffman or Equal | DAH4001B |
| 4 | 4 | 175A Power Distribution Terminal Block, #2/0 to #14 AWG Wire Size Range, IP20 Finger-Safe | Bussmann or Equal | PDBFS220 |
| 5 | 2 | Square D H-Frame, 30A, 3P, 600V, Thermal-Magnetic Circuit Breaker and NEMA 1 Surface -Mount Enclosure | Square D or Equal | HDL36030 & J250S |
| 6 | 1 | Type 1 Surge Protective Device, 480V, 3 Phase Delta, 3-Wire + Ground with Transient Filter and Surge Counter | Joslyn or Equal | JSP240-3D480-FB |
| 7 | 1 | Square D Mini-Power Zone, 5kVA, 480V-240/120V, NEMA 3R Enclosure with Primary & Secondary Main Breakers | Square D or Equal | MPZ5S40F |
| 8 | 5 | Square D Type QO Plug-On Circuit Breaker, 15A, IP, 120/240V for MPZ Panelboard | Square D or Equal | QO115 |
| 9 | 1 | Square D Type QO Plug-On Circuit Breaker, 15A, IP, 120/240V with 30 mA Ground Fault Protection for MPZ Panelboard | Square D or Equal | QO115EPD |
| 10 | 1 | Duplex 15A, 125V, GFCI Type Receptacle, Heavy Duty, 2P, 3-Wire Grounded, Ivory | Hubbell or Equal | GF15IL |
| 11 | 1 | Handy Box and Receptacle Cover | Raco or Equal | 8660 & 864 |
| 12 | 1 | Copper Bonded Steel Ground Rod, 3/4" Dia x 10 Ft Long | Erico or Equal | 613400 |
| 13 | 1 | 3-Phase Motor Protection Relay, 120Vac Control Power, 13 Protective Functions, Trip and Alarm Fail-Safe Relays | Littelfuse Powr-Gard | PGR-6150-120 |
| 14 | 1 | Operator Interface for Motor Protection Relay | Littelfuse Powr-Gard | PGR-6150-OPI |
| 15 | 1 | Motor Protection Circuit Breaker, Red/Yellow Lockable Knob, 480v, 3 PH, 60Hz 2.5 to 4A Adjustable Range with Front-Mounted N.O. Aux Contact | Allen-Bradley | 140M-C2E-B40-KY & 140M-C-AFA10 |
| 16 | 1 | IEC Contactor, 9A, 480V, 3 Ph, 60 Hz 120V, 1 N.O. Aux Contact, 60Hz Coil | Allen-Bradley | 100-C09D10 |
| 17 | 1 | 3 Position Selector Switch, Spring-Return from Left, 2 Contact Blocks with Hand-Off-Auto Legend Plate | Allen-Bradley | 800T-J4B & 800T-X511 |
| 18 | 1 | Green LED Pilot Light, 120Vac, 60 Hz | Allen-Bradley | 800T-QH2G |
| 19 | 1 | NEMA 4/13 Die Cast, 2-Hole Surface Mount Pushbutton Enclosure | Allen-Bradley | 800T-2TZ |
| 20 | 1 | DPDT Plug-In Relay, 24VDC Coil, LED, Push-to-Test and Manual Override and Socket | Allen-Bradley | 700-HA32Z24-3-4 & 700-HN100 |
| 21 | Lot | DIN Rail #3 for Mounting Components as required | Allen-Bradley | 199-DR1 |
| 22 | Lot | DIN Rail, 30A Terminal Blocks, End Anchors, End Barriers as required | Allen-Bradley | 1492-N22, 1492-HM1 1492-N23, 1492-NM36 |





PUMP STATION CONTROL PANEL DETAIL
NTS




PUMP STATION CONTROL PANEL DETAIL
NTS


AQ
TYP E-302A





TYPICAL PUMP STATION ONE LINE
NTS

5KVA 480V-120/240V MINIMUM POWER ZONE

GROUNDWATER EXTRACTION TRENCH PUMP STATION




PLAN




SECTION A

NOTES:

1. 7 BARS PERPENDICULAR TO 5'-4" DIMENSION TOP AND BOTTOM.
   4 BARS PERPENDICULAR TO 2'-6" DIMENSION TOP AND BOTTOM

CONTROL PANEL PAD DETAIL
NTS

TIMOTHY C. KESSLER, P.E.
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 24GE03749500
SGS

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 3 | 12/02/16 | DCB 007.4.2 | TDD | SGS |
| 2 | 05/20/16 | DCB 007.4.1 | TDD | SGS |
| 1 | 08/14/15 | DCB 007.4 | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |

DSGN TDD DR RJR CHK SHM APVD SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL

WIRING DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 587-2823
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-302A |
| SHEET | 65A OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR68-EN-302A WIRING DIAGRAM.dwg PLOT DATE: Fri, 16 Dec 2016 PLOT TIME: 10:46 AM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 054.6 **Type:** Minor(a)<br>**Effective Date:** September 2016 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** Interim Grading SA-6N | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** This DCB includes several revisions to the interim/final grading and SESCP drawings on the SA-6 North Chromium Remedy. The changes are depicted on the listed Drawings. This DCB confirms directives issued to Entact in the field.

The minor Grading Changes include localized areas as noted below


- Relocation and grading of the drainage swale along the temporary road at the west end of the Cap. Flow has been directed to the SA-7 outfall in lieu of sheet-flow over the Hackensack bulkhead embankment.
- Adding fill along the eastern 300 ft of the SA-7/SA-6N boundary on SA-6N to provide for a gradual transition from the SA-7 paved road to the SA-6N interim grades. This will be a temporary condition to improve surface drainage pending redevelopment.

SESCP changes include the following

- Installation of a crushed stone toe drain along SA-7 and use of the former asphalt roadway to conduct stormwater to the Hackensack River in lieu of the in-slope parabolic swale shown in the IFC design on both SA-6N.
- Installation of Erosion Control mat on the steep edge slopes on the north and south sides of both SA-6N. Conditions will continue to be observed and supplemental measures implemented if necessary
- Installation of supplemental diversion berms to direct water through the culverts under the temporary road.
- Installation/restoration of stone check dams near the surface water outfall to the Hackensack River on SA-7. The precise location and dimension of the check dams will be field engineered based on observed flow during storm events.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Drawings:<br>CN - 125<br>CN - 126 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 12/01/16 |
| **(Name / Signature):** | **Does DCB Result in CCO? (b)** ☐ Yes ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS BASED ON MINIMAL FILL THICKNESS REQUIREMENTS. FINAL GRADES MAY VARY AFTER CONTRACTIBILITY REVIEW.
4. REFER TO APPENDIX K CONCEPTUAL REDEVELOPMENT PLANS (100% REMEDIAL DESIGN REPORT) FOR FUTURE UTILITY ALIGNMENTS AND PRELIMINARY ALTERNATIVE GRADING CONCEPTS.
5. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/29/16 | TDD | TDD | RJR | SGS |
| 1 | 05/13/16 | TDD | | | SGS |
| 0 | 06/07/13 | TDD | | | SGS |
| | | BY | | | APVD |

DCB 054.6
DCB 054.3
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

INTERIM GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 -2829
NJ Cert of Authorization 24GA28019500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-125 |
| SHEET | 30 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR30-C-125 Final Grade Drain SESC Plan.dwg PLOT DATE: Thu, 01 Dec 2016 PLOT TIME: 8:56 AM

NOTES:

1. REFER TO SHEET GN–003 AND GN–004 FOR GENERAL NOTES.
2. REFER TO SHEET GN–002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS BASED ON MINIMAL FILL THICKNESS REQUIREMENTS. FINAL GRADES MAY VARY AFTER CONTRACTIBILITY REVIEW.
4. REFER TO APPENDIX K CONCEPTUAL REDEVELOPMENT PLANS (100% REMEDIAL DESIGN REPORT) FOR FUTURE UTILITY ALIGNMENTS AND PRELIMINARY ALTERNATIVE GRADING CONCEPTS.
5. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

MATCH LINE SHEET CN–125

HACKENSACK RIVER

PIERHEAD AND BULKHEAD LINE AS ADOPTED DECEMBER 9, 1929

APPROXIMATE LOCATION OF OUTFALL

EA8 INTERIM RESTORATION PENDING BULKHEAD RESTORATION CONTOURED TO SHOW POST CR REMEDIATION AND SEEDED

FINAL RESTORATION GRADE (TYP)

EXISTING CULVERTS 12" PVC AND 6" CPP PIPES INV=6.6 IN

EXISTING CULVERTS 8" HDPS AND 6" CPP PIPES INV=6.6 OUT

INSTALL ROCK OUTLET FILTER AJ CN–126 CN–308

SEDIMENT BOOM

SAND BAG OVERFLOW WEIR

EXISTING BERM

GROUNDWATER TREATMENT PLANT (SEE NOTE GN23 ON SHEET GN–003)

1 STORY MASONRY BUILDING

(5) CARGO CONTAINERS

(4) CARGO CONTAINERS

(6) CARGO CONTAINERS

WOOD SHED

TRAILER

OPEN STORAGE

EMERGENCY OUTFLOW STRUCTURE

HYDRAULIC BARRIER (SEE PLAN AND PROFILE SHEETS SN–201 THRU SN–203)

CONSTRUCTION WATER TREATMENT AREA SEE SHEET CN–106

INSTALL INLET PROTECTION (TYP) INLET FILTER DETAIL AL CN–126 CN–308

TYPICAL VEGETATIVE SWALE R CN–126 CN–304

INTERIM GRADES TO MEET EXISTING GRADES AFTER DEMOLITION OF SEDIMENTATION BASIN. SEE SEDIMENTATION BASIN NOTES ON SHEET GN–004

INSTALLED EROSION CONTROL BLANKET

INSTALLED DIVERSION BERM

EXISTING SA7 PERIMETER ROAD

RELOCATED SA7 PERIMETER ROAD

EXISTING SOIL CEMENT BENTONITE WALL (TYP) (SEE SHEETS SN–204 AND SN–205)

AJ CN–126 CN–308 INSTALL ROCK OUTLET FILTER

XX CN–126 CN–309 SA–7 EDGE DETAIL

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 3 | 11/29/16 | TDD | TDD | RJR | SGS |
| 2 | 05/13/16 | | DCB 054.6 | TDD | SGS |
| 1 | 09/13/13 | | DCB 054.3 | TDD | SGS |
| 0 | 06/07/13 | | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| | | | REVISION | BY | APVD |

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

INTERIM GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 888 - 2828
NJ Cert of Authorization 24GA28019600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-126 |
| SHEET | 31 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR31-C-126 Final Grade Drain SESC Plan.dwg PLOT DATE: Thu, 01 Dec 2016 PLOT TIME: 9:01 AM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 030.2 **Type:** Minor(a)<br>**Effective Date:** September 2016 |
| **Project Location:** SA-6 South | **Associated RFI:** |
| **Title:** Cap Final Grading and Development Area grading and Restoration | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** This DCB summarizes several field engineering directions provided to Entact. This DCB includes several minor revisions to the final grading in the SA-6 South Chromium Remedy Cap and Development Areas. The changes have been made to improve surface water flows and enhance Sedimentation and Erosion Control Drawings C-125, C-126 and C-127 cover the area of both the Cap and the Development Area. The Restoration details previously shown on drawing C-128 have been added to these three drawings. C-128 has been deleted from the set.

- Installation of a crushed stone toe drain along SA-7 toe, and use of the former asphalt roadway to conduct stormwater to the Hackensack River, in lieu of the "in-slope" parabolic swale shown in the IFC design. The drain is located where the toe of slope temporarily terminates in SA-7 pending raising SA-7 to the Bayfront Development grades. The toe drain is considered to be more resilient than the original swale design and will provide equal or better sedimentation and erosion control.
- Adding topsoil over the eastern 300 ft. of the cap along SA-7/SA-6S boundary to provide for a gradual transition from the SA-7 paved road to the SA-6S Final Grades.
- Extent of demarcation geotextile, crushed stone, and DGA placed over the Development Area to meet covering of Historic Fill regulations. The restoration grades were modified to accommodate placement of gravel over foundations and pavement in a number of areas that were not included in the IFC restoration drawing.
- Installation of Erosion Control mat on the steep edge slopes on the north and south sides of SA-6S. The precise limits of mat will be determined in the field based on observed performance.
- Installation of supplement diversion berms to direct water through the culverts under the temporary roads. The location and size of the berms shown on the drawings may be modified in the field based on observation of the performance in storm events
- Installation/restoration of stone check dams and diversion dams near the surface water outfall to the Hackensack River on SA-7. The precise location and dimension of the check dams will be field engineered based on observed flow during storm events.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:**<br>Documents minor changes in grading and improved stormwater control.<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>C-125, C-126, C-127.<br>C-128 deleted. |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 12/01/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |




NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002
3. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| | | TDD | | RJR | TDD | SHM | SHM |
| 3 | 11/29/16 | DCB 030.2 | | | | TDD | SGS |
| 2 | 4/15/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | | | | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | | | | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | | TDD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 889 - 2829
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-125 |
| SHEET | 30 OF 66 |




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002
3. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| DSGN | TDD | DR RJR | TDD | SHM |
| 3 | 11/29/16 | DCB 030.2 | TDD | SGS |
| 2 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND EROSION SEDIMENT CONTROL PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28018900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-126 |
| SHEET | 31 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR31-C-126 Final Grade Plan.dwg PLOT DATE: Thu, 01 Dec 2016 PLOT TIME: 9:11 AM




NOTES:

1. REFER TO GENERAL NOTES SHEET G–003 AND G–004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G–002
3. THE PRECISE LOCATION AND DIMENSION OF THE CHECK DAMS AND DIVERSION DAMS WILL BE FIELD LOCATED/ENGINEERED BASED ON OBSERVED FLOW DURING STORM EVENTS.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 4 | 11/29/16 | TDD | | RJR | TDD |
| 3 | 4/18/16 | DCB 030.2 | | | |
| 2 | 11/16/15 | DCB 30.1 - REVISED GRADING AND RESTORATION | | | |
| 1 | 10/11/13 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | | | |
| 0 | 06/07/13 | MODIFIED BARRIER WALL ALIGNMENT | | | |
| | | ISSUED FOR CONSTRUCTION | | | |
| | | REVISION | BY | CHK | APVD |
| | | | TDD | SGS | SGS |
| | | | TDD | SGS | SHM |
| | | | RJR | SGS | |
| | | | TDD | SHM | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-127 |
| SHEET | 32 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR32-C-127 Final Grade Plan.dwg PLOT DATE: Thu, 01 Dec 2016 PLOT TIME: 9:15 AM

## DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6, Jersey City, New Jersey** | **DCB Type: Minor**<br>**Effective Date: 05/19/14** |
| **Project Location: SA-6 South**<br>**Site Owner: Honeywell** | **Associated RFI:**<br>☐ Yes, RFI No. _____ ☒ None |
| **Client: AMEC**<br>**Contractor (*Subcontractor*): ENTACT** | **Project No.: 3480130377** |

**Description of Change/Modification:**

Honeywell will defer all excavation in the area shown on the attached **Figure 1**. This area includes a portion of Cell 153 and Cell 154 through Cell 156 in their entirety (see Photo 1). This design change is necessary due to unanticipated subsurface conditions, approximately 5 feet of concrete was encountered in the subgrade of this area during excavation in Cell 153 (see cross-section A-A'). Vibration during demolition of the concrete so that excavation may proceed as shown on Drawings C-112 & C-113 in the SA-6 100% Design is expected to impact the integrity of the fragile bulkhead in this area (see Photo 2). Therefore, removal of the concrete/asphalt berm, demolition of subsurface concrete, and excavation to the specified design elevations in the area shown on **Figure 1** will be deferred until implementation of the Bayfront Redevelopment Plan when the bulkhead will be either repaired or replaced.


| | |
|---|---|
| **Reason for Change/Modification:**<br>☒ Unforeseen or Differing Site Conditions<br>☒ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | **Explanation or Reason:** Deferred Excavation Due to Unanticipated Excessive Concrete<br>**Attachments:** ☒ Yes ☐ No<br>**Cost Implication:** ☒ Yes ☐ No<br>**>$50K** TBD<br>**Schedule Impact** ☐ Yes ☒ No |
| **Additional Comments:** DCB anticipated to require review and approval by third parties. | **Design Documents Affected:** Drawings C-112 & C-113 |

**Honeywell (AP) Review:**

| **Individual: Geoff Shallard** **Discipline: EOR** | **Initial** | **Date** |
|---|---|---|
| | | |
| | | |
| | | |

| | | |
|---|---|---|
| **Contractor (*Subcontractor*) Review:** | **Does DCB Result in CCO?** | ☒ Yes ☐ No |
| **(Name / Signature):** | **Date** | |

**Distribution:**




LEGEND

- CONFIRMATORY BOTTOM SAMPLE ELEVATION
- CONFIRMATORY SIDEWALL SAMPLE ELEVATION
- 0.0 POINT ELEVATION
- POINT POINT DESCRIPTION
- BOTTOM CENTER POINT ELEVATION STRATUM D
- BOTTOM CENTER POINT ELEVATION <20 PPM
- BOTTOM CORNER POINT ELEVATION <20 PPM
- DESIGNED STRATUM D EXCAVATION LIMIT
- PREVIOUSLY SUBMITTED DATA
- CURRENT EXCAVATION TO STRATUM D
- CURRENT EXCAVATION TO <20 PPM
- TOP OF EXCAVATION SLOPE
- LIMIT OF EXCAVATION AREA

ENTACT 302 Unity Plaza Latrobe, PA 15650

DRAWING NAME
EXCAVATION BOTTOM ELEVATIONS
PERIOD 04-14-14 TO 05-01-14

PROJECT NAME & LOCATION
HONEYWELL SA-6 REMEDIATION
JERSEY CITY, NJ

Photo 1 - Deferred Area at SA-6
South (Site 073)

JOB NO. 3480130377 SHEET 1 OF 1
PHASE TASK
JOB NAME SA-6 CHROMIUM REMEDY
BY DEM DATE 5/13/14
CHECKED BY DATE

amec
American Metro Center 200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
+1 (609) 689-2829 Fax +1 (609) 689-2838

# SECTION A-A'




Photo 2 - Bulkhead at Deferred Area at SA-6 South (Site 073)

**Honeywell RES** → Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB Type: Minor (a)<br>Effective Date: 12/23/2014 |
| Project Location: SA-6 NORTH, SA6-SOUTH | Associated RFI: |
| Title: Site 163 Deferred Areas | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

When conducting the Site 163 shallow excavation remedy along the cove, unreinforced mass concrete and a steel structure were identified in direct contact with structural components of the bulkhead. These locations were inspected by the Amec engineer and it was determined that removal could be detrimental to the integrity of the bulkhead.

The location and description of the three isolated and small Deferred Areas are shown on the attached drawing.


The total volume of the materials left in place is estimated to be less than 35 cubic yards.

As noted the material left in place was concrete. There was no visible sign of the concrete being "chromium impacted".

The remediation of this de minimis material will be completed along with the other SA-6 South bulkhead deferral area along the river, once the permanent bulkhead is installed.

| | |
|---|---|
| Reason for Change/Modification:<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other (describe) | Explanation or Reason: Modified due to field conditions.<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: |
| Honeywell (AP) Review:<br>Individual Discipline | Initial [signature] Date 12/20/16 |
| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: |
| Distribution: | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




SITE 163 DEFERRED EXCAVATION AREA 1:

REMOVAL OF EXISTING CONCRETE MAY IMPACT BULKHEAD INTEGRITY

DESIGN EXCAVATION BOTTOM = 5.20 FT (NGVD 29)

PROJECTED REMOVAL VOLUME = 10 CY

SITE 163 DEFERRED EXCAVATION AREA 2:

REMOVAL OF EXISTING STEEL VAULT FILLED WITH SAND MAY IMPACT BULKHEAD INTEGRITY

DESIGN EXCAVATION BOTTOM = 3.60 FT (NGVD 29)

PROJECTED REMOVAL VOLUME = 5 CY

SITE 163 DEFERRED EXCAVATION AREA 3:

REMOVAL OF EXISTING SOIL AND CONCRETE MAY IMPACT BULKHEAD INTEGRITY

DESIGN EXCAVATION BOTTOM = 5.60 FT (NGVD 29)

PROJECTED REMOVAL VOLUME = 20 CY

0 10 20 40
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| DSGN | TDD | DR | CHK | APVD |
| | TDD | RJR | TDD | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

STUDY AREA 6 SOUTH
CHROMIUM REMEDY
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37394

DRAWING STATUS
CONSTRUCTION DRAWINGS

SITE 163
DEFERRED EXCAVATION AREAS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 588-2929

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | 01/21/15 |
| PROJ | 3480-10-0027 |
| DWG | 001 |
| SHEET | 1 OF 1 |

FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 Deferment Areas\Figure 1 Site 163 Deferment Areas.dwg PLOT DATE: Wed, 21 Jan 2015 PLOT TIME: 11:46 AM

Honeywell RES

→Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| Project Name: Chromium Remedy Study Area 6<br>Jersey City, NJ | DCB No.: 23 DCB Type: Minor (a)<br>Effective Date: 4/30/15 |
| Project Location: SA-6 | Associated RFI: |
| Title: JCIA Trash Pit Closure | ☐ Yes, RFI No. ___ ☑ None |
| | Project No.: 3480130377 |
| Contractor (Subcontractor): Entact | |

A concrete protuberance was encountered 12-13 ft below grade, which prevented driving the sheet to full depth immediately adjacent the JCIA trash pit. The closure sheet was notched per the attached sections to clear the concrete. A series of 8" holes were augured and grouted starting at the JCIA pit and moving out along the alignment of the closure section to provide continuity with the pit. The closure sections were then lowered/pushed to the design depth.


| | |
|---|---|
| Reason for Change/Modification:<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | Explanation or Reason: Obstruction encountered during HB sheetpile driving adjacent the JCIA trash pit<br>Attachments: ☑ Yes ☐ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: |

Honeywell (AP) Review:

| Individual | Discipline | Initial | Date |
|---|---|---|---|
| (Name / Signature): | | Does DCB Result in CCO? ☐ Yes (b) ☑ No | Date: ~~4/30/15~~ 6/8/15 |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




JCIA TRASH PIT – WEST CLOSURE
NTS


Prepared/Date: TDD 4/14/15
Checked/Date:

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ 08619
Phone: (609) 689 - 2829
NJ Certificate of Authorization
Number 24GA28010900

FIGURE 1
VHB CLOSURE DETAIL
Project 3480-10-0027

C:\Donovan\SA-6 North\2013 Excavation Surfaces\SA-6 North VHB\SA-6 North VHB Closure Sections.dwg Mon, 20 Apr 2015 - 1:42pm tony.donovan




JCIA TRASH PIT – EAST CLOSURE
NTS

Prepared/Date: TDD 4/14/15
Checked/Date:

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc
200 American Metro Blvd. Suite 113
Hamilton, NJ 08619
Phone: (609) 689 - 2829
NJ Certificate of Authorization
Number 24GA28010900

FIGURE 2
VHB CLOSURE DETAIL
Project 3480-10-0027

C:\Donovan\SA-6 North\2013 Excavation Surfaces\SA-6 North VHB\SA-6 North VHB Closure Sections.dwg Mon, 20 Apr 2015 - 1:43pm tony.donovan

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name: Chromium Remedy Study Area 6 Jersey City, NJ** | **DCB No.: DCB Type: Minor (a)** |
| | **Effective Date: 6/5/15** |
| **Project Location: SA-6 South** | **Associated RFI:** |
| **Title: SA-6 South Contingent GW Piezometer Locations** | ☐ **Yes, RFI No. __** ☑ **None (Request via e-mail)** |
| | **Project No.:** 3480130377 |
| **Contractor (Subcontractor): ENTACT** | |

**Description of Change/Modification:**

The general location of the paired piezometers was depicted in the Plan view of the Contingent system.

Specific coordinates were not included.

ENTACT has requested specific coordinates.

In preparing the coordinates Amec Foster Wheeler reviewed the locations shown in the IFC design with the latest road and utility designs prepared by CHA. This has resulted in minor movements of the piezometers. The movement will have no impact on the performance of the piezometers to meet their intended purpose for measurement of the hydraulic gradient across the wall.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐Design Revision<br>☐ Owner/Client Request<br>☑ Other (See Explanation) | **Explanation or Reason:** Adjustments to avoid conflicts with future development and to keep piezometers out of roadways. |
| | Attachments: ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| Additional Comments: | Design Documents Affected: |

Honeywell (AP) Review:

| **Individual:** Geoff Shallard **Discipline:** EOR | **Initial** | **Date** |
|---|---|---|
| | | |

| | |
|---|---|
| (Name / Signature): | Does DCB Result in CCO? ☐ Yes (b) ☑ No<br>Date: |

Distribution:

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

PZ16
N=684751.18
E=602508.94

PZ15
N=684735.78
E=602497.53

PZ14
N=684420.82
E=602907.51

PZ13
N=684391.71
E=602893.97

PZ12
N=684207.73
E=603276.91

PZ11
N=684200.51
E=603290.09

PZ19
685587.17
601500.99

PZ20
N=685584.00
E=601504.14

PZ18
N=685136.43
E=601988.86

PZ17
N=685121.22
E=601977.60

HORIZONTAL SCALE: 1" = 40'

0 20 40 80

SCALE IN FEET

Prepared/Date: RJR 07/09/15
Checked/Date: SGS 07/09/15

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019900

Piezometer Location
Project 3480-13-0377
Figure 1

Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design - SAs - 2015\CAD\SA6 - North - South - RA_Excavation_Trench\CR34 - C - 201_Cont_Offs_Trench.dwg Thu, 09 Jul 2015 - 8:47pm roger.ripster

Honeywell RES

Honeywell.com

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 50 **DCB Type:** Minor (a)<br>**Effective Date:** 10/02/15 |
| **Project Location:** SA-6 North and South | **Associated RFI:** |
| **Title:** Warning Tape above Root Barrier | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** ENTACT installed warning tape above the geocomposite drainage layer (GDL), as called for in Drawings C-301 and CN-301. As an additional precautionary measure, ENTACT will install warning tape directly on top of the root barrier layer. The warning tape will generally be installed perpendicular to the warning tape above the GDL. On the steep slopes into roadway/utility corridors and the tree planting areas the tape will be set running from the top of the slope to the bottom of the slope.

The warning tape will be the same tape used above the orange GDL warning fabric, i.e. a 6 inch wide yellow PE tape with 3.5 inch bold back lettering which meets the specified requirements for a distinctive colored high-visibility marking. The tape will be placed at no more than 5 ft. on center.

| | |
|---|---|
| Reason for Change/Modification:<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>**Attachments:** ☐ Yes ☑ No<br>Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 10/2/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.: DCB 030 Type:** Minor(a)<br>**Effective Date: 11/12/2015** |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Final Grade Revisions | ☑ Yes, RFI Nos. 057 ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description. The Final Grades were revised to allow for a 0.25 increase in subgrade elevations eastern portions of SA-6 where subgrade had not been completed at the time (July 2015). The changes in subgrade were made in conjunction with the elimination of the utility corridor near the jug handle. The Subgrade changes were conveyed in DCB 027.**

**In parallel with the grade changes Amec Foster Wheeler and Entact developed a methodology for adapting grading of the cover soils to offsets from either subgrade or Final Development Grade. The methodology was described in the response to RFI 057. Some minor changes (0.1 to 0.2 ft.) have also been made in localized areas to improve surface drainage.**

**Offsets from the final cover soil will be used in the Machine Control to complete cover soil grading as noted in RFI 057. This DCB impacts Final Grade Drawings C-125, C-126 and C-127 and the associated electronic files.**

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See description above |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:** Drawings C-125, C-126, C-127 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 11/19/15 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | TDD | DR RJR CHK TDD | APVD | SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THIE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 588 - 2629
http://www.amecfw.com/environment/

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-125 |
| SHEET | 30 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR30-C-125 Final Grade Plan.dwg PLOT DATE: Mon, 16 Nov 2015 PLOT TIME: 10:45 AM

SA-7

MATCH LINE SHEET C-127

MATCH LINE SHEET C-125

TYPICAL SA-7 EDGE DETAIL (H, C-126 | C-301)

TEMPORARY CONSTRUCTION FENCE (L, C-126 | C-302)

INSTALL TEMPORARY ROCK OUTLET FILTER (TYP) (AK, C-126 | C-307)

SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005) (AG, C-126 | C-307)

EXISTING SOIL CEMENT BENTONITE WALL, SEE PLAN AND PROFILE SHEETS S-204 THRU S-206

EXISTING SA-7 PERIMETER ROAD RELOCATE AS NECESSARY TO ACCOMMODATE FINAL GRADING AND EROSION CONTROL MEASURES

RELOCATED SA-7 PAVED PERIMETER ROAD

TYPICAL VEGETATED SWALE (Q, C-126 | C-303)

HYDRAULIC BARRIER, SEE PLAN AND PROFILE SHEETS S-201 THRU S-203

SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005) (AG, C-126 | C-307)

TEMPORARY CONSTRUCTION TRAILERS

CHAINLINK FENCE ON PRECAST CONCRETE BARRIER (TYP) (M, C-126 | C-302)

INSTALL 186 LF 12" HDPE @ 0.5%

MATERIAL STORAGE AREA

KELLOGG STREET

DROYERS COVE

CHAIN LINK FENCE WITH DOUBLE GATE

STABILIZED CONSTRUCTION ACCESS (J, C-126 | C-302; AH, C-126 | C-307)

APPROXIMATE LIMIT OF DISTURBANCE (TYP) (SEE NOTE EXC7 ON SHEET G-004)

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 11/16/15 | TDD | SGS | SHM | SHM |
| 0 | 06/07/13 | TDD | SHM | APVD | |
| | REVISION | | BY | | |

DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25'
ISSUED FOR CONSTRUCTION

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CIVIL
REMEDIATION FINAL GRADING, DRAINAGE, AND EROSION SEDIMENT CONTROL PLAN

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

amec foster wheeler
Environment & Infrastructure, Inc.
2790 Whitehorse-Hamilton Square, Suite 113
Hamilton, NJ, 08619, (609) 888-2829
NJ Certificate of Authorization Number 24GA28019900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-126 |
| SHEET | 31 OF 66 |




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS | |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM | |
| | | REVISION | BY | APVD | |

TDD RJR TDD

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SHM

ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.
THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATEN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 889 - 2629
NJ Certificate of Authorization Number 24GA28019500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-127 |
| SHEET | 32 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR32-C-127 Final Grade Plan.dwg PLOT DATE: Mon, 16 Nov 2015 PLOT TIME: 10:13 AM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** DCB-054 **Type:** Minor(a)<br>**Effective Date:** 2/2/2016 |
| **Project Location:** SA-6N | **Associated RFI:** |
| **Title:** Increase grade 0.25' in Landscape Area | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** The final grade in the landscape area has been raised by a nominal amount of 0.25'. Roadways and sidewalks have been retained at the IFC design elevations. The approach is consistent with that undertaken on SA-6S.

In the initial transmittal Amec is providing the electronic files for the subgrade/geomembrane surface and the top of SCB and sheetpile Barrier Wall. Hard copy of related drawing files will be submitted under separate cover. The subgrade surface has been extended 10 ft. beyond the Barrier Walls in consideration of Machine Control requirements.

Hard copy drawings will be issued in multiple phases. The first phase will be replacement of Geomembrane Grade drawings CN-123 and CN-124, and Barrier Wall Plan and Profiles SN-201, SN-202, SN-203, SN-204 and SN-205. Second phase will include the Interim Grading plans and associated details. The utility Corridor Drawing CN-515 will also be revised to reflect the latest CHA utility corridors. The location and dimension of the Geofoam blocks will be added to CN-515.

In the process of revision, Amec coordinated the subgrade design with CHA to reflect their latest utility plans. CHA has made a number of changes subsequent to the issue of Amec's IFC design. CHA changes included deletion of some structures and relocation of certain utilities. Amec has adjusted subgrade surfaces where these changes were made. Items of specific note include:

- *Elimination of the cap pump station*
- *Revision to the utility corridors*
- *Simplification of the Geomembrane grading*
- *Revision to the top of SCB/Sheetpile barrier wall at some locations*
- *The area of GCL has been expanded to elevation 7. The IFC design was based on a seasonal high groundwater of 5.5. Readings since that time have indicated that seasonal highs may be slightly higher (max 6.3).*
- *The location and extent of the Sand/Bentonite plug. Note: in locations where the barrier wall is at elevation 7 or higher no plug will be required.*

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>NA |

| | | | |
|---|---|---|---|
| **Honeywell (AP) Review:** | | | |
| **Individual:** Geoff Shallard | **Discipline:** EOR | **Initial:** | **Date:** 2/2/16 |
| **(Name / Signature):** | | **Does DCB Result in CCO?** | ☐ Yes (b) ☑ No |
| | | **Date:** | |
| **Distribution:** | | | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b) – If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 054.1 **DCB Type:** Minor(a)<br>**Effective Date:** 2/22/16 |
| **Project Location:** SA-6N | **Associated RFI:** |
| **Title:** Geomembrane Subgrade Revisions | ☑ Yes, RFI #: 64 ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

DCB 054 included issuance of a revised subgrade design that included changes resulting from raising the cap grades by 0.25 ft. in the landscaped areas and revisions to utility corridors to reflect the latest CHA utility design.

To accommodate Entact's request to relocate Pump Station #1 (RFI 64) it was necessary to revise the subgrade. Subgrade has been lowered at the new location to accommodate the vault and piping, and raised in the original pump station location.

In addition AmecFW reviewed the "driven" top of barrier elevations through the Sedimentation Basin. The underlying soils were found to be very soft under the sedimentation basin and Entact experienced difficulty in preventing the previously driven sheet from being drawn down by the next sheet driven. A significant number of sheets were recorded as being between 11.4 ft. and 12.0 ft. For grading purposes, it is necessary to have a reasonably uniform elevation. The attached plan is based on trimming the sections of wall that are below 12.0 to a uniform elevation of 11.5 ft. Trimmed sheets will require touch up of the epoxy coating.


DCB 054 required that the top of wall elevations of the Barrier Wall should be checked following surcharge and prior to trimming the wall. If any discrepancies are observed, they should be immediately brought to the attention of the EOR for resolution.

Some field engineering is likely to be required to smooth the subgrade contours at the locations of the steps down into the Sedimentation Basin on both the east and west sides of the Sedimentation Basin.

The two revised subgrade drawings are attached to this DCB. The electronic files for the geomembrane subgrade and revised top of the barrier wall are also attached.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>Pump Station #1 relocation |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Changes were made to accommodate requested contractor change to Pump Station location and actual installed barrier wall elevations. | **Design Documents Affected:**<br>Drawings CN-123, CN-124 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 2/23/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TO OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.
5. CONTRACTOR TO RESURVEY TOP OF BARRIER WALL FOLLOWING SURCHARGE REMOVAL AND PROVIDE RESULTS TO THE EOR. THE EOR WILL REVIEW AND DETERMINE IF ANY SMALL LOCALIZED AREAS EXIST WHERE THE TOP OF SHEET IS BELOW THE DESIGN SUBGRADE. IF SUCH AREAS ARE IDENTIFIED THEY WILL BE EVALUATED BY THE ENGINEER AND A FIELD DESIGN CHANGE WILL BE MADE TO ADJUST THE SUBGRADE TO THE TOP OF WALL.

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 3 | 02/19/16 | DCB 054.1 REVISED SED BASIN AND PS#1 SUBGRADE | TDD | SGS |
| 2 | 02/01/16 | DCB 054 INCREASED LANDSCAPE GRADE 0.25 FEET | TDD | SGS |
| 1 | 02/24/15 | DCB 007.5 | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | TDD | DR RJR CHK TDD APVD SGS | | |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

# GEOMEMBRANE GRADING PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619 (609) 890-2999
NJ Cert of Authorization: 24GA28315900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-123 |
| SHEET | 28 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR28-C-123 Geomembrane Grade.dwg PLOT DATE: Tue, 23 Feb 2016 PLOT TIME: 2:25 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TO OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.
5. CONTRACTOR TO RESURVEY TOP OF BARRIER WALL FOLLOWING SURCHARGE REMOVAL AND PROVIDE RESULTS TO THE EOR. THE EOR WILL REVIEW AND DETERMINE IF ANY SMALL LOCALIZED AREAS EXIST WHERE THE TOP OF SHEET IS BELOW THE DESIGN SUBGRADE. IF SUCH AREAS ARE IDENTIFIED THEY WILL BE EVALUATED BY THE ENGINEER AND A FIELD DESIGN CHANGE WILL BE MADE TO ADJUST THE SUBGRADE TO THE TOP OF WALL.

| NO. | DATE | REVISION | CHK |
|---|---|---|---|
| 4 | 02/16/16 | DCB 054.1 REVISED SED BASIN AND PS#1 SUBGRADE | TDD |
| 3 | 02/01/16 | DCB 054 INCREASE LANDSCAPE GRADE 0.25 FEET | TDD |
| 2 | 02/24/15 | DCB 007.5 | TDD |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD |

DSGN TDD DR RJR CHK TDD APVD

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS APVD BY

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

GEOMEMBRANE GRADING PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Cert of Authorization 24GA28019300

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-124 |
| SHEET | 29 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR29-C-124 Geomembrane Grade.dwg PLOT DATE: Fri, 19 Feb 2016 PLOT TIME: 2:26 PM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 054.2 **DCB Type:** Minor(a)<br>**Effective Date:** 2/25/16 |
| **Project Location:** SA-6N | **Associated RFI:** |
| **Title:** Barrier Wall & SCB Wall Plan and Profile | ☑ Yes, RFI Nos. 64 ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** DCB 054 included issuance of a revised subgrade design that included changes resulting from raising the cap grades by 0.25 ft. in the landscaped areas and revisions to utility corridors to reflect the latest CHA utility design.

To accommodate Entact's request to relocate Pump Station #1 (RFI 64) it was necessary to revise the subgrade. Subgrade has been lowered at the new location to accommodate the vault and piping and raised in the original pump station location.

In addition, AmecFW reviewed the "driven" top of barrier elevations through the Sedimentation Basin. The underlying soils were found to be very soft under the sedimentation basin and Entact experienced difficulty in preventing the previously driven sheet from being drawn down by the next sheet driven. A significant number of sheets were recorded as being between 11.4 ft. and 12.0 ft. For grading purposes it is necessary to have a reasonably uniform elevation. The subgrade plan and barrier wall plan and profile are based on trimming the sections of wall that are below 12.0 to a uniform elevation of 11.5 ft. Trimmed sheets will require touch up of the epoxy coating.

DCB 054 required that the top of wall elevations of the Barrier Wall should be checked following surcharge and prior to trimming the wall. If any discrepancies are observed that should be immediately brought to the attention of the EOR for resolution.


Some field engineering is likely to be required to smooth the subgrade contours at the locations of the steps down into the Sedimentation Basin on both the east and west sides of the Sedimentation Basin.


This DCB is limited to issue of the hard copy Signed and Sealed revisions to the SCB Wall and Barrier Wall Plan and Profile Sheets SN-201, SN-202, SN-203, SN-204 and SN-205.

The electronic files that provide the subgrade surface and top of barrier wall profile were provided with DCB 054.1.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>Pump Station#1 relocation<br>**Attachments:** ☑ Yes ☐ No<br>Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** Changes were made to accommodate requested contractor change to Pump Station location and actual installed barrier wall elevations. | **Design Documents Affected:**<br>Drawings SN-201, SN-202, SN-203, SN-204 and SN-205 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 3/3/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. STATION 14+00 TO 19+00 THE TOE OF THE SHEETPILE WILL BE DRIVEN TO THE TOP OF THE STRATUM S1.

REV.1

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 0+00 | 2+37 | -4 | AZ 19-700 |
| STRUCTURAL | 2+37 | 5+60 | -18 | AZ 19-700 |
| NON STRUCTURAL | 5+60 | 5+80 | -14 | AZ 19-700 |
| NON STRUCTURAL | 5+80 | 6+64 | -12 | AZ 19-700 |
| STRUCTURAL | 6+64 | 8+64 | -33 | AZ 38-700N |
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |

5. REFER TO SHEET CN-125 AND CN-126 FOR INTERIM GRADE.
6. CONTRACTOR TO RESURVEY TOP OF BARRIER WALL FOLLOWING SURCHARGE REMOVAL AND PROVIDE RESULTS TO THE EOR. THE EOR WILL REVIEW AND DETERMINE IF ANY SMALL LOCALIZED AREAS EXIST WHERE THE TOP OF SHEET IS BELOW THE DESIGN SUBGRADE. IF SUCH AREAS ARE IDENTIFIED THEY WILL BE EVALUATED BY THE ENGINEER AND A FIELD DESIGN CHANGE WILL BE MADE TO ADJUST THE SUBGRADE TO THE TOP OF WALL.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | REVISION |
|---|---|---|---|---|---|
| 2 | 02/25/16 | TDD | TDD | RJR | DCB 054.2 INCREASED LANDSCAPE GRADE (0.25 FEET |
| 1 | 10/10/13 | RJR | SGS | | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM |
| 0 | 06/07/13 | TDD | SGS | | ISSUED FOR CONSTRUCTION |
| | | BY | APVD | | |

© 2016 HONEYWELL INTERNATIONAL INC. ALL RIGHTS RESERVED. THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-201 |
| SHEET | 54 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR54-SN-201 HBW Design Pln Prof.dwg PLOT DATE: Fri, 04 Mar 2016 PLOT TIME: 11:44 AM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET ON CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE
4. DCB 13. THE HYDRAULIC BARRIER HAS BEEN REALIGNED BETWEEN STA 10+12 TO STA 12+50. THE TOP OF WALL HAS ALSO BEEN LOWERED TO EFFECTIVELY INCREASE THE SIZE OF THE UTILITY CORRIDOR ON THE NORTHERN HALF OF STEGMAN BOULEVARD. REFER TO DRAWINGS CN-123 AND CN-124 FOR ASSOCIATED REVISIONS TO THE GEOMEMBRANE GRADING IN THIS LOCATION.

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| NON STRUCTURAL | 8+64 | 9+85 | -6 | AZ 19-700 |
| NON STRUCTURAL | 9+85 | 14+00 | -6 | AZ 19-700 |
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |

5. REFER TO SHEET CN-125 AND CN-126 FOR INTERIM GRADE.
6. CONTRACTOR TO RESURVEY TOP OF BARRIER WALL FOLLOWING SURCHARGE REMOVAL AND PROVIDE RESULTS TO THE EOR. THE EOR WILL REVIEW AND DETERMINE IF ANY SMALL LOCALIZED AREAS EXIST WHERE THE TOP OF SHEET IS BELOW THE DESIGN SUBGRADE. IF SUCH AREAS ARE IDENTIFIED THEY WILL BE EVALUATED BY THE ENGINEER AND A FIELD DESIGN CHANGE WILL BE MADE TO ADJUST THE SUBGRADE TO THE TOP OF WALL.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
3/4/16

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 3 | 02/25/16 | DCB 054.2 INCREASED LANDSCAPE GRADE 0.25 FEET | TDD | SGS |
| 2 | 08/12/14 | DCB 13 HYDRAULIC BARRIER REALIGNMENT | SGS | RJR |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | DR TDD | BY | APVD |
| | | RJR | | BCO |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ. 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

HYDRAULIC BARRIER
PLAN AND PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Cert of Authorization #GA28215000


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-202 |
| SHEET | 55 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR55-SN-202 HBW Design Pln Prof.dwg PLOT DATE: Fri, 04 Mar 2016 PLOT TIME: 11:51 AM




REV.1

| HYDRAULIC BARRIER | STATION BEGINS | STATION ENDS | TOE ELEVATION | SHEET PILE |
|---|---|---|---|---|
| STRUCTURAL | 14+00 | 19+00 | SEE NOTE 4 | AZ 19-700 |
| NON STRUCTURAL | 19+00 | 23+38 | -10 | AZ 19-700 |

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET GN-003, NOTE HB17 AND DETAIL E ON SHEET CN-301 FOR WALL/CAP CONNECTIONS BELOW THE SITE HISTORIC WATER TABLE.
4. REFER TO SHEET CN-125 AND CN-126 FOR INTERIM GRADE.
5. CONTRACTOR TO RESURVEY TOP OF BARRIER WALL FOLLOWING SURCHARGE REMOVAL AND PROVIDE RESULTS TO THE EOR. THE EOR WILL REVIEW AND DETERMINE IF ANY SMALL LOCALIZED AREAS EXIST WHERE THE TOP OF SHEET IS BELOW THE DESIGN SUBGRADE. IF SUCH AREAS ARE IDENTIFIED THEY WILL BE EVALUATED BY THE ENGINEER AND A FIELD DESIGN CHANGE WILL BE MADE TO ADJUST THE SUBGRADE TO THE TOP OF WALL.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 2 | 02/25/16 | DCB 054.2 INCREASED LANDSCAPE GRADE 0.25 FEET | TDD | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS |
| DSGN | | TDD DR RJR | TDD | APVD |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD, BOX 2102, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


HYDRAULIC BARRIER
PLAN AND PROFILE


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Cert of Authorization 24GA28010300

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-203 |
| SHEET | 56 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR56-SN-203 HBW Design Pln Prof.dwg PLOT DATE: Fri, 04 Mar 2016 PLOT TIME: 11:58 AM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-125 AND CN-126 FOR INTERIM GRADE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
3/9/16

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 02/25/16 | DCB 054.2 INCREASED LANDSCAPE GRADE 0.25 FEET | TDD | SGS | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS | SGS |
| | | REVISION | BY | APVD | |
| | | | TDD | RJR | TDD |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


EXISTING SA-7 SCB WALL
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2929
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-204 |
| SHEET | 57 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-125 AND CN-126 FOR INTERIM GRADE.

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 02/25/16 | DCB 054.2 INCREASED LANDSCAPE GRADE 0.25 FEET | TDD | SGS | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | RJR | SGS | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SGS | |
| | | REVISION | BY | APVD | |

TDD RJR TDD

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
SGS

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

EXISTING SA-7 SCB WALL
PLAN AND PROFILE

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2929
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | SN-205 |
| SHEET | 58 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR58-SN-205 SCB Plan and Profile.dwg PLOT DATE: Fri, 04 Mar 2016 PLOT TIME: 2:02 PM

Honeywell RES

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 030.1 **DCB Type:** Minor(a)<br>**Effective Date:** 4/15/16 |
| **Project Location:** SA-6 South<br>**Title:** Final Grade Revisions | **Associated RFI:**<br>☐ Yes: ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.** DCB 030 provided for revision to the Final Grades to allow for a 0.25 foot increase in subgrade elevations in the eastern portions of SA-6S Open Space AOC.


DCB 030.1 relates to the Final Grades in the "Development AOC" south of the Open Space AOC. Both the Open Space AOC and the Development AOC grading is shown on the Final Grade Drawings C-125, C-126 and C-127.

The associated electronic files for the grading will be transmitted as part of this DCB. The Development Plan grading is shown at 1 ft. contours. Due to the relatively "flat" final grades,p 1 ft. contours as shown in the hard copy do not provide details on break points. The electronic files provided as part of this DCB do provide detailed information on the grading. Therefore the electronic files will be used for grading.

The Final Cover Soil types are shown on the Restoration Plan C-128. Sheet C 309 Civil Details has been updated to reflect the use of Skaps 121 as the demarcation layer.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** See description above |
| | **Attachments:** ☑ Yes ☐ No<br>Drawings C-125, C-126, C-127, C-128, C-309 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☐ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Drawings C-125, C-126, C-127, C-128, C-309 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** [signature] **Date:** 4/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | BY | APV'D |
|---|---|---|---|---|
| 2 | 4/15/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | TDD DR RJR CHK TDD APV'D | | SHM |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2828
NJ Certificate of Authorization Number 24GA28019600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-125 |
| SHEET | 30 OF 66 |

SA-7

MATCH LINE SHEET C-127

MATCH LINE SHEET C-125

H C-126 C-301 TYPICAL SA-7 EDGE DETAIL

L C-126 C-302 TEMPORARY CONSTRUCTION FENCE

INSTALL TEMPORARY ROCK OUTLET FILTER (TYP)

AK C-126 C-307

SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005)

AG C-126 C-307

EXISTING SOIL CEMENT BENTONITE WALL, SEE PLAN AND PROFILE SHEETS S-204 THRU S-206

EXISTING SA-7 PERIMETER ROAD RELOCATE AS NECESSARY TO ACCOMMODATE FINAL GRADING AND EROSION CONTROL MEASURES

RELOCATED SA-7 PAVED PERIMETER ROAD

Q C-126 C-303 TYPICAL VEGETATED SWALE

HYDRAULIC BARRIER, SEE PLAN AND PROFILE SHEETS S-201 THRU S-203

AG C-126 C-307

SILTATION FENCE (TYP) (SEE SEDIMENT BARRIERS NOTE 5 ON SHEET G-005)

CB-3
RIM = 7.90
INV OUT = 5.50

T C-126 C-303

INLET FILTER (TYP) AJ C-126 C-307

STORM TRENCH (TYP) U C-126 C-303

INSTALL 186 LF 12" HDPE @ 0.5%

CHAINLINK FENCE ON PRECAST CONCRETE BARRIER (TYP)

M C-126 C-302

INSTALL 77 LF 12" HDPE @ 0.5%

INSTALL 200 LF 12" HDPE @ 0.5%

CB-5
RIM = 6.50
INV. IN = 3.10
INV OUT = 3.00

CHAIN LINK FENCE WITH DOUBLE GATE

J C-126 C-302

STABILIZED CONSTRUCTION ACCESS

AH C-126 C-307

KELLOGG STREET
(80' WIDE R.O.W.)

DROYERS COVE

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

0 20 40 80
SCALE IN FEET

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 2 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 1 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | TDD DR RJR | TDD | BY APVD |

SAMUEL G. SHALLARD
SHM LICENSE NUMBER: 43507
NJ PROFESSIONAL ENGINEER

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND IS LOANED CONDITIONED UPON THE BORROWER'S AGREEMENT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


REMEDIATION FINAL GRADING, DRAINAGE, AND EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd. Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019600

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-126 |
| SHEET | 31 OF 66 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6S\CR31-C-126 Final Grade Plan.dwg PLOT DATE: Mon, 18 Apr 2016 PLOT TIME: 12:02 PM




# DROYERS COVE

NOTES:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

MATCH LINE SHEET C-126

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CADS\ABS\CR32-C-127 Final Grade Plan.dwg PLOT DATE: Mon, 18 Apr 2016 PLOT TIME: 12:05 PM

| | |
|---|---|
| SHEET | 32 OF 66 |
| DWG | C-127 |
| PROJ | 3480-12-0317 |
| DATE | |

VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

REMEDIATION FINAL GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

**Honeywell**
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

| NO. | DATE | REVISION | BY | APVD |
|---|---|---|---|---|
| 3 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 2 | 11/16/15 | DCB 30 FINAL DEVELOPMENT GRADE REVISIONS 0.25' | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |

| DSGN | DR | CHK | APVD |
|---|---|---|---|
| TDD | RJR | TDD | SHM |

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507
4/18/2016

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

NOTE:

1. REFER TO SHEET G-003 AND G-004 FOR GENERAL NOTES.
2. REFER TO SHEET G-002 FOR LEGEND AND
3. EXISTING ASPHALTIC PAVEMENT AREAS TO BE FIELD INSPECTED BY LSRP DURING RESTORATION ACTIVITIES. FINAL HISTORIC FILL CAP IN THESE AREAS MAY INCLUDE CRACK FILLING OR INSTALLING A GRAVEL COVER SYSTEM.




| | | | | |
|---|---|---|---|---|
| 3 | 4/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 2 | 05/06/15 | REVISED EDGE DETAIL | TDD | SGS |
| 1 | 10/11/13 | MODIFIED BARRIER WALL ALIGNMENT | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| NO. | DATE | REVISION | BY | APVD |

DSGN TDD | DR RJR | CHK TDD | APVD SHM

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL

RESTORATION PLAN

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number
24GA28010900

SAMUEL G. SHALLARD
4/18/16
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1"
DATE
PROJ 3480-12-0317
DWG C-128
SHEET 33 OF 66

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


FILE NAME: C:\Donovan\SA-6 South Excavation Limits April 20122013 Excavation Shapes\CR33-C-128 Surface Restoration Plan.dwg PLOT DATE: Mon, 18 Apr 2016 PLOT TIME: 12:17 PM




TYPICAL EDGE DETAIL ABOVE GROUNDWATER TABLE (BO)
NTS
C-121 | C-309





PAVEMENT SECTION DETAIL (BA)
NTS
C-108 | C-309
C-109
C-110





NOTE:
NO HISTORIC FILL SHALL BE PLACED ON SA-7


EXCAVATION AREA (BJ)
NTS
TYP | C-309





HISTORIC FILL CAP PLANTER AREAS (BB)
TYP | C-309




PAVEMENT TRANSITION DETAIL (BL)
NTS
TYP | C-309




EXCAVATION EDGE RESTORATION DETAIL (BM)
NTS
TYP | C-309





BELOW GROUNDWATER

GCL AREAS STA 0+00 TO STA 15+00

TYPICAL EDGE DETAIL - LINER BELOW FINAL SCB ELEVATION (BN)
NTS
C-121 | C-309

| STA | FINAL SCB WALL ELEVATION |
|---|---|
| 0+00 TO 3+22 | 8.75 FEET |
| REMAINING LENGTH | SCB WALL TO BE CUT AT LINER GRADE BUT IN NO CASE SHALL SCB WALL BE CUT LOWER THAN 0.75 FEET ABOVE THE PERIMETER POOL ELEVATIONS |




(SEE SHEET C-121 FOR AREAS BELOW HISTORIC GROUNDWATER TABLE)

TYPICAL CAP COMPONENTS BELOW GROUNDWATER (G)
NTS
TYP | C-309

NOTE:

1. REFER TO GENERAL NOTES SHEET G-003 AND G-004.
2. REFER TO LEGEND AND ABBREVIATIONS SHEET G-002.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 5 | 04/18/16 | DCB 30.1 - REVISED GRADING AND RESTORATION | TDD | SGS |
| 4 | 07/21/15 | REVISED DETAIL BN | RJR | SGS |
| 3 | 05/27/15 | REVISED DETAILS | TDD | SGS |
| 2 | 05/20/15 | REVISED DETAILS | RJR | SGS |
| 1 | 05/05/15 | REVISED DETAIL | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | TDD | SHM |
| DSGN | | DR: TDD | BY: RJR | APVD: SHM |

Honeywell
101 COLUMBIA RD. BOX 2105, MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 SOUTH
SITES 073, 124, 125, 134, 140, AND 163
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL
MISCELLANEOUS DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING.
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | C-309 |
| SHEET | 45 OF 66 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 55 **DCB Type:** Minor(a)<br>**Effective Date:** 5/3/16 |
| **Project Location:** SA-6 | **Associated RFI:** |
| **Title:** Planting Soil Gradations USDA Clarification | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

The laboratory results of all gradations for planting soils shall be presented in terms of the USDA classification system rather than USCS.

The ASTM methodology, which includes hydrometer, remains the same, with the exception that a #270 sieve should be added to align with the USDA classification of silt at 0.05 mm.

The laboratory reports should clearly designate that the classification is based on USDA and any values stated for Gravel/Sand/Silt &Clay should also be calculated based on the USDA analysis.


The Specification values for the Horizon A, Horizon B and Horizon C soils are all defined based on the USDA Soil Classification. When calculating the Sand, Silt and Clay percentage, the Gravel component (% retained on the #10 sieve), should be removed from the calculation.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Otherp | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No<br>USCS and USDA Classification Comparison |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>NA |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 4/20/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

# USCS vs. USDA Particle Size Comparison

## USDA Soil Classification System




## Unified Soil Classification System

OhioEPA

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 054.3 **DCB Type:** Minor(a)<br>**Effective Date:** 5/11/16 |
| **Project Location:** SA-6N | **Associated RFI:** |
| **Title:** Interim Grade Revisions | ☐ Yes, RFI No.: ☐ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

DCB 054 included issuance of a revised subgrade design that included changes resulting from raising the cap grades by 0.25 ft. in the landscaped areas and revisions to utility corridors to reflect the latest CHA utility design.


This change impacted the Geomembrane/Subgrade surface (DCB 054.1), Barrier Wall plan and profiles (DCB 054.2) and the Interim Grades (DCB 054.3)

The two revised interim grade drawings are attached to this DCB. The electronic files for the interim grade are also attached.

This file replaces the CAD file that was provided on May 02, 2016 for "Planning Purposes" and volume calculations. The changes in the file since that time has been limited to smoothing of contours to simplify grading.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>Subgrade was adjusted to increase capacity below the liner. |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** To meet minimum cover requirements the Interim grade also required revision. | **Design Documents Affected:**<br>Drawings CN-125, CN-126 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 5/26/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS BASED ON MINIMAL FILL THICKNESS REQUIREMENTS. FINAL GRADES MAY VARY AFTER CONSTRUCTIBILITY REVIEW.
4. REFER TO APPENDIX K CONCEPTUAL REDEVELOPMENT PLANS (100% REMEDIAL DESIGN REPORT) FOR FUTURE UTILITY ALIGNMENTS AND PRELIMINARY ALTERNATIVE GRADING CONCEPTS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 05/13/16 | TDD | TDD | RJR | TDD |
| 0 | 06/07/13 | TDD | SGS | BY | SGS |

DCB 054.3
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

# INTERIM GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2929
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-125 |
| SHEET | 30 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR30-C-125 Final Grade Drain SESC Plan.dwg PLOT DATE: Fri, 13 May 2016 PLOT TIME: 1:37 PM

NOTES:

1. REFER TO SHEET GN–003 AND GN–004 FOR GENERAL NOTES.
2. REFER TO SHEET GN–002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS BASED ON MINIMAL FILL THICKNESS REQUIREMENTS. FINAL GRADES MAY VARY AFTER CONSTRUCTABILITY REVIEW.
4. REFER TO APPENDIX K CONCEPTUAL REDEVELOPMENT PLANS (100% REMEDIAL DESIGN REPORT) FOR FUTURE UTILITY ALIGNMENTS AND PRELIMINARY ALTERNATIVE GRADING CONCEPTS.

EA8 INTERIM RESTORATION PENDING BULKHEAD RESTORATION CONTOURED TO SHOW POST CR REMEDIATION AND SEEDED

APPROXIMATE LOCATION OF OUTFALL

PIERHEAD AND BULKHEAD LINE AS ADOPTED DECEMBER 9, 1929

HACKENSACK RIVER

GROUNDWATER TREATMENT PLANT (SEE NOTE GN23 ON SHEET GN–003)

1 STORY MASONRY BUILDING

CONSTRUCTION WATER TREATMENT AREA SEE SHEET CN–106

INSTALL INLET PROTECTION (TYP) INLET FILTER DETAIL CN–126 CN–308

INTERIM GRADES TO MEET EXISTING GRADES AFTER DEMOLITION OF SEDIMENTATION BASIN. SEE SEDIMENTATION BASIN NOTES ON SHEET GN–004

TYPICAL VEGETATIVE SWALE CN–126 CN–304

HYDRAULIC BARRIER (SEE PLAN AND PROFILE SHEETS SN–201 THRU SN–203)

FINAL RESTORATION GRADE (TYP)

MATCH LINE SHEET CN–125

TYPICAL PAVED PARABOLIC SWALE CN–126 CN–304

INSTALL ROCK OUTLET FILTER CN–126 CN–308

RELOCATED SA7 PERIMETER ROAD

EXISTING SOIL CEMENT BENTONITE WALL (TYP) (SEE SHEETS SN–204 AND SN–205)

0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
LICENSE NUMBER 43507
NJ PROFESSIONAL ENGINEER

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 05/13/16 | TDD | | RJR | TDD |
| 1 | 09/13/13 | DCB 054.3 | | | |
| 0 | 06/07/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | | |
| | | 09/13/13 | | | |
| | | REVISION | BY | APVD | |
| | | TDD | SGS | SGS | SGS |
| | | RJR | SGS | SGS | |
| | | TDD | SGS | SGS | |

ALL PATENTED AND PATENTABLE FEATURES AND/OR CONFIDENTIAL INFORMATION AND TO USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, N WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

# INTERIM GRADING, DRAINAGE, AND SOIL EROSION SEDIMENT CONTROL PLAN

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2820
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-126 |
| SHEET | 31 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR31-C-126 Final Grade Drain SESC Plan.dwg PLOT DATE: Fri, 13 May 2016 PLOT TIME: 1:38 PM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 054.4 **DCB Type:** Minor(a)<br>**Effective Date:** 5/20/16 |
| **Project Location:** SA-6N | **Associated RFI:** |
| **Title:** Geomembrane Subgrade Revisions - Pump Station #1 Corridor | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description.**

DCB 054 included issuance of a revised subgrade design that included changes resulting from raising the cap grades by 0.25 ft. in the landscaped areas and revisions to utility corridors to reflect the latest CHA utility design.

To accommodate Entact's request to relocate Pump Station #1 (RFI 64) it was necessary to revise the subgrade. The Subgrade was lowered at the new location to accommodate the vault and piping and raised in the original pump station location. An initial revision was made in DCB 054.1.

Following further review it was deemed necessary to lower the geomembrane in this area to provide additional separation between the geomembrane and bottom of the vault.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☑ Other | **Explanation or Reason:**<br>Pump Station #1 relocation: increase subgrade clearance |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Drawing CN-124 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 5/23/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ Yes (b) ☑ No<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.

HACKENSACK RIVER

PIERHEAD AND BULKHEAD LINE AS ADOPTED DECEMBER 9,

1 STORY MASONRY BUILDING

A SERIES OF STRAIGHT LINES WILL BE SET ON THE 12 CONTOUR IN THE SEDIMENTATION BASIN. THE BARRIER WALL (PREVIOUSLY SHOWN AT ELEVATION 12) WILL BE TRIMMED TO ELEVATION 11.5. THE SLOPE AND DISTANCE WILL VARY BETWEEN THE 12 CONTOUR AND THE 11.5 TOP OF SHEET.

CAP LINER TO HYDRAULIC BARRIER WALL EDGE DETAIL. (SEE SHEET CN-516 SECTION B-B)

C CN-124 CN-301 TYPICAL UTILITY CORRIDOR HYDRAULIC BARRIER CROSSING DETAIL WITH GEOFOAM BLOCKS

A CN-124 CN-301 CAP AREA BUILDUP DETAIL (SEE NOTE 3)

MATCH LINE SHEET CN-123

EXISTING SOIL CEMENT BENTONITE WALL

CAP LINER TO SCB WALL EDGE DETAIL. (SEE SHEET CN-516 SECTION A-A)

BF CN-124 SN-301 TYPICAL CONNECTION HYDRAULIC BARRIER WALL TO SCB WALL

SA-7

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. CONTOURS SHOWN ON THIS DRAWING REPRESENT THE TOP OF THE LINEAR LOW DENSITY POLYETHYLENE MEMBRANE (60 MIL) LINER/ TO OF SUBGRADE.
4. CONSERVATION EASEMENT REPRESENTS THE LIMIT OF THE RESTRICTED AREA PER THE CONSENT DECREE.
5. CONTRACTOR TO RESURVEY TOP OF BARRIER WALL FOLLOWING SURCHARGE REMOVAL AND PROVIDE RESULTS TO THE EOR. THE EOR WILL REVIEW AND DETERMINE IF ANY SMALL LOCALIZED AREAS EXIST WHERE THE TOP OF SHEET IS BELOW THE DESIGN SUBGRADE. IF SUCH AREAS ARE IDENTIFIED THEY WILL BE EVALUATED BY THE ENGINEER AND A FIELD DESIGN CHANGE WILL BE MADE TO ADJUST THE SUBGRADE TO THE TOP OF WALL.

0 20 40 80
SCALE IN FEET

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 5 | 05/20/16 | | | | TDD SGS |
| 4 | 02/16/16 | DCB 054.4 PUMP STATION #1 CORRIDOR | | | TDD SGS |
| 3 | 02/01/16 | DCB 054.1 REVISED SED BASIN AND PS#1 SUBGRADE | | | TDD SGS |
| 2 | 02/24/15 | DCB 054 INCREASE LANDSCAPE GRADE 0.25 FEET | | | TDD SGS |
| 1 | 09/13/13 | DCB 007.5 | | | TDD SGS |
| 0 | 06/07/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | | RJR SGS |
| | | ISSUED FOR CONSTRUCTION | | | TDD SGS |
| | | REVISION | | | BY APVD |

TDD RJR TDD SGS

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507


Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950


CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

GEOMEMBRANE GRADING PLAN


amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd Suite 113,
Hamilton, NJ 08619 Phone: (609) 585-2829
NJ Cert of Authorization 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-124 |
| SHEET | 29 OF 70 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.



FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR29-C-124 Geomembrane Grade.dwg PLOT DATE: Fri, 20 May 2016 PLOT TIME: 1:49 PM

DESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** 7.2.2 **DCB Type:** Minor (a)<br>**Effective Date:** 6/6/16 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** GW Extraction System – FM and E&I | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |

**Description:**

DCB-007.1, issued to Entact on 6/12/14, was provided for the trench detail portion of the modified groundwater system design. At the time of issue details for the SA-6N trench were subject to potential further modification.

DCB-007.2, issued to Entact on 11/24/14, provided the details for the SA-6N groundwater collection trenches and associated electrical supply and groundwater discharge piping.

DCB-007.2.1, draft prepared on 9/2/15, provided a revised version of 007.2. DCB-007.2.1 was not issued to Entact. However Entact was verbally briefed on the proposed changes, including elimination of E&I wiring from the scope, the same as for SA-6S. The revisions pertained to the following items:

- Electrical wiring and Instrumentation wire was eliminated
- Conduit sizes and type were updated.
- Conduit was shown terminating outside of the groundwater treatment plant
- Conduit and piping from Pump Station MH#2 was re-routed into the adjacent utility corridor to the west. The re-routing reduced excavation of subgrade and provided a more direct routing now that all discharge is to be routed to the GWTP.

DCB 007.2.2 was triggered by the following several changes in project scope:

- Re-re-routing of the Contingent Groundwater System Discharge for both SA-6N and SA-6S from the JCMUA grit chamber to the new GWTP.
- Revisions to the Cap grading and utility corridors which allowed for elimination of the Cap Drainage Pump Station.
- Running PS#1 FM as a separate line to the GWTP

The following drawings will be re-issued as part of DCB 7.2.2:

Contingent Groundwater Extractions System Plan and Profile and Details

- CN-201
- CN-202
- CN-203
- CN-204
- CN-305 (Groundwater Extraction System Details)
- CN-306 (Groundwater Extraction System Details)
- CN-310 (Groundwater Extraction Trench Details).


Electrical Drawings


- EN-301 (Not for Construction)
- EN-302 (Not for Construction)
- EN-303

It is noted that the 5 piezometric pairs on SA-6N are not included in this DCB. The piezometers are to be installed by Amec Foster Wheeler. Access to each location will be provided by Entact.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☐ Unforeseen or Differing Site Conditions<br>☑ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** : Design changed based on information gathered during construction |
| | **Attachments:** ☑ Yes ☐ No<br>CN-201, CN-202, CN-203, CN-204, CN-305, CN-306, CN-310, EN-301 (Not IFC), EN-302 (Not IFC), EN-303 |
| | Cost Implication: ☑ Yes ☐ No<br>>$50k ☑ Yes ☐ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>CN-201, CN-202, CN-203, CN-204, CN-305, CN-306, CN-310, EN-301 (Not IFC), EN-302 (Not IFC), EN-303 |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** GS **Date:** 6/10/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☑ **Yes (b)** ☐ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. FOR FORCE MAIN PROFILE INFORMATION SEE SHEET CN-204.
4. FINAL PLAN VIEW ALIGNMENT MAY BE ADJUSTED SUBJECT TO THE APPROVAL OF THE ENGINEER TO AVOID OBSTRUCTIONS SUCH AS EXISTING BUILDING FOUNDATIONS, ABANDONED UTILITIES AND PILES.
5. TRENCH INVERT HAS BEEN DESIGNED TO BE ABOVE STRATUM O AND STRATUM D. INVERTS MAY BE ADJUSTED DURING DESIGN DEVELOPMENT OR IN RESPONSE TO OBSERVED FIELD CONDITIONS SUBJECT TO THE APPROVAL OF THE ENGINEER AND GROUNDWATER MODELER.
6. PLACE STONE LOOSE IN GROUNDWATER COLLECTION TRENCH. RUN PLATE COMPACTOR OR EQUAL OVER TRENCH PRIOR TO INSTALLING GEOTEXTILE FABRIC.
7. BACKFILL ABOVE GEOTEXTILE FABRIC MAY BE COMPOSED OF EXCAVATED TRENCH SPOIL OR OTHER MATERIAL THAT CAN BE READILY COMPACTED. WET SOIL OVERSIZED DEBRIS OR OTHER MATERIALS AS DEEMED UNSUITABLE CONSISTENT WITH THE EARTHWORK SPECIFICATION 1.04.B. WILL NOT BE USED. BACKFILL WILL BE PLACED IN LIFTS CONSISTENT WITH THE EARTHWORKS SPECIFICATION 3.12.B.4.
8. FLEXIBLE COUPLINGS SHALL BE FLEXJOINT COUPLING AS MANUFACTURED BY ETHYLENE, LLC OR EQUAL. FLEXIBLE COUPLINGS SHALL HAVE A MINIMUM OF (2) BELLOWS AND BE TEFLON-LINED WITH 316 SS FLANGES (POWER BAKED EPOXY COATING APPLIED) AND VITON CASKETS.
9. CONCRETE ENCASEMENT REQUIRED ON E&I CONDUIT IF BURIAL DEPTH IS LESS THAN 24" OR OTHERWISE NOTED.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | TDD | RJR | TDD | SGS |
| 4 | 06/06/16 | DCB 007.2.2 | | TDD | SGS |
| 3 | 09/02/15 | DCB 007.2.1 | | TDD | SGS |
| 2 | 11/19/14 | DCB 007.2 | | TDD | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | RJR | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD | SGS |
| | | REVISION | | BY | APVD |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ. 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ. 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-201 |
| SHEET | 33 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR33-CN-201-Cont_GWE_Trench.dwg PLOT DATE: Mon, 06 Jun 2016 PLOT TIME: 3:21 PM




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-201 FOR NOTES.
4. BARRIER WALL ALIGNMENT SUBJECT TO FINAL LAYOUT CHANGES.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 4 | 06/06/16 | TDD | TDD | RJR | APVD |
| 3 | 09/02/15 | DCB 007.2.2 | | | |
| 2 | 11/19/14 | DCB 007.2.1 | | | |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | | |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | | |
| NO. | DATE | REVISION | BY | APVD | |
| 4 | 06/06/16 | | RJR | SGS | |
| 3 | 09/02/15 | | TDD | SGS | |
| 2 | 11/19/14 | | TDD | SGS | |
| 1 | 09/13/13 | | RJR | SGS | |
| 0 | 06/07/13 | | TDD | SGS | |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


# CONTINGENT GROUNDWATER EXTRACTION SYSTEM PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-202 |
| SHEET | 34 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. REFER TO SHEET CN-201 FOR NOTES.

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| | | TDD | RJR | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | | TDD | SGS |
| 1 | 09/13/13 | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM | | RJR | SGS |
| 2 | 11/19/14 | DCB 007.2 | | TDD | SGS |
| 3 | 09/02/15 | DCB 007.2.1 | | TDD | SGS |
| 4 | 06/06/16 | DCB 007.2.2 | | TDD | SGS |

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM
PLAN AND PROFILE

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019000

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-203 |
| SHEET | 35 OF 70 |






NOTE:


THE FM FROM MH#1 AND MH#2 OCCUPY THE SAME ALIGNMENT BETWEEN THE GWTP 0+00 AND STN. 7+40. THE FM (S) WILL BE INSTALLED ON THE SAME LINE AND GRADE WITH A NOMINAL 6 INCH PLAN VIEW SEPARATION. AIR RELEASE/LEAK DETECTION, AND WYE CLEANOUTS, FOR THE TWO FM'S SHOULD BE COLLOCATED IN THE SAME 2X2 STRUCTURES BETWEEN 0+00 AND 7+40

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. THE DESIGN OF THE CONTINGENT GROUNDWATER EXTRACTION SYSTEM IS CONCEPTUAL AND HAS BEEN BASED ON THE AVAILABLE HYDROGEOLOGIC INFORMATION. THE DESIGN IS BASED ON A THEORETICAL SCENARIO USING CONSERVATIVE ASSUMPTIONS. HONEYWELL WILL CONTINUE TO EVALUATE PERTINENT INFORMATION GATHERED THROUGH DEWATERING AND OTHER CONSTRUCTION OPERATIONS. THIS INFORMATION WILL BE USED TO CALIBRATE THE GROUNDWATER CAPTURE MODEL, SUBJECT TO RESULTS OF THAT MODEL CALIBRATION AND EVALUATION OF THE IMPACTS ON THE SYSTEM DESIGN HONEYWELL MAY PROPOSE ALTERNATIVE GROUNDWATER EXTRACTION DESIGNS CAPABLE OF MEETING THE CRITERIA STATED IN ARTICLE III A 58 OF THE CONSENT DECREE.




HORIZONTAL SCALE
0 20 40 80
SCALE IN FEET

VERTICAL SCALE
0 2 4 8
SCALE IN FEET

| NO | DATE | DSGN | DR | CHK | REVISION |
|---|---|---|---|---|---|
| 4 | 06/06/16 | TDD | RJR | TDD | DCB 007.2.2 |
| 3 | 09/02/15 | | | | DCB 007.2.1 |
| 2 | 11/19/14 | | | | DCB 007.2 |
| 1 | 09/13/13 | | | | HBW RE-ALIGNMENT ADJACENT TO 72-INCH FM |
| 0 | 06/07/13 | | | | ISSUED FOR CONSTRUCTION |

APVD BY: SGS RJR SGS TDD SGS TDD SGS RJR SGS TDD SGS

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CONTINGENT GROUNDWATER EXTRACTION SYSTEM PLAN AND PROFILE


amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-204 |
| SHEET | 36 OF 70 |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONTINGENT INFORMATION AND ITS USE IS CONDITIONED UPON THE USER'S AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR36-CN-204-Cont_GWE_Trench.dwg PLOT DATE: Mon, 06 Jun 2016 PLOT TIME: 3:34 PM





JUNCTION MANHOLE #1 DETAIL V
NTS STA 4+72.5 CN-201 CN-305





NOTES:

1. USE THUNDERLINE LINK-SEAL TYPE LS 475-C FOR 2"ø PIPELINES AND TYPE LS 425-C FOR 1"ø PIPELINES OR EQUAL AT ALL LEAK DETECTION MANHOLES.
2. USE PRESSURE GAGE AND PROBE ON THE HIGH SIDE OF MH ONLY. BASED ON FORCE MAIN ORIENTATION.
3. USE LOCK-JOINT FLEXIBLE MANHOLE SLEEVE OR KOR-N-SEAL JOINT SLEEVE OR EQUAL AT ALL PENETRATIONS.


TYPICAL PENETRATION W/DOUBLE WALL HDPE PIPE DETAIL W
NTS CN-201 CN-305 CN-305





AIR RELEASE VALVE DETAIL @ EW X
NTS CN-201 CN-305 CN-203 CN-306




JUNCTION MANHOLE #1 @ GWTP AZ
NTS CN-204 CN-305




FLOW METER STRUCTURE DETAIL BG
NTS STA 52+31 CN-201 CN-305




NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. THE INSTALLATION CONTRACTOR SHALL PROVIDE A PERMANENT SIGN INDICATING THAT THE JUNCTION MANHOLE AND THE FLOW METER STRUCTURE IS A CONFINED SPACE ENTRY STRUCTURE.
4. ALL ALUMINUM HATCHES SHALL BE PROVIDED WITH SS HINGES, HOLD OPEN ARMS, AND SPRING ASSIST.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 06/06/16 | RJR | SGS | SGS | SGS |
| 1 | 05/12/16 | RJR | SGS | REO | BY |
| 0 | 06/07/13 | REO | REO | RJR | APVD |

DCB 007.2.2
DCB 7.2
ISSUED FOR CONSTRUCTION
REVISION

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 889 - 2829
NJ Cert of Authorization 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"


| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-305 |
| SHEET | 40 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR40-C-305 Contingent Pump Well Details.dwg PLOT DATE: Mon, 06 Jun 2016 PLOT TIME: 1:50 PM





EXTRACTION WELL PIPE TRENCH OVER CAP
NTS

Y
CN-202 CN-306
CN-304




GROUNDWATER EXTRACTION WELL DETAIL
NTS


AA
CN-201 CN-306
CN-202




NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER, TERMINAL BOX, CONDUIT, OR WIRING.

PIEZOMETER DETAIL
NTS


AB
CN-201 CN-306
CN-202
CN-203




FROM STATION 7+40.82 TO 12+73.82 FROM STATION 0+00 TO 7+40.82.

GROUNDWATER FORCE MAIN PIPE TRENCH OUTSIDE CAP
NTS

Z
CN-202 CN-306
CN-307




NOTE:
PZ-1, 3, 5, 7, AND 9 HAVE NO TRANSDUCER TERMINAL BOX, CONDUIT, OR WIRING.

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 1 | 06/06/16 | REO | RJR | REO | SGS |
| 0 | 06/07/13 | DCB 007 2.2 ISSUED FOR CONSTRUCTION | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR ROAD MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


CONTINGENT GROUNDWATER EXTRACTION SYSTEM DETAILS

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619, (609) 889 - 2829
NJ Cert of Authorization 24GA28019500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-306 |
| SHEET | 41 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6N\100 Percent\CR41-C-306 Extraction Well Details.dwg PLOT DATE: Mon, 06 Jun 2016 PLOT TIME: 1:47 PM





## PIPE PERFORATIONS (CD)

NTS — TYP | CN–310


CONSTRUCTION SEQUENCE

- SET MANHOLE BASE AND RISER SECTIONS.
- EXTEND RISER WITH SURCHARGE AND FILL PLACEMENT.
- PLACE TEMPORARY COVER.
- MEASURE TOP/ BOTTOM ELEVATION POST SURCHARGE.
- REVIEW RISER SECTIONS AND IF NECESSARY ORDER A NEW RISER TO MEET DESIGN GRADE.
- OR ADJUST DESIGN GRADE TO MATCH AVAILABLE RISERS – SUBJECT TO ENGINEERS APPROVAL.





## LINER ANCHOR TO CONCRETE STRUCTURE (CE)

NTS — CN–201 | CN–310; CN–202; CN–203




## TYPICAL ACCESS MANHOLE FINAL CONDITION (CB)

NTS STA=1+55±, AND STA=18+00± — CN–201 | CN–310; CN–203







## ELBOW PIPE CLEANOUT (CF)

NTS — CN–202 | CN–310




## GROUNDWATER EXTRACTION PUMP STATION STA 7+02± & STA 12+50± (CC)


NTS — CN–202 | CN–310; CN–203; CN–204

NOTE:

PUMPS, WIRING, CONTROLS BY OTHERS UNDER SEPERATE CONTRACT.

PARTS LIST

| ITEM | QTY | MANUFACTURER\ PART NO. | DESCRIPTION |
|---|---|---|---|
| 30" X 30" PUMP STATION HATCH | 1 | ej FABRICATION PRODUCT H30303191 OR APPROVED EQUAL | SPRING LOADED ALUMINUM VAULT HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |
| 36" X 50" VALVE VAULT HATCH | 1 | PENNSYLVANIA INSERT CORP STOCK# ATH3050D I#2 OR APPROVED EQUAL | SPRING LOADED ALUMINUM HATCH H20 RATED WITH INSULATION, LOCK BOX, SS HINGES, HOLD OPEN ARM, AND FALL PROTECTION |




## GROUNDWATER TRENCH SURCHARGE CONDITION (CA)

NTS — TYP | CN–310

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO | DATE | REVISION | CHK | DR | APVD |
|---|---|---|---|---|---|
| 4 | 06/06/16 | DCB 007.2.2 | TDD | SGS | SGS |
| 3 | 09/02/15 | DCB 007.2.1 DETAIL CE MODIFIED | TDD | SGS | SGS |
| 2 | 11/19/14 | DCB 007.2 | TDD | SGS | SGS |
| 1 | 05/14/14 | DCB 007 | TDD | SGS | APVD |
| DSGN | | | TDD | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

CIVIL


GROUNDWATER EXTRACTION TRENCH DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2929
NJ Certificate of Authorization Number 24GA28010900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | CN-310 |
| SHEET | 45 OF 70 |

FILE NAME: Z:\Projects\HONEYWELL\JERSEY CITY\Cap Design-SA6-C3D\CAD\SA6-North-South-GW_Extraction_Trench\NCR45-CN-310 Extraction Trench Details.dwg PLOT DATE: Mon, 06 Jun 2016 PLOT TIME: 3:16 PM




ABBREVIATIONS:

| | |
|---|---|
| ø | PHASE |
| A | AMPS |
| AF | AMP FUSE |
| C | CONDUIT |
| CT | CURRENT TRANSFORMER |
| EH | ELECTRIC HANDHOLE |
| EW | EXTRACTION WELL |
| FWE | FURNISHED WITH EQUIPMENT |
| FV | FULL VOLTAGE NON-REVERSING |
| GND | GROUND |
| HP | HORSEPOWER |
| HZ | HERTZ |
| ID | INVERTER DRIVE |
| LT | LEVEL TRANSMITTER |
| LTMF | LIQUID-TIGHT METALLIC FLEXIBLE CONDUIT |
| MLO | MAIN LUGS ONLY |
| NEC | NATIONAL ELECTRICAL CODE |
| P | POLE |
| PIC | PROCESS INDICATING CONTROLLER |
| PVC | POLYVINYL CHLORIDE |
| RGS | RIGID GALVANIZED STEEL |
| SE | SERVICE ENTRANCE |
| TSP | TWISTED SHIELDED PAIR |
| TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| V | VOLTAGE |
| W | WIRE |

NOTES:

1. REFER TO SHEET G-002 FOR LEGEND AND ABBREVIATIONS.
2. REFER TO SHEET G-003 FOR GENERAL NOTES.
3. ALL CONDUITS SHALL BE POLYVINYL CHLORIDE DIRECT BURIAL UNLESS NOTED OTHERWISE.
4. ALL PROPOSED CONDUITS WILL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR. ALL PROPOSED WIRING WILL BE INSTALLED BY OTHERS IN THE FUTURE.
5. PUMP, PUMP CONTROL, AND PUMP STARTER TO BE SUPPLIED AND INSTALLED BY OTHERS IN THE FUTURE.
6. THE CONTRACTOR SHALL INSTALL THE 3"ø PVC SCH 40 CONDUIT FROM THE EXTRACTION WELLS INTO AND INCLUDE THE CONSTRUCTION OF THE EH @ THE GWTP. THE CONDUIT FROM THIS EH TO THE GWTP AND INSIDE WILL BE INSTALLED BY OTHERS IN THE FUTURE.

NOT FOR CONSTRUCTION
Mon, 06 Jun 2016

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | REVISION | CHK | APVD |
|---|---|---|---|---|
| 2 | 05/06/16 | DCB 007.2.2 | TDD | SGS |
| 1 | 09/02/15 | DCB 007.2.1 | TDD | SGS |
| 0 | 06/07/13 | ISSUED FOR CONSTRUCTION | GCP | SGS |
| DSGN | GCP | DR RJR | CHK GCP | APVD BY SGS |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE IDEAS, AND/OR CONFIDENTIAL INFORMATION AND IS CONDITIONED UPON LIMITED USE. IT IS NOT TO BE REPRODUCED THE DRAWING, IN WHOLE OR PART, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY


DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ONE LINE DIAGRAM

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28070900

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-301 |
| SHEET | 67 OF 70 |




EXTRACTION WELL PUMP WIRING DIAGRAM (AN)

NTS TYPICAL FOR ONE LEVEL TRANSDUCER AND ONE EXTRACTION WELL PUMP CONTROL (SEE NOTE 9)


CN-126 | EN-302

NOTE:
ALL 480V WIRING SHALL BE #12 AWG MINIMUM.
CONTROL WIRING SHALL BE #14 AWG MINIMUM

**PUMP, PANEL, LEVEL CONTROL, AND WIRING NOT PART OF THIS CONTRACT**

EXTRACTION WELL PUMP NOTES:

1. PUMP LEVEL CONTROLLER LOCATED IN THE EVEN NUMBERED PIEZOMETERS IS BASED ON MERCOID SERIES MPCJ.
2. LE ELEMENT BASED ON PS-98i MODEL 3C261T WITH FEP INW CABLE BY INSTRUMENTATION NORTHWEST. SEVERAL PUMPS MAY BE CONNECTED IN SERIES TO THE OUTPUT OF ONE LE ELEMENT.
3. ULTRASONIC LOW LEVEL SENSOR BASED ON OMEGA LVU SERIES. MATERIAL SHALL BE PFA OR EQUAL. SECURE CABLE AND SENSOR TO DISCHARGE PIPE AND SET SENSING POINT 3 INCHES MINIMUM ABOVE PUMP INTAKE.
4. PUMP SAFETY SWITCH BASED ON OMEGA MODEL LVCN.
5. PILOT LIGHTS TO BE PUSH TO TEST AS INDICATED.
6. PUMP CONTROL PANEL SHALL BE NEMA 3R WITH LOCKING HASP. SIZED AS REQUIRED FOR EQUIPMENT. MOUNT COMPONENTS ON DIN RAIL OR STANDARD 1/4 DIN MOUNTING HARDWARE. ALL COMPONENTS SHALL BE INTERNAL TO ENCLOSURE.
7. BOND WELL CASING TO GROUND CONDUCTOR.
8. CONNECT PUMP MOTOR TO GROUND CONDUCTOR.
9. WHEN ONE LEVEL TRANSDUCER IS USED TO CONTROL TWO OR THREE EXTRACTION WELL PUMPS, CONNECT EXTRACTION WELL PUMP PIC CONTROLLERS IN SERIES WITH THE ONE TRANSDUCER IN 4-20mA CURRENT LOOP.
10. ALL PANELS WILL BE DEAD FRONT, LOCKABLE AND WITH NO VISIBLE EXTERIOR LIGHTS.




NOTE:
ALL 480V WIRING SHALL BE #12 AWG MINIMUM.
CONTROL WIRING SHALL BE #14 AWG MINIMUM


CAP DRAINAGE PUMP NOTES:

1. WIRE FLOATS FOR PUMP DOWN CONTROL SET RANGE FOR 6 INCHES BETWEEN PUMP ON TO PUMP OFF. SET HIGH LEVEL SWITCH TO BE ACTIVE 6 INCHES ABOVE PUMP START.
2. SECURE FLOATS TO DISCHARGE PIPE.
3. PROVIDE JUNCTION BOX IN SUMP FOR CONNECTION OF FLOATS.
4. FLOAT SWITCH EQUAL TO DWYER RFW.
5. PILOT LIGHTS TO BE PUSH TO TEST AS INDICATED.
6. CONNECT PUMP MOTOR TO GROUND CONDUCTOR.
7. ALL PANELS WILL BE DEAD FRONT, LOCKABLE AND WITH NO VISIBLE EXTERIOR LIGHTS.

CAP DRAINAGE PUMP STATION CONTROL WIRING DIAGRAM (AP)

NTS

EN-302 | EN-302




NOTES:

1. ALL CONDUITS SHALL BE 1" RGS MINIMUM.
2. LOCATE THE PUMP MOTOR STARTER PANEL WITHIN 5' OF THE CAP DRAINAGE PUMP STATION STRUCTURE.

CAP DRAINAGE PUMP STATION CONTROL PANEL DETAIL (AR)

NTS

CN-201 | EN-302
CN-202

NOTES:

1. REFER TO SHEET GN-003 AND GN-004 FOR GENERAL NOTES.
2. REFER TO SHEET GN-002 FOR LEGEND AND ABBREVIATIONS.
3. THE COMBINATION OF THE MOTOR CIRCUIT PROTECTOR AND THE OVERLOAD SHALL BE UL MOTOR COMBINATIONS.

NOT FOR CONSTRUCTION

Mon, 06 Jun 2016

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD |
|---|---|---|---|---|---|
| 2 | 06/06/16 | GCP | RGR | GCP | APVD |
| 1 | 09/02/15 | TDD | SGS | GCP | SGS |
| 0 | 06/07/13 | TDD | SGS | BY | APVD |
| | | | ISSUED FOR CONSTRUCTION | REVISION | |

DCB 007.2.2
DCB 007.2.1

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS


WIRING DIAGRAMS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900


VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-302 |
| SHEET | 68 OF 70 |


THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.




ELECTRICAL HANDHOLE DETAIL (AU)
NTS
CN–105 | EN–303
CN–201
CN–202




PIEZOMETER CONDUIT DETAIL (CN)
NTS
SN–204 | EN–303





**OUTSIDE CAP** (SEE DETAIL CN ON EN–303)

**OVER CAP**

PIEZOMETER INSTRUMENTATION CONDUIT TRENCH (AX)
NTS
CN–201 | EN–303
CN–202
CN–203

NOTE:

1. PROVIDE CONCRETE ENCASEMENT IF CONDUIT IS LESS THAN 24–INCHES BELOW DEVELOPMENT GRADE.
2. INSTALL PULL STRING/WIRE IN E&I CONDUIT FOR INSTALLATION OF PUMPS, WIRING, CONTROLS IN THE FUTURE BY OTHERS.




DUCT WAY NOTES:

1. ENCASED BURIAL REQUIRED IF THE COVER DEPTH IS LESS THAN 24" OR OTHERWISE SPECIFIED.
2. CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS, OR AS SPECIFIED.
3. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAY WITH LESS THAN 24" OF COVER #4@12" OC MIN 2. EXTEND 4' BEYOND ROAD EDGE.
3. MINIMUM COVER TO TOP OF CONCRETE ENVELOPE SHALL BE 24" [610mm].
4. INSTALL IN A 4'–0" MAX WIDTH TRENCH SIMILAR TO DETAIL Z ON C–306.

DUCT BANK DETAILS (AW)
NTS
EN–303

NOTES:

1. REFER TO SHEET GN–003 AND GN–004 FOR GENERAL NOTES.
2. REFER TO SHEET GN–002 FOR LEGEND AND ABBREVIATIONS.

SAMUEL G. SHALLARD
NJ PROFESSIONAL ENGINEER
LICENSE NUMBER 43507

| NO. | DATE | DSGN | DR | CHK | APVD | BY | APVD |
|---|---|---|---|---|---|---|---|
| 2 | 06/06/16 | GCP | RJR | GCP | APVD | TDD | SGS |
| 1 | 09/02/15 | DCB 007.2.2 | | | | TDD | SGS |
| 0 | 06/07/13 | DCB 007.2.1 | | | | GCP | SGS |
| | | ISSUED FOR CONSTRUCTION | | | | | |
| | | REVISION | | | | | |

THIS DRAWING IS THE PROPERTY OF AMEC, INCLUDING ALL PATENTED AND PATENTABLE FEATURES, AND/OR CONFIDENTIAL INFORMATION AND ITS USE IS CONDITIONED UPON THE USERS AGREEMENT NOT TO REPRODUCE THE DRAWING, IN WHOLE OR PART, NOR THE MATERIAL DESCRIBED THEREON, NOR THE USE OF THE DRAWING FOR ANY PURPOSE OTHER THAN SPECIFICALLY PERMITTED IN WRITING BY AMEC.

Honeywell
115 TABOR RD. MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH
SITES 087 AND 088
JERSEY CITY, NEW JERSEY

DRAWING STATUS
100 PERCENT DESIGN DRAWINGS

ELECTRICAL DETAILS

amec
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619
(609) 588 - 2929
www.amec.com
NJ Certificate of Authorization Number
24GA28010500

VERIFY SCALE
BAR IS ONE INCH ON ORIGINAL DRAWING
0 1"

| | |
|---|---|
| DATE | |
| PROJ | 3480-12-0317 |
| DWG | EN-303 |
| SHEET | 69 OF 70 |

Honeywell RES

→ Honeywell.com

PDESIGN CHANGE BULLETIN

| | |
|---|---|
| **Project Name:** Chromium Remedy Study Area 6<br>Jersey City, NJ | **DCB No.:** **Type:** Minor(a)<br>**Effective Date:** 7/14/16 |
| **Project Location:** SA-6 North | **Associated RFI:** |
| **Title:** North Cap - Field Engineered Subgrade Adjustments | ☐ Yes, RFI Nos. ☑ None |
| **Contractor (Subcontractor):** ENTACT | **Project No.:** 3480130377 |


**Description.**

During the course of subgrade construction two field conditions were identified that resulted in the need for minor adjustments to several small localized areas of the subgrade to achieve positive drainage. In one area these field developed changes resulted in a change in elevation of the Construction Control Grid subgrade elevation.

In addition there were several minor changes in the top elevation of the Hydraulic Barrier wall. These changes were made to avoid major changes to the Construction Water Treatment forcemain and to address several locations where the final top elevations of driven sheets were slightly below the design levels. These changes did result in a very small reduction in capacity under the cap and had no impact on the containment and hydraulic requirements of the wall. The changes are so minor they are not readily visible on the hard copy drawings. Revisions were issued to Entact in electronic format and will be incorporated in As Built documentation.

| | |
|---|---|
| **Reason for Change/Modification:**<br>☑ Unforeseen or Differing Site Conditions<br>☐ Design Revision<br>☐ Owner/Client Request<br>☐ Other | **Explanation or Reason:** |
| | **Attachments:** ☑ Yes ☐ No |
| | Cost Implication: ☐ Yes ☑ No<br>>$50k ☐ Yes ☑ No<br>Schedule Implication ☐ Yes ☑ No |
| **Additional Comments:** | **Design Documents Affected:**<br>Construction Control Grid<br>Top of Barrier Wall and Subgrade |
| **Honeywell (AP) Review:**<br>**Individual:** Geoff Shallard **Discipline:** EOR | **Initial:** **Date:** 12/12/16 |
| **(Name / Signature):** | **Does DCB Result in CCO?** ☐ **Yes (b)** ☑ **No**<br>**Date:** |
| **Distribution:** | |

(a) – Major/Minor DCB designation – major DCB's impact cost and/or schedule and may require third party review/approval
(b)– If DCB is to result in a CCO, follow the CCO process and provide a SOW and cost estimate.




153 16.66 GRID POINT

2054 17.00 BREAK POINT

1157 12.31 BOUND POINT

0 10 20 40

SCALE IN FEET

DCB 054.5 – REVISED CONTROL GRID ELEVATIONS 12/12/16

Prepared/Date: RJR 05/12/16
Checked/Date: TDD 05/12/16

NOTE: REFER TO FIGURE 1.3 FOR REVISED GRID POINT ELEVATION SUMMARY TABLE.


Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019300

SA-6 NORTH CONSTRUCTION CONTROL GRID
FIGURE 1 OF 3
Project 3480-13-0377
Figure 1.1

C:\Donovan\GIA- 6 North\2013 Excavation Surfaces\GIA- 6 North Cap Surveys\Figure - Survey Control Grid.dwg Mon, 12 Dec 2016 - 12:46pm tony.donovan




153 16.66 GRID POINT

2054 17.00 BREAK POINT

1157 12.31 BOUND POINT

NOTE: REFER TO FIGURE 1.3 FOR REVISED GRID POINT ELEVATION SUMMARY TABLE.

0 10 20 40
SCALE IN FEET

DCB 054.5 – REVISED CONTROL GRID ELEVATIONS 12/12/16

Prepared/Date: RJR 05/12/16
Checked/Date: TDD 05/12/16

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962

CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28019600

SA-6 NORTH CONSTRUCTION CONTROL GRID
FIGURE 2 OF 3
Project 3480-13-0377
Figure 1.2

C:\Donovan\SA-6 North\2013 Excavation Surfaces\SA-6 North Cap Surveys\Figure - Survey Control Grid.dwg Mon, 12 Dec 2016 - 12:45pm tony.donovan

**DCB 054.5 - REVISED SUBGRADE ELEVATION SUMMARY**

| CONTROL GRID POINT ID | DESCRIPTION | SUBGRADE DESIGN ELEV (FT) | REVISED SUBGRADE DESIGN ELEV (FT) |
|---|---|---|---|
| 160 | GRID | 17.62 | 17.44 |
| 161 | GRID | 17.65 | 17.39 |
| 533 | GRID | 10.17 | 10.88 |
| 1044 | BNDY | 18.03 | 16.59 |
| 1055 | BNDY | 11.84 | 11.43 |
| 1070 | BNDY | 14.78 | 13.85 |
| 1071 | BNDY | 14.27 | 14.01 |
| 1107 | BNDY | 8.55 | 10.75 |
| 1108 | BNDY | 8.50 | 10.75 |
| 1109 | BNDY | 8.86 | 10.75 |
| 1110 | BNDY | 9.63 | 10.75 |
| 1111 | BNDY | 9.76 | 10.75 |
| 1112 | BNDY | 9.94 | 10.75 |
| 1113 | BNDY | 10.18 | 10.75 |
| 1114 | BNDY | 10.43 | 10.75 |
| 1115 | BNDY | 10.68 | 10.75 |
| 1136 | BNDY | 8.98 | 9.65 |
| 1184 | BNDY | 8.50 | 10.75 |

153 16.66 GRID POINT

2054 17.00 BREAK POINT

1157 12.31 BOUND POINT

0 10 20 40
SCALE IN FEET

DCB 054.5 – REVISED CONTROL GRID ELEVATIONS 12/12/16

Prepared/Date: RJR 05/12/16
Checked/Date: TDD 05/12/16

Honeywell
101 COLUMBIA RD., BOX 2105
MORRISTOWN, NJ 07962


CHROMIUM REMEDY
STUDY AREA 6 NORTH
JERSEY CITY, NEW JERSEY
HONEYWELL SITE ID - 37472

amec foster wheeler
Environment & Infrastructure, Inc.
200 American Metro Blvd, Suite 113
Hamilton, NJ, 08619, (609) 689 - 2829
NJ Certificate of Authorization Number 24GA28010900

SA-6 NORTH CONSTRUCTION CONTROL GRID
FIGURE 3 OF 3
Project 3480-13-0377
Figure 1.3

O:\Donovan\SA-6 North\2013 Excavation Surfaces\SA-6 North Cap Surveys\Figure - Survey Control Grid.dwg Mon, 12 Dec 2016 - 12:43pm tony.donovan

**ATTACHMENT Q**
**SA-6 NORTH AND SOUTH SOIL EROSION AND SEDIMENT CONTROL**
**RECORD DRAWING**




Created By: TDD 05/26/17
Checked By: EGC 05/26/17

0 20 40 80
SCALE IN FEET

Honeywell
115 TABOR ROAD
MORRIS PLAINS, NJ 07950

CHROMIUM REMEDY
STUDY AREA 6 NORTH AND SOUTH
JERSEY CITY, NEW JERSEY

amec foster wheeler
Environment & Infrastructure, Inc.
511 Congress Street, Suite 200
Portland, Maine 04104 (207) 775-5401

SOIL EROSION AND SEDIMENT CONTROL
RECORD DRAWING
FIGURE 1

C:\Donovan\SA-6 South Excavation Limits April 2012\2013 Excavation Shapes\SA-6 South Remedial Action Report\SA-6 SESC AB.dwg Fri, 26 May 2017 – 11:46am tony.donovan

**APPENDIX S**

**ADDITIONAL DOCUMENTS**
**(CD ONLY)**

**PART 25 OF 25**

- **Excavation Certification E-Mails**

**ATTACHMENT A-1**
**60 KELLOGG EXCAVATION CERTIFICATION E-MAIL**

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, August 03, 2016 2:00 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E; Shallard, Samuel G.
**Subject:** FW: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Here is SM acknowledgement of 60 Kellogg

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, July 13, 2016 5:29 PM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Morris, John <John.Morris@honeywell.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>; Jeremy.Karpatkin@aporter.com <Jeremy.Karpatkin@aporter.com>; Liza Walsh (LWalsh@TheWalshFirm.com) <LWalsh@TheWalshFirm.com>; Hector Ruiz (HRuiz@TheWalshFirm.com) <HRuiz@TheWalshFirm.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; Kim Hosea (k.hosea@cea-enviro.com) <k.hosea@cea-enviro.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Bill,

The Special Master acknowledges receipt of your June 28, 2016 email and the supporting documentation accompanying the SA-6 South Excavation Complete Submittal for the 60 Kellogg Building Area and your subsequent emails confirming that the white-ish material observed in the excavation was included in the sidewall soil samples collected where residual material was observed for final confirmation and represented in the final post-excavation soil sampling results provided in your June 28 email and where all hexavalent chromium results were reported at less than 20 mg/kg.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, July 12, 2016 11:16 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Lewis, Thomas <tlewis@louisberger.com>; Morris, John <John.Morris@honeywell.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; Jeremy.Karpatkin@aporter.com <Jeremy.Karpatkin@aporter.com>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; Kim Hosea (k.hosea@cea-enviro.com) <k.hosea@cea-enviro.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Steve,

I have reviewed your email question with the Amec field team who observed the excavation and collected the post-excavation sidewall soil samples.
Amec indicates that the whitish material was included in the sidewall soil samples where residual material was observed.
Please let us know if you have any remaining questions on this item.

Regards,
Bill Hague

**William J. Hague P.E.**

Honeywell
Director - Remediation Design & Construction
Corporate HSE&R
115 Tabor Road
Morris Plains, NJ 07950
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Saturday, July 02, 2016 5:22 PM
**To:** Hague, William
**Cc:** RGT Special Master; Lewis, Thomas; Morris, John; JFarrell@jcnj.org; Francis J. Borin; JWatson@jcnj.org; Clifford, Joseph T; Daneker, Michael D.; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); ' (kmillian@tpmlaw.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; Jeremy.Karpatkin@aporter.com; 'Ben Ross (bross@disposalsafety.com)'; Kim Hosea (k.hosea@cea-enviro.com)
**Subject:** RE: SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Bill,

Please see the following regarding the June 28, 2016 Excavation Complete Submittal for the 60 Kellogg Building Area:

The email states that "the post-excavation soil sampling location selection was biased according to field observations and not just geometrically predetermined" and that "Sidewall samples were biased to include residual whitish material if observed." Please confirm, as requested in my June 16 email, that the white-ish material was directly sampled and analyzed to determine whether hexavalent chromium concentrations in this material are above or below 20 ppm.

In addition, your email states: "The excavation was subsequently extended to approximately 14 ft by 14 ft in width and length to remove additional soil exhibiting whitish discolorations". However, as noted in my June 16 email, during my June 14 site visit I observed what appeared to be white-ish material in the southwestern face of the excavation, approximately 2 feet below the surface at what appeared to be the final excavation boundary. If the white-ish material was directly sampled and determined to contain less that 20ppm hexavalent

chromium, then leaving residual material in the excavation is not an issue. However, if the white-ish material was determined to contain hexavalent chromium above 20ppm, please confirm whether or not the observed white-ish material was subsequently removed as part of continued excavation efforts so that no white-ish material confirmed above 20 ppm hexavalent chromium remained visible at the excavation boundaries.

We look forward to your response.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, June 28, 2016 9:45 PM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Lewis, Thomas <tlewis@louisberger.com>; Morris, John <John.Morris@honeywell.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; '(kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; Jeremy.Karpatkin@aporter.com <Jeremy.Karpatkin@aporter.com>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; Kim Hosea (k.hosea@cea-enviro.com) <k.hosea@cea-enviro.com>
**Subject:** SA-6 South Excavation Complete Submittal - 60 Kellogg Building Area

Steve,

We are providing this email notification that our laboratory data validation has been completed, all soil sample results showing concentrations of hexavalent chromium < 20 ppm are now final, thus, the added Excavation Area at 60 Kellogg Street can now be closed out (which is part of the SA-6 South Chromium Remedy).

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of excavation completion covers the work completed on 06/02/16. This submittal includes the excavation around the 60 Kellogg Street Building (Site 125 on SA-6 South) where suspect material had been observed and sampled in accordance with the submittal to All Parties, dated May 17, 2016. We are also addressing your email to Honeywell dated June 16, 2016 with clarification that the post-excavation soil sampling location selection was biased according to field observations and not just geometrically predetermined.

Attachments to the submittal include the Maser Table with bottom and sidewall confirmation points, and an Excavation Bottom Map showing sample locations and excavation limits.

- Initially, Amec personnel collected a soil sample (post demolition of the 60 Kellogg building raised slab) biased to a greenish discoloration in surficial soils identified between timber piles that formerly supported the 60 Kellogg building.
- This initial soil sample confirmed the presence of COPR and resulted in a proposed shallow excavation plan to address these soils by removing an area ~10 ft by 10 ft by 3 ft deep in size around this sample location (as detailed in the May 17, 2016 submittal to the parties).

- On June 2, 2016, the excavation was conducted to depths ranging from approximately 2.9 ft to 4.2 ft Below Ground Surface.
- The bottom and sides of the excavation at the final limits were visually inspected by Amec personnel. All of the original greenish discoloration was removed but some whitish material was observed in several sidewall locations.
- The excavation was subsequently extended to approximately 14 ft by 14 ft in width and length to remove additional soil exhibiting whitish discolorations.
- Five soil samples were collected from the excavation: one from each sidewall and one from the bottom of the excavation. Sidewall samples were biased to include residual whitish material if observed. The bottom sample was located the area where additional suspect material was also observed during excavation.
- This sampling frequency meets the approved frequencies established in the 100% Design.
- Coordinates for Survey of the finished excavation at the bottom and sidewall sample locations are tabulated in the Maser Tables.
- Sample locations are shown on the Entact “As Built” Excavation Figure attached.
- The final post-excavation soil sampling results were as follow:
    - 125-SB-308 <0.55 mg/Kg
    - 125-SB-309 0.66 mg/Kg
    - 125-SB-310 <0.52 mg/Kg
    - 125-SB-311 2.3 mg/Kg
    - 125-SB-312 1.9 mg/Kg
- All hexavalent chromium results were less than 20 mg/kg, thus, no further remediation is necessary.
- Maser collected bottom of excavation points to prepare a topographic Map of the bottom of excavation.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.

Regards,
Bill Hague

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**ATTACHMENT B-2**
**SA-6 SOUTH E-MAIL CERTIFICATIONS OF EXCAVATION COMPLETION**

## Egnaczyk, Steve

**From:** Kevin J. Coakley <KCoakley@connellfoley.com>
**Sent:** Friday, April 25, 2014 8:56 AM
**To:** 'kmillian@tpmlaw.com'; 'aalcorn@tpmlaw.com'; 'eric@golub-isabel.com'; 'kkinsella@decotiislaw.com'; 'Michael D. Daneker (Michael.Daneker@aporter.com)'; 'Jeremy Karpatkin (Jeremy.Karpatkin@aporter.com)'; 'Jeremy Farrell' (JFarrell@jcnj.org)
**Cc:** 'rgtspecialmaster@aol.com'; Sean Jackson (Sean@RosemontAssocs.com); Egnaczyk, Steve; Lewis, Thomas; Liza M. Walsh; Agnes Antonian
**Subject:** Honeywell Excavation Submittals

Dear Counsel:

During Tuesday's Special Master All Parties Meeting, it was agreed that Honeywell would continue to provide notifications to the parties certifying that cells within the SA6 North and South excavation have been completed in accordance with the 100% Design and request an email acknowledgement only from the Special Master that the Special Master is in receipt of the supporting documentation accompanying the notification. The Special Master's technical representative will continue to perform periodic visual inspections of the completed excavation areas prior to backfilling and provide a response to Honeywell's email submittals within 48-hours.

Honeywell will continue to conduct the excavation operations as detailed in the SA-6 South Standard Operating Procedure (SOP) - Confirmation of Excavation Limits, dated March 3, 2014 that provides Honeywell's basis for assessing and demonstrating that the limits of excavation as defined in the 100% Design are being met and documented.

Specifically and as noted in Honeywell's April 17, 2014 Response to Plaintiffs' Comments regarding Excavation of Cells 44-52, Honeywell will:

- continue to collect the survey data necessary to prepare the topographic map as indicated in the first bullet of Section 5.0 in the SOP,
- prepare the topographic map to meet the requirements of Section 02315 Part 3.03 Topographic Surveys, Part C. Post Excavation Survey of the Technical Specifications, and
- provide the topographic survey as part of the final certification.

Honeywell acknowledges that as it is no longer waiting for ICO acknowledgement of the above described progress reports on cell excavation confirmation, and therefore Honeywell will be proceeding at risk as it relates to these specific issues from ICO's perspective, or for that matter, Jersey City's perspective as well. Honeywell will continue to submit these reports to all parties at the same time it transmits them to the Special Master.

Please respond to this email within 48 hours if you do not concur that this description represents the agreement reached at Tuesday's meeting.

**Kevin J. Coakley**

Partner
Connell Foley LLP
85 Livingston Avenue
Roseland, NJ 07068
Office: (973) 535-0500
Direct: (973) 533-4230
Fax: (973) 535-9217

kcoakley@connellfoley.com
www.connellfoley.com
Vcard

STATEMENT OF CONFIDENTIALITY: The information contained in this transmission including any attached documentation is privileged and confidential. It is intended only for the use of the individual or entity named above. If the reader of this message is not the intended recipient, you are hereby notified that any dissemination, distribution or copy of this communication is strictly prohibited. If you have received this communication in error, please notify Connell Foley LLP immediately by replying to this email. Please delete all copies of this message and any attachments immediately.

IRS CIRCULAR 230 DISCLOSURE: As required by U.S. Treasury Regulations governing tax practice, you are advised that any written tax advice contained herein was not intended or written to be used, and cannot be used, by any taxpayer for the purpose of avoiding tax penalties that may be imposed under the Internal Revenue Code.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:41 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA6 South Remedy Implementation

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, November 01, 2013 10:06 AM
**To:** Clifford, Joseph T; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; ' (John.Morris@honeywell.com)'; 'cpravlik@tpmlaw.com'; ' (Michael_Daneker@aporter.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA6 South Remedy Implementation

Joe,

This email responds to your email of October 29, 2013 requesting approval to backfill cells 1 and 2 at the Study Area 6 South excavation. The October 29 email responded to the Special Master's email of October 26 and prior emails, which requested that Honeywell confirm that the excavation areas were completed and provide supporting documents that describe the survey protocol addressing how the excavation was completed, especially in areas where the meadow mat was encountered above the projected excavation depth. The Special Master also requested a document tracking the progress and status of the excavation. In its October 29 submittal Honeywell attached two documents: (1) Excavation Bottom Elevations Plan for the period of 10/22/13 to 10/24/13 and (b) Excavation and Backfill Progress Summary End of October 2, 2013 Plan. The Excavation Bottom Elevations Plan shows that the excavation in Cells 1 and 2 was performed to Stratum D. The October 29, email confirms that the excavation in both cells terminates in Stratum D as visually confirmed by Amec personnel. Amec inspectors certified that the impacted soils in the 100% Design have been removed and that the requirements to allow backfilling have been met. In addition, I observed the conditions of the excavation on Tuesday, 10/29 and then again, with the Special Master on Wednesday, October 30, 2013. The Special Master and his team's visual observations are consistent with Amec's representation that the Stratum D is clearly visible as a continuous layer in these two cells. The Special Master has also received Plaintiffs letter of October 31, 2013 approving Honeywell's request. Based on Honeywell's certified representations in the October 29, 2013 email and the documents attached thereto, the Special Master's observations, and the fact that the Stratum D is well defined and continuous, the Special Master approves backfilling of Cells 1 and 2.

To ensure that in the future the confirmation process is efficient and does not delay the project going forward, the Special Master requests that in addition to the documents provided with the October 29 email, Honeywell include additional information clearly defining the final excavation depths in the cells and, as requested before, drawings showing the extent of the meadow mat. Such information will also support the Excavation Declarations that will be filed with the Court to document compliance with the Consent Order and the 100% Design. While the initial two cells had a clearly defined final depth of excavation for each cell, that is not likely to be the case in the future, especially when the excavation cells become larger. The Special Master suggests that a table (similar to the example shown below) would provide the necessary information to the Special Master and the parties to ensure an efficient and effective review and confirmation. This table should provide a reference to the PDI sample result(s) that established the original depth(s) of excavation for the Excavation Cell or general area, realizing that an explanation would be required if meadow mat was

encountered and the excavation was halted at a shallower depth or if other field conditions impacted achieving the design excavation depth. This table is similar to what was provided during the COPR excavation.

| Excavation Cell | 100% Design PDI Sample Result Depths(s) and sample location(s) | Actual Excavation Depth(s) and reference, for example: bgs, MSL | Comments/Exceptions |
|---|---|---|---|
| 1 | (-) 9.5 ft based on PDI Confirmatory Sample Location XXX-SB-XXX | (-) 4.5 ft. | Excavated to depth of meadow mat at (-) 4.5 ft MSL. |
| 2 | (-) 8.5 ft in Area A *[Areas to be defined in the Excavation Bottom Plan;* (-) 6 ft in Area B | Area A: (-) 9 ft<br>Area B: (-) 8.5 ft | |

The Special Master is looking forward to further discussing these issues at the next technical call. At that time the Special Master would like to address the number of survey points that will be necessary to document the excavation bottom, especially in the larger cells with anticipated varying depths of excavation.

Further, we request that Honeywell prepare for discussion a form of Declaration to be filed with the Court showing excavation completion in accordance with the 100% Design. We would expect that the form of Declaration will be in a format substantially similar to that filed in connection with Study Area 7.

Regards, Steve

Steven J. Egnaczyk
Program Director
THE Louis Berger Group, INC.
350 Eagleview Boulevard |Suite 250 | Exton, PA 19341-1178
Phone: 610.363.5395 | Fax: 610.363.5390
Cell: 610.212.1492
Email: segnaczyk@louisberger.com
http://www.louisberger.com

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Tuesday, October 29, 2013 9:05 PM
**To:** Egnaczyk, Steve; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; ' (John.Morris@honeywell.com)'; 'cpravlik@tpmlaw.com'; ' (Michael_Daneker@aporter.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; Isabelle Procaccino; McWatters, Michael
**Subject:** RE: SA6 South Remedy Implementation

Steve,

I am sending this email on behalf of Honeywell.

As discussed at our weekly meetings, we are at a point of being ready to backfill and approval of the submittal content is critical to moving forward.

Below is a description of completed excavation activities for which we are requesting an acknowledgement in order that we can proceed with backfill.

We are also attaching herein two supporting drawings:

1. Exhibit A - depicts the 156, 15-ft wide cells that comprise the SA-6 South excavation which will be used as a excavation progress chart;
2. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for the first two cells completed as described below.

- *Full scale excavation of Chromium Impacted Materials began on 10/21/2013.*
- *For planning and implementation purposes, the excavation is subdivided into 156, 15 ft wide cells with Cell 1 located near Route 440.*
- *For the period ending 10/24/2013 excavation is complete for Cells 1 and 2.*
- *The excavation in both cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, a bottom-of-excavation confirmatory point is located within Cell 2.*
- *The surveyed coordinates of the bottom-of-excavation confirmatory point are included in the attached figure.*
- *The easterly limit of Cell 1 and the north and south limits of Cells 1 and 2 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*

Honeywell acknowledges that your email includes a request for potential additional information regarding locations where meadow is encountered, we will respond separately to that item.

Please let us know if you have comments or questions on the information contained in this email. Thank you. –Joe

**Joseph T. Clifford, P.E.**
**AMEC Environment & Infrastructure**
**200 American Metro Blvd, Suite 113, Hamilton NJ 08619**
**973-455-4163 direct dial**
**610-505-9315 cell**

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Saturday, October 26, 2013 2:34 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; ' (John.Morris@honeywell.com)'; 'cpravlik@tpmlaw.com'; ' (Michael_Daneker@aporter.com)'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com;

Clifford, Joseph T; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; Isabelle Procaccino; McWatters, Michael; Clifford, Joseph T
**Subject:** SA6 South Remedy Implementation

Bill,

As we discussed earlier this week, please advise when you plan to forward the information Honeywell proposes to provide to the Special Master and the parties to confirm the completion of excavation for delineated excavation cells. We are also expecting a document that will track the progress and status of the excavation (i.e., a drawing delineating the excavation grids similar to the drawing provide for the SA7 COPR Excavation). Recognizing that excavation work is now underway, it is important to get these items to us so the parties and the Special Master have sufficient time to review them without causing delay to your planned schedule to backfill the completed cells. In addition, during this week's site construction meeting there were some new drawings that Honeywell has generated that appear to show the projected extent of the meadow mat within each excavation cell. The presence of the meadow mat in the excavation cells raises a question as to how Honeywell intends to document/address the areas where meadow mat is encountered above the anticipated floor of excavation (especially if the meadow mat was not previously anticipated in such an area). A description of the survey protocol addressing this issue as well as the new drawings that Honeywell has generated would be useful for the parties to have as we follow the implementation of the excavation plan; please confirm when Honeywell can provide these new drawings and survey protocols to the Special Master and Plaintiffs.

Regards, Steve

Steven J. Egnaczyk
Program Director
THE Louis Berger Group, INC.
350 Eagleview Boulevard |Suite 250 | Exton, PA 19341-1178
Phone: 610.363.5395 | Fax: 610.363.5390
Cell: 610.212.1492
Email: segnaczyk@louisberger.com
http://www.louisberger.com

THINK GREEN: Please do not print this email unless absolutely necessary.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc. (LBG), the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:41 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA6 South Remedy Implementation

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, November 08, 2013 10:08 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amec.com>; Mojka, John <John.Mojka@Honeywell.com>; Bills, Stuart B <Stuart.Bills@amec.com>
**Subject:** FW: SA6 South Remedy Implementation

FYI

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, November 08, 2013 3:29 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA6 South Remedy Implementation

Bill,

We are in receipt of your email of November 5 regarding Excavation Bottom Elevations for the period 10-25-13 to 10-31-13 and your notification that your contractor is ready to backfill Excavation Cells 3, 4 and 5. During my site visit on November 5, I observed the excavation area and that Excavation Cells 3, 4, and 5 were fully excavated to the meadow mat. In addition, during our discussion on November 6 you clarified the information shown on the Figure ("Excavation Bottom Elevations, Period 10-25-13 to 10-31-13") and the Table prepared by Maser ("SA-6 South Excavation: Confirmatory Points") that were included in your November 5 submittal. The Special Master looks forward to receiving this figure and table in future submittals revised as we discussed as this will aid the Special Master in evaluating the excavation completion. Please be advised that the Special Master continues to evaluate what the process should be regarding excavation completion/backfill approval and we will be following up with the parties shortly. Recognizing that this part of the site is still within the boundary of the meadow mat the Special Master is comfortable in authorizing the backfill of Excavation Cells 3, 4 and 5.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, November 05, 2013 5:36 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA6 South Remedy Implementation

Steve,

As discussed at our weekly meeting today, we are hereby notifying you that our contractor is ready to backfill Cells 3, 4 and 5 starting on Friday Nov 8.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

Below is a description of completed excavation activities specific for these Cells consistent with the language provided in our description of completed Cells 1 and 2.

- *For the period 10/25/2013 to 10/31/2013 excavation is complete for Cells 3, 4 and 5.*
- *The excavation in all cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, a bottom-of-excavation confirmatory point is located within Cell 3.*
- *The surveyed location of the bottom-of-excavation confirmatory point is included in the attached figure.*
- *The north and south limits of Cells 3, 4 and 5 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*

We are also attaching herein three supporting documents:

1. Excavation Progress Map through October 31, 2013 - depicts the 156, 15-ft wide cells that comprise the SA-6 South excavation and the updated excavation progress chart;
2. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for Cells 3, 4 and 5 which have been completed as described below.
3. Post-Excavation Confirmatory Sample Table Survey 103113 – provides the PDI Sampling Location and updated survey information post-excavation which corresponds to this set of Cells.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:41 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 6 through 9

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, November 15, 2013 11:13 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 6 through 9
**Importance:** High

Bill,

We are in receipt of your email of November 13 and attached Excavation Bottom Map and Post-Excavation Confirmatory Sample Table Survey regarding Excavation Bottom Elevations for the period 11-1-13 to 11-7-13. The November 13 email includes information regarding the excavation procedures and certifies that the excavation met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 6, 7, 8 and 9 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on November 12 and observed the excavation area. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 6, 7, 8 and 9 were fully excavated to the meadow mat. Therefore, the Special Master has no objection to Honeywell's proposal to backfill these cells. The Special Master reiterates the concern raised previously and discussed yesterday on the technical call with Joe Clifford and ICO representatives as it relates to how the depth of excavation points have been identified. As this area is entirely meadow mat, the Special Master is comfortable with Honeywell proceeding with backfill. However, the Special Master still has unresolved questions as it relates to those cells where the depth of excavation will not reach or be defined by the meadow mat. It is our expectation that we can discuss, and hopefully resolve, those issues at Tuesday's meeting.

Regards, Steve

Steven J. Egnaczyk
Program Director
THE Louis Berger Group, INC.
350 Eagleview Boulevard |Suite 250 | Exton, PA 19341-1178
Phone: 610.363.5395 | Fax: 610.363.5390
Cell: 610.212.1492
Email: segnaczyk@louisberger.com
http://www.louisberger.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should

immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, November 13, 2013 8:39 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 6 through 9

Steve,

As a follow up to our weekly meeting yesterday, we are hereby notifying you that our contractor is ready to backfill Cells 6 through 9 starting on Friday Nov 15th.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

Below is a description of completed excavation activities specific for these cells. consistent

- *For the period 11/01/2013 to 11/07/2013 excavation is complete for Cells 6, 7, 8 and 9.*
- *The excavation in all cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, bottom of excavation confirmatory points are located within Cells 6, 7, 8 and 9.*
- *The surveyed location of the bottom of excavation confirmatory points are included in the attached figure.*
- *The location of confirmatory sidewall samples are listed in the PDI. To date none of the PDI confirmatory sidewall sample locations have been encountered.*
- *The north and south limits of Cells 6, 7, 8 and 9 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
-

We are also attaching two supporting documents:

1. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for Cells 6 through 9 which have been completed.
2. Post-Excavation Confirmatory Sample Table Survey 1109713 – provides the PDI Sampling Location and updated survey information post-excavation which corresponds to this set of Cells.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells.

Thank you
Bill Hague

**Honeywell**

## William J. Hague P.E.

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:42 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 10 through 12

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Monday, November 25, 2013 3:50 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 10 through 12
**Importance:** High

Bill,

We are in receipt of your email of November 21 and attached Excavation Bottom Map – 111413, Confirmatory Points Certification - 111413 and Excavation Progress Map – 111413 regarding Excavation Bottom Elevations for the period 11-8-13 to 11-14-13. The November 21 email includes information regarding the excavation procedures and certifies that the excavation met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 10, 11 and 12 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on November 21 and observed the excavation area. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 10, 11 and 12 were fully excavated to the meadow mat. Therefore, the Special Master has no objection to Honeywell's proposal to backfill these cells.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by The Louis Berger Group, Inc., (LBG) the information and statements herein do not constitute a binding commitment or warranty by LBG. LBG assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, November 21, 2013 1:24 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'Rob Antonicello'; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 10 through 12

Steve,

As discussed in our all parties meeting Tuesday, we are hereby notifying you that our contractor is ready to backfill Cells 10 through 12 starting on Friday Nov 22th.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

Below is a description of completed excavation activities specific for these cells.

- *For the period 11/08/2013 to 11/14/2013 excavation is complete for Cells 10, 11 and 12.*
- *The excavation in all cells terminates in Stratum D.*
- *A survey of the bottom is attached.*
- *Based upon the design documentation, bottom of excavation confirmatory points are located within Cells 10, 11 and 12.*
- *The surveyed location of the bottom of excavation confirmatory points are included in the attached figure.*
- *The first confirmatory PDI sidewall sample is identified in Cell 11. The sample location is inside the temporary sheetpile which was driven along the section Kellogg Street Jughandle.*
- *The north and south limits of Cells 10, 11 and 12 consist of sheet pile.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*

We are also attaching three supporting documents:

1. Excavation Bottom Map -includes the surveyed post-excavation bottom elevations for Cells 10 through 12 which have been completed.
2. Post-Excavation Confirmatory Sample Table Survey 111413 – provides the PDI Sampling Location and updated survey information post-excavation which corresponds to this set of Cells.
3. Excavation Progress Map – includes excavation status of the cells as of 111413.

We are in the process of working with Amec and the surveyor on making improvements to the supporting documents as discussed in our meeting and should have those soon.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962

973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:42 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 13 through 16

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Sunday, December 22, 2013 8:07 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 13 through 16
**Importance:** High

Bill,

We are in receipt of your email of December 16 and attached Confirmation Points Certification – 112113, Excavation Bottom Map – 112513 (Rev.1), Excavation Progress Map – 112113, Confirmation Points Certification – 120513, Excavation Bottom Map – 120513 (Rev.1), and Excavation Progress Map – 120513. The December 16 email includes information regarding the excavation procedures and certifies that the excavation met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 13, 14, 15 and 16 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on November 21, November 26, December 3, and December 5 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 13, 14, 15 and 16 were fully excavated to the meadow mat. Therefore, the Special Master has no objection to Honeywell's proposal to backfill these cells.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, December 16, 2013 10:23 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell

Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 13 through 16

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 13 through 16 .

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers two periods:

- 11/15/13 to 11/25/13 - Cells 13 and 14
- 11/26/13 to 12/05/13 - Cells 15 and 16

For ease of review the attachments for each period are grouped together.

1. The bottom of excavation for Cells 13, 14, 15 and 16 was terminated in Stratum D. Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.
2. Excavation Bottom Elevation Figures are included for both periods.
    1. Confirmatory points located within Cells 13 and 14 are shown on the Excavation Bottom Elevation figure for 11/15 to 11/25
    2. Confirmatory Bottom points located within Cells 15 and the Sidewall Samples for Cell 16 are shown on the Excavation Bottom Elevation figure for 11/26 to 12/05. A Reference Confirmatory Point was used for the bottom of Cell 16
3. Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A separate table is included for each period and the Cells which are the subject of the submittal period are highlighted in yellow.
4. The north and south limits of Cells 13, 14, 15 and 16 consist of sheet pile.
5. Sheet pile on the excavation face has been cleaned of visible soil materials.
6. The bottom and lateral limits of each cell were visually inspected by Amec personnel.
7. Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
8. Excavation progress Maps are shown for each period. Excavation is continuing in Cells 17 and 18 as shown in the Excavation Progress Map.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you will be on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction

Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:42 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 17 through 20

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, January 24, 2014 10:58 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 17 through 20
**Importance:** High

Bill,

We are in receipt of your email of January 8, 2014 and the following attachments: Confirmation Points Certification – 121213, Excavation Bottom Map – 121313 (Rev.2), and Excavation Progress Map – 121213. The January 8 email includes information regarding the excavation procedures and certifies that the excavation of Cells 17 through 20 met the 100% Design requirements. Honeywell indicates that the contractor is ready to backfill Excavation Cells 17, 18, 19 and 20 and requests the Special Master's response. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on December 10, December 13, and December 17, 2013 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that Excavation Cells 17 and 18 were fully excavated to the meadow mat and that Excavation Cells 19 and 20 were partially excavated to the meadow mat. For the areas of Excavation Cells 19 and 20 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Map – 121313 (Rev.2)" showing the Excavation Bottom Elevations for the period 12-06-13 to 12-12-13 and "Confirmation Points Certification – 121213" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 19 and 20:

| Excavation Cell No.* | Bottom Target Coordinate (MSL) | Actual Coordinates (of the confirmatory bottom sample survey point) (MSL) |
|---|---|---|
| 19 | 2.4 | 2.0 |
| 20 | 2.4 | 2.0 |

*where meadow mat was not encountered

Honeywell notes on the Confirmation Points Certification table that in establishing the Bottom Target Coordinate for an excavation cell based on the PDI results reported in the 100% Design, an "R" designates a "Reference Confirmatory Point for a designated Bottom Excavation Area" that has not been shown on the Excavation Bottom Figure (i.e., the excavation has not yet reached the cell where the PDI boring was located). In future submittals, it would be helpful if Honeywell

would provide the location or reference the Cell Number of the Reference Point on the Excavation Bottom Figure for reference purposes even if the respective excavation cell where the PDI result is located has not yet been reached.

Based on the information provided by Honeywell in this notification and the discussions held during this week's Special Master All Parties Meeting where Plaintiffs noted no objection, the Special Master has no objection to Honeywell's proposal to backfill these cells.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, January 08, 2014 11:25 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 17 through 20

Steve,

We are providing this email notification that our contractor is read to backfill Cells 17 through 20.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the period 12/06/13 to 12/12/13.

Cells 17, 18, 19 and 20

- The bottom of excavation for Cells 17, 18, was terminated in Stratum D. The majority of the bottom of Cells 19, 20, was terminated in Stratum D. The Southern section of cells 19 and 20 was terminated in Stratum O <20 PPM soils.
- Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.
- An Excavation Bottom Elevation Figure is included for the period.
- Confirmatory points located within Cells 17, 18, 19 and 20 are shown on the Excavation Bottom Elevation figure.
- Confirmatory Sidewall Samples for Cells 18 and 20 are shown on the Excavation Bottom Elevation figure.
- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.
- The northern limits of Cells 17, 18, 19 and 20 consist of sheet pile Barrier Wall. Approximately half of the southern extent of Cell 17 is terminated at the temporary sheetpile. The remainder of cell 17 and

cells 18, 19 and 20 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.

- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- Excavation progress Maps are provided. Excavation is continuing in Cells 21 and 22.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you will be on-site this week to review the progress. Also please note we did upload data on backfill materials yesterday in response to earlier comments

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:43 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 21 through 25

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, March 06, 2014 4:38 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Bill,
Thanks very much for your reply. Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, March 06, 2014 4:36 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Steve
Thanks for your note below. I have reviewed the results with the Amec team for rows 21 through 25 and can confirm that all survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.

Regards
Bill Hague

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Tuesday, March 04, 2014 2:26 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Bill,

We are in receipt of your email of January 28, 2014 and the following attachments: Confirmation Points Certification – 010914 (rev1), Excavation Bottom Elevations Period – 121313 to 010914 (Rev.1), and Excavation Progress Map – 010914. The January 28 email includes information regarding the excavation procedures and certifies that the excavation of Cells 21 through 25 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 21, 22, 23, 24 and 25 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on December 17, 19, 24 and 31, 2013 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 21 through 25 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevation of the meadow mat. For the areas of Excavation Cells 21 through 25 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 121313 to 010914 (Rev.1)" showing the Excavation Bottom Elevations for the period 12-13-13 to 1-09-14 and "Confirmation Points Certification – 010914" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 21 and 25:

| Excavation Cell No.* | Bottom Target Coordinate (MSL) | Actual Coordinates (of the confirmatory bottom sample survey point) (MSL) |
|---|---|---|
| 21 | 2.4 | 1.9 |
| 22 | 2.4 | 2.0 |
| 22 | 1.8 | -0.1 |
| 23 | 2.4 | -1.9 |
| 24 | 2.4 | 2.1 |
| 25 | 1.6 | 0.4 |

*where meadow mat was not encountered

In addition, the Special Master acknowledges Plaintiffs' February 21, 2014 email regarding excavation of cells 21-29 where Plaintiffs noted they have no further comments regarding the excavation of cells 21-29 and agreed that cells 21-29 have been excavated to the appropriate depth and may be backfilled.

The Special Master has no objection to Honeywell's proposal to backfill Cells 21 through 25, subject to Honeywell confirming by email that it agrees that the following statement, inserted in its subsequent Excavation Completion Reports, also applies to these cells (numbers 21 thru 25):

"All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered."

Please confirm via email.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, January 28, 2014 2:02 PM

**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; Dfanciullo@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 21 through 25

Steve
Apologies to all, I had the incorrect attachments on the initial email. Correct attachments are provided here.
Thanks
Bill

---

**From:** Hague, William
**Sent:** Tuesday, January 28, 2014 1:35 PM
**To:** 'Egnaczyk, Steve'
**Cc:** 'RGT Special Master'; 'Kevin J. Coakley (KCoakley@connellfoley.com)'; "Liza M. Walsh' (LWalsh@connellfoley.com)'; "AGNES ANTONIAN' (AAntonian@connellfoley.com)'; 'Lewis, Thomas'; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; 'JFarrell@jcnj.org'; 'Dfanciullo@jcnj.org'; 'David Isabel'; 'Eric Tomaszewski'; 'Francis J. Borin'; 'Clifford, Joseph T'; 'KKINSELLA@decotiislaw.com'; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; 'McWatters, Michael'; 'JWatson@jcnj.org'
**Subject:** SA-6S : Excavation Completion in Cells 21 through 25

Steve,

We are providing this email notification that our contractor is read to backfill Cells 21 through 25.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the period: 12/13/13 to 01/09/14 - Cells 21, 22, 23, 24 and 25.

- *The majority of the bottom of Cells 21, 22, 23, 24 and 25 were terminated in Stratum D. The Southern limit of cells 21, 22, 23, 24 and 25 were terminated in Stratum O <20 PPM soils.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *An Excavation Bottom Elevation Figure is included for the period.*
- *Confirmatory Bottom Points located within Cells 21, 22, 23, 24 and 25 are shown on the Excavation Bottom Elevation figure.*
- *A Confirmatory Sidewall Sample for Cells 22 and 25 is also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.*
- *The northern limits of Cells 21, 22, 23, 24 and 25 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 21, 22, 23, 24 and 25 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*

- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps are provided. Excavation is continuing in Cells 26, 27, and 28.*

Note that we are also preparing a PDI location map for the SA-6 South area as requested by Kim Hosea at the last Special Master All Hands mtg and should have this available tomorrow which we will release with the next cell excavation summary email..

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 26 through 29

-----Original Message-----
From: Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
Sent: Friday, March 07, 2014 5:54 PM
To: Hague, William
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; (kmillian@tpmlaw.com); Morris, John (MTO); cpravlik@tpmlaw.com; Daneker, Michael; DelisleB@jcnj.org; Aalcorn@tpmlaw.com; MWeaver@tpmlaw.com; Jeremy.Karpatkin@aporter.com; JFarrell@jcnj.org; David Isabel; Eric Tomaszewski; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; Ben Ross (bross@disposalsafety.com); Bruce A. Bell; Kim Bell Hosea (k.bell@cea-enviro.com); McWatters, Michael; JWatson@jcnj.org
Subject: Re: SA-6S : Excavation Completion in Cells 26 through 29

Bill,
Thanks very much.
Steve

Sent from my iPhone

On Mar 7, 2014, at 5:39 PM, "Hague, William"
<william.hague@honeywell.com<mailto:william.hague@honeywell.com>> wrote:

Steve
To follow up on your email below. We confirm that all survey points in the excavation cells 26 through 29 were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.

Please contact me if there are any additional questions.

Regards
Bill Hague

From: Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
Sent: Friday, March 07, 2014 2:04 PM
To: Hague, William
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com<mailto:KCoakley@connellfoley.com>); 'Liza M. Walsh' (LWalsh@connellfoley.com<mailto:LWalsh@connellfoley.com>); 'AGNES ANTONIAN' (AAntonian@connellfoley.com<mailto:AAntonian@connellfoley.com>); Lewis, Thomas; '(kmillian@tpmlaw.com<mailto:kmillian@tpmlaw.com>)'; Morris, John (MTO); 'cpravlik@tpmlaw.com<mailto:cpravlik@tpmlaw.com>'; Daneker, Michael; 'DelisleB@jcnj.org<mailto:DelisleB@jcnj.org>'; 'Aalcorn@tpmlaw.com<mailto:Aalcorn@tpmlaw.com>'; 'MWeaver@tpmlaw.com<mailto:MWeaver@tpmlaw.com>';

'Jeremy.Karpatkin@aporter.com<mailto:Jeremy.Karpatkin@aporter.com>'; JFarrell@jcnj.org<mailto:JFarrell@jcnj.org>; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com<mailto:KKINSELLA@decotiislaw.com>; 'Ben Ross (bross@disposalsafety.com<mailto:bross@disposalsafety.com>)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com<mailto:k.bell@cea-enviro.com>)'; McWatters, Michael; JWatson@jcnj.org<mailto:JWatson@jcnj.org>
Subject: RE: SA-6S : Excavation Completion in Cells 26 through 29
Importance: High

Bill,

We are in receipt of your email of January 29, 2014 and the following attachments: Confirmation Points Certification – 011614 (rev1), Excavation Bottom Elevations Period – 011014 to 011614 (Rev.1), and Excavation Progress Map – 011614. The January 29 email includes information regarding the excavation procedures and certifies that the excavation of Cells 26 through 29 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 26, 27, 28 and 29 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on December 31, 2013 and January 7, 9 and 14, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 26 through 29 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevations of the meadow mat. For the areas of Excavation Cells 26 through 29 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 011014 to 011614 (Rev.1)" showing the Excavation Bottom Elevations for the period 1-10-14 to 1-16-14 and "Confirmation Points Certification – 011614" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 26 through 29:

Excavation Cell No.*

Bottom Target Coordinate – based on PDI
(MSL)

Bottom Target Coordinate – based on Predetermined Bottom Elevations1
(MSL)

Actual Coordinates
(of the confirmatory bottom sample survey point)
(MSL)

26

1.6

0.4

0.3**

27

1.6

0.4

0.4**

28

1.6

0.4

0.2

29

3.5

2.1

2.1**

*where meadow mat was not encountered
**elevation based on Surveyed Center Point
1 Corresponds with the 9 “standardized” excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

Honeywell also provided confirmation that the southern limit of excavation of cells 26, 27, 28, and 29 terminates at the less than (“<”)20 ppm line (delineated by Honeywell) at the bottom of excavation and the cells are cut back at a stable slope beyond the 20ppm line.

In addition, the Special Master acknowledges Plaintiffs' February 21, 2014 email regarding excavation of cells 21-29 where Plaintiffs noted they have no further comments regarding the excavation of cells 21-29 and agreed that cells 21-29 have been excavated to the appropriate depth and may be backfilled.

The Special Master has no objection to Honeywell's proposal to backfill Cells 26 through 29, subject to Honeywell confirming that it agrees that the following statement, inserted in its subsequent Excavation Completion Reports, also applies to these cells (numbers 26 thru 29):

"All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered."

Please confirm via email.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, “LB”), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

From: Hague, William [mailto:william.hague@honeywell.com]

Sent: Wednesday, January 29, 2014 2:27 PM
To: Egnaczyk, Steve
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com<mailto:KCoakley@connellfoley.com>); 'Liza M. Walsh' (LWalsh@connellfoley.com<mailto:LWalsh@connellfoley.com>); 'AGNES ANTONIAN' (AAntonian@connellfoley.com<mailto:AAntonian@connellfoley.com>); Lewis, Thomas; ' (kmillian@tpmlaw.com<mailto:kmillian@tpmlaw.com>)'; Morris, John (MTO); 'cpravlik@tpmlaw.com<mailto:cpravlik@tpmlaw.com>'; Daneker, Michael; 'DelisleB@jcnj.org<mailto:DelisleB@jcnj.org>'; 'Aalcorn@tpmlaw.com<mailto:Aalcorn@tpmlaw.com>'; 'MWeaver@tpmlaw.com<mailto:MWeaver@tpmlaw.com>'; 'Jeremy.Karpatkin@aporter.com<mailto:Jeremy.Karpatkin@aporter.com>'; JFarrell@jcnj.org<mailto:JFarrell@jcnj.org>; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com<mailto:KKINSELLA@decotiislaw.com>; 'Ben Ross (bross@disposalsafety.com<mailto:bross@disposalsafety.com>)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com<mailto:k.bell@cea-enviro.com>)'; McWatters, Michael; JWatson@jcnj.org<mailto:JWatson@jcnj.org>
Subject: RE: SA-6S : Excavation Completion in Cells 26 through 29

Steve,

We are providing this email notification that our contractor is read to backfill Cells 26 through 29.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the period: 01/10/14 to 01/16/14 - Cells 26, 27, 28 and 29.

Ø The majority of the bottom of Cells 26, 27, 28, and 29 were terminated in Stratum D. The Southern limit of cells 26, 27, 28, and 29 were terminated in Stratum O <20 PPM soils.

Ø Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.

Ø An Excavation Bottom Elevation Figure is included for the period.

Ø Confirmatory Bottom Points located within Cells 26, 27, 28, and 29 are shown on the Excavation Bottom Elevation figure.

Ø A Confirmatory Sidewall Sample for Cell 28 is also shown on the Excavation Bottom Elevation figure.

Ø Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.

Ø The northern limits of Cells 26, 27, 28, and 29 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 26, 27, 28, and 29 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.

Ø Sheet pile on the excavation face has been cleaned of visible soil materials.

Ø The bottom and lateral limits of each cell were visually inspected by Amec personnel.

Ø Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.

Ø Excavation progress Maps are provided. Excavation is continuing in Cells 30 and 31.

Note that this submittal includes the additional PDI Reference Bottom Sample Location Map for SA-6 South requested during the January 21, 2014 SM Meeting. This location map corresponds to the Figure presented depicting the 41 individual color-coded bottom excavation areas within SA-6 South, and the Reference Boring Summary Table identifying the coordinates and the corresponding Cell location previously provided to the parties.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

Honeywell
William J. Hague P.E.
Director - Remediation Design & Construction Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com<mailto:william.hague@honeywell.com>

_____
The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 30 through 37

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Monday, March 10, 2014 10:32 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 30 through 37

Bill,
Thanks very much. The additional figures you provided record the progress of excavation for Cells 30-35. Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, March 10, 2014 10:23 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 30 through 37

Steve,

We believe your question arises from the fact that we submitted a single email package of tables and supporting figures for several weekly periods.

I have asked Amec to provide just the original Excavation Bottom Map for each of the four weekly periods which document the surveying for Cells 30 through 37. These survey maps are attached for weeks ending 01/23/14 (Cells 30 and 31), 01/30/14 (Cells 32 and 33), 02/06/14 (Cells 34 and 35), and 02/13/14 (Cells 36 and 37).

Please let me know if you have any other questions.

Regards,
Bill Hague

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, March 07, 2014 2:11 PM
**To:** Hague, William

**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 30 through 37

Bill,

We are in receipt of your email of February 28, 2014 and the following attachments: Confirmation Points Certification – 021314, Excavation Bottom Elevations Period – 020914 to 021314, and Excavation Progress Maps – 012314, – 013014, – 020614, and– 021314. The February 28 email includes information regarding the excavation procedures and certifies that the excavation of Cells 30 through 37 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 30, 31, 32, 33, 34, 35, 36 and 37 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on January 16, 23, 28, 30, and February 4 and 11, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 30 through 37 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevations of the meadow mat. For the areas of Excavation Cells 30 through 37 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 020914 to 021314" showing the Excavation Bottom Elevations for the period 2-9-14 to 2-13-14 and "Confirmation Points Certification – 021314" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 30 through 37:

| Excavation Cell No.* | Bottom Target Coordinate – based on PDI (MSL) | Bottom Target Coordinate – based on Predetermined Bottom Elevations[1] (MSL) | (of the c |
|---|---|---|---|
| 30 | 3.5 | 2.1 | |
| 31 | 3.5 | 2.1 | |
| 32 | 3.5 | 2.1 | |
| 33 | 3.5 | 2.1 | |
| 34 | 3.5 | 2.1 | |
| 35 | 3.5 | 2.1 | |
| 36 | 3.5 | 2.1 | |
| 37 | 3.5 | 2.1 | |

*where meadow mat was not encountered

**elevation based on Surveyed Center Point

[1] Corresponds with the 9 "standardized" excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

Please note Figure: "Excavation Bottom Elevations Period – 020914 to 021314" appears to show current excavation to Stratum D (gray shading) only in Excavation Cells 36 and 37 and Excavation Cells 30 through 35 with cross-hatching depicting "Previously Submitted Data". However, the Special Master is not aware of a previous submittal showing Cells 30 through 35 with gray shading denoting being excavated to Stratum D and Table: "Confirmation Points Certification – 021314"reports that Stratum D was reached in portions of Excavation Cells 30 through 37. Please confirm whether the Figure is correct.

Honeywell also provided confirmation that the southern limit of excavation of cells 30 through 37 terminates at the less than ("<")20 ppm line (delineated by Honeywell) at the bottom of excavation and [the cells] are cut back at a stable slope beyond the 20ppm line.

In addition, the Special Master acknowledges Plaintiffs' March 5, 2014 correspondence regarding excavation of cells 30-39 where Plaintiffs noted they believe that Honeywell has excavated cells 30 through 39 to the appropriate depth.

Following confirmation of the question raised above regarding the depiction of areas excavated to the meadow mat, the Special Master has no objection to Honeywell's proposal to backfill Cells 30 through 37.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, February 28, 2014 10:29 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 26 through 29

Steve,

We are providing this email notification that our contractor is read to backfill Cells 30 through 37.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following individual periods:

01/17/14 to 01/23/14 - Cells 30 and 31
01/24/14 to 01/30/14 – Cells 32 and 33
01/31/14 to 02/06/14 – Cells 34 and 35
02/07/14 to 02/13/14 – Cells 36 and 37

- *The majority of the bottom of Cells 30 through 37 were terminated in Stratum D. The Southern limit of cells 30 through 37 were terminated in Stratum O <20 PPM soils. Area 4 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *An Excavation Bottom Elevation Figure is included for Cells 30 through 37.*
- *Confirmatory Bottom Points located within Cells 30 through 37 are shown on the Excavation Bottom Elevation figure.*
- *A Confirmatory Sidewall Sample for Cell 31, 32,33, and 35 are also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 30 through 37.*

- *The northern limits of Cells 30 through 37 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 30 and 37 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps for each grouping of cells are provided*
- *Excavation is continuing in Cells 38 and 39.*
- *Amec confirms that all survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Note that this submittal includes the additional "four corner points" identifying the surveyed locations and elevations of excavation bottoms which were completed above the meadow mat consistent with our comment responses to the parties.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:43 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 38 and 39

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, March 07, 2014 2:19 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 38 and 39

Bill,

We are in receipt of your email of March 3, 2014 and the following attachments: Confirmation Points Certification – 022014, Excavation Bottom Elevations Period – 021414 to 022014, and Excavation Progress Map – 022014. The March 3 email includes information regarding the excavation procedures and certifies that the excavation of Cells 38 and 39 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 38 and 39 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on February 11 and 18, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 38 through 39 were partially excavated to the meadow mat and the attached table and survey elevations report the survey elevations of the meadow mat. For the areas of Excavation Cells 38 and 39 that were not excavated to the meadow mat, Honeywell provided the attachment "Excavation Bottom Elevations Period – 021414 to 022014" showing the Excavation Bottom Elevations for the period 2-14-14 to 2-20-14 and "Confirmation Points Certification – 022014" that compares the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation that shows the following for Excavation Cells 38 and 39:

| Excavation Cell No.* | Bottom Target Coordinate – based on PDI (MSL) | Bottom Target Coordinate – based Predetermined Bottom Elevations[1] (MSL) | Actual Coordinate (of the confirmatory bottom samp (MSL) |
|---|---|---|---|
| 38 | 3.5 | 2.1 | 2.1 |
| 39 | 3.5 | 2.1 | 2.0 |

*where meadow mat was not encountered

[1] Corresponds with the 9 "standardized" excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

Honeywell also provided confirmation that the southern limit of excavation of cells 38 and 39 terminates at the less than ("<")20 ppm line (delineated by Honeywell) at the bottom of excavation and [the cells] are cut back at a stable slope beyond the 20ppm line.

In addition, the Special Master acknowledges Plaintiffs' March 5, 2014 correspondence regarding excavation of cells 30-39 where Plaintiffs noted they believe that Honeywell has excavated cells 30 through 39 to the appropriate depth.

The Special Master has no objection to Honeywell's proposal to backfill Cells 38 and 39.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, March 03, 2014 8:03 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 38 and 39

Steve,

We are providing this email notification that our contractor is read to backfill Cells 38 and 39.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following individual period: 02/14/14 to 02/20/14 – Cells 38 and 39

Please note that we will be sending to your attention later today the SOP you requested for excavation depth/ survey confirmation.

- *The majority of the bottom of Cells 38 and 39 were terminated in Stratum D. The Southern limit of cells 38 and 39 were terminated in Stratum O <20 PPM soils. Area 4 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *Excavation Bottom Elevation Figures are included for each of the cell groupings noted above.*
- *Confirmatory Bottom Points located within Cells 38 and 39 are shown on the Excavation Bottom Elevation figures.*
- *A Confirmatory Sidewall Sample for Cell 39 is also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 38 and 39.*
- *The northern limits of Cells 38 and 39 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 38 and 39 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*

- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps for Cells 38 and 39. Excavation is continuing in Cells 40 and 41.*
- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Note that this submittal includes the additional language regarding certification that elevations of excavation bottoms were at or below design excavation elevations and representative of final excavation complete grade(s) throughout the portion of cells where we did not encounter Stratum D.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 40 through 43

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, March 28, 2014 4:21 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 40 through 43

Bill,

We are in receipt of your email of March 23, 2014 and the following attachments: Confirmation Points Certification – 022714 and Confirmation Points Certification – 030614 containing the Confirmation Points Certification Tables and the following figures: Excavation Bottom Elevations - Period 022114 to 022714, Excavation Bottom Elevations Period - 022814 to 030614, Excavation Progress Map – 022714, and Excavation Progress Map – 030614. The March 23 email includes information regarding the excavation procedures and certifies that the excavation of Cells 40 through 43 met the 100% Design requirements. Honeywell indicated that the contractor is ready to backfill Excavation Cells 40 through 43 and requests the Special Master's acknowledgment of the notification. The Special Master has reviewed the documents provided by Honeywell and his representatives visited the site on February 18 and 25 and March 4 and March 11, 2014 and observed the excavation areas. Based on our visual observations and the documentation provided by Honeywell it appears that portions of Excavation Cells 40 through 43 were excavated to the meadow mat and the attached tables and survey elevations report the final survey elevation of the meadow mat. For the areas of Excavation Cells 40 through 43 that were not excavated to the meadow mat, Honeywell provided the following figures and tables: Excavation Bottom Elevations Period – 022114 to 022414 (Figure), Excavation Bottom Elevations Period – 022814 to 030614 (Figure) and ENTACT Letters of Transmittal dated March 11, 2014 (re: Survey Data and Verification – Cells 40 and 41) and March 14, 2014 (re: Survey Data and Verification – Cells 42 and 43) that compare the Bottom Target Coordinates (based on PDI) versus the Actual Excavation Elevation and the Bottom Target Coordinates based on the Predetermined Bottom Elevations versus the Surveyed Center Point Elevation that shows the following for Excavation Cells 40 through 43:

| Excavation Cell No.* | Reference Table 1.2 | | Referenc | |
|---|---|---|---|---|
| | Bottom Target Coordinate – based on PDI (MSL) | Actual Coordinates (of the confirmatory bottom sample survey point) (MSL) | Bottom Target Coordinate – based Predetermined Bottom Elevations** (MSL) | T |
| 40 | 1.7 | 0.0 | 0.4 | |
| 41 | 0.4 | 0.1 | 0.4 | |
| 42 | 0.4 | 0.1 | 0.4 | |

| | | | |
|---|---|---|---|
| 43 | 0.5 | 0.1 | 0.4 |

*where Stratum D (meadow mat) was not encountered

** Correspond to the 9 “standardized” excavation intervals shown on Figure 4: SA-6 South Color Coded Excavation with Reference Samples, 1/28/14.

In addition, Honeywell confirmed in the email that “All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.” In addition, the ENTACT transmittals include a verification that Maser Consulting, P.A. (“Maser)has surveyed the bottom of excavations and that the final excavation grade(s) are at or below the design excavation grades throughout the corresponding excavation cells and a certification from Maser that the elevations, with their corresponding date obtained, of the Confirmatory Points depicted in Table 1, Center Points in Table 2, Sidewall Confirmatory Sidewall Points Table 3 and Bottom of Excavation topographic spot elevations are correct, and representative of the as-built post-excavation grades throughout the corresponding excavation cells.

Honeywell also provided confirmation that the Southern Limit of excavation of Cells 40, 41, 42, and 43 terminate at the less than (“<”)20 ppm line (delineated by Honeywell) at the bottom of excavation and [the cells] are cut back at a stable slope beyond the 20ppm line and that Standardized Excavation Interval - Area 7 was excavated down to Stratum D.

Lastly, the Special Master acknowledges Plaintiffs' March 28, 2014 email regarding excavation of cells 40-43 where Plaintiffs noted they believe cells 40 through 43 have been excavated to the appropriate depth.

The Special Master has no objection to Honeywell's proposal to backfill Cells 40 through 43.

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, “LB”), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, March 23, 2014 7:33 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 40 through 43

Steve,

We are providing this email notification that our contractor is read to backfill Cells 40, 41, 42 and 43.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following individual periods:

02/21/14 to 02/27/14 – Cells 40 and 41
02/28/14 to 03/06/14 – Cells 42 and 43

- *The majority of Cells 40 and 41 were terminated in Stratum D. Approximately half of the bottom of Cells 42 and 43 were terminated in Stratum D. The Southern limit of cells 40, 41, 42 and 43 were terminated in Stratum O <20 PPM soils. Area 7 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft.*
- *The Excavation Bottom Elevation Figures is included for the cells noted above.*
- *Confirmatory Bottom Points located within Cells 40, 42 and 43 are shown on the Excavation Bottom Elevation figures.*
- *Confirmatory Sidewall Samples for Cell 40 and 42 are also shown on the Excavation Bottom Elevation figures.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 40 and 41 and Cells 42 and 43 for each of the weekly periods.*
- *The northern limits of Cells 40, 41, 42 and 43 consist of sheet pile Barrier Wall. The Southern Limit of excavation of Cells 40, 41, 42 and 43 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation progress Maps for each grouping are provided. Excavation is continuing in Cells 44 through 48.*
- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Note that this submittal includes the additional language regarding certification that elevations of excavation bottoms were at or below design excavation elevations and representative of final excavation complete grade(s) throughout the portion of cells where we did not encounter Stratum D.

Please let us know if you have comments or questions on the proposed backfill schedule for these cells. We understand you were on-site this week to review the progress.

Thank you
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, March 06, 2017 10:00 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA6South excavation of cells 44-52

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

---

**From:** Karpatkin, Jeremy C. [mailto:Jeremy.Karpatkin@apks.com]
**Sent:** Monday, March 06, 2017 9:58 AM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Subject:** FW: SA6South excavation of cells 44-52

---

Jeremy C. Karpatkin
**Arnold & Porter Kaye Scholer LLP**
601 Massachusetts Ave., NW | Washington | DC 20001-3743
T: +1 202.942.5564 | F: +1 202.942.5999
jeremy.karpatkin@apks.com | www.apks.com

---

**From:** segnaczyk@louisberger.com
**Sent:** Thursday, April 17, 2014 4:12 PM
**To:** Hague, William
**Cc:** aantonian@connellfoley.com; kcoakley@connellfoley.com; lwalsh@connellfoley.com; tlewis@louisberger.com; Daneker, Michael D.; Karpatkin, Jeremy C.; Morris, John (MTO); 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; kmillian@tpmlaw.com; Graham, Stephanie; 'A. Kim Bell Hosea'; b.bell@cea-enviro.com; bross@disposalsafety.com; rgtspecialmaster@aol.com; aalcorn@tpmlaw.com
**Subject:** RE: SA6South excavation of cells 44-52

Bill,
Letter was received.
Thanks, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, April 17, 2014 4:04 PM
**To:** Egnaczyk, Steve
**Cc:** 'Agnes Antonian'; 'Kevin Coakley'; 'Liza M. Walsh'; Lewis, Thomas; Daneker, Michael; 'Jeremy Karpatkin'; Morris, John (MTO); 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; Kathleen L. Millian; Graham, Stephanie; 'A. Kim Bell Hosea'; 'Bruce A. Bell'; BRoss@disposalsafety.com; 'Senator Robert Torricelli'; Alicia Clark Alcorn
**Subject:** RE: SA6South excavation of cells 44-52

Steve
Our response to this letter you reference went out about ½ hour ago at 3:25.
Let me know if you have an issue getting access.

Regards
Bill

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, April 17, 2014 3:52 PM
**To:** Hague, William
**Cc:** 'Agnes Antonian'; 'Kevin Coakley'; 'Liza M. Walsh'; Lewis, Thomas; Daneker, Michael; 'Jeremy Karpatkin'; Morris, John (MTO); 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; Kathleen L. Millian; 'A. Kim Bell Hosea'; 'Bruce A. Bell'; BRoss@disposalsafety.com; 'Senator Robert Torricelli'; Alicia Clark Alcorn
**Subject:** RE: SA6South excavation of cells 44-52

Bill,

Could you please provide the status of your reply to Plaintiff's letter regarding excavation of cells 44-52?

Regards, Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Alicia Clark Alcorn [mailto:aalcorn@tpmlaw.com]
**Sent:** Friday, April 11, 2014 12:33 PM
**To:** 'Senator Robert Torricelli'
**Cc:** 'Agnes Antonian'; 'Kevin Coakley'; 'Liza M. Walsh'; Lewis, Thomas; Egnaczyk, Steve; 'Michael Daneker'; 'Jeremy Karpatkin'; 'Hague, William'; 'John Morris (john.morris@honeywell.com)'; 'Jeremy Farrell (jfarrell@jcnj.org)'; 'Jason T. Watson (jwatson@jcnj.org)'; Kathleen L. Millian; 'A. Kim Bell Hosea'; 'Bruce A. Bell'; BRoss@disposalsafety.com
**Subject:** SA6South excavation of cells 44-52

Please see the attached.

Alicia C. Alcorn
Terris, Pravlik & Millian, LLP
1121 12th Street N.W.
Washington, DC 20005-4632
Main Telephone: 202-682-2100 ext.8471
Direct Dial: 202-204-8471
Facsimile: 202-289-6795
E-Mail: aalcorn@tpmlaw.com

The information in this e-mail is intended only for the use of the designated recipient(s) and may contain confidential and privileged information. If the reader of this e-mail is not the intended recipient(s), you are hereby notified that you have received this e-mail in error and that any review, dissemination, distribution, or copying of this message is strictly prohibited. If you have received this e-mail in error, please notify the sender by reply e-mail and destroy all copies of the original e-mail.

---

This communication may contain information that is legally privileged, confidential or exempt from disclosure. If you are not the intended recipient, please note that any dissemination, distribution, or copying of this communication is strictly prohibited. Anyone who receives this message in error should notify the sender immediately by telephone or by return e-mail and delete it from his or her computer.

For more information about Arnold & Porter Kaye Scholer LLP, click here:
http://www.apks.com

Honeywell

**Honeywell**
**101 Columbia Rd**
**Morristown, NJ 07962**

April 17, 2014 *Via Express Mail*

Honorable Robert G. Torricelli
Office of the Special Master
41 W. State St., Suite 2F
Trenton, NJ 08608

**Subject:** **Response to Comments Provided by Plaintiffs, April 11, 2004**
**Excavation of Cells 44 Through 52**
**Study Area 6 South**

Dear Senator Torricelli:

Honeywell has attached a memorandum prepared by its engineer, Amec, responding to comments provided by Plaintiffs on April 11th, pertaining to the excavation of cells 44 through 52 in Study Area 6 South.

If you have any questions, please contact the undersigned at (973) 455-2175.

Sincerely,

William J. Hague
Director, Remediation
Engineering and Construction

WJH:sgf

Encl: 04/17/14 Amec Memorandum re: Response to Comments on Study Area 6 South – Excavation of Cells 44 Through 52

cc: (electronic copy only)
Joe Clifford - AMEC
Michael Daneker - Arnold & Porter LLP
Jeremy Karpatkin - Arnold & Porter LLP
Dr. Bruce Bell - Carpenter Environmental Associates, Inc.
Kim Hosea - Carpenter Environmental Associates, Inc.
Jeremy Farrell - City Hall
Jason Watson – City Hall
Agnieszka Antonian - Connell Foley LLP
Kevin Coakley, Esq. - Connell Foley LLP
Liza Walsh - Connell Foley LLP
Frank Borin - DeCotiis, Fitzpatrick & Cole, LLP
Kevin Kinsella - DeCotiis, Fitzpatrick & Cole, LLP
Dr. Benjamin Ross - Disposal Safety, Inc.
David Isabel - Golub & Isabel PC
Tom Byrne - Honeywell
Maria Kaouris - Honeywell

John Morris - Honeywell
Alicia Clark Alcorn - Terris, Pravlik & Millian, LLP
Kathleen Millian - Terris, Pravlik & Millian, LLP
Carolyn Smith-Pravlik - Terris, Pravlik & Millian, LLP
Steve Egnaczyk - The Louis Berger Group, Inc.
Thomas Lewis - The Louis Berger Group, Inc.

**Memo**

| | | | |
|---|---|---|---|
| Date: | **4/17/2014** | cc: | **John Morris, Maria Kaouris, John Mojka, Jeremy Karpatkin, Michael Daneker** |
| From: | **Joe Clifford/Geoff Shallard** | | |
| To: | **Bill Hague** | | |
| Subject: | **Response to Comments on Study Area 6 South – Excavation of Cells 44 Through 52** | | |

AMEC Environment & Infrastructure, Inc. (Amec), on behalf of Honeywell, has prepared the following responses to the comments that were submitted by Plaintiffs regarding the Study Area 6 South – Excavation of Cells 44 through 52 in a letter dated April 11, 2014. For convenience, Amec has listed each comment from Terris, Pravlik & Millian, LLP and the corresponding technical response from Amec.

## Responses to Comments from Terris, Pravlik and Millian (TPM)

**Terris, Pravlik and Millian Comment (TPM-1):**
*On March 3, 2014, Honeywell provided the SA-6 South Standard Operating Procedure Confirmation of Excavation Limits ("SOP"). Plaintiffs are in the process of reviewing and preparing technical comments on the SOP which we will circulate to all parties in the near future. However, we note that the documentation of the excavation of cells 42-52 provided by Honeywell does not conform to the requirements of Honeywell's SOP.*

**Amec Response:** Contrary to the Plaintiffs' assertion, Amec believes that the documentation of cells 44-52 (we assume the 42-52 was a typographical error) is being provided in conformance with the Honeywell SOP as explained in Amec's second response below.

**Terris, Pravlik and Millian Comment (TPM-2):**
*In Particular, the SOP (p.3) states that for the bottom excavation in excavation areas where Stratum D is encountered, "[t]he Surveyor documents the elevations at the approximate corners and center of each excavation cell and other points that they deem necessary to prepare the topographic survey." With respect to cells 44-52, the documentation provided by Honeywell does not include survey data for the corner points of the Stratum D excavation area within each cell. If these data were collected, Honeywell should provide the data to the Special Master and parties. If the corner points data were not collected, we request that Honeywell provide an explanation as to why the SOP is not being followed. In addition, if the data were not collected,*

AMEC
200 American Metro Blvd, Suite 113
Hamilton, NJ 08619
Tel 609-689-2829
Fax 609-689-2838
amec.com

*Honeywell should require that the contractors go back and collect all the data points required by the SOP.*

**Amec Response:** Amec confirms that the surveyor has collected the data necessary to prepare the topographic map as indicated in the first bullet of Section 5.0 in the SOP. The topographic map will be prepared to meet the requirements of Section 02315 Part 3.03 Topographic Surveys, Part C. Post Excavation Survey of the Technical Specifications. Copies of the survey points at Stratum D approximate to the corners of cells 44-52 are attached. The topographic survey will be provided as part of the final certification.

**Terris, Pravlik and Millian Comment (TPM-3):**
*Based upon the documentation provided by Honeywell regarding the excavation areas within cells 44-52 that were excavated to a depth other than the Stratum D, plaintiffs concur that Honeywell has excavated those areas to the appropriate depth. As to the excavation areas within cells 44-52 that were to be excavated to the Stratum D, plaintiffs will wait for Honeywell's response to these comments prior to making a determination as to whether excavation was to the appropriate depth.*

**Amec Response:** The requested information has been provided as noted above.

CAP AREA (TYP)

HYDRAULIC BARRIER (TYP)

−2.2 −2.5 −2.6 −2.5 −2.6 −2.8 −3.2 −3.1 −3.3 −3.3

9 58 57 56 55 54 53 52 51 50 49 48 47 46 45 44 43 42 41 40 39 38

BOT OF EXC
AREA 6 = (2.50)

−3.7

BOT OF EXC
AREA 7 = (1.20)

−2.7 −2.7 −3.3 −3.3 −2.8 −2.8 −3.8 −2.8 −3.3

BOT OF EXC
AREA 8 = 0.40

LIMIT OF STRATUM D EXPOSURE PER
THIRD PARTY SURVEY (TYP)

BOT OF EXC
AREA 9 = (1.20)

LIMIT OF ANTICIPATED STRATUM D
EXPOSURE PER DESIGN (TYP)

−3.8 BOE ELEVATION AT EDGE OF STRATUM D
PER THIRD PARTY SURVEY (TYP)

0 5 10 20
SCALE IN FEET

Prepared/Date: TDD 4/18/14
Checked/Date: SGS 4/18/14

| | | | |
|---|---|---|---|
| Honeywell<br>101 COLUMBIA RD, BOX 2105<br>MORRISTOWN, NJ 07962 | CHROMIUM REMEDY<br>STUDY AREA 6 SOUTH<br>JERSEY CITY, NEW JERSEY | amec | SA-6 SOUTH<br>STRATUM D CELLS 44 THRU 52<br>FIGURE 1 |

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:55 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6S : Excavation Completion in Cells 44 through 48

Same as last email, don't see an acknowledgement from SM, use this as placeholder.

---

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:44 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Subject:** FW: SA-6S : Excavation Completion in Cells 44 through 48

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, April 06, 2014 1:11 PM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; Daneker, Michael <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 44 through 48

Steve,

We are providing this email notification that our contractor is read to backfill Cells 44, 45, 46, 47 and 48.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the following two individual periods:

03/07/14 to 03/13/14 – Cells 44 and 45
03/14/14 to 03/20/14 – Cells 46, 47 and 48

- *Approximately half of the bottom of Cells 44 and 45 were terminated in Stratum D. The Southern limit of cells 44 and 45 were terminated in Stratum O <20 PPM soils. Area 7 was carried down to Stratum D.*

- *Approximately 30-40% of the bottom of Cells 46, 47 and 48 were terminated in Stratum D. The Southern limit of cells 46, 47 and 48 were terminated in Stratum O <20 PPM soils. Area 7 was carried down to Stratum D.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises up to 2 feet above the general elevation of the Stratum D on these cells. The ridge appears to be more prominent as the excavation has advanced to the west. The ridge is part of the contiguous Stratum D geologic horizon.*
- *A significant number of pilings are being encountered. The pilings supported the 60 Kellogg St warehouse structure. Pilings are being sheared flush with the bottom of excavation.*
- *Excavation Bottom Elevation Figures are included for the cells noted above.*
- *Confirmatory Bottom Points located within Cells 44, 45, 46, 47 and 48 are shown on the Excavation Bottom Elevation figure.*
- *A Confirmatory Sidewall Sample 125-SB-067 for Cell 44 and Sample 125-PT-15 for Cell 47 are also shown on the respective Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 44 and 45 for the week ending 03/13/14 and Cells 46, 47 and 48 for the week ending 03/20/14.*
- *The northern limits of Cells 44, 45, 46, 47 and 48 consist of sheet pile Barrier Wall. The Southern Limit of excavation of Cells 44, 45, 46, 47 and 48 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials. There are several joints where excess grout from the grouted joint is evident adhering to the sheets. Some grout that is strongly adhering to the sheet was left in place.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *Excavation Progress Maps are provided. Excavation is continuing in Cells 49 and 50.*
- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Thanks
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 49 through 52

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, April 09, 2014 10:53 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 49 through 52

Bill,
Thanks very much. Steve

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger or its respective affiliated companies (collectively, "LB"), the information and statements herein do not constitute a binding commitment or warranty by LB, and LB assumes no responsibility for any misperceptions, errors or misunderstandings.

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, April 09, 2014 10:50 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 49 through 52

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 49, 50, 51 and 52.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 03/21/14 to 03/27/14.

- *Approximately 60% of the bottom of Cells 49, 50, 51 and 52 were terminated in Stratum D. The Southern limit of cells 49, 50, 51 and 52 were terminated in Stratum O*

- *An Excavation Bottom Elevation Figure is included for the cells noted above.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises above the general elevation of the Stratum D on these cells. The ridge is part of the contiguous Stratum D geologic horizon.*
- *A significant number of pilings continue to be encountered. The pilings supported the 60 Kellogg St warehouse structure. Pilings are being sheared flush with the bottom of excavation.*
- *Confirmatory Bottom Points located within Cells 49, 50, 51 and 52 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples 125-SB-081 for Cell 49, 125-SB-091 for Cell 50, 125-SB-080 for Cell 51 and 125-SB-092 for Cell 52 are also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 49, 50, 51 and 52.*
- *The northern limits of Cells 49, 50, 51 and 52 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 49, 50, 51 and 52 terminate at the*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Maps is provided. Excavation is continuing in Cells 53 and 54.*

- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Please note that additional lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the southern limits of Cells 50, 51 and 52, Stratum O is divided by the line separating designated Area 8 from Area 9.

Thanks
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:54 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6S : Excavation Completion in Cells 53 through 56

Eric, there was a period in time where the SM had my email incorrect, so I don't think I have the acknowledgement for this one. Use this as placeholder

---

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:45 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amecfw.com>
**Subject:** FW: SA-6S : Excavation Completion in Cells 53 through 56

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, April 11, 2014 8:32 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; Daneker, Michael <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 53 through 56

Steve,

We are providing this email notification that our contractor is read to backfill Cells 53, 54, 55 and 56.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 03/28/14 to 04/04/14.

- *Approximately 40% of the bottom of Cells 53, 54, 55 and 56 were terminated in Stratum D. The Southern limit of cells 53, 54, 55 and 56 were terminated in Stratum O <20 PPM soils.*

- *An Excavation Bottom Elevation Figure is included for the cells noted above.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises above the general elevation of the Stratum D on these cells. The ridge is part of the contiguous Stratum D geologic horizon. Portion of the top of the ridge was removed in Cells 55 and 56 to permit clean excavation to the Area 8 boundary.*
- *Lines has been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the southern limits of Cells 53, 54, 55 and 56 the Stratum O is divided by Area 8, Area 9 and Area 10*
- *Pilings from the 60 Kellogg St warehouse were sheared flush with the bottom of excavation.*
- *Confirmatory Bottom Points located within Cells 53, 54, 55 and 56 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples 125-SB-079 for Cell 53, and 125-SB-087, 125-SB-080 for Cell 56, are also shown on the Excavation Bottom Elevation figure.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 53, 54, 55 and 56*
- *The northern limits of Cells 53, 54, 55 and 56 consist of sheet pile Barrier Wall. The Southern Limit of excavation of Cells 53, 54, 55 and 56 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided. Excavation is continuing in Cells 57 and 58.*

- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Thanks
Bill Hague

**Honeywell**

**William J. Hague P.E.**

Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:44 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 57 & 58

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, May 01, 2014 5:23 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 57 & 58
**Importance:** High

Bill,

The Special Master is in receipt of your April 28, 2014 email and the supporting documentation regarding Excavation Completion in Cells 57 and 58 and the notification that the contractor is ready to backfill Cells 57 and 58. We have no objection to Honeywell's proposal to backfill Cells 57 and 58.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, April 28, 2014 7:49 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 57 & 58

Steve,

We are providing this email notification that our contractor is read to backfill Cells 57 and 58.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 04/05/14 to 04/11/14.

- *Approximately 40% of the bottom of Cells 57 and 58 were terminated in Stratum D. The Southern limit of cells 57 and 58 were terminated in Stratum O <20 PPM soils.*
- *An Excavation Bottom Elevation Figure is included for the cells noted above.*
- *Due to natural variations in the surface elevation of the Stratum D the bottom elevation varies by a nominal amount of approximately 1 ft. There is a naturally occurring narrow east west trending ridge in the surface of the Stratum D (fibrous brown meadow mat) near the midpoint of the excavation that rises above the general elevation of the Stratum D on these cells. The ridge is part of the contiguous Stratum D geologic horizon. Portion of the top of the ridge was removed in cells 57 and 58 to permit clean excavation to the Area 8 boundary.*
- *Lines has been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the southern limits of Cells 57 and 58 the Stratum O is terminated at the respective Area 8 and Area 10 excavation elevations.*
- *Pilings from the 60 Kellogg St warehouse were sheared flush with the bottom of excavation.*
- *Confirmatory Bottom Points located within Cells 57 and 58 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples. There were no confirmatory sidewall samples in cells 57 and 58.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to Cells 57 and 58.*
- *The northern limits of Cells 57 and 58 consist of sheet pile Barrier Wall. The Southern Limit of excavation of cells 57 and 58 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided. Excavation has been temporarily terminated in Cell 59. The excavation and backfill faces will be stabilized and excavation will be started at the western portion of the site in Cell 153/154.*

- *All survey points in the excavation cell were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cell, except for those areas where Stratum D was encountered.*

Also please find attached the Figure 1 showing Stratum D corner elevations as discussed at our last all parties meeting. We had previously sent this figure for Cells 44-52 in response to plaintiffs comments, so we are herein attaching the figure for Cells 53-58.

Thanks
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road

Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:12 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 59 through 68

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, December 12, 2014 11:47 AM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JWatson@jcnj.org; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; Morris, John (MTO) <John.Morris@honeywell.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 59 through 68

Bill,

The Special Master is in receipt of your November 24, 2014 email and the supporting documentation regarding Excavation Completion in Cells 59-68 and your notification that the requirements to allow backfilling have been met. Honeywell has also reported that as indicated in the previous submittal for Cells 69-75, the lens of anomalous white material approximately 2 feet below ground surface (BGS) was also observed in Cells 68 to 61. Consistent with the response to Cells 69 to 75 and as reported in Honeywell's November 17 response to Plaintiffs' November 11, 2014 email, the anomalous white material was previously identified and sampled during the PDI program and found to be less than 20 ppm hexavalent chromium in all locations shown on the updated Figure 1. Honeywell further reported in the November 17 response that an additional sample of the material was collected at the same depth during the active excavation and this result was also reported at less than 20 ppm hexavalent chromium.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, November 24, 2014 12:31 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael;

JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 59 through 68

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 59 through 68.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 10/17/14 to 10/30/14.

This Excavation Submittal includes Cells 59 through 68.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- As indicated in the previous submittal for cells 69-75 Amec inspectors identified a lens of white material approximately 2 ft. below ground surface. This lens was also observed in Cells 68 to 61. Based on review of the PDI data and a targeted sample taken from the lens at the time of excavation that lens shows no indication of the presence of chromium above 20 mg/KG. The extent and testing of the lens has been addressed in previous emails with the Special Master and Plaintiffs.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas in the Cells 59 through 68.
- The bottom of excavation for Area 11 and Area 14 were both terminated in Stratum D.
- The bottom of excavation for Areas 8, 10 and 12 were terminated in Stratum O, at or below the respective Excavation Bottom Elevations.
- The contiguous excavation in SA-6S between Cell 1 and Cell 156 is complete excluding the deferred Area by the Hackensack River.
- Excavation will proceed in Site 163 and the lens of anomalous material extending south of Cell 104.
- Confirmatory Bottom Points are located within Cells 59, 61, 63, 64 66, 67, and 68. Reference Points were also used in Cells 59, 60, 61, 62, 63, 65, 66, 67, and 68.
- The northern excavation limit was the Barrier Wall.
- The southern limit of Cells 59 through Cell 68 is sloped excavation.
- There were Confirmatory Sidewall Samples in Cells 59, 60, 61, 64, 65, 67, and 68.

As previously discussed, we intend on issuing a separate certification email on the Site 163 shallow excavation and an amended certification once the Cell 104 anomalous material excavation is complete.

Regards,

Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, December 01, 2014 10:32 AM
**To:** Ambrose, David M; Shallard, Samuel G.
**Cc:** Bills, Stuart B; Christodoulatos, Eric G
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 69-75

This is the last set of cells that SM has responded to.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, November 26, 2014 10:01 AM
**To:** 'Hague, William'; Clifford, Joseph T
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 69-75

Bill/Joe,

The Special Master is in receipt of your November 3, 2014 email and the supporting documentation regarding Excavation Completion in Cells 69-75 and your notification that the requirements to allow backfilling have been met. In addition, the Special Master is in receipt of Honeywell's November 17 email response and updated Figure 1 showing locations of additional analytical information and the extent of the observed anomalous white material in response to Plaintiffs' November 11, 2014 email. As reported in Honeywell's November 17 response, the anomalous white material was previously identified and sampled during the PDI program and found to be less than 20 ppm hexavalent chromium in all locations shown on the updated Figure 1. Honeywell then collected an additional sample of the material at the same depth during the active excavation and this result was also reported at less than 20 ppm hexavalent chromium.

Regards, Steve

**Steven J. Egnaczyk**
Program Director | Environmental and Disaster Management Services

direct +1.610.363.5395
mobile +1.610.212.1492
fax +1.610.363.5390
email segnaczyk@louisberger.com
web louisberger.com

**Louis Berger**
350 Eagleview Boulevard | Exton | PA | 19341-1178| USA

*Celebrating 60 Years*

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Monday, November 03, 2014 2:37 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 69-75

Steve,

I am providing this email on behalf of Honeywell.

We are providing this email notification that our contractor is ready to backfill Cells 69 through 75.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 10/03/14 to 10/16/14.

This Excavation Submittal includes Cells 69 through 75.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors identified a lens of white material approximately 2 ft. below ground surface over at the southern end of Cell 70. Review of the PDI data shows sidewall soil samples at a similar depth interval ( 140-SB-025, 140-SB-034 and 140-SB-072) indicated hexavalent chromium results that were
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas in the Cells 69 through 75.
- Area 14 was terminated in Stratum D.
- Areas elevations for 8, 12 and 13 were terminated in Stratum O at or below at the respective Excavation Bottom Elevations.
- Excavation will proceed from Cell 68 to the east.
- The excavation will continue through Cell 59 at which point it will connect to the previously excavated area of Cells 1 through 58.
- Confirmatory Bottom Points located within Cells 75, 74, 73, 72, 71, 70 and 69.
- The northern excavation limit was the Barrier Wall.

- The southern limit of Cells 69 through the eastern portion of Cell 71 is sloped excavation. The southern limit of the western portion of Cell 71 and Cells 72 through 75 is temporary sheetpile.
- There were Confirmatory Sidewall Samples in Cells 71 (2 locations) and 75.

Regards.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:25 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 76-79
**Attachments:** GCL Area 100314_2.pdf

---

**From:** Clifford, Joseph T
**Sent:** Wednesday, November 05, 2014 10:47 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org; Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 76-79

Steve,

I am providing this email on behalf of Honeywell.

We are providing this response to your clarification request received in an email dated October 30, 2014 regarding the Excavation Complete Submittal on Cells 76 - 79. HON has reviewed the requested information with Amec and can offer the following statements:

- The 100% Design for Cell 76 and 77 indicates excavation to Stratum D at a target elevation of -2.5 feet.
- After reaching the Stratum D layer within the excavation, Amec inspectors identified a limited discontinuity in the Stratum D surface.
- Amec instructed the contractor to remove additional material which revealed that the discontinuity was smaller than thought, and then directed the contractor to repair the area using GCL in accordance with 100% Design.
- Amec confirms that the excavation limits and the repaired area both meet the requirements of the 100% Design.

We are also including an updated figure of the actual GCL repair area, with the “drawing scale” now added, in response to a separate email request from Kim Hosea received on October 27, 2014.

Please let us know if you need more information on this item.

Regards.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, October 30, 2014 6:28 PM
**To:** Hague, William; Clifford, Joseph T
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 76-79

Bill/Joe,

The Special Master is in receipt of your October 24, 2014 email and the supporting documentation regarding Excavation Completion in Cells 76-79 and your notification that the requirements to allow backfilling have been met. Honeywell reports that in the southern limit of Cells 76/77 there were portions of the Stratum D material missing. Honeywell also reports their contractor successfully completed repairs to this area. Please provide a certification which confirms that: 1) impacted soils as defined in the 100% Design were removed from the discontinuous area to the design depth for Excavation Area 14, and 2) the area was repaired and the requirements to allow backfilling as required in the 100% Design were met.

Regards, Steve

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Friday, October 24, 2014 7:27 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 76-79

Steve,

I am providing this email on behalf of Honeywell.

We are providing this email notification that our contractor is ready to backfill Cells 76 through 79.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 09/25/14 to 10/02/14.

This Excavation Submittal includes Cells 76 through 79.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- The northern excavation limit was the Barrier Wall.
- The southern limit is temporary sheet pile.
- There was one Confirmatory Sidewall Samples in Cell 77.
- All Cells are in Area 14.
- Area 14 was designed to terminate in Stratum D.
- All cells terminated in Stratum D with the exception of an area of discontinuous Stratum D as discussed below.
- At the southern limit of Cell 76/77, a discontinuity was identified in the Stratum D. The area of the discontinuity is shown on the attached Figure titled “As Built GCL Area Cells 75, 76 and 77”. There appeared to be a vertical displacement downward in the stratum D along the western edge of the area shaded in yellow on the figure. Excavation revealed that the Stratum D sloped back up to the typical Stratum D top elevation along the eastern edge of the area. To establish continuity in the Stratum D a Geosynthetic Clay Liner (GCL) was deployed over the area as depicted by the green shading on the figure. The Stratum D was continuous east of the repair area.
- The Confirmatory Bottom Point sample locations are provided for Cells 76 through 79.
- Excavation will proceed from Cell 75 to the east.

Regards.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Monday, October 20, 2014 10:49 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 80 through 83

**Importance:** High

**Follow Up Flag:** Follow up
**Flag Status:** Completed

*Stuart B. Bills*
**Senior Associate Construction Manager**
**AMEC E&I, Inc.**
**(252) 202-1411**

**stuart.bills@amec.com**
**www.amec.com**

***Confidentiality Notice: The above message may contain information covered by the attorney-client and/or litigation work product privileges. The message should be treated as Privileged and Confidential unless specifically stated otherwise within the message. If you are not the intended recipient of this message, please delete it immediately and notify the sender of the error. This message should not be forwarded without the approval of counsel.***

---

**From:** Clifford, Joseph T
**Sent:** Monday, October 20, 2014 10:25 AM
**To:** Shallard, Samuel G.; Bills, Stuart B; Nagg, Dennis E
**Cc:** Ambrose, David M; Mojka, John
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 80 through 83
**Importance:** High

Good to go.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, October 15, 2014 9:51 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 80 through 83
**Importance:** High

Bill,

The Special Master is in receipt of your October 10, 2014 email and the supporting documentation regarding Excavation Completion in Cells 80-83 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Friday, October 10, 2014 1:14 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 80 through 83

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 80 through 83.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 09/05/14 to 09/25/14.

This Excavation Submittal includes Cells 80 through 83.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- Cells 80 through 83 are all in Area 14 which was designed to terminate in Stratum D.
- Cells 80 through 83 all terminated in Stratum D.
- The Confirmatory Bottom Point sample locations are provided for Cells 80 through 83 on the attached Excavation Bottom Map.
- The northern excavation limit was the Barrier Wall.
- The southern limit is partially temporary sheet pile (Cell 80 and part of 81) and partially sloped excavation (Cell 83, 82 and part of 81).
- There were Confirmatory Sidewall Samples in Cells 80, 82 and 83.
- Excavation will proceed from Cell 79 to the east.

Regards,

Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:15 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal Cells 84-89

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, October 16, 2014 1:12 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amec.com>; Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 84-89

Joe,
Thanks very much. Steve

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Thursday, October 16, 2014 11:58 AM
**To:** Egnaczyk, Steve; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 84-89

Steve,

I am sending this email on behalf of Honeywell.

Per your request, attached please find the Maser Consulting Survey Data Table inclusive of Cells 84 - 89 with the signed ENTACT Letter of Transmittal cover page.

This attachment replaces the one submitted in the original email from Bill Hague on October 2, 2014 which did not include the ENTACT transmittal.

Please let us know if you need any other information relative to Cells 84 – 89 completion submittal.

Regards.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, October 15, 2014 9:49 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal Cells 84-89
**Importance:** High

Bill,

The Special Master is in receipt of your October 2, 2014 email and the supporting documentation regarding Excavation Completion in Cells 84-89 and the notification that the contractor is ready to backfill these Cells. Consistent with previous submittals, please either provide the ENTACT Letter of Transmittal with the signed Survey Data Verification, confirming that Maser Consulting, P.A. ("Maser) has surveyed the bottom of excavations and that the final excavation grade(s) are at or below the design excavation grades throughout the corresponding excavation cells or confirmation that this verification is not applicable to this submittal.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, October 02, 2014 7:38 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal Cells 84-89

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 84 through 89.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 08/22/14 to 09/04/14.

This Excavation Submittal includes Cells 84 through 89.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All cells were terminated were terminated in Stratum D.
- Confirmatory Bottom Points located within Cells 89, 88, 87, 86, 85. A Reference Point was used for Cell 84.
- The northern excavation limit was the Barrier Wall.
- The southern limit is sloped excavation.
- There were Confirmatory Sidewall Samples in Cells 89 and 84.
- It is noted that the southerly limit of the <20 PPM line was straightened in Cells 84 through 89 and carried further to the south to simplify excavation geometry in this area. We excavated in a straight line between 134-SB-100 (Cell 89) and 140-SB-059 (Cell 83) to simply excavation rather than jogging back in to 140-SB-060 (Cell 84). This results in the sidewall sample in Cell 84 (140-SB-060) being located within the final excavation limits.
- Excavation will proceed from Cell 83 to the east.

Regards,
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Friday, September 05, 2014 10:36 AM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 90 through 99

Stuart Bills
AMEC E&I

Sent via the Samsung GALAXY S®4, an AT&T 4G LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:09/05/2014 10:34 (GMT-05:00)
To: "Shallard, Samuel G." ,"Bills, Stuart B"
Cc: "Nagg, Dennis E" ,"Ambrose, David M" ,"Mojka, John"
Subject: FW: SA-6S : Excavation Completion in Cells 90 through 99

Good to go

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, September 05, 2014 10:02 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 90 through 99
Bill,
The Special Master is in receipt of your September 3, 2014 email and the supporting documentation regarding Excavation Completion in Cells 90 through 99 and the notification that the contractor is ready to backfill these Cells.
Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, September 03, 2014 9:37 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 90 through 99
Steve,

We are providing this email notification that our contractor is ready to backfill Cells 90 through 99.
We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.
This submittal notification of SA-6 South excavation completion covers the individual period from 08/08/14 to 08/21/14.
It is noted that a sidewall sample was taken from of a thin lens of grayish material identified directly above the Stratum D in the face of the step up from Area 15 into Area 16 in Cell 104. This sample came back with a validated result of hexavalent chromium > 20 ppm. Further investigation and sampling is being conducted as needed to delineate and remove this material.
As discussed, this over-excavation of the 100% Design footprint (based upon the 20 ppm contour established during the PDI) will result in an amended certification email for affected cells and additional laboratory data on sidewall will be provided once validated.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All cells were terminated were terminated in Stratum D.
- Confirmatory Bottom Points located within Cells 99, 98, 97, 96, 95, 93, 91, and 90.
- The northern excavation limit was the Barrier Wall. The southern limit is sloped excavation
- There were Confirmatory Sidewall Samples in Cells 92 and 96.
- Excavation will proceed from Cell 89 to the east.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:12 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, February 04, 2015 6:23 PM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Ben Davis <bdavis@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41
**Importance:** High

Bill,

The Special Master is in receipt of your January 7, 2015 email and the supporting documentation regarding the Amended Certification for Excavation Complete in Cells 100 to 106A and new Excavation Complete Certification for Area 41 and your notification that the requirements to allow backfilling have been met. Please confirm that the certification statements contained in your email refer to both the expanded excavation in Cells 100 to 106A and Area 41.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, January 07, 2015 2:40 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T;

KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41

**AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 100 TO 106A AND NEW EXCAVATION COMPLETE CERTIFICATION FOR AREA 41**

Steve,

We are providing an amended certification regarding completion of excavation in Cells 100 to 106A which was originally submitted by Honeywell to the parties by email on August 18, 2014.

As discussed in the September 16, 2014 monthly Special Master meeting/call, Honeywell and Amec indicated that an amended certification would be needed based upon analytical information received on the anomalous material indicating hexavalent concentrations > 20 ppm.

Subsequent to the original submittal, Honeywell also directed Amec to determine the lateral extent of the anomaly and collect additional sidewall soil samples consistent with our approved plans. Honeywell kept the parties informed that the additional delineation would require some time as other site conditions including stockpile management had to be completed by the excavation contractor before a drill rig could access the area.

The investigation resulted in collection of a total of 16 soil samples for hexavalent chromium, 15 of these using a drill rig and the last one collected as a post-excavation sidewall sample (see Figure 10 Anomalous Lens Boring Location Map attached).

The lateral extent of the lens was defined by locations of soil samples 134-SB-170, 134-SB-171, 134-SB175 and 134-SB-177, which all had hexavalent chromium < 20 ppm. This last soil sample designated as 134-SB-177 was collected post-excavation and confirmed to be < 20 ppm. The area was excavated to these soil sample locations in late November/early December and inspected by Amec and resurveyed by Maser on December 8, 2014.

The investigation program confirmed that the lens was present just above the Stratum D. Excavation was continued laterally to the excavation limits or until there was no visible grey lens. Area 41 is a small isolated excavation area identified in the 100% Design which was performed concurrent with the anomaly material excavation. The faces of excavation were inspected by Amec as noted below:

- Coordinates for Survey of the finished excavation to Stratum D are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal.
- The excavation was extended from Cell 104 in a Southwest to West direction.
- The bottom of the excavation followed the surface of the Stratum D.
- The excavation was extended to the limits defined by the investigation.
- The bottom of the excavation was visually inspected by Amec personnel to confirm that all of the grey lens had been removed and Stratum D exposed.
- The sidewall slopes were laid back to provide stable conditions.
- The limits of the excavation were visually inspected by Amec personal to confirm that the grey lens was no longer visible.
- In cases where the lens was determined to still be visible the excavation was expanded and the process repeated until a visibly clean limit was established.

- Additional confirmation sampling was conducted in these cases to provide a sidewall sampling frequency that met the NJDEP Technical Regulation requirements incorporated into the approved 100% Design.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- There was a total of 8 Confirmatory Sidewall Samples, 4 locations for the limits of the Cell 104 anomalous material and 4 locations for Area 41.
- 10 Confirmatory Center Point elevations were recorded consistent with the Cell Layout to provide a record in this submittal of the elevation of the Stratum D. Additional coordinates were surveyed and will be used for production of the excavation bottom survey.

An Amended Excavation Bottom Elevation Map showing the additional area of excavation of visually-impacted concrete and subsequent soil > 20 ppm is attached and highlighted in gray.

The added < 20 ppm soil sample confirmatory locations are also shown on the map. Analytical data for the additional soil samples collected in this excavation area was provided in the SA-6 Monthly Progress Reports and is updated in Figure 10 attached.

The Maser Survey Table showing the confirmatory points has been updated to reflect the added soil sample locations with hexavalent chromium < 20 ppm (highlighted in yellow on page 19 of 20 and labeled as “Lens Area”) which are additional sidewall confirmatory samples for SA-6 South.

As all of the over excavation for this anomalous material extended to Stratum D, no additional bottom samples were necessary.

Lastly, during a recent weekly progress meeting, you asked about a single point in the HON/Amec submittal of Excavation Complete in Cells 59 through 68 (originally submitted on November 24, 2014). Specifically you asked if the table correctly identified the Target Elevation for the Depth of Excavation in the Maser Table for point C-70-3. Amec Engineers have reviewed the Maser table and concur that the Target Depth for point C-70-3 should be 0.4 feet (consistent with the target excavation depth for Area 13) and the corrected Maser table (attached).

Regards
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:37 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Complete Submittal - Area 41

**Importance:** High

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, February 11, 2015 5:31 PM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; Ben Davis <bdavis@tpmlaw.com> (bdavis@tpmlaw.com) <bdavis@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: SA-6 South Excavation Complete Submittal - Area 41
**Importance:** High

Bill,

The Special Master is in receipt of your February 9, 2015 email and the supporting documentation regarding Excavation Completion in Area 41 and your notification that the requirements to allow backfilling have been met.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, February 09, 2015 2:48 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal - Area 41

Steve,

We are providing an amended certification regarding completion of excavation in Area 41 which was originally submitted by Honeywell to the parties by email on January 7, 2015.

In response to your questions raised last week via phone call with Amec, we understand that a clarification was requested to certify that the standard inspections were also performed specific to Area 41 and not just Cells 100 to 106A.

As a result, we are providing this amended certification for Area 41 only.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

The following statements and attached data are specific to Area 41:

- Coordinates for Survey of the finished excavation are tabulated in the Maser Tables.
- The bottom of the excavation was terminated in Stratum O.
- One PDI bottom sample location 134-SB-026 is associated with Area 41 and is shaded yellow on Page 9 of the Maser Table.
- The sidewall slopes were laid back to provide stable conditions.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- There was a total of 4 Confirmatory Sidewall Samples for Area 41. These samples and included and shaded yellow on Page 20 of the Maser Table. The samples form the corners of the Excavation.
- The Excavation Bottom Elevation Map showing Area 41 is attached.
- The bottom and sides of the excavation was visually inspected by Amec personnel to confirm there was no indication of visibly impacted soils.
- Backfill in Area 41 has been initiated.

Note that there were no changes needed to the attachments.

Please let us know if you have any other questions on this item.
Regards,
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly

notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Wednesday, August 13, 2014 2:52 PM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

**Importance:** High

Stuart Bills
AMEC E&I
Sent via the Samsung GALAXY S®4, an AT&T 4G LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:08/13/2014 14:10 (GMT-05:00)
To: "Bills, Stuart B" ,"Mojka, John"
Cc: "Kaouris, Maria" ,"Ambrose, David M" ,"Shallard, Samuel G."
Subject: FW: SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

fyi

---

**From:** Egnaczyk, Steve [segnaczyk@louisberger.com]
**Sent:** Wednesday, August 13, 2014 11:32 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

Bill,
The Special Master is in receipt of your August 4, 2014 email and the supporting documentation regarding Excavation Completion in Cells 106B through 118B and 107A through 114A and the notification that the contractor is ready to backfill these Cells.
Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, August 04, 2014 7:59 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T;

Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 106B through 118B and 107A through 114A

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 106B through 118B and 107A through 114A.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 06/30/14 to 07/14/14.

As previously indicated, select cells are being split into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

Cells 106 through 118 are physically divided into an A and B designation by a peninsula of

Commencing at Cell 105 the cells are no longer divided by the

Please note that the Maser table has been updated to include the missing reference points in Cells 117 and 119.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits.
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 106B through 118B and 107A through 114A, the excavation is terminated at the respective Area 15, 16, 17, 18, 24, 28 and 29 excavation elevations.
- Excavation will proceed from Cell 106 to the east to Cell 104.
- Cells 118 B, 117 B, 116B and a significant portion of 115B encountered Stratum D and was terminated accordingly (see Excavation Bottom Elevation figure). In general the northern portion of the excavation (Cells with A designation) was terminated in Stratum O at or below the Target Elevations.
- Stratum D was encountered in the easterly portion of Cell 107 A (Area 15). Area 15 (-4.3 bottom elev.) will be excavated to Stratum D as the excavation moves to the east.
- In Cells 112B to 114B the excavation limits were deepened to beyond the defined chromium impacted soil limits to remove soils below 3 UST's.
- Confirmatory Bottom Points located within Cells 106B through 118B and 107A through 114A are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were Confirmatory Sidewall Samples in Cells 113A, 111A, 109A, 107A, 118B, 116B, 115B, 112B, 110B and 107B.
- The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

Question regarding Cell 117 was addressed in the submittal for Cells 106B through 118B and 107A through 114A, submitted to Parties on August 4, 2014.

**Christodoulatos, Eric G**

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:17 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: SA-6S : Excavation Completion in Cells 115a to 120

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Thursday, July 24, 2014 9:41 AM
**To:** Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; Daneker, Michael <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 115a to 120

Bill,

I have one (1) question regarding the submittal: Could you please clarify/confirm why there was no entry for Cell 117 on Maser Table 1.4 listing the SA-6 South Excavation: Confirmatory Points (Page 5 of 1) provided with the ENTACT Transmittal)?

Otherwise, the Special Master is in receipt of your July 16, 2014 email and the supporting documentation regarding Excavation Completion in Cells 115a to 120 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, July 16, 2014 8:53 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea

(k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 115a to 120

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 115A to 120.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 06/26/14 to 06/30/14.

As previously indicated, select cells are being split into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

For reporting purposes Cells 120 is treated as a complete cell without the A and B designation.
Cells 115 through 119 are physically divided into an A and B designation by a peninsula of <20 PPM soil.
For this report both the A and B portion of Cell 119 is included.
For Cells 115 through 118 only the A portion is included. The B portion of these cells will be included in future submittals.

.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 121 through 125, the excavation is terminated at the respective Area 17, 18, 19, 20, 21, 22, 24 and 28 excavation elevations.
- Excavation will proceed from Cell 119B to the east to Cell 116B. Excavation will proceed from Cell 114A to the east to Cell 112A.
- A significant portion of the Southern portion of the cells encountered Stratum D and was terminated accordingly (see Excavation Bottom Elevation figure). The northern portion of the excavation was terminated in Stratum O at or below the Target Elevations.
- In Cells 115 to 118 the excavation limits were extended to the south and deepened to beyond the defined chromium impacted soil limits to remove VOC impacted soils
- Confirmatory Bottom Points located within Cells 115A through 120 are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were Confirmatory Sidewall Samples in Cells 115, 117, 119, and 120.

- The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:38 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 121 through 125

-----Original Message-----
From: Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
Sent: Thursday, July 10, 2014 5:51 AM
To: Hague, William
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
Subject: RE: SA-6S : Excavation Completion in Cells 121 through 125

Bill,

The Special Master is in receipt of your July 3, 2014 email and the supporting documentation regarding Excavation Completion in Cells 121 through 125 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

From: Hague, William [william.hague@honeywell.com]
Sent: Thursday, July 03, 2014 10:29 AM
To: Egnaczyk, Steve
Cc: RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
Subject: SA-6S : Excavation Completion in Cells 121 through 125

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 121 to 125.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 06/11/14 to 06/25/14.

As previously indicated, select cells are being split into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

During daily excavation and survey confirmation, Cells 121 through 125 were completed in full without the need to subdivide into A and B sections. Therefore, in this submittal the full north to south area of each cell was completed without the A/B designation as reflected in the Excavation Bottom Elevation Figure and Maser Tables.

* Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits

* Sheet pile on the excavation face has been cleaned of visible soil materials.

* The bottom and lateral limits of each cell were visually inspected by Amec personnel.

* Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.

* An Excavation Progress Map is provided.

* All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.

* Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 121 through 125, the excavation is terminated at the respective Area 19, 20, 21, 22, 23, 25 26, and 27 excavation elevations.

* Excavation will proceed from Cell 120 to the east to Cell 114. Starting in Cell 120 the excavation will again be split into A and B segments with a peninsula of <20 PPM soils separating the A and B areas.

* A significant portion of the Southern portion of the cells encountered Stratum D and was terminated accordingly (see Excavation Bottom Elevation figure). The northern portion of the excavation was terminated in Stratum O at or below the Target Elevations.

* Confirmatory Bottom Points located within Cells 121 through 125 are shown on the Excavation Bottom Elevation figure.

* The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were no Confirmatory Sidewall Samples in Cells 121 to 125. The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Regards,
Bill

Honeywell

William J. Hague P.E.
Director - Remediation Design & Construction Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com<mailto:william.hague@honeywell.com>

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Friday, June 27, 2014 9:30 AM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 126 to 128

**Importance:** High

**Follow Up Flag:** Follow up
**Flag Status:** Completed

Stuart Bills
AMEC E&I
Sent via the Samsung GALAXY S®4, an AT&T 4G
LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:06/27/2014 09:25 (GMT-05:00)
To: "Bills, Stuart B" ,"Shallard, Samuel G." ,"Nagg, Dennis E"
Cc: "Mojka, John" ,"Kaouris, Maria"
Subject: FW: SA-6S : Excavation Completion in Cells 126 to 128

Fyi.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, June 27, 2014 9:23 AM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 126 to 128
**Importance:** High

Bill,

The Special Master is in receipt of your June 19, 2014 email and the supporting documentation regarding Excavation Completion in Cells 126 to 128 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, June 19, 2014 8:01 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 126 to 128

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 126 to 128.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 05/22/14 to 06/10/14.

As previously indicated cells are being spilt into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

During daily excavation and survey confirmation Cells 129 through 133 were divided into A and B sections as reflected in the Maser Tables. There is no clean unexcavated dividing line in the middle of site as there was in Cells 137 through 146. For this submittal the full north south area of each cell was completed as indicated in the Excavation Bottom Elevation figure.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 129 to 133, the excavation is terminated at the respective Area 21, 22, 23, 26, 30, 32 and 34 excavation elevations.
- Excavation will proceed from Cell 125 to the east into Cell 123.
- The excavation was continued to the Target Elevations in all locations.

- A limited portion of the deeper excavations Area 24 and 26 (southern portion of the excavation) was terminated at or below the Target level which was coincidental with the upper surface of the Stratum D. The remainder of the excavations was terminated in Stratum O.
- Confirmatory Bottom Points located within Cells 126 through 129 are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall. There were no Confirmatory Sidewall Samples in Cells 126 to 129. The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Per the SOP, we are showing the corner elevations as discussed.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Bills, Stuart B
**Sent:** Thursday, June 12, 2014 5:14 PM
**To:** Christodoulatos, Eric G
**Subject:** Fwd: SA-6S : Excavation Completion in Cells 129 through 133

**Importance:** High

**Follow Up Flag:** Follow up
**Flag Status:** Completed

Stuart Bills
AMEC E&I
Sent via the Samsung GALAXY S®4, an AT&T 4G
LTE smartphone

-------- Original message --------
From: "Clifford, Joseph T"
Date:06/12/2014 17:06 (GMT-05:00)
To: "Shallard, Samuel G." ,"Bills, Stuart B" ,"Nagg, Dennis E"
Cc: "Kaouris, Maria" ,"Mojka, John"
Subject: FW: SA-6S : Excavation Completion in Cells 129 through 133

FYI.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, June 11, 2014 5:26 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 129 through 133
**Importance:** High

Bill,
The Special Master is in receipt of your June 8, 2014 email and the supporting documentation regarding Excavation Completion in Cells 129 to 133 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, June 08, 2014 5:57 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 129 through 133

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 129 to 133.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 05/20/14 to 05/27/14.

As previously indicated cells are being spilt into subparts A and B at the discretion of the Engineer. The split is based on either the geometry of the excavation and cell overlay or due to constructability considerations related to the need to backfill adjacent to the Barrier wall prior to completion and approval of the full cell. The A designation will be applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell.

During daily excavation and survey confirmation Cells 129 through 133 were divided into A and B sections as reflected in the Maser Tables. There is no clean unexcavated dividing line in the middle of site as there was in Cells 137 through 146. For this submittal the full north south area of each cell was completed as indicated in the Excavation Bottom Elevation figure.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits
- Sheet pile on the excavation face has been cleaned of visible soil materials.
- The bottom and lateral limits of each cell were visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells except for those areas noted for deferral.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 129 to 133, the excavation is terminated at the respective Area 21, 23, 30, 31, 32, 34, and 35 excavation elevations.
- Excavation will proceed from Cell 128 to the east into Cell 125.
- The bottom of cells 129 through 133 were terminated in Stratum O.

- Confirmatory Bottom Points located within Cells 129 through 133 are shown on the Excavation Bottom Elevation figure.
- The northern excavation limit was the Barrier Wall. The southern limit as the Temporary Sheetpile wall.
- There were no Confirmatory Sidewall Samples in Cells 129-133. The remedial design calls for an area south of the temporary sheetpile support and bulkhead to be remediated by a combination of shallow excavation and insitu treatment. This work will be tracked separately to the main excavation currently being conducted.

Per the SOP, we are showing the corner elevations as discussed at our last all parties meeting.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

Please note: This e-mail documented excavation completion in cells 137B through 146B. The cells identified in the subject line were mislabeled. EGC 2/27/17

**Christodoulatos, Eric G**

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:36 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 134 to 136 and 138B to 145B

**Importance:** High

1st of many emails you requested

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Sunday, June 08, 2014 7:17 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 134 to 136 and 138B to 145B
**Importance:** High

Bill,

The Special Master is in receipt of your May 27, 2014 email and the supporting documentation regarding Excavation Completion in Cells 134 to 136 and 138B to 145B and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Tuesday, May 27, 2014 7:58 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 134 to 136 and 138B to 145B

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 134 to 136 and 138B to 145B.

As discussed in our weekly meetings, we have separated the western cells into A and B designations with A being the portion of cells closest to the barrier wall and B being the portion closest to Kellogg St. We provided in a previous email on May 18, 2014 the figure.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 05/01/14 to 05/19/14.

- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% design limits*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided.*
- *All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells except for those areas noted for deferral.*
- *Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 134 to 136 and 138B to 146B, the excavation is terminated at the respective Area 31, 32, 33, 36 and 39 excavation elevations.*
- *Excavation will proceed from Cell 134 to the east.*

*EXCAVATION CELLS 137B THROUGH 146B*

- *The bottom of Cells 137B through 146B were terminated in Stratum O.*
- *Confirmatory Bottom Points located within Cells 137B through 146B are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples are shown in Cells 138B, 141B, 142B 143B and 146B.*
- *Sample 073-SB-051 is interior to the excavation approximately on the dividing line of Cells 138B and 139B. This is an area where the excavation limits shown on the 100% design for Cells 139B and 140B was adjusted to the north to simplify the excavation geometry.*
- *The northern limits of Cells 137 B THROUGH 146 B terminates at the 20 PPM line that is interior to the site. The profile of the excavation face is composed of very loose Stratum O sands overlain by several feet of historic fill. The slope had to be laid back much more than at the east end of the site to provide a stable slope. This results in the top of slope being significantly further beyond the <20 PPM line than the eastern portion of the site.*
- *The Southern limits of Cells 137 B to 146 B were terminated at the temporary sheet pile that forms the southern limit of excavation in these cells.*

*EXCAVATION CELLS 134 to 136*

- *These cells were not split.*
- *For Cells 134 through 136, the bottom of the excavation was terminated in Stratum O.*
- *The Southern limits of Cells 134 through 136 were terminated at the temporary sheet pile that forms the southern limit of excavation in these cells which is coincident with the <20 PPM line..*
- *Confirmatory Bottom Points located within Cells 134 to 136 are shown on the Excavation Bottom Elevation figure.*

- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal.*
- *The northern limits of Cells 134 to 136 consist of sheet pile Barrier Wall.*

Per the SOP, we are showing the corner elevations as discussed at our last all parties meeting.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Wednesday, July 16, 2014 9:36 AM
**To:** Christodoulatos, Eric G
**Subject:** FW: SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Tuesday, May 27, 2014 3:43 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

Bill,

The Special Master is in receipt of your May 18, 2014 email and the supporting documentation regarding Excavation Completion in Cells 137A to 146A and 147 to 152 and the notification that the contractor is ready to backfill these Cells.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Sunday, May 18, 2014 8:31 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; Daneker, Michael; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; Clifford, Joseph T; 'Joseph.Clifford@amec.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

Steve,

We are providing this email notification that our contractor is ready to backfill Cells 137A to 146A and 147 to 152 .

As discussed in our weekly meetings, we have separated the western cells into A and B designations with A being the portion of cells closest to the barrier wall and B being the portion closest to Kellogg St. We are providing herein a new figure (see SA-6 South Split Cells 4.pdf which provides the graphical delineation for purposes of better understanding our statements below.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 04/25/14 to 04/29/14.

*EXCAVATION CELLS 149 THROUGH 152*

- *Excavation commenced on 4/14 in the western portion of the site. This portion of the site had a surface primarily composed of a series of foundations and slabs at variable elevations.*
- *Due to the presence of several feet of concrete, Cell 153 is only partially excavated at this time and as a result is not being included in the email indicating that excavation is complete at this time.*
- *The approved 100% Design in this area (Area 40) indicated deferral of excavation below elevation 5.7.*
- *Visual inspection of the bottom and sidewalls of Cells 149 through 152 indicated the presence of chromium impacted concrete. Removal of these materials vertically resulted in excavation below elevation 5.7. Visually impacted concrete was removed laterally along the south easterly edge of the Cell 150 into Cell 149 as evidenced by the limit of excavation shown on the Bottom Excavation Elevation figure.*
- *Cells 149 through 152 were terminated in historic fill.*
- *Confirmatory Bottom Points located within Cells 148-152 are shown on the Excavation Bottom Elevation figure.*
- *Confirmatory Sidewall Samples are shown in Cells 149, 150 and 152.*
- *The northern limits of Cells 149-152 consist of sheet pile Barrier Wall.*
- *The Southern limit of cells 149-152 were terminated in 0 <20 PPM historic fill soils.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% Design limits. In several areas of Cell 149-152 the excavation depth was increased (we were able to get additional materials and minimize future deferral volumes remaining) and these locations are shown with a green shading. These areas are also outlined in Excavation Bottom Elevation figure.*

*EXCAVATION CELLS 147 to 148 and 137A to 146A*

- *The cell excavation designations in this area have been split into subparts A and B. The A designation is applied to the portion of the cell adjacent to the hydraulic barrier and the B designation includes the southern part of the cell. This designation clarification was made for two reasons:*
    - *For Cells 137 through 146, the excavation area is not continuous north to south, meaning there is an area of <20 PPM soils not requiring excavation In the middle of the cells (see Figure 2 Color Coded Excavation Bottom).*
    - *For Cells 136 to the east this approach was used to facilitate surveying of the subarea A (including corners and center points). This reduces the time cycle between excavation and backfill adjacent to the hydraulic barrier which helps to minimize sheet deflection.*
- *Cells 137A through 146A, 147 and 148 excavation was terminated in either historic fill or Stratum O.*
- *The Southern limit of Cells 137A to 146A, 145 and 148 was terminated in either historic fill or Stratum O <20 PPM soils.*
- *Lines have been added to the Excavation Bottom Map to delineate the limits of the Excavation Bottom Areas. In the Cells 137A-146A and 147 to 148, the excavation is terminated at the respective Area 32, 33, 36, 37, 38 and 40 excavation elevations.*
- *Confirmatory Bottom Points located within Cells 137A-146A, 147 and 148 are shown on the Excavation Bottom Elevation figure.*

- *Confirmatory Sidewall Samples are shown in Cells 137A, 139A, 142A, 143A and 148.*
- *Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal.*
- *The northern limits of Cells 137 to 146 consist of sheet pile Barrier Wall.*
- *The Southern Limit of excavation of Cells 137A to 146A, 147 and 148 terminate at the <20 PPM line at the bottom of excavation and are cut back at a stable slope beyond the 20 PPM line.*
- *Sheet pile on the excavation face has been cleaned of visible soil materials.*
- *The bottom and lateral limits of each cell were visually inspected by Amec personnel.*
- *Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met.*
- *An Excavation Progress Map is provided.*
- *Excavation will proceed from Cell 136A to the east and from Cell 146B to the east.*
- *All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells except for those areas noted for deferral.*

Per the SOP, we are showing the corner elevations as discussed at our last all parties meeting.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, (LB) the information and statements herein do not constitute a binding commitment or warranty by LB. LB assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, January 30, 2017 3:10 PM
**To:** Christodoulatos, Eric G
**Cc:** Nagg, Dennis E
**Subject:** FW: Amendment to SA-6S : Excavation Completion in Cells 149 to 152

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, October 29, 2014 4:15 PM
**To:** Clifford, Joseph T <Joseph.Clifford@amec.com>; Hague, William <william.hague@honeywell.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'cpravlik@tpmlaw.com' <cpravlik@tpmlaw.com>; 'Daneker, Michael' <Michael_Daneker@aporter.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; 'David Isabel' <dlisabel@golub-isabel.com>; 'Eric Tomaszewski' <eric@golub-isabel.com>; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org
**Subject:** RE: Amendment to SA-6S : Excavation Completion in Cells 149 to 152

Bill/Joe,

The Special Master is in receipt of your October 23, 2014 email providing supplementation information for the Amended Certification for Excavation Completion in Cells 149 to 152 emailed on October 1, 2014 and that the requirements to allow backfilling have been met.

Regards, Steve

---

**From:** Clifford, Joseph T [mailto:Joseph.Clifford@amec.com]
**Sent:** Thursday, October 23, 2014 8:32 AM
**To:** Egnaczyk, Steve; Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: Amendment to SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

**SUPPLEMENTAL INFORMATION FOR AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 149 TO 152 EMAILED ON OCTOBER 1, 2014.**

Steve,

I am sending this email on behalf of Honeywell.

In response to your email dated October 10 to Bill Hague, Honeywell and Amec are providing the following supplemental information:

- The top portion of the design excavation in Cells 149 through 152 consisted of a combination of reinforced and unreinforced concrete. As indicated in the May 27th submittal the concrete at the design limits was observed to be chromium impacted: "Visual inspection of the bottom of excavation and sidewalls of Cells 149 through 152 indicated the presence of chromium impacted concrete in the concrete sidewall". The excavation was therefore expanded to remove the visibly impacted concrete.

- The expansion of the design excavation necessitated obtaining additional sidewall samples. Two new Confirmatory Sidewall Soil Samples (designated 073-SB-079 and 073-SB-082) were collected and documented in the Maser table attached to the October 1, 2014 email from Honeywell (see page 14 of 15).

- The Final Limits of excavation (highlighted in green) and location of the Confirmatory Sidewall Soil Samples are shown on the Bottom Excavation Map (Amended) attached to the October 1, 2014 email from Honeywell.

- The bottom of excavation elevation matched the adjacent excavation in Cell 149 and Cell 150. As indicated in the Bottom Excavation Map (Amended), the southern portion of the additional excavation was excavated to elevation 2 and the northern portion to approximately elevation 4.

- The vertical and horizontal limits of excavation were surveyed by Maser, including supplemental survey points for use in preparation of the as-built excavation topographic map that will accompany the Declaration which will be submitted following completion of the SA-6S excavation.

- The additional excavation area depicted on the Bottom Excavation Map (Amended and highlighted in green) represents the boundaries of the area resurveyed on July 31, 2014.

- The bottom and lateral limits of the additional excavation area were visually inspected by Amec personnel prior to the July 31, 2014 Maser Survey. Amec personnel did not observe any additionally impacted soils.

- Amec inspectors certify to the best of our technical ability that impacted soils as defined in the 100% Design have been removed from the additional excavation area and that the requirements to allow backfilling have been met.

We are re-submitting the two attachments from our October 1, 2014 transmittal.

Please let us know if you have any more questions regarding this Amended Submittal for Cells 149 to 152.

Regards.

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Friday, October 10, 2014 3:24 PM
**To:** Hague, William
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** RE: Amendment to SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152
**Importance:** High

Bill,

The Special Master is in receipt of your October 1, 2014 email below regarding the Amended Certification for Excavation Complete in Cells 149 to 152 and provides the following comments:

1. Because Honeywell needed to perform additional excavation to address this area of contamination that extended beyond the defined excavation boundaries presented in the color-coded excavation map (i.e., Figure 4 that depicts the 41 areas of the SA6 South excavation and the pre-determined depths of excavation) to fully comply with the SA6 South 100% Design, consistent with the initial May 27, 2014 submittal, please provide a re-certification from Honeywell/AMEC/Maser that:
    a. The bottom and lateral limits of the expanded excavation area were visually inspected by Honeywell/Amec personnel and no additional visually impacted area was observed.
    b. Impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling [of this additional excavation area ]have been met.
    c. The additional excavation area depicted on the attached figure (and highlighted in green) represents the boundaries of area resurveyed on July 31, 2014.
2. Please confirm whether any additional survey points were collected in the expanded excavation area from the bottom of the completed excavation area.

Regards, Steve

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Wednesday, October 01, 2014 10:40 AM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; Clifford, Joseph T; Clifford, Joseph T; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** Amendment to SA-6S : Excavation Completion in Cells 137A to 146A and 147 to 152

**AMENDED CERTIFICATION FOR EXCAVATION COMPLETE IN CELLS 149 TO 152.**

Steve,

We are providing an amended certification regarding completion of excavation in Cells 149 to 152 which was originally submitted by Honeywell to the parties by email on May 27, 2014.

As noted in the original May 27, 2014 email for these cells, the following observation was noted by the Amec engineer:

- *Visual inspection of the bottom and sidewalls of Cells 149 through 152 indicated the presence of chromium impacted concrete. Removal of these materials vertically resulted in excavation below elevation 5.7. Visually impacted concrete was removed laterally along the south easterly edge of the Cell 150 into Cell 149 as evidenced by the limit of excavation shown on the Bottom Excavation Elevation figure.*

Once the visually-impacted concrete was removed, Honeywell made the original email certification to the parties.

Subsequent to the submittal, Honeywell also directed Amec to collect two additional sidewall soil samples on the eastern excavation edge 073-SB-079 and 073-SB-080. While hexavalent chromium in soil sample 073-SB-079 was < 20 ppm, the second sample 073-SB-080 was > 20 ppm, which necessitated a step out soil sample approximately five feet to the east. This last soil sample designated as 073-SB-082 was confirmed to be < 20 ppm and the contractor returned to this area to remove the small area of residual soil > 20 ppm. The area was excavated in July and resurveyed on July 31, 2014.

An Amended Excavation Bottom Elevation Map showing the additional area of excavation of visually-impacted concrete and subsequent soil > 20 ppm is attached and highlighted in green. As shown in this figure, the area slightly enlarges the limits of Cells 148, 149 and 150.

The added < 20 ppm soil sample confirmatory locations are also shown on the map. Analytical data for the three soil samples collected in this excavation area was provided in the SA-6 Monthly Progress Report No. 2014-07 submitted to the parties on August 14, 2014.

Lastly, the Maser Survey Table showing the confirmatory points has been updated to reflect the two recent soil sample locations with hexavalent chromium < 20 ppm (highlighted in green on page 14 of 15) which are additional sidewall confirmatory samples for SA-6 South.

Regards,
Bill

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the

attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

The information contained in this e-mail is intended only for the individual or entity to whom it is addressed.
Its contents (including any attachments) may contain confidential and/or privileged information.
If you are not an intended recipient you must not use, disclose, disseminate, copy or print its contents.
If you receive this e-mail in error, please notify the sender by reply e-mail and delete and destroy the message.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Tuesday, January 31, 2017 10:45 AM
**To:** Christodoulatos, Eric G
**Cc:** Shallard, Samuel G.
**Subject:** FW: SA-6 South Site 163 Post-Remediation Sampling

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

Found it!

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, May 13, 2015 7:55 PM
**To:** Kathleen L. Millian <kmillian@tpmlaw.com>; Michael.Daneker@aporter.com
**Cc:** RGT Special Master <RGTSpecialMaster@aol.com>; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO) <tom.byrne@honeywell.com>; Kaouris, Maria <Maria.Kaouris@Honeywell.com>; Alicia Clark Alcorn <aalcorn@tpmlaw.com>; Carolyn Smith Pravlik <cpravlik@tpmlaw.com>; Lewis, Thomas <tlewis@louisberger.com>; McWatters, Michael <mmcwatters@louisberger.com>; Ben Davis <bdavis@tpmlaw.com>; Toskos, Theodoros <Theodoros.Toskos@amec.com>; Morris, John (MTO) [John.Morris@honeywell.com] <John.Morris@honeywell.com>; Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>; Clifford, Joseph T <Joseph.Clifford@amec.com>
**Subject:** RE: SA-6 South Site 163 Post-Remediation Sampling

All,

As Honeywell has provided the information requested by Plaintiffs' in their April 30, email, the Special Master requests the parties be prepared to address the issue of "rebound" at next week's Special Master All Parties Meeting. The Special Master refers to the discussion in Honeywell's April 3, 2015 correspondence regarding post-treatment "rebound" of residual soil concentrations of hexavalent chromium, and specifically, to define "rebound" should there be detections of hexavalent chromium above 20 ppm during post-remediation sampling at Site 163, as well as Treatment Areas 7, 8, and 10 on SA6 North.

Regards, Steve

---

**From:** Clifford, Joseph T [mailto:joseph.clifford@amecfw.com]
**Sent:** Wednesday, May 13, 2015 9:03 AM
**To:** Kathleen L. Millian; Egnaczyk, Steve
**Cc:** RGT Special Master; Michael.Daneker@aporter.com; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO); Kaouris, Maria; Alicia Clark Alcorn; Carolyn Smith Pravlik; Lewis, Thomas; McWatters, Michael; Ben Davis; Toskos, Theodoros; Morris, John (MTO) [John.Morris@honeywell.com]; Hague, William [william.hague@honeywell.com]
**Subject:** RE: SA-6 South Site 163 Post-Remediation Sampling

Kathy/Steve,

I am sending this email on behalf of Honeywell.

Please find attached the figure you requested showing the location of the Soil Boring 140-SB-P05 which was the location used for the cores sent to Battelle. The figure also shows the proximate PDI soil delineation used in the 100% Design. The area around this boring was excavated to Stratum D.

Let us know if you have any other questions on this item.

Thank you. -Joe

---

**From:** Kathleen L. Millian [mailto:kmillian@tpmlaw.com]
**Sent:** Thursday, April 30, 2015 3:13 PM
**To:** Morris, John (MTO); Hague, William
**Cc:** RGT Special Master; Clifford, Joseph T; Michael.Daneker@aporter.com; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO); Kaouris, Maria; Alicia Clark Alcorn; Carolyn Smith Pravlik; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mmcwatters@louisberger.com; Ben Davis; Toskos, Theodoros
**Subject:** RE: SA-6 South Site 163 Post-Remediation Sampling

Plaintiffs write concerning the issue of potential rebound at Site 163. On April 3, 2015, Honeywell submitted to the Special Master a memorandum prepared by Amec Foster Wheeler, entitled "Analysis of Chromium 'Rebound,' with Application to Site 163." Some of Amec's positions on rebound are based on a draft report that was prepared by Battelle in September 2008, entitled "Investigation of Chromium in SA-6S Core Segments."

Plaintiffs' experts, Benjamin Ross, Ph.D. and George Flowers, Ph.D., request certain additional information to enable a full understanding of the September 2008 draft report. In particular, we request to know the location from which the core segments were taken. Plaintiffs request that Honeywell provide a figure of the relevant portion of Study Area 6 South showing both: (1) the location from which the core was taken; and (2) the locations of and contaminant levels at the borings which were used to delineate the hexavalent chromium in the vicinity of the core.

Thank your for your attention to this matter.

Sincerely,

Kathleen L. Millian
TERRIS, PRAVLIK & MILLIAN, LLP
1121 12th Street, N.W.
Washington, D.C. 20005
Main Telephone: 202-682-2100
Direct Dial: 202-204-8478
Facsimile: 202-289-6795
email: kmillian@tpmlaw.com

The information in this e-mail is intended only for the use of the designated recipient(s) and may contain confidential and privileged information.
If the reader of this message is not the intended recipient(s), you are hereby notified that you have received this email in error and that any review, dissemination, distribution, or copying of this message is strictly prohibited. If you have received this communication in error, please notify the sender by reply e-mail and destroy all copies of the original message.

**From:** Graham, Stephanie [mailto:Stephanie.Graham@honeywell.com]
**Sent:** Friday, April 03, 2015 4:17 PM
**To:** RGT Special Master
**Cc:** Joseph.Clifford@amecfw.com; Michael.Daneker@aporter.com; Jeremy.Karpatkin@aporter.com; B.Bell@cea-enviro.com; K.Hosea@cea-enviro.com; JFarrell@jcnj.org; jwatson@jcnj.org; AAntonian@connellfoley.com; KCoakley@connellfoley.com; LWalsh@connellfoley.com; FBORIN@decotiislaw.com; KKINSELLA@decotiislaw.com; BRoss@disposalsafety.com; disabel@golub-isabel.com; Byrne, Tom (MTO); Hague, William; Kaouris, Maria; Morris, John (MTO); Alicia Clark Alcorn; Kathleen L. Millian; Carolyn Smith Pravlik; SEgnaczyk@louisberger.com; TLewis@louisberger.com; mmcwatters@louisberger.com; Ben Davis; Toskos, Theodoros
**Subject:** SA-6 South Site 163 Post-Remediation Sampling

Attached please find Honeywell correspondence re:

**Site 163 Post-Remediation Sampling**
**Study Area 6 (SA-6) South**
**Jersey City, New Jersey**

Please note that this information has also been made available on the Louis Berger SharePoint Site.

Thank you,

Stephanie Graham

**Amec Foster Wheeler**
c/o Honeywell
101 Columbia Tpke
Morristown, NJ 07962
Phone: 973-455-4209

This message is the property of Amec Foster Wheeler plc and/or its subsidiaries and/or affiliates and is intended only for the named recipient(s). Its contents (including any attachments) may be confidential, legally privileged or otherwise protected from disclosure by law. Unauthorised use, copying, distribution or disclosure of any of it may be unlawful and is strictly prohibited. We assume no responsibility to persons other than the intended named recipient(s) and do not accept liability for any errors or omissions which are a result of email transmission. If you have received this message in error, please notify us immediately by reply email to the sender and confirm that the original message and any attachments and copies have been destroyed and deleted from your system. This disclaimer applies to any and all messages originating from us and set out above. For Canada and the United States: If you believe this is an unsolicited email and do not wish to receive future commercial electronic messages from us, please click unsubscribe@amecfw.com and include "Unsubscribe" in the subject line.

Please click http://amecfw.com/email-disclaimer for notices and company information in relation to emails originating in the UK, Italy or France.

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Tuesday, January 03, 2017 10:47 AM
**To:** Christodoulatos, Eric G; Shallard, Samuel G.
**Subject:** FW: SA-6 South Excavation Complete Submittal - Site 163

**Follow Up Flag:** Follow up
**Flag Status:** Flagged

Here is the first part. I will search for the follow up email.

---

**From:** Egnaczyk, Steve [mailto:segnaczyk@louisberger.com]
**Sent:** Wednesday, December 31, 2014 10:57 AM
**To:** Hague, William
**Cc:** RGT Special Master ; Kevin J. Coakley (KCoakley@connellfoley.com) ; 'Liza M. Walsh' (LWalsh@connellfoley.com) ; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) ; Lewis, Thomas ; ' (kmillian@tpmlaw.com)' ; 'Aalcorn@tpmlaw.com' ; 'cpravlik@tpmlaw.com' ; Ben Davis ; 'Daneker, Michael' ; 'Jeremy.Karpatkin@aporter.com' ; Morris, John (MTO) ; 'DelisleB@jcnj.org' ; JFarrell@jcnj.org; JWatson@jcnj.org; 'David Isabel' ; 'Eric Tomaszewski' ; Francis J. Borin ; KKINSELLA@decotiislaw.com; Clifford, Joseph T ; 'Ben Ross (bross@disposalsafety.com)' ; 'Bruce A. Bell' ; 'Kim Bell Hosea (k.bell@cea-enviro.com)' ; McWatters, Michael
**Subject:** RE: SA-6 South Excavation Complete Submittal - Site 163

Bill,

The Special Master is in receipt of your December 11, 2014 email and the supporting documentation regarding Excavation Completion of Site 163 and the small (undesignated) diamond shaped area west of the "main" Site 163 excavation area and your notification that the requirements to allow backfilling have been met. Honeywell also reports that as a result of an inspection and evaluation of the Droyer's Cove bulkhead and associated mass concrete located along the shoreline of Droyer's Cove that borders the southern limit of the excavation, a decision was reached by Honeywell as to the safe limits of excavation and several areas were deferred from excavation. The Special Master concurs with Plaintiffs' request contained in their December 19 email that Honeywell provide information regarding the three (3) areas shown in the figure attached to your email (Excavation Bottom Elevations, Site 163, Period 10-30-4 to 11-13-14) that have been deferred from excavation.

Regards, Steve

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Thursday, December 11, 2014 4:34 PM
**To:** Egnaczyk, Steve
**Cc:** RGT Special Master; Kevin J. Coakley (KCoakley@connellfoley.com); 'Liza M. Walsh' (LWalsh@connellfoley.com); 'AGNES ANTONIAN' (AAntonian@connellfoley.com); Lewis, Thomas; ' (kmillian@tpmlaw.com)'; Morris, John (MTO); 'cpravlik@tpmlaw.com'; 'Daneker, Michael'; 'DelisleB@jcnj.org'; 'Aalcorn@tpmlaw.com'; 'MWeaver@tpmlaw.com'; 'Jeremy.Karpatkin@aporter.com'; JFarrell@jcnj.org; 'David Isabel'; 'Eric Tomaszewski'; Francis J. Borin; Clifford, Joseph T; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)'; 'Bruce A. Bell'; 'Kim Bell Hosea (k.bell@cea-enviro.com)'; McWatters, Michael; JWatson@jcnj.org
**Subject:** SA-6 South Excavation Complete Submittal - Site 163

Steve,

We are providing this email notification that our contractor is ready to backfill the shallow (0-4 feet below grade) soil excavation in Site 163.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of SA-6 South excavation completion covers the individual period from 10/30/14 to 11/13/14.

This submittal covers the main Chromium portion of the Site 163 excavation and the diamond shaped area west of the "main excavation". Additional shallow excavation will be conducted to remove non-chromium impacted soils west of the "main excavation" limits shown. The Issued for Construction design indicated Excavation for site 163 using below ground surface depths. These depths were converted to elevation (NGVD 29 datum) prior to implementation of the excavation. All excavation depths and the Maser table reports based on elevations.

Due to the shallow depth and geometry of the excavation "cell numbering" was not used.

- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables. A yellow background shading has been applied to sample locations which are the subject of this submittal that were terminated at the 100% Design limits.
- Temporary sheetpile which was driven at the southern limit for the excavation of Cells 106 through 129 was still in place and served as the northern limit of the Site 163 excavation. The face of the temporary sheet was cleaned of visible soil materials.
- The southern excavation limit was designed with variable offsets from the Droyer's Cove bulkhead based on the PDI samples. The bulkhead and associated mass concrete was inspected as excavation progressed and decisions reached as to the safe limits of removal. As a result of this inspection and evaluation process one concrete structure was left in place at the southwest corner of the excavation and a sliver of material was left in place at the south east corner as shown on the Excavation Bottom Elevation plan. There was no visual indication of chromium impact in the concrete left in place.
- The top 6 inches of the "deadmen" for the bulkhead were exposed in the bottom of the excavation.
- The bottom and lateral limits of the excavation was visually inspected by Amec personnel.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design have been removed and that the requirements to allow backfilling have been met subject to the isolated areas noted above.
- An Excavation Progress Map is provided.
- All survey points in the excavation cells were at or below the design excavation elevations and are representative of the final excavation grade(s) throughout the excavation cells.
- Lines have been added to the Excavation Bottom Map to delineate the limits of the steps in bottom elevations in the Excavation Area.
- The bottom of excavation was terminated in Stratum O or fill at or below the respective Excavation Bottom Elevations.
- Excavation will proceed to remove the Lens of Anomalous material that extended beyond the design limit by Cell 104.
- There were 11 Confirmatory Sidewall Samples taken in the main area and 4 Confirmatory sidewall samples in the Diamond shaped area.

We note that a field decision was made to add an additional protective measure to protect the clean backfill. This measure included use of a geotextile and riprap/crushed concrete with the objective of increasing erosion protection

until the new bulkhead is installed by Bayfront. The Design Change Bulletin showing this enhancement of the 100% Design is being prepared for distribution to the parties.

Regards
Bill Hague

**Honeywell**
**William J. Hague P.E.**
Director - Remediation Design & Construction
Corporate HSE&R
101 Columbia Road
Morristown, NJ 07962
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

This message, including any attachments hereto, may contain privileged and/or confidential information and is intended solely for the attention and use of the intended addressee(s). If you are not the intended addressee, you may neither use, copy, nor deliver to anyone this message or any of its attachments. In such case, you should immediately destroy this message and its attachments and kindly notify the sender by reply mail. Unless made by a person with actual authority conferred by Louis Berger, the information and statements herein do not constitute a binding commitment or warranty by Louis Berger. Louis Berger assumes no responsibility for any misperceptions, errors or misunderstandings. You are urged to verify any information that is confusing and report any errors/concerns to us in writing.

**ATTACHMENT C-1**
**SITE 163 EXCAVATION CERTIFICATION E-MAIL**

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:18 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: SA-6 South Excavation Submittal - Site 163 Residential Area
**Attachments:** Final AB PDI Locations Site 163_ Feb 2016_1.pdf; Figure 1 - Site 163 Addtional Excavation Areas.pdf; Confirmation Points Cert site163 2016 Chrome area_041316-signed.pdf

---

**From:** Hague, William [mailto:william.hague@honeywell.com]
**Sent:** Monday, April 25, 2016 10:53 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** RGT Special Master <rgtspecialmaster@aol.com>; Kevin J. Coakley (KCoakley@connellfoley.com) <KCoakley@connellfoley.com>; 'Liza M. Walsh' (LWalsh@connellfoley.com) <LWalsh@connellfoley.com>; 'AGNES ANTONIAN' (AAntonian@connellfoley.com) <AAntonian@connellfoley.com>; Lewis, Thomas <tlewis@louisberger.com>; ' (kmillian@tpmlaw.com)' <kmillian@tpmlaw.com>; Morris, John (MTO) <John.Morris@honeywell.com>; 'DelisleB@jcnj.org' <DelisleB@jcnj.org>; 'Aalcorn@tpmlaw.com' <Aalcorn@tpmlaw.com>; 'MWeaver@tpmlaw.com' <MWeaver@tpmlaw.com>; 'Jeremy.Karpatkin@aporter.com' <Jeremy.Karpatkin@aporter.com>; JFarrell@jcnj.org; Francis J. Borin <FBORIN@decotiislaw.com>; KKINSELLA@decotiislaw.com; 'Ben Ross (bross@disposalsafety.com)' <bross@disposalsafety.com>; 'Bruce A. Bell' <b.bell@cea-enviro.com>; 'Kim Bell Hosea (k.bell@cea-enviro.com)' <k.bell@cea-enviro.com>; McWatters, Michael <mmcwatters@louisberger.com>; JWatson@jcnj.org; Clifford, Joseph T <Joseph.Clifford@amec.com>; Daneker, Michael D. <Michael.Daneker@APORTER.COM>
**Subject:** SA-6 South Excavation Submittal - Site 163 Residential Area

Steve,

We are providing this email notification that our contractor is complete in Excavation Area at Site 163 Residential Footprint which is part of the SA-6 South Chromium Remedy. The excavation of this specific area within Site 163 was developed subsequent to the 100% Design (which originally identified this area as an in-situ treatment area) and as a result is documented by the figures included in the approved Design Change Bulletin - DCB 2015-0928.

We are requesting an email acknowledgement that the Special Master is in receipt of this email and the supporting documentation accompanying this notification.

This submittal notification of Site 163 excavation completion covers the individual period of 12/28/15 to 02/19/16. This submittal includes the full extent of Site 163 as shown on the approved DCB 2015-0928 drawings.

- The submittal include a “Maser” signed table of the Confirmation Points and the Entact “As Built” Excavation Figure.
- The excavation was conducted using temporary sheetpile on all sides. The sheetpile was driven so that the inside face of the sheetpile was at or slightly beyond the excavation limits shown on Figure 1 of DCB 2015-0928. (copy attached).
- Coordinates for Survey and Confirmatory Points are tabulated in the Maser Tables.

- The bottom excavation elevations were measured using the Machine Control GPS.
- The bottom of excavation elevations were at or below the design Bottom of Excavation Elevations.
- For safety reasons no entry was permitted to inspect the bottom of the excavation. The bottom of the excavation was visually inspected by Amec personnel from outside the sheetpile.
- The Bottom of Excavation was observed to be of a consistent elevation and at or below the elevation at the survey confirmation locations.
- As shown on the As Built excavation bottom figure only one area was noted to be at being Stratum D. Stratum D fragments were detected at in other isolated locations within the deepest excavation. The majority of the excavation was terminated in a silty sand, Stratum O type soil.
- The web of the sheetpile was outside of the designated excavation limit.
- Amec inspectors certify to the best our technical ability that impacted soils as defined in the 100% Design and subsequent DCB 2015-0928 have been removed and that the requirements to allow backfilling were met.
- Lines have been added to the As Built Excavation Map to delineate the limits of the steps in bottom elevations in the Excavation Area.
- Changes in elevation between areas was small and therefore near vertical faces were excavated at locations where the design bottom elevations changed.
- There were 5 Confirmatory Sidewall, and 5 Confirmatory Bottom locations exposed during the excavation and these are depicted on the Maser Survey Tables and Entact Bottom of Excavation Figure.

Please call or email me with any questions.
Regards,
Bill Hague

**William J. Hague P.E.**

Honeywell
Director - Remediation Design & Construction
Corporate HSE&R
115 Tabor Road
Morris Plains, NJ 07950
973-455-2175
973-455-3802 Fax
973-896-9366 Cell
william.hague@honeywell.com

## Christodoulatos, Eric G

**From:** Clifford, Joseph T
**Sent:** Monday, February 27, 2017 8:22 AM
**To:** Christodoulatos, Eric G; Nagg, Dennis E
**Subject:** FW: Response to Verbal Questions on Site 163 Excavation

---

**From:** Clifford, Joseph T
**Sent:** Thursday, May 05, 2016 7:40 AM
**To:** Egnaczyk, Steve <segnaczyk@louisberger.com>
**Cc:** Hague, William [william.hague@honeywell.com] <william.hague@honeywell.com>
**Subject:** Response to Verbal Questions on Site 163 Excavation

Steve,

I am sending this email on behalf of Honeywell, and in response to your call on April 27, 2016, when you asked two questions regarding our April 25, 2016 - Site 163 Excavation Completion Email Notification to the parties.

Below are the questions and our responses.

1. **What is our rationale for the BOE design for Area B, which does not have a bottom PDI sample?**

   - *"PDI samples from across the localized area were used and interpolated consistent with the 100% Design approach. The approved DCB 2015-0928 explicitly stated that Honeywell would implement this excavation without any additional sampling required."*

2. **We mention that no Amec inspections were performed in the bottom of the excavation, yet at some point we did have Entact laborers in the backfill placing geotextile**.

   - *"At the time of excavation completion, the bottom soils were deemed too soft to safely enter the excavation. The excavation was sufficiently dewatered to allow our inspections from the existing grade as necessary to attest to our inspection protocols. Once the initial bridge lift was placed and the bottom stabilized, Entact crew was able to enter the excavation to place the geotextile in accordance with the 100% Design specifications."*

If these responses adequately address your inquiry, Honeywell would be pleased to provide an Amended Certification of Excavation Complete Email adding these clarifications upon your request.

Please contact me on my cell at 610-505-9315 or Bill Hague at 973-455-2175 with any further questions on this item.

Thank you. -Joe

**Joseph T. Clifford, P.E.**
Sr. Principal Engineer

Cell Phone (610) 505- 9315
Email joseph.clifford@amecfw.com